Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
1A	Contaminated Sub-Slab Vapors	-	-	EHS Building	AOCs that encompass the EHS building (AOC-1) include indoor air (AOC-1A) and sub-slab vapor (AOC-1B). The source of COPCs is related to historical industrial operations (former building locations shown on Figure 1-3), specifically a TCE-impacted soil area identified to the north of Room 127 (Figure 2-1). While the presence of the EHS building slab reduces the potential for stormwater infiltration, the COPCs reported present a potential source area for vertical migration through the soil column to the water table. Historical geotechnical borings beneath the EHS showed the underlying silty clay aquitard sloping toward the west/southwest (Figure 4-3 and 4-4). Therefore, historical releases may have migrated along the top of the aquitard toward AOC-18.	Remnant VOCs in subsurface soil can volatilize and migrate vertically through vadose zone soil toward the EHS building slab, or dissolved and migrate toward and then downgradient in groundwater.	1. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants. 2. Off-site surface water users/ecological communities: VOC-impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors.	Soil Vapor	V, P	1952 DOH Sampling Report 1967 Lancy Report and Figures 1977-79 SHS Construction and Demolition Plans 1977 Empire Soils Report 2003 DOH Health Consultation 2009 EMP 2010 DOH Health Consultation 2011 2013 EMP Annual Reports 2013 IA Sampling 2014 VI Assessment 2018 Supplemental VI Assessment 2019 ISMP 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 2. Extent of TCE source in soil has been further investigated outside of the EHS building footprint as described for AOC-13 / AOC-16 and AOC-18. 3. Potential pathway for VOC migration along stormwater drain backfill north of Room 127 investigated by soil and groundwater sampling and groundwater investigation for VOCs downgradient of the EHS building (Figure 6-1D and 6-2D). 4. TCE soil vapor impacts in areas outside of mitigated SSDS installation areas are limited to the Pool Filter Room and Sub-Slab Boiler Room (Figure 5V-2A-F). These rooms are used for chemical storage and are not occupied regularly. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Sampling of indoor air for PCBs was conducted in 2021. Results have been reported in ISMP PRRs for 2019–2025 and 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Indoor air PCB analytical results are compared to the USEPA PCB Exposure Levels in Table 6-1E. PCBs in indoor air were all at least two orders of magnitude below the USEPA PCB Exposure Level of 0.1 µg/m3. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Sub-Slab Soil Vapors - Yes	NA	-	-	See Table 5-2 for Sub-Slab Soil Vapor Sampling locations and results.	-	-	-	-	-
1B	Indoor Air Quality	-	-	EHS Building				Indoor Air	V, P			Indoor Air - Yes	NA	-	-	See Table 5-1A for Indoor Air Sampling Results	-	-	-	-	-
2	Pre-1979 Combined Industrial/ Storm Sewer	-	-	Site-Wide	AOC-2 (Pre-1979 Combined Industrial/Storm Sewer, or "former industrial sewer") remains in place at the Site. The orientation, construction and depth of the sewer is known based on depictions of industrial waste facilities and operations (Lancy, 1967) and numerous rounds of site investigation using geophysical methods, test pit excavations and robotic CCTV camera inspection (March 2019 Site Characterization Report). The water table is at approximately 14 to 16 ft bgs (greater on the western part of the Site; shallower on the east) and groundwater flow direction is toward the east-northeast. The sewer flow direction was toward the south and it is present near the water table in the south/southeast portion of the site (near CB-15). While no specific potential release has been identified, the sewer contains fine-grained material from historical site operations and from the ingress of surrounding soil through breaches in the sewer wall. COPCs including PCBs and metals have been detected in fine-grained material in the former industrial sewer at CB-24 (Figure 5-16) based on the findings of the March 2019 Site Characterization Report, and the location of breaches and obstructions along the former industrial sewer are indicated on Figure 5-16. The COPCs reported in fine grained material in the sewer and the presence of breaches in the sewer line present a potential source area to surrounding soil and there is unknown potential for vertical migration through the soil column to the water table.	Fine grained material can migrate downstream within the sewer via infiltrating stormwater, or migrate from the sewer into adjacent soil through breaches in the sewer pipe. PCBs and metals in the fine grained material that leaves the sewer can dissolve and migrate vertically toward the water table then downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in fine grained material within the sewer, or adjacent soil. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the sewer toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewer) toward off-site surface water receptors.	Fine Grained Material Soil Groundwater	P, M, S, V	2013 IRM PDI 2019 March Site Characterization Report 2019 May FFC PDI Activities Work Plan - Amendment #3 2019 August FFC PDI Activities Work Plan - Amendment #4 2020 Interim Remedial Measure #5 Work Plan 2021 May Soil and Groundwater Investigation Work Plan EHS Building Area 2024 Groundwater Monitoring Network Update - Addendum #3	1. The FIS located along the eastern property, identified as part of AOC-2 (Pre-1979 Combined Industrial/Storm Sewer), was evaluated through inline camera surveys, test pitting, sewer content (fine-grained material) sampling, and soil investigation as part of the RI and the FFC PDI (Figure 5-16). 2a. Fine-grained materials were collected from inside catch basins as part of the FIS investigation in 2019 including CB-24 and CB-28. Concentrations were detected above Class C SGVs for various metals including arsenic, barium, cadmium, chromium, copper, lead, mercury, nickel, silver, and zinc. PCB concentrations were reported at 2,452 mg/kg and 28.86 mg/kg (Figure 5-17 and Table 5-14). 2b.Fine-grained materials were collected from inside the FIS in December 2019 from Segment 3 (sample ID "Test Pit 3" from Test Pit 3b) and from Segment 4 (sample ID "Test Pit 2"). Concentrations were detected above Class C SGVs for metals (copper, lead, nickel, and zinc). PCB concentrations were reported at 45.29 mg/kg and 95.75 mg/kg (Figure 5-16 and Table 5-13). 3. Soil samples collected adjacent to Segments 2 and 3 had no detections of total PCBs above Restricted Residential SCOs or Protection of Groundwater SCOs. Arsenic was detected in sample SSHS-B2773-SUB-6-8 and SSHS-B2774-SUB-8-10 at concentrations of 17 and 21 mg/kg, respectively—above the Restricted Residential SCO and Protection of Groundwater SCO of 16 mg/kg. The source of arsenic is unknown. Arsenic detections were lower in the adjacent samples of fine-grained material in CB-24, Test Pit 2, and Test Pit 3b. Soil results do not indicate a release from the FIS to surrounding soils. 4. PCB TOGS groundwater standard exceedances in the East of Gym area (MW-30, MW-34, MW-41, MW-67S, MW-68S, and MW-89S (Table 5-8) are outside the Revised BCP Site Boundary but adjacent to the FIS (Figure 6-1A and Figure 6-2A). 5. TCE was detected at greater than TOGS groundwater standard at 22-32 ft bgs in temporary well B2978A (10 ug/L) adjacent to CB-28 (Table 5-11). Groundwater results do not indicate a release from the storm sewer, rather, it is likely related to AOC-11. 6. FIS removal was conducted during IRM #5, including removal of Segments 2 and 3 along the FFC boundary, Segments 4 and 5, Segment 7 within the FFC, and Segment 8 to the IRM haul road, to remove potential sources of hazardous waste. Confirmation sampling following FIS removal detected total PCBs at or above TSCA levels at FIS-S347 from 14-16 ft bgs. Conclusion: Vertical and lateral extent of AOC-2 has been defined in fine grained material, soil, and groundwater as part of the RI for #c808022. The source of AOC-2 was identified as the Former Industrial Sewer and has been removed as part of IRM #5 and IRM #5A2. Off-Site delineation will be completed and discussed in the #c808054 RIR/AA. Groundwater monitoring will continue under the SMP for Site #c808022.	Fine Grained Material - Yes Soil - Yes Groundwater - Yes	NA	-	MW-99I MW-99S MW-20 MW-68S MW-41	-	-	Not detected above RR SCOs	10 ft	Not detected above RR SCOs	-

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
2A	18" Clay Pipe at SE Property Corner	-	-	#c808054	AOC-2A/2B (18-in clay pipe, drywell near CB-15 and 5-ft box culvert) remain in place at the southeastern corner of the Site located on Site #c808054. The orientation, construction and depth of these features are known based on historical depictions (Lancy, 1967) and site investigation using geophysical methods, test pit excavations and robotic CCTV camera inspection (March 2019 Site Characterization Report). These features are near the water table at approximately 14 ft bgs. While no specific potential release has been identified, COPCs (P, S, M) were reported in fine-grained material sampled from catch basins. The COPCs reported in fine grained material in these features present a potential source area to surrounding soil and the underlying water table.	Fine grained material can migrate downstream within the sewer and culvert via infiltrating stormwater, or migrate from the sewer into adjacent soil. PCBs, SVOCs and metals in the fine grained material that leaves the sewer or culvert can dissolve and migrate vertically toward the water table then downgradient through groundwater. Stormwater containing fine grained materials discharging from these features could migrate to off site surface water.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in fine grained material within the sewer, or adjacent soil. 2. Off-site surface water users/ecological communities: Impacted groundwater or storm water (if present) may migrate downgradient/ downstream of the sewer toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewer) toward off-site surface water receptors.	Soil Groundwater	P, M, S, V	Investigations Completed as part of this AOC are documented under #c808054	Investigations completed as part of this AOC are documented under #c808054	To be investigated as part of #c808054							
2B	Drywell at SE Property Corner	-	-	#c808054																	
2C	Drywell Near Building 49	-	-	NAF	AOC-2C (Drywell near former Building 49) is located at the southeastern corner of the Northern Athletic Fields (Figure 1-4). It is located along an alignment parallel to the Site boundary but not visible by way of surface reconnaissance. The location and construction of this feature is known based on historical site drawings. The depth of this former drywell relative to the water table (present approximately 14 to 16 ft bgs) is unknown. While no specific potential release has been identified, COPCs have been reported in soil near this feature above protection of groundwater screening criteria. The COPCs reported present a potential source area for vertical migration through the soil column to the water table at the feature.	Fine grained material within the former dry well can migrate downstream within the sewer via infiltrating stormwater, or migrate from the dry well sewer into adjacent soil.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in fine grained material within the dry well, or adjacent soil. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the dry well toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewer) toward off-site surface water receptors.	Soil Groundwater	P, M, S, V	2001 Sampling Report 2003 Health Consultation 2009 EMP 2018 FFC RI/PDI Work Plan 2019 Revised Remedial Investigation Work Plan 2023 July Groundwater Monitoring Network Update - Addendum #3 2026 NAF CCR	1. AOC-2C was evaluated by soil and groundwater investigations in 2021, TPH diesel range organics were detected above the nuisance criteria of 1,000 mg/kg at B3343, B3668, B3669, and B3670 in the southeastern corner of the NAF between 10 and 16 ft bgs (Figures 5-4F to 5-4H). Metals, SVOCs, and VOCs were not detected above Restricted Residential SCOs or Protection of Groundwater SCOs at those locations or in surrounding soils. PCBs exceeded Protection of Groundwater SCOs in this area at B572A from 16-18 ft bgs but is vertically delineated below 18 ft bgs. 2.TOGS groundwater standards exceedances at the adjacent monitoring well, MW-58, were for iron and manganese only and are attributed to groundwater redox fluctuations and are not Site-related (Figure 6-1B and Figure 6-2B). This sampling was completed under the Groundwater Monitoring Network Update - Addendum #3. 3. Excavation as part of IRM #5A2 (Area 3) in the southeast corner of the NAF did not identify a historical drywell associated with AOC-2C. Conclusion: Comprehensive excavations were completed as part of IRM #5A2; however, the drywell associated with AOC-2C was not located. COPCs in soil and groundwater investigations completed under the #c808022 RI have been laterally and vertically defined based on the information above.	Soil - Yes Groundwater - Yes	4	MW-58	MW-98S MW-98I MW-99S MW-99I	-	-	18 ft	Not detected above RR SCOs		
2D	Manhole SW-73 Near Building 28A	-	-	FFC	AOC-2D (Manhole SW-73) was located near Former Building 28A (Figure 1-3 and 1-4); this area was previously addressed by sampling and remedial actions for IRM #1 and the FFC PDI. COPCs including PCBs and metals have been detected in fine-grained material in the former industrial sewer at CB-01 and CB-24 (Figure 5-16) based on the findings of the March 2019 Site Characterization Report. The depth of this former manhole relative to the water table (present approximately 14 to 16 ft bgs) is unknown. Like other features associated with the former industrial sewer, the presence of COPCs in fine grained material in the manhole presents a potential source area to surrounding soil and the underlying water table.	Fine grained material (if present) within the former manhole can migrate downstream within the sewer via infiltrating stormwater, or migrate from the manhole into adjacent soil.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in fine grained material within the manhole, or adjacent soil. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the manhole toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewer) toward off-site surface water receptors.	Soil Groundwater	P	1952 DOH Waste Sampling 2001 Sampling Report 2003 Health Consultation 2009 EMP 2015 May Site Characterization Work Plan - Addendum #1 2016 January Site Characterization Work Plan - Addendum #2 2016 August Site Characterization Work Plan - Addendum #3 2017 February Site Characterization Work Plan - Addendum #4 2017 March Site Characterization Work Plan - Addendum #5 2017 IRM #1 Work Plan 2019 March Site Characterization Report 2021 May Soil and Groundwater Investigation Work Plan - EHS Building Area 2024 IRM #3 CCR	1. PCBs above PoG, RRSCOs, and hazardous waste criteria were identified within and surrounding AOC-2D from 0-16 ft bgs between 2015 and 2017 under the Site Characterization Work Plan and subsequent addenda. 2. Remediation for IRM #3, completed in 2019, occurred within the AOC-2D footprint from 14-16 ft bgs. IRM confirmation samples collected at the base of the excavation and AOC footprint above SCOs for PCBs included IRM3-B016 (2.68 mg/kg), IRM3-S201 (5.79 mg/kg), and IRM4-S163BOT2 (12.09 mg/kg) as depicted on Figure 6-4H. IRM confirmation samples above SCOs are laterally delineated by B2812, B800, B792, and B803/B803A and vertically delineated by B800, B792, and B803A. 3. Temporary monitoring well (B2752) and monitoring wells (MW-15S and MW-84S) were installed to measure PCB concentrations in groundwater below AOC-2D. Total and dissolved PCBs were reported above TOGS groundwater standards for MW-15S in 2016 at 0.48 and 0.594 µg/L. Temporary monitoring well B2752 was sampled in 2019 and was ND. MW-15S was decommissioned in preparation for excavation of IRM #1. MW-84S was installed to replace MW-15S in 2021. Results for PCBs at MW-84S were ND. Conclusion: Vertical and lateral extent of AOC-2D has been defined in soil and groundwater as part of the RI for #c808022. Comprehensive excavations were completed as part of IRM #3; however, the manhole associated with AOC-2D was not located. PCBs in soil and groundwater investigations completed under the #c808022 RI have been laterally and vertically defined based on the information above.	Soil - Yes Groundwater - Yes	16	-	B3861S B3861I	-	-	16 ft	-	-	-

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
2E	Waste Pit near Building 44	-	-	EHS Building	AOC-2E (Former waste pit) underlies the EHS building (Figure 1-4). The depth of this feature relative to the water table (present approximately 14 to 16 ft bgs) or the presence of COPCs in its immediate vicinity are unknown. While no specific potential release has been identified, COPCs have been reported in soil near this feature above protection of groundwater screening criteria. While the presence of the EHS building slab reduces the potential for stormwater infiltration, the COPCs reported present a potential source area for vertical migration through the soil column to the water table at the feature. The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers. The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B).	COPCs in subsurface soil (if present) can migrate toward the water table and then downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	1967 Lancy Report &Figures 1958 DOH Industrial Outfall Report 1977-79 SHS Construction and Demolition Plans Sanborns Fire Insurance Maps Oil House 1994 Miller Pond Spill #94-166682001 Sampling Report 2003 Health Consultation 2009 EMP 2010 ACR 2013 IRM PDI 2014 VI Assessment 2018 Supplemental VI Assessment 2021 May Soil and Groundwater Investigation Work Plan - EHS Building Area 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. Monitoring wells installed downgradient and/or cross gradient of AOC-2E include MW-13 and MW-85I located within Site #c808022 and MW-88S and MW-88I located within Site #c808054. 1a. MW-13 was sampled for total and/or dissolved PCBs in February and July 2021 and April 2024. For each event, results were below TOGS. SVOCs and VOCs were sampled in August 2014, February and July 2021, and April 2024. For each event, results were below TOGS. Metals and PFAS were sampled in February and July 2021. PFAS was reported below TOGS; however, metals, specifically for iron (1,000-3,300 µg/L) and manganese (420-760 µg/L) were reported above TOGS for each sampling event. 1b. MW-85I was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, PCBs and VOCs were below TOGS. In 2024, iron exceeded TOGS at 310 µg/L. SVOCs were reported above TOGS in July 2021 for DEHP at 13 µg/L but were below TOGS in September 2021 and in 2024. 1c. MW-88I was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, results for PCBs, SVOCs, and VOCs were below TOGS. Metals exceeded TOGS in 2024, specifically for iron (890 µg/L). 1d. MW-88S was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, results for PCBs, SVOCs, and VOCs were below TOGS. Metals exceeded TOGS for each sampling event, specifically for iron (800-7,300 µg/L) and manganese (1,600-2,300 µg/L). 2. Concentrations reported above TOGS for iron and manganese only are attributed to groundwater redox fluctuations and are not Site-related. DEHP is a common lab contaminant and is not a Site COPC. 3. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor sample SSHS-23-SS was collected in the vicinity of AOC-2E, within Room 156. VOCs were reported below NYSDOH Matrix Guidelines at SSHS-23-SS. 4. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). Conclusion: Nature and extent of potential groundwater contamination associated with AOC-2E beneath the EHS building was investigated through sampling of downgradient monitoring wells. COPCs in groundwater samples collected on Site #c808022 and #c808054 have been defined based on the information above. SSDS have been installed in to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring.	Groundwater - Yes	NA	-	MW-88S MW-88I	SSHS-23-SS	Gymnasium	As additional soil investigation beneath the EHS building was not feasible the presence of COPCs in soil within the portions of AOC-2E underlying the school building is unknown			
3	1979 Storm Sewer	-	-	Site-Wide	AOC 3 (1979 storm sewer) is currently used as the high school's storm water drainage system, and the location is shown on Figure 1-4. Pre-RI work, including FFC RI/PDI, has assessed the location, orientation and depth of sewer. Fine grained material from catch basins within the FFC have been assessed and sampled where material was present as part of the FFC RI/ IRM#3 PDI. Given the depth of the catch basins (up to 12 feet bgs) relative to the water table (present approximately 14 to 16 ft bgs) these COPCs present a potential source area for vertical migration through the soil column to the water table.	Fine grained material (if present) within the storm sewer can migrate downstream within the sewer via stormwater transport, or migrate from the storm sewer or catch basins into adjacent soil.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in fine grained material within the storm sewer, catch basins, or adjacent soil. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the storm sewer toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewer) toward off-site surface water receptors.	Fine-Grained Material Soil Groundwater	S,M,P	2013 IRM PDI Data Report 2019 FFC PDI Activities Work Plan - Amendment #3 2019 FFC PDI Activities Work Plan - Amendment #4 2020 FFC PDI Data Report 2026 FFC CCR	1. The active EHS storm sewer water line (post-1979) located on the south side of the FFC (flowing W-E) with laterals extending north along the east and west sides of the FFC, identified as AOC-3, was evaluated through inline camera surveys, geophysical investigation, inspection of catch basins (dimensions, depths, integrity of structure), catch basin content (fine-grained material) sampling, soil investigation, and groundwater investigation as part of the RI and FFC PDI. 2. Twenty (20) catch basins were inspected along the current storm sewer line in the FFC as part of the investigation in 2019 (Table 2-7). All catch basins were observed to have solid bottoms. Fine-grained materials were collected from inside (13) catch basins (Table 5-14). For two catch basins (CB-05, CB-09), fine grained materials were not observed during 2019 field inspection, so data from a sampling event in 2015 were included for evaluation. Concentrations were detected above NYSDEC Class C SGVs for total PAHs (CB-05) and chromium (CB-09). Given that no spatial trends were observed, and the most downstream catch basin (CB-05) had exceedances for total PAHs only, this indicated that these exceedances were localized. Exceedances remain in place in catch basins due to active EHS use of the storm sewer line. 3. Soil samples were collected adjacent to the down-gradient side of CB-05 and CB-09 where exceedances were detected in catch basin fine-grained material (Table 5-14). There were no detections in samples collected by CB-05. PCBs were detected above the subsurface screening criteria in sample B2977-SUB-10-12 (13.48 mg/kg) collected adjacent to CB-09, but there were no exceedances in sample B2977-12-14. This exceedance is laterally delineated by B653, B3567, B621, and B646 and vertically delineated by B2877, B2724, B653, and B3567. Soil results do not indicate a release from the storm sewer to surrounding soils. The soil exceedance at B2977-SUB-10-12 remains in place (Table 5-6A). 4a. Monitoring wells installed directly downgradient of the exceedance at CB-09 on Site #c808022 include temporary wells B3557, B3558, B3559, B3560, B3561, B3562, B3563, B3563I, B3564, B3565, B3566, and MW-103S and MW-103I. The temporary wells were sampled in January 2021 for total and/or dissolved PCBs, metals, and VOCs. During this event, results for PCBs were above TOGS in nine of the temporary wells, ranging from 0.097 ug/L (B3571) to 32.85 ug/L (B3563I). PCBs were detected below TOGS in well B3559 and non-detect in wells B3557 and B3560. Metals were detected in all 12 wells, but none exceeded TOGS. VOCs were detected in wells B3563 and B3563I but did not exceed TOGS. MW-103S and MW-103I were sampled for total and/or dissolved PCBs, metals, SVOCs, VOCs, and 1,4-dioxane in September 2023 and April 2024. For each event, results for total PCBs exceeded TOGS. MW-103I had concentrations of 6 ug/L and 7.99 ug/L, and MW-103S had concentrations of 2 ug/L and 1.6 ug/L, respectively. Metals and SVOCs were detected but did not exceed TOGS for both wells on both sampling dates. VOCs and 1,4-dioxane were non-detect for both wells on both sampling dates. Groundwater results do not indicate a release from the storm sewer. 4b. Monitoring wells installed directly downgradient of the exceedance at CB-05 on Site #c808022 include MW-33, MW-34, and MW-10. MW-33 was sampled in March 2016 for PCBs (detected below TOGS); in February 2021 for metals, PCBs, emerging contaminants, VOCs, and SVOCs; and in July 2021 for PCBs, metals, VOCs, SVOCs, and emerging contaminants. The February 2021 sample had metals exceedances of TOGS for iron (3,000 ug/L) and manganese (1,500 ug/L), emerging contaminants detected below TOGS, and no detection for PCBs, VOCs, or SVOCs. The July 2021 sample had a metals exceedance of TOGS for iron (1,700 ug/L) and manganese (990 ug/L), a SVOCs exceedance of TOGS for bis(2-ethylhexyl) phthalate (DEHP, 8 ug/L), emerging contaminants detected below TOGS, and no detection for PCBs or VOCs. MW-34 was sampled in August 2018 and March 2016 for PCBs and in February, March, and April 2021 for PCBs, metals, emerging contaminants, VOCs, and SVOCs. PCBs exceeded TOGS in samples taken in 2014 (1.9 ug/L) and 2016 (1.1 ug/L). In 2021, PCBs exceeded TOGS in February and April (0.59 ug/L and 0.29 ug/L, respectively), and metals exceeded TOGS in February and April for iron (6,400 ug/L and 1,100 ug/L, respectively) and manganese (1,700 and 1,100, respectively), and SVOCs exceeded TOGS in March and April for bis(2-ethylhexyl)phthalate (DEHP, 9.8 ug/L). Emerging contaminants were detected below TOGS, and VOCs were not detected in 2021. MW-10 was sampled in August 2014 for PCBs (non-detect); February 2021 for PCBs (non-detect), metals, and VOCs (non-detect); March 2021 for SVOCs (non-detect), and July 2021 for PCBs, metals, VOCs, and SVOCs. Metals exceeded TOGS in February 2021 for iron (4,300 ug/L) and manganese (1,500 ug/L). In July 2021, metals exceeded TOGS for iron (1,800 ug/L) and manganese (1,100 ug/L), SVOCs exceeded TOGS for bis(2-ethylhexyl) phthalate (DEHP, 44 ug/L), and PCBs and VOCs were not detected. 5. Concentrations reported above TOGS for iron and manganese only are attributed to groundwater redox fluctuations and are not Site-related. DEHP is a common lab contaminant and is not a Site COPC. Conclusion: Vertical and lateral extent of AOC-3 has been defined in fine grained material, soil, and groundwater as part of the RI for #c808022 based on the supporting information above.	Fine-Grained Material- Yes Soil - Yes Groundwater - Yes	NA	-	MW-11S MW-11I MW-44 MW-38 MW-102S MW-102I MW-33 MW-39 MW-103S MW-103I B3557 B3558 B3559 B3560 B3561 B3562 B3563 B3563I B3564 B3565 B3566	-	K-Wing	14 ft	8 ft	Not detected above RRSCOs	-

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
3A	1979 Drywell Field	AOC-3A-1	-	NAF	AOC 3A (Drywell Fields) includes eight (8) discrete areas characterized by NYSDEC as drywell fields located in the Northern Athletic Fields and near the tennis courts (Figure 1-4). One (1) small area near the tennis courts was characterized by sampling associated with IRM #1. The location and construction of these dry wells are known based on historical site drawings. Their depth relative to the water table (present approximately 14 to 16 ft bgs) is unknown. While no specific potential release has been identified, historical operation of these structures have the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table.	Fine grained material (if present) within the former dry wells can migrate downstream within the sewer via infiltrating stormwater, or migrate from the dry well structures into adjacent soil.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in fine grained material within the dry well, or adjacent soil. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the dry well toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewer) toward off-site surface water receptors.	Soil Groundwater	P, M, S, V	1977-79 SHS Construction and Demolition Plans 2001 Sampling Report 2003 Health Consultation 2009 EMP 2022 Dry Well Closure Plan 2022 Revised NAF Dry Well Soil Quality Verification WP 2023 Revised NAF Dry Well Soil Quality Verification Report 2023 Dry Well DW-3B Soil Quality Verification Update 2024 Dry Well Closure Plan, Amendment #1 2024 Dry Well Closure Report 2026 NAF CCR	1. AOC-3A is comprised of eight discrete areas characterized as drywell fields, including DW-1, DW-2, DW-3, DW-3A, DW-3B, DW-20, DW-21, DW-N and one unnamed drywell in the NAF, and one unnamed drywell west of the tennis courts. As these wells were encountered during IRM activities, the surrounding soil and groundwater was evaluated, as well as fine-grained material encountered inside the dry wells, before wells were abandoned in place or removed. 2. DW-1, DW-2, and DW-3 were identified northwest of the softball field during IRM #5A2 excavations, and removed between 8 November 2021 and 10 November 2021. Confirmation samples were taken, and there were no exceedances of screening criteria at DW-1 or DW-2. A DW-3 sidewall confirmation sample had a restricted residential exceedance (1300 mg/kg) of copper at 4-6 ft bgs (IRM5A2-DW3-S1) and a PoG exceedance (50 mg/kg; 270 mg/kg) of chromium(III+IV) and nickel at 8-10 ft bgs (IRM5A2-DW3-4). These exceedances remain in place and are laterally delineated by B3254, B418-S2, S448, and AreaC-B3-S1 and B3069, B3921, DW-16, B2056, and B3055, respectively. They are both vertically delineated by DW3-BOT1, B3069, and B3921. No groundwater TOG exceedances have been detected in MW-54, located adjacent to AOC-3A, indicating no groundwater impacts from DW-3. 3. Drywell DW-20 was encountered during excavations on 20 April 2022 at 2 feet bgs. A soil sample was collected from the interior of DW-20 (IRM5A2-A5-DW1) and did not show exceedances of IRM #5A2 screening criteria or action levels. An 8-in diameter steel pipe connection to the south was observed, and on 3 May 2022, DW-21 was observed approximately 90-inches south of the pipe opening at 2.5 feet bgs. DW-21 was not sampled. Removal of DW-21 was not feasible due to its proximity to the EHS maintenance shed, therefore a Dry Well Closure Plan was submitted and approved as modified. The dry wells were abandoned in place using flowable fill. MW-63I and MW-63S are in this AOC-3A area and have been sampled for PCBs, metals, SVOCs, and VOCs in February 2021, April 2021, and September 2023. MW-63I had one TOGS exceedances of PCBs (0.53 ug/L) in February 2021. There were no other exceedances of any constituents in either well. This PCB exceedance is unlikely to be associated with AOC-3A as there were no exceedances from the drywell sample. 4. Dry wells DW-3A and DW-3B were exposed during soil removal excavations for IRM #5A2 in the EHS shotput and discs area. DW-3A was removed due to an exceedance of the PoG SCO for PCBs in a sidewall sample at 4-6 feet bgs (FL-FISN-S41), and soil was excavated to a depth of 6 feet bgs. Due to an exceedance of the PoG SCO for arsenic in a sidewall sample from an IRM #5A2 excavation approximately 28 feet northwest of DW-3B, Geosyntec evaluated anticipated groundwater mounding at DW-3B. It was concluded that stormwater infiltration from DW-3B would not result in groundwater contact with the area of the PoG SCO exceedance, so modification was not needed, and the dry well remains in place. 5. Exceedances of PCB PoG down to 18 ft beneath the softball fields and near AOC-19 (SSHS-B3884-SUB-14-16, 121 mg/kg, and SSHS-B3884-16-18, 32.1 mg/kg) were sampled in 2021. Additional groundwater data at MW-50 indicated PCB exceedances in this area in 2021 (2.3 ug/L). Between 8 February 2022 and 9 February 2022, an unnamed historical dry well located beneath the softball fields was encountered and removed to facilitate excavations to 16 ft. The exceedance at 18 feet remains in place, and is laterally delineated by B3923, B3454, S311, and S725 and vertically delineated by B3884, B3924, and B3926. Data above SCOs for soil and GW above TOGS are not indicative of a release from AOC-3A, but rather, likely related to AOC-19 (see AOC-19). 6. During excavation along the northern Site boundary under IRM #5A2 Addendum #8 Phase 7, a dry well (DW-N) was observed at the northern entrance to the VFW property at approximately 1.5 feet bgs. On 9 April 2024, a sample of fine-grained materials was collected from the interior where no detections above PoG SCOs were reported. MW-53 is located adjacent to DW-N, and has been sampled in February 2021, April 2021, and September 2023. No exceedances of TOGS were detected for PCBs, metals, VOCs, or SVOCs. DW-N was filled with flowable fill and abandoned in place. Historical plans indicate two additional dry wells on the northern property line, but no other dry wells were identified by IRM activities. It is presumed that these two wells no longer exist and/or were removed when the gas line was installed. 7. Significant excavations were conducted up to 12 feet bgs along the eastern property line where historical plans indicate additional dry wells, but no dry wells were encountered. It is presumed that they may have been removed during the gas line installation. 8. Historical plans indicate one dry well located west of the tennis courts, however, its footprint is outside of #c808022. This well was not encountered during excavations or RI investigation borings, investigations completed for this location are documented under #c808054. Conclusion: Vertical and lateral extent of AOC-3A has been defined in soil, groundwater, and fine-grained material as part of the RI for #c808022 as discussed above. Comprehensive excavations were completed as part of IRM #5A2. Drywells associated with AOC-3A were either not located, or were identified and removed during the IRM.	Soil - Yes Groundwater - Yes	10	MW-51, MW-106, MW-57R, MW-100S, MW-100I, B3882, B3916S, B3916I	MW-96 MW-97	-	-	25 ft	40 ft	4 ft	-
		AOC-3A-3											10	MW-66I, MW-66S	MW-64S MW-64I	-	-				
		AOC-3A-4											6	MW-63I, MW-63S	MW-56	-	-				
		AOC-3A-5											5	MW-54	MW-50S MW-50I	-	-				
		AOC-3A-6											3	-	MW-49	-	-				
		AOC-3A-7											13	MW-50I, MW-50S	MW-50R MW-51	-	-				
		AOC-3A-8											4	MW-48, MW-53	-	-	-				
		AOC-3A-2		#c808054									To be investigated as part of #c808054								
4	Earthen Waste Pits near EHS Gym and Pool	-	-	EHS Building	AOC 4 (Earthen waste pits) is located below the EHS gymnasium on Site #c808022 and an adjoining portion on #c808054 (Figure 1-4). The location and depth of the former waste pits are known from historical documentation. The former elevations of the waste pits were from approximately 852 to 857 feet msl. While the presence of the EHS building slab reduces the potential for stormwater infiltration through this AOC, the feature has the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table (present approximately 14 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers.	COPCs in impacted soil within or beneath the former waste pits (if present) can dissolved and migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	2001 Sampling Report 2003 Health Consultation 2004 IIWA GW Investigation 2006 Guidance for Evaluating Vapor Intrusion in The State of New York 2009 EMP 2010 Health Consultation 2010 ACR 2014 VI Assessment 2017 Soil Vapor Intrusion Updates, May 2017: Updates to Soil Vapor/Indoor Air Decision Matrix 2018 Supplemental VI Assessment 2019 ISMP 2021 May Soil and Groundwater Investigation Work Plan EHS Building Area 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. AOCs within the footprint of the EHS building (see Figure 1-4) including AOC-4, were evaluated using conventional indoor air, outdoor air, and sub-slab vapor sampling data and HVS data, as well as data from previous soil and groundwater investigations and the RI groundwater investigation. 2. Sub-Slab Vapor: 1,1,1-trichloroethane (TCA) and Trichloroethene (TCE) were detected below the east side of the Gymnasium in 2009 at concentrations of 23,000 µg/m3 and 28 µg/m3, respectively. ECSD installed a sub-slab vapor mitigation system in the Gymnasium in 2010. Sub-slab vapor below the Gymnasium was not sampled by Unisys in 2014 and 2018 due to the presence of the vapor mitigation system. Sampling of the Gymnasium SSD effluent by Unisys detected 19 µg/m3 of TCE in June 2018 and 3.4 µg/m3 of TCE in November 2023. TCA was not detected above the laboratory reporting limit. This suggests that TCE may be present in sub-slab vapor below the Gymnasium at decreasing concentrations, but the continued presence of TCA is unknown. 3. Indoor Air: ECSD collected indoor air samples at eight locations in December 2009 as part of the Indoor Air Quality Action Plan included in the EMP. 1,1,1-trichloroethane (TCA) was detected at a concentration of 2.4 µg/m3 in the Gymnasium, below the Soil Vapor/Indoor Air Decision Matrix 2 value for mitigation of 3 µg/m3 issued in 2006 and maintained in the Soil Vapor/Indoor Air Decision Matrix B value for mitigation issued in 2017. 4. Vapor Mitigation: A sub-slab vapor mitigation system was installed in the EHS gymnasium as part of a remodeling project conducted in 2010 (Sterling, 2011). The vapor mitigation system consists of a vapor barrier and a SSD system. 5. Monitoring wells installed directly downgradient and/or crossgradient of AOC-4 on Site #c808054 include MW-12, MW-87I, MW-88I, and MW-88S. 5a. MW-12 was sampled for total and/or dissolved PCBs in July and September 2021. For each event, results for PCBs were below TOGS. Metals exceeded TOGS in February 2021 for aluminum (4,200 µg/L), iron (7,000 µg/L) and manganese (1,300 µg/L). Dissolved manganese exceeded TOGS at 360 µg/L. Iron was also detected above TOGS in July 2021 at 560 µg/L. SVOCs exceeded TOGS in 2000 for Benzo(a)anthracene (1. 2 µg/L) and chrysene (2.8 µg/L) but were below TOGS in 2021. DEHP exceeded TOGS in July 2021 at 6.1 µg/L. MW-12 was sampled 17 times between 1997 and 2021. During these sample events, cis-1,2-dochloroethene (9 µg/L) and freon (30-160 µg/L) were reported above TOGS. Results in 2021 did not report VOCs above TOGS. 5b. MW-87I was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, results for PCBs and VOCs were below TOGS. Metals exceeded for iron (400 µg/L) in July 2021 and July and September 2021 for manganese (340-630 µg/L). SVOCs exceeded TOGS for DEHP in July (13 µg/L) and September (21 µg/L) 2021. 5c. MW-88I was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, results for PCBs, SVOCs, and VOCs were below TOGS. Metals exceeded TOGS in 2024, specifically for iron (890 µg/L). 5d. MW-88S was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, results for PCBs, SVOCs, and VOCs were below TOGS. Metals exceeded TOGS for each sampling event, specifically for iron (800-7,300 µg/L) and manganese (1,600-2,300 µg/L). 5e. Concentrations reported above TOGS for iron and manganese only are attributed to groundwater redox fluctuations and are not Site-related. Conclusion: Soil Vapor and indoor air have been assessed and investigated as part of AOC-1. Nature and extent of potential groundwater contamination associated with AOC-4 beneath the EHS building was investigated through sampling of downgradient monitoring wells. Additional soil investigation downgradient of AOC-4 is being addressed under #c808054. COPCs in groundwater samples collected on Site #c808022 and #c808054 have been defined based on the information above for this AOC.	Groundwater - Yes	NA	-	MW-12 MW-87I MW-88S MW-88I SB1 B26-A B29-A	SV-GYM EAST	Gymnasium	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-4 underlying the school building is unknown			

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
5	Sludge Tanks/ Beds/Brick Pits near Building 64	AOC-5-1	-	EHS Building	AOC 5 (sludge tanks/beds/brick pits near Building 64) underlies the EHS building (Figure 1-4). Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil. While the presence of the EHS building slab reduces the potential for stormwater infiltration through this AOC, the feature has the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers.	COPCs in impacted soil within or beneath the former pits (if present) can dissolved and migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	2003 DOH Health Consultation 2009 EMP 2009 Indoor Air/Sub-slab Vapor Investigation 2010 DOH Health Consultation 2013 IA Sampling 2014 VI Assessment 2018 Supplemental VI Assessment 2019 ISMP 2020 April Remedial Investigation Workplan Amendment 2021 April Soil and Groundwater Investigation Workplan - EHS Building Area (EoG) 2022 June Groundwater Monitoring Network Update 2023 August Groundwater Monitoring Network Update - Addendum #3 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. Monitoring wells installed downgradient of AOC-5 includes MW-91S and MW-91I location on Site #c808054. 1a: MW-911 was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in September and November 2021 and April 2024. PFAS was only sampled in September and November 2021. PCBs, metals, SVOCs, VOCs, and PFAS were reported below TOGS for each sampling event. 1b: MW-91S was sampled for total and/or dissolved PCBs, metals, SVOCs, VOCs in September and November 2021 and April 2024. PFAS was only sampled in September and November 2021. PCBs, SVOCs, and VOCs were reported below TOGS for each sampling event. Total and dissolved manganese was reported above TOGS (720-740 µg/L) in September 2021, but below in November 2021 and April 2024. Perfluorooctanesulfonic acid (PFOS) was reported above TOGS (5.7 ng/L) in September 2021, but below in November 2021. 1c. Concentrations reported above TOGS for iron and manganese only are attributed to groundwater redox fluctuations and are not Site-related. Concentrations for PFOS above TOGS is believed to be attributed to an off-site upgradient source. 2. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor samples were collected within AOC-5-4 (SSHS-10-SS), AOC-5-2 (SSHS-09-SS), in the vicinity of AOC-5V-2A-F (SSHS-08-SS and SSHS-03-SS), and in the vicinity of AOC-5-1 (SS-133). Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. VOCs were detected below NYSDOH Matrix Guidelines for these sample locations with the exception of SSHS-03-SS. Sub-slab samples collected near AOC-5 in Room 127 (SSHS-03-SS) had TCE (39,000 µg/m3) and cis-1,2-DCE (2,000 µg/m3) observed above NYSDOH Matrix guidelines for sub-slab vapor (Figure 5V-2A-F). Based on the detections of TCE and cis-1,2-DCE, Unisys installed a sub-slab vapor mitigation system in the F-Wing in 2014 as discussed in Section 3.2.4. TCE and cis-1,2-DCE were detected in the SSD system effluent in November 2023 with concentrations of 339 µg/m3 and 66.6 µg/m3, respectively. TCE effluent concentrations decreased between June 2018 and July 2021, increased in December 2021, then slightly decreased in November 2023 as shown on Figure 6V-2. This indicates that TCE and cis-1,2-DCE are still present in sub-slab vapor below F-Wing and may potentially be associated with AOC-5. 3. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). Conclusion: Soil Vapor and indoor air have been assessed and investigated as part of AOC-1. Nature and extent of potential groundwater contamination associated with AOC-5 beneath the EHS building was investigated through sampling of downgradient monitoring wells located on Site #c808054. COPCs in groundwater samples collected on Site #c808054 have been defined as part of #c808022 based on the information above.	Groundwater - Yes	NA	-	MW-71S MW-71I MW-90S MW-90I MW-91S MW-91I	SS-133	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-5 underlying the school building is unknown			
		AOC-5-2											NA	-		SSHS-09-SS	-				
		AOC-5-3											NA	-		SSHS-08-SS, SSHS-03-SS	F-Wing				
		AOC-5-4											NA	-		SSHS-10-SS	-				

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
6	Concrete Vaults	AOC-6-3	-	EHS Building	AOC 6 (concrete vaults) are discrete areas characterized by NYSDEC as former concrete vaults located north of the EHS building and one discrete area straddling the southwestern Site boundary (Figure 1-4). Two other discrete areas identified as part of AOC 6 lie off Site to the south and as such are not included in the RI for this Site. The former concrete vault area north of the EHS building has been characterized by the RI of the FFC and PDI activities for IRM #3. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table (located approximately 14 to 16 ft bgs).	COPCs in impacted soil within or beneath the former vaults (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	1967 Lancy Report and Figures 1977-79 SHS Construction and Demolition Plans 1977 Empire Soils Report 1994 Miller Pond Spill #94-16668 2003 DOH Health Consultation 2009 EMP 2010 DOH Health Consultation 2011 2013 EMP Annual Reports 2014 VI Assessment 2015 May Site Characterization Work Plan - Addendum #1 2016 January Site Characterization Work Plan - Addendum #2 2016 August Site Characterization Work Plan - Addendum #3 2017 February Site Characterization Work Plan - Addendum #4 2017 March Site Characterization Work Plan - Addendum #5 2018 Supplemental VI Assessment 2019 ISMP 2019 March Site Characterization Report 2020 September Football Field Complex Pre-Design Investigation Report 2023 Annual Heating Season Sampling 2024-2025 PRRs 2026 FFC CCR	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor sample SSHS-164 was collected within AOC-6-3. VOCs were reported below NYSDOH guidelines at SSHS-164. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-6-3 on groundwater quality were evaluated using samples collected from monitoring wells located downgradient of the AOC. Monitoring wells installed downgradient of AOC-6-3 include MW-85I and MW-13. Groundwater samples collected as part of the RI investigation of AOC-6 were analyzed for PCBs, metals, SVOCs, and VOCs. Groundwater samples are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Groundwater analytical results are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs, metals, VOCs, and SVOCs were not observed above TOGS groundwater standards at MW-85I and MW-13 downgradient of AOC-6-3. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2025 and 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	NA	-	MW-85I MW-13	SSHS-164	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-6-3 underlying the school building is unknown			
		AOC-6-1		NAF			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. One soil boring, B3103, was installed within AOC-6-1 to a maximum depth of 16 ft bgs. COPCs, including PCBs, metals, and VOCs, were not identified above Restricted Residential SCOs. As per the 2019 RI Work Plan, SVOCs were previously collected within 30 ft of AOC-6-1 including B38 and B404 where concentrations were not identified above Restricted Residential SCOs. Historical vaults associated with AOC-6 were not identified during IRM excavations. 2. Monitoring well MW-65 was installed within AOC-6-1. MW-65R was installed downgradient of AOC-6-1. PCBs, Metals, SVOCS, and VOCs were reported below TOGS groundwater standards. Metals were not consistently reported at concentrations above TOGS groundwater standards in monitoring wells with the exception of thallium, iron, and manganese. For these three metals, further evaluation found that thallium exceedances are due to false positive bias due to the analytical method, and iron and manganese concentrations are not Site-related. Conclusion: Comprehensive excavations were completed as part of IRM #4, IRM #4A, IRM #5 where a specific source of AOC-6-1 was not identified. Vertical and lateral extent of AOC-6-1 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above		16	MW-65	MW-65R	-	-	Not detected above RR SCOs			
		AOC-6-2		FFC			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater		1. Soil borings completed within AOC 6-2, 6-7, 6-8, 6-9, and 6-10 were completed between 2016 to 2019 from 0 to 16 ft bgs for PCBs, metals, SVOCs, and VOCs. Concentrations above SCOs were identified for PCBs ranging between 1.03-37.2 mg/kg. PCBs exceeding SCOs were subsequently removed during excavations completed on the FFC during IRM #4, IRM #4A, and IRM #5. Historical vaults associated with AOC-6 were not identified during IRM excavations. 1a. PCBs remain in place above RRSCOs and/or PoG in confirmation samples collected following slide rail excavations to 16ft bgs as well as borings completed within the AOC footprint or immediately up-gradient to depths of 42 ft bgs, but are laterally and vertically delineated in soil. 2. Monitoring wells installed downgradient of AOC-6 and of areas where concentrations above SCOs remain at or below the water table include MW-13, MW-36, MW-40, and MW-85I. 2a. MW-13 was sampled for total and/or dissolved PCBs in February and July 2021 and April 2024. For each event, results were below TOGS. SVOCs and VOCs were sampled in August 2014, February and July 2021, and April 2024. For each event, results were below TOGS. Metals and PFAS were sampled in February and July 2021. PFAS was reported below TOGS; however, metals, specifically for iron (1,000-3,300 µg/L) and manganese (420-760 µg/L) were reported above TOGS for each sampling event. Metals were not detected above SCOs during soil investigations completed within AOC-6. 2b. MW-36 was sampled for total and/or dissolved PCBs in March 2016, August 2018, and March and April 2021. For each sampling event, PCB results were below TOGS. Total and/or dissolved metals and VOCs were sampled in August 2018 and March and April 2021. For each sampling event, VOCs were below TOGS. Total and dissolved Metals concentrations exceeded TOGS for each sampling event for iron (2,000-8,300 µg/L) and manganese (1,000-3,700 µg/L), with the exception of totals concentrations for arsenic (41 µg/L) and lead (31 µg/L) which exceeded TOGS in March 2021. Additional sampling completed in April 2021 for total and dissolved arsenic and lead did not exceed TOGS. SVOCs were sampled in August 2018 and March and April 2021 where DEHP exceeded TOGS at 5.3 and 9.9 µg/L. 2c. MW-40 was sampled for total PCBs, metals, SVOCs, and VOCs in May 2019 and February 2021. For each sampling event, PCB, SVOC, and VOCs results were below TOGS. Metals concentration exceeded TOGS for each sampling event, specifically iron (4,000-4,500 µg/L) and manganese (660-930 µg/L). 2d. MW-85I was sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in July and September 2021 and April 2024. For each event, PCBs and VOCs were below TOGS. In 2024, iron exceeded TOGS at 310 µg/L. SVOCs were reported above TOGS in July 2021 for DEHP at 13 µg/L but were below TOGS in September 2021 and in 2024. 2e. Concentrations reported above TOGS for iron and manganese only are attributed to groundwater redox fluctuations and are not Site-related. DEHP is a common lab contaminant and is not a Site COPC. Conclusion: Comprehensive excavations were completed as part of IRM #4, IRM #4A, IRM #5 where a specific source of AOC 6-2, 6-7, 6-8, 6-9, and 6-10 was not identified. Vertical and lateral extent of AOC-6 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above		16	-	MW-44 MW-38 MW-36 B3864S B3864I B3859S B3859I B3869S B3860I B3557 B3881I B3556 B2629 B3558 B3559	-	-	14 ft	6 ft	2 ft	Not detected above RR SCO
		AOC-6-7											6	-		-	-				
		AOC-6-8											8	-		-	-				
		AOC-6-9											8	-		-	-				
		AOC-6-10											13	-		-	-				
		AOC-6-4		#c808054			-	-		-	-	To be investigated as part of #c808054 and #p808049									
		AOC-6-5		#p808049			-	-		-	-											
		AOC-6-6		#p808049			-	-		-	-											

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
7	Drywell Structures	AOC-7-1	-	EHS Building	AOC 7 (drywell structures) underlies the EHS building and the southwest portion of the NAF (Figure 1-4). While the presence of the EHS building slab reduces the potential for stormwater infiltration through this AOC, the feature has the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through previous vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers.	COPCs in impacted soil within or beneath the former drywells structures (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	1977-79 SHS Construction and Demolition Plans 2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011 2013 EMP Annual Reports 2014 VI Assessment 2018 Supplemental VI Assessment 2019 ISMP 2020 April Remedial Investigation Workplan Amendment 2021 April Soil and Groundwater Investigation Workplan - EHS Building Area (EoG) 2022 June Groundwater Monitoring Network Update 2023 August Groundwater Monitoring Network Update - Addendum #3 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor samples were collected near AOC-7-1 in Room 103 (SS-103) and Room 106 (SSHS-14-SS) and were observed below NYSDOH Matrix Guidelines for sub-slab vapor. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-7-1 on groundwater quality were evaluated using samples collected from monitoring wells located downgradient of the AOC. Monitoring wells installed downgradient of AOC-7-1 include MW-90S, MW-90I, MW-91S, and MW-91I. Groundwater samples collected as part of the RI investigation of AOC-7-1 were analyzed for PCBs, metals, SVOCs, and VOCs. Groundwater samples are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Groundwater analytical results are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs, metals, SVOCs, and VOCs were not observed above TOGS groundwater standards downgradient of AOC-7-1. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2025 and 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	NA	-	MW-90S MW-90I MW-91S MW-91I	SS-103, SSHS-14-SS	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-7-1 underlying the school building is unknown		
		AOC-7-2		NAF			1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. Monitoring wells installed adjacent to AOC-7 located on the western portion of the NAF/tennis courts include MW-66I and MW-66S located on Site #c808022, and MW-78I, and MW-78S located on Site #c808054. 1a. MW-66I and MW-66S were sampled in February and April 2021 and September 2023 for total and/or dissolved PCBs, metals, SVOC, and VOCs. For each sampling event, PCBs, metals, and VOCs were below TOGS. SVOC concentrations were detected above TOGS at MW-66I in April 2021 for DEHP (7.8 µg/L) 1b. MW-78I and MW-78S were sampled in September and November 2021 and April 2024 for total and/or dissolved PCBs, metals, SVOCs, and VOCs. For each sampling event, PCBs and VOCs were below TOGS. Metals concentrations were detected above TOGS in April 2024 at MW-78I for thallium (3.2 µg/L). SVOCs concentrations were detected above TOGS at MW-78I in September 2021 for benz(b)fluoranthene (0.084 µg/L), benzo(k)fluoranthene (0.082 µg/L), chrysene (0.093 µg/L), and indeno(1,2,3-cd)pyrene (0.073 µg/L). SVOCs concentrations were detected above TOGS at MW-78S in September 2021 for benz(a)anthracene (0.095 µg/L) benz(b)fluoranthene (0.15 µg/L), benzo(k)fluoranthene (0.17 µg/L), chrysene (0.16 µg/L), and indeno(1,2,3-cd)pyrene (0.15 µg/L). Samples collected in November 2021 and September 2023 for SVOCs were below TOGS for both MW-78I and MW-78S. 2. Monitoring wells installed adjacent to AOC-7 located beneath the High school building include MW-74I, MW-74S, MW-90I, and MW-90S located on Site #c808054. 2a. MW-74I and MW-74S were sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in September and October 2021 and April 2024. For each sampling event, PCBs, SVOCs, and VOCs were below TOGS. Total metals for iron was reported above TOGS in April 2024 at MW-74I only (390 µg/L). 2b. MW-91S and MW-91I were sampled for total and/or dissolved PCBs, metals, SVOCs, and VOCs in September and November 2021 and April 2024. PFAS was only sampled in September and November 2021. PCBs, SVOCs, VOCs, and PFAS were reported below TOGS for each sampling event. Metals were reported below TOGS for MW-91I. Total and dissolved metals for manganese was reported above TOGS (720-740 µg/L) in September 2021 for MW-91S, but below in November 2021 and April 2024. Perfluorooctanesulfonic acid (PFOS) was reported above TOGS for MW-91S (5.7 ng/L) in September 2021, but below in November 2021. 2c. Concentrations reported above TOGS for iron and manganese only are attributed to groundwater redox fluctuations and are not Site-related. DEHP is a common lab contaminant and is not a Site COPC. 3. Excavations for IRM #5A2 and ISMP were completed within a portion AOC-7 located on the western portion of the NAF; however, drywell structures were not identified. Conclusion: Nature and extent of potential groundwater contamination associated with AOC-7 on the western portion of the NAF and beneath the EHS building was investigated through sampling of downgradient monitoring wells located on Site #c808022 and #c808054. COPCs in groundwater samples collected on Site #c808022 and #c808054 have been defined based on the information above.		0	MW-66S, MW-66I	MW-65 MW-65R	-	-	4 ft	32 ft	Not detected above RR SCO	
8	Westinghouse Transformer Spill near Building 28A	-	-	FFC	AOC 8 (Former Westinghouse PCB release) is located within the southwestern portion of the FFC (Figure 1-4). Transformer oil was released to a storm drain, and then flowed into an oil water separator that discharged into a site culvert that drained into various tributaries in a wetland, and then into Coldbrook Creek. Investigation of the oil water separator and site culvert are being addressed under NYSDEC Site #808043. This suspected release area associated with this AOC has been characterized by the RI of the FFC and PDI activities for IRM #3 and through sampling and remedial actions for IRM #3. The former release has the potential to have resulted in COPCs to be present in underlying soil, and there is unknown potential for vertical COPC migration through the soil column to the water table (present approximately 14 to 16 feet bgs).	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater	P, M, S, V	1975 DEC Spill Report 1975 Chemung Co. HD Spill Report 2001 Sampling Report 2009 EMP 2018 FFC RI/PDI Work Plan 2019 Revised Remedial Investigation Work Plan 2019 IRM #1 CCR 2024 IRM #3 CCR 2026 FFC CCR	1. AOC-8 was evaluated through soil and groundwater sampling during IRM #1, IRM #3, and IRM #4, and FFC RI and PDI activities. 2. Soil samples were collected adjacent to AOC-8 during IRM #1, and PCB exceedances were detected above NYS hazardous material in several samples (IRM3-B333 between 6-10 ft bgs and B276 between 4-8 ft bgs). IRM #1 excavations were conducted down to 4 ft bgs, and these areas were to be addressed in future IRMs. IRM #3 excavated this area down to 16 ft bgs, removing the aforementioned PCB exceedances. One confirmation sample, SSHS-IRM3-PIPE10-C collected from 14-16 ft bgs had SVOC concentrations above PoG SCOs (Figure 6-4H). Pipe 10 was left in place due to technical impracticability for removal, and is likely unrelated to AOC-8. 3. Monitoring wells installed directly downgradient and/or cross gradient of AOC-8 on Site #c808022 include temporary wells B3557, B3558, B3559, B3560, B3561, B3562, B3563, B3563I, B3564, B3565, B3566, B3571, and MW-103S, MW-103I, and MW-39. 3a. The temporary wells were sampled in January 2021 for total and/or dissolved PCBs, metals, and VOCs. During this event, results for PCBs were above TOGS in nine of the temporary wells, ranging from 0.097 ug/L (B3571) to 32.85 ug/L (B3563I). PCBs were detected below TOGS in well B3559 and non-detect in wells B3557 and B3560. Metals were detected in all 12 wells, but none exceeded TOGS. VOCs were detected in wells B3563 and B3563I but did not exceed TOGS. 3b. MW-103S and MW-103I were sampled for total and/or dissolved PCBs, metals, SVOCs, VOCs, and 1,4-dioxane in September 2023 and April 2024. For each event, results for total PCBs exceeded TOGS. MW-103I had concentrations of 6 ug/L and 7.99 ug/L, and MW-103S had concentrations of 2 ug/L and 1.6 ug/L, respectively. Metals and SVOCs were detected but did not exceed TOGS for both wells on both sampling dates. VOCs and 1,4-dioxane were non-detect for both wells on both sampling dates. 3c. MW-39 was sampled for total and/or dissolved PCBs in March 2016 and sampled again for total and/or dissolved PCBs, metals, SVOCs, VOCs, and 1,4-dioxane in August 2018. Results for total and dissolved PCBs were detected below TOGS in 2016 and were non-detect in 2018. Metals exceeded TOGS in August 2018 for iron (620 mg/L). SVOCs were detected but did not exceed TOGS, and VOCs and 1,4-dioxane were not detected in 2018. 3d. Concentrations reported above TOGS for iron only are attributed to groundwater redox fluctuations and are not Site-related. Conclusion: Vertical and lateral extent of AOC-8 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Comprehensive excavations were completed as part of IRM #3 on the FFC with AOC-8 down to 16ft.	Soil - Yes Groundwater - Yes	16	-	MW-39 B3855S B3855I	-	-	8 ft	6 ft	10 ft	Not detected above RR SCO

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
9	Oil Storage and Handling, Oil House, Waste Oil Storage, and Quench Oil Reservoir	AOC-9-2	-	EHS Building	AOC 9 (former oil houses) are two discrete areas characterized as former oil houses, the larger of which is located on the eastern edge of the Site, the smaller in the southwest part of the Site (Figure 1-4). The area on the eastern edge of the Site has been characterized by the RI of the FFC and PDI activities for IRM #3. The smaller area in the southwest part of the Site entirely underlies the EHS building. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil. While the presence of the EHS building slab reduces the potential for stormwater infiltration through the former oil house which lies beneath the building footprint, both features have the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers in the former oil house beneath the building.	COPCs in impacted soil beneath the former structures (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	Sanborn Fire Insurance Maps 1967 Lancy Report and Figures 1977 Empire Soils Report 1994 Miller Pond Spill #94-16668 2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 DOH Health Consultation 2011 2013 EMP Annual Reports 2014 VI Assessment 2018 Supplemental VI Assessment 2018 FFC RI/PDI Work Plan 2018 FFC PDI Work Plan, Amendment #1 2019 FFC PDI Work Plan, Amendment #3 2019 ISMP 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor samples were collected in the vicinity of AOC-9-2 at SS-07-SS and SS-120 and were observed below NYSDOH Matrix Guidelines. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-9-2 on groundwater quality were evaluated using samples collected from monitoring wells located downgradient of the AOC. Monitoring wells installed downgradient of AOC-9-2 include MW-90S, MW-90I, MW-91S, and MW-91I. Groundwater samples collected as part of the RI investigation of AOC-9-2 were analyzed for PCBs, metals, SVOCs, and VOCs. Groundwater samples are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Groundwater analytical results are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs, metals, SVOCs, and VOCs were not observed above TOGS groundwater standards downgradient of AOC-9-2. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2025 and 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	NA	-	MW-90S MW-90I MW-91S MW-91I	SS-07-SS, SS-120	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-9-2 underlying the school building is unknown			
		AOC-9-1		FFC				Soil Groundwater			1. The portion of AOC-9 location on the eastern side of the FFC was evaluated through soil and groundwater sampling during implementation of IRM #5 and FFC RI and PDI activities. The smaller portion of AOC-9 located under the west side of the high school was evaluated through groundwater monitoring downgradient to determine any groundwater impacts. 2. FFC RI and PDI activities completed in the FFC in 2019 detected PCBs, metals, and SVOCs above PoG and RRSCOs within and surrounding AOC-9. Samples above SCOs for PCBs included B2053-4-6 (2.499 mg/kg). This exceedance is laterally delineated by B2028, B2192, B2015, and B2027 and vertically delineated by B2053, B2028, B2052, and B2192. Samples above SCOs for SVOCs included B2808-2-4 for indeno (1,2,3-cd)pyrene (1.1 mg/kg) and benzo(b)fluoranthene (1.2 mg/kg), and B2246-2-4 for total PAHs (409.3 mg/kg), benz(a)anthracene (29 mg/kg), benzo(a)pyrene (13 mg/kg), benzo(a)fluoranthene (35 mg/kg), benzo(k)fluoranthene (16 mg/kg), and chrysene (28 mg/kg). These exceedances were delineated laterally with B2952, B2810, and B2026 and delineated vertically with B2809 and B2027. Finally, samples above SCOs for metals included B2053-4-6 for chromium (III + IV) (41 mg/kg) and copper (340 mg/kg). This exceedance was delineated laterally with B2052, B2027, and B2245 and vertically with B2028 and B2053. All of these exceedances were excavated during excavations. 3. Monitoring wells installed cross- and down-gradient from AOC-9 in the FFC include MW-11S and MW-11D. MW-11D exceeded TOGS for benzo(k)fluoranthene (0.14 ug/L) and chrysene (0.12 ug/L) during April 2021 sampling. No other exceedances of TOGS have been detected. 3a. Monitoring wells installed down-gradient from the portion of AOC-9 under the west side of EHS include MW-90I, MW-90S, MW-74I, and MW-74S located on Site #c808054. There were no TOGS exceedances at either location for metals, SVOCs, VOCs, or PCBs. There were exceedances of TOGS for PFOS at MW-90I when sampled in October 2021 (5.6 ng/L) and April 2024 (4.1 ng/L). There were exceedances of TOGS for PFOS at MW-90S in September 2021 (10 ng/L), October 2021 (6.7 ng/L), and April 2024 (13 ng/L) as well as an exceedance of TOGS for PFOA in April 2024 (7.8 ng/L). Conclusion: Vertical and lateral extent of AOC-9 located on the FFC has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Comprehensive excavations were completed as part of IRM #3 on the FFC with AOC-9 down to 16ft. Lateral extent of AOC-9 beneath the EHS building was investigated through sampling of downgradient monitoring wells located on Site #c808054		16	-	MW-20 B3876	-	F-Wing	6 ft	Not detected above RR SCOs		
10A	Contaminated Subsurface Soils	AOC-10A-1	Metals at location B24	#c808054	AOC 10A (Subsurface Soils Exceeding SCOs) includes areas where Pre-RI results indicated metals in soil at B43, B42, B52, B24, B35, and SS-14. The former Site activities have resulted in the potential for COPCs to be present in underlying soil, and there is unknown potential for vertical COPC migration through the soil column to the water table (present approximately 14 to 16 feet bgs).	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to these areas. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of these areas toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater	M	1977 Empire Soils Report 2001 Sampling Report 2003 Health Consultation 2009 EMP 2015 Site Characterization Work Plan Addendum #1 2016 Site Characterization Work Plan Addendum #2 2016 Site Characterization Work Plan Addendum #3 2019 IRM #3 Work Plan 2019 Revised Remedial Investigation Work Plan 2020 IRM #5 Work Plan 2021 Soil and Groundwater Investigation Work Plan EHS Building Area 2023 Groundwater Mon. Network Update Add #1 2023 Groundwater Mon. Network Update Add. #2 2023 Groundwater Mon. Network Update Add. #3 2024 Groundwater Mon. Network Update Add. #4 2026 NAF CCR	1a. Pre-RI results identified at B43 detected metals concentrations above 20x TCLP criteria for lead from at 0.5-2.5 ft bgs 2,210 mg/kg located on the northern portion of the NAF. B43 was removed during excavation of IRM #5A2. Metals are delineated at this sample location by B3079 from 2.5-16 ft bgs (Figure 6-3A through Figure 6-3J) 1b. Pre-RI results identified at B42 detected metals concentrations above RRSCOs for arsenic, (32.1 mg/kg), copper (4,080 mg/kg) lead (783 mg/kg), and nickel (517 mg/kg) at 0.5-2.5 ft bgs located on the western central portion of the NAF. B42 was removed during excavation of IRM #5A2 to 4 ft bgs. Although RI and IRM samples were not collected within the exact location of B42, numerous samples were collected laterally to the north, south, east, and west delineating the nature and extent of B42 (Figure 6-3A through Figure 6-3J). 1c. Pre-RI results identified at B52 detected metals concentrations above RRSCOs for barium (1,449 mg/kg) at 0.5-2.5 ft bgs located in the central portion of the NAF, within the northern portion of AOC-12. B52 was removed during excavation of IRM #5A2 to 4 ft bgs Figure 6-3B. Although RI and IRM samples were not collected within the exact location of B52, numerous samples were collected laterally to the north (B5005, A-6-B277A, NAF-UT-S10), south (A5-B404), east (FIS-LAT1-S3, FIS-LAT1-S4, A6-B274A), and west (A6-B275, NAF-UT-S13, NAF-UT-S15, B5007, and A6-B271A) delineating the nature and extent of B52. 1d. Pre-RI results identified at B35 detected metals concentrations above RRSCOs for arsenic (16.2 mg/kg) from 2-4 ft bgs. This sample is being investigated under Site #c808054. 1e. Pre-RI results identified at B24 detected metals concentrations above RRSCOs for arsenic (56.2 mg/kg), barium (434 mg/kg), copper (2,300 mg/kg), lead (3,940 mg/kg), and nickel (761 mg/kg) from 1-4 ft bgs. This sample is being investigated under Site #c808054. 2a. Monitoring wells installed downgradient of B43 (MW-54 and MW-54R) did not have lead concentration detected above TOGS during the seasonal high and low monitoring period (Figure 5-5B-1 and Figure 5-5B-2). 2b. Monitoring well MW-55, installed within AOC-10 at B42 did not have detections above TOGS for arsenic, copper, lead, or nickel during the seasonal high and low monitoring period (Figure 5-5B-1 and Figure 5-5B-2). 2c. Monitoring wells installed adjacent (MW-56) or downgradient (MW-106 and MW-57R) of B52 did not have barium concentrations above TOGS during the seasonal high and low monitoring period (Figure 5-5B-1 and Figure 5-5B-2). 2d. Temporary monitoring wells (B4153S, B4153I, B4152S, B4152I) and permanent monitoring well (MW-82) installed downgradient and/or crossgradient of B35 did not have concentrations reported above TOGS for arsenic during the seasonal high and/or low monitoring period (Figure 5-5B-1 and Figure 5-5B-2). 2e. Temporary monitoring wells (B4150S and B4150I) and permanent monitoring well (MW-43) installed adjacent to B24 did not have concentrations reported above TOGS for arsenic, barium, copper, lead, or nickel during the seasonal high and/or low monitoring period (Figure 5-5B-1 and Figure 5-5B-2). Conclusion: Vertical and lateral extent of AOC-10A (B43, B42, and B52) located in the NAF has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Based on these observations, no further assessment is warranted to further define the nature and extent of impacts in soil and groundwater on Site #c808022. The investigation of soil and groundwater associated with B24 and B35 will be completed and discussed in the #c808054 RIR/AA. Groundwater monitoring will continue under the SMP for Site #c808022	Soil - Yes Groundwater - Yes	To be investigated as part of #c808054							
		AOC-10A-2	Metals at location B35	#c808054									4	MW-55	-	-	-	-	14 ft	-	-
		AOC-10A-3	Metals at location SS14	#c808054									5	-	MW-54 MW-54R	-	-	-	14 ft	-	-
		AOC-10A-4	Metals at B42	NAF									6	MW-56	MW-57R	-	-	-	14 ft	-	-
		AOC-10A-5	Metals at B43																		
		AOC-10A-6	Metals at B52																		

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
10B	Contaminated Subsurface Soils	AOC-10B -1	PCBs at location B3	FFC	AOC 10B (Subsurface Soils Exceeding SCOs) includes areas where Pre-RI results indicated PCBs in soil at B3, FB7 and B15; VOCs in soil at FB5; and SVOCs in soil at FB6. The former Site activities have resulted in the potential for COPCs to be present in underlying soil, and there is unknown potential for vertical COPC migration through the soil column to the water table (present approximately 14 to 16 feet bgs). The locations lie outside of the EHS building footprint, therefore, the potential for VOCs to migrate into indoor air is considered to be an incomplete pathway.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to these areas. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of these areas toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater	P,V,S	1977 Empire Soils Report 2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011 2013 EMP Annual Reports 2014 VI Assessment 2015 Site Characterization Work Plan Addendum #1 2016 Site Characterization Work Plan Addendum #2 2016 Site Characterization Work Plan Addendum #3 2018 Supplemental VI Assessment 2019 ISMP 2019 IRM #3 Work Plan 2019 Revised Remedial Investigation Work Plan 2020 IRM #5 Work Plan 2021 Soil and Groundwater Investigation Work Plan EHS Building Area 2023 Annual Heating Season Sampling 2023 Groundwater Mon. Network Update Add #1 2023 Groundwater Mon. Network Update Add. #2 2023 Groundwater Mon. Network Update Add. #3 2024 Groundwater Mon. Network Update Add. #4 2024-2025 PRRs 2026 NAF CCR	1. MW-58 is used as downgradient monitoring point for AOC-10B. There have been no detections above TOGS SCOs for PCBs, SVOCs or VOCs at MW-58. Iron and Manganese have been detected above TOGS SCOs in MW-58 but Iron and Manganese have not been associated with Site-related contamination (Tables 5-8 - 5-11). 2. Pre-RI results identified at B3, FB-7 and B15 have PCB detections above screening SCOs. FB-5 has VOC detections above RR SCOs and FB-6 has SVOC detections above RR SCOs. All samples have since been excavated during IRM #5 and IRM #5A2. 3. The nature and extent of possible COPC exceedances within AOC-10B has been investigated during RI sampling events and further investigated during IRM #5. No SVOC or VOC exceedances have been detected within AOC-10B locations (Figure 1-4). PCBs were detected above POG SCOs at B2194 (4-6 ft bgs). This boring was vertically delineated by following boring samples and laterally delineated by other borings and IRM #5 confirmation samples (Figures 6-4A-H). - FISR-S4 has a Metals Restricted Residential exceedance at 6-8 ft bgs remaining in place but is vertically delineated by FISR-S5 at 8-10 ft bgs and laterally delineated by FISR-S3 (Figure 6-4D and Figure 6-4E). Conclusion: Vertical and lateral extent of soil and groundwater in AOC-10B on Site #c808022 has been defined as discussed above. Metals exceedances found in groundwater have not been determined to be site related and soils have been lateral/vertically delineated by IRM #5A2 confirmation samples.	Soil - Yes Groundwater - Yes	12	B3874	MW-20	-	-	2 ft	-	-	-
		AOC-10B -2	PCBs at location FB7										10	-	MW-38 MW-102I MW-102S	-	-	6 ft	-	-	-
		AOC-10B -3	PCBs at location B15										15	-	MW-104I MW-104S	-	-	8 ft	-	-	-
		AOC-10B -4	VOCs at location FB5										9	-	MW-11S MW-11I B2544 B2544A B3092A B3978b	-	-	-	-	-	Not detected above RR SCO
		AOC-10B -5	SVOCs at location FB6										8	-	MW-44 MW-48 B3864I B3877I B3877S	-	-	-	-	2 ft	-
10C	Contaminated Subsurface Soils	AOC-10C -1	Petroleum Impacts	FFC	AOC 10C (Subsurface Soils Exceeding SCOs) includes an area where Pre-RI results indicated petroleum impacts in soil at the FFC. The former Site activities have resulted in the potential for COPCs to be present in underlying soil, and there is unknown potential for vertical COPC migration through the soil column to the water table (present approximately 14 to 16 feet bgs). A sheen was observed at the water table during groundwater sampling in previous investigations (Geosyntec, 2017). A review of groundwater data indicates the absence of COPCs above TOGS at locations where a sheen was observed (MW-10, MW-13, MW-33, MW-11S). However, the sheen indicates potential VOC, SVOC or DRO impacts to groundwater. The locations lie outside of the EHS building footprint, therefore, the potential for VOCs to migrate into indoor air is considered to be an incomplete pathway.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to these areas. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of these areas toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater	V,S,DRO		1. The following monitoring wells were used as downgradient monitoring points for AOC-10C but have been decommissioned: MW-39, MW-36, MW-40, MW-38, and MW-44. 2. MW-102I/S is used as a downgradient monitoring point for AOC-10C. - MW-102S has detections above TOGS SCOs during the most recent sampling event of Benz(a)anthracene, Benzo(b)fluoranthene, Benzo(k)fluoranthene, Chrysene, and Indeno (1,2,3-cd)pyrene but the distribution of SVOC exceedances has been spatially and temporally inconsistent across the Site and the SVOCs only sporadically exceeded TOGS standards at the listed monitoring wells. 3. The nature and extent of possible COPC exceedances within AOC-10C has been investigated during RI sampling events and further investigated during IRM #5. No VOC or TPH exceedances have been detected within any AOC-10C locations (Figure 1-4). SVOC Restricted Residential exceedances were detected in boring B2226 at depths of 6-8 and 8-10 ft bgs. - The 6-8 exceedance was excavated during IRM #5. - The 8-10 exceedance still remains in place but is vertically delineated by samples at 10-12 and 12-14. This sample is also laterally delineated by multiple other borings and IRM #5 confirmation samples (Figures 6-4A-H). - Elevated levels of PCBs and Metals have been detected within AOC-10C but all samples have been vertically and laterally delineated by borings or IRM #5 confirmation samples (Figures 6-4A-H). Conclusion: Vertical and lateral extent of AOC-10C located on Site #c808022 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. SVOCs and VOCs have been laterally and vertically defined in both the groundwater and soil with any detections above SCOs determined to be sporadic and inconsistent.	Soil - Yes Groundwater - Yes	7	B2542, B2542A	MW-44 MW-38 MW-102S MW-102I B2541 B3865A B3865I B3860I B3093 B3094	-	-	-	-	Not detected above RR SCOs
		AOC-10C -2											7	SSHS-B2543		-	-	-	-	Not detected above RR SCOs
		AOC-10C -3											12	-		-	-	-	-	Not detected above RR SCOs
		AOC-10C -4											12	-		-	-	-	-	Not detected above RR SCOs
		AOC-10C -5											11	-		-	-	-	-	Not detected above RR SCOs
10D	Contaminated Subsurface Soils	AOC-10D -1	Oil in shallow soils	EHS Building	AOC 10D (Subsurface Soils Exceeding SCOs) includes areas where previous investigation of the EHS building footprint (Empire, 1977) encountered oil-impacted soil. Two areas were characterized by NYSDEC as oil in shallow soils underlying the EHS Building and three areas were characterized as oil in deep soils, mostly underlying the EHS building. Previously collected SVOC data for B26 and B29-A characterize shallow soil east of the EHS Building. Historical operations have the potential to have resulted in release of COPCs to underlying soil. While the presence of the EHS building slab reduces the potential for stormwater infiltration through the areas that lie beneath the building footprint, there is unknown potential for vertical migration of COPCs through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers in the former oil house beneath the building.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature (areas outside of the EHS Building footprint only). 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors. 3. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	S, V, DRO		1. According to the Soil and Groundwater Investigation Work Plan EHS Building Area MW-10, MW-12, MW-32 and MW-33 are downgradient monitoring points for AOC-10D. - MW-10, MW-12, MW-32 and MW-33 had Bis(2-ethylhexyl) phthalate (DEHP) detected above TOGS SCOs but DEHP is a common cross-contaminant and is not a Site COPC. (Table 5-10) The Wisconsin Department of Natural Resources (WDNR) recognizes DEHP as a common contaminant due to its widespread use in plastics such as polyvinyl chloride (WDNR, 2002). At the Site, monitoring well casings are constructed of polyvinyl chloride and low-density polyethylene tubing is used for low-flow sample collection, both of which are potential sources of DEHP contamination. Historically, detections of DEHP at the Site have been infrequent and sporadic, with no discernible pattern across specific monitoring wells. - MW-12 had historic Freon-113 detections above TOGS SCOs but no detections during the more recent sampling events. No other detections above TOGS SCOs were detected in MW-10, MW-12, MW-32 and MW-33. (Table 5-11) 2. Other monitoring wells used to monitor AOC-10D are MW-87I, MW-88I/S, MW-103I/S, MW-104S/I, and MW-86I (Figure 2-3). - MW-104S had detections of Benz(a)anthracene and Chrysene above TOGS SCOs during the 2023 sampling event but did not have detections above TOGS SCOs during the 2024 sampling event. (Table 5-10) - MW-87I had Bis(2-ethylhexyl) phthalate (DEHP) detected above TOGS SCOs but DEHP is a common cross-contaminant and is not a Site COPC. (Table 5-10). DEHP is frequently detected as a cross-contaminant in groundwater sampling programs, originating from materials used in well construction, sample collection, and laboratory analysis. 3. Soil data for B26 and B29-A within AOC-10D is located east of the EHS building outside of the BCP Site Boundary. The nature and extent of soils within AOC-10D will be investigated as part of Site #c808054 4. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor samples SSHS-16-SS and SSHS-17-SS were collected within AOC-10D-1. Sub-slab soil vapor samples SSHS-01-SS, SSHS-02-SS, SSHS-03-SS, SSHS-08-SS and SS-133 were collected within AOC-10D-6. AOC-10D-5 overlaps AOC-10D-6. SSHS-01-SS was also collected within AOC-10D-5. VOCs were detected below NYSDOH Matrix Guidelines for the sample locations collected within AOC-10D-1 (SSHS-16-SS and SSHS-17-SS). TCE and cis-1,2-DCE were detected above the NYSDOH Matrix Guidelines at SSHS-02-SS, SSHS-03-SS, and SSHS-08-SS collected within AOC-10D-6. Based on the detections of TCE and cis-1,2-DCE, Unisys installed a sub-slab vapor mitigation system in the F-Wing in 2014 as discussed in Section 3.2.4. TCE and cis-1,2-DCE were detected in the SSD system effluent in November 2023 with concentrations of 339 µg/m3 and 66.6 µg/m3, respectively. TCE effluent concentrations decreased between June 2018 and July 2021, increased in December 2021, then slightly decreased in November 2023 as shown on Figure 6V-2. This indicates that TCE and cis-1,2-DCE are still present in sub-slab vapor below F-Wing and may potentially be associated with AOC-10D. 5. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). Conclusion: Soil Vapor and indoor air have been assessed and investigated as part of AOC-1. Vertical and lateral extent of AOC-10D located underneath the EHS building and east of the EHS building has been defined in groundwater as part of the RI for #c808022 as discussed above. Based on these observations, no further assessment is warranted to further define the nature and extent of impacts in groundwater on Site #c808022. The investigation of the soil will be completed and discussed in the #c808054 RIR/AA. Groundwater monitoring will continue under the SMP for Site #c808022	Soil - Yes Groundwater - Yes	NA	-	MW-90S MW-90I MW-91S MW-91I MW-71S MW-71I	SSHS-16-SS, SSHS-17-SS	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-10D underlying the school building is unknown		
		AOC-10D -2		EHS Building									NA	MW-12, MW-87I, MW-88I, MW-88S, SSHS-B26-A, SSHS-B29-A, SSHS-SB1	MW-9I MW-9S	-	Gymnasium				
		AOC-10D -3		EHS Building									NA	MW-88I, MW-88S		-	Gymnasium				
		AOC-10D -4		EHS Building/ FFC									16	MW-104S, MW-104I	MW-85I MW-13 MW-88S MW-88I	SSHS-164, SSHS-22-SS	Gymnasium	-	-	Not detected above RR SCO	
		AOC-10D -5		EHS Building									NA	-	MW-90S MW-90I MW-91S MW-91I MW-71S MW-71I	SSHS-01-SS	F-Wing	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-10D underlying the school building is unknown			
		AOC-10D -6		EHS Building									NA	-		SSHS-01-SS, SSHS-02-SS, SSHS-03-SS, SSHS-08-SS, SS-133	F-Wing				

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
11	VOC- and Petroleum Impacted Groundwater	-	-	Site-Wide	AOC 11 (Groundwater with measurable oil product or concentrations above TOGS) includes areas where pre-RI results indicated groundwater was impacted. A sheen, which may be an indication of petroleum impact, had been observed at MW-11S (FFC). Pre-RI results indicated VOC-impacted groundwater at MW-8 and MW-30 (East of Gym; downgradient of the Revised BCP Site); petroleum-impacted groundwater at MW-8, MW-10, MW-32, MW-34 and MW-41 (East of Gym; downgradient of the Revised BCP Site); and PCB impacts at MW-15S (FFC) and MW-8 and MW-41 (East of Gym; downgradient of the Revised BCP Site). The nature and extent of the impacts listed above have been fully characterized. The potential for VOCs in groundwater to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). Shallow groundwater is not known to be used at the Site or immediately downgradient, therefore, exposure to impacted groundwater by ingestion or other use is considered an incomplete pathway.	COPCs in impacted groundwater can migrate toward downgradient receptors.	1. On-Site Subsurface Construction Workers: People can come into contact, in the highly unlikely event given the 14 to 16-ft depth to groundwater, if they complete ground-intrusive work at the Site that extends below the depth of the water table. 2. There are no domestic water supply wells at or immediately downgradient of the Site; people can come into contact if private wells are installed on the property in the future. 3. Soil vapor: VOCs in groundwater can volatize to soil vapor.	Groundwater Soil Vapor Indoor Air	P, M, S, V	1994 Miller Pond Spill #94-16668 1998 Spills EA Report 2001 Sampling Report 2003 Health Consultation 2004 IIWA GW Investigation 2008 Spills GW Sampling 2010 DOH Health Consultation 2011 2013 EMP Annual Reports 2014 VI Assessment 2018 Supplemental VI Assessment 2018 July FFC RI/PDI Activities Work Plan 2018 August - FFC RI/PDI Work Plan - Am #1 2018 October - FFC RI/PDI Work Plan - Am #2 2019 ISMP 2019 Revised Remedial Investigation Workplan 2020 Soil and Groundwater Investigation Workplan 2021 Soil and Groundwater Investigation Workplan, FFC - Slide Rail 2021 Soil and Groundwater Investigation Workplan EHS Building Area 2021 Soil and Groundwater Investigation Workplan Add., NAF 2022 Groundwater Monitoring Network Update 2023 Annual Heating Season Sampling 2023 Pre-Construction Monitoring Program Work Plan for Proposed Infiltration Gallery 2023 Add. #2 to Soil and Groundwater Investigation WP - EHS Building Area 2023 Groundwater Mon. Network Update Add #1 2023 Groundwater Mon. Network Update Add. #2 2023 Groundwater Mon. Network Update Add. #3 2024 Groundwater Mon. Network Update Add. #4 2024-2025 PRRs	1. The potential for VI has been assessed beneath the EHS building, and currently not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). See AOC-1 for additional information on soil vapor and indoor air investigations. 2. In the FFC, Potential impacts of AOC-11 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of the AOC. Monitoring wells installed within AOC-11 on the FFC area include MW-11S, MW-11I, MW-15S, MW-15D, MW-102I, MW-102S. Monitoring wells installed downgradient of AOC-11 on the FFC area include MW-44, MW-38, MW-13, MW-85I, and MW-84S. Temporary monitoring wells installed within AOC-11 on the FFC include B2544 (analyzed for PCBs, metals, SVOCs, and VOCs), B2544A (analyzed for VOCs), B3857 (analyzed for PCBs, metals, SVOCs, and VOCs), B2090A (analyzed for metals, and VOCs), B3092A (analyzed for VOCs), and B2819 (analyzed for VOCs). Temporary monitoring wells B3859S (analyzed for PCBs), B3859I (analyzed for PCBs), B3861S (analyzed for PCBs), B3861I (analyzed for PCBs), B2752 (analyzed for PCBs, metals, SVOCs, and VOCs), B4007 (analyzed for PCBs) were installed downgradient of the FFC. PCBs and metals were not observed above TOGS groundwater standards at any of these locations. VOCs were detected above the TOGS groundwater standard for TCE within AOC-11 at MW-11I and temporary monitoring wells B2544, B2544A, B2819, B2090A, and B2978b. The maximum concentration of TCE was observed at B2819 at 25 µg/L in May 2019. The downgradient extent of this TOGS groundwater exceedance for TCE is defined off-Site at MW-107S and MW-107I. TCE impacted soils were encountered during the FFC IRM and ISMP excavations within the vicinity of AOC-10B-4 and were the source for the TCE concentrations in groundwater at this area. These TCE-impacted soils were excavated as part of the FFC IRM. SVOCS were detected above the TOGS groundwater at MW-11D and MW-102S. MW-11D is screened below the silty clay aquitard. SVOCs were detected above TOGS groundwater standards at MW-102S in April 2024 but were not previously detected above TOGS groundwater standards in September 2023. As further discussed in Section 6.2.3, the distribution of SVOC exceedances across the Site has been sporadic, non-repeatable, and spatially inconsistent; therefore, additional investigation is not warranted. A sheen, which may be an indication of petroleum impact, had previously been observed at MW-11S FFC. No measured layer of NAPL was observed at MW-11S during gauging events. Total Petroleum Hydrocarbons – Diesel range organics (TPH-DRO) was detected at a concentration of 13 mg/L at MW-11S in May 2019. 3.Potential impacts to groundwater at AOC-11 within the EHS Building area have been assessed through groundwater data collected downgradient of the AOC, outside of the EHS building footprint. Groundwater samples are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Monitoring wells downgradient outside of the EHS building footprint used to assess potential groundwater impacts from AOC-11 include MW-47, MW-47I, MW-12, MW-71S, MW-71I and temporary monitoring wells B93 (analyzed for VOCs), B94 (analyzed for VOCs), B95 (analyzed for VOCs), B96 (analyzed for VOCs), and B29-A (analyzed for PCBs, SVOCs, and VOCs). PCBs and metals were reported below TOGS groundwater standards at these monitoring wells. VOCs were reported above TOGS groundwater standards at MW-47I. This portion of AOC-11 overlaps with AOC-13 (former metal cleaning, vapor degreaser and solvent still areas). MW-47I exceeded the TOGS groundwater standard for benzene (1.5 µg/L compared to TOGS of 1 µg/L) in September 2021. Benzene was observed as non-detect at MW-47I in samples collected in October 2021 and April 2024. TCE was observed above the TOGS groundwater standard (5 µg/L) at B92 (5.6 µg/L) and B94 (8.9 µg/L) in August 2014. TCE was detected below TOGS groundwater standards at MW-47 in September 2016 (3.9 µg/L) and non-detect in February 2021 and July 2021. TCE was non-detect at MW-47I in September 2021, October 2021, and April 2024. Therefore, further assessment is not warranted. VOCS were reported downgradient of AOC-11 at MW-12. MW-12 exceeded the TOGS groundwater standard for cis-1,2 DCE (one exceedance, 9 µg/L), Freon 113 (maximum result 160 µg/L), and TCE (two exceedances, 9J and 6.8 µg/L) in samples collected between May 2000 and July 2007. These VOC compounds all were observed as non-detect in more recent samplings in February 2021 and July 2021. Therefore, further assessment is not warranted. 4. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor samples SSHS-23-SS, SSHS-04-SS, and SSHS-05-SS were collected within proximity to AOC-11 underneath F-wing. VOCs were reported below NYSDOH Matrix Guidelines at SSHS-23-SS. VOCs were reported above NYSDOH Matrix Guidelines at SSHS-04-SS, and SSHS-05-SS. This portion of AOC-11 overlaps with AOC-13 (former metal cleaning, vapor degreaser and solvent still areas). TCE was reported above NYSDOH Matrix Guidelines at SSHS-04-SS (390 µg/m3) and SSHS-05-SS (2,100 µg/m3). Based on the detections of TCE and cis-1,2-DCE, Unisys installed a sub-slab vapor mitigation system in the F-Wing in 2014 as discussed in Section 3.2.4. TCE detected in the SSD system effluent in November 2023 with concentrations of 339 µg/m3. TCE effluent concentrations decreased between June 2018 and July 2021, increased in December 2021, then slightly decreased in November 2023 as shown on Figure 6V-2. This indicates that TCE is still present in sub-slab vapor below F-Wing and may potentially be associated with AOC-11. TCA and TCE were detected in sub-slab below the east side of the Gymnasium (SV-GM EAST) in 2009 near AOC-11 at concentrations of 23,000 µg/m3 and 28 µg/m3, respectively (Appendix B). ECSD installed a sub-slab vapor mitigation system in the Gymnasium in 2010. Sub-slab vapor below the Gymnasium was not sampled in 2014 and 2018 due to the presence of the vapor mitigation system. Sampling of the Gymnasium SSD effluent detected 19 µg/m3 of TCE in June 2018 and 3.4 µg/m3 of TCE in November 2023. TCA was not detected above the laboratory reporting limit. This indicates that TCE is still present in sub-slab vapor below the Gymnasium at decreasing concentrations and may potentially be associated with AOC-11. 5. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). Conclusion: Nature and extent of PCBs, metals, SVOCs, and VOCs in groundwater have been defined at and downgradient of AOC-11 using a comprehensive data collection and evaluation effort including COPC concentration and water level data collected under low and high water table conditions from the groundwater monitoring well network installed for the Revised BCP Site and further supported by monitoring wells installed for the adjoining site #c808054.	Groundwater - Yes	NA	FFC: MW-11S, MW-11I, MW-15S, MW-15D, MW-102I, MW-102S, B2544, B2544A, B3857, B2090A, B3092A, B2819	MW-84S MW-85I MW-13 MW-38 MW-44 B3859S B3859I B3861S B3861I B2752 B4007 MW-47 MW-47I MW-12 MW-71S MW-71I B93 B94 B95 B96 B29-A	SSHS-23-SS, SSHS-04-SS, SSHS-05-SS, SV-GYM EAST	F-Wing, Gymnasium, K-Wing	-	-	-	-
11A	Measured Oil Product at MW-8, MW-10, and MW-32	-	-	#c808054								To be investigated as part of #c808054									
11B	PCBs at MW-41	-	-	#c808054								To be investigated as part of #c808054									

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
12	Plating, Heat Treatment and Tumbling Areas	AOC-12-3	Plating, Heat Treatment, Tumbling Area	EHS Building	AOC 12 (Former plating, heat treatment and tumbling areas) is located on the southwestern side of the Site and at former Buildings 49 (NAF) and 67E (FFC) on the eastern side of the Site (Figure 1-3 and Figure 1-4). The portion of the AOC in the southwestern side of the Site partly underlies the EHS building on Site #c808054 and is overlapped by AOC 16 and AOC 17 (Figure 1-4). While the presence of the EHS building slab reduces the potential for stormwater infiltration through the area which lie beneath the building footprint, there is unknown potential for vertical migration of COPCs through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers in the portion of the AOC beneath the building.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011-2013 ACRs 2014 VI Assessment 2018 Supplemental VI Assessment 2018 July FFC RI/PDI Activities Work Plan 2018 August - FFC RI/PDI Work Plan - Amendment #1 2018 October - FFC RI/PDI Work Plan - Amendment #2 2019 March Site Characterization Report 2019 May FFC PDI Activities Work Plan - Amendment #3 2019 August FFC PDI Activities Work Plan - Amendment #4 2020 Interim Remedial Measure #5 Work Plan 2023 Annual Heating Season Sampling 2024-2025 PRRs 2026 NAF CCR 2026 FFC CCR	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 and screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor samples were collected within AOC-12-3 at SS-122, SS-06-SS, SS-120 and SS-07-SS and were observed below NYSDOH Matrix Guidelines. See AOC-1 (Section 5.2.1 and 5.2.2) for additional information on indoor air and soil vapor investigations. The current nature and extent of VOCs in sub-slab vapor and indoor air is discussed in Section 6.1. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-12-3 on groundwater quality were evaluated using samples collected from monitoring wells located downgradient of the AOC. Monitoring wells MW-90S, MW-90I, MW-91S, and MW-91I were installed downgradient of AOC-12-3 and analyzed for PCBs, metals, SVOCs, and VOCs. Temporary monitoring well B3203A was installed within AOC-12-3 and was analyzed for PCBs, metals, SVOCs and VOCs. Temporary monitoring wells B97 and B3203B were installed within AOC-12-3 and analyzed for VOCs. Groundwater samples are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Groundwater analytical results are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs, metals, SVOCs, and VOCs were not observed above TOGS groundwater standards within or downgradient of AOC-12-3. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2020 and the 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	NA	SSHS-B3203A, SSHS-B3203B, SSHS-B97	MW-90I MW-90S MW-91I MW-91S	SS-122, SSHS-06-SS, SSHS-07-SS, SS-12	F-Wing	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-12-3 underlying the school building is unknown			
		AOC-12-1	Building 49	NAF			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature (areas outside of the EHS Building footprint only). 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. Two soil borings, B3109 and B3336, were installed within AOC-12-1 to a maximum depth of 14 ft bgs. COPCs, including PCBs, metals, SVOCs, and VOCs, were not identified within AOC-12-1 above Restricted Residential SCOs. 2. Potential impacts of AOC-12-1 on groundwater quality were evaluated using samples collected from monitoring wells located downgradient of the AOC. Monitoring wells MW-100S and MW-100I are located downgradient of AOC-12-1. Groundwater samples collected as part of the RI investigation of AOC-12-1 were analyzed for PCBs, metals, SVOCs, and VOCs. Results are shown compared to TOGS groundwater standards on Figures 5-5A-1 through 5-5D-2. Groundwater analytical results including those from previous investigations are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs, metals, SVOCs, and VOCs were not reported above TOGS groundwater standards downgradient of AOC-12-1. Conclusion: Vertical and lateral extent of AOC-12-1 located on the NAF has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Based on these observations, no further assessment is warranted to further define the nature and extent of impacts in groundwater and soil on Site #c808022. Off-Site delineation will be completed and discussed in the #c808054 RIR/AA. Groundwater monitoring will continue under the SMP for Site #c808022		8	-	MW-100S MW-100I	-	-	Not detected above RR SCO			
		AOC-12-2	Building 67 E	FFC			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature (areas outside of the EHS Building footprint only). 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. A total of 11 soil borings were installed within AOC-12-2 to a maximum depth of 14 ft bgs across multiple soil sampling events (Section 2.2). Within the FFC, soil borings were collected on a 60x60 ft grid to the water table and subsequent step out samples collected on approximately 30 ft spacing to further define the nature and extent of COPCs observed above Restricted Residential SCOs. COPCs, including PCBs, metals, and SVOCs, were identified within AOC-12-2 above Restricted Residential SCOs. VOCs were not identified within AOC-12-2 above Restricted Residential SCOs. PCBs above the Restricted Residential SCO were observed up to a depth of 6 ft bgs. Metals above the Restricted Residential SCOs, including barium, chromium, and copper, were observed up to a depth of 12 ft bgs. SVOCs above the Restricted Residential SCOs, including benzo(b)fluoranthene and indeno (1,2,3-cd)pyrene, were observed up to a depth of 2 ft bgs. 2. Potential impacts of AOC-12-2 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of the AOC. Temporary monitoring well B2221 was installed within AOC-12-2 and analyzed for metals. Temporary monitoring wells B3877S and B3877I were installed downgradient of AOC-12-2 and analyzed for PCBs, metals, and SVOCs. Monitoring well MW-44 is located downgradient of AOC-12-2 and was analyzed for PCBs, SVOCs, and VOCs. Results are shown compared to TOGS groundwater standards on Figures 5-8A-1 through 5-8D-2. Groundwater analytical results including those from previous investigations are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs and SVOCs were not reported above TOGS groundwater standards within or downgradient of AOC-12-2. Metals were reported above the TOGS groundwater standard for chromium (210 µg/L) at B2221 in May 2019. Chromium was not reported above TOGS groundwater standards downgradient of temporary monitoring well B2221 at B3877I, B3877S, and MW-44. TCE was reported above the TOGS groundwater standard for (8.1 µg/L) at B3877S sample in April 2021. TCE was reported below the TOGS groundwater standard downgradient of B3877S at MW-20 in July 2021, located off-Site. As temporary monitoring wells are installed for short-term investigation purposes and are typically sampled shortly after installation, the resulting data may reflect localized disturbance, incomplete equilibration, and short-term turbidity-related influences that can bias reported groundwater concentrations. In contrast, permanent monitoring wells provide a more reliable measure of ambient groundwater quality and dissolved-phase conditions within the aquifer as they are designed, developed, and sampled to better represent stable formation water over time. Accordingly, the absence of TCE exceedances in the downgradient permanent monitoring well is considered more representative of actual aquifer conditions than the isolated exceedances reported in temporary monitoring well samples. Therefore, additional investigation is not warranted. Conclusion: Vertical and lateral extent of AOC-12-2 located on the FFC has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Based on these observations, no further assessment is warranted to further define the nature and extent of impacts in groundwater and soil on Site #c808022. Off-Site delineation will be completed and discussed in the #c808054 RIR/AA. Groundwater monitoring will continue under the SMP for Site #c808022		13	SSHS-B2221	MW-44 B3877I B3877S	-	-	6 ft	12 ft	2 ft	Not detected above RR SCO

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
13	Metals Cleaning, Vapor Degreaser and Solvent Still	-	-	EHS Building	AOC 13 (Former location of metal cleaning, vapor degreaser and solvent still areas) partly underlies the EHS building but mostly lies outside to the north of the building (Figure 1-4), and is overlapped by AOC 11, AOC 16 and AOC 17. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil. While the presence of the EHS building slab reduces the potential for stormwater infiltration through the area which lie beneath the building footprint, there is unknown potential for vertical migration of COPCs through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers in the portion of the AOC beneath the building.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature (areas outside of the EHS Building footprint only). 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors. 3. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011-2013 ACRs 2014 VI Assessment 2018 Supplemental VI Assessment 2016 Site Characterization Work Plan Addendum #3 2019 ISMP 2019 Revised Remedial Investigation Work Plan 2019 Remedial Investigation Work Plan update 2022 RIWP Groundwater Monitoring Network Update Plan 2023 Annual Heating Season Sampling 2024 Groundwater Monitoring Network - Addendum #4 2024-2025 PRRs	1. AOC 13 is overlapped by AOCs 16 and 17, and the extent of COPCs is addressed by sampling of those AOCs. 2. B574 was proposed within AOC-13 and sampled as part of the Site Characterization Work Plan Addendum #3. - No exceedances detected. 3. MW-47 was proposed and installed as a downgradient monitoring point for AOC-13 as part of Site Characterization Work Plan Addendum #3. Iron (500 ug/L) was detected above TOGS SCOs during the February 2021 sampling event, but was not detected above TOGS SCOs before or since. 4. MW-47I was installed in August of 2021 and sampled in September 2021. Multiple exceedances have been detected over the course of sampling events taking place between 2021 - 2024. This includes Metals, SVOCs and VOC exceedances according to the Groundwater Monitoring Network - Addendum #4. 5.Samples B3158 and B3159 were sampled in Jan 2020 as part of the Remedial Investigation Work Plan update within AOC-13 (Figure 1-4) while numerous samples were taken within AOCs 16 and 17 laterally delineating AOC-13. - Both samples are vertically delineated. 6. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor sample SSHS-04-SS and SSHS-05-SS were within AOC-13. TCE was reported above NYSDOH Matrix Guidelines at SSHS-04-SS (390 µg/m3) and SSHS-05-SS (2,100 µg/m3). Based on the detections of TCE, Unisys installed a sub-slab vapor mitigation system in the F-Wing in 2014 as discussed in Section 3.2.4. TCE was detected in the SSD system effluent for the F-Wing in November 2023 with concentrations of 339 µg/m3 (Table 6-1C). TCE effluent concentrations decreased between June 2018 and July 2021, increased in December 2021, then slightly decreased in November 2023 as shown on Figure 6V-2. This indicates that TCE is still present in sub-slab vapor below F-Wing and may potentially be associated with AOC-13. 7. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). Conclusion: Soil Vapor and indoor air have been assessed and investigated as part of AOC-1. Vertical and lateral extent of AOC-13 located in the Teachers Parking lot has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Possible AOC-13 contamination in soil and groundwater is laterally delineated by sampling completed for AOC-16 and AOC-17 discussed below due to the AOCs overlapping. All borings taken within the AOC-13 area (B3158 and B3159) are vertically delineated by samples reported below Restricted Residential SCOs. Groundwater has been investigated though sampling at MW-47/MW-47I downgradient of AOC-13.	Soil - Yes Groundwater - Yes	NA	B93, B95	MW-47 MW-47I B92 B94	SSHS-04-SS, SSHS-05-SS	F-Wing	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-13 underlying the school building is unknown			
14	Power Washer, Rust Prevention Dip Operation	AOC-14-2	Sludge Settling Pond	#c808054	AOC-14 is former power washer, rust prevention and dip operations areas and includes four discrete areas. AOC-14-3 is located in the Tennis Courts and Main Parking Lot area (Figure 1-4). AOC-14-3 spatially overlaps with AOC-16-3. AOC-14-2 and AOC-14-4 are located within the New BCP Site and will be discussed in the #c808054 RI/AA. AOC-14-1 is located to the south of the Site and will be addressed in the SC of the Former Scott Technologies Site (NYSDEC #p808049). Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil, and there is unknown potential for vertical migration through the soil column to the water table.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in groundwater within or adjacent to these areas. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of these areas toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Groundwater	S,M	2001 Sampling Report 2003 Health Consultation 2009 EMP 2017 Site Characterization Report 2019 Site Characterization Report 2023 Groundwater Mon. Network Update Add #1 2023 Groundwater Mon. Network Update Add. #2 2023 Groundwater Mon. Network Update Add. #3 2024 Groundwater Mon. Network Update Add. #4 2024 IRM #3 CCR 2026 FFC CCR	1. Based on the findings presented in the Site Characterization report, investigations completed in the main parking lot associated with AOC-14 were fully addressed and additional investigation was not required. AOC-14 in the main teacher parking lot was sampled for PCBs, metals, SVOCs and VOCs at B90 from 0-16 ft bgs. No detections above RRSCOs were reported. Boring locations completed adjacent to AOC-14 in the student parking lot include B81, B84, B87 for PCBs, metals, SVCOs, and VOCs from 0-14 ft bgs. Detections above RRSCOs for PCBs, metals, and VOCs were not identified. PAHs were detected above RRSCOs from 0-2 ft bgs at B81 for benz(a)anthracene (1.4 mg/kg), benzo(a)pyrene (1.9 mg/kg) benzo(b)fluoranthene (2.3 mg/kg), dibenz(a,h)anthracene (0.45 mg/kg), and indeno(1,2,3-cd)pyrene (0.45 mg/kg). B84 also exceeded indeno(1,2,3-cd)pyrene (0.64 mg/kg) from 0-2 ft bgs. PAHs in shallow soil samples are likely attributable to asphalt pavement rather than historical operations associated with AOC-14 in the student parking lot. 2. Excavations associated with IRM #3 were completed within the majority of AOC-14 (with the exception of the very northwest corner) located in the student parking lot from 0-6 ft bgs. IRM3-Pipe20 was a sidewall collected within AOC-14 from 0-2 ft bgs which exceeded PAHs for benz(a)anthracene (5.7 mg/kg), benzo(a)pyrene (4.7 mg/kg), benzo(b)fluoranthene (6.6 mg/kg), chrysene (6.5 mg/kg), dibenz(a,h)anthracene (1 mg/kg), and indeno(1,2,3-cd)pyrene (3.1 mg/kg) and RRSCOs or 20x TCLP for metals including arsenic (47 mg/kg), chromium (170 mg/kg), copper (840 mg/kg), and lead (630 mg/kg). Pipe20 was left in place due to technical impracticability for removal as reported in the IRM #3 CCR. As stated above, PAHs in shallow soil samples are likely attributable to asphalt pavement rather than historical operations associated with AOC-14 in the student parking lot. Pipe 20 is laterally delineated from 0-2 ft bgs for metals by IRM3-S010, IRM3-S008, IRM3-S009, IRM3-S059, and B84. Pipe20 is vertically delineated by IRM3-S032B, IRM3-S031, IRM3-S067F, and IRM3-S032A (Figure 6-5A and Figure 6-5B) 3. SVOCs were not reported above TOGS for low and seasonal highs (Figure 5-11C-1 and Figure 5-11C-2) in any monitoring wells surrounding the AOC-14 areas located in the student parking lot (MW-92I, MW-92S, MW-103I, and MW-103S) and the teacher parking lot (MW-75I, MW-75S, MW-93I, and MW-93S). Metals were not reported above TOGS for COPCs identified in Soil (discussed above) in low and high season sampling (Figure 5-11B-1 and Figure 5-11B-2) in the student parking lot (MW-92I, MW-92S, MW-103I, and MW-103S) and the teacher parking lot (MW-75I, MW-75S, MW-93I, and MW-93S). Conclusion: Vertical and lateral extent of metals and SVOCs associated with AOC-14 located in the student and teacher parking lot has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. PAHs that remain in shallow soil samples are attributable to asphalt pavement rather than historical operations associated with AOC-14 in the student parking lot.	To be investigated as part of #c808054								
		AOC-14-3		TC & MP Lot								Soil - Yes Groundwater - Yes	4	MW-92S, MW-92I	MW-39	-	-	-	Not detected above RR SCO	2 ft	-
		AOC-14-4	Paint Shop	#c808054								To be investigated as part of #c808054									
		AOC-14-1	Sludge Settling Pond	#p808049								To be investigated as part of #c808054									

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
15	Wire Pickling Area	AOC-15-2	-	FFC/EHS Building	AOC 15 (Wire Pickling Area) includes two discrete former wire pickling areas, one of which is off Site to the south, and not part of the RI (Figure 1-4). The on-Site part of AOC 15 partly underlies the EHS building but extends outside of the EHS building to the east and west. The area to the west of EHS is located off-site in Site #c808054. Soil has been sampled at seven (7) locations in the eastern area previously for PCBs and no further sampling for PCBs is needed. Groundwater has been sampled at MW-13 located at this AOC, and there have been no COPC impacts at this well. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil. While the presence of the EHS building slab reduces the potential for stormwater infiltration through the area which lie beneath the building footprint, there is unknown potential for vertical migration of COPCs through the soil column to the water table (present approximately 14 to 16 feet bgs). The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers in the portion of the AOC beneath the building.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	S,M	2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011-2013 ACRs 2014 VI Assessment 2018 Supplemental VI Assessment 2019 ISMP 2021 Soil and Groundwater Investigation WP, FFC - Slide Rail 2021 Soil and Groundwater Investigation WP - EHS Building Area 2023 Annual Heating Season Sampling 2024-2025 PRRs	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab soil vapor sample SSHS-23-SS and SS-164 were within AOC-15-2. There were no exceedances at either sampling location. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-15-2 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of the AOC. Monitoring wells MW-13 and MW-85I were installed within AOC-15-2 within the portion of the AOC that extends to the east of the EHS Building onto the New BCP Site. MW-104I and MW-104S were installed adjacent to AOC-15-2 to the west of the EHS Building. MW-33 was installed off-Site and downgradient of the AOC. Groundwater samples are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Groundwater analytical results are presented in Tables 5-9 and 5-10 for metals and SVOCs, respectively, and are compared to TOGS groundwater standards. Metals were not detected above TOGS groundwater standards at these locations. SVOCs, including benz(a)anthracene and chrysene, were detected above TOGS groundwater standards at MW-104S in September 2023. SVOCs were detected below TOGS groundwater standards at MW-104S in April 2024. As further discussed in Section 6.2.3, the distribution of SVOC exceedances across the Site has been sporadic, non-repeatable, and spatially inconsistent; therefore, additional investigation is not warranted. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2020 and the 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	12	MW-13, MW-85I, MW-104I, MW-104S	MW-33	SS-164, SSHS-23-SS	-	-	4 ft	Not detected above RR SCO	-
		AOC-15-1	-	#p808049			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature (areas outside of the EHS Building footprint only). 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. AOC-15 was evaluated through soil and groundwater investigations in the East of Gym area (offsite, discussed in #c808054) and the West of A-Wing area. AOC-15 was not investigated below the EHS building. It was determined that the physical constraints of the EHS building made drilling operations necessary to conduct additional soil investigations beneath the building impractical and unsafe. The ceiling height did not provide the vertical clearance required for drill rig masts. Additionally, indoor air flow posed ventilation challenges with the drill rig exhaust, and the confined space amplified the sound level beyond the acceptable occupational safety threshold. 2. Soil exceedances in AOC-15 in the West of A-wing area include exceedances of SCOs for PCBs at 2-4 ft bgs for B339 (9.17 mg/kg) and B467 (3765 mg/kg), which were excavated during FFC activities (IRM #3, IRM #4), PCB exceedances at 4-6 ft bgs for B467 (308.3 mg/kg), B477 (94.1 mg/kg), and B622 (22.78 mg/kg) which were delineated laterally by B744, B2764, B246, and B255, and delineated vertically by B467, B622, and B743. Finally, there were exceedances of TSCA at B477-6-8 (135.7 mg/kg, excavated) and RRSCO at B622-8-10 (6.92 mg/kg, left in place). These exceedances were delineated laterally by B654, B337, and B623 and vertically by B623, B622, and B743. There were no soil exceedances for metals, SVOCs, or VOCs in soil in the west of A-Wing area of AOC-15. 3. Groundwater monitoring wells located within or downgradient to AOC-15 include MW-13, MW-104I, MW-104S, MW-85I (on site #c808022), MW-88I and MW-88S (on site #808054). Exceedances for SVOCs were detected at MW-104S during September 2023 sampling event (benz(a)anthracene, 0.076 ug/L and chrysene, 0.097 ug/L). The distribution of SVOC exceedances has been spatially and temporally inconsistent across the Site. Additionally, MW-13 had an exceedance for PFOS (3.5 ng/L) during the February 2021 sampling event. PFAS exceedances are present on the upgradient western side of the Revised BCP Site and indicate an off-site source of PFAS impacts. No other groundwater exceedances were detected for any COPCs. 3a. There were several exceedances for temporary wells installed adjacent (cross gradient to the north) of AOC-15 in the west of A-wing area. The temporary wells were sampled in January 2021 for total and/or dissolved PCBs, metals, and VOCs. During this event, results for PCBs were above TOGS in nine of the temporary wells, ranging from 0.097 ug/L (B3571) to 32.85 ug/L (B3563I). PCBs were detected below TOGS in well B3559 and non-detect in wells B3557 and B3560. Metals were detected in all 12 wells, but none exceeded TOGS. VOCs were detected in wells B3563 and B3563I but did not exceed TOGS. Conclusion: Vertical and lateral extent of AOC-15 located on Site #c808022 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Lateral extent of AOC-15 located beneath the EHS building was investigated through sampling of downgradient monitoring wells located on Site #c808054. The remaining section of AOC-15 located in the East of Gym area is being investigated under Site #c808054.	To be investigated as part of #p808049							

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
16, South	Machine Shop Area	AOC-16-1	-	EHS Building	AOC 16 (Former machine shop areas) includes four discrete areas on Site. The northern portion of AOC 16 is coincident with and slightly larger than a possible plating area portion of AOC 17. While the location of former machine shop and plating areas is known based on historic records, there are no records regarding the decommissioning and demolition of the former buildings at this location. Two discrete areas of AOC 16 are at the FFC. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil. While no specific potential release has been identified, there may be a potential for a past release to surface soil due to former industrial land use, and there is unknown potential for vertical migration through the soil column to the water table. Figure 1-4.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air	P, M, S, V	2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011-2013 ACRs 2014 VI Assessment 2015 Site Characterization Work Plan Addendum #1 2016 Site Characterization Work Plan Addendum #2 2018 Supplemental VI Assessment 2016 Site Characterization Work Plan Addendum #3 2019 Revised Remedial Investigation Workplan 2019 ISMP 2020 Site Wide RI Work Plan Amendment #1 2020 IRM #5 Revised Workplan Final 2021 Soil and Groundwater Investigation Workplan - EHS Building Area (EOG) 2023 NAF Well Decommissioning Plan 2023 Annual Heating Season Sampling 2024-2025 PRRs 2024 Groundwater Monitoring Network - Addendum #4 2026 FFC CCR	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab vapor samples were collected within AOC-16-1 at SSHS-04-SS, SSHS-05-SS, SSHS-06-SS, SSHS-07-SS, SSHS-12-SS, SSHS-13-SS, SS-122, and SS-120. TCE was detected above NYSDOH Matrix Guidelines for sub-slab vapor at SSHS-04-SS (390 µg/m3) and SSHS-05-SS (2,100 µg/m3) within AOC-16-1. VOCs detected in sub-slab vapor above NYSDOH guidelines have been mitigated by the installation of sub-slab vapor mitigation systems described in Section 3.2. TCE effluent concentrations for the F-Wing area (portion of EHS building located above AOC-16-1) decreased between June 2018 and July 2021, increased in December 2021, then slightly decreased in November 2023 as shown on Figure 6V-2. This indicates that TCE is still present in sub-slab vapor beneath the EHS Building and may potentially be associated with AOC-16-1. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-16-1 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of the AOC. Monitoring wells MW-83S, MW-83I, and MW-94S were installed within AOC-16-1. Monitoring wells MW-94I, MW-47, MW-47I, MW-90S, MW-90I, MW-74I and MW-74S are located downgradient of AOC-16-1. Temporary monitoring well B3203A was installed within AOC-16-1 and analyzed for PCBs, metals, SVOCs. Other temporary monitoring wells were installed within AOC-16-1 for analysis of VOCs, including B3205A, B3025B, B93, B96, B97, B3202A, B3202B, B3203A, B3203B, B3204A, and B3204B. PCBs, metals, and SVOCs were not detected above TOGS groundwater standards within and downgradient of AOC-16-1. VOCs were detected above TOGS groundwater standards downgradient of AOC-16-1 at MW-47I and temporary monitoring wells B92 and B94. MW-47I exceeded the TOGS groundwater standard for benzene (1.5 µg/L compared to TOGS of 1 µg/L) in September 2021. Benzene was non-detect at MW-47I in samples collected in October 2021 and April 2024. TCE was detected above the TOGS groundwater standard (5 µg/L) at temporary monitoring wells B92 (5.6 µg/L) and B94 (8.9 µg/L) in August 2014. TCE was not detected above TOGS groundwater standards at MW-47 in September 2016 (3.9 µg/L) and was non-detect in February 2021 and July 2021. TCE was non-detect at MW-47I in September 2021, October 2021, and April 2024. As temporary monitoring wells are installed for short-term investigation purposes and are typically sampled shortly after installation, the resulting data may reflect localized disturbance, incomplete equilibration, and short-term turbidity-related influences that can bias reported groundwater concentrations. In contrast, permanent monitoring wells provide a more reliable measure of ambient groundwater quality and dissolved-phase conditions within the aquifer as they are designed, developed, and sampled to better represent stable formation water over time. Accordingly, the absence of TCE exceedances in the downgradient permanent monitoring wells is considered more representative of actual aquifer conditions than the isolated exceedances reported in temporary monitoring well samples. Therefore, additional investigation is not warranted. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2020 and the 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	NA	MW-83I, MW-83S, B3202A, B3202B, B3203A, B3203B, B3204A, B3204B, B3205A, B3205B, B93, B95, B96, B97	MW-94S MW-94I MW-47 MW-47I MW-90S MW-90I	SS-120, SS-122, SSHS-04-SS, SSHS-05-SS, SSHS-06-SS, SSHS-07-SS, SSHS-12-SS, SSHS-13-SS	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-16-1 underlying the school building is unknown			
		AOC-16-3		NAF/FFC			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. MW-83S/I was installed and sampled as a monitoring point for AOC-16 as part of the Soil and Groundwater Investigation Workplan - EHS Building Area (EOG) (Figure 2-3). Other monitoring wells associated with AOC-16 include MW-47 and MW-61S according to the Site Wide RI Work Plan Amendment #1. 2. According to the 2023 NAF Well Decommissioning Plan, MW-44, MW-38 and MW-40 were decommissioned and were all downgradient monitoring points for AOC-16. MW-102I/S are now the primary downgradient monitoring point for AOC-16 south (Figure 2-3). - MW-102 has had Thallium, and SVOCs detected above TOGS SCOs between sampling events in 2023 and 2024. The distribution of Metals, and SVOC exceedances has been spatially and temporally inconsistent across the Site and the SVOCs only sporadically exceeded TOGS standards at the listed monitoring wells. Further evaluation found that thallium exceedances are due to false positive bias due to the analytical method. Based on these results no further assessment is warranted to further define the nature and extent of Metals and SVOCs impacts to groundwater at the Revised BCP Site. 3. AOC-16 has had the extent of possible soil contamination investigated across many different soil sampling events as shown in SCWP Addendum #1. PCB, Metal, SVOC and VOC exceedances were detected in soil borings within AOC-16 according to the Revised Remedial Investigation workplan. These exceedances were then addressed during IRM #5 and were vertically and laterally delineated. Soil exceedances found within AOC-16 that were excavated during IRM #5 are discussed below: - The following samples had PCBs detected above NYS Hazardous Waste SCOs (>= 50 mg/kg)and were excavated during IRM #5: B233 and B242 (0-2 ft bgs); B239A, FB7-D, B229, B230, B314, B242 and B2691 (2-4 ft bgs); B227, B229, B2675 and B234A (4-6 ft bgs). (Figure 5-7A - Figure 5-7E) - The following samples had PCBs detected above IRM Subsurface SCOs (> 10 mg/kg) and were excavated during IRM #5: FB7-A, FB7-C, B227, B239 and B314 (0-2 ft bgs); B2326, B2602, B240, B228, B412, B2357, B2305, and B2508 (2-4 ft bgs); FB7-DA, B233, B228, and B230 (4-6 ft bgs); B227 (6-8 ft bgs) (Figure 5-7A - Figure 5-7E) - The following samples had PCBs detected above POG SCOs (> 3.2 mg/kg) and were excavated during IRM #5: FB7-D, B229, B320, B408, and B2903 (0-2 ft bgs); B2334, B2320, B218, B227, B2331, B408 and B2193 (2-4 ft bgs); B218, B2651, B222, B223, B320, B314, B313, B319, B239A, and B2526 (4-6 ft bgs); B323, and B2675 (8-10 ft bgs) (Figure 5-7A - Figure 5-7E) - The following samples had PCBs detected above RR SCOs (> 1 mg/kg) and were excavated during IRM #5: B218, B223, B230, B237, B308, , B2693, B2501, and B2306 (0-2 ft bgs); FB7-A, FB7-C, B2333, B222, B237, B2321, B2510, B2693, B2692, B2919, B2507, and B2509 (2-4 ft bgs); B2333, B412, B312, B2664, and B2663 (4-6 ft bgs) (Figure 5-7A - Figure 5-7E) - The following samples had Metals detected above RR SCOs and were excavated during IRM #5: B2226, and B2193 (2-4 ft bgs); B2223, B2226, and B2225 (4-6 ft bgs); B2781, and B2935 (8-10 ft bgs) (Figure 5-7A - Figure 5-7E) 4. During IRM #5 the majority of borings with detected exceedances of comparison SCOs were excavated. The following borings with exceedances still remaining in place are B2227 (PCBs exceeding POGs SCOs) at 6-12 ft bgs, B2226 (PCBs exceeding POG SCOs) at 8-12 ft bgs, B2110 (Metals exceeding RR SCOs) at 6-16 ft bgs, B234A (PCBs exceeding NYS Hazardous SCOs) at 6-8 ft bgs, B233 (PCBs exceeding POG SCOs) at 6-10 ft bgs, B319 (PCBs exceeding POG SCOs) 6-10 ft bgs, B322 (PCBs exceeding RR SCOs) 6-10 ft bgs, B2700 (PCBs exceeding POG SCOs) at 8-10 ft bgs, and B227A (PCBs exceeding POG SCOs) at 8-10 ft bgs. (Figure 6-4A - Figure 6-4H) - The above samples are all laterally delineated by further IRM #5 sampling. Conclusion: Vertical and lateral extent of AOC-16 located on Site #c808022 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Lateral and vertical extent of AOC-16 South was investigated as part of historical RI sampling events as well as IRM #5.		16	MW-106, MW-16, MW-52, MW-56, MW-57, MW-59I, MW-59IR, MW-59S, MW-59SR, MW-60, MW-60IR, MW-60SR, MW-63S, MW-63I, MW-65, MW-65R, MW-76I, MW-76S, MW-79I, MW-79S, MW-92I, MW-92S, B2722, B3090, B572A, B3856I, B3856S, B3867, B3868I, B3868S, B3869I, B3869S, B3874, B3883, B3885, B3886, B3893I, B3893S, B3909I, B3909S	MW-106 MW-57R MW-100S MW-100I MW-58 MW-36	-	-	32 ft	14 ft	20 ft	26 ft

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
16, West		AOC-16-4		FFC			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater	P, M	2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011-2013 ACRs 2019 Revised Remedial Investigation Workplan 2020 Site Wide RI Work Plan Amendment #1 2021 Soil and Groundwater Investigation Workplan - EHS Building Area (EOG) 2023 NAF Well Decommissioning Plan 2024 Groundwater Monitoring Network - Addendum #4 2026 FFC CCR	1. Monitoring wells associated with AOC-16 are MW-11S, MW-11D, MW-28, MW-29, MW-44, MW-52, MW-53, MW-54, and MW-56 (Figure 2-3) according to the Site Wide RI Work Plan Amendment #1. 2. Further monitoring wells installed downgradient of AOC-16 are MW-59IR/SR, MW-100I/S, MW-57R, MW-106, MW-79I/S, MW-76I/S, MW-92I/S, and MW-58. The following monitoring wells have had PCB or Metals detections above TOGS. - MW-56 had a PCB detections above TOGS (0.59 ug/L) during 2021 sampling but no PCB detections in following sampling events (Table 5-8). - MW-106 has consistent low level TOGS exceedances (0.32 - 0.57 ug/L) but there have no PCB detections in MW-97 further downgradient as well as MW-57R directly adjacent to MW-106 (Figure 2-3). - Metals were not consistently reported at concentrations above TOGS groundwater standards in monitoring wells with the exception of thallium, iron, and manganese. For these three metals, further evaluation found that thallium exceedances are due to false positive bias due to the analytical method, and iron and manganese concentrations are not Site-related. Based on these results no further assessment is warranted to further define the nature and extent of metals impacts to groundwater at the Revised BCP Site. 3. A total of 95 soil borings were advanced within AOC-16-4 and AOC-16-5 to a maximum depth of 38 ft bgs. Within the FFC, soil borings were collected on a 60x60 ft grid to the water table and subsequent step out samples collected on approximately 30 ft spacing to further define the nature and extent of COPCs observed above Restricted Residential SCOs. COPCs including PCBs, metals, and SVOCs were detected above Restricted Residential SCOs. VOCs were not detected above Restricted Residential SCOs. PCBs were detected above the Restricted Residential SCO up to 12 ft bgs, metals up to 14 ft bgs, and SVOCs up to 10 ft bgs. VOCs were not detected above Restricted Residential SCOs within AOC-16-4 or AOC-16-5. Excavations within AOC-16-4 were completed up to 7 ft bgs and excavations within AOC-16-5 completed to 9 ft bgs as part of the FFC IRM, as discussed in Section 3.2.4. COPCs identified in soil within AOC-16 may be related to these historic features but have been removed by FFC IRM excavations except at locations noted in Section 5. Groundwater quality data demonstrates that COPC concentrations remaining in place do not indicate an ongoing source contributing to groundwater exceedances above TOGS standards. Conclusion: Nature and extent of potential soil and groundwater contamination associated with AOC-16-4 and AOC-16-5 on the north and western portion of the NAF has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Based on these observations, no further assessment is warranted to further define the nature and extent of impacts in groundwater and soil potentially associated with AOC-16-4 or AOC-16-5 on Site #c808022.	Soil - Yes Groundwater - Yes	7	SSHS-B2542, SSHS-B2542A	MW-11S MW-11D B2541 B2819 B3858I B3858S B3865I B3865S	-	-	-	-	-	-
		AOC-16-5											9	SSHS-B3093, SSHS-B3094, SSHS-B3859I, SSHS-B3859S, SSHS-B3860I, SSHS-B3860S	MW-44 MW-38 B3863 B3864S B3864I	-	-	-	-	-	-
16		AOC-16-2		#p808049	-	-	-	-	-	-	-	To be investigated as part of #c808054									

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
17	Possible Disposal Areas	AOC-17-4	Possible Plating Area	EHS Building	AOC 17 (Possible Disposal Areas) includes a possible former plating area in the northern part of the Site; coincident with AOC16; four (4) former potential disposal areas, three (3) on the southwestern part of the Site and one (1) on the southeastern part of the Site; two of these areas underlie the EHS Building. A former acid drainage pit in the southeastern part of the Site underlies the EHS Building and a former coal pile located in the southeastern corner of the Site was excavated during IRM #2. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil. While the presence of the EHS building slab reduces the potential for stormwater infiltration through the areas that lie beneath the building footprint, there is unknown potential for vertical migration of COPCs through the soil column to the water table (present approximately 14 to 16 feet bgs). While no specific potential release has been identified in the former disposal area east of the gymnasium, there may be a potential for past release to surface soil due to former industrial land use, and there is unknown potential for vertical migration through the soil column to the water table. The potential for VOCs to migrate into indoor air has been assessed through soil vapor investigation, and considered to be an incomplete pathway (Figures 6V-1A and 6V-1B). The presence of the EHS building slab precludes the potential for direct contact with COPCs in soil by subsurface construction workers in the portion of the AOC beneath the building. Figure 1-4.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient of the EHS building toward off-site surface water receptors, or along preferential pathways (e.g., backfill around stormwater drains north of the EHS building) toward off-site surface water receptors. 2. EHS Building occupants: VOC-impacted sub-slab vapor underlies portions of the EHS building, posing a potential vapor intrusion (VI) risk in indoor air to occupants.	Soil Groundwater Soil Vapor Indoor Air		Sanborn Fire Insurance Maps 1967 Lancy Report and Figures 1988 PSA 2001 Sampling Report 2003 Health Consultation 2009 EMP 2010 Health Consultation 2011-2013 ACRs 2014 VI Assessment 2015 Site Characterization Work Plan Addendum #1 2016 Site Characterization Work Plan Addendum #2 2016 Site Characterization Work Plan Addendum #3 2018 Supplemental VI Assessment 2018 IRM #2 PDI Workplan 2018 Amendment #1 to the IRM#2 PDI Workplan 2018 FFC RI/PDI Activities Workplan 2018 Amendment #1 - FFC RI/PDI Workplan 2018 SVIA Report 2019 ISMP 2019 IRM #2 CCR 2019 Revised Remedial Investigation Workplan 2020 Site Wide RI Work Plan Amendment #1 2021 Soil and Groundwater Investigation Workplan - EHS Building Area (EOG) 2023 Addendum #2 to the Soil and Groundwater Investigation Workplan - EHS Building Area 2023 Annual Heating Season Sampling 2024 Groundwater Monitoring Network - Addendum #4 2024-2025 PRRs	1. The potential for VOCs to migrate into indoor air has been assessed through previous sub-slab soil vapor investigation. Sub-slab vapor analytical results are presented in Table 5-2 screened against NYSDOH Matrix Guidelines for sub-slab vapor. Sample locations are shown on Figure 5V-2A-F. Sub-slab vapor samples were collected within AOC-17-4 (SSHS-04-SS, SSHS-05-SS, SSHS-06-SS, SSHS-07-SS, SSHS-12-SS, SS-122, and SS-120), AOC-17-5 (SS-133, SSHS-08-SS, SSHS-09-SS, and SSHS-10-SS), AOC-17-8 (SSHS-22-SS) and adjacent to AOC-17-6 (SSHS-01-SS). TCE was detected above NYSDOH Matrix Guidelines for sub-slab vapor at SSHS-04-SS (390 µg/m3) and SSHS-05-SS (2,100 µg/m3) within AOC-17-4. TCE was detected below NYSDOH Matrix Guidelines for sub-slab vapor collected within AOC-17-5 and AOC-17-8 and adjacent to AOC-17-6. VOCs detected in sub-slab vapor above NYSDOH guidelines have been mitigated by the installation of sub-slab vapor mitigation systems described in Section 3.2. TCE effluent concentrations for the F-Wing area (portion of EHS building located above AOC-17-4 and AOC-17-5) decreased between June 2018 and July 2021, increased in December 2021, then slightly decreased in November 2023 as shown on Figure 6V-2. This indicates that TCE is still present in sub-slab vapor beneath the EHS Building and may potentially be associated with AOC-17-4. 2. The potential for VI has been assessed throughout the EHS building. The nature and extent of sub-slab vapor impacts has been defined (Figure 5V-2A-F). SSDS systems have been installed in areas requiring mitigation (Figures 3-2 and 5V-2A-F). Therefore, VI is not considered a complete exposure pathway (Soil Vapor Intrusion Assessment). 3. Potential impacts of AOC-17-4, AOC-17-5, and AOC-17-6 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of these AOCs, outside of the EHS Building. Monitoring well MW-83I and temporary monitoring wells B93 (analyzed for VOCs), B94 (analyzed for VOCs), B95 (analyzed for VOCs), B96 (analyzed for VOCs), B97 (analyzed for VOCs), B3202A (analyzed for VOCs), B3202B (analyzed for VOCs), B3203A (analyzed for PCBs, metals, SVOCs, and VOCs), B3203B (analyzed for VOCs), B3204A (analyzed for VOCs), and B3204B (analyzed for VOCs), were installed within AOC-17-4. Monitoring wells located downgradient of AOC-17-4, AOC-17-5, and AOC-17-6 include MW-47, MW-47I, MW-90S, MW-90I, MW-91S and MW-91I. Results are shown compared to TOGS groundwater standards on Figures 5-2A-1 through 5-2D-2. Groundwater analytical results including those from previous investigations are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs, metals, and SVOCs were not detected above TOGS groundwater standards within or downgradient of AOC-17-4, AOC-17-5, and AOC-17-6. MW-47I located downgradient of AOC-17-4 exceeded the TOGS groundwater standard for benzene (1.5 µg/L compared to TOGS of 1 µg/L) in September 2021. Benzene was non-detect at MW-47I in samples collected in October 2021 and April 2024. Therefore, further investigation is not warranted. TCE was detected above the TOGS groundwater standard (5 µg/L) at B92 (5.6 µg/L) and B94 (8.9 µg/L) in August 2014. TCE was detected below TOGS groundwater standards at adjacent monitoring well MW-47 in September 2016 (3.9 µg/L) and non-detect in February 2021 and July 2021. TCE was non-detect at MW-47I in September 2021, October 2021, and April 2024. As temporary monitoring wells are installed for short-term investigation purposes and are typically sampled shortly after installation, the resulting data may reflect localized disturbance, incomplete equilibration, and short-term turbidity-related influences that can bias reported groundwater concentrations. In contrast, permanent monitoring wells provide a more reliable measure of ambient groundwater quality and dissolved-phase conditions within the aquifer as they are designed, developed, and sampled to better represent stable formation water over time. Accordingly, the absence of TCE exceedances in the adjacent permanent monitoring wells is considered more representative of actual aquifer conditions than the isolated exceedances reported in temporary monitoring well samples. Therefore, additional investigation is not warranted. 4. Potential impacts of AOC-17-8 on groundwater quality was evaluated using samples collected from monitoring wells located downgradient of this AOC, outside of the EHS Building. Monitoring wells MW-85I, MW-13, MW-88S, and MW-88I and temporary monitoring well B29-A (analyzed for PCBs, SVOCs, and VOCs) were installed downgradient of AOC-17-8. PCBs, metals, SVOCs, and VOCs were not detected above TOGS groundwater standards at these monitoring wells. Conclusion: SSDS have been installed in the Gymnasium, K-Wing Science Addition, Cafeteria and Cafeteria Addition, F-Wing, and Music Wing of EHS to mitigate potential VI to indoor air. Sampling of indoor air for VOCs has been conducted as part of post-remediation monitoring under the ISMP and ISMP Amendment #1 between December 2019 through present day. Results have been reported in ISMP PRRs for 2019–2020 and the 2023 Heating Season Soil Vapor Intrusion Monitoring and Sampling Report. VOCs included on NYSDOH Soil Vapor/Indoor Air Decision Matrices have not been detected above the indoor air guideline values for mitigation under ISMP post-remediation monitoring. Based on these findings, the potential VI to indoor air has been mitigated. Additional sampling of indoor air for VOCs will continue under the SMP for Site #c808022. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	NA	MW-83I, B3202A, B3202B, B3203A, B3203B, B3204A, B3204B, B93, B94, B95, B96, B97	MW-47 MW-47I MW-90S MW-90I MW91S MW-91I	SSHS-04-SS, SSHS-05-SS, SSHS-06-SS, SSHS-07-SS, SSHS-12-SS, SS-122, SS-120	-	As additional soil investigation beneath the EHS building was not feasible, the presence of COPCs in soil within the portions of AOC-17 underlying the school building is unknown			
		AOC-17-5	Possible Disposal Area										NA	-		SS-133, SSHS-08-SS, SSHS-09-SS, SSHS-10-SS	F-Wing				
		AOC-17-6	Possible Disposal Area										NA	-		SSHS-01-SS	Cafeteria				
		AOC-17-7	Possible Disposal Area										NA	-	-	-	K-Wing				
		AOC-17-8	Acid Drainage Pit										NA	-	MW-85I MW-13 MW-88S MW-88I B29-A	SSHS-22-SS	Gymnasium				
		AOC-17-3	Former Coal Pile	Rear Parking Lot			1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature (areas outside of the EHS Building footprint only). 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater			1. A total of 86 soil borings were installed within AOC-17-3 to a maximum depth of 18.07 ft bgs across multiple soil sample events (Section 2.2). Soil borings collected within AOC-17-3 include samples collected as part of the IRM #2 PDI, IRM #2 PDI Amendments #1-5, Addendum 4 to the Soil and Groundwater Investigation Work Plan EHS Building Area, and Addendum 6 to the Soil and Groundwater Investigation Work Plan. COPCs including PCBs, metals, and SVOCs were identified within AOC-17-3 above Restricted Residential SCOs. VOCs were not identified within AOC-17-3 above Restricted Residential SCOs. PCBs above the Restricted Residential SCO were detected up to a depth of 14 ft bgs. Metals above the Restricted Residential SCO, including arsenic, chromium, copper, mercury, lead, nickel, and selenium, were detected up to a depth of 14 ft bgs. SVOCs above the Restricted Residential SCO, including benz(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, and indeno(1,2,3-cd)pyrene, were detected up to a depth of 6 ft bgs. 2. Exceedances remaining in place within AOC-17 in the Rear Parking Lot area are laterally delineated by the following areas: - To the East/West exceedances remaining in place within AOC-17 in the Rear Parking Lot area are laterally delineated by Site #808054. - To the North exceedances remaining in place within AOC-17 in the Rear Parking Lot area are laterally delineated by the EHS building and associated sampling events. - To the South exceedances remaining in place within AOC-17 in the Rear Parking Lot area are laterally delineated by Site #808043 3. Of the sample locations with exceedances remaining in place, 10 of the sample locations are vertically delineated by additional samples. (Figures 6-6A - 6-6J). Additional vertical delineation of 65 sample locations that exceed RRSCOs in precluded by subsurface building structures or utilities. 4. Soils that remain in place within IRM #2 are either below concrete obstructions and utilities or the result of construction modifications (i.e., additional sloping and benching) due to the obstructions. 3. Potential impacts of AOC-17-3 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of the AOC. Monitoring wells installed within AOC-17-3 include MW-46, MW-70S, MW-70I, MW-73S, and MW-73I. Temporary monitoring wells installed within AOC-17-3 include B23 which was analyzed for metals, SVOCs, and VOCs. Monitoring wells downgradient of AOC-17-3 include MW-42 and MW-82S. Temporary monitoring wells downgradient of AOC-17-3 include B4154I and B4154S which were both analyzed for PCBs, metals, SVOCs, and VOCs. Groundwater samples collected as part of the RI investigation of AOC-17-3 were analyzed for PCBs, metals, SVOCs, and VOCs. Results are shown compared to TOGS groundwater standards on Figures 5-14A-1 through 5-14D-2. Groundwater analytical results including those from previous investigations are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. PCBs and VOCs were not detected above TOGS groundwater standards within or downgradient of AOC-17-3. Conclusion: Lateral extent of AOC-17-3 has been defined in soil and groundwater on Site #808054. Vertical extent of soil contamination in the rear parking lot area is vertically delineated by soil borings and grab samples that are either below concrete obstructions and utilities or the result of construction modifications (i.e., additional sloping and benching) due to the obstructions.		14	MW-46, MW-70I, MW-70S, MW-73I, MW-73S, SSHS-B23	MW-42 MW-82S B4151I B4154S	-	-	14 ft	14 ft	6 ft	-

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
		AOC-17-9	Possible Plating Area	NAF							1. A total of 145 soil borings were installed within AOC-17-9 to a maximum depth of 34 ft bgs across multiple soil sampling events (Section 2.2). Within the NAF, soil borings were collected on a 60x60 ft grid to the water table and subsequent step out samples collected on approximately 30 ft spacing to further define the nature and extent of COPCs observed above Restricted Residential SCOs. COPCs including PCBs, metals, and SVOCs were detected within AOC-17-9 above Restricted Residential SCOs. VOCs were not detected within AOC-17-9 above Restricted Residential SCOs. PCBs above the Restricted Residential SCO were detected up to a depth of 18 ft bgs, below the water table (approximately 16 ft bgs). Metals above Restricted Residential SCOs, including barium, cadmium, chromium, copper, lead, mercury, and zinc, were detected up to a depth of 14 ft bgs. SVOCs above the Restricted Residential SCOs, including benz(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene, dibenz(a,h)anthracene, fluoranthene, and indeno(1,2,3-cd)pyrene, were detected up to a depth of 10 ft bgs. 2. Potential impacts of AOC-17-9 on groundwater quality were evaluated using samples collected from monitoring wells located within and downgradient of the AOC. Monitoring wells installed within AOC-17-9 include MW-56, MW-57, MW-59S, MW-59I, MW-60, MW-60SR, MW-60IR, and MW-65R. Temporary monitoring wells installed within AOC-17-9 include B3883 (analyzed for PCBs), B3885 (analyzed for PCBs), B3886 (analyzed for PCBs, metals, SVOCs, and VOCs), B3903S (analyzed for PCBs), B3903I (analyzed for PCBs), B3909S (analyzed for PCBs), B3909I (analyzed for PCBs), B3893I (analyzed for PCBs), and B3893S (analyzed for PCBs). Monitoring wells downgradient of AOC-17-9 include MW-57R, MW-100S, and MW-100I. Groundwater samples collected as part of the RI investigation of AOC-17-9 were analyzed for PCBs, metals, SVOCs, and VOCs. Results are shown compared to TOGS groundwater standards on Figures 5-5A-1 through 5-5D-2. Groundwater analytical results including those from previous investigations are presented in Tables 5-8, 5-9, 5-10, and 5-11, for PCBs, metals, SVOCs, and VOCs, respectively, and are compared to TOGS groundwater standards. Metals and VOCs were not detected above TOGS groundwater standards. PCBs and SVOCs were detected above TOGS groundwater standards and are discussed further below. Conclusion: Lateral extent of AOC-17-9 has been defined in soil and groundwater as part of the RI for #c808022 as discussed above. Based on these observations, no further assessment is warranted to further define the nature and extent of impacts in groundwater and soil potentially associated with AOC-17-3 on Site #c808022.		16	MW-56, MW-57, MW-59I, MW-59S, MW-60, MW-60IR, MW-60SR, MW-65R, B3883, B3885, B3886, B3893I, B3893S, B3903I, B3903S, B3909I, B3909S	MW-57R MW-100S MW-100I	-	-	18 ft	14 ft	10 ft	-
		AOC-17-1	Possible Disposal Area	#p808049						-	-	To be investigated as part of #c808054									
		AOC-17-2	Possible Disposal Area	#p808049						-	-										
18	2017 Storm Drain Installation and TCE-Impacted Soils	AOC-18-1	2017 TCE Impacted Soil Area	#c808054	AOC-18 (TCE Investigation Area) is defined as the area where TCE was detected by ECSD contractors in grab soil samples at concentrations of up to 10,000 µg/kg during the EHS stormwater sewer installation, and the sanitary ejector northwest of this area. Historical operations near these structures have the potential to have resulted in release of COPCs to underlying soil and there is an unknown potential for vertical migration through the soil column to the water table (located approximately 16 ft bgs). Because of the suspected presence of TCE or other VOCs in this AOC, soil and groundwater samples will also be collected to assess for the presence of emerging contaminants (1,4-dioxane and PFAS).	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	1. On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature. 2. Off-site surface water users/ecological communities: Impacted groundwater (if present) may migrate downgradient toward off-site surface water receptors, or along preferential pathways (e.g., backfill around sewers) toward off-site surface water receptors.	Soil Groundwater	P,M,S,V	Investigations Completed as part of this AOC are documented under #c808054	Investigations completed as part of this AOC are documented under #c808054	To be investigated as part of #c808054								
		AOC-18-2	Sanitary Sewer Ejector	#c808054																	

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
19	Former Drum Nest Area	-	-	NAF	AOC-19 was identified when a former drum nest area was encountered during implementation of IRM activities in the Northern Athletic Fields (NAF) on 5 January 2022.There may be a potential for past release to surface soil due to former industrial land use, and there is unknown potential for vertical migration through the soil column to the water table.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature.	Soil Groundwater	P, V	2019 Revised Remedial Investigation Workplan 2020 Revised RI Work Plan - Amendment #1 2023 Groundwater Mon. Network Update Add #1 2023 Groundwater Mon. Network Update Add. #2 2023 Groundwater Mon. Network Update Add. #3 2023 Addendum #2 to the Soil and Groundwater Investigation Workplan - EHS Building Area 2024 Groundwater Monitoring Network - Addendum # 2026 NAF CCR	1a. PCBs were observed to exceed Restricted Residential SCOs below the water table (Table 6-4A). These PCB exceedances were observed between 14 and 34 ft bgs as shown on Figure 6-3l-Q. PCB exceedances in the NAF are not vertically defined at B3920 from 31.85V-2A-F3.85 ft bgs, but is vertically defined by the clay layer at 35 ft bgs. PCBs are horizontally defined for BCP Site c808022 by the Restricted Residential SCO Limits depicted on Figures 6-3l-Q. PCB exceedances below the water table are inferred to the Revised BCP Site Boundary based on off-Site Restricted Residential SCO exceedances which will be addressed as part of the RI of #c808054. Total PCB concentrations at or above TSCA levels of 50 mg/kg are present from 16-30 ft bgs. These concentrations range from 65.1 to 13,000 mg/kg. These TSCA level PCB concentrations are primarily located in the vicinity of AOC-19 and are defined within Site #c808022. Residual PCBs may affect groundwater quality; a groundwater monitoring program will be included in the SMP. VOCs observed to exceed Restricted Residential SCOs below the water table include PCE and TCE (Table 6-4D). These VOC exceedances were observed between 24 and 30 ft bgs as shown on Figures 6-3M-O. PCE above the Restricted Residential SCO below the water table was observed at 40 mg/kg at B3454. TCE above the Restricted Residential SCO below the water table ranged from 25 - 170 mg/kg, with the maximum value observed at B3920. VOC exceedances in the NAF are vertically defined at 30 ft bgs. VOCs are horizontally defined for BCP Site c808022 by the Restricted Residential SCO Limits depicted on Figures 6-3M-O 1b. On 5 January 2022, drums were encountered in the IRM #5A2 2- to 4-foot excavation in AOC-19. An odor was detected, and a black liquid was observed. PID measurements greater than 100 ppm were observed within the odorous and stained area. Samples of the drum contents and surrounding soils were collected and submitted for laboratory analyses, and the area was secured during the period of the investigation by covering it with a tarp. Detections in the drum contents included PCBs (22 mg/kg), benzene (25 mg/kg), ethylbenzene (45 mg/kg), toluene (270 mg/kg), total xylenes (330 mg/kg), naphthalene (38 mg/kg), and lead (190 mg/kg). PCBs were detected in surrounding soils at 22,000 mg/kg. VOCs detected in the surrounding soils included benzene (0.60 mg/L) and trichloroethene (1.2 mg/L). The drums and surrounding soils were managed in accordance with IRM #5A2 Addendum #1, relocated and staged for transport and disposal in accordance with IRM #5A2 Addendum #3, and transported for disposal in accordance with IRM #5A2 Addendum #5. Soil impacts associated with AOC-19 were removed with excavation to the water table during IRM #5A2 2a. PCB concentrations downgradient of AOC-19 at MW-50S, MW-50I, MW-52, MW-51, MW-96, MW-106 have been observed above TOGS groundwater standards. Relative to the area of PCB exceedances of TOGS groundwater standards, MW-50S, MW-50I, and MW-52 are located hydraulically upgradient, with MW-51 and MW-106 downgradient, and MW-96 downgradient of MW-51 and MW-106. • Former monitoring wells MW-50S, MW-50I, and MW-52 characterize the upgradient extent of PCBs in this area. These monitoring wells were sampled in February and April 2021. These locations exceeded TOGS for PCBs in April 2021 (concentrations of 2.3 µg/L, 0.14 µg/L and 7.6 µg/L, respectively). The maximum concentration of PCBs at MW-50S, MW-50I, and MW-52 was 2.3 µg/L in April 2021, 0.14 µg/L in April 2021, and 12.5 µg/L in February 2021, respectively. These monitoring well locations were decommissioned as part of IRM #5A2 in December 2021. • MW-51 is located approximately 100 ft east (downgradient) of MW-50S, MW-50I, and MW-52. PCBs have been sampled at MW-51 as part of seven sampling events in February 2021, April 2021, May 2023, September 2023, November 2023, January 2024, and April 2024. The maximum concentration of PCBs observed at MW-51 was 0.75 µg/L in February 2021. PCBs at MW-51 have been reported above TOGS in February 2021, April 2021 and September 2021, but reported below TOGS for samples collected in May 2023 and the three most recent sampling events in November 2023, January 2024, and April 2024, which also were reported as non-detections. PCBs concentrations at MW-51 have generally decreased from the initial sampling event in February 2021 to April 2024 (0.74 µg/L to non-detect). • MW-106 is located approximately 100 ft east (downgradient) of MW-52 and 80 ft south (cross gradient) of MW-51. PCBs have been sampled at MW-106 as part of five sampling events in May 2023, September 2023, November 2023, January 2024, and April 2024. The maximum concentration of PCBs at MW-106 observed was 0.57 µg/L in November 2023. PCBs at MW-106 have been reported above TOGS in May, September, and November 2023, but reported below TOGS for the sample collected in January 2024 (0.044 µg/L). PCB concentrations at MW-106 have generally decreased from the initial sampling event in May 2023 to April 2024 (0.48 µg/L to 0.35 µg/L). • MW-96 is located approximately 135 ft east (downgradient) of MW-51 and MW-106. MW-96 is located off-Site, outside the Revised BCP Site Boundary. MW-96 is located outside the Revised BCP Site Boundary but discussed below to inform evaluation of groundwater nature and extent downgradient of AOC-19. PCBs have been sampled at MW-96 as part of five sampling events in May 2023, September 2023, November 2023, January 2024, and April 2024. The maximum concentration of PCBs observed at MW-96 was 0.69 µg/L in February 2024. PCBs at MW-96 were reported above TOGS in May 2023, November 2023, and January 2024, but reported below TOGS for samples collected in September 2023 and April 2024, which were reported as non-detections. PCBs concentrations have generally decreased from the initial sampling event in May 2023 to April 2024 (0.35 µg/L to non-detect). 2b. Downgradient of AOC-19, VOC concentrations at MW-50S, MW-50I, MW-51, and MW-96 have been observed above TOGS groundwater standards. • MW-50S and MW-50I are located cross gradient from AOC-19 to the north. MW-50S and MW-50I were sampled twice for VOCs in February 2021 and April 2021. In February 2021 TCE was observed above TOGS groundwater standards (5 µg/L) at MW-50I (6.5 µg/L) and below TOGS groundwater standards at MW-50S (4.4 µg/L). In April 2021 TCE was observed above TOGS groundwater standards at MW-50S (6.4 µg/L) and below TOGS groundwater standards at MW-50I (4.3 µg/L). MW-50S and MW-50I were decommissioned as part of IRM #5A2 in December 2021. • MW-51 is located downgradient of AOC-19 and approximately 100 feet downgradient of MW-50S and MW50I. VOCs have been sampled at MW-51 as part of seven sampling events in February 2021, April 2021, May 2023, September 2023, November 2023, January 2024, and April 2024. Acetone, Freon 113, PCE, and TCE were observed above TOGS groundwater standards at MW-51. The maximum concentration of Freon 113 observed above the TOGS groundwater standard (5 µg/L) at MW-51 was 34 µg/L in November 2023. Freon 113 was reported above TOGS at MW-51 in samples collected in February 2021, April 2021, May 2023, September 2023, and November 2023, but has been reported below TOGS in the two most recent samples collected in January 2023, and April 2024 (3.4 µg/L and 1.1 µg/L, respectively). Freon 113 concentrations at MW-51 have been observed to generally decrease over time with the two most recent results being below TOGS. The maximum concentration of PCE observed above the TOGS groundwater standard (5 µg/L) at MW-51 was 14 µg/L in February 2021. TCE was reported above TOGS at MW-51 in samples collected in February 2021, April 2021, May 2023, November 2023 and April 2024 but has been reported below TOGS in September 2023, and January 2024 (3.9 µg/L and 4.9 µg/L, respectively). PCE concentrations at MW-51 have been observed to generally decrease over time. The maximum concentration of TCE observed above the TOGS groundwater standard (5 µg/L) at MW-51 was 94 µg/L in November 2023. TCE was reported above TOGS at MW-51 in samples collected in February 2021, April 2021, May 2023, September 2023, November 2023, January 2024 and April 2024. TCE concentrations at MW-51 have been observed to generally decrease over time. • MW-96 is under investigation as part of Site #c808054. Conclusions: Vertical and lateral extent of AOC-19 has been defined in soil and groundwater as part of the RI for #c808022. The source of AOC-19 was identified as a drum nest and has been removed as part of IRM #5A2. PCB concentrations downgradient of AOC-19 have generally been observed to decrease over time. The decrease in PCB concentrations generally coincides with the removal of impacts soiled in January 2022. PCBs at MW-51 were previously detected above TOGS in February and April 2021 (0.75 µg/L and 0.1 µg/L, respectively). Sampling of MW-51 in May 2023, following removal of the impacted soils, was reported below TOGS (0.1 µg/L). MW-51 was sampled for PCBs in February 2024 and April 2024, with results reported as non-detect. Based on these observations, no further assessment is warranted to further define the nature and extent of PCB impacts in groundwater on Site #c808022. Off-Site delineation will be completed and discussed in the #c808054 RIR/AA. Groundwater monitoring will continue under the SMP for Site #c808022.	Soil - Yes Groundwater - Yes	16	MW-52, B3883, B3886	MW-51 MW-106 MW-50S (cross-gradient) MW-50I (cross-gradient)	-	-	32 ft	-	-	28 ft

DRAFT

Table 1-1
Areas of Concern
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

AOC ID	AOC Description	Sub-AOCs	Sub-AOC Description	AOC Location	Conceptual Site Model			Media of Concern	COPC	Investigations Completed	Investigation Summary	Nature and Extent Defined	Approximate Excavation Depth	Summary of environmental media samples supporting AOC delineation			Co-located SSDS	Depth of Soil Impact (RR SCO exceedances)			
					Potential Source	Potential Transport Mechanism	Potential Exposure Pathway/Receptor							Monitoring Wells within or adjacent to AOC	Downgradient Monitoring Wells	Sub-Slab Soil Vapor		PCBs	Metals	SVOCs	VOCs
20	Historical Water Line	-	-	NAF	AOC 20 (historical water line) is defined as the area where confirmation samples during IRM #5A2 detected concentrations of mercury up to 200 mg/kg and lead up to 6,100 mg/kg during excavation along the eastern property line of the NAF (Figure 1-4). There may be a potential for past release to surface soil due to former industrial land use, and there is unknown potential for vertical migration through the soil column to the water table.	COPCs in impacted soil within or beneath the release area (if present) can migrate vertically toward the water table, and then migrate downgradient in groundwater.	On-Site Subsurface Construction Workers: Subsurface excavation workers at the Site could come into direct contact with COPCs in soil within or adjacent to this feature.	Soil Groundwater	M	2023 Continued NAF Soil Cover Verification Interim Sampling #2 2023 IRM #5A2 - Addendum #8 Phase 3 2023 IRM #5A2 - Addendum #8 Phase 3 Amendment #1 2023 Groundwater Mon. Network Update Add #1 2023 Groundwater Mon. Network Update Add. #2 2023 Groundwater Mon. Network Update Add. #3 2024 Groundwater Mon. Network Update Add. #4 2026 NAF CCR	1.Soil Cover verification samples were collected along the eastern property line of the NAF in order to leave native material in place. This was in part to keep the structural integrity of the permanent fence in place. Results from this sampling within AOC-20 indicated concentrations above RRSCOs for mercury where the highest concentrations were reported at SCV44-0.17-0.75 (10 mg/kg), SCV49-0.17-0.75 (9.3 mg/kg), SCV49-0.75-1.75 (22 mg/kg, corresponding duplicate 63 mg/kg), SCV50-0-0.58 (120 mg/kg), and SCV50-0.58-1.58 (200 mg/kg). Lead concentrations above RRSCOs were reported as high as 4,800 mg/kg at SCV54-0.17-0.75. 2. Additional samples were collected in three separate locations (two valves and one pipe sample) in July 2023 where a historical waterline and associated pipe valves were observed during IRM #5A2 believed to be associated with the elevated metals concentrations identified along the eastern property line (WLV1, WLV2, and WLP). Metals concentrations for the two waterline valve samples were detected above RRSCOs for arsenic (150-160 mg/kg), cadmium (27 mg/kg), chromium (190-220 mg/kg), copper (530 mg/kg), manganese (4,000-4,900 mg/kg), and nickel (750 mg/kg). The water line pipe (WLP) sample was collected from the physical pipe, co-located with the highest concentrations mercury concentrations identified in soil at SCV50 listed above. Mercury concentrations for this sample were detected at 5.2 mg/kg. 3. Addendum #8 Phase #3 (A8PH3) was completed in September 2023 to address exceedances of RRSCO and IRM #5A2 subsurface action levels in native soils along the eastern NAF property boundary, including the samples listed above. Analytical data received for A8PH3 identified lead concentrations above 20x TCLP hazardous waste criteria for lead. TCLP analysis for metals were requested for sample A8PH3-B28 due to the detection of 6,100 mg/kg of lead. Lead was detected at 12 mg/L in the TCLP analysis, above the RCRA toxicity characteristic for lead of 5 mg/L. Mercury was detected above RRSCO and 20x TCLP hazardous waste criteria within AOC-20 at sample locations A8PH3-B31, A8PH3-B2, A8PH3-B33 (DUP318) and A8PH3-B34 with concentrations ranging between 5.2 and 13 mg/kg. Mercury was detected in the same area to a depth of 8 ft bgs at IRM #5A2 confirmation sample locations S120-S3, S120-S4, and B1158-S6 at concentrations ranging from 5.7 to 24 mg/kg. The mercury and lead exceedances are delineated laterally by other A8PH3 samples as well as IRM #5A2 confirmation samples. 4. Addendum #8 Phase 3 - Amendment #1 (A8PH3A1) was completed in December 2023 through January 2024 to remove exceedances above 20x TCLP and/or RCRA toxicity characteristics discussed above in native soils remaining along the eastern property boundary to the #c808022 BCP limit associated with a historical water line. Exceedances above RRSCOs and 20x TCLP hazardous waste criteria remain in place along the sidewall of the eastern property line, located on Site #c808054. These exceedances are laterally delineated on Site #c808022 by imported fill placed as backfill or confirmation samples collected during the Addendum #8 phases (Figure 6-3A through Figure 6-3F) 5. Monitoring wells within the footprint of AOC-20 or downgradient include MW-57R and MW-97. MW-57R did not have reported detections for metals above TOGS. MW-97 did not have metals detections above TOGS for the above aforementioned metal analytes. Iron was detected above TOGS in November 2023 (390) and January 2024 (530). In addition, thallium was also reported above TOGS in January 2024 (4.2) and April 2024 (4.6). Iron TOGS groundwater standards exceedances are related to groundwater redox fluctuations that are consistent with background, unimpacted regional groundwater characteristics and are not Site-related. Thallium exceedances are attributed to false positive and biased-high results of USEPA Method 6010 for the metals analyses. The false positives and biased-high results are likely due to spectral interferences (Chapnick et al., 2010). Detections of these metals in groundwater do not indicate a metals source in the vicinity of AOC-20. Conclusion: Vertical and lateral extent of AOC-20 in soil and groundwater as part of the RI for #c808022 as discussed above. The source was identified as an historical water line and remediated through excavations completed under IRM #5A2 - Addendum #8 Phase 3 and Addendum #8 Phase 3 Amendment #1. Mercury exceedances remain in place at the Site boundary and will be investigated as part of the RI of Site #c808054.	Soil - Yes Groundwater - Yes	8	MW-57R, MW-100S, MW-100I, B3915, B3914	MW-97	-	-	-	8 ft	-	-

Notes:
-Media of Concern and COPCs are provided from 2019 RI Work Plan
-Approximate depth of excavation represented the maximum depth an IRM excavation occurred within that AOC. Depth of excavation does not indicate the AOC was excavated down to that depth. A range of excavation depths were used to meet IRM objectives. Exact excavation depths are provided in above referenced CCRs.
-NA: Not Applicable
-Depth of Soil Impacts are provided based on COPCs identified at the time of sampling during the Remedial Investigation. Depths do not define the nature and extent of contamination which are presented in Section 6.
-Lateral and vertical delineation of impacts observed are provided by Site Areas, which encompass the above AOCs, on Appendix S
-Co-located SSDS indicates that the AOC is located within or overlaps the footprint of an SSDS. This designation does not imply that the SSDS provides complete coverage of the AOC
"-" Not Applicable

DRAFT

TABLE 2-1
2018 SVIA Sampling Locations and Rationale

Former Sperry Remington – North Portion #c808022
Elmira, New York

Location	Sample Types	Rationale
Room 127 Gym Cafeteria K-Wing	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr) 1 liter SSDS Stack Sample (2 grabs/stack corresponding to IA sampling periods)	Evaluate SSDS impact on indoor air at representative locations. Evaluate role of HVAC operation on indoor air concentrations.
Room 100	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr)	Evaluate role of HVAC operation on indoor air concentrations in Unmitigated Areas where TCE was previously detected.
Room 104 Room 138 A	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr)	Elevated Freon in Sub-slab. Evaluate role of HVAC operation on indoor air concentrations.
Room 139 Near SV-WS Room 145 Near SV NR	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr)	Evaluate role of HVAC operation on indoor air concentrations at locations with ~neutral cross-slab differential pressure.
Room 103 Room 168	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr) SS with HVAC in Unoccupied mode (grab)	Evaluate role of HVAC operation on indoor air concentrations at locations with open cracks (Room 103) and sealed cracks (Room 168).
Room 133 Room 109	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr) SS with HVAC in Unoccupied mode (grab)	Confirm extent of F Wing TCE impacts.
Room 120 Room 122	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr) SS with HVAC in Unoccupied mode (grab)	Reevaluate locations with elevated TCE reporting limit in sub-slab samples collected by Geosyntec in July 2014.
Room 151A (Subslab) Room 149 Indoor Air	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr) SS with HVAC in Unoccupied mode (grab) Two Summas – HVS Grab	Evaluate VI potential in area with elevated TCE in sub-slab concentrations collected by NYSDEC & NYSDOH in August 2000. Because Room 151A is not frequently occupied, IA sampling will take place in classroom 149 which is next door.
Room 148 Room 135	IA with HVAC in Occupied Mode (8 hr) and IA with HVAC in Unoccupied mode (8 hr) SS with HVAC in Unoccupied mode (grab) Two Summas – HVS Grab	Evaluate VI potential in area not previously evaluated.
F Wing Rooftop K Wing Rooftop	OA with HVAC in Occupied Mode (8 hr) OA with HVAC in Unoccupied mode (8 hr)	Characterize the potential influence of background ambient air sources.

DRAFT

Notes:

hr = hour; HVAC = heating, ventilation, and air conditioning; HVS = high volume sampling; IA = indoor air; NYSDEC = New York State Department of Environmental Conservation; NYSDOH = New York State Department of Health; OA = outdoor air; SS = sub-slab; SSDS = sub-slab depressurization system. TCE = trichloroethene; VI = vapor intrusion.

Parameters Sampled: Volatile organic compounds were analyzed by U.S. EPA Method TO-15

Air samples were collected in 6-liter Summa® canisters equipped with calibrated flow controllers at an approximate flow rate of 12.5 mL/min over an 8- to 10-hour sampling period.

Sub-slab vapor samples were collected from temporary points. The sub-slab sampling points were installed by Geosyntec as 5/8-inch diameter holes and advanced to a point approximately six (6) inches below the slab. Sub-slab vapor samples were collected in 1-liter Summa® canisters equipped with calibrated flow controllers at an approximate flow rate of 200 mL/min for a nominal duration of 5 minutes.

TABLE 2-2
Differential Pressure Monitoring Points

Former Sperry Remington – North Portion #c808022
Elmira, New York

Differential Pressure Monitoring Points	
Location	**Type**
Room 127	Permanent
Gymnasium (SV Gym West)	Permanent
Cafeteria Addition (MAG-NW1)	Permanent
Cafeteria Retrofit (Mag-SE1)	Permanent
K Wing (K04 Stack -Un) (SV K04-Occ)	Permanent
Rm 100 (SV-LIB)	Permanent
Rm 139 (Near SV-WS)	Permanent
Rm 145 (Near SV-NR)	Temporary
Rm 103	Temporary
Rm 168	Temporary
Rm 133	Temporary
Rm 109	Temporary
Rm 120	Temporary
Rm 122	Temporary
Rm 151 A (SV-151 A)	Permanent
Rm 148	Temporary
Rm 135	Temporary

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	0 - 0.5 ft	856.23	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	2 - 3 ft	856.23	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	0 - 0.5 ft	854.04	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	1 - 4 ft	854.04	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	0 - 0.5 ft	856.73	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	1 - 2 ft	856.73	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	0 - 0.5 ft	857.03	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	5 - 6 ft	857.03	--	--	--	X	X	X	X	-
Football Field	SSHS-B15	B23454	5/10/2000	4 - 5 ft	856.90	--	--	--	X	X	X	X	-
Football Field	SSHS-B15	B23455	5/10/2000	0 - 0.5 ft	856.90	--	--	--	X	X	X	X	-
Football Field	SSHS-SS1	B23456	5/10/2000	0 - 0.5 ft	856.57	--	--	--	X	X	X	X	-
Football Field	SSHS-SS2	B23458	5/10/2000	0 - 0.5 ft	856.23	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	0 - 0.5 ft	851.17	--	--	--	X	X	X	X	-
Football Field	SSHS-B6	B23486	5/11/2000	1 - 3 ft	855.49	--	--	--	X	X	X	X	-
Football Field	SSHS-B9	B23482	5/11/2000	2 - 3 ft	855.34	-	-	-	X	X	X	X	-
Football Field	SSHS-SS4	B23483	5/11/2000	0 - 0.5 ft		--	--	--	X	X	X	X	-
Football Field	SSHS-B2	B23488	5/12/2000	1 - 2 ft	855.22	--	--	--	X	X	X	X	-
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	4 - 8 ft	853.27	-	-	-	X	-	-	-	-
Football Field	SSHS-FB1	B23493	6/29/2000	0.5 - 2 ft	857.00	--	--	--	X	X	X	X	-
Football Field	SSHS-FB1	B23495	6/29/2000	16 - 18 ft	857.00	855.82	-1.18	14.82-16.82 ft	X	X	X	X	-
Football Field	SSHS-FB1	B23494	6/29/2000	6 - 8 ft	857.00	855.82	-1.18	4.82-6.82 ft	X	X	X	X	-
Football Field	SSHS-FB2	B23496	6/29/2000	0.5 - 1 ft	856.72	-	-	-	X	X	X	X	-
Football Field	SSHS-FB3	B23497	6/29/2000	3 - 4 ft	856.72	--	--	--	X	X	X	X	-
Football Field	SSHS-FB4	B23498	6/29/2000	3 - 4 ft	856.18	-	-	-	X	X	X	X	-
Football Field	SSHS-FB5	B23499	6/29/2000	2 - 4 ft	855.33	-	-	-	X	X	X	X	-
Football Field	SSHS-FB5	B23400	6/29/2000	6 - 8 ft	855.33	-	-	-	X	X	X	X	-
Football Field	SSHS-FB6	B23402	6/29/2000	17 - 19 ft	856.63	855.63	-1.00	16.00-18.00 ft	X	X	X	X	-
Football Field	SSHS-FB6	B23401	6/29/2000	1 - 2 ft	856.63	--	--	--	X	X	X	X	-
Football Field	SSHS-FB7	B23403	6/29/2000	1 - 3 ft	856.66	--	--	--	X	X	X	X	-
Football Field	SSHS-FB8	B23404	6/29/2000	1 - 3 ft	856.63	--	--	--	X	X	X	X	-
Football Field	SSHS-FB8	B23405	6/29/2000	4 - 6 ft	856.63	--	--	--	X	X	X	X	-
Football Field	SSHS-FB9	B23406	6/29/2000	1 - 2 ft	855.29	--	--	--	X	X	X	X	-
Football Field	SSHS-B15	B23405T2	7/11/2000	0.75 - 1 ft	856.90	--	--	--	X	-	X	X	-
Football Field	SSHS-B15	B23408T2	7/11/2000	0 - 0.5 ft	856.90	--	--	--	-	-	-	X	-
Football Field	SSHS-SS1	B23406T2	7/11/2000	0 - 0.5 ft	856.57	--	--	--	-	-	-	X	-
Football Field	SSHS-SS2	B23407T2	7/11/2000	0 - 0.5 ft	856.23	--	--	--	-	-	-	X	-
Football Field	SSHS-B15	B23405T2-1	7/27/2000	0 - 0.5 ft	856.90	--	--	--	-	-	-	X	-
Football Field	SSHS-B15	B23404T2-1	7/27/2000	1 - 1.5 ft	856.90	--	--	--	X	-	X	X	-
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	0 - 0.5 ft	856.57	--	--	--	-	-	-	X	-
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	0 - 0.5 ft	856.23	--	--	--	-	-	-	X	-
Football Field	SSHS-FB5	B23403T3	8/14/2000	0 - 0.25 ft	855.33	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5	B23407T3	8/14/2000	1 - 1.5 ft	855.33	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	0 - 0.5 ft	855.33	--	--	--	-	-	-	X	-
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	0 - 0.5 ft	855.33	--	--	--	-	-	-	X	-
Football Field	SSHS-FB6	B23406T3	8/14/2000	1 - 1.5 ft	856.63	--	--	--	-	-	X	X	-
Football Field	SSHS-FB6	B23402T3	8/14/2000	0 - 0.5 ft	856.63	--	--	--	-	-	X	X	-
Football Field	SSHS-FB7	B23405T3	8/14/2000	1.5 - 2 ft	856.66	--	--	--	X	-	-	-	-
Football Field	SSHS-FB7	B23401T3	8/14/2000	0 - 0.5 ft	856.66	--	--	--	X	-	-	-	-
Northern Athletic Field	SSHS-B36	_12 Sep 00B36_-	9/12/2000	0 - 0.5 ft	856.63	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B36	_12 Sep 00B36_0.5-2.5	9/12/2000	0.5 - 2.5 ft	856.63	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_-	9/12/2000	0 - 0.5 ft	856.46	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_0.5-2.5	9/12/2000	0.5 - 2.5 ft	856.46	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_8-10	9/12/2000	8 - 10 ft	856.46	855.88	-0.57	7.42-9.43 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_-	9/12/2000	0 - 0.5 ft	856.64	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_1-4.5	9/12/2000	0.5 - 5 ft	856.64	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_-	9/12/2000	0 - 0.5 ft	856.78	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_0.5-2.5	9/12/2000	0.5 - 2.5 ft	856.78	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B40	_12 Sep 00B40_0.5-2.5	9/12/2000	0.5 - 2.5 ft	856.91	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B40	_12 Sep 00B40_-	9/12/2000	0 - 0.5 ft	856.91	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B41	B41	9/12/2000	0 - 0.5 ft	857.21	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	0.5 - 2.5 ft	857.21	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B42	B42	9/12/2000	0 - 0.5 ft	856.22	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	0.5 - 2.5 ft	856.22	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B43	B43	9/12/2000	0 - 0.5 ft	856.12	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	0.5 - 2.5 ft	856.12	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-SS10	_12 Sep 00SS10_-	9/12/2000	0 - 0.5 ft	856.05	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-SS11	_12 Sep 00SS11_-	9/12/2000	0 - 0.5 ft	855.98	--	--	--	X	X	X	X	-
Football Field	SSHS-SS5	SS5	9/12/2000	0 - 0.5 ft	856.43	--	--	--	X	X	X	X	-
Football Field	SSHS-SS6	SS6	9/12/2000	0 - 0.5 ft	856.00	--	--	--	X	X	X	X	-
Football Field	SSHS-SS7	SS7	9/12/2000	0 - 0.5 ft	857.07	--	--	--	X	X	X	X	-
Football Field	SSHS-SS8	SS8	9/12/2000	0 - 0.5 ft	856.32	--	--	--	X	X	X	X	-
Football Field	SSHS-SS9	SS9	9/12/2000	0 - 0.5 ft	856.01	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B44	B44	9/13/2000	0 - 0.5 ft	856.39	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	0.5 - 2.5 ft	856.39	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B45	B45	9/13/2000	0 - 0.5 ft	857.89	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	0.5 - 2.5 ft	857.89	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	8 - 10 ft	858.24	858.17	-0.07	7.93-9.93 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B46	B46	9/13/2000	0 - 0.5 ft	858.24	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	0.5 - 2.5 ft	858.24	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	3 - 5 ft	856.71	856.92	0.21	3.21-5.21 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B47	B47	9/13/2000	0 - 0.5 ft	856.71	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	0.5 - 2.5 ft	855.11	855.12	0.01	0.51-2.51 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B48	B48	9/13/2000	0 - 0.5 ft	855.11	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_-	9/13/2000	0 - 0.5 ft	854.58	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_0.5-2.5	9/13/2000	0.5 - 2.5 ft	854.58	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_4-7	9/13/2000	4 - 7 ft	854.58	857.45	2.87	6.87-9.87 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_-	9/13/2000	0 - 0.5 ft	854.29	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_0.5-2.5	9/13/2000	0.5 - 2.5 ft	854.29	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_-	9/13/2000	0 - 0.5 ft	855.37	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_0.5-2.5	9/13/2000	0.5 - 2.5 ft	855.37	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_-	9/13/2000	0 - 0.5 ft	855.33	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_0.5-2.5	9/13/2000	0.5 - 2.5 ft	855.33	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_4-6	9/13/2000	4 - 6 ft	855.33	--	--	--	X	X	X	X	-
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	0.5 - 2.5 ft	852.39	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B55	B55	9/13/2000	0 - 0.5 ft	852.39	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B56	B56	9/13/2000	0 - 0.5 ft	852.85	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	0.5 - 2.5 ft	852.85	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	0.5 - 2.5 ft	852.42	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B57	B57	9/13/2000	0 - 0.5	852.42	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B58	B58	9/13/2000	0 - 0.5 ft	852.33	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	0.5 - 2.5 ft	852.33	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B59	B59	9/13/2000	0 - 0.5 ft	852.46	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	0.5 - 2.5 ft	852.46	-	-	-	X	X	X	X	-
EHS Building	SSHS-B4S	B4-C1-Composite	7/25/2007	0.5 - 2 ft	-	-	-	0.5 - 2 ft	X	X	-	-	-
EHS Building	SSHS-B4S	B4-C2-Composite	7/25/2007	2 - 2.9 ft	-	-	-	2 - 2.9 ft	X	X	-	-	-
EHS Building	SSHS-B3S	B3-C1-Composite	7/25/2007	0.5 - 2 ft	855.70	855.70	0.00	0.5 - 2 ft	X	X	-	-	-
EHS Building	SSHS-B3S	B3-C2-Composite	7/25/2007	2 - 2.9 ft	855.70	-	-	2 - 2.9 ft	X	X	-	-	-
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	0 - 2.5 ft	855.75	-	-	0 - 2.5 ft	X	X	X	X	-
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	0 - 2.6 ft	-	-	-	0 - 2.6 ft	X	X	-	-	-
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	0 - 2.6 ft	-	-	-	0 - 2.6 ft	X	X	-	-	-
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	0 - 2.6 ft	-	-	-	0 - 2.6 ft	X	X	-	-	-
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	0 - 1.8 ft	-	-	-	0 - 1.8 ft	X	X	-	-	-
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	0 - 2 ft	-	-	-	0 - 2 ft	X	X	-	-	-
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	0 - 2 ft	855.50	-	-	0 - 2 ft	X	X	X	X	-
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	0 - 2.5 ft	855.52	-	-	0 - 2.5 ft	X	X	X	X	-
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	0 - 2.5 ft	855.59	-	-	0 - 2.5 ft	X	X	X	X	-
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	0 - 2 ft	855.51	-	-	0 - 2 ft	X	X	X	X	-
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	0 - 2.2 ft	856.03	-	-	0 - 2.2 ft	X	X	X	X	-
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	0 - 2.2 ft	855.45	-	-	0 - 2.2 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B46-A	SSHS-B46-A-SS	7/21/2014	0 - 0.17 ft	858.26	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	7/21/2014	0 - 0.17 ft	856.74	-	-	-	-	-	X	-	-
Football Field	SSHS-FB5-A	SSHS-FB5-A-SS	7/21/2014	0 - 0.17 ft	855.47	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-1.5	7/21/2014	1.5 - 1.5 ft	855.47	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-2.5	7/21/2014	2.5 - 2.5 ft	855.47	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-B	SSHS-FB5-B-SS	7/21/2014	0 - 0.17 ft	855.39	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-1.5	7/21/2014	1.5 - 1.5 ft	855.39	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-2.5	7/21/2014	2.5 - 2.5 ft	855.39	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-C	SSHS-FB5-C-SS	7/21/2014	0 - 0.17 ft	855.97	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-1.5	7/21/2014	1.5 - 1.5 ft	855.97	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-2.5	7/21/2014	2.5 - 2.5 ft	855.97	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-D	SSHS-FB5-D-SS	7/21/2014	0 - 0.17 ft	855.49	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-1.5	7/21/2014	1.5 - 1.5 ft	855.49	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-2.5	7/21/2014	2.5 - 2.5 ft	855.49	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-E	SSHS-FB5-E-SS	7/21/2014	0 - 0.17 ft	855.42	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-1.5	7/21/2014	1.5 - 1.5 ft	855.42	-	-	-	-	-	-	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-FB5-E	SSHS-FB5-DUP1	7/21/2014	2.5 - 2.5 ft	855.42	-	-	-	-	-	-	X	-
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-2.5	7/21/2014	2.5 - 2.5 ft	855.42	-	-	-	-	-	-	X	-
Football Field	SSHS-FB7-A	SSHS-FB7-A-SUB-1-2	7/21/2014	1 - 2 ft	856.41	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-A	SSHS-FB7-A-SS	7/21/2014	0 - 0.17 ft	856.41	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-A	SSHS-FB7-A-SUB-0.17-1	7/21/2014	0.17 - 1 ft	856.41	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-A	SSHS-FB7-A-SUB-2-3	7/21/2014	2 - 3 ft	856.41	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-B	SSHS-FB7-B-SUB-1-2	7/21/2014	1 - 2 ft	856.19	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-B	SSHS-FB7-B-SS	7/21/2014	0 - 0.17 ft	856.19	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-B	SSHS-FB7-B-SUB-0.17-1	7/21/2014	0.17 - 1 ft	856.19	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-B	SSHS-FB7-B-SUB-2-3	7/21/2014	2 - 3 ft	856.19	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-C	SSHS-FB7-C-SUB-1-2	7/21/2014	1 - 2 ft	856.56	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-C	SSHS-FB7-C-SS	7/21/2014	0 - 0.17 ft	856.56	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-C	SSHS-FB7-C-SUB-0.17-1	7/21/2014	0.17 - 1 ft	856.56	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-C	SSHS-FB7-DUP4	7/21/2014	0.17 - 1 ft	856.56	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-C	SSHS-FB7-C-SUB-2-3	7/21/2014	2 - 3 ft	856.56	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-D	SSHS-FB7-D-SUB-2-3	7/21/2014	2 - 3 ft	856.62	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-D	SSHS-FB7-DUP2	7/21/2014	2 - 3 ft	856.62	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-D	SSHS-FB7-D-SS	7/21/2014	0 - 0.17 ft	856.62	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-D	SSHS-FB7-D-SUB-0.17-1	7/21/2014	0.17 - 1 ft	856.62	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-D	SSHS-FB7-D-SUB-1-2	7/21/2014	1 - 2 ft	856.62	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-E	SSHS-FB7-E-SUB-1-2	7/21/2014	1 - 2 ft	856.28	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-E	SSHS-FB7-DUP3	7/21/2014	0 - 0.17 ft	856.28	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-E	SSHS-FB7-E-SS	7/21/2014	0 - 0.17 ft	856.28	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-E	SSHS-FB7-E-SUB-0.17-1	7/21/2014	0.17 - 1 ft	856.28	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-E	SSHS-FB7-E-SUB-2-3	7/21/2014	2 - 3 ft	856.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-A	SSHS-B15-A-SS	7/22/2014	0 - 0.17 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-A	SSHS-DUP7	7/22/2014	0 - 0.17 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-A	SSHS-B15-A-0.17-1	7/22/2014	0.17 - 1 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-A	SSHS-B15-A-1-2	7/22/2014	1 - 2 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-A	SSHS-B15-A-2-3	7/22/2014	2 - 3 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-B	SSHS-B15-B-SS	7/22/2014	0 - 0.17 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-B	SSHS-B15-B-0.17-1	7/22/2014	0.17 - 1 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-B	SSHS-B15-B-1-2	7/22/2014	1 - 2 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-B	SSHS-B15-B-2-3	7/22/2014	2 - 3 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-B	SSHS-B15-DUP8	7/22/2014	2 - 3 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-C	SSHS-B15-C-2-3	7/22/2014	2 - 3 ft	856.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-C	SSHS-B15-C-SS	7/22/2014	0 - 0.17 ft	856.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-C	SSHS-B15-C-0.17-1	7/22/2014	0.17 - 1 ft	856.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-C	SSHS-B15-C-1-2	7/22/2014	1 - 2 ft	856.91	-	-	-	X	-	-	-	-
EHS Building	SSHS-B4SS-A	SSHS-B4SS-A-SS	7/22/2014	0 - 0.17 ft	855.50	-	-	0 - 0.17 ft	X	-	-	-	-
Football Field	SSHS-FB10	SSHS-FB10-A-SS	7/22/2014	0 - 0.17 ft	855.71	-	-	-	X	-	X	-	-
Football Field	SSHS-FB11	SSHS-FB11-A-SS	7/22/2014	0 - 0.17 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-FB1-A	SSHS-FB1-A-SS	7/22/2014	0 - 0.17 ft	856.72	-	-	-	X	-	-	-	-
Football Field	SSHS-FB2-A	SSHS-FB2-A-SS	7/22/2014	0 - 0.17 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-FB3-A	SSHS-FB3-A-SS	7/22/2014	0 - 0.17 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-FB4-A	SSHS-FB4-A-SS	7/22/2014	0 - 0.17 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-FB6-A	SSHS-DUP5	7/22/2014	0 - 0.17 ft	856.14	-	-	-	X	-	X	-	-
Football Field	SSHS-FB6-A	SSHS-FB6-A-SS	7/22/2014	0 - 0.17 ft	856.14	-	-	-	X	-	X	-	-
Football Field	SSHS-FB9-A	SSHS-FB9-A-SS	7/22/2014	0 - 0.17 ft	854.80	-	-	-	X	-	X	-	-
Football Field	SSHS-SS12	SSHS-SS12-DUP6	7/22/2014	1 - 2 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-A	SSHS-SS12-A-1-2	7/22/2014	1 - 2 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-A	SSHS-SS12-A-2-3	7/22/2014	2 - 3 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-A	SSHS-SS12-A-SS	7/22/2014	0 - 0.17 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-A	SSHS-SS12-A-0.17-1	7/22/2014	0.17 - 1 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-B	SSHS-SS12-B-2-3	7/22/2014	2 - 3 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-B	SSHS-SS12-B-SS	7/22/2014	0 - 0.17 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-B	SSHS-SS12-B-0.17-1	7/22/2014	0.17 - 1 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-B	SSHS-SS12-B-1-2	7/22/2014	1 - 2 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-C	SSHS-SS12-C-2-3	7/22/2014	2 - 3 ft	855.81	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-C	SSHS-SS12-C-1-2	7/22/2014	1 - 2 ft	855.81	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-C	SSHS-SS12-C-SS	7/22/2014	0 - 0.17 ft	855.81	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-C	SSHS-SS12-C-0.17-1	7/22/2014	0.17 - 1 ft	855.81	-	-	-	X	-	-	-	-
Football Field	SSHS-SS15	SSHS-SS15-SS	7/22/2014	0 - 0.17 ft	857.17	-	-	-	X	-	-	-	-
Football Field	SSHS-SS16	SSHS-SS16-SS	7/22/2014	0 - 0.17 ft	857.27	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	0.17 - 2 ft	856.60	856.60	0.00	0.17 - 2 ft	-	-	-	X	-
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	0.17 - 2 ft	856.60	856.60	0.00	0.17 - 2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	10 - 15 ft	856.60	856.60	0.00	10 - 15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	2 - 6 ft	856.60	856.60	0.00	2 - 6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	6 - 10 ft	856.60	856.60	0.00	6 - 10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	10 - 14.5 ft	854.77	854.77	0.00	10 - 14.5 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	2 - 6 ft	854.77	854.77	0.00	2 - 6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	2 - 6 ft	854.77	854.77	0.00	2 - 6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	6 - 10 ft	854.77	854.77	0.00	6 - 10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	0.17 - 2 ft	855.54	855.54	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	10 - 15 ft	855.54	855.54	0.00	10-15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	10 - 15 ft	855.54	855.54	0.00	10-15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	2 - 6 ft	855.54	855.54	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	6 - 10 ft	855.54	855.54	0.00	6-10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	0.17 - 2 ft	854.20	854.20	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	10 - 15 ft	854.20	854.20	0.00	10-15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	2 - 6 ft	854.20	854.20	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	6 - 10 ft	854.20	854.20	0.00	6-10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	0.17 - 2 ft	855.00	855.00	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	10 - 15 ft	855.00	855.00	0.00	10-15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	2 - 6 ft	855.00	855.00	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	6 - 10 ft	855.00	855.00	0.00	6-10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	0.17 - 2 ft	853.90	853.90	0.00	0.17 - 2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	10 - 15 ft	853.90	853.90	0.00	10 - 15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	2 - 6 ft	853.90	853.90	0.00	2 - 6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	2 - 6 ft	853.90	853.90	0.00	2 - 6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	6 - 10 ft	853.90	853.90	0.00	6 - 10 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	12 - 15.5 ft	852.95	852.89	-0.06	11.94-15.44 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	3 - 6 ft	852.95	852.89	-0.06	2.94-5.94 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	3 - 6 ft	852.95	852.89	-0.06	2.94-5.94 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	8 - 10 ft	852.95	852.89	-0.06	7.94-9.94 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	0 - 2 ft	852.95	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	10 - 12 ft	851.65	851.60	-0.05	9.95-11.95 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	6 - 9 ft	851.65	851.60	-0.05	5.95-8.95 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	0 - 2 ft	851.65	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	4 - 6 ft	851.65	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	4 - 6 ft	850.41	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	10 - 12 ft	850.41	850.12	-0.29	9.71-11.71 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	8 - 10 ft	850.41	850.12	-0.29	7.71-9.71 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	0 - 2 ft	850.41	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	2 - 4 ft	851.94	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	6 - 8 ft	851.94	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	0 - 2 ft	851.94	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	0 - 2 ft	850.45	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	2 - 6 ft	850.45	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	10 - 12 ft	850.45	850.29	-0.16	9.84-11.84 ft	X	X	X	X	-
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	8 - 10 ft	850.45	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	0 - 2 ft	852.07	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	2 - 6 ft	852.07	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	6 - 8 ft	852.07	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	2 - 4 ft	850.53	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	4 - 6 ft	850.53	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	4 - 6 ft	850.53	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	0 - 2 ft	850.53	-	-	-	X	X	X	X	-
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	6 - 10 ft	855.98	-	-	-	X	X	X	X	-
Football Field	SSHS-B70	081514 01:15_SSHS-B70-SS	8/14/2014	0 - 0.17 ft	855.98	-	-	-	X	X	X	X	-
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	0.17 - 2 ft	855.98	-	-	-	X	X	X	X	-
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	10 - 14 ft	855.98	-	-	-	X	X	X	X	-
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	2 - 6 ft	855.98	-	-	-	X	X	X	X	-
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)DL	8/14/2014	6 - 10 ft	855.98	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	0.17 - 2 ft	856.08	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	10 - 15 ft	856.08	856.35	0.27	10.27-15.27 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	2 - 6 ft	856.08	856.35	0.27	2.27-6.27 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	2 - 6 ft	856.08	856.35	0.27	2.27-6.27 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	6 - 10 ft	856.08	856.35	0.27	6.27-10.27 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	0 - 0.17 ft	856.08	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	10 - 15 ft	856.25	857.34	1.09	11.09-16.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	2 - 6 ft	856.25	857.34	1.09	3.09-7.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	6 - 10 ft	856.25	857.34	1.09	7.09-11.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	0 - 0.17 ft	856.25	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	0.17 - 2 ft	856.25	-	-	-	X	X	X	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	0.17 - 2 ft	855.88	857.91	2.03	2.2-4.03 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	10 - 15 ft	855.88	857.91	2.03	12.03-17.03 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	2 - 6 ft	855.88	857.91	2.03	4.03-8.03 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	6 - 10 ft	855.88	857.91	2.03	8.03-12.03 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	6 - 10 ft	855.88	857.91	2.03	8.03-12.03 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	0 - 0.17 ft	855.88	-	-	-	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	0.17 - 2 ft	855.75	855.75	0.00	0.17 - 2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	10 - 15 ft	855.75	855.75	0.00	10 - 15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	2 - 6 ft	855.75	855.75	0.00	2 - 6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	6 - 10 ft	855.75	855.75	0.00	6 - 10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	0.17 - 2 ft	855.92	855.92	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	10 - 13.5 ft	855.92	855.92	0.00	10-13.5 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	2 - 6 ft	855.92	855.92	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	2 - 6 ft	855.92	855.92	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	6 - 10 ft	855.92	855.92	0.00	6-10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	0.17 - 2 ft	854.77	854.77	0.00	0.17 - 2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	0.17 - 2 ft	856.00	856.00	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	10 - 14 ft	856.00	856.00	0.00	10-14 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	2 - 6 ft	856.00	856.00	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	6 - 10 ft	856.00	856.00	0.00	6-10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	6 - 10 ft	856.00	856.00	0.00	6-10 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	0.17 - 2 ft	855.86	855.86	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	10 - 15 ft	855.86	855.86	0.00	10-15 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	2 - 6 ft	855.86	855.86	0.00	2-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	6 - 10 ft	855.86	855.86	0.00	6-10 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	2.5 - 4.5 ft	856.19	856.45	0.26	2.76-4.76 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	6 - 9.5 ft	856.19	856.45	0.26	6.26-9.76 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	6 - 9.5 ft	856.19	856.45	0.26	6.26-9.76 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	0.17 - 2 ft	856.19	-	-	-	X	X	X	X	-
Football Field	SSHS-B236	SSHS-B236-SUB-0-2	7/14/2015	0 - 2 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B238	SSHS-B238-SUB-0-2	7/14/2015	0 - 2 ft	856.59	-	-	-	X	-	-	-	-
Football Field	SSHS-B239	SSHS-B239-SUB-0-2	7/14/2015	0 - 2 ft	857.05	-	-	-	X	-	-	-	-
Football Field	SSHS-B241	SSHS-B241-SUB-0-2	7/14/2015	0 - 2 ft	856.84	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	7/14/2015	0 - 2 ft	856.00	856.42	0.42	0.42 - 2.42 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B286	SSHS-B286-SUB-0-2	7/14/2015	0 - 2 ft	856.40	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B287	SSHS-B287-SUB-0-2	7/14/2015	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B305	SSHS-B305-SS	7/14/2015	0 - 0.17 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B305	SSHS-B305-SUB-0.17-2	7/14/2015	0.17 - 2 ft	855.32	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B40-A	SSHS-B40-A-SUB-0-2	7/14/2015	0 - 2 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B221	SSHS-B221-SUB-2-4	7/15/2015	2 - 4 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B221	SSHS-B221-SUB-6-8	7/15/2015	6 - 8 ft	855.95	855.96	0.01	6.01-8.01 ft	X	-	-	-	-
Football Field	SSHS-B221	SSHS-B221-SUB-0-2	7/15/2015	0 - 2 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B221	SSHS-B221-SUB-4-6	7/15/2015	4 - 6 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B226	SSHS-B226-SUB-2-3	7/15/2015	2 - 3 ft	856.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B226	SSHS-B226-SUB-0-2	7/15/2015	0 - 2 ft	856.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B227	SSHS-B227-SUB-4-6	7/15/2015	4 - 6 ft	856.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B227	SSHS-B227-SUB-0-2	7/15/2015	0 - 2 ft	856.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B227	SSHS-B227-SUB-6-8	7/15/2015	6 - 8 ft	856.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B227	SSHS-B227-SUB-2-4	7/15/2015	2 - 4 ft	856.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B228	SSHS-B228-SUB-2-4	7/15/2015	2 - 4 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B228	SSHS-B228-SUB-4-6	7/15/2015	4 - 6 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B228	SSHS-B228-SUB-0-2	7/15/2015	0 - 2 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B228	PS-FD-#2	7/15/2015	6 - 8 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B228	SSHS-B228-SUB-6-8	7/15/2015	6 - 8 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B229	SSHS-B229-SUB-2-4	7/15/2015	2 - 4 ft	857.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B229	SSHS-B229-SUB-4-6	7/15/2015	4 - 6 ft	857.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B229	PS-FD-#3	7/15/2015	0 - 2 ft	857.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B229	SSHS-B229-SUB-0-2	7/15/2015	0 - 2 ft	857.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B229	SSHS-B229-SUB-6-8	7/15/2015	6 - 8 ft	857.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B241	PS-FD-#1	7/15/2015	0 - 2 ft	856.84	-	-	-	X	-	-	-	-
Football Field	SSHS-FB10-A	SSHS-FB10-A-SUB-0-2	7/15/2015	0 - 2 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-FB6-AA	SSHS-FB6-AA-SUB-0-2	7/15/2015	0 - 2 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-BA	SSHS-FB7-BA-SUB-4-6	7/15/2015	4 - 6 ft	856.25	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-BA	SSHS-FB7-BA-SUB-6-8	7/15/2015	6 - 8 ft	856.25	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-DA	SSHS-FB7-DA-SUB-4-6	7/15/2015	4 - 6 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-FB7-DA	SSHS-FB7-DA-SUB-6-8	7/15/2015	6 - 8 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B216	SSHS-B216-SUB-2-4	7/16/2015	2 - 4 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B216	SSHS-B216-SUB-6-8	7/16/2015	6 - 8 ft	855.82	855.81	-0.01	5.99-7.99 ft	X	-	-	-	-
Football Field	SSHS-B216	SSHS-B216-SUB-0-2	7/16/2015	0 - 2 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B216	SSHS-B216-SUB-4-6	7/16/2015	4 - 6 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B217	SSHS-B217-SUB-0-2	7/16/2015	0 - 2 ft	856.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B217	SSHS-B217-SUB-2-4	7/16/2015	2 - 4 ft	856.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B217	SSHS-B217-SUB-4-6	7/16/2015	4 - 6 ft	856.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B217	SSHS-B217-SUB-6-8	7/16/2015	6 - 8 ft	856.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B218	SSHS-B218-SUB-0-2	7/16/2015	0 - 2 ft	856.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B218	SSHS-B218-SUB-2-4	7/16/2015	2 - 4 ft	856.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B218	PS-FD-#4	7/16/2015	4 - 6 ft	856.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B218	SSHS-B218-SUB-4-6	7/16/2015	4 - 6 ft	856.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B218	SSHS-B218-SUB-6-8	7/16/2015	6 - 8 ft	856.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B222	SSHS-B222-SUB-0-2	7/16/2015	0 - 2 ft	856.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B222	SSHS-B222-SUB-2-4	7/16/2015	2 - 4 ft	856.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B222	SSHS-B222-SUB-4-6	7/16/2015	4 - 6 ft	856.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B222	SSHS-B222-SUB-6-8	7/16/2015	6 - 8 ft	856.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B278	SSHS-B278-SUB-4-6	7/16/2015	4 - 6 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B278	SSHS-B278-SUB-6-8	7/16/2015	6 - 8 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B278	SSHS-B278-SUB-0-2	7/16/2015	0 - 2 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B278	SSHS-B278-SUB-2-4	7/16/2015	2 - 4 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B280	SSHS-B280-SUB-4-6	7/16/2015	4 - 6 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B280	PS-FD-#6	7/16/2015	0 - 2 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B280	SSHS-B280-SUB-0-2	7/16/2015	0 - 2 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B280	SSHS-B280-SUB-2-4	7/16/2015	2 - 4 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B280	SSHS-B280-SUB-6-8	7/16/2015	6 - 8 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B283	SSHS-B283-SUB-0-2	7/16/2015	0 - 2 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B283	PS-FD-#5	7/16/2015	4 - 6 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B283	SSHS-B283-SUB-4-6	7/16/2015	4 - 6 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B283	SSHS-B283-SUB-6-8	7/16/2015	6 - 8 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B283	SSHS-B283-SUB-2-4	7/16/2015	2 - 4 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-FB9-AA	SSHS-FB9-AA-SS	7/16/2015	0 - 0.17 ft	854.80	-	-	-	X	-	-	-	-
Football Field	SSHS-FB9-AA	SSHS-FB9-AA-SUB-0.17-0.5	7/16/2015	0.17 - 0.5 ft	854.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B261	SSHS-B261-SUB-2-4	7/17/2015	2 - 4 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B261	SSHS-B261-SUB-0-2	7/17/2015	0 - 2 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B261	SSHS-B261-SUB-4-6	7/17/2015	4 - 6 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B261	SSHS-B261-SUB-6-8	7/17/2015	6 - 8 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B264	SSHS-B264-SUB-2-3	7/17/2015	2 - 3 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B264	SSHS-B264-SUB-0-2	7/17/2015	0 - 2 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B265	SSHS-B265-SUB-0-2	7/17/2015	0 - 2 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B265	SSHS-B265-SUB-2-4	7/17/2015	2 - 4 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B265	SSHS-B265-SUB-4-6	7/17/2015	4 - 6 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B265	SSHS-B265-SUB-6-8	7/17/2015	6 - 8 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B266	SSHS-B266-SUB-4-6	7/17/2015	4 - 6 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B266	SSHS-B266-SUB-6-8	7/17/2015	6 - 8 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B266	SSHS-B266-SUB-2-4	7/17/2015	2 - 4 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B266	PS-FD-#8	7/17/2015	0 - 2 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B266	SSHS-B266-SUB-0-2	7/17/2015	0 - 2 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B269	PS-FD-#9	7/17/2015	0 - 2 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B269	SSHS-B269-SUB-0-2	7/17/2015	0 - 2 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B269	SSHS-B269-SUB-2-3	7/17/2015	2 - 3 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B270	SSHS-B270-SUB-2-4	7/17/2015	2 - 4 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B270	SSHS-B270-SUB-4-5	7/17/2015	4 - 5 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B270	SSHS-B270-SUB-0-2	7/17/2015	0 - 2 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B271	SSHS-B271-SUB-4-6	7/17/2015	4 - 6 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B271	SSHS-B271-SUB-0-2	7/17/2015	0 - 2 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B271	SSHS-B271-SUB-2-4	7/17/2015	2 - 4 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B271	SSHS-B271-SUB-6-8	7/17/2015	6 - 8 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B275	SSHS-B275-SUB-2-4	7/17/2015	2 - 4 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B275	SSHS-B275-SUB-4-5.5	7/17/2015	4 - 5.5 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B275	SSHS-B275-SUB-0-2	7/17/2015	0 - 2 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B281	PA-FD-#7	7/17/2015	4 - 6 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B281	SSHS-B281-SUB-4-6	7/17/2015	4 - 6 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B281	SSHS-B281-SUB-0-2	7/17/2015	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B281	SSHS-B281-SUB-2-4	7/17/2015	2 - 4 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B281	SSHS-B281-SUB-6-8	7/17/2015	6 - 8 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-CA	SSHS-SS12-CA-SUB-4-6	7/17/2015	4 - 6 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-CA	PS-FD-#10	7/17/2015	6 - 8 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-SS12-CA	SSHS-SS12-CA-SUB-6-8	7/17/2015	6 - 8 ft	855.83	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-2-4	7/20/2015	2 - 4 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-0-2	7/20/2015	0 - 2 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-4-6	7/20/2015	4 - 6 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-6-8	7/20/2015	6 - 8 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B117	PS-FD-#20	7/20/2015	4 - 6 ft	850.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-4-6	7/20/2015	4 - 6 ft	850.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-6-8	7/20/2015	6 - 8 ft	850.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-0-2	7/20/2015	0 - 2 ft	850.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-2-4	7/20/2015	2 - 4 ft	850.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B118	PS-FD-#12	7/20/2015	0 - 2 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-0-2	7/20/2015	0 - 2 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-2-4	7/20/2015	2 - 4 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-4-6	7/20/2015	4 - 6 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B118	PS-FD-#13	7/20/2015	6 - 8 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-6-8	7/20/2015	6 - 8 ft	850.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-AA	SSHS-B15-AA-SUB-4-6	7/20/2015	4 - 6 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B15-AA	SSHS-B15-AA-SUB-6-8	7/20/2015	6 - 8 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B248	PS-FD-#11	7/20/2015	0 - 2 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B248	SSHS-B248-SUB-0-2	7/20/2015	0 - 2 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B248	SSHS-B248-SUB-2-4	7/20/2015	2 - 4 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B248	SSHS-B248-SUB-4-6	7/20/2015	4 - 6 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B248	SSHS-B248-SUB-6-8	7/20/2015	6 - 8 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B251	SSHS-B251-SUB-0-2	7/20/2015	0 - 2 ft	856.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B251	SSHS-B251-SUB-2-3	7/20/2015	2 - 3 ft	856.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B252	SSHS-B252-SUB-0-2	7/20/2015	0 - 2 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B252	SSHS-B252-SUB-2-4	7/20/2015	2 - 4 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B252	SSHS-B252-SUB-4-6	7/20/2015	4 - 6 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B252	SSHS-B252-SUB-6-8	7/20/2015	6 - 8 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B256	SSHS-B256-SUB-0-2	7/20/2015	0 - 2 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B256	SSHS-B256-SUB-4-6	7/20/2015	4 - 6 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B256	SSHS-B256-SUB-2-4	7/20/2015	2 - 4 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B256	SSHS-B256-SUB-6-8	7/20/2015	6 - 8 ft	856.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-2-4	7/21/2015	2 - 4 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-0-2	7/21/2015	0 - 2 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-4-6	7/21/2015	4 - 6 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-6-8	7/21/2015	6 - 8 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-2-4	7/21/2015	2 - 4 ft	850.42	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B110	PS-FD-#14	7/21/2015	4 - 6 ft	850.42	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-4-6	7/21/2015	4 - 6 ft	850.42	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-0-2	7/21/2015	0 - 2 ft	850.42	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-6-8	7/21/2015	6 - 8 ft	850.42	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B111	PS-FD-#15	7/21/2015	4 - 6 ft	850.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-4-6	7/21/2015	4 - 6 ft	850.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-0-2	7/21/2015	0 - 2 ft	850.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-2-4	7/21/2015	2 - 4 ft	850.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-6-8	7/21/2015	6 - 8 ft	850.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-0-2	7/21/2015	0 - 2 ft	850.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-2-4	7/21/2015	2 - 4 ft	850.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-4-6	7/21/2015	4 - 6 ft	850.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-6-8	7/21/2015	6 - 8 ft	850.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-2-4	7/21/2015	2 - 4 ft	850.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-4-6	7/21/2015	4 - 6 ft	850.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-0-2	7/21/2015	0 - 2 ft	850.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-6-8	7/21/2015	6 - 8 ft	850.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-0-2	7/21/2015	0 - 2 ft	850.98	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-2-4	7/21/2015	2 - 4 ft	850.98	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-4-6	7/21/2015	4 - 6 ft	850.98	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-6-8	7/21/2015	6 - 8 ft	850.98	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B130	PS-FD-#16	7/21/2015	2 - 4 ft	851.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-2-4	7/21/2015	2 - 4 ft	851.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-0-2	7/21/2015	0 - 2 ft	851.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-4-6	7/21/2015	4 - 6 ft	851.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-6-8	7/21/2015	6 - 8 ft	851.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-0-2	7/21/2015	0 - 2 ft	851.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-2-4	7/21/2015	2 - 4 ft	851.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B141	PS-FD-#18	7/21/2015	4 - 6 ft	851.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-4-6	7/21/2015	4 - 6 ft	851.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-6-8	7/21/2015	6 - 8 ft	851.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-0-2	7/21/2015	0 - 2 ft	851.86	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-2-4	7/21/2015	2 - 4 ft	851.86	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-4-6	7/21/2015	4 - 6 ft	851.86	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-6-8	7/21/2015	6 - 8 ft	851.86	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B143	SSHS-B143-SUB-0-1	7/21/2015	0 - 1 ft	852.07	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-0-2	7/21/2015	0 - 2 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-2-4	7/21/2015	2 - 4 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-4-6	7/21/2015	4 - 6 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B144	PS-FD-#17	7/21/2015	6 - 8 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-6-8	7/21/2015	6 - 8 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-6-8	7/21/2015	6 - 8 ft	852.27	852.59	0.32	6.32-8.32 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-2-4	7/21/2015	2 - 4 ft	852.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B149	PS-FD-#19	7/21/2015	0 - 2 ft	852.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-0-2	7/21/2015	0 - 2 ft	852.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-4-6	7/21/2015	4 - 6 ft	852.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-2-4	7/21/2015	2 - 4 ft	852.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-4-6	7/21/2015	4 - 6 ft	852.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-0-2	7/21/2015	0 - 2 ft	852.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-6-8	7/21/2015	6 - 8 ft	852.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B160	SSHS-B160-SUB-0-1.5	7/21/2015	0 - 1.5 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B103	PS-FD-#21	7/22/2015	2 - 4 ft	849.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-2-4	7/22/2015	2 - 4 ft	849.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-0-2	7/22/2015	0 - 2 ft	849.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-4-6	7/22/2015	4 - 6 ft	849.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-6-8	7/22/2015	6 - 8 ft	849.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-0-2	7/22/2015	0 - 2 ft	849.32	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-2-4	7/22/2015	2 - 4 ft	849.32	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-4-6	7/22/2015	4 - 6 ft	849.32	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-6-8	7/22/2015	6 - 8 ft	849.32	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-2-4	7/22/2015	2 - 4 ft	849.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-0-2	7/22/2015	0 - 2 ft	849.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-4-6	7/22/2015	4 - 6 ft	849.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-6-8	7/22/2015	6 - 8 ft	849.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-2-4	7/22/2015	2 - 4 ft	849.39	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-4-6	7/22/2015	4 - 6 ft	849.39	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-0-2	7/22/2015	0 - 2 ft	849.39	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-6-8	7/22/2015	6 - 8 ft	849.39	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-2-4	7/22/2015	2 - 4 ft	849.10	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-4-6	7/22/2015	4 - 6 ft	849.10	849.29	0.19	4.19-6.19 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-6-8	7/22/2015	6 - 8 ft	849.10	849.29	0.19	6.19-8.19 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-0-2	7/22/2015	0 - 2 ft	849.10	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-2-4	7/22/2015	2 - 4 ft	849.57	849.70	0.13	2.13-4.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B108	PS-FD-#22	7/22/2015	4 - 6 ft	849.57	849.70	0.13	4.13-6.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-4-6	7/22/2015	4 - 6 ft	849.57	849.70	0.13	4.13-6.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-6-8	7/22/2015	6 - 8 ft	849.57	849.70	0.13	6.13-8.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-0-2	7/22/2015	0 - 2 ft	849.57	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-4-6	7/22/2015	4 - 6 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-6-7	7/22/2015	6 - 7 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-0-2	7/22/2015	0 - 2 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-2-4	7/22/2015	2 - 4 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B122	PS-FD-#23	7/22/2015	0 - 2 ft	851.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-0-2	7/22/2015	0 - 2 ft	851.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-2-4	7/22/2015	2 - 4 ft	851.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-4-6	7/22/2015	4 - 6 ft	851.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B122	PS-FD-#24	7/22/2015	6 - 7 ft	851.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-6-7	7/22/2015	6 - 7 ft	851.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-2-4	7/22/2015	2 - 4 ft	851.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-4-6	7/22/2015	4 - 6 ft	851.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-0-2	7/22/2015	0 - 2 ft	851.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-6-7	7/22/2015	6 - 7 ft	851.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-6-8	7/22/2015	6 - 8 ft	851.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B146	PS-FD-#25	7/22/2015	4 - 6 ft	851.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-4-6	7/22/2015	4 - 6 ft	851.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-0-2	7/22/2015	0 - 2 ft	851.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-2-4	7/22/2015	2 - 4 ft	851.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B147	PS-FD-#31	7/23/2015	2 - 4 ft	852.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-2-4	7/23/2015	2 - 4 ft	852.20	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-4-6	7/23/2015	4 - 6 ft	852.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-0-2	7/23/2015	0 - 2 ft	852.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-6-8	7/23/2015	6 - 8 ft	852.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-2-4	7/24/2015	2 - 4 ft	851.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-4-6	7/24/2015	4 - 6 ft	851.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-0-2	7/24/2015	0 - 2 ft	851.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B121	PS-FD-#33	7/24/2015	6 - 7 ft	851.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-6-7	7/24/2015	6 - 7 ft	851.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-2-4	7/24/2015	2 - 4 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-0-2	7/24/2015	0 - 2 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-4-6	7/24/2015	4 - 6 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-6-8	7/24/2015	6 - 8 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-2-4	7/24/2015	2 - 4 ft	851.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-0-2	7/24/2015	0 - 2 ft	851.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-4-6	7/24/2015	4 - 6 ft	851.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B145	PS-FD-#32	7/24/2015	6 - 8 ft	851.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-6-8	7/24/2015	6 - 8 ft	851.85	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B288	SSHS-B288-SUB-0-2	7/24/2015	0 - 2 ft	856.22	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B289	SSHS-B289-SUB-0-2	7/24/2015	0 - 2 ft	856.37	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B290	SSHS-B290-SUB-0-2	7/24/2015	0 - 2 ft	856.36	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B295	SSHS-B295-SS	7/24/2015	0 - 0.17 ft	852.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B135	SSHS-B135-SUB-0-2	7/27/2015	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B138	SSHS-B138-SUB-0-2	7/27/2015	0 - 2 ft	855.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B150	SSHS-B150-SUB-0-2	7/27/2015	0 - 2 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B150	SSHS-B150-SUB-2-4	7/27/2015	2 - 4 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B150	SSHS-B150-SUB-4-6	7/27/2015	4 - 6 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B164	CS-FD-#1	7/27/2015	0 - 2 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B164	SSHS-B164-SUB-0-2	7/27/2015	0 - 2 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B164	SSHS-B164-SUB-2-4	7/27/2015	2 - 4 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B165	SSHS-B165-SUB-0-2	7/27/2015	0 - 2 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B166	SSHS-B166-SUB-0-2	7/27/2015	0 - 2 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B168	SSHS-B168-SUB-2-4	7/27/2015	2 - 4 ft	855.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B168	SSHS-B168-SUB-0-2	7/27/2015	0 - 2 ft	855.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B168	SSHS-B168-SUB-4-6	7/27/2015	4 - 6 ft	855.64	-	-	-	X	-	-	-	-
Football Field	SSHS-B170	SSHS-B170-SUB-0-2	7/27/2015	0 - 2 ft	856.27	-	-	-	X	-	-	-	-
Football Field	SSHS-B231	CS-FD-#3	7/27/2015	2 - 4 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B231	SSHS-B231-SUB-2-4	7/27/2015	2 - 4 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B231	SSHS-B231-SUB-0-2	7/27/2015	0 - 2 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B231	SSHS-B231-SUB-4-6	7/27/2015	4 - 6 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B231	CS-FD-#4	7/27/2015	6 - 8 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B231	SSHS-B231-SUB-6-8	7/27/2015	6 - 8 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B232	SSHS-B232-SUB-2-4	7/27/2015	2 - 4 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B232	SSHS-B232-SUB-6-8	7/27/2015	6 - 8 ft	856.44	856.44	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B232	SSHS-B232-SUB-8-10	7/27/2015	8 - 10 ft	856.44	856.44	0.00	8-10 ft	X	-	-	-	-
Football Field	SSHS-B232	SSHS-B232-SUB-0-2	7/27/2015	0 - 2 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B232	CS-FD-#2	7/27/2015	4 - 6 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B232	SSHS-B232-SUB-4-6	7/27/2015	4 - 6 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B237	SSHS-B237-SUB-0-2	7/27/2015	0 - 2 ft	857.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B237	SSHS-B237-SUB-2-4	7/27/2015	2 - 4 ft	857.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B239A	SSHS-B239A-SUB-2-4	7/27/2015	2 - 4 ft	856.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B239A	SSHS-B239A-SUB-4-6	7/27/2015	4 - 6 ft	856.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B240	SSHS-B240-SUB-2-4	7/27/2015	2 - 4 ft	857.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B240	SSHS-B240-SUB-0-2	7/27/2015	0 - 2 ft	857.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B242	SSHS-B242-SUB-0-2	7/27/2015	0 - 2 ft	857.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B242	SSHS-B242-SUB-2-4	7/27/2015	2 - 4 ft	857.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B169	SSHS-B169-SUB-0.17-2	7/28/2015	0.17 - 2 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B169	SSHS-B169-SS	7/28/2015	0 - 0.17 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B175	SSHS-B175-SS	7/28/2015	0 - 0.17 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B175	SSHS-B175-SUB-0.17-2	7/28/2015	0.17 - 2 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B212	SSHS-B212-SUB-2-4	7/28/2015	2 - 4 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B212	SSHS-B212-SUB-6-8	7/28/2015	6 - 8 ft	855.42	855.41	-0.01	5.99-7.99 ft	X	-	-	-	-
Football Field	SSHS-B212	SSHS-B212-SUB-0-2	7/28/2015	0 - 2 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B212	SSHS-B212-SUB-4-6	7/28/2015	4 - 6 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B214	SSHS-B214-SUB-0-2	7/28/2015	0 - 2 ft	855.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B214	CS-FD-#7	7/28/2015	2 - 4 ft	855.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B214	SSHS-B214-SUB-2-4	7/28/2015	2 - 4 ft	855.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B214	SSHS-B214-SUB-4-6	7/28/2015	4 - 6 ft	855.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B214	SSHS-B214-SUB-6-8	7/28/2015	6 - 8 ft	855.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B220	SSHS-B220-SUB-6-8	7/28/2015	6 - 8 ft	855.52	855.52	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B220	SSHS-B220-SUB-2-4	7/28/2015	2 - 4 ft	855.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B220	SSHS-B220-SUB-0-2	7/28/2015	0 - 2 ft	855.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B220	SSHS-B220-SUB-4-6	7/28/2015	4 - 6 ft	855.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B223	SSHS-B223-SUB-0-2	7/28/2015	0 - 2 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B223	SSHS-B223-SUB-2-4	7/28/2015	2 - 4 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B223	SSHS-B223-SUB-4-6	7/28/2015	4 - 6 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B223	SSHS-B223-SUB-6-8	7/28/2015	6 - 8 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B225	CS-FD-#6	7/28/2015	2 - 4 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B225	SSHS-B225-SUB-2-4	7/28/2015	2 - 4 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B225	SSHS-B225-SUB-0-2	7/28/2015	0 - 2 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B225	SSHS-B225-SUB-4-6	7/28/2015	4 - 6 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B227A	SSHS-B227A-SUB-8-10	7/28/2015	8 - 10 ft	856.71	856.71	0.00	8-10 ft	X	-	-	-	-
Football Field	SSHS-B230	SSHS-B230-SUB-2-4	7/28/2015	2 - 4 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B230	SSHS-B230-SUB-4-6	7/28/2015	4 - 6 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B230	SSHS-B230-SUB-0-2	7/28/2015	0 - 2 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B230	CS-FD-#8	7/28/2015	6 - 8 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B230	SSHS-B230-SUB-6-8	7/28/2015	6 - 8 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B233	SSHS-B233-SUB-0-2	7/28/2015	0 - 2 ft	856.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B233	SSHS-B233-SUB-2-4	7/28/2015	2 - 4 ft	856.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B233	SSHS-B233-SUB-8-10	7/28/2015	8 - 10 ft	856.93	856.94	0.01	8.01-10.01 ft	X	-	-	-	-
Football Field	SSHS-B233	CS-FD-#5	7/28/2015	4 - 6 ft	856.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B233	SSHS-B233-SUB-4-6	7/28/2015	4 - 6 ft	856.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B233	SSHS-B233-SUB-6-8	7/28/2015	6 - 8 ft	856.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B234A	SSHS-B234A-SUB-6-8	7/28/2015	6 - 8 ft	857.08	857.08	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B234A	SSHS-B234A-SUB-4-6	7/28/2015	4 - 6 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B234A	SSHS-B234A-SUB-0-2	7/28/2015	0 - 2 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B234A	SSHS-B234A-SUB-2-4	7/28/2015	2 - 4 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-FB10AA	SSHS-FB10AA-SUB-2-4	7/28/2015	2 - 4 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B259	SSHS-B259-SUB-2-4	7/29/2015	2 - 4 ft	855.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B259	SSHS-B259-SUB-0-2	7/29/2015	0 - 2 ft	855.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B260	SSHS-B260-SUB-2-4	7/29/2015	2 - 4 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B260	SSHS-B260-SUB-4-6	7/29/2015	4 - 6 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B260	SSHS-B260-SUB-6-8	7/29/2015	6 - 8 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B260	SSHS-B260-SUB-0-2	7/29/2015	0 - 2 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B262	SSHS-B262-SUB-2-4	7/29/2015	2 - 4 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B262	SSHS-B262-SUB-0-2	7/29/2015	0 - 2 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B262	CS-FD-#9	7/29/2015	4 - 6 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B262	SSHS-B262-SUB-4-6	7/29/2015	4 - 6 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B262	SSHS-B262-SUB-6-8	7/29/2015	6 - 8 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B266A	SSHS-B266A-SUB-8-10	7/29/2015	8 - 10 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B268	SSHS-B268-SUB-2-4	7/29/2015	2 - 4 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B268	SSHS-B268-SUB-0-2	7/29/2015	0 - 2 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B268	SSHS-B268-SUB-4-6	7/29/2015	4 - 6 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B268	SSHS-B268-SUB-6-8	7/29/2015	6 - 8 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B273	SSHS-B273-SUB-2-4	7/29/2015	2 - 4 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B273	SSHS-B273-SUB-4-6	7/29/2015	4 - 6 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B273	CS-FD-#10	7/29/2015	0 - 2 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B273	SSHS-B273-SUB-0-2	7/29/2015	0 - 2 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B273	SSHS-B273-SUB-6-8	7/29/2015	6 - 8 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B274	SSHS-B274-SUB-2-4	7/29/2015	2 - 4 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B274	SSHS-B274-SUB-4-6	7/29/2015	4 - 6 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B274	SSHS-B274-SUB-0-2	7/29/2015	0 - 2 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B274	SSHS-B274-SUB-6-8	7/29/2015	6 - 8 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B276	SSHS-B276-SUB-4-6	7/29/2015	4 - 6 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B276	SSHS-B276-SUB-6-8	7/29/2015	6 - 8 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B276	SSHS-B276-SUB-2-4	7/29/2015	2 - 4 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B276	SSHS-B276-SUB-0-2	7/29/2015	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B277	SSHS-B277-SUB-6-8	7/29/2015	6 - 8 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B277	SSHS-B277-SUB-0-2	7/29/2015	0 - 2 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B277	SSHS-B277-SUB-2-4	7/29/2015	2 - 4 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B277	SSHS-B277-SUB-4-6	7/29/2015	4 - 6 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B278A	SSHS-B278A-SUB-8-10	7/29/2015	8 - 10 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B279	SSHS-B279-SUB-4-6	7/29/2015	4 - 6 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B279	SSHS-B279-SUB-0-2	7/29/2015	0 - 2 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B279	SSHS-B279-SUB-2-4	7/29/2015	2 - 4 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B279	CS-FD-#11	7/29/2015	6 - 8 ft	856.14	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B279	SSHS-B279-SUB-6-8	7/29/2015	6 - 8 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B282	SSHS-B282-SUB-4-5	7/29/2015	4 - 5 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B282	CS-FD-#12	7/29/2015	0 - 2 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B282	SSHS-B282-SUB-0-2	7/29/2015	0 - 2 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B282	SSHS-B282-SUB-2-4	7/29/2015	2 - 4 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B283A	SSHS-B283A-SUB-8-10	7/29/2015	8 - 10 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B284	CS-FD-#13	7/29/2015	0 - 2 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B284	SSHS-B284-SUB-0-2	7/29/2015	0 - 2 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B284	SSHS-B284-SUB-2-4	7/29/2015	2 - 4 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B284	SSHS-B284-SUB-4-6	7/29/2015	4 - 6 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B284	SSHS-B284-SUB-6-8	7/29/2015	6 - 8 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B246	SSHS-B246-SUB-0-2	7/30/2015	0 - 2 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B246	SSHS-B246-SUB-2-4	7/30/2015	2 - 4 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B249	SSHS-B249-SUB-0-2	7/30/2015	0 - 2 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B249	CS-FD-#14	7/30/2015	2 - 4 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B249	SSHS-B249-SUB-2-4	7/30/2015	2 - 4 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B250	SSHS-B250-SUB-2-4	7/30/2015	2 - 4 ft	856.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B250	CS-FD-#15	7/30/2015	0 - 2 ft	856.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B250	SSHS-B250-SUB-0-2	7/30/2015	0 - 2 ft	856.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B253	SSHS-B253-SUB-0-2	7/30/2015	0 - 2 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B253	SSHS-B253-SUB-2-4	7/30/2015	2 - 4 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B254	SSHS-B254-SUB-0-2	7/30/2015	0 - 2 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B254	SSHS-B254-SUB-2-4	7/30/2015	2 - 4 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B255	SSHS-B255-SUB-0-2	7/30/2015	0 - 2 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B255	SSHS-B255-SUB-2-4	7/30/2015	2 - 4 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B255	SSHS-B255-SUB-4-6	7/30/2015	4 - 6 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B255	SSHS-B255-SUB-6-8	7/30/2015	6 - 8 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B257	SSHS-B257-SUB-4-6	7/30/2015	4 - 6 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B257	SSHS-B257-SUB-6-8	7/30/2015	6 - 8 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B257	CS-FD-#16	7/30/2015	0 - 2 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B257	SSHS-B257-SUB-0-2	7/30/2015	0 - 2 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B257	SSHS-B257-SUB-2-4	7/30/2015	2 - 4 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B257	SSHS-B257-SUB-8-10	7/30/2015	8 - 10 ft	856.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B267	SSHS-B267-SUB-2-4	7/30/2015	2 - 4 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B267	SSHS-B267-SUB-0-2	7/30/2015	0 - 2 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B267	SSHS-B267-SUB-4-6	7/30/2015	4 - 6 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B267	SSHS-B267-SUB-6-8	7/30/2015	6 - 8 ft	855.57	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-4-6	7/31/2015	4 - 6 ft	850.91	850.71	-0.20	3.8-5.8 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-6-8	7/31/2015	6 - 8 ft	850.91	850.71	-0.20	5.8-7.8 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-0-2	7/31/2015	0 - 2 ft	850.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B125	CS-FD-#18	7/31/2015	2 - 4 ft	850.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-2-4	7/31/2015	2 - 4 ft	850.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B126	CS-FD-#19	7/31/2015	4 - 6 ft	850.94	850.82	-0.12	3.88-5.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-4-6	7/31/2015	4 - 6 ft	850.94	850.82	-0.12	3.88-5.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-6-8	7/31/2015	6 - 8 ft	850.94	850.82	-0.12	5.88-7.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-8-10	7/31/2015	8 - 10 ft	850.94	850.82	-0.12	7.88-9.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-0-2	7/31/2015	0 - 2 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-2-4	7/31/2015	2 - 4 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-4-6	7/31/2015	4 - 6 ft	850.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-0-2	7/31/2015	0 - 2 ft	850.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-2-4	7/31/2015	2 - 4 ft	850.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-6-8	7/31/2015	6 - 8 ft	850.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-0-2	7/31/2015	0 - 2 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B129	CS-FD-#17	7/31/2015	2 - 4 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-2-4	7/31/2015	2 - 4 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-4-6	7/31/2015	4 - 6 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-8-10	7/31/2015	8 - 10 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-6-8	7/31/2015	6 - 8 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B140	SSHS-B140-SUB-0-2	7/31/2015	0 - 2 ft	851.74	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B140	SSHS-B140-SUB-2-4	7/31/2015	2 - 4 ft	851.74	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-0-2	7/31/2015	0 - 2 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-2-4	7/31/2015	2 - 4 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-4-6	7/31/2015	4 - 6 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-6-8	7/31/2015	6 - 8 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B106A	CS-FD-#21	8/3/2015	8 - 10 ft	849.39	849.17	-0.22	7.78-9.78 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B106A	SSHS-B106A-SUB-8-10	8/3/2015	8 - 10 ft	849.39	849.17	-0.22	7.78-9.78 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B117A	SSHS-B117A-SUB-8-10	8/3/2015	8 - 10 ft	850.60	850.42	-0.18	7.82-9.82 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B119A	SSHS-B119A-SUB-8-10	8/3/2015	8 - 10 ft	850.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-2-4	8/3/2015	2 - 4 ft	851.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-4-6	8/3/2015	4 - 6 ft	851.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-6-8	8/3/2015	6 - 8 ft	851.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-8-10	8/3/2015	8 - 10 ft	851.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-0-2	8/3/2015	0 - 2 ft	851.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-0-2	8/3/2015	0 - 2 ft	852.64	852.58	-0.06	0-1.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-2-4	8/3/2015	2 - 4 ft	852.64	852.58	-0.06	1.94-3.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-4-6	8/3/2015	4 - 6 ft	852.64	852.58	-0.06	3.94-5.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-6-8	8/3/2015	6 - 8 ft	852.64	852.58	-0.06	5.94-7.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-6-8	8/3/2015	6 - 8 ft	851.34	851.26	-0.08	5.92-7.92 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-0-2	8/3/2015	0 - 2 ft	851.34	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-2-4	8/3/2015	2 - 4 ft	851.34	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-4-6	8/3/2015	4 - 6 ft	851.34	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-2-4	8/3/2015	2 - 4 ft	852.19	852.56	0.37	2.37-4.37 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-4-6	8/3/2015	4 - 6 ft	852.19	852.56	0.37	4.37-6.37 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-6-8	8/3/2015	6 - 8 ft	852.19	852.56	0.37	6.37-8.37 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-0-2	8/3/2015	0 - 2 ft	852.19	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B156	SSHS-B156-SUB-0-2	8/3/2015	0 - 2 ft	852.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B156	SSHS-B156-SUB-2-4	8/3/2015	2 - 4 ft	852.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-4-6	8/3/2015	4 - 6 ft	852.33	852.34	0.01	4.01-6.01 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B159	CS-FD-#25	8/3/2015	0 - 2 ft	852.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-0-2	8/3/2015	0 - 2 ft	852.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-6-8	8/3/2015	6 - 8 ft	852.33	852.34	0.01	6.01-8.01 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-2-4	8/3/2015	2 - 4 ft	852.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-6-8	8/3/2015	6 - 8 ft	852.12	852.20	0.08	6.08-8.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-8-10	8/3/2015	8 - 10 ft	852.12	852.20	0.08	8.08-10.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-2-4	8/3/2015	2 - 4 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-4-6	8/3/2015	4 - 6 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B161	CS-FD-#24	8/3/2015	2 - 4 ft	852.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-2-4	8/3/2015	2 - 4 ft	852.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-6-8	8/3/2015	6 - 8 ft	852.38	852.57	0.19	6.19-8.19 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-0-2	8/3/2015	0 - 2 ft	852.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-4-6	8/3/2015	4 - 6 ft	852.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-4-6	8/3/2015	4 - 6 ft	852.38	852.56	0.18	4.18-6.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-6-8	8/3/2015	6 - 8 ft	852.38	852.56	0.18	6.18-8.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-2-4	8/3/2015	2 - 4 ft	852.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-0-2	8/3/2015	0 - 2 ft	852.38	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B163	CS-FD-#23	8/3/2015	0 - 2 ft	852.21	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B163	SSHS-B163-SUB-0-2	8/3/2015	0 - 2 ft	852.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B151	SSHS-B151-SUB-0.17-2	8/5/2015	0.17 - 2 ft	854.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B151	SSHS-B151-SS	8/5/2015	0 - 0.17 ft	854.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B173	CS-FD-#101	8/5/2015	0.17 - 2 ft	854.70	-	-	-	X	-	-	-	-
Football Field	SSHS-B173	SSHS-B173-SUB-0.17-2	8/5/2015	0.17 - 2 ft	854.70	-	-	-	X	-	-	-	-
Football Field	SSHS-B173	SSHS-B173-SS	8/5/2015	0 - 0.17 ft	854.70	-	-	-	X	-	-	-	-
Football Field	SSHS-B303	SSHS-B303-SUB-0-1	8/5/2015	0 - 1 ft	854.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B304	SSHS-B304-SUB-0-1	8/5/2015	0 - 1 ft	855.55	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B306	SSHS-B306-SUB-0-2	3/1/2016	0 - 2 ft	856.22	-	-	-	X	-	-	-	-
Football Field	SSHS-B315	SSHS-B315-SUB-0.17-2	3/1/2016	0.17 - 2 ft	855.19	-	-	-	X	-	-	-	-
Football Field	SSHS-B315	PS-FD-1	3/1/2016	0 - 0.17 ft	855.19	-	-	-	X	-	-	-	-
Football Field	SSHS-B315	SSHS-B315-SS	3/1/2016	0 - 0.17 ft	855.19	-	-	-	X	-	-	-	-
Football Field	SSHS-B317	SSHS-B317-SUB-0-2	3/1/2016	0 - 2 ft	856.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B324	SSHS-B324-SS	3/1/2016	0 - 0.17 ft	855.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B324	PS-FD-2	3/1/2016	0.17 - 2 ft	855.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B324	SSHS-B324-SUB-0.17-2	3/1/2016	0.17 - 2 ft	855.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B325	SSHS-B325-SUB-2-4	3/1/2016	2 - 4 ft	855.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B308	SSHS-B308-SUB-0-2	3/2/2016	0 - 2 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B308	SSHS-B308-SUB-2-4	3/2/2016	2 - 4 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B308	SSHS-B308-SUB-4-6	3/2/2016	4 - 6 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B309	SSHS-B309-SUB-2-4	3/2/2016	2 - 4 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B309	SSHS-B309-SUB-0-2	3/2/2016	0 - 2 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B309	SSHS-B309-SUB-4-6	3/2/2016	4 - 6 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B310	SSHS-B310-SUB-2-4	3/2/2016	2 - 4 ft	854.81	-	-	-	X	-	-	-	-
Football Field	SSHS-B310	SSHS-B310-SUB-4-6	3/2/2016	4 - 6 ft	854.81	-	-	-	X	-	-	-	-
Football Field	SSHS-B310	SSHS-B310-SUB-0-2	3/2/2016	0 - 2 ft	854.81	-	-	-	X	-	-	-	-
Football Field	SSHS-B311	SSHS-B311-SUB-0-2	3/2/2016	0 - 2 ft	854.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B311	SSHS-B311-SUB-2-4	3/2/2016	2 - 4 ft	854.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B312	SSHS-B312-SUB-6-8	3/2/2016	6 - 8 ft	857.49	857.49	0.00	6-8 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B312	SSHS-B312-SUB-2-4	3/2/2016	2 - 4 ft	857.49	-	-	-	X	-	-	-	-
Football Field	SSHS-B312	SSHS-B312-SUB-4-6	3/2/2016	4 - 6 ft	857.49	-	-	-	X	-	-	-	-
Football Field	SSHS-B313	SSHS-B313-SUB-4-6	3/2/2016	4 - 6 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B313	PS-FD-4	3/2/2016	6 - 8 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B313	SSHS-B313-SUB-6-8	3/2/2016	6 - 8 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B314	SSHS-B314-SUB-2-4	3/2/2016	2 - 4 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B314	SSHS-B314-SUB-6-8	3/2/2016	6 - 8 ft	856.85	856.85	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B314	PS-FD-5	3/2/2016	0 - 2 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B314	SSHS-B314-SUB-0-2	3/2/2016	0 - 2 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B314	PS-FD-6	3/2/2016	4 - 6 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B314	SSHS-B314-SUB-4-6	3/2/2016	4 - 6 ft	856.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B316	SSHS-B316-SUB-2-4	3/2/2016	2 - 4 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B316	PS-FD-3	3/2/2016	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B316	SSHS-B316-SUB-0-2	3/2/2016	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B316	SSHS-B316-SUB-4-6	3/2/2016	4 - 6 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B318	SSHS-B318-SUB-0-2	3/2/2016	0 - 2 ft	856.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B318	SSHS-B318-SUB-2-4	3/2/2016	2 - 4 ft	856.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B319	SSHS-B319-SUB-8-10	3/2/2016	8 - 10 ft	857.02	857.02	0.00	8-10 ft	X	-	-	-	-
Football Field	SSHS-B319	SSHS-B319-SUB-4-6	3/2/2016	4 - 6 ft	857.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B320	SSHS-B320-SUB-0-2	3/2/2016	0 - 2 ft	856.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B320	SSHS-B320-SUB-4-6	3/2/2016	4 - 6 ft	856.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B322	SSHS-B322-SUB-8-10	3/2/2016	8 - 10 ft	857.31	857.32	0.01	8.01-10.01 ft	X	-	-	-	-
Football Field	SSHS-B323	SSHS-B323-SUB-8-10	3/2/2016	8 - 10 ft	856.59	-	-	-	X	-	-	-	-
Football Field	SSHS-B326	SSHS-B326-SUB-2-4	3/2/2016	2 - 4 ft	854.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B326	SSHS-B326-SUB-0-2	3/2/2016	0 - 2 ft	854.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B326	SSHS-B326-SUB-4-6	3/2/2016	4 - 6 ft	854.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B321	SSHS-B321-SUB-4-6	3/3/2016	4 - 6 ft	854.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B327	SSHS-B327-SUB-0-2	3/3/2016	0 - 2 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B327	SSHS-B327-SUB-2-4	3/3/2016	2 - 4 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B327	SSHS-B327-SUB-4-6	3/3/2016	4 - 6 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B328	SSHS-B328-SUB-2-4	3/3/2016	2 - 4 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B328	SSHS-B328-SUB-0-2	3/3/2016	0 - 2 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B328	SSHS-B328-SUB-4-6	3/3/2016	4 - 6 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B329	SSHS-B329-SUB-0-2	3/3/2016	0 - 2 ft	855.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B329	SSHS-B329-SUB-2-4	3/3/2016	2 - 4 ft	855.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B329	SSHS-B329-SUB-4-6	3/3/2016	4 - 6 ft	855.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B329	SSHS-B329-SUB-6-8	3/3/2016	6 - 8 ft	855.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B329	SSHS-B329-SUB-8-10	3/3/2016	8 - 10 ft	855.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B331	SSHS-B331-SUB-0-2	3/3/2016	0 - 2 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B331	SSHS-B331-SUB-2-4	3/3/2016	2 - 4 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B331	PS-FD-9	3/3/2016	4 - 6 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B331	SSHS-B331-SUB-4-6	3/3/2016	4 - 6 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B331	SSHS-B331-SUB-6-8	3/3/2016	6 - 8 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B331	SSHS-B331-SUB-8-10	3/3/2016	8 - 10 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B332	SSHS-B332-SUB-0-2	3/3/2016	0 - 2 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B332	SSHS-B332-SUB-4-6	3/3/2016	4 - 6 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B332	SSHS-B332-SUB-6-8	3/3/2016	6 - 8 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B332	SSHS-B332-SUB-8-10	3/3/2016	8 - 10 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B333	SSHS-B333-SUB-4-6	3/3/2016	4 - 6 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B333	SSHS-B333-SUB-6-8	3/3/2016	6 - 8 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B333	SSHS-B333-SUB-8-10	3/3/2016	8 - 10 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B333	SSHS-B333-SUB-0-2	3/3/2016	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B333	SSHS-B333-SUB-2-4	3/3/2016	2 - 4 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B334	PS-FD-10	3/3/2016	2 - 4 ft	856.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B334	SSHS-B334-SUB-2-4	3/3/2016	2 - 4 ft	856.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B334	SSHS-B334-SUB-4-6	3/3/2016	4 - 6 ft	856.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B334	SSHS-B334-SUB-8-10	3/3/2016	8 - 10 ft	856.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B334	SSHS-B334-SUB-0-2	3/3/2016	0 - 2 ft	856.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B334	SSHS-B334-SUB-6-8	3/3/2016	6 - 8 ft	856.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B335	SSHS-B335-SUB-8-10	3/3/2016	8 - 10 ft	856.16	856.49	0.33	8.33-10.33 ft	X	-	-	-	-
Football Field	SSHS-B335	SSHS-B335-SUB-0-2	3/3/2016	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B335	SSHS-B335-SUB-2-4	3/3/2016	2 - 4 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B335	SSHS-B335-SUB-4-6	3/3/2016	4 - 6 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B335	PS-FD-11	3/3/2016	4 - 6 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B336	SSHS-B336-SUB-8-10	3/3/2016	8 - 10 ft	856.00	856.01	0.01	8.01-10.01 ft	X	-	-	-	-
Football Field	SSHS-B336	SSHS-B336-SUB-0-2	3/3/2016	0 - 2 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B336	SSHS-B336-SUB-2-4	3/3/2016	2 - 4 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B336	SSHS-B336-SUB-4-6	3/3/2016	4 - 6 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B336	SSHS-B336-SUB-6-8	3/3/2016	6 - 8 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B341	SSHS-B341-SUB-8-10	3/3/2016	8 - 10 ft	855.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B342	PS-FD-7	3/3/2016	8 - 10 ft	855.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B342	SSHS-B342-SUB-8-10	3/3/2016	8 - 10 ft	855.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B344	SSHS-B344-SUB-0-2	3/3/2016	0 - 2 ft	855.69	-	-	-	X	-	-	-	-
Football Field	SSHS-B344	SSHS-B344-SUB-4-6	3/3/2016	4 - 6 ft	855.69	-	-	-	X	-	-	-	-
Football Field	SSHS-B344	PS-FD-8	3/3/2016	6 - 8 ft	855.69	-	-	-	X	-	-	-	-
Football Field	SSHS-B344	SSHS-B344-SUB-6-8	3/3/2016	6 - 8 ft	855.69	-	-	-	X	-	-	-	-
Football Field	SSHS-B344	SSHS-B344-SUB-8-10	3/3/2016	8 - 10 ft	855.69	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B380	SSHS-B380-SUB-0-2	3/7/2016	0 - 2 ft	853.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-0-2	3/8/2016	0 - 2 ft	852.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-4-6	3/8/2016	4 - 6 ft	852.79	852.76	-0.03	3.97-5.97 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-6-8	3/8/2016	6 - 8 ft	852.79	852.76	-0.03	5.97-7.97 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-8-10	3/8/2016	8 - 10 ft	852.79	852.76	-0.03	7.97-9.97 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-2-4	3/8/2016	2 - 4 ft	852.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-0-2	3/8/2016	0 - 2 ft	852.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-2-4	3/8/2016	2 - 4 ft	852.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-4-6	3/8/2016	4 - 6 ft	852.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B376	SSHS-B376-SUB-2-4	3/8/2016	2 - 4 ft	851.45	851.32	-0.13	1.87-3.87 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B377	SSHS-B377-SUB-8-10	3/8/2016	8 - 10 ft	850.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B377	SSHS-B377B-SUB-10-12	3/8/2016	10 - 12 ft	850.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-2-4	3/8/2016	2 - 4 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-8-10	3/8/2016	8 - 10 ft	850.73	850.50	-0.23	7.77-9.77 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-4-6	3/8/2016	4 - 6 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B379	SSHS-B379-SUB-2-4	3/8/2016	2 - 4 ft	851.22	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B386	PS-FD-20	3/8/2016	2 - 4 ft	852.82	853.09	0.27	2.27-4.27 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-2-4	3/8/2016	2 - 4 ft	852.82	853.09	0.27	2.27-4.27 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-4-6	3/8/2016	4 - 6 ft	852.82	853.09	0.27	4.27-6.27 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-0-2	3/8/2016	0 - 2 ft	852.82	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B394	PS-FD-18	3/8/2016	8 - 10 ft	851.52	851.47	-0.05	7.95-9.95 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-8-10	3/8/2016	8 - 10 ft	851.52	851.47	-0.05	7.95-9.95 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-2-4	3/8/2016	2 - 4 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-4-6	3/8/2016	4 - 6 ft	851.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B330	SSHS-B330B-SUB-10-12	3/9/2016	10 - 12 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B330	SSHS-B330-SUB-2-4	3/9/2016	2 - 4 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B330	SSHS-B330-SUB-6-8	3/9/2016	6 - 8 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B330	SSHS-B330-SUB-8-10	3/9/2016	8 - 10 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B330	SSHS-B330B-SUB-12-14	3/9/2016	12 - 14 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B330	SSHS-B330-SUB-4-6	3/9/2016	4 - 6 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B337	SSHS-B337-SUB-8-10	3/9/2016	8 - 10 ft	856.65	856.65	0.00	8-10 ft	X	-	-	-	-
Football Field	SSHS-B337	SSHS-B337-SUB-4-6	3/9/2016	4 - 6 ft	856.65	-	-	-	X	-	-	-	-
Football Field	SSHS-B338	SSHS-B338-SUB-2-4	3/9/2016	2 - 4 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B338	SSHS-B338-SUB-6-8	3/9/2016	6 - 8 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B338	PS-FD-21	3/9/2016	0 - 2 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B338	SSHS-B338-SUB-0-2	3/9/2016	0 - 2 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B338	SSHS-B338-SUB-4-6	3/9/2016	4 - 6 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B338	SSHS-B338-SUB-8-10	3/9/2016	8 - 10 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B339	SSHS-B339-SUB-0-2	3/9/2016	0 - 2 ft	856.05	-	-	-	X	-	-	-	-
Football Field	SSHS-B339	SSHS-B339-SUB-2-4	3/9/2016	2 - 4 ft	856.05	-	-	-	X	-	-	-	-
Football Field	SSHS-B340	SSHS-B340-SUB-2-4	3/9/2016	2 - 4 ft	855.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B381	PS-FD-22	3/9/2016	0 - 2 ft	852.40	852.92	0.52	0.52-2.52 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B381	SSHS-B381-SUB-0-2	3/9/2016	0 - 2 ft	852.40	852.92	0.52	0.52-2.52 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-0-2	3/9/2016	0 - 2 ft	850.28	850.38	0.10	0.1-2.1 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-2-4	3/9/2016	2 - 4 ft	850.28	850.38	0.10	2.1-4.1 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-4-6	3/10/2016	4 - 6 ft	852.56	852.68	0.12	4.12-6.12 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-6-8	3/10/2016	6 - 8 ft	852.56	852.68	0.12	6.12-8.12 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-8-10	3/10/2016	8 - 10 ft	852.56	852.68	0.12	8.12-10.12 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B373	PS-FD-24	3/10/2016	2 - 4 ft	852.56	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-2-4	3/10/2016	2 - 4 ft	852.56	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-2-4	3/10/2016	2 - 4 ft	852.41	852.73	0.32	2.32-4.32 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-4-6	3/10/2016	4 - 6 ft	852.41	852.73	0.32	4.32-6.32 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-6-8	3/10/2016	6 - 8 ft	852.41	852.73	0.32	6.32-8.32 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-0-2	3/10/2016	0 - 2 ft	852.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B388	SSHS-B388-SUB-6-8	3/10/2016	6 - 8 ft	850.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B389	SSHS-B389-SUB-10-12	3/10/2016	10 - 12 ft	851.50	851.68	0.18	10.18-12.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B389	SSHS-B389-SUB-8-10	3/10/2016	8 - 10 ft	851.50	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B390	PS-FD-25	3/10/2016	8 - 10 ft	851.95	852.16	0.21	8.21-10.21 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B390	SSHS-B390-SUB-8-10	3/10/2016	8 - 10 ft	851.95	852.16	0.21	8.21-10.21 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B391	SSHS-B391-SUB-8-10	3/10/2016	8 - 10 ft	849.56	849.52	-0.04	7.96-9.96 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B392	SSHS-B392-SUB-8-10	3/10/2016	8 - 10 ft	850.00	849.45	-0.55	7.45-9.45 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B393	SSHS-B393-SUB-8-10	3/10/2016	8 - 10 ft	849.93	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B395	SSHS-B395-SUB-8-10	3/10/2016	8 - 10 ft	851.50	851.82	0.32	8.32-10.32 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B396	SSHS-B396-SUB-8-10	3/10/2016	8 - 10 ft	850.83	851.09	0.26	8.26-10.26 ft	X	-	-	-	-
Football Field	SSHS-B411	SSHS-B411-SUB-0-2	8/22/2016	0 - 2 ft	856.36	-	-	-	X	-	-	-	-
Football Field	SSHS-B414	SSHS-B414-SUB-0-2	8/22/2016	0 - 2 ft	856.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B415	SSHS-B415-SUB-0-2	8/22/2016	0 - 2 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B415	PS-FD-2	8/22/2016	2 - 4 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B415	SSHS-B415-SUB-2-4	8/22/2016	2 - 4 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B416	SSHS-B416-SUB-2-4	8/22/2016	2 - 4 ft	855.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B416	SSHS-B416-SUB-0-2	8/22/2016	0 - 2 ft	855.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B417	SSHS-B417-SUB-0-2	8/22/2016	0 - 2 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B417	SSHS-B417-SUB-2-4	8/22/2016	2 - 4 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B423	SSHS-B423-SUB-0-2	8/22/2016	0 - 2 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	0 - 2 ft	856.17	-	-	-	X	X	X	-	-
Football Field	SSHS-B424	SSHS-B424-SUB-2-4	8/22/2016	2 - 4 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B425	SSHS-B425-SUB-2-4	8/22/2016	2 - 4 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B425	SSHS-B425-SUB-0-2	8/22/2016	0 - 2 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B431	SSHS-B431-SUB-2-4	8/22/2016	2 - 4 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B432	PS-FD-1	8/22/2016	4 - 6 ft	855.16	855.27	0.11	4.11-6.11 ft	X	-	-	-	-
Football Field	SSHS-B432	SSHS-B432-SUB-4-6	8/22/2016	4 - 6 ft	855.16	855.27	0.11	4.11-6.11 ft	X	-	-	-	-
Football Field	SSHS-B432	SSHS-B432-SUB-2-4	8/22/2016	2 - 4 ft	855.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	0 - 2 ft	855.16	-	-	-	-	-	X	-	-
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	0 - 2 ft	855.08	-	-	-	-	-	X	-	-
Football Field	SSHS-B434	SSHS-B434-SUB-2-4	8/22/2016	2 - 4 ft	855.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B436	SSHS-B436-SUB-4-6	8/22/2016	4 - 6 ft	855.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B418	SSHS-B418-SUB-0-2	8/23/2016	0 - 2 ft	855.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B418	SSHS-B418-SUB-2-4	8/23/2016	2 - 4 ft	855.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B419	SSHS-B419-SUB-0-2	8/23/2016	0 - 2 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B419	SSHS-B419-SUB-2-4	8/23/2016	2 - 4 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B420	SSHS-B420-SUB-0-2	8/23/2016	0 - 2 ft	855.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B420	SSHS-B420-SUB-2-4	8/23/2016	2 - 4 ft	855.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B421	SSHS-B421-SUB-4-6	8/23/2016	4 - 6 ft	854.90	855.42	0.52	4.52-6.52 ft	X	-	-	-	-
Football Field	SSHS-B421	SSHS-B421-SUB-0-2	8/23/2016	0 - 2 ft	854.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B421	SSHS-B421-SUB-2-4	8/23/2016	2 - 4 ft	854.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B422	SSHS-B422-SUB-4-6	8/23/2016	4 - 6 ft	855.04	855.52	0.48	4.48-6.48 ft	X	-	-	-	-
Football Field	SSHS-B422	SSHS-B422-SUB-0-2	8/23/2016	0 - 2 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B422	SSHS-B422-SUB-2-4	8/23/2016	2 - 4 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B426	SSHS-B426-SUB-0-2	8/23/2016	0 - 2 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B427	PS-FD-5	8/23/2016	0 - 2 ft	855.43	-	-	-	X	-	-	-	-
Football Field	SSHS-B427	SSHS-B427-SUB-0-2	8/23/2016	0 - 2 ft	855.43	-	-	-	X	-	-	-	-
Football Field	SSHS-B433	SSHS-B433-SUB-4-6	8/23/2016	4 - 6 ft	855.58	855.58	0.00	4-6 ft	X	-	-	-	-
Football Field	SSHS-B433	SSHS-B433-SUB-2-4	8/23/2016	2 - 4 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B435	SSHS-B435-SUB-6-8	8/23/2016	6 - 8 ft	856.34	-	-	-	X	-	-	-	-
Football Field	SSHS-B494	SSHS-B494-SUB-0-2	8/23/2016	0 - 2 ft	854.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B495	SSHS-B495-SUB-0-2	8/23/2016	0 - 2 ft	855.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B496	PS-FD-3	8/23/2016	0 - 2 ft	855.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B496	SSHS-B496-SUB-0-2	8/23/2016	0 - 2 ft	855.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B441	SSHS-B441-SUB-2-4	8/24/2016	2 - 4 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B441	SSHS-B441-SUB-4-6	8/24/2016	4 - 6 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B441	SSHS-B441-SUB-0-2	8/24/2016	0 - 2 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B441	SSHS-B441-SUB-6-8	8/24/2016	6 - 8 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B442	SSHS-B442-SUB-0-2	8/24/2016	0 - 2 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B442	SSHS-B442-SUB-2-4	8/24/2016	2 - 4 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B442	SSHS-B442-SUB-4-6	8/24/2016	4 - 6 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B442	SSHS-B442-SUB-6-8	8/24/2016	6 - 8 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B447	SSHS-447-SUB-0-2	8/24/2016	0 - 2 ft	855.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B453	SSHS-B453-SUB-0-2	8/24/2016	0 - 2 ft	855.65	-	-	-	X	-	-	-	-
Football Field	SSHS-B454	SSHS-B454-SUB-0-2	8/24/2016	0 - 2 ft	855.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B458	SSHS-B458-SUB-0-2	8/24/2016	0 - 2 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B468	SSHS-B468-SUB-2-4	8/24/2016	2 - 4 ft	855.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B468	SSHS-B468-SUB-4-6	8/24/2016	4 - 6 ft	855.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B471	PS-FD-6	8/24/2016	6 - 8 ft	855.65	-	-	-	X	-	-	-	-
Football Field	SSHS-B471	SSHS-B471-SUB-6-8	8/24/2016	6 - 8 ft	855.65	-	-	-	X	-	-	-	-
Football Field	SSHS-B471	SSHS-B471-SUB-8-10	8/24/2016	8 - 10 ft	855.65	-	-	-	X	-	-	-	-
Football Field	SSHS-B472	SSHS-B472-SUB-8-10	8/24/2016	8 - 10 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B474	SSHS-B474-SUB-8-10	8/24/2016	8 - 10 ft	856.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B474	SSHS-B474-SUB-10-12	8/24/2016	10 - 12 ft	856.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B481	SSHS-B481-SS	8/24/2016	0 - 0.17 ft	856.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B482	PS-FD-7	8/24/2016	10 - 12 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B482	SSHS-B482-SUB-10-12	8/24/2016	10 - 12 ft	856.12	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B397	082616 09:00_PS-FD-10	8/25/2016	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B397	SSHS-B397-SUB-0-2	8/25/2016	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B398	SSHS-B398-SUB-0-2	8/25/2016	0 - 2 ft	856.20	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	0 - 2 ft	856.45	856.57	0.12	0.12-2.12 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B400	SSHS-B400-SUB-0-2	8/25/2016	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B401	SSHS-B401-SUB-0-2	8/25/2016	0 - 2 ft	856.35	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	0 - 2 ft	856.65	-	-	-	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	0 - 0.17 ft	855.65	858.37	2.72	2.72-2.89 ft	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	0.17 - 1 ft	855.65	858.37	2.72	2.89-3.72 ft	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	1 - 2 ft	855.65	858.37	2.72	3.72-4.72 ft	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B406	PS-FD-39	8/25/2016	0 - 0.17 ft	855.97	856.64	0.67	0.67-0.84 ft	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SS	8/25/2016	0 - 0.17 ft	855.97	856.64	0.67	0.67-0.84 ft	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-0.17-1	8/25/2016	0.17 - 1 ft	855.97	856.64	0.67	0.84-1.67 ft	-	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	1 - 2 ft	855.97	856.64	0.67	1.67-2.67 ft	-	-	X	-	-
Football Field	SSHS-B407	SSHS-B407-SUB-6-8	8/25/2016	6 - 8 ft	857.28	857.28	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B407	SSHS-B407-SUB-0-2	8/25/2016	0 - 2 ft	857.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B407	SSHS-B407-SUB-2-4	8/25/2016	2 - 4 ft	857.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B407	PS-FD-8	8/25/2016	4 - 6 ft	857.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B407	SSHS-B407-SUB-4-6	8/25/2016	4 - 6 ft	857.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B408	SSHS-B408-SUB-0-2	8/25/2016	0 - 2 ft	857.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B408	SSHS-B408-SUB-2-4	8/25/2016	2 - 4 ft	857.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B409	SSHS-B409-SUB-0-2	8/25/2016	0 - 2 ft	857.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B410	SSHS-B410-SUB-2-4	8/25/2016	2 - 4 ft	856.77	856.76	-0.01	1.99-3.99 ft	X	-	-	-	-
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	0 - 2 ft	856.77	-	-	-	X	X	X	-	-
Football Field	SSHS-B412	SSHS-B412-SUB-6-8	8/25/2016	6 - 8 ft	856.86	856.86	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B412	SSHS-B412-SUB-2-4	8/25/2016	2 - 4 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B412	SSHS-B412-SUB-0-2	8/25/2016	0 - 2 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B412	SSHS-B412-SUB-4-6	8/25/2016	4 - 6 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B430	PS-FD-9	8/25/2016	0 - 2 ft	855.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B430	SSHS-B430-SUB-0-2	8/25/2016	0 - 2 ft	855.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	0 - 2 ft	856.23	-	-	-	-	-	X	-	-
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	0 - 2 ft	856.21	-	-	-	-	-	X	-	-
Football Field	SSHS-B478	SSHS-B478-SUB-12-14	8/25/2016	12 - 14 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B478	SSHS-B478-SUB-6-8	8/25/2016	6 - 8 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B478	SSHS-B478-SUB-8-10	8/25/2016	8 - 10 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B478	SSHS-B478-SUB-10-12	8/25/2016	10 - 12 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B413	SSHS-B413-SUB-2-4	8/26/2016	2 - 4 ft	856.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B413	SSHS-B413-SUB-0-2	8/26/2016	0 - 2 ft	856.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B428	SSHS-B428-SS	8/26/2016	0 - 0.17 ft	855.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B428	SSHS-B428-SUB-0.17-2	8/26/2016	0.17 - 2 ft	855.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B429	SSHS-B429-SS	8/26/2016	0 - 0.17 ft	854.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B429	SSHS-B429-SUB-0.17-2	8/26/2016	0.17 - 2 ft	854.95	-	-	-	X	-	X	-	-
Football Field	SSHS-B438	SSHS-B438-SUB-2-4	8/26/2016	2 - 4 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B438	SSHS-B438-SUB-8-10	8/26/2016	8 - 10 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B438	SSHS-B438-SUB-4-6	8/26/2016	4 - 6 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B438	SSHS-B438-SUB-6-8	8/26/2016	6 - 8 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B438	SSHS-B438-SUB-0-2	8/26/2016	0 - 2 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B439	SSHS-B439-SUB-0-2	8/26/2016	0 - 2 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B439	SSHS-B439-SUB-2-4	8/26/2016	2 - 4 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B440	SSHS-B440-SUB-0-2	8/26/2016	0 - 2 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B440	SSHS-B440-SUB-6-8	8/26/2016	6 - 8 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B440	SSHS-B440-SUB-2-4	8/26/2016	2 - 4 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B440	SSHS-B440-SUB-4-6	8/26/2016	4 - 6 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B440	SSHS-B440-SUB-8-10	8/26/2016	8 - 10 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B444	SSHS-B444-SUB-2-4	8/26/2016	2 - 4 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B444	SSHS-B444-SUB-6-8	8/26/2016	6 - 8 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B444	SSHS-B444-SUB-8-10	8/26/2016	8 - 10 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B444	SSHS-B444-SUB-0-2	8/26/2016	0 - 2 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B444	PS-FD-11	8/26/2016	4 - 6 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B444	SSHS-B444-SUB-4-6	8/26/2016	4 - 6 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B445	SSHS-B445-SS	8/26/2016	0 - 0.17 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B464	SSHS-B464-SUB-4-6	8/29/2016	4 - 6 ft	856.94	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B464	SSHS-B464-SUB-6-8	8/29/2016	6 - 8 ft	856.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B464	SSHS-B464-SUB-0-2	8/29/2016	0 - 2 ft	856.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B464	SSHS-B464-SUB-2-4	8/29/2016	2 - 4 ft	856.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B466	SSHS-B466-SUB-0-2	8/29/2016	0 - 2 ft	856.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B467	SSHS-B467-SUB-0-2	8/29/2016	0 - 2 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B467	SSHS-B467-SUB-2-4	8/29/2016	2 - 4 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B467	SSHS-B467-SUB-4-6	8/29/2016	4 - 6 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B467	SSHS-B467-SUB-6-8	8/29/2016	6 - 8 ft	856.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B469	SSHS-B469-SUB-10-12	8/29/2016	10 - 12 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B469	SSHS-B469-SUB-12-14	8/29/2016	12 - 14 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B469	SSHS-B469-SUB-8-10	8/29/2016	8 - 10 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B469	PS-FD-12	8/29/2016	2 - 4 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B469	SSHS-B469-SUB-2-4	8/29/2016	2 - 4 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B469	SSHS-B469-SUB-6-8	8/29/2016	6 - 8 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B470	SSHS-B470-SUB-8-10	8/29/2016	8 - 10 ft	856.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B470	SSHS-B470-SUB-12-14	8/29/2016	12 - 14 ft	856.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B470	SSHS-B470-SUB-10-12	8/29/2016	10 - 12 ft	856.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B470	SSHS-B470-SUB-6-8	8/29/2016	6 - 8 ft	856.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B475	SSHS-B475-SUB-10-12	8/29/2016	10 - 12 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B475	PS-FD-13	8/29/2016	8 - 10 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B475	SSHS-B475-SUB-8-10	8/29/2016	8 - 10 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B476	SSHS-B476-SUB-6-8	8/29/2016	6 - 8 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B477	SSHS-B477-SUB-4-6	8/29/2016	4 - 6 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B477	SSHS-B477-SUB-6-8	8/29/2016	6 - 8 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B477	SSHS-B477-SUB-0-2	8/29/2016	0 - 2 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B477	PS-FD-14	8/29/2016	2 - 4 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B477	SSHS-B477-SUB-2-4	8/29/2016	2 - 4 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B479	SSHS-B479-SUB-4-6	8/29/2016	4 - 6 ft	856.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B479	SSHS-B479-SUB-0-2	8/29/2016	0 - 2 ft	856.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B479	SSHS-B479-SUB-10-12	8/29/2016	10 - 12 ft	856.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B479	SSHS-B479-SUB-6-8	8/29/2016	6 - 8 ft	856.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B480	SSHS-B480-SUB-10-12	8/29/2016	10 - 12 ft	856.90	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	0 - 2 ft	855.98	-	-	-	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B403	SSHS-B403-SUB-0-2	8/30/2016	0 - 2 ft	856.22	-	-	-	X	-	-	-	-
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	0 - 2 ft	855.21	-	-	-	-	-	X	-	-
Football Field	SSHS-B455	SSHS-B455-SUB-0-2	8/30/2016	0 - 2 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B455	SSHS-B455-SUB-4-6	8/30/2016	4 - 6 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B455	PS-FD-16	8/30/2016	6 - 8 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B455	SSHS-B455-SUB-6-8	8/30/2016	6 - 8 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B455	SSHS-B455-SUB-8-10	8/30/2016	8 - 10 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B456	SSHS-B456-SUB-4-6	8/30/2016	4 - 6 ft	855.99	855.99	0.00	4-6 ft	X	-	-	-	-
Football Field	SSHS-B456	SSHS-B456-SUB-0-2	8/30/2016	0 - 2 ft	855.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B457	SSHS-B457-SUB-0-2	8/30/2016	0 - 2 ft	855.74	855.74	0.00	0-2 ft	X	-	-	-	-
Football Field	SSHS-B473	SSHS-B473-SUB-0-2	8/30/2016	0 - 2 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B473	SSHS-B473-SUB-4-6	8/30/2016	4 - 6 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B473	PS-FD-15	8/30/2016	6 - 8 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B473	SSHS-B473-SUB-6-8	8/30/2016	6 - 8 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B473	SSHS-B473-SUB-8-10	8/30/2016	8 - 10 ft	856.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B570	SSHS-B570-SUB-0-2	8/30/2016	0 - 2 ft	853.41	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B571	090616 09:00_PS-FD-42	8/30/2016	0 - 2 ft	856.63	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B571	SSHS-B571-SUB-0-2	8/30/2016	0 - 2 ft	856.63	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	8/30/2016	6 - 8 ft	852.49	854.82	2.33	8.33-10.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	8/30/2016	8 - 10 ft	852.49	854.82	2.33	10.33-12.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	0 - 2 ft	852.49	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-2-4	8/30/2016	2 - 4 ft	852.49	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-4-6	8/30/2016	4 - 6 ft	852.49	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-4-6	8/30/2016	4 - 6 ft	850.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-10-12	8/30/2016	10 - 12 ft	850.92	850.97	0.05	10.05-12.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-12-14	8/30/2016	12 - 14 ft	850.92	850.97	0.05	12.05-14.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-8-10	8/30/2016	8 - 10 ft	850.92	850.97	0.05	8.05-10.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-0-2	8/30/2016	0 - 2 ft	850.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-2-4	8/30/2016	2 - 4 ft	850.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW-FD-2	8/30/2016	2 - 4 ft	850.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-6-8	8/30/2016	6 - 8 ft	850.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B460	SSHS-B460-SUB-0-2	8/31/2016	0 - 2 ft	855.48	-	-	-	X	-	-	-	-
Football Field	SSHS-B461	SSHS-B461-SUB-0-2	8/31/2016	0 - 2 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B461	PS-FD-17	8/31/2016	2 - 3 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B461	SSHS-B461-SUB-2-3	8/31/2016	2 - 3 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B462	SSHS-B462-SUB-2-3	8/31/2016	2 - 3 ft	855.34	-	-	-	X	-	-	-	-
Football Field	SSHS-B462	SSHS-B462-SUB-0-2	8/31/2016	0 - 2 ft	855.34	-	-	-	X	-	-	-	-
Football Field	SSHS-B463	SSHS-B463-SUB-2-3	8/31/2016	2 - 3 ft	854.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B463	SSHS-B463-SUB-0-2	8/31/2016	0 - 2 ft	854.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B561	SSHS-B561-SS	9/2/2016	0 - 0.17 ft	847.44	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B562	SSHS-B562-SS	9/2/2016	0 - 0.17 ft	847.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B564	SSHS-B564-SS	9/2/2016	0 - 0.17 ft	848.83	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B565	SSHS-B565-SS	9/2/2016	0 - 0.17 ft	847.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B566	SSHS-B566-SS	9/2/2016	0 - 0.17 ft	846.57	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	16 - 18 ft	852.44	854.81	2.37	18.37-20.37 ft	X	-	X	X	-
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	10 - 12 ft	852.44	854.81	2.37	12.37-14.37 ft	-	-	X	X	-
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	12 - 14 ft	852.44	854.81	2.37	14.37-16.37 ft	-	-	X	X	-
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	14 - 16 ft	852.44	854.81	2.37	16.37-18.37 ft	X	-	X	X	-
Football Field	SSHS-B443	SSHS-B443-SUB-2-4	9/14/2016	2 - 4 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B443	PS-FD-25	9/14/2016	4 - 6 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B443	SSHS-B443-SUB-4-6	9/14/2016	4 - 6 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B443	SSHS-B443-SUB-6-8	9/14/2016	6 - 8 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B443	SSHS-B443-SUB-0-2	9/14/2016	0 - 2 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B439	SSHS-B439-SUB-6-8	9/15/2016	6 - 8 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B439	SSHS-B439-SUB-8-10	9/15/2016	8 - 10 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B443	SSHS-B443-SUB-8-10	9/15/2016	8 - 10 ft	855.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B525	SSHS-B525-SUB-0-2	9/16/2016	0 - 2 ft	853.93	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B525	SSHS-B525-SUB-2-4	9/16/2016	2 - 4 ft	853.93	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B526	SSHS-B526-SUB-2-4	9/16/2016	2 - 4 ft	853.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B526	SSHS-B526-SUB-0-2	9/16/2016	0 - 2 ft	853.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B527	SSHS-B527-SUB-2-4	9/16/2016	2 - 4 ft	853.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B527	SSHS-B527-SUB-0-2	9/16/2016	0 - 2 ft	853.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B528	SSHS-B528-SUB-2-4	9/16/2016	2 - 4 ft	853.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B528	SSHS-B528-SUB-0-2	9/16/2016	0 - 2 ft	853.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B528	PS-FD-27	9/16/2016	0 - 2 ft	853.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B529	SSHS-B529-SUB-0-2	9/16/2016	0 - 2 ft	852.61	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B531	PS-FD-28	9/16/2016	0 - 2 ft	852.31	852.87	0.57	0.57-2.57 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B531	SSHS-B531-SUB-0-2	9/16/2016	0 - 2 ft	852.31	852.87	0.57	0.57-2.57 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B554	SSHS-B554-SUB-2-4	9/16/2016	2 - 4 ft	852.21	852.78	0.57	2.57-4.57 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-4-6	9/21/2016	4 - 6 ft	852.47	853.03	0.56	4.56-6.56 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-6-8	9/21/2016	6 - 8 ft	852.47	853.03	0.56	6.56-8.56 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B536	PS-FD-32	9/21/2016	8 - 10 ft	852.47	853.03	0.56	8.56-10.56 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-8-10	9/21/2016	8 - 10 ft	852.47	853.03	0.56	8.56-10.56 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B538	SSHS-B538-SUB-10-12	9/21/2016	10 - 12 ft	851.14	851.09	-0.05	9.95-11.95 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B538	SSHS-B538-SUB-8-10	9/21/2016	8 - 10 ft	851.14	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B539	SSHS-B539-SUB-6-8	9/21/2016	6 - 8 ft	850.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B541	SSHS-B541-SUB-8-10	9/21/2016	8 - 10 ft	850.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B543	SSHS-B543-SUB-8-10	9/21/2016	8 - 10 ft	851.17	851.32	0.15	8.15-10.15 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B543	SSHS-B543-SUB-10-12	9/21/2016	10 - 12 ft	851.17	851.32	0.15	10.15-12.15 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B546	SSHS-B546-SUB-6-8	9/21/2016	6 - 8 ft	850.62	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B547	SSHS-B547-SUB-6-8	9/21/2016	6 - 8 ft	850.68	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	6 - 8 ft	850.36	-	-	-	X	-	X	-	-
Rear Parking Lot	SSHS-B548	SSHS-B548-SUB-6-8	9/21/2016	6 - 8 ft	850.36	-	-	-	X	-	X	-	-
Rear Parking Lot	SSHS-B549	SSHS-B549-SUB-6-8	9/21/2016	6 - 8 ft	850.17	849.92	-0.25	5.75-7.75 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B551	SSHS-B551-SUB-4-6	9/21/2016	4 - 6 ft	851.74	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-4-6	9/21/2016	4 - 6 ft	853.01	853.17	0.16	4.16-6.16 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-6-8	9/21/2016	6 - 8 ft	853.01	853.17	0.16	6.16-8.16 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-8-10	9/21/2016	8 - 10 ft	853.01	853.17	0.16	8.16-10.16 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B553	SSHS-B553-SUB-4-6	9/21/2016	4 - 6 ft	850.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	0 - 2 ft	851.24	-	-	-	-	-	X	-	-
Rear Parking Lot	SSHS-B530	PS-FD-35	9/22/2016	2 - 4 ft	851.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B530	SSHS-B530-SUB-2-4	9/22/2016	2 - 4 ft	851.85	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B533	SSHS-B533-SUB-8-10	9/22/2016	8 - 10 ft	852.02	852.38	0.36	8.36-10.36 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B534	SSHS-B534-SUB-4-6	9/22/2016	4 - 6 ft	852.33	852.53	0.20	4.2-6.2 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B534	SSHS-B534-SUB-8-10	9/22/2016	8 - 10 ft	852.33	852.53	0.20	8.2-10.2 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B535	SSHS-B535-SUB-8-10	9/22/2016	8 - 10 ft	851.76	851.82	0.06	8.06-10.06 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-10-12	9/22/2016	10 - 12 ft	850.44	850.26	-0.18	9.82-11.82 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-12-14	9/22/2016	12 - 14 ft	850.44	850.26	-0.18	11.82-13.82 ft	-	X	-	-	-
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-8-10	9/22/2016	8 - 10 ft	850.44	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-6-8	9/22/2016	6 - 8 ft	850.44	-	-	-	-	-	X	-	-
Rear Parking Lot	SSHS-B540	SSHS-B540-SUB-8-10	9/22/2016	8 - 10 ft	851.56	851.74	0.18	8.18-10.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-10-12	9/22/2016	10 - 12 ft	850.47	850.35	-0.12	9.88-11.88 ft	X	X	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-12-14	9/22/2016	12 - 14 ft	850.47	850.35	-0.12	11.88-13.88 ft	-	X	-	-	-
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-8-10	9/22/2016	8 - 10 ft	850.47	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B544	SSHS-B544-SUB-8-10	9/22/2016	8 - 10 ft	851.21	851.02	-0.19	7.81-9.81 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B544	SSHS-B544-SUB-4-6	9/22/2016	4 - 6 ft	851.21	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B545	SSHS-B545-SUB-10-12	9/22/2016	10 - 12 ft	850.94	850.75	-0.19	9.81-11.81 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B545	SSHS-B545-SUB-8-10	9/22/2016	8 - 10 ft	850.94	850.75	-0.19	7.81-9.81 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-4-6	9/22/2016	4 - 6 ft	851.35	851.20	-0.15	3.85-5.85 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-6-8	9/22/2016	6 - 8 ft	851.35	851.20	-0.15	5.85-7.85 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-8-10	9/22/2016	8 - 10 ft	851.35	851.20	-0.15	7.85-9.85 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B523	SSHS-B523-SUB-0-2	9/23/2016	0 - 2 ft	854.05	-	-	-	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-10-12	9/27/2016	10 - 12 ft	854.61	855.67	1.06	11.06-13.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-12-14	9/27/2016	12 - 14 ft	854.61	855.67	1.06	13.06-15.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-14-16	9/27/2016	14 - 16 ft	854.61	855.67	1.06	15.06-17.06 ft	X	-	-	-	-
Football Field	SSHS-B451	DUP2102	9/27/2016	16 - 18 ft	854.61	855.67	1.06	17.06-19.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-16-18	9/27/2016	16 - 18 ft	854.61	855.67	1.06	17.06-19.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-18-20	9/27/2016	18 - 20 ft	854.61	855.67	1.06	19.06-21.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-4-6	9/27/2016	4 - 6 ft	854.61	855.67	1.06	5.06-7.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-6-8	9/27/2016	6 - 8 ft	854.61	855.67	1.06	7.06-9.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-8-10	9/27/2016	8 - 10 ft	854.61	855.67	1.06	9.06-11.06 ft	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-0-2	9/27/2016	0 - 2 ft	854.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B451	SSHS-B451-SUB-2-4	9/27/2016	2 - 4 ft	854.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B452	SSHS-B452-SUB-4-6	9/27/2016	4 - 6 ft	854.99	855.46	0.47	4.47-6.47 ft	X	-	-	-	-
Football Field	SSHS-B452	SSHS-B452-SUB-6-8	9/27/2016	6 - 8 ft	854.99	855.46	0.47	6.47-8.47 ft	X	-	-	-	-
Football Field	SSHS-B452	DUP2103	9/27/2016	8 - 10 ft	854.99	855.46	0.47	8.47-10.47 ft	X	-	-	-	-
Football Field	SSHS-B452	SSHS-B452-SUB-8-10	9/27/2016	8 - 10 ft	854.99	855.46	0.47	8.47-10.47 ft	X	-	-	-	-
Football Field	SSHS-B452	SSHS-B452-SUB-0-2	9/27/2016	0 - 2 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B452	SSHS-B452-SUB-2-4	9/27/2016	2 - 4 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B612	SSHS-B612-SS	2/7/2017	0 - 0.17 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B614	DUP-1	2/7/2017	0 - 0.17 ft	856.36	-	-	-	X	-	-	-	-
Football Field	SSHS-B614	SSHS-B614-SS	2/7/2017	0 - 0.17 ft	856.36	-	-	-	X	-	-	-	-
Football Field	SSHS-B615	SSHS-B615-SS	2/7/2017	0 - 0.17 ft	856.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B616	SSHS-B616-SS	2/7/2017	0 - 0.17 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B617	SSHS-B617-SS	2/7/2017	0 - 0.17 ft	855.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B618	SSHS-B618-SS	2/7/2017	0 - 0.17 ft	855.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B613	SSHS-B613-SS	2/8/2017	0 - 0.17 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B625	SSHS-B625-SUB-10-12	2/8/2017	10 - 12 ft	856.01	856.01	0.00	10-12 ft	X	-	-	-	-
Football Field	SSHS-B625	SSHS-B625-SUB-12-14	2/8/2017	12 - 14 ft	856.01	856.01	0.00	12-14 ft	X	-	-	-	-
Football Field	SSHS-B627	SSHS-B627-SUB-12-14	2/8/2017	12 - 14 ft	856.12	856.36	0.24	12.24-14.24 ft	X	-	-	-	-
Football Field	SSHS-B608	SSHS-B608-SS	2/9/2017	0 - 0.17 ft	855.41	-	-	-	X	-	-	-	-
Football Field	SSHS-B609	SSHS-B609-SS	2/9/2017	0 - 0.17 ft	855.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B611	PS-FD-3	2/9/2017	0 - 0.17 ft	857.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B611	SSHS-B611-SS	2/9/2017	0 - 0.17 ft	857.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-12-14	2/9/2017	12 - 14 ft	855.38	855.50	0.12	12.12-14.12 ft	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-14-16	2/9/2017	14 - 16 ft	855.38	855.50	0.12	14.12-16.12 ft	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-0.17-2	2/9/2017	0.17 - 2 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-10-12	2/9/2017	10 - 12 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-2-4	2/9/2017	2 - 4 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-4-6	2/9/2017	4 - 6 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-6-8	2/9/2017	6 - 8 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SUB-8-10	2/9/2017	8 - 10 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B626	SSHS-B626-SUB-10-12	2/9/2017	10 - 12 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B626	PS-FD-2	2/9/2017	12 - 14 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B626	SSHS-B626-SUB-12-14	2/9/2017	12 - 14 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B628	SSHS-B628-SUB-12-14	2/9/2017	12 - 14 ft	855.84	855.84	0.00	12-14 ft	X	-	-	-	-
Football Field	SSHS-B629	SSHS-B629-SUB-12-14	2/9/2017	12 - 14 ft	855.95	855.95	0.00	12-14 ft	X	-	-	-	-
Football Field	SSHS-B629	SSHS-B629-SUB-6-8	2/9/2017	6 - 8 ft	855.95	855.95	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B629	SSHS-B629-SUB-8-10	2/9/2017	8 - 10 ft	855.95	855.95	0.00	8-10 ft	X	-	-	-	-
Football Field	SSHS-B644	PS-FD-4	2/9/2017	10 - 12 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B644	SSHS-B644-SUB-10-12	2/9/2017	10 - 12 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B644	SSHS-B644-SUB-14-16	2/9/2017	14 - 16 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B644	SSHS-B644-SUB-12-14	2/9/2017	12 - 14 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B649	SSHS-B649-SUB-2-4	2/9/2017	2 - 4 ft	855.70	-	-	-	X	-	-	-	-
Football Field	SSHS-B668	021017 09:20_SSHS-B668-SUB-12-14	2/9/2017	12 - 14 ft	855.60	-	-	-	X	-	-	-	-
Football Field	SSHS-B668	021017 09:20_SSHS-B668-SUB-10-12	2/9/2017	10 - 12 ft	855.60	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B577	SSHS-B577-SUB-0.17-2	2/10/2017	0.17 - 2 ft	856.11	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B577	SSHS-B577-SUB-2-4	2/10/2017	2 - 4 ft	856.11	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B577	SSHS-B577-SS	2/10/2017	0 - 0.17 ft	856.11	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B577	021117 09:30_DUP-2	2/10/2017	0.17 - 2 ft	856.11	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	2/10/2017	2 - 4 ft	856.11	856.72	0.61	2.61-4.61 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	2/10/2017	2 - 4 ft	856.14	856.15	0.01	2.01-4.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-0.17-2	2/10/2017	0.17 - 2 ft	855.97	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	2/10/2017	4 - 6 ft	855.97	856.56	0.59	4.59-6.59 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B586	SSHS-B586-SS	2/10/2017	0 - 0.17 ft	855.97	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-2-4	2/10/2017	2 - 4 ft	855.97	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B595	SSHS-B595-SS	2/10/2017	0 - 0.17 ft	856.24	856.25	0.01	0-0.17 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B595	PS-FD-8	2/10/2017	0.17 - 2 ft	856.24	856.25	0.01	0.18-2.01 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B595	SSHS-B595-SUB-0.17-2	2/10/2017	0.17 - 2 ft	856.24	856.25	0.01	0.18-2.01 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B596	SSHS-B596-SS	2/10/2017	0 - 0.17 ft	855.41	855.78	0.37	0.37-0.54 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B596	SSHS-B596-SUB-0.17-2	2/10/2017	0.17 - 2 ft	855.41	855.78	0.37	0.54-2.37 ft	X	-	-	-	-
Football Field	SSHS-B605	SSHS-B605-SS	2/10/2017	0 - 0.17 ft	855.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B606	SSHS-B606-SS	2/10/2017	0 - 0.17 ft	855.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B607	SSHS-B607-SS	2/10/2017	0 - 0.17 ft	855.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B610	SSHS-B610-SS	2/10/2017	0 - 0.17 ft	854.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B624	SSHS-B624-SS	2/10/2017	0 - 0.17 ft	855.38	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-10-12	2/10/2017	10 - 12 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-12-14	2/10/2017	12 - 14 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-4-6	2/10/2017	4 - 6 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-6-8	2/10/2017	6 - 8 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-8-10	2/10/2017	8 - 10 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-10-12	2/10/2017	10 - 12 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-12-14	2/10/2017	12 - 14 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-2-4	2/10/2017	2 - 4 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	PS-FD-5	2/10/2017	4 - 6 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-4-6	2/10/2017	4 - 6 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-6-8	2/10/2017	6 - 8 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-8-10	2/10/2017	8 - 10 ft	855.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-12-14	2/10/2017	12 - 14 ft	855.23	855.23	0.00	12-14 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-0-2	2/10/2017	0 - 2 ft	855.22	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-2-4	2/10/2017	2 - 4 ft	855.22	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-4-6	2/10/2017	4 - 6 ft	855.22	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-8-10	2/10/2017	8 - 10 ft	855.22	-	-	-	X	-	-	-	-
Football Field	SSHS-B657	SSHS-B657-SUB-14-16	2/10/2017	14 - 16 ft	856.13	856.21	0.08	14.08-16.08 ft	X	-	-	-	-
Football Field	SSHS-B667	021117 09:30_SSHS-B667-SUB-10-12	2/10/2017	10 - 12 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B667	021117 09:30_SSHS-B667-SUB-12-14	2/10/2017	12 - 14 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B667	021117 09:30_SSHS-B667-SUB-14-16	2/10/2017	14 - 16 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B671	021117 09:30_SSHS-B671-SUB-10-12	2/10/2017	10 - 12 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B671	021117 09:30_PS-FD-6	2/10/2017	14 - 16 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B671	021117 09:30_SSHS-B671-SUB-14-16	2/10/2017	14 - 16 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	SSHS-B620-SUB-2-4	2/13/2017	2 - 4 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	SSHS-B620-SUB-4-6	2/13/2017	4 - 6 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	SSHS-B620-SUB-0-2	2/13/2017	0 - 2 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	SSHS-B620-SUB-10-12	2/13/2017	10 - 12 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	PS-FD-13	2/13/2017	6 - 8 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	SSHS-B620-SUB-6-8	2/13/2017	6 - 8 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B620	SSHS-B620-SUB-8-10	2/13/2017	8 - 10 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B621	SSHS-B621-SUB-10-12	2/13/2017	10 - 12 ft	854.74	855.25	0.51	10.51-12.51 ft	X	-	-	-	-
Football Field	SSHS-B621	SSHS-B621-SUB-12-14	2/13/2017	12 - 14 ft	854.74	855.25	0.51	12.51-14.51 ft	X	-	-	-	-
Football Field	SSHS-B621	SSHS-B621-SUB-14-16	2/13/2017	14 - 16 ft	854.74	855.25	0.51	14.51-16.51 ft	X	-	-	-	-
Football Field	SSHS-B621	PS-FD-12	2/13/2017	6 - 8 ft	854.74	-	-	-	X	-	-	-	-
Football Field	SSHS-B621	SSHS-B621-SUB-6-8	2/13/2017	6 - 8 ft	854.74	-	-	-	X	-	-	-	-
Football Field	SSHS-B621	SSHS-B621-SUB-8-10	2/13/2017	8 - 10 ft	854.74	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B636	PS-FD-10	2/13/2017	0 - 2 ft	855.28	855.28	0.00	0-2 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B636	SSHS-B636-SUB-0-2	2/13/2017	0 - 2 ft	855.28	855.28	0.00	0-2 ft	X	-	-	-	-
Football Field	SSHS-B645	SSHS-B645-SUB-14-16	2/13/2017	14 - 16 ft	855.01	855.48	0.47	14.47-16.47 ft	X	-	-	-	-
Football Field	SSHS-B645	SSHS-B645-SUB-10-12	2/13/2017	10 - 12 ft	855.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B645	SSHS-B645-SUB-12-14	2/13/2017	12 - 14 ft	855.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B646	SSHS-B646-SUB-12-14	2/13/2017	12 - 14 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B646	SSHS-B646-SUB-14-16	2/13/2017	14 - 16 ft	854.99	855.40	0.41	14.41-16.41 ft	X	-	-	-	-
Football Field	SSHS-B646	SSHS-B646-SUB-10-12	2/13/2017	10 - 12 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B655	SSHS-B655-SUB-4-6	2/13/2017	4 - 6 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B655	SSHS-B655-SUB-6-8	2/13/2017	6 - 8 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B655	SSHS-B655-SUB-8-10	2/13/2017	8 - 10 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B661	SSHS-B661-SUB-4-6	2/13/2017	4 - 6 ft	855.41	-	-	-	X	-	-	-	-
Football Field	SSHS-B666	021617 08:35_SSHS-B666-SUB-8-10	2/13/2017	8 - 10 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B669	021617 08:35_SSHS-B669-SUB-12-14	2/13/2017	12 - 14 ft	855.09	-	-	-	X	-	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B669	021617 08:35_SSHS-B669-SUB-10-12	2/13/2017	10 - 12 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B669	021617 08:35_SSHS-B669-SUB-14-16	2/13/2017	14 - 16 ft	855.09	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B581	SSHS-B581-SUB-2-4	2/14/2017	2 - 4 ft	856.09	856.86	0.77	2.77-4.77 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B582	SSHS-B582-SUB-2-4	2/14/2017	2 - 4 ft	856.23	856.89	0.66	2.66-4.66 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B583	SSHS-B583-SUB-2-4	2/14/2017	2 - 4 ft	856.19	857.52	1.33	3.33-5.33 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B584	SSHS-B584-SUB-2-4	2/14/2017	2 - 4 ft	855.99	856.47	0.48	2.48-4.48 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B584	PS-FD-19	2/14/2017	2 - 4 ft	855.99	856.47	0.48	2.48-4.48 ft	X	-	-	-	-
Football Field	SSHS-B619	SSHS-B619-SUB-0-2	2/14/2017	0 - 2 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B619	SSHS-B619-SUB-10-12	2/14/2017	10 - 12 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B619	PS-FD-14	2/14/2017	2 - 4 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B619	SSHS-B619-SUB-2-4	2/14/2017	2 - 4 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B619	SSHS-B619-SUB-4-6	2/14/2017	4 - 6 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B619	SSHS-B619-SUB-6-8	2/14/2017	6 - 8 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B619	SSHS-B619-SUB-8-10	2/14/2017	8 - 10 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B630	SSHS-B630-SUB-10-12	2/14/2017	10 - 12 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B630	SSHS-B630-SUB-12-14	2/14/2017	12 - 14 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B630	PS-FD-17	2/14/2017	8 - 10 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B630	SSHS-B630-SUB-8-10	2/14/2017	8 - 10 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B630	SSHS-B630-SUB-14-16	2/14/2017	14 - 16 ft	855.88	855.88	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-14-16	2/14/2017	14 - 16 ft	855.56	855.59	0.03	14.03-16.03 ft	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-0-2	2/14/2017	0 - 2 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-2-4	2/14/2017	2 - 4 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-6-8	2/14/2017	6 - 8 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-10-12	2/14/2017	10 - 12 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-12-14	2/14/2017	12 - 14 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-4-6	2/14/2017	4 - 6 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B650	SSHS-B650-SUB-8-10	2/14/2017	8 - 10 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	SSHS-B651-SUB-12-14	2/14/2017	12 - 14 ft	855.56	855.57	0.01	12.01-14.01 ft	X	-	-	-	-
Football Field	SSHS-B651	SSHS-B651-SUB-14-16	2/14/2017	14 - 16 ft	855.56	855.57	0.01	14.01-16.01 ft	X	-	-	-	-
Football Field	SSHS-B651	SSHS-651-SUB-0-2	2/14/2017	0 - 2 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	SSHS-B651-SUB-10-12	2/14/2017	10 - 12 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	SSHS-651-SUB-2-4	2/14/2017	2 - 4 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	SSHS-B651-SUB-4-6	2/14/2017	4 - 6 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	PS-FD-15	2/14/2017	6 - 8 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	SSHS-B651-SUB-6-8	2/14/2017	6 - 8 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B651	SSHS-B651-SUB-8-10	2/14/2017	8 - 10 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-4-6	2/14/2017	4 - 6 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	PS-FD-16	2/14/2017	6 - 8 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-6-8	2/14/2017	6 - 8 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-8-10	2/14/2017	8 - 10 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-12-14	2/14/2017	12 - 14 ft	855.55	855.58	0.03	12.03-14.03 ft	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-14-16	2/14/2017	14 - 16 ft	855.55	855.58	0.03	14.03-16.03 ft	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-0-2	2/14/2017	0 - 2 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-10-12	2/14/2017	10 - 12 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B652	SSHS-B652-SUB-2-4	2/14/2017	2 - 4 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B653	SSHS-B653-SUB-12-14	2/14/2017	12 - 14 ft	855.63	855.62	-0.01	11.99-13.99 ft	X	-	-	-	-
Football Field	SSHS-B653	SSHS-B653-SUB-14-16	2/14/2017	14 - 16 ft	855.63	855.62	-0.01	13.99-15.99 ft	X	-	-	-	-
Football Field	SSHS-B653	SSHS-B653-SUB-4-6	2/14/2017	4 - 6 ft	855.63	-	-	-	X	-	-	-	-
Football Field	SSHS-B653	SSHS-B653-SUB-6-8	2/14/2017	6 - 8 ft	855.63	-	-	-	X	-	-	-	-
Football Field	SSHS-B653	SSHS-B653-SUB-8-10	2/14/2017	8 - 10 ft	855.63	-	-	-	X	-	-	-	-
Football Field	SSHS-B653	SSHS-B653-SUB-10-12	2/14/2017	10 - 12 ft	855.63	-	-	-	X	-	-	-	-
Football Field	SSHS-B656	SSHS-B656-SUB-12-14	2/14/2017	12 - 14 ft	855.93	855.93	0.00	12-14 ft	X	-	-	-	-
Football Field	SSHS-B656	SSHS-B656-SUB-10-12	2/14/2017	10 - 12 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B670	021617 08:35_PS-FD-18	2/14/2017	14 - 16 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B670	021617 08:35_SSHS-B670-SUB-14-16	2/14/2017	14 - 16 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B576	SSHS-B576-SS	2/15/2017	0 - 0.17 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B576	SSHS-B576-SUB-0.17-2	2/15/2017	0.17 - 2 ft	855.75	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B578	SSHS-B578-SUB-0-2	2/15/2017	0 - 2 ft	857.45	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B578	PS-FD-20	2/15/2017	0 - 2 ft	857.45	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B578	SSHS-B578-SUB-2-4	2/15/2017	2 - 4 ft	856.31	857.46	1.15	3.15-5.15 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B579	SSHS-B579-SUB-0-2	2/15/2017	0 - 2 ft	856.16	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B579	SSHS-B579-SUB-2-4	2/15/2017	2 - 4 ft	856.16	856.78	0.62	2.62-4.62 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B587	PS-FD-21	2/15/2017	0 - 2 ft	856.06	858.19	2.13	2.13-4.13 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B587	SSHS-B587-SUB-0-2	2/15/2017	0 - 2 ft	856.06	858.19	2.13	2.13-4.13 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-0-2	2/15/2017	0 - 2 ft	856.06	858.01	1.95	1.95-3.95 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-4-6	2/15/2017	4 - 6 ft	856.06	858.01	1.95	5.95-7.95 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B591	SSHS-B591-SUB-0-2	2/15/2017	0 - 2 ft	856.21	857.85	1.64	1.64-3.64 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B592	SSHS-B592-SUB-0-2	2/15/2017	0 - 2 ft	856.38	857.26	0.88	0.88-2.88 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B593	SSHS-B593-SUB-0-2	2/15/2017	0 - 2 ft	856.22	856.93	0.71	0.71-2.71	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B594	PS-FD-22	2/15/2017	0 - 2 ft	856.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B594	SSHS-B594-SUB-0-2	2/15/2017	0 - 2 ft	856.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B594	SSHS-B594-SUB-2-4	2/15/2017	2 - 4 ft	856.17	856.69	0.52	2.52-4.52 ft	X	-	-	-	-
Football Field	SSHS-B660	SSHS-B660-SUB-4-6	2/15/2017	4 - 6 ft	856.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B662	021617 08:35_PS-FD-23	2/15/2017	4 - 6 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B662	021617 08:35_SSHS-B662-SUB-4-6	2/15/2017	4 - 6 ft	855.93	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B664	SSHS-B664-SUB-0-2	2/15/2017	0 - 2 ft	856.32	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B664	SSHS-B664-SUB-2-4	2/15/2017	2 - 4 ft	856.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B622	SSHS-B622-SUB-10-12	2/16/2017	10 - 12 ft	856.13	856.14	0.01	10.01-12.01 ft	X	-	-	-	-
Football Field	SSHS-B622	SSHS-B622-SUB-8-10	2/16/2017	8 - 10 ft	856.13	856.14	0.01	8.01-10.01 ft	X	-	-	-	-
Football Field	SSHS-B622	SSHS-B622-SUB-4-6	2/16/2017	4 - 6 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B622	SSHS-B622-SUB-6-8	2/16/2017	6 - 8 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B631	SSHS-B631-SUB-12-14	2/16/2017	12 - 14 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B631	SSHS-B631-SUB-14-16	2/16/2017	14 - 16 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B635	SSHS-B635-SUB-8-10	2/16/2017	8 - 10 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B635	SSHS-B635-SUB-12-14	2/16/2017	12 - 14 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B647	PS-FD-24	2/16/2017	14 - 16 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B647	SSHS-B647-SUB-14-16	2/16/2017	14 - 16 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B647	SSHS-B647-SUB-0-2	2/16/2017	0 - 2 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B654	SSHS-B654-SUB-10-12	2/16/2017	10 - 12 ft	855.76	855.77	0.01	10.01-12.01 ft	X	-	-	-	-
Football Field	SSHS-B654	SSHS-B654-SUB-4-6	2/16/2017	4 - 6 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B654	SSHS-B654-SUB-8-10	2/16/2017	8 - 10 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B658	SSHS-B658-SUB-14-16	2/16/2017	14 - 16 ft	856.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B659	SSHS-B659-SUB-14-16	2/16/2017	14 - 16 ft	856.83	856.83	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B659	PS-FD-27	2/16/2017	12 - 14 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B659	SSHS-B659-SUB-12-14	2/16/2017	12 - 14 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B659	SSHS-B659-SUB-8-10	2/16/2017	8 - 10 ft	856.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B672	021817 08:50_PS-FD-26	2/16/2017	6 - 8 ft	856.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B672	021817 08:50_SSHS-B672-SUB-6-8	2/16/2017	6 - 8 ft	856.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B673	021817 08:50_SSHS-B673-SUB-10-12	2/16/2017	10 - 12 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B673	021817 08:50_SSHS-B673-SUB-8-10	2/16/2017	8 - 10 ft	855.92	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-10-12	3/20/2017	10 - 12 ft	855.39	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-12-14	3/20/2017	12 - 14 ft	855.39	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-14-16	3/20/2017	14 - 16 ft	855.39	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-2-4	3/20/2017	2 - 4 ft	855.39	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-4-6	3/20/2017	4 - 6 ft	855.39	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-10-12	3/20/2017	10 - 12 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-12-14	3/20/2017	12 - 14 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-14-16	3/20/2017	14 - 16 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-2-4	3/20/2017	2 - 4 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-4-6	3/20/2017	4 - 6 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_PS-FD-2	3/20/2017	8 - 10 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-8-10	3/20/2017	8 - 10 ft	855.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_PS-FD-1	3/20/2017	10 - 12 ft	855.50	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-10-12	3/20/2017	10 - 12 ft	855.50	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-12-14	3/20/2017	12 - 14 ft	855.50	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-2-4	3/20/2017	2 - 4 ft	855.50	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-4-6	3/20/2017	4 - 6 ft	855.50	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B704	032117 09:20_SSHS-B704-SUB-2-4	3/20/2017	2 - 4 ft	855.70	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B716	032117 09:20_SSHS-B716-SUB-14-16	3/20/2017	14 - 16 ft	855.07	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B674	032217 08:50_SSHS-B674-SUB-0-2	3/21/2017	0 - 2 ft	856.28	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B674	032217 08:50_SSHS-B674-SUB-2-4	3/21/2017	2 - 4 ft	856.28	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B675	032217 08:50_SSHS-B675-SUB-0-2	3/21/2017	0 - 2 ft	857.36	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B676	032217 08:50_SSHS-B676-SUB-0-2	3/21/2017	0 - 2 ft	856.94	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B677	032217 08:50_PS-FD-3	3/21/2017	0 - 2 ft	856.08	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B677	SSHS-B677-SUB-0-2	3/21/2017	0 - 2 ft	856.08	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B677	SSHS-B677-SUB-2-4	3/21/2017	2 - 4 ft	856.08	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	3/21/2017	0 - 2 ft	856.07	857.58	1.51	1.51-3.51 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-2-4	3/21/2017	2 - 4 ft	855.48	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_PS-FD-5	3/21/2017	10 - 12 ft	855.48	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-10-12	3/21/2017	10 - 12 ft	855.48	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-12-14	3/21/2017	12 - 14 ft	855.48	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-14-16	3/21/2017	14 - 16 ft	855.48	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-4-6	3/21/2017	4 - 6 ft	855.48	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B694	032217 08:50_SSHS-B694-SUB-10-12	3/21/2017	10 - 12 ft	855.61	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-2-4	3/21/2017	2 - 4 ft	855.71	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	10 - 12 ft	855.71	855.71	0.00	10 - 12 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	12 - 14 ft	855.71	855.71	0.00	12 - 14 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	14 - 16 ft	855.71	855.71	0.00	14 - 16 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	4 - 6 ft	855.71	855.71	0.00	4 - 6 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B718	032217 08:50_SSHS-B718-SUB-14-16	3/21/2017	14 - 16 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	10 - 12 ft	855.02	855.65	0.63	10.63-12.63 ft	X	-	-	-	-
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-12-14	3/22/2017	12 - 14 ft	855.02	855.65	0.63	12.63-14.63 ft	X	-	-	-	-
Football Field	SSHS-B684	032317 09:00_SSHS-B684-SUB-10-12	3/22/2017	10 - 12 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B684	032317 09:00_SSHS-B684-SUB-12-14	3/22/2017	12 - 14 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B686	032317 09:00_SSHS-B686-SUB-10-12	3/22/2017	10 - 12 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B686	032317 09:00_SSHS-B686-SUB-12-14	3/22/2017	12 - 14 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B687	032317 09:00_SSHS-B687-SUB-10-12	3/22/2017	10 - 12 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B700	032317 09:00_SSHS-B700-SUB-10-12	3/22/2017	10 - 12 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B700	032317 09:00_PS-FD-7	3/22/2017	12 - 14 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B700	032317 09:00_SSHS-B700-SUB-12-14	3/22/2017	12 - 14 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B700	032317 09:00_SSHS-B700-SUB-6-8	3/22/2017	6 - 8 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B706	032317 09:00_SSHS-B706-SUB-10-12	3/22/2017	10 - 12 ft	855.85	-	-	-	X	-	-	-	-
Football Field	SSHS-B707	032317 09:00_SSHS-B707-SUB-4-6	3/22/2017	4 - 6 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B707	032317 09:00_SSHS-B707-SUB-10-12	3/22/2017	10 - 12 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B707	032317 09:00_PS-FD-8	3/22/2017	4 - 6 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B709	032317 09:00_SSHS-B709-SUB-6-8	3/22/2017	6 - 8 ft	855.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B712	032317 09:00_SSHS-B712-SUB-10-12	3/22/2017	10 - 12 ft	856.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B714	032317 09:00_SSHS-B714-SUB-12-14	3/22/2017	12 - 14 ft	856.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B715	032317 09:00_SSHS-B715-SUB-12-14	3/22/2017	12 - 14 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B715	032317 09:00_PS-FD-6	3/22/2017	8 - 10 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B715	032317 09:00_SSHS-B715-SUB-8-10	3/22/2017	8 - 10 ft	855.856	-	-	-	X	-	-	-	-
Football Field	SSHS-B719	SSHS-B719-SUB-14-16	3/22/2017	14 - 16 ft	855.53	-	-	-	X	-	-	-	-
Football Field	SSHS-B685	032417 08:45_SSHS-B685-SUB-10-12	3/23/2017	10 - 12 ft	855.54	-	-	-	X	-	-	-	-
Football Field	SSHS-B685	032417 08:45_SSHS-B685-SUB-12-14	3/23/2017	12 - 14 ft	855.54	-	-	-	X	-	-	-	-
Football Field	SSHS-B685	032417 08:45_SSHS-B685-SUB-14-16	3/23/2017	14 - 16 ft	855.54	-	-	-	X	-	-	-	-
Football Field	SSHS-B701	032417 08:45_SSHS-B701-SUB-10-12	3/23/2017	10 - 12 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B701	032417 08:45_SSHS-B701-SUB-12-14	3/23/2017	12 - 14 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B701	032417 08:45_SSHS-B701-SUB-8-10	3/23/2017	8 - 10 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B710	032417 08:45_SSHS-B710-SUB-6-8	3/23/2017	6 - 8 ft	856.19	-	-	-	X	-	-	-	-
Football Field	SSHS-B711	032417 08:45_SSHS-B711-SUB-6-8	3/23/2017	6 - 8 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B717	032417 08:45_SSHS-B717-SUB-14-16	3/23/2017	14 - 16 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B733	SSHS-B733-SS	4/11/2017	0 - 0.17 ft	856.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B734	PS-FD-1	4/11/2017	0 - 0.17 ft	856.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B734	SSHS-B734-SS	4/11/2017	0 - 0.17 ft	856.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B735	SSHS-B735-SS	4/11/2017	0 - 0.17 ft	857.01	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B720	SSHS-B720-SUB-2-4	4/12/2017	2 - 4 ft	855.48	855.48	0.00	2-4 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B720	SSHS-B720-SUB-4-6	4/12/2017	4 - 6 ft	855.48	855.48	0.00	4-6 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B722	SSHS-B722-SUB-2-4	4/12/2017	2 - 4 ft	855.14	855.14	0.00	2-4 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B722	SSHS-B722-SUB-4-6	4/12/2017	4 - 6 ft	855.14	855.14	0.00	4-6 ft	X	-	-	-	-
Football Field	SSHS-B724	SSHS-B724-SUB-12-14	4/12/2017	12 - 14 ft	855.97	856.12	0.15	12.15-14.15 ft	X	-	-	-	-
Football Field	SSHS-B724	SSHS-B724-SUB-10-12	4/12/2017	10 - 12 ft	855.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B730	SSHS-B730-SUB-14-16	4/12/2017	14 - 16 ft	855.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B739	SSHS-B739-SUB-2-4	4/12/2017	2 - 4 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B739	SSHS-B739-SUB-4-6	4/12/2017	4 - 6 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B739	PS-FD-3	4/12/2017	6 - 8 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B739	SSHS-B739-SUB-6-8	4/12/2017	6 - 8 ft	855.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B741	SSHS-B741-SUB-8-10	4/12/2017	8 - 10 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B742	SSHS-B742-SUB-10-12	4/12/2017	10 - 12 ft	855.72	-	-	-	X	-	-	-	-
Football Field	SSHS-B742	SSHS-B742-SUB-12-14	4/12/2017	12 - 14 ft	855.72	-	-	-	X	-	-	-	-
Football Field	SSHS-B723	SSHS-B723-SUB-6-8	4/13/2017	6 - 8 ft	856.74	-	-	-	X	-	-	-	-
Football Field	SSHS-B723	SSHS-B723-SUB-16-18	4/13/2017	16 - 18 ft	856.74	856.74	0.00	16-18 ft	X	-	-	-	-
Football Field	SSHS-B723	SSHS-B723-SUB-18-20	4/13/2017	18 - 20 ft	856.74	856.74	0.00	18-20 ft	X	-	-	-	-
Football Field	SSHS-B740	PS-FD-4	4/13/2017	2 - 4 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B740	SSHS-B740-SUB-2-4	4/13/2017	2 - 4 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B743	SSHS-B743-SUB-6-8	4/13/2017	6 - 8 ft	855.75	855.75	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B743	SSHS-B743-SUB-0-2	4/13/2017	0 - 2 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B744	SSHS-B744-SUB-0-2	4/13/2017	0 - 2 ft	856.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B744	SSHS-B744-SUB-2-4	4/13/2017	2 - 4 ft	856.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B787	SSHS-B787-SUB-8-10	5/15/2017	8 - 10 ft	855.70	-	-	-	X	-	-	-	-
Football Field	SSHS-B793	SSHS-B793-SUB-4-6	5/15/2017	4 - 6 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B793	SSHS-B793-SUB-6-8	5/15/2017	6 - 8 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B807	SSHS-B807-SUB-4-6	5/15/2017	4 - 6 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B807	SSHS-B807-SUB-6-8	5/15/2017	6 - 8 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B807	PS-FD-1	5/15/2017	8 - 10 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B807	SSHS-B807-SUB-8-10	5/15/2017	8 - 10 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B809	SSHS-B809-SUB-2-4	5/15/2017	2 - 4 ft	855.49	-	-	-	X	-	-	-	-
Football Field	SSHS-B812	SSHS-B812-SUB-12-14	5/15/2017	12 - 14 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B812	SSHS-B812-SUB-8-10	5/15/2017	8 - 10 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B782	SSHS-B782-SUB-2-4	5/16/2017	2 - 4 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B788	SSHS-B788-SUB-10-12	5/16/2017	10 - 12 ft	855.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B791	SSHS-B791-SUB-2-4	5/16/2017	2 - 4 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B791	PS-FD-2	5/16/2017	2 - 4 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B791	SSHS-B791-SUB-4-6	5/16/2017	4 - 6 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B792	SSHS-B792-SUB-12-14	5/16/2017	12 - 14 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B792	SSHS-B792-SUB-8-10	5/16/2017	8 - 10 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B792	SSHS-B792-SUB-14-16	5/16/2017	14 - 16 ft	855.95	855.96	0.01	14.01-16.01 ft	X	-	-	-	-
Football Field	SSHS-B792	SSHS-B792-SUB-10-12	5/16/2017	10 - 12 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B794	SSHS-B794-SUB-4-6	5/16/2017	4 - 6 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B794	SSHS-B794-SUB-2-4	5/16/2017	2 - 4 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B794	PS-FD-6	5/16/2017	6 - 8 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B794	SSHS-B794-SUB-6-8	5/16/2017	6 - 8 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B795	SSHS-B795-SUB-2-4	5/16/2017	2 - 4 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B795	SSHS-B795-SUB-4-6	5/16/2017	4 - 6 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B795	PS-FD-3	5/16/2017	6 - 8 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B795	SSHS-B795-SUB-6-8	5/16/2017	6 - 8 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B795	SSHS-B795-SUB-8-10	5/16/2017	8 - 10 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B796	SSHS-B796-SUB-4-6	5/16/2017	4 - 6 ft	856.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B796	SSHS-B796-SUB-6-8	5/16/2017	6 - 8 ft	856.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B797	PS-FD-5	5/16/2017	6 - 8 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B797	SSHS-B797-SUB-6-8	5/16/2017	6 - 8 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B797	SSHS-B797-SUB-4-6	5/16/2017	4 - 6 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B798	SSHS-B798-SUB-10-12	5/16/2017	10 - 12 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B798	SSHS-B798-SUB-2-4	5/16/2017	2 - 4 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B798	SSHS-B798-SUB-8-10	5/16/2017	8 - 10 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B803	SSHS-B803-SUB-14-16	5/16/2017	14 - 16 ft	855.86	855.86	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B803	SSHS-B803-SUB-10-12	5/16/2017	10 - 12 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B803	SSHS-B803-SUB-12-14	5/16/2017	12 - 14 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B803	SSHS-B803-SUB-4-6	5/16/2017	4 - 6 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B803	SSHS-B803-SUB-6-8	5/16/2017	6 - 8 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B803	SSHS-B803-SUB-8-10	5/16/2017	8 - 10 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B804	SSHS-B804-SUB-10-12	5/16/2017	10 - 12 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B804	SSHS-B804-SUB-12-14	5/16/2017	12 - 14 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B804	SSHS-B804-SUB-14-16	5/16/2017	14 - 16 ft	855.75	855.74	-0.01	13.99-15.99 ft	X	-	-	-	-
Football Field	SSHS-B804	SSHS-B804-SUB-4-6	5/16/2017	4 - 6 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B804	SSHS-B804-SUB-8-10	5/16/2017	8 - 10 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B805	PS-FD-4	5/16/2017	8 - 10 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B808	SSHS-B808-SUB-4-6	5/16/2017	4 - 6 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B811	SSHS-B811-SUB-12-14	5/16/2017	12 - 14 ft	855.61	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B783	SSHS-B783-SUB-2-4	5/17/2017	2 - 4 ft	855.31	855.31	0.00	2-4 ft	X	-	-	-	-
Football Field	SSHS-B785	SSHS-B785-SUB-6-8	5/17/2017	6 - 8 ft	855.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B786	PS-FD-7	5/17/2017	6 - 8 ft	855.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B786	SSHS-B786-SUB-6-8	5/17/2017	6 - 8 ft	855.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B790	SSHS-B790-SUB-2-4	5/17/2017	2 - 4 ft	855.88	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-12-14	5/17/2017	12 - 14 ft	855.37	855.37	0.00	12-14 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-14-16	5/17/2017	14 - 16 ft	855.37	855.37	0.00	14-16 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B799	PS-FD-8	5/17/2017	10 - 12 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-10-12	5/17/2017	10 - 12 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-2-4	5/17/2017	2 - 4 ft	855.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-10-12	5/17/2017	10 - 12 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-12-14	5/17/2017	12 - 14 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-4-6	5/17/2017	4 - 6 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-6-8	5/17/2017	6 - 8 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-8-10	5/17/2017	8 - 10 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-14-16	5/17/2017	14 - 16 ft	855.92	855.97	0.05	14.05-16.05 ft	X	-	-	-	-
Football Field	SSHS-B800	SSHS-B800-SUB-2-4	5/17/2017	2 - 4 ft	855.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B801	SSHS-B801-SUB-4-6	5/17/2017	4 - 6 ft	856.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B801	PS-FD-9	5/17/2017	10 - 12 ft	856.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B801	SSHS-B801-SUB-10-12	5/17/2017	10 - 12 ft	856.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B801	SSHS-B801-SUB-12-14	5/17/2017	12 - 14 ft	856.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B801	SSHS-B801-SUB-8-10	5/17/2017	8 - 10 ft	856.98	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B802	SSHS-B802-SUB-12-14	5/17/2017	12 - 14 ft	856.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B802	SSHS-B802-SUB-8-10	5/17/2017	8 - 10 ft	856.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B805	SSHS-B805-SUB-10-12	5/17/2017	10 - 12 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B805	SSHS-B805-SUB-4-6	5/17/2017	4 - 6 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B814	SSHS-B814-SS	5/18/2017	0 - 0.17 ft	855.66	-	-	-	X	-	-	-	-
Football Field	SSHS-B814	SSHS-B814-SUB-0.17-2	5/18/2017	0.17 - 2 ft	855.66	-	-	-	X	-	-	-	-
Football Field	SSHS-B815	SSHS-B815-SS	5/18/2017	0 - 0.17 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B815	PS-FD-10	5/18/2017	0.17 - 2 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B815	SSHS-B815-SUB-0.17-2	5/18/2017	0.17 - 2 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B816	SSHS-B816-SS	5/18/2017	0 - 0.17 ft	856.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B816	SSHS-B816-SUB-0.17-2	5/18/2017	0.17 - 2 ft	856.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B817	SSHS-B817-SS	5/18/2017	0 - 0.17 ft	855.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B817	SSHS-B817-SUB-0.17-2	5/18/2017	0.17 - 2 ft	855.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B818	SSHS-B818-SS	5/18/2017	0 - 0.17 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B818	SSHS-B818-SUB-0.17-2	5/18/2017	0.17 - 2 ft	856.02	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B745	PS-FD-13	5/22/2017	0 - 2 ft	855.73	856.22	0.49	0.49-2.49 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B745	SSHS-B745-SUB-0-2	5/22/2017	0 - 2 ft	855.73	856.22	0.49	0.49-2.49 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B746	SSHS-B746-SUB-0-2	5/22/2017	0 - 2 ft	855.63	856.41	0.78	0.78-2.78 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B747	SSHS-B747-SUB-0-2	5/22/2017	0 - 2 ft	856.07	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B747	SSHS-B747-SUB-2-4	5/22/2017	2 - 4 ft	856.07	856.37	0.30	2.30-4.30 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B748	SSHS-B748-SUB-0-2	5/22/2017	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B748	SSHS-B748-SUB-2-4	5/22/2017	2 - 4 ft	856.15	856.67	0.52	2.52-4.52 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B749	PS-FD-11	5/22/2017	0 - 2 ft	856.27	856.91	0.64	0.64-2.64 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B749	SSHS-B749-SUB-0-2	5/22/2017	0 - 2 ft	856.27	856.91	0.64	2.64-4.64 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B750	SSHS-B750-SUB-0-2	5/22/2017	0 - 2 ft	856.17	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B750	SSHS-B750-SUB-2-4	5/22/2017	2 - 4 ft	856.17	856.71	0.54	2.54-4.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-0-2	5/22/2017	0 - 2 ft	856.21	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-0-2	5/22/2017	0 - 2 ft	856.21	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-2-4	5/22/2017	2 - 4 ft	856.21	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-2-4	5/22/2017	2 - 4 ft	856.21	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B752	PS-FD-12	5/22/2017	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B752	SSHS-B752-SUB-0-2	5/22/2017	0 - 2 ft	856.15	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B752	SSHS-B752-SUB-2-4	5/22/2017	2 - 4 ft	856.15	856.60	0.45	2.45-4.45 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B756	SSHS-B756-SUB-2-4	5/22/2017	2 - 4 ft	856.09	856.56	0.47	2.47-4.47 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B757	SSHS-B757-SUB-2-4	5/22/2017	2 - 4 ft	856.25	857.10	0.85	2.85-4.85 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B758	SSHS-B758-SUB-0-2	5/22/2017	0 - 2 ft	856.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B758	SSHS-B758-SUB-2-4	5/22/2017	2 - 4 ft	856.30	857.16	0.86	2.86-4.86 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B759	PS-FD-14	5/22/2017	0 - 2 ft	856.24	857.82	1.58	1.58-3.58 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B759	SSHS-B759-SUB-0-2	5/22/2017	0 - 2 ft	856.24	857.82	1.58	1.58-3.58 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B761	SSHS-B761-SUB-2-4	5/22/2017	2 - 4 ft	856.13	856.73	0.60	2.6-4.6 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B765	SSHS-B765-SUB-0-2	5/22/2017	0 - 2 ft	856.08	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B765	SSHS-B765-SUB-2-4	5/22/2017	2 - 4 ft	856.08	856.48	0.40	2.40-4.40 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B766	SSHS-B766-SUB-0-2	5/22/2017	0 - 2 ft	856.26	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B766	SSHS-B766-SUB-2-4	5/22/2017	2 - 4 ft	856.26	856.88	0.62	2.62-4.62 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B767	SSHS-B767-SUB-0-2	5/22/2017	0 - 2 ft	855.87	856.21	0.34	0.34-2.34 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B768	SSHS-B768-SUB-0-2	5/22/2017	0 - 2 ft	855.82	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B768	SSHS-B768-SUB-2-4	5/22/2017	2 - 4 ft	855.82	855.87	0.05	2.05-4.05 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B769	SSHS-B769-SUB-0-2	5/22/2017	0 - 2 ft	855.85	856.07	0.22	0.22-2.22 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B770	SSHS-B770-SUB-0-2	5/22/2017	0 - 2 ft	856.04	856.56	0.52	0.52-2.52 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-0-2	5/22/2017	0 - 2 ft	856.31	857.09	0.78	0.78-2.78 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-2-4	5/22/2017	2 - 4 ft	856.31	857.09	0.78	2.78-4.78 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B772	SSHS-B772-SUB-0-2	5/22/2017	0 - 2 ft	856.30	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B772	SSHS-B772-SUB-2-4	5/22/2017	2 - 4 ft	856.30	857.04	0.74	2.74-4.74 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B773	SSHS-B773-SUB-0-2	5/22/2017	0 - 2 ft	856.38	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B773	SSHS-B773-SUB-2-4	5/22/2017	2 - 4 ft	856.38	857.12	0.74	2.74-4.74 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B774	SSHS-B774-SUB-0-2	5/22/2017	0 - 2 ft	856.38	857.34	0.96	0.96-2.96 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B778	SSHS-B778-SUB-0-2	5/22/2017	0 - 2 ft	855.75	858.14	2.39	2.39-4.39 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B778	SSHS-B778-SUB-2-4	5/22/2017	2 - 4 ft	855.75	858.14	2.39	4.39-6.39 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B779	SSHS-B779-SUB-0-2	5/22/2017	0 - 2 ft	856.22	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B780	SSHS-B780-SUB-0-2	5/22/2017	0 - 2 ft	857.31	857.29	-0.02	0-1.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B753	SSHS-B753-SUB-2-4	5/23/2017	2 - 4 ft	856.28	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B754	SSHS-B754-SUB-2-4	5/23/2017	2 - 4 ft	856.12	856.86	0.74	2.74-4.74 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B755	SSHS-B755-SUB-2-4	5/23/2017	2 - 4 ft	856.01	856.68	0.67	2.67-4.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B760	SSHS-B760-SUB-2-4	5/23/2017	2 - 4 ft	856.25	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B762	SSHS-B762-SUB-2-4	5/23/2017	2 - 4 ft	856.41	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B763	SSHS-B763-SUB-2-4	5/23/2017	2 - 4 ft	856.04	856.62	0.58	2.58-4.58 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-0-2	5/23/2017	0 - 2 ft	855.99	858.05	2.06	2.06-4.06 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-2-4	5/23/2017	2 - 4 ft	855.99	858.05	2.06	4.06-6.06 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B781	SSHS-B781-SUB-2-4	5/23/2017	2 - 4 ft	856.09	857.50	1.41	3.41 - 5.41 ft	X	-	-	-	-
Football Field	SSHS-B791	PS-FD-16	5/23/2017	6 - 8 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B791	SSHS-B791-SUB-6-8	5/23/2017	6 - 8 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B820	PS-FD-17	5/23/2017	4 - 6 ft	856.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B820	SSHS-B820-SUB-4-6	5/23/2017	4 - 6 ft	856.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B820	SSHS-B820-SUB-6-8	5/23/2017	6 - 8 ft	856.20	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	0 - 2 ft	855.66	858.45	2.79	2.79-4.79 ft	X	X	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	10 - 12 ft	855.66	858.45	2.79	12.79-14.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	12 - 14 ft	855.66	858.45	2.79	14.79-16.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	14 - 16 ft	855.66	858.45	2.79	16.79-18.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	14 - 16 ft	855.66	858.45	2.79	16.79-18.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	2 - 4 ft	855.66	858.45	2.79	4.79-6.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	4 - 6 ft	855.66	858.45	2.79	6.79-8.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	6 - 8 ft	855.66	858.45	2.79	8.79-10.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	8 - 10 ft	855.66	858.45	2.79	10.79-12.79 ft	X	-	X	-	-
Tennis Courts / Main Parking Lot	SSHS-B822	DUP-1	6/19/2017	0 - 2 ft	856.39	857.30	0.91	0.91-2.91 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B822	SSHS-B822-SUB-0-2	6/19/2017	0 - 2 ft	856.39	857.30	0.91	0.91-2.91 ft	X	-	-	-	-
Football Field	SSHS-B284A	SSHS-B284A-SUB-4-6	7/10/2017	4 - 6 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B284A	PS-FD-1	7/10/2017	6 - 8 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B284A	SSHS-B284A-SUB-6-8	7/10/2017	6 - 8 ft	856.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B336A	SSHS-B336A-SUB-2-4	7/10/2017	2 - 4 ft	856.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B455A	SSHS-B455A-SUB-8-10	7/10/2017	8 - 10 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B629A	SSHS-B629A-SUB-6-8	7/10/2017	6 - 8 ft	855.95	855.95	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B629A	SSHS-B629A-SUB-8-10	7/10/2017	8 - 10 ft	855.95	855.95	0.00	8-10 ft	X	-	-	-	-
Football Field	SSHS-B671A	071117 08:30_SSHS-B671A-SUB-10-12	7/10/2017	10 - 12 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B686A	071117 08:30_SSHS-B686A-SUB-10-12	7/10/2017	10 - 12 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B712A	071117 08:30_SSHS-B712A-SUB-10-12	7/10/2017	10 - 12 ft	856.16	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-NE SIDEWALL S1	NORTH EXCAVATION SIDEWALL S1	7/10/2017	0 - 2 ft	856.41	-	-	-	X	-	-	-	-
Football Field	SSHS-B15A	SSHS-B15A-SUB-4-6	7/11/2017	4 - 6 ft	856.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B15A	SSHS-B15A-SUB-6-8	7/11/2017	6 - 8 ft	856.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B248A	PS-FD-3	7/11/2017	4 - 6 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B248A	SSHS-B248A-SUB-4-6	7/11/2017	4 - 6 ft	856.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B329A	SSHS-B329A-SUB-10-12	7/11/2017	10 - 12 ft	855.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B625A	SSHS-B625A-SUB-10-12	7/11/2017	10 - 12 ft	856.01	856.01	0.00	10-12 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-10-12	7/11/2017	10 - 12 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-12-14	7/11/2017	12 - 14 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632A	PS-FD-2	7/11/2017	4 - 6 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-4-6	7/11/2017	4 - 6 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-6-8	7/11/2017	6 - 8 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-8-10	7/11/2017	8 - 10 ft	855.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B803A	SSHS-B803A-SUB-10-12	7/11/2017	10 - 12 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B803A	SSHS-B803A-SUB-8-10	7/11/2017	8 - 10 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B804A	SSHS-B804A-SUB-4-6	7/11/2017	4 - 6 ft	855.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B255A	SSHS-B255A-SUB-4-6	7/12/2017	4 - 6 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B255A	SSHS-B255A-SUB-6-8	7/12/2017	6 - 8 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B630A	SSHS-B630A-SUB-14-16	7/12/2017	14 - 16 ft	855.88	855.88	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B657A	SSHS-B657A-SUB-14-16	7/12/2017	14 - 16 ft	856.13	856.21	0.08	14.08-16.08 ft	X	-	-	-	-
Football Field	SSHS-B671A	071317 07:30_SSHS-B671A-SUB-14-16	7/12/2017	14 - 16 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B685A	071317 07:30_SSHS-B685A-SUB-14-16	7/12/2017	14 - 16 ft	855.54	-	-	-	X	-	-	-	-
Football Field	SSHS-B717A	071317 07:30_SSHS-B717A-SUB-14-16	7/12/2017	14 - 16 ft	855.76	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B718A	071317 07:30_SSHS-B718A-SUB-14-16	7/12/2017	14 - 16 ft	855.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B782A	SSHS-B782A-SUB-2-4	7/12/2017	2 - 4 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B795A	SSHS-B795A-SUB-2-4	7/12/2017	2 - 4 ft	856.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B798A	PS-FD-6	7/12/2017	2 - 4 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B798A	SSHS-B798A-SUB-2-4	7/12/2017	2 - 4 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B803A	SSHS-B803A-SUB-14-16	7/12/2017	14 - 16 ft	855.86	855.86	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B804A	SSHS-B804A-SUB-14-16	7/12/2017	14 - 16 ft	855.75	855.74	-0.01	13.99-15.99 ft	X	-	-	-	-
Football Field	SSHS-B805A	SSHS-B805A-SUB-10-12	7/12/2017	10 - 12 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B805A	SSHS-B805A-SUB-4-6	7/12/2017	4 - 6 ft	856.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B278A	SSHS-B278A-SUB-2-4	7/13/2017	2 - 4 ft	855.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B330A	SSHS-B330A-SUB-6-8	7/13/2017	6 - 8 ft	856.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B330A	SSHS-B330A-SUB-8-10	7/13/2017	8 - 10 ft	856.86	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632B	SSHS-B632B-SUB-10-12	7/13/2017	10 - 12 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632B	SSHS-B632B-SUB-6-8	7/13/2017	6 - 8 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B632C	SSHS-B632C-SUB-0-2	7/13/2017	0 - 2 ft	855.37	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B679B	071417 08:00_SSHS-B679B-SUB-0-2	7/13/2017	0 - 2 ft	855.48	-	-	-	X	-	-	-	-
Football Field	SSHS-B685B	071417 08:00_SSHS-B685B-SUB-0-2	7/13/2017	0 - 2 ft	855.54	-	-	-	X	-	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B742A	SSHS-B742A-SUB-10-12	7/13/2017	10 - 12 ft	855.72	-	-	-	X	-	-	-	-
Football Field	SSHS-B797A	SSHS-B797A-SUB-4-6	7/13/2017	4 - 6 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B797A	DS-PD-7	7/13/2017	6 - 8 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B797A	SSHS-B797A-SUB-6-0	7/13/2017	6 - 8 ft	856.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B825	PS-FD-9	7/13/2017	0 - 2 ft	855.59	-	-	-	X	-	-	-	-
Football Field	SSHS-B825	SSHS-B825-SUB-0-2	7/13/2017	0 - 2 ft	855.59	-	-	-	X	-	-	-	-
Football Field	SSHS-B826	SSHS-B826-SUB-0-2	7/13/2017	0 - 2 ft	855.69	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B827	SSHS-B827-SUB-0-2	7/13/2017	0 - 2 ft	855.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B169B	B169-B	8/3/2017	0 - 0.5 ft	855.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-4-6	1/8/2018	4 - 6 ft	852.22	852.35	0.13	4.13-6.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-0-2	1/8/2018	0 - 2 ft	852.22	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-2-4	1/8/2018	2 - 4 ft	852.22	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B869	SSHS-B869-SUB-2-4	1/8/2018	2 - 4 ft	852.60	852.55	-0.05	1.95-3.95 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B929	SSHS-B929-SUB-2-4	1/8/2018	2 - 4 ft	852.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-4-6	1/9/2018	4 - 6 ft	852.50	852.68	0.18	4.18-6.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-6-8	1/9/2018	6 - 8 ft	852.50	852.68	0.18	6.18-8.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-0-2	1/9/2018	0 - 2 ft	852.53	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-10-12	1/9/2018	10 - 12 ft	852.00	852.24	0.24	10.24-12.24 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-12-14	1/9/2018	12 - 14 ft	852.00	852.24	0.24	12.24-14.24 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-4-6	1/9/2018	4 - 6 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-2-4	1/9/2018	2 - 4 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-0-2	1/9/2018	0 - 2 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-6-8	1/9/2018	6 - 8 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-2-4	1/9/2018	2 - 4 ft	851.70	851.63	-0.07	1.93-3.93 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-4-6	1/9/2018	4 - 6 ft	851.70	851.63	-0.07	3.93-5.93 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B854	PS-FD-3	1/9/2018	0 - 2 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-0-2	1/9/2018	0 - 2 ft	851.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-2-4	1/9/2018	2 - 4 ft	852.32	852.74	0.42	2.42-4.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B864	PS-FD-2	1/9/2018	2 - 4 ft	852.32	852.74	0.42	2.42-4.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-4-6	1/9/2018	4 - 6 ft	852.32	852.74	0.42	4.42-6.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-6-8	1/9/2018	6 - 8 ft	852.32	852.74	0.42	6.42-8.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-0-2	1/9/2018	0 - 2 ft	852.32	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B894	SSHS-B894-SUB-4-6	1/9/2018	4 - 6 ft	853.55	853.68	0.13	4.13-6.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B894	SSHS-B894-SUB-2-4	1/9/2018	2 - 4 ft	853.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B895	SSHS-B895-SUB-4-6	1/9/2018	4 - 6 ft	851.80	851.77	-0.03	3.97-5.97 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B895	SSHS-B895-SUB-2-4	1/9/2018	2 - 4 ft	851.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-6-8	1/9/2018	6 - 8 ft	852.40	852.89	0.49	6.49-8.49 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-8-10	1/9/2018	8 - 10 ft	852.40	852.89	0.49	8.49-10.49 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B904	PS-FD-4	1/9/2018	2 - 4 ft	852.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-2-4	1/9/2018	2 - 4 ft	852.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-0-2	1/9/2018	0 - 2 ft	852.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-4-6	1/9/2018	4 - 6 ft	852.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B936	SSHS-B936-SUB-2-4	1/9/2018	2 - 4 ft	853.76	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B938	SSHS-B938-SUB-2-4	1/9/2018	2 - 4 ft	851.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-0-2	1/10/2018	0 - 2 ft	852.37	852.65	0.28	0.28-2.28 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-2-4	1/10/2018	2 - 4 ft	852.37	852.65	0.28	2.28-4.28 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-4-6	1/10/2018	4 - 6 ft	852.37	852.65	0.28	4.28-6.28 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-4-6	1/10/2018	4 - 6 ft	852.79	852.91	0.12	4.12-6.12 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-2-4	1/10/2018	2 - 4 ft	852.87	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B831	PS-FD-6	1/10/2018	0 - 2 ft	852.87	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-0-2	1/10/2018	0 - 2 ft	852.87	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B832	PS-FD-7	1/10/2018	2 - 4 ft	854.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-2-4	1/10/2018	2 - 4 ft	854.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-0-2	1/10/2018	0 - 2 ft	854.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-4-6	1/10/2018	4 - 6 ft	854.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-6-8	1/10/2018	6 - 8 ft	854.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-10-12	1/10/2018	10 - 12 ft	851.40	851.77	0.37	10.37-12.37 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-12-14	1/10/2018	12 - 14 ft	851.40	851.77	0.37	12.37-14.37 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-2-4	1/10/2018	2 - 4 ft	851.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-0-2	1/10/2018	0 - 2 ft	851.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-6-8	1/10/2018	6 - 8 ft	851.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-8-10	1/10/2018	8 - 10 ft	851.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-6-8	1/10/2018	6 - 8 ft	849.98	850.22	0.24	6.24-8.24 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-2-4	1/10/2018	2 - 4 ft	850.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-4-6	1/10/2018	4 - 6 ft	850.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B931	SSHS-B931-SUB-0-2	1/10/2018	0 - 2 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B931	SSHS-B931-SUB-4-6	1/10/2018	4 - 6 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-4-6	1/10/2018	4 - 6 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-0-2	1/10/2018	0 - 2 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B934	PS-FD-5	1/10/2018	0 - 2 ft	849.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B934	SSHS-B934-SUB-0-2	1/10/2018	0 - 2 ft	849.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B935	SSHS-B935-SUB-0-2	1/10/2018	0 - 2 ft	847.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B943	SSHS-B943-SUB-2-4	1/10/2018	2 - 4 ft	850.06	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-2-4	1/11/2018	2 - 4 ft	854.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-0-2	1/11/2018	0 - 2 ft	854.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B830	PS-FD-10	1/11/2018	0 - 2 ft	854.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-2-4	1/11/2018	2 - 4 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-6-8	1/11/2018	6 - 8 ft	851.20	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-2-4	1/11/2018	2 - 4 ft	853.20	853.51	0.31	2.31-4.31 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-4-6	1/11/2018	4 - 6 ft	853.20	853.51	0.31	4.31-6.31 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-0-2	1/11/2018	0 - 2 ft	853.61	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-6-8	1/11/2018	6 - 8 ft	851.07	850.66	-0.41	5.59-7.59 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-2-4	1/11/2018	2 - 4 ft	851.07	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B909	SSHS-909-SUB-2-4	1/11/2018	2 - 4 ft	849.90	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-2-4	1/11/2018	2 - 4 ft	849.70	850.44	0.74	2.74-4.74 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6	1/11/2018	4 - 6 ft	849.70	850.44	0.74	4.74-6.74 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B921	PS-FD-8	1/11/2018	2 - 4 ft	852.39	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B921	SSHS-B921-SUB-2-4	1/11/2018	2 - 4 ft	852.39	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B939	PS-FD-9	1/11/2018	2 - 4 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B939	SSHS-939-SUB-2-4	1/11/2018	2 - 4 ft	850.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6	1/11/2018	4 - 6 ft	849.70	850.44	0.74	4.74-6.74 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-0-2	1/12/2018	0 - 2 ft	853.08	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-2-4	1/12/2018	2 - 4 ft	853.08	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B834	PS-FD-13	1/12/2018	4 - 6 ft	853.08	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-4-6	1/12/2018	4 - 6 ft	853.08	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-6-8	1/12/2018	6 - 8 ft	853.08	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-0-2	1/12/2018	0 - 2 ft	852.96	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-2-4	1/12/2018	2 - 4 ft	852.96	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-4-6	1/12/2018	4 - 6 ft	852.96	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-6-8	1/12/2018	6 - 8 ft	852.96	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	0 - 2 ft	850.62	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	4 - 6 ft	850.62	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-6-8	1/12/2018	6 - 8 ft	850.62	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-6-8	1/12/2018	6 - 8 ft	851.80	852.52	0.72	6.72-8.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-10-12	1/12/2018	10 - 12 ft	851.80	852.52	0.72	10.72-12.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-12-14	1/12/2018	12 - 14 ft	851.80	852.52	0.72	12.72-14.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-8-10	1/12/2018	8 - 10 ft	851.80	852.52	0.72	8.72-10.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-0-2	1/12/2018	0 - 2 ft	852.37	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-2-4	1/12/2018	2 - 4 ft	852.37	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B898	PS-FD-12	1/12/2018	2 - 4 ft	852.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B898	SSHS-B898-SUB-2-4	1/12/2018	2 - 4 ft	852.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B898	SSHS-B898-SUB-4-6	1/12/2018	4 - 6 ft	852.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B898	SSHS-B898-SUB-6-8	1/12/2018	6 - 8 ft	852.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B915	SSHS-B915-SUB-2-4	1/12/2018	2 - 4 ft	852.83	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B919	SSHS-B919-SUB-10-12	1/12/2018	10 - 12 ft	851.30	851.09	-0.21	9.79-11.79 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B919	SSHS-B919-SUB-6-8	1/12/2018	6 - 8 ft	851.13	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B922	SSHS-B922-SUB-2-4	1/12/2018	2 - 4 ft	852.19	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B925	SSHS-B925-SUB-4-6	1/12/2018	4 - 6 ft	852.80	852.88	0.08	4.08-6.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B925	PS-FD-14	1/12/2018	2 - 4 ft	852.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B925	SSHS-B925-SUB-2-4	1/12/2018	2 - 4 ft	852.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B828	SSHS-B828-SUB-0-2	1/14/2018	0 - 2 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B828	PS-FD-16	1/14/2018	2 - 4 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B828	SSHS-B828-SUB-2-4	1/14/2018	2 - 4 ft	851.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B941	SSHS-B941-SUB-2-4	1/14/2018	2 - 4 ft	850.36	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B941	SSHS-B941-SUB-4-6	1/14/2018	4 - 6 ft	850.36	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B942	SSHS-B942-SUB-2-4	1/14/2018	2 - 4 ft	850.79	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-2-4	1/16/2018	2 - 4 ft	852.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	0 - 2 ft	852.30	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-10-12	1/16/2018	10 - 12 ft	850.90	850.66	-0.24	9.76-11.76 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-2-4	1/16/2018	2 - 4 ft	850.75	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B920	PS-FD-17	1/16/2018	4 - 6 ft	850.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-4-6	1/16/2018	4 - 6 ft	850.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-6-8	1/16/2018	6 - 8 ft	850.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-0-2	1/16/2018	0 - 2 ft	850.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-8-10	1/16/2018	8 - 10 ft	850.75	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B930	PS-FD-18	1/16/2018	2 - 4 ft	851.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-0-2	1/16/2018	0 - 2 ft	851.77	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-2-4	1/16/2018	2 - 4 ft	851.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-10-12	1/17/2018	10 - 12 ft	850.56	850.62	0.06	10.06-12.06 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-12-14	1/17/2018	12 - 14 ft	850.56	850.62	0.06	12.06-14.06 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-6-8	1/17/2018	6 - 8 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-0-2	1/17/2018	0 - 2 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	2 - 4 ft	850.70	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-8-10	1/17/2018	8 - 10 ft	850.70	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-10-12	1/17/2018	10 - 12 ft	850.40	850.24	-0.16	9.84-11.84 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B885	PS-FD-21	1/17/2018	2 - 4 ft	850.48	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-2-4	1/17/2018	2 - 4 ft	850.48	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-0-2	1/17/2018	0 - 2 ft	850.48	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-6-8	1/17/2018	6 - 8 ft	850.48	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-8-10	1/17/2018	8 - 10 ft	850.48	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-12-14	1/17/2018	12 - 14 ft	850.89	851.05	0.16	12.16-14.16 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-2-4	1/17/2018	2 - 4 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-0-2	1/17/2018	0 - 2 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B892	PS-FD-19	1/17/2018	4 - 6 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-4-6	1/17/2018	4 - 6 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-10-12	1/17/2018	10 - 12 ft	850.94	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-6-8	1/17/2018	6 - 8 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-8-10	1/17/2018	8 - 10 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-8-10	1/17/2018	8 - 10 ft	850.00	850.04	0.04	8.04-10.04 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	0 - 2 ft	850.31	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B905	PS-FD-20	1/17/2018	6 - 8 ft	850.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-6-8	1/17/2018	6 - 8 ft	850.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-4-6	1/17/2018	4 - 6 ft	850.31	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-10-12	1/18/2018	10 - 12 ft	850.25	850.52	0.27	10.27-12.27 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-12-14	1/18/2018	12 - 14 ft	850.25	850.52	0.27	12.27-14.27 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-8-10	1/18/2018	8 - 10 ft	850.25	850.52	0.27	8.27-10.27 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-0-2	1/18/2018	0 - 2 ft	850.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-2-4	1/18/2018	2 - 4 ft	850.25	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B839	PS-FD-25	1/18/2018	6 - 8 ft	850.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-6-8	1/18/2018	6 - 8 ft	850.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-10-12	1/18/2018	10 - 12 ft	851.50	851.17	-0.33	9.67-11.67 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-6-8	1/18/2018	6 - 8 ft	850.33	850.69	0.36	6.36-8.36 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B850	PS-FD-23	1/18/2018	2 - 4 ft	850.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-2-4	1/18/2018	2 - 4 ft	850.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-4-6	1/18/2018	4 - 6 ft	850.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-0-2	1/18/2018	0 - 2 ft	850.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-10-12	1/18/2018	10 - 12 ft	851.29	851.55	0.26	10.26-12.26 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B851	PS-FD-24	1/18/2018	0 - 2 ft	851.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-0-2	1/18/2018	0 - 2 ft	851.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-2-4	1/18/2018	2 - 4 ft	851.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-4-6	1/18/2018	4 - 6 ft	851.45	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-6-8	1/18/2018	6 - 8 ft	851.45	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-10-12	1/18/2018	10 - 12 ft	851.10	851.42	0.32	10.32-12.32 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-2-4	1/18/2018	2 - 4 ft	851.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-4-6	1/18/2018	4 - 6 ft	851.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	0 - 2 ft	851.27	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-6-8	1/18/2018	6 - 8 ft	851.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-8-10	1/18/2018	8 - 10 ft	851.27	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-12-14	1/18/2018	12 - 14 ft	850.56	851.07	0.51	12.51-14.51 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-2-4	1/18/2018	2 - 4 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-6-8	1/18/2018	6 - 8 ft	850.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	0 - 2 ft	850.94	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B918	SSHS-B918-SUB-6-8	1/18/2018	6 - 8 ft	850.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B918	SSHS-B918-SUB-8-10	1/18/2018	8 - 10 ft	850.41	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B926	SSHS-B926-SUB-2-4	1/18/2018	2 - 4 ft	852.34	853.06	0.72	2.72-4.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B843	PS-FD-29	1/19/2018	6 - 8 ft	851.40	851.34	-0.06	5.94-7.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-6-8	1/19/2018	6 - 8 ft	851.40	851.34	-0.06	5.94-7.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-8-10	1/19/2018	8 - 10 ft	851.40	851.34	-0.06	7.94-9.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-10-12	1/19/2018	10 - 12 ft	851.40	851.34	-0.06	9.94-11.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-4-6	1/19/2018	4 - 6 ft	851.03	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-2-4	1/19/2018	2 - 4 ft	851.03	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-2-4	1/19/2018	2 - 4 ft	850.69	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-4-6	1/19/2018	4 - 6 ft	850.69	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-6-8	1/19/2018	6 - 8 ft	850.69	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-10-12	1/19/2018	10 - 12 ft	851.20	851.36	0.16	10.16-12.16 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B852	PS-FD-28	1/19/2018	0 - 2 ft	851.29	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-0-2	1/19/2018	0 - 2 ft	851.29	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-2-4	1/19/2018	2 - 4 ft	851.29	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-4-6	1/19/2018	4 - 6 ft	851.29	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-6-8	1/19/2018	6 - 8 ft	851.29	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-8-10	1/19/2018	8 - 10 ft	851.29	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-10-12	1/19/2018	10 - 12 ft	851.30	851.82	0.52	10.52-12.52 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-12-14	1/19/2018	12 - 14 ft	851.30	851.82	0.52	12.52-14.52 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B879	PS-FD-27	1/19/2018	2 - 4 ft	851.64	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-2-4	1/19/2018	2 - 4 ft	851.64	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-8-10	1/19/2018	8 - 10 ft	851.30	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-6-8	1/19/2018	6 - 8 ft	851.64	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-10-12	1/19/2018	10 - 12 ft	850.37	850.66	0.29	10.29-12.29 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-12-14	1/19/2018	12 - 14 ft	850.37	850.66	0.29	12.29-14.29 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-0-2	1/19/2018	0 - 2 ft	850.66	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-2-4	1/19/2018	2 - 4 ft	850.66	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-4-6	1/19/2018	4 - 6 ft	850.66	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-6-8	1/19/2018	6 - 8 ft	850.66	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-8-10	1/19/2018	8 - 10 ft	850.66	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-10-12	1/19/2018	10 - 12 ft	851.10	851.65	0.55	10.55-12.55 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-0-2	1/19/2018	0 - 2 ft	851.47	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-2-4	1/19/2018	2 - 4 ft	851.47	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-4-6	1/19/2018	4 - 6 ft	851.47	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-6-8	1/19/2018	6 - 8 ft	851.47	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-10-12	1/19/2018	10 - 12 ft	850.90	851.38	0.48	10.48-12.48 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-12-14	1/19/2018	12 - 14 ft	850.90	851.38	0.48	12.48-14.48 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-2-4	1/19/2018	2 - 4 ft	851.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-0-2	1/19/2018	0 - 2 ft	851.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-4-6	1/19/2018	4 - 6 ft	851.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-6-8	1/19/2018	6 - 8 ft	851.16	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-2-4	1/19/2018	2 - 4 ft	850.80	850.99	0.19	2.19-4.19 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-6-8	1/19/2018	6 - 8 ft	850.80	850.99	0.19	6.19-8.19 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-8-10	1/19/2018	8 - 10 ft	850.80	850.99	0.19	8.19-10.19 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B924	SSHS-B924-SUB-2-4	1/19/2018	2 - 4 ft	851.60	852.22	0.62	2.62-4.62 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B933	SSHS-B933-SUB-2-4	1/19/2018	2 - 4 ft	850.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B933	PS-FD-26	1/19/2018	0 - 2 ft	850.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B933	SSHS-B933-SUB-0-2	1/19/2018	0 - 2 ft	850.91	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-4-6	1/20/2018	4 - 6 ft	852.37	852.79	0.42	4.42-6.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-0-2	1/20/2018	0 - 2 ft	852.83	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B837	PS-FD-32	1/20/2018	2 - 4 ft	852.83	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-2-4	1/20/2018	2 - 4 ft	852.83	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-12-14	1/20/2018	12 - 14 ft	849.70	849.74	0.04	12.04-14.04 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-2-4	1/20/2018	2 - 4 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-0-2	1/20/2018	0 - 2 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-4-6	1/20/2018	4 - 6 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-10-12	1/20/2018	10 - 12 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-6-8	1/20/2018	6 - 8 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-8-10	1/20/2018	8 - 10 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-10-12	1/20/2018	10 - 12 ft	850.05	849.85	-0.20	9.80-11.80 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-12-14	1/20/2018	12 - 14 ft	850.05	849.85	-0.20	11.80-13.80 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-2-4	1/20/2018	2 - 4 ft	850.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-4-6	1/20/2018	4 - 6 ft	850.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B841	PS-FD-30	1/20/2018	0 - 2 ft	850.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-0-2	1/20/2018	0 - 2 ft	850.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-6-8	1/20/2018	6 - 8 ft	850.17	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-8-10	1/20/2018	8 - 10 ft	850.17	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-6-8	1/20/2018	6 - 8 ft	851.78	852.12	0.34	6.34-8.34 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-2-4	1/20/2018	2 - 4 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-4-6	1/20/2018	4 - 6 ft	852.12	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-0-2	1/20/2018	0 - 2 ft	852.12	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-6-8	1/20/2018	6 - 8 ft	851.19	851.58	0.39	6.39-8.39 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-8-10	1/20/2018	8 - 10 ft	851.19	851.58	0.39	8.39-10.39 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B848	PS-FD-33	1/20/2018	2 - 4 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-2-4	1/20/2018	2 - 4 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-2-4	1/20/2018	2 - 4 ft	850.15	-	-	-	X	-	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-0-2	1/20/2018	0 - 2 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-4-6	1/20/2018	4 - 6 ft	850.15	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-2-4	1/20/2018	2 - 4 ft	853.66	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-4-6	1/20/2018	4 - 6 ft	853.66	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-0-2	1/20/2018	0 - 2 ft	853.66	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B875	SSHS-B875-SUB-2-4	1/20/2018	2 - 4 ft	852.93	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-10-12	1/20/2018	10 - 12 ft	851.47	851.87	0.40	10.40-12.40 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-8-10	1/20/2018	8 - 10 ft	851.47	851.87	0.40	8.40-10.40 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-6-8	1/20/2018	6 - 8 ft	851.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-10-12	1/20/2018	10 - 12 ft	851.96	852.10	0.14	10.14-12.14 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-8-10	1/20/2018	8 - 10 ft	852.06	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-2-4	1/20/2018	2 - 4 ft	852.06	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B883	PS-FD-31	1/20/2018	6 - 8 ft	852.06	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-6-8	1/20/2018	6 - 8 ft	852.06	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-2-4	1/20/2018	2 - 4 ft	852.09	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-4-6	1/20/2018	4 - 6 ft	852.09	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B912	SSHS-B912-SUB-2-4	1/20/2018	2 - 4 ft	851.46	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B937	SSHS-B937-SUB-4-6	1/20/2018	4 - 6 ft	851.90	852.53	0.63	4.63-6.63 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B944	SSHS-B944-SUB-4-6	1/20/2018	4 - 6 ft	850.11	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-6-8	1/22/2018	6 - 8 ft	851.80	851.59	-0.21	5.79-7.79 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-10-12	1/22/2018	10 - 12 ft	851.80	851.59	-0.21	9.79-11.79 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-8-10	1/22/2018	8 - 10 ft	851.80	851.59	-0.21	7.79-9.79 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-2-4	1/22/2018	2 - 4 ft	851.80	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B842	PS-FD-34	1/22/2018	4 - 6 ft	851.80	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-4-6	1/22/2018	4 - 6 ft	851.80	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-0-2	1/22/2018	0 - 2 ft	850.73	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	2 - 4 ft	850.73	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	4 - 6 ft	850.73	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-6-8	1/22/2018	6 - 8 ft	850.73	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-2-4	1/22/2018	2 - 4 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B880	PS-FD-36	1/22/2018	0 - 2 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-0-2	1/22/2018	0 - 2 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-10-12	1/22/2018	10 - 12 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-6-8	1/22/2018	6 - 8 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-6-8	1/22/2018	6 - 8 ft	848.90	849.62	0.72	6.72-8.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-8-10	1/22/2018	8 - 10 ft	848.90	849.62	0.72	8.72-10.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-2-4	1/22/2018	2 - 4 ft	849.63	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-0-2	1/22/2018	0 - 2 ft	849.63	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-4-6	1/22/2018	4 - 6 ft	849.63	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-10-12	1/22/2018	10 - 12 ft	849.80	849.67	-0.13	9.87-11.87 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-12-14	1/22/2018	12 - 14 ft	849.80	849.67	-0.13	11.87-13.87 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-0-2	1/22/2018	0 - 2 ft	850.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	2 - 4 ft	850.02	-	-	-	X	X	X	X	-
Rear Parking Lot	SSHS-B888	PS-FD-37	1/22/2018	0 - 2 ft	850.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-4-6	1/22/2018	4 - 6 ft	850.02	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-8-10	1/22/2018	8 - 10 ft	850.02	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	2 - 4 ft	852.03	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	4 - 6 ft	852.03	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-6-8	1/22/2018	6 - 8 ft	851.54	851.99	0.45	6.45-8.45 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-4-6	1/22/2018	4 - 6 ft	851.62	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B914	SSHS-B914-SUB-4-6	1/22/2018	4 - 6 ft	853.70	853.73	0.03	4.03-6.03 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B914	SSHS-B914-SUB-2-4	1/22/2018	2 - 4 ft	853.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B940	SSHS-B940-SUB-2-4	1/22/2018	2 - 4 ft	849.71	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-0-2	1/22/2018	0 - 2 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-2-4	1/22/2018	2 - 4 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-6-8	1/22/2018	6 - 8 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-4-6	1/22/2018	4 - 6 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-6-8	1/22/2018	6 - 8 ft	849.00	849.52	0.52	6.52-8.52 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-2-4	1/22/2018	2 - 4 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-4-6	1/22/2018	4 - 6 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B946	PS-FD-35	1/22/2018	0 - 2 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-0-2	1/22/2018	0 - 2 ft	850.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B947	SSHS-B947-SUB-6-8	1/22/2018	6 - 8 ft	851.09	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-4-6	1/23/2018	4 - 6 ft	854.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-6-8	1/23/2018	6 - 8 ft	854.01	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-4-6	1/23/2018	4 - 6 ft	851.20	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-10-12	1/23/2018	10 - 12 ft	850.33	850.69	0.36	10.36-12.36 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-8-10	1/23/2018	8 - 10 ft	850.33	850.69	0.36	8.36-10.36 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B875	SSHS-B875-SUB-4-6	1/23/2018	4 - 6 ft	852.93	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-10-12	1/23/2018	10 - 12 ft	851.90	852.26	0.36	10.36-12.36 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B890	PS-FD-38	1/23/2018	8 - 10 ft	851.90	852.26	0.36	8.36-10.36 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-8-10	1/23/2018	8 - 10 ft	851.90	852.26	0.36	8.36-10.36 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-2-4	1/23/2018	2 - 4 ft	851.62	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-8-10	1/23/2018	8 - 10 ft	851.68	851.70	0.02	8.02-10.02 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-6-8	1/23/2018	6 - 8 ft	851.77	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B938	SSHS-B938-SUB-4-6	1/23/2018	4 - 6 ft	851.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B939	SSHS-B939-SUB-6-8	1/23/2018	6 - 8 ft	850.07	850.20	0.13	6.13-8.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B948	PS-FD-39	1/23/2018	10 - 12 ft	851.70	851.83	0.13	10.13-12.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B948	SSHS-B948-SUB-10-12	1/23/2018	10 - 12 ft	851.70	851.83	0.13	10.13-12.13 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-4-6	1/24/2018	4 - 6 ft	851.33	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-6-8	1/24/2018	6 - 8 ft	851.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-6-8	1/24/2018	6 - 8 ft	850.66	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-10-12	1/24/2018	10 - 12 ft	850.60	850.52	-0.08	9.92-11.92 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-8-10	1/24/2018	8 - 10 ft	850.62	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-6-8	1/24/2018	6 - 8 ft	851.60	852.25	0.65	6.65-8.65 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B932	PS-FD-40	1/24/2018	2 - 4 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-2-4	1/24/2018	2 - 4 ft	850.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B942	SSHS-B942-SUB-8-10	1/24/2018	8 - 10 ft	851.00	850.61	-0.39	7.61-9.61 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-6-8	2/27/2018	6 - 8 ft	853.70	853.92	0.22	6.22-8.22 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-8-10	2/27/2018	8 - 10 ft	853.70	853.92	0.22	8.22-10.22 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-2-4	2/27/2018	2 - 4 ft	854.22	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B956	SSHS-B956-SUB-8-10	2/27/2018	8 - 10 ft	852.70	852.91	0.21	8.21-10.21 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B956	SSHS-B956-SUB-6-8	2/27/2018	6 - 8 ft	852.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B951	SSHS-B951-SUB-2-4	2/28/2018	2 - 4 ft	852.70	852.64	-0.06	1.94-3.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-4-6	2/28/2018	4 - 6 ft	853.70	853.92	0.22	4.22-6.22 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-12-14	2/28/2018	12 - 14 ft	852.80	852.80	0.00	12-14 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-8-10	2/28/2018	8 - 10 ft	852.80	852.80	0.00	8-10 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-6-8	2/28/2018	6 - 8 ft	852.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B959	PS-FD-3	2/28/2018	6 - 8 ft	851.40	851.14	-0.26	5.74-7.74 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-6-8	2/28/2018	6 - 8 ft	851.40	851.14	-0.26	5.74-7.74 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-8-10	2/28/2018	8 - 10 ft	851.40	851.14	-0.26	7.74-9.74 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B959	PS-FD-2	2/28/2018	0 - 2 ft	851.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-0-2	2/28/2018	0 - 2 ft	851.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-2-4	2/28/2018	2 - 4 ft	851.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-4-6	2/28/2018	4 - 6 ft	851.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B960	SSHS-B960-SUB-8-10	2/28/2018	8 - 10 ft	850.97	850.85	-0.12	7.88-9.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B960	SSHS-B960-SUB-2-4	2/28/2018	2 - 4 ft	850.88	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-10-12	2/28/2018	10 - 12 ft	851.85	852.05	0.20	10.20-12.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-12-14	2/28/2018	12 - 14 ft	851.85	852.05	0.20	12.20-14.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-8-10	2/28/2018	8 - 10 ft	851.85	852.05	0.20	8.20-10.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-2-4	2/28/2018	2 - 4 ft	852.05	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-4-6	2/28/2018	4 - 6 ft	852.05	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B982	SSHS-B982-SUB-2-4	2/28/2018	2 - 4 ft	851.56	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B982	SSHS-B982-SUB-4-6	2/28/2018	4 - 6 ft	851.56	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B983	PS-FD-1	2/28/2018	2 - 4 ft	851.11	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B983	SSHS-B983-SUB-2-4	2/28/2018	2 - 4 ft	851.11	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B985	SSHS-B985-SUB-6-8	2/28/2018	6 - 8 ft	851.33	851.63	0.30	6.30-8.30 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B985	SSHS-B985-SUB-4-6	2/28/2018	4 - 6 ft	851.36	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B998	SSHS-B998-SUB-8-10	2/28/2018	8 - 10 ft	851.30	850.55	-0.75	7.25-9.25 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B965	SSHS-B965-SUB-6-8	3/1/2018	6 - 8 ft	851.00	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B968	SSHS-B968-SUB-0-2	3/1/2018	0 - 2 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B968	SSHS-B968-SUB-2-4	3/1/2018	2 - 4 ft	851.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B969	PS-FD-6	3/1/2018	2 - 4 ft	850.19	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B969	SSHS-B969-SUB-2-4	3/1/2018	2 - 4 ft	850.19	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B969	SSHS-B969-SUB-4-6	3/1/2018	4 - 6 ft	850.19	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B970	SSHS-B970-SUB-4-6	3/1/2018	4 - 6 ft	850.71	850.32	-0.39	3.61-5.61 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-10-12	3/1/2018	10 - 12 ft	852.19	852.39	0.20	10.20-12.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-12-14	3/1/2018	12 - 14 ft	852.19	852.39	0.20	12.20-14.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-4-6	3/1/2018	4 - 6 ft	852.19	852.39	0.20	4.20-6.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-6-8	3/1/2018	6 - 8 ft	852.19	852.39	0.20	6.20-8.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-8-10	3/1/2018	8 - 10 ft	852.19	852.39	0.20	8.20-10.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-10-12	3/1/2018	10 - 12 ft	851.96	852.03	0.07	10.07-12.07 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-12-14	3/1/2018	12 - 14 ft	851.96	852.03	0.07	12.07-14.07 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-6-8	3/1/2018	6 - 8 ft	851.96	852.03	0.07	6.07-8.07 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-8-10	3/1/2018	8 - 10 ft	851.96	852.03	0.07	8.07-10.07 ft	X	-	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-4-6	3/1/2018	4 - 6 ft	851.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B984	SSHS-B984-SUB-4-6	3/1/2018	4 - 6 ft	851.89	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B993	PS-FD-4	3/1/2018	10 - 12 ft	851.75	851.76	0.01	10.01-12.01 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B993	SSHS-B993-SUB-10-12	3/1/2018	10 - 12 ft	851.75	851.76	0.01	10.01-12.01 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B993	SSHS-B993-SUB-12-14	3/1/2018	12 - 14 ft	851.75	851.76	0.01	12.01-14.01 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B994	SSHS-B994-SUB-4-6	3/1/2018	4 - 6 ft	852.12	852.52	0.40	4.40-6.40 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B995	PS-FD-5	3/1/2018	4 - 6 ft	849.89	849.94	0.05	4.05-6.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B995	SSHS-B995-SUB-4-6	3/1/2018	4 - 6 ft	849.89	849.94	0.05	4.05-6.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B995	SSHS-B995-SUB-0-2	3/1/2018	0 - 2 ft	850.03	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1004	SSHS-B1004-SUB-4-6	3/3/2018	4 - 6 ft	850.31	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1005	SSHS-B1005-SUB-4-6	3/3/2018	4 - 6 ft	851.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1006	SSHS-B1006-SUB-10-12	3/3/2018	10 - 12 ft	851.67	851.88	0.21	10.21-12.21 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1007	PS-FD-7	3/3/2018	12 - 14 ft	851.90	852.28	0.38	12.38-14.38 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1007	SSHS-B1007-SUB-12-14	3/3/2018	12 - 14 ft	851.90	852.28	0.38	12.38-14.38 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1008	SSHS-B1008-SUB-12-14	3/3/2018	12 - 14 ft	852.10	852.13	0.03	12.03-14.03 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B974	PS-FD-9	3/3/2018	4 - 6 ft	852.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B974	SSHS-B974-SUB-4-6	3/3/2018	4 - 6 ft	852.78	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B950	SSHS-B950-SUB-2-4	3/4/2018	2 - 4 ft	852.44	852.70	0.26	2.26-4.26 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B952	SSHS-B952-SUB-6-8	3/4/2018	6 - 8 ft	850.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B952	PS-FD-11	3/4/2018	10 - 12 ft	850.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B952	SSHS-B952-SUB-10-12	3/4/2018	10 - 12 ft	850.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-12-14	3/4/2018	12 - 14 ft	849.70	849.58	-0.12	11.88-13.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-6-8	3/4/2018	6 - 8 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-8-10	3/4/2018	8 - 10 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B958	PS-FD-13	3/4/2018	10 - 12 ft	851.26	851.68	0.42	10.42-12.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B958	SSHS-B958-SUB-10-12	3/4/2018	10 - 12 ft	851.26	851.68	0.42	10.42-12.42 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B958	SSHS-B958-SUB-6-8	3/4/2018	6 - 8 ft	851.53	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B963	PS-FD-14	3/4/2018	4 - 6 ft	853.05	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B963	SSHS-B963-SUB-4-6	3/4/2018	4 - 6 ft	853.05	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B963	SSHS-B963-SUB-6-8	3/4/2018	6 - 8 ft	853.05	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B967	SSHS-B967-SUB-2-4	3/4/2018	2 - 4 ft	851.89	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B967	PS-FD-15	3/4/2018	2 - 4 ft	851.89	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B976	SSHS-B976-SUB-6-8	3/4/2018	6 - 8 ft	849.14	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B976	PS-FD-10	3/4/2018	6 - 8 ft	849.14	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B979	PS-FD-12	3/4/2018	10 - 12 ft	849.85	850.02	0.17	10.17-12.17 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B979	SSHS-B979-SUB-10-12	3/4/2018	10 - 12 ft	849.85	850.02	0.17	10.17-12.17 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B980	SSHS-B980-SUB-12-14	3/4/2018	12 - 14 ft	849.90	849.89	-0.01	11.99-13.99 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B992	SSHS-B992-SUB-8-10	3/4/2018	8 - 10 ft	852.95	853.53	0.58	8.58-10.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B992	SSHS-B992-SUB-10-12	3/4/2018	10 - 12 ft	852.95	853.53	0.58	10.58-12.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B954	SSHS-B954-SUB-6-8	3/5/2018	6 - 8 ft	851.89	853.01	1.12	7.12-9.12 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B961	SSHS-B961-SUB-8-10	3/5/2018	8 - 10 ft	850.20	850.07	-0.13	7.87-9.87 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B962	SSHS-B962-SUB-8-10	3/5/2018	8 - 10 ft	850.09	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B975	SSHS-B975-SUB-4-6	3/5/2018	4 - 6 ft	852.46	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B975	SSHS-B975-SUB-6-8	3/5/2018	6 - 8 ft	852.46	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B978	PS-FD-17	3/5/2018	10 - 12 ft	852.09	852.56	0.47	10.47-12.47 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-10-12	3/5/2018	10 - 12 ft	852.09	852.56	0.47	10.47-12.47 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-12-14	3/5/2018	12 - 14 ft	852.09	852.56	0.47	12.47-14.47 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-6-8	3/5/2018	6 - 8 ft	852.09	852.56	0.47	6.47-8.47 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-8-10	3/5/2018	8 - 10 ft	852.09	852.56	0.47	8.47-10.47 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B986	SSHS-B986-SUB-6-8	3/5/2018	6 - 8 ft	852.00	852.41	0.41	6.41-8.41 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B989	SSHS-B989-SUB-10-12	3/5/2018	10 - 12 ft	853.10	853.59	0.49	10.49-12.49 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B989	PS-FD-16	3/5/2018	8 - 10 ft	853.10	853.59	0.49	8.49-10.49 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B989	SSHS-B989-SUB-8-10	3/5/2018	8 - 10 ft	853.10	853.59	0.49	8.49-10.49 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-12-14	4/24/2018	12 - 14 ft	852.00	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-14-16	4/24/2018	14 - 16 ft	852.00	852.29	0.29	14.29-16.29 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1010	SSHS-B1010-SUB-10-12	4/24/2018	10 - 12 ft	851.50	852.08	0.58	10.58-12.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1010	SSHS-B1010-SUB-12-14	4/24/2018	12 - 14 ft	851.50	852.08	0.58	12.58-14.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1016	SSHS-B1016-SUB-10-12	4/24/2018	10 - 12 ft	849.90	849.78	-0.12	9.88-11.88 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1017	SSHS-B1017-SUB-10-12	4/24/2018	10 - 12 ft	853.03	853.47	0.44	10.44-12.44 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1017	SSHS-B1017-SUB-8-10	4/24/2018	8 - 10 ft	853.03	853.47	0.44	8.44-10.44 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1018	SSHS-B1018-SUB-10-12	4/24/2018	10 - 12 ft	852.50	852.75	0.25	10.25-12.25 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1018	SSHS-B1018-SUB-8-10	4/24/2018	8 - 10 ft	852.50	852.75	0.25	8.25-10.25 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1026	SSHS-B1026-SUB-14-16	4/24/2018	14 - 16 ft	852.10	852.15	0.05	14.05-16.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1014	SSHS-B1014-SUB-4-6	4/25/2018	4 - 6 ft	853.67	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B1015	SSHS-B1015-SUB-12-14	4/25/2018	12 - 14 ft	853.20	853.64	0.44	12.44-14.44 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1024	SSHS-B1024-SUB-2-4	4/25/2018	2 - 4 ft	852.60	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1018	SSHS-B1018b-SUB-10-12	4/26/2018	10 - 12 ft	852.50	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1020	PS-FD-04	4/26/2018	8 - 10 ft	851.20	850.89	-0.31	7.69-9.69 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1020	SSHS-B1020-SUB-8-10	4/26/2018	8 - 10 ft	851.20	850.89	-0.31	7.69-9.69 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1023b	SSHS-B1023b-SUB-12-14	4/26/2018	12 - 14 ft	853.90	853.73	-0.17	11.83-13.83 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1025	SSHS-B1025-SUB-14-16	4/26/2018	14 - 16 ft	852.50	852.33	-0.17	13.83-15.83 ft	X	-	-	-	-
Football Field	SSHS-B1055	SSHS-B1055-SS	5/22/2018	0 - 0.17 ft	857.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B1056	SSHS-B1056-SS	5/22/2018	0 - 0.17 ft	857.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B1057	SSHS-B1057-SS	5/22/2018	0 - 0.17 ft	857.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B1058	SSHS-B1058-SS	5/22/2018	0 - 0.17 ft	857.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B1059	SSHS-B1059-SS	5/22/2018	0 - 0.17 ft	857.18	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1189	DUP-1	6/16/2018	0 - 2 ft	853.96	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1189	SSHS-B1189-SUB-0-2	6/16/2018	0 - 2 ft	853.96	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1196	SSHS-B1196-SUB-0-2	6/16/2018	0 - 2 ft	853.82	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1063	SSHS-B1063-SUB-0-2	6/19/2018	0 - 2 ft	852.50	852.65	0.15	0.15-2.15 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1190	SSHS-B1190-SUB-0-2	6/19/2018	0 - 2 ft	853.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1191	SSHS-B1191-SUB-0-2	6/19/2018	0 - 2 ft	853.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1064	SSHS-B1064-SUB-0-2	6/23/2018	0 - 2 ft	850.48	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1071	DUP-2	6/23/2018	0 - 2 ft	852.51	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1071	SSHS-B1071-SUB-0-2	6/23/2018	0 - 2 ft	852.51	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1075	SSHS-B1075-SUB-0-2	6/23/2018	0 - 2 ft	852.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1194	SSHS-B1194-SUB-0-2	6/23/2018	0 - 2 ft	851.92	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-0-2	6/24/2018	0 - 2 ft	850.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1070	SSHS-B1070-SUB-0-2	6/24/2018	0 - 2 ft	850.30	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1073	SSHS-B1073-SUB-2-4	6/24/2018	2 - 4 ft	852.50	852.73	0.23	2.23-4.23 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1189	SSHS-B1189-SUB-4-6	6/24/2018	4 - 6 ft	853.90	853.81	-0.09	3.91-5.91 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-0-2	6/25/2018	0 - 2 ft	851.62	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1069	SSHS-B1069-SUB-0-2	6/26/2018	0 - 2 ft	850.14	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1192	SSHS-B1192-SUB-0-2	6/26/2018	0 - 2 ft	852.13	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1195	SSHS-B1195-SUB-0-2	6/26/2018	0 - 2 ft	849.43	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1212	SSHS-B1212-SUB-4-6	6/27/2018	4 - 6 ft	853.67	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1084	SSHS-B1084-SUB-8-10	6/28/2018	8 - 10 ft	853.50	853.60	0.10	8.10-10.10 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1088	SSHS-B1088-SUB-6-8	6/28/2018	6 - 8 ft	853.97	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1229	SSHS-B1229-SUB-2-4	6/28/2018	2 - 4 ft	853.00	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1234	SSHS-B1234-SUB-4-6	6/28/2018	4 - 6 ft	852.82	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1234	SSHS-B1234-SUB-8-10	6/28/2018	8 - 10 ft	852.60	852.88	0.28	8.28-10.28 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1064	SSHS-B1064-SUB-4-6	6/29/2018	4 - 6 ft	850.52	850.70	0.18	4.18-6.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1074	PS-FD-5	6/29/2018	2 - 4 ft	851.08	851.80	0.72	2.72-4.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1074	SSHS-B1074-SUB-2-4	6/29/2018	2 - 4 ft	851.08	851.80	0.72	2.72-4.72 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1076	SSHS-B1076-SUB-2-4	6/29/2018	2 - 4 ft	851.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1080	SSHS-B1080B-SUB-6-8	6/29/2018	6 - 8 ft	852.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1109	SSHS-B1109-SUB-8-10	6/29/2018	8 - 10 ft	851.50	851.68	0.18	8.18-10.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1194	SSHS-B1194-SUB-4-6	6/29/2018	4 - 6 ft	852.03	851.97	-0.06	3.94-5.94 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1202	SSHS-B1202-SUB-2-4	6/29/2018	2 - 4 ft	852.10	852.96	0.86	2.86-4.86 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1202	SSHS-B1202-SUB-4-6	6/29/2018	4 - 6 ft	852.10	852.96	0.86	4.86-6.86 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1214	PS-FD-4	6/29/2018	4 - 6 ft	852.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1214	SSHS-B1214-SUB-4-6	6/29/2018	4 - 6 ft	852.25	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1216	SSHS-B1216-SUB-4-6	6/29/2018	4 - 6 ft	852.51	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1231	SSHS-B1231-SUB-4-6	6/29/2018	4 - 6 ft	851.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1232	SSHS-B1232-SUB-4-6	6/29/2018	4 - 6 ft	851.94	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1242	SSHS-B1242-SUB-6-8	6/29/2018	6 - 8 ft	851.78	852.83	1.05	7.05-9.05 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1243	SSHS-B1243-SUB-6-8	6/29/2018	6 - 8 ft	851.53	852.30	0.77	6.77-8.77 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1077	SSHS-B1077-SUB-2-4	6/30/2018	2 - 4 ft	851.36	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1079	PS-FD-7	6/30/2018	4 - 6 ft	850.74	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1079	SSHS-B1079-SUB-4-6	6/30/2018	4 - 6 ft	850.74	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1105	SSHS-B1105-SUB-4-6	6/30/2018	4 - 6 ft	851.18	850.76	-0.42	3.58-5.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1160	SSHS-B1160-SUB-10-12	6/30/2018	10 - 12 ft	851.49	851.07	-0.42	9.58-11.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1203	SSHS-B1203-SUB-2-4	6/30/2018	2 - 4 ft	851.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1215	PS-FD-6	6/30/2018	4 - 6 ft	851.81	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1215	SSHS-B1215-SUB-4-6	6/30/2018	4 - 6 ft	851.81	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1221	SSHS-B1221-SUB-6-8	6/30/2018	6 - 8 ft	851.57	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1230	SSHS-B1230-SUB-2-4	6/30/2018	2 - 4 ft	852.63	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-4-6	7/1/2018	4 - 6 ft	850.40	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-10-12	7/1/2018	10 - 12 ft	850.17	850.19	0.02	10.02-12.02 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1204	SSHS-B1204-SUB-2-4	7/1/2018	2 - 4 ft	850.64	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1219	SSHS-B1219-SUB-4-6	7/1/2018	4 - 6 ft	850.09	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1219	SSHS-B1219-SUB-10-12	7/1/2018	10 - 12 ft	850.00	849.86	-0.14	9.86-11.86 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1224	SSHS-B1224-SUB-6-8	7/1/2018	6 - 8 ft	850.57	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1224	SSHS-B1224-SUB-8-10	7/1/2018	8 - 10 ft	850.64	850.30	-0.34	7.66-9.66 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1244	SSHS-B1244-SUB-6-8	7/1/2018	6 - 8 ft	848.20	849.22	1.02	7.02-9.02 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Rear Parking Lot	SSHS-B1251	SSHS-B1251-SUB-10-12	7/1/2018	10 - 12 ft	849.70	849.77	0.07	10.07-12.07 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-10-12	7/1/2018	10 - 12 ft	849.20	848.96	-0.24	9.76-11.76 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-10-12	7/1/2018	10 - 12 ft	849.20	848.96	-0.24	9.76-11.76 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-10-12	7/1/2018	10 - 12 ft	849.77	849.85	0.08	10.08-12.08 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-10-12	7/1/2018	10 - 12 ft	849.77	849.85	0.08	10.08-12.08 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-12-14	7/1/2018	12 - 14 ft	849.77	849.85	0.08	12.08-14.08 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-12-14	7/1/2018	12 - 14 ft	849.77	849.85	0.08	12.08-14.08 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1075	SSHS-B1075-SUB-2-4	7/2/2018	2 - 4 ft	852.95	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1206	SSHS-B1206-SUB-2-4	7/2/2018	2 - 4 ft	852.54	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1206	SSHS-B1206-SUB-4-6	7/2/2018	4 - 6 ft	852.30	852.65	0.35	4.35-6.35 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1220	SSHS-B1220-SUB-6-8	7/2/2018	6 - 8 ft	852.30	852.77	0.47	6.47-8.47 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1223	SSHS-B1223-SUB-6-8	7/2/2018	6 - 8 ft	850.41	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1223	7-2-FD-1	7/2/2018	6 - 8 ft	850.41	850.59	0.18	6.18-8.18 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1233	SSHS-B1233-SUB-4-6	7/2/2018	4 - 6 ft	852.40	852.81	0.41	4.41-6.41 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1235	SSHS-B1235-SUB-4-6	7/2/2018	4 - 6 ft	848.02	848.61	0.59	4.59-6.59 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1236	SSHS-B1236-SUB-4-6	7/2/2018	4 - 6 ft	850.26	850.34	0.08	4.08-6.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1236	SSHS-B1236-SUB-6-8	7/2/2018	6 - 8 ft	850.26	850.34	0.08	6.08-8.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1237	SSHS-B1237-SUB-4-6	7/2/2018	4 - 6 ft	850.26	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1237	SSHS-B1237-SUB-8-10	7/2/2018	8 - 10 ft	849.85	849.99	0.14	8.14-10.14 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1104	SSHS-B1104-SUB-4-6	7/5/2018	4 - 6 ft	851.81	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1162	SSHS-B1162-SUB-8-10	7/5/2018	8 - 10 ft	850.38	850.67	0.29	8.29-10.29 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1205	SSHS-B1205-SUB-2-4	7/5/2018	2 - 4 ft	851.33	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1205	SSHS-B1205-SUB-12-14	7/5/2018	12 - 14 ft	851.11	851.51	0.40	12.40-14.40 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1076	SSHS-B1076-SUB-4-6	7/6/2018	4 - 6 ft	851.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1076	SSHS-B1076-SUB-4-6-DUP	7/6/2018	4 - 6 ft	851.75	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1081	SSHS-B1081-SUB-6-8	7/6/2018	6 - 8 ft	851.28	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1086	SSHS-B1086-SUB-10-12	7/6/2018	10 - 12 ft	850.69	851.13	0.44	10.44-12.44 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1091	SSHS-B1091-SUB-14-16	7/6/2018	14 - 16 ft	851.86	852.06	0.20	14.20-16.20 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16	7/6/2018	14 - 16 ft	852.20	852.41	0.21	14.21-16.21 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16-DUP	7/6/2018	14 - 16 ft	852.20	852.41	0.21	14.21-16.21 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16	7/6/2018	14 - 16 ft	851.97	852.05	0.08	14.08-16.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16-DUP	7/6/2018	14 - 16 ft	851.97	852.05	0.08	14.08-16.08 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1094	SSHS-B1094-SUB-14-16	7/6/2018	14 - 16 ft	851.75	851.77	0.02	14.02-16.02 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1104	SSHS-B1104-SUB-12-14	7/6/2018	12 - 14 ft	851.32	852.00	0.68	12.68-14.68 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1122	SSHS-B1122-SUB-10-12	7/6/2018	10 - 12 ft	851.50	851.52	0.02	10.02-12.02 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1158	SSHS-B1158-SUB-8-10	7/6/2018	8 - 10 ft	850.44	850.14	-0.30	7.70-9.70 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-4-6	7/6/2018	4 - 6 ft	851.75	851.44	-0.31	3.69-5.69 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-10-12	7/6/2018	10 - 12 ft	851.80	852.61	0.81	10.81-12.81 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-12-14	7/6/2018	12 - 14 ft	851.80	852.61	0.81	12.81-14.81 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-8-10	7/6/2018	8 - 10 ft	851.80	852.61	0.81	8.81-10.81 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1203	SSHS-B1203-SUB-4-6	7/6/2018	4 - 6 ft	851.27	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1228	SSHS-B1228-SUB-2-4	7/6/2018	2 - 4 ft	851.50	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1247	SSHS-B1247-SUB-10-12	7/6/2018	10 - 12 ft	851.72	852.30	0.58	10.58-12.58 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1249	SSHS-B1249-SUB-10-12	7/6/2018	10 - 12 ft	851.72	852.01	0.29	10.29-12.29 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1249	SSHS-B1249-SUB-10-12-DUP	7/6/2018	10 - 12 ft	851.72	852.01	0.29	10.29-12.29 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1255	SSHS-B1255-SUB-4-6-BOT	7/9/2018	4 - 6 ft	853.59	853.81	0.22	4.22-6.22 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1257	SSHS-B1257-SUB-6-8-BOT	7/10/2018	6 - 8 ft	852.90	853.50	0.60	6.60-8.60 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1396	B1396-6FT	7/21/2018	4 - 6 ft	852.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	12 - 14 ft	856.03	856.03	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-10-12	7/23/2018	10 - 12 ft	856.03	856.03	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-8-10	7/23/2018	8 - 10 ft	856.03	856.03	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-2-4	7/23/2018	2 - 4 ft	856.03	-	-	-	X	X	-	-	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-4-6	7/23/2018	4 - 6 ft	856.03	-	-	-	X	X	-	-	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	0.17 - 2 ft	856.03	-	-	-	X	X	X	X	-
Football Field	SSHS-B2230	PS-FD-7	7/23/2018	6 - 8 ft	856.03	-	-	-	X	X	-	-	-
Football Field	SSHS-B2230	SSHS-B2230-SUB-6-8	7/23/2018	6 - 8 ft	856.03	-	-	-	X	X	-	-	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-10-12	7/23/2018	10 - 12 ft	856.14	856.13	-0.01	9.99-11.99 ft	X	X	-	-	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	12 - 14 ft	856.14	856.13	-0.01	11.99-13.99 ft	X	X	-	X	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-8-10	7/23/2018	8 - 10 ft	856.14	856.13	-0.01	7.99-9.99 ft	X	X	-	-	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-2-4	7/23/2018	2 - 4 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	0.17 - 2 ft	856.14	-	-	-	X	X	X	X	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-4-6	7/23/2018	4 - 6 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B2231	SSHS-B2231-SUB-6-8	7/23/2018	6 - 8 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-10-12	7/23/2018	10 - 12 ft	855.41	855.54	0.13	10.13-12.13 ft	X	X	-	-	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	12 - 14 ft	855.41	855.54	0.13	12.13-14.13 ft	X	X	-	X	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-8-10	7/23/2018	8 - 10 ft	855.41	855.54	0.13	8.13-10.13 ft	X	X	-	-	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	0 - 0.17 ft	855.41	-	-	-	-	X	X	-	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-2-4	7/23/2018	2 - 4 ft	855.41	-	-	-	X	X	-	-	-
Football Field	SSHS-B2234	PS-FD-5	7/23/2018	4 - 6 ft	855.41	-	-	-	X	X	-	-	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-4-6	7/23/2018	4 - 6 ft	855.41	-	-	-	X	X	-	-	-
Football Field	SSHS-B2234	SSHS-B2234-SUB-6-8	7/23/2018	6 - 8 ft	855.41	-	-	-	X	X	-	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-10-12	7/23/2018	10 - 12 ft	855.30	855.51	0.21	10.21-12.21 ft	X	X	-	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	12 - 14 ft	855.30	855.51	0.21	12.21-14.21 ft	X	X	-	X	-
Football Field	SSHS-B2235	PS-FD-3	7/23/2018	8 - 10 ft	855.30	855.51	0.21	8.21-10.21 ft	X	X	-	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-8-10	7/23/2018	8 - 10 ft	855.30	855.51	0.21	8.21-10.21 ft	X	X	-	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	0.17 - 2 ft	855.30	-	-	-	-	X	X	X	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	0 - 0.17 ft	855.30	-	-	-	-	X	X	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-2-4	7/23/2018	2 - 4 ft	855.30	-	-	-	X	X	-	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-4-6	7/23/2018	4 - 6 ft	855.30	-	-	-	X	X	-	-	-
Football Field	SSHS-B2235	SSHS-B2235-SUB-6-8	7/23/2018	6 - 8 ft	855.30	-	-	-	X	X	-	-	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-10-12	7/23/2018	10 - 12 ft	855.07	-	-	-	X	X	-	-	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	12 - 14 ft	855.07	-	-	-	X	X	-	X	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	0 - 0.17 ft	855.07	-	-	-	-	X	X	-	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	0.17 - 2 ft	855.07	-	-	-	-	X	X	X	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-2-4	7/23/2018	2 - 4 ft	855.07	-	-	-	-	X	-	-	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-4-6	7/23/2018	4 - 6 ft	855.07	-	-	-	-	X	-	-	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-6-8	7/23/2018	6 - 8 ft	855.07	-	-	-	-	X	-	-	-
Football Field	SSHS-B2238	SSHS-B2238-SUB-8-10	7/23/2018	8 - 10 ft	855.07	-	-	-	-	X	-	-	-
Football Field	SSHS-B2239	SSHS-B2239-SUB-2-4	7/23/2018	2 - 4 ft	855.51	-	-	-	X	X	-	-	-
Football Field	SSHS-B2239	PS-FD-4	7/23/2018	10 - 12 ft	855.51	-	-	-	-	X	-	-	-
Football Field	SSHS-B2239	SSHS-B2239-SUB-10-12	7/23/2018	10 - 12 ft	855.51	-	-	-	-	X	-	-	-
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	12 - 14 ft	855.51	-	-	-	-	X	-	X	-
Football Field	SSHS-B2239	SSHS-B2239-SUB-4-6	7/23/2018	4 - 6 ft	855.51	-	-	-	X	X	-	-	-
Football Field	SSHS-B2239	SSHS-B2239-SUB-6-8	7/23/2018	6 - 8 ft	855.51	-	-	-	X	X	-	-	-
Football Field	SSHS-B2239	SSHS-B2239-SUB-8-10	7/23/2018	8 - 10 ft	855.51	-	-	-	-	X	-	-	-
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	12 - 14 ft	855.85	855.85	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2240	SSHS-B2240-SUB-10-12	7/23/2018	10 - 12 ft	855.85	855.85	0.00	10-12 ft	-	X	-	-	-
Football Field	SSHS-B2240	SSHS-B2240-SUB-2-4	7/23/2018	2 - 4 ft	855.85	-	-	-	-	X	-	-	-
Football Field	SSHS-B2240	SSHS-B2240-SUB-4-6	7/23/2018	4 - 6 ft	855.85	-	-	-	-	X	-	-	-
Football Field	SSHS-B2240	SSHS-B2240-SUB-6-8	7/23/2018	6 - 8 ft	855.85	-	-	-	-	X	-	-	-
Football Field	SSHS-B2240	SSHS-B2240-SUB-8-10	7/23/2018	8 - 10 ft	855.85	-	-	-	X	X	-	-	-
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	12 - 14 ft	855.46	855.52	0.06	12.06-14.06 ft	-	X	-	X	-
Football Field	SSHS-B2241	SSHS-B2241-SUB-10-12	7/23/2018	10 - 12 ft	855.46	-	-	-	-	X	-	-	-
Football Field	SSHS-B2241	PS-FD-6	7/23/2018	2 - 4 ft	855.46	-	-	-	-	X	-	-	-
Football Field	SSHS-B2241	SSHS-B2241-SUB-2-4	7/23/2018	2 - 4 ft	855.46	-	-	-	-	X	-	-	-
Football Field	SSHS-B2241	SSHS-B2241-SUB-4-6	7/23/2018	4 - 6 ft	855.46	-	-	-	-	X	-	-	-
Football Field	SSHS-B2241	SSHS-B2241-SUB-6-8	7/23/2018	6 - 8 ft	855.46	-	-	-	-	X	-	-	-
Football Field	SSHS-B2241	SSHS-B2241-SUB-8-10	7/23/2018	8 - 10 ft	855.46	-	-	-	-	X	-	-	-
Football Field	SSHS-B2242	SSHS-B2242-SUB-8-10	7/23/2018	8 - 10 ft	856.09	-	-	-	X	X	-	-	-
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	12 - 14 ft	856.09	-	-	-	X	X	-	X	-
Football Field	SSHS-B2242	SSHS-B2242-SUB-10-12	7/23/2018	10 - 12 ft	856.09	-	-	-	X	X	-	-	-
Football Field	SSHS-B2242	SSHS-B2242-SUB-2-4	7/23/2018	2 - 4 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2242	PS-FD-2	7/23/2018	4 - 6 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2242	SSHS-B2242-SUB-4-6	7/23/2018	4 - 6 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2242	SSHS-B2242-SUB-6-8	7/23/2018	6 - 8 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	12 - 14 ft	856.00	-	-	-	X	X	-	X	-
Football Field	SSHS-B2243	SSHS-B2243-SUB-10-12	7/23/2018	10 - 12 ft	856.00	-	-	-	-	X	-	-	-
Football Field	SSHS-B2243	SSHS-B2243-SUB-2-4	7/23/2018	2 - 4 ft	856.00	-	-	-	-	X	-	-	-
Football Field	SSHS-B2243	SSHS-B2243-SUB-4-6	7/23/2018	4 - 6 ft	856.00	-	-	-	-	X	-	-	-
Football Field	SSHS-B2243	SSHS-B2243-SUB-6-8	7/23/2018	6 - 8 ft	856.00	-	-	-	-	X	-	-	-
Football Field	SSHS-B2243	SSHS-B2243-SUB-8-10	7/23/2018	8 - 10 ft	856.00	-	-	-	-	X	-	-	-
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	12 - 14 ft	856.09	856.15	0.06	12.06-14.06 ft	X	X	-	X	-
Football Field	SSHS-B2244	SSHS-B2244-SUB-10-12	7/23/2018	10 - 12 ft	856.09	856.15	0.06	10.06-12.06 ft	X	X	-	-	-
Football Field	SSHS-B2244	PS-FD-1	7/23/2018	12 - 14 ft	856.09	856.15	0.06	12.06-14.06 ft	-	X	-	-	-
Football Field	SSHS-B2244	SSHS-B2244-SUB-2-4	7/23/2018	2 - 4 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2244	SSHS-B2244-SUB-4-6	7/23/2018	4 - 6 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2244	SSHS-B2244-SUB-6-8	7/23/2018	6 - 8 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B2244	SSHS-B2244-SUB-8-10	7/23/2018	8 - 10 ft	856.09	-	-	-	-	X	-	-	-
Rear Parking Lot	SSHS-B1325	SSHS-B1325-SUB-2-4	7/24/2018	2 - 4 ft	852.59	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1373	SSHS-B1373-SUB-8-10	7/24/2018	8 - 10 ft	852.50	852.89	0.39	8.39-10.39 ft	X	-	-	-	-
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	0 - 0.17 ft	856.16	-	-	-	X	X	X	-	-
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	0 - 0.17 ft	856.82	-	-	-	X	X	X	-	-
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	0 - 0.17 ft	856.99	-	-	-	X	X	X	-	-
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	0 - 0.17 ft	856.61	-	-	-	X	X	X	-	-
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	0 - 0.17 ft	856.77	-	-	-	X	X	X	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	0 - 2 ft	855.07	-	-	-	X	-	X	X	-
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	12 - 14 ft	855.07	855.49	0.42	12.42-14.42 ft	X	X	-	X	-
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	2 - 4 ft	855.07	-	-	-	X	X	X	-	-
Football Field	SSHS-B2185	SSHS-B2185-SUB-10-12	7/24/2018	10 - 12 ft	855.07	855.49	0.42	10.42-12.42 ft	X	X	-	-	-
Football Field	SSHS-B2185	PS-FD-16	7/24/2018	4 - 6 ft	855.07	855.49	0.42	4.42-6.42 ft	X	X	-	-	-
Football Field	SSHS-B2185	SSHS-B2185-SUB-4-6	7/24/2018	4 - 6 ft	855.07	855.49	0.42	4.42-6.42 ft	X	X	-	-	-
Football Field	SSHS-B2185	SSHS-B2185-SUB-6-8	7/24/2018	6 - 8 ft	855.07	855.49	0.42	6.42-8.42 ft	X	X	-	-	-
Football Field	SSHS-B2185	SSHS-B2185-SUB-8-10	7/24/2018	8 - 10 ft	855.07	855.49	0.42	8.42-10.42 ft	X	X	-	-	-
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	0 - 2 ft	854.94	-	-	-	X	X	X	X	-
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	2 - 4 ft	854.94	-	-	-	X	X	X	-	-
Football Field	SSHS-B2186	SSHS-B2186-SUB-10-12	7/24/2018	10 - 12 ft	854.94	855.41	0.47	10.47-12.47 ft	X	X	-	-	-
Football Field	SSHS-B2186	SSHS-B2186-SUB-4-6	7/24/2018	4 - 6 ft	854.94	855.41	0.47	4.47-6.47 ft	X	X	-	-	-
Football Field	SSHS-B2186	SSHS-B2186-SUB-6-8	7/24/2018	6 - 8 ft	854.94	855.41	0.47	6.47-8.47 ft	X	X	-	-	-
Football Field	SSHS-B2186	SSHS-B2186-SUB-8-10	7/24/2018	8 - 10 ft	854.94	855.41	0.47	8.47-10.47 ft	X	X	-	-	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-10-12	7/24/2018	10 - 12 ft	856.10	856.10	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	0 - 2 ft	856.10	-	-	-	-	X	X	X	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	2 - 4 ft	856.10	856.10	0.00	2-4 ft	-	X	X	-	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-4-6	7/24/2018	4 - 6 ft	856.10	856.10	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-6-8	7/24/2018	6 - 8 ft	856.10	856.10	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-8-10	7/24/2018	8 - 10 ft	856.10	856.10	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	12 - 14 ft	856.10	856.10	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	2 - 4 ft	855.99	-	-	-	X	X	X	-	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-4-6	7/24/2018	4 - 6 ft	855.99	-	-	-	X	X	-	-	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	0 - 2 ft	855.99	-	-	-	-	X	X	X	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-10-12	7/24/2018	10 - 12 ft	855.99	855.99	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-6-8	7/24/2018	6 - 8 ft	855.99	855.99	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2188	PS-FD-14	7/24/2018	8 - 10 ft	855.99	855.99	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-8-10	7/24/2018	8 - 10 ft	855.99	855.99	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	12 - 14 ft	855.99	855.99	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	0 - 2 ft	855.74	-	-	-	X	X	X	X	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	2 - 4 ft	855.74	-	-	-	X	X	X	-	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-4-6	7/24/2018	4 - 6 ft	855.74	-	-	-	X	X	-	-	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	12 - 14 ft	855.74	855.90	0.16	12.16-14.16 ft	X	X	-	X	-
Football Field	SSHS-B2189	PS-FD-12	7/24/2018	10 - 12 ft	855.74	855.90	0.16	10.16-12.16 ft	X	X	-	-	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-10-12	7/24/2018	10 - 12 ft	855.74	855.90	0.16	10.16-12.16 ft	X	X	-	-	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-6-8	7/24/2018	6 - 8 ft	855.74	855.90	0.16	6.16-8.16 ft	X	X	-	-	-
Football Field	SSHS-B2189	SSHS-B2189-SUB-8-10	7/24/2018	8 - 10 ft	855.74	855.90	0.16	8.16-10.16 ft	X	X	-	-	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	2 - 4 ft	856.18	-	-	-	X	X	X	-	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-4-6	7/24/2018	4 - 6 ft	856.18	-	-	-	X	X	-	-	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-6-8	7/24/2018	6 - 8 ft	856.18	856.18	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	0 - 2 ft	856.18	-	-	-	-	X	X	X	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-10-12	7/24/2018	10 - 12 ft	856.18	856.18	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-8-10	7/24/2018	8 - 10 ft	856.18	856.18	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	12 - 14 ft	856.18	856.18	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	0 - 0.17 ft	857.04	-	-	-	-	X	X	-	-
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	0 - 0.17 ft	856.19	-	-	-	X	X	X	-	-
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	0 - 0.17 ft	855.94	-	-	-	X	X	X	-	-
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	0 - 2 ft	855.03	-	-	-	X	X	X	X	-
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	0 - 2 ft	855.03	-	-	-	X	X	X	X	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-10-12	7/24/2018	10 - 12 ft	854.99	855.43	0.44	10.44-12.44 ft	X	X	-	-	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	12 - 14 ft	854.99	855.43	0.44	12.44-14.44 ft	X	X	X	X	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	2 - 4 ft	854.99	855.43	0.44	2.44-4.44 ft	X	X	X	-	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-4-6	7/24/2018	4 - 6 ft	854.99	855.43	0.44	4.44-6.44 ft	X	X	-	-	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-6-8	7/24/2018	6 - 8 ft	854.99	855.43	0.44	6.44-8.44 ft	X	X	-	-	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-8-10	7/24/2018	8 - 10 ft	854.99	855.43	0.44	8.44-10.44 ft	X	X	-	-	-
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	0 - 2 ft	854.99	-	-	-	X	X	X	X	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	12 - 14 ft	855.05	855.51	0.46	12.46-14.46 ft	-	X	-	X	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	0 - 2 ft	855.05	-	-	-	-	X	X	X	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-10-12	7/24/2018	10 - 12 ft	855.05	-	-	-	-	X	-	-	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	2 - 4 ft	855.05	-	-	-	X	X	X	-	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-4-6	7/24/2018	4 - 6 ft	855.05	-	-	-	X	X	-	-	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-6-8	7/24/2018	6 - 8 ft	855.05	-	-	-	X	X	-	-	-
Football Field	SSHS-B2198	SSHS-B2198-SUB-8-10	7/24/2018	8 - 10 ft	855.05	-	-	-	X	X	-	-	-
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	0 - 0.17 ft	855.14	-	-	-	X	X	X	-	-
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	0 - 0.17 ft	855.11	-	-	-	X	X	X	-	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	12 - 14 ft	855.38	855.38	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	0.17 - 2 ft	855.38	-	-	-	-	X	X	X	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-10-12	7/24/2018	10 - 12 ft	855.38	-	-	-	X	X	-	-	-
Football Field	SSHS-B2221	PS-FD-11	7/24/2018	2 - 4 ft	855.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-2-4	7/24/2018	2 - 4 ft	855.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-4-6	7/24/2018	4 - 6 ft	855.38	-	-	-	X	X	-	-	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-6-8	7/24/2018	6 - 8 ft	855.38	-	-	-	X	X	-	-	-
Football Field	SSHS-B2221	SSHS-B2221-SUB-8-10	7/24/2018	8 - 10 ft	855.38	-	-	-	X	X	-	-	-
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	0.17 - 2 ft	857.03	-	-	-	-	X	X	X	-
Football Field	SSHS-B2225	SSHS-B2225-SUB-2-4	7/24/2018	2 - 4 ft	857.03	-	-	-	-	X	-	-	-
Football Field	SSHS-B2225	SSHS-B2225-SUB-4-6	7/24/2018	4 - 6 ft	857.03	-	-	-	-	X	-	-	-
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	0 - 0.17 ft	855.33	-	-	-	-	X	X	-	-
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	0 - 0.17 ft	856.14	-	-	-	-	X	X	-	-
Football Field	SSHS-B2232	PS-FD-9	7/24/2018	10 - 12 ft	856.82	856.82	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-10-12	7/24/2018	10 - 12 ft	856.82	856.82	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	12 - 14 ft	856.82	856.82	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-6-8	7/24/2018	6 - 8 ft	856.82	856.82	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-8-10	7/24/2018	8 - 10 ft	856.82	856.82	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	0.17 - 2 ft	856.82	-	-	-	-	X	X	X	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-2-4	7/24/2018	2 - 4 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2232	SSHS-B2232-SUB-4-6	7/24/2018	4 - 6 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-10-12	7/24/2018	10 - 12 ft	854.83	855.35	0.52	10.52-12.52 ft	X	X	-	-	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	12 - 14 ft	854.83	855.35	0.52	12.52-14.52 ft	X	X	-	X	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-6-8	7/24/2018	6 - 8 ft	854.83	855.35	0.52	6.52-8.52 ft	X	X	-	-	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-8-10	7/24/2018	8 - 10 ft	854.83	855.35	0.52	8.52-10.52 ft	X	X	-	-	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	0.17 - 2 ft	854.83	-	-	-	-	X	X	X	-
Football Field	SSHS-B2233	PS-FD-8	7/24/2018	2 - 4 ft	854.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-2-4	7/24/2018	2 - 4 ft	854.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2233	SSHS-B2233-SUB-4-6	7/24/2018	4 - 6 ft	854.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	0 - 0.17 ft	855.30	-	-	-	-	X	X	-	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-10-12	7/24/2018	10 - 12 ft	855.25	855.52	0.27	10.27-12.27 ft	X	X	-	-	-
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	12 - 14 ft	855.25	855.52	0.27	12.27-14.27 ft	X	X	-	X	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	12 - 14 ft	855.25	855.52	0.27	12.27-14.27 ft	X	X	-	X	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-8-10	7/24/2018	8 - 10 ft	855.25	855.52	0.27	8.27-10.27 ft	X	X	-	-	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	0 - 2 ft	855.25	-	-	-	X	X	X	X	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	2 - 4 ft	855.25	-	-	-	X	X	X	-	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-4-6	7/24/2018	4 - 6 ft	855.25	-	-	-	X	X	-	-	-
Football Field	SSHS-B2245	SSHS-B2245-SUB-6-8	7/24/2018	6 - 8 ft	855.25	-	-	-	X	X	-	-	-
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.59	-	-	-	X	X	X	X	-
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	2 - 4 ft	855.59	-	-	-	X	X	X	-	-
Football Field	SSHS-B2052	SSHS-B2052-SUB-4-6	7/25/2018	4 - 6 ft	855.59	-	-	-	X	X	-	-	-
Football Field	SSHS-B2052	PS-FD-24	7/25/2018	6 - 8 ft	855.59	-	-	-	X	X	-	-	-
Football Field	SSHS-B2052	SSHS-B2052-SUB-6-8	7/25/2018	6 - 8 ft	855.59	-	-	-	X	X	-	-	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.00	-	-	-	X	X	X	X	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-10-12	7/25/2018	10 - 12 ft	855.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	12 - 14 ft	855.00	-	-	-	X	X	-	X	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-2-4	7/25/2018	2 - 4 ft	855.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	4 - 6 ft	855.00	-	-	-	X	X	X	X	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-6-8	7/25/2018	6 - 8 ft	855.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2053	PS-FD-26	7/25/2018	8 - 10 ft	855.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2053	SSHS-B2053-SUB-8-10	7/25/2018	8 - 10 ft	855.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2070	SSHS-B2070-SUB-10-12	7/25/2018	10 - 12 ft	854.72	855.22	0.50	10.5-12.5 ft	X	X	-	-	-
Football Field	SSHS-B2070	SSHS-B2070-SUB-4-6	7/25/2018	4 - 6 ft	854.72	855.22	0.50	4.5-6.5 ft	X	X	-	-	-
Football Field	SSHS-B2070	SSHS-B2070-SUB-6-8	7/25/2018	6 - 8 ft	854.72	855.22	0.50	6.5-8.5 ft	X	X	-	-	-
Football Field	SSHS-B2070	SSHS-B2070-SUB-8-10	7/25/2018	8 - 10 ft	854.72	855.22	0.50	8.5-10.5 ft	X	X	-	-	-
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	0.17 - 2 ft	854.72	855.22	0.50	0.67-2.5 ft	X	X	X	X	-
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	12 - 14 ft	854.72	855.22	0.50	12.5-14.5 ft	X	X	-	X	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	0.17 - 2 ft	856.82	-	-	-	X	X	X	X	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-10-12	7/25/2018	10 - 12 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2072	PS-FD-22	7/25/2018	2 - 4 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-2-4	7/25/2018	2 - 4 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-4-6	7/25/2018	4 - 6 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-6-8	7/25/2018	6 - 8 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-8-10	7/25/2018	8 - 10 ft	856.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	12 - 14 ft	856.82	856.83	0.01	12.01-14.01 ft	X	X	-	X	-
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	0.17 - 2 ft	856.99	-	-	-	X	X	X	X	-
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	0.17 - 2 ft	856.99	-	-	-	X	X	X	X	-
Football Field	SSHS-B2073	SSHS-B2073-SUB-2-4	7/25/2018	2 - 4 ft	856.99	-	-	-	X	X	-	-	-
Football Field	SSHS-B2073	SSHS-B2073-SUB-4-6	7/25/2018	4 - 6 ft	856.99	-	-	-	X	X	-	-	-
Football Field	SSHS-B2073	SSHS-B2073-SUB-6-8	7/25/2018	6 - 8 ft	856.99	-	-	-	X	X	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2073	SSHS-B2073-SUB-8-10	7/25/2018	8 - 10 ft	856.99	-	-	-	X	X	-	-	-
Football Field	SSHS-B2073	SSHS-B2073-SUB-10-12	7/25/2018	10 - 12 ft	856.99	856.99	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	12 - 14 ft	856.99	856.99	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.40	-	-	-	X	X	X	X	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-10-12	7/25/2018	10 - 12 ft	855.40	855.39	-0.01	9.99-11.99 ft	X	X	-	-	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-2-4	7/25/2018	2 - 4 ft	855.40	855.39	-0.01	1.99-3.99 ft	X	X	-	-	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-4-6	7/25/2018	4 - 6 ft	855.40	855.39	-0.01	3.99-5.99 ft	X	X	-	-	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-6-8	7/25/2018	6 - 8 ft	855.40	855.39	-0.01	5.99-7.99 ft	X	X	-	-	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-8-10	7/25/2018	8 - 10 ft	855.40	855.39	-0.01	7.99-9.99 ft	X	X	-	-	-
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	12 - 14 ft	855.40	855.39	-0.01	11.99-13.99 ft	X	X	-	X	-
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	0.17 - 2 ft	856.61	-	-	-	X	X	X	X	-
Football Field	SSHS-B2091	SSHS-B2091-SUB-10-12	7/25/2018	10 - 12 ft	856.61	856.61	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	12 - 14 ft	856.61	856.61	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2091	SSHS-B2091-SUB-4-6	7/25/2018	4 - 6 ft	856.61	856.61	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2091	SSHS-B2091-SUB-6-8	7/25/2018	6 - 8 ft	856.61	856.61	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2091	SSHS-B2091-SUB-8-10	7/25/2018	8 - 10 ft	856.61	856.61	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	0.17 - 2 ft	856.77	-	-	-	X	X	X	X	-
Football Field	SSHS-B2092	PS-FD-27	7/25/2018	2 - 4 ft	856.77	-	-	-	X	X	-	-	-
Football Field	SSHS-B2092	SSHS-B2092-SUB-2-4	7/25/2018	2 - 4 ft	856.77	-	-	-	X	X	-	-	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.64	-	-	-	X	X	X	X	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-10-12	7/25/2018	10 - 12 ft	855.64	855.64	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-2-4	7/25/2018	2 - 4 ft	855.64	855.64	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-4-6	7/25/2018	4 - 6 ft	855.64	855.64	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-6-8	7/25/2018	6 - 8 ft	855.64	855.64	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-8-10	7/25/2018	8 - 10 ft	855.64	855.64	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	12 - 14 ft	855.64	855.64	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.25	-	-	-	X	X	X	X	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-10-12	7/25/2018	10 - 12 ft	855.25	855.48	0.23	10.23-12.23 ft	X	X	-	-	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	12 - 14 ft	855.25	855.48	0.23	12.23-14.23 ft	X	X	-	X	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-2-4	7/25/2018	2 - 4 ft	855.25	855.48	0.23	2.23-4.23 ft	X	X	-	-	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-4-6	7/25/2018	4 - 6 ft	855.25	855.48	0.23	4.23-6.23 ft	X	X	-	-	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-6-8	7/25/2018	6 - 8 ft	855.25	855.48	0.23	6.23-8.23 ft	X	X	-	-	-
Football Field	SSHS-B2109	SSHS-B2109-SUB-8-10	7/25/2018	8 - 10 ft	855.25	855.48	0.23	8.23-10.23 ft	X	X	-	-	-
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	0.17 - 2 ft	854.78	-	-	-	X	X	X	X	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	0.17 - 2 ft	854.78	-	-	-	X	X	X	X	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-2-4	7/25/2018	2 - 4 ft	854.78	-	-	-	X	X	-	-	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-4-6	7/25/2018	4 - 6 ft	854.78	-	-	-	X	X	-	-	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-10-12	7/25/2018	10 - 12 ft	854.78	855.36	0.58	10.58-12.58 ft	X	X	-	-	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	12 - 14 ft	854.78	855.36	0.58	12.58-14.58 ft	X	X	X	X	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-6-8	7/25/2018	6 - 8 ft	854.78	855.36	0.58	6.58-8.58 ft	X	X	-	-	-
Football Field	SSHS-B2110	SSHS-B2110-SUB-8-10	7/25/2018	8 - 10 ft	854.78	855.36	0.58	8.58-10.58 ft	X	X	-	-	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.91	-	-	-	X	X	X	X	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-2-4	7/25/2018	2 - 4 ft	855.91	855.91	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-10-12	7/25/2018	10 - 12 ft	855.91	855.91	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-4-6	7/25/2018	4 - 6 ft	855.91	855.91	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-6-8	7/25/2018	6 - 8 ft	855.91	855.91	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-8-10	7/25/2018	8 - 10 ft	855.91	855.91	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	12 - 14 ft	855.91	855.91	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	0.17 - 2 ft	856.01	-	-	-	X	X	X	X	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-10-12	7/25/2018	10 - 12 ft	856.01	856.01	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2128	PS-FD-19	7/25/2018	2 - 4 ft	856.01	856.01	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-2-4	7/25/2018	2 - 4 ft	856.01	856.01	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-4-6	7/25/2018	4 - 6 ft	856.01	856.01	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-6-8	7/25/2018	6 - 8 ft	856.01	856.01	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-8-10	7/25/2018	8 - 10 ft	856.01	856.01	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	12 - 14 ft	856.01	856.01	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	0.17 - 2 ft	855.33	-	-	-	X	X	X	X	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	0.17 - 2 ft	855.33	-	-	-	X	X	X	X	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-10-12	7/25/2018	10 - 12 ft	855.33	855.52	0.19	10.19-12.19 ft	X	X	-	-	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	12 - 14 ft	855.33	855.52	0.19	12.19-14.19 ft	X	X	-	X	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-2-4	7/25/2018	2 - 4 ft	855.33	855.52	0.19	2.19-4.19 ft	X	X	-	-	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-4-6	7/25/2018	4 - 6 ft	855.33	855.52	0.19	4.19-6.19 ft	X	X	-	-	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-6-8	7/25/2018	6 - 8 ft	855.33	855.52	0.19	6.19-8.19 ft	X	X	-	-	-
Football Field	SSHS-B2129	SSHS-B2129-SUB-8-10	7/25/2018	8 - 10 ft	855.33	855.52	0.19	8.19-10.19 ft	X	X	-	-	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	0.17 - 2 ft	856.56	-	-	-	-	X	X	X	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-10-12	7/25/2018	10 - 12 ft	856.56	856.56	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-2-4	7/25/2018	2 - 4 ft	856.56	856.56	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-4-6	7/25/2018	4 - 6 ft	856.56	856.56	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2143	PS-FD-21	7/25/2018	6 - 8 ft	856.56	856.56	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-6-8	7/25/2018	6 - 8 ft	856.56	856.56	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-8-10	7/25/2018	8 - 10 ft	856.56	856.56	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	12 - 14 ft	856.56	856.56	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2194	SSHS-B2194-SUB-2-4	7/25/2018	2 - 4 ft	856.19	-	-	-	X	X	-	-	-
Football Field	SSHS-B2194	SSHS-B2194-SUB-10-12	7/25/2018	10 - 12 ft	856.19	856.19	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2194	SSHS-B2194-SUB-4-6	7/25/2018	4 - 6 ft	856.19	856.19	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2194	PS-FD-30	7/25/2018	6 - 8 ft	856.19	856.19	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2194	SSHS-B2194-SUB-6-8	7/25/2018	6 - 8 ft	856.19	856.19	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2194	SSHS-B2194-SUB-8-10	7/25/2018	8 - 10 ft	856.19	856.19	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2216	SSHS-B2216-SUB-10-12	7/25/2018	10 - 12 ft	855.16	855.46	0.30	10.3-12.3 ft	X	X	-	-	-
Football Field	SSHS-B2216	PS-FD-25	7/25/2018	2 - 4 ft	855.16	855.46	0.30	2.3-4.3 ft	X	X	-	-	-
Football Field	SSHS-B2216	SSHS-B2216-SUB-2-4	7/25/2018	2 - 4 ft	855.16	855.46	0.30	2.3-4.3 ft	X	X	-	-	-
Football Field	SSHS-B2216	SSHS-B2216-SUB-4-6	7/25/2018	4 - 6 ft	855.16	855.46	0.30	4.3-6.3 ft	X	X	-	-	-
Football Field	SSHS-B2216	SSHS-B2216-SUB-6-8	7/25/2018	6 - 8 ft	855.16	855.46	0.30	6.3-8.3 ft	X	X	-	-	-
Football Field	SSHS-B2216	SSHS-B2216-SUB-8-10	7/25/2018	8 - 10 ft	855.16	855.46	0.30	8.3-10.3 ft	X	X	-	-	-
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	12 - 14 ft	855.16	855.46	0.30	12.3-14.3 ft	X	X	-	X	-
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	0 - 0.17 ft	855.38	-	-	-	-	X	X	-	-
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	0 - 0.17 ft	855.74	-	-	-	-	X	X	-	-
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	0 - 0.17 ft	856.38	-	-	-	-	X	X	-	-
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	0 - 0.17 ft	854.93	-	-	-	-	X	X	-	-
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	0 - 0.17 ft	857.03	-	-	-	-	X	X	-	-
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	0 - 0.17 ft	856.56	-	-	-	-	X	X	-	-
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	0 - 0.17 ft	856.82	-	-	-	-	X	X	-	-
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	0 - 0.17 ft	855.25	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-2-4	7/26/2018	2 - 4 ft	852.76	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-8-10	7/26/2018	8 - 10 ft	852.76	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	0.17 - 2 ft	852.76	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-10-12	7/26/2018	10 - 12 ft	852.76	854.11	1.35	11.35-13.35 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	12 - 14 ft	852.76	854.11	1.35	13.35-15.35 ft	X	X	-	X	-
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	0.17 - 2 ft	854.55	-	-	-	-	X	X	X	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	0.17 - 2 ft	854.55	-	-	-	X	X	X	X	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-10-12	7/26/2018	10 - 12 ft	854.55	854.52	-0.03	9.97-11.97 ft	X	X	-	-	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	12 - 14 ft	854.55	854.52	-0.03	11.97-13.97 ft	X	X	-	X	-
Football Field	SSHS-B2025	PS-FD-37	7/26/2018	2 - 4 ft	854.55	854.52	-0.03	1.97-3.97 ft	X	X	-	-	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-2-4	7/26/2018	2 - 4 ft	854.55	854.52	-0.03	1.97-3.97 ft	X	X	-	-	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-4-6	7/26/2018	4 - 6 ft	854.55	854.52	-0.03	3.97-5.97 ft	X	X	-	-	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-6-8	7/26/2018	6 - 8 ft	854.55	854.52	-0.03	5.97-7.97 ft	X	X	-	-	-
Football Field	SSHS-B2025	SSHS-B2025-SUB-8-10	7/26/2018	8 - 10 ft	854.55	854.52	-0.03	7.97-9.97 ft	X	X	-	-	-
Football Field	SSHS-B2026	SSHS-B2026-SUB-10-12	7/26/2018	10 - 12 ft	855.26	855.47	0.21	10.21-12.21 ft	X	X	-	-	-
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	12 - 14 ft	855.26	855.47	0.21	12.21-14.21 ft	X	X	-	X	-
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	2 - 4 ft	855.26	855.47	0.21	2.21-4.21 ft	X	X	X	-	-
Football Field	SSHS-B2026	PS-FD-38	7/26/2018	4 - 6 ft	855.26	855.47	0.21	4.21-6.21 ft	X	X	-	-	-
Football Field	SSHS-B2026	SSHS-B2026-SUB-4-6	7/26/2018	4 - 6 ft	855.26	855.47	0.21	4.21-6.21 ft	X	X	-	-	-
Football Field	SSHS-B2026	SSHS-B2026-SUB-6-8	7/26/2018	6 - 8 ft	855.26	855.47	0.21	6.21-8.21 ft	X	X	-	-	-
Football Field	SSHS-B2026	SSHS-B2026-SUB-8-10	7/26/2018	8 - 10 ft	855.26	855.47	0.21	8.21-10.21 ft	X	X	-	-	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.22	-	-	-	X	X	X	X	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	10 - 12 ft	855.22	-	-	-	X	X	X	X	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-2-4	7/26/2018	2 - 4 ft	855.22	-	-	-	X	X	-	-	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-4-6	7/26/2018	4 - 6 ft	855.22	-	-	-	X	X	-	-	-
Football Field	SSHS-B2027	PS-FD-39	7/26/2018	6 - 8 ft	855.22	-	-	-	X	X	-	-	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-6-8	7/26/2018	6 - 8 ft	855.22	-	-	-	X	X	-	-	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	8 - 10 ft	855.22	-	-	-	X	X	X	X	-
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	12 - 14 ft	855.22	855.52	0.30	12.3-14.3 ft	X	X	-	X	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.23	-	-	-	X	X	X	X	-
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	0.17 - 2 ft	855.23	-	-	-	X	X	X	X	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-2-4	7/26/2018	2 - 4 ft	855.23	-	-	-	X	X	-	-	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-4-6	7/26/2018	4 - 6 ft	855.23	-	-	-	X	X	-	-	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-10-12	7/26/2018	10 - 12 ft	855.23	855.54	0.31	10.31-12.31 ft	X	X	-	-	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	12 - 14 ft	855.23	855.54	0.31	12.31-14.31 ft	X	X	-	X	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-6-8	7/26/2018	6 - 8 ft	855.23	855.54	0.31	6.31-8.31 ft	X	X	-	-	-
Football Field	SSHS-B2028	SSHS-B2028-SUB-8-10	7/26/2018	8 - 10 ft	855.23	855.54	0.31	8.31-10.31 ft	X	X	-	-	-
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.45	-	-	-	X	X	X	X	-
Football Field	SSHS-B2050	SSHS-B2050-SUB-10-12	7/26/2018	10 - 12 ft	855.45	855.45	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2050	SSHS-B2050-SUB-2-4	7/26/2018	2 - 4 ft	855.45	855.45	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2050	SSHS-B2050-SUB-4-6	7/26/2018	4 - 6 ft	855.45	855.45	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2050	SSHS-B2050-SUB-6-8	7/26/2018	6 - 8 ft	855.45	855.45	0.00	6-8 ft	X	X	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2050	SSHS-B2050-SUB-8-10	7/26/2018	8 - 10 ft	855.45	855.45	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	12 - 14 ft	855.45	855.45	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	0 - 0.17 ft	855.40	-	-	-	-	X	X	-	-
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	0 - 0.17 ft	855.64	-	-	-	X	X	X	-	-
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	0 - 0.17 ft	855.25	-	-	-	X	X	X	-	-
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	0 - 0.17 ft	854.78	-	-	-	X	X	X	-	-
Football Field	SSHS-B2192	SSHS-B2192-SUB-10-12	7/26/2018	10 - 12 ft	855.49	855.50	0.01	10.01-12.01 ft	X	X	-	-	-
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	12 - 14 ft	855.49	855.50	0.01	12.01-14.01 ft	X	X	-	X	-
Football Field	SSHS-B2192	PS-FD-34	7/26/2018	4 - 6 ft	855.49	855.50	0.01	4.01-6.01 ft	X	X	-	-	-
Football Field	SSHS-B2192	SSHS-B2192-SUB-4-6	7/26/2018	4 - 6 ft	855.49	855.50	0.01	4.01-6.01 ft	X	X	-	-	-
Football Field	SSHS-B2192	SSHS-B2192-SUB-6-8	7/26/2018	6 - 8 ft	855.49	855.50	0.01	6.01-8.01 ft	X	X	-	-	-
Football Field	SSHS-B2192	SSHS-B2192-SUB-8-10	7/26/2018	8 - 10 ft	855.49	855.50	0.01	8.01-10.01 ft	X	X	-	-	-
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	0.17 - 2 ft	857.04	-	-	-	-	X	X	X	-
Football Field	SSHS-B2193	PS-FD-33	7/26/2018	2 - 4 ft	857.04	-	-	-	X	X	-	-	-
Football Field	SSHS-B2193	SSHS-B2193-SUB-2-4	7/26/2018	2 - 4 ft	857.04	-	-	-	X	X	-	-	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.94	-	-	-	X	X	X	X	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-2-4	7/26/2018	2 - 4 ft	855.94	-	-	-	X	X	-	-	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-10-12	7/26/2018	10 - 12 ft	855.94	855.94	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	12 - 14 ft	855.94	855.94	0.00	12-14 ft	X	X	X	X	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-4-6	7/26/2018	4 - 6 ft	855.94	855.94	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-6-8	7/26/2018	6 - 8 ft	855.94	855.94	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2195	PS-FD-31	7/26/2018	8 - 10 ft	855.94	855.94	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2195	SSHS-B2195-SUB-8-10	7/26/2018	8 - 10 ft	855.94	855.94	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.06	-	-	-	X	X	X	X	-
Football Field	SSHS-B2213	PS-FD-35	7/26/2018	10 - 12 ft	855.06	855.53	0.47	10.47-12.47 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-10-12	7/26/2018	10 - 12 ft	855.06	855.53	0.47	10.47-12.47 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-2-4	7/26/2018	2 - 4 ft	855.06	855.53	0.47	2.47-4.47 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-4-6	7/26/2018	4 - 6 ft	855.06	855.53	0.47	4.47-6.47 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-6-8	7/26/2018	6 - 8 ft	855.06	855.53	0.47	6.47-8.47 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-8-10	7/26/2018	8 - 10 ft	855.06	855.53	0.47	8.47-10.47 ft	X	X	-	-	-
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	12 - 14 ft	855.06	855.53	0.47	12.47-14.47 ft	X	X	-	X	-
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.14	-	-	-	X	X	X	-	-
Football Field	SSHS-B2214	SSHS-B2214-SUB-10-12	7/26/2018	10 - 12 ft	855.14	855.34	0.20	10.2-12.2 ft	X	X	-	-	-
Football Field	SSHS-B2214	SSHS-B2214-SUB-4-6	7/26/2018	4 - 6 ft	855.14	855.34	0.20	4.2-6.2 ft	X	X	-	-	-
Football Field	SSHS-B2214	SSHS-B2214-SUB-8-10	7/26/2018	8 - 10 ft	855.14	855.34	0.20	8.2-10.2 ft	X	X	-	-	-
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	12 - 14 ft	855.14	855.34	0.20	12.2-14.2 ft	X	X	-	X	-
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	0.17 - 2 ft	855.11	-	-	-	X	X	X	X	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	0.17 - 2 ft	855.11	-	-	-	X	X	X	X	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-10-12	7/26/2018	10 - 12 ft	855.11	855.30	0.19	10.19-12.19 ft	X	X	-	-	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-2-4	7/26/2018	2 - 4 ft	855.11	855.30	0.19	2.19-4.19 ft	X	X	-	-	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-4-6	7/26/2018	4 - 6 ft	855.11	855.30	0.19	4.19-6.19 ft	X	X	-	-	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-6-8	7/26/2018	6 - 8 ft	855.11	855.30	0.19	6.19-8.19 ft	X	X	-	-	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-8-10	7/26/2018	8 - 10 ft	855.11	855.30	0.19	8.19-10.19 ft	X	X	-	-	-
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	12 - 14 ft	855.11	855.30	0.19	12.19-14.19 ft	X	X	-	X	-
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	0 - 0.17 ft	855.08	-	-	-	X	X	X	-	-
Football Field	SSHS-B2223	SSHS-B2223-SUB-2-4	7/26/2018	2 - 4 ft	856.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B2223	SSHS-B2223-SUB-4-6	7/26/2018	4 - 6 ft	856.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B2223	SSHS-B2223-SUB-6-8	7/26/2018	6 - 8 ft	856.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B2223	PS-FD-42	7/26/2018	8 - 10 ft	856.38	-	-	-	X	X	-	-	-
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	8 - 10 ft	856.38	-	-	-	X	X	X	X	-
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	10 - 12 ft	856.38	856.37	-0.01	9.99-11.99 ft	X	X	X	X	-
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	12 - 14 ft	856.38	856.37	-0.01	11.99-13.99 ft	X	X	X	X	-
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	0.17 - 2 ft	854.93	-	-	-	-	X	X	X	-
Football Field	SSHS-B2224	SSHS-B2224-SUB-2-4	7/26/2018	2 - 4 ft	854.93	-	-	-	-	X	-	-	-
Football Field	SSHS-B2224	PS-FD-44	7/26/2018	10 - 12 ft	854.93	855.29	0.36	10.36-12.36 ft	X	X	-	-	-
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	10 - 12 ft	854.93	855.29	0.36	10.36-12.36 ft	X	X	X	X	-
Football Field	SSHS-B2224	SSHS-B2224-SUB-4-6	7/26/2018	4 - 6 ft	854.93	855.29	0.36	4.36-6.36 ft	X	X	-	-	-
Football Field	SSHS-B2224	SSHS-B2224-SUB-6-8	7/26/2018	6 - 8 ft	854.93	855.29	0.36	6.36-8.36 ft	X	X	-	-	-
Football Field	SSHS-B2224	SSHS-B2224-SUB-8-10	7/26/2018	8 - 10 ft	854.93	855.29	0.36	8.36-10.36 ft	X	X	-	-	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	0.17 - 2 ft	856.56	-	-	-	-	X	X	X	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	2 - 4 ft	856.56	-	-	-	-	X	X	X	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	4 - 6 ft	856.56	-	-	-	-	X	X	X	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	6 - 8 ft	856.56	-	-	-	-	X	X	X	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	12 - 14 ft	856.56	856.56	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	10 - 12 ft	856.56	856.56	0.00	10-12 ft	X	X	X	X	-
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	8 - 10 ft	856.56	856.56	0.00	8-10 ft	-	X	X	X	-
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	0.17 - 2 ft	856.55	-	-	-	-	X	X	X	-
Football Field	SSHS-B2227	SSHS-B2227-SUB-2-4	7/26/2018	2 - 4 ft	856.55	-	-	-	-	X	-	-	-
Football Field	SSHS-B2227	SSHS-B2227-SUB-4-6	7/26/2018	4 - 6 ft	856.55	-	-	-	-	X	-	-	-
Football Field	SSHS-B2227	SSHS-B2227-SUB-6-8	7/26/2018	6 - 8 ft	856.55	-	-	-	-	X	-	-	-
Football Field	SSHS-B2227	SSHS-B2227-SUB-10-12	7/26/2018	10 - 12 ft	856.55	856.55	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2227	SSHS-B2227-SUB-8-10	7/26/2018	8 - 10 ft	856.55	856.55	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	0 - 2 ft	855.24	-	-	-	X	X	X	X	-
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	0 - 2 ft	855.24	-	-	-	X	X	X	X	-
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	2 - 4 ft	855.24	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-10-12	7/27/2018	10 - 12 ft	856.20	856.42	0.22	10.22-12.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-2-4	7/27/2018	2 - 4 ft	856.20	856.42	0.22	2.22-4.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-4-6	7/27/2018	4 - 6 ft	856.20	856.42	0.22	4.22-6.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-6-8	7/27/2018	6 - 8 ft	856.20	856.42	0.22	6.22-8.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-8-10	7/27/2018	8 - 10 ft	856.20	856.42	0.22	8.22-10.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	0 - 2 ft	856.20	856.42	0.22	0.22-2.22 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	12 - 14 ft	856.20	856.42	0.22	12.22-14.22 ft	X	X	-	X	-
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.50	-	-	-	-	X	X	X	-
Football Field	SSHS-B2031	PS-FD-48	7/27/2018	10 - 12 ft	855.50	855.50	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2031	SSHS-B2031-SUB-10-12	7/27/2018	10 - 12 ft	855.50	855.50	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2031	SSHS-B2031-SUB-2-4	7/27/2018	2 - 4 ft	855.50	855.50	0.00	2-4 ft	X	X	-	-	-
Football Field	SSHS-B2031	SSHS-B2031-SUB-4-6	7/27/2018	4 - 6 ft	855.50	855.50	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B2031	SSHS-B2031-SUB-6-8	7/27/2018	6 - 8 ft	855.50	855.50	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2031	SSHS-B2031-SUB-8-10	7/27/2018	8 - 10 ft	855.50	855.50	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	0.17 - 2 ft	854.88	-	-	-	-	X	X	X	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-2-4	7/27/2018	2 - 4 ft	854.88	-	-	-	-	X	-	-	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-10-12	7/27/2018	10 - 12 ft	854.88	855.51	0.63	10.63-12.63 ft	X	X	-	-	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	12 - 14 ft	854.88	855.51	0.63	12.63-14.63 ft	X	X	-	X	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-4-6	7/27/2018	4 - 6 ft	854.88	855.51	0.63	4.63-6.63 ft	-	X	-	-	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-6-8	7/27/2018	6 - 8 ft	854.88	855.51	0.63	6.63-8.63 ft	-	X	-	-	-
Football Field	SSHS-B2032	PS-FD-46	7/27/2018	8 - 10 ft	854.88	855.51	0.63	8.63-10.63 ft	-	X	-	-	-
Football Field	SSHS-B2032	SSHS-B2032-SUB-8-10	7/27/2018	8 - 10 ft	854.88	855.51	0.63	8.63-10.63 ft	-	X	-	-	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	0.17 - 2 ft	854.70	-	-	-	-	X	X	X	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-2-4	7/27/2018	2 - 4 ft	854.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-10-12	7/27/2018	10 - 12 ft	854.70	855.74	1.04	11.04-13.04 ft	-	X	-	-	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	12 - 14 ft	854.70	855.74	1.04	13.04-15.04 ft	-	X	-	X	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-4-6	7/27/2018	4 - 6 ft	854.70	855.74	1.04	5.04-7.04 ft	-	X	-	-	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-6-8	7/27/2018	6 - 8 ft	854.70	855.74	1.04	7.04-9.04 ft	-	X	-	-	-
Football Field	SSHS-B2033	SSHS-B2033-SUB-8-10	7/27/2018	8 - 10 ft	854.70	855.74	1.04	9.04-11.04 ft	-	X	-	-	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.08	-	-	-	X	X	X	X	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-2-4	7/27/2018	2 - 4 ft	855.08	-	-	-	X	X	-	-	-
Football Field	SSHS-B2051	PS-FD-45	7/27/2018	4 - 6 ft	855.08	-	-	-	X	X	-	-	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-4-6	7/27/2018	4 - 6 ft	855.08	-	-	-	X	X	-	-	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-10-12	7/27/2018	10 - 12 ft	855.08	855.37	0.29	10.29-12.29 ft	X	X	-	-	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	12 - 14 ft	855.08	855.37	0.29	12.29-14.29 ft	X	X	-	X	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-6-8	7/27/2018	6 - 8 ft	855.08	855.37	0.29	6.29-8.29 ft	X	X	-	-	-
Football Field	SSHS-B2051	SSHS-B2051-SUB-8-10	7/27/2018	8 - 10 ft	855.08	855.37	0.29	8.29-10.29 ft	X	X	-	-	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	0.17 - 2 ft	856.16	-	-	-	X	X	X	-	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-2-4	7/27/2018	2 - 4 ft	856.16	-	-	-	X	X	-	-	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-4-6	7/27/2018	4 - 6 ft	856.16	-	-	-	X	X	-	-	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-6-8	7/27/2018	6 - 8 ft	856.16	-	-	-	X	X	-	-	-
Football Field	SSHS-B2071	PS-FD-47	7/27/2018	10 - 12 ft	856.16	856.16	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-10-12	7/27/2018	10 - 12 ft	856.16	856.16	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	12 - 14 ft	856.16	856.16	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2071	SSHS-B2071-SUB-8-10	7/27/2018	8 - 10 ft	856.16	856.16	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.97	-	-	-	X	X	X	-	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-2-4	7/27/2018	2 - 4 ft	855.97	-	-	-	X	X	-	-	-
Football Field	SSHS-B2090	PS-FD-49	7/27/2018	4 - 6 ft	855.97	-	-	-	X	X	-	-	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-4-6	7/27/2018	4 - 6 ft	855.97	-	-	-	X	X	-	-	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-10-12	7/27/2018	10 - 12 ft	855.97	855.96	-0.01	9.99-11.99 ft	X	X	-	-	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	12 - 14 ft	855.97	855.96	-0.01	11.99-13.99 ft	X	X	-	X	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-6.8	7/27/2018	6 - 8 ft	855.97	855.96	-0.01	5.99-7.99 ft	X	X	-	-	-
Football Field	SSHS-B2090	SSHS-B2090-SUB-8-10	7/27/2018	8 - 10 ft	855.97	855.96	-0.01	7.99-9.99 ft	X	X	-	-	-
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	0 - 2 ft	856.06	-	-	-	X	X	X	X	-
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	2 - 4 ft	856.06	-	-	-	X	X	X	-	-
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	2 - 4 ft	856.06	-	-	-	X	X	X	-	-
Football Field	SSHS-B2190	SSHS-B2190-SUB-4-6	7/27/2018	4 - 6 ft	856.06	-	-	-	X	X	-	-	-
Football Field	SSHS-B2190	SSHS-B2190-SUB-6-8	7/27/2018	6 - 8 ft	856.06	856.06	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B2190	SSHS-B2190-SUB-8-10	7/27/2018	8 - 10 ft	856.06	856.06	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.08	-	-	-	X	X	X	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2217	SSHS-B2217-SUB-2-4	7/27/2018	2 - 4 ft	855.08	-	-	-	X	X	-	-	-
Football Field	SSHS-B2217	SSHS-B2217-SUB-10-12	7/27/2018	10 - 12 ft	855.08	855.32	0.24	10.24-12.24 ft	X	X	-	-	-
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	12 - 14 ft	855.08	855.32	0.24	12.24-14.24 ft	X	X	-	X	-
Football Field	SSHS-B2217	PS-FD-51	7/27/2018	4 - 6 ft	855.08	855.32	0.24	4.24-6.24 ft	X	X	-	-	-
Football Field	SSHS-B2217	SSHS-B2217-SUB-4-6	7/27/2018	4 - 6 ft	855.08	855.32	0.24	4.24-6.24 ft	X	X	-	-	-
Football Field	SSHS-B2217	SSHS-B2217-SUB-6-8	7/27/2018	6 - 8 ft	855.08	855.32	0.24	6.24-8.24 ft	X	X	-	-	-
Football Field	SSHS-B2217	SSHS-B2217-SUB-8-10	7/27/2018	8 - 10 ft	855.08	855.32	0.24	8.24-10.24 ft	X	X	-	-	-
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	0.17 - 2 ft	855.33	-	-	-	-	X	X	X	-
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.33	-	-	-	-	X	X	X	-
Football Field	SSHS-B2228	SSHS-B2228-SUB-4-6	7/27/2018	4 - 6 ft	855.33	-	-	-	X	X	-	-	-
Football Field	SSHS-B2228	SSHS-B2228-SUB-6-8	7/27/2018	6 - 8 ft	855.33	-	-	-	X	X	-	-	-
Football Field	SSHS-B2228	SSHS-B2228-SUB-10-12	7/27/2018	10 - 12 ft	855.33	855.33	0.00	10-12 ft	X	X	-	-	-
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	12 - 14 ft	855.33	855.33	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B2228	SSHS-B2228-SUB-8-10	7/27/2018	8 - 10 ft	855.33	855.33	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.28	-	-	-	X	X	X	X	-
Football Field	SSHS-B2229	SSHS-B2229-SUB-2-4	7/27/2018	2 - 4 ft	855.28	-	-	-	X	X	-	-	-
Football Field	SSHS-B2229	SSHS-B2229-SUB-4-6	7/27/2018	4 - 6 ft	855.28	-	-	-	X	X	-	-	-
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.25	-	-	-	-	X	X	X	-
Football Field	SSHS-B2236	SSHS-B2236-SUB-2-4	7/27/2018	2 - 4 ft	855.25	-	-	-	X	X	-	-	-
Football Field	SSHS-B2236	PS-FD-52	7/27/2018	4 - 6 ft	855.25	-	-	-	X	X	-	-	-
Football Field	SSHS-B2236	SSHS-B2236-SUB-4-6	7/27/2018	4 - 6 ft	855.25	-	-	-	X	X	-	-	-
Football Field	SSHS-B2237	SSHS-B2237-SUB-2-4	7/27/2018	2 - 4 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	0.17 - 2 ft	855.30	-	-	-	-	X	X	X	-
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	0.17 - 2 ft	855.30	-	-	-	-	X	X	X	-
Rear Parking Lot	SSHS-B1082	SSHS-B1082-SUB-6-8	7/28/2018	6 - 8 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1082	SSHS-B1082-SUB-8-10	7/28/2018	8 - 10 ft	850.01	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-2-4	7/28/2018	2 - 4 ft	851.62	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1204	SSHS-B1204-SUB-10-12	7/28/2018	10 - 12 ft	850.73	850.43	-0.30	9.70-11.70 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1218	SSHS-B1218-SUB-4-6	7/28/2018	4 - 6 ft	849.34	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1238	SSHS-B1238-SUB-4-6	7/28/2018	4 - 6 ft	848.61	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1238	SSHS-B1238-SUB-8-10	7/28/2018	8 - 10 ft	848.61	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1239	SSHS-B1239-SUB-4-6	7/28/2018	4 - 6 ft	847.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1239	SSHS-B1239-SUB-6-8	7/28/2018	6 - 8 ft	847.52	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1245	SSHS-B1245-SUB-4-6	7/28/2018	4 - 6 ft	849.10	850.00	0.90	4.90-6.90 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1245	SSHS-B1245-SUB-6-8	7/28/2018	6 - 8 ft	849.10	850.00	0.90	6.90-8.90 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-6-8	7/28/2018	6 - 8 ft	849.24	-	-	-	X	-	-	-	-
Rear Parking Lot	SSHS-B1253	SSHS-B1253-SUB-6-8	7/28/2018	8 - 10 ft	851.00	850.95	-0.05	7.95-9.95 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B1395a	SSHS-B1395-SUB-0-2	7/28/2018	0 - 2 ft	851.59	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	0 - 0.17 ft	852.76	-	-	-	X	X	X	-	-
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	0 - 0.17 ft	854.55	-	-	-	X	X	X	-	-
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	0 - 0.17 ft	855.26	855.47	0.21	0.21-0.38 ft	X	X	X	-	-
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	0 - 0.17 ft	855.22	-	-	-	X	X	X	-	-
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	0 - 0.17 ft	855.23	-	-	-	X	X	X	-	-
Football Field	SSHS-B2031	FD-57	7/28/2018	0 - 0.17 ft	855.50	-	-	-	-	X	X	-	-
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	0 - 0.17 ft	855.50	-	-	-	-	X	X	-	-
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	0 - 0.17 ft	854.88	-	-	-	-	X	X	-	-
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	0 - 0.17 ft	854.70	-	-	-	-	X	X	-	-
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	0 - 0.17 ft	855.45	-	-	-	X	X	X	-	-
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	0 - 0.17 ft	855.08	-	-	-	X	X	X	-	-
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	0 - 0.17 ft	855.00	-	-	-	X	X	X	-	-
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	0 - 0.17 ft	854.72	-	-	-	X	X	X	-	-
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	0 - 0.17 ft	855.91	-	-	-	X	X	X	-	-
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	0 - 0.17 ft	856.01	-	-	-	X	X	X	-	-
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	0 - 0.17 ft	855.33	-	-	-	X	X	X	-	-
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	0 - 0.17 ft	856.56	-	-	-	-	X	X	-	-
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	0 - 0.17 ft	855.49	-	-	-	-	X	X	-	-
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	0 - 0.17 ft	855.28	-	-	-	-	X	X	-	-
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	0 - 0.17 ft	854.83	-	-	-	-	X	X	-	-
Rear Parking Lot	SSHS-B1346	SSHS-B1346-SUB-4-6	8/3/2018	4 - 6 ft	851.99	852.20	0.21	4.21-6.21 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1390	SSHS-B1390-SUB-8-10	8/4/2018	8 - 10 ft	851.82	-	-	-	X	X	-	-	-
Rear Parking Lot	SSHS-B1500	SSHS-B1500 (6-8) 20180821	8/21/2018	6 - 8 ft	-	847.03	-	6-8 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B1502	SSHS-B1502 (10-12) 20180821	8/21/2018	10 - 12 ft	-	850.00	-	9.71-11.71 ft	X	-	-	-	-
Football Field	SSHS-B2450	SSHS-B2450-SS	8/24/2018	0 - 0.17 ft	855.62	-	-	-	X	-	-	-	-
Football Field	SSHS-B2451	SSHS-B2451-SS	8/24/2018	0 - 0.17 ft	855.47	-	-	-	X	-	-	-	-
Football Field	SSHS-B2452	SSHS-B2452-SS	8/24/2018	0 - 0.17 ft	855.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B2453	SSHS-B2453-SS	8/24/2018	0 - 0.17 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B2454	SSHS-B2454-SS	8/24/2018	0 - 0.17 ft	856.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B2455	PS-FD-2	8/24/2018	0 - 0.17 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B2455	SSHS-B2455-SS	8/24/2018	0 - 0.17 ft	855.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B2310	SSHS-B2310-SUB-2-4	8/27/2018	2 - 4 ft	856.81	-	-	-	X	-	-	-	-
Football Field	SSHS-B2310	SSHS-B2310-SUB-4-6	8/27/2018	4 - 6 ft	856.81	-	-	-	X	-	-	-	-
Football Field	SSHS-B2312	SSHS-B2312-SUB-0.17-2	8/27/2018	0.17 - 2 ft	856.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B2313	SSHS-B2313-SUB-0.17-2	8/27/2018	0.17 - 2 ft	856.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B2342	SSHS-B2342-SUB-0.17-2	8/27/2018	0.17 - 2 ft	855.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B2343	SSHS-B2343-SUB-2-4	8/27/2018	2 - 4 ft	855.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2343	SSHS-B2343-SUB-0.17-2	8/27/2018	0.17 - 2 ft	855.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2343	SSHS-B2343-SUB-4-6	8/27/2018	4 - 6 ft	855.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2344	SSHS-B2344-SUB-2-4	8/27/2018	2 - 4 ft	854.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B2344	SSHS-B2344-SUB-4-6	8/27/2018	4 - 6 ft	854.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B2350	SSHS-B2350-SUB-2-4	8/27/2018	2 - 4 ft	856.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B2352	SSHS-B2352-SUB-2-4	8/27/2018	2 - 4 ft	855.74	-	-	-	X	-	-	-	-
Football Field	SSHS-B2352	SSHS-B2352-SUB-4-6	8/27/2018	4 - 6 ft	855.74	-	-	-	X	-	-	-	-
Football Field	SSHS-B2353	SSHS-B2353-SUB-2-4	8/27/2018	2 - 4 ft	855.66	-	-	-	X	-	-	-	-
Football Field	SSHS-B2353	SSHS-B2353-SUB-4-6	8/27/2018	4 - 6 ft	855.66	-	-	-	X	-	-	-	-
Football Field	SSHS-B2354	SSHS-B2354-SUB-2-4	8/27/2018	2 - 4 ft	855.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B2354	PS-FD-3	8/27/2018	4 - 6 ft	855.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B2354	SSHS-B2354-SUB-4-6	8/27/2018	4 - 6 ft	855.52	-	-	-	X	-	-	-	-
Football Field	SSHS-B2360	PS-FD-4	8/27/2018	2 - 4 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2360	SSHS-B2360-SUB-2-4	8/27/2018	2 - 4 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2360	SSHS-B2360-SUB-4-6	8/27/2018	4 - 6 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2411	SSHS-B2411-SUB-6-8	8/27/2018	6 - 8 ft	855.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B2411	SSHS-B2411-SUB-8-10	8/27/2018	8 - 10 ft	855.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B2301	SSHS-B2301-SUB-0.17-2	8/28/2018	0.17 - 2 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B2301	SSHS-B2301-SUB-2-4	8/28/2018	2 - 4 ft	855.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B2309	SSHS-B2309-SUB-2-4	8/28/2018	2 - 4 ft	856.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B2309	SSHS-B2309-SUB-0.17-2	8/28/2018	0.17 - 2 ft	856.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B2309	SSHS-B2309-SUB-4-6	8/28/2018	4 - 6 ft	856.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B2314	SSHS-B2314-SUB-2-4	8/28/2018	2 - 4 ft	854.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B2329	SSHS-B2329-SUB-6-8	8/28/2018	6 - 8 ft	856.92	856.92	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B2330	PS-FD-5	8/28/2018	4 - 6 ft	856.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B2330	SSHS-B2330-SUB-4-6	8/28/2018	4 - 6 ft	856.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B2336	SSHS-B2336-SUB-2-4	8/28/2018	2 - 4 ft	856.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2338	SSHS-B2338-SUB-2-4	8/28/2018	2 - 4 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B2339	SSHS-B2339-SUB-2-4	8/28/2018	2 - 4 ft	855.51	-	-	-	X	-	-	-	-
Football Field	SSHS-B2340	SSHS-B2340-SUB-2-4	8/28/2018	2 - 4 ft	856.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2346	PS-FD-6	8/28/2018	2 - 4 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2346	SSHS-B2346-SUB-2-4	8/28/2018	2 - 4 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2356	SSHS-B2356-SUB-2-4	8/28/2018	2 - 4 ft	856.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2356	SSHS-B2356-SUB-4-6	8/28/2018	4 - 6 ft	856.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2357	SSHS-B2357-SUB-2-4	8/28/2018	2 - 4 ft	856.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B2362	SSHS-B2362-SUB-4-6	8/28/2018	4 - 6 ft	855.13	855.25	0.12	4.12-6.12 ft	X	-	-	-	-
Football Field	SSHS-B2376	SSHS-B2376-SUB-0.17-2	8/28/2018	0.17 - 2 ft	855.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B2300	SSHS-B2300-SUB-0.17-2	8/29/2018	0.17 - 2 ft	855.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B2300	SSHS-B2300-SUB-2-4	8/29/2018	2 - 4 ft	855.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B2305	SSHS-B2305-SUB-2-4	8/29/2018	2 - 4 ft	857.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B2305	SSHS-B2305-SUB-0.17-2	8/29/2018	0.17 - 2 ft	857.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B2306	SSHS-B2306-SUB-0.17-2	8/29/2018	0.17 - 2 ft	857.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2306	SSHS-B2306-SUB-2-4	8/29/2018	2 - 4 ft	857.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2307	SSHS-B2307-SUB-0.17-2	8/29/2018	0.17 - 2 ft	857.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B2307	SSHS-B2307-SUB-2-4	8/29/2018	2 - 4 ft	857.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B2315	SSHS-B2315-SUB-0.17-2	8/29/2018	0.17 - 2 ft	854.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B2315	SSHS-B2315-SUB-2-4	8/29/2018	2 - 4 ft	854.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B2316	SSHS-B2316-SUB-2-4	8/29/2018	2 - 4 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B2317	SSHS-B2317-SUB-0.17-2	8/29/2018	0.17 - 2 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B2317	SSHS-B2317-SUB-2-4	8/29/2018	2 - 4 ft	855.56	-	-	-	X	-	-	-	-
Football Field	SSHS-B2318	SSHS-B2318-SUB-0.17-2	8/29/2018	0.17 - 2 ft	856.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B2320	SSHS-B2320-SUB-2-4	8/29/2018	2 - 4 ft	856.53	-	-	-	X	-	-	-	-
Football Field	SSHS-B2321	SSHS-B2321-SUB-2-4	8/29/2018	2 - 4 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B2326	SSHS-B2326-SUB-2-4	8/29/2018	2 - 4 ft	856.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B2331	SSHS-B2331-SUB-2-4	8/29/2018	2 - 4 ft	856.68	-	-	-	X	-	-	-	-
Football Field	SSHS-B2333	SSHS-B2333-SUB-2-4	8/29/2018	2 - 4 ft	856.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B2333	SSHS-B2333-SUB-4-6	8/29/2018	4 - 6 ft	856.57	-	-	-	X	-	-	-	-
Football Field	SSHS-B2334	SSHS-B2334-SUB-2-4	8/29/2018	2 - 4 ft	856.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B2335	SSHS-B2335-SUB-2-4	8/29/2018	2 - 4 ft	855.82	-	-	-	X	-	-	-	-
Football Field	SSHS-B2337	SSHS-B2337-SUB-2-4	8/29/2018	2 - 4 ft	855.56	-	-	-	X	-	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2358	SSHS-B2358-SUB-4-6	8/29/2018	4 - 6 ft	855.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B2367	SSHS-B2367-SUB-6-8	8/29/2018	6 - 8 ft	856.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B2368	SSHS-B2368-SUB-6-8	8/29/2018	6 - 8 ft	856.48	856.48	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B2369	SSHS-B2369-SUB-6-8	8/29/2018	6 - 8 ft	856.80	856.80	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B2321	PS-FD-10	8/30/2018	2 - 4 ft	856.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B2341	SSHS-B2341-SUB-2-4	8/30/2018	2 - 4 ft	855.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B2341	SSHS-B2341-SUB-6-8	8/30/2018	6 - 8 ft	855.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B2341	SSHS-B2341-SUB-8-10	8/30/2018	8 - 10 ft	855.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B2385	SSHS-B2385-SUB-0.17-2	8/30/2018	0.17 - 2 ft	855.00	855.38	0.38	0.55-2.38 ft	X	-	-	-	-
Football Field	SSHS-B2385	SSHS-B2385-SUB-2-4	8/30/2018	2 - 4 ft	855.00	855.38	0.38	2.38-4.38 ft	X	-	-	-	-
Football Field	SSHS-B2386	SSHS-B2386-SUB-0.17-2	8/30/2018	0.17 - 2 ft	855.18	855.37	0.19	0.36-2.19 ft	X	-	-	-	-
Football Field	SSHS-B2386	SSHS-B2386-SUB-2-4	8/30/2018	2 - 4 ft	855.18	855.37	0.19	2.19-4.19 ft	X	-	-	-	-
Football Field	SSHS-B2513	PS-FD-1	10/29/2018	4 - 6 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2513	SSHS-B2513-SUB-4-6	10/29/2018	4 - 6 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2520	SSHS-B2520-SUB-2-4	10/29/2018	2 - 4 ft	854.94	-	-	-	X	-	-	-	-
Football Field	SSHS-B2521	SSHS-B2521-SUB-2-4	10/29/2018	2 - 4 ft	855.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B2522	PS-FD-2	10/29/2018	2 - 4 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B2522	SSHS-B2522-SUB-2-4	10/29/2018	2 - 4 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B2522	SSHS-B2522-SUB-4-6	10/29/2018	4 - 6 ft	855.42	-	-	-	X	-	-	-	-
Football Field	SSHS-B2523	SSHS-B2523-SUB-2-4	10/29/2018	2 - 4 ft	855.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B2523	SSHS-B2523-SUB-4-6	10/29/2018	4 - 6 ft	855.03	855.47	0.44	4.44-6.44 ft	X	-	-	-	-
Football Field	SSHS-B2524	SSHS-B2524-SUB-2-4	10/29/2018	2 - 4 ft	855.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B2529	SSHS-B2529-SUB-4-6	10/29/2018	4 - 6 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B2530	SSHS-B2530-SUB-4-6	10/29/2018	4 - 6 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-0.17-2	10/29/2018	0.17 - 2 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-10-12	10/29/2018	10 - 12 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-2-4	10/29/2018	2 - 4 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-4-6	10/29/2018	4 - 6 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-6-8	10/29/2018	6 - 8 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-8-10	10/29/2018	8 - 10 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2532	SSHS-B2532-SUB-14-16	10/29/2018	14 - 16 ft	855.29	855.30	0.01	14.01-16.01 ft	X	-	-	-	-
Football Field	SSHS-B2500	SSHS-B2500-SUB-0.17-2	10/30/2018	0.17 - 2 ft	854.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B2501	SSHS-B2501-SUB-0.17-2	10/30/2018	0.17 - 2 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B2502	SSHS-B2502-SUB-0.17-2	10/30/2018	0.17 - 2 ft	854.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B2503	SSHS-B2503-SUB-0.17-2	10/30/2018	0.17 - 2 ft	855.00	-	-	-	X	-	-	-	-
Football Field	SSHS-B2504	SSHS-B2504-SUB-0.17-2	10/30/2018	0.17 - 2 ft	856.73	-	-	-	X	-	-	-	-
Football Field	SSHS-B2505	SSHS-B2505-SUB-0.17-2	10/30/2018	0.17 - 2 ft	856.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B2506	SSHS-B2506-SUB-0.17-2	10/30/2018	0.17 - 2 ft	856.53	-	-	-	X	-	-	-	-
Football Field	SSHS-B2519	SSHS-B2519-SUB-2-4	10/30/2018	2 - 4 ft	854.99	-	-	-	X	-	-	-	-
Football Field	SSHS-B2527	SSHS-B2527-SUB-10-12	10/30/2018	10 - 12 ft	855.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2527	SSHS-B2527-SUB-12-14	10/30/2018	12 - 14 ft	855.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2527	SSHS-B2527-SUB-14-16	10/30/2018	14 - 16 ft	855.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2527	SSHS-B2527-SUB-6-8	10/30/2018	6 - 8 ft	855.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2527	SSHS-B2527-SUB-8-10	10/30/2018	8 - 10 ft	855.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B2528	SSHS-B2528-SUB-0.17-2	10/30/2018	0.17 - 2 ft	854.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B2531	SSHS-B2531-SUB-0.17-2	10/30/2018	0.17 - 2 ft	856.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B2533	SSHS-B2533-SUB-10-12	10/30/2018	10 - 12 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2533	SSHS-B2533-SUB-12-14	10/30/2018	12 - 14 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2533	SSHS-B2533-SUB-14-16	10/30/2018	14 - 16 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2534	SSHS-B2534-SUB-10-12	10/30/2018	10 - 12 ft	855.61	-	-	-	X	-	-	-	-
Football Field	SSHS-B2534	SSHS-B2534-SUB-12-14	10/30/2018	12 - 14 ft	855.61	855.76	0.15	12.15-14.15 ft	X	-	-	-	-
Football Field	SSHS-B2534	SSHS-B2534-SUB-14-16	10/30/2018	14 - 16 ft	855.61	855.76	0.15	14.15-16.15 ft	X	-	-	-	-
Football Field	SSHS-B2535	SSHS-B2535-SUB-10-12	10/30/2018	10 - 12 ft	854.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B2535	SSHS-B2535-SUB-12-14	10/30/2018	12 - 14 ft	854.97	-	-	-	X	-	-	-	-
Football Field	SSHS-B2535	SSHS-B2535-SUB-14-16	10/30/2018	14 - 16 ft	854.97	855.22	0.25	14.25-16.25 ft	X	-	-	-	-
Football Field	SSHS-B2536	PS-FD-3	10/30/2018	12 - 14 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2536	SSHS-B2536-SUB-12-14	10/30/2018	12 - 14 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2537	PS-FD-4	10/30/2018	0.17 - 2 ft	855.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B2537	SSHS-B2537-SUB-0.17-2	10/30/2018	0.17 - 2 ft	855.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B2538	SSHS-B2538-SUB-0.17-2	10/30/2018	0.17 - 2 ft	854.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B2540	SSHS-B2540-SUB-2-4	10/30/2018	2 - 4 ft	854.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B2507	SSHS-B2507-SUB-2-4	10/31/2018	2 - 4 ft	857.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B2508	PS-FD-5	10/31/2018	2 - 4 ft	857.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B2508	SSHS-B2508-SUB-2-4	10/31/2018	2 - 4 ft	857.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B2509	SSHS-B2509-SUB-2-4	10/31/2018	2 - 4 ft	857.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B2510	SSHS-B2510-SUB-2-4	10/31/2018	2 - 4 ft	857.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B2511	SSHS-B2511-SUB-2-4	10/31/2018	2 - 4 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2512	SSHS-B2512-SUB-2-4	10/31/2018	2 - 4 ft	854.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B2514	SSHS-B2514-SUB-2-4	10/31/2018	2 - 4 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2515	SSHS-B2515-SUB-2-4	10/31/2018	2 - 4 ft	855.58	-	-	-	X	-	-	-	-
Football Field	SSHS-B2516	SSHS-B2516-SUB-2-4	10/31/2018	2 - 4 ft	855.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B2517	SSHS-B2517-SUB-0.17-2	10/31/2018	0.17 - 2 ft	855.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B2517	SSHS-B2517-SUB-2-4	10/31/2018	2 - 4 ft	855.67	-	-	-	X	-	-	-	-
Football Field	SSHS-B2518	SSHS-B2518-SUB-2-4	10/31/2018	2 - 4 ft	856.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B2525	SSHS-B2525-SUB-4-6	10/31/2018	4 - 6 ft	856.41	-	-	-	X	-	-	-	-
Football Field	SSHS-B2526	PS-FD-6	10/31/2018	4 - 6 ft	856.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B2526	SSHS-B2526-SUB-4-6	10/31/2018	4 - 6 ft	856.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B2539	SSHS-B2539-SUB-2-4	10/31/2018	2 - 4 ft	854.77	-	-	-	X	-	-	-	-
Football Field	SSHS-B2747	SSHS-B2747-SUB-2-4	4/23/2019	2 - 4 ft	856.08	-	-	-	-	X	-	-	-
Football Field	SSHS-B2747	SSHS-B2747-SUB-6-8	4/23/2019	6 - 8 ft	856.08	-	-	-	-	X	-	-	-
Football Field	SSHS-B2747	SSHS-B2747-SUB-10-12	4/23/2019	10 - 12 ft	856.08	856.07	-0.01	9.99-11.99 ft	-	X	-	-	-
Football Field	SSHS-B2747	SSHS-B2747-SUB-12-14	4/23/2019	12 - 14 ft	856.08	856.07	-0.01	11.99-13.99 ft	-	X	-	-	-
Football Field	SSHS-B2747	SSHS-B2747-SUB-8-10	4/23/2019	8 - 10 ft	856.08	856.07	-0.01	7.99-9.99 ft	-	X	-	-	-
Football Field	SSHS-B2753	SSHS-B2753-SUB-2-4	4/23/2019	2 - 4 ft	856.56	-	-	-	X	X	-	-	-
Football Field	SSHS-B2753	SSHS-B2753-SUB-4-6	4/23/2019	4 - 6 ft	856.56	-	-	-	X	X	-	-	-
Football Field	SSHS-B2753	SSHS-B2753-SUB-6-8	4/23/2019	6 - 8 ft	856.56	-	-	-	-	X	-	-	-
Football Field	SSHS-B2753	PS-FD-4	4/23/2019	8 - 10 ft	856.56	-	-	-	-	X	-	-	-
Football Field	SSHS-B2753	SSHS-B2753-SUB-8-10	4/23/2019	8 - 10 ft	856.56	-	-	-	-	X	-	-	-
Football Field	SSHS-B2753	SSHS-B2753-SUB-10-12	4/23/2019	10 - 12 ft	856.56	856.57	0.01	10.01-12.01 ft	-	X	-	-	-
Football Field	SSHS-B2753	SSHS-B2753-SUB-12-14	4/23/2019	12 - 14 ft	856.56	856.57	0.01	12.01-14.01 ft	-	X	-	-	-
Football Field	SSHS-B2766	SSHS-B2766-SUB-6-8	4/23/2019	6 - 8 ft	855.84	-	-	-	X	X	-	-	-
Football Field	SSHS-B2767	PS-FD-3	4/23/2019	2 - 4 ft	856.06	-	-	-	-	X	-	-	-
Football Field	SSHS-B2767	SSHS-B2767-SUB-2-4	4/23/2019	2 - 4 ft	856.06	-	-	-	-	X	-	-	-
Football Field	SSHS-B2767	SSHS-B2767-SUB-4-6	4/23/2019	4 - 6 ft	856.06	-	-	-	-	X	-	-	-
Football Field	SSHS-B2767	SSHS-B2767-SUB-10-12	4/23/2019	10 - 12 ft	856.06	856.06	0.00	10-12 ft	-	X	-	-	-
Football Field	SSHS-B2767	SSHS-B2767-SUB-12-14	4/23/2019	12 - 14 ft	856.06	856.06	0.00	12-14 ft	-	X	-	-	-
Football Field	SSHS-B2767	SSHS-B2767-SUB-6-8	4/23/2019	6 - 8 ft	856.06	856.06	0.00	6-8 ft	-	X	-	-	-
Football Field	SSHS-B2767	SSHS-B2767-SUB-8-10	4/23/2019	8 - 10 ft	856.06	856.06	0.00	8-10 ft	-	X	-	-	-
Football Field	SSHS-B2634	PS-FD-5	4/24/2019	12 - 14 ft	855.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B2634	SSHS-B2634-SUB-6-8	4/24/2019	6 - 8 ft	855.37	-	-	-	X	X	-	-	-
Football Field	SSHS-B2634	SSHS-B2634-SUB-12-14	4/24/2019	12 - 14 ft	855.37	-	-	-	X	-	-	-	-
Football Field	SSHS-B2637	SSHS-B2637-SUB-4-6	4/24/2019	4 - 6 ft	855.39	-	-	-	X	X	-	-	-
Football Field	SSHS-B2637	SSHS-B2637-SUB-12-14	4/24/2019	12 - 14 ft	855.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B2637	SSHS-B2637-SUB-2-4	4/24/2019	2 - 4 ft	855.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B2637	PS-FD-6	4/24/2019	8 - 10 ft	855.39	-	-	-	X	X	-	-	-
Football Field	SSHS-B2637	SSHS-B2637-SUB-8-10	4/24/2019	8 - 10 ft	855.39	-	-	-	X	X	-	-	-
Football Field	SSHS-B2679	SSHS-B2679-SUB-10-12	4/24/2019	10 - 12 ft	855.15	-	-	-	X	X	-	-	-
Football Field	SSHS-B2679	SSHS-B2679-SUB-4-6	4/24/2019	4 - 6 ft	855.15	-	-	-	X	X	-	-	-
Football Field	SSHS-B2679	SSHS-B2679-SUB-8-10	4/24/2019	8 - 10 ft	855.15	-	-	-	X	X	-	-	-
Football Field	SSHS-B2679	SSHS-B2679-SUB-14-16	4/24/2019	14 - 16 ft	855.15	855.37	0.22	14.22-16.22 ft	X	X	-	-	-
Football Field	SSHS-B2724	SSHS-B2724-SUB-4-6	4/24/2019	4 - 6 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B2724	SSHS-B2724-SUB-6-8	4/24/2019	6 - 8 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B2724	PS-FD-8	4/24/2019	2 - 4 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B2724	SSHS-B2724-SUB-2-4	4/24/2019	2 - 4 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B2724	SSHS-B2724-SUB-12-14	4/24/2019	12 - 14 ft	855.34	855.35	0.01	12.01-14.01 ft	X	X	-	-	-
Football Field	SSHS-B2741	SSHS-B2741-SUB-10-12	4/24/2019	10 - 12 ft	855.31	-	-	-	-	X	-	-	-
Football Field	SSHS-B2743	SSHS-B2743-SUB-10-12	4/24/2019	10 - 12 ft	855.11	-	-	-	-	X	-	-	-
Football Field	SSHS-B2745	PS-FD-7	4/24/2019	10 - 12 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2745	SSHS-B2745-SUB-10-12	4/24/2019	10 - 12 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-10-12	4/24/2019	10 - 12 ft	856.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-12-14	4/24/2019	12 - 14 ft	856.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-14-16	4/24/2019	14 - 16 ft	856.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-2-4	4/24/2019	2 - 4 ft	856.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-4-6	4/24/2019	4 - 6 ft	856.83	-	-	-	-	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-6-8	4/24/2019	6 - 8 ft	856.83	-	-	-	-	X	-	-	-
Football Field	SSHS-B2752	SSHS-B2752-SUB-8-10	4/24/2019	8 - 10 ft	856.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B2629	SSHS-B2629-SUB-10-12	4/25/2019	10 - 12 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2629	SSHS-B2629-SUB-2-4	4/25/2019	2 - 4 ft	855.32	-	-	-	X	X	-	-	-
Football Field	SSHS-B2629	PS-FD-12	4/25/2019	4 - 6 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2629	SSHS-B2629-SUB-4-6	4/25/2019	4 - 6 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2629	PS-FD-9	4/25/2019	6 - 8 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2629	SSHS-B2629-SUB-6-8	4/25/2019	6 - 8 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2629	SSHS-B2629-SUB-8-10	4/25/2019	8 - 10 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2629	SSHS-B2629-SUB-14-16	4/25/2019	14 - 16 ft	855.32	855.43	0.11	14.11-16.11 ft	X	-	-	-	-
Football Field	SSHS-B2660	SSHS-B2660-SUB-2-4	4/25/2019	2 - 4 ft	855.76	-	-	-	X	X	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2660	SSHS-B2660-SUB-4-6	4/25/2019	4 - 6 ft	855.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B2661	SSHS-B2661-SUB-10-12	4/25/2019	10 - 12 ft	854.80	-	-	-	X	-	-	-	-
Football Field	SSHS-B2661	SSHS-B2661-SUB-4-6	4/25/2019	4 - 6 ft	854.80	-	-	-	X	X	-	-	-
Football Field	SSHS-B2674	SSHS-B2674-SUB-6-8	4/25/2019	6 - 8 ft	854.92	-	-	-	X	-	-	-	-
Football Field	SSHS-B2682	SSHS-B2682-SUB-2-4	4/25/2019	2 - 4 ft	854.91	-	-	-	X	X	-	-	-
Football Field	SSHS-B2742	SSHS-B2742-SUB-10-12	4/25/2019	10 - 12 ft	855.04	-	-	-	-	X	-	-	-
Football Field	SSHS-B2760	SSHS-B2760-SUB-14-16	4/25/2019	14 - 16 ft	856.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B2760	SSHS-B2760-SUB-4-6	4/25/2019	4 - 6 ft	856.06	-	-	-	X	X	-	-	-
Football Field	SSHS-B2760	SSHS-B2760-SUB-6-8	4/25/2019	6 - 8 ft	856.06	-	-	-	X	X	-	-	-
Football Field	SSHS-B2761	SSHS-B2761-SUB-12-14	4/25/2019	12 - 14 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B2761	SSHS-B2761-SUB-14-16	4/25/2019	14 - 16 ft	856.14	856.33	0.19	14.19-16.19 ft	X	-	-	-	-
Football Field	SSHS-B2765	SSHS-B2765-SUB-2-4	4/25/2019	2 - 4 ft	855.77	-	-	-	-	X	-	-	-
Football Field	SSHS-B2765	PS-FD-13	4/25/2019	4 - 6 ft	855.77	-	-	-	-	X	-	-	-
Football Field	SSHS-B2765	SSHS-B2765-SUB-4-6	4/25/2019	4 - 6 ft	855.77	-	-	-	-	X	-	-	-
Football Field	SSHS-B2765	SSHS-B2765-SUB-6-8	4/25/2019	6 - 8 ft	855.77	-	-	-	-	X	-	-	-
Football Field	SSHS-B2765	SSHB-B2765-SUB-8-10	4/25/2019	8 - 10 ft	855.77	-	-	-	-	X	-	-	-
Football Field	SSHS-B2684	SSHS-B2684-SUB-2-4	4/26/2019	2 - 4 ft	856.09	-	-	-	X	X	-	-	-
Football Field	SSHS-B2684	SSHS-B2684-SUB-10-12	4/26/2019	10 - 12 ft	856.09	-	-	-	X	X	-	-	-
Football Field	SSHS-B2684	SSHS-B2684-SUB-12-14	4/26/2019	12 - 12 ft	856.09	-	-	-	X	-	-	-	-
Football Field	SSHS-B2684	SSHS-B2684-SUB-8-10	4/26/2019	8 - 10 ft	856.09	-	-	-	X	X	-	-	-
Football Field	SSHS-B2725	SSHS-B2725-SUB-6-8	4/26/2019	6 - 8 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B2725	SSHS-B2725-SUB-8-10	4/26/2019	8 - 10 ft	856.14	-	-	-	X	X	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	10 - 12 ft	855.30	-	-	-	X	-	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	12 - 14 ft	855.30	855.30	0.00	12 - 14 ft	X	-	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	12 - 14 ft	855.30	855.30	0.00	12 - 14 ft	X	-	X	X	-
Football Field	SSHS-B2756	PS-FD-14	4/26/2019	12 - 14 ft	856.39	856.41	0.02	12.02-14.02 ft	X	-	-	-	-
Football Field	SSHS-B2756	SSHS-B2756-SUB-12-14	4/26/2019	12 - 14 ft	856.39	856.41	0.02	12.02-14.02 ft	X	-	-	-	-
Football Field	SSHS-B2757	SSHS-B2757-SUB-12-14	4/26/2019	12 - 14 ft	856.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B2757	SSHS-B2757-SUB-8-10	4/26/2019	8 - 10 ft	856.35	-	-	-	X	X	-	-	-
Football Field	SSHS-B2758	SSHS-B2758-SUB-12-14	4/26/2019	12 - 14 ft	856.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B2759	SSHS-B2759-SUB-12-14	4/26/2019	12 - 14 ft	856.32	856.44	0.12	12.12-14.12 ft	X	-	-	-	-
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	2 - 4 ft	856.14	-	-	-	-	-	X	X	-
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	4 - 6 ft	856.14	-	-	-	-	-	X	X	-
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	4 - 6 ft	856.14	-	-	-	-	-	X	X	-
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	6 - 8 ft	856.14	-	-	-	-	-	X	X	-
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	10 - 12 ft	856.14	856.25	0.11	10.11-12.11 ft	-	-	X	X	-
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	12 - 14 ft	856.14	856.25	0.11	12.11-14.11 ft	-	-	X	X	-
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	8 - 10 ft	856.14	856.25	0.11	8.11-10.11 ft	-	-	X	X	-
Football Field	SSHS-B2763	SSHS-B2763-SUB-2-4	4/26/2019	2 - 4 ft	856.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2763	SSHS-B2763-SUB-4-6	4/26/2019	4 - 6 ft	856.00	-	-	-	X	X	-	-	-
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	10 - 12 ft	856.00	856.00	0.00	10-12 ft	-	-	X	X	-
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	10 - 12 ft	856.00	856.00	0.00	10-12 ft	-	-	X	X	-
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	6 - 8 ft	856.00	856.00	0.00	6-8 ft	-	-	X	X	-
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	8 - 10 ft	856.00	856.00	0.00	8-10 ft	-	-	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B2683	SSHS-B2683-SUB-12-14	4/27/2019	12 - 14 ft	855.72	855.72	0.00	12-14 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-12-14	4/27/2019	12 - 14 ft	855.31	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-10-12	4/27/2019	10 - 12 ft	855.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-12-14	4/27/2019	12 - 14 ft	855.65	-	-	-	X	X	-	-	-
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-10-12	4/27/2019	10 - 12 ft	855.65	-	-	-	X	X	-	-	-
Football Field	SSHS-B2771	SSHS-B2771-SUB-10-12	5/13/2019	10 - 12 ft	854.87	-	-	-	X	X	-	-	-
Football Field	SSHS-B2771	SSHS-B2771-SUB-6-8	5/13/2019	6 - 8 ft	854.87	-	-	-	X	X	-	-	-
Football Field	SSHS-B2771	SSHS-B2771-SUB-8-10	5/13/2019	8 - 10 ft	854.87	-	-	-	X	X	-	-	-
Football Field	SSHS-B2773	SSHS-B2773-SUB-6-8	5/13/2019	6 - 8 ft	854.27	854.35	0.08	6.08-8.08 ft	X	X	-	-	-
Football Field	SSHS-B2773	SSHS-B2773-SUB-8-10	5/13/2019	8 - 10 ft	854.27	854.35	0.08	8.08-10.08 ft	X	X	-	-	-
Football Field	SSHS-B2774	SSHS-B2774-SUB-6-8	5/13/2019	6 - 8 ft	854.02	854.07	0.05	6.05-8.05 ft	X	X	-	-	-
Football Field	SSHS-B2774	SSHS-B2774-SUB-8-10	5/13/2019	8 - 10 ft	854.02	854.07	0.05	8.05-10.05 ft	X	X	-	-	-
Football Field	SSHS-B2623	SSHS-B2623-SUB-0.17-2	5/14/2019	0.17 - 2 ft	854.91	-	-	-	X	-	-	-	-
Football Field	SSHS-B2624	SSHS-B2624-SUB-0.17-2	5/14/2019	0.17 - 2 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2650	SSHS-B2650-SUB-4-6	5/14/2019	4 - 6 ft	855.84	-	-	-	X	-	-	-	-
Football Field	SSHS-B2696	PS-FD-5	5/14/2019	2 - 4 ft	855.18	-	-	-	X	-	-	-	-
Football Field	SSHS-B2696	SSHS-B2696-SUB-2-4	5/14/2019	2 - 4 ft	855.18	-	-	-	X	-	-	-	-
Football Field	SSHS-B2697	SSHS-B2697-SUB-2-4	5/14/2019	2 - 4 ft	855.16	-	-	-	X	-	-	-	-
Football Field	SSHS-B2698	SSHS-B2698-SUB-4-6	5/14/2019	4 - 6 ft	855.31	-	-	-	X	X	-	-	-
Football Field	SSHS-B2698	SSHS-B2698-SUB-2-4	5/14/2019	2 - 4 ft	855.31	-	-	-	X	X	-	-	-
Football Field	SSHS-B2699	PS-FD-6	5/14/2019	4 - 6 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B2699	SSHS-B2699-SUB-4-6	5/14/2019	4 - 6 ft	856.14	-	-	-	X	-	-	-	-
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	0.17 - 2 ft	854.79	-	-	-	X	X	X	X	-
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	0.17 - 2 ft	854.80	-	-	-	X	X	X	X	-
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	0.17 - 2 ft	855.15	-	-	-	X	X	X	X	-
Football Field	SSHS-B2768	PS-FD-4	5/14/2019	0.17 - 2 ft	855.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B2768	SSHS-B2768-SUB-0.17-2	5/14/2019	0.17 - 2 ft	855.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B2803	SSHS-B2803-SUB-0.17-2	5/14/2019	0.17 - 2 ft	855.69	-	-	-	-	X	-	-	-
Football Field	SSHS-B2607	SSHS-B2607-SUB-4-6	5/15/2019	4 - 6 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B2612	SSHS-B2612-SUB-2-4	5/15/2019	2 - 4 ft	855.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B2613	PS-FD-10	5/15/2019	6 - 8 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B2613	SSHS-B2613-SUB-6-8	5/15/2019	6 - 8 ft	855.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B2614	SSHS-B2614-SUB-2-4	5/15/2019	2 - 4 ft	855.06	-	-	-	X	-	-	-	-
Football Field	SSHS-B2615	SSHS-B2615-SUB-2-4	5/15/2019	2 - 4 ft	855.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/15/2019	4 - 6 ft	855.13	-	-	-	-	-	-	X	-
Football Field	SSHS-B2617	SSHS-B2617-SUB-2-4	5/15/2019	2 - 4 ft	855.78	-	-	-	X	-	-	-	-
Football Field	SSHS-B2621	SSHS-B2621-SUB-2-4	5/15/2019	2 - 4 ft	855.04	-	-	-	X	X	-	-	-
Football Field	SSHS-B2621	SSHS-B2621-SUB-4-6	5/15/2019	4 - 6 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B2621	PS-FD-8	5/15/2019	6 - 8 ft	855.04	-	-	-	-	-	-	X	-
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/15/2019	6 - 8 ft	855.04	-	-	-	-	-	-	X	-
Football Field	SSHS-B2636	SSHS-B2636-SUB-2-4	5/15/2019	2 - 4 ft	855.13	-	-	-	X	-	-	-	-
Football Field	SSHS-B2652	SSHS-B2652-SUB-4-6	5/15/2019	4 - 6 ft	856.40	-	-	-	X	-	-	-	-
Football Field	SSHS-B2686	SSHS-B2686-SUB-0.17-2	5/15/2019	0.17 - 2 ft	855.51	-	-	-	X	-	-	-	-
Football Field	SSHS-B2686	PS-FD-9	5/15/2019	6 - 8 ft	855.51	855.51	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/15/2019	6 - 8 ft	855.51	855.51	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	0.17 - 2 ft	855.87	-	-	-	X	X	X	X	-
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	0.17 - 2 ft	856.23	-	-	-	X	X	X	X	-
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	0.17 - 2 ft	856.92	-	-	-	X	X	X	X	-
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	0.17 - 2 ft	857.01	-	-	-	X	X	X	X	-
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	0.17 - 2 ft	857.02	-	-	-	X	X	X	X	-
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	0.17 - 2 ft	856.77	-	-	-	X	X	X	X	-
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/15/2019	14 - 16 ft	854.80	855.64	0.84	14.84-16.84 ft	-	-	-	X	-
Football Field	SSHS-B2744	SSHS-B2744-SUB-4-6	5/15/2019	4 - 6 ft	855.45	-	-	-	-	X	-	-	-
Football Field	SSHS-B2769	SSHS-B2769-SUB-0.17-2	5/15/2019	0.17 - 2 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2792	SSHS-B2792-SS	5/15/2019	0 - 0.17 ft	856.18	-	-	-	-	X	-	-	-
Football Field	SSHS-B2793	SSHS-B2793-SS	5/15/2019	0 - 0.17 ft	855.44	-	-	-	-	X	-	-	-
Football Field	SSHS-B2794	SSHS-B2794-SS	5/15/2019	0 - 0.17 ft	856.38	-	-	-	-	X	-	-	-
Football Field	SSHS-B2795	SSHS-B2795-SS	5/15/2019	0 - 0.17 ft	855.78	-	-	-	-	X	-	-	-
Football Field	SSHS-B2796	SSHS-B2796-SS	5/15/2019	0 - 0.17 ft	855.92	-	-	-	-	X	-	-	-
Football Field	SSHS-B2797	SSHS-B2797-SS	5/15/2019	0 - 0.17 ft	856.56	-	-	-	-	X	-	-	-
Football Field	SSHS-B2798	SSHS-B2798-SS	5/15/2019	0 - 0.17 ft	856.60	-	-	-	-	X	-	-	-
Football Field	SSHS-B2799	SSHS-B2799-SS	5/15/2019	0 - 0.17 ft	855.91	-	-	-	-	X	-	-	-
Football Field	SSHS-B2800	PS-FD-7	5/15/2019	0 - 0.17 ft	856.14	-	-	-	-	X	-	-	-
Football Field	SSHS-B2800	SSHS-B2800-SS	5/15/2019	0 - 0.17 ft	856.14	-	-	-	-	X	-	-	-
Football Field	SSHS-B2806	SSHS-B2806-SUB-0.17-2	5/15/2019	0.17 - 2 ft	855.10	-	-	-	X	-	-	-	-
Football Field	SSHS-B2619	SSHS-B2619-SUB-6-8	5/16/2019	6 - 8 ft	855.10	855.30	0.20	6.2-8.2 ft	X	-	-	-	-
Football Field	SSHS-B2620	PS-FD-17	5/16/2019	6 - 8 ft	855.02	855.27	0.25	6.25-8.25 ft	X	-	-	-	-
Football Field	SSHS-B2620	SSHS-B2620-SUB-6-8	5/16/2019	6 - 8 ft	855.02	855.27	0.25	6.25-8.25 ft	X	-	-	-	-
Football Field	SSHS-B2625	SSHS-B2625-SUB-10-12	5/16/2019	10 - 12 ft	855.18	-	-	-	-	X	-	-	-
Football Field	SSHS-B2625	SSHS-B2625-SUB-2-4	5/16/2019	2 - 4 ft	855.18	-	-	-	X	X	-	-	-
Football Field	SSHS-B2625	PS-FD-14	5/16/2019	4 - 6 ft	855.18	-	-	-	X	-	-	-	-
Football Field	SSHS-B2625	SSHS-B2625-SUB-4-6	5/16/2019	4 - 6 ft	855.18	-	-	-	X	-	-	-	-
Football Field	SSHS-B2625	SSHS-B2625-SUB-6-8	5/16/2019	6 - 8 ft	855.18	-	-	-	-	X	-	-	-
Football Field	SSHS-B2625	SSHS-B2625-SUB-8-10	5/16/2019	8 - 10 ft	855.18	-	-	-	-	X	-	-	-
Football Field	SSHS-B2648	SSHS-B2648-SUB-0.17-2	5/16/2019	0.17 - 2 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2648	SSHS-B2648-SUB-4-6	5/16/2019	4 - 6 ft	855.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2648	SSHS-B2648-SUB-6-8	5/16/2019	6 - 8 ft	855.86	855.86	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B2668	SSHS-B2668-SUB-6-8	5/16/2019	6 - 8 ft	855.01	-	-	-	X	-	-	-	-
Football Field	SSHS-B2676	SSHS-B2676-SUB-4-6	5/16/2019	4 - 6 ft	856.26	-	-	-	X	-	-	-	-
Football Field	SSHS-B2676	SSHS-B2676-SUB-8-10	5/16/2019	8 - 10 ft	856.26	856.26	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B2695	SSHS-B2695-SUB-2-4	5/16/2019	2 - 4 ft	855.08	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	0.17 - 2 ft	855.37	-	-	-	X	X	X	X	-
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	0.17 - 2 ft	855.37	-	-	-	X	X	X	X	-
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	0.17 - 2 ft	855.37	-	-	-	X	X	X	X	-
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	0.17 - 2 ft	854.96	-	-	-	X	X	X	X	-
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	0.17 - 2 ft	854.89	-	-	-	X	X	X	X	-
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	0.17 - 2 ft	855.48	-	-	-	X	X	X	X	-
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	0.17 - 2 ft	855.48	-	-	-	X	X	X	X	-
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	0.17 - 2 ft	855.30	-	-	-	X	X	X	X	-
Football Field	SSHS-B2718	SSHS-B2718-SUB-10-12	5/16/2019	10 - 12 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2718	PS-FD-13	5/16/2019	2 - 4 ft	855.30	-	-	-	-	X	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2718	SSHS-B2718-SUB-2-4	5/16/2019	2 - 4 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2718	SSHS-B2718-SUB-4-6	5/16/2019	4 - 6 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2718	SSHS-B2718-SUB-6-8	5/16/2019	6 - 8 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2718	SSHS-B2718-SUB-8-10	5/16/2019	8 - 10 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2780	SSHS-B2780-SUB-10-12	5/16/2019	10 - 12 ft	855.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2780	PS-FD-12	5/16/2019	2 - 4 ft	855.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2780	SSHS-B2780-SUB-2-4	5/16/2019	2 - 4 ft	855.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2780	SSHS-B2780-SUB-4-6	5/16/2019	4 - 6 ft	855.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2780	SSHS-B2780-SUB-6-8	5/16/2019	6 - 8 ft	855.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2780	SSHS-B2780-SUB-8-10	5/16/2019	8 - 10 ft	855.70	-	-	-	-	X	-	-	-
Football Field	SSHS-B2802	SSHS-B2802-SUB-0.17-2	5/16/2019	0.17 - 2 ft	855.97	-	-	-	-	X	-	-	-
Football Field	SSHS-B2805	PS-FD-11	5/16/2019	8 - 10 ft	856.47	856.46	-0.01	7.99-9.99 ft	-	X	-	-	-
Football Field	SSHS-B2805	SSHS-B2805-SUB-8-10	5/16/2019	8 - 10 ft	856.47	856.46	-0.01	7.99-9.99 ft	-	X	-	-	-
Football Field	SSHS-B2600	SSHS-B2600-SUB-2-4	5/17/2019	2 - 4 ft	856.75	-	-	-	X	-	-	-	-
Football Field	SSHS-B2602	PS-FD-20	5/17/2019	2 - 4 ft	857.05	-	-	-	X	-	-	-	-
Football Field	SSHS-B2602	SSHS-B2602-SUB-2-4	5/17/2019	2 - 4 ft	857.05	-	-	-	X	-	-	-	-
Football Field	SSHS-B2618	PS-FD-18	5/17/2019	2 - 4 ft	855.12	-	-	-	X	X	-	-	-
Football Field	SSHS-B2618	SSHS-B2618-SUB-2-4	5/17/2019	2 - 4 ft	855.12	-	-	-	X	X	-	-	-
Football Field	SSHS-B2618	SSHS-B2618-SUB-4-6	5/17/2019	4 - 6 ft	855.12	-	-	-	X	X	-	-	-
Football Field	SSHS-B2618	SSHS-B2618-SUB-0.17-2	5/17/2019	0.17 - 2 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2618	SSHS-B2618-SUB-6-8	5/17/2019	6 - 8 ft	855.12	-	-	-	-	X	-	-	-
Football Field	SSHS-B2618	PS-FD-19	5/17/2019	10 - 12 ft	855.12	855.29	0.17	10.17-12.17 ft	-	X	-	-	-
Football Field	SSHS-B2618	SSHS-B2618-SUB-10-12	5/17/2019	10 - 12 ft	855.12	855.29	0.17	10.17-12.17 ft	-	X	-	-	-
Football Field	SSHS-B2618	SSHS-B2618-SUB-8-10	5/17/2019	8 - 10 ft	855.12	855.29	0.17	8.17-10.17 ft	-	X	-	-	-
Football Field	SSHS-B2621	PS-FD-8	5/17/2019	6 - 8 ft	855.04	-	-	-	-	-	X	-	-
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/17/2019	6 - 8 ft	855.04	-	-	-	-	-	X	-	-
Football Field	SSHS-B2626	SSHS-B2626-SUB-4-6	5/17/2019	4 - 6 ft	856.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B2649	SSHS-B2649-SUB-2-4	5/17/2019	2 - 4 ft	856.28	-	-	-	X	X	-	-	-
Football Field	SSHS-B2649	SSHS-B2649-SUB-0.17-2	5/17/2019	0.17 - 2 ft	856.28	-	-	-	-	X	-	-	-
Football Field	SSHS-B2649	SSHS-B2649-SUB-4-6	5/17/2019	4 - 6 ft	856.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B2649	SSHS-B2649-SUB-6-8	5/17/2019	6 - 8 ft	856.28	856.28	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B2667	SSHS-B2667-SUB-4-6	5/17/2019	4 - 6 ft	857.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2675	SSHS-B2675-SUB-4-6	5/17/2019	4 - 6 ft	857.15	-	-	-	X	X	-	-	-
Football Field	SSHS-B2675	SSHS-B2675-SUB-8-10	5/17/2019	8 - 10 ft	857.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B2685	SSHS-B2685-SUB-0.17-2	5/17/2019	0.17 - 2 ft	855.39	-	-	-	X	-	-	-	-
Football Field	SSHS-B2685	SSHS-B2685-SUB-4-6	5/17/2019	4 - 6 ft	855.39	855.54	0.15	4.15-6.15 ft	X	-	-	-	-
Football Field	SSHS-B2700	SSHS-B2700-SUB-8-10	5/17/2019	8 - 10 ft	856.68	856.69	0.01	8.01-10.01 ft	X	X	-	-	-
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	0.17 - 2 ft	856.13	-	-	-	X	X	X	X	-
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	14 - 16 ft	854.80	855.64	0.84	14.84-16.84 ft	-	-	X	-	-
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	8 - 10 ft	856.99	-	-	-	-	X	X	X	-
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	2 - 4 ft	855.18	-	-	-	-	-	X	X	-
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	4 - 6 ft	855.39	-	-	-	-	-	X	X	-
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	2 - 4 ft	855.11	-	-	-	-	-	X	X	-
Football Field	SSHS-B2609	SSHS-B2609-SUB-2-4	5/18/2019	2 - 4 ft	854.74	-	-	-	X	-	-	-	-
Football Field	SSHS-B2627	SSHS-B2627-SUB-2-4	5/18/2019	2 - 4 ft	854.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B2651	SSHS-B2651-SUB-4-6	5/18/2019	4 - 6 ft	856.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B2654	PS-FD-21	5/18/2019	4 - 6 ft	855.51	-	-	-	X	-	-	-	-
Football Field	SSHS-B2654	SSHS-B2654-SUB-4-6	5/18/2019	4 - 6 ft	855.51	-	-	-	X	-	-	-	-
Football Field	SSHS-B2655	SSHS-B2655-SUB-4-6	5/18/2019	4 - 6 ft	855.38	-	-	-	X	-	-	-	-
Football Field	SSHS-B2656	SSHS-B2656-SUB-4-6	5/18/2019	4 - 6 ft	854.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B2657	SSHS-B2657-SUB-4-6	5/18/2019	4 - 6 ft	854.90	-	-	-	X	-	-	-	-
Football Field	SSHS-B2658	SSHS-B2658-SUB-4-6	5/18/2019	4 - 6 ft	854.89	-	-	-	X	-	-	-	-
Football Field	SSHS-B2659	SSHS-B2659-SUB-4-6	5/18/2019	4 - 6 ft	855.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B2671	SSHS-B2671-SUB-6-8	5/18/2019	6 - 8 ft	855.78	855.78	0.00	6-8 ft	X	-	-	-	-
Football Field	SSHS-B2673	SSHS-B2673-SUB-2-4	5/18/2019	2 - 4 ft	855.02	-	-	-	X	X	-	-	-
Football Field	SSHS-B2673	PS-FD-23	5/18/2019	6 - 8 ft	855.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B2673	SSHS-B2673-SUB-6-8	5/18/2019	6 - 8 ft	855.02	-	-	-	X	-	-	-	-
Football Field	SSHS-B2734	PS-FD-22	5/18/2019	0.17 - 2 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2734	SSHS-B2734-SUB-0.17-2	5/18/2019	0.17 - 2 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2734	SSHS-B2734-SUB-2-4	5/18/2019	2 - 4 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2739	SSHS-B2739-SUB-4-6	5/18/2019	4 - 6 ft	855.28	-	-	-	-	X	-	-	-
Football Field	SSHS-B2740	SSHS-B2740-SUB-6-8	5/18/2019	6 - 8 ft	855.30	-	-	-	-	X	-	-	-
Football Field	SSHS-B2760A	SSHS-B2760-SUB-16-18	5/18/2019	16 - 18 ft	856.24	856.24	0.00	16-18 ft	X	-	-	-	-
Football Field	SSHS-B2761	SSHS-B2761-SUB-16-18	5/18/2019	16 - 18 ft	856.14	856.33	0.19	16.19-18.19 ft	X	-	-	-	-
Football Field	SSHS-B2811	SSHS-B2811-SUB-14-16	5/18/2019	14 - 16 ft	856.01	856.01	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B2812	SSHS-B2812-SUB-14-16	5/18/2019	14 - 16 ft	856.10	856.10	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B2813	SSHS-B2813-SUB-14-16	5/18/2019	14 - 16 ft	856.22	856.21	-0.01	13.99-15.99 ft	X	-	-	-	-
Football Field	SSHS-B2814	SSHS-B2814-SUB-14-16	5/18/2019	14 - 16 ft	856.31	856.31	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B2815	SSHS-B2815-SUB-14-16	5/18/2019	14 - 16 ft	856.40	856.40	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B2816	SSHS-B2816-SUB-14-16	5/18/2019	14 - 16 ft	856.38	856.39	0.01	14.01-16.01 ft	X	-	-	-	-
Football Field	SSHS-B2817	SSHS-B2817-SUB-14-16	5/18/2019	14 - 16 ft	856.07	856.07	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B2818	SSHS-B2818-SUB-14-16	5/18/2019	14 - 16 ft	856.15	856.43	0.28	14.28-16.28 ft	X	-	-	-	-
Football Field	SSHS-B2603	SSHS-B2603-SUB-0.17-2	5/19/2019	0.17 - 2 ft	855.24	-	-	-	X	-	-	-	-
Football Field	SSHS-B2604	SSHS-B2604-SUB-0.17-2	5/19/2019	0.17 - 2 ft	855.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B2608	PS-FD-25	5/19/2019	2 - 4 ft	855.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B2608	SSHS-B2608-SUB-2-4	5/19/2019	2 - 4 ft	855.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B2639	SSHS-B2639-SUB-2-4	5/19/2019	2 - 4 ft	855.11	855.38	0.27	2.27-4.27 ft	X	-	-	-	-
Football Field	SSHS-B2642	SSHS-B2642-SUB-2-4	5/19/2019	2 - 4 ft	855.14	855.38	0.24	2.24-4.24 ft	X	-	-	-	-
Football Field	SSHS-B2643	SSHS-B2643-SUB-2-4	5/19/2019	2 - 4 ft	854.91	855.38	0.47	2.47-4.47 ft	X	-	-	-	-
Football Field	SSHS-B2646	SSHS-B2646-SUB-2-4	5/19/2019	2 - 4 ft	854.76	-	-	-	X	-	-	-	-
Football Field	SSHS-B2646	SSHS-B2646-SUB-4-6	5/19/2019	4 - 6 ft	854.76	-	-	-	-	X	-	-	-
Football Field	SSHS-B2653	SSHS-B2653-SUB-4-6	5/19/2019	4 - 6 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B2672	SSHS-B2672-SUB-2-4	5/19/2019	2 - 4 ft	856.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B2672	SSHS-B2672-SUB-6-8	5/19/2019	6 - 8 ft	856.34	-	-	-	X	-	-	-	-
Football Field	SSHS-B2703	SSHS-B2703-SUB-0.17-2	5/19/2019	0.17 - 2 ft	854.92	-	-	-	X	X	-	-	-
Football Field	SSHS-B2703	SSHS-B2703-SUB-2-4	5/19/2019	2 - 4 ft	854.92	-	-	-	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B2754	PS-FD-24	5/19/2019	14 - 16 ft	855.32	855.32	0.00	14-16 ft	X	-	-	-	-
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-14-16	5/19/2019	14 - 16 ft	855.32	855.32	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B2776	SSHS-B2776-SUB-2-4	5/19/2019	2 - 4 ft	855.72	-	-	-	-	X	-	-	-
Football Field	SSHS-B2776	SSHS-B2776-SUB-4-6	5/19/2019	4 - 6 ft	855.72	-	-	-	-	X	-	-	-
Football Field	SSHS-B2777	SSHS-B2777-SUB-2-4	5/19/2019	2 - 4 ft	854.82	-	-	-	-	X	-	-	-
Football Field	SSHS-B2777	SSHS-B2777-SUB-4-6	5/19/2019	4 - 6 ft	854.82	-	-	-	-	X	-	-	-
Football Field	SSHS-B2777	SSHS-B2777-SUB-6-8	5/19/2019	6 - 8 ft	854.82	855.37	0.55	6.55-8.55 ft	-	X	-	-	-
Football Field	SSHS-B2778	SSHS-B2778-SUB-2-4	5/19/2019	2 - 4 ft	855.64	-	-	-	-	X	-	-	-
Football Field	SSHS-B2778	SSHS-B2778-SUB-4-6	5/19/2019	4 - 6 ft	855.64	-	-	-	-	X	-	-	-
Football Field	SSHS-B2778	SSHS-B2778-SUB-6-8	5/19/2019	6 - 8 ft	855.64	855.65	0.01	6.01-8.01 ft	-	X	-	-	-
Football Field	SSHS-B2779	SSHS-B2779-SUB-2-4	5/19/2019	2 - 4 ft	855.06	-	-	-	-	X	-	-	-
Football Field	SSHS-B2779	SSHS-B2779-SUB-4-6	5/19/2019	4 - 6 ft	855.06	-	-	-	-	X	-	-	-
Football Field	SSHS-B2779	SSHS-B2779-SUB-6-8	5/19/2019	6 - 8 ft	855.06	855.39	0.33	6.33-8.33 ft	-	X	-	-	-
Football Field	SSHS-B2783	SSHS-B2783-SUB-4-6	5/19/2019	4 - 6 ft	854.95	-	-	-	-	X	-	-	-
Football Field	SSHS-B2784	SSHS-B2784-SUB-4-6	5/19/2019	4 - 6 ft	855.04	-	-	-	-	X	-	-	-
Football Field	SSHS-B2804	SSHS-B2804-SUB-4-6	5/19/2019	4 - 6 ft	855.74	-	-	-	-	X	-	-	-
Football Field	SSHS-B2610	SSHS-B2610-SUB-2-4	5/20/2019	2 - 4 ft	857.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B2611	SSHS-B2611-SUB-2-4	5/20/2019	2 - 4 ft	857.20	-	-	-	X	-	-	-	-
Football Field	SSHS-B2632	SSHS-B2632-SUB-12-14	5/20/2019	12 - 14 ft	854.95	-	-	-	X	-	-	-	-
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	14 - 16 ft	854.95	855.25	0.30	14.3-16.3 ft	-	-	X	X	-
Football Field	SSHS-B2663	PS-FD-28	5/20/2019	4 - 6 ft	857.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B2663	SSHS-B2663-SUB-4-6	5/20/2019	4 - 6 ft	857.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B2664	SSHS-B2664-SUB-4-6	5/20/2019	4 - 6 ft	857.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B2665	SSHS-B2665-SUB-4-6	5/20/2019	4 - 6 ft	857.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B2666	SSHS-B2666-SUB-4-6	5/20/2019	4 - 6 ft	857.28	-	-	-	X	-	-	-	-
Football Field	SSHS-B2691	SSHS-B2691-SUB-2-4	5/20/2019	2 - 4 ft	857.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B2692	PS-FD-27	5/20/2019	2 - 4 ft	857.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B2692	SSHS-B2692-SUB-2-4	5/20/2019	2 - 4 ft	857.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	0.17 - 2 ft	857.04	-	-	-	X	X	X	X	-
Football Field	SSHS-B2693	SSHS-B2693-SUB-2-4	5/20/2019	2 - 4 ft	857.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	0.17 - 2 ft	855.26	-	-	-	X	X	X	X	-
Football Field	SSHS-B2709	SSHS-B2709-SUB-4-6	5/20/2019	4 - 6 ft	855.26	855.34	0.08	4.08-6.08 ft	-	X	-	-	-
Football Field	SSHS-B2782	SSHS-B2782-SUB-4-6	5/20/2019	4 - 6 ft	855.29	-	-	-	-	X	-	-	-
Football Field	SSHS-B2785	SSHS-B2785-SUB-6-8	5/20/2019	6 - 8 ft	856.43	-	-	-	-	X	-	-	-
Football Field	SSHS-B2786	SSHS-B2786-SUB-6-8	5/20/2019	6 - 8 ft	856.97	856.98	0.01	6.01-8.01 ft	-	X	-	-	-
Football Field	SSHS-B2787	SSHS-B2787-SUB-6-8	5/20/2019	6 - 8 ft	857.02	857.01	-0.01	5.99-7.99 ft	-	X	-	-	-
Football Field	SSHS-B2788	PS-FD-26	5/20/2019	6 - 8 ft	856.74	856.74	0.00	6-8 ft	-	X	-	-	-
Football Field	SSHS-B2788	SSHS-B2788-SUB-6-8	5/20/2019	6 - 8 ft	856.74	856.74	0.00	6-8 ft	-	X	-	-	-
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	2 - 4 ft	855.10	855.29	0.19	2.19-4.19 ft	-	-	X	X	-
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/21/2019	4 - 6 ft	855.13	-	-	-	-	-	X	-	-
Football Field	SSHS-B2645	SSHS-B2645-SUB-2-4	5/21/2019	2 - 4 ft	855.03	-	-	-	X	-	-	-	-
Football Field	SSHS-B2677	SSHS-B2677-SUB-0.17-2	5/21/2019	0.17 - 2 ft	855.87	-	-	-	X	-	-	-	-
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	6 - 8 ft	855.51	855.51	0.00	6-8 ft	-	-	X	-	-
Football Field	SSHS-B2690	PS-FD-29	5/21/2019	0.17 - 2 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2690	SSHS-B2690-SUB-0.17-2	5/21/2019	0.17 - 2 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	0.17 - 2 ft	855.05	-	-	-	X	X	X	X	-
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	0.17 - 2 ft	855.05	-	-	-	X	X	X	X	-
Football Field	SSHS-B2708	SSHS-B2708-SUB-6-8	5/21/2019	6 - 8 ft	855.05	-	-	-	-	X	-	-	-
Football Field	SSHS-B2728	SSHS-B2728-SUB-0.17-2	5/21/2019	0.17 - 2 ft	856.47	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2729	SSHS-B2729-SUB-0.17-2	5/21/2019	0.17 - 2 ft	856.49	-	-	-	X	-	-	-	-
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	4 - 6 ft	856.49	-	-	-	-	-	X	X	-
Football Field	SSHS-B2730	SSHS-B2730-SUB-0.17-2	5/21/2019	0.17 - 2 ft	856.08	-	-	-	X	-	-	-	-
Football Field	SSHS-B2731	PS-FD-30	5/21/2019	0.17 - 2 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B2731	SSHS-B2731-SUB-0.17-2	5/21/2019	0.17 - 2 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B2732	SSHS-B2732-SUB-0.17-2	5/21/2019	0.17 - 2 ft	855.83	-	-	-	X	-	-	-	-
Football Field	SSHS-B2789	SSHS-B2789-SUB-6-8	5/21/2019	6 - 8 ft	855.23	855.57	0.34	6.34-8.34 ft	-	X	-	-	-
Football Field	SSHS-B2790	SSHS-B2790-SUB-6-8	5/21/2019	6 - 8 ft	855.30	855.52	0.22	6.22-8.22 ft	-	X	-	-	-
Football Field	SSHS-B2801	SSHS-B2801-SUB-0.17-2	5/21/2019	0.17 - 2 ft	856.07	-	-	-	-	X	-	-	-
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	4 - 6 ft	854.92	855.51	0.59	4.59-6.59 ft	-	-	X	X	-
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	6 - 8 ft	854.92	855.51	0.59	6.59-8.59 ft	-	X	X	X	-
Football Field	SSHS-B2606	PS-FD-34	5/22/2019	0.17 - 2 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B2606	SSHS-B2606-SUB-0.17-2	5/22/2019	0.17 - 2 ft	855.71	-	-	-	X	-	-	-	-
Football Field	SSHS-B2644	SSHS-B2644-SUB-2-4	5/22/2019	2 - 4 ft	856.70	-	-	-	X	-	-	-	-
Football Field	SSHS-B2689	SSHS-B2689-SUB-0.17-2	5/22/2019	0.17 - 2 ft	855.78	-	-	-	X	-	-	-	-
Football Field	SSHS-B2726	PS-FD-32	5/22/2019	0.17 - 2 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2726	SSHS-B2726-SUB-0.17-2	5/22/2019	0.17 - 2 ft	856.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2727	PS-FD-33	5/22/2019	0.17 - 2 ft	856.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B2727	SSHS-B2727-SUB-0.17-2	5/22/2019	0.17 - 2 ft	856.45	-	-	-	X	-	-	-	-
Football Field	SSHS-B2603A	SSHS-B2603A-SS	6/12/2019	0 - 0.17 ft	855.23	-	-	-	X	-	-	-	-
Football Field	SSHS-B2624A	PS-FD-1	6/12/2019	0 - 0.17 ft	855.29	-	-	-	X	-	-	X	-
Football Field	SSHS-B2624A	SSHS-B2624A-SS	6/12/2019	0 - 0.17 ft	855.29	-	-	-	X	-	-	-	-
Football Field	SSHS-B2703A	SSHS-B2703A-SS	6/12/2019	0 - 0.17 ft	855.18	-	-	-	X	-	-	-	-
Football Field	SSHS-B2717A	SSHS-B2717A-SS	6/12/2019	0 - 0.17 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-GS-01	SSHS-GS-01	8/23/2019	0.5 - 0.5 ft	855.29	-	-	-	X	X	-	-	-
Football Field	SSHS-GS-02	SSHS-GS-02	8/23/2019	0.5 - 0.5 ft	855.18	-	-	-	X	X	-	-	-
Football Field	SSHS-GS-03	SSHS-GS-03	8/23/2019	0.5 - 0.5 ft	855.06	-	-	-	X	X	-	-	-
Football Field	SSHS-GS-04	SSHS-GS-04	8/23/2019	0.5 - 0.5 ft	855.13	-	-	-	X	X	-	-	-
Football Field	SSHS-GS-05	SSHS-GS-05	8/23/2019	0.5 - 0.5 ft	855.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	0 - 0.17 ft	852.58	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-10-12	8/26/2019	10 - 12 ft	852.37	854.67	2.30	12.3-14.3 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	12 - 14 ft	852.37	854.67	2.30	14.3-16.3 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-2-4	8/26/2019	2 - 4 ft	852.37	854.67	2.30	4.3-6.3 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-4-6	8/26/2019	4 - 6 ft	852.37	854.67	2.30	6.3-8.3 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-6-8	8/26/2019	6 - 8 ft	852.37	854.67	2.30	8.3-10.3 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-8-10	8/26/2019	8 - 10 ft	852.37	854.67	2.30	10.3-12.3 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	0 - 0.17 ft	854.09	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	0 - 0.17 ft	853.86	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-2-4	8/26/2019	2 - 4 ft	853.71	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-DUP5	8/26/2019	2 - 4 ft	853.71	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-4-6	8/26/2019	4 - 6 ft	853.71	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-6-8	8/26/2019	6 - 8 ft	853.71	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	8/26/2019	0.17 - 2 ft	853.71	-	-	-	X	-	X	X	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-10-12	8/26/2019	10 - 12 ft	853.71	855.73	2.02	12.02-14.02 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-12-14	8/26/2019	12 - 14 ft	853.71	855.73	2.02	14.02-16.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-8-10	8/26/2019	8 - 10 ft	853.71	855.73	2.02	10.02-12.02 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	14 - 16 ft	853.71	855.73	2.02	16.02-18.02 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	12 - 14 ft	853.71	855.73	2.02	14.02-16.02 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	0 - 0.17 ft	853.76	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-2-4	8/26/2019	2 - 4 ft	853.76	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-4-6	8/26/2019	4 - 6 ft	853.76	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	0.17 - 2 ft	853.76	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-10-12	8/26/2019	10 - 12 ft	853.76	855.66	1.90	11.9-13.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-6-8	8/26/2019	6 - 8 ft	853.76	855.66	1.90	7.9-9.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-8-10	8/26/2019	8 - 10 ft	853.76	855.66	1.90	9.9-11.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	12 - 14 ft	853.76	855.66	1.90	13.9-15.9 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.08	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.17	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-10-12	8/26/2019	10 - 12 ft	855.10	856.53	1.43	11.43-13.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-12-14	8/26/2019	12 - 14 ft	855.10	856.53	1.43	13.43-15.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-4-6	8/26/2019	4 - 6 ft	855.10	856.53	1.43	5.43-7.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-6-8	8/26/2019	6 - 8 ft	855.10	856.53	1.43	7.43-9.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-8-10	8/26/2019	8 - 10 ft	855.10	856.53	1.43	9.43-11.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	14 - 16 ft	855.10	856.53	1.43	15.43-17.43 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.10	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-2-4	8/26/2019	2 - 4 ft	855.10	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	0.17 - 2 ft	855.10	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-10-12	8/26/2019	10 - 12 ft	854.81	856.27	1.46	11.46-13.46 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-6-8	8/26/2019	6 - 8 ft	854.81	856.27	1.46	7.46-9.46 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-8-10	8/26/2019	8 - 10 ft	854.81	856.27	1.46	9.46-11.46 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	12 - 14 ft	854.81	856.27	1.46	13.46-15.46 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	0 - 0.17 ft	854.81	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-2-4	8/26/2019	2 - 4 ft	854.81	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-4-6	8/26/2019	4 - 6 ft	854.81	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	0.17 - 2 ft	854.81	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.22	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.08	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-10-12	8/26/2019	10 - 12 ft	856.17	857.50	1.33	11.33-13.33 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-12-14	8/26/2019	12 - 14 ft	856.17	857.50	1.33	13.33-15.33 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-4-6	8/26/2019	4 - 6 ft	856.17	857.50	1.33	5.33-7.33 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-6-8	8/26/2019	6 - 8 ft	856.17	857.50	1.33	7.33-9.33 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-8-10	8/26/2019	8 - 10 ft	856.17	857.50	1.33	9.33-11.33 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	14 - 16 ft	856.17	857.50	1.33	15.33-17.33 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.17	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-2-4	8/26/2019	2 - 4 ft	856.17	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	0.17 - 2 ft	856.17	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-4-6	8/26/2019	4 - 6 ft	855.60	856.84	1.24	5.24-7.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-6-8	8/26/2019	6 - 8 ft	855.60	856.84	1.24	7.24-9.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-8-10	8/26/2019	8 - 10 ft	855.60	856.84	1.24	9.24-11.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	10 - 12 ft	855.60	856.84	1.24	11.24-13.24 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.60	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-2-4	8/26/2019	2 - 4 ft	855.60	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	0.17 - 2 ft	855.60	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	0 - 0.17 ft	857.02	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.95	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-10-12	8/26/2019	10 - 12 ft	856.77	857.84	1.07	11.07-13.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	12 - 14 ft	856.77	857.84	1.07	13.07-15.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-6-8	8/26/2019	6 - 8 ft	856.77	857.84	1.07	7.07-9.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-8-10	8/26/2019	8 - 10 ft	856.77	857.84	1.07	9.07-11.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-2-4	8/26/2019	2 - 4 ft	856.77	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.77	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-4-6	8/26/2019	4 - 6 ft	856.77	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	0.17 - 2 ft	856.77	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-10-12	8/26/2019	10 - 12 ft	856.77	857.30	0.53	10.53-12.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	12 - 14 ft	856.77	857.30	0.53	12.53-14.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-4-6	8/26/2019	4 - 6 ft	856.77	857.30	0.53	4.53-6.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-6-8	8/26/2019	6 - 8 ft	856.77	857.30	0.53	6.53-8.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-8-10	8/26/2019	8 - 10 ft	856.77	857.30	0.53	8.53-10.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.77	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-2-4	8/26/2019	2 - 4 ft	856.77	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	0.17 - 2 ft	856.77	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.86	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.92	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	12 - 14 ft	856.86	857.85	0.99	12.99-14.99 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.86	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-10-12	8/26/2019	10 - 12 ft	856.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-2-4	8/26/2019	2 - 4 ft	856.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-4-6	8/26/2019	4 - 6 ft	856.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-6-8	8/26/2019	6 - 8 ft	856.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-8-10	8/26/2019	8 - 10 ft	856.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	0.17 - 2 ft	856.86	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-10-12	8/26/2019	10 - 12 ft	856.70	857.12	0.42	10.42-12.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-2-4	8/26/2019	2 - 4 ft	856.70	857.12	0.42	2.42-4.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-4-6	8/26/2019	4 - 6 ft	856.70	857.12	0.42	4.42-6.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-6-8	8/26/2019	6 - 8 ft	856.70	857.12	0.42	6.42-8.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-8-10	8/26/2019	8 - 10 ft	856.70	857.12	0.42	8.42-10.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	12 - 14 ft	856.70	857.12	0.42	12.42-14.42 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.86	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.19	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-10-12	8/26/2019	10 - 12 ft	855.97	857.05	1.08	11.08-13.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-4-6	8/26/2019	4 - 6 ft	855.97	857.05	1.08	5.08-7.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-6-8	8/26/2019	6 - 8 ft	855.97	857.05	1.08	7.08-9.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-8-10	8/26/2019	8 - 10 ft	855.97	857.05	1.08	9.08-11.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	12 - 14 ft	855.97	857.05	1.08	13.08-15.08 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	0 - 0.17 ft	855.97	-	-	-	X	X	X	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-2-4	8/26/2019	2 - 4 ft	855.97	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	0.17 - 2 ft	855.97	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-10-12	8/26/2019	10 - 12 ft	856.40	856.53	0.13	10.13-12.13 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-2-4	8/26/2019	2 - 4 ft	856.40	856.53	0.13	2.13-4.13 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-4-6	8/26/2019	4 - 6 ft	856.40	856.53	0.13	4.13-6.13 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-6-8	8/26/2019	6 - 8 ft	856.40	856.53	0.13	6.13-8.13 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-8-10	8/26/2019	8 - 10 ft	856.40	856.53	0.13	8.13-10.13 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	12 - 14 ft	856.40	856.53	0.13	12.13-14.13 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0-0.17	8/26/2019	0 - 0.17 ft	856.40	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	0.17 - 2 ft	856.40	-	-	-	-	X	-	X	-
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	0 - 0.17 ft	852.36	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-10-12	8/27/2019	10 - 12 ft	852.36	852.39	0.03	10.03-12.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	12 - 14 ft	852.36	852.39	0.03	12.03-14.03 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-2-4	8/27/2019	2 - 4 ft	852.36	852.39	0.03	2.03-4.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-4-6	8/27/2019	4 - 6 ft	852.36	852.39	0.03	4.03-6.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-6-8	8/27/2019	6 - 8 ft	852.36	852.39	0.03	6.03-8.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-8-10	8/27/2019	8 - 10 ft	852.36	852.39	0.03	8.03-10.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	0.17 - 2 ft	852.58	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-10-12	8/27/2019	10 - 12 ft	852.58	854.74	2.16	12.16-14.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	12 - 14 ft	852.58	854.74	2.16	14.16-16.16 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-2-4	8/27/2019	2 - 4 ft	852.58	854.74	2.16	4.16-6.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-4-6	8/27/2019	4 - 6 ft	852.58	854.74	2.16	6.16-8.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-6-8	8/27/2019	6 - 8 ft	852.58	854.74	2.16	8.16-10.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-8-10	8/27/2019	8 - 10 ft	852.58	854.74	2.16	10.16-12.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	0 - 0.17 ft	853.78	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	0 - 0.17 ft	853.82	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	0.17 - 2 ft	853.82	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-10-12	8/27/2019	10 - 12 ft	853.82	854.59	0.77	10.77-12.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-2-4	8/27/2019	2 - 4 ft	853.82	854.59	0.77	2.77-4.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-4-6	8/27/2019	4 - 6 ft	853.82	854.59	0.77	4.77-6.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-6-8	8/27/2019	6 - 8 ft	853.82	854.59	0.77	6.77-8.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-8-10	8/27/2019	8 - 10 ft	853.82	854.59	0.77	8.77-10.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	12 - 14 ft	853.82	854.59	0.77	12.77-14.77 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-2-4	8/27/2019	2 - 4 ft	854.09	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-4-6	8/27/2019	4 - 6 ft	854.09	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	0.17 - 2 ft	854.09	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-10-12	8/27/2019	10 - 12 ft	854.09	855.31	1.22	11.22-13.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-6-8	8/27/2019	6 - 8 ft	854.09	855.31	1.22	7.22-9.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-8-10	8/27/2019	8 - 10 ft	854.09	855.31	1.22	9.22-11.22 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	12 - 14 ft	854.09	855.31	1.22	13.22-15.22 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-2-4	8/27/2019	2 - 4 ft	853.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-4-6	8/27/2019	4 - 6 ft	853.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	0.17 - 2 ft	853.86	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-10-12	8/27/2019	10 - 12 ft	853.86	855.74	1.88	11.88-13.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-6-8	8/27/2019	6 - 8 ft	853.86	855.74	1.88	7.88-9.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-8-10	8/27/2019	8 - 10 ft	853.86	855.74	1.88	9.88-11.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	12 - 14 ft	853.86	855.74	1.88	13.88-15.88 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	0 - 0.17 ft	854.60	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	0 - 0.17 ft	855.22	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	0.17 - 2 ft	855.08	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-10-12	8/27/2019	10 - 12 ft	855.08	855.61	0.53	10.53-12.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-2-4	8/27/2019	2 - 4 ft	855.08	855.61	0.53	2.53-4.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-4-6	8/27/2019	4 - 6 ft	855.08	855.61	0.53	4.53-6.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-6-8	8/27/2019	6 - 8 ft	855.08	855.61	0.53	6.53-8.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-8-10	8/27/2019	8 - 10 ft	855.08	855.61	0.53	8.53-10.53 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	12 - 14 ft	855.08	855.61	0.53	12.53-14.53 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-10-12	8/27/2019	10 - 12 ft	855.25	856.15	0.90	10.9-12.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-2-4	8/27/2019	2 - 4 ft	855.25	856.15	0.90	2.9-4.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-4-6	8/27/2019	4 - 6 ft	855.25	856.15	0.90	4.9-6.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-6-8	8/27/2019	6 - 8 ft	855.25	856.15	0.90	6.9-8.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-8-10	8/27/2019	8 - 10 ft	855.25	856.15	0.90	8.9-10.9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	12 - 14 ft	855.25	856.15	0.90	12.9-14.9 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-2-4	8/27/2019	2 - 4 ft	855.17	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	0.17 - 2 ft	855.17	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-10-12	8/27/2019	10 - 12 ft	855.17	856.58	1.41	11.41-13.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-4-6	8/27/2019	4 - 6 ft	855.17	856.58	1.41	5.41-7.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-6-8	8/27/2019	6 - 8 ft	855.17	856.58	1.41	7.41-9.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-8-10	8/27/2019	8 - 10 ft	855.17	856.58	1.41	9.41-11.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	12 - 14 ft	855.17	856.58	1.41	13.41-15.41 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	0 - 0.17 ft	855.78	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	0 - 0.17 ft	856.00	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	0 - 0.17 ft	856.03	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-4-6	8/27/2019	4 - 6 ft	856.22	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-10-12	8/27/2019	10 - 12 ft	856.22	856.03	-0.19	9.81-11.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.22	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	2 - 4 ft	856.22	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-6-8	8/27/2019	6 - 8 ft	856.22	856.03	-0.19	5.81-7.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-8-10	8/27/2019	8 - 10 ft	856.22	856.03	-0.19	7.81-9.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	12 - 14 ft	856.22	856.03	-0.19	11.81-13.81 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-2-4	8/27/2019	2 - 4 ft	856.24	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-4-6	8/27/2019	4 - 6 ft	856.24	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-10-12	8/27/2019	10 - 12 ft	856.24	856.75	0.51	10.51-12.51 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.24	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-6-8	8/27/2019	6 - 8 ft	856.24	856.75	0.51	6.51-8.51 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-8-10	8/27/2019	8 - 10 ft	856.24	856.75	0.51	8.51-10.51 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	12 - 14 ft	856.24	856.75	0.51	12.51-14.51 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-2-4	8/27/2019	2 - 4 ft	856.08	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-4-6	8/27/2019	4 - 6 ft	856.08	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-10-12	8/27/2019	10 - 12 ft	856.08	857.32	1.24	11.24-13.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.08	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-6-8	8/27/2019	6 - 8 ft	856.08	857.32	1.24	7.24-9.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-8-10	8/27/2019	8 - 10 ft	856.08	857.32	1.24	9.24-11.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	12 - 14 ft	856.08	857.32	1.24	13.24-15.24 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	0 - 0.17 ft	856.47	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	0 - 0.17 ft	856.71	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	0 - 0.17 ft	856.96	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-10-12	8/27/2019	10 - 12 ft	857.02	856.09	-0.93	9.07-11.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-6-8	8/27/2019	6 - 8 ft	857.02	856.09	-0.93	5.07-7.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-8-10	8/27/2019	8 - 10 ft	857.02	856.09	-0.93	7.07-9.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	12 - 14 ft	857.02	856.09	-0.93	11.07-13.07 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-2-4	8/27/2019	2 - 4 ft	857.02	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-4-6	8/27/2019	4 - 6 ft	857.02	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	0.17 - 2 ft	857.02	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-4-6	8/27/2019	4 - 6 ft	856.91	856.86	-0.05	3.95-5.95 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-6-8	8/27/2019	6 - 8 ft	856.91	856.86	-0.05	5.95-7.95 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-8-10	8/27/2019	8 - 10 ft	856.91	856.86	-0.05	7.95-9.95 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	10 - 12 ft	856.91	856.86	-0.05	9.95-11.95 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-2-4	8/27/2019	2 - 4 ft	856.91	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.91	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-10-12	8/27/2019	10 - 12 ft	856.95	857.80	0.85	10.85-12.85 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-8-10	8/27/2019	8 - 10 ft	856.95	857.80	0.85	8.85-10.85 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	12 - 14 ft	856.95	857.80	0.85	12.85-14.85 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-2-4	8/27/2019	2 - 4 ft	856.95	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-4-6	8/27/2019	4 - 6 ft	856.95	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-6-8	8/27/2019	6 - 8 ft	856.95	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.95	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	0 - 0.17 ft	857.14	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-4-6	8/27/2019	4 - 6 ft	857.18	856.02	-1.16	2.84-4.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-6-8	8/27/2019	6 - 8 ft	857.18	856.02	-1.16	4.84-6.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-8-10	8/27/2019	8 - 10 ft	857.18	856.02	-1.16	6.84-8.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	10 - 12 ft	857.18	856.02	-1.16	8.84-10.84 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-2-4	8/27/2019	2 - 4 ft	857.18	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	0.17 - 2 ft	857.18	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	0 - 0.17 ft	857.18	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-10-12	8/27/2019	10 - 12 ft	856.99	856.91	-0.08	9.92-11.92 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	12 - 14 ft	856.99	856.91	-0.08	11.92-13.92 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-2-4	8/27/2019	2 - 4 ft	856.99	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-4-6	8/27/2019	4 - 6 ft	856.99	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-6-8	8/27/2019	6 - 8 ft	856.99	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-8-10	8/27/2019	8 - 10 ft	856.99	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-10-12	8/27/2019	10 - 12 ft	856.92	857.74	0.82	10.82-12.82 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-8-10	8/27/2019	8 - 10 ft	856.92	857.74	0.82	8.82-10.82 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	12 - 14 ft	856.92	857.74	0.82	12.82-14.82 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-2-4	8/27/2019	2 - 4 ft	856.92	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-4-6	8/27/2019	4 - 6 ft	856.92	-	-	-	X	X	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-6-8	8/27/2019	6 - 8 ft	856.92	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.92	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	0 - 0.17 ft	857.12	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-10-12	8/27/2019	10 - 12 ft	855.86	856.29	0.43	10.43-12.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-12-14	8/27/2019	12 - 14 ft	855.86	856.29	0.43	12.43-14.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	14 - 16 ft	855.86	856.29	0.43	14.43-16.43 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-4-6	8/27/2019	4 - 6 ft	855.86	856.29	0.43	4.43-6.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-6-8	8/27/2019	6 - 8 ft	855.86	856.29	0.43	6.43-8.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-8-10	8/27/2019	8 - 10 ft	855.86	856.29	0.43	8.43-10.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	0.17 - 2 ft	855.86	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-2-4	8/27/2019	2 - 4 ft	855.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-10-12	8/27/2019	10 - 12 ft	856.19	856.93	0.74	10.74-12.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-6-8	8/27/2019	6 - 8 ft	856.19	856.93	0.74	6.74-8.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-8-10	8/27/2019	8 - 10 ft	856.19	856.93	0.74	8.74-10.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	12 - 14 ft	856.19	856.93	0.74	12.74-14.74 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-2-4	8/27/2019	2 - 4 ft	856.19	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-4-6	8/27/2019	4 - 6 ft	856.19	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	0.17 - 2 ft	856.19	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	0 - 0.17 ft	853.35	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	12 - 14 ft	853.51	-	-	-	X	X	-	X	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	0 - 0.17 ft	853.51	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-10-12	8/28/2019	10 - 12 ft	853.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-2-4	8/28/2019	2 - 4 ft	853.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-4-6	8/28/2019	4 - 6 ft	853.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-6-8	8/28/2019	6 - 8 ft	853.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-8-10	8/28/2019	8 - 10 ft	853.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	0.17 - 2 ft	853.51	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-2-4	8/28/2019	2 - 4 ft	853.78	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-4-6	8/28/2019	4 - 6 ft	853.78	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	0.17 - 2 ft	853.78	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-6-8	8/28/2019	6 - 8 ft	853.78	853.15	-0.63	5.37-7.37 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-8-10	8/28/2019	8 - 10 ft	853.78	853.15	-0.63	7.37-9.37 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	0 - 0.17 ft	854.13	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	12 - 14 ft	854.13	-	-	-	X	X	-	X	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-10-12	8/28/2019	10 - 12 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-2-4	8/28/2019	2 - 4 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-4-6	8/28/2019	4 - 6 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-6-8	8/28/2019	6 - 8 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-8-10	8/28/2019	8 - 10 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	12 - 14 ft	854.13	-	-	-	X	X	-	X	-
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-2-4	8/28/2019	2 - 4 ft	854.97	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-10-12	8/28/2019	10 - 12 ft	854.97	853.59	-1.38	8.62-10.62 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-6-8	8/28/2019	6 - 8 ft	854.97	853.59	-1.38	4.62-6.62 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-8-10	8/28/2019	8 - 10 ft	854.97	853.59	-1.38	6.62-8.62 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	12 - 14 ft	854.97	853.59	-1.38	10.62-12.62 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	0.17 - 2 ft	855.22	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-10-12	8/28/2019	10 - 12 ft	855.22	855.02	-0.20	9.8-11.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-2-4	8/28/2019	2 - 4 ft	855.22	855.02	-0.20	1.8-3.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-4-6	8/28/2019	4 - 6 ft	855.22	855.02	-0.20	3.8-5.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-6-8	8/28/2019	6 - 8 ft	855.22	855.02	-0.20	5.8-7.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-8-10	8/28/2019	8 - 10 ft	855.22	855.02	-0.20	7.8-9.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	12 - 14 ft	855.22	855.02	-0.20	11.8-13.8 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	0 - 0.17 ft	855.10	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	0 - 0.17 ft	855.17	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	0 - 0.17 ft	855.23	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-2-4	8/28/2019	2 - 4 ft	855.23	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-4-6	8/28/2019	4 - 6 ft	855.23	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-6-8	8/28/2019	6 - 8 ft	855.23	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	0.17 - 2 ft	855.23	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-8-10	8/28/2019	8 - 10 ft	855.23	857.40	2.17	10.17-12.17 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	0.17 - 2 ft	855.78	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-10-12	8/28/2019	10 - 12 ft	855.78	856.62	0.84	10.84-12.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-2-4	8/28/2019	2 - 4 ft	855.78	856.62	0.84	2.84-4.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-4-6	8/28/2019	4 - 6 ft	855.78	856.62	0.84	4.84-6.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-6-8	8/28/2019	6 - 8 ft	855.78	856.62	0.84	6.84-8.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-8-10	8/28/2019	8 - 10 ft	855.78	856.62	0.84	8.84-10.84 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	12 - 14 ft	855.78	856.62	0.84	12.84-14.84 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-2-4	8/28/2019	2 - 4 ft	856.00	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.00	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-10-12	8/28/2019	10 - 12 ft	856.00	854.20	-1.80	8.2-10.2 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-4-6	8/28/2019	4 - 6 ft	856.00	854.20	-1.80	2.2-4.2 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-6-8	8/28/2019	6 - 8 ft	856.00	854.20	-1.80	4.2-6.2 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-8-10	8/28/2019	8 - 10 ft	856.00	854.20	-1.80	6.2-8.2 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	12 - 14 ft	856.00	854.20	-1.80	10.2-12.2 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-2-4	8/28/2019	2 - 4 ft	856.03	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.03	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-10-12	8/28/2019	10 - 12 ft	856.03	855.07	-0.96	9.04-11.04 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-4-6	8/28/2019	4 - 6 ft	856.03	855.07	-0.96	3.04-5.04 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-6-8	8/28/2019	6 - 8 ft	856.03	855.07	-0.96	5.04-7.04 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-8-10	8/28/2019	8 - 10 ft	856.03	855.07	-0.96	7.04-9.04 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	12 - 14 ft	856.03	855.07	-0.96	11.04-13.04 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	0 - 0.17 ft	856.20	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	0 - 0.17 ft	855.88	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	0 - 0.17 ft	856.09	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.09	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-10-12	8/28/2019	10 - 12 ft	856.09	857.58	1.49	11.49-13.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	12 - 14 ft	856.09	857.58	1.49	13.49-15.49 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-2-4	8/28/2019	2 - 4 ft	856.09	857.58	1.49	3.49-5.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-4-6	8/28/2019	4 - 6 ft	856.09	857.58	1.49	5.49-7.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-6-8	8/28/2019	6 - 8 ft	856.09	857.58	1.49	7.49-9.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-8-10	8/28/2019	8 - 10 ft	856.09	857.58	1.49	9.49-11.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.47	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-10-12	8/28/2019	10 - 12 ft	856.47	856.55	0.08	10.08-12.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	12 - 14 ft	856.47	856.55	0.08	12.08-14.08 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-2-4	8/28/2019	2 - 4 ft	856.47	856.55	0.08	2.08-4.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-4-6	8/28/2019	4 - 6 ft	856.47	856.55	0.08	4.08-6.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-6-8	8/28/2019	6 - 8 ft	856.47	856.55	0.08	6.08-8.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-8-10	8/28/2019	8 - 10 ft	856.47	856.55	0.08	8.08-10.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.71	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-2-4	8/28/2019	2 - 4 ft	856.71	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-10-12	8/28/2019	10 - 12 ft	856.71	854.42	-2.29	7.71-9.71 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	12 - 14 ft	856.71	854.42	-2.29	9.71-11.71 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-4-6	8/28/2019	4 - 6 ft	856.71	854.42	-2.29	1.71-3.71 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-6-8	8/28/2019	6 - 8 ft	856.71	854.42	-2.29	3.71-5.71 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-8-10	8/28/2019	8 - 10 ft	856.71	854.42	-2.29	5.71-7.71 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-2-4	8/28/2019	2 - 4 ft	856.96	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.96	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-10-12	8/28/2019	10 - 12 ft	856.96	855.38	-1.58	8.42-10.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-12-14	8/28/2019	12 - 14 ft	856.96	855.38	-1.58	10.42-12.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-4-6	8/28/2019	4 - 6 ft	856.96	855.38	-1.58	2.42-4.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-6-8	8/28/2019	6 - 8 ft	856.96	855.38	-1.58	4.42-6.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-8-10	8/28/2019	8 - 10 ft	856.96	855.38	-1.58	6.42-8.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	14 - 16 ft	856.96	855.38	-1.58	12.42-14.42 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-10-12	8/28/2019	10 - 12 ft	856.51	857.05	0.54	10.54-12.54 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	12 - 14 ft	856.51	857.05	0.54	12.54-14.54 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-4-6	8/28/2019	4 - 6 ft	856.51	857.05	0.54	4.54-6.54 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-6-8	8/28/2019	6 - 8 ft	856.51	857.05	0.54	6.54-8.54 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-8-10	8/28/2019	8 - 10 ft	856.51	857.05	0.54	8.54-10.54 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-2-4	8/28/2019	2 - 4 ft	856.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-10-12	8/28/2019	10 - 12 ft	856.76	856.63	-0.13	9.87-11.87 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	12 - 14 ft	856.76	856.63	-0.13	11.87-13.87 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-2-4	8/28/2019	2 - 4 ft	856.76	856.63	-0.13	1.87-3.87 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-4-6	8/28/2019	4 - 6 ft	856.76	856.63	-0.13	3.87-5.87 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-6-8	8/28/2019	6 - 8 ft	856.76	856.63	-0.13	5.87-7.87 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-8-10	8/28/2019	8 - 10 ft	856.76	856.63	-0.13	7.87-9.87 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	0.17 - 2 ft	856.76	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-10-12	8/28/2019	10 - 12 ft	856.89	856.00	-0.89	9.11-11.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	12 - 14 ft	856.89	856.00	-0.89	11.11-13.11 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-4-6	8/28/2019	4 - 6 ft	856.89	856.00	-0.89	3.11-5.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-6-8	8/28/2019	6 - 8 ft	856.89	856.00	-0.89	5.11-7.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-8-10	8/28/2019	8 - 10 ft	856.89	856.00	-0.89	7.11-9.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-2-4	8/28/2019	2 - 4 ft	856.89	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	8/28/2019	10 - 12 ft	857.14	855.25	-1.89	8.11-10.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-28	8/28/2019	6 - 8 ft	857.14	855.25	-1.89	4.11-6.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	8/28/2019	6 - 8 ft	857.14	855.25	-1.89	4.11-6.11 ft	X	X	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	8/28/2019	8 - 10 ft	857.14	855.25	-1.89	6.11-8.11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	12 - 14 ft	857.14	855.25	-1.89	10.11-12.11 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-2.4	8/28/2019	2 - 4 ft	857.14	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-4-6	8/28/2019	4 - 6 ft	857.14	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	8/28/2019	0.17 - 2 ft	857.14	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	0.17 - 2 ft	857.14	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	0 - 0.17 ft	856.73	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	0 - 0.17 ft	856.55	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-10-12	8/28/2019	10 - 12 ft	857.12	856.70	-0.42	9.58-11.58 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	12 - 14 ft	857.12	856.70	-0.42	11.58-13.58 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-6-8	8/28/2019	6 - 8 ft	857.12	856.70	-0.42	5.58-7.58 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-8-10	8/28/2019	8 - 10 ft	857.12	856.70	-0.42	7.58-9.58 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	0.17 - 2 ft	857.12	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-2-4	8/28/2019	2 - 4 ft	857.12	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-4-6	8/28/2019	4 - 6 ft	857.12	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	0 - 0.17 ft	858.38	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	0 - 0.17 ft	853.35	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	0 - 0.17 ft	853.09	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	0 - 0.17 ft	851.95	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	10 - 12 ft	852.25	853.25	1.00	11-13 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-2-4	8/29/2019	2 - 4 ft	852.25	853.25	1.00	3-5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-4-6	8/29/2019	4 - 6 ft	852.25	853.25	1.00	5-7 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-6-8	8/29/2019	6 - 8 ft	852.25	853.25	1.00	7-9 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-8-10	8/29/2019	8 - 10 ft	852.25	853.25	1.00	9-11 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-10-12	8/29/2019	10 - 12 ft	852.31	852.62	0.31	10.31-12.31 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	12 - 14 ft	852.31	852.62	0.31	12.31-14.31 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-2-4	8/29/2019	2 - 4 ft	852.31	852.62	0.31	2.31-4.31 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-4-6	8/29/2019	4 - 6 ft	852.31	852.62	0.31	4.31-6.31 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-6-8	8/29/2019	6 - 8 ft	852.31	852.62	0.31	6.31-8.31 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-8-10	8/29/2019	8 - 10 ft	852.31	852.62	0.31	8.31-10.31 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	0 - 0.17 ft	853.88	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	0 - 0.17 ft	853.85	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	0 - 0.17 ft	853.28	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	0.17 - 2 ft	852.90	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-2-4	8/29/2019	2 - 4 ft	852.90	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-4-6	8/29/2019	4 - 6 ft	852.90	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-6-8	8/29/2019	6 - 8 ft	852.90	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-10-12	8/29/2019	10 - 12 ft	852.90	857.00	4.10	14.1-16.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	12 - 14 ft	852.90	857.00	4.10	16.1-18.1 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-8-10	8/29/2019	8 - 10 ft	852.90	857.00	4.10	12.1-14.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	0.17 - 2 ft	853.35	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	10 - 12 ft	853.35	-	-	-	X	X	-	X	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-2-4	8/29/2019	2 - 4 ft	853.35	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-4-6	8/29/2019	4 - 6 ft	853.35	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-6-8	8/29/2019	6 - 8 ft	853.35	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-8-10	8/29/2019	8 - 10 ft	853.35	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-10-12	8/29/2019	10 - 12 ft	853.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-2-4	8/29/2019	2 - 4 ft	853.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-4-6	8/29/2019	4 - 6 ft	853.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-6-8	8/29/2019	6 - 8 ft	853.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	0.17 - 2 ft	853.54	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-8-10	8/29/2019	8 - 10 ft	853.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	12 - 14 ft	853.54	855.13	1.59	13.59-15.59 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	0 - 0.17 ft	854.48	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	0 - 0.17 ft	854.59	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	0.17 - 2 ft	854.13	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-2-4	8/29/2019	2 - 4 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-4-6	8/29/2019	4 - 6 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-6-8	8/29/2019	6 - 8 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-8-10	8/29/2019	8 - 10 ft	854.13	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-10-12	8/29/2019	10 - 12 ft	854.13	857.81	3.68	13.68-15.68 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	12 - 14 ft	854.13	857.81	3.68	15.68-17.68 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-10-12	8/29/2019	10 - 12 ft	854.60	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-2-4	8/29/2019	2 - 4 ft	854.60	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-4-6	8/29/2019	4 - 6 ft	854.60	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-6-8	8/29/2019	6 - 8 ft	854.60	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	0.17 - 2 ft	854.60	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-8-10	8/29/2019	8 - 10 ft	854.60	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	12 - 14 ft	854.60	856.02	1.42	13.42-15.42 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.09	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.60	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.76	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.85	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	0.17 - 2 ft	855.10	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-10-12	8/29/2019	10 - 12 ft	855.10	858.65	3.55	13.55-15.55 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	12 - 14 ft	855.10	858.65	3.55	15.55-17.55 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-2-4	8/29/2019	2 - 4 ft	855.10	858.65	3.55	5.55-7.55 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-4-6	8/29/2019	4 - 6 ft	855.10	858.65	3.55	7.55-9.55 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-6-8	8/29/2019	6 - 8 ft	855.10	858.65	3.55	9.55-11.55 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-8-10	8/29/2019	8 - 10 ft	855.10	858.65	3.55	11.55-13.55 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	0.17 - 2 ft	855.17	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-2-4	8/29/2019	2 - 4 ft	855.17	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-4-6	8/29/2019	4 - 6 ft	855.17	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-10-12	8/29/2019	10 - 12 ft	855.17	858.67	3.50	13.5-15.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	12 - 14 ft	855.17	858.67	3.50	15.5-17.5 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-6-8	8/29/2019	6 - 8 ft	855.17	858.67	3.50	9.5-11.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-8-10	8/29/2019	8 - 10 ft	855.17	858.67	3.50	11.5-13.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.15	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.98	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.41	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.01	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	0.17 - 2 ft	856.01	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-10-12	8/29/2019	10 - 12 ft	856.01	856.77	0.76	10.76-12.76 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	12 - 14 ft	856.01	856.77	0.76	12.76-14.76 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-2-4	8/29/2019	2 - 4 ft	856.01	856.77	0.76	2.76-4.76 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-4-6	8/29/2019	4 - 6 ft	856.01	856.77	0.76	4.76-6.76 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-6-8	8/29/2019	6 - 8 ft	856.01	856.77	0.76	6.76-8.76 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-8-10	8/29/2019	8 - 10 ft	856.01	856.77	0.76	8.76-10.76 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	0.17 - 2 ft	856.20	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-10-12	8/29/2019	10 - 12 ft	856.20	858.70	2.50	12.5-14.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	12 - 14 ft	856.20	858.70	2.50	14.5-16.5 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-2-4	8/29/2019	2 - 4 ft	856.20	858.70	2.50	4.5-6.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-4-6	8/29/2019	4 - 6 ft	856.20	858.70	2.50	6.5-8.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-6-8	8/29/2019	6 - 8 ft	856.20	858.70	2.50	8.5-10.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-8-10	8/29/2019	8 - 10 ft	856.20	858.70	2.50	10.5-12.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	0.17 - 2 ft	855.88	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-10-12	8/29/2019	10 - 12 ft	855.88	858.82	2.94	12.94-14.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	12 - 14 ft	855.88	858.82	2.94	14.94-16.94 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-2-4	8/29/2019	2 - 4 ft	855.88	858.82	2.94	4.94-6.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-4-6	8/29/2019	4 - 6 ft	855.88	858.82	2.94	6.94-8.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-6-8	8/29/2019	6 - 8 ft	855.88	858.82	2.94	8.94-10.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-8-10	8/29/2019	8 - 10 ft	855.88	858.82	2.94	10.94-12.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.91	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.40	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.38	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-10-12	8/29/2019	10 - 12 ft	855.92	856.73	0.81	10.81-12.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-6-8	8/29/2019	6 - 8 ft	855.92	856.73	0.81	6.81-8.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-8-10	8/29/2019	8 - 10 ft	855.92	856.73	0.81	8.81-10.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.36	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	0.17 - 2 ft	856.36	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-10-12	8/29/2019	10 - 12 ft	856.36	857.37	1.01	11.01-13.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	12 - 14 ft	856.36	857.37	1.01	13.01-15.01 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-2-4	8/29/2019	2 - 4 ft	856.36	857.37	1.01	3.01-5.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-4-6	8/29/2019	4 - 6 ft	856.36	857.37	1.01	5.01-7.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-6-8	8/29/2019	6 - 8 ft	856.36	857.37	1.01	7.01-9.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-8-10	8/29/2019	8 - 10 ft	856.36	857.37	1.01	9.01-11.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.58	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	0 - 0.17 ft	856.73	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-10-12	8/29/2019	10 - 12 ft	857.13	857.39	0.26	10.26-12.26 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	12 - 14 ft	857.13	857.39	0.26	12.26-14.26 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-2-4	8/29/2019	2 - 4 ft	857.13	857.39	0.26	2.26-4.26 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-4-6	8/29/2019	4 - 6 ft	857.13	857.39	0.26	4.26-6.26 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-6-8	8/29/2019	6 - 8 ft	857.13	857.39	0.26	6.26-8.26 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-8-10	8/29/2019	8 - 10 ft	857.13	857.39	0.26	8.26-10.26 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.13	-	-	-	X	X	X	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	0.17 - 2 ft	857.13	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-10-12	8/29/2019	10 - 12 ft	856.55	857.05	0.50	10.5-12.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	12 - 14 ft	856.55	857.05	0.50	12.5-14.5 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-2-4	8/29/2019	2 - 4 ft	856.55	857.05	0.50	2.5-4.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-4-6	8/29/2019	4 - 6 ft	856.55	857.05	0.50	4.5-6.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-6-8	8/29/2019	6 - 8 ft	856.55	857.05	0.50	6.5-8.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-8-10	8/29/2019	8 - 10 ft	856.55	857.05	0.50	8.5-10.5 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	0.17 - 2 ft	856.55	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.12	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.77	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.68	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-10-12	8/29/2019	10 - 12 ft	857.57	857.81	0.24	10.24-12.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-12-14	8/29/2019	12 - 14 ft	857.57	857.81	0.24	12.24-14.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	14 - 16 ft	857.57	857.81	0.24	14.24-16.24 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-6-8	8/29/2019	6 - 8 ft	857.57	857.81	0.24	6.24-8.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-8-10	8/29/2019	8 - 10 ft	857.57	857.81	0.24	8.24-10.24 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.57	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	0.17 - 2 ft	857.57	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-2-4	8/29/2019	2 - 4 ft	857.57	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-4-6	8/29/2019	4 - 6 ft	857.57	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-10-12	8/29/2019	10 - 12 ft	857.45	857.88	0.43	10.43-12.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-12-14	8/29/2019	12 - 14 ft	857.45	857.88	0.43	12.43-14.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	14 - 16 ft	857.45	857.88	0.43	14.43-16.43 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-2-4	8/29/2019	2 - 4 ft	857.45	857.88	0.43	2.43-4.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-4-6	8/29/2019	4 - 6 ft	857.45	857.88	0.43	4.43-6.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-6-8	8/29/2019	6 - 8 ft	857.45	857.88	0.43	6.43-8.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-8-10	8/29/2019	8 - 10 ft	857.45	857.88	0.43	8.43-10.43 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	0.17 - 2 ft	857.45	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	0 - 0.17 ft	855.06	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.44	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	0 - 0.17 ft	857.92	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	0 - 0.17 ft	858.28	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-2-4	8/29/2019	2 - 4 ft	858.27	858.28	0.01	2.01-4.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-4-6	8/29/2019	4 - 6 ft	858.27	858.28	0.01	4.01-6.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-10-12	8/29/2019	10 - 12 ft	858.27	858.28	0.01	10.01-12.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-12-14	8/29/2019	12 - 14 ft	858.27	858.28	0.01	12.01-14.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	14 - 16 ft	858.27	858.28	0.01	14.01-16.01 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-6-8	8/29/2019	6 - 8 ft	858.27	858.28	0.01	6.01-8.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-8-10	8/29/2019	8 - 10 ft	858.27	858.28	0.01	8.01-10.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	0 - 0.17 ft	858.27	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	0.17 - 2 ft	858.27	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	0.17 - 2 ft	851.95	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-10-12	8/30/2019	10 - 12 ft	851.95	852.83	0.88	10.88-12.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	12 - 14 ft	851.95	852.83	0.88	12.88-14.88 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-2-4	8/30/2019	2 - 4 ft	851.95	852.83	0.88	2.88-4.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-4-6	8/30/2019	4 - 6 ft	851.95	852.83	0.88	4.88-6.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-6-8	8/30/2019	6 - 8 ft	851.95	852.83	0.88	6.88-8.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-8-10	8/30/2019	8 - 10 ft	851.95	852.83	0.88	8.88-10.88 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	0.17 - 2 ft	853.85	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-10-12	8/30/2019	10 - 12 ft	853.85	854.62	0.77	10.77-12.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	12 - 14 ft	853.85	854.62	0.77	12.77-14.77 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-2-4	8/30/2019	2 - 4 ft	853.85	854.62	0.77	2.77-4.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-4-6	8/30/2019	4 - 6 ft	853.85	854.62	0.77	4.77-6.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-6-8	8/30/2019	6 - 8 ft	853.85	854.62	0.77	6.77-8.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-8-10	8/30/2019	8 - 10 ft	853.85	854.62	0.77	8.77-10.77 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	0.17 - 2 ft	853.28	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-10-12	8/30/2019	10 - 12 ft	853.28	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-2-4	8/30/2019	2 - 4 ft	853.28	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-4-6	8/30/2019	4 - 6 ft	853.28	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-6-8	8/30/2019	6 - 8 ft	853.28	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-8-10	8/30/2019	8 - 10 ft	853.28	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	12 - 14 ft	853.28	855.95	2.67	14.67-16.67 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	0.17 - 2 ft	854.59	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-2-4	8/30/2019	2 - 4 ft	854.59	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-4-6	8/30/2019	4 - 6 ft	854.59	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-10-12	8/30/2019	10 - 12 ft	854.59	855.82	1.23	11.23-13.23 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-12-14	8/30/2019	12 - 14 ft	854.59	855.82	1.23	13.23-15.23 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	14 - 16 ft	854.59	855.82	1.23	15.23-17.23 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-6-8	8/30/2019	6 - 8 ft	854.59	855.82	1.23	7.23-9.23 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-8-10	8/30/2019	8 - 10 ft	854.59	855.82	1.23	9.23-11.23 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	0.17 - 2 ft	855.85	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-10-12	8/30/2019	10 - 12 ft	855.85	856.37	0.52	10.52-12.52 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	12 - 14 ft	855.85	856.37	0.52	12.52-14.52 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-2-4	8/30/2019	2 - 4 ft	855.85	856.37	0.52	2.52-4.52 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-4-6	8/30/2019	4 - 6 ft	855.85	856.37	0.52	4.52-6.52 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-6-8	8/30/2019	6 - 8 ft	855.85	856.37	0.52	6.52-8.52 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-8-10	8/30/2019	8 - 10 ft	855.85	856.37	0.52	8.52-10.52 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	0.17 - 2 ft	856.38	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-10-12	8/30/2019	10 - 12 ft	856.38	856.82	0.44	10.44-12.44 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	12 - 14 ft	856.38	856.82	0.44	12.44-14.44 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-2-4	8/30/2019	2 - 4 ft	856.38	856.82	0.44	2.44-4.44 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-4-6	8/30/2019	4 - 6 ft	856.38	856.82	0.44	4.44-6.44 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-6-8	8/30/2019	6 - 8 ft	856.38	856.82	0.44	6.44-8.44 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-8-10	8/30/2019	8 - 10 ft	856.38	856.82	0.44	8.44-10.44 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	0.17 - 2 ft	856.73	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-10-12	8/30/2019	10 - 12 ft	856.73	857.22	0.49	10.49-12.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-12-14	8/30/2019	12 - 14 ft	856.73	857.22	0.49	12.49-14.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	14 - 16 ft	856.73	857.22	0.49	14.49-16.49 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-2-4	8/30/2019	2 - 4 ft	856.73	857.22	0.49	2.49-4.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-4-6	8/30/2019	4 - 6 ft	856.73	857.22	0.49	4.49-6.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-6-8	8/30/2019	6 - 8 ft	856.73	857.22	0.49	6.49-8.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-8-10	8/30/2019	8 - 10 ft	856.73	857.22	0.49	8.49-10.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	0.17 - 2 ft	857.68	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-2-4	8/30/2019	2 - 4 ft	857.68	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-4-6	8/30/2019	4 - 6 ft	857.68	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-6-8	8/30/2019	6 - 8 ft	857.68	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-10-12	8/30/2019	10 - 12 ft	857.68	857.65	-0.03	9.97-11.97 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-12-14	8/30/2019	12 - 14 ft	857.68	857.65	-0.03	11.97-13.97 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-14-16	8/30/2019	14 - 16 ft	857.68	857.65	-0.03	13.97-15.97 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	16 - 18 ft	857.68	857.65	-0.03	15.97-17.97 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-8-10	8/30/2019	8 - 10 ft	857.68	857.65	-0.03	7.97-9.97 ft	X	X	-	-	-
Football Field	SSHS-B3094	SSHS-DUP-56	8/30/2019	6 - 8 ft	857.26	857.26	0.00	6-8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-10-12	8/30/2019	10 - 12 ft	855.06	855.25	0.19	10.19-12.19 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	12 - 14 ft	855.06	855.25	0.19	12.19-14.19 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-4-6	8/30/2019	4 - 6 ft	855.06	855.25	0.19	4.19-6.19 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-6-8	8/30/2019	6 - 8 ft	855.06	855.25	0.19	6.19-8.19 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-8-10	8/30/2019	8 - 10 ft	855.06	855.25	0.19	8.19-10.19 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	0.17 - 2 ft	855.06	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-2-4	8/30/2019	2 - 4 ft	855.06	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-10-12	8/30/2019	10 - 12 ft	858.28	858.08	-0.20	9.8-11.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-12-14	8/30/2019	12 - 14 ft	858.28	858.08	-0.20	11.8-13.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-14-16	8/30/2019	14 - 16 ft	858.28	858.08	-0.20	13.8-15.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-16-18	8/30/2019	16 - 18 ft	858.28	858.08	-0.20	15.8-17.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-2-4	8/30/2019	2 - 4 ft	858.28	858.08	-0.20	1.8-3.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-4-6	8/30/2019	4 - 6 ft	858.28	858.08	-0.20	3.8-5.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-6-8	8/30/2019	6 - 8 ft	858.28	858.08	-0.20	5.8-7.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-8-10	8/30/2019	8 - 10 ft	858.28	858.08	-0.20	7.8-9.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	0.17 - 2 ft	858.28	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-10-12	8/30/2019	10 - 12 ft	858.38	858.48	0.10	10.1-12.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-12-14	8/30/2019	12 - 14 ft	858.38	858.48	0.10	12.1-14.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16	8/30/2019	14 - 16 ft	858.38	858.48	0.10	14.1-16.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	16 - 18 ft	858.38	858.48	0.10	16.1-18.1 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-2-4	8/30/2019	2 - 4 ft	858.38	858.48	0.10	2.1-4.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-4-6	8/30/2019	4 - 6 ft	858.38	858.48	0.10	4.1-6.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-6-8	8/30/2019	6 - 8 ft	858.38	858.48	0.10	6.1-8.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-8-10	8/30/2019	8 - 10 ft	858.38	858.48	0.10	8.1-10.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	0.17 - 2 ft	858.38	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	0.17 - 2 ft	853.35	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-10-12	9/3/2019	10 - 12 ft	855.74	853.44	-2.30	10.09-12.09 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	12 - 14 ft	853.35	853.44	0.09	12.09-14.09 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-2-4	9/3/2019	2 - 4 ft	853.35	853.44	0.09	2.09-4.09 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-4-6	9/3/2019	4 - 6 ft	853.35	853.44	0.09	4.09-6.09 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-6-8	9/3/2019	6 - 8 ft	853.35	853.44	0.09	6.09-8.09 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-8-10	9/3/2019	8 - 10 ft	853.35	853.44	0.09	8.09-10.09 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	0.17 - 2 ft	853.09	-	-	-	X	X	X	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-2-4	9/3/2019	2 - 4 ft	853.09	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	10 - 12 ft	853.09	853.12	0.03	10.03-12.03 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-4-6	9/3/2019	4 - 6 ft	853.09	853.12	0.03	4.03-6.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-6-8	9/3/2019	6 - 8 ft	853.09	853.12	0.03	6.03-8.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-8-10	9/3/2019	8 - 10 ft	853.09	853.12	0.03	8.03-10.03 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	0.17 - 2 ft	853.88	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-10-12	9/3/2019	10 - 12 ft	853.88	854.29	0.41	10.41-12.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	12 - 14 ft	853.88	854.29	0.41	12.41-14.41 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-2-4	9/3/2019	2 - 4 ft	853.88	854.29	0.41	2.41-4.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-4-6	9/3/2019	4 - 6 ft	853.88	854.29	0.41	4.41-6.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-6-8	9/3/2019	6 - 8 ft	853.88	854.29	0.41	6.41-8.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-8-10	9/3/2019	8 - 10 ft	853.88	854.29	0.41	8.41-10.41 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	0.17 - 2 ft	854.13	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-10-12	9/3/2019	10 - 12 ft	854.13	854.48	0.35	10.35-12.35 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	12 - 14 ft	854.13	854.48	0.35	12.35-14.35 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-4-6	9/3/2019	4 - 6 ft	854.13	854.48	0.35	4.35-6.35 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-6-8	9/3/2019	6 - 8 ft	854.13	854.48	0.35	6.35-8.35 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-8-10	9/3/2019	8 - 10 ft	854.13	854.48	0.35	8.35-10.35 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	0.17 - 2 ft	854.48	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-10-12	9/3/2019	10 - 12 ft	854.48	854.90	0.42	10.42-12.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	12 - 14 ft	854.48	854.90	0.42	12.42-14.42 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-2-4	9/3/2019	2 - 4 ft	854.48	854.90	0.42	2.42-4.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-4-6	9/3/2019	4 - 6 ft	854.48	854.90	0.42	4.42-6.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-6-8	9/3/2019	6 - 8 ft	854.48	854.90	0.42	6.42-8.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-8-10	9/3/2019	8 - 10 ft	854.48	854.90	0.42	8.42-10.42 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-2-4	9/3/2019	2 - 4 ft	855.00	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-10-12	9/3/2019	10 - 12 ft	855.00	855.16	0.16	10.16-12.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	12 - 14 ft	855.00	855.16	0.16	12.16-14.16 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-4-6	9/3/2019	4 - 6 ft	855.00	855.16	0.16	4.16-6.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-6-8	9/3/2019	6 - 8 ft	855.00	855.16	0.16	6.16-8.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-8-10	9/3/2019	8 - 10 ft	855.00	855.16	0.16	8.16-10.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	0.17 - 2 ft	855.09	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-10-12	9/3/2019	10 - 12 ft	855.09	855.21	0.12	10.12-12.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	12 - 14 ft	855.09	855.21	0.12	12.12-14.12 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-2-4	9/3/2019	2 - 4 ft	855.09	855.21	0.12	2.12-4.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-4-6	9/3/2019	4 - 6 ft	855.09	855.21	0.12	4.12-6.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-6-8	9/3/2019	6 - 8 ft	855.09	855.21	0.12	6.12-8.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-8-10	9/3/2019	8 - 10 ft	855.09	855.21	0.12	8.12-10.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	0.17 - 2 ft	855.60	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	0.17 - 2 ft	855.76	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-10-12	9/3/2019	10 - 12 ft	855.76	855.72	-0.04	9.96-11.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	12 - 14 ft	855.76	855.72	-0.04	11.96-13.96 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-2-4	9/3/2019	2 - 4 ft	855.76	855.72	-0.04	1.96-3.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-4-6	9/3/2019	4 - 6 ft	855.76	855.72	-0.04	3.96-5.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-6-8	9/3/2019	6 - 8 ft	855.76	855.72	-0.04	5.96-7.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-8-10	9/3/2019	8 - 10 ft	855.76	855.72	-0.04	7.96-9.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-6-8	9/3/2019	6 - 8 ft	855.98	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	0.17 - 2 ft	855.98	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-2-4	9/3/2019	2 - 4 ft	855.98	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-4-6	9/3/2019	4 - 6 ft	855.98	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	12 - 14 ft	855.98	855.94	-0.04	11.96-13.96 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-8-10	9/3/2019	8 - 10 ft	855.98	855.94	-0.04	7.96-9.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-10-12	9/3/2019	10 - 12 ft	855.98	855.94	-0.04	9.96-11.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	0.17 - 2 ft	856.41	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-10-12	9/3/2019	10 - 12 ft	856.41	856.22	-0.19	9.81-11.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	12 - 14 ft	856.41	856.22	-0.19	11.81-13.81 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-2-4	9/3/2019	2 - 4 ft	856.41	856.22	-0.19	1.81-3.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-4-6	9/3/2019	4 - 6 ft	856.41	856.22	-0.19	3.81-5.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-6-8	9/3/2019	6 - 8 ft	856.41	856.22	-0.19	5.81-7.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-8-10	9/3/2019	8 - 10 ft	856.41	856.22	-0.19	7.81-9.81 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	0.17 - 2 ft	856.40	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-10-12	9/3/2019	10 - 12 ft	856.40	856.48	0.08	10.08-12.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-12-14	9/3/2019	12 - 14 ft	856.40	856.48	0.08	12.08-14.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	14 - 16 ft	856.40	856.48	0.08	14.08-16.08 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-2-4	9/3/2019	2 - 4 ft	856.40	856.48	0.08	2.08-4.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-4-6	9/3/2019	4 - 6 ft	856.40	856.48	0.08	4.08-6.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-6-8	9/3/2019	6 - 8 ft	856.40	856.48	0.08	6.08-8.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-8-10	9/3/2019	8 - 10 ft	856.40	856.48	0.08	8.08-10.08 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	0 - 0.17 ft	852.90	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	0.17 - 2 ft	855.15	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-10-12	9/4/2019	10 - 12 ft	855.15	855.32	0.17	10.17-12.17 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	12 - 14 ft	855.15	855.32	0.17	12.17-14.17 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-2-4	9/4/2019	2 - 4 ft	855.15	855.32	0.17	2.17-4.17 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-4-6	9/4/2019	4 - 6 ft	855.15	855.32	0.17	4.17-6.17 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-6-8	9/4/2019	6 - 8 ft	855.15	855.32	0.17	6.17-8.17 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-8-10	9/4/2019	8 - 10 ft	855.15	855.32	0.17	8.17-10.17 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	0.17 - 2 ft	855.86	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-10-12	9/4/2019	10 - 12 ft	855.86	856.02	0.16	10.16-12.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	12 - 14 ft	855.86	856.02	0.16	12.16-14.16 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-2-4	9/4/2019	2 - 4 ft	855.86	856.02	0.16	2.16-4.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-4-6	9/4/2019	4 - 6 ft	855.86	856.02	0.16	4.16-6.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-6-8	9/4/2019	6 - 8 ft	855.86	856.02	0.16	6.16-8.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-8-10	9/4/2019	8 - 10 ft	855.86	856.02	0.16	8.16-10.16 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	0.17 - 2 ft	856.58	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-10-12	9/4/2019	10 - 12 ft	856.58	856.76	0.18	10.18-12.18 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-12-14	9/4/2019	12 - 14 ft	856.58	856.76	0.18	12.18-14.18 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	14 - 16 ft	856.58	856.76	0.18	14.18-16.18 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-2-4	9/4/2019	2 - 4 ft	856.58	856.76	0.18	2.18-4.18 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-4-6	9/4/2019	4 - 6 ft	856.58	856.76	0.18	4.18-6.18 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-6-8	9/4/2019	6 - 8 ft	856.58	856.76	0.18	6.18-8.18 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-8-10	9/4/2019	8 - 10 ft	856.58	856.76	0.18	8.18-10.18 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	0.17 - 2 ft	856.96	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-10-12	9/4/2019	10 - 12 ft	856.96	857.03	0.07	10.07-12.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	12 - 14 ft	856.96	857.03	0.07	12.07-14.07 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-2-4	9/4/2019	2 - 4 ft	856.96	857.03	0.07	2.07-4.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-4-6	9/4/2019	4 - 6 ft	856.96	857.03	0.07	4.07-6.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	6 - 8 ft	856.96	857.03	0.07	6.07-8.07 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-8-10	9/4/2019	8 - 10 ft	856.96	857.03	0.07	8.07-10.07 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	0.17 - 2 ft	857.12	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-10-12	9/4/2019	10 - 12 ft	857.12	857.26	0.14	10.14-12.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	12 - 14 ft	857.12	857.26	0.14	12.14-14.14 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-2-4	9/4/2019	2 - 4 ft	857.12	857.26	0.14	2.14-4.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-4-6	9/4/2019	4 - 6 ft	857.12	857.26	0.14	4.14-6.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-6-8	9/4/2019	6 - 8 ft	857.12	857.26	0.14	6.14-8.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-8-10	9/4/2019	8 - 10 ft	857.12	857.26	0.14	8.14-10.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	0.17 - 2 ft	857.77	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-10-12	9/4/2019	10 - 12 ft	857.77	857.49	-0.28	9.72-11.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-12-14	9/4/2019	12 - 14 ft	857.77	857.49	-0.28	11.72-13.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	14 - 16 ft	857.77	857.49	-0.28	13.72-15.72 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-2-4	9/4/2019	2 - 4 ft	857.77	857.49	-0.28	1.72-3.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-4-6	9/4/2019	4 - 6 ft	857.77	857.49	-0.28	3.72-5.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-6-8	9/4/2019	6 - 8 ft	857.77	857.49	-0.28	5.72-7.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-8-10	9/4/2019	8 - 10 ft	857.77	857.49	-0.28	7.72-9.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	0.17 - 2 ft	857.44	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-10-12	9/4/2019	10 - 12 ft	857.44	857.92	0.48	10.48-12.48 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-12-14	9/4/2019	12 - 14 ft	857.44	857.92	0.48	12.48-14.48 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	14 - 16 ft	857.44	857.92	0.48	14.48-16.48 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-2-4	9/4/2019	2 - 4 ft	857.44	857.92	0.48	2.48-4.48 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-4-6	9/4/2019	4 - 6 ft	857.44	857.92	0.48	4.48-6.48 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-6-8	9/4/2019	6 - 8 ft	857.44	857.92	0.48	6.48-8.48 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-8-10	9/4/2019	8 - 10 ft	857.44	857.92	0.48	8.48-10.48 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	0.17 - 2 ft	857.92	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-10-12	9/4/2019	10 - 12 ft	857.92	857.93	0.01	10.01-12.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-12-14	9/4/2019	12 - 14 ft	857.92	857.93	0.01	12.01-14.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	14 - 16 ft	857.92	857.93	0.01	14.01-16.01 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-2-4	9/4/2019	2 - 4 ft	857.92	857.93	0.01	2.01-4.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-4-6	9/4/2019	4 - 6 ft	857.92	857.93	0.01	4.01-6.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-6-8	9/4/2019	6 - 8 ft	857.92	857.93	0.01	6.01-8.01 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-8-10	9/4/2019	8 - 10 ft	857.92	857.93	0.01	8.01-10.01 ft	X	X	-	-	-
Football Field	SSHS-B2908	SSHS-B2908-SUB-0.17-2	11/4/2019	0.17 - 2 ft	854.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2917	DUP-06	11/4/2019	2 - 4 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B2917	SSHS-B2917-SUB-2-4	11/4/2019	2 - 4 ft	855.04	-	-	-	X	-	-	-	-
Football Field	SSHS-B2918	SSHS-B2918-SUB-2-4	11/4/2019	2 - 4 ft	854.96	-	-	-	X	-	-	-	-
Football Field	SSHS-B2919	SSHS-B2919-SUB-2-4	11/4/2019	2 - 4 ft	854.98	-	-	-	X	-	-	-	-
Football Field	SSHS-B2920	SSHS-B2920-SUB-2-4	11/4/2019	2 - 4 ft	854.85	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B2922	SSHS-B2922-SUB-2-4	11/4/2019	2 - 4 ft	855.21	-	-	-	X	-	-	-	-
Football Field	SSHS-B2929	DUP-10	11/4/2019	2 - 4 ft	855.22	-	-	-	-	X	-	-	-
Football Field	SSHS-B2929	SSHS-B2929-SUB-2-4	11/4/2019	2 - 4 ft	855.22	-	-	-	-	X	-	-	-
Football Field	SSHS-B2943	SSHS-B2943-SUB-4-6	11/4/2019	4 - 6 ft	854.94	855.38	0.44	4.44-6.44 ft	X	-	-	-	-
Football Field	SSHS-B2912	DUP-04	11/5/2019	0.17 - 2 ft	855.19	-	-	-	X	-	X	-	-
Football Field	SSHS-B2912	SSHS-B2912-SUB-0.17-2	11/5/2019	0.17 - 2 ft	855.19	-	-	-	X	-	X	-	-
Football Field	SSHS-B2923	SSHS-B2923-SUB-4-6	11/5/2019	4 - 6 ft	855.19	-	-	-	X	-	-	-	-
Football Field	SSHS-B2924	DUP-07	11/5/2019	4 - 6 ft	855.27	-	-	-	X	-	-	-	-
Football Field	SSHS-B2924	SSHS-B2924-SUB-4-6	11/5/2019	4 - 6 ft	855.27	-	-	-	X	-	-	-	-
Football Field	SSHS-B2925	SSHS-B2925-SUB-4-6	11/5/2019	4 - 6 ft	855.34	855.52	0.18	4.18-6.18 ft	X	-	-	-	-
Football Field	SSHS-B2926	SSHS-B2926-SUB-2-4	11/5/2019	2 - 4 ft	855.61	-	-	-	-	X	-	-	-
Football Field	SSHS-B2926	DUP-08	11/5/2019	4 - 6 ft	855.61	-	-	-	X	X	-	-	-
Football Field	SSHS-B2926	SSHS-B2926-SUB-4-6	11/5/2019	4 - 6 ft	855.61	-	-	-	X	X	-	-	-
Football Field	SSHS-B2928	SSHS-B2928-SUB-2-4	11/5/2019	2 - 4 ft	855.83	-	-	-	-	X	-	-	-
Football Field	SSHS-B2928	SSHS-B2928-SUB-4-6	11/5/2019	4 - 6 ft	855.83	-	-	-	-	X	-	-	-
Football Field	SSHS-B2934	SSHS-B2934-SUB-8-10	11/5/2019	8 - 10 ft	856.64	-	-	-	-	X	-	-	-
Football Field	SSHS-B2935	SSHS-B2935-SUB-8-10	11/5/2019	8 - 10 ft	857.04	-	-	-	-	X	-	-	-
Football Field	SSHS-B2936	SSHS-B2936-SUB-8-10	11/5/2019	8 - 10 ft	856.94	856.92	-0.02	7.98-9.98 ft	-	X	-	-	-
Football Field	SSHS-B2937	SSHS-B2937-SUB-8-10	11/5/2019	8 - 10 ft	856.90	856.90	0.00	8-10 ft	-	X	-	-	-
Football Field	SSHS-B2942	DUP-11	11/5/2019	6 - 8 ft	855.26	855.32	0.06	6.06-8.06 ft	-	X	-	-	-
Football Field	SSHS-B2942	SSHS-B2942-SUB-6-8	11/5/2019	6 - 8 ft	855.26	855.32	0.06	6.06-8.06 ft	-	X	-	-	-
Football Field	SSHS-B2953	DUP-13	11/5/2019	0.17 - 2 ft	855.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B2953	SSHS-B2953-SUB-0.17-2	11/5/2019	0.17 - 2 ft	855.33	-	-	-	X	-	-	-	-
Football Field	SSHS-B2954	SSHS-B2954-SUB-0.17-2	11/5/2019	0.17 - 2 ft	854.86	-	-	-	X	-	-	-	-
Football Field	SSHS-B2955	SSHS-B2955-SUB-4-6	11/5/2019	4 - 6 ft	855.11	-	-	-	X	-	-	-	-
Football Field	SSHS-B2961	SSHS-B2961-SUB-10-12	11/5/2019	10 - 12 ft	855.28	855.38	0.10	10.1-12.1 ft	X	-	-	-	-
Football Field	SSHS-B2963	DUP-14	11/5/2019	2 - 4 ft	855.27	-	-	-	-	X	-	-	-
Football Field	SSHS-B2963	SSHS-B2963-SUB-2-4	11/5/2019	2 - 4 ft	855.27	-	-	-	-	X	-	-	-
Football Field	SSHS-B2966	SSHS-B2966-SUB-4-6	11/5/2019	4 - 6 ft	855.41	-	-	-	-	X	-	-	-
Football Field	SSHS-B2989	SSHS-B2989-SUB-4-6	11/5/2019	4 - 6 ft	855.59	-	-	-	X	-	-	-	-
Football Field	SSHS-B2900	DUP-01	11/6/2019	0.17 - 2 ft	855.76	-	-	-	X	-	X	-	-
Football Field	SSHS-B2900	SSHS-B2900-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.76	-	-	-	X	-	X	-	-
Football Field	SSHS-B2901	DUP-02	11/6/2019	0.17 - 2 ft	856.05	-	-	-	X	-	X	-	-
Football Field	SSHS-B2901	SSHS-B2901-SUB-0.17-2	11/6/2019	0.17 - 2 ft	856.05	-	-	-	X	-	X	-	-
Football Field	SSHS-B2902	SSHS-B2902-SUB-0.17-2	11/6/2019	0.17 - 2 ft	856.47	-	-	-	X	-	-	-	-
Football Field	SSHS-B2903	SSHS-B2903-SUB-0.17-2	11/6/2019	0.17 - 2 ft	856.79	-	-	-	X	-	-	-	-
Football Field	SSHS-B2904	SSHS-B2904-SUB-0.17-2	11/6/2019	0.17 - 2 ft	856.15	-	-	-	X	-	-	-	-
Football Field	SSHS-B2906	SSHS-B2906-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.46	-	-	-	X	X	-	-	-
Football Field	SSHS-B2907	SSHS-B2907-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.77	-	-	-	X	X	-	-	-
Football Field	SSHS-B2910	SSHS-B2910-SUB-0.17-2	11/6/2019	0.17 - 2 ft	856.07	-	-	-	X	-	-	-	-
Football Field	SSHS-B2911	SSHS-B2911-SUB-0.17-2	11/6/2019	0.17 - 2 ft	854.88	-	-	-	X	-	X	-	-
Football Field	SSHS-B2913	SSHS-B2913-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.40	-	-	-	X	-	-	-	-
Football Field	SSHS-B2914	SSHS-B2914-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.30	-	-	-	X	-	-	-	-
Football Field	SSHS-B2914	DUP-05	11/6/2019	2 - 4 ft	855.30	-	-	-	-	-	X	-	-
Football Field	SSHS-B2914	SSHS-B2914-SUB-2-4	11/6/2019	2 - 4 ft	855.30	-	-	-	-	-	X	-	-
Football Field	SSHS-B2921	SSHS-B2921-SUB-2-4	11/6/2019	2 - 4 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2921	SSHS-B2921-SUB-4-6	11/6/2019	4 - 6 ft	855.12	-	-	-	X	-	-	-	-
Football Field	SSHS-B2927	DUP-09	11/6/2019	0.17 - 2 ft	855.16	-	-	-	-	X	-	-	-
Football Field	SSHS-B2927	SSHS-B2927-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.16	-	-	-	-	X	-	-	-
Football Field	SSHS-B2931	SSHS-B2931-SUB-4-6	11/6/2019	4 - 6 ft	856.02	-	-	-	-	X	-	-	-
Football Field	SSHS-B2932	SSHS-B2932-SUB-4-6	11/6/2019	4 - 6 ft	855.47	-	-	-	-	X	-	-	-
Football Field	SSHS-B2933	SSHS-B2933-SUB-4-6	11/6/2019	4 - 6 ft	855.61	-	-	-	-	X	-	-	-
Football Field	SSHS-B2938	SSHS-B2938-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.53	-	-	-	-	-	X	-	-
Football Field	SSHS-B2939	SSHS-B2939-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.56	-	-	-	-	-	X	-	-
Football Field	SSHS-B2940	SSHS-B2940-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.06	-	-	-	-	-	X	-	-
Football Field	SSHS-B2941	SSHS-B2941-SUB-0.17-2	11/6/2019	0.17 - 2 ft	855.17	-	-	-	-	-	X	-	-
Football Field	SSHS-B2952	SSHS-B2952-SUB-2-4	11/6/2019	2 - 4 ft	855.18	-	-	-	-	-	X	-	-
Football Field	SSHS-B2962	SSHS-B2962-SUB-12-14	11/6/2019	12 - 14 ft	855.36	-	-	-	X	-	-	-	-
Football Field	SSHS-B2905	SSHS-B2905-SUB-0.17-2	11/7/2019	0.17 - 2 ft	856.07	-	-	-	X	X	-	-	-
Football Field	SSHS-B2915	SSHS-B2915-SUB-2-4	11/7/2019	2 - 4 ft	856.44	-	-	-	X	-	-	-	-
Football Field	SSHS-B2916	SSHS-B2916-SUB-2-4	11/7/2019	2 - 4 ft	856.41	856.40	-0.01	1.99-3.99 ft	X	-	-	-	-
Football Field	SSHS-B2930	SSHS-B2930-SUB-2-4	11/7/2019	2 - 4 ft	855.06	-	-	-	-	X	-	-	-
Football Field	SSHS-B2944	SSHS-B2944-SUB-2-4	11/7/2019	2 - 4 ft	856.50	-	-	-	X	-	-	-	-
Football Field	SSHS-B2956	SSHS-B2956-SUB-2-4	11/7/2019	2 - 4 ft	854.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B2956	SSHS-B2956-SUB-4-6	11/7/2019	4 - 6 ft	854.88	-	-	-	X	-	-	-	-
Football Field	SSHS-B2958	SSHS-B2958-SUB-4-6	11/7/2019	4 - 6 ft	855.63	-	-	-	X	-	-	-	-
Football Field	SSHS-B2959	SSHS-B2959-SUB-10-12	11/7/2019	10 - 12 ft	855.25	-	-	-	X	-	-	-	-
Football Field	SSHS-B2960	SSHS-B2960-SUB-10-12	11/7/2019	10 - 12 ft	855.17	-	-	-	X	X	-	-	-
Football Field	SSHS-B2964	SSHS-B2964-SUB-10-12	11/7/2019	10 - 12 ft	854.90	-	-	-	-	X	-	-	-
Football Field	SSHS-B2965	SSHS-B2965-SUB-10-12	11/7/2019	10 - 12 ft	854.88	-	-	-	-	X	-	-	-
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	12 - 14 ft	854.56	854.87	0.31	12 - 14 ft	X	X	X	-	-
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	10 - 12 ft	855.35	855.37	0.02	10.02-12.02 ft	X	X	X	-	-
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	12 - 14 ft	855.35	855.37	0.02	12.02-14.02 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-0.17-2	12/16/2019	0.17 - 2 ft	856.22	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-2-4	12/16/2019	2 - 4 ft	856.22	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-0.17-2	12/16/2019	0.17 - 2 ft	856.13	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-2-4	12/16/2019	2 - 4 ft	856.13	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-0.17-2	12/16/2019	0.17 - 2 ft	855.94	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-2-4	12/16/2019	2 - 4 ft	855.94	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-2-4	12/16/2019	2 - 4 ft	856.96	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-4-6	12/16/2019	4 - 6 ft	856.96	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3313	SSHS-B3313-SUB-2-4	12/16/2019	2 - 4 ft	856.94	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3313	SSHS-B3313-SUB-4-6	12/16/2019	4 - 6 ft	856.94	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-0.17-2	12/16/2019	0.17 - 2 ft	856.94	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	2 - 4 ft	856.94	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	4 - 6 ft	856.94	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	0.17 - 2 ft	856.62	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-2-4	12/16/2019	2 - 4 ft	856.62	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-4-6	12/16/2019	4 - 6 ft	856.62	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-2-4	12/16/2019	2 - 4 ft	856.86	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-4-6	12/16/2019	4 - 6 ft	856.86	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-2-4	12/16/2019	2 - 4 ft	856.76	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-4-6	12/16/2019	4 - 6 ft	856.76	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3320	SSHS-B3320-SUB-2-4	12/16/2019	2 - 4 ft	856.83	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3320	SSHS-B3320-SUB-4-6	12/16/2019	4 - 6 ft	856.83	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	0.17 - 2 ft	855.76	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-2-4	12/16/2019	2 - 4 ft	855.76	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	0.17 - 2 ft	856.21	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-2-4	12/16/2019	2 - 4 ft	856.21	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	0.17 - 2 ft	856.48	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-2-4	12/16/2019	2 - 4 ft	856.48	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	0.17 - 2 ft	855.88	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-2-4	12/16/2019	2 - 4 ft	855.88	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-0.17-2	12/16/2019	0.17 - 2 ft	853.99	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-2-4	12/16/2019	2 - 4 ft	853.99	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-0.17-2	12/16/2019	0.17 - 2 ft	854.39	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-2-4	12/16/2019	2 - 4 ft	854.39	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	4 - 6 ft	853.34	855.35	2.01	6.01-8.01 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-0.17-2	12/16/2019	0.17 - 2 ft	853.34	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-2-4	12/16/2019	2 - 4 ft	853.34	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-0.17-2	12/16/2019	0.17 - 2 ft	854.14	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-2-4	12/16/2019	2 - 4 ft	854.14	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	4 - 6 ft	852.74	855.10	2.36	6.36-8.36 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-0.17-2	12/16/2019	0.17 - 2 ft	852.74	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-2-4	12/16/2019	2 - 4 ft	852.74	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	2 - 4 ft	851.73	852.70	0.97	2.97-4.97 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-0.17-2	12/16/2019	0.17 - 2 ft	851.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	2 - 4 ft	852.38	854.95	2.57	4.57-6.57 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-0.17-2	12/16/2019	0.17 - 2 ft	852.38	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-0.17-2	12/16/2019	0.17 - 2 ft	853.06	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-2-4	12/16/2019	2 - 4 ft	853.06	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-4-6	12/16/2019	4 - 6 ft	853.06	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-0.17-2	12/16/2019	0.17 - 2 ft	853.75	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-2-4	12/16/2019	2 - 4 ft	853.75	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	2 - 4 ft	855.54	854.58	-0.96	1.04-3.04 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-0.17-2	12/17/2019	0.17 - 2 ft	855.54	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.21	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-2-4	12/17/2019	2 - 4 ft	856.21	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.34	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-2-4	12/17/2019	2 - 4 ft	856.34	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3287	SSHS-B3287-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.65	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3287	SSHS-B3287-SUB-2-4	12/17/2019	2 - 4 ft	857.65	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	2 - 4 ft	856.90	856.50	-0.40	1.6-3.6 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.90	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3289	SSHS-B3289-SUB-2-4	12/17/2019	2 - 4 ft	857.03	856.77	-0.26	1.74-3.74 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3289	SSHS-B3289-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.03	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3290	SSHS-B3290-SUB-2-4	12/17/2019	2 - 4 ft	857.23	856.80	-0.43	1.57-3.57 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3290	SSHS-B3290-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.23	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.22	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-2-4	12/17/2019	2 - 4 ft	857.22	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.35	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-2-4	12/17/2019	2 - 4 ft	857.35	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.15	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-2-4	12/17/2019	2 - 4 ft	857.15	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.87	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-2-4	12/17/2019	2 - 4 ft	856.87	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-0.17-2	12/17/2019	0.17 - 2 ft	855.96	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-2-4	12/17/2019	2 - 4 ft	855.96	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.02	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-2-4	12/17/2019	2 - 4 ft	857.02	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.20	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-2-4	12/17/2019	2 - 4 ft	857.20	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.10	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-2-4	12/17/2019	2 - 4 ft	857.10	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.38	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-2-4	12/17/2019	2 - 4 ft	856.38	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.19	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-2-4	12/17/2019	2 - 4 ft	856.19	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-2-4	12/17/2019	2 - 4 ft	856.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.97	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	2 - 4 ft	856.97	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	0.17 - 2 ft	857.04	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-2-4	12/17/2019	2 - 4 ft	857.04	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.00	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-2-4	12/17/2019	2 - 4 ft	856.00	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	2 - 4 ft	855.68	855.91	0.23	2.23-4.23 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-0.17-2	12/17/2019	0.17 - 2 ft	855.68	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-2-4	12/17/2019	2 - 4 ft	856.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.64	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-2-4	12/17/2019	2 - 4 ft	856.64	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	2 - 4 ft	856.43	856.96	0.53	2.53-4.53 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.43	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	0.17 - 2 ft	856.17	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-2-4	12/17/2019	2 - 4 ft	856.17	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-0.17-2	12/17/2019	0.17 - 2 ft	853.63	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-2-4	12/17/2019	2 - 4 ft	853.63	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3258	SSHS-B3258-SUB-2-4	12/18/2019	2 - 4 ft	856.41	856.86	0.45	2.45-4.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3258	SSHS-B3258-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.41	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0-0.17	12/18/2019	0 - 0.17 ft	856.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0-0.17	12/18/2019	0 - 0.17 ft	857.03	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0.17-2	12/18/2019	0.17 - 2 ft	857.03	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0-0.17	12/18/2019	0 - 0.17 ft	857.52	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0.17-2	12/18/2019	0.17 - 2 ft	857.52	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	14 - 16 ft	854.30	857.51	3.21	17.21-19.21 ft	X	-	-	X	-
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-14-16	12/18/2019	14 - 16 ft	854.04	857.78	3.74	17.74-19.74 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-12-14	12/18/2019	12 - 14 ft	854.04	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-0.17-2	12/18/2019	0.17 - 2 ft	854.04	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-2-4	12/18/2019	2 - 4 ft	854.04	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-14-16	12/18/2019	14 - 16 ft	853.76	857.23	3.47	17.47-19.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-12-14	12/18/2019	12 - 14 ft	853.76	857.23	3.47	15.47-17.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-12-14	12/18/2019	12 - 14 ft	854.51	857.10	2.59	14.59-16.59 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-14-16	12/18/2019	14 - 16 ft	854.51	857.10	2.59	16.59-18.59 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-14-16	12/18/2019	14 - 16 ft	854.73	857.54	2.81	16.81-18.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-0.17-2	12/18/2019	0.17 - 2 ft	854.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-12-14	12/18/2019	12 - 14 ft	854.73	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-2-4	12/18/2019	2 - 4 ft	854.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-0.17-2	12/18/2019	0.17 - 2 ft	854.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-2-4	12/18/2019	2 - 4 ft	854.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-2-4	12/18/2019	2 - 4 ft	855.88	858.85	2.97	4.97-6.97 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0-0.17	12/18/2019	0 - 0.17 ft	855.88	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0.17-2	12/18/2019	0.17 - 2 ft	855.88	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-2-4	12/18/2019	2 - 4 ft	855.39	858.94	3.55	5.55-7.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0-0.17	12/18/2019	0 - 0.17 ft	855.39	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0.17-2	12/18/2019	0.17 - 2 ft	855.39	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	2 - 4 ft	856.00	857.99	1.99	3.99-5.99 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.00	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0-0.17	12/18/2019	0.17 - 2 ft	856.00	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.15	858.40	2.25	2.42-4.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-2-4	12/18/2019	2 - 4 ft	856.15	858.40	2.25	4.25-6.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0-0.17	12/18/2019	0 - 0.17 ft	856.15	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-0.17-2	12/18/2019	0.17 - 2 ft	855.80	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-2-4	12/18/2019	2 - 4 ft	855.80	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	2 - 4 ft	856.25	856.90	0.65	2.65-4.65 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.25	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	4 - 6 ft	856.44	857.46	1.02	5.02-7.02 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.44	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	2 - 4 ft	856.44	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B3277	SSHS-B3277-SUB-4-6	12/18/2019	4 - 6 ft	856.31	857.29	0.98	4.98-6.98 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3277	SSHS-B3277-SUB-2-4	12/18/2019	2 - 4 ft	856.31	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3278	SSHS-B3278-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.22	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3279	SSHS-B3279-SUB-2-4	12/18/2019	2 - 4 ft	856.57	856.71	0.14	2.14-4.14 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3279	SSHS-B3279-SUB-4-6	12/18/2019	4 - 6 ft	856.57	856.71	0.14	4.14-6.14 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	4 - 6 ft	856.56	856.77	0.21	4.21-6.21 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.56	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	2 - 4 ft	856.56	-	-	-	-	X	X	-	-
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	2 - 4 ft	856.88	856.81	-0.07	1.93-3.93 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.88	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.89	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-2-4	12/18/2019	2 - 4 ft	856.89	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	2 - 4 ft	856.35	856.53	0.18	2.18-4.18 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-0.17-2	12/18/2019	0.17 - 2 ft	856.35	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3241	SSHS-B3241-SUB-0.17-2	12/19/2019	0.17 - 2 ft	856.35	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3241	SSHS-B3241-SUB-2-4	12/19/2019	2 - 4 ft	856.35	857.24	0.89	2.89-4.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-0.17-2	12/19/2019	0.17 - 2 ft	856.23	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-2-4	12/19/2019	2 - 4 ft	856.23	857.22	0.99	2.99-4.99 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-4-6	12/19/2019	4 - 6 ft	856.23	857.22	0.99	4.99-6.99 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3243	SSHS-B3243-SUB-2-4	12/19/2019	2 - 4 ft	856.13	857.96	1.83	3.83-5.83 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3243	SSHS-B3243-SUB-4-6	12/19/2019	4 - 6 ft	856.13	857.96	1.83	5.83-7.83 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0-0.17	12/19/2019	0 - 0.17 ft	857.74	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.74	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-2-4	12/19/2019	2 - 4 ft	857.74	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-6-8	12/19/2019	6 - 8 ft	857.74	857.53	-0.21	5.79-7.79 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-8-10	12/19/2019	8 - 10 ft	857.74	857.53	-0.21	7.79-9.79 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0-0.17	12/19/2019	0 - 0.17 ft	857.37	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.37	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-2-4	12/19/2019	2 - 4 ft	857.37	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-6-8	12/19/2019	6 - 8 ft	857.37	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-8-10	12/19/2019	8 - 10 ft	857.37	857.51	0.14	8.14-10.14 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0-0.17	12/19/2019	0 - 0.17 ft	858.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0.17-2	12/19/2019	0.17 - 2 ft	858.13	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-2-4	12/19/2019	2 - 4 ft	858.13	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-6-8	12/19/2019	6 - 8 ft	858.13	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-8-10	12/19/2019	8 - 10 ft	858.13	857.94	-0.19	7.81-9.81 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-0-0.17	12/19/2019	0 - 0.17 ft	857.57	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3247	SSHS-B-3247-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.57	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-2-4	12/19/2019	2 - 4 ft	857.57	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-6-8	12/19/2019	6 - 8 ft	857.57	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-8-10	12/19/2019	8 - 10 ft	857.57	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3248	SSHS-B3248-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.19	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3248	SSHS-B3248-SUB-2-4	12/19/2019	2 - 4 ft	857.19	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	12/19/2019	0 - 0.17 ft	857.44	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.44	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-2-4	12/19/2019	2 - 4 ft	857.44	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0.17-2	12/19/2019	0.17 - 2 ft	858.02	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0-0.17	12/19/2019	0 - 0.17 ft	858.02	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	2 - 4 ft	858.02	858.03	0.01	2.01-4.01 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3251	SSHS-B3251-SUB-0.17-2	12/19/2019	0 - 0.17 ft	858.34	-	-	-	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3251	SSHS-B3251-SUB-2-4	12/19/2019	2 - 4 ft	858.34	858.34	0.00	2-4 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	12/19/2019	0 - 0.17 ft	857.46	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.46	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	2 - 4 ft	857.46	857.80	0.34	2.34-4.34 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-0.17-2	12/19/2019	0.17 - 2 ft	858.40	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	2 - 4 ft	858.40	858.37	-0.03	1.97-3.97 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-0.17-2	12/19/2019	0.17 - 2 ft	856.34	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-2-4	12/19/2019	2 - 4 ft	856.34	856.66	0.32	2.32-4.32 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.06	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	2 - 4 ft	857.06	857.52	0.46	2.46-4.46 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-0.17-2	12/19/2019	0.17 - 2 ft	858.14	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-2-4	12/19/2019	2 - 4 ft	858.14	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-0.17-2	12/19/2019	0.17 - 2 ft	858.41	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	2 - 4 ft	858.41	858.46	0.05	2.05-4.05 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-0.17-2	12/19/2019	0.17 - 2 ft	857.33	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	2 - 4 ft	857.33	857.76	0.43	2.43-4.43 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-0.17-2	12/19/2019	0.17 - 2 ft	858.57	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	2 - 4 ft	858.57	858.48	-0.09	1.91-3.91 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	16 - 17 ft	858.31	858.15	-0.16	15.84-16.84 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-0.17-2	12/20/2019	0.17 - 2 ft	853.42	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	2 - 4 ft	853.42	854.03	0.61	2.61-4.61 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	0.17 - 2 ft	853.22	-	-	-	-	-	X	X	-
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	2 - 4 ft	853.22	853.68	0.46	2.46-4.46 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-0.17-2	12/20/2019	0.17 - 2 ft	853.19	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-0.17-2	12/20/2019	0.17 - 2 ft	853.57	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	2 - 4 ft	853.57	853.82	0.25	2.25-4.25 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3229	SSHS-B3229-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.55	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3229	SSHS-B3229-SUB-2-4	12/20/2019	2 - 4 ft	855.55	855.45	-0.10	1.9-3.9 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3230	SSHS-B3230-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.45	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3230	SSHS-B3230-SUB-2-4	12/20/2019	2 - 4 ft	855.45	855.49	0.04	2.04-4.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3231	SSHS-B3231-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.72	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3231	SSHS-B3231-SUB-2-4	12/20/2019	2 - 4 ft	855.72	855.63	-0.09	1.91-3.91 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	2 - 4 ft	855.71	855.63	-0.08	1.92-3.92 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	4 - 6 ft	855.71	855.63	-0.08	3.92-5.92 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.71	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-2-4	12/20/2019	2 - 4 ft	855.71	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-6-8	12/20/2019	6 - 8 ft	855.71	855.74	0.03	6.03-8.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-8-10	12/20/2019	8 - 10 ft	855.71	855.74	0.03	8.03-10.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3234	SSHS-B3234-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.92	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3234	SSHS-B3234-SUB-2-4	12/20/2019	2 - 4 ft	855.92	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-0.17-2	12/20/2019	0.17 - 2 ft	856.44	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-2-4	12/20/2019	2 - 4 ft	856.44	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-6-8	12/20/2019	6 - 8 ft	856.44	856.25	-0.19	5.81-7.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-8-10	12/20/2019	8 - 10 ft	856.44	856.25	-0.19	7.81-9.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-0.17-2	12/20/2019	0.17 - 2 ft	856.32	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-2-4	12/20/2019	2 - 4 ft	856.32	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-6-8	12/20/2019	6 - 8 ft	856.32	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-8-10	12/20/2019	8 - 10 ft	856.32	856.30	-0.02	7.98-9.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3237	SSHS-B3237-SUB-0.17-2	12/20/2019	0.17 - 2 ft	856.01	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3237	SSHS-B3237-SUB-2-4	12/20/2019	2 - 4 ft	856.01	856.02	0.01	2.01-4.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3238	SSHS-B3238-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.23	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3238	SSHS-B3238-SUB-2-4	12/20/2019	2 - 4 ft	855.23	855.98	0.75	2.75-4.75 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3239	SSHS-B3239-SUB-0.17-2	12/20/2019	0.17 - 2 ft	855.81	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3239	SSHS-B3239-SUB-2-4	12/20/2019	2 - 4 ft	855.81	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3240	SSHS-B3240-SUB-0.17-2	12/20/2019	0.17 - 2 ft	856.04	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3240	SSHS-B3240-SUB-2-4	12/20/2019	2 - 4 ft	856.04	856.82	0.78	2.78-4.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-14-16	12/20/2019	14 - 16 ft	858.13	857.94	-0.19	13.81-15.81 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	10 - 12 ft	851.57	852.53	0.96	10.96-12.96 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	12 - 14 ft	851.57	852.53	0.96	12.96-14.96 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	6 - 8 ft	851.57	852.53	0.96	6.96-8.96 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	8 - 10 ft	851.57	852.53	0.96	8.96-10.96 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	0.17 - 2 ft	856.74	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	0.17 - 2 ft	856.74	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	0.17 - 2 ft	856.74	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	2 - 4 ft	856.74	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-10-12	1/13/2020	10 - 12 ft	856.74	856.68	-0.06	9.94-11.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	12 - 14 ft	856.74	856.68	-0.06	11.94-13.94 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-4-6	1/13/2020	4 - 6 ft	856.74	856.68	-0.06	3.94-5.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-6-8	1/13/2020	6 - 8 ft	856.74	856.68	-0.06	5.94-7.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-8-10	1/13/2020	8 - 10 ft	856.74	856.68	-0.06	7.94-9.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	0.17 - 2 ft	856.75	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	0.5 - 2 ft	856.75	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	0.5 - 2 ft	856.75	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	2 - 4 ft	856.75	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-4-6	1/13/2020	4 - 6 ft	856.75	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-10-12	1/13/2020	10 - 12 ft	856.75	856.69	-0.06	9.94-11.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	12 - 14 ft	856.75	856.69	-0.06	11.94-13.94 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-6-8	1/13/2020	6 - 8 ft	856.75	856.69	-0.06	5.94-7.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-8-10	1/13/2020	8 - 10 ft	856.75	856.69	-0.06	7.94-9.94 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	0.5 - 2 ft	856.74	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	2 - 4 ft	856.74	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-4-6	1/13/2020	4 - 6 ft	856.74	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-10-12	1/13/2020	10 - 12 ft	856.74	856.23	-0.51	9.49-11.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	12 - 14 ft	856.74	856.23	-0.51	11.49-13.49 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-6-8	1/13/2020	6 - 8 ft	856.74	856.23	-0.51	5.49-7.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-8-10	1/13/2020	8 - 10 ft	856.74	856.23	-0.51	7.49-9.49 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-10-12	1/13/2020	10 - 12 ft	856.47	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-12-14	1/13/2020	12 - 14 ft	856.47	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-4-6	1/13/2020	4 - 6 ft	856.47	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-6-8	1/13/2020	6 - 8 ft	856.47	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-8-10	1/13/2020	8 - 10 ft	856.47	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	0.17 - 2 ft	856.47	-	-	-	-	X	-	X	-
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	14 - 16 ft	856.47	856.36	-0.11	13.89-15.89 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	0.17 - 2 ft	856.82	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	0.5 - 2 ft	856.82	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	2 - 4 ft	856.82	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-10-12	1/13/2020	10 - 12 ft	856.82	856.64	-0.18	9.82-11.82 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	12 - 14 ft	856.82	856.64	-0.18	11.82-13.82 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-4-6	1/13/2020	4 - 6 ft	856.82	856.64	-0.18	3.82-5.82 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-6-8	1/13/2020	6 - 8 ft	856.82	856.64	-0.18	5.82-7.82 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-8-10	1/13/2020	8 - 10 ft	856.82	856.64	-0.18	7.82-9.82 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	0.5 - 2 ft	856.73	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	2 - 4 ft	856.73	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-4-6	1/14/2020	4 - 6 ft	856.73	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-10-12	1/14/2020	10 - 12 ft	856.73	856.62	-0.11	9.89-11.89 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	12 - 14 ft	856.73	856.62	-0.11	11.89-13.89 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-6-8	1/14/2020	6 - 8 ft	856.73	856.62	-0.11	5.89-7.89 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-8-10	1/14/2020	8 - 10 ft	856.73	856.62	-0.11	7.89-9.89 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	0.5 - 2 ft	856.72	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	2 - 4 ft	856.72	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-4-6	1/14/2020	4 - 6 ft	856.72	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-10-12	1/14/2020	10 - 12 ft	856.72	856.30	-0.42	9.58-11.58 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	12 - 14 ft	856.72	856.30	-0.42	11.58-13.58 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-6-8	1/14/2020	6 - 8 ft	856.72	856.30	-0.42	5.58-7.58 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-8-10	1/14/2020	8 - 10 ft	856.72	856.30	-0.42	7.58-9.58 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	0.17 - 2 ft	857.55	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-2-4	1/14/2020	2 - 4 ft	857.55	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-10-12	1/14/2020	10 - 12 ft	857.55	856.76	-0.79	9.21-11.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	12 - 14 ft	857.55	856.76	-0.79	11.21-13.21 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-4-6	1/14/2020	4 - 6 ft	857.55	856.76	-0.79	3.21-5.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-6-8	1/14/2020	6 - 8 ft	857.55	856.76	-0.79	5.21-7.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-8-10	1/14/2020	8 - 10 ft	857.55	856.76	-0.79	7.21-9.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-2-4	1/14/2020	2 - 4 ft	856.36	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	0.17 - 2 ft	856.36	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-10-12	1/14/2020	10 - 12 ft	856.36	856.08	-0.28	9.72-11.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-4-6	1/14/2020	4 - 6 ft	856.36	856.08	-0.28	3.72-5.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-6-8	1/14/2020	6 - 8 ft	856.36	856.08	-0.28	5.72-7.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-8-10	1/14/2020	8 - 10 ft	856.36	856.08	-0.28	7.72-9.72 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	12 - 14 ft	856.36	856.08	-0.28	11.72-13.72 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-2-4	1/14/2020	2 - 4 ft	856.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-4-6	1/14/2020	4 - 6 ft	856.54	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-10-12	1/14/2020	10 - 12 ft	856.54	856.53	-0.01	9.99-11.99 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	12 - 14 ft	856.54	856.53	-0.01	11.99-13.99 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-6-8	1/14/2020	6 - 8 ft	856.54	856.53	-0.01	5.99-7.99 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	2 - 4 ft	856.70	-	-	-	X	X	X	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-4-6	1/14/2020	4 - 6 ft	856.70	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	0.5 - 2 ft	856.70	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-10-12	1/14/2020	10 - 12 ft	856.70	855.84	-0.86	9.14-11.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-6-8	1/14/2020	6 - 8 ft	856.70	855.84	-0.86	5.14-7.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-8-10	1/14/2020	8 - 10 ft	856.70	855.84	-0.86	7.14-9.14 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	12 - 14 ft	856.70	855.84	-0.86	11.14-13.14 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-2-4	1/14/2020	2 - 4 ft	856.85	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-4-6	1/14/2020	4 - 6 ft	856.85	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	0.17 - 2 ft	856.85	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-10-12	1/14/2020	10 - 12 ft	856.85	855.95	-0.90	9.1-11.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-6-8	1/14/2020	6 - 8 ft	856.85	855.95	-0.90	5.1-7.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-8-10	1/14/2020	8 - 10 ft	856.85	855.95	-0.90	7.1-9.1 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	12 - 14 ft	856.85	855.95	-0.90	11.1-13.1 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	0.17 - 2 ft	857.05	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-2-4	1/15/2020	2 - 4 ft	857.05	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-10-12	1/15/2020	10 - 12 ft	857.05	857.26	0.21	10.21-12.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	12 - 14 ft	857.05	857.26	0.21	12.21-14.21 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-4-6	1/15/2020	4 - 6 ft	857.05	857.26	0.21	4.21-6.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-6-8	1/15/2020	6 - 8 ft	857.05	857.26	0.21	6.21-8.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-8-10	1/15/2020	8 - 10 ft	857.05	857.26	0.21	8.21-10.21 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	0.17 - 2 ft	857.26	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-2-4	1/15/2020	2 - 4 ft	857.26	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-4-6	1/15/2020	4 - 6 ft	857.26	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-10-12	1/15/2020	10 - 12 ft	857.26	856.77	-0.49	9.51-11.51 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	12 - 14 ft	857.26	856.77	-0.49	11.51-13.51 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-6-8	1/15/2020	6 - 8 ft	857.26	856.77	-0.49	5.51-7.51 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-8-10	1/15/2020	8 - 10 ft	857.26	856.77	-0.49	7.51-9.51 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	0.17 - 2 ft	856.32	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-2-4	1/15/2020	2 - 4 ft	856.32	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-10-12	1/15/2020	10 - 12 ft	856.32	856.06	-0.26	9.74-11.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	12 - 14 ft	856.32	856.06	-0.26	11.74-13.74 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-4-6	1/15/2020	4 - 6 ft	856.32	856.06	-0.26	3.74-5.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-6-8	1/15/2020	6 - 8 ft	856.32	856.06	-0.26	5.74-7.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-8-10	1/15/2020	8 - 10 ft	856.32	856.06	-0.26	7.74-9.74 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	0.17 - 2 ft	857.08	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-2-4	1/15/2020	2 - 4 ft	857.08	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-10-12	1/15/2020	10 - 12 ft	857.08	857.00	-0.08	9.92-11.92 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	12 - 14 ft	857.08	857.00	-0.08	11.92-13.92 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-4-6	1/15/2020	4 - 6 ft	857.08	857.00	-0.08	3.92-5.92 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-6-8	1/15/2020	6 - 8 ft	857.08	857.00	-0.08	5.92-7.92 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-8-10	1/15/2020	8 - 10 ft	857.08	857.00	-0.08	7.92-9.92 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	0.17 - 2 ft	856.71	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	2 - 4 ft	856.71	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-4-6	1/15/2020	4 - 6 ft	856.71	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-10-12	1/15/2020	10 - 12 ft	856.71	856.67	-0.04	9.96-11.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	12 - 14 ft	856.71	856.67	-0.04	11.96-13.96 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-6-8	1/15/2020	6 - 8 ft	856.71	856.67	-0.04	5.96-7.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-8-10	1/15/2020	8 - 10 ft	856.71	856.67	-0.04	7.96-9.96 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0.17-2	1/15/2020	0.17 - 2 ft	856.51	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-2-4	1/15/2020	2 - 4 ft	856.51	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-10-12	1/15/2020	10 - 12 ft	856.51	856.63	0.12	10.12-12.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	12 - 14 ft	856.51	856.63	0.12	12.12-14.12 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-4-6	1/15/2020	4 - 6 ft	856.51	856.63	0.12	4.12-6.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-6-8	1/15/2020	6 - 8 ft	856.51	856.63	0.12	6.12-8.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-8-10	1/15/2020	8 - 10 ft	856.51	856.63	0.12	8.12-10.12 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-6-8	1/15/2020	6 - 8 ft	856.74	856.72	-0.02	5.98-7.98 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	0.17 - 2 ft	856.74	856.72	-0.02	0.15-1.98 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-10-12	1/15/2020	10 - 12 ft	856.74	856.72	-0.02	9.98-11.98 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	12 - 14 ft	856.74	856.72	-0.02	11.98-13.98 ft	X	X	-	X	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-2-4	1/15/2020	2 - 4 ft	856.74	856.72	-0.02	1.98-3.98 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-4-6	1/15/2020	4 - 6 ft	856.74	856.72	-0.02	3.98-5.98 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-8-10	1/15/2020	8 - 10 ft	856.74	856.72	-0.02	7.98-9.98 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	0 - 0.17 ft	857.05	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	0 - 0.17 ft	857.55	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	0 - 0.17 ft	856.32	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	0 - 0.17 ft	857.08	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	0 - 0.17 ft	856.36	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	0 - 0.17 ft	856.51	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	0 - 0.17 ft	856.54	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	0 - 0.17 ft	856.74	856.72	-0.02	0-0.15 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	1/23/2020	0 - 0.17 ft	857.44	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	1/23/2020	0 - 0.17 ft	857.46	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	2 - 4 ft	853.19	853.36	0.17	2.17-4.17 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	0 - 0.17 ft	856.85	-	-	-	X	X	X	-	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	0.17 - 2 ft	856.30	-	-	-	X	X	X	X	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	2 - 4 ft	856.30	-	-	-	X	X	X	-	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-4-6	7/27/2020	4 - 6 ft	856.30	-	-	-	X	X	-	-	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-10-12	7/27/2020	10 - 12 ft	856.30	856.31	0.01	10.01-12.01 ft	X	X	-	-	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	12 - 14 ft	856.30	856.31	0.01	12.01-14.01 ft	X	X	-	X	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-6-8	7/27/2020	6 - 8 ft	856.30	856.31	0.01	6.01-8.01 ft	X	X	-	-	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-8-10	7/27/2020	8 - 10 ft	856.30	856.31	0.01	8.01-10.01 ft	X	X	-	-	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	0.17 - 2 ft	856.51	-	-	-	X	X	X	X	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	2 - 4 ft	856.51	-	-	-	X	X	X	-	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	10 - 12 ft	856.51	856.51	0.00	10-12 ft	X	X	X	X	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	12 - 14 ft	856.51	856.51	0.00	12-14 ft	X	X	-	X	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	4 - 6 ft	856.51	856.51	0.00	4-6 ft	X	X	X	X	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-6-8	7/27/2020	6 - 8 ft	856.51	856.51	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B3461	SSHS-B3461-SUB-8-10	7/27/2020	8 - 10 ft	856.51	856.51	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	0.17 - 2 ft	856.28	-	-	-	X	X	X	X	-
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	2 - 4 ft	856.28	-	-	-	X	X	X	X	-
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	4 - 6 ft	856.28	-	-	-	X	X	X	X	-
Football Field	SSHS-B3464	SSHS-B3464-SUB-6-8	7/27/2020	6 - 8 ft	856.28	856.27	-0.01	5.99-7.99 ft	X	X	-	-	-
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	8 - 10 ft	856.28	856.27	-0.01	7.99-9.99 ft	X	X	-	X	-
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	0.17 - 2 ft	855.50	855.50	0.00	0.17-2 ft	X	X	X	X	-
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	2 - 4 ft	855.50	855.50	0.00	2-4 ft	X	X	X	-	-
Football Field	SSHS-B3472	SSHS-B3472-SUB-4-6	7/27/2020	4 - 6 ft	855.50	855.50	0.00	4-6 ft	X	X	-	-	-
Football Field	SSHS-B3472	SSHS-B3472-SUB-6-8	7/27/2020	6 - 8 ft	855.50	855.50	0.00	6-8 ft	X	X	-	-	-
Football Field	SSHS-B3472	SSHS-B3472-SUB-8-10	7/27/2020	8 - 10 ft	855.50	855.50	0.00	8-10 ft	X	X	-	-	-
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	10 - 12 ft	855.50	855.50	0.00	10-12 ft	X	X	-	X	-
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	2 - 4 ft	855.34	-	-	-	X	X	X	X	-
Football Field	SSHS-B3473	DUP15	7/27/2020	0.17 - 2 ft	855.34	-	-	-	X	X	X	X	-
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	0.17 - 2 ft	855.34	-	-	-	X	X	X	X	-
Football Field	SSHS-B3473	SSHS-B3473-SUB-4-6	7/27/2020	4 - 6 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B3473	SSHS-B3473-SUB-6-8	7/27/2020	6 - 8 ft	855.34	855.50	0.16	6.16-8.16 ft	X	X	-	-	-
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	8 - 10 ft	855.34	855.50	0.16	8.16-10.16 ft	X	X	-	X	-
Football Field	SSHS-B3474	SSHS-B3474-SUB-0.17-2	7/27/2020	0.17 - 2 ft	855.64	855.65	0.01	0.18-2.01 ft	X	X	-	-	-
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	2 - 4 ft	855.64	855.65	0.01	2.01-4.01 ft	X	X	X	X	-
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	0.17 - 2 ft	855.34	855.39	0.05	0.22-2.05 ft	X	X	X	X	-
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	2 - 4 ft	855.34	855.39	0.05	2.05-4.05 ft	X	X	X	X	-
Football Field	SSHS-B3476	SSHS-B3476-SUB-0.17-2	7/27/2020	0.17 - 2 ft	855.25	855.45	0.20	0.37-2.2 ft	X	X	-	-	-
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	2 - 4 ft	855.25	855.45	0.20	2.2-4.2 ft	X	X	X	X	-
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	0.17 - 2 ft	855.68	855.71	0.03	0.2-2.03 ft	X	X	X	X	-
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	2 - 4 ft	855.68	855.71	0.03	2.03-4.03 ft	X	X	X	X	-
Football Field	SSHS-B3456	DUP09	7/28/2020	0.17 - 2 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B3456	SSHS-B3456-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	7/28/2020	2 - 4 ft	855.34	-	-	-	X	X	-	-	-
Football Field	SSHS-B3457	SSHS-B3457-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B3457	SSHS-B3457-SUB-2-4	7/28/2020	2 - 4 ft	855.82	-	-	-	X	X	-	-	-
Football Field	SSHS-B3458	SSHS-B3458-SUB-0.17-2	7/28/2020	0.17 - 2 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B3458	DUP10	7/28/2020	2 - 4 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B3458	SSHS-B3458-SUB-2-4	7/28/2020	2 - 4 ft	856.14	-	-	-	X	X	-	-	-
Football Field	SSHS-B3460	SSHS-B3460-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B3460	SSHS-B3460-SUB-2-4	7/28/2020	2 - 4 ft	855.83	-	-	-	X	X	-	-	-
Football Field	SSHS-B3462	DUP11	7/28/2020	0.17 - 2 ft	855.77	-	-	-	X	X	-	-	-
Football Field	SSHS-B3462	SSHS-B3462-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.77	-	-	-	X	X	-	-	-
Football Field	SSHS-B3462	SSHS-B3462-SUB-2-4	7/28/2020	2 - 4 ft	855.77	-	-	-	X	X	-	-	-
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	0.17 - 2 ft	856.64	-	-	-	X	X	X	-	-
Football Field	SSHS-B3463	SSHS-B3463-SUB-2-4	7/28/2020	2 - 4 ft	856.64	-	-	-	X	X	-	-	-
Football Field	SSHS-B3465	SSHS-B3465-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.46	-	-	-	X	X	-	-	-
Football Field	SSHS-B3465	DUP12	7/28/2020	2 - 4 ft	855.46	-	-	-	X	X	-	-	-
Football Field	SSHS-B3465	SSHS-B3465-SUB-2-4	7/28/2020	2 - 4 ft	855.46	-	-	-	X	X	-	-	-
Football Field	SSHS-B3466	SSHS-B3466-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.76	-	-	-	X	X	-	-	-
Football Field	SSHS-B3466	SSHS-B3466-SUB-2-4	7/28/2020	2 - 4 ft	855.76	-	-	-	X	X	-	-	-
Football Field	SSHS-B3467	SSHS-B3467-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.68	-	-	-	X	X	-	-	-
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	2 - 4 ft	855.68	-	-	-	X	X	X	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B3468	SSHS-B3468-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.93	-	-	-	X	X	-	-	-
Football Field	SSHS-B3468	DUP13	7/28/2020	2 - 4 ft	855.93	-	-	-	X	X	-	-	-
Football Field	SSHS-B3468	SSHS-B3468-SUB-2-4	7/28/2020	2 - 4 ft	855.93	-	-	-	X	X	-	-	-
Football Field	SSHS-B3469	SSHS-B3469-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.50	-	-	-	X	X	-	-	-
Football Field	SSHS-B3469	SSHS-B3469-SUB-2-4	7/28/2020	2 - 4 ft	855.50	-	-	-	X	X	-	-	-
Football Field	SSHS-B3470	SSHS-B3470-SUB-0.17-2	7/28/2020	0.17 - 2 ft	855.73	-	-	-	X	X	-	-	-
Football Field	SSHS-B3470	DUP14	7/28/2020	0.17 - 2 ft	855.73	-	-	-	X	X	-	-	-
Football Field	SSHS-B3470	SSHS-B3470-SUB-2-4	7/28/2020	2 - 4 ft	855.73	-	-	-	X	X	-	-	-
Football Field	SSHS-B3471	SSHS-B3471-SUB-0.17-2	7/28/2020	0.17 - 2 ft	856.03	-	-	-	X	X	-	-	-
Football Field	SSHS-B3471	SSHS-B3471-SUB-2-4	7/28/2020	2 - 4 ft	856.03	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	0 - 0.17 ft	858.23	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	0 - 0.17 ft	858.23	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.23	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.23	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0-0.17	7/28/2020	0 - 0.17 ft	858.45	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.45	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0-0.17	7/28/2020	0 - 0.17 ft	858.43	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.43	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0-0.17	7/28/2020	0 - 0.17 ft	858.58	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.58	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0-0.17	7/28/2020	0 - 0.17 ft	856.51	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0.17-2	7/28/2020	0.17 - 2 ft	856.51	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0-0.17	7/28/2020	0 - 0.17 ft	857.00	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0.17-2	7/28/2020	0.17 - 2 ft	857.00	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0-0.17	7/28/2020	0 - 0.17 ft	856.50	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0.17-2	7/28/2020	0.17 - 2 ft	856.50	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0-0.17	7/28/2020	0 - 0.17 ft	858.42	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.42	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3491	SSHS-B3491-SUB-0.17-2	7/28/2020	0.17 - 2 ft	858.35	-	-	-	X	-	-	-	-
Football Field	SSHS-B3473	DUP06	7/30/2020	0.17 - 2 ft	855.34	-	-	-	-	-	-	X	-
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/30/2020	0.17 - 2 ft	855.34	-	-	-	-	-	-	X	-
Football Field	SSHS-B3473	DUP17	7/30/2020	2 - 4 ft	855.34	-	-	-	-	-	-	X	-
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	8/31/2020	2 - 4 ft	855.34	-	-	-	-	X	-	-	-
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	8/31/2020	12 - 14 ft	856.30	856.31	0.01	12.01-14.01 ft	-	X	-	-	-
Football Field	SSHS-B3500	SSHS-B3500-SUB-0.17-2	8/31/2020	0.17 - 2 ft	856.02	856.02	0.00	0.17-2 ft	X	-	-	-	-
Football Field	SSHS-B3501	SSHS-B3501-SUB-0.17-2	8/31/2020	0.17 - 2 ft	855.88	855.90	0.02	0.19-2.02 ft	X	X	-	-	-
Football Field	SSHS-B3502	DUP-16	8/31/2020	4 - 6 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B3502	SSHS-B3502-SUB-4-6	8/31/2020	4 - 6 ft	856.09	-	-	-	-	X	-	-	-
Football Field	SSHS-B3503	SSHS-B3503-SUB-4-6	8/31/2020	4 - 6 ft	856.71	856.71	0.00	4-6 ft	-	X	-	-	-
Football Field	SSHS-B3504	SSHS-B3504-SUB-4-6	8/31/2020	4 - 6 ft	856.71	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3505	SSHS-B3505-SUB-0.17-2	8/31/2020	0.17 - 2 ft	853.31	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3505	SSHS-B3505-SUB-2-4	8/31/2020	2 - 4 ft	853.31	-	-	-	X	-	-	-	-
Football Field	SSHS-B3506	SSHS-B3506-SUB-0.17-2	8/31/2020	0.17 - 2 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B3506	SSHS-B3506-SUB-2-4	8/31/2020	2 - 4 ft	856.17	-	-	-	X	-	-	-	-
Football Field	SSHS-B3507	SSHS-B3507-SUB-0.17-2	8/31/2020	0.17 - 2 ft	855.31	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3508	SSHS-B3508-SUB-0.17-2	8/31/2020	0.17 - 2 ft	856.03	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3508	SSHS-B3508-SUB-2-4	8/31/2020	2 - 4 ft	856.03	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3509	SSHS-B3509-SUB-0.17-2	8/31/2020	0.17 - 2 ft	855.93	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3509	SSHS-B3509-SUB-2-4	8/31/2020	2 - 4 ft	855.93	-	-	-	X	-	-	-	-
Football Field	SSHS-B3510	SSHS-B3510-SUB-0.17-2	8/31/2020	0.17 - 2 ft	855.32	-	-	-	X	-	-	-	-
Football Field	SSHS-B3511	DUP-18	8/31/2020	2 - 4 ft	855.66	-	-	-	X	-	-	-	-
Football Field	SSHS-B3511	SSHS-B3511-SUB-2-4	8/31/2020	2 - 4 ft	855.66	-	-	-	X	-	-	-	-
Football Field	SSHS-B3512	SSHS-B3512-SUB-2-4	8/31/2020	2 - 4 ft	855.72	-	-	-	X	-	-	-	-
Football Field	SSHS-B3526	SSHS-B3526-SUB-0.17-2	9/3/2020	0.17 - 2 ft	855.55	-	-	-	X	-	-	-	-
Football Field	SSHS-B3527	SSHS-B3527-SUB-0.17-2	9/3/2020	0.17 - 2 ft	855.96	-	-	-	X	-	-	-	-
Football Field	SSHS-B3555	DUP-21	1/11/2021	16 - 18 ft	855.30	855.33	0.03	16.03-18.03 ft	X	X	-	X	-
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	16 - 18 ft	855.30	855.33	0.03	16.03-18.03 ft	X	X	-	X	-
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	18 - 20 ft	855.30	855.33	0.03	18.03-20.03 ft	X	X	-	X	-
Football Field	SSHS-B3555	SSHS-B3555-SUB-20-22	1/11/2021	20 - 22 ft	855.30	855.33	0.03	20.03-22.03 ft	X	X	-	-	-
Football Field	SSHS-B3555	SSHS-B3555-SUB-22-24	1/11/2021	22 - 24 ft	855.30	855.33	0.03	22.03-24.03 ft	X	X	-	-	-
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	18 - 20 ft	855.18	855.38	0.20	18.2-20.2 ft	X	X	-	X	-
Football Field	SSHS-B3557	DUP-23	1/11/2021	16 - 18 ft	855.18	855.38	0.20	16.2-18.2 ft	X	X	-	-	-
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	16 - 18 ft	855.18	855.38	0.20	16.2-18.2 ft	X	X	-	X	-
Football Field	SSHS-B3557	SSHS-B3557-SUB-20-22	1/11/2021	20 - 22 ft	855.18	855.38	0.20	20.2-22.2 ft	X	X	-	-	-
Football Field	SSHS-B3557	SSHS-B3557-SUB-22-24	1/11/2021	22 - 24 ft	855.18	855.38	0.20	22.2-24.2 ft	X	X	-	-	-
Football Field	SSHS-B3560	DUP-26	1/11/2021	16 - 18 ft	855.32	855.47	0.15	16.15-18.15 ft	X	X	-	-	-
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	16 - 18 ft	855.32	855.47	0.15	16.15-18.15 ft	X	X	-	X	-
Football Field	SSHS-B3560	SSHS-B3560-SUB-18-20	1/11/2021	18 - 20 ft	855.32	855.47	0.15	18.15-20.15 ft	X	X	-	-	-
Football Field	SSHS-B3560	SSHS-B3560-SUB-20-22	1/11/2021	20 - 22 ft	855.32	855.47	0.15	20.15-22.15 ft	X	X	-	-	-
Football Field	SSHS-B3560	SSHS-B3560-SUB-22-24	1/11/2021	22 - 24 ft	855.32	855.47	0.15	22.15-24.15 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563-SUB-22-24	1/11/2021	22 - 24 ft	855.01	855.38	0.37	22.37-24.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563-SUB-20-22	1/11/2021	20 - 22 ft	855.01	855.38	0.37	20.37-22.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563-SUB-16-18	1/11/2021	16 - 18 ft	855.01	855.38	0.37	16.37-18.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	18 - 20 ft	855.01	855.38	0.37	18.37-20.37 ft	X	X	-	X	-
Football Field	SSHS-B3558	DUP-24	1/12/2021	16 - 18 ft	855.27	855.53	0.26	16.26-18.26 ft	X	X	-	-	-
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	16 - 18 ft	855.27	855.53	0.26	16.26-18.26 ft	X	X	-	X	-
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	18 - 20 ft	855.27	855.53	0.26	18.26-20.26 ft	X	X	-	X	-
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	20 - 22 ft	855.27	855.53	0.26	20.26-22.26 ft	X	X	-	X	-
Football Field	SSHS-B3558	SSHS-B3558-SUB-22-24	1/12/2021	22 - 24 ft	855.27	855.53	0.26	22.26-24.26 ft	X	X	-	-	-
Football Field	SSHS-B3559	DUP-25	1/12/2021	16 - 18 ft	855.35	855.36	0.01	16.01-18.01 ft	X	X	-	-	-
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	16 - 18 ft	855.35	855.36	0.01	16.01-18.01 ft	X	X	-	X	-
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	18 - 20 ft	855.35	855.36	0.01	18.01-20.01 ft	X	X	-	X	-
Football Field	SSHS-B3559	SSHS-B3559-SUB-20-22	1/12/2021	20 - 22 ft	855.35	855.36	0.01	20.01-22.01 ft	X	X	-	-	-
Football Field	SSHS-B3559	SSHS-B3559-SUB-22-24	1/12/2021	22 - 24 ft	855.35	855.36	0.01	22.01-24.01 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564-SUB-16-18	1/12/2021	16 - 18 ft	855.22	855.42	0.20	16.2-18.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	18 - 20 ft	855.22	855.42	0.20	18.2-20.2 ft	X	X	-	X	-
Football Field	SSHS-B3564	SSHS-B3564-SUB-20-22	1/12/2021	20 - 22 ft	855.22	855.42	0.20	20.2-22.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564-SUB-22-24	1/12/2021	22 - 24 ft	855.22	855.42	0.20	22.2-24.2 ft	X	X	-	-	-
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	16 - 18 ft	855.32	855.45	0.13	16.13-18.13 ft	X	X	-	X	-
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	18 - 20 ft	855.32	855.45	0.13	18.13-20.13 ft	X	X	-	X	-
Football Field	SSHS-B3565	SSHS-B3565-SUB-20-22	1/12/2021	20 - 22 ft	855.32	855.45	0.13	20.13-22.13 ft	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-12-14	1/12/2021	12 - 14 ft	855.28	855.43	0.15	12.15-14.15 ft	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-14-16	1/12/2021	14 - 16 ft	855.28	855.43	0.15	14.15-16.15 ft	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-16-18	1/12/2021	16 - 18 ft	855.28	855.43	0.15	16.15-18.15 ft	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	18 - 20 ft	855.28	855.43	0.15	18.15-20.15 ft	X	X	-	X	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-20-22	1/12/2021	20 - 22 ft	855.28	855.43	0.15	20.15-22.15 ft	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-22-24	1/12/2021	22 - 24 ft	855.28	855.43	0.15	22.15-24.15 ft	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-8-10	1/12/2021	8 - 10 ft	855.28	-	-	-	X	X	-	-	-
Football Field	SSHS-B3566	SSHS-B3566-SUB-10-12	1/12/2021	10 - 12 ft	855.28	-	-	-	X	X	-	-	-
Football Field	SSHS-B3567	SSHS-B3567-SUB-12-14	1/12/2021	12 - 14 ft	855.39	855.47	0.08	12.08-14.08 ft	X	X	-	-	-
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	14 - 16 ft	855.39	855.47	0.08	14.08-16.08 ft	X	X	-	X	-
Football Field	SSHS-B3567	SSHS-B3567-SUB-8-10	1/12/2021	8 - 10 ft	855.39	-	-	-	X	X	-	-	-
Football Field	SSHS-B3567	SSHS-B3567-SUB-10-12	1/12/2021	10 - 12 ft	855.39	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3508A	SSHS-B3508-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.03	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3509A	SSHS-B3509-SUB-0.17-2	1/13/2021	0.17 - 2 ft	855.93	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3510A	SSHS-B3510-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3511A	SSHS-B3511-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.97	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3512A	SSHS-B3512-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.63	857.09	0.46	0.63-2.46 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3513	SSHS-B3513-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.86	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3514	SSHS-B3514-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.41	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3515	SSHS-B3515-SUB-0.17-2	1/13/2021	0.17 - 2 ft	856.77	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3520	SSHS-B3520-SUB-2-4	1/13/2021	2 - 4 ft	856.69	-	-	-	-	X	-	-	-
Football Field	SSHS-B3556	DUP-22	1/13/2021	16 - 18 ft	855.33	855.47	0.14	16.14-18.14 ft	X	X	-	-	-
Football Field	SSHS-B3556	SSHS-B3556-SUB-16-18	1/13/2021	16 - 18 ft	855.33	855.47	0.14	16.14-18.14 ft	X	X	-	-	-
Football Field	SSHS-B3556	DUP-29	1/13/2021	18 - 20 ft	855.33	855.47	0.14	18.14-20.14 ft	-	-	-	X	-
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	18 - 20 ft	855.33	855.47	0.14	18.14-20.14 ft	X	X	-	X	-
Football Field	SSHS-B3556	SSHS-B3556-SUB-20-22	1/13/2021	20 - 22 ft	855.33	855.47	0.14	20.14-22.14 ft	X	X	-	-	-
Football Field	SSHS-B3556	SSHS-B3556-SUB-22-24	1/13/2021	22 - 24 ft	855.33	855.47	0.14	22.14-24.14 ft	X	X	-	-	-
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	16 - 18 ft	855.17	855.41	0.24	16.24-18.24 ft	X	X	-	X	-
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	18 - 20 ft	855.17	855.41	0.24	18.24-20.24 ft	X	X	-	X	-
Football Field	SSHS-B3561	SSHS-B3561-SUB-20-22	1/13/2021	20 - 22 ft	855.17	855.41	0.24	20.24-22.24 ft	X	X	-	-	-
Football Field	SSHS-B3561	SSHS-B3561-SUB-22-24	1/13/2021	22 - 24 ft	855.17	855.41	0.24	22.24-24.24 ft	X	X	-	-	-
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	16 - 18 ft	855.07	855.40	0.33	16.33-18.33 ft	X	X	-	X	-
Football Field	SSHS-B3562	SSHS-B3562-SUB-18-20	1/13/2021	18 - 20 ft	855.07	855.40	0.33	18.33-20.33 ft	X	X	-	-	-
Football Field	SSHS-B3562	SSHS-B3562-SUB-20-22	1/13/2021	20 - 22 ft	855.07	855.40	0.33	20.33-22.33 ft	X	X	-	-	-
Football Field	SSHS-B3562	SSHS-B3562-SUB-22-24	1/13/2021	22 - 24 ft	855.07	855.40	0.33	22.33-24.33 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-14-16	1/13/2021	14 - 16 ft	855.01	855.38	0.37	14.37-16.37 ft	X	X	-	-	-
Football Field	SSHS-B3565	SSHS-B3565-SUB-22-24	1/13/2021	22 - 24 ft	855.32	855.45	0.13	22.13-24.13 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0-0.17	1/14/2021	0 - 0.17 ft	858.31	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	1/14/2021	4 - 6 ft	858.31	858.13	-0.18	3.82-5.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0-0.17	1/14/2021	0 - 0.17 ft	858.43	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	1/14/2021	0 - 0.17 ft	858.30	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	4 - 6 ft	858.30	858.61	0.31	4.31-6.31 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0-0.17	1/14/2021	0 - 0.17 ft	858.39	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0-0.17	1/14/2021	0 - 0.17 ft	858.31	-	-	-	-	-	X	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	2 - 4 ft	858.50	858.30	-0.20	1.8-3.8 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B3522A	SSHS-B3522-SUB-8-10	1/14/2021	8 - 10 ft	857.57	857.69	0.12	8.12-10.12 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3523A	SSHS-B3523-SUB-8-10	1/14/2021	8 - 10 ft	858.01	858.02	0.01	8.01-10.01 ft	-	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-24-26	1/14/2021	24 - 26 ft	855.01	855.38	0.37	24.37-26.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-26-28	1/14/2021	26 - 28 ft	855.01	855.38	0.37	26.37-28.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-28-30	1/14/2021	28 - 30 ft	855.01	855.38	0.37	28.37-30.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-34-36	1/14/2021	34 - 36 ft	855.01	855.38	0.37	34.37-36.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-30-32	1/14/2021	30 - 32 ft	855.01	855.38	0.37	30.37-32.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-32-34	1/14/2021	32 - 34 ft	855.01	855.38	0.37	32.37-34.37 ft	X	X	-	-	-
Football Field	SSHS-B3563	SSHS-B3563A-SUB-36-37	1/15/2021	36 - 37 ft	855.01	855.38	0.37	36.37-37.37 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-24-26	1/15/2021	24 - 26 ft	855.22	855.42	0.20	24.2-26.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-36-37	1/15/2021	36 - 37 ft	855.22	855.42	0.20	36.2-37.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-32-34	1/15/2021	32 - 34 ft	855.22	855.42	0.20	32.2-34.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-26-28	1/15/2021	26 - 28 ft	855.22	855.42	0.20	26.2-28.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-28-30	1/15/2021	28 - 30 ft	855.22	855.42	0.20	28.2-30.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-30-32	1/15/2021	30 - 32 ft	855.22	855.42	0.20	30.2-32.2 ft	X	X	-	-	-
Football Field	SSHS-B3564	SSHS-B3564A-SUB-34-36	1/15/2021	34 - 36 ft	855.22	855.42	0.20	34.2-36.2 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	16 - 18 ft	855.08	855.49	0.41	16.41-18.41 ft	X	X	-	X	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	18 - 20 ft	855.08	855.49	0.41	18.41-20.41 ft	X	X	-	X	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-20-22	1/18/2021	20 - 22 ft	855.08	855.49	0.41	20.41-22.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-22-24	1/18/2021	22 - 24 ft	855.08	855.49	0.41	22.41-24.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-24-26	1/18/2021	24 - 26 ft	855.08	855.49	0.41	24.41-26.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-26-28	1/18/2021	26 - 28 ft	855.08	855.49	0.41	26.41-28.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-28-30	1/18/2021	28 - 30 ft	855.08	855.49	0.41	28.41-30.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-30-32	1/18/2021	30 - 32 ft	855.08	855.49	0.41	30.41-32.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	DUP-30	1/18/2021	32 - 34 ft	855.08	855.49	0.41	32.41-34.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-32-34	1/18/2021	32 - 34 ft	855.08	855.49	0.41	32.41-34.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	DUP-31	1/18/2021	34 - 35 ft	855.08	855.49	0.41	34.41-35.41 ft	X	X	-	-	-
Football Field	SSHS-B3568	SSHS-B3568-SUB-34-35	1/18/2021	34 - 36 ft	855.08	855.49	0.41	34.41-36.41 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-16-18	1/18/2021	16 - 18 ft	855.21	855.30	0.09	16.09-18.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-18-20	1/18/2021	18 - 20 ft	855.21	855.30	0.09	18.09-20.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-20-22	1/18/2021	20 - 22 ft	855.21	855.30	0.09	20.09-22.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-22-24	1/18/2021	22 - 24 ft	855.21	855.30	0.09	22.09-24.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-24-26	1/18/2021	24 - 26 ft	855.21	855.30	0.09	24.09-26.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-26-28	1/18/2021	26 - 28 ft	855.21	855.30	0.09	26.09-28.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-28-30	1/18/2021	28 - 30 ft	855.21	855.30	0.09	28.09-30.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-30-32	1/18/2021	30 - 32 ft	855.21	855.30	0.09	30.09-32.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	DUP-35	1/18/2021	32 - 34 ft	855.21	855.30	0.09	32.09-34.09 ft	X	X	-	-	-
Football Field	SSHS-B3571	SSHS-B3571-SUB-32-34	1/18/2021	32 - 34 ft	855.21	855.30	0.09	32.09-34.09 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-16-18	1/19/2021	16 - 18 ft	855.07	855.22	0.15	16.15-18.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	18 - 20 ft	855.07	855.22	0.15	18.15-20.15 ft	X	X	-	X	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-20-22	1/19/2021	20 - 22 ft	855.07	855.22	0.15	20.15-22.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-22-24	1/19/2021	22 - 24 ft	855.07	855.22	0.15	22.15-24.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-24-26	1/19/2021	24 - 26 ft	855.07	855.22	0.15	24.15-26.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-26-28	1/19/2021	26 - 28 ft	855.07	855.22	0.15	26.15-28.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-28-30	1/19/2021	28 - 30 ft	855.07	855.22	0.15	28.15-30.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-30-32	1/19/2021	30 - 32 ft	855.07	855.22	0.15	30.15-32.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	DUP-32	1/19/2021	32 - 34 ft	855.07	855.22	0.15	32.15-34.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	SSHS-B3569-SUB-32-34	1/19/2021	32 - 34 ft	855.07	855.22	0.15	32.15-34.15 ft	X	X	-	-	-
Football Field	SSHS-B3569	DUP-33	1/19/2021	34 - 36 ft	855.07	855.22	0.15	34.15-36.15 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-16-18	1/19/2021	16 - 18 ft	855.27	855.46	0.19	16.19-18.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	18 - 20 ft	855.27	855.46	0.19	18.19-20.19 ft	X	X	-	X	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	20 - 22 ft	855.27	855.46	0.19	20.19-22.19 ft	X	X	-	X	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-22-24	1/19/2021	22 - 24 ft	855.27	855.46	0.19	22.19-24.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-24-26	1/19/2021	24 - 26 ft	855.27	855.46	0.19	24.19-26.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-26-28	1/19/2021	26 - 28 ft	855.27	855.46	0.19	26.19-28.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-28-30	1/19/2021	28 - 30 ft	855.27	855.46	0.19	28.19-30.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-30-32	1/19/2021	30 - 32 ft	855.27	855.46	0.19	30.19-32.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	DUP-34	1/19/2021	32 - 34 ft	855.27	855.46	0.19	32.19-34.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-32-34	1/19/2021	32 - 34 ft	855.27	855.46	0.19	32.19-34.19 ft	X	X	-	-	-
Football Field	SSHS-B3570	SSHS-B3570-SUB-34-35	1/19/2021	34 - 36 ft	855.27	855.46	0.19	34.19-36.19 ft	X	X	-	-	-
Football Field	SSHS-B3571	DUP-35	1/19/2021	32 - 34 ft	855.21	855.30	0.09	32.09-34.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3554	DUP-12	1/20/2021	8 - 10 ft	854.07	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-0.17-2	1/20/2021	0.17 - 2 ft	854.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-2-4	1/20/2021	2 - 4 ft	854.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-4-6	1/20/2021	4 - 6 ft	854.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-6-8	1/20/2021	6 - 8 ft	854.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	8 - 10 ft	854.07	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	10 - 12 ft	854.07	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	12 - 14 ft	854.07	857.79	3.72	15.72-17.72 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	14 - 16 ft	854.07	857.79	3.72	17.72-19.72 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	16 - 18 ft	854.07	857.79	3.72	19.72-21.72 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-18-20	1/20/2021	18 - 20 ft	854.07	857.79	3.72	21.72-23.72 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-20-22	1/20/2021	20 - 22 ft	854.07	857.79	3.72	23.72-25.72 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-22-23	1/20/2021	22 - 23 ft	854.07	857.79	3.72	25.72-26.72 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	16 - 18 ft	854.31	857.51	3.20	19.2-21.2 ft	X	-	-	X	-
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-18-20	1/21/2021	18 - 20 ft	854.31	857.51	3.20	21.2-23.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-20-22	1/21/2021	20 - 22 ft	854.31	857.51	3.20	23.2-25.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-22-24	1/21/2021	22 - 24 ft	854.31	857.51	3.20	25.2-27.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-10-12	1/21/2021	10 - 12 ft	853.76	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-16-18	1/21/2021	16 - 18 ft	853.76	857.23	3.47	19.47-21.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-20-22	1/21/2021	20 - 22 ft	853.76	857.23	3.47	23.47-25.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-18-20	1/21/2021	18 - 20 ft	853.76	857.23	3.47	21.47-23.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-10-12	1/21/2021	10 - 12 ft	854.61	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-12-14	1/21/2021	12 - 14 ft	854.61	858.08	3.47	15.47-17.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-14-16	1/21/2021	14 - 16 ft	854.61	858.08	3.47	17.47-19.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-16-18	1/21/2021	16 - 18 ft	854.61	858.08	3.47	19.47-21.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3503A	SSHS-B3503-SUB-0.17-2	1/21/2021	0.17 - 2 ft	854.30	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	8 - 10 ft	854.14	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	10 - 12 ft	853.65	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-18-20	1/22/2021	18 - 20 ft	854.61	858.08	3.47	21.47-23.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-20-22	1/22/2021	20 - 22 ft	854.61	858.08	3.47	23.47-25.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-0.17-2	1/22/2021	0.17 - 2 ft	854.14	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-2-4	1/22/2021	2 - 4 ft	854.14	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-4-6	1/22/2021	4 - 6 ft	854.14	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-6-8	1/22/2021	6 - 8 ft	854.14	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	8 - 10 ft	854.14	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	10 - 12 ft	854.14	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	18 - 20 ft	854.14	857.83	3.69	21.69-23.69 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-20-22	1/22/2021	20 - 22 ft	854.14	857.83	3.69	23.69-25.69 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	16 - 18 ft	854.14	857.83	3.69	19.69-21.69 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	10 - 12 ft	853.65	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	12 - 14 ft	853.65	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	14 - 16 ft	853.65	857.32	3.67	17.67-19.67 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	16 - 18 ft	853.65	857.32	3.67	19.67-21.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	18 - 20 ft	853.65	857.32	3.67	21.67-23.67 ft	X	-	-	X	-
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	20 - 22 ft	853.65	857.32	3.67	23.67-25.67 ft	X	-	-	X	-
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	22 - 24 ft	853.65	857.32	3.67	25.67-27.67 ft	X	-	-	X	-
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	22 - 24 ft	853.65	857.32	3.67	25.67-27.67 ft	X	-	-	X	-
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	2 - 4 ft	856.72	856.88	0.16	2.16-4.16 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	4 - 6 ft	856.72	856.88	0.16	4.16-6.16 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	10 - 12 ft	853.60	-	-	-	X	X	X	-	X
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	2 - 4 ft	856.06	857.63	1.57	3.57-5.57 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	4 - 6 ft	856.06	857.63	1.57	5.57-7.57 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	2 - 4 ft	856.76	856.63	-0.13	1.87-3.87 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	4 - 6 ft	856.76	856.63	-0.13	3.87-5.87 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-14-16	1/23/2021	14 - 16 ft	853.86	856.33	2.47	16.47-18.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-10-12	1/23/2021	10 - 12 ft	853.86	856.33	2.47	12.47-14.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-12-14	1/23/2021	12 - 14 ft	853.86	856.33	2.47	14.47-16.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-16-18	1/23/2021	16 - 18 ft	853.86	856.33	2.47	18.47-20.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-18-20	1/23/2021	18 - 20 ft	853.86	856.33	2.47	20.47-22.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-20-22	1/23/2021	20 - 22 ft	853.86	856.33	2.47	22.47-24.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-22-24	1/23/2021	22 - 24 ft	853.86	856.33	2.47	24.47-26.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-0.17-2	1/23/2021	0.17 - 2 ft	853.98	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-2-4	1/23/2021	2 - 4 ft	853.98	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-0.17-2	1/23/2021	0.17 - 2 ft	853.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-2-4	1/23/2021	2 - 4 ft	853.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3623	SSHS-B3623-SUB-2-4	1/23/2021	2 - 4 ft	855.47	858.93	3.46	5.46-7.46 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3623	SSHS-B3623-SUB-0.17-2	1/23/2021	0.17 - 2 ft	855.47	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3624	SSHS-B3624-SUB-2-4	1/23/2021	2 - 4 ft	855.26	858.01	2.75	4.75-6.75 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3624	SSHS-B3624-SUB-0.17-2	1/23/2021	0.17 - 2 ft	855.26	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-0.17-2	1/23/2021	0.17 - 2 ft	855.69	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-2-4	1/23/2021	2 - 4 ft	855.69	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-0.17-2	1/23/2021	0.17 - 2 ft	857.05	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-2-4	1/23/2021	2 - 4 ft	857.05	-	-	-	-	-	X	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	10 - 12 ft	853.60	-	-	-	X	X	X	-	X
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	12 - 14 ft	853.60	-	-	-	X	X	X	-	X
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-14-16	1/23/2021	14 - 16 ft	853.60	855.95	2.35	16.35-18.35 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	16 - 18 ft	853.60	855.95	2.35	18.35-20.35 ft	X	X	X	-	X
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-18-20	1/23/2021	18 - 20 ft	853.60	855.95	2.35	20.35-22.35 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-20-22	1/23/2021	20 - 22 ft	853.60	855.95	2.35	22.35-24.35 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-22-24	1/23/2021	22 - 24 ft	853.60	855.95	2.35	24.35-26.35 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	2 - 4 ft	853.34	853.48	0.14	2.14-4.14 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-2-4	1/25/2021	2 - 4 ft	855.59	855.55	-0.04	1.96-3.96 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-4-6	1/25/2021	4 - 6 ft	855.59	855.55	-0.04	3.96-5.96 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-2-4	1/25/2021	2 - 4 ft	857.70	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-4-6	1/25/2021	4 - 6 ft	857.70	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	2 - 4 ft	856.35	856.68	0.33	2.33-4.33 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	4 - 6 ft	856.35	856.68	0.33	4.33-6.33 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3500A	SSHS-B3500-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.38	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3500A	SSHS-B3500-SUB-2-4	1/25/2021	2 - 4 ft	855.38	855.47	0.09	2.09-4.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3501A	SSHS-B3501-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.77	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3501A	SSHS-B3501-SUB-2-4	1/25/2021	2 - 4 ft	855.77	855.89	0.12	2.12-4.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.86	-	-	-	X	X	-	-	-
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-2-4	1/25/2021	2 - 4 ft	855.86	857.66	1.80	3.8-5.8 ft	X	X	-	-	-
Northern Athletic Field	SSHS-B3516	SSHS-B3516-SUB-2-4	1/25/2021	2 - 4 ft	856.33	856.96	0.63	2.63-4.63 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3516	SSHS-B3516-SUB-4-6	1/25/2021	4 - 6 ft	856.33	856.96	0.63	4.63-6.63 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3521	SSHS-B3521-SUB-6-8	1/25/2021	6 - 8 ft	855.79	855.68	-0.11	5.89-7.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3521	SSHS-B3521-SUB-8-10	1/25/2021	8 - 10 ft	855.79	855.68	-0.11	7.89-9.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3603	SSHS-B3603-SUB-2-4	1/25/2021	2 - 4 ft	855.89	855.73	-0.16	1.84-3.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3603	SSHS-B3603-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.89	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3604	SSHS-B3604-SUB-2-4	1/25/2021	2 - 4 ft	855.40	855.57	0.17	2.17-4.17 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3604	SSHS-B3604-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.40	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3605	SSHS-B3605-SUB-2-4	1/25/2021	2 - 4 ft	855.99	856.05	0.06	2.06-4.06 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3605	SSHS-B3605-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.99	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3606	SSHS-B3606-SUB-2-4	1/25/2021	2 - 4 ft	855.37	855.65	0.28	2.28-4.28 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3606	SSHS-B3606-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.37	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3607	SSHS-B3607-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.19	857.92	2.73	2.9-4.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3607	SSHS-B3607-SUB-2-4	1/25/2021	2 - 4 ft	855.19	857.92	2.73	4.73-6.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3608	SSHS-B3608-SUB-2-4	1/25/2021	2 - 4 ft	856.10	855.95	-0.15	1.85-3.85 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3608	SSHS-B3608-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.10	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3609	SSHS-B3609-SUB-2-4	1/25/2021	2 - 4 ft	855.67	858.61	2.94	4.94-6.94 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3609	SSHS-B3609-SUB-0.17-2	1/25/2021	0.17 - 2 ft	855.67	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3610	SSHS-B3610-SUB-2-4	1/25/2021	2 - 4 ft	856.08	856.39	0.31	2.31-4.31 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3610	SSHS-B3610-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.08	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3611	SSHS-B3611-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.16	858.07	1.91	2.08-3.91 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3611	SSHS-B3611-SUB-2-4	1/25/2021	2 - 4 ft	856.16	858.07	1.91	3.91-5.91 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3612	SSHS-B3612-SUB-2-4	1/25/2021	2 - 4 ft	856.56	857.03	0.47	2.47-4.47 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3612	SSHS-B3612-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.56	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	2 - 4 ft	856.82	857.09	0.27	2.27-4.27 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.82	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-0.17-2	1/25/2021	0.17 - 2 ft	857.48	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-2-4	1/25/2021	2 - 4 ft	857.48	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	2 - 4 ft	857.88	857.61	-0.27	1.73-3.73 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-0.17-2	1/25/2021	0.17 - 2 ft	857.88	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	2 - 4 ft	858.03	857.85	-0.18	1.82-3.82 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-0.17-2	1/25/2021	0.17 - 2 ft	858.03	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3617	SSHS-B3617-SUB-2-4	1/25/2021	2 - 4 ft	856.07	856.84	0.77	2.77-4.77 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3617	SSHS-B3617-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3618	SSHS-B3618-SUB-2-4	1/25/2021	2 - 4 ft	856.15	857.13	0.98	2.98-4.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3618	SSHS-B3618-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.15	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3619	SSHS-B3619-SUB-2-4	1/25/2021	2 - 4 ft	856.42	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3619	SSHS-B3619-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.42	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	2 - 4 ft	856.26	856.45	0.19	2.19-4.19 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.26	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3621	SSHS-B3621-SUB-2-4	1/25/2021	2 - 4 ft	856.33	856.42	0.09	2.09-4.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3621	SSHS-B3621-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.33	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3622	SSHS-B3622-SUB-2-4	1/25/2021	2 - 4 ft	856.17	858.35	2.18	4.18-6.18 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3622	SSHS-B3622-SUB-0.17-2	1/25/2021	0.17 - 2 ft	856.17	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3631	SSHS-B3631-SUB-4-6	1/25/2021	4 - 6 ft	856.31	857.24	0.93	4.93-6.93 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3631	SSHS-B3631-SUB-2-4	1/25/2021	2 - 4 ft	856.31	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	2 - 4 ft	853.34	853.48	0.14	2.14-4.14 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	4 - 6 ft	853.34	853.48	0.14	4.14-6.14 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	2 - 4 ft	857.57	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	2 - 4 ft	857.57	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6	1/26/2021	4 - 6 ft	857.57	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	2 - 4 ft	857.46	857.78	0.32	2.32-4.32 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	2 - 4 ft	857.46	857.78	0.32	2.32-4.32 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	4 - 6 ft	857.46	857.78	0.32	4.32-6.32 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	4 - 6 ft	857.46	857.78	0.32	4.32-6.32 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	2 - 4 ft	858.35	858.41	0.06	2.06-4.06 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	4 - 6 ft	858.35	858.41	0.06	4.06-6.06 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3247A	SSHS-B3247A-SUB-10-12	1/26/2021	10 - 12 ft	857.58	857.70	0.12	10.12-12.12 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3247A	SSHS-B3247A-SUB-12-14	1/26/2021	12 - 14 ft	857.58	857.70	0.12	12.12-14.12 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	4 - 6 ft	858.55	858.46	-0.09	3.91-5.91 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	6 - 8 ft	858.55	858.46	-0.09	5.91-7.91 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	2 - 4 ft	858.11	858.22	0.11	2.11-4.11 ft	X	-	X	-	-
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	2 - 4 ft	858.11	858.22	0.11	2.11-4.11 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	4 - 6 ft	858.11	858.22	0.11	4.11-6.11 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	2 - 4 ft	858.42	858.49	0.07	2.07-4.07 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	4 - 6 ft	858.42	858.49	0.07	4.07-6.07 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	2 - 4 ft	858.46	858.46	0.00	2-4 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	4 - 6 ft	858.46	858.46	0.00	4-6 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.35	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-2-4	1/26/2021	2 - 4 ft	858.35	858.44	0.09	2.09-4.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-4-6	1/26/2021	4 - 6 ft	858.35	858.44	0.09	4.09-6.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	0.17 - 2 ft	858.31	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.31	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	2 - 4 ft	858.31	858.13	-0.18	1.82-3.82 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.43	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.30	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	2 - 4 ft	858.30	858.61	0.31	2.31-4.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.46	858.50	0.04	0.21-2.04 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	2 - 4 ft	858.46	858.50	0.04	2.04-4.04 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	4 - 6 ft	858.46	858.50	0.04	4.04-6.04 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.39	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	2 - 4 ft	858.39	858.21	-0.18	1.82-3.82 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	4 - 6 ft	858.39	858.21	-0.18	3.82-5.82 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.31	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	2 - 4 ft	858.31	858.56	0.25	2.25-4.25 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	4 - 6 ft	858.31	858.56	0.25	4.25-6.25 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-0.17-2	1/26/2021	0.17 - 2 ft	857.28	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-2-4	1/26/2021	2 - 4 ft	857.28	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-2-4	1/26/2021	2 - 4 ft	856.64	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-4-6	1/26/2021	4 - 6 ft	856.64	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3594	DUP-13	1/26/2021	0.17 - 2 ft	858.38	-	-	-	X	-	X	-	-
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	0.17 - 2 ft	858.38	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	2 - 4 ft	858.38	858.34	-0.04	1.96-3.96 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	4 - 6 ft	858.38	858.34	-0.04	3.96-5.96 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3634	SSHS-B3634-SUB-6-8	1/26/2021	6 - 8 ft	857.44	857.49	0.05	6.05-8.05 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3634	SSHS-B3634-SUB-8-10	1/26/2021	8 - 10 ft	857.44	857.49	0.05	8.05-10.05 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3635	SSHS-B3635-SUB-6-8	1/26/2021	6 - 8 ft	857.87	857.72	-0.15	5.85-7.85 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3635	SSHS-B3635-SUB-8-10	1/26/2021	8 - 10 ft	857.87	857.72	-0.15	7.85-9.85 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3636	SSHS-B3636-SUB-6-8	1/26/2021	6 - 8 ft	857.79	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3636	SSHS-B3636-SUB-8-10	1/26/2021	8 - 10 ft	857.79	857.79	0.00	8-10 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3637	SSHS-B3637-SUB-10-12	1/26/2021	10 - 12 ft	857.63	857.60	-0.03	9.97-11.97 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3637	SSHS-B3637-SUB-8-10	1/26/2021	8 - 10 ft	857.63	857.60	-0.03	7.97-9.97 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3638	SSHS-B3638-SUB-10-12	1/26/2021	10 - 12 ft	857.95	857.95	0.00	10-12 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3638	SSHS-B3638-SUB-8-10	1/26/2021	8 - 10 ft	857.95	857.95	0.00	8-10 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-2-4	1/27/2021	2 - 4 ft	857.02	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-4-6	1/27/2021	4 - 6 ft	857.02	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	2 - 4 ft	857.14	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6	1/27/2021	4 - 6 ft	857.14	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	2 - 4 ft	857.14	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-2-4	1/27/2021	2 - 4 ft	855.96	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	4 - 6 ft	855.96	857.03	1.07	5.07-7.07 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-2-4	1/27/2021	2 - 4 ft	854.73	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	4 - 6 ft	856.41	855.18	-1.23	2.77-4.77 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	6 - 8 ft	856.41	855.18	-1.23	4.77-6.77 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-4-6	1/27/2021	4 - 6 ft	857.13	-	-	-	-	-	X	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-6-8	1/27/2021	6 - 8 ft	857.13	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-2-4	1/27/2021	2 - 4 ft	856.72	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	4 - 6 ft	856.72	854.93	-1.79	2.21-4.21 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-0.17-2	1/27/2021	0.17 - 2 ft	855.81	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-2-4	1/27/2021	2 - 4 ft	855.81	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-2-4	1/27/2021	2 - 4 ft	857.15	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-4-6	1/27/2021	4 - 6 ft	857.15	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3632	SSHS-B3632-SUB-2-4	1/27/2021	2 - 4 ft	856.69	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3632	SSHS-B3632-SUB-4-6	1/27/2021	4 - 6 ft	856.69	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3633	SSHS-B3633-SUB-2-4	1/27/2021	2 - 4 ft	856.94	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3633	SSHS-B3633-SUB-4-6	1/27/2021	4 - 6 ft	856.94	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-0.17-2	1/27/2021	0.17 - 2 ft	856.65	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-2-4	1/27/2021	2 - 4 ft	856.65	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-0.17-2	1/27/2021	0.17 - 2 ft	856.99	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-2-4	1/27/2021	2 - 4 ft	856.99	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3600	SSHS-B3600-SUB-16-18	1/28/2021	16 - 18 ft	851.93	853.96	2.03	18.03-20.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3600	SSHS-B3600-SUB-18-20	1/28/2021	18 - 20 ft	851.93	853.96	2.03	20.03-22.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3601	SSHS-B3601-SUB-16-18	1/28/2021	16 - 18 ft	852.55	855.03	2.48	18.48-20.48 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3601	SSHS-B3601-SUB-18-20	1/28/2021	18 - 20 ft	852.55	855.03	2.48	20.48-22.48 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	12 - 14 ft	851.94	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	12 - 14 ft	851.94	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	12 - 14 ft	852.33	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-18-20	1/28/2021	18 - 20 ft	852.44	854.81	2.37	20.37-22.37 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	4 - 6 ft	856.89	856.18	-0.71	3.29-5.29 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	6 - 8 ft	856.89	856.18	-0.71	5.29-7.29 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-0.17-2	1/29/2021	0.17 - 2 ft	856.79	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-0.17-2	1/29/2021	0.17 - 2 ft	856.79	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-2-4	1/29/2021	2 - 4 ft	856.79	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-2-4	1/29/2021	2 - 4 ft	856.79	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3647	SSHS-B3647-SUB-0.17-2	1/29/2021	0.17 - 2 ft	856.70	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3647	SSHS-B3647-SUB-2-4	1/29/2021	2 - 4 ft	856.70	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3648	SSHS-B3648-SUB-0.17-2	1/29/2021	0.17 - 2 ft	856.51	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3648	SSHS-B3648-SUB-2-4	1/29/2021	2 - 4 ft	856.51	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3649	SSHS-B3649-SUB-0.17-2	1/29/2021	0.17 - 2 ft	856.47	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3649	SSHS-B3649-SUB-2-4	1/29/2021	2 - 4 ft	856.47	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3649	SSHS-B3649-SUB-2-4	1/29/2021	2 - 4 ft	856.47	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-0.17-2	1/29/2021	0.17 - 2 ft	856.95	-	-	-	-	X	-	-	-
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	2 - 4 ft	856.95	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/1/2021	0.17 - 2 ft	856.70	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-2-4	2/1/2021	2 - 4 ft	856.70	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-0.17-2	2/1/2021	0.17 - 2 ft	856.45	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-2-4	2/1/2021	2 - 4 ft	856.45	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-20-22	2/1/2021	20 - 22 ft	852.44	854.81	2.37	22.37-24.37 ft	X	-	-	-	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-2-4	2/2/2021	2 - 4 ft	854.85	-	-	-	-	-	-	X	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-10-12	2/2/2021	10 - 12 ft	854.85	855.40	0.55	10.55-12.55 ft	-	-	-	X	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-12-14	2/2/2021	12 - 14 ft	854.85	855.40	0.55	12.55-14.55 ft	-	-	-	X	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-14-16	2/2/2021	14 - 16 ft	854.85	855.40	0.55	14.55-16.55 ft	-	-	-	X	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-4-6	2/2/2021	4 - 6 ft	854.85	855.40	0.55	4.55-6.55 ft	-	-	-	X	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-6-8	2/2/2021	6 - 8 ft	854.85	855.40	0.55	6.55-8.55 ft	-	-	-	X	-
Football Field	SSHS-B3575	SSHS-B3575-SUB-8-10	2/2/2021	8 - 10 ft	854.85	855.40	0.55	8.55-10.55 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-2-4	2/2/2021	2 - 4 ft	856.66	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-0.17-2	2/2/2021	0.17 - 2 ft	856.10	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-2-4	2/2/2021	2 - 4 ft	856.10	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	10 - 12 ft	851.67	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	12 - 14 ft	851.67	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	14 - 16 ft	851.67	-	-	-	X	X	X	-	-
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	0.17 - 2 ft	856.82	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-2-4	2/2/2021	2 - 4 ft	856.82	-	-	-	-	X	-	-	-
Football Field	SSHS-B3573	SSHS-B3573-SUB-2-4	2/3/2021	2 - 4 ft	855.66	-	-	-	-	-	-	X	-
Football Field	SSHS-B3573	DUP-28	2/3/2021	10 - 12 ft	855.66	855.66	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3573	SSHS-B3573-SUB-10-12	2/3/2021	10 - 12 ft	855.66	855.66	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3573	SSHS-B3573-SUB-12-14	2/3/2021	12 - 14 ft	855.66	855.66	0.00	12-14 ft	-	-	-	X	-
Football Field	SSHS-B3573	SSHS-B3573-SUB-4-6	2/3/2021	4 - 6 ft	855.66	855.66	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3573	SSHS-B3573-SUB-6-8	2/3/2021	6 - 8 ft	855.66	855.66	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B3573	SSHS-B3573-SUB-8-10	2/3/2021	8 - 10 ft	855.66	855.66	0.00	8-10 ft	-	-	-	X	-
Football Field	SSHS-B3574	SSHS-B3574-SUB-2-4	2/3/2021	2 - 4 ft	855.72	-	-	-	-	-	-	X	-
Football Field	SSHS-B3574	SSHS-B3574-SUB-4-6	2/3/2021	4 - 6 ft	855.72	-	-	-	-	-	-	X	-
Football Field	SSHS-B3574	SSHS-B3574-SUB-10-12	2/3/2021	10 - 12 ft	855.72	855.72	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3574	SSHS-B3574-SUB-12-14	2/3/2021	12 - 14 ft	855.72	855.72	0.00	12-14 ft	-	-	-	X	-
Football Field	SSHS-B3574	SSHS-B3574-SUB-6-8	2/3/2021	6 - 8 ft	855.72	855.72	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B3574	SSHS-B3574-SUB-8-10	2/3/2021	8 - 10 ft	855.72	855.72	0.00	8-10 ft	-	-	-	X	-
Football Field	SSHS-B3576	SSHS-B3576-SUB-2-4	2/3/2021	2 - 4 ft	855.76	-	-	-	-	-	-	X	-
Football Field	SSHS-B3576	SSHS-B3576-SUB-10-12	2/3/2021	10 - 12 ft	855.76	855.76	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3576	SSHS-B3576-SUB-12-14	2/3/2021	12 - 14 ft	855.76	855.76	0.00	12-14 ft	-	-	-	X	-
Football Field	SSHS-B3576	DUP-27	2/3/2021	4 - 6 ft	855.76	855.76	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3576	SSHS-B3576-SUB-4-6	2/3/2021	4 - 6 ft	855.76	855.76	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3576	SSHS-B3576-SUB-6-8	2/3/2021	6 - 8 ft	855.76	855.76	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B3576	SSHS-B3576-SUB-8-10	2/3/2021	8 - 10 ft	855.76	855.76	0.00	8-10 ft	-	-	-	X	-
Football Field	SSHS-B3578	SSHS-B3578-SUB-2-4	2/3/2021	2 - 4 ft	855.72	-	-	-	-	-	-	X	-
Football Field	SSHS-B3578	SSHS-B3578-SUB-10-12	2/3/2021	10 - 12 ft	855.72	855.72	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3578	SSHS-B3578-SUB-12-14	2/3/2021	12 - 14 ft	855.72	855.72	0.00	12-14 ft	-	-	-	X	-
Football Field	SSHS-B3578	SSHS-B3578-SUB-4-6	2/3/2021	4 - 6 ft	855.72	855.72	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3578	SSHS-B3578-SUB-6-8	2/3/2021	6 - 8 ft	855.72	855.72	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B3578	DUP-29	2/3/2021	8 - 10 ft	855.72	855.72	0.00	8-10 ft	-	-	-	X	-
Football Field	SSHS-B3578	SSHS-B3578-SUB-8-10	2/3/2021	8 - 10 ft	855.72	855.72	0.00	8-10 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	4 - 6 ft	856.66	856.50	-0.16	3.84-5.84 ft	-	-	X	-	-
Football Field	SSHS-B3572	SSHS-B3572-SUB-10-12	2/4/2021	10 - 12 ft	855.42	855.51	0.09	10.09-12.09 ft	-	-	-	X	-
Football Field	SSHS-B3572	SSHS-B3572-SUB-12-14	2/4/2021	12 - 14 ft	855.42	855.51	0.09	12.09-14.09 ft	-	-	-	X	-
Football Field	SSHS-B3572	SSHS-B3572-SUB-2-4	2/4/2021	2 - 4 ft	855.42	855.51	0.09	2.09-4.09 ft	-	-	-	X	-
Football Field	SSHS-B3572	SSHS-B3572-SUB-4-6	2/4/2021	4 - 6 ft	855.42	855.51	0.09	4.09-6.09 ft	-	-	-	X	-
Football Field	SSHS-B3572	DUP-30	2/4/2021	6 - 8 ft	855.42	855.51	0.09	6.09-8.09 ft	-	-	-	X	-
Football Field	SSHS-B3572	SSHS-B3572-SUB-6-8	2/4/2021	6 - 8 ft	855.42	855.51	0.09	6.09-8.09 ft	-	-	-	X	-
Football Field	SSHS-B3572	SSHS-B3572-SUB-8-10	2/4/2021	8 - 10 ft	855.42	855.51	0.09	8.09-10.09 ft	-	-	-	X	-
Football Field	SSHS-B3593	SSHS-B3593-SUB-2-4	2/4/2021	2 - 4 ft	854.95	855.33	0.38	2.38-4.38 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/4/2021	0.17 - 2 ft	856.70	-	-	-	-	-	-	X	-
Football Field	SSHS-B3596	DUP-37	2/4/2021	0.17 - 2 ft	855.23	-	-	-	-	-	-	X	-
Football Field	SSHS-B3596	SSHS-B3596-SUB-0.17-2	2/4/2021	0.17 - 2 ft	855.23	-	-	-	-	-	-	X	-
Football Field	SSHS-B3597	SSHS-B3597-SUB-0.17-2	2/4/2021	0.17 - 2 ft	855.28	-	-	-	-	-	-	X	-
Football Field	SSHS-B3598	SSHS-B3598-SUB-2-4	2/4/2021	2 - 4 ft	854.90	-	-	-	-	-	-	X	-
Football Field	SSHS-B3599	DUP-38	2/4/2021	2 - 4 ft	855.25	-	-	-	-	-	-	X	-
Football Field	SSHS-B3599	SSHS-B3599-SUB-2-4	2/4/2021	2 - 4 ft	855.25	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-10-12	2/5/2021	10 - 12 ft	856.15	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-12-14	2/5/2021	12 - 14 ft	856.15	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-2-4	2/5/2021	2 - 4 ft	856.15	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-4-6	2/5/2021	4 - 6 ft	856.15	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-6-8	2/5/2021	6 - 8 ft	856.15	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-8-10	2/5/2021	8 - 10 ft	856.15	-	-	-	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-14-16	2/5/2021	14 - 16 ft	856.15	856.15	0.00	14-16 ft	-	-	-	X	-
Football Field	SSHS-B3577	SSHS-B3577-SUB-16-18	2/5/2021	16 - 18 ft	856.15	856.15	0.00	16-18 ft	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-10-12	2/5/2021	10 - 12 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-12-14	2/5/2021	12 - 14 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-2-4	2/5/2021	2 - 4 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-4-6	2/5/2021	4 - 6 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	DUP-31	2/5/2021	6 - 8 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-6-8	2/5/2021	6 - 8 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-8-10	2/5/2021	8 - 10 ft	856.27	-	-	-	-	-	-	X	-
Football Field	SSHS-B3579	SSHS-B3579-SUB-14-16	2/5/2021	14 - 16 ft	856.27	856.28	0.01	14.01-16.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-2-4	2/5/2021	2 - 4 ft	856.23	-	-	-	-	-	-	X	-
Football Field	SSHS-B3580	DUP-32	2/5/2021	10 - 12 ft	856.23	856.24	0.01	10.01-12.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-10-12	2/5/2021	10 - 12 ft	856.23	856.24	0.01	10.01-12.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-12-14	2/5/2021	12 - 14 ft	856.23	856.24	0.01	12.01-14.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-14-16	2/5/2021	14 - 16 ft	856.23	856.24	0.01	14.01-16.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-16-18	2/5/2021	16 - 18 ft	856.23	856.24	0.01	16.01-18.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-4-6	2/5/2021	4 - 6 ft	856.23	856.24	0.01	4.01-6.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-6-8	2/5/2021	6 - 8 ft	856.23	856.24	0.01	6.01-8.01 ft	-	-	-	X	-
Football Field	SSHS-B3580	SSHS-B3580-SUB-8-10	2/5/2021	8 - 10 ft	856.23	856.24	0.01	8.01-10.01 ft	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-2-4	2/5/2021	2 - 4 ft	856.18	-	-	-	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-10-12	2/5/2021	10 - 12 ft	856.18	856.18	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-12-14	2/5/2021	12 - 14 ft	856.18	856.18	0.00	12-14 ft	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-14-16	2/5/2021	14 - 16 ft	856.18	856.18	0.00	14-16 ft	-	-	-	X	-
Football Field	SSHS-B3581	DUP-33	2/5/2021	4 - 6 ft	856.18	856.18	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-4-6	2/5/2021	4 - 6 ft	856.18	856.18	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-6-8	2/5/2021	6 - 8 ft	856.18	856.18	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B3581	SSHS-B3581-SUB-8-10	2/5/2021	8 - 10 ft	856.18	856.18	0.00	8-10 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-10-12	2/5/2021	10 - 12 ft	855.93	855.93	0.00	10-12 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-12-14	2/5/2021	12 - 14 ft	855.93	855.93	0.00	12-14 ft	-	-	-	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B3582	DUP-35	2/5/2021	14 - 16 ft	855.93	855.93	0.00	14-16 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-14-16	2/5/2021	14 - 16 ft	855.93	855.93	0.00	14-16 ft	-	-	-	X	-
Football Field	SSHS-B3582	DUP-34	2/5/2021	2 - 4 ft	855.93	855.93	0.00	2-4 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-2-4	2/5/2021	2 - 4 ft	855.93	855.93	0.00	2-4 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-4-6	2/5/2021	4 - 6 ft	855.93	855.93	0.00	4-6 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-6-8	2/5/2021	6 - 8 ft	855.93	855.93	0.00	6-8 ft	-	-	-	X	-
Football Field	SSHS-B3582	SSHS-B3582-SUB-8-10	2/5/2021	8 - 10 ft	855.93	855.93	0.00	8-10 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-10-12	2/5/2021	10 - 12 ft	855.33	855.44	0.11	10.11-12.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-12-14	2/5/2021	12 - 14 ft	855.33	855.44	0.11	12.11-14.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	DUP-36	2/5/2021	14 - 16 ft	855.33	855.44	0.11	14.11-16.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-14-16	2/5/2021	14 - 16 ft	855.33	855.44	0.11	14.11-16.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-2-4	2/5/2021	2 - 4 ft	855.33	855.44	0.11	2.11-4.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-4-6	2/5/2021	4 - 6 ft	855.33	855.44	0.11	4.11-6.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-6-8	2/5/2021	6 - 8 ft	855.33	855.44	0.11	6.11-8.11 ft	-	-	-	X	-
Football Field	SSHS-B3583	SSHS-B3583-SUB-8-10	2/5/2021	8 - 10 ft	855.33	855.44	0.11	8.11-10.11 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-16-18	3/31/2021	16 - 18 ft	855.62	856.75	1.13	17.13-19.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-18-20	3/31/2021	18 - 20 ft	855.62	856.75	1.13	19.13-21.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-20-22	3/31/2021	20 - 22 ft	855.62	856.75	1.13	21.13-23.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	040321 10:45_DUP-23	3/31/2021	22 - 24 ft	855.62	856.75	1.13	23.13-25.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-22-24	3/31/2021	22 - 24 ft	855.62	856.75	1.13	23.13-25.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-24-26	3/31/2021	24 - 26 ft	855.62	856.75	1.13	25.13-27.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-26-28	3/31/2021	26 - 28 ft	855.62	856.75	1.13	27.13-29.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-28-29	3/31/2021	28 - 29 ft	855.62	856.75	1.13	29.13-30.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-29-30	3/31/2021	29 - 30 ft	855.62	856.75	1.13	30.13-31.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-16-18	3/31/2021	16 - 18 ft	856.45	857.00	0.55	16.55-18.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-18-20	3/31/2021	18 - 20 ft	856.45	857.00	0.55	18.55-20.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-20-22	3/31/2021	20 - 22 ft	856.45	857.00	0.55	20.55-22.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-22-24	3/31/2021	22 - 24 ft	856.45	857.00	0.55	22.55-24.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-24-26	3/31/2021	24 - 26 ft	856.45	857.00	0.55	24.55-26.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-26-28	3/31/2021	26 - 28 ft	856.45	857.00	0.55	26.55-28.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-28-30	3/31/2021	28 - 30 ft	856.45	857.00	0.55	28.55-30.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-30-32	3/31/2021	30 - 32 ft	856.45	857.00	0.55	30.55-32.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-32-34	3/31/2021	32 - 34 ft	856.45	857.00	0.55	32.55-34.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-34-36	3/31/2021	34 - 36 ft	856.45	857.00	0.55	34.55-36.55 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	24.5 - 26 ft	855.62	856.75	1.13	25.63-27.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-30-32	4/1/2021	30 - 32 ft	855.62	856.75	1.13	31.13-33.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-32-33	4/1/2021	32 - 33 ft	855.62	856.75	1.13	33.13-34.13 ft	X	-	-	-	-
Football Field	SSHS-B3874	DUP-25	4/1/2021	24 - 26 ft	852.54	853.57	1.03	25.03-27.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	DUP-33	4/1/2021	24 - 26 ft	852.54	853.57	1.03	25.03-27.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	16 - 18 ft	852.54	853.57	1.03	17.03-19.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	18 - 20 ft	852.54	853.57	1.03	19.03-21.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	20 - 22 ft	852.54	853.57	1.03	21.03-23.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	22 - 24 ft	852.54	853.57	1.03	23.03-25.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	24 - 26 ft	852.54	853.57	1.03	25.03-27.03 ft	X	X	X	X	X
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	26 - 28 ft	852.54	853.57	1.03	27.03-29.03 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	16 - 18 ft	855.62	856.75	1.13	17.13-19.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	18 - 20 ft	855.62	856.75	1.13	19.13-21.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	20 - 22 ft	855.62	856.75	1.13	21.13-23.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	22 - 24 ft	855.62	856.75	1.13	23.13-25.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	24 - 24.5 ft	855.62	856.75	1.13	25.13-25.63 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	24.5 - 26 ft	855.62	856.75	1.13	25.63-27.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	26 - 28 ft	855.62	856.75	1.13	27.13-29.13 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	28 - 28.5 ft	855.62	856.75	1.13	29.13-29.63 ft	X	X	X	X	X
Football Field	SSHS-B3875	SSHS-B3875-SUB-16-18	4/2/2021	16 - 18 ft	854.82	855.57	0.75	16.75-18.75 ft	X	-	-	-	-
Football Field	SSHS-B3875	SSHS-B3875-SUB-18-20	4/2/2021	18 - 20 ft	854.82	855.57	0.75	18.75-20.75 ft	X	-	-	-	-
Football Field	SSHS-B3875	SSHS-B3875-SUB-20-22	4/2/2021	20 - 22 ft	854.82	855.57	0.75	20.75-22.75 ft	X	-	-	-	-
Football Field	SSHS-B3875	SSHS-B3875-SUB-22-23	4/2/2021	22 - 23 ft	854.82	855.57	0.75	22.75-23.75 ft	X	-	-	-	-
Football Field	SSHS-B3875	SSHS-B3875-SUB-23-24	4/2/2021	23 - 24 ft	854.82	855.57	0.75	23.75-24.75 ft	X	-	-	-	-
Football Field	SSHS-B3875	SSHS-B3875-SUB-24-26	4/2/2021	24 - 26 ft	854.82	855.57	0.75	24.75-26.75 ft	X	-	-	-	-
Football Field	SSHS-B3875	SSHS-B3875-SUB-26-27	4/2/2021	26 - 27 ft	854.82	855.57	0.75	26.75-27.75 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	16 - 18 ft	855.09	855.50	0.41	16.41-18.41 ft	X	-	X	X	-
Football Field	SSHS-B3876	DUP-27	4/2/2021	18 - 20 ft	855.09	855.50	0.41	18.41-20.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	18 - 20 ft	855.09	855.50	0.41	18.41-20.41 ft	X	-	X	X	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	20 - 22 ft	855.09	855.50	0.41	20.41-22.41 ft	X	-	X	X	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-22-24	4/2/2021	22 - 24 ft	855.09	855.50	0.41	22.41-24.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-24-26	4/2/2021	24 - 26 ft	855.09	855.50	0.41	24.41-26.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-26-28	4/2/2021	26 - 28 ft	855.09	855.50	0.41	26.41-28.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-28-30	4/2/2021	28 - 30 ft	855.09	855.50	0.41	28.41-30.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-30-32	4/2/2021	30 - 32 ft	855.09	855.50	0.41	30.41-32.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-32-33	4/2/2021	32 - 33 ft	855.09	855.50	0.41	32.41-33.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-33-34	4/2/2021	33 - 34 ft	855.09	855.50	0.41	33.41-34.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-34-36	4/2/2021	34 - 36 ft	855.09	855.50	0.41	34.41-36.41 ft	X	-	-	-	-
Football Field	SSHS-B3876	SSHS-B3876-SUB-36-37	4/2/2021	36 - 37 ft	855.09	855.50	0.41	36.41-37.41 ft	X	-	-	-	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-16-18	4/5/2021	16 - 18 ft	854.82	855.53	0.71	16.71-18.71 ft	X	-	-	-	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	18 - 20 ft	854.82	855.53	0.71	18.71-20.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	20 - 22 ft	854.82	855.53	0.71	20.71-22.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	22 - 24 ft	854.82	855.53	0.71	22.71-24.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	24 - 26 ft	854.82	855.53	0.71	24.71-26.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	26 - 28 ft	854.82	855.53	0.71	26.71-28.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	28 - 30 ft	854.82	855.53	0.71	28.71-30.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	30 - 32 ft	854.82	855.53	0.71	30.71-32.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	32 - 34 ft	854.82	855.53	0.71	32.71-34.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	34 - 36 ft	854.82	855.53	0.71	34.71-36.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	36 - 38 ft	854.82	855.53	0.71	36.71-38.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-38-40	4/5/2021	38 - 40 ft	854.82	855.53	0.71	38.71-40.71 ft	X	-	-	-	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	40 - 42 ft	854.82	855.53	0.71	40.71-42.71 ft	X	-	X	X	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-42-43	4/5/2021	42 - 43 ft	854.82	855.53	0.71	42.71-43.71 ft	X	-	-	-	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-43-45	4/5/2021	43 - 45 ft	854.82	855.53	0.71	43.71-45.71 ft	X	-	-	-	-
Football Field	SSHS-B3878	SSHS-B3878-SUB-45-47	4/5/2021	45 - 47 ft	854.82	855.53	0.71	45.71-47.71 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-16-18	4/7/2021	16 - 18 ft	855.86	855.86	0.00	16-18 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-18-20	4/7/2021	18 - 20 ft	855.86	855.86	0.00	18-20 ft	X	-	-	-	-
Football Field	SSHS-B3856	DUP-10	4/7/2021	20 - 22 ft	855.86	855.86	0.00	20-22 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-20-22	4/7/2021	20 - 22 ft	855.86	855.86	0.00	20-22 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-22-24	4/7/2021	22 - 24 ft	855.86	855.86	0.00	22-24 ft	X	-	-	-	-
Football Field	SSHS-B3856	DUP-36	4/7/2021	24 - 26 ft	855.86	855.86	0.00	24-26 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-24-26	4/7/2021	24 - 26 ft	855.86	855.86	0.00	24-26 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-26-28	4/7/2021	26 - 28 ft	855.86	855.86	0.00	26-28 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-28-30	4/7/2021	28 - 30 ft	855.86	855.86	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B3857	SSHS-B3857-SUB-16-18	4/7/2021	16 - 18 ft	855.25	855.29	0.04	16.04-18.04 ft	X	-	-	-	-
Football Field	SSHS-B3857	SSHS-B3857-SUB-18-20	4/7/2021	18 - 20 ft	855.25	855.29	0.04	18.04-20.04 ft	X	-	-	-	-
Football Field	SSHS-B3857	SSHS-B3857-SUB-20-22	4/7/2021	20 - 22 ft	855.25	855.29	0.04	20.04-22.04 ft	X	-	-	-	-
Football Field	SSHS-B3857	SSHS-B3857-SUB-22-24	4/7/2021	22 - 24 ft	855.25	855.29	0.04	22.04-24.04 ft	X	-	-	-	-
Football Field	SSHS-B3857	SSHS-B3857-SUB-24-26	4/7/2021	24 - 26 ft	855.25	855.29	0.04	24.04-26.04 ft	X	-	-	-	-
Football Field	SSHS-B3857	SSHS-B3857-SUB-26-28	4/7/2021	26 - 28 ft	855.25	855.29	0.04	26.04-28.04 ft	X	-	-	-	-
Football Field	SSHS-B3866	SSHS-B3866-SUB-16-18	4/7/2021	16 - 18 ft	855.09	855.50	0.41	16.41-18.41 ft	X	-	-	-	-
Football Field	SSHS-B3866	DUP-21	4/7/2021	18 - 20 ft	855.09	855.50	0.41	18.41-20.41 ft	X	-	-	-	-
Football Field	SSHS-B3866	SSHS-B3866-SUB-18-20	4/7/2021	18 - 20 ft	855.09	855.50	0.41	18.41-20.41 ft	X	-	-	-	-
Football Field	SSHS-B3866	SSHS-B3866-SUB-20-22	4/7/2021	20 - 22 ft	855.09	855.50	0.41	20.41-22.41 ft	X	-	-	-	-
Football Field	SSHS-B3866	SSHS-B3866-SUB-22-23	4/7/2021	22 - 23 ft	855.09	855.50	0.41	22.41-23.41 ft	X	-	-	-	-
Football Field	SSHS-B3866	SSHS-B3866-SUB-23-25	4/7/2021	23 - 25 ft	855.09	855.50	0.41	23.41-25.41 ft	X	-	-	-	-
Football Field	SSHS-B3866	SSHS-B3866-SUB-25-27	4/7/2021	25 - 27 ft	855.09	855.50	0.41	25.41-27.41 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-30-32	4/8/2021	30 - 32 ft	855.86	855.86	0.00	30-32 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-32-34	4/8/2021	32 - 34 ft	855.86	855.86	0.00	32-34 ft	X	-	-	-	-
Football Field	SSHS-B3856	SSHS-B3856-SUB-34-36	4/8/2021	34 - 36 ft	855.86	855.86	0.00	34-36 ft	X	-	-	-	-
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	16 - 18 ft	856.13	856.13	0.00	16-18 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	18 - 20 ft	856.13	856.13	0.00	18-20 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	20 - 22 ft	856.13	856.13	0.00	20-22 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	22 - 24 ft	856.13	856.13	0.00	22-24 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	24 - 26 ft	856.13	856.13	0.00	24-26 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	26 - 28 ft	856.13	856.13	0.00	26-28 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	28 - 30 ft	856.13	856.13	0.00	28-20 ft	X	X	X	X	X
Football Field	SSHS-B3865	DUP-20	4/8/2021	28 - 30 ft	856.13	856.13	0.00	28-30 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	30 - 32 ft	856.13	856.13	0.00	30-32 ft	X	X	X	X	X
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	32 - 34 ft	856.13	856.13	0.00	32-34 ft	X	X	X	X	X
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	16 - 18 ft	855.85	855.85	0.00	16-18 ft	X	-	X	X	-
Football Field	SSHS-B3863	DUP-39	4/9/2021	18 - 20 ft	855.85	855.85	0.00	18-20 ft	-	-	-	X	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	18 - 20 ft	855.85	855.85	0.00	18-20 ft	X	-	X	X	-
Football Field	SSHS-B3863	DUP-18	4/9/2021	20 - 22 ft	855.85	855.85	0.00	20-22 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	20 - 22 ft	855.85	855.85	0.00	20-22 ft	X	-	X	X	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	22 - 24 ft	855.85	855.85	0.00	22-24 ft	X	-	X	X	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-24-26	4/9/2021	24 - 26 ft	855.85	855.85	0.00	24-26 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-26-28	4/9/2021	26 - 28 ft	855.85	855.85	0.00	26-28 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	28 - 30 ft	855.85	855.85	0.00	28-30 ft	X	-	X	X	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-30-32	4/9/2021	30 - 32 ft	855.85	855.85	0.00	30-32 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-32-34	4/9/2021	32 - 34 ft	855.85	855.85	0.00	32-34 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B3863	SSHS-B3863-SUB-34-36	4/9/2021	34 - 36 ft	855.85	855.85	0.00	34-36 ft	X	-	-	-	-
Football Field	SSHS-B3864	DUP-19	4/9/2021	16 - 18 ft	856.06	856.07	0.01	16.01-18.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	16 - 18 ft	856.06	856.07	0.01	16.01-18.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	18 - 20 ft	856.06	856.07	0.01	18.01-20.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	20 - 22 ft	856.06	856.07	0.01	20.01-22.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	22 - 24 ft	856.06	856.07	0.01	22.01-24.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	24 - 26 ft	856.06	856.07	0.01	24.01-26.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	26 - 28 ft	856.06	856.07	0.01	26.01-28.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	28 - 30 ft	856.06	856.07	0.01	28.01-30.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	DUP-37	4/9/2021	30 - 32 ft	856.06	856.07	0.01	30.01-32.01 ft	-	-	-	X	-
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	30 - 32 ft	856.06	856.07	0.01	30.01-32.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	DUP-38	4/9/2021	32 - 34 ft	856.06	856.07	0.01	32.01-34.01 ft	-	-	-	X	-
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	32 - 34 ft	856.06	856.07	0.01	32.01-34.01 ft	X	X	X	X	X
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	34 - 36 ft	856.06	856.07	0.01	34.01-36.01 ft	X	X	X	X	X
Football Field	SSHS-B3858	SSHS-B3858-SUB-16-18	4/10/2021	16 - 18 ft	856.08	856.08	0.00	16-18 ft	X	-	-	-	-
Football Field	SSHS-B3858	DUP-12	4/10/2021	18 - 20 ft	856.08	856.08	0.00	18-20 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	18 - 20 ft	856.08	856.08	0.00	18-20 ft	X	-	X	X	-
Football Field	SSHS-B3858	DUP-34	4/10/2021	20 - 22 ft	856.08	856.08	0.00	20-22 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	20 - 22 ft	856.08	856.08	0.00	20-22 ft	X	-	X	X	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-22-24	4/10/2021	22 - 24 ft	856.08	856.08	0.00	22-24 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-24-26	4/10/2021	24 - 26 ft	856.08	856.08	0.00	24-26 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-26-28	4/10/2021	26 - 28 ft	856.08	856.08	0.00	26-28 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-28-30	4/10/2021	28 - 30 ft	856.08	856.08	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-30-31	4/10/2021	30 - 31 ft	856.08	856.08	0.00	30-31 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-31-33	4/10/2021	31 - 33 ft	856.08	856.08	0.00	31-33 ft	X	-	-	-	-
Football Field	SSHS-B3858	SSHS-B3858-SUB-33-35	4/10/2021	33 - 35 ft	856.08	856.08	0.00	33-35 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-36-37	4/10/2021	36 - 37 ft	855.85	855.85	0.00	36-37 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-37-39	4/10/2021	37 - 39 ft	855.85	855.85	0.00	37-39 ft	X	-	-	-	-
Football Field	SSHS-B3863	SSHS-B3863-SUB-39-41	4/10/2021	39 - 41 ft	855.85	855.85	0.00	39-41 ft	X	-	-	-	-
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	16 - 18 ft	855.38	855.49	0.11	16.11-18.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	18 - 20 ft	855.38	855.49	0.11	18.11-20.11 ft	X	X	X	X	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	20 - 22 ft	855.38	855.49	0.11	20.11-22.11 ft	X	X	X	X	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	22 - 24 ft	855.38	855.49	0.11	22.11-24.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	24 - 26 ft	855.38	855.49	0.11	24.11-26.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	26 - 28 ft	855.38	855.49	0.11	26.11-28.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	28 - 30 ft	855.38	855.49	0.11	28.11-30.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	30 - 32 ft	855.38	855.49	0.11	30.11-32.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	32 - 34 ft	855.38	855.49	0.11	32.11-34.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	34 - 36 ft	855.38	855.49	0.11	34.11-36.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	36 - 38 ft	855.38	855.49	0.11	36.11-38.11 ft	X	X	X	-	X
Football Field	SSHS-B3855	DUP-03	4/12/2021	16 - 18 ft	855.28	855.28	0.00	16-18 ft	X	-	X	-	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	16 - 18 ft	855.28	855.28	0.00	16-18 ft	X	-	X	X	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	18 - 20 ft	855.28	855.28	0.00	18-20 ft	X	-	X	X	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-20-22	4/12/2021	20 - 22 ft	855.28	855.28	0.00	20-22 ft	X	-	-	-	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-22-24	4/12/2021	22 - 24 ft	855.28	855.28	0.00	22-24 ft	X	-	-	-	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-24-26	4/12/2021	24 - 26 ft	855.28	855.28	0.00	24-26 ft	X	-	-	-	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-26-28	4/12/2021	26 - 28 ft	855.28	855.28	0.00	26-28 ft	X	-	-	-	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-28-30	4/12/2021	28 - 30 ft	855.28	855.28	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B3859	DUP-13	4/12/2021	16 - 18 ft	857.14	857.14	0.00	16-18 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-16-18	4/12/2021	16 - 18 ft	857.14	857.14	0.00	16-18 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	18 - 20 ft	857.14	857.14	0.00	18-20 ft	X	-	X	X	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	20 - 22 ft	857.14	857.14	0.00	20-22 ft	X	-	X	X	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	22 - 24 ft	857.14	857.14	0.00	22-24 ft	X	-	X	X	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-24-26	4/12/2021	24 - 26 ft	857.14	857.14	0.00	24-26 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	26 - 28 ft	857.14	857.14	0.00	26-28 ft	X	-	X	X	-
Football Field	SSHS-B3859	DUP-35	4/12/2021	28 - 30 ft	857.14	857.14	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-28-30	4/12/2021	28 - 30 ft	857.14	857.14	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-30-32	4/12/2021	30 - 32 ft	857.14	857.14	0.00	30-32 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-32-34	4/12/2021	32 - 34 ft	857.14	857.14	0.00	32-34 ft	X	-	-	-	-
Football Field	SSHS-B3859	SSHS-B3859-SUB-34-36	4/12/2021	34 - 36 ft	857.14	857.14	0.00	34-36 ft	X	-	-	-	-
Football Field	SSHS-B3877	DUP-28	4/12/2021	16 - 18 ft	855.38	855.49	0.11	16.11-18.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	DUP-29	4/12/2021	32 - 34 ft	855.38	855.49	0.11	32.11-34.11 ft	X	X	X	-	X
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	38 - 40 ft	855.38	855.49	0.11	38.11-40.11 ft	X	X	X	-	X
Football Field	SSHS-B3855	SSHS-B3855-SUB-30-32	4/13/2021	30 - 32 ft	855.28	855.28	0.00	30-32 ft	X	-	-	-	-
Football Field	SSHS-B3855	SSHS-B3855-SUB-32-34	4/13/2021	32 - 34 ft	855.28	855.28	0.00	32-34 ft	X	-	-	-	-
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	16 - 18 ft	856.50	856.50	0.00	16-18 ft	X	X	X	X	-
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	18 - 20 ft	856.50	856.50	0.00	18-20 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	20 - 22 ft	856.50	856.50	0.00	20-22 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	22 - 24 ft	856.50	856.50	0.00	22-24 ft	X	X	X	X	X
Football Field	SSHS-B3860	DUP-14	4/13/2021	24 - 26 ft	856.50	856.50	0.00	24-26 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	24 - 26 ft	856.50	856.50	0.00	24-26 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	26 - 28 ft	856.50	856.50	0.00	26-28 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	28 - 30 ft	856.50	856.50	0.00	28-30 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	30 - 32 ft	856.50	856.50	0.00	30-32 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	32 - 34 ft	856.50	856.50	0.00	32-34 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	34 - 36 ft	856.50	856.50	0.00	34-36 ft	X	X	X	X	X
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	36 - 38 ft	856.50	856.50	0.00	36-38 ft	X	X	X	X	X
Football Field	SSHS-B3861	SSHS-B3861-SUB-16-18	4/14/2021	16 - 18 ft	855.76	855.87	0.11	16.11-18.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-18-20	4/14/2021	18 - 20 ft	855.76	855.87	0.11	18.11-20.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-20-22	4/14/2021	20 - 22 ft	855.76	855.87	0.11	20.11-22.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-22-24	4/14/2021	22 - 24 ft	855.76	855.87	0.11	22.11-24.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-24-26	4/14/2021	24 - 26 ft	855.76	855.87	0.11	24.11-26.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-26-28	4/14/2021	26 - 28 ft	855.76	855.87	0.11	26.11-28.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-28-30	4/14/2021	28 - 30 ft	855.76	855.87	0.11	28.11-30.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-30-32	4/14/2021	30 - 32 ft	855.76	855.87	0.11	30.11-32.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-32-34	4/14/2021	32 - 34 ft	855.76	855.87	0.11	32.11-34.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-34-36	4/14/2021	34 - 36 ft	855.76	855.87	0.11	34.11-36.11 ft	X	-	-	-	-
Football Field	SSHS-B3861	SSHS-B3861-SUB-36-38	4/14/2021	36 - 38 ft	855.76	855.87	0.11	36.11-38.11 ft	X	-	-	-	-
Football Field	SSHS-B3881	DUP-08	4/14/2021	28 - 30 ft	855.29	855.53	0.24	28.24-30.24 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	16 - 18 ft	855.20	855.37	0.17	16.17-18.17 ft	X	-	X	X	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	18 - 20 ft	855.20	855.37	0.17	18.17-20.17 ft	X	-	X	X	-
Football Field	SSHS-B3880	DUP-07	4/17/2021	20 - 22 ft	855.20	855.37	0.17	20.17-22.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-20-22	4/17/2021	20 - 22 ft	855.20	855.37	0.17	20.17-22.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-22-24	4/17/2021	22 - 24 ft	855.20	855.37	0.17	22.17-24.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-24-26	4/17/2021	24 - 26 ft	855.20	855.37	0.17	24.17-26.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-26-28	4/17/2021	26 - 28 ft	855.20	855.37	0.17	26.17-28.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-28-30	4/17/2021	28 - 30 ft	855.20	855.37	0.17	28.17-30.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-30-32	4/17/2021	30 - 32 ft	855.20	855.37	0.17	30.17-32.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-32-34	4/17/2021	32 - 34 ft	855.20	855.37	0.17	32.17-34.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-34-36	4/17/2021	34 - 36 ft	855.20	855.37	0.17	34.17-36.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-36-38	4/17/2021	36 - 38 ft	855.20	855.37	0.17	36.17-38.17 ft	X	-	-	-	-
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	22 - 24 ft	855.26	855.36	0.10	22.1-24.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	16 - 18 ft	855.26	855.36	0.10	16.1-18.1 ft	X	X	X	X	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	18 - 20 ft	855.26	855.36	0.10	18.1-20.1 ft	X	X	X	X	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	20 - 22 ft	855.26	855.36	0.10	20.1-22.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	24 - 26 ft	855.26	855.36	0.10	24.1-26.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	32 - 34 ft	855.26	855.36	0.10	32.1-34.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	DUP-09	4/18/2021	26 - 28 ft	855.26	855.36	0.10	26.1-28.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	26 - 28 ft	855.26	855.36	0.10	26.1-28.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	28 - 30 ft	855.26	855.36	0.10	28.1-30.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	30 - 32 ft	855.26	855.36	0.10	30.1-32.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	34 - 36 ft	855.26	855.36	0.10	34.1-36.1 ft	X	X	X	-	X
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	16 - 18 ft	855.29	855.53	0.24	16.24-18.24 ft	X	-	X	X	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	18 - 20 ft	855.29	855.53	0.24	18.24-20.24 ft	X	-	X	X	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	20 - 22 ft	855.29	855.53	0.24	20.24-22.24 ft	X	-	X	X	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-22-24	4/18/2021	22 - 24 ft	855.29	855.53	0.24	22.24-24.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-24-26	4/18/2021	24 - 26 ft	855.29	855.53	0.24	24.24-26.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-26-28	4/18/2021	26 - 28 ft	855.29	855.53	0.24	26.24-28.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	DUP-08	4/18/2021	28 - 30 ft	855.29	855.53	0.24	28.24-30.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-28-30	4/18/2021	28 - 30 ft	855.29	855.53	0.24	28.24-30.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-30-32	4/18/2021	30 - 32 ft	855.29	855.53	0.24	30.24-32.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-32-34	4/18/2021	32 - 34 ft	855.29	855.53	0.24	32.24-34.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-34-35	4/18/2021	34 - 35 ft	855.29	855.53	0.24	34.24-35.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-35-37	4/18/2021	35 - 36 ft	855.29	855.53	0.24	35.24-36.24 ft	X	-	-	-	-
Football Field	SSHS-B3881	SSHS-B3881-SUB-37-39	4/18/2021	37 - 39 ft	855.29	855.53	0.24	37.24-39.24 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-22-24	4/18/2021	22 - 24 ft	854.96	855.37	0.41	22.41-24.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	DUP-02	4/18/2021	24 - 26 ft	854.96	855.37	0.41	24.41-26.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-24-26	4/18/2021	24 - 26 ft	854.96	855.37	0.41	24.41-26.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-34-36	4/18/2021	34 - 36 ft	854.96	855.37	0.41	34.41-36.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	DUP-01	4/18/2021	16 - 18 ft	854.96	855.37	0.41	16.41-18.41 ft	X	-	X	X	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	16 - 18 ft	854.96	855.37	0.41	16.41-18.41 ft	X	-	X	X	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-26-28	4/18/2021	26 - 28 ft	854.96	855.37	0.41	26.41-28.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-32-34	4/18/2021	32 - 34 ft	854.96	855.37	0.41	32.41-34.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-36-38	4/18/2021	36 - 38 ft	854.96	855.37	0.41	36.41-38.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-38-40	4/18/2021	38 - 40 ft	854.96	855.37	0.41	38.41-40.41 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	18 - 20 ft	854.96	855.37	0.41	18.41-20.41 ft	X	-	X	X	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	20 - 22 ft	854.96	855.37	0.41	20.41-22.41 ft	X	-	X	X	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-28-30	4/18/2021	28 - 30 ft	854.96	855.37	0.41	28.41-30.41 ft	X	-	-	-	-
Football Field	SSHS-B645A	SSHS-B645A-SUB-40-42	4/18/2021	40 - 42 ft	854.96	855.37	0.41	40.41-42.41 ft	X	-	-	-	-
Football Field	SSHS-B3858	DUP-12	4/19/2021	20 - 22 ft	856.08	856.08	0.00	20-22 ft	X	X	X	X	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	36 - 38 ft	855.26	855.36	0.10	36.1-38.1 ft	X	X	X	-	X
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	38 - 40 ft	855.26	855.36	0.10	38.1-40.1 ft	X	X	X	-	X
Football Field	SSHS-B3871	DUP-11	4/19/2021	16 - 18 ft	855.34	855.50	0.16	16.16-18.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	16 - 18 ft	855.34	855.50	0.16	16.16-18.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	18 - 20 ft	855.34	855.50	0.16	18.16-20.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	20 - 22 ft	855.34	855.50	0.16	20.16-22.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	22 - 24 ft	855.34	855.50	0.16	22.16-24.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	24 - 26 ft	855.34	855.50	0.16	24.16-26.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	26 - 28 ft	855.34	855.50	0.16	26.16-28.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	28 - 30 ft	855.34	855.50	0.16	28.16-30.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	30 - 32 ft	855.34	855.50	0.16	30.16-32.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	DUP-32	4/19/2021	32 - 34 ft	855.34	855.50	0.16	32.16-34.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	32 - 34 ft	855.34	855.50	0.16	32.16-34.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	34 - 36 ft	855.34	855.50	0.16	34.16-36.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	36 - 37 ft	855.34	855.50	0.16	36.16-37.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	37 - 39 ft	855.34	855.50	0.16	37.16-39.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	39 - 41 ft	855.34	855.50	0.16	39.16-41.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	41 - 43 ft	855.34	855.50	0.16	41.16-43.16 ft	X	X	X	X	X
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	43 - 45 ft	855.34	855.50	0.16	43.16-45.16 ft	X	X	X	X	X
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	16 - 18 ft	854.94	855.38	0.44	16.44-18.44 ft	X	-	X	X	-
Football Field	SSHS-B3873	DUP-06	4/19/2021	18 - 20 ft	854.94	855.38	0.44	18.44-20.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-18-20	4/19/2021	18 - 20 ft	854.94	855.38	0.44	18.44-20.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-20-22	4/19/2021	20 - 22 ft	854.94	855.38	0.44	20.44-22.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-22-24	4/19/2021	22 - 24 ft	854.94	855.38	0.44	22.44-24.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	24 - 26 ft	854.94	855.38	0.44	24.44-26.44 ft	X	-	X	X	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-26-28	4/19/2021	26 - 28 ft	854.94	855.38	0.44	26.44-28.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-28-30	4/19/2021	28 - 30 ft	854.94	855.38	0.44	28.44-30.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-30-32	4/19/2021	30 - 32 ft	854.94	855.38	0.44	30.44-32.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-32-34	4/19/2021	32 - 34 ft	854.94	855.38	0.44	32.44-34.44 ft	X	-	-	-	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	34 - 36 ft	854.94	855.38	0.44	34.44-36.44 ft	X	-	X	X	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	36 - 38 ft	854.94	855.38	0.44	36.44-38.44 ft	X	-	X	X	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	38 - 40 ft	854.94	855.38	0.44	38.44-40.44 ft	X	-	X	X	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	40 - 42 ft	854.94	855.38	0.44	40.44-42.44 ft	X	-	X	X	-
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	42 - 44 ft	854.94	855.38	0.44	42.44-44.44 ft	X	-	X	X	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-38-40	4/19/2021	38 - 40 ft	855.20	855.37	0.17	38.17-40.17 ft	X	-	-	-	-
Football Field	SSHS-B3880	SSHS-B3880-SUB-40-42	4/19/2021	40 - 42 ft	855.20	855.37	0.17	40.17-42.17 ft	X	-	-	-	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	16 - 18 ft	855.35	855.48	0.13	16.13-18.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	DUP-05	4/20/2021	34 - 36 ft	855.35	855.48	0.13	34.13-36.13 ft	X	-	-	-	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-34-36	4/20/2021	34 - 36 ft	855.35	855.48	0.13	34.13-36.13 ft	X	-	-	-	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-36-38	4/20/2021	36 - 38 ft	855.35	855.48	0.13	36.13-38.13 ft	X	-	-	-	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	18 - 20 ft	855.35	855.48	0.13	18.13-20.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	20 - 22 ft	855.35	855.48	0.13	20.13-22.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	22 - 24 ft	855.35	855.48	0.13	22.13-24.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	24 - 26 ft	855.35	855.48	0.13	24.13-26.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	26 - 28 ft	855.35	855.48	0.13	26.13-28.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	28 - 30 ft	855.35	855.48	0.13	28.13-30.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	30 - 32 ft	855.35	855.48	0.13	30.13-32.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	32 - 34 ft	855.35	855.48	0.13	32.13-34.13 ft	X	-	X	X	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-38-40	4/20/2021	38 - 40 ft	855.35	855.48	0.13	38.13-40.13 ft	X	-	-	-	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-40-42	4/20/2021	40 - 42 ft	855.35	855.48	0.13	40.13-42.13 ft	X	-	-	-	-
Football Field	SSHS-B3872	SSHS-B3872-SUB-42-44	4/20/2021	42 - 44 ft	855.35	855.48	0.13	42.13-44.13 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	28 - 30 ft	856.75	856.65	-0.10	27.9-29.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	16 - 18 ft	852.20	852.57	0.37	16.37-18.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	14 - 16 ft	856.75	856.65	-0.10	13.9-15.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	16 - 18 ft	856.75	856.65	-0.10	15.9-17.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	18 - 20 ft	856.75	856.65	-0.10	17.9-19.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	20 - 22 ft	856.75	856.65	-0.10	19.9-21.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	22 - 24 ft	856.75	856.65	-0.10	21.9-23.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	24 - 26 ft	856.75	856.65	-0.10	23.9-25.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	26 - 28 ft	856.75	856.65	-0.10	25.9-27.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	28 - 30 ft	856.75	856.65	-0.10	27.9-29.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	30 - 32 ft	856.75	856.65	-0.10	29.9-31.9 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	14 - 16 ft	852.20	852.57	0.37	14.37-16.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	16 - 18 ft	852.20	852.57	0.37	16.37-18.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	18 - 20 ft	852.20	852.57	0.37	18.37-20.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	20 - 22 ft	852.20	852.57	0.37	20.37-22.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	22 - 24 ft	852.20	852.57	0.37	22.37-24.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	24 - 26 ft	852.20	852.57	0.37	24.37-26.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	26 - 28 ft	852.20	852.57	0.37	26.37-28.37 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-14-16	5/7/2021	14 - 16 ft	857.27	857.87	0.60	14.6-16.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-16-18	5/7/2021	16 - 18 ft	857.27	857.87	0.60	16.6-18.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-18-20	5/7/2021	18 - 20 ft	857.27	857.87	0.60	18.6-20.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-20-22	5/7/2021	20 - 22 ft	857.27	857.87	0.60	20.6-22.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-22-24	5/7/2021	22 - 24 ft	857.27	857.87	0.60	22.6-24.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-24-26	5/7/2021	24 - 26 ft	857.27	857.87	0.60	24.6-26.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-26-28	5/7/2021	26 - 28 ft	857.27	857.87	0.60	26.6-28.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-28-30	5/7/2021	28 - 30 ft	857.27	857.87	0.60	28.6-30.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-30-32	5/7/2021	30 - 32 ft	857.27	857.87	0.60	30.6-32.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-32-33	5/7/2021	32 - 33 ft	857.27	857.87	0.60	32.6-33.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-33-35	5/7/2021	33 - 35 ft	857.27	857.87	0.60	33.6-35.6 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-14-16	5/7/2021	14 - 16 ft	857.06	856.73	-0.33	13.67-15.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-16-18	5/7/2021	16 - 18 ft	857.06	856.73	-0.33	15.67-17.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-18-20	5/7/2021	18 - 20 ft	857.06	856.73	-0.33	17.67-19.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-20-22	5/7/2021	20 - 22 ft	857.06	856.73	-0.33	19.67-21.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-22-24	5/7/2021	22 - 24 ft	857.06	856.73	-0.33	21.67-23.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-24-26	5/7/2021	24 - 26 ft	857.06	856.73	-0.33	23.67-25.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-26-28	5/7/2021	26 - 28 ft	857.06	856.73	-0.33	25.67-27.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-28-30	5/7/2021	28 - 30 ft	857.06	856.73	-0.33	27.67-29.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-30-32	5/7/2021	30 - 32 ft	857.06	856.73	-0.33	29.67-31.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-32-34	5/7/2021	32 - 34 ft	857.06	856.73	-0.33	31.67-33.67 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-14-16	5/10/2021	14 - 16 ft	856.83	856.65	-0.18	13.82-15.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-16-18	5/10/2021	16 - 18 ft	856.83	856.65	-0.18	15.82-17.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-18-20	5/10/2021	18 - 20 ft	856.83	856.65	-0.18	17.82-19.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-20-22	5/10/2021	20 - 22 ft	856.83	856.65	-0.18	19.82-21.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-22-24	5/10/2021	22 - 24 ft	856.83	856.65	-0.18	21.82-23.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-24-26	5/10/2021	24 - 26 ft	856.83	856.65	-0.18	23.82-25.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-26-28	5/10/2021	26 - 28 ft	856.83	856.65	-0.18	25.82-27.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-28-30	5/10/2021	28 - 30 ft	856.83	856.65	-0.18	27.82-29.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-30-32	5/10/2021	30 - 32 ft	856.83	856.65	-0.18	29.82-31.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-32-34	5/10/2021	32 - 34 ft	856.83	856.65	-0.18	31.82-33.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-34-36	5/10/2021	34 - 36 ft	856.83	856.65	-0.18	33.82-35.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-36-38	5/10/2021	36 - 38 ft	856.83	856.65	-0.18	35.82-37.82 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-14-16	5/10/2021	14 - 16 ft	856.60	856.69	0.09	14.09-16.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-16-18	5/10/2021	16 - 18 ft	856.60	856.69	0.09	16.09-18.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-18-20	5/10/2021	18 - 20 ft	856.60	856.69	0.09	18.09-20.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-20-22	5/10/2021	20 - 22 ft	856.60	856.69	0.09	20.09-22.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-22-24	5/10/2021	22 - 24 ft	856.60	856.69	0.09	22.09-24.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-24-26	5/10/2021	24 - 26 ft	856.60	856.69	0.09	24.09-26.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3882	DUP-1	5/10/2021	14 - 16 ft	852.29	853.40	1.11	15.11-17.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	18 - 20 ft	853.37	853.81	0.44	18.44-20.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	14 - 16 ft	853.37	853.81	0.44	14.44-16.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	16 - 18 ft	853.37	853.81	0.44	16.44-18.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	18 - 20 ft	853.37	853.81	0.44	18.44-20.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	20 - 22 ft	853.37	853.81	0.44	20.44-22.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	22 - 24 ft	853.37	853.81	0.44	22.44-24.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	24 - 25 ft	853.37	853.81	0.44	24.44-25.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	25 - 27 ft	853.37	853.81	0.44	25.44-27.44 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	14 - 16 ft	852.29	853.40	1.11	15.11-17.11 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	16 - 18 ft	852.29	853.40	1.11	17.11-19.11 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	18 - 20 ft	852.29	853.40	1.11	19.11-21.11 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	20 - 22 ft	852.29	853.40	1.11	21.11-23.11 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	22 - 23 ft	852.29	853.40	1.11	23.11-24.11 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	23 - 25 ft	852.29	853.40	1.11	24.11-26.11 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-14-16	5/11/2021	14 - 16 ft	853.49	857.33	3.84	17.84-19.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-16-18	5/11/2021	16 - 18 ft	853.49	857.33	3.84	19.84-21.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-18-20	5/11/2021	18 - 20 ft	853.49	857.33	3.84	21.84-23.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-22-24	5/11/2021	22 - 24 ft	853.49	857.33	3.84	25.84-27.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-24-25	5/11/2021	24 - 25 ft	853.49	857.33	3.84	27.84-28.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-20-22	5/11/2021	20 - 22 ft	853.49	857.33	3.84	23.84-25.84 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-25-27	5/11/2021	25 - 27 ft	853.49	857.33	3.84	28.84-30.84 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	14 - 16 ft	852.15	852.94	0.79	14.79-16.79 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	16 - 18 ft	852.15	852.94	0.79	16.79-18.79 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	18 - 20 ft	852.15	852.94	0.79	18.79-20.79 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	20 - 22 ft	852.15	852.94	0.79	20.79-22.79 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	22 - 24 ft	852.15	852.94	0.79	22.79-24.79 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	24 - 25 ft	852.15	852.94	0.79	24.79-25.79 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-14-16	5/11/2021	14 - 16 ft	852.98	852.99	0.01	14.01-16.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-16-18	5/11/2021	16 - 18 ft	852.98	852.99	0.01	16.01-18.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-18-20	5/11/2021	18 - 20 ft	852.98	852.99	0.01	18.01-20.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-20-22	5/11/2021	20 - 22 ft	852.98	852.99	0.01	20.01-22.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-22-24	5/11/2021	22 - 24 ft	852.98	852.99	0.01	22.01-24.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-24-25	5/11/2021	24 - 25 ft	852.98	852.99	0.01	24.01-25.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-25-27	5/11/2021	25 - 27 ft	852.98	852.99	0.01	25.01-27.01 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-26-28	5/11/2021	26 - 28 ft	856.60	856.69	0.09	26.09-28.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-28-30	5/11/2021	28 - 30 ft	856.60	856.69	0.09	28.09-30.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-30-32	5/11/2021	30 - 32 ft	856.60	856.69	0.09	30.09-32.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-32-34	5/11/2021	32 - 34 ft	856.60	856.69	0.09	32.09-34.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-34-36	5/11/2021	34 - 36 ft	856.60	856.69	0.09	34.09-36.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-36-38	5/11/2021	36 - 38 ft	856.60	856.69	0.09	36.09-38.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-38-40	5/11/2021	38 - 40 ft	856.60	856.69	0.09	38.09-40.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-40-41	5/11/2021	40 - 41 ft	856.60	856.69	0.09	40.09-41.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-41-43	5/11/2021	41 - 43 ft	856.60	856.69	0.09	41.09-43.09 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-14-16	5/11/2021	14 - 16 ft	856.72	856.50	-0.22	13.78-15.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-16-18	5/11/2021	16 - 18 ft	856.72	856.50	-0.22	15.78-17.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-18-20	5/11/2021	18 - 20 ft	856.72	856.50	-0.22	17.78-19.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-20-22	5/11/2021	20 - 22 ft	856.72	856.50	-0.22	19.78-21.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-22-24	5/11/2021	22 - 24 ft	856.72	856.50	-0.22	21.78-23.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	8 - 10 ft	856.50	855.82	-0.68	7.32-9.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	4 - 6 ft	856.50	855.82	-0.68	3.32-5.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	6 - 8 ft	856.50	855.82	-0.68	5.32-7.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	8 - 10 ft	856.50	855.82	-0.68	7.32-9.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	10 - 12 ft	856.50	855.82	-0.68	9.32-11.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	12 - 14 ft	856.50	855.82	-0.68	11.32-13.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	14 - 16 ft	856.50	855.82	-0.68	13.32-15.32 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18	5/11/2021	16 - 18 ft	856.50	855.82	-0.68	15.32-17.32 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-14-16	5/12/2021	14 - 16 ft	856.79	856.60	-0.19	13.81-15.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-16-18	5/12/2021	16 - 18 ft	856.79	856.60	-0.19	15.81-17.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-18-20	5/12/2021	18 - 20 ft	856.79	856.60	-0.19	17.81-19.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-20-22	5/12/2021	20 - 22 ft	856.79	856.60	-0.19	19.81-21.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-22-24	5/12/2021	22 - 24 ft	856.79	856.60	-0.19	21.81-23.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-24-26	5/12/2021	24 - 26 ft	856.79	856.60	-0.19	23.81-25.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-26-28	5/12/2021	26 - 28 ft	856.79	856.60	-0.19	25.81-27.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-28-30	5/12/2021	28 - 30 ft	856.79	856.60	-0.19	27.81-29.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-30-32	5/12/2021	30 - 32 ft	856.79	856.60	-0.19	29.81-31.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-32-34	5/12/2021	32 - 34 ft	856.79	856.60	-0.19	31.81-33.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-14-16	5/12/2021	14 - 16 ft	856.44	857.55	1.11	15.11-17.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-16-18	5/12/2021	16 - 18 ft	856.44	857.55	1.11	17.11-19.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-18-20	5/12/2021	18 - 20 ft	856.44	857.55	1.11	19.11-21.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-20-22	5/12/2021	20 - 22 ft	856.44	857.55	1.11	21.11-23.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-22-24	5/12/2021	22 - 24 ft	856.44	857.55	1.11	23.11-25.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-24-26	5/12/2021	24 - 26 ft	856.44	857.55	1.11	25.11-27.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-26-28	5/12/2021	26 - 28 ft	856.44	857.55	1.11	27.11-29.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-28-30	5/12/2021	28 - 30 ft	856.44	857.55	1.11	29.11-31.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-30-32	5/12/2021	30 - 32 ft	856.44	857.55	1.11	31.11-33.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-24-26	5/12/2021	24 - 26 ft	856.72	856.50	-0.22	23.78-25.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-26-28	5/12/2021	26 - 28 ft	856.72	856.50	-0.22	25.78-27.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-28-29	5/12/2021	28 - 29 ft	856.72	856.50	-0.22	27.78-28.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-29-31	5/12/2021	29 - 31 ft	856.72	856.50	-0.22	28.78-30.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-14-16	5/12/2021	14 - 16 ft	852.53	854.78	2.25	16.25-18.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-16-18	5/12/2021	16 - 18 ft	852.53	854.78	2.25	18.25-20.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-18-20	5/12/2021	18 - 20 ft	852.53	854.78	2.25	20.25-22.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-20-22	5/12/2021	20 - 22 ft	852.53	854.78	2.25	22.25-24.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-22-24	5/12/2021	22 - 24 ft	852.53	854.78	2.25	24.25-26.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-24-26	5/12/2021	24 - 26 ft	852.53	854.78	2.25	26.25-28.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-26-28	5/12/2021	26 - 28 ft	852.53	854.78	2.25	28.25-30.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-28-30	5/12/2021	28 - 30 ft	852.53	854.78	2.25	30.25-32.25 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-10-12	5/12/2021	10 - 12 ft	854.82	854.84	0.02	10.02-12.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-12-14	5/12/2021	12 - 14 ft	854.82	854.84	0.02	12.02-14.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-14-16	5/12/2021	14 - 16 ft	854.82	854.84	0.02	14.02-16.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-2-4	5/12/2021	2 - 4 ft	854.82	854.84	0.02	2.02-4.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-4-6	5/12/2021	4 - 6 ft	854.82	854.84	0.02	4.02-6.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-6-8	5/12/2021	6 - 8 ft	854.82	854.84	0.02	6.02-8.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-8-10	5/12/2021	8 - 10 ft	854.82	854.84	0.02	8.02-10.02 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-0.17-2	5/12/2021	0.17 - 2 ft	854.82	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	14 - 16 ft	852.28	852.59	0.31	14.31-16.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	0.17 - 2 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	14 - 16 ft	852.28	852.59	0.31	14.31-16.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	18 - 20 ft	852.28	852.59	0.31	18.31-20.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	20 - 22 ft	852.28	852.59	0.31	20.31-22.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	22 - 24 ft	852.28	852.59	0.31	22.31-24.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	24 - 26 ft	852.28	852.59	0.31	24.31-26.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	26 - 28 ft	852.28	852.59	0.31	26.31-28.31 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	0.17 - 2 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	2 - 4 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	4 - 6 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	6 - 8 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	8 - 10 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	10 - 12 ft	853.71	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	12 - 14 ft	853.71	854.79	1.08	13.08-15.08 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	14 - 16 ft	853.71	854.79	1.08	15.08-17.08 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	14 - 16 ft	856.89	856.55	-0.34	13.66-15.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	16 - 18 ft	856.89	856.55	-0.34	15.66-17.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	18 - 20 ft	856.89	856.55	-0.34	17.66-19.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	20 - 22 ft	856.89	856.55	-0.34	19.66-21.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	20 - 22 ft	856.89	856.55	-0.34	19.66-21.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	22 - 24 ft	856.89	856.55	-0.34	21.66-23.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	30 - 32 ft	856.89	856.55	-0.34	29.66-31.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-32-34	5/13/2021	32 - 34 ft	856.89	856.55	-0.34	31.66-33.66 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	24 - 26 ft	856.89	856.55	-0.34	23.66-25.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	26 - 28 ft	856.89	856.55	-0.34	25.66-27.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	28 - 30 ft	856.89	856.55	-0.34	27.66-29.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	30 - 32 ft	856.89	856.55	-0.34	29.66-31.66 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-14-16	5/13/2021	14 - 16 ft	856.49	857.15	0.66	14.66-16.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-16-18	5/13/2021	16 - 18 ft	856.49	857.15	0.66	16.66-18.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-18-20	5/13/2021	18 - 20 ft	856.49	857.15	0.66	18.66-20.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-20-22	5/13/2021	20 - 22 ft	856.49	857.15	0.66	20.66-22.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-22-24	5/13/2021	22 - 24 ft	856.49	857.15	0.66	22.66-24.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-24-26	5/13/2021	24 - 26 ft	856.49	857.15	0.66	24.66-26.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-26-28	5/13/2021	26 - 28 ft	856.49	857.15	0.66	26.66-28.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-28-30	5/13/2021	28 - 30 ft	856.49	857.15	0.66	28.66-30.66 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-14-16	5/13/2021	14 - 16 ft	857.53	857.85	0.32	14.32-16.32 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-16-18	5/13/2021	16 - 18 ft	857.53	857.85	0.32	16.32-18.32 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-18-20	5/13/2021	18 - 20 ft	857.53	857.85	0.32	18.32-20.32 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-20-22	5/13/2021	20 - 22 ft	857.53	857.85	0.32	20.32-22.32 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-22-24	5/13/2021	22 - 24 ft	857.53	857.85	0.32	22.32-24.32 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-24-26	5/13/2021	24 - 26 ft	857.53	857.85	0.32	24.32-26.32 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-16-18	5/13/2021	16 - 18 ft	853.71	854.79	1.08	17.08-19.08 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-18-20	5/13/2021	18 - 20 ft	853.71	854.79	1.08	19.08-21.08 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-14-16	5/14/2021	14 - 16 ft	855.59	856.04	0.45	14.45-16.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-16-18	5/14/2021	16 - 18 ft	855.59	856.04	0.45	16.45-18.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-18-20	5/14/2021	18 - 20 ft	855.59	856.04	0.45	18.45-20.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-20-22	5/14/2021	20 - 22 ft	855.59	856.04	0.45	20.45-22.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-22-24	5/14/2021	22 - 24 ft	855.59	856.04	0.45	22.45-24.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-24-26	5/14/2021	24 - 26 ft	855.59	856.04	0.45	24.45-26.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-26-27	5/14/2021	26 - 27 ft	855.59	856.04	0.45	26.45-27.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-27-29	5/14/2021	27 - 29 ft	855.59	856.04	0.45	27.45-29.45 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-14-16	5/14/2021	14 - 16 ft	856.33	857.11	0.78	14.78-16.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-16-18	5/14/2021	16 - 18 ft	856.33	857.11	0.78	16.78-18.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-18-20	5/14/2021	18 - 20 ft	856.33	857.11	0.78	18.78-20.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-20-22	5/14/2021	20 - 22 ft	856.33	857.11	0.78	20.78-22.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-22-24	5/14/2021	22 - 24 ft	856.33	857.11	0.78	22.78-24.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-24-26	5/14/2021	24 - 26 ft	856.33	857.11	0.78	24.78-26.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-26-28	5/14/2021	26 - 28 ft	856.33	857.11	0.78	26.78-28.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-28-30	5/14/2021	28 - 30 ft	856.33	857.11	0.78	28.78-30.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-30-31	5/14/2021	30 - 31 ft	856.33	857.11	0.78	30.78-31.78 ft	X	-	-	-	-

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-31-33	5/14/2021	31 - 33 ft	856.33	857.11	0.78	31.78-33.78 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	14 - 16 ft	857.50	857.17	-0.33	13.67-15.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	14 - 16 ft	857.50	857.17	-0.33	13.67-15.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	16 - 18 ft	857.50	857.17	-0.33	15.67-17.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	18 - 20 ft	857.50	857.17	-0.33	17.67-19.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	20 - 22 ft	857.50	857.17	-0.33	19.67-21.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	22 - 24 ft	857.50	857.17	-0.33	21.67-23.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	24 - 26 ft	857.50	857.17	-0.33	23.67-25.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	26 - 28 ft	857.50	857.17	-0.33	25.67-27.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	28 - 30 ft	857.50	857.17	-0.33	27.67-29.67 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-14-16	5/14/2021	14 - 16 ft	856.30	857.63	1.33	15.33-17.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-16-18	5/14/2021	16 - 18 ft	856.30	857.63	1.33	17.33-19.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-18-20	5/14/2021	18 - 20 ft	856.30	857.63	1.33	19.33-21.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-20-22	5/14/2021	20 - 22 ft	856.30	857.63	1.33	21.33-23.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-22-24	5/14/2021	22 - 24 ft	856.30	857.63	1.33	23.33-25.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-24-25	5/14/2021	24 - 25 ft	856.30	857.63	1.33	25.33-26.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-25-27	5/14/2021	25 - 27 ft	856.30	857.63	1.33	26.33-28.33 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-14-16	5/15/2021	14 - 16 ft	855.62	854.16	-1.46	12.54-14.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-16-18	5/15/2021	16 - 18 ft	855.62	854.16	-1.46	14.54-16.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-18-20	5/15/2021	18 - 20 ft	855.62	854.16	-1.46	16.54-18.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-20-22	5/15/2021	20 - 22 ft	855.62	854.16	-1.46	18.54-20.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-22-24	5/15/2021	22 - 24 ft	855.62	854.16	-1.46	20.54-22.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-24-26	5/15/2021	24 - 26 ft	855.62	854.16	-1.46	22.54-24.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-14-16	5/15/2021	14 - 16 ft	854.53	854.89	0.36	14.36-16.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-16-18	5/15/2021	16 - 18 ft	854.53	854.89	0.36	16.36-18.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-18-20	5/15/2021	18 - 20 ft	854.53	854.89	0.36	18.36-20.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-20-22	5/15/2021	20 - 22 ft	854.53	854.89	0.36	20.36-22.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-22-23	5/15/2021	22 - 23 ft	854.53	854.89	0.36	22.36-23.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-23-25	5/15/2021	23 - 25 ft	854.53	854.89	0.36	23.36-25.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-14-16	5/15/2021	14 - 16 ft	855.68	856.30	0.62	14.62-16.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-16-18	5/15/2021	16 - 18 ft	855.68	856.30	0.62	16.62-18.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-18-20	5/15/2021	18 - 20 ft	855.68	856.30	0.62	18.62-20.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-20-22	5/15/2021	20 - 22 ft	855.68	856.30	0.62	20.62-22.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-22-24	5/15/2021	22 - 24 ft	855.68	856.30	0.62	22.62-24.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-24-25	5/15/2021	24 - 25 ft	855.68	856.30	0.62	24.62-25.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-25-27	5/15/2021	25 - 27 ft	855.68	856.30	0.62	25.62-27.62 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-26-28	5/16/2021	26 - 28 ft	855.62	854.16	-1.46	24.54-26.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-28-30	5/16/2021	28 - 30 ft	855.62	854.16	-1.46	26.54-28.54 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-14-16	5/16/2021	14 - 16 ft	855.21	855.33	0.12	14.12-16.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-16-18	5/16/2021	16 - 18 ft	855.21	855.33	0.12	16.12-18.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-18-20	5/16/2021	18 - 20 ft	855.21	855.33	0.12	18.12-20.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-20-22	5/16/2021	20 - 22 ft	855.21	855.33	0.12	20.12-22.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-22-23	5/16/2021	22 - 23 ft	855.21	855.33	0.12	22.12-23.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-23-25	5/16/2021	23 - 25 ft	855.21	855.33	0.12	23.12-25.12 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-14-16	5/16/2021	14 - 16 ft	852.79	854.90	2.11	16.11-18.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-16-18	5/16/2021	16 - 18 ft	852.79	854.90	2.11	18.11-20.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-18-20	5/16/2021	18 - 20 ft	852.79	854.90	2.11	20.11-22.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-20-22	5/16/2021	20 - 22 ft	852.79	854.90	2.11	22.11-24.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-22-24	5/16/2021	22 - 24 ft	852.79	854.90	2.11	24.11-26.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-24-26	5/16/2021	24 - 26 ft	852.79	854.90	2.11	26.11-28.11 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	10 - 12 ft	856.37	856.43	0.06	10.06-12.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	12 - 14 ft	856.37	856.43	0.06	12.06-14.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	14 - 16 ft	856.37	856.43	0.06	14.06-16.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	16 - 18 ft	856.37	856.43	0.06	16.06-18.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	4 - 6 ft	856.37	856.43	0.06	4.06-6.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	6 - 8 ft	856.37	856.43	0.06	6.06-8.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	8 - 10 ft	856.37	856.43	0.06	8.06-10.06 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	14 - 16 ft	852.29	853.40	1.11	15.11-17.11 ft	-	-	-	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	16 - 18 ft	852.29	853.40	1.11	17.11-19.11 ft	-	-	-	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	18 - 20 ft	852.29	853.40	1.11	19.11-21.11 ft	-	-	-	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	20 - 22 ft	852.29	853.40	1.11	21.11-23.11 ft	-	-	-	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	22 - 24 ft	852.29	853.40	1.11	23.11-25.11 ft	-	-	-	X	X
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	24 - 26 ft	852.29	853.40	1.11	25.11-27.11 ft	-	-	-	X	X
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-14-16	5/18/2021	14 - 16 ft	854.47	855.96	1.49	15.49-17.49 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	DUP-20	5/18/2021	14 - 16 ft	856.45	856.26	-0.19	13.81-15.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-14-16	5/18/2021	14 - 16 ft	856.45	856.26	-0.19	13.81-15.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-16-18	5/18/2021	16 - 18 ft	856.45	856.26	-0.19	15.81-17.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-18-20	5/18/2021	18 - 20 ft	856.45	856.26	-0.19	17.81-19.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-20-22	5/18/2021	20 - 22 ft	856.45	856.26	-0.19	19.81-21.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-22-24	5/18/2021	22 - 24 ft	856.45	856.26	-0.19	21.81-23.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-24-26	5/18/2021	24 - 26 ft	856.45	856.26	-0.19	23.81-25.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-26-28	5/18/2021	26 - 28 ft	856.45	856.26	-0.19	25.81-27.81 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	4 - 6 ft	855.95	855.66	-0.29	3.71-5.71 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	6 - 8 ft	855.95	855.66	-0.29	5.71-7.71 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	8 - 10 ft	855.95	855.66	-0.29	7.71-9.71 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	10 - 12 ft	855.95	855.66	-0.29	9.71-11.71 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	12 - 14 ft	855.95	855.66	-0.29	11.71-13.71 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	14 - 16 ft	855.95	855.66	-0.29	13.71-15.71 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	14 - 16 ft	853.77	855.45	1.68	15.68-17.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	16 - 18 ft	853.77	855.45	1.68	17.68-19.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	18 - 20 ft	853.77	855.45	1.68	19.68-21.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-16-18	5/19/2021	16 - 18 ft	854.47	855.96	1.49	17.49-19.49 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-18-20	5/19/2021	18 - 20 ft	854.47	855.96	1.49	19.49-21.49 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-20-22	5/19/2021	20 - 22 ft	854.47	855.96	1.49	21.49-23.49 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-22-24	5/19/2021	22 - 24 ft	854.47	855.96	1.49	23.49-25.49 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-24-26	5/19/2021	24 - 26 ft	854.47	855.96	1.49	25.49-27.49 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-26-28	5/19/2021	26 - 28 ft	854.47	855.96	1.49	27.49-29.49 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-16-18	5/19/2021	16 - 18 ft	855.31	855.41	0.10	16.1-18.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	18 - 20 ft	855.31	855.41	0.10	18.1-20.1 ft	X	-	X	X	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-20-22	5/19/2021	20 - 22 ft	855.31	855.41	0.10	20.1-22.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-22-24	5/19/2021	22 - 24 ft	855.31	855.41	0.10	22.1-24.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-24-26	5/19/2021	24 - 26 ft	855.31	855.41	0.10	24.1-26.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	DUP-203	5/19/2021	26 - 28 ft	855.31	855.41	0.10	26.1-28.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-26-28	5/19/2021	26 - 28 ft	855.31	855.41	0.10	26.1-28.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	DUP-204	5/19/2021	28 - 30 ft	855.31	855.41	0.10	28.1-30.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-28-30	5/19/2021	28 - 30 ft	855.31	855.41	0.10	28.1-30.1 ft	X	-	-	-	-
Football Field	SSHS-B4013	DUP-206	5/19/2021	16 - 18 ft	855.81	855.80	-0.01	15.99-17.99 ft	X	-	X	X	-
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	16 - 18 ft	855.81	855.80	-0.01	15.99-17.99 ft	X	-	X	X	-
Football Field	SSHS-B4013	SSHS-B4013-SUB-18-20	5/19/2021	18 - 20 ft	855.81	855.80	-0.01	17.99-19.99 ft	X	-	-	-	-
Football Field	SSHS-B4013	SSHS-B4013-SUB-28-30	5/19/2021	28 - 30 ft	855.81	855.80	-0.01	27.99-29.99 ft	X	-	-	-	-
Football Field	SSHS-B4013	SSHS-B4013-SUB-30-32	5/19/2021	30 - 32 ft	855.81	855.80	-0.01	29.99-31.99 ft	X	-	-	-	-
Football Field	SSHS-B4013	SSHS-B4013-SUB-32-34	5/19/2021	32 - 34 ft	855.81	855.80	-0.01	31.99-33.99 ft	X	-	-	-	-
Football Field	SSHS-B4013	SSHS-B4013-SUB-34-36	5/19/2021	34 - 36 ft	855.81	855.80	-0.01	33.99-35.99 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	14 - 16 ft	853.77	855.45	1.68	15.68-17.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	20 - 22 ft	853.77	855.45	1.68	21.68-23.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	28 - 30 ft	853.77	855.45	1.68	29.68-31.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	22 - 24 ft	853.77	855.45	1.68	23.68-25.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	24 - 26 ft	853.77	855.45	1.68	25.68-27.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	26 - 28 ft	853.77	855.45	1.68	27.68-29.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	28 - 30 ft	853.77	855.45	1.68	29.68-31.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	20 - 22 ft	853.77	855.45	1.68	21.68-23.68 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16	5/19/2021	14 - 16 ft	856.98	855.02	-1.96	12.04-14.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18	5/19/2021	16 - 18 ft	856.98	855.02	-1.96	14.04-16.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-18-20	5/19/2021	18 - 20 ft	856.98	855.02	-1.96	16.04-18.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-20-22	5/19/2021	20 - 22 ft	856.98	855.02	-1.96	18.04-20.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-22-24	5/19/2021	22 - 24 ft	856.98	855.02	-1.96	20.04-22.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-24-26	5/19/2021	24 - 26 ft	856.98	855.02	-1.96	22.04-24.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-26-28	5/19/2021	26 - 28 ft	856.98	855.02	-1.96	24.04-26.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-28-30	5/19/2021	28 - 30 ft	856.98	855.02	-1.96	26.04-28.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-30-31	5/19/2021	30 - 31 ft	856.98	855.02	-1.96	28.04-29.04 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	31 - 33 ft	856.98	855.02	-1.96	29.04-31.04 ft	X	X	X	X	X
Football Field	SSHS-B4009	SSHS-B4009-SUB-16-18	5/20/2021	16 - 18 ft	855.17	855.25	0.08	16.08-18.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	DUP-200	5/20/2021	18 - 20 ft	855.17	855.25	0.08	18.08-20.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	18 - 20 ft	855.17	855.25	0.08	18.08-20.08 ft	X	-	X	X	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	20 - 22 ft	855.17	855.25	0.08	20.08-22.08 ft	X	-	X	X	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	22 - 24 ft	855.17	855.25	0.08	22.08-24.08 ft	X	-	X	X	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-24-26	5/20/2021	24 - 26 ft	855.17	855.25	0.08	24.08-26.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-26-28	5/20/2021	26 - 28 ft	855.17	855.25	0.08	26.08-28.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-28-30	5/20/2021	28 - 30 ft	855.17	855.25	0.08	28.08-30.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-30-32	5/20/2021	30 - 32 ft	855.17	855.25	0.08	30.08-32.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	32 - 34 ft	855.17	855.25	0.08	32.08-34.08 ft	X	-	X	X	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-34-36	5/20/2021	34 - 36 ft	855.17	855.25	0.08	34.08-36.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-36-38	5/20/2021	36 - 38 ft	855.17	855.25	0.08	36.08-38.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-38-40	5/20/2021	38 - 40 ft	855.17	855.25	0.08	38.08-40.08 ft	X	-	-	-	-
Football Field	SSHS-B4009	SSHS-B4009-SUB-40-42	5/20/2021	40 - 42 ft	855.17	855.25	0.08	40.08-42.08 ft	X	-	-	-	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	16 - 18 ft	855.47	855.47	0.00	16-18 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	18 - 20 ft	855.47	855.47	0.00	18-20 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	20 - 22 ft	855.47	855.47	0.00	20-22 ft	X	-	X	X	-
Football Field	SSHS-B4010	DUP-201	5/20/2021	22 - 24 ft	855.47	855.47	0.00	22-24 ft	X	-	-	-	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	22 - 24 ft	855.47	855.47	0.00	22-24 ft	X	-	X	X	-
Football Field	SSHS-B4010	DUP-202	5/20/2021	24 - 26 ft	855.47	855.47	0.00	24-26 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	24 - 26 ft	855.47	855.47	0.00	24-26 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	26 - 28 ft	855.47	855.47	0.00	26-28 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-28-30	5/20/2021	28 - 30 ft	855.47	855.47	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-30-32	5/20/2021	30 - 32 ft	855.47	855.47	0.00	30-32 ft	X	-	-	-	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-32-33	5/20/2021	32 - 33 ft	855.47	855.47	0.00	32-33 ft	X	-	-	-	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	33 - 35 ft	855.47	855.47	0.00	33-35 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	35 - 37 ft	855.47	855.47	0.00	35-37 ft	X	-	X	X	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-37-39	5/20/2021	37 - 39 ft	855.47	855.47	0.00	37-39 ft	X	-	-	-	-
Football Field	SSHS-B4010	SSHS-B4010-SUB-39-41	5/20/2021	39 - 41 ft	855.47	855.47	0.00	39-41 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-32-34	5/20/2021	32 - 34 ft	855.31	855.41	0.10	32.1-34.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-30-32	5/20/2021	30 - 32 ft	855.31	855.41	0.10	30.1-32.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-34-36	5/20/2021	34 - 36 ft	855.31	855.41	0.10	34.1-36.1 ft	X	-	-	-	-
Football Field	SSHS-B4011	SSHS-B4011-SUB-36-38	5/20/2021	36 - 38 ft	855.31	855.41	0.10	36.1-38.1 ft	X	-	-	-	-
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	18 - 20 ft	855.04	855.41	0.37	18.37-20.37 ft	X	-	X	X	-
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	20 - 22 ft	855.04	855.41	0.37	20.37-22.37 ft	X	-	X	X	-
Football Field	SSHS-B4012	SSHS-B4012-SUB-30-32	5/21/2021	30 - 32 ft	855.04	855.41	0.37	30.37-32.37 ft	X	-	-	-	-
Football Field	SSHS-B4012	DUP-205	5/21/2021	32 - 34 ft	855.04	855.41	0.37	32.37-34.37 ft	X	-	-	-	-
Football Field	SSHS-B4012	SSHS-B4012-SUB-32-34	5/21/2021	32 - 34 ft	855.04	855.41	0.37	32.37-34.37 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-14-16	6/10/2021	14 - 16 ft	856.20	856.23	0.03	14.03-16.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-16-18	6/10/2021	16 - 18 ft	856.20	856.23	0.03	16.03-18.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-18-20	6/10/2021	18 - 20 ft	856.20	856.23	0.03	18.03-20.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-20-22	6/10/2021	20 - 22 ft	856.20	856.23	0.03	20.03-22.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-22-24	6/10/2021	22 - 24 ft	856.20	856.23	0.03	22.03-24.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-24-26	6/10/2021	24 - 26 ft	856.20	856.23	0.03	24.03-26.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-26-28	6/10/2021	26 - 28 ft	856.20	856.23	0.03	26.03-28.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-14-16	6/11/2021	14 - 16 ft	855.61	855.81	0.20	14.2-16.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-16-18	6/11/2021	16 - 18 ft	855.61	855.81	0.20	16.2-18.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-18-20	6/11/2021	18 - 20 ft	855.61	855.81	0.20	18.2-20.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-20-22	6/11/2021	20 - 22 ft	855.61	855.81	0.20	20.2-22.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-22-24	6/11/2021	22 - 24 ft	855.61	855.81	0.20	22.2-24.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-24-26	6/11/2021	24 - 26 ft	855.61	855.81	0.20	24.2-26.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-26-28	6/11/2021	26 - 28 ft	855.61	855.81	0.20	26.2-28.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-28-30	6/11/2021	28 - 30 ft	855.61	855.81	0.20	28.2-30.2 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-14-16	6/11/2021	14 - 16 ft	855.12	855.85	0.73	14.73-16.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-16-18	6/11/2021	16 - 18 ft	855.12	855.85	0.73	16.73-18.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-18-20	6/11/2021	18 - 20 ft	855.12	855.85	0.73	18.73-20.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-20-22	6/11/2021	20 - 22 ft	855.12	855.85	0.73	20.73-22.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-22-24	6/11/2021	22 - 24 ft	855.12	855.85	0.73	22.73-24.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-24-26	6/11/2021	24 - 26 ft	855.12	855.85	0.73	24.73-26.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-26-28	6/11/2021	26 - 28 ft	855.12	855.85	0.73	26.73-28.73 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-10-12	6/17/2021	10 - 12 ft	853.79	853.15	-0.64	9.36-11.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-14-16	6/17/2021	14 - 16 ft	853.79	853.15	-0.64	13.36-15.36 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	12 - 14 ft	853.79	853.15	-0.64	11.36-13.36 ft	X	-	X	X	-
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-10-12	6/17/2021	10 - 12 ft	854.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-12-14	6/17/2021	12 - 14 ft	854.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-14-16	6/17/2021	14 - 16 ft	854.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-4-6	6/17/2021	4 - 6 ft	854.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-6-8	6/17/2021	6 - 8 ft	854.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-8-10	6/17/2021	8 - 10 ft	854.13	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3930A	SSHS-B3930A-SUB-8-10	6/17/2021	8 - 10 ft	856.76	855.86	-0.90	7.1-9.1 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-4-6	6/17/2021	4 - 6 ft	856.63	-	-	-	-	-	-	X	-
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-10-12	6/17/2021	10 - 12 ft	856.63	855.62	-1.01	8.99-10.99 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-6-8	6/17/2021	6 - 8 ft	856.63	855.62	-1.01	4.99-6.99 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-8-10	6/17/2021	8 - 10 ft	856.63	855.62	-1.01	6.99-8.99 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-4-6	6/17/2021	4 - 6 ft	857.09	-	-	-	-	-	-	X	-
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-10-12	6/17/2021	10 - 12 ft	857.09	855.85	-1.24	8.76-10.76 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-6-8	6/17/2021	6 - 8 ft	857.09	855.85	-1.24	4.76-6.76 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-8-10	6/17/2021	8 - 10 ft	857.09	855.85	-1.24	6.76-8.76 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-10-12	6/17/2021	10 - 12 ft	856.55	855.68	-0.87	9.13-11.13 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-4-6	6/17/2021	4 - 6 ft	856.55	855.68	-0.87	3.13-5.13 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-6-8	6/17/2021	6 - 8 ft	856.55	855.68	-0.87	5.13-7.13 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-8-10	6/17/2021	8 - 10 ft	856.55	855.68	-0.87	7.13-9.13 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-4-6	6/17/2021	4 - 6 ft	856.72	-	-	-	-	-	-	X	-
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-10-12	6/17/2021	10 - 12 ft	856.72	855.95	-0.77	9.23-11.23 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-6-8	6/17/2021	6 - 8 ft	856.72	855.95	-0.77	5.23-7.23 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-8-10	6/17/2021	8 - 10 ft	856.72	855.95	-0.77	7.23-9.23 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-4-6	6/17/2021	4 - 6 ft	856.53	-	-	-	-	-	-	X	-
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-6-8	6/17/2021	6 - 8 ft	856.53	856.13	-0.40	5.6-7.6 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3884A	SSHS-B3884A-SUB-12-14	6/18/2021	12 - 14 ft	853.49	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-12-14	6/18/2021	12 - 14 ft	854.11	857.72	3.61	15.61-17.61 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-14-16	6/18/2021	14 - 16 ft	854.11	857.72	3.61	17.61-19.61 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-16-18	6/18/2021	16 - 18 ft	854.11	857.72	3.61	19.61-21.61 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-18-20	6/18/2021	18 - 20 ft	854.11	857.72	3.61	21.61-23.61 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-12-14	6/18/2021	12 - 14 ft	854.03	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-14-16	6/18/2021	14 - 16 ft	854.03	857.60	3.57	17.57-19.57 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-16-18	6/18/2021	16 - 18 ft	854.03	857.60	3.57	19.57-21.57 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-18-20	6/18/2021	18 - 20 ft	854.03	857.60	3.57	21.57-23.57 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-12-14	6/18/2021	12 - 14 ft	853.31	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-14-16	6/18/2021	14 - 16 ft	853.31	857.20	3.89	17.89-19.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-16-18	6/18/2021	16 - 18 ft	853.31	857.20	3.89	19.89-21.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-18-20	6/18/2021	18 - 20 ft	853.31	857.20	3.89	21.89-23.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-20-22	6/18/2021	20 - 22 ft	853.31	857.20	3.89	23.89-25.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-16-18	6/18/2021	16 - 18 ft	853.29	857.05	3.76	19.76-21.76 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-12-14	6/18/2021	12 - 14 ft	853.29	857.05	3.76	15.76-17.76 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-14-16	6/18/2021	14 - 16 ft	853.29	857.05	3.76	17.76-19.76 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-18-20	6/18/2021	18 - 20 ft	853.29	857.05	3.76	21.76-23.76 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-10-12	6/18/2021	10 - 12 ft	853.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-4-6	6/18/2021	4 - 6 ft	853.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-6-8	6/18/2021	6 - 8 ft	853.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-8-10	6/18/2021	8 - 10 ft	853.07	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-12-14	6/18/2021	12 - 14 ft	853.07	854.10	1.03	13.03-15.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-14-16	6/18/2021	14 - 16 ft	853.07	854.10	1.03	15.03-17.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-16-18	6/18/2021	16 - 18 ft	853.07	854.10	1.03	17.03-19.03 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-10-12	6/18/2021	10 - 12 ft	854.16	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-6-8	6/18/2021	6 - 8 ft	854.16	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-4-6	6/18/2021	4 - 6 ft	854.16	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-8-10	6/18/2021	8 - 10 ft	854.16	-	-	-	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-12-14	6/18/2021	12 - 14 ft	854.16	854.85	0.69	12.69-14.69 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-14-16	6/18/2021	14 - 16 ft	854.16	854.85	0.69	14.69-16.69 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-16-18	6/18/2021	16 - 18 ft	854.16	854.85	0.69	16.69-18.69 ft	X	-	-	-	-
Football Field	SSHS-B3526	DUP-7	6/22/2021	8 - 10 ft	855.55	855.94	0.39	8.39-10.39 ft	X	-	-	-	-
Football Field	SSHS-B3526	SSHS-B3526-SUB-8-10	6/22/2021	8 - 10 ft	855.55	855.94	0.39	8.39-10.39 ft	X	-	-	-	-
Football Field	SSHS-B3527	DUP-8	6/22/2021	8 - 10 ft	855.96	856.08	0.12	8.12-10.12 ft	X	-	-	-	-
Football Field	SSHS-B3527	SSHS-B3527-SUB-8-10	6/22/2021	8 - 10 ft	855.96	856.08	0.12	8.12-10.12 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-14-16	6/30/2021	14 - 16 ft	855.88	855.88	0.00	14-16 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	16 - 18 ft	855.88	855.88	0.00	16-18 ft	X	-	X	X	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	18 - 20 ft	855.88	855.88	0.00	18-20 ft	X	-	X	X	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-20-22	6/30/2021	20 - 22 ft	855.88	855.88	0.00	20-22 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-22-24	6/30/2021	22 - 24 ft	855.88	855.88	0.00	22-24 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	24 - 26 ft	855.88	855.88	0.00	24-26 ft	X	-	X	X	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-26-28	6/30/2021	26 - 28 ft	855.88	855.88	0.00	26-28 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-28-30	6/30/2021	28 - 30 ft	855.88	855.88	0.00	28-30 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-30-32	6/30/2021	30 - 32 ft	855.88	855.88	0.00	30-32 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-32-34	6/30/2021	32 - 34 ft	855.88	855.88	0.00	32-34 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-34-36	6/30/2021	34 - 36 ft	855.88	855.88	0.00	34-36 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-36-38	6/30/2021	36 - 38 ft	855.88	855.88	0.00	36-38 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-38-40	6/30/2021	38 - 40 ft	855.88	855.88	0.00	38-40 ft	X	-	-	-	-
Football Field	SSHS-B4015	SSHS-B4015-SUB-40-42	6/30/2021	40 - 42 ft	855.88	855.88	0.00	40-42 ft	X	-	-	-	-
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	14 - 16 ft	855.99	855.97	-0.02	13.98-15.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	16 - 18 ft	855.99	855.97	-0.02	15.98-17.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	18 - 20 ft	855.99	855.97	-0.02	17.98-19.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	20 - 22 ft	855.99	855.97	-0.02	19.98-21.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	22 - 24 ft	855.99	855.97	-0.02	21.98-23.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	24 - 26 ft	855.99	855.97	-0.02	23.98-25.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	26 - 28 ft	855.99	855.97	-0.02	25.98-27.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	28 - 30 ft	855.99	855.97	-0.02	27.98-29.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	30 - 32 ft	855.99	855.97	-0.02	29.98-31.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	32 - 34 ft	855.99	855.97	-0.02	31.98-33.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	34 - 36 ft	855.99	855.97	-0.02	33.98-35.98 ft	X	X	X	X	X

DRAFT

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	36 - 38 ft	855.99	855.97	-0.02	35.98-37.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	38 - 40 ft	855.99	855.97	-0.02	37.98-39.98 ft	X	X	X	X	X
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	40 - 42 ft	855.99	855.97	-0.02	39.98-41.98 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	26 - 28 ft	853.40	855.25	1.85	27.85-29.85 ft	X	-	X	X	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	24 - 26 ft	853.40	855.25	1.85	25.85-27.85 ft	X	-	X	X	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	28 - 30 ft	853.40	855.25	1.85	29.85-31.85 ft	X	-	X	X	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-14-16	7/1/2021	14 - 16 ft	853.40	855.25	1.85	15.85-17.85 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-16-18	7/1/2021	16 - 18 ft	853.40	855.25	1.85	17.85-19.85 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-18-20	7/1/2021	18 - 20 ft	853.40	855.25	1.85	19.85-21.85 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	30 - 32 ft	853.40	855.25	1.85	31.85-33.85 ft	X	-	X	X	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-20-22	7/1/2021	20 - 22 ft	853.40	855.25	1.85	21.85-23.85 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-22-24	7/1/2021	22 - 24 ft	853.40	855.25	1.85	23.85-25.85 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	0 - 0.17 ft	856.80	856.80	0.00	0 - 0.17 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	0.17 - 1 ft	856.80	856.80	0.00	0.17 - 1 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	1 - 2 ft	856.80	856.80	0.00	1 - 2 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	2 - 4 ft	856.80	856.80	0.00	2 - 4 ft	-	X	X	-	-
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	4 - 6 ft	856.80	856.80	0.00	4 - 6 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	0 - 0.17 ft	857.47	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	0.17 - 1 ft	857.47	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	1 - 2 ft	857.47	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	2 - 4 ft	857.47	857.20	-0.27	1.73-3.73 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	2 - 4 ft	857.47	857.20	-0.27	1.73-3.73 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	4 - 6 ft	857.47	857.20	-0.27	3.73-5.73 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	0 - 0.17 ft	856.76	-	-	-	-	-	X	X	-
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	0.17 - 1 ft	856.76	-	-	-	-	-	X	X	-
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	1 - 2 ft	856.76	-	-	-	-	-	X	X	-
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	2 - 4 ft	856.76	856.40	-0.36	1.64-3.64 ft	-	-	X	X	-
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	0 - 0.17 ft	856.62	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	0 - 0.17 ft	856.62	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	0 - 0.17 ft	856.74	856.72	-0.02	0-0.15 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	0 - 0.17 ft	856.88	856.88	0.00	0-0.17 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	0 - 0.17 ft	857.18	857.19	0.01	0.01-0.18 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	0 - 0.17 ft	857.75	857.80	0.05	0.05-0.22 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	4 - 6 ft	857.11	856.25	-0.86	3.14-5.14 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	4 - 6 ft	856.99	856.10	-0.89	3.11-5.11 ft	-	-	X	-	-
Northern Athletic Field	SSHS-B4027	SSHS-B4027-SUB-4-6	7/1/2021	4 - 6 ft	856.99	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3096A	SSHS-B3096A-SUB-2-4	7/19/2021	2 - 4 ft	855.86	-	-	-	-	-	X	-	-
Northern Athletic Field	SSHS-B3602	SSHS-B3602-SUB-16-18	7/19/2021	16 - 18 ft	852.97	855.09	2.12	18.12-20.12 ft	X	-	-	-	-
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	0 - 0.17 ft	848.28	848.28	0.00	0 - 0.17 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	0.17 - 2 ft	848.28	848.28	0.00	0.17 - 2 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	2 - 4 ft	848.28	848.28	0.00	2 - 4 ft	X	X	-	-	-
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	4 - 6 ft	848.28	848.28	0.00	4 - 6 ft	-	X	-	-	-
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	6 - 8 ft	848.28	848.28	0.00	6 - 8 ft	-	X	-	-	-
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	8 - 10 ft	848.28	848.28	0.00	8 - 10 ft	-	X	-	-	-
Rear Parking Lot	SSHS-B3840	SSHS-B3840	7/23/2021	10 - 12 ft	847.79	847.79	0.00	10 - 12 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3012A	SSHS-B3012A-SUB-14-16	7/26/2021	14 - 16 ft	853.25	856.18	2.93	16.93-18.93 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3012A	SSHS-B3012A-SUB-16-18	7/26/2021	16 - 18 ft	853.25	856.18	2.93	18.93-20.93 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3013A	SSHS-B3013A-SUB-14-16	7/26/2021	14 - 16 ft	852.88	857.02	4.14	18.14-20.14 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3013A	SSHS-B3013A-SUB-16-18	7/26/2021	16 - 18 ft	852.88	857.02	4.14	20.14-22.14 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3925A	SSHS-B3925A-SUB-16-18	7/26/2021	16 - 18 ft	853.31	857.20	3.89	19.89-21.89 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-12-14	7/26/2021	12 - 14 ft	853.87	857.04	3.17	15.17-17.17 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-14-16	7/26/2021	14 - 16 ft	853.87	857.04	3.17	17.17-19.17 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-16-18	7/26/2021	16 - 18 ft	853.87	857.04	3.17	19.17-21.17 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	16 - 18 ft	856.82	856.75	-0.07	15.93-17.93 ft	-	-	X	X	-
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	16 - 18 ft	856.70	856.66	-0.04	15.96-17.96 ft	-	-	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	12 - 14 ft	855.73	855.73	0.00	12-14 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	14 - 16 ft	855.73	855.73	0.00	14-16 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	4 - 6 ft	855.73	855.73	0.00	4-6 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	0 - 0.17 ft	855.73	855.73	0.00	0-0.17 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	0.17 - 2 ft	855.73	855.73	0.00	0.17-2 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	10 - 12 ft	855.73	855.73	0.00	10-12 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	16 - 18 ft	855.73	855.73	0.00	16-18 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	18 - 20 ft	855.73	855.73	0.00	18-20 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	2 - 4 ft	855.73	855.73	0.00	2-4 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	6 - 8 ft	855.73	855.73	0.00	6-8 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	8 - 10 ft	855.73	855.73	0.00	8-10 ft	X	X	X	X	X
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	0.17 - 2 ft	855.97	855.97	0.00	0.17-2 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	10 - 12 ft	855.97	855.97	0.00	10-12 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	12 - 14 ft	855.97	855.97	0.00	12-14 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	14 - 16 ft	855.97	855.97	0.00	14-16 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	2 - 4 ft	855.97	855.97	0.00	2-4 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	4 - 6 ft	855.97	855.97	0.00	4-6 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	6 - 8 ft	855.97	855.97	0.00	6-8 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	8 - 10 ft	855.97	855.97	0.00	8-10 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	0 - 0.17 ft	856.07	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	0.17 - 2 ft	856.07	-	-	-	X	X	X	X	X
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	2 - 4 ft	856.07	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	4 - 6 ft	856.07	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	6 - 8 ft	856.07	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	10 - 12 ft	856.07	856.16	0.09	10.09-12.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	12 - 14 ft	856.07	856.16	0.09	12.09-14.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	14 - 16 ft	856.07	856.16	0.09	14.09-16.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	16 - 18 ft	856.07	856.16	0.09	16.09-18.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	18 - 20 ft	856.07	856.16	0.09	18.09-20.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	20 - 22 ft	856.07	856.16	0.09	20.09-22.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	22 - 24 ft	856.07	856.16	0.09	22.09-24.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	24 - 26 ft	856.07	856.16	0.09	24.09-26.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	26 - 28 ft	856.07	856.16	0.09	26.09-28.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	28 - 30 ft	856.07	856.16	0.09	28.09-30.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	30 - 32 ft	856.07	856.16	0.09	30.09-32.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	32 - 34 ft	856.07	856.16	0.09	32.09-34.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	34 - 36 ft	856.07	856.16	0.09	34.09-36.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	36 - 38 ft	856.07	856.16	0.09	36.09-38.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	38 - 40 ft	856.07	856.16	0.09	38.09-40.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	40 - 42 ft	856.07	856.16	0.09	40.09-42.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	42 - 44 ft	856.07	856.16	0.09	42.09-44.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	44 - 46 ft	856.07	856.16	0.09	44.09-46.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	46 - 48 ft	856.07	856.16	0.09	46.09-48.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	48 - 50 ft	856.07	856.16	0.09	48.09-50.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	50 - 52 ft	856.07	856.16	0.09	50.09-52.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	52 - 54 ft	856.07	856.16	0.09	52.09-54.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	54 - 56 ft	856.07	856.16	0.09	54.09-56.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	8 - 10 ft	856.07	856.16	0.09	8.09-10.09 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3853	SSHS-B3853-SUB-6-8	9/16/2021	6 - 8 ft	856.30	856.51	0.21	6.21-8.21 ft	-	X	-	-	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	0 - 0.17 ft	856.64	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	2 - 4 ft	856.64	-	-	-	-	-	X	X	X
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	4 - 6 ft	856.64	-	-	-	-	-	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	20 - 22 ft	856.64	856.68	0.04	20.04-22.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	10 - 12 ft	856.64	856.68	0.04	10.04-12.04 ft	-	-	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	12 - 14 ft	856.64	856.68	0.04	12.04-14.04 ft	-	-	X	-	X
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	14 - 16 ft	856.64	856.68	0.04	14.04-16.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	16 - 18 ft	856.64	856.68	0.04	16.04-18.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	18 - 20 ft	856.64	856.68	0.04	18.04-20.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	22 - 24 ft	856.64	856.68	0.04	22.04-24.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	24 - 26 ft	856.64	856.68	0.04	24.04-26.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	26 - 28 ft	856.64	856.68	0.04	26.04-28.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	28 - 30 ft	856.64	856.68	0.04	28.04-30.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	30 - 32 ft	856.64	856.68	0.04	30.04-32.04 ft	X	X	X	-	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	32 - 34 ft	856.64	856.68	0.04	32.04-34.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	34 - 36 ft	856.64	856.68	0.04	34.04-36.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	36 - 38 ft	856.64	856.68	0.04	36.04-38.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	38 - 40 ft	856.64	856.68	0.04	38.04-40.04 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	6 - 8 ft	856.64	856.68	0.04	6.04-8.04 ft	-	-	X	X	X
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	8 - 10 ft	856.64	856.68	0.04	8.04-10.04 ft	-	-	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	10 - 12 ft	858.24	858.24	0.00	10-12 ft	-	X	-	X	X
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	12 - 14 ft	858.24	858.24	0.00	12-14 ft	-	X	-	X	-
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	14 - 16 ft	858.24	858.24	0.00	14-16 ft	-	X	-	X	X
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	16 - 18 ft	858.24	858.24	0.00	16-18 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	18 - 20 ft	858.24	858.24	0.00	18-20 ft	X	X	X	X	-
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	2 - 4 ft	858.24	858.24	0.00	2-4 ft	-	X	-	X	X
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	4 - 6 ft	858.24	858.24	0.00	4-6 ft	-	X	-	X	-
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	6 - 8 ft	858.24	858.24	0.00	6-8 ft	-	X	-	X	X
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	8 - 10 ft	858.24	858.24	0.00	8-10 ft	-	X	-	X	-
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	10 - 12 ft	857.91	857.91	0.00	10-12 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	12 - 14 ft	857.91	857.91	0.00	12-14 ft	X	X	X	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	14 - 16 ft	857.91	857.91	0.00	14-16 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	16 - 18 ft	857.91	857.91	0.00	16-18 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	18 - 20 ft	857.91	857.91	0.00	18-20 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	2 - 4 ft	857.91	857.91	0.00	2-4 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	4 - 6 ft	857.91	857.91	0.00	4-6 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	6 - 8 ft	857.91	857.91	0.00	6-8 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	8 - 10 ft	857.91	857.91	0.00	8-10 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-14-16	9/22/2021	14 - 16 ft	854.12	856.10	1.98	15.98-17.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-16-18	9/22/2021	16 - 18 ft	854.12	856.10	1.98	17.98-19.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-18-20	9/22/2021	18 - 20 ft	854.12	856.10	1.98	19.98-21.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-22-24	9/22/2021	22 - 24 ft	854.12	856.10	1.98	23.98-25.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-24-25	9/22/2021	24 - 25 ft	854.12	856.10	1.98	25.98-26.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-25-27	9/22/2021	25 - 27 ft	854.12	856.10	1.98	26.98-28.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-27-29	9/22/2021	27 - 29 ft	854.12	856.10	1.98	28.98-30.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	18 - 20 ft	856.72	856.72	0.00	18-20 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	4 - 6 ft	856.72	856.72	0.00	4-6 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	10 - 12 ft	856.72	856.72	0.00	10-12 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	12 - 14 ft	856.72	856.72	0.00	12-14 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	14 - 16 ft	856.72	856.72	0.00	14-16 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	16 - 18 ft	856.72	856.72	0.00	16-18 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	2 - 4 ft	856.72	856.72	0.00	2-4 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	6 - 8 ft	856.72	856.72	0.00	6-8 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	8 - 10 ft	856.72	856.72	0.00	8-10 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/23/2021	30 - 32 ft	856.64	856.68	0.04	30.04-32.04 ft	-	-	-	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	0.17 - 2 ft	856.42	856.42	0.00	0.17-2 ft	-	X	X	X	X
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	10 - 12 ft	856.42	856.42	0.00	10-12 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	12 - 14 ft	856.42	856.42	0.00	12-14 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	14 - 16 ft	856.42	856.42	0.00	14-16 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	16 - 18 ft	856.42	856.42	0.00	16-18 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	18 - 20 ft	856.42	856.42	0.00	18-20 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	2 - 4 ft	856.42	856.42	0.00	2-4 ft	X	X	X	X	-
Football Field	SSHS-B4164	DUP-20	9/23/2021	4 - 6 ft	856.42	856.42	0.00	4-6 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	4 - 6 ft	856.42	856.42	0.00	4-6 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	6 - 8 ft	856.42	856.42	0.00	6-8 ft	X	X	X	X	-
Football Field	SSHS-B4164	DUP-21	9/23/2021	8 - 10 ft	856.42	856.42	0.00	8-10 ft	X	X	X	X	-
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	8 - 10 ft	856.42	856.42	0.00	8-10 ft	X	X	X	X	-
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	6 - 8 ft	856.00	856.00	0.00	6-8 ft	-	-	X	X	X
Football Field	SSHS-B4165	SSHS-B4165-SUB-0.17-2	9/23/2021	0.17 - 2 ft	856.00	856.00	0.00	0.17-2 ft	X	-	-	-	-
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	12 - 14 ft	856.00	856.00	0.00	12-14 ft	-	-	X	-	X
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	10 - 12 ft	856.00	856.00	0.00	10-12 ft	-	-	X	X	X
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	14 - 16 ft	856.00	856.00	0.00	14-16 ft	X	X	X	X	-
Football Field	SSHS-B4165	DUP-22	9/23/2021	16 - 18 ft	856.00	856.00	0.00	16-18 ft	X	X	-	X	-
Football Field	SSHS-B4165	DUP-39	9/23/2021	18 - 20 ft	856.00	856.00	0.00	18-20 ft	X	X	-	-	-
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	16 - 18 ft	856.00	856.00	0.00	16-18 ft	X	X	X	X	X
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	18 - 20 ft	856.00	856.00	0.00	18-20 ft	X	X	X	X	-
Football Field	SSHS-B4165	SSHS-B4165-SUB-2-4	9/23/2021	2 - 4 ft	856.00	856.00	0.00	2-4 ft	-	-	-	X	-
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	4 - 6 ft	856.00	856.00	0.00	4-6 ft	-	-	X	X	-
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	8 - 10 ft	856.00	856.00	0.00	8-10 ft	-	-	X	X	-
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-26-28	10/25/2021	26 - 28 ft	853.65	857.32	3.67	29.67-31.67 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-24-26	10/25/2021	24 - 26 ft	853.65	857.32	3.67	27.67-29.67 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-20-22	10/25/2021	20 - 22 ft	853.31	854.91	1.60	21.6-23.6 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-22-24	10/25/2021	22 - 24 ft	853.31	854.91	1.60	23.6-25.6 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-20-22	10/25/2021	20 - 22 ft	852.55	853.09	0.54	20.54-22.54 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-22-24	10/25/2021	22 - 24 ft	852.55	853.09	0.54	22.54-24.54 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-24-26	10/25/2021	24 - 26 ft	852.55	853.09	0.54	24.54-26.54 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-26-28	10/25/2021	26 - 28 ft	852.55	853.09	0.54	26.54-28.54 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-28-30	10/25/2021	28 - 30 ft	852.55	853.09	0.54	28.54-30.54 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-20-22	10/25/2021	20 - 22 ft	854.31	857.88	3.57	23.57-25.57 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-22-24	10/25/2021	22 - 24 ft	854.31	857.88	3.57	25.57-27.57 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-24-26	10/25/2021	24 - 26 ft	854.31	857.88	3.57	27.57-29.57 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-20-22	10/25/2021	20 - 22 ft	853.70	857.40	3.70	23.7-25.7 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-22-24	10/25/2021	22 - 24 ft	853.70	857.40	3.70	25.7-27.7 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-24-26	10/25/2021	24 - 26 ft	853.70	857.40	3.70	27.7-29.7 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-26-28	10/26/2021	26 - 28 ft	854.31	857.88	3.57	29.57-31.57 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-28-30	10/26/2021	28 - 30 ft	854.31	857.88	3.57	31.57-33.57 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-20-22	10/26/2021	20 - 22 ft	854.78	855.87	1.09	21.09-23.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-22-24	10/26/2021	22 - 24 ft	854.78	855.87	1.09	23.09-25.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-24-26	10/26/2021	24 - 26 ft	854.78	855.87	1.09	25.09-27.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-26-28	10/26/2021	26 - 28 ft	854.78	855.87	1.09	27.09-29.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-28-30	10/26/2021	28 - 30 ft	854.78	855.87	1.09	29.09-31.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-30-32	10/27/2021	30 - 32 ft	854.78	855.87	1.09	31.09-33.09 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-20-22	11/1/2021	20 - 22 ft	854.12	856.10	1.98	21.98-23.98 ft	X	-	-	-	-
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-20-22	11/1/2021	20 - 22 ft	854.60	858.21	3.61	23.61-25.61 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-22-24	11/1/2021	22 - 24 ft	854.60	858.21	3.61	25.61-27.61 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-24-26	11/1/2021	24 - 26 ft	854.60	858.21	3.61	27.61-29.61 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-26-28	11/1/2021	26 - 28 ft	854.60	858.21	3.61	29.61-31.61 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-0.17-2	11/1/2021	0.17 - 2 ft	852.29	-	-	-	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-2-4	11/1/2021	2 - 4 ft	852.29	-	-	-	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-10-12	11/1/2021	10 - 12 ft	852.29	853.31	1.02	11.02-13.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-12-14	11/1/2021	12 - 14 ft	852.29	853.31	1.02	13.02-15.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-14-16	11/1/2021	14 - 16 ft	852.29	853.31	1.02	15.02-17.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-16-18	11/1/2021	16 - 18 ft	852.29	853.31	1.02	17.02-19.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-18-20	11/1/2021	18 - 20 ft	852.29	853.31	1.02	19.02-21.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-20-22	11/1/2021	20 - 22 ft	852.29	853.31	1.02	21.02-23.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-22-24	11/1/2021	22 - 24 ft	852.29	853.31	1.02	23.02-25.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-24-26	11/1/2021	24 - 26 ft	852.29	853.31	1.02	25.02-27.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-26-28	11/1/2021	26 - 28 ft	852.29	853.31	1.02	27.02-29.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-4-6	11/1/2021	4 - 6 ft	852.29	853.31	1.02	5.02-7.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-6-8	11/1/2021	6 - 8 ft	852.29	853.31	1.02	7.02-9.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-8-10	11/1/2021	8 - 10 ft	852.29	853.31	1.02	9.02-11.02 ft	-	-	-	X	-
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	10 - 12 ft	856.18	856.99	0.81	10.81-12.81 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-12-14	6/4/2022	12 - 14 ft	856.18	856.99	0.81	12.81-14.81 ft	-	-	X	-	-
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	14 - 16 ft	856.18	856.99	0.81	14.81-16.81 ft	-	X	X	X	-
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	6 - 8 ft	856.18	856.99	0.81	6.81-8.81 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	8 - 10 ft	856.18	856.99	0.81	8.81-10.81 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	4 - 6 ft	856.18	-	-	-	-	-	X	X	-
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	10 - 12 ft	857.21	855.60	-1.61	8.39-10.39 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	12 - 14 ft	857.21	855.60	-1.61	10.39-12.39 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	14 - 16 ft	857.21	855.60	-1.61	12.39-14.39 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	6 - 8 ft	857.21	855.60	-1.61	4.39-6.39 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	8 - 10 ft	857.21	855.60	-1.61	6.39-8.39 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	4 - 6 ft	857.21	-	-	-	X	X	X	X	-
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	10 - 12 ft	856.60	856.86	0.26	10.26-12.26 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	12 - 14 ft	856.60	856.86	0.26	12.26-14.26 ft	-	-	X	-	-
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	14 - 16 ft	856.60	856.86	0.26	14.26-16.26 ft	-	X	X	X	-
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-4-6	6/4/2022	4 - 6 ft	856.60	856.86	0.26	4.26-6.26 ft	-	-	-	X	-
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	6 - 8 ft	856.60	856.86	0.26	6.26-8.26 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	8 - 10 ft	856.60	856.86	0.26	8.26-10.26 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	10 - 12 ft	856.27	856.38	0.11	10.11-12.11 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	12 - 14 ft	856.27	856.38	0.11	12.11-14.11 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	14 - 16 ft	856.27	856.38	0.11	14.11-16.11 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	4 - 6 ft	856.27	856.38	0.11	4.11-6.11 ft	X	-	X	X	-
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	6 - 8 ft	856.27	856.38	0.11	6.11-8.11 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	8 - 10 ft	856.27	856.38	0.11	8.11-10.11 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	10 - 12 ft	856.61	857.29	0.68	10.68-12.68 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	12 - 14 ft	856.61	857.29	0.68	12.68-14.68 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	14 - 16 ft	856.61	857.29	0.68	14.68-16.68 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	4 - 6 ft	856.61	857.29	0.68	4.68-6.68 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	6 - 8 ft	856.61	857.29	0.68	6.68-8.68 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	8 - 10 ft	856.61	857.29	0.68	8.68-10.68 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	10 - 12 ft	856.38	856.44	0.06	10.06-12.06 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	12 - 14 ft	856.38	856.44	0.06	12.06-14.06 ft	-	-	X	-	-
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	14 - 16 ft	856.38	856.44	0.06	14.06-16.06 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	4 - 6 ft	856.38	856.44	0.06	4.06-6.06 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	6 - 8 ft	856.38	856.44	0.06	6.06-8.06 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	8 - 10 ft	856.38	856.44	0.06	8.06-10.06 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	10 - 12 ft	856.66	856.67	0.01	10.01-12.01 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	12 - 14 ft	856.66	856.67	0.01	12.01-14.01 ft	-	-	X	-	-
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	14 - 16 ft	856.66	856.67	0.01	14.01-16.01 ft	X	X	X	X	-
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	4 - 6 ft	856.66	856.67	0.01	4.01-6.01 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	6 - 8 ft	856.66	856.67	0.01	6.01-8.01 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	8 - 10 ft	856.66	856.67	0.01	8.01-10.01 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	10 - 12 ft	856.60	856.56	-0.04	9.96-11.96 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	12 - 14 ft	856.60	856.56	-0.04	11.96-13.96 ft	-	-	X	-	-
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	14 - 16 ft	856.60	856.56	-0.04	13.96-15.96 ft	X	X	X	X	-

DRAFT

Table 2-3
Soil Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Site Location	Location	Sample Name	Sample Date	Sample depth at time of sampling[5] (bgs)	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Sample depth from final grade[6] (bfg)	PCBs	Metals	SVOCs	VOCs	PFAS
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	4 - 6 ft	856.60	856.56	-0.04	3.96-5.96 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	6 - 8 ft	856.60	856.56	-0.04	5.96-7.96 ft	-	-	X	X	-
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	8 - 10 ft	856.60	856.56	-0.04	7.96-9.96 ft	-	-	X	X	-
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	10 - 12 ft	851.23	851.23	0.00	10 - 12 ft	X	X	X	X	X
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	12 - 14 ft	851.23	851.23	0.00	12 - 14 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	16 - 18 ft	853.38	855.00	1.62	17.62-19.62 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	18 - 20 ft	853.38	855.00	1.62	19.62-21.62 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	20 - 22 ft	853.38	855.00	1.62	21.62-23.62 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	22 - 24 ft	853.38	855.00	1.62	23.62-25.62 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	24 - 26 ft	853.38	855.00	1.62	25.62-27.62 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	26 - 28 ft	853.38	855.00	1.62	27.62-29.62 ft	X	X	X	X	X
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	16 - 18 ft	853.43	854.71	1.28	17.28-19.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	18 - 20 ft	853.43	854.71	1.28	19.28-21.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	20 - 22 ft	853.43	854.71	1.28	21.28-23.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	22 - 24 ft	853.43	854.71	1.28	23.28-25.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	22 - 24 ft	853.43	854.71	1.28	23.28-25.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	24 - 26 ft	853.43	854.71	1.28	25.28-27.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	26 - 28 ft	853.43	854.71	1.28	27.28-29.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	28 - 30 ft	853.43	854.71	1.28	29.28-31.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	30 - 32 ft	853.43	854.71	1.28	31.28-33.28 ft	X	X	X	X	-
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	30 - 32 ft	853.43	854.71	1.28	31.28-33.28 ft	X	X	X	X	-
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10	1/30/2023	8 - 10 ft	848.46	848.46	0.00	8-10 ft	-	X	-	-	-
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12	1/30/2023	10 - 12 ft	848.46	848.46	0.00	10-12 ft	-	X	-	-	-
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14	1/30/2023	12 - 14 ft	848.46	848.46	0.00	12-14 ft	-	X	-	-	-
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16	1/30/2023	14 - 16 ft	848.46	848.46	0.00	14-16 ft	-	X	-	-	-
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	0.17 - 2 ft	852.78	852.78	0.00	0.17 - 2 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	2 - 4 ft	852.78	852.78	0.00	2 - 4 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	4 - 6 ft	852.78	852.78	0.00	4 - 6 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	6 - 8 ft	852.78	852.78	0.00	6 - 8 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	8 - 10 ft	852.78	852.78	0.00	8 - 10 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	10 - 12 ft	852.78	852.78	0.00	10 - 12 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	12 - 14 ft	852.78	852.78	0.00	12 - 14 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	14 - 16 ft	852.78	852.78	0.00	14 - 16 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	16 - 18 ft	852.78	852.78	0.00	16 - 18 ft	X	X	X	X	-
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	14 - 16 ft	851.23	851.23	0.00	14 - 16 ft	X	X	X	X	X
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	16 - 18 ft	851.23	851.23	0.00	16 - 18 ft	X	X	X	X	X
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01	8/12/2024	4.65 - 6.65 ft	850.65	850.65	0.00	4.65 - 6.65 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	2.65-4.65 ft	850.65	850.65	0.00	2.65-4.65 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	4.65 - 6.65 ft	850.65	850.65	0.00	4.65 - 6.65 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	6.65-8.65 ft	850.65	850.65	0.00	6.65-8.65 ft	-	X	X	X	-
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	10.65-12.65 ft	850.65	850.65	0.00	10.65-12.65 ft	-	X	X	X	-
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	12.65-14.65 ft	850.65	850.65	0.00	12.65-14.65 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	13.63-15.63 ft	851.63	851.63	0.00	13.63-15.63 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	14.03-16.03 ft	852.03	852.03	0.00	14.03-16.03 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-836-834	8/12/2024	16.03-18.03 ft	852.03	852.03	0.00	16.03-18.03 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	15.89-17.89 ft	849.89	849.89	0.00	15.89-17.89 ft	X	-	-	-	-
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	6.76-8.76 ft	852.76	852.76	0.00	6.76-8.76 ft	-	X	X	X	-
Rear Parking Lot	SPA4-B5507	SSHS-SPA4-B5507-ELEV-834-832	8/13/2024	16.07-18.07 ft	850.07	850.07	0.00	16.07-18.07 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	4.76-6.76 ft	852.76	852.76	0.00	4.76-6.76 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	6.76-8.76 ft	852.76	852.76	0.00	6.76-8.76 ft	-	X	X	X	-
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	8.76-10.76 ft	852.76	852.76	0.00	8.76-10.76 ft	-	X	-	-	-
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	7.21-9.21 ft	851.21	851.21	0.00	7.21-9.21 ft	-	X	-	-	-
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	14.26-16.26 ft	850.26	850.26	0.00	14.26-16.26 ft	-	X	-	-	-
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	12.12-14.12 ft	850.12	850.12	0.00	12.12-14.12 ft	-	X	-	-	-
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	14.12-16.12 ft	850.12	850.12	0.00	14.12-16.12 ft	-	X	-	-	-

Notes

- - Excavated samples do not have "Final Grade", "Sample depth from Final Grade" or "Change in Surface Elevation Data"

ft bfg - Feet Below Final Grade

ft bgs - Feet Below Ground Surface

Samples collected by NYSDEC in "May-October 2000 NYSDEC Sampling Report" included sample depths as "surface". These samples are assumed to have been collected from 0-0.5 ft bgs.

[1] - Ground surface elevation at the time of sampling is only provided for soil boring locations

[2] - Final grade elevation provided for samples remaining in place. Final grade elevations were not collected for samples outside of the BCP Boundary and are denoted as "--"

[3] - Change in surface elevation calculates for soil boring locations that have not been excavated. Positive values indicate net increase in ground surface elevation, negative values indicate net decrease in ground surface elevation.

[5] - Sample depth at time of sampling provided for grab samples and soil boring. For IRM/ISMP samples, sample depth at time of sampling represents the depth interval in which the associated grad sample was collected within. For soil borings, sample depth at time of sampling represents the depth interval from which a composite sample was collected.

[6] - Sample depth from final grade calculated for both IRM/ISMP and soil boring sample locations left in place (not excavated). Sample depth from final grade calculated for IRM/ISMP sample locations by comparing sample elevation to final grade elevation (i.e., final grade elevation of 857.18 ft amsl minus sample elevation of 847.44 ft amsl equals sample depth below final grade of 9.74 ft below final grade). Sample depth from final grade calculated for boring locations by comparing surface elevation at the time of sampling to the final grade elevation and correcting sample depths based on alterations to ground surface elevation (i.e., Surface elevation at time of sampling of 853.54 ft amsl and final grade elevation of 855.13 ft amsl indicates surface elevation increased 1.59 ft after sample collection. A sample previously collected at this location from 12-14 ft below ground surface [at the time of sampling] is now located 13.59-15.59 ft below final grade.)

Lab method used: 8082A/ SW8082A - PCBs

Lab method used: 6010C/SW6010C/SW6010D - Metals, SW6020B - Manganese, SW7470A/SW7471B - Mercury

Lab method used: 8270D/SW8270D/8270D_LL/SW8270E/8270E-LL - SVOCs

Lab method used: 8260C/SW8260C/8260C_LL/SW8260D - VOCs

Lab method used: E537(M)/PFC_IDA - PFAS

DRAFT

TABLE 2-4
Monitoring Well Construction Details

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well Information					Survey Data					Well construction							
Well ID	Type	Location	Status	Installation Date	Easting	Northing	Ground Elevation (ft amsl)	TOC Elevation (ft amsl)	Survey Date (month-year)	Known Well Construction Details	Screen length (ft)	Top of Screen (ft bgs)	Bottom of Screen (ft bgs)	Top of Screen (ft bTOC)	Bottom of Screen (ft bTOC)	Top of Screen (ft amsl)	Bottom of Screen (ft amsl)
MW-1	Flush Mount	Offsite - Millers Pond	Active	12/19/1996	763258.00	754238.62	853.46	853.34	April-2023	Yes	9.50	12.00	21.50	11.88	21.38	841.46	831.96
MW-2	Flush Mount	Offsite - Millers Pond	Active	12/19/1996	763273.15	754294.35	853.40	852.86	April-2023	Yes	11.50	15.00	26.50	14.46	25.96	838.40	826.90
MW-3	Flush Mount	Offsite - Millers Pond	Active	12/20/1996	763293.64	754365.92	852.96	852.76	April-2023	Yes	9.50	12.00	21.50	11.80	21.30	840.96	831.46
MW-4	Flush Mount	Offsite - NYSEG	Decommissioned	4/10/1997	762961.44	753978.02	843.58	846.12	April-2023	Yes	9.50	3.65	13.15	6.19	15.69	839.93	830.43
MW-5I	Stick-up	Offsite - Decker	Active	4/10/2023	762866.32	754263.54	840.26	839.96	April-2023	Yes	10.00	7.00	17.00	6.70	16.70	833.26	823.26
MW-5S	Flush Mount	Offsite - Decker	Active	4/9/1997	762852.09	754257.33	839.91	842.49	April-2023	Yes	9.50	2.90	12.40	5.49	14.99	837.01	827.51
MW-6	Flush Mount	South Parking Lot	Inactive	11/9/1997	762776.07	753773.75	-	-	Unknown	Yes	10.00	7.30	16.80	-	-	-	-
MW-7	Flush Mount	South Parking Lot	Inactive	12/9/1997	762705.49	753928.02	-	852.47	September-2014	Yes	10.00	9.00	18.50	-	-	-	-
MW-8I	Flush Mount	East of Gym	Active	6/16/2021	762648.06	754025.69	854.40	853.88	September-2021	Yes	10.00	35.00	45.00	34.48	44.48	819.40	809.40
MW-8S	Flush Mount	East of Gym	Active	12/8/1997	762649.46	754022.15	854.39	853.93	August-2023	Yes	9.50	7.30	16.80	6.83	16.33	847.09	837.59
MW-9I	Flush Mount	East of Gym	Active	6/29/2021	762564.61	754180.01	854.20	853.65	September-2021	Yes	10.00	33.00	43.00	32.45	42.45	821.20	811.20
MW-9S	Flush Mount	East of Gym	Active	12/9/1997	762572.38	754165.45	854.25	854.03	August-2023	Yes	9.50	9.00	18.50	8.78	18.28	845.25	835.75
MW-10	Stick-up - No Casing	East of Gym	Active	12/9/1997	762481.22	754302.75	853.13	854.07	April-2023	Yes	9.50	9.00	18.50	9.94	19.44	844.13	834.63
MW-11D	Flush Mount	FFC	Active	5/2/2003	762292.80	754704.56	855.42	854.80	March-2023	Yes	5.00	73.50	78.50	72.88	77.88	781.92	776.92
MW-11I	Stick-Up	Offsite - Norfolk Southern	Active	7/10/2025	762315.79	754713.83	853.15	856.57	August-2025	Yes	10.00	16.00	26.00	19.42	29.42	837.15	827.15
MW-11S	Flush Mount	FFC	Active	12/10/1997	762293.54	754699.34	855.43	855.14	April-2023	Yes	10.00	10.00	20.00	9.71	19.71	845.43	835.43
MW-12	Flush Mount	East of Gym	Active	12/10/1997	762485.41	754099.18	856.55	855.13	March-2021	Yes	9.35	9.50	18.85	8.08	17.43	847.05	837.70
MW-13	Flush Mount	East of Gym	Active	12/10/1997	762357.54	754233.58	855.33	854.94	March-2021	Yes	11.00	9.50	20.50	9.11	20.11	845.83	834.83
MW-14	Flush Mount	Teachers Parking Lot	Inactive	12/11/1997	762507.92	753875.25	-	-	Unknown	Yes	11.00	9.50	20.50	-	-	-	-
MW-15D	Flush Mount	Teachers Parking Lot	Decommissioned	4/29/2003	762119.48	754148.18	-	855.75	September-2014	Yes	10.00	66.50	76.50	-	-	-	-
MW-15S	Flush Mount	Teachers Parking Lot	Decommissioned	12/11/1997	762124.56	754149.24	-	855.72	September-2014	Yes	10.00	10.00	20.00	-	-	-	-
MW-16	Flush Mount	Student Parking Lot	Inactive	12/11/1997	761973.75	754439.27	-	854.89	September-2014	Yes	10.50	9.50	20.00	-	-	-	-
MW-17	Flush Mount	Offsite - NYSEG	Decommissioned	12/12/1997	762823.52	754703.40	849.93	852.65	April-2023	Yes	9.50	12.80	22.30	15.52	25.02	837.13	827.63
MW-18	Flush Mount	Offsite - Millers Pond	Inactive	7/7/1998	763366.96	755209.99	-	851.37	September-2014	Yes	4.80	9.50	14.30	-	-	-	-
MW-19D	Flush Mount	Offsite - Millers Pond	Inactive	No Record	762825.34	755039.82	-	-	Unknown	**No**	10.00	9.50	19.50	-	-	-	-
MW-19S	Flush Mount	Offsite - Millers Pond	Inactive	7/7/1998	762826.27	755040.28	-	-	Unknown	Yes	10.00	10.65	20.65	-	-	-	-
MW-20	Flush Mount	Offsite - NYSEG	Active	7/8/1998	762599.18	754708.01	852.85	852.29	April-2023	Yes	10.70	8.50	19.20	7.94	18.64	844.35	833.65
MW-21	Flush Mount	Offsite - FFC	Inactive	7/16/1998	762393.62	755134.64	-	-	Unknown	Yes	8.50	12.35	20.85	-	-	-	-
MW-22	Flush Mount	Offsite - NYSEG	Active	7/16/1998	762994.04	754489.22	843.23	846.18	April-2023	Yes	9.50	11.60	21.10	14.55	24.05	831.63	822.13
MW-23	Flush Mount	Offsite - Millers Pond	Inactive	7/16/1998	763439.38	754906.24	-	-	Unknown	Yes	9.50	9.20	18.20	-	-	-	-
MW-24	Flush Mount	Offsite - Millers Pond	Inactive	7/16/1998	763372.66	754627.03	-	-	Unknown	Yes	9.50	9.75	18.75	-	-	-	-
MW-25	Flush Mount	Offsite - Millers Pond	Inactive	7/17/1998	763499.81	754324.46	-	-	Unknown	Yes	10.00	8.75	18.75	-	-	-	-
MW-26	Flush Mount	Offsite - Millers Pond	Active	7/17/1998	763297.58	754017.56	844.12	843.69	April-2023	Yes	9.50	7.05	16.55	6.62	16.12	837.07	827.57
MW-27	Flush Mount	Offsite - Millers Pond	Inactive	7/17/1998	763275.36	753747.94	-	-	Unknown	Yes	9.50	2.90	12.40	-	-	-	-
MW-28	Flush Mount	Offsite - FFC	Inactive	7/17/1998	762167.23	755066.03	-	-	Unknown	Yes	9.50	12.50	21.50	-	-	-	-
MW-29	Flush Mount	Offsite - FFC	Inactive	7/17/1998	762098.83	755271.60	-	-	Unknown	Yes	9.50	12.40	21.40	-	-	-	-
MW-30	Flush Mount	East of Gym	Active	No Record	762563.07	754097.22	854.13	853.53	August-2023	**No**	10.00	8.00	18.00	7.40	17.40	846.13	836.13
MW-31	Flush Mount	East of Gym	Inactive	No Record	762536.15	754158.88	-	853.75	September-2014	**No**	10.00	8.00	18.00	-	-	-	-
MW-32	Flush Mount	East of Gym	Active	No Record	762492.62	754283.79	853.42	852.89	August-2023	**No**	10.00	8.00	18.00	7.47	17.47	845.42	835.42
MW-33	Flush Mount	East of Gym	Active	No Record	762456.41	754293.67	-	853.89	September-2014	**No**	10.00	10.00	20.00	-	-	-	-
MW-34	Flush Mount	East of Gym	Active	No Record	762470.80	754327.40	-	853.69	September-2014	**No**	10.00	10.00	20.00	-	-	-	-
MW-36	Flush Mount	FFC	Decommissioned	No Record	762280.79	754326.33	-	855.66	September-2014	**No**	10.00	9.00	19.00	-	-	-	-
MW-37	Flush Mount	FFC	Inactive	No Record	762371.17	754294.11	-	854.55	September-2014	**No**	10.00	-	-	-	-	-	-
MW-38	Flush Mount	FFC	Decommissioned	No Record	762398.26	754419.60	-	854.86	September-2014	**No**	10.00	9.90	19.90	-	-	-	-

DRAFT

TABLE 2-4
Monitoring Well Construction Details

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well Information					Survey Data					Well construction							
Well ID	Type	Location	Status	Installation Date	Easting	Northing	Ground Elevation (ft amsl)	TOC Elevation (ft amsl)	Survey Date (month-year)	Known Well Construction Details	Screen length (ft)	Top of Screen (ft bgs)	Bottom of Screen (ft bgs)	Top of Screen (ft bTOC)	Bottom of Screen (ft bTOC)	Top of Screen (ft amsl)	Bottom of Screen (ft amsl)
MW-39	Flush Mount	FFC	**Decommissioned**	No Record	762202.45	754295.28	-	854.87	September-2014	**No**	10.00	15.00	25.00	-	-	-	-
MW-40	Flush Mount	FFC	**Decommissioned**	No Record	762363.35	754360.95	-	854.90	September-2014	**No**	10.00	14.40	24.40	-	-	-	-
MW-41	Flush Mount	East of Gym	**Active**	12/9/2005	762551.07	754348.38	856.58	859.28	August-2023	Yes	20.00	5.00	25.00	7.70	27.70	851.58	831.58
MW-42	Flush Mount	South Parking Lot	**Decommissioned**	3/1/2016	762766.95	753757.35	-	-	Unknown	Yes	10.00	12.00	22.00	-	-	-	-
MW-43	Flush Mount	South Parking Lot	**Active**	3/1/2016	762714.91	753874.68	852.22	851.81	August-2023	Yes	10.00	10.00	20.00	9.59	19.59	842.22	832.22
MW-44	Flush Mount	FFC	**Decommissioned**	2/29/2016	762381.45	754476.78	-	-	Unknown	Yes	10.00	20.00	30.00	-	-	-	-
MW-46	Flush Mount	South Parking Lot	**Decommissioned**	8/20/2016	762679.20	753716.60	-	-	Unknown	Yes	10.00	15.00	25.00	-	-	-	-
MW-47	Flush Mount	Teachers Parking Lot	**Active**	8/29/2016	762102.73	753783.32	855.39	855.13	August-2023	Yes	10.00	17.75	27.75	17.50	27.50	837.64	827.64
MW-47I	Flush Mount	Teachers Parking Lot	**Active**	8/24/2021	762104.49	753784.86	855.41	855.03	September-2021	Yes	10.00	28.00	38.00	27.62	37.62	827.41	817.41
MW-48	Flush Mount	NAF	**Decommissioned**	1/22/2021	761871.18	755742.71	853.29	853.00	March-2023	Yes	15.00	20.00	35.00	19.71	34.71	833.29	818.29
MW-48R	Flush Mount	NAF	**Active**	7/25/2023	761913.95	755653.34	853.30	852.68	April-2024	Yes	15.00	11.00	26.00	11.12	26.12	842.30	827.30
MW-49	Flush Mount	NAF	**Decommissioned**	2/5/2021	761804.16	755552.68	855.52	855.05	March-2023	Yes	15.00	20.00	35.00	19.53	34.53	835.52	820.52
MW-50I	Flush Mount	NAF	**Decommissioned**	1/21/2021	761893.62	755428.13	853.96	853.61	March-2023	Yes	10.00	25.00	35.00	24.65	34.65	828.96	818.96
MW-50R	Flush Mount	NAF	**Active**	7/26/2023	761916.22	755504.30	856.42	856.20	April-2024	Yes	15.00	11.00	26.00	12.25	27.25	845.42	830.42
MW-50S	Flush Mount	NAF	**Decommissioned**	1/21/2021	761889.23	755429.18	854.12	853.83	March-2023	Yes	5.00	15.50	20.50	15.21	20.21	838.62	833.62
MW-51	Flush Mount	NAF	**Active**	1/20/2021	762007.09	755417.02	852.38	852.67	April-2024	Yes	10.00	14.00	24.00	15.34	25.34	838.38	828.38
MW-52	Flush Mount	NAF	**Decommissioned**	1/20/2021	761901.41	755353.29	854.10	853.73	March-2023	Yes	10.00	17.00	27.00	16.63	26.63	837.10	827.10
MW-53	Flush Mount	NAF	**Decommissioned**	2/5/2021	761750.10	755686.18	854.59	854.14	March-2023	Yes	15.00	15.00	30.00	14.55	29.55	839.59	824.59
MW-54	Flush Mount	NAF	**Decommissioned**	2/4/2021	761696.70	755411.28	856.39	856.11	March-2023	Yes	15.00	15.00	30.00	14.72	29.72	841.39	826.39
MW-54R	Flush Mount	NAF	**Active**	7/25/2023	761710.78	755429.86	857.37	856.83	April-2024	Yes	15.00	11.00	26.00	12.00	27.00	846.37	831.37
MW-55	Flush Mount	NAF	**Active**	2/3/2021	761737.32	755286.31	856.80	856.33	April-2024	Yes	15.00	14.00	29.00	14.92	29.92	842.80	827.80
MW-56	Flush Mount	NAF	**Active**	2/8/2021	761929.90	755187.87	855.89	854.16	April-2024	Yes	15.00	13.00	28.00	13.12	28.12	842.89	827.89
MW-57	Flush Mount	NAF	**Decommissioned**	2/8/2021	761983.67	755078.64	855.79	855.36	March-2023	Yes	15.00	9.50	20.15	9.07	19.72	850.64	835.64
MW-57R	Flush Mount	NAF	**Active**	4/4/2023	762080.28	755241.02	851.87	852.41	April-2024	Yes	10.00	11.00	21.00	12.77	22.77	840.87	830.87
MW-58	Flush Mount	NAF	**Active**	1/25/2021	762212.78	754905.64	852.15	853.27	April-2024	Yes	15.00	7.00	22.00	10.61	25.61	845.15	830.15
MW-59I	Flush Mount	NAF	**Decommissioned**	2/9/2021	762007.16	754919.02	856.43	856.14	March-2023	Yes	5.00	28.00	33.00	27.71	32.71	828.43	823.43
MW-59IR	Flush Mount	NAF	**Active**	7/27/2023	762027.47	754832.63	856.00	856.05	April-2024	Yes	5.00	26.00	31.00	27.50	32.50	830.00	825.00
MW-59S	Flush Mount	NAF	**Decommissioned**	2/9/2021	762003.30	754917.57	856.64	856.34	March-2023	Yes	10.00	15.00	25.00	14.70	24.70	841.64	831.64
MW-59SR	Flush Mount	NAF	**Active**	7/28/2023	762021.62	754829.93	856.31	856.09	April-2024	Yes	10.00	14.50	24.50	15.50	25.50	841.81	831.81
MW-60	Flush Mount	NAF	**Decommissioned**	1/28/2021	761839.97	754944.16	856.45	856.12	March-2023	Yes	15.00	20.00	35.00	19.67	34.67	836.45	821.45
MW-60IR	Flush Mount	NAF	**Active**	7/27/2023	761819.23	754955.83	855.99	855.90	April-2024	Yes	5.00	29.00	34.00	29.70	34.70	826.99	821.99
MW-60SR	Flush Mount	NAF	**Active**	7/27/2023	761813.23	754955.48	856.07	856.08	April-2024	Yes	10.00	12.50	22.50	13.10	23.10	843.57	833.57
MW-61	Flush Mount	NAF	**Decommissioned**	1/25/2021	761528.06	755525.65	857.65	857.39	March-2023	Yes	10.00	25.00	35.00	24.74	34.74	832.65	822.65
MW-62	Flush Mount	NAF	**Decommissioned**	2/4/2021	761583.20	755348.98	857.70	857.33	March-2023	Yes	10.00	25.00	35.00	24.63	34.63	832.70	822.70
MW-62R	Flush Mount	NAF	**Active**	7/25/2023	761538.88	755272.10	857.56	857.94	April-2024	Yes	15.00	14.00	29.00	15.90	30.90	843.56	828.56
MW-63I	Flush Mount	NAF	**Active**	1/29/2021	761758.08	755093.75	857.28	856.54	April-2024	Yes	10.00	19.00	29.00	19.69	29.69	838.28	828.28
MW-63S	Flush Mount	NAF	**Active**	1/29/2021	761762.58	755092.18	857.28	856.35	April-2024	Yes	10.00	10.00	20.00	10.57	20.57	847.28	837.28
MW-64I	Flush Mount	NAF	**Active**	1/27/2021	761659.87	754882.80	857.01	856.81	May-2023	Yes	10.00	26.00	36.00	25.80	35.80	831.01	821.01
MW-64S	Flush Mount	NAF	**Active**	1/27/2021	761655.32	754881.15	856.98	856.80	May-2023	Yes	10.00	12.00	22.00	11.82	21.82	844.98	834.98
MW-65	Flush Mount	NAF	**Decommissioned**	1/26/2021	761819.58	754785.10	856.63	856.28	March-2021	Yes	15.00	16.00	31.00	15.65	30.65	840.63	825.63
MW-65R	Flush Mount	NAF	**Active**	7/27/2023	761847.10	754796.80	856.04	856.47	April-2024	Yes	15.00	14.50	29.50	16.10	31.10	841.54	826.54
MW-66I	Flush Mount	NAF	**Active**	1/28/2021	761583.56	754786.04	857.08	856.74	May-2023	Yes	10.00	31.00	41.00	30.66	40.66	826.08	816.08
MW-66S	Flush Mount	NAF	**Active**	1/28/2021	761581.76	754781.28	857.16	856.76	May-2023	Yes	10.00	18.00	28.00	17.60	27.60	839.16	829.16
MW-67I	Stick-up	Offsite - Norfolk Southern	**Active**	6/24/2021	762668.34	754068.85	852.53	855.46	September-2021	Yes	10.00	30.00	40.00	32.93	42.93	822.53	812.53
MW-67S	Stick-up	Offsite - Norfolk Southern	**Active**	6/25/2021	762665.34	754063.69	852.28	855.19	September-2021	Yes	10.00	12.50	22.50	15.41	25.41	839.78	829.78
MW-68S	Stick-up	Offsite - Norfolk Southern	**Active**	6/28/2021	762525.34	754319.88	851.57	854.59	September-2021	Yes	10.00	16.00	26.00	19.02	29.02	835.57	825.57
MW-69I	Stick-up	Offsite - Norfolk Southern	**Active**	6/23/2021	762610.23	754315.18	856.38	859.21	September-2021	Yes	10.00	53.00	63.00	55.83	65.83	803.38	793.38
MW-70I	Flush Mount	South Parking Lot	**Active**	8/3/2021	762686.79	753624.30	847.70	847.63	September-2021	Yes	10.00	31.00	41.00	30.93	40.93	816.70	806.70

DRAFT

TABLE 2-4
Monitoring Well Construction Details

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well Information					Survey Data					Well construction							
Well ID	Type	Location	Status	Installation Date	Easting	Northing	Ground Elevation (ft amsl)	TOC Elevation (ft amsl)	Survey Date (month-year)	Known Well Construction Details	Screen length (ft)	Top of Screen (ft bgs)	Bottom of Screen (ft bgs)	Top of Screen (ft bTOC)	Bottom of Screen (ft bTOC)	Top of Screen (ft amsl)	Bottom of Screen (ft amsl)
MW-70S	Flush Mount	South Parking Lot	Active	8/3/2021	762682.48	753626.15	848.20	848.08	September-2021	Yes	10.00	14.00	24.00	13.88	23.88	834.20	824.20
MW-71I	Flush Mount	South Parking Lot	Active	8/9/2021	762561.53	753855.90	854.75	854.42	September-2021	Yes	10.00	40.00	50.00	39.67	49.67	814.75	804.75
MW-71S	Flush Mount	South Parking Lot	Active	8/9/2021	762556.64	753854.16	854.90	854.57	September-2021	Yes	10.00	16.00	26.00	15.67	25.67	838.90	828.90
MW-72I	Flush Mount	South Parking Lot	Active	8/4/2021	762518.99	753493.14	849.30	849.01	September-2021	Yes	10.00	29.00	39.00	28.71	38.71	820.30	810.30
MW-72S	Flush Mount	South Parking Lot	Active	8/5/2021	762515.77	753496.29	849.50	849.19	September-2021	Yes	10.00	13.50	23.50	13.19	23.19	836.00	826.00
MW-73I	Flush Mount	South Parking Lot	Active	8/5/2021	762548.45	753672.53	852.30	852.04	September-2021	Yes	10.00	28.50	38.50	28.24	38.24	823.80	813.80
MW-73S	Flush Mount	South Parking Lot	Active	8/6/2021	762542.14	753670.84	852.40	852.12	September-2021	Yes	10.00	13.00	23.00	12.72	22.72	839.40	829.40
MW-74I	Flush Mount	Southern Entranceway	Active	8/11/2021	762260.67	753484.25	854.30	854.13	September-2021	Yes	10.00	38.00	48.00	37.83	47.83	816.30	806.30
MW-74S	Flush Mount	Southern Entranceway	Active	8/12/2021	762255.96	753482.96	854.40	854.15	September-2021	Yes	10.00	14.00	24.00	13.75	23.75	840.40	830.40
MW-75I	Flush Mount	Teachers Parking Lot	Active	8/25/2021	761977.31	754070.69	855.10	854.81	September-2021	Yes	10.00	25.00	35.00	24.71	34.71	830.10	820.10
MW-75S	Flush Mount	Teachers Parking Lot	Active	8/27/2021	761969.53	754064.44	855.10	854.30	September-2021	Yes	10.00	13.00	23.00	12.20	22.20	842.10	832.10
MW-76I	Flush Mount	Student Parking Lot	Active	8/31/2021	761934.52	754282.93	856.55	856.00	September-2021	Yes	10.00	21.00	31.00	20.45	30.45	835.55	825.55
MW-76S	Flush Mount	Student Parking Lot	Active	8/31/2021	761927.97	754279.50	856.45	856.05	September-2021	Yes	10.00	15.00	25.00	14.60	24.60	841.45	831.45
MW-77I	Flush Mount	Student Parking Lot	Active	8/30/2021	761802.58	754178.96	853.95	853.59	September-2021	Yes	10.00	20.00	30.00	19.64	29.64	833.95	823.95
MW-77S	Flush Mount	Student Parking Lot	Active	8/31/2021	761803.20	754176.60	854.05	853.45	September-2021	Yes	10.00	13.00	23.00	12.40	22.40	841.05	831.05
MW-78I	Flush Mount	Tennis Court Area	Active	9/2/2021	761666.47	754552.33	855.90	855.54	September-2021	Yes	10.00	36.00	46.00	35.64	45.64	819.90	809.90
MW-78S	Flush Mount	Tennis Court Area	Active	9/2/2021	761663.14	754551.45	855.90	855.44	September-2021	Yes	10.00	14.00	24.00	13.54	23.54	841.90	831.90
MW-79I	Flush Mount	Tennis Court Area	Active	9/2/2021	761929.24	754474.01	856.15	855.72	September-2021	Yes	10.00	23.00	33.00	22.57	32.57	833.15	823.15
MW-79S	Flush Mount	Tennis Court Area	Active	9/2/2021	761920.75	754472.13	856.40	856.01	September-2021	Yes	10.00	16.00	26.00	15.61	25.61	840.40	830.40
MW-81I	Flush Mount	East of Gym	Active	6/29/2021	762575.92	754082.32	854.08	853.60	September-2021	Yes	10.00	36.00	46.00	35.52	45.52	818.08	808.08
MW-82S	Stick-up	South Parking Lot	Active	8/2/2021	762855.24	753696.72	849.47	852.05	September-2021	Yes	10.00	15.00	25.00	17.58	27.58	834.47	824.47
MW-83I	Flush Mount	Southern Entranceway	Active	8/27/2021	762081.25	753533.93	855.35	854.77	September-2021	Yes	10.00	23.00	33.00	22.42	32.42	832.35	822.35
MW-83S	Flush Mount	Southern Entranceway	Active	8/26/2021	762086.76	753523.39	854.95	854.71	September-2021	Yes	10.00	14.00	24.00	13.76	23.76	840.95	830.95
MW-84S	Flush Mount	Teachers Parking Lot	Active	8/23/2021	762116.67	754151.94	855.80	855.54	September-2021	Yes	10.00	16.00	26.00	15.74	25.74	839.80	829.80
MW-85I	Flush Mount	East of Gym	Active	6/16/2021	762352.26	754242.32	855.96	855.12	April-2023	Yes	10.00	31.00	41.00	30.16	40.16	824.96	814.96
MW-86I	Flush Mount	East of Gym	Active	6/29/2021	762504.07	754270.50	853.95	853.56	September-2021	Yes	10.00	34.00	44.00	33.61	43.61	819.95	809.95
MW-87I	Flush Mount	East of Gym	Active	6/29/2021	762512.81	754106.26	856.30	855.02	September-2021	Yes	10.00	33.00	43.00	31.72	41.72	823.30	813.30
MW-88I	Flush Mount	East of Gym	Active	6/16/2021	762454.26	754171.96	856.12	855.33	September-2021	Yes	10.00	35.00	45.00	34.21	44.21	821.12	811.12
MW-88S	Flush Mount	East of Gym	Active	6/16/2021	762455.58	754176.03	856.12	855.15	September-2021	Yes	10.00	15.00	25.00	14.03	24.03	841.12	831.12
MW-89I	Flush Mount	East of Gym	Active	6/11/2021	762492.87	753972.01	855.38	854.77	September-2021	Yes	10.00	39.00	49.00	38.39	48.39	816.38	806.38
MW-89S	Flush Mount	East of Gym	Active	6/11/2021	762489.24	753970.98	855.30	855.00	September-2021	Yes	10.00	15.00	25.00	14.70	24.70	840.30	830.30
MW-90I	Flush Mount	Courtyard	Active	8/19/2021	762267.94	753627.76	855.52	855.39	September-2021	Yes	10.00	33.00	43.00	32.87	42.87	822.52	812.52
MW-90S	Flush Mount	Courtyard	Active	8/19/2021	762264.60	753626.48	855.55	855.38	September-2021	Yes	10.00	16.00	26.00	15.83	25.83	839.55	829.55
MW-91I	Flush Mount	South Parking Lot	Active	8/20/2021	762461.94	753668.33	853.72	853.53	September-2021	Yes	10.00	36.00	46.00	35.81	45.81	817.72	807.72
MW-91S	Flush Mount	South Parking Lot	Active	8/20/2021	762457.30	753666.69	853.72	853.56	September-2021	Yes	10.00	14.00	24.00	13.84	23.84	839.72	829.72
MW-92I	Flush Mount	Student Parking Lot	Active	9/1/2021	761989.52	754300.79	855.81	855.38	September-2021	Yes	10.00	25.00	35.00	24.57	34.57	830.81	820.81
MW-92S	Flush Mount	Student Parking Lot	Active	9/1/2021	761987.97	754304.87	855.77	855.34	September-2021	Yes	10.00	16.00	26.00	15.57	25.57	839.77	829.77
MW-93I	Flush Mount	Teachers Parking Lot	Active	8/30/2021	762056.92	754094.72	855.55	854.97	September-2021	Yes	10.00	28.00	38.00	27.42	37.42	827.55	817.55
MW-93S	Flush Mount	Teachers Parking Lot	Active	8/26/2021	762049.31	754090.53	855.62	855.28	September-2021	Yes	10.00	16.00	26.00	15.66	25.66	839.62	829.62
MW-94I	Flush Mount	Teachers Parking Lot	Active	8/24/2021	762035.11	753860.83	853.15	852.93	September-2021	Yes	10.00	26.00	36.00	25.78	35.78	827.15	817.15
MW-94S	Flush Mount	Teachers Parking Lot	Active	8/24/2021	762029.96	753855.20	853.00	852.74	September-2021	Yes	10.00	12.00	22.00	11.74	21.74	841.00	831.00
MW-95I	Flush Mount	Offsite - FM Howell	Active	4/6/2023	762175.11	755744.17	850.96	850.74	April-2023	Yes	10.00	19.00	29.00	18.78	28.78	831.96	821.96

DRAFT

TABLE 2-4
Monitoring Well Construction Details

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well Information					Survey Data					Well construction							
Well ID	Type	Location	Status	Installation Date	Easting	Northing	Ground Elevation (ft amsl)	TOC Elevation (ft amsl)	Survey Date (month-year)	Known Well Construction Details	Screen length (ft)	Top of Screen (ft bgs)	Bottom of Screen (ft bgs)	Top of Screen (ft bTOC)	Bottom of Screen (ft bTOC)	Top of Screen (ft amsl)	Bottom of Screen (ft amsl)
MW-95S	Flush Mount	Offsite - FM Howell	Active	4/6/2023	762171.29	755753.49	850.98	850.72	April-2023	Yes	10.00	14.00	24.00	13.74	23.74	836.98	826.98
MW-96	Stick-up	Offsite - Norfolk Southern	Active	4/5/2023	762144.24	755420.00	860.26	864.27	April-2023	Yes	15.00	16.00	31.00	20.01	35.01	844.26	829.26
MW-97	Stick-up	Offsite - Norfolk Southern	Active	4/5/2023	762222.30	755240.65	859.56	863.29	April-2023	Yes	15.00	17.00	32.00	20.73	35.73	842.56	827.56
MW-98I	Flush Mount	Offsite - Willys St	Active	7/21/2022	762452.90	755121.67	853.24	852.85	April-2023	Yes	10.00	30.00	35.00	29.61	34.61	828.24	818.24
MW-98S	Flush Mount	Offsite - Willys St	Active	7/20/2022	762441.35	755116.23	853.45	853.21	April-2023	Yes	5.00	17.00	27.00	16.76	26.76	831.45	826.45
MW-99I	Flush Mount	Offsite - Morrow St	Active	4/12/2023	762540.94	754901.05	853.78	853.48	April-2023	Yes	10.00	36.00	46.00	35.70	45.70	817.78	807.78
MW-99S	Flush Mount	Offsite - Morrow St	Active	4/12/2023	762549.58	754904.50	853.68	853.38	April-2023	Yes	10.00	14.00	24.00	13.70	23.70	839.68	829.68
MW-100I	Flush Mount	NAF	Active	7/28/2023	762151.59	755097.31	852.57	851.64	April-2024	Yes	5.00	25.00	30.00	27.00	32.00	827.57	822.57
MW-100S	Flush Mount	NAF	Active	7/31/2023	762148.51	755102.37	852.09	851.84	April-2024	Yes	10.00	12.00	22.00	14.20	24.20	840.09	830.09
MW-101I	Stick-up	Offsite - Decker	Active	4/11/2023	762813.76	754145.81	843.89	848.02	April-2023	Yes	10.00	14.50	24.50	18.63	28.63	829.39	819.39
MW-101S	Stick-up	Offsite - Decker	Active	4/11/2023	762809.99	754154.30	843.54	843.23	April-2023	Yes	10.00	4.50	14.50	4.19	14.19	839.04	829.04
MW-102I	Flush Mount	FFC	Active	4/4/2023	762432.08	754384.70	855.11	854.73	April-2023	Yes	10.00	37.00	47.00	36.62	46.62	818.11	808.11
MW-102S	Flush Mount	FFC	Active	4/4/2023	762436.41	754373.06	855.06	854.77	April-2023	Yes	10.00	15.00	25.00	14.71	24.71	840.06	830.06
MW-103I	Flush Mount	Former Slide Rail	Active	7/28/2022	762215.16	754229.62	855.56	855.27	April-2023	Yes	10.00	28.00	38.00	27.71	37.71	827.56	817.56
MW-103S	Flush Mount	Former Slide Rail	Active	7/28/2022	762211.18	754229.07	855.62	854.99	April-2023	Yes	10.00	15.00	25.00	14.37	24.37	840.62	830.62
MW-104I	Flush Mount	School Entrance	Active	4/5/2023	762227.13	754145.61	855.45	855.22	April-2023	Yes	10.00	30.00	40.00	29.77	39.77	825.45	815.45
MW-104S	Flush Mount	School Entrance	Active	4/5/2023	762226.98	754129.54	855.27	854.96	April-2023	Yes	10.00	13.50	23.50	13.19	23.19	841.77	831.77
MW-105I	Flush Mount	School Entrance	Active	7/27/2022	762253.01	753992.78	854.89	854.65	April-2023	Yes	10.00	27.00	37.00	26.76	36.76	827.89	817.89
MW-105S	Flush Mount	School Entrance	Active	4/4/2023	762245.22	753988.74	855.02	854.72	April-2023	Yes	10.00	13.00	23.00	12.70	22.70	842.02	832.02
MW-106	Flush Mount	NAF	Active	4/4/2023	762032.63	755340.61	852.46	852.54	April-2024	Yes	15.00	9.00	24.00	10.61	25.61	843.46	828.46
MW-107I	Flush Mount	Offsite - Morrow St	Active	7/8/2025	762854.69	755031.21	851.95	851.67	August-2025	Yes	10.00	28.00	38.00	27.71	37.71	823.95	813.95
MW-107S	Flush Mount	Offsite - Morrow St	Active	7/8/2025	762848.78	755028.77	852.12	851.88	August-2025	Yes	10.00	15.00	25.00	14.76	24.76	837.12	827.12
MW-108	Flush Mount	Offsite - Shepler St	Active	7/9/2025	762903.78	755521.68	847.81	847.56	August-2025	Yes	10.00	7.00	17.00	6.76	16.76	840.81	830.81
MW-D	Flush Mount	East of Gym	Inactive	5/6/2003	762572.98	754064.22	-	-	Unknown	Yes	10.00	34.00	44.00	-	-	-	-

Notes:
-ft amsl: feet above mean sea level
-ft bgs: feet below ground surface
-ft bTOC: feet below top of casing
"-": No existing data/proposed data collection
-X and Y coordinates in NY State Plane Central NAD 1983
-Vertical datum is North American Vertical Datum of 1988
-Surveys completed by New York State Licensed Surveyor
-Inactive refers to monitoring wells that are referenced in historical reports and documents, but which were unable to be located in the field and are presumed to have been removed or lost. No known decommissioning records exist for these wells.
-Monitoring wells without known construction details are assumed to have 10 ft screen. Top and bottom of well screen are estimated based on field depth to bottom measurements.
-Damaged monitoring wells have been made unusable
-Ground Elevation is surveyed ground surface elevation at time of well construction. Due to regrading activities at the Site, ground elevation has been modified at certain locations.

DRAFT

Table 2-5
Groundwater Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-1	MW-1	Permanent	9/26/1997	--	--	--	X	--
MW-1	MW1	Permanent	5/11/2000	--	X	X	--	--
MW-1	MW1	Permanent	7/27/2000	--	X	--	--	--
MW-1	MW-1	Permanent	4/2/2002	--	--	--	X	--
MW-1	MW-1	Permanent	2/17/2021	X	X	X	X	--
MW-1	MW-1	Permanent	7/14/2021	X	X	X	X	--
MW-1	SSHS-MW-1-04112024	Permanent	4/11/2024	--	X	--	X	--
MW-2	MW-2	Permanent	9/26/1997	--	--	--	X	--
MW-2	MW-2	Permanent	4/2/2002	--	--	--	X	--
MW-2	MW-2	Permanent	2/17/2021	X	X	X	X	--
MW-2	MW-2	Permanent	7/14/2021	X	X	X	X	--
MW-3	MW-3	Permanent	9/26/1997	--	--	--	X	--
MW-3	MW-3	Permanent	4/2/2002	--	--	--	X	--
MW-3	MW-3	Permanent	2/17/2021	X	X	X	X	--
MW-3	MW-3	Permanent	7/14/2021	X	X	X	X	--
MW-4	MW-4	Permanent	9/26/1997	--	--	--	X	--
MW-4	MW4	Permanent	5/17/2000	--	--	X	X	--
MW-4	MW-4	Permanent	5/17/2000	--	--	--	X	--
MW-4	MW4	Permanent	9/20/2000	--	X	X	--	--
MW-4	MW-4	Permanent	9/20/2000	--	--	--	X	--
MW-4	MW-4	Permanent	7/23/2002	--	--	--	X	--
MW-4	MW-4	Permanent	6/28/2005	--	--	--	X	--
MW-4	MW-4	Permanent	5/20/2006	--	--	--	X	--
MW-4	MW-4	Permanent	3/26/2008	--	--	--	--	--
MW-5I	SSHS-MW-5I-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-5I	SSHS-MW-5I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-5S	MW-5	Permanent	9/26/1997	--	--	--	X	--
MW-5S	MW-5	Permanent	12/19/1997	--	--	--	X	--
MW-5S	MW5	Permanent	5/16/2000	--	X	X	X	--
MW-5S	MW-5	Permanent	5/16/2000	--	--	--	X	--
MW-5S	MW5	Permanent	9/20/2000	--	X	X	X	--
MW-5S	MW-5	Permanent	9/20/2000	--	--	--	X	--
MW-5S	MW-5	Permanent	4/2/2002	--	--	--	X	--
MW-5S	MW-5	Permanent	7/23/2002	--	--	--	X	--
MW-5S	MW-5	Permanent	5/20/2003	--	--	--	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-5S	MW-5	Permanent	5/20/2003	--	--	--	X	--
MW-5S	MW-5	Permanent	9/24/2003	--	--	--	X	--
MW-5S	MW-5	Permanent	9/24/2003	--	--	--	X	--
MW-5S	MW-5	Permanent	6/1/2004	--	--	--	X	--
MW-5S	MW-5	Permanent	12/30/2004	--	--	--	X	--
MW-5S	MW-5	Permanent	6/28/2005	--	--	--	X	--
MW-5S	MW-5	Permanent	12/28/2005	--	--	--	X	--
MW-5S	MW-5	Permanent	5/25/2006	--	--	--	X	--
MW-5S	MW-5	Permanent	7/12/2007	--	--	--	X	--
MW-5S	MW-5	Permanent	2/23/2021	X	X	X	X	--
MW-5S	MW-5	Permanent	7/15/2021	X	X	X	--	--
MW-5S	MW-5	Permanent	7/15/2021	--	--	--	X	--
MW-7	MW-7	Permanent	5/20/2003	--	--	--	X	--
MW-7	MW-7	Permanent	6/28/2005	--	--	--	X	--
MW-8I	MW-8I	Permanent	7/1/2021	X	X	X	X	X
MW-8I	DUP-1	Permanent	8/30/2021	X	X	X	X	X
MW-8I	MW-8I	Permanent	8/30/2021	X	X	X	X	X
MW-8I	SSHS-MW-8I-04302024	Permanent	4/30/2024	X	X	X	X	--
MW-8S	MW-8	Permanent	4/2/2002	--	--	--	X	--
MW-8S	MW-8	Permanent	6/19/2002	--	--	--	X	--
MW-8S	MW-8	Permanent	7/23/2002	--	--	--	X	--
MW-8S	MW-8	Permanent	5/20/2003	--	--	--	X	--
MW-8S	MW-8	Permanent	5/20/2003	--	--	--	X	--
MW-8S	MW-8	Permanent	9/24/2003	--	--	--	X	--
MW-8S	MW-8	Permanent	9/24/2003	--	--	--	X	--
MW-8S	MW-8-D20	Permanent	9/24/2003	--	--	--	X	--
MW-8S	MW-8	Permanent	6/1/2004	--	--	--	X	--
MW-8S	MW-8	Permanent	12/30/2004	--	--	--	X	--
MW-8S	MW-8	Permanent	6/28/2005	--	--	--	X	--
MW-8S	MW-8	Permanent	12/28/2005	--	--	--	X	--
MW-8S	MW-8	Permanent	5/25/2006	--	--	--	X	--
MW-8S	MW-8	Permanent	7/12/2007	--	--	--	X	--
MW-8S	MW-8	Permanent	8/20/2014	--	--	--	X	--
MW-8S	MW-8	Permanent	8/20/2014	--	--	--	X	--
MW-8S	GW-FD-3_F	Permanent	3/22/2016	X	--	--	--	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-8S	SSHS-MW-8S	Permanent	3/22/2016	X	--	--	--	--
MW-8S	SSHS-MW-8S_F	Permanent	3/22/2016	X	--	--	--	--
MW-8S	MW-8S	Permanent	2/18/2021	X	X	X	X	X
MW-8S	MW-8S	Permanent	7/12/2021	X	X	X	X	X
MW-8S	SSHS-MW-8S-04052024	Permanent	4/5/2024	--	--	--	X	--
MW-9I	MW-9I	Permanent	7/14/2021	X	X	X	X	--
MW-9I	MW-9I	Permanent	8/31/2021	X	X	X	X	--
MW-9I	SSHS-MW-9I-04292024	Permanent	4/29/2024	X	X	X	X	--
MW-9S	MW-9	Permanent	5/20/2003	--	--	--	X	--
MW-9S	SSHS-MW-9	Permanent	3/21/2016	X	--	--	--	--
MW-9S	SSHS-MW-9_F	Permanent	3/21/2016	X	--	--	--	--
MW-9S	MW-9	Permanent	2/20/2021	X	X	X	X	--
MW-9S	MW-9	Permanent	7/14/2021	X	X	X	X	--
MW-9S	SSHS-MW-9S-04052024	Permanent	4/5/2024	X	--	--	X	--
MW-10	MW-10	Permanent	8/21/2014	X	--	--	--	--
MW-10	MW-10	Permanent	2/24/2021	X	X	--	X	--
MW-10	MW-10	Permanent	3/24/2021	--	--	X	--	--
MW-10	MW-10	Permanent	7/13/2021	X	X	--	X	--
MW-10	MW-10	Permanent	7/13/2021	--	--	X	--	--
MW-11D	MW-11D	Permanent	5/20/2003	--	--	--	X	--
MW-11D	MW-11D	Permanent	9/24/2006	--	--	--	X	--
MW-11D	MW-11D-GW	Permanent	11/1/2018	X	X	X	X	--
MW-11D	MW-11D	Permanent	2/23/2021	X	X	X	X	--
MW-11D	MW-11D	Permanent	4/30/2021	X	X	X	X	--
MW-11D	MW-11D	Permanent	7/15/2021	--	--	X	--	--
MW-11I	SSHS-MW-11I-07142025	Permanent	7/14/2025	--	--	--	X	--
MW-11I	SSHS-MW-11I-11132025	Permanent	11/13/2025	--	--	--	X	--
MW-11S	MW-11S	Permanent	5/20/2003	--	--	--	X	--
MW-11S	SSHS-MW-11S	Permanent	3/23/2016	X	--	--	--	--
MW-11S	SSHS-MW-11S_F	Permanent	3/23/2016	X	--	--	--	--
MW-11S	FD-1	Permanent	11/1/2018	X	X	X	X	--
MW-11S	MW-11S-GW	Permanent	11/1/2018	X	X	X	X	--
MW-11S	DUP-01	Permanent	7/25/2019	X	X	X	X	--
MW-11S	MW-11S	Permanent	7/25/2019	X	X	X	X	--
MW-11S	TAC22_MW-11S (180-93333-4)	Permanent	7/27/2019	--	--	--	--	X

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-11S	MW-11S	Permanent	2/23/2021	X	X	X	X	X
MW-11S	MW-11S	Permanent	4/30/2021	X	X	X	X	X
MW-11S	MW-11S	Permanent	4/30/2021	--	--	--	--	X
MW-12	MW-12	Permanent	12/19/1997	--	--	--	X	--
MW-12	MW-12	Permanent	5/17/2000	--	X	X	X	--
MW-12	MW-12	Permanent	5/17/2000	--	--	--	X	--
MW-12	MW12	Permanent	9/20/2000	--	X	X	--	--
MW-12	MW-12	Permanent	9/20/2000	--	--	--	X	--
MW-12	MW-12	Permanent	4/2/2002	--	--	--	X	--
MW-12	MW-12	Permanent	7/23/2002	--	--	--	X	--
MW-12	MW-12	Permanent	5/20/2003	--	--	--	X	--
MW-12	MW-12	Permanent	5/20/2003	--	--	--	X	--
MW-12	MW-12	Permanent	9/24/2003	--	--	--	X	--
MW-12	MW-12	Permanent	9/24/2003	--	--	--	X	--
MW-12	MW-12	Permanent	6/1/2004	--	--	--	X	--
MW-12	MW-12	Permanent	12/30/2004	--	--	--	X	--
MW-12	MW-12	Permanent	6/28/2005	--	--	--	X	--
MW-12	MW-12	Permanent	12/28/2005	--	--	--	X	--
MW-12	MW-12	Permanent	7/12/2007	--	--	--	X	--
MW-12	MW-12	Permanent	2/21/2021	X	X	X	X	--
MW-12	MW-12	Permanent	7/14/2021	X	X	X	X	--
MW-13	DUP-1	Permanent	8/20/2014	--	--	--	X	--
MW-13	MW-13	Permanent	8/20/2014	--	--	--	X	--
MW-13	DUP-02	Permanent	2/21/2021	X	X	X	X	X
MW-13	MW-13	Permanent	2/21/2021	X	X	X	X	X
MW-13	MW-13	Permanent	7/15/2021	X	X	X	X	X
MW-13	SSHS-MW-13-04232024	Permanent	4/23/2024	X	--	--	--	--
MW-15D	MW-15D	Permanent	4/29/2003	--	--	--	X	--
MW-15D	MW-15D	Permanent	5/20/2003	--	--	--	X	--
MW-15D	MW-15D	Permanent	9/24/2006	--	--	--	X	--
MW-15S	MW-15S	Permanent	5/20/2003	--	--	--	X	--
MW-15S	SSHS-MW-15S	Permanent	9/27/2016	X	--	--	--	--
MW-17	MW17	Permanent	5/17/2000	--	X	X	X	--
MW-17	MW17	Permanent	9/20/2000	--	X	X	X	--
MW-17	MW-17	Permanent	5/20/2003	--	--	--	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-20	MW20	Permanent	5/17/2000	--	X	X	X	--
MW-20	MW20	Permanent	9/20/2000	--	X	X	--	--
MW-20	MW-20	Permanent	2/23/2021	X	X	X	X	--
MW-20	MW-20	Permanent	7/15/2021	X	X	X	X	--
MW-22	MW-22	Permanent	5/20/2003	--	--	--	X	--
MW-22	MW-22	Permanent	2/23/2021	X	X	X	X	--
MW-22	MW-22	Permanent	7/15/2021	X	X	X	X	--
MW-26	MW-26	Permanent	2/17/2021	X	X	X	X	--
MW-26	MW-26	Permanent	7/14/2021	X	X	X	X	--
MW-26	SSHS-MW-26-04112024	Permanent	4/11/2024	--	--	X	--	--
MW-30	MW-30	Permanent	4/2/2002	--	--	--	X	--
MW-30	MW-30	Permanent	6/19/2002	--	--	--	X	--
MW-30	MW-30	Permanent	7/23/2002	--	--	--	X	--
MW-30	MW-30	Permanent	5/20/2003	--	--	--	X	--
MW-30	MW-30	Permanent	5/20/2003	--	--	--	X	--
MW-30	MW-30-D20	Permanent	5/20/2003	--	--	--	X	--
MW-30	MW-30	Permanent	9/24/2003	--	--	--	X	--
MW-30	MW-30	Permanent	9/24/2003	--	--	--	X	--
MW-30	MW-30-D20	Permanent	9/24/2003	--	--	--	X	--
MW-30	MW-30	Permanent	6/1/2004	--	--	--	X	--
MW-30	MW-30	Permanent	12/30/2004	--	--	--	X	--
MW-30	MW-30	Permanent	6/28/2005	--	--	--	X	--
MW-30	MW-30	Permanent	12/28/2005	--	--	--	X	--
MW-30	MW-30	Permanent	5/25/2006	--	--	--	X	--
MW-30	MW-30	Permanent	7/12/2007	--	--	--	X	--
MW-30	MW-30	Permanent	8/21/2014	--	--	--	X	--
MW-30	MW-30	Permanent	8/21/2014	--	--	--	X	--
MW-30	MW-30	Permanent	8/21/2014	--	--	--	--	--
MW-30	MW-30	Permanent	7/26/2019	X	X	X	X	--
MW-30	TAC22_MW-30 (180-93333-7)	Permanent	7/26/2019	--	--	--	--	X
MW-30	MW-30	Permanent	2/19/2021	X	X	X	X	--
MW-30	MW-30	Permanent	7/16/2021	X	X	X	X	--
MW-30	SSHS-MW-30-04302024	Permanent	4/30/2024	X	X	--	X	--
MW-31	MW-31	Permanent	5/20/2003	--	--	--	X	--
MW-31	GW-FD-1	Permanent	3/22/2016	X	--	--	--	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-31	SSHS-MW-31	Permanent	3/22/2016	X	--	--	--	--
MW-31	SSHS-MW-31_F	Permanent	3/22/2016	X	--	--	--	--
MW-32	MW-32	Permanent	3/26/2008	X	--	--	--	--
MW-32	SSHS-MW-32	Permanent	3/21/2016	X	--	--	--	--
MW-32	SSHS-MW-32_F	Permanent	3/21/2016	X	--	--	--	--
MW-32	MW-32	Permanent	2/22/2021	X	X	X	X	--
MW-32	MW-32	Permanent	7/13/2021	X	X	X	X	--
MW-32	SSHS-MW-32-04042024	Permanent	4/4/2024	X	--	--	--	--
MW-33	GW-FD-2	Permanent	3/23/2016	X	--	--	--	--
MW-33	SSHS-MW-33	Permanent	3/23/2016	X	--	--	--	--
MW-33	SSHS-MW-33_F	Permanent	3/23/2016	X	--	--	--	--
MW-33	MW-33	Permanent	2/19/2021	X	X	X	X	X
MW-33	MW-33	Permanent	7/13/2021	X	X	X	X	X
MW-34	DUP-2	Permanent	8/22/2014	X	--	--	--	--
MW-34	MW-34	Permanent	8/22/2014	X	--	--	--	--
MW-34	GW-FD-4_F	Permanent	3/23/2016	X	--	--	--	--
MW-34	SSHS-MW-34	Permanent	3/23/2016	X	--	--	--	--
MW-34	SSHS-MW-34_F	Permanent	3/23/2016	X	--	--	--	--
MW-34	MW-34	Permanent	2/24/2021	X	X	--	X	X
MW-34	MW-34	Permanent	3/23/2021	--	--	X	--	--
MW-34	MW-34	Permanent	4/30/2021	X	X	X	X	X
MW-34	SSHS-MW-34-04302024	Permanent	4/30/2024	X	--	--	--	--
MW-36	SSHS-MW-36	Permanent	3/23/2016	X	--	--	--	--
MW-36	SSHS-MW-36_F	Permanent	3/23/2016	X	--	--	--	--
MW-36	SSHS-MW36	Permanent	8/22/2018	X	X	X	X	--
MW-36	SSHS-MW36	Permanent	8/22/2018	--	--	--	X	--
MW-36	MW-36	Permanent	3/23/2021	X	X	X	X	--
MW-36	MW-36	Permanent	4/30/2021	X	X	X	X	--
MW-38	MW-38	Permanent	8/21/2014	X	--	--	--	--
MW-38	SSHS-MW-38	Permanent	3/23/2016	X	--	--	--	--
MW-38	SSHS-MW-38_F	Permanent	3/23/2016	X	--	--	--	--
MW-38	SSHS-MW-38	Permanent	8/23/2018	X	X	X	X	--
MW-38	PS-FD-1	Permanent	8/24/2018	X	X	X	X	--
MW-38	MW-38	Permanent	3/24/2021	X	X	X	X	--
MW-38	DUP-1	Permanent	4/30/2021	X	X	X	X	--

DRAFT

Table 2-5
Groundwater Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-38	MW-38	Permanent	4/30/2021	X	X	X	X	--
MW-39	SSHS-MW-39	Permanent	3/23/2016	X	--	--	--	--
MW-39	SSHS-MW-39_F	Permanent	3/23/2016	X	--	--	--	--
MW-39	SSHS-MW-39	Permanent	8/23/2018	X	X	X	X	--
MW-40	MW-40	Permanent	5/23/2019	X	X	X	X	--
MW-40	MW-40	Permanent	2/23/2021	X	X	X	X	--
MW-41	MW-41	Permanent	3/26/2008	X	--	--	X	--
MW-41	MW-41	Permanent	8/22/2014	X	--	--	--	--
MW-41	SSHS-MW-41	Permanent	3/23/2016	X	--	--	--	--
MW-41	SSHS-MW-41_F	Permanent	3/23/2016	X	--	--	--	--
MW-41	DUP-03	Permanent	2/20/2021	X	X	X	X	--
MW-41	MW-41	Permanent	2/20/2021	X	X	X	X	--
MW-41	MW-41	Permanent	7/13/2021	X	X	X	X	--
MW-41	SSHS-MW-41-04112024	Permanent	4/11/2024	X	--	--	--	--
MW-42	SSHS-MW-42	Permanent	3/23/2016	X	--	--	--	--
MW-42	SSHS-MW-42_F	Permanent	3/23/2016	X	--	--	--	--
MW-43	SSHS-MW-43	Permanent	3/23/2016	X	--	--	--	--
MW-43	SSHS-MW-43_F	Permanent	3/23/2016	X	--	--	--	--
MW-43	MW-43	Permanent	2/16/2021	X	X	X	--	--
MW-43	MW-43	Permanent	2/24/2021	--	--	--	X	--
MW-43	MW-43	Permanent	7/13/2021	X	X	X	X	--
MW-44	SSHS-MW-44	Permanent	3/23/2016	X	--	--	--	--
MW-44	SSHS-MW-44_F	Permanent	3/23/2016	X	--	--	--	--
MW-44	SSHS-MW-44	Permanent	8/23/2018	X	X	X	X	--
MW-46	SSHS-MW-46	Permanent	9/27/2016	X	--	--	--	--
MW-47	SSHS-MW-47	Permanent	9/26/2016	--	--	--	X	--
MW-47	GW-FD-0927	Permanent	9/27/2016	X	--	--	--	--
MW-47	TAC22_MW-47 (180-93333-2)	Permanent	7/27/2019	--	--	--	--	X
MW-47	DUP-01	Permanent	2/22/2021	X	X	X	X	X
MW-47	MW-47	Permanent	2/22/2021	X	X	X	X	X
MW-47	MW-47	Permanent	7/12/2021	X	X	X	X	X
MW-47I	MW-47I	Permanent	9/10/2021	X	X	X	X	X
MW-47I	DUP-01	Permanent	10/27/2021	X	X	X	X	X
MW-47I	MW-47I	Permanent	10/27/2021	X	X	X	X	X
MW-47I	SSHS-DUP-01-04252024	Permanent	4/25/2024	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-47I	SSHS-MW-47I-04252024	Permanent	4/25/2024	X	X	X	X	--
MW-48	MW-48	Permanent	2/17/2021	X	X	X	X	X
MW-48	MW-48	Permanent	4/26/2021	X	X	X	X	X
MW-48R	SSHS-MW-48R-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-48R	SSHS-MW-48R-09132023	Permanent	9/13/2023	X	X	X	--	--
MW-48R	SSHS-DUP-01-11152023	Permanent	11/15/2023	X	X	X	X	--
MW-48R	SSHS-MW-48R-11152023	Permanent	11/15/2023	X	X	X	X	--
MW-48R	DUP-01-01162024	Permanent	1/16/2024	X	X	X	X	--
MW-48R	SSHS-MW-48R-01162024	Permanent	1/16/2024	X	X	X	X	--
MW-48R	SSHS-DUP-02-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-48R	SSHS-MW-48R-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-49	DUP-04	Permanent	2/17/2021	X	X	X	X	--
MW-49	MW-49	Permanent	2/17/2021	X	X	X	X	--
MW-49	MW-49	Permanent	4/28/2021	X	X	X	X	--
MW-50I	SSHS-RI-MW-50I	Permanent	2/12/2021	X	X	X	X	--
MW-50I	MW-50I	Permanent	4/28/2021	X	X	X	X	--
MW-50R	SSHS-MW-50R-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-50R	SSHS-MW-50R-04082024	Permanent	4/8/2024	X	--	X	X	--
MW-50S	SSHS-RI-MW-50S	Permanent	2/12/2021	X	X	X	X	--
MW-50S	MW-50S	Permanent	4/28/2021	X	X	X	X	--
MW-51	DUP-05	Permanent	2/12/2021	X	X	X	X	--
MW-51	DUP-05	Permanent	2/12/2021	--	--	--	X	--
MW-51	SSHS-RI-MW-51	Permanent	2/12/2021	X	X	X	X	--
MW-51	SSHS-RI-MW-51	Permanent	2/12/2021	--	--	--	X	--
MW-51	MW-51	Permanent	4/27/2021	X	X	--	--	--
MW-51	MW-51	Permanent	4/27/2021	X	--	--	X	--
MW-51	SSHS-MW-51-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-51	SSHS-MW-51-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-51	SSHS-DUP-04-09142023	Permanent	9/14/2023	X	X	X	--	--
MW-51	SSHS-MW-51-09142023	Permanent	9/14/2023	X	X	X	--	--
MW-51	SSHS-MW-51-11142023	Permanent	11/14/2023	X	X	X	X	--
MW-51	SSHS-MW-51-01172024	Permanent	1/17/2024	--	--	--	X	--
MW-51	SSHS-MW-51-01182024	Permanent	1/18/2024	X	X	X	--	--
MW-51	SSHS-MW-51-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-52	SSHS-RI-MW-52	Permanent	2/12/2021	X	X	X	X	X

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-52	DUP-2	Permanent	4/28/2021	X	X	X	X	X
MW-52	MW-52	Permanent	4/28/2021	X	X	X	X	X
MW-53	MW-53	Permanent	2/17/2021	X	X	X	X	--
MW-53	MW-53	Permanent	4/26/2021	X	X	X	X	--
MW-53	SSHS-MW-53-09042023	Permanent	9/4/2023	X	X	X	X	--
MW-54	MW-54	Permanent	2/16/2021	X	X	X	--	--
MW-54	MW-54	Permanent	2/25/2021	--	--	--	X	X
MW-54	MW-54	Permanent	4/27/2021	X	X	X	X	X
MW-54	SSHS-RI-MW-54	Permanent	5/10/2021	--	--	X	--	--
MW-54R	SSHS-MW-54R-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-54R	SSHS-MW-54R-04052024	Permanent	4/5/2024	--	--	X	--	--
MW-55	MW-55	Permanent	2/16/2021	X	X	X	--	--
MW-55	MW-55	Permanent	2/24/2021	--	--	--	X	--
MW-55	MW-55	Permanent	4/29/2021	--	--	X	X	--
MW-55	SSHS-RI-MW-55	Permanent	5/10/2021	X	X	--	--	--
MW-55	DUP-01-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-55	SSHS-MW-55-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-55	SSHS-DUP-06-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-55	SSHS-MW-55-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-55	SSHS-MW-55-09132023	Permanent	9/13/2023	X	X	X	--	--
MW-55	SSHS-MW-55-11152023	Permanent	11/15/2023	X	X	X	X	--
MW-55	SSHS-MW-55-01162024	Permanent	1/16/2024	X	X	X	X	--
MW-55	SSHS-MW-55-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-56	MW-56	Permanent	2/17/2021	X	X	X	X	--
MW-56	MW-56	Permanent	4/29/2021	--	--	X	X	--
MW-56	SSHS-RI-MW-56	Permanent	5/12/2021	X	X	--	--	--
MW-56	SSHS-MW-56-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-56	SSHS-MW-56-04082024	Permanent	4/8/2024	X	--	--	--	--
MW-57	MW-57	Permanent	2/18/2021	X	X	X	X	--
MW-57	MW-57	Permanent	4/29/2021	X	X	X	X	--
MW-57	DUP-01	Permanent	7/13/2022	X	X	X	X	--
MW-57	MW-57	Permanent	7/13/2022	X	X	X	X	--
MW-57R	SSHS-MW-57R-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-57R	SSHS-MW-57R-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-57R	SSHS-MW-57R-09142023	Permanent	9/14/2023	X	X	X	--	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-57R	SSHS-MW-57R-11132023	Permanent	11/13/2023	X	X	X	X	--
MW-57R	SSHS-MW-57R-01172024	Permanent	1/17/2024	X	X	X	X	--
MW-57R	SSHS-MW-57R-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-58	MW-58	Permanent	2/21/2021	X	X	X	X	X
MW-58	MW-58	Permanent	4/30/2021	X	X	X	X	X
MW-58	SSHS-DUP-01-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-58	SSHS-MW-58-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-59I	MW-59I	Permanent	2/19/2021	X	X	X	X	--
MW-59I	MW-59I	Permanent	4/29/2021	X	X	X	X	--
MW-59I	MW-59I	Permanent	7/12/2022	X	X	X	X	--
MW-59S	MW-59S	Permanent	2/19/2021	X	X	X	X	--
MW-59S	MW-59S	Permanent	4/29/2021	X	X	X	X	--
MW-59S	MW-59S	Permanent	7/13/2022	X	X	X	X	--
MW-60	MW-60	Permanent	2/18/2021	X	X	X	X	--
MW-60	MW-60	Permanent	4/29/2021	X	X	X	X	--
MW-60	MW-60	Permanent	7/12/2022	X	X	X	X	--
MW-60IR	SSHS-MW-60IR-04052024	Permanent	4/5/2024	--	--	X	--	--
MW-60SR	SSHS-MW-60SR-04052024	Permanent	4/5/2024	--	--	X	--	--
MW-61	MW-61	Permanent	2/16/2021	X	X	X	--	--
MW-61	MW-61	Permanent	2/25/2021	--	--	--	X	X
MW-61	MW-61	Permanent	4/27/2021	X	X	X	X	X
MW-61	MW-61	Permanent	7/12/2022	X	X	X	X	--
MW-62	MW-62	Permanent	2/16/2021	X	X	X	--	--
MW-62	MW-62	Permanent	2/24/2021	--	--	--	X	--
MW-62	MW-62	Permanent	4/27/2021	X	X	X	X	--
MW-62	MW-62	Permanent	7/12/2022	X	X	X	X	--
MW-62R	SSHS-MW-62R-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-62R	SSHS-MW-62R-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-63I	MW-63I	Permanent	2/18/2021	X	X	X	X	--
MW-63I	MW-63I	Permanent	4/29/2021	X	--	X	X	--
MW-63I	SSHS-RI-MW-63I	Permanent	5/10/2021	--	X	--	--	--
MW-63I	SSHS-MW-63I-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-63S	MW-63S	Permanent	2/18/2021	X	X	X	X	--
MW-63S	MW-63S	Permanent	4/29/2021	X	--	X	X	--
MW-63S	SSHS-RI-MW-63S	Permanent	5/10/2021	--	X	--	--	--

DRAFT

Table 2-5
Groundwater Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-63S	SSHS-MW-63S-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-64I	MW-64I	Permanent	2/20/2021	X	X	X	X	--
MW-64I	MW-64I	Permanent	4/28/2021	X	X	X	X	--
MW-64I	SSHS-MW-64I-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-64I	SSHS-MW-64I-04052024	Permanent	4/5/2024	--	--	X	--	--
MW-64S	MW-64S	Permanent	2/20/2021	X	X	X	X	X
MW-64S	MW-64S	Permanent	4/28/2021	X	X	X	X	X
MW-64S	SSHS-MW-64S-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-65	MW-65	Permanent	2/20/2021	X	X	X	X	--
MW-65	DUP-3	Permanent	4/26/2021	X	X	X	X	--
MW-65	MW-65	Permanent	4/26/2021	X	X	X	X	--
MW-65	SSHS-DUP1-08152022	Permanent	8/15/2022	X	X	X	X	--
MW-65	SSHS-MW-65-08152022	Permanent	8/15/2022	X	X	X	X	--
MW-65R	SSHS-MW-65R-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-65R	SSHS-MW-65R-04082024	Permanent	4/8/2024	X	X	X	X	--
MW-66I	MW-66I	Permanent	2/20/2021	X	X	X	X	--
MW-66I	MW-66I	Permanent	4/28/2021	X	X	X	X	--
MW-66I	SSHS-MW-66I-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-66S	MW-66S	Permanent	2/19/2021	X	X	X	X	--
MW-66S	MW-66S	Permanent	4/28/2021	X	X	X	X	--
MW-66S	SSHS-MW-66S-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-67I	MW-67I	Permanent	7/16/2021	X	X	X	X	--
MW-67I	MW-67I	Permanent	8/31/2021	X	X	X	X	--
MW-67I	SSHS-MW-67I-04282024	Permanent	4/28/2024	X	X	X	X	--
MW-67S	MW-67S	Permanent	7/16/2021	X	X	X	X	--
MW-67S	MW-67S	Permanent	8/31/2021	X	X	X	X	--
MW-67S	SSHS-DUP-03-04282024	Permanent	4/28/2024	X	X	X	X	--
MW-67S	SSHS-MW-67S-04282024	Permanent	4/28/2024	X	X	X	X	--
MW-68S	DUP-3	Permanent	7/13/2021	X	X	X	X	--
MW-68S	MW-68S	Permanent	7/13/2021	X	X	X	X	--
MW-68S	DUP-2	Permanent	9/9/2021	X	X	X	X	--
MW-68S	MW-68S	Permanent	9/9/2021	X	X	X	X	--
MW-68S	SSHS-MW-68S-04282024	Permanent	4/28/2024	X	X	X	X	--
MW-69I	MW-69I	Permanent	7/13/2021	X	X	X	X	--
MW-69I	MW-69I	Permanent	9/3/2021	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-69I	SSHS-MW-69I-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-70I	MW-70I	Permanent	9/9/2021	X	X	X	X	--
MW-70I	MW-70I	Permanent	10/27/2021	X	X	X	X	--
MW-70I	SSHS-MW-70I-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-70S	MW-70S	Permanent	9/7/2021	X	X	X	X	--
MW-70S	MW-70S	Permanent	10/27/2021	X	X	X	X	--
MW-70S	DUP-02	Permanent	5/4/2023	X	X	X	X	X
MW-70S	SSHS-MW-70S-05042023	Permanent	5/4/2023	X	X	X	X	X
MW-70S	SSHS-MW-70S-09152023	Permanent	9/15/2023	X	X	X	X	X
MW-70S	SSHS-DUP-04-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-70S	SSHS-MW-70S-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-71I	MW-71I	Permanent	9/7/2021	X	X	X	X	--
MW-71I	MW-71I	Permanent	10/27/2021	X	X	X	X	--
MW-71I	SSHS-MW-71I-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-71S	MW-71S	Permanent	9/7/2021	X	X	X	X	--
MW-71S	MW-71S	Permanent	10/27/2021	X	X	X	X	--
MW-71S	SSHS-MW-71S-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-72I	MW-72I	Permanent	9/8/2021	X	X	X	X	--
MW-72I	DUP-02	Permanent	10/27/2021	X	X	X	X	--
MW-72I	MW-72I	Permanent	10/27/2021	X	X	X	--	--
MW-72I	MW-72I	Permanent	10/27/2021	--	--	--	X	--
MW-72I	SSHS-MW-72I-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-72S	MW-72S	Permanent	9/8/2021	X	X	X	X	--
MW-72S	MW-72S	Permanent	10/27/2021	X	X	X	--	--
MW-72S	MW-72S	Permanent	10/27/2021	--	--	--	X	--
MW-72S	SSHS-MW-72S-05042023	Permanent	5/4/2023	X	X	X	X	X
MW-72S	SSHS-MW-72S-09152023	Permanent	9/15/2023	X	X	X	X	X
MW-72S	SSHS-MW-72S-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-73I	MW-73I	Permanent	9/8/2021	X	X	X	X	--
MW-73I	MW-73I	Permanent	10/27/2021	X	X	X	X	--
MW-73I	SSHS-MW-73I-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-73S	MW-73S	Permanent	9/8/2021	X	X	X	X	--
MW-73S	MW-73S	Permanent	10/26/2021	X	X	X	X	--
MW-73S	SSHS-MW-73S-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-74I	MW-74I	Permanent	9/8/2021	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-74I	MW-74I	Permanent	10/27/2021	X	X	X	X	--
MW-74I	SSHS-MW-74I-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-74S	MW-74S	Permanent	9/8/2021	X	X	X	X	--
MW-74S	MW-74S	Permanent	10/27/2021	X	X	X	X	--
MW-74S	SSHS-DUP-05-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-74S	SSHS-MW-74S-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-75I	MW-75I	Permanent	9/9/2021	X	X	X	X	X
MW-75I	MW-75I	Permanent	10/29/2021	X	X	X	X	X
MW-75I	SSHS-MW-75I-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-75S	MW-75S	Permanent	9/9/2021	X	X	X	X	X
MW-75S	MW-75S	Permanent	10/29/2021	X	X	X	X	X
MW-75S	SSHS-MW-75S-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-76I	MW-76I	Permanent	9/10/2021	X	X	X	X	--
MW-76I	DUP-03	Permanent	10/28/2021	X	X	X	X	--
MW-76I	MW-76I	Permanent	10/28/2021	X	X	X	X	--
MW-76I	SSHS-MW-76I-04082024	Permanent	4/8/2024	--	X	--	--	--
MW-76S	MW-76S	Permanent	9/10/2021	X	X	X	X	--
MW-76S	MW-76S	Permanent	10/28/2021	X	X	X	X	--
MW-76S	SSHS-MW-76S-04082024	Permanent	4/8/2024	X	X	X	X	--
MW-76S	SSHS-MW-76S-04222024	Permanent	4/22/2024	X	X	X	X	--
MW-77I	MW-77I	Permanent	9/10/2021	X	X	X	X	--
MW-77I	MW-77I	Permanent	10/28/2021	X	X	X	X	--
MW-77I	SSHS-MW-77I-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-77S	MW-77S	Permanent	9/10/2021	X	X	X	X	--
MW-77S	MW-77S	Permanent	10/28/2021	X	X	X	X	--
MW-77S	SSHS-MW-77S-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-78I	MW-78I	Permanent	9/10/2021	X	X	X	X	--
MW-78I	MW-78I	Permanent	11/2/2021	X	X	X	X	--
MW-78I	SSHS-MW-78I-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-78S	DUP-5	Permanent	9/10/2021	X	X	X	X	--
MW-78S	MW-78S	Permanent	9/10/2021	X	X	X	X	--
MW-78S	MW-78S	Permanent	11/2/2021	X	X	X	X	--
MW-78S	SSHS-MW-78S-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-79I	MW-79I	Permanent	9/10/2021	X	X	X	X	--
MW-79I	DUP-04	Permanent	11/2/2021	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-79I	MW-79I	Permanent	11/2/2021	X	X	X	--	--
MW-79I	MW-79I	Permanent	11/2/2021	--	--	--	X	--
MW-79I	SSHS-MW-79I-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-79S	MW-79S	Permanent	9/10/2021	X	X	X	X	--
MW-79S	MW-79S	Permanent	11/2/2021	X	X	X	--	--
MW-79S	MW-79S	Permanent	11/2/2021	--	--	--	X	--
MW-79S	SSHS-DUP-06-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-79S	SSHS-MW-79S-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-81I	MW-81I	Permanent	7/16/2021	X	X	X	X	X
MW-81I	MW-81I	Permanent	8/31/2021	X	X	X	X	X
MW-81I	SSHS-MW-81I-04262024	Permanent	4/26/2024	X	X	X	X	--
MW-82S	DUP-3	Permanent	9/7/2021	X	X	X	X	X
MW-82S	MW-82S	Permanent	9/7/2021	X	X	X	X	X
MW-82S	MW-82S	Permanent	10/27/2021	X	X	X	X	X
MW-82S	SSHS-MW-82S-05012024	Permanent	5/1/2024	X	X	X	X	--
MW-83I	MW-83I	Permanent	9/8/2021	X	X	X	X	X
MW-83I	MW-83I	Permanent	10/27/2021	X	X	X	X	--
MW-83I	MW-83I	Permanent	10/28/2021	--	--	--	--	X
MW-83I	SSHS-MW-83I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-83S	MW-83S	Permanent	9/8/2021	X	X	X	X	X
MW-83S	MW-83S	Permanent	10/27/2021	X	X	X	--	--
MW-83S	MW-83S	Permanent	10/27/2021	--	--	--	X	--
MW-83S	MW-83S	Permanent	10/28/2021	--	--	--	--	X
MW-83S	SSHS-MW-83S-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-84S	MW-84S	Permanent	9/9/2021	X	X	X	X	--
MW-84S	MW-84S	Permanent	10/27/2021	X	X	X	X	--
MW-84S	SSHS-DUP-07-04152024	Permanent	4/15/2024	X	X	X	X	--
MW-84S	SSHS-MW-84S-04152024	Permanent	4/15/2024	X	X	X	X	--
MW-85I	MW-85I	Permanent	7/15/2021	X	X	X	X	--
MW-85I	MW-85I	Permanent	9/2/2021	X	X	X	X	--
MW-85I	SSHS-MW-85I-04222024	Permanent	4/22/2024	X	X	X	X	--
MW-86I	MW-86I	Permanent	7/13/2021	X	X	X	X	--
MW-86I	MW-86I	Permanent	9/1/2021	X	X	X	X	--
MW-86I	SSHS-MW-86I-04042024	Permanent	4/4/2024	X	X	X	X	--
MW-87I	MW-87I	Permanent	7/14/2021	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-87I	MW-87I	Permanent	9/2/2021	X	X	X	X	--
MW-87I	SSHS-MW-87I-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-88I	MW-88I	Permanent	7/15/2021	X	X	X	X	--
MW-88I	MW-88I	Permanent	9/2/2021	X	X	X	X	--
MW-88I	SSHS-MW-88I-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-88S	MW-88S	Permanent	7/15/2021	X	X	X	X	--
MW-88S	MW-88S	Permanent	9/2/2021	X	X	X	X	--
MW-88S	SSHS-MW-88S-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-89I	MW-89I	Permanent	7/12/2021	X	X	X	X	X
MW-89I	MW-89I	Permanent	9/1/2021	X	X	X	X	X
MW-89I	SSHS-MW-89I-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-89S	MW-89S	Permanent	7/12/2021	X	X	X	X	X
MW-89S	MW-89S	Permanent	9/1/2021	X	X	X	X	X
MW-89S	SSHS-MW-89S-04302024	Permanent	4/30/2024	X	X	X	X	--
MW-90I	MW-90I	Permanent	9/8/2021	X	X	X	X	X
MW-90I	MW-90I	Permanent	10/28/2021	X	X	X	X	X
MW-90I	SSHS-MW-90I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-90S	MW-90S	Permanent	9/8/2021	X	X	X	X	X
MW-90S	MW-90S	Permanent	10/28/2021	X	X	X	X	X
MW-90S	SSHS-MW-90S-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-91I	MW-91I	Permanent	9/9/2021	X	X	X	X	X
MW-91I	MW-91I	Permanent	11/2/2021	X	X	X	X	X
MW-91I	SSHS-MW-91I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-91S	MW-91S	Permanent	9/9/2021	X	X	X	X	X
MW-91S	MW-91S	Permanent	11/2/2021	X	X	X	X	X
MW-91S	SSHS-MW-91S-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-92I	MW-92I	Permanent	9/10/2021	X	X	X	X	--
MW-92I	MW-92I	Permanent	10/28/2021	X	X	X	X	--
MW-92I	SSHS-MW-92I-04082024	Permanent	4/8/2024	X	X	X	X	--
MW-92S	MW-92S	Permanent	9/10/2021	X	X	X	X	--
MW-92S	MW-92S	Permanent	10/28/2021	X	X	X	X	--
MW-92S	SSHS-MW-92S-04052024	Permanent	4/5/2024	X	X	X	X	--
MW-93I	DUP-4	Permanent	9/9/2021	X	X	X	X	--
MW-93I	MW-93I	Permanent	9/9/2021	X	X	X	X	--
MW-93I	MW-93I	Permanent	10/29/2021	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-93I	SSHS-DUP-08-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-93I	SSHS-MW-93I-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-93S	MW-93S	Permanent	9/9/2021	X	X	X	X	--
MW-93S	MW-93S	Permanent	10/29/2021	X	X	X	X	--
MW-93S	SSHS-MW-93S-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-94I	MW-94I	Permanent	9/9/2021	X	X	X	X	X
MW-94I	MW-94I	Permanent	10/27/2021	X	X	X	X	X
MW-94I	SSHS-MW-94I-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-94S	MW-94S	Permanent	9/9/2021	X	X	X	X	X
MW-94S	MW-94S	Permanent	10/27/2021	X	X	X	X	X
MW-94S	SSHS-MW-94S-04112024	Permanent	4/11/2024	X	X	X	X	--
MW-95I	SSHS-MW-95I-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-95I	SSHS-MW-95I-11142023	Permanent	11/14/2023	X	X	X	X	--
MW-95I	SSHS-MW-95I-01162024	Permanent	1/16/2024	X	X	X	X	--
MW-95I	SSHS-MW-95I-04092024	Permanent	4/9/2024	--	--	--	X	--
MW-95I	SSHS-MW-95I-04112024	Permanent	4/11/2024	X	X	X	--	--
MW-95S	SSHS-MW-95S-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-95S	SSHS-MW-95S-11142023	Permanent	11/14/2023	X	X	X	X	--
MW-95S	SSHS-MW-95S-01162024	Permanent	1/16/2024	X	X	X	X	--
MW-95S	SSHS-MW-95S-04092024	Permanent	4/9/2024	--	--	--	X	--
MW-95S	SSHS-MW-95S-04112024	Permanent	4/11/2024	X	X	X	--	--
MW-96	SSHS-MW-96-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-96	SSHS-MW-96-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-96	SSHS-MW-96-09152023	Permanent	9/15/2023	X	X	X	--	--
MW-96	SSHS-MW-96-11142023	Permanent	11/14/2023	X	X	X	X	--
MW-96	SSHS-MW-96-01172024	Permanent	1/17/2024	X	X	X	X	--
MW-96	SSHS-MW-96-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-97	SSHS-MW-97-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-97	SSHS-MW-97-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-97	SSHS-MW-97-09152023	Permanent	9/15/2023	X	X	X	--	--
MW-97	SSHS-MW-97-11142023	Permanent	11/14/2023	X	X	X	X	--
MW-97	SSHS-MW-97-01172024	Permanent	1/17/2024	X	X	X	X	--
MW-97	SSHS-MW-97-04092024	Permanent	4/9/2024	X	X	X	X	--
MW-98I	DUP-01	Permanent	9/1/2022	X	X	X	X	--
MW-98I	MW-98I	Permanent	9/1/2022	X	X	X	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-98I	SSHS-MW-98I-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-98I	SSHS-MW-98I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-98S	MW-98S	Permanent	9/1/2022	X	X	X	X	--
MW-98S	SSHS-MW-98S-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-98S	SSHS-MW-98S-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-99I	SSHS-MW-99I-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-99I	SSHS-MW-99I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-99S	SSHS-MW-99S-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-99S	SSHS-MW-99S-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-100I	SSHS-MW-100I-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-100I	SSHS-MW-100I-04082024	Permanent	4/8/2024	X	X	X	X	--
MW-100S	SSHS-DUP-02-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-100S	SSHS-MW-100S-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-100S	SSHS-MW-100S-04082024	Permanent	4/8/2024	X	X	X	X	--
MW-101I	SSHS-MW-101I-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-101I	SSHS-MW-101I-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-101S	SSHS-MW-101S-09132023	Permanent	9/13/2023	X	X	X	X	--
MW-101S	SSHS-MW-101S-04102024	Permanent	4/10/2024	X	X	X	X	--
MW-102I	SSHS-MW-102I-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-102I	SSHS-MW-102I-04222024	Permanent	4/22/2024	X	X	X	X	--
MW-102S	SSHS-MW-102S-09142023	Permanent	9/14/2023	X	X	X	X	--
MW-102S	SSHS-MW-102S-04222024	Permanent	4/22/2024	X	X	X	X	--
MW-103I	SSHS-MW-103I-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-103I	SSHS-MW-103I-04162024	Permanent	4/16/2024	X	X	X	X	--
MW-103S	SSHS-MW-103S-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-103S	SSHS-MW-103S-04162024	Permanent	4/16/2024	X	X	X	X	--
MW-104I	SSHS-DUP-03-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-104I	SSHS-MW-104I-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-104I	SSHS-MW-104I-04162024	Permanent	4/16/2024	X	X	X	X	--
MW-104S	SSHS-MW-104S-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-104S	SSHS-MW-104S-04162024	Permanent	4/16/2024	X	X	X	X	--
MW-105I	SSHS-MW-105I-09152023	Permanent	9/15/2023	X	X	X	X	--
MW-105I	SSHS-MW-105I-04172024	Permanent	4/17/2024	X	X	X	X	--
MW-105S	SSHS-MW-105S-09122023	Permanent	9/12/2023	X	X	X	X	--
MW-105S	SSHS-MW-105S-04252024	Permanent	4/25/2024	X	X	X	X	--

DRAFT

Table 2-5
Groundwater Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
MW-106	SSHS-MW-106-05022023	Permanent	5/2/2023	X	X	X	X	--
MW-106	SSHS-MW-106-09122023	Permanent	9/12/2023	--	--	--	X	--
MW-106	SSHS-MW-106-09142023	Permanent	9/14/2023	X	X	X	--	--
MW-106	SSHS-MW-106-11142023	Permanent	11/14/2023	X	X	X	X	--
MW-106	SSHS-MW-106-01182024	Permanent	1/18/2024	X	X	X	X	--
MW-106	SSHS-MW-106-04092024	Permanent	4/9/2024	--	--	--	X	--
MW-106	SSHS-MW-106-04102024	Permanent	4/10/2024	X	X	X	--	--
MW-107I	SSHS-MW-107I-07102025	Permanent	7/11/2025	--	--	--	X	--
MW-107I	SSHS-MW-107I-11132025	Permanent	11/13/2025	--	--	--	X	--
MW-107S	SSHS-MW-107S-07102025	Permanent	7/11/2025	--	--	--	X	--
MW-107S	SSHS-MW-107S-11132025	Permanent	11/13/2025	--	--	--	X	--
MW-108	SSHS-DUP-01-07112025	Permanent	7/11/2025	X	--	--	X	--
MW-108	SSHS-MW-108-07112025	Permanent	7/11/2025	X	--	--	X	--
MW-108	SSHS-DUP-01-11132025	Permanent	11/13/2025	X	--	--	X	--
MW-108	SSHS-MW-108-11132025	Permanent	11/13/2025	X	--	--	X	--
MW-D	D1	Permanent	5/5/2003	--	--	--	X	--
MW-D	D1-D2.5	Permanent	5/5/2003	--	--	--	X	--
MW-D	D2	Permanent	5/5/2003	--	--	--	X	--
MW-D	D2-D10	Permanent	5/5/2003	--	--	--	X	--
MW-D	D3	Permanent	5/5/2003	--	--	--	X	--
MW-D	D4	Permanent	5/5/2003	--	--	--	X	--
MW-D	MW-D	Permanent	5/5/2003	--	--	--	X	--
MW-D	MW-D	Permanent	5/20/2003	--	--	--	X	--
MW-D	MW-D	Permanent	5/20/2003	--	--	--	X	--
MW-D	MW-D-D2.5	Permanent	5/20/2003	--	--	--	X	--
MW-D	MW-D	Permanent	9/24/2003	--	--	--	X	--
MW-D	MW-D	Permanent	9/24/2003	--	--	--	X	--
MW-D	MW-D	Permanent	6/1/2004	--	--	--	X	--
MW-D	MW-D	Permanent	12/30/2004	--	--	--	X	--
MW-D	MW-D	Permanent	12/28/2005	--	--	--	X	--
MW-D	MW-D	Permanent	7/12/2007	--	--	--	X	--
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	Permanent	8/4/2021	X	X	X	X	--
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	Permanent	8/12/2021	--	--	--	--	X
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	Permanent	7/29/2021	X	X	X	X	X
SSHS-B2090A	SSHS-B2090A	Temporary	5/22/2019	--	X	--	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
SSHS-B2221	SSHS-B2221A	Temporary	5/22/2019	--	X	--	--	--
SSHS-B23	B23	Temporary	5/9/2000	--	X	X	X	--
SSHS-B2541	SSHS-B2541-GW	Temporary	10/29/2018	--	X	X	--	--
SSHS-B2542	SSHS-B2542-GW	Temporary	10/29/2018	--	X	X	--	--
SSHS-B2542A	SSHS-B2542A	Temporary	5/22/2019	--	X	--	X	--
SSHS-B2543	SSHS-B2543-GW	Temporary	10/30/2018	--	X	X	--	--
SSHS-B2544	SSHS-B2544-GW	Temporary	10/30/2018	X	X	X	X	--
SSHS-B2544A	SSHS-B2544A	Temporary	6/25/2019	--	--	--	X	--
SSHS-B2629	SSHS-B2629	Temporary	4/25/2019	X	X	X	X	--
SSHS-B26-A	SSHS-B26-A-GW-18-22	Temporary	8/14/2014	--	--	X	X	--
SSHS-B2722	SSHS-B2722	Temporary	5/21/2019	--	X	--	--	--
SSHS-B2752	SSHS-B2752	Temporary	4/25/2019	X	X	X	X	--
SSHS-B2819	SSHS-B2819	Temporary	5/22/2019	--	--	--	X	--
SSHS-B2978b	SSHS-B2978b	Temporary	11/12/2019	--	--	--	X	--
SSHS-B2978b	DUP-03	Temporary	11/12/2019	--	--	--	X	--
SSHS-B29-A	SSHS-B29-A-GW-18-22	Temporary	8/13/2014	X	--	X	X	--
SSHS-B3088	B3088	Temporary	7/27/2019	--	--	X	--	--
SSHS-B3088	TAC22_B3088 (180-93333-9)	Temporary	7/27/2019	--	--	--	--	X
SSHS-B3089	B3089	Temporary	7/26/2019	--	--	--	--	--
SSHS-B3089	TAC22_B3089 (180-93333-8)	Temporary	7/26/2019	--	--	--	--	X
SSHS-B3090	SSHS-B3090	Temporary	8/8/2019	--	--	--	X	--
SSHS-B3092A	SSHS-B3092	Temporary	8/8/2019	--	--	--	X	--
SSHS-B3093	B3093	Temporary	7/27/2019	--	--	--	X	--
SSHS-B3094	SSHS-B3094	Temporary	8/9/2019	--	--	--	X	--
SSHS-B3200A	DUP-01	Temporary	9/15/2019	X	X	X	X	X
SSHS-B3200A	SSHS-B3200a	Temporary	9/15/2019	X	X	X	X	X
SSHS-B3200B	SSHS-B3200b	Temporary	9/15/2019	--	--	--	X	X
SSHS-B3201A	SSHS-B3201a	Temporary	9/15/2019	--	--	--	X	--
SSHS-B3201B	SSHS-B3201b	Temporary	9/14/2019	--	--	--	X	--
SSHS-B3202A	SSHS-B3202a	Temporary	9/14/2019	--	--	--	X	--
SSHS-B3202B	SSHS-B3202b	Temporary	9/14/2019	--	--	--	X	--
SSHS-B3203A	SSHS-3203a	Temporary	9/13/2019	X	X	X	X	--
SSHS-B3203B	SSHS-3203b	Temporary	9/13/2019	--	--	--	X	--
SSHS-B3204A	SSHS-3204a	Temporary	9/13/2019	--	--	--	X	--
SSHS-B3204B	SSHS-3204b	Temporary	9/13/2019	--	--	--	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
SSHS-B3205A	SSHS-B3205a	Temporary	9/14/2019	--	--	--	X	X
SSHS-B3205B	SSHS-B3205b	Temporary	9/14/2019	--	--	--	X	X
SSHS-B3555	SSHS-RI-B3555 TEMP	Temporary	1/16/2021	X	X	--	X	--
SSHS-B3556	SSHS-RI-B3556-TEMP	Temporary	1/14/2021	X	X	--	X	--
SSHS-B3557	SSHS-RI-B3557 TEMP	Temporary	1/13/2021	X	X	--	X	--
SSHS-B3558	SSHS-RI-B3558-TEMP	Temporary	1/15/2021	X	X	--	X	--
SSHS-B3559	SSHS-RI-B3559 TEMP	Temporary	1/16/2021	X	X	--	X	--
SSHS-B3560	SSHS-RI-B3560-TEMP	Temporary	1/15/2021	X	--	--	--	--
SSHS-B3560	SSHS-RI-B3560R TEMP	Temporary	1/19/2021	--	X	--	X	--
SSHS-B3561		Temporary	1/15/2021	X	--	--	--	--
SSHS-B3561	SSHS-RI-B3561-TEMP	Temporary	1/15/2021	X	--	--	--	--
SSHS-B3561	SSHS-RI-B3561R TEMP	Temporary	1/18/2021	--	X	--	X	--
SSHS-B3561	SSHS-RI-DUP27	Temporary	1/18/2021	--	X	--	X	--
SSHS-B3562	DUP-28	Temporary	1/14/2021	X	X	--	X	--
SSHS-B3562	SSHS-RI-B3562-TEMP	Temporary	1/14/2021	X	X	--	X	--
SSHS-B3563	SSHS-RI-B3563-TEMP	Temporary	1/14/2021	X	X	--	X	--
SSHS-B3563I	SSHS-RI-B3563I TEMP	Temporary	1/16/2021	X	X	--	X	--
SSHS-B3564	SSHS-RI-B3564-TEMP	Temporary	1/15/2021	X	--	--	--	--
SSHS-B3564	SSHS-RI-B3564R TEMP	Temporary	1/18/2021	--	X	--	X	--
SSHS-B3565	SSHS-RI-B3565-TEMP	Temporary	1/14/2021	X	X	--	X	--
SSHS-B3566	SSHS-RI-B3566-TEMP	Temporary	1/15/2021	X	--	--	--	--
SSHS-B3566	SSHS-RI-B3566R TEMP	Temporary	1/18/2021	--	X	--	X	--
SSHS-B3571	SSHS-RI-B3571 TEMP	Temporary	1/16/2021	X	X	--	X	--
SSHS-B510	SSHS-B510	Temporary	9/20/2016	X	--	X	X	--
SSHS-B572A	SSHS-B572A	Temporary	9/2/2016	X	--	X	X	--
SSHS-B575A	SSHS-B575A	Temporary	9/19/2016	--	--	X	X	--
SSHS-B575B	SSHS-B575B	Temporary	9/19/2016	--	--	X	X	--
SSHS-B575C	PS-FD-54	Temporary	9/19/2016	--	--	X	X	--
SSHS-B575C	SSHS-B575C	Temporary	9/21/2016	--	--	X	X	--
SSHS-B92	SSHS-B92-GW-18-22	Temporary	8/12/2014	--	--	--	X	--
SSHS-B93	DUP-3-GW	Temporary	8/12/2014	--	--	--	X	--
SSHS-B93	SSHS-B93-GW-18-22	Temporary	8/12/2014	--	--	--	X	--
SSHS-B94	SSHS-B94-GW-18-22	Temporary	8/12/2014	--	--	--	X	--
SSHS-B95	SSHS-B95-GW-18-22	Temporary	8/12/2014	--	--	--	X	--
SSHS-B96	SSHS-B96-GW-18-22	Temporary	8/12/2014	--	--	--	X	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
SSHS-B97	SSHS-B97-GW-18-22	Temporary	8/13/2014	--	--	--	X	--
SSHS-B98	SSHS-B98-GW-18-22	Temporary	8/13/2014	--	--	--	X	--
SSHS-B99	SSHS-99-GW-17-21	Temporary	8/13/2014	X	--	X	X	--
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	Temporary	7/1/2021	X	X	X	X	X
SSHS-RI-B3855I TEMP	DUP-GW-01	Temporary	4/15/2021	X	--	--	--	--
SSHS-RI-B3855I TEMP	SSHS-RI-B3855I TEMP	Temporary	4/15/2021	X	--	--	--	--
SSHS-RI-B3855S TEMP	SSHS-RI-B3855S TEMP	Temporary	4/16/2021	X	--	--	--	--
SSHS-RI-B3856I TEMP	SSHS-RI-B3856I TEMP	Temporary	4/8/2021	X	--	--	--	--
SSHS-RI-B3856S TEMP	SSHS-RI-B3856S TEMP	Temporary	4/8/2021	X	--	--	--	--
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	Temporary	4/9/2021	X	X	X	X	X
SSHS-RI-B3858I TEMP	SSHS-RI-B3858I TEMP	Temporary	4/13/2021	X	--	--	--	--
SSHS-RI-B3858S TEMP	SSHS-RI-B3858S TEMP	Temporary	4/13/2021	X	--	--	--	--
SSHS-RI-B3859I TEMP	SSHS-RI-B3859I TEMP	Temporary	4/16/2021	X	--	--	--	--
SSHS-RI-B3859S TEMP	SSHS-RI-B3859S TEMP	Temporary	4/16/2021	X	--	--	--	--
SSHS-RI-B3860I TEMP	DUP-GW-02	Temporary	4/15/2021	X	X	X	X	X
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	Temporary	4/15/2021	X	X	X	X	X
SSHS-RI-B3860S TEMP	SSHS-RI-B3860S TEMP	Temporary	4/15/2021	X	--	--	--	--
SSHS-RI-B3861I TEMP	DUP-GW-03	Temporary	4/21/2021	X	--	--	--	--
SSHS-RI-B3861I TEMP	SSHS-RI-B3861I TEMP	Temporary	4/21/2021	X	--	--	--	--
SSHS-RI-B3861S TEMP	SSHS-RI-B3861S TEMP	Temporary	4/21/2021	X	--	--	--	--
SSHS-RI-B3862 TEMP	SSHS-RI-B3862 TEMP	Temporary	4/7/2021	X	--	--	--	--
SSHS-RI-B3863 TEMP	SSHS-RI-B3863 TEMP	Temporary	4/14/2021	X	--	--	--	--
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	Temporary	4/13/2021	X	X	X	X	X
SSHS-RI-B3864S TEMP	SSHS-RI-B3864S TEMP	Temporary	4/13/2021	X	--	--	--	--
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	Temporary	4/9/2021	X	X	X	X	X
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	Temporary	4/9/2021	X	X	X	X	X
SSHS-RI-B3866 TEMP	DUP-GW-04 P	Temporary	4/8/2021	X	--	--	--	--
SSHS-RI-B3866 TEMP	SSHS-RI-B3866 TEMP	Temporary	4/8/2021	X	--	--	--	--
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	Temporary	4/6/2021	X	X	X	X	X
SSHS-RI-B3868I TEMP	SSHS-RI-B3868I TEMP	Temporary	4/6/2021	X	--	--	--	--
SSHS-RI-B3868S TEMP	SSHS-RI-B3868S TEMP	Temporary	4/6/2021	X	--	--	--	--
SSHS-RI-B3869I TEMP	SSHS-RI-B3869I TEMP	Temporary	4/5/2021	X	--	--	--	--
SSHS-RI-B3869S TEMP	SSHS-RI-B3869S TEMP	Temporary	4/6/2021	X	--	--	--	--
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	Temporary	4/7/2021	X	X	X	X	X
SSHS-RI-B3875 TEMP	SSHS-RI-B3875 TEMP	Temporary	4/5/2021	X	--	--	--	--

DRAFT

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
SSHS-RI-B3876 TEMP	040621 10:00_SSHS-RI-B3876 TEMP	Temporary	4/5/2021	X	--	--	--	--
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	Temporary	4/14/2021	X	X	X	X	X
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	Temporary	4/14/2021	X	X	X	X	X
SSHS-RI-B3878 TEMP	SSHS-RI-B3878 TEMP	Temporary	4/7/2021	X	--	--	--	--
SSHS-RI-B3879 TEMP	SSHS-RI-B3879 TEMP	Temporary	4/7/2021	X	--	--	--	--
SSHS-RI-B3881I TEMP	SSHS-RI-B3881I TEMP	Temporary	4/18/2021	X	--	--	--	--
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	Temporary	5/14/2021	X	X	X	X	X
SSHS-RI-B3883-TEMP	SSHS-RI-B3883-TEMP	Temporary	5/20/2021	X	--	--	--	--
SSHS-RI-B3885-TEMP	SSHS-RI-B3885-TEMP	Temporary	9/23/2021	X	--	--	--	--
SSHS-RI-B3886-TEMP	DUP-GW-01	Temporary	5/19/2021	X	X	X	X	X
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	Temporary	5/19/2021	X	X	X	X	X
SSHS-RI-B3890I-TEMP	DUP-GW-02	Temporary	5/14/2021	X	--	--	--	--
SSHS-RI-B3890I-TEMP	SSHS-RI-B3890I-TEMP	Temporary	5/14/2021	X	--	--	--	--
SSHS-RI-B3890S-TEMP	SSHS-RI-B3890S-TEMP	Temporary	5/18/2021	X	--	--	--	--
SSHS-RI-B3893I-TEMP	SSHS-RI-B3893I-TEMP	Temporary	5/14/2021	X	--	--	--	--
SSHS-RI-B3893S-TEMP	SSHS-RI-B3893S-TEMP	Temporary	5/18/2021	X	--	--	--	--
SSHS-RI-B3894-TEMP	SSHS-RI-B3894-TEMP	Temporary	5/13/2021	X	--	--	--	--
SSHS-RI-B3898-TEMP	DUP-GW-03	Temporary	5/19/2021	X	--	--	--	--
SSHS-RI-B3898-TEMP	SSHS-RI-B3898-TEMP	Temporary	5/19/2021	X	--	--	--	--
SSHS-RI-B3903I-TEMP	SSHS-RI-B3903I-TEMP	Temporary	5/20/2021	X	--	--	--	--
SSHS-RI-B3903S-TEMP	SSHS-RI-B3903S-TEMP	Temporary	5/20/2021	X	--	--	--	--
SSHS-RI-B3904I-TEMP	SSHS-RI-B3904I-TEMP	Temporary	5/11/2021	X	--	--	--	--
SSHS-RI-B3904S-TEMP	SSHS-RI-B3904S-TEMP	Temporary	5/11/2021	X	--	--	--	--
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	Temporary	5/11/2021	X	X	X	X	X
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	Temporary	5/11/2021	X	X	X	X	X
SSHS-RI-B3909I-TEMP	SSHS-RI-B3909I-TEMP	Temporary	5/12/2021	X	--	--	--	--
SSHS-RI-B3909S-TEMP	SSHS-RI-B3909S-TEMP	Temporary	5/12/2021	X	--	--	--	--
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	Temporary	5/13/2021	X	X	X	X	X
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	Temporary	5/12/2021	X	X	X	X	X
SSHS-RI-B3916I-TEMP	SSHS-RI-B3916I-TEMP	Temporary	5/13/2021	X	--	--	--	--
SSHS-RI-B3916S-TEMP	SSHS-RI-B3916S-TEMP	Temporary	5/18/2021	X	--	--	--	--
SSHS-RI-B4007-TEMP	SSHS-RI-B4007-TEMP	Temporary	5/21/2021	X	--	--	--	--
SSHS-RI-B4008I-TEMP	SSHS-RI-B4008I-TEMP	Temporary	9/23/2021	X	--	--	--	--
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	Temporary	7/23/2021	X	X	X	X	--
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	Temporary	7/26/2021	X	X	X	X	X

DRAFT

Table 2-5
Groundwater Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

Location	Sample Name	Monitoring Well Type	Sample Date	PCBs	Metals	SVOCs	VOCs	PFAS
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	Temporary	7/28/2021	X	X	X	X	X
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	Temporary	7/29/2021	X	X	X	X	X
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	Temporary	7/28/2021	X	X	X	X	X
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	Temporary	7/27/2021	X	X	X	X	X
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	Temporary	7/27/2021	X	X	X	X	X
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	Temporary	7/26/2021	X	X	X	X	X
SSHS-SB1	SB1	Temporary	4/28/2003	--	--	--	X	--
SSHS-SB2	SB2	Temporary	4/28/2003	--	--	--	X	--

Notes:
-"X" denotes parameter requested for sample.
Lab method used: 8082A/ SW8082A - PCBs
Lab method used: 6010C/SW6010C/SW6010D - Metals, SW6020B - Manganese, SW7470A/SW7471B - Mercury
Lab method used: 8270D/SW8270D/8270D_LL/SW8270E/8270E-LL - SVOCs
Lab method used: 8260C/SW8260C/8260C_LL/SW8260D - VOCs
Lab method used: E537(M)/PFC_IDA - PFAS

DRAFT

August 2018	November 2018	May 2019	July 2019	February-March 2021	April 2021	May 2021	July 2021	August-September 2021	October-November 2021	July-August 2022	September 2022	May 2023	September 2023	November 2023	January 2024	April-May 2024	July 2025	November 2025
MW-36	MW-11D	MW-40	MW-11S	MW-1	MW-11S	MW-55	MW-1	MW-8I	MW-47I	MW-57	MW-98S	MW-51	MW-5I	MW-48R	MW-48R	MW-1	MW-11I	MW-11I
MW-38	MW-11S		MW-30	MW-2	MW-11D	MW-56	MW-2	MW-9I	MW-70I	MW-59I	MW-98I	MW-55	MW-48R	MW-51	MW-51	MW-5I	MW-107I	MW-107I
MW-39			MW-47	MW-3	MW-34	MW-63I	MW-3	MW-47I	MW-70S	MW-59S		MW-57R	MW-50R	MW-55	MW-55	MW-8I	MW-107S	MW-107S
MW-44				MW-5S	MW-36	MW-63S	MW-5S	MW-67I	MW-71I	MW-60		MW-70S	MW-51	MW-57R	MW-57R	MW-8S	MW-108	MW-108
				MW-8S	MW-38		MW-8I	MW-67S	MW-71S	MW-61		MW-72S	MW-53	MW-95I	MW-95I	MW-9I		
				MW-9S	MW-48		MW-8S	MW-68S	MW-72I	MW-62		MW-96	MW-54R	MW-95S	MW-95S	MW-9S		
				MW-10	MW-49		MW-9I	MW-69I	MW-72S	MW-65		MW-97	MW-55	MW-96	MW-96	MW-13		
				MW-11D	MW-50S		MW-9S	MW-70I	MW-73I			MW-106	MW-56	MW-97	MW-97	MW-26		
				MW-11S	MW-50I		MW-10	MW-70S	MW-73S				MW-57R	MW-106	MW-106	MW-30		
				MW-12	MW-51		MW-11D	MW-71S	MW-74I				MW-58			MW-32		
				MW-13	MW-52		MW-12	MW-71I	MW-74S				MW-62R			MW-34		
				MW-20	MW-53		MW-13	MW-72S	MW-75I				MW-63I			MW-41		
				MW-22	MW-54		MW-20	MW-72I	MW-75S				MW-63S			MW-47		
				MW-26	MW-55		MW-22	MW-73I	MW-76I				MW-64I			MW-47I		
				MW-30	MW-56		MW-26	MW-73S	MW-76S				MW-64S			MW-48R		
				MW-32	MW-57		MW-30	MW-74I	MW-77I				MW-65R			MW-50R		
				MW-33	MW-58		MW-32	MW-74S	MW-77S				MW-66I			MW-51		
				MW-34	MW-59I		MW-33	MW-75I	MW-78I				MW-66S			MW-54R		
				MW-36	MW-59S		MW-41	MW-75S	MW-78S				MW-70S			MW-55		
				MW-38	MW-60		MW-43	MW-76S	MW-79I				MW-72S			MW-56		
				MW-40	MW-61		MW-47	MW-76I	MW-79S				MW-95I			MW-57R		
				MW-41	MW-62		MW-67S	MW-77I	MW-82S				MW-95S			MW-60IR		
				MW-43	MW-63S		MW-67I	MW-77S	MW-83I				MW-96			MW-60SR		
				MW-47	MW-63I		MW-68S	MW-78S	MW-83S				MW-97			MW-62R		
				MW-48	MW-64I		MW-69I	MW-78I	MW-84S				MW-98I			MW-64I		
				MW-49	MW-64S		MW-81I	MW-79S	MW-90I				MW-98S			MW-65R		
				MW-50S	MW-65		MW-85I	MW-79I	MW-90S				MW-99I			MW-67I		
				MW-50I	MW-66I		MW-86I	MW-81I	MW-91I				MW-99S			MW-67S		
				MW-51	MW-66S		MW-87I	MW-82S	MW-91S				MW-100I			MW-68S		
				MW-52			MW-88S	MW-83S	MW-92I				MW-100S			MW-69I		
				MW-53			MW-88I	MW-83I	MW-92S				MW-101I			MW-70I		
				MW-54			MW-89S	MW-84S	MW-93I				MW-101S			MW-70S		
				MW-55			MW-89I	MW-85I	MW-93S				MW-102I			MW-71I		
				MW-56				MW-86I	MW-94I				MW-102S			MW-71S		
				MW-57				MW-87I	MW-94S				MW-103I			MW-72I		
				MW-58				MW-88I					MW-103S			MW-72S		
				MW-59S				MW-88S					MW-104I			MW-73I		
				MW-59I				MW-89S					MW-104S			MW-73S		
				MW-60				MW-89I					MW-105I			MW-74I		
				MW-61				MW-90I					MW-105S			MW-74S		
				MW-62				MW-90S					MW-106			MW-75I		
				MW-63S				MW-91I								MW-75S		
				MW-63I				MW-91S								MW-76I		
				MW-64S				MW-92S								MW-76S		
				MW-64I				MW-92I								MW-77I		
				MW-65				MW-93S								MW-77S		
				MW-66I				MW-93I								MW-78I		
				MW-66S				MW-94I								MW-78S		
								MW-94S								MW-79I		
																MW-79S		
																MW-81I		
																MW-82S		
																MW-83I		
																MW-83S		
																MW-84S		
																MW-85I		
																MW-86I		

DRAFT

Table 2-5
Groundwater Investigation Summary

Former Sperry Remington Site - North Portion #c808022
Elmira, NY

August 2018	November 2018	May 2019	July 2019	February-March 2021	April 2021	May 2021	July 2021	August-September 2021	October-November 2021	July-August 2022	September 2022	May 2023	September 2023	November 2023	January 2024	April-May 2024	July 2025	November 2025
																MW-87I		
																MW-88I		
																MW-88S		
																MW-89I		
																MW-89S		
																MW-90I		
																MW-90S		
																MW-91I		
																MW-91S		
																MW-92I		
																MW-92S		
																MW-93I		
																MW-93S		
																MW-94I		
																MW-94S		
																MW-95I		
																MW-95S		
																MW-96		
																MW-97		
																MW-98I		
																MW-98S		
																MW-99I		
																MW-99S		
																MW-100I		
																MW-100S		
																MW-101I		
																MW-101S		
																MW-102I		
																MW-102S		
																MW-103I		
																MW-103S		
																MW-104I		
																MW-104S		
																MW-105I		
																MW-105S		
																MW-106		

Notes:
Shaded monitoring wells do not have purge logs available

DRAFT

TABLE 2-6
Camera Survey Observations

Former Sperry Remington – North Portion #c808022
Elmira, New York

Segment	Active?	Construction	Extent and Orientation Investigation Complete	Condition / Existence of Laterals	Surface Access Points	Fine-Grained Material Characterized	Notes
1 (Storm, west-east along northern side of FFC)	Yes	12-in diameter concrete, 8 feet depth to base at MH-1	Yes. West to east, confirmed via camera survey (2014 and 2019), geophysical survey (2019) and construction drawings provided by Chemung County Sewer District (CCSD) (2019).	Approximately 377 feet of the sewer was camera surveyed to the west where it terminated at a manhole located in South Main Street (ST-6). Approximately 251 feet of the sewer was camera surveyed to the east (2019) and laterals were identified as depicted on **Figure 2-4**. No breaches of the line were observed.	One identified (MH-1) through field assessment, construction drawings, and geophysical survey. Outside of the FFC two additional downstream access points (MH-2 and MH-3) were identified and sampled (2019).	Yes. Observed and sampled at MH-1. Samples were also collected from the off-site manhole locations.	MH-2 removed during IRM excavations.
2 (Former Industrial, from CB-24 to CB-01)	No	24-in diameter concrete, 7 feet depth to base at CB-24	Yes. Extends south from CB-24 exiting the FFC and Site to the south, re-entering the Site and continuing to CB-1 south of the FFC, confirmed to FFC southern fence line by 2019 geophysical survey and camera survey from a test pit located near the southern fence line.	Approximately 75 feet of the sewer was camera surveyed (2014), and the survey was terminated at an obstruction caused by a breach in the top of the sewer pipe. A camera survey was completed in 2019 to confirm the pipe location from the breach past the southern fence line. One 10-in diameter lateral enters at CB-24 from the west (**Figure 2-4**); no other laterals were identified during the camera survey.	One identified (CB-24) through field assessment and geophysical survey. Access from south (CB-1) blocked by breach.	Yes. Observed and sampled at CB-24 (2016).	The lateral entering CB-24 from the west is listed as Segment 5, below. Segment 2 was removed during IRM #5 from CB-24 to southern end of the FFC.

DRAFT

TABLE 2-6
Camera Survey Observations

Former Sperry Remington – North Portion #c808022
Elmira, New York

Segment	Active?	Construction	Extent and Orientation Investigation Complete	Condition / Existence of Laterals	Surface Access Points	Fine-Grained Material Characterized	Notes
3 (Former Industrial, north from CB-24)	No	24-in diameter concrete, 7 feet depth to base at CB-24, top of pipe observed in test pit installed north of the visitor's grandstand was approximately 3 feet.	Yes (FFC portion); northern extent confirmed via camera survey (2014, 2019,2021), test pitting (2019, 2021) and geophysical survey (2019). Observed to run roughly parallel with the FFC east fence line. Suspected to connect with CB-39 (AOC 2C) in the southeast corner of the Northern Athletic Fields based on geophysical survey (2019). Observed to terminate at a vault with opening to the west (2021).	Approximately 22 feet of the sewer was camera surveyed (2019) north from CB-24, and the survey was terminated at an obstruction caused by tree roots. One 10-in concrete lateral enters from the west approximately six feet north of CB-24 (listed as Segment 4, below). A test pit was installed in December 2019 approximately 85 feet to the north of CB-24 to access Segment 3. A robotic CCTV camera survey was performed an additional 40 feet north, where it was terminated on tree roots.	One identified (CB-24) through field assessment and geophysical survey.	Yes. Observed and sampled at CB-24 (2016).	The lateral entering Segment 3 from the west is listed as Segment 4, below. Segment 3 was removed during IRM #5.

DRAFT

TABLE 2-6
Camera Survey Observations

Former Sperry Remington – North Portion #c808022
Elmira, New York

Segment	Active?	Construction	Extent and Orientation Investigation Complete	Condition / Existence of Laterals	Surface Access Points	Fine-Grained Material Characterized	Notes
4 (Former Industrial, enters Segment 3 from west)	No	10-in diameter concrete, 6 feet depth to base of pipe based on depth of Segment 3.	No. This lateral was observed to enter Segment 3 at a point approximately seven feet north of CB-24, from the west, via camera survey (2019).	None identified through geophysical survey (electromagnetic, GPR) (2019).	CB-24 is seven feet to the south.	Sampling was impracticable given lack of access point.	The diameter of this lateral and orientation relative to nearest access point CB-24 precludes access by robotic CCTV camera survey. Based on the extent and orientation of Segment 5 (described below) it is presumed that Segment 4 continued toward the northwest beneath the football field. The presence of the visitor's grandstand precluded the ability to install a test pit to confirm orientation. Segment 4 was identified as Pipe 18 during IRM #5 and was removed.

DRAFT

TABLE 2-6
Camera Survey Observations

Former Sperry Remington – North Portion #c808022
Elmira, New York

Segment	Active?	Construction	Extent and Orientation Investigation Complete	Condition / Existence of Laterals	Surface Access Points	Fine-Grained Material Characterized	Notes
5 (Former Industrial, enters CB-24 from west)	No	10-in diameter concrete, 6 feet depth to base based on CB-24 observations	Yes. This segment was identified through test pitting and was observed to run toward the northwest. Geophysics were used to continue mapping the sewer beneath the football field (2019).	None identified through geophysical survey (electromagnetic, GPR) (2019).	One identified (CB-24) through field assessment and geophysical survey.	Yes. Sample collected from test pit (2019).	The diameter of this lateral and orientation relative to nearest access point CB-24 precludes access by robotic CCTV camera survey. The orientation of Segment 5 was determined based on observations at Test Pit 2 and by locating a rodder placed into Segment 5 at CB-24 and extending to Test Pit 2. Segment 5 was thus shown to extend from CB-24 to the northwest through Test Pit 2. Segment 5 was identified as Pipe 32 during IRM #5 and was removed.

DRAFT

TABLE 2-6
Camera Survey Observations

Former Sperry Remington – North Portion #c808022
Elmira, New York

Segment	Active?	Construction	Extent and Orientation Investigation Complete	Condition / Existence of Laterals	Surface Access Points	Fine-Grained Material Characterized	Notes
7 (Former Industrial west of CB-39)	No	50-inch clay tile	Yes. This segment was identified during IRM #5 excavation. Camera survey was completed to the west (2021). A vault was encountered approximately 25 feet to the west. Camera survey was completed to the north.	Approximately 25 feet of the sewer was camera surveyed to west terminating at vault. From the vault, approximately 21 feet was camera surveyed to the north. Survey was terminated due to fine-grained material and observations of bentonite.	Manhole CB-39 east of SE corner of FFC.	No. Camera survey was conducted as part of IRM #5 FIS removal. Segment 7 was removed within the FFC boundary.	Sewer line extends north onto the Northern Athletic Fields and was exposed and removed during IRM #5A2.
8 (Former Industrial south of CB-39)	No	50-inch clay tile	Yes. This segment was identified during IRM #5 excavation. Camera survey was completed to the south and to the west (2021). A vault was encountered approximately 25 feet to the west. Camera survey was completed to the north.	Approximately 346 feet of the sewer was camera surveyed to the south to a manhole (CB-40).	Manhole MH-40 east of SE corner of FFC. Manhole MH-40 located under the IRM #5 haul road and not accessible.	No. Camera survey was conducted as part of IRM #5 FIS removal.	Segment 8 remains in place.

DRAFT

TABLE 2-7
Catch Basin Inspection Summary

Former Sperry Remington – North Portion #c808022
Elmira, New York

Catch Basin ID	Construction Material	Depth to Bottom (ft bgs)	Date Inspected	Fine-Grained Material Thickness Observed in 2019 (ft)	Date Sampled	Number of Laterals Observed	Comments
CB-06	Concrete	13.2	6/25/2019	0	5/28/2015	4	One 14", two 12", one 36" lateral
CB-07	Concrete	4.3	6/25/2019	0	5/28/2015	1	One 10" lateral
CB-09	Concrete	12	6/24/2019	0	5/28/2015	4	One 36", one 28", one 24", one 16" lateral
CB-11	Concrete	12.5	5/15/2019	1-1.5	5/15/2019	3	Two 18" laterals, one 12" lateral
CB-12	Concrete	9.5	5/15/2019	0	NA	3	Two 16" laterals, one 12" lateral
CB-13	Concrete	7.5	5/15/2019	0.15-0.25	6/25/2019	3	Two 12" laterals, one 14" lateral
CB-20	Concrete	5	6/24/2019	1	6/24/2019	1	14" lateral
CB-25	Concrete	5	6/24/2019	0.75	6/24/2019	1	One 12" lateral
CB-26	Concrete	6.75	6/25/2019	0.3	6/25/2019	2	Two 12" laterals. 4" standing water
CB-27	Concrete	8	6/25/2019	0.25	6/25/2019	3	Three 12" laterals
CB-28	Concrete and Brick/mortar	6.5	6/25/2019	1	6/25/2019	Unk	Could not identify tie-in. Likely covered with sediment. Concrete bottom, brick walls, no lid
CB-29	Concrete	9	6/25/2019	0	NA	2	Two 12" laterals
CB-30	Concrete	11.3	6/25/2019	0	NA	2	One 12", one 14" lateral
CB-31	Concrete	5	6/25/2019	0.15-0.25	6/25/2019	1	One 12" lateral
CB-32	Concrete	5	6/24/2019	0.8	6/24/2019	2	One 3" lateral, one 12" lateral
CB-33	Concrete	4.8	6/24/2019	1	6/24/2019	2	Two 12" laterals
CB-34	Concrete	6	5/15/2019	>0.25	5/15/2019	3	Three 12" laterals, 3" standing water
CB-35	Concrete	5	5/15/2019	0.25	6/24/2019	2	Two 12" laterals
CB-36	Concrete	4	6/24/2019	1-1.5	6/24/2019	1	One 12" lateral
CB-37	Concrete	4.5	6/24/2019	0.5-1	6/24/2019	1	One 12" lateral, Inlet half filled with sediment
CB-38	Concrete	7.8	5/15/2019	>0.25	5/15/2019	2	Two 12" laterals. Approx 12" standing water
MH-1	Concrete	9	5/13/2019	>0.25	5/14/2019	2	Two 12" laterals
MH-2	Concrete and Brick/mortar	6.4	12/21/2019	0	11/7/2019	3	Two 12" laterals, one 16" lateral

DRAFT

TABLE 3-1
Summary of IRMs Performed

Former Sperry Remington – North Portion #c808022
Elmira, New York

IRM	Work Plan Submittal	Work Plan Approval	Start	Finish	Soil Removed (CY)	Hazardous Waste (Tons)	Non-Hazardous Waste (Tons)
IRM #1	7/11/2017	8/10/2017	6/19/2017	9/8/2017	6,805	1,350	2,580
IRM #2	7/13/2018	7/25/2018	6/22/2018	10/25/2018	16,050	12,951	16,507
IRM #3	6/18/2019	6/13/2019	6/28/2019	10/14/2019	11,545	8,250	3,268
IRM #4	5/19/2020	5/28/2020	6/1/2020	8/28/2020	6,500	4,079	3,977
IRM #4A	9/8/2020	9/18/2020	9/21/2020	3/9/2021	59,260	38,000	49,000
IRM #5	11/24/2020	12/4/2020	12/15/2020	4/5/2022			
IRM #5A3	6/10/2022	7/1/2022	7/26/2022	9/3/2022			
IRM #5A2	10/8/2021	10/22/2021	10/22/2021	7/31/2024	111,600	25,000	180,000
NAF Restoration	--	--	--	7/31/2024	10,000	--	5,000

Notes:
CF = cubic yards; IRM = Interim Remedial Measure; NAF = Northern Athletic Fields.

DRAFT

TABLE 3-2
Summary of IRM Action Levels

Former Sperry Remington – North Portion #c808022
Elmira, New York

IRM	Depth (ft bgs)	Interim Remedial Measure (IRM) Action Level[1]					Groundwater
		PCBs	Metals	SVOCs	VOCs	TPHs	All COPCs (excluding TPHs)
IRM #1	0-2	>1 m/kg	N/A				N/A
	2-14	>10 mg/kg[6]					
	>14[9]	>3.2 mg/kg					
IRM #2	0-2	>1 m/kg	N/A				N/A
	2-14	>10 mg/kg[6]					
	>14[9]	N/A					
IRM #3	0-2	Restricted Residential[2]				N/A	N/A
	2-14	>10 mg/kg[6]	>20 x TCLP (>200 x TCLP for Lead)[7]	N/A			
	>14[9]	>3.2 mg/kg					
IRM #4 / IRM #4A	0-2	Restricted Residential[2]				N/A	N/A
	2-14	>10 mg/kg[6]	>20 x TCLP (>200 x TCLP for Lead)[7]	N/A			
	>14[9]	>3.2 mg/kg					
IRM #5 / IRM #5A1 / IRM #5A3	0-2	Restricted Residential[2]				> 100 mg/kg[4]	NYSDEC TOGs[5]
	2-14	>10 mg/kg[6]	>20 x TCLP (>200 x TCLP for Lead)[7]	Total PAHs > 100 mg/kg[8]	Restricted Residential[2]	N/A	
	>14[9]	Protection of Groundwater [3]					
IRM #5A2	0-2	Restricted Residential[2]				> 100 mg/kg[4]	NYSDEC TOGs[5]
	2-14	>10 mg/kg[6]	>20 x TCLP (>200 x TCLP for Lead)[7]	Total PAHs > 100 mg/kg[8]	Restricted Residential[2]	N/A	
	>14[9]	Protection of Groundwater [3]					

Notes:
ft bgs - feet below ground surface
VOCs - volatile organic compounds
SVOCs - semivolatile organic compounds
PCBs - polychlorinated biphenyls
TCLP - toxicity characteristic leaching procedure
TPHs - total petroleum hydrocarbons-diesel range organics
PAHs - total polyaromatic hydrocarbons
N/A - no standard applied for this depth and/or constituent

(1) Per CP-51/Soil Cleanup Guidance, Section V.F.2. "The exceedance of one or more applicable SCOs or SSCOs, (which is the lower of protection of public health, protection of groundwater, or protection of ecological resources soil cleanup objectives as described in Section III below), alone does not trigger the need for remedial action, define "unacceptable" levels of contaminant in soil, or indicates that a stie qualifies for any DEC remedial program (e.g., BCP, SSF). As noted in the definition of SCO above, SCOs and SSCOs are applicable statewide and do not account for many site-specific considerations which could potentially results in higher levels. Therefore, soil concentrations that are higher than the applicable SCOs or SSCOs are not necessarily health or environmental concerns."
(2) Restricted Residential - per 6 NYCRR Part 375 Table 375-6.8(b): Restricted Use Soil Cleanup Objectives
(3) Protection of Groundwater - per 6 NYCRR Part 375 Table 375-6.8(b): Protection of Groundwater Cleanup Objectives
(4) Nuisance criteria established for the project
(5) NYSDEC TOGS - New York State Groundwater Effluent Limitations Class (GA) (per Section 6 CRR-NY 703.6)
(6) CP-51/Soil Cleanup Guidance, Section V.I.2
(7) Remedial Action Objective to remove potential sources, i.e. concentrations that are indicative of potential hazardous waste
(8) An action level for total PAHs is proposed in lieu of individual PAH SCOs. Per 6 NYCRR Part 375 Table 375-6.8(b), SCOs for restricted residential use are capped at 100 mg/kg
(9) Depth to water was measured at 16.1 ft bgs at monitoring well MW-15S in September 2016

DRAFT

TABLE 4-1
Groundwater Elevation Measurements

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well ID	September 2023 Sitewide Gauging Event				April 2024 Sitewide Gauging Event			
	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)
MW-1	16.76	17.94	853.34	836.58	17.00	17.99	853.34	836.34
MW-2	16.94	23.10	852.86	835.92	16.71	23.13	852.86	836.15
MW-3	16.81	21.51	852.76	835.95	16.64	21.61	852.76	836.12
MW-4	NM**	NM**	846.12	NM**	NM**	NM**	846.12	NM**
MW-5I	2.19	17.02	839.96	837.77	2.08	17.00	839.96	837.88
MW-5S	4.67	13.60	842.49	837.82	4.59	13.60	842.49	837.90
MW-8I	14.83	44.91	853.88	839.05	15.73	44.45	853.88	838.15
MW-8S	14.76	18.22	853.93	839.17	14.68	18.20	853.93	839.25
MW-9I	14.80	42.98	853.65	838.85	14.65	42.90	853.65	839.00
MW-9S	14.89	20.28	854.03	839.14	14.73	20.25	854.03	839.30
MW-10	15.23	22.06	854.07	838.84	15.06	22.06	854.07	839.01
MW-11S	NM**	NM**	855.14	NM**	NM**	NM**	855.14	NM**
MW-11D	18.15	78.30	854.80	836.65	NM	NM	854.80	NM
MW-12	15.36	19.37	855.13	839.77	15.29	19.30	855.13	840.07
MW-13	NM*	15.82	854.94	NM*	NM*	14.99	854.94	NM*
MW-17	NM**	NM**	852.65	NM**	NM**	NM**	852.65	NM**
MW-20	14.34	18.47	852.29	837.95	14.14	18.48	852.29	838.15
MW-22	9.63	13.55	846.18	836.55	9.49	13.94	846.18	836.69
MW-26	9.26	14.88	843.69	834.43	8.45	15.00	843.69	835.24
MW-30	11.12	16.10	853.53	842.41	14.23	15.97	853.53	839.30
MW-32	NM*	13.85	852.89	NM*	15.03	18.81	852.89	837.86
MW-33	NM***	NM***	853.89	NM***	14.91	19.43	853.89	838.98
MW-34	NM**	NM**	853.69	NM**	NM**	NM**	853.69	NM**
MW-41	20.33	27.31	858.90	838.57	20.17	27.32	859.28	839.11
MW-43	12.71	19.94	851.81	839.10	12.60	19.90	851.81	839.21
MW-47	14.17	27.67	855.13	840.96	14.01	27.70	855.13	841.12
MW-47I	14.00	37.45	855.03	841.03	13.87	37.50	855.03	841.16
MW-48R	13.17	26.42	853.50	840.33	13.12	26.30	852.68	840.01
MW-50R	17.40	27.17	857.67	840.27	16.28	25.70	856.20	839.92
MW-51	13.55	24.26	853.93	840.38	12.79	24.80	852.67	839.88
MW-53	13.80	24.58	854.14	840.34	--	--	--	--
MW-54R	17.95	24.45	858.37	840.42	16.58	25.85	856.83	840.25
MW-55	17.00	29.82	858.13	841.13	15.76	28.50	856.33	840.57
MW-56	15.07	28.12	856.01	840.94	13.85	26.63	854.16	840.31
MW-57R	13.32	22.02	853.67	840.35	12.55	22.82	852.41	839.86
MW-58	15.38	25.04	855.76	840.38	14.07	22.95	853.27	839.20

DRAFT

TABLE 4-1
Groundwater Elevation Measurements

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well ID	September 2023 Sitewide Gauging Event				April 2024 Sitewide Gauging Event			
	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)
MW-59IR	16.69	32.92	857.50	840.81	15.53	24.00	856.05	840.52
MW-59SR	16.41	24.96	857.31	840.90	15.49	31.60	856.09	840.60
MW-60IR	15.71	33.29	856.69	840.98	15.14	32.60	855.90	840.76
MW-60SR	15.67	23.11	856.67	841.00	15.25	22.57	856.08	840.83
MW-62R	18.48	30.13	859.46	840.98	17.20	28.70	857.94	840.74
MW-63I	17.51	29.55	858.67	841.16	15.53	28.42	856.54	841.01
MW-63S	17.30	21.52	857.89	840.59	15.73	19.79	856.35	840.62
MW-64I	15.20	35.68	856.81	841.61	15.33	35.74	856.81	841.48
MW-64S	15.15	21.12	856.80	841.65	15.34	21.20	856.80	841.46
MW-65R	16.61	30.31	857.64	841.03	15.55	29.19	856.47	840.92
MW-66I	15.11	40.59	856.74	841.63	15.26	40.65	856.74	841.48
MW-66S	14.99	27.58	856.76	841.77	15.16	27.60	856.76	841.60
MW-67I	16.60	44.19	855.46	838.86	16.46	44.19	855.46	839.00
MW-67S	16.31	24.81	855.19	838.88	16.19	24.83	855.19	839.00
MW-68S	15.93	27.69	854.59	838.66	15.75	27.60	854.59	838.84
MW-69I	20.84	64.60	859.21	838.37	20.66	64.61	859.21	838.55
MW-70I	8.40	40.41	847.63	839.23	8.32	40.42	847.63	839.31
MW-70S	8.82	24.77	848.08	839.26	8.78	24.76	848.08	839.30
MW-71I	14.94	49.70	854.42	839.48	14.84	49.70	854.42	839.58
MW-71S	15.06	25.63	854.57	839.51	14.94	25.60	854.57	839.63
MW-72I	9.78	41.31	849.01	839.23	8.93	41.35	849.01	840.08
MW-72S	9.98	23.40	849.19	839.21	9.75	23.45	849.19	839.44
MW-73I	12.49	38.50	852.04	839.55	12.24	38.48	852.04	839.80
MW-73S	12.52	22.88	852.12	839.60	12.12	22.90	852.12	840.00
MW-74I	13.71	48.72	854.13	840.42	13.33	48.78	854.13	840.80
MW-74S	13.66	30.36	854.15	840.49	13.22	24.95	854.15	840.93
MW-75I	13.57	35.90	854.81	841.24	13.62	36.00	854.81	841.19
MW-75S	13.04	21.62	854.30	841.26	12.99	21.70	854.30	841.31
MW-76I	14.97	30.89	856.00	841.03	14.91	24.15	856.00	841.09
MW-76S	14.94	24.11	856.05	841.11	14.96	30.90	856.05	841.09
MW-77I	11.84	30.67	853.59	841.75	11.90	30.75	853.59	841.69
MW-77S	11.59	22.57	853.45	841.86	11.65	22.64	853.45	841.80
MW-78I	14.05	45.48	855.54	841.49	14.22	45.52	855.54	841.32
MW-78S	13.93	24.72	855.44	841.51	14.10	24.80	855.44	841.34
MW-79I	14.66	33.26	855.72	841.06	14.72	33.35	855.72	841.00
MW-79S	14.98	24.59	856.01	841.03	15.02	24.65	856.01	840.99

DRAFT

TABLE 4-1
Groundwater Elevation Measurements

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well ID	September 2023 Sitewide Gauging Event				April 2024 Sitewide Gauging Event			
	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)
MW-81I	15.55	46.88	853.60	838.05	13.44	45.83	853.60	840.16
MW-82S	13.19	26.97	852.05	838.86	13.15	26.97	852.05	838.90
MW-83I	13.91	33.77	854.77	840.86	13.60	33.80	854.77	841.17
MW-83S	13.66	23.54	854.71	841.05	13.40	23.60	854.71	841.31
MW-84S	14.75	25.26	855.54	840.79	14.72	25.27	855.54	840.82
MW-85I	15.36	41.78	855.12	839.76	15.25	41.63	855.12	839.87
MW-86I	14.79	44.90	853.56	838.77	14.59	44.75	853.56	838.97
MW-87I	15.76	30.36	855.02	839.26	15.68	39.87	855.02	839.34
MW-88I	16.00	44.90	855.33	839.33	15.94	44.90	855.33	839.39
MW-88S	15.76	23.80	855.15	839.39	15.74	23.80	855.15	839.41
MW-89I	15.28	48.15	854.77	839.49	15.20	47.70	854.77	839.57
MW-89S	14.99	23.67	855.00	840.01	14.90	23.68	855.00	840.10
MW-90I	14.82	26.25	855.39	840.57	14.53	43.10	855.39	840.86
MW-90S	14.84	43.12	855.38	840.54	14.57	26.25	855.38	840.81
MW-91I	13.78	45.92	853.53	839.75	13.36	45.95	853.53	840.17
MW-91S	13.81	25.23	853.56	839.75	13.39	25.22	853.56	840.17
MW-92I	14.41	35.31	855.38	840.97	14.43	35.33	855.38	840.95
MW-92S	14.35	24.46	855.34	840.99	14.35	24.46	855.34	840.99
MW-93I	14.11	37.38	854.97	840.86	14.06	37.13	854.97	840.91
MW-93S	14.41	23.43	855.28	840.87	14.34	23.43	855.28	840.94
MW-94I	11.79	36.38	852.93	841.14	11.69	36.38	852.93	841.24
MW-94S	11.45	21.15	852.74	841.29	11.31	21.18	852.74	841.43
MW-95I	11.06	NM	850.74	839.68	11.34	28.64	850.74	839.40
MW-95S	11.02	NM	850.72	839.70	11.37	24.11	850.72	839.35
MW-96	23.94	34.63	864.27	840.33	24.26	39.65	864.27	840.01
MW-97	23.76	35.55	863.29	839.53	24.10	35.53	863.29	839.19
MW-98I	15.06	34.90	852.85	837.79	15.01	34.90	852.85	837.84
MW-98S	15.38	27.12	853.21	837.83	15.35	27.16	853.21	837.86
MW-99I	15.66	45.79	853.48	837.82	15.54	45.77	853.48	837.94
MW-99S	15.52	24.48	853.38	837.86	15.39	24.49	853.38	837.99
MW-100I	14.50	33.16	854.57	840.07	12.05	30.20	851.64	839.59
MW-100S	14.07	22.88	854.29	840.22	12.15	19.65	851.84	839.69
MW-101I	9.51	28.53	848.02	838.51	9.36	28.53	848.02	838.66
MW-101S	4.73	12.91	843.23	838.50	4.64	12.98	843.23	838.59
MW-102I	15.95	47.28	854.73	838.78	15.84	47.28	854.73	838.89
MW-102S	15.99	24.73	854.77	838.78	15.89	24.77	854.77	838.88

DRAFT

TABLE 4-1
Groundwater Elevation Measurements

Former Sperry Remington – North Portion #c808022
Elmira, New York

Well ID	September 2023 Sitewide Gauging Event				April 2024 Sitewide Gauging Event			
	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)	Depth to Water (ft TOC)	Total Depth (ft TOC)	TOC Elevation (ft MSL)	GW Elevation (ft MSL)
MW-103I	14.82	38.48	855.27	840.45	14.75	38.47	855.27	840.52
MW-103S	14.42	24.99	854.99	840.57	14.40	24.95	854.99	840.59
MW-104I	14.55	39.94	855.22	840.67	14.52	40.03	855.22	840.70
MW-104S	14.30	22.98	854.96	840.66	14.25	22.95	854.96	840.71
MW-105I	14.06	26.56	854.65	840.59	13.98	36.66	854.65	840.67
MW-105S	14.19	22.40	854.72	840.53	14.09	22.30	854.72	840.63
MW-106	13.81	26.39	854.21	840.40	12.65	24.78	852.54	839.89

Notes:
ft TOC = feet below top of casing; ft msl = feet above mean sea level; NM = not measured;
* = well observed to be dry; ** = well observed to be damaged; *** = well unable to be located;
-- = well abandoned.
Elevations in North American Vertical Datum of 1988.
TOC elevations at some wells varies between September 2023 and April 2024 due to well modifications and subsequent resurveying completed between the two monitoring events.
September 2023 gauging event completed on 11 September 2023
April 2024 gauging event completed on 1 April 2024

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
							ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix A				
						1 ug/m3 and above - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** 0.2 to <1 ug/m3 and sub-slab vapor <6 ug/m3- Matrix Outcome = NFA <0.2 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor <60 ug/m3- Matrix Outcome = NFA				
						Sub-Slab Vapor Concentration Associated with Location				
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report					
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	<6	0.04635	--	ND	ND
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	<6	0.15446	--	ND	ND
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	6 to <60	ND	--	ND	ND
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	<6	ND	--	ND	ND
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	<6	0.3	--	< 0.098	< 0.098
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	<6	< 0.098	--	< 0.098	< 0.098
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	<6	< 1	--	< 1	< 1
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	>60	< 1	--	< 1	< 1
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	6 to <60	< 1	--	< 1	< 1
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	<6	< 1	--	< 1	< 1
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	>60	< 1	--	< 1	< 1
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	<6	< 1	--	< 1	< 1
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	>60	< 1	--	< 1	< 1
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	>60	< 1	--	--	--
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	<6	< 1	--	--	--
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	<6	0.33	0.38	0.97	< 0.6
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	>60	0.22	0.32	< 0.6	< 0.6
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	<6	0.49	0.38	1	< 0.6
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	>60	1	0.38	< 0.6	< 0.6
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	>60	1.4	0.45	1.1	< 0.6
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	>60	2.4	0.32	0.69	< 0.6
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	<6	0.27	0.38	0.6	< 0.6
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	<6	0.44	0.38	1	< 0.6
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.17 U	0.63	< 0.063 U	< 0.13 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	0.44	0.41	< 0.063 U	< 0.13 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	>60	1.9	0.66	< 0.063 U	0.25

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
							ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix A				
						1 ug/m3 and above - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** 0.2 to <1 ug/m3 and sub-slab vapor <6 ug/m3- Matrix Outcome = NFA <0.2 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor <60 ug/m3- Matrix Outcome = NFA				
						Sub-Slab Vapor Concentration Associated with Location				
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report					
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	>60	0.51	0.62	< 0.064 U	< 0.13 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	>60	0.28	0.38	< 0.061 U	< 0.12 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	>60	0.18	0.39	< 0.063 U	< 0.13 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.17 U	0.40	< 0.063 U	< 0.12 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	0.17	0.39	< 0.064 U	< 0.13 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.17 U	0.40	< 0.063 U	< 0.13 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.17 U	0.38	< 0.062 U	< 0.12 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	6 to <60	< 0.17 U	0.38	< 0.063 U	< 0.12 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.18 U	0.38	< 0.065 U	< 0.13 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	6 to <60	< 0.17 U	0.36	< 0.064 U	< 0.13 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.17 U	0.39	< 0.062 U	< 0.12 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	0.19	0.39	< 0.064 U	< 0.13 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	>60	1.9	0.35	< 0.063 U	0.24
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	6 to <60	< 0.16 U	0.39	< 0.059 U	< 0.12 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	6 to <60	< 0.16 U	0.41	< 0.061 U	< 0.12 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.42	< 0.062 U	< 0.12 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.39	< 0.062 U	< 0.12 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.41	< 0.063 U	< 0.12 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.39	< 0.062 U	< 0.12 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.40	< 0.063 U	< 0.13 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.40	< 0.063 U	< 0.12 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	0.67	0.39	< 0.061 U	< 0.12 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.35	< 0.064 U	< 0.13 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.17 U	0.40	< 0.063 U	< 0.13 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	6 to <60	< 2.7 U	< 3.1 U	< 2 U	< 2 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.17 U	0.47	< 0.062 U	< 0.12 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
							ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix A				
						1 ug/m3 and above - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** 0.2 to <1 ug/m3 and sub-slab vapor <6 ug/m3- Matrix Outcome = NFA <0.2 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor <60 ug/m3- Matrix Outcome = NFA				
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report	Sub-Slab Vapor Concentration Associated with Location				
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.17 U	0.43	< 0.064 U	< 0.13 U
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.17 U	0.45	< 0.061 U	< 0.12 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	6 to <60	< 0.16 U	0.40	< 0.061 U	< 0.12 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	<6	0.77	0.45	< 0.059 U	1.6
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.16 U	0.39	< 0.061 U	< 0.12 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.17 U	0.48	< 0.063 U	< 0.12 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	>60	< 0.17 U	0.38	< 0.064 U	< 0.13 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.18 U	0.42	< 0.067 U	< 0.13 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.17 U	0.43	< 0.063 U	< 0.12 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	<6	0.48	0.34	< 0.062 U	< 0.12 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	<6	< 0.18 U	0.49	< 0.065 U	< 0.13 U
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	>60	0.23	0.38	< 0.061 U	< 0.12 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	<6	< 0.16 U	0.57	< 0.059 U	< 0.12 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.16 U	0.46	< 0.060 U	< 0.12 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.17 U	0.5	< 0.062 U	< 0.12 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.16 U	0.49	< 0.061 U	< 0.12 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.16 U	0.42	< 0.060 U	< 0.12 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.18 U	0.35	< 0.065 U	< 0.13 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	<6	0.26	0.49	< 0.059 U	< 0.12 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.17 U	0.48	< 0.063 U	< 0.12 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.18 U	0.37	< 0.067 U	< 0.13 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.16 U	0.44	< 0.060 U	< 0.12 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.16 U	0.50	< 0.058 U	< 0.12 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<6	0.16	0.50	< 0.059 U	0.15
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	>60	0.37	0.62	< 0.059 U	< 0.12 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.16 U	0.50	< 0.061 U	< 0.12 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
							ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix A				
						1 ug/m3 and above - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** 0.2 to <1 ug/m3and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** 0.2 to <1 ug/m3 and sub-slab vapor <6 ug/m3- Matrix Outcome = NFA <0.2 ug/m3 and sub-slab vapor >60 ug/m3 - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor <60 ug/m3- Matrix Outcome = NFA				
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report	Sub-Slab Vapor Concentration Associated with Location				
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.30 U	< 0.35 U	< 0.11 U	< 0.22 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	>60	< 0.16 U	0.48	< 0.059 U	< 0.12 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.16 U	0.39	< 0.059 U	< 0.12 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.17 U	0.44	< 0.062 U	< 0.12 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.17 U	0.42	< 0.062 U	< 0.12 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.16 U	0.38	< 0.061 U	< 0.12 U
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.16 U	0.49	< 0.061 U	< 0.12 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.16 U	0.50	< 0.060 U	< 0.12 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.17 U	0.36	< 0.062 U	< 0.12 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	6 to <60	< 0.17 U	0.46	< 0.063 U	< 0.12 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.17 U	0.40	< 0.063 U	< 0.12 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.17 U	0.48	< 0.062 U	< 0.12 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	>60	< 0.17 U	0.45	< 0.062 U	< 0.12 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	>60	< 0.17 U	0.47	< 0.061 U	< 0.12 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix B			
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 100 to <1,000 ug/m3 - Matrix Outcome = **Monitor** 3 to <10 ug/m3 and sub-slab vapor <100 ug/m3 - Matrix Outcome = NFA <3 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** <3 ug/m3 and sub-slab vapor <1,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	<100	ND	3.56989	ND
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	<100	ND	0.10851	0.0359
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	<100	ND	0.1776	0.0108
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	<100	ND	ND	ND
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	<100	--	0.2	0.2
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	<100	--	0.1	< 0.1
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	<100	1	1.5	< 1
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	>1000	< 1	1.5	1
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	<100	< 1	< 1.5	1
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	<100	1	< 1.5	1
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	<100	1	1.5	1
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	<100	1	1.5	2.1
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	<100	1	1.5	1
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	<100	--	1.5	1.8
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	<100	--	< 1.5	1
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	<100	< 0.53	< 1	< 0.83
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	>1000	< 0.53	< 1	2.4
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	<100	< 0.53	< 1	< 0.83
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<100	< 0.53	< 1	< 0.83
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<100	< 0.53	0.69	< 0.83
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	<100	< 0.53	< 1	< 0.83
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	<100	< 0.53	< 1	< 0.83
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	<100	< 0.53	0.76	< 0.83
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.17 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.17 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.17 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix B			
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 100 to <1,000 ug/m3 - Matrix Outcome = **Monitor** 3 to <10 ug/m3 and sub-slab vapor <100 ug/m3 - Matrix Outcome = NFA <3 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** <3 ug/m3 and sub-slab vapor <1,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.18 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.17 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.18 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.17 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.18 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.18 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	1.6	< 0.21 U	< 0.17 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<100	< 1.1 U	< 0.22 U	< 0.18 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.0 U	< 0.20 U	< 0.16 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.22 U	< 0.17 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.21 U	< 0.17 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.22 U	< 0.18 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<100	< 1.1 U	< 0.22 U	< 0.17 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	<100	< 17 U	< 3.4 U	< 2.7 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	<100	1.1	0.21	< 0.17 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix B			
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 100 to <1,000 ug/m3 - Matrix Outcome = **Monitor** 3 to <10 ug/m3 and sub-slab vapor <100 ug/m3 - Matrix Outcome = NFA <3 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** <3 ug/m3 and sub-slab vapor <1,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	<100	1.2	0.29	0.59
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.1 U	0.65	< 0.17 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	<100	1.2	1.9	< 0.16 U
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	<100	1.6	0.58	< 0.17 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	<100	< 1.1 U	0.32	< 0.17 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.1 U	< 0.22 U	< 0.18 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.2 U	< 0.23 U	< 0.18 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	<100	< 1.1 U	< 0.22 U	< 0.18 U
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	<100	< 1.0 U	0.33	< 0.16 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	<100	< 1.0 U	0.25	< 0.16 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.1 U	0.22	< 0.17 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	<100	< 1.0 U	0.26	< 0.16 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	<100	< 1.1 U	< 0.22 U	< 0.18 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.0 U	< 0.20 U	< 0.16 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.1 U	0.26	< 0.17 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.2 U	< 0.23 U	< 0.18 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.0 U	< 0.20 U	< 0.16 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.0 U	< 0.20 U	< 0.16 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.0 U	< 0.20 U	< 0.16 U
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	<100	8.6	< 0.20 U	< 0.16 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.1 U	< 0.21 U	< 0.17 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix B			
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 3 to <10 ug/m3 and sub-slab vapor 100 to <1,000 ug/m3 - Matrix Outcome = **Monitor** 3 to <10 ug/m3 and sub-slab vapor <100 ug/m3 - Matrix Outcome = NFA <3 ug/m3 and sub-slab vapor 1,000 ug/m3 and above - Matrix Outcome = **Mitigate** <3 ug/m3 and sub-slab vapor <1,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	<100	2.4	< 0.38 U	< 0.31 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.0 U	< 0.20 U	< 0.16 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.0 U	< 0.20 U	< 0.16 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.1 U	< 0.21 U	0.27
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.0 U	< 0.21 U	< 0.16 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<100	< 1.1 U	< 0.21 U	< 0.17 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<100	< 1.1 U	< 0.21 U	< 0.17 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Vinyl Chloride
							ug/m3
NYSDDOH Matrix						Matrix C	
						0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 60 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** <0.2 ug/m3 and sub-slab vapor <6 ug/m3 - Matrix Outcome = NFA		
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	<6	ND
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	<6	ND
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	<6	ND
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	<6	ND
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	<6	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	<6	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	<6	--
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	<6	--
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	<6	--
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	<6	--
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	<6	--
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	<6	--
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	<6	--
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	<6	--
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	<6	--
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	<6	< 0.1
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	<6	< 0.1
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Vinyl Chloride
							ug/m3
NYSDDOH Matrix						Matrix C	
						0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 60 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** <0.2 ug/m3 and sub-slab vapor <6 ug/m3 - Matrix Outcome = NFA		
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.039 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.040 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.040 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.040 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.042 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.040 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<6	< 0.041 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	<6	< 0.040 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.038 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.039 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.040 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.040 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.040 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.040 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.041 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.040 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.039 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.041 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<6	< 0.041 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	<6	< 1.3 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.040 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Vinyl Chloride
							ug/m3
NYSDDOH Matrix						Matrix C	
						0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 60 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** <0.2 ug/m3 and sub-slab vapor <6 ug/m3 - Matrix Outcome = NFA	
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.041 U
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.04 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.039 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.038 U
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.039 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.040 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.041 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.043 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.040 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.04 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	<6	< 0.042 U
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.04 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	<6	< 0.038 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.039 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.04 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.039 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	<6	< 0.039 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	<6	< 0.042 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.038 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.040 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.043 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.038 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.037 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.038 U
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.038 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.039 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Vinyl Chloride
							ug/m3
NYSDDOH Matrix						Matrix C	
						0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 60 ug/m3 and above - Matrix Outcome = **Mitigate** <0.2 ug/m3 and sub-slab vapor 6 to <60 ug/m3 - Matrix Outcome = **Monitor** <0.2 ug/m3 and sub-slab vapor <6 ug/m3 - Matrix Outcome = NFA	
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.072 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.038 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.038 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.040 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.040 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.039 U
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.039 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.039 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.040 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.040 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	<6	< 0.040 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	<6	< 0.040 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<6	< 0.04 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<6	< 0.04 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
							ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix D							
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 60 to <600 ug/m3 - Matrix Outcome = **Monitor** 2 to <10 ug/m3 and sub-slab vapor <60 ug/m3 - Matrix Outcome = NFA <2 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** <2 ug/m3 and sub-slab vapor <600 ug/m3 - Matrix Outcome = NFA							
						Sub-Slab Vapor Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report								
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	<60	1.15173	--	0.38401	--	--	--	0.44527
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	<60	ND	--	0.5114	--	--	--	0.65444
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	<60	ND	--	0.6538	--	--	--	0.6012
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	<60	ND	--	10.36	--	--	--	7.51
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	<60	--	--	--	--	--	--	0.3
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	<60	--	--	--	--	--	--	0.8
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	<60	1.2	< 1	--	1	--	--	1
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	<60	1.1	< 1	--	1	--	--	1
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	<60	< 1	< 1	--	1	--	--	1
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	<60	1.2	< 1	--	1.1	--	--	1
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	<60	1.1	< 1	--	1	--	--	1
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	<60	1.4	< 1	--	1.5	--	--	1.1
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	<60	1.1	< 1	--	1	--	--	1
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	<60	--	--	--	9.4	1.7	--	1.2
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	<60	--	--	--	75	19	--	2.2
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	<60	0.49	< 0.52	< 0.66	0.55	< 0.75	< 0.71	< 0.66
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.42	< 0.52	< 0.66	< 0.75	< 0.75	< 0.71	< 0.66
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.42	< 0.52	< 0.66	< 0.75	< 0.75	< 0.71	< 0.66
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.45	< 0.52	< 0.66	1.1	< 0.75	< 0.71	< 0.66
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.58	< 0.52	< 0.66	1.8	< 0.75	< 0.71	< 0.66
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.42	< 0.52	< 0.66	< 0.75	< 0.75	< 0.71	< 0.66
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.65	1.5	< 0.66	1	< 0.75	< 0.71	< 0.66
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	<60	0.52	< 0.52	< 0.66	< 0.75	< 0.75	< 0.71	< 0.66
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	< 0.26 U	< 0.55 U	0.42	< 0.79 U	< 0.79 U	< 3.7 U	0.56
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.44	< 0.55 U	0.68	< 0.79 U	< 0.79 U	< 3.7 U	0.68
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.27	< 0.55 U	0.32	< 0.78 U	< 0.78 U	< 3.7 U	0.43

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
							ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix							Matrix D						
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 60 to <600 ug/m3 - Matrix Outcome = **Monitor** 2 to <10 ug/m3 and sub-slab vapor <60 ug/m3 - Matrix Outcome = NFA <2 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** <2 ug/m3 and sub-slab vapor <600 ug/m3 - Matrix Outcome = NFA							
						Sub-Slab Vapor Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report								
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	< 0.26 U	< 0.55 U	0.29	< 0.79 U	< 0.79 U	< 3.8 U	0.38
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.25	< 0.53 U	0.32	< 0.76 U	< 0.76 U	< 3.6 U	0.42
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	< 0.25 U	< 0.55 U	0.32	< 0.78 U	< 0.78 U	< 3.7 U	0.41
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	< 0.25 U	< 0.54 U	0.26	< 0.78 U	< 0.78 U	< 3.7 U	0.33
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.32	< 0.55 U	0.40	< 0.79 U	< 0.79 U	< 3.8 U	0.59
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.36	< 0.55 U	0.42	1.0	< 0.78 U	< 3.7 U	0.55
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.26	< 0.54 U	0.24	< 0.78 U	< 0.78 U	< 3.7 U	0.34
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	< 0.25 U	< 0.54 U	0.23	< 0.78 U	< 0.78 U	< 3.7 U	0.29
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	0.66	< 0.56 U	1.0	0.97	< 0.80 U	< 3.8 U	1.3
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	< 0.26 U	< 0.56 U	0.27	< 0.80 U	< 0.80 U	< 3.8 U	0.36
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	<60	1.5	1.4	3.1	1.6	< 0.77 U	< 3.7 U	4.0
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	60 to <600	0.40	< 0.56 U	0.50	0.96	< 0.80 U	< 3.8 U	0.64
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	<60	0.41	< 0.54 U	0.58	< 0.78 U	< 0.78 U	< 3.7 U	0.82
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.24 U	< 0.51 U	< 0.13 U	< 0.73 U	< 0.73 U	< 3.5 U	< 0.13 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	0.27	< 0.53 U	< 0.13 U	< 0.76 U	< 0.76 U	< 3.6 U	< 0.13 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.25 U	< 0.54 U	< 0.14 U	< 0.77 U	< 0.77 U	< 3.7 U	< 0.14 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.25 U	< 0.54 U	< 0.14 U	< 0.77 U	< 0.77 U	< 3.6 U	< 0.14 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.25 U	< 0.54 U	< 0.14 U	< 0.78 U	< 0.78 U	< 3.7 U	0.14
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.25 U	< 0.54 U	0.14	< 0.77 U	< 0.77 U	< 3.6 U	0.17
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.25 U	< 0.55 U	< 0.14 U	< 0.78 U	< 0.78 U	< 3.7 U	< 0.14 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.25 U	< 0.54 U	< 0.14 U	< 0.78 U	< 0.78 U	< 3.7 U	< 0.14 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	0.94	< 0.53 U	1.4	3.4	1.2	< 3.6 U	2.2
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	< 0.26 U	< 0.56 U	< 0.14 U	< 0.80 U	< 0.80 U	< 3.8 U	< 0.14 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<60	0.28	< 0.55 U	0.14	< 0.79 U	< 0.79 U	< 3.7 U	0.18
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	<60	< 1.6 U	< 1.7 U	< 2.2 U	< 2.4 U	< 2.4 U	< 2.3 U	< 2.2 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	<60	0.47	0.62	0.38	< 0.77 U	< 0.77 U	< 3.7 U	0.47

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
							ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix D							
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 60 to <600 ug/m3 - Matrix Outcome = **Monitor** 2 to <10 ug/m3 and sub-slab vapor <60 ug/m3 - Matrix Outcome = NFA <2 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** <2 ug/m3 and sub-slab vapor <600 ug/m3 - Matrix Outcome = NFA							
						Sub-Slab Vapor Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report								
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	<60	2.5	0.73	1.6	2.7	< 0.80 U	< 3.8 U	2.2
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	<60	0.31	< 0.53 U	0.18	< 0.76 U	< 0.76 U	< 3.6 U	0.22
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	<60	0.37	< 0.53 U	0.21	< 0.75 U	< 0.75 U	< 3.6 U	0.26
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	<60	0.52	0.52	3.4	1.5	< 0.73 U	< 3.4 U	5.2
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	<60	0.52	0.71	2.3	3.4	0.77	< 3.6 U	3.2
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	60 to <600	0.57	< 0.54 U	0.75	1.2	< 0.78 U	< 3.7 U	0.97
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	<60	0.3	< 0.55 U	0.17	< 0.79 U	< 0.79 U	< 3.8 U	0.22
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	<60	0.37	1	0.29	< 0.82 U	< 0.82 U	< 3.9 U	0.34
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	<60	0.50	1.6	0.45	< 0.78 U	< 0.78 U	< 3.7 U	0.60
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	<60	0.39	1.3	0.28	< 0.77 U	< 0.77 U	< 3.7 U	0.37
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	<60	2.9	1.1	1.4	1.6	< 0.81 U	< 3.8 U	1.7
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	<60	0.42	1.4	0.31	< 0.76 U	< 0.76 U	< 3.6 U	0.37
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	<60	0.33	< 0.51 U	0.15	< 0.73 U	< 0.73 U	< 3.4 U	0.27
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	60 to <600	0.60	< 0.52 U	0.70	1.0	< 0.75 U	< 3.6 U	0.92
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	<60	0.44	< 0.54 U	0.31	< 0.77 U	< 0.77 U	< 3.6 U	0.41
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	<60	0.94	< 0.53 U	0.70	0.97	< 0.75 U	< 3.6 U	0.88
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	<60	0.40	< 0.52 U	2.1	< 0.75 U	< 0.75 U	< 3.6 U	1.9
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	<60	0.44	4.3	0.6	< 0.81 U	< 0.81 U	< 3.8 U	0.61
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	<60	0.28	< 0.52 U	0.18	< 0.74 U	< 0.74 U	< 3.5 U	0.22
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	<60	0.26	< 0.54 U	< 0.14 U	< 0.78 U	< 0.78 U	< 3.7 U	< 0.14 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.35	< 0.58 U	< 0.15 U	< 0.83 U	< 0.83 U	< 3.9 U	0.18
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.36	< 0.52 U	0.13	< 0.74 U	< 0.74 U	< 3.5 U	0.16
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<60	0.27	< 0.50 U	< 0.13 U	< 0.72 U	< 0.72 U	< 3.4 U	0.14
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<60	0.30	< 0.51 U	0.15	< 0.73 U	< 0.73 U	< 3.5 U	0.19
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.62	2.4	1.6	2.0	< 0.74 U	4.4	2.3
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	<60	0.29	< 0.53 U	0.15	< 0.75 U	< 0.75 U	< 3.6 U	0.18

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
							ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix							Matrix D						
						10 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** 2 to <10 ug/m3 and sub-slab vapor 60 to <600 ug/m3 - Matrix Outcome = **Monitor** 2 to <10 ug/m3 and sub-slab vapor <60 ug/m3 - Matrix Outcome = NFA <2 ug/m3 and sub-slab vapor 600 ug/m3 and above - Matrix Outcome = **Mitigate** <2 ug/m3 and sub-slab vapor <600 ug/m3 - Matrix Outcome = NFA							
						Sub-Slab Vapor Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report								
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.50	1.2	1.4	3.5	< 1.4 U	< 6.6 U	2.4
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	<60	0.30	< 0.51 U	0.13	< 0.73 U	< 0.73 U	< 3.5 U	0.16
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.25	< 0.51 U	0.14	< 0.73 U	< 0.73 U	< 3.5 U	0.18
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	<60	< 0.25 U	< 0.54 U	< 0.14 U	< 0.77 U	< 0.77 U	< 3.6 U	< 0.14 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.26	< 0.54 U	< 0.14 U	< 0.77 U	< 0.77 U	< 3.6 U	0.16
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.48	< 0.53 U	0.27	0.73 J	< 0.75 U	< 3.6 U	0.37
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<60	0.27	< 0.53 U	< 0.13 U	< 0.75 U	< 0.75 U	< 3.6 U	0.13 J
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<60	0.26	< 0.52 U	0.20	< 0.75 U	< 0.75 U	< 3.6 U	0.30
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	<60	0.98	< 0.54 U	< 0.14 U	< 0.77 U	< 0.77 U	< 3.6 U	0.15
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	<60	< 0.25 U	< 0.54 U	0.21	< 0.78 U	< 0.78 U	< 3.7 U	0.24
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	60 to <600	< 0.25 U	< 0.54 U	0.15	< 0.78 U	< 0.78 U	< 3.7 U	0.24
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	<60	< 0.25 U	< 0.54 U	0.16	< 0.77 U	< 0.77 U	< 3.6 U	0.22
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<60	0.44	< 0.54 U	0.16	< 0.77 U	< 0.77 U	< 3.6 U	0.22
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<60	0.45	< 0.53 U	0.14	< 0.76 U	< 0.76 U	< 3.6 U	0.2

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							N-Heptane	m,p-Xylene	N-Hexane
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix E			
						20 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 200 to <2,000 ug/m3 - Matrix Outcome = **Monitor** 6 to <20 ug/m3 and sub-slab vapor <200 ug/m3 - Matrix Outcome = NFA <6 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and sub-slab vapor <2,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	<200	--	1.21712	--
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	<200	--	1.70774	--
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	<200	--	1.5614	--
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	<200	--	21.78	--
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	<200	--	0.8	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	<200	--	2.2	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	<200	< 1	1	< 1
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	<200	< 1	1	< 1
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	<200	1	1	1
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	<200	1.6	1	1
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	<200	1.2	1	1
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	<200	1.9	1.6	1.4
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	<200	1	1	1
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	<200	< 1	1.8	--
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	<200	1.1	1.5	--
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	<200	< 0.62	< 1.3	< 0.54
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	<200	< 0.62	< 1.3	< 0.54
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	<200	0.87	< 1.3	0.97
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<200	< 0.62	0.66	< 0.54
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<200	< 0.62	0.88	< 0.54
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	<200	6.4	< 1.3	< 0.54
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	<200	0.79	1	0.79
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	<200	0.67	0.79	< 0.54
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.66 U	1.6	< 0.56 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	0.98	2.1	< 0.56 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.65 U	1.2	< 0.56 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							N-Heptane	m,p-Xylene	N-Hexane
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix E			
						20 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 200 to <2,000 ug/m3 - Matrix Outcome = **Monitor** 6 to <20 ug/m3 and sub-slab vapor <200 ug/m3 - Matrix Outcome = NFA <6 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and sub-slab vapor <2,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.66 U	1.1	< 0.57 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.63 U	1.2	< 0.54 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.65 U	1.2	< 0.56 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.65 U	1.0	< 0.56 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.66 U	1.6	< 0.57 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	3.7	1.6	1.7
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.65 U	0.96	< 0.56 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.65 U	0.82	< 0.56 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	1.4	4.1	1.6
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	< 0.66 U	0.97	< 0.57 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	9.4	13	5.7
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<200	6.5	1.8	1.8
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	<200	2.3	2.4	< 0.56 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.61 U	0.30	< 0.52 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.63 U	0.34	< 0.54 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.64 U	< 0.27 U	< 0.55 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.64 U	< 0.27 U	< 0.55 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.65 U	0.36	< 0.56 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.64 U	0.41	< 0.55 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.65 U	< 0.28 U	< 0.56 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.65 U	< 0.27 U	< 0.56 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	1.3	6.4	2.5
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.66 U	< 0.28 U	< 0.57 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<200	< 0.66 U	1.4	< 0.56 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	<200	< 2 U	< 2.2 U	< 1.8 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	<200	1.1	1.3	< 0.55 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							N-Heptane	m,p-Xylene	N-Hexane
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix E			
						20 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 200 to <2,000 ug/m3 - Matrix Outcome = **Monitor** 6 to <20 ug/m3 and sub-slab vapor <200 ug/m3 - Matrix Outcome = NFA <6 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and sub-slab vapor <2,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	<200	1.9	6.1	4.3
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	<200	0.76	0.58	0.71
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	<200	< 0.63 U	0.70	< 0.54 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	<200	2.0	15	1.7
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	<200	1.4	9.2	1.6
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	200 to <2000	0.92	2.7	0.92
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	<200	0.92	0.58	< 0.57 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	<200	1.4	0.92	1.3
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	<200	1.8	1.6	0.59
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	<200	< 0.64 U	1	1.2
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	<200	2.3	5.0	5.2
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	<200	6.2	1	0.77
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	<200	< 0.61 U	0.51	< 0.52 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	200 to <2000	1.0	2.6	1.0
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	<200	< 0.64 U	1	0.82
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	<200	1.8	3.0	1.6
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	<200	1.4	7.5	0.96
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	<200	2.3	1.5	< 0.58 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	<200	< 0.61 U	0.64	< 0.53 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	<200	< 0.65 U	0.36	0.79
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	<200	< 0.69 U	0.39	< 0.60 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	<200	< 0.62 U	0.44	< 0.53 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<200	0.78	0.35	0.86
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<200	0.80	0.44	0.82
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	<200	1.6	5.0	0.78
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	<200	0.73	0.46	0.61

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							N-Heptane	m,p-Xylene	N-Hexane
							ug/m3	ug/m3	ug/m3
NYSDDOH Matrix						Matrix E			
						20 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <20 ug/m3 and sub-slab vapor 200 to <2,000 ug/m3 - Matrix Outcome = **Monitor** 6 to <20 ug/m3 and sub-slab vapor <200 ug/m3 - Matrix Outcome = NFA <6 ug/m3 and sub-slab vapor 2,000 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and sub-slab vapor <2,000 ug/m3 - Matrix Outcome = NFA			
						Sub-Slab Vapor Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report				
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	<200	2.3	4.7	1.7
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	<200	0.90	0.42	< 0.52 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	<200	< 0.61 U	0.49	< 0.52 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	<200	< 0.64 U	< 0.27 U	< 0.55 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	<200	< 0.64 U	0.45	< 0.55 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	<200	1.2	0.97	0.94
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<200	< 0.63 U	0.35	< 0.54 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<200	< 0.62 U	0.70	< 0.54 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	<200	< 0.64 U	0.42	1.3
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	<200	< 0.65 U	0.76	< 0.56 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	200 to <2000	< 0.65 U	0.58	< 0.56 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	<200	< 0.64 U	0.58	< 0.55 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<200	< 0.64 U	0.58	< 0.55 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<200	< 0.64 U	0.48	< 0.55 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Toluene
							ug/m3
NYSDDOH Matrix						Matrix F	
						50 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 300 to <3,000 ug/m3 - Matrix Outcome = **Monitor** 10 to <50 ug/m3 and sub-slab vapor <300 ug/m3 - Matrix Outcome = NFA <10 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** <10 ug/m3 and sub-slab vapor <3,000 ug/m3 - Matrix Outcome = NFA		
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	<300	4.22136
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	<300	3.53854
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	<300	6.0972
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	<300	111.77
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	<300	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	<300	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	<300	1.6
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	<300	1.6
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	<300	14
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	<300	2.8
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	<300	2.8
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	<300	5.9
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	<300	2.7
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	<300	6.4
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	<300	3.2
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	<300	1
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	<300	2.3
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	<300	1.3
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<300	8.8
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	<300	9.2
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	<300	6.6
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	<300	4.6
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	<300	2.1
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	5.3
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	5.6
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	2.3

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Toluene
							ug/m3
NYSDDOH Matrix						Matrix F	
						50 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 300 to <3,000 ug/m3 - Matrix Outcome = **Monitor** 10 to <50 ug/m3 and sub-slab vapor <300 ug/m3 - Matrix Outcome = NFA <10 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** <10 ug/m3 and sub-slab vapor <3,000 ug/m3 - Matrix Outcome = NFA		
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	2.5
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	1.8
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	1.7
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	1.4
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	1.9
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	3.9
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	1.8
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	1.4
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	13
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	4.4
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	44
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	<300	4.7
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	<300	5.0
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.52
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.81
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.50
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.38
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.92
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	1.2
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.58
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.63
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	20
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	0.53
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	<300	1.1
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	<300	< 1.9 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	<300	3.1

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Toluene
							ug/m3
NYSDDOH Matrix						Matrix F	
						50 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 300 to <3,000 ug/m3 - Matrix Outcome = **Monitor** 10 to <50 ug/m3 and sub-slab vapor <300 ug/m3 - Matrix Outcome = NFA <10 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** <10 ug/m3 and sub-slab vapor <3,000 ug/m3 - Matrix Outcome = NFA		
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	<300	17
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	<300	1.3
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	<300	3.4
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	<300	11
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	<300	6.8
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	300 to <3000	4.1
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	<300	4.4
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	<300	2.2
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	<300	3.6
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	<300	2.2
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	<300	15
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	<300	5.1
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	<300	1.0
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	300 to <3000	4.0
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	<300	2.4
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	<300	5.6
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	<300	2.6
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	<300	6.2
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	<300	1.4
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	<300	0.76
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	<300	1.2
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	<300	0.96
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<300	0.85
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	<300	1.2
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	<300	23
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	<300	1.4

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Toluene
							ug/m3
NYSDDOH Matrix						Matrix F	
						50 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 10 to <50 ug/m3 and sub-slab vapor 300 to <3,000 ug/m3 - Matrix Outcome = **Monitor** 10 to <50 ug/m3 and sub-slab vapor <300 ug/m3 - Matrix Outcome = NFA <10 ug/m3 and sub-slab vapor 3,000 ug/m3 and above - Matrix Outcome = **Mitigate** <10 ug/m3 and sub-slab vapor <3,000 ug/m3 - Matrix Outcome = NFA		
						Sub-Slab Vapor Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report		
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	<300	9.0
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	<300	1.4
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	<300	1.2
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	<300	0.54
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	<300	0.83
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	<300	3.4
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<300	0.90
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	<300	1.7
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	<300	0.76
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	<300	2.0
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	300 to <3000	0.85
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	<300	0.62
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<300	1
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	<300	1

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Acetone	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix														
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report									
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	1	--	--	--	< 1	--	< 1	--	--	--
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	1	--	--	--	< 1	--	1	--	--	--
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	5.7	--	--	--	< 1	--	< 1	--	--	--
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	15	--	--	--	< 1	--	1.2	--	--	--
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	15	--	--	--	< 1	--	1.1	--	--	--
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	8.4	--	--	--	< 1	--	1.3	--	--	--
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	12	--	--	--	< 1	--	1	--	--	--
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	32	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	40	--	--	--	--	--	--	--	--	--
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	17	< 0.88	< 1	< 1.6	< 0.59	< 0.34	0.36	< 0.47	< 0.7	< 0.4
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	17	< 0.88	< 1	< 1.6	< 0.59	< 0.34	1	< 0.47	< 0.7	< 0.4
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	16	< 0.88	< 1	< 1.6	< 0.59	< 0.34	0.78	< 0.47	< 0.7	< 0.4
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	37	< 0.88	0.9	< 1.6	< 0.59	< 0.34	1.4	< 0.47	< 0.7	< 0.4
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	37	< 0.88	1	< 1.6	< 0.59	< 0.34	1.4	0.32	< 0.7	< 0.4
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	14	< 0.88	< 1	< 1.6	< 0.59	< 0.34	0.51	< 0.47	< 0.7	< 0.4
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	23	< 0.88	< 1	< 1.6	< 0.59	< 0.34	0.84	0.95	< 0.7	< 0.4
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	18	< 0.88	< 1	< 1.6	< 0.59	< 0.34	0.57	< 0.47	< 0.7	< 0.4
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	32	< 0.83 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.4 U	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	43 J	< 0.83 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	5.0	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	20	< 0.82 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	2.7	< 2.5 U	< 0.73 U	< 0.21 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Acetone	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	16	< 0.83 U	< 1.1 U	< 1.7 U	< 3.1 U	< 0.36 U	< 2.4 U	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	12 J	< 0.80 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.3 U	2.5	< 0.71 U	< 0.20 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	11 J	< 0.82 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	2.5	< 2.5 U	< 0.73 U	< 0.21 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	11 J	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.3 U	< 2.5 U	< 0.73 U	< 0.21 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	11 J	< 0.83 U	< 1.1 U	< 1.7 U	< 3.1 U	< 0.36 U	< 2.4 U	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	21 J	< 0.82 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	3.0	< 2.5 U	< 0.73 U	< 0.21 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	12 J	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	2.5	< 2.5 U	< 0.73 U	< 0.21 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	9.6 J	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.3 U	< 2.5 U	< 0.73 U	< 0.21 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	37 J	< 0.84 U	< 1.1 U	< 1.7 U	< 3.2 U	< 0.36 U	3.3	< 2.5 U	< 0.75 U	< 0.22 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	14 J	< 0.84 U	< 1.1 U	< 1.7 U	< 3.1 U	< 0.36 U	6.2	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	110 J	< 0.81 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.35 U	4.4	< 2.4 U	< 0.72 U	< 0.21 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	26 J	< 0.84 U	< 1.1 U	< 1.7 U	< 3.1 U	< 0.36 U	3.2	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	22 J	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	2.9	< 2.5 UJ	< 0.73 U	< 0.21 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	5.8 J	< 0.77 U	< 1.0 U	< 1.5 U	< 2.9 U	< 0.33 U	< 2.2 U	< 2.3 UJ	< 0.68 U	< 0.20 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	5.3 J	< 0.80 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.3 U	< 2.4 UJ	< 0.71 U	< 0.20 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	4.8 J	< 0.81 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.35 U	< 2.3 U	< 2.4 UJ	< 0.72 U	< 0.21 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	3.4 J	< 0.81 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.3 U	< 2.4 UJ	< 0.72 U	< 0.20 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	9.2 J	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.3 U	< 2.5 UJ	< 0.73 U	< 0.21 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	6.5 J	< 0.81 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.3 U	< 2.4 UJ	< 0.72 U	< 0.20 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	4.3 J	< 0.82 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.3 U	< 2.5 UJ	< 0.73 U	< 0.21 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	3.8 J	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.3 U	< 2.5 UJ	< 0.73 U	< 0.21 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	22 J	< 0.79 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.2 U	< 2.4 UJ	< 0.70 U	< 0.20 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	3.8 J	< 0.84 U	< 1.1 U	< 1.7 U	< 3.1 U	< 0.36 U	< 2.4 U	< 2.5 U	< 0.74 U	< 0.21 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	6.3 J	< 0.83 U	< 1.1 U	< 1.6 U	< 3.1 U	< 0.35 U	< 2.4 U	< 2.5 UJ	< 0.74 U	< 0.21 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	< 12 U	< 2.6 U	< 3.4 U	< 5.2 U	< 19 U	< 1.1 U	< 5.9 U	< 6.2 U	< 2.3 U	< 5.3 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	29	< 0.81 U	2.9	< 1.6 U	< 30 U	< 0.35 U	2.9	< 2.4 U	< 0.72 U	< 0.21 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Acetone	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane
							ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix																
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report											
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	45	< 0.84 U	3.8	< 1.7 U	< 31 U	< 0.36 U	10	< 2.5 U	< 0.74 U	< 0.21 U
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	26	< 0.8 U	< 1 U	< 1.6 U	< 30 U	< 0.34 U	3.4	< 2.4 U	< 0.71 U	< 0.2 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	17	< 0.79 U	< 1.0 U	< 1.6 U	< 30 U	< 0.34 U	< 2.2 U	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	87	< 0.77 U	1.1	< 1.5 U	< 29 U	< 0.33 U	9.1	< 2.3 U	< 0.68 U	< 0.20 U
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	31	< 0.79 U	1.8	< 1.6 U	< 30 U	< 0.34 U	5.0	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	28	< 0.82 U	3.9	< 1.6 U	< 31 U	< 0.35 U	3.2	< 2.5 U	< 0.73 U	< 0.21 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	26	< 0.83 U	< 1.1 U	< 1.7 U	< 31 U	< 0.36 U	2.4	< 2.5 U	< 0.74 U	< 0.21 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	27	< 0.87 U	< 1.1 U	< 1.7 U	< 33 U	< 0.37 U	3.8	< 2.6 U	< 0.77 U	< 0.22 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	42	< 0.82 U	< 1.0 U	< 1.6 U	< 31 U	< 0.35 U	4.0	< 2.5 U	< 0.73 U	< 0.21 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	22	< 0.81 U	< 1 U	< 1.6 U	< 30 U	< 0.35 U	3.3	< 2.4 U	< 0.72 U	< 0.21 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	55	< 0.85 U	1.8	< 1.7 U	< 3.2 U	< 0.36 U	3.3	< 2.6 U	< 0.76 U	< 0.22 U
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	26	< 0.8 U	< 1 U	< 1.6 U	< 30 U	< 0.34 U	3.1	< 2.4 U	< 0.71 U	< 0.2 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	34	< 0.77 U	15	< 1.5 U	< 2.9 U	< 0.33 U	3.6	< 2.3 U	< 0.68 U	< 0.20 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	28	< 0.79 U	4.4	< 1.6 U	< 30 U	< 0.34 U	3.3	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	41	< 0.81 U	11	< 1.6 U	< 30 U	< 0.34 U	4.2	< 2.4 U	< 0.72 U	< 0.2 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	84	< 0.79 U	3.5	< 1.6 U	< 30 U	< 0.34 U	41	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	26	< 0.79 U	1.2	< 1.6 U	< 30 U	< 0.34 U	2.6	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	32	< 0.85 U	< 1.1 U	< 1.7 U	< 32 U	< 0.36 U	6.7	< 2.6 U	< 0.76 U	< 0.22 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	16	< 0.78 U	< 1.0 U	< 1.6 U	< 2.9 U	< 0.33 U	2.7	< 2.3 U	< 0.69 U	< 0.20 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	19	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	2.3 J	< 2.5 U	< 0.73 U	< 0.21 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	23	< 0.87 U	< 1.1 U	< 1.7 U	< 33 U	< 0.37 U	4.5	< 2.6 U	< 0.78 U	< 0.22 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	22	< 0.78 U	1.4	< 1.6 U	< 29 U	< 0.33 U	3.8	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	16	< 0.76 U	< 0.98 U	< 1.5 U	< 2.8 U	< 0.32 U	< 2.2 U	< 2.3 U	< 0.67 U	< 0.19 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	16	< 0.77 U	< 1.0 U	< 1.5 U	< 2.9 U	< 0.33 U	< 2.2 U	< 2.3 U	< 0.68 U	< 0.20 U
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	36	< 0.78 U	< 1.0 U	< 1.6 U	< 29 U	< 0.33 U	7.6	< 2.3 U	< 0.69 U	< 0.20 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	15	< 0.79 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	2.9	< 2.4 U	< 0.70 U	< 0.20 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Acetone	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	20	< 1.4 U	< 1.9 U	< 2.9 U	< 54 U	< 0.62 U	< 4.1 U	< 4.4 U	< 1.3 U	< 0.37 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	16	< 0.77 U	< 1.0 U	< 1.5 U	< 2.9 U	< 0.33 U	3.4	< 2.3 U	< 0.68 U	< 0.20 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	29	< 0.77 U	< 1.0 U	< 1.5 U	< 29 U	< 0.33 U	4.1	< 2.3 U	< 0.68 U	< 0.20 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	13	< 0.81 U	1.0 J	< 1.6 U	< 30 U	< 0.34 U	< 2.3 U	< 2.4 U	< 0.72 U	< 0.20 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	31	< 0.81 U	< 1.0 U	< 1.6 U	< 30 U	< 0.34 U	4.2	< 2.4 U	< 0.72 U	< 0.20 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	26	< 0.79 U	< 1.0 U	< 1.6 U	< 30 U	< 0.34 U	5.9	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	11	< 0.79 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.2 U	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	12	< 0.79 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.2 U	< 2.4 U	< 0.70 U	< 0.20 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	17	< 0.81 U	< 1.0 U	< 1.6 U	< 30 U	< 0.34 U	4.4	< 2.4 U	< 0.72 U	< 0.20 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	13	< 0.82 U	< 1.0 U	< 1.6 U	< 3.1 U	< 0.35 U	2.4	< 2.5 U	< 0.73 U	< 0.21 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	23	< 0.82 U	< 1.0 U	< 1.6 U	< 31 U	< 0.35 U	4.1	< 2.5 U	< 0.73 U	< 0.21 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	18	< 0.81 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	3.1	< 2.4 U	< 0.72 U	< 0.20 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	9.4	< 0.81 U	< 1 U	< 1.6 U	< 3 U	< 0.34 U	< 2.3 U	< 2.4 U	< 0.72 U	< 0.2 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	5	< 0.8 U	< 1 U	< 1.6 U	< 3 U	< 0.34 U	< 2.3 U	< 2.4 U	< 0.71 U	< 0.2 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	0.1756	--	--	--	--	--	--	--	--	--
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	0.18946	--	--	--	--	--	--	--	--	--
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	0.1634	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	ND	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	1	1	--	--	--	--	--	--	2.7	--
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	1	1	--	--	--	--	--	--	2.2	--
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	1.2	1	--	--	--	--	--	--	2.5	--
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	1	1.1	--	--	--	--	--	--	8.7	--
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	1.2	1.1	--	--	--	--	--	--	6.5	--
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	2.6	1.1	--	--	--	--	--	--	4.7	--
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	1.6	1.1	--	--	--	--	--	--	6.1	--
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	--	1.6	--	--	--	--	--	--	12	--
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	--	< 1	--	--	--	--	--	--	8.7	--
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	0.69	0.8	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	25	0.49
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	28	0.63	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	4.2	< 0.62
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	0.94	0.67	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	9.6	0.41
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	65	0.69	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	3.3	< 0.62
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	55	0.61	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	27	0.49
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	0.94	0.55	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	12	< 0.62
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	4.2	0.5	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	6	< 0.62
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	1.8	0.61	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	25	0.49
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.24	1.2	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	4.4	< 0.13 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	1.0	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	12	< 0.13 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.96	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	16	< 0.13 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.33	1.0	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	< 0.19 U	17	< 0.13 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.15 U	0.79	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	0.031 J	10	< 0.12 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.76	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	13	< 0.13 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.15 U	0.90	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	6.5	< 0.13 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.79	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	< 0.19 U	9.9	< 0.13 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.92	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	9.5	< 0.13 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.15 U	0.86	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	9.7	< 0.13 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.15 U	1.1	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	0.044 B	15	< 0.13 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.84	< 2.6 U	< 1.4 U	< 0.25 U	< 0.98 U	< 0.98 U	< 0.20 U	9.6	< 0.13 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.76	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	< 0.19 U	13	< 0.13 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.15 U	0.84	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	6.9	< 0.13 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.16 U	0.94	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	< 0.19 U	11	< 0.13 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	< 0.15 U	0.84	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	11	< 0.13 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.59	0.76	< 2.3 U	< 1.3 U	< 0.23 U	< 0.90 U	< 0.90 U	< 0.18 U	2.0	< 0.12 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.57	0.73	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	2.2	< 0.12 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.15 U	0.85	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	2.0	< 0.13 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.15 U	0.78	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	2.0	< 0.13 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.33	0.81	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	4.9	< 0.13 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.37	0.70	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	4.9	< 0.13 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.16 U	0.74	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	2.2	< 0.13 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.39	0.74	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	2.0	< 0.13 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.70	0.81	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	3.5	< 0.12 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.16 U	0.71	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	0.22 B	2.1	< 0.13 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.24	0.78	< 2.5 U	< 1.4 U	< 0.24 U	< 0.96 U	< 0.96 U	< 0.19 U	2.4	< 0.13 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	< 2.4 U	< 10 U	< 6.3 U	< 4.2 U	< 3.8 U	< 3 U	< 3 U	< 3 U	< 2.5 U	< 2 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	11	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	22	< 0.13 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	15	< 1.7 U	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	< 0.19 U	41	< 0.13 U
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	0.38	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.93 U	< 0.93 U	< 0.19 U	51	< 0.12 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	0.64	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	25	< 0.12 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	5.3	1.5	< 2.3 U	< 1.3 U	< 0.23 U	< 0.89 U	< 0.89 U	< 0.18 U	14	< 0.12 U
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	7.1	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	7.9	< 0.12 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	16	< 1.6 U	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	14	< 0.13 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	1.2	< 1.7 U	< 2.5 U	< 1.4 U	< 0.25 U	< 0.97 U	< 0.97 U	< 0.19 U	32	< 0.13 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	1.7	< 1.7 U	< 2.6 U	< 1.4 U	< 0.26 U	< 1 U	< 1 U	< 0.2 U	32	< 0.14 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	4.4	< 1.6 U	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	24	< 0.13 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	1.2	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	39	< 0.13 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	7.6	< 1.7 U	< 2.6 U	< 1.4 U	< 0.25 U	< 0.99 U	< 0.99 U	< 0.20 U	40	< 0.13 U
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	2.4	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.93 U	< 0.93 U	< 0.19 U	22	< 0.12 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	51	< 1.5 U	< 2.3 U	4.6	< 0.23 U	< 0.89 U	< 0.89 U	< 0.18 U	6.9	< 0.12 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	16	1.6	< 2.4 U	< 1.3 U	< 0.23 U	< 0.91 U	< 0.91 U	< 0.18 U	14	< 0.12 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	48	< 1.6 U	< 2.4 U	2.9	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	7.2	< 0.13 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	15	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	26	< 0.12 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	4.7	< 1.6 U	< 2.4 U	< 1.3 U	< 0.23 U	< 0.91 U	< 0.91 U	< 0.18 U	7.6	< 0.12 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	3.4	< 1.7 U	< 2.6 U	< 1.4 U	< 0.25 U	< 0.99 U	< 0.99 U	< 0.2 U	30	< 0.13 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	0.19	< 1.5 U	< 2.3 U	< 1.3 U	< 0.23 U	< 0.90 U	< 0.90 U	< 0.18 U	22	< 0.12 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	0.18	< 1.6 U	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	4.1	< 0.13 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	0.34	< 1.7 U	< 2.6 U	< 1.4 U	< 0.26 U	< 1.0 U	< 1.0 U	< 0.20 U	3.1	< 0.14 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	5.3	< 1.6 U	< 2.4 U	< 1.3 U	< 0.23 U	< 0.91 U	< 0.91 U	< 0.18 U	3.7	< 0.12 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	0.42	< 1.5 U	< 2.3 U	< 1.2 U	< 0.22 U	< 0.88 U	< 0.88 U	< 0.18 U	3.7	< 0.12 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	0.40	< 1.5 U	< 2.3 U	< 1.3 U	< 0.23 U	< 0.90 U	< 0.90 U	< 0.18 U	3.6	< 0.12 U
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	0.53	< 1.5 U	< 2.3 U	< 1.3 U	< 0.23 U	< 0.90 U	< 0.90 U	< 0.18 U	4.2	< 0.12 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	0.31	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	12	< 0.12 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	0.50	< 2.9 U	< 4.4 U	< 2.4 U	< 0.43 U	< 1.7 U	< 1.7 U	< 0.34 U	3.0	< 0.23 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	0.42	< 1.5 U	< 2.3 U	< 1.3 U	< 0.23 U	< 0.90 U	< 0.90 U	< 0.18 U	6.8	< 0.12 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	0.63	< 1.5 U	< 2.3 U	< 1.3 U	< 0.23 U	< 0.90 U	< 0.90 U	< 0.18 U	5.5	< 0.12 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	3.1	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	3.6	< 0.13 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	1.1	1.7	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	3.1	< 0.13 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	1.5	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	4.4	< 0.12 U
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	0.17	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	4.3	< 0.12 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	0.17	< 1.6 U	< 2.4 U	< 1.3 U	< 0.23 U	< 0.91 U	< 0.91 U	< 0.18 U	4.3	< 0.12 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	0.69	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	2.9	< 0.13 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	0.17	< 1.6 U	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	7.3	< 0.13 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	0.85	< 1.6 U	< 2.5 U	< 1.3 U	< 0.24 U	< 0.95 U	< 0.95 U	< 0.19 U	3.2	< 0.13 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	0.45	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	2.7	< 0.13 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	< 0.15 U	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.94 U	< 0.94 U	< 0.19 U	2.3	< 0.13 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	< 0.15 U	< 1.6 U	< 2.4 U	< 1.3 U	< 0.24 U	< 0.93 U	< 0.93 U	< 0.19 U	2.4	< 0.12 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

						1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	ND	ND	--	--	--	--	--	--	--	--
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	0.04923	ND	--	--	--	--	--	--	--	--
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	ND	ND	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	ND	ND	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	200	--	--
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	6.1	--	--
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	6.7	--	--
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	145	--	--
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	175	--	--
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	45	--	--
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	75	--	--
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	30	--	--
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	25	--	--
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	6.5	< 0.75	< 1.6
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	3.5	< 0.75	< 1.6
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	13	< 0.75	< 1.6
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	3.2	< 0.75	< 1.6
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	3.7	< 0.75	< 1.6
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	7.9	< 0.75	< 1.6
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	12	< 0.75	< 1.6
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	7.1	< 0.75	< 1.6
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.63 U	< 0.74 U	< 0.73 U	< 0.73 U	< 0.22 U	< 0.58 U	5.9	< 0.79 U	< 8.5 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.37	< 0.63 U	< 0.74 U	< 0.73 U	< 0.73 U	< 0.22 U	0.59	55 J	< 0.79 U	< 8.5 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.53	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	22	< 0.78 U	< 8.5 U

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.17	< 0.64 U	< 0.74 U	< 0.73 U	< 0.73 U	< 0.22 U	< 0.58 U	11	< 0.79 U	< 8.6 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.18	< 0.61 U	< 0.71 U	< 0.70 U	< 0.70 U	< 0.22 U	< 0.55 U	12 J	< 0.76 U	< 8.2 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.21	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	6.6 J	< 0.78 U	< 8.5 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	7.4 J	< 0.78 U	< 8.4 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.64 U	< 0.74 U	< 0.73 U	< 0.73 U	< 0.22 U	< 0.58 U	8.1 J	< 0.79 U	< 8.6 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	22 J	< 0.78 U	< 8.5 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.62 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	10 J	< 0.78 U	< 8.4 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	0.79	9.3 J	< 0.78 U	< 8.4 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.65 U	< 0.75 U	< 0.74 U	< 0.74 U	< 0.23 U	0.92	22 J	< 0.80 U	< 8.7 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.64 U	< 0.75 U	< 0.74 U	< 0.74 U	< 0.23 U	1.0	50 J	< 0.80 U	< 8.6 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	25 J	1.4	< 8.4 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	0.19	< 0.64 U	< 0.75 U	< 0.74 U	< 0.74 U	< 0.23 U	0.65	27 J	< 0.80 U	< 8.6 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	1.6	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	21 J	< 0.78 U	< 8.4 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.12 U	< 0.59 U	< 0.69 U	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	5.6 J	< 0.73 U	< 7.9 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.12 U	< 0.61 U	< 0.71 U	< 0.70 U	< 0.70 U	< 0.22 U	0.66	6.8 J	< 0.76 U	< 8.2 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	0.66	2.3 J	< 0.77 U	< 8.4 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	2.3 J	< 0.77 U	< 8.3 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.13	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	8.8 J	< 0.78 U	< 8.4 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	0.13	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	7.6 J	< 0.77 U	< 8.3 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	< 1.5 UJ	< 0.78 U	< 8.5 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	2.5 J	< 0.78 U	< 8.4 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.12 U	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	100 J	2.9	< 8.2 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.13 U	< 0.64 U	< 0.75 U	< 0.74 U	< 0.74 U	< 0.23 U	< 0.58 U	3.0 J	< 0.80 U	< 8.6 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 0.13 U	< 0.63 U	< 0.74 U	< 0.73 U	< 0.73 U	< 0.22 U	< 0.58 U	< 1.5 UJ	< 0.79 U	< 8.5 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	< 2 U	< 2 U	< 2.3 U	< 2.3 U	< 2.3 U	< 3.5 U	< 7.2 U	< 3.8 U	< 2.4 U	< 21 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	0.43	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	1.2	51	< 0.77 U	< 8.4 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	0.16	< 0.64 U	< 0.75 U	< 0.74 U	< 0.74 U	< 0.23 U	< 0.58 U	32	2.0	< 8.6 U
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	0.16	< 0.61 U	< 0.72 U	< 0.7 U	< 0.7 U	< 0.22 U	< 0.56 U	8.7	< 0.76 U	< 8.3 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	0.12	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	17	< 0.75 U	< 8.2 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	0.15	< 0.59 U	< 0.68 U	< 0.67 U	< 0.67 U	< 0.21 U	< 0.53 U	17	1.0	< 7.9 U
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	0.14	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	0.93	36	3.8	< 8.2 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	0.17	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	26	0.98	< 8.4 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	< 0.13 U	< 0.64 U	< 0.74 U	< 0.73 U	< 0.73 U	< 0.22 U	< 0.58 U	13	< 0.79 U	< 8.6 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	0.22	< 0.67 U	< 0.78 U	< 0.76 U	< 0.76 U	< 0.23 U	< 0.6 U	24	< 0.82 U	< 9 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	0.42	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	1.5	62	< 0.78 U	< 8.4 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	0.28	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	21	< 0.77 U	< 8.4 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	< 0.13 U	< 0.65 U	< 0.76 U	< 0.74 U	< 0.74 U	< 0.23 U	< 0.59 U	99	1.3	< 8.7 UJ
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	1.1	< 0.61 U	< 0.72 U	< 0.7 U	< 0.7 U	< 0.22 U	< 0.56 U	36	< 0.76 U	< 8.3 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	< 0.12 U	< 0.59 U	< 0.68 U	< 0.67 U	< 0.67 U	< 0.21 U	< 0.53 U	< 1.4 U	< 0.73 U	< 7.9 UJ
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	0.18	< 0.60 U	< 0.70 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	25	0.92	< 8.1 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	4.6	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	52	< 0.77 U	< 8.3 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	0.16	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	60	< 0.75 U	< 8.2 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	0.16	< 0.60 U	< 0.70 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	25	< 0.75 U	< 8.1 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	0.62	< 0.65 U	< 0.76 U	< 0.74 U	< 0.74 U	< 0.23 U	< 0.59 U	62	< 0.81 U	< 8.7 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	< 0.12 U	< 0.59 U	< 0.69 U	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	6.7	< 0.74 U	< 8.0 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	6.4	< 0.78 U	< 8.4 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	< 0.14 U	< 0.67 U	< 0.78 U	< 0.77 U	< 0.77 U	< 0.24 U	< 0.61 U	6.1	< 0.83 U	< 9.0 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	0.90	< 0.60 U	< 0.70 U	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	13	< 0.74 U	< 8.0 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	< 0.12 U	< 0.58 U	< 0.67 U	< 0.66 U	< 0.66 U	< 0.20 U	< 0.53 U	14	< 0.72 U	< 7.8 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	< 0.12 U	< 0.59 U	< 0.69 U	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	15	< 0.73 U	< 7.9 U
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	0.14	< 0.59 U	1.7	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	14	1.7	< 8.0 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	< 0.12 U	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	10	< 0.75 U	< 8.2 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix															
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report										
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	0.25	< 1.1 U	< 1.3 U	< 1.3 U	< 1.3 U	< 0.39 U	< 1.0 U	12	2.5	< 15 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	0.27	< 0.59 U	< 0.69 U	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	16	< 0.73 U	< 7.9 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	0.30	< 0.59 U	< 0.69 U	< 0.68 U	< 0.68 U	< 0.21 U	< 0.54 U	48	< 0.73 U	< 7.9 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	3.7	< 0.77 U	< 8.3 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	11	< 0.77 U	< 8.3 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	< 0.12 U	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	15	< 0.75 U	< 8.2 U
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	< 0.12 U	< 0.61 U	< 0.71 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	6.8	< 0.75 U	< 8.2 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	< 0.12 U	< 0.60 U	< 0.70 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	7.0	< 0.75 U	< 8.1 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	17	< 0.77 U	< 8.3 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	7.7	< 0.78 U	< 8.4 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	< 0.13 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.22 U	< 0.57 U	12	< 0.78 U	< 8.4 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	7.6	< 0.77 U	< 8.3 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	< 0.13 U	< 0.62 U	< 0.72 U	< 0.71 U	< 0.71 U	< 0.22 U	< 0.56 U	6.6 J	< 0.77 U	< 8.3 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	< 0.12 U	< 0.61 U	< 0.72 U	< 0.7 U	< 0.7 U	< 0.22 U	< 0.56 U	7.3 J	< 0.76 U	< 8.3 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix																
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report											
CAFETERIA	CAFETERIA-19971104-TRAIN3COLUME1	Cafeteria	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--	--
IA-LoadingDock	OUTSIDE-LOADDOCK-19971104-TRAIN5COLUME4	Outside Loading Dock	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--	--
IA-Outside111	OUTSIDE-RM111-19971104-TRAIN1COLUME5	Outside Room 111	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-19971104-TRAIN4COLUME6	Library	11/4/1997	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--	--
LIBRARY	LIBRARY-20000419-IA-LIBRARY	Library	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--	--
POOL	POOL-20000419-IA-POOL	Pool	4/19/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	--	--
CAFETERIA	CAFETERIA-20000523-IA-CAFETERIA	Cafeteria	5/23/2000	NYSDOH Consultation	NA	--	--	< 1	--	--	--	--	--	--	1.4	< 1
GYM	GYM-20000523-IA-GYM	Gym	5/23/2000	NYSDOH Consultation	NA	--	--	< 1	--	--	--	--	--	--	1	1
GYM-STOREROOM	GYM-STOREROOM-20000523-IA-GYMSTOREROOM	Gym Storage room	5/23/2000	NYSDOH Consultation	NA	--	--	3.8	--	--	--	--	--	--	1	1
LIBRARY	LIBRARY-20000523-IA-LIBRARY	Library	5/23/2000	NYSDOH Consultation	NA	--	--	3.1	--	--	--	--	--	--	1.9	1
IA-127	RM-127-20000523-IA-127	Room 127	5/23/2000	NYSDOH Consultation	NA	--	--	3.3	--	--	--	--	--	--	1.8	1
RM-138	RM-138-20000523-IA-138	Room 138	5/23/2000	NYSDOH Consultation	NA	--	--	< 1	--	--	--	--	--	--	4.1	< 1
RM-148	RM-148-20000523-IA-148	Room 148	5/23/2000	NYSDOH Consultation	NA	--	--	1	--	--	--	--	--	--	2.1	1.1
BSMT-SCIROOM	BSMT-SCIROOM-20000831-IA-BASEMANTSCIRM	Room 151	8/31/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	12	1.6
LIBRARY	LIBRARY-20000831-IA-LIBRARY	Library	8/31/2000	NYSDOH Consultation	NA	--	--	--	--	--	--	--	--	--	2.9	1.4
CAFETERIA	CAFETERIA-20091216-IA-CAF	Cafeteria	12/16/2009	IAQAP Mitigation Veritification	NA	< 1.2	4.3	< 1.2	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	2.5	7.2
GYM	GYM-20091216-IA-GYM	Gym	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	3.6	1	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	0.8	16
LIBRARY	LIBRARY-20091216-IA-LIB	Library	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	24	1.1	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	1	7.3
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-DUP5	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	5.2	< 1.2	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	1.1	66
POOL-FILTERROOM	POOL-FILTERROOM-20091216-IA-PF	Pool Filter Room	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	5	< 1.2	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	1.4	97
RM-127	RM-127-20091216-IA-127	Room 127	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	11	< 1.2	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	0.91	4.8
RM-138	RM-138-20091216-IA-138	Room 138	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	< 0.37	1.3	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	2	6.6
RM-151A	RM-151A-20091216-IA-151A	Room 151A	12/16/2009	IAQAP Mitigation Verification	NA	< 1.2	10	< 1.2	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	2.5	9
SSHS-01-IA	SSHS-07-08-14-01-IA	Hallway Near Main Entrance	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	< 2.0 U	< 0.66 U	< 0.58 U	< 0.68 U	< 0.22 U	< 2.4 U	< 5.9 U	< 0.17 U	1.4	< 1.2 U
SSHS-08-IA	SSHS-07-08-14-08-IA	Room 129 (Guidance)	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	11	3.4	< 0.58 U	1.0	< 0.22 U	< 2.4 U	< 5.9 U	< 0.17 U	< 0.90 U	< 1.2 U
SSHS-03-IA	SSHS-07-08-14-03-IA	Room 127	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	< 2.0 U	< 0.65 U	< 0.57 U	< 0.68 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.6	< 1.2 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix																
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report											
SSHS-02-IA	SSHS-07-08-14-02-IA	Room 130	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	< 2.0 U	< 0.66 U	< 0.58 U	< 0.68 U	< 0.22 U	< 2.4 U	< 6.0 U	< 0.18 U	1.5	< 1.2 U
SSHS-04-IA	SSHS-07-08-14-04-IA	Room 125	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	2.0	< 0.63 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.7 U	< 0.17 U	< 0.86 U	< 1.2 U
SSHS-05-IA	SSHS-07-08-14-05-IA	Room 124	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	< 2.0 U	< 0.65 U	< 0.57 U	< 0.68 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	< 0.89 U	< 1.2 U
SSHS-07-IA	SSHS-07-08-14-07-IA	Room 120	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	< 1.9 U	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.0	< 1.2 U
SSHS-06-IA	SSHS-07-08-14-06-IA	Room 122	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	< 2.0 U	< 0.66 U	< 0.58 U	< 0.68 U	< 0.22 U	< 2.4 U	< 6.0 U	< 0.18 U	1.0	< 1.2 U
SSHS-11-IA	SSHS-07-08-14-11-IA	Room 115	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	4.7	< 0.65 U	< 0.57 U	0.76	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.0	< 1.2 U
SSHS-12-IA	SSHS-07-08-14-12-IA	Room 116	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	< 1.9 U	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	0.90	< 1.2 U
SSHS-13-IA	SSHS-07-08-14-13-IA	Room 111	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	< 1.9 U	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	< 0.89 U	< 1.2 U
SSHS-14-IA	SSHS-07-08-14-14-IA	Room 103	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	2.5	< 0.67 U	< 0.59 U	< 0.69 U	< 0.22 U	< 2.4 U	< 6.0 U	< 0.18 U	1.0	< 1.2 U
SSHS-15-IA	SSHS-07-08-14-15-IA	Room 105	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	< 2.0 U	2.3	< 0.58 U	< 0.69 U	< 0.22 U	< 2.4 U	< 6.0 U	< 0.18 U	< 0.91 U	< 1.2 U
SSHS-10-IA	SSHS-07-08-14-10-IA	Room 101	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.2 U	4.9	< 0.64 U	< 0.57 U	0.70	< 0.22 U	< 2.3 U	< 5.8 U	< 0.17 U	1.1	< 1.2 U
SSHS-09-IA	SSHS-07-08-14-09-IA	Room 100 (Library)	7/8/2014	Vapor Intrusion Assessment	1407149R1	< 3.3 U	6.1	< 0.66 U	< 0.58 U	0.83	< 0.22 U	< 2.4 U	< 6.0 U	< 0.18 U	< 0.91 U	< 1.2 U
SSHS-IAON-127	SSHS-07-08-14-IAON-127	Room 127	7/9/2014	Vapor Intrusion Assessment	1407148R1	< 3.2 U	8.4	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	0.91	< 1.2 U
SSHS-21-IA	SSHS-07-10-14-21-IA	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.0 U	< 1.8 U	< 0.61 U	< 0.54 U	< 0.63 U	< 0.20 U	< 2.2 U	< 5.5 U	< 0.16 U	0.94	< 1.1 U
SSHS-21-IA	SSHS-07-10-14-21-IA-DUP	Room 145 Nurses Office	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	2.8	< 0.63 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.7 U	< 0.17 U	1.1	< 1.2 U
SSHS-16-IA	SSHS-07-10-14-16-IA	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	< 1.9 U	< 0.64 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.8 U	< 0.17 U	0.95	< 1.2 U
SSHS-16-IA	SSHS-07-10-14-16-IA-DUP	Auditorium	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	< 1.9 U	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	< 0.88 U	< 1.2 U
SSHS-22-IA	SSHS-07-10-14-22-IA	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	< 1.9 U	1.9	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.1	< 1.2 U
SSHS-22-IA	SSHS-07-10-14-22-IA-DUP	Room 171 (Aux Gym)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	< 1.9 U	1.9	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	0.88	< 1.2 U
SSHS-19-IA	SSHS-07-10-14-19-IA	Room 138A	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	< 2.0 U	< 0.65 U	< 0.57 U	< 0.68 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	0.93	< 1.2 U
SSHS-17-IA	SSHS-07-10-14-17-IA	Room 136A	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.2 U	< 1.9 U	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.1	< 1.2 U
SSHS-18-IA	SSHS-07-10-14-18-IA	Custodian Break Room (M14)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.1 U	4.6	< 0.63 U	< 0.55 U	3.1	< 0.21 U	< 2.2 U	< 5.7 U	< 0.17 U	1.2	< 1.2 U
SSHS-23-IA	SSHS-07-10-14-23-IA	Room 156 (Girls Locker Room)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.3 U	< 2.0 U	< 0.66 U	< 0.58 U	< 0.69 U	< 0.22 U	< 2.4 U	< 6.0 U	< 0.18 U	1.0	< 1.2 U
SSHS-20-IA	SSHS-07-10-14-20-IA	Room 142 (Wellness Ctr)	7/10/2014	Vapor Intrusion Assessment	1407185R1	< 3.3 U	8.6	1.3	< 0.58 U	< 0.68 U	< 0.22 U	< 2.4 U	< 5.9 U	< 0.17 U	0.95	< 1.2 U
SSHS-21-IA	1807026A_1807026A-21A	Room 145 (Nurses Office)	6/28/2018	Supplemental VI Assessment	1807026A	< 8.2 U	< 4.9 U	< 2 U	< 7.2 U	< 2.1 U	< 3.4 U	< 1.5 U	< 15 U	< 2.7 U	< 2.8 U	< 3.8 U
EHS-IA-133	EHS-062818-IA-133-UN	Room 133	6/28/2018	Supplemental VI Assessment	1807030	< 3.2 U	8.9	< 0.64 U	< 0.57 U	0.94	< 0.22 U	< 2.3 U	< 5.8 U	< 0.17 U	1.4	< 1.2 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix																
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report											
EHS-IA-139	EHS-062818-IA-139-UN	Room 139	6/28/2018	Supplemental VI Assessment	1807030	< 3.3 U	8.6	0.99 J0	< 0.58 U	4.9	< 0.22 U	5.3	< 6.0 U	< 0.18 U	1.4	< 1.2 U
EHS-IA-104	EHS-062818-IA-104-UN	Room 104	6/28/2018	Supplemental VI Assessment	1807031	< 3.2 U	2.8	< 0.63 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.3	< 1.2 U
EHS-IA-109	EHS-062818-IA-109-UN	Room 109	6/28/2018	Supplemental VI Assessment	1807030	< 3.1 U	3.4	< 0.63 U	< 0.55 U	< 0.65 U	< 0.21 U	< 2.2 U	< 5.7 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-151A	EHS-062818-IA-151A-UN	Room 149	6/28/2018	Supplemental VI Assessment	1807030	< 3.0 U	11	0.85 J0	< 0.53 U	0.94	< 0.20 U	< 2.2 U	< 5.5 U	< 0.16 U	1.2	< 1.1 U
EHS-IA-CAF	EHS-062818-IA-CAF-UN	Cafeteria	6/28/2018	Supplemental VI Assessment	1807030	< 3.1 U	7.3	1.3 J0	< 0.55 U	2.5	< 0.21 U	< 2.2 U	< 5.7 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-135	EHS-062818-IA-135-UN	Room 135	6/28/2018	Supplemental VI Assessment	1807030	< 3.2 U	5.8	0.94 J0	< 0.57 U	1.1	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.4	< 1.2 U
EHS-IA-148	EHS-062818-IA-148-UN	Room 148	6/28/2018	Supplemental VI Assessment	1807031	< 3.3 U	2.7	< 0.66 U	< 0.58 U	< 0.68 U	< 0.22 U	< 2.4 U	< 6 U	< 0.18 U	1.2	< 1.2 U
EHS-IA-103	EHS-062818-IA-103-UN	Room 103 (Hallway)	6/28/2018	Supplemental VI Assessment	1807031	< 3.4 U	4.2	0.69 J0	< 0.6 U	< 0.72 U	< 0.23 U	< 2.5 U	< 6.2 U	< 0.18 U	1.3	< 1.3 U
EHS-IA-100	EHS-062818-IA-100-UN	Room 100 (Library)	6/28/2018	Supplemental VI Assessment	1807030	< 3.2 U	10	0.70 J0	< 0.57 U	0.88	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.5	< 1.2 U
EHS-IA-120	EHS-062818-IA-120-UN	Room 120	6/28/2018	Supplemental VI Assessment	1807031	< 3.2 U	3.3	< 0.64 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-164	EHS-062818-IA-164-UN	Room 168	6/28/2018	Supplemental VI Assessment	1807026B	< 3.4 U	6.0	< 0.67 U	< 0.59 U	< 0.70 U	< 0.22 U	< 2.4 U	< 6.1 UJ	< 0.18 U	1.4	< 1.2 U
EHS-IA-127	EHS-062818-IA-127-UN	Room 127	6/28/2018	Supplemental VI Assessment	1807031	< 3.2 U	6.8	0.73 J0	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-GYM	EHS-062818-IA-GYM-UN	Gymnasium	6/28/2018	Supplemental VI Assessment	1807026B	< 3.0 U	< 1.8 U	< 0.61 U	< 0.53 U	< 0.63 U	< 0.20 U	< 2.2 U	< 5.5 UJ	< 0.16 U	< 0.83 U	< 1.1 U
EHS-IA-135	EHS-062818-IA-135-UN-DUP	Room 135	6/28/2018	Supplemental VI Assessment	1807030	< 3.1 U	5.2	1.0 J0	< 0.55 U	0.97	< 0.21 U	< 2.2 U	< 5.6 U	< 0.16 U	1.3	< 1.2 U
EHS-IA-145	EHS-062818-IA-145-UN	Room 145	6/28/2018	Supplemental VI Assessment	1807031	< 3.2 U	15	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-138A	EHS-062818-IA-138A-UN	Room 138A	6/28/2018	Supplemental VI Assessment	1807030	< 3.1 U	4.9	1.7 J0	< 0.55 U	0.81	< 0.21 U	140	< 5.7 U	< 0.17 U	1.6	< 1.2 U
EHS-IA-K	EHS-062818-IA-K-UN	K-Wing	6/28/2018	Supplemental VI Assessment	1807030	< 3.1 U	12	1.2 J0	< 0.55 U	< 0.65 U	< 0.21 U	< 2.2 U	< 5.6 U	< 0.16 U	1.3	< 1.2 U
EHS-IA-122	EHS-062818-IA-122-UN	Room 122	6/28/2018	Supplemental VI Assessment	1807031	< 3.4 U	9.6	1.2 J0	< 0.59 U	1.3	< 0.22 U	< 2.4 U	< 6.1 U	< 0.18 U	1.2	< 1.2 U
EHS-IA-104	EHS-062918-IA-104-OCC	Room 104	6/29/2018	Supplemental VI Assessment	1807029	< 3.1 U	< 1.8 U	< 0.61 U	< 0.54 U	< 0.64 U	< 0.20 U	< 2.2 U	< 5.6 U	< 0.16 U	1.3	< 1.1 U
EHS-IA-103	EHS-062918-IA-103-OCC	Room 103 (Hallway)	6/29/2018	Supplemental VI Assessment	1807029	< 3.2 U	1.9	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.3	< 1.2 U
EHS-IA-151A	EHS-062918-IA-151A-OCC	Room 149	6/29/2018	Supplemental VI Assessment	1807026B	< 3.5 U	< 2.1 U	< 0.69 U	< 0.61 U	< 0.72 U	0.32	< 2.5 U	< 6.3 U	< 0.18 U	1.2	< 1.3 U
EHS-IA-145	EHS-062918-IA-145-OCC	Room 145	6/29/2018	Supplemental VI Assessment	1807026B	< 3.1 U	4.4	< 0.62 U	< 0.54 U	< 0.64 U	0.37	< 2.2 U	< 5.6 U	< 0.16 U	1.3	< 1.2 U
EHS-IA-100	EHS-062918-IA-100-OCC	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	< 3.0 U	2.2	< 0.60 U	< 0.53 U	< 0.62 U	< 0.20 U	< 2.2 U	< 5.4 U	< 0.16 U	1.4	< 1.1 U
EHS-IA-100	EHS-062918-IA-100-OCC-DUP	Room 100 (Library)	6/29/2018	Supplemental VI Assessment	1807029	< 3.0 U	4.2	< 0.61 U	< 0.54 U	< 0.63 U	< 0.20 U	< 2.2 U	< 5.5 U	< 0.16 U	1.3	< 1.1 U
EHS-IA-148	EHS-062918-IA-148-OCC	Room 148	6/29/2018	Supplemental VI Assessment	1807026B	< 3.1 U	6.8	0.96	< 0.54 U	1.2	< 0.20 U	< 2.2 U	< 5.6 U	< 0.16 U	1.1	< 1.1 U
EHS-IA-122	EHS-062918-IA-122-OCC	Room 122	6/29/2018	Supplemental VI Assessment	1807029	< 3.1 U	< 1.9 U	< 0.63 U	< 0.55 U	< 0.65 U	< 0.21 U	< 2.2 U	< 5.7 U	< 0.17 U	1.3	< 1.2 U

DRAFT

TABLE 5-1A
Indoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDDOH Matrix																
Sample Location	Sample Name	EHS Building Location	Sample Date	Sampling Program	Lab Report											
EHS-IA-164	EHS-062918-IA-164-OCC	Room 168	6/29/2018	Supplemental VI Assessment	1807026B	< 5.8 U	6.2	< 1.2 U	< 1.0 U	< 1.2 U	< 0.38 U	< 4.1 U	< 10 U	< 0.31 U	< 1.6 U	< 2.2 U
EHS-IA-127	EHS-062918-IA-127-OCC	Room 127	6/29/2018	Supplemental VI Assessment	1807029	< 3.0 U	2.0	< 0.61 U	< 0.54 U	< 0.63 U	< 0.20 U	< 2.2 U	< 5.5 U	< 0.16 U	1.3	< 1.1 U
EHS-IA-133	EHS-062918-IA-133-OCC	Room 133	6/29/2018	Supplemental VI Assessment	1807026B	< 3.0 U	6.3	< 0.61 U	< 0.54 U	< 0.63 U	< 0.20 U	< 2.2 U	< 5.5 U	< 0.16 U	1.2	< 1.1 U
EHS-IA-GYM	EHS-062918-IA-GYM-OCC	Gymnasium	6/29/2018	Supplemental VI Assessment	1807026B	< 3.2 U	< 1.9 U	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-KWING	EHS-062918-IA-K-OCC	K-Wing	6/29/2018	Supplemental VI Assessment	1807026B	< 3.2 U	5.8	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-139	EHS-062918-IA-139-OCC	Room 139	6/29/2018	Supplemental VI Assessment	1807026B	< 3.1 U	3.8	< 0.63 U	< 0.55 U	1.3	< 0.21 U	2.6	< 5.7 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-120	EHS-062918-IA-120-OCC	Room 120	6/29/2018	Supplemental VI Assessment	1807029	< 3.1 U	< 1.9 U	< 0.63 U	< 0.55 U	< 0.65 U	< 0.21 U	< 2.2 U	< 5.7 U	< 0.17 U	1.3	< 1.2 U
EHS-IA-120	EHS-062918-IA-120-OCC-DUP	Room 120	6/29/2018	Supplemental VI Assessment	1807029	< 3.1 U	< 1.9 U	< 0.62 U	< 0.55 U	< 0.65 U	< 0.21 U	< 2.2 U	< 5.6 U	< 0.16 U	1.3	< 1.2 U
EHS-IA-138A	EHS-062918-IA-138A-OCC	Room 138A	6/29/2018	Supplemental VI Assessment	1807026B	< 3.2 U	< 1.9 U	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	7.0	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-109	EHS-062918-IA-109-OCC	Room 109	6/29/2018	Supplemental VI Assessment	1807029	< 3.2 U	< 1.9 U	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-135	EHS-062918-IA-135-OCC	Room 135	6/29/2018	Supplemental VI Assessment	1807026B	< 3.2 U	2.2	< 0.65 U	< 0.57 U	< 0.67 U	< 0.22 U	< 2.3 U	< 5.9 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-CAF	EHS-062918-IA-CAF-OCC	Cafeteria	6/29/2018	Supplemental VI Assessment	1807029	< 3.2 U	< 1.9 U	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.3	< 1.2 U
EHS-IA-148	EHS-122718-IA-148-OCC	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	< 3.2 U	< 1.9 U	< 0.64 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U
EHS-IA-148	EHS-122718-IA-148-OCC-DUP	Room 148	12/27/2018	Supplemental VI Assessment	1812608A	< 3.2 U	< 1.9 U	< 0.63 U	< 0.56 U	< 0.66 U	< 0.21 U	< 2.3 U	< 5.8 U	< 0.17 U	1.2	< 1.2 U

DRAFT

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
"--" Analyte not reported
IAQAP - Indoor Air Quality Action Plan
1997 Lab method used: US EPA Method TO-2
2000 Lab method used: NYSDOH VOLA-CAN 3 and VOLA-CAN 4
2009-2018 Lab method used: TO-15/TO-15_SIM - VOCs
NA: Not available
Shaded cells identify indoor air samples collected subsequent to SSDS installation and located within the area of influence
NYSDOH Matrix Outcome - Mitigate
NYSDOH Matrix Outcome - Mitigate (classification is driven by the sub-slab vapor concentration)

Indoor air concentrations are shaded in accordance with the outcomes presented on NYSDOH Soil Vapor/Indoor Air Matrix Guidelines. Sample locations with an indoor air concentration equal to or greater than the applicable Matrix indoor-air concentration value are categorized as "Mitigate" and are shown in blue. Sample locations with an indoor air concentration below the maximum matrix concentration threshold may have a matrix outcome of "Mitigate" when the corresponding sub-slab vapor concentration meets or exceeds sub-slab vapor criteria and are shaded in dark grey. At these grey-shaded locations, the "Mitigate" classification is driven by the sub-slab vapor concentration rather than by the indoor air result itself, which reflects a detection below the Matrix indoor air threshold. Accordingly, the "Mitigate" designation at these locations should not be interpreted as indicating an indoor air quality concern, but rather reflects the conservative, protective design of the Matrix framework, which recommends mitigation based on sub-slab vapor concentrations.

DRAFT

TABLE 5-1B
Outdoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Acetone	Benzene	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chloroethane	Chloroform	Chloromethane
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	Type	EHS Building Location	Sample Date	Lab Report	--	--	--	--	--	--	--	--	--	--	--	--	--	--
OA-OUTSIDE	OUTSIDE-20000419-OA-OUTSIDE	Outdoor Air	Outside west of Gym	4/19/2000	NA	--	--	--	--	--	--	--	--	--	--	--	--	--	--
OA-OUTSIDE	OUTSIDE-20000523-OA-OUTSIDE	Outdoor Air	Outside west of Gym	5/23/2000	NA	3.6	1	--	--	--	< 1	--	1	--	--	--	--	< 1	1
OA-COURTYARD	)R-COURTYARD-20000831-OA-COU	Outdoor Air	Courtyard	8/31/2000	NA	6.6	--	--	--	--	--	--	--	--	--	--	--	--	< 1
OA-UR	ROOF-20091216-OA-DUP5	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	9.9	0.36	< 0.88	< 1	< 1.6	< 0.59	< 0.34	< 0.9	< 0.47	< 0.26	< 0.7	< 0.4	< 0.74	0.55
OA-UR	ROOF-20091216-OA-UR	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	9.9	0.39	< 0.88	< 1	< 1.6	< 0.59	< 0.34	< 0.9	< 0.47	< 0.26	< 0.7	< 0.4	0.6	0.57
SSHS-OA-01	SSHS-07-08-14-OA-01	Outdoor Air	Rooftop (Room 127)	7/8/2014	1407149R1	9.5 J	< 0.32 U	< 1.0 U	< 1.4 U	< 2.1 U	< 3.9 U	< 0.45 U	< 3.0 U	< 3.1 U	0.35	< 0.93 U	< 0.27 U	< 0.20 U	0.84
SSHS-OAON-01	SSHS-07-08-14-OAON-01	Outdoor Air	Rooftop (Room 127)	7/9/2014	1407148R1	9.4 J	0.28	< 0.85 U	< 1.1 U	< 1.7 U	< 3.2 U	< 0.36 U	< 2.4 U	< 2.6 UJ	0.36	< 0.76 U	< 0.22 U	0.16 J	0.79
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	5.5 J	0.26 U	0.86 U	1.1 U	1.7 U	3.2 U	0.37 U	2.4 U	2.6 U	--	0.76 U	--	--	--
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	--	0.26 U	--	--	--	--	--	--	--	0.35	--	0.22 U	0.16 U	0.79
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	5.5 J	< 0.26 U	< 0.86 U	< 1.1 U	< 1.7 U	< 3.2 U	< 0.37 U	< 2.4 U	< 2.6 U	0.35	< 0.76 U	< 0.22 U	< 0.16 U	0.79
OA-127	EHS-062818-Oa-127-UN	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	12	0.40 J	< 0.88 U	< 1.1 U	< 1.8 U	< 3.3 U	< 0.38 U	< 2.5 U	< 2.7 U	0.49	< 0.79 U	< 0.22 U	< 0.17 U	< 1.8 U
OA-127	EHS-062818-OA-127-UN-DUP	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	11	0.29 J	< 0.80 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.3 U	< 2.4 U	0.51	< 0.71 U	< 0.20 U	< 0.15 U	< 1.6 U
OA-K	EHS-062818-OA-K-UN	Outdoor Air	Rooftop (K-Wing)	6/28/2018	1807026B	13	0.26	< 0.79 U	< 1.0 U	< 1.6 U	< 3.0 U	< 0.34 U	< 2.2 U	< 2.4 U	0.52	< 0.70 U	< 0.20 U	0.17	< 1.6 U
OA-K	EHS-062918-OA-K-OCC	Outdoor Air	Rooftop (K-Wing)	6/29/2018	1807029	25	1.0	< 1.4 U	< 1.8 U	< 2.7 U	< 5.2 U	< 0.59 U	11	< 4.1 U	0.47	< 1.2 U	< 0.35 U	0.43	< 2.7 U
OA-127	EHS-062918-OA-127-OCC	Outdoor Air	Rooftop (Room 127)	6/29/2018	1807029	14	< 0.26 U	< 0.86 U	< 1.1 U	< 1.7 U	< 3.2 U	< 0.37 U	3.2	< 2.6 U	0.48	< 0.76 U	< 0.22 U	< 0.16 U	< 1.7 U
OA-M	EHS-083018-OA-M-UN	Outdoor Air	Rooftop (Music Wing)	8/30/2018	1808702	12	< 0.26 U	< 0.85 U	< 1.1 U	< 1.7 U	< 3.2 U	< 0.36 U	< 2.4 U	< 2.6 U	0.52	< 0.76 U	< 0.22 U	< 0.16 U	1.7
OA-M	1812608A_EHS-122718-OA-M-OCC	Outdoor Air	Rooftop (Music Wing)	12/27/2018	1812608A	4.9	0.34	< 0.76 U	< 0.98 U	< 1.5 U	< 2.8 U	< 0.32 U	< 2.2 U	< 2.3 U	0.46	< 0.68 U	< 0.19 U	< 0.14 U	< 1.5 U

DRAFT

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
NA: Not Available
Lab method used: TO-15/TO-15_SIM - VOCs

TABLE 5-1B
Outdoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						3-Chloropropene	Cyclohexane		Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene
						ug/m3	ug/m3		ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	Type	EHS Building Location	Sample Date	Lab Report	--	--	--	--	--	--	--	--	--	--	--	--	--	--
OA-OUTSIDE	OUTSIDE-20000419-OA-OUTSIDE	Outdoor Air	Outside west of Gym	4/19/2000	NA	--	--	--	--	--	--	--	--	--	--	--	< 0.1	< 0.1	--
OA-OUTSIDE	OUTSIDE-20000523-OA-OUTSIDE	Outdoor Air	Outside west of Gym	5/23/2000	NA	--	< 1	< 2	--	--	--	--	--	2.1	--	--	< 1	< 1	--
OA-COURTYARD	)R-COURTYARD-20000831-OA-COU	Outdoor Air	Courtyard	8/31/2000	NA	--	--	--	--	--	--	--	--	2.6	--	--	--	--	--
OA-UR	ROOF-20091216-OA-DUP5	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.48	< 0.52	< 2	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	9	< 0.62	< 0.62	0.73	< 0.6	< 0.6
OA-UR	ROOF-20091216-OA-UR	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.48	< 0.52	< 2	< 1.3	< 1.2	< 0.92	< 0.92	< 0.92	5.5	< 0.62	< 0.62	0.81	< 0.6	< 0.6
SSHS-OA-01	SSHS-07-08-14-OA-01	Outdoor Air	Rooftop (Room 127)	7/8/2014	1407149R1	< 3.2 U	< 0.70 U	< 2	< 1.7 U	< 0.31 U	< 1.2 U	< 1.2 U	< 0.24 U	2.0	< 0.16 U	< 0.16 U	< 0.080 U	< 0.16 U	< 0.80 U
SSHS-OAON-01	SSHS-07-08-14-OAON-01	Outdoor Air	Rooftop (Room 127)	7/9/2014	1407148R1	< 2.6 U	< 0.56 U	< 2	< 1.4 U	< 0.25 U	< 0.99 U	< 0.99 U	< 0.20 U	1.6	< 0.13 U	< 0.13 U	< 0.065 U	< 0.13 U	< 0.65 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	2.6 U	0.57 U	< 2	1.4 U	--	1 U	1 U	--	--	0.13 U	0.13 U	0.066 U	0.13 U	0.66 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	--	--		--	0.26 U	--	--	0.2 U	1.9	0.13 U	0.13 U	0.066 U	0.13 U	0.66 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	< 2.6 U	< 0.57 U	< 2	< 1.4 U	< 0.26 U	< 1.0 U	< 1.0 U	< 0.20 U	1.9	< 0.13 U	< 0.13 U	< 0.066 U	< 0.13 U	< 0.66 U
OA-127	EHS-062818-Oa-127-UN	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 2.7 U	< 0.59 U	< 2	< 1.4 U	< 0.26 U	< 1.0 U	< 1.0 U	< 0.20 U	2.4	< 0.14 U	< 0.14 U	< 0.068 U	< 0.14 U	< 0.68 U
OA-127	EHS-062818-OA-127-UN-DUP	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 2.4 U	< 0.53 U	< 2	< 1.3 U	< 0.24 U	< 0.92 U	< 0.92 U	< 0.18 U	2.4	< 0.12 U	< 0.12 U	< 0.061 U	< 0.12 U	< 0.61 U
OA-K	EHS-062818-OA-K-UN	Outdoor Air	Rooftop (K-Wing)	6/28/2018	1807026B	< 2.4 U	< 0.52 U	< 2	< 1.3 U	< 0.23 U	< 0.91 U	< 0.91 U	< 0.18 U	2.5	< 0.12 U	< 0.12 U	< 0.060 U	< 0.12 U	< 0.60 U
OA-K	EHS-062918-OA-K-OCC	Outdoor Air	Rooftop (K-Wing)	6/29/2018	1807029	< 4.2 U	2.7	2 to < 10	< 2.3 U	< 0.41 U	< 1.6 U	< 1.6 U	< 0.32 U	2.9	< 0.22 U	0.41	< 0.10 U	< 0.21 U	< 1.0 U
OA-127	EHS-062918-OA-127-OCC	Outdoor Air	Rooftop (Room 127)	6/29/2018	1807029	< 2.6 U	< 0.57 U	< 2	< 1.4 U	< 0.26 U	< 1.0 U	< 1.0 U	< 0.20 U	2.5	< 0.13 U	< 0.13 U	< 0.066 U	0.36	< 0.66 U
OA-M	EHS-083018-OA-M-UN	Outdoor Air	Rooftop (Music Wing)	8/30/2018	1808702	< 2.6 U	< 0.56 U	< 2	< 1.4 U	< 0.25 U	< 0.99 U	< 0.99 U	< 0.2 U	2.4	< 0.13 U	< 0.13 U	< 0.065 U	< 0.13 U	< 0.65 U
OA-M	1812608A_EHS-122718-OA-M-OCC	Outdoor Air	Rooftop (Music Wing)	12/27/2018	1812608A	< 2.3 U	< 0.5 U	< 2	< 1.2 U	< 0.22 U	< 0.88 U	< 0.88 U	< 0.18 U	2.2	< 0.12 U	< 0.12 U	< 0.058 U	< 0.12 U	< 0.58 U

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
NA: Not Available
Lab method used: TO-15/TO-15_SIM - VOCs

DRAFT

TABLE 5-1B
Outdoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	Ethylbenzene	4-Ethyltoluene	N-Heptane		Hexachlorobutadiene	N-Hexane	2-Hexanone	Isopropanol
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3		ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	Type	EHS Building Location	Sample Date	Lab Report	--	--	--	--	--	--	--	--	--	--	--	--	--	--
OA-OUTSIDE	OUTSIDE-20000419-OA-OUTSIDE	Outdoor Air	Outside west of Gym	4/19/2000	NA	--	--	--	--	--	3.9	--	--	1	< 6	--	1	--	--
OA-OUTSIDE	OUTSIDE-20000523-OA-OUTSIDE	Outdoor Air	Outside west of Gym	5/23/2000	NA	--	--	--	--	--	1.9	--	--	1.9	< 6	--	--	--	--
OA-COURTYARD	)R-COURTYARD-20000831-OA-COU	Outdoor Air	Courtyard	8/31/2000	NA	--	--	--	--	--	ND	< 0.66	< 0.75	< 0.62	< 6	< 1.6	< 0.54	< 1.2	< 0.37
OA-UR	ROOF-20091216-OA-DUP5	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	< 0.66	< 0.75	< 0.62	< 6	< 1.6	< 0.54	< 1.2	< 0.37
OA-UR	ROOF-20091216-OA-UR	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	2.9 J	< 0.18 U	< 0.99 U	< 0.83 U	< 6	< 11 U	< 0.71 U	< 4.1 U	< 2.5 U
SSHS-OA-01	SSHS-07-08-14-OA-01	Outdoor Air	Rooftop (Room 127)	7/8/2014	1407149R1	< 0.93 U	< 0.92 U	< 0.92 U	< 0.28 U	1.5	3.3 J	0.15	< 0.81 U	< 0.67 U	< 6	< 8.7 U	< 0.58 U	< 3.4 U	< 2.0 U
SSHS-OAON-01	SSHS-07-08-14-OAON-01	Outdoor Air	Rooftop (Room 127)	7/9/2014	1407148R1	< 0.76 U	< 0.74 U	< 0.74 U	< 0.23 U	< 0.59 U	1.6 UJ	0.14 U	0.82 U	0.68 U	< 6	8.8 U	0.58 U	3.4 U	2 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	0.77 U	0.75 U	0.75 U	--	0.6 U	< 1.6 UJ	< 0.14 U	< 0.82 U	< 0.68 U	< 6	< 8.8 U	< 0.58 U	< 3.4 U	< 2.0 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	--	--	--	0.23 U	--	3.8	< 0.15 U	< 0.84 U	< 0.70 U	< 6	< 9.1 UJ	0.66 J	< 3.5 U	< 2.1 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	< 0.77 U	< 0.75 U	< 0.75 U	< 0.23 U	< 0.60 U	3.3	< 0.13 U	< 0.76 U	< 0.63 U	< 6	< 8.2 UJ	< 0.54 UJ	< 3.2 U	< 1.9 U
OA-127	EHS-062818-Oa-127-UN	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 0.79 U	< 0.78 U	< 0.78 U	< 0.24 U	< 0.62 U	3.2	< 0.13 U	< 0.75 U	< 0.62 U	< 6	< 8.1 UJ	< 0.54 U	< 3.1 U	< 1.9 U
OA-127	EHS-062818-OA-127-UN-DUP	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 0.71 U	< 0.70 U	< 0.70 U	< 0.22 U	< 0.55 U	15	3.8	3.0	5.0	< 6	< 14 U	5.1	< 5.4 U	10
OA-K	EHS-062818-OA-K-UN	Outdoor Air	Rooftop (K-Wing)	6/28/2018	1807026B	< 0.70 U	< 0.69 U	< 0.69 U	< 0.21 U	< 0.55 U	12	< 0.14 U	< 0.82 U	< 0.68 U	< 6	< 8.8 U	< 0.58 U	< 3.4 U	2.1
OA-K	EHS-062918-OA-K-OCC	Outdoor Air	Rooftop (K-Wing)	6/29/2018	1807029	< 1.2 U	< 1.2 U	< 1.2 U	< 0.37 U	< 0.96 U	3.1	< 0.14 U	< 0.81 U	< 0.67 U	< 6	< 8.7 U	< 0.58 U	< 3.4 U	< 2 U
OA-127	EHS-062918-OA-127-OCC	Outdoor Air	Rooftop (Room 127)	6/29/2018	1807029	< 0.77 U	< 0.75 U	< 0.75 U	< 0.23 U	4.2	5.8 J	< 0.13 U	< 0.72 U	< 0.6 U	< 6	< 7.8 U	< 0.52 U	< 3 U	< 1.8 U
OA-M	EHS-083018-OA-M-UN	Outdoor Air	Rooftop (Music Wing)	8/30/2018	1808702	< 0.76 U	< 0.74 U	< 0.74 U	< 0.23 U	< 0.59 U									
OA-M	1812608A_EHS-122718-OA-M-OCC	Outdoor Air	Rooftop (Music Wing)	12/27/2018	1812608A	< 0.68 U	< 0.67 U	< 0.67 U	< 0.2 U	< 0.53 U									

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
NA: Not Available
Lab method used: TO-15/TO-15_SIM - VOCs

DRAFT

TABLE 5-1B
Outdoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Methylene Chloride	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene (Tetrachloroethylene) (PCE)	Tetrahydrofuran	Toluene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane (TCA)	1,1,2-Trichloroethane	Trichloroethene (Trichloroethylene) (TCE)	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon 113)
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	Type	EHS Building Location	Sample Date	Lab Report	--	--	--	--	--	--	--	--	--	--	--	--	--	--
OA-OUTSIDE	OUTSIDE-20000419-OA-OUTSIDE	Outdoor Air	Outside west of Gym	4/19/2000	NA	--	--	--	--	--	0.1	--	--	--	0.1	--	< 0.098	--	--
OA-OUTSIDE	OUTSIDE-20000523-OA-OUTSIDE	Outdoor Air	Outside west of Gym	5/23/2000	NA	1	< 1	--	--	--	< 1.5	--	1.4	--	< 1	--	< 1	1.1	1
OA-COURTYARD	)R-COURTYARD-20000831-OA-COU	Outdoor Air	Courtyard	8/31/2000	NA	--	--	--	--	--	< 1.5	--	1	--	< 1	--	< 1	2.1	< 1
OA-UR	ROOF-20091216-OA-DUP5	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.53	< 1.2	< 0.55	< 0.65	< 1	< 1	< 0.45	< 0.57	< 1.1	< 0.83	< 0.83	< 0.22	0.91	5.5
OA-UR	ROOF-20091216-OA-UR	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.53	< 1.2	< 0.55	< 0.65	< 1	< 1	< 0.45	0.5	< 1.1	< 0.83	< 0.83	< 0.22	1.7	6.3
SSHS-OA-01	SSHS-07-08-14-OA-01	Outdoor Air	Rooftop (Room 127)	7/8/2014	1407149R1	< 1.4 U	< 0.83 U	< 0.73 U	< 0.86 U	< 0.28 U	< 0.27 U	< 3.0 U	1.2	< 7.5 U	< 0.22 U	< 0.22 U	< 0.22 U	< 1.1 U	< 1.5 U
SSHS-OAON-01	SSHS-07-08-14-OAON-01	Outdoor Air	Rooftop (Room 127)	7/9/2014	1407148R1	< 1.1 U	< 0.67 U	< 0.59 U	< 0.70 U	< 0.22 U	< 0.22 U	< 2.4 U	1.2	< 6.1 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.92 U	< 1.2 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	1.2 U	0.68 U	0.6 U	0.71 U	0.23 U	0.22 U	2.4 U	0.3	6.2 U	0.18 U	0.18 U	0.18 U	0.93 U	1.3 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	--	--	0.6 U	--	0.23 U	0.22 U	--	0.3	--	0.18 U	0.18 U	0.18 U	--	--
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	< 1.2 U	< 0.68 U	< 0.60 U	< 0.71 U	< 0.23 U	< 0.22 U	< 2.4 U	0.30	< 6.2 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.93 U	< 1.3 U
OA-127	EHS-062818-Oa-127-UN	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 1.2 U	< 0.70 U	< 0.62 U	< 0.73 U	< 0.23 U	0.54	< 2.5 U	0.74	< 6.3 UJ	< 0.19 U	< 0.19 U	0.34 J	1.4 J	< 1.3 U
OA-127	EHS-062818-OA-127-UN-DUP	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 1.1 U	< 0.63 U	< 0.56 U	< 0.66 U	< 0.21 U	0.50	< 2.3 U	0.70	< 5.7 UJ	< 0.17 U	< 0.17 U	0.20 J	< 0.86 UJ	< 1.2 U
OA-K	EHS-062818-OA-K-UN	Outdoor Air	Rooftop (K-Wing)	6/28/2018	1807026B	< 1.0 U	< 0.62 U	< 0.55 U	< 0.65 U	< 0.21 U	0.29	< 2.2 U	0.50	< 5.6 UJ	< 0.16 U	< 0.16 U	< 0.16 U	< 0.85 U	< 1.2 U
OA-K	EHS-062918-OA-K-OCC	Outdoor Air	Rooftop (K-Wing)	6/29/2018	1807029	4.2	1.6	< 0.96 U	3.3	< 0.36 U	0.40	< 3.9 U	140	< 9.9 U	< 0.29 U	< 0.29 U	< 0.28 U	< 1.5 U	< 2.0 U
OA-127	EHS-062918-OA-127-OCC	Outdoor Air	Rooftop (Room 127)	6/29/2018	1807029	< 1.2 U	< 0.68 U	< 0.60 U	< 0.71 U	< 0.23 U	< 0.22 U	< 2.4 U	0.56	< 6.2 U	< 0.18 U	< 0.18 U	0.73	1.3	< 1.3 U
OA-M	EHS-083018-OA-M-UN	Outdoor Air	Rooftop (Music Wing)	8/30/2018	1808702	< 1.1 U	< 0.67 U	< 0.59 U	< 0.7 U	< 0.22 U	< 0.22 U	< 2.4 U	0.59	< 6.1 U	< 0.18 U	< 0.18 U	< 0.18 U	1.4	< 1.2 U
OA-M	1812608A_EHS-122718-OA-M-OCC	Outdoor Air	Rooftop (Music Wing)	12/27/2018	1812608A	< 1 U	< 0.6 U	< 0.53 U	< 0.63 U	< 0.2 U	< 0.2 U	< 2.2 U	0.27	< 5.4 U	< 0.16 U	< 0.16 U	< 0.16 U	1.2	< 1.1 U

DRAFT

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
NA: Not Available
Lab method used: TO-15/TO-15_SIM - VOCs

TABLE 5-1B
Outdoor Air Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	Vinyl Chloride	o-Xylene	m,p-Xylene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	Type	EHS Building Location	Sample Date	Lab Report	--	--	--	--	--	--
OA-OUTSIDE	OUTSIDE-20000419-OA-OUTSIDE	Outdoor Air	Outside west of Gym	4/19/2000	NA	--	--	--	--	0.2	0.7
OA-OUTSIDE	OUTSIDE-20000523-OA-OUTSIDE	Outdoor Air	Outside west of Gym	5/23/2000	NA	1	--	--	--	1	1
OA-COURTYARD	OR-COURTYARD-20000831-OA-COU	Outdoor Air	Courtyard	8/31/2000	NA	1	< 1	--	--	1	1
OA-UR	ROOF-20091216-OA-DUP5	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.75	< 0.75	< 0.71	< 0.1	< 0.66	< 1.3
OA-UR	ROOF-20091216-OA-UR	Outdoor Air	Rooftop (F-Wing)	12/16/2009	NA	< 0.75	< 0.75	< 0.71	< 0.1	< 0.66	< 1.3
SSHS-OA-01	SSHS-07-08-14-OA-01	Outdoor Air	Rooftop (Room 127)	7/8/2014	1407149R1	< 0.99 U	< 0.99 U	< 4.7 U	< 0.052 U	0.20	0.61
SSHS-OAON-01	SSHS-07-08-14-OAON-01	Outdoor Air	Rooftop (Room 127)	7/9/2014	1407148R1	< 0.81 U	< 0.81 U	< 3.8 U	< 0.042 U	0.20	0.58
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	0.82 U	0.82 U	3.9 U	0.042 U	0.14 U	0.29 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	--	--	--	0.042 U	0.14 U	0.29 U
SSHS-OA-02	SSHS-07-10-14-OA-O2	Outdoor Air	Rooftop (Auditorium)	7/10/2014	1407185R1	< 0.82 U	< 0.82 U	< 3.9 U	< 0.042 U	< 0.14 U	< 0.29 U
OA-127	EHS-062818-Oa-127-UN	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 0.84 U	< 0.84 U	< 4.0 U	< 0.044 U	< 0.15 U	< 0.30 U
OA-127	EHS-062818-OA-127-UN-DUP	Outdoor Air	Rooftop (Room 127)	6/28/2018	1807026B	< 0.76 U	< 0.76 U	< 3.6 U	< 0.039 U	< 0.13 U	0.28
OA-K	EHS-062818-OA-K-UN	Outdoor Air	Rooftop (K-Wing)	6/28/2018	1807026B	< 0.75 U	< 0.75 U	< 3.6 U	< 0.039 U	< 0.13 U	< 0.26 U
OA-K	EHS-062918-OA-K-OCC	Outdoor Air	Rooftop (K-Wing)	6/29/2018	1807029	3.9	< 1.3 U	7.5	< 0.068 U	4.9	12
OA-127	EHS-062918-OA-127-OCC	Outdoor Air	Rooftop (Room 127)	6/29/2018	1807029	< 0.82 U	< 0.82 U	< 3.9 U	< 0.042 U	< 0.14 U	< 0.29 U
OA-M	EHS-083018-OA-M-UN	Outdoor Air	Rooftop (Music Wing)	8/30/2018	1808702	< 0.81 U	< 0.81 U	< 3.8 U	< 0.042 U	< 0.14 U	0.29
OA-M	1812608A_EHS-122718-OA-M-OCC	Outdoor Air	Rooftop (Music Wing)	12/27/2018	1812608A	< 0.72 U	< 0.72 U	< 3.4 U	< 0.038 U	< 0.13 U	< 0.26 U

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
NA: Not Available
Lab method used: TO-15/TO-15_SIM - VOCs

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
						ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices						Matrix A			
						60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 to <1 ug/m3 - Matrix Outcome = Monitor 6 to <60 ug/m3 and indoor air <0.2 ug/m3- Matrix Outcome = NFA <6 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <1 ug/m3- Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location				
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report					
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	0.2 to <1	150	--	< 1	< 1
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	<0.2	14	--	< 1	< 1
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	>1	325	--	2.6	1.1
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	0.2 to <1	170	--	--	--
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	0.2 to <1	97	< 0.96	< 0.6	< 0.6
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	<0.2	28	< 0.96	240	< 0.6
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	<0.2	< 0.82	< 0.96	< 0.6	< 0.6
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	<0.2	< 0.82	< 0.96	< 0.6	< 0.6
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	<0.2	0.71	< 0.96	< 0.6	< 0.6
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	>1	< 0.82	< 0.96	< 0.6	< 0.6
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	>1	460	< 0.96	1.2	3.2
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	>1	2100	< 0.96	< 0.6	300
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	<0.2	< 0.82	< 0.96	< 0.6	< 0.6
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	<0.2	< 0.82	< 0.96	< 0.6	< 0.6
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	0.2 to <1	1.2	< 0.96	< 0.6	< 0.6
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	>1	4.2	< 0.96	< 0.6	< 0.6
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	<0.2	3.1	< 0.96	< 0.6	< 0.6
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	<0.2	0.6	< 0.96	< 0.6	< 0.6
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	>1	39000	< 140 U	*< 91 U*	2000
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	0.2 to <1	390	< 18 U	*< 11 U*	*< 11 U*

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

						Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
						ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices						Matrix A			
						60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 to <1 ug/m3 - Matrix Outcome = Monitor 6 to <60 ug/m3 and indoor air <0.2 ug/m3- Matrix Outcome = NFA <6 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <1 ug/m3- Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location				
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report					
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	0.2 to <1	***< 6.2 U***	< 7.3 U	< 4.6 U	< 4.6 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	<0.2	< 12 U	< 14 U	< 9.0 U	< 9.0 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	<0.2	< 5.9 U	< 6.9 U	< 4.3 U	< 4.3 U
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	<0.2	2100	< 57 U	< 36 U	< 36 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	<0.2	< 59 U	< 69 U	< 44 U	< 44 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	<0.2	**< 62 U**	< 73 U	**< 46 U**	**< 46 U**
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	<0.2	< 24 U	< 29 U	< 18 U	< 18 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	<0.2	< 5.9 U	< 6.9 U	< 4.3 U	< 4.3 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	<0.2	< 6.0 U	< 7.1 U	< 4.5 U	< 4.5 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	0.2 to <1	7300	< 28 U	***< 18 U***	83
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	<0.2	7200	< 28 U	< 17 U	74
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	<0.2	11	< 7.2 U	< 4.5 U	< 4.5 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	0.2 to <1	< 63 U	< 74 U	***< 46 U***	***< 46 U***
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	<0.2	7.3	< 7.2 U	< 4.5 U	< 4.5 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	<0.2	< 6.3 U	< 7.4 U	< 4.6 U	< 4.6 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	<0.2	< 6.4 U	< 7.5 U	< 4.7 U	< 4.7 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	<0.2	< 6.2 U	< 7.3 U	< 4.6 U	< 4.6 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	<0.2	< 6.0 U	< 7.0 U	< 4.4 U	< 4.4 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	<0.2	9.4	< 7.0 U	< 4.4 U	< 4.4 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	<0.2	< 12 U	< 14 U	< 9.1 U	< 9.1 U

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene
						ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices						Matrix A			
						60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 to <1 ug/m3 - Matrix Outcome = Monitor <6 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <1 ug/m3- Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location				
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report					
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	<0.2	14	< 7.4 U	***< 4.7 U***	***< 4.7 U***
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	<0.2 to 1	***< 24 U***	< 28 U	***< 18 U***	***< 18 U***
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	<0.2	< 6.1 U	< 7.1 U	< 4.5 U	< 4.5 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	<0.2	< 6.2 U	< 7.2 U	< 4.5 U	< 4.5 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	<0.2	11	< 7.3 U	< 4.6 U	< 4.6 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	0.2 to <1	< 6 U	< 7 U	< 4.4 U	< 4.4 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	<0.2	< 5.9 U	< 6.9 U	< 4.4 U	< 4.4 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	<0.2	< 6.3 U	< 7.3 U	< 4.6 U	< 4.6 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	<0.2	< 5.6 U	< 6.6 U	< 4.1 U	< 4.1 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	<0.2	< 12 U	< 14 U	< 8.9 U	< 8.9 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	0.2 to <1	160	< 6.9 U	< 4.4 U	< 4.4 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	>1	< 6 U	< 7 U	< 4.4 U	< 4.4 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	<0.2	< 5.9 U	< 6.9 U	< 4.4 U	< 4.4 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
						ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix B			
					1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 3 to <10 ug/m3 - Matrix Outcome = **Monitor** 100 to <1,000 ug/m3 and indoor air <3 ug/m3 - Matrix Outcome = NFA <100 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <100 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report				
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	<3	1	70	2.7
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	<3	< 1	3.2	55
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	<3	3.2	14	12
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	<3	--	25	14
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	<3	< 0.53	1.9	5
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	<3	< 0.53	54	23000
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	<3	< 0.53	< 1	1.2
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	<3	1.9	< 1	3.4
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	<3	1.5	< 1	< 0.83
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	<3	0.42	3.1	1.7
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	<3	3.4	7.4	16
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	<3	0.46	2.6	1.6
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	<3	< 0.53	< 1	< 0.83
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	<3	< 0.53	< 1	< 0.83
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	<3	< 0.53	1.2	5.7
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	<3	0.42	1.1	1.7
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	<3	0.88	< 1	0.83
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	<3	< 0.53	< 1	1.7
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	<3	< 800 U	< 160 U	< 120 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	<3	< 98 U	< 19 U	< 15 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
						ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix B			
					1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 3 to <10 ug/m3 - Matrix Outcome = **Monitor** 100 to <1,000 ug/m3 and indoor air <3 ug/m3 - Matrix Outcome = NFA <100 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <100 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report				
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	<3	< 40 U	< 7.8 U	< 6.3 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	<3	< 79 U	< 15 U	42
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	<3	< 38 U	34	17
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	<3	< 320 U	< 62 U	< 50 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	<3	< 380 U	< 75 U	< 60 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	<3	< 400 U	< 78 U	< 63 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	<3	< 160 U	< 31 U	< 25 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	<3	< 38 U	29	14
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	<3	< 39 U	7.7	< 6.1 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	<3	< 160 U	< 31 U	< 25 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	<3	< 150 U	< 30 U	< 24 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	<3	< 40 U	< 7.7 U	< 6.2 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	<3	< 410 U	< 80 U	< 64 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	<3	< 40 U	24	9.0
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	<3	< 41 U	< 8.0 U	< 6.4 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	<3	< 42 U	< 8.1 U	< 6.5 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	<3	< 40 U	< 7.8 U	40
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	<3	< 39 U	< 7.6 U	< 6.1 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	<3	< 39 U	16	< 6.1 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	<3	< 80 U	< 16 U	< 12 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

						Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
						ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix B			
					1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 3 to <10 ug/m3 - Matrix Outcome = **Monitor** 100 to <1,000 ug/m3 and indoor air <3 ug/m3 - Matrix Outcome = NFA <100 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <100 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report				
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	<3	< 41 U	< 8.0 U	6.6
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	<3	< 160 U	< 30 U	< 24 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	<3	< 39 U	< 7.7 U	< 6.2 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	<3	< 40 U	< 7.8 U	< 6.2 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	<3	< 40 U	< 7.9 U	< 6.4 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	<3	< 39 U	< 7.6 U	< 6.1 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	<3	< 38 U	< 7.5 U	< 6 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	<3	< 40 U	< 7.9 U	< 6.4 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	<3	< 36 U	< 7.1 U	< 5.7 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	<3	< 78 U	< 15 U	< 12 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	3 to <10	< 38 U	< 7.5 U	< 6 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	<3	< 39 U	14	< 6.1 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	<3	< 38 U	11	< 6 U

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Vinyl Chloride
						ug/m3
Soil Vapor Matrices					Matrix C	
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = **Monitor** **<6 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = Mitigate** <6 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = NFA	
					Indoor Air Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report		
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	<0.2	--
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	<0.2	--
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	<0.2	--
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	<0.2	--
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	<0.2	< 0.39
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	<0.2	0.78
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	<0.2	0.44
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	<0.2	0.42
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	<0.2	< 0.39
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	<0.2	< 0.39
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	<0.2	0.52
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	<0.2	0.55
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	<0.2	< 0.39
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	<0.2	< 0.39
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	<0.2	0.52
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	<0.2	0.39
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	<0.2	2.1
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	<0.2	< 0.39
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	<0.2	< 59 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	<0.2	< 7.2 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Vinyl Chloride
						ug/m3
Soil Vapor Matrices					Matrix C	
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = **Monitor** <6 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = NFA	
					Indoor Air Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report		
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	<0.2	< 3.0 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	<0.2	< 5.8 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	<0.2	< 2.8 U
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	<0.2	< 23 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	<0.2	< 28 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	<0.2	< 30 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	<0.2	< 12 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	<0.2	< 2.8 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	<0.2	< 2.9 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	<0.2	< 12 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	<0.2	< 11 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	<0.2	< 2.9 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	<0.2	< 30 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	<0.2	< 2.9 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	<0.2	< 3.0 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	<0.2	< 3.0 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	<0.2	< 3.0 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	<0.2	< 2.8 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	<0.2	< 2.8 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	<0.2	< 5.9 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

						Vinyl Chloride
						ug/m3
Soil Vapor Matrices						Matrix C
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = **Monitor** <6 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = NFA	
					Indoor Air Concentration Associated with Location	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report		
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	<0.2	< 3.0 U
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	<0.2	< 11 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	<0.2	< 2.9 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	<0.2	< 2.9 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	<0.2	< 3 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	<0.2	< 2.9 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	<0.2	< 2.8 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	<0.2	< 3 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	<0.2	< 2.7 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	<0.2	< 5.7 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	<0.2	< 2.8 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	<0.2	< 2.9 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	<0.2	< 2.8 U

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices						Matrix D						
						600 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 2 to <10 ug/m3 - Matrix Outcome = **Monitor** 60 to <600 ug/m3 and indoor air <2 ug/m3 - Matrix Outcome = NFA <60 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <60 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA							
					Indoor Air Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report								
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	<2	1.5	< 1	--	1	--	--	1
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	<2	1	< 1	--	1.4	--	--	1
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	<2	1.1	1	--	2.3	--	--	1
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	2 to <10	--	--	--	< 1	< 1	--	1
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	<2	0.81	< 0.52	2	3.7	0.85	0.95	2.2
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	<2	17	< 0.52	3.4	2.4	0.65	0.95	2
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	<2	0.42	< 0.52	0.53	0.6	< 0.75	< 0.71	0.62
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	<2	30	< 0.52	3.3	4.6	1.1	1.6	2.7
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	<2	1.8	< 0.52	1.7	0.75	< 0.75	< 0.71	0.66
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	<2	1.8	< 0.52	1.3	2.5	0.9	0.9	1
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	<2	1.4	2.6	0.97	4.1	1.4	1	0.88
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	<2	1.4	< 0.52	2.6	4.2	0.85	0.57	2.5
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	<2	0.75	< 0.52	1.9	2.3	0.65	< 0.71	1.8
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	<2	0.58	< 0.52	1.6	2.2	0.65	< 0.71	1.5
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	<2	1.2	< 0.52	2.8	5.3	1.2	< 0.71	2.6
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	<2	1.7	2.9	2.9	4.5	1.1	1	2.8
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	<2	1.9	< 0.52	1.5	1.6	< 0.75	0.66	1.1
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	<2	0.36	< 0.52	< 0.66	1.2	< 0.75	< 0.71	0.49
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	<2	< 74 U	< 79 U	< 100 U	< 110 U	< 110 U	< 110 U	< 100 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	<2	< 9.0 U	< 9.7 U	< 12 U	< 14 U	< 14 U	< 13 U	< 12 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices						Matrix D						
						600 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 2 to <10 ug/m3 - Matrix Outcome = **Monitor** 60 to <600 ug/m3 and indoor air <2 ug/m3 - Matrix Outcome = NFA <60 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <60 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA							
					Indoor Air Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report								
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	<2	< 3.7 U	< 4.0 U	< 5.0 U	< 5.7 U	< 5.7 U	< 5.4 U	< 5.0 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	2 to <10	< 7.3 U	< 7.8 U	9.9	< 11 U	< 11 U	< 11 U	< 9.9 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	<2	86	< 3.8 U	68	72	20	< 5.1 U	18
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	<2	< 29 U	< 31 U	< 40 U	< 45 U	< 45 U	< 42 U	< 40 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	<2	< 35 U	< 38 U	< 48 U	< 54 U	< 54 U	< 51 U	< 48 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	<2	< 37 U	< 40 U	< 50 U	< 57 U	< 57 U	< 54 U	< 50 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	<2	< 14 U	< 16 U	< 20 U	< 22 U	< 22 U	< 21 U	< 20 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	2 to <10	< 3.6 U	< 3.9 U	< 4.9 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.9 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	<2	< 14 U	< 16 U	< 20 U	< 22 U	< 22 U	< 21 U	< 20 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	<2	< 14 U	< 15 U	< 19 U	< 22 U	< 22 U	< 20 U	< 19 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	<2	3.8	6.1	< 4.9 U	< 5.6 U	< 5.6 U	7.4	5.0
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	<2	< 38 U	< 40 U	< 51 U	< 58 U	< 58 U	< 55 U	< 51 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	<2	< 3.6 U	< 3.9 U	< 5.0 U	< 5.6 U	< 5.6 U	< 5.3 U	< 5.0 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	<2	5.2	7.7	< 5.1 U	6.3	< 5.8 U	< 5.5 U	< 5.1 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	<2	7.7	7.3	< 5.2 U	8.6	< 5.9 U	< 5.6 U	5.6
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	<2	4.3	< 4.0 U	< 5.0 U	< 5.7 U	< 5.7 U	< 5.4 U	< 5.0 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	<2	< 3.6 U	< 3.8 U	< 4.8 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.8 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	<2	< 3.6 U	< 3.8 U	< 4.8 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.8 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	<2	< 7.3 U	< 7.9 U	< 10 U	< 11 U	< 11 U	< 11 U	< 10 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices						Matrix D						
						600 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 2 to <10 ug/m3 - Matrix Outcome = **Monitor** 60 to <600 ug/m3 and indoor air <2 ug/m3 - Matrix Outcome = NFA <60 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <60 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA							
					Indoor Air Concentration Associated with Location							
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report								
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	<2	< 3.8 U	< 4.1 U	< 5.1 U	< 5.8 U	< 5.8 U	< 5.5 U	< 5.1 U
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	2 to <10	< 14 U	< 15 U	< 20 U	< 22 U	< 22 U	< 21 U	< 20 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	<2	< 3.6 U	< 3.9 U	< 4.9 U	< 5.6 U	< 5.6 U	< 5.3 U	< 4.9 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	<2	< 3.6 U	32	< 5 U	< 5.6 U	< 5.6 U	< 5.3 U	< 5 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	<2	< 3.7 U	< 4 U	< 5 U	< 5.7 U	< 5.7 U	< 5.4 U	< 5 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	<2	< 3.6 U	28	< 4.9 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.9 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	2 to <10	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	<2	< 3.7 U	< 4 U	5.5	< 5.7 U	< 5.7 U	< 5.4 U	< 5 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	<2	< 3.3 U	18	26	< 5.1 U	< 5.1 U	< 4.9 U	25
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	<2	8	12	150	< 11 U	< 11 U	< 10 U	150
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	2 to <10	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	2 to <10	< 3.6 U	< 3.8 U	< 4.9 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.9 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	2 to <10	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						N-Heptane	N-Hexane	m,p-Xylene
						ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix E			
					2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 6 to <20 ug/m3 - Matrix Outcome = **Monitor** 200 to <2,000 ug/m3 and indoor air <6 ug/m3 - Matrix Outcome = NFA <200 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** <200 ug/m3 and indoor air <20 ug/m3 - Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report				
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	<6	1.2	< 1	1
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	<6	< 1	1	1
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	<6	1.9	1	1.1
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	<6	< 1	--	1
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	<6	4	< 0.54	6.6
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	<6	50	65	6.8
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	<6	< 0.62	< 0.54	1.7
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	<6	6.6	< 0.54	9.9
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	<6	0.67	< 0.54	0.62
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	<6	7.1	22	3.7
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	<6	5.3	6.8	2.1
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	<6	3.9	< 0.54	7.6
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	<6	3.2	3.2	4.9
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	<6	2.9	3.2	4
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	<6	9.3	8.1	9.5
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	<6	6.3	7.1	9.2
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	<6	25	54	4.1
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	<6	< 0.62	< 0.54	0.88
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	<6	< 94 U	< 81 U	< 100 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	<6	< 12 U	< 10 U	< 12 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

						N-Heptane	N-Hexane	m,p-Xylene
						ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix E			
					2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 6 to <20 ug/m3 - Matrix Outcome = **Monitor** 200 to <2,000 ug/m3 and indoor air <6 ug/m3 - Matrix Outcome = NFA <200 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** <200 ug/m3 and indoor air <20 ug/m3 - Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report				
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	<6	< 4.7 U	< 4.1 U	< 5.0 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	<6	< 9.3 U	< 8.0 U	< 9.9 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	<6	5.1	9.1	300
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	<6	< 37 U	< 32 U	< 40 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	<6	< 45 U	< 39 U	< 48 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	<6	< 47 U	< 41 U	< 50 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	<6	< 19 U	< 16 U	< 20 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	<6	< 4.5 U	< 3.8 U	< 4.8 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	6 to <20	< 4.6 U	< 4.0 U	< 4.9 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	<6	< 19 U	< 16 U	< 20 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	<6	< 18 U	< 15 U	< 19 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	<6	< 4.7 U	9.0	14
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	<6	< 48 U	< 41 U	< 51 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	<6	< 4.7 U	< 4.0 U	< 5.0 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	<6	15	10	9.4
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	<6	11	13	23
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	<6	< 4.7 U	< 4.1 U	64
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	<6	< 4.6 U	< 3.9 U	< 4.8 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	<6	< 4.6 U	< 3.9 U	< 4.8 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	<6	< 9.4 U	< 8.1 U	< 10 U

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

						N-Heptane	N-Hexane	m,p-Xylene
						ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix E			
					2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 6 to <20 ug/m3 - Matrix Outcome = **Monitor** 200 to <2,000 ug/m3 and indoor air <6 ug/m3 - Matrix Outcome = NFA <200 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** <200 ug/m3 and indoor air <20 ug/m3 - Matrix Outcome = NFA			
					Indoor Air Concentration Associated with Location			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report				
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	<6	< 4.8 U	4.6	11
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	6 to <20	< 18 U	< 16 U	< 20 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	<6	< 4.6 U	4.5	6.7
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	<6	< 4.7 U	43	< 5 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	<6	< 4.8 U	5.3	< 5 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	<6	< 4.6 U	26	< 4.9 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	<6	< 4.5 U	< 3.9 U	< 4.8 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	<6	< 4.8 U	< 4.1 U	< 5 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	<6	11	31	69
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	<6	28	32	410
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	<6	< 4.5 U	< 3.9 U	< 4.8 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	<6	< 4.6 U	< 3.9 U	< 4.9 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	<6	< 4.5 U	< 3.9 U	< 4.8 U

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Toluene	Acetone	Benzyl chloride	Bromodichloromethane	Bromoform
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix F					
					3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 10 to <50 ug/m3 - Matrix Outcome = **Monitor** 300 to <3,000 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA <300 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** <300 ug/m3 and indoor air <50 ug/m3 - Matrix Outcome = NFA					
					Indoor Air Concentration Associated with Location					
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report						
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	<10	1	16	--	--	--
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	<10	1.1	3.8	--	--	--
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	<10	1.5	9.4	--	--	--
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	<10	1	3.7	--	--	--
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	<10	19	27	< 0.88	< 1	< 1.6
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	<10	39	190	< 0.88	11	< 1.6
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	<10	5.8	22	< 0.88	< 1	< 1.6
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	<10	45	110	< 0.88	< 1	< 1.6
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	<10	2.9	25	< 0.88	< 1	< 1.6
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	<10	14	120	< 0.88	< 1	< 1.6
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	<10	7.1	51	< 0.88	12	< 1.6
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	<10	29	130	< 0.88	< 1	< 1.6
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	<10	31	190	< 0.88	< 1	< 1.6
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	<10	37	190	< 0.88	< 1	< 1.6
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	<10	21	47	< 0.88	< 1	< 1.6
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	<10	31	49	< 0.88	< 1	< 1.6
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	<10	16	77	< 0.88	2.7	< 1.6
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	<10	1.7	11	< 0.88	< 1	< 1.6
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	<10	< 87 U	< 550 U	< 120 U	< 150 U	< 240 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	<10	< 11 U	< 67 U	< 15 U	< 19 U	< 29 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Toluene	Acetone	Benzyl chloride	Bromodichloromethane	Bromoform
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix F					
					3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 10 to <50 ug/m3 - Matrix Outcome = **Monitor** 300 to <3,000 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA <300 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** <300 ug/m3 and indoor air <50 ug/m3 - Matrix Outcome = NFA					
					Indoor Air Concentration Associated with Location					
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report						
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	<10	< 4.4 U	28	< 6.0 U	< 7.7 U	< 12 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	<10	< 8.6 U	200	< 12 U	< 15 U	< 24 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	<10	49	210	< 5.7 U	< 7.3 U	< 11 U
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	<10	< 34 U	< 220 U	< 47 U	< 61 U	< 94 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	<10	< 41 U	< 260 U	< 57 U	< 74 U	< 110 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	<10	< 44 U	320	< 60 U	< 77 U	< 120 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	<10	< 17 U	< 110 U	< 24 U	< 30 U	< 47 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	<10	< 4.1 U	< 26 U	< 5.7 U	< 7.3 U	< 11 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	10 to <50	< 4.2 U	97	< 5.8 U	< 7.5 U	< 12 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	<10	< 17 U	< 110 U	< 24 U	< 30 U	< 47 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	<10	< 16 U	< 100 U	< 23 U	< 29 U	< 45 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	<10	35	45	< 5.9 U	< 7.6 U	< 12 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	<10	< 44 U	< 280 U	< 61 U	< 79 U	< 120 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	<10	< 4.3 U	< 27 U	< 5.9 U	< 7.7 U	< 12 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	<10	13	< 28 U	< 6.1 U	< 7.9 U	< 12 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	<10	24	< 28 U	< 6.2 U	< 8.0 U	< 12 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	<10	6.6	< 27 U	< 6.0 U	< 7.7 U	< 12 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	<10	< 4.2 U	30	< 5.8 U	< 7.5 U	< 12 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	<10	< 4.2 U	< 26 U	< 5.8 U	< 7.5 U	< 12 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	<10	< 8.7 U	530	< 12 U	< 15 U	< 24 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Toluene	Acetone	Benzyl chloride	Bromodichloromethane	Bromoform
						ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices					Matrix F					
					3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 10 to <50 ug/m3 - Matrix Outcome = **Monitor** 300 to <3,000 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA <300 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** <300 ug/m3 and indoor air <50 ug/m3 - Matrix Outcome = NFA					
					Indoor Air Concentration Associated with Location					
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report						
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	<10	19	36	< 6.1 U	< 7.9 U	< 12 U
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	10 to <50	< 17 U	< 110 U	< 23 U	< 30 U	< 46 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	<10	12	49	< 5.8 U	< 7.6 U	< 12 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	<10	< 4.3 U	120	< 5.9 U	< 7.7 U	< 12 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	<10	< 4.4 U	160	< 6 U	< 7.8 U	< 12 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	<10	< 4.2 U	140	< 5.8 U	< 7.5 U	< 12 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	<10	< 4.1 U	88	< 5.7 U	< 7.4 U	< 11 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	<10	< 4.4 U	160	< 6 U	< 7.8 U	< 12 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	<10	540	360	< 5.4 U	< 7 U	< 11 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	<10	2900	1400	< 12 U	< 15 U	< 23 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	10 to <50	10	81	< 5.7 U	< 7.4 U	< 11 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	<10	< 4.2 U	37	< 5.8 U	< 7.5 U	< 12 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	10 to <50	6.9	74	< 5.7 U	< 7.4 U	< 11 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane	Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices																	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report													
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	6.5	--	2.2	--	--	--	1	1.5	--	--	--	--	--
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	1.1	--	1	--	--	--	5.4	1	--	--	--	--	--
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	1	--	1.4	--	--	--	1000	1	--	--	--	--	--
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	--	--	--	--	--	--	--	< 1	--	--	--	--	--
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	< 0.59	< 0.34	3.1	0.92	< 0.7	< 0.4	1.9	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	< 0.59	< 0.34	< 0.9	15	< 0.7	3	79	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	< 0.59	< 0.34	0.9	< 0.47	< 0.7	< 0.4	27	1	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	< 0.59	< 0.34	210	2.3	< 0.7	2.8	4.8	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	< 0.59	< 0.34	13	1.2	< 0.7	< 0.4	5.3	0.69	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	< 0.59	< 0.34	6.4	3.9	< 0.7	< 0.4	15	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	< 0.59	< 0.34	3.2	3.5	< 0.7	2.2	1100	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	< 0.59	< 0.34	5.5	1.2	< 0.7	2.4	7.9	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	< 0.59	< 0.34	3.5	2.3	< 0.7	0.91	4.1	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	< 0.59	< 0.34	3.2	2.7	< 0.7	0.86	4	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	< 0.59	< 0.34	9	3.6	< 0.7	2.1	4.7	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	< 0.59	< 0.34	6.6	3.4	< 0.7	2.5	5	< 0.31	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	< 0.59	< 0.34	19	13	< 0.7	9.7	18	0.27	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	< 0.59	< 0.34	0.84	0.76	< 0.7	< 0.4	32	0.69	< 0.48	< 1.3	< 1.2	< 0.92	< 0.92
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	< 900 U	< 51 U	< 270 U	< 290 U	< 110 U	< 240 U	< 110 U	< 480 U	< 290 U	< 200 U	< 180 U	< 140 U	< 140 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	< 110 U	< 6.3 U	< 33 U	< 35 U	< 13 U	< 30 U	< 14 U	< 58 U	< 35 U	< 24 U	< 22 U	< 17 U	< 17 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane	Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices																	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report													
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	< 45 U	< 2.6 U	< 14 U	< 14 U	< 5.3 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.8 U	< 8.9 U	< 6.9 U	< 6.9 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	< 88 U	< 5.0 U	29	< 28 U	< 10 U	< 24 U	< 11 U	< 47 U	< 28 U	< 19 U	< 17 U	< 14 U	< 14 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	< 42 U	< 2.4 U	44	< 14 U	< 5.0 U	< 12 U	< 5.3 U	< 23 U	< 14 U	< 9.3 U	< 8.4 U	< 6.6 U	< 6.6 U
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	< 350 U	< 20 U	< 110 U	< 110 U	< 42 U	< 96 U	< 44 U	< 190 U	< 110 U	< 78 U	< 70 U	< 55 U	< 55 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	< 430 U	< 24 U	< 130 U	< 140 U	< 51 U	< 120 U	< 54 U	< 230 U	< 140 U	< 94 U	< 84 U	< 66 U	< 66 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	< 450 U	< 26 U	< 140 U	< 140 U	< 53 U	< 120 U	< 56 U	< 240 U	< 140 U	< 98 U	< 89 U	< 69 U	< 69 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	< 180 U	< 10 U	< 54 U	< 57 U	< 21 U	< 48 U	< 22 U	< 94 U	< 57 U	< 39 U	< 35 U	< 27 U	< 27 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	< 42 U	< 2.4 U	< 13 U	< 14 U	< 5.0 U	< 12 U	< 5.3 U	< 23 U	< 14 U	< 9.3 U	< 8.4 U	< 6.6 U	< 6.6 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	< 44 U	< 2.5 U	16	< 14 U	< 5.2 U	< 12 U	< 5.5 U	< 23 U	< 14 U	< 9.6 U	< 8.6 U	< 6.8 U	< 6.8 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	< 180 U	< 10 U	< 54 U	< 56 U	< 21 U	< 48 U	< 22 U	< 94 U	< 57 U	< 39 U	< 35 U	< 27 U	< 27 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	< 170 U	< 9.7 U	< 52 U	< 55 U	< 20 U	< 46 U	< 21 U	< 91 U	< 55 U	< 37 U	< 34 U	< 26 U	< 26 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	< 44 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.7 U	< 8.8 U	< 6.8 U	< 6.8 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	< 460 U	< 26 U	< 140 U	< 150 U	< 54 U	< 120 U	< 57 U	< 240 U	< 150 U	< 100 U	< 90 U	< 71 U	< 71 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	< 44 U	< 2.5 U	< 14 U	< 14 U	< 5.3 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.8 U	< 8.8 U	< 6.9 U	< 6.9 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	< 46 U	< 2.6 U	< 14 U	< 15 U	< 5.4 U	< 12 U	< 5.7 U	< 24 U	< 15 U	< 10 U	< 9.0 U	< 7.1 U	< 7.1 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	< 46 U	< 2.6 U	< 14 U	< 15 U	< 5.5 U	< 13 U	< 5.8 U	< 25 U	< 15 U	< 10 U	< 9.2 U	< 7.2 U	< 7.2 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	< 45 U	< 2.6 U	< 14 U	< 14 U	< 5.3 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.8 U	< 8.9 U	< 6.9 U	< 6.9 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	< 43 U	< 2.5 U	< 13 U	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.5 U	< 8.6 U	< 6.7 U	< 6.7 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	< 43 U	< 2.5 U	< 13 U	36	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.5 U	< 8.6 U	< 6.7 U	< 6.7 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	< 89 U	< 5.1 U	44	< 29 U	< 10 U	< 24 U	< 11 U	< 47 U	< 29 U	< 20 U	< 18 U	< 14 U	< 14 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane	Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene	1,3-Dichlorobenzene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices																	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report													
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	< 46 U	< 2.6 U	< 14 U	< 15 U	< 5.4 U	< 12 U	< 5.8 U	< 24 U	< 15 U	< 10 U	< 9.1 U	< 7.1 U	< 7.1 U
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	< 170 U	< 9.9 U	< 53 U	< 56 U	< 21 U	< 47 U	< 22 U	< 93 U	< 56 U	< 38 U	< 34 U	< 27 U	< 27 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	< 44 U	< 2.5 U	19	< 14 U	< 5.2 U	< 12 U	14	< 23 U	< 14 U	< 9.6 U	< 8.7 U	< 6.8 U	< 6.8 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	< 44 U	< 2.5 U	15	< 14 U	< 5.3 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.8 U	< 8.8 U	< 6.9 U	< 6.9 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	< 45 U	< 2.6 U	37	< 14 U	< 5.4 U	< 12 U	< 5.7 U	< 24 U	< 14 U	< 9.9 U	< 9 U	< 7 U	< 7 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	< 43 U	< 2.5 U	14	< 14 U	< 5.2 U	< 12 U	< 5.5 U	< 23 U	< 14 U	< 9.5 U	< 8.6 U	< 6.7 U	< 6.7 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	< 43 U	< 2.4 U	< 13 U	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.4 U	< 6.6 U	< 6.6 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	< 45 U	< 2.6 U	< 14 U	< 14 U	< 5.4 U	< 12 U	< 5.7 U	< 24 U	< 14 U	< 9.9 U	< 9 U	< 7 U	< 7 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	< 40 U	< 2.3 U	22	< 13 U	< 4.8 U	< 11 U	15	< 22 U	< 13 U	< 8.9 U	< 8 U	< 6.3 U	< 6.3 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	< 87 U	< 5 U	26 J	< 28 U	< 10 U	< 24 U	< 11 U	< 46 U	< 28 U	< 19 U	< 17 U	< 13 U	< 13 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	< 43 U	< 2.4 U	14	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.4 U	< 6.6 U	< 6.6 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	< 43 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	< 5.5 U	< 23 U	< 14 U	< 9.5 U	< 8.6 U	< 6.7 U	< 6.7 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	< 43 U	< 2.4 U	17	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.4 U	< 6.6 U	< 6.6 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane	1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices																	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report													
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	--	450	--	--	--	--	--	--	--	--	8.7	--	--
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	--	23	--	--	--	--	--	--	--	--	2.5	--	--
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	--	140	--	--	--	--	--	--	--	--	6.9	--	--
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	--	280	--	--	--	--	--	--	--	--	< 1	--	--
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	0.67	33	< 0.62	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	< 0.75	< 1.6
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	1.2	3600	85	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	0.6	< 1.6
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	< 0.92	4.5	< 0.62	< 0.62	0.52	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	3	< 0.75	< 1.6
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	< 0.92	87	2.1	0.95	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	1.6	< 1.6
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	< 0.92	48	0.62	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	2.7	< 0.75	< 1.6
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	< 0.92	980	< 0.62	0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	8.8	0.75	< 1.6
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	0.67	110	1.7	0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	1.4	< 1.6
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	< 0.92	1800	1.3	0.45	21	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	1	< 1.6
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	< 0.92	460	0.7	0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	7.2	0.8	< 1.6
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	< 0.92	420	0.62	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	8.3	0.7	< 1.6
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	1.1	270	1.1	0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	1.3	< 1.6
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	< 0.92	360	1.7	0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	1.2	< 1.6
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	< 0.92	65	3.9	0.53	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	< 0.75	< 1.6
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	< 0.92	4.7	1.7	< 0.62	< 0.6	< 0.7	< 0.69	< 0.69	< 1.1	< 1.1	ND	< 0.75	< 1.6
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	< 140 U	1100	< 93 U	< 93 U	170	< 110 U	< 100 U	< 100 U	< 160 U	< 330 U	< 170 U	< 110 U	< 980 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	< 17 U	3600	< 11 U	< 11 U	< 11 U	< 13 U	< 13 U	< 13 U	< 20 U	< 41 U	< 21 U	< 14 U	< 120 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane	1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices																	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report													
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	< 6.9 U	79	< 4.7 U	< 4.7 U	< 4.6 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.1 U	< 17 U	< 8.7 U	< 5.7 U	< 49 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	< 14 U	2800	< 9.2 U	< 9.2 U	< 9.0 U	< 10 U	< 10 U	< 10 U	< 16 U	< 33 U	64	< 11 U	< 97 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	< 6.6 U	140	< 4.4 U	< 4.4 U	< 4.3 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.6 U	< 16 U	100	67	< 47 U
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	< 55 U	13000	< 37 U	< 37 U	< 36 U	< 42 U	< 41 U	< 41 U	< 64 U	< 130 U	< 68 U	< 45 U	< 390 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	< 66 U	12000	< 44 U	< 44 U	< 44 U	< 51 U	< 50 U	< 50 U	< 77 U	< 160 U	< 83 U	< 54 U	< 470 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	< 69 U	18000	< 47 U	< 47 U	< 46 U	< 53 U	< 52 U	< 52 U	< 81 U	< 170 U	< 87 U	< 57 U	< 490 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	< 27 U	6900	< 18 U	< 18 U	< 18 U	< 21 U	< 21 U	< 21 U	< 32 U	< 66 U	< 34 U	< 22 U	< 190 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	< 6.6 U	26	< 4.4 U	< 4.4 U	< 4.3 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.6 U	< 16 U	8.5	< 5.4 U	< 47 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	< 6.8 U	120	< 4.6 U	< 4.6 U	< 4.5 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.9 U	< 16 U	63	< 5.5 U	< 48 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	< 27 U	3100	< 18 U	< 18 U	22	< 21 U	< 21 U	< 21 U	< 32 U	< 65 U	< 34 U	< 22 U	< 190 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	< 26 U	2900	< 18 U	< 18 U	22	< 20 U	< 20 U	< 20 U	< 31 U	< 63 U	< 33 U	< 22 U	< 190 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	< 6.8 U	620	< 4.6 U	< 4.6 U	< 4.5 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.0 U	< 16 U	51	< 5.6 U	< 49 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	< 71 U	22000	< 48 U	< 48 U	< 46 U	< 54 U	< 53 U	< 53 U	< 82 U	< 170 U	< 88 U	< 58 U	< 500 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	< 6.9 U	1400	< 4.6 U	< 4.6 U	< 4.5 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.0 U	< 16 U	< 8.6 U	< 5.6 U	< 49 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	< 7.1 U	270	< 4.8 U	< 4.8 U	< 4.6 U	< 5.4 U	< 5.3 U	< 5.3 U	< 8.2 U	< 17 U	< 8.8 U	< 5.8 U	< 50 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	< 7.2 U	880	< 4.8 U	< 4.8 U	< 4.7 U	< 5.5 U	< 5.4 U	< 5.4 U	< 8.4 U	< 17 U	< 9.0 U	6.3	< 51 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	< 6.9 U	58	< 4.7 U	< 4.7 U	< 4.6 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.1 U	< 17 U	< 8.7 U	< 5.7 U	< 49 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	< 6.7 U	540	< 4.5 U	< 4.5 U	< 4.4 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.8 U	< 16 U	< 8.4 U	< 5.5 U	< 48 U
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	< 6.7 U	14	< 4.5 U	< 4.5 U	< 4.4 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.8 U	< 16 U	< 8.4 U	< 5.5 U	< 48 U
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	< 14 U	48	< 9.3 U	< 9.3 U	< 9.1 U	< 11 U	< 10 U	< 10 U	< 16 U	< 33 U	< 17 U	< 11 U	< 98 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane	1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices																	
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report													
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	< 7.1 U	20	< 4.8 U	< 4.8 U	< 4.7 U	< 5.4 U	< 5.4 U	< 5.4 U	< 8.2 U	< 17 U	43	< 5.8 U	< 50 U
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	< 27 U	5000	< 18 U	< 18 U	< 18 U	< 21 U	< 20 U	< 20 U	< 31 U	< 65 U	< 34 U	< 22 U	< 190 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	< 6.8 U	33	< 4.6 U	< 4.6 U	< 4.5 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.9 U	< 16 U	< 8.5 U	< 5.6 U	< 48 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	< 6.9 U	12	< 4.6 U	< 4.6 U	< 4.5 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8 U	< 16 U	210	< 5.6 U	< 49 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	< 7 U	240	< 4.7 U	< 4.7 U	< 4.6 U	< 5.4 U	< 5.3 U	< 5.3 U	< 8.1 U	< 17 U	130	< 5.7 U	< 50 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	< 6.7 U	1100	< 4.5 U	< 4.5 U	< 4.4 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.8 U	< 16 U	130	< 5.5 U	< 48 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	< 6.6 U	630	< 4.4 U	< 4.4 U	< 4.4 U	< 5.1 U	< 5 U	< 5 U	< 7.7 U	< 16 U	160	< 5.4 U	< 47 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	< 7 U	770	< 4.7 U	< 4.7 U	< 4.6 U	< 5.4 U	< 5.3 U	< 5.3 U	< 8.1 U	< 17 U	80	< 5.7 U	< 50 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	< 6.3 U	13	< 4.2 U	< 4.2 U	< 4.1 U	< 4.8 U	< 4.7 U	< 4.7 U	< 7.3 U	< 15 U	210	6.6	< 44 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	< 13 U	11	< 9.1 U	< 9.1 U	< 8.9 U	< 10 U	< 10 U	< 10 U	< 16 U	< 32 U	810	42	< 96 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	< 6.6 U	810	< 4.4 U	< 4.4 U	< 4.4 U	< 5.1 U	< 5 U	< 5 U	< 7.7 U	< 16 U	86	< 5.4 U	< 47 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	< 6.7 U	8.9	< 4.5 U	< 4.5 U	< 4.4 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.8 U	< 16 U	77	< 5.5 U	< 48 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	< 6.6 U	17	< 4.4 U	< 4.4 U	< 4.4 U	< 5.1 U	< 5 U	< 5 U	< 7.7 U	< 16 U	120	< 5.4 U	< 47 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon 113)
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices															
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report											
SUB-SLAB BOILER ROOM	BOILERROOM-20000523-SV-BR	Boiler Room	5/23/2000	Unknown	--	--	1	--	--	--	--	--	--	50	16
SUB-SLAB GYM STORAGE	GYM-STOREROOM-20000523-SV-GYMSTOREROOM	Gym Storage Room	5/23/2000	Unknown	--	--	< 1	--	--	--	--	--	--	2.1	27
SUB-SLAB POOL FILTER ROOM	POOL-FILTERROOM-20000523-SV-PF	Pool Filter Room	5/23/2000	Unknown	--	--	1	--	--	--	--	--	--	7.3	1000
SUB-SLAB RM151A	BSMT-SCIROOM-20000831-SV-BASEMANTSCIRM	Room 151A	8/31/2000	Unknown	--	--	--	--	--	--	--	--	--	8.9	65
SV-BR	BOILERROOM-20091216-SV-BR	Boiler Room	12/16/2009	Unknown	< 1.2	2.9	0.71	< 0.55	1.1	< 1	< 0.45	< 1.1	< 0.83	4.2	3.1
SV-GYM-EAST	GYM-EAST-20091216-SV-GYMEAST	East Side of Gym	12/16/2009	Unknown	< 1.2	< 0.37	7	< 0.55	2.3	< 1	< 0.45	< 1.1	< 0.83	21	1100
SV-GS	GYM-STOREROOM-20091216-SV-GS	Gym Storage Room	12/16/2009	Unknown	< 1.2	2.2	2.2	< 0.55	1	< 1	< 0.45	< 1.1	< 0.83	1.5	36
SV-HALL-113	HALL-RM113B-20091216-SV-HALL113	Hallway Behind Room 113B	12/16/2009	Unknown	< 1.2	< 0.37	1.4	< 0.55	0.87	< 1	< 0.45	< 1.1	< 0.83	1.3	3
SV-GL	HALL-OUTGYM-20091216-SV-GL	Hallway Outside of Gym	12/16/2009	Unknown	< 1.2	3.1	0.66	< 0.55	16	< 1	< 0.45	< 1.1	< 0.83	0.86	6.6
SV-LIB	LIBRARY-20091216-SV-LIB	Library	12/16/2009	Unknown	< 1.2	2.9	2	< 0.55	0.43	< 1	< 0.45	< 1.1	< 0.83	1	1.6
SV-PF	POOL-FILTERROOM-20091216-SV-PF	Pool Filter Room	12/16/2009	Unknown	< 1.2	3.2	0.54	< 0.55	2.1	< 1	< 0.45	< 1.1	< 0.83	3.8	660
SV-127	RM-127-20091216-SV-127	Room 127	12/16/2009	Unknown	< 1.2	< 0.37	1.8	< 0.55	1.3	< 1	< 0.45	< 1.1	< 0.83	0.86	< 1.2
SV-WS	RM-139C-20091216-SV-DUP5	Room 139C	12/16/2009	Unknown	< 1.2	9.5	0.58	< 0.55	< 1.2	< 1	< 0.45	< 1.1	< 0.83	1.3	6.2
SV-WS	RM-139C-20091216-SV-WS	Room 139C	12/16/2009	Unknown	< 1.2	< 0.37	0.54	< 0.55	0.58	< 1	< 0.45	< 1.1	< 0.83	1.3	3.5
SV-NR	RM-146-20091216-SV-NR	Room 146	12/16/2009	Unknown	3	< 0.37	< 1.2	< 0.55	1.9	< 1	< 0.45	< 1.1	< 0.83	34	17
SV-151A	RM-151A-20091216-SV-151A	Room 151A	12/16/2009	Unknown	< 1.2	< 0.37	1.3	< 0.55	1.2	< 1	< 0.45	< 1.1	< 0.83	1.9	33
SV-WM	RM-159-20091216-SV-WM	Room 159	12/16/2009	Unknown	< 1.2	< 0.37	7.2	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	0.69	4.8
SV-GYM-WEST	GYM-WEST-20091216-SV-GYMWEST	West Side of Gym	12/16/2009	Unknown	< 1.2	2.8	0.92	< 0.55	< 0.65	< 1	< 0.45	< 1.1	< 0.83	0.86	39
SSHS-03-SS	SSHS-07-13-14-03-SS	Room 127	7/13/2014	1407264	< 380 U	< 230 U	< 94 U	< 83 U	< 98 U	< 160 U	< 68 U	< 680 U	< 120 U	< 130 U	< 180 U
SSHS-04-SS	SSHS-07-13-14-04-SS	Room 125	7/13/2014	1407264	< 46 U	< 28 U	< 12 U	< 10 U	< 12 U	< 19 U	< 8.3 U	< 84 U	< 15 U	< 16 U	< 22 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon 113)
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices															
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report											
SSHS-08-SS	SSHS-07-13-14-08-SS	Room 129 (Guidance)	7/13/2014	1407264	< 19 U	< 11 U	< 4.7 U	< 4.2 U	< 4.9 U	< 7.9 U	< 3.4 U	< 34 U	< 6.3 U	< 6.5 U	< 8.8 U
SSHS-01-SS	SSHS-07-13-14-01-SS	Hallway Near Main Entrance	7/13/2014	1407264	< 37 U	< 22 U	< 9.3 U	< 8.2 U	530	< 16 U	< 6.7 U	< 68 U	< 12 U	< 13 U	< 17 U
SSHS-09-SS	SSHS-07-13-14-09-SS	Hallway Outside Library	7/13/2014	1407264	< 18 U	< 11 U	< 4.5 U	< 3.9 U	330	< 7.5 U	< 3.2 U	< 32 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-05-SS	SSHS-07-13-14-05-SS	Room 124	7/13/2014	1407264	< 150 U	< 89 U	< 37 U	< 33 U	< 39 U	< 62 U	< 27 U	< 270 U	< 50 U	< 51 U	< 70 U
SSHS-06-SS	SSHS-07-13-14-06-SS	Room 122	7/13/2014	1407264	< 180 U	< 110 U	< 45 U	< 40 U	< 47 U	< 76 U	< 32 U	< 330 U	< 60 U	< 62 U	< 84 U
SSHS-07-SS	SSHS-07-14-14-07-SS	Room 120	7/14/2014	1407264	< 190 U	< 110 U	60	< 42 U	< 49 U	< 79 U	< 34 U	< 340 U	< 63 U	< 65 U	< 88 U
SSHS-12-SS	SSHS-07-14-14-12-SS	Room 116	7/14/2014	1407264	< 75 U	< 45 U	< 19 U	< 16 U	< 19 U	< 31 U	< 13 U	< 140 U	< 25 U	< 26 U	< 35 U
SSHS-11-SS	SSHS-07-14-14-11-SS	Room 115	7/14/2014	1407264	< 18 U	< 11 U	< 4.5 U	< 3.9 U	< 4.7 U	< 7.5 U	< 3.2 U	< 32 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-10-SS	SSHS-07-14-14-10-SS	Room 101	7/14/2014	1407264	< 18 U	< 11 U	< 4.6 U	< 4.0 U	< 4.8 U	< 7.7 U	< 3.3 U	< 33 U	< 6.1 U	17	< 8.6 U
SSHS-02-SS	SSHS-07-14-14-02-SS	Room 130	7/14/2014	1407264	< 74 U	< 45 U	< 18 U	< 16 U	< 19 U	< 31 U	< 13 U	< 130 U	< 25 U	< 26 U	< 35 U
SSHS-02-SS	SSHS-07-14-14-02-SS-DUP	Room 130	7/14/2014	1407264	< 72 U	< 43 U	< 18 U	< 16 U	< 19 U	< 30 U	< 13 U	< 130 U	< 24 U	< 25 U	< 34 U
SSHS-14-SS	SSHS-07-14-14-14-SS	Room 106	7/14/2014	1407264	< 19 U	< 11 U	< 4.7 U	< 4.1 U	< 4.8 U	< 7.8 U	< 3.4 U	< 34 U	< 6.2 U	< 6.4 U	< 8.7 U
SSHS-15-SS	SSHS-07-14-14-15-SS	Room 104	7/14/2014	1407264	< 190 U	< 120 U	< 48 U	< 42 U	< 50 U	< 81 U	< 35 U	< 350 U	< 64 U	< 66 U	< 90 U
SSHS-13-SS	SSHS-07-14-14-13-SS	Room 111	7/14/2014	1407264	< 19 U	< 11 U	< 4.7 U	< 4.1 U	< 4.9 U	< 7.9 U	< 3.4 U	< 34 U	< 6.2 U	< 6.4 U	< 8.8 U
SSHS-16-SS	SSHS-07-14-14-16-SS	Back Stage	7/14/2014	1407264	< 19 U	< 12 U	< 4.8 U	< 4.2 U	11	< 8.1 U	< 3.5 U	< 35 U	< 6.4 U	< 6.6 U	< 9.0 U
SSHS-19-SS	SSHS-07-14-14-19-SS	Room 138A	7/14/2014	1407264	< 20 U	< 12 U	< 4.9 U	< 4.3 U	< 5.1 U	< 8.2 U	< 3.5 U	< 35 U	< 6.5 U	< 6.7 U	< 9.2 U
SSHS-20-SS	SSHS-07-14-14-20-SS	Room 142 (Wellness Ctr)	7/14/2014	1407264	< 19 U	< 11 U	14	< 4.2 U	< 4.9 U	< 7.9 U	< 3.4 U	< 34 U	< 6.3 U	< 6.5 U	< 8.8 U
SSHS-17-SS	SSHS-07-14-14-17-SS	Hallway Outside Room 136A	7/14/2014	1407264	< 18 U	< 11 U	< 4.6 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	13
SSHS-21-SS	SSHS-07-14-14-21-SS	Room 145 Nurses Office	7/14/2014	1407264	< 18 U	< 11 U	< 4.6 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	15
SSHS-22-SS	SSHS-07-14-14-22-SS	Room 171 (Aux Gym)	7/14/2014	1407264	< 38 U	170	2000	< 8.3 U	< 9.8 U	< 16 U	< 6.8 U	< 68 U	< 12 U	< 13 U	< 18 U

DRAFT

TABLE 5-2
Sub-slab Vapor Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					2-Hexanone	Isopropanol	Methyl Isobutyl Ketone	Methyl T-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon 113)
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Soil Vapor Matrices															
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report											
SSHS-21-SS	SSHS-07-14-14-21-SS-DUP	Room 145 Nurses Office	7/14/2014	1407264	< 19 U	< 12 U	< 4.8 U	< 4.2 U	< 5.0 U	< 8.1 U	< 3.5 U	< 35 U	< 6.4 U	< 6.6 U	16
SSHS-18-SS	SSHS-07-14-14-18-SS	Custodian's Storage	7/14/2014	1407264	< 74 U	< 44 U	< 18 U	< 16 U	< 19 U	< 31 U	< 13 U	< 130 U	< 24 U	130	< 34 U
SSHS-23-SS	SSHS-07-14-14-23-SS	Room 156 (Girls Locker Room)	7/14/2014	1407264	< 18 U	< 11 U	< 4.6 U	< 4.1 U	< 4.8 U	< 7.8 U	< 3.3 U	< 34 U	< 6.2 U	< 6.3 U	< 8.7 U
SS-103	EHS-062818-SS-103-UN	Room 103	6/28/2018	1807026A	< 19 U	< 11 U	< 4.7 U	< 16 U	< 4.9 U	< 7.9 U	< 3.4 U	< 34 U	< 6.2 U	< 6.4 U	< 8.8 U
SS-109	EHS-062818-SS-109-UN	Room 109	6/28/2018	1807026A	< 19 U	23	8	< 17 U	< 5 U	< 8 U	< 3.4 U	< 34 U	< 6.4 U	< 6.5 U	< 8.9 U
SS-120	EHS-062818-SS-120-UN	Room 120	6/28/2018	1807026A	< 18 U	17	23	< 16 U	< 4.8 U	< 7.7 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	< 8.6 U
SS-122	EHS-062818-SS-122-UN	Room 122	6/28/2018	1807026A	< 18 U	< 11 U	10	< 16 U	< 4.7 U	< 7.6 U	< 3.2 U	< 33 U	< 6 U	< 6.2 U	< 8.4 U
SS-133	EHS-062818-SS-133-UN	Room 133	6/28/2018	1807026A	< 19 U	< 11 U	< 4.8 U	< 17 U	150	< 8 U	< 3.4 U	< 34 U	< 6.4 U	< 6.5 U	< 8.9 U
SS-135	EHS-062818-SS-135-UN	Room 135	6/28/2018	1807026A	< 17 U	11	< 4.3 U	< 15 U	< 4.4 U	< 7.2 U	< 3.1 U	< 31 U	< 5.7 U	< 5.9 U	< 8 U
SS-135	EHS-062818-SS-135-UN-DUP	Room 135	6/28/2018	1807026A	< 37 U	< 22 U	< 9.2 U	< 32 U	< 9.6 U	< 15 U	< 6.6 U	< 67 U	< 12 U	25	< 17 U
SS-148	EHS-062818-SS-148-UN	Room 148	6/28/2018	1807026A	< 18 U	< 11 U	< 4.5 U	< 16 U	< 4.7 U	< 7.6 U	< 3.2 U	< 33 U	< 6 U	< 6.2 U	< 8.4 U
SS-151	EHS-062818-SS-151-UN	Room 151A	6/28/2018	1807026A	< 18 U	< 11 U	< 4.6 U	< 16 U	< 4.8 U	< 7.7 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	< 8.6 U
SS-164	EHS-062818-SS-164-UN	Room 168	6/28/2018	1807026A	< 18 U	< 11 U	< 4.5 U	< 16 U	< 4.7 U	< 7.6 U	< 3.2 U	< 33 U	< 6 U	< 6.2 U	< 8.4 U

DRAFT

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
"--" Analyte not reported
2000 Lab method used: NYSDOH VOLA-CAN 3 and VOLA-CAN 4
2009-2018 Lab method used: TO-15/TO-15_SIM - VOCs
NA: Not available
Shaded cells identify indoor air samples collected subsequent to SSDS installation and located within the area of influence
NYSDOH Matrix Outcome - Mitigate
NFA: No Further Action

Sub-slab vapor concentrations are shaded in accordance with the outcomes presented on NYSDOH Soil Vapor/Indoor Air Matrix Guidelines. Sample locations with a sub-slab vapor concentration equal to or greater than the applicable Matrix indoor-air concentration value are categorized as "Mitigate" and are shown in blue.

Samples with detection limits exceeding applicable monitor guidance concentrations are shown in **orange.**

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene		Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
						ug/m3	ug/m3	ug/m3	ug/m3		ug/m3	ug/m3	ug/m3
					Matrix A					Matrix B			
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 to <1 ug/m3 - Matrix Outcome = **Monitor** 6 to <60 ug/m3 and indoor air <0.2 ug/m3- Matrix Outcome = NFA <6 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <1 ug/m3- Matrix Outcome = NFA					1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 3 to <10 ug/m3 - Matrix Outcome = **Monitor** 100 to <1,000 ug/m3 and indoor air <3 ug/m3 - Matrix Outcome = NFA <100 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <100 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report									
HVS-135	EHS-062918-HVS-135-1	Room 135	6/29/2018	1807029	<0.2	< 6.4 U	< 7.5 U	< 4.7 U	< 4.7 U	<3	< 41 U	< 8.1 U	< 6.5 U
HVS-135	EHS-062918-HVS-135-2	Room 135	6/29/2018	1807029	<0.2	< 6.5 U	< 7.6 U	< 4.8 U	< 4.8 U	<3	< 42 U	< 8.2 U	< 6.6 U
HVS-148	EHS-062918-HVS-148-1	Room 148	6/29/2018	1807029	0.2 to <1	380	< 7.3 U	< 4.6 U	< 4.6 U	3 to <10	< 40 U	< 7.9 U	< 6.4 U
HVS-148	EHS-062918-HVS-148-2	Room 148	6/29/2018	1807029	0.2 to <1	380	< 7.6 U	< 4.8 U	< 4.8 U	3 to <10	< 42 U	< 8.2 U	< 6.6 U
HVS-151	EHS-062918-HVS-151-1	Room 151A	6/29/2018	1807029	>1	< 6.5 U	< 7.6 U	< 4.8 U	< 4.8 U	<3	< 42 U	< 8.2 U	< 6.6 U
HVS-151	EHS-062918-HVS-151-2	Room 151A	6/29/2018	1807029	>1	< 6.4 U	< 7.5 U	< 4.7 U	< 4.7 U	<3	< 41 U	< 8.1 U	< 6.5 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-1	Hallway Near Main Entrance	7/16/2014	1407303	<0.2	9.8	< 6.8 U	< 4.3 U	< 4.3 U	<3	< 38 U	< 7.4 U	23
SSHS-01-HVS	SSHS-7-16-14-1-HVS-2	Hallway Near Main Entrance	7/16/2014	1407303	<0.2	17	< 6.8 U	< 4.3 U	< 4.3 U	<3	< 38 U	< 7.4 U	16
SSHS-02-HVS	SSHS-07-15-14-02-HVS-1	Room 130	7/15/2014	1407281R1	0.2 to <1	6700	< 29 U	< 18 U	120	<3	< 160 U	< 31 U	< 25 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS2	Room 130	7/15/2014	1407281R1	0.2 to <1	3500	< 18 U	< 11 U	70	<3	< 100 U	< 19 U	< 16 U
SSHS-03-HVS	SSHS-07-16-14-03-HVS-02	Room 127	7/16/2014	1407303	>1	20000	*< 92 U*	< 58 U	970	<3	< 510 U	< 99 U	< 80 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1	Room 127	7/16/2014	1407303	>1	28000	*< 140 U*	*< 89 U*	1500	<3	< 780 U	< 150 U	< 120 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1-DUP	Room 127	7/16/2014	1407303	>1	28000	*< 140 U*	*< 87 U*	1500	<3	< 760 U	< 150 U	< 120 U
SSHS-04-HVS	SSHS-07-15-14-04-HVS1	Room 125	7/15/2014	1407281R1	0.2 to <1	310	< 17 U	< 11 U	< 11 U	<3	< 96 U	< 19 U	< 15 U
SSHS-04-HVS	SSHS-7-15-14-04-HVS-2	Room 125	7/15/2014	1407281R1	0.2 to <1	330	< 18 U	< 11 U	< 11 U	<3	< 98 U	< 19 U	< 15 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS1	Room 124	7/15/2014	1407281R1	<0.2	2600	*< 140 U*	*< 88 U*	*< 88 U*	*<3*	< 770 U	< 150 U	< 120 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS2	Room 124	7/15/2014	1407281R1	<0.2	1600	< 42 U	< 26 U	< 26 U	<3	< 230 U	< 45 U	< 36 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-1	Room 122	7/15/2014	1407281R1	<0.2	< 59 U	*< 69 U*	< 44 U	< 44 U	<3	< 380 U	< 75 U	< 60 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-2	Room 122	7/15/2014	1407281R1	<0.2	*< 80 U*	*< 93 U*	< 59 U	< 59 U	<3	< 510 U	< 100 U	< 81 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS1	Room 120	7/15/2014	1407281R1	<0.2	*< 86 U*	*< 100 U*	*< 63 U*	*< 63 U*	*<3*	< 550 U	< 110 U	< 87 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS2	Room 120	7/15/2014	1407281R1	<0.2	*< 61 U*	*< 72 U*	< 45 U	< 45 U	<3	< 400 U	< 77 U	< 62 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-1	Hallway Outside Guidance Area	7/16/2014	1407303	0.2 to <1	3300	< 17 U	< 11 U	< 11 U	<3	< 95 U	< 18 U	< 15 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-2	Hallway Outside Guidance Area	7/16/2014	1407303	0.2 to <1	2800	< 14 U	< 8.8 U	< 8.8 U	<3	< 77 U	< 15 U	< 12 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-1	Hallway Outside Library	7/15/2014	1407281R1	<0.2	< 9.1 U	< 11 U	< 6.7 U	< 6.7 U	<3	< 59 U	27	11
SSHS-09-HVS	SSHS-7-15-14-9-HVS-2	Hallway Outside Library	7/15/2014	1407281R1	<0.2	< 5.8 U	< 6.8 U	< 4.3 U	< 4.3 U	<3	< 38 U	25	8.7
SSHS-10-HVS	SSHS-7-16-14-10-HVS-1	Room 101	7/16/2014	1407281R1	<0.2	< 6.0 U	< 7.0 U	< 4.4 U	< 4.4 U	<3	< 38 U	< 7.5 U	< 6.0 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-2	Room 101	7/16/2014	1407281R1	<0.2	< 7.7 U	< 9.1 U	< 5.7 U	< 5.7 U	<3	< 50 U	< 9.8 U	< 7.8 U
SSHS-11-HVS	SSHS-07-15-14-11-HVS-01	Room 115	7/15/2014	1407281R1	<0.2	< 5.9 U	< 6.9 U	< 4.4 U	< 4.4 U	<3	< 38 U	12	< 6.0 U
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2	Room 115	7/15/2014	1407281R1	<0.2	< 6.0 U	< 7.0 U	< 4.4 U	< 4.4 U	<3	< 39 U	9.9	< 6.1 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Trichloroethene (Trichloroethylene) (TCE)	Carbon Tetrachloride	1,1-Dichloroethene (1,1-Dichloroethylene)	cis-1,2-Dichloroethene		Methylene Chloride	Tetrachloroethene (Tetrachloroethylene) (PCE)	1,1,1-Trichloroethane (TCA)
						ug/m3	ug/m3	ug/m3	ug/m3		ug/m3	ug/m3	ug/m3
					Matrix A					Matrix B			
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 to <1 ug/m3 - Matrix Outcome = **Monitor** 6 to <60 ug/m3 and indoor air <0.2 ug/m3- Matrix Outcome = NFA <6 ug/m3 and indoor air >1 ug/m3 - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <1 ug/m3- Matrix Outcome = NFA					1,000 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 100 to <1,000 ug/m3 and indoor air 3 to <10 ug/m3 - Matrix Outcome = **Monitor** 100 to <1,000 ug/m3 and indoor air <3 ug/m3 - Matrix Outcome = NFA <100 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <100 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA			
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report									
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2-DUP	Room 115	7/15/2014	1407281R1	<0.2	< 6.0 U	< 7.0 U	< 4.4 U	< 4.4 U	<3	< 38 U	8.6	< 6.0 U
SSHS-12-HVS	SSHS-07-15-14-12-HVS-02	Room 116	7/15/2014	1407281R1	<0.2	< 24 U	< 28 U	< 18 U	< 18 U	<3	< 160 U	< 30 U	< 24 U
SSHS-12-HVS	SSHS-7-15-14-12-HVS-01	Room 116	7/15/2014	1407281R1	<0.2	< 29 U	< 34 U	< 22 U	< 22 U	<3	< 190 U	< 37 U	< 30 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS1	Room 111	7/15/2014	1407281R1	<0.2	< 6.0 U	< 7.0 U	< 4.4 U	< 4.4 U	<3	< 39 U	9.9	< 6.1 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS2	Room 111	7/15/2014	1407281R1	<0.2	< 6.1 U	< 7.1 U	< 4.5 U	< 4.5 U	<3	< 39 U	8.4	< 6.2 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS1	Room 106	7/15/2014	1407281R1	<0.2	< 8.6 U	< 10 U	< 6.3 U	< 6.3 U	<3	< 55 U	< 11 U	< 8.7 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS2	Room 106	7/15/2014	1407281R1	<0.2	< 6.1 U	< 7.1 U	< 4.5 U	< 4.5 U	<3	< 39 U	< 7.7 U	< 6.2 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-01	Back Stage	7/16/2014	1407303	<0.2	< 60 U	***< 70 U***	< 44 U	< 44 U	<3	< 390 U	< 76 U	< 61 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-02	Back Stage	7/16/2014	1407303	<0.2	< 12 U	< 14 U	< 8.8 U	< 8.8 U	<3	< 77 U	< 15 U	< 12 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-1	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 5.9 U	< 6.9 U	< 4.4 U	< 4.4 U	<3	< 38 U	< 7.5 U	< 6.0 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-2	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 5.8 U	< 6.7 U	< 4.2 U	< 4.2 U	<3	< 37 U	< 7.2 U	< 5.8 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-01	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 5.9 U	< 6.9 U	< 4.4 U	< 4.4 U	<3	< 38 U	< 7.5 U	< 6.0 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-02	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 6.2 U	< 7.3 U	< 4.6 U	< 4.6 U	<3	< 40 U	< 7.8 U	< 6.3 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-01	Custodian's Storage	7/16/2014	1407303	<0.2 to 1	< 20 U	< 24 U	< 15 U	< 15 U	<3	< 130 U	< 25 U	< 20 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-02	Custodian's Storage	7/16/2014	1407303	<0.2 to 1	< 22 U	< 26 U	< 16 U	< 16 U	<3	< 140 U	< 28 U	< 22 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-01	Room 138A	7/16/2014	1407303	<0.2	< 12 U	< 14 U	< 9.0 U	< 9.0 U	<3	< 79 U	38	< 12 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-02	Room 138A	7/16/2014	1407303	<0.2	< 13 U	< 16 U	< 9.9 U	< 9.9 U	<3	< 87 U	29	< 14 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS1	Room 142 (Wellness Ctr)	7/16/2014	1407303	<0.2	< 5.9 U	< 6.9 U	< 4.3 U	< 4.3 U	<3	< 38 U	9.7	26
SSHS-20-HVS	SSHS-7-16-14-20-HVS2	Room 142 (Wellness Ctr)	7/16/2014	1407303	<0.2	< 5.8 U	< 6.8 U	< 4.3 U	< 4.3 U	<3	< 38 U	7.4	19
SSHS-21-HVS	SSHS-7-16-14-21-HVS-1	Room 145 Nurses Office	7/16/2014	1407303	<0.2	7.3	< 7.1 U	< 4.5 U	< 4.5 U	<3	< 39 U	< 7.6 U	< 6.1 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-2	Room 145 Nurses Office	7/16/2014	1407303	<0.2	7.4	< 7.0 U	< 4.4 U	< 4.4 U	<3	< 38 U	< 7.5 U	< 6.0 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-01	Room 171 (Aux Gym)	7/16/2014	1407303	<0.2	< 6.1 U	< 7.2 U	< 4.5 U	< 4.5 U	<3	< 40 U	< 7.7 U	< 6.2 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-02	Room 171 (Aux Gym)	7/16/2014	1407303	<0.2	< 5.9 U	< 6.9 U	< 4.3 U	< 4.3 U	<3	< 38 U	< 7.4 U	< 6.0 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS1	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	<0.2	< 9.1 U	< 11 U	< 6.7 U	< 6.7 U	<3	< 59 U	< 11 U	< 9.2 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS2	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	<0.2	< 6.2 U	< 7.2 U	< 4.5 U	< 4.5 U	<3	< 40 U	< 7.8 U	< 6.2 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Vinyl Chloride		Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
						ug/m3		ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
						Matrix C		Matrix D						
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = **Monitor** <6 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = NFA			600 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 2 to <10 ug/m3 - Matrix Outcome = **Monitor** 60 to <600 ug/m3 and indoor air <2 ug/m3 - Matrix Outcome = NFA <60 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <60 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA						
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report										
HVS-135	EHS-062918-HVS-135-1	Room 135	6/29/2018	1807029	<0.2	< 3.0 U	<2	< 3.8 U	< 4.1 U	< 5.2 U	< 5.8 U	< 5.8 U	< 5.6 U	< 5.2 U
HVS-135	EHS-062918-HVS-135-2	Room 135	6/29/2018	1807029	<0.2	< 3.1 U	<2	< 3.9 U	< 4.2 U	< 5.2 U	< 5.9 U	< 5.9 U	< 5.6 U	< 5.2 U
HVS-148	EHS-062918-HVS-148-1	Room 148	6/29/2018	1807029	<0.2	< 3.0 U	2 to <10	< 3.7 U	< 4.0 U	< 5.0 U	< 5.7 U	< 5.7 U	< 5.4 U	< 5.0 U
HVS-148	EHS-062918-HVS-148-2	Room 148	6/29/2018	1807029	<0.2	< 3.1 U	2 to <10	< 3.9 U	< 4.2 U	< 5.2 U	< 5.9 U	< 5.9 U	< 5.6 U	< 5.2 U
HVS-151	EHS-062918-HVS-151-1	Room 151A	6/29/2018	1807029	<0.2	< 3.1 U	2 to <10	< 3.9 U	< 4.2 U	< 5.2 U	< 5.9 U	< 5.9 U	< 5.6 U	< 5.2 U
HVS-151	EHS-062918-HVS-151-2	Room 151A	6/29/2018	1807029	<0.2	< 3.0 U	2 to <10	< 3.8 U	< 4.1 U	< 5.2 U	< 5.8 U	< 5.8 U	< 5.6 U	< 5.2 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-1	Hallway Near Main Entrance	7/16/2014	1407303	<0.2	< 2.8 U	<2	47	< 3.7 U	100	270	67	< 5.1 U	180
SSHS-01-HVS	SSHS-7-16-14-1-HVS-2	Hallway Near Main Entrance	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.7 U	< 4.7 U	< 5.3 U	< 5.3 U	< 5.1 U	< 4.7 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS-1	Room 130	7/15/2014	1407281R1	<0.2	< 12 U	<2	< 15 U	< 16 U	< 20 U	< 22 U	< 22 U	< 21 U	< 20 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS2	Room 130	7/15/2014	1407281R1	<0.2	< 7.3 U	<2	< 9.2 U	< 9.9 U	< 12 U	< 14 U	< 14 U	< 13 U	< 12 U
SSHS-03-HVS	SSHS-07-16-14-03-HVS-02	Room 127	7/16/2014	1407303	<0.2	< 37 U	<2	< 47 U	< 50 U	< 64 U	< 72 U	< 72 U	< 68 U	< 64 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1	Room 127	7/16/2014	1407303	<0.2	< 57 U	<2	< 72 U	< 77 U	< 97 U	< 110 U	< 110 U	< 100 U	< 97 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1-DUP	Room 127	7/16/2014	1407303	<0.2	< 56 U	<2	< 70 U	< 75 U	< 95 U	< 110 U	< 110 U	< 100 U	< 95 U
SSHS-04-HVS	SSHS-07-15-14-04-HVS1	Room 125	7/15/2014	1407281R1	<0.2	< 7.1 U	<2	< 8.9 U	< 9.6 U	< 12 U	< 14 U	< 14 U	< 13 U	< 12 U
SSHS-04-HVS	SSHS-7-15-14-04-HVS-2	Room 125	7/15/2014	1407281R1	<0.2	< 7.2 U	<2	< 9.0 U	< 9.7 U	< 12 U	< 14 U	< 14 U	< 13 U	< 12 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS1	Room 124	7/15/2014	1407281R1	<0.2	< 57 U	<2	< 71 U	< 77 U	< 97 U	< 110 U	< 110 U	< 100 U	< 97 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS2	Room 124	7/15/2014	1407281R1	<0.2	< 17 U	<2	< 21 U	< 23 U	< 29 U	< 33 U	< 33 U	< 31 U	< 29 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-1	Room 122	7/15/2014	1407281R1	<0.2	< 28 U	<2	< 35 U	< 38 U	< 48 U	< 54 U	< 54 U	< 51 U	< 48 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-2	Room 122	7/15/2014	1407281R1	<0.2	< 38 U	<2	< 47 U	< 51 U	< 64 U	< 73 U	< 73 U	< 69 U	< 64 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS1	Room 120	7/15/2014	1407281R1	<0.2	< 41 U	<2	< 51 U	< 55 U	< 69 U	< 78 U	< 78 U	< 74 U	< 69 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS2	Room 120	7/15/2014	1407281R1	<0.2	< 29 U	<2	< 36 U	< 39 U	< 49 U	< 56 U	< 56 U	< 53 U	< 50 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-1	Hallway Outside Guidance Area	7/16/2014	1407303	<0.2	< 7.0 U	<2	9.0	< 9.4 U	< 12 U	< 13 U	< 13 U	< 13 U	< 12 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-2	Hallway Outside Guidance Area	7/16/2014	1407303	<0.2	< 5.6 U	<2	< 7.1 U	< 7.6 U	< 9.6 U	< 11 U	< 11 U	< 10 U	< 9.6 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-1	Hallway Outside Library	7/15/2014	1407281R1	<0.2	< 4.3 U	<2	< 5.4 U	< 5.8 U	< 7.4 U	< 8.4 U	< 8.4 U	< 7.9 U	< 7.4 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-2	Hallway Outside Library	7/15/2014	1407281R1	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.7 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.7 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-1	Room 101	7/16/2014	1407281R1	<0.2	< 2.8 U	2 to <10	110	< 3.8 U	76	120	34	< 5.2 U	170
SSHS-10-HVS	SSHS-7-16-14-10-HVS-2	Room 101	7/16/2014	1407281R1	<0.2	< 3.7 U	2 to <10	< 4.6 U	< 5.0 U	< 6.2 U	< 7.1 U	< 7.1 U	< 6.7 U	< 6.2 U
SSHS-11-HVS	SSHS-07-15-14-11-HVS-01	Room 115	7/15/2014	1407281R1	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2	Room 115	7/15/2014	1407281R1	<0.2	< 2.8 U	<2	< 3.6 U	< 3.8 U	< 4.8 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.8 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						Vinyl Chloride		Benzene	Cyclohexane	Ethylbenzene	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	o-Xylene
						ug/m3		ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
						Matrix C		Matrix D						
					60 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** 6 to <60 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = **Monitor** <6 ug/m3 and indoor air 0.2 ug/m3 and above - Matrix Outcome = **Mitigate** <6 ug/m3 and indoor air <0.2 ug/m3 - Matrix Outcome = NFA			600 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** 60 to <600 ug/m3 and indoor air 2 to <10 ug/m3 - Matrix Outcome = **Monitor** 60 to <600 ug/m3 and indoor air <2 ug/m3 - Matrix Outcome = NFA <60 ug/m3 and indoor air 10 ug/m3 and above - Matrix Outcome = **Mitigate** <60 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA						
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report										
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2-DUP	Room 115	7/15/2014	1407281R1	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.2 U	< 4.8 U
SSHS-12-HVS	SSHS-07-15-14-12-HVS-02	Room 116	7/15/2014	1407281R1	<0.2	< 12 U	<2	< 14 U	< 15 U	< 20 U	< 22 U	< 22 U	< 21 U	< 20 U
SSHS-12-HVS	SSHS-7-15-14-12-HVS-01	Room 116	7/15/2014	1407281R1	<0.2	< 14 U	<2	< 17 U	< 19 U	< 24 U	< 27 U	< 27 U	< 25 U	< 24 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS1	Room 111	7/15/2014	1407281R1	<0.2	< 2.9 U	<2	< 3.6 U	< 3.8 U	< 4.9 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.9 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS2	Room 111	7/15/2014	1407281R1	<0.2	< 2.9 U	<2	< 3.6 U	< 3.9 U	< 4.9 U	< 5.6 U	< 5.6 U	< 5.3 U	< 4.9 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS1	Room 106	7/15/2014	1407281R1	<0.2	< 4.1 U	<2	< 5.1 U	< 5.5 U	< 6.9 U	< 7.8 U	< 7.8 U	< 7.4 U	< 6.9 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS2	Room 106	7/15/2014	1407281R1	<0.2	< 2.9 U	<2	< 3.6 U	< 3.9 U	< 4.9 U	< 5.6 U	< 5.6 U	< 5.3 U	< 4.9 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-01	Back Stage	7/16/2014	1407303	<0.2	< 29 U	<2	< 36 U	< 38 U	< 49 U	< 55 U	< 55 U	< 52 U	< 49 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-02	Back Stage	7/16/2014	1407303	<0.2	< 5.6 U	<2	< 7.1 U	< 7.6 U	< 9.6 U	< 11 U	< 11 U	< 10 U	< 9.6 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-1	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-2	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 2.7 U	<2	< 3.4 U	< 3.7 U	< 4.6 U	< 5.2 U	< 5.3 U	< 5.0 U	< 4.6 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-01	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-02	Hallway Outside Room 136A	7/16/2014	1407303	<0.2	< 3.0 U	<2	< 3.7 U	< 4.0 U	< 5.0 U	< 5.7 U	< 5.7 U	< 5.4 U	< 5.0 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-01	Custodian's Storage	7/16/2014	1407303	<0.2	< 9.6 U	2 to <10	< 12 U	< 13 U	< 16 U	< 18 U	< 18 U	< 18 U	< 16 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-02	Custodian's Storage	7/16/2014	1407303	<0.2	< 10 U	2 to <10	< 13 U	< 14 U	< 18 U	< 20 U	< 20 U	< 19 U	< 18 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-01	Room 138A	7/16/2014	1407303	<0.2	< 5.8 U	<2	< 7.2 U	< 7.8 U	< 9.8 U	< 11 U	< 11 U	< 11 U	< 9.8 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-02	Room 138A	7/16/2014	1407303	<0.2	< 6.4 U	<2	< 8.0 U	< 8.6 U	< 11 U	< 12 U	< 12 U	< 12 U	< 11 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS1	Room 142 (Wellness Ctr)	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS2	Room 142 (Wellness Ctr)	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.7 U	< 4.7 U	< 5.3 U	< 5.3 U	< 5.1 U	< 4.7 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-1	Room 145 Nurses Office	7/16/2014	1407303	<0.2	< 2.9 U	<2	< 3.6 U	< 3.9 U	< 4.9 U	< 5.5 U	< 5.5 U	< 5.2 U	< 4.9 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-2	Room 145 Nurses Office	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.2 U	< 4.8 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-01	Room 171 (Aux Gym)	7/16/2014	1407303	<0.2	< 2.9 U	<2	< 3.6 U	< 3.9 U	< 4.9 U	< 5.6 U	< 5.6 U	< 5.3 U	< 5.0 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-02	Room 171 (Aux Gym)	7/16/2014	1407303	<0.2	< 2.8 U	<2	< 3.5 U	< 3.8 U	< 4.8 U	< 5.4 U	< 5.4 U	< 5.1 U	< 4.8 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS1	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	<0.2	< 4.3 U	<2	< 5.4 U	< 5.8 U	< 7.3 U	< 8.3 U	< 8.3 U	< 7.9 U	< 7.3 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS2	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	<0.2	< 2.9 U	<2	< 3.6 U	< 3.9 U	< 5.0 U	< 5.6 U	< 5.6 U	< 5.3 U	< 5.0 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						N-Heptane	N-Hexane	m,p-Xylene		Toluene	Acetone
						ug/m3	ug/m3	ug/m3		ug/m3	ug/m3
					Matrix E				Matrix F		
					2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 6 to <20 ug/m3 - Matrix Outcome = **Monitor** 200 to <2,000 ug/m3 and indoor air <6 ug/m3 - Matrix Outcome = NFA <200 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** <200 ug/m3 and indoor air <20 ug/m3 - Matrix Outcome = NFA				3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 10 to <50 ug/m3 - Matrix Outcome = **Monitor** 300 to <3,000 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA <300 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** <300 ug/m3 and indoor air <50 ug/m3 - Matrix Outcome = NFA		
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report							
HVS-135	EHS-062918-HVS-135-1	Room 135	6/29/2018	1807029	<6	< 4.9 U	< 4.2 U	7.5	<10	130	100
HVS-135	EHS-062918-HVS-135-2	Room 135	6/29/2018	1807029	<6	< 5.0 U	< 4.3 U	7.6	<10	90	64
HVS-148	EHS-062918-HVS-148-1	Room 148	6/29/2018	1807029	<6	< 4.8 U	< 4.1 U	< 5.0 U	10 to <50	8.9	< 28 U
HVS-148	EHS-062918-HVS-148-2	Room 148	6/29/2018	1807029	<6	< 5.0 U	< 4.3 U	< 5.2 U	10 to <50	< 4.6 U	< 29 U
HVS-151	EHS-062918-HVS-151-1	Room 151A	6/29/2018	1807029	<6	< 5.0 U	< 4.3 U	< 5.2 U	<10	< 4.6 U	130
HVS-151	EHS-062918-HVS-151-2	Room 151A	6/29/2018	1807029	<6	< 4.9 U	< 4.2 U	< 5.2 U	<10	< 4.5 U	43
SSHS-01-HVS	SSHS-7-16-14-1-HVS-1	Hallway Near Main Entrance	7/16/2014	1407303	<6	5.3	10	470	<10	190	63
SSHS-01-HVS	SSHS-7-16-14-1-HVS-2	Hallway Near Main Entrance	7/16/2014	1407303	<6	< 4.4 U	< 3.8 U	< 4.7 U	<10	< 4.1 U	< 26 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS-1	Room 130	7/15/2014	1407281R1	<6	< 19 U	< 16 U	< 20 U	<10	23	< 110 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS2	Room 130	7/15/2014	1407281R1	<6	< 12 U	28	< 12 U	<10	< 11 U	< 68 U
SSHS-03-HVS	SSHS-07-16-14-03-HVS-02	Room 127	7/16/2014	1407303	<6	< 60 U	< 52 U	< 64 U	<10	< 55 U	< 350 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1	Room 127	7/16/2014	1407303	<6	< 92 U	< 79 U	< 97 U	<10	< 84 U	< 530 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1-DUP	Room 127	7/16/2014	1407303	<6	< 90 U	< 77 U	< 95 U	<10	< 82 U	< 520 U
SSHS-04-HVS	SSHS-07-15-14-04-HVS1	Room 125	7/15/2014	1407281R1	<6	< 11 U	< 9.8 U	< 12 U	<10	< 10 U	< 66 U
SSHS-04-HVS	SSHS-7-15-14-04-HVS-2	Room 125	7/15/2014	1407281R1	<6	< 12 U	< 9.9 U	< 12 U	<10	< 10 U	< 67 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS1	Room 124	7/15/2014	1407281R1	<6	< 91 U	< 78 U	< 97 U	<10	< 84 U	< 530 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS2	Room 124	7/15/2014	1407281R1	<6	< 27 U	< 24 U	< 29 U	<10	< 25 U	< 160 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-1	Room 122	7/15/2014	1407281R1	<6	< 45 U	< 39 U	< 48 U	<10	< 41 U	< 260 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-2	Room 122	7/15/2014	1407281R1	<6	< 61 U	< 52 U	< 64 U	<10	< 56 U	< 350 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS1	Room 120	7/15/2014	1407281R1	<6	< 65 U	< 56 U	< 69 U	<10	< 60 U	< 380 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS2	Room 120	7/15/2014	1407281R1	<6	< 47 U	< 40 U	< 50 U	<10	< 43 U	< 270 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-1	Hallway Outside Guidance Area	7/16/2014	1407303	<6	< 11 U	< 9.6 U	< 12 U	<10	12	83
SSHS-08-HVS	SSHS-7-16-14-8-HVS-2	Hallway Outside Guidance Area	7/16/2014	1407303	<6	< 9.0 U	< 7.8 U	< 9.6 U	<10	< 8.3 U	94
SSHS-09-HVS	SSHS-7-15-14-9-HVS-1	Hallway Outside Library	7/15/2014	1407281R1	<6	< 7.0 U	< 6.0 U	< 7.4 U	<10	< 6.4 U	< 40 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-2	Hallway Outside Library	7/15/2014	1407281R1	<6	< 4.5 U	< 3.8 U	< 4.7 U	<10	< 4.1 U	< 26 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-1	Room 101	7/16/2014	1407281R1	6 to <20	< 4.5 U	< 3.9 U	410	10 to <50	620	67
SSHS-10-HVS	SSHS-7-16-14-10-HVS-2	Room 101	7/16/2014	1407281R1	6 to <20	< 5.9 U	< 5.1 U	< 6.2 U	10 to <50	6.1	< 34 U
SSHS-11-HVS	SSHS-07-15-14-11-HVS-01	Room 115	7/15/2014	1407281R1	<6	< 4.5 U	7.0	< 4.8 U	<10	< 4.1 U	< 26 U
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2	Room 115	7/15/2014	1407281R1	<6	< 4.6 U	12	< 4.8 U	<10	6.0	< 26 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

						N-Heptane	N-Hexane	m,p-Xylene		Toluene	Acetone
						ug/m3	ug/m3	ug/m3		ug/m3	ug/m3
					Matrix E				Matrix F		
					2,000 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** 200 to <2,000 ug/m3 and indoor air 6 to <20 ug/m3 - Matrix Outcome = **Monitor** 200 to <2,000 ug/m3 and indoor air <6 ug/m3 - Matrix Outcome = NFA <200 ug/m3 and indoor air 20 ug/m3 and above - Matrix Outcome = **Mitigate** <200 ug/m3 and indoor air <20 ug/m3 - Matrix Outcome = NFA				3,000 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** 300 to <3,000 ug/m3 and indoor air 10 to <50 ug/m3 - Matrix Outcome = **Monitor** 300 to <3,000 ug/m3 and indoor air <10 ug/m3 - Matrix Outcome = NFA <300 ug/m3 and indoor air 50 ug/m3 and above - Matrix Outcome = **Mitigate** <300 ug/m3 and indoor air <50 ug/m3 - Matrix Outcome = NFA		
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report							
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2-DUP	Room 115	7/15/2014	1407281R1	<6	< 4.5 U	12	< 4.8 U	<10	5.9	< 26 U
SSHS-12-HVS	SSHS-07-15-14-12-HVS-02	Room 116	7/15/2014	1407281R1	<6	< 18 U	< 16 U	< 20 U	<10	< 17 U	< 110 U
SSHS-12-HVS	SSHS-7-15-14-12-HVS-01	Room 116	7/15/2014	1407281R1	<6	< 22 U	< 19 U	< 24 U	<10	< 20 U	< 130 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS1	Room 111	7/15/2014	1407281R1	<6	< 4.6 U	< 3.9 U	< 4.9 U	<10	< 4.2 U	< 27 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS2	Room 111	7/15/2014	1407281R1	<6	< 4.6 U	< 4.0 U	< 4.9 U	<10	5.4	< 27 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS1	Room 106	7/15/2014	1407281R1	<6	< 6.5 U	< 5.6 U	< 6.9 U	<10	< 6.0 U	< 38 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS2	Room 106	7/15/2014	1407281R1	<6	< 4.6 U	4.7	< 4.9 U	<10	5.3	< 27 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-01	Back Stage	7/16/2014	1407303	<6	< 46 U	< 39 U	< 49 U	<10	< 42 U	< 270 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-02	Back Stage	7/16/2014	1407303	<6	< 9.0 U	< 7.8 U	< 9.6 U	<10	< 8.3 U	< 52 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-1	Hallway Outside Room 136A	7/16/2014	1407303	<6	< 4.5 U	< 3.9 U	< 4.8 U	<10	6.7	33
SSHS-16-HVS	SSHS-7-16-14-16-HVS-2	Hallway Outside Room 136A	7/16/2014	1407303	<6	< 4.4 U	< 3.8 U	< 4.6 U	<10	< 4.0 U	33
SSHS-17-HVS	SSHS-07-16-14-17-HVS-01	Hallway Outside Room 136A	7/16/2014	1407303	<6	< 4.5 U	< 3.9 U	< 4.8 U	<10	< 4.1 U	< 26 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-02	Hallway Outside Room 136A	7/16/2014	1407303	<6	< 4.7 U	< 4.1 U	< 5.0 U	<10	< 4.4 U	< 27 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-01	Custodian's Storage	7/16/2014	1407303	6 to <20	< 15 U	< 13 U	< 16 U	10 to <50	< 14 U	< 89 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-02	Custodian's Storage	7/16/2014	1407303	6 to <20	< 17 U	< 14 U	< 18 U	10 to <50	< 15 U	< 98 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-01	Room 138A	7/16/2014	1407303	<6	< 9.3 U	< 8.0 U	< 9.8 U	<10	16	160
SSHS-19-HVS	SSHS-07-16-14-19-HVS-02	Room 138A	7/16/2014	1407303	<6	< 10 U	< 8.8 U	< 11 U	<10	13	210
SSHS-20-HVS	SSHS-7-16-14-20-HVS1	Room 142 (Wellness Ctr)	7/16/2014	1407303	<6	< 4.5 U	< 3.8 U	< 4.8 U	<10	< 4.1 U	34
SSHS-20-HVS	SSHS-7-16-14-20-HVS2	Room 142 (Wellness Ctr)	7/16/2014	1407303	<6	< 4.4 U	< 3.8 U	< 4.7 U	<10	< 4.1 U	48
SSHS-21-HVS	SSHS-7-16-14-21-HVS-1	Room 145 Nurses Office	7/16/2014	1407303	<6	< 4.6 U	< 4.0 U	< 4.9 U	<10	7.2	< 27 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-2	Room 145 Nurses Office	7/16/2014	1407303	<6	< 4.5 U	< 3.9 U	< 4.8 U	<10	5.8	27
SSHS-22-HVS	SSHS-07-16-14-22-HVS-01	Room 171 (Aux Gym)	7/16/2014	1407303	<6	< 4.7 U	< 4.0 U	< 5.0 U	<10	4.7	84
SSHS-22-HVS	SSHS-07-16-14-22-HVS-02	Room 171 (Aux Gym)	7/16/2014	1407303	<6	< 4.5 U	< 3.8 U	< 4.8 U	<10	< 4.1 U	32
SSHS-23-HVS	SSHS-07-16-14-23-HVS1	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	<6	< 6.9 U	< 6.0 U	< 7.3 U	<10	< 6.4 U	< 40 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS2	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	<6	< 4.7 U	< 4.0 U	< 5.0 U	<10	< 4.3 U	< 27 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane	Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report															
HVS-135	EHS-062918-HVS-135-1	Room 135	6/29/2018	1807029	< 6.2 U	< 8.0 U	< 12 U	< 46 U	< 2.6 U	23	< 15 U	< 5.5 U	< 12 U	< 5.8 U	< 24 U	< 15 U	< 10 U	< 9.1 U	< 7.2 U
HVS-135	EHS-062918-HVS-135-2	Room 135	6/29/2018	1807029	< 6.3 U	< 8.1 U	< 12 U	< 47 U	< 2.7 U	< 14 U	< 15 U	< 5.6 U	< 13 U	< 5.9 U	< 25 U	< 15 U	< 10 U	< 9.3 U	< 7.3 U
HVS-148	EHS-062918-HVS-148-1	Room 148	6/29/2018	1807029	< 6.0 U	< 7.8 U	< 12 U	< 45 U	< 2.6 U	< 14 U	< 14 U	< 5.4 U	< 12 U	< 5.7 U	< 24 U	< 14 U	< 9.9 U	< 9.0 U	< 7.0 U
HVS-148	EHS-062918-HVS-148-2	Room 148	6/29/2018	1807029	< 6.3 U	< 8.1 U	< 12 U	< 47 U	< 2.7 U	< 14 U	< 15 U	< 5.6 U	< 13 U	< 5.9 U	< 25 U	< 15 U	< 10 U	< 9.3 U	< 7.3 U
HVS-151	EHS-062918-HVS-151-1	Room 151A	6/29/2018	1807029	< 6.3 U	< 8.1 U	< 12 U	< 47 U	< 2.7 U	< 14 U	< 15 U	< 5.6 U	< 13 U	< 5.9 U	< 25 U	< 15 U	< 10 U	< 9.3 U	< 7.3 U
HVS-151	EHS-062918-HVS-151-2	Room 151A	6/29/2018	1807029	< 6.2 U	< 8.0 U	< 12 U	< 46 U	< 2.6 U	< 14 U	< 15 U	< 5.5 U	< 12 U	< 5.8 U	< 24 U	< 15 U	< 10 U	< 9.1 U	< 7.2 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-1	Hallway Near Main Entrance	7/16/2014	1407303	< 5.6 U	< 7.3 U	< 11 U	< 42 U	< 2.4 U	15	< 14 U	< 5.0 U	< 11 U	< 5.3 U	< 22 U	< 14 U	< 9.2 U	< 8.3 U	< 6.5 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-2	Hallway Near Main Entrance	7/16/2014	1407303	< 5.6 U	< 7.3 U	< 11 U	< 42 U	< 2.4 U	< 13 U	< 14 U	< 5.0 U	< 11 U	< 5.3 U	< 22 UJ	< 14 U	< 9.2 U	< 8.3 U	< 6.5 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS-1	Room 130	7/15/2014	1407281R1	< 24 U	< 31 U	< 47 U	< 180 U	< 10 U	< 54 U	< 57 U	< 21 U	< 48 U	< 22 U	< 94 U	< 57 U	< 39 U	< 35 U	< 28 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS2	Room 130	7/15/2014	1407281R1	< 15 U	< 19 U	< 30 U	< 110 U	< 6.3 U	< 34 U	< 36 U	< 13 U	< 30 U	< 14 U	< 59 U	< 36 U	< 24 U	< 22 U	< 17 U
SSHS-03-HVS	SSHS-07-16-14-03-HVS-02	Room 127	7/16/2014	1407303	< 76 U	< 98 U	< 150 U	< 570 U	< 32 U	< 170 U	< 180 U	< 67 U	< 150 U	< 72 U	< 300 U	< 180 U	< 120 U	< 110 U	< 88 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1	Room 127	7/16/2014	1407303	< 120 U	< 150 U	< 230 U	< 870 U	< 50 U	< 260 U	< 280 U	< 100 U	< 240 U	< 110 U	< 460 U	< 280 U	< 190 U	< 170 U	< 130 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1-DUP	Room 127	7/16/2014	1407303	< 110 U	< 150 U	< 230 U	< 850 U	< 48 U	< 260 U	< 270 U	< 100 U	< 230 U	< 110 U	< 450 U	< 270 U	< 190 U	< 170 U	< 130 U
SSHS-04-HVS	SSHS-07-15-14-04-HVS1	Room 125	7/15/2014	1407281R1	< 14 U	< 18 U	< 29 U	< 110 U	< 6.1 U	< 33 U	< 34 U	< 13 U	< 29 U	< 14 U	< 57 U	< 35 U	< 24 U	< 21 U	< 17 U
SSHS-04-HVS	SSHS-7-15-14-04-HVS-2	Room 125	7/15/2014	1407281R1	< 14 U	< 19 U	< 29 U	< 110 U	< 6.2 U	< 33 U	< 35 U	< 13 U	< 30 U	< 14 U	< 58 U	< 35 U	< 24 U	< 22 U	< 17 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS1	Room 124	7/15/2014	1407281R1	< 120 U	< 150 U	< 230 U	< 870 U	< 49 U	< 260 U	< 280 U	< 100 U	< 240 U	< 110 U	< 460 U	< 280 U	< 190 U	< 170 U	< 130 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS2	Room 124	7/15/2014	1407281R1	< 35 U	< 45 U	< 69 U	< 260 U	< 15 U	< 79 U	< 83 U	< 31 U	< 71 U	< 33 U	< 140 U	< 84 U	< 57 U	< 51 U	< 40 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-1	Room 122	7/15/2014	1407281R1	< 57 U	< 74 U	< 110 U	< 430 U	< 24 U	< 130 U	< 140 U	< 51 U	< 120 U	< 54 U	< 230 U	< 140 U	< 94 U	< 84 U	< 66 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-2	Room 122	7/15/2014	1407281R1	< 77 U	< 99 U	< 150 U	< 570 U	< 33 U	< 170 U	< 180 U	< 68 U	< 160 U	< 72 U	< 300 U	< 180 U	< 130 U	< 110 U	< 89 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS1	Room 120	7/15/2014	1407281R1	< 82 U	< 110 U	< 160 U	< 620 U	< 35 U	< 190 U	< 200 U	< 73 U	< 170 U	< 78 U	< 330 U	< 200 U	< 140 U	< 120 U	< 96 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS2	Room 120	7/15/2014	1407281R1	< 59 U	< 76 U	< 120 U	< 440 U	< 25 U	< 130 U	< 140 U	< 52 U	< 120 U	< 56 U	< 240 U	< 140 U	< 97 U	< 88 U	< 68 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-1	Hallway Outside Guidance Area	7/16/2014	1407303	< 14 U	< 18 U	< 28 U	< 110 U	< 6.0 U	80	< 34 U	< 12 U	< 29 U	< 13 U	< 56 U	< 34 U	< 23 U	< 21 U	< 16 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-2	Hallway Outside Guidance Area	7/16/2014	1407303	< 11 U	< 15 U	< 23 U	< 86 U	< 4.9 U	34	< 28 U	< 10 U	< 23 U	< 11 U	< 46 U	< 28 U	< 19 U	< 17 U	< 13 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-1	Hallway Outside Library	7/15/2014	1407281R1	< 8.8 U	< 11 U	< 18 U	< 66 U	< 3.8 U	36	< 21 U	< 7.8 U	< 18 U	< 8.3 U	< 35 U	< 21 U	< 14 U	< 13 U	< 10 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-2	Hallway Outside Library	7/15/2014	1407281R1	< 5.6 U	< 7.3 U	< 11 U	< 42 U	< 2.4 U	< 13 U	< 14 U	< 5.0 U	< 12 U	< 5.3 U	< 22 U	< 14 U	< 9.3 U	< 8.4 U	< 6.6 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-1	Room 101	7/16/2014	1407281R1	< 5.7 U	< 7.4 U	< 11 U	< 43 U	< 2.4 U	23	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.5 U	< 6.7 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-2	Room 101	7/16/2014	1407281R1	< 7.4 U	< 9.6 U	< 15 U	< 56 U	< 3.2 U	< 17 U	< 18 U	< 6.6 U	< 15 U	< 7.0 U	< 30 U	< 18 U	< 12 U	< 11 U	< 8.6 U
SSHS-11-HVS	SSHS-07-15-14-11-HVS-01	Room 115	7/15/2014	1407281R1	< 5.7 U	< 7.4 U	< 11 U	< 43 U	< 2.4 U	< 13 U	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.4 U	< 6.6 U
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2	Room 115	7/15/2014	1407281R1	< 5.8 U	< 7.5 U	< 12 U	< 43 U	< 2.5 U	< 13 U	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.5 U	< 8.6 U	< 6.7 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	2-Butanone	Carbon disulfide	Chlorobenzene	Chloroethane	Chloroform	Chloromethane	3-Chloropropene	Dibromochloromethane	1,2-Dibromoethane (EDB)	1,2-Dichlorobenzene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report															
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2-DUP	Room 115	7/15/2014	1407281R1	< 5.7 U	< 7.4 U	< 11 U	< 43 U	< 2.4 U	< 13 U	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.5 U	< 6.7 U
SSHS-12-HVS	SSHS-07-15-14-12-HVS-02	Room 116	7/15/2014	1407281R1	< 23 U	< 30 U	< 46 U	< 170 U	< 10 U	< 53 U	< 56 U	< 21 U	< 47 U	< 22 U	< 93 U	< 56 U	< 38 U	< 34 U	< 27 U
SSHS-12-HVS	SSHS-7-15-14-12-HVS-01	Room 116	7/15/2014	1407281R1	< 28 U	< 36 U	< 56 U	< 210 U	< 12 U	< 64 U	< 68 U	< 25 U	< 58 U	< 27 U	< 110 U	< 68 U	< 46 U	< 42 U	< 33 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS1	Room 111	7/15/2014	1407281R1	< 5.8 U	< 7.5 U	< 12 U	< 43 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	< 5.5 U	< 23 U	< 14 U	< 9.5 U	< 8.6 U	< 6.7 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS2	Room 111	7/15/2014	1407281R1	< 5.9 U	< 7.6 U	< 12 U	< 44 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	< 5.5 U	< 23 U	< 14 U	< 9.7 U	< 8.7 U	< 6.8 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS1	Room 106	7/15/2014	1407281R1	< 8.2 U	< 11 U	< 16 U	< 62 U	< 3.5 U	< 19 U	< 20 U	< 7.3 U	< 17 U	< 7.8 U	< 33 U	< 20 U	< 14 U	< 12 U	< 9.6 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS2	Room 106	7/15/2014	1407281R1	< 5.9 U	< 7.6 U	< 12 U	< 44 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	< 5.5 U	< 23 U	< 14 U	< 9.7 U	< 8.7 U	< 6.8 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-01	Back Stage	7/16/2014	1407303	< 58 U	< 75 U	< 120 U	< 430 U	< 25 U	< 130 U	< 140 U	< 52 U	< 120 U	< 55 U	< 230 U	< 140 U	< 95 U	< 86 U	< 67 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-02	Back Stage	7/16/2014	1407303	< 11 U	< 15 U	< 23 U	< 86 U	< 4.9 U	< 26 U	< 28 U	< 10 U	< 23 U	< 11 U	< 46 U	< 28 U	< 19 U	< 17 U	< 13 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-1	Hallway Outside Room 136A	7/16/2014	1407303	< 5.7 U	< 7.4 U	< 11 U	< 43 U	< 2.4 U	31	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.4 U	< 6.6 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-2	Hallway Outside Room 136A	7/16/2014	1407303	< 5.5 U	< 7.2 U	< 11 U	< 42 U	< 2.4 U	< 13 U	< 13 U	< 4.9 U	< 11 U	< 5.2 U	< 22 U	< 13 U	< 9.1 U	< 8.2 U	< 6.4 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-01	Hallway Outside Room 136A	7/16/2014	1407303	< 5.7 U	< 7.4 U	< 11 U	< 43 U	< 2.4 U	< 13 U	< 14 U	< 5.1 U	< 12 U	< 5.4 U	< 23 U	< 14 U	< 9.4 U	< 8.4 U	< 6.6 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-02	Hallway Outside Room 136A	7/16/2014	1407303	< 6.0 U	< 7.7 U	< 12 U	< 45 U	< 2.6 U	< 14 U	< 14 U	< 5.3 U	< 12 U	< 5.6 U	< 24 UJ	< 14 U	< 9.8 U	< 8.9 U	< 6.9 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-01	Custodian's Storage	7/16/2014	1407303	< 19 U	< 25 U	< 39 U	< 140 U	< 8.3 U	< 44 U	< 47 U	< 17 U	< 40 U	< 18 U	< 78 U	< 47 U	< 32 U	< 29 U	< 22 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-02	Custodian's Storage	7/16/2014	1407303	< 21 U	< 28 U	< 42 U	< 160 U	< 9.1 U	< 48 U	< 51 U	< 19 U	< 43 U	< 20 U	< 85 U	< 51 U	< 35 U	< 32 U	< 25 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-01	Room 138A	7/16/2014	1407303	< 12 U	< 15 U	< 23 U	< 88 U	< 5.0 U	< 27 U	< 28 U	< 10 U	< 24 U	< 11 U	< 47 U	< 28 U	< 19 U	< 17 U	< 14 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-02	Room 138A	7/16/2014	1407303	< 13 U	< 17 U	< 26 U	< 97 U	< 5.5 U	< 30 U	< 31 U	< 12 U	< 26 U	< 12 U	< 52 U	< 31 U	< 21 U	< 19 U	< 15 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS1	Room 142 (Wellness Ctr)	7/16/2014	1407303	< 5.7 U	< 7.3 U	< 11 U	< 42 U	< 2.4 U	< 13 U	< 14 U	< 5.0 U	< 12 U	< 5.3 U	< 23 U	< 14 U	< 9.3 U	< 8.4 U	< 6.6 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS2	Room 142 (Wellness Ctr)	7/16/2014	1407303	< 5.6 U	< 7.3 U	< 11 U	< 42 U	< 2.4 U	< 13 U	< 14 U	< 5.0 U	< 11 U	< 5.3 U	< 22 U	< 14 U	< 9.2 U	< 8.3 U	< 6.5 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-1	Room 145 Nurses Office	7/16/2014	1407303	< 5.8 U	< 7.5 U	< 12 U	< 44 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	5.9	< 23 U	< 14 U	< 9.6 U	< 8.6 U	< 6.8 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-2	Room 145 Nurses Office	7/16/2014	1407303	< 5.7 U	< 7.4 U	< 11 U	< 43 U	< 2.4 U	< 13 U	< 14 U	< 5.1 U	< 12 U	16	< 23 U	< 14 U	< 9.4 U	< 8.5 U	< 6.7 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-01	Room 171 (Aux Gym)	7/16/2014	1407303	< 5.9 U	< 7.6 U	< 12 U	< 44 U	< 2.5 U	< 13 U	< 14 U	< 5.2 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.7 U	< 8.8 U	< 6.8 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-02	Room 171 (Aux Gym)	7/16/2014	1407303	< 5.7 U	< 7.3 U	< 11 U	< 42 U	< 2.4 U	< 13 U	< 14 U	< 5.0 U	< 12 U	< 5.3 U	< 23 U	< 14 U	< 9.3 U	< 8.4 U	< 6.6 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS1	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	< 8.7 U	< 11 U	< 17 U	< 66 U	< 3.7 U	< 20 U	< 21 U	< 7.8 U	< 18 U	< 8.2 U	< 35 U	< 21 U	< 14 U	< 13 U	< 10 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS2	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	< 5.9 U	< 7.7 U	< 12 U	< 44 U	< 2.5 U	< 14 U	< 14 U	< 5.3 U	< 12 U	< 5.6 U	< 24 U	< 14 U	< 9.8 U	< 8.8 U	< 6.9 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane	1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene	2-Hexanone
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report															
HVS-135	EHS-062918-HVS-135-1	Room 135	6/29/2018	1807029	< 7.2 U	< 7.2 U	8.0	< 4.8 U	< 4.8 U	< 4.7 U	< 5.5 U	< 5.4 U	< 5.4 U	< 8.3 U	< 17 U	29	< 5.8 U	< 51 U	< 19 U
HVS-135	EHS-062918-HVS-135-2	Room 135	6/29/2018	1807029	< 7.3 U	< 7.3 U	7.7	< 4.9 U	< 4.9 U	< 4.8 U	< 5.6 U	< 5.5 U	< 5.5 U	< 8.4 U	< 17 U	20	< 5.9 U	< 52 U	< 20 U
HVS-148	EHS-062918-HVS-148-1	Room 148	6/29/2018	1807029	< 7.0 U	< 7.0 U	1800	< 4.7 U	< 4.7 U	< 4.6 U	< 5.4 U	< 5.3 U	< 5.3 U	< 8.1 U	< 17 U	12	< 5.7 U	< 50 U	< 19 U
HVS-148	EHS-062918-HVS-148-2	Room 148	6/29/2018	1807029	< 7.3 U	< 7.3 U	2800 E	< 4.9 U	< 4.9 U	< 4.8 U	< 5.6 U	< 5.5 U	< 5.5 U	< 8.4 U	< 17 U	< 9.1 U	< 5.9 U	< 52 U	< 20 U
HVS-151	EHS-062918-HVS-151-1	Room 151A	6/29/2018	1807029	< 7.3 U	< 7.3 U	12	< 4.9 U	< 4.9 U	< 4.8 U	< 5.6 U	< 5.5 U	< 5.5 U	< 8.4 U	< 17 U	9.1	< 5.9 U	< 52 U	< 20 U
HVS-151	EHS-062918-HVS-151-2	Room 151A	6/29/2018	1807029	< 7.2 U	< 7.2 U	12	< 4.8 U	< 4.8 U	< 4.7 U	< 5.5 U	< 5.4 U	< 5.4 U	< 8.3 U	< 17 U	< 9.0 U	< 5.8 U	< 51 U	< 19 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-1	Hallway Near Main Entrance	7/16/2014	1407303	< 6.5 U	< 6.5 U	1600	< 4.4 U	< 4.4 U	< 4.3 U	< 5.0 U	< 4.9 U	< 4.9 U	< 7.6 U	< 16 U	< 8.2 U	210	< 46 U	< 18 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-2	Hallway Near Main Entrance	7/16/2014	1407303	< 6.5 U	< 6.5 U	1200	< 4.4 U	< 4.4 U	< 4.3 U	< 5.0 U	< 4.9 U	< 4.9 U	< 7.6 U	< 16 U	< 8.2 U	< 5.3 U	< 46 U	< 18 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS-1	Room 130	7/15/2014	1407281R1	< 28 U	< 28 U	820	< 18 U	< 18 U	23	< 21 U	< 21 U	< 21 U	< 32 U	< 66 U	< 34 U	< 22 U	< 200 U	< 75 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS2	Room 130	7/15/2014	1407281R1	< 17 U	< 17 U	650	< 12 U	< 12 U	< 11 U	< 13 U	< 13 U	< 13 U	< 20 U	< 41 U	< 22 U	< 14 U	< 120 U	< 47 U
SSHS-03-HVS	SSHS-07-16-14-03-HVS-02	Room 127	7/16/2014	1407303	< 88 U	< 88 U	440	< 59 U	< 59 U	69	< 68 U	< 66 U	< 66 U	< 100 U	< 210 U	< 110 U	< 72 U	< 620 U	< 240 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1	Room 127	7/16/2014	1407303	< 130 U	< 130 U	730	< 91 U	< 91 U	110	< 100 U	< 100 U	< 100 U	< 160 U	< 320 U	< 170 U	< 110 U	< 960 U	< 370 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1-DUP	Room 127	7/16/2014	1407303	< 130 U	< 130 U	640	< 89 U	< 89 U	100	< 100 U	< 99 U	< 99 U	< 150 U	< 320 U	< 160 U	< 110 U	< 930 U	< 360 U
SSHS-04-HVS	SSHS-07-15-14-04-HVS1	Room 125	7/15/2014	1407281R1	< 17 U	< 17 U	2300	< 11 U	< 11 U	< 11 U	< 13 U	< 12 U	< 12 U	< 19 U	< 40 U	< 21 U	< 14 U	< 120 U	< 45 U
SSHS-04-HVS	SSHS-7-15-14-04-HVS-2	Room 125	7/15/2014	1407281R1	< 17 U	< 17 U	2600	< 11 U	< 11 U	< 11 U	< 13 U	< 13 U	< 13 U	< 20 U	< 40 U	< 21 U	< 14 U	< 120 U	< 46 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS1	Room 124	7/15/2014	1407281R1	< 130 U	< 130 U	18000	< 90 U	< 90 U	< 88 U	< 100 U	< 100 U	< 100 U	< 160 U	< 320 U	< 170 U	< 110 U	< 950 U	< 360 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS2	Room 124	7/15/2014	1407281R1	< 40 U	< 40 U	5600	< 27 U	< 27 U	< 26 U	< 31 U	< 30 U	< 30 U	< 47 U	< 96 U	< 50 U	< 33 U	< 280 U	< 110 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-1	Room 122	7/15/2014	1407281R1	< 66 U	< 66 U	13000	< 44 U	< 44 U	< 44 U	< 51 U	< 50 U	< 50 U	< 77 U	< 160 U	< 83 U	< 54 U	< 470 U	< 180 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-2	Room 122	7/15/2014	1407281R1	< 89 U	< 89 U	12000	< 60 U	< 60 U	< 59 U	< 68 U	< 67 U	< 67 U	< 100 U	< 210 U	< 110 U	< 73 U	< 630 U	< 240 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS1	Room 120	7/15/2014	1407281R1	< 96 U	< 96 U	15000	< 64 U	< 64 U	< 63 U	< 74 U	< 72 U	< 72 U	< 110 U	< 230 U	< 120 U	< 78 U	< 680 U	< 260 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS2	Room 120	7/15/2014	1407281R1	< 68 U	< 68 U	13000	< 46 U	< 46 U	< 45 U	< 53 U	< 52 U	< 52 U	< 80 U	< 160 U	< 86 U	< 56 U	< 490 U	< 190 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-1	Hallway Outside Guidance Area	7/16/2014	1407303	< 16 U	< 16 U	100	< 11 U	< 11 U	< 11 U	< 13 U	< 12 U	< 12 U	< 19 U	< 39 U	< 20 U	< 13 U	< 120 U	< 45 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-2	Hallway Outside Guidance Area	7/16/2014	1407303	< 13 U	< 13 U	67	< 8.9 U	< 8.9 U	< 8.8 U	< 10 U	< 10 U	< 10 U	< 15 U	< 32 U	< 17 U	< 11 U	< 94 U	< 36 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-1	Hallway Outside Library	7/15/2014	1407281R1	< 10 U	< 10 U	64	< 6.9 U	< 6.9 U	< 6.7 U	< 7.8 U	< 7.7 U	< 7.7 U	< 12 U	< 24 U	< 13 U	< 8.4 U	< 72 U	< 28 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-2	Hallway Outside Library	7/15/2014	1407281R1	< 6.6 U	< 6.6 U	53	< 4.4 U	< 4.4 U	< 4.3 U	< 5.0 U	< 4.9 U	< 4.9 U	< 7.6 U	< 16 U	< 8.2 U	< 5.4 U	< 46 U	< 18 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-1	Room 101	7/16/2014	1407281R1	< 6.7 U	< 6.7 U	71	< 4.5 U	< 4.5 U	< 4.4 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.8 U	< 16 U	< 8.4 U	90	< 47 U	< 18 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-2	Room 101	7/16/2014	1407281R1	< 8.6 U	< 8.6 U	60	< 5.8 U	< 5.8 U	< 5.7 U	< 6.6 U	< 6.5 U	< 6.5 U	< 10 U	< 21 U	< 11 U	< 7.1 U	< 61 U	< 24 U
SSHS-11-HVS	SSHS-07-15-14-11-HVS-01	Room 115	7/15/2014	1407281R1	< 6.6 U	< 6.6 U	22	< 4.4 U	< 4.4 U	< 4.4 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.7 U	< 16 U	< 8.3 U	< 5.4 U	< 47 U	< 18 U
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2	Room 115	7/15/2014	1407281R1	< 6.7 U	< 6.7 U	21	< 4.5 U	< 4.5 U	< 4.4 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.8 U	< 16 U	< 8.4 U	< 5.5 U	< 48 U	< 18 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

					1,3-Dichlorobenzene	1,4-Dichlorobenzene	Dichlorodifluoromethane (Freon12)	1,1-Dichloroethane	1,2-Dichloroethane	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	1,2-Dichlorotetrafluoroethane (Freon 114)	1,4-Dioxane	Ethanol	4-Ethyltoluene	Hexachlorobutadiene	2-Hexanone
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report															
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2-DUP	Room 115	7/15/2014	1407281R1	< 6.7 U	< 6.7 U	21	< 4.5 U	< 4.5 U	< 4.4 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.8 U	< 16 U	< 8.4 U	< 5.4 U	< 47 U	< 18 U
SSHS-12-HVS	SSHS-07-15-14-12-HVS-02	Room 116	7/15/2014	1407281R1	< 27 U	< 27 U	4600	< 18 U	< 18 U	< 18 U	< 21 U	< 20 U	< 20 U	< 31 U	< 65 U	< 34 U	< 22 U	< 190 U	< 74 U
SSHS-12-HVS	SSHS-7-15-14-12-HVS-01	Room 116	7/15/2014	1407281R1	< 33 U	< 33 U	4800	< 22 U	< 22 U	< 22 U	< 25 U	< 25 U	< 25 U	< 38 U	< 78 U	< 41 U	< 27 U	< 230 U	< 89 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS1	Room 111	7/15/2014	1407281R1	< 6.7 U	< 6.7 U	750	< 4.5 U	< 4.5 U	< 4.4 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.8 U	< 16 U	< 8.4 U	< 5.5 U	< 48 U	< 18 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS2	Room 111	7/15/2014	1407281R1	< 6.8 U	< 6.8 U	1200	< 4.6 U	< 4.6 U	< 4.5 U	< 5.2 U	< 5.2 U	< 5.2 U	< 7.9 U	< 16 U	< 8.6 U	< 5.6 U	< 48 U	< 18 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS1	Room 106	7/15/2014	1407281R1	< 9.6 U	< 9.6 U	280	< 6.4 U	< 6.4 U	< 6.3 U	< 7.4 U	< 7.2 U	< 7.2 U	< 11 U	< 23 U	39	< 7.8 U	< 68 U	< 26 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS2	Room 106	7/15/2014	1407281R1	< 6.8 U	< 6.8 U	320	< 4.6 U	< 4.6 U	< 4.5 U	< 5.2 U	< 5.2 U	< 5.2 U	< 7.9 U	< 16 U	38	< 5.6 U	< 48 U	< 18 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-01	Back Stage	7/16/2014	1407303	< 67 U	< 67 U	16000	< 45 U	< 45 U	< 44 U	< 52 U	< 51 U	< 51 U	< 78 U	< 160 U	< 84 U	< 55 U	< 480 U	< 180 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-02	Back Stage	7/16/2014	1407303	< 13 U	< 13 U	3700	< 8.9 U	< 8.9 U	< 8.8 U	< 10 U	< 10 U	< 10 U	< 15 U	< 32 U	< 17 U	< 11 U	< 94 U	< 36 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-1	Hallway Outside Room 136A	7/16/2014	1407303	< 6.6 U	< 6.6 U	180	< 4.4 U	< 4.4 U	< 4.4 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.7 U	< 16 U	< 8.3 U	< 5.4 U	< 47 U	< 18 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-2	Hallway Outside Room 136A	7/16/2014	1407303	< 6.4 U	< 6.4 U	200	< 4.3 U	< 4.3 U	< 4.2 U	< 4.9 U	< 4.8 U	< 4.8 U	< 7.5 U	< 15 U	< 8.1 U	< 5.3 U	< 46 U	< 18 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-01	Hallway Outside Room 136A	7/16/2014	1407303	< 6.6 U	< 6.6 U	1600	< 4.4 U	< 4.4 U	< 4.4 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.7 U	< 16 U	< 8.3 U	< 5.4 U	< 47 U	< 18 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-02	Hallway Outside Room 136A	7/16/2014	1407303	< 6.9 U	< 6.9 U	840	< 4.7 U	< 4.7 U	< 4.6 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.1 U	< 17 U	< 8.7 U	< 5.7 U	< 49 U	< 19 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-01	Custodian's Storage	7/16/2014	1407303	< 22 U	< 22 U	5800	< 15 U	< 15 U	< 15 U	< 17 U	< 17 U	< 17 U	< 26 U	< 54 U	< 28 U	< 18 U	< 160 U	< 62 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-02	Custodian's Storage	7/16/2014	1407303	< 25 U	< 25 U	6700	< 17 U	< 17 U	< 16 U	< 19 U	< 19 U	< 19 U	< 29 U	< 59 U	< 31 U	< 20 U	< 180 U	< 67 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-01	Room 138A	7/16/2014	1407303	< 14 U	< 14 U	3100	< 9.2 U	< 9.2 U	< 9.0 U	< 10 U	< 10 U	< 10 U	< 16 U	< 33 U	< 17 U	< 11 U	< 97 U	< 37 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-02	Room 138A	7/16/2014	1407303	< 15 U	< 15 U	4500	< 10 U	< 10 U	< 9.9 U	< 12 U	< 11 U	< 11 U	< 18 U	< 36 U	< 19 U	< 12 U	< 110 U	< 41 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS1	Room 142 (Wellness Ctr)	7/16/2014	1407303	< 6.6 U	< 6.6 U	87	< 4.4 U	< 4.4 U	< 4.3 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.6 U	< 16 U	< 8.2 U	< 5.4 U	< 47 U	< 18 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS2	Room 142 (Wellness Ctr)	7/16/2014	1407303	< 6.5 U	< 6.5 U	140	< 4.4 U	< 4.4 U	< 4.3 U	< 5.0 U	< 4.9 U	< 4.9 U	< 7.6 U	< 16 U	< 8.2 U	< 5.3 U	< 46 U	< 18 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-1	Room 145 Nurses Office	7/16/2014	1407303	< 6.8 U	< 6.8 U	13	< 4.6 U	< 4.6 U	< 4.5 U	< 5.2 U	< 5.1 U	< 5.1 U	< 7.9 U	< 16 U	< 8.5 U	< 5.5 U	< 48 U	< 18 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-2	Room 145 Nurses Office	7/16/2014	1407303	< 6.7 U	< 6.7 U	12	< 4.5 U	< 4.5 U	< 4.4 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.8 U	< 16 U	< 8.4 U	< 5.4 U	< 47 U	< 18 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-01	Room 171 (Aux Gym)	7/16/2014	1407303	< 6.8 U	< 6.8 U	78	< 4.6 U	< 4.6 U	< 4.5 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.0 U	< 16 U	< 8.6 U	< 5.6 U	< 49 U	< 19 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-02	Room 171 (Aux Gym)	7/16/2014	1407303	< 6.6 U	< 6.6 U	180	< 4.4 U	< 4.4 U	< 4.3 U	< 5.1 U	< 5.0 U	< 5.0 U	< 7.6 U	< 16 U	< 8.2 U	< 5.4 U	< 47 U	< 18 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS1	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	< 10 U	< 10 U	27	< 6.8 U	< 6.8 U	< 6.7 U	< 7.8 U	< 7.7 U	< 7.7 U	< 12 U	< 24 U	< 13 U	< 8.3 U	< 72 U	< 28 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS2	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	< 6.9 U	< 6.9 U	29	< 4.6 U	< 4.6 U	< 4.5 U	< 5.3 U	< 5.2 U	< 5.2 U	< 8.0 U	< 16 U	< 8.6 U	< 5.6 U	< 49 U	< 19 U

DRAFT

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

					Isopropanol	Methyl Isobutyl Ketone	Methyl *T*-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon 11
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report										
HVS-135	EHS-062918-HVS-135-1	Room 135	6/29/2018	1807029	< 12 U	< 4.9 U	< 17 U	< 5.1 U	< 8.2 U	< 3.5 U	< 35 U	< 6.5 U	21	< 9.1 U
HVS-135	EHS-062918-HVS-135-2	Room 135	6/29/2018	1807029	< 12 U	< 5.0 U	< 17 U	< 5.2 U	< 8.3 U	< 3.6 U	< 36 U	< 6.6 U	29	< 9.3 U
HVS-148	EHS-062918-HVS-148-1	Room 148	6/29/2018	1807029	< 11 U	< 4.8 U	< 17 U	< 5.0 U	< 8.0 U	< 3.4 U	< 34 U	< 6.4 U	< 6.5 U	< 8.9 U
HVS-148	EHS-062918-HVS-148-2	Room 148	6/29/2018	1807029	< 12 U	< 5.0 U	< 17 U	< 5.2 U	< 8.3 U	< 3.6 U	< 36 U	< 6.6 U	< 6.8 U	< 9.3 U
HVS-151	EHS-062918-HVS-151-1	Room 151A	6/29/2018	1807029	< 12 U	< 5.0 U	< 17 U	< 5.2 U	< 8.3 U	74	< 36 U	< 6.6 U	< 6.8 U	< 9.3 U
HVS-151	EHS-062918-HVS-151-2	Room 151A	6/29/2018	1807029	< 12 U	< 4.9 U	< 17 U	< 5.1 U	< 8.2 U	< 3.5 U	< 35 U	< 6.5 U	< 6.7 U	< 9.1 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-1	Hallway Near Main Entrance	7/16/2014	1407303	< 11 U	< 4.4 U	< 3.9 U	< 4.6 U	< 7.4 U	< 3.2 U	< 32 U	< 5.9 U	< 6.1 U	< 8.3 U
SSHS-01-HVS	SSHS-7-16-14-1-HVS-2	Hallway Near Main Entrance	7/16/2014	1407303	< 11 U	< 4.4 U	< 3.9 U	< 4.6 U	< 7.4 U	< 3.2 U	< 32 U	< 5.9 U	< 6.1 U	< 8.3 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS-1	Room 130	7/15/2014	1407281R1	< 45 U	< 19 U	< 16 U	< 19 U	< 31 U	< 13 U	< 140 U	< 25 U	< 26 U	< 35 U
SSHS-02-HVS	SSHS-07-15-14-02-HVS2	Room 130	7/15/2014	1407281R1	< 28 U	< 12 U	< 10 U	< 12 U	< 20 U	< 8.5 U	< 85 U	< 16 U	< 16 U	< 22 U
SSHS-03-HVS	SSHS-07-16-14-03-HVS-02	Room 127	7/16/2014	1407303	< 140 U	< 60 U	< 53 U	< 62 U	< 100 U	< 43 U	< 430 U	< 80 U	< 82 U	< 110 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1	Room 127	7/16/2014	1407303	< 220 U	< 92 U	< 81 U	< 95 U	< 150 U	< 66 U	< 660 U	< 120 U	< 120 U	< 170 U
SSHS-03-HVS	SSHS-7-16-14-3-HVS-1-DUP	Room 127	7/16/2014	1407303	< 220 U	< 90 U	< 79 U	< 93 U	< 150 U	< 64 U	< 650 U	< 120 U	< 120 U	< 170 U
SSHS-04-HVS	SSHS-07-15-14-04-HVS1	Room 125	7/15/2014	1407281R1	< 27 U	< 11 U	< 10 U	< 12 U	< 19 U	< 8.2 U	< 82 U	< 15 U	< 16 U	< 21 U
SSHS-04-HVS	SSHS-7-15-14-04-HVS-2	Room 125	7/15/2014	1407281R1	< 28 U	< 12 U	< 10 U	< 12 U	< 19 U	< 8.3 U	< 83 U	< 15 U	< 16 U	< 22 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS1	Room 124	7/15/2014	1407281R1	< 220 U	< 91 U	< 80 U	< 95 U	< 150 U	< 66 U	< 660 U	< 120 U	< 120 U	< 170 U
SSHS-05-HVS	SSHS-07-15-14-05-HVS2	Room 124	7/15/2014	1407281R1	< 66 U	< 27 U	< 24 U	< 28 U	< 46 U	< 20 U	< 200 U	< 36 U	< 38 U	< 51 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-1	Room 122	7/15/2014	1407281R1	< 110 U	< 45 U	< 40 U	< 47 U	< 76 U	< 32 U	< 330 U	< 60 U	< 62 U	< 84 U
SSHS-06-HVS	SSHS-7-15-14-06-HVS-2	Room 122	7/15/2014	1407281R1	< 140 U	< 61 U	< 53 U	< 63 U	< 100 U	< 44 U	< 440 U	< 81 U	< 83 U	< 110 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS1	Room 120	7/15/2014	1407281R1	< 160 U	< 65 U	< 58 U	< 68 U	< 110 U	< 47 U	< 470 U	< 87 U	< 90 U	< 120 U
SSHS-07-HVS	SSHS-07-15-14-07-HVS2	Room 120	7/15/2014	1407281R1	< 110 U	< 47 U	< 41 U	< 48 U	< 78 U	< 34 U	< 340 U	< 62 U	< 64 U	< 87 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-1	Hallway Outside Guidance Area	7/16/2014	1407303	< 27 U	< 11 U	< 9.8 U	97	< 19 U	< 8.0 U	< 81 U	< 15 U	< 15 U	< 21 U
SSHS-08-HVS	SSHS-7-16-14-8-HVS-2	Hallway Outside Guidance Area	7/16/2014	1407303	< 22 U	< 9.0 U	< 8.0 U	28	< 15 U	< 6.5 U	< 66 U	< 12 U	< 12 U	< 17 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-1	Hallway Outside Library	7/15/2014	1407281R1	< 17 U	< 7.0 U	< 6.1 U	< 7.2 U	< 12 U	< 5.0 U	< 50 U	< 9.3 U	< 9.6 U	< 13 U
SSHS-09-HVS	SSHS-7-15-14-9-HVS-2	Hallway Outside Library	7/15/2014	1407281R1	< 11 U	< 4.5 U	< 3.9 U	< 4.6 U	< 7.5 U	< 3.2 U	< 32 U	< 5.9 U	< 6.1 U	< 8.4 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-1	Room 101	7/16/2014	1407281R1	< 11 U	< 4.5 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.3 U	< 33 U	< 6.0 U	6.7	< 8.5 U
SSHS-10-HVS	SSHS-7-16-14-10-HVS-2	Room 101	7/16/2014	1407281R1	< 14 U	< 5.9 U	< 5.2 U	< 6.1 U	< 9.9 U	< 4.2 U	< 43 U	< 7.8 U	< 8.1 U	< 11 U
SSHS-11-HVS	SSHS-07-15-14-11-HVS-01	Room 115	7/15/2014	1407281R1	< 11 U	< 4.5 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.2 U	< 33 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2	Room 115	7/15/2014	1407281R1	< 11 U	< 4.6 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	< 8.5 U

TABLE 5-3
HVS Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

					Isopropanol	Methyl Isobutyl Ketone	Methyl *T*-Butyl Ether (MTBE)	Styrene	1,1,2,2-Tetrachloroethane	Tetrahydrofuran	1,2,4-Trichlorobenzene	1,1,2-Trichloroethane	Trichlorofluoromethane (Freon 11)	1,1,2-Trichloro-1,2,2-Trifluoroethane (Freon 11
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample Location	Sample Name	EHS Building Location	Sample Date	Lab Report										
SSHS-11-HVS	SSHS-7-15-14-11-HVS-2-DUP	Room 115	7/15/2014	1407281R1	< 11 U	< 4.5 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.3 U	< 33 U	< 6.0 U	< 6.2 U	< 8.5 U
SSHS-12-HVS	SSHS-07-15-14-12-HVS-02	Room 116	7/15/2014	1407281R1	< 44 U	< 18 U	< 16 U	< 19 U	< 31 U	< 13 U	< 130 U	< 24 U	< 25 U	< 34 U
SSHS-12-HVS	SSHS-7-15-14-12-HVS-01	Room 116	7/15/2014	1407281R1	< 54 U	< 22 U	< 20 U	< 23 U	< 37 U	< 16 U	< 160 U	< 30 U	< 31 U	< 42 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS1	Room 111	7/15/2014	1407281R1	< 11 U	< 4.6 U	< 4.0 U	< 4.8 U	< 7.7 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	< 8.6 U
SSHS-13-HVS	SSHS-07-15-14-13-HVS2	Room 111	7/15/2014	1407281R1	< 11 U	< 4.6 U	< 4.1 U	< 4.8 U	< 7.8 U	< 3.3 U	< 34 U	< 6.2 U	< 6.4 U	< 8.7 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS1	Room 106	7/15/2014	1407281R1	< 16 U	< 6.5 U	< 5.8 U	< 6.8 U	< 11 U	< 4.7 U	< 47 U	< 8.7 U	< 9.0 U	< 12 U
SSHS-14-HVS	SSHS-07-15-14-14-HVS2	Room 106	7/15/2014	1407281R1	< 11 U	< 4.6 U	< 4.1 U	< 4.8 U	< 7.8 U	< 3.3 U	< 34 U	< 6.2 U	< 6.4 U	< 8.7 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-01	Back Stage	7/16/2014	1407303	< 110 U	< 46 U	< 40 U	< 48 U	< 77 U	< 33 U	< 330 U	< 61 U	< 63 U	< 86 U
SSHS-15-HVS	SSHS-07-16-14-15-HVS-02	Back Stage	7/16/2014	1407303	< 22 U	< 9.0 U	< 8.0 U	< 9.4 U	< 15 U	< 6.5 U	< 66 U	< 12 U	< 12 U	< 17 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-1	Hallway Outside Room 136A	7/16/2014	1407303	< 11 U	< 4.5 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.2 U	< 33 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-16-HVS	SSHS-7-16-14-16-HVS-2	Hallway Outside Room 136A	7/16/2014	1407303	< 10 U	< 4.4 U	< 3.8 U	< 4.6 U	< 7.3 U	< 3.2 U	< 32 U	< 5.8 U	< 6.0 U	< 8.2 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-01	Hallway Outside Room 136A	7/16/2014	1407303	< 11 U	< 4.5 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.2 U	< 33 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-17-HVS	SSHS-07-16-14-17-HVS-02	Hallway Outside Room 136A	7/16/2014	1407303	< 11 U	< 4.7 U	< 4.2 U	< 4.9 U	< 7.9 U	< 3.4 U	< 34 U	< 6.3 U	< 6.5 U	< 8.8 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-01	Custodian's Storage	7/16/2014	1407303	< 37 U	< 15 U	< 14 U	< 16 U	< 26 U	< 11 U	< 110 U	< 20 U	69	< 29 U
SSHS-18-HVS	SSHS-07-16-14-18-HVS-02	Custodian's Storage	7/16/2014	1407303	< 40 U	< 17 U	< 15 U	< 17 U	< 28 U	< 12 U	< 120 U	< 22 U	75	< 31 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-01	Room 138A	7/16/2014	1407303	< 22 U	< 9.3 U	< 8.2 U	< 9.7 U	< 16 U	< 6.7 U	< 67 U	< 12 U	< 13 U	< 17 U
SSHS-19-HVS	SSHS-07-16-14-19-HVS-02	Room 138A	7/16/2014	1407303	< 25 U	< 10 U	< 9.0 U	< 11 U	< 17 U	< 7.4 U	< 74 U	< 14 U	< 14 U	< 19 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS1	Room 142 (Wellness Ctr)	7/16/2014	1407303	< 11 U	< 4.5 U	< 3.9 U	< 4.7 U	< 7.5 U	< 3.2 U	< 32 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-20-HVS	SSHS-7-16-14-20-HVS2	Room 142 (Wellness Ctr)	7/16/2014	1407303	< 11 U	< 4.4 U	< 3.9 U	< 4.6 U	< 7.4 U	< 3.2 U	< 32 U	< 5.9 U	< 6.1 U	< 8.3 U
SSHS-21-HVS	SSHS-7-16-14-21-HVS-1	Room 145 Nurses Office	7/16/2014	1407303	< 11 U	< 4.6 U	< 4.0 U	< 4.8 U	< 7.7 U	< 3.3 U	< 33 U	< 6.1 U	< 6.3 U	11
SSHS-21-HVS	SSHS-7-16-14-21-HVS-2	Room 145 Nurses Office	7/16/2014	1407303	< 11 U	< 4.5 U	< 4.0 U	< 4.7 U	< 7.6 U	< 3.3 U	< 33 U	< 6.0 U	< 6.2 U	< 8.5 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-01	Room 171 (Aux Gym)	7/16/2014	1407303	18	180	< 4.1 U	< 4.8 U	< 7.8 U	< 3.4 U	< 34 U	< 6.2 U	< 6.4 U	< 8.7 U
SSHS-22-HVS	SSHS-07-16-14-22-HVS-02	Room 171 (Aux Gym)	7/16/2014	1407303	< 11 U	47	< 3.9 U	< 4.7 U	< 7.5 U	< 3.2 U	< 32 U	< 6.0 U	< 6.2 U	< 8.4 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS1	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	< 17 U	< 6.9 U	< 6.1 U	< 7.2 U	< 12 U	< 5.0 U	< 50 U	< 9.2 U	< 9.5 U	< 13 U
SSHS-23-HVS	SSHS-07-16-14-23-HVS2	Room 156 (Girls Locker Room)	7/16/2014	1407281R1	< 11 U	< 4.7 U	< 4.1 U	< 4.9 U	< 7.9 U	< 3.4 U	< 34 U	< 6.2 U	< 6.4 U	< 8.8 U

Notes
VOCs - Volatile Organic Compounds
ug/m3 - micrograms per meter cubed
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at the value indicated
"--" Analyte not reported
Lab method used: TO-15/TO-15_SIM - VOCs
NA: Not available
Shaded cells identify indoor air samples collected subsequent to SSDS installation and located within the area of influence
NYSDOH Matrix Outcome - Mitigate
NFA: No Further Action

Sub-slab vapor concentrations are shaded in accordance with the outcomes presented on NYSDOH Soil Vapor/Indoor Air Matrix Guidelines. Sample locations with a sub-slab vapor concentration equal to or greater than the applicable Matrix indoor-air concentration value are categorized as "Mitigate" and are shown in blue.

Samples with detection limits exceeding applicable monitor guidance concentrations are shown in **orange.**

DRAFT

Notes

PCBs - Polychlorinated Biphenyls
SVOCs - Semivolatile Organic Compounds
VOCs - Volatile Organic Compounds
PAH - Polycyclic Aromatic Hydrocarbons
PFAS - Per- and Polyfluoroalkyl Substances
µg/kg - micrograms per kilogram
mg/kg - milligrams per kilogram
ft bgs - Feet Below Ground Surface
ft bfg - Feet Below Final Grade
-- Sample was not within Final Grade limits or located beneath field house and unable to be surveyed or verified
^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA, DLCK or MRL standard: Instrument related QC is outside acceptance limits.
^+ - Continuing Calibration Verification (CCV) is outside acceptance limits, high biased.
* - LCS or LCSD is outside acceptance limits
*+ - LCS and/or LCSD is outside acceptance limits, high biased
*1 - LCS/LCSD RPD exceeds control limits
*3 - ISTD response or retention time outside acceptable limits
B - Compound detected in method blank
E - Exceeds instrument calibration range.
F1 - MS and/or MSD Recovery is outside acceptance limits.
F2 - MS/MSD RPD exceeds control limits
H - Sample was received and analyzed past holding time.
I - Value is EMPC (estimated maximum possible concentration)
EMPC - Estimated maximum possible concentration
p - The %RPD between the primary and confirmation column/detector is >40%. The lower value has been reported
J- - The analyte was positively identified; however, the associated numerical value is likely to be lower than the concentration of the analyte in the sample due to negative bias of associated QC or calibration data or attributable to matrix interference
J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated QC or calibration data or attributable to matrix interference.
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
R - The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence
T - Indicates that a quality control parameter has exceeded laboratory limits
U - non-detect at the value indicated
UJ - The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
Samples collected by NYSDEC in "May-October 2000 NYSDEC Sampling Report" included sample depths as "surface". These samples are assumed to have been collected from 0-0.5 ft bgs.

[1] - Ground surface elevation at the time of sampling is only provided for soil boring locations

[2] - Final grade elevation provided for samples remaining in place. Final grade elevations were not collected for samples outside of the BCP Boundary and are denoted as "--"

[3] - Change in surface elevation calculates for soil boring locations that have not been excavated. Positive values indicate net increase in ground surface elevation, negative values indicate net decrease in ground surface elevation.

[4] - Grab sample elevation provided for IRM and ISMP sample locations. Elevation represents point at which grab sample was collected.

[5] - Sample depth at time of sampling provided for grab samples and soil boring. For IRM/ISMP samples, sample depth at time of sampling represents the depth interval in which the associated grab sample was collected within. For soil borings, sample depth at time of sampling represents the depth interval from which a composite sample was collected.

[6] - Sample depth from final grade calculated for both IRM/ISMP and soil boring sample locations left in place (not excavated). Sample depth from final grade calculated for IRM/ISMP sample locations by comparing sample elevation to final grade elevation (i.e., final grade elevation of 857.18 ft amsl minus sample elevation of 847.44 ft amsl equals sample depth below final grade of 9.74 ft below final grade). Sample depth from final grade calculated for boring locations by comparing surface elevation at the time of sampling to the final grade elevation and correcting sample depths based on alterations to ground surface elevation (i.e., Surface elevation at time of sampling of 853.54 ft amsl and final grade elevation of 855.13 ft amsl indicates surface elevation increased 1.59 ft after sample collection. A sample previously collected at this location from 12-14 ft below ground surface [at the time of sampling] is now located 13.59-15.59 ft below final grade.)

[7] - For excavation status, soil boring samples that did not have their entire composite depth excavated are denoted as "Not Excavated" (i.e., sample depths only partially excavated are shown as left in place)
Lab method used: 8082A/ SW8082A - PCBs
Lab method used: 6010C/SW6010C/SW6010D - Metals, SW6020B - Manganese, SW7470A/SW7471B - Mercury
Lab method used: 8270D/SW8270D/8270D_LL/SW8270E/8270E-LL - SVOCs
Lab method used: 8260C/SW8260C/8260C_LL/SW8260D - VOCs
Lab Method used: E537(M)/PFC_IDA - PFAS
Soil Cleanup Objectives presented derived from 6 NYCRR PART 375 Table 375-6-8(b) (May 2023)
Analyte concentrations detected above Unrestricted Soil Cleanup Objectives are presented in light gray
Analyte concentrations detected above Restricted Residential Soil Cleanup Objectives are presented in dark gray
Analyte concentrations detected above Protection of Groundwater Soil Cleanup Objectives are presented in blue font
Analyte concentrations with potential to exhibit the characteristic of toxicity for metals are presented in black
Analyte concentrations detected above New York State Hazardous Waste Criteria are presented in black with red text

DRAFT

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	13.75	< 0.027 U	< 0.034 U	< 0.031 U	< 0.029 U	13	< 0.026 U	0.75	< 0.039 U	< 0.023 U
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-0-2	7/22/2015	849.40	0 - 2 ft	180-46170-1	Excavated	39.7	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	29 J	9.5 J	1.2 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-0-2	7/22/2015	849.32	0 - 2 ft	180-46170-1	Excavated	92.6	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	66 J	24 J	2.6 J	< 0.36 U	< 0.19 U
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-0-2	7/22/2015	849.26	0 - 2 ft	180-46170-1	Excavated	38.3	< 0.079 U	< 0.097 U	< 0.13 U	< 0.098 U	27 J	10 J	1.3 J	< 0.14 U	< 0.078 U
Football Field	SSHS-B1055	SSHS-B1055-SS	5/22/2018	857.15	0 - 0.17 ft	180-77978-1	Excavated	0.022	< 0.0079 U	< 0.016 U	< 0.014 U	< 0.015 U	< 0.019 U	0.022 J	< 0.0069 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B1056	SSHS-B1056-SS	5/22/2018	857.26	0 - 0.17 ft	180-77978-1	Excavated	0.38	< 0.0078 U	< 0.016 U	< 0.014 U	< 0.014 U	0.25 J	0.13 J	< 0.0068 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B1057	SSHS-B1057-SS	5/22/2018	857.02	0 - 0.17 ft	180-77978-1	Excavated	0.026	< 0.0094 U	< 0.019 U	< 0.017 U	< 0.017 U	0.026 J	< 0.02 U	< 0.0082 U	< 0.02 U	< 0.014 U
Football Field	SSHS-B1058	SSHS-B1058-SS	5/22/2018	857.09	0 - 0.17 ft	180-77978-1	Excavated	ND	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	< 0.016 U	< 0.0066 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B1059	SSHS-B1059-SS	5/22/2018	857.18	0 - 0.17 ft	180-77978-1	Excavated	ND	< 0.0083 U	< 0.017 U	< 0.015 U	< 0.015 U	< 0.02 U	< 0.017 U	< 0.0073 U	< 0.018 U	< 0.012 U
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-0-2	7/22/2015	849.39	0 - 2 ft	180-46170-1	Excavated	13.45	< 0.043 U	< 0.052 U	< 0.072 U	< 0.053 U	9.5 J	3.4 J	0.55 J	< 0.077 U	< 0.042 U
Rear Parking Lot	SSHS-B1063	SSHS-B1063-SUB-0-2	6/19/2018	852.50	0 - 2 ft	200-43950-2	Not Excavated	0.0081	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.0081 J	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1064	SSHS-B1064-SUB-0-2	6/23/2018	850.48	0 - 2 ft	200-44028-1	Excavated	ND	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-0-2	6/24/2018	850.40	0 - 2 ft	200-44046-1	Excavated	89.9	< 1.7 UJ	< 1.7 UJ	< 1.7 UJ	< 1.7 UJ	65 J	22 J	2.9 J	< 1.7 UJ	< 1.7 UJ
Rear Parking Lot	SSHS-B1069	SSHS-B1069-SUB-0-2	6/26/2018	850.14	0 - 2 ft	200-44065-1	Excavated	0.0266	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.018 J	0.0086 J	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-0-2	7/22/2015	849.10	0 - 2 ft	180-46170-1	Excavated	5.47	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	3.9 J	1.4 J	0.17 J	< 0.0073 U	< 0.004 U
Rear Parking Lot	SSHS-B1070	SSHS-B1070-SUB-0-2	6/24/2018	850.30	0 - 2 ft	200-44046-1	Excavated	2.09	< 0.029 UJ	< 0.029 UJ	< 0.029 UJ	< 0.029 UJ	1.4 J	0.59 J	0.1 J	< 0.029 UJ	< 0.029 UJ
Rear Parking Lot	SSHS-B1071	DUP-2	6/23/2018	852.51	0 - 2 ft	200-44028-1	Excavated	0.0081	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.0081 J	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1071	SSHS-B1071-SUB-0-2	6/23/2018	852.51	0 - 2 ft	200-44028-1	Excavated	ND	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U
Rear Parking Lot	SSHS-B1075	SSHS-B1075-SUB-0-2	6/23/2018	852.95	0 - 2 ft	200-44028-1	Excavated	5.97	< 0.058 U	< 0.058 U	< 0.058 U	< 0.058 U	4.3 J	1.5 J	0.17 J	< 0.058 U	< 0.058 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-0-2	7/22/2015	849.57	0 - 2 ft	180-46170-1	Excavated	1.135	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.0051 U	0.71 J	0.34 J	0.085 J	< 0.0074 U	< 0.004 U
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-0-2	7/21/2015	850.20	0 - 2 ft	180-46139-1	Excavated	3.086	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	2.2 J	0.79 J	0.096 J	< 0.0066 U	< 0.0036 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated	14					14				
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-0-2	7/21/2015	850.42	0 - 2 ft	180-46139-1	Excavated	0.2957	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.22 J	0.067 J	0.0087 J	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-0-2	7/21/2015	850.45	0 - 2 ft	180-46139-1	Excavated	0.0919	< 0.0034 U	< 0.0042 U	< 0.0058 U	< 0.0043 U	0.068 J	0.019 J	0.0049 J	< 0.0062 U	< 0.0034 U
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-0-2	7/22/2015	850.70	0 - 2 ft	180-46170-1	Excavated	0.0083	< 0.0035 U	< 0.0043 U	< 0.006 U	< 0.0044 U	0.0083 J	< 0.0041 U	< 0.0038 U	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-0-2	7/21/2015	850.38	0 - 2 ft	180-46139-1	Excavated	6.11	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	4.2 J	1.7 J	0.21 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-0-2	7/20/2015	850.54	0 - 2 ft	180-46139-1	Excavated	3.15	< 0.0036 U	< 0.0044 U	< 0.006 U	< 0.0044 U	2.2 J	0.85 J	0.1 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-0-2	7/20/2015	850.60	0 - 2 ft	180-46139-1	Excavated	42.5	< 0.075 U	< 0.093 U	< 0.13 U	< 0.093 U	31 J	9.9 J	1.6 J	< 0.14 U	< 0.074 U
Rear Parking Lot	SSHS-B118	PS-FD-#12	7/20/2015	850.73	0 - 2 ft	180-46075-1	Excavated	263	< 0.37 U	< 0.46 U	< 0.63 U	< 0.46 U	180 J	71 J	12 J	< 0.67 U	< 0.37 U
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-0-2	7/20/2015	850.73	0 - 2 ft	180-46075-1	Excavated	243	< 0.37 U	< 0.45 U	< 0.62 U	< 0.45 U	170 J	65 J	8 J	< 0.66 U	< 0.36 U
Rear Parking Lot	SSHS-B1189	DUP-1	6/16/2018	853.96	0 - 2 ft	200-43950-2	Excavated	0.0079	< 0.0031 U	< 0.0031 U	< 0.0031 U	< 0.0031 U	0.0079 J	< 0.0031 U	< 0.0031 U	< 0.0031 U	< 0.0031 U
Rear Parking Lot	SSHS-B1189	SSHS-B1189-SUB-0-2	6/16/2018	853.96	0 - 2 ft	200-43950-2	Excavated	0.012	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U	0.012 J	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-0-2	7/21/2015	850.77	0 - 2 ft	180-46139-1	Excavated	42	< 0.071 U	< 0.087 U	< 0.12 U	< 0.088 U	30 J	11 J	1 J	< 0.13 U	< 0.07 U
Rear Parking Lot	SSHS-B1190	SSHS-B1190-SUB-0-2	6/19/2018	853.92	0 - 2 ft	200-43950-2	Excavated	6.7	< 0.15 U	< 0.15 U	< 0.15 U	< 0.15 U	6.7	< 0.15 U	< 0.15 U	< 0.15 U	< 0.15 U
Rear Parking Lot	SSHS-B1191	SSHS-B1191-SUB-0-2	6/19/2018	853.59	0 - 2 ft	200-43950-2	Excavated	26	< 0.89 U	< 0.89 U	< 0.89 U	< 0.89 U	26	< 0.89 U	< 0.89 U	< 0.89 U	< 0.89 U
Rear Parking Lot	SSHS-B1192	SSHS-B1192-SUB-0-2	6/26/2018	852.13	0 - 2 ft	200-44065-1	Excavated	3.72	< 0.059 U	< 0.059 U	< 0.059 U	< 0.059 U	2.6 J	0.96 J	0.16 J	< 0.059 U	< 0.059 U
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-0-2	6/25/2018	851.62	0 - 2 ft	200-44046-1	Excavated	0.654	< 0.012 UJ	< 0.012 UJ	< 0.012 UJ	< 0.012 UJ	0.44 J	0.19 J	0.024 J	< 0.012 UJ	< 0.012 UJ
Rear Parking Lot	SSHS-B1194	SSHS-B1194-SUB-0-2	6/23/2018	851.92	0 - 2 ft	200-44028-1	Excavated	2.836	< 0.029 U	< 0.029 U	< 0.029 U	< 0.029 U	2 J	0.75 J	0.086 J	< 0.029 U	< 0.029 U
Rear Parking Lot	SSHS-B1195	SSHS-B1195-SUB-0-2	6/26/2018	849.43	0 - 2 ft	200-44065-1	Excavated	37.2	< 0.7 U	< 0.7 U	< 0.7 U	< 0.7 U	26 J	9.5 J	1.7 J	< 0.7 U	< 0.7 U
Rear Parking Lot	SSHS-B1196	SSHS-B1196-SUB-0-2	6/16/2018	853.82	0 - 2 ft	200-43950-2	Excavated	0.0079	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U	0.0079 J	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	ND	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U		
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-0-2	7/21/2015	850.98	0 - 2 ft	180-46139-1	Excavated	67.8	< 0.18 U	< 0.22 U	< 0.31 U	< 0.23 U	48 J	17 J	2.8 J	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-0-2	7/24/2015	851.01	0 - 2 ft	180-46251-1	Excavated	3.99	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.9 J	0.98 J	0.11 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B122	PS-FD-#23	7/22/2015	851.00	0 - 2 ft	180-46170-1	Excavated	0.007	< 0.0036 U	< 0.0045 U	< 0.0061 U	< 0.0045 U	0.007 J	< 0.0042 U	< 0.0039 U	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-0-2	7/22/2015	851.00	0 - 2 ft	180-46170-1	Excavated	0.0247	< 0.0035 U	< 0.0043 U	< 0.006 U	< 0.0044 U	0.02 J	0.0047 J	< 0.0038 U	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-0-2	8/3/2015	851.17	0 - 2 ft	180-46601-1	Excavated	1.893	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	1.2 J	0.65 J	0.043 J	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-0-2	7/31/2015	850.91	0 - 2 ft	180-46444-1	Excavated	0.35	< 0.0035 U	< 0.0044 U	< 0.006 U	< 0.0044 U	0.24 J	0.096 J	0.014 J	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-0-2	7/31/2015	850.94	0 - 2 ft	180-46444-1	Excavated	9.91	< 0.037 U	< 0.045 U	< 0.062 U	< 0.045 U	6.6 J	2.8 J	0.51 J	< 0.066 U	< 0.036 U
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-0-2	7/31/2015	850.97	0 - 2 ft	180-46444-1	Excavated	16.78	< 0.035 U	< 0.043 U	< 0.06 U	< 0.044 U	11 J	5 J	0.78 J	< 0.064 U	< 0.035 U
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-0-2	7/31/2015	851.20	0 - 2 ft	180-46444-1	Excavated	94.8	< 0.19 U	< 0.23 U	< 0.31 U	< 0.23 U	66 J	25 J	3.8 J	< 0.34 U	< 0.18 U
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	0.15	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	0.15	< 0.044 U	< 0.044 U		
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-0-2	7/21/2015	851.31	0 - 2 ft	180-46139-1	Excavated	24.96	< 0.036 U	< 0.045 U	< 0.062 U	< 0.045 U	18 J	6 J	0.96 J	< 0.066 U	< 0.036 U
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-0-2	7/24/2015	851.52	0 - 2 ft	180-46251-1	Excavated	0.943	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.65 J	0.25 J	0.043 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-0-2	7/22/2015	851.41	0 - 2 ft	180-46170-1	Excavated	0.813	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.56 J	0.22 J	0.033 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-0-2	8/3/2015	852.64	0 - 2 ft	180-46601-1	Not Excavated	0.722	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	0.44 J	0.24 J	0.042 J	< 0.0066 U	< 0.0036 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B135	SSHS-B135-SUB-0-2	7/27/2015	856.16	0 - 2 ft	180-46300-1	Excavated	1.449	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.88 J	0.49 J	0.079 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B138	SSHS-B138-SUB-0-2	7/27/2015	855.68	0 - 2 ft	180-46300-1	Excavated	0.55	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.32 J	0.19 J	0.04 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-0-2	8/3/2015	851.34	0 - 2 ft	180-46601-1	Excavated	5.65	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	3.6 J	1.9 J	0.15 J	< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B1395a	SSHS-B1395-SUB-0-2	7/28/2018	851.59	0 - 2 ft	180-80273-1	Excavated	0.261	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.22 J	0.041 J	< 0.0053 U	< 0.013 U	< 0.009 U
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	ND	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U		
Rear Parking Lot	SSHS-B140	SSHS-B140-SUB-0-2	7/31/2015	851.74	0 - 2 ft	180-46444-1	Excavated	2.18	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	1.4 J	0.64 J	0.14 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-0-2	7/21/2015	851.79	0 - 2 ft	180-46139-1	Excavated	2.063	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	1.4 J	0.61 J	0.053 J	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-0-2	7/21/2015	851.86	0 - 2 ft	180-46139-1	Excavated	21.91	< 0.073 U	< 0.089 U	< 0.12 U	< 0.09 U	15 J	6.1 J	0.81 J	< 0.13 U	< 0.072 U
Rear Parking Lot	SSHS-B143	SSHS-B143-SUB-0-1	7/21/2015	852.07	0 - 1 ft	180-46139-1	Excavated	0.767	< 0.0034 U	< 0.0042 U	< 0.0058 U	< 0.0043 U	0.54 J	0.2 J	0.027 J	< 0.0062 U	< 0.0034 U
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-0-2	7/21/2015	851.71	0 - 2 ft	180-46139-1	Excavated	91	< 0.18 U	< 0.22 U	< 0.31 U	< 0.22 U	66 J	21 J	4 J	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-0-2	7/24/2015	851.85	0 - 2 ft	180-46251-1	Excavated	3.1	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	2.1 J	0.89 J	0.11 J	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-0-2	7/22/2015	851.73	0 - 2 ft	180-46170-1	Excavated	0.0075	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.0075 J	< 0.0041 U	< 0.0038 U	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-0-2	7/23/2015	852.20	0 - 2 ft	180-46218-1	Excavated	0.931	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	0.66 J	0.24 J	0.031 J	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-0-2	8/3/2015	852.19	0 - 2 ft	180-46601-1	Excavated	ND	< 0.0034 U	< 0.0042 U	< 0.0058 U	< 0.0043 U	< 0.0042 U	< 0.004 U	< 0.0037 U	< 0.0062 U	< 0.0034 U
Rear Parking Lot	SSHS-B149	PS-FD-#19	7/21/2015	852.27	0 - 2 ft	180-46139-1	Excavated	0.349	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.22 J	0.11 J	0.019 J	< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-0-2	7/21/2015	852.27	0 - 2 ft	180-46139-1	Excavated	0.282	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.17 J	0.097 J	0.015 J	< 0.0065 U	< 0.0035 U
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	0.19	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	0.19	< 0.043 U	< 0.043 U		
Football Field	SSHS-B150	SSHS-B150-SUB-0-2	7/27/2015	855.84	0 - 2 ft	180-46300-1	Excavated	12.12	< 0.02 U	< 0.025 U	< 0.034 U	< 0.025 U	7.9 J	3.7 J	0.52 J	< 0.036 U	< 0.02 U
Football Field	SSHS-B151	SSHS-B151-SS	8/5/2015	854.80	0 - 0.17 ft	180-46628-2	Excavated	3.6	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	1.9 J	1.5 J	0.2 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B156	SSHS-B156-SUB-0-2	8/3/2015	852.91	0 - 2 ft	180-46601-1	Excavated	16.43	< 0.072 U	< 0.088 U	< 0.12 U	< 0.089 U	11 J	4.9 J	0.53 J	< 0.13 U	< 0.071 U
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-0-2	7/31/2015	852.12	0 - 2 ft	180-46444-1	Excavated	14.93	< 0.018 U	< 0.022 U	< 0.03 U	< 0.022 U	9.8 J	4.4 J	0.73 J	< 0.032 U	< 0.018 U
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-0-2	7/21/2015	852.02	0 - 2 ft	180-46139-1	Excavated	0.439	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.29 J	0.12 J	0.029 J	< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B159	CS-FD-#25	8/3/2015	852.33	0 - 2 ft	180-46601-1	Excavated	62.1	< 0.18 U	< 0.22 U	< 0.3 U	< 0.22 U	43 J	17 J	2.1 J	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-0-2	8/3/2015	852.33	0 - 2 ft	180-46601-1	Excavated	106.2	< 0.36 U	< 0.44 U	< 0.61 U	< 0.45 U	82 J	22 J	2.2 J	< 0.65 U	< 0.36 U
Football Field	SSHS-B15-A	SSHS-B15-A-SS	7/22/2014	856.92	0 - 0.17 ft	180-35079-1	Excavated	0.152	< 0.00067 U	< 0.00085 U	< 0.00077 U	< 0.00073 U	0.086 J	0.066 J	< 0.00064 U	< 0.00098 U	< 0.00057 U
Football Field	SSHS-B15-A	SSHS-DUP7	7/22/2014	856.92	0 - 0.17 ft	180-35079-1	Excavated	ND	< 0.0014 U	< 0.0017 U	< 0.0016 U	< 0.0015 U	< 0.00086 U	< 0.0013 U	< 0.0013 U	< 0.002 U	< 0.0012 U
Football Field	SSHS-B15-B	SSHS-B15-B-SS	7/22/2014	856.80	0 - 0.17 ft	180-35079-1	Excavated	1.02	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	0.62 J	0.4 J	< 0.0013 U	< 0.0021 U	< 0.0012 U
Football Field	SSHS-B15-C	SSHS-B15-C-SS	7/22/2014	856.91	0 - 0.17 ft	180-35079-1	Excavated	0.07	< 0.0013 U	< 0.0017 U	< 0.0015 U	< 0.0015 U	0.038 J	0.032 J	< 0.0013 U	< 0.002 U	< 0.0011 U
Rear Parking Lot	SSHS-B160	SSHS-B160-SUB-0-1.5	7/21/2015	852.12	0 - 1.5 ft	180-46139-1	Excavated	23.31	< 0.069 U	< 0.085 U	< 0.12 U	< 0.086 U	15 J	7.4 J	0.91 J	< 0.13 U	< 0.068 U
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-0-2	8/3/2015	852.38	0 - 2 ft	180-46601-1	Excavated	21.88	< 0.071 U	< 0.087 U	< 0.12 U	< 0.088 U	15 J	6.3 J	0.58 J	< 0.13 U	< 0.07 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-0-2	8/3/2015	852.38	0 - 2 ft	180-46601-1	Excavated	1.38	< 0.0035 U	< 0.0042 U	< 0.0059 U	< 0.0043 U	1 J	0.38 J		< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B163	CS-FD-#23	8/3/2015	852.21	0 - 2 ft	180-46601-1	Excavated	4.36	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	2.7 J	1.5 J	0.16 J	< 0.0067 U	< 0.0036 U
Rear Parking Lot	SSHS-B163	SSHS-B163-SUB-0-2	8/3/2015	852.21	0 - 2 ft	180-46601-1	Excavated	4.54	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	3 J	1.4 J	0.14 J	< 0.0065 U	< 0.0036 U
Football Field	SSHS-B164	CS-FD-#1	7/27/2015	855.84	0 - 2 ft	180-46300-1	Excavated	4.91	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.1 J	1.6 J	0.21 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B164	SSHS-B164-SUB-0-2	7/27/2015	855.84	0 - 2 ft	180-46300-1	Excavated	2.21	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	1.4 J	0.71 J	0.1 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B165	SSHS-B165-SUB-0-2	7/27/2015	855.61	0 - 2 ft	180-46300-1	Excavated	1.9	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	1.2 J	0.59 J	0.11 J	< 0.0069 U	< 0.0037 U
Football Field	SSHS-B166	SSHS-B166-SUB-0-2	7/27/2015	855.88	0 - 2 ft	180-46300-1	Excavated	0.51	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0047 U	0.39 J	0.12 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B168	SSHS-B168-SUB-0-2	7/27/2015	855.64	0 - 2 ft	180-46300-1	Excavated	1.082	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.68 J	0.33 J	0.072 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B169	SSHS-B169-SS	7/28/2015	855.30	0 - 0.17 ft	180-46310-1	Excavated	1.74	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	1 J	0.63 J	0.11 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B169B	B169-B	8/3/2017	855.30	0 - 0.5 ft	180-68926-1	Excavated	0.74	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	0.37	0.27	0.1	< 0.014 U	< 0.0061 U
Football Field	SSHS-B170	SSHS-B170-SUB-0-2	7/27/2015	856.27	0 - 2 ft	180-46300-1	Excavated	0.27	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.16 J	0.09 J	0.02 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B173	SSHS-B173-SS	8/5/2015	854.70	0 - 0.17 ft	180-46628-2	Excavated	3.6	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	2 J	1.4 J	0.2 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B175	SSHS-B175-SS	7/28/2015	855.09	0 - 0.17 ft	180-46310-1	Excavated	0.321	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.14 J	0.13 J	0.051 J	< 0.0073 U	< 0.004 U
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	11					11				
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	9.5					9.5				
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	8.4					8.4				
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated	ND	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	< 0.016 U	< 0.0066 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated	0.321	< 0.0073 U	< 0.015 U	< 0.013 U	< 0.013 U	< 0.018 U	0.26	0.061	< 0.016 U	< 0.011 U
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated	0.23	< 0.0073 U	< 0.014 U	< 0.013 U	< 0.013 U	0.07	0.16	< 0.0064 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated	ND	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.0062 U	< 0.015 U	< 0.011 U
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated	ND	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	0.86	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.41	0.34	0.11	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated	ND	< 0.0077 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.019 U	< 0.016 U	< 0.0067 U	< 0.017 U	< 0.011 U
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated	0.152	< 0.0076 U	< 0.015 U	< 0.014 U	< 0.014 U	0.063	0.089	< 0.0067 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated	0.015	< 0.0071 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	0.015 J	< 0.0062 U	< 0.015 U	< 0.011 U
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated	ND	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	< 0.016 U	< 0.0066 U	< 0.016 U	< 0.011 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated	ND	< 0.0079 U	< 0.016 U	< 0.014 U	< 0.015 U	< 0.019 U	< 0.017 U	< 0.0069 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated	ND	< 0.008 U	< 0.016 U	< 0.015 U	< 0.015 U	< 0.02 U	< 0.017 U	< 0.007 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated	0.3	< 0.0077 U	< 0.015 U	< 0.014 U	< 0.014 U	0.18	0.12	< 0.0067 U	< 0.017 U	< 0.011 U
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated	0.142	< 0.0078 U	< 0.016 U	< 0.014 U	< 0.014 U	0.08	0.062	< 0.0069 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated	0.021	< 0.008 U	< 0.016 U	< 0.015 U	< 0.015 U	< 0.019 U	0.021 J	< 0.007 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated	0.018	< 0.0077 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.019 U	0.018 J	< 0.0067 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated	0.048	< 0.0082 U	< 0.016 U	< 0.015 U	< 0.015 U	0.026	0.022 J	< 0.0071 U	< 0.018 U	< 0.012 U
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated	ND	< 0.0097 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.02 U	< 0.0085 U	< 0.021 U	< 0.014 U
Football Field	SSHS-B212	SSHS-B212-SUB-0-2	7/28/2015	855.42	0 - 2 ft	180-46310-1	Excavated	21.45	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	15 J	6 J	0.45 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated	0.099	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	0.037	0.062	< 0.0061 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated	0.091	< 0.0079 U	< 0.016 U	< 0.014 U	< 0.014 U	0.045	0.046	< 0.0069 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated	0.24	< 0.0077 U	< 0.015 U	< 0.014 U	< 0.014 U	0.13	0.11	< 0.0067 U	< 0.017 U	< 0.011 U
Football Field	SSHS-B214	SSHS-B214-SUB-0-2	7/28/2015	855.97	0 - 2 ft	180-46310-1	Excavated	0.76	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.32 J	0.36 J	0.08 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B216	SSHS-B216-SUB-0-2	7/16/2015	855.82	0 - 2 ft	180-46033-1	Excavated	15.4	< 0.02 U	< 0.025 U	< 0.034 U	< 0.025 U	11 J	4.4 J	< 0.021 U	< 0.036 U	< 0.02 U
Football Field	SSHS-B217	SSHS-B217-SUB-0-2	7/16/2015	856.26	0 - 2 ft	180-46033-1	Excavated	0.69	< 0.0042 U	< 0.0051 U	< 0.007 U	< 0.0052 U	0.48 J	0.21 J	< 0.0045 U	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B218	SSHS-B218-SUB-0-2	7/16/2015	856.58	0 - 2 ft	180-46033-1	Excavated	2.276	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	1.5 J	0.7 J	0.076 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	0.958	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.58	0.28	0.098	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	3.61	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7	1.7	0.21	< 0.013 U	< 0.009 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	1.697	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	1	0.63	0.067	< 0.013 U	< 0.0086 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	1.63	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	1.1	0.44	0.09	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated	0.15	< 0.0078 U	< 0.016 U	< 0.014 U	< 0.014 U	< 0.019 U	0.15	< 0.0068 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated	0.986	< 0.0078 U	< 0.015 U	< 0.014 U	< 0.014 U	0.5	0.44	0.046	< 0.017 U	< 0.012 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	19.8	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	15	4.8		< 0.13 U	< 0.091 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	23.52	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	18	4.7	0.82	< 0.13 U	< 0.091 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	9.5	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	6.2	3	0.3	< 0.067 U	< 0.046 U
Football Field	SSHS-B220	SSHS-B220-SUB-0-2	7/28/2015	855.52	0 - 2 ft	180-46310-1	Excavated	4.278	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.1 J	1.1 J	0.078 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B221	SSHS-B221-SUB-0-2	7/15/2015	855.95	0 - 2 ft	180-45961-1	Excavated	20.2	< 0.08 U	< 0.098 U	< 0.14 U	< 0.099 U	14 J	6.2 J	< 0.086 U	< 0.14 U	< 0.079 U
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated	0.025	< 0.0077 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.019 U	0.025	< 0.0068 U	< 0.017 U	< 0.012 U
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated	0.27	< 0.0073 U	< 0.014 U	< 0.013 U	< 0.013 U	0.12	0.15	< 0.0063 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated	0.076	< 0.0087 U	< 0.017 U	< 0.016 U	< 0.016 U	0.027	0.049	< 0.0076 U	< 0.019 U	< 0.013 U
Football Field	SSHS-B222	SSHS-B222-SUB-0-2	7/16/2015	856.64	0 - 2 ft	180-46033-1	Excavated	0.967	< 0.0042 U	< 0.0051 U	< 0.007 U	< 0.0052 U	0.61 J	0.31 J	0.047 J	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B223	SSHS-B223-SUB-0-2	7/28/2015	856.68	0 - 2 ft	180-46310-1	Excavated	1.88	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	1 J	0.69 J	0.19 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	0.52	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.14	0.26	0.12	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	0.5	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.14	0.25	0.11	< 0.013 U	< 0.0091 U
Football Field	SSHS-B225	SSHS-B225-SUB-0-2	7/28/2015	855.94	0 - 2 ft	180-46310-1	Excavated	7.64	< 0.0039 U,F1	< 0.0048 U	< 0.0066 U	< 0.0048 U	5.4 J	2.1 J	0.14 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B226	SSHS-B226-SUB-0-2	7/15/2015	856.35	0 - 2 ft	180-45961-1	Excavated	9.79	< 0.041 U	< 0.05 U	< 0.069 U	< 0.051 U	9.6	< 0.048 U	0.19 J	< 0.074 U	< 0.04 U
Football Field	SSHS-B227	SSHS-B227-SUB-0-2	7/15/2015	856.71	0 - 2 ft	180-45961-1	Excavated	11.19	< 0.04 U	< 0.05 U	< 0.069 U	< 0.05 U	11	< 0.047 U	0.19 J	< 0.073 U	< 0.04 U
Football Field	SSHS-B228	SSHS-B228-SUB-0-2	7/15/2015	856.95	0 - 2 ft	180-45961-1	Excavated	0.137	< 0.004 U	< 0.005 U	< 0.0069 U	< 0.005 U	< 0.005 U	0.099 J	0.038 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B229	PS-FD-#3	7/15/2015	857.03	0 - 2 ft	180-45961-1	Excavated	5.91	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	4 J	1.8 J	0.11 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B229	SSHS-B229-SUB-0-2	7/15/2015	857.03	0 - 2 ft	180-45961-1	Excavated	4	< 0.004 U	< 0.005 U	< 0.0069 U	< 0.005 U	2.7 J	1.2 J	0.1 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B230	SSHS-B230-SUB-0-2	7/28/2015	857.08	0 - 2 ft	180-46310-1	Excavated	1.771	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	1.3 J	0.43 J	0.041 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B231	SSHS-B231-SUB-0-2	7/27/2015	856.10	0 - 2 ft	180-46300-1	Excavated	23.11	< 0.039 U	< 0.048 U	< 0.067 U	< 0.049 U	17 J	5.5 J	0.61 J	< 0.071 U	< 0.039 U
Football Field	SSHS-B232	SSHS-B232-SUB-0-2	7/27/2015	856.44	0 - 2 ft	180-46300-1	Excavated	3.61	< 0.0039 U	< 0.0047 U	< 0.0066 U	< 0.0048 U	2.3 J	1.1 J	0.21 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B233	SSHS-B233-SUB-0-2	7/28/2015	856.93	0 - 2 ft	180-46310-1	Excavated	56.1	< 0.08 U	< 0.098 U	< 0.13 U	< 0.099 U	40 J	15 J	1.1 J	< 0.14 U	< 0.079 U
Football Field	SSHS-B234A	SSHS-B234A-SUB-0-2	7/28/2015	857.08	0 - 2 ft	180-46310-1	Excavated	0.652	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.36 J	0.21 J	0.082 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B236	SSHS-B236-SUB-0-2	7/14/2015	856.80	0 - 2 ft	180-45961-1	Excavated	0.0933	< 0.0037 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	0.052 J	0.032 J	0.0093 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B237	SSHS-B237-SUB-0-2	7/27/2015	857.09	0 - 2 ft	180-46300-1	Excavated	2.8	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	1.7 J	0.99 J	0.11 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B238	SSHS-B238-SUB-0-2	7/14/2015	856.59	0 - 2 ft	180-45961-1	Excavated	0.886	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.54 J	0.29 J	0.056 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B239	SSHS-B239-SUB-0-2	7/14/2015	857.05	0 - 2 ft	180-45961-1	Excavated	14.23	< 0.04 U	< 0.049 U	< 0.068 U	< 0.05 U	14	< 0.047 U	0.23	< 0.072 U	< 0.039 U
Football Field	SSHS-B240	SSHS-B240-SUB-0-2	7/27/2015	857.39	0 - 2 ft	180-46300-1	Excavated	0.608	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.36 J	0.21 J	0.038 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B241	SSHS-B241-SUB-0-2	7/14/2015	856.84	0 - 2 ft	180-45961-1	Excavated	0.356	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.23 J	0.11 J	0.016 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B241	PS-FD-#1	7/15/2015	856.84	0 - 2 ft	180-45961-1	Excavated	0.522	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.35 J	0.16 J	0.012 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B242	SSHS-B242-SUB-0-2	7/27/2015	857.07	0 - 2 ft	180-46300-1	Excavated	93.4	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	67 J	24 J	2.4 J	< 0.36 U	< 0.19 U
Football Field	SSHS-B2450	SSHS-B2450-SS	8/24/2018	855.62	0 - 0.17 ft	180-81268-1	Excavated	0.093	< 0.0078 U	< 0.015 U	< 0.014 U	< 0.014 U	0.033	0.043	0.017 J	< 0.017 U	< 0.012 U
Football Field	SSHS-B2451	SSHS-B2451-SS	8/24/2018	855.47	0 - 0.17 ft	180-81268-1	Excavated	0.082	< 0.0074 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	0.06	0.022 J	< 0.016 U	< 0.011 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2452	SSHS-B2452-SS	8/24/2018	855.90	0 - 0.17 ft	180-81268-1	Excavated	0.047	< 0.0076 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	0.033	0.014 J	< 0.016 U	< 0.011 U
Football Field	SSHS-B2453	SSHS-B2453-SS	8/24/2018	856.09	0 - 0.17 ft	180-81268-1	Excavated	0.226	< 0.0077 U	< 0.015 U	< 0.014 U	< 0.014 U	0.11	0.094	0.022 J	< 0.017 U	< 0.012 U
Football Field	SSHS-B2454	SSHS-B2454-SS	8/24/2018	856.33	0 - 0.17 ft	180-81268-1	Excavated	0.185	< 0.0076 U	< 0.015 U	< 0.014 U	< 0.014 U	0.085	0.082	0.018 J	< 0.016 U	< 0.011 U
Football Field	SSHS-B2455	PS-FD-2	8/24/2018	855.95	0 - 0.17 ft	180-81268-1	Excavated	0.047	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	0.034	0.013 J	< 0.016 U	< 0.011 U
Football Field	SSHS-B2455	SSHS-B2455-SS	8/24/2018	855.95	0 - 0.17 ft	180-81268-1	Excavated	0.063	< 0.0076 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.019 U	0.047	0.016 J	< 0.016 U	< 0.011 U
Football Field	SSHS-B246	SSHS-B246-SUB-0-2	7/30/2015	856.12	0 - 2 ft	180-46426-1	Excavated	0.486	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	0.27 J	0.19 J	0.026 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B248	PS-FD-#11	7/20/2015	856.87	0 - 2 ft	180-46075-1	Excavated	1.306	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.88 J	0.38 J	0.046 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B248	SSHS-B248-SUB-0-2	7/20/2015	856.87	0 - 2 ft	180-46075-1	Excavated	1.128	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.74 J	0.35 J	0.038 J	< 0.0074 U	< 0.004 U
Football Field	SSHS-B249	SSHS-B249-SUB-0-2	7/30/2015	856.83	0 - 2 ft	180-46426-1	Excavated	0.0442	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.021 J	0.017 J	0.0062 J	< 0.0074 U	< 0.004 U
Football Field	SSHS-B250	CS-FD-#15	7/30/2015	856.50	0 - 2 ft	180-46426-1	Excavated	1.196	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.62 J	0.49 J	0.086 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B250	SSHS-B250-SUB-0-2	7/30/2015	856.50	0 - 2 ft	180-46426-1	Excavated	1.135	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.57 J	0.47 J	0.095 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B251	SSHS-B251-SUB-0-2	7/20/2015	856.76	0 - 2 ft	180-46075-1	Excavated	1.146	< 0.0042 U	< 0.0052 U	< 0.0071 U	< 0.0052 U	0.77 J	0.33 J	0.046 J	< 0.0076 U	< 0.0041 U
Football Field	SSHS-B252	SSHS-B252-SUB-0-2	7/20/2015	856.86	0 - 2 ft	180-46075-1	Excavated	0.1541	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.098 J	0.051 J	0.0051 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B253	SSHS-B253-SUB-0-2	7/30/2015	856.85	0 - 2 ft	180-46426-1	Excavated	0.183	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.086 J	0.072 J	0.025 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B254	SSHS-B254-SUB-0-2	7/30/2015	856.06	0 - 2 ft	180-46426-1	Excavated	0.559	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.33 J	0.2 J	0.029 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B255	SSHS-B255-SUB-0-2	7/30/2015	856.67	0 - 2 ft	180-46426-1	Excavated	1.667	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.97 J	0.61 J	0.087 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B256	SSHS-B256-SUB-0-2	7/20/2015	856.85	0 - 2 ft	180-46075-1	Excavated	104.5	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	68 J	33 J	3.5 J	< 0.34 U	< 0.19 U
Football Field	SSHS-B257	CS-FD-#16	7/30/2015	856.92	0 - 2 ft	180-46426-1	Excavated	2.7	< 0.0044 U	< 0.0054 U	< 0.0074 U	< 0.0054 U	1.6 J	0.98 J	0.12 J	< 0.008 U	< 0.0043 U
Football Field	SSHS-B257	SSHS-B257-SUB-0-2	7/30/2015	856.92	0 - 2 ft	180-46426-1	Excavated	0.801	< 0.0042 U	< 0.0052 U	< 0.0071 U	< 0.0052 U	0.48 J	0.28 J	0.041 J	< 0.0076 U	< 0.0041 U
Football Field	SSHS-B259	SSHS-B259-SUB-0-2	7/29/2015	855.79	0 - 2 ft	180-46367-1	Excavated	0.941	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	0.7 J	0.15 J	0.091 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B260	SSHS-B260-SUB-0-2	7/29/2015	856.02	0 - 2 ft	180-46367-1	Excavated	2.098	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	1.2 J	0.8 J	0.098 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B2603A	SSHS-B2603A-SS	6/12/2019	855.23	0 - 0.17 ft	180-91215-1	Excavated	5.92	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	3.1 J	2.3 J	0.52 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B261	SSHS-B261-SUB-0-2	7/17/2015	855.83	0 - 2 ft	180-46045-1	Excavated	2.31	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	1.4 J	0.79 J	0.12 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B262	SSHS-B262-SUB-0-2	7/29/2015	855.62	0 - 2 ft	180-46367-1	Excavated	2.44	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	1.5 J	0.83 J	0.11 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B2624A	PS-FD-1	6/12/2019	855.29	0 - 0.17 ft	180-91215-1	Excavated	0.199	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.12 J	0.056 J	0.023 J	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B2624A	SSHS-B2624A-SS	6/12/2019	855.29	0 - 0.17 ft	180-91215-1	Excavated	0.245	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.16 J	0.059 J	0.026 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B264	SSHS-B264-SUB-0-2	7/17/2015	855.93	0 - 2 ft	180-46045-1	Excavated	3.82	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.1 J	1.4 J	0.32 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B265	SSHS-B265-SUB-0-2	7/17/2015	855.73	0 - 2 ft	180-46045-1	Excavated	11.01	< 0.019 U	< 0.023 U	< 0.032 U	< 0.023 U	7.2 J	3.3 J	0.51 J	< 0.034 U	< 0.019 U
Football Field	SSHS-B266	PS-FD-#8	7/17/2015	855.92	0 - 2 ft	180-46045-1	Excavated	4.62	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	2.7 J	1.6 J	0.32 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B266	SSHS-B266-SUB-0-2	7/17/2015	855.92	0 - 2 ft	180-46045-1	Excavated	3.35	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	1.9 J	1.2 J	0.25 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B267	SSHS-B267-SUB-0-2	7/30/2015	855.57	0 - 2 ft	180-46426-1	Excavated	0.0701	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.029 J	0.032 J	0.0091 J	< 0.0065 U	< 0.0035 U
Football Field	SSHS-B268	SSHS-B268-SUB-0-2	7/29/2015	855.75	0 - 2 ft	180-46367-1	Excavated	7.64	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	6.4 J	0.86 J	0.38 J	< 0.068 U	< 0.037 U
Football Field	SSHS-B269	PS-FD-#9	7/17/2015	855.71	0 - 2 ft	180-46045-1	Excavated	22	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	15 J	6.2 J	0.8 J	< 0.069 U	< 0.037 U
Football Field	SSHS-B269	SSHS-B269-SUB-0-2	7/17/2015	855.71	0 - 2 ft	180-46045-1	Excavated	37.4	< 0.038 U	< 0.047 U	< 0.065 U	< 0.048 U	25 J	11 J	1.4 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B270	SSHS-B270-SUB-0-2	7/17/2015	855.94	0 - 2 ft	180-46045-1	Excavated	3.04	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	1.9 J	0.96 J	0.18 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2703A	SSHS-B2703A-SS	6/12/2019	855.18	0 - 0.17 ft	180-91215-1	Excavated	5.23	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	2.9 J	1.9 J	0.43 J	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B271	SSHS-B271-SUB-0-2	7/17/2015	855.95	0 - 2 ft	180-46045-1	Excavated	5.02	< 0.0041 U	< 0.0051 U	< 0.007 U	< 0.0051 U	3 J	1.7 J	0.32 J	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B2717A	SSHS-B2717A-SS	6/12/2019	856.07	0 - 0.17 ft	180-91215-1	Excavated	1.64	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.87 J	0.52 J	0.25 J	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B273	CS-FD-#10	7/29/2015	855.95	0 - 2 ft	180-46367-1	Excavated	1.74	< 0.0042 U	< 0.0052 U	< 0.0071 U	< 0.0052 U	1.2 J	0.33 J	0.21 J	< 0.0076 U	< 0.0042 U
Football Field	SSHS-B273	SSHS-B273-SUB-0-2	7/29/2015	855.95	0 - 2 ft	180-46367-1	Excavated	2.31	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	1.1 J	1 J	0.21 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B274	SSHS-B274-SUB-0-2	7/29/2015	856.07	0 - 2 ft	180-46367-1	Excavated	5.74	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	3.3 J	2.2 J	0.24 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B275	SSHS-B275-SUB-0-2	7/17/2015	856.07	0 - 2 ft	180-46045-1	Excavated	2.99	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	1.8 J	1 J	0.19 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B276	SSHS-B276-SUB-0-2	7/29/2015	856.16	0 - 2 ft	180-46367-1	Excavated	3.73	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	3.5 J		0.23 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B277	SSHS-B277-SUB-0-2	7/29/2015	855.87	0 - 2 ft	180-46367-1	Excavated	3.17	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.3 J	0.72 J	0.15 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B278	SSHS-B278-SUB-0-2	7/16/2015	855.94	0 - 2 ft	180-46033-1	Excavated	1.11	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.69 J	0.36 J	0.06 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B279	SSHS-B279-SUB-0-2	7/29/2015	856.14	0 - 2 ft	180-46367-1	Excavated	2.37	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1.7 J	0.52 J	0.15 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B280	PS-FD-#6	7/16/2015	855.92	0 - 2 ft	180-46033-1	Excavated	2.269	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	1.4 J	0.78 J	0.089 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B280	SSHS-B280-SUB-0-2	7/16/2015	855.92	0 - 2 ft	180-46033-1	Excavated	1.86	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	1.1 J	0.69 J	0.07 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B281	SSHS-B281-SUB-0-2	7/17/2015	856.15	0 - 2 ft	180-46045-1	Excavated	9.29	< 0.019 U	< 0.023 U	< 0.032 U	< 0.023 U	5.9 J	3.1 J	0.29 J	< 0.034 U	< 0.019 U
Football Field	SSHS-B282	CS-FD-#12	7/29/2015	855.62	0 - 2 ft	180-46367-1	Excavated	2.86	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	2 J	0.69 J	0.17 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B282	SSHS-B282-SUB-0-2	7/29/2015	855.62	0 - 2 ft	180-46367-1	Excavated	2.33	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1.5 J	0.68 J	0.15 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B283	SSHS-B283-SUB-0-2	7/16/2015	855.95	0 - 2 ft	180-46033-1	Excavated	17.4	< 0.077 U	< 0.095 U	< 0.13 U	< 0.096 U	12 J	5.4 J	< 0.083 U	< 0.14 U	< 0.076 U
Football Field	SSHS-B284	CS-FD-#13	7/29/2015	856.13	0 - 2 ft	180-46367-1	Excavated	12.55	< 0.036 U	< 0.044 U	< 0.061 U	< 0.045 U	9.3 J	2.7 J	0.55 J	< 0.066 U	< 0.036 U
Football Field	SSHS-B284	SSHS-B284-SUB-0-2	7/29/2015	856.13	0 - 2 ft	180-46367-1	Excavated	12.74	< 0.037 U	< 0.045 U	< 0.062 U	< 0.045 U	9.4 J	2.8 J	0.54 J	< 0.066 U	< 0.036 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	7/14/2015	856.00	0 - 2 ft	180-45961-1	Not Excavated	0.877	< 0.0038	< 0.0046	< 0.0064	< 0.0047	0.51	0.29	0.077	< 0.0069	< 0.0037
Northern Athletic Field	SSHS-B286	SSHS-B286-SUB-0-2	7/14/2015	856.40	0 - 2 ft	180-45961-1	Excavated	2.59	< 0.0038	< 0.0047	< 0.0065	< 0.0047	1.7	0.7	0.19	< 0.0069	< 0.0038

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B287	SSHS-B287-SUB-0-2	7/14/2015	856.16	0 - 2 ft	180-45961-1	Excavated	3.38	< 0.0038	< 0.0047	< 0.0065	< 0.0048	2.3	0.84	0.24	< 0.007	< 0.0038
Northern Athletic Field	SSHS-B288	SSHS-B288-SUB-0-2	7/24/2015	856.22	0 - 2 ft	180-46251-2	Excavated	1.81	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1 J	0.63 J	0.18 J	< 0.0066 U	< 0.0036 U
Northern Athletic Field	SSHS-B289	SSHS-B289-SUB-0-2	7/24/2015	856.37	0 - 2 ft	180-46251-2	Excavated	1.88	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1 J	0.68 J	0.2 J	< 0.0066 U	< 0.0036 U
Northern Athletic Field	SSHS-B290	SSHS-B290-SUB-0-2	7/24/2015	856.36	0 - 2 ft	180-46251-2	Excavated	2.15	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	1.1 J	0.79 J	0.26 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B295	SSHS-B295-SS	7/24/2015	852.68	0 - 0.17 ft	180-46251-2	Excavated	0.0427	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	0.014 J	0.019 J	0.0097 J	< 0.0065 U	< 0.0036 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated	14					14				
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated	0.052	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	0.052	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated	0.012	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	0.012 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated	0.146	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	0.061 J	0.085 J	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.008 U	< 0.003 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated	ND	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated	0.035	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	0.035	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated	ND	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	< 0.0053 U	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated	0.017	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	0.017 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated	0.026	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.01 J	0.016 J	< 0.0065 U	< 0.008 U	< 0.0031 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated	0.0278	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.0088 J	0.019 J	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B303	SSHS-B303-SUB-0-1	8/5/2015	854.42	0 - 1 ft	180-46628-2	Excavated	0.096	< 0.0036 U	< 0.0044 U	< 0.006 U	< 0.0044 U	0.023 J	0.048 J	0.025 J	< 0.0064 U	< 0.0035 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.0068 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated	0.223	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	0.13 J	0.093 J	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated	ND	< 0.0074 U	< 0.0081 U	< 0.0055 U	< 0.0033 U	< 0.0055 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated	ND	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.007 U	< 0.0066 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated	0.631	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.36 J	0.23 J	0.041 J	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B304	SSHS-B304-SUB-0-1	8/5/2015	855.55	0 - 1 ft	180-46628-2	Excavated	0.0066	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	< 0.0044 U	0.0066 J	< 0.0038 U	< 0.0065 U	< 0.0035 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated	0.0218	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	0.0098 J	0.012 J	< 0.0066 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated	0.377	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.12 J	0.2 J	0.057 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated	0.0227	< 0.007 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.0077 J	0.015 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated	0.172	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.055 J	0.082 J	0.035 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated	0.015	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	0.015 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.0077 U	< 0.0084 U	< 0.0058 U	< 0.0035 U	< 0.0057 U	< 0.0071 U	< 0.0068 U	< 0.0084 U	< 0.0032 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.007 U	< 0.0066 U	< 0.0082 U	< 0.0031 U
Football Field	SSHS-B305	SSHS-B305-SS	7/14/2015	855.32	0 - 0.17 ft	180-45961-2	Excavated	ND	< 0.0041	< 0.005	< 0.0069	< 0.005	< 0.005	< 0.0047	< 0.0043	< 0.0073	< 0.004
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated	ND	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	< 0.0056 U	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	ND	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated	0.1	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0032 U	0.041 J	0.059 J	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated	1.7	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.84 J	0.71 J	0.15 J	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated	0.084	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.022 J	0.062 J		< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated	0.195	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.1 J	0.06 J	0.035 J	< 0.0075 U	< 0.0029 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated	0.195	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	0.085 J	0.11 J	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B306	SSHS-B306-SUB-0-2	3/1/2016	856.22	0 - 2 ft	180-52611-1	Excavated	2.5	< 0.0085	< 0.013	< 0.0047	< 0.0069	1.4	0.8	0.3	< 0.0058	< 0.0035
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated	0.01	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	0.01 J	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated	0.0062	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	0.0062 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated	0.192	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	0.099 J	0.059 J	0.034 J	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated	0.063	< 0.0071 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.023 J	0.027 J	0.013 J	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated	ND	< 0.0076 U	< 0.0078 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated	0.394	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	0.19 J	0.14 J	0.064 J	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated	0.471	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	0.15 J	0.23 J	0.091 J	< 0.0082 U	< 0.0031 U
Football Field	SSHS-B308	SSHS-B308-SUB-0-2	3/2/2016	857.14	0 - 2 ft	180-52664-1	Excavated	1.327	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.92 J	0.35 J	0.057 J	< 0.0063 U	< 0.0038 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated	0.62	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	0.12 J	0.32 J	0.18 J	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated	0.042	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.028 J	0.014 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated	0.446	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	0.18 J	0.21 J	0.056 J	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated	0.453	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	0.16 J	0.2 J	0.093 J	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated	0.009	< 0.0074 U	< 0.0081 U	< 0.0055 U	< 0.0033 U	< 0.0055 U	0.009 J	< 0.0065 U	< 0.008 U	< 0.0031 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated	1.2	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.67 J	0.35 J	0.18 J	< 0.0079 U	< 0.003 U
Football Field	SSHS-B309	SSHS-B309-SUB-0-2	3/2/2016	855.88	0 - 2 ft	180-52664-1	Excavated	0.141	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	0.1 J	0.041 J	< 0.0071 U	< 0.0065 U	< 0.0039 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated	0.494	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.31 J	0.14 J	0.044 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	0.0244	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.015 J	0.0094 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B310	SSHS-B310-SUB-0-2	3/2/2016	854.81	0 - 2 ft	180-52664-1	Excavated	2.45	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	1.8 J	0.54 J	0.11 J	< 0.0058 U	< 0.0035 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.008 U	< 0.0087 U	< 0.006 U	< 0.0036 U	< 0.0059 U	< 0.0074 U	< 0.007 U	< 0.0087 U	< 0.0033 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.0074 U	< 0.0081 U	< 0.0056 U	< 0.0033 U	< 0.0055 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B311	SSHS-B311-SUB-0-2	3/2/2016	854.93	0 - 2 ft	180-52664-1	Excavated	4.61	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	3.2 J	1.1 J	0.31 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated	ND	< 0.0089 U	< 0.0097 U	< 0.0067 U	< 0.004 U	< 0.0066 U	< 0.0082 U	< 0.0078 U	< 0.0096 U	< 0.0037 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B314	PS-FD-5	3/2/2016	856.85	0 - 2 ft	180-52664-1	Excavated	14.41	< 0.091 U	< 0.14 U	< 0.05 U	< 0.073 U	10 J	4 J	0.41 J	< 0.061 U	< 0.037 U
Football Field	SSHS-B314	SSHS-B314-SUB-0-2	3/2/2016	856.85	0 - 2 ft	180-52664-1	Excavated	15.15	< 0.091 U	< 0.14 U	< 0.05 U	< 0.074 U	10 J	4.8 J	0.35 J	< 0.062 U	< 0.037 U
Football Field	SSHS-B315	PS-FD-1	3/1/2016	855.19	0 - 0.17 ft	180-52611-1	Excavated	3.71	< 0.011 U	< 0.017 U	< 0.0059 U	< 0.0086 U	3.4	< 0.0086 U	0.31	< 0.0073 U	< 0.0044 U
Football Field	SSHS-B315	SSHS-B315-SS	3/1/2016	855.19	0 - 0.17 ft	180-52611-1	Excavated	3.31	< 0.011 U	< 0.017 U	< 0.0059 U	< 0.0087 U	3	< 0.0088 U	0.31	< 0.0074 U	< 0.0044 U
Football Field	SSHS-B316	PS-FD-3	3/2/2016	856.16	0 - 2 ft	180-52664-1	Excavated	8.36	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	6 J	2 J	0.36 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B316	SSHS-B316-SUB-0-2	3/2/2016	856.16	0 - 2 ft	180-52664-1	Excavated	6.18	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	4.8 J	1.2 J	0.18 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B317	SSHS-B317-SUB-0-2	3/1/2016	856.52	0 - 2 ft	180-52611-1	Excavated	0.222	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	0.16	< 0.0076 U	0.062	< 0.0064 U	< 0.0038 U
Football Field	SSHS-B318	SSHS-B318-SUB-0-2	3/2/2016	856.20	0 - 2 ft	180-52664-1	Excavated	0.233	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.12 J	0.084 J	0.029 J	< 0.0063 U	< 0.0038 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated	3.02	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	1.1 J	1.4 J	0.52 J	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated	ND	< 0.0074 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B320	SSHS-B320-SUB-0-2	3/2/2016	856.57	0 - 2 ft	180-52664-1	Excavated	3.29	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	2 J	1.1 J	0.19 J	< 0.0064 U	< 0.0038 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated	0.15	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	< 0.0055 U	0.15	< 0.0065 U	< 0.008 U	< 0.0031 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated	ND	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.007 U	< 0.0066 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated	0.011	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	0.011 J	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	0.058	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.036 J	0.022 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated	0.034	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.019 J	0.015 J	< 0.0064 U	< 0.008 U	< 0.003 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated	0.256	< 0.0077 U	< 0.0084 U	< 0.0058 U	< 0.0035 U	0.087 J	0.11 J	0.059 J	< 0.0083 U	< 0.0032 U
Football Field	SSHS-B324	SSHS-B324-SS	3/1/2016	855.23	0 - 0.17 ft	180-52611-1	Excavated	0.842	< 0.011 U	< 0.017 U	< 0.0058 U	< 0.0085 U	0.75	< 0.0085 U	0.092	< 0.0072 U	< 0.0043 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0-0.17	12/19/2019	857.74	0 - 0.17 ft	180-100363-3	Excavated	ND	< 0.0084 U	< 0.0091 U	< 0.0063 U	< 0.0038 U	< 0.0062 U	< 0.0078 U	< 0.0073 U	< 0.0091 U	< 0.0035 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0-0.17	12/19/2019	857.37	0 - 0.17 ft	180-100363-1	Excavated	0.027	< 0.0083 U	< 0.009 U	< 0.0062 U	< 0.0037 U	0.014 J	0.013 J	< 0.0072 U	< 0.0089 U	< 0.0034 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0-0.17	12/19/2019	858.13	0 - 0.17 ft	180-100363-1	Excavated	0.038	< 0.0084 U	< 0.0091 U	< 0.0063 U	< 0.0038 U	0.014 J	0.024 J	< 0.0073 U	< 0.009 U	< 0.0035 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-0-0.17	12/19/2019	857.57	0 - 0.17 ft	180-100363-3	Excavated	1.41	< 0.0081 U	< 0.0088 U	< 0.0061 U	< 0.0037 U	0.84 J	0.44 J	0.13 J	< 0.0088 U	< 0.0034 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	12/19/2019	857.44	0 - 0.17 ft	180-100363-1	Excavated	0.39	< 0.0082 U	< 0.0089 U	< 0.0061 U	< 0.0037 U	0.18 J	0.21 J	< 0.0072 U	< 0.0088 U	< 0.0034 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	1/23/2020	857.44	0 - 0.17 ft	180-101497-4	Excavated	0.73	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.0035 U	0.31 J	0.3 J	0.12 J	< 0.0084 U	< 0.0032 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0-0.17	12/19/2019	858.02	0 - 0.17 ft	180-100363-2	Excavated	2.6	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	1.4 J	1.1 J	0.1 J	< 0.0082 U	< 0.0032 U
Northern Athletic Field	SSHS-B3251	SSHS-B3251-SUB-0.17-2	12/19/2019	858.34	0 - 0.17 ft	180-100363-2	Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	12/19/2019	857.46	0 - 0.17 ft	180-100363-1	Excavated	0.233	< 0.0081 U	< 0.0088 U	< 0.0061 U	< 0.0037 U	0.093 J	0.14 J	< 0.0071 U	< 0.0088 U	< 0.0034 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	1/23/2020	857.46	0 - 0.17 ft	180-101497-4	Excavated	0.56	< 0.0079 U	< 0.0086 U	< 0.0059 U	< 0.0036 U	0.19 J	0.25 J	0.12 J	< 0.0086 U	< 0.0033 U
Football Field	SSHS-B326	SSHS-B326-SUB-0-2	3/2/2016	854.91	0 - 2 ft	180-52664-1	Excavated	20.11	< 0.089 U	< 0.14 U	< 0.049 U	< 0.072 U	13 J	6.5 J	0.61 J	< 0.061 U	< 0.036 U
Football Field	SSHS-B327	SSHS-B327-SUB-0-2	3/3/2016	855.58	0 - 2 ft	180-52706-1	Excavated	1.95	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.99 J	0.78 J	0.18 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0-0.17	12/18/2019	855.88	0 - 0.17 ft	180-100380-1	Excavated	0.111	< 0.0081 U	< 0.0089 U	< 0.0061 U	< 0.0037 U	0.054 J	0.057 J	< 0.0071 U	< 0.0088 U	< 0.0034 U
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0-0.17	12/18/2019	855.39	0 - 0.17 ft	180-100380-1	Excavated	0.791	< 0.009 U	< 0.0098 U	< 0.0068 U	< 0.0041 U	0.35 J	0.35 J	0.091 J	< 0.0097 U	< 0.0037 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0-0.17	12/18/2019	856.15	0 - 0.17 ft	180-100380-2	Excavated	1.08	< 0.0082 U	< 0.0089 U	< 0.0061 U	< 0.0037 U	0.53 J	0.41 J	0.14 J	< 0.0089 U	< 0.0034 U
Football Field	SSHS-B328	SSHS-B328-SUB-0-2	3/3/2016	855.04	0 - 2 ft	180-52706-1	Excavated	2.721	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.9 J	0.74 J	0.081 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B329	SSHS-B329-SUB-0-2	3/3/2016	855.91	0 - 2 ft	180-52706-1	Excavated	0.251	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.18 J	0.059 J	0.012 J	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B331	SSHS-B331-SUB-0-2	3/3/2016	855.61	0 - 2 ft	180-52706-1	Excavated	1.489	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.91 J	0.48 J	0.099 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B332	SSHS-B332-SUB-0-2	3/3/2016	855.09	0 - 2 ft	180-52706-1	Excavated	0.626	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.4 J	0.18 J	0.046 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B333	SSHS-B333-SUB-0-2	3/3/2016	856.15	0 - 2 ft	180-52706-1	Excavated	2.22	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	1.3 J	0.75 J	0.17 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B334	SSHS-B334-SUB-0-2	3/3/2016	856.23	0 - 2 ft	180-52706-1	Excavated	0.784	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.54 J	0.2 J	0.044 J	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B335	SSHS-B335-SUB-0-2	3/3/2016	856.16	0 - 2 ft	180-52706-1	Excavated	3.53	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	2.3 J	1 J	0.23 J	< 0.0064 U	< 0.0038 U
Football Field	SSHS-B336	SSHS-B336-SUB-0-2	3/3/2016	856.00	0 - 2 ft	180-52706-1	Excavated	10.52	< 0.0096 U	< 0.015 U	< 0.0053 U	< 0.0078 U	6.1 J	3.7 J	0.72 J	< 0.0065 U	< 0.0039 U
Football Field	SSHS-B338	PS-FD-21	3/9/2016	855.82	0 - 2 ft	180-52876-1	Excavated	4.19	< 0.0092 U	< 0.014 U	< 0.005 U	< 0.0074 U	2.9 J	1.1 J	0.19 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B338	SSHS-B338-SUB-0-2	3/9/2016	855.82	0 - 2 ft	180-52876-1	Excavated	5.71	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	4 J	1.5 J	0.21 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B339	SSHS-B339-SUB-0-2	3/9/2016	856.05	0 - 2 ft	180-52876-1	Excavated	1.008	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.66 J	0.29 J	0.058 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B344	SSHS-B344-SUB-0-2	3/3/2016	855.69	0 - 2 ft	180-52706-1	Excavated	4.36	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0067 U	2.6 J	1.4 J	0.36 J	< 0.0057 U	< 0.0034 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0-0.17	1/14/2021	858.31	0 - 0.17 ft	180-116002-2	Excavated	0.0573	0.0078	0.0085	0.0059	0.0035	0.0058	0.0072	0.0069	0.0085	0.0032
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0-0.17	1/14/2021	858.43	0 - 0.17 ft	180-116002-2	Excavated	0.0526	0.0072	0.0078	0.0054	0.0032	0.0053	0.0066	0.0063	0.0078	0.003
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	1/14/2021	858.30	0 - 0.17 ft	180-116002-2	Excavated	0.0493	0.0067	0.0073	0.0051	0.003	0.005	0.0062	0.0059	0.0073	0.0028
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	0.079	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.079	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	0.017	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	< 0.005 U	0.017 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-0-0.2	3/8/2016	852.79	0 - 2 ft	180-52813-1	Excavated	71.4	< 0.081 U	< 0.13 U	< 0.044 U	< 0.065 U	56 J	13 J	2.4 J	< 0.055 U	< 0.033 U
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-0-2	3/8/2016	852.92	0 - 2 ft	180-52813-1	Excavated	25.5	< 0.081 U	< 0.13 U	< 0.044 U	< 0.065 U	20 J	4.4 J	1.1 J	< 0.055 U	< 0.033 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-0-2	3/10/2016	852.41	0 - 2 ft	180-52921-1	Excavated	0.013	< 0.0077 U	< 0.012 U	< 0.0042 U	< 0.0062 U	0.013 J	< 0.0062 U	< 0.0058 U	< 0.0052 U	< 0.0031 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	ND	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U		
Rear Parking Lot	SSHS-B380	SSHS-B380-SUB-0-2	3/7/2016	853.88	0 - 2 ft	180-52771-1	Excavated	1.421	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	0.88 J	0.47 J	0.071 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B381	PS-FD-22	3/9/2016	852.40	0 - 2 ft	180-52876-1	Not Excavated	0.124	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.081 J	0.034 J	0.009 J	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B381	SSHS-B381-SUB-0-2	3/9/2016	852.40	0 - 2 ft	180-52876-1	Not Excavated	0.428	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.28 J	0.12 J	0.028 J	< 0.0054 U	< 0.0033 U
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-0-2	3/9/2016	850.28	0 - 2 ft	180-52876-1	Not Excavated	0.0204	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	0.0094 J	0.011 J	< 0.0068 U	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	0 - 0.17 ft	180-124920-1	Not Excavated	0.058	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.03 J	0.028 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	0.0234	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.014 J	0.0094 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-0-2	3/8/2016	852.82	0 - 2 ft	180-52813-1	Excavated	3.4	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	2.2 J	1 J	0.2 J	< 0.0054 U	< 0.0033 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	ND	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U		
Northern Athletic Field	SSHS-B397	082616 09:00 PS-FD-10	8/25/2016	856.15	0 - 2 ft	180-57995-1	Excavated	1.26	< 0.0084	< 0.013	< 0.0046	< 0.0068	0.57	0.5	0.19	< 0.0057	< 0.0034
Northern Athletic Field	SSHS-B397	SSHS-B397-SUB-0-2	8/25/2016	856.15	0 - 2 ft	180-57995-1	Excavated	1.08	< 0.0086	< 0.014	< 0.0047	< 0.0069	0.49	0.43	0.16	< 0.0058	< 0.0035
Northern Athletic Field	SSHS-B398	SSHS-B398-SUB-0-2	8/25/2016	856.20	0 - 2 ft	180-57995-1	Excavated	0.92	< 0.0089	< 0.014	< 0.0049	< 0.0072	0.47	0.32	0.13	< 0.006	< 0.0036
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	0.415	< 0.0084	< 0.013	< 0.0046	< 0.0068	0.21	0.15	0.055	< 0.0057	< 0.0034
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated	14					14				
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	0.16	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	0.16	< 0.041 U	< 0.041 U		
Northern Athletic Field	SSHS-B400	SSHS-B400-SUB-0-2	8/25/2016	856.16	0 - 2 ft	180-57995-1	Excavated	0.58	< 0.0085	< 0.013	< 0.0047	< 0.0069	0.28	0.21	0.09	< 0.0058	< 0.0035
Northern Athletic Field	SSHS-B401	SSHS-B401-SUB-0-2	8/25/2016	856.35	0 - 2 ft	180-57995-1	Excavated	0.466	< 0.0084	< 0.013	< 0.0046	< 0.0067	0.21	0.18	0.076	< 0.0057	< 0.0034
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	0.168	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.034 U	0.059 J	0.082 J	0.027 J	< 0.0057 U	< 0.0035 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	0.0598	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.036	0.017 J	0.0068 JP	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	0.168	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.12	0.048	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	0.131	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.1	0.031	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	0.227	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.19	0.037	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	0.023	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.023	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	0.057	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.047	0.01 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B403	SSHS-B403-SUB-0-2	8/30/2016	856.22	0 - 2 ft	180-58129-1	Excavated	1.01	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.034 U	0.54 J	0.37 J	0.1 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B407	SSHS-B407-SUB-0-2	8/25/2016	857.28	0 - 2 ft	180-57995-1	Excavated	0.012	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.012 J	< 0.0073 U	< 0.0067 U	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B408	SSHS-B408-SUB-0-2	8/25/2016	857.31	0 - 2 ft	180-57995-1	Excavated	7.91	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.034 U	5.5 J	2.3 J	0.11 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B409	SSHS-B409-SUB-0-2	8/25/2016	857.14	0 - 2 ft	180-57995-1	Excavated	0.756	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.43 J	0.26 J	0.066 J	< 0.0061 U	< 0.0037 U
Northern Athletic Field	SSHS-B40-A	SSHS-B40-A-SUB-0-2	7/14/2015	856.85	0 - 2 ft	180-45961-1	Excavated	0.97	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.45 J	0.38 J	0.14 J	< 0.0069 U	< 0.0037 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	0.073	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.034 U	0.046 J	0.027 J	< 0.0068 U	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B411	SSHS-B411-SUB-0-2	8/22/2016	856.36	0 - 2 ft	180-57858-1	Excavated	2.62	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.034 U	1.4 J	0.95 J	0.27 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B412	SSHS-B412-SUB-0-2	8/25/2016	856.86	0 - 2 ft	180-57995-1	Excavated	0.31	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.034 U	0.2 J	0.11 J	< 0.0069 U	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B413	SSHS-B413-SUB-0-2	8/26/2016	856.37	0 - 2 ft	180-58029-1	Excavated	1.202	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.034 U	0.83 J	0.3 J	0.072 J	< 0.0056 U	< 0.0033 U
Football Field	SSHS-B414	SSHS-B414-SUB-0-2	8/22/2016	856.26	0 - 2 ft	180-57858-1	Excavated	2.6	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.034 U	1.6 J	0.86 J	0.14 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B415	SSHS-B415-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	6.5	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.034 U	4.1 J	2 J	0.4 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B416	SSHS-B416-SUB-0-2	8/22/2016	855.45	0 - 2 ft	180-57858-1	Excavated	9.4	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	5.7 J	3.2 J	0.5 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B417	SSHS-B417-SUB-0-2	8/22/2016	854.89	0 - 2 ft	180-57858-1	Excavated	36.6	< 0.045 U	< 0.071 U	< 0.024 U	< 0.034 U	25 J	8.9 J	2.7 J	< 0.03 U	< 0.018 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	0.015	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	0.015 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B418	SSHS-B418-SUB-0-2	8/23/2016	855.15	0 - 2 ft	180-57888-1	Excavated	20.6	< 0.043 U	< 0.067 U	< 0.023 U	< 0.034 U	12 J	7.2 J	1.4 J	< 0.029 U	< 0.017 U
Football Field	SSHS-B419	SSHS-B419-SUB-0-2	8/23/2016	855.07	0 - 2 ft	180-57888-1	Excavated	2.72	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	1.5 J	0.97 J	0.25 J	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	0.056	< 0.999	< 0.999	< 0.999	< 0.999	0.056	< 0.999	< 0.999		
Football Field	SSHS-B420	SSHS-B420-SUB-0-2	8/23/2016	855.20	0 - 2 ft	180-57888-1	Excavated	3.82	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	2.2 J	1.3 J	0.32 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B421	SSHS-B421-SUB-0-2	8/23/2016	854.90	0 - 2 ft	180-57888-1	Excavated	0.85	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.34 J	0.4 J	0.11 J	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B422	SSHS-B422-SUB-0-2	8/23/2016	855.04	0 - 2 ft	180-57888-1	Excavated	7.69	< 0.04 U	< 0.063 U	< 0.022 U	< 0.032 U	3.9 J	3.3 J	0.49 J	< 0.027 U	< 0.016 U
Football Field	SSHS-B423	SSHS-B423-SUB-0-2	8/22/2016	855.10	0 - 2 ft	180-57858-1	Excavated	10.1	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	4.9 J	4.1 J	1.1 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	0.591	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.034 U	0.35 J	0.19 J	0.051 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B425	SSHS-B425-SUB-0-2	8/22/2016	855.58	0 - 2 ft	180-57858-1	Excavated	1.097	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.64 J	0.37 J	0.087 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B426	SSHS-B426-SUB-0-2	8/23/2016	855.71	0 - 2 ft	180-57888-1	Excavated	0.26	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.15 J	0.11 J	< 0.0063 U	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B427	PS-FD-5	8/23/2016	855.43	0 - 2 ft	180-57888-1	Excavated	12.45	< 0.041 U	< 0.064 U	< 0.022 U	< 0.033 U	8.6 J	3.2 J	0.65 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B427	SSHS-B427-SUB-0-2	8/23/2016	855.43	0 - 2 ft	180-57888-1	Excavated	11.67	< 0.041 U	< 0.065 U	< 0.023 U	< 0.033 U	7.7 J	3.5 J	0.47 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B428	SSHS-B428-SS	8/26/2016	855.50	0 - 0.17 ft	180-58029-1	Excavated	2.05	< 0.01 U	< 0.016 U	< 0.0056 U	< 0.034 U	1.3 J	0.57 J	0.18 J	< 0.0069 U	< 0.0041 U
Football Field	SSHS-B429	SSHS-B429-SS	8/26/2016	854.95	0 - 0.17 ft	180-58029-1	Excavated	1.319	< 0.0097 U	< 0.015 U	< 0.0053 U	< 0.034 U	0.83 J	0.39 J	0.099 J	< 0.0066 U	< 0.004 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B430	PS-FD-9	8/25/2016	855.35	0 - 2 ft	180-57995-1	Excavated	0.172	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.063 J	0.09 J	0.019 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B430	SSHS-B430-SUB-0-2	8/25/2016	855.35	0 - 2 ft	180-57995-1	Excavated	0.11	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.034 U	0.042 J	0.068 J	< 0.007 U	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B438	SSHS-B438-SUB-0-2	8/26/2016	854.99	0 - 2 ft	180-58029-3	Excavated	8.18	< 0.034 U	< 0.13 U	< 0.046 U	< 0.034 U	5.2 J	2.6 J	0.38 J	< 0.057 U	< 0.034 U
Football Field	SSHS-B439	SSHS-B439-SUB-0-2	8/26/2016	855.06	0 - 2 ft	180-58029-3	Excavated	134.2	< 0.41 U	< 0.65 U	< 0.23 U	< 0.33 U	88 J	42 J	4.2 J	< 0.28 U	< 0.17 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B440	SSHS-B440-SUB-0-2	8/26/2016	855.30	0 - 2 ft	180-58029-1	Excavated	53.9	< 0.17 UJ	< 0.26 U	< 0.092 U	< 0.13 U	38 J	14 J	1.9 J	< 0.11 U	< 0.068 U
Football Field	SSHS-B441	SSHS-B441-SUB-0-2	8/24/2016	854.89	0 - 2 ft	180-57932-1	Excavated	0.91	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.7 J	0.21 J	< 0.007 U	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B442	SSHS-B442-SUB-0-2	8/24/2016	855.06	0 - 2 ft	180-57932-1	Excavated	2.55	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.7 J	0.69 J	0.16 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B443	SSHS-B443-SUB-0-2	9/14/2016	855.30	0 - 2 ft	180-58722-1	Excavated	5.01	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	3.5 J	1.3 J	0.21 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B444	SSHS-B444-SUB-0-2	8/26/2016	855.07	0 - 2 ft	180-58029-1	Excavated	6.63	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0066 U	4.4 J	1.8 J	0.43 J	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B445	SSHS-B445-SS	8/26/2016	856.02	0 - 0.17 ft	180-58029-1	Excavated	10.4	< 0.011 U	< 0.017 U	< 0.0058 U	< 0.0085 U	5.3 J	4 J	1.1 J	< 0.0072 U	< 0.0043 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B451	SSHS-B451-SUB-0-2	9/27/2016	854.61	0 - 2 ft	180-59163-1	Excavated	0.93	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	0.56 J	0.37 J	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B452	SSHS-B452-SUB-0-2	9/27/2016	854.99	0 - 2 ft	180-59163-1	Excavated	0.072	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	0.058 J	0.014 J	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B453	SSHS-B453-SUB-0-2	8/24/2016	855.65	0 - 2 ft	180-57932-1	Excavated	2.74	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	1.6 J	1 J	0.14 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B454	SSHS-B454-SUB-0-2	8/24/2016	855.00	0 - 2 ft	180-57932-1	Excavated	3.63	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	2.4 J	1 J	0.23 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B455	SSHS-B455-SUB-0-2	8/30/2016	855.84	0 - 2 ft	180-58129-1	Excavated	ND	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	< 0.0064 U	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B456	SSHS-B456-SUB-0-2	8/30/2016	855.99	0 - 2 ft	180-58129-1	Excavated	ND	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	< 0.0065 U	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B457	SSHS-B457-SUB-0-2	8/30/2016	855.74	0 - 2 ft	180-58129-1	Not Excavated	0.038	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.022 J	0.016 J	< 0.0062 U	< 0.0056 U	< 0.0034 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B458	SSHS-B458-SUB-0-2	8/24/2016	856.14	0 - 2 ft	180-57932-1	Excavated	2.64	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	1.6 J	0.92 J	0.12 J	< 0.0057 U	< 0.0034 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	1.83	< 0.999	< 0.999	< 0.999	< 0.999	1.7	< 0.999	0.13		
Football Field	SSHS-B460	SSHS-B460-SUB-0-2	8/31/2016	855.48	0 - 2 ft	180-58236-1	Excavated	13.81	< 0.041 U	< 0.065 U	< 0.023 U	< 0.033 U	10 J	3.1 J	0.71 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B461	SSHS-B461-SUB-0-2	8/31/2016	855.42	0 - 2 ft	180-58236-1	Excavated	10.9	< 0.04 U	< 0.064 U	< 0.022 U	< 0.033 U	8 J	2.4 J	0.5 J	< 0.027 U	< 0.016 U
Football Field	SSHS-B462	SSHS-B462-SUB-0-2	8/31/2016	855.34	0 - 2 ft	180-58236-1	Excavated	6.75	< 0.0089 U	< 0.014 U	< 0.0048 U	< 0.0071 U	5 J	1.5 J	0.25 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B463	SSHS-B463-SUB-0-2	8/31/2016	854.92	0 - 2 ft	180-58236-1	Excavated	6.7	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	4.8 J	1.6 J	0.3 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B464	SSHS-B464-SUB-0-2	8/29/2016	856.94	0 - 2 ft	180-58133-1	Excavated	0.047	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.027 J	0.02 J	< 0.0065 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B466	SSHS-B466-SUB-0-2	8/29/2016	856.03	0 - 2 ft	180-58133-1	Excavated	54.1	< 0.17 U	< 0.26 U	< 0.092 U	< 0.14 U	37 J	16 J	1.1 J	< 0.11 U	< 0.068 U
Football Field	SSHS-B467	SSHS-B467-SUB-0-2	8/29/2016	856.10	0 - 2 ft	180-58133-1	Excavated	2279	< 4.3 U	< 6.7 U	< 2.3 U	< 3.4 U	1600 J	630 J	49 J	< 2.9 U	< 1.7 U
Northern Athletic Field	SSHS-B46-A	SSHS-B46-A-SS	7/21/2014	858.26	0 - 0.17 ft	180-35053-1	Excavated	0.177	< 0.0015	< 0.0019	< 0.0017	< 0.0016	0.1	0.077	< 0.0014	< 0.0022	< 0.0013
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B473	SSHS-B473-SUB-0-2	8/30/2016	856.07	0 - 2 ft	180-58129-1	Excavated	0.424	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.3 J	0.11 J	0.014 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B477	SSHS-B477-SUB-0-2	8/29/2016	856.06	0 - 2 ft	180-58133-1	Excavated	0.529	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.3 J	0.2 J	0.029 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B479	SSHS-B479-SUB-0-2	8/29/2016	856.39	0 - 2 ft	180-58133-1	Excavated	3.01	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1.9 J	1 J	0.11 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B481	SSHS-B481-SS	8/24/2016	856.03	0 - 0.17 ft	180-57932-1	Excavated	0.603	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	0.4 J	0.16 J	0.043 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B494	SSHS-B494-SUB-0-2	8/23/2016	854.88	0 - 2 ft	180-57888-1	Excavated	7.7	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	5.1 J	2.2 J	0.4 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B495	SSHS-B495-SUB-0-2	8/23/2016	855.25	0 - 2 ft	180-57888-1	Excavated	2.97	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	2 J	0.83 J	0.14 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B496	PS-FD-3	8/23/2016	855.35	0 - 2 ft	180-57888-1	Excavated	3.09	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1.9 J	1 J	0.19 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B496	SSHS-B496-SUB-0-2	8/23/2016	855.35	0 - 2 ft	180-57888-1	Excavated	3.76	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	2.2 J	1.3 J	0.26 J	< 0.0056 U	< 0.0034 U
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated	3.5	< U	< U	< U	< U	3.5	< U	< U		
EHS Building	SSHS-B4SS-A	SSHS-B4SS-A-SS	7/22/2014	855.50	0 - 0.17 ft	180-35079-1	Not Excavated	ND	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	< 0.00088 U	< 0.0013 U	< 0.0013 U	< 0.002 U	< 0.0012 U
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	0.15	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	0.15	< 0.042 U	< 0.042 U		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	ND	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U		
Rear Parking Lot	SSHS-B523	SSHS-B523-SUB-0-2	9/23/2016	854.05	0 - 2 ft	180-59040-1	Excavated	0.085	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	0.052 J	0.022 J	0.011 J	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B525	SSHS-B525-SUB-0-2	9/16/2016	853.93	0 - 2 ft	180-58783-1	Excavated	0.0355	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	0.027 J	0.0085 J	< 0.0059 U	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B526	SSHS-B526-SUB-0-2	9/16/2016	853.95	0 - 2 ft	180-58783-1	Excavated	4.82	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	3.6 J	0.97 J	0.25 J	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B527	SSHS-B527-SUB-0-2	9/16/2016	853.71	0 - 2 ft	180-58783-1	Excavated	49.2	< 0.41 U	< 0.65 U	< 0.22 U	< 0.33 U	36 J	11 J	2.2 J	< 0.28 U	< 0.17 U
Rear Parking Lot	SSHS-B528	SSHS-B528-SUB-0-2	9/16/2016	853.01	0 - 2 ft	180-58783-1	Excavated	10.95	< 0.08 U	< 0.13 U	< 0.044 U	< 0.065 U	8 J	2.5 J	0.45 J	< 0.054 U	< 0.033 U
Rear Parking Lot	SSHS-B528	PS-FD-27	9/16/2016	853.01	0 - 2 ft	180-58783-1	Excavated	6.42	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	4.6 J	1.5 J	0.32 J	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B529	SSHS-B529-SUB-0-2	9/16/2016	852.61	0 - 2 ft	180-58783-1	Excavated	5.44	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	4 J	1.2 J	0.24 J	< 0.0055 U	< 0.0033 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	ND	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U		
Rear Parking Lot	SSHS-B531	PS-FD-28	9/16/2016	852.31	0 - 2 ft	180-58783-1	Not Excavated	0.269	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.17 J	0.076 J	0.023 J	< 0.0053 U	< 0.0032 U
Rear Parking Lot	SSHS-B531	SSHS-B531-SUB-0-2	9/16/2016	852.31	0 - 2 ft	180-58783-1	Not Excavated	0.234	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.15 J	0.065 J	0.019 J	< 0.0054 U	< 0.0033 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	ND	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U		
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated	ND	< U	< U	< U	< U	< U	< U	< U		
Rear Parking Lot	SSHS-B561	SSHS-B561-SS	9/2/2016	847.44	0 - 0.17 ft	180-58309-1	Excavated	3.35	< 0.0094 U	< 0.015 U	< 0.0052 U	< 0.0076 U	2.2 J	1 J	0.15 J	< 0.0064 U	< 0.0039 U
Rear Parking Lot	SSHS-B562	SSHS-B562-SS	9/2/2016	847.97	0 - 0.17 ft	180-58309-1	Excavated	0.101	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.054 J	0.047 J	< 0.0063 U	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B564	SSHS-B564-SS	9/2/2016	848.83	0 - 0.17 ft	180-58309-1	Excavated	5.7	< 0.0098 U	< 0.015 U	< 0.0054 U	< 0.0079 U	3.3 J	2.1 J	0.3 J	< 0.0066 U	< 0.004 U
Rear Parking Lot	SSHS-B565	SSHS-B565-SS	9/2/2016	847.59	0 - 0.17 ft	180-58309-1	Excavated	4.58	< 0.01 U	< 0.016 U	< 0.0057 U	< 0.0084 U	2.6 J	1.7 J	0.28 J	< 0.007 U	< 0.0042 U
Rear Parking Lot	SSHS-B566	SSHS-B566-SS	9/2/2016	846.57	0 - 0.17 ft	180-58309-1	Excavated	6.15	< 0.0099 U	< 0.016 U	< 0.0054 U	< 0.008 U	3.6 J	2.2 J	0.35 J	< 0.0067 U	< 0.004 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated	0.078							0.078		
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	ND	< 0.0082	< 0.013	< 0.0045	< 0.0066	< 0.0042	< 0.0066	< 0.0061	< 0.0055	< 0.0033
Football Field	SSHS-B576	SSHS-B576-SS	2/15/2017	855.75	0 - 0.17 ft	180-63517-1	Excavated	0.038	< 0.012 U	< 0.011 U	< 0.0088 U	< 0.018 U	0.019 J	0.019 J	< 0.015 U	< 0.016 U	< 0.0068 U
Northern Athletic Field	SSHS-B577	SSHS-B577-SS	2/10/2017	856.11	0 - 0.17 ft	180-63389-1	Excavated	0.017	< 0.013	< 0.012	< 0.0094	< 0.019	< 0.011	< 0.01	0.017	< 0.017	< 0.0072
Tennis Courts / Main Parking Lot	SSHS-B578	SSHS-B578-SUB-0-2	2/15/2017	857.45	0 - 2 ft	180-63517-1	Excavated	1.62	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.68 J	0.67 J	0.27 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B578	PS-FD-20	2/15/2017	857.45	0 - 2 ft	180-63517-1	Excavated	2.54	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.6 J	1.5 J	0.44 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B579	SSHS-B579-SUB-0-2	2/15/2017	856.16	0 - 2 ft	180-63517-1	Excavated	2.22	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	1.1 J	0.87 J	0.25 J	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B586	SSHS-B586-SS	2/10/2017	855.97	0 - 0.17 ft	180-63389-1	Excavated	ND	< 0.012	< 0.012	< 0.0089	< 0.018	< 0.011	< 0.0098	< 0.015	< 0.016	< 0.0068
Tennis Courts / Main Parking Lot	SSHS-B587	PS-FD-21	2/15/2017	856.06	0 - 2 ft	180-63517-1	Not Excavated	0.068	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.04 J	0.028 J	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B587	SSHS-B587-SUB-0-2	2/15/2017	856.06	0 - 2 ft	180-63517-1	Not Excavated	0.104	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.063 J	0.041 J	< 0.012 U	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-0-2	2/15/2017	856.06	0 - 2 ft	180-63517-1	Not Excavated	0.292	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.15 J	0.11 J	0.032 J	< 0.013 U	< 0.0055 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B591	SSHS-B591-SUB-0-2	2/15/2017	856.21	0 - 2 ft	180-63517-1	Not Excavated	0.018	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0086 U	0.018	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B592	SSHS-B592-SUB-0-2	2/15/2017	856.38	0 - 2 ft	180-63517-1	Not Excavated	0.53	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.19 J	0.2 J	0.14 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B593	SSHS-B593-SUB-0-2	2/15/2017	856.22	0 - 2 ft	180-63517-1	Not Excavated	0.223	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.045 J	0.12 J	0.058 J	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B594	PS-FD-22	2/15/2017	856.17	0 - 2 ft	180-63517-1	Excavated	2.52	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	1.4 J	0.87 J	0.25 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B594	SSHS-B594-SUB-0-2	2/15/2017	856.17	0 - 2 ft	180-63517-1	Excavated	1.74	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	1 J	0.58 J	0.16 J	< 0.014 U	< 0.0061 U
Tennis Courts / Main Parking Lot	SSHS-B595	SSHS-B595-SS	2/10/2017	856.24	0 - 0.17 ft	180-63389-1	Not Excavated	0.021	< 0.012 U	< 0.012 U	< 0.009 U	< 0.018 U	0.011 J	0.01 J	< 0.015 U	< 0.016 U	< 0.0069 U
Tennis Courts / Main Parking Lot	SSHS-B596	SSHS-B596-SS	2/10/2017	855.41	0 - 0.17 ft	180-63389-1	Not Excavated	0.039	< 0.012 U	< 0.011 U	< 0.0086 U	< 0.017 U	0.012 J	0.012 J	0.015 J	< 0.016 U	< 0.0066 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated	14					14				
Football Field	SSHS-B605	SSHS-B605-SS	2/10/2017	855.33	0 - 0.17 ft	180-63389-1	Excavated	0.088	< 0.011 U	< 0.011 U	< 0.0084 U	< 0.017 U	0.043 J	0.045 J	< 0.014 U	< 0.015 U	< 0.0064 U
Football Field	SSHS-B606	SSHS-B606-SS	2/10/2017	855.21	0 - 0.17 ft	180-63389-1	Excavated	0.11	< 0.012 U	< 0.012 U	< 0.0092 U	< 0.018 U	0.057 J	0.053 J	< 0.015 U	< 0.017 U	< 0.0071 U
Football Field	SSHS-B607	SSHS-B607-SS	2/10/2017	855.67	0 - 0.17 ft	180-63389-1	Excavated	0.377	< 0.013 U	< 0.012 U	< 0.0094 U	< 0.019 U	0.21 J	0.14 J	0.027 J	< 0.017 U	< 0.0073 U
Football Field	SSHS-B608	SSHS-B608-SS	2/9/2017	855.41	0 - 0.17 ft	180-63367-1	Excavated	0.424	< 0.014 U	< 0.013 U	< 0.01 U	< 0.02 U	0.23 J	0.16 J	0.034 J	< 0.018 U	< 0.0078 U
Football Field	SSHS-B609	SSHS-B609-SS	2/9/2017	855.85	0 - 0.17 ft	180-63367-1	Excavated	0.536	< 0.013 U	< 0.012 U	< 0.0095 U	< 0.019 U	0.33 J	0.18 J	0.026 J	< 0.017 U	< 0.0073 U
Football Field	SSHS-B610	SSHS-B610-SS	2/10/2017	854.80	0 - 0.17 ft	180-63389-1	Excavated	0.945	< 0.013 U	< 0.013 U	< 0.01 U	< 0.02 U	0.48 J	0.39 J	0.075 J	< 0.018 U	< 0.0077 U
Football Field	SSHS-B611	PS-FD-3	2/9/2017	857.31	0 - 0.17 ft	180-63367-1	Excavated	0.436	< 0.012 U	< 0.012 U	< 0.0091 U	< 0.018 U	0.25 J	0.16 J	0.026 J	< 0.017 U	< 0.007 U
Football Field	SSHS-B611	SSHS-B611-SS	2/9/2017	857.31	0 - 0.17 ft	180-63367-1	Excavated	0.415	< 0.013 U	< 0.013 U	< 0.0098 U	< 0.02 U	0.23 J	0.16 J	0.025 J	< 0.018 U	< 0.0075 U
Football Field	SSHS-B612	SSHS-B612-SS	2/7/2017	857.08	0 - 0.17 ft	180-63367-1	Excavated	0.059	< 0.012 U	< 0.012 U	< 0.009 U	< 0.018 U	0.037 J	0.022 J	< 0.015 U	< 0.016 U	< 0.0069 U
Football Field	SSHS-B613	SSHS-B613-SS	2/8/2017	856.09	0 - 0.17 ft	180-63367-1	Excavated	0.165	< 0.013 U	< 0.012 U	< 0.0094 U	< 0.019 U	0.086 J	0.055 J	0.024 J	< 0.017 U	< 0.0073 U
Football Field	SSHS-B614	DUP-1	2/7/2017	856.36	0 - 0.17 ft	180-63367-1	Excavated	1.83	< 0.012 U	< 0.012 U	< 0.0089 U	< 0.018 U	1.2 J	0.5 J	0.13 J	< 0.016 U	< 0.0069 U
Football Field	SSHS-B614	SSHS-B614-SS	2/7/2017	856.36	0 - 0.17 ft	180-63367-1	Excavated	1.92	< 0.012 U	< 0.012 U	< 0.0089 U	< 0.018 U	1.3 J	0.5 J	0.12 J	< 0.016 U	< 0.0068 U
Football Field	SSHS-B615	SSHS-B615-SS	2/7/2017	856.42	0 - 0.17 ft	180-63367-1	Excavated	0.393	< 0.012 U	< 0.012 U	< 0.009 U	< 0.018 U	0.24 J	0.12 J	0.033 J	< 0.016 U	< 0.007 U
Football Field	SSHS-B616	SSHS-B616-SS	2/7/2017	855.76	0 - 0.17 ft	180-63367-1	Excavated	0.652	< 0.013 U	< 0.012 U	< 0.0094 U	< 0.019 U	0.43 J	0.18 J	0.042 J	< 0.017 U	< 0.0072 U
Football Field	SSHS-B617	SSHS-B617-SS	2/7/2017	855.01	0 - 0.17 ft	180-63367-1	Excavated	1.026	< 0.012 U	< 0.012 U	< 0.0093 U	< 0.019 U	0.66 J	0.29 J	0.076 J	< 0.017 U	< 0.0072 U
Football Field	SSHS-B618	SSHS-B618-SS	2/7/2017	855.15	0 - 0.17 ft	180-63367-1	Excavated	2.75	< 0.013 U	< 0.012 U	< 0.0095 U	< 0.019 U	1.8 J	0.77 J	0.18 J	< 0.017 U	< 0.0073 U
Football Field	SSHS-B619	SSHS-B619-SUB-0-2	2/14/2017	855.58	0 - 2 ft	180-63507-1	Excavated	3.36	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	2.3 J	0.89 J	0.17 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B620	SSHS-B620-SUB-0-2	2/13/2017	855.29	0 - 2 ft	180-63507-1	Excavated	5.46	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	3.7 J	1.4 J	0.36 J	< 0.014 U	< 0.0061 U
Football Field	SSHS-B624	SSHS-B624-SS	2/10/2017	855.38	0 - 0.17 ft	180-63389-1	Excavated	2.25	< 0.012 U	< 0.012 U	< 0.009 U	< 0.018 U	1.2 J	0.9 J	0.15 J	< 0.016 U	< 0.0069 U
Tennis Courts / Main Parking Lot	SSHS-B632C	SSHS-B632C-SUB-0-2	7/13/2017	855.37	0 - 2 ft	180-68203-1	Excavated	0.016	< 0.01 U	< 0.0097 U	< 0.0075 U	< 0.015 U	0.016 J	< 0.0083 U	< 0.013 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-0-2	2/10/2017	855.22	0 - 2 ft	180-63389-1	Excavated	0.0267	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.019 J	0.0077 J	< 0.012 U	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B636	PS-FD-10	2/13/2017	855.28	0 - 2 ft	180-63507-1	Not Excavated	0.05	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.013 U	0.031 J	0.019 J	< 0.011 U	< 0.012 U	< 0.0051 U
Tennis Courts / Main Parking Lot	SSHS-B636	SSHS-B636-SUB-0-2	2/13/2017	855.28	0 - 2 ft	180-63507-1	Not Excavated	0.038	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.013 U	0.024 J	0.014 J	< 0.011 U	< 0.012 U	< 0.0052 U
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	2	< 0.0026 U	< 0.0033 U	< 0.003 U	< 0.0029 U	1.9	< 0.0025 U	0.1	< 0.0038 U	< 0.0023 U
Football Field	SSHS-B647	SSHS-B647-SUB-0-2	2/16/2017	856.87	0 - 2 ft	180-63593-1	Excavated	0.042	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.028 J	0.014 J	< 0.013 U	< 0.014 U	< 0.0059 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	10.5	< 0.026 U	< 0.033 U	< 0.03 U	< 0.028 U	10	< 0.025 U	0.5	< 0.038 U	< 0.022 U
Football Field	SSHS-B650	SSHS-B650-SUB-0-2	2/14/2017	855.56	0 - 2 ft	180-63507-1	Excavated	16.52	< 0.097 U	< 0.095 U	< 0.073 U	< 0.15 U	12 J	3.9 J	0.62 J	< 0.13 U	< 0.056 U
Football Field	SSHS-B651	SSHS-651-SUB-0-2	2/14/2017	855.56	0 - 2 ft	180-63507-1	Excavated	2.14	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.5 J	0.54 J	0.1 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B652	SSHS-B652-SUB-0-2	2/14/2017	855.55	0 - 2 ft	180-63507-1	Excavated	25.69	< 0.094 U	< 0.092 U	< 0.07 U	< 0.14 U	20 J	4.8 J	0.89 J	< 0.13 U	< 0.054 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	25.1	< 0.051 U	< 0.066 U	< 0.059 U	< 0.056 U	24	< 0.049 U	1.1	< 0.075 U	< 0.044 U
Northern Athletic Field	SSHS-B664	SSHS-B664-SUB-0-2	2/15/2017	856.32	0 - 2 ft	180-63517-1	Excavated	3.76	< 0.0098	< 0.0096	< 0.0073	< 0.015	2.3	1.1	0.36	< 0.013	< 0.0056
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	272	< 0.54 U	< 0.69 U	< 0.62 U	< 0.59 U	260	< 0.52 U	12	< 0.8 U	< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B674	032217 08:50_SSHS-B674-SUB-0-2	3/21/2017	856.28	0 - 2 ft	180-64494-1	Excavated	1.05	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.69	0.25	0.11	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B675	032217 08:50_SSHS-B675-SUB-0-2	3/21/2017	857.36	0 - 2 ft	180-64494-1	Excavated	0.137	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.071	0.041	0.025	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B676	032217 08:50_SSHS-B676-SUB-0-2	3/21/2017	856.94	0 - 2 ft	180-64494-1	Excavated	0.168	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.1	0.043	0.025	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B677	032217 08:50_PS-FD-3	3/21/2017	856.08	0 - 2 ft	180-64494-2	Excavated	2.16	< 0.0098	< 0.0095	< 0.0073	< 0.015	1.5	0.47	0.19	< 0.013	< 0.0056
Northern Athletic Field	SSHS-B677	SSHS-B677-SUB-0-2	3/21/2017	856.08	0 - 2 ft	180-64494-1	Excavated	2.17	< 0.0099	< 0.0097	< 0.0074	< 0.015	1.5	0.47	0.2	< 0.013	< 0.0057
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	3/21/2017	856.07	0 - 2 ft	180-64494-1	Not Excavated	0.551	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.38	0.11	0.061	< 0.013	< 0.0056
Tennis Courts / Main Parking Lot	SSHS-B679B	071417 08:00_SSHS-B679B-SUB-0-2	7/13/2017	855.48	0 - 2 ft	180-68203-1	Excavated	0.287	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.18	0.091	0.016 J	< 0.013 U	< 0.0054 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	104.9	< 0.26 U	< 0.34 U	< 0.3 U	< 0.29 U	100	< 0.25 U	4.9	< 0.39 U	< 0.23 U
Football Field	SSHS-B685B	071417 08:00_SSHS-B685B-SUB-0-2	7/13/2017	855.54	0 - 2 ft	180-68203-1	Excavated	15.68	< 0.098 U	< 0.095 U	< 0.073 U	< 0.15 U	11	3.9	0.78	< 0.13 U	< 0.056 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	0.571	< 0.0027 U	< 0.0034 U	< 0.0031 U	< 0.0029 U	0.52	< 0.0026 U	0.051	< 0.0039 U	< 0.0023 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated	11					11				
Football Field	SSHS-B70	081514 01:15_SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	0.823	< 0.0032 U	< 0.0041 U	< 0.0037 U	< 0.0035 U	0.74	< 0.003 U	0.083	< 0.0047 U	< 0.0027 U
Football Field	SSHS-B733	SSHS-B733-SS	4/11/2017	856.84	0 - 0.17 ft	180-65117-1	Excavated	0.077	< 0.012 U	< 0.012 U	< 0.0088 U	< 0.018 U	< 0.011 U	0.054	0.023	< 0.016 U	< 0.0068 U
Football Field	SSHS-B734	PS-FD-1	4/11/2017	856.89	0 - 0.17 ft	180-65117-1	Excavated	0.078	< 0.011 U	< 0.011 U	< 0.0086 U	< 0.017 U	< 0.01 U	0.059	0.019 J	< 0.016 U	< 0.0066 U
Football Field	SSHS-B734	SSHS-B734-SS	4/11/2017	856.89	0 - 0.17 ft	180-65117-1	Excavated	0.077	< 0.012 U	< 0.011 U	< 0.0086 U	< 0.017 U	< 0.01 U	0.059	0.018 J	< 0.016 U	< 0.0066 U
Football Field	SSHS-B735	SSHS-B735-SS	4/11/2017	857.01	0 - 0.17 ft	180-65117-1	Excavated	0.054	< 0.012 U	< 0.012 U	< 0.0089 U	< 0.018 U	< 0.011 U	0.054	< 0.015 U	< 0.016 U	< 0.0068 U

DRAFT

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B743	SSHS-B743-SUB-0-2	4/13/2017	855.75	0 - 2 ft	180-65226-1	Excavated	0.846	< 0.011 U	< 0.011 U	< 0.0082 U	< 0.016 U	0.54	0.25	0.056	< 0.015 U	< 0.0063 U
Football Field	SSHS-B744	SSHS-B744-SUB-0-2	4/13/2017	856.21	0 - 2 ft	180-65226-1	Excavated	0.475	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.33	0.12	0.025	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B745	PS-FD-13	5/22/2017	855.73	0 - 2 ft	180-66618-1	Not Excavated	0.36	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.24	0.094	0.026	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B745	SSHS-B745-SUB-0-2	5/22/2017	855.73	0 - 2 ft	180-66618-1	Not Excavated	0.421	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.28	0.11	0.031	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B746	SSHS-B746-SUB-0-2	5/22/2017	855.63	0 - 2 ft	180-66618-1	Not Excavated	0.402	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.25	0.12	0.032	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B747	SSHS-B747-SUB-0-2	5/22/2017	856.07	0 - 2 ft	180-66618-1	Excavated	1.162	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.71	0.36	0.092	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B748	SSHS-B748-SUB-0-2	5/22/2017	856.15	0 - 2 ft	180-66618-1	Excavated	1.33	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.76	0.45	0.12	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B749	PS-FD-11	5/22/2017	856.27	0 - 2 ft	180-66618-1	Not Excavated	0.676	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.29	0.29	0.096	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B749	SSHS-B749-SUB-0-2	5/22/2017	856.27	0 - 2 ft	180-66618-1	Not Excavated	0.89	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.37	0.39	0.13	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	ND	< 0.0032	< 0.0041	< 0.0036	< 0.0035	< 0.002	< 0.003	< 0.003	< 0.0047	< 0.0027
Tennis Courts / Main Parking Lot	SSHS-B750	SSHS-B750-SUB-0-2	5/22/2017	856.17	0 - 2 ft	180-66618-1	Excavated	1.44	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.81	0.48	0.15	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-0-2	5/22/2017	856.21	0 - 2 ft	180-66618-1	Excavated	3.35	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	2.1	1	0.25	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-0-2	5/22/2017	856.21	0 - 2 ft	180-66618-1	Excavated	3.35	< 0.0096	< 0.0094	< 0.0072	< 0.014	2.1	1	0.25	< 0.013	< 0.0055
Tennis Courts / Main Parking Lot	SSHS-B752	PS-FD-12	5/22/2017	856.15	0 - 2 ft	180-66618-1	Excavated	1.44	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.85	0.46	0.13	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B752	SSHS-B752-SUB-0-2	5/22/2017	856.15	0 - 2 ft	180-66618-1	Excavated	1.01	< 0.0092 U	< 0.009 U	< 0.0068 U	< 0.014 U	0.57	0.34	0.1	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B758	SSHS-B758-SUB-0-2	5/22/2017	856.30	0 - 2 ft	180-66618-1	Excavated	1.27	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.81	0.35	0.11	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B759	PS-FD-14	5/22/2017	856.24	0 - 2 ft	180-66618-1	Not Excavated	1.07	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.55	0.39	0.13	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B759	SSHS-B759-SUB-0-2	5/22/2017	856.24	0 - 2 ft	180-66618-1	Not Excavated	0.452	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.23	0.17	0.052	< 0.012 U	< 0.0052 U
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	0.352	< 0.003	< 0.0038	< 0.0034	< 0.0033	0.3	< 0.0029	0.052	< 0.0044	< 0.0026
Tennis Courts / Main Parking Lot	SSHS-B765	SSHS-B765-SUB-0-2	5/22/2017	856.08	0 - 2 ft	180-66618-2	Excavated	1.89	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	1.3	0.46	0.13	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B766	SSHS-B766-SUB-0-2	5/22/2017	856.26	0 - 2 ft	180-66618-2	Excavated	0.415	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.2	0.16	0.055	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B767	SSHS-B767-SUB-0-2	5/22/2017	855.87	0 - 2 ft	180-66618-2	Excavated	0.685	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.39	0.24	0.055	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B768	SSHS-B768-SUB-0-2	5/22/2017	855.82	0 - 2 ft	180-66618-2	Excavated	1.14	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.72	0.33	0.09	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B769	SSHS-B769-SUB-0-2	5/22/2017	855.85	0 - 2 ft	180-66618-2	Not Excavated	0.863	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.53	0.26	0.073	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	ND	< 0.003	< 0.0039	< 0.0035	< 0.0033	< 0.0019	< 0.0029	< 0.0029	< 0.0045	< 0.0026
Tennis Courts / Main Parking Lot	SSHS-B770	SSHS-B770-SUB-0-2	5/22/2017	856.04	0 - 2 ft	180-66618-2	Not Excavated	0.307	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.15	0.12	0.037	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-0-2	5/22/2017	856.31	0 - 2 ft	180-66618-2	Not Excavated	0.404	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	< 0.0084 U	0.35	0.054	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B772	SSHS-B772-SUB-0-2	5/22/2017	856.30	0 - 2 ft	180-66618-2	Excavated	1.28	< 0.0091 U	< 0.0088 U	< 0.0068 U	< 0.014 U	0.76	0.38	0.14	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B773	SSHS-B773-SUB-0-2	5/22/2017	856.38	0 - 2 ft	180-66618-2	Excavated	1.21	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.61	0.42	0.18	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B774	SSHS-B774-SUB-0-2	5/22/2017	856.38	0 - 2 ft	180-66618-2	Not Excavated	0.359	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.16	0.15	0.049	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-0-2	5/23/2017	855.99	0 - 2 ft	180-66622-1	Not Excavated	0.301	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.17	0.097	0.034	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B778	SSHS-B778-SUB-0-2	5/22/2017	855.75	0 - 2 ft	180-66618-2	Excavated	8.44	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	5.4	2.3	0.74	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B779	SSHS-B779-SUB-0-2	5/22/2017	856.22	0 - 2 ft	180-66618-2	Excavated	0.517	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.3	0.17	0.047	< 0.012 U	< 0.0053 U
Northern Athletic Field	SSHS-B780	SSHS-B780-SUB-0-2	5/22/2017	857.31	0 - 2 ft	180-66618-2	Not Excavated	0.246	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.15	0.073	0.023	< 0.013 U	< 0.0056 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated	11					11				
Football Field	SSHS-B814	SSHS-B814-SS	5/18/2017	855.66	0 - 0.17 ft	180-66476-1	Excavated	2.39	< 0.012 U	< 0.011 U	< 0.0087 U	< 0.017 U	1.2	0.98	0.21	< 0.016 U	< 0.0067 U
Football Field	SSHS-B815	SSHS-B815-SS	5/18/2017	856.09	0 - 0.17 ft	180-66476-1	Excavated	3.2	< 0.011 U	< 0.011 U	< 0.0085 U	< 0.017 U	1.6	1.6		< 0.015 U	< 0.0066 U
Football Field	SSHS-B816	SSHS-B816-SS	5/18/2017	856.25	0 - 0.17 ft	180-66476-1	Excavated	1.41	< 0.011 U	< 0.011 U	< 0.0083 U	< 0.017 U	0.75	0.53	0.13	< 0.015 U	< 0.0064 U
Football Field	SSHS-B817	SSHS-B817-SS	5/18/2017	855.68	0 - 0.17 ft	180-66476-1	Excavated	0.332	< 0.011 U	< 0.011 U	< 0.0085 U	< 0.017 U	0.14	0.14	0.052	< 0.015 U	< 0.0065 U
Football Field	SSHS-B818	SSHS-B818-SS	5/18/2017	856.02	0 - 0.17 ft	180-66476-1	Excavated	1.38	< 0.011 U	< 0.011 U	< 0.0084 U	< 0.017 U	0.64	0.6	0.14	< 0.015 U	< 0.0065 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B822	DUP-1	6/19/2017	856.39	0 - 2 ft	180-67517-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B822	SSHS-B822-SUB-0-2	6/19/2017	856.39	0 - 2 ft	180-67517-1	Not Excavated	ND	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.009 U	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B825	PS-FD-9	7/13/2017	855.59	0 - 2 ft	180-68203-1	Excavated	53.4	< 0.48 U	< 0.47 U	< 0.36 U	< 0.72 U	39	12	2.4	< 0.65 U	< 0.28 U
Football Field	SSHS-B825	SSHS-B825-SUB-0-2	7/13/2017	855.59	0 - 2 ft	180-68203-1	Excavated	10.84	< 0.095 U	< 0.093 U	< 0.071 U	< 0.14 U	8	2.4	0.44	< 0.13 U	< 0.055 U
Football Field	SSHS-B826	SSHS-B826-SUB-0-2	7/13/2017	855.69	0 - 2 ft	180-68203-1	Excavated	10.5	< 0.096 U	< 0.093 U	< 0.071 U	< 0.14 U	7.1	3.1	0.3	< 0.13 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B827	SSHS-B827-SUB-0-2	7/13/2017	855.20	0 - 2 ft	180-68203-1	Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Rear Parking Lot	SSHS-B828	SSHS-B828-SUB-0-2	1/14/2018	851.95	0 - 2 ft	180-74210-1	Excavated	3.93	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8 J	0.89 J	0.24 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-0-2	1/10/2018	852.37	0 - 2 ft	180-74125-1	Not Excavated	ND	< 0.0055 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.013 U	< 0.012 U	< 0.0048 U	< 0.012 U	< 0.0082 U
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-0-2	1/11/2018	854.01	0 - 2 ft	180-74124-1	Excavated	48.1	< 0.29 U	< 0.59 U	< 0.54 U	< 0.54 U	36 J	9.9 J	2.2 J	< 0.63 U	< 0.44 U
Rear Parking Lot	SSHS-B830	PS-FD-10	1/11/2018	854.01	0 - 2 ft	180-74124-1	Excavated	7.57	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	5.6 J	1.6 J	0.37 J	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B831	PS-FD-6	1/10/2018	852.87	0 - 2 ft	180-74125-1	Excavated	5.53	< 0.028 U	< 0.056 U	< 0.051 U	< 0.052 U	4.1 J	1.1 J	0.33 J	< 0.061 U	< 0.042 U
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-0-2	1/10/2018	852.87	0 - 2 ft	180-74125-1	Excavated	0.517	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.37 J	0.12 J	0.027 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-0-2	1/10/2018	854.16	0 - 2 ft	180-74125-1	Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-0-2	1/12/2018	853.08	0 - 2 ft	180-74207-1	Excavated	79.6	< 0.29 U	< 0.58 U	< 0.53 U	< 0.54 U	55 J	21 J	3.6 J	< 0.63 U	< 0.43 U
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-0-2	1/9/2018	852.53	0 - 2 ft	180-74014-1	Excavated	7.16	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	5.1 J	1.7 J	0.36 J	< 0.012 U	< 0.0085 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-0-2	1/12/2018	852.96	0 - 2 ft	180-74207-1	Excavated	204	< 0.29 U	< 0.58 U	< 0.53 U	< 0.53 U	130 J	61 J	13 J	< 0.63 U	< 0.43 U
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-0-2	1/20/2018	852.83	0 - 2 ft	180-74390-1	Excavated	17.5	< 0.24 U	< 0.47 U	< 0.43 U	< 0.44 U	12 J	4.9 J	0.6 J	< 0.51 U	< 0.35 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-0-2	1/9/2018	851.95	0 - 2 ft	180-74014-1	Excavated	0.091	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.064 J	0.027 J	< 0.0049 U	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-0-2	1/18/2018	850.25	0 - 2 ft	180-74307-1	Excavated	17.51	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	13 J	3.7 J	0.81 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-0-2	1/20/2018	850.15	0 - 2 ft	180-74390-1	Excavated	39.4	< 0.057 U	< 0.11 U	< 0.1 U	< 0.1 U	29 J	9.2 J	1.2 J	< 0.12 U	< 0.084 U
Rear Parking Lot	SSHS-B841	PS-FD-30	1/20/2018	850.17	0 - 2 ft	180-74390-1	Excavated	46.5	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	33 J	12 J	1.5 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-0-2	1/20/2018	850.17	0 - 2 ft	180-74390-1	Excavated	29.03	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	21 J	7.1 J	0.93 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-0-2	1/20/2018	852.12	0 - 2 ft	180-74390-1	Excavated	23.25	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	16 J	6.4 J	0.85 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-0-2	1/18/2018	850.33	0 - 2 ft	180-74307-1	Excavated	0.366	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.25 J	0.099 J	0.017 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B851	PS-FD-24	1/18/2018	851.45	0 - 2 ft	180-74307-1	Excavated	12.25	< 0.029 U	< 0.058 U	< 0.053 U	< 0.053 U	9.2 J	2.5 J	0.55 J	< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-0-2	1/18/2018	851.45	0 - 2 ft	180-74307-1	Excavated	12.34	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	8.9 J	3.1 J	0.34 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B852	PS-FD-28	1/19/2018	851.29	0 - 2 ft	180-74310-1	Excavated	8.54	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	6 J	2.3 J	0.24 J	< 0.12 U	< 0.085 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-0-2	1/19/2018	851.29	0 - 2 ft	180-74310-1	Excavated	5.59	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	3.9 J	1.5 J	0.19 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-0-2	1/8/2018	852.22	0 - 2 ft	180-74016-1	Excavated	2.01	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	1.4 J	0.5 J	0.11 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B854	PS-FD-3	1/9/2018	851.71	0 - 2 ft	180-74014-1	Excavated	0.019	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.019	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-0-2	1/9/2018	851.71	0 - 2 ft	180-74014-1	Excavated	ND	< 0.0055 U	< 0.011 U	< 0.0099 U	< 0.01 U	< 0.013 U	< 0.011 U	< 0.0048 U	< 0.012 U	< 0.0081 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-0-2	1/10/2018	851.59	0 - 2 ft	180-74125-1	Excavated	14.34	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	10 J	3.6 J	0.74 J	< 0.12 U	< 0.085 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-0-2	1/17/2018	850.70	0 - 2 ft	180-74241-1	Excavated	0.076	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.057 J	0.019 J	< 0.0051 U	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-0-2	1/20/2018	850.15	0 - 2 ft	180-74390-1	Excavated	0.1639	< 0.0058 U	< 0.011 U	< 0.01 U	< 0.011 U	0.11 J	0.045 J	0.0089 J	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-0-2	1/9/2018	852.32	0 - 2 ft	180-74014-1	Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	851.27	0 - 2 ft	180-74307-2	Excavated	1.971	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	1.4 J	0.49 J	0.081 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B880	PS-FD-36	1/22/2018	850.01	0 - 2 ft	180-74331-1	Excavated	29.7	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	20 J	8.4 J	1.3 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-0-2	1/22/2018	850.01	0 - 2 ft	180-74331-1	Excavated	35.8	< 0.069 U	< 0.14 U	< 0.13 U	< 0.13 U	24 J	9.5 J	2.3 J	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-0-2	1/22/2018	849.63	0 - 2 ft	180-74331-1	Excavated	38	< 0.074 U	< 0.15 U	< 0.13 U	< 0.14 U	26 J	9.6 J	2.4 J	< 0.16 U	< 0.11 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-0-2	1/19/2018	850.66	0 - 2 ft	180-74310-1	Excavated	102.8	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	76 J	24 J	2.8 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-0-2	1/22/2018	850.02	0 - 2 ft	180-74331-1	Excavated	14.52	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	10 J	3.9 J	0.62 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B888	PS-FD-37	1/22/2018	850.02	0 - 2 ft	180-74331-1	Excavated	7.52	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	5.2 J	2 J	0.32 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-0-2	1/12/2018	852.37	0 - 2 ft	180-74207-1	Excavated	75.3	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	49 J	22 J	4.3 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-0-2	1/19/2018	851.47	0 - 2 ft	180-74310-1	Excavated	54.5	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	40 J	13 J	1.5 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-0-2	1/17/2018	850.94	0 - 2 ft	180-74241-1	Excavated	22.1	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	15 J	6 J	1.1 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-0-2	1/19/2018	851.16	0 - 2 ft	180-74310-1	Excavated	31.5	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	23 J	7.6 J	0.9 J	< 0.13 U	< 0.09 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-0-2	1/9/2018	852.71	0 - 2 ft	180-74014-1	Excavated	29	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	21 J	6.6 J	1.4 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	850.31	0 - 2 ft	180-74241-2	Excavated	10.89	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	8 J	2.4 J	0.49 J	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-0-2	1/16/2018	850.75	0 - 2 ft	180-74203-1	Excavated	0.247	< 0.0055 U	< 0.011 U	< 0.01 U	< 0.01 U	0.23 J		0.017 J	< 0.012 U	< 0.0083 U
Rear Parking Lot	SSHS-B931	SSHS-B931-SUB-0-2	1/10/2018	850.20	0 - 2 ft	180-74125-1	Excavated	13.04	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	9.4 J	3 J	0.64 J	< 0.063 U	< 0.043 U
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-0-2	1/10/2018	850.54	0 - 2 ft	180-74125-1	Excavated	0.091	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.091	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B933	PS-FD-26	1/19/2018	850.91	0 - 2 ft	180-74310-1	Excavated	21.67	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	16 J	5.1 J	0.57 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B933	SSHS-B933-SUB-0-2	1/19/2018	850.91	0 - 2 ft	180-74310-1	Excavated	16.34	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	12 J	3.6 J	0.74 J	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B934	PS-FD-5	1/10/2018	849.30	0 - 2 ft	180-74125-1	Excavated	18.5	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	12 J	5.3 J	1.2 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B934	SSHS-B934-SUB-0-2	1/10/2018	849.30	0 - 2 ft	180-74125-1	Excavated	23.7	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	14 J	7.6 J	2.1 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B935	SSHS-B935-SUB-0-2	1/10/2018	847.88	0 - 2 ft	180-74125-1	Excavated	12.89	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	8.1 J	3.9 J	0.89 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-0-2	1/22/2018	850.00	0 - 2 ft	180-74331-1	Excavated	175.3	< 0.75 U	< 1.5 U	< 1.4 U	< 1.4 U	130 J	37 J	8.3 J	< 1.6 U	< 1.1 U
Rear Parking Lot	SSHS-B946	PS-FD-35	1/22/2018	850.00	0 - 2 ft	180-74331-1	Excavated	6.23	< 0.0072 U	< 0.014 U	< 0.013 U	< 0.013 U	4.3 J	1.5 J	0.43 J	< 0.016 U	< 0.011 U
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-0-2	1/22/2018	850.00	0 - 2 ft	180-74331-1	Excavated	6.81	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	4.8 J	1.6 J	0.41 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B959	PS-FD-2	2/28/2018	851.25	0 - 2 ft	180-75403-1	Excavated	20.8	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	13	6.5	1.3	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-0-2	2/28/2018	851.25	0 - 2 ft	180-75403-1	Excavated	13.34	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	8.7	3.8	0.84	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B968	SSHS-B968-SUB-0-2	3/1/2018	851.52	0 - 2 ft	180-75478-1	Excavated	4.61	< 0.029 U	< 0.057 U	< 0.052 U	< 0.053 U	2.8	1.6	0.21	< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B995	SSHS-B995-SUB-0-2	3/1/2018	850.03	0 - 2 ft	180-75478-1	Excavated	65	< 0.17 U	< 0.33 U	< 0.31 U	< 0.31 U	47	16	2	< 0.36 U	< 0.25 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
Football Field	SSHS-FB10	SSHS-FB10-A-SS	7/22/2014	855.71	0 - 0.17 ft	180-35079-1	Excavated	0.92	< 0.0008 U	< 0.001 U	< 0.00092 U	< 0.00087 U	0.62 J	0.3 J	< 0.00076 U	< 0.0012 U	< 0.00069 U
Football Field	SSHS-FB10-A	SSHS-FB10-A-SUB-0-2	7/15/2015	855.73	0 - 2 ft	180-45961-1	Excavated	48	< 0.083 U	< 0.1 U	< 0.14 U	< 0.1 U	34 J	14 J	< 0.089 U	< 0.15 U	< 0.082 U
Football Field	SSHS-FB11	SSHS-FB11-A-SS	7/22/2014	855.55	0 - 0.17 ft	180-35079-1	Excavated	0.159	< 0.00082 U	< 0.0011 U	< 0.00094 U	< 0.0009 U	0.088 J	0.071 J	< 0.00078 U	< 0.0012 U	< 0.00071 U
Football Field	SSHS-FB1-A	SSHS-FB1-A-SS	7/22/2014	856.72	0 - 0.17 ft	180-35079-1	Excavated	0.36	< 0.00079 U	< 0.001 U	< 0.00091 U	< 0.00087 U	0.25 J	0.11 J	< 0.00076 U	< 0.0012 U	< 0.00069 U
Football Field	SSHS-FB2-A	SSHS-FB2-A-SS	7/22/2014	856.16	0 - 0.17 ft	180-35079-1	Excavated	0.11	< 0.0014 U	< 0.0019 U	< 0.0017 U	< 0.0016 U	< 0.00092 U	0.11	< 0.0014 U	< 0.0021 U	< 0.0012 U
Football Field	SSHS-FB3-A	SSHS-FB3-A-SS	7/22/2014	856.44	0 - 0.17 ft	180-35079-1	Excavated	0.151	< 0.0008 U	< 0.001 U	< 0.00092 U	< 0.00088 U	0.1 J	0.051 J	< 0.00077 U	< 0.0012 U	< 0.00069 U

TABLE 5-4A
Surface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-FB4-A	SSHS-FB4-A-SS	7/22/2014	856.11	0 - 0.17 ft	180-35079-1	Excavated	0.098	< 0.0017 U	< 0.0022 U	< 0.0019 U	< 0.0019 U	0.037 J	0.061 J	< 0.0016 U	< 0.0025 U	< 0.0015 U
Football Field	SSHS-FB6-A	SSHS-DUP5	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	0.42	< 0.0016 U	< 0.0021 U	< 0.0019 U	< 0.0018 U	0.23 J	0.19 J	< 0.0016 U	< 0.0024 U	< 0.0014 U
Football Field	SSHS-FB6-A	SSHS-FB6-A-SS	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	0.33	< 0.0008 U	< 0.001 U	< 0.00092 U	< 0.00087 U	0.18 J	0.15 J	< 0.00076 U	< 0.0012 U	< 0.00069 U
Football Field	SSHS-FB6-AA	SSHS-FB6-AA-SUB-0-2	7/15/2015	856.09	0 - 2 ft	180-45961-1	Excavated	2.01	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	1.3 J	0.71 J	< 0.0071 U	< 0.0038 U
Football Field	SSHS-FB7	B23401T3	8/14/2000	856.66	0 - 0.5 ft	NA	Excavated	0.19	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	0.19	< 0.046 U	< 0.046 U		
Football Field	SSHS-FB7-A	SSHS-FB7-A-SS	7/21/2014	856.41	0 - 0.17 ft	180-35053-1	Excavated	0.41	< 0.0015 U	< 0.0019 U	< 0.0017 U	< 0.0016 U	0.28 J	0.13 J	< 0.0014 U	< 0.0022 U	< 0.0013 U
Football Field	SSHS-FB7-B	SSHS-FB7-B-SS	7/21/2014	856.19	0 - 0.17 ft	180-35053-1	Excavated	0.229	< 0.0014 U	< 0.0019 U	< 0.0017 U	< 0.0016 U	0.14 J	0.089 J	< 0.0014 U	< 0.0021 U	< 0.0013 U
Football Field	SSHS-FB7-C	SSHS-FB7-C-SS	7/21/2014	856.56	0 - 0.17 ft	180-35053-1	Excavated	0.065	< 0.0015 U	< 0.002 U	< 0.0018 U	< 0.0017 U	0.037 J	0.028 J	< 0.0015 U	< 0.0023 U	< 0.0013 U
Football Field	SSHS-FB7-D	SSHS-FB7-D-SS	7/21/2014	856.62	0 - 0.17 ft	180-35053-1	Excavated	0.29	< 0.0016 U	< 0.0021 U	< 0.0019 U	< 0.0018 U	0.18 J	0.11 J	< 0.0016 U	< 0.0024 U	< 0.0014 U
Football Field	SSHS-FB7-E	SSHS-FB7-DUP3	7/21/2014	856.28	0 - 0.17 ft	180-35053-1	Excavated	9.3	< 0.013 U	< 0.016 U	< 0.015 U	< 0.014 U	6.8 J	2.5 J	< 0.012 U	< 0.019 U	< 0.011 U
Football Field	SSHS-FB7-E	SSHS-FB7-E-SS	7/21/2014	856.28	0 - 0.17 ft	180-35053-1	Excavated	0.26	< 0.0015 U	< 0.0019 U	< 0.0017 U	< 0.0016 U	0.16 J	0.1 J	< 0.0014 U	< 0.0021 U	< 0.0013 U
Football Field	SSHS-FB9-A	SSHS-FB9-A-SS	7/22/2014	854.80	0 - 0.17 ft	180-35079-1	Excavated	2.091	< 0.0016 U	< 0.0021 U	< 0.0018 U	< 0.0018 U	1.2 J	0.8 J	< 0.0015 U	0.091 J	< 0.0014 U
Football Field	SSHS-FB9-AA	SSHS-FB9-AA-SS	7/16/2015	854.80	0 - 0.17 ft	180-46033-1	Excavated	2.52	< 0.0046 U	< 0.0057 U	< 0.0078 U	< 0.0057 U	1.4 J	0.95 J	0.17 J	< 0.0084 U	< 0.0046 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-0-2	8/30/2016	850.92	0 - 2 ft	180-58275-1	Excavated	5.1	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	3.4 J	1.5 J	0.2 J	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-NE SIDEWALL S1	NORTH EXCAVATION SIDEWALL S1	7/10/2017	856.41	0 - 2 ft	180-68039-1	Excavated	6.24	< 0.0093	< 0.009	< 0.0069	< 0.014	3.8	1.9	0.54	< 0.013	< 0.0053
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	ND	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U		
Northern Athletic Field	SSHS-SS10	_12 Sep 00SS10_-	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	0.73	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.63	< 0.045 U	0.1		
Northern Athletic Field	SSHS-SS11	_12 Sep 00SS11_-	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	0.73	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.58	< 0.037 U	0.15		
Football Field	SSHS-SS12-A	SSHS-SS12-A-SS	7/22/2014	855.86	0 - 0.17 ft	180-35079-1	Excavated	0.58	< 0.00074 U	< 0.00095 U	< 0.00086 U	< 0.00081 U	0.37 J	0.21 J	< 0.00071 U	< 0.0011 U	< 0.00064 U
Football Field	SSHS-SS12-B	SSHS-SS12-B-SS	7/22/2014	856.00	0 - 0.17 ft	180-35079-1	Excavated	4.3	< 0.0036 U	< 0.0046 U	< 0.0041 U	< 0.0039 U	2.1 J	2.2 J	< 0.0034 U	< 0.0052 U	< 0.0031 U
Football Field	SSHS-SS12-C	SSHS-SS12-C-SS	7/22/2014	855.81	0 - 0.17 ft	180-35079-1	Excavated	0.56	< 0.00074 U	< 0.00094 U	< 0.00085 U	< 0.00081 U	0.3 J	0.26 J	< 0.0007 U	< 0.0011 U	< 0.00064 U
Football Field	SSHS-SS15	SSHS-SS15-SS	7/22/2014	857.17	0 - 0.17 ft	180-35079-1	Excavated	0.0854	< 0.0016 U	< 0.002 U	< 0.0018 U	< 0.0017 U	0.042 J	0.036 J	< 0.0015 U	0.0074 J	< 0.0014 U
Football Field	SSHS-SS16	SSHS-SS16-SS	7/22/2014	857.27	0 - 0.17 ft	180-35079-1	Excavated	0.053	< 0.00079 U	< 0.001 U	< 0.00091 U	< 0.00086 U	0.028 J	0.025 J	< 0.00075 U	< 0.0012 U	< 0.00068 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	0.98	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	0.73	< 0.46 U	0.25		
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	ND	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U		
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	0.053	< 0.045 U	< 0.045 U	< 0.045 U	< 0.045 U	0.053	< 0.045 U	< 0.045 U		
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	ND	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U		
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	0.22	< 0.045 U	< 0.045 U	< 0.045 U	< 0.045 U	0.22	< 0.045 U	< 0.045 U		

DRAFT

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			3.6	104	< 0.7 U	< 0.7 U		81.7			18.8		20.5		
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	7900	< 0.21 U	12	82	0.38 J	0.12 J	16000	12		7.7	63	21000	54	3900	540
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated	9510	0.25	8.2	89.3	0.42	1.9	19100	15.9 *E	< U		65.7	25500	63.6 NE	5010	458 *E
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated			4.2	120	< 0.62 U	< 0.62 U		15.8			14.9		17.7		
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated			3.5	75.5	< 0.66 U	< 0.66 U		19.5			19		22.2		
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated			6.2	114	< 0.64 U	< 0.64 U		12.3			14.8		17.9		
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated			4.4	111	< 0.65 U	< 0.65 U		15.5			18.5		21		
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008		0 - 2.6 ft	-	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700	171 NE	3760	379 *E
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008		0 - 2.6 ft	-	Not Excavated															
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008		0 - 2.6 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated	11000	< 0.47 U	7.8	110	0.55	0.2 J	4000	15		9.6	22	22000	26	3700	630
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated	8100	< 0.44 U	7.9	100	0.45 J	0.22 J	2600	13		7.6	21	17000	30	2400	480
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated	10000	< 0.48 U	6.8	110	0.5 J	0.17 J	2500	14		8.3	24	22000	30	2700	540
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.45 U	6.7	100	0.51 J	0.19 J	2000	17		8.5	14	20000	16	2800	510
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated	8600	< 0.47 U	6.6	82	0.43 J	0.16 J	2000	13		7.4	16	18000	15	2500	480
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	7400	< 0.4 U	5.9	78	0.32 J	0.11 J	31000	11		6.1	24	17000	30	14000	360
Football Field	SSHS-B2031	FD-57	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	9800	< 0.45 U	6.7	87	0.45 J	0.11 J	2300	14		7.9	15	19000	15	2600	490
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.42 U	6.9	88	0.48 J	0.12 J	2200	15		8.1	15	20000	16	2800	510
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	854.88	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.43 U	6.9	100	0.51	0.15 J	2500	17		8.5	14	20000	14	2900	500
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	854.70	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.44 U	7.2	110	0.52	0.15 J	2400	16		8.8	18	21000	18	2900	540
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated	11000	0.54 J	7.5	110	0.55 J	0.21 J	2800	17		9.2	20	21000	28	3000	540
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated	11000	< 0.48 U	6.7	99	0.54 J	0.37 J	3300	52		8.7	26	22000	23	3100	490
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated	12000	< 0.46 U	7.7	110	0.53 J	< 0.049 U	2800	38		9.5	19	21000	19	3200	500
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated	10000	0.67 J	7.1	96	0.52 J	0.2 J	3900	15		8.6	20	21000	120	2900	550
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated	10000	< 0.5 U	6.4	100	0.49 J	0.33 J	7200	55		8.3	21	21000	19	5000	490
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated	12000	< 0.53 U	7.2	110	0.55 J	0.33 J	5200	48		9.2	23	23000	22	3800	540
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated	9000	< 0.48 U	6.6	89	0.44 J	0.27 J	4200	37		7.7	21	19000	29	3200	460
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	855.40	0 - 0.17 ft	180-80225-3	Excavated	9900	< 0.46 U	6.8	91	0.5 J	< 0.049 U	2200	14		8.5	17	19000	19	2700	460
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated	11000	< 0.52 U	7.4	85	0.52 J	0.3 J	3400	52		8.4	24	21000	21	3100	470
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated	11000	< 0.53 U	6.8	110	0.55 J	0.29 J	3700	46		8.8	22	22000	18	3300	520
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated	10000	< 0.47 U	7.3	92	0.53 J	0.14 J	3100	15		8.5	17	20000	18	2900	470
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated	10000	1.8	7.5	100	0.51 J	< 0.057 U	3000	53		10	39	21000	130	2900	640
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated	6300	< 0.62 U	3.6	84	0.32 J	0.24 J	24000	19		5.3 J	85	13000	19	4300	400
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.46 U	7.6	100	0.54	0.22 J	2500	14		8.5	16	20000	19	2800	520
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.5 U	8.2	110	0.51 J	0.21 J	3500	18		7.8	23	20000	28	2900	450
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated	11000	< 0.51 U	7	110	0.54 J	0.16 J	3600	15		8.6	24	20000	30	2800	540
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	856.56	0 - 0.17 ft	180-80275-1	Excavated	8700	< 0.48 U	6.2	95	0.45 J	0.19 J	4200	12		7.4	20	18000	23	2600	450
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	7700	0.65 J	9	120	0.4 J	0.24 J	9600	34		8.4	300	30000	120	3000	530
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	9200	< 0.37 U	7.4	73	0.4 J	0.17 J	22000	14		8	51	25000	35	5100	490
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	8800	< 0.39 U	6.1	110	0.35 J	0.16 J	19000	15		7.1	63	20000	520	4600	410
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	6100	< 0.36 U	15	63	0.3 J	0.089 J	49000	8.9		5.4	26	15000	25	19000	400
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	7900	< 0.35 U	5.3	84	0.32 J	0.14 J	65000	11		6.8	31	17000	16	7000	450
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	5900	< 0.36 U	3.9	44	0.24 J	0.11 J	46000	8.4		4.7 J	22	22000	18	4800	400
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	855.49	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.48 U	6.4	99	0.52 J	0.29 J	3600	41		8.5	22	21000	23	3100	490
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	857.04	0 - 0.17 ft	180-80105-2	Excavated	9900	< 0.48 U	6.3	96	0.47 J	0.24 J	4500	38		7.8	22	20000	34	3200	470
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated	12000	< 0.52 U	7.2	110	0.59 J	0.28 J	2800	40		8.9	23	23000	24	3200	500
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated	9300	< 0.47 U	6.5	89	0.49 J	0.26 J	2900	37		7.5	21	19000	22	2700	420
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	8100	1.4	13	190	0.42 J	0.22 J	9700	30		11	93	55000	230	2800	960
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	7600	< 0.4 U	8.3	180	0.39 J	0.25 J	23000	16		7.2	71	25000	200	4200	530
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	6300	< 0.37 U	5.1	190	0.36 J	0.29 J	40000	12		4.3 J	56	14000	180	3600	400
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	4500	< 0.38 U	5.1	35	0.27 J	0.066 J	9700	5.8		4 J	15	12000	8.8	2300	350
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated	12000	< 0.5 U	6.9	100	0.58	0.27 J	2700	43		9.1	22	23000	21	3200	500
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated	7100	< 0.47 U	5.9	73	0.39 J	0.21 J	6200	14		6.2 J	25	17000	65	3200	360
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated	8900	< 0.58 U	5.4	99	0.46 J	0.24 J	4200	21		7 J	24	18000	29	2600	390
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	855.38	0 - 0.17 ft	180-80157-2	Excavated	11000	< 0.48 U	7.2	100	0.54 J	0.3 J	2800	45		9.2	24	22000	24	3100	500
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	855.74	0 - 0.17 ft	180-80157-2	Excavated	10000	< 0.53 U	6.5	82	0.48 J	0.24 J	4400	42		7.9	20	19000	19	3300	420
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	856.38	0 - 0.17 ft	180-80157-2	Excavated	11000	< 0.6 U,F1	6.6	92	0.51 J	0.36 J	7600	71		8.3 J	26	20000	32	3300	450
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	854.93	0 - 0.17 ft	180-80157-2	Excavated	9100	< 0.6 U	7	84	0.43 J	1.1	4900	23		7.3 J	25	18000	35	2900	450
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	857.03	0 - 0.17 ft	180-80157-2	Excavated	10000	< 0.51 U	6.8	95	0.48 J	0.25 J	5200	45		8.3	20	19000	18	3700	480
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	856.56	0 - 0.17 ft	180-80157-2	Excavated	10000	< 0.5 U	7.4	94	0.49 J	0.33 J	4400	51		8.4	26	20000	46	3100	460
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	855.33	0 - 0.17 ft	180-80106-3	Excavated	9700	< 0.66 U	8.4	100	0.51 J	0.48 J	3800	26		8 J	25	20000	34	2800	500
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	855.28	0 - 0.17 ft	180-80275-1	Excavated	8600	< 0.4 U	5	57	0.35 J	0.1 J	18000	11		6.7	18	17000	13	5000	370
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	856.14	0 - 0.17 ft	180-80106-3	Excavated	9200	< 0.4 U	5	59	0.38 J	0.071 J	19000	12		7.4	18	18000	13	4800	360
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	856.82	0 - 0.17 ft	180-80157-2	Excavated	11000	< 0.49 U	6.6	84	0.51 J	0.24 J	4500	44		8.7	20	20000	17	3400	470
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	854.83	0 - 0.17 ft	180-80275-1	Excavated	10000	< 0.5 U	6.6	99	0.52 J	0.23 J	3200	21		8	20	20000	58	2700	440
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	855.41	0 - 0.17 ft	180-80091-4	Excavated	8500	< 0.4 U	4.6	52	0.34 J	0.089 J	23000	11		7	17	17000	13	5200	400
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	855.30	0 - 0.17 ft	180-80091-4	Excavated	8500	< 0.38 U	4.6	53	0.35 J	0.082 J	21000	11		6.9	17	18000	11	7400	390
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	855.25	0 - 0.17 ft	180-80157-3	Excavated	11000	< 0.45 U	7	100	0.5 J	0.19 J	6800	14		9	16	20000	15	3700	490
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	855.30	0 - 0.17 ft	180-80106-3	Excavated	10000	< 0.79 U	7.8	120	0.56 J	0.47 J	7400	19		7.5 J	29	19000	38	2900	500
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	855.07	0 - 0.17 ft	180-80091-4	Excavated	8500	< 0.39 U	5.1	58	0.34 J	0.083 J	21000	11		6.9	21	17000	18	4600	340
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	11000	< 0.39 U,F1	5.6	66	0.42 J	0.12 J	5400	14		8.6	22	21000	14	4100	470
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	7100	16	9.8	77	0.35 J	< 0.044 U	9400	22		10	150	54000	95	2800	590
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	7700	1 J	5.4	79	0.35 J	< 0.041 U	15000	14		7.1	86	21000	56	3200	750
Football Field	SSHS-B2792	SSHS-B2792-SS	5/15/2019	856.18	0 - 0.17 ft	180-90165-1	Excavated	11000	< 0.52 U	6.9	110	0.56 J	0.36 J	5000	48		9	28	21000	25	4100	520

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.06 U	20.1		< 0.71 U	< 1.4 U						77.8
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	0.032 J	47	750	0.54 J	< 0.043 U	92 J		0.17 J		13	110
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated	0.14	44.4 *E	790	2.1	< U	207		< U		15	90.3 NE
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.06 U	20.8		< 0.64 U	< 1.2 U						61.4
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.06 U	22.5		< 0.65 U	< 1.3 U						79.6
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.06 U	19.3		< 0.64 U	< 1.3 U						58.4
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.06 U	20.8		< 0.63 U	< 1.3 U						68.8
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	0.042	453 *E	900	1.8	< U	1270		< U		14.7	111 NE
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	0 - 2.6 ft	-	Not Excavated							< U				
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	0 - 2.6 ft	-	Not Excavated							< U				
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated	0.16	22	1200	< 0.71 U	< 0.14 U	44 J		< 0.29 U		15	78
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated	0.057	20	1100	< 0.66 U	< 0.13 U	40 J		< 0.27 U		12	110
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated	0.036 J	24	970	< 0.72 U	< 0.15 U	42 J		< 0.29 U		14	70
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated	0.032 J	19	900	< 0.68 U	< 0.14 U	39 J		< 0.28 U		14	99
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated	0.028 J	17	1100	< 0.71 U	< 0.15 U	55 J		< 0.29 U		13	80
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	0.68	17	670	< 0.6 U	0.42 J	91 J		< 0.24 U		14	74
Football Field	SSHS-B2031	FD-57	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	0.026 J	17	890	< 0.68 U	< 0.14 U	< 34 U		< 0.28 U		14	58
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	0.024 J	18	980	< 0.64 U	< 0.13 U	42 J		< 0.26 U		15	57
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	854.88	0 - 0.17 ft	180-80275-1	Excavated	0.024 J	19	950	< 0.66 U	< 0.13 U	37 J		< 0.27 U		13	60
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	854.70	0 - 0.17 ft	180-80275-1	Excavated	0.076	21	1200	0.69 J	< 0.14 U	39 J		< 0.27 U		14	63
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated	0.23	25	1500	< 0.75 U	< 0.15 U	40 J		< 0.3 U		15	72
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated	0.066	21		< 0.73 U	< 0.15 U	65 J		< 0.29 U		15	73
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated	0.036 J	20	1500	< 0.7 U	< 0.14 U	64 J		0.31 J		16	68
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated	0.12	19	1400	< 0.75 U	< 0.15 U	51 J		< 0.31 U		14	69
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated	0.054	20		< 0.76 U	< 0.16 U	48 J		< 0.31 U		14	69
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated	0.052	21		< 0.8 U	< 0.16 U	66 J		< 0.32 U		16	75
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated	0.081	18		< 0.73 U	< 0.15 U	46 J		< 0.3 U		13	69
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	855.40	0 - 0.17 ft	180-80225-3	Excavated	0.14	19	1300	< 0.69 U	< 0.14 U	36 J		0.4 J		14	60
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated	0.18	28		< 0.79 U	< 0.16 U	74 J		< 0.32 U		14	73
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated	0.088	23		< 0.8 U	< 0.16 U	70 J		< 0.32 U		15	71
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated	0.076	21	1100	< 0.7 U	< 0.14 U	< 35 U		< 0.29 U		14	63
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated	0.16	32		< 0.81 U	< 0.17 U	52 J		0.33 J		16	140
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated	0.038 J	140		< 0.94 U	< 0.19 U	360 J		< 0.38 U		16	170
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated	0.055	19	1200	< 0.69 U	< 0.14 U	41 J		< 0.28 U		15	100
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated	0.19	20		< 0.75 U	0.26 J	53 J		< 0.31 U		16	79
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated	0.19	27		< 0.77 U	< 0.16 U	68 J		< 0.31 U		15	73
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	856.56	0 - 0.17 ft	180-80275-1	Excavated	0.064	20		< 0.73 U	< 0.15 U	38 J		< 0.3 U		12	210
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	0.08	110		0.82 J	< 0.12 U	110 J		< 0.23 U		17	140
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	0.051	39		0.74 J	< 0.11 U	80 J		< 0.23 U		15	100
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	0.051	31		< 0.59 U	< 0.12 U	69 J		< 0.24 U		14	130
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	0.059	18		0.79 J	< 0.11 U	80 J		< 0.22 U		17	58
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	0.019 J	21		< 0.53 U	< 0.11 U	75 J		< 0.21 U		24	62
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	0.027 J	17		0.62 J	< 0.11 U	77 J		< 0.22 U		27	62
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	855.49	0 - 0.17 ft	180-80275-1	Excavated	0.068	24		< 0.73 U	< 0.15 U	70 J		< 0.29 U		14	69
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	857.04	0 - 0.17 ft	180-80105-2	Excavated	0.089	18		< 0.73 U	< 0.15 U	52 J		< 0.3 U		14	69
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated	0.059	22		< 0.79 U	< 0.16 U	65 J		< 0.32 U		16	73
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated	0.073	20		< 0.72 U	< 0.15 U	52 J		< 0.29 U		14	64
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.095	730		0.68 J	0.15 J	74 J		< 0.24 U		18	360
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.097	94		0.69 J	< 0.12 U	97 J		< 0.24 U		17	120
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	0.11	47		< 0.56 U	< 0.11 U	130 J		< 0.23 U		12	120
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	0.037	11		< 0.57 U	< 0.12 U	61 J		< 0.23 U		15	34
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated	0.076	22		< 0.75 U	< 0.15 U	65 J		< 0.31 U		17	74
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated	0.13	20		< 0.71 U	< 0.15 U	53 J		< 0.29 U		13	270
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated	0.15	23		< 0.87 U	< 0.18 U	70 J		< 0.35 U		13	110
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	855.38	0 - 0.17 ft	180-80157-2	Excavated	0.057	22	1200	< 0.72 U	< 0.15 U	47 J		< 0.29 U		16	74
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	855.74	0 - 0.17 ft	180-80157-2	Excavated	0.037 J	20	1100	< 0.81 U	< 0.16 U	52 J		< 0.33 U		14	64
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	856.38	0 - 0.17 ft	180-80157-2	Excavated	0.074	21	1400	< 0.9 U	< 0.18 U	81 J		< 0.37 U		15	79
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	854.93	0 - 0.17 ft	180-80157-2	Excavated	0.19	22	820 J	< 0.9 U	< 0.18 U	59 J		< 0.37 U		17	630
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	857.03	0 - 0.17 ft	180-80157-2	Excavated	0.035 J	20	1300	< 0.77 U	< 0.16 U	51 J		< 0.31 U		13	67
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	856.56	0 - 0.17 ft	180-80157-2	Excavated	0.088	21	1300	< 0.76 U	< 0.16 U	48 J		< 0.31 U		15	80
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	855.33	0 - 0.17 ft	180-80106-3	Excavated	0.045 J	22	800 J	< 0.99 U	< 0.2 U	76 J		< 0.4 U		17	480
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	855.28	0 - 0.17 ft	180-80275-1	Excavated	0.018 J	16	770	< 0.61 U	< 0.12 U	60 J		< 0.25 U		13	56
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	856.14	0 - 0.17 ft	180-80106-3	Excavated	0.018 J	18	660	< 0.6 U	< 0.12 U	64 J		< 0.24 U		14	55
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	856.82	0 - 0.17 ft	180-80157-2	Excavated	0.086	20	1400	< 0.74 U	< 0.15 U	50 J		< 0.3 U		14	67
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	854.83	0 - 0.17 ft	180-80275-1	Excavated	0.05	22	800	< 0.76 U	< 0.16 U	44 J		< 0.31 U		15	280
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	855.41	0 - 0.17 ft	180-80091-4	Excavated	0.015 J	16	730	< 0.61 U	< 0.12 U	70 J		< 0.25 U		13	55
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	855.30	0 - 0.17 ft	180-80091-4	Excavated	0.015 J	16	710	< 0.57 U	< 0.12 U	77 J		< 0.23 U		13	49
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	855.25	0 - 0.17 ft	180-80157-3	Excavated	0.02 J	21	1000	< 0.69 U	< 0.14 U	39 J		< 0.28 U		13	200
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	855.30	0 - 0.17 ft	180-80106-3	Excavated	0.11	24	1000 J	< 1.2 U	< 0.24 U	90 J		< 0.49 U		18	510
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	855.07	0 - 0.17 ft	180-80091-4	Excavated	0.019 J	17	710	< 0.6 U	< 0.12 U	66 J		< 0.24 U		12	56
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	0.018 J	21	690	< 0.59 U	< 0.12 U	58 J		< 0.24 U		14	130
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	4	31	660	< 0.62 U	< 0.13 U	69 J		< 0.25 U		28	150
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	0.095	22	680	< 0.59 U	< 0.12 U	63 J		0.27 J		16	140
Football Field	SSHS-B2792	SSHS-B2792-SS	5/15/2019	856.18	0 - 0.17 ft	180-90165-1	Excavated	0.079	42	1100	< 0.78 U	< 0.16 U	47 J		< 0.49 U		15	87

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2793	SSHS-B2793-SS	5/15/2019	855.44	0 - 0.17 ft	180-90165-1	Excavated	10000	< 0.45 UJ	7	120	0.5 J	0.37 J	4700 J-	44		8.9	35	20000	31	3700	520
Football Field	SSHS-B2794	SSHS-B2794-SS	5/15/2019	856.38	0 - 0.17 ft	180-90165-1	Excavated	12000	< 0.49 U	7.2	110	0.6	0.35 J	4100	43		10	22	23000	21	3500	610
Football Field	SSHS-B2795	SSHS-B2795-SS	5/15/2019	855.78	0 - 0.17 ft	180-90165-1	Excavated	10000	< 0.51 U	6.2	100	0.5 J	0.35 J	4400	49		8.2	25	20000	23	3400	480
Football Field	SSHS-B2796	SSHS-B2796-SS	5/15/2019	855.92	0 - 0.17 ft	180-90165-1	Excavated	11000	< 0.54 U	7.1	110	0.56 J	0.4 J	3200	64		9.4	27	22000	23	3300	540
Football Field	SSHS-B2797	SSHS-B2797-SS	5/15/2019	856.56	0 - 0.17 ft	180-90165-1	Excavated	11000	< 0.5 U	7.2	100	0.54 J	0.35 J	5100	48		9.2	23	22000	22	3800	520
Football Field	SSHS-B2798	SSHS-B2798-SS	5/15/2019	856.60	0 - 0.17 ft	180-90165-1	Excavated	11000	< 0.51 U	7.1	99	0.52 J	0.34 J	8000	59		8.9	27	22000	22	4300	540
Football Field	SSHS-B2799	SSHS-B2799-SS	5/15/2019	855.91	0 - 0.17 ft	180-90165-1	Excavated	12000	< 0.49 U	8.3	100	0.59	0.38 J	4100	63		9.8	27	24000	25	4100	550
Football Field	SSHS-B2800	PS-FD-7	5/15/2019	856.14	0 - 0.17 ft	180-90165-1	Excavated	11000	< 0.5 U	7.4	110	0.54 J	0.42 J	4100 J	65		9.1	27	22000	24	3400	540
Football Field	SSHS-B2800	SSHS-B2800-SS	5/15/2019	856.14	0 - 0.17 ft	180-90165-1	Excavated	10000	< 0.51 U	7.1	99	0.52 J	0.4 J	7900 J	61		8.5	26	21000	23	5200	520
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300	70.5 NE	4400	267 *E
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated	11000	0.63 J	8.1	120	0.59	0.2 J	2100	16		8.9	36	21000	39	2600	530
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated	11000	0.8 J	8	110	0.57	0.15 J	1900	17		8.9	29	21000	28	2700	520
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated	11000	0.71 J	7.2	98	0.55	0.14 J	1500	14		8.5	28	22000	22	2700	480
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated	11000	0.52 J	6.9	130	0.56	0.2 J	2200	28		9.2	17	20000	16	3000	610
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated	9400	< 0.39 UJ	6.4	190 J	0.47	0.2 J	33000 J	20		8	19	19000	29	7600 J	580
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated	12000	< 0.45 U	7	98	0.58	0.1 J	1100	17		9.6	15	21000	14	2900	510
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated	11000	< 0.47 U	6.5	110	0.53 J	0.11 J	1600	14		8.4	14	19000	13	2700	480
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated	11000	0.69 J	7	100	0.54	0.1 J	1800	16		8.7	18	20000	14	2800	520
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated	10000	0.5 J	6.8	97	0.52 J	0.14 J	2000 J	16		8.1	14	19000	13	2900 J	480
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated	8100	< 0.38 U	5.5	42	0.51	0.075 J	45000	18		6.1	11	17000	7.6	27000	250
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated	6600	< 0.36 U	3.7	44	0.47	0.095 J	49000	15		7.5	12	17000	7.1	31000	320
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated	13000	< 0.47 U	7.5	150	0.6	0.21 J	2200	28		9.5	16	20000	14	3100	620
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated	13000	< 0.46 U	7.2	140	0.58	0.23 J	2400	35		8.9	16	20000	15	2900	570
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated	10000	< 0.45 U	6.6	110	0.53	0.21 J	1900	35		8.6	15	20000	13	3000	530
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated	9800	< 0.45 U	7.7	100	0.51 J	0.22 J	3600	33		8.4	17	20000	16	3100	510
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated	9900	0.63 J	6.8	100	0.54	0.21 J	2500	32		8.8	17	20000	18	2900	530
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated	11000	< 0.44 U	8	110	0.56	0.13 J	2000	16		8.2	20	20000	53	2600	490
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated	11000	0.7 J	6.6	100	0.55	0.092 J	1600	15		8.4	20	20000	16	2800	470
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated	10000	< 0.45 U	6.3	100	0.48 J	0.13 J	1700	16		7.7	15	18000	12	2700	470
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated	11000	< 0.42 U	6	91	0.47 J	0.16 J	1400	24		7.4	14	17000	12	2600	430
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated	12000	0.45 J	7.1	92	0.54	0.16 J	4900	28		8.7	17	19000	15	4300	510
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated	10000	0.58 J	6.6	94	0.5	0.2 J	2400	28		8	18	19000	23	2700	510
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated	11000	0.45 J	6.5	91	0.55	0.19 J	2500	31		8.5	17	20000	15	3000	460
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated	12000	< 0.45 U	6.9	100	0.59	0.23 J	2300	35		9.5	18	21000	17	3100	530
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated	11000	< 0.44 U	7.2	120	0.58	0.25 J	2300	41		9.5	17	21000	17	3100	590
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated	12000	0.49 J	6.6	120	0.57	0.13 J	1500	17		8.6	15	20000	14	2900	550
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated	12000	< 0.46 U	8	110	0.58	0.14 J	2700	16		9.8	18	21000	20	3000	550
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated	11000	< 0.5 U	6.8	120	0.55 J	0.095 J	1800	15		8.3	15	19000	17	2800	510
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated	9600	< 0.46 U	5.9	88	0.46 J	0.091 J	2900	14		7.3	13	18000	12	3100	400
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated	12000	0.55 J	7.6	110	0.58	0.18 J	2200	23		9.3	18	21000	16	3100	550
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated	12000	0.6 J	7.1	120	0.56	0.19 J	2200	27		8.9	20	21000	18	3000	550
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated	12000	< 0.44 U	6.9	120	0.55	0.19 J	2100	27		9	17	20000	19	2900	530
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated	12000	< 0.45 U	7.4	140	0.57	0.22 J	2600	23		9.1	19	20000	25	3000	600
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated	11000	0.53 J	6.9	120	0.56	0.19 J	6300 J-	22		8.8	21	20000	19	4700 J-	540
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated	11000	< 0.42 U	6.9	120	0.53	0.22 J	2500	33		8.6	19	19000	19	2800	550
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated	9600	< 0.49 U	6.1	89	0.5 J	0.22 J	4000	35		7.8	16	19000	15	3500	450
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated	9800	< 0.43 U	6.3	94	0.53	0.24 J	2800	37		8.1	18	19000	17	2900	460
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated	13000	0.58 J	7.6	100	0.83	0.27 J	6000	39		10	21	26000	18	5100	470
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated	16000	0.69 J	8.1	100	0.92	0.22 J	4400	44		9.9	20	26000	16	4300	460
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	11000	< 0.42 U	6.8	100	0.53	0.13 J	1700	14		8.5	14	19000	15	2700	490
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	12000	0.61 J	7.8	110	0.61	0.11 J	2100	17		9.5	18	22000	18	3100	530
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated	9800	0.66 J	7.4	94	0.49 J	0.12 J	3800	14		7.6	18	19000	31	2900	460
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated	9700	< 0.39 U	5.2	87	0.49	0.08 J	28000	13		9.2	16	18000	11	16000	690
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated	11000	< 0.45 UJ	7.6	98 J-	0.53 J	0.16 J	2100 J-	20 J		9.1 J	18 J	20000	16	3000 J-	520
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated	11000	< 0.45 U	7.3	130	0.54	0.21 J	2600	26		8.6	23	20000	29	2800	540
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated	11000	< 0.43 U	7.3	130	0.55	0.19 J	2200	25		8.8	20	20000	28	2800	550
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated	12000	< 0.42 U	7.8	130	0.55	0.18 J	2600	22		9.4	21	21000	59	3000	550
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated	11000	0.65 J	7.7	140	0.56	0.84	2200	23		9.2	18	20000	20	2900	580
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated	9800	0.55 J	6.3	100	0.48	0.2 J	2100	24		8.2	17	18000	28	2700	490
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated	11000	< 0.46 U	7.1	130	0.58	0.21 J	2400	26		8.8	17	21000	21	3000	560
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	12000	< 0.47 U	7.3	100	0.57	0.13 J	1800	17		9.2	16	20000	16	2900	530
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated	6300	< 0.37 U	4.1	43	0.44	0.097 J	57000	17		8.4	17	18000	6.9	37000	310
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated	8600	< 0.46 U	6.4	96	0.51 J	0.19 J	4200	16		7.4	14	18000	15	3600	420
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated	9500	< 0.44 U	6.5	90	0.51 J	0.16 J	6900	23		8	15	20000	16	4100	440
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	11000	< 0.45 U	7.3	97	0.56	0.23 J	2700	33		9	19	21000	21	3100	510
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated	12000	0.57 J	7	110	0.59	0.092 J	1800	16		8.6	14	20000	13	2900	520
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated	11000	0.61 J	7.5	110	0.56	0.22 J	1900	14		8.7	17	20000	26	2800	510
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated	11000	0.46 J	7.1	110	0.56	0.25 J	2900	43		9.2	20	21000	38	3000	490
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated	12000	0.54 J	7.8	98	0.58	0.21 J	2500	29		9.7	23	22000	32	3200	520
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated	6100	< 0.35 UJ	3.9	36	0.47	0.097 J	59000	16		6.6	11	14000	5.4	38000	250
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated	12000	< 0.44 U	6.9	110	0.57	0.23 J	2400	27		9.1	16	21000	16	3200	520
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated	10000	0.63 J	7	120	0.54 J	0.12 J	2000	15		8.2	21	20000	27	2700	530
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated	11000	< 0.45 U	7	94	0.52 J	0.1 J	1800	15		8.5	14	20000	15	2700	450
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated	11000	0.56 J	7.8	130	0.56 J	0.15 J	1800	16		8.3	20	20000	26	2700	510

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2793	SSHS-B2793-SS	5/15/2019	855.44	0 - 0.17 ft	180-90165-1	Excavated	0.074 J	93	1100	< 0.69 U	< 0.14 U	43 J		< 0.43 U		14	100 J+
Football Field	SSHS-B2794	SSHS-B2794-SS	5/15/2019	856.38	0 - 0.17 ft	180-90165-1	Excavated	0.19	24	1200	< 0.75 U	< 0.15 U	45 J		< 0.47 U		17	76
Football Field	SSHS-B2795	SSHS-B2795-SS	5/15/2019	855.78	0 - 0.17 ft	180-90165-1	Excavated	0.32	25	1500	< 0.77 U	< 0.16 U	51 J		< 0.48 U		14	83
Football Field	SSHS-B2796	SSHS-B2796-SS	5/15/2019	855.92	0 - 0.17 ft	180-90165-1	Excavated	0.06	23	1200	< 0.81 U	< 0.17 U	43 J		< 0.51 U		16	81
Football Field	SSHS-B2797	SSHS-B2797-SS	5/15/2019	856.56	0 - 0.17 ft	180-90165-1	Excavated	0.042 J	21	1200	< 0.75 U	< 0.15 U	47 J		< 0.47 U		15	75
Football Field	SSHS-B2798	SSHS-B2798-SS	5/15/2019	856.60	0 - 0.17 ft	180-90165-1	Excavated	0.063	22	1200	< 0.77 U	< 0.16 U	46 J		< 0.48 U		15	82
Football Field	SSHS-B2799	SSHS-B2799-SS	5/15/2019	855.91	0 - 0.17 ft	180-90165-1	Excavated	0.064	27	1300	< 0.75 U	< 0.15 U	50 J		< 0.47 U		16	82
Football Field	SSHS-B2800	PS-FD-7	5/15/2019	856.14	0 - 0.17 ft	180-90165-1	Excavated	0.13	24	1300	< 0.76 U	< 0.16 U	47 J		< 0.47 U		15	81
Football Field	SSHS-B2800	SSHS-B2800-SS	5/15/2019	856.14	0 - 0.17 ft	180-90165-1	Excavated	0.1	29	1200	< 0.77 U	< 0.16 U	45 J		< 0.48 U		14	76
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated	0.082	84 *E	494	1.3	< U	132		< U		9.4	103 NE
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated	0.06	27	1300	< 0.68 U	< 0.14 U	41 J		< 0.42 U		17	81
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated	0.043 J	25	1300	< 0.72 U	< 0.15 U	< 36 U		< 0.45 U		15	73
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated	0.03 J	24	1200	0.74 J	< 0.14 U	36 J		< 0.43 U		15	73
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated	0.033 J	21	1700	< 0.65 U	< 0.13 U	< 33 U		< 0.4 U		670	620
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated	0.088	19	1100	0.83 J	< 0.12 U	60 J		< 0.37 U		13	61
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated	0.026 J	21	1100	< 0.69 U	< 0.14 U	< 34 U		< 0.43 U		16	58
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated	0.043	20	1100	< 0.7 U	< 0.14 U	36 J		< 0.44 U		15	56
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated	0.051	20	1200	< 0.68 U	< 0.14 U	< 34 U		< 0.42 U		14	59
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated	0.023 J	18	1400	< 0.72 U	< 0.15 U	< 36 UJ		< 0.45 U		14	90
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated	< 0.013 U	8.8	1300	0.71 J	< 0.12 U	81 J		< 0.35 U		28	24
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated	< 0.015 U	9.7	1200	1.1	< 0.11 U	67 J		< 0.34 U		24	25
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated	0.025 J	22	1600	< 0.71 U	< 0.15 U	< 36 U		< 0.44 U		17	69
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated	0.041	21	1600	< 0.69 U	< 0.14 U	< 35 U		< 0.43 U		17	68
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated	0.027 J	19	1400	< 0.68 U	< 0.14 U	< 34 U		< 0.43 U		14	62
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated	0.039	19	1300	< 0.69 U	< 0.14 U	36 J		< 0.43 U		13	65
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated	0.084	19	1200	< 0.7 U	< 0.14 U	< 35 U		< 0.43 U		14	66
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated	0.04 J	20	1300	< 0.67 U	< 0.14 U	44 J		< 0.42 U		17	63
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated	< 0.021 U	20	1100	< 0.71 U	< 0.14 U	< 36 U		< 0.44 U		15	58
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated	0.023 J	18	1400	< 0.68 U	< 0.14 U	41 J		< 0.42 U		14	57
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated	0.024 J	17	1400	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U		15	57
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated	0.046	20	1600	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U		16	64
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated	0.099	18	1300	< 0.64 U	< 0.13 U	36 J		< 0.4 U		14	68
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated	0.06	20	1400	< 0.68 U	< 0.14 U	35 J		< 0.42 U		14	64
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated	0.096	21	< 73 U	< 0.68 U	< 0.14 U	44 J		< 0.43 U		17	72
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated	0.15	22	1500	< 0.67 U	< 0.14 U	40 J		< 0.42 U		16	72
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated	0.033 J	19	1400	< 0.72 U	< 0.15 U	< 36 U		< 0.45 U		16	59
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated	0.028 J	23	1600	< 0.69 U	< 0.14 U	37 J		< 0.43 U		16	64
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated	0.021 J	19	1200	< 0.75 U	< 0.15 U	38 J		< 0.47 U		15	59
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated	0.019 J	17	1100	< 0.7 U	< 0.14 U	43 J		< 0.44 U		14	55
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated	0.031 J	21	1700	< 0.73 U	< 0.15 U	43 J		< 0.45 U		18	68
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated	0.049	22	1600	< 0.7 U	< 0.14 U	46 J		< 0.44 U		17	73
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated	0.11	20	1500	< 0.67 U	< 0.14 U	42 J		< 0.42 U		16	65
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated	0.11	22	1700	< 0.68 U	< 0.14 U	< 34 U		< 0.43 U		16	72
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated	0.036 J	20	1300	< 0.65 U	< 0.14 U	< 33 U		< 0.4 U		15	67
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated	0.051	20	1600	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U		16	70
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated	0.062	18	1100	< 0.75 U	< 0.15 U	51 J		< 0.47 U		12	63
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated	0.11	19	1200	< 0.66 U	< 0.13 U	38 J		< 0.41 U		13	66
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated	0.23	20	1200	< 0.75 U	< 0.15 U	68 J		< 0.47 U		26	70
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated	0.13	20	1600	< 0.74 U	< 0.15 U	83 J		< 0.46 U		31	69
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	0.051	19	1400	< 0.64 U	< 0.13 U	35 J		< 0.4 U		15	59
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	0.04	21	1600	< 0.72 U	< 0.15 U	40 J		< 0.45 U		17	66
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated	0.047	17	1400	< 0.72 U	< 0.15 U	40 J		< 0.45 U		15	70
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated	< 0.015 U	16	1200	0.61 J	< 0.12 U	47 J		< 0.37 U		17	43
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated	0.037 J	21 J	1300 J	< 0.73 UJ	< 0.14 U	45 J		< 0.46 U		15 J	63
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated	0.36	21	1700	0.68 J	< 0.14 U	51 J		< 0.43 U		17	80
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated	0.082	22	1600	< 0.65 U	< 0.13 U	43 J		< 0.41 U		16	70
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated	0.078	26	1600	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U		16	73
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated	0.031 J	22	1700	< 0.62 U	< 0.13 U	< 31 U		< 0.39 U		15	68
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated	0.13	20	1300	< 0.61 U	< 0.13 U	< 31 U		< 0.38 U		14	64
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated	0.076	21	1400	< 0.69 U	< 0.14 U	39 J		< 0.43 U		14	65
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	0.022 J	21	1200	< 0.71 U	< 0.15 U	44 J		< 0.44 U		16	64
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated	< 0.015 U	8.9	1100	0.75 J	< 0.11 U	61 J		< 0.34 U		21	22
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated	0.043	16	940	< 0.69 U	< 0.14 U	51 J		< 0.43 U		14	55
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated	0.12	18	1200	< 0.66 U	< 0.14 U	40 J		< 0.41 U		16	58
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	0.37	21	1400	< 0.69 U	< 0.14 U	40 J		< 0.43 U		15	72
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated	0.022 J	19	1300	< 0.71 U	< 0.15 U	< 36 U		< 0.44 U		16	57
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated	0.026 J	20	1000	< 0.69 U	< 0.14 U	48 J		< 0.43 U		15	64
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated	0.076	21	1600	< 0.66 U	< 0.14 U	< 33 U		< 0.41 U		16	79
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated	0.057	27	1600	0.73 J	< 0.14 U	< 32 U		< 0.39 U		17	76
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated	< 0.014 U	8.6	970	0.74 J	< 0.11 U	76 J		< 0.33 U		19	25 J-
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated	0.049	21	< 70 U	< 0.66 U	< 0.14 U	47 J		< 0.41 U		16	66
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated	0.027 J	23	1400	< 0.71 U	< 0.15 U	< 36 UJ		< 0.44 U		14	64
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated	0.026 J	19	1200	< 0.68 U	< 0.14 U	37 J		< 0.42 U		14	55
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated	0.036 J	21	1600	< 0.76 U	< 0.16 U	48 J		< 0.47 U		16	65

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated	11000	< 0.45 U	7.1	120	0.52 J	0.12 J	1800	14		8.7	17	20000	24	2700	510
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated	10000	0.56 J	6.9	130	0.52 J	0.099 J	2000	15		8.2	19	20000	37	2600	520
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated	11000	0.49 J	7.6	110	0.53 J	0.11 J	1900	17		8.5	24	20000	21	2800	520
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	10000	0.5 J	7.2	89	0.49 J	0.12 J	1800	14		8.5	16	20000	19	2600	490
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated	12000	0.47 J	7.5	89	0.55	0.087 J	1800	15		8.5	16	20000	17	2800	460
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated	10000	< 0.45 U	6.9	100	0.49 J	0.12 J	1700	13		8	15	18000	20	2400	470
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated	7900	< 0.4 U	6.7	75	0.38 J	0.15 J	17000	12		7.3	15	15000	17	6900	400
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	8800	< 0.38 U	5.8	96	0.41 J	0.23 J	34000	14		7.2	18	17000	15	8000	500
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated	10000	< 0.45 U	6.8	100	0.54	0.17 J	2200	19		8.7	17	20000	17	3000	480
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated	7500	0.47 J	8	180	0.86	0.12 J	21000	18		12	17	12000	9.6	13000	610
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0-0.17	8/26/2019	856.40	0 - 0.17 ft	180-94754-1	Excavated	9400	0.5 J	6.2	99	0.5	0.31 J	6300	16		7.9	21	20000	25	4000	550
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated	9400	< 0.45 UJ	9.7	92	0.48 J	0.21 J	7800 J-	14		8.4	34	20000	35	4400 J-	470
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated	9300	< 0.41 U	6.3	99	0.49	0.16 J	3000	11		7.8	16	18000	18	2700	500
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated	1700	< 0.4 U	2.5	36	0.22 J	0.043 J	3400	3.1		5.8	5	6500	2.4	780	120
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated	9100	< 0.43 U	12	97	0.5	0.21 J	4900	13		7.6	16	17000	26	3600	460
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated	9600	< 0.43 U	7.5	84	0.48 J	0.2 J	2700	13		7.9	15	18000	15	2700	470
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated	8800	< 0.43 U	6.8	88	0.44 J	0.2 J	3300	12		7.4	18	18000	25	2900	490
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated	9100	< 0.52 U	6.6	100	0.48 J	0.22 J	3700	12		7.6 J	15	18000	25	2700	490
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated	9800	< 0.37 U	7.2	120	0.48	0.18 J	12000	15		8.7	19	19000	21	4100	580
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated	10000	0.54 J	7.1	110	0.52 J	0.14 J	2300	14		8.8	16	19000	20	2500	540
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated	7800	< 0.38 U	5.3	95	0.42 J	0.15 J	3000	9.6		7.3	12	16000	13	2500	440
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated	11000	< 0.47 U	7.3	110	0.58	0.11 J	1800	15		9.1	18	20000	17	2800	490
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated	12000	< 0.49 U	7.4	110	0.56 J	0.15 J	2400	14		8.8	17	19000	21	2800	520
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated	11000	0.45 J	7.8	110	0.55	0.17 J	2800	14		8.5	19	20000	27	2800	510
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	11000	0.5 J	6.8	100	0.51 J	0.11 J	2100	16		8.1	16	19000	18	2700	470
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated	11000	< 0.49 U	5.7	93	0.48 J	0.13 J	2100	14		7.9	16	18000	18	2700	550
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated	12000	0.53 J	7.3	100	0.54 J	0.16 J	3400	17		9	23	21000	23	3000	510
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated		< 1.13 U	5.91	80.4	< 0.566 U	< 0.566 U		10.9		6.43	15.6		24.2		
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	10000	< 0.034 U	6.4	90	0.47	0.12 J	7500	13		8.2	19	19000	18	3800	480
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated		< 1.1 U	3.5	59.4	< 0.54 U	< 0.54 U		5.8		8.3	6.8 N		9.7		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated		< 1.16 U	5.16	108	0.588	< 0.578 U		20.7		9.66	18.8		23.2		
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	0 - 0.17 ft	180-124920-1	Not Excavated	9200	< 0.41 U	7.3	98	0.44 J	0.049 J	3200	12		8.3	14	18000	14	2600	470
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	11000	< 0.33 U	11	85	0.5	< 0.036 U	4100	14		11	17	25000	11	3400	420
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated		< 1.26 U	5.03	89.3	< 0.631 U	< 0.631 U		21.5		8.11	14.8		15.3		
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300	70.5 NE	4400	267 *E
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated		< 1.24 U	5.01	111	< 0.62 U	< 0.62 U		73.1		8.98	22.8		26.3		
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	0 - 0.17 ft	180-123985-1	Not Excavated	8700	< 0.36 UJ	10	92	0.45	0.063 J	16000	14		7.3	17	16000	20	7700	400
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	8800	< 0.36 UT	6.6	82	0.48	< 0.039 U	2000	10		7.3	11	17000	12	2800 T	400
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	9900	0.56 J	8.9	94	0.47	0.12 J	6800	17		8.6	23	20000	42	4600	480
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	9300	< 0.38 U	8.3	85	0.44 J	0.14 J	8900	17		8.0	22	19000	48	5800	420
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	7800	< 0.32 U	6.3	77	0.34 J	0.066 J	22000	10		6.7	19	16000	16	4000	380
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	9200	0.42 J	6.9	83	0.42	0.087 J	3000	11		7.8	15	17000	24	2600	470
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	9500	0.35 J	6.5	94	0.45	0.075 J	4600	12		7.9	15	18000	19	3200	450
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	9300	< 0.30 U	6.6	93	0.43	0.099 J	5700	11		8.3	16	18000	21	3600	510
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated		< 1.18	5.5	101	0.619	< 0.591		32		9.17	14.3		19.4		
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	11000	< 0.034 U	6.4	110	0.55	0.17 J	2500	27		9.2	17	21000	16	3300	510 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	8900	< 0.034 U	5.5	73	0.34 J	0.12 J	63000	13		7.6	23	18000	11	11000	550
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated		< 1.2	5.4	113	0.61	< 0.61		28.9		9.4	21.4		23.4		
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	8600	< 0.034 U	9	140	0.45	0.66	8100	13		7.9	27	19000	42	3200	530
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated		< 1.11	4.54	64.5	< 0.554	< 0.554		8.82		6.43	9.5		11.2		
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated		< 1.28	5.4	101	0.679	< 0.639		16.1		9.95	14.2		15.1		
Football Field	SSHS-B447	SSHS-447-SUB-0-2	8/24/2016	855.38	0 - 2 ft	180-57932-1	Excavated	6900	1.1	5.7	83	0.33 J	0.12 J	18000	11		6.3	50	16000	52	4900	420
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated		< 1.31	6.5	106	< 0.65	< 0.65		15		9.8	17.4		19.3		
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated		< 1.31	5.84	110	< 0.656	< 0.656		14.3		8.66	13.5		16.1		
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated		1.31	5.7	125	< 0.656	< 0.656		16.6		9.1	16.3		18.3		
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated		< 1.33	5.83	115	< 0.654	< 0.654		14.6		9.16	13.8		17.5		
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600	32 NE	4150	481 *E
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated		< 1.27 U	5.67	121	< 0.635 U	< 0.635 U		16.9		10.3	18.7		16.6		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated		< 1.12 U	3.9	36.8	< 0.558 U	< 0.558 U		13.2		< 5.58 U	7.38		5.51		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated		< 1.3 U	5.8	144	< 0.66 U	< 0.66 U		37.9		10.2	19.2		17.3		
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated		< 1.33 U	4.78	92.3	< 0.666 U	0.77		58.2		10.2	22.4		16		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated		< 1.35 U	5.72	133	< 0.673 U	0.907		91.4		10.9	23.1		20.2		
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated		< 1.3 U	5.8	124	< 0.67 U	< 0.67 U		39.5		9.9	19.8		34		
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated			4.76	112		0.654		51.2		9.06	18.3		17		
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated			5.3	84.2		0.58		39.1		9.2	19.3		20.2		
Northern Athletic Field	SSHS-B570	SSHS-B570-SUB-0-2	8/30/2016	853.41	0 - 2 ft	180-58129-1	Excavated	8000	< 0.39	7.8	75	0.38	0.57	3700	13		6.5	17	17000	11	2900	410
Northern Athletic Field	SSHS-B571	090616 09:00 PS-FD-42	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	9100	< 0.38	8.9	95	0.47	0.71	12000	12		8.1	19	20000	27	3400	490
Northern Athletic Field	SSHS-B571	SSHS-B571-SUB-0-2	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	9100	< 0.37	8.6	94	0.5	0.64	7100	12		8.2	17	18000	24	3400	520
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	8400	0.38	8.2	81	0.42	0.64	12000	14		7.8	21	18000	21	5200	540
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated		< 1.14 U	5.23	43.4	< 0.571 U	0.63		15.9		6.32	8.07		5.06		
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated		< 1.19 U	5.36	109	0.652	< 0.597 U		19.2		10	19.3		16.2		
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300	70.5 NE	4400	267 *E
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	6500	< 0.2 U	5.5	140	0.28 J	0.12 J	52000	8.6		5.8	20	15000	10	5300	520
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	6100	< 0.21 U	5	35	0.24 J	< 0.015 U	30000	8		5.2 J	24	14000	11	6900	390

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated	0.023 J	24	1300	< 0.68 U	< 0.14 U	43 J		< 0.42 U		15	58
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated	0.025 J	22	1300	< 0.74 U	< 0.15 U	38 J		< 0.46 U		14	61
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated	0.034 J	22	1500	< 0.74 U	< 0.15 U	180 J		< 0.46 U		16	69
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	0.029 J	18	1200	< 0.66 U	< 0.13 U	36 J		< 0.41 U		15	57
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated	0.026 J	19	1400	< 0.68 U	< 0.14 U	41 J		< 0.42 U		15	58
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated	0.025 J	18	1300	< 0.68 U	< 0.14 U	37 J		< 0.42 U		14	56
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated	0.027 J	14	1200	< 0.61 U	< 0.12 U	< 31 U		< 0.38 U		14	68
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	0.034 J	17	1000	0.9 J	< 0.12 U	56 J		< 0.36 U		13	59
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated	0.038 J	21	1000	< 0.68 U	< 0.14 U	< 34 U		< 0.42 U		14	63
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated	< 0.014 U	28	2200	< 0.57 U	< 0.12 U	130 J		< 0.35 U		15	75
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0-0.17	8/26/2019	856.40	0 - 0.17 ft	180-94754-1	Excavated	0.088	18	1200	0.77 J	< 0.12 U	54 J		< 0.35 U		15	78
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated	0.041 J	19	1100	< 0.69 U	< 0.14 U	< 81 U		< 0.43 U		15	97 J-
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated	0.041	18	1100	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U		13	55
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated	< 0.026 U	3.5 J	270 J	< 0.6 U	< 0.12 U	< 71 U		< 0.38 U		3.1 J	11
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated	0.053	17	1200	< 0.65 U	< 0.13 U	< 76 U		< 0.4 U		14	73
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated	< 0.025 U	17	1100	< 0.65 U	< 0.13 U	< 76 U		< 0.4 U		14	63
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated	0.025 J	17	1100	< 0.65 U	< 0.13 U	< 76 U		< 0.41 U		13	66
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated	< 0.034 U	17	1600	< 0.8 U	< 0.16 U	< 93 U		< 0.5 U		13	78
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated	0.088	20	1200	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U		13	61
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated	0.027 J	18	1300	< 0.7 U	< 0.14 U	59 J		< 0.44 U		15	54
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated	0.03 J	16	1000	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U		11	53
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated	0.026 J	21	1400	< 0.71 U	< 0.15 U	< 36 U		< 0.44 U		15	59
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated	0.028 J	21	1700	< 0.74 U	< 0.15 U	45 J		< 0.46 U		16	66
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated	0.033 J	21	1500	1 J	< 0.14 U	41 J		< 0.42 U		16	69
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	0.025 J	19	1200	< 0.72 U	< 0.15 U	39 J		< 0.45 U		14	60
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated	0.021 J	17	1100	< 0.75 U	< 0.15 U	42 J		< 0.47 U		16	60
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated	0.041 J	21	1400	< 0.77 U	< 0.16 U	76 J		< 0.48 U		17	72
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	0.0618	14.3		0.908	< 1.13 U			< 1.13 U	< 56.6 U	12.3	59.1
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	0.037	19	1000	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		14	64
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.05 U	7.6		< 0.54 U	< 1.1 U			< 1.1 U	< 53.9 U	6.6	27.7
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0578 U	21		1.64	< 1.16 U			< 1.16 U	< 57.8 U	17.2	70.5
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	0 - 0.17 ft	180-124920-1	Not Excavated	0.057	19	1400	< 0.63 U	< 0.13 U	< 74 U		< 0.39 U		13	61
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.021 U	23	1400	< 0.51 U	< 0.1 U	< 59 U		< 0.32 U		17	62
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0631 U	17.6		0.871	< 1.26 U			< 1.26 U	< 63.1 U	17	56.3
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated	0.082	84 *E	494	1.3	< U	132		< U		9.4	103 NE
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	0.0757	28.6		1.15	< 1.24 U			< 1.24 U	< 62 U	17.2	77.7
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	0 - 0.17 ft	180-123985-1	Not Excavated	0.03 J	16	1500	< 0.55 U	< 0.11 U	< 65 U		< 0.34 UJ		14	70
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.021 U	16	1300	< 0.55 UT	< 0.11 U	< 64 U		< 0.34 U		13	80 T
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	0.041	20	1100	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		17	91
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	0.040	18	1100	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U		16	87
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.019 U	17	980	0.78 J	< 0.099 U	< 57 U		< 0.30 U		12	61
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	0.033	17	1100	< 0.41 U	< 0.084 U	< 48 U		< 0.26 U		14	75
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.023 U	18	1500	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		13	70
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.023 U	19	1400	0.61 J	< 0.094 U	< 54 U		< 0.29 U		13	82
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	0.227	18.9		< 0.591	< 1.18			< 1.18	< 59.1	16.3	71.6
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	0.045	22	1000	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		17	61
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	0.026 J	19	770	1.2	< 0.034 U	100 J		< 0.034 U		14	60
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.06	23.7		< 0.59	< 1.2			< 1.2	< 60.9	16.5	70.4
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	0.1	20	700	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		13	75
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0554	13.1		0.879	< 1.11			< 1.11	< 55.4	11.8	48.1
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0639	20.7		0.81	< 1.28			< 1.28	< 63.9	18.9	62.6
Football Field	SSHS-B447	SSHS-447-SUB-0-2	8/24/2016	855.38	0 - 2 ft	180-57932-1	Excavated	0.69	64	580	0.79 J	< 0.16 U	< 140 U		< 0.49 U		14	92
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.06	20.8		< 0.63	< 1.3			< 1.3	< 65.3	17.5	63.1
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0656	17.6		< 0.656	< 1.31			< 1.31	< 65.6	16	57.1
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.06	20.1		< 0.63	< 1.3			< 1.3	< 65.1	16	63
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0664	18.6		0.883	< 1.33			< 1.33	< 66.4	18.1	55.8
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated	0.0087	19.3 *E	682	1.7	< U	110		< U		13.3	68.5 NE
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0635 U	22.2		1.57	< 1.27 U			< 1.27 U	< 63.5 U	17.9	64.1
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0558 U	5.27		< 0.558 U	< 1.12 U			< 1.12 U	< 55.8 U	27.6	26.6
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.07 U	21.9		< 0.66 U	< 1.3 U			< 1.3 U	< 66.5 U	17.6	67.9
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0666 U	22.8		1.62	< 1.33 U			< 1.33 U	< 66.6 U	16.6	68.7
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0673 U	27.6		1.47	< 1.35 U			< 1.35 U	< 67.3 U	19.9	84.4
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	0.236	21.9		0.7	< 1.3 U			< 1.4 U	< 67.2 U	16.5	77.3
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated		20.1		1.18						14.7	67.4
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated		21.6								17	66
Northern Athletic Field	SSHS-B570	SSHS-B570-SUB-0-2	8/30/2016	853.41	0 - 2 ft	180-58129-1	Excavated	0.18	16	590	< 0.43	< 0.18	< 150		< 0.55		12	53
Northern Athletic Field	SSHS-B571	090616 09:00 PS-FD-42	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	0.21	21	710	< 0.42	< 0.18	< 150		< 0.53		14	63
Northern Athletic Field	SSHS-B571	SSHS-B571-SUB-0-2	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	0.16	19	680	0.41	< 0.17	< 150		< 0.52		14	58
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	0.15	18	730	< 0.42	< 0.18	< 150		< 0.53		12	60
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0571 U	5.62		0.967	< 1.14 U			< 1.14 U	< 57.1 U	33.4	25.5
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.0597 U	24.8		0.962	< 1.19 U			< 1.19 U	< 59.7 U	20.5	67.5
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated	0.082	84 *E	494	1.3	< U	132		< U		9.4	103 NE
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	0.014 J	16	530	0.29 J	< 0.04 U	170 J		< 0.15 U		11	53
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	0.032 J	17	< 6.8 U	0.41 J	< 0.043 U	120 J		< 0.16 U		10	61

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	6400	< 0.21 U	7.8	70	0.31 J	< 0.015 U	14000	16		6.2	91	20000	130	4200	360
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	8100	0.93 J	21	270	0.39 J	< 0.015 U	29000	47		12	980	38000	590	4200	410
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	5600	< 0.22 U	8.9	82	0.3 J	< 0.015 U	16000	14		5.5	60	19000	66	3400	310
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	6600	< 0.22 U	6.7	54	0.32 J	< 0.016 U	25000	8.1		6.5	20	16000	15	4900	450
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700	171 NE	3760	379 *E
Football Field	SSHS-B70	081514 01:15_SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	11000	< 0.25 U	8.5	110	0.58	< 0.018 U	2200	14		9	18	21000	23	2800	650
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	11000	< 0.27	8.4	110	0.56	0.13	3900	17		9.5	16	21000	16	3400	550
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	8400	< 0.24	7.3	81	0.45	< 0.017	7000	11		7.5	18	19000	14	3400	490
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	9000	0.33	6.6	92	0.46	< 0.016	21000	11		7.8	13	17000	11	3200	520
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700	171 NE	3760	379 *E
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	6600	< 0.38 U	6	150	0.32 J	0.16 J	14000	9.1		6.4	24	15000	27	2400	690
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-0-2	1/22/2018	850.73	0 - 2 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-0-2	1/11/2018	853.61	0 - 2 ft	180-74124-2	Excavated															
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-0-2	1/20/2018	853.66	0 - 2 ft	180-74390-2	Excavated															
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	851.27	0 - 2 ft	180-74307-2	Excavated															
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-0-2	1/17/2018	850.48	0 - 2 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated															
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600	32 NE	4150	481 *E
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	850.31	0 - 2 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated															
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated															
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-0-2	1/16/2018	851.77	0 - 2 ft	180-74203-2	Excavated															
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600	32 NE	4150	481 *E
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated			6.2	111	< 0.74 U	< 0.74 U		88.1			24.8		30.3		
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated		< 1.12 U	5.91	92.7	< 0.559 U	< 0.559 U		11.6		7.86	19.4		23.4		
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated		< 1.11 U	6.63	99.6	< 0.554 U	< 0.554 U		12.2		8.19	20.1		25.8		
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			5.3	124	< 0.69 U	< 0.69 U		107			25.6		26.2		
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated			4	134	< 0.68 U	< 0.68 U		14.3			14.6		18.4		
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated			6.8	110	< 0.65 U	< 0.65 U		20.8			20.5		23.5		
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated		< 1.36 U	5.28	97.4	< 0.682 U	< 0.682 U		89.5		9.22	28.2		20.5		
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated		< 1.42 U	5.58	95.8	< 0.708 U	< 0.708 U		103		9.35	26.6		21.5		
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated		< 1.31 U	7	93.4	< 0.66 U	0.72		73.9		9	25.8 N		59.1		
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated		< 1.43 U	4.01	105	< 0.714 U	< 0.714 U		74.6		9.67	24.4		21		
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated		< 1.36 U	4.62	102	< 0.682 U	0.745		106		9.86	27.6		22.8		

DRAFT

TABLE 5-4B
Surface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	0.046	52	560	0.76 J	< 0.043 U	120 J		< 0.16 U		12	110
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	0.65	870	610	1.8	0.39 J	640		< 0.16 U		16	250
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	0.06	40	< 6.9 U	0.82 J	< 0.044 U	180 J		< 0.16 U		11	79
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	0.025 J	16	610	0.51 J	< 0.044 U	180 J		< 0.16 U		12	57
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated	0.042	453 *E	900	1.8	< U	1270		< U		14.7	111 NE
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	0.032 J	20	1100	0.53 J	< 0.05 U	37 J		< 0.18 U		16	61
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	0.041	21	880	< 0.36	< 0.054	27		< 0.2		15	69
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	0.041	16	840	1.2	< 0.048	37		< 0.17		12	69
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	0.033	16	710	1.1	< 0.046	37		< 0.17		12	58
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated	0.042	453 *E	900	1.8	< U	1270		< U		14.7	111 NE
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	0.095	17	530	< 0.42 U	< 0.18 U	< 150 U		< 0.53 U		9.9	68
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-0-2	1/22/2018	850.73	0 - 2 ft	180-74331-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-0-2	1/11/2018	853.61	0 - 2 ft	180-74124-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-0-2	1/20/2018	853.66	0 - 2 ft	180-74390-2	Excavated							< 10 U				
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	851.27	0 - 2 ft	180-74307-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-0-2	1/17/2018	850.48	0 - 2 ft	180-74241-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated							< 11 U				
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated	0.0087	19.3 *E	682	1.7	< U	110		< U		13.3	68.5 NE
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	850.31	0 - 2 ft	180-74241-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-0-2	1/16/2018	851.77	0 - 2 ft	180-74203-2	Excavated							< 11 U				
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated	0.0087	19.3 *E	682	1.7	< U	110		< U		13.3	68.5 NE
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.07 U	20.7		< 0.76 U	< 1.5 U						90.6
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	0.147	18.1		1.02	< 1.12 U			< 1.12 U	< 55.9 U	15.4	72.6
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	0.113	19.2		0.732	< 1.11 U			< 1.11 U	< 55.4 U	16.6	70.1
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.07 U	25.8		< 0.7 U	< 1.4 U						92.6
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.7 U	21.8		< 0.68 U	< 1.4 U						62.7
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.06 U	21.3		< 0.65 U	< 1.3 U						68
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	0.158	21.1		1.58	< 1.36 U			< 1.36 U	< 68.2 U	17.2	83.2
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	0.0812	21.5		1.44	< 1.42 U			< 1.42 U	< 70.8 U	17	85.6
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	0.0934	20.5		< 0.67 U	< 1.3 U			< 1.3 U	< 65.6 U	15.5	81.5
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	0.164	22.4		1.07	< 1.43 U			< 1.43 U	< 71.4 U	17.4	77
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	0.142	23.3		1.43	< 1.36 U			< 1.36 U	< 68.2 U	18.6	86.5

DRAFT

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U					
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated			0.104	< 0.0069 U	< 0.0082 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.023 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated			2.28		< U		0.1 J				0.25 J	0.22 J	0.31 J	0.12 J	0.15 J				0.57	
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated			ND	< 0.42 U	< 0.42 U		< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U					
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated			5.56	< 4.4 U	< 4.4 U		< 4.4 U				< 4.4 U	< 4.4 U	< 4.4 U	< 4.4 U	0.95 J					
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated			ND	< 0.43 U	< 0.43 U		< 0.43 U				< 0.43 U	< 0.43 U	< 0.43 U	< 0.43 U	< 0.43 U					
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated			1.803	< 0.43 U	< 0.43 U		< 0.43 U				0.14 J	0.16 J	0.17 J	0.15 J	0.14 J					
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated			5.37		< U		0.12 J				0.46	0.47	0.63	0.26 J	0.36				0.68	
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated			1.18	< 0.0011 U	0.037	< 0.015 U	0.021	< 0.05 U	< 0.024 U	0.28	0.11	0.12	0.19	0.059	0.067	< 0.017 U	< 0.017 U	< 0.014 U	0.16	< 0.019 U
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated			1.3982	< 0.001 U	0.026	< 0.015 U	0.023	< 0.048 U	< 0.023 U	0.063 J	0.13	0.13	0.22	0.052	0.054	< 0.016 U	< 0.016 U	< 0.013 U	0.29	< 0.019 U
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated			1.4527	< 0.001 U	0.03	< 0.015 U	0.023	< 0.049 U	< 0.023 U	0.069 J	0.12	0.14	0.17	0.059	0.076	< 0.016 U	< 0.016 U	< 0.014 U	0.21	< 0.019 U
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated			0.297	< 0.00099 U	< 0.00046 U	< 0.014 U	< 0.001 U	< 0.047 U	< 0.022 U	0.076 J	0.022	0.025	0.041	0.01	0.016	< 0.016 U	< 0.016 U	< 0.013 U	0.11	< 0.018 U
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated			0.299	< 0.00099 U	< 0.00046 U	0.019 J	< 0.001 U	< 0.047 U	< 0.022 U	0.13	0.019	0.026	0.045	0.014	0.021	< 0.016 U	< 0.016 U	< 0.013 U	0.44	< 0.018 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated			3.782	< 0.0022 U	0.13	< 0.032 U	0.062	< 0.11 U	< 0.05 U	< 0.067 U	0.32	0.36	0.57	0.19	0.15	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.041 U
Football Field	SSHS-B2031	FD-57	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated			0.512	0.016 J	< 0.00088 U	< 0.028 U	< 0.002 U	< 0.09 U	< 0.043 U	< 0.058 U	0.025	0.033	0.039	0.019	0.025	< 0.03 U	< 0.03 U	< 0.025 U	< 0.13 U	< 0.035 U
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated			0.2867	0.0052 J	0.0048 J	< 0.014 U	0.0045 J	< 0.046 U	< 0.022 U	0.079 J	< 0.0008 U	0.028	0.041	0.022	0.017	< 0.015 U	< 0.015 U	< 0.013 U	0.12	< 0.018 U
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	854.88	0 - 0.17 ft	180-80275-1	Excavated			0.24	< 0.00099 U	< 0.00045 U	< 0.014 U	< 0.001 U	< 0.047 U	< 0.022 U	0.04 J	0.015	0.018	0.026	0.015	0.017	< 0.016 U	< 0.016 U	< 0.013 U	0.12	< 0.018 U
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	854.70	0 - 0.17 ft	180-80275-1	Excavated			0.476	< 0.00093 U	0.022	< 0.014 U	0.024	< 0.044 U	< 0.021 U	0.037 J	0.026	0.046	0.091	0.018	0.025	< 0.015 U	< 0.015 U	< 0.012 U	0.087	< 0.017 U
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated			1.7351	< 0.0011 U	0.058	< 0.016 U	0.031	< 0.052 U	< 0.024 U	0.11 J	0.18	0.16	0.23	0.11	0.082	< 0.017 U	< 0.017 U	< 0.014 U	0.19	< 0.02 U
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated			0.588	< 0.0011 U	0.012	< 0.016 U	0.009 J	< 0.051 U	< 0.024 U	0.072 J	0.04	0.052	0.074	0.031	0.057	< 0.017 U	< 0.017 U	< 0.014 U	0.18	< 0.02 U
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated			0.318	< 0.00099 U	0.0044 J	< 0.014 U	0.0061 J	< 0.047 U	< 0.022 U	0.13	0.019	0.025	0.035	0.0089	0.022	< 0.016 U	< 0.016 U	< 0.013 U	0.081 J	< 0.018 U
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated			0.544	< 0.0011 U	0.015	< 0.016 U	0.012	< 0.051 U	< 0.024 U	0.072 J	0.046	0.044	0.08	0.021	0.023	< 0.017 U	< 0.017 U	< 0.014 U	0.25	< 0.02 U
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated			0.3298	< 0.0011 U	0.0087 J	< 0.016 U	< 0.0012 U	< 0.054 U	< 0.025 U	0.074 J	0.027	0.025	0.04	0.0088 J	0.021	< 0.018 U	< 0.018 U	< 0.015 U	0.078 J	< 0.021 U
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated			0.1482	< 0.0011 U	< 0.00051 U	< 0.016 U	< 0.0011 U	< 0.053 U	< 0.025 U	< 0.034 U	0.012	0.014	0.02	0.011	0.013	< 0.018 U	< 0.018 U	< 0.015 U	< 0.075 U	< 0.021 U
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated			1.083	< 0.0011 U	< 0.00049 U	< 0.015 U	0.02	< 0.051 U	< 0.024 U	0.034 J	0.095	0.093	0.13	0.051	0.068	< 0.017 U	< 0.017 U	< 0.014 U	< 0.072 U	< 0.02 U
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	855.40	0 - 0.17 ft	180-80225-3	Excavated			0.946	< 0.001 U	0.03	< 0.015 U	0.013	< 0.048 U	< 0.023 U	< 0.031 U	0.079	0.093	0.15	0.051	0.04	< 0.016 U	< 0.016 U	< 0.013 U	< 0.068 U	< 0.019 U
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated			1.021	< 0.0011 U	0.028	< 0.016 U	0.017	< 0.053 U	< 0.025 U	0.043 J	0.082	0.096	0.13	0.049	0.056	< 0.018 U	< 0.018 U	< 0.015 U	< 0.076 U	< 0.021 U
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated			0.3339	< 0.0011 U	0.012	< 0.016 U	0.0059 J	< 0.053 U	< 0.025 U	0.048 J	0.033	0.035	0.046	< 0.001 U	0.019	< 0.018 U	< 0.018 U	< 0.015 U	0.095 J	< 0.021 U
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated			1.063	< 0.0011 U	0.032	< 0.015 U	0.017	< 0.051 U	< 0.024 U	< 0.032 U	0.077	0.088	0.2	0.073	0.071	< 0.017 U	< 0.017 U	< 0.014 U	0.14	< 0.02 U
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated			1.013	< 0.0011 U	< 0.00052 U	< 0.016 U	0.015	< 0.054 U	< 0.025 U	< 0.034 U	0.083	0.1	0.15	0.074	0.038	< 0.018 U	< 0.018 U	< 0.015 U	< 0.076 U	< 0.021 U
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated			0.36	< 0.0014 U	< 0.00062 U	< 0.02 U	< 0.0014 U	< 0.064 U	< 0.03 U	0.07 J	0.031	0.032	0.047	0.021	< 0.00062 U	< 0.021 U	< 0.021 U	< 0.018 U	0.17	< 0.025 U
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated			0.962	< 0.001 U	0.017	< 0.015 U	0.014	< 0.048 U	< 0.022 U	0.078 J	0.079	0.091	0.13	0.053	0.035	< 0.016 U	< 0.016 U	< 0.013 U	0.25	< 0.018 U
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated			2.979	< 0.0011 U	0.059	< 0.016 U	0.12	< 0.052 U	< 0.025 U	0.24	0.23	0.25	0.4	0.098	0.13	< 0.017 U	< 0.017 U	< 0.015 U	0.34	< 0.02 U
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated			2.439	0.021	0.04	< 0.015 U	0.054	< 0.05 U	< 0.024 U	0.085 J	0.2	0.21	0.28	0.1	0.085	< 0.017 U	< 0.017 U	< 0.014 U	0.088 J	< 0.02 U
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	856.56	0 - 0.17 ft	180-80275-1	Excavated			1.8585	0.0075 J	0.042	< 0.015 U	0.029	< 0.049 U	< 0.023 U	0.067 J	0.14	0.18	0.27	0.092	0.09	< 0.016 U	< 0.016 U	< 0.014 U	0.32	< 0.019 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated			7.328	< 0.0043 U	0.17	< 0.062 U	0.21	< 0.2 U	< 0.096 U	< 0.13 U	0.64	0.54	0.87	0.29	0.26	< 0.067 U	< 0.067 U	< 0.056 U	< 0.29 U	< 0.079 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated			3.347	0.032 J	0.056	< 0.063 U	0.11	< 0.21 U	< 0.098 U	< 0.13 U	0.28	0.25	0.32	0.11	0.18	< 0.069 U	< 0.069 U	< 0.057 U	< 0.29 U	< 0.08 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated			1.736	< 0.00086 U	0.073	< 0.012 U	0.042	< 0.041 U	< 0.019 U	< 0.026 U	0.16	0.17	0.24	0.073	0.12	< 0.014 U	< 0.014 U	< 0.011 U	< 0.058 U	< 0.016 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated			3.373	< 0.0034 U	0.079	< 0.049 U	0.054	< 0.16 U	< 0.076 U	< 0.1 U	0.33	0.31	0.46	0.15	0.18	< 0.053 U	< 0.053 U	< 0.044 U	< 0.23 U	< 0.062 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated			1.668	< 0.002 U	0.049	< 0.029 U	0.024	< 0.096 U	< 0.045 U	< 0.061 U	0.14	0.17	0.3	0.1	< 0.00093 U	< 0.032 U	< 0.032 U	< 0.027 U	< 0.14 U	< 0.037 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated			1.215	< 0.00078 U	0.052	< 0.011 U	0.019	< 0.037 U	< 0.018 U	< 0.024 U	0.092	0.11	0.19	0.11	0.056	< 0.012 U	< 0.012 U	< 0.01 U	< 0.053 U	< 0.014 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated			1.761	< 0.004 U	0.029 J	< 0.058 U	0.019 J	< 0.19 U	< 0.09 U	< 0.12 U	0.11	0.25	0.38	< 0.0036 U	< 0.0018 U	< 0.063 U	< 0.063 U	< 0.053 U	< 0.27 U	< 0.074 U
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	855.49	0 - 0.17 ft	180-80275-1	Excavated			1.4865	0.012	0.038	< 0.015 U	0.03	< 0.05 U	< 0.024 U	0.092 J	0.13	0.15	0.2	0.083	0.086	< 0.017 U	< 0.017 U	< 0.014 U	0.14	< 0.02 U
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	857.04	0 - 0.17 ft	180-80105-2	Excavated			0.5158	< 0.0011 U	< 0.00049 U	< 0.016 U	0.0088 J	< 0.051 U	< 0.024 U	< 0.032 U	0.043	0.045	0.063	0.027	0.038	< 0.017 U	< 0.017 U	< 0.014 U	< 0.072 U	< 0.02 U
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated			0.5261	< 0.0011 U	0.016	< 0.016 U	0.0091 J	< 0.053 U	< 0.025 U	< 0.034 U	0.042	0.047	0.069	0.029	0.049	< 0.018 U	< 0.018 U	< 0.015 U	< 0.075 U	< 0.021 U
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated			0.629	< 0.0011 U	0.019	< 0.016 U	0.011	< 0.052 U	< 0.025 U	0.052 J	0.052	0.062	0.094	0.038	0.031	< 0.017 U	< 0.017 U	< 0.014 U	< 0.074 U	< 0.02 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated			3.163	0.017	0.072	< 0.025 U	0.072	< 0.08 U	< 0.038 U	< 0.051 U	0.28	0.25	0.42	0.12	0.15	< 0.027 U	< 0.027 U	< 0.022 U	< 0.11 U	< 0.031 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated			3.517	0.021	0.084	< 0.032 U	0.088	< 0.1 U	< 0.049 U	< 0.067 U	0.31	0.27	0.43	0.14	0.17	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.041 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated			10.331	0.081	0.059	< 0.05 U	0.29	< 0.16 U	< 0.077 U	< 0.1 U	0.96	0.92	1.3	0.59	0.38	< 0.054 U	< 0.054 U	< 0.045 U	< 0.23 U	< 0.063 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated			0.66	< 0.017 U	< 0.0076 U	< 0.24 U	< 0.017 U	< 0.79 U	< 0.37 U	< 0.5 U	< 0.014 U	< 0.014 U	< 0.013 U	< 0.015 U	< 0.0076 U	< 0.26 U	< 0.26 U	< 0.22 U	< 1.1 U	< 0.31 U
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated			1.06	< 0.0011 U	0.027	< 0.016 U	0.018	< 0.051 U	< 0.024 U	< 0.033 U	0.078	0.09	0.13	0.045	0.096	< 0.017 U	< 0.017 U	< 0.014 U	< 0.072 U	< 0.02 U
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated			6.553	< 0.001 U	0.22	0.055 J	0.11	< 0.049 U	0.043 J	0.13 J	0.45	0.59	1	0.44	0.29	< 0.016 U	< 0.016 U	< 0.014 U	0.31	< 0.019 U
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated			2.188	< 0.0012 U	0.052	< 0.017 U	0.043	< 0.057 U	< 0.027 U	< 0.037 U	0.16	0.19	0.27	0.13	0.095	< 0.019 U	< 0.019 U	< 0.016 U	< 0.081 U	< 0.022 U
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	855.38	0 - 0.17 ft	180-80157-2	Excavated			1.86	0.026	0.011	< 0.016 U	0.076	< 0.054 U	< 0.025 U	0.053 J	0.16	0.12	0.17	0.055	0.085	< 0.018 U	< 0.018 U	< 0.015 U	< 0.076 U	< 0.021 U
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	855.74	0 - 0.17 ft	180-80157-2	Excavated			0.599	< 0.0012 U	0.015	< 0.017 U	0.013	< 0.055 U	< 0.026 U	< 0.035 U	0.054	0.05	0.077	0.022	0.045	< 0.018 U	< 0.018 U	< 0.015 U	< 0.078 U	< 0.021 U
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	856.38	0 - 0.17 ft	180-80157-2	Excavated			0.4191	< 0.0014 U	0.0084 J	< 0.02 U	0.0091 J	< 0.066 U	< 0.031 U	< 0.042 U	0.037	0.035	0.051	0.017	0.029	< 0.022 U	< 0.022 U	< 0.018 U	< 0.094 U	< 0.026 U
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	854.93	0 - 0.17 ft	180-80157-2	Excavated			0.7215	< 0.0013 U	0.0067 J	0.072 J	0.0095 J	< 0.062 U	< 0.029 U	0.078 J	0.042	0.056	0.11	0.038	0.094	< 0.021 U	< 0.021 U	< 0.017 U	0.52	< 0.024 U
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	857.03	0 - 0.17 ft	180-80157-2	Excavated			0.4378	< 0.0011 U	0.013	< 0.015 U	0.0095	< 0.05 U	< 0.024 U	0.053 J	0.039	0.035	0.061	0.014	0.037	< 0.017 U	< 0.017 U	< 0.014 U	< 0.071 U	< 0.02 U
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	856.56	0 - 0.17 ft	180-80157-2	Excavated			1.484	< 0.0011 U	0.039	< 0.017 U	0.024	< 0.054 U	< 0.026 U	0.041 J	0.14	0.11	0.18	0.059	0.091	< 0.018 U	< 0.018 U	< 0.015 U	< 0.077 U	< 0.021 U
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	855.33	0 - 0.17 ft	180-80106-3	Excavated			1.0042	< 0.0014 U	< 0.00065 U	0.031 J	0.0082 J	< 0.067 U	< 0.032 U	< 0.043 U	0.076	0.084	0.16	0.046	0.069	< 0.022 U	< 0.022 U	< 0.019 U	0.31	< 0.026 U
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	855.28	0 - 0.17 ft	180-80275-1	Excavated			0.5595	< 0.00089 U	0.0084	< 0.013 U	0.012	< 0.042 U	< 0.02 U	< 0.027 U	0.047	0.049	0.063	0.024	0.033	< 0.014 U	< 0.014 U	< 0.012 U	0.11	< 0.016 U
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	856.14	0 - 0.17 ft	180-80106-3	Excavated			3.503	0.018	0.036	< 0.013 U	0.11	< 0.041 U	< 0.019 U	< 0.026 U	0.36	0.26	0.33	0.15	0.13	< 0.014 U	< 0.014 U	< 0.011 U	0.059 J	< 0.016 U
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	856.82	0 - 0.17 ft	180-80157-2	Excavated			0.4319	< 0.0011 U	0.01	< 0.016 U	0.011	< 0.053 U	< 0.025 U	0.039 J	0.038	0.033	0.049	0.025	0.03	< 0.018 U	< 0.018 U	< 0.015 U	< 0.075 U	< 0.021 U
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	854.83	0 - 0.17 ft	180-80275-1	Excavated			1.108	< 0.0011 U	0.03	0.026 J	0.013	< 0.051 U	< 0.024 U	0.2	0.086	0.11	0.18	0.05	0.056	< 0.017 U	< 0.017 U	< 0.014 U	0.37	< 0.02 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	855.41	0 - 0.17 ft	180-80091-4	Excavated			2.727	0.052	0.011	< 0.013 U	0.14	< 0.042 U	< 0.02 U	< 0.027 U	0.22	0.18	0.22	0.084	0.092	< 0.014 U	< 0.014 U	< 0.012 U	< 0.06 U	< 0.016 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	855.30	0 - 0.17 ft	180-80091-4	Excavated			0.3326	< 0.00087 U	0.0054 J	< 0.013 U	0.005 J	< 0.041 U	< 0.019 U	< 0.026 U	0.026	0.031	0.042	0.019	0.02	< 0.014 U	< 0.014 U	< 0.011 U	< 0.058 U	< 0.016 U
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	855.25	0 - 0.17 ft	180-80157-3	Excavated			0.292	< 0.00099 U	< 0.00046 U	< 0.014 U	< 0.001 U	< 0.047 U	< 0.022 U	< 0.03 U	0.026	0.026	0.037	0.012	0.023	< 0.016 U	< 0.016 U	< 0.013 U	0.094	< 0.018 U
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	855.30	0 - 0.17 ft	180-80106-3	Excavated			0.6281	< 0.0017 U	< 0.00079 U	0.03 J	0.0081 J	< 0.081 U	< 0.038 U	< 0.052 U	0.046	0.047	0.084	0.036	0.072	< 0.027 U	< 0.027 U	< 0.023 U	0.61	< 0.032 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	855.07	0 - 0.17 ft	180-80091-4	Excavated			0.9861	< 0.00089 U	0.014	< 0.013 U	0.017	< 0.042 U	< 0.02 U	< 0.027 U	0.082	0.096	0.12	0.04	0.059	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated			0.0771	< 0.00086 U	< 0.0004 U	< 0.012 U	< 0.00088 U	< 0.041 U	< 0.019 U	0.029 J	0.0081	< 0.00072 U	0.015	< 0.00077 U	0.016	< 0.014 U	< 0.014 U	< 0.011 U	< 0.058 U	< 0.016 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated			1.286	< 0.00087 U	0.026	< 0.013 U	0.035	< 0.041 U	0.031 J	< 0.026 U	0.077	0.089	0.17	0.06	0.041	< 0.014 U	< 0.014 U	< 0.011 U	0.15	< 0.016 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated			1.268	< 0.0018 U	0.026	< 0.026 U	0.033	< 0.084 U	< 0.039 U	< 0.053 U	0.088	0.12	0.17	0.094	< 0.00081 U	< 0.028 U	< 0.028 U	< 0.023 U	0.13 J	< 0.032 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated			2.64		0.092 J		0.11 J				0.21 J	0.29 J	0.47	0.18 J	0.23 J				0.53	
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated			3.9	< 0.025 U	0.15	< 0.023 U	0.1	< 0.19 U	< 0.018 U	< 0.053 U	0.34	0.33	0.47	0.24	0.3	< 0.02 U	< 0.016 U	< 0.032 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated			4.87	< 0.025 U	0.23	< 0.023 U	0.14	< 0.19 U	< 0.018 U		0.47	0.49	0.74	0.18	0.37	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U

DRAFT

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Butylbenzyl phthalate	**Caprolactam**	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**	**3,3-Dichlorobenzidine**	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B10	B10 10 May 00 0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated									< 0.47 U	< 0.47 U	< 0.47 U								
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.049 U	< 0.27 U	< 0.0066 U	< 0.029 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.04 U	< 0.0085 U	< 0.0079 U	< 0.035 U	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated									0.22 J										
Northern Athletic Field	SSHS-B12	B12 10 May 00 0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated									< 0.42 U	< 0.42 U	< 0.42 U								
Northern Athletic Field	SSHS-B13	B13 10 May 00 0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated									0.46 J	< 4.4 U	0.66 J								
Northern Athletic Field	SSHS-B14	B14 10 May 00 0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated									< 0.43 U	< 0.43 U	< 0.43 U								
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated									0.2 J	0.043 J	< 0.43 U								
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated									0.44										
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated	< 0.031 U	< 0.1 U	< 0.026 U	< 0.042 U	< 0.063 U	< 0.019 U	< 0.014 U	< 0.019 U	0.11	0.025	0.022 J	< 0.06 U	< 0.061 U	< 0.043 U	< 0.056 U	< 0.019 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated	< 0.029 U	< 0.1 U	< 0.025 U	< 0.04 U	< 0.06 U	< 0.019 U	< 0.013 U	< 0.019 U	0.14	< 0.00088 U	< 0.017 U	< 0.058 U	< 0.059 U	< 0.041 U	< 0.054 U	< 0.019 U	< 0.029 U	< 0.037 U	< 0.11 U
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated	< 0.03 U	< 0.1 U	< 0.026 U	< 0.041 U	< 0.061 U	< 0.019 U	< 0.014 U	< 0.019 U	0.16	0.025	0.018 J	< 0.058 U	< 0.06 U	< 0.042 U	< 0.054 U	< 0.019 U	< 0.03 U	< 0.038 U	< 0.11 U
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated	< 0.029 U	< 0.098 U	< 0.025 U	< 0.039 U	< 0.059 U	< 0.018 U	< 0.013 U	< 0.018 U	0.031	< 0.00086 U	< 0.017 U	< 0.056 U	< 0.058 U	< 0.041 U	< 0.052 U	< 0.018 U	< 0.029 U	< 0.037 U	< 0.1 U
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated	< 0.029 U	< 0.098 U	< 0.025 U	< 0.039 U	< 0.059 U	< 0.018 U	< 0.013 U	< 0.018 U	0.032	< 0.00086 U	< 0.017 U	< 0.056 U	< 0.058 U	< 0.041 U	< 0.052 U	< 0.018 U	< 0.029 U	< 0.037 U	< 0.1 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.065 U	< 0.22 U	< 0.056 U	< 0.088 U	< 0.13 U	< 0.041 U	< 0.029 U	< 0.041 U	0.44	< 0.0019 U	< 0.038 U	< 0.13 U	< 0.13 U	< 0.091 U	< 0.12 U	< 0.041 U	< 0.065 U	< 0.082 U	< 0.23 U
Football Field	SSHS-B2031	FD-57	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	< 0.055 U	< 0.19 U	< 0.048 U	< 0.075 U	< 0.11 U	< 0.035 U	< 0.025 U	< 0.035 U	0.043	< 0.0017 U	< 0.033 U	< 0.11 U	< 0.11 U	< 0.078 U	< 0.1 U	< 0.035 U	< 0.055 U	< 0.07 U	< 0.2 U
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	< 0.028 U	< 0.095 U	< 0.024 U	< 0.038 U	< 0.057 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.0014 U	< 0.00084 U	< 0.016 U	< 0.055 U	< 0.056 U	< 0.039 U	< 0.051 U	< 0.018 U	< 0.028 U	< 0.036 U	< 0.1 U
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	854.88	0 - 0.17 ft	180-80275-1	Excavated	< 0.029 U	< 0.097 U	< 0.025 U	< 0.039 U	< 0.058 U	< 0.018 U	< 0.013 U	< 0.018 U	0.02	< 0.00086 U	< 0.017 U	< 0.056 U	< 0.057 U	< 0.04 U	< 0.052 U	< 0.018 U	0.038 J	< 0.036 U	< 0.1 U
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	854.70	0 - 0.17 ft	180-80275-1	Excavated	< 0.027 U	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.045	< 0.00081 U	< 0.016 U	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated	< 0.032 U	< 0.11 U	< 0.027 U	< 0.043 U	< 0.065 U	< 0.02 U	< 0.014 U	< 0.02 U	0.18	0.025	< 0.019 U	< 0.062 U	< 0.063 U	< 0.044 U	< 0.057 U	< 0.02 U	< 0.032 U	< 0.04 U	< 0.11 U
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.042 U	< 0.064 U	< 0.02 U	< 0.014 U	< 0.02 U	0.052	< 0.00093 U	< 0.018 U	< 0.061 U	< 0.062 U	< 0.044 U	< 0.057 U	< 0.02 U	0.046 J	< 0.04 U	< 0.11 U
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated	< 0.029 U	< 0.098 U	< 0.025 U	< 0.039 U	< 0.059 U	< 0.018 U	< 0.013 U	< 0.018 U	0.027	< 0.00086 U	< 0.017 U	< 0.056 U	< 0.058 U	< 0.041 U	< 0.052 U	< 0.018 U	< 0.029 U	< 0.037 U	< 0.1 U
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.043 U	< 0.064 U	< 0.02 U	< 0.014 U	< 0.02 U	0.049	< 0.00094 U	< 0.019 U	< 0.061 U	< 0.063 U	< 0.044 U	< 0.057 U	< 0.02 U	< 0.031 U	< 0.04 U	< 0.11 U
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated	< 0.033 U	< 0.11 U	< 0.028 U	< 0.045 U	< 0.067 U	< 0.021 U	< 0.015 U	< 0.021 U	0.039	< 0.00098 U	< 0.019 U	< 0.064 U	< 0.066 U	< 0.046 U	< 0.06 U	< 0.021 U	< 0.033 U	< 0.042 U	< 0.12 U
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated	< 0.032 U	< 0.11 U	< 0.028 U	< 0.044 U	< 0.066 U	< 0.021 U	< 0.015 U	< 0.021 U	0.014	< 0.00097 U	< 0.019 U	< 0.063 U	< 0.064 U	< 0.045 U	< 0.059 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.12 U
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.042 U	< 0.063 U	< 0.02 U	< 0.014 U	< 0.02 U	0.11	0.024	< 0.018 U	< 0.061 U	< 0.062 U	< 0.044 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	855.40	0 - 0.17 ft	180-80225-3	Excavated	< 0.029 U	< 0.1 U	< 0.025 U	< 0.04 U	< 0.06 U	< 0.019 U	< 0.013 U	< 0.019 U	0.085	< 0.00088 U	< 0.017 U	< 0.058 U	< 0.059 U	< 0.041 U	< 0.054 U	< 0.019 U	< 0.029 U	< 0.037 U	< 0.11 U
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated	< 0.033 U	< 0.11 U	< 0.028 U	< 0.045 U	< 0.067 U	< 0.021 U	< 0.015 U	< 0.021 U	0.094	0.015	0.023 J	< 0.064 U	< 0.065 U	< 0.046 U	< 0.059 U	< 0.021 U	< 0.033 U	< 0.042 U	< 0.12 U
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated	< 0.032 U	< 0.11 U	< 0.028 U	< 0.044 U	< 0.066 U	< 0.021 U	< 0.015 U	< 0.021 U	0.037	< 0.00097 U	< 0.019 U	< 0.063 U	< 0.065 U	< 0.046 U	< 0.059 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.12 U
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.042 U	< 0.063 U	< 0.02 U	< 0.014 U	< 0.02 U	0.1	< 0.00093 U	< 0.018 U	< 0.06 U	< 0.062 U	< 0.044 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated	< 0.033 U	< 0.11 U	< 0.028 U	< 0.045 U	< 0.067 U	< 0.021 U	< 0.015 U	< 0.021 U	0.1	< 0.00099 U	< 0.019 U	< 0.064 U	< 0.066 U	< 0.046 U	< 0.06 U	< 0.021 U	< 0.033 U	< 0.042 U	< 0.12 U
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated	< 0.039 U	< 0.13 U	< 0.034 U	< 0.053 U	< 0.08 U	< 0.025 U	< 0.018 U	< 0.025 U	0.043	< 0.0012 U	< 0.023 U	< 0.077 U	< 0.078 U	< 0.055 U	< 0.071 U	< 0.025 U	< 0.039 U	< 0.05 U	< 0.14 U
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated	< 0.029 U	< 0.099 U	< 0.025 U	< 0.04 U	< 0.059 U	< 0.018 U	< 0.013 U	< 0.018 U	0.095	< 0.00087 U	< 0.017 U	< 0.057 U	< 0.058 U	< 0.041 U	< 0.053 U	< 0.018 U	< 0.029 U	< 0.037 U	< 0.11 U
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated	< 0.032 U	< 0.11 U	0.04 J	< 0.044 U	< 0.066 U	< 0.02 U	< 0.015 U	< 0.02 U	0.26	0.038	0.043 J	< 0.063 U	< 0.064 U	< 0.045 U	< 0.058 U	< 0.02 U	< 0.032 U	< 0.041 U	< 0.12 U
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated	< 0.031 U	< 0.1 U	< 0.026 U	< 0.042 U	< 0.063 U	< 0.02 U	< 0.014 U	< 0.02 U	0.21	0.022	0.048 J	< 0.06 U	< 0.061 U	< 0.043 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	856.56	0 - 0.17 ft	180-80275-1	Excavated	< 0.03 U	< 0.1 U	< 0.026 U	< 0.041 U	< 0.061 U	< 0.019 U	< 0.014 U	< 0.019 U	0.17	0.018	0.034 J	< 0.058 U	< 0.059 U	< 0.042 U	< 0.054 U	< 0.019 U	< 0.03 U	< 0.038 U	< 0.11 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.12 U	< 0.42 U	< 0.11 U	< 0.17 U	< 0.25 U	< 0.079 U	< 0.056 U	< 0.079 U	0.7	0.11	0.1 J	< 0.24 U	< 0.25 U	< 0.17 U	< 0.22 U	< 0.079 U	< 0.12 U	< 0.16 U	< 0.45 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.13 U	< 0.43 U	< 0.11 U	< 0.17 U	< 0.26 U	< 0.08 U	< 0.057 U	< 0.08 U	0.37	< 0.0038 U	< 0.075 U	< 0.25 U	< 0.25 U	< 0.18 U	< 0.23 U	< 0.08 U	< 0.13 U	< 0.16 U	< 0.46 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.025 U	< 0.085 U	< 0.021 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.18	0.036	0.015 J	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.098 U	< 0.33 U	< 0.085 U	< 0.13 U	< 0.2 U	< 0.062 U	< 0.044 U	< 0.062 U	0.41	0.065	< 0.058 U	< 0.19 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.062 U	< 0.098 U	< 0.12 U	< 0.36 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.059 U	< 0.2 U	< 0.051 U	< 0.08 U	< 0.12 U	< 0.037 U	< 0.027 U	< 0.037 U	0.25	< 0.0018 U	< 0.035 U	< 0.11 U	< 0.12 U	< 0.083 U	< 0.11 U	< 0.037 U	< 0.059 U	< 0.075 U	< 0.21 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.023 U	< 0.077 U	< 0.02 U	< 0.031 U	< 0.046 U	< 0.014 U	< 0.01 U	< 0.014 U	0.17	< 0.00068 U	< 0.013 U	< 0.044 U	< 0.045 U	< 0.032 U	< 0.041 U	< 0.014 U	< 0.023 U	< 0.029 U	< 0.083 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.12 U	< 0.4 U	< 0.1 U	< 0.16 U	< 0.24 U	< 0.074 U	< 0.053 U	< 0.074 U	0.28	< 0.0035 U	< 0.069 U	< 0.23 U	< 0.23 U	< 0.16 U	< 0.21 U	< 0.074 U	< 0.12 U	< 0.15 U	< 0.42 U
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	855.49	0 - 0.17 ft	180-80275-1	Excavated	< 0.031 U	< 0.1 U	< 0.027 U	< 0.042 U	< 0.063 U	< 0.02 U	< 0.014 U	< 0.02 U	0.14	0.03	0.018 J	< 0.06 U	< 0.062 U	< 0.043 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	857.04	0 - 0.17 ft	180-80105-2	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.042 U	< 0.063 U	< 0.02 U	< 0.014 U	< 0.02 U	0.047	< 0.00093 U	< 0.018 U	< 0.061 U	< 0.062 U	< 0.044 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated	< 0.033 U	< 0.11 U	< 0.028 U	< 0.044 U	< 0.067 U	< 0.021 U	< 0.015 U	< 0.021 U	0.048	< 0.00098 U	< 0.019 U	< 0.064 U	< 0.065 U	< 0.046 U	< 0.059 U	< 0.021 U	< 0.033 U	< 0.041 U	< 0.12 U
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated	< 0.032 U	< 0.11 U	< 0.027 U	< 0.043 U	< 0.065 U	< 0.02 U	< 0.014 U	< 0.02 U	0.067	< 0.00095 U	< 0.019 U	< 0.062 U	< 0.064 U	< 0.045 U	< 0.058 U	< 0.02 U	< 0.032 U	< 0.04 U	< 0.12 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.049 U	< 0.17 U	< 0.042 U	< 0.067 U	< 0.1 U	< 0.031 U	< 0.022 U	< 0.031 U	0.35	0.057	0.053 J	< 0.096 U	< 0.098 U	< 0.069 U	< 0.089 U	< 0.031 U	< 0.049 U	< 0.063 U	< 0.18 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.064 U	< 0.22 U	< 0.055 U	< 0.087 U	< 0.13 U	< 0.041 U	< 0.029 U	< 0.041 U	0.37	0.055	0.066 J	< 0.12 U	< 0.13 U	< 0.09 U	< 0.12 U	< 0.041 U	< 0.064 U	< 0.081 U	< 0.23 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.099 U	< 0.34 U	0.098 J	< 0.14 U	< 0.2 U	< 0.063 U	< 0.045 U	< 0.063 U	0.99	< 0.003 U	0.094 J	< 0.19 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.063 U	< 0.099 U	< 0.13 U	< 0.36 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.48 U	< 1.6 U	< 0.41 U	< 0.65 U	< 0.98 U	< 0.31 U	< 0.22 U	< 0.31 U	0.29	< 0.014 U	< 0.28 U	< 0.94 U	< 0.96 U	< 0.68 U	< 0.87 U	< 0.31 U	< 0.48 U	< 0.61 U	< 1.7 U
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.042 U	< 0.064 U	< 0.02 U	< 0.014 U	< 0.02 U	0.085	< 0.00093 U	< 0.018 U	< 0.061 U	< 0.062 U	< 0.044 U	< 0.057 U	< 0.02 U	< 0.031 U	< 0.04 U	< 0.11 U
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated	0.046 J	< 0.1 U	0.078	< 0.041 U	< 0.061 U	< 0.019 U	< 0.014 U	< 0.019 U	0.55	0.068	0.093	< 0.058 U	< 0.06 U	< 0.042 U	< 0.054 U	< 0.019 U	< 0.03 U	< 0.038 U	< 0.11 U
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated	< 0.035 U	< 0.12 U	< 0.03 U	< 0.048 U	< 0.071 U	< 0.022 U	< 0.016 U	< 0.022 U	0.19	< 0.001 U	0.03 J	< 0.068 U	< 0.07 U	< 0.049 U	< 0.064 U	< 0.022 U	< 0.035 U	< 0.044 U	< 0.13 U
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	855.38	0 - 0.17 ft	180-80157-2	Excavated	< 0.033 U	< 0.11 U	0.029 J	< 0.045 U	< 0.067 U	< 0.021 U	< 0.015 U	< 0.021 U	0.16	0.023	0.024 J	< 0.064 U	< 0.066 U	< 0.046 U	< 0.06 U	< 0.021 U	< 0.033 U	< 0.042 U	< 0.12 U
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	855.74	0 - 0.17 ft	180-80157-2	Excavated	< 0.034 U	< 0.11 U	< 0.029 U	< 0.046 U	< 0.069 U	< 0.021 U	< 0.015 U	< 0.021 U	0.062	0.011	< 0.02 U	< 0.066 U	< 0.067 U	< 0.047 U	< 0.061 U	< 0.021 U	< 0.034 U	< 0.043 U	< 0.12 U
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	856.38	0 - 0.17 ft	180-80157-2	Excavated	< 0.04 U	< 0.14 U	< 0.035 U	< 0.055 U	< 0.083 U	< 0.026 U	< 0.018 U	< 0.026 U	0.046	< 0.0012 U	< 0.024 U	< 0.079 U	< 0.081 U	< 0.057 U	< 0.074 U	< 0.026 U	< 0.04 U	< 0.051 U	< 0.15 U
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	854.93	0 - 0.17 ft	180-80157-2	Excavated	0.054 J	< 0.13 U	< 0.033 U	< 0.052 U	< 0.078 U	< 0.024 U	< 0.017 U	< 0.024 U	0.085	< 0.0011 U	< 0.022 U	< 0.074 U	< 0.076 U	< 0.054 U	< 0.069 U	< 0.024 U	< 0.038 U	< 0.048 U	< 0.14 U
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	857.03	0 - 0.17 ft	180-80157-2	Excavated	< 0.031 U	< 0.1 U	< 0.027 U	< 0.042 U	< 0.063 U	< 0.02 U	< 0.014 U	< 0.02 U	0.044	0.0093	< 0.018 U	< 0.06 U	< 0.061 U	< 0.043 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.039 U	< 0.11 U
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	856.56	0 - 0.17 ft	180-80157-2	Excavated	< 0.033 U	< 0.11 U	< 0.029 U	< 0.045 U	< 0.068 U	< 0.021 U	< 0.015 U	< 0.021 U	0.16	0.027	0.02 J	< 0.065 U	< 0.066 U	< 0.047 U	< 0.06 U	< 0.021 U	< 0.033 U	< 0.042 U	< 0.12 U
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	855.33	0 - 0.17 ft	180-80106-3	Excavated	< 0.041 U	< 0.14 U	< 0.036 U	< 0.056 U	< 0.084 U	< 0.026 U	< 0.019 U	< 0.026 U	0.12	0.016	< 0.024 U	< 0.08 U	< 0.082 U	< 0.058 U	< 0.075 U	< 0.026 U	< 0.041 U	< 0.052 U	< 0.15 U
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	855.28	0 - 0.17 ft	180-80275-1	Excavated	< 0.026 U	< 0.088 U	< 0.022 U	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.054	0.0095	< 0.015 U	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.094 U
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	856.14	0 - 0.17 ft	180-80106-3	Excavated	< 0.025 U	< 0.085 U	< 0.022 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.31	0.039	< 0.015 U	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	856.82	0 - 0.17 ft	180-80157-2	Excavated	< 0.032 U	< 0.11 U	< 0.028 U	< 0.044 U	< 0.066 U	< 0.021 U	< 0.015 U	< 0.021 U	0.044	< 0.00097 U	< 0.019 U	< 0.063 U	< 0.065 U	< 0.046 U	< 0.059 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.12 U
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	854.83	0 - 0.17 ft	180-80275-1	Excavated	< 0.031 U	< 0.11 U	< 0.027 U	< 0.042 U	< 0.064 U	< 0.02 U	< 0.014 U	< 0.02 U	0.11	< 0.00093 U	< 0.018 U	< 0.061 U	< 0.062 U	< 0.044 U	< 0.056 U	< 0.02 U	< 0.031 U	< 0.04 U	< 0.11 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	855.41	0 - 0.17 ft	180-80091-4	Excavated	< 0.026 U	< 0.088 U	0.079	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.21	0.031	0.054 J	< 0.05 U	< 0.052 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.094 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	855.30	0 - 0.17 ft	180-80091-4	Excavated	< 0.025 U	< 0.086 U	< 0.022 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.028	0.0076	< 0.015 U	< 0.049 U	< 0.05 U	< 0.035 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	855.25	0 - 0.17 ft	180-80157-3	Excavated	< 0.029 U	< 0.098 U	< 0.025 U	< 0.039 U	< 0.059 U	< 0.018 U	< 0.013 U	< 0.018 U	0.034	< 0.00086 U	< 0.017 U	< 0.056 U	< 0.057 U	< 0.04 U	< 0.052 U	< 0.018 U	< 0.029 U	< 0.036 U	< 0.1 U
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	855.30	0 - 0.17 ft	180-80106-3	Excavated	< 0.05 U	< 0.17 U	< 0.043 U	< 0.068 U	< 0.1 U	< 0.032 U	< 0.023 U	< 0.032 U	0.072	< 0.0015 U	< 0.029 U	< 0.097 U	< 0.099 U	< 0.07 U	< 0.09 U	< 0.032 U	< 0.05 U	< 0.063 U	< 0.18 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	855.07	0 - 0.17 ft	180-80091-4	Excavated	< 0.026 U	< 0.087 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.095	0.017	< 0.015 U	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.093 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.025 U	< 0.085 U	< 0.022 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.013	< 0.00075 U	< 0.015 U	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.025 U	< 0.086 U	< 0.022 U	< 0.034 U	< 0.052 U	< 0.016 U	< 0.011 U	< 0.016 U	0.14	< 0.00076 U	0.034 J	< 0.049 U	< 0.05 U	< 0.036 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.051 U	< 0.17 U	< 0.044 U	< 0.07 U	< 0.1 U	< 0.032 U	< 0.023 U	< 0.032 U	0.13	< 0.0015 U	< 0.03 U	< 0.1 U	< 0.1 U	< 0.072 U	< 0.093 U	< 0.032 U	< 0.051 U	< 0.065 U	< 0.19 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated									0.25 J										
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated	< 0.29 U	< 0.28 U	0.033 J	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.4	0.06 J	0.02 J	< 0.4 UJ	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated	< 0.3 U	< 0.28 U	0.026 J	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.56	0.12	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated							< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.037 U	< 0.42 U	< 0.029 U			< 0.041 U	0.028 J	< 0.0094 U	< 0.0076 U	< 0.008 U	< 0.038 U	< 0.026 U	< 0.0074 U	< 0.025 U		< 0.027 U	0.029 J	< 0.035 U	0.018 J
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated							0.46						0.14 J						
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated							< 0.42 U	< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated							0.49 J	< 4.4 U	< 4.4 U				< 4.4 U	< 4.4 U				< 4.4 U	1.8 J
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated							< 0.43 U	< 0.43 U	< 0.43 U				< 0.43 U	< 0.43 U				< 0.43 U	< 0.43 U
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated							0.28 J	< 0.43 U	< 0.43 U				0.12 J	< 0.43 U				< 0.43 U	< 0.43 U
EHS Building	SSHS-B15S	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated							1						0.31 J						
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated	< 0.078 U	< 0.2 U	< 0.086 U			< 0.021 U	0.17	< 0.00074 U	< 0.0029 U	< 0.017 U	< 0.086 U	< 0.013 U	0.063	< 0.043 U	< 0.04 U	< 0.017 U	0.014		0.053
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated	< 0.075 U	< 0.19 U	< 0.083 U			< 0.02 U	0.24	0.0082 J	< 0.0028 U	< 0.016 U	< 0.083 U	< 0.012 U	0.053	< 0.041 U	< 0.039 U	< 0.016 U	0.02		0.048
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated	< 0.076 U	< 0.19 U	< 0.084 U			< 0.02 U	0.24	0.0077 J	< 0.0028 U	< 0.016 U	< 0.084 U	< 0.012 U	0.069	< 0.042 U	< 0.039 U	< 0.016 U	0.022		0.059
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated	< 0.073 U	< 0.19 U	< 0.081 U			< 0.02 U	0.047	< 0.00069 U	< 0.0027 U	< 0.016 U	< 0.081 U	< 0.012 U	0.012	< 0.041 U	< 0.038 U	< 0.016 U	0.0098		0.034
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated	< 0.073 U	< 0.19 U	< 0.081 U			< 0.02 U	0.045	< 0.00069 U	< 0.0027 U	< 0.016 U	< 0.081 U	< 0.012 U	0.015	< 0.041 U	< 0.038 U	< 0.016 U	0.008 J		0.028
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.16 U	< 0.42 U	< 0.18 U			< 0.044 U	0.5	0.03	< 0.0062 U	< 0.035 U	< 0.18 U	< 0.026 U	0.11	< 0.091 U	< 0.085 U	< 0.035 U	0.15		0.25
Football Field	SSHS-B2031	FD-57	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	< 0.14 U	< 0.36 U	< 0.16 U			< 0.038 U	0.06	< 0.0013 U	< 0.0053 U	< 0.03 U	< 0.16 U	< 0.023 U	0.021	< 0.078 U	< 0.073 U	< 0.03 U	0.039		0.15
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	< 0.071 U	< 0.18 U	< 0.079 U			< 0.019 U	0.044	< 0.00067 U	< 0.0027 U	< 0.015 U	< 0.079 U	< 0.011 U	0.016	< 0.039 U	< 0.037 U	< 0.015 U	0.017		0.056
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	854.88	0 - 0.17 ft	180-80275-1	Excavated	< 0.073 U	< 0.18 U	< 0.08 U			< 0.019 U	0.035	< 0.00069 U	< 0.0027 U	< 0.016 U	< 0.08 U	< 0.012 U	0.014	< 0.04 U	< 0.038 U	< 0.016 U	0.012		0.039
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	854.70	0 - 0.17 ft	180-80275-1	Excavated	< 0.069 U	< 0.17 U	< 0.076 U			< 0.018 U	0.057	< 0.00065 U	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.027	< 0.038 U	< 0.036 U	< 0.015 U	0.017		0.05
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated	< 0.08 U	< 0.2 U	< 0.089 U			< 0.022 U	0.28	0.0061 J	< 0.003 U	< 0.017 U	< 0.089 U	< 0.013 U	0.078	< 0.044 U	< 0.042 U	< 0.017 U	0.026		0.083
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated	< 0.079 U	< 0.2 U	< 0.088 U			< 0.021 U	0.069	< 0.00075 U	< 0.003 U	< 0.017 U	< 0.088 U	< 0.013 U	0.044	< 0.044 U	< 0.041 U	< 0.017 U	0.018		0.062
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated	< 0.073 U	< 0.19 U	< 0.081 U			< 0.02 U	0.046	< 0.00069 U	< 0.0027 U	< 0.016 U	< 0.081 U	< 0.012 U	0.016	< 0.041 U	< 0.038 U	< 0.016 U	0.015		0.053
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated	< 0.08 U	< 0.2 U	< 0.088 U			< 0.021 U	0.083	< 0.00076 U	< 0.003 U	< 0.017 U	< 0.088 U	< 0.013 U	0.021	< 0.044 U	< 0.041 U	< 0.017 U	0.018		0.067
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated	< 0.084 U	< 0.21 U	< 0.092 U			< 0.022 U	0.054	< 0.00079 U	< 0.0031 U	< 0.018 U	< 0.092 U	< 0.013 U	0.021	< 0.046 U	< 0.043 U	< 0.018 U	0.0075 J		0.016
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated	< 0.082 U	< 0.21 U	< 0.091 U			< 0.022 U	0.024	< 0.00078 U	< 0.0031 U	< 0.018 U	< 0.091 U	< 0.013 U	0.0095 J	< 0.045 U	< 0.042 U	< 0.018 U	< 0.00073 U		< 0.0012 U
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated	< 0.079 U	< 0.2 U	< 0.087 U			< 0.021 U	0.16	0.007 J	< 0.003 U	< 0.017 U	< 0.087 U	< 0.013 U	0.058	< 0.044 U	< 0.041 U	< 0.017 U	0.022		0.026
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	855.40	0 - 0.17 ft	180-80225-3	Excavated	< 0.075 U	< 0.19 U	< 0.083 U			< 0.02 U	0.17	< 0.00071 U	< 0.0028 U	< 0.016 U	< 0.083 U	< 0.012 U	0.043	< 0.041 U	< 0.039 U	< 0.016 U	0.022		0.072
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated	< 0.083 U	< 0.21 U	< 0.092 U			< 0.022 U	0.17	< 0.00079 U	< 0.0031 U	< 0.018 U	< 0.092 U	< 0.013 U	0.056	< 0.046 U	< 0.043 U	< 0.018 U	0.026		0.062
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated	< 0.083 U	< 0.21 U	< 0.091 U			< 0.022 U	0.068	< 0.00078 U	< 0.0031 U	< 0.018 U	< 0.091 U	< 0.013 U	< 0.00052 U	< 0.046 U	< 0.043 U	< 0.018 U	< 0.00074 U		0.02
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated	< 0.079 U	< 0.2 U	< 0.087 U			< 0.021 U	0.15	< 0.00075 U	< 0.003 U	< 0.017 U	< 0.087 U	< 0.013 U	0.069	< 0.044 U	< 0.041 U	< 0.017 U	0.028		0.066
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated	< 0.084 U	< 0.21 U	< 0.093 U			< 0.022 U	0.19	< 0.00079 U	< 0.0031 U	< 0.018 U	< 0.093 U	< 0.013 U	0.042	< 0.046 U	< 0.043 U	< 0.018 U	0.012		0.032
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated	< 0.1 U	< 0.25 U	< 0.11 U			< 0.027 U	0.082	< 0.00094 U	< 0.0037 U	< 0.021 U	< 0.11 U	< 0.016 U	< 0.00062 U	< 0.055 U	< 0.052 U	< 0.021 U	0.014		0.018
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated	< 0.074 U	< 0.19 U	< 0.082 U			< 0.02 U	0.16	< 0.0007 U	< 0.0028 U	< 0.016 U	< 0.082 U	< 0.012 U	0.035	< 0.041 U	< 0.038 U	< 0.016 U	0.027		0.073
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated	< 0.082 U	< 0.21 U	< 0.09 U			< 0.022 U	0.5	0.013	< 0.0031 U	< 0.017 U	< 0.09 U	< 0.013 U	0.13	< 0.045 U	< 0.042 U	< 0.017 U	0.045		0.16
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated	< 0.078 U	< 0.2 U	< 0.086 U			< 0.021 U	0.43	0.015	< 0.0029 U	< 0.017 U	< 0.086 U	< 0.013 U	0.082	< 0.043 U	< 0.04 U	< 0.017 U	0.043		0.16
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	856.56	0 - 0.17 ft	180-80275-1	Excavated	< 0.076 U	< 0.19 U	< 0.084 U			< 0.02 U	0.31	< 0.00072 U	< 0.0028 U	< 0.016 U	< 0.084 U	< 0.012 U	0.082	< 0.042 U	< 0.039 U	< 0.016 U	0.037		0.12
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.31 U	< 0.8 U	< 0.35 U			< 0.084 U	1.3	0.028 J	< 0.012 U	< 0.067 U	< 0.35 U	< 0.051 U	0.27	< 0.17 U	< 0.16 U	< 0.067 U	0.11		0.23
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.32 U	< 0.81 U	< 0.36 U			< 0.086 U	0.51	0.045	< 0.012 U	< 0.069 U	< 0.36 U	< 0.052 U	0.15	< 0.18 U	< 0.17 U	< 0.069 U	0.12		0.14
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.063 U	< 0.16 U	< 0.07 U			< 0.017 U	0.23	< 0.0006 U	< 0.0024 U	< 0.014 U	< 0.07 U	< 0.01 U	0.11	< 0.035 U	< 0.033 U	< 0.014 U	0.042		0.069
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.25 U	< 0.63 U	< 0.28 U			< 0.067 U	0.48	< 0.0024 U	< 0.0093 U	< 0.053 U	< 0.28 U	< 0.04 U	0.17	< 0.14 U	< 0.13 U	< 0.053 U	0.074		0.064
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.15 U	< 0.38 U	< 0.17 U			< 0.04 U	0.26	< 0.0014 U	< 0.0056 U	< 0.032 U	< 0.17 U	< 0.024 U	0.07	< 0.083 U	< 0.077 U	< 0.032 U	0.045		0.054
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.058 U	< 0.15 U	< 0.064 U			< 0.015 U	0.18	< 0.00055 U	< 0.0022 U	< 0.012 U	< 0.064 U	< 0.0093 U	0.048	< 0.032 U	< 0.03 U	< 0.012 U	0.027		< 0.00085 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.3 U	< 0.75 U	< 0.33 U			< 0.079 U	0.31	< 0.0028 U	< 0.011 U	< 0.063 U	< 0.33 U	< 0.048 U	< 0.0018 U	< 0.16 U	< 0.15 U	< 0.063 U	0.075		0.022 J
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	855.49	0 - 0.17 ft	180-80275-1	Excavated	< 0.078 U	< 0.2 U	< 0.087 U			< 0.021 U	0.22	0.0075 J	< 0.0029 U	< 0.017 U	< 0.087 U	< 0.013 U	0.076	< 0.043 U	< 0.041 U	< 0.017 U	0.023		0.059
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	857.04	0 - 0.17 ft	180-80105-2	Excavated	< 0.079 U	< 0.2 U	< 0.087 U			< 0.021 U	0.076	< 0.00075 U	< 0.003 U	< 0.017 U	< 0.087 U	< 0.013 U	0.027	< 0.044 U	< 0.041 U	< 0.017 U	0.011		0.029
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated	< 0.083 U	< 0.21 U	< 0.092 U			< 0.022 U	0.074	< 0.00078 U	< 0.0031 U	< 0.018 U	< 0.092 U	< 0.013 U	0.039	< 0.046 U	< 0.043 U	< 0.018 U	0.0095 J		0.016
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated	< 0.081 U	< 0.21 U	< 0.09 U			< 0.022 U	0.092	< 0.00077 U	< 0.003 U	< 0.017 U	< 0.09 U	< 0.013 U	0.031	< 0.045 U	< 0.042 U	< 0.017 U	0.017		0.038
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.13 U	< 0.32 U	< 0.14 U			< 0.034 U	0.47	0.017	< 0.0047 U	< 0.027 U	< 0.14 U	< 0.02 U	0.15	< 0.069 U	< 0.065 U	< 0.027 U	0.15		0.12
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.16 U	< 0.41 U	< 0.18 U			< 0.044 U	0.53	0.023	< 0.0061 U	< 0.035 U	< 0.18 U	< 0.026 U	0.17	< 0.09 U	< 0.084 U	< 0.035 U	0.16		0.14
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.25 U	< 0.64 U	< 0.28 U			< 0.068 U	1.8	0.11	< 0.0095 U	< 0.054 U	< 0.28 U	< 0.041 U	0.38	< 0.14 U	< 0.13 U	< 0.054 U	0.11		0.12
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 1.2 U	< 3.1 U	< 1.4 U			< 0.33 U	0.1 J	< 0.012 U	< 0.046 U	< 0.26 U	< 1.4 U	< 0.2 U	< 0.0076 U	< 0.68 U	< 0.63 U	< 0.26 U	< 0.011 U		< 0.018 U
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated	< 0.079 U	< 0.2 U	< 0.088 U			< 0.021 U	0.15	< 0.00075 U	< 0.003 U	< 0.017 U	< 0.088 U	< 0.013 U	0.071	< 0.044 U	< 0.041 U	< 0.017 U	0.028		0.075
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated	< 0.076 U	< 0.19 U	< 0.084 U			< 0.02 U	0.99	0.015	< 0.0028 U	< 0.016 U	< 0.084 U	< 0.012 U	0.29	< 0.042 U	< 0.039 U	< 0.016 U	0.15		0.59
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated	< 0.089 U	< 0.23 U	< 0.098 U			< 0.024 U	0.4	< 0.00084 U	< 0.0033 U	< 0.019 U	< 0.098 U	< 0.014 U	0.1	< 0.049 U	< 0.046 U	< 0.019 U	0.05		0.19
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	855.38	0 - 0.17 ft	180-80157-2	Excavated	< 0.084 U	< 0.21 U	< 0.093 U			< 0.022 U	0.31	0.037	< 0.0031 U	< 0.018 U	< 0.093 U	< 0.013 U	0.08	< 0.046 U	< 0.043 U	< 0.018 U	0.026		0.028
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	855.74	0 - 0.17 ft	180-80157-2	Excavated	< 0.086 U	< 0.22 U	< 0.095 U			< 0.023 U	0.087	< 0.00081 U	< 0.0032 U	< 0.018 U	< 0.095 U	< 0.014 U	0.036	< 0.047 U	< 0.044 U	< 0.018 U	0.011		0.011
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	856.38	0 - 0.17 ft	180-80157-2	Excavated	< 0.1 U	< 0.26 U	< 0.11 U			< 0.028 U	0.064	< 0.00097 U	< 0.0039 U	< 0.022 U	< 0.11 U	< 0.017 U	0.03	< 0.057 U	< 0.053 U	< 0.022 U	0.013		0.013
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	854.93	0 - 0.17 ft	180-80157-2	Excavated	< 0.097 U	< 0.25 U	< 0.11 U			< 0.026 U	0.1	< 0.00092 U	< 0.0036 U	< 0.021 U	< 0.11 U	< 0.016 U	0.046	< 0.054 U	< 0.05 U	< 0.021 U	0.018		0.016
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	857.03	0 - 0.17 ft	180-80157-2	Excavated	< 0.078 U	< 0.2 U	< 0.087 U			< 0.021 U	0.062	< 0.00074 U	< 0.0029 U	< 0.017 U	< 0.087 U	< 0.013 U	0.029	< 0.043 U	< 0.041 U	< 0.017 U	0.011		0.015
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	856.56	0 - 0.17 ft	180-80157-2	Excavated	< 0.084 U	< 0.21 U	< 0.093 U			< 0.023 U	0.24	< 0.0008 U	< 0.0032 U	< 0.018 U	< 0.093 U	< 0.014 U	0.085	< 0.047 U	< 0.044 U	< 0.018 U	0.053		0.038
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	855.33	0 - 0.17 ft	180-80106-3	Excavated	< 0.1 U	< 0.27 U	< 0.12 U			< 0.028 U	0.17	< 0.00099 U	< 0.0039 U	< 0.022 U	< 0.12 U	< 0.017 U	0.055	< 0.058 U	< 0.054 U	< 0.022 U	0.012		0.01 J
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	855.28	0 - 0.17 ft	180-80275-1	Excavated	< 0.066 U	< 0.17 U	< 0.073 U			< 0.018 U	0.092	< 0.00062 U	< 0.0025 U	< 0.014 U	< 0.073 U	< 0.011 U	0.031	< 0.036 U	< 0.034 U	< 0.014 U	0.0065 J		0.02
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	856.14	0 - 0.17 ft	180-80106-3	Excavated	< 0.064 U	< 0.16 U	< 0.07 U			< 0.017 U	0.72	0.026	< 0.0024 U	< 0.014 U	< 0.07 U	< 0.01 U	0.14	< 0.035 U	< 0.033 U	< 0.014 U	0.0065 J		< 0.00093 U
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	856.82	0 - 0.17 ft	180-80157-2	Excavated	< 0.083 U	< 0.21 U	< 0.091 U			< 0.022 U	0.062	0.0049 J	< 0.0031 U	< 0.018 U	< 0.091 U	< 0.013 U	0.028	< 0.046 U	< 0.043 U	< 0.018 U	0.0089 J		0.015
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	854.83	0 - 0.17 ft	180-80275-1	Excavated	< 0.079 U	< 0.2 U	< 0.088 U			< 0.021 U	0.18	< 0.00075 U	< 0.003 U	< 0.017 U	< 0.088 U	< 0.013 U	0.047	< 0.044 U	< 0.041 U	< 0.017 U	0.029		0.079
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	855.41	0 - 0.17 ft	180-80091-4	Excavated	< 0.066 U	< 0.17 U	< 0.073 U			< 0.018 U	0.45	0.069	< 0.0025 U	< 0.014 U	< 0.073 U	< 0.011 U	0.095	< 0.036 U	< 0.034 U	< 0.014 U	0.03		0.054
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	855.30	0 - 0.17 ft	180-80091-4	Excavated	< 0.064 U	< 0.16 U	< 0.071 U			< 0.017 U	0.061	< 0.00061 U	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	0.019	< 0.035 U	< 0.033 U	< 0.014 U	< 0.00057 U		< 0.00094 U
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	855.25	0 - 0.17 ft	180-80157-3	Excavated	< 0.073 U	< 0.18 U	< 0.081 U			< 0.02 U	0.051	< 0.00069 U	< 0.0027 U	< 0.016 U	< 0.081 U	< 0.012 U	0.019	< 0.04 U	< 0.038 U	< 0.016 U	< 0.00065 U		< 0.0011 U
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	855.30	0 - 0.17 ft	180-80106-3	Excavated	< 0.13 U	< 0.32 U	< 0.14 U			< 0.034 U	0.1	< 0.0012 U	< 0.0047 U	< 0.027 U	< 0.14 U	< 0.02 U	0.036	< 0.07 U	< 0.065 U	< 0.027 U	0.012 J		< 0.0018 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	855.07	0 - 0.17 ft	180-80091-4	Excavated	< 0.065 U	< 0.17 U	< 0.072 U			< 0.017 U	0.18	0.0065 J	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.052	< 0.036 U	< 0.034 U	< 0.014 U	< 0.00058 U		0.0046 J
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.063 U	< 0.16 U,F2	< 0.07 U			< 0.017 U	0.013	< 0.0006 U	< 0.0024 U	< 0.014 U	< 0.07 U,F1	< 0.01 U	< 0.0004 U	< 0.035 U	< 0.033 U	< 0.014 U	< 0.00057 U		< 0.00093 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.064 U	< 0.16 U	< 0.071 U			< 0.017 U	0.19	0.024	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	< 0.0004 U	< 0.036 U	0.04 J	< 0.014 U	0.15		0.11
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.13 U	< 0.33 U	< 0.14 U			< 0.035 U	0.22	< 0.0012 U	< 0.0049 U	< 0.028 U	< 0.14 U	< 0.021 U	< 0.00081 U	< 0.072 U	< 0.067 U	< 0.028 U	0.051		0.083
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated							0.31 J						0.2 J						
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.52	0.023 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.26	< 0.12 U	< 0.13 U	< 0.022 U	0.051 J		0.077 J
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated	< 0.027 U	< 1.2 U	< 0.021 U			< 0.13 U	0.46	0.018 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.3	< 0.12 U	< 0.13 U	< 0.022 U	0.033 J		0.035 J

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

							2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.8	100	0.33	100					
Restricted - Residential																6.7	100	100	100					
Protection of Groundwater																0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																	
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated									< 1.1 U	< 0.47 U	< 0.47 U	< 0.47 U					
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.16 U	< 0.15 U	< 0.14 U	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	0.036 J	< 0.0084 U	0.022 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated											0.31 J						
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated										< 1 U	< 0.42 U	< 0.42 U	< 0.42 U					
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated										< 11 U	1.4 J	< 4.4 U	0.46 J					
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated										< 1 U	< 0.43 U	< 0.43 U	< 0.43 U					
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated										< 1 U	0.11 J	< 0.43 U	0.29 J					
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated											0.47		0.84					
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SS	7/28/2018	852.76	0 - 0.17 ft	180-80275-1	Excavated	< 0.056 U	< 0.068 U	< 0.083 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.017 U	< 0.081 U	0.052	< 0.011 U	0.14		< 0.019 U	< 0.41 U	< 0.096 U	< 0.089 U
Football Field	SSHS-B2025	SSHS-B2025-SS	7/28/2018	854.55	0 - 0.17 ft	180-80275-1	Excavated	< 0.054 U	< 0.066 U	< 0.08 U	< 0.017 U	< 0.017 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.078 U	0.09	< 0.011 U	0.21		< 0.019 U	< 0.39 U	< 0.092 U	< 0.086 U
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	0 - 0.17 ft	180-80275-1	Not Excavated	< 0.054 U	< 0.066 U	< 0.081 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.079 U	0.094	0.025 J	0.21		< 0.019 U	< 0.4 U	< 0.093 U	< 0.087 U
Football Field	SSHS-B2027	SSHS-B2027-SS	7/28/2018	855.22	0 - 0.17 ft	180-80275-1	Excavated	< 0.052 U	< 0.064 U	< 0.079 U	< 0.017 U	< 0.017 U	< 0.12 U		< 0.014 U	< 0.016 U	< 0.076 U	0.019	< 0.01 U	0.04		< 0.018 U	< 0.38 U	< 0.09 U	< 0.084 U
Football Field	SSHS-B2028	SSHS-B2028-SS	7/28/2018	855.23	0 - 0.17 ft	180-80275-1	Excavated	< 0.052 U	< 0.064 U	< 0.079 U	< 0.017 U	< 0.017 U	< 0.12 U		< 0.014 U	0.017 J	< 0.076 U	0.018	< 0.01 U	0.036		< 0.018 U	< 0.38 U	< 0.09 U	< 0.084 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.12 U	< 0.14 U	< 0.18 U	< 0.038 U	< 0.038 U	< 0.28 U		< 0.032 U	< 0.035 U	< 0.17 U	0.29	< 0.023 U	0.51		< 0.041 U	< 0.86 U	< 0.2 U	< 0.19 U
Football Field	SSHS-B2031	FD-57	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	< 0.1 U	< 0.12 U	< 0.15 U	< 0.033 U	< 0.033 U	< 0.24 U		< 0.028 U	< 0.03 U	< 0.15 U	0.03	< 0.02 U	0.051		< 0.035 U	< 0.73 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B2031	SSHS-B2031-SS	7/28/2018	855.50	0 - 0.17 ft	180-80275-1	Excavated	< 0.051 U	< 0.062 U	< 0.076 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.074 U	0.02	< 0.01 U	0.033		< 0.018 U	< 0.37 U	< 0.088 U	< 0.081 U
Football Field	SSHS-B2032	SSHS-B2032-SS	7/28/2018	854.88	0 - 0.17 ft	180-80275-1	Excavated	< 0.052 U	< 0.064 U	< 0.078 U	< 0.017 U	< 0.017 U	< 0.12 U		< 0.014 U	< 0.016 U	< 0.075 U	0.013	< 0.01 U	0.028		< 0.018 U	< 0.38 U	< 0.089 U	< 0.083 U
Football Field	SSHS-B2033	SSHS-B2033-SS	7/28/2018	854.70	0 - 0.17 ft	180-80275-1	Excavated	< 0.049 U	< 0.06 U	< 0.074 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.071 U	0.021	< 0.0098 U	0.046		< 0.017 U	< 0.36 U	< 0.085 U	< 0.079 U
Football Field	SSHS-B2050	SSHS-B2050-SS	7/28/2018	855.45	0 - 0.17 ft	180-80275-1	Excavated	< 0.057 U	< 0.07 U	< 0.086 U	< 0.019 U	< 0.019 U	< 0.13 U		< 0.016 U	< 0.017 U	< 0.083 U	0.07	0.037 J	0.22		< 0.02 U	< 0.42 U	< 0.099 U	< 0.092 U
Football Field	SSHS-B2051	SSHS-B2051-SS	7/28/2018	855.08	0 - 0.17 ft	180-80275-1	Excavated	< 0.057 U	< 0.069 U	< 0.085 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.016 U	< 0.017 U	< 0.082 U	0.034	< 0.011 U	0.064		< 0.02 U	< 0.41 U	< 0.098 U	< 0.09 U
Football Field	SSHS-B2053	SSHS-B2053-SS	7/28/2018	855.00	0 - 0.17 ft	180-80275-1	Excavated	< 0.052 U	< 0.064 U	< 0.078 U	< 0.017 U	< 0.017 U	< 0.12 U		< 0.014 U	< 0.016 U	< 0.076 U	0.025	< 0.01 U	0.035		< 0.018 U	< 0.38 U	< 0.09 U	< 0.084 U
Football Field	SSHS-B2070	SSHS-B2070-SS	7/28/2018	854.72	0 - 0.17 ft	180-80275-1	Excavated	< 0.057 U	< 0.07 U	< 0.086 U	< 0.019 U	< 0.019 U	< 0.13 U		< 0.016 U	< 0.017 U	< 0.083 U	0.032	< 0.011 U	0.066		< 0.02 U	< 0.42 U	< 0.098 U	< 0.091 U
Football Field	SSHS-B2071	SSHS-B2071-SS	7/24/2018	856.16	0 - 0.17 ft	180-80105-2	Excavated	< 0.06 U	< 0.073 U	< 0.09 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.087 U	0.031	< 0.012 U	0.047		< 0.021 U	< 0.44 U	< 0.1 U	< 0.095 U
Football Field	SSHS-B2072	SSHS-B2072-SS	7/24/2018	856.82	0 - 0.17 ft	180-80105-2	Excavated	< 0.059 U	< 0.072 U	< 0.088 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.085 U	0.0097 J	< 0.012 U	0.021		< 0.021 U	< 0.43 U	< 0.1 U	< 0.094 U
Football Field	SSHS-B2073	SSHS-B2073-SS	7/24/2018	856.99	0 - 0.17 ft	180-80105-2	Excavated	< 0.056 U	< 0.069 U	< 0.085 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.017 U	< 0.082 U	0.091	< 0.011 U	0.15		< 0.02 U	< 0.41 U	< 0.097 U	< 0.09 U
Football Field	SSHS-B2089	SSHS-B2089-SS	7/26/2018	855.40	0 - 0.17 ft	180-80225-3	Excavated	< 0.054 U	< 0.066 U	< 0.08 U	< 0.017 U	< 0.017 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.078 U	0.051	< 0.011 U	0.099		< 0.019 U	< 0.39 U	< 0.092 U	< 0.086 U
Football Field	SSHS-B2091	SSHS-B2091-SS	7/24/2018	856.61	0 - 0.17 ft	180-80105-3	Excavated	< 0.059 U	< 0.073 U	< 0.089 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.086 U	0.074	0.023 J	0.12		< 0.021 U	< 0.43 U	< 0.1 U	< 0.095 U
Football Field	SSHS-B2092	SSHS-B2092-SS	7/24/2018	856.77	0 - 0.17 ft	180-80105-2	Excavated	< 0.059 U	< 0.072 U	< 0.089 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.086 U	0.023	0.033 J	0.047		< 0.021 U	< 0.43 U	< 0.1 U	< 0.094 U
Football Field	SSHS-B2108	SSHS-B2108-SS	7/26/2018	855.64	0 - 0.17 ft	180-80225-3	Excavated	< 0.056 U	< 0.069 U	< 0.084 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.017 U	< 0.082 U	0.058	< 0.011 U	0.094		< 0.02 U	< 0.41 U	< 0.097 U	< 0.09 U
Football Field	SSHS-B2109	SSHS-B2109-SS	7/26/2018	855.25	0 - 0.17 ft	180-80225-3	Excavated	< 0.06 U	< 0.073 U	< 0.09 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.087 U	0.079	< 0.012 U	0.11		< 0.021 U	< 0.44 U	< 0.1 U	< 0.096 U
Football Field	SSHS-B2110	SSHS-B2110-SS	7/26/2018	854.78	0 - 0.17 ft	180-80225-3	Excavated	< 0.071 U	< 0.087 U	< 0.11 U	< 0.023 U	< 0.023 U	< 0.17 U		< 0.02 U	< 0.021 U	< 0.1 U	0.031	< 0.014 U	0.055		< 0.025 U	< 0.52 U	< 0.12 U	< 0.11 U
Football Field	SSHS-B2127	SSHS-B2127-SS	7/28/2018	855.91	0 - 0.17 ft	180-80275-1	Excavated	< 0.053 U	< 0.065 U	< 0.079 U	< 0.017 U	< 0.017 U	< 0.12 U		< 0.015 U	< 0.016 U	< 0.077 U	0.067	< 0.011 U	0.13		< 0.018 U	< 0.39 U	< 0.091 U	< 0.085 U
Football Field	SSHS-B2128	SSHS-B2128-SS	7/28/2018	856.01	0 - 0.17 ft	180-80275-1	Excavated	< 0.058 U	< 0.071 U	< 0.087 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.017 U	< 0.085 U	0.25	0.038 J	0.4		< 0.02 U	< 0.43 U	< 0.1 U	< 0.093 U
Football Field	SSHS-B2129	SSHS-B2129-SS	7/28/2018	855.33	0 - 0.17 ft	180-80275-1	Excavated	< 0.056 U	< 0.068 U	< 0.084 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.017 U	< 0.081 U	0.23	0.084	0.34		< 0.02 U	< 0.41 U	< 0.096 U	< 0.089 U
Football Field	SSHS-B2143	SSHS-B2143-SS	7/28/2018	856.56	0 - 0.17 ft	180-80275-1	Excavated	< 0.054 U	< 0.066 U	< 0.081 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.078 U	0.11	< 0.011 U	0.24		< 0.019 U	< 0.4 U	< 0.093 U	< 0.086 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.22 U	< 0.28 U	< 0.34 U	< 0.073 U	< 0.073 U	< 0.53 U		< 0.062 U	< 0.067 U	< 0.33 U	0.93	< 0.045 U	0.95		< 0.079 U	< 1.6 U	< 0.39 U	< 0.36 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.23 U	< 0.28 U	< 0.34 U	< 0.075 U	< 0.075 U	< 0.54 U		< 0.063 U	< 0.069 U	< 0.33 U	0.43	< 0.046 U	0.42		< 0.08 U	< 1.7 U	< 0.4 U	< 0.37 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.045 U	< 0.055 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.012 U	< 0.014 U	< 0.066 U	0.096	< 0.0091 U	0.21		< 0.016 U	< 0.33 U	< 0.078 U	< 0.072 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.18 U	< 0.22 U	< 0.27 U	< 0.058 U	< 0.058 U	< 0.42 U		< 0.049 U	< 0.053 U	< 0.26 U	0.17	< 0.036 U	0.53		< 0.062 U	< 1.3 U	< 0.31 U	< 0.28 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.11 U	< 0.13 U	< 0.16 U	< 0.035 U	< 0.035 U	< 0.25 U		< 0.029 U	< 0.032 U	< 0.15 U	0.1	< 0.021 U	0.2		< 0.037 U	< 0.78 U	< 0.18 U	< 0.17 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.041 U	< 0.051 U	< 0.062 U	< 0.013 U	< 0.013 U	< 0.097 U		< 0.011 U	< 0.012 U	< 0.06 U	0.08	< 0.0083 U	0.16		< 0.014 U	< 0.3 U	< 0.071 U	< 0.066 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.21 U	< 0.26 U	< 0.32 U	< 0.069 U	< 0.069 U	< 0.5 U		< 0.058 U	< 0.063 U	< 0.31 U	0.19	< 0.042 U	0.2		< 0.074 U	< 1.5 U	< 0.36 U	< 0.34 U
Football Field	SSHS-B2192	SSHS-B2192-SS	7/28/2018	855.49	0 - 0.17 ft	180-80275-1	Excavated	< 0.056 U	< 0.069 U	< 0.084 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.017 U	< 0.081 U	0.093	0.026 J	0.17		< 0.02 U	< 0.41 U	< 0.096 U	< 0.09 U
Football Field	SSHS-B2193	SSHS-B2193-SS	7/24/2018	857.04	0 - 0.17 ft	180-80105-2	Excavated	< 0.056 U	< 0.069 U	< 0.085 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.016 U	< 0.017 U	< 0.082 U	0.042	< 0.011 U	0.07		< 0.02 U	< 0.41 U	< 0.097 U	< 0.09 U
Football Field	SSHS-B2194	SSHS-B2194-SS	7/24/2018	856.19	0 - 0.17 ft	180-80105-2	Excavated	< 0.059 U	< 0.072 U	< 0.089 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.086 U	0.032	< 0.012 U	0.072		< 0.021 U	< 0.43 U	< 0.1 U	< 0.095 U
Football Field	SSHS-B2195	SSHS-B2195-SS	7/24/2018	855.94	0 - 0.17 ft	180-80105-2	Excavated	< 0.058 U	< 0.071 U	< 0.087 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.017 U	< 0.084 U	0.041	< 0.012 U	0.072		< 0.02 U	< 0.42 U	< 0.1 U	< 0.093 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.089 U	< 0.11 U	< 0.13 U	< 0.029 U	< 0.029 U	< 0.21 U		< 0.025 U	< 0.027 U	< 0.13 U	0.32	< 0.018 U	0.37		< 0.031 U	< 0.65 U	< 0.15 U	< 0.14 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.12 U	< 0.14 U	< 0.17 U	< 0.038 U	< 0.038 U	< 0.27 U		< 0.032 U	< 0.035 U	< 0.17 U	0.37	< 0.023 U	0.43		< 0.041 U	< 0.85 U	< 0.2 U	< 0.19 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.18 U	< 0.22 U	< 0.27 U	< 0.059 U	< 0.059 U	< 0.42 U		< 0.05 U	< 0.054 U	< 0.26 U	0.81	< 0.036 U	1.6		< 0.063 U	< 1.3 U	< 0.31 U	< 0.29 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.87 U	< 1.1 U	< 1.3 U	< 0.28 U	< 0.28 U	< 2.1 U		< 0.24 U	< 0.26 U	< 1.3 U	0.12 J	< 0.17 U	0.15		< 0.31 U	< 6.4 U	< 1.5 U	< 1.4 U
Football Field	SSHS-B2214	SSHS-B2214-SS	7/24/2018	855.14	0 - 0.17 ft	180-80105-2	Excavated	< 0.057 U	< 0.069 U	< 0.085 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.016 U	< 0.017 U	< 0.082 U	0.082	0.029 J	0.14		< 0.02 U	< 0.41 U	< 0.098 U	< 0.09 U
Football Field	SSHS-B2215	SSHS-B2215-SS	7/24/2018	855.11	0 - 0.17 ft	180-80105-2	Excavated	< 0.054 U	< 0.066 U	< 0.081 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.079 U	0.38	0.031 J	0.79		< 0.019 U	< 0.4 U	< 0.094 U	< 0.087 U
Football Field	SSHS-B2217	SSHS-B2217-SS	7/26/2018	855.08	0 - 0.17 ft	180-80225-3	Excavated	< 0.064 U	< 0.078 U	< 0.095 U	< 0.021 U	< 0.021 U	< 0.15 U		< 0.017 U	< 0.019 U	< 0.092 U	0.18	< 0.013 U	0.24		< 0.022 U	< 0.47 U	< 0.11 U	< 0.1 U
Football Field	SSHS-B2221	SSHS-B2221-SS	7/25/2018	855.38	0 - 0.17 ft	180-80157-2	Excavated	< 0.06 U	< 0.073 U	< 0.09 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.087 U	0.27	0.04 J	0.26		< 0.021 U	< 0.44 U	< 0.1 U	< 0.096 U
Football Field	SSHS-B2222	SSHS-B2222-SS	7/25/2018	855.74	0 - 0.17 ft	180-80157-2	Excavated	< 0.061 U	< 0.075 U	< 0.092 U	< 0.02 U	< 0.02 U	< 0.14 U		< 0.017 U	< 0.018 U	< 0.089 U	0.047	0.33	0.084		< 0.021 U	< 0.45 U	< 0.11 U	< 0.098 U
Football Field	SSHS-B2223	SSHS-B2223-SS	7/25/2018	856.38	0 - 0.17 ft	180-80157-2	Excavated	< 0.074 U	< 0.09 U	< 0.11 U	< 0.024 U	< 0.024 U	< 0.17 U		< 0.02 U	< 0.022 U	< 0.11 U	0.031	0.12	0.057		< 0.026 U	< 0.54 U	< 0.13 U	< 0.12 U
Football Field	SSHS-B2224	SSHS-B2224-SS	7/25/2018	854.93	0 - 0.17 ft	180-80157-2	Excavated	< 0.069 U	< 0.085 U	< 0.1 U	< 0.022 U	< 0.022 U	< 0.16 U		< 0.019 U	< 0.021 U	< 0.1 U	0.04	0.049 J	0.085		< 0.024 U	< 0.51 U	< 0.12 U	< 0.11 U
Football Field	SSHS-B2225	SSHS-B2225-SS	7/25/2018	857.03	0 - 0.17 ft	180-80157-2	Excavated	< 0.056 U	< 0.068 U	< 0.084 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.017 U	< 0.081 U	0.029	0.11	0.054		< 0.02 U	< 0.41 U	< 0.096 U	< 0.089 U
Football Field	SSHS-B2226	SSHS-B2226-SS	7/25/2018	856.56	0 - 0.17 ft	180-80157-2	Excavated	< 0.06 U	< 0.074 U	< 0.09 U	< 0.02 U	< 0.02 U	< 0.14 U		< 0.017 U	< 0.018 U	< 0.087 U	0.1	0.086	0.23		< 0.021 U	< 0.44 U	< 0.1 U	< 0.096 U
Football Field	SSHS-B2228	SSHS-B2228-SS	7/24/2018	855.33	0 - 0.17 ft	180-80106-3	Excavated	< 0.075 U	< 0.092 U	< 0.11 U	< 0.024 U	< 0.024 U	< 0.18 U		< 0.021 U	< 0.022 U	< 0.11 U	0.06	< 0.015 U	0.13		< 0.026 U	< 0.55 U	< 0.13 U	< 0.12 U
Football Field	SSHS-B2229	SSHS-B2229-SS	7/28/2018	855.28	0 - 0.17 ft	180-80275-1	Excavated	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.049	< 0.0094 U	0.076		< 0.016 U	< 0.34 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2231	SSHS-B2231-SS	7/24/2018	856.14	0 - 0.17 ft	180-80106-3	Excavated	< 0.045 U	< 0.056 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.39	< 0.0091 U	0.52		< 0.016 U	< 0.33 U	< 0.078 U	< 0.073 U
Football Field	SSHS-B2232	SSHS-B2232-SS	7/25/2018	856.82	0 - 0.17 ft	180-80157-2	Excavated	< 0.059 U	< 0.072 U	< 0.088 U	< 0.019 U	< 0.019 U	< 0.14 U		< 0.016 U	< 0.018 U	< 0.085 U	0.036	< 0.012 U	0.056		< 0.021 U	< 0.43 U	< 0.1 U	< 0.094 U
Football Field	SSHS-B2233	SSHS-B2233-SS	7/28/2018	854.83	0 - 0.17 ft	180-80275-1	Excavated	< 0.056 U	< 0.069 U	< 0.085 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.016 U	< 0.017 U	< 0.082 U	0.057	< 0.011 U	0.14		< 0.02 U	< 0.41 U	< 0.097 U	< 0.09 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-SS	7/23/2018	855.41	0 - 0.17 ft	180-80091-4	Excavated	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.51	< 0.0094 U	0.32		< 0.016 U	< 0.34 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-SS	7/23/2018	855.30	0 - 0.17 ft	180-80091-4	Excavated	< 0.046 U	< 0.056 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.027	< 0.0091 U	0.047		< 0.016 U	< 0.33 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2236	SSHS-B2236-SS	7/25/2018	855.25	0 - 0.17 ft	180-80157-3	Excavated	< 0.052 U	< 0.064 U	< 0.078 U	< 0.017 U	< 0.017 U	< 0.12 U		< 0.014 U	< 0.016 U	< 0.075 U	0.021	< 0.01 U	0.043		< 0.018 U	< 0.38 U	< 0.09 U	< 0.083 U
Football Field	SSHS-B2237	SSHS-B2237-SS	7/24/2018	855.30	0 - 0.17 ft	180-80106-3	Excavated	< 0.09 U	< 0.11 U	< 0.14 U	< 0.029 U	< 0.029 U	< 0.21 U		< 0.025 U	< 0.027 U	< 0.13 U	0.049	< 0.018 U	0.078		< 0.032 U	< 0.66 U	< 0.16 U	< 0.14 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-SS	7/23/2018	855.07	0 - 0.17 ft	180-80091-4	Excavated	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.077	< 0.0093 U	0.14		< 0.016 U	< 0.34 U	< 0.08 U	< 0.075 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.045 U	< 0.055 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.012 U	< 0.014 U	< 0.066 U,F1,F2	< 0.00083 U	< 0.0091 U	0.012		< 0.016 U	< 0.33 U,F1	< 0.078 U	< 0.072 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.046 U	< 0.056 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.22	0.062	0.13		< 0.016 U	< 0.34 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.093 U	< 0.11 U	< 0.14 U	< 0.03 U	< 0.03 U	< 0.22 U		< 0.026 U	< 0.028 U	< 0.13 U	0.16	< 0.019 U	0.17		< 0.032 U	< 0.68 U	< 0.16 U	< 0.15 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated											0.1 J		0.34 J					
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0-0.17	8/29/2019	853.35	0 - 0.17 ft	180-95024-2	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.21	< 0.13 U	0.57		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0-0.17	8/29/2019	853.09	0 - 0.17 ft	180-95006-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.067 J	< 0.13 U	0.92		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated			1.007	< 0.025 U	0.045 J	< 0.023 U	0.026 J	< 0.19 U	< 0.018 U	< 0.053 U	0.1	0.086	0.13	0.057 J	0.077 J	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated			0.279	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	0.033 J	< 0.018 U	0.043 J	< 0.025 U	0.038 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated			0.85	< 0.023 U	0.025 J	< 0.022 U	0.023 J	< 0.18 U	< 0.017 U	< 0.05 U	0.073 J	0.08 J	0.12	0.05 J	0.08 J	< 0.019 U	< 0.015 U	< 0.03 U	3 J	< 0.028 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated			0.206	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	0.03 J	0.028 J	0.033 J	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated			0.427	< 0.026 U	< 0.02 U	< 0.025 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	0.047 J	0.035 J	0.059 J	< 0.027 U	0.035 J	< 0.022 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.032 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated			0.344	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	0.038 J	0.037 J	0.054 J	< 0.026 U	0.03 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.031 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated			0.106	< 0.026 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.019 U	< 0.055 U	0.02 J	< 0.019 UJ	< 0.022 UJ	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated			0.102	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.055 U	0.022 J	< 0.019 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated			0.843	< 0.025 U	0.04 J	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	0.061 J	0.083 J	0.11	0.043 J	0.099	< 0.021 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated			0.075	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	0.024 J	< 0.018 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated			1.113	< 0.024 U	0.02 J	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	0.11	0.12	0.13	0.056 J	0.087	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated			0.497	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	0.055 J	0.055 J	0.077 J	0.027 J	0.045 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated			3.072	< 0.025 U	0.12	< 0.024 U	0.079 J	< 0.19 U	< 0.019 U	< 0.055 U	0.27	0.29	0.39	0.16	0.24	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated			0.3	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.055 U	0.033 J	0.03 J	0.043 J	< 0.026 U	0.026 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated			0.309	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	0.038 J	0.032 J	0.044 J	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated			0.112	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.05 U	0.02 J	< 0.017 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated			1.422	< 0.025 U	0.065 J	< 0.023 U	0.04 J	< 0.19 U	< 0.018 U	< 0.053 U	0.099	0.13	0.17	0.054 J	0.17	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated			1.145	< 0.024 U	0.069 J	< 0.023 U	0.039 J	< 0.18 U	< 0.017 U	< 0.052 U	0.081 J	0.097	0.13	0.046 J	0.13	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated			0.228	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	0.025 J	< 0.019 U	< 0.022 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated			0.091	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.016 U	< 0.019 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated			0.141	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	0.026 J	< 0.019 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated			0.49	< 0.027 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.057 U	0.044 J	0.045 J	0.069 J	< 0.028 U	0.046 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated			4.095	< 0.026 U	0.082 J	< 0.025 U	0.11	< 0.2 U	< 0.019 U		0.39	0.33	0.37	0.15	0.23	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated			0.356	< 0.027 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.057 U	0.04 J	0.037 J	0.054 J	< 0.028 U	0.031 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated			0.478	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	0.046 J	0.043 J	0.064 J	0.026 J	0.035 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated			0.314	< 0.027 U	< 0.021 U	< 0.026 U	< 0.024 U	< 0.21 U	< 0.02 U	< 0.059 U	0.041 J	0.038 J	0.052 J	< 0.028 U	0.031 J	< 0.023 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated			1.708	< 0.025 U	0.1	< 0.023 U	0.061 J	< 0.19 U	< 0.018 U	< 0.054 U	0.17	0.17	0.25	0.065 J	0.15	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated			0.471	< 0.025 U	0.024 J	< 0.024 U	< 0.023 U	< 0.19 U	< 0.019 U	< 0.055 U	0.042 J	0.047 J	0.054 J	0.029 J	0.046 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated			1.966	0.03 J	0.019 J	< 0.023 U	0.082 J	< 0.19 U	< 0.018 U	< 0.053 U	0.18	0.14	0.17	0.063 J	0.12	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated			3.973	< 0.024 U	0.13	< 0.023 U	0.093	< 0.18 U	< 0.018 U	< 0.052 U	0.35	0.37	0.45	0.2	0.37	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated			6.569	< 0.024 U	0.2	< 0.023 U	0.22	< 0.19 U	< 0.018 U	< 0.052 U	0.59	0.59	0.66	0.25	0.48	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated			0.339	< 0.027 U	< 0.021 U	< 0.025 U	< 0.024 U	< 0.21 U	< 0.02 U	< 0.058 U	0.03 J	0.031 J	0.049 J	< 0.028 U	0.046 J	< 0.022 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated			0.457	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	0.036 J	0.037 J	0.047 J	0.026 J	0.045 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated			0.501	< 0.027 U	< 0.021 U	< 0.025 U	< 0.024 U	< 0.21 U	< 0.02 U	< 0.058 U	0.045 J	0.05 J	0.069 J	< 0.028 U	0.05 J	< 0.022 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated			0.226	< 0.027 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.02 U	< 0.058 U	0.027 J	0.031 J	< 0.023 U	< 0.028 U	0.028 J	< 0.022 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated			0.488	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	0.043 J	0.046 J	0.066 J	0.028 J	0.038 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated			3.742	< 0.027 U	0.086 J	< 0.025 U	0.067 J	< 0.2 U	< 0.019 U		0.4	0.33	0.42	0.18	0.25	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated			0.536	< 0.025 U	0.02 J	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U		0.055 J	0.059 J	0.08 J	< 0.026 U	0.054 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated			0.443	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.019 U		0.044 J	0.049 J	0.047 J	0.037 J	0.041 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated			5.162	< 0.025 U	0.31	< 0.024 U	0.16	< 0.19 U	< 0.018 U	< 0.054 U	0.51	0.49	0.64	0.28	0.49	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated			2.277	< 0.025 U	0.093	< 0.023 U	0.064 J	< 0.19 U	< 0.018 U	< 0.053 U	0.21	0.19	0.27	0.097	0.2	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated			1.144	< 0.025 U	0.033 J	< 0.023 U	0.025 J	< 0.19 U	< 0.018 U	< 0.053 U	0.1	0.1	0.15	0.043 J	0.11	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated			1.965	< 0.024 U	0.11	< 0.022 U	0.056 J	< 0.18 U	< 0.017 U	< 0.051 U	0.18	0.18	0.25	0.08 J	0.19	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated			1.197	< 0.024 U	0.045 J	< 0.022 U	0.027 J	< 0.18 U	< 0.017 U	< 0.051 U	0.1	0.11	0.16	0.041 J	0.12	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated			0.394	< 0.026 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.019 U	< 0.055 U	0.04 J	0.046 J	0.059 J	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated			0.346	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	0.039 J	0.034 J	0.038 J	< 0.026 U	0.042 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated			0.774	< 0.026 U	0.032 J	< 0.024 U	< 0.023 U	< 0.19 U	< 0.019 U	< 0.055 U	0.073 J	0.079 J	0.11	0.029 J	0.081 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated			0.623	< 0.023 U	0.026 J	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.055 J	0.054 J	0.059 J	0.039 J	0.073 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated			4.252	< 0.025 U	0.078 J	< 0.024 U	0.091	< 0.19 U	< 0.018 U	< 0.055 U	0.41	0.36	0.44	0.19	0.32	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated			0.282	< 0.026 U	< 0.02 U	< 0.025 U	< 0.023 U	< 0.2 U	< 0.019 U		0.033 J	0.027 J	0.043 J	< 0.027 U	0.033 J	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated			0.437	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U		0.045 J	0.039 J	0.07 J	< 0.026 U	0.041 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.031 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated			1.976	< 0.024 U	0.075 J	< 0.023 U	0.052 J	< 0.18 U	< 0.017 U	< 0.052 U	0.17	0.18	0.23	0.092	0.19	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated			1.498	< 0.024 U	0.054 J	< 0.023 U	0.043 J	< 0.18 U	< 0.018 U	< 0.052 U	0.13	0.13	0.17	0.069 J	0.14	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated			0.194	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.055 U	0.032 J	< 0.019 U	0.047 J	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated			0.896	< 0.027 U	0.03 J	< 0.025 U	< 0.024 UJ	< 0.2 U	< 0.02 U	< 0.058 U	0.082 J	0.084 J	0.11	0.056 J	0.067 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated			0.247	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	0.032 J	0.027 J	0.036 J	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated			5.798	< 0.027 U	0.32	< 0.025 U	0.17	< 0.2 U	< 0.02 U	< 0.058 U	0.57	0.56	0.71	0.3	0.49	< 0.022 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated			0.454	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U		0.041 J	0.045 J	0.053 J	0.035 J	0.046 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated			1.152	< 0.027 U	< 0.02 U	< 0.025 U	0.032 J	< 0.2 U	< 0.019 U	< 0.057 U	0.11	0.094	0.12	0.047 J	0.066 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated			2.07	< 0.026 U	0.12	< 0.025 U	0.074 J	< 0.2 U	< 0.019 U	< 0.057 U	0.2	0.2	0.29	0.091 J	0.19	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated			0.537	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	0.05 J	0.052 J	0.067 J	0.033 J	0.034 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated			0.632	< 0.026 U	< 0.02 U	< 0.025 U	< 0.023 U	< 0.2 U	< 0.019 U		0.072 J	0.061 J	0.087 J	< 0.027 U	0.054 J	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated			6.231	< 0.025 U	0.34	< 0.024 U	0.18	< 0.19 U	< 0.018 U		0.6	0.63	0.9	0.23	0.6	< 0.021 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated			1.724	< 0.023 U	0.036 J	< 0.022 U	0.039 J	< 0.17 U	< 0.017 U	< 0.049 U	0.17	0.18	0.23	0.087	0.14	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated			1.385	< 0.021 U	0.02 J	< 0.02 U	0.027 J	< 0.16 U	< 0.016 U	< 0.046 U	0.12	0.12	0.17	0.055 J	0.091	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated			0.457	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	0.044 J	0.05 J	0.062 J	< 0.025 U	0.042 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated			3.473	< 0.028 U	0.025 J	< 0.027 U	0.05 J	< 0.22 U	< 0.021 U	< 0.061 U	0.31	0.31	0.39	0.11	0.25	< 0.024 U	< 0.018 U	< 0.037 U	< 0.53 U	< 0.035 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated			0.759	< 0.026 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.057 U	0.073 J	0.072 J	0.093	0.036 J	0.061 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated			0.537	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.048 J	0.047 J	0.061 J	< 0.024 U	0.039 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Butylbenzyl phthalate	**Caprolactam**	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**	**3,3-Dichlorobenzidine**	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.12	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.039 J	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.085	< 0.018 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 UJ	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.031 J	< 0.02 U	< 0.02 U	< 0.42 UJ	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.051 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.026 U	0.042 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.027 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.61 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.021 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.77 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.026 U	0.079 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.017 U	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.11	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.057 J	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated	< 0.3 U	< 0.29 U	0.03 J	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.33	0.042 J	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.044 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.033 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.023 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.17 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.12	< 0.019 U	0.019 J	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.09	< 0.019 U	0.029 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated	< 0.3 U	< 0.29 U	< 0.02 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.037 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.76 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.017 U	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.026 U	0.024 J	< 0.019 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	0.058 J	< 0.021 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated	< 0.31 U	< 0.29 U	0.057 J	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.33	0.059 J	0.032 J	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	0.047 J	< 0.021 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.79 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.054 J	< 0.019 U	< 0.019 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated	< 0.32 U	< 0.31 U	< 0.022 U	< 0.016 U	< 0.022 U	< 0.022 U	< 0.022 U	< 0.029 U	0.035 J	< 0.021 U	< 0.021 U	< 0.44 U	< 0.036 U	< 0.17 U	< 0.029 U	< 0.017 U	< 0.21 U	< 0.27 U	< 0.81 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.18	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.057 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.16 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated	< 0.29 U	< 0.28 U	0.027 J	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.15	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated	< 0.29 U	< 0.27 U	0.02 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.34	0.08 J	0.025 J	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.25 U	< 0.73 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated	< 0.29 U	< 0.27 U	0.058 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.54	0.093	0.04 J	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated	< 0.32 U	< 0.31 U	< 0.022 U	< 0.016 U	< 0.022 U	< 0.022 U	< 0.022 U	< 0.028 U	0.037 J	< 0.021 U	< 0.021 U	< 0.44 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.21 U	< 0.27 U	< 0.81 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.043 J	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.016 U	< 0.022 U	< 0.022 U	< 0.022 U	< 0.028 U	0.051 J	< 0.021 U	< 0.021 U	< 0.44 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.21 U	< 0.27 U	< 0.81 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.016 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	0.028 J	< 0.021 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.055 J	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	0.44	0.08 J	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.071 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.05 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated	< 0.3 U	< 0.28 U	0.036 J	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.53	0.12	< 0.019 U	< 0.41 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.22	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.12	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.18	0.05 J	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.11	< 0.018 U	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.048 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.77 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.037 J	< 0.019 U	< 0.019 U	< 0.41 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.013 U	< 0.015 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.012 U	< 0.15 U	< 0.2 U	< 0.59 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.021 U	< 0.027 U	0.079 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.056 J	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.3 U	< 0.29 U	0.039 J	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.37	0.081 J	0.035 J	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.035 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.026 U	0.054 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated	< 0.29 U	< 0.27 U	0.02 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.19	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.14	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.012 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.6 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.028 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	0.11 J	< 0.021 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 UJ	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.037 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.77 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated	< 0.32 U	< 0.3 U	0.028 J	< 0.016 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	0.63	0.15	< 0.02 U	< 0.44 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.81 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.063 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	0.12	< 0.021 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated	< 0.32 U	< 0.3 U	< 0.021 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	0.23	< 0.021 U	< 0.02 U	< 0.43 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.79 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.067 J	< 0.02 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.07 J	< 0.02 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated	< 0.3 U	< 0.28 U	0.037 J	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.026 U	0.73	0.16	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.18	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.045 J	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.015 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.012 U	< 0.15 U	< 0.2 U	< 0.59 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated	0.35 J	< 0.32 U	0.035 J	< 0.016 U	< 0.023 U	< 0.023 U	< 0.023 U	< 0.03 U	0.32	0.063 J	< 0.022 U	< 0.46 U	< 0.038 U	< 0.17 U	< 0.031 U	< 0.018 U	< 0.22 U	< 0.29 U	< 0.85 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated	0.32 J	< 0.3 U	< 0.022 U	< 0.015 UJ	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	0.071 J	< 0.021 U	< 0.02 U	< 0.43 U	< 0.035 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.79 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated	0.28 J	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.048 J	< 0.018 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	0.36 J	< 0.23 U	< 0.69 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.12	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.064 J	< 0.12 U	< 0.13 U	< 0.022 U	0.022 J		0.022 J
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.053 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.029 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.13 U	0.11	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.07 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		0.016 J
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.041 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	< 0.018 U	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.067 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.03 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.058 J	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	0.026 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.033 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	< 0.018 UJ	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated	< 0.022 U	< 0.94 U	< 0.017 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated	< 0.022 U	< 0.96 U	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.032 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	< 0.018 U	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.097	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	0.079 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		0.063 J
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.026 J	< 0.017 U	< 0.03 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.017 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.017 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.18	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.074 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated	< 0.027 U	< 1.2 U	< 0.021 U			< 0.13 U	0.069 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.043 J	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.42	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.19	< 0.13 U	< 0.13 U	< 0.022 U	0.047 J		0.041 J
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.051 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.02 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.058 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.026 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.12 U	0.037 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.016 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated	< 0.026 U	< 1.2 U	< 0.021 U			< 0.13 U	0.15	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.13	< 0.12 U	< 0.13 U	< 0.022 U	0.035 J		0.13
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.11	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	0.091	< 0.12 U	< 0.12 U	< 0.021 U	0.051 J		0.15
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.044 J	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	< 0.018 U	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		0.058 J
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.13 U	0.037 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.017 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		0.023 J
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.038 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.045 U	< 0.022 U	< 0.018 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		0.019 J
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated	< 0.029 U	< 1.2 U	< 0.023 U			< 0.14 U	0.085 J	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.038 J	< 0.13 U	< 0.14 U	< 0.024 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.7	0.039 J	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.2	< 0.13 U	< 0.13 U	< 0.023 U	0.039 J		0.057 J
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.059 J	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.027 J	< 0.13 U	< 0.14 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.073 J	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.03 J	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.017 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated	< 0.029 U	< 1.3 U	< 0.023 U			< 0.15 U	0.051 J	< 0.019 U	< 0.034 U	< 0.028 U	< 0.048 U	< 0.024 U	0.023 J	< 0.14 U	< 0.14 U	< 0.024 U	< 0.023 U		< 0.018 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated	< 0.027 U	< 1.2 U	< 0.021 U			< 0.13 U	0.21	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.13	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		0.019 J
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.066 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.038 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated	< 0.026 U	< 1.2 U	< 0.021 U			< 0.13 U	0.31	0.022 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.079 J	< 0.12 U	< 0.13 U	< 0.022 U	0.045 J		0.07 J
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.54	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.31	< 0.12 U	< 0.12 U	< 0.022 U	0.038 J		0.15
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	1	0.056 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.43	< 0.12 U	< 0.12 U	< 0.022 U	0.046 J		0.18
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated	< 0.029 U	< 1.3 U	< 0.023 U			< 0.15 U	0.047 J	< 0.018 U	< 0.034 U	< 0.027 U	< 0.048 U	< 0.024 U	< 0.019 U	< 0.13 U	< 0.14 U	< 0.024 U	< 0.023 U		0.029 J
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated	< 0.027 U	< 1.2 U	< 0.021 U			< 0.13 U	0.062 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.042 J	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		0.035 J
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated	< 0.029 U	< 1.3 U	< 0.023 U			< 0.15 U	0.078 J	< 0.018 U	< 0.034 U	< 0.027 U	< 0.048 U	< 0.024 U	0.039 J	< 0.13 U	< 0.14 U	< 0.024 U	< 0.022 U		0.023 J
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated	< 0.029 U	< 1.3 U	< 0.023 U			< 0.15 U	0.049 J	< 0.018 U	< 0.033 U	< 0.027 U	< 0.048 U	< 0.024 U	0.022 J	< 0.13 U	< 0.14 U	< 0.024 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.082 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	0.03 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.029 U	< 1.2 U	< 0.023 U			< 0.14 U	0.55	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.22	< 0.13 U	< 0.14 U	< 0.024 U	0.022 J		0.035 J
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.068 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.04 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated	< 0.023 U	< 1 U	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.061 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.029 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.61	0.018 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.39	< 0.12 U	< 0.13 U	< 0.022 U	0.034 J		0.074 J
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.33	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.17	< 0.12 U	< 0.13 U	< 0.022 U	0.024 J		0.056 J
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated	< 0.027 U	< 1.2 U	< 0.021 U			< 0.13 U	0.15	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.089	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		0.039 J
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.13 U	0.25	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.15	< 0.12 U	< 0.12 U	< 0.021 U	0.02 J		0.053 J
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.13 U	0.15	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.097	< 0.12 U	< 0.12 U	< 0.021 U	0.021 J		0.079 J
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.072 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	< 0.018 U	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		0.038 J
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.052 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.031 J	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated	< 0.021 U	< 0.92 U	< 0.017 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.014 U	< 0.098 U	< 0.1 U	< 0.018 U	< 0.016 U		< 0.013 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.098	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.074 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		0.019 J
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.13 U	0.083	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.052 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		0.045 J
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.66	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.26	< 0.13 U	< 0.13 U	< 0.022 U	0.06 J		0.18
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.042 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.025 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.064 J	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	0.033 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.28	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.15	< 0.12 U		< 0.021 U	0.029 J	< 0.12 U	0.072 J
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.21	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	0.13	< 0.12 U	< 0.12 U	< 0.021 U	0.024 J		0.058 J
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated	< 0.022 U	< 0.94 U	< 0.017 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.048 J	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	< 0.018 U	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated	< 0.029 U	< 1.3 U	< 0.023 U			< 0.15 U	0.13	< 0.018 U	< 0.033 U	< 0.027 U	< 0.048 U	< 0.024 U	0.056 J	< 0.13 U	< 0.14 U	< 0.024 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.049 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	< 0.018 U	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated	< 0.029 U	< 1.3 U	< 0.023 U			< 0.15 U	0.73	0.027 J	< 0.034 U	< 0.027 U	< 0.048 U	< 0.024 U	0.42	< 0.13 U	< 0.14 U	< 0.024 U	0.046 J		0.051 J
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.067 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.036 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated	< 0.029 U	< 1.2 U	< 0.023 U			< 0.14 U	0.2	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.053 J	< 0.13 U	< 0.14 U	< 0.024 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.26	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.16	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.079 J	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	0.028 J	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.097	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.043 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.66	0.028 J	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	0.46	< 0.13 U	< 0.13 U	< 0.022 U	0.034 J		0.053 J
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.12 U	0.25	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	0.13	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.023 U	< 1 U	< 0.019 U			< 0.12 U	0.24	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.099	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.016 J
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.067 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	0.039 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		0.016 J
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated	< 0.021 U	< 0.92 U	< 0.017 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.016 U		< 0.013 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated	< 0.031 U	< 1.3 U	< 0.025 U			< 0.15 U	0.62	< 0.019 U	< 0.035 U	< 0.029 U	< 0.05 U	< 0.025 U	0.19	< 0.14 U	< 0.14 U	< 0.025 U	< 0.024 U		< 0.019 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.11	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.047 J	< 0.13 U	< 0.14 U	< 0.023 U	< 0.022 U		0.024 J
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.12 U	0.1	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.033 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2-Nitroaniline	**3-Nitroaniline**	**4-Nitroaniline**	**Nitrobenzene**	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**	**Pyridine**	**1,2,4,5-Tetrachlorobenzene**	**2,3,4,6-Tetrachlorophenol**	**2,4,5-Trichlorophenol**	**2,4,6-Trichlorophenol**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.8	100	0.33	100					
Restricted - Residential																	6.7	100	100	100					
Protection of Groundwater																	0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																		
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0-0.17	8/29/2019	851.95	0 - 0.17 ft	180-95006-3	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.035 J	< 0.13 U	0.17		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3016-SUB-0-0.17	8/27/2019	852.36	0 - 0.17 ft	180-94829-1	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	0.044 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0-0.17	8/26/2019	852.58	0 - 0.17 ft	180-94754-3	Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.033 J	< 0.12 U	0.11		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0-0.17	8/29/2019	853.88	0 - 0.17 ft	180-95024-2	Excavated	< 0.21 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.14 U	0.043 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0-0.17	8/29/2019	853.85	0 - 0.17 ft	180-95006-3	Excavated	< 0.21 U	< 0.11 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.033 J	< 0.14 U	0.07 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0-0.17	8/29/2019	853.28	0 - 0.17 ft	180-95006-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	< 0.023 U	< 0.13 U	0.059 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0-0.17	9/4/2019	852.90	0 - 0.17 ft	180-95165-4	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	< 0.024 U	< 0.13 U	0.026 J		< 0.019 U	< 0.18 U	< 0.032 U	< 0.024 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0-0.17	8/28/2019	853.35	0 - 0.17 ft	180-94903-1	Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0-0.17	8/28/2019	853.51	0 - 0.17 ft	180-94902-3	Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0-0.17	8/27/2019	853.78	0 - 0.17 ft	180-94829-1	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.13 U	0.027 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0-0.17	8/27/2019	853.82	0 - 0.17 ft	180-94829-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.037 J	< 0.13 U	0.092		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0-0.17	8/26/2019	854.09	0 - 0.17 ft	180-94754-2	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	0.025 J		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0-0.17	8/26/2019	853.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.046 J	< 0.13 U	0.2		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0-0.17	8/26/2019	853.76	0 - 0.17 ft	180-94754-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	0.069 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0-0.17	8/29/2019	854.48	0 - 0.17 ft	180-95024-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.16	< 0.13 U	0.46		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0-0.17	8/29/2019	854.59	0 - 0.17 ft	180-95006-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	< 0.024 U	< 0.13 U	0.053 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0-0.17	8/28/2019	854.13	0 - 0.17 ft	180-94903-1	Excavated	< 0.21 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.72 U	0.026 J	< 0.14 U	0.052 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0-0.17	8/27/2019	854.60	0 - 0.17 ft	180-94829-1	Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.032 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0-0.17	8/27/2019	855.22	0 - 0.17 ft	180-94829-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.069 J	< 0.13 U	0.16		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0-0.17	8/26/2019	855.08	0 - 0.17 ft	180-94754-2	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.071 J	< 0.13 U	0.11		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0-0.17	8/26/2019	855.17	0 - 0.17 ft	180-94754-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.026 J	< 0.13 U	0.038 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0-0.17	8/26/2019	855.10	0 - 0.17 ft	180-94752-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	0.031 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0-0.17	8/26/2019	854.81	0 - 0.17 ft	180-94752-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	< 0.023 U	< 0.13 U	0.034 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0-0.17	8/29/2019	855.09	0 - 0.17 ft	180-95024-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.074 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.027 J	< 0.14 U	0.078 J		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0-0.17	8/29/2019	855.60	0 - 0.17 ft	180-95006-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.51	< 0.14 U	0.62		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0-0.17	8/29/2019	855.76	0 - 0.17 ft	180-95006-3	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	< 0.025 U	< 0.14 U	0.061 J		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0-0.17	8/29/2019	855.85	0 - 0.17 ft	180-95006-3	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.035 J	< 0.13 U	0.072 J		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0-0.17	8/28/2019	855.10	0 - 0.17 ft	180-94903-1	Excavated	< 0.22 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.075 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.76 U	< 0.025 U	< 0.14 U	0.043 J		< 0.02 U	< 0.2 U	< 0.034 U	< 0.026 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0-0.17	8/28/2019	855.17	0 - 0.17 ft	180-94903-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.063 J	< 0.13 U	0.24		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0-0.17	8/28/2019	855.23	0 - 0.17 ft	180-94903-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.026 J	< 0.13 U	0.066 J		< 0.019 U	< 0.18 U	< 0.032 U	< 0.024 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0-0.17	8/27/2019	855.78	0 - 0.17 ft	180-94829-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.25	< 0.13 U	0.3		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0-0.17	8/27/2019	856.00	0 - 0.17 ft	180-94829-1	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.17	< 0.13 U	0.55		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0-0.17	8/27/2019	856.03	0 - 0.17 ft	180-94829-1	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.55	< 0.13 U	0.93		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0-0.17	8/26/2019	856.22	0 - 0.17 ft	180-94754-2	Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.075 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.75 U	0.025 J	< 0.14 U	0.045 J		< 0.02 U	< 0.2 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0-0.17	8/26/2019	856.08	0 - 0.17 ft	180-94754-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.028 J	< 0.13 U	0.056 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0-0.17	8/26/2019	856.17	0 - 0.17 ft	180-94754-2	Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.075 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.75 U	0.029 J	< 0.14 U	0.067 J		< 0.02 U	< 0.2 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0-0.17	8/26/2019	855.60	0 - 0.17 ft	180-94752-1	Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.074 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.75 U	< 0.025 U	< 0.14 U	0.041 J		< 0.02 U	< 0.19 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.024 J	< 0.13 U	0.076 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.074 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.14	< 0.14 U	0.63		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0-0.17	8/29/2019	856.41	0 - 0.17 ft	180-95006-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.037 J	< 0.13 U	0.072 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0-0.17	8/29/2019	856.01	0 - 0.17 ft	180-95006-3	Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0-0.17	8/28/2019	856.20	0 - 0.17 ft	180-94903-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.026 J	< 0.13 U	0.059 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0-0.17	8/28/2019	855.88	0 - 0.17 ft	180-94902-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	0.16	< 0.13 U	0.69		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0-0.17	8/28/2019	856.09	0 - 0.17 ft	180-94903-1	Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.14	< 0.13 U	0.33		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0-0.17	8/27/2019	856.47	0 - 0.17 ft	180-94829-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.058 J	< 0.13 U	0.16		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0-0.17	8/27/2019	856.71	0 - 0.17 ft	180-94829-1	Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.086	< 0.12 U	0.26		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0-0.17	8/27/2019	856.96	0 - 0.17 ft	180-94829-1	Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.053 J	< 0.12 U	0.15		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0-0.17	8/26/2019	857.02	0 - 0.17 ft	180-94754-2	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.027 J	< 0.13 U	0.064 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.024 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	0.026 J	< 0.13 U	0.047 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0-0.17	8/26/2019	856.95	0 - 0.17 ft	180-94754-3	Excavated	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94754-1	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.037 J	< 0.13 U	0.095		< 0.019 U	< 0.18 U	< 0.032 U	< 0.024 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0-0.17	8/26/2019	856.77	0 - 0.17 ft	180-94752-3	Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.033 J	< 0.12 U	0.074 J		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.3	< 0.13 U	0.59		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0-0.17	8/29/2019	856.40	0 - 0.17 ft	180-95006-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	< 0.024 U	< 0.14 U	0.044 J		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0-0.17	8/29/2019	856.38	0 - 0.17 ft	180-95006-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.023 J	< 0.13 U	0.068 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	8/27/2019	857.14	0 - 0.17 ft	180-94829-2	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.11	< 0.13 U	0.26		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0-0.17	8/27/2019	857.18	0 - 0.17 ft	180-94829-2	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.078 J	< 0.13 U	0.2		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0-0.17	8/26/2019	856.92	0 - 0.17 ft	180-94754-3	Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0-0.17	8/26/2019	856.86	0 - 0.17 ft	180-94752-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	< 0.024 U	< 0.13 U	0.039 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0-0.17	8/29/2019	856.36	0 - 0.17 ft	180-95006-3	Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.074 U	< 0.33 U		< 0.032 U	< 0.15 U	< 0.75 U	0.061 J	< 0.14 U	0.14 J		< 0.02 U	< 0.19 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0-0.17	8/29/2019	856.58	0 - 0.17 ft	180-95024-2	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	0.028 J	< 0.14 U	0.038 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/28/2019	856.73	0 - 0.17 ft	180-94903-1	Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.074 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.75 U	0.18	< 0.14 U	0.81		< 0.02 U	< 0.19 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0-0.17	8/29/2019	856.73	0 - 0.17 ft	180-95006-2	Excavated	< 0.21 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.072 U	< 0.32 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.14 U	0.068 J		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0-0.17	8/29/2019	857.13	0 - 0.17 ft	180-95006-3	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.074 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.12	< 0.14 U	0.19		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0-0.17	8/28/2019	856.55	0 - 0.17 ft	180-94903-1	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.085 J	< 0.14 U	0.29		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.04 J	< 0.13 U	0.087 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0-0.17	8/29/2019	857.77	0 - 0.17 ft	180-95006-3	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.048 J	< 0.14 U	0.1		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0-0.17	8/29/2019	857.68	0 - 0.17 ft	180-95006-2	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.12	< 0.13 U	0.88		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0-0.17	8/27/2019	857.12	0 - 0.17 ft	180-94829-2	Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.078 J	< 0.12 U	0.24		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0-0.17	8/26/2019	855.86	0 - 0.17 ft	180-94754-2	Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.097	< 0.11 U	0.22		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0-0.17	8/26/2019	856.19	0 - 0.17 ft	180-94754-3	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.026 J	< 0.13 U	0.066 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0-0.17	8/26/2019	855.97	0 - 0.17 ft	180-94754-1	Excavated	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0-0.17	1/19/2020	857.05	0 - 0.17 ft	180-101269-1	Excavated	< 0.23 U	< 0.13 U	< 0.024 U	< 0.18 U	< 0.079 U	< 0.35 U		< 0.033 U	< 0.16 U	< 0.79 U	0.25	< 0.15 U	0.61		< 0.021 U	< 0.21 U	< 0.035 U	< 0.027 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0-0.17	1/19/2020	857.55	0 - 0.17 ft	180-101269-1	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.042 J	< 0.14 U	0.13		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0-0.17	1/19/2020	856.32	0 - 0.17 ft	180-101269-1	Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.051 J	< 0.12 U	0.11		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated			3.634	< 0.026 U	0.045 J	< 0.024 U	0.088 J	< 0.2 U	< 0.019 U	< 0.056 U	0.34	0.32	0.38	0.14	0.22	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated			0.499	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	0.041 J	0.048 J	0.065 J	0.025 J	0.042 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated			1.588	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	0.13	0.15	0.19	0.064 J	0.13	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated			1.657	< 0.031 U	< 0.024 U	< 0.03 U	< 0.028 U	< 0.24 U	< 0.023 U	< 0.068 U	0.13	0.15	0.21	0.076 J	0.14	< 0.026 U	< 0.02 U	< 0.04 U	0.6 J	< 0.038 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated			1.706	< 0.023 U	< 0.018 U	< 0.022 U	0.046 J	< 0.18 U	< 0.017 U	< 0.05 U	0.16	0.13	0.15	0.063 J	0.1	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated			19.365	0.034 J	0.97	< 0.025 U	0.49	< 0.2 U	< 0.019 U	< 0.057 U	1.8	1.9	2.6	0.95	1.5	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated			3.399	0.012 J	0.036 J	< 0.01 U	0.069	< 0.081 U	< 0.0077 U		0.24	0.25	0.27	0.12	0.25	< 0.0088 U	< 0.0067 U	< 0.014 U	< 0.2 U	< 0.013 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated			0.389	< 0.027 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U		0.037 J	0.038 J	0.048 J	< 0.028 U	0.038 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated			0.896	< 0.026 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.056 U	0.082 J	0.085 J	0.12	0.042 J	0.065 J	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated			3.761	< 0.025 U	0.098	< 0.024 U	0.073 J	< 0.19 U	< 0.019 U	< 0.055 U	0.34	0.3	0.47	0.17	0.27	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated			0.914	< 0.026 U	0.035 J	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U		0.091 J	0.092	0.11	0.058 J	0.077 J	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated			0.828	< 0.026 U	0.04 J	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	0.077 J	0.082 J	0.12	0.044 J	0.072 J	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated			5.24	< 0.027 U	0.29	< 0.026 U	0.19	< 0.21 U	< 0.02 U	< 0.059 U	0.49	0.47	0.69	0.2	0.42	< 0.023 U	< 0.017 U	< 0.035 U	< 0.51 U	< 0.033 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-0-0.17	12/19/2019	857.57	0 - 0.17 ft	180-100363-3	Excavated			13.33	< 0.029 U	0.75 J	< 0.027 U	0.35 J	< 0.22 U	0.023 J		1.2 J	1.4 J	1.8 J	0.66 J	1.2 J	< 0.024 U	< 0.018 U	< 0.037 U	< 0.53 U	< 0.035 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	1/23/2020	857.44	0 - 0.17 ft	180-101497-4	Excavated			2.822	< 0.028 U	0.15	< 0.026 U	0.064 J	< 0.21 U	< 0.02 U		0.26	0.28	0.38	0.12	0.24	< 0.023 U	< 0.018 U	< 0.036 U	< 0.52 U	< 0.034 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0-0.17	12/19/2019	858.02	0 - 0.17 ft	180-100363-2	Excavated			2.154	< 0.028 U	0.15	< 0.026 U	0.067 J	< 0.21 U	< 0.02 U	< 0.06 U	0.19	0.22	0.32	0.1	0.2	< 0.023 U	< 0.017 U	< 0.036 U	< 0.51 U	< 0.034 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	1/23/2020	857.46	0 - 0.17 ft	180-101497-4	Excavated			5.5	< 0.028 U	0.25	< 0.026 U	0.14	< 0.21 U	< 0.02 U		0.51	0.51	0.65	0.24	0.41	< 0.023 U	< 0.018 U	< 0.036 U	< 0.52 U	< 0.034 U
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0-0.17	12/18/2019	856.31	0 - 0.17 ft	180-100380-2	Excavated			38.14	0.15 J	2.8	< 0.061 U	1.4	< 0.49 U	< 0.047 U	< 0.14 U	3.3	3.5	4.7	1.5	3.1	< 0.053 U	< 0.041 U	< 0.083 U	< 1.2 U	< 0.078 U
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0-0.17	12/18/2019	857.03	0 - 0.17 ft	180-100380-2	Excavated			10.647	< 0.026 U	0.72	< 0.025 U	0.4	< 0.2 U	< 0.019 U	< 0.056 U	0.9	0.96	1.3	0.45	0.88	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0-0.17	12/18/2019	857.52	0 - 0.17 ft	180-100380-2	Excavated			14.19	< 0.029 U	0.88	< 0.027 U	0.44	< 0.22 U	< 0.021 U	< 0.063 U	1.3	1.3	1.7	0.61	1.1	< 0.024 U	< 0.018 U	< 0.038 U	< 0.54 U	< 0.035 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated			26.654	0.12	0.83	< 0.025 U	1.3	< 0.2 U	0.023 J	< 0.057 U	2.3	1.8	1.8	0.78	0.99	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated			26.654	0.12	0.83	< 0.025 U	1.3	< 0.2 U	0.023 J	< 0.057 U	2.3	1.8	1.8	0.78	0.99	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0-0.17	7/28/2020	858.45	0 - 0.17 ft	180-108872-1	Excavated			6.756	< 0.026 U	0.34	< 0.024 U	0.2	< 0.2 U	< 0.019 U	< 0.056 U	0.58	0.62	0.78	0.3	0.57	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0-0.17	7/28/2020	858.43	0 - 0.17 ft	180-108872-1	Excavated			166.7	0.33 J	7.3	< 0.23 U	4.1	< 1.9 U	< 0.18 U	< 0.53 U	14	16	20	7.2	12	< 0.2 U	< 0.15 U	< 0.31 U	< 4.5 U	< 0.3 U
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0-0.17	7/28/2020	858.58	0 - 0.17 ft	180-108872-1	Excavated			3.595	< 0.025 U	0.24	< 0.023 U	0.11	< 0.19 U	< 0.018 U	< 0.053 U	0.32	0.34	0.43	0.14	0.27	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0-0.17	7/28/2020	856.51	0 - 0.17 ft	180-108872-1	Excavated			0.686	< 0.023 U	0.02 J	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.061 J	0.076 J	0.1	0.029 J	0.079 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0-0.17	7/28/2020	857.00	0 - 0.17 ft	180-108872-1	Excavated			0.264	< 0.022 U	0.025 J	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	0.04 J	0.048 J	< 0.023 U	0.059 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0-0.17	7/28/2020	856.50	0 - 0.17 ft	180-108872-1	Excavated			2.727	< 0.022 U	0.033 J	< 0.02 U	0.067 J	< 0.16 U	< 0.016 U	< 0.046 U	0.2	0.21	0.26	0.083	0.18	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0-0.17	7/28/2020	858.42	0 - 0.17 ft	180-108872-1	Excavated			161.35	0.43 J	8.5	< 0.22 U	4.5	< 1.8 U	< 0.17 U	< 0.5 U	14	15	19	6.7	12	< 0.19 U	< 0.15 U	< 0.3 U	< 4.3 U	< 0.28 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	1/14/2021	858.30	0 - 0.17 ft	180-116002-2	Excavated			2.247	0.024	0.079	0.022	0.038	0.18	0.017	0.051	0.21	0.2	0.22	0.13	0.16	0.02	0.015	0.031	0.44	0.029
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0-0.17	1/14/2021	858.39	0 - 0.17 ft	180-116002-2	Excavated			193.99	0.46	8.8	0.12	4.1	0.95	0.11	0.27	17	16	21	6.7	14	0.1	0.079	0.16	2.3	0.15
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0-0.17	1/14/2021	858.31	0 - 0.17 ft	180-116002-2	Excavated			52.22	0.13	1.8	0.023	1.2	0.18	0.018	0.052	4.6	4.5	5.5	2.1	3.7	0.02	0.015	0.031	0.45	0.029
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated			0.609	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.05 U	0.055 J	0.048 J	0.072 J	0.034 J	0.039 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated			0.045	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated			0.055	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated			ND	< 0.42 U	< 0.42 U		< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated			0.411	< 0.0071	0.039	< 0.03	0.02	< 0.036	< 0.033	< 0.055	0.058	0.07	< 0.012	< 0.015	< 0.0073	< 0.024	< 0.0099	< 0.0079	< 0.059	< 0.032
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated			2.64		0.092 J		0.11 J				0.21 J	0.29 J	0.47	0.18 J	0.23 J				0.53	
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated			ND	< 0.41 U	< 0.41 U		< 0.41 U				< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	0 - 0.17 ft	180-123985-1	Not Excavated			0.826	< 0.023 U	< 0.017 U	< 0.021 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.074 J	0.082	0.11	0.038 J	0.061 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated			0.083	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated			1.184	< 0.022 U	0.054 J	< 0.021 U	0.032 J	< 0.17 U	< 0.016 U	< 0.047 U	0.094	0.13	0.16	0.05 J	0.12	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated			9.04	< 0.034 U	0.19 J	< 0.034 U	0.21 J	< 0.36 U	< 0.034 U	< 0.55 U	0.81	0.78	0.98	0.43 J	0.7 J	< 0.24 U	< 0.099 U	< 0.08 U	< 0.6 U	< 0.32 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated			3.321	< 0.022 U	0.11	< 0.021 U	0.092	< 0.17 U	< 0.016 U	< 0.048 U	0.27	0.38	0.65	0.15	0.37	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated			4.126	< 0.022 U	0.1	< 0.021 U	0.094	< 0.17 U	< 0.016 U	< 0.048 U	0.33	0.43	0.66	0.2	0.35	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated			0.583	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.05 J	0.062 J	0.086	0.031 J	0.052 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated			0.44	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.043 J	0.046 J	0.061 J	0.028 J	0.045 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated			0.312	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.034 J	0.046 J	< 0.018 U	< 0.022 U	0.039 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated			0.338	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.036 J	0.043 J	0.055 J	0.028 J	0.039 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated			ND	< 0.067	< 0.08	< 0.29	< 0.068	< 0.34	< 0.31	< 0.52	< 0.088	< 0.07	< 0.11	< 0.14	< 0.07	< 0.23	< 0.094	< 0.075	< 0.57	< 0.3
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	0 - 0.17 ft	180-57995-1	Not Excavated			6.951	< 0.034 U	0.11 J	< 0.034 U	0.19 J	< 0.039 U	< 0.034 U	< 0.034 U	0.64 J	0.61 J	0.72 J	0.32	0.5	< 0.026 U	< 0.011 U	< 0.0087 U	< 0.065 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	PS-FD-39	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated			2.574	< 0.034 U	< 0.0096 U	< 0.034 U	0.024 J	< 0.041 U	< 0.034 U	< 0.063 U	0.19	0.24	0.35	0.12	0.24	< 0.027 U	< 0.011 U	< 0.009 U	0.4 J	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SS	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated			2.409	< 0.034 U	< 0.0098 U	< 0.034 U	0.028 J	< 0.042 U	< 0.034 U	< 0.064 U	0.18	0.21	0.28	0.15	0.18	< 0.028 U	< 0.011 U	< 0.0092 U	0.13 J	< 0.037 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated			ND	< 0.39	< 0.39		< 0.39				< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated			0.151	< 0.034 U	< 0.0091 U	< 0.034 U	< 0.0078 U	< 0.039 U	< 0.034 U	< 0.06 U	< 0.034 U	< 0.034 U	< 0.013 U	< 0.016 U	< 0.0079 U	< 0.026 U	< 0.011 U	< 0.0086 U	< 0.064 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated			0.415	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.049 U	0.044 J	0.039 J	0.053 J	0.027 J	0.042 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated			1.278	< 0.41	< 0.41		< 0.41				0.11	0.13	0.12	0.13	0.11	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated			3.958	0.017 J	0.031 J	< 0.034 U	0.086	< 0.038 U	< 0.034 U	< 0.058 U	0.39	0.33	0.4	0.21	0.22	< 0.025 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated			ND	< 0.37	< 0.37		< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated			0.199	< 0.0078 U	0.011 J	< 0.034 U	0.013 J	< 0.04 U	< 0.036 U	< 0.061 U	< 0.01 U	< 0.0082 U	< 0.013 U	< 0.016 U	< 0.0081 U	< 0.027 U	< 0.011 U	< 0.0088 U	< 0.066 U	< 0.035 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated			2.079	0.02 J	0.034 J	< 0.032 U	0.07 J	< 0.038 U	< 0.035 U	< 0.059 U	0.19	0.16	0.2	0.12	0.13	< 0.026 U	< 0.011 U	< 0.0085 U	< 0.064 U	< 0.034 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated			ND	< 0.42	< 0.42		< 0.42				< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated			0.302	< 0.0074 U	0.019 J	< 0.031 U	0.015 J	< 0.037 U	< 0.034 U	< 0.057 U	0.048 J	< 0.0077 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.033 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated			1.681	< 0.007 U	0.039 J	< 0.03 U	0.037 J	< 0.035 U	< 0.032 U	< 0.054 U	0.14	0.14	0.19	0.074	0.13	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated			0.163	< 0.43	< 0.43		< 0.43				< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated			13.43	0.16	0.33	< 0.031 U	0.49	< 0.037 U	< 0.034 U	< 0.057 U	1.1	1.1	1.4	0.55	0.99	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated			ND	< 0.43	< 0.43		< 0.43				< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated			12.11	< 0.43	0.44		0.37				1.1	1.4	1.1	1.1	1.2	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	7/21/2014	856.74	0 - 0.17 ft	180-35053-1	Excavated			9.838	0.015	0.37	0.0085	0.29	< 0.0074	< 0.0067	< 0.011	0.9	0.84	1.1	0.48	0.82	< 0.005	< 0.002	< 0.0016	0.035	< 0.0066
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated			ND	< 0.44	< 0.44		< 0.44				< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated			ND		< U		< U				< U	< U	< U	< U	< U				1.1	
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated			ND	< 0.42 U	< 0.42 U		< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ethe	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated	< 0.31 U	< 0.29 U	0.021 J	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.33	0.059 J	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated	0.29 J	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.051 J	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated	0.65	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.15	0.033 J	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	0.2 J	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated	0.56	< 0.35 U	< 0.025 U	< 0.018 U	< 0.026 U	< 0.025 U	< 0.025 U	< 0.033 U	0.16	0.036 J	< 0.024 U	< 0.51 U	< 0.042 U	< 0.19 U	< 0.034 U	< 0.02 U	< 0.24 U	< 0.32 U	< 0.94 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated	0.3 J	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	0.15	0.029 J	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated	< 0.32 U	< 0.3 U	0.086 J	< 0.015 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	2.3	0.39	0.029 J	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated	< 0.13 U	< 0.12 U	0.062	< 0.0061 U	< 0.0087 U	< 0.0085 U	< 0.0086 U	< 0.011 U	0.26	0.077	0.0081 J	< 0.17 U	< 0.014 U	< 0.065 U	< 0.011 U	< 0.0067 U	< 0.081 U	< 0.11 U	< 0.32 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	0.051 J	< 0.021 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated	< 0.31 U	< 0.3 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.1	< 0.02 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated	< 0.3 U	< 0.29 U	0.031 J	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.42	0.066 J	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.26 U	< 0.76 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.015 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	0.11	< 0.021 U	< 0.02 U	< 0.43 U	< 0.035 U	< 0.16 U	< 0.029 U	< 0.017 U	< 0.2 U	< 0.27 U	< 0.79 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.098	< 0.02 U	< 0.02 U	< 0.42 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.77 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated	< 0.33 U	< 0.31 U	0.036 J	< 0.016 U	< 0.022 U	< 0.022 U	< 0.022 U	< 0.029 U	0.53	0.11	< 0.021 U	< 0.44 U	< 0.037 U	< 0.17 U	< 0.029 U	< 0.017 U	< 0.21 U	< 0.28 U	< 0.82 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-0-0.17	12/19/2019	857.57	0 - 0.17 ft	180-100363-3	Excavated	< 0.34 U	< 0.32 U	0.061 J	< 0.016 U	< 0.023 U	< 0.023 U	< 0.023 U	< 0.03 U	1.4 J	0.36 J	0.045 J	< 0.46 U	< 0.038 U	< 0.17 U	< 0.031 U	< 0.018 U	< 0.22 U	< 0.29 U	< 0.85 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	1/23/2020	857.44	0 - 0.17 ft	180-101497-4	Excavated	< 0.33 U	< 0.32 U	< 0.023 U	< 0.016 U	< 0.023 U	< 0.022 U	< 0.023 U	< 0.029 U	0.29	0.13	< 0.021 U	< 0.45 U	< 0.037 U	< 0.17 U	< 0.03 U	< 0.018 U	< 0.21 U	< 0.28 U	< 0.84 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0-0.17	12/19/2019	858.02	0 - 0.17 ft	180-100363-2	Excavated	< 0.33 U	< 0.31 U	< 0.023 U	< 0.016 U	< 0.023 U	< 0.022 U	< 0.022 U	< 0.029 U	0.25	< 0.022 U	< 0.021 U	< 0.45 U	< 0.037 U	< 0.17 U	< 0.03 U	< 0.017 U	< 0.21 U	< 0.28 U	< 0.83 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	1/23/2020	857.46	0 - 0.17 ft	180-101497-4	Excavated	< 0.33 U	< 0.32 U	0.032 J	< 0.016 U	< 0.023 U	< 0.022 U	< 0.023 U	< 0.03 U	0.56	0.18	< 0.021 U	< 0.45 U	< 0.038 U	< 0.17 U	< 0.03 U	< 0.018 U	< 0.21 U	< 0.28 U	< 0.84 U
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0-0.17	12/18/2019	856.31	0 - 0.17 ft	180-100380-2	Excavated	< 0.77 U	< 0.73 U	0.27	< 0.037 U	< 0.053 U	< 0.051 U	< 0.052 U	< 0.068 U	3.9	0.8	0.083 J	< 1 U	< 0.086 U	< 0.39 U	< 0.069 U	< 0.041 U	< 0.49 U	< 0.65 U	< 1.9 U
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0-0.17	12/18/2019	857.03	0 - 0.17 ft	180-100380-2	Excavated	< 0.31 U	< 0.3 U	0.096	< 0.015 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.028 U	1.1	0.21	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.016 U	< 0.2 U	< 0.26 U	< 0.78 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0-0.17	12/18/2019	857.52	0 - 0.17 ft	180-100380-2	Excavated	< 0.35 U	< 0.33 U	0.094 J	< 0.017 U	< 0.024 U	< 0.023 U	< 0.024 U	< 0.031 U	1.5	0.3	< 0.022 U	< 0.47 U	< 0.039 U	< 0.18 U	< 0.031 U	< 0.018 U	< 0.22 U	< 0.29 U	< 0.87 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated	< 0.32 U	< 0.3 U	0.3	< 0.031 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	1.9	0.33	0.18 J	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated	< 0.32 U	< 0.3 U	0.3	< 0.031 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	1.9	0.33	0.18 J	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0-0.17	7/28/2020	858.45	0 - 0.17 ft	180-108872-1	Excavated	< 0.31 U	< 0.29 U	0.05 J	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	0.68	0.14	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.033 U	< 0.2 U	< 0.26 U	< 0.77 U
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0-0.17	7/28/2020	858.43	0 - 0.17 ft	180-108872-1	Excavated	< 2.9 U	< 2.8 U	1	< 0.29 U	< 0.2 U	< 0.2 U	< 0.2 U	< 0.26 U	17	2.9	0.31 J	< 4 U	< 0.33 U	< 1.5 U	< 0.26 U	< 0.31 U	< 1.9 U	< 2.5 U	< 7.3 U
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0-0.17	7/28/2020	858.58	0 - 0.17 ft	180-108872-1	Excavated	< 0.3 U	< 0.28 U	0.022 J	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.37	0.13	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0-0.17	7/28/2020	856.51	0 - 0.17 ft	180-108872-1	Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.074 J	< 0.051 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0-0.17	7/28/2020	857.00	0 - 0.17 ft	180-108872-1	Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0-0.17	7/28/2020	856.50	0 - 0.17 ft	180-108872-1	Excavated	< 0.26 U	< 0.24 U	0.041 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.22	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0-0.17	7/28/2020	858.42	0 - 0.17 ft	180-108872-1	Excavated	< 2.7 U	< 2.6 U	1.1	< 0.27 U	< 0.19 U	< 0.18 U	< 0.19 U	< 0.24 U	17	3.1	0.33 J	< 3.7 U	< 0.31 U	< 1.4 U	< 0.25 U	< 0.3 U	< 1.8 U	< 2.3 U	< 6.9 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	1/14/2021	858.30	0 - 0.17 ft	180-116002-2	Excavated	0.28	0.27	0.019	0.028	0.019	0.019	0.019	0.025	0.26	0.053	0.018	0.38	0.032	0.14	0.026	0.031	0.18	0.24	0.71
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0-0.17	1/14/2021	858.39	0 - 0.17 ft	180-116002-2	Excavated	1.5	1.4	1.1	0.15	0.1	0.1	0.1	0.13	19	3.8	0.37	2	0.17	0.77	0.14	0.16	0.95	1.3	3.8
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0-0.17	1/14/2021	858.31	0 - 0.17 ft	180-116002-2	Excavated	0.29	0.27	0.24	0.029	0.02	0.019	0.019	0.025	4.8	1.1	0.076	0.39	0.032	0.15	0.026	0.031	0.18	0.24	0.72
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.06 J	< 0.034 U	< 0.15 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.13 U	< 0.16 U	< 0.034 U	< 0.23 U	< 0.034 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.38 U		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.42 U		< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.1 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	< 0.05	< 0.28	< 0.0068	< 0.029	< 0.034	< 0.0077	< 0.03	< 0.041	0.06	< 0.0082	< 0.036	< 0.039	< 0.0074	0.041	< 0.057	< 0.04	< 0.046	< 0.039	< 0.15
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated									0.25 J										
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.41 U		< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 2.1 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 UJ	< 0.018 U	< 0.018 U	< 0.024 U	0.079	< 0.051 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.73 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.11	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.3 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.83	0.15 J	< 0.36 U	< 0.034 U	< 0.074 U	< 0.034 U	< 0.58 U	< 0.4 U	< 0.034 U	< 0.39 U	< 0.034 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.32	0.09	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.26 U	< 0.25 U	0.041 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.4	0.097	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.063 J	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.048 J	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.043 J	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	0.18 J	< 0.22 U	< 0.67 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated	< 0.48	< 2.6	< 0.064	< 0.28	< 0.32	< 0.073	< 0.29	< 0.39	< 0.083	< 0.078	< 0.34	< 0.37	< 0.07	< 0.38	< 0.55	< 0.38	< 0.44	< 0.37	< 1.4
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.3 U	0.095	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.55 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0081 U	< 0.034 U	< 0.063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	PS-FD-39	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.32 U	0.018 J	< 0.033 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25	< 0.034 U	< 0.041 U	< 0.034 U	< 0.0084 U	< 0.034 U	< 0.065 U	< 0.045 U	0.054 J	< 0.044 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SS	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.32 U	0.029 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.23	< 0.034 U	< 0.042 U	< 0.034 U	< 0.0086 U	< 0.034 U	< 0.067 U	< 0.046 U	< 0.034 U	< 0.045 U	< 0.034 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.39		< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 2
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	< 0.034 U	< 0.3 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0095 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.008 U	< 0.034 U	< 0.062 U	< 0.043 U	< 0.034 U	< 0.042 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.41		< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	0.13	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 2.1
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	< 0.034 U	< 0.29 U	0.037 J	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.37	< 0.034 U	< 0.038 U	< 0.034 U	< 0.0078 U	< 0.034 U	< 0.061 U	< 0.042 U	< 0.034 U	< 0.041 U	< 0.034 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.37		< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 1.9
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated	< 0.056 U	< 0.31 U	< 0.0075 U	< 0.033 U	< 0.038 U	< 0.0085 U	< 0.033 U	< 0.045 U	< 0.0097 U	< 0.0091 U	< 0.04 U	< 0.043 U	< 0.0082 U	< 0.045 U	< 0.064 U	< 0.044 U	< 0.051 U	< 0.043 U	< 0.16 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated	< 0.054 U	< 0.3 U	< 0.0073 U	< 0.032 U	< 0.036 U	< 0.0082 U	< 0.032 U	< 0.044 U	0.16	< 0.0088 U	< 0.039 U	< 0.042 U	< 0.0079 U	< 0.043 U	< 0.062 U	< 0.043 U	< 0.049 U	< 0.041 U	< 0.16 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.42		< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 2.2
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated	< 0.052 U	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.035 U	< 0.008 U	< 0.031 U	< 0.043 U	0.056 J	< 0.0085 U	< 0.038 U	< 0.041 U	< 0.0077 U	0.046 J	< 0.06 U	< 0.042 U	< 0.048 U	< 0.04 U	< 0.15 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated	< 0.05 U	< 0.27 U	0.016 J	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	0.17	0.022 J	< 0.036 U	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.045 U	< 0.038 U	< 0.15 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.43		< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	0.047	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 2.2
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated	< 0.052 U	< 0.29 U	0.16	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	1.2	0.24	0.14 J	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.43		< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 2.2
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.43		0.054	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	1.3	0.36	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 2.2
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	7/21/2014	856.74	0 - 0.17 ft	180-35053-1	Excavated	0.038	< 0.057	0.056	< 0.0061	< 0.007	< 0.0016	< 0.0062	< 0.0084	1.1	0.22	0.018	< 0.008	< 0.0015	< 0.0083	< 0.012	< 0.0082	0.013	< 0.008	< 0.03
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.44		< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 2.3
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated									< U										
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.42 U		< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.2 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3,4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.59	0.019 J	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.19	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		0.028 J
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated	< 0.026 U	< 1.1 U	< 0.021 U			< 0.13 U	0.077 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	0.035 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated	< 0.027 U	< 1.2 U	< 0.021 U			< 0.13 U	0.26	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.1	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated	< 0.034 U	< 1.5 U	< 0.027 U			< 0.17 U	0.27	< 0.021 U	< 0.039 U	< 0.032 U	< 0.056 U	< 0.028 U	0.11	< 0.16 U	< 0.16 U	< 0.028 U	< 0.026 U		< 0.021 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated	< 0.025 U	< 1.1 U	< 0.02 U			< 0.13 U	0.27	0.016 J	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.082	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		< 0.016 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated	< 0.029 U	< 1.2 U	< 0.023 U			< 0.14 U	2.4	0.081 J	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	1.3	< 0.13 U	< 0.14 U	< 0.024 U	0.083 J		0.12
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated	< 0.011 U	< 0.5 U	< 0.0092 U			< 0.058 U	0.71	0.031 J	< 0.013 U	< 0.011 U	< 0.019 U	< 0.0095 U	0.22	< 0.053 U	< 0.054 U	< 0.0094 U	< 0.0089 U		< 0.0072 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated	< 0.029 U	< 1.2 U	< 0.023 U			< 0.14 U	0.053 J	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.025 J	< 0.13 U	< 0.14 U	< 0.024 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.15	< 0.018 U	< 0.033 U	< 0.027 U	< 0.046 U	< 0.023 U	0.06 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated	< 0.027 U	< 1.2 U	< 0.022 U			< 0.14 U	0.6	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	0.2	< 0.13 U	< 0.13 U	< 0.022 U	0.035 J		0.032 J
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	0.13	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.066 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated	< 0.028 U	< 1.2 U	< 0.022 U			< 0.14 U	0.11	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.063 J	< 0.13 U	< 0.13 U	< 0.023 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated	< 0.029 U	< 1.3 U	< 0.024 U			< 0.15 U	0.71	0.035 J	< 0.034 U	< 0.028 U	< 0.049 U	< 0.024 U	0.36	< 0.14 U	< 0.14 U	< 0.024 U	0.039 J		0.065 J
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-0-0.17	12/19/2019	857.57	0 - 0.17 ft	180-100363-3	Excavated	< 0.031 U	< 1.3 U	< 0.025 U			< 0.15 U	1.4 J	0.06 J	< 0.036 U	< 0.029 U	< 0.051 U	< 0.026 U	1.1 J	< 0.14 U	< 0.15 U	< 0.025 U	0.18 J		0.25 J
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	1/23/2020	857.44	0 - 0.17 ft	180-101497-4	Excavated	< 0.03 U	< 1.3 U	< 0.024 U			< 0.15 U	0.33	< 0.019 U	< 0.035 U	< 0.028 U	< 0.05 U	< 0.025 U	0.21	< 0.14 U	< 0.14 U	< 0.025 U	0.031 J		0.033 J
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0-0.17	12/19/2019	858.02	0 - 0.17 ft	180-100363-2	Excavated	< 0.03 U	< 1.3 U	< 0.024 U			< 0.15 U	0.27	< 0.019 U	< 0.035 U	< 0.028 U	< 0.049 U	< 0.025 U	0.17	< 0.14 U	< 0.14 U	< 0.025 U	0.026 J		< 0.019 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	1/23/2020	857.46	0 - 0.17 ft	180-101497-4	Excavated	< 0.03 U	< 1.3 U	< 0.024 U			< 0.15 U	0.73	0.028 J	< 0.035 U	< 0.029 U	< 0.05 U	< 0.025 U	0.38	< 0.14 U	< 0.14 U	< 0.025 U	0.052 J		0.062 J
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0-0.17	12/18/2019	856.31	0 - 0.17 ft	180-100380-2	Excavated	< 0.069 U	< 3 U	< 0.056 U			< 0.35 U	5.3	0.28	< 0.08 U	< 0.065 U	< 0.11 U	< 0.058 U	2.6	< 0.32 U	< 0.33 U	< 0.057 U	0.18 J		0.31
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0-0.17	12/18/2019	857.03	0 - 0.17 ft	180-100380-2	Excavated	< 0.028 U	< 1.2 U	< 0.023 U			< 0.14 U	1.6	< 0.018 U	< 0.033 U	< 0.027 U	< 0.046 U	< 0.023 U	0.71	< 0.13 U	< 0.13 U	< 0.023 U	0.045 J		0.057 J
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0-0.17	12/18/2019	857.52	0 - 0.17 ft	180-100380-2	Excavated	< 0.031 U	< 1.4 U	< 0.025 U			< 0.16 U	2	0.09 J	< 0.036 U	< 0.03 U	< 0.052 U	< 0.026 U	0.93	< 0.15 U	< 0.15 U	< 0.026 U	0.049 J		0.07 J
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated	< 0.029 U	< 2.6 U	< 0.07 U			< 0.14 U	5.3	0.37	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.97	< 0.13 U	< 0.14 U	< 0.024 U	0.036 J		0.094
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated	< 0.029 U	< 2.6 U	< 0.07 U			< 0.14 U	5.3	0.37	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	0.97	< 0.13 U		< 0.024 U	0.036 J	< 0.14 U	0.094
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0-0.17	7/28/2020	858.45	0 - 0.17 ft	180-108872-1	Excavated	< 0.028 U	< 2.5 U	< 0.068 U			< 0.14 U	0.98	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	0.44	< 0.13 U	< 0.13 U	< 0.023 U	0.042 J		0.066 J
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0-0.17	7/28/2020	858.43	0 - 0.17 ft	180-108872-1	Excavated	< 0.26 U	< 24 U	< 0.64 U			< 1.3 U	26	0.77 J	< 0.3 U	< 0.25 U	< 0.43 U	< 0.22 U	9.6	< 1.2 U	< 1.2 U	< 0.22 U	0.77 J		1.2
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0-0.17	7/28/2020	858.58	0 - 0.17 ft	180-108872-1	Excavated	< 0.027 U	< 2.4 U	< 0.065 U			< 0.13 U	0.48	0.02 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.24	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		0.035 J
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0-0.17	7/28/2020	856.51	0 - 0.17 ft	180-108872-1	Excavated	< 0.025 U	< 2.2 U	< 0.06 U			< 0.12 U	0.086	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	0.061 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0-0.17	7/28/2020	857.00	0 - 0.17 ft	180-108872-1	Excavated	< 0.023 U	< 2.1 U	< 0.057 U			< 0.12 U	0.038 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.04 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0-0.17	7/28/2020	856.50	0 - 0.17 ft	180-108872-1	Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	0.56	0.027 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.16	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0-0.17	7/28/2020	858.42	0 - 0.17 ft	180-108872-1	Excavated	< 0.25 U	< 22 U	< 0.6 U			< 1.2 U	25	0.82	< 0.29 U	< 0.23 U	< 0.41 U	< 0.21 U	9.6	< 1.1 U	< 1.2 U	< 0.2 U	0.83		1.2
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	1/14/2021	858.30	0 - 0.17 ft	180-116002-2	Excavated	0.025	2.3	0.062			0.13	0.36	0.016	0.03	0.024	0.042	0.021	0.12	0.12		0.021	0.02	0.12	0.016
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0-0.17	1/14/2021	858.39	0 - 0.17 ft	180-116002-2	Excavated	0.13	12	0.33			0.68	33	1.1	0.16	0.13	0.22	0.11	11	0.63	0.64	0.11	0.56		0.83
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0-0.17	1/14/2021	858.31	0 - 0.17 ft	180-116002-2	Excavated	0.026	2.3	0.063			0.13	9.9	0.27	0.03	0.024	0.043	0.022	3	0.12	0.12	0.021	0.14		0.22
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 1.9 U	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.24 U			< 0.12 U	0.12	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	0.041 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 1.9 U	< 0.37 U				0.045 J	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.38 U	< 2 U	< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.14 U	< 2.2 U	< 0.21 U			< 0.11 U	0.032 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.42 U	< 2.1 U	< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U		< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	< 0.038	< 0.44	< 0.03			< 0.042	0.073	< 0.0097	< 0.0078	< 0.0082	< 0.04	< 0.026	< 0.0076	< 0.026		< 0.028	0.028	< 0.036	0.034
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated							0.31 J						0.2 J						
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.41 U	< 2.1 U	< 0.41 U				< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U		< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.06 U			< 0.12 U	0.14	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.051 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.026 U	< 2.3 U	< 0.064 U	< 0.13 U			0.041 J	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.023 U	< 2.1 U	< 0.057 U			< 0.12 U	0.16	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.09	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.017 J
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	< 0.034 U	< 0.034 U	< 0.3 U			< 0.42 U	1.3	< 0.034 U	< 0.079 U	< 0.034 U	< 0.034 U	< 0.034 U	0.58 J	< 0.034 U	< 0.034 U	< 0.034 U	0.073 J		0.21 J
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			0.31	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.27	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			0.52	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.29	< 0.11 U		< 0.02 U	0.024 J	< 0.11 U	0.045 J
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.022 U	< 2 U	< 0.053 U	< 0.11 U			0.09	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.042 J	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 0.022 U	< 2 U	< 0.055 U	< 0.11 U			0.074	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			0.069 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			0.075 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated	< 0.36	< 4.2	< 0.28			< 0.4	< 0.075	< 0.092	< 0.074	< 0.078	< 0.38	< 0.25	< 0.072	< 0.24		< 0.26	< 0.063	< 0.34	< 0.06
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.032 U			< 0.046 U	1.3	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.46	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.061 J
Tennis Courts / Main Parking Lot	SSHS-B406	PS-FD-39	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U			< 0.048 U	0.5	< 0.034 U	< 0.0089 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SS	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U			< 0.049 U	0.47	< 0.034 U	< 0.0091 U	< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.034 U	< 0.034 U	< 0.034 U	0.026 J		0.061 J
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.39	< 2	< 0.39				< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39		< 0.39	< 0.39	< 0.39	< 0.39
Football Field	SSHS-B410	SSHS-B410-SUB-0-0.2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	< 0.034 U	< 0.034 U	< 0.032 U			< 0.046 U	0.048 J	< 0.034 U	< 0.0085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0082 U	< 0.034 U	< 0.034 U	< 0.034 U	0.021 J		0.059 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.23 U			< 0.12 U	0.073 J	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	0.039 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.41	< 2.1	< 0.41				0.17	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	0.11	< 0.41		< 0.41	< 0.41	< 0.41	< 0.41
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	< 0.034 U	< 0.034 U	< 0.031 U			< 0.044 U	0.66	< 0.034 U	< 0.0082 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U	< 0.034 U	< 0.034 U	0.035 J		0.055 J
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.37	< 1.9	< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37		< 0.37	< 0.37	< 0.37	< 0.37
Football Field	SSHS-B432	SSHS-B432-SUB-0-0.2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated	< 0.042 U	< 0.49 U	< 0.033 U			< 0.047 U	0.053 J	< 0.011 U	< 0.0087 U	< 0.0091 U	< 0.044 U	< 0.029 U	< 0.0084 U	< 0.028 U	< 0.04 U	< 0.031 U	< 0.0073 U		0.035 J
Football Field	SSHS-B434	SSHS-B434-SUB-0-0.2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated	< 0.041 U	< 0.47 U	< 0.032 U			< 0.045 U	0.31	0.027 J	< 0.0084 U	< 0.0088 U	< 0.042 U	< 0.028 U	0.11	< 0.028 U	< 0.039 U	< 0.03 U	0.024 J		0.042 J
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.42	< 2.2	< 0.42				< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42		< 0.42	< 0.42	< 0.42	< 0.42
Football Field	SSHS-B448	SSHS-B448-SUB-0-0.2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated	< 0.04 U	< 0.46 U	< 0.031 U			< 0.044 U	0.07 J	< 0.01 U	< 0.0082 U	< 0.0086 U	< 0.041 U	< 0.028 U	< 0.0079 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.0069 U		< 0.0066 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-0.2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated	< 0.037 U	< 0.43 U	< 0.029 U			< 0.042 U	0.21	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U	0.11	< 0.025 U	< 0.036 U	< 0.027 U	0.033 J		0.098
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.43	< 2.2	< 0.43				0.057	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43		< 0.43	< 0.43	< 0.43	< 0.43
Football Field	SSHS-B450	SSHS-B450-SUB-0-0.2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated	< 0.039 U	< 0.45 U	< 0.031 U			< 0.043 U	1.9	0.17	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	0.87	< 0.026 U	< 0.037 U	< 0.029 U	0.18		0.36
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.43	< 2.2	< 0.43				< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43		< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.43	< 2.2	< 0.43				1.3	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	1	< 0.43		< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	7/21/2014	856.74	0 - 0.17 ft	180-35053-1	Excavated	< 0.0078	< 0.09	< 0.0061				1.5	0.044	< 0.0016	< 0.0017	< 0.0082	< 0.0054	0.7	< 0.0053		< 0.0057	0.032	< 0.0074	0.049
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.44	< 2.3	< 0.44				< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44		< 0.44	< 0.44	< 0.44	< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated							< U						< U						
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.42 U	< 2.2 U	< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U		< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 1.9 U	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U

							2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.8	100	0.33	100					
Restricted - Residential																6.7	100	100	100					
Protection of Groundwater																0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																	
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0-0.17	1/19/2020	857.08	0 - 0.17 ft	180-101269-1	Excavated	< 0.21 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.72 U	0.24	< 0.14 U	0.69		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0-0.17	1/19/2020	856.36	0 - 0.17 ft	180-101269-1	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.025 J	< 0.13 U	0.09		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0-0.17	1/19/2020	856.51	0 - 0.17 ft	180-101269-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.091	< 0.13 U	0.29		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0-0.17	1/19/2020	856.54	0 - 0.17 ft	180-101269-1	Excavated	< 0.25 U	< 0.14 U	< 0.026 U	< 0.2 U	< 0.087 U	< 0.38 U		< 0.037 U	< 0.18 U	< 0.88 U	0.085 J	< 0.16 U	0.29		< 0.024 U	< 0.23 U	< 0.039 U	< 0.03 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	0 - 0.17 ft	180-101269-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.18	< 0.12 U	0.33		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0-0.17	8/29/2019	857.57	0 - 0.17 ft	180-95006-3	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.074 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.5	< 0.14 U	3		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0-0.17	5/12/2020	856.85	0 - 0.17 ft	180-105660-1	Excavated	< 0.084 U	< 0.047 U	< 0.009 U	< 0.068 U	< 0.029 U	< 0.13 U		< 0.013 U	< 0.061 U	< 0.3 U	0.39	< 0.056 U	0.5		< 0.008 U	< 0.077 U	< 0.013 U	< 0.01 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0-0.17	8/29/2019	855.06	0 - 0.17 ft	180-95006-2	Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.074 U	< 0.33 U		< 0.031 U	< 0.15 U	< 0.75 U	0.034 J	< 0.14 U	0.065 J		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0-0.17	8/29/2019	857.44	0 - 0.17 ft	180-95024-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.062 J	< 0.14 U	0.13		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0-0.17	8/29/2019	857.92	0 - 0.17 ft	180-95006-3	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.2	< 0.13 U	0.62		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.04 J	< 0.14 U	0.14		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0-0.17	8/29/2019	858.27	0 - 0.17 ft	180-95006-3	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	0.032 J	< 0.14 U	0.13		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0-0.17	8/28/2019	858.38	0 - 0.17 ft	180-94903-1	Excavated	< 0.22 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.076 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.76 U	0.24	< 0.14 U	0.73		< 0.02 U	< 0.2 U	< 0.034 U	< 0.026 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-0-0.17	12/19/2019	857.57	0 - 0.17 ft	180-100363-3	Excavated	< 0.23 U	< 0.13 U	< 0.024 U	< 0.18 U	< 0.079 U	< 0.35 U		< 0.034 U	< 0.16 U	< 0.8 U	0.35 J	< 0.15 U	1.8 J		< 0.021 U	< 0.21 U	< 0.035 U	< 0.027 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0-0.17	1/23/2020	857.44	0 - 0.17 ft	180-101497-4	Excavated	< 0.22 U	< 0.12 U	< 0.024 U	< 0.18 U	< 0.077 U	< 0.34 U		< 0.033 U	< 0.16 U	< 0.78 U	0.095 J	< 0.15 U	0.39		< 0.021 U	< 0.2 U	< 0.035 U	< 0.027 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0-0.17	12/19/2019	858.02	0 - 0.17 ft	180-100363-2	Excavated	< 0.22 U	< 0.12 U	< 0.023 U	< 0.18 U	< 0.077 U	< 0.34 U		< 0.033 U	< 0.16 U	< 0.77 U	0.077 J	< 0.15 U	0.29		< 0.021 U	< 0.2 U	< 0.034 U	< 0.026 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0-0.17	1/23/2020	857.46	0 - 0.17 ft	180-101497-4	Excavated	< 0.22 U	< 0.12 U	< 0.024 U	< 0.18 U	< 0.078 U	< 0.34 U		< 0.033 U	< 0.16 U	< 0.78 U	0.23	< 0.15 U	0.87		< 0.021 U	< 0.2 U	< 0.035 U	< 0.027 U
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0-0.17	12/18/2019	856.31	0 - 0.17 ft	180-100380-2	Excavated	< 0.51 U	< 0.28 U	< 0.054 U	< 0.41 U	< 0.18 U	< 0.78 U		< 0.076 U	< 0.37 U	< 1.8 U	1.7	< 0.34 U	5.6		< 0.048 U	< 0.47 U	< 0.08 U	< 0.061 U
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0-0.17	12/18/2019	857.03	0 - 0.17 ft	180-100380-2	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.48	< 0.14 U	1.6		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0-0.17	12/18/2019	857.52	0 - 0.17 ft	180-100380-2	Excavated	< 0.23 U	< 0.13 U	< 0.025 U	< 0.19 U	< 0.081 U	< 0.36 U		< 0.034 U	< 0.17 U	< 0.81 U	0.65	< 0.15 U	2.2		< 0.022 U	< 0.21 U	< 0.036 U	< 0.028 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.074 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	4.3	< 0.14 U	4.3		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	7/28/2020	858.23	0 - 0.17 ft	180-108872-1	Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.074 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	4.3	< 0.14 U	4.3		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0-0.17	7/28/2020	858.45	0 - 0.17 ft	180-108872-1	Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	0.3	< 0.14 U	1.1		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0-0.17	7/28/2020	858.43	0 - 0.17 ft	180-108872-1	Excavated	< 1.9 U	< 1.1 U	< 0.21 U	< 1.6 U	< 0.68 U	< 3 U		< 0.29 U	< 1.4 U	< 6.8 U	7.6	< 1.3 U	28		< 0.18 U	< 1.8 U	< 0.3 U	< 0.23 U
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0-0.17	7/28/2020	858.58	0 - 0.17 ft	180-108872-1	Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.15	< 0.13 U	0.56		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0-0.17	7/28/2020	856.51	0 - 0.17 ft	180-108872-1	Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.029 J	< 0.12 U	0.091		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0-0.17	7/28/2020	857.00	0 - 0.17 ft	180-108872-1	Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.039 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0-0.17	7/28/2020	856.50	0 - 0.17 ft	180-108872-1	Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.34	< 0.11 U	0.42		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0-0.17	7/28/2020	858.42	0 - 0.17 ft	180-108872-1	Excavated	< 1.8 U	< 1 U	< 0.19 U	< 1.5 U	< 0.64 U	< 2.8 U		< 0.27 U	< 1.3 U	< 6.4 U	8	< 1.2 U	25		< 0.17 U	< 1.7 U	< 0.29 U	< 0.22 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	1/14/2021	858.30	0 - 0.17 ft	180-116002-2	Excavated	0.19	0.1	0.02	0.15	0.066	0.29		0.028	0.14	0.66	0.12	0.12	0.32		0.018	0.17	0.029	0.023
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0-0.17	1/14/2021	858.39	0 - 0.17 ft	180-116002-2	Excavated	0.99	0.55	0.11	0.8	0.35	1.5		0.15	0.73	3.5	14	0.66	32		0.094	0.91	0.16	0.12
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0-0.17	1/14/2021	858.31	0 - 0.17 ft	180-116002-2	Excavated	0.19	0.11	0.02	0.15	0.067	0.29		0.028	0.14	0.67	2.9	0.13	8.3		0.018	0.17	0.03	0.023
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	0.044 J	< 0.12 U	0.096		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 2 U	< 2 U	< 2 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.023 J		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 2.1 U	< 2.1 U	< 2.1 U	< 0.42 U	< 0.42 U	< 2.1 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.1 U	< 0.42 U	< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	< 0.16	< 0.15	< 0.15	< 0.031	< 0.04	< 0.13		< 0.0086	< 0.034	< 0.033	0.035	< 0.0087	0.061		< 0.028	< 0.024	< 0.039	< 0.055
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated											0.1 J		0.34 J					
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 2.1 U	< 2.1 U	< 2.1 U	< 0.41 U	< 0.41 U	< 2.1 U	< 0.41 U	< 0.41 U	< 0.41 U	< 2.1 U	< 0.41 U	< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.061 J	< 0.12 U	0.13		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	0.042 J		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.061 J	< 0.11 U	0.16		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	< 0.034 U	< 0.034 U	< 1.5 U	< 0.034 U	< 0.034 U	< 1.3 U		< 0.034 U	< 0.034 U	< 0.034 U	0.66 J	< 0.087 U	1.4		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.079	< 0.12 U	0.34		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.21	< 0.12 U	0.5		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.028 J	< 0.11 U	0.079		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.026 J	< 0.11 U	0.069 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.023 J	< 0.11 U	0.058 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.062 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated	< 1.6	< 1.4	< 1.4	< 0.29	< 0.39	< 1.3		< 0.082	< 0.32	< 0.31	< 0.11	< 0.083	< 0.071		< 0.27	< 0.22	< 0.37	< 0.52
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.15 U		< 0.034 U	< 0.034 U	< 0.034 U	0.65	< 0.0095 U	0.95 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	PS-FD-39	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.15 U		< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.0099 U	0.33		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SS	8/25/2016	855.97	0 - 0.17 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.16 U		< 0.034 U	< 0.034 U	< 0.034 U	0.15	< 0.01 U	0.31		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 2	< 2	< 2	< 0.39	< 0.39	< 2	< 0.39	< 0.39	< 0.39	< 2	< 0.39	< 0.39	< 0.39				< 0.39	< 0.39
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.15 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0094 U	0.044 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.031 J	< 0.12 U	0.067 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 2.1	< 2.1	< 2.1	< 0.41	< 0.41	< 2.1	< 0.41	< 0.41	< 0.41	< 2.1	0.068	< 0.41	0.2				< 0.41	< 0.41
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	0.36	< 0.0091 U	0.65		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 1.9	< 1.9	< 1.9	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37				< 0.37	< 0.37
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated	< 0.18 U	< 0.17 U	< 0.17 U	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0096 U	< 0.038 U	< 0.036 U	0.04 J	< 0.0096 U	0.058 J		< 0.031 U	< 0.026 U	< 0.043 U	< 0.061 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	0.24	< 0.0093 U	0.3		< 0.03 U	< 0.025 U	< 0.042 U	< 0.059 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 2.2	< 2.2	< 2.2	< 0.42	< 0.42	< 2.2	< 0.42	< 0.42	< 0.42	< 2.2	< 0.42	< 0.42	< 0.42				< 0.42	< 0.42
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.009 U	< 0.035 U	< 0.034 U	0.037 J	< 0.0091 U	0.076 J		< 0.029 U	< 0.025 U	< 0.041 U	< 0.057 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	0.13	< 0.0086 U	0.23		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 2.2	< 2.2	< 2.2	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	0.059				< 0.43	< 0.43
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	1.2	< 0.009 U	1.7		< 0.029 U	< 0.024 U	< 0.04 U	< 0.057 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 2.2	< 2.2	< 2.2	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43				< 0.43	< 0.43
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 2.2	< 2.2	< 2.2	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43	< 2.2	0.28	< 0.43	1.6				< 0.43	< 0.43
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	7/21/2014	856.74	0 - 0.17 ft	180-35053-1	Excavated	< 0.034	< 0.031	< 0.031	< 0.0063	< 0.0083	< 0.028		< 0.0018	< 0.007	< 0.0068	0.48	< 0.0018	1.3		< 0.0057	< 0.0049	< 0.0081	< 0.011
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 2.3	< 2.3	< 2.3	< 0.44	< 0.44	< 2.3	< 0.44	< 0.44	< 0.44	< 2.3	< 0.44	< 0.44	< 0.44				< 0.44	< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated											< U							
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 2.2 U	< 2.2 U	< 2.2 U	< 0.42 U	< 0.42 U	< 2.2 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.2 U	< 0.42 U	< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated			0.049	< 0.46 U	< 0.46 U		< 0.46 U				< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated			ND	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated			ND	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated			0.184	< 0.46 U	< 0.46 U		< 0.46 U				< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated			ND																0.044	
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated			0.681	< 0.0066 U	< 0.0078 U	< 0.028 U	0.013 J	< 0.033 U	< 0.03 U	< 0.051 U	0.039 J	0.029 J	0.052 J	< 0.014 U	0.029 J	< 0.022 U	< 0.0092 U	< 0.0074 U	< 0.055 U	< 0.03 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated			1.06																	
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated			1.214	< 0.0069	0.027	< 0.03	0.04	< 0.035	< 0.032	< 0.054	0.11	0.095	0.11	0.053	0.074	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated			ND	< 0.39 U	< 0.39 U		< 0.39 U				< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated			2.69		0.092 J		0.11 J				0.21 J	0.29 J	0.47	0.18 J	0.23 J				0.53	
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated			0.039	< 0.0067 U	< 0.008 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.031 U	< 0.053 U	< 0.0088 U	< 0.007 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0094 U	< 0.0076 U	< 0.057 U	< 0.031 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated			0.04	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated			0.557	< 0.0068 U	< 0.0081 U	< 0.029 U	0.013 J	< 0.034 U	< 0.032 U	< 0.053 U	0.046 J	0.041 J	0.058 J	0.028 J	0.044 J	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated			1.638	< 0.0071 U	0.037 J	0.065 J	0.038 J	< 0.036 U	0.055 J	< 0.056 U	0.1	0.085	0.15	0.053 J	0.086	< 0.024 U	< 0.01 U	< 0.008 U	< 0.06 U	< 0.032 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated			2.914	0.018 J	0.12	< 0.029 U	0.11	< 0.035 U	< 0.032 U	< 0.054 U	0.22	0.25	0.41	0.15	0.25	< 0.024 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated			8.528	0.071 J	0.4	< 0.03 U	0.36	< 0.036 U	< 0.033 U	< 0.055 U	0.77	0.78	0.91	0.43	0.75	< 0.024 U	< 0.0099 U	< 0.0079 U	< 0.059 U	< 0.032 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46	0.47	0.63	0.26 J	0.36				0.68	
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated			1.603	< 0.0082 U	0.044 J	< 0.035 U	0.036 J	< 0.042 U	< 0.038 U	< 0.064 U	0.13	0.15	0.2	0.081 J	0.15	< 0.028 U	< 0.011 U	< 0.0092 U	< 0.069 U	< 0.037 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated			0.431	< 0.0082	< 0.0098	< 0.035	< 0.0083	< 0.042	< 0.038	< 0.064	0.037	0.043	0.054	0.025	0.035	< 0.028	< 0.011	< 0.0092	0.09	< 0.037
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated			1.318	< 0.0078	< 0.0093	< 0.034	0.02	< 0.04	< 0.036	< 0.061	0.11	0.12	0.15	0.073	0.12	< 0.027	< 0.011	< 0.0088	< 0.066	< 0.035
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated			0.07	< 0.0078	< 0.0094	< 0.034	< 0.008	< 0.04	< 0.036	< 0.061	< 0.01	< 0.0082	< 0.013	< 0.017	< 0.0081	< 0.027	< 0.011	< 0.0088	< 0.066	< 0.036
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46	0.47	0.63	0.26 J	0.36				0.68	
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated			60.581	0.061 J	1.1	< 0.025 U	2	< 0.051 U	0.043 J	< 0.024 U	5.5	4.7	5.7	2.2	3.5	< 0.021 U	< 0.022 U	< 0.024 U	< 0.25 U	< 0.035 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated																				
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U	< U	< U	< U	< U				1.1	
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated																				
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated																				
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U	< U	< U	< U	< U				1.1	
Football Field	SSHS-FB10	SSHS-FB10-A-SS	7/22/2014	855.71	0 - 0.17 ft	180-35079-1	Excavated			0.8201	0.0056 J	0.014	0.0056 J	0.023	< 0.0042 U	< 0.0038 U		0.076	0.068	0.088	0.031	0.058	< 0.0028 U	< 0.0011 U	< 0.00092 U	0.094	< 0.0037 U
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated			0.171	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U					
Football Field	SSHS-FB6-A	SSHS-DUP5	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated			1.291	0.016	0.042	0.0062 J	0.055	< 0.0043 U	< 0.0039 U		0.11	0.1	0.13	0.052	0.093	< 0.0029 U	< 0.0012 U	< 0.00095 U	0.061 J	< 0.0038 U
Football Field	SSHS-FB6-A	SSHS-FB6-A-SS	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated			2.571	0.06	0.035	0.0055 J	0.13	< 0.0042 U	0.0045 J		0.22	0.19	0.21	0.096	0.14	< 0.0028 U	< 0.0012 U	< 0.00093 U	0.12	< 0.0037 U
Football Field	SSHS-FB9-A	SSHS-FB9-A-SS	7/22/2014	854.80	0 - 0.17 ft	180-35079-1	Excavated			0.7125	0.0028 J	0.023	0.0047 J	0.021	< 0.0042 U	< 0.0038 U		0.057	0.064	0.086	0.033	0.066	< 0.0028 U	< 0.0012 U	< 0.00093 U	0.059 J	< 0.0038 U
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated			ND	< 0.5 U	< 0.5 U		< 0.5 U				< 0.5 U	< 0.5 U	< 0.5 U	< 0.5 U	< 0.5 U					
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated			1	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated			0.38	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U					
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated			0.604	< 0.46 U	< 0.46 U		< 0.46 U				< 0.46 U	0.081 J	0.097 J	0.074 J	0.094 J					
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated			0.338	< 0.43 U	< 0.43 U		< 0.43 U				< 0.43 U	0.05 J	0.046 J	< 0.43 U	0.046 J					
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated			ND	< 0.45 U	< 0.45 U		< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated			0.22	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	0.048 J	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	0.05 J	< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated			ND		< 0.45 U		< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U

DRAFT

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7							
Restricted - Residential																3.9	0.33	59							
Protection of Groundwater																1	1000	210							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.46 U		< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.44 U		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.44 U		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.46 U		< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	0.056 J	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated																			
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated	< 0.047 U	< 0.26 U	0.0087 J	< 0.027 U	< 0.031 U	< 0.0071 U	< 0.028 U	< 0.038 U	0.076	< 0.0076 U	0.036 J	< 0.036 U	< 0.0068 U	< 0.037 U	< 0.053 U	< 0.037 U	< 0.043 U	< 0.036 U	< 0.14 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated																			
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	< 0.049	< 0.27	0.014	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	0.091	0.02	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.38 U		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.39 U		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 2 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated									0.25 J										
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.048 U	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.032 U	< 0.0073 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0078 U	< 0.035 U	< 0.037 U	< 0.007 U	< 0.038 U	< 0.055 U	< 0.038 U	< 0.044 U	< 0.037 U	< 0.14 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.048 U	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.048 U	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	0.065 J	0.018 J	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.038 U	< 0.044 U	< 0.037 U	< 0.14 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.051 U	< 0.28 U	0.022 J	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.18	< 0.0083 U	0.13 J	< 0.039 U	< 0.0074 U	< 0.041 U	< 0.058 U	< 0.04 U	< 0.047 U	< 0.039 U	< 0.15 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.049 U	< 0.27 U	0.022 J	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	0.29	0.076	0.042 J	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.05 U	< 0.28 U	0.07 J	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.81	0.19	0.037 J	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated									0.44										
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.058 U	< 0.32 U	< 0.0079 U	< 0.034 U	< 0.039 U	< 0.0089 U	< 0.035 U	< 0.047 U	0.16	0.04 J	< 0.042 U	< 0.045 U	< 0.0086 U	< 0.047 U	< 0.067 U	< 0.047 U	< 0.053 U	< 0.045 U	< 0.17 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.058	< 0.32	< 0.0079	< 0.034	< 0.039	< 0.0089	< 0.035	< 0.047	0.045	< 0.0095	< 0.042	< 0.045	< 0.0086	< 0.047	< 0.067	< 0.046	< 0.053	< 0.045	< 0.17
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.056	< 0.31	< 0.0075	< 0.033	< 0.038	< 0.0085	< 0.033	< 0.045	0.12	< 0.0091	< 0.04	< 0.043	< 0.0082	< 0.045	< 0.064	< 0.044	< 0.051	< 0.043	< 0.16
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.056	< 0.31	< 0.0075	< 0.033	< 0.038	< 0.0085	< 0.033	< 0.045	< 0.0097	< 0.0091	< 0.04	< 0.043	< 0.0082	< 0.045	< 0.064	< 0.045	< 0.051	< 0.043	< 0.16
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated									0.44										
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	< 0.27 U	< 0.17 U	0.95	< 0.021 U	< 0.039 U	< 0.024 U	< 0.026 U	< 0.026 U	4.3	0.93	0.3 J	< 0.15 U	< 0.03 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.043 U	< 0.68 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated																			
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated									< U										
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated																			
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated																			
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated									< U										
Football Field	SSHS-FB10	SSHS-FB10-A-SS	7/22/2014	855.71	0 - 0.17 ft	180-35079-1	Excavated	0.014 J	< 0.032 U	0.0094	< 0.0034 U	< 0.0039 U	< 0.00089 U	< 0.0035 U	< 0.0048 U	0.086	0.015	< 0.0042 U	< 0.0045 U	< 0.00086 U	< 0.0047 U	< 0.0067 U	< 0.0047 U	0.009 J	< 0.0045 U	< 0.017 U
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated									0.046 J	< 0.44 U	< 0.44 U								
Football Field	SSHS-FB6-A	SSHS-DUP5	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	0.031 J	< 0.033 U	0.017	< 0.0035 U	< 0.004 U	< 0.00092 U	< 0.0036 U	< 0.0049 U	0.12	0.026	0.008 J	< 0.0047 U	< 0.00088 U	< 0.0048 U	< 0.0069 U	< 0.0048 U	0.01 J	< 0.0046 U	< 0.018 U
Football Field	SSHS-FB6-A	SSHS-FB6-A-SS	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	< 0.0059 U	< 0.032 U	0.051	< 0.0034 U	< 0.004 U	< 0.0009 U	< 0.0035 U	< 0.0048 U	0.22	0.043	0.031 J	< 0.0045 U	< 0.00086 U	< 0.0047 U	< 0.0067 U	< 0.0047 U	0.01 J	< 0.0045 U	< 0.017 U
Football Field	SSHS-FB9-A	SSHS-FB9-A-SS	7/22/2014	854.80	0 - 0.17 ft	180-35079-1	Excavated	0.015 J	< 0.033 U	0.007 J	< 0.0035 U	< 0.004 U	< 0.0009 U	< 0.0035 U	< 0.0048 U	0.073	0.017	0.0042 J	< 0.0046 U	< 0.00086 U	0.005 J	< 0.0067 U	< 0.0047 U	0.011 J	< 0.0045 U	< 0.017 U
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated									< 0.5 U	< 0.5 U	< 0.5 U								
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated									< 0.47 U	< 0.47 U	< 0.47 U								
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated									0.059 J	< 0.46 U	< 0.46 U								
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated									0.046 J	< 0.43 U	< 0.43 U								
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.45 U		< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.47 U		< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.44 U		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	0.045 J	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.47 U		< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.45 U		< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U

DRAFT

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.46 U	< 2.4 U	< 0.46 U				0.049 J	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U		< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 2.3 U	< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 2.3 U	< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.46 U	< 2.4 U	< 0.46 U				0.067 J	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U		< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated																			
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated	< 0.035 U	< 0.41 U	< 0.028 U			< 0.039 U	0.096	0.016 J	< 0.0073 U	< 0.0076 U	< 0.037 U	< 0.025 U	0.021 J	< 0.024 U		< 0.026 U	0.1	< 0.033 U	0.059 J
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated							0.63												
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	< 0.037	< 0.43	< 0.029			< 0.041	0.2	< 0.0095	< 0.0077	< 0.008	< 0.039	< 0.026	0.066	< 0.025		< 0.027	0.008	< 0.035	0.025
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.38 U	< 1.9 U	< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.39 U	< 2 U	< 0.39 U				< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated							0.31 J						0.2 J						
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.036 U	< 0.42 U	< 0.028 U			< 0.04 U	< 0.0075 U	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	< 0.0072 U	< 0.025 U		< 0.026 U	0.029 J	< 0.034 U	0.019 J
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.036 U	< 0.42 U	< 0.029 U			< 0.041 U	0.01 J	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	< 0.0073 U	< 0.025 U		< 0.027 U	0.025 J	< 0.035 U	0.019 J
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.036 U	< 0.42 U	< 0.029 U			< 0.041 U	0.061 J	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	0.035 J	< 0.025 U		< 0.027 U	0.045 J	< 0.035 U	0.033 J
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.038 U	< 0.44 U	< 0.03 U			< 0.043 U	0.15	0.024 J	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	0.062 J	< 0.026 U		< 0.028 U	0.46	< 0.036 U	0.3
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.037 U	< 0.43 U	< 0.029 U			< 0.041 U	0.36	< 0.0094 U	< 0.0076 U	< 0.008 U	< 0.039 U	< 0.026 U	0.21	< 0.025 U		< 0.027 U	0.12	< 0.035 U	0.09
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.038 U	< 0.44 U	< 0.03 U			< 0.042 U	1.2	0.094	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U	0.6	< 0.026 U		< 0.028 U	0.042 J	< 0.036 U	0.053 J
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated							1						0.31 J						
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.044 U	< 0.51 U	< 0.034 U			< 0.049 U	0.25	< 0.011 U	< 0.0091 U	< 0.0096 U	< 0.046 U	< 0.031 U	0.12	< 0.03 U	< 0.042 U	< 0.032 U	0.013 J		< 0.0074 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.044	< 0.51	< 0.034			< 0.049	0.076	< 0.011	< 0.0091	< 0.0095	< 0.046	< 0.031	0.029	< 0.03		< 0.032	< 0.0077	< 0.042	< 0.0074
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.042	< 0.49	< 0.033			< 0.047	0.21	< 0.011	< 0.0087	< 0.0091	< 0.044	< 0.029	0.098	< 0.029		< 0.031	0.018	< 0.04	0.051
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.042	< 0.49	< 0.033			< 0.047	0.037	< 0.011	< 0.0087	< 0.0091	< 0.044	< 0.029	< 0.0084	< 0.029		< 0.031	< 0.0073	< 0.04	< 0.007
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated							1						0.31 J						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	< 0.025 U	< 0.74 U	< 0.049 U			< 0.055 U	8.7	0.3	< 0.03 U	< 0.023 U	< 0.031 U	< 0.026 U	3.2	< 0.032 U	0.11 J	< 0.02 U	0.13		0.59
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated			< 0.96 U						< 0.58 U	< 0.46 U		< 0.52 U		< 0.64 U	< 0.64 U				
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated							< U						< U						
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated			< 0.97 U						< 0.59 U	< 0.46 U		< 0.52 U		< 0.64 U				< 0.65 U	
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated			< 0.47 U						< 0.28 U	< 0.22 U		< 0.25 U		< 0.31 U				< 0.31 U,F2	
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated							< U						< U						
Football Field	SSHS-FB10	SSHS-FB10-A-SS	7/22/2014	855.71	0 - 0.17 ft	180-35079-1	Excavated	< 0.0044 U	< 0.051 U	< 0.0035 U				0.14	0.0057 J	< 0.00091 U	< 0.00096 U	< 0.0046 U	< 0.0031 U	0.051	< 0.003 U	< 0.0042 U	< 0.0032 U	0.0066 J		0.0078 J
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated							0.058 J	< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U
Football Field	SSHS-FB6-A	SSHS-DUP5	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	< 0.0045 U	< 0.052 U	< 0.0036 U				0.22	0.016	< 0.00094 U	< 0.00098 U	< 0.0047 U	< 0.0032 U	0.082	< 0.0031 U	< 0.0043 U	< 0.0033 U	0.0085 J		0.011
Football Field	SSHS-FB6-A	SSHS-FB6-A-SS	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	< 0.0044 U	< 0.051 U	< 0.0035 U				0.44	0.052	< 0.00092 U	< 0.00096 U	< 0.0046 U	< 0.0031 U	0.13	< 0.003 U	< 0.0042 U	< 0.0032 U	0.018		0.03
Football Field	SSHS-FB9-A	SSHS-FB9-A-SS	7/22/2014	854.80	0 - 0.17 ft	180-35079-1	Excavated	< 0.0044 U	< 0.051 U	< 0.0035 U				0.11	0.0017 J	< 0.00092 U	< 0.00096 U	< 0.0046 U	< 0.0031 U	0.057	< 0.003 U	< 0.0042 U	< 0.0032 U	0.01		0.013
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated							< 0.5 U	< 0.5 U	< 0.5 U				< 0.5 U	< 0.5 U				< 0.5 U	< 0.5 U
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 1.9 U	< 0.37 U				0.56	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 1.9 U	< 0.37 U				0.38	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated							< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated							0.059 J	< 0.46 U	< 0.46 U				0.075 J	< 0.46 U				< 0.46 U	< 0.46 U
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated							0.084 J	< 0.43 U	< 0.43 U				< 0.43 U	< 0.43 U				< 0.43 U	< 0.43 U
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.45 U	< 2.3 U	< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U		< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.47 U	< 2.4 U	< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U		< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 2.3 U	< 0.44 U				0.071 J	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.47 U	< 2.4 U	< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U		< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.45 U	< 2.3 U	< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U		< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U

DRAFT

TABLE 5-4C
Surface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

							2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.8	100	0.33	100					
Restricted - Residential																6.7	100	100	100					
Protection of Groundwater																0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																	
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 2.4 U	< 2.4 U	< 2.4 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	< 0.46 U				< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 2.3 U	< 2.3 U	< 2.3 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 2.3 U	< 2.3 U	< 2.3 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 2.4 U	< 2.4 U	< 2.4 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	0.061 J				< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated																		
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated	< 0.15 U	< 0.14 U	< 0.14 U	< 0.028 U	< 0.038 U	< 0.12 U		< 0.008 U	< 0.032 U	< 0.031 U	0.16	< 0.0081 U	0.091		< 0.026 U	< 0.022 U	< 0.036 U	< 0.051 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated													0.43					
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0084	< 0.033	< 0.032	0.13	< 0.0085	0.2		< 0.027	< 0.023	< 0.038	< 0.054
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 1.9 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 2 U	< 2 U	< 2 U	< 0.39 U	< 0.39 U	< 2 U	< 0.39 U	< 0.39 U	< 0.39 U	< 2 U	< 0.39 U	< 0.39 U	< 0.39 U				< 0.39 U	< 0.39 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated											0.1 J		0.34 J					
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.16 U	< 0.14 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0082 U	< 0.033 U	< 0.031 U	0.02 J	< 0.0083 U	< 0.0071 U		< 0.027 U	< 0.023 U	< 0.037 U	< 0.053 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	0.011 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	0.056 J	< 0.0083 U	0.059 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0087 U	< 0.034 U	< 0.033 U	0.28	< 0.0088 U	0.13		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.16 U	< 0.15 U	< 0.14 U	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	0.19	< 0.0085 U	0.29		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.16 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.51	< 0.0087 U	1		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated											0.47		0.84					
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.19 U	< 0.18 U	< 0.17 U	< 0.036 U	< 0.047 U	< 0.16 U		< 0.01 U	< 0.04 U	< 0.038 U	0.076 J	< 0.01 U	0.21		< 0.032 U	< 0.027 U	< 0.046 U	< 0.064 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.19	< 0.18	< 0.17	< 0.036	< 0.047	< 0.16		< 0.01	< 0.039	< 0.038	0.029	< 0.01	0.058		< 0.032	< 0.027	< 0.046	< 0.064
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.18	< 0.17	< 0.17	< 0.034	< 0.045	< 0.15		2	< 0.038	< 0.036	0.066	< 0.0096	0.18		< 0.031	< 0.026	< 0.044	< 0.061
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.18	< 0.17	< 0.17	< 0.034	< 0.045	< 0.15		< 0.0096	< 0.038	< 0.037	< 0.013	< 0.0097	0.033		< 0.031	< 0.026	< 0.044	< 0.061
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated											0.47		0.84					
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	< 0.13 U	< 0.11 U	< 0.13 U	< 0.028 U	< 0.027 U	< 0.38 U		< 0.025 U	< 0.058 U	< 0.69 U	7.9	< 0.05 U	11		< 0.026 U	< 0.029 U	< 0.035 U	< 0.032 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated				< 0.55 U						< 14 U				< 0.69 U			< 0.69 U	< 0.63 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated											< U		< U					
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated				< 0.56 U						< 14 U				< 0.7 U			< 0.69 U	< 0.64 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated				< 0.27 U						< 6.7 U,F1				< 0.34 U			< 0.34 U	< 0.31 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated											< U		< U					
Football Field	SSHS-FB10	SSHS-FB10-A-SS	7/22/2014	855.71	0 - 0.17 ft	180-35079-1	Excavated	< 0.019 U	< 0.018 U	< 0.017 U	< 0.0036 U	< 0.0047 U	< 0.016 U		< 0.001 U	< 0.004 U	< 0.0038 U	0.071	0.005 J	0.094		< 0.0032 U	< 0.0028 U	< 0.0046 U	< 0.0064 U
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated										< 2.3 U	< 0.44 U	< 0.44 U	0.067 J					
Football Field	SSHS-FB6-A	SSHS-DUP5	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	< 0.02 U	< 0.018 U	< 0.018 U	< 0.0037 U	< 0.0048 U	< 0.016 U		< 0.001 U	< 0.0041 U	< 0.0039 U	0.11	< 0.001 U	0.15		< 0.0033 U	< 0.0028 U	< 0.0047 U	< 0.0066 U
Football Field	SSHS-FB6-A	SSHS-FB6-A-SS	7/22/2014	856.14	0 - 0.17 ft	180-35079-1	Excavated	< 0.019 U	< 0.018 U	< 0.017 U	< 0.0036 U	< 0.0047 U	< 0.016 U		< 0.001 U	< 0.004 U	< 0.0038 U	0.33	< 0.001 U	0.28		< 0.0033 U	< 0.0028 U	< 0.0046 U	< 0.0064 U
Football Field	SSHS-FB9-A	SSHS-FB9-A-SS	7/22/2014	854.80	0 - 0.17 ft	180-35079-1	Excavated	< 0.019 U	< 0.018 U	< 0.017 U	< 0.0036 U	< 0.0048 U	< 0.016 U		< 0.001 U	< 0.004 U	< 0.0039 U	0.037	< 0.001 U	0.074		< 0.0033 U	< 0.0028 U	< 0.0046 U	< 0.0065 U
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated										< 1.2 U	< 0.5 U	< 0.5 U	< 0.5 U					
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	0.44				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated										< 1.1 U	< 0.47 U	< 0.47 U	< 0.47 U					
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated										< 1.1 U	< 0.46 U	< 0.46 U	0.065 J					
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated										< 1 U	< 0.43 U	< 0.43 U	0.066 J					
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 2.3 U	< 2.3 U	< 2.3 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U				< 0.45 U	< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 2.4 U	< 2.4 U	< 2.4 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 2.3 U	< 2.3 U	< 2.3 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	0.056 J				< 0.44 U	< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 2.4 U	< 2.4 U	< 2.4 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 2.3 U	< 2.3 U	< 2.3 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U				< 0.45 U	< 0.45 U

DRAFT

TABLE 5-4D
Surface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.0071 U						< 0.0071 U	< 0.0071 U			< 0.0071 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.004 U	< 0.00054 U	< 0.00055 U	< 0.00045 U	< 0.00036 U	< 0.00059 U	< 0.00041 U	< 0.00036 U	< 0.00061 U	< 0.00057 U	< 0.0012 U	< 0.00047 U	< 0.00069 U	< 0.0003 U	< 0.0006 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0064 U						< 0.0064 U	< 0.0064 U			< 0.0064 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U						< 0.0067 U	< 0.0067 U			< 0.0067 U			
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			0.0029 J			
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			< 0.0065 U			
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.024 U	< 0.0061 U						< 0.0061 U	< 0.0061 U			< 0.0061 U			
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U						< 0.0057 U	< 0.0057 U			< 0.0057 U			
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	0.008 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	0.075	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	0.064	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	0.011 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	0.015 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	0.0087 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	0.013 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	0.0035 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.074	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.062	< 0.0025 U	< 0.0025 U	< 0.003 U	< 0.0034 U	< 0.0058 U	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0033 U	< 0.0027 U	< 0.005 U	< 0.0016 U	< 0.004 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	0.016 J,F2,F1	0.00067 J	< 0.00058 U	< 0.00074 U	< 0.0004 U	< 0.0017 U	0.0029 J	< 0.00083 U	< 0.0005 U	< 0.00047 U	< 0.0011 U	< 0.00072 U	< 0.00055 U	0.0016 J	< 0.00076 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	0.03	< 0.00065 U	< 0.00059 U	< 0.00077 U	< 0.00041 U	< 0.0018 U	< 0.0007 U	< 0.00085 U	< 0.00052 U	< 0.00048 U	< 0.0011 U	< 0.00074 U	< 0.00057 U	0.0022 J	< 0.00078 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	0.014 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U,F2	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2624A	PS-FD-1	6/12/2019	855.29	0 - 0.17 ft	180-91215-1	Excavated	0.0059 J	< 0.0024 U						< 0.0041 U	< 0.0019 U			< 0.0026 U			
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 UJ	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 UJ	< 0.0019 U	< 0.003 UJ	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.0044 U	< 0.0027 U	< 0.0027 U	< 0.0033 U	< 0.0036 U	< 0.0062 U	< 0.0042 U	< 0.0046 U	< 0.0022 U	< 0.0033 U	< 0.0036 U	< 0.0029 U	< 0.0053 U	< 0.0017 U	< 0.0043 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 UJ	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.0029 UJ	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.00066 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.034 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	0.0069 J	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.0034 U	< 0.0002 U	< 0.00029 U	< 0.00054 U	< 0.002 U	< 0.00037 U	< 0.002 U	< 0.00039 U	< 0.00054 U	< 0.00052 U	< 0.00092 U	< 0.00025 U	< 0.00025 U	< 0.00057 U	< 0.002 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.0051 U	< 0.0019 U	< 0.0039 U	< 0.0031 U	< 0.0033 U	< 0.0030 U	< 0.0053 U	< 0.0027 U	< 0.0017 U	< 0.0033 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UJ	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.024	< 0.0059		< 0.0059	< 0.0059	< 0.0059	< 0.012	< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059		
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.025	< 0.0062		< 0.0062	< 0.0062	< 0.0062	< 0.012	< 0.0062	< 0.0062	< 0.0062	< 0.0062	0.0015	< 0.0062		
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.022	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.011	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0064		< 0.0064	< 0.0064	< 0.0064	< 0.013	< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064		
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0065		< 0.0065	< 0.0065	< 0.0065	0.0014	< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065		
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.013	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.013	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.027	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.013	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.022 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.028 U	< 0.0069 U	< 0.0069 U		< 0.0069 U	< 0.0069 U	< 0.014 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U		
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.007 U		< 0.007 U	< 0.007 U	< 0.007 U	< 0.014 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	0.0083	< 0.007 U		
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated															
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.024 U	< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	< 0.012 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U		
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.0042 U	< 0.00056 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.0013 U	< 0.00049 U	< 0.00071 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U	< 0.0007 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00069 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.0047 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00069 U	< 0.00048 U	< 0.00042 U	< 0.00071 U	< 0.00066 U	< 0.0014 U	< 0.00054 U	< 0.00079 U	< 0.00035 U	< 0.0007 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.0055 U	< 0.00075 U	< 0.00076 U	< 0.00062 U	< 0.00049 U	< 0.00082 U	< 0.00057 U	< 0.00049 U	< 0.00084 U	< 0.00079 U	< 0.0017 U	< 0.00065 U	< 0.00094 U	< 0.00041 U	< 0.00083 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.0051 U	< 0.00069 U	< 0.0007 U	< 0.00057 U	< 0.00045 U	< 0.00076 U	< 0.00052 U	< 0.00046 U	< 0.00077 U	< 0.00073 U	< 0.0016 U	< 0.0006 U	< 0.00087 U	< 0.00038 U	< 0.00077 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U

DRAFT

TABLE 5-4D
Surface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.00054 U	< 0.00069 U	< 0.00054 U	< 0.00064 U	< 0.00053 U	< 0.00051 U	< 0.00046 U	< 0.00049 U	< 0.00068 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00048 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.0064 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0064 U	< 0.0064 U	< 0.0064 U		< 0.0064 U	< 0.0064 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 4.4 U	< 4.4 U	< 4.4 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U			
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.0065 U			< 0.43 U	< 0.43 U	< 0.43 U	< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0065 U			< 0.43 U	< 0.43 U	< 0.43 U	< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0061 U						< 0.0061 U	< 0.0061 U	< 0.0061 U		< 0.0061 U	< 0.0061 U			
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0057 U						< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U			
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.0028 U	< 0.0032 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.0024 U	< 0.0028 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.0023 U	< 0.0027 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0027 U	< 0.0031 U	< 0.0034 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.003 U	< 0.0035 U	< 0.0038 U	< 0.0052 U	< 0.0021 U	< 0.0013 U	< 0.0023 U	< 0.0019 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.0027 U	< 0.00049 U	< 0.0005 U	< 0.00055 U	< 0.0009 U	< 0.00058 U	< 0.0008 U	< 0.00048 U	< 0.001 U	< 0.0012 U	< 0.00062 U	< 0.00076 U	< 0.0006 U	< 0.00036 U	< 0.00043 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.0028 U	< 0.00051 U	< 0.00052 U	< 0.00057 U	< 0.00093 U	< 0.00059 U	< 0.00083 U	< 0.00049 U	< 0.001 U	< 0.0012 U	< 0.00064 U	< 0.00078 U	< 0.00062 U	< 0.00037 U	< 0.00044 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2624A	PS-FD-1	6/12/2019	855.29	0 - 0.17 ft	180-91215-1	Excavated	< 0.0048 U			< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U		< 0.0019 U	< 0.0031 U			
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.0047 U	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 UJ	< 0.0021 UJ
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.0053 U	< 0.0038 U	< 0.004 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U	< 0.004 U	< 0.0055 U	< 0.0022 U	< 0.0035 U	< 0.0034 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.0046 U	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 UJ	< 0.002 UJ
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.0047 U	< 0.0033 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 UJ	< 0.0021 UJ
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.0047 U	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.0057 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.034 U	< 0.00067 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.034 U	< 0.00026 U	< 0.034 U	< 0.034 U	< 0.00066 U	< 0.00054 U	< 0.034 U	< 0.00075 U	< 0.0023 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.0056 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0058 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.0019 U	< 0.00052 U	< 0.00034 U	< 0.00032 U	< 0.00021 U	< 0.00057 U	< 0.0005 U	< 0.0002 U	< 0.0005 U	< 0.0021 U	< 0.00052 U	< 0.00042 U	< 0.002 U	< 0.00059 U	< 0.0018 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0063 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.0062 U			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.0059 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U	< 0.0030 U	< 0.0054 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0030 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	0.01	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	0.011	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.0059			< 0.39	< 0.39	< 0.39	< 0.0059	< 0.0059	< 0.0059		< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.0062			< 0.41	< 0.41	< 0.41	< 0.0062	< 0.0062	< 0.0062		< 0.0062	< 0.0062	< 0.0062	< 0.0062	< 0.0062
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0055			< 0.37	< 0.37	< 0.37	< 0.0055	< 0.0055	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0064			< 0.42	< 0.42	< 0.42	< 0.0064	< 0.0064	< 0.0064		< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.0065			< 0.43	< 0.43	< 0.43	< 0.0065	< 0.0065	< 0.0065		< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0066			< 0.43	< 0.43	< 0.43	< 0.0066	< 0.0066	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.0066			< 0.43	< 0.43	< 0.43	< 0.0066	< 0.0066	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0066			< 0.44	< 0.44	< 0.44	< 0.0066	< 0.0066	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0063 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0056 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.0069 U			< 0.46 U	< 0.46 U	< 0.46 U	< 0.0069 U	< 0.0069 U	< 0.0069 U		< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 0.44 U	< 0.44 U	< 0.44 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 0.44 U	< 0.44 U	< 0.44 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.007 U			< 0.46 U	< 0.46 U	< 0.46 U	< 0.007 U	< 0.007 U	< 0.007 U		< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated															
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0057 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.006 U			< 0.39 U	< 0.39 U	< 0.39 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.00056 U	< 0.00072 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00053 U	< 0.00048 U	< 0.00051 U	< 0.00071 U		< 0.00059 U	< 0.0005 U	< 0.00045 U	< 0.00057 U	< 0.0005 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00058 U	< 0.00053 U	< 0.00056 U	< 0.00078 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.00063 U	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00054 U	< 0.00057 U	< 0.00079 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00063 U	< 0.00056 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.00074 U	< 0.00095 U	< 0.00074 U	< 0.00088 U	< 0.00073 U	< 0.0007 U	< 0.00064 U	< 0.00068 U	< 0.00094 U		< 0.00078 U	< 0.00066 U	< 0.0006 U	< 0.00075 U	< 0.00066 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.72	0 - 2 ft	180-35818-1	Excavated	< 0.00069 U	< 0.00088 U	< 0.00068 U	< 0.00082 U	< 0.00067 U	< 0.00065 U	< 0.00059 U	< 0.00063 U	< 0.00087 U		< 0.00072 U	< 0.00061 U	< 0.00056 U	< 0.00069 U	< 0.00061 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00048 U	< 0.00052 U	< 0.00071 U		< 0.00059 U	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.0005 U

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U						< 0.014 U					< 0.0071 U	< 0.0071 U		
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.00052 U	< 0.00086 U	< 0.00056 U	< 0.00055 U	< 0.00073 U	< 0.00058 U	< 0.00071 U	< 0.00053 U	< 0.0006 U	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00068 U	< 0.00071 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.0064 U						< 0.013 U					< 0.0064 U	< 0.0064 U		
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.0067 U						< 0.013 U					< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					0.025	< 0.0065 U		
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					0.016	< 0.0065 U		
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0061 U						< 0.012 U					< 0.0061 U	< 0.0061 U		
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0057 U						< 0.011 U					0.0011 J	< 0.0057 U		
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.0025 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0054 U	< 0.003 U	< 0.0076 U	< 0.0027 U	< 0.0037 U	< 0.0024 U	< 0.0047 U	< 0.0017 U	< 0.0038 U	< 0.0026 U	< 0.0022 U	< 0.0027 U	< 0.0021 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.00068 U	< 0.00096 U	< 0.001 U	< 0.00079 U	< 0.0046 U	0.0023 J	< 0.00095 U	< 0.0013 U	< 0.00054 U	< 0.0007 U	< 0.00053 U	< 0.00054 U	0.0014 J	< 0.00055 U	< 0.00073 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.0007 U	< 0.00099 U	< 0.0011 U	< 0.00082 U	< 0.0047 U	0.0035 J	< 0.00098 U	< 0.0013 U	< 0.00056 U	< 0.00072 U	< 0.00054 U	< 0.00056 U	0.0012 J	< 0.00057 U	< 0.00075 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U,F1	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2624A	PS-FD-1	6/12/2019	855.29	0 - 0.17 ft	180-91215-1	Excavated	< 0.0027 U						< 0.0036 U		< 0.0046 U			< 0.0025 U	< 0.0021 U		
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0044 U	< 0.0046 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.003 U	< 0.0026 U	< 0.0058 U	< 0.0032 U	< 0.0082 U	< 0.0029 U	< 0.004 U	< 0.0026 U	< 0.0051 U	< 0.0018 U	< 0.0041 U	< 0.0028 U	< 0.0023 U	< 0.0049 U	< 0.0052 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.0025 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0043 U	< 0.0046 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0043 U	< 0.0046 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	0.011	< 0.0057 U		< 0.37 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.00036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00079 U	< 0.034 U	< 0.0017 U	< 0.00051 U	< 0.00026 U	< 0.034 U	< 0.0007 U	< 0.00039 U	< 0.034 U	< 0.00032 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.0056 U	0.0027 J	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	0.016	< 0.0056 U		< 0.37 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0058 U	< 0.0058 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.38 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.00028 U	< 0.00093 U	< 0.002 U	< 0.00061 U	< 0.0025 U	< 0.00062 U	< 0.0015 U	< 0.0013 U	< 0.0004 U	< 0.0002 U	< 0.00066 U	< 0.00055 U	< 0.00031 U	< 0.00043 U	< 0.00025 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.42 U
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.0062 U	< 0.0062 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		< 0.41 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0034 U	< 0.0097 U	< 0.0032 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.0059	< 0.0059	< 0.012				< 0.012	< 0.012		< 0.0059	< 0.0059	< 0.0059	< 0.0059		< 0.39
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0018 U	< 0.034 U	< 0.0031 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.0062	< 0.0062	< 0.012				< 0.012	< 0.012		< 0.0062	< 0.0062	< 0.0062	< 0.0062		< 0.41
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.011				< 0.011	< 0.011		< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.37
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0064	< 0.0064	< 0.013				< 0.013	< 0.013		< 0.0064	< 0.0064	< 0.0064	< 0.0064		< 0.42
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.0065	< 0.0065	< 0.013				< 0.013	< 0.013		< 0.0065	< 0.0065	< 0.0065	< 0.0065		< 0.43
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.013				< 0.013	< 0.013		< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.43
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.013				< 0.013	< 0.013		< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.43
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.013				< 0.013	< 0.013		< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.42 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.37 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.0069 U	< 0.0069 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U		< 0.46 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.44 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.44 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.007 U	0.0017 J	< 0.014 U				< 0.014 U	< 0.014 U		< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U		< 0.46 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated		0.0023										0.0018			
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.006 U	< 0.006 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.39 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.00054 U	< 0.00089 U	< 0.00058 U	< 0.00057 U	< 0.00075 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.00059 U	< 0.00098 U	< 0.00063 U	< 0.00062 U	< 0.00083 U	< 0.00067 U	< 0.00081 U	< 0.0006 U	< 0.00069 U	< 0.00065 U	< 0.00066 U	< 0.00062 U	< 0.00067 U	< 0.00078 U	< 0.00081 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.0006 U	< 0.00099 U	< 0.00064 U	< 0.00063 U	< 0.00084 U	< 0.00068 U	< 0.00082 U	< 0.00061 U	< 0.0007 U	< 0.00066 U	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00079 U	< 0.00082 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.00071 U	< 0.0012 U	< 0.00076 U	< 0.00075 U	< 0.001 U	< 0.0008 U	< 0.00098 U	< 0.00072 U	< 0.00083 U	< 0.00078 U	< 0.00079 U	< 0.00075 U	< 0.00081 U	< 0.00093 U	< 0.00098 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.00066 U	< 0.0011 U	< 0.00071 U	< 0.00069 U	< 0.00092 U	< 0.00074 U	< 0.0009 U	< 0.00067 U	< 0.00076 U	< 0.00072 U	< 0.00073 U	< 0.0007 U	< 0.00075 U	< 0.00086 U	< 0.0009 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.00054 U	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U

DRAFT

TABLE 5-4D
Surface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U		< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.00039 U	< 0.00067 U	0.00094 J	< 0.00074 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated			0.0023 J					
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.0064 U		< 0.0064 U		< 0.0064 U	< 0.0064 U	< 0.0064 U	
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.0067 U		< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0061 U		< 0.0061 U		< 0.0061 U	< 0.0061 U	< 0.0061 U	
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0057 U		0.0016 J		< 0.0057 U	< 0.0057 U	< 0.0057 U	
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated				0.0051 J				
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.0027 U	< 0.0026 U	0.0026 J	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0032 U	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0047 U	< 0.0024 U	< 0.0031 U	< 0.0055 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.00049 U	< 0.0008 U	0.0021 J	< 0.0012 U	< 0.0011 U	< 0.00072 U	< 0.00062 U	< 0.0012 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.00051 U	< 0.00083 U	< 0.00058 U	< 0.0013 U	< 0.0011 U	0.001 J	< 0.00064 U	< 0.0012 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2624A	PS-FD-1	6/12/2019	855.29	0 - 0.17 ft	180-91215-1	Excavated	< 0.0031 U		< 0.0019 U		< 0.0045 U			< 0.0053 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft		Not Excavated				0.0051 J				
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0-0.17	8/29/2019	855.15	0 - 0.17 ft	180-95024-2	Excavated	< 0.0031 UJ	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0-0.17	8/29/2019	855.98	0 - 0.17 ft	180-95006-2	Excavated	< 0.0035 U	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0051 U	< 0.0026 U	< 0.0034 U	< 0.006 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0-0.17	8/29/2019	856.91	0 - 0.17 ft	180-95024-2	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0-0.17	8/29/2019	857.12	0 - 0.17 ft	180-95024-2	Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0-0.17	8/29/2019	858.28	0 - 0.17 ft	180-95006-2	Excavated	< 0.0031 U	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-0-0.17	9/17/2021	856.64	0 - 0.17 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00087 U	< 0.034 U	< 0.00087 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0-0.17	9/16/2021	856.07	0 - 0.17 ft	180-127205-2	Excavated	< 0.0003 U	< 0.00053 U	< 0.00089 U	< 0.00038 U	< 0.0005 U	< 0.00068 U	< 0.00053 U	< 0.00068 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated				0.0051 J				
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17	7/1/2021	857.47	0 - 0.17 ft	1801239851	Excavated	< 0.0022 U	< 0.0013 U	< 0.0021 U	< 0.0055 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0095 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0-0.17	7/1/2021	856.76	0 - 0.17 ft	180-123985-1	Excavated	< 0.0019 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 UJ	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B4020	DUP-2	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17	7/1/2021	856.62	0 - 0.17 ft	1801239851	Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	0.0024 J	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	0.0022 J	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059		< 0.0059	
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.0088 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.0062	< 0.0062	< 0.0062	< 0.0062	< 0.0062		< 0.0062	
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.0055	
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064		< 0.0064	
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065		< 0.0065	
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.0066	
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.0066	
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.0066	
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated			< U					
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated								
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated			0.0051 J					
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.00041 U	< 0.00069 U	< 0.00055 U	< 0.00077 U	< 0.00039 U	< 0.0012 U	< 0.00065 U	
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.00045 U	< 0.00076 U	< 0.0006 U	< 0.00084 U	< 0.00043 U	< 0.0013 U	< 0.00072 U	
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.00045 U	< 0.00077 U	0.0024 J	< 0.00086 U	< 0.00044 U	< 0.0014 U	< 0.00073 U	
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.00054 U	< 0.00092 U	0.0025 J	< 0.001 U	< 0.00052 U	< 0.0016 U	< 0.00086 U	
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.0005 U	< 0.00085 U	0.0015 J	< 0.00094 U	< 0.00048 U	< 0.0015 U	< 0.0008 U	
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.00041 U	< 0.0007 U	< 0.00055 U	< 0.00077 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	

TABLE 5-4D
Surface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B70	081514 01:15_SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.006 U	< 0.00081 U	< 0.00083 U	< 0.00068 U	< 0.00053 U	< 0.00089 U	< 0.00062 U	< 0.00054 U	< 0.00091 U	< 0.00086 U	< 0.0019 U	< 0.00071 U	< 0.001 U	< 0.00045 U	< 0.0009 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.0065	< 0.00088	< 0.0009	< 0.00073	< 0.00058	< 0.00096	< 0.00067	< 0.00058	< 0.00099	< 0.00092	< 0.002	< 0.00076	< 0.0011	< 0.00048	< 0.00097
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.0074	< 0.001	< 0.001	< 0.00083	< 0.00066	< 0.0011	< 0.00076	< 0.00066	< 0.0011	< 0.0011	< 0.0023	< 0.00087	< 0.0013	< 0.00055	< 0.0011
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.0066	< 0.00089	< 0.00091	< 0.00074	< 0.00058	< 0.00097	< 0.00068	< 0.00059	< 0.001	< 0.00094	< 0.002	< 0.00077	< 0.0011	< 0.00049	< 0.00099
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U,*	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U,*	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated															
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.029 U	< 0.0072 U						< 0.0072 U	< 0.0072 U			< 0.0072 U			
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0069 U						< 0.0069 U	< 0.0069 U			< 0.0069 U			
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.03 U	< 0.0074 U						< 0.0074 U	< 0.0074 U			< 0.0074 U			
Football Field	SSHS-FB5-A	SSHS-FB5-A-SS	7/21/2014	855.47	0 - 0.17 ft	180-35053-1	Excavated	< 0.0057 U	< 0.00077 U	< 0.00079 U	< 0.00064 U	< 0.00051 U	< 0.00085 U	< 0.00059 U	< 0.00051 U	< 0.00087 U	< 0.00081 U	< 0.0018 U	< 0.00067 U	< 0.00098 U	< 0.00043 U	< 0.00086 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SS	7/21/2014	855.39	0 - 0.17 ft	180-35053-1	Excavated	0.097	< 0.00091 U	< 0.00093 U	< 0.00076 U	< 0.0006 U	< 0.001 U	< 0.00069 U	< 0.0006 U	< 0.001 U	< 0.00096 U	< 0.0021 U	< 0.00079 U	< 0.0012 U	< 0.0005 U	< 0.001 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SS	7/21/2014	855.97	0 - 0.17 ft	180-35053-1	Excavated	0.24	< 0.001 U	< 0.001 U	< 0.00085 U	< 0.00067 U	< 0.0011 U	< 0.00077 U	< 0.00067 U	< 0.0011 U	< 0.0011 U	< 0.0023 U	< 0.00088 U	< 0.0013 U	< 0.00056 U	< 0.0011 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SS	7/21/2014	855.49	0 - 0.17 ft	180-35053-1	Excavated	< 0.0059 U	< 0.0008 U	< 0.00082 U	< 0.00067 U	< 0.00053 U	< 0.00088 U	< 0.00061 U	< 0.00053 U	< 0.0009 U	< 0.00084 U	< 0.0018 U	< 0.0007 U	< 0.001 U	< 0.00044 U	< 0.00089 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SS	7/21/2014	855.42	0 - 0.17 ft	180-35053-1	Excavated	< 0.0056 U	< 0.00076 U	< 0.00078 U	< 0.00063 U	< 0.0005 U	< 0.00083 U	< 0.00058 U	< 0.0005 U	< 0.00086 U	< 0.0008 U	< 0.0018 U	< 0.00066 U	< 0.00096 U	< 0.00042 U	< 0.00085 U
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated															
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.03 U	< 0.0076 U						< 0.0076 U	< 0.0076 U			< 0.0076 U			
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			< 0.0065 U			
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U						< 0.0067 U	< 0.0067 U			< 0.0067 U			
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.022 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.022 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.0071 U						< 0.0071 U	< 0.0071 U			< 0.0071 U			
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			< 0.0065 U			
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0066 U						< 0.0066 U	< 0.0066 U			< 0.0066 U			
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.007 U						< 0.007 U	< 0.007 U			< 0.007 U			
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			0.0021 J			
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.014 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.014 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	0.011 J	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.029 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.014 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.014 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.00081 U	< 0.001 U	< 0.0008 U	< 0.00096 U	< 0.00079 U	< 0.00077 U	< 0.00069 U	< 0.00074 U	< 0.001 U		< 0.00085 U	< 0.00072 U	< 0.00065 U	< 0.00082 U	< 0.00072 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.00088	< 0.0011	< 0.00087	< 0.001	< 0.00085	< 0.00083	< 0.00075	< 0.0008	< 0.0011		< 0.00092	< 0.00078	< 0.00071	< 0.00088	< 0.00078
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.001	< 0.0013	< 0.00099	< 0.0012	< 0.00097	< 0.00094	< 0.00085	< 0.00091	< 0.0013		< 0.001	< 0.00088	< 0.0008	< 0.001	< 0.00089
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.00089	< 0.0011	< 0.00088	< 0.0011	< 0.00087	< 0.00084	< 0.00076	< 0.00081	< 0.0011		< 0.00093	< 0.00079	< 0.00072	< 0.00089	< 0.00079
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	0.0022 J	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated															
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.0072 U						< 0.0072 U	< 0.0072 U	< 0.0072 U		< 0.0072 U	< 0.0072 U			
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0069 U						< 0.0069 U	< 0.0069 U	< 0.0069 U		< 0.0069 U	< 0.0069 U			
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0074 U						< 0.0074 U	< 0.0074 U	< 0.0074 U		< 0.0074 U	< 0.0074 U			
Football Field	SSHS-FB5-A	SSHS-FB5-A-SS	7/21/2014	855.47	0 - 0.17 ft	180-35053-1	Excavated	< 0.00077 U	< 0.00099 U	< 0.00076 U	< 0.00091 U	< 0.00075 U	< 0.00073 U	< 0.00066 U	< 0.0007 U	< 0.00097 U		< 0.00081 U	< 0.00068 U	< 0.00062 U	< 0.00078 U	< 0.00069 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SS	7/21/2014	855.39	0 - 0.17 ft	180-35053-1	Excavated	< 0.00091 U	< 0.0012 U	< 0.0009 U	< 0.0011 U	< 0.00089 U	< 0.00086 U	< 0.00078 U	< 0.00083 U	< 0.0011 U		< 0.00095 U	< 0.00081 U	< 0.00073 U	< 0.00092 U	< 0.00081 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SS	7/21/2014	855.97	0 - 0.17 ft	180-35053-1	Excavated	< 0.001 U	< 0.0013 U	< 0.001 U	< 0.0012 U	< 0.00099 U	< 0.00096 U	< 0.00087 U	< 0.00093 U	< 0.0013 U		< 0.0011 U	< 0.0009 U	< 0.00082 U	< 0.001 U	< 0.0009 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SS	7/21/2014	855.49	0 - 0.17 ft	180-35053-1	Excavated	< 0.0008 U	< 0.001 U	< 0.00079 U	< 0.00095 U	< 0.00078 U	< 0.00076 U	< 0.00068 U	< 0.00073 U	< 0.001 U		< 0.00084 U	< 0.00071 U	< 0.00065 U	< 0.00081 U	< 0.00071 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SS	7/21/2014	855.42	0 - 0.17 ft	180-35053-1	Excavated	< 0.00076 U	< 0.00097 U	< 0.00075 U	< 0.0009 U	< 0.00074 U	< 0.00072 U	< 0.00065 U	< 0.00069 U	< 0.00096 U		< 0.00079 U	< 0.00067 U	< 0.00061 U	< 0.00077 U	< 0.00068 U
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated				< 0.44 U	< 0.44 U	< 0.44 U									
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0076 U			< 0.5 U	< 0.5 U	< 0.5 U	< 0.0076 U	< 0.0076 U	< 0.0076 U		< 0.0076 U	< 0.0076 U			
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0067 U						< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U			
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.0056 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.0055 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U			
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0066 U						< 0.0066 U	< 0.0066 U	< 0.0066 U		< 0.0066 U	< 0.0066 U			
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.007 U			< 0.46 U	< 0.46 U	< 0.46 U	< 0.007 U	< 0.007 U	< 0.007 U		< 0.007 U	< 0.007 U			
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.0065 U			< 0.43 U	< 0.43 U	< 0.43 U	< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.0068 U			< 0.45 U	< 0.45 U	< 0.45 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 0.44 U	< 0.44 U	< 0.44 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.0068 U			< 0.45 U	< 0.45 U	< 0.45 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.00077 U	< 0.0013 U	< 0.00083 U	< 0.00082 U	< 0.0011 U	< 0.00087 U	< 0.0011 U	< 0.00079 U	< 0.0009 U	< 0.00085 U	< 0.00087 U	< 0.00082 U	< 0.00088 U	< 0.001 U	< 0.0011 U
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.00084	< 0.0014	< 0.0009	< 0.00088	< 0.0012	< 0.00094	< 0.0011	< 0.00085	< 0.00097	< 0.00092	< 0.00094	< 0.00089	< 0.00095	< 0.0011	< 0.0011
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.00095	< 0.0016	< 0.001	< 0.001	< 0.0013	< 0.0011	< 0.0013	< 0.00097	< 0.0011	< 0.001	< 0.0011	< 0.001	< 0.0011	< 0.0013	< 0.0013
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.00085	< 0.0014	< 0.00091	< 0.00089	< 0.0012	< 0.00096	< 0.0012	< 0.00086	< 0.00099	< 0.00093	< 0.00095	< 0.0009	< 0.00096	< 0.0011	< 0.0012
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated															
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.0072 U						< 0.014 U					< 0.0072 U	< 0.0072 U		
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0069 U						< 0.014 U					< 0.0069 U	< 0.0069 U		
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0074 U						< 0.015 U					< 0.0074 U	< 0.0074 U		
Football Field	SSHS-FB5-A	SSHS-FB5-A-SS	7/21/2014	855.47	0 - 0.17 ft	180-35053-1	Excavated	< 0.00074 U	< 0.0012 U	< 0.00079 U	< 0.00078 U	< 0.001 U	< 0.00083 U	< 0.001 U	< 0.00075 U	< 0.00086 U	< 0.00081 U	< 0.00082 U	< 0.00078 U	< 0.00084 U	< 0.00097 U	< 0.001 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SS	7/21/2014	855.39	0 - 0.17 ft	180-35053-1	Excavated	< 0.00087 U	< 0.0014 U	< 0.00093 U	< 0.00092 U	< 0.0012 U	< 0.00098 U	< 0.0012 U	< 0.00088 U	< 0.001 U	< 0.00095 U	< 0.00097 U	< 0.00092 U	< 0.00099 U	< 0.0011 U	< 0.0012 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SS	7/21/2014	855.97	0 - 0.17 ft	180-35053-1	Excavated	< 0.00097 U	< 0.0016 U	< 0.001 U	< 0.001 U	< 0.0014 U	< 0.0011 U	< 0.0013 U	< 0.00098 U	< 0.0011 U	< 0.0011 U	< 0.0011 U	< 0.001 U	< 0.0011 U	< 0.0013 U	< 0.0013 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SS	7/21/2014	855.49	0 - 0.17 ft	180-35053-1	Excavated	< 0.00076 U	< 0.0013 U	< 0.00082 U	< 0.00081 U	< 0.0011 U	< 0.00086 U	< 0.001 U	< 0.00078 U	< 0.00089 U	< 0.00084 U	< 0.00085 U	< 0.00081 U	< 0.00087 U	< 0.001 U	< 0.001 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SS	7/21/2014	855.42	0 - 0.17 ft	180-35053-1	Excavated	< 0.00073 U	< 0.0012 U	< 0.00078 U	< 0.00077 U	< 0.001 U	< 0.00082 U	< 0.001 U	< 0.00074 U	< 0.00084 U	< 0.0008 U	< 0.00081 U	< 0.00077 U	< 0.00082 U	< 0.00095 U	< 0.001 U
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated															
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0076 U						< 0.015 U					0.082	< 0.0076 U		
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					< 0.0065 U	< 0.0065 U		
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0067 U						< 0.013 U					< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	0.027	< 0.0056 U		< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U						< 0.014 U					0.023	< 0.0071 U		
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					< 0.0065 U	< 0.0065 U		
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0066 U						< 0.013 U					< 0.0066 U	< 0.0066 U		
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.007 U						< 0.014 U					0.0036 J	< 0.007 U		
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					0.004 J	< 0.0065 U		
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0068 U	< 0.0068 U	0.0079	< 0.0068 U		< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0067 U	< 0.0067 U	0.036	< 0.0067 U		< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0071 U	< 0.0071 U	0.01	< 0.0071 U		< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0068 U	< 0.0068 U	0.037	< 0.0068 U		< 0.45 U

DRAFT

TABLE 5-4D
Surface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated			0.0051 J					
Football Field	SSHS-B70	081514 01:15 SSHS-B70-SS	8/14/2014	855.98	0 - 0.17 ft	180-35818-2	Excavated	< 0.00059 U	< 0.001 U	< 0.00079 U	< 0.0011 U	< 0.00057 U	< 0.0018 U	< 0.00094 U	
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	8/14/2014	856.08	0 - 0.17 ft	180-35818-2	Excavated	< 0.00063	< 0.0011	< 0.00086	< 0.0012	< 0.00061		< 0.001	
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	8/14/2014	856.25	0 - 0.17 ft	180-35818-1	Excavated	< 0.00072	< 0.0012	< 0.00097	< 0.0014	< 0.0007		< 0.0012	
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	8/14/2014	855.88	0 - 0.17 ft	180-35818-1	Excavated	< 0.00064	< 0.0011	< 0.00087	< 0.0012	< 0.00062		< 0.001	
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated			0.0051 J					
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0025 U	< 0.0024 U	0.0024 J	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated			< U					
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0028 U	< 0.0027 U	0.016	< 0.0016 U	< 0.0041 U		< 0.0027 U	< 0.0048 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U		< 0.0026 U	< 0.0045 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated			< U					
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.0072 U		< 0.0072 U		< 0.0072 U	< 0.0072 U	< 0.0072 U	
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0069 U		< 0.0069 U		< 0.0069 U	< 0.0069 U	< 0.0069 U	
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0074 U		< 0.0074 U		< 0.0074 U	< 0.0074 U	< 0.0074 U	
Football Field	SSHS-FB5-A	SSHS-FB5-A-SS	7/21/2014	855.47	0 - 0.17 ft	180-35053-1	Excavated	< 0.00056 U	< 0.00095 U	< 0.00075 U	< 0.0011 U	< 0.00054 U	< 0.0017 U	< 0.00089 U	
Football Field	SSHS-FB5-B	SSHS-FB5-B-SS	7/21/2014	855.39	0 - 0.17 ft	180-35053-1	Excavated	< 0.00066 U	< 0.0011 U	< 0.00089 U	< 0.0012 U	< 0.00063 U	< 0.002 U	< 0.0011 U	
Football Field	SSHS-FB5-C	SSHS-FB5-C-SS	7/21/2014	855.97	0 - 0.17 ft	180-35053-1	Excavated	< 0.00073 U	< 0.0013 U	< 0.00099 U	< 0.0014 U	< 0.00071 U	< 0.0022 U	< 0.0012 U	
Football Field	SSHS-FB5-D	SSHS-FB5-D-SS	7/21/2014	855.49	0 - 0.17 ft	180-35053-1	Excavated	< 0.00058 U	< 0.00099 U	< 0.00078 U	< 0.0011 U	< 0.00056 U	< 0.0017 U	< 0.00093 U	
Football Field	SSHS-FB5-E	SSHS-FB5-E-SS	7/21/2014	855.42	0 - 0.17 ft	180-35053-1	Excavated	< 0.00055 U	< 0.00094 U	< 0.00074 U	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.00088 U	
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated								
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0076 U		< 0.0076 U		< 0.0076 U	< 0.0076 U	< 0.0076 U	
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0067 U		< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U		< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0066 U		< 0.0066 U		< 0.0066 U	< 0.0066 U	< 0.0066 U	
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.007 U		< 0.007 U		< 0.007 U	< 0.007 U	< 0.007 U	
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	

DRAFT

																						Emerging C
										1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
										ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted										100	100	100									
Restricted - Residential										13000	13000	13000									
Protection of Groundwater										100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status														
Football Field	SSHS-B2026	073118 08:50 SSHS-B2026-SS	SSHS-B2026-SS	855.26	0 - 0.17 ft	180-80275-1	Not Excavated					< 20 U									
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	856.74	0 - 0.17 ft	180-101269-1	Not Excavated					< 130 U									
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	856.80	0 - 0.17 ft	180-123985-1	Not Excavated					< 120 U									
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	856.74	0 - 0.17 ft	1801239851	Not Excavated	< 110 U			< 0.36 U	< 0.024 U	0.15 J	< 0.038 U	0.075 J	< 0.066 U	< 0.034 U	0.088 J	< 0.030 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	856.88	0 - 0.17 ft	1801239851	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	0.20 J	< 0.041 U	0.11 J	< 0.071 U	< 0.037 U	0.10 J	< 0.033 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	857.18	0 - 0.17 ft	1801239851	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.17 J	< 0.042 U	0.10 J	< 0.073 U	< 0.038 U	0.11 J	< 0.034 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	857.75	0 - 0.17 ft	1801239851	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.27	< 0.045 U	0.085 J	< 0.077 U	< 0.040 U	0.12 J	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	855.65	0 - 0.17 ft	180-57995-1	Not Excavated			< 46 U											
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SS	SSHS-B406-SS	855.97	0 - 0.17 ft	180-57995-1	Not Excavated			< 49 U											
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	855.73	0 - 0.17 ft	180-127066-2	Not Excavated			< 120 U	< 0.056 U	< 0.044 U	< 0.054 U	< 0.06 U	< 0.056 U	< 0.035 U	< 0.057 U	< 0.044 U	< 0.034 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	856.20	0 - 2 ft	180-80252-1	Not Excavated			< 44 U											
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	856.45	0 - 2 ft	180-57995-1	Not Excavated			< 42											
Rear Parking Lot	SSHS-B568	092316 08:45 SSHS-B568-SUB-0-2	SSHS-B568-SUB-0-2	851.24	0 - 2 ft	180-59020-1	Not Excavated			< 39 U											
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-0.17-2 (1)	SSHS-B68-0.17-2 (1)	852.07	0 - 2 ft	180-35818-1	Not Excavated			< 41 U											
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-0.17-2 (1)	SSHS-B69-0.17-2 (1)	850.53	0 - 2 ft	180-35818-1	Not Excavated			< 42 U											
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	855.66	0 - 2 ft	180-66622-2	Not Excavated			< 55 U											
Northern Athletic Field	SCV67A-0.17-1	SSHS-IRM5A2-SCV67A-0.17-1-20221214	SSHS-IRM5A2-SCV67A-0.17-1	–	0.17-1	1801493712	Not Excavated				< 0.063 U	< 0.050 U	0.50	< 0.068 U	0.10 J	0.045 J	< 0.064 U	0.16 J	< 0.038 U
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-0.17-2-20230118	SSHS-PDI6-B5105-SUB-0.17-2	855.73	0.17-2	1801508221	Not Excavated	< 110 U											
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-0.17-2-20230209	SSHS-PDI6-B5109-SUB-0.17-2	852.78	0.17-2	1801518942	Not Excavated	< 110 U											
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	852.51	0 - 2 ft	1801219031	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.031 U	< 0.034 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	852.51	0 - 2 ft	1801164042	Not Excavated	< 130 U			< 0.46 U	< 0.031 U	0.67 B	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U	< 0.036 U	< 0.038 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	853.96	0 - 2 ft	1801239851	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	0.087 J	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U	0.034 J	< 0.033 U
Northern Athletic Field	SSHS-B2024	073118 08:50 SSHS-B2024-SS	SSHS-B2024-SS	852.76	0 - 0.17 ft	180-80275-1	Excavated			< 21 U											
Football Field	SSHS-B2025	073118 08:50 SSHS-B2025-SS	SSHS-B2025-SS	854.55	0 - 0.17 ft	180-80275-1	Excavated			< 20 U											
Football Field	SSHS-B2027	073118 08:50 SSHS-B2027-SS	SSHS-B2027-SS	855.22	0 - 0.17 ft	180-80275-1	Excavated			< 20 U											
Football Field	SSHS-B2028	073118 08:50 SSHS-B2028-SS	SSHS-B2028-SS	855.23	0 - 0.17 ft	180-80275-1	Excavated			< 20 U											
Football Field	SSHS-B2031	073118 08:50 FD-57	FD-57	855.50	0 - 0.17 ft	180-80275-1	Excavated			< 38 U											
Football Field	SSHS-B2031	073118 08:50 SSHS-B2031-SS	SSHS-B2031-SS	855.50	0 - 0.17 ft	180-80275-1	Excavated			< 19 U											
Football Field	SSHS-B2032	073118 08:50 SSHS-B2032-SS	SSHS-B2032-SS	854.88	0 - 0.17 ft	180-80275-1	Excavated			< 19 U											
Football Field	SSHS-B2033	073118 08:50 SSHS-B2033-SS	SSHS-B2033-SS	854.70	0 - 0.17 ft	180-80275-1	Excavated			< 18 U											
Football Field	SSHS-B2050	073118 08:50 SSHS-B2050-SS	SSHS-B2050-SS	855.45	0 - 0.17 ft	180-80275-1	Excavated			< 22 U											
Football Field	SSHS-B2051	073118 08:50 SSHS-B2051-SS	SSHS-B2051-SS	855.08	0 - 0.17 ft	180-80275-1	Excavated			< 21 U											
Football Field	SSHS-B2053	073118 08:50 SSHS-B2053-SS	SSHS-B2053-SS	855.00	0 - 0.17 ft	180-80275-1	Excavated			< 20 U											
Football Field	SSHS-B2070	073118 08:50 SSHS-B2070-SS	SSHS-B2070-SS	854.72	0 - 0.17 ft	180-80275-1	Excavated			< 21 U											
Football Field	SSHS-B2071	072518 09:00 SSHS-B2071-SS	SSHS-B2071-SS	856.16	0 - 0.17 ft	180-80105-2	Excavated			< 22 U											
Football Field	SSHS-B2072	072518 09:00 SSHS-B2072-SS	SSHS-B2072-SS	856.82	0 - 0.17 ft	180-80105-2	Excavated			< 22 U											
Football Field	SSHS-B2073	072518 09:00 SSHS-B2073-SS	SSHS-B2073-SS	856.99	0 - 0.17 ft	180-80105-2	Excavated			< 21 U											
Football Field	SSHS-B2089	072718 09:00 SSHS-B2089-SS	SSHS-B2089-SS	855.40	0 - 0.17 ft	180-80225-3	Excavated			< 20 U											
Football Field	SSHS-B2091	072518 09:00 SSHS-B2091-SS	SSHS-B2091-SS	856.61	0 - 0.17 ft	180-80105-3	Excavated			< 22 U											
Football Field	SSHS-B2092	072518 09:00 SSHS-B2092-SS	SSHS-B2092-SS	856.77	0 - 0.17 ft	180-80105-2	Excavated			< 22 U											
Football Field	SSHS-B2108	072718 09:00 SSHS-B2108-SS	SSHS-B2108-SS	855.64	0 - 0.17 ft	180-80225-3	Excavated			< 21 U											
Football Field	SSHS-B2109	072718 09:00 SSHS-B2109-SS	SSHS-B2109-SS	855.25	0 - 0.17 ft	180-80225-3	Excavated			< 22 U											
Football Field	SSHS-B2110	072718 09:00 SSHS-B2110-SS	SSHS-B2110-SS	854.78	0 - 0.17 ft	180-80225-3	Excavated			< 27 U											
Football Field	SSHS-B2127	073118 08:50 SSHS-B2127-SS	SSHS-B2127-SS	855.91	0 - 0.17 ft	180-80275-1	Excavated			< 20 U											
Football Field	SSHS-B2128	073118 08:50 SSHS-B2128-SS	SSHS-B2128-SS	856.01	0 - 0.17 ft	180-80275-1	Excavated			< 22 U											
Football Field	SSHS-B2129	073118 08:50 SSHS-B2129-SS	SSHS-B2129-SS	855.33	0 - 0.17 ft	180-80275-1	Excavated			< 21 U											
Football Field	SSHS-B2143	073118 08:50 SSHS-B2143-SS	SSHS-B2143-SS	856.56	0 - 0.17 ft	180-80275-1	Excavated			< 20 U											
Football Field	SSHS-B2192	073118 08:50 SSHS-B2192-SS	SSHS-B2192-SS	855.49	0 - 0.17 ft	180-80275-1	Excavated			< 21 U											
Football Field	SSHS-B2193	072518 09:00 SSHS-B2193-SS	SSHS-B2193-SS	857.04	0 - 0.17 ft	180-80105-2	Excavated			< 21 U											
Football Field	SSHS-B2194	072518 09:00 SSHS-B2194-SS	SSHS-B2194-SS	856.19	0 - 0.17 ft	180-80105-2	Excavated			< 22 U											
Football Field	SSHS-B2195	072518 09:00 SSHS-B2195-SS	SSHS-B2195-SS	855.94	0 - 0.17 ft	180-80105-2	Excavated			< 22 U											
Football Field	SSHS-B2214	072518 09:00 SSHS-B2214-SS	SSHS-B2214-SS	855.14	0 - 0.17 ft	180-80105-2	Excavated			< 21 U											
Football Field	SSHS-B2215	072518 09:00 SSHS-B2215-SS	SSHS-B2215-SS	855.11	0 - 0.17 ft	180-80105-2	Excavated			< 20 U											
Football Field	SSHS-B2217	072718 09:00 SSHS-B2217-SS	SSHS-B2217-SS	855.08	0 - 0.17 ft	180-80225-3	Excavated			< 24 U											
Football Field	SSHS-B2221	072618 08:50 SSHS-B2221-SS	SSHS-B2221-SS	855.38	0 - 0.17 ft	180-80157-2	Excavated			< 22 U											
Football Field	SSHS-B2222	072618 08:50 SSHS-B2222-SS	SSHS-B2222-SS	855.74	0 - 0.17 ft	180-80157-2	Excavated			< 23 U											
Football Field	SSHS-B2223	072618 08:50 SSHS-B2223-SS	SSHS-B2223-SS	856.38	0 - 0.17 ft	180-80157-2	Excavated			< 28 U											
Football Field	SSHS-B2224	072618 08:50 SSHS-B2224-SS	SSHS-B2224-SS	854.93	0 - 0.17 ft	180-80157-2	Excavated			< 26 U											
Football Field	SSHS-B2225	072618 08:50 SSHS-B2225-SS	SSHS-B2225-SS	857.03	0 - 0.17 ft	180-80157-2	Excavated			< 21 U											
Football Field	SSHS-B2226	072618 08:50 SSHS-B2226-SS	SSHS-B2226-SS	856.56	0 - 0.17 ft	180-80157-2	Excavated			< 23 U											
Football Field	SSHS-B2228	072518 09:00 SSHS-B2228-SS	SSHS-B2228-SS	855.33	0 - 0.17 ft	180-80106-3	Excavated			< 28 U											
Football Field	SSHS-B2229	073118 08:50 SSHS-B2229-SS	SSHS-B2229-SS	855.28	0 - 0.17 ft	180-80275-1	Excavated			< 18 U											
Football Field	SSHS-B2231	072518 09:00 SSHS-B2231-SS	SSHS-B2231-SS	856.14	0 - 0.17 ft	180-80106-3	Excavated			< 17 U											
Football Field	SSHS-B2232	072618 08:50 SSHS-B2232-SS	SSHS-B2232-SS	856.82	0 - 0.17 ft	180-80157-2	Excavated			< 22 U											

DRAFT

TABLE 5-4E
Surface Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2026	073118 08:50 SSHS-B2026-SS	SSHS-B2026-SS	855.26	0 - 0.17 ft	180-80275-1	Not Excavated												
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	856.74	0 - 0.17 ft	180-101269-1	Not Excavated												
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	856.80	0 - 0.17 ft	180-123985-1	Not Excavated												
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	856.74	0 - 0.17 ft	1801239851	Not Excavated	0.069 J	0.13 J	< 0.080 U	0.35 J	0.18 J	< 0.075 U	< 0.053 U	< 0.050 U	0.081 J	< 0.24 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	856.88	0 - 0.17 ft	1801239851	Not Excavated	0.083 J	0.13 J	< 0.087 U	0.52 J	0.27	< 0.082 U	< 0.057 U	< 0.054 U	0.082 J	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	857.18	0 - 0.17 ft	1801239851	Not Excavated	0.092 J	0.15 J	< 0.089 U	0.55	0.26	< 0.084 U	< 0.059 U	< 0.056 U	0.12 J	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	857.75	0 - 0.17 ft	1801239851	Not Excavated	0.096 J	0.18 J	< 0.094 U	0.46 J	0.36	< 0.088 U	< 0.062 U	< 0.059 U	0.094 J	< 0.29 U	< 0.17 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	855.65	0 - 0.17 ft	180-57995-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SS	SSHS-B406-SS	855.97	0 - 0.17 ft	180-57995-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	855.73	0 - 0.17 ft	180-127066-2	Not Excavated	< 0.036 U	0.04 J	< 34 U	0.15 J	0.073 J	< 0.048 U	< 0.043 U	< 34 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	856.20	0 - 2 ft	180-80252-1	Not Excavated												
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	856.45	0 - 2 ft	180-57995-1	Not Excavated												
Rear Parking Lot	SSHS-B568	092316 08:45 SSHS-B568-SUB-0-2	SSHS-B568-SUB-0-2	851.24	0 - 2 ft	180-59020-1	Not Excavated												
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-0.17-2 (1)	SSHS-B68-0.17-2 (1)	852.07	0 - 2 ft	180-35818-1	Not Excavated												
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-0.17-2 (1)	SSHS-B69-0.17-2 (1)	850.53	0 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	855.66	0 - 2 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SCV67A-0.17-1	SSHS-IRM5A2-SCV67A-0.17-1-20221214	SSHS-IRM5A2-SCV67A-0.17-1	--	0.17-1	1801493712	Not Excavated	0.096 J	0.21 J	< 0.043 U	1.2	0.47	0.14 J	< 0.048 U	0.037 J	0.11 J	< 0.046 U	< 0.035 U	< 0.030 U
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-0.17-2-20230118	SSHS-PDI6-B5105-SUB-0.17-2	855.73	0.17-2	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-0.17-2-20230209	SSHS-PDI6-B5109-SUB-0.17-2	852.78	0.17-2	1801518942	Not Excavated												
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	852.51	0 - 2 ft	1801219031	Not Excavated	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.059 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	852.51	0 - 2 ft	1801164042	Not Excavated	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	853.96	0 - 2 ft	1801239851	Not Excavated	0.075 J	< 0.038 U	< 0.086 U	0.25 J	0.11 J	< 0.081 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B2024	073118 08:50 SSHS-B2024-SS	SSHS-B2024-SS	852.76	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2025	073118 08:50 SSHS-B2025-SS	SSHS-B2025-SS	854.55	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2027	073118 08:50 SSHS-B2027-SS	SSHS-B2027-SS	855.22	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2028	073118 08:50 SSHS-B2028-SS	SSHS-B2028-SS	855.23	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2031	073118 08:50 FD-57	FD-57	855.50	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2031	073118 08:50 SSHS-B2031-SS	SSHS-B2031-SS	855.50	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2032	073118 08:50 SSHS-B2032-SS	SSHS-B2032-SS	854.88	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2033	073118 08:50 SSHS-B2033-SS	SSHS-B2033-SS	854.70	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2050	073118 08:50 SSHS-B2050-SS	SSHS-B2050-SS	855.45	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2051	073118 08:50 SSHS-B2051-SS	SSHS-B2051-SS	855.08	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2053	073118 08:50 SSHS-B2053-SS	SSHS-B2053-SS	855.00	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2070	073118 08:50 SSHS-B2070-SS	SSHS-B2070-SS	854.72	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2071	072518 09:00 SSHS-B2071-SS	SSHS-B2071-SS	856.16	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2072	072518 09:00 SSHS-B2072-SS	SSHS-B2072-SS	856.82	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2073	072518 09:00 SSHS-B2073-SS	SSHS-B2073-SS	856.99	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2089	072718 09:00 SSHS-B2089-SS	SSHS-B2089-SS	855.40	0 - 0.17 ft	180-80225-3	Excavated												
Football Field	SSHS-B2091	072518 09:00 SSHS-B2091-SS	SSHS-B2091-SS	856.61	0 - 0.17 ft	180-80105-3	Excavated												
Football Field	SSHS-B2092	072518 09:00 SSHS-B2092-SS	SSHS-B2092-SS	856.77	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2108	072718 09:00 SSHS-B2108-SS	SSHS-B2108-SS	855.64	0 - 0.17 ft	180-80225-3	Excavated												
Football Field	SSHS-B2109	072718 09:00 SSHS-B2109-SS	SSHS-B2109-SS	855.25	0 - 0.17 ft	180-80225-3	Excavated												
Football Field	SSHS-B2110	072718 09:00 SSHS-B2110-SS	SSHS-B2110-SS	854.78	0 - 0.17 ft	180-80225-3	Excavated												
Football Field	SSHS-B2127	073118 08:50 SSHS-B2127-SS	SSHS-B2127-SS	855.91	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2128	073118 08:50 SSHS-B2128-SS	SSHS-B2128-SS	856.01	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2129	073118 08:50 SSHS-B2129-SS	SSHS-B2129-SS	855.33	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2143	073118 08:50 SSHS-B2143-SS	SSHS-B2143-SS	856.56	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2192	073118 08:50 SSHS-B2192-SS	SSHS-B2192-SS	855.49	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2193	072518 09:00 SSHS-B2193-SS	SSHS-B2193-SS	857.04	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2194	072518 09:00 SSHS-B2194-SS	SSHS-B2194-SS	856.19	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2195	072518 09:00 SSHS-B2195-SS	SSHS-B2195-SS	855.94	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2214	072518 09:00 SSHS-B2214-SS	SSHS-B2214-SS	855.14	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2215	072518 09:00 SSHS-B2215-SS	SSHS-B2215-SS	855.11	0 - 0.17 ft	180-80105-2	Excavated												
Football Field	SSHS-B2217	072718 09:00 SSHS-B2217-SS	SSHS-B2217-SS	855.08	0 - 0.17 ft	180-80225-3	Excavated												
Football Field	SSHS-B2221	072618 08:50 SSHS-B2221-SS	SSHS-B2221-SS	855.38	0 - 0.17 ft	180-80157-2	Excavated												
Football Field	SSHS-B2222	072618 08:50 SSHS-B2222-SS	SSHS-B2222-SS	855.74	0 - 0.17 ft	180-80157-2	Excavated												
Football Field	SSHS-B2223	072618 08:50 SSHS-B2223-SS	SSHS-B2223-SS	856.38	0 - 0.17 ft	180-80157-2	Excavated												
Football Field	SSHS-B2224	072618 08:50 SSHS-B2224-SS	SSHS-B2224-SS	854.93	0 - 0.17 ft	180-80157-2	Excavated												
Football Field	SSHS-B2225	072618 08:50 SSHS-B2225-SS	SSHS-B2225-SS	857.03	0 - 0.17 ft	180-80157-2	Excavated												
Football Field	SSHS-B2226	072618 08:50 SSHS-B2226-SS	SSHS-B2226-SS	856.56	0 - 0.17 ft	180-80157-2	Excavated												
Football Field	SSHS-B2228	072518 09:00 SSHS-B2228-SS	SSHS-B2228-SS	855.33	0 - 0.17 ft	180-80106-3	Excavated												
Football Field	SSHS-B2229	073118 08:50 SSHS-B2229-SS	SSHS-B2229-SS	855.28	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2231	072518 09:00 SSHS-B2231-SS	SSHS-B2231-SS	856.14	0 - 0.17 ft	180-80106-3	Excavated												
Football Field	SSHS-B2232	072618 08:50 SSHS-B2232-SS	SSHS-B2232-SS	856.82	0 - 0.17 ft	180-80157-2	Excavated												

DRAFT

								Emerging C										
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2233	073118 08:50_SSHS-B2233-SS	SSHS-B2233-SS	854.83	0 - 0.17 ft	180-80275-1	Excavated			< 21 U									
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-SS	SSHS-B2234-SUB-SS	855.41	0 - 0.17 ft	180-80091-4	Excavated			< 18 U									
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-SS	SSHS-B2235-SUB-SS	855.30	0 - 0.17 ft	180-80091-4	Excavated			< 17 U									
Football Field	SSHS-B2236	072618 08:50_SSHS-B2236-SS	SSHS-B2236-SS	855.25	0 - 0.17 ft	180-80157-3	Excavated			< 20 U									
Football Field	SSHS-B2237	072518 09:00_SSHS-B2237-SS	SSHS-B2237-SS	855.30	0 - 0.17 ft	180-80106-3	Excavated			< 34 U									
Football Field	SSHS-B2238	072418 08:50_SSHS-B2238-SUB-SS	SSHS-B2238-SUB-SS	855.07	0 - 0.17 ft	180-80091-4	Excavated			< 17 U									
Northern Athletic Field	SSHS-B3001	083019 09:00_SSHS-B3001-SUB-0-0.17	SSHS-B3001-SUB-0-0.17	853.35	0 - 0.17 ft	180-95024-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3002	083019 09:00_SSHS-B3002-SUB-0-0.17	SSHS-B3002-SUB-0-0.17	853.09	0 - 0.17 ft	180-95006-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3003	083019 09:00_SSHS-B3003-SUB-0-0.17	SSHS-B3003-SUB-0-0.17	851.95	0 - 0.17 ft	180-95006-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3016-SUB-0-0.17	SSHS-B3016-SUB-0-0.17	852.36	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3007	082719 09:30_SSHS-B3007-SUB-0-0.17	SSHS-B3007-SUB-0-0.17	852.58	0 - 0.17 ft	180-94754-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3009	083019 09:00_SSHS-B3009-SUB-0-0.17	SSHS-B3009-SUB-0-0.17	853.88	0 - 0.17 ft	180-95024-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3011	083019 09:00_SSHS-B3011-SUB-0-0.17	SSHS-B3011-SUB-0-0.17	853.85	0 - 0.17 ft	180-95006-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3012	083019 09:00_SSHS-B3012-SUB-0-0.17	SSHS-B3012-SUB-0-0.17	853.28	0 - 0.17 ft	180-95006-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3013	090519 09:00_SSHS-B3013-SUB-0-0.17	SSHS-B3013-SUB-0-0.17	852.90	0 - 0.17 ft	180-95165-4	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3014	082919 09:10_SSHS-B3014-SUB-0-0.17	SSHS-B3014-SUB-0-0.17	853.35	0 - 0.17 ft	180-94903-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3015	082919 09:10_SSHS-B3015-SUB-0-0.17	SSHS-B3015-SUB-0-0.17	853.51	0 - 0.17 ft	180-94902-3	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3017	082819 09:00_SSHS-B3017-SUB-0-0.17	SSHS-B3017-SUB-0-0.17	853.78	0 - 0.17 ft	180-94829-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-0-0.17	SSHS-B3018-SUB-0-0.17	853.82	0 - 0.17 ft	180-94829-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3019	082719 09:30_SSHS-B3019-SUB-0-0.17	SSHS-B3019-SUB-0-0.17	854.09	0 - 0.17 ft	180-94754-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3020	082719 09:30_SSHS-B3020-SUB-0-0.17	SSHS-B3020-SUB-0-0.17	853.86	0 - 0.17 ft	180-94754-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-0-0.17	SSHS-B3022-SUB-0-0.17	853.76	0 - 0.17 ft	180-94754-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3023	083019 09:00_SSHS-B3023-SUB-0-0.17	SSHS-B3023-SUB-0-0.17	854.48	0 - 0.17 ft	180-95024-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3025	083019 09:00_SSHS-B3025-SUB-0-0.17	SSHS-B3025-SUB-0-0.17	854.59	0 - 0.17 ft	180-95006-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3026	082919 09:10_SSHS-B3026-SUB-0-0.17	SSHS-B3026-SUB-0-0.17	854.13	0 - 0.17 ft	180-94903-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3028	082819 09:00_SSHS-B3028-SUB-0-0.17	SSHS-B3028-SUB-0-0.17	854.60	0 - 0.17 ft	180-94829-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3030	082819 09:00_SSHS-B3030-SUB-0-0.17	SSHS-B3030-SUB-0-0.17	855.22	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3031	082719 09:30_SSHS-B3031-SUB-0-0.17	SSHS-B3031-SUB-0-0.17	855.08	0 - 0.17 ft	180-94754-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3033	082719 09:30_SSHS-B3033-SUB-0-0.17	SSHS-B3033-SUB-0-0.17	855.17	0 - 0.17 ft	180-94754-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-0-0.17	SSHS-B3034-SUB-0-0.17	855.10	0 - 0.17 ft	180-94752-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-0-0.17	SSHS-B3035-SUB-0-0.17	854.81	0 - 0.17 ft	180-94752-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3036	083019 09:00_SSHS-B3036-SUB-0-0.17	SSHS-B3036-SUB-0-0.17	855.09	0 - 0.17 ft	180-95024-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3037	083019 09:00_SSHS-B3037-SUB-0-0.17	SSHS-B3037-SUB-0-0.17	855.60	0 - 0.17 ft	180-95006-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3038	083019 09:00_SSHS-B3038-SUB-0-0.17	SSHS-B3038-SUB-0-0.17	855.76	0 - 0.17 ft	180-95006-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3039	083019 09:00_SSHS-B3039-SUB-0-0.17	SSHS-B3039-SUB-0-0.17	855.85	0 - 0.17 ft	180-95006-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3040	082919 09:10_SSHS-B3040-SUB-0-0.17	SSHS-B3040-SUB-0-0.17	855.10	0 - 0.17 ft	180-94903-1	Excavated			< 150 U									
Northern Athletic Field	SSHS-B3041	082919 09:10_SSHS-B3041-SUB-0-0.17	SSHS-B3041-SUB-0-0.17	855.17	0 - 0.17 ft	180-94903-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3042	082919 09:10_SSHS-B3042-SUB-0-0.17	SSHS-B3042-SUB-0-0.17	855.23	0 - 0.17 ft	180-94903-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3043	082819 09:00_SSHS-B3043-SUB-0-0.17	SSHS-B3043-SUB-0-0.17	855.78	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3044	082819 09:00_SSHS-B3044-SUB-0-0.17	SSHS-B3044-SUB-0-0.17	856.00	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3045	082819 09:00_SSHS-B3045-SUB-0-0.17	SSHS-B3045-SUB-0-0.17	856.03	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3046	082719 09:30_SSHS-B3046-SUB-0-0.17	SSHS-B3046-SUB-0-0.17	856.22	0 - 0.17 ft	180-94754-2	Excavated			< 150 U									
Northern Athletic Field	SSHS-B3048	082719 09:30_SSHS-B3048-SUB-0-0.17	SSHS-B3048-SUB-0-0.17	856.08	0 - 0.17 ft	180-94754-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-0-0.17	SSHS-B3049-SUB-0-0.17	856.17	0 - 0.17 ft	180-94754-2	Excavated			< 150 U									
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-0-0.17	SSHS-B3050-SUB-0-0.17	855.60	0 - 0.17 ft	180-94752-1	Excavated			< 150 U									
Northern Athletic Field	SSHS-B3051	083019 09:00_SSHS-B3051-SUB-0-0.17	SSHS-B3051-SUB-0-0.17	855.15	0 - 0.17 ft	180-95024-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3052	083019 09:00_SSHS-B3052-SUB-0-0.17	SSHS-B3052-SUB-0-0.17	855.98	0 - 0.17 ft	180-95006-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3053	083019 09:00_SSHS-B3053-SUB-0-0.17	SSHS-B3053-SUB-0-0.17	856.41	0 - 0.17 ft	180-95006-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-0-0.17	SSHS-B3054-SUB-0-0.17	856.01	0 - 0.17 ft	180-95006-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3055	082919 09:10_SSHS-B3055-SUB-0-0.17	SSHS-B3055-SUB-0-0.17	856.20	0 - 0.17 ft	180-94903-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3056	082919 09:10_SSHS-B3056-SUB-0-0.17	SSHS-B3056-SUB-0-0.17	855.88	0 - 0.17 ft	180-94902-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-0-0.17	SSHS-B3057-SUB-0-0.17	856.09	0 - 0.17 ft	180-94903-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3058	082819 09:00_SSHS-B3058-SUB-0-0.17	SSHS-B3058-SUB-0-0.17	856.47	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3059	082819 09:00_SSHS-B3059-SUB-0-0.17	SSHS-B3059-SUB-0-0.17	856.71	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3060	082819 09:00_SSHS-B3060-SUB-0-0.17	SSHS-B3060-SUB-0-0.17	856.96	0 - 0.17 ft	180-94829-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3061	082719 09:30_SSHS-B3061-SUB-0-0.17	SSHS-B3061-SUB-0-0.17	857.02	0 - 0.17 ft	180-94754-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3062	083019 09:00_SSHS-B3062-SUB-0-0.17	SSHS-B3062-SUB-0-0.17	856.91	0 - 0.17 ft	180-95024-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3063	082719 09:30_SSHS-B3063-SUB-0-0.17	SSHS-B3063-SUB-0-0.17	856.95	0 - 0.17 ft	180-94754-3	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-0-0.17	SSHS-B3064-SUB-0-0.17	856.77	0 - 0.17 ft	180-94754-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-0-0.17	SSHS-B3065-SUB-0-0.17	856.77	0 - 0.17 ft	180-94752-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3066	082719 09:30_SSHS-B3066-SUB-0-0.17	SSHS-B3066-SUB-0-0.17	855.86	0 - 0.17 ft	180-94754-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3067	083019 09:00_SSHS-B3067-SUB-0-0.17	SSHS-B3067-SUB-0-0.17	856.40	0 - 0.17 ft	180-95006-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3068	083019 09:00_SSHS-B3068-SUB-0-0.17	SSHS-B3068-SUB-0-0.17	856.38	0 - 0.17 ft	180-95006-3	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	SSHS-B3073-SUB-0-0.17	857.14	0 - 0.17 ft	180-94829-2	Excavated			< 130 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2233	073118 08:50 SSHS-B2233-SS	SSHS-B2233-SS	854.83	0 - 0.17 ft	180-80275-1	Excavated												
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-SS	SSHS-B2234-SUB-SS	855.41	0 - 0.17 ft	180-80091-4	Excavated												
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-SS	SSHS-B2235-SUB-SS	855.30	0 - 0.17 ft	180-80091-4	Excavated												
Football Field	SSHS-B2236	072618 08:50 SSHS-B2236-SS	SSHS-B2236-SS	855.25	0 - 0.17 ft	180-80157-3	Excavated												
Football Field	SSHS-B2237	072518 09:00 SSHS-B2237-SS	SSHS-B2237-SS	855.30	0 - 0.17 ft	180-80106-3	Excavated												
Football Field	SSHS-B2238	072418 08:50 SSHS-B2238-SUB-SS	SSHS-B2238-SUB-SS	855.07	0 - 0.17 ft	180-80091-4	Excavated												
Northern Athletic Field	SSHS-B3001	083019 09:00 SSHS-B3001-SUB-0-0.17	SSHS-B3001-SUB-0-0.17	853.35	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3002	083019 09:00 SSHS-B3002-SUB-0-0.17	SSHS-B3002-SUB-0-0.17	853.09	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3003	083019 09:00 SSHS-B3003-SUB-0-0.17	SSHS-B3003-SUB-0-0.17	851.95	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3016-SUB-0-0.17	SSHS-B3016-SUB-0-0.17	852.36	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3007	082719 09:30 SSHS-B3007-SUB-0-0.17	SSHS-B3007-SUB-0-0.17	852.58	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3009	083019 09:00 SSHS-B3009-SUB-0-0.17	SSHS-B3009-SUB-0-0.17	853.88	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3011	083019 09:00 SSHS-B3011-SUB-0-0.17	SSHS-B3011-SUB-0-0.17	853.85	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3012	083019 09:00 SSHS-B3012-SUB-0-0.17	SSHS-B3012-SUB-0-0.17	853.28	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3013	090519 09:00 SSHS-B3013-SUB-0-0.17	SSHS-B3013-SUB-0-0.17	852.90	0 - 0.17 ft	180-95165-4	Excavated												
Northern Athletic Field	SSHS-B3014	082919 09:10 SSHS-B3014-SUB-0-0.17	SSHS-B3014-SUB-0-0.17	853.35	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3015	082919 09:10 SSHS-B3015-SUB-0-0.17	SSHS-B3015-SUB-0-0.17	853.51	0 - 0.17 ft	180-94902-3	Excavated												
Northern Athletic Field	SSHS-B3017	082819 09:00 SSHS-B3017-SUB-0-0.17	SSHS-B3017-SUB-0-0.17	853.78	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-0-0.17	SSHS-B3018-SUB-0-0.17	853.82	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3019	082719 09:30 SSHS-B3019-SUB-0-0.17	SSHS-B3019-SUB-0-0.17	854.09	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3020	082719 09:30 SSHS-B3020-SUB-0-0.17	SSHS-B3020-SUB-0-0.17	853.86	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-0-0.17	SSHS-B3022-SUB-0-0.17	853.76	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3023	083019 09:00 SSHS-B3023-SUB-0-0.17	SSHS-B3023-SUB-0-0.17	854.48	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3025	083019 09:00 SSHS-B3025-SUB-0-0.17	SSHS-B3025-SUB-0-0.17	854.59	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3026	082919 09:10 SSHS-B3026-SUB-0-0.17	SSHS-B3026-SUB-0-0.17	854.13	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3028	082819 09:00 SSHS-B3028-SUB-0-0.17	SSHS-B3028-SUB-0-0.17	854.60	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3030	082819 09:00 SSHS-B3030-SUB-0-0.17	SSHS-B3030-SUB-0-0.17	855.22	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3031	082719 09:30 SSHS-B3031-SUB-0-0.17	SSHS-B3031-SUB-0-0.17	855.08	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3033	082719 09:30 SSHS-B3033-SUB-0-0.17	SSHS-B3033-SUB-0-0.17	855.17	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-0-0.17	SSHS-B3034-SUB-0-0.17	855.10	0 - 0.17 ft	180-94752-2	Excavated												
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-0-0.17	SSHS-B3035-SUB-0-0.17	854.81	0 - 0.17 ft	180-94752-1	Excavated												
Northern Athletic Field	SSHS-B3036	083019 09:00 SSHS-B3036-SUB-0-0.17	SSHS-B3036-SUB-0-0.17	855.09	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3037	083019 09:00 SSHS-B3037-SUB-0-0.17	SSHS-B3037-SUB-0-0.17	855.60	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3038	083019 09:00 SSHS-B3038-SUB-0-0.17	SSHS-B3038-SUB-0-0.17	855.76	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3039	083019 09:00 SSHS-B3039-SUB-0-0.17	SSHS-B3039-SUB-0-0.17	855.85	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3040	082919 09:10 SSHS-B3040-SUB-0-0.17	SSHS-B3040-SUB-0-0.17	855.10	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3041	082919 09:10 SSHS-B3041-SUB-0-0.17	SSHS-B3041-SUB-0-0.17	855.17	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-0-0.17	SSHS-B3042-SUB-0-0.17	855.23	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3043	082819 09:00 SSHS-B3043-SUB-0-0.17	SSHS-B3043-SUB-0-0.17	855.78	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3044	082819 09:00 SSHS-B3044-SUB-0-0.17	SSHS-B3044-SUB-0-0.17	856.00	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3045	082819 09:00 SSHS-B3045-SUB-0-0.17	SSHS-B3045-SUB-0-0.17	856.03	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3046	082719 09:30 SSHS-B3046-SUB-0-0.17	SSHS-B3046-SUB-0-0.17	856.22	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3048	082719 09:30 SSHS-B3048-SUB-0-0.17	SSHS-B3048-SUB-0-0.17	856.08	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-0-0.17	SSHS-B3049-SUB-0-0.17	856.17	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-0-0.17	SSHS-B3050-SUB-0-0.17	855.60	0 - 0.17 ft	180-94752-1	Excavated												
Northern Athletic Field	SSHS-B3051	083019 09:00 SSHS-B3051-SUB-0-0.17	SSHS-B3051-SUB-0-0.17	855.15	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3052	083019 09:00 SSHS-B3052-SUB-0-0.17	SSHS-B3052-SUB-0-0.17	855.98	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3053	083019 09:00 SSHS-B3053-SUB-0-0.17	SSHS-B3053-SUB-0-0.17	856.41	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-0-0.17	SSHS-B3054-SUB-0-0.17	856.01	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3055	082919 09:10 SSHS-B3055-SUB-0-0.17	SSHS-B3055-SUB-0-0.17	856.20	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3056	082919 09:10 SSHS-B3056-SUB-0-0.17	SSHS-B3056-SUB-0-0.17	855.88	0 - 0.17 ft	180-94902-3	Excavated												
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-0-0.17	SSHS-B3057-SUB-0-0.17	856.09	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3058	082819 09:00 SSHS-B3058-SUB-0-0.17	SSHS-B3058-SUB-0-0.17	856.47	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3059	082819 09:00 SSHS-B3059-SUB-0-0.17	SSHS-B3059-SUB-0-0.17	856.71	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3060	082819 09:00 SSHS-B3060-SUB-0-0.17	SSHS-B3060-SUB-0-0.17	856.96	0 - 0.17 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3061	082719 09:30 SSHS-B3061-SUB-0-0.17	SSHS-B3061-SUB-0-0.17	857.02	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3062	083019 09:00 SSHS-B3062-SUB-0-0.17	SSHS-B3062-SUB-0-0.17	856.91	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3063	082719 09:30 SSHS-B3063-SUB-0-0.17	SSHS-B3063-SUB-0-0.17	856.95	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-0-0.17	SSHS-B3064-SUB-0-0.17	856.77	0 - 0.17 ft	180-94754-1	Excavated												
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-0-0.17	SSHS-B3065-SUB-0-0.17	856.77	0 - 0.17 ft	180-94752-3	Excavated												
Northern Athletic Field	SSHS-B3066	082719 09:30 SSHS-B3066-SUB-0-0.17	SSHS-B3066-SUB-0-0.17	855.86	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3067	083019 09:00 SSHS-B3067-SUB-0-0.17	SSHS-B3067-SUB-0-0.17	856.40	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3068	083019 09:00 SSHS-B3068-SUB-0-0.17	SSHS-B3068-SUB-0-0.17	856.38	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0-0.17	SSHS-B3073-SUB-0-0.17	857.14	0 - 0.17 ft	180-94829-2	Excavated												

DRAFT

																						Emerging C
									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100										
Restricted - Residential									13000	13000	13000										
Protection of Groundwater									100	100	100										
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status														
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-0-0.17	SSHS-B3074-SUB-0-0.17	857.18	0 - 0.17 ft	180-94829-2	Excavated				< 130 U										
Northern Athletic Field	SSHS-B3076	082719 09:30_SSHS-B3076-SUB-0-0.17	SSHS-B3076-SUB-0-0.17	856.92	0 - 0.17 ft	180-94754-3	Excavated				< 110 U										
Northern Athletic Field	SSHS-B3077	082719 09:30_SSHS-B3077-SUB-0-0.17	SSHS-B3077-SUB-0-0.17	856.86	0 - 0.17 ft	180-94752-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-0-0.17	SSHS-B3079-SUB-0-0.17	856.36	0 - 0.17 ft	180-95006-3	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3080	083019 09:00_SSHS-B3080-SUB-0-0.17	SSHS-B3080-SUB-0-0.17	856.58	0 - 0.17 ft	180-95024-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3082	082919 09:10_SSHS-B3082-SUB-0-0.17	SSHS-B3082-SUB-0-0.17	856.73	0 - 0.17 ft	180-94903-1	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3082	083019 09:00_SSHS-B3082-SUB-0-0.17	SSHS-B3082-SUB-0-0.17	856.73	0 - 0.17 ft	180-95006-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-0-0.17	SSHS-B3083-SUB-0-0.17	857.13	0 - 0.17 ft	180-95006-3	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3084	082919 09:10_SSHS-B3084-SUB-0-0.17	SSHS-B3084-SUB-0-0.17	856.55	0 - 0.17 ft	180-94903-1	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3085	083019 09:00_SSHS-B3085-SUB-0-0.17	SSHS-B3085-SUB-0-0.17	857.12	0 - 0.17 ft	180-95024-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3086	083019 09:00_SSHS-B3086-SUB-0-0.17	SSHS-B3086-SUB-0-0.17	857.77	0 - 0.17 ft	180-95006-3	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3087	083019 09:00_SSHS-B3087-SUB-0-0.17	SSHS-B3087-SUB-0-0.17	857.68	0 - 0.17 ft	180-95006-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3095	082819 09:00_SSHS-B3095-SUB-0-0.17	SSHS-B3095-SUB-0-0.17	857.12	0 - 0.17 ft	180-94829-2	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3096	082719 09:30_SSHS-B3096-SUB-0-0.17	SSHS-B3096-SUB-0-0.17	855.86	0 - 0.17 ft	180-94754-2	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3097	082719 09:30_SSHS-B3097-SUB-0-0.17	SSHS-B3097-SUB-0-0.17	856.19	0 - 0.17 ft	180-94754-3	Excavated				< 130 U										
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-0-0.17	SSHS-B3098-SUB-0-0.17	855.97	0 - 0.17 ft	180-94754-1	Excavated				< 110 U										
Northern Athletic Field	SSHS-B3107	012120 08:10_SSHS-B3107-SUB-0-0.17	SSHS-B3107-SUB-0-0.17	857.05	0 - 0.17 ft	180-101269-1	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3108	012120 08:10_SSHS-B3108-SUB-0-0.17	SSHS-B3108-SUB-0-0.17	857.55	0 - 0.17 ft	180-101269-1	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3110	012120 08:10_SSHS-B3110-SUB-0-0.17	SSHS-B3110-SUB-0-0.17	856.32	0 - 0.17 ft	180-101269-1	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3111	012120 08:10_SSHS-B3111-SUB-0-0.17	SSHS-B3111-SUB-0-0.17	857.08	0 - 0.17 ft	180-101269-1	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3113	012120 08:10_SSHS-B3113-SUB-0-0.17	SSHS-B3113-SUB-0-0.17	856.36	0 - 0.17 ft	180-101269-1	Excavated				< 130 U										
Northern Athletic Field	SSHS-B3116	012120 08:10_SSHS-B3116-SUB-0-0.17	SSHS-B3116-SUB-0-0.17	856.51	0 - 0.17 ft	180-101269-1	Excavated				< 130 U										
Northern Athletic Field	SSHS-B3117	012120 08:10_SSHS-B3117-SUB-0-0.17	SSHS-B3117-SUB-0-0.17	856.54	0 - 0.17 ft	180-101269-1	Excavated				< 170 U										
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-0-0.17	SSHS-B3181-SUB-0-0.17	857.57	0 - 0.17 ft	180-95006-3	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3184	051220 04:51_SSHS-B3184-SUB-0-0.17	SSHS-B3184-SUB-0-0.17	856.85	0 - 0.17 ft	180-105660-1	Excavated				< 58 U										
Northern Athletic Field	SSHS-B3214	083019 09:00_SSHS-B3214-SUB-0-0.17	SSHS-B3214-SUB-0-0.17	855.06	0 - 0.17 ft	180-95006-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3220	083019 09:00_SSHS-B3220-SUB-0-0.17	SSHS-B3220-SUB-0-0.17	857.44	0 - 0.17 ft	180-95024-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3221	083019 09:00_SSHS-B3221-SUB-0-0.17	SSHS-B3221-SUB-0-0.17	857.92	0 - 0.17 ft	180-95006-3	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3222	083019 09:00_SSHS-B3222-SUB-0-0.17	SSHS-B3222-SUB-0-0.17	858.28	0 - 0.17 ft	180-95006-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-0-0.17	SSHS-B3223-SUB-0-0.17	858.27	0 - 0.17 ft	180-95006-3	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3224	082919 09:10_SSHS-B3224-SUB-0-0.17	SSHS-B3224-SUB-0-0.17	858.38	0 - 0.17 ft	180-94903-1	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3247	122119 10:30_SSHS-B3247-SUB-0-0.17	SSHS-B3247-SUB-0-0.17	857.57	0 - 0.17 ft	180-100363-3	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3249	012520 10:00_SSHS-B3249-SUB-0-0.17	SSHS-B3249-SUB-0-0.17	857.44	0 - 0.17 ft	180-101497-4	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-0-0.17	SSHS-B3250-SUB-0-0.17	858.02	0 - 0.17 ft	180-100363-2	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3252	012520 10:00_SSHS-B3252-SUB-0-0.17	SSHS-B3252-SUB-0-0.17	857.46	0 - 0.17 ft	180-101497-4	Excavated				< 150 U										
Northern Athletic Field	SSHS-B3261	122119 10:30_SSHS-B3261-SUB-0-0.17	SSHS-B3261-SUB-0-0.17	856.31	0 - 0.17 ft	180-100380-2	Excavated				< 350 U										
Northern Athletic Field	SSHS-B3262	122119 10:30_SSHS-B3262-SUB-0-0.17	SSHS-B3262-SUB-0-0.17	857.03	0 - 0.17 ft	180-100380-2	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3263	122119 10:30_SSHS-B3263-SUB-0-0.17	SSHS-B3263-SUB-0-0.17	857.52	0 - 0.17 ft	180-100380-2	Excavated				< 160 U										
Northern Athletic Field	SSHS-B3481	072920 09:00_SSHS-B3481-SUB-0-0.17	SSHS-B3481-SUB-0-0.17	858.23	0 - 0.17 ft	180-108872-1	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	SSHS-B3481-SUB-0-0.17	858.23	0 - 0.17 ft	180-108872-1	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3484	072920 09:00_SSHS-B3484-SUB-0-0.17	SSHS-B3484-SUB-0-0.17	858.45	0 - 0.17 ft	180-108872-1	Excavated				< 140 U										
Northern Athletic Field	SSHS-B3485	072920 09:00_SSHS-B3485-SUB-0-0.17	SSHS-B3485-SUB-0-0.17	858.43	0 - 0.17 ft	180-108872-1	Excavated				< 1300 U										
Northern Athletic Field	SSHS-B3486	072920 09:00_SSHS-B3486-SUB-0-0.17	SSHS-B3486-SUB-0-0.17	858.58	0 - 0.17 ft	180-108872-1	Excavated				< 130 U										
Northern Athletic Field	SSHS-B3487	072920 09:00_SSHS-B3487-SUB-0-0.17	SSHS-B3487-SUB-0-0.17	856.51	0 - 0.17 ft	180-108872-1	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3488	072920 09:00_SSHS-B3488-SUB-0-0.17	SSHS-B3488-SUB-0-0.17	857.00	0 - 0.17 ft	180-108872-1	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3489	072920 09:00_SSHS-B3489-SUB-0-0.17	SSHS-B3489-SUB-0-0.17	856.50	0 - 0.17 ft	180-108872-1	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3490	072920 09:00_SSHS-B3490-SUB-0-0.17	SSHS-B3490-SUB-0-0.17	858.42	0 - 0.17 ft	180-108872-1	Excavated				< 1200 U										
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	SSHS-B3496-SUB-0-0.17	858.30	0 - 0.17 ft	180-116002-2	Excavated				130										
Northern Athletic Field	SSHS-B3498	011521 08:45_SSHS-B3498-SUB-0-0.17	SSHS-B3498-SUB-0-0.17	858.39	0 - 0.17 ft	180-116002-2	Excavated				680										
Northern Athletic Field	SSHS-B3499	011521 08:45_SSHS-B3499-SUB-0-0.17	SSHS-B3499-SUB-0-0.17	858.31	0 - 0.17 ft	180-116002-2	Excavated				130										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-0-0.17	SSHS-B3646A-SUB-0-0.17	856.64	0 - 0.17 ft	180-127265-1	Excavated				< 120 U										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-0-0.17	SSHS-B3852-SUB-0-0.17	856.07	0 - 0.17 ft	180-127205-2	Excavated				< 110 U										
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17-20210701	SSHS-B4018-SUB-0-0.17	857.47	0 - 0.17 ft	1801239851	Excavated	< 130 U				< 0.44 U	< 0.030 U	0.13 J	< 0.047 U	0.050 J	< 0.080 U	< 0.042 U	0.062 J	< 0.037 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-0-0.17	SSHS-B4019-SUB-0-0.17	856.76	0 - 0.17 ft	180-123985-1	Excavated				< 120 U										
Northern Athletic Field	SSHS-B4020	DUP-2-20210701	DUP-2	852.51	0 - 2 ft	1801239851	Excavated	< 120 U				< 0.40 U	0.037 J	0.19 J	0.13 J	0.30	0.15 J	< 0.038 U	0.14 J	< 0.033 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17-20210701	SSHS-B4020-SUB-0-0.17	856.62	0 - 0.17 ft	1801239851	Excavated	< 120 U				< 0.40 U	0.033 J	0.20 J	0.095 J	0.26	0.15 J	< 0.038 U	0.14 J	< 0.033 U
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	SSHS-B47-A-SS	856.74	0 - 0.17 ft	180-35053-1	Excavated														
Football Field	SSHS-B70	081514 01:15_SSHS-B70-SS	081514 01:15_SSHS-B70-SS	855.98	0 - 0.17 ft	180-35818-2	Excavated				< 49 U										
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	SSHS-B75-SS	856.08	0 - 0.17 ft	180-35818-2	Excavated				< 49										
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	SSHS-B76-SS	856.25	0 - 0.17 ft	180-35818-1	Excavated				< 47										
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	SSHS-B77-SS	855.88	0 - 0.17 ft	180-35818-1	Excavated				< 47										
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-0.17-2 (1)	SSHS-B101-0.17-2 (1)	852.95	0 - 2 ft	180-35818-2	Excavated				< 41 U										
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-0-2	SSHS-B2185-SUB-0-2	855.07	0 - 2 ft	180-80106-3	Excavated				< 84 U										
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-0-2	SSHS-B2186-SUB-0-2	854.94	0 - 2 ft	180-80106-2	Excavated				< 86 U										

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-0-0.17	SSHS-B3074-SUB-0-0.17	857.18	0 - 0.17 ft	180-94829-2	Excavated												
Northern Athletic Field	SSHS-B3076	082719 09:30_SSHS-B3076-SUB-0-0.17	SSHS-B3076-SUB-0-0.17	856.92	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3077	082719 09:30_SSHS-B3077-SUB-0-0.17	SSHS-B3077-SUB-0-0.17	856.86	0 - 0.17 ft	180-94752-2	Excavated												
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-0-0.17	SSHS-B3079-SUB-0-0.17	856.36	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3080	083019 09:00_SSHS-B3080-SUB-0-0.17	SSHS-B3080-SUB-0-0.17	856.58	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3082	082919 09:10_SSHS-B3082-SUB-0-0.17	SSHS-B3082-SUB-0-0.17	856.73	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3082	083019 09:00_SSHS-B3082-SUB-0-0.17	SSHS-B3082-SUB-0-0.17	856.73	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-0-0.17	SSHS-B3083-SUB-0-0.17	857.13	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3084	082919 09:10_SSHS-B3084-SUB-0-0.17	SSHS-B3084-SUB-0-0.17	856.55	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3085	083019 09:00_SSHS-B3085-SUB-0-0.17	SSHS-B3085-SUB-0-0.17	857.12	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3086	083019 09:00_SSHS-B3086-SUB-0-0.17	SSHS-B3086-SUB-0-0.17	857.77	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3087	083019 09:00_SSHS-B3087-SUB-0-0.17	SSHS-B3087-SUB-0-0.17	857.68	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3095	082819 09:00_SSHS-B3095-SUB-0-0.17	SSHS-B3095-SUB-0-0.17	857.12	0 - 0.17 ft	180-94829-2	Excavated												
Northern Athletic Field	SSHS-B3096	082719 09:30_SSHS-B3096-SUB-0-0.17	SSHS-B3096-SUB-0-0.17	855.86	0 - 0.17 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3097	082719 09:30_SSHS-B3097-SUB-0-0.17	SSHS-B3097-SUB-0-0.17	856.19	0 - 0.17 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-0-0.17	SSHS-B3098-SUB-0-0.17	855.97	0 - 0.17 ft	180-94754-1	Excavated												
Northern Athletic Field	SSHS-B3107	012120 08:10_SSHS-B3107-SUB-0-0.17	SSHS-B3107-SUB-0-0.17	857.05	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3108	012120 08:10_SSHS-B3108-SUB-0-0.17	SSHS-B3108-SUB-0-0.17	857.55	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3110	012120 08:10_SSHS-B3110-SUB-0-0.17	SSHS-B3110-SUB-0-0.17	856.32	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3111	012120 08:10_SSHS-B3111-SUB-0-0.17	SSHS-B3111-SUB-0-0.17	857.08	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3113	012120 08:10_SSHS-B3113-SUB-0-0.17	SSHS-B3113-SUB-0-0.17	856.36	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3116	012120 08:10_SSHS-B3116-SUB-0-0.17	SSHS-B3116-SUB-0-0.17	856.51	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3117	012120 08:10_SSHS-B3117-SUB-0-0.17	SSHS-B3117-SUB-0-0.17	856.54	0 - 0.17 ft	180-101269-1	Excavated												
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-0-0.17	SSHS-B3181-SUB-0-0.17	857.57	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3184	051220 04:51_SSHS-B3184-SUB-0-0.17	SSHS-B3184-SUB-0-0.17	856.85	0 - 0.17 ft	180-105660-1	Excavated												
Northern Athletic Field	SSHS-B3214	083019 09:00_SSHS-B3214-SUB-0-0.17	SSHS-B3214-SUB-0-0.17	855.06	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3220	083019 09:00_SSHS-B3220-SUB-0-0.17	SSHS-B3220-SUB-0-0.17	857.44	0 - 0.17 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3221	083019 09:00_SSHS-B3221-SUB-0-0.17	SSHS-B3221-SUB-0-0.17	857.92	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3222	083019 09:00_SSHS-B3222-SUB-0-0.17	SSHS-B3222-SUB-0-0.17	858.28	0 - 0.17 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-0-0.17	SSHS-B3223-SUB-0-0.17	858.27	0 - 0.17 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3224	082919 09:10_SSHS-B3224-SUB-0-0.17	SSHS-B3224-SUB-0-0.17	858.38	0 - 0.17 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3247	122119 10:30_SSHS-B3247-SUB-0-0.17	SSHS-B3247-SUB-0-0.17	857.57	0 - 0.17 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3249	012520 10:00_SSHS-B3249-SUB-0-0.17	SSHS-B3249-SUB-0-0.17	857.44	0 - 0.17 ft	180-101497-4	Excavated												
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-0-0.17	SSHS-B3250-SUB-0-0.17	858.02	0 - 0.17 ft	180-100363-2	Excavated												
Northern Athletic Field	SSHS-B3252	012520 10:00_SSHS-B3252-SUB-0-0.17	SSHS-B3252-SUB-0-0.17	857.46	0 - 0.17 ft	180-101497-4	Excavated												
Northern Athletic Field	SSHS-B3261	122119 10:30_SSHS-B3261-SUB-0-0.17	SSHS-B3261-SUB-0-0.17	856.31	0 - 0.17 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3262	122119 10:30_SSHS-B3262-SUB-0-0.17	SSHS-B3262-SUB-0-0.17	857.03	0 - 0.17 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3263	122119 10:30_SSHS-B3263-SUB-0-0.17	SSHS-B3263-SUB-0-0.17	857.52	0 - 0.17 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3481	072920 09:00_SSHS-B3481-SUB-0-0.17	SSHS-B3481-SUB-0-0.17	858.23	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0-0.17	SSHS-B3481-SUB-0-0.17	858.23	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3484	072920 09:00_SSHS-B3484-SUB-0-0.17	SSHS-B3484-SUB-0-0.17	858.45	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3485	072920 09:00_SSHS-B3485-SUB-0-0.17	SSHS-B3485-SUB-0-0.17	858.43	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3486	072920 09:00_SSHS-B3486-SUB-0-0.17	SSHS-B3486-SUB-0-0.17	858.58	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3487	072920 09:00_SSHS-B3487-SUB-0-0.17	SSHS-B3487-SUB-0-0.17	856.51	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3488	072920 09:00_SSHS-B3488-SUB-0-0.17	SSHS-B3488-SUB-0-0.17	857.00	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3489	072920 09:00_SSHS-B3489-SUB-0-0.17	SSHS-B3489-SUB-0-0.17	856.50	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3490	072920 09:00_SSHS-B3490-SUB-0-0.17	SSHS-B3490-SUB-0-0.17	858.42	0 - 0.17 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0-0.17	SSHS-B3496-SUB-0-0.17	858.30	0 - 0.17 ft	180-116002-2	Excavated												
Northern Athletic Field	SSHS-B3498	011521 08:45_SSHS-B3498-SUB-0-0.17	SSHS-B3498-SUB-0-0.17	858.39	0 - 0.17 ft	180-116002-2	Excavated												
Northern Athletic Field	SSHS-B3499	011521 08:45_SSHS-B3499-SUB-0-0.17	SSHS-B3499-SUB-0-0.17	858.31	0 - 0.17 ft	180-116002-2	Excavated												
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-0-0.17	SSHS-B3646A-SUB-0-0.17	856.64	0 - 0.17 ft	180-127265-1	Excavated												
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-0-0.17	SSHS-B3852-SUB-0-0.17	856.07	0 - 0.17 ft	180-127205-2	Excavated												
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0-0.17-20210701	SSHS-B4018-SUB-0-0.17	857.47	0 - 0.17 ft	1801239851	Excavated	0.069 J	0.053 J	< 0.098 U	0.26 J	0.10 J	< 0.092 U	< 0.065 U	< 0.061 U	< 0.043 UT	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-0-0.17	SSHS-B4019-SUB-0-0.17	856.76	0 - 0.17 ft	180-123985-1	Excavated												
Northern Athletic Field	SSHS-B4020	DUP-2-20210701	DUP-2	852.51	0 - 2 ft	1801239851	Excavated	0.18 J	0.19 J	< 0.089 U	0.80	0.32	0.10 J	< 0.058 U	< 0.055 U	0.12 J	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B4020	SSHS-B4020-SUB-0-0.17-20210701	SSHS-B4020-SUB-0-0.17	856.62	0 - 0.17 ft	1801239851	Excavated	0.14 J	0.17 J	< 0.088 U	0.69	0.34	0.12 J	< 0.058 U	< 0.055 U	0.15 J	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B47-A	SSHS-B47-A-SS	SSHS-B47-A-SS	856.74	0 - 0.17 ft	180-35053-1	Excavated												
Football Field	SSHS-B70	081514 01:15_SSHS-B70-SS	081514 01:15_SSHS-B70-SS	855.98	0 - 0.17 ft	180-35818-2	Excavated												
Northern Athletic Field	SSHS-B75	SSHS-B75-SS	SSHS-B75-SS	856.08	0 - 0.17 ft	180-35818-2	Excavated												
Northern Athletic Field	SSHS-B76	SSHS-B76-SS	SSHS-B76-SS	856.25	0 - 0.17 ft	180-35818-1	Excavated												
Northern Athletic Field	SSHS-B77	SSHS-B77-SS	SSHS-B77-SS	855.88	0 - 0.17 ft	180-35818-1	Excavated												
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-0.17-2 (1)	SSHS-B101-0.17-2 (1)	852.95	0 - 2 ft	180-35818-2	Excavated												
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-0-2	SSHS-B2185-SUB-0-2	855.07	0 - 2 ft	180-80106-3	Excavated												
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-0-2	SSHS-B2186-SUB-0-2	854.94	0 - 2 ft	180-80106-2	Excavated												

DRAFT

								Emerging C										
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-0-2	SSHS-B2187-SUB-0-2	856.10	0 - 2 ft	180-80106-1	Excavated			< 17 U									
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-0-2	SSHS-B2188-SUB-0-2	855.99	0 - 2 ft	180-80106-2	Excavated			< 67 U									
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-0-2	SSHS-B2189-SUB-0-2	855.74	0 - 2 ft	180-80105-3	Excavated			< 40 U									
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-0-2	SSHS-B2190-SUB-0-2	856.06	0 - 2 ft	180-80252-1	Excavated			< 15 U									
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-0-2	SSHS-B2191-SUB-0-2	856.18	0 - 2 ft	180-80105-3	Excavated			< 79 U									
Football Field	SSHS-B2196	072518 09:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-80106-2	Excavated			< 34 U									
Football Field	SSHS-B2196	072518 09:00 SSHS-B2196-SUB-0-2	SSHS-B2196-SUB-0-2	855.03	0 - 2 ft	180-80106-2	Excavated			< 44 U									
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-0-2	SSHS-B2197-SUB-0-2	854.99	0 - 2 ft	180-80105-1	Excavated			< 68 U									
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-0-2	SSHS-B2198-SUB-0-2	855.05	0 - 2 ft	180-80105-2	Excavated			< 330 U									
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-0-2	SSHS-B2245-SUB-0-2	855.25	0 - 2 ft	180-80106-1	Excavated			< 17 U									
Football Field	SSHS-B2246	072718 09:00 PS-FD-36	PS-FD-36	855.24	0 - 2 ft	180-80225-3	Excavated			< 17 U									
Football Field	SSHS-B2246	072718 09:00 SSHS-B2246-SUB-0-2	SSHS-B2246-SUB-0-2	855.24	0 - 2 ft	180-80225-1	Excavated			< 35 U									
Tennis Courts / Main Parking Lot	SSHS-B402	090616 09:00 SSHS-B402-SUB-0-2	SSHS-B402-SUB-0-2	855.98	0 - 2 ft	180-58129-1	Excavated			< 420 U									
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	SSHS-B404-SUB-0-2	856.65	0 - 2 ft	180-57995-1	Excavated			< 400									
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-0-2	SSHS-B410-SUB-0-2	856.77	0 - 2 ft	180-57995-1	Excavated			< 46 U									
Football Field	SSHS-B424	082316 09:15 SSHS-B424-SUB-0-2	SSHS-B424-SUB-0-2	856.17	0 - 2 ft	180-57858-1	Excavated			< 44 U									
Football Field	SSHS-B432	082316 09:15 SSHS-B432-SUB-0-2	SSHS-B432-SUB-0-2	855.16	0 - 2 ft	180-57858-1	Excavated			< 47 U									
Football Field	SSHS-B434	082316 09:15 SSHS-B434-SUB-0-2	SSHS-B434-SUB-0-2	855.08	0 - 2 ft	180-57858-1	Excavated			< 45 U									
Football Field	SSHS-B448	082616 09:00 SSHS-B448-SUB-0-2	SSHS-B448-SUB-0-2	856.23	0 - 2 ft	180-57995-1	Excavated			< 44 U									
Football Field	SSHS-B449	090616 09:00 SSHS-B449-SUB-0-2	SSHS-B449-SUB-0-2	855.21	0 - 2 ft	180-58129-1	Excavated			< 42 U									
Football Field	SSHS-B450	082616 09:00 SSHS-B450-SUB-0-2	SSHS-B450-SUB-0-2	856.21	0 - 2 ft	180-57995-1	Excavated			< 43 U									
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	SSHS-B572-SUB-0-2	852.49	0 - 2 ft	180-58129-1	Excavated			< 41									
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-0.17-2 (1)	SSHS-B64-0.17-2 (1)	851.65	0 - 2 ft	180-35818-2	Excavated			< 40 U									
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-0.17-2 (1)	SSHS-B65-0.17-2 (1)	850.41	0 - 2 ft	180-35818-1	Excavated			< 41 U									
Rear Parking Lot	SSHS-B66	081514 01:15 SSHS-B66-0.17-2 (1)	SSHS-B66-0.17-2 (1)	851.94	0 - 2 ft	180-35818-1	Excavated			< 41 U									
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-0.17-2 (1)	SSHS-B67-0.17-2 (1)	850.45	0 - 2 ft	180-35818-1	Excavated			< 43 U									
Football Field	SSHS-B2705	051719 09:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2762	042819 10:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-89521-1	Excavated			< 240 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-0-2	SSHS-B2187-SUB-0-2	856.10	0 - 2 ft	180-80106-1	Excavated												
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-0-2	SSHS-B2188-SUB-0-2	855.99	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-0-2	SSHS-B2189-SUB-0-2	855.74	0 - 2 ft	180-80105-3	Excavated												
Football Field	SSHS-B2190	072818 11:30_SSHS-B2190-SUB-0-2	SSHS-B2190-SUB-0-2	856.06	0 - 2 ft	180-80252-1	Excavated												
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-0-2	SSHS-B2191-SUB-0-2	856.18	0 - 2 ft	180-80105-3	Excavated												
Football Field	SSHS-B2196	072518 09:00_PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2196	072518 09:00_SSHS-B2196-SUB-0-2	SSHS-B2196-SUB-0-2	855.03	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-0-2	SSHS-B2197-SUB-0-2	854.99	0 - 2 ft	180-80105-1	Excavated												
Football Field	SSHS-B2198	072518 09:00_SSHS-B2198-SUB-0-2	SSHS-B2198-SUB-0-2	855.05	0 - 2 ft	180-80105-2	Excavated												
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-0-2	SSHS-B2245-SUB-0-2	855.25	0 - 2 ft	180-80106-1	Excavated												
Football Field	SSHS-B2246	072718 09:00_PS-FD-36	PS-FD-36	855.24	0 - 2 ft	180-80225-3	Excavated												
Football Field	SSHS-B2246	072718 09:00_SSHS-B2246-SUB-0-2	SSHS-B2246-SUB-0-2	855.24	0 - 2 ft	180-80225-1	Excavated												
Tennis Courts / Main Parking Lot	SSHS-B402	090616 09:00_SSHS-B402-SUB-0-2	SSHS-B402-SUB-0-2	855.98	0 - 2 ft	180-58129-1	Excavated												
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	SSHS-B404-SUB-0-2	856.65	0 - 2 ft	180-57995-1	Excavated												
Football Field	SSHS-B410	082616 09:00_SSHS-B410-SUB-0-2	SSHS-B410-SUB-0-2	856.77	0 - 2 ft	180-57995-1	Excavated												
Football Field	SSHS-B424	082316 09:15_SSHS-B424-SUB-0-2	SSHS-B424-SUB-0-2	856.17	0 - 2 ft	180-57858-1	Excavated												
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-0-2	SSHS-B432-SUB-0-2	855.16	0 - 2 ft	180-57858-1	Excavated												
Football Field	SSHS-B434	082316 09:15_SSHS-B434-SUB-0-2	SSHS-B434-SUB-0-2	855.08	0 - 2 ft	180-57858-1	Excavated												
Football Field	SSHS-B448	082616 09:00_SSHS-B448-SUB-0-2	SSHS-B448-SUB-0-2	856.23	0 - 2 ft	180-57995-1	Excavated												
Football Field	SSHS-B449	090616 09:00_SSHS-B449-SUB-0-2	SSHS-B449-SUB-0-2	855.21	0 - 2 ft	180-58129-1	Excavated												
Football Field	SSHS-B450	082616 09:00_SSHS-B450-SUB-0-2	SSHS-B450-SUB-0-2	856.21	0 - 2 ft	180-57995-1	Excavated												
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	SSHS-B572-SUB-0-2	852.49	0 - 2 ft	180-58129-1	Excavated												
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-0.17-2 (1)	SSHS-B64-0.17-2 (1)	851.65	0 - 2 ft	180-35818-2	Excavated												
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-0.17-2 (1)	SSHS-B65-0.17-2 (1)	850.41	0 - 2 ft	180-35818-1	Excavated												
Rear Parking Lot	SSHS-B66	081514 01:15_SSHS-B66-0.17-2 (1)	SSHS-B66-0.17-2 (1)	851.94	0 - 2 ft	180-35818-1	Excavated												
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-0.17-2 (1)	SSHS-B67-0.17-2 (1)	850.45	0 - 2 ft	180-35818-1	Excavated												
Football Field	SSHS-B2705	051719 09:00_PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2762	042819 10:00_PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-89521-1	Excavated												

DRAFT

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	0.0939	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.059 J	0.028 J	0.0069 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	13.75	< 0.027 U	< 0.034 U	< 0.031 U	< 0.029 U	13	< 0.026 U	0.75	< 0.039 U	< 0.023 U
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-0-2	7/22/2015	849.40	0 - 2 ft	180-46170-1	Excavated	39.7	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	29 J	9.5 J	1.2 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-0-2	7/22/2015	849.32	0 - 2 ft	180-46170-1	Excavated	92.6	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	66 J	24 J	2.6 J	< 0.36 U	< 0.19 U
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-0-2	7/22/2015	849.26	0 - 2 ft	180-46170-1	Excavated	38.3	< 0.079 U	< 0.097 U	< 0.13 U	< 0.098 U	27 J	10 J	1.3 J	< 0.14 U	< 0.078 U
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-0-2	7/22/2015	849.39	0 - 2 ft	180-46170-1	Excavated	13.45	< 0.043 U	< 0.052 U	< 0.072 U	< 0.053 U	9.5 J	3.4 J	0.55 J	< 0.077 U	< 0.042 U
Rear Parking Lot	SSHS-B1063	SSHS-B1063-SUB-0-2	6/19/2018	852.50	0 - 2 ft	200-43950-2	Not Excavated	0.0081	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.0081 J	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1064	SSHS-B1064-SUB-0-2	6/23/2018	850.48	0 - 2 ft	200-44028-1	Excavated	ND	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-0.2	6/24/2018	850.40	0 - 2 ft	200-44046-1	Excavated	89.9	< 1.7 UJ	< 1.7 UJ	< 1.7 UJ	< 1.7 UJ	65 J	22 J	2.9 J	< 1.7 UJ	< 1.7 UJ
Rear Parking Lot	SSHS-B1069	SSHS-B1069-SUB-0-2	6/26/2018	850.14	0 - 2 ft	200-44065-1	Excavated	0.0266	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.018 J	0.0086 J	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-0-2	7/22/2015	849.10	0 - 2 ft	180-46170-1	Excavated	5.47	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	3.9 J	1.4 J	0.17 J	< 0.0073 U	< 0.004 U
Rear Parking Lot	SSHS-B1070	SSHS-B1070-SUB-0-2	6/24/2018	850.30	0 - 2 ft	200-44046-1	Excavated	2.09	< 0.029 UJ	< 0.029 UJ	< 0.029 UJ	< 0.029 UJ	1.4 J	0.59 J	0.1 J	< 0.029 UJ	< 0.029 UJ
Rear Parking Lot	SSHS-B1071	DUP-2	6/23/2018	852.51	0 - 2 ft	200-44028-1	Excavated	0.0081	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.0081 J	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1071	SSHS-B1071-SUB-0-2	6/23/2018	852.51	0 - 2 ft	200-44028-1	Excavated	ND	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U	< 0.0028 U
Rear Parking Lot	SSHS-B1075	SSHS-B1075-SUB-0-2	6/23/2018	852.95	0 - 2 ft	200-44028-1	Excavated	5.97	< 0.058 U	< 0.058 U	< 0.058 U	< 0.058 U	4.3 J	1.5 J	0.17 J	< 0.058 U	< 0.058 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-0-2	7/22/2015	849.57	0 - 2 ft	180-46170-1	Excavated	1.135	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.0051 U	0.71 J	0.34 J	0.085 J	< 0.0074 U	< 0.004 U
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-0-2	7/21/2015	850.20	0 - 2 ft	180-46139-1	Excavated	3.086	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	2.2 J	0.79 J	0.096 J	< 0.0066 U	< 0.0036 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated	14					14				
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-0-2	7/21/2015	850.42	0 - 2 ft	180-46139-1	Excavated	0.2957	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.22 J	0.067 J	0.0087 J	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-0-2	7/21/2015	850.45	0 - 2 ft	180-46139-1	Excavated	0.0919	< 0.0034 U	< 0.0042 U	< 0.0058 U	< 0.0043 U	0.068 J	0.019 J	0.0049 J	< 0.0062 U	< 0.0034 U
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-0-2	7/22/2015	850.70	0 - 2 ft	180-46170-1	Excavated	0.0083	< 0.0035 U	< 0.0043 U	< 0.006 U	< 0.0044 U	0.0083 J	< 0.0041 U	< 0.0038 U	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-0-2	7/21/2015	850.38	0 - 2 ft	180-46139-1	Excavated	6.11	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	4.2 J	1.7 J	0.21 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-0-2	7/20/2015	850.54	0 - 2 ft	180-46139-1	Excavated	3.15	< 0.0036 U	< 0.0044 U	< 0.006 U	< 0.0044 U	2.2 J	0.85 J	0.1 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-0-2	7/20/2015	850.60	0 - 2 ft	180-46139-1	Excavated	42.5	< 0.075 U	< 0.093 U	< 0.13 U	< 0.093 U	31 J	9.9 J	1.6 J	< 0.14 U	< 0.074 U
Rear Parking Lot	SSHS-B118	PS-FD-#12	7/20/2015	850.73	0 - 2 ft	180-46075-1	Excavated	263	< 0.37 U	< 0.46 U	< 0.63 U	< 0.46 U	180 J	71 J	12 J	< 0.67 U	< 0.37 U
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-0-2	7/20/2015	850.73	0 - 2 ft	180-46075-1	Excavated	243	< 0.37 U	< 0.45 U	< 0.62 U	< 0.45 U	170 J	65 J	8 J	< 0.66 U	< 0.36 U
Rear Parking Lot	SSHS-B1189	DUP-1	6/16/2018	853.96	0 - 2 ft	200-43950-2	Excavated	0.0079	< 0.0031 U	< 0.0031 U	< 0.0031 U	< 0.0031 U	0.0079 J	< 0.0031 U	< 0.0031 U	< 0.0031 U	< 0.0031 U
Rear Parking Lot	SSHS-B1189	SSHS-B1189-SUB-0-2	6/16/2018	853.96	0 - 2 ft	200-43950-2	Excavated	0.012	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U	0.012 J	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-0-2	7/21/2015	850.77	0 - 2 ft	180-46139-1	Excavated	42	< 0.071 U	< 0.087 U	< 0.12 U	< 0.088 U	30 J	11 J	1 J	< 0.13 U	< 0.07 U
Rear Parking Lot	SSHS-B1190	SSHS-B1190-SUB-0-2	6/19/2018	853.92	0 - 2 ft	200-43950-2	Excavated	6.7	< 0.15 U	< 0.15 U	< 0.15 U	< 0.15 U	6.7	< 0.15 U	< 0.15 U	< 0.15 U	< 0.15 U
Rear Parking Lot	SSHS-B1191	SSHS-B1191-SUB-0-2	6/19/2018	853.59	0 - 2 ft	200-43950-2	Excavated	26	< 0.89 U	< 0.89 U	< 0.89 U	< 0.89 U	26	< 0.89 U	< 0.89 U	< 0.89 U	< 0.89 U
Rear Parking Lot	SSHS-B1192	SSHS-B1192-SUB-0-2	6/26/2018	852.13	0 - 2 ft	200-44065-1	Excavated	3.72	< 0.059 U	< 0.059 U	< 0.059 U	< 0.059 U	2.6 J	0.96 J	0.16 J	< 0.059 U	< 0.059 U
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-0-2	6/25/2018	851.62	0 - 2 ft	200-44046-1	Excavated	0.654	< 0.012 UJ	< 0.012 UJ	< 0.012 UJ	< 0.012 UJ	0.44 J	0.19 J	0.024 J	< 0.012 UJ	< 0.012 UJ
Rear Parking Lot	SSHS-B1194	SSHS-B1194-SUB-0-2	6/23/2018	851.92	0 - 2 ft	200-44028-1	Excavated	2.836	< 0.029 U	< 0.029 U	< 0.029 U	< 0.029 U	2 J	0.75 J	0.086 J	< 0.029 U	< 0.029 U
Rear Parking Lot	SSHS-B1195	SSHS-B1195-SUB-0-2	6/26/2018	849.43	0 - 2 ft	200-44065-1	Excavated	37.2	< 0.7 U	< 0.7 U	< 0.7 U	< 0.7 U	26 J	9.5 J	1.7 J	< 0.7 U	< 0.7 U
Rear Parking Lot	SSHS-B1196	SSHS-B1196-SUB-0-2	6/16/2018	853.82	0 - 2 ft	200-43950-2	Excavated	0.0079	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U	0.0079 J	< 0.0032 U	< 0.0032 U	< 0.0032 U	< 0.0032 U
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	ND	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U		
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	ND	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U		
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-0-2	7/21/2015	850.98	0 - 2 ft	180-46139-1	Excavated	67.8	< 0.18 U	< 0.22 U	< 0.31 U	< 0.23 U	48 J	17 J	2.8 J	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-0-2	7/24/2015	851.01	0 - 2 ft	180-46251-1	Excavated	3.99	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.9 J	0.98 J	0.11 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B122	PS-FD-#23	7/22/2015	851.00	0 - 2 ft	180-46170-1	Excavated	0.007	< 0.0036 U	< 0.0045 U	< 0.0061 U	< 0.0045 U	0.007 J	< 0.0042 U	< 0.0039 U	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-0-2	7/22/2015	851.00	0 - 2 ft	180-46170-1	Excavated	0.0247	< 0.0035 U	< 0.0043 U	< 0.006 U	< 0.0044 U	0.02 J	0.0047 J	< 0.0038 U	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-0-2	8/3/2015	851.17	0 - 2 ft	180-46601-1	Excavated	1.893	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	1.2 J	0.65 J	0.043 J	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-0-2	7/31/2015	850.91	0 - 2 ft	180-46444-1	Excavated	0.35	< 0.0035 U	< 0.0044 U	< 0.006 U	< 0.0044 U	0.24 J	0.096 J	0.014 J	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-0-2	7/31/2015	850.94	0 - 2 ft	180-46444-1	Excavated	9.91	< 0.037 U	< 0.045 U	< 0.062 U	< 0.045 U	6.6 J	2.8 J	0.51 J	< 0.066 U	< 0.036 U
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-0-2	7/31/2015	850.97	0 - 2 ft	180-46444-1	Excavated	16.78	< 0.035 U	< 0.043 U	< 0.06 U	< 0.044 U	11 J	5 J	0.78 J	< 0.064 U	< 0.035 U
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-0-2	7/31/2015	851.20	0 - 2 ft	180-46444-1	Excavated	94.8	< 0.19 U	< 0.23 U	< 0.31 U	< 0.23 U	66 J	25 J	3.8 J	< 0.34 U	< 0.18 U
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	0.15	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	0.15	< 0.044 U	< 0.044 U		
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	ND	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U		
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-0-2	7/21/2015	851.31	0 - 2 ft	180-46139-1	Excavated	24.96	< 0.036 U	< 0.045 U	< 0.062 U	< 0.045 U	18 J	6 J	0.96 J	< 0.066 U	< 0.036 U
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-0-2	7/24/2015	851.52	0 - 2 ft	180-46251-1	Excavated	0.943	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.65 J	0.25 J	0.043 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-0-2	7/22/2015	851.41	0 - 2 ft	180-46170-1	Excavated	0.813	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.56 J	0.22 J	0.033 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-0-2	8/3/2015	852.64	0 - 2 ft	180-46601-1	Not Excavated	0.722	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	0.44 J	0.24 J	0.042 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B135	SSHS-B135-SUB-0-2	7/27/2015	856.16	0 - 2 ft	180-46300-1	Excavated	1.449	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.88 J	0.49 J	0.079 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B138	SSHS-B138-SUB-0-2	7/27/2015	855.68	0 - 2 ft	180-46300-1	Excavated	0.55	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.32 J	0.19 J	0.04 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-0-2	8/3/2015	851.34	0 - 2 ft	180-46601-1	Excavated	5.65	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	3.6 J	1.9 J	0.15 J	< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B1395a	SSHS-B1395-SUB-0-2	7/28/2018	851.59	0 - 2 ft	180-80273-1	Excavated	0.261	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.22 J	0.041 J	< 0.0053 U	< 0.013 U	< 0.009 U
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	ND	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U		
Rear Parking Lot	SSHS-B140	SSHS-B140-SUB-0-2	7/31/2015	851.74	0 - 2 ft	180-46444-1	Excavated	2.18	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	1.4 J	0.64 J	0.14 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-0-2	7/21/2015	851.79	0 - 2 ft	180-46139-1	Excavated	2.063	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	1.4 J	0.61 J	0.053 J	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-0-2	7/21/2015	851.86	0 - 2 ft	180-46139-1	Excavated	21.91	< 0.073 U	< 0.089 U	< 0.12 U	< 0.09 U	15 J	6.1 J	0.81 J	< 0.13 U	< 0.072 U

DRAFT

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B143	SSHS-B143-SUB-0-1	7/21/2015	852.07	0 - 1 ft	180-46139-1	Excavated	0.767	< 0.0034 U	< 0.0042 U	< 0.0058 U	< 0.0043 U	0.54 J	0.2 J	0.027 J	< 0.0062 U	< 0.0034 U
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-0-2	7/21/2015	851.71	0 - 2 ft	180-46139-1	Excavated	91	< 0.18 U	< 0.22 U	< 0.31 U	< 0.22 U	66 J	21 J	4 J	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-0-2	7/24/2015	851.85	0 - 2 ft	180-46251-1	Excavated	3.1	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	2.1 J	0.89 J	0.11 J	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-0-2	7/22/2015	851.73	0 - 2 ft	180-46170-1	Excavated	0.0075	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.0075 J	< 0.0041 U	< 0.0038 U	< 0.0063 U	< 0.0035 U
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-0-2	7/23/2015	852.20	0 - 2 ft	180-46218-1	Excavated	0.931	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	0.66 J	0.24 J	0.031 J	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-0-2	8/3/2015	852.19	0 - 2 ft	180-46601-1	Excavated	ND	< 0.0034 U	< 0.0042 U	< 0.0058 U	< 0.0043 U	< 0.0042 U	< 0.004 U	< 0.0037 U	< 0.0062 U	< 0.0034 U
Rear Parking Lot	SSHS-B149	PS-FD-#19	7/21/2015	852.27	0 - 2 ft	180-46139-1	Excavated	0.349	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.22 J	0.11 J	0.019 J	< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-0-2	7/21/2015	852.27	0 - 2 ft	180-46139-1	Excavated	0.282	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.17 J	0.097 J	0.015 J	< 0.0065 U	< 0.0035 U
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	0.19	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	0.19	< 0.043 U	< 0.043 U		
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated	0.042	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	0.042	< 0.038 U	< 0.038 U		
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated	0.11	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.11	< 0.037 U	< 0.037 U		
Football Field	SSHS-B150	SSHS-B150-SUB-0-2	7/27/2015	855.84	0 - 2 ft	180-46300-1	Excavated	12.12	< 0.02 U	< 0.025 U	< 0.034 U	< 0.025 U	7.9 J	3.7 J	0.52 J	< 0.036 U	< 0.02 U
Football Field	SSHS-B151	SSHS-B151-SUB-0.17-2	8/5/2015	854.80	0.17 - 2 ft	180-46628-2	Excavated	43.6	< 0.19 U	< 0.23 U	< 0.31 U	< 0.23 U	29 J	13 J	1.6 J	< 0.34 U	< 0.18 U
Rear Parking Lot	SSHS-B156	SSHS-B156-SUB-0-2	8/3/2015	852.91	0 - 2 ft	180-46601-1	Excavated	16.43	< 0.072 U	< 0.088 U	< 0.12 U	< 0.089 U	11 J	4.9 J	0.53 J	< 0.13 U	< 0.071 U
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-0-2	7/31/2015	852.12	0 - 2 ft	180-46444-1	Excavated	14.93	< 0.018 U	< 0.022 U	< 0.03 U	< 0.022 U	9.8 J	4.4 J	0.73 J	< 0.032 U	< 0.018 U
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-0-2	7/21/2015	852.02	0 - 2 ft	180-46139-1	Excavated	0.439	< 0.0035 U	< 0.0043 U	< 0.0059 U	< 0.0043 U	0.29 J	0.12 J	0.029 J	< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B159	CS-FD-#25	8/3/2015	852.33	0 - 2 ft	180-46601-1	Excavated	62.1	< 0.18 U	< 0.22 U	< 0.3 U	< 0.22 U	43 J	17 J	2.1 J	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-0-2	8/3/2015	852.33	0 - 2 ft	180-46601-1	Excavated	106.2	< 0.36 U	< 0.44 U	< 0.61 U	< 0.45 U	82 J	22 J	2.2 J	< 0.65 U	< 0.36 U
Football Field	SSHS-B15-A	SSHS-B15-A-0.17-1	7/22/2014	856.92	0.17 - 1 ft	180-35079-1	Excavated	6.5	< 0.0033 U	< 0.0042 U	< 0.0038 U	< 0.0036 U	4.6 J	1.9 J	< 0.0031 U	< 0.0048 U	< 0.0028 U
Football Field	SSHS-B15-A	SSHS-B15-A-1-2	7/22/2014	856.92	1 - 2 ft	180-35079-1	Excavated	0.55	< 0.00067 U	< 0.00086 U	< 0.00077 U	< 0.00073 U	0.4 J	0.15 J	< 0.00064 U	< 0.00098 U	< 0.00058 U
Football Field	SSHS-B15-B	SSHS-B15-B-0.17-1	7/22/2014	856.80	0.17 - 1 ft	180-35079-1	Excavated	6.3	< 0.0066 U	< 0.0084 U	< 0.0075 U	< 0.0072 U	4.3 J	2 J	< 0.0063 U	< 0.0097 U	< 0.0057 U
Football Field	SSHS-B15-B	SSHS-B15-B-1-2	7/22/2014	856.80	1 - 2 ft	180-35079-1	Excavated	0.144	< 0.0013 U	< 0.0017 U	< 0.0015 U	< 0.0015 U	0.088 J	0.056 J	< 0.0013 U	< 0.002 U	< 0.0011 U
Football Field	SSHS-B15-C	SSHS-B15-C-0.17-1	7/22/2014	856.91	0.17 - 1 ft	180-35079-1	Excavated	5.7	< 0.0066 U	< 0.0085 U	< 0.0076 U	< 0.0072 U	4 J	1.7 J	< 0.0063 U	< 0.0097 U	< 0.0057 U
Football Field	SSHS-B15-C	SSHS-B15-C-1-2	7/22/2014	856.91	1 - 2 ft	180-35079-1	Excavated	1.169	< 0.0013 U	< 0.0017 U	< 0.0015 U	< 0.0015 U	0.81 J	0.33 J	< 0.0013 U	0.029 J	< 0.0012 U
Rear Parking Lot	SSHS-B160	SSHS-B160-SUB-0-1.5	7/21/2015	852.12	0 - 1.5 ft	180-46139-1	Excavated	23.31	< 0.069 U	< 0.085 U	< 0.12 U	< 0.086 U	15 J	7.4 J	0.91 J	< 0.13 U	< 0.068 U
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-0-2	8/3/2015	852.38	0 - 2 ft	180-46601-1	Excavated	21.88	< 0.071 U	< 0.087 U	< 0.12 U	< 0.088 U	15 J	6.3 J	0.58 J	< 0.13 U	< 0.07 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-0-2	8/3/2015	852.38	0 - 2 ft	180-46601-1	Excavated	1.38	< 0.0035 U	< 0.0042 U	< 0.0059 U	< 0.0043 U	1 J	0.38 J		< 0.0063 U	< 0.0034 U
Rear Parking Lot	SSHS-B163	CS-FD-#23	8/3/2015	852.21	0 - 2 ft	180-46601-1	Excavated	4.36	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	2.7 J	1.5 J	0.16 J	< 0.0067 U	< 0.0036 U
Rear Parking Lot	SSHS-B163	SSHS-B163-SUB-0-2	8/3/2015	852.21	0 - 2 ft	180-46601-1	Excavated	4.54	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	3 J	1.4 J	0.14 J	< 0.0065 U	< 0.0036 U
Football Field	SSHS-B164	CS-FD-#1	7/27/2015	855.84	0 - 2 ft	180-46300-1	Excavated	4.91	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.1 J	1.6 J	0.21 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B164	SSHS-B164-SUB-0-2	7/27/2015	855.84	0 - 2 ft	180-46300-1	Excavated	2.21	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	1.4 J	0.71 J	0.1 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B165	SSHS-B165-SUB-0-2	7/27/2015	855.61	0 - 2 ft	180-46300-1	Excavated	1.9	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	1.2 J	0.59 J	0.11 J	< 0.0069 U	< 0.0037 U
Football Field	SSHS-B166	SSHS-B166-SUB-0-2	7/27/2015	855.88	0 - 2 ft	180-46300-1	Excavated	0.51	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0047 U	0.39 J	0.12 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B168	SSHS-B168-SUB-0-2	7/27/2015	855.64	0 - 2 ft	180-46300-1	Excavated	1.082	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.68 J	0.33 J	0.072 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B169	SSHS-B169-SUB-0.17-2	7/28/2015	855.30	0.17 - 2 ft	180-46310-1	Excavated	80.3	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	55 J	23 J	2.3 J	< 0.34 U	< 0.18 U
Football Field	SSHS-B169B	B169-B	8/3/2017	855.30	0 - 0.5 ft	180-68926-1	Excavated	0.74	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	0.37	0.27	0.1	< 0.014 U	< 0.0061 U
Football Field	SSHS-B170	SSHS-B170-SUB-0-2	7/27/2015	856.27	0 - 2 ft	180-46300-1	Excavated	0.27	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.16 J	0.09 J	0.02 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B173	CS-FD-#101	8/5/2015	854.70	0.17 - 2 ft	180-46628-2	Excavated	48.6	< 0.075 U	< 0.093 U	< 0.13 U	< 0.093 U	32 J	15 J	1.6 J	< 0.14 U	< 0.074 U
Football Field	SSHS-B173	SSHS-B173-SUB-0.17-2	8/5/2015	854.70	0.17 - 2 ft	180-46628-2	Excavated	42.4	< 0.076 U	< 0.093 U	< 0.13 U	< 0.094 U	28 J	13 J	1.4 J	< 0.14 U	< 0.075 U
Football Field	SSHS-B175	SSHS-B175-SUB-0.17-2	7/28/2015	855.09	0.17 - 2 ft	180-46310-1	Excavated	6.23	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	4.2 J	1.8 J	0.23 J	< 0.007 U	< 0.0038 U
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	11					11				
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	9.5					9.5				
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	8.4					8.4				
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	ND	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U		
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	2.12	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	1	1	0.12	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	0.098	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.027	0.041	0.03	< 0.015 U	< 0.01 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	0.054	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.021	0.033	< 0.0056 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	0.86	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.41	0.34	0.11	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	0.017	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	0.017 J	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	ND	< 0.0073 U	< 0.015 U	< 0.013 U	< 0.013 U	< 0.018 U	< 0.015 U	< 0.0064 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	0.23	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.12	0.11	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	ND	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated	0.044	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.026	0.018 J	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	1.563	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.71	0.78	0.073	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	1.614	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.92	0.6	0.094	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	0.917	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.49	0.33	0.097	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	ND	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.01 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated	0.63	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.26	0.26	0.11	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	1.84	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.71	0.91	0.22	< 0.014 U	< 0.0094 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	1.052	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.6	0.36	0.092	< 0.013 U	< 0.009 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	0.077	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.031	0.046	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	0.16	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.08	0.057	0.023	< 0.014 U	< 0.01 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	0.029	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.029	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	0.016	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	< 0.015 U	0.016 J	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B212	SSHS-B212-SUB-0-2	7/28/2015	855.42	0 - 2 ft	180-46310-1	Excavated	21.45	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	15 J	6 J	0.45 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	0.0307	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.021	0.0097 J	< 0.015 U	< 0.01 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	0.739	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.4	0.26	0.079	< 0.014 U	< 0.01 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	0.191	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11	0.081	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	0.195	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11	0.085	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B214	SSHS-B214-SUB-0-2	7/28/2015	855.97	0 - 2 ft	180-46310-1	Excavated	0.76	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.32 J	0.36 J	0.08 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B216	SSHS-B216-SUB-0-2	7/16/2015	855.82	0 - 2 ft	180-46033-1	Excavated	15.4	< 0.02 U	< 0.025 U	< 0.034 U	< 0.025 U	11 J	4.4 J	< 0.021 U	< 0.036 U	< 0.02 U
Football Field	SSHS-B217	SSHS-B217-SUB-0-2	7/16/2015	856.26	0 - 2 ft	180-46033-1	Excavated	0.69	< 0.0042 U	< 0.0051 U	< 0.007 U	< 0.0052 U	0.48 J	0.21 J	< 0.0045 U	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B218	SSHS-B218-SUB-0-2	7/16/2015	856.58	0 - 2 ft	180-46033-1	Excavated	2.276	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	1.5 J	0.7 J	0.076 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	0.958	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.58	0.28	0.098	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	3.61	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7	1.7	0.21	< 0.013 U	< 0.009 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	1.697	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	1	0.63	0.067	< 0.013 U	< 0.0086 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	1.63	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	1.1	0.44	0.09	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	0.88	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.73	0.15	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	19.8	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	15	4.8		< 0.13 U	< 0.091 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	23.52	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	18	4.7	0.82	< 0.13 U	< 0.091 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	9.5	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	6.2	3	0.3	< 0.067 U	< 0.046 U
Football Field	SSHS-B220	SSHS-B220-SUB-0-2	7/28/2015	855.52	0 - 2 ft	180-46310-1	Excavated	4.278	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.1 J	1.1 J	0.078 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B221	SSHS-B221-SUB-0-2	7/15/2015	855.95	0 - 2 ft	180-45961-1	Excavated	20.2	< 0.08 U	< 0.098 U	< 0.14 U	< 0.099 U	14 J	6.2 J	< 0.086 U	< 0.14 U	< 0.079 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	0.034	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.034	< 0.0058 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated	0.5	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.36	0.095	0.045	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	0.185	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.09	0.095	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	0.22	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11	0.11	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	5.02	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	4.5	0.52	< 0.014 U	< 0.0095 U
Football Field	SSHS-B222	SSHS-B222-SUB-0-2	7/16/2015	856.64	0 - 2 ft	180-46033-1	Excavated	0.967	< 0.0042 U	< 0.0051 U	< 0.007 U	< 0.0052 U	0.61 J	0.31 J	0.047 J	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	10.5	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4	5	1.5	< 0.014 U	< 0.0095 U
Football Field	SSHS-B223	SSHS-B223-SUB-0-2	7/28/2015	856.68	0 - 2 ft	180-46310-1	Excavated	1.88	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	1 J	0.69 J	0.19 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	2.01	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.3	0.71		< 0.014 U	< 0.0096 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	3.487	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	2.3	1.1	0.087	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	0.52	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.14	0.26	0.12	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	0.5	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.14	0.25	0.11	< 0.013 U	< 0.0091 U
Football Field	SSHS-B225	SSHS-B225-SUB-0-2	7/28/2015	855.94	0 - 2 ft	180-46310-1	Excavated	7.64	< 0.0039 U,F1	< 0.0048 U	< 0.0066 U	< 0.0048 U	5.4 J	2.1 J	0.14 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B226	SSHS-B226-SUB-0-2	7/15/2015	856.35	0 - 2 ft	180-45961-1	Excavated	9.79	< 0.041 U	< 0.05 U	< 0.069 U	< 0.051 U	9.6	< 0.048 U	0.19 J	< 0.074 U	< 0.04 U
Football Field	SSHS-B227	SSHS-B227-SUB-0-2	7/15/2015	856.71	0 - 2 ft	180-45961-1	Excavated	11.19	< 0.04 U	< 0.05 U	< 0.069 U	< 0.05 U	11	< 0.047 U	0.19 J	< 0.073 U	< 0.04 U
Football Field	SSHS-B228	SSHS-B228-SUB-0-2	7/15/2015	856.95	0 - 2 ft	180-45961-1	Excavated	0.137	< 0.004 U	< 0.005 U	< 0.0069 U	< 0.005 U	< 0.005 U	0.099 J	0.038 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B229	PS-FD-#3	7/15/2015	857.03	0 - 2 ft	180-45961-1	Excavated	5.91	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	4 J	1.8 J	0.11 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B229	SSHS-B229-SUB-0-2	7/15/2015	857.03	0 - 2 ft	180-45961-1	Excavated	4	< 0.004 U	< 0.005 U	< 0.0069 U	< 0.005 U	2.7 J	1.2 J	0.1 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B230	SSHS-B230-SUB-0-2	7/28/2015	857.08	0 - 2 ft	180-46310-1	Excavated	1.771	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	1.3 J	0.43 J	0.041 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2300	SSHS-B2300-SUB-0.17-2	8/29/2018	855.68	0.17 - 2 ft	180-81403-1	Excavated	3.8	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2.7	1.1		< 0.013 U	< 0.0092 U
Football Field	SSHS-B2301	SSHS-B2301-SUB-0.17-2	8/28/2018	855.09	0.17 - 2 ft	180-81347-1	Excavated	0.468	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.3	0.14	0.028	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2305	SSHS-B2305-SUB-0.17-2	8/29/2018	857.26	0.17 - 2 ft	180-81403-1	Excavated	0.29	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.14	0.15	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2306	SSHS-B2306-SUB-0.17-2	8/29/2018	857.17	0.17 - 2 ft	180-81403-1	Excavated	2.459	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7	0.68	0.079	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2307	SSHS-B2307-SUB-0.17-2	8/29/2018	857.15	0.17 - 2 ft	180-81403-1	Excavated	0.248	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.15	0.098	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2309	SSHS-B2309-SUB-0.17-2	8/28/2018	856.61	0.17 - 2 ft	180-81347-1	Excavated	0.257	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.16	0.097	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B231	SSHS-B231-SUB-0-2	7/27/2015	856.10	0 - 2 ft	180-46300-1	Excavated	23.11	< 0.039 U	< 0.048 U	< 0.067 U	< 0.049 U	17 J	5.5 J	0.61 J	< 0.071 U	< 0.039 U
Football Field	SSHS-B2312	SSHS-B2312-SUB-0.17-2	8/27/2018	856.88	0.17 - 2 ft	180-81330-1	Excavated	2.767	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.9	0.84	0.027	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2313	SSHS-B2313-SUB-0.17-2	8/27/2018	856.38	0.17 - 2 ft	180-81330-1	Excavated	0.207	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.12	0.087	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2315	SSHS-B2315-SUB-0.17-2	8/29/2018	854.95	0.17 - 2 ft	180-81403-1	Excavated	4.75	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3.1	1.4	0.25	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2317	SSHS-B2317-SUB-0.17-2	8/29/2018	855.56	0.17 - 2 ft	180-81403-1	Excavated	0.034	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.018 J	0.016 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2318	SSHS-B2318-SUB-0.17-2	8/29/2018	856.42	0.17 - 2 ft	180-81403-1	Excavated	0.28	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.17	0.11	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B232	SSHS-B232-SUB-0-2	7/27/2015	856.44	0 - 2 ft	180-46300-1	Excavated	3.61	< 0.0039 U	< 0.0047 U	< 0.0066 U	< 0.0048 U	2.3 J	1.1 J	0.21 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B233	SSHS-B233-SUB-0-2	7/28/2015	856.93	0 - 2 ft	180-46310-1	Excavated	56.1	< 0.08 U	< 0.098 U	< 0.13 U	< 0.099 U	40 J	15 J	1.1 J	< 0.14 U	< 0.079 U
Football Field	SSHS-B2342	SSHS-B2342-SUB-0.17-2	8/27/2018	855.45	0.17 - 2 ft	180-81330-1	Excavated	0.128	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.07	0.058	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2343	SSHS-B2343-SUB-0.17-2	8/27/2018	855.24	0.17 - 2 ft	180-81330-1	Excavated	0.711	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.43	0.25	0.031	< 0.013 U	< 0.0091 U
Football Field	SSHS-B234A	SSHS-B234A-SUB-0-2	7/28/2015	857.08	0 - 2 ft	180-46310-1	Excavated	0.652	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.36 J	0.21 J	0.082 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B236	SSHS-B236-SUB-0-2	7/14/2015	856.80	0 - 2 ft	180-45961-1	Excavated	0.0933	< 0.0037 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	0.052 J	0.032 J	0.0093 J	< 0.0068 U	< 0.0037 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B237	SSHS-B237-SUB-0-2	7/27/2015	857.09	0 - 2 ft	180-46300-1	Excavated	2.8	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	1.7 J	0.99 J	0.11 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2376	SSHS-B2376-SUB-0.17-2	8/28/2018	855.08	0.17 - 2 ft	180-81347-1	Excavated	0.057	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.034	0.023	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B238	SSHS-B238-SUB-0-2	7/14/2015	856.59	0 - 2 ft	180-45961-1	Excavated	0.886	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.54 J	0.29 J	0.056 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B2385	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	0.17 - 2 ft	180-81525-1	Not Excavated	1.51	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.012 U	< 0.017 U	1.2	0.31	< 0.015 U	< 0.01 U
Football Field	SSHS-B2386	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	0.17 - 2 ft	180-81525-1	Not Excavated	0.088	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.071	0.017 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B239	SSHS-B239-SUB-0-2	7/14/2015	857.05	0 - 2 ft	180-45961-1	Excavated	14.23	< 0.04 U	< 0.049 U	< 0.068 U	< 0.05 U	14	< 0.047 U	0.23	< 0.072 U	< 0.039 U
Football Field	SSHS-B240	SSHS-B240-SUB-0-2	7/27/2015	857.39	0 - 2 ft	180-46300-1	Excavated	0.608	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.36 J	0.21 J	0.038 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B241	SSHS-B241-SUB-0-2	7/14/2015	856.84	0 - 2 ft	180-45961-1	Excavated	0.356	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.23 J	0.11 J	0.016 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B241	PS-FD-#1	7/15/2015	856.84	0 - 2 ft	180-45961-1	Excavated	0.522	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.35 J	0.16 J	0.012 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B242	SSHS-B242-SUB-0-2	7/27/2015	857.07	0 - 2 ft	180-46300-1	Excavated	93.4	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	67 J	24 J	2.4 J	< 0.36 U	< 0.19 U
Football Field	SSHS-B246	SSHS-B246-SUB-0-2	7/30/2015	856.12	0 - 2 ft	180-46426-1	Excavated	0.486	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	0.27 J	0.19 J	0.026 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B248	PS-FD-#11	7/20/2015	856.87	0 - 2 ft	180-46075-1	Excavated	1.306	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.88 J	0.38 J	0.046 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B248	SSHS-B248-SUB-0-2	7/20/2015	856.87	0 - 2 ft	180-46075-1	Excavated	1.128	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.74 J	0.35 J	0.038 J	< 0.0074 U	< 0.004 U
Football Field	SSHS-B249	SSHS-B249-SUB-0-2	7/30/2015	856.83	0 - 2 ft	180-46426-1	Excavated	0.0442	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.021 J	0.017 J	0.0062 J	< 0.0074 U	< 0.004 U
Football Field	SSHS-B250	CS-FD-#15	7/30/2015	856.50	0 - 2 ft	180-46426-1	Excavated	1.196	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.62 J	0.49 J	0.086 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B250	SSHS-B250-SUB-0-2	7/30/2015	856.50	0 - 2 ft	180-46426-1	Excavated	1.135	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.57 J	0.47 J	0.095 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B2500	SSHS-B2500-SUB-0.17-2	10/30/2018	854.97	0.17 - 2 ft	180-83544-1	Excavated	0.42	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.36 J	0.06 J	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2501	SSHS-B2501-SUB-0.17-2	10/30/2018	855.04	0.17 - 2 ft	180-83544-1	Excavated	1.44	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	1.2 J	0.24 J	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2502	SSHS-B2502-SUB-0.17-2	10/30/2018	854.88	0.17 - 2 ft	180-83544-1	Excavated	0.112	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.099 J	0.013 J	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2503	SSHS-B2503-SUB-0.17-2	10/30/2018	855.00	0.17 - 2 ft	180-83544-1	Excavated	0.444	< 0.0069 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	0.38 J	0.064 J	< 0.015 U	< 0.01 U
Football Field	SSHS-B2504	SSHS-B2504-SUB-0.17-2	10/30/2018	856.73	0.17 - 2 ft	180-83544-1	Excavated	0.769	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.56 J	0.17 J	0.039 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2505	SSHS-B2505-SUB-0.17-2	10/30/2018	856.45	0.17 - 2 ft	180-83544-1	Excavated	2.05	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.3 J	0.59 J	0.16 J	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2506	SSHS-B2506-SUB-0.17-2	10/30/2018	856.53	0.17 - 2 ft	180-83544-1	Excavated	1.357	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.96 J	0.32 J	0.077 J	< 0.014 U	< 0.0095 U
Football Field	SSHS-B251	SSHS-B251-SUB-0-2	7/20/2015	856.76	0 - 2 ft	180-46075-1	Excavated	1.146	< 0.0042 U	< 0.0052 U	< 0.0071 U	< 0.0052 U	0.77 J	0.33 J	0.046 J	< 0.0076 U	< 0.0041 U
Football Field	SSHS-B2517	SSHS-B2517-SUB-0.17-2	10/31/2018	855.67	0.17 - 2 ft	180-83573-1	Excavated	0.967	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.57 J	0.35 J	0.047 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B252	SSHS-B252-SUB-0-2	7/20/2015	856.86	0 - 2 ft	180-46075-1	Excavated	0.1541	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.098 J	0.051 J	0.0051 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B2528	SSHS-B2528-SUB-0.17-2	10/30/2018	854.76	0.17 - 2 ft	180-83544-1	Excavated	3.91	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	3 J	0.75 J	0.16 J	< 0.014 U	< 0.01 U
Football Field	SSHS-B253	SSHS-B253-SUB-0-2	7/30/2015	856.85	0 - 2 ft	180-46426-1	Excavated	0.183	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.086 J	0.072 J	0.025 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B2531	SSHS-B2531-SUB-0.17-2	10/30/2018	856.55	0.17 - 2 ft	180-83544-1	Excavated	1.053	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.64 J	0.32 J	0.093 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-0.17-2	10/29/2018	855.29	0.17 - 2 ft	180-83541-1	Excavated	2.33	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	1.6 J	0.58 J	0.15 J	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2537	PS-FD-4	10/30/2018	855.50	0.17 - 2 ft	180-83544-1	Excavated	0.074	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.038 J	0.03 J	0.006 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2537	SSHS-B2537-SUB-0.17-2	10/30/2018	855.50	0.17 - 2 ft	180-83544-1	Excavated	0.15	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.08 J	0.059 J	0.011 J	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2538	SSHS-B2538-SUB-0.17-2	10/30/2018	854.98	0.17 - 2 ft	180-83544-1	Excavated	134.8	< 0.24 U	< 0.47 U	< 0.43 U	< 0.43 U	88 J	43 J	3.8 J	< 0.51 U	< 0.35 U
Football Field	SSHS-B254	SSHS-B254-SUB-0-2	7/30/2015	856.06	0 - 2 ft	180-46426-1	Excavated	0.559	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.33 J	0.2 J	0.029 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B255	SSHS-B255-SUB-0-2	7/30/2015	856.67	0 - 2 ft	180-46426-1	Excavated	1.667	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.97 J	0.61 J	0.087 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B256	SSHS-B256-SUB-0-2	7/20/2015	856.85	0 - 2 ft	180-46075-1	Excavated	104.5	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	68 J	33 J	3.5 J	< 0.34 U	< 0.19 U
Football Field	SSHS-B257	CS-FD-#16	7/30/2015	856.92	0 - 2 ft	180-46426-1	Excavated	2.7	< 0.0044 U	< 0.0054 U	< 0.0074 U	< 0.0054 U	1.6 J	0.98 J	0.12 J	< 0.008 U	< 0.0043 U
Football Field	SSHS-B257	SSHS-B257-SUB-0-2	7/30/2015	856.92	0 - 2 ft	180-46426-1	Excavated	0.801	< 0.0042 U	< 0.0052 U	< 0.0071 U	< 0.0052 U	0.48 J	0.28 J	0.041 J	< 0.0076 U	< 0.0041 U
Football Field	SSHS-B259	SSHS-B259-SUB-0-2	7/29/2015	855.79	0 - 2 ft	180-46367-1	Excavated	0.941	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	0.7 J	0.15 J	0.091 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B260	SSHS-B260-SUB-0-2	7/29/2015	856.02	0 - 2 ft	180-46367-1	Excavated	2.098	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	1.2 J	0.8 J	0.098 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B2603	SSHS-B2603-SUB-0.17-2	5/19/2019	855.24	0.17 - 2 ft	180-90323-1	Excavated	66.5	< 0.13 U	< 0.14 U	< 0.095 U	< 0.057 U	51 J	12 J	3.5 J	< 0.14 U	< 0.052 U
Football Field	SSHS-B2604	SSHS-B2604-SUB-0.17-2	5/19/2019	855.25	0.17 - 2 ft	180-90323-1	Excavated	6.64	< 0.0077 U	< 0.0084 U	< 0.0057 U	< 0.0035 U	4.4 J	1.7 J	0.54 J	< 0.0083 U	< 0.0032 U
Football Field	SSHS-B2606	PS-FD-34	5/22/2019	855.71	0.17 - 2 ft	180-90524-1	Excavated	2.4	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.6 J	0.59 J	0.21 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2606	SSHS-B2606-SUB-0.17-2	5/22/2019	855.71	0.17 - 2 ft	180-90524-1	Excavated	2.68	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.9 J	0.58 J	0.2 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B261	SSHS-B261-SUB-0-2	7/17/2015	855.83	0 - 2 ft	180-46045-1	Excavated	2.31	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	1.4 J	0.79 J	0.12 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2618	SSHS-B2618-SUB-0.17-2	5/17/2019	855.12	0.17 - 2 ft	180-90275-1	Excavated	7.77	< 0.03 U	< 0.032 U	< 0.022 U	< 0.013 U	4.8 J	2.3 J	0.67 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B262	SSHS-B262-SUB-0-2	7/29/2015	855.62	0 - 2 ft	180-46367-1	Excavated	2.44	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	1.5 J	0.83 J	0.11 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B2623	SSHS-B2623-SUB-0.17-2	5/14/2019	854.91	0.17 - 2 ft	180-90048-1	Excavated	4.01	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2.6 J	1 J	0.41 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2624	SSHS-B2624-SUB-0.17-2	5/14/2019	855.29	0.17 - 2 ft	180-90048-1	Excavated	16.6	< 0.032 U	< 0.035 U	< 0.024 U	< 0.015 U	11 J	3.9 J	1.7 J	< 0.035 U	< 0.013 U
Football Field	SSHS-B264	SSHS-B264-SUB-0-2	7/17/2015	855.93	0 - 2 ft	180-46045-1	Excavated	3.82	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.1 J	1.4 J	0.32 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B2648	SSHS-B2648-SUB-0.17-2	5/16/2019	855.86	0.17 - 2 ft	180-90231-1	Excavated	3.41	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.003 U	2.7 J	0.71 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B265	SSHS-B265-SUB-0-2	7/17/2015	855.73	0 - 2 ft	180-46045-1	Excavated	11.01	< 0.019 U	< 0.023 U	< 0.032 U	< 0.023 U	7.2 J	3.3 J	0.51 J	< 0.034 U	< 0.019 U
Football Field	SSHS-B266	PS-FD-#8	7/17/2015	855.92	0 - 2 ft	180-46045-1	Excavated	4.62	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	2.7 J	1.6 J	0.32 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B266	SSHS-B266-SUB-0-2	7/17/2015	855.92	0 - 2 ft	180-46045-1	Excavated	3.35	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	1.9 J	1.2 J	0.25 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B267	SSHS-B267-SUB-0-2	7/30/2015	855.57	0 - 2 ft	180-46426-1	Excavated	0.0701	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.029 J	0.032 J	0.0091 J	< 0.0065 U	< 0.0035 U
Football Field	SSHS-B2677	SSHS-B2677-SUB-0.17-2	5/21/2019	855.87	0.17 - 2 ft	180-90380-1	Excavated	3.82	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	2.2 J	1.4 J	0.22 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B268	SSHS-B268-SUB-0-2	7/29/2015	855.75	0 - 2 ft	180-46367-1	Excavated	7.64	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	6.4 J	0.86 J	0.38 J	< 0.068 U	< 0.037 U
Football Field	SSHS-B2685	SSHS-B2685-SUB-0.17-2	5/17/2019	855.39	0.17 - 2 ft	180-90275-1	Excavated	5.57	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	3.7 J	1.4 J	0.47 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-0.17-2	5/15/2019	855.51	0.17 - 2 ft	180-90165-1	Excavated	5.11	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	3.3 J	1.3 J	0.51 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2689	SSHS-B2689-SUB-0.17-2	5/22/2019	855.78	0.17 - 2 ft	180-90524-1	Excavated	2.81	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2 J	0.59 J	0.22 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B269	PS-FD-#9	7/17/2015	855.71	0 - 2 ft	180-46045-1	Excavated	22	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	15 J	6.2 J	0.8 J	< 0.069 U	< 0.037 U
Football Field	SSHS-B269	SSHS-B269-SUB-0-2	7/17/2015	855.71	0 - 2 ft	180-46045-1	Excavated	37.4	< 0.038 U	< 0.047 U	< 0.065 U	< 0.048 U	25 J	11 J	1.4 J	< 0.07 U	< 0.038 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2690	PS-FD-29	5/21/2019	855.32	0.17 - 2 ft	180-90380-1	Excavated	1.77	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.84 J	0.75 J	0.18 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2690	SSHS-B2690-SUB-0.17-2	5/21/2019	855.32	0.17 - 2 ft	180-90380-1	Excavated	3.53	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.9 J	1.3 J	0.33 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	1.25	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.4 J	0.58 J	0.27 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B270	SSHS-B270-SUB-0-2	7/17/2015	855.94	0 - 2 ft	180-46045-1	Excavated	3.04	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	1.9 J	0.96 J	0.18 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2703	SSHS-B2703-SUB-0.17-2	5/19/2019	854.92	0.17 - 2 ft	180-90323-2	Excavated	151.3	< 0.31 U	< 0.34 U	< 0.23 U	< 0.14 U	120 J	24 J	7.3 J	< 0.33 U	< 0.13 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.013	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	0.013 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.236	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.054 J	0.1 J	0.082 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.179	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.045 J	0.067 J	0.067 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	1.08	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.65 J	0.43 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	0.052	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	0.052	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	0.43	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.26 J	0.14 J	0.03 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	0.343	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.21 J	0.11 J	0.023 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	0.247	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.032 J	0.15 J	0.065 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B271	SSHS-B271-SUB-0-2	7/17/2015	855.95	0 - 2 ft	180-46045-1	Excavated	5.02	< 0.0041 U	< 0.0051 U	< 0.007 U	< 0.0051 U	3 J	1.7 J	0.32 J	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.349	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U		0.25 J	0.099 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.484	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.19 J	0.2 J	0.094 J	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	0.55	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.37 J	0.18 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	0.115	< 0.0033 U	< 0.0036 U	< 0.0025 U	< 0.0015 U	0.081 J	0.034 J	< 0.0029 U	< 0.0036 U	< 0.0014 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	1.15	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.83 J	0.32 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	0.066	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.045 J	0.021 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	0.05	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.03 J	0.02 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	0.083	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.058 J	0.025 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	124	< 0.32 U	< 0.35 U	< 0.24 U	< 0.15 U	78 J	35 J	11 J	< 0.35 U	< 0.13 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	4.21	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2.9 J	0.97 J	0.34 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	0.3	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.17 J	0.091 J	0.039 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	1.22	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.69 J	0.38 J	0.15 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	4.27	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	2.6 J	1.2 J	0.47 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2726	PS-FD-32	5/22/2019	856.12	0.17 - 2 ft	180-90524-1	Excavated	0.492	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.32 J	0.13 J	0.042 J	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B2726	SSHS-B2726-SUB-0.17-2	5/22/2019	856.12	0.17 - 2 ft	180-90524-1	Excavated	0.58	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.5 J		0.08 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2727	PS-FD-33	5/22/2019	856.45	0.17 - 2 ft	180-90524-1	Excavated	0.388	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.27 J	0.086 J	0.032 J	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B2727	SSHS-B2727-SUB-0.17-2	5/22/2019	856.45	0.17 - 2 ft	180-90524-1	Excavated	7.91	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	6 J	1.5 J	0.41 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B2728	SSHS-B2728-SUB-0.17-2	5/21/2019	856.47	0.17 - 2 ft	180-90380-1	Excavated	22.1	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	13 J	7.8 J	1.3 J	< 0.068 U	< 0.026 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-0.17-2	5/21/2019	856.49	0.17 - 2 ft	180-90380-1	Excavated	5.1	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.1 J	2.5 J	0.5 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B273	CS-FD-#10	7/29/2015	855.95	0 - 2 ft	180-46367-1	Excavated	1.74	< 0.0042 U	< 0.0052 U	< 0.0071 U	< 0.0052 U	1.2 J	0.33 J	0.21 J	< 0.0076 U	< 0.0042 U
Football Field	SSHS-B273	SSHS-B273-SUB-0-2	7/29/2015	855.95	0 - 2 ft	180-46367-1	Excavated	2.31	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	1.1 J	1 J	0.21 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B2730	SSHS-B2730-SUB-0.17-2	5/21/2019	856.08	0.17 - 2 ft	180-90380-1	Excavated	2.74	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.7 J	0.84 J	0.2 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2731	PS-FD-30	5/21/2019	856.44	0.17 - 2 ft	180-90380-1	Excavated	1.112	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.74 J	0.32 J	0.052 J	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B2731	SSHS-B2731-SUB-0.17-2	5/21/2019	856.44	0.17 - 2 ft	180-90380-1	Excavated	2.68	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.7 J	0.8 J	0.18 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2732	SSHS-B2732-SUB-0.17-2	5/21/2019	855.83	0.17 - 2 ft	180-90380-1	Excavated	0.198	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.12 J	0.061 J	0.017 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B274	SSHS-B274-SUB-0-2	7/29/2015	856.07	0 - 2 ft	180-46367-1	Excavated	5.74	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	3.3 J	2.2 J	0.24 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B275	SSHS-B275-SUB-0-2	7/17/2015	856.07	0 - 2 ft	180-46045-1	Excavated	2.99	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	1.8 J	1 J	0.19 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B276	SSHS-B276-SUB-0-2	7/29/2015	856.16	0 - 2 ft	180-46367-1	Excavated	3.73	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	3.5 J		0.23 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B2768	PS-FD-4	5/14/2019	855.11	0.17 - 2 ft	180-90048-1	Excavated	1.06	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.65 J	0.29 J	0.12 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2768	SSHS-B2768-SUB-0.17-2	5/14/2019	855.11	0.17 - 2 ft	180-90048-1	Excavated	3.08	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	1.9 J	0.83 J	0.35 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2769	SSHS-B2769-SUB-0.17-2	5/15/2019	855.10	0.17 - 2 ft	180-90165-1	Excavated	5.96	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	5 J		0.96 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B277	SSHS-B277-SUB-0-2	7/29/2015	855.87	0 - 2 ft	180-46367-1	Excavated	3.17	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.3 J	0.72 J	0.15 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B278	SSHS-B278-SUB-0-2	7/16/2015	855.94	0 - 2 ft	180-46033-1	Excavated	1.11	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.69 J	0.36 J	0.06 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B279	SSHS-B279-SUB-0-2	7/29/2015	856.14	0 - 2 ft	180-46367-1	Excavated	2.37	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1.7 J	0.52 J	0.15 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B280	PS-FD-#6	7/16/2015	855.92	0 - 2 ft	180-46033-1	Excavated	2.269	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	1.4 J	0.78 J	0.089 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B280	SSHS-B280-SUB-0-2	7/16/2015	855.92	0 - 2 ft	180-46033-1	Excavated	1.86	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	1.1 J	0.69 J	0.07 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2806	SSHS-B2806-SUB-0.17-2	5/15/2019	855.10	0.17 - 2 ft	180-90165-1	Excavated	0.075	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.034 J	0.025 J	0.016 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B281	SSHS-B281-SUB-0-2	7/17/2015	856.15	0 - 2 ft	180-46045-1	Excavated	9.29	< 0.019 U	< 0.023 U	< 0.032 U	< 0.023 U	5.9 J	3.1 J	0.29 J	< 0.034 U	< 0.019 U
Football Field	SSHS-B282	CS-FD-#12	7/29/2015	855.62	0 - 2 ft	180-46367-1	Excavated	2.86	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	2 J	0.69 J	0.17 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B282	SSHS-B282-SUB-0-2	7/29/2015	855.62	0 - 2 ft	180-46367-1	Excavated	2.33	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1.5 J	0.68 J	0.15 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B283	SSHS-B283-SUB-0-2	7/16/2015	855.95	0 - 2 ft	180-46033-1	Excavated	17.4	< 0.077 U	< 0.095 U	< 0.13 U	< 0.096 U	12 J	5.4 J	< 0.083 U	< 0.14 U	< 0.076 U
Football Field	SSHS-B284	CS-FD-#13	7/29/2015	856.13	0 - 2 ft	180-46367-1	Excavated	12.55	< 0.036 U	< 0.044 U	< 0.061 U	< 0.045 U	9.3 J	2.7 J	0.55 J	< 0.066 U	< 0.036 U
Football Field	SSHS-B284	SSHS-B284-SUB-0-2	7/29/2015	856.13	0 - 2 ft	180-46367-1	Excavated	12.74	< 0.037 U	< 0.045 U	< 0.062 U	< 0.045 U	9.4 J	2.8 J	0.54 J	< 0.066 U	< 0.036 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	7/14/2015	856.00	0 - 2 ft	180-45961-1	Not Excavated	0.877	< 0.0038	< 0.0046	< 0.0064	< 0.0047	0.51	0.29	0.077	< 0.0069	< 0.0037
Northern Athletic Field	SSHS-B286	SSHS-B286-SUB-0-2	7/14/2015	856.40	0 - 2 ft	180-45961-1	Excavated	2.59	< 0.0038	< 0.0047	< 0.0065	< 0.0047	1.7	0.7	0.19	< 0.0069	< 0.0038
Northern Athletic Field	SSHS-B287	SSHS-B287-SUB-0-2	7/14/2015	856.16	0 - 2 ft	180-45961-1	Excavated	3.38	< 0.0038	< 0.0047	< 0.0065	< 0.0048	2.3	0.84	0.24	< 0.007	< 0.0038
Northern Athletic Field	SSHS-B288	SSHS-B288-SUB-0-2	7/24/2015	856.22	0 - 2 ft	180-46251-2	Excavated	1.81	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1 J	0.63 J	0.18 J	< 0.0066 U	< 0.0036 U
Northern Athletic Field	SSHS-B289	SSHS-B289-SUB-0-2	7/24/2015	856.37	0 - 2 ft	180-46251-2	Excavated	1.88	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	1 J	0.68 J	0.2 J	< 0.0066 U	< 0.0036 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B290	SSHS-B290-SUB-0-2	7/24/2015	856.36	0 - 2 ft	180-46251-2	Excavated	2.15	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	1.1 J	0.79 J	0.26 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B2900	DUP-01	11/6/2019	855.76	0.17 - 2 ft	180-98355-3	Excavated	10.4	< 0.066 U	< 0.072 U	< 0.05 U	< 0.03 U	6 J	3.1 J	1.3 J	< 0.072 U	< 0.027 U
Football Field	SSHS-B2900	SSHS-B2900-SUB-0.17-2	11/6/2019	855.76	0.17 - 2 ft	180-98355-2	Excavated	0.4	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	0.23 J	0.17 J	< 0.0059 UJ	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2901	DUP-02	11/6/2019	856.05	0.17 - 2 ft	180-98355-3	Excavated	0.94	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.51 J	0.32 J	0.11 J	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2901	SSHS-B2901-SUB-0.17-2	11/6/2019	856.05	0.17 - 2 ft	180-98355-2	Excavated	2.63	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	1.6 J	0.7 J	0.33 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2902	SSHS-B2902-SUB-0.17-2	11/6/2019	856.47	0.17 - 2 ft	180-98355-2	Excavated	1.95	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	1.4 J	0.55 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2903	SSHS-B2903-SUB-0.17-2	11/6/2019	856.79	0.17 - 2 ft	180-98355-2	Excavated	3.37	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	2.1 J	0.89 J	0.38 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2904	SSHS-B2904-SUB-0.17-2	11/6/2019	856.15	0.17 - 2 ft	180-98355-2	Excavated	1.28	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.81 J	0.33 J	0.14 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2905	SSHS-B2905-SUB-0.17-2	11/7/2019	856.07	0.17 - 2 ft	180-98520-1	Excavated	3.9	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	2.6 J	0.98 J	0.32 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2906	SSHS-B2906-SUB-0.17-2	11/6/2019	855.46	0.17 - 2 ft	180-98355-3	Excavated	0.42	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.42	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2907	SSHS-B2907-SUB-0.17-2	11/6/2019	855.77	0.17 - 2 ft	180-98355-3	Excavated	0.63	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.63	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2908	SSHS-B2908-SUB-0.17-2	11/4/2019	854.86	0.17 - 2 ft	180-98355-1	Excavated	0.368	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.22 J	0.1 J	0.048 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2910	SSHS-B2910-SUB-0.17-2	11/6/2019	856.07	0.17 - 2 ft	180-98355-2	Excavated	2.19	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	1.4 J	0.59 J	0.2 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2911	SSHS-B2911-SUB-0.17-2	11/6/2019	854.88	0.17 - 2 ft	180-98355-2	Excavated	3.09	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.8 J	0.85 J	0.44 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2912	DUP-04	11/5/2019	855.19	0.17 - 2 ft	180-98355-3	Excavated	16.5	< 0.063 U	< 0.069 U	< 0.047 U	< 0.029 U	8.3 J	6.3 J	1.9 J	< 0.069 U	< 0.026 U
Football Field	SSHS-B2912	SSHS-B2912-SUB-0.17-2	11/5/2019	855.19	0.17 - 2 ft	180-98355-1	Excavated	13.5	< 0.032 U	< 0.035 U	< 0.024 U	< 0.014 U	8 J	3.8 J	1.7 J	< 0.035 U	< 0.013 U
Football Field	SSHS-B2913	SSHS-B2913-SUB-0.17-2	11/6/2019	855.40	0.17 - 2 ft	180-98355-3	Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2914	SSHS-B2914-SUB-0.17-2	11/6/2019	855.30	0.17 - 2 ft	180-98355-2	Excavated	0.364	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.19 J	0.12 J	0.054 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B2953	DUP-13	11/5/2019	855.33	0.17 - 2 ft	180-98355-3	Excavated	3.32	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.9 J	1.1 J	0.32 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2953	SSHS-B2953-SUB-0.17-2	11/5/2019	855.33	0.17 - 2 ft	180-98355-1	Excavated	4.01	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	2.5 J	1.1 J	0.41 J	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B2954	SSHS-B2954-SUB-0.17-2	11/5/2019	854.86	0.17 - 2 ft	180-98355-1	Excavated	7.06	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	3.9 J	2.3 J	0.86 J	< 0.0071 U	< 0.0027 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated	14					14				
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	0.029	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	0.029	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 UJ	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	0.051	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.051	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	0.011	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.011 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	0.142	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.07 J	0.072 J	< 0.0054 UJ	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	0.136	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.013 J	0.065 J	0.058 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	0.045	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.045	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 UJ	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 UJ	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	0.204	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.12 J	0.084 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	0.027	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	0.014 J	0.013 J	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	0.061	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.039 J	0.022 J	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	0.14	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.14	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B303	SSHS-B303-SUB-0-1	8/5/2015	854.42	0 - 1 ft	180-46628-2	Excavated	0.096	< 0.0036 U	< 0.0044 U	< 0.006 U	< 0.0044 U	0.023 J	0.048 J	0.025 J	< 0.0064 U	< 0.0035 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	0.0079	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	0.0079 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	1.96	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.98 J	0.71 J	0.27 J	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	0.012	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.012 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	3.5	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	2.5 J	0.82 J	0.18 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B304	SSHS-B304-SUB-0-1	8/5/2015	855.55	0 - 1 ft	180-46628-2	Excavated	0.0066	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	< 0.0044 U	0.0066 J	< 0.0038 U	< 0.0065 U	< 0.0035 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	0.082	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.043 J	0.039 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	0.914	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.5 J	0.35 J	0.064 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	ND	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	0.69	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.26 J	0.32 J	0.11 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	0.239	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.091 J	0.11 J	0.038 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	0.019	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 UJ	0.019	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	0.044	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.024 J	0.02 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B305	SSHS-B305-SUB-0.17-2	7/14/2015	855.32	0.17 - 2 ft	180-45961-2	Excavated	0.0432	< 0.0038	< 0.0046	< 0.0064	< 0.0047	0.021	0.016	0.0062	< 0.0068	< 0.0037
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	0.082	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.047 J	0.035 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	1.85	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1 J	0.64 J	0.21 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	0.226	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.11 J	0.093 J	0.023 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	0.169	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	0.08 J	0.089 J	< 0.0057 UJ	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	2.23	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	1.2 J	0.84 J	0.19 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	0.07	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U		0.07 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	0.37	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.22 J	0.11 J	0.04 J	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	0.062	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.034 J	0.028 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B306	SSHS-B306-SUB-0-2	3/1/2016	856.22	0 - 2 ft	180-52611-1	Excavated	2.5	< 0.0085	< 0.013	< 0.0047	< 0.0069	1.4	0.8	0.3	< 0.0058	< 0.0035
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	0.049	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.026 J	0.023 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	0.064	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.033 J	0.019 J	0.012 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	0.025	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.015 J	0.01 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	0.024	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.012 J	0.012 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	0.015	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.015 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	0.093	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.038 J	0.039 J	0.016 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	0.126	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.045 J	0.047 J	0.034 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	0.126	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.04 J	0.051 J	0.035 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	2.36	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	1.2 J	0.88 J	0.28 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	0.02	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	0.02	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	1.15	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.41 J	0.54 J	0.2 J	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B308	SSHS-B308-SUB-0-2	3/2/2016	857.14	0 - 2 ft	180-52664-1	Excavated	1.327	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.92 J	0.35 J	0.057 J	< 0.0063 U	< 0.0038 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	0.045	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.015 J	0.016 J	0.014 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	0.01	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.01 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	0.675	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.29 J	0.29 J	0.095 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	1.08	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.48 J	0.48 J	0.12 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	0.018	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	0.018 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	0.015	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.0073 J	0.0077 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	0.437	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.28 J	0.13 J	0.027 J	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B309	SSHS-B309-SUB-0-2	3/2/2016	855.88	0 - 2 ft	180-52664-1	Excavated	0.141	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	0.1 J	0.041 J	< 0.0071 U	< 0.0065 U	< 0.0039 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	6.7	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	5.1 J	1.3 J	0.3 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	0.163	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.052 J	0.075 J	0.036 J	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	0.0351	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.0081 J	0.014 J	0.013 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	0.284	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.12 J	0.11 J	0.054 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B310	SSHS-B310-SUB-0-2	3/2/2016	854.81	0 - 2 ft	180-52664-1	Excavated	2.45	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	1.8 J	0.54 J	0.11 J	< 0.0058 U	< 0.0035 U
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	0.084	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.021 J	0.037 J	0.026 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	0.091	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.021 J	0.041 J	0.029 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	0.091	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.021 J	0.041 J	0.029 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	0.076	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.035 J	0.027 J	0.014 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	0.047	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.028 J	0.019 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	0.047	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.028 J	0.019 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	0.169	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.078 J	0.061 J	0.03 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	0.167	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.069 J	0.061 J	0.037 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	0.185	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.072 J	0.067 J	0.046 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	0.102	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.041 J	0.036 J	0.025 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	0.036	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.021 J	0.015 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	0.304	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.095 J	0.11 J	0.099 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	0.265	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.086 J	0.11 J	0.069 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B311	SSHS-B311-SUB-0-2	3/2/2016	854.93	0 - 2 ft	180-52664-1	Excavated	4.61	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	3.2 J	1.1 J	0.31 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	0.221	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.072 J	0.09 J	0.059 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	0.032	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.01 J	0.011 J	0.011 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	0.616	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.32 J	0.23 J	0.066 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B314	PS-FD-5	3/2/2016	856.85	0 - 2 ft	180-52664-1	Excavated	14.41	< 0.091 U	< 0.14 U	< 0.05 U	< 0.073 U	10 J	4 J	0.41 J	< 0.061 U	< 0.037 U
Football Field	SSHS-B314	SSHS-B314-SUB-0-2	3/2/2016	856.85	0 - 2 ft	180-52664-1	Excavated	15.15	< 0.091 U	< 0.14 U	< 0.05 U	< 0.074 U	10 J	4.8 J	0.35 J	< 0.062 U	< 0.037 U
Football Field	SSHS-B315	SSHS-B315-SUB-0.17-2	3/1/2016	855.19	0.17 - 2 ft	180-52611-1	Excavated	11.99	< 0.087 U,F1	< 0.14 U	< 0.047 U	< 0.07 U	8.2 J	3.2 J	0.59 J	< 0.059 U	< 0.035 U
Football Field	SSHS-B316	PS-FD-3	3/2/2016	856.16	0 - 2 ft	180-52664-1	Excavated	8.36	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	6 J	2 J	0.36 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B316	SSHS-B316-SUB-0-2	3/2/2016	856.16	0 - 2 ft	180-52664-1	Excavated	6.18	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	4.8 J	1.2 J	0.18 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B317	SSHS-B317-SUB-0-2	3/1/2016	856.52	0 - 2 ft	180-52611-1	Excavated	0.222	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	0.16	< 0.0076 U	0.062	< 0.0064 U	< 0.0038 U
Football Field	SSHS-B318	SSHS-B318-SUB-0-2	3/2/2016	856.20	0 - 2 ft	180-52664-1	Excavated	0.233	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.12 J	0.084 J	0.029 J	< 0.0063 U	< 0.0038 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	4.8	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	2.5 J	2.3 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	1.32	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.38 J	0.61 J	0.33 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B320	SSHS-B320-SUB-0-2	3/2/2016	856.57	0 - 2 ft	180-52664-1	Excavated	3.29	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	2 J	1.1 J	0.19 J	< 0.0064 U	< 0.0038 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	0.085	< 0.0078 U	< 0.0084 U	< 0.0058 U	< 0.0035 U	0.035 J	0.033 J	0.017 J	< 0.0084 U	< 0.0032 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	0.0076	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	0.0076 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	1.309	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.8 J	0.47 J	0.039 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	0.87	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.34 J	0.53 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3229	SSHS-B3229-SUB-0.17-2	12/20/2019	855.55	0.17 - 2 ft	180-100362-1	Excavated	0.357	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.2 J	0.11 J	0.047 J	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3230	SSHS-B3230-SUB-0.17-2	12/20/2019	855.45	0.17 - 2 ft	180-100362-1	Excavated	0.275	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.11 J	0.1 J	0.065 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3231	SSHS-B3231-SUB-0.17-2	12/20/2019	855.72	0.17 - 2 ft	180-100362-1	Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-0.17-2	12/20/2019	855.71	0.17 - 2 ft	180-100362-1	Excavated	2.95	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	1.6 J	0.97 J	0.38 J	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3234	SSHS-B3234-SUB-0.17-2	12/20/2019	855.92	0.17 - 2 ft	180-100362-1	Excavated	2.77	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.7 J	0.7 J	0.37 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-0.17-2	12/20/2019	856.44	0.17 - 2 ft	180-100362-1	Excavated	0.049	< 0.007 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.024 J	0.025 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-0.17-2	12/20/2019	856.32	0.17 - 2 ft	180-100362-1	Excavated	0.094	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.04 J	0.036 J	0.018 J	< 0.0079 U	< 0.003 U
Northern Athletic Field	SSHS-B3237	SSHS-B3237-SUB-0.17-2	12/20/2019	856.01	0.17 - 2 ft	180-100361-1	Excavated	1.023	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.7 J	0.28 J	0.043 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3238	SSHS-B3238-SUB-0.17-2	12/20/2019	855.23	0.17 - 2 ft	180-100361-1	Excavated	0.118	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	0.071 J	0.047 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3239	SSHS-B3239-SUB-0.17-2	12/20/2019	855.81	0.17 - 2 ft	180-100362-1	Excavated	1.38	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.71 J	0.55 J	0.12 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B324	PS-FD-2	3/1/2016	855.23	0.17 - 2 ft	180-52611-1	Excavated	7.32	< 0.0089 U	< 0.014 U	< 0.0048 U	< 0.0071 U	5.5 J	1.4 J	0.42 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B324	SSHS-B324-SUB-0.17-2	3/1/2016	855.23	0.17 - 2 ft	180-52611-1	Excavated	7.57	< 0.043 U	< 0.068 U	< 0.024 U	< 0.035 U	5.3 J	1.9 J	0.37 J	< 0.029 U	< 0.018 U
Northern Athletic Field	SSHS-B3240	SSHS-B3240-SUB-0.17-2	12/20/2019	856.04	0.17 - 2 ft	180-100362-1	Excavated	1.42	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.82 J	0.49 J	0.11 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3241	SSHS-B3241-SUB-0.17-2	12/19/2019	856.35	0.17 - 2 ft	180-100363-3	Excavated	0.452	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.3 J	0.12 J	0.032 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-0.17-2	12/19/2019	856.23	0.17 - 2 ft	180-100363-3	Excavated	1.46	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.94 J	0.38 J	0.14 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3247	SSHS-B-3247-SUB-0.17-2	12/19/2019	857.57	0.17 - 2 ft	180-100363-3	Excavated	1.249	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.89 J	0.32 J	0.039 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3248	SSHS-B3248-SUB-0.17-2	12/19/2019	857.19	0.17 - 2 ft	180-100363-2	Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0.17-2	12/19/2019	857.44	0.17 - 2 ft	180-100363-1	Excavated	6	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	2.9 J	3.1 J	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0.17-2	12/19/2019	858.02	0.17 - 2 ft	180-100363-1	Excavated	21.57	< 0.068 U	< 0.074 U	< 0.051 U	< 0.03 U	15 J	5.9 J	0.67 J	< 0.073 U	< 0.028 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0.17-2	12/19/2019	857.46	0.17 - 2 ft	180-100363-1	Excavated	1.96	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	1.1 J	0.86 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-0.17-2	12/19/2019	858.40	0.17 - 2 ft	180-100363-2	Excavated	0.027	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.01 J	0.017 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-0.17-2	12/19/2019	856.34	0.17 - 2 ft	180-100363-2	Excavated	0.112	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.05 J	0.062 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-0.17-2	12/19/2019	857.06	0.17 - 2 ft	180-100363-1	Excavated	0.6	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.16 J	0.44 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-0.17-2	12/19/2019	858.14	0.17 - 2 ft	180-100363-2	Excavated	0.83	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U		0.52 J	0.31 J	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3258	SSHS-B3258-SUB-0.17-2	12/18/2019	856.41	0.17 - 2 ft	180-100380-1	Excavated	0.071	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.031 J	0.022 J	0.018 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-0.17-2	12/19/2019	857.33	0.17 - 2 ft	180-100363-2	Excavated	0.3	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.11 J	0.19 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B326	SSHS-B326-SUB-0-2	3/2/2016	854.91	0 - 2 ft	180-52664-1	Excavated	20.11	< 0.089 U	< 0.14 U	< 0.049 U	< 0.072 U	13 J	6.5 J	0.61 J	< 0.061 U	< 0.036 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-0.17-2	1/22/2021	854.14	0.17 - 2 ft	1801163651	Excavated	0.217	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.097	0.12	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B327	SSHS-B327-SUB-0-2	3/3/2016	855.58	0 - 2 ft	180-52706-1	Excavated	1.95	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.99 J	0.78 J	0.18 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0.17-2	12/18/2019	855.88	0.17 - 2 ft	180-100380-1	Excavated	0.54	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.2 J	0.26 J	0.08 J	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0.17-2	12/18/2019	855.39	0.17 - 2 ft	180-100380-1	Excavated	2.72	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.003 U	1.6 J	0.89 J	0.23 J	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0.17-2	12/18/2019	856.00	0.17 - 2 ft	180-100380-1	Excavated	2.56	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.2 J	1 J	0.36 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0-0.17	12/18/2019	856.00	0.17 - 2 ft	180-100380-1	Excavated	1.12	< 0.0081 U	< 0.0089 U	< 0.0061 U	< 0.0037 U	0.33 J	0.59 J	0.2 J	< 0.0088 U	< 0.0034 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	0.17 - 2 ft	180-100380-2	Not Excavated	1.44	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.75 J	0.52 J	0.17 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B328	SSHS-B328-SUB-0-2	3/3/2016	855.04	0 - 2 ft	180-52706-1	Excavated	2.721	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.9 J	0.74 J	0.081 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3287	SSHS-B3287-SUB-0.17-2	12/17/2019	857.65	0.17 - 2 ft	180-100148-6	Excavated	0.121	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.073 J	0.029 J	0.019 J	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-0.17-2	12/17/2019	856.90	0.17 - 2 ft	180-100148-6	Excavated	0.555	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.42 J	0.11 J	0.025 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3289	SSHS-B3289-SUB-0.17-2	12/17/2019	857.03	0.17 - 2 ft	180-100148-6	Excavated	0.07	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.04 J	0.018 J	0.012 J	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B329	SSHS-B329-SUB-0-2	3/3/2016	855.91	0 - 2 ft	180-52706-1	Excavated	0.251	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.18 J	0.059 J	0.012 J	< 0.0053 U	< 0.0032 U
Northern Athletic Field	SSHS-B3290	SSHS-B3290-SUB-0.17-2	12/17/2019	857.23	0.17 - 2 ft	180-100148-6	Excavated	0.076	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	0.04 J	0.024 J	0.012 J	< 0.0073 U	< 0.0028 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-0.17-2	12/17/2019	857.15	0.17 - 2 ft	180-100148-5	Excavated	0.038	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.014 J	0.013 J	0.011 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-0.17-2	12/17/2019	856.87	0.17 - 2 ft	180-100148-4	Excavated	0.489	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.29	0.14	0.059	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-0.17-2	12/17/2019	857.20	0.17 - 2 ft	180-100148-5	Excavated	0.027	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.011 J	0.009 J	0.007 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-0.17-2	12/17/2019	857.10	0.17 - 2 ft	180-100148-4	Excavated	0.483	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.24	0.16	0.083	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-0.17-2	12/17/2019	856.38	0.17 - 2 ft	180-100148-3	Excavated	0.338	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.11 J	0.14 J	0.088 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated	0.147	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.06 J	0.051 J	0.036 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B331	SSHS-B331-SUB-0-2	3/3/2016	855.61	0 - 2 ft	180-52706-1	Excavated	1.489	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.91 J	0.48 J	0.099 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B332	SSHS-B332-SUB-0-2	3/3/2016	855.09	0 - 2 ft	180-52706-1	Excavated	0.626	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.4 J	0.18 J	0.046 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B333	SSHS-B333-SUB-0-2	3/3/2016	856.15	0 - 2 ft	180-52706-1	Excavated	2.22	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	1.3 J	0.75 J	0.17 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B334	SSHS-B334-SUB-0-2	3/3/2016	856.23	0 - 2 ft	180-52706-1	Excavated	0.784	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.54 J	0.2 J	0.044 J	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B335	SSHS-B335-SUB-0-2	3/3/2016	856.16	0 - 2 ft	180-52706-1	Excavated	3.53	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	2.3 J	1 J	0.23 J	< 0.0064 U	< 0.0038 U
Football Field	SSHS-B336	SSHS-B336-SUB-0-2	3/3/2016	856.00	0 - 2 ft	180-52706-1	Excavated	10.52	< 0.0096 U	< 0.015 U	< 0.0053 U	< 0.0078 U	6.1 J	3.7 J	0.72 J	< 0.0065 U	< 0.0039 U
Football Field	SSHS-B338	PS-FD-21	3/9/2016	855.82	0 - 2 ft	180-52876-1	Excavated	4.19	< 0.0092 U	< 0.014 U	< 0.005 U	< 0.0074 U	2.9 J	1.1 J	0.19 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B338	SSHS-B338-SUB-0-2	3/9/2016	855.82	0 - 2 ft	180-52876-1	Excavated	5.71	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	4 J	1.5 J	0.21 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B339	SSHS-B339-SUB-0-2	3/9/2016	856.05	0 - 2 ft	180-52876-1	Excavated	1.008	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.66 J	0.29 J	0.058 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B344	SSHS-B344-SUB-0-2	3/3/2016	855.69	0 - 2 ft	180-52706-1	Excavated	4.36	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0067 U	2.6 J	1.4 J	0.36 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B3456	DUP09	7/28/2020	855.34	0.17 - 2 ft	180-108872-2	Excavated	0.436	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.18 J	0.21 J	0.046 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3456	SSHS-B3456-SUB-0.17-2	7/28/2020	855.34	0.17 - 2 ft	180-108872-2	Excavated	0.78	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.19 J	0.59 J	< 0.0052 UJ	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3457	SSHS-B3457-SUB-0.17-2	7/28/2020	855.82	0.17 - 2 ft	180-108872-2	Excavated	0.425	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.23 J	0.16 J	0.035 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3458	SSHS-B3458-SUB-0.17-2	7/28/2020	856.14	0.17 - 2 ft	180-108872-2	Excavated	2.006	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.4 J	0.52 J	0.086 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	0.279	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.16 J	0.1 J	0.019 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3460	SSHS-B3460-SUB-0.17-2	7/28/2020	855.83	0.17 - 2 ft	180-108872-2	Excavated	79.6	< 0.29 U	< 0.32 U	< 0.22 U	< 0.13 U	59 J	18 J	2.6 J	< 0.32 U	< 0.12 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	0.25	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.15 J	0.1 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3462	DUP11	7/28/2020	855.77	0.17 - 2 ft	180-108872-2	Excavated	2.46	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.5 J	0.82 J	0.14 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3462	SSHS-B3462-SUB-0.17-2	7/28/2020	855.77	0.17 - 2 ft	180-108872-2	Excavated	3.58	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.3 J	1.1 J	0.18 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated	0.75	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.48 J	0.27 J		< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	0.8	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.5 J	0.3 J		< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3465	SSHS-B3465-SUB-0.17-2	7/28/2020	855.46	0.17 - 2 ft	180-108872-2	Excavated	5.12	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.5 J	1.4 J	0.22 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3466	SSHS-B3466-SUB-0.17-2	7/28/2020	855.76	0.17 - 2 ft	180-108872-2	Excavated	13.38	< 0.03 U	< 0.032 U	< 0.022 U	< 0.013 U	10 J	3.1 J	0.28 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B3467	SSHS-B3467-SUB-0.17-2	7/28/2020	855.68	0.17 - 2 ft	180-108872-2	Excavated	0.633	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.42 J	0.18 J	0.033 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3468	SSHS-B3468-SUB-0.17-2	7/28/2020	855.93	0.17 - 2 ft	180-108872-2	Excavated	0.146	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.091 J	0.044 J	0.011 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3469	SSHS-B3469-SUB-0.17-2	7/28/2020	855.50	0.17 - 2 ft	180-108872-2	Excavated	2.03	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.1 J	0.79 J	0.14 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3470	SSHS-B3470-SUB-0.17-2	7/28/2020	855.73	0.17 - 2 ft	180-108872-2	Excavated	11.89	< 0.058 U	< 0.063 U	< 0.044 U	< 0.026 U	8.3 J	3.1 J	0.49 J	< 0.063 U	< 0.024 U
Football Field	SSHS-B3470	DUP14	7/28/2020	855.73	0.17 - 2 ft	180-108872-2	Excavated	2.85	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2 J	0.74 J	0.11 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3471	SSHS-B3471-SUB-0.17-2	7/28/2020	856.03	0.17 - 2 ft	180-108872-2	Excavated	7.56	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	5 J	2.2 J	0.36 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	1.78	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.1 J	0.58 J	0.1 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	3.2	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.8 J	1.2 J	0.2 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	4.72	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	2.3 J	2.1 J	0.32 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	0.17 - 2 ft	180-108826-1	Not Excavated	0.031	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.016 J	0.015 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	0.15	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.075 J	0.055 J	0.02 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	0.17 - 2 ft	180-108826-1	Not Excavated	0.408	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.23 J	0.14 J	0.038 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	0.235	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.13 J	0.086 J	0.019 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3491	SSHS-B3491-SUB-0.17-2	7/28/2020	858.35	0.17 - 2 ft	180-108872-1	Excavated	0.388	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.28 J	0.098 J	0.01 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-0.17-2	1/26/2021	858.35	0.17 - 2 ft	180-116462-1	Excavated	0.016	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.016 J	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.021	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.013 J	0.008 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.0236	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.015 J	0.0086 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0.17-2	1/26/2021	858.43	0.17 - 2 ft	180-116462-1	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	0.017	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.017 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	0.059	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.012 J	0.027	0.02	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3500	SSHS-B3500-SUB-0.17-2	8/31/2020	856.02	0.17 - 2 ft	180-110264-1	Not Excavated	0.16	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.067 J	0.064 J	0.029 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3500A	SSHS-B3500-SUB-0.17-2	1/25/2021	855.38	0.17 - 2 ft	180-116404-1	Excavated	0.071	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.05 J	0.021 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3501	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	0.17 - 2 ft	180-110264-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3501A	SSHS-B3501-SUB-0.17-2	1/25/2021	855.77	0.17 - 2 ft	180-116404-1	Excavated	0.165	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.12 J	0.045 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-0.17-2	1/25/2021	855.86	0.17 - 2 ft	180-116404-1	Excavated	0.186	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.092 J	0.076 J	0.018 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3505	SSHS-B3505-SUB-0.17-2	8/31/2020	853.31	0.17 - 2 ft	180-110264-1	Excavated	37.7	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	26 J	10 J	1.7 J	< 0.067 U	< 0.025 U
Football Field	SSHS-B3506	SSHS-B3506-SUB-0.17-2	8/31/2020	856.17	0.17 - 2 ft	180-110264-1	Excavated	3.44	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	2.4 J	0.87 J	0.17 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3507	SSHS-B3507-SUB-0.17-2	8/31/2020	855.31	0.17 - 2 ft	180-110264-1	Excavated	0.724	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.42 J	0.25 J	0.054 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3508	SSHS-B3508-SUB-0.17-2	8/31/2020	856.03	0.17 - 2 ft	180-110264-1	Excavated	2.82	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.7 J	0.92 J	0.2 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3509	SSHS-B3509-SUB-0.17-2	8/31/2020	855.93	0.17 - 2 ft	180-110264-1	Excavated	1.09	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.56 J	0.42 J	0.11 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3510	SSHS-B3510-SUB-0.17-2	8/31/2020	855.32	0.17 - 2 ft	180-110264-1	Excavated	0.969	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.57 J	0.33 J	0.069 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3526	SSHS-B3526-SUB-0.17-2	9/3/2020	855.55	0.17 - 2 ft	180-110468-1	Excavated	0.233	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.088 J	0.1 J	0.045 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3527	SSHS-B3527-SUB-0.17-2	9/3/2020	855.96	0.17 - 2 ft	180-110468-1	Excavated	0.393	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.18 J	0.16 J	0.053 J	< 0.006 U	< 0.0023 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-0.17-2	1/20/2021	854.07	0.17 - 2 ft	1801162471	Excavated	0.3554	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.25	0.1	0.0054 JP	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3594	DUP-13	1/26/2021	858.38	0.17 - 2 ft	1801164621	Excavated	0.084	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.046	0.038	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	0.112	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.058	0.054	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	0.079	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.079	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B36	12 Sep 00B36 0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	0.38	< 0.035 U	< 0.035 U	< 0.035 U	< 0.035 U	0.28	< 0.035 U	0.1		
Northern Athletic Field	SSHS-B3603	SSHS-B3603-SUB-0.17-2	1/25/2021	855.89	0.17 - 2 ft	180-116404-1	Excavated	0.1	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.056 J	0.03 J	0.014 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3604	SSHS-B3604-SUB-0.17-2	1/25/2021	855.40	0.17 - 2 ft	180-116404-1	Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3605	SSHS-B3605-SUB-0.17-2	1/25/2021	855.99	0.17 - 2 ft	180-116404-1	Excavated	0.048	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.031 J	0.017 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3606	SSHS-B3606-SUB-0.17-2	1/25/2021	855.37	0.17 - 2 ft	180-116404-1	Excavated	0.108	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.059 J	0.049 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3607	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	0.17 - 2 ft	180-116404-1	Not Excavated	0.166	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.074 J	0.073 J	0.019 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3608	SSHS-B3608-SUB-0.17-2	1/25/2021	856.10	0.17 - 2 ft	180-116404-1	Excavated	0.0195	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.0099 J	0.0096 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3609	SSHS-B3609-SUB-0.17-2	1/25/2021	855.67	0.17 - 2 ft	180-116404-1	Excavated	0.116	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.05 J	0.066 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3610	SSHS-B3610-SUB-0.17-2	1/25/2021	856.08	0.17 - 2 ft	180-116404-1	Excavated	0.0536	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.024 J	0.021 J	0.0086 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3611	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	0.17 - 2 ft	180-116404-1	Not Excavated	0.42	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.2 J	0.22 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3612	SSHS-B3612-SUB-0.17-2	1/25/2021	856.56	0.17 - 2 ft	180-116404-1	Excavated	0.037	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.022 J	0.015 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3617	SSHS-B3617-SUB-0.17-2	1/25/2021	856.07	0.17 - 2 ft	180-116404-1	Excavated	0.284	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.13 J	0.12 J	0.034 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3618	SSHS-B3618-SUB-0.17-2	1/25/2021	856.15	0.17 - 2 ft	180-116404-1	Excavated	15.9	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	10 J	5.9 J	< 0.055 U	< 0.068 U	< 0.026 U
Northern Athletic Field	SSHS-B3619	SSHS-B3619-SUB-0.17-2	1/25/2021	856.42	0.17 - 2 ft	180-116404-1	Excavated	0.582	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.26 J	0.29 J	0.032 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-0.17-2	1/25/2021	856.26	0.17 - 2 ft	180-116404-1	Excavated	0.117	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.053 J	0.064 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3621	SSHS-B3621-SUB-0.17-2	1/25/2021	856.33	0.17 - 2 ft	180-116404-1	Excavated	0.127	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.033 J	0.075 J	0.019 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3622	SSHS-B3622-SUB-0.17-2	1/25/2021	856.17	0.17 - 2 ft	180-116404-1	Excavated	24.06	< 0.032 U	< 0.035 U	< 0.024 U	< 0.014 U	19 J	4.8 J	0.26 J	< 0.035 U	< 0.013 U
Northern Athletic Field	SSHS-B3623	SSHS-B3623-SUB-0.17-2	1/23/2021	855.47	0.17 - 2 ft	180-116404-1	Excavated	1.44	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.64 J	0.69 J	0.11 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3624	SSHS-B3624-SUB-0.17-2	1/23/2021	855.26	0.17 - 2 ft	180-116404-1	Excavated	0.41	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.16 J	0.25 J		< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	0.287	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.15	0.11	0.027	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3648	SSHS-B3648-SUB-0.17-2	1/29/2021	856.51	0.17 - 2 ft	180-116665-1	Excavated	1.18	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.75 J	0.35 J	0.08 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3649	SSHS-B3649-SUB-0.17-2	1/29/2021	856.47	0.17 - 2 ft	180-116665-1	Excavated	0.2252	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.14 J	0.076 J	0.0092 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B37	12 Sep 00B37 0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	ND	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-0-2	3/8/2016	852.79	0 - 2 ft	180-52813-1	Excavated	71.4	< 0.081 U	< 0.13 U	< 0.044 U	< 0.065 U	56 J	13 J	2.4 J	< 0.055 U	< 0.033 U
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-0-2	3/8/2016	852.92	0 - 2 ft	180-52813-1	Excavated	25.5	< 0.081 U	< 0.13 U	< 0.044 U	< 0.065 U	20 J	4.4 J	1.1 J	< 0.055 U	< 0.033 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-0-2	3/10/2016	852.41	0 - 2 ft	180-52921-1	Excavated	0.013	< 0.0077 U	< 0.012 U	< 0.0042 U	< 0.0062 U	0.013 J	< 0.0062 U	< 0.0058 U	< 0.0052 U	< 0.0031 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	ND	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	0.87	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.74	< 0.037 U	0.13		
Rear Parking Lot	SSHS-B380	SSHS-B380-SUB-0-2	3/7/2016	853.88	0 - 2 ft	180-52771-1	Excavated	1.421	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	0.88 J	0.47 J	0.071 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B381	PS-FD-22	3/9/2016	852.40	0 - 2 ft	180-52876-1	Not Excavated	0.124	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.081 J	0.034 J	0.009 J	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B381	SSHS-B381-SUB-0-2	3/9/2016	852.40	0 - 2 ft	180-52876-1	Not Excavated	0.428	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.28 J	0.12 J	0.028 J	< 0.0054 U	< 0.0033 U
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-0-2	3/9/2016	850.28	0 - 2 ft	180-52876-1	Not Excavated	0.0204	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	0.0094 J	0.011 J	< 0.0068 U	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	0.17 - 2 ft	180-124920-1	Not Excavated	5.58	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.1 J	2.1 J	0.38 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	0.026	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-0-2	3/8/2016	852.82	0 - 2 ft	180-52813-1	Excavated	3.4	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	2.2 J	1 J	0.2 J	< 0.0054 U	< 0.0033 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	ND	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U		
Northern Athletic Field	SSHS-B39	12 Sep 00B39 0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	0.173	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.12	0.053	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	0.232	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.15	0.071	0.011 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-0.17-2	5/12/2021	854.82	0.17 - 2 ft	180-121548-2	Excavated	0.549	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.38 J	0.13 J	0.039 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B397	082616 09:00 PS-FD-10	8/25/2016	856.15	0 - 2 ft	180-57995-1	Excavated	1.26	< 0.0084	< 0.013	< 0.0046	< 0.0068	0.57	0.5	0.19	< 0.0057	< 0.0034
Northern Athletic Field	SSHS-B397	SSHS-B397-SUB-0-2	8/25/2016	856.15	0 - 2 ft	180-57995-1	Excavated	1.08	< 0.0086	< 0.014	< 0.0047	< 0.0069	0.49	0.43	0.16	< 0.0058	< 0.0035
Northern Athletic Field	SSHS-B398	SSHS-B398-SUB-0-2	8/25/2016	856.20	0 - 2 ft	180-57995-1	Excavated	0.92	< 0.0089	< 0.014	< 0.0049	< 0.0072	0.47	0.32	0.13	< 0.006	< 0.0036
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	0.415	< 0.0084	< 0.013	< 0.0046	< 0.0068	0.21	0.15	0.055	< 0.0057	< 0.0034
EHS Building	SSHS-B3S	B3-C1-Composite	7/25/2007	855.70	0.5 - 2 ft	NA	Not Excavated	32	< U	< U	< U	< U	32	< U	< U		
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated	14					14				
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	0.16	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	0.16	< 0.041 U	< 0.041 U		
Northern Athletic Field	SSHS-B40	12 Sep 00B40 0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	1.31	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	1.2	< 0.037 U	0.11		
Northern Athletic Field	SSHS-B400	SSHS-B400-SUB-0-2	8/25/2016	856.16	0 - 2 ft	180-57995-1	Excavated	0.58	< 0.0085	< 0.013	< 0.0047	< 0.0069	0.28	0.21	0.09	< 0.0058	< 0.0035
Northern Athletic Field	SSHS-B401	SSHS-B401-SUB-0-2	8/25/2016	856.35	0 - 2 ft	180-57995-1	Excavated	0.466	< 0.0084	< 0.013	< 0.0046	< 0.0067	0.21	0.18	0.076	< 0.0057	< 0.0034
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	0.046	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.028	0.018 J	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	0.301	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.16	0.12	0.021	< 0.0067 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	0.168	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.034 U	0.059 J	0.082 J	0.027 J	< 0.0057 U	< 0.0035 U
Tennis Courts / Main Parking Lot	SSHS-B403	SSHS-B403-SUB-0-2	8/30/2016	856.22	0 - 2 ft	180-58129-1	Excavated	1.01	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.034 U	0.54 J	0.37 J	0.1 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B407	SSHS-B407-SUB-0-2	8/25/2016	857.28	0 - 2 ft	180-57995-1	Excavated	0.012	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.012 J	< 0.0073 U	< 0.0067 U	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B408	SSHS-B408-SUB-0-2	8/25/2016	857.31	0 - 2 ft	180-57995-1	Excavated	7.91	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.034 U	5.5 J	2.3 J	0.11 J	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B409	SSHS-B409-SUB-0-2	8/25/2016	857.14	0 - 2 ft	180-57995-1	Excavated	0.756	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.43 J	0.26 J	0.066 J	< 0.0061 U	< 0.0037 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B40-A	SSHS-B40-A-SUB-0-2	7/14/2015	856.85	0 - 2 ft	180-45961-1	Excavated	0.97	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.45 J	0.38 J	0.14 J	< 0.0069 U	< 0.0037 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	0.073	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.034 U	0.046 J	0.027 J	< 0.0068 U	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B411	SSHS-B411-SUB-0-2	8/22/2016	856.36	0 - 2 ft	180-57858-1	Excavated	2.62	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.034 U	1.4 J	0.95 J	0.27 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B412	SSHS-B412-SUB-0-2	8/25/2016	856.86	0 - 2 ft	180-57995-1	Excavated	0.31	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.034 U	0.2 J	0.11 J	< 0.0069 U	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B413	SSHS-B413-SUB-0-2	8/26/2016	856.37	0 - 2 ft	180-58029-1	Excavated	1.202	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.034 U	0.83 J	0.3 J	0.072 J	< 0.0056 U	< 0.0033 U
Football Field	SSHS-B414	SSHS-B414-SUB-0-2	8/22/2016	856.26	0 - 2 ft	180-57858-1	Excavated	2.6	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.034 U	1.6 J	0.86 J	0.14 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B415	SSHS-B415-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	6.5	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.034 U	4.1 J	2 J	0.4 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B416	SSHS-B416-SUB-0-2	8/22/2016	855.45	0 - 2 ft	180-57858-1	Excavated	9.4	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	5.7 J	3.2 J	0.5 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-0.17-2	9/23/2021	856.00	0.17 - 2 ft	180-127595-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	0.034	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	0.011 J	0.023 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B417	SSHS-B417-SUB-0-2	8/22/2016	854.89	0 - 2 ft	180-57858-1	Excavated	36.6	< 0.045 U	< 0.071 U	< 0.024 U	< 0.034 U	25 J	8.9 J	2.7 J	< 0.03 U	< 0.018 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B418	SSHS-B418-SUB-0-2	8/23/2016	855.15	0 - 2 ft	180-57888-1	Excavated	20.6	< 0.043 U	< 0.067 U	< 0.023 U	< 0.034 U	12 J	7.2 J	1.4 J	< 0.029 U	< 0.017 U
Football Field	SSHS-B419	SSHS-B419-SUB-0-2	8/23/2016	855.07	0 - 2 ft	180-57888-1	Excavated	2.72	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	1.5 J	0.97 J	0.25 J	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	0.056	< 0.999	< 0.999	< 0.999	< 0.999	0.056	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B420	SSHS-B420-SUB-0-2	8/23/2016	855.20	0 - 2 ft	180-57888-1	Excavated	3.82	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	2.2 J	1.3 J	0.32 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B421	SSHS-B421-SUB-0-2	8/23/2016	854.90	0 - 2 ft	180-57888-1	Excavated	0.85	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.34 J	0.4 J	0.11 J	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B422	SSHS-B422-SUB-0-2	8/23/2016	855.04	0 - 2 ft	180-57888-1	Excavated	7.69	< 0.04 U	< 0.063 U	< 0.022 U	< 0.032 U	3.9 J	3.3 J	0.49 J	< 0.027 U	< 0.016 U
Football Field	SSHS-B423	SSHS-B423-SUB-0-2	8/22/2016	855.10	0 - 2 ft	180-57858-1	Excavated	10.1	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	4.9 J	4.1 J	1.1 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	0.591	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.034 U	0.35 J	0.19 J	0.051 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B425	SSHS-B425-SUB-0-2	8/22/2016	855.58	0 - 2 ft	180-57858-1	Excavated	1.097	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.64 J	0.37 J	0.087 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B426	SSHS-B426-SUB-0-2	8/23/2016	855.71	0 - 2 ft	180-57888-1	Excavated	0.26	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.15 J	0.11 J	< 0.0063 U	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B427	PS-FD-5	8/23/2016	855.43	0 - 2 ft	180-57888-1	Excavated	12.45	< 0.041 U	< 0.064 U	< 0.022 U	< 0.033 U	8.6 J	3.2 J	0.65 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B427	SSHS-B427-SUB-0-2	8/23/2016	855.43	0 - 2 ft	180-57888-1	Excavated	11.67	< 0.041 U	< 0.065 U	< 0.023 U	< 0.033 U	7.7 J	3.5 J	0.47 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B428	SSHS-B428-SUB-0.17-2	8/26/2016	855.50	0.17 - 2 ft	180-58029-1	Excavated	8.84	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.034 U	4.8 J	3.1 J	0.94 J	< 0.0057 U	< 0.0035 U
Football Field	SSHS-B429	SSHS-B429-SUB-0.17-2	8/26/2016	854.95	0.17 - 2 ft	180-58029-1	Excavated	9	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.034 U	6.2 J	2.3 J	0.5 J	< 0.0061 U	< 0.0036 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	0.39	< 0.999	< 0.999	< 0.999	< 0.999	0.39	< 0.999	< 0.999		
Football Field	SSHS-B430	PS-FD-9	8/25/2016	855.35	0 - 2 ft	180-57995-1	Excavated	0.172	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.034 U	0.063 J	0.09 J	0.019 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B430	SSHS-B430-SUB-0-2	8/25/2016	855.35	0 - 2 ft	180-57995-1	Excavated	0.11	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.034 U	0.042 J	0.068 J	< 0.007 U	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B438	SSHS-B438-SUB-0-2	8/26/2016	854.99	0 - 2 ft	180-58029-3	Excavated	8.18	< 0.034 U	< 0.13 U	< 0.046 U	< 0.034 U	5.2 J	2.6 J	0.38 J	< 0.057 U	< 0.034 U
Football Field	SSHS-B439	SSHS-B439-SUB-0-2	8/26/2016	855.06	0 - 2 ft	180-58029-3	Excavated	134.2	< 0.41 U	< 0.65 U	< 0.23 U	< 0.33 U	88 J	42 J	4.2 J	< 0.28 U	< 0.17 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B440	SSHS-B440-SUB-0-2	8/26/2016	855.30	0 - 2 ft	180-58029-1	Excavated	53.9	< 0.17 UJ	< 0.26 U	< 0.092 U	< 0.13 U	38 J	14 J	1.9 J	< 0.11 U	< 0.068 U
Football Field	SSHS-B441	SSHS-B441-SUB-0-2	8/24/2016	854.89	0 - 2 ft	180-57932-1	Excavated	0.91	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.7 J	0.21 J	< 0.007 U	< 0.0063 U	< 0.0038 U
Football Field	SSHS-B442	SSHS-B442-SUB-0-2	8/24/2016	855.06	0 - 2 ft	180-57932-1	Excavated	2.55	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.7 J	0.69 J	0.16 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B443	SSHS-B443-SUB-0-2	9/14/2016	855.30	0 - 2 ft	180-58722-1	Excavated	5.01	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	3.5 J	1.3 J	0.21 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B444	SSHS-B444-SUB-0-2	8/26/2016	855.07	0 - 2 ft	180-58029-1	Excavated	6.63	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0066 U	4.4 J	1.8 J	0.43 J	< 0.0055 U	< 0.0033 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B451	SSHS-B451-SUB-0-2	9/27/2016	854.61	0 - 2 ft	180-59163-1	Excavated	0.93	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	0.56 J	0.37 J	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B452	SSHS-B452-SUB-0-2	9/27/2016	854.99	0 - 2 ft	180-59163-1	Excavated	0.072	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	0.058 J	0.014 J	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B453	SSHS-B453-SUB-0-2	8/24/2016	855.65	0 - 2 ft	180-57932-1	Excavated	2.74	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	1.6 J	1 J	0.14 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B454	SSHS-B454-SUB-0-2	8/24/2016	855.00	0 - 2 ft	180-57932-1	Excavated	3.63	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	2.4 J	1 J	0.23 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B455	SSHS-B455-SUB-0-2	8/30/2016	855.84	0 - 2 ft	180-58129-1	Excavated	ND	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	< 0.0064 U	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B456	SSHS-B456-SUB-0-2	8/30/2016	855.99	0 - 2 ft	180-58129-1	Excavated	ND	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	< 0.0065 U	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B457	SSHS-B457-SUB-0-2	8/30/2016	855.74	0 - 2 ft	180-58129-1	Not Excavated	0.038	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.022 J	0.016 J	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B458	SSHS-B458-SUB-0-2	8/24/2016	856.14	0 - 2 ft	180-57932-1	Excavated	2.64	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	1.6 J	0.92 J	0.12 J	< 0.0057 U	< 0.0034 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	1.83	< 0.999	< 0.999	< 0.999	< 0.999	1.7	< 0.999	0.13		
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	0.32	< 0.999	< 0.999	< 0.999	< 0.999	0.32	< 0.999	< 0.999		
Football Field	SSHS-B460	SSHS-B460-SUB-0-2	8/31/2016	855.48	0 - 2 ft	180-58236-1	Excavated	13.81	< 0.041 U	< 0.065 U	< 0.023 U	< 0.033 U	10 J	3.1 J	0.71 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B461	SSHS-B461-SUB-0-2	8/31/2016	855.42	0 - 2 ft	180-58236-1	Excavated	10.9	< 0.04 U	< 0.064 U	< 0.022 U	< 0.033 U	8 J	2.4 J	0.5 J	< 0.027 U	< 0.016 U
Football Field	SSHS-B462	SSHS-B462-SUB-0-2	8/31/2016	855.34	0 - 2 ft	180-58236-1	Excavated	6.75	< 0.0089 U	< 0.014 U	< 0.0048 U	< 0.0071 U	5 J	1.5 J	0.25 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B463	SSHS-B463-SUB-0-2	8/31/2016	854.92	0 - 2 ft	180-58236-1	Excavated	6.7	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	4.8 J	1.6 J	0.3 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B464	SSHS-B464-SUB-0-2	8/29/2016	856.94	0 - 2 ft	180-58133-1	Excavated	0.047	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.027 J	0.02 J	< 0.0065 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B466	SSHS-B466-SUB-0-2	8/29/2016	856.03	0 - 2 ft	180-58133-1	Excavated	54.1	< 0.17 U	< 0.26 U	< 0.092 U	< 0.14 U	37 J	16 J	1.1 J	< 0.11 U	< 0.068 U
Football Field	SSHS-B467	SSHS-B467-SUB-0-2	8/29/2016	856.10	0 - 2 ft	180-58133-1	Excavated	2279	< 4.3 U	< 6.7 U	< 2.3 U	< 3.4 U	1600 J	630 J	49 J	< 2.9 U	< 1.7 U
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B473	SSHS-B473-SUB-0-2	8/30/2016	856.07	0 - 2 ft	180-58129-1	Excavated	0.424	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.3 J	0.11 J	0.014 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B477	SSHS-B477-SUB-0-2	8/29/2016	856.06	0 - 2 ft	180-58133-1	Excavated	0.529	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.3 J	0.2 J	0.029 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B479	SSHS-B479-SUB-0-2	8/29/2016	856.39	0 - 2 ft	180-58133-1	Excavated	3.01	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1.9 J	1 J	0.11 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B494	SSHS-B494-SUB-0-2	8/23/2016	854.88	0 - 2 ft	180-57888-1	Excavated	7.7	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	5.1 J	2.2 J	0.4 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B495	SSHS-B495-SUB-0-2	8/23/2016	855.25	0 - 2 ft	180-57888-1	Excavated	2.97	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	2 J	0.83 J	0.14 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B496	PS-FD-3	8/23/2016	855.35	0 - 2 ft	180-57888-1	Excavated	3.09	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1.9 J	1 J	0.19 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B496	SSHS-B496-SUB-0-2	8/23/2016	855.35	0 - 2 ft	180-57888-1	Excavated	3.76	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	2.2 J	1.3 J	0.26 J	< 0.0056 U	< 0.0034 U
EHS Building	SSHS-B4S	B4-C1-Composite	7/25/2007	-	0.5 - 2 ft	-	Not Excavated	3.5	< U	< U	< U	< U	3.5	< U	< U		
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated	3.5					3.5				
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_ -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	0.15	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	0.15	< 0.042 U	< 0.042 U		
Northern Athletic Field	SSHS-B50	13 Sep 00B50_0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B51	13 Sep 00B51_ -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B51	13 Sep 00B51_0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52_ -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	ND	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52_0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Rear Parking Lot	SSHS-B523	SSHS-B523-SUB-0-2	9/23/2016	854.05	0 - 2 ft	180-59040-1	Excavated	0.085	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	0.052 J	0.022 J	0.011 J	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B525	SSHS-B525-SUB-0-2	9/16/2016	853.93	0 - 2 ft	180-58783-1	Excavated	0.0355	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	0.027 J	0.0085 J	< 0.0059 U	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B526	SSHS-B526-SUB-0-2	9/16/2016	853.95	0 - 2 ft	180-58783-1	Excavated	4.82	< 0.0079 U	< 0.013 U	< 0.0043 U	< 0.0064 U	3.6 J	0.97 J	0.25 J	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B527	SSHS-B527-SUB-0-2	9/16/2016	853.71	0 - 2 ft	180-58783-1	Excavated	49.2	< 0.41 U	< 0.65 U	< 0.22 U	< 0.33 U	36 J	11 J	2.2 J	< 0.28 U	< 0.17 U
Rear Parking Lot	SSHS-B528	SSHS-B528-SUB-0-2	9/16/2016	853.01	0 - 2 ft	180-58783-1	Excavated	10.95	< 0.08 U	< 0.13 U	< 0.044 U	< 0.065 U	8 J	2.5 J	0.45 J	< 0.054 U	< 0.033 U
Rear Parking Lot	SSHS-B528	PS-FD-27	9/16/2016	853.01	0 - 2 ft	180-58783-1	Excavated	6.42	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	4.6 J	1.5 J	0.32 J	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B529	SSHS-B529-SUB-0-2	9/16/2016	852.61	0 - 2 ft	180-58783-1	Excavated	5.44	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	4 J	1.2 J	0.24 J	< 0.0055 U	< 0.0033 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53_ -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	ND	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U		
Northern Athletic Field	SSHS-B53	13 Sep 00B53_0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Rear Parking Lot	SSHS-B531	PS-FD-28	9/16/2016	852.31	0 - 2 ft	180-58783-1	Not Excavated	0.269	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.17 J	0.076 J	0.023 J	< 0.0053 U	< 0.0032 U
Rear Parking Lot	SSHS-B531	SSHS-B531-SUB-0-2	9/16/2016	852.31	0 - 2 ft	180-58783-1	Not Excavated	0.234	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.15 J	0.065 J	0.019 J	< 0.0054 U	< 0.0033 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54_ -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	ND	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U		
Northern Athletic Field	SSHS-B54	13 Sep 00B54_0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	ND	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U		
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated	ND	< U	< U	< U	< U	< U	< U	< U		
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated	ND	< U	< U	< U	< U	< U	< U	< U		
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated	0.078							0.078		
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated	0.053							0.053		
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	ND	< 0.0082	< 0.013	< 0.0045	< 0.0066	< 0.0042	< 0.0066	< 0.0061	< 0.0055	< 0.0033
Football Field	SSHS-B576	SSHS-B576-SUB-0.17-2	2/15/2017	855.75	0.17 - 2 ft	180-63517-1	Excavated	0.253	< 0.011 U	< 0.011 U	< 0.008 U	< 0.016 U	0.11 J	0.089 J	0.054 J	< 0.015 U	< 0.0062 U
Northern Athletic Field	SSHS-B577	SSHS-B577-SUB-0.17-2	2/10/2017	856.11	0.17 - 2 ft	180-63389-1	Excavated	3.86	< 0.01	< 0.0098	< 0.0075	< 0.015	2.3	0.96	0.6	< 0.014	< 0.0058
Northern Athletic Field	SSHS-B577	021117 09:30_DUP-2	2/10/2017	856.11	0.17 - 2 ft	180-63389-1	Excavated	0.436	< 0.0096	< 0.0093	< 0.0071	< 0.014	0.26	0.12	0.056	< 0.013	< 0.0055
Tennis Courts / Main Parking Lot	SSHS-B578	SSHS-B578-SUB-0-2	2/15/2017	857.45	0 - 2 ft	180-63517-1	Excavated	1.62	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.68 J	0.67 J	0.27 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B578	PS-FD-20	2/15/2017	857.45	0 - 2 ft	180-63517-1	Excavated	2.54	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.6 J	1.5 J	0.44 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B579	SSHS-B579-SUB-0-2	2/15/2017	856.16	0 - 2 ft	180-63517-1	Excavated	2.22	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	1.1 J	0.87 J	0.25 J	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-0.17-2	2/10/2017	855.97	0.17 - 2 ft	180-63389-1	Excavated	1.36	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.84	0.37	0.15	< 0.013	< 0.0056
Tennis Courts / Main Parking Lot	SSHS-B587	PS-FD-21	2/15/2017	856.06	0 - 2 ft	180-63517-1	Not Excavated	0.068	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.04 J	0.028 J	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B587	SSHS-B587-SUB-0-2	2/15/2017	856.06	0 - 2 ft	180-63517-1	Not Excavated	0.104	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.063 J	0.041 J	< 0.012 U	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	ND	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U	< 0.999 U		
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-0-2	2/15/2017	856.06	0 - 2 ft	180-63517-1	Not Excavated	0.292	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.15 J	0.11 J	0.032 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B591	SSHS-B591-SUB-0-2	2/15/2017	856.21	0 - 2 ft	180-63517-1	Not Excavated	0.018	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0086 U	0.018	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B592	SSHS-B592-SUB-0-2	2/15/2017	856.38	0 - 2 ft	180-63517-1	Not Excavated	0.53	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.19 J	0.2 J	0.14 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B593	SSHS-B593-SUB-0-2	2/15/2017	856.22	0 - 2 ft	180-63517-1	Not Excavated	0.223	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.045 J	0.12 J	0.058 J	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B594	PS-FD-22	2/15/2017	856.17	0 - 2 ft	180-63517-1	Excavated	2.52	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	1.4 J	0.87 J	0.25 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B594	SSHS-B594-SUB-0-2	2/15/2017	856.17	0 - 2 ft	180-63517-1	Excavated	1.74	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	1 J	0.58 J	0.16 J	< 0.014 U	< 0.0061 U
Tennis Courts / Main Parking Lot	SSHS-B595	PS-FD-8	2/10/2017	856.24	0.17 - 2 ft	180-63389-1	Not Excavated	0.081	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.037 J	0.028 J	0.016 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B595	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	0.17 - 2 ft	180-63389-1	Not Excavated	0.063	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.037 J	0.026 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B596	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	0.17 - 2 ft	180-63389-1	Not Excavated	0.327	< 0.011 U	< 0.011 U	< 0.008 U	< 0.016 U	0.2 J	0.093 J	0.034 J	< 0.015 U	< 0.0062 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated	14					14				
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Football Field	SSHS-B619	SSHS-B619-SUB-0-2	2/14/2017	855.58	0 - 2 ft	180-63507-1	Excavated	3.36	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	2.3 J	0.89 J	0.17 J	< 0.013 U	< 0.0055 U

DRAFT

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B620	SSHS-B620-SUB-0-2	2/13/2017	855.29	0 - 2 ft	180-63507-1	Excavated	5.46	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	3.7 J	1.4 J	0.36 J	< 0.014 U	< 0.0061 U
Football Field	SSHS-B624	SSHS-B624-SUB-0.17-2	2/9/2017	855.38	0.17 - 2 ft	180-63367-1	Excavated	5.25	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	3.4 J	1.5 J	0.35 J	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B632C	SSHS-B632C-SUB-0-2	7/13/2017	855.37	0 - 2 ft	180-68203-1	Excavated	0.016	< 0.01 U	< 0.0097 U	< 0.0075 U	< 0.015 U	0.016 J	< 0.0083 U	< 0.013 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-0-2	2/10/2017	855.22	0 - 2 ft	180-63389-1	Excavated	0.0267	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.019 J	0.0077 J	< 0.012 U	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B636	PS-FD-10	2/13/2017	855.28	0 - 2 ft	180-63507-1	Not Excavated	0.05	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.013 U	0.031 J	0.019 J	< 0.011 U	< 0.012 U	< 0.0051 U
Tennis Courts / Main Parking Lot	SSHS-B636	SSHS-B636-SUB-0-2	2/13/2017	855.28	0 - 2 ft	180-63507-1	Not Excavated	0.038	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.013 U	0.024 J	0.014 J	< 0.011 U	< 0.012 U	< 0.0052 U
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	2	< 0.0026 U	< 0.0033 U	< 0.003 U	< 0.0029 U	1.9	< 0.0025 U	0.1	< 0.0038 U	< 0.0023 U
Football Field	SSHS-B647	SSHS-B647-SUB-0-2	2/16/2017	856.87	0 - 2 ft	180-63593-1	Excavated	0.042	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.028 J	0.014 J	< 0.013 U	< 0.014 U	< 0.0059 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	10.5	< 0.026 U	< 0.033 U	< 0.03 U	< 0.028 U	10	< 0.025 U	0.5	< 0.038 U	< 0.022 U
Football Field	SSHS-B650	SSHS-B650-SUB-0-2	2/14/2017	855.56	0 - 2 ft	180-63507-1	Excavated	16.52	< 0.097 U	< 0.095 U	< 0.073 U	< 0.15 U	12 J	3.9 J	0.62 J	< 0.13 U	< 0.056 U
Football Field	SSHS-B651	SSHS-651-SUB-0-2	2/14/2017	855.56	0 - 2 ft	180-63507-1	Excavated	2.14	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.5 J	0.54 J	0.1 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B652	SSHS-B652-SUB-0-2	2/14/2017	855.55	0 - 2 ft	180-63507-1	Excavated	25.69	< 0.094 U	< 0.092 U	< 0.07 U	< 0.14 U	20 J	4.8 J	0.89 J	< 0.13 U	< 0.054 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	25.1	< 0.051 U	< 0.066 U	< 0.059 U	< 0.056 U	24	< 0.049 U	1.1	< 0.075 U	< 0.044 U
Northern Athletic Field	SSHS-B664	SSHS-B664-SUB-0-2	2/15/2017	856.32	0 - 2 ft	180-63517-1	Excavated	3.76	< 0.0098	< 0.0096	< 0.0073	< 0.015	2.3	1.1	0.36	< 0.013	< 0.0056
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	272	< 0.54 U	< 0.69 U	< 0.62 U	< 0.59 U	260	< 0.52 U	12	< 0.8 U	< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B674	032217 08:50_SSHS-B674-SUB-0-2	3/21/2017	856.28	0 - 2 ft	180-64494-1	Excavated	1.05	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.69	0.25	0.11	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B675	032217 08:50_SSHS-B675-SUB-0-2	3/21/2017	857.36	0 - 2 ft	180-64494-1	Excavated	0.137	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.071	0.041	0.025	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B676	032217 08:50_SSHS-B676-SUB-0-2	3/21/2017	856.94	0 - 2 ft	180-64494-1	Excavated	0.168	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.1	0.043	0.025	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B677	032217 08:50_PS-FD-3	3/21/2017	856.08	0 - 2 ft	180-64494-2	Excavated	2.16	< 0.0098	< 0.0095	< 0.0073	< 0.015	1.5	0.47	0.19	< 0.013	< 0.0056
Northern Athletic Field	SSHS-B677	SSHS-B677-SUB-0-2	3/21/2017	856.08	0 - 2 ft	180-64494-1	Excavated	2.17	< 0.0099	< 0.0097	< 0.0074	< 0.015	1.5	0.47	0.2	< 0.013	< 0.0057
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	3/21/2017	856.07	0 - 2 ft	180-64494-1	Not Excavated	0.551	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.38	0.11	0.061	< 0.013	< 0.0056
Tennis Courts / Main Parking Lot	SSHS-B679B	071417 08:00_SSHS-B679B-SUB-0-2	7/13/2017	855.48	0 - 2 ft	180-68203-1	Excavated	0.287	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.18	0.091	0.016 J	< 0.013 U	< 0.0054 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	104.9	< 0.26 U	< 0.34 U	< 0.3 U	< 0.29 U	100	< 0.25 U	4.9	< 0.39 U	< 0.23 U
Football Field	SSHS-B685B	071417 08:00_SSHS-B685B-SUB-0-2	7/13/2017	855.54	0 - 2 ft	180-68203-1	Excavated	15.68	< 0.098 U	< 0.095 U	< 0.073 U	< 0.15 U	11	3.9	0.78	< 0.13 U	< 0.056 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	0.571	< 0.0027 U	< 0.0034 U	< 0.0031 U	< 0.0029 U	0.52	< 0.0026 U	0.051	< 0.0039 U	< 0.0023 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated	11					11				
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	1.5	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	1.4	< 0.0027 U	0.1	< 0.0041 U	< 0.0024 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Football Field	SSHS-B743	SSHS-B743-SUB-0-2	4/13/2017	855.75	0 - 2 ft	180-65226-1	Excavated	0.846	< 0.011 U	< 0.011 U	< 0.0082 U	< 0.016 U	0.54	0.25	0.056	< 0.015 U	< 0.0063 U
Football Field	SSHS-B744	SSHS-B744-SUB-0-2	4/13/2017	856.21	0 - 2 ft	180-65226-1	Excavated	0.475	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.33	0.12	0.025	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B745	PS-FD-13	5/22/2017	855.73	0 - 2 ft	180-66618-1	Not Excavated	0.36	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.24	0.094	0.026	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B745	SSHS-B745-SUB-0-2	5/22/2017	855.73	0 - 2 ft	180-66618-1	Not Excavated	0.421	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.28	0.11	0.031	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B746	SSHS-B746-SUB-0-2	5/22/2017	855.63	0 - 2 ft	180-66618-1	Not Excavated	0.402	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.25	0.12	0.032	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B747	SSHS-B747-SUB-0-2	5/22/2017	856.07	0 - 2 ft	180-66618-1	Excavated	1.162	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.71	0.36	0.092	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B748	SSHS-B748-SUB-0-2	5/22/2017	856.15	0 - 2 ft	180-66618-1	Excavated	1.33	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.76	0.45	0.12	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B749	PS-FD-11	5/22/2017	856.27	0 - 2 ft	180-66618-1	Not Excavated	0.676	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.29	0.29	0.096	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B749	SSHS-B749-SUB-0-2	5/22/2017	856.27	0 - 2 ft	180-66618-1	Not Excavated	0.89	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.37	0.39	0.13	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	4.07	< 0.0027	< 0.0035	< 0.0031	< 0.003	3.7	< 0.0026	0.37	< 0.004	< 0.0024
Tennis Courts / Main Parking Lot	SSHS-B750	SSHS-B750-SUB-0-2	5/22/2017	856.17	0 - 2 ft	180-66618-1	Excavated	1.44	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.81	0.48	0.15	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-0-2	5/22/2017	856.21	0 - 2 ft	180-66618-1	Excavated	3.35	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	2.1	1	0.25	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-0-2	5/22/2017	856.21	0 - 2 ft	180-66618-1	Excavated	3.35	< 0.0096	< 0.0094	< 0.0072	< 0.014	2.1	1	0.25	< 0.013	< 0.0055
Tennis Courts / Main Parking Lot	SSHS-B752	PS-FD-12	5/22/2017	856.15	0 - 2 ft	180-66618-1	Excavated	1.44	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.85	0.46	0.13	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B752	SSHS-B752-SUB-0-2	5/22/2017	856.15	0 - 2 ft	180-66618-1	Excavated	1.01	< 0.0092 U	< 0.009 U	< 0.0068 U	< 0.014 U	0.57	0.34	0.1	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B758	SSHS-B758-SUB-0-2	5/22/2017	856.30	0 - 2 ft	180-66618-1	Excavated	1.27	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.81	0.35	0.11	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B759	PS-FD-14	5/22/2017	856.24	0 - 2 ft	180-66618-1	Not Excavated	1.07	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.55	0.39	0.13	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B759	SSHS-B759-SUB-0-2	5/22/2017	856.24	0 - 2 ft	180-66618-1	Not Excavated	0.452	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.23	0.17	0.052	< 0.012 U	< 0.0052 U
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	0.53	< 0.0028	< 0.0036	< 0.0032	< 0.003	0.47	< 0.0026	0.06	< 0.0041	< 0.0024
Tennis Courts / Main Parking Lot	SSHS-B765	SSHS-B765-SUB-0-2	5/22/2017	856.08	0 - 2 ft	180-66618-2	Excavated	1.89	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	1.3	0.46	0.13	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B766	SSHS-B766-SUB-0-2	5/22/2017	856.26	0 - 2 ft	180-66618-2	Excavated	0.415	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.2	0.16	0.055	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B767	SSHS-B767-SUB-0-2	5/22/2017	855.87	0 - 2 ft	180-66618-2	Excavated	0.685	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.39	0.24	0.055	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B768	SSHS-B768-SUB-0-2	5/22/2017	855.82	0 - 2 ft	180-66618-2	Excavated	1.14	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.72	0.33	0.09	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B769	SSHS-B769-SUB-0-2	5/22/2017	855.85	0 - 2 ft	180-66618-2	Not Excavated	0.863	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.53	0.26	0.073	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	0.162	< 0.0026	< 0.0033	< 0.0029	< 0.0028	0.089	< 0.0024	0.073	< 0.0038	< 0.0022
Tennis Courts / Main Parking Lot	SSHS-B770	SSHS-B770-SUB-0-2	5/22/2017	856.04	0 - 2 ft	180-66618-2	Not Excavated	0.307	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.15	0.12	0.037	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-0-2	5/22/2017	856.31	0 - 2 ft	180-66618-2	Not Excavated	0.404	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	< 0.0084 U	0.35	0.054	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B772	SSHS-B772-SUB-0-2	5/22/2017	856.30	0 - 2 ft	180-66618-2	Excavated	1.28	< 0.0091 U	< 0.0088 U	< 0.0068 U	< 0.014 U	0.76	0.38	0.14	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B773	SSHS-B773-SUB-0-2	5/22/2017	856.38	0 - 2 ft	180-66618-2	Excavated	1.21	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.61	0.42	0.18	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B774	SSHS-B774-SUB-0-2	5/22/2017	856.38	0 - 2 ft	180-66618-2	Not Excavated	0.359	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.16	0.15	0.049	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-0-2	5/23/2017	855.99	0 - 2 ft	180-66622-1	Not Excavated	0.301	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.17	0.097	0.034	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B778	SSHS-B778-SUB-0-2	5/22/2017	855.75	0 - 2 ft	180-66618-2	Excavated	8.44	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	5.4	2.3	0.74	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B779	SSHS-B779-SUB-0-2	5/22/2017	856.22	0 - 2 ft	180-66618-2	Excavated	0.517	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.3	0.17	0.047	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	0.76	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	0.63	< 0.0027 U	0.13	< 0.0041 U	< 0.0024 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B780	SSHS-B780-SUB-0-2	5/22/2017	857.31	0 - 2 ft	180-66618-2	Not Excavated	0.246	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.15	0.073	0.023	< 0.013 U	< 0.0056 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated	11					11				
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Football Field	SSHS-B814	SSHS-B814-SUB-0.17-2	5/18/2017	855.66	0.17 - 2 ft	180-66476-2	Excavated	1.272	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.016 U	0.73	0.48	0.062	< 0.014 U	< 0.006 U
Football Field	SSHS-B815	PS-FD-10	5/18/2017	856.09	0.17 - 2 ft	180-66476-1	Excavated	1.076	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.016 U	0.59	0.4	0.086	< 0.014 U	< 0.006 U
Football Field	SSHS-B815	SSHS-B815-SUB-0.17-2	5/18/2017	856.09	0.17 - 2 ft	180-66476-1	Excavated	7.06	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	3.7	2.8	0.56	< 0.014 U	< 0.0059 U
Football Field	SSHS-B816	SSHS-B816-SUB-0.17-2	5/18/2017	856.25	0.17 - 2 ft	180-66476-2	Excavated	0.605	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.016 U	0.39	0.16	0.055	< 0.014 U	< 0.006 U
Football Field	SSHS-B817	SSHS-B817-SUB-0.17-2	5/18/2017	855.68	0.17 - 2 ft	180-66476-2	Excavated	0.322	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.18	0.088	0.054	< 0.014 U	< 0.0059 U
Football Field	SSHS-B818	SSHS-B818-SUB-0.17-2	5/18/2017	856.02	0.17 - 2 ft	180-66476-2	Excavated	0.29	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.016 U	0.17	0.12	< 0.013 U	< 0.014 U	< 0.006 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B822	DUP-1	6/19/2017	856.39	0 - 2 ft	180-67517-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B822	SSHS-B822-SUB-0-2	6/19/2017	856.39	0 - 2 ft	180-67517-1	Not Excavated	ND	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.009 U	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B825	PS-FD-9	7/13/2017	855.59	0 - 2 ft	180-68203-1	Excavated	53.4	< 0.48 U	< 0.47 U	< 0.36 U	< 0.72 U	39	12	2.4	< 0.65 U	< 0.28 U
Football Field	SSHS-B825	SSHS-B825-SUB-0-2	7/13/2017	855.59	0 - 2 ft	180-68203-1	Excavated	10.84	< 0.095 U	< 0.093 U	< 0.071 U	< 0.14 U	8	2.4	0.44	< 0.13 U	< 0.055 U
Football Field	SSHS-B826	SSHS-B826-SUB-0-2	7/13/2017	855.69	0 - 2 ft	180-68203-1	Excavated	10.5	< 0.096 U	< 0.093 U	< 0.071 U	< 0.14 U	7.1	3.1	0.3	< 0.13 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B827	SSHS-B827-SUB-0-2	7/13/2017	855.20	0 - 2 ft	180-68203-1	Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Rear Parking Lot	SSHS-B828	SSHS-B828-SUB-0-2	1/14/2018	851.95	0 - 2 ft	180-74210-1	Excavated	3.93	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8 J	0.89 J	0.24 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-0-2	1/10/2018	852.37	0 - 2 ft	180-74125-1	Not Excavated	ND	< 0.0055 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.013 U	< 0.012 U	< 0.0048 U	< 0.012 U	< 0.0082 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-0-2	1/11/2018	854.01	0 - 2 ft	180-74124-1	Excavated	48.1	< 0.29 U	< 0.59 U	< 0.54 U	< 0.54 U	36 J	9.9 J	2.2 J	< 0.63 U	< 0.44 U
Rear Parking Lot	SSHS-B830	PS-FD-10	1/11/2018	854.01	0 - 2 ft	180-74124-1	Excavated	7.57	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	5.6 J	1.6 J	0.37 J	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B831	PS-FD-6	1/10/2018	852.87	0 - 2 ft	180-74125-1	Excavated	5.53	< 0.028 U	< 0.056 U	< 0.051 U	< 0.052 U	4.1 J	1.1 J	0.33 J	< 0.061 U	< 0.042 U
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-0-2	1/10/2018	852.87	0 - 2 ft	180-74125-1	Excavated	0.517	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.37 J	0.12 J	0.027 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-0-2	1/10/2018	854.16	0 - 2 ft	180-74125-1	Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-0-2	1/12/2018	853.08	0 - 2 ft	180-74207-1	Excavated	79.6	< 0.29 U	< 0.58 U	< 0.53 U	< 0.54 U	55 J	21 J	3.6 J	< 0.63 U	< 0.43 U
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-0-2	1/9/2018	852.53	0 - 2 ft	180-74014-1	Excavated	7.16	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	5.1 J	1.7 J	0.36 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-0-2	1/12/2018	852.96	0 - 2 ft	180-74207-1	Excavated	204	< 0.29 U	< 0.58 U	< 0.53 U	< 0.53 U	130 J	61 J	13 J	< 0.63 U	< 0.43 U
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-0-2	1/20/2018	852.83	0 - 2 ft	180-74390-1	Excavated	17.5	< 0.24 U	< 0.47 U	< 0.43 U	< 0.44 U	12 J	4.9 J	0.6 J	< 0.51 U	< 0.35 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-0-2	1/9/2018	851.95	0 - 2 ft	180-74014-1	Excavated	0.091	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.064 J	0.027 J	< 0.0049 U	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-0-2	1/18/2018	850.25	0 - 2 ft	180-74307-1	Excavated	17.51	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	13 J	3.7 J	0.81 J	< 0.063 U	< 0.044 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-0-2	1/20/2018	850.15	0 - 2 ft	180-74390-1	Excavated	39.4	< 0.057 U	< 0.11 U	< 0.1 U	< 0.1 U	29 J	9.2 J	1.2 J	< 0.12 U	< 0.084 U
Rear Parking Lot	SSHS-B841	PS-FD-30	1/20/2018	850.17	0 - 2 ft	180-74390-1	Excavated	46.5	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	33 J	12 J	1.5 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-0-2	1/20/2018	850.17	0 - 2 ft	180-74390-1	Excavated	29.03	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	21 J	7.1 J	0.93 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-0-2	1/20/2018	852.12	0 - 2 ft	180-74390-1	Excavated	23.25	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	16 J	6.4 J	0.85 J	< 0.26 U	< 0.18 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-0-2	1/18/2018	850.33	0 - 2 ft	180-74307-1	Excavated	0.366	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.25 J	0.099 J	0.017 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B851	PS-FD-24	1/18/2018	851.45	0 - 2 ft	180-74307-1	Excavated	12.25	< 0.029 U	< 0.058 U	< 0.053 U	< 0.053 U	9.2 J	2.5 J	0.55 J	< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-0-2	1/18/2018	851.45	0 - 2 ft	180-74307-1	Excavated	12.34	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	8.9 J	3.1 J	0.34 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B852	PS-FD-28	1/19/2018	851.29	0 - 2 ft	180-74310-1	Excavated	8.54	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	6 J	2.3 J	0.24 J	< 0.12 U	< 0.085 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-0-2	1/19/2018	851.29	0 - 2 ft	180-74310-1	Excavated	5.59	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	3.9 J	1.5 J	0.19 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-0-2	1/8/2018	852.22	0 - 2 ft	180-74016-1	Excavated	2.01	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	1.4 J	0.5 J	0.11 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-B854	PS-FD-3	1/9/2018	851.71	0 - 2 ft	180-74014-1	Excavated	0.019	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.019	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-0-2	1/9/2018	851.71	0 - 2 ft	180-74014-1	Excavated	ND	< 0.0055 U	< 0.011 U	< 0.0099 U	< 0.01 U	< 0.013 U	< 0.011 U	< 0.0048 U	< 0.012 U	< 0.0081 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-0-2	1/10/2018	851.59	0 - 2 ft	180-74125-1	Excavated	14.34	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	10 J	3.6 J	0.74 J	< 0.12 U	< 0.085 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-0-2	1/17/2018	850.70	0 - 2 ft	180-74241-1	Excavated	0.076	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.057 J	0.019 J	< 0.0051 U	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-0-2	1/20/2018	850.15	0 - 2 ft	180-74390-1	Excavated	0.1639	< 0.0058 U	< 0.011 U	< 0.01 U	< 0.011 U	0.11 J	0.045 J	0.0089 J	< 0.012 U	< 0.0086 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0034 U	< 0.0031 U	< 0.0029 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-0-2	1/9/2018	852.32	0 - 2 ft	180-74014-1	Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.012 U	< 0.0086 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	0.185	< 0.0027 U	< 0.0035 U	< 0.0032 U	< 0.003 U	0.15	< 0.0026 U	0.035	< 0.004 U	< 0.0024 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	851.27	0 - 2 ft	180-74307-2	Excavated	1.971	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	1.4 J	0.49 J	0.081 J	< 0.012 U	< 0.0085 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	0.085	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	0.049	< 0.0027 U	0.036	< 0.0041 U	< 0.0024 U
Rear Parking Lot	SSHS-B880	PS-FD-36	1/22/2018	850.01	0 - 2 ft	180-74331-1	Excavated	29.7	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	20 J	8.4 J	1.3 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-0-2	1/22/2018	850.01	0 - 2 ft	180-74331-1	Excavated	35.8	< 0.069 U	< 0.14 U	< 0.13 U	< 0.13 U	24 J	9.5 J	2.3 J	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-0-2	1/22/2018	849.63	0 - 2 ft	180-74331-1	Excavated	38	< 0.074 U	< 0.15 U	< 0.13 U	< 0.14 U	26 J	9.6 J	2.4 J	< 0.16 U	< 0.11 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-0-2	1/19/2018	850.66	0 - 2 ft	180-74310-1	Excavated	102.8	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	76 J	24 J	2.8 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-0-2	1/22/2018	850.02	0 - 2 ft	180-74331-1	Excavated	14.52	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	10 J	3.9 J	0.62 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B888	PS-FD-37	1/22/2018	850.02	0 - 2 ft	180-74331-1	Excavated	7.52	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	5.2 J	2 J	0.32 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-0-2	1/12/2018	852.37	0 - 2 ft	180-74207-1	Excavated	75.3	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	49 J	22 J	4.3 J	< 0.26 U	< 0.18 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	0.0263	< 0.0027 U	< 0.0034 U	< 0.0031 U	< 0.0029 U	0.019	< 0.0025 U	0.0073 J	< 0.0039 U	< 0.0023 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-0-2	1/19/2018	851.47	0 - 2 ft	180-74310-1	Excavated	54.5	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	40 J	13 J	1.5 J	< 0.13 U	< 0.088 U

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-0-2	1/17/2018	850.94	0 - 2 ft	180-74241-1	Excavated	22.1	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	15 J	6 J	1.1 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-0-2	1/19/2018	851.16	0 - 2 ft	180-74310-1	Excavated	31.5	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	23 J	7.6 J	0.9 J	< 0.13 U	< 0.09 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-0-2	1/9/2018	852.71	0 - 2 ft	180-74014-1	Excavated	29	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	21 J	6.6 J	1.4 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	850.31	0 - 2 ft	180-74241-2	Excavated	10.89	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	8 J	2.4 J	0.49 J	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-0-2	1/16/2018	850.75	0 - 2 ft	180-74203-1	Excavated	0.247	< 0.0055 U	< 0.011 U	< 0.01 U	< 0.01 U	0.23 J		0.017 J	< 0.012 U	< 0.0083 U
Rear Parking Lot	SSHS-B931	SSHS-B931-SUB-0-2	1/10/2018	850.20	0 - 2 ft	180-74125-1	Excavated	13.04	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	9.4 J	3 J	0.64 J	< 0.063 U	< 0.043 U
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-0-2	1/10/2018	850.54	0 - 2 ft	180-74125-1	Excavated	0.091	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.091	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B933	PS-FD-26	1/19/2018	850.91	0 - 2 ft	180-74310-1	Excavated	21.67	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	16 J	5.1 J	0.57 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B933	SSHS-B933-SUB-0-2	1/19/2018	850.91	0 - 2 ft	180-74310-1	Excavated	16.34	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	12 J	3.6 J	0.74 J	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B934	PS-FD-5	1/10/2018	849.30	0 - 2 ft	180-74125-1	Excavated	18.5	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	12 J	5.3 J	1.2 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B934	SSHS-B934-SUB-0-2	1/10/2018	849.30	0 - 2 ft	180-74125-1	Excavated	23.7	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	14 J	7.6 J	2.1 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B935	SSHS-B935-SUB-0-2	1/10/2018	847.88	0 - 2 ft	180-74125-1	Excavated	12.89	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	8.1 J	3.9 J	0.89 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-0-2	1/22/2018	850.00	0 - 2 ft	180-74331-1	Excavated	175.3	< 0.75 U	< 1.5 U	< 1.4 U	< 1.4 U	130 J	37 J	8.3 J	< 1.6 U	< 1.1 U
Rear Parking Lot	SSHS-B946	PS-FD-35	1/22/2018	850.00	0 - 2 ft	180-74331-1	Excavated	6.23	< 0.0072 U	< 0.014 U	< 0.013 U	< 0.013 U	4.3 J	1.5 J	0.43 J	< 0.016 U	< 0.011 U
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-0-2	1/22/2018	850.00	0 - 2 ft	180-74331-1	Excavated	6.81	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	4.8 J	1.6 J	0.41 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B959	PS-FD-2	2/28/2018	851.25	0 - 2 ft	180-75403-1	Excavated	20.8	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	13	6.5	1.3	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-0-2	2/28/2018	851.25	0 - 2 ft	180-75403-1	Excavated	13.34	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	8.7	3.8	0.84	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B968	SSHS-B968-SUB-0-2	3/1/2018	851.52	0 - 2 ft	180-75478-1	Excavated	4.61	< 0.029 U	< 0.057 U	< 0.052 U	< 0.053 U	2.8	1.6	0.21	< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B995	SSHS-B995-SUB-0-2	3/1/2018	850.03	0 - 2 ft	180-75478-1	Excavated	65	< 0.17 U	< 0.33 U	< 0.31 U	< 0.31 U	47	16	2	< 0.36 U	< 0.25 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	2.94	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	2.1	< 0.038 U	0.84		
Football Field	SSHS-FB10-A	SSHS-FB10-A-SUB-0-2	7/15/2015	855.73	0 - 2 ft	180-45961-1	Excavated	48	< 0.083 U	< 0.1 U	< 0.14 U	< 0.1 U	34 J	14 J	< 0.089 U	< 0.15 U	< 0.082 U
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	0.13	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	0.13	< 0.04 U	< 0.04 U		
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	1.006	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	0.94	< 0.04 U	0.066		
Football Field	SSHS-FB6-AA	SSHS-FB6-AA-SUB-0-2	7/15/2015	856.09	0 - 2 ft	180-45961-1	Excavated	2.01	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	1.3 J	0.71 J	< 0.0071 U	< 0.0038 U
Football Field	SSHS-FB7	B23401T3	8/14/2000	856.66	0 - 0.5 ft	NA	Excavated	0.19	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	0.19	< 0.046 U	< 0.046 U		
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	4.2	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 100 U	< 0.04 U	4.2		
Football Field	SSHS-FB7	B23405T3	8/14/2000	856.66	1.5 - 2 ft	NA	Excavated	160	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	160	< 0.04 U	< 0.04 U		
Football Field	SSHS-FB7-A	SSHS-FB7-A-SUB-0.17-1	7/21/2014	856.41	0.17 - 1 ft	180-35053-1	Excavated	0.216	< 0.0013 U	< 0.0017 U	< 0.0015 U	< 0.0015 U	0.15 J	0.066 J	< 0.0013 U	< 0.002 U	< 0.0012 U
Football Field	SSHS-FB7-A	SSHS-FB7-A-SUB-1-2	7/21/2014	856.41	1 - 2 ft	180-35053-1	Excavated	26.9	< 0.028 U	< 0.036 U	< 0.032 U	< 0.03 U	20 J	6.9 J	< 0.026 U	< 0.041 U	< 0.024 U
Football Field	SSHS-FB7-B	SSHS-FB7-B-SUB-0.17-1	7/21/2014	856.19	0.17 - 1 ft	180-35053-1	Excavated	0.063	< 0.0015 U	< 0.0019 U	< 0.0017 U	< 0.0016 U	0.041 J	0.022 J	< 0.0014 U	< 0.0021 U	< 0.0013 U
Football Field	SSHS-FB7-B	SSHS-FB7-B-SUB-1-2	7/21/2014	856.19	1 - 2 ft	180-35053-1	Excavated	30.2	< 0.072 U	< 0.093 U	< 0.083 U	< 0.079 U	23 J	7.2 J	< 0.069 U	< 0.11 U	< 0.062 U
Football Field	SSHS-FB7-C	SSHS-FB7-C-SUB-0.17-1	7/21/2014	856.56	0.17 - 1 ft	180-35053-1	Excavated	3.75	< 0.0015 U	< 0.0019 U	< 0.0017 U	< 0.0016 U	2.6 J	0.99 J	< 0.0014 U	0.16 J	< 0.0013 U
Football Field	SSHS-FB7-C	SSHS-FB7-DUP4	7/21/2014	856.56	0.17 - 1 ft	180-35053-1	Excavated	3.76	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	2.6 J	1 J	< 0.0013 U	0.16 J	< 0.0012 U
Football Field	SSHS-FB7-C	SSHS-FB7-C-SUB-1-2	7/21/2014	856.56	1 - 2 ft	180-35053-1	Excavated	23.2	< 0.014 U	< 0.018 U	< 0.016 U	< 0.015 U	16 J	6.2 J	< 0.013 U	1 J	< 0.012 U
Football Field	SSHS-FB7-D	SSHS-FB7-D-SUB-0.17-1	7/21/2014	856.62	0.17 - 1 ft	180-35053-1	Excavated	0.184	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	0.12 J	0.064 J	< 0.0013 U	< 0.002 U	< 0.0012 U
Football Field	SSHS-FB7-D	SSHS-FB7-D-SUB-1-2	7/21/2014	856.62	1 - 2 ft	180-35053-1	Excavated	6.8	< 0.0074 U	< 0.0095 U	< 0.0085 U	< 0.0081 U	5 J	1.8 J	< 0.007 U	< 0.011 U	< 0.0064 U
Football Field	SSHS-FB7-E	SSHS-FB7-E-SUB-0.17-1	7/21/2014	856.28	0.17 - 1 ft	180-35053-1	Excavated	7.1	< 0.0069 U	< 0.0088 U	< 0.0079 U	< 0.0075 U	5 J	2.1 J	< 0.0066 U	< 0.01 U	< 0.0059 U
Football Field	SSHS-FB7-E	SSHS-FB7-E-SUB-1-2	7/21/2014	856.28	1 - 2 ft	180-35053-1	Excavated	25.6	< 0.028 U	< 0.035 U	< 0.032 U	< 0.03 U	19 J	6.6 J	< 0.026 U	< 0.041 U	< 0.024 U
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	0.068	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	0.068		
Football Field	SSHS-FB9-AA	SSHS-FB9-AA-SUB-0.17-0.5	7/16/2015	854.80	0.17 - 0.5 ft	180-46033-1	Excavated	2.5	< 0.0043 U	< 0.0052 U	< 0.0072 U	< 0.0053 U	1.5 J	0.87 J	0.13 J	< 0.0077 U	< 0.0042 U
Football Field	SSHS-GS-01	SSHS-GS-01	8/23/2019	855.29	0.5 - 0.5 ft	180-94662-1	Excavated	4.23	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2.6	1.2	0.43	< 0.0068 U	< 0.0026 U
Football Field	SSHS-GS-02	SSHS-GS-02	8/23/2019	855.18	0.5 - 0.5 ft	180-94662-1	Excavated	209.8	< 3 U	< 3.3 U	< 2.3 U	< 1.4 U	130	70	9.8	< 3.3 U	< 1.3 U
Football Field	SSHS-GS-03	SSHS-GS-03	8/23/2019	855.06	0.5 - 0.5 ft	180-94662-1	Excavated	305	< 3.1 U	< 3.4 U	< 2.3 U	< 1.4 U	190	100	15	< 3.4 U	< 1.3 U
Football Field	SSHS-GS-04	SSHS-GS-04	8/23/2019	855.13	0.5 - 0.5 ft	180-94662-1	Excavated	199.8	< 3.1 U	< 3.4 U	< 2.3 U	< 1.4 U	120	70	9.8	< 3.3 U	< 1.3 U
Football Field	SSHS-GS-05	SSHS-GS-05	8/23/2019	855.13	0.5 - 0.5 ft	180-94662-1	Excavated	13.9	< 0.062 U	< 0.068 U	< 0.047 U	< 0.028 U	7.4	5.4	1.1	< 0.067 U	< 0.026 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-0-2	8/30/2016	850.92	0 - 2 ft	180-58275-1	Excavated	5.1	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	3.4 J	1.5 J	0.2 J	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-NE SIDEWALL S1	NORTH EXCAVATION SIDEWALL S1	7/10/2017	856.41	0 - 2 ft	180-68039-1	Excavated	6.24	< 0.0093	< 0.009	< 0.0069	< 0.014	3.8	1.9	0.54	< 0.013	< 0.0053
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	ND	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U	< 0.05 U		
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	0.73	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.63	< 0.045 U	0.1		
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	0.73	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	0.58	< 0.037 U	0.15		
Football Field	SSHS-SS12	SSHS-SS12-DUP6	7/22/2014	855.88	1 - 2 ft	180-35079-1	Excavated	34	< 0.027 U	< 0.035 U	< 0.031 U	< 0.029 U	22 J	12 J	< 0.026 U	< 0.04 U	< 0.023 U
Football Field	SSHS-SS12-A	SSHS-SS12-A-0.17-1	7/22/2014	855.86	0.17 - 1 ft	180-35079-1	Excavated	1.38	< 0.00068 U	< 0.00087 U	< 0.00078 U	< 0.00074 U	0.93 J	0.45 J	< 0.00065 U	< 0.001 U	< 0.00059 U
Football Field	SSHS-SS12-A	SSHS-SS12-A-1-2	7/22/2014	855.86	1 - 2 ft	180-35079-1	Excavated	32.1	< 0.013 U	< 0.017 U	< 0.015 U	< 0.014 U	23 J	9.1 J	< 0.013 U	< 0.019 U	< 0.011 U
Football Field	SSHS-SS12-B	SSHS-SS12-B-0.17-1	7/22/2014	856.00	0.17 - 1 ft	180-35079-1	Excavated	2.6	< 0.0034 U	< 0.0044 U	< 0.0039 U	< 0.0037 U	1.5 J	1.1 J	< 0.0032 U	< 0.005 U	< 0.0029 U
Football Field	SSHS-SS12-B	SSHS-SS12-B-1-2	7/22/2014	856.00	1 - 2 ft	180-35079-1	Excavated	9.3	< 0.0067 U	< 0.0086 U	< 0.0077 U	< 0.0073 U	5.7 J	3.6 J	< 0.0064 U	< 0.0098 U	< 0.0058 U
Football Field	SSHS-SS12-C	SSHS-SS12-C-0.17-1	7/22/2014	855.81	0.17 - 1 ft	180-35079-1	Excavated	2.48	< 0.0034 U	< 0.0043 U	< 0.0039 U	< 0.0037 U	1.6 J	0.88 J	< 0.0032 U	< 0.0049 U	< 0.0029 U
Football Field	SSHS-SS12-C	SSHS-SS12-C-1-2	7/22/2014	855.81	1 - 2 ft	180-35079-1	Excavated	14.4	< 0.0066 U	< 0.0084 U	< 0.0076 U	< 0.0072 U	9.9 J	4.5 J	< 0.0063 U	< 0.0097 U	< 0.0057 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	0.98	< 0.046 U	< 0.046 U	< 0.046 U	< 0.046 U	0.73	< 0.46 U	0.25		

DRAFT

TABLE 5-5A
Shallow Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	ND	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U	< 0.043 U		
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	0.053	< 0.045 U	< 0.045 U	< 0.045 U	< 0.045 U	0.053	< 0.045 U	< 0.045 U		
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	ND	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U	< 0.044 U		
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	ND	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U	< 0.047 U		
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	0.22	< 0.045 U	< 0.045 U	< 0.045 U	< 0.045 U	0.22	< 0.045 U	< 0.045 U		

DRAFT

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**	**Lead**	**Magnesium**	**Manganese**
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential									16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater									16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity									100	2000		20		100					1000		
			5 & 6	5 & 6																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]														
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	3500	0.21 J	2.8	26	0.13 J	< 0.050 UJ	23000 J	4.9		3.6	14	9100	5.3	5400	200
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			3.6	104	< 0.7 U	< 0.7 U		81.7			18.8		20.5		
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	7900	< 0.21 U	12	82	0.38 J	0.12 J	16000	12		7.7	63	21000	54	3900	540
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated	9510	0.25	8.2	89.3	0.42	1.9	19100	15.9 *E	< U		65.7	25500	63.6 NE	5010	458 *E
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated			4.2	120	< 0.62 U	< 0.62 U		15.8			14.9		17.7		
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated			4.5	105	< 0.55 U	< 0.55 U		11.1			21.7		19.1		
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated			3.5	75.5	< 0.66 U	< 0.66 U		19.5			19		22.2		
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated			12.4	93.2	< 0.57 U	< 0.57 U		12.6			51.1		46.8		
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated			6.2	114	< 0.64 U	< 0.64 U		12.3			14.8		17.9		
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated			4.4	111	< 0.65 U	< 0.65 U		15.5			18.5		21		
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700	171 NE	3760	379 *E
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated			7	136	< 0.61 U	< 0.61 U		14			15.9		16.7		
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	8600	0.59 J	7.5	86	0.47	< 0.04 U	11000	11		8	48	20000	56	3500	790
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	10000	< 0.43 U	7.4	110	0.52	0.24 J	5100	24		8.4	24	21000	67	3300	490
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	8100	1.2	7.6	100	0.4 J	< 0.04 U	9100	24		7.7	62	24000	93	2700	480
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	13000	< 0.43 U	8.6	130	0.62	< 0.045 U	2700	16		12	19	24000	18	4000	680
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	11000	< 0.46 U	7.5	97	0.49 J	< 0.049 U	3900	16		10	38	24000	28	4100	570
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	9200	< 0.38 U	6.7	79	0.43 J	0.13 J	9000	13		7.5	54	22000	40	3500	460
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	7400	< 0.4 U	5.9	78	0.32 J	0.11 J	31000	11		6.1	24	17000	30	14000	360
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	12000	< 0.41 U	7	92	0.52	0.11 J	2200	15		9.5	20	23000	17	3300	530
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	12000	< 0.39 U	8.3	160	0.56	0.28 J	11000	17		9.7	43	27000	86	3900	530
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	7700	< 0.37 U	6.3	92	0.35 J	0.16 J	17000	12		6.6	35	19000	43	3900	410
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	12000	< 0.39 U	7.1	100	0.55	< 0.042 U	2700	15		9.6	17	20000	49	3000	530
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	12000	< 0.49 U	6.9	110	0.58	0.32 J	2900	48		9.3	21	23000	18	3500	530
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	13000	< 0.39 U	7.3	96	0.61	0.093 J	2100	17		9.8	16	22000	18	3200	480
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	11000	< 0.4 U	7	90	0.51	0.17 J	5000	21		8.8	26	21000	27	3000	470
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	11000	< 0.43 U	6.9	95	0.52	0.14 J	2100	14		9.1	18	20000	27	2800	530
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated	11000	< 0.4 U	7.7	100	0.47	0.18 J	6700	19		8.9	48	26000	36	3900	650
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	8500	< 0.41 U	6.4	110	0.4 J	0.11 J	7500	12		7.7	37	18000	36	3000	460
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	9500	< 0.41 U	7.9	130	0.47 J	0.17 J	6300	14		8.4	26	19000	56	3300	490
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	9400	0.45 J	8.6	120	0.48	< 0.043 U	5000	15		7.8	36	21000	150	3000	490
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	13000	< 0.44 U	7.3	110	0.61	0.061 J	2400	15		10	16	23000	15	3600	520
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated	6700	< 0.41 U	6.6	98	0.32 J	0.18 J	15000	16		5.3 J	63	23000	170	2600	290
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	8000	0.42 J	9	480	0.47	0.35 J	15000	31		10	220	24000	140	3300	480
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	11000	< 0.38 U	6.9	110	0.59	< 0.041 U	2700	14		10	20	20000	15	3000	600
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	9100	< 0.43 U	6.9	110	0.47 J	0.21 J	18000	14		7.3	40	19000	63	4100	440
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	9700	16	8.9	140	0.49	0.58 J	16000	18		9.2	170	26000	270	2900	630
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	7200	8.7	9.1	240	0.44 J	0.26 J	4200	14		7.6	140	21000	360	2600	480
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	6800	6	9	330	0.44 J	0.36 J	2500	16		8	190	29000	130	2200	350
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	10000	< 0.42 U	6.5	99	0.51	0.14 J	2700	14		9	25	20000	15	3100	560
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	9100	< 0.41 U	7.6	110	0.44 J	0.15 J	18000	15		7.7	32	20000	45	3200	450
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	11000	< 0.42 U	7	110	0.55	0.14 J	5700	15		9.3	28	21000	37	3400	540
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	13000	33	10	110	0.6	0.16 J	8800	17		11	190	30000	120	3500	470
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	7500	< 0.39 U	6.2	77	0.35 J	0.11 J	9900	10		6.3	34	16000	36	2500	510
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	7700	0.65 J	9	120	0.4 J	0.24 J	9600	34		8.4	300	30000	120	3000	530
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	9200	< 0.37 U	7.4	73	0.4 J	0.17 J	22000	14		8	51	25000	35	5100	490
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	8800	< 0.39 U	6.1	110	0.35 J	0.16 J	19000	15		7.1	63	20000	520	4600	410
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	6100	< 0.36 U	15	63	0.3 J	0.089 J	49000	8.9		5.4	26	15000	25	19000	400
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	7900	< 0.35 U	5.3	84	0.32 J	0.14 J	65000	11		6.8	31	17000	16	7000	450
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	5900	< 0.36 U	3.9	44	0.24 J	0.11 J	46000	8.4		4.7 J	22	22000	18	4800	400
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	9400	< 0.42 U	7	120	0.46 J	0.24 J	4000	21		7.3	28	19000	86	2800	490
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	7600	< 0.41 U	9	78	0.56	0.2 J	39000	15		8	27	16000	25	23000	490
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	8100	1.4	13	190	0.42 J	0.22 J	9700	30		11	93	55000	230	2800	960
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	7600	< 0.4 U	8.3	180	0.39 J	0.25 J	23000	16		7.2	71	25000	200	4200	530
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	6300	< 0.37 U	5.1	190	0.36 J	0.29 J	40000	12		4.3 J	56	14000	180	3600	400
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	4500	< 0.38 U	5.1	35	0.27 J	0.066 J	9700	5.8		4 J	15	12000	8.8	2300	350
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	10000	< 0.41 U	6.7	100	0.46 J	< 0.044 U	4200	13		8.8	29	19000	23	2800	490
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated	5000	1 J	7.1	90	0.4 J	< 0.045 U	11000	11		5.4 J	50	21000	42	1700	270
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	3700	1.3	9.6	170	0.38 J	0.068 J	6100	8.6		4.6 J	44	21000	42	2000	140
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	5000	1.6	6.5	89	0.37 J	< 0.041 U	12000	11		5.7	40	22000	220	1900	210
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	7500	1.1 J	6.5	160	0.76	0.23 J	27000	15		6.4	87	21000	120	3000	310
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	8600	< 0.4 U	6.6	92	0.42 J	0.16 J	13000	16		7.5	24	17000	45	3400	420
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	5000	0.75 J	7.7	310	0.31 J	0.065 J	21000	23		5.5 J	100	20000	180	8900	350
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	9300	< 0.41 U,F1	5.8	89	0.43 J	0.16 J	2600	14		6.9	19	18000	28	2200	380
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	8600	< 0.41 U	6.7	91	0.4 J	< 0.044 U	4500	21		7.4	33	18000	86	3400	410
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	9600	< 0.42 U	7.2	120	0.45 J	< 0.044 U	5200	17		7.9	36	20000	74	2900	450
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	14000	< 0.4 U	8	90	0.6	< 0.043 U	15000	19		11	24	24000	36	3500	550
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	8700	< 0.4 U	7.4	85	0.48	0.2 J	1700	15		8.5	26	19000	50	2100	470
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	9600	0.56 J	12	570	0.53	1.3	10000	29		8.6	130	32000	450	2900	590
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	9200	< 0.4 U	6.4	86	0.41 J	0.14 J	10000	16		7.2	41	19000	66	3900	430
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	11000	< 0.39 U,F1	17	82	0.51	0.13 J	14000	15		7.5	31	28000	32	3700	400

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
				5 & 6	5 & 6													
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]											
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.016 U	9.8	240 J	0.34 J	< 0.071 U	220 J		< 0.19 U		6.2	37
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.06 U	20.1		< 0.71 U	< 1.4 U						77.8
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	0.032 J	47	750	0.54 J	< 0.043 U	92 J		0.17 J		13	110
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated	0.14	44.4 *E	790	2.1	< U	207		< U		15	90.3 NE
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.06 U	20.8		< 0.64 U	< 1.2 U						61.4
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	< 0.06 U	15.1		< 0.56 U	< 1.1 U						69.4
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.06 U	22.5		< 0.65 U	< 1.3 U						79.6
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	0.09	19.5		0.86	< 1.1 U						66.6
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.06 U	19.3		< 0.64 U	< 1.3 U						58.4
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.06 U	20.8		< 0.63 U	< 1.3 U						68.8
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated	0.042	453 *E	900	1.8	< U	1270		< U		14.7	111 NE
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	0 - 2.6 ft	-	Not Excavated							< U				
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	0 - 2.6 ft	-	Not Excavated							< U				
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	< 0.06 U	23.3		< 0.61 U	< 1.2 U						73.1
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	0.78	16	740	< 0.57 U	< 0.12 U	80 J		0.36 J		18	77
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	0.13	20	880	< 0.64 U	< 0.13 U	83 J		< 0.26 U		15	73
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	0.088	38	770	< 0.56 U	< 0.12 U	66 J		< 0.23 U		16	120
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	0.037 J	25	1100	< 0.64 U	< 0.13 U	39 J		0.5 J		19	73
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	0.047	24	890	< 0.7 U	< 0.14 U	49 J		0.42 J		17	88
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	0.057	21	680	< 0.58 U	< 0.12 U	130 J		< 0.24 U		15	76
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	0.68	17	670	< 0.6 U	0.42 J	91 J		< 0.24 U		14	74
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	0.022 J	22	740	< 0.61 U	< 0.13 U	< 31 U		< 0.25 U		16	67
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	0.036 J	51	900	< 0.6 U	< 0.12 U	110 J		< 0.24 U		18	130
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	0.023 J	34	680	< 0.56 U	< 0.11 U	55 J		< 0.23 U		12	76
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	0.055	20	1200	< 0.59 U	< 0.12 U	33 J		< 0.24 U		16	62
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	0.026 J	22		< 0.74 U	< 0.15 U	54 J		< 0.3 U		16	70
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	0.027 J	23		< 0.59 U	< 0.12 U	71 J		< 0.24 U		16	60
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	0.099	21	960	< 0.61 U	< 0.12 U	81 J		< 0.25 U		14	64
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	0.18	20	920	< 0.65 U	< 0.13 U	33 J		< 0.26 U		14	59
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated	0.15	23		< 0.61 U	< 0.12 U	71 J		< 0.25 U		16	89
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	0.22	20		< 0.62 U	< 0.13 U	90 J		< 0.25 U		13	96
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	1.1	21	970	< 0.62 U	< 0.13 U	73 J		< 0.25 U		15	92
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	0.23	19		< 0.61 U	0.17 J	77 J		0.35 J		18	96
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	0.96	23	910	< 0.67 U	< 0.14 U	39 J		< 0.27 U		16	58
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated	0.27	55		< 0.62 U	< 0.13 U	98 J		< 0.25 U		16	97
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	1	1900		0.67 J	< 0.12 U	150 J		< 0.25 U		16	650
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	0.59	21		< 0.58 U	< 0.12 U	63 J		0.23 J		15	62
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	0.84	71	900	< 0.64 U	< 0.13 U	97 J		< 0.26 U		15	96
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	0.23	40		< 0.62 U	< 0.13 U	95 J		< 0.25 U		17	420
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	0.084	1600	640	< 0.63 U	3.2	51 J		< 0.25 U		13	200
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	0.11	2200		< 0.6 U	7	56 J		< 0.24 U		14	370
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	0.62	22	750	< 0.63 U	< 0.13 U	47 J		< 0.26 U		13	69
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	0.55	25		< 0.62 U	< 0.13 U	90 J		< 0.25 U		14	89
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	0.4	25		< 0.63 U	< 0.13 U	58 J		< 0.26 U		15	71
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	0.35	27		< 0.61 U	< 0.12 U	460 J		< 0.25 U		20	93
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	0.12	40		< 0.59 U	< 0.12 U	68 J		< 0.24 U		11	76
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	0.08	110		0.82 J	< 0.12 U	110 J		< 0.23 U		17	140
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	0.051	39		0.74 J	< 0.11 U	80 J		< 0.23 U		15	100
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	0.051	31		< 0.59 U	< 0.12 U	69 J		< 0.24 U		14	130
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	0.059	18		0.79 J	< 0.11 U	80 J		< 0.22 U		17	58
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	0.019 J	21		< 0.53 U	< 0.11 U	75 J		< 0.21 U		24	62
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	0.027 J	17		0.62 J	< 0.11 U	77 J		< 0.22 U		27	62
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	0.19	18		< 0.64 U	< 0.13 U	66 J		< 0.26 U		15	79
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	0.15	24		0.78 J	< 0.13 U	130 J		< 0.25 U		14	63
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.095	730		0.68 J	0.15 J	74 J		< 0.24 U		18	360
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.097	94		0.69 J	< 0.12 U	97 J		< 0.24 U		17	120
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	0.11	47		< 0.56 U	< 0.11 U	130 J		< 0.23 U		12	120
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	0.037	11		< 0.57 U	< 0.12 U	61 J		< 0.23 U		15	34
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	0.15	18	990	< 0.62 U	< 0.13 U	52 J		0.25 J		15	65
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated	0.13	18		0.89 J,^	< 0.13 U	180 J		0.37 J		14	85
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	0.069	13		0.87 J	< 0.12 U	100 J		< 0.24 U		12	44
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	0.11	12		0.66 J,^	< 0.12 U	150 J		< 0.23 U		14	58
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	0.15	170		< 0.63 U	< 0.13 U	280 J		< 0.26 U		16	160
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	0.11	19	670	0.64 J	< 0.12 U	69 J		< 0.25 U		14	94
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	0.085	110	550 J	0.85 J,^	< 0.13 U	130 J		< 0.26 U		15	110
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	0.11	16	680	< 0.62 U	< 0.13 U	65 J		< 0.25 U		13	55
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	0.19	17	720	< 0.62 U	0.16 J	70 J		0.44 J		18	91
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	0.092	44	890	< 0.63 U,^	< 0.13 U	100 J		< 0.26 U		15	78
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	0.038 J	37	1100	< 0.61 U	< 0.13 U	110 J		0.25 J		21	99
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	0.044	28	760	< 0.61 U	< 0.12 U	62 J		< 0.25 U		18	84
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	0.12	210	890	0.81 J	< 0.13 U	170 J		< 0.25 U		19	350
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	0.08	22	760	0.61 J	< 0.12 U	76 J		< 0.25 U		15	80
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	0.052	20	780	1.2	< 0.12 U	100 J		< 0.24 U		17	64

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
				5 & 6	5 & 6																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	10000	< 0.41 U	12	91	0.51	0.15 J	4200	14		7.5	28	20000	39	2300	490
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	8900	< 0.39 U	7.1	85	0.43 J	0.16 J	19000	14		8.1	28	19000	69	3300	620
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	10000	< 0.4 U	6.8	81	0.46 J	0.18 J	20000	18		7.9	29	20000	27	4400	450
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	7700	< 0.38 U	5	71	0.33 J	0.084 J	30000	12		6.2	22	17000	14	5200	490
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	8600	0.72 J	8.3	6100	0.4 J	0.11 J	12000	23		7.8	250	29000	430	3800	1200
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	9100	< 0.8 U	8	5000	0.4 J	0.38 J	33000	26		5.8 J	230	27000	1900	3900	950
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	6600	< 0.36 U	4.2	42	0.26 J	0.09 J	80000	8.9		5.7	20	15000	7	15000	350
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	11000	< 0.39 U,F1	5.6	66	0.42 J	0.12 J	5400	14		8.6	22	21000	14	4100	470
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	7100	16	9.8	77	0.35 J	< 0.044 U	9400	22		10	150	54000	95	2800	590
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	7700	1 J	5.4	79	0.35 J	< 0.041 U	15000	14		7.1	86	21000	56	3200	750
Football Field	SSHS-B2649	SSHS-B2649-SUB-0.17-2	5/17/2019	856.28	0.17 - 2 ft	180-90275-1	Excavated	9900	< 0.39 U	7.5	150	0.48	0.17 J	7000	13		8.2	24	20000	110	3100	500
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	9000	1.1 J	10	160	0.51	0.4 J	6700	23		11	150	36000	120	2700	560
Football Field	SSHS-B2703	SSHS-B2703-SUB-0.17-2	5/19/2019	854.92	0.17 - 2 ft	180-90323-2	Excavated															
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	9800	< 0.4 U	8	100	0.62	0.17 J	2600	13		8.3	23	20000	31	2500	600
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	10000	0.54 J	7.8	100	0.53	0.15 J	9600 J	14		8.4	44	23000	46	3300	470
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	9800	1.3 J	7.6	110	0.51	0.17 J	22000 J	13		7.9	43	22000	47	3500	460
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	10000	0.8 J	7.4	94	0.47	0.16 J	11000	14		8.2	40	21000	59	3500	530
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	10000	0.61 J	7.2	93	0.47 J	0.14 J	8300 J-	14		8.7	30	22000	40	3500	510
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	10000	< 0.41 U	7.1	110	0.5	0.17 J	2300	13		8.8	16	19000	19	2900	580
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	11000	< 0.41 U	7.5	110	0.53	0.17 J	2400	14		9.3	16	20000	20	2900	600
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	8100	0.93 J	7.5	97	0.41 J	0.17 J	11000	12		7.2	62	23000	46	3600	420
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	11000	0.93 J	8	97	0.51	0.2 J	4000	21		9.1	51	55000 J	46	3300	650
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	11000	0.84 J	7.8	91	0.49	0.18 J	3200	20		8.7	39	22000 J	45	3300	490
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	13000	< 0.44 U	8	110	0.62	0.13 J	2500	15		11	28	23000	27	3300	610
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	10000	< 0.43 U	7	90	0.46 J	0.16 J	2100	16		8.6	27	20000	47	2900	510
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	9700	< 0.43 U	9.5	110	0.5	0.22 J	3500	20		8.2	26	23000	52	3000	560
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	11000	0.41 J	7.4	120	0.57	0.19 J	2800	20		9.7	18	21000	24	3200	530
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	9000	< 0.43 U	7.5	130	0.43 J	0.26 J	2800	16		6.4	47	17000	120	2100	540
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	13000	< 0.45 U	7.7	120	0.64	0.17 J	2200	18		11	16	23000	15	3400	600
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	6400	1.5	11	240	0.51	0.46 J	6200	22		7.4	130	40000	150	1900	440
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	9100	0.6 J	8.5	200	0.47	0.3 J	18000	16		7.5	53	23000	84	3700	470
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	8100	< 0.4 U	7.4	70	0.38 J	0.17 J	15000	13		8.6	27	20000	19	3200	500
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	6400	< 0.37 U	4.9	59	0.27 J	0.21 J	75000	9		5.6	29	15000	25	6500	430
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	4700	< 0.39 U	4.2	83	0.2 J	0.24 J	47000	13		4.7 J	40	13000	42	3600	300
Football Field	SSHS-B2734	PS-FD-22	5/18/2019	855.30	0.17 - 2 ft	180-90319-1	Excavated	6700	1.4 J-	19	3100	0.42 J	1.6	11000 J-	22		14	170	39000	380	2400	490
Football Field	SSHS-B2734	SSHS-B2734-SUB-0.17-2	5/18/2019	855.30	0.17 - 2 ft	180-90319-1	Excavated	7400	1 J	17	2500	0.44 J	1	9000	36		13	140	35000	300	2400	580
Football Field	SSHS-B2801	SSHS-B2801-SUB-0.17-2	5/21/2019	856.07	0.17 - 2 ft	180-90380-1	Excavated	11000	< 0.42 U	8.7	130	0.58	0.21 J	5100	21		10	35	23000	28	3300	660
Football Field	SSHS-B2802	SSHS-B2802-SUB-0.17-2	5/16/2019	855.97	0.17 - 2 ft	180-90231-1	Excavated	8400	0.85 J	7.7	120	0.42 J	0.18 J	7500	16		7	65	19000	76	3100	460
Football Field	SSHS-B2803	SSHS-B2803-SUB-0.17-2	5/14/2019	855.69	0.17 - 2 ft	180-90048-1	Excavated	8900	0.54 J	8.7	110	0.47 J	0.19 J	2500	15		6.8	39	19000	65	2200	470
Football Field	SSHS-B2905	SSHS-B2905-SUB-0.17-2	11/7/2019	856.07	0.17 - 2 ft	180-98520-1	Excavated	9100	0.76 J	6.1	100	0.41 J+	0.19 J	28000	18 J+		7.6	87 J	24000	94 J-	6100 J-	500 J+
Football Field	SSHS-B2906	SSHS-B2906-SUB-0.17-2	11/6/2019	855.46	0.17 - 2 ft	180-98355-3	Excavated	6900	0.57 J	5.4	66	0.36 J	0.057 J	28000	9.5 J+		6.2	50	17000	27	6700 J-	400 J+
Football Field	SSHS-B2907	SSHS-B2907-SUB-0.17-2	11/6/2019	855.77	0.17 - 2 ft	180-98355-3	Excavated	6300	0.56 J	5.6	66	0.36 J	0.049 J	9500	8.9 J+		5.7	34	17000	36	2700	510 J+
Football Field	SSHS-B2927	DUP-09	11/6/2019	855.16	0.17 - 2 ft	180-98355-3	Excavated	7500	4 J	4.8	65	0.32 J	0.069 J	27000	9.8 J+		6.1	34	17000	31	6200	390 J+
Football Field	SSHS-B2927	SSHS-B2927-SUB-0.17-2	11/6/2019	855.16	0.17 - 2 ft	180-98355-3	Excavated	6900	0.44 J	4.2	68	0.28 J	0.062 J	22000	9.8 J+		6	26	16000	27	5300	400 J+
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300	70.5 NE	4400	267 *E
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	9200	1 J	11	120	0.49 J	0.19 J	3300	19		7.3	64	21000	66	2000	430
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	12000	0.43 J	7.3	120	0.56	0.11 J	1800 J	17		9.4	14 J	20000	13 J	2900	520
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	11000	0.53 J	7	95	0.55	0.15 J	1700	15		9	26	21000	28	2800	530
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	9400	< 0.37 U	6.7	97	0.46	0.15 J	3000	17		7.8	19	18000	47	2700	510
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	8900	0.42 J	8.1	46	0.42 J	0.085 J	620	11		8	23	20000	11	2500	380
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	10000	< 0.4 U	6.4	93	0.5	0.097 J	1300	13		8.1	16	18000	11	2500	450
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	10000	0.61 J	6.4	84	0.47 J	0.084 J	1700	12		7.1	21	18000	15	2500	490
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	4300 J	< 0.4 UJ	4.6 J	41	0.2 J	0.18 J	52000 J	6.4 J		4 J	14 J	11000 J	7.5 J	25000 J	390
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	9600	< 0.38 U	6.7	99	0.49	0.076 J	1700	12		8.2	16	19000	10	2800	520
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	10000	0.47 J	7	91	0.51	0.14 J	8200	14		8.6	19	20000	20	6200	440
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	9300	0.38 J	5.8	80	0.46	0.082 J	3700 J-	14		7.6	14	18000	9.7	3500	460
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	10000	< 0.42 U	6.6	96	0.47 J	0.17 J	1700	19		7.9	19	18000	24	2600	510
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	11000	< 0.41 U	6.2	84	0.45 J	0.098 J	1400	16		8	24	20000	10	2800	470
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	13000	< 0.42 U	6.2	110	0.53	0.14 J	1700	25		9.1	15	22000	15	3300	520
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	9300	< 0.38 U	6.5	80	0.43 J	0.14 J	1600	21		8.1	17	18000	13	2500	500
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	8700	< 0.39 UJ	6.2	55	0.38 J	0.12 J	1700	15		7.1	27	17000	13	2500	460
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	9900	1 J	14	110	0.53	0.19 J	7000	18		10	31	41000	42	3500	700
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	9600	0.61 J	6.8	96	0.47 J	0.11 J	1700	13		7.1	18	17000	120	2200	450
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	10000	0.7 J	5.3	93	0.61	< 0.046 U	1400	12		5.7 J	27	16000	14	2200	270
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	9700	< 0.39 U	7.3	100	0.48	0.089 J	1800	13		7.7	30	18000	18	2400	480
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	9900	< 0.41 U	6.3	65	0.43 J	0.13 J	1100	18		7.6	19	18000	11	2500	410
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	12000	0.5 J	7.2	85	0.54	0.14 J	1700	24		9.3	18	21000	16	3000	530
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	9400	< 0.4 U	5.5	97	0.4 J	0.12 J	1900	12		6.2	18	15000	29	1900	660
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	8200	0.4 J	5.1	50	0.37 J	0.073 J	2900	11		5.9	18	16000	15	2400	420
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	9600	0.52 J	6	85	0.45	0.14 J	2200	16		7.6	18	18000	25	2700	550
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	10000	0.57 J	6.5	95	0.48	0.15 J	2300	18		7.9	17	19000	14	3000	500
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	11000	< 0.4 U	6.7	100	0.52	0.097 J	1400	14		8.5	14	18000	15	2500	530
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	11000	< 0.43 UJ	7.3	110	0.55	0.13 J	3000	15		9.8	17	20000	20	3100	550

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
				5 & 6	5 & 6													
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	0.062	19	710	< 0.62 U	< 0.13 U	86 J		< 0.25 U		16	80
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	0.051	25	570	< 0.59 U	< 0.12 U	53 J		< 0.24 U		14	120
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	0.024 J	26	850	< 0.61 U	< 0.13 U	81 J		< 0.25 U		15	70
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	0.019 J	20	670	< 0.57 U	< 0.12 U	71 J		< 0.23 U		11	60
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	0.22	140	950	< 0.59 U	< 0.12 U	350 J		0.27 J		17	280
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	0.18	190	900	< 0.61 U	< 0.12 U	560 J		< 0.25 U		14	200
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.008 U	16	640	< 0.55 U	< 0.11 U	120 J		< 0.22 U		10	59
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	0.018 J	21	690	< 0.59 U	< 0.12 U	58 J		< 0.24 U		14	130
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	1	31	660	< 0.62 U	< 0.13 U	69 J		< 0.25 U		28	150
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	0.095	22	680	< 0.59 U	< 0.12 U	63 J		0.27 J		16	140
Football Field	SSHS-B2649	SSHS-B2649-SUB-0.17-2	5/17/2019	856.28	0.17 - 2 ft	180-90275-1	Excavated	0.12	19		< 0.59 U	< 0.12 U	61 J		< 0.37 U		15	71
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	0.2	44		0.71 J	< 0.12 U	100 J		< 0.38 U		18	160
Football Field	SSHS-B2703	SSHS-B2703-SUB-0.17-2	5/19/2019	854.92	0.17 - 2 ft	180-90323-2	Excavated							37 J-				
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.038	20	910	< 0.61 U	< 0.12 U	< 31 U		< 0.38 U		18	83
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.53	28	990	< 0.62 U	< 0.13 U	< 31 U		< 0.38 U		16	84
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.81	25		< 0.64 U	< 0.13 U	620 U		< 0.4 U		16	83
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	0.62	22	890	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U		16	89
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	0.35 J	21	920	< 0.62 U	< 0.13 U	< 31 U		< 0.38 U		16	79
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	0.028 J	19	990	< 0.62 U	< 0.13 U	42 J		< 0.39 U		15	62
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.018 U	20	1100	< 0.62 U	< 0.13 U	45 J		< 0.39 U		15	65
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	0.26	19		0.7 J	< 0.11 U	100 J		< 0.35 U		14	91
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.18 J	22		< 0.61 U	< 0.12 U	590 U		< 0.38 U		20	94
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.063 J	23		< 0.6 U	< 0.12 U	580 U		< 0.37 U		17	88
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	0.12	24		< 0.66 U	< 0.14 U	55 J		< 0.41 U		18	68
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	0.063	18		< 0.65 U	< 0.13 U	44 J		< 0.4 U		15	81
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	0.13	19		< 0.65 U	< 0.13 U	49 J		< 0.4 U		16	95
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	0.048	21		< 0.61 U	< 0.13 U	53 J		< 0.38 U		15	67
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	0.1	15		< 0.65 U	< 0.13 U	51 J		< 0.4 U		14	95
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	0.052	23		< 0.68 U	< 0.14 U	48 J		< 0.43 U		17	62
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	0.25	57		0.96 J	< 0.13 U	120 J		< 0.39 U		17	160
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	0.12	29	930	< 0.61 U	< 0.12 U	< 31 U		< 0.38 U		16	130
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	0.015 J	23	750	< 0.61 U	< 0.13 U	59 J		< 0.38 U		14	80
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	0.02 J	26	610	1 J	< 0.11 U	100 J		< 0.35 U		9.5	66
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	0.019 J	41	480 J	0.84 J	< 0.12 U	68 J		< 0.37 U		14	78
Football Field	SSHS-B2734	PS-FD-22	5/18/2019	855.30	0.17 - 2 ft	180-90319-1	Excavated	0.15	3500	610	1.3	< 0.13 U	210 J		< 0.38 U		14	760
Football Field	SSHS-B2734	SSHS-B2734-SUB-0.17-2	5/18/2019	855.30	0.17 - 2 ft	180-90319-1	Excavated	0.14	2600	660	0.81 J	< 0.13 U	210 J		< 0.41 U		15	580
Football Field	SSHS-B2801	SSHS-B2801-SUB-0.17-2	5/21/2019	856.07	0.17 - 2 ft	180-90380-1	Excavated	0.21 J	26	1100	< 0.63 U	< 0.13 U	71 J		< 0.39 U		18	77
Football Field	SSHS-B2802	SSHS-B2802-SUB-0.17-2	5/16/2019	855.97	0.17 - 2 ft	180-90231-1	Excavated	1.1	66	860	< 0.62 U	< 0.13 U	610 U		< 0.39 U		15	110
Football Field	SSHS-B2803	SSHS-B2803-SUB-0.17-2	5/14/2019	855.69	0.17 - 2 ft	180-90048-1	Excavated	0.065	37	720	< 0.65 U	< 0.13 U	58 J		< 0.41 U		14	75
Football Field	SSHS-B2905	SSHS-B2905-SUB-0.17-2	11/7/2019	856.07	0.17 - 2 ft	180-98520-1	Excavated	0.024 J	40 J-	890	< 0.53 U	< 0.11 U	72 J		< 0.33 U		18	130
Football Field	SSHS-B2906	SSHS-B2906-SUB-0.17-2	11/6/2019	855.46	0.17 - 2 ft	180-98355-3	Excavated	0.096 J+	58 J	700	< 0.56 U	< 0.11 U	74 J		< 0.35 U		16	74 J+
Football Field	SSHS-B2907	SSHS-B2907-SUB-0.17-2	11/6/2019	855.77	0.17 - 2 ft	180-98355-3	Excavated	0.062	53	650	< 0.56 U	< 0.12 U	< 66 U		< 0.35 U		13	73
Football Field	SSHS-B2927	DUP-09	11/6/2019	855.16	0.17 - 2 ft	180-98355-3	Excavated	0.29	20	820	< 0.54 U	< 0.11 U	83 J		< 0.34 U		15	84
Football Field	SSHS-B2927	SSHS-B2927-SUB-0.17-2	11/6/2019	855.16	0.17 - 2 ft	180-98355-3	Excavated	0.36	30	680	< 0.5 U	< 0.1 U	59 J		< 0.31 U		13	72
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated	0.082	84 *E	494	1.3	< U	132		< U		9.4	103 NE
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	0.083	23	770	< 0.71 U	< 0.14 U	74 J		< 0.44 U		17	89
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	0.032 J	21	1400	< 0.66 UJ	< 0.13 U	40 J		< 0.41 U		16	59
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	0.065	24	1100	< 0.58 U	< 0.12 U	36 J		< 0.36 U		15	65
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	0.12	18	970	< 0.56 U	< 0.11 U	< 28 U		< 0.35 U		14	65
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.015 U	19	1000	< 0.61 U	< 0.12 U	39 J		< 0.38 U		15	62
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	0.02 J	19	1100	< 0.61 U	< 0.12 U	31 J		< 0.38 U		14	51
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	0.039	18	750	< 0.63 U	< 0.13 U	46 J		< 0.39 U		15	54
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	0.034 J	10 J	750	< 0.6 U	< 0.12 U	92 J		< 0.38 U		7.8 J	44
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	0.026 J	19	870	< 0.58 U	< 0.12 U	47 J		< 0.36 U		13	61
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	0.029 J	18	1000	< 0.6 U	< 0.12 U	62 J		< 0.37 U		17	66
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.016 U	17	940	< 0.56 U	< 0.11 U	69 J		< 0.35 U		15	50
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	0.035 J	19	1100	< 0.63 U	< 0.13 U	39 J		< 0.39 U		15	61
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.017 U	19	800	< 0.62 U	< 0.13 U	36 J		< 0.39 U		14	58
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	0.046	23	940	< 0.64 U	< 0.13 U	54 J		< 0.4 U		18	65
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	0.034	18	930	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U		13	53
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	0.19	17	820	< 0.59 U	< 0.12 U	43 J		< 0.37 U		13	61
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	0.25	25	820	< 0.61 U	< 0.13 U	53 J		< 0.38 U		15	78
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	0.046	16	970	< 0.64 U	< 0.13 U	37 J		< 0.4 U		14	56
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	0.025 J	15	690	< 0.65 U	< 0.13 U	45 J		< 0.4 U		14	49
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	0.035	19	810	< 0.59 U	< 0.12 U	48 J		< 0.37 U		14	65
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	0.021 J	17	940	< 0.62 U	< 0.13 U	37 J		< 0.38 U		16	54
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	0.053	21	1300	< 0.59 U	< 0.12 U	40 J		< 0.37 U		17	79
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	0.1	14	730	< 0.61 U	< 0.13 U	< 31 U		< 0.38 U		14	53
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	0.029 J	14	820	< 0.54 U	< 0.11 U	< 27 U		< 0.34 U		12	50
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	0.12	17	< 60 U	< 0.56 U	< 0.11 U	45 J		< 0.35 U		14	64
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	0.15	18	1000	< 0.59 U	< 0.12 U	47 J		< 0.37 U		15	68
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	0.035 J	18	1000	< 0.61 U	< 0.12 U	41 J		< 0.38 U		15	55
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	0.036 J	22	960	< 0.65 UJ	< 0.13 U	39 J		< 0.41 U		12	63

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**	**Lead**	**Magnesium**	**Manganese**
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential									16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater									16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity									100	2000		20		100					1000		
				5 & 6	5 & 6																
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]														
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	11000	< 0.43 U	7.1	120	0.5	0.11 J	1500	13		7.3	17	18000	15	2400	590
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	12000	0.72 J	7.2	96	0.53	0.089 J	2100	16		8.8	21	21000	20	3000	480
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	10000	0.61 J	7.9	94	0.52	0.12 J	1700	14		9.1	31	20000	21	2600	780
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	9900	0.49 J	7.6	110	0.49	0.13 J	4400	17		7.4	27	19000	33	2500	490
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	11000	< 0.41 U	6.9	130	0.38 J	< 0.044 U	680	15		5 J	22	25000	25	2200	210
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	9900	0.48 J-	7.1	140	0.47 J	0.15 J	2800	13		7.3	22	18000	34	2400	900
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	12000	< 0.4 U	7.8	120	0.54	0.15 J	4800	18		8.9	32	21000	23	3000	620
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	9300	0.41 J	7.3	93	0.39 J	0.1 J	2600 J	12		6.3	25	16000	54 J	1900	600
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	9400	< 0.39 U	6.2	93	0.45 J	0.14 J	6500	14		7.5	24	17000	31	2600	540
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	11000	0.45 J	7.4	150	0.52	0.14 J	10000	17		9.2	19	22000	25	3100	700
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	9000	< 0.4 U	6.7	98	0.43 J	0.2 J	19000	13		6.9	31	17000	66	5600	490
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	9400	0.55 J	6.1	77	0.48	0.14 J	6000	14		7.3	21	18000	37	2600	400
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	7500	0.82 J	8	93	0.5	0.13 J	7700	13		6.2	27	18000	40	2000	310
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	11000	0.48 J	7.1	110	0.57	0.1 J	1600	13		9.2	15	21000	14	2900	520
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	12000	0.66 J	8.2	94	0.54 J	0.092 J	2000 J	14		9.5	21	22000	18	3100	530
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	12000	0.55 J	11	110	0.62	0.13 J	2600	14		9.3	19	22000	51	2900	520
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	11000	0.55 J	6.6	93	0.5	0.11 J	4200	13		8.6	20	19000	14	3400	850
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	12000	< 0.41 U	7.9	110	0.59	0.072 J	1800	14		9.7	28 J	22000	16	3100	560
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	11000	0.54 J	7.4	140	0.56	0.19 J	5200 J	20		8.7	28	20000	31	3000	540
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	10000	0.61 J	7.8	120	0.54	0.14 J	9800	18		7.7	32	20000	43	2800	490
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	11000	0.69 J	8.1	120	0.52	0.17 J	6900	20		10	30	42000	79	3200	880
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	11000	< 0.39 UJ	7.1	120	0.54	0.38 J	1900	16		9	21	20000	19	2800	570
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	9300	0.72 J	14	94	0.45 J	0.22 J	6100	18		7.5	39	26000	61	2700	560
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	8600	< 0.39 UJ	4.7	80	0.38 J	0.11 J	1900	12		6.6	14	17000	15	2200	430
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	12000	0.49 J	8.2	110	0.59	0.15 J	2700	16		10	20	22000	25	3200	580
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	13000	0.43 J	7.9	92	0.64	0.11 J	2100	15		10	16	24000	14	3700	550
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	9500	0.47 J	7.1	100	0.52	0.15 J	3300	13		8.5	17	20000	22	3000	540
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	9800	< 0.38 U	6.6	98	0.5	0.12 J	4000	15		8.5	16	19000	16	3100	490
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	11000	0.51 J	6.7	94	0.52	0.075 J	1500	14		8.2	16	21000	12	2700	470
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	12000	< 0.42 U	7	110	0.58	0.11 J	1600	15		9.2	15	20000	14	2900	550
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	11000	< 0.42 UJ	7.7	110	0.54	0.15 J	1700	14		8.4	20	20000	29	2600	510
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	10000	1 J	9.3	120	0.54	0.33 J	8300 J	19		8.8	69	26000	110 J	2600	490
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	10000	0.81 J	7.7	110	0.51 J	0.16 J	6400	18		7.8	51	20000	64	2800	540
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	8900	0.69 J	7.2	120	0.44 J	0.18 J	8700	28		7.5	34	19000	62	2800	490
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	11000	< 0.4 U	8.9	110	0.53	0.18 J	16000	21		9.2	47	21000	58	3200	470
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	9700	< 0.39 U	6.6	90	0.56	0.13 J	14000	15		8.8	16	20000	17	8100	470
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	11000	< 0.39 U	6.3	93	0.47	0.12 J	4100	14		8.4	17	20000	19	3100	470
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	11000	< 0.42 U	7.2	110	0.48 J	0.12 J	2200	14		8.4	33	21000	26	2800	600
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	9900	0.56 J	8.2	86	0.45 J	0.074 J	1400	12		6.8	15	19000	16	2400	300
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	12000	0.61 J	8.1	110 J-	0.57	0.14 J	2000	14		8.9	17	21000	18	2700 J-	520
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	9100	0.72 J	6.5	97	0.46 J	0.11 J	1600	11		7.6	18	17000	20	2300	480
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	11000	0.58 J	7.8	93	0.46 J	0.088 J	1400	13		7.6	26	20000	30	2500	500
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	9100	< 0.4 U	7	71	0.41 J	0.11 J	1300	12		6.4	32	18000	23	2100	390
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	9700	0.61 J-	11	92 J	0.5 J	0.15 J	6600 J	13		7.5	24	20000	26	2800	450
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	10000	0.5 J	8.8	87	0.49	0.11 J	3000	12		7.6	23	20000	25	2900	460
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	9000	0.86 J	6.3	90	0.43 J	0.12 J	1800	11		6.3	14	16000	17	2000	400
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	8000	0.54 J	6.6	91	0.42 J	0.16 J	12000	12		7.6	17	16000	21	4000	470
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	10000	< 0.43 U	7.7	120	0.5	0.39 J	3500	17		8.3	18	19000	24	2500	530
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	10000	0.41 J	7	110	0.52	0.14 J	2100	14		8.6	18	19000	25	2800	500
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	8600	0.49 J	7.1	180	0.49	0.24 J	7300	17		7.8	41	18000	47	3000	450
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	8000	< 0.36 U	5.4	65	0.33 J	0.16 J	44000	11		7.1	24	19000	12	11000	460
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	4800	< 0.32 U	3.3	47	0.19 J	0.1 J	20000	6.7		3.7 J	16	11000	44	4200	340
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	4800	< 0.28 UJ	4.9 J-	64 J	0.22 J	0.14 J	16000	6.5 J-		3.9 J	17 J-	12000	52 J	3900 J-	430
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	4800	< 0.28 UJ	4.9 J-	64 J	0.22 J	0.14 J	16000	6.5 J-		3.9 J	17 J-	12000	52 J	3900 J-	430
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	4100	< 0.35 U	3.7	33	0.18 J	0.075 J	19000	5.1		3.5 J	12	9400	17	6200	240
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	3200	< 0.37 U	2.3	29	0.12 J	0.074 J	20000	4.1		2.6 J	13	7700	9.9	4100	230
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	3200	< 0.37 U	2.3	29	0.12 J	0.074 J	20000	4.1		2.6 J	13	7700	9.9	4100	230
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	7300	< 0.38 U	4.4	51	0.27 J	0.14 J	29000	9.5		6	22	16000	15	7200	340
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	3500	< 0.3 U	2.8	28	0.14 J	0.082 J	31000	5.7		3 J	15	8100	11	3500	250
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	6000	< 0.38 U	4.5	43	0.22 J	0.1 J	18000	7.4		5.4 J	31	19000	14	6200	260
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	3700	< 0.37 U	3.3	28	0.15 J	0.09 J	20000	4.9		3 J	12	8700	9.8	4400	230
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	6200	< 0.31 UJ	4.8	52	0.26 J	0.14 J	27000	8.8		5.1	19	14000	94 J	5800 J	380
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	5000	< 0.37 U	4.3	39	0.19 J	0.12 J	36000	6.5		4.6 J	16	12000	10	8700	440
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	1300	< 0.37 U	1.6	50	0.059 J	0.048 J	11000	2.4		1.2 J	5.7	3500	5	1500	80
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	8100	< 0.38 UJ	6.3	70 J	0.38 J	0.15 J	4400 J	10		6.8	27 J-	17000	35 J	2600 J	560
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	8600	< 0.38 U	6.2	93	0.47 J	0.17 J	5800 J	12		7.3	31	17000	37	2800	470
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	4800	< 0.38 U	3.9	35	0.24 J	0.075 J	26000 J	6.9		6.4	13	12000	7.1 J	4600 J	270
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	6500	< 0.28 U	5.9	64	0.33	0.17 J	4100	9.1		6.1	13	13000	31	2500	410
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	7400	< 0.37 U	6	210 J	0.37 J	0.15 J	12000	9.1		5.3 J	20	14000	54 J	2500	390
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	5400	< 0.27 U	4	39	0.21 J	0.1 J	22000	7.4		5	22	14000	11 J	3800	350
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	8900	< 0.37 U	9	100	0.42 J	0.19 J	11000	11		8.6	22	20000	24	4500	720
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	7700	< 0.4 U	6.3	89	0.43 J	0.17 J	2600	10		5.2 J	17	16000	28	1400	280
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	9300	0.41 J	7.9	120	0.51	0.22 J	2600	14		7	31	19000	36	2000	410

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
				5 & 6	5 & 6													
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	0.019 J	17	850	< 0.65 U	< 0.13 U	< 33 U		< 0.4 U		16	67
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	0.025 J	21	870	< 0.62 U	< 0.13 U	55 J		< 0.39 U		16	64
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	0.026 J	20	740	< 0.59 U	< 0.12 U	53 J		< 0.37 U		15	69
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	0.054	19	860	1 J	< 0.12 U	65 J		< 0.37 U		15	71
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	0.053	14	560 J	0.72 J	< 0.13 U	49 J		< 0.38 U		18	48
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	0.059	18	780	< 0.63 U	< 0.13 U	52 J		< 0.39 U		15	70 J+
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	0.076	20	1100	< 0.6 U	< 0.12 U	51 J		< 0.37 U		17	70
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	0.12 J	14	690	< 0.59 U	< 0.12 U	54 J		< 0.37 U		15	77
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	0.26	19	850	0.59 J	< 0.12 U	87 J		< 0.37 U		14	65
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	0.18	22	980	< 0.59 U	< 0.12 U	79 J		< 0.37 U		16	65
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	1.3	21	920	0.68 J	< 0.12 U	110 J		< 0.38 U		15	76
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	0.69	19	740	< 0.59 U	< 0.12 U	69 J		< 0.37 U		14	60
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	2.4 J	18	980	< 0.59 U	< 0.12 U	140 J		< 0.37 U		14	55
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	0.05	20	790	< 0.58 UJ	< 0.12 U	39 J		< 0.36 U		14	57
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	0.045	20	730	< 0.63 U	< 0.13 U	48 J		< 0.39 U		16	63
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	0.14	21	1200	< 0.63 U	< 0.13 U	70 J		< 0.39 U		18	66
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	0.025 J	18	910	< 0.59 U	< 0.12 U	40 J		< 0.37 U		16	57
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	0.028 J	23	930	< 0.62 U	< 0.13 U	49 J		< 0.38 U		16	66
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	0.26	22	1100	< 0.61 U	< 0.12 U	51 J		< 0.38 U		15	81
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	0.14	24	1000	< 0.63 U	< 0.13 U	86 J		< 0.39 U		16	79
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	0.053	31	1000	0.7 J	< 0.13 U	98 J		< 0.39 U		23	73
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	0.04	21	1200	< 0.59 U	< 0.12 U	40 J		< 0.37 U		16	64
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	0.3	78	900	< 0.6 U	< 0.12 U	65 J		< 0.37 U		16	100
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	0.21 J	15	730	< 0.6 U	< 0.12 U	< 30 U		< 0.37 U		12	48 J+
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	1.2	24	1100	< 0.6 U	< 0.12 U	61 J		< 0.37 U		17	74
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.016 U	24	1000	< 0.62 U	< 0.13 U	53 J		< 0.38 U		18	64
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	0.058	19	700	< 0.6 U	< 0.12 U	58 J		< 0.37 U		13	58
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	0.12	19	790	< 0.58 U	< 0.12 U	40 J		< 0.36 U		13	56
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	0.028 J	18	700	0.68 J	< 0.13 U	38 J		< 0.39 U		16	53
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	0.028 J	20	1100	< 0.63 U	< 0.13 U	< 32 U		< 0.39 U		16	57
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	0.027 J	21	990	< 0.64 U	< 0.13 U	38 J		< 0.4 U		15	58
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	0.1	32	900	< 0.59 U	< 0.12 U	80 J		< 0.37 U		19	100
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	0.14	24	850	< 0.61 U	< 0.12 U	88 J		< 0.38 U		17	90
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	0.16	22	790	< 0.6 U	< 0.12 U	< 30 U		< 0.37 U		17	83
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	0.07	86	1000	0.68 J	< 0.12 U	83 J		< 0.37 U		17	82
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	0.069	20	970	0.69 J	< 0.12 U	150 J		< 0.37 U		17	51
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	0.46	20	< 63 U	< 0.6 U	< 0.12 U	50 J		< 0.37 U		14	60
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	0.042	23	920	< 0.63 U	< 0.13 U	47 J		< 0.39 U		16	79
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	0.048 J	16	640	0.76 J	< 0.13 U	40 J		< 0.38 U		14	51
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	0.035 J	20	980	< 0.64 U	< 0.13 U	49 J		< 0.4 U		16	59 J-
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	0.04	23	1000	< 0.64 U	< 0.13 U	39 J		< 0.4 U		13	56
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	0.028 J	19	750	< 0.61 U	< 0.13 U	48 J		< 0.38 U		16	61
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	0.026 J	18	570 J	< 0.6 U	< 0.12 U	56 J		< 0.37 U		16	66
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	0.078	18	910	0.94 J	< 0.14 U	79 J		< 0.42 U		16	59
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	0.031 J	17	680	< 0.64 U	< 0.13 U	60 J		< 0.4 U		15	59
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	0.022 J	15	880	< 0.65 U	< 0.13 U	56 J		< 0.41 U		13	46
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	0.036	18	970	< 0.6 U	< 0.12 U	59 J		< 0.37 U		13	59 J+
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	0.093	19	1000	< 0.65 U	< 0.13 U	51 J		< 0.4 U		14	71
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	0.14	20	1000	< 0.62 U	< 0.13 U	< 31 U		< 0.38 U		15	62
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	0.12 J	20	920	< 0.56 U	0.29 J	88 J		< 0.35 U		13	97
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	0.066	19	740	0.76 J	< 0.11 U	96 J		< 0.34 U		12	75
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	0.061	11	370 J	< 0.49 U	< 0.1 U	< 58 U		< 0.31 U		13	40
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	0.063	12 J-	370 J	< 0.42 UJ	< 0.087 UJ	< 50 UJ		< 0.26 UJ		11 J-	48 J-
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	0.063	12 J-	370 J	< 0.42 UJ	< 0.087 UJ	< 50 UJ		< 0.26 UJ		11 J-	48 J-
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	0.12	8.8	390 J	< 0.52 U	< 0.11 U	< 62 U		< 0.33 U		8.5	35
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	0.076	8.6	270 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		11	29
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	0.076	8.6	270 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		11	29
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	0.073	16	600	0.72 J	< 0.12 U	72 J		< 0.35 U		11	58
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	0.032 J	8.9	260 J	0.45 J	< 0.092 U	< 53 U		< 0.28 U		8.8	29
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	0.11	15	420 J	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		14	48
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	0.088	9.3	340 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		10	33
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	0.35	14	540	0.68 J	< 0.095 U	55 J		< 0.29 U		13	58 J-
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	0.022 J	12	480 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		11	49
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	< 0.026 U	3.6 J	170 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		4.9 J	16
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	0.49 J	20	560	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		12	61 J-
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	0.065	21	690	< 0.58 UJ	< 0.12 U	< 68 U		< 0.36 U		14	61
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	< 0.021 UJ	12	420 J	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		7.2	30
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	0.077	13	550	< 0.43 U	< 0.088 U	< 50 U		< 0.27 U		10	60
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	0.97 J	13	630	< 0.56 U	< 0.11 U	72 J		< 0.35 U		13	120 J
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	0.34 J	15	440	< 0.41 U	< 0.084 U	55 J		< 0.26 U		8.4	46
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	0.047	20	820	< 0.56 U	< 0.11 U	< 65 UJ		< 0.35 U		13	92
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	0.045	14	590	0.65 J	< 0.12 U	89 J		< 0.37 U		12	41
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	0.04	19	950 J	< 0.59 UJ	< 0.12 U	73 J		< 0.37 U		16	56

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
				5 & 6	5 & 6																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	3800	< 0.33 U	2.7	28	0.12 J	0.088 J	77000	4.9		3.3 J	13	9100	8.1	36000	310
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	8000	< 0.41 U	5.6	87	0.41 J	0.15 J	16000	9.9		7.2	13	16000	12	6200	500
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	14000	< 0.47 U	7.1	100	0.61	0.057 J	950	14		8.6	19	21000	16	2600	530
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	11000	0.66 J	7	110	0.52	0.14 J	4300	13		8.8	19	20000	18	2800	610
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	9100	0.61 J	7.4	87	0.45	0.17 J	2900	11		7.2	23	19000	29	3200 J-	420
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	11000	0.66 J	7.2	120	0.53	0.11 J	2300	13		9.2	14	20000	15	3000	570
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	9800	0.52 J	7	98	0.46	0.11 J	2100	13		7.9	16	18000	21	2500	490
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	6800	0.7 J	9.5	130	0.46 J	0.37 J	2400	15		6.1 J	80	21000	74	1500	310
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	856.97	0.17 - 2 ft	180-100148-4	Excavated	5900	< 0.46 U	5.4	79	0.3	0.23 J	12000	9.5		8.4	31	47000	30	2000	240
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated	8700	< 0.3 UJ	5.4	79	0.4	0.16 J	6100	16		6.9	17	16000	22	2600	400
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	856.64	0.17 - 2 ft	180-100148-4	Excavated	7900	< 0.28 U	5.4	66	0.37	0.15 J	3700	12		6.2	16	15000	30	2600	430
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	856.17	0.17 - 2 ft	180-100148-4	Excavated	7000	< 0.28 U	4.6	65	0.5	0.14 J	18000	9.1		5.5	25	13000	25	3100	240
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	856.62	0.17 - 2 ft	180-100148-2	Excavated	9400	0.61 J	5.9	75	0.5	0.14 J	12000	14		7.3	20	18000	31	5200	410
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	855.76	0.17 - 2 ft	180-100148-2	Excavated	7200	0.5 J	6.1	60	0.42 J	0.12 J	17000	9.3		5.7 J	22	17000	24	2500	340
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	856.21	0.17 - 2 ft	180-100148-3	Excavated	8600	< 0.32 UJ	6.1	65	0.43	0.14 J	7300	12		6.4	24	17000	34	2400	350
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	856.48	0.17 - 2 ft	180-100148-3	Excavated	11000	< 0.32 UJ	6.7	92 J	0.57	0.18 J	12000	20		7.5	14	22000	12	7300 J	400
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	855.88	0.17 - 2 ft	180-100148-3	Excavated	9400	< 0.3 UJ	5.8	82	0.42	0.17 J	17000	11		6.9	25	17000	41	3500	600
Football Field	SSHS-B3456	DUP09	7/28/2020	855.34	0.17 - 2 ft	180-108872-2	Excavated	7800	< 0.33 U	6.5	59	0.36 J	0.13 J	8200	11		6.1	30	19000	29	3100	480
Football Field	SSHS-B3456	SSHS-B3456-SUB-0.17-2	7/28/2020	855.34	0.17 - 2 ft	180-108872-2	Excavated	7600	< 0.23 U	5.9	63	0.32	0.15 J	13000	15		6.7	35	24000	35	4000	610
Football Field	SSHS-B3457	SSHS-B3457-SUB-0.17-2	7/28/2020	855.82	0.17 - 2 ft	180-108872-2	Excavated	9300	< 0.29 U	6.9	90	0.47	0.15 J	33000	12		7.5	26	17000	39	3600	460
Football Field	SSHS-B3458	SSHS-B3458-SUB-0.17-2	7/28/2020	856.14	0.17 - 2 ft	180-108872-2	Excavated	6500	< 0.3 U	5.5	67	0.27 J	0.14 J	23000	9.6		6.1	36	18000	29	5100	400
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	9700	< 0.35 UJ	5.9	77	0.41	0.11 J	15000	12		7.9	25	20000	16	5000 J-	400
Football Field	SSHS-B3460	SSHS-B3460-SUB-0.17-2	7/28/2020	855.83	0.17 - 2 ft	180-108872-2	Excavated	6500	1.1	10	190	0.38	0.28 J	9400	20		6.5	77	30000	140	2300	350
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	9600	< 0.34 U	5.9	100	0.43	0.22 J	2400	11		8.4	15	18000	23	2600	730
Football Field	SSHS-B3462	DUP11	7/28/2020	855.77	0.17 - 2 ft	180-108872-2	Excavated	10000	< 0.34 U	6.6	95	0.46	0.12 J	5800	13		7.2	31 J	19000	130 J	2900	420
Football Field	SSHS-B3462	SSHS-B3462-SUB-0.17-2	7/28/2020	855.77	0.17 - 2 ft	180-108872-2	Excavated	9800	< 0.33 U	6.8	90	0.43	0.12 J	6400	12		7.1	83 J	19000	44 J	2900	440
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated	8400	0.31 J	7.3	93	0.39	0.16 J	6700	15		8.2	54	22000	49	2700	560
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	13000	< 0.34 U	8.1	100	0.57	0.15 J	2300	15		10	17	22000	19	3200	670
Football Field	SSHS-B3465	SSHS-B3465-SUB-0.17-2	7/28/2020	855.46	0.17 - 2 ft	180-108872-2	Excavated	8000	< 0.23 U	7.5	78	0.33	0.15 J	32000	16		7.4	33	24000	37	5800	410
Football Field	SSHS-B3466	SSHS-B3466-SUB-0.17-2	7/28/2020	855.76	0.17 - 2 ft	180-108872-2	Excavated	9800	0.26 J	6	84	0.42	0.12 J	8800	13		7.5	36	20000	32	3400	440
Football Field	SSHS-B3467	SSHS-B3467-SUB-0.17-2	7/28/2020	855.68	0.17 - 2 ft	180-108872-2	Excavated	11000	< 0.35 U	7.5	250	0.51	0.23 J	5100	15		8.9	24	21000	35	3500	650
Football Field	SSHS-B3468	SSHS-B3468-SUB-0.17-2	7/28/2020	855.93	0.17 - 2 ft	180-108872-2	Excavated	7800	< 0.23 U	6.8	55	0.33	0.1 J	14000	9.9		6.6	25	17000	22	4800	350
Football Field	SSHS-B3469	SSHS-B3469-SUB-0.17-2	7/28/2020	855.50	0.17 - 2 ft	180-108872-2	Excavated	7500	0.93 J	7.1	140	0.37 J	0.23 J	8200	15		6.2	72	36000	150	1900	370
Football Field	SSHS-B3470	SSHS-B3470-SUB-0.17-2	7/28/2020	855.73	0.17 - 2 ft	180-108872-2	Excavated	8600	2.3	7.8	100	0.4	0.17 J	12000	13		7.3	68	21000	74	3800	390
Football Field	SSHS-B3470	DUP14	7/28/2020	855.73	0.17 - 2 ft	180-108872-2	Excavated	7500	0.26 J	4.6	63	0.31	0.12 J	50000	12		5	41	15000	26	4400	330 J
Football Field	SSHS-B3471	SSHS-B3471-SUB-0.17-2	7/28/2020	856.03	0.17 - 2 ft	180-108872-2	Excavated	7900	< 0.32 UJ	6.1	65	0.34 J	0.12 J	45000	11		5.9	32	16000	40	3900	380
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	6400	7.7	4.9	54	0.32 J	0.22 J	60000	8.9		5.3	36	13000	36	5300	350
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	6300	< 0.29 U	5.9	61	0.28 J	0.13 J	21000	8.7		5.5	35	16000	29	3400	390
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	7900	< 0.32 U	7	81	0.38	0.13 J	15000	11		6.7	31	17000	38	2900	420
Football Field	SSHS-B3474	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	0.17 - 2 ft	180-108826-1	Not Excavated	5100	< 0.22 U	3.4	39	0.22 J	0.093 J	25000	7.3		5.3	24	12000	14	4100	270
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	7800	0.31 J	6.2	71	0.32	0.25 J	19000	13		6.4	52	22000	50	4300	450
Football Field	SSHS-B3476	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	0.17 - 2 ft	180-108826-1	Not Excavated	7200	0.56 J	6.9	77	0.31 J	0.19 J	32000	16		6.2	53	20000	76	4200	350
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	6100	0.82 J	4.6	45	0.25 J	0.16 J	35000	8.2		5.3	28	14000	27	4800	330
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	10000	0.5 J	6.4	100	0.49	0.16 J	2100	13		8.3	15	18000	18	2600	580
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	11000	0.63 J	6.4	97	0.49	0.15 J	2100	14		8.4	15	19000	18	2700	570
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	10000	1.3	8	140	0.53	0.84	4400	16		9.2	76	19000	110	2900	540
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	9000	0.83 J	9.7	110	0.47	0.58 J	4000	13		6.7	26	17000	130	2300	500
Football Field	SSHS-B3501	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	0.17 - 2 ft	180-110264-1	Not Excavated													9.5		
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-0.17-2	1/25/2021	855.86	0.17 - 2 ft	180-116404-1	Excavated	9600	0.45 J	8	85	0.46	0.2 J	2100	44	< 0.25 U	9.1	370	25000	49	2600	590
Northern Athletic Field	SSHS-B3511A	SSHS-B3511-SUB-0.17-2	1/13/2021	856.97	0.17 - 2 ft	180-115927-1	Excavated	13000	0.78 J	7.3	120	0.76	0.15 J	10000	21		10	24	25000	32	7200	520
Northern Athletic Field	SSHS-B3512A	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	0.17 - 2 ft	180-115927-1	Not Excavated	12000	1.1 J	9.4	110	0.63	0.16 J	6600	17		9.8	41	25000	37	3800	530
Northern Athletic Field	SSHS-B3513	SSHS-B3513-SUB-0.17-2	1/13/2021	856.86	0.17 - 2 ft	180-115927-1	Excavated	12000	0.75 J	7.8	120	0.61	0.17 J	2500	16		9.4	17	21000	16	3200	580
Northern Athletic Field	SSHS-B3514	SSHS-B3514-SUB-0.17-2	1/13/2021	856.41	0.17 - 2 ft	180-115927-1	Excavated	11000	0.73 J	7.1	110	0.57	0.16 J	4700	15		9.1	15	20000	17	3700	510
Northern Athletic Field	SSHS-B3515	SSHS-B3515-SUB-0.17-2	1/13/2021	856.77	0.17 - 2 ft	180-115927-1	Excavated	8800	0.68 J	7.3	99	0.44	0.17 J	16000	12		7.1	23	18000	30	3400	440
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	10000	0.64 J	6.6	120	0.48 J	0.14 J	1400	14		7.7	15	18000	17	2400	520
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated		< 1.13 U	5.91	80.4	< 0.566 U	< 0.566 U		10.9		6.43	15.6		24.2		
Northern Athletic Field	SSHS-B36	12 Sep 00B36 0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated		< 1.06 U	8.98	50.9	< 0.532 U	< 0.532 U		8.74		6.32	24.9		14.3		
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-0.17-2	1/29/2021	856.95	0.17 - 2 ft	1801166651	Excavated	5500	< 0.29 U	4.6	71	0.23 J	0.13 J	60000	7.2		4.2	22	12000	57	3200	310
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	5300	< 0.33 U	4.4	36	0.22 J	0.11 J	43000	7.2		4.4 J	18	12000	11	6700	320
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-0.17-2	1/29/2021	856.79	0.17 - 2 ft	180-116665-1	Excavated	8200	< 0.29 U	6.5	91	0.36	0.22 J	12000	18		6	29	16000	57	3300	360
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-0.17-2	1/29/2021	856.79	0.17 - 2 ft	180-116665-1	Excavated	8200	< 0.29 U	6.5	91	0.36	0.22 J	12000	18		6	29	16000	57	3300	360
Northern Athletic Field	SSHS-B3647	SSHS-B3647-SUB-0.17-2	1/29/2021	856.70	0.17 - 2 ft	180-116665-1	Excavated	5400	< 0.24 U	3.4	44	0.2 J	0.07 J	28000	9.7		3.8	16	11000	10	3900	290
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated		< 1.1 U	3.5	59.4	< 0.54 U	< 0.54 U		5.8		8.3	6.8 N		9.7		
Northern Athletic Field	SSHS-B37	12 Sep 00B37 0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated		< 1.04 U	2.56	39.1	< 0.521 U	< 0.521 U		6.24		< 5.21 U	18.4		5.49		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated		< 1.16 U	5.16	108	0.588	< 0.578 U		20.7		9.66	18.8		23.2		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated		< 1.11 U	5.76	87.2	< 0.557 U	< 0.557 U		11.6		7.03	26.5		29.4		
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	0.17 - 2 ft	180-124920-1	Not Excavated	6000	0.53 J	24	180	0.4	0.12 J	27000	12		7.2	50	25000	60	3900	530
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	7700	< 0.32 U	6.3	60	0.3 J	0.094 J	27000	11		6.2	19	18000	15	9500	460
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated		< 1.26 U	5.03	89.3	< 0.631 U	< 0.631 U		21.5		8.11	14.8		15.3		
Northern Athletic Field	SSHS-B39	12 Sep 00B39 0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated		< 1.09 U	5.16	83.8	< 0.554 U	< 0.554 U		10.1		7.07	34.4		56		
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	10000	< 0.38 U	6.0	110	0.45	0.15 J	1800	16		7.3	17	18000	18	2400	500
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	8500	< 0.39 U	5.6	95	0.38 J	0.14 J	2300	14		6.2	17	17000	25	2300	410
EHS Building	SSHS-B3S	B3-C1-Composite	7/25/2007	855.70	0.5 - 2 ft	NA	Not Excavated															

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
				5 & 6	5 & 6													
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	< 0.023 U	11	380 J	0.82 J	< 0.1 U	110 J		< 0.31 U		14	38
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	0.038 J	16	760	< 0.62 U	< 0.13 U	< 72 U		< 0.38 U		12	48
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	0.026 J	17	680 J	0.79 J	< 0.15 U	39 J		< 0.44 U		20	55
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	0.019 J	20	1100	< 0.62 U	< 0.13 U	44 J		< 0.39 U		14	62
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	0.043	21	860	< 0.58 U	< 0.12 U	45 J		< 0.36 U		15	75 J-
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	0.022 J	20	1100	< 0.67 U	< 0.14 U	47 J		< 0.42 U		14	58
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	0.03 J	18	870	< 0.58 U	< 0.12 U	42 J		< 0.36 U		14	58
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	0.047	27	700	0.67 J	< 0.13 U	100 J		< 0.4 U		17	100
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	856.97	0.17 - 2 ft	180-100148-4	Excavated	0.95	92	560	1.5	< 0.071 U	63 J		0.23 J		14	54
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated	0.18	17	1100	< 0.45 U	< 0.092 U	97 J		0.28 J		13	57
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	856.64	0.17 - 2 ft	180-100148-4	Excavated	0.52	17	870	< 0.42 U	< 0.086 U	63 J		0.39 J		12	53
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	856.17	0.17 - 2 ft	180-100148-4	Excavated	1.4	31	1300	0.95	< 0.085 U	160 J		< 0.26 U		14	57
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	856.62	0.17 - 2 ft	180-100148-2	Excavated	0.43	18	850	< 0.61 U	< 0.12 U	74 J		< 0.38 U		16	58
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	855.76	0.17 - 2 ft	180-100148-2	Excavated	1	24	610	< 0.59 U	< 0.12 U	74 J		< 0.37 U		12	51
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	856.21	0.17 - 2 ft	180-100148-3	Excavated	0.3	17	860	< 0.48 U	< 0.098 U	60 J		0.38 J		13	52
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	856.48	0.17 - 2 ft	180-100148-3	Excavated	0.47	16	1200	< 0.49 U	< 0.1 U	< 57 U		0.46 J		22	45
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	855.88	0.17 - 2 ft	180-100148-3	Excavated	0.36	17	960	0.51 J	< 0.092 U	80 J		0.48 J		15	77
Football Field	SSHS-B3456	DUP09	7/28/2020	855.34	0.17 - 2 ft	180-108872-2	Excavated	0.073	22	590	< 0.5 UJ	< 0.1 U	< 58 UJ		< 0.31 U		13	65
Football Field	SSHS-B3456	SSHS-B3456-SUB-0.17-2	7/28/2020	855.34	0.17 - 2 ft	180-108872-2	Excavated	0.073	29	540	0.59 J	< 0.071 U	66 J		< 0.22 U		12	62
Football Field	SSHS-B3457	SSHS-B3457-SUB-0.17-2	7/28/2020	855.82	0.17 - 2 ft	180-108872-2	Excavated	0.072 J+	42	770	1.1	< 0.09 U	180 J		< 0.27 U		13	64
Football Field	SSHS-B3458	SSHS-B3458-SUB-0.17-2	7/28/2020	856.14	0.17 - 2 ft	180-108872-2	Excavated	0.12	20	490	0.53 J	< 0.092 U	59 J		< 0.28 U		11	82
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	0.036 J	26	820	0.63 J	< 0.11 U	81 J		< 0.33 U		12	67
Football Field	SSHS-B3460	SSHS-B3460-SUB-0.17-2	7/28/2020	855.83	0.17 - 2 ft	180-108872-2	Excavated	0.15	45	660	1.2	< 0.097 U	93 J		< 0.3 U		17	130
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	0.047	19	730	< 0.51 U	< 0.1 U	< 60 U		< 0.32 U		13	75
Football Field	SSHS-B3462	DUP11	7/28/2020	855.77	0.17 - 2 ft	180-108872-2	Excavated	0.11 J	23	810	< 0.52 U	< 0.11 U	94 J		< 0.32 U		15	73
Football Field	SSHS-B3462	SSHS-B3462-SUB-0.17-2	7/28/2020	855.77	0.17 - 2 ft	180-108872-2	Excavated	0.039 J	21	670	< 0.5 U	< 0.1 U	73 J		< 0.31 U		15	76
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated	0.099	29	570	< 0.45 U	< 0.091 U	86 J		< 0.28 U		16	70
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	0.056	23	1100	< 0.51 U	< 0.1 U	75 J		< 0.32 U		18	62
Football Field	SSHS-B3465	SSHS-B3465-SUB-0.17-2	7/28/2020	855.46	0.17 - 2 ft	180-108872-2	Excavated	2.2	56	650	0.93	< 0.071 U	66 J		< 0.22 U		15	73
Football Field	SSHS-B3466	SSHS-B3466-SUB-0.17-2	7/28/2020	855.76	0.17 - 2 ft	180-108872-2	Excavated	0.057	25	750	0.56 J	< 0.071 U	54 J		< 0.22 U		16	75
Football Field	SSHS-B3467	SSHS-B3467-SUB-0.17-2	7/28/2020	855.68	0.17 - 2 ft	180-108872-2	Excavated	0.074	29	920	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		16	75
Football Field	SSHS-B3468	SSHS-B3468-SUB-0.17-2	7/28/2020	855.93	0.17 - 2 ft	180-108872-2	Excavated	0.096 J	24	570	0.55 J	< 0.07 U	48 J		< 0.21 U		12	66
Football Field	SSHS-B3469	SSHS-B3469-SUB-0.17-2	7/28/2020	855.50	0.17 - 2 ft	180-108872-2	Excavated	0.19	29	700	0.7 J	< 0.11 U	230 J		< 0.35 U		14	110
Football Field	SSHS-B3470	SSHS-B3470-SUB-0.17-2	7/28/2020	855.73	0.17 - 2 ft	180-108872-2	Excavated	0.55	84	760	0.8 J	< 0.11 U	73 J		< 0.32 U		16	120
Football Field	SSHS-B3470	DUP14	7/28/2020	855.73	0.17 - 2 ft	180-108872-2	Excavated	0.4 J	49	530	0.88	< 0.078 U	83 J		< 0.24 U		14	60
Football Field	SSHS-B3471	SSHS-B3471-SUB-0.17-2	7/28/2020	856.03	0.17 - 2 ft	180-108872-2	Excavated	0.15	23	650	0.92 J	< 0.099 U	84 J		< 0.3 U		13	65 J+
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	0.082	18	670	1.3	< 0.089 U	450		< 0.27 U		12	89
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	0.042 J	17	580	0.45 J	< 0.089 U	71 J		< 0.27 U		10	66
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	0.075 J	20	740	0.57 J	< 0.098 U	82 J		< 0.3 U		13	72
Football Field	SSHS-B3474	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	0.17 - 2 ft	180-108826-1	Not Excavated	0.019 J	21	500	0.54 J	< 0.067 U	72 J		< 0.21 U		8.2	51
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	0.041	28	630	< 0.41 U	< 0.084 U	84 J		< 0.25 U		14	180
Football Field	SSHS-B3476	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	0.17 - 2 ft	180-108826-1	Not Excavated	0.065	120	690	0.81 J	< 0.11 U	290 J		< 0.34 U		13	95
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	0.045	17	510	0.66 J	< 0.088 U	150 J		< 0.27 U		11	72
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.028 J	19		< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		15	57
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.024 U	19		< 0.56 U	< 0.12 U	< 66 U		< 0.35 U		16	58
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	0.086	21		0.69 J	0.15 J	< 72 U		< 0.39 U		18	190
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	0.089	17	660	0.75 J	< 0.12 U	< 71 U		< 0.38 U		17	110
Football Field	SSHS-B3501	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	0.17 - 2 ft	180-110264-1	Not Excavated											
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-0.17-2	1/25/2021	855.86	0.17 - 2 ft	180-116404-1	Excavated	< 0.025 U	72	720	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U		16	100
Northern Athletic Field	SSHS-B3511A	SSHS-B3511-SUB-0.17-2	1/13/2021	856.97	0.17 - 2 ft	180-115927-1	Excavated	0.048	26	1200	< 0.58 U	< 0.12 U	100 J		< 0.36 U		23	69
Northern Athletic Field	SSHS-B3512A	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	0.17 - 2 ft	180-115927-1	Not Excavated	0.29	27	1100	< 0.62 U	< 0.13 U	72 J		< 0.38 U		17	78
Northern Athletic Field	SSHS-B3513	SSHS-B3513-SUB-0.17-2	1/13/2021	856.86	0.17 - 2 ft	180-115927-1	Excavated	0.043	22	1300	< 0.6 U	< 0.12 U	< 70 U		< 0.37 U		16	60
Northern Athletic Field	SSHS-B3514	SSHS-B3514-SUB-0.17-2	1/13/2021	856.41	0.17 - 2 ft	180-115927-1	Excavated	0.036 J	22	1200	< 0.6 U	< 0.12 U	< 70 U		< 0.37 U		15	65
Northern Athletic Field	SSHS-B3515	SSHS-B3515-SUB-0.17-2	1/13/2021	856.77	0.17 - 2 ft	180-115927-1	Excavated	0.23	20	880	< 0.53 U	1.1	< 62 U		< 0.33 U		14	120
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	< 0.023 U	19	840	< 0.63 U	< 0.13 U	< 74 U		< 0.39 U		14	61
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	0.0618	14.3		0.908	< 1.13 U			< 1.13 U	< 56.6 U	12.3	59.1
Northern Athletic Field	SSHS-B36	12 Sep 00B36 0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.0532 U	13.4		0.93	< 1.06 U			< 1.06 U	< 53.2 U	14.5	55.2
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-0.17-2	1/29/2021	856.95	0.17 - 2 ft	1801166651	Excavated	0.17	13	510	0.70 J	< 0.088 U	87 J		< 0.27 U		10	48
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.019 U	12	580	< 0.51 U	< 0.10 U	69 J		< 0.32 U		9.4	45
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-0.17-2	1/29/2021	856.79	0.17 - 2 ft	180-116665-1	Excavated	0.2	18	660	< 0.44 U	< 0.09 U	76 J		< 0.27 U		14	98
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-0.17-2	1/29/2021	856.79	0.17 - 2 ft	180-116665-1	Excavated	0.2	18	660	< 0.44 U	< 0.09 U	76 J		< 0.27 U		14	98
Northern Athletic Field	SSHS-B3647	SSHS-B3647-SUB-0.17-2	1/29/2021	856.70	0.17 - 2 ft	180-116665-1	Excavated	0.046	11	680	< 0.36 U	< 0.074 U	130 J		< 0.22 U		8.5	38
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.05 U	7.6		< 0.54 U	< 1.1 U			< 1.1 U	< 53.9 U	6.6	27.7
Northern Athletic Field	SSHS-B37	12 Sep 00B37 0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.0521 U	11.3		1.43	< 1.04 U			< 1.04 U	< 52.1 U	10.1	58.3
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0578 U	21		1.64	< 1.16 U			< 1.16 U	< 57.8 U	17.2	70.5
Northern Athletic Field	SSHS-B38	12 Sep 00B38 1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	0.0764	18.2		0.721	< 1.11 U			< 1.11 U	< 55.7 U	16.7	77.4
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	0.17 - 2 ft	180-124920-1	Not Excavated	0.071	36	590	1	< 0.11 U	190 J		< 0.32 U		16	110
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.021 U	16	770	0.81 J	< 0.1 U	69 J		< 0.3 U		12	72
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0631 U	17.6		0.871	< 1.26 U			< 1.26 U	< 63.1 U	17	56.3
Northern Athletic Field	SSHS-B39	12 Sep 00B39 0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	1.95	22.6		1.57	< 1.09 U			< 1.09 U	< 54.4 U	16.3	70.9
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	0.046	20	950	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U		14	56
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	0.060	23	950	< 0.60 U	< 0.12 U	< 70 U		< 0.37 U		12	53
EHS Building	SSHS-B3S	B3-C1-Composite	7/25/2007	855.70	0.5 - 2 ft	NA	Not Excavated							< U				

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
				5 & 6	5 & 6																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]															
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300	70.5 NE	4400	267 *E
Northern Athletic Field	SSHS-B40	12 Sep 00B40 0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated		< 1.12 U	5.82	91.4	< 0.561 U	< 0.561 U		14		7.16	43		50.2		
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated		< 1.24 U	5.01	111	< 0.62 U	< 0.62 U		73.1		8.98	22.8		26.3		
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	0.17 - 1 ft	180-123985-1	Not Excavated	8100	< 0.36 UJ	7.1	66	0.36 J	0.046 J	17000	11		6.9	18	18000	22	4100	380
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	856.80	1 - 2 ft	180-123985-1	Not Excavated	7800	0.36 J	7.1	130	0.45	0.08 J	2800	11		7.1	29	18000	44	2000	350
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	8800	< 0.40 U	6.5	89	0.44 J	< 0.043 U	1700	11		7.4	12	17000	11	2500	430
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	6000	< 0.35 U	4.4	61	0.29 J	0.071 J	6600	9.2		4.8 J	14	11000	17	1900	270
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated		< 1.18	5.5	101	0.619	< 0.591		32		9.17	14.3		19.4		
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated		< 1.12	8.93	146	0.601	< 0.562		16.5		7.11	60.1		110		
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	11000	< 0.034 U	6.4	110	0.55	0.17 J	2500	27		9.2	17	21000	16	3300	510 J
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	8900	< 0.034 U	5.9	60	0.34 J	0.071 J	41000	11		7.9	26	19000	9.5	7700	340
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	5700	0.31 J	5	62	0.23 J	0.1 J	66000	8.9		5	33	14000	26	8600	330
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	8300	< 0.034 U	5.6	55	0.31 J	0.086 J	52000	11		7.2	26	18000	10	8900	460
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated		< 1.2	5.4	113	0.61	< 0.61		28.9		9.4	21.4		23.4		
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated		< 3.93	32.1	153	1.12	0.612		74.1		14.6	4080		783		
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	8600	< 0.034 U	9	140	0.45	0.66	8100	13		7.9	27	19000	42	3200	530
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated		< 1.11	4.54	64.5	< 0.554	< 0.554		8.82		6.43	9.5		11.2		
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated		< 1.2	7.02	241	< 0.6	< 0.6		10.5		6.82	36.5		2210		
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated		< 1.28	5.4	101	0.679	< 0.639		16.1		9.95	14.2		15.1		
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated		< 1.1	5.06	81.5	< 0.55	< 0.55		10		7.18	22.2		23.8		
Football Field	SSHS-B447	SSHS-447-SUB-0-2	8/24/2016	855.38	0 - 2 ft	180-57932-1	Excavated	6900	1.1	5.7	83	0.33 J	0.12 J	18000	11		6.3	50	16000	52	4900	420
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated		< 1.31	6.5	106	< 0.65	< 0.65		15		9.8	17.4		19.3		
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated		< 1.11	7.28	62.4	< 0.557	< 0.557		8.36		6.67	23.1		26.1		
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated		< 1.31	5.84	110	< 0.656	< 0.656		14.3		8.66	13.5		16.1		
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated		< 1.11	6.68	103	0.568	< 0.555		8.88		7.2	19.4		29.9		
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated		1.31	5.7	125	< 0.656	< 0.656		16.6		9.1	16.3		18.3		
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated		< 1.16	4.07	58.5	< 0.578	< 0.578		8.02		< 5.78	8.18		8.15		
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated		< 1.33	5.83	115	< 0.654	< 0.654		14.6		9.16	13.8		17.5		
EHS Building	SSHS-B4S	B4-C1-Composite	7/25/2007	-	0.5 - 2 ft	-	Not Excavated															
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600	32 NE	4150	481 *E
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated		< 1.27 U	5.67	121	< 0.635 U	< 0.635 U		16.9		10.3	18.7		16.6		
Northern Athletic Field	SSHS-B50	13 Sep 00B50 0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated		< 1.1 U	6.1	112	< 0.57 U	< 0.57 U		13.9		9.5	42.7 N		22.2		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated		< 1.12 U	3.9	36.8	< 0.558 U	< 0.558 U		13.2		< 5.58 U	7.38		5.51		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated		< 1.09 U	7.76	98.9	< 0.545 U	< 0.545 U		10.1		7.79	28.6		14.8		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated		< 1.3 U	5.8	144	< 0.66 U	< 0.66 U		37.9		10.2	19.2		17.3		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated		< 1.08 U	8.28	61.2	< 0.542 U	< 0.542 U		12.1		9.08	30.3		10.5		
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated		< 1.33 U	4.78	92.3	< 0.666 U	0.77		58.2		10.2	22.4		16		
Northern Athletic Field	SSHS-B53	13 Sep 00B53 0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated		< 1.1 U	3.38	51.3	< 0.549 U	< 0.549 U		6.77		< 5.49 U	12.1		11.2		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated		< 1.35 U	5.72	133	< 0.673 U	0.907		91.4		10.9	23.1		20.2		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated		< 1.17 U	2.35	112	< 0.587 U	< 0.587 U		11		6.44	12.8		16.2		
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated		< 1.14 U	7.07	94.4	< 0.57 U	< 0.57 U		8.3		6.36	27.7		174		
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated		< 1.3 U	5.8	124	< 0.67 U	< 0.67 U		39.5		9.9	19.8		34		
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated			4.76	112		0.654		51.2		9.06	18.3		17		
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated			3.86	39.2				7.01		5.51	20.2		5.79		
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated			3.05	32.4				7.45		5.99	26.6		13.3		
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated			5.3	84.2		0.58		39.1		9.2	19.3		20.2		
Northern Athletic Field	SSHS-B570	SSHS-B570-SUB-0-2	8/30/2016	853.41	0 - 2 ft	180-58129-1	Excavated	8000	< 0.39	7.8	75	0.38	0.57	3700	13		6.5	17	17000	11	2900	410
Northern Athletic Field	SSHS-B571	090616 09:00 PS-FD-42	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	9100	< 0.38	8.9	95	0.47	0.71	12000	12		8.1	19	20000	27	3400	490
Northern Athletic Field	SSHS-B571	SSHS-B571-SUB-0-2	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	9100	< 0.37	8.6	94	0.5	0.64	7100	12		8.2	17	18000	24	3400	520
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	8400	0.38	8.2	81	0.42	0.64	12000	14		7.8	21	18000	21	5200	540
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated		< 1.14 U	5.23	43.4	< 0.571 U	0.63		15.9		6.32	8.07		5.06		
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated		< 1.14 U	4.91	98.9	< 0.569 U	< 0.569 U		10.4		6.94	28.4		16.6		
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated		< 1.19 U	5.36	109	0.652	< 0.597 U		19.2		10	19.3		16.2		
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated		< 1.09 U	6.76	68.8	< 0.544 U	< 0.544 U		9.71		7.88	21.8		9.82		
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300	70.5 NE	4400	267 *E
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated			6	174	< 0.53 U	< 0.53 U		10.2			29.2		50.3		
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	6500	< 0.2 U	5.5	140	0.28 J	0.12 J	52000	8.6		5.8	20	15000	10	5300	520
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	6100	< 0.21 U	5	35	0.24 J	< 0.015 U	30000	8		5.2 J	24	14000	11	6900	390
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	6400	< 0.21 U	7.8	70	0.31 J	< 0.015 U	14000	16		6.2	91	20000	130	4200	360
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	8100	0.93 J	21	270	0.39 J	< 0.015 U	29000	47		12	980	38000	590	4200	410
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	5600	< 0.22 U	8.9	82	0.3 J	< 0.015 U	16000	14		5.5	60	19000	66	3400	310
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	6600	< 0.22 U	6.7	54	0.32 J	< 0.016 U	25000	8.1		6.5	20	16000	15	4900	450
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700	171 NE	3760	379 *E
Football Field	SSHS-B70	081514 01:15 SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	10000	< 0.21 U	7.5	100	0.53	< 0.015 U	1700	12		8.8	15	19000	15	2600	490
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	8200	< 0.22	6	89	0.32	0.066	23000	8.8		5	29	14000	21	3400	360
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	6900	< 0.22	9.1	92	0.37	0.15	22000	9.6		6.7	35	16000	46	4800	540
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	8700	< 0.23	7.7	58	0.4	< 0.016	11000	11		7	20	18000	14	3200	390
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	5500	0.21	4.1	35	0.22	< 0.014	33000	7.1		4.7	20	13000	6.7	3200	420
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	8200	0.23 J	7.6	78	0.37 J	< 0.015 U	14000	9.8		5.9	37	18000	33	3200	410
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700	171 NE	3760	379 *E
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	7900	0.29 J	8.3	94	0.42	< 0.015 U	13000	16		6.9	51	19000	41	3500	490
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	6600	2.1	12	71	0.34 J	0.26 J	26000	9		9.3	110	48000	59	3400	440
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	6600	< 0.38 U	6	150	0.32 J	0.16 J	14000	9.1		6.4	24	15000	27	2400	690

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
				5 & 6	5 & 6													
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]											
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated	0.082	84 *E	494	1.3	< U	132		< U		9.4	103 NE
Northern Athletic Field	SSHS-B40	12 Sep 00B40 0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	0.245	25.7		1.68	< 1.12 U			< 1.12 U	< 56.1 U	16.7	81.5
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	0.0757	28.6		1.15	< 1.24 U			< 1.24 U	< 62 U	17.2	77.7
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.024 U	17	880	< 0.54 U	< 0.11 U	< 63 U		< 0.34 UJ		13	96
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	856.80	1 - 2 ft	180-123985-1	Not Excavated	0.084	19	890	< 0.48 U	< 0.099 U	< 57 U		< 0.3 UJ		15	60
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.019 U	16	1100	< 0.60 U	< 0.12 U	< 71 U		< 0.38 U		12	57
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	0.065	13	640	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		9.5	43
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	0.227	18.9		< 0.591	< 1.18			< 1.18	< 59.1	16.3	71.6
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	0.124	22		1.73	< 1.12			< 1.12	< 56.2	19.3	138
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	0.045	22	1000	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		17	61
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.034 U	26	970	< 0.034 U	< 0.034 U	78 J		< 0.034 U		15	70
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	0.042	17	650	0.91	< 0.034 U	230 J		< 0.034 U		15	55
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	0.022 J	20	800	< 0.034 U	< 0.034 U	150 J		< 0.034 U		12	68
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.06	23.7		< 0.59	< 1.2			< 1.2	< 60.9	16.5	70.4
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	0.103	517		3.43	< 1.13			< 1.13	137	35.9	844
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	0.1	20	700	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		13	75
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0554	13.1		0.879	< 1.11			< 1.11	< 55.4	11.8	48.1
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	0.0617	16		< 0.6	< 1.2			< 1.2	< 60	16.1	70
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0639	20.7		0.81	< 1.28			< 1.28	< 63.9	18.9	62.6
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	0.0636	14.7		1.43	< 1.1			< 1.1	< 55	16.9	53.5
Football Field	SSHS-B447	SSHS-447-SUB-0-2	8/24/2016	855.38	0 - 2 ft	180-57932-1	Excavated	0.69	64	580	0.79 J	< 0.16 U	< 140 U		< 0.49 U		14	92
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.06	20.8		< 0.63	< 1.3			< 1.3	< 65.3	17.5	63.1
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.0557	13.5		0.994	< 1.11			< 1.11	< 55.7	16.1	53
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0656	17.6		< 0.656	< 1.31			< 1.31	< 65.6	16	57.1
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.0555	13.3		1.33	< 1.11			< 1.11	< 55.5	17.1	45.9
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.06	20.1		< 0.63	< 1.3			< 1.3	< 65.1	16	63
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.0578	12		< 0.578	< 1.16			< 1.16	< 57.8	14.2	39.4
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0664	18.6		0.883	< 1.33			< 1.33	< 66.4	18.1	55.8
EHS Building	SSHS-B4S	B4-C1-Composite	7/25/2007	-	0.5 - 2 ft	-	Not Excavated							< U				
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated	0.0087	19.3 *E	682	1.7	< U	110		< U		13.3	68.5 NE
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0635 U	22.2		1.57	< 1.27 U			< 1.27 U	< 63.5 U	17.9	64.1
Northern Athletic Field	SSHS-B50	13 Sep 00B50 0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	< 0.05 U	20.6		< 0.57 U	< 1.1 U			< 1.1 U	< 56.8 U	16.9	63.2
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0558 U	5.27		< 0.558 U	< 1.12 U			< 1.12 U	< 55.8 U	27.6	26.6
Northern Athletic Field	SSHS-B51	13 Sep 00B51 0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 0.0545 U	17.2		0.618	< 1.09 U			< 1.09 U	< 54.5 U	16.1	69.7
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.07 U	21.9		< 0.66 U	< 1.3 U			< 1.3 U	< 66.5 U	17.6	67.9
Northern Athletic Field	SSHS-B52	13 Sep 00B52 0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.0542 U	19.6		0.777	< 1.08 U			< 1.08 U	< 54.2 U	17.4	61.8
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0666 U	22.8		1.62	< 1.33 U			< 1.33 U	< 66.6 U	16.6	68.7
Northern Athletic Field	SSHS-B53	13 Sep 00B53 0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.0549 U	9.78		0.67	< 1.1 U			< 1.1 U	< 54.9 U	10.7	39.8
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0673 U	27.6		1.47	< 1.35 U			< 1.35 U	< 67.3 U	19.9	84.4
Northern Athletic Field	SSHS-B54	13 Sep 00B54 0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	0.111	14		0.68	< 1.17 U			< 1.17 U	< 58.7 U	16.4	46.6
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	0.112	13.9		1.6	< 1.14 U			< 1.14 U	< 57 U	14.7	86.1
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	0.236	21.9		0.7	< 1.3 U			< 1.4 U	< 67.2 U	16.5	77.3
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated		20.1		1.18						14.7	67.4
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated		12.6		0.717						11	66
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated		13.7								11.1	76.7
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated		21.6								17	66
Northern Athletic Field	SSHS-B570	SSHS-B570-SUB-0-2	8/30/2016	853.41	0 - 2 ft	180-58129-1	Excavated	0.18	16	590	< 0.43	< 0.18	< 150		< 0.55		12	53
Northern Athletic Field	SSHS-B571	090616 09:00 PS-FD-42	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	0.21	21	710	< 0.42	< 0.18	< 150		< 0.53		14	63
Northern Athletic Field	SSHS-B571	SSHS-B571-SUB-0-2	8/30/2016	856.63	0 - 2 ft	180-58129-1	Excavated	0.16	19	680	0.41	< 0.17	< 150		< 0.52		14	58
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	0.15	18	730	< 0.42	< 0.18	< 150		< 0.53		12	60
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0571 U	5.62		0.967	< 1.14 U			< 1.14 U	< 57.1 U	33.4	25.5
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	0.0658	14.7		1.22	< 1.14 U			< 1.14 U	< 56.9 U	19.2	72.1
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.0597 U	24.8		0.962	< 1.19 U			< 1.19 U	< 59.7 U	20.5	67.5
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.0544 U	17.6		0.959	< 1.09 U			< 1.09 U	< 54.4 U	18.6	62.5
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated	0.082	84 *E	494	1.3	< U	132		< U		9.4	103 NE
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	2.7	19.5		< 0.6 U	< 1.1 U						106
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	0.014 J	16	530	0.29 J	< 0.04 U	170 J		< 0.15 U		11	53
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	0.032 J	17	< 6.8 U	0.41 J	< 0.043 U	120 J		< 0.16 U		10	61
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	0.046	52	560	0.76 J	< 0.043 U	120 J		< 0.16 U		12	110
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	0.65	870	610	1.8	0.39 J	640		< 0.16 U		16	250
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	0.06	40	< 6.9 U	0.82 J	< 0.044 U	180 J		< 0.16 U		11	79
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	0.025 J	16	610	0.51 J	< 0.044 U	180 J		< 0.16 U		12	57
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated	0.042	453 *E	900	1.8	< U	1270		< U		14.7	111 NE
Football Field	SSHS-B70	081514 01:15 SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	0.046	19	830	< 0.28 U	< 0.042 U	28 J		< 0.15 U		14	51
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	0.038	13	770	< 0.29	< 0.044	200		< 0.16		12	61
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	0.65	18	610	0.68	< 0.044	58		< 0.16		15	79
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	0.042	17	650	< 0.31	< 0.047	48		< 0.17		15	56
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	0.015	11	500	1	< 0.041	41		< 0.15		9.5	47
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	0.2	16	700	0.57 J	< 0.042 U	190 J		< 0.15 U		14	72
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated	0.042	453 *E	900	1.8	< U	1270		< U		14.7	111 NE
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	0.051	22	650	< 0.27 U	< 0.041 U	210 J		< 0.15 U		15	79
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	0.023 J	18	450 J	1 J	< 0.045 U	330 J		0.37 J		13	120
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	0.095	17	530	< 0.42 U	< 0.18 U	< 150 U		< 0.53 U		9.9	68

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
				5 & 6	5 & 6																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]															
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	5400	< 0.22 U	7.2	32	0.26 J	< 0.016 U	26000	7		5.8	18	14000	11	3300	370
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	8600	0.23 J	8.3	80 J	0.41	< 0.015 U	5100 J	11 J		7.6	47 J	19000	27	3400	450
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-0-2	1/22/2018	850.73	0 - 2 ft	180-74331-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	8500	< 0.21 U	6	56	0.35 J	0.05 J	2900	8.6		5.7	15	16000	9.4	2100	420
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	5200	< 0.21 U	5	40	0.26 J	0.082 J	19000	6.4		5.3	28	13000	18	4000	460
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	7800	0.36 J	5.6	59	0.33 J	< 0.015 U	13000	9.5		5.6	55	16000	31	3400	350
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-0-2	1/11/2018	853.61	0 - 2 ft	180-74124-2	Excavated															
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-0-2	1/20/2018	853.66	0 - 2 ft	180-74390-2	Excavated															
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	851.27	0 - 2 ft	180-74307-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	8000	< 0.21 U	8.1	63	0.4 J	0.065 J	5800	17		6.4	36	20000	72	2400	280
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-0-2	1/17/2018	850.48	0 - 2 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	6200	< 0.2 U	6.8	50	0.31 J	0.06 J	10000	7.5		5.5	24	17000	9.4	3500	470
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600	32 NE	4150	481 *E
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	850.31	0 - 2 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated															
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated															
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-0-2	1/16/2018	851.77	0 - 2 ft	180-74203-2	Excavated															
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600	32 NE	4150	481 *E
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated			7.3	165	< 0.55 U	< 0.55 U		134			92.6		123		
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated			5.7	76.4	0.65	< 0.59 U		12.9			17		16.4		
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated			8.2	68.6	< 0.58 U	< 0.58 U		10.4			55.7		36.6		
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated			6.4	115	< 0.59 U	< 0.59 U		11.6			54.9		82		
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated			7.1	171	< 0.54 U	< 0.54 U		9.3			23.8		29.9		
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated			6.1	102	< 0.6 U	< 0.6 U		11			56.2		63.9		
Football Field	SSHS-GS-01	SSHS-GS-01	8/23/2019	855.29	0.5 - 0.5 ft	180-94662-1	Excavated	8000	0.7 J	8.7	86	0.43 J	0.27 J	3500	12		7	42	20000	51	2300	620
Football Field	SSHS-GS-02	SSHS-GS-02	8/23/2019	855.18	0.5 - 0.5 ft	180-94662-1	Excavated	8500	1.8	12	130	0.5	0.27 J	8000	22		7.3	120	28000	140	3300	440
Football Field	SSHS-GS-03	SSHS-GS-03	8/23/2019	855.06	0.5 - 0.5 ft	180-94662-1	Excavated	7200	1.3	12	110	0.45	0.24 J	4600	14		6.9	83	23000	130	2500	430
Football Field	SSHS-GS-04	SSHS-GS-04	8/23/2019	855.13	0.5 - 0.5 ft	180-94662-1	Excavated	6400	1.4	13	88	0.47 J	0.29 J	3300	14		6.3	65	25000	100	2100	380
Football Field	SSHS-GS-05	SSHS-GS-05	8/23/2019	855.13	0.5 - 0.5 ft	180-94662-1	Excavated	9100	2.1	12	250	0.47 J	0.28 J	10000	24		7.8	180	29000	260	2900	500
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated			6.2	111	< 0.74 U	< 0.74 U		88.1			24.8		30.3		
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated		< 1.12 U	5.91	92.7	< 0.559 U	< 0.559 U		11.6		7.86	19.4		23.4		
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated		< 1.11 U	6.63	99.6	< 0.554 U	< 0.554 U		12.2		8.19	20.1		25.8		
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			5.3	124	< 0.69 U	< 0.69 U		107			25.6		26.2		
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated			4	134	< 0.68 U	< 0.68 U		14.3			14.6		18.4		
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated			6.8	110	< 0.65 U	< 0.65 U		20.8			20.5		23.5		
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated		< 1.36 U	5.28	97.4	< 0.682 U	< 0.682 U		89.5		9.22	28.2		20.5		
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated		< 1.42 U	5.58	95.8	< 0.708 U	< 0.708 U		103		9.35	26.6		21.5		
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated		< 1.31 U	7	93.4	< 0.66 U	0.72		73.9		9	25.8 N		59.1		
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated		< 1.43 U	4.01	105	< 0.714 U	< 0.714 U		74.6		9.67	24.4		21		
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated		< 1.36 U	4.62	102	< 0.682 U	0.745		106		9.86	27.6		22.8		

DRAFT

TABLE 5-5B
Shallow Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
				5 & 6	5 & 6													
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Lab Report	Excavation Status[7]											
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	0.015 J	13	540	0.82 J	< 0.044 U	210 J		< 0.16 U		9.9	42
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	0.046	18	600	< 0.28 U	< 0.042 U	370 J		< 0.15 U		14	59 J
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-0-2	1/22/2018	850.73	0 - 2 ft	180-74331-2	Excavated							< 11 U				
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	0.017 J	12	400 J	0.43 J	< 0.042 U	200 J		< 0.15 U		13	41
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	0.018 J	12	380 J	0.45 J	< 0.043 U	240 J		< 0.15 U		8.7	51
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	0.035 J	18	< 6.5 U	< 0.27 U	< 0.041 U	220 J		< 0.15 U		13	55
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-0-2	1/11/2018	853.61	0 - 2 ft	180-74124-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-0-2	1/20/2018	853.66	0 - 2 ft	180-74390-2	Excavated							< 10 U				
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-0-2	1/18/2018	851.27	0 - 2 ft	180-74307-2	Excavated							< 11 U				
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	0.033 J	16	450 J	0.55 J	< 0.043 U	300 J		< 0.15 U		14	57
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-0-2	1/17/2018	850.48	0 - 2 ft	180-74241-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated							< 11 U				
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	0.013 J	13	420 J	< 0.27 U	< 0.04 U	200 J		< 0.15 U		10	57
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated	0.0087	19.3 *E	682	1.7	< U	110		< U		13.3	68.5 NE
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-0-2	1/17/2018	850.31	0 - 2 ft	180-74241-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-0-2	1/16/2018	851.77	0 - 2 ft	180-74203-2	Excavated							< 11 U				
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated	0.0087	19.3 *E	682	1.7	< U	110		< U		13.3	68.5 NE
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	0.26	62.2		0.74	< 1.1 U						148
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	< 0.06 U	22.4		< 0.6 U	< 1.17 U						60.5
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	0.06	21.5		0.99	< 1.15 U						96
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	0.07	44.6		< 0.59 U	< 1.18 U						69.3
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	< 0.05 U	49.7		< 0.67 U	< 1.09 U						97.2
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	0.07	20.5		< 0.6 U	< 1.21 U						97.6
Football Field	SSHS-GS-01	SSHS-GS-01	8/23/2019	855.29	0.5 - 0.5 ft	180-94662-1	Excavated	0.089	25	530 J	0.68 J	< 0.12 U	51 J		< 0.36 U		15	110
Football Field	SSHS-GS-02	SSHS-GS-02	8/23/2019	855.18	0.5 - 0.5 ft	180-94662-1	Excavated	0.11	73	670	0.91 J	< 0.12 U	100 J		< 0.36 U		16	140
Football Field	SSHS-GS-03	SSHS-GS-03	8/23/2019	855.06	0.5 - 0.5 ft	180-94662-1	Excavated	0.076	40	620	< 0.58 U	< 0.12 U	64 J		< 0.36 U		15	130
Football Field	SSHS-GS-04	SSHS-GS-04	8/23/2019	855.13	0.5 - 0.5 ft	180-94662-1	Excavated	0.085	33	560 J	0.67 J	< 0.13 U	69 J		< 0.38 U		15	200
Football Field	SSHS-GS-05	SSHS-GS-05	8/23/2019	855.13	0.5 - 0.5 ft	180-94662-1	Excavated	0.19	150	840	0.86 J	< 0.13 U	120 J		< 0.39 U		18	140
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.07 U	20.7		< 0.76 U	< 1.5 U						90.6
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	0.147	18.1		1.02	< 1.12 U			< 1.12 U	< 55.9 U	15.4	72.6
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	0.113	19.2		0.732	< 1.11 U			< 1.11 U	< 55.4 U	16.6	70.1
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.07 U	25.8		< 0.7 U	< 1.4 U						92.6
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.7 U	21.8		< 0.68 U	< 1.4 U						62.7
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.06 U	21.3		< 0.65 U	< 1.3 U						68
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	0.158	21.1		1.58	< 1.36 U			< 1.36 U	< 68.2 U	17.2	83.2
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	0.0812	21.5		1.44	< 1.42 U			< 1.42 U	< 70.8 U	17	85.6
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	0.0934	20.5		< 0.67 U	< 1.3 U			< 1.3 U	< 65.6 U	15.5	81.5
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	0.164	22.4		1.07	< 1.43 U			< 1.43 U	< 71.4 U	17.4	77
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	0.142	23.3		1.43	< 1.36 U			< 1.36 U	< 68.2 U	18.6	86.5

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U						
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated			0.104	< 0.0069 U	< 0.0082 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.023 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U	< 0.049 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated			2.28		< U		0.1 J				0.25 J	0.22 J	0.31 J	0.12 J	0.15 J				0.57		
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated			ND	< 0.42 U	< 0.42 U		< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U						
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated			0.043	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U						
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated			5.56	< 4.4 U	< 4.4 U		< 4.4 U				< 4.4 U	< 4.4 U	< 4.4 U	< 4.4 U	0.95 J						
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated			13.13	< 3.8 U	0.62 J		0.43 J				1.1 J	1.2 J	1.2 J	1.1 J	1.4 J						
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated			ND	< 0.43 U	< 0.43 U		< 0.43 U				< 0.43 U	< 0.43 U	< 0.43 U	< 0.43 U	< 0.43 U						
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated			1.803	< 0.43 U	< 0.43 U		< 0.43 U				0.14 J	0.16 J	0.17 J	0.15 J	0.14 J						
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated			0.095	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U						
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U						
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated			5.37		< U		0.12 J				0.46	0.47	0.63	0.26 J	0.36				0.68		
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated			ND	< 0.41 U	< 0.41 U		< 0.41 U				< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U						
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated			11.145	< 0.0017 U	0.29	< 0.025 U	0.3	< 0.082 U	< 0.039 U	< 0.052 U	0.91	0.86	1.5	0.63	0.22	< 0.027 U	< 0.027 U	< 0.023 U	< 0.12 U	< 0.032 U	< 0.05 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated			1.7603	0.0063 J	0.074	< 0.014 U	0.025	< 0.045 U	< 0.021 U	< 0.029 U	0.14	0.18	0.27	0.11	0.13	< 0.015 U	< 0.015 U	< 0.013 U	< 0.064 U	< 0.018 U	< 0.028 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated			3.6564	0.0074 J	0.097	0.021 J	0.063	< 0.041 U	< 0.019 U	< 0.026 U	0.31	0.35	0.6	0.25	0.099	< 0.014 U	< 0.014 U	< 0.011 U	0.06 J	< 0.016 U	< 0.025 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated			0.0607	< 0.0009 U	< 0.00041 U	< 0.013 U	< 0.00092 U	< 0.042 U	< 0.02 U	< 0.027 U	0.0072 J	0.0056 J	0.0086	< 0.0008 U	0.0049 J	< 0.014 U	< 0.014 U	< 0.012 U	0.064 J	< 0.017 U	< 0.026 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated			1.848	0.032	0.0097	< 0.014 U	0.075	< 0.046 U	< 0.022 U	< 0.029 U	0.14	0.12	0.16	0.06	0.092	< 0.015 U	< 0.015 U	< 0.013 U	< 0.065 U	< 0.018 U	< 0.028 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated			1.4908	0.0068 J	0.031	< 0.013 U	0.037	< 0.042 U	< 0.02 U	< 0.027 U	0.12	0.13	0.18	0.083	0.083	< 0.014 U	< 0.014 U	< 0.012 U	0.26	< 0.016 U	< 0.026 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated			3.782	< 0.0022 U	0.13	< 0.032 U	0.062	< 0.11 U	< 0.05 U	< 0.067 U	0.32	0.36	0.57	0.19	0.15	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.041 U	< 0.065 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated			0.107	< 0.0009 U	< 0.00042 U	< 0.013 U	< 0.00093 U	< 0.043 U	< 0.02 U	< 0.027 U	0.0092	0.012	0.02	0.0094	< 0.00042 U	< 0.014 U	< 0.014 U	< 0.012 U	< 0.061 U	< 0.017 U	< 0.026 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated			1.803	< 0.00088 U	0.086	0.018 J	0.033	< 0.041 U	< 0.02 U	< 0.026 U	0.088	0.14	0.25	0.068	0.11	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.025 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated			0.349	< 0.00083 U	0.0058 J	< 0.012 U	0.006 J	< 0.039 U	< 0.018 U	< 0.025 U	0.028	0.029	0.053	0.013	0.027	< 0.013 U	< 0.013 U	< 0.011 U	< 0.055 U	< 0.015 U	< 0.024 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated			0.993	< 0.00091 U	0.04	< 0.013 U	0.019	< 0.043 U	< 0.02 U	< 0.027 U	0.067	0.092	0.15	0.059	0.039	< 0.014 U	< 0.014 U	< 0.012 U	0.15	< 0.017 U	< 0.026 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated			0.389	< 0.001 U	0.0054 J	< 0.015 U	0.0063 J	< 0.049 U	< 0.023 U	< 0.031 U	0.034	0.037	0.046	0.019	0.026	< 0.016 U	< 0.016 U	< 0.014 U	0.076 J	< 0.019 U	< 0.03 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated			0.854	< 0.00088 U	0.0089	< 0.013 U	0.024	< 0.042 U	< 0.02 U	< 0.027 U	0.069	0.069	0.087	0.037	0.047	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.025 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated			2.597	< 0.00093 U	0.065	< 0.013 U	0.048	< 0.044 U	0.021 J	< 0.028 U	0.17	0.16	0.29	0.11	0.23	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated			1.0195	< 0.00093 U	0.055	< 0.013 U	0.024	< 0.044 U	< 0.021 U	< 0.028 U	0.062	0.07	0.11	0.053	0.12	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated			0.3118	< 0.00088 U	0.014	< 0.013 U	0.0058 J	< 0.042 U	< 0.02 U	0.028 J	0.022	0.032	0.061	0.019	0.02	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated			13.102	0.025	0.2	< 0.026 U	0.33	< 0.085 U	< 0.04 U	< 0.054 U	1.1	1	1.4	0.56	0.76	< 0.028 U	< 0.028 U	< 0.024 U	< 0.12 U	< 0.033 U	< 0.052 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated			14.28	0.2	0.15	< 0.012 U	0.48	< 0.041 U	0.058	< 0.026 U	1.3	0.98	1.5	0.61	0.54	< 0.014 U	< 0.014 U	< 0.011 U	0.1	< 0.016 U	< 0.025 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated			6.416	0.037	0.11	< 0.013 U	0.15	< 0.042 U	0.026 J	< 0.027 U	0.63	0.51	0.69	0.31	0.36	< 0.014 U	< 0.014 U	< 0.012 U	< 0.06 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated			6.983	0.02	0.24	< 0.013 U	0.16	< 0.044 U	0.042 J	< 0.028 U	0.5	0.49	0.73	0.28	0.62	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated			17.256	0.039	0.41	< 0.053 U	0.49	< 0.17 U	< 0.081 U	< 0.11 U	1.3	1.4	2.4	0.76	0.58	< 0.057 U	< 0.057 U	< 0.048 U	< 0.24 U	< 0.067 U	< 0.11 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated			8.693	0.018	0.2	< 0.026 U	0.18	< 0.086 U	< 0.041 U	< 0.055 U	0.71	0.74	1.1	0.33	0.64	< 0.029 U	< 0.029 U	< 0.024 U	< 0.12 U	< 0.033 U	< 0.052 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated			4.3441	0.0081	0.14	< 0.012 U	0.094	< 0.04 U	0.02 J	< 0.026 U	0.39	0.36	0.57	0.18	0.29	< 0.013 U	< 0.013 U	< 0.011 U	< 0.057 U	< 0.016 U	< 0.025 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated			3.3	0.013	0.081	< 0.013 U	0.067	< 0.044 U	0.021 J	< 0.028 U	0.22	0.25	0.37	0.13	0.28	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated			3.968	0.012	0.098	< 0.013 U	0.067	< 0.044 U	< 0.021 U	< 0.028 U	0.32	0.34	0.5	0.18	0.36	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated			2.041	< 0.0089 U	0.12	< 0.13 U	0.13	< 0.42 U	< 0.2 U	< 0.27 U	0.14	0.11	0.15	0.051 J	0.25	< 0.14 U	< 0.14 U	< 0.12 U	< 0.59 U	< 0.16 U	< 0.26 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated			1.935	< 0.0088 U	0.09	< 0.13 U	0.077	< 0.42 U	< 0.2 U	< 0.27 U	0.12	0.12	0.15	0.068 J	0.23	< 0.14 U	< 0.14 U	< 0.12 U	< 0.59 U	< 0.16 U	< 0.26 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated			2.9315	0.0057 J	0.025	< 0.014 U	0.034	< 0.044 U	< 0.021 U	< 0.028 U	0.3	0.25	0.35	0.1	0.19	< 0.015 U	< 0.015 U	< 0.012 U	0.085 J	< 0.017 U	< 0.027 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated			2.0544	0.0074 J	0.039	< 0.014 U	0.043	< 0.044 U	< 0.021 U	0.029 J	0.17	0.17	0.24	0.092	0.14	< 0.015 U	< 0.015 U	< 0.012 U	0.11	< 0.017 U	< 0.027 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated			3.0089	< 0.00094 U	0.066	< 0.014 U	0.047	< 0.045 U	< 0.021 U	< 0.029 U	0.26	0.26	0.37	0.12	0.24	< 0.015 U	< 0.015 U	< 0.012 U	< 0.063 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated			7.074	< 0.00092 U	0.11	< 0.013 U	0.11	< 0.044 U	< 0.021 U	< 0.028 U	0.62	0.57	0.8	0.28	0.54	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated			2.702	0.012	0.066	< 0.013 U	0.047	< 0.042 U	< 0.02 U	< 0.027 U	0.22	0.23	0.36	0.11	0.21	< 0.014 U	< 0.014 U	< 0.012 U	< 0.06 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated			7.328	< 0.0043 U	0.17	< 0.062 U	0.21	< 0.2 U	< 0.096 U	< 0.13 U	0.64	0.54	0.87	0.29	0.26	< 0.067 U	< 0.067 U	< 0.056 U	< 0.29 U	< 0.079 U	< 0.12 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated			3.347	0.032 J	0.056	< 0.063 U	0.11	< 0.21 U	< 0.098 U	< 0.13 U	0.28	0.25	0.32	0.11	0.18	< 0.069 U	< 0.069 U	< 0.057 U	< 0.29 U	< 0.08 U	< 0.13 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated			1.736	< 0.00086 U	0.073	< 0.012 U	0.042	< 0.041 U	< 0.019 U	< 0.026 U	0.16	0.17	0.24	0.073	0.12	< 0.014 U	< 0.014 U	< 0.011 U	< 0.058 U	< 0.016 U	< 0.025 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated			3.373	< 0.0034 U	0.079	< 0.049 U	0.054	< 0.16 U	< 0.076 U	< 0.1 U	0.33	0.31	0.46	0.15	0.18	< 0.053 U	< 0.053 U	< 0.044 U	< 0.23 U	< 0.062 U	< 0.098 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated			1.668	< 0.002 U	0.049	< 0.029 U	0.024	< 0.096 U	< 0.045 U	< 0.061 U	0.14	0.17	0.3	0.1	< 0.00093 U	< 0.032 U	< 0.032 U	< 0.027 U	< 0.14 U	< 0.037 U	< 0.059 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated			1.215	< 0.00078 U	0.052	< 0.011 U	0.019	< 0.037 U	< 0.018 U	< 0.024 U	0.092	0.11	0.19	0.11	0.056	< 0.012 U	< 0.012 U	< 0.01 U	< 0.053 U	< 0.014 U	< 0.023 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated			1.761	< 0.004 U	0.029 J	< 0.058 U	0.019 J	< 0.19 U	< 0.09 U	< 0.12 U	0.11	0.25	0.38	< 0.0036 U	< 0.0018 U	< 0.063 U	< 0.063 U	< 0.053 U	< 0.27 U	< 0.074 U	< 0.12 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated			3.026	0.045	0.019	< 0.013 U	0.12	< 0.044 U	< 0.021 U	< 0.028 U	0.28	0.23	0.35	0.13	0.054	< 0.015 U	< 0.015 U	< 0.012 U	0.087	< 0.017 U	< 0.027 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated			1.694	0.011	0.039	< 0.013 U	0.038	< 0.044 U	< 0.021 U	< 0.028 U	0.13	0.14	0.25	0.11	0.047	< 0.015 U	< 0.015 U	< 0.012 U	0.099	< 0.017 U	< 0.027 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated			3.163	0.017	0.072	< 0.025 U	0.072	< 0.08 U	< 0.038 U	< 0.051 U	0.28	0.25	0.42	0.12	0.15	< 0.027 U	< 0.027 U	< 0.022 U	< 0.11 U	< 0.031 U	< 0.049 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated			3.517	0.021	0.084	< 0.032 U	0.088	< 0.1 U	< 0.049 U	< 0.067 U	0.31	0.27	0.43	0.14	0.17	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.041 U	< 0.064 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated			10.331	0.081	0.059	< 0.05 U	0.29	< 0.16 U	< 0.077 U	< 0.1 U	0.96	0.92	1.3	0.59	0.38	< 0.054 U	< 0.054 U	< 0.045 U	< 0.23 U	< 0.063 U	< 0.099 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated			0.66	< 0.017 U	< 0.0076 U	< 0.24 U	< 0.017 U	< 0.79 U	< 0.37 U	< 0.5 U	< 0.014 U	< 0.014 U	< 0.013 U	< 0.015 U	< 0.0076 U	< 0.26 U	< 0.26 U	< 0.22 U	< 1.1 U	< 0.31 U	< 0.48 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated			1.193	< 0.00091 U	0.031	< 0.013 U	0.029	< 0.043 U	< 0.02 U	0.042 J	0.099	0.11	0.17	0.07	0.03	< 0.014 U	< 0.014 U	< 0.012 U	0.064 J	< 0.017 U	< 0.026 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated			19.895	0.095	0.59	< 0.026 U	0.53	< 0.086 U	0.098 J	< 0.055 U	1.4	1.6	2.4	0.73	0.91	< 0.029 U	< 0.029 U	< 0.024 U	0.15 J	< 0.033 U	< 0.052 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated			7.341	0.018	0.27	< 0.012 U	0.13	< 0.041 U	0.058	< 0.026 U	0.45	0.65	1.2	0.44	0.49	< 0.014 U	< 0.014 U	< 0.011 U	0.066 J	< 0.016 U	< 0.025 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated			121.81	0.26	1.7	< 0.26 U	4	< 0.84 U	< 0.4 U	< 0.53 U	9.4	8.3	12	5	3.9	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.33 U	< 0.51 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated			14.346	0.032	0.29	< 0.033 U	0.26	< 0.11 U	< 0.051 U	< 0.068 U	1.1	1.2	2	0.68	0.55	< 0.036 U	< 0.036 U	< 0.03 U	< 0.15 U	< 0.042 U	< 0.066 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated			4.837	0.034	0.059	0.016 J	0.12	< 0.042 U	< 0.02 U	< 0.027 U	0.47	0.37	0.54	0.15	0.21	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.025 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated			3.447	< 0.0046 U	0.086	< 0.067 U	0.1	< 0.22 U	< 0.1 U	< 0.14 U	0.23	0.25	0.39	0.15	0.15	< 0.073 U	< 0.073 U	< 0.061 U	< 0.31 U	< 0.085 U	< 0.13 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated			1.538	< 0.00091 U	0.075	< 0.013 U	0.027	< 0.043 U	< 0.02 U	< 0.028 U	0.13	0.13	0.23	0.065	0.11	< 0.014 U	< 0.014 U	< 0.012 U	< 0.061 U	< 0.017 U	< 0.026 U

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated								< 0.47 U	< 0.47 U	< 0.47 U										
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.27 U	< 0.0066 U	< 0.029 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.04 U	< 0.0085 U	< 0.0079 U	< 0.035 U	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.42 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated								0.22 J												
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated								< 0.42 U	< 0.42 U	< 0.42 U										
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated								0.043 J	< 0.38 U	< 0.38 U										
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated								0.46 J	< 4.4 U	0.66 J										
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated								1.4 J	0.41 J	< 3.8 U										
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated								< 0.43 U	< 0.43 U	< 0.43 U										
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated								0.2 J	0.043 J	< 0.43 U										
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated								< 0.38 U	< 0.38 U	< 0.38 U										
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated								< 0.37 U	< 0.37 U	< 0.37 U										
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated								0.44												
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated								< 0.41 U	< 0.41 U	< 0.41 U										
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	< 0.17 U	0.18	< 0.068 U	< 0.1 U	< 0.032 U	< 0.023 U	< 0.032 U	0.84	< 0.0015 U	0.15	< 0.098 U	< 0.1 U	< 0.071 U	< 0.091 U	< 0.032 U	< 0.05 U	< 0.064 U	< 0.18 U	< 0.13 U	< 0.32 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	< 0.094 U	< 0.024 U	< 0.038 U	< 0.056 U	< 0.018 U	< 0.013 U	< 0.018 U	0.18	< 0.00083 U	0.029 J	< 0.054 U	< 0.055 U	< 0.039 U	< 0.05 U	< 0.018 U	< 0.028 U	< 0.035 U	< 0.091 U	< 0.064 U	< 0.18 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	< 0.086 U	< 0.022 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.37	< 0.00075 U	0.023 J	< 0.049 U	< 0.05 U	< 0.035 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U	< 0.064 U	< 0.16 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	< 0.088 U	< 0.022 U	< 0.035 U	< 0.053 U	< 0.017 U	< 0.012 U	< 0.017 U	0.0059 J	< 0.00078 U	< 0.015 U	< 0.051 U	< 0.052 U	< 0.037 U	< 0.047 U	< 0.017 U	< 0.026 U	< 0.033 U	< 0.094 U	< 0.066 U	< 0.17 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.095 U	0.038 J	< 0.038 U	< 0.057 U	< 0.018 U	< 0.013 U	< 0.018 U	0.13	< 0.00084 U	0.024 J	< 0.055 U	< 0.056 U	< 0.039 U	< 0.051 U	< 0.018 U	< 0.028 U	< 0.036 U	< 0.1 U	< 0.071 U	< 0.18 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.088 U	< 0.022 U	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.13	< 0.00077 U	0.017 J	< 0.05 U	< 0.052 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.094 U	< 0.066 U	< 0.17 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.22 U	< 0.056 U	< 0.088 U	< 0.13 U	< 0.041 U	< 0.029 U	< 0.041 U	0.44	< 0.0019 U	< 0.038 U	< 0.13 U	< 0.13 U	< 0.091 U	< 0.12 U	< 0.041 U	< 0.065 U	< 0.082 U	< 0.23 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	< 0.089 U	< 0.023 U	< 0.036 U	< 0.053 U	< 0.017 U	< 0.012 U	< 0.017 U	0.013	< 0.00078 U	< 0.015 U	< 0.051 U	< 0.052 U	< 0.037 U	< 0.047 U	< 0.017 U	< 0.026 U	< 0.033 U	< 0.095 U	< 0.066 U	< 0.17 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	< 0.086 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.13	< 0.00076 U	0.04 J	< 0.05 U	< 0.051 U	< 0.036 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.065 U	< 0.16 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	< 0.082 U	< 0.021 U	< 0.033 U	< 0.049 U	< 0.015 U	< 0.011 U	< 0.015 U	0.04	< 0.00072 U	< 0.014 U	< 0.047 U	< 0.048 U	< 0.034 U	< 0.043 U	< 0.015 U	< 0.024 U	< 0.03 U	< 0.087 U	< 0.061 U	< 0.15 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	< 0.087 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.06	0.017	< 0.015 U	< 0.05 U	< 0.051 U	< 0.036 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.065 U	< 0.16 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	< 0.091 U	0.029 J	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.24	0.047	0.044 J	< 0.052 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.097 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.083	< 0.00081 U	0.032 J	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated	< 0.087 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.034	< 0.00077 U	< 0.015 U	< 0.05 U	< 0.051 U	< 0.036 U	< 0.046 U	< 0.016 U	< 0.026 U	< 0.032 U	< 0.093 U	< 0.065 U	< 0.16 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	< 0.18 U	0.12	< 0.071 U	< 0.11 U	< 0.033 U	< 0.024 U	< 0.033 U	1.1	0.18	0.11 J	< 0.1 U	< 0.1 U	< 0.073 U	< 0.095 U	< 0.033 U	< 0.052 U	< 0.066 U	< 0.19 U	< 0.13 U	< 0.34 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	< 0.085 U	0.23	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	1.2	0.18	0.18	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.09 U	< 0.063 U	< 0.16 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	< 0.088 U	0.06	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.65	0.1	0.054 J	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.094 U	< 0.065 U	< 0.17 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	< 0.092 U	0.14	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.49	0.11	0.12	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.069 U	< 0.17 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated	< 0.36 U	0.23 J	< 0.14 U	< 0.22 U	< 0.067 U	< 0.048 U	< 0.067 U	1.3	0.14	0.22 J	< 0.21 U	< 0.21 U	< 0.15 U	< 0.19 U	< 0.067 U	< 0.11 U	< 0.13 U	< 0.38 U	< 0.27 U	< 0.68 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	< 0.18 U	0.064 J	< 0.072 U	< 0.11 U	< 0.033 U	< 0.024 U	< 0.033 U	0.72	0.15	0.09 J	< 0.1 U	< 0.1 U	< 0.074 U	< 0.095 U	< 0.033 U	< 0.052 U	< 0.067 U	< 0.19 U	< 0.13 U	< 0.34 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	< 0.084 U	0.035 J	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	0.4	0.073	0.049 J	< 0.048 U	< 0.049 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.031 U	< 0.089 U	< 0.063 U	< 0.16 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	< 0.091 U	0.047 J	< 0.036 U	< 0.054 U	< 0.017 U	< 0.012 U	< 0.017 U	0.25	0.051	0.055 J	< 0.052 U	< 0.053 U	< 0.037 U	< 0.048 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.097 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	< 0.091 U	0.031 J	< 0.036 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.4	0.076	0.028 J	< 0.052 U	< 0.053 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.097 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	< 0.87 U	< 0.22 U	< 0.35 U	< 0.52 U	< 0.16 U	< 0.12 U	< 0.16 U	0.14	< 0.0077 U	< 0.15 U	< 0.5 U	< 0.51 U	< 0.36 U	< 0.47 U	< 0.16 U	< 0.26 U	< 0.33 U	< 0.93 U	< 0.65 U	< 1.7 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	< 0.87 U	< 0.22 U	< 0.35 U	< 0.52 U	< 0.16 U	< 0.12 U	< 0.16 U	0.15	< 0.0077 U	< 0.15 U	< 0.5 U	< 0.51 U	< 0.36 U	< 0.46 U	< 0.16 U	< 0.26 U	< 0.33 U	< 0.93 U	< 0.65 U	< 1.6 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.34	0.049	< 0.016 U	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.069 U	< 0.17 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.17	0.034	0.04 J	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.099 U	< 0.069 U	< 0.17 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	< 0.093 U	0.024 J	< 0.037 U	< 0.056 U	< 0.017 U	< 0.012 U	< 0.017 U	0.29	0.051	0.02 J	< 0.053 U	< 0.055 U	< 0.038 U	< 0.05 U	< 0.017 U	< 0.027 U	< 0.035 U	< 0.099 U	< 0.069 U	< 0.18 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	< 0.091 U	0.07	< 0.036 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.65	0.11	0.033 J	< 0.052 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.097 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	< 0.088 U	0.029 J	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.24	0.05	0.029 J	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.093 U	< 0.065 U	< 0.17 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.42 U	< 0.11 U	< 0.17 U	< 0.25 U	< 0.079 U	< 0.056 U	< 0.079 U	0.7	0.11	0.1 J	< 0.24 U	< 0.25 U	< 0.17 U	< 0.22 U	< 0.079 U	< 0.12 U	< 0.16 U	< 0.45 U	< 0.31 U	< 0.8 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.43 U	< 0.11 U	< 0.17 U	< 0.26 U	< 0.08 U	< 0.057 U	< 0.08 U	0.37	< 0.0038 U	< 0.075 U	< 0.25 U	< 0.25 U	< 0.18 U	< 0.23 U	< 0.08 U	< 0.13 U	< 0.16 U	< 0.46 U	< 0.32 U	< 0.81 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.085 U	< 0.021 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.18	0.036	0.015 J	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U	< 0.063 U	< 0.16 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.33 U	< 0.085 U	< 0.13 U	< 0.2 U	< 0.062 U	< 0.044 U	< 0.062 U	0.41	0.065	< 0.058 U	< 0.19 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.062 U	< 0.098 U	< 0.12 U	< 0.36 U	< 0.25 U	< 0.63 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.2 U	< 0.051 U	< 0.08 U	< 0.12 U	< 0.037 U	< 0.027 U	< 0.037 U	0.25	< 0.0018 U	< 0.035 U	< 0.11 U	< 0.12 U	< 0.083 U	< 0.11 U	< 0.037 U	< 0.059 U	< 0.075 U	< 0.21 U	< 0.15 U	< 0.38 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.077 U	< 0.02 U	< 0.031 U	< 0.046 U	< 0.014 U	< 0.01 U	< 0.014 U	0.17	< 0.00068 U	< 0.013 U	< 0.044 U	< 0.045 U	< 0.032 U	< 0.041 U	< 0.014 U	< 0.023 U	< 0.029 U	< 0.083 U	< 0.058 U	< 0.15 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.4 U	< 0.1 U	< 0.16 U	< 0.24 U	< 0.074 U	< 0.053 U	< 0.074 U	0.28	< 0.0035 U	< 0.069 U	< 0.23 U	< 0.23 U	< 0.16 U	< 0.21 U	< 0.074 U	< 0.12 U	< 0.15 U	< 0.42 U	< 0.3 U	< 0.75 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	< 0.092 U	0.043 J	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.26	< 0.00081 U	0.034 J	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.16	< 0.00081 U	0.018 J	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.17 U	< 0.042 U	< 0.067 U	< 0.1 U	< 0.031 U	< 0.022 U	< 0.031 U	0.35	0.057	0.053 J	< 0.096 U	< 0.098 U	< 0.069 U	< 0.089 U	< 0.031 U	< 0.049 U	< 0.063 U	< 0.18 U	< 0.13 U	< 0.32 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.22 U	< 0.055 U	< 0.087 U	< 0.13 U	< 0.041 U	< 0.029 U	< 0.041 U	0.37	0.055	0.066 J	< 0.12 U	< 0.13 U	< 0.09 U	< 0.12 U	< 0.041 U	< 0.064 U	< 0.081 U	< 0.23 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.34 U	0.098 J	< 0.14 U	< 0.2 U	< 0.063 U	< 0.045 U	< 0.063 U	0.99	< 0.003 U	0.094 J	< 0.19 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.063 U	< 0.099 U	< 0.13 U	< 0.36 U	< 0.25 U	< 0.64 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 1.6 U	< 0.41 U	< 0.65 U	< 0.98 U	< 0.31 U	< 0.22 U	< 0.31 U	0.29	< 0.014 U	< 0.28 U	< 0.94 U	< 0.96 U	< 0.68 U	< 0.87 U	< 0.31 U	< 0.48 U	< 0.61 U	< 1.7 U	< 1.2 U	< 3.1 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	< 0.089 U	< 0.023 U	< 0.036 U	< 0.054 U	< 0.017 U	< 0.012 U	< 0.017 U	0.1	< 0.00079 U	< 0.016 U	< 0.051 U	< 0.052 U	< 0.037 U	< 0.048 U	< 0.017 U	< 0.026 U	< 0.033 U	< 0.095 U	< 0.067 U	< 0.17 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated	< 0.18 U	0.36	< 0.071 U	< 0.11 U	< 0.033 U	< 0.024 U	< 0.033 U	1.4	0.22	0.31	< 0.1 U	< 0.1 U	< 0.074 U	< 0.095 U	< 0.033 U	< 0.052 U	< 0.067 U	< 0.19 U	< 0.13 U	< 0.34 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	< 0.085 U	0.1	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.62	< 0.00075 U	0.13	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U	< 0.063 U	< 0.16 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	< 1.7 U	3.3	< 0.7 U	< 1 U	< 0.33 U	< 0.23 U	< 0.33 U	8.4	1	0.97 J	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.33 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	< 0.22 U	0.15	< 0.089 U	< 0.13 U	< 0.042 U	< 0.03 U	< 0.042 U	1.2	< 0.002 U	0.13 J	< 0.13 U	< 0.13 U	< 0.092 U	< 0.12 U	< 0.042 U	< 0.066 U	< 0.083 U	< 0.24 U	< 0.17 U	< 0.42 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	< 0.087 U	0.047 J	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.5	0.073	0.037 J	< 0.05 U	< 0.051 U	< 0.036 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.065 U	< 0.16 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	< 0.46 U	< 0.12 U	< 0.18 U	< 0.27 U	< 0.085 U	< 0.061 U	< 0.085 U	0.36	< 0.004 U	< 0.079 U	< 0.26 U	< 0.27 U	< 0.19 U	< 0.24 U	< 0.085 U	< 0.13 U	< 0.17 U	< 0.49 U	< 0.34 U	< 0.86 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	< 0.09 U	< 0.023 U	< 0.036 U	< 0.054 U	< 0.017 U	< 0.012 U	< 0.017 U	0.16	0.03	< 0.016 U	< 0.052 U	< 0.053 U	< 0.037 U	< 0.048 U	< 0.017 U	< 0.026 U	< 0.034 U	< 0.096 U	< 0.067 U	< 0.17 U

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated					< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.029 U			< 0.041 U	0.028 J	< 0.0094 U	< 0.0076 U	< 0.008 U	< 0.038 U	< 0.026 U	< 0.0074 U	< 0.025 U		< 0.027 U	0.029 J
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated					0.46						0.14 J				
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated					< 0.42 U	< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U			
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated					< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated					0.49 J	< 4.4 U	< 4.4 U				< 4.4 U	< 4.4 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated					1.5 J	< 3.8 U	< 3.8 U				1.1 J	< 3.8 U			
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated					< 0.43 U	< 0.43 U	< 0.43 U				< 0.43 U	< 0.43 U			
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated					0.28 J	< 0.43 U	< 0.43 U				0.12 J	< 0.43 U			
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated					0.049 J	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U			
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated					< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U			
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated					1						0.31 J				
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated					< 0.41 U	< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U			
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	< 0.14 U			< 0.034 U	2.3	0.045	< 0.0048 U	< 0.027 U	< 0.14 U	< 0.02 U	0.25	< 0.071 U	< 0.066 U	< 0.027 U	0.095
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	< 0.078 U			< 0.019 U	0.2	< 0.00066 U	< 0.0026 U	< 0.015 U	< 0.078 U	< 0.011 U	0.11	< 0.039 U	< 0.036 U	< 0.015 U	0.12
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	< 0.071 U			< 0.017 U	0.65	0.017	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	0.1	< 0.035 U	< 0.033 U	< 0.014 U	0.071
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	< 0.073 U			< 0.018 U	0.0093	< 0.00063 U	< 0.0025 U	< 0.014 U	< 0.073 U	< 0.011 U	0.0044 J	< 0.037 U	< 0.034 U	< 0.014 U	< 0.00059 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.079 U			< 0.019 U	0.34	0.032	< 0.0027 U	< 0.015 U	< 0.079 U	< 0.011 U	0.073	< 0.039 U	< 0.037 U	< 0.015 U	0.018
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.073 U			< 0.018 U	0.25	< 0.00062 U	< 0.0025 U	< 0.014 U	< 0.073 U	< 0.011 U	0.065	< 0.036 U	< 0.034 U	< 0.014 U	0.036
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.18 U			< 0.044 U	0.5	0.03	< 0.0062 U	< 0.035 U	< 0.18 U	< 0.026 U	0.11	< 0.091 U	< 0.085 U	< 0.035 U	0.15
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	< 0.074 U			< 0.018 U	0.02	< 0.00063 U	< 0.0025 U	< 0.014 U	< 0.074 U	< 0.011 U	< 0.00042 U	< 0.037 U	< 0.034 U	< 0.014 U	< 0.00059 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	< 0.071 U			< 0.017 U	0.18	< 0.00061 U	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	0.084	< 0.036 U	< 0.033 U	< 0.014 U	0.13
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	< 0.067 U			< 0.016 U	0.049	< 0.00058 U	< 0.0023 U	< 0.013 U	< 0.067 U	< 0.0098 U	0.024	< 0.034 U	< 0.032 U	< 0.013 U	0.014
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	< 0.074 U			< 0.018 U	0.15	< 0.00063 U	< 0.0025 U	< 0.014 U	< 0.074 U	< 0.011 U	< 0.00042 U	< 0.037 U	< 0.035 U	< 0.014 U	0.063
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	< 0.085 U			< 0.021 U	0.067	< 0.00072 U	< 0.0029 U	< 0.016 U	< 0.085 U	< 0.012 U	0.021	< 0.042 U	< 0.04 U	< 0.016 U	< 0.00068 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	< 0.072 U			< 0.017 U	0.15	< 0.00061 U	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.043	< 0.036 U	< 0.033 U	< 0.014 U	0.0046 J
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	< 0.076 U			< 0.018 U	0.34	0.012	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.19	0.068 J	0.2 J	< 0.015 U	0.088
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	< 0.076 U			< 0.018 U	0.11	0.0045 J	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.076	< 0.038 U	< 0.035 U	< 0.015 U	0.037
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated	< 0.072 U			< 0.017 U	0.04	< 0.00061 U	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.017	< 0.036 U	< 0.034 U	< 0.014 U	< 0.00058 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	< 0.15 U			< 0.036 U	2.2	0.047	< 0.005 U	< 0.028 U	< 0.15 U	< 0.021 U	0.63	< 0.073 U	< 0.069 U	< 0.028 U	0.13
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	< 0.07 U			< 0.017 U	2.1	0.2	< 0.0024 U	< 0.014 U	< 0.07 U	< 0.01 U	0.55	< 0.035 U	< 0.033 U	< 0.014 U	0.28
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	< 0.072 U			< 0.018 U	1	0.039	< 0.0025 U	< 0.014 U	< 0.072 U	< 0.011 U	0.34	< 0.036 U	< 0.034 U	< 0.014 U	0.12
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	< 0.076 U			< 0.018 U	0.97	0.023	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.48	< 0.038 U	< 0.036 U	< 0.015 U	0.16
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated	< 0.3 U			< 0.072 U	3.3	0.087	< 0.01 U	< 0.057 U	< 0.3 U	< 0.043 U	0.55	< 0.15 U	< 0.14 U	< 0.057 U	0.22
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	< 0.15 U			< 0.036 U	1.2	0.035	< 0.005 U	< 0.029 U	< 0.15 U	< 0.021 U	0.52	< 0.074 U	< 0.069 U	< 0.029 U	0.14
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	< 0.069 U			< 0.017 U	0.66	0.019	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U	0.28	< 0.035 U	< 0.032 U	< 0.013 U	0.087
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	< 0.075 U			< 0.018 U	0.46	0.019	< 0.0025 U	< 0.015 U	< 0.075 U	< 0.011 U	0.19	< 0.037 U	< 0.035 U	< 0.015 U	0.074
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	< 0.075 U			< 0.018 U	0.51	0.015	< 0.0026 U	< 0.015 U	< 0.075 U	< 0.011 U	0.27	< 0.038 U	< 0.035 U	< 0.015 U	0.047
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	< 0.72 U			< 0.17 U	0.18	< 0.0062 U	< 0.024 U	< 0.14 U	< 0.72 U	< 0.1 U	0.1	< 0.36 U	< 0.34 U	< 0.14 U	0.21
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	< 0.72 U			< 0.17 U	0.15	< 0.0062 U	< 0.024 U	< 0.14 U	< 0.72 U	< 0.1 U	0.13	< 0.36 U	< 0.34 U	< 0.14 U	0.19
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	< 0.076 U			< 0.018 U	0.35	0.0048 J	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.14	< 0.038 U	< 0.036 U	< 0.015 U	0.024
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	< 0.076 U			< 0.018 U	0.29	0.012	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.11	< 0.038 U	< 0.036 U	< 0.015 U	0.033
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	< 0.077 U			< 0.019 U	0.47	0.0079 J	< 0.0026 U	< 0.015 U	< 0.077 U	< 0.011 U	0.22	< 0.038 U	< 0.036 U	< 0.015 U	0.037
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	< 0.075 U			< 0.018 U	1.3	0.014	< 0.0026 U	< 0.015 U	< 0.075 U	< 0.011 U	0.46	< 0.038 U	< 0.035 U	< 0.015 U	0.046
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	< 0.072 U			< 0.018 U	0.36	0.013	< 0.0025 U	< 0.014 U	< 0.072 U	< 0.011 U	0.16	< 0.036 U	< 0.034 U	< 0.014 U	0.053
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.35 U			< 0.084 U	1.3	0.028 J	< 0.012 U	< 0.067 U	< 0.35 U	< 0.051 U	0.27	< 0.17 U	< 0.16 U	< 0.067 U	0.11
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.36 U			< 0.086 U	0.51	0.045	< 0.012 U	< 0.069 U	< 0.36 U	< 0.052 U	0.15	< 0.18 U	< 0.17 U	< 0.069 U	0.12
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.07 U			< 0.017 U	0.23	< 0.0006 U	< 0.0024 U	< 0.014 U	< 0.07 U	< 0.01 U	0.11	< 0.035 U	< 0.033 U	< 0.014 U	0.042
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.28 U			< 0.067 U	0.48	< 0.0024 U	< 0.0093 U	< 0.053 U	< 0.28 U	< 0.04 U	0.17	< 0.14 U	< 0.13 U	< 0.053 U	0.074
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.17 U			< 0.04 U	0.26	< 0.0014 U	< 0.0056 U	< 0.032 U	< 0.17 U	< 0.024 U	0.07	< 0.083 U	< 0.077 U	< 0.032 U	0.045
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.064 U			< 0.015 U	0.18	< 0.00055 U	< 0.0022 U	< 0.012 U	< 0.064 U	< 0.0093 U	0.048	< 0.032 U	< 0.03 U	< 0.012 U	0.027
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.33 U			< 0.079 U	0.31	< 0.0028 U	< 0.011 U	< 0.063 U	< 0.33 U	< 0.048 U	< 0.0018 U	< 0.16 U	< 0.15 U	< 0.063 U	0.075
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	< 0.076 U			< 0.018 U	0.61	0.044	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.056	< 0.038 U	< 0.035 U	< 0.015 U	0.043
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	< 0.076 U			< 0.018 U	0.31	0.011	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U	0.049	< 0.038 U	< 0.035 U	< 0.015 U	0.036
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.14 U			< 0.034 U	0.47	0.017	< 0.0047 U	< 0.027 U	< 0.14 U	< 0.02 U	0.15	< 0.069 U	< 0.065 U	< 0.027 U	0.15
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.18 U			< 0.044 U	0.53	0.023	< 0.0061 U	< 0.035 U	< 0.18 U	< 0.026 U	0.17	< 0.09 U	< 0.084 U	< 0.035 U	0.16
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.28 U			< 0.068 U	1.8	0.11	< 0.0095 U	< 0.054 U	< 0.28 U	< 0.041 U	0.38	< 0.14 U	< 0.13 U	< 0.054 U	0.11
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 1.4 U			< 0.33 U	0.1 J	< 0.012 U	< 0.046 U	< 0.26 U	< 1.4 U	< 0.2 U	< 0.0076 U	< 0.68 U	< 0.63 U	< 0.26 U	< 0.011 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	< 0.074 U			< 0.018 U	0.24	< 0.00063 U	< 0.0025 U	< 0.014 U	< 0.074 U	< 0.011 U	0.04	< 0.037 U	< 0.035 U	< 0.014 U	0.019
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated	< 0.15 U			< 0.036 U	3.4	0.25	< 0.005 U	< 0.029 U	< 0.15 U	< 0.021 U	0.86	< 0.074 U	< 0.069 U	< 0.029 U	0.33
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	< 0.07 U			< 0.017 U	0.96	0.023	< 0.0024 U	< 0.014 U	< 0.07 U	< 0.01 U	0.41	< 0.035 U	< 0.033 U	< 0.014 U	0.28
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	< 1.4 U			< 0.35 U	25	0.73	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U	4.1	< 0.72 U	< 0.67 U	< 0.28 U	0.39
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	< 0.18 U			< 0.045 U	2.8	0.054	< 0.0063 U	< 0.036 U	< 0.18 U	< 0.027 U	0.45	< 0.092 U	< 0.086 U	< 0.036 U	0.22
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	< 0.072 U			< 0.017 U	0.84	0.03	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.21	< 0.036 U	< 0.033 U	< 0.014 U	0.12
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	< 0.38 U			< 0.091 U	0.51	0.07	< 0.013 U	< 0.073 U	< 0.38 U	< 0.055 U	0.12	< 0.19 U	< 0.18 U	< 0.073 U	0.17
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	< 0.074 U			< 0.018 U	0.23	< 0.00064 U	< 0.0025 U	< 0.014 U	< 0.074 U,F1	< 0.011 U	0.1	< 0.037 U	< 0.035 U	< 0.014 U	0.051

DRAFT

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.47 U	< 0.47 U										< 1.1 U	< 0.47 U	< 0.47 U	< 0.47 U					
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.035 U	0.018 J	< 0.16 U	< 0.15 U	< 0.14 U	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	0.036 J	< 0.0084 U	0.022 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated													0.31 J							
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.42 U	< 0.42 U										< 1 U	< 0.42 U	< 0.42 U	< 0.42 U					
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	< 0.38 U	< 0.38 U										< 0.93 U	< 0.38 U	< 0.38 U	< 0.38 U					
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 4.4 U	1.8 J										< 11 U	1.4 J	< 4.4 U	0.46 J					
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	< 3.8 U	< 3.8 U										< 9.3 U	0.59 J	< 3.8 U	1.7 J					
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.43 U	< 0.43 U										< 1 U	< 0.43 U	< 0.43 U	< 0.43 U					
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.43 U	< 0.43 U										< 1 U	0.11 J	< 0.43 U	0.29 J					
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated	< 0.38 U	< 0.38 U										< 2 U	< 0.38 U	< 0.38 U	0.046 J					
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated	< 0.37 U	< 0.37 U										< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U					
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated													0.47		0.84					
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	< 0.41 U	< 0.41 U										< 1 U	< 0.41 U	< 0.41 U	< 0.41 U					
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated		0.29	< 0.091 U	< 0.11 U	< 0.14 U	< 0.03 U	< 0.03 U	< 0.21 U		< 0.025 U	< 0.027 U	< 0.13 U	1.6	< 0.018 U	1.4		< 0.032 U	< 0.67 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated		0.091	< 0.05 U	< 0.061 U	< 0.075 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.073 U	0.098	< 0.01 U	0.22		< 0.018 U	< 0.37 U	< 0.086 U	< 0.08 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated		0.11	< 0.046 U	< 0.056 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.22	< 0.0091 U	0.51		< 0.016 U	< 0.33 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated		< 0.00097 U	< 0.047 U	< 0.058 U	< 0.071 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.0055 J	< 0.0094 U	0.0093		< 0.017 U	< 0.35 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated		0.024	< 0.051 U	< 0.062 U	< 0.076 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.074 U	0.31	< 0.01 U	0.26		< 0.018 U	< 0.37 U	< 0.088 U	< 0.081 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated		0.056	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.15	< 0.0094 U	0.2		< 0.016 U	< 0.34 U	< 0.081 U	< 0.075 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated		0.25	< 0.12 U	< 0.14 U	< 0.18 U	< 0.038 U	< 0.038 U	< 0.28 U		< 0.032 U	< 0.035 U	< 0.17 U	0.29	< 0.023 U	0.51		< 0.041 U	< 0.86 U	< 0.2 U	< 0.19 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated		< 0.00097 U	< 0.047 U	< 0.058 U	< 0.071 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.069 U	0.0084	< 0.0095 U	0.015		< 0.017 U	< 0.35 U	< 0.082 U	< 0.076 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated		0.43	< 0.046 U	< 0.056 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.067 U	0.12	0.0097 J	0.17		< 0.016 U	< 0.34 U	< 0.079 U	< 0.074 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated		0.011	< 0.043 U	< 0.053 U	< 0.065 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.063 U	0.026	< 0.0087 U	0.043		< 0.015 U	< 0.32 U	< 0.075 U	< 0.07 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated		0.15	< 0.048 U	< 0.058 U	< 0.072 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.069 U	0.086	< 0.0095 U	0.095		< 0.017 U	< 0.35 U	< 0.082 U	< 0.076 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated		0.0077 J	< 0.055 U	< 0.067 U	< 0.082 U	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.079 U	0.031	< 0.011 U	0.056		< 0.019 U	< 0.4 U	< 0.094 U	< 0.088 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated		0.011	< 0.046 U	< 0.057 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.067 U	0.11	< 0.0092 U	0.13		< 0.016 U	< 0.34 U	< 0.08 U	< 0.074 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated		0.28	< 0.049 U	< 0.06 U	< 0.073 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.21	0.15	0.27		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated		0.14	< 0.049 U	< 0.06 U	< 0.073 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.079	0.015 J	0.088		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-0.17-2	7/27/2018	856.16	0.17 - 2 ft	180-80251-2	Excavated		0.011	< 0.046 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.067 U	0.016	< 0.0093 U	0.034		< 0.016 U	< 0.34 U	< 0.08 U	< 0.074 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated		0.27	< 0.095 U	< 0.12 U	< 0.14 U	< 0.031 U	< 0.031 U	< 0.22 U		< 0.026 U	< 0.028 U	< 0.14 U	1.4	< 0.019 U	2.1		< 0.033 U	< 0.69 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated		0.34	< 0.045 U	< 0.055 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.012 U	< 0.014 U	< 0.066 U	1.8	0.0098 J	2.3		< 0.016 U	< 0.33 U	< 0.078 U	< 0.072 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated		0.16	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.63	< 0.0094 U	0.81		< 0.016 U	< 0.34 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated		0.66	< 0.049 U	< 0.06 U	< 0.074 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.013 U	< 0.015 U	< 0.071 U	0.69	0.033 J	0.76		< 0.017 U	< 0.36 U	< 0.085 U	< 0.078 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-0.17-2	7/27/2018	855.97	0.17 - 2 ft	180-80251-2	Excavated		0.81	< 0.19 U	< 0.23 U	< 0.29 U	< 0.062 U	< 0.062 U	< 0.45 U		< 0.053 U	< 0.057 U	< 0.28 U	1.7	0.045 J	2.4		< 0.067 U	< 1.4 U	< 0.33 U	< 0.31 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated		0.38	< 0.095 U	< 0.12 U	< 0.14 U	< 0.031 U	< 0.031 U	< 0.22 U		< 0.026 U	< 0.029 U	< 0.14 U	0.77	0.025 J	1.2		< 0.033 U	< 0.7 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated		0.19	< 0.045 U	< 0.055 U	< 0.067 U	< 0.015 U	< 0.015 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.065 U	0.33	0.012 J	0.5		< 0.016 U	< 0.33 U	< 0.077 U	< 0.071 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated		0.23	< 0.048 U	< 0.059 U	< 0.073 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.07 U	0.33	0.011 J	0.44		< 0.017 U	< 0.35 U	< 0.083 U	< 0.077 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated		0.088	< 0.049 U	< 0.06 U	< 0.073 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.07 U	0.25	< 0.0097 U	0.58		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated		0.42	< 0.47 U	< 0.57 U	< 0.7 U	< 0.15 U	< 0.15 U	< 1.1 U		< 0.13 U	< 0.14 U	< 0.68 U	0.21	< 0.093 U	0.16		< 0.16 U	< 3.4 U	< 0.8 U	< 0.75 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated		0.37	< 0.46 U	< 0.57 U	< 0.7 U	< 0.15 U	< 0.15 U	< 1.1 U		< 0.13 U	< 0.14 U	< 0.67 U	0.2	< 0.093 U	0.17		< 0.16 U	< 3.4 U	< 0.8 U	< 0.74 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated		0.058	< 0.049 U	< 0.06 U	< 0.074 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.071 U	0.15	< 0.0098 U	0.61		< 0.017 U	< 0.36 U	< 0.085 U	< 0.079 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated		0.066	< 0.049 U	< 0.06 U	< 0.074 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.071 U	0.19	0.016 J	0.32		< 0.017 U	< 0.36 U	< 0.085 U	< 0.079 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated		0.073	< 0.05 U	< 0.061 U	< 0.074 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.072 U	0.2	< 0.0099 U	0.4		< 0.017 U	< 0.36 U	< 0.086 U	< 0.079 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated		0.1	< 0.049 U	< 0.06 U	< 0.073 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.52	0.012 J	1		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated		0.12	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.2	< 0.0093 U	0.37		< 0.016 U	< 0.34 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated		0.23	< 0.22 U	< 0.28 U	< 0.34 U	< 0.073 U	< 0.073 U	< 0.53 U		< 0.062 U	< 0.067 U	< 0.33 U	0.93	< 0.045 U	0.95		< 0.079 U	< 1.6 U	< 0.39 U	< 0.36 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated		0.14	< 0.23 U	< 0.28 U	< 0.34 U	< 0.075 U	< 0.075 U	< 0.54 U		< 0.063 U	< 0.069 U	< 0.33 U	0.43	< 0.046 U	0.42		< 0.08 U	< 1.7 U	< 0.4 U	< 0.37 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated		0.069	< 0.045 U	< 0.055 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.012 U	< 0.014 U	< 0.066 U	0.096	< 0.0091 U	0.21		< 0.016 U	< 0.33 U	< 0.078 U	< 0.072 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated		0.064	< 0.18 U	< 0.22 U	< 0.27 U	< 0.058 U	< 0.058 U	< 0.42 U		< 0.049 U	< 0.053 U	< 0.26 U	0.17	< 0.036 U	0.53		< 0.062 U	< 1.3 U	< 0.31 U	< 0.28 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated		0.054	< 0.11 U	< 0.13 U	< 0.16 U	< 0.035 U	< 0.035 U	< 0.25 U		< 0.029 U	< 0.032 U	< 0.15 U	0.1	< 0.021 U	0.2		< 0.037 U	< 0.78 U	< 0.18 U	< 0.17 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated		< 0.00085 U	< 0.041 U	< 0.051 U	< 0.062 U	< 0.013 U	< 0.013 U	< 0.097 U		< 0.011 U	< 0.012 U	< 0.06 U	0.08	< 0.0083 U	0.16		< 0.014 U	< 0.3 U	< 0.071 U	< 0.066 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated		0.022 J	< 0.21 U	< 0.26 U	< 0.32 U	< 0.069 U	< 0.069 U	< 0.5 U		< 0.058 U	< 0.063 U	< 0.31 U	0.19	< 0.042 U	0.2		< 0.074 U	< 1.5 U	< 0.36 U	< 0.34 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated		0.047	< 0.049 U	< 0.06 U	< 0.073 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.41	< 0.0098 U	0.39		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated		0.088	< 0.049 U	< 0.06 U	< 0.073 U	0.049 J	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.15	< 0.0098 U	0.2		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated		0.12	< 0.089 U	< 0.11 U	< 0.13 U	< 0.029 U	< 0.029 U	< 0.21 U		< 0.025 U	< 0.027 U	< 0.13 U	0.32	< 0.018 U	0.37		< 0.031 U	< 0.65 U	< 0.15 U	< 0.14 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated		0.14	< 0.12 U	< 0.14 U	< 0.17 U	< 0.038 U	< 0.038 U	< 0.27 U		< 0.032 U	< 0.035 U	< 0.17 U	0.37	< 0.023 U	0.43		< 0.041 U	< 0.85 U	< 0.2 U	< 0.19 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated		0.12	< 0.18 U	< 0.22 U	< 0.27 U	< 0.059 U	< 0.059 U	< 0.42 U		< 0.05 U	< 0.054 U	< 0.26 U	0.81	< 0.036 U	1.6		< 0.063 U	< 1.3 U	< 0.31 U	< 0.29 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated		< 0.018 U	< 0.87 U	< 1.1 U	< 1.3 U	< 0.28 U	< 0.28 U	< 2.1 U		< 0.24 U	< 0.26 U	< 1.3 U	0.12 J	< 0.17 U	0.15		< 0.31 U	< 6.4 U	< 1.5 U	< 1.4 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated		0.045	< 0.048 U	< 0.058 U	< 0.072 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.069 U	0.1	< 0.0095 U	0.16		< 0.017 U	< 0.35 U	< 0.082 U	< 0.076 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-0.17-2	7/26/2018	855.14	0.17 - 2 ft	180-80227-3	Excavated		0.9	< 0.095 U	< 0.12 U	< 0.14 U	< 0.031 U	< 0.031 U	< 0.22 U		< 0.026 U	< 0.029 U	< 0.14 U	2.5	< 0.019 U	2.7		< 0.033 U	< 0.7 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated		0.54	< 0.045 U	< 0.056 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.012 U	< 0.014 U	< 0.066 U	0.61	0.035 J	0.8		< 0.016 U	< 0.33 U	< 0.078 U	< 0.073 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated		0.72	< 0.93 U	< 1.1 U	< 1.4 U	< 0.3 U	< 0.3 U	< 2.2 U		< 0.26 U	< 0.28 U	< 1.3 U	19	< 0.19 U	20		< 0.33 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated		0.62	< 0.12 U	< 0.15 U	< 0.18 U	< 0.039 U	< 0.039 U	< 0.28 U		< 0.033 U	< 0.036 U	< 0.17 U	1.1	< 0.024 U	2.3		< 0.042 U	< 0.87 U	< 0.21 U	< 0.19 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated		0.12	< 0.046 U	< 0.057 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.067 U	0.53	< 0.0092 U	0.64		< 0.016 U	< 0.34 U	< 0.08 U	< 0.074 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated		0.097	< 0.24 U	< 0.3 U	< 0.36 U	< 0.079 U	< 0.079 U	< 0.57 U		< 0.067 U	< 0.073 U	< 0.35 U	0.52	< 0.049 U	0.5		< 0.085 U	< 1.8 U	< 0.42 U	< 0.39 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated		0.05	< 0.048 U	< 0.059 U	< 0.072 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.07 U,F1	0.086	< 0.0096 U	0.19		< 0.017 U	< 0.35 U,F1	< 0.083 U	< 0.077 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated			2.0927	0.0057 J	0.048	0.015 J	0.023	< 0.044 U	< 0.021 U	< 0.028 U	0.17	0.2	0.32	0.11	0.15	< 0.015 U	< 0.015 U	< 0.012 U	0.072 J	< 0.017 U	< 0.027 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated			0.742	< 0.00089 U	0.013	< 0.013 U	0.015	< 0.042 U	< 0.02 U	< 0.027 U	0.058	0.061	0.091	0.031	0.055	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated			0.2901	< 0.00092 U	< 0.00042 U	< 0.013 U	< 0.00094 U	< 0.043 U	< 0.021 U	< 0.028 U	0.025	0.029	0.038	< 0.00082 U	0.025	< 0.014 U	< 0.014 U	< 0.012 U	0.1	< 0.017 U	< 0.027 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated			0.4945	< 0.0017 U	< 0.00078 U	< 0.025 U	0.0075 J	< 0.081 U	< 0.038 U	< 0.051 U	0.038	0.038	0.059	0.021	0.035	< 0.027 U	< 0.027 U	< 0.022 U	< 0.11 U	< 0.031 U	< 0.049 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated			44.59	1.4	0.061	< 0.086 U	2.3	< 0.28 U	0.17 J	< 0.18 U	2.9	2.6	3.7	1.2	0.77	< 0.094 U	< 0.094 U	< 0.079 U	0.79	< 0.11 U	< 0.17 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated			2.216	< 0.0009 U	0.074	< 0.013 U	0.046	< 0.042 U	< 0.02 U	< 0.027 U	0.18	0.2	0.26	0.1	0.16	< 0.014 U	< 0.014 U	< 0.012 U	< 0.06 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated			3.091	0.012	0.11	< 0.013 U	0.049	< 0.043 U	< 0.02 U	< 0.027 U	0.27	0.29	0.41	0.15	0.23	< 0.014 U	< 0.014 U	< 0.012 U	< 0.06 U	< 0.017 U	< 0.026 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated			8.093	0.058	0.22	< 0.013 U	0.21	< 0.042 U	< 0.02 U	< 0.027 U	0.73	0.75	1.2	0.52	0.32	< 0.014 U	< 0.014 U	< 0.012 U	< 0.06 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated			2.8003	0.0083	0.12	< 0.013 U	0.045	< 0.043 U	< 0.02 U	< 0.027 U	0.24	0.23	0.47	0.18	0.13	< 0.014 U	< 0.014 U	< 0.012 U	0.088	< 0.017 U	< 0.026 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated			3.079	< 0.00089 U	0.081	< 0.013 U	0.046	< 0.042 U	< 0.02 U	< 0.027 U	0.26	0.24	0.33	0.09	0.17	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated			0.2707	< 0.00084 U	0.0048 J	< 0.012 U	0.0057 J	< 0.04 U	< 0.019 U	< 0.025 U	0.021	0.021	0.039	0.016	0.019	< 0.013 U	< 0.013 U	< 0.011 U	< 0.056 U	< 0.015 U	< 0.024 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated			4.5	< 0.018 U	< 0.0082 U	< 0.26 U	0.13 J	< 0.84 U	< 0.4 U	< 0.54 U	< 0.015 U	< 0.015 U	0.34	< 0.016 U	< 0.0082 U	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.33 U	< 0.51 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated			4.78	< 0.022 U	< 0.01 U	< 0.32 U	< 0.023 U	< 1.1 U	< 0.5 U	< 0.67 U	0.57	< 0.019 U	0.31	< 0.02 U	< 0.01 U	< 0.35 U	< 0.35 U	< 0.29 U	< 1.5 U	< 0.41 U	< 0.64 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated			0.0774	< 0.00083 U	< 0.00038 U	< 0.012 U	< 0.00085 U	< 0.039 U	< 0.019 U	< 0.025 U	0.0064 J	0.0076	0.011	0.004 J	0.0062 J	< 0.013 U	< 0.013 U	< 0.011 U	< 0.056 U	< 0.015 U	< 0.024 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated			0.0771	< 0.00086 U	< 0.0004 U	< 0.012 U	< 0.00088 U	< 0.041 U	< 0.019 U	0.029 J	0.0081	< 0.00072 U	0.015	< 0.00077 U	0.016	< 0.014 U	< 0.014 U	< 0.011 U	< 0.058 U	< 0.016 U	< 0.025 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated			1.286	< 0.00087 U	0.026	< 0.013 U	0.035	< 0.041 U	0.031 J	< 0.026 U	0.077	0.089	0.17	0.06	0.041	< 0.014 U	< 0.014 U	< 0.011 U	0.15	< 0.016 U	< 0.025 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated			1.268	< 0.0018 U	0.026	< 0.026 U	0.033	< 0.084 U	< 0.039 U	< 0.053 U	0.088	0.12	0.17	0.094	< 0.00081 U	< 0.028 U	< 0.028 U	< 0.023 U	0.13 J	< 0.032 U	< 0.051 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated			3.768	< 0.069 U	0.14 J	< 0.065 U	0.11 J	< 0.53 U	< 0.051 U		0.3	0.29	0.39	0.15 J	0.38	< 0.057 U	< 0.044 U	< 0.089 U	< 1.3 U	< 0.084 U	< 0.83 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated			0.637	< 0.023 U	0.027 J	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U		0.015 J	0.056 J	0.075 J	< 0.024 U	0.098	< 0.019 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated			6.765	< 0.022 U	0.44	< 0.021 U	0.23	< 0.17 U	0.057 J		0.38 J	0.52 J	0.75 J	0.25 J	0.94	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated			11.288	< 0.022 U	0.53	< 0.021 U	0.29	< 0.17 U	0.055 J		0.69 J	0.97 J	1.4 J	0.52 J	1.5	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated			9.796	< 0.022 U	0.41	< 0.021 U	0.23	< 0.17 U	0.051 J		0.82	0.87	1.3	0.53	0.9	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated			3.137	< 0.022 U	0.089	< 0.021 U	0.079	< 0.17 U	< 0.016 U		0.25	0.27	0.38	0.13	0.26	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated			0.938	< 0.023 U	0.032 J	< 0.022 U	0.025 J	< 0.18 U	< 0.017 U	< 0.05 R	0.089	0.093	0.12	0.042 J	0.071 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated			0.826	< 0.024 U	0.021 J	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 R	0.073 J	0.084	0.1	0.036 J	0.066 J	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	0.32 J
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated			11.489	0.05 J	0.29	0.024 J	0.47	< 0.16 U	0.042 J		0.83	0.85	1.1	0.36	0.87	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated			2.626	< 0.023 U	0.11	< 0.021 U	0.076 J	< 0.17 U	0.02 J		0.18	0.2	0.25	0.13	0.21	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated			2.216	< 0.022 U	0.087	< 0.021 U	0.073 J	< 0.17 U	0.033 J		0.15	0.17	0.23	0.092	0.2	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated			5.426	< 0.023 U	0.2	< 0.022 U	0.13	< 0.18 U	0.024 J		0.38	0.52	0.66	0.23	0.66	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated			0.172	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U		0.021 J	0.018 J	0.023 J	< 0.024 U	0.019 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	0.31 J
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated			1.664	< 0.024 U	0.065 J	< 0.022 U	0.05 J	< 0.18 U	< 0.017 U		0.14	0.15	0.19	0.074 J	0.13	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated			0.189	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U		0.022 J	0.023 J	0.028 J	< 0.025 U	0.024 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated			0.349	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U		0.035 J	0.035 J	0.048 J	< 0.025 U	0.034 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated			1.277	< 0.024 U	0.025 J	< 0.023 U	0.046 J	< 0.18 U	< 0.018 U		0.11	0.1	0.12	0.06 J	0.08 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated			43.52	0.43	0.71	< 0.11 U	1.7	< 0.88 U	0.13 J		3.5	3.1	4.1	1.2	2.9	< 0.095 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated			11.285	0.096	0.11	< 0.021 U	0.36	< 0.17 U	0.025 J		0.97	0.86	1.1	0.41	0.66	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated			0.6	0.024 J	< 0.017 U	< 0.021 U	0.026 J	< 0.17 U	< 0.016 U	< 0.048 R	0.038 J	0.028 J	0.053 J	< 0.023 U	0.037 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated			4.803	0.058 J	0.077	< 0.02 U	0.16	< 0.16 U	< 0.015 U	< 0.045 R	0.39	0.36	0.57	0.16	0.31	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated			1.247	< 0.022 U	0.034 J	< 0.02 U	0.041 J	< 0.16 U	< 0.016 U	< 0.046 R	0.11	0.097	0.14	0.061 J	0.085	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2900	DUP-01	11/6/2019	855.76	0.17 - 2 ft	180-98355-3	Excavated			1.689	< 0.023 U	0.031 J	< 0.021 U	0.039 J	< 0.17 U	0.025 J	< 0.049 U	0.14	0.12	0.15	0.053 J	0.11	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2900	SSHS-B2900-SUB-0.17-2	11/6/2019	855.76	0.17 - 2 ft	180-98355-2	Excavated			2.154	< 0.024 U	0.036 J	< 0.022 U	0.049 J	< 0.18 U	0.027 J	< 0.051 U	0.16	0.16	0.2	0.067 J	0.14	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Football Field	SSHS-B2901	DUP-02	11/6/2019	856.05	0.17 - 2 ft	180-98355-3	Excavated			4.195	0.024 J	0.1 J	< 0.022 U	0.093	< 0.18 U	0.055 J	< 0.051 U	0.28	0.28	0.37	0.14	0.37 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U	< 0.28 U
Football Field	SSHS-B2901	SSHS-B2901-SUB-0.17-2	11/6/2019	856.05	0.17 - 2 ft	180-98355-2	Excavated			3.265	< 0.022 UJ	0.053 J	< 0.021 U	0.091	< 0.17 U	0.03 J	< 0.048 U	0.27	0.22	0.3	0.12	0.2 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2911	SSHS-B2911-SUB-0.17-2	11/6/2019	854.88	0.17 - 2 ft	180-98355-2	Excavated			4.124	0.038 J	0.03 J	< 0.021 U	0.14	< 0.17 U	< 0.016 U	< 0.047 U	0.38 J	0.32	0.38	0.17	0.21	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2912	DUP-04	11/5/2019	855.19	0.17 - 2 ft	180-98355-3	Excavated			100.6	1.5	0.26 J	< 0.084 U	4.9	< 0.67 U	0.16 J	< 0.19 U	9.1	6.8	7.4	3	4.2	< 0.073 U	< 0.056 U	< 0.11 U	< 1.6 U	< 0.11 U	< 1.1 U
Football Field	SSHS-B2912	SSHS-B2912-SUB-0.17-2	11/5/2019	855.19	0.17 - 2 ft	180-98355-1	Excavated			127.3	2.4	0.26 J	< 0.17 U	7.2	< 1.4 U	0.31 J	< 0.39 U	11	8.4	8.2	4.2	4.2	< 0.15 U	< 0.11 U	< 0.23 U	< 3.4 U	< 0.22 U	< 2.2 U
Football Field	SSHS-B2938	SSHS-B2938-SUB-0.17-2	11/6/2019	855.53	0.17 - 2 ft	180-98355-3	Excavated			36.088	0.046 J	0.48	< 0.021 U	0.48	< 0.17 U	0.11 J	< 0.048 U	1.4	1.3	1.8	0.61	1.8	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2939	SSHS-B2939-SUB-0.17-2	11/6/2019	855.56	0.17 - 2 ft	180-98355-3	Excavated			30.412	< 0.068 U	0.46	< 0.064 U	0.39	< 0.52 U	0.082 J	< 0.15 U	1.2	1.2	1.4	0.65	1.3	< 0.057 U	< 0.043 U	< 0.088 U	< 1.3 U	< 0.083 U	< 0.82 U
Football Field	SSHS-B2940	SSHS-B2940-SUB-0.17-2	11/6/2019	855.06	0.17 - 2 ft	180-98355-3	Excavated			1.99	< 0.022 U	0.029 J	< 0.021 U	0.023 J	< 0.17 U	< 0.016 U	< 0.047 U	0.085	0.083	0.11	0.037 J	0.096	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2941	SSHS-B2941-SUB-0.17-2	11/6/2019	855.17	0.17 - 2 ft	180-98355-3	Excavated			23.772	< 0.042 U	0.22	< 0.04 U	0.25	< 0.32 U	0.038 J	< 0.091 U	1.1	0.95	1.2	0.4	0.9	< 0.035 U	< 0.027 U	< 0.055 U	< 0.78 U	< 0.051 U	< 0.51 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated			2.64		0.092 J		0.11 J				0.21 J	0.29 J	0.47	0.18 J	0.23 J				0.53		
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 45 U		7.58	< 0.025 U	0.24	< 0.024 U	0.2	< 0.19 U	< 0.018 U	< 0.054 U	0.69	0.71	0.85	0.35	0.73	< 0.021 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.031 U	< 0.3 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 44 U		0.044	< 0.024 U	< 0.018 UJ	< 0.023 U	< 0.022 UJ	< 0.18 U	< 0.018 U	< 0.052 U	< 0.016 UJ	< 0.018 UJ	< 0.021 UJ	< 0.025 UJ	< 0.018 UJ	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	51 J		0.798	< 0.022 U	0.034 J	< 0.021 U	0.021 J	< 0.17 U	< 0.016 U	< 0.048 U	0.084	0.075 J	0.11	0.045 J	0.06 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	61		2.159	< 0.021 U	0.048 J	< 0.02 U	0.047 J	< 0.16 U	< 0.015 U	< 0.045 U	0.13	0.25	0.33	0.13	0.29	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 40 U		ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.014 U	< 0.017 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 38 U		0.124	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.016 J	0.018 J	0.026 J	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 40 U		0.295	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.035 J	0.031 J	0.048 J	< 0.023 U	0.027 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 40 U		0.206	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.03 J	0.024 J	0.032 J	< 0.023 U	< 0.016 UJ	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 39 U		ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		< 0.015 U	< 0.017 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 39 U		0.507	< 0.021 U	0.021 J	< 0.02 U	0.019 J	< 0.16 U	< 0.015 U		0.048 J	0.052 J	0.049 J	0.027 J	0.041 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 37 U		0.077	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.015 J	< 0.016 U	0.021 J	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	540		0.859	< 0.023 U	0.033 J	< 0.021 U	0.049 J	< 0.17 U	< 0.016 U		0.079	0.063 J	0.068 J	0.041 J	0.13	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 42 U		ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.015 U	< 0.017 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	93		0.879	< 0.023 U	0.043 J	< 0.021 U	0.029 J	< 0.17 U	< 0.017 U	< 0.049 U	0.047 J	0.068 J	0.087	0.042 J	0.12	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	2300		ND	< 0.044 U	0.077 J	< 0.041 U	< 0.039 U	< 0.33 U	< 0.032 U	< 0.095 U	< 0.029 U	< 0.033 U	< 0.037 U	< 0.046 U	< 0.033 U	< 0.036 U	< 0.028 U	< 0.056 U	< 0.81 U	< 0.053 U	< 0.52 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	49 J		6.907	< 0.021 U	0.11	< 0.02 U	0.082	< 0.16 U	< 0.015 U	< 0.045 U	0.67	0.65	0.78	0.28	0.67	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	< 0.093 U	< 0.023 U	< 0.037 U	< 0.056 U	< 0.017 U	< 0.012 U	< 0.017 U	0.21	0.039	0.032 J	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.035 U	< 0.099 U	< 0.069 U	< 0.18 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	< 0.087 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.074	< 0.00077 U	< 0.015 U	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.093 U	< 0.065 U	< 0.17 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	< 0.09 U	< 0.023 U	< 0.036 U	< 0.054 U	< 0.017 U	< 0.012 U	< 0.017 U	0.045	< 0.0008 U	< 0.016 U	< 0.052 U	< 0.053 U	< 0.037 U	< 0.048 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.097 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	< 0.17 U	< 0.042 U	< 0.067 U	< 0.1 U	< 0.031 U	< 0.022 U	< 0.031 U	0.047	< 0.0015 U	< 0.029 U	< 0.096 U	< 0.098 U	< 0.069 U	< 0.089 U	< 0.031 U	< 0.049 U	< 0.063 U	< 0.18 U	< 0.13 U	< 0.32 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	< 0.59 U	1.2	< 0.24 U	< 0.35 U	< 0.11 U	< 0.079 U	< 0.11 U	2.6	< 0.0052 U	1	< 0.34 U	< 0.35 U	< 0.24 U	< 0.31 U	< 0.11 U	< 0.17 U	< 0.22 U	< 0.63 U	< 0.44 U	< 1.1 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	< 0.088 U	< 0.022 U	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.21	0.036	0.021 J	< 0.051 U	< 0.052 U	< 0.037 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.094 U	< 0.066 U	< 0.17 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	< 0.089 U	< 0.023 U	< 0.036 U	< 0.053 U	< 0.017 U	< 0.012 U	< 0.017 U	0.34	0.055	0.021 J	< 0.051 U	< 0.052 U	< 0.037 U	< 0.047 U	< 0.017 U	< 0.026 U	< 0.033 U	< 0.095 U	< 0.066 U	< 0.17 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	< 0.088 U	0.07	< 0.035 U	< 0.053 U	< 0.016 U	< 0.012 U	< 0.016 U	0.76	0.11	0.052 J	< 0.051 U	< 0.052 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.094 U	< 0.066 U	< 0.17 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	< 0.09 U	< 0.023 U	< 0.036 U	< 0.054 U	< 0.017 U	< 0.012 U	< 0.017 U	0.31	< 0.00079 U	0.032 J	< 0.051 U	< 0.053 U	< 0.037 U	< 0.048 U	< 0.017 U	< 0.026 U	< 0.033 U	< 0.096 U	< 0.067 U	< 0.17 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	< 0.087 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.31	0.044	< 0.015 U	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.093 U	< 0.065 U	< 0.17 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.015 U	< 0.011 U	< 0.015 U	0.033	< 0.00073 U	< 0.014 U	< 0.047 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.015 U	< 0.024 U	< 0.031 U	< 0.088 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	< 1.7 U	< 0.44 U	< 0.7 U	< 1 U	< 0.33 U	< 0.23 U	< 0.33 U	1.5	< 0.015 U	< 0.3 U	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.33 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	< 2.2 U	< 0.56 U	< 0.88 U	< 1.3 U	< 0.41 U	< 0.29 U	< 0.41 U	1.4	< 0.019 U	< 0.38 U	< 1.3 U	< 1.3 U	< 0.91 U	< 1.2 U	< 0.41 U	< 0.64 U	< 0.82 U	< 2.3 U	< 1.6 U	< 4.2 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.082 U	< 0.021 U	< 0.033 U	< 0.049 U	< 0.015 U	< 0.011 U	< 0.015 U	0.0088	< 0.00072 U	< 0.014 U	< 0.047 U	< 0.048 U	< 0.034 U	< 0.044 U	< 0.015 U	< 0.024 U	< 0.031 U	< 0.087 U	< 0.061 U	< 0.16 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.085 U	< 0.022 U	< 0.034 U	< 0.051 U	< 0.016 U	< 0.011 U	< 0.016 U	0.013	< 0.00075 U	< 0.015 U	< 0.049 U	< 0.05 U	< 0.035 U	< 0.045 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.091 U	< 0.063 U	< 0.16 U,F2
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.086 U	< 0.022 U	< 0.034 U	< 0.052 U	< 0.016 U	< 0.011 U	< 0.016 U	0.14	< 0.00076 U	0.034 J	< 0.049 U	< 0.05 U	< 0.036 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.064 U	< 0.16 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.17 U	< 0.044 U	< 0.07 U	< 0.1 U	< 0.032 U	< 0.023 U	< 0.032 U	0.13	< 0.0015 U	< 0.03 U	< 0.1 U	< 0.1 U	< 0.072 U	< 0.093 U	< 0.032 U	< 0.051 U	< 0.065 U	< 0.19 U	< 0.13 U	< 0.33 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	< 0.78 U	0.056 J	< 0.04 U	< 0.057 U	< 0.055 U	< 0.056 U	< 0.073 U	0.29	0.078 J	< 0.053 U	< 1.1 U	< 0.093 U	< 0.42 U	< 0.075 U	< 0.044 U	< 0.53 U	< 0.7 U	< 2.1 U	< 0.074 U	< 3.2 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.076 J	< 0.018 U	0.017 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.1	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.42 J	0.16 J	0.12 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.12	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.72 J	0.3 J	0.14 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.072 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.73	0.19	0.13 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.025 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.25	0.058 J	0.029 J	< 0.36 UJ	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.09	0.024 J	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.08 J	0.02 J	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	< 0.24 U	0.13	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.83	0.2	0.12 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.033 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.2	0.053 J	0.039 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.031 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.15	0.041 J	0.053 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.26 U	0.053 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.37	0.14	0.04 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	0.017 J	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.16	0.034 J	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.019 J	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 1.1 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.032 J	< 0.018 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 1.1 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	0.11	0.027 J	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 1.3 U	0.72	< 0.067 U	< 0.094 U	< 0.092 U	< 0.093 U	< 0.12 U	3.1	0.73	0.53 J	< 1.9 U	< 0.15 U	< 0.7 U	< 0.12 U	< 0.073 U	< 0.88 U	< 1.2 U	< 3.4 U	< 0.12 U	< 5.4 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	< 0.25 U	0.14	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.97	0.22	0.08 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.037 J	< 0.017 U	0.017 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.24 U	0.073	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.37	0.086	0.042 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.98 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.24 U	< 0.018 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.11	0.025 J	0.018 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2900	DUP-01	11/6/2019	855.76	0.17 - 2 ft	180-98355-3	Excavated	< 0.26 U	0.022 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.2	0.031 J	0.039 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Football Field	SSHS-B2900	SSHS-B2900-SUB-0.17-2	11/6/2019	855.76	0.17 - 2 ft	180-98355-2	Excavated	< 0.27 U	0.025 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.26	0.035 J	0.043 J	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 UJ	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 UJ	< 0.026 U	< 1.1 U
Football Field	SSHS-B2901	DUP-02	11/6/2019	856.05	0.17 - 2 ft	180-98355-3	Excavated	< 0.27 U	0.041 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.48	0.081 J	0.087 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2901	SSHS-B2901-SUB-0.17-2	11/6/2019	856.05	0.17 - 2 ft	180-98355-2	Excavated	< 0.25 U	0.035 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.33	0.062 J	0.049 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B2911	SSHS-B2911-SUB-0.17-2	11/6/2019	854.88	0.17 - 2 ft	180-98355-2	Excavated	< 0.25 U	0.058 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.39 J	0.06 J	0.04 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 1 U
Football Field	SSHS-B2912	DUP-04	11/5/2019	855.19	0.17 - 2 ft	180-98355-3	Excavated	< 1 U	1.8	< 0.051 U	< 0.072 U	< 0.071 U	< 0.072 U	< 0.093 U	8.4	1.3	1.2 J	< 1.4 U	< 0.12 U	< 0.54 U	< 0.096 U	< 0.056 U	< 0.67 U	< 0.9 U	< 2.7 U	< 0.095 U	< 4.1 U
Football Field	SSHS-B2912	SSHS-B2912-SUB-0.17-2	11/5/2019	855.19	0.17 - 2 ft	180-98355-1	Excavated	< 2.1 U	2.6	< 0.11 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.19 U	9.7	1.5	2.1 J	< 3 U	< 0.24 U	< 1.1 U	< 0.2 U	< 0.11 U	< 1.4 U	< 1.8 U	< 5.5 U	< 0.2 U	< 8.5 U
Football Field	SSHS-B2938	SSHS-B2938-SUB-0.17-2	11/6/2019	855.53	0.17 - 2 ft	180-98355-3	Excavated	< 0.25 U	0.24	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.4	0.35	0.27 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B2939	SSHS-B2939-SUB-0.17-2	11/6/2019	855.56	0.17 - 2 ft	180-98355-3	Excavated	< 0.77 U	0.18 J	< 0.04 U	< 0.056 U	< 0.054 U	< 0.055 U	< 0.072 U	1.2	0.28	0.19 J	< 1.1 U	< 0.092 U	< 0.42 U	< 0.074 U	< 0.043 U	< 0.52 U	< 0.69 U	< 2 UJ	< 0.073 U	< 3.2 U
Football Field	SSHS-B2940	SSHS-B2940-SUB-0.17-2	11/6/2019	855.06	0.17 - 2 ft	180-98355-3	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.11	0.018 J	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Football Field	SSHS-B2941	SSHS-B2941-SUB-0.17-2	11/6/2019	855.17	0.17 - 2 ft	180-98355-3	Excavated	< 0.48 U	0.15	< 0.025 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.045 U	1.3	0.25	0.078 J	< 0.69 U	< 0.057 U	< 0.26 U	< 0.046 U	< 0.027 U	< 0.32 U	< 0.43 U	< 1.3 U	< 0.046 U	< 2 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated								0.25 J												
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 0.29 U	0.047 J	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	0.65	0.14	0.042 J	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.76 U	< 0.027 U	< 1.2 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.016 UJ	< 0.019 UJ	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.089	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.13	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.02 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.036 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.025 J	< 0.017 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.064 J	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.078 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.016 U	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.067 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	< 0.5 U	< 0.036 U	< 0.025 U	< 0.036 U	< 0.035 U	< 0.035 U	< 0.046 U	< 0.03 U	< 0.034 U	< 0.033 U	< 0.71 U	< 0.059 U	< 0.27 U	< 0.047 U	< 0.028 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.047 U	< 2 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	< 0.24 U	0.055 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.64	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	< 0.077 U			< 0.019 U	0.24	< 0.00065 U	< 0.0026 U	< 0.015 U	< 0.077 U	< 0.011 U	0.12	< 0.038 U	< 0.036 U	< 0.015 U	0.13
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	< 0.072 U			< 0.017 U	0.11	< 0.00062 U	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.042	< 0.036 U	< 0.034 U	< 0.014 U	0.027
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	< 0.075 U			< 0.018 U	0.046	< 0.00064 U	< 0.0025 U	< 0.014 U	< 0.075 U	< 0.011 U	< 0.00042 U	< 0.037 U	< 0.035 U	< 0.014 U	0.012
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	< 0.14 U			< 0.034 U	0.074	< 0.0012 U	< 0.0047 U	< 0.027 U	< 0.14 U	< 0.02 U	0.027	< 0.069 U	< 0.065 U	< 0.027 U	0.014 J
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	< 0.49 U			< 0.12 U	9.2	1.6	< 0.017 U	< 0.094 U	< 0.49 U	< 0.071 U	0.72	< 0.24 U	< 0.23 U	< 0.094 U	0.79
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	< 0.073 U			< 0.018 U	0.39	0.013	< 0.0025 U	< 0.014 U	< 0.073 U	< 0.011 U	0.13	< 0.037 U	< 0.034 U	< 0.014 U	0.039
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	< 0.074 U			< 0.018 U	0.46	0.016	< 0.0025 U	< 0.014 U	< 0.074 U,F1	< 0.011 U	0.2	< 0.037 U	< 0.034 U	< 0.014 U	0.048
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	< 0.073 U			< 0.018 U	1.2	0.075	< 0.0025 U	< 0.014 U	< 0.073 U	< 0.011 U	0.3	< 0.036 U	< 0.034 U	< 0.014 U	0.11
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	< 0.074 U			< 0.018 U	0.41	< 0.00063 U	< 0.0025 U	< 0.014 U	< 0.074 U	< 0.011 U	0.12	< 0.037 U	< 0.035 U	< 0.014 U	0.12
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	< 0.072 U			< 0.017 U	0.6	0.012	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.16	< 0.036 U	< 0.034 U	< 0.014 U	0.056
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	< 0.068 U			< 0.017 U	0.034	< 0.00058 U	< 0.0023 U	< 0.013 U	< 0.068 U	< 0.0099 U	0.013	< 0.034 U	< 0.032 U	< 0.013 U	0.014
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	< 1.4 U			< 0.35 U	0.43	< 0.012 U	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U	< 0.0082 U	< 0.72 U	< 0.68 U	< 0.28 U	0.27
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	< 1.8 U			< 0.44 U	0.45	< 0.016 U	< 0.061 U	< 0.35 U	< 1.8 U	< 0.26 U	< 0.01 U	< 0.91 U	< 0.85 U	< 0.35 U	0.32
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.068 U			< 0.016 U	0.011	< 0.00058 U	< 0.0023 U	< 0.013 U	< 0.068 U	< 0.0098 U	0.0063 J	< 0.034 U	< 0.032 U	< 0.013 U	< 0.00055 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.07 U			< 0.017 U	0.013	< 0.0006 U	< 0.0024 U	< 0.014 U	< 0.07 U,F1	< 0.01 U	< 0.0004 U	< 0.035 U	< 0.033 U	< 0.014 U	< 0.00057 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.071 U			< 0.017 U	0.19	0.024	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	< 0.0004 U	< 0.036 U	0.04 J	< 0.014 U	0.15
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.14 U			< 0.035 U	0.22	< 0.0012 U	< 0.0049 U	< 0.028 U	< 0.14 U	< 0.021 U	< 0.00081 U	< 0.072 U	< 0.067 U	< 0.028 U	0.051
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	< 0.06 U			< 0.38 U	0.56	< 0.047 U	< 0.086 U	< 0.07 U	< 0.12 U	< 0.062 U	0.26	< 0.35 U		< 0.061 U	0.1 J
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.02 U			< 0.12 U	0.036 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.07 J	< 0.11 U	< 0.12 U	< 0.02 U	0.034 J
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	0.73 J	0.035 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.67 J	< 0.11 U	< 0.11 U	< 0.019 U	0.17
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	1.3 J	0.038 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	1.2 J	< 0.11 U		< 0.02 U	0.2
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	1.1	0.036 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.77	< 0.11 U	< 0.11 U	< 0.02 U	0.2
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	0.51	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.22	< 0.11 U	< 0.11 U	< 0.02 U	0.042 J
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.02 U			< 0.13 U	0.14	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.062 J	< 0.12 U		< 0.02 U	< 0.019 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.02 U			< 0.13 U	0.14	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.055 J	< 0.12 U		< 0.021 U	< 0.02 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	< 0.018 U			< 0.11 U	1.9	0.079	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.75	< 0.11 U		< 0.019 U	0.15
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	0.35	0.017 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.19	< 0.11 U		< 0.02 U	0.082
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	0.26	< 0.015 UJ	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.17	< 0.11 U		< 0.02 U	0.1
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.02 U			< 0.13 U	0.68	0.026 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.56	< 0.12 U		< 0.021 U	0.072 J
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	< 0.02 U			< 0.13 U	0.032 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.019 J	< 0.12 U		< 0.021 U	< 0.019 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	< 0.021 U			< 0.13 U	0.24	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.12	< 0.12 U		< 0.021 U	0.031 J
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.021 U			< 0.13 U	0.028 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.019 J	< 0.12 U		< 0.021 U	< 0.02 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.021 U			< 0.13 U	0.062 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.028 J	< 0.12 U		< 0.021 U	< 0.02 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	< 0.021 U			< 0.13 U	0.22	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.074 J	< 0.12 U		< 0.021 U	< 0.02 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 0.1 U			< 0.62 U	7.5	0.56	< 0.14 U	< 0.12 U	< 0.2 U	< 0.1 U	2.4	< 0.57 U		< 0.1 U	0.58
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	< 0.019 U			< 0.12 U	2	0.099	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.61	< 0.11 U	< 0.11 U	< 0.019 U	0.12
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.019 U			< 0.12 U	0.083	0.021 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.034 J	< 0.11 U		< 0.02 U	0.039 J
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.018 U			< 0.11 U	0.81	0.05 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.27	< 0.1 U		< 0.019 U	0.069 J
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.019 U			< 0.12 U	0.19	0.022 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.076	< 0.11 U		< 0.019 U	0.033 J
Football Field	SSHS-B2900	DUP-01	11/6/2019	855.76	0.17 - 2 ft	180-98355-3	Excavated	< 0.02 U			< 0.12 U	0.19	< 0.015 UJ	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.096	< 0.11 U	< 0.12 U	< 0.02 U	0.18
Football Field	SSHS-B2900	SSHS-B2900-SUB-0.17-2	11/6/2019	855.76	0.17 - 2 ft	180-98355-2	Excavated	< 0.021 U			< 0.13 U	0.26	0.023 J	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.11	< 0.12 U	< 0.12 U	< 0.021 U	0.21
Football Field	SSHS-B2901	DUP-02	11/6/2019	856.05	0.17 - 2 ft	180-98355-3	Excavated	< 0.02 U			< 0.13 U	0.43	0.027 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.27	< 0.12 U	< 0.12 U	< 0.021 U	0.42 J
Football Field	SSHS-B2901	SSHS-B2901-SUB-0.17-2	11/6/2019	856.05	0.17 - 2 ft	180-98355-2	Excavated	< 0.019 U			< 0.12 U	0.42	0.022 J	< 0.028 U	< 0.023 UJ	< 0.039 U	< 0.02 U	0.17	< 0.11 U	< 0.11 U	< 0.02 U	0.21 J
Football Field	SSHS-B2911	SSHS-B2911-SUB-0.17-2	11/6/2019	854.88	0.17 - 2 ft	180-98355-2	Excavated	< 0.019 U			< 0.12 U	0.62 J	0.041 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.18	< 0.11 U	< 0.11 U	< 0.019 U	0.064 J
Football Field	SSHS-B2912	DUP-04	11/5/2019	855.19	0.17 - 2 ft	180-98355-3	Excavated	< 0.077 U			< 0.48 U	16	2	< 0.11 U	< 0.09 U	< 0.16 U	< 0.079 U	3.7	< 0.44 U	< 0.45 U	< 0.078 U	0.81 J
Football Field	SSHS-B2912	SSHS-B2912-SUB-0.17-2	11/5/2019	855.19	0.17 - 2 ft	180-98355-1	Excavated	< 0.16 U			< 0.99 U	20	3.2	< 0.23 U	< 0.19 UJ	< 0.32 U	< 0.16 U	4.1	< 0.91 U	< 0.93 U	< 0.16 U	1.7 J
Football Field	SSHS-B2938	SSHS-B2938-SUB-0.17-2	11/6/2019	855.53	0.17 - 2 ft	180-98355-3	Excavated	< 0.019 U			< 0.12 U	2.3	0.058 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	1.3	< 0.11 U		< 0.02 U	0.47
Football Field	SSHS-B2939	SSHS-B2939-SUB-0.17-2	11/6/2019	855.56	0.17 - 2 ft	180-98355-3	Excavated	< 0.059 U			< 0.37 U	2.1	0.086 J	< 0.085 U	< 0.069 U	< 0.12 UJ	< 0.061 U	1	< 0.34 U		< 0.061 U	0.31
Football Field	SSHS-B2940	SSHS-B2940-SUB-0.17-2	11/6/2019	855.06	0.17 - 2 ft	180-98355-3	Excavated	< 0.019 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.069 J	< 0.11 U		< 0.019 U	0.022 J
Football Field	SSHS-B2941	SSHS-B2941-SUB-0.17-2	11/6/2019	855.17	0.17 - 2 ft	180-98355-3	Excavated	< 0.037 U			< 0.23 U	1.7	0.076 J	< 0.053 U	< 0.043 U	< 0.075 U	< 0.038 U	0.78	< 0.21 U		< 0.038 U	0.13 J
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated					0.31 J						0.2 J				
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 0.022 U			< 0.14 U	0.99	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.023 U	0.6	< 0.13 U	< 0.13 U	< 0.022 U	0.088
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 0.021 U			< 0.13 U	0.023 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	< 0.017 UJ	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	< 0.019 U			< 0.12 U	0.1	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.051 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	< 0.018 U			< 0.11 U	0.27	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.25	< 0.1 U	< 0.11 U	< 0.018 U	0.023 J
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 0.019 U			< 0.12 U	0.021 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 0.019 U			< 0.12 U	0.043 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.023 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 0.019 U			< 0.12 U	0.029 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 0.018 U			< 0.11 U	0.063 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.029 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.019 U			< 0.12 U	0.021 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	< 0.02 U			< 0.12 U	0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.047 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.02 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.016 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	< 0.02 U			< 0.12 U	0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.089	< 0.11 U	< 0.12 U	< 0.02 U	0.029 J
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	< 0.038 U			< 0.24 U	< 0.04 U	< 0.03 U	< 0.055 U	< 0.045 U	< 0.078 U	< 0.039 U	< 0.031 U	< 0.22 U	< 0.22 U	< 0.039 U	< 0.037 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	< 0.018 U			< 0.11 U	1.2	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.55	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated		0.095	< 0.049 U	< 0.061 U	< 0.074 U	< 0.016 U	< 0.016 U	< 0.12 U		< 0.014 U	< 0.015 U	< 0.072 U	0.12	< 0.0099 U	0.29		< 0.017 U	< 0.36 U	< 0.085 U	< 0.079 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated		0.029	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.076	< 0.0093 U	0.1		< 0.016 U	< 0.34 U	< 0.08 U	< 0.075 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated		0.0081	< 0.048 U	< 0.059 U	< 0.072 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.07 U	0.031	< 0.0097 U	0.043		< 0.017 U	< 0.35 U	< 0.083 U	< 0.077 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated		0.04	< 0.089 U	< 0.11 U	< 0.13 U	< 0.029 U	< 0.029 U	< 0.21 U		< 0.025 U	< 0.027 U	< 0.13 U	0.046	< 0.018 U	0.062		< 0.031 U	< 0.66 U	< 0.15 U	< 0.14 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated		1	< 0.31 U	< 0.39 U	< 0.47 U	< 0.1 U	< 0.1 U	< 0.74 U		< 0.086 U	< 0.094 U	< 0.46 U	8.7	< 0.063 U	5.9		< 0.11 U	< 2.3 U	< 0.54 U	< 0.5 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated		0.081	< 0.047 U	< 0.058 U	< 0.071 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.17	< 0.0094 U	0.24		< 0.016 U	< 0.35 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated		0.059	< 0.047 U	< 0.058 U	< 0.071 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.069 U,F1	0.17	< 0.0095 U	0.38		< 0.017 U	< 0.35 U,F1	< 0.082 U	< 0.076 U,F2
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated		0.13	< 0.047 U	< 0.058 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.63	< 0.0094 U	1.1		< 0.016 U	< 0.34 U	< 0.081 U	< 0.075 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated		0.077	< 0.048 U	< 0.058 U	< 0.072 U	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.069 U	0.17	< 0.0096 U	0.41		< 0.017 U	< 0.35 U	< 0.082 U	< 0.076 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated		0.047	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.32	< 0.0093 U	0.45		< 0.016 U	< 0.34 U	< 0.08 U	< 0.075 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated		0.013	< 0.044 U	< 0.054 U	< 0.066 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.064 U	0.025	< 0.0088 U	0.031		< 0.015 U	< 0.32 U	< 0.076 U	< 0.071 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated		0.14 J	< 0.93 U	< 1.1 U	< 1.4 U	< 0.3 U	< 0.3 U	< 2.2 U		< 0.26 U	< 0.28 U	< 1.4 U	0.76	0.4 J	1.2		< 0.33 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated		0.15 J	< 1.2 U	< 1.4 U	< 1.8 U	< 0.38 U	< 0.38 U	< 2.7 U		< 0.32 U	< 0.35 U	< 1.7 U	0.7	0.3 J	1.2		< 0.41 U	< 8.6 U	< 2 U	< 1.9 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated		< 0.0009 U	< 0.044 U	< 0.054 U	< 0.066 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.063 U	0.0061 J	< 0.0087 U	0.01		< 0.015 U	< 0.32 U	< 0.075 U	< 0.07 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated		< 0.00093 U	< 0.045 U	< 0.055 U	< 0.068 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.012 U	< 0.014 U	< 0.066 U,F1,F2	< 0.00083 U	< 0.0091 U	0.012		< 0.016 U	< 0.33 U,F1	< 0.078 U	< 0.072 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated		0.11	< 0.046 U	< 0.056 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.22	0.062	0.13		< 0.016 U	< 0.34 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated		0.083	< 0.093 U	< 0.11 U	< 0.14 U	< 0.03 U	< 0.03 U	< 0.22 U		< 0.026 U	< 0.028 U	< 0.13 U	0.16	< 0.019 U	0.17		< 0.032 U	< 0.68 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	< 0.35 U	0.2 J	< 0.55 U	< 0.31 U	< 0.059 U	< 0.44 U	< 0.19 U	< 0.85 U		< 0.082 U	< 0.4 U	< 1.9 U	0.32	< 0.36 U	0.44		< 0.052 U	< 0.5 U	< 0.086 U	< 0.066 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated		0.04 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.074 J	< 0.12 U	0.097		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated		0.65	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.42	< 0.11 U	0.61 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.11 U	0.66	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.6	< 0.12 U	1.1 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated		0.73	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.39	< 0.12 U	1.2		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated		0.13	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.2	< 0.12 U	0.4		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.052 J	< 0.12 U	0.13		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.052 J	< 0.12 U	0.12		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	< 0.11 U	0.5	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	1.2	< 0.11 U	1.5		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.11 U	0.31	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.18	< 0.12 U	0.28		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.11 U	0.31	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.15	< 0.12 U	0.22		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.12 U	0.2	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.65 U	0.31	< 0.12 U	0.56		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.023 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	< 0.12 U	0.046 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.11	< 0.12 U	0.22		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	0.026 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.027 J	< 0.13 U	0.048 J		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.15	< 0.13 U	0.18		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 0.59 U	1.3	< 0.91 U	< 0.51 U	< 0.097 U	< 0.73 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	5.3	< 0.61 U	5.7		< 0.086 U	< 0.83 U	< 0.14 U	< 0.11 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated		0.13	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.3	< 0.12 U	1.5		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.11 U	0.074 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.081	< 0.12 U	0.064 J		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.11 U	0.069 J	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.5	< 0.11 U	0.64		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.11 U	0.03 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.11	< 0.11 U	0.15		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2900	DUP-01	11/6/2019	855.76	0.17 - 2 ft	180-98355-3	Excavated		0.13	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 UJ		< 0.027 U	< 0.13 U	< 0.63 U	0.24	< 0.12 U	0.19		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B2900	SSHS-B2900-SUB-0.17-2	11/6/2019	855.76	0.17 - 2 ft	180-98355-2	Excavated		0.15	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 UJ		< 0.028 U	< 0.14 U	< 0.66 U	0.28	< 0.13 U	0.26		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B2901	DUP-02	11/6/2019	856.05	0.17 - 2 ft	180-98355-3	Excavated		0.47 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 UJ		< 0.028 U	< 0.14 U	< 0.66 U	0.46	< 0.12 U	0.42		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B2901	SSHS-B2901-SUB-0.17-2	11/6/2019	856.05	0.17 - 2 ft	180-98355-2	Excavated		0.26 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 UJ		< 0.026 U	< 0.13 U	< 0.62 U	0.39	< 0.12 U	0.41		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2911	SSHS-B2911-SUB-0.17-2	11/6/2019	854.88	0.17 - 2 ft	180-98355-2	Excavated		0.075 J	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 UJ		< 0.026 U	< 0.13 U	< 0.61 U	0.52 J	< 0.12 U	0.6 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2912	DUP-04	11/5/2019	855.19	0.17 - 2 ft	180-98355-3	Excavated		1.3 J	< 0.7 U	< 0.39 U	< 0.075 U	< 0.56 U	< 0.25 U	< 1.1 UJ		< 0.1 U	< 0.51 U	< 2.5 U	16	< 0.47 U	15		< 0.066 U	< 0.64 U	< 0.11 U	< 0.084 U
Football Field	SSHS-B2912	SSHS-B2912-SUB-0.17-2	11/5/2019	855.19	0.17 - 2 ft	180-98355-1	Excavated		3.2 J	< 1.4 U	< 0.81 U	< 0.15 U	< 1.2 U	< 0.5 U	< 2.2 UJ		< 0.21 U	< 1.1 U	< 5.1 U	22	< 0.96 U	18		< 0.14 U	< 1.3 U	< 0.23 U	< 0.17 U
Football Field	SSHS-B2938	SSHS-B2938-SUB-0.17-2	11/6/2019	855.53	0.17 - 2 ft	180-98355-3	Excavated	< 0.11 U	1.7	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 UJ		< 0.026 U	< 0.13 U	< 0.62 U	1.4	< 0.12 U	2.1		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2939	SSHS-B2939-SUB-0.17-2	11/6/2019	855.56	0.17 - 2 ft	180-98355-3	Excavated	< 0.35 U	1	< 0.54 U	< 0.3 U	< 0.058 U	< 0.43 U	< 0.19 U	< 0.83 UJ		< 0.08 U	< 0.4 U	< 1.9 U	1.4	< 0.36 U	2		< 0.051 U	< 0.49 U	< 0.085 U	< 0.065 U
Football Field	SSHS-B2940	SSHS-B2940-SUB-0.17-2	11/6/2019	855.06	0.17 - 2 ft	180-98355-3	Excavated	< 0.11 U	0.07 J	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 UJ		< 0.026 U	< 0.13 U	< 0.61 U	0.074 J	< 0.12 U	0.11		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2941	SSHS-B2941-SUB-0.17-2	11/6/2019	855.17	0.17 - 2 ft	180-98355-3	Excavated	< 0.22 U	0.33	< 0.34 U	< 0.19 U	< 0.036 U	< 0.27 U	< 0.12 U	< 0.52 UJ		< 0.05 U	< 0.25 U	< 1.2 U	0.95	< 0.22 U	1.7		< 0.032 U	< 0.31 U	< 0.053 U	< 0.04 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated														0.1 J	0.34 J					
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated		0.32	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.35	< 0.13 U	1		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated		< 0.016 UJ	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 UJ	< 0.13 U	0.021 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated		< 0.015 U	< 0.17 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.033 J	< 0.12 U	0.13		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated		0.078	< 0.16 U	< 0.092 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.074	< 0.11 U	0.18		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.023 J		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated		< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.052 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.026 J	< 0.11 U	0.04 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated		< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.036 J	< 0.11 U	0.079		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.02 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated		0.02 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.064 J	< 0.12 U	0.11		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated		0.1	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.046 J	< 0.12 U	0.074 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated		< 0.03 U	< 0.35 U	< 0.19 U	< 0.037 U	< 0.28 U	< 0.12 U	< 0.53 U		< 0.052 U	< 0.25 U	< 1.2 U	< 0.041 U	< 0.23 U	< 0.036 U		< 0.033 U	< 0.32 U	< 0.054 U	< 0.042 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated		0.025 J	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.26	< 0.11 U	1.1		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (I	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7																					
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	6900		ND	< 0.11 U	0.3 J	< 0.1 U	< 0.095 U	< 0.8 U	< 0.077 U	< 0.23 U	< 0.069 U	< 0.08 U	< 0.09 U	< 0.11 U	1.4	< 0.087 U	< 0.067 U	< 0.14 U	< 2 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	310		1.419	< 0.022 U	0.053 J	< 0.021 U	0.038 J	< 0.17 U	< 0.016 U	< 0.049 U	0.11	0.11	0.14	0.07 J	0.17	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 42 U		1.313	< 0.025 U	0.051 J	< 0.023 U	0.038 J	< 0.19 U	< 0.018 U	< 0.053 U	0.12	0.13	0.16	0.067 J	0.11	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 40 U		0.111	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.016 J	< 0.017 U	0.023 J	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	49 J		1.332	< 0.021 U	0.034 J	< 0.02 U	0.047 J	< 0.16 U	< 0.016 U		0.14	0.11	0.15	0.059 J	0.086	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 39 U		ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		< 0.014 U	< 0.016 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	80		0.601	< 0.022 U	0.022 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.054 J	0.065 J	0.073 J	0.029 J	0.056 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	840		3.74	< 0.023 U	0.41	< 0.021 U	0.18	< 0.17 U	0.035 J	< 0.049 U	0.24	0.37	0.45	0.14	0.59	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	450		0.958	< 0.021 U	0.12	< 0.019 U	0.04 J	< 0.16 U	0.025 J	< 0.044 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.021 U	0.21	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	690		0.915	< 0.021 U	0.064 J	< 0.02 U	0.069 J	< 0.16 U	0.029 J	< 0.046 U	0.053 J	0.031 J	0.044 J	< 0.022 U	0.091	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	64		0.284	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.029 J	0.027 J	0.038 J	< 0.023 U	0.045 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 40 U		0.376	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.033 J	0.042 J	0.052 J	< 0.023 U	0.043 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 42 U		3.443	< 0.024 U	0.057 J	< 0.023 U	0.098	< 0.18 U	< 0.017 U	< 0.052 U	0.34	0.29	0.32	0.14	0.22	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 41 U		0.423	< 0.023 U	0.021 J	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.05 U	0.046 J	0.04 J	0.06 J	< 0.024 U	0.036 J	< 0.019 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 40 U		1.563	< 0.022 U	0.035 J	< 0.021 U	0.04 J	< 0.17 U	< 0.016 U		0.16	0.13	0.2	0.057 J	0.1	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 39 U		2.018	< 0.022 U	0.059 J	< 0.02 U	0.043 J	< 0.16 U	< 0.016 U		0.23	0.15	0.22	0.11	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	91		3.926	< 0.022 U	0.15	< 0.02 U	0.088	< 0.16 U	< 0.016 U		0.38	0.39	0.47	0.2	0.29	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	1600		0.056	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.015 U	< 0.018 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	71		0.801	< 0.023 U	0.028 J	< 0.022 U	0.022 J	< 0.17 U	0.03 J	< 0.049 U	0.06 J	0.061 J	0.083	< 0.024 U	0.061 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	580		8.452	< 0.022 U	0.26	< 0.021 U	0.25	< 0.17 U	0.016 J	< 0.048 U	0.75	0.76	0.92	0.37	0.73	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	390		6.467	< 0.021 U	0.25	< 0.02 U	0.16	< 0.16 U	0.026 J		0.56	0.59	0.67	0.31	0.65	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	1500		7.273	0.027 J	0.29	< 0.02 U	0.25	< 0.16 U	0.059 J	< 0.047 U	0.49	0.48	0.61	0.24	0.87	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	110		0.449	< 0.022 U	0.017 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.035 J	0.027 J	0.046 J	< 0.023 U	0.045 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	1000		4.659	0.022 J	0.33	< 0.021 U	0.16	< 0.17 U	0.061 J	< 0.048 U	0.27	0.3	0.4	0.15	0.65	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	1300		2.871	< 0.022 U	0.15	< 0.021 U	0.081	< 0.17 U	0.024 J	< 0.048 U	0.2	0.23	0.31	0.13	0.37	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	1500		9.408	0.022 J	0.38 J	< 0.021 U	0.41 J	< 0.17 U	0.052 J	< 0.048 U	0.66 J	0.55 J	0.74 J	0.27 J	0.95 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 39 U		0.015	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.015 J	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 40 U		3.604	< 0.022 U	0.12 J	< 0.021 U	0.11 J	< 0.17 U	< 0.016 U	< 0.047 U	0.37 J	0.33 J	0.4 J	0.17 J	0.26 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 41 U		0.486	< 0.023 U	0.018 J	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.043 J	0.047 J	0.063 J	0.026 J	0.044 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 39 U		ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.015 U	< 0.017 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 42 U		0.964	< 0.023 U	0.033 J	< 0.021 U	0.021 J	< 0.17 U	< 0.016 U		0.11 J	0.093 J	0.14 J	0.043 J	0.077 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	330 J		3.443	< 0.022 U	0.15 J	< 0.021 U	0.097 J	< 0.17 U	< 0.016 U		0.32	0.31	0.41	0.15	0.31	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	96		19.912	0.03 J	0.52	< 0.021 U	0.44	< 0.17 U	0.024 J		1.9	1.5	2.1	0.53	1.2	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	43 J		1.216	< 0.023 U	0.031 J	< 0.022 U	0.029 J	< 0.18 U	< 0.017 U	< 0.051 U	0.11	0.11	0.15	0.046 J	0.084	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	460 J		2.148	< 0.023 U	0.098	< 0.021 U	0.062 J	< 0.17 U	< 0.017 U	< 0.049 U	0.18	0.2	0.25	0.096	0.24	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	800		3.355	< 0.022 U	0.18	< 0.021 U	0.097	< 0.17 U	0.02 J	< 0.047 U	0.25	0.3	0.38	0.14	0.44	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	130		7.889	< 0.022 U	0.25	< 0.021 U	0.22	< 0.17 U	0.56	< 0.048 U	0.66	0.59	0.73	0.3	0.59	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	95		7.437	0.057 J	0.12	< 0.021 U	0.21	< 0.17 U	0.021 J	< 0.048 U	0.65	0.53	0.68	0.3	0.45	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	150		ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	210		2.738	< 0.022 U	0.13	< 0.021 U	0.088	< 0.17 U	< 0.016 U	< 0.048 U	0.24	0.25	0.35	0.11	0.28	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	50 J		3.225	< 0.022 U	0.11	< 0.021 U	0.088	< 0.17 U	< 0.016 U	< 0.048 U	0.32	0.28	0.32	0.17	0.27	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 40 U		0.056	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.015 U	< 0.017 U	0.019 J	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	< 41 U		0.528	< 0.023 U	0.023 J	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.054 J	0.052 J	0.06 J	0.033 J	0.042 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 40 U		0.365	< 0.022 U	0.027 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.044 J	0.039 J	0.052 J	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	100 J		45.9	0.11 J	1.4 J	< 0.02 U	1.8 J	< 0.16 U	0.074 J	< 0.046 U	4.1 J	3.5 J	4.5 J	1.5 J	2.9 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	160 J		14.192	0.022 J	0.51 J	< 0.02 U	0.31 J	< 0.16 U	0.015 J	< 0.045 U	1.5 J	1.4 J	1.7 J	0.64 J	1.1 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	270 J		6.686	< 0.022 UJ	0.24 J	< 0.02 U	0.18 J	< 0.16 U	0.02 J	< 0.047 U	0.61 J	0.62 J	0.77 J	0.31 J	0.62 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	200		3.17	< 0.022 U	0.11	< 0.021 U	0.11	< 0.17 U	0.017 J	< 0.048 U	0.24	0.25	0.29	0.15	0.33	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 38 U		ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	62		4.928	< 0.022 U	0.087	< 0.02 U	0.16	< 0.16 U	< 0.016 U	< 0.047 U	0.44	0.34	0.44	0.19	0.29	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 40 U		2.558	< 0.022 U	0.14	< 0.021 U	0.073 J	< 0.17 U	< 0.016 U	< 0.048 U	0.27	0.21	0.33	0.11	0.2	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 43 U		0.423	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.04 J	0.031 J	0.049 J	< 0.024 U	0.027 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 40 U		1.551	< 0.023 U	0.076 J	< 0.022 U	0.046 J	< 0.18 U	< 0.017 U	< 0.05 U	0.14	0.14	0.23	0.05 J	0.14	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 40 U		0.609	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.061 J	0.056 J	0.08	< 0.024 U	0.038 J	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 40 U		1.996	< 0.022 U	0.091	< 0.021 U	0.054 J	< 0.17 U	< 0.016 U	< 0.048 U	0.19	0.16	0.24	0.091	0.15	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	78		5.711	< 0.022 U	0.26	< 0.02 U	0.14	< 0.16 U	< 0.016 U		0.56	0.53	0.71	0.3	0.45	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 43 U		3.661	< 0.023 U	0.11	< 0.022 U	0.085	< 0.18 U	< 0.017 U		0.34	0.26	0.36	0.12	0.21	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 39 U		0.566	< 0.023 U	0.019 J	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.054 J	0.05 J	0.076 J	0.026 J	0.046 J	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	72		15.136	< 0.024 U	0.56	< 0.023 U	0.35	< 0.18 U	< 0.018 U	< 0.052 U	1.5	1.5	2.1	0.81	1.3	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	53 J		7.346	0.064 J	0.055 J	< 0.021 U	0.25	< 0.17 U	< 0.016 U		0.67	0.52	0.72	0.18	0.32	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	61		10.48	0.15	0.12	< 0.021 U	0.35	< 0.17 U	0.041 J	< 0.048 U	0.92	0.71	0.95	0.3	0.6	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	86		2.508	0.033 J	0.048 J	< 0.021 U	0.099	< 0.17 U	< 0.016 U	< 0.048 U	0.22	0.18	0.24	0.079	0.17	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	170		21.711	0.027 J	0.57	< 0.02 U	0.62	< 0.16 U	0.034 J	< 0.045 U	2	1.9	2.2	0.88	2.2	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	900		34.33	< 0.53 U	< 0.41 U	< 0.5 U	0.87 J	< 4.1 U	< 0.39 U	< 1.1 U	2.4	2.2	3.1	0.78 J	2.1	< 0.44 U	< 0.34 U	< 0.69 U	< 9.9 U	< 0.65 U	< 6.4 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	1200		20.43	< 0.52 U	0.53 J	< 0.49 U	0.55 J	< 4 U	< 0.38 U	< 1.1 U	1.6 J	1.9	2.1	0.88 J	1.5 J	< 0.43 U	< 0.33 U	< 0.67 U	< 9.6 U	< 0.63 U	< 6.2 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	1200		20.43	< 0.52 U	0.53 J	< 0.49 U	0.55 J	< 4 U	< 0.38 U	< 1.1 U	1.6 J	1.9	2.1	0.88 J	1.5 J	< 0.43 U	< 0.33 U	< 0.67 U	< 9.6 U	< 0.63 U	< 6.2 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7																				
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 1.2 U	< 0.086 U	< 0.061 U	< 0.086 U	< 0.084 U	< 0.085 U	< 0.11 U	< 0.072 U	< 0.082 U	< 0.08 U	< 1.7 U	< 0.14 U	< 0.64 U	< 0.11 U	< 0.067 U	< 0.8 U	< 1.1 U	< 3.2 U	< 0.11 U	< 4.9 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	< 0.25 U	0.018 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.13	< 0.017 UJ	0.022 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.14	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.026 U	< 1.2 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.024 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	0.027 J	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.046 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	< 0.26 U	0.026 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.28	< 0.018 U	0.076 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	0.056 J	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.96 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.064 J	< 0.017 U	0.079 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.027 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.044 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 0.27 U	0.042 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.27	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.049 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.17	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 0.24 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.24	0.042 J	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	< 0.24 U	0.028 J	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.45	0.087	0.017 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.056 J	< 0.018 U	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.063 J	< 0.018 U	0.026 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	< 0.25 U	0.044 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.67	0.16	0.055 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	< 0.24 U	0.058 J	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.56	0.13	0.054 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	< 0.24 U	0.089	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.54	0.14	0.13 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.042 J	< 0.017 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	< 0.25 U	0.059 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.34	0.077 J	0.15 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	< 0.25 U	0.035 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.23	< 0.017 U	0.058 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	< 0.25 U	0.11 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.7 J	0.12 J	0.2 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 0.25 U	0.033 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.39 J	< 0.017 UJ	0.018 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	0.08 J	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.12 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	< 0.25 U	0.021 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.37	0.063 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	< 0.26 U	0.093	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	1.9	0.35	0.059 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.11	0.028 J	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	< 0.26 UJ	< 0.018 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.18	< 0.018 U	0.019 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	< 0.25 U	0.034 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.25	< 0.017 U	0.042 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	< 0.25 UJ	0.083	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.64	0.15	0.3 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 UJ	< 0.024 U	< 1 UJ
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	< 0.25 U	0.076 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.67	0.12	0.056 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.26	0.077 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.33	0.064 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.019 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.057 J	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.045 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	< 0.24 U	0.59 J	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	3.8 J	0.73 J	0.33 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.24 U	0.044 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	1.5 J	0.27 J	0.035 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.98 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.24 U	0.038 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.59 J	0.15 J	0.041 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.25	< 0.017 U	0.043 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 0.24 U	< 0.018 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	< 0.24 U	0.049 J	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.4	0.067 J	0.046 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.29	0.043 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.047 J	< 0.018 U	0.019 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.17	0.044 J	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.065 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.21	0.031 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	< 0.25 U	0.03 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.65	0.13	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 0.26 U	0.024 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.39	< 0.018 U	0.026 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.067 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	< 0.27 U	0.071 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	1.7	0.32	0.021 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	< 0.25 U	0.1	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.62	0.096	0.056 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	< 0.25 U	0.17	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.8	0.16	0.14 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	< 0.25 U	0.039 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.2	< 0.017 U	0.029 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	< 0.24 U	0.1	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	1.8	0.42	0.11 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated																				
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	< 6 U	0.52 J	< 0.31 U	< 0.44 U	< 0.42 U	< 0.43 U	< 0.56 U	2.7	0.46 J	< 0.41 U	< 8.6 U	< 0.71 U	< 3.2 U	< 0.57 U	< 0.34 U	< 4.1 U	< 5.4 U	< 16 U	< 0.57 U	< 25 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 5.9 U	< 0.42 U	< 0.3 U	< 0.43 U	< 0.42 U	< 0.42 U	< 0.55 U	1.8	< 0.4 U	< 0.4 U	< 8.4 U	< 0.7 U	< 3.2 U	< 0.56 U	< 0.33 U	< 4 U	< 5.3 U	< 16 U	< 0.56 U	< 24 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 5.9 U	< 0.42 U	< 0.3 U	< 0.43 U	< 0.42 U	< 0.42 U	< 0.55 U	1.8	< 0.4 U	< 0.4 U	< 8.4 U	< 0.7 U	< 3.2 U	< 0.56 U	< 0.33 U	< 4 U	< 5.3 U	< 16 U	< 0.56 U	< 24 U

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 0.091 U			< 0.57 U	< 0.097 U	< 0.072 U	< 0.13 U	< 0.11 U	< 0.19 U	< 0.095 U	0.51	< 0.53 U		< 0.093 U	< 0.088 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	< 0.019 U			< 0.12 U	0.19	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.11	< 0.11 U	< 0.11 U	< 0.02 U	0.025 J
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 0.021 U			< 0.13 U	0.18	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.11	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 0.02 U			< 0.12 U	0.024 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.016 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	< 0.019 U			< 0.12 U	0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.073 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	< 0.019 U			< 0.12 U	0.07 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.047 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	< 0.02 U			< 0.12 U	0.28	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.42	< 0.11 U	< 0.12 U	< 0.02 U	0.16
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	< 0.018 U			< 0.11 U	0.039 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.11 U	< 0.018 U	0.096
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	< 0.019 U			< 0.12 U	0.083	0.018 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.043 J	< 0.11 U	< 0.11 U	< 0.019 U	0.064 J
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	< 0.019 U			< 0.12 U	0.033 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 0.019 U			< 0.12 U	0.048 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.033 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 0.021 U			< 0.13 U	0.59	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.21	< 0.12 U	< 0.12 U	< 0.021 U	0.031 J
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 0.02 U			< 0.12 U	0.066 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.035 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 0.019 U			< 0.12 U	0.23	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.081	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 0.019 U			< 0.12 U	0.29	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.1	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	< 0.019 U			< 0.12 U	0.46	0.022 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.25	< 0.11 U	< 0.11 U	< 0.019 U	0.038 J
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	< 0.02 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.017 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	< 0.02 U			< 0.12 U	0.08	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	0.048 J	< 0.11 U	< 0.12 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	< 0.019 U			< 0.12 U	1.3	0.042 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.62	< 0.11 U	< 0.11 U	< 0.02 U	0.063 J
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	< 0.019 U			< 0.12 U	0.82	0.027 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.5	< 0.11 U	< 0.11 U	< 0.019 U	0.094 J
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	< 0.019 U			< 0.12 U	0.99	0.086	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.55	< 0.11 U	< 0.11 U	< 0.019 U	0.22
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	< 0.019 U			< 0.12 U	0.043 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.031 J	< 0.11 U	< 0.11 U	< 0.019 U	0.027 J
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	< 0.019 U			< 0.12 U	0.41	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.34	< 0.11 U	< 0.11 U	< 0.02 U	0.28
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	< 0.019 U			< 0.12 U	0.3	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.24	< 0.11 U	< 0.11 U	< 0.02 U	0.086
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	< 0.019 U			< 0.12 U	1.5 J	0.076 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.5 J	< 0.11 U	< 0.11 U	< 0.02 U	0.21 J
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 0.018 U			< 0.12 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 0.019 U			< 0.12 U	0.52 J	< 0.015 UJ	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.22 J	< 0.11 U	< 0.11 U	< 0.019 U	0.061 J
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 0.02 U			< 0.13 U	0.054 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.03 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 0.019 U			< 0.12 U	0.12 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.061 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	< 0.019 U			< 0.12 U	0.43	0.018 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.24	< 0.11 U	< 0.11 U	< 0.02 U	0.038 J
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	< 0.02 U			< 0.12 U	3.2	0.072 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	1.1	< 0.11 U	< 0.12 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	< 0.02 U			< 0.13 U	0.18	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.084	< 0.12 U	< 0.12 U	< 0.021 U	0.021 J
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	< 0.02 U			< 0.12 U	0.28	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.18	< 0.11 U	< 0.12 U	< 0.02 U	0.029 J
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	< 0.019 U			< 0.12 U	0.36	0.018 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.33	< 0.11 U	< 0.11 U	< 0.019 U	0.079
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	< 0.019 U			< 0.12 U	1.4	0.059 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.51	< 0.11 U	< 0.11 U	< 0.02 U	0.078
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	< 0.019 U			< 0.12 U	1.3	0.06 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.41	< 0.11 U	< 0.11 U	< 0.02 U	0.11
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	< 0.019 U			< 0.12 U	0.33	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.24	< 0.11 U	< 0.11 U	< 0.02 U	0.037 J
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	< 0.019 U			< 0.12 U	0.49	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.21	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 0.019 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	< 0.02 U			< 0.13 U	0.077 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.04 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.019 U			< 0.12 U	0.068 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	< 0.019 U			< 0.12 U	7.5 J	0.43 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	2.6 J	< 0.11 U	< 0.11 U	< 0.019 U	0.35 J
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.018 U			< 0.11 U	1.9 J	0.06 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.95 J	< 0.1 U		< 0.019 U	0.074
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.019 U			< 0.12 U	0.87 J	0.026 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.52 J	< 0.11 U		< 0.019 U	0.084
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	< 0.019 U			< 0.12 U	0.53	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.26	< 0.11 U	< 0.11 U	< 0.02 U	0.09
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	< 0.019 U			< 0.12 U	0.96	0.021 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.25	< 0.11 U	< 0.11 U	< 0.019 U	0.024 J
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 0.019 U			< 0.12 U	0.34	0.017 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.16	< 0.11 U	< 0.11 U	< 0.02 U	0.026 J
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 0.02 U			< 0.12 U	0.057 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.025 J	< 0.11 U	< 0.12 U	< 0.02 U	0.079 J
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 0.02 U			< 0.12 U	0.18	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.11	< 0.11 U	< 0.12 U	< 0.02 U	0.054 J
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 0.02 U			< 0.12 U	0.1	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.038 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 0.019 U			< 0.12 U	0.29	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.11	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	< 0.019 U			< 0.12 U	0.69	0.023 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.38	< 0.11 U	< 0.11 U	< 0.019 U	0.048 J
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 0.02 U			< 0.13 U	0.63	0.024 J	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.18	< 0.12 U	< 0.12 U	< 0.021 U	0.086
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 0.02 U			< 0.12 U	0.087	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.037 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	< 0.021 U			< 0.13 U	1.6	0.056 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	1.1	< 0.12 U	< 0.12 U	< 0.021 U	0.073 J
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	< 0.019 U			< 0.12 U	1.3 J	0.079	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.29	< 0.11 U	< 0.11 U	< 0.02 U	0.027 J
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	< 0.019 U			< 0.12 U	1.8	0.13	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.54	< 0.11 U	< 0.11 U	< 0.02 U	0.18
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	< 0.019 U			< 0.12 U	0.42	0.037 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.16	< 0.11 U	< 0.11 U	< 0.02 U	0.034 J
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	< 0.018 U			< 0.11 U	3.3	0.084	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	1.8	< 0.11 U	< 0.11 U	< 0.019 U	0.12
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated															
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	< 0.46 U			< 2.9 UJ	6.9	0.52 J	< 0.66 U	< 0.54 U	< 0.95 U	< 0.48 U	1.6 J	< 2.7 U	< 2.7 U	< 0.47 U	< 0.44 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.45 U			< 2.8 UJ	3.3	< 0.36 U	< 0.65 U	< 0.53 U	< 0.93 U	< 0.47 U	1.2 J	< 2.6 U	< 2.7 U	< 0.46 U	< 0.43 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.45 U			< 2.8 UJ	3.3	< 0.36 U	< 0.65 U	< 0.53 U	< 0.93 U	< 0.47 U	1.2 J	< 2.6 U		< 0.46 U	< 0.43 U

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 0.54 U	< 0.071 U	< 0.84 U	< 0.47 U	< 0.089 U	< 0.67 U	< 0.29 U	< 1.3 U		< 0.12 U	< 0.61 U	< 2.9 U	< 0.098 U	< 0.56 U	< 0.087 U		< 0.079 U	< 0.76 U	< 0.13 U	< 0.1 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated		0.071 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.1 J	< 0.12 U	0.18		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated		< 0.017 U	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.068 J	< 0.13 U	0.19		< 0.018 U	< 0.18 U	< 0.031 U	< 0.023 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.024 J		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.12	< 0.11 U	0.2		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated		0.048 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.036 J	< 0.12 U	0.077		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated		0.36	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.17	< 0.12 U	0.26		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated		0.56	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.08	< 0.11 U	0.029 J		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated		0.14	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.22	< 0.11 U	0.059 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated		0.026 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.026 J	< 0.12 U	0.033 J		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.03 J	< 0.12 U	0.051 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated		0.045 J	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.36	< 0.13 U	0.56		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.033 J	< 0.12 U	0.058 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated		0.015 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.27		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated		0.02 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.093	< 0.11 U	0.35		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated		0.049 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.19	< 0.11 U	0.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated		< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated		0.18	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.062 J	< 0.12 U	0.081		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated		0.24	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.54	< 0.12 U	1.1		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated		0.35	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.32	< 0.11 U	0.82		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated		0.64	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.62	< 0.11 U	0.74		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated		0.095	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.042 J	< 0.12 U	0.043 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated		0.86	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.35	< 0.12 U	0.33		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated		0.31	< 0.17 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.19	< 0.12 U	0.28		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated		0.51 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.3 J	< 0.12 U	1.1 J		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated		0.054 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.27 J	< 0.12 U	0.51 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.041 J	< 0.12 U	0.058 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.039 J	< 0.12 U	0.14 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated		0.065 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.16	< 0.12 U	0.5		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated		0.39	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	1.7	< 0.12 U	3.5		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated		0.039 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.076 J	< 0.12 U	0.17		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated		0.12	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.1	< 0.12 U	0.26		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated		0.28	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.17	< 0.11 U	0.34		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated		0.34	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.74	< 0.12 U	0.96		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated		0.17	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.83	< 0.12 U	1		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated		0.083	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.32		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated		0.043 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.53		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated		0.018 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.042 J	< 0.12 U	0.071 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.043 J	< 0.12 U	0.074 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated		0.63 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	5.2 J	< 0.11 U	6.6 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.11 U	0.17	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.47	< 0.11 U	2.2 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.11 U	0.28	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.3	< 0.11 U	0.84 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated		0.17	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.25	< 0.12 U	0.34		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated		0.05 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.55	< 0.11 U	0.77		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated		0.025 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.1	< 0.12 U	0.39		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated		0.04 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.059 J	< 0.12 U	0.048 J		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated		0.049 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.062 J	< 0.12 U	0.19		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.061 J	< 0.12 U	0.11		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated		0.02 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.13	< 0.12 U	0.32		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated		0.058 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.22	< 0.11 U	0.87		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated		0.062 J	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.38	< 0.12 U	0.62		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.039 J	< 0.12 U	0.084		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated		0.11	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.39	< 0.13 U	2.3		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated		0.037 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	1	< 0.12 U	1.2		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated		0.37	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.4	< 0.12 U	1.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated		0.09	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.27	< 0.12 U	0.31		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated		0.38	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	1.3	< 0.11 U	2.8		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated																				
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated		< 0.36 U	< 4.2 U	< 2.4 U	< 0.45 U	< 3.4 U	< 1.5 U	< 6.5 U		< 0.63 U	< 3.1 U	< 15 U	5	< 2.8 U	5.7		< 0.4 U	< 3.9 U	< 0.66 U	< 0.51 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated		< 0.35 U	< 4.1 U	< 2.3 U	< 0.44 U	< 3.3 U	< 1.4 U	< 6.4 U		< 0.61 U	< 3 U	< 15 U	2.2	< 2.7 U	3.4		< 0.39 U	< 3.8 U	< 0.65 U	< 0.5 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 2.7 U	< 0.35 U	< 4.1 U	< 2.3 U	< 0.44 U	< 3.3 U	< 1.4 U	< 6.4 U		< 0.61 U	< 3 U	< 15 U	2.2	< 2.7 U	3.4		< 0.39 U	< 3.8 U	< 0.65 U	< 0.5 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	450		ND	< 0.43 U	< 0.33 U	< 0.41 U	< 0.39 U	< 3.3 U	< 0.32 U	< 0.94 U	< 0.28 U	< 0.33 U	< 0.37 U	< 0.45 U	< 0.33 U	< 0.36 U	< 0.27 U	< 0.56 U	< 8 U	< 0.53 U	< 5.2 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	870		247.4	4.3	< 0.66 U	< 0.81 U	8	< 6.6 U	< 0.63 U	< 1.9 U	15	13	17	6.4	11	< 0.71 U	< 0.54 U	< 1.1 U	< 16 U	< 1 U	< 10 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	870		247.4	4.3	< 0.66 U	< 0.81 U	8	< 6.6 U	< 0.63 U	< 1.9 U	15	13	17	6.4	11	< 0.71 U	< 0.54 U	< 1.1 U	< 16 U	< 1 U	< 10 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	250		2.363	< 0.042 U	0.054 J	< 0.039 U	0.08 J	< 0.32 U	< 0.03 U	< 0.09 U	0.19	0.18	0.25	0.064 J	0.19	< 0.034 U	< 0.026 U	< 0.054 U	< 0.77 U	< 0.051 U	< 0.5 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	530																				
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	890 J		44.23	0.84 J	< 0.41 U	< 0.5 U	1.3 J	< 4.1 U	< 0.39 U	< 1.2 U	3	2.6	3.2	1.1 J	2.4	< 0.44 U	< 0.34 U	< 0.69 U	< 9.9 U	< 0.65 U	< 6.4 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	1000		1.01	< 0.55 U	< 0.42 U	< 0.52 U	< 0.49 U	< 4.2 U	< 0.4 U	< 1.2 U	< 0.36 U	< 0.41 U	< 0.47 U	< 0.57 U	< 0.41 U	< 0.45 U	< 0.34 U	< 0.7 U	< 10 U	< 0.66 U	< 6.5 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	350		9.194	0.14 J	0.19 J	< 0.097 U	0.29 J	< 0.78 U	< 0.075 U	< 0.22 U	0.82	0.67	0.85	0.23 J	0.69	< 0.085 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.13 U	< 1.2 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	170		0.676	< 0.043 U	< 0.032 U	< 0.04 U	< 0.038 U	< 0.32 U	< 0.031 U	< 0.092 U	0.059 J	0.054 J	0.073 J	< 0.044 U	0.065 J	< 0.035 U	< 0.027 U	< 0.055 U	< 0.79 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	59		ND	< 0.21 U	< 0.16 U	< 0.2 U	< 0.19 U	< 1.6 U	< 0.16 U	< 0.46 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.22 U	< 0.16 U	< 0.18 U	< 0.13 U	< 0.27 U	< 3.9 U	< 0.26 U	< 2.5 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	190 J		5.985	< 0.021 U	0.19 J	< 0.02 U	0.22 J	< 0.16 U	0.023 J	< 0.046 U	0.51 J	0.46 J	0.51 J	0.23 J	0.43 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	130 J		13.022	0.031 J	0.38	< 0.021 U	0.64 J	< 0.17 U	0.019 J	< 0.049 U	1.3	0.87	1	0.37	0.59 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	57 J		ND	< 0.021 U	< 0.016 UJ	< 0.02 U	< 0.019 UJ	< 0.16 U	< 0.015 U	< 0.045 U	< 0.014 UJ	< 0.016 UJ	< 0.018 UJ	< 0.022 UJ	< 0.016 UJ	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 41 U		3.157	< 0.023 U	0.047 J	< 0.021 U	0.078 J	< 0.17 U	< 0.016 U	< 0.049 U	0.36	0.31	0.36	0.1	0.21	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	500 J		6.972	0.049 J	0.12	< 0.02 U	0.2 J	< 0.16 U	0.018 J	< 0.046 U	0.63	0.54	0.62	0.24	0.45	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	160		6.646	< 0.021 U	0.16 J	< 0.02 U	0.18 J	< 0.16 U	0.017 J	< 0.045 U	0.69 J	0.62 J	0.69 J	0.26 J	0.55 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0.17-2	1/15/2020	856.51	0.17 - 2 ft	180-101084-1	Excavated	59 J																				
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0.17-2	1/14/2020	856.54	0.17 - 2 ft	180-101038-2	Excavated	67																				
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 41 UJ		2.908	< 0.022 U	0.051 J	< 0.02 U	0.081 J	< 0.17 U	< 0.016 U	< 0.047 U	0.28 J	0.27 J	0.32 J	0.094 J	0.23 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	300		56.12	0.1	2.7	0.029 J	1.5	< 0.17 U	0.028 J	< 0.048 U	5.6	5.4	7.4	2.7	4.6	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	140		42.93	0.1 J	1.7	0.027 J	1.1	< 0.17 U	0.029 J	< 0.048 U	4	3.4	4.4	1.9	2.7	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	270		1.1	< 0.31 U	< 0.24 U	< 0.29 U	< 0.28 U	< 2.4 U	< 0.23 U	< 0.67 U	< 0.2 U	< 0.23 U	< 0.27 U	< 0.32 U	< 0.23 U	< 0.26 U	< 0.2 U	< 0.4 U	< 5.7 U	< 0.38 U	< 3.7 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 44 U		0.017	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	0.017 J	< 0.019 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 48 U		0.341	< 0.027 U	< 0.021 U	< 0.026 U	< 0.025 U	< 0.21 U	< 0.02 U	< 0.059 U	0.041 J	0.034 J	0.049 J	< 0.028 U	< 0.02 U	< 0.023 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.033 U	< 0.33 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	50 J		7.058	< 0.023 U	0.28	< 0.022 U	0.15	< 0.17 U	< 0.017 U	< 0.05 U	0.75	0.53	0.85	0.3	0.3	< 0.019 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 38 U		1.987	< 0.022 U	0.093	< 0.021 U	0.06 J	< 0.17 U	< 0.016 U	< 0.047 U	0.18	0.17	0.27	0.083	0.15	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 42 U		0.282	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.031 J	0.034 J	0.046 J	< 0.024 U	0.022 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 41 U		1.631	< 0.022 U	0.066 J	< 0.021 U	0.039 J	< 0.17 U	< 0.016 U		0.17	0.15	0.21	0.076 J	0.14	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	110		35.382	0.062 J	1.8	< 0.022 U	1.3	< 0.18 U	0.048 J	< 0.051 U	3.2	3.1	4.3	1.6	3.5	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-0.17-2	12/20/2019	853.42	0.17 - 2 ft	180-100361-1	Excavated			0.865	< 0.022 U	0.091	< 0.021 U	0.043 J	< 0.17 U	< 0.016 U	< 0.048 U	0.057 J	0.085	0.14	0.033 J	0.097	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated			5.712	0.029 J	0.38	< 0.021 U	0.2	< 0.17 U	< 0.017 U	< 0.049 U	0.47	0.52	0.63	0.26	0.56	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-0.17-2	12/20/2019	853.19	0.17 - 2 ft	180-100361-1	Excavated			0.151	< 0.022 U	0.018 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.019 J	0.022 J	0.026 J	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-0.17-2	12/20/2019	853.57	0.17 - 2 ft	180-100362-1	Excavated			0.857	< 0.024 U	0.077 J	< 0.022 U	0.032 J	< 0.18 U	< 0.017 U	< 0.051 U	0.069 J	0.077 J	0.099	0.034 J	0.093	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0.17-2	12/19/2019	857.74	0.17 - 2 ft	180-100363-3	Excavated			6.666	< 0.023 U	0.45	< 0.022 U	0.22	< 0.17 U	< 0.017 U	< 0.049 U	0.62	0.63	0.85	0.28	0.61	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0.17-2	12/19/2019	857.37	0.17 - 2 ft	180-100363-3	Excavated			7.313	< 0.024 U	0.39	< 0.022 U	0.17	< 0.18 U	< 0.017 U		0.71	0.72	0.93	0.41	0.61	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0.17-2	12/19/2019	858.13	0.17 - 2 ft	180-100363-1	Excavated			14.05	0.067 J	0.75	< 0.023 U	0.39	< 0.18 U	< 0.018 U	< 0.052 U	1.3	1.3	1.7	0.64	1.1	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3247	SSHS-B-3247-SUB-0.17-2	12/19/2019	857.57	0.17 - 2 ft	180-100363-3	Excavated	< 42 U		20.35	0.05 J	1	0.021 J	0.54	< 0.17 U	0.023 J		1.9	1.9	2.6	0.83	1.6	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0.17-2	12/19/2019	857.44	0.17 - 2 ft	180-100363-1	Excavated	190		7.29	< 0.024 U	0.5	< 0.022 U	0.26	< 0.18 U	< 0.017 U	< 0.051 U	0.61	0.69	0.95	0.35	0.65	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0.17-2	12/19/2019	858.02	0.17 - 2 ft	180-100363-1	Excavated	120		5.589	< 0.024 U	0.35	< 0.023 U	0.18	< 0.18 U	< 0.018 U	< 0.052 U	0.47	0.56	0.88	0.22	0.54	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0.17-2	12/19/2019	857.46	0.17 - 2 ft	180-100363-1	Excavated	520		25.578	0.068 J	1.5	< 0.022 U	0.76	< 0.18 U	0.026 J	< 0.051 U	2.4	2.5	3.3	1.4	2	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-0.17-2	12/19/2019	858.40	0.17 - 2 ft	180-100363-2	Excavated	< 42 U		0.764	< 0.024 U	0.037 J	< 0.023 U	0.024 J	< 0.18 U	< 0.018 U	< 0.052 U	0.071 J	0.067 J	0.091	0.037 J	0.066 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-0.17-2	12/19/2019	857.06	0.17 - 2 ft	180-100363-1	Excavated	85		46.568	0.098	2.6	< 0.022 U	1.2	< 0.18 U	< 0.017 U	< 0.051 U	4.4	4.3	6	1.8	3.6	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-0.17-2	12/19/2019	858.14	0.17 - 2 ft	180-100363-2	Excavated	210		73.94	0.2	3.4	< 0.023 U	2.4	< 0.18 U	0.091 J	< 0.052 U	6.6	5.9	8.5	2.4	6.7	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-0.17-2	12/19/2019	858.41	0.17 - 2 ft	180-100363-2	Excavated	89 J		2.192	< 0.024 U	0.1	< 0.023 U	0.056 J	< 0.18 U	< 0.017 U	< 0.052 U	0.21	0.22	0.26	0.14	0.19	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-0.17-2	12/19/2019	857.33	0.17 - 2 ft	180-100363-2	Excavated	280		16.269	0.049 J	1.1	< 0.022 U	0.58	< 0.18 U	0.024 J	< 0.05 U	1.5	1.6	2.1	0.77	1.5	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-0.17-2	12/19/2019	858.57	0.17 - 2 ft	180-100363-1	Excavated	560		113.78	0.32	6.5	< 0.073 U	3.7	< 0.59 U	0.092 J	< 0.17 U	9.9	9.7	13	5.2	8.7	< 0.064 U	< 0.049 U	< 0.099 U	< 1.4 U	< 0.093 U	< 0.92 U
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0.17-2	12/18/2019	856.31	0.17 - 2 ft	180-100380-2	Excavated			95.03	0.26	5.6	< 0.064 U	2.9	< 0.51 U	0.082 J	< 0.15 U	8.5	8.9	12	3.4	7.6	< 0.056 U	< 0.043 U	< 0.087 U	< 1.2 U	< 0.082 U	< 0.81 U
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0.17-2	12/18/2019	857.03	0.17 - 2 ft	180-100380-2	Excavated			2.14	< 0.021 U	0.13	< 0.02 U	0.067 J	< 0.16 U	< 0.015 U	< 0.046 U	0.19	0.2	0.28	0.085	0.17	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0.17-2	12/18/2019	857.52	0.17 - 2 ft	180-100380-2	Excavated			3.673	< 0.024 U	0.2	< 0.022 U	0.11	< 0.18 U	< 0.017 U	< 0.051 U	0.33	0.34	0.48	0.13	0.27	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-0.17-2	12/18/2019	854.04	0.17 - 2 ft	180-100380-1	Excavated			5.31	< 0.023 U	0.37	< 0.022 U	0.2	< 0.18 U	< 0.017 U	< 0.05 U	0.51	0.49	0.6	0.24	0.66	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-2	Excavated	53 J		1.518	< 0.024 U	0.071 J	< 0.023 U	0.04 J	< 0.18 U	< 0.018 U	< 0.052 U	0.13	0.14	0.15	0.063 J	0.23	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-0.17-2	1/27/2021	854.73	0.17 - 2 ft	180-116529-1	Excavated	< 43 U	< 43 U																			
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-1	Excavated			1.8	< 0.023 U	0.079 J	< 0.022 U	0.052 J	< 0.18 U	< 0.017 U	< 0.05 U	0.21	0.17	0.21	0.059 J	0.18	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0.17-2	12/18/2019	855.88	0.17 - 2 ft	180-100380-1	Excavated	< 46 U																				
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0.17-2	12/18/2019	855.39	0.17 - 2 ft	180-100380-1	Excavated	90																				
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0.17-2	12/18/2019	856.00	0.17 - 2 ft	180-100380-1	Excavated	99 J		2.951	< 0.024 U	0.14	< 0.023 U	0.11	< 0.18 U	< 0.017 U	< 0.052 U	0.26	0.27	0.29	0.15	0.33	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	0.17 - 2 ft	180-100380-2	Not Excavated	680																				
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-0.17-2	12/18/2019	855.80	0.17 - 2 ft	180-100380-1	Excavated	110		3.31	< 0.025 U	0.15	< 0.024 U	0.1	< 0.19 U	< 0.018 U	< 0.054 U	0.29	0.3	0.34	0.16	0.37	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-0.17-2	2/2/2021	855.85	0.17 - 2 ft	180-116723-1	Excavated	750																				
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-0.17-2	12/18/2019	856.25	0.17 - 2 ft	180-100380-2	Excavated			15.049	0.049 J	0.35	< 0.021 U	0.64	< 0.17 U	0.026 J	< 0.049 U	1.3	1.2	1.4	0.66	0.85	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-0.17-2	12/18/2019	856.44	0.17 - 2 ft	180-100380-1	Excavated			1.584	< 0.023 U	0.069 J	< 0.022 U	0.055 J	< 0.18 U	< 0.017 U	< 0.05 U	0.14	0.13	0.16	0.048 J	0.18	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3278	SSHS-B3278-SUB-0.17-2	12/18/2019	856.22	0.17 - 2 ft	180-100380-2	Excavated			5.7	< 0.023 U	0.23	0.036 J	0.12	< 0.18 U	0.025 J	< 0.05 U	0.48	0.56	0.68	0.21	0.66	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-0.17-2	12/18/2019	856.56	0.17 - 2 ft	180-100380-2	Excavated			21.478	0.058 J	1.4	< 0.022 U	0.74	< 0.17 U	0.052 J	< 0.049 U	1.8	2.2	2.9	1	2.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-0.17-2	12/18/2019	856.88	0.17 - 2 ft	180-100380-2	Excavated			22.958	0.058 J	1.2	< 0.024 U	0.9	< 0.19 U	0.032 J	< 0.054 U	2	2	2.3	1.2	1.9	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-0.17-2	12/18/2019	856.89	0.17 - 2 ft	180-100380-2	Excavated			5.89	< 0.023 U	0.28	< 0.021 U	0.19	< 0.17 U	0.021 J	< 0.049 U	0.52	0.55	0.77	0.13	0.61	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-0.17-2	12/18/2019	856.35	0.17 - 2 ft	180-100380-2	Excavated			53.283	0.093	1.4	< 0.021 U	2	< 0.17 U	0.03 J	< 0.049 U	4.8	4.7	5.9	1.8	2.8	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-0.17-2	12/17/2019	855.54	0.17 - 2 ft	180-100148-5	Excavated	1600		1.638	< 0.022 U	0.15	< 0.021 U	0.062 J	< 0.17 U	0.023 J		0.066 J	0.064 J	0.09	< 0.023 U	0.69	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	< 4.9 U	< 0.35 U	< 0.25 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.46 U	< 0.3 U	< 0.34 U	< 0.33 U	< 7 U	< 0.58 U	< 2.6 U	< 0.47 U	< 0.27 U	< 3.3 U	< 4.4 U	< 13 U	< 0.47 U	< 20 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 9.7 U	7.1	< 0.5 U	< 0.7 U	< 0.69 U	< 0.7 U	< 0.91 U	16	2.6 J	2.1 J	< 14 U	< 1.2 U	< 5.3 U	< 0.93 U	< 0.54 U	< 6.6 U	< 8.7 U	< 26 U	< 0.92 U	< 40 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 9.7 U	7.1	< 0.5 U	< 0.7 U	< 0.69 U	< 0.7 U	< 0.91 U	16	2.6 J	2.1 J	< 14 U	< 1.2 U	< 5.3 U	< 0.93 U	< 0.54 U	< 6.6 U	< 8.7 U	< 26 U	< 0.92 U	< 40 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	< 0.47 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.044 U	0.2	0.04 J	< 0.032 U	< 0.67 U	< 0.056 U	< 0.25 U	< 0.045 U	< 0.026 U	< 0.32 U	< 0.42 U	< 1.2 U	< 0.045 U	< 1.9 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated																				
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	< 6 U	0.78 J	< 0.31 U	< 0.44 U	< 0.43 U	< 0.43 U	< 0.56 U	3.2	0.46 J	0.43 J	< 8.6 U	< 0.71 U	< 3.3 U	< 0.58 U	< 0.34 U	< 4.1 U	< 5.4 U	< 16 U	< 0.57 U	< 25 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	< 6.2 U	< 0.44 U	< 0.32 U	< 0.45 U	< 0.44 U	< 0.44 U	< 0.58 U	< 0.37 U	< 0.42 U	< 0.42 U	< 8.9 U	< 0.73 U	< 3.3 U	< 0.59 U	< 0.34 U	< 4.2 U	< 5.5 U	< 16 U	< 0.59 U	< 26 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	< 1.2 U	0.12 J	< 0.06 U	< 0.084 U	< 0.082 U	< 0.083 U	< 0.11 U	0.88	0.16 J	0.094 J	< 1.7 U	< 0.14 U	< 0.63 U	< 0.11 U	< 0.065 U	< 0.78 U	< 1 U	< 3.1 U	< 0.11 U	< 4.8 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	< 0.48 U	< 0.035 U	< 0.025 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.045 U	0.07 J	< 0.033 U	< 0.032 U	< 0.69 U	< 0.057 U	< 0.26 U	< 0.046 U	< 0.027 U	< 0.32 U	< 0.43 U	< 1.3 U	< 0.046 U	< 2 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	< 2.4 U	< 0.17 U	< 0.12 U	< 0.17 U	< 0.17 U	< 0.17 U	< 0.22 U	< 0.15 U	< 0.17 U	< 0.16 U	< 3.5 U	< 0.29 U	< 1.3 U	< 0.23 U	< 0.13 U	< 1.6 U	< 2.2 U	< 6.4 U	< 0.23 U	< 10 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	< 0.24 U	0.071 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.45 J	0.095 J	0.057 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	< 0.26 U	0.1 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	1.1	0.19 J	0.15 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	< 0.24 U	< 0.017 UJ	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 UJ	< 0.016 UJ	< 0.016 UJ	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 0.25 U	0.018 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.32	0.059 J	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	< 0.24 U	0.11 J	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.61 J	0.13	0.064 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	< 0.24 U	0.023 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.57 J	0.13 J	0.038 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 0.98 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0.17-2	1/15/2020	856.51	0.17 - 2 ft	180-101084-1	Excavated																				
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0.17-2	1/14/2020	856.54	0.17 - 2 ft	180-101038-2	Excavated																				
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 0.25 U	0.029 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.24 J	0.056 J	< 0.017 UJ	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	< 0.25 U	0.24	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	6.5	1.2	0.074 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	< 0.25 U	0.21	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	4.6	0.71	0.12 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	< 3.5 U	< 0.25 U	< 0.18 U	< 0.25 U	< 0.25 U	< 0.25 U	< 0.33 U	0.33 J	< 0.24 U	< 0.24 U	< 5 U	< 0.42 U	< 1.9 U	< 0.33 U	< 0.2 U	< 2.4 U	< 3.1 U	< 9.3 U	< 0.33 U	< 15 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.017 U	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.026 U	< 1.2 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.31 U	< 0.022 U	< 0.016 U	< 0.022 U	< 0.022 U	< 0.022 U	< 0.029 U	0.045 J	< 0.021 U	< 0.021 U	< 0.44 U	< 0.037 U	< 0.17 U	< 0.029 U	< 0.017 U	< 0.21 U	< 0.28 U	< 0.82 U	< 0.029 U	< 1.3 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.31 U	< 0.022 U	< 0.016 U	< 0.022 U	< 0.022 U	< 0.022 U	< 0.029 U	0.045 J	< 0.021 U	< 0.021 U	< 0.44 U	< 0.037 U	< 0.17 U	< 0.029 U	< 0.017 U	< 0.21 U	< 0.28 U	< 0.82 U	< 0.029 U	< 1.3 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	< 0.26 U	0.037 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.86	0.13	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.22	< 0.017 U	0.017 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.04 J	< 0.018 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.19	0.037 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.27 U	0.22	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	3.7	0.79	0.07 J	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-0.17-2	12/20/2019	853.42	0.17 - 2 ft	180-100361-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.081	0.027 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated	< 0.26 U	0.046 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.52	0.19	0.044 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-0.17-2	12/20/2019	853.19	0.17 - 2 ft	180-100361-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.017 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-0.17-2	12/20/2019	853.57	0.17 - 2 ft	180-100362-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.075 J	0.084	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0.17-2	12/19/2019	857.74	0.17 - 2 ft	180-100363-3	Excavated	< 0.26 U	0.034 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.69	0.22	0.029 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0.17-2	12/19/2019	857.37	0.17 - 2 ft	180-100363-3	Excavated	< 0.27 U	0.03 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.77	0.21	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0.17-2	12/19/2019	858.13	0.17 - 2 ft	180-100363-1	Excavated	< 0.27 U	0.086	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	1.4	0.29	0.045 J	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3247	SSHS-B-3247-SUB-0.17-2	12/19/2019	857.57	0.17 - 2 ft	180-100363-3	Excavated	< 0.25 U	0.098	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	2.1	0.45	0.071 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0.17-2	12/19/2019	857.44	0.17 - 2 ft	180-100363-1	Excavated	< 0.27 U	0.061 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.79	0.16	0.059 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0.17-2	12/19/2019	858.02	0.17 - 2 ft	180-100363-1	Excavated	< 0.27 U	0.03 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.53	0.16	0.024 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0.17-2	12/19/2019	857.46	0.17 - 2 ft	180-100363-1	Excavated	< 0.27 U	0.15	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	2.7	0.52	0.065 J	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-0.17-2	12/19/2019	858.40	0.17 - 2 ft	180-100363-2	Excavated	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.08 J	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-0.17-2	12/19/2019	857.06	0.17 - 2 ft	180-100363-1	Excavated	< 0.27 U	0.26	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	4.9	0.96	0.063 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-0.17-2	12/19/2019	858.14	0.17 - 2 ft	180-100363-2	Excavated	< 0.27 U	0.51	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	7.5	1.6	0.35 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-0.17-2	12/19/2019	858.41	0.17 - 2 ft	180-100363-2	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.22	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-0.17-2	12/19/2019	857.33	0.17 - 2 ft	180-100363-2	Excavated	< 0.26 U	0.11	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	1.7	0.41	0.048 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-0.17-2	12/19/2019	858.57	0.17 - 2 ft	180-100363-1	Excavated	< 0.87 U	0.74	< 0.045 U	< 0.063 U	< 0.061 U	< 0.062 U	< 0.081 U	12	2.1	0.2 J	< 1.2 U	< 0.1 U	< 0.47 U	< 0.083 U	< 0.049 U	< 0.59 U	< 0.78 U	< 2.3 U	< 0.083 U	< 3.6 U
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0.17-2	12/18/2019	856.31	0.17 - 2 ft	180-100380-2	Excavated	< 0.76 U	0.59	< 0.039 U	< 0.055 U	< 0.054 U	< 0.055 U	< 0.071 U	9.9	1.9	0.23 J	< 1.1 U	< 0.09 U	< 0.41 U	< 0.073 U	< 0.043 U	< 0.51 U	< 0.68 U	< 2 U	< 0.072 U	< 3.2 U
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0.17-2	12/18/2019	857.03	0.17 - 2 ft	180-100380-2	Excavated	< 0.24 U	0.017 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.24	0.042 J	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0.17-2	12/18/2019	857.52	0.17 - 2 ft	180-100380-2	Excavated	< 0.27 U	0.023 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.4	0.077 J	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-0.17-2	12/18/2019	854.04	0.17 - 2 ft	180-100380-1	Excavated	< 0.26 U	0.034 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.55	0.14	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-2	Excavated	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	0.14	< 0.019 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-0.17-2	1/27/2021	854.73	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.2	0.053 J	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0.17-2	12/18/2019	855.88	0.17 - 2 ft	180-100380-1	Excavated																				
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0.17-2	12/18/2019	855.39	0.17 - 2 ft	180-100380-1	Excavated																				
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0.17-2	12/18/2019	856.00	0.17 - 2 ft	180-100380-1	Excavated	< 0.27 U	0.035 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.31	0.068 J	0.019 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	0.17 - 2 ft	180-100380-2	Not Excavated																				
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-0.17-2	12/18/2019	855.80	0.17 - 2 ft	180-100380-1	Excavated	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.34	0.075 J	0.024 J	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.027 U	< 1.2 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-0.17-2	2/2/2021	855.85	0.17 - 2 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-0.17-2	12/18/2019	856.25	0.17 - 2 ft	180-100380-2	Excavated	< 0.26 U	0.14	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	1.2	0.21	0.1 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-0.17-2	12/18/2019	856.44	0.17 - 2 ft	180-100380-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.17	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3278	SSHS-B3278-SUB-0.17-2	12/18/2019	856.22	0.17 - 2 ft	180-100380-2	Excavated	< 0.26 U	0.033 J	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.57	0.16	0.028 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-0.17-2	12/18/2019	856.56	0.17 - 2 ft	180-100380-2	Excavated	< 0.26 U	0.13	< 0.013 U	< 0.019 U	< 0.018 U	< 0.024 U	2.1	0.54	0.088 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-0.17-2	12/18/2019	856.88	0.17 - 2 ft	180-100380-2	Excavated	< 0.28 U	0.12	< 0.015 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.026 U	2.2	0.42	0.09 J	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.027 U	< 1.2 U
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-0.17-2	12/18/2019	856.89	0.17 - 2 ft	180-100380-2	Excavated	< 0.26 U	0.046 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.55	0.14	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-0.17-2	12/18/2019	856.35	0.17 - 2 ft	180-100380-2	Excavated	< 0.25 U	0.35	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	5.2	0.84	0.4	< 0.36 U	< 0.03 U	< 0.14 U	0.037 J	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-0.17-2	12/17/2019	855.54	0.17 - 2 ft	180-100148-5	Excavated	< 0.25 U	0.021 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.08	< 0.017 U	0.036 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	< 0.38 U			< 2.4 UJ	< 0.4 U	< 0.3 U	< 0.54 U	< 0.44 U	< 0.77 U	< 0.39 U	< 0.31 U	< 2.2 U	< 2.2 U	< 0.38 U	< 0.36 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.75 U			< 4.7 UJ	52	4.7	< 1.1 U	< 0.88 U	< 1.5 U	< 0.77 U	8.4	< 4.3 U	< 4.4 U	< 0.76 U	< 0.72 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.75 U			< 4.7 UJ	52	4.7	< 1.1 U	< 0.88 U	< 1.5 U	< 0.77 U	8.4	< 4.3 U		< 0.76 U	< 0.72 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	< 0.036 U			< 0.23 UJ	0.37	< 0.028 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U	0.13 J	< 0.21 U	< 0.21 U	< 0.037 U	< 0.035 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated															
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	< 0.46 U			< 2.9 UJ	9	0.93 J	< 0.66 U	< 0.54 U	< 0.95 U	< 0.48 U	1.8 J	< 2.7 U	< 2.7 U	< 0.47 U	< 0.44 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	< 0.47 U			< 3 UJ	0.52 J	< 0.37 U	< 0.68 U	< 0.56 U	< 0.97 U	< 0.49 U	< 0.38 U	< 2.7 U	< 2.8 U	< 0.48 U	< 0.46 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	< 0.089 U			< 0.56 U	1.3	0.16 J	< 0.13 U	< 0.1 U	< 0.18 U	< 0.092 U	0.51	< 0.51 U	< 0.53 U	< 0.091 U	< 0.086 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	< 0.037 U			< 0.23 U	0.11 J	< 0.029 U	< 0.053 U	< 0.043 U	< 0.076 U	< 0.038 U	0.052 J	< 0.21 U	< 0.22 U	< 0.038 U	< 0.036 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	< 0.18 U			< 1.2 U	< 0.2 U	< 0.15 U	< 0.27 U	< 0.22 U	< 0.38 U	< 0.19 U	< 0.15 U	< 1.1 U	< 1.1 U	< 0.19 U	< 0.18 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	< 0.018 U			< 0.12 UJ	0.95 J	0.03 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.34 J	< 0.11 U	< 0.11 U	< 0.019 U	0.089 J
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	< 0.02 U			< 0.12 U	2.3	0.071 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.56 J	< 0.11 U	< 0.12 U	< 0.02 U	0.052 J
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	< 0.018 U			< 0.11 U	< 0.019 UJ	< 0.014 UJ	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.015 UJ	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 UJ
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 0.02 U			< 0.12 U	0.51	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.19	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	< 0.019 U			< 0.12 U	1.1 J	0.073 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.39	< 0.11 U	< 0.11 U	< 0.019 U	0.067 J
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	< 0.018 U			< 0.11 U	0.96 J	0.036 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.48 J	< 0.1 U	< 0.11 U	< 0.019 U	0.059 J
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0.17-2	1/15/2020	856.51	0.17 - 2 ft	180-101084-1	Excavated															
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0.17-2	1/14/2020	856.54	0.17 - 2 ft	180-101038-2	Excavated															
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 0.019 U			< 0.12 U	0.48 J	< 0.015 UJ	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.2 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 UJ
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	< 0.019 U			< 0.12 U	6.7	0.23	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	3.7	< 0.11 U	< 0.11 U	< 0.02 U	0.21
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	< 0.019 U			< 0.12 U	6.3	0.22	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	2.3	< 0.11 U	< 0.11 U	< 0.02 U	0.18
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	< 0.27 U			< 1.7 U	0.38 J	< 0.21 U	< 0.39 U	< 0.32 U	< 0.55 U	< 0.28 U	< 0.22 U	< 1.5 U	< 1.6 U	< 0.27 U	< 0.26 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 0.021 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.017 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.024 U			< 0.15 U	0.053 J	< 0.019 U	< 0.034 U	< 0.028 U	< 0.048 U	< 0.024 U	0.033 J	< 0.14 U	< 0.14 U	< 0.024 U	< 0.023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	< 0.02 U			< 0.12 U	1.2	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.42	< 0.11 U	< 0.12 U	< 0.02 U	0.027 J
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 0.019 U			< 0.12 U	0.28	0.018 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.14	< 0.11 U	< 0.11 U	< 0.019 U	0.037 J
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 0.02 U			< 0.13 U	0.04 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.023 J	< 0.12 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 0.019 U			< 0.12 U	0.2	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.12	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.02 U			< 0.13 U	4	0.15	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	2.8	< 0.12 U	< 0.12 U	< 0.021 U	0.27
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-0.17-2	12/20/2019	853.42	0.17 - 2 ft	180-100361-1	Excavated	< 0.019 U			< 0.12 U	0.079	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.072 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated	< 0.02 U			< 0.12 U	0.68	0.043 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.46	< 0.11 U	< 0.12 U	< 0.02 U	0.14
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-0.17-2	12/20/2019	853.19	0.17 - 2 ft	180-100361-1	Excavated	< 0.019 U			< 0.12 U	0.021 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.022 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-0.17-2	12/20/2019	853.57	0.17 - 2 ft	180-100362-1	Excavated	< 0.02 U			< 0.13 U	0.087	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.076 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0.17-2	12/19/2019	857.74	0.17 - 2 ft	180-100363-3	Excavated	< 0.02 U			< 0.12 U	0.76	0.036 J	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	0.52	< 0.11 U	< 0.12 U	< 0.02 U	0.1
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0.17-2	12/19/2019	857.37	0.17 - 2 ft	180-100363-3	Excavated	< 0.02 U			< 0.13 U	0.85	0.028 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.53	< 0.12 U	< 0.12 U	< 0.021 U	0.05 J
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0.17-2	12/19/2019	858.13	0.17 - 2 ft	180-100363-1	Excavated	< 0.021 U			< 0.13 U	1.9	0.093	< 0.03 UJ	< 0.025 U	< 0.043 U	< 0.022 U	0.91	< 0.12 U	< 0.12 U	< 0.022 U	0.1
Northern Athletic Field	SSHS-B3247	SSHS-B-3247-SUB-0.17-2	12/19/2019	857.57	0.17 - 2 ft	180-100363-3	Excavated	< 0.019 U			< 0.12 U	2.5	0.14	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	1.5	< 0.11 U	< 0.11 U	< 0.02 U	0.17
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0.17-2	12/19/2019	857.44	0.17 - 2 ft	180-100363-1	Excavated	< 0.02 U			< 0.13 U	0.83	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.55	< 0.12 U	< 0.12 U	< 0.021 U	0.2
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0.17-2	12/19/2019	858.02	0.17 - 2 ft	180-100363-1	Excavated	< 0.021 U			< 0.13 U	0.55	0.029 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.42	< 0.12 U	< 0.12 U	< 0.021 U	0.082 J
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0.17-2	12/19/2019	857.46	0.17 - 2 ft	180-100363-1	Excavated	< 0.021 U			< 0.13 U	3.1	0.14	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	1.7	< 0.12 U	< 0.12 U	< 0.021 U	0.16
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-0.17-2	12/19/2019	858.40	0.17 - 2 ft	180-100363-2	Excavated	< 0.021 U			< 0.13 U	0.12	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	0.061 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-0.17-2	12/19/2019	857.06	0.17 - 2 ft	180-100363-1	Excavated	< 0.021 U			< 0.13 U	6.4	0.22	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	3.1	< 0.12 U	< 0.12 U	< 0.021 U	0.14
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-0.17-2	12/19/2019	858.14	0.17 - 2 ft	180-100363-2	Excavated	< 0.021 U			< 0.13 U	8.7	0.47	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	5.2	< 0.12 U	< 0.12 U	< 0.021 U	0.54
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-0.17-2	12/19/2019	858.41	0.17 - 2 ft	180-100363-2	Excavated	< 0.021 U			< 0.13 U	0.3	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.14	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-0.17-2	12/19/2019	857.33	0.17 - 2 ft	180-100363-2	Excavated	< 0.02 U			< 0.13 U	1.9	0.1	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	1.2	< 0.12 U	< 0.12 U	< 0.021 U	0.15
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-0.17-2	12/19/2019	858.57	0.17 - 2 ft	180-100363-1	Excavated	< 0.067 U			< 0.42 U	17	0.75	< 0.096 U	< 0.078 U	< 0.14 U	< 0.069 U	7.2	< 0.38 U	< 0.39 U	< 0.068 U	0.48
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0.17-2	12/18/2019	856.31	0.17 - 2 ft	180-100380-2	Excavated	< 0.058 U			< 0.37 U	13	0.68	< 0.084 U	< 0.069 U	< 0.12 U	< 0.06 U	6.4	< 0.34 U	< 0.34 U	< 0.06 U	0.45
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0.17-2	12/18/2019	857.03	0.17 - 2 ft	180-100380-2	Excavated	< 0.018 U			< 0.11 U	0.31	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.14	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0.17-2	12/18/2019	857.52	0.17 - 2 ft	180-100380-2	Excavated	< 0.02 U			< 0.13 U	0.54	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.22	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-0.17-2	12/18/2019	854.04	0.17 - 2 ft	180-100380-1	Excavated	< 0.02 U			< 0.13 U	0.52	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.49	< 0.12 U	< 0.12 U	< 0.021 U	0.028 J
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-2	Excavated	< 0.021 U			< 0.13 U	0.13	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.15	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-0.17-2	1/27/2021	854.73	0.17 - 2 ft	180-116529-1	Excavated															
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-1	Excavated	< 0.02 U			< 0.13 U	0.2	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.15	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0.17-2	12/18/2019	855.88	0.17 - 2 ft	180-100380-1	Excavated															
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0.17-2	12/18/2019	855.39	0.17 - 2 ft	180-100380-1	Excavated															
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0.17-2	12/18/2019	856.00	0.17 - 2 ft	180-100380-1	Excavated	< 0.021 U			< 0.13 U	0.34	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.24	< 0.12 U	< 0.12 U	< 0.021 U	0.046 J
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	0.17 - 2 ft	180-100380-2	Not Excavated															
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-0.17-2	12/18/2019	855.80	0.17 - 2 ft	180-100380-1	Excavated	< 0.022 U			< 0.14 U	0.36	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.28	< 0.12 U	< 0.13 U	< 0.022 U	0.052 J
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-0.17-2	2/2/2021	855.85	0.17 - 2 ft	180-116723-1	Excavated															
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-0.17-2	12/18/2019	856.25	0.17 - 2 ft	180-100380-2	Excavated	< 0.02 U			< 0.12 U	2.6	0.1	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.77	< 0.11 U	< 0.12 U	< 0.02 U	0.075 J
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-0.17-2	12/18/2019	856.44	0.17 - 2 ft	180-100380-1	Excavated	< 0.02 U			< 0.13 U	0.17	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.14	< 0.12 U	< 0.12 U	< 0.021 U	0.034 J
Northern Athletic Field	SSHS-B3278	SSHS-B3278-SUB-0.17-2	12/18/2019	856.22	0.17 - 2 ft	180-100380-2	Excavated	< 0.02 U			< 0.13 U	0.46	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.49	< 0.12 U	< 0.12 U	< 0.021 U	0.15
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-0.17-2	12/18/2019	856.56	0.17 - 2 ft	180-100380-2	Excavated	< 0.02 U			< 0.12 U	2.4	0.12	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	1.7	< 0.11 U	< 0.12 U	< 0.02 U	0.25
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-0.17-2	12/18/2019	856.88	0.17 - 2 ft	180-100380-2	Excavated	< 0.022 U			< 0.14 U	3.3	0.14	< 0.031 U	< 0.025 U	< 0.045 U	< 0.022 U	1.6	< 0.12 U	< 0.13 U	< 0.022 U	0.19
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-0.17-2	12/18/2019	856.89	0.17 - 2 ft	180-100380-2	Excavated	< 0.02 U			< 0.12 U	0.67	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.49	< 0.11 U	< 0.12 U	< 0.02 U	0.097
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-0.17-2	12/18/2019	856.35	0.17 - 2 ft	180-100380-2	Excavated	< 0.019 U			< 0.12 U	8.6	0.29	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	2.8	< 0.11 U	< 0.11 U	< 0.02 U	0.19
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-0.17-2	12/17/2019	855.54	0.17 - 2 ft	180-100148-5	Excavated	< 0.019 U			< 0.12 U	0.14	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.12	< 0.11 U	< 0.11 U	< 0.02 U	0.1

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated		< 0.29 U	< 3.4 U	< 1.9 U	< 0.37 U	< 2.8 U	< 1.2 U	< 5.3 U		< 0.51 U	< 2.5 U	< 12 U	< 0.4 U	< 2.3 U	< 0.36 U		< 0.33 U	< 3.1 U	< 0.54 U	< 0.41 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated		< 0.58 U	< 6.8 U	< 3.8 U	< 0.73 U	< 5.5 U	< 2.4 U	< 11 U		< 1 U	< 5 U	< 24 U	45	< 4.5 U	44		< 0.65 U	< 6.2 U	< 1.1 U	< 0.82 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 4.4 U	< 0.58 U	< 6.8 U	< 3.8 U	< 0.73 U	< 5.5 U	< 2.4 U	< 11 U		< 1 U	< 5 U	< 24 U	45	< 4.5 U	44		< 0.65 U	< 6.2 U	< 1.1 U	< 0.82 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated		0.069 J	< 0.33 U	< 0.18 U	< 0.035 U	< 0.26 U	< 0.12 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.21	< 0.22 U	0.39		< 0.031 U	< 0.3 U	< 0.052 U	< 0.04 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated																				
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated		< 0.36 U	< 4.2 U	< 2.4 U	< 0.45 U	< 3.4 U	< 1.5 U	< 6.5 U		< 0.63 U	< 3.1 U	< 15 U	7.5	< 2.8 U	6.9		< 0.4 U	< 3.9 U	< 0.66 U	< 0.51 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated		< 0.37 U	< 4.3 U	< 2.4 U	< 0.46 U	< 3.5 U	< 1.5 U	< 6.7 U		< 0.64 U	< 3.2 U	< 15 U	< 0.51 U	< 2.9 U	0.49 J		< 0.41 U	< 4 U	< 0.68 U	< 0.52 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated		0.094 J	< 0.82 U	< 0.46 U	< 0.087 U	< 0.66 U	< 0.29 U	< 1.3 U		< 0.12 U	< 0.6 U	< 2.9 U	1	< 0.54 U	1.4		< 0.077 U	< 0.75 U	< 0.13 U	< 0.098 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated		< 0.029 U	< 0.34 U	< 0.19 U	< 0.036 U	< 0.27 U	< 0.12 U	< 0.52 U		< 0.05 U	< 0.25 U	< 1.2 U	0.083 J	< 0.22 U	0.11 J		< 0.032 U	< 0.31 U	< 0.053 U	< 0.041 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated		< 0.14 U	< 1.7 U	< 0.94 U	< 0.18 U	< 1.4 U	< 0.59 U	< 2.6 U		< 0.25 U	< 1.2 U	< 6 U	< 0.2 U	< 1.1 U	< 0.18 U		< 0.16 U	< 1.5 U	< 0.26 U	< 0.2 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated		0.27 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.6 J	< 0.11 U	0.89 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated		0.1	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	2 J	< 0.12 U	1.9		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated		< 0.014 UJ	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 UJ	< 0.11 U	< 0.017 UJ		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated		0.02 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.17	< 0.12 U	0.47		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated		0.17	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.85 J	< 0.11 U	0.92 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated		0.17 J	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.43 J	< 0.11 U	0.88 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-0.17-2	1/15/2020	856.51	0.17 - 2 ft	180-101084-1	Excavated																				
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-0.17-2	1/14/2020	856.54	0.17 - 2 ft	180-101038-2	Excavated																				
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated		0.037 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.23 J	< 0.11 U	0.39 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated		0.29	< 0.17 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.6	< 0.12 U	8.6		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated		0.2	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	3.7 J	< 0.12 U	7.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated		< 0.21 U	< 2.5 U	< 1.4 U	< 0.26 U	< 2 U	< 0.86 U	< 3.8 U		< 0.37 U	< 1.8 U	< 8.7 U	< 0.29 U	< 1.6 U	0.39 J		< 0.23 U	< 2.2 U	< 0.38 U	< 0.3 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated		< 0.017 U	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.031 U	< 0.023 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated		< 0.018 U	< 0.22 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.075 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.76 U	0.032 J	< 0.14 U	0.054 J		< 0.02 U	< 0.2 U	< 0.034 U	< 0.026 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated		0.028 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.34	< 0.12 U	1.2		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated		0.04 J	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.096	< 0.12 U	0.28		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U	0.046 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.049 J	< 0.12 U	0.25		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated		0.58	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	1.3	< 0.12 U	5		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-0.17-2	12/20/2019	853.42	0.17 - 2 ft	180-100361-1	Excavated		0.016 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.025 J	< 0.12 U	0.11		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated		0.14	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.26	< 0.12 U	0.75		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-0.17-2	12/20/2019	853.19	0.17 - 2 ft	180-100361-1	Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.024 J		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-0.17-2	12/20/2019	853.57	0.17 - 2 ft	180-100362-1	Excavated		< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.031 J	< 0.12 U	0.1		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-0.17-2	12/19/2019	857.74	0.17 - 2 ft	180-100363-3	Excavated		0.13	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.23	< 0.12 U	0.87		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-0.17-2	12/19/2019	857.37	0.17 - 2 ft	180-100363-3	Excavated		0.075 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.2	< 0.12 U	1.1		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-0.17-2	12/19/2019	858.13	0.17 - 2 ft	180-100363-1	Excavated		0.12	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.74	< 0.13 U	2.1		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3247	SSHS-B-3247-SUB-0.17-2	12/19/2019	857.57	0.17 - 2 ft	180-100363-3	Excavated		0.24	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	1.2	< 0.12 U	2.8		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-0.17-2	12/19/2019	857.44	0.17 - 2 ft	180-100363-1	Excavated		0.17	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.35	< 0.12 U	0.93		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-0.17-2	12/19/2019	858.02	0.17 - 2 ft	180-100363-1	Excavated		0.09	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.19	< 0.13 U	0.77		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-0.17-2	12/19/2019	857.46	0.17 - 2 ft	180-100363-1	Excavated		0.24	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.95	< 0.13 U	3.8		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-0.17-2	12/19/2019	858.40	0.17 - 2 ft	180-100363-2	Excavated		< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.047 J	< 0.13 U	0.1		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-0.17-2	12/19/2019	857.06	0.17 - 2 ft	180-100363-1	Excavated		0.19	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	2.2	< 0.13 U	7.2		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-0.17-2	12/19/2019	858.14	0.17 - 2 ft	180-100363-2	Excavated		0.67	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	6.1	< 0.13 U	11		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-0.17-2	12/19/2019	858.41	0.17 - 2 ft	180-100363-2	Excavated		0.027 J	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.099	< 0.13 U	0.33		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-0.17-2	12/19/2019	857.33	0.17 - 2 ft	180-100363-2	Excavated		0.23	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.53	< 0.12 U	2.1		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-0.17-2	12/19/2019	858.57	0.17 - 2 ft	180-100363-1	Excavated		0.71	< 0.61 U	< 0.34 U	< 0.065 U	< 0.49 U	< 0.21 U	< 0.94 U		< 0.091 U	< 0.45 U	< 2.1 U	6.5	< 0.41 U	17		< 0.058 U	< 0.56 U	< 0.095 U	< 0.073 U
Northern Athletic Field	SSHS-B3261	SSHS-B3261-SUB-0.17-2	12/18/2019	856.31	0.17 - 2 ft	180-100380-2	Excavated		0.69	< 0.53 U	< 0.3 U	< 0.057 U	< 0.43 U	< 0.19 U	< 0.82 U		< 0.079 U	< 0.39 U	< 1.9 U	4.9	< 0.36 U	14		< 0.051 U	< 0.49 U	< 0.084 U	< 0.064 U
Northern Athletic Field	SSHS-B3262	SSHS-B3262-SUB-0.17-2	12/18/2019	857.03	0.17 - 2 ft	180-100380-2	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.096	< 0.11 U	0.32		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3263	SSHS-B3263-SUB-0.17-2	12/18/2019	857.52	0.17 - 2 ft	180-100380-2	Excavated		0.016 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.17	< 0.12 U	0.59		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-0.17-2	12/18/2019	854.04	0.17 - 2 ft	180-100380-1	Excavated		0.05 J	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.17	< 0.12 U	0.69		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-2	Excavated		0.03 J	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.68 U	0.075 J	< 0.13 U	0.24		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-0.17-2	1/27/2021	854.73	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-0.17-2	12/18/2019	854.73	0.17 - 2 ft	180-100380-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.056 J	< 0.12 U	0.26		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-0.17-2	12/18/2019	855.88	0.17 - 2 ft	180-100380-1	Excavated																				
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-0.17-2	12/18/2019	855.39	0.17 - 2 ft	180-100380-1	Excavated																				
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-0.17-2	12/18/2019	856.00	0.17 - 2 ft	180-100380-1	Excavated		0.073 J	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.15	< 0.13 U	0.36		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	0.17 - 2 ft	180-100380-2	Not Excavated																				
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-0.17-2	12/18/2019	855.80	0.17 - 2 ft	180-100380-1	Excavated		0.075 J	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	0.18	< 0.13 U	0.44		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-0.17-2	2/2/2021	855.85	0.17 - 2 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-0.17-2	12/18/2019	856.25	0.17 - 2 ft	180-100380-2	Excavated		0.17	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	1.6	< 0.12 U	2.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-0.17-2	12/18/2019	856.44	0.17 - 2 ft	180-100380-1	Excavated		0.051 J	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.12	< 0.12 U	0.22		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3278	SSHS-B3278-SUB-0.17-2	12/18/2019	856.22	0.17 - 2 ft	180-100380-2	Excavated		0.28	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.23	< 0.12 U	0.8		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-0.17-2	12/18/2019	856.56	0.17 - 2 ft	180-100380-2	Excavated		0.45	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.67	< 0.12 U	2.7		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-0.17-2	12/18/2019	856.88	0.17 - 2 ft	180-100380-2	Excavated		0.34	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	1.4	< 0.13 U	3.2		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-0.17-2	12/18/2019	856.89	0.17 - 2 ft	180-100380-2	Excavated		0.16	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.32	< 0.12 U	0.79		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-0.17-2	12/18/2019	856.35	0.17 - 2 ft	180-100380-2	Excavated		0.26	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	4.9	< 0.12 U	7.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-0.17-2	12/17/2019	855.54	0.17 - 2 ft	180-100148-5	Excavated		0.16	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.09	< 0.12 U	0.076 J		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-0.17-2	12/17/2019	856.21	0.17 - 2 ft	180-100148-5	Excavated	360		10.708	0.032 J	0.53	< 0.022 U	0.33	< 0.18 U	0.06 J		0.83	0.96	1.1	0.46	1.1	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-0.17-2	12/17/2019	856.34	0.17 - 2 ft	180-100148-5	Excavated	1600		620.9	3.8	22	< 0.23 U	33	< 1.9 U	1.7 J		49	45	45	17	30	< 0.2 U	< 0.16 U	< 0.32 U	< 4.6 U	< 0.3 U	< 2.9 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-0.17-2	12/17/2019	856.90	0.17 - 2 ft	180-100148-6	Excavated	62		3.761	< 0.022 U	0.13	< 0.021 U	0.081	< 0.17 U	< 0.016 U	< 0.047 U	0.37	0.37	0.45	0.17	0.29	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-0.17-2	12/17/2019	857.22	0.17 - 2 ft	180-100148-6	Excavated	670		30.281	0.071 J	1.9	< 0.062 U	1	< 0.5 U	0.086 J	< 0.14 U	2.6	2.5	3.8	1.2	3.1	< 0.055 U	< 0.042 U	< 0.085 U	< 1.2 U	< 0.08 U	< 0.79 U
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-0.17-2	12/17/2019	857.35	0.17 - 2 ft	180-100148-5	Excavated	170		3.453	< 0.023 U	0.12	< 0.022 U	0.084	< 0.17 U	< 0.017 U		0.3	0.3	0.33	0.16	0.31	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-0.17-2	12/17/2019	857.15	0.17 - 2 ft	180-100148-5	Excavated	320		11.621	< 0.044 U	0.39	< 0.042 U	0.31	< 0.34 U	0.046 J		1	0.99	1.2	0.45	1	< 0.037 U	< 0.028 U	< 0.057 U	< 0.82 U	< 0.054 U	< 0.53 U
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-0.17-2	12/17/2019	856.87	0.17 - 2 ft	180-100148-4	Excavated	240																				
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-0.17-2	12/17/2019	855.96	0.17 - 2 ft	180-100148-4	Excavated			92.86	0.17 J	1.7	< 0.11 U	4	< 0.92 U	0.12 J		8.4	7.3	8	3.3	5.4	< 0.1 U	< 0.076 U	< 0.16 U	< 2.2 U	< 0.15 U	< 1.4 U
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-0.17-2	12/16/2019	856.22	0.17 - 2 ft	180-100148-2	Excavated			17.67	< 0.09 U	1.2	< 0.085 U	0.57	< 0.68 U	< 0.066 U		1.5	1.6	2.1	0.69	1.7	< 0.075 U	< 0.057 U	< 0.12 U	< 1.7 U	< 0.11 U	< 1.1 U
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-0.17-2	12/17/2019	857.02	0.17 - 2 ft	180-100148-5	Excavated	530		5.128	< 0.024 U	0.3	< 0.023 U	0.16	< 0.18 U	0.048 J		0.36	0.38	0.45	0.17	0.57	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-0.17-2	12/17/2019	857.20	0.17 - 2 ft	180-100148-5	Excavated	1600		13.026	0.058 J	0.27	< 0.021 U	0.26	< 0.17 U	0.095 J		0.88	0.53	0.96	0.28	0.61	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-0.17-2	12/17/2019	857.10	0.17 - 2 ft	180-100148-4	Excavated	130																				
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-0.17-2	12/17/2019	856.38	0.17 - 2 ft	180-100148-3	Excavated	110		11.815	0.058 J	0.23	< 0.022 U	0.42	< 0.17 U	0.019 J		1.1	0.92	1	0.38	0.76	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-0.17-2	12/16/2019	856.13	0.17 - 2 ft	180-100148-2	Excavated			10.371	0.063 J	0.2	< 0.044 U	0.23	< 0.36 U	< 0.034 U		1	0.85	0.97	0.42	0.68	< 0.039 U	< 0.03 U	< 0.061 U	< 0.87 U	< 0.057 U	< 0.56 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-0.17-2	12/17/2019	856.19	0.17 - 2 ft	180-100148-5	Excavated	1100		4.602	0.031 J	0.27	< 0.023 U	0.16	< 0.19 U	0.081 J		0.26	0.29	0.36	0.13	0.51	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-0.17-2	12/17/2019	856.73	0.17 - 2 ft	180-100148-5	Excavated	890		4.553	< 0.023 U	0.22	< 0.022 U	0.14	< 0.18 U	0.032 J		0.32	0.33	0.39	0.15	0.49	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	856.97	0.17 - 2 ft	180-100148-4	Excavated	93		21.464	0.11	0.32	< 0.022 U	0.5	< 0.18 U	0.075 J		2	1.7	1.9	0.89	1.4	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated	570																				
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-0.17-2	12/16/2019	855.94	0.17 - 2 ft	180-100148-2	Excavated	61		3.177	< 0.023 U	0.059 J	< 0.022 U	0.062 J	< 0.18 U	0.038 J		0.22	0.18	0.23	0.075 J	0.17	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-0.17-2	12/17/2019	856.00	0.17 - 2 ft	180-100148-6	Excavated	180		1.883	< 0.048 U	0.071 J	< 0.046 U	0.055 J	< 0.37 U	< 0.035 U	< 0.1 U	0.15 J	0.14 J	0.16 J	0.091 J	0.14 J	< 0.04 U	< 0.031 U	< 0.062 U	< 0.9 U	< 0.059 U	< 0.58 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-0.17-2	12/17/2019	855.68	0.17 - 2 ft	180-100148-6	Excavated	4400		3.502	< 0.023 U	0.16	< 0.022 U	0.078 J	< 0.18 U	0.038 J		0.3	0.14 J-	0.15 J-	0.083 J-	0.27 J-	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-0.17-2	12/17/2019	856.31	0.17 - 2 ft	180-100148-4	Excavated	600		2.054	< 0.024 U	0.11	< 0.022 U	0.054 J	< 0.18 U	0.03 J		0.12	0.14	0.16	0.054 J	0.27	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	856.64	0.17 - 2 ft	180-100148-4	Excavated	3000																				
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-0.17-2	12/16/2019	856.96	0.17 - 2 ft	180-100148-2	Excavated	110 J																				
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-0.17-2	12/16/2019	856.94	0.17 - 2 ft	180-100148-2	Excavated	990		4.285	< 0.024 U	0.17	< 0.023 U	0.11	< 0.18 U	0.029 J		0.32	0.33	0.41	0.15	0.46	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-0.17-2	12/17/2019	856.43	0.17 - 2 ft	180-100148-6	Excavated	230		2.433	< 0.022 U	0.11	< 0.021 U	0.068 J	< 0.17 U	< 0.016 U	< 0.048 U	0.2	0.2	0.21	0.091	0.19	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	856.17	0.17 - 2 ft	180-100148-4	Excavated	1200																				
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	856.62	0.17 - 2 ft	180-100148-2	Excavated	410																				
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-0.17-2	12/16/2019	856.86	0.17 - 2 ft	180-100148-3	Excavated	120																				
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-0.17-2	12/16/2019	856.76	0.17 - 2 ft	180-100148-3	Excavated	240																				
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	855.76	0.17 - 2 ft	180-100148-2	Excavated	860																				
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	856.21	0.17 - 2 ft	180-100148-3	Excavated	750																				
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-0.17-2	1/28/2021	856.22	0.17 - 2 ft	180-116609-1	Excavated	1500	1500																			
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	856.48	0.17 - 2 ft	180-100148-3	Excavated	< 41 U																				
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	855.88	0.17 - 2 ft	180-100148-3	Excavated	400																				
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-0.17-2	12/16/2019	853.99	0.17 - 2 ft	180-100148-1	Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.015 U	< 0.017 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-0.17-2	12/16/2019	854.39	0.17 - 2 ft	180-100148-1	Excavated	1300		10.718	0.048 J	0.45	< 0.021 U	0.4	< 0.17 U	0.14 J	< 0.049 U	0.65	0.63	0.8	0.34	0.77	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-0.17-2	12/16/2019	853.34	0.17 - 2 ft	180-100148-1	Excavated			0.147	< 0.021 U	0.016 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.02 J	< 0.016 U	< 0.018 U	< 0.022 U	0.055 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-0.17-2	12/16/2019	854.14	0.17 - 2 ft	180-100148-1	Excavated	380		4.761	< 0.024 U	0.28	< 0.023 U	0.17	< 0.18 U	0.044 J	< 0.052 U	0.31	0.37	0.5	0.18	0.6	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-0.17-2	12/16/2019	852.74	0.17 - 2 ft	180-100148-1	Excavated	49 J		1.295	< 0.022 U	0.071 J	< 0.021 U	0.044 J	< 0.17 U	< 0.016 U	< 0.048 U	0.097	0.11	0.16	0.059 J	0.15	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-0.17-2	12/16/2019	851.73	0.17 - 2 ft	180-100148-1	Excavated	56 J		0.98	< 0.024 U	0.048 J	< 0.022 U	0.037 J	< 0.18 U	< 0.017 U	< 0.051 U	0.066 J	0.087	0.13	0.045 J	0.1	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-0.17-2	12/16/2019	852.38	0.17 - 2 ft	180-100148-1	Excavated	200		5.858	< 0.023 U	0.24	< 0.022 U	0.17	< 0.18 U	< 0.017 U	< 0.05 U	0.57	0.55	0.84	0.24	0.45	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-0.17-2	12/16/2019	853.06	0.17 - 2 ft	180-100148-1	Excavated	54 J		0.545	< 0.023 U	0.019 J	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.038 J	0.062 J	0.051 J	0.032 J	0.085	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-0.17-2	12/16/2019	853.75	0.17 - 2 ft	180-100148-1	Excavated	75		0.265	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.023 J	0.03 J	0.03 J	< 0.023 U	0.032 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3334	SSHS-B3334-SUB-0.17-2	12/17/2019	853.15	0.17 - 2 ft	180-100148-6	Excavated	100 J																				
Northern Athletic Field	SSHS-B3335	SSHS-B3335-SUB-0.17-2	12/17/2019	853.90	0.17 - 2 ft	180-100148-4	Excavated	43 J																				
Northern Athletic Field	SSHS-B3336	SSHS-B3336-SUB-0.17-2	12/17/2019	854.13	0.17 - 2 ft	180-100148-4	Excavated	< 42 U																				
Northern Athletic Field	SSHS-B3337	SSHS-B3337-SUB-0.17-2	12/17/2019	854.69	0.17 - 2 ft	180-100148-4	Excavated	2100																				
Northern Athletic Field	SSHS-B3338	SSHS-B3338-SUB-0.17-2	12/17/2019	855.11	0.17 - 2 ft	180-100148-4	Excavated	1900																				
Northern Athletic Field	SSHS-B3340	SSHS-B3340-SUB-0.17-2	12/17/2019	853.87	0.17 - 2 ft	180-100148-6	Excavated	< 39 U																				
Northern Athletic Field	SSHS-B3341	SSHS-B3341-SUB-0.17-2	12/17/2019	853.57	0.17 - 2 ft	180-100148-6	Excavated	120																				
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-0.17-2	12/17/2019	853.63	0.17 - 2 ft	180-100148-5	Excavated	98		11.028	< 0.022 U	0.32	< 0.021 U	0.23	< 0.17 U	0.029 J		0.97	1	1.2	0.43	0.86	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated		44 J	0.111	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	0.03 J	< 0.023 U	0.02 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated		85	4.65	0.029 J	0.21	< 0.022 U	0.18	< 0.18 U	< 0.017 U	< 0.051 U	0.45	0.46	0.49	0.2	0.31	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U	< 0.28 U
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated			5.354	< 0.022 U	0.25	< 0.02 U	0.17	< 0.16 U	< 0.016 U	< 0.046 U	0.5	0.57	0.75	0.17	0.43 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated		50 J	38.42	0.33	1.5	< 0.042 U	1.7	< 0.34 U	0.049 J	< 0.095 U	3.5	3.2	3.1	1.3	2	< 0.037 U	< 0.028 U	< 0.057 U	< 0.82 U	< 0.054 U	< 0.53 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated		150	3.46	< 0.1 U	0.1 J	< 0.097 U	< 0.092 U	< 0.78 U	< 0.075 U	< 0.22 U	0.31 J	0.25 J	0.32 J	0.16 J	0.25 J	< 0.085 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.12 U	< 1.2 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	340		2.059	< 0.023 U	0.11 J	< 0.022 U	0.062 J	< 0.18 U	< 0.017 U	< 0.05 U	0.19 J	0.24 J	0.26 J	0.078 J	0.22 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	490		12.57	< 0.11 U	0.83 J	< 0.1 U	0.44 J	< 0.82 U	< 0.078 U	< 0.23 U	1.2 J	1.2 J	1.3 J	0.6 J	1 J	< 0.089 U	< 0.068 U	< 0.14 U	< 2 U	< 0.13 U	< 1.3 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated			5.96	< 0.021 U	0.15	< 0.02 U	0.18	< 0.16 U	0.026 J	< 0.045 U	0.52	0.53	0.6	0.24	0.56	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated			2.459	< 0.042 U	0.084 J	< 0.039 U	0.055 J	< 0.32 U	< 0.03 U	< 0.09 U	0.23	0.26	0.32	0.11 J	0.23	< 0.034 U	< 0.026 U	< 0.053 U	< 0.77 U	< 0.05 U	< 0.5 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated			0.842	< 0.02 U	0.11 J	< 0.019 U	0.086 J	< 0.15 U	< 0.015 U	< 0.044 U	0.048 J	0.057 J	0.062 J	0.022 J	0.17 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated			0.842	< 0.02 U	0.11 J	< 0.019 U	0.086 J	< 0.15 U	< 0.015 U	< 0.044 U	0.048 J	0.057 J	0.062 J	0.022 J	0.17 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0.17-2	7/28/2020	858.45	0.17 - 2 ft	180-108872-1	Excavated			106.74	0.42	4	< 0.1 U	3.1	< 0.81 U	0.096 J	< 0.23 U	8.8	7.7	9.5	3.8	5.9	< 0.088 U	< 0.067 U	< 0.14 U	< 2 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0.17-2	7/28/2020	858.43	0.17 - 2 ft	180-108872-1	Excavated			95.48	0.28 J	4.1	< 0.19 U	2.3	< 1.5 U	< 0.15 U	< 0.44 U	8.2	8.4	11	4.2	6.5	< 0.17 U	< 0.13 U	< 0.26 U	< 3.7 U	< 0.25 U	< 2.4 U
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0.17-2	7/28/2020	858.58	0.17 - 2 ft	180-108872-1	Excavated			5.172	< 0.021 U	0.31	< 0.02 U	0.17	< 0.16 U	< 0.016 U	< 0.046 U	0.5	0.44	0.56	0.2	0.35	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0.17-2	7/28/2020	856.51	0.17 - 2 ft	180-108872-1	Excavated			2.641	< 0.024 U	0.15	< 0.022 U	0.083	< 0.18 U	0.019 J	< 0.051 U	0.23	0.25	0.36	0.09	0.24	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-0.17-2	12/17/2019	856.21	0.17 - 2 ft	180-100148-5	Excavated	< 0.26 U	0.1	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.83	0.29	0.11 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-0.17-2	12/17/2019	856.34	0.17 - 2 ft	180-100148-5	Excavated	< 2.8 U	6.1	< 0.14 U	< 0.2 U	< 0.2 U	< 0.2 U	< 0.26 U	41	7.1	8.7	< 4 U	< 0.33 U	< 1.5 U	0.28 J	< 0.16 U	< 1.9 U	< 2.5 U	< 7.4 U	< 0.26 U	< 12 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-0.17-2	12/17/2019	856.90	0.17 - 2 ft	180-100148-6	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.35	0.13	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-0.17-2	12/17/2019	857.22	0.17 - 2 ft	180-100148-6	Excavated	< 0.75 U	0.16 J	< 0.038 U	< 0.054 U	< 0.053 U	< 0.053 U	< 0.07 U	2.8	0.84	0.16 J	< 1.1 U	< 0.088 U	< 0.4 U	< 0.071 U	< 0.042 U	< 0.5 U	< 0.67 U	< 2 U	< 0.071 U	< 3.1 U
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-0.17-2	12/17/2019	857.35	0.17 - 2 ft	180-100148-5	Excavated	< 0.26 U	0.025 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.26	0.13	0.035 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-0.17-2	12/17/2019	857.15	0.17 - 2 ft	180-100148-5	Excavated	< 0.5 U	0.086 J	< 0.026 UJ	< 0.036 U	< 0.035 U	< 0.036 U	< 0.047 U	0.92	0.35	0.1 J	< 0.72 U	< 0.059 U	< 0.27 U	< 0.048 U	< 0.028 U	< 0.34 U	< 0.45 U	< 1.3 U	< 0.048 U	< 2.1 U
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-0.17-2	12/17/2019	856.87	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-0.17-2	12/17/2019	855.96	0.17 - 2 ft	180-100148-4	Excavated	< 1.4 U	0.45	< 0.07 UJ	< 0.099 U	< 0.096 U	< 0.097 U	< 0.13 U	7.2	1.5	0.62 J	< 2 U	< 0.16 U	< 0.73 U	< 0.13 U	< 0.076 U	< 0.92 U	< 1.2 U	< 3.6 U	< 0.13 U	< 5.6 U
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-0.17-2	12/16/2019	856.22	0.17 - 2 ft	180-100148-2	Excavated	< 1 U	0.11 J	< 0.052 U	< 0.074 U	< 0.072 U	< 0.073 U	< 0.095 U	1.6	0.63	0.075 J	< 1.5 U	< 0.12 U	< 0.55 U	< 0.097 U	< 0.057 U	< 0.68 U	< 0.91 U	< 2.7 U	< 0.097 U	< 4.2 U
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-0.17-2	12/17/2019	857.02	0.17 - 2 ft	180-100148-5	Excavated	< 0.27 U	0.051 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.35	0.16	0.097 J	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-0.17-2	12/17/2019	857.20	0.17 - 2 ft	180-100148-5	Excavated	< 0.26 U	0.054 J	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.98	0.21	0.33 J	< 0.37 U	< 0.03 U	< 0.14 U	0.049 J	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-0.17-2	12/17/2019	857.10	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-0.17-2	12/17/2019	856.38	0.17 - 2 ft	180-100148-3	Excavated	< 0.26 U	0.13	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	1	0.26	0.056 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-0.17-2	12/16/2019	856.13	0.17 - 2 ft	180-100148-2	Excavated	< 0.53 U	0.079 J	< 0.027 U	< 0.039 U	< 0.038 U	< 0.038 U	< 0.05 U	0.99	0.31	0.054 J	< 0.76 U	< 0.063 U	< 0.29 U	< 0.051 U	< 0.03 U	< 0.36 U	< 0.48 U	< 1.4 U	< 0.051 U	< 2.2 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-0.17-2	12/17/2019	856.19	0.17 - 2 ft	180-100148-5	Excavated	< 0.28 U	0.042 J	< 0.014 UJ	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.3	0.15	0.14 J	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-0.17-2	12/17/2019	856.73	0.17 - 2 ft	180-100148-5	Excavated	< 0.26 U	0.048 J	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.33	0.14	0.076 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	856.97	0.17 - 2 ft	180-100148-4	Excavated	< 0.26 U	0.19	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	1.8	0.39	0.18 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-0.17-2	12/16/2019	855.94	0.17 - 2 ft	180-100148-2	Excavated	< 0.26 U	0.019 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.22	0.1	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-0.17-2	12/17/2019	856.00	0.17 - 2 ft	180-100148-6	Excavated	< 0.55 U	< 0.039 U	< 0.028 U	< 0.04 U	< 0.039 U	< 0.039 U	< 0.051 U	0.16 J	0.16 J	< 0.037 U	< 0.79 U	< 0.065 U	< 0.3 U	< 0.052 U	< 0.031 U	< 0.37 U	< 0.49 U	< 1.5 U	< 0.052 U	< 2.3 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-0.17-2	12/17/2019	855.68	0.17 - 2 ft	180-100148-4	Excavated	< 0.26 U	0.027 J	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.68	0.14 J-	0.085 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-0.17-2	12/17/2019	856.31	0.17 - 2 ft	180-100148-4	Excavated	< 0.27 U	0.022 J	< 0.014 UJ	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.13	0.11	0.057 J	< 0.38 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	856.64	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-0.17-2	12/16/2019	856.96	0.17 - 2 ft	180-100148-2	Excavated																				
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-0.17-2	12/16/2019	856.94	0.17 - 2 ft	180-100148-2	Excavated	< 0.27 U	0.04 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.32	0.15	0.069 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-0.17-2	12/17/2019	856.43	0.17 - 2 ft	180-100148-6	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.2	0.095	0.028 J	< 0.36 U	< 0.03 U	< 0.14 U	0.044 J	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	856.17	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	856.62	0.17 - 2 ft	180-100148-2	Excavated																				
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-0.17-2	12/16/2019	856.86	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-0.17-2	12/16/2019	856.76	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	855.76	0.17 - 2 ft	180-100148-2	Excavated																				
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	856.21	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-0.17-2	1/28/2021	856.22	0.17 - 2 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	856.48	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	855.88	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-0.17-2	12/16/2019	853.99	0.17 - 2 ft	180-100148-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.015 U	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-0.17-2	12/16/2019	854.39	0.17 - 2 ft	180-100148-1	Excavated	< 0.26 U	0.12	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.69	0.17	0.39	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-0.17-2	12/16/2019	853.34	0.17 - 2 ft	180-100148-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.021 J	< 0.017 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-0.17-2	12/16/2019	854.14	0.17 - 2 ft	180-100148-1	Excavated	< 0.27 U	0.066 J	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.32	0.074 J	0.095 J	< 0.39 UJ	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-0.17-2	12/16/2019	852.74	0.17 - 2 ft	180-100148-1	Excavated	< 0.25 U	0.019 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.11	0.029 J	0.019 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-0.17-2	12/16/2019	851.73	0.17 - 2 ft	180-100148-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.099	0.025 J	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-0.17-2	12/16/2019	852.38	0.17 - 2 ft	180-100148-1	Excavated	< 0.26 U	0.045 J	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	0.54	0.14	0.041 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-0.17-2	12/16/2019	853.06	0.17 - 2 ft	180-100148-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.045 J	0.019 J	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-0.17-2	12/16/2019	853.75	0.17 - 2 ft	180-100148-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.032 J	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3334	SSHS-B3334-SUB-0.17-2	12/17/2019	853.15	0.17 - 2 ft	180-100148-6	Excavated																				
Northern Athletic Field	SSHS-B3335	SSHS-B3335-SUB-0.17-2	12/17/2019	853.90	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3336	SSHS-B3336-SUB-0.17-2	12/17/2019	854.13	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3337	SSHS-B3337-SUB-0.17-2	12/17/2019	854.69	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3338	SSHS-B3338-SUB-0.17-2	12/17/2019	855.11	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3340	SSHS-B3340-SUB-0.17-2	12/17/2019	853.87	0.17 - 2 ft	180-100148-6	Excavated																				
Northern Athletic Field	SSHS-B3341	SSHS-B3341-SUB-0.17-2	12/17/2019	853.57	0.17 - 2 ft	180-100148-6	Excavated																				
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-0.17-2	12/17/2019	853.63	0.17 - 2 ft	180-100148-5	Excavated	< 0.25 U	0.048 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.89	0.26	0.069 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	< 0.27 U	0.032 J	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.44	0.15	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 2.3 U
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated	< 0.24 U	0.036 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.51 J	0.12	0.016 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	< 0.5 U	0.28	< 0.052 U	< 0.036 U	< 0.035 U	< 0.036 U	< 0.046 U	3.1	0.67	0.19 J	< 0.71 U	< 0.059 U	< 0.27 U	< 0.048 U	< 0.057 U	< 0.34 U	< 0.45 U	< 1.3 U	< 0.047 U	< 4.3 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	< 1.2 U	< 0.083 U	< 0.12 U	< 0.084 U	< 0.082 U	< 0.083 U	< 0.11 U	0.34 J	< 0.23 U	< 0.078 U	< 1.7 U	< 0.14 U	< 0.63 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U	< 0.11 U	< 9.9 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	0.19 J	< 0.052 UJ	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U	< 2.2 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	< 1.2 U	< 0.087 U	< 0.13 U	< 0.088 U	< 0.086 U	< 0.087 U	< 0.11 U	1.2 J	0.52 J	< 0.082 U	< 1.7 U	< 0.14 U	< 0.65 U	< 0.12 U	< 0.14 U	< 0.82 U	< 1.1 U	< 3.2 U	< 0.12 U	< 10 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.24 U	0.046 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.5	0.13	0.059 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.47 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.044 U	0.26	< 0.092 U	< 0.032 U	< 0.67 U	< 0.056 U	< 0.25 U	< 0.045 U	< 0.053 U	< 0.32 U	< 0.42 U	< 1.2 U	< 0.045 U	< 4 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.072 J	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	0.03 J	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.072 J	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	0.03 J	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0.17-2	7/28/2020	858.45	0.17 - 2 ft	180-108872-1	Excavated	< 1.2 U	0.67	< 0.13 U	< 0.087 U	< 0.084 U	< 0.085 U	< 0.11 U	9.2	1.6	0.34 J	< 1.7 U	< 0.14 U	< 0.65 U	< 0.11 U	< 0.14 U	< 0.81 U	< 1.1 U	< 3.2 U	< 0.11 U	< 10 U
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0.17-2	7/28/2020	858.43	0.17 - 2 ft	180-108872-1	Excavated	< 2.3 U	0.57 J	< 0.24 U	< 0.17 U	< 0.16 U	< 0.16 U	< 0.21 U	9.7	1.7	0.26 J	< 3.3 U	< 0.27 U	< 1.2 U	< 0.22 U	< 0.26 U	< 1.5 U	< 2 U	< 6.1 U	< 0.22 U	< 19 U
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0.17-2	7/28/2020	858.58	0.17 - 2 ft	180-108872-1	Excavated	< 0.24 U	0.025 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.53	0.14	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0.17-2	7/28/2020	856.51	0.17 - 2 ft	180-108872-1	Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.28	0.068 J	0.021 J	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 2.3 U

DRAFT

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-0.17-2	12/17/2019	856.21	0.17 - 2 ft	180-100148-5	Excavated	< 0.02 U			< 0.13 U	1.3	0.096	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.91	< 0.12 U	< 0.12 U	< 0.021 U	0.22
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-0.17-2	12/17/2019	856.34	0.17 - 2 ft	180-100148-5	Excavated	< 0.21 U			< 1.3 U	110	16	< 0.31 U	< 0.25 U	< 0.44 U	< 0.22 U	29	< 1.2 U	< 1.3 U	< 0.22 U	6.3
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-0.17-2	12/17/2019	856.90	0.17 - 2 ft	180-100148-6	Excavated	< 0.019 U			< 0.12 U	0.53	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.28	< 0.11 U	< 0.11 U	< 0.019 U	0.033 J
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-0.17-2	12/17/2019	857.22	0.17 - 2 ft	180-100148-6	Excavated	< 0.057 U			< 0.36 U	3.4	0.18 J	< 0.082 U	< 0.067 U	< 0.12 U	< 0.059 U	2.6	< 0.33 U	< 0.34 U	< 0.059 U	0.48
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-0.17-2	12/17/2019	857.35	0.17 - 2 ft	180-100148-5	Excavated	< 0.02 U			< 0.12 U	0.45	0.019 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.27	< 0.11 U	< 0.12 U	< 0.02 U	0.057 J
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-0.17-2	12/17/2019	857.15	0.17 - 2 ft	180-100148-5	Excavated	< 0.038 U			< 0.24 U	1.7	0.051 J	< 0.055 U	< 0.045 U	< 0.079 U	< 0.04 U	0.94	< 0.22 U	< 0.23 U	< 0.039 U	0.16
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-0.17-2	12/17/2019	856.87	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-0.17-2	12/17/2019	855.96	0.17 - 2 ft	180-100148-4	Excavated	< 0.1 U			< 0.65 U	17	0.59	< 0.15 U	< 0.12 U	< 0.21 U	< 0.11 U	5.2	< 0.6 U	< 0.61 U	< 0.11 U	0.38 J
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-0.17-2	12/16/2019	856.22	0.17 - 2 ft	180-100148-2	Excavated	< 0.078 U			< 0.49 U	2.1	0.12 J	< 0.11 U	< 0.091 U	< 0.16 U	< 0.081 U	1.4	< 0.45 U	< 0.46 U	< 0.08 U	0.18 J
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-0.17-2	12/17/2019	857.02	0.17 - 2 ft	180-100148-5	Excavated	< 0.021 U			< 0.13 U	0.66	0.038 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.42	< 0.12 U	< 0.12 U	< 0.022 U	0.17
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-0.17-2	12/17/2019	857.20	0.17 - 2 ft	180-100148-5	Excavated	< 0.02 U			< 0.12 U	2.5	0.078 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.58	0.12 J	0.34 J	< 0.02 U	0.4
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-0.17-2	12/17/2019	857.10	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-0.17-2	12/17/2019	856.38	0.17 - 2 ft	180-100148-3	Excavated	< 0.02 U			< 0.12 U	2.1	0.067 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.7	< 0.11 U	< 0.12 U	< 0.02 U	0.087
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-0.17-2	12/16/2019	856.13	0.17 - 2 ft	180-100148-2	Excavated	< 0.041 U			< 0.26 U	1.6	0.058 J	< 0.059 U	< 0.048 U	< 0.084 U	< 0.042 U	0.62	< 0.23 U	< 0.24 U	< 0.042 U	0.09 J
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-0.17-2	12/17/2019	856.19	0.17 - 2 ft	180-100148-5	Excavated	< 0.021 U			< 0.13 U	0.46	0.071 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.35	< 0.12 U	< 0.12 U	< 0.022 U	0.34
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-0.17-2	12/17/2019	856.73	0.17 - 2 ft	180-100148-5	Excavated	< 0.02 U			< 0.12 U	0.64	0.033 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.33	< 0.11 U	< 0.12 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	856.97	0.17 - 2 ft	180-100148-4	Excavated	< 0.02 U			< 0.12 U	3.6	0.094	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	1.2	< 0.11 U	< 0.12 U	< 0.02 U	0.28
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated															
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-0.17-2	12/16/2019	855.94	0.17 - 2 ft	180-100148-2	Excavated	< 0.02 U			< 0.13 U	0.37	0.02 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.14	< 0.12 U	< 0.12 U	< 0.02 U	0.21
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-0.17-2	12/17/2019	856.00	0.17 - 2 ft	180-100148-6	Excavated	< 0.042 U			< 0.26 U	0.25	< 0.033 U	< 0.06 U	< 0.049 U	< 0.086 U	< 0.043 U	0.13 J	< 0.24 U	< 0.25 U	< 0.043 U	< 0.04 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-0.17-2	12/17/2019	855.68	0.17 - 2 ft	180-100148-4	Excavated	< 0.02 U			< 0.13 U	0.26	0.061 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.22 J-	< 0.12 U	< 0.12 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-0.17-2	12/17/2019	856.31	0.17 - 2 ft	180-100148-4	Excavated	< 0.02 U			< 0.13 U	0.18	0.016 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.16	< 0.12 U	< 0.12 U	< 0.021 U	0.16
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	856.64	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-0.17-2	12/16/2019	856.96	0.17 - 2 ft	180-100148-2	Excavated															
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-0.17-2	12/16/2019	856.94	0.17 - 2 ft	180-100148-2	Excavated	< 0.021 U			< 0.13 U	0.51	0.025 J	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	0.33	< 0.12 U	< 0.12 U	< 0.021 U	0.12
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-0.17-2	12/17/2019	856.43	0.17 - 2 ft	180-100148-6	Excavated	< 0.019 U			< 0.12 U	0.3	0.019 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.17	< 0.11 U	< 0.11 U	< 0.02 U	0.082
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	856.17	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	856.62	0.17 - 2 ft	180-100148-2	Excavated															
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-0.17-2	12/16/2019	856.86	0.17 - 2 ft	180-100148-8	Excavated															
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-0.17-2	12/16/2019	856.76	0.17 - 2 ft	180-100148-3	Excavated															
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	855.76	0.17 - 2 ft	180-100148-2	Excavated															
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	856.21	0.17 - 2 ft	180-100148-3	Excavated															
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-0.17-2	1/28/2021	856.22	0.17 - 2 ft	180-116609-1	Excavated															
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	856.48	0.17 - 2 ft	180-100148-3	Excavated															
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	855.88	0.17 - 2 ft	180-100148-3	Excavated															
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-0.17-2	12/16/2019	853.99	0.17 - 2 ft	180-100148-1	Excavated	< 0.019 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-0.17-2	12/16/2019	854.39	0.17 - 2 ft	180-100148-1	Excavated	< 0.02 U			< 0.12 U	1.4	0.13	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.59	< 0.11 U	< 0.12 U	< 0.02 U	0.55
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-0.17-2	12/16/2019	853.34	0.17 - 2 ft	180-100148-1	Excavated	< 0.018 U			< 0.12 U	0.025 J	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-0.17-2	12/16/2019	854.14	0.17 - 2 ft	180-100148-1	Excavated	< 0.021 U			< 0.13 U	0.52	0.027 J	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	0.4	< 0.12 U	< 0.12 U	< 0.021 U	0.14
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-0.17-2	12/16/2019	852.74	0.17 - 2 ft	180-100148-1	Excavated	< 0.019 U			< 0.12 U	0.15	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.11	< 0.11 U	< 0.11 U	< 0.02 U	0.027 J
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-0.17-2	12/16/2019	851.73	0.17 - 2 ft	180-100148-1	Excavated	< 0.02 U			< 0.13 U	0.11	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.081 J	< 0.12 U	< 0.12 U	< 0.021 U	0.022 J
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-0.17-2	12/16/2019	852.38	0.17 - 2 ft	180-100148-1	Excavated	< 0.02 U			< 0.13 U	0.8	0.018 J	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.42	< 0.12 U	< 0.12 U	< 0.021 U	0.049 J
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-0.17-2	12/16/2019	853.06	0.17 - 2 ft	180-100148-1	Excavated	< 0.02 U			< 0.12 U	0.056 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.069 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-0.17-2	12/16/2019	853.75	0.17 - 2 ft	180-100148-1	Excavated	< 0.019 U			< 0.12 U	0.035 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.027 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3334	SSHS-B3334-SUB-0.17-2	12/17/2019	853.15	0.17 - 2 ft	180-100148-6	Excavated															
Northern Athletic Field	SSHS-B3335	SSHS-B3335-SUB-0.17-2	12/17/2019	853.90	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3336	SSHS-B3336-SUB-0.17-2	12/17/2019	854.13	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3337	SSHS-B3337-SUB-0.17-2	12/17/2019	854.69	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3338	SSHS-B3338-SUB-0.17-2	12/17/2019	855.11	0.17 - 2 ft	180-100148-4	Excavated															
Northern Athletic Field	SSHS-B3340	SSHS-B3340-SUB-0.17-2	12/17/2019	853.87	0.17 - 2 ft	180-100148-6	Excavated															
Northern Athletic Field	SSHS-B3341	SSHS-B3341-SUB-0.17-2	12/17/2019	853.57	0.17 - 2 ft	180-100148-6	Excavated															
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-0.17-2	12/17/2019	853.63	0.17 - 2 ft	180-100148-5	Excavated	< 0.019 U			< 0.12 U	1.7	0.038 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.83	< 0.11 U	< 0.11 U	< 0.02 U	0.11
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	< 0.058 U			< 0.12 U	0.028 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	< 0.062 U			< 0.13 U	0.63	0.048 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.28	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated	< 0.056 U			< 0.12 U	0.7 J	0.042 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.33	< 0.11 U	< 0.11 U	< 0.019 U	0.028 J
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	< 0.12 U			< 0.24 U	6	0.68	< 0.055 U	< 0.045 U	< 0.078 U	< 0.04 U	1.9	< 0.22 U	< 0.22 U	< 0.039 U	0.18
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	< 0.27 U			< 0.56 U	0.73	< 0.07 U	< 0.13 U	< 0.1 U	< 0.18 U	< 0.092 U	0.22 J	< 0.51 U	< 0.52 U	< 0.091 U	< 0.085 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	< 0.061 U			< 0.13 U	0.25 J	< 0.016 UJ	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.15 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	< 0.28 U			< 0.58 U	1.5 J	0.12 J	< 0.13 U	< 0.11 U	< 0.19 U	< 0.096 U	0.91 J	< 0.53 U	< 0.55 U	< 0.095 U	< 0.089 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.055 U			< 0.11 U	0.85	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.44	< 0.1 U	< 0.11 U	< 0.019 U	0.068 J
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.11 U			< 0.22 U	0.33	< 0.028 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U	0.18	< 0.21 U	< 0.21 U	< 0.037 U	< 0.035 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated	< 0.053 U			< 0.11 U	0.072 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.093 J	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated	< 0.053 U			< 0.11 U	0.072 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.093 J	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0.17-2	7/28/2020	858.45	0.17 - 2 ft	180-108872-1	Excavated	< 0.28 U			< 0.57 U	19	1.3	< 0.13 U	< 0.11 U	< 0.19 U	< 0.095 U	4.8	< 0.53 U	< 0.54 U	< 0.094 U	0.46
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0.17-2	7/28/2020	858.43	0.17 - 2 ft	180-108872-1	Excavated	< 0.53 U			< 1.1 U	15	0.55 J	< 0.25 U	< 0.21 U	< 0.36 U	< 0.18 U	5.4	< 1 U	< 1 U	< 0.18 U	0.48 J
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0.17-2	7/28/2020	858.58	0.17 - 2 ft	180-108872-1	Excavated	< 0.056 U			< 0.12 U	0.76	0.031 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.3	< 0.11 U	< 0.11 U	< 0.019 U	0.024 J
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0.17-2	7/28/2020	856.51	0.17 - 2 ft	180-108872-1	Excavated	< 0.063 U			< 0.13 U	0.31	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.19	< 0.12 U	< 0.12 U	< 0.021 U	0.07 J

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-0.17-2	12/17/2019	856.21	0.17 - 2 ft	180-100148-5	Excavated		0.48	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.65 U	0.69	< 0.12 U	1.3		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-0.17-2	12/17/2019	856.34	0.17 - 2 ft	180-100148-5	Excavated		11	< 2 U	< 1.1 U	< 0.21 U	< 1.6 U	< 0.68 U	< 3 U		< 0.29 U	< 1.4 U	< 6.9 U	91	< 1.3 U	93		< 0.18 U	< 1.8 U	< 0.31 U	< 0.23 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-0.17-2	12/17/2019	856.90	0.17 - 2 ft	180-100148-6	Excavated		0.06 J	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.13	< 0.12 U	0.55		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-0.17-2	12/17/2019	857.22	0.17 - 2 ft	180-100148-6	Excavated		0.89	< 0.52 U	< 0.29 U	< 0.056 U	< 0.42 U	< 0.18 U	< 0.81 U		< 0.078 U	< 0.38 U	< 1.8 U	1.3	< 0.35 U	4		< 0.05 U	< 0.48 U	< 0.082 U	< 0.063 U
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-0.17-2	12/17/2019	857.35	0.17 - 2 ft	180-100148-5	Excavated		0.18	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.2	< 0.12 U	0.46		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-0.17-2	12/17/2019	857.15	0.17 - 2 ft	180-100148-5	Excavated		0.49	< 0.35 U	< 0.2 UJ	< 0.037 U	< 0.28 U	< 0.12 U	< 0.54 U		< 0.052 U	< 0.26 U	< 1.2 U	0.72	< 0.23 U	1.5		< 0.033 U	< 0.32 U	< 0.055 U	< 0.042 U
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-0.17-2	12/17/2019	856.87	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-0.17-2	12/17/2019	855.96	0.17 - 2 ft	180-100148-4	Excavated		1.3	< 0.95 U	< 0.53 UJ	< 0.1 U	< 0.77 U	< 0.33 U	< 1.5 U		< 0.14 U	< 0.7 U	< 3.4 U	9.5	< 0.63 U	14		< 0.09 U	< 0.87 U	< 0.15 U	< 0.11 U
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-0.17-2	12/16/2019	856.22	0.17 - 2 ft	180-100148-2	Excavated		0.27 J	< 0.71 U	< 0.4 U	< 0.076 U	< 0.57 U	< 0.25 U	< 1.1 U		< 0.11 U	< 0.52 U	< 2.5 U	0.99	< 0.47 U	2.4		< 0.068 U	< 0.65 U	< 0.11 U	< 0.086 U
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-0.17-2	12/17/2019	857.02	0.17 - 2 ft	180-100148-5	Excavated		0.56	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.33	< 0.13 U	0.52		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-0.17-2	12/17/2019	857.20	0.17 - 2 ft	180-100148-5	Excavated		1.5	< 0.18 U	< 0.1 UJ	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	1.8	0.22 J	1.8		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-0.17-2	12/17/2019	857.10	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-0.17-2	12/17/2019	856.38	0.17 - 2 ft	180-100148-3	Excavated		0.15	< 0.18 U	< 0.1 UJ	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	1.2	< 0.12 U	1.7		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-0.17-2	12/16/2019	856.13	0.17 - 2 ft	180-100148-2	Excavated		0.15 J	< 0.37 U	< 0.21 U	< 0.04 U	< 0.3 U	< 0.13 U	< 0.57 U		< 0.056 U	< 0.27 U	< 1.3 U	0.83	< 0.25 U	1.6		< 0.035 U	< 0.34 U	< 0.058 U	< 0.045 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-0.17-2	12/17/2019	856.19	0.17 - 2 ft	180-100148-5	Excavated		0.69	< 0.19 U	< 0.11 UJ	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.43	< 0.13 U	0.41		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-0.17-2	12/17/2019	856.73	0.17 - 2 ft	180-100148-5	Excavated		0.32	< 0.18 U	< 0.1 UJ	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.42	< 0.12 U	0.52		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-0.17-2	12/17/2019	856.97	0.17 - 2 ft	180-100148-4	Excavated		0.88	< 0.18 U	< 0.1 UJ	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	2	< 0.12 U	3		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-0.17-2	12/17/2019	857.04	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-0.17-2	12/16/2019	855.94	0.17 - 2 ft	180-100148-2	Excavated		0.73	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.32	< 0.12 U	0.34		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-0.17-2	12/17/2019	856.00	0.17 - 2 ft	180-100148-6	Excavated		0.087 J	< 0.38 U	< 0.21 U	< 0.041 U	< 0.31 U	< 0.13 U	< 0.59 U		< 0.057 U	< 0.28 U	< 1.4 U	0.13 J	< 0.26 U	0.23		< 0.036 U	< 0.35 U	< 0.06 U	< 0.046 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-0.17-2	12/17/2019	855.68	0.17 - 2 ft	180-100148-4	Excavated		0.3	< 0.18 U	< 0.1 UJ	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.32	< 0.12 U	0.5		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-0.17-2	12/17/2019	856.31	0.17 - 2 ft	180-100148-4	Excavated		0.35	< 0.19 U	< 0.1 UJ	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.14	< 0.12 U	0.17		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-0.17-2	12/17/2019	856.64	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-0.17-2	12/16/2019	856.96	0.17 - 2 ft	180-100148-2	Excavated																				
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-0.17-2	12/16/2019	856.94	0.17 - 2 ft	180-100148-2	Excavated		0.36	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.3	< 0.13 U	0.51		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-0.17-2	12/17/2019	856.43	0.17 - 2 ft	180-100148-6	Excavated		0.19	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.18	< 0.12 U	0.32		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-0.17-2	12/17/2019	856.17	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-0.17-2	12/16/2019	856.62	0.17 - 2 ft	180-100148-2	Excavated																				
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-0.17-2	12/16/2019	856.86	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-0.17-2	12/16/2019	856.76	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-0.17-2	12/16/2019	855.76	0.17 - 2 ft	180-100148-2	Excavated																				
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-0.17-2	12/16/2019	856.21	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-0.17-2	1/28/2021	856.22	0.17 - 2 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-0.17-2	12/16/2019	856.48	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-0.17-2	12/16/2019	855.88	0.17 - 2 ft	180-100148-3	Excavated																				
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-0.17-2	12/16/2019	853.99	0.17 - 2 ft	180-100148-1	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-0.17-2	12/16/2019	854.39	0.17 - 2 ft	180-100148-1	Excavated		1.6	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	1.4	< 0.12 U	1.1		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-0.17-2	12/16/2019	853.34	0.17 - 2 ft	180-100148-1	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.026 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-0.17-2	12/16/2019	854.14	0.17 - 2 ft	180-100148-1	Excavated		0.47	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.33	< 0.13 U	0.49		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-0.17-2	12/16/2019	852.74	0.17 - 2 ft	180-100148-1	Excavated		0.081	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.065 J	< 0.12 U	0.13		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-0.17-2	12/16/2019	851.73	0.17 - 2 ft	180-100148-1	Excavated		0.031 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.059 J	< 0.12 U	0.11		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-0.17-2	12/16/2019	852.38	0.17 - 2 ft	180-100148-1	Excavated		0.12	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.26	< 0.12 U	0.74		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-0.17-2	12/16/2019	853.06	0.17 - 2 ft	180-100148-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.033 J	< 0.12 U	0.055 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-0.17-2	12/16/2019	853.75	0.17 - 2 ft	180-100148-1	Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.022 J	< 0.12 U	0.034 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3334	SSHS-B3334-SUB-0.17-2	12/17/2019	853.15	0.17 - 2 ft	180-100148-6	Excavated																				
Northern Athletic Field	SSHS-B3335	SSHS-B3335-SUB-0.17-2	12/17/2019	853.90	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3336	SSHS-B3336-SUB-0.17-2	12/17/2019	854.13	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3337	SSHS-B3337-SUB-0.17-2	12/17/2019	854.69	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3338	SSHS-B3338-SUB-0.17-2	12/17/2019	855.11	0.17 - 2 ft	180-100148-4	Excavated																				
Northern Athletic Field	SSHS-B3340	SSHS-B3340-SUB-0.17-2	12/17/2019	853.87	0.17 - 2 ft	180-100148-6	Excavated																				
Northern Athletic Field	SSHS-B3341	SSHS-B3341-SUB-0.17-2	12/17/2019	853.57	0.17 - 2 ft	180-100148-6	Excavated																				
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-0.17-2	12/17/2019	853.63	0.17 - 2 ft	180-100148-5	Excavated		0.5	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.52	< 0.12 U	1.6		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated		< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.033 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated		0.023 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.27	< 0.12 U	0.69		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3463	SSHS-B3463-SUB-0.17-2	7/28/2020	856.64	0.17 - 2 ft	180-108872-3	Excavated		0.052 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.26 J	< 0.11 U	0.75 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated		0.14 J	< 0.35 U	< 0.19 U	< 0.037 U	< 0.28 U	< 0.12 U	< 0.54 U		< 0.052 U	< 0.26 U	< 1.2 U	4.7	< 0.23 U	6.1		< 0.033 U	< 0.32 U	< 0.055 U	< 0.042 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated		< 0.069 U	< 0.81 U	< 0.45 U	< 0.087 U	< 0.65 U	< 0.28 U	< 1.3 U		< 0.12 U	< 0.59 U	< 2.9 U	0.23 J	< 0.54 U	0.65		< 0.077 U	< 0.74 U	< 0.13 U	< 0.098 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated		0.033 J	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.066 J	< 0.12 U	0.32 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated		0.16 J	< 0.85 U	< 0.47 U	< 0.091 U	< 0.68 U	< 0.3 U	< 1.3 U		< 0.13 U	< 0.62 U	< 3 U	0.52 J	< 0.56 U	1.9 J		< 0.08 U	< 0.78 U	< 0.13 U	< 0.1 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated		0.15	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.42	< 0.11 U	0.84		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated		0.034 J	< 0.33 U	< 0.18 U	< 0.035 U	< 0.26 U	< 0.11 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.11 J	< 0.22 U	0.34		< 0.031 U	< 0.3 U	< 0.051 U	< 0.04 U
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated		0.019 J	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.062 J	< 0.11 U	0.079 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3481-SUB-0.17-2	SSHS-B3481-SUB-0.17-2	7/28/2020	858.23	0.17 - 2 ft	180-108872-1	Excavated	< 0.1 U	0.019 J	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.062 J	< 0.11 U	0.079 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3484	SSHS-B3484-SUB-0.17-2	7/28/2020	858.45	0.17 - 2 ft	180-108872-1	Excavated		0.62	< 0.84 U	< 0.47 U	< 0.089 U	< 0.67 U	< 0.29 U	< 1.3 U		< 0.12 U	< 0.61 U	< 3 U	13	< 0.56 U	18		< 0.079 U	< 0.77 U	< 0.13 U	< 0.1 U
Northern Athletic Field	SSHS-B3485	SSHS-B3485-SUB-0.17-2	7/28/2020	858.43	0.17 - 2 ft	180-108872-1	Excavated		0.75	< 1.6 U	< 0.89 U	< 0.17 U	< 1.3 U	< 0.56 U	< 2.5 U		< 0.24 U	< 1.2 U	< 5.6 U	5.5	< 1.1 U	16		< 0.15 U	< 1.5 U	< 0.25 U	< 0.19 U
Northern Athletic Field	SSHS-B3486	SSHS-B3486-SUB-0.17-2	7/28/2020	858.58	0.17 - 2 ft	180-108872-1	Excavated		0.041 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.26	< 0.11 U	0.89		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3487	SSHS-B3487-SUB-0.17-2	7/28/2020	856.51	0.17 - 2 ft	180-108872-1	Excavated		0.05 J	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.16	< 0.13 U	0.33		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0.17-2	7/28/2020	857.00	0.17 - 2 ft	180-108872-1	Excavated			4.763	< 0.025 U	0.21	< 0.023 U	0.15	< 0.19 U	< 0.018 U	< 0.053 U	0.47	0.5	0.52	0.23	0.38	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0.17-2	7/28/2020	856.50	0.17 - 2 ft	180-108872-1	Excavated			5.804	0.021 J	0.44	< 0.019 U	0.23	< 0.15 U	< 0.015 U	< 0.043 U	0.49	0.57	0.74	0.26	0.58	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0.17-2	7/28/2020	858.42	0.17 - 2 ft	180-108872-1	Excavated			124.86	0.45 J	5.5	< 0.2 U	3.3	< 1.6 U	< 0.15 U	< 0.46 U	10	10	13	4.6	8	< 0.18 U	< 0.13 U	< 0.27 U	< 3.9 U	< 0.26 U	< 2.5 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated			1.388	< 0.023 U	0.062 J	< 0.022 U	0.032 J	< 0.17 U	< 0.017 U	< 0.049 U	0.13	0.14	0.16	0.082	0.11	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated			1.255	< 0.024 U	0.04 J	< 0.022 U	0.038 J	< 0.18 U	< 0.017 U	< 0.051 U	0.11	0.12	0.18	0.054 J	0.1	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0.17-2	1/26/2021	858.43	0.17 - 2 ft	180-116462-1	Excavated	53 J	53 J																			
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	120	120	7.703	0.059 J	0.2	< 0.022 U	0.21	< 0.17 U	< 0.017 U	< 0.049 U	0.7	0.64	0.85	0.29	0.52	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated		1000	186.99	0.47	7.8	< 0.11 U	4.9	< 0.88 U	< 0.084 U	< 0.25 U	17	16	21	6.9	15	< 0.096 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0.17-2	1/26/2021	858.39	0.17 - 2 ft	180-116462-1	Excavated	1200	1200	305.86	0.96	12 J	< 0.11 U	8.8 J	< 0.87 U	0.17 J	< 0.25 U	26 J	23 J	27 J	11 J	16 J	< 0.095 U	< 0.072 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-1	Excavated	110	110	4.795	< 0.025 U	0.13	< 0.023 U	0.11	< 0.19 U	< 0.018 U	< 0.053 U	0.45	0.42	0.6	0.16	0.33	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3503A	SSHS-B3503-SUB-0.17-2	1/21/2021	854.30	0.17 - 2 ft	180-116310-1	Excavated			3.416	< 0.07 U	0.22 J	< 0.066 U	0.096 J	< 0.53 U	< 0.051 U		0.29	0.34	0.45	0.16 J	0.35	< 0.058 U	< 0.044 U	< 0.09 U	< 1.3 U	< 0.085 U	< 0.83 U
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-0.17-2	1/23/2021	853.98	0.17 - 2 ft	180-116404-1	Excavated			6.246	< 0.023 U	0.29	< 0.022 U	0.18	< 0.18 U	0.032 J	< 0.051 U	0.45	0.57	0.61	0.3	0.66	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-0.17-2	1/23/2021	853.31	0.17 - 2 ft	180-116404-1	Excavated			5.233	< 0.022 U	0.17	< 0.021 U	0.13	< 0.17 U	0.021 J	< 0.048 U	0.43	0.51	0.63	0.17	0.46	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-0.17-2	1/26/2021	857.28	0.17 - 2 ft	180-116462-1	Excavated			3.003	< 0.022 U	0.13	< 0.021 U	0.096	< 0.17 U	< 0.016 U	< 0.048 U	0.26	0.27	0.32	0.14	0.23	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3508A	SSHS-B3508-SUB-0.17-2	1/13/2021	856.03	0.17 - 2 ft	180-115927-1	Excavated			0.24	< 0.11 U	< 0.083 U	< 0.1 U	< 0.098 U	< 0.83 U	< 0.079 U	< 0.23 U	< 0.17 U	< 0.16 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.09 U	< 0.069 U	< 0.14 U	< 2 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3509A	SSHS-B3509-SUB-0.17-2	1/13/2021	855.93	0.17 - 2 ft	180-115927-1	Excavated			2.835	< 0.022 U	0.071 J	< 0.021 U	0.067 J	< 0.17 U	< 0.016 U	< 0.048 U	0.27	0.28	0.33	0.099	0.22	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3510A	SSHS-B3510-SUB-0.17-2	1/13/2021	856.73	0.17 - 2 ft	180-115927-1	Excavated			1.515	< 0.022 U	< 0.017 U	< 0.021 U	0.029 J	< 0.17 U	< 0.016 U	< 0.047 U	0.11	0.055 J	0.1	0.038 J	0.065 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-0.17-2	1/27/2021	858.50	0.17 - 2 ft	180-116529-1	Excavated	48 J	48 J																			
Northern Athletic Field	SSHS-B3594	DUP-13	1/26/2021	858.38	0.17 - 2 ft	1801164621	Excavated			0.986	< 0.024 U	0.045 J	< 0.022 U	0.023 J	< 0.18 U	< 0.017 U	< 0.051 U	0.096	0.094	0.13	0.042 J	0.079 J	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated			1.254	< 0.024 U	0.078 J	< 0.022 U	0.035 J	< 0.18 U	< 0.017 U	< 0.051 U	0.12	0.12	0.15	0.062 J	0.092	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/1/2021	856.70	0.17 - 2 ft	180-116686-1	Excavated			4.962	0.043 J	0.1	< 0.02 U	0.12	< 0.16 U	< 0.016 U	< 0.046 U	0.4	0.39	0.48	0.12	0.36	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36_0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated			ND	< 0.35 U	< 0.35 U		< 0.35 U				< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-0.17-2	1/25/2021	856.82	0.17 - 2 ft	180-116404-1	Excavated			1.32	< 0.022 U	0.067 J	< 0.021 U	0.036 J	< 0.17 U	< 0.016 U	< 0.048 U	0.13	0.14	0.18	0.07 J	0.12	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-0.17-2	1/25/2021	857.48	0.17 - 2 ft	180-116404-1	Excavated			6.256	< 0.023 U	0.3	< 0.021 U	0.14	< 0.17 U	< 0.016 U	< 0.049 U	0.55	0.59	0.86	0.35	0.59	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-0.17-2	1/25/2021	857.88	0.17 - 2 ft	180-116404-1	Excavated			2.052	< 0.022 U	0.093	< 0.021 U	0.042 J	< 0.17 U	< 0.016 U		0.18	0.2	0.28	0.11	0.15	< 0.019 U	< 0.014 UJ	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-0.17-2	1/25/2021	858.03	0.17 - 2 ft	180-116404-1	Excavated			1.235	< 0.023 U	0.06 J	< 0.022 U	0.033 J	< 0.17 U	< 0.017 U	< 0.049 U	0.12	0.11	0.17	0.072 J	0.11	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-0.17-2	1/25/2021	856.26	0.17 - 2 ft	180-116404-1	Excavated			82.4	0.19 J	2.8	< 0.1 U	1.8	< 0.83 U	< 0.08 U	< 0.24 U	7.8	6.5	8.2	2.6	4.2	< 0.09 U	< 0.069 U	< 0.14 U	< 2 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-0.17-2	1/23/2021	855.69	0.17 - 2 ft	180-116404-1	Excavated			2.969	0.039 J	0.065 J	< 0.022 U	< 0.021 UJ	< 0.18 U	0.038 J	< 0.051 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	0.17 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-0.17-2	1/27/2021	855.81	0.17 - 2 ft	180-116529-1	Excavated			1.723	< 0.022 U	0.12	< 0.021 U	0.056 J	< 0.17 U	0.021 J	< 0.048 U	0.11	0.15	0.18	0.074 J	0.22	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-0.17-2	2/1/2021	856.45	0.17 - 2 ft	180-116686-1	Excavated			6.12	< 0.046 U	0.54 J	< 0.043 U	0.17 J	< 0.35 U	0.052 J	< 0.099 U	0.42 J	0.54 J	0.69 J	0.24 J	0.76 J	< 0.038 U	< 0.029 U	< 0.059 U	< 0.84 U	< 0.055 U	< 0.55 U
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-0.17-2	1/23/2021	857.05	0.17 - 2 ft	180-116404-1	Excavated			10.628	0.027 J	0.82	0.023 J	0.42	< 0.15 U	0.028 J	< 0.043 U	0.91	1	1.4	0.5	1	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-0.17-2	1/27/2021	856.65	0.17 - 2 ft	180-116529-1	Excavated			3.41	< 0.022 U	0.12	< 0.021 U	0.11	< 0.17 U	< 0.016 U	< 0.048 U	0.28	0.3	0.3	0.13	0.3	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-0.17-2	2/2/2021	856.10	0.17 - 2 ft	180-116723-1	Excavated			1.52	< 0.023 U	0.08	< 0.021 U	0.041 J	< 0.17 U	0.026 J	< 0.049 U	0.096	0.11	0.12	0.067 J	0.21	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-0.17-2	1/27/2021	856.99	0.17 - 2 ft	180-116529-1	Excavated			11.665	< 0.022 U	0.43	< 0.021 U	0.29	< 0.17 U	0.034 J	< 0.047 U	1	1.1	1.3	0.56	1.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated			0.133	< 0.02 U	0.017 J	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.032 U	< 0.03 U	0.03 J	< 0.021 U	0.031 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-0.17-2	1/27/2021	855.11	0.17 - 2 ft	180-116529-1	Excavated	420	420																			
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-0.17-2	1/27/2021	854.67	0.17 - 2 ft	180-116529-1	Excavated	53 J	53 J																			
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-0.17-2	1/28/2021	856.29	0.17 - 2 ft	180-116609-1	Excavated	1200	1200																			
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-0.17-2	1/28/2021	856.63	0.17 - 2 ft	180-116609-1	Excavated	130	130																			
Northern Athletic Field	SSHS-B37	_12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated			0.045	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated			1.34	< 0.34 U	< 0.34 U		< 0.34 U				< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_ -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated			51	< 1.8 U	< 1.8 U		2.2				4.8	4.2	2.7	3.3	2.3	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated			0.199	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	0.044 J	< 0.021 U	0.029 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_ -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated			ND	< 0.42 U	< 0.42 U		< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated			5.04	< 1.8 U	0.22 J		< 1.8 U				0.36 J	0.46 J	0.4 J	0.37 J	0.62 J	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated			6.465	< 0.022 U	0.17	< 0.021 U	0.15	< 0.17 U	< 0.016 U	< 0.048 U	0.61	0.47	0.82	0.28	0.54	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated			5.565	< 0.022 U	0.14	< 0.021 U	0.14	< 0.17 U	< 0.016 U	< 0.048 U	0.48	0.55	0.54	0.27	0.45	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated			0.411	< 0.0071	0.039	< 0.03	0.02	< 0.036	< 0.033	< 0.055	0.058	0.07	< 0.012	< 0.015	< 0.0073	< 0.024	< 0.0099	< 0.0079	< 0.059	< 0.032	< 0.05
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated			2.64		0.092 J		0.11 J				0.21 J	0.29 J	0.47	0.18 J	0.23 J				0.53		
Northern Athletic Field	SSHS-B40	_12 Sep 00B40_0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated			ND	< 1.9 U	< 1.9 U		< 1.9 U				< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B40	_12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated			ND	< 0.41 U	< 0.41 U		< 0.41 U				< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	0.17 - 1 ft	180-123985-1	Not Excavated			1.191	< 0.022 U	< 0.017 U	< 0.021 U	0.021 J	< 0.17 U	< 0.016 U	< 0.047 U	0.096	0.11	0.15	0.064 J	0.078	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	856.80	1 - 2 ft	180-123985-1	Not Excavated			5.147	< 0.021 U	0.33	< 0.02 U	0.13	< 0.16 U	< 0.016 U	< 0.046 U	0.41	0.53	0.75	0.22	0.53	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated			1.021	< 0.023 U	< 0.017 U	< 0.021 U	0.023 J	< 0.17 U	< 0.017 U	< 0.049 U	0.1	0.11	0.091	0.073 J	0.082	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated			3.62	< 0.022 U	0.17	< 0.02 U	0.1	< 0.17 U	< 0.016 U	< 0.047 U	0.3	0.39	0.51	0.18	0.34	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated			2.639	< 0.022 U	0.14	< 0.021 U	0.066 J	< 0.17 U	< 0.016 U	< 0.048 U	0.2	0.26	0.36	0.11	0.24	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated			10.295	< 0.022 U	0.61	< 0.02 U	0.31	< 0.16 U	< 0.016 U	< 0.047 U	0.8	1.1	1.4	0.33	1.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated			9.04	< 0.034 U	0.19 J	< 0.034 U	0.21 J	< 0.36 U	< 0.034 U	< 0.55 U	0.81	0.78	0.98	0.43 J	0.7 J	< 0.24 U	< 0.099 U	< 0.08 U	< 0.6 U	< 0.32 U	< 0.034 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated			ND	< 0.067	< 0.08	< 0.29	< 0.068	< 0.34	< 0.31	< 0.52	< 0.088	< 0.07	< 0.11	< 0.14	< 0.07	< 0.23	< 0.094	< 0.075	< 0.57	< 0.3	< 0.48
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	0.17 - 1 ft	180-57995-1	Not Excavated			100.877	0.087 J	1.6	< 0.034 U	3.1	< 0.071 U	< 0.034 U	< 0.11 U	9.3	8.1	9.9	3.5	6.1	< 0.048 U	< 0.02 U	< 0.016 U	< 0.12 U	< 0.064 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	1 - 2 ft	180-57995-1	Not Excavated			7.668	< 0.034 U	0.11	< 0.034 U	0.24	< 0.034 U	< 0.034 U	< 0.052 U	0.66	0.61	0.77	0.21	0.47	< 0.023 U	< 0.0093 U	< 0.0075 U	< 0.056 U	< 0.03 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	0.17 - 1 ft	180-57995-1	Not Excavated			2.622	< 0.034 U	0.13	< 0.034 U	0.069 J	< 0.038 U	< 0.034 U	< 0.058 U	0.23	0.27	0.34	0.097	0.26	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	1 - 2 ft	180-57995-1	Not Excavated			3.154	0.029 J	0.065 J	< 0.034 U	0.1	< 0.036 U	< 0.034 U	< 0.055 U	0.26	0.25	0.3	0.13	0.23	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated			ND	< 0.39	< 0.39		< 0.39				< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated			ND	< 0.37	< 0.37		< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0.17-2	7/28/2020	857.00	0.17 - 2 ft	180-108872-1	Excavated	< 0.28 U	0.023 J	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.48	0.099	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U	< 2.4 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0.17-2	7/28/2020	856.50	0.17 - 2 ft	180-108872-1	Excavated	< 0.23 U	0.045 J	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.57	0.15	0.023 J	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0.17-2	7/28/2020	858.42	0.17 - 2 ft	180-108872-1	Excavated	< 2.4 U	0.89	< 0.25 U	< 0.17 U	< 0.17 U	< 0.17 U	< 0.22 U	13	2.2	0.44 J	< 3.4 U	< 0.28 U	< 1.3 U	< 0.23 U	< 0.27 U	< 1.6 U	< 2.1 U	< 6.3 U	< 0.23 U	< 20 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.16	< 0.051 U	< 0.017 U	< 0.37 U	< 0.031 U	0.17 J	< 0.025 U	< 0.03 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.2 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.13	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0.17-2	1/26/2021	858.43	0.17 - 2 ft	180-116462-1	Excavated																				
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	< 0.26 U	0.075 J	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.73	0.16	0.031 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 1.3 U	1	< 0.14 U	< 0.095 U	< 0.092 U	< 0.093 U	< 0.12 U	17	3.8	0.41 J	< 1.9 U	< 0.16 U	< 0.71 U	< 0.12 U	< 0.15 U	< 0.88 U	< 1.2 U	< 3.5 U	< 0.12 U	< 11 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0.17-2	1/26/2021	858.39	0.17 - 2 ft	180-116462-1	Excavated	< 1.3 U	2.1 J	< 0.14 UJ	< 0.094 U	< 0.092 U	< 0.093 U	< 0.12 U	29 J	4.2 J	0.8 J	< 1.9 UJ	< 0.15 U	< 0.7 U	< 0.12 UJ	< 0.15 U	< 0.87 U	< 1.2 U	< 3.4 U	< 0.12 U	
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-1	Excavated	< 0.28 U	0.038 J	< 0.029 UJ	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.45	0.085 J	< 0.019 U	< 0.4 U	< 0.033 U	0.15 J	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U	< 2.4 U
Northern Athletic Field	SSHS-B3503A	SSHS-B3503-SUB-0.17-2	1/21/2021	854.30	0.17 - 2 ft	180-116310-1	Excavated	< 0.79 U	< 0.057 U	< 0.082 U	< 0.057 U	< 0.056 U	< 0.056 U	< 0.073 U	0.34	< 0.16 U	< 0.053 U	< 1.1 UJ	< 0.093 U	< 0.43 U	< 0.075 U	< 0.09 U	< 0.53 U	< 0.7 U	< 2.1 U	< 0.075 U	
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-0.17-2	1/23/2021	853.98	0.17 - 2 ft	180-116404-1	Excavated	< 0.26 U	0.055 J	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.43	0.12	0.08 J	< 0.38 U	< 0.031 U	< 0.14 U	0.094 J	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 2.3 U
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-0.17-2	1/23/2021	853.31	0.17 - 2 ft	180-116404-1	Excavated	< 0.25 U	0.033 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.4	0.087	0.043 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-0.17-2	1/26/2021	857.28	0.17 - 2 ft	180-116462-1	Excavated	< 0.25 U	0.023 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.25	0.061 J	0.024 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3508A	SSHS-B3508-SUB-0.17-2	1/13/2021	856.03	0.17 - 2 ft	180-115927-1	Excavated	< 1.2 U	< 0.088 U	< 0.13 U	< 0.089 U	< 0.087 U	< 0.088 U	< 0.11 U	< 0.21 U	< 0.24 U	< 0.083 U	< 1.8 U	< 0.15 U	0.67 J	< 0.12 U	< 0.14 U	< 0.83 U	< 1.1 U	< 3.3 U	< 0.12 U	< 10 U
Northern Athletic Field	SSHS-B3509A	SSHS-B3509-SUB-0.17-2	1/13/2021	855.93	0.17 - 2 ft	180-115927-1	Excavated	< 0.25 U	< 0.018 U	< 0.026 UJ	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.26	0.058 J	0.02 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 UJ
Northern Athletic Field	SSHS-B3510A	SSHS-B3510-SUB-0.17-2	1/13/2021	856.73	0.17 - 2 ft	180-115927-1	Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.13	< 0.049 U	0.038 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-0.17-2	1/27/2021	858.50	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3594	DUP-13	1/26/2021	858.38	0.17 - 2 ft	1801164621	Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.12	< 0.052 U	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 2.3 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.14	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	0.14 J	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 2.3 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/1/2021	856.70	0.17 - 2 ft	180-116686-1	Excavated	< 0.24 U	0.054 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.44	0.076	0.034 J	< 0.35 U	< 0.029 U	0.18 J	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36_0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 1.8 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-0.17-2	1/25/2021	856.82	0.17 - 2 ft	180-116404-1	Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.13	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-0.17-2	1/25/2021	857.48	0.17 - 2 ft	180-116404-1	Excavated	< 0.25 U	0.024 J	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.63	0.2	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-0.17-2	1/25/2021	857.88	0.17 - 2 ft	180-116404-1	Excavated	< 0.25 UJ	< 0.018 U	< 0.027 UJ	< 0.018 UJ	< 0.018 U	< 0.018 U	< 0.024 U	0.22	< 0.05 U	< 0.017 U	< 0.36 UJ	< 0.03 U	< 0.14 U	< 0.024 UJ	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-0.17-2	1/25/2021	858.03	0.17 - 2 ft	180-116404-1	Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.15	< 0.051 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.2 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-0.17-2	1/25/2021	856.26	0.17 - 2 ft	180-116404-1	Excavated	< 1.2 U	0.27 J	< 0.13 U	< 0.089 U	< 0.087 U	< 0.088 U	< 0.11 U	8.2	1.1	0.15 J	< 1.8 U	< 0.15 U	< 0.66 U	< 0.12 U	< 0.14 U	< 0.83 U	< 1.1 U	< 3.3 U	< 0.12 U	< 11 U
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-0.17-2	1/23/2021	855.69	0.17 - 2 ft	180-116404-1	Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	0.072 J	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 UJ	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 2.3 U
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-0.17-2	1/27/2021	855.81	0.17 - 2 ft	180-116529-1	Excavated	< 0.25 U	0.021 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.13	< 0.049 U	0.025 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-0.17-2	2/1/2021	856.45	0.17 - 2 ft	180-116686-1	Excavated	< 0.52 U	0.078 J	< 0.054 U	< 0.037 U	< 0.036 U	< 0.037 U	< 0.048 U	0.46 J	0.13 J	0.095 J	< 0.74 U	< 0.061 U	< 0.28 U	< 0.049 U	< 0.059 U	< 0.35 U	< 0.46 U	< 1.4 U	< 0.049 U	< 4.4 U
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-0.17-2	1/23/2021	857.05	0.17 - 2 ft	180-116404-1	Excavated	< 0.23 U	0.07	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	1	0.25	0.055 J	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-0.17-2	1/27/2021	856.65	0.17 - 2 ft	180-116529-1	Excavated	< 0.25 U	0.027 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.26	< 0.05 U	0.026 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-0.17-2	2/2/2021	856.10	0.17 - 2 ft	180-116723-1	Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.12	< 0.05 U	0.037 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-0.17-2	1/27/2021	856.99	0.17 - 2 ft	180-116529-1	Excavated	< 0.25 U	0.07 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.98	0.24	0.078 J	< 0.35 U	< 0.029 U	0.13 J	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	0.12 J	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-0.17-2	1/27/2021	855.11	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-0.17-2	1/27/2021	854.67	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-0.17-2	1/28/2021	856.29	0.17 - 2 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-0.17-2	1/28/2021	856.63	0.17 - 2 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B37	_12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 1.8 U	< 0.34 U	< 1.8 U
Northern Athletic Field	SSHS-B38	_12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 2 U
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated		< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	4	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 9.5 U	< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B39	_12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated		< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.1 U	< 0.42 U	< 2.1 U
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated		< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	0.39 J	0.19 J	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 9.2 U	< 1.8 U	< 9.2 U
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.25 U	0.035 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.58	0.15	0.035 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.25 U	0.04 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.39	0.095	0.021 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	< 0.28	< 0.0068	< 0.029	< 0.034	< 0.0077	< 0.03	< 0.041	0.06	< 0.0082	< 0.036	< 0.039	< 0.0074	0.041	< 0.057	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated								0.25 J												
Northern Athletic Field	SSHS-B40	_12 Sep 00B40_0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated		< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 9.5 U	< 1.9 U	< 9.5 U
Northern Athletic Field	SSHS-B40	_12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated		< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 2.1 U	< 0.41 U	< 2.1 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 UJ	< 0.018 U	< 0.018 U	< 0.023 U	0.12	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	856.80	1 - 2 ft	180-123985-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 UJ	< 0.017 U	< 0.017 U	< 0.022 U	0.47	0.14	0.031 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.096	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.25 U	0.022 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.37	0.091	0.017 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated	< 0.25 U	0.022 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.26	0.063 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated	< 0.24 U	0.07 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.96	0.29	0.035 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	< 0.034 U	< 0.034 U	< 0.3 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.83	0.15 J	< 0.36 U	< 0.034 U	< 0.074 U	< 0.034 U	< 0.58 U	< 0.4 U	< 0.034 U	< 0.39 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated	< 2.6	< 0.064	< 0.28	< 0.32	< 0.073	< 0.29	< 0.39	< 0.083	< 0.078	< 0.34	< 0.37	< 0.07	< 0.38	< 0.55	< 0.38	< 0.44	< 0.37	< 1.4	< 0.36	< 4.2
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	0.17 - 1 ft	180-57995-1	Not Excavated	< 0.55 U	1.7	< 0.059 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	7.3	1.4	0.39 J	< 0.034 U	< 0.015 U	< 0.034 U	< 0.11 U	< 0.08 U	< 0.034 U	< 0.077 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	1 - 2 ft	180-57995-1	Not Excavated	< 0.26 U	0.12	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.55	0.12	0.034 J	< 0.034 U	< 0.007 U	< 0.034 U	< 0.054 U	< 0.038 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	0.17 - 1 ft	180-57995-1	Not Excavated	< 0.29 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.22	< 0.034 U	< 0.038 U	< 0.034 U	< 0.0078 U	< 0.034 U	< 0.061 U	< 0.042 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	1 - 2 ft	180-57995-1	Not Excavated	< 0.28 U	0.042 J	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24	< 0.034 U	< 0.036 U	< 0.034 U	< 0.0074 U	< 0.034 U	< 0.058 U	< 0.04 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated		< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 2	< 0.39	< 2
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated		< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 1.9

Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0.17-2	7/28/2020	857.00	0.17 - 2 ft	180-108872-1	Excavated	< 0.065 U			< 0.13 U	0.58	0.034 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.32	< 0.12 U	< 0.13 U	< 0.022 U	0.033 J
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0.17-2	7/28/2020	856.50	0.17 - 2 ft	180-108872-1	Excavated	< 0.052 U			< 0.11 U	0.68	0.038 J	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	0.46	< 0.1 U	< 0.1 U	< 0.018 U	0.069 J
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0.17-2	7/28/2020	858.42	0.17 - 2 ft	180-108872-1	Excavated	< 0.55 U			< 1.1 U	21	0.94	< 0.26 U	< 0.21 U	< 0.38 U	< 0.19 U	6.6	< 1.1 U	< 1.1 U	< 0.19 U	0.68 J
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.06 U			< 0.12 U	0.21	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.082	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.062 U			< 0.13 U	0.16	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.09	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0.17-2	1/26/2021	858.43	0.17 - 2 ft	180-116462-1	Excavated															
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	< 0.06 U			< 0.12 U	1.1	0.063 J	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	0.45	< 0.11 U	< 0.12 U	< 0.02 U	0.032 J
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.3 U	< 0.63 U			28	1	< 0.14 U	< 0.12 U	< 0.21 U	< 0.1 U	12	< 0.58 U		< 0.1 U	0.6
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0.17-2	1/26/2021	858.39	0.17 - 2 ft	180-116462-1	Excavated	< 0.3 U			< 0.62 U	53	2.9 J	< 0.14 U	< 0.12 U	< 0.2 U	< 0.1 U	13 J	< 0.57 U	< 0.59 U	< 0.1 U	0.79
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-1	Excavated	< 0.065 U			< 0.13 U	0.75	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.26	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U
Northern Athletic Field	SSHS-B3503A	SSHS-B3503-SUB-0.17-2	1/21/2021	854.30	0.17 - 2 ft	180-116310-1	Excavated	< 0.18 U			< 0.38 U	0.44	< 0.048 U	< 0.087 U	< 0.071 U	< 0.12 U	< 0.062 U	0.24	< 0.35 U	< 0.36 U	< 0.062 U	0.078 J
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-0.17-2	1/23/2021	853.98	0.17 - 2 ft	180-116404-1	Excavated	< 0.061 U			< 0.13 U	0.79	0.046 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.48	< 0.12 U	0.23 J	< 0.021 U	0.11
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-0.17-2	1/23/2021	853.31	0.17 - 2 ft	180-116404-1	Excavated	< 0.058 U			< 0.12 U	0.78	0.026 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.39	< 0.11 U	< 0.11 U	< 0.02 U	0.082
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-0.17-2	1/26/2021	857.28	0.17 - 2 ft	180-116462-1	Excavated	< 0.058 U			< 0.12 U	0.46	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.18	< 0.11 U	< 0.11 U	< 0.02 U	0.04 J
Northern Athletic Field	SSHS-B3508A	SSHS-B3508-SUB-0.17-2	1/13/2021	856.03	0.17 - 2 ft	180-115927-1	Excavated	< 0.28 U			< 0.59 U	< 0.1 U	< 0.074 U	< 0.14 U	< 0.11 U	< 0.19 U	< 0.097 U	< 0.19 U	< 0.54 U	< 0.55 U	< 0.096 U	< 0.091 U
Northern Athletic Field	SSHS-B3509A	SSHS-B3509-SUB-0.17-2	1/13/2021	855.93	0.17 - 2 ft	180-115927-1	Excavated	< 0.059 U			< 0.12 U	0.42	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.17	< 0.11 U	< 0.11 U	< 0.02 U	0.04 J
Northern Athletic Field	SSHS-B3510A	SSHS-B3510-SUB-0.17-2	1/13/2021	856.73	0.17 - 2 ft	180-115927-1	Excavated	< 0.058 U			< 0.12 U	0.33	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.048 J	< 0.11 U	< 0.11 U	< 0.019 U	0.029 J
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-0.17-2	1/27/2021	858.50	0.17 - 2 ft	180-116529-1	Excavated															
Northern Athletic Field	SSHS-B3594	DUP-13	1/26/2021	858.38	0.17 - 2 ft	1801164621	Excavated	< 0.062 U	< 0.13 U			0.14	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.064 J	< 0.12 U		< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	< 0.062 U	< 0.13 U			0.19	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.08 J	< 0.12 U		< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/1/2021	856.70	0.17 - 2 ft	180-116686-1	Excavated	< 0.056 U			< 0.12 U	0.87	0.063 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.28	< 0.11 U	< 0.11 U	< 0.019 U	0.035 J
Northern Athletic Field	SSHS-B36	_12 Sep 00B36_ -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B36	_12 Sep 00B36_0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.35 U				< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U		< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-0.17-2	1/25/2021	856.82	0.17 - 2 ft	180-116404-1	Excavated	< 0.058 U			< 0.12 U	0.14	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.093	< 0.11 U	< 0.11 U	< 0.02 U	0.038 J
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-0.17-2	1/25/2021	857.48	0.17 - 2 ft	180-116404-1	Excavated	< 0.059 U			< 0.12 U	0.63	0.016 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.5	< 0.11 U	< 0.12 U	< 0.02 U	0.079
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-0.17-2	1/25/2021	857.88	0.17 - 2 ft	180-116404-1	Excavated	< 0.059 U			< 0.12 U	0.25	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.16	< 0.11 UJ	< 0.11 U	< 0.02 U	0.045 J
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-0.17-2	1/25/2021	858.03	0.17 - 2 ft	180-116404-1	Excavated	< 0.06 U			< 0.12 U	0.14	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.099	< 0.11 U	< 0.12 U	< 0.02 U	0.019 J
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-0.17-2	1/25/2021	856.26	0.17 - 2 ft	180-116404-1	Excavated	< 0.29 U			< 0.59 U	15	0.39	< 0.14 U	< 0.11 U	< 0.19 U	< 0.098 U	3.5	< 0.54 U	< 0.56 U	< 0.097 U	0.19 J
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-0.17-2	1/23/2021	855.69	0.17 - 2 ft	180-116404-1	Excavated	< 0.061 U			< 0.13 U	0.46	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.14 J	< 0.12 U	0.12 J	< 0.021 U	0.16
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-0.17-2	1/27/2021	855.81	0.17 - 2 ft	180-116529-1	Excavated	< 0.058 U			< 0.12 U	0.19	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.15	< 0.11 U	< 0.11 U	< 0.02 U	0.06 J
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-0.17-2	2/1/2021	856.45	0.17 - 2 ft	180-116686-1	Excavated	< 0.12 U			< 0.25 U	0.65 J	< 0.031 U	< 0.057 U	< 0.046 U	< 0.081 U	< 0.041 U	0.52 J	< 0.23 U	< 0.23 U	< 0.04 U	0.2 J
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-0.17-2	1/23/2021	857.05	0.17 - 2 ft	180-116404-1	Excavated	< 0.053 U			< 0.11 U	1.2	0.071	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	0.83	< 0.1 U	< 0.1 U	< 0.018 U	0.16
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-0.17-2	1/27/2021	856.65	0.17 - 2 ft	180-116529-1	Excavated	< 0.058 U			< 0.12 U	0.53	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.23	< 0.11 U	< 0.11 U	< 0.02 U	0.049 J
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-0.17-2	2/2/2021	856.10	0.17 - 2 ft	180-116723-1	Excavated	< 0.059 U			< 0.12 U	0.13	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.086	< 0.11 U	< 0.12 U	< 0.02 U	0.094
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-0.17-2	1/27/2021	856.99	0.17 - 2 ft	180-116529-1	Excavated	< 0.057 U			< 0.12 U	1.7	0.045 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.86	< 0.11 U	< 0.11 U	< 0.019 U	0.12
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.053 U	< 0.11 U			0.037 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-0.17-2	1/27/2021	855.11	0.17 - 2 ft	180-116529-1	Excavated															
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-0.17-2	1/27/2021	854.67	0.17 - 2 ft	180-116529-1	Excavated															
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-0.17-2	1/28/2021	856.29	0.17 - 2 ft	180-116609-1	Excavated															
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-0.17-2	1/28/2021	856.63	0.17 - 2 ft	180-116609-1	Excavated															
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_ -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.37 U				0.045 J	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.34 U				0.5	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U		< 0.34 U	< 0.34 U
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_ -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U		< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B38	_12 Sep 00B38_1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	< 1.8 U				11	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	2.4	< 1.8 U		< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.21 U			< 0.11 U	0.057 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_ -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U		< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B39	_12 Sep 00B39_0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	< 1.8 U				0.65 J	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	0.42 J	< 1.8 U		< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.058 U	< 0.12 U			0.91	0.025 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.48	< 0.11 U		< 0.02 U	0.028 J
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.059 U	< 0.12 U			0.97	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.34	< 0.11 U		< 0.02 U	0.024 J
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	< 0.03			< 0.042	0.073	< 0.0097	< 0.0078	< 0.0082	< 0.04	< 0.026	< 0.0076	< 0.026		< 0.028	0.028
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated					0.31 J						0.2 J				
Northern Athletic Field	SSHS-B40	_12 Sep 00B40_0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	< 1.9 U				< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U		< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B40	_12 Sep 00B40_ -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.41 U				< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U		< 0.41 U	< 0.41 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.058 U			< 0.12 U	0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.062 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	856.80	1 - 2 ft	180-123985-1	Not Excavated	< 0.056 U			< 0.12 U	0.6	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.39	< 0.11 U	< 0.11 U	< 0.019 U	0.087
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.059 U	< 0.12 U			0.17	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.066 J	< 0.11 U		< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.057 U	< 0.12 U			0.35	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.28	< 0.11 U		< 0.019 U	0.029 J
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated	< 0.059 U			< 0.12 U	0.35	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.19	< 0.11 U	< 0.11 U	< 0.02 U	0.022 J
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated	< 0.056 U			< 0.12 U	1.2	0.055 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.76	< 0.11 U	< 0.11 U	< 0.019 U	0.08
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated	< 0.3 U			< 0.42 U	1.3	< 0.034 U	< 0.079 U	< 0.034 U	< 0.034 U	< 0.034 U	0.58 J	< 0.034 U	< 0.034 U	< 0.034 U	0.073 J
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated	< 0.28			< 0.4	< 0.075	< 0.092	< 0.074	< 0.078	< 0.38	< 0.25	< 0.072	< 0.24		< 0.26	< 0.063
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	0.17 - 1 ft	180-57995-1	Not Excavated	< 0.059 U			< 0.084 U	20	0.45	< 0.016 U	< 0.034 U	< 0.034 U	< 0.034 U	5.8	< 0.034 U	0.13 J	< 0.034 U	0.18
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	1 - 2 ft	180-57995-1	Not Excavated	< 0.028 U			< 0.04 U	1.6	0.036 J	< 0.0074 U	< 0.034 U	< 0.034 U	< 0.034 U	0.41	< 0.034 U	< 0.034 U	< 0.034 U	0.014 J
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	0.17 - 1 ft	180-57995-1	Not Excavated	< 0.031 U			< 0.044 U	0.38	< 0.034 U	< 0.0083 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U	< 0.034 U	< 0.034 U	0.029 J
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	1 - 2 ft	180-57995-1	Not Excavated	< 0.03 U			< 0.042 U	0.57	0.027 J	< 0.0079 U	< 0.034 U	< 0.034 U	< 0.034 U	0.19	< 0.034 U	< 0.034 U	< 0.034 U	0.037 J
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.39				< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39	< 0.39		< 0.39	< 0.39
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37		< 0.37	< 0.37

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3488	SSHS-B3488-SUB-0.17-2	7/28/2020	857.00	0.17 - 2 ft	180-108872-1	Excavated		0.04 J	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.23	< 0.13 U	0.73		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3489	SSHS-B3489-SUB-0.17-2	7/28/2020	856.50	0.17 - 2 ft	180-108872-1	Excavated		0.075	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.22	< 0.11 U	0.72		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3490	SSHS-B3490-SUB-0.17-2	7/28/2020	858.42	0.17 - 2 ft	180-108872-1	Excavated		0.77	< 1.7 U	< 0.93 U	< 0.18 U	< 1.3 U	< 0.58 U	< 2.6 U		< 0.25 U	< 1.2 U	< 5.9 U	11	< 1.1 U	20		< 0.16 U	< 1.5 U	< 0.26 U	< 0.2 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.062 J	< 0.12 U	0.22		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated		< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.083	< 0.13 U	0.19		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3495	SSHS-B3495-SUB-0.17-2	1/26/2021	858.43	0.17 - 2 ft	180-116462-1	Excavated																				
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated		0.041 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.69	< 0.12 U	1.2		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.59 U	0.92	< 0.92 U	< 0.51 U	< 0.098 U	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	14	< 0.61 U	29		< 0.087 U	< 0.84 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-0.17-2	1/26/2021	858.39	0.17 - 2 ft	180-116462-1	Excavated		1	< 0.91 U	< 0.51 UJ	< 0.097 U	< 0.73 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.66 U	< 3.2 U	35	< 0.61 U	55		< 0.086 U	< 0.83 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-1	Excavated		< 0.017 U	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.34	< 0.13 U	0.84		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3503A	SSHS-B3503-SUB-0.17-2	1/21/2021	854.30	0.17 - 2 ft	180-116310-1	Excavated		< 0.047 U	< 0.55 U	< 0.31 U	< 0.059 U	< 0.44 U	< 0.19 U	< 0.85 U		< 0.082 U	< 0.4 U	< 1.9 U	0.23 J	< 0.37 U	0.48		< 0.052 U	< 0.5 U	< 0.086 U	< 0.066 U
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-0.17-2	1/23/2021	853.98	0.17 - 2 ft	180-116404-1	Excavated		0.45	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.65 U	0.43	< 0.12 U	0.73		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-0.17-2	1/23/2021	853.31	0.17 - 2 ft	180-116404-1	Excavated		0.22	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.3	< 0.12 U	0.7		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-0.17-2	1/26/2021	857.28	0.17 - 2 ft	180-116462-1	Excavated		0.086	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.22	< 0.12 U	0.43		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3508A	SSHS-B3508-SUB-0.17-2	1/13/2021	856.03	0.17 - 2 ft	180-115927-1	Excavated		< 0.074 U	< 0.86 U	< 0.48 U	< 0.092 U	< 0.69 U	< 0.3 U	< 1.3 U		< 0.13 U	< 0.63 U	< 3 U	0.13 J	< 0.57 U	0.11 J		< 0.082 U	< 0.79 U	< 0.13 U	< 0.1 U
Northern Athletic Field	SSHS-B3509A	SSHS-B3509-SUB-0.17-2	1/13/2021	855.93	0.17 - 2 ft	180-115927-1	Excavated		0.091	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.18	< 0.12 U	0.39		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3510A	SSHS-B3510-SUB-0.17-2	1/13/2021	856.73	0.17 - 2 ft	180-115927-1	Excavated		0.11	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.22	< 0.12 U	0.28		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-0.17-2	1/27/2021	858.50	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3594	DUP-13	1/26/2021	858.38	0.17 - 2 ft	1801164621	Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.038 J	< 0.12 U	0.16		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.055 J	< 0.12 U	0.21		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/1/2021	856.70	0.17 - 2 ft	180-116686-1	Excavated		0.07 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.54	< 0.11 U	0.71		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 - 12 Sep 00B36_0.5-2.5	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B36		9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.35 U	< 0.35 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 0.35 U	< 0.35 U				< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-0.17-2	1/25/2021	856.82	0.17 - 2 ft	180-116404-1	Excavated		0.028 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.053 J	< 0.12 U	0.2		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-0.17-2	1/25/2021	857.48	0.17 - 2 ft	180-116404-1	Excavated		0.13	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.18	< 0.12 U	0.89		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-0.17-2	1/25/2021	857.88	0.17 - 2 ft	180-116404-1	Excavated		0.071 J	< 0.18 U	< 0.099 U	< 0.019 UJ	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.079	< 0.12 UJ	0.31		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-0.17-2	1/25/2021	858.03	0.17 - 2 ft	180-116404-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.051 J	< 0.12 U	0.18		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-0.17-2	1/25/2021	856.26	0.17 - 2 ft	180-116404-1	Excavated		0.22 J	< 0.86 U	< 0.48 U	< 0.092 U	< 0.69 U	< 0.3 U	< 1.3 U		< 0.13 U	< 0.63 U	< 3 U	6.7	< 0.57 U	16		< 0.082 U	< 0.79 U	< 0.14 U	< 0.1 U
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-0.17-2	1/23/2021	855.69	0.17 - 2 ft	180-116404-1	Excavated		0.15	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.81	< 0.12 U	1.2		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-0.17-2	1/27/2021	855.81	0.17 - 2 ft	180-116529-1	Excavated		0.19	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.093	< 0.12 U	0.18		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-0.17-2	2/1/2021	856.45	0.17 - 2 ft	180-116686-1	Excavated		0.57 J	< 0.36 U	< 0.2 U	< 0.039 U	< 0.29 U	< 0.13 U	< 0.56 U		< 0.054 U	< 0.26 U	< 1.3 U	0.34 J	< 0.24 U	0.63 J		< 0.034 U	< 0.33 U	< 0.057 U	< 0.044 U
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-0.17-2	1/23/2021	857.05	0.17 - 2 ft	180-116404-1	Excavated		0.19	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.43	< 0.11 U	1.4		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-0.17-2	1/27/2021	856.65	0.17 - 2 ft	180-116529-1	Excavated		0.13	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.33	< 0.12 U	0.51		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-0.17-2	2/2/2021	856.10	0.17 - 2 ft	180-116723-1	Excavated		0.26	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.1	< 0.12 U	0.18		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-0.17-2	1/27/2021	856.99	0.17 - 2 ft	180-116529-1	Excavated		0.33	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.56	< 0.12 U	1.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.035 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-0.17-2	1/27/2021	855.11	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-0.17-2	1/27/2021	854.67	0.17 - 2 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-0.17-2	1/28/2021	856.29	0.17 - 2 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-0.17-2	1/28/2021	856.63	0.17 - 2 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B37	12 Sep 00B37 - 12 Sep 00B37_0.5-2.5	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B37		9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.34 U	< 0.34 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.34 U	< 0.34 U	< 1.8 U	< 0.34 U	< 0.34 U	< 0.34 U	< 1.8 U	0.41	< 0.34 U	0.43				< 0.34 U	< 0.34 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 - 12 Sep 00B38_1-4.5	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.38 U	< 0.38 U	< 2 U	< 2 U	< 2 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B38		9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	< 1.8 U	< 1.8 U	< 9.5 U	< 9.5 U	< 9.5 U	< 1.8 U	< 1.8 U	< 9.5 U	< 1.8 U	< 1.8 U	< 1.8 U	< 9.5 U	5.7	< 1.8 U	8.4				< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.021 J	< 0.11 U	0.048 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 - 12 Sep 00B39_0.5-2.5	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.42 U	< 0.42 U	< 2.1 U	< 2.1 U	< 2.1 U	< 0.42 U	< 0.42 U	< 2.1 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.1 U	< 0.42 U	< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B39		9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	< 1.8 U	0.27 J	< 9.2 U	< 9.2 U	< 9.2 U	< 1.8 U	< 1.8 U	< 9.2 U	< 1.8 U	< 1.8 U	< 1.8 U	< 9.2 U	0.38 J	< 1.8 U	0.53 J				< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.11 U	0.1	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.35	< 0.12 U	1		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.11 U	0.1	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.42	< 0.12 U	0.82		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	0 - 2 ft	180-57995-1	Not Excavated	< 0.036	0.034	< 0.16	< 0.15	< 0.15	< 0.031	< 0.04	< 0.13		< 0.0086	< 0.034	< 0.033	0.035	< 0.0087	0.061		< 0.028	< 0.024	< 0.039	< 0.055
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated													0.1 J		0.34 J						
Northern Athletic Field	SSHS-B40	12 Sep 00B40_0.5-2.5 12 Sep 00B40 -	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 9.5 U	< 9.5 U	< 9.5 U	< 1.9 U	< 1.9 U	< 9.5 U	< 1.9 U	< 1.9 U	< 1.9 U	< 9.5 U	< 1.9 U	< 1.9 U	< 1.9 U				< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B40		9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.41 U	< 0.41 U	< 2.1 U	< 2.1 U	< 2.1 U	< 0.41 U	< 0.41 U	< 2.1 U	< 0.41 U	< 0.41 U	< 0.41 U	< 2.1 U	< 0.41 U	< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	0.17 - 1 ft	180-123985-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.11	< 0.12 U	0.18		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-1-2	7/1/2021	856.80	1 - 2 ft	180-123985-1	Not Excavated		0.097	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.18	< 0.11 U	0.7		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.06 J	< 0.12 U	0.15		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.11 U	0.059 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.13	< 0.11 U	0.52		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated		0.03 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.14	< 0.12 U	0.37		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated		0.14	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.45	< 0.11 U	1.4		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Tennis Courts / Main Parking Lot	SSHS-B402	SSHS-B402-SUB-0-2	8/30/2016	855.98	0 - 2 ft	180-58129-1	Excavated		0.21 J	< 0.034 U	< 0.034 U	< 1.5 U	< 0.034 U	< 0.034 U	< 1.3 U		< 0.034 U	< 0.034 U	< 0.034 U	0.66 J	< 0.087 U	1.4		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	8/25/2016	856.65	0 - 2 ft	180-57995-1	Excavated	< 0.34	< 0.06	< 1.6	< 1.4	< 1.4	< 0.29	< 0.39	< 1.3		< 0.082	< 0.32	< 0.31	< 0.11	< 0.083	< 0.071		< 0.27	< 0.22	< 0.37	< 0.52
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	0.17 - 1 ft	180-57995-1	Not Excavated		0.84	< 0.034 U	< 0.034 U	< 0.3 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	11	< 0.017 U	14		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	1 - 2 ft	180-57995-1	Not Excavated		0.072	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.13 U		< 0.034 U	< 0.034 U	< 0.034 U	0.82	< 0.0082 U	1.1		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	0.17 - 1 ft	180-57995-1	Not Excavated		0.096	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.0092 U	0.31		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	1 - 2 ft	180-57995-1	Not Excavated		0.078	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.0087 U	0.4		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.39	< 0.39	< 2	< 2	< 2	< 0.39	< 0.39	< 2	< 0.39	< 0.39	< 0.39	< 2	< 0.39	< 0.39	< 0.39				< 0.39	< 0.39
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	< 0.37	< 0.37	< 1.9	< 1.9	< 1.9	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37				< 0.37	< 0.37

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated			0.151	< 0.034 U	< 0.0091 U	< 0.034 U	< 0.0078 U	< 0.039 U	< 0.034 U	< 0.06 U	< 0.034 U	< 0.034 U	< 0.013 U	< 0.016 U	< 0.0079 U	< 0.026 U	< 0.011 U	< 0.0086 U	< 0.064 U	< 0.035 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated			24.79	< 0.034 U	0.7	< 0.034 U	0.62 J	< 1.5 U	< 0.034 U	< 0.43 U	2.1	2	2.8	0.93	2.3	< 1.3 U	< 0.12 U	< 0.25 U	< 3.7 U	< 1.5 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated			0.715	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.064 J	0.054 J	0.084	0.03 J	0.053 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated			1.278	< 0.41	< 0.41		< 0.41				0.11	0.13	0.12	0.13	0.11	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated			3.91	< 0.75	< 0.75		< 0.75				< 0.75	0.81	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated			3.958	0.017 J	0.031 J	< 0.034 U	0.086	< 0.038 U	< 0.034 U	< 0.058 U	0.39	0.33	0.4	0.21	0.22	< 0.025 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B429	SSHS-B429-SUB-0.17-2	8/26/2016	854.95	0.17 - 2 ft	180-58029-1	Excavated			4.817	0.095	< 0.0088 U	< 0.034 U	0.18	< 0.037 U	< 0.034 U	< 0.058 U	0.37	0.34	0.38	0.18	0.29	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.033 U	< 0.034 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated			ND	< 0.37	< 0.37		< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated			ND	< 0.4	< 0.4		< 0.4				< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated			0.199	< 0.0078 U	0.011 J	< 0.034 U	0.013 J	< 0.04 U	< 0.036 U	< 0.061 U	< 0.01 U	< 0.0082 U	< 0.013 U	< 0.016 U	< 0.0081 U	< 0.027 U	< 0.011 U	< 0.0088 U	< 0.066 U	< 0.035 U	< 0.056 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated			2.079	0.02 J	0.034 J	< 0.032 U	0.07 J	< 0.038 U	< 0.035 U	< 0.059 U	0.19	0.16	0.2	0.12	0.13	< 0.026 U	< 0.011 U	< 0.0085 U	< 0.064 U	< 0.034 U	< 0.054 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated			ND	< 0.42	< 0.42		< 0.42				< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated			ND	< 0.36	< 0.36		< 0.36				< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated			0.302	< 0.0074 U	0.019 J	< 0.031 U	0.015 J	< 0.037 U	< 0.034 U	< 0.057 U	0.048 J	< 0.0077 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.033 U	< 0.052 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated			1.681	< 0.007 U	0.039 J	< 0.03 U	0.037 J	< 0.035 U	< 0.032 U	< 0.054 U	0.14	0.14	0.19	0.074	0.13	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated			0.163	< 0.43	< 0.43		< 0.43				< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated			ND	< 0.37	< 0.37		< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated			13.43	0.16	0.33	< 0.031 U	0.49	< 0.037 U	< 0.034 U	< 0.057 U	1.1	1.1	1.4	0.55	0.99	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated			ND	< 0.43	< 0.43		< 0.43				< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated			ND	< 0.37	< 0.37		< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated			12.11	< 0.43	0.44		0.37				1.1	1.4	1.1	1.1	1.2	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated			ND	< 0.38	< 0.38		< 0.38				< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated			ND	< 0.44	< 0.44		< 0.44				< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated			ND		< U		< U				< U	< U	< U	< U	< U				1.1		
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_-	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated			ND	< 0.42 U	< 0.42 U		< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_-	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated			48.1	< 1.8 U	2.8		< 1.8 U				4.4	5.4	5.2	4.6	4.9	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_-	9/13/2000	855.39	0 - 0.5 ft	-	Excavated			0.049	< 0.46 U	< 0.46 U		< 0.46 U				< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated			< 0	< 0.36 U	< 0.36 U		< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_-	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated			ND	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated			ND	< 0.36 U	< 0.36 U		< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_-	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated			ND	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated			10.3	< 1.9 U	< 1.9 U		< 1.9 U				< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated			9.28	< 0.38 U	< 0.38 U		< 0.38 U				0.78	0.88	0.8	0.72	0.71	< 0.38 U	< 0.38 U	< 0.38 U	0.91	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated			0.184	< 0.46 U	< 0.46 U		< 0.46 U				< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated			ND																0.044		
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated			ND																		
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated			0.681	< 0.0066 U	< 0.0078 U	< 0.028 U	0.013 J	< 0.033 U	< 0.03 U	< 0.051 U	0.039 J	0.029 J	0.052 J	< 0.014 U	0.029 J	< 0.022 U	< 0.0092 U	< 0.0074 U	< 0.055 U	< 0.03 U	< 0.047 U
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated			1.83								0.4	0.41									
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated			1.06																		
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated			1.214	< 0.0069	0.027	< 0.03	0.04	< 0.035	< 0.032	< 0.054	0.11	0.095	0.11	0.053	0.074	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated			ND	< 0.39 U	< 0.39 U		< 0.39 U				< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated			ND	< 0.36 U	< 0.36 U		< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated			2.69		0.092 J		0.11 J				0.21 J	0.29 J	0.47	0.18 J	0.23 J				0.53		
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated			2.866	< 0.36 U	0.042 J		< 0.36 U				0.24 J	0.35 J	0.32 J	0.28 J	0.31 J						
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated			0.039	< 0.0067 U	< 0.008 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.031 U	< 0.053 U	< 0.0088 U	< 0.007 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0094 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated			0.04	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated			0.557	< 0.0068 U	< 0.0081 U	< 0.029 U	0.013 J	< 0.034 U	< 0.032 U	< 0.053 U	0.046 J	0.041 J	0.058 J	0.028 J	0.044 J	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated			1.638	< 0.0071 U	0.037 J	0.065 J	0.038 J	< 0.036 U	0.055 J	< 0.056 U	0.1	0.085	0.15	0.053 J	0.086	< 0.024 U	< 0.01 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated			2.914	0.018 J	0.12	< 0.029 U	0.11	< 0.035 U	< 0.032 U	< 0.054 U	0.22	0.25	0.41	0.15	0.25	< 0.024 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U	< 0.049 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated			8.528	0.071 J	0.4	< 0.03 U	0.36	< 0.036 U	< 0.033 U	< 0.055 U	0.77	0.78	0.91	0.43	0.75	< 0.024 U	< 0.0099 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46	0.47	0.63	0.26 J	0.36				0.68		
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated			0.678	< 0.0072 U	0.037 J	< 0.031 U	0.022 J	< 0.037 U	< 0.034 U	< 0.057 U	0.055 J	0.067 J	0.1	0.018 J	0.068 J	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.052 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated			1.478	< 0.007	0.033	< 0.03	0.037	< 0.035	< 0.032	< 0.054	0.14	0.14	0.17	0.051	0.12	< 0.024	< 0.0098	< 0.0078	< 0.059	< 0.032	< 0.05
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated			8.64	< 0.071	0.58	< 0.3	0.26	< 0.36	< 0.33	< 0.55	0.81	0.89	1.1	0.36	0.76	< 0.24	< 0.099	< 0.079	< 0.6	< 0.32	< 0.5
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated			2.603	< 0.0072	< 0.0085	< 0.031	0.091	< 0.036	< 0.033	< 0.056	0.22	0.17	0.21	0.081	0.11	< 0.025	< 0.01	< 0.008	< 0.06	< 0.032	< 0.051
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.008	< 0.029	< 0.0069	< 0.034	< 0.031	< 0.053	< 0.0088	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0076	< 0.057	< 0.031	< 0.048
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated			13.285	0.043 J	0.37	< 0.031 U	0.39	< 0.037 U	0.043 J	< 0.056 U	1.2	1.1	1.3	0.54	1.2	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46	0.47	0.63	0.26 J	0.36				0.68		
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated			29.55	0.07 J	0.62	< 0.03 U	0.79	< 0.036 U	0.14 J	< 0.055 UJ	1.4	1.9	2.3	0.83	2.1	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated			1.093	< 0.0072 U	0.017 J	< 0.031 U	0.017 J	< 0.036 U	< 0.033 U	< 0.056 U	0.09	0.083	0.11	0.036 J	0.086	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated			60.581	0.061 J	1.1	< 0.025 U	2	< 0.051 U	0.043 J	< 0.024 U	5.5	4.7	5.7	2.2	3.5	< 0.021 U	< 0.022 U	< 0.024 U	< 0.25 U	< 0.035 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated			0.099	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	0.021 J	< 0.0072 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	< 0.3 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0095 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.008 U	< 0.034 U	< 0.062 U	< 0.043 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.22 U	< 0.034 U	< 0.091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	< 2.2 U	0.2 J	< 0.9 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.9	0.5 J	< 1.3 U	< 0.034 U	< 0.27 U	< 0.034 U	< 1.2 U	< 1.4 U	< 0.034 U	< 2 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.07 J	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated		< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	0.13	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	< 2.1	< 0.41	< 2.1
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated		< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	1.1	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 3.8	< 0.75	< 3.8
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	< 0.29 U	0.037 J	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.37	< 0.034 U	< 0.038 U	< 0.034 U	< 0.0078 U	< 0.034 U	< 0.061 U	< 0.042 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B429	SSHS-B429-SUB-0.17-2	8/26/2016	854.95	0.17 - 2 ft	180-58029-1	Excavated	< 0.29 U	0.074 J	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.36	< 0.034 U	0.052 J	< 0.034 U	< 0.0077 U	< 0.034 U	< 0.06 U	< 0.042 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated		< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 1.9
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated		< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 2	< 0.4	< 2
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated	< 0.31 U	< 0.0075 U	< 0.033 U	< 0.038 U	< 0.0085 U	< 0.033 U	< 0.045 U	< 0.0097 U	< 0.0091 U	< 0.04 U	< 0.043 U	< 0.0082 U	< 0.045 U	< 0.064 U	< 0.044 U	< 0.051 U	< 0.043 U	< 0.16 U	< 0.042 U	< 0.49 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated	< 0.3 U	< 0.0073 U	< 0.032 U	< 0.036 U	< 0.0082 U	< 0.032 U	< 0.044 U	0.16	< 0.0088 U	< 0.039 U	< 0.042 U	< 0.0079 U	< 0.043 U	< 0.062 U	< 0.043 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.041 U	< 0.47 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated		< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 2.2	< 0.42	< 2.2
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated		< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 1.9	< 0.36	< 1.9
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.035 U	< 0.008 U	< 0.031 U	< 0.043 U	0.056 J	< 0.0085 U	< 0.038 U	< 0.041 U	< 0.0077 U	0.046 J	< 0.06 U	< 0.042 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.04 U	< 0.46 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated	< 0.27 U	0.016 J	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	0.17	0.022 J	< 0.036 U	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.045 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated		< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	0.047	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 2.2
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated		< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 1.9
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated	< 0.29 U	0.16	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	1.2	0.24	0.14 J	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated		< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 2.2
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated		< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 1.9
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated		0.054	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	1.3	0.36	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 2.2
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated		< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 2	< 0.38	< 2
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated		< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 2.3	< 0.44	< 2.3
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated								< U												
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_ -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated		< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.2 U	< 0.42 U	< 2.2 U
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_ -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated		< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	5.1	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 9.3 U	< 1.8 U	< 9.3 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_ -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated		< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 2.4 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 1.8 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_ -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 2.3 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.9 U	< 0.36 U	< 1.9 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_ -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 2.3 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated		< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	2.1	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 10 U	< 1.9 U	< 10 U
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	0.94	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 1.9 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated		< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	0.056 J	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 2.4 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated																				
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated																				
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated	< 0.26 U	0.0087 J	< 0.027 U	< 0.031 U	< 0.0071 U	< 0.028 U	< 0.038 U	0.076	< 0.0076 U	0.036 J	< 0.036 U	< 0.0068 U	< 0.037 U	< 0.053 U	< 0.037 U	< 0.043 U	< 0.036 U	< 0.14 U	< 0.035 U	< 0.41 U
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated								0.39												
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated																				
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	< 0.27	0.014	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	0.091	0.02	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.43
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 1.9 U
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 1.9 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 2 U	< 0.39 U	< 2 U
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 1.8 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated								0.25 J												
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated								0.28 J	0.096 J	< 0.36 U										
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.032 U	< 0.0073 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0078 U	< 0.035 U	< 0.037 U	< 0.007 U	< 0.038 U	< 0.055 U	< 0.038 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	0.065 J	0.018 J	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.038 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.28 U	0.022 J	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.18	< 0.0083 U	0.13 J	< 0.039 U	< 0.0074 U	< 0.041 U	< 0.058 U	< 0.04 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.27 U	0.022 J	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	0.29	0.076	0.042 J	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.28 U	0.07 J	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.81	0.19	0.037 J	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated								0.44												
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	< 0.28 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	0.067 J	0.018 J	< 0.037 U	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	< 0.27	< 0.0067	< 0.029	< 0.033	< 0.0076	< 0.03	< 0.04	0.13	0.038	< 0.036	< 0.038	< 0.0073	< 0.04	< 0.057	< 0.04	< 0.046	< 0.038	< 0.15	< 0.038	< 0.43
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 2.8	< 0.068	< 0.29	< 0.34	< 0.077	< 0.3	< 0.41	0.88	0.2	< 0.36	< 0.39	< 0.074	< 0.4	< 0.58	< 0.4	< 0.46	< 0.39	< 1.5	< 0.38	< 4.4
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.28	0.044	< 0.03	< 0.034	< 0.0078	< 0.03	< 0.041	0.18	< 0.0083	< 0.037	< 0.039	< 0.0075	< 0.041	< 0.058	< 0.041	< 0.047	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0084	< 0.0078	< 0.035	< 0.037	< 0.0071	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.28 U	0.086	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	1.2	0.23	0.12 J	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated								0.44												
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.28 U	0.14	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	1.7	0.45	0.65	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	0.15	< 0.0083 U	< 0.037 U	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	< 0.17 U	0.95	< 0.021 U	< 0.039 U	< 0.024 U	< 0.026 U	< 0.026 U	4.3	0.93	0.3 J	< 0.15 U	< 0.03 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.043 U	< 0.68 U	< 0.025 U	< 0.74 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	0.022 J	< 0.0081 U	< 0.036 U	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**	**Hexachloroethane**	**Indeno (1,2,3-cd)pyrene**	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated	< 0.032 U			< 0.046 U	0.048 J	< 0.034 U	< 0.0085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0082 U	< 0.034 U	< 0.034 U	< 0.034 U	0.021 J
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	< 2.1 U			< 1.1 U	3.8	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U	< 0.034 U	2	< 0.034 U	< 0.034 U	< 0.034 U	0.22 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.21 U			< 0.11 U	0.13	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.042 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.41				0.17	< 0.41	< 0.41	< 0.41	< 0.41	< 0.41	0.11	< 0.41		< 0.41	< 0.41
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	< 0.75				< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75	< 0.75		< 0.75	< 0.75
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated	< 0.031 U			< 0.044 U	0.66	< 0.034 U	< 0.0082 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U	< 0.034 U	< 0.034 U	0.035 J
Football Field	SSHS-B429	SSHS-B429-SUB-0.17-2	8/26/2016	854.95	0.17 - 2 ft	180-58029-1	Excavated	< 0.031 U			< 0.044 U	0.92	0.082	< 0.0082 U	< 0.034 U	< 0.034 U	< 0.034 U	0.26	< 0.034 U	< 0.034 U	< 0.034 U	0.048 J
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37		< 0.37	< 0.37
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	< 0.4				< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4	< 0.4		< 0.4	< 0.4
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated	< 0.033 U			< 0.047 U	0.053 J	< 0.011 U	< 0.0087 U	< 0.0091 U	< 0.044 U	< 0.029 U	< 0.0084 U	< 0.028 U	< 0.04 U	< 0.031 U	< 0.0073 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated	< 0.032 U			< 0.045 U	0.31	0.027 J	< 0.0084 U	< 0.0088 U	< 0.042 U	< 0.028 U	0.11	< 0.028 U	< 0.039 U	< 0.03 U	0.024 J
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.42				< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42	< 0.42		< 0.42	< 0.42
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	< 0.36				< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36		< 0.36	< 0.36
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated	< 0.031 U			< 0.044 U	0.07 J	< 0.01 U	< 0.0082 U	< 0.0086 U	< 0.041 U	< 0.028 U	< 0.0079 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.0069 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated	< 0.029 U			< 0.042 U	0.21	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U	0.11	< 0.025 U	< 0.036 U	< 0.027 U	0.033 J
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.43				0.057	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43		< 0.43	< 0.43
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37		< 0.37	< 0.37
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated	< 0.031 U			< 0.043 U	1.9	0.17	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	0.87	< 0.026 U	< 0.037 U	< 0.029 U	0.18
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.43				< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43		< 0.43	< 0.43
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.37				< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37	< 0.37		< 0.37	< 0.37
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.43				1.3	< 0.43	< 0.43	< 0.43	< 0.43	< 0.43	1	< 0.43		< 0.43	< 0.43
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.38				< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38		< 0.38	< 0.38
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.44				< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44	< 0.44		< 0.44	< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated					< U						< U				
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_-	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.42 U				< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U	< 0.42 U		< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_-	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 1.8 U				5.9	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	< 1.8 U	4	< 1.8 U		< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_-	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.46 U				0.049 J	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U		< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U		< 0.36 U	< 0.36 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_-	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U		< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U		< 0.36 U	< 0.36 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_-	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U		< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	< 1.9 U				2.9	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U	< 1.9 U		< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	< 0.38 U				1.8	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	0.65	< 0.38 U		< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.46 U				0.067 J	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U	< 0.46 U		< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated															
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated															
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated	< 0.028 U			< 0.039 U	0.096	0.016 J	< 0.0073 U	< 0.0076 U	< 0.037 U	< 0.025 U	0.021 J	< 0.024 U		< 0.026 U	0.1
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated					0.63										
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated					0.63										
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	< 0.029			< 0.041	0.2	< 0.0095	< 0.0077	< 0.008	< 0.039	< 0.026	0.066	< 0.025		< 0.027	0.008
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U		< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U		< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.39 U				< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U		< 0.39 U	< 0.39 U
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U		< 0.36 U	< 0.36 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated					0.31 J						0.2 J				
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated					0.33 J	< 0.36 U	< 0.36 U				0.28 J	< 0.36 U			
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.028 U			< 0.04 U	< 0.0075 U	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	< 0.0072 U	< 0.025 U		< 0.026 U	0.029 J
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.029 U			< 0.041 U	0.01 J	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	< 0.0073 U	< 0.025 U		< 0.027 U	0.025 J
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.029 U			< 0.041 U	0.061 J	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	0.035 J	< 0.025 U		< 0.027 U	0.045 J
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.03 U			< 0.043 U	0.15	0.024 J	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	0.062 J	< 0.026 U		< 0.028 U	0.46
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.029 U			< 0.041 U	0.36	< 0.0094 U	< 0.0076 U	< 0.008 U	< 0.039 U	< 0.026 U	0.21	< 0.025 U		< 0.027 U	0.12
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.03 U			< 0.042 U	1.2	0.094	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U	0.6	< 0.026 U		< 0.028 U	0.042 J
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated					1						0.31 J				
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	< 0.03 U			< 0.043 U	0.094	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.041 U	< 0.027 U	0.054 J	< 0.026 U	< 0.037 U	< 0.028 U	0.011 J
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	< 0.029			< 0.042	0.22	< 0.0096	< 0.0077	< 0.0081	< 0.039	< 0.026	0.097	< 0.025		< 0.027	0.041
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 0.3			< 0.42	1	< 0.097	< 0.078	< 0.082	< 0.4	< 0.26	0.6	< 0.26		< 0.28	0.17
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.03			< 0.043	0.51	0.019	< 0.0079	< 0.0083	< 0.04	< 0.027	0.11	< 0.026		< 0.028	0.0074
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025	< 0.0072	< 0.025		< 0.026	< 0.0063
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.03 U			< 0.043 U	1.9	0.072 J	< 0.008 U	< 0.0084 U	< 0.041 U	< 0.027 U	0.97	< 0.026 U	< 0.037 U	< 0.028 U	0.15
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated					1						0.31 J				
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	4	0.61	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	1.8	< 0.026 U	0.056 J	< 0.028 U	0.33
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	0.12	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	0.083	< 0.026 U	< 0.037 U	< 0.028 U	0.034 J
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated	< 0.049 U			< 0.055 U	8.7	0.3	< 0.03 U	< 0.023 U	< 0.031 U	< 0.026 U	3.2	< 0.032 U	0.11 J	< 0.02 U	0.13
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.042 U	0.033 J	< 0.0095 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0065 U

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B410	SSHS-B410-SUB-0-2	8/25/2016	856.77	0 - 2 ft	180-57995-1	Excavated		0.059 J	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.15 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0094 U	0.044 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	< 0.016 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated		0.84	< 0.034 U	< 0.034 U	< 1.3 U	< 0.034 U	< 0.034 U	< 2.4 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.5	< 1 U	3.5		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.068 J	< 0.11 U	0.12		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.41	< 0.41	< 2.1	< 2.1	< 2.1	< 0.41	< 0.41	< 2.1	< 0.41	< 0.41	< 0.41	< 2.1	0.068	< 0.41	0.2				< 0.41	< 0.41
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	< 0.75	< 0.75	< 3.8	< 3.8	< 3.8	< 0.75	< 0.75	< 3.8	< 0.75	< 0.75	< 0.75	< 3.8	2	< 0.75	< 0.75				< 0.75	< 0.75
Football Field	SSHS-B424	SSHS-B424-SUB-0-2	8/22/2016	856.17	0 - 2 ft	180-57858-1	Excavated		0.055 J	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.36	< 0.0091 U	0.65		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B429	SSHS-B429-SUB-0.17-2	8/26/2016	854.95	0.17 - 2 ft	180-58029-1	Excavated		0.07 J	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.66	< 0.0091 U	0.63		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.37	< 0.37	< 1.9	< 1.9	< 1.9	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37				< 0.37	< 0.37
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	< 0.4	< 0.4	< 2	< 2	< 2	< 0.4	< 0.4	< 2	< 0.4	< 0.4	< 0.4	< 2	< 0.4	< 0.4	< 0.4				< 0.4	< 0.4
Football Field	SSHS-B432	SSHS-B432-SUB-0-2	8/22/2016	855.16	0 - 2 ft	180-57858-1	Excavated		0.035 J	< 0.18 U	< 0.17 U	< 0.17 U	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0096 U	< 0.038 U	< 0.036 U	0.04 J	< 0.0096 U	0.058 J		< 0.031 U	< 0.026 U	< 0.043 U	< 0.061 U
Football Field	SSHS-B434	SSHS-B434-SUB-0-2	8/22/2016	855.08	0 - 2 ft	180-57858-1	Excavated		0.042 J	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	0.24	< 0.0093 U	0.3		< 0.03 U	< 0.025 U	< 0.042 U	< 0.059 U
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.42	< 0.42	< 2.2	< 2.2	< 2.2	< 0.42	< 0.42	< 2.2	< 0.42	< 0.42	< 0.42	< 2.2	< 0.42	< 0.42	< 0.42				< 0.42	< 0.42
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	< 0.36	< 0.36	< 1.9	< 1.9	< 1.9	< 0.36	< 0.36	< 1.9	< 0.36	< 0.36	< 0.36	< 1.9	< 0.36	< 0.36	< 0.36				< 0.36	< 0.36
Football Field	SSHS-B448	SSHS-B448-SUB-0-2	8/25/2016	856.23	0 - 2 ft	180-57995-1	Excavated		< 0.0066 U	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.009 U	< 0.035 U	< 0.034 U	0.037 J	< 0.0091 U	0.076 J		< 0.029 U	< 0.025 U	< 0.041 U	< 0.057 U
Football Field	SSHS-B449	SSHS-B449-SUB-0-2	8/30/2016	855.21	0 - 2 ft	180-58129-1	Excavated		0.098	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	0.13	< 0.0086 U	0.23		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.43	< 0.43	< 2.2	< 2.2	< 2.2	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	0.059				< 0.43	< 0.43
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.37	< 0.37	< 1.9	< 1.9	< 1.9	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37				< 0.37	< 0.37
Football Field	SSHS-B450	SSHS-B450-SUB-0-2	8/25/2016	856.21	0 - 2 ft	180-57995-1	Excavated		0.36	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	1.2	< 0.009 U	1.7		< 0.029 U	< 0.024 U	< 0.04 U	< 0.057 U
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.43	< 0.43	< 2.2	< 2.2	< 2.2	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43				< 0.43	< 0.43
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.37	< 0.37	< 1.9	< 1.9	< 1.9	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37	< 1.9	< 0.37	< 0.37	< 0.37				< 0.37	< 0.37
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.43	< 0.43	< 2.2	< 2.2	< 2.2	< 0.43	< 0.43	< 2.2	< 0.43	< 0.43	< 0.43	< 2.2	0.28	< 0.43	1.6				< 0.43	< 0.43
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.38	< 0.38	< 2	< 2	< 2	< 0.38	< 0.38	< 2	< 0.38	< 0.38	< 0.38	< 2	< 0.38	< 0.38	< 0.38				< 0.38	< 0.38
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.44	< 0.44	< 2.3	< 2.3	< 2.3	< 0.44	< 0.44	< 2.3	< 0.44	< 0.44	< 0.44	< 2.3	< 0.44	< 0.44	< 0.44				< 0.44	< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated													< U							
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_-	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.42 U	< 0.42 U	< 2.2 U	< 2.2 U	< 2.2 U	< 0.42 U	< 0.42 U	< 2.2 U	< 0.42 U	< 0.42 U	< 0.42 U	< 2.2 U	< 0.42 U	< 0.42 U	< 0.42 U				< 0.42 U	< 0.42 U
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_-	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B51	_13 Sep 00B51_0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 1.8 U	< 1.8 U	< 9.3 U	< 9.3 U	< 9.3 U	< 1.8 U	< 1.8 U	< 9.3 U	< 1.8 U	< 1.8 U	< 1.8 U	< 9.3 U	< 1.8 U	< 1.8 U	8.6				< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_-	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.46 U	< 0.46 U	< 2.4 U	< 2.4 U	< 2.4 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	< 0.46 U				< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.36 U	< 0.36 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 0.36 U	< 0.36 U				< 0.36 U	< 0.36 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_-	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 0.44 U	< 2.3 U	< 2.3 U	< 2.3 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B53	_13 Sep 00B53_0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.36 U	< 0.36 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.36 U	< 0.36 U	< 1.9 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.9 U	< 0.36 U	< 0.36 U	< 0.36 U				< 0.36 U	< 0.36 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_-	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 0.44 U	< 2.3 U	< 2.3 U	< 2.3 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	< 1.9 U	< 1.9 U	< 10 U	< 10 U	< 10 U	< 1.9 U	< 1.9 U	< 10 U	< 1.9 U	< 1.9 U	< 1.9 U	< 10 U	3.2	< 1.9 U	2.1				< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	< 0.38 U	< 0.38 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	0.5	< 0.38 U	1.5				< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.46 U	< 0.46 U	< 2.4 U	< 2.4 U	< 2.4 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	< 0.46 U	< 2.4 U	< 0.46 U	< 0.46 U	0.061 J				< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B56	B56	9/13/2000	852.85	0 - 0.5 ft	NA	Excavated																				
Northern Athletic Field	SSHS-B56	B56-0.5-2.5	9/13/2000	852.85	0.5 - 2.5 ft	NA	Excavated																				
Rear Parking Lot	SSHS-B568	SSHS-B568-SUB-0-2	9/21/2016	851.24	0 - 2 ft	180-59020-1	Excavated	< 0.033 U	0.059 J	< 0.15 U	< 0.14 U	< 0.14 U	< 0.028 U	< 0.038 U	< 0.12 U		< 0.008 U	< 0.032 U	< 0.031 U	0.16	< 0.0081 U	0.091		< 0.026 U	< 0.022 U	< 0.036 U	< 0.051 U
Northern Athletic Field	SSHS-B57	B57-0.5-2.5	9/13/2000	852.42	0.5 - 2.5 ft	NA	Excavated																				
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated															0.43					
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	8/30/2016	852.49	0 - 2 ft	180-58129-1	Excavated	< 0.035	0.025	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0084	< 0.033	< 0.032	0.13	< 0.0085	0.2		< 0.027	< 0.023	< 0.038	< 0.054
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.38 U	< 0.38 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	< 0.38 U	< 0.38 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U	< 1.9 U	< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.39 U	< 0.39 U	< 2 U	< 2 U	< 2 U	< 0.39 U	< 0.39 U	< 2 U	< 0.39 U	< 0.39 U	< 0.39 U	< 2 U	< 0.39 U	< 0.39 U	< 0.39 U				< 0.39 U	< 0.39 U
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.36 U	< 0.36 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 0.36 U	< 0.36 U				< 0.36 U	< 0.36 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated													0.1 J		0.34 J					
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	< 0.36 U	< 0.36 U										< 0.87 U	0.08 J	< 0.36 U	0.3 J					
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.034 U	0.019 J	< 0.16 U	< 0.14 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0082 U	< 0.033 U	< 0.031 U	0.02 J	< 0.0083 U	< 0.0071 U		< 0.027 U	< 0.023 U	< 0.037 U	< 0.053 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.035 U	0.019 J	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	0.011 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.035 U	0.033 J	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	0.056 J	< 0.0083 U	0.059 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.036 U	0.3	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0087 U	< 0.034 U	< 0.033 U	0.28	< 0.0088 U	0.13		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.035 U	0.09	< 0.16 U	< 0.15 U	< 0.14 U	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	0.19	< 0.0085 U	0.29		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.036 U	0.053 J	< 0.16 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.51	< 0.0087 U	1		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated													0.47		0.84					
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.031 U	< 0.042 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	0.033 J	< 0.0089 U	0.082		< 0.029 U	< 0.024 U	< 0.04 U	< 0.056 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	< 0.036	0.035	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0085	< 0.034	< 0.033	0.11	< 0.0086	0.19		< 0.028	< 0.023	< 0.039	< 0.054
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 0.36	0.26	< 1.6	< 1.5	< 1.5	< 0.31	< 0.41	< 1.3		< 0.086	< 0.34	< 0.33	0.52	< 0.087	1		< 0.28	< 0.24	< 0.39	< 0.55
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.036	0.032	< 0.17	< 0.15	< 0.15	< 0.031	< 0.041	< 0.14		< 0.0087	< 0.035	< 0.033	0.45	< 0.0088	0.42		< 0.028	< 0.024	< 0.04	< 0.056
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.034	< 0.0061	< 0.16	< 0.14	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.033	< 0.031	< 0.011	< 0.0083	< 0.0071		< 0.027	< 0.023	< 0.038	< 0.053
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated		0.45	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	0.99	< 0.0089 U	1.7		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated													0.47		0.84					
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated		0.9	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	4.1	< 0.0087 U	6.6		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated		0.068 J	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	0.14	< 0.0088 U	0.11		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	0 - 2 ft	180-66622-2	Not Excavated		0.59	< 0.13 U	< 0.11 U	< 0.13 U	< 0.028 U	< 0.027 U	< 0.38 U		< 0.025 U	< 0.058 U	< 0.69 U	7.9	< 0.05 U	11		< 0.026 U	< 0.029 U	< 0.035 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated		< 0.0062 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	< 0.012 U	< 0.0086 U	0.023 J		< 0.027 U	< 0.023 U	< 0.039 U	< 0.054 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated			7.197	0.054 J	0.54	< 0.03 U	0.37	< 0.036 U	< 0.033 U	< 0.055 U	0.57	0.65	0.9	0.31	0.81	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated			0.129	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.037 U	< 0.033 U	< 0.056 U	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated			1.234	< 0.0069 U	0.023 J	< 0.03 U	0.02 J	< 0.035 U	< 0.032 U	< 0.054 U	0.1	0.096	0.13	0.057 J	0.12	< 0.024 U	< 0.0096 U	< 0.0078 U	< 0.058 U	< 0.031 U	< 0.049 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated			4.093	< 0.0071 U	0.12	< 0.03 U	0.09	< 0.036 U	< 0.033 U	< 0.055 UJ	0.36	0.31	0.46	0.18	0.33	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated			5.042	0.01 J	0.13	< 0.031 U	0.11	< 0.036 U	< 0.033 U	< 0.056 U	0.4	0.44	0.56	0.17	0.57	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.032 U	< 0.051 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated			ND																		
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated			0.3491	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	0.034 J	0.031 J	0.037 J	0.018 J	0.032 J	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U	< U	< U	< U	< U				1.1		
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated			ND																		
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated			ND																		
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U	< U	< U	< U	< U				1.1		
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated			21.8	0.23 J	0.16 J		0.72				1.9	1.7	1.3	1.3	1.3						
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated			20.76	0.3 J	0.17 J		0.8				1.6	1.3	1.1	1.2	1						
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated			937.9	4.9 J	23		69				68	58	44	51	34						
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated			10.778	0.13 J	0.17 J		0.44				0.95	0.79	0.67	0.76	0.56						
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated			0.171	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U						
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated			8.195	0.051 J	< 0.4 U		0.15 J				0.28 J	0.24 J	0.19 J	0.18 J	0.14 J						
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated			1.777	< 0.37 U	< 0.37 U		0.055				0.16 J	0.13 J	0.13 J	0.13 J	0.11 J						
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated			12.104	< 0.41 U	0.61		0.54				1.1	1.1	1.1	1	0.84						
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated			ND	< 0.5 U	< 0.5 U		< 0.5 U				< 0.5 U	< 0.5 U	< 0.5 U	< 0.5 U	< 0.5 U						
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10_-	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated			1	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11_-	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated			0.38	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U						
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated			0.604	< 0.46 U	< 0.46 U		< 0.46 U				< 0.46 U	0.081 J	0.097 J	0.074 J	0.094 J						
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated			0.338	< 0.43 U	< 0.43 U		< 0.43 U				< 0.43 U	0.05 J	0.046 J	< 0.43 U	0.046 J						
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated			ND	< 0.45 U	< 0.45 U		< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated			0.22	< 0.44 U	< 0.44 U		< 0.44 U				< 0.44 U	< 0.44 U	0.048 J	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	0.05 J	< 0.44 U	< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated			ND	< 0.47 U	< 0.47 U		< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated			ND		< 0.45 U		< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.28 U	0.06 J	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.64	0.2	0.042 J	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0084 U	< 0.037 U	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.27 U	0.0097 J	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	0.12	0.032 J	< 0.035 U	< 0.038 U	< 0.0072 U	0.05 J	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.44	0.091	< 0.036 U	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.28 U	0.035 J	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.041 U	0.4	0.11	0.056 J	< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated																				
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	0.037 J	0.0081 J	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated								< U												
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated																				
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated																				
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated								< U												
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated								2	0.45	0.14 J										
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated								1.6	0.39 J	0.28 J										
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated								64	11	0.099 J										
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated								0.9	0.24 J	0.099 J										
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated								0.046 J	< 0.44 U	< 0.44 U										
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated								0.32 J	0.053 J	< 0.4 U										
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated								0.21 J	0.053 J	< 0.37 U										
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated								1.4	0.3 J	< 0.41 U										
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated								< 0.5 U	< 0.5 U	< 0.5 U										
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated								< 0.47 U	< 0.47 U	< 0.47 U										
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated								0.059 J	< 0.46 U	< 0.46 U										
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated								0.046 J	< 0.43 U	< 0.43 U										
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated		< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 2.3 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated		< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 2.4 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated		< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	0.045 J	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 2.3 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated		< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 2.4 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated		< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 2.3 U

DRAFT

TABLE 5-5C
Shallow Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	0.77	0.083	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	0.64	< 0.026 U	< 0.036 U	< 0.028 U	0.076
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	0.02 J	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	0.0073 J
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	0.15	< 0.0095 U	< 0.0077 U	< 0.008 U	< 0.039 U	< 0.026 U	0.099	< 0.025 U	< 0.035 U	< 0.027 U	0.031 J
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	0.6	< 0.0097 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	0.27	< 0.026 U	< 0.036 U	< 0.028 U	0.026 J
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	0.62	0.022 J	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	0.47	< 0.026 U	< 0.037 U	< 0.028 U	0.059 J
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.96 U						< 0.58 U	< 0.46 U		< 0.52 U		< 0.64 U	< 0.64 U		
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	0.037 J	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	0.028 J	< 0.025 U	< 0.035 U	< 0.027 U	0.0071 J
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated					< U						< U				
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.97 U						< 0.59 U	< 0.46 U		< 0.52 U		< 0.64 U			
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.47 U						< 0.28 U	< 0.22 U		< 0.25 U		< 0.31 U			
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated					< U						< U				
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated					3.6	0.2 J	< 0.38 U				1.3	< 0.38 U			
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated					3.1	0.31 J	< 0.4 U				0.99	< 0.4 U			
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated					190	22	< 4 U				35	< 4 U			
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated					1.7	0.16 J	< 0.38 U				0.52	< 0.38 U			
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated					0.058 J	< 0.44 U	< 0.44 U				< 0.44 U	< 0.44 U			
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated					0.62	0.041 J	< 0.4 U				0.14 J	< 0.4 U			
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated					0.25 J	< 0.37 U	< 0.37 U				0.075 J	< 0.37 U			
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated					1.7	< 0.41 U	< 0.41 U				0.81	< 0.41 U			
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated					< 0.5 U	< 0.5 U	< 0.5 U				< 0.5 U	< 0.5 U			
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10_-	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.37 U				0.56	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11_-	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.37 U				0.38	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated					< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U			
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated					0.059 J	< 0.46 U	< 0.46 U				0.075 J	< 0.46 U			
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated					0.084 J	< 0.43 U	< 0.43 U				< 0.43 U	< 0.43 U			
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U		< 0.45 U	< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U		< 0.47 U	< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.44 U				0.071 J	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U	< 0.44 U		< 0.44 U	< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.47 U				< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U	< 0.47 U		< 0.47 U	< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.45 U				< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U		< 0.45 U	< 0.45 U

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated		0.1	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	0.36	< 0.0087 U	0.74		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated		0.085	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.0089 U	0.024 J		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated		0.075	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	0.075	< 0.0085 U	0.16		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated		0.052 J	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	0.27	< 0.0087 U	0.64		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated		0.24	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	0.32	< 0.0088 U	0.6		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated						< 0.55 U						< 14 U				< 0.69 U			< 0.69 U	< 0.63 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated		0.015 J	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	0.03 J	< 0.0084 U	0.042 J		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated													< U		< U					
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.65 U					< 0.56 U						< 14 U				< 0.7 U		< 0.69 U	< 0.64 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.31 U,F2					< 0.27 U						< 6.7 U,F1				< 0.34 U		< 0.34 U	< 0.31 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated													< U		< U					
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	< 0.38 U	0.1 J										< 1.9 U	2.8	< 0.38 U	2.9					
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	< 0.4 U	0.36 J										< 2.1 U	2.8	< 0.4 U	2.9					
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	< 4 U	22										< 20 U	150	< 4 U	140					
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated	< 0.38 U	0.058 J										< 2 U	1.3	< 0.38 U	1.6					
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 0.44 U										< 2.3 U	< 0.44 U	< 0.44 U	0.067 J					
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	< 0.4 U	< 0.4 U										< 2.1 U	5.33	< 0.4 U	0.46					
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	< 0.41 U	0.074 J										< 2.1 U	0.54	< 0.41 U	1.6					
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	< 0.37 U	0.054 J										< 1.9 U	0.24 J	< 0.37 U	0.18 J					
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.5 U	< 0.5 U										< 1.2 U	< 0.5 U	< 0.5 U	< 0.5 U					
Northern Athletic Field	SSHS-SS10	_12 Sep 00SS10_-	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	0.44				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-SS11	_12 Sep 00SS11_-	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.47 U	< 0.47 U										< 1.1 U	< 0.47 U	< 0.47 U	< 0.47 U					
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.46 U	< 0.46 U										< 1.1 U	< 0.46 U	< 0.46 U	0.065 J					
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.43 U	< 0.43 U										< 1 U	< 0.43 U	< 0.43 U	0.066 J					
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.45 U	< 0.45 U	< 2.3 U	< 2.3 U	< 2.3 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U				< 0.45 U	< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.47 U	< 0.47 U	< 2.4 U	< 2.4 U	< 2.4 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.44 U	< 0.44 U	< 2.3 U	< 2.3 U	< 2.3 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	< 0.44 U	< 2.3 U	< 0.44 U	< 0.44 U	0.056 J				< 0.44 U	< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.47 U	< 0.47 U	< 2.4 U	< 2.4 U	< 2.4 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U	< 2.4 U	< 0.47 U	< 0.47 U	< 0.47 U				< 0.47 U	< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.45 U	< 0.45 U	< 2.3 U	< 2.3 U	< 2.3 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U	< 2.3 U	< 0.45 U	< 0.45 U	< 0.45 U				< 0.45 U	< 0.45 U

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 UJ	< 0.0039 U	< 0.0020 U	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 UJ	< 0.0023 U	< 0.0031 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.0071 U						< 0.0071 U	< 0.0071 U			< 0.0071 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.004 U	< 0.00054 U	< 0.00055 U	< 0.00045 U	< 0.00036 U	< 0.00059 U	< 0.00041 U	< 0.00036 U	< 0.00061 U	< 0.00057 U	< 0.0012 U	< 0.00047 U	< 0.00069 U	< 0.0003 U	< 0.0006 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0064 U						< 0.0064 U	< 0.0064 U			< 0.0064 U			
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	< 0.023 U	< 0.0058 U						< 0.0058 U	< 0.0058 U			< 0.0058 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U						< 0.0067 U	< 0.0067 U			< 0.0067 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	< 0.023 U	< 0.0058 U						< 0.0058 U	< 0.0058 U			0.0013 J			
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			0.0029 J			
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			< 0.0065 U			
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated	< 0.023 U	< 0.0058 U						< 0.0058 U	< 0.0058 U			< 0.0058 U			
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.024 U	< 0.0061 U						< 0.0061 U	< 0.0061 U			< 0.0061 U			
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U						< 0.0057 U	< 0.0057 U			< 0.0057 U			
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U						< 0.0057 U	< 0.0057 U			< 0.0057 U			
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	< 0.025 U	< 0.0063 U						< 0.0063 U	< 0.0063 U			< 0.0063 U			
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	< 0.0047 U	< 0.0029 U	< 0.0029 U	< 0.0035 U	< 0.0039 U	< 0.0067 U	< 0.0045 U	< 0.0049 U	< 0.0023 U	< 0.0036 U	< 0.0038 U	< 0.0031 U	< 0.0057 U	< 0.0018 U	< 0.0046 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U,*
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	0.077	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	0.021 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	0.008 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	< 0.0042 U	< 0.0026 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0059 U	< 0.004 U	< 0.0044 U	< 0.0021 U	< 0.0032 U	< 0.0034 U	< 0.0028 U	< 0.0051 U	< 0.0016 U	< 0.004 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	0.017 J	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	0.0096 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	0.0091 J	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	0.0071 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	0.024	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	0.025	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	0.0089 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	0.0069 J	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	0.075	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	0.064	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	0.011 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	0.015 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	0.0087 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	0.013 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	0.0035 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	< 0.0042 U	< 0.0026 U	< 0.0026 U	< 0.0032 U	< 0.0035 U	< 0.006 U	< 0.004 U	< 0.0045 U	< 0.0021 U	< 0.0032 U	< 0.0035 U	< 0.0028 U	< 0.0052 U	< 0.0016 U	< 0.0041 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.074	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	0.062	< 0.0025 U	< 0.0025 U	< 0.003 U	< 0.0034 U	< 0.0058 U	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0033 U	< 0.0027 U	< 0.005 U	< 0.0016 U	< 0.004 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	0.016 J,F2,F1	0.00067 J	< 0.00058 U	< 0.00074 U	< 0.0004 U	< 0.0017 U	0.0029 J	< 0.00083 U	< 0.0005 U	< 0.00047 U	< 0.0011 U	< 0.00072 U	< 0.00055 U	0.0016 J	< 0.00076 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	0.03	< 0.00065 U	< 0.00059 U	< 0.00077 U	< 0.00041 U	< 0.0018 U	< 0.0007 U	< 0.00085 U	< 0.00052 U	< 0.00048 U	< 0.0011 U	< 0.00074 U	< 0.00057 U	0.0022 J	< 0.00078 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	0.0045 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	0.021 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	< 0.86 U	< 0.54 U	< 0.52 U	< 0.64 U	< 0.71 U	< 1.2 U	< 0.82 U	< 0.9 U	< 0.43 U	< 0.66 U	< 0.71 U	< 0.58 U	< 1.1 U	< 0.33 U	< 0.84 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	0.041	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U,F2	< 0.0027 U	< 0.003 U,F2	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U,F2	< 0.0028 U,F2	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U,F2
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	0.0081 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U,F1	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U,F1	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	< 0.004 U	< 0.0025 U	< 0.0024 U	< 0.003 U	< 0.0033 U	< 0.0056 U	< 0.0038 U	< 0.0042 U	< 0.002 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0048 U	< 0.0015 U	< 0.0039 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	0.0067 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	0.017 J	< 0.0026 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0059 U	< 0.0039 U	< 0.0043 U	< 0.0021 U	< 0.0031 U	< 0.0034 U	< 0.0028 U	< 0.005 U	< 0.0016 U	< 0.004 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 UJ	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.071 U	< 0.071 U	< 0.071 U		< 0.071 U	< 0.071 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.00054 U	< 0.00069 U	< 0.00054 U	< 0.00064 U	< 0.00053 U	< 0.00051 U	< 0.00046 U	< 0.00049 U	< 0.00068 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00048 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.0064 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0064 U	< 0.0064 U	< 0.0064 U		< 0.0064 U	< 0.0064 U			
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	< 0.0058 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 4.4 U	< 4.4 U	< 4.4 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U			
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	< 0.0058 U			< 3.8 U	< 3.8 U	< 3.8 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U			
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.0065 U			< 0.43 U	< 0.43 U	< 0.43 U	< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0065 U			< 0.43 U	< 0.43 U	< 0.43 U	< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated	< 0.0058 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U			
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0061 U						< 0.0061 U	< 0.0061 U	< 0.0061 U		< 0.0061 U	< 0.0061 U			
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0057 U						< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U			
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated	< 0.0057 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U			
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	< 0.0063 U			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.0063 U	< 0.0063 U			
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	< 0.0035 U	< 0.0041 U	< 0.0043 U	< 0.006 U	< 0.0024 U	< 0.0015 U	< 0.0027 U	< 0.0022 U	< 0.0042 U	< 0.0059 U	< 0.0023 U	< 0.0038 U	< 0.0036 U	< 0.0024 U	< 0.0026 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	< 0.0028 U	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0047 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.0028 U	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.0028 U	< 0.0032 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	< 0.0028 U	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	0.0026 J	< 0.0029 U	< 0.0031 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	< 0.0029 U	< 0.0034 U	< 0.0036 U	< 0.005 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	0.0034 J	< 0.0033 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	< 0.0029 U	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.002 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	< 0.0031 U	< 0.0036 U	< 0.0038 U	< 0.0053 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U	< 0.0038 U	< 0.0052 U	< 0.0021 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	< 0.0027 U	< 0.0032 U	< 0.0034 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	0.0029 J	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.002 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	0.0028 J	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0047 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	0.003 J	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	0.0033 J	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	0.0025 J	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	< 0.0028 U	< 0.0032 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	0.0026 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	0.0037 J	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	0.0025 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.0024 U	< 0.0028 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.0023 U	< 0.0027 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	< 0.0032 U	< 0.0037 U	< 0.0039 U	< 0.0054 U	< 0.0021 U	< 0.0014 U	< 0.0024 U	< 0.002 U	< 0.0038 U	< 0.0054 U	< 0.0021 U	< 0.0034 U	< 0.0033 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	< 0.0028 U	< 0.0032 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0027 U	< 0.0031 U	< 0.0034 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.003 U	< 0.0035 U	< 0.0038 U	< 0.0052 U	< 0.0021 U	< 0.0013 U	< 0.0023 U	< 0.0019 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.0027 U	< 0.00049 U	< 0.0005 U	< 0.00055 U	< 0.0009 U	< 0.00058 U	< 0.0008 U	< 0.00048 U	< 0.001 U	< 0.0012 U	< 0.00062 U	< 0.00076 U	< 0.0006 U	< 0.00036 U	< 0.00043 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.0028 U	< 0.00051 U	< 0.00052 U	< 0.00057 U	< 0.00093 U	< 0.00059 U	< 0.00083 U	< 0.00049 U	< 0.001 U	< 0.0012 U	< 0.00064 U	< 0.00078 U	< 0.00062 U	< 0.00037 U	< 0.00044 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	< 0.0028 U	< 0.0032 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	< 0.64 U	< 0.75 U	< 0.8 U	< 1.1 U	< 0.43 U	< 0.28 U	< 0.49 U	< 0.4 U	< 0.78 U	< 1.1 U	< 0.43 U	< 0.69 U	< 0.67 U	< 0.44 U	< 0.47 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	0.0029 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	< 0.0027 U	< 0.0032 U,F2	< 0.0034 U	< 0.0047 U,F2	< 0.0019 U	< 0.0012 U,F2	< 0.0021 U	< 0.0017 U,F2	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U,F2	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	0.0034 J	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	< 0.003 U	< 0.0034 U	< 0.0037 U	< 0.005 U	< 0.002 U	< 0.0013 U	< 0.0023 U	< 0.0018 U	< 0.0036 U	< 0.005 U	< 0.002 U	< 0.0032 U	< 0.0031 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	< 0.0031 U	< 0.0036 U	< 0.0038 U	< 0.0053 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U	< 0.0037 U	< 0.0052 U	< 0.0021 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	< 0.0028 U	< 0.0033 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U						< 0.014 U					< 0.0071 U	< 0.0071 U		
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.00052 U	< 0.00086 U	< 0.00056 U	< 0.00055 U	< 0.00073 U	< 0.00058 U	< 0.00071 U	< 0.00053 U	< 0.0006 U	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00068 U	< 0.00071 U
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.0064 U						< 0.013 U					< 0.0064 U	< 0.0064 U		
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	< 0.0058 U						< 0.012 U					0.0016 J	< 0.0058 U		
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.0067 U						< 0.013 U					< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	< 0.0058 U						< 0.012 U					0.0036 J	< 0.0058 U		
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					0.025	< 0.0065 U		
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					0.016	< 0.0065 U		
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated	< 0.0058 U						< 0.012 U					< 0.0058 U	< 0.0058 U		
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0061 U						< 0.012 U					< 0.0061 U	< 0.0061 U		
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0057 U						< 0.011 U					0.0011 J	< 0.0057 U		
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated	< 0.0057 U						< 0.011 U					0.0011 J	< 0.0057 U		
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated															
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	< 0.0063 U						< 0.013 U					< 0.0063 U	< 0.0063 U		
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	< 0.0032 U	< 0.0028 U	< 0.0062 U	< 0.0034 U	< 0.0088 U	< 0.0031 U	< 0.0043 U	< 0.0028 U	< 0.0055 U	< 0.002 U	< 0.0044 U	< 0.003 U	< 0.0025 U	< 0.0031 U	< 0.0024 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.0025 U	< 0.0023 U	< 0.0049 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.0025 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	< 0.0025 U	< 0.0023 U	< 0.0049 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	< 0.0021 U	< 0.0018 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.002 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	< 0.0027 U	< 0.0024 U	< 0.0052 U	< 0.0029 U	< 0.0073 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0055 U	< 0.0031 U	< 0.0078 U	< 0.0028 U	< 0.0038 U	< 0.0024 U	< 0.0049 U	< 0.0018 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0027 U	< 0.0021 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0043 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0024 U	< 0.0021 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	0.0094	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	< 0.0025 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	< 0.0029 U	< 0.0026 U	< 0.0056 U	< 0.0031 U	< 0.0079 U	< 0.0028 U	< 0.0039 U	< 0.0025 U	< 0.005 U	< 0.0018 U	< 0.004 U	< 0.0027 U	< 0.0023 U	< 0.0028 U	< 0.0022 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	< 0.0025 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0054 U	< 0.003 U	< 0.0076 U	< 0.0027 U	< 0.0037 U	< 0.0024 U	< 0.0047 U	< 0.0017 U	< 0.0038 U	< 0.0026 U	< 0.0022 U	< 0.0027 U	< 0.0021 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.00068 U	< 0.00096 U	< 0.001 U	< 0.00079 U	< 0.0046 U	0.0023 J	< 0.00095 U	< 0.0013 U	< 0.00054 U	< 0.0007 U	< 0.00053 U	< 0.00054 U	0.0014 J	< 0.00055 U	< 0.00073 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.0007 U	< 0.00099 U	< 0.0011 U	< 0.00082 U	< 0.0047 U	0.0035 J	< 0.00098 U	< 0.0013 U	< 0.00056 U	< 0.00072 U	< 0.00054 U	< 0.00056 U	0.0012 J	< 0.00057 U	< 0.00075 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	< 0.59 U	< 0.52 U	< 1.1 U	< 0.63 U	< 1.6 U	< 0.57 U	< 0.79 U	0.74 J	< 1 U	< 0.36 U	< 0.81 U	< 0.55 U	< 0.46 U	< 0.56 U	< 0.44 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U,F2	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U,F2	< 0.0035 U,F2	< 0.0023 U	< 0.002 U	< 0.0024 U,F1	< 0.0019 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U,F1	< 0.0018 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	< 0.0027 U	< 0.0024 U	< 0.0053 U	< 0.0029 U	< 0.0074 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0046 U	< 0.0017 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0026 U	< 0.002 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0055 U	< 0.003 U	< 0.0077 U	< 0.0028 U	< 0.0038 U	< 0.0024 U	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0027 U	< 0.0021 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U

DRAFT

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Rear Parking Lot	PDI6-B5109	DUP-45	2/9/2023	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 0.0016 U	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 UJ	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_0-0.25	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U		< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	
Rear Parking Lot	SSHS-B101	SSHS-B101-0.17-2 (1)	8/14/2014	852.95	0 - 2 ft	180-35818-2	Excavated	< 0.00039 U	< 0.00067 U	0.00094 J	< 0.00074 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	0 - 2.5 ft	NA	Not Excavated			0.0023 J					
Northern Athletic Field	SSHS-B12	B12_10 May 00_0-0.25	5/10/2000	854.04	0 - 0.5 ft	NA	Excavated	< 0.0064 U		< 0.0064 U		< 0.0064 U	< 0.0064 U	< 0.0064 U	
Northern Athletic Field	SSHS-B12	B12_10 May 00_1-4	5/10/2000	854.04	1 - 4 ft	NA	Excavated	< 0.0058 U		< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	
Northern Athletic Field	SSHS-B13	B13_10 May 00_0-0.25	5/10/2000	856.73	0 - 0.5 ft	NA	Excavated	< 0.0067 U		< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-B13	B13_10 May 00_1-2	5/10/2000	856.73	1 - 2 ft	NA	Excavated	< 0.0058 U		0.0098		< 0.0058 U	0.0015 J	0.0014 J	
Northern Athletic Field	SSHS-B14	B14_10 May 00_0-0.25	5/10/2000	857.03	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-B15	B23455	5/10/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-B15	B23405T2	7/11/2000	856.90	0.75 - 1 ft	NA	Excavated	< 0.0058 U		< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	
Football Field	SSHS-B15	B23408T2	7/11/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0061 U		< 0.0061 U		< 0.0061 U	< 0.0061 U	< 0.0061 U	
Football Field	SSHS-B15	B23405T2-1	7/27/2000	856.90	0 - 0.5 ft	NA	Excavated	< 0.0057 U		0.0016 J		< 0.0057 U	< 0.0057 U	< 0.0057 U	
Football Field	SSHS-B15	B23404T2-1	7/27/2000	856.90	1 - 1.5 ft	NA	Excavated	< 0.0057 U		0.0016 J		< 0.0057 U	< 0.0057 U	< 0.0057 U	
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	0 - 2.6 ft	-	Not Excavated				0.0051 J				
Football Field	SSHS-B2	B23488	5/12/2000	855.22	1 - 2 ft	NA	Excavated	< 0.0063 U		< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-0.17-2	7/26/2018	852.76	0.17 - 2 ft	180-80225-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Football Field	SSHS-B2025	PS-FD-40	7/26/2018	854.55	0.17 - 2 ft	180-80227-3	Excavated	< 0.0037 U	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0055 U	< 0.0028 U	< 0.0036 U	< 0.0064 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-0.17-2	7/26/2018	854.55	0.17 - 2 ft	180-80225-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-0.17-2	7/26/2018	855.22	0.17 - 2 ft	180-80227-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.005 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-0.17-2	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2028	PS-FD-41	7/26/2018	855.23	0.17 - 2 ft	180-80227-3	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	0 - 2 ft	180-80252-1	Not Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-0.17-2	7/27/2018	855.50	0.17 - 2 ft	180-80251-2	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-0.17-2	7/27/2018	854.88	0.17 - 2 ft	180-80251-1	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-0.17-2	7/27/2018	854.70	0.17 - 2 ft	180-80251-1	Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-0.17-2	7/26/2018	855.45	0.17 - 2 ft	180-80225-1	Excavated	< 0.0031 U	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-0.17-2	7/25/2018	855.59	0.17 - 2 ft	180-80154-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-0.17-2	7/25/2018	855.00	0.17 - 2 ft	180-80157-1	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	0.17 - 2 ft	180-80157-3	Not Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-0.17-2	7/25/2018	856.82	0.17 - 2 ft	180-80154-2	Excavated	< 0.0033 U	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0048 U	< 0.0025 U	< 0.0032 U	< 0.0057 U
Football Field	SSHS-B2073	PS-FD-28	7/25/2018	856.99	0.17 - 2 ft	180-80157-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-0.17-2	7/25/2018	856.99	0.17 - 2 ft	180-80157-3	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-0.17-2	7/25/2018	855.40	0.17 - 2 ft	180-80157-3	Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-0.17-2	7/25/2018	856.61	0.17 - 2 ft	180-80154-1	Excavated	< 0.0029 U	< 0.0028 U	0.0041 J	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-0.17-2	7/25/2018	856.77	0.17 - 2 ft	180-80157-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-0.17-2	7/25/2018	855.64	0.17 - 2 ft	180-80154-2	Excavated	< 0.0029 U	< 0.0028 U	0.0025 J	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-0.17-2	7/25/2018	855.25	0.17 - 2 ft	180-80154-1	Excavated	< 0.0031 U	< 0.0029 U	0.013	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2110	PS-FD-18	7/25/2018	854.78	0.17 - 2 ft	180-80157-2	Excavated	< 0.0026 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-0.17-2	7/25/2018	854.78	0.17 - 2 ft	180-80154-1	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-0.17-2	7/25/2018	855.91	0.17 - 2 ft	180-80154-3	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-0.17-2	7/25/2018	856.01	0.17 - 2 ft	180-80154-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2129	PS-FD-17	7/25/2018	855.33	0.17 - 2 ft	180-80157-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-0.17-2	7/25/2018	855.33	0.17 - 2 ft	180-80157-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-0.17-2	7/25/2018	856.56	0.17 - 2 ft	180-80154-3	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-0-2	7/24/2018	855.07	0 - 2 ft	180-80106-3	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-0-2	7/24/2018	854.94	0 - 2 ft	180-80106-2	Excavated	< 0.0027 U	< 0.0026 U	0.0026 J	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-0-2	7/24/2018	856.10	0 - 2 ft	180-80106-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-0-2	7/24/2018	855.99	0 - 2 ft	180-80106-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-0-2	7/24/2018	855.74	0 - 2 ft	180-80105-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-0-2	7/27/2018	856.06	0 - 2 ft	180-80252-1	Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-0-2	7/24/2018	856.18	0 - 2 ft	180-80105-3	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-0.17-2	7/26/2018	857.04	0.17 - 2 ft	180-80225-1	Excavated	< 0.0034 U	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0049 U	< 0.0025 U	< 0.0033 U	< 0.0058 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-0.17-2	7/26/2018	855.94	0.17 - 2 ft	180-80225-1	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2196	PS-FD-15	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2196	SSHS-B2196-SUB-0-2	7/24/2018	855.03	0 - 2 ft	180-80106-2	Excavated	< 0.0032 U	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0047 U	< 0.0024 U	< 0.0031 U	< 0.0055 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-0-2	7/24/2018	854.99	0 - 2 ft	180-80105-1	Excavated	< 0.00049 U	< 0.0008 U	0.0021 J	< 0.0012 U	< 0.0011 U	< 0.00072 U	< 0.00062 U	< 0.0012 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-0-2	7/24/2018	855.05	0 - 2 ft	180-80105-2	Excavated	< 0.00051 U	< 0.00083 U	< 0.00058 U	< 0.0013 U	< 0.0011 U	0.001 J	< 0.00064 U	< 0.0012 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-0.17-2	7/26/2018	855.06	0.17 - 2 ft	180-80225-2	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2215	PS-FD-43	7/26/2018	855.11	0.17 - 2 ft	180-80227-3	Excavated	< 0.0029 U	< 0.0028 U	0.084	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-0.17-2	7/26/2018	855.11	0.17 - 2 ft	180-80227-2	Excavated	< 0.68 U	< 0.66 U	17	< 0.4 U	< 1 U	< 0.51 U	< 0.67 U	< 1.2 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-0.17-2	7/27/2018	855.08	0.17 - 2 ft	180-80251-3	Excavated	< 0.0028 U	< 0.0027 U	0.021	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-0.17-2	7/24/2018	855.38	0.17 - 2 ft	180-80106-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-0.17-2	7/26/2018	854.93	0.17 - 2 ft	180-80227-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2225	SSHS-B2225-SUB-0.17-2	7/24/2018	857.03	0.17 - 2 ft	180-80105-3	Excavated	< 0.0029 U	< 0.0028 U,F2	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-0.17-2	7/26/2018	856.56	0.17 - 2 ft	180-80227-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-0.17-2	7/26/2018	856.55	0.17 - 2 ft	180-80227-1	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2228	PS-FD-53	7/27/2018	855.33	0.17 - 2 ft	180-80252-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-0.17-2	7/27/2018	855.33	0.17 - 2 ft	180-80251-3	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-0.17-2	7/27/2018	855.28	0.17 - 2 ft	180-80252-1	Excavated	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0046 U	< 0.0023 U	< 0.0031 U	< 0.0054 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-0.17-2	7/23/2018	856.03	0.17 - 2 ft	180-80091-4	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-0.17-2	7/23/2018	856.14	0.17 - 2 ft	180-80091-2	Excavated	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0048 U	< 0.0025 U	< 0.0032 U	< 0.0056 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-0.17-2	7/24/2018	856.82	0.17 - 2 ft	180-80105-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	0.098	0.0011 J	< 0.0005 U	< 0.00065 U	< 0.00034 U	< 0.0015 U	0.0029 J	< 0.00072 U	< 0.00044 U	< 0.00041 U	< 0.00096 U	< 0.00063 U	< 0.00048 U	0.0022 J	< 0.00066 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	0.012 J	< 0.0026 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0059 U	< 0.0039 U	< 0.0043 U	< 0.0021 U	< 0.0031 U	< 0.0034 U	< 0.0028 U	< 0.005 U	< 0.0016 U	< 0.004 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.011 U	0.0013 J	< 0.00047 U	< 0.00061 U	< 0.00032 U	< 0.0014 U	0.0013 J	< 0.00067 U	< 0.00041 U	< 0.00038 U	< 0.0009 U	< 0.00059 U	< 0.00045 U	0.0044 J	< 0.00062 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	0.014 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U,F2	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	0.023 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 UJ	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 UJ	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.021 J	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.02 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	< 0.0033 UJ	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 UJ	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 UJ	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.0044 U	< 0.0027 U	< 0.0027 U	< 0.0033 U	< 0.0036 U	< 0.0063 U	< 0.0042 U	< 0.0046 U	< 0.0022 U	< 0.0034 U	< 0.0036 U	< 0.0029 U	< 0.0054 U	< 0.0017 UJ	< 0.0043 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.0057 U	< 0.0036 U	< 0.0035 U	< 0.0043 U	< 0.0047 U	< 0.0081 U	< 0.0055 U	< 0.006 U	< 0.0029 U	< 0.0044 U	< 0.0047 U	< 0.0038 U	< 0.007 U	< 0.0022 UJ	< 0.0056 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	0.022 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 UJ	< 0.0033 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.021 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	0.0025 J	< 0.0041 UJ	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	0.015 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 UJ	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 UJ	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	0.017 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 UJ	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 UJ	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 UJ	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.0039 U	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0055 UJ	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 UJ	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	0.015 U	< 0.0026 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0058 UJ	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0034 U	< 0.0027 U	< 0.005 UJ	< 0.0016 U	< 0.004 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0028 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 UJ	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 UJ	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 UJ	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 0.0044 U	< 0.0027 U	< 0.0027 U	< 0.0033 U	< 0.0036 U	< 0.0063 U	< 0.0042 U	< 0.0046 U	< 0.0022 U	< 0.0033 U	< 0.0036 U	< 0.0029 U	< 0.0054 U	< 0.0017 U	< 0.0043 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0056 U	< 0.0037 U	< 0.0041 U	< 0.002 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0048 U	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	< 0.0042 U	< 0.0026 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.006 U	< 0.004 U	< 0.0044 U	< 0.0021 U	< 0.0032 U	< 0.0034 U	< 0.0028 U	< 0.0051 U	< 0.0016 U	< 0.0041 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0022 UJ	< 0.0024 UJ	< 0.0042 U	< 0.0028 U	< 0.0031 U	< 0.0015 U	< 0.0023 UJ	< 0.0024 U	< 0.002 U	< 0.0036 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 UJ	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.0041 U	< 0.0025 U	< 0.0025 U	< 0.003 U	< 0.0034 U	< 0.0058 U	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0033 U	< 0.0027 U	< 0.005 UJ	< 0.0016 U	< 0.004 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0022 UJ	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0031 U	< 0.0015 U	< 0.0023 UJ	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	< 0.0041 U	< 0.0025 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0058 U	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0033 U	< 0.0027 U	< 0.005 U	< 0.0016 U	< 0.004 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 0.0041 U	< 0.0025 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0058 U	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0034 U	< 0.0027 U	< 0.005 U	< 0.0016 U	< 0.004 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 UJ	< 0.0024 UJ	< 0.0042 U	< 0.0028 U	< 0.0031 U	< 0.0015 U	< 0.0022 UJ	< 0.0024 U	< 0.002 U	< 0.0036 U	< 0.0011 U	< 0.0029 UJ
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 UJ	< 0.0026 UJ	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 UJ	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 UJ
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0021 UJ	< 0.0023 UJ	< 0.0039 U	< 0.0026 U	< 0.0029 U	< 0.0014 U	< 0.0021 UJ	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 UJ	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 UJ	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	0.044	< 0.0025 U	< 0.0025 U	< 0.003 U	< 0.0034 U	< 0.0058 U	< 0.0039 U	< 0.0043 U	< 0.002 U	< 0.0031 U	< 0.0033 U	< 0.0027 U	< 0.005 U	< 0.0016 U	< 0.004 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	< 0.0035 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	< 0.0024 U	< 0.00043 U	< 0.00044 U	< 0.00048 U	< 0.00078 U	< 0.0005 U	< 0.0007 U	< 0.00042 U	< 0.00087 U	< 0.0011 U	< 0.00054 U	< 0.00066 U	< 0.00052 U	< 0.00031 U	< 0.00038 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	< 0.0031 U	< 0.0036 U	< 0.0038 U	< 0.0053 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U	< 0.0037 U	< 0.0052 U	< 0.0021 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.0022 U	< 0.0004 U	< 0.00041 U	< 0.00045 U	< 0.00073 U	< 0.00047 U	< 0.00065 U	< 0.00039 U	< 0.00081 U	< 0.00099 U	< 0.00051 U	< 0.00062 U	< 0.00049 U	< 0.00029 U	< 0.00035 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 UJ	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 UJ	< 0.0028 U	< 0.0018 U	< 0.002 UJ
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.0053	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	0.0083	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0044 UJ	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	< 0.0042 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	0.0047 J	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.0054 U	< 0.0038 U	< 0.0041 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U	< 0.004 U	< 0.0056 U	< 0.0022 U	< 0.0035 U	< 0.0034 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.007 U	< 0.0049 U	< 0.0053 U	< 0.0036 U	< 0.0029 U	< 0.0018 U	< 0.0033 U	< 0.0026 U	< 0.0052 U	< 0.0072 U	< 0.0029 U	< 0.0046 U	< 0.0044 U	< 0.0029 U	< 0.0031 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.007	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	0.0055	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 UJ	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 UJ	< 0.0026 U	< 0.0017 U	< 0.0018 UJ
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	0.0042 J	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	0.0066	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.0047 U	< 0.0033 U	< 0.0036 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	< 0.005 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U	< 0.0037 U	< 0.0052 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.0043 U	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 0.0054 U	< 0.0038 U	< 0.0041 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U	< 0.004 U	< 0.0055 U	< 0.0022 U	< 0.0035 U	< 0.0034 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 0.0048 U	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.002 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	< 0.0051 U	< 0.0036 U	< 0.0039 U	< 0.0027 U	< 0.0021 U	< 0.0014 U	< 0.0024 U	< 0.0019 U	< 0.0038 U	< 0.0053 U	< 0.0021 U	< 0.0034 U	< 0.0033 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.0036 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.00096 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0037 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 UJ	< 0.0016 UJ
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 UJ	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0032 UJ	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.005 U	< 0.0035 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0023 U	< 0.0019 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	< 0.0036 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00097 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 UJ	< 0.0016 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0047 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	< 0.005 U	< 0.0035 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0023 U	< 0.0019 U	< 0.0037 U	< 0.0052 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	0.0027 J
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 0.005 U	< 0.0035 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U	< 0.0037 U	< 0.0052 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	< 0.0036 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.00095 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0037 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 UJ	< 0.0016 UJ
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 UJ	< 0.002 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 0.0043 U	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 UJ	< 0.0017 UJ
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	< 0.0034 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00089 U	< 0.0016 U	< 0.0013 U	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0022 U	< 0.0022 U	< 0.0014 UJ	< 0.0015 UJ
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	< 0.005 U	< 0.0035 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0023 U	< 0.0019 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 UJ	< 0.0017 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	< 0.00059 U	< 0.00083 U	< 0.00089 U	< 0.00069 U	< 0.004 U,*	0.0038 J	0.0068 J	< 0.0011 U	< 0.00047 U	< 0.0006 U	< 0.00046 U	< 0.00047 U	0.0035 J	< 0.00048 U	< 0.00064 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	< 0.0028 U	< 0.0025 U	< 0.0055 U	< 0.003 U	< 0.0077 U	< 0.0027 U	< 0.0038 U	< 0.0024 U	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0027 U	< 0.0021 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.00056 U	< 0.00078 U	< 0.00083 U	< 0.00064 U	< 0.0037 U,*	0.008 J	< 0.00077 U	< 0.0011 U	< 0.00044 U	< 0.00057 U	< 0.00043 U	< 0.00044 U	0.0025 J	< 0.00045 U	< 0.0006 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U,F1	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 UJ	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 UJ	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 UJ	< 0.002 UJ	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.003 U	< 0.0027 U	< 0.0059 U	< 0.0032 U	< 0.0082 U	< 0.0029 U	< 0.004 U	< 0.0026 U	< 0.0051 U	< 0.0019 U	< 0.0042 U	< 0.0028 U	< 0.0024 U	< 0.0049 U	< 0.0052 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.0039 U	< 0.0035 U	< 0.0076 U	< 0.0042 U	< 0.011 U	< 0.0038 U	< 0.0052 U	< 0.0034 U	< 0.0067 U	< 0.0024 U	< 0.0054 U	< 0.0036 U	< 0.0031 U	< 0.0064 U	< 0.0067 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 UJ	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 UJ	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 UJ	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 UJ	< 0.0045 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.0021 U	< 0.0043 U	< 0.0045 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	< 0.0028 U	< 0.0025 U	< 0.0055 U	< 0.003 U	< 0.0077 U	< 0.0027 U	< 0.0038 U	< 0.0024 UJ	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0046 U	< 0.0048 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	0 - 1.8 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 0.003 U	< 0.0027 U	< 0.0058 U	< 0.0032 U	< 0.0082 U	< 0.0029 U	< 0.004 U	< 0.0026 U	< 0.0051 U	< 0.0019 U	< 0.0042 U	< 0.0028 U	< 0.0023 U	< 0.0049 U	< 0.0052 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 0.0027 U	< 0.0024 U	< 0.0052 U	< 0.0029 U	< 0.0073 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0046 U	< 0.0017 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0044 U	< 0.0046 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	< 0.0024 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	< 0.0029 U	< 0.0025 U	< 0.0056 U	< 0.0031 U	< 0.0078 U	< 0.0028 U	< 0.0039 U	< 0.0025 U	< 0.0049 U	< 0.0018 U	< 0.004 U	< 0.0027 U	< 0.0022 U	< 0.0047 U	< 0.0049 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.002 U	< 0.0018 U	< 0.0039 U	< 0.0022 U	< 0.0055 U	< 0.002 U	< 0.0027 U	< 0.0017 U	< 0.0034 U	< 0.0012 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	< 0.0024 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0054 U	< 0.003 U	< 0.0076 U	< 0.0027 U	< 0.0037 U	< 0.0024 U	< 0.0047 U	< 0.0017 U	< 0.0038 U	< 0.0026 U	< 0.0022 U	< 0.0046 U	< 0.0048 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	< 0.002 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0027 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0035 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0044 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0054 U	< 0.003 U	< 0.0076 U	< 0.0027 U	< 0.0038 U	< 0.0024 U	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0046 U	< 0.0048 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 0.0028 U	< 0.0025 U	< 0.0054 U	< 0.003 U	< 0.0077 U	< 0.0027 U	< 0.0038 U	< 0.0024 U	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0046 U	< 0.0048 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	< 0.002 U	< 0.0018 U	< 0.0039 U	< 0.0022 U	< 0.0055 U	< 0.002 U	< 0.0027 U	< 0.0017 U	< 0.0034 U	< 0.0012 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	< 0.0019 U	< 0.0017 U	< 0.0037 U	< 0.002 U	< 0.0052 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0032 U	< 0.0012 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0031 U	< 0.0033 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	< 0.0028 U	< 0.0025 U	< 0.0054 U	< 0.003 U	< 0.0076 U	< 0.0027 U	< 0.0037 U	< 0.0024 U	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0046 U	< 0.0048 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0021 U	< 0.0043 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2233	SSHS-B2233-SUB-0.17-2	7/24/2018	854.83	0.17 - 2 ft	180-80105-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-0.17-2	7/23/2018	855.30	0.17 - 2 ft	180-80091-1	Excavated	< 0.00043 U	< 0.0007 U	0.00098 J	< 0.0011 U	< 0.00093 U	0.0017 J	< 0.00054 U	0.0017 J
Football Field	SSHS-B2236	SSHS-B2236-SUB-0.17-2	7/27/2018	855.25	0.17 - 2 ft	180-80251-3	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B2237	PS-FD-54	7/27/2018	855.30	0.17 - 2 ft	180-80252-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2237	SSHS-B2237-SUB-0.17-2	7/27/2018	855.30	0.17 - 2 ft	180-80252-1	Excavated	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0048 U	< 0.0025 U	< 0.0032 U	< 0.0056 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-0.17-2	7/23/2018	855.07	0.17 - 2 ft	180-80091-1	Excavated	< 0.0004 U	< 0.00065 U	< 0.00046 U	< 0.001 U	< 0.00087 U	0.0012 J	< 0.00051 U	0.0012 J
Football Field	SSHS-B2245	SSHS-B2245-SUB-0-2	7/24/2018	855.25	0 - 2 ft	180-80106-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2246	PS-FD-36	7/26/2018	855.24	0 - 2 ft	180-80225-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-0-2	7/26/2018	855.24	0 - 2 ft	180-80225-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-0.17-2	5/20/2019	857.04	0.17 - 2 ft	180-90324-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 UJ	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B2704	SSHS-B2704-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2705	PS-FD-15	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2705	SSHS-B2705-SUB-0.17-2	5/16/2019	855.37	0.17 - 2 ft	180-90231-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2706	SSHS-B2706-SUB-0.17-2	5/16/2019	854.96	0.17 - 2 ft	180-90231-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2707	SSHS-B2707-SUB-0.17-2	5/16/2019	854.89	0.17 - 2 ft	180-90231-1	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 UJ	< 0.0039 UJ	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2708	PS-FD-31	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.0035 U	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0051 U	< 0.0026 U	< 0.0034 U	< 0.006 U
Football Field	SSHS-B2708	SSHS-B2708-SUB-0.17-2	5/21/2019	855.05	0.17 - 2 ft	180-90380-1	Excavated	< 0.0045 U	< 0.0044 U	< 0.0027 U	< 0.0026 U	< 0.0066 U	< 0.0034 U	< 0.0044 U	< 0.0078 U
Football Field	SSHS-B2709	SSHS-B2709-SUB-0.17-2	5/20/2019	855.26	0.17 - 2 ft	180-90324-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2710	PS-FD-16	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2710	SSHS-B2710-SUB-0.17-2	5/16/2019	855.48	0.17 - 2 ft	180-90231-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 UJ	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2711	SSHS-B2711-SUB-0.17-2	5/15/2019	855.87	0.17 - 2 ft	180-90165-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-B2712	SSHS-B2712-SUB-0.17-2	5/15/2019	856.23	0.17 - 2 ft	180-90165-1	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 UJ	< 0.0037 UJ	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2713	SSHS-B2713-SUB-0.17-2	5/15/2019	856.92	0.17 - 2 ft	180-90165-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 UJ	< 0.0042 UJ	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2714	SSHS-B2714-SUB-0.17-2	5/15/2019	857.01	0.17 - 2 ft	180-90165-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-B2715	SSHS-B2715-SUB-0.17-2	5/15/2019	857.02	0.17 - 2 ft	180-90165-1	Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 UJ	< 0.0045 UJ	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2716	SSHS-B2716-SUB-0.17-2	5/15/2019	856.77	0.17 - 2 ft	180-90165-1	Excavated	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0019 UJ	< 0.0048 UJ	< 0.0024 U	< 0.0032 U	< 0.0056 U
Football Field	SSHS-B2717	SSHS-B2717-SUB-0.17-2	5/17/2019	856.13	0.17 - 2 ft	180-90275-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	0.0055 J	< 0.0029 U	0.0072 J
Football Field	SSHS-B2718	SSHS-B2718-SUB-0.17-2	5/16/2019	855.30	0.17 - 2 ft	180-90231-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2719	SSHS-B2719-SUB-0.17-2	5/14/2019	854.79	0.17 - 2 ft	180-90048-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-0.17-2	5/14/2019	854.80	0.17 - 2 ft	180-90048-1	Excavated	< 0.0028 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2721	SSHS-B2721-SUB-0.17-2	5/14/2019	855.15	0.17 - 2 ft	180-90048-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	--	0 - 1.8 ft	--	Not Excavated				0.0051 J				
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-0.17-2	9/3/2019	853.35	0.17 - 2 ft	180-95155-1	Excavated	< 0.0035 U	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0051 U	< 0.0026 U	< 0.0034 U	< 0.006 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-0.17-2	9/3/2019	853.09	0.17 - 2 ft	180-95155-1	Excavated	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0046 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-0.17-2	8/30/2019	851.95	0.17 - 2 ft	180-95047-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-0.17-2	8/27/2019	852.58	0.17 - 2 ft	180-94824-3	Excavated	< 0.0033 U	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0049 U	< 0.0025 U	< 0.0032 U	< 0.0057 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-0.17-2	9/3/2019	853.88	0.17 - 2 ft	180-95155-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-0.17-2	9/3/2019	854.13	0.17 - 2 ft	180-95155-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-0.17-2	8/30/2019	853.85	0.17 - 2 ft	180-95047-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-0.17-2	8/30/2019	853.28	0.17 - 2 ft	180-95047-2	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-0.17-2	8/29/2019	852.90	0.17 - 2 ft	180-94981-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-0.17-2	8/29/2019	853.35	0.17 - 2 ft	180-94981-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-0.17-2	8/28/2019	853.51	0.17 - 2 ft	180-94902-3	Excavated	< 0.0023 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.004 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-0.17-2	8/29/2019	853.54	0.17 - 2 ft	180-94981-2	Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-0.17-2	8/28/2019	853.78	0.17 - 2 ft	180-94900-2	Excavated	< 0.0032 U	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0047 U	< 0.0024 U	< 0.0031 U	< 0.0055 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-0.17-2	8/27/2019	853.82	0.17 - 2 ft	180-94829-1	Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-0.17-2	8/27/2019	854.09	0.17 - 2 ft	180-94824-3	Excavated	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.005 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-0.17-2	8/27/2019	853.86	0.17 - 2 ft	180-94824-2	Excavated	< 0.0032 U	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0048 U	< 0.0024 U	< 0.0032 U	< 0.0056 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-0.17-2	8/26/2019	853.71	0.17 - 2 ft	180-94752-2	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-0.17-2	8/26/2019	853.76	0.17 - 2 ft	180-94754-3	Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-0.17-2	9/3/2019	854.48	0.17 - 2 ft	180-95155-2	Excavated	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0048 U	< 0.0024 U	< 0.0032 U	< 0.0056 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-0.17-2	8/30/2019	854.59	0.17 - 2 ft	180-95047-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-0.17-2	8/29/2019	854.13	0.17 - 2 ft	180-94981-3	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-0.17-2	8/29/2019	854.60	0.17 - 2 ft	180-94981-2	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-0.17-2	8/28/2019	855.22	0.17 - 2 ft	180-94902-1	Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0014 U	< 0.0034 U	< 0.0017 U	< 0.0023 U	< 0.004 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-0.17-2	8/27/2019	855.08	0.17 - 2 ft	180-94824-2	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-0.17-2	8/27/2019	855.17	0.17 - 2 ft	180-94824-1	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-0.17-2	8/26/2019	855.10	0.17 - 2 ft	180-94752-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-0.17-2	8/26/2019	854.81	0.17 - 2 ft	180-94752-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-0.17-2	9/3/2019	855.09	0.17 - 2 ft	180-95155-2	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3037	SSHS-B3037-SUB-0.17-2	9/3/2019	855.60	0.17 - 2 ft	180-95155-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-0.17-2	9/3/2019	855.76	0.17 - 2 ft	180-95162-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-0.17-2	8/30/2019	855.85	0.17 - 2 ft	180-95047-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-0.17-2	8/29/2019	855.10	0.17 - 2 ft	180-94981-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-0.17-2	8/29/2019	855.17	0.17 - 2 ft	180-94981-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-0.17-2	8/28/2019	855.23	0.17 - 2 ft	180-94902-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-0.17-2	8/28/2019	855.78	0.17 - 2 ft	180-94902-2	Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0016 U	< 0.0021 U	< 0.0038 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-0.17-2	8/28/2019	856.00	0.17 - 2 ft	180-94900-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-0.17-2	8/28/2019	856.03	0.17 - 2 ft	180-94900-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-0.17-2	8/27/2019	856.22	0.17 - 2 ft	180-94824-1	Excavated	< 0.0032 U	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0047 U	< 0.0024 U	< 0.0032 U	< 0.0056 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-0.17-2	8/27/2019	856.24	0.17 - 2 ft	180-94819-1	Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-0.17-2	8/27/2019	856.08	0.17 - 2 ft	180-94819-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-0.17-2	8/26/2019	856.17	0.17 - 2 ft	180-94754-2	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-0.17-2	8/26/2019	855.60	0.17 - 2 ft	180-94752-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 UJ	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 UJ	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 UJ	< 0.0041 U	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.002 UJ	< 0.0022 UJ	< 0.0038 U	< 0.0026 U	< 0.0028 U	< 0.0013 U	< 0.002 UJ	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.001 U	< 0.0026 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 UJ	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 UJ	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 UJ	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	0.0038 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 UJ	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 UJ	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 UJ	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 UJ	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 UJ	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0028 U	< 0.003 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	< 0.004 U	< 0.0025 U	< 0.0025 U	< 0.003 U	< 0.0033 U	< 0.0058 U	< 0.0039 U	< 0.0042 U	< 0.002 U	< 0.0031 U	< 0.0033 U	< 0.0027 U	< 0.0049 U	< 0.0016 U	< 0.0039 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	0.008 J	< 0.0016 U	< 0.0016 U	< 0.002 UJ	< 0.0022 U	< 0.0037 U	< 0.0025 U	< 0.0027 U	< 0.0013 U	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.001 U	< 0.0025 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 UJ	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	< 0.0044 U	< 0.0027 U	< 0.0027 U	< 0.0033 U	< 0.0036 U	< 0.0062 U	< 0.0042 U	< 0.0046 U	< 0.0022 U	< 0.0033 U	< 0.0036 U	< 0.0029 U	< 0.0053 U	< 0.0017 U	< 0.0042 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	0.0035 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	0.0047 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 UJ	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.0044 U	< 0.0028 U	< 0.0027 U	< 0.0033 U	< 0.0037 U	< 0.0063 U	< 0.0042 U	< 0.0047 U	< 0.0022 U	< 0.0034 U	< 0.0036 U	< 0.003 U	< 0.0054 U	< 0.0017 U	< 0.0043 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0036 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0032 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.004 U	< 0.0025 U	< 0.0024 U	< 0.003 U	< 0.0033 U	< 0.0057 U	< 0.0038 U	< 0.0042 U	< 0.002 U	< 0.003 U	< 0.0033 U	< 0.0027 U	< 0.0049 U	< 0.0015 U	< 0.0039 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated	0.021 J	< 0.0031 U	< 0.0031 U	< 0.0038 U	< 0.0042 U	< 0.0072 U	< 0.0048 U	< 0.0053 U	< 0.0025 U	< 0.0038 U	< 0.0041 U	< 0.0034 U	< 0.0062 U	< 0.002 U	< 0.0049 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 UJ	< 0.0018 UJ
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 0.0043 U	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 UJ	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 UJ	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	< 0.0047 U	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	< 0.0033 U	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00087 U	< 0.0015 U	< 0.0012 U	< 0.0024 U	< 0.0034 U	< 0.0013 U	< 0.0022 U	< 0.0021 U	< 0.0014 UJ	< 0.0015 UJ
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 UJ	< 0.0018 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	< 0.0047 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 UJ	< 0.0017 UJ
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 0.0046 U	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 UJ	< 0.0017 UJ
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0047 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	< 0.0049 U	< 0.0035 U	< 0.0037 U	< 0.0026 U	< 0.002 U	< 0.0013 U	< 0.0023 U	< 0.0019 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0032 U	< 0.0031 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	< 0.0032 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0013 U	< 0.00084 U	< 0.0015 U	< 0.0012 U	< 0.0024 U	< 0.0033 U	< 0.0013 U	< 0.0021 U	< 0.002 U	< 0.0013 U	< 0.0014 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	< 0.0053 U	< 0.0038 U	< 0.004 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U	< 0.0039 U	< 0.0055 U	< 0.0022 U	< 0.0035 U	< 0.0034 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	< 0.0042 U	< 0.0029 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	0.0042 J	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	0.0042 J	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	0.005 J	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	0.0048 J	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	0.0047 J	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	0.0044 J	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	< 0.0042 UJ	< 0.0029 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	< 0.0042 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 UJ	< 0.0019 UJ
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	0.004 J	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.0054 U	< 0.0038 U	< 0.0041 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U	< 0.004 U	< 0.0056 U	< 0.0022 U	< 0.0036 U	< 0.0035 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 0.0046 U	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 0.0047 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0049 U	< 0.0035 U	< 0.0037 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0023 U	< 0.0018 U	< 0.0036 U	< 0.005 U	< 0.002 U	< 0.0032 U	< 0.0031 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated	< 0.0061 U	< 0.0044 U	< 0.0047 U	< 0.0032 U	< 0.0025 U	< 0.0016 U	< 0.0029 U	< 0.0023 U	< 0.0046 U	< 0.0064 U	< 0.0025 U	< 0.0041 U	< 0.0039 U	< 0.0026 U	< 0.0028 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	0.0046 J	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	< 0.0046 UJ	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7															
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 0.0025 U	< 0.0023 U	< 0.0049 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	< 0.0026 U	< 0.0023 U	< 0.0052 U	< 0.0028 U	< 0.0073 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0044 U	< 0.0046 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	< 0.0018 U	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.005 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0011 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0032 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0045 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.004 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0021 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0034 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	< 0.0028 U	< 0.0024 U	< 0.0054 U	< 0.003 U	0.0086 J	< 0.0027 U	< 0.0037 U	< 0.0024 U	< 0.0047 U	< 0.0017 U	< 0.0038 U	< 0.0026 U	< 0.0022 U	< 0.0045 U	< 0.0048 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	< 0.0018 U	< 0.0016 U	< 0.0035 U	< 0.0019 U	< 0.0049 U	< 0.0017 U	< 0.0024 U	< 0.0015 U	< 0.003 U	< 0.0011 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.0029 U	< 0.0031 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	< 0.003 U	< 0.0026 U	< 0.0058 U	< 0.0032 U	< 0.0081 U	< 0.0029 U	< 0.004 U	< 0.0026 U	< 0.0051 U	< 0.0018 U	< 0.0041 U	< 0.0028 U	< 0.0023 U	< 0.0049 U	< 0.0051 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.003 U	< 0.0027 U	< 0.0059 U	< 0.0033 U	< 0.0083 U	< 0.003 U	< 0.0041 U	< 0.0026 U	< 0.0052 U	< 0.0019 U	< 0.0042 U	< 0.0028 U	< 0.0024 U	< 0.005 U	< 0.0052 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0045 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0027 U	< 0.0024 U	< 0.0053 U	< 0.0029 U	< 0.0075 U	< 0.0027 U	< 0.0037 U	< 0.0024 U	< 0.0047 U	< 0.0017 U	< 0.0038 U	< 0.0025 U	< 0.0021 U	< 0.0045 U	< 0.0047 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated	< 0.0034 U	< 0.003 U	< 0.0067 U	< 0.0037 U	< 0.0094 U	< 0.0034 U	< 0.0046 U	< 0.003 U	< 0.0059 U	< 0.0021 U	< 0.0048 U	< 0.0032 U	< 0.0027 U	< 0.0057 U	< 0.0059 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0043 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-0.17-2	9/4/2019	855.15	0.17 - 2 ft	180-95165-1	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-0.17-2	9/3/2019	855.98	0.17 - 2 ft	180-95155-3	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-0.17-2	9/3/2019	856.41	0.17 - 2 ft	180-95155-3	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-0.17-2	8/29/2019	856.01	0.17 - 2 ft	180-95024-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 002 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-0.17-2	8/29/2019	856.20	0.17 - 2 ft	180-95006-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-0.17-2	8/29/2019	855.88	0.17 - 2 ft	180-94981-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 002 U	< 0.0026 U	< 0.0047 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-0.17-2	8/28/2019	856.09	0.17 - 2 ft	180-94900-3	Excavated	< 0.0031 U	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-0.17-2	8/28/2019	856.47	0.17 - 2 ft	180-94902-2	Excavated	< 0.0021 U	< 0.002 U	< 0.0013 U	< 0.0012 U	< 0.0031 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-0.17-2	8/28/2019	856.71	0.17 - 2 ft	180-94902-1	Excavated	< 0.0027 UJ	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3060	SSHS-B3060-SUB-0.17-2	8/28/2019	856.96	0.17 - 2 ft	180-94900-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-0.17-2	8/27/2019	857.02	0.17 - 2 ft	180-94824-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 UJ	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-0.17-2	8/27/2019	856.91	0.17 - 2 ft	180-94819-3	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.003 U	< 0.0052 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-0.17-2	8/27/2019	856.95	0.17 - 2 ft	180-94819-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94754-1	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-0.17-2	8/26/2019	856.77	0.17 - 2 ft	180-94752-3	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-0.17-2	9/4/2019	855.86	0.17 - 2 ft	180-95165-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-0.17-2	9/3/2019	856.40	0.17 - 2 ft	180-95162-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-0.17-2	8/30/2019	856.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-0.17-2	8/28/2019	856.76	0.17 - 2 ft	180-94900-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-27	8/28/2019	857.14	0.17 - 2 ft	180-94903-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U		< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	8/28/2019	857.14	0.17 - 2 ft	180-94900-1	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U		< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-0.17-2	8/27/2019	857.18	0.17 - 2 ft	180-94824-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-0.17-2	8/27/2019	856.92	0.17 - 2 ft	180-94819-2	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-0.17-2	8/26/2019	856.86	0.17 - 2 ft	180-94752-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-0.17-2	8/29/2019	856.36	0.17 - 2 ft	180-95024-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-0.17-2	9/4/2019	856.58	0.17 - 2 ft	180-95165-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-0.17-2	9/4/2019	856.96	0.17 - 2 ft	180-95165-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-0.17-2	8/30/2019	856.73	0.17 - 2 ft	180-95047-3	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-0.17-2	8/29/2019	857.13	0.17 - 2 ft	180-95024-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-0.17-2	8/29/2019	856.55	0.17 - 2 ft	180-95006-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.005 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-0.17-2	9/4/2019	857.12	0.17 - 2 ft	180-95165-3	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-0.17-2	9/4/2019	857.77	0.17 - 2 ft	180-95165-2	Excavated	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.005 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-0.17-2	8/30/2019	857.68	0.17 - 2 ft	180-95047-2	Excavated	< 0.0032 U	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0047 U	< 0.0024 U	< 0.0031 U	< 0.0055 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-0.17-2	8/28/2019	857.12	0.17 - 2 ft	180-94902-1	Excavated	< 0.0021 UJ	< 0.002 U	< 0.0012 U	< 0.0012 U	< 0.003 U	< 0.0016 U	< 0.002 U	< 0.0036 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-0.17-2	8/27/2019	855.86	0.17 - 2 ft	180-94819-3	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-0.17-2	8/27/2019	856.19	0.17 - 2 ft	180-94819-3	Excavated	< 0.0035 U	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0051 U	< 0.0026 U	< 0.0034 U	< 0.0059 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-0.17-2	8/26/2019	855.97	0.17 - 2 ft	180-94754-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-0.17-2	8/26/2019	856.40	0.17 - 2 ft	180-94754-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3100	DUP-01	1/13/2020	856.74	0.17 - 2 ft	180-100985-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	1/13/2020	856.74	0.17 - 2 ft	180-100985-1	Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U		< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3101	DUP-02	1/13/2020	856.75	0.17 - 2 ft	180-100985-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	1/13/2020	856.75	0.5 - 2 ft	180-100985-1	Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U		< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-0.17-2	1/13/2020	856.74	0.5 - 2 ft	180-100985-1	Excavated	< 0.0026 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U		< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-0.17-2	1/13/2020	856.47	0.17 - 2 ft	180-100985-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3104	DUP-04	1/13/2020	856.82	0.17 - 2 ft	180-100985-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-0.5-2	1/13/2020	856.82	0.5 - 2 ft	180-100985-2	Excavated	< 0.0028 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-0.17-2	1/14/2020	856.73	0.5 - 2 ft	180-101038-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-0.17-2	1/14/2020	856.72	0.5 - 2 ft	180-101038-1	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-0.17-2	1/15/2020	857.05	0.17 - 2 ft	180-101084-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-0.17-2	1/14/2020	857.55	0.17 - 2 ft	180-101038-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-0.17-2	1/15/2020	857.26	0.17 - 2 ft	180-101084-2	Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-0.17-2	1/15/2020	856.32	0.17 - 2 ft	180-101084-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-0.17-2	1/15/2020	857.08	0.17 - 2 ft	180-101084-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-0.17-2	1/15/2020	856.71	0.17 - 2 ft	180-101084-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-0.17-2	1/14/2020	856.36	0.17 - 2 ft	180-101038-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	0.17 - 2 ft	180-101084-3	Not Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-0.17-2	8/29/2019	857.57	0.17 - 2 ft	180-95006-3	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-0.17-2	8/29/2019	857.45	0.17 - 2 ft	180-95024-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-0.5-2	1/14/2020	856.70	0.5 - 2 ft	180-101038-1	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-0.17-2	1/14/2020	856.85	0.17 - 2 ft	180-101038-2	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-0.17-2	8/30/2019	855.06	0.17 - 2 ft	180-95050-1	Excavated	< 0.0035 U	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0052 U	< 0.0026 U	< 0.0034 U	< 0.0061 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-0.17-2	9/4/2019	857.44	0.17 - 2 ft	180-95165-3	Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-0.17-2	9/4/2019	857.92	0.17 - 2 ft	180-95165-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-0.17-2	8/30/2019	858.28	0.17 - 2 ft	180-95047-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-0.17-2	8/29/2019	858.27	0.17 - 2 ft	180-95006-2	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.003 U	< 0.0052 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-0.17-2	8/30/2019	858.38	0.17 - 2 ft	180-95050-1	Excavated	< 0.0032 U	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0047 U	< 0.0024 U	< 0.0031 U	< 0.0055 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-0.17-2	12/20/2019	853.22	0.17 - 2 ft	180-100362-1	Excavated	< 0.004 U	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0059 U	< 0.003 U	< 0.0039 U	< 0.0069 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-0.17-2	7/27/2020	856.30	0.17 - 2 ft	180-108826-2	Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-0.17-2	7/27/2020	856.51	0.17 - 2 ft	180-108826-2	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-0.17-2	7/27/2020	856.28	0.17 - 2 ft	180-108826-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 UJ	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	0.17 - 2 ft	180-108826-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 UJ	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B3473	DUP15	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3473	DUP06	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	0.0098 J	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/4/2021	856.70	0.17 - 2 ft	180-116864-1	Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3596	DUP-37	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3596	SSHS-B3596-SUB-0.17-2	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.004 U
Football Field	SSHS-B3597	SSHS-B3597-SUB-0.17-2	2/4/2021	855.28	0.17 - 2 ft	180-116864-1	Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 UJ
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B36	12 Sep 00B36 0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.021 U	< 0.0053 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	0.0069 J	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-B37	12 Sep 00B37 0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.021 U	< 0.0052 U		< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		
Northern Athletic Field	SSHS-B38	12 Sep 00B38 1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	< 0.022 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.0048 U	< 0.00028 U	< 0.00041 U	< 0.00077 U	< 0.0029 U	< 0.00052 U	< 0.0029 U	< 0.00056 U	< 0.00076 U	< 0.00073 U	< 0.0013 U	< 0.00035 U	< 0.00035 U	< 0.0008 U	< 0.0029 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		
Northern Athletic Field	SSHS-B39	12 Sep 00B39 0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	< 0.022 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B40	12 Sep 00B40 0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	< 0.022 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated	< 0.0045 UJ	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated	< 0.0043 UJ	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.024	< 0.0059		< 0.0059	< 0.0059	< 0.0059	< 0.012	< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059		
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	< 0.022	< 0.0056		< 0.0056	< 0.0056	< 0.0056	< 0.011	< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056		
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.025	< 0.0062		< 0.0062	< 0.0062	< 0.0062	< 0.012	< 0.0062	< 0.0062	< 0.0062	< 0.0062	< 0.0062	0.0015	< 0.0062	
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	< 0.023	< 0.0057		< 0.0057	< 0.0057	< 0.0057	< 0.011	< 0.0057	< 0.0057	< 0.0057	< 0.0057	< 0.0057	< 0.0057	< 0.0057	
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-0.17-2	11/1/2021	852.29	0.17 - 2 ft	180-129325-1	Excavated	< 0.023 U	< 0.00076 U	< 0.0013 U	< 0.0016 U	< 0.0026 U	< 0.0045 U	< 0.0013 U	< 0.0035 U	< 0.001 U	< 0.003 U	< 0.003 U	< 0.00086 U	< 0.0025 U	< 0.0015 U	< 0.0039 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.022	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.011	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	< 0.024	< 0.006		< 0.006	< 0.006	< 0.006	< 0.012	< 0.006	< 0.006	< 0.006	< 0.006	< 0.006	< 0.006		
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0064		< 0.0064	< 0.0064	< 0.0064	< 0.013	< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064		
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	< 0.022	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.011	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0065		< 0.0065	< 0.0065	< 0.0065	0.0014	< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065		
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.022	< 0.0056		< 0.0056	< 0.0056	< 0.0056	< 0.011	< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056		
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.013	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.022	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.011	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.026	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.013	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.023	< 0.0058		< 0.0058	< 0.0058	< 0.0058	< 0.012	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058		
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.027	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.013	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.025 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		
Northern Athletic Field	SSHS-B50	13 Sep 00B50 0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	0.0087 J	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.022 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-B51	13 Sep 00B51 0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 0.022 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.028 U	< 0.0069 U	< 0.0069 U		< 0.0069 U	< 0.0069 U	< 0.014 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.022 U	< 0.0054 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-B53	13 Sep 00B53 0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.022 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	< 0.023 U	< 0.0059 U		< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U		
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.007 U		< 0.007 U	< 0.007 U	< 0.007 U	< 0.014 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	0.0083	< 0.007 U		
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated															
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.024 U	< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	< 0.012 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U		
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.022 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	< 0.022 U	< 0.0055 U						< 0.0055 U	< 0.0055 U			0.0013 J			
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.0042 U	< 0.00056 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.0013 U	< 0.00049 U	< 0.00071 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U	< 0.0007 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00069 U

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	0.0071 J	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3473	DUP06	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.015	< 0.0016 U	< 0.0029 UJ	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.0097	< 0.0016 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	0.0067	< 0.0016 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	0.012	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/4/2021	856.70	0.17 - 2 ft	180-116864-1	Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3596	DUP-37	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3596	SSHS-B3596-SUB-0.17-2	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3597	SSHS-B3597-SUB-0.17-2	2/4/2021	855.28	0.17 - 2 ft	180-116864-1	Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.0057 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36_0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.0053 U			< 0.35 U	< 0.35 U	< 0.35 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.0056 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37_0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.0052 U			< 0.34 U	< 0.34 U	< 0.34 U	< 0.0052 U	< 0.0052 U	< 0.0052 U		< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0058 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38_1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	< 0.0056 U			< 1.8 U	< 1.8 U	< 1.8 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.0026 U	< 0.00074 U	< 0.00047 U	< 0.00045 U	< 0.0003 U	< 0.0008 U	< 0.0007 U	< 0.00029 U	< 0.0007 U	< 0.003 U	< 0.00073 U	< 0.00059 U	< 0.0029 U	< 0.00083 U	< 0.0025 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0063 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39_0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	< 0.0054 U			< 1.8 U	< 1.8 U	< 1.8 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B40	12 Sep 00B40_0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	< 0.0056 U			< 1.9 U	< 1.9 U	< 1.9 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.0062 U			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.0059			< 0.39	< 0.39	< 0.39	< 0.0059	< 0.0059	< 0.0059		< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	< 0.0056			< 0.37	< 0.37	< 0.37	< 0.0056	< 0.0056	< 0.0056		< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.0062			< 0.41	< 0.41	< 0.41	< 0.0062	< 0.0062	< 0.0062		< 0.0062	< 0.0062	< 0.0062	< 0.0062	< 0.0062
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	< 0.0057			< 0.75	< 0.75	< 0.75	< 0.0057	< 0.0057	< 0.0057		< 0.0057	< 0.0057	< 0.0057	< 0.0057	< 0.0057
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-0.17-2	11/1/2021	852.29	0.17 - 2 ft	180-129325-1	Excavated	< 0.013 U	< 0.00084 U	< 0.001 U	< 0.0012 U	< 0.00089 U	< 0.00096 U	< 0.00075 U	< 0.00084 U	< 0.002 U	< 0.0012 U	< 0.0016 U	< 0.0015 U	< 0.00093 U	< 0.0031 U	< 0.004 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0055			< 0.37	< 0.37	< 0.37	< 0.0055	< 0.0055	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	< 0.006			< 0.4	< 0.4	< 0.4	< 0.006	< 0.006	< 0.006		< 0.006	< 0.006	< 0.006	< 0.006	< 0.006
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0064			< 0.42	< 0.42	< 0.42	< 0.0064	< 0.0064	< 0.0064		< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	< 0.0055			< 0.36	< 0.36	< 0.36	< 0.0055	< 0.0055	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.0065			< 0.43	< 0.43	< 0.43	< 0.0065	< 0.0065	< 0.0065		< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.0056			< 0.37	< 0.37	< 0.37	< 0.0056	< 0.0056	< 0.0056		< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0066			< 0.43	< 0.43	< 0.43	< 0.0066	< 0.0066	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.0055			< 0.37	< 0.37	< 0.37	< 0.0055	< 0.0055	< 0.0055		< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.0066			< 0.43	< 0.43	< 0.43	< 0.0066	< 0.0066	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.0058			< 0.38	< 0.38	< 0.38	< 0.0058	< 0.0058	< 0.0058		< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0066			< 0.44	< 0.44	< 0.44	< 0.0066	< 0.0066	< 0.0066		< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0063 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Northern Athletic Field	SSHS-B50	13 Sep 00B50_0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0056 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51_0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 0.0055 U			< 1.8 U	< 1.8 U	< 1.8 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.0069 U			< 0.46 U	< 0.46 U	< 0.46 U	< 0.0069 U	< 0.0069 U	< 0.0069 U		< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52_0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.0054 U			< 0.36 U	< 0.36 U	< 0.36 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 0.44 U	< 0.44 U	< 0.44 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53_0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.0055 U			< 0.36 U	< 0.36 U	< 0.36 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 0.44 U	< 0.44 U	< 0.44 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54_0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	< 0.0059 U			< 1.9 U	< 1.9 U	< 1.9 U	< 0.0059 U	< 0.0059 U	< 0.0059 U		< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.007 U			< 0.46 U	< 0.46 U	< 0.46 U	< 0.007 U	< 0.007 U	< 0.007 U		< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated															
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0057 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.006 U			< 0.39 U	< 0.39 U	< 0.39 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.0054 U			< 0.36 U	< 0.36 U	< 0.36 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	< 0.0055 U			< 0.36 U	< 0.36 U	< 0.36 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.0055 U	< 0.0055 U				
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.00056 U	< 0.00072 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00053 U	< 0.00048 U	< 0.00051 U	< 0.00071 U		< 0.00059 U	< 0.0005 U	< 0.00045 U	< 0.00057 U	< 0.0005 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00058 U	< 0.00053 U	< 0.00056 U	< 0.00078 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0034 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B3473	DUP06	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0045 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/4/2021	856.70	0.17 - 2 ft	180-116864-1	Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3596	DUP-37	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3596	SSHS-B3596-SUB-0.17-2	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.009 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3597	SSHS-B3597-SUB-0.17-2	2/4/2021	855.28	0.17 - 2 ft	180-116864-1	Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	0.011	< 0.0057 U		< 0.37 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.0053 U	< 0.0053 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		< 0.35 U
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.0056 U	0.0027 J	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	0.016	< 0.0056 U		< 0.37 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.0052 U	< 0.0052 U	< 0.01 U				< 0.01 U	< 0.01 U		< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U		< 0.34 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0058 U	< 0.0058 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.38 U
Northern Athletic Field	SSHS-B38	12 Sep 00B38 1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 1.8 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.0004 U	< 0.0013 U	< 0.0029 U	< 0.00087 U	< 0.0035 U	< 0.00087 U	< 0.0021 U	< 0.0019 U	< 0.00056 U	< 0.00029 U	< 0.00093 U	< 0.00077 U	< 0.00043 U	< 0.00061 U	< 0.00035 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.42 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	< 0.0054 U	< 0.0054 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 1.8 U
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B40	12 Sep 00B40 0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 1.9 U
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.0062 U	< 0.0062 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		< 0.41 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.0022 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 UJ	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 UJ	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.0059	< 0.0059	< 0.012				< 0.012	< 0.012		< 0.0059	< 0.0059	< 0.0059	< 0.0059		< 0.39
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	< 0.0056	< 0.0056	< 0.011				< 0.011	< 0.011		< 0.0056	< 0.0056	< 0.0056	< 0.0056		< 0.37
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 UJ
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.0062	< 0.0062	< 0.012				< 0.012	< 0.012		< 0.0062	< 0.0062	< 0.0062	< 0.0062		< 0.41
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	< 0.0057	< 0.0057	< 0.011				< 0.011	< 0.011		< 0.0057	< 0.0057	< 0.0057	< 0.0057		< 0.75
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-0.17-2	11/1/2021	852.29	0.17 - 2 ft	180-129325-1	Excavated	< 0.0011 U	< 0.0014 U	< 0.0044 U	< 0.0021 U	< 0.0037 U	< 0.0013 U	< 0.0039 U	< 0.004 U	< 0.0022 U	< 0.0013 U	< 0.0016 U	< 0.00079 U	< 0.00084 U	< 0.0032 U	< 0.0027 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.011				< 0.011	< 0.011		< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.37
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	< 0.006	< 0.006	< 0.012				< 0.012	< 0.012		< 0.006	< 0.006	< 0.006	< 0.006		< 0.4
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0064	< 0.0064	< 0.013				< 0.013	< 0.013		< 0.0064	< 0.0064	< 0.0064	< 0.0064		< 0.42
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.011				< 0.011	< 0.011		< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.36
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.0065	< 0.0065	< 0.013				< 0.013	< 0.013		< 0.0065	< 0.0065	< 0.0065	< 0.0065		< 0.43
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.0056	< 0.0056	< 0.011				< 0.011	< 0.011		< 0.0056	< 0.0056	< 0.0056	< 0.0056		< 0.37
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.013				< 0.013	< 0.013		< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.43
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.011				< 0.011	< 0.011		< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.37
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.013				< 0.013	< 0.013		< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.43
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.012				< 0.012	< 0.012		< 0.0058	< 0.0058	< 0.0058	< 0.0058		< 0.38
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.013				< 0.013	< 0.013		< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.44
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U		< 0.42 U
Northern Athletic Field	SSHS-B50	13 Sep 00B50 0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.37 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.37 U
Northern Athletic Field	SSHS-B51	13 Sep 00B51 0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 1.8 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.0069 U	< 0.0069 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U		< 0.46 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.0054 U	< 0.0054 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.36 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.44 U
Northern Athletic Field	SSHS-B53	13 Sep 00B53 0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.36 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.44 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	< 0.0059 U	< 0.0059 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U		< 1.9 U
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.38 U
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.007 U	0.0017 J	< 0.014 U				< 0.014 U	< 0.014 U		< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U		< 0.46 U
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated		0.0023										0.0018			
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.38 U
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.38 U
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.006 U	< 0.006 U	< 0.012 U				< 0.012 U	< 0.012 U		< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.39 U
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.0054 U	< 0.0054 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.36 U
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	< 0.0055 U						< 0.011 U					0.0086	< 0.055 U		
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.00054 U	< 0.00089 U	< 0.00058 U	< 0.00057 U	< 0.00075 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.00059 U	< 0.00098 U	< 0.00063 U	< 0.00062 U	< 0.00083 U	< 0.00067 U	< 0.00081 U	< 0.0006 U	< 0.00069 U	< 0.00065 U	< 0.00066 U	< 0.00062 U	< 0.00067 U	< 0.00078 U	< 0.00081 U

DRAFT

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-2	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B3473	DUP06	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-0.17-2	7/30/2020	855.34	0.17 - 2 ft	180-108931-1	Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	0.17 - 2 ft	180-108826-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3494	DUP-19	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-0.17-2	1/26/2021	858.31	0.17 - 2 ft	180-116462-2	Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-0.17-2	1/26/2021	858.30	0.17 - 2 ft	180-116462-2	Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2	1/26/2021	858.38	0.17 - 2 ft	1801164622	Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-0.17-2	2/4/2021	856.70	0.17 - 2 ft	180-116864-1	Excavated	< 0.0019 U	< 0.0011 U	0.009	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3596	DUP-37	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.0019 U	< 0.0011 U	0.0035 J	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3596	SSHS-B3596-SUB-0.17-2	2/4/2021	855.23	0.17 - 2 ft	180-116864-1	Excavated	< 0.002 U	< 0.0012 U	0.0044 J	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	SSHS-B3597	SSHS-B3597-SUB-0.17-2	2/4/2021	855.28	0.17 - 2 ft	180-116864-1	Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B36	12 Sep 00B36 -	9/12/2000	856.63	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B36	12 Sep 00B36 0.5-2.5	9/12/2000	856.63	0.5 - 2.5 ft	NA	Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2	2/2/2021	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 -	9/12/2000	856.46	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-B37	12 Sep 00B37 0.5-2.5	9/12/2000	856.46	0.5 - 2.5 ft	NA	Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	
Northern Athletic Field	SSHS-B38	12 Sep 00B38 -	9/12/2000	856.64	0 - 0.5 ft	NA	Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	
Northern Athletic Field	SSHS-B38	12 Sep 00B38 1-4.5	9/12/2000	856.64	0.5 - 5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-0.17-2	9/16/2021	856.07	0.17 - 2 ft	180-127205-2	Excavated	< 0.00042 U	< 0.00075 U	< 0.0013 U	< 0.00054 U	< 0.0007 U	< 0.00096 U	< 0.00075 U	< 0.00096 U
Northern Athletic Field	SSHS-B39	12 Sep 00B39 -	9/12/2000	856.78	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	
Northern Athletic Field	SSHS-B39	12 Sep 00B39 0.5-2.5	9/12/2000	856.78	0.5 - 2.5 ft	NA	Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	
Northern Athletic Field	SSHS-B3917	DUP-39	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2	5/12/2021	853.71	0.17 - 2 ft	1801215482	Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	0 - 2 ft	-	Not Excavated				0.0051 J				
Northern Athletic Field	SSHS-B40	12 Sep 00B40 0.5-2.5	9/12/2000	856.91	0.5 - 2.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-B40	12 Sep 00B40 -	9/12/2000	856.91	0 - 0.5 ft	NA	Excavated	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1	7/1/2021	857.47	0.17 - 1 ft	1801239851	Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2	7/1/2021	857.47	1 - 2 ft	1801239851	Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-0.17-1	7/1/2021	856.76	0.17 - 1 ft	180-123985-1	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-1-2	7/1/2021	856.76	1 - 2 ft	180-123985-1	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-B41	B41	9/12/2000	857.21	0 - 0.5 ft	NA	Excavated	< 0.0059	< 0.0059	< 0.0059	< 0.0059	< 0.0059		< 0.0059	
Northern Athletic Field	SSHS-B41	B41-0.5-2.5	9/12/2000	857.21	0.5 - 2.5 ft	NA	Excavated	< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056		< 0.0056	
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	0.17 - 2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Northern Athletic Field	SSHS-B42	B42	9/12/2000	856.22	0 - 0.5 ft	NA	Excavated	< 0.0062	< 0.0062	< 0.0062	< 0.0062	< 0.0062		< 0.0062	
Northern Athletic Field	SSHS-B42	B42-0.5-2.5	9/12/2000	856.22	0.5 - 2.5 ft	NA	Excavated	< 0.0057	< 0.0057	< 0.0057	< 0.0057	< 0.0057		< 0.0057	
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-0.17-2	11/1/2021	852.29	0.17 - 2 ft	180-129325-1	Excavated	< 0.0019 U	< 0.0012 U	0.00098 J	< 0.0029 U	< 0.0019 U	< 0.00085 U	< 0.00094 U	< 0.0017 U
Northern Athletic Field	SSHS-B43	B43	9/12/2000	856.12	0 - 0.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.0055	
Northern Athletic Field	SSHS-B43	B43-0.5-2.5	9/12/2000	856.12	0.5 - 2.5 ft	NA	Excavated	< 0.006	< 0.006	< 0.006	< 0.006	< 0.006		< 0.006	
Northern Athletic Field	SSHS-B44	B44	9/13/2000	856.39	0 - 0.5 ft	NA	Excavated	< 0.0064	< 0.0064	< 0.0064	< 0.0064	< 0.0064		< 0.0064	
Northern Athletic Field	SSHS-B44	B44-0.5-2.5	9/13/2000	856.39	0.5 - 2.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.0055	
Northern Athletic Field	SSHS-B45	B45	9/13/2000	857.89	0 - 0.5 ft	NA	Excavated	< 0.0065	< 0.0065	< 0.0065	< 0.0065	< 0.0065		< 0.0065	
Northern Athletic Field	SSHS-B45	B45-0.5-2.5	9/13/2000	857.89	0.5 - 2.5 ft	NA	Excavated	< 0.0056	< 0.0056	< 0.0056	< 0.0056	< 0.0056		< 0.0056	
Northern Athletic Field	SSHS-B46	B46	9/13/2000	858.24	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.0066	
Northern Athletic Field	SSHS-B46	B46-0.5-2.5	9/13/2000	858.24	0.5 - 2.5 ft	NA	Excavated	< 0.0055	< 0.0055	< 0.0055	< 0.0055	< 0.0055		< 0.0055	
Northern Athletic Field	SSHS-B47	B47	9/13/2000	856.71	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.0066	
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	0.5 - 2.5 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058		< 0.0058	
Northern Athletic Field	SSHS-B48	B48	9/13/2000	855.11	0 - 0.5 ft	NA	Excavated	< 0.0066	< 0.0066	< 0.0066	< 0.0066	< 0.0066		< 0.0066	
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	0 - 2 ft	NA	Not Excavated			< U					
Northern Athletic Field	SSHS-B50	13 Sep 00B50 -	9/13/2000	854.58	0 - 0.5 ft	NA	Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	
Northern Athletic Field	SSHS-B50	13 Sep 00B50 0.5-2.5	9/13/2000	854.58	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B51	13 Sep 00B51 -	9/13/2000	854.29	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-B51	13 Sep 00B51 0.5-2.5	9/13/2000	854.29	0.5 - 2.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	0.032	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	
Northern Athletic Field	SSHS-B52	13 Sep 00B52 -	9/13/2000	855.39	0 - 0.5 ft	-	Excavated	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	< 0.0069 U	
Northern Athletic Field	SSHS-B52	13 Sep 00B52 0.5-2.5	9/13/2000	855.39	0.5 - 2.5 ft	-	Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	
Northern Athletic Field	SSHS-B53	13 Sep 00B53 -	9/13/2000	855.37	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-B53	13 Sep 00B53 0.5-2.5	9/13/2000	855.37	0.5 - 2.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	
Northern Athletic Field	SSHS-B54	13 Sep 00B54 -	9/13/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-B54	13 Sep 00B54 0.5-2.5	9/13/2000	855.33	0.5 - 2.5 ft	NA	Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	
Northern Athletic Field	SSHS-B55	B55-0.5-2.5	9/13/2000	852.39	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B55	B55	9/13/2000	852.39	0 - 0.5 ft	NA	Excavated	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	< 0.007 U	
Northern Athletic Field	SSHS-B57	B57	9/13/2000	852.42	0 - 0.5	NA	Excavated								
Northern Athletic Field	SSHS-B58	B58	9/13/2000	852.33	0 - 0.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B58	B58-0.5-2.5	9/13/2000	852.33	0.5 - 2.5 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B59	B59	9/13/2000	852.46	0 - 0.5 ft	NA	Excavated	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	< 0.006 U	
Northern Athletic Field	SSHS-B59	B59-0.5-2.5	9/13/2000	852.46	0.5 - 2.5 ft	NA	Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	0 - 2.5 ft	NA	Not Excavated			0.0051 J					
Football Field	SSHS-B6	B23486	5/11/2000	855.49	1 - 3 ft	NA	Excavated	< 0.055 U		0.0014 J		< 0.055 U	< 0.055 U	< 0.055 U	
Rear Parking Lot	SSHS-B64	SSHS-B64-0.17-2 (1)	8/14/2014	851.65	0 - 2 ft	180-35818-2	Excavated	< 0.00041 U	< 0.00069 U	< 0.00055 U	< 0.00077 U	< 0.00039 U	< 0.0012 U	< 0.00065 U	
Rear Parking Lot	SSHS-B65	SSHS-B65-0.17-2 (1)	8/14/2014	850.41	0 - 2 ft	180-35818-1	Excavated	< 0.00045 U	< 0.00076 U	< 0.0006 U	< 0.00084 U	< 0.00043 U	< 0.0013 U	< 0.00072 U	

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.0047 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00069 U	< 0.00048 U	< 0.00042 U	< 0.00071 U	< 0.00066 U	< 0.0014 U	< 0.00054 U	< 0.00079 U	< 0.00035 U	< 0.0007 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.0055 U	< 0.00075 U	< 0.00076 U	< 0.00062 U	< 0.00049 U	< 0.00082 U	< 0.00057 U	< 0.00049 U	< 0.00084 U	< 0.00079 U	< 0.0017 U	< 0.00065 U	< 0.00094 U	< 0.00041 U	< 0.00083 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.0051 U	< 0.00069 U	< 0.0007 U	< 0.00057 U	< 0.00045 U	< 0.00076 U	< 0.00052 U	< 0.00046 U	< 0.00077 U	< 0.00073 U	< 0.0016 U	< 0.0006 U	< 0.00087 U	< 0.00038 U	< 0.00077 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	< 0.0059 U	< 0.0008 U	< 0.00082 U	< 0.00067 U	< 0.00053 U	< 0.00088 U	< 0.00061 U	< 0.00053 U,*	< 0.0009 U	< 0.00084 U	< 0.0018 U	< 0.0007 U	< 0.001 U	< 0.00044 U	< 0.00089 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	0.0061	< 0.00072	< 0.00073	< 0.00059	< 0.00047	< 0.00078	< 0.00054	< 0.00047	< 0.0008	< 0.00075	< 0.0016	< 0.00062	< 0.0009	< 0.00039	< 0.00079
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 0.0055	< 0.00074	< 0.00076	< 0.00062	< 0.00049	< 0.00081	< 0.00056	< 0.00049	< 0.00083	< 0.00078	< 0.0017	< 0.00064	< 0.00094	< 0.00041	< 0.00082
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.0047	< 0.00064	< 0.00065	< 0.00053	< 0.00042	< 0.0007	< 0.00048	< 0.00042	< 0.00071	< 0.00067	< 0.0015	< 0.00055	< 0.0008	< 0.00035	< 0.00071
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0049	< 0.00066	< 0.00067	< 0.00055	< 0.00043	< 0.00072	< 0.0005	< 0.00044	< 0.00074	< 0.00069	< 0.0015	< 0.00057	< 0.00083	< 0.00036	< 0.00073
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.0053 U	< 0.00072 U	< 0.00073 U	< 0.0006 U	< 0.00047 U	< 0.00079 U	< 0.00055 U	< 0.00048 U	< 0.00081 U	< 0.00076 U	< 0.0017 U	< 0.00062 U	< 0.00091 U	< 0.0004 U	< 0.0008 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated															
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0052 U	< 0.0007 U	< 0.00071 U	< 0.00058 U	< 0.00046 U	< 0.00076 U	< 0.00053 U	< 0.00046 U	< 0.00078 U	< 0.00073 U	< 0.0016 U	< 0.0006 U	< 0.00088 U	< 0.00038 U	< 0.00077 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	0.0079 J	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00043 U	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0053 U	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0046 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U	< 0.0007 U	< 0.00066 U	< 0.0014 U	< 0.00054 U	< 0.00079 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.005 U	< 0.00067 U	< 0.00068 U	< 0.00056 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0056 U	< 0.00076 U	< 0.00078 U	< 0.00063 U	< 0.0005 U	< 0.00083 U	< 0.00058 U	< 0.0005 U	< 0.00086 U	< 0.0008 U	< 0.0017 U	< 0.00066 U	< 0.00096 U	< 0.00042 U	< 0.00085 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0055 U	< 0.00074 U	< 0.00076 U	< 0.00062 U	< 0.00049 U	< 0.00081 U	< 0.00056 U	< 0.00049 U	< 0.00083 U	< 0.00078 U	< 0.0017 U	< 0.00064 U	< 0.00093 U	< 0.00041 U	< 0.00082 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.0005 U	< 0.0004 U	< 0.00066 U	< 0.00046 U	< 0.0004 U	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00052 U	< 0.00076 U	< 0.00033 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0051 U	< 0.00069 U	< 0.00071 U	< 0.00058 U	< 0.00046 U	< 0.00076 U	< 0.00053 U	< 0.00046 U	< 0.00078 U	< 0.00073 U	< 0.0016 U	< 0.0006 U	< 0.00088 U	< 0.00038 U	< 0.00077 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0044 U	< 0.00059 U	< 0.0006 U	< 0.00049 U	< 0.00039 U	< 0.00064 U	< 0.00045 U	< 0.00039 U	< 0.00066 U	< 0.00062 U	< 0.0014 U	< 0.00051 U	< 0.00074 U	< 0.00032 U	< 0.00065 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U,*	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U,*	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated															
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	0.0064 J	< 0.0057 U						< 0.0057 U	< 0.0057 U			< 0.0057 U			
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	0.0089 J	< 0.006 U						< 0.006 U	< 0.006 U			< 0.006 U			
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.029 U	< 0.0072 U						< 0.0072 U	< 0.0072 U			< 0.0072 U			
Football Field	SSHS-FB5	B23407T3	8/14/2000	855.33	1 - 1.5 ft	NA	Excavated	< 0.024 U	< 0.006 U						< 0.006 U	< 0.006 U			< 0.006 U			
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0069 U						< 0.0069 U	< 0.0069 U			< 0.0069 U			
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.03 U	< 0.0074 U						< 0.0074 U	< 0.0074 U			< 0.0074 U			
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-1.5	7/21/2014	855.47	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.0059 U	< 0.00079 U	< 0.00081 U	< 0.00066 U	< 0.00052 U	< 0.00087 U	< 0.0006 U	< 0.00052 U	< 0.00089 U	< 0.00083 U	< 0.0018 U	< 0.00069 U	< 0.001 U	< 0.00043 U	< 0.00088 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-1.5	7/21/2014	855.39	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.0047 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00069 U	< 0.00048 U	< 0.00042 U	< 0.00071 U	< 0.00066 U	< 0.0014 U	< 0.00055 U	< 0.00079 U	< 0.00035 U	< 0.0007 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-1.5	7/21/2014	855.97	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.0056 U	< 0.00076 U	< 0.00078 U	< 0.00063 U	< 0.0005 U	< 0.00083 U	< 0.00058 U	< 0.0005 U	< 0.00085 U	< 0.0008 U	< 0.0017 U	< 0.00066 U	< 0.00096 U	< 0.00042 U	< 0.00084 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-1.5	7/21/2014	855.49	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.0037 U	< 0.0005 U	< 0.00051 U	< 0.00041 U	< 0.00033 U	< 0.00054 U	0.00065 J	< 0.00033 U	< 0.00056 U	< 0.00052 U	< 0.0011 U	< 0.00043 U	< 0.00063 U	< 0.00027 U	< 0.00055 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-1.5	7/21/2014	855.42	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.005 U	< 0.00067 U	< 0.00069 U	< 0.00056 U	< 0.00044 U	< 0.00074 U	< 0.00051 U	< 0.00044 U	< 0.00075 U	< 0.00071 U	< 0.0015 U	< 0.00058 U	< 0.00085 U	< 0.00037 U	< 0.00075 U
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	< 0.024 U	< 0.006 U						< 0.006 U	< 0.006 U			0.0018 J			
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated															
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated															
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	< 0.024 U	< 0.0061 U						< 0.0061 U	< 0.0061 U			< 0.0061 U			
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	0.17	0.0013 J						< 0.0056 U	< 0.0056 U			0.0025 J			
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	< 0.025 U	< 0.0062 U						< 0.0062 U	< 0.0062 U			< 0.0062 U			
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.03 U	< 0.0076 U						< 0.0076 U	< 0.0076 U			< 0.0076 U			
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			< 0.0065 U			
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0067 U						< 0.0067 U	< 0.0067 U			< 0.0067 U			
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.022 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.022 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.0071 U						< 0.0071 U	< 0.0071 U			< 0.0071 U			
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			< 0.0065 U			
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0066 U						< 0.0066 U	< 0.0066 U			< 0.0066 U			
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.007 U						< 0.007 U	< 0.007 U			< 0.007 U			
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.026 U	< 0.0065 U						< 0.0065 U	< 0.0065 U			0.0021 J			
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.014 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.028 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.014 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	0.011 J	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.029 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.014 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.027 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.014 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.00063 U	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00054 U	< 0.00057 U	< 0.00079 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00063 U	< 0.00056 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.00074 U	< 0.00095 U	< 0.00074 U	< 0.00088 U	< 0.0073 U	< 0.0007 U	< 0.00064 U	< 0.00068 U	< 0.00094 U		< 0.00078 U	< 0.00066 U	< 0.0006 U	< 0.00075 U	< 0.00066 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.00069 U	< 0.00088 U	< 0.00068 U	< 0.00082 U	< 0.00067 U	< 0.00065 U	< 0.00059 U	< 0.00063 U	< 0.00087 U		< 0.00072 U	< 0.00061 U	< 0.00056 U	< 0.00069 U	< 0.00061 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00048 U	< 0.00052 U	< 0.00071 U		< 0.00059 U	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.0005 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B70	081514 01:15 SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	< 0.0008 U	< 0.001 U	< 0.00079 U	< 0.00095 U	< 0.00078 U	< 0.00076 U	< 0.00068 U	< 0.00073 U	< 0.001 U		< 0.00084 U	< 0.00071 U,*	< 0.00065 U	< 0.00081 U	< 0.00071 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	< 0.00071	< 0.00091	< 0.00071	< 0.00085	< 0.0007	< 0.00068	< 0.00061	< 0.00065	< 0.0009		< 0.00075	< 0.00063	< 0.00058	< 0.00072	< 0.00063
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 0.00074	< 0.00095	< 0.00073	< 0.00088	< 0.00072	< 0.0007	< 0.00063	< 0.00067	< 0.00093		< 0.00077	< 0.00066	< 0.0006	< 0.00075	< 0.00066
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.00063	< 0.00081	< 0.00063	< 0.00075	< 0.00062	< 0.0006	< 0.00054	< 0.00058	< 0.0008		< 0.00066	< 0.00056	< 0.00051	< 0.00064	< 0.00056
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00066	< 0.00084	< 0.00065	< 0.00078	< 0.00064	< 0.00062	< 0.00056	< 0.0006	< 0.00083		< 0.00069	< 0.00058	< 0.00053	< 0.00066	< 0.00058
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00072 U	< 0.00092 U	< 0.00071 U	< 0.00085 U	< 0.0007 U	< 0.00068 U	< 0.00061 U	< 0.00065 U	< 0.00091 U		< 0.00075 U	< 0.00064 U	< 0.00058 U	< 0.00072 U	< 0.00064 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated															
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00069 U	< 0.00089 U	< 0.00069 U	< 0.00082 U	< 0.00068 U	< 0.00066 U	< 0.00059 U	< 0.00063 U	< 0.00087 U		< 0.00072 U	< 0.00061 U	< 0.00056 U	< 0.0007 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00065 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00068 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00053 U	< 0.00057 U	< 0.00079 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00063 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00067 U	< 0.00086 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U	< 0.00084 U		< 0.0007 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00076 U	< 0.00097 U	< 0.00075 U	< 0.0009 U	< 0.00074 U	< 0.00072 U	< 0.00065 U	< 0.00069 U	< 0.00096 U		< 0.00079 U	< 0.00067 U	< 0.00061 U	< 0.00077 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00095 U	< 0.00073 U	< 0.00088 U	< 0.00072 U	< 0.0007 U	< 0.00063 U	< 0.00067 U	< 0.00093 U		< 0.00077 U	< 0.00065 U	< 0.0006 U	< 0.00074 U	< 0.00066 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0006 U	< 0.00077 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U	< 0.00076 U		< 0.00063 U	< 0.00053 U	< 0.00049 U	< 0.00061 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.00089 U	< 0.00068 U	< 0.00082 U	< 0.00067 U	< 0.00066 U	< 0.00059 U	< 0.00063 U	< 0.00087 U		< 0.00072 U	< 0.00061 U	< 0.00056 U	< 0.0007 U	< 0.00061 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00059 U	< 0.00075 U	< 0.00058 U	< 0.0007 U	< 0.00057 U	< 0.00056 U	< 0.0005 U	< 0.00053 U	< 0.00074 U		< 0.00061 U	< 0.00052 U	< 0.00047 U	< 0.00059 U	< 0.00052 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	0.0022 J	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated															
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	< 0.0057 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U			
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	< 0.006 U			0.73	< 0.4 U	< 0.4 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.006 U	< 0.006 U			
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.0072 U						< 0.0072 U	< 0.0072 U	< 0.0072 U		< 0.0072 U	< 0.0072 U			
Football Field	SSHS-FB5	B23407T3	8/14/2000	855.33	1 - 1.5 ft	NA	Excavated	< 0.006 U						< 0.006 U	< 0.006 U	< 0.006 U		< 0.006 U	< 0.006 U			
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0069 U						< 0.0069 U	< 0.0069 U	< 0.0069 U		< 0.0069 U	< 0.0069 U			
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0074 U						< 0.0074 U	< 0.0074 U	< 0.0074 U		< 0.0074 U	< 0.0074 U			
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-1.5	7/21/2014	855.47	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00079 U	< 0.001 U	< 0.00078 U	< 0.00093 U	< 0.00077 U	< 0.00075 U	< 0.00067 U	< 0.00072 U	< 0.00099 U		< 0.00082 U	< 0.0007 U	< 0.00064 U	< 0.00079 U	< 0.0007 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-1.5	7/21/2014	855.39	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00063 U	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00054 U	< 0.00057 U	< 0.00079 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00063 U	< 0.00056 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-1.5	7/21/2014	855.97	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00076 U	< 0.00097 U	< 0.00075 U	< 0.0009 U	< 0.00074 U	< 0.00072 U	< 0.00065 U	< 0.00069 U	< 0.00096 U		< 0.00079 U	< 0.00067 U	< 0.00061 U	< 0.00076 U	< 0.00067 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-1.5	7/21/2014	855.49	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00049 U	< 0.00064 U	< 0.00049 U	< 0.00059 U	< 0.00048 U	< 0.00047 U	< 0.00042 U	< 0.00045 U	< 0.00062 U		< 0.00052 U	< 0.00044 U	< 0.0004 U	< 0.0005 U	< 0.00044 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-1.5	7/21/2014	855.42	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00067 U	< 0.00086 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U	< 0.00084 U		< 0.0007 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.0006 U
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	< 0.006 U			< 4 U	< 4 U	< 4 U	< 0.006 U	0.014	< 0.006 U		< 0.006 U	< 0.006 U			
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated				< 0.38 U	< 0.38 U	< 0.38 U									
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated				< 0.44 U	< 0.44 U	< 0.44 U									
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	< 0.0061 U			< 0.4 U	< 0.4 U	< 0.4 U	< 0.0061 U	< 0.0061 U	< 0.0061 U		< 0.0061 U	< 0.0061 U			
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	0.0015 J			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U			
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	< 0.0062 U			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		< 0.0062 U	< 0.0062 U			
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0076 U			< 0.5 U	< 0.5 U	< 0.5 U	< 0.0076 U	< 0.0076 U	< 0.0076 U		< 0.0076 U	< 0.0076 U			
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0067 U						< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U			
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.0056 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0056 U	< 0.0056 U	< 0.0056 U		< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.0055 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U			
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0066 U						< 0.0066 U	< 0.0066 U	< 0.0066 U		< 0.0066 U	< 0.0066 U			
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.007 U			< 0.46 U	< 0.46 U	< 0.46 U	< 0.007 U	< 0.007 U	< 0.007 U		< 0.007 U	< 0.007 U			
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.0065 U			< 0.43 U	< 0.43 U	< 0.43 U	< 0.0065 U	< 0.0065 U	< 0.0065 U		< 0.0065 U	< 0.0065 U			
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.0068 U			< 0.45 U	< 0.45 U	< 0.45 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.0067 U			< 0.44 U	< 0.44 U	< 0.44 U	< 0.0067 U	< 0.0067 U	< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.0071 U			< 0.47 U	< 0.47 U	< 0.47 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.0068 U			< 0.45 U	< 0.45 U	< 0.45 U	< 0.0068 U	< 0.0068 U	< 0.0068 U		< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.0006 U	< 0.00099 U	< 0.00064 U	< 0.00063 U	< 0.00084 U	< 0.00068 U	< 0.00082 U	< 0.00061 U	< 0.0007 U	< 0.00066 U	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00079 U	< 0.00082 U
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.00071 U	< 0.0012 U	< 0.00076 U	< 0.00075 U	< 0.001 U	< 0.0008 U	< 0.00098 U	< 0.00072 U	< 0.00083 U	< 0.00078 U	< 0.00079 U	< 0.00075 U	< 0.00081 U	< 0.00093 U	< 0.00098 U
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.00066 U	< 0.0011 U	< 0.00071 U	< 0.00069 U	< 0.00092 U	< 0.00074 U	< 0.0009 U	< 0.00067 U	< 0.00076 U	< 0.00072 U	< 0.00073 U	< 0.0007 U	< 0.00075 U	< 0.00086 U	< 0.0009 U
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.00054 U	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated															
Football Field	SSHS-B70	081514 01:15_SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	< 0.00076 U	< 0.0013 U,*	< 0.00082 U	< 0.00081 U	< 0.0011 U	< 0.00086 U	< 0.001 U	< 0.00078 U	< 0.00089 U	< 0.00084 U	< 0.00085 U	< 0.00081 U	< 0.00087 U	< 0.001 U	< 0.001 U
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	< 0.00068	< 0.0011	< 0.00073	< 0.00072	< 0.00096	< 0.00077	< 0.00093	< 0.00069	< 0.00079	< 0.00075	< 0.00076	< 0.00072	< 0.00077	< 0.0009	< 0.00093
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 0.00071	< 0.0012	< 0.00076	< 0.00075	< 0.00099	< 0.0008	< 0.00097	< 0.00072	< 0.00082	< 0.00078	< 0.00079	< 0.00075	< 0.0008	< 0.00093	< 0.00097
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.00061	< 0.001	< 0.00065	< 0.00064	< 0.00085	< 0.00068	< 0.00083	< 0.00062	< 0.0007	< 0.00066	< 0.00068	< 0.00064	< 0.00069	< 0.0008	< 0.00083
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00063	< 0.001	< 0.00067	< 0.00066	< 0.00088	< 0.00071	< 0.00086	< 0.00064	< 0.00073	< 0.00069	< 0.0007	< 0.00066	< 0.00071	< 0.00083	< 0.00086
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00069 U	< 0.0011 U	< 0.00074 U	< 0.00072 U	< 0.00096 U	< 0.00077 U	< 0.00094 U	< 0.0007 U	< 0.0008 U	< 0.00075 U	< 0.00077 U	< 0.00073 U	< 0.00078 U	< 0.0009 U	< 0.00094 U
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated															
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00066 U	< 0.0011 U	< 0.0007 U	< 0.0007 U	< 0.00093 U	< 0.00075 U	< 0.00091 U	< 0.00067 U	< 0.00077 U	< 0.00073 U	< 0.00074 U	< 0.0007 U	< 0.00075 U	< 0.00087 U	< 0.00091 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00068 U	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U	< 0.00074 U	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.00089 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0006 U	< 0.00099 U	< 0.00064 U	< 0.00063 U	< 0.00083 U	< 0.00067 U	< 0.00082 U	< 0.0006 U	< 0.00069 U	< 0.00065 U	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00078 U	< 0.00082 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00072 U	< 0.00087 U	< 0.00065 U	< 0.00074 U	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00084 U	< 0.00087 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00073 U	< 0.0012 U	< 0.00078 U	< 0.00077 U	< 0.001 U	< 0.00082 U	< 0.001 U	< 0.00074 U	< 0.00084 U	< 0.0008 U	< 0.00081 U	< 0.00077 U	< 0.00082 U	< 0.00095 U	< 0.001 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.0012 U	< 0.00076 U	< 0.00074 U	< 0.00099 U	< 0.0008 U	< 0.00097 U	< 0.00072 U	< 0.00082 U	< 0.00077 U	< 0.00079 U	< 0.00075 U	< 0.0008 U	< 0.00093 U	< 0.00097 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00058 U	< 0.00096 U	< 0.00062 U	< 0.00061 U	< 0.00081 U	< 0.00065 U	< 0.00079 U	< 0.00059 U	< 0.00067 U	< 0.00063 U	< 0.00064 U	< 0.00061 U	< 0.00065 U	< 0.00076 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.0011 U	< 0.00071 U	< 0.0007 U	< 0.00093 U	< 0.00075 U	< 0.00091 U	< 0.00067 U	< 0.00077 U	< 0.00073 U	< 0.00074 U	< 0.0007 U	< 0.00075 U	< 0.00087 U	< 0.00091 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00056 U	< 0.00093 U	< 0.0006 U	< 0.00059 U	< 0.00079 U	< 0.00063 U	< 0.00077 U	< 0.00057 U	< 0.00065 U	< 0.00062 U	< 0.00063 U	< 0.00059 U	< 0.00064 U	< 0.00074 U	< 0.00077 U
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated															
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated															
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	< 0.0057 U						< 0.011 U					0.013	< 0.0057 U		
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	< 0.006 U						< 0.012 U					0.0029 J	< 0.006 U		
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.0072 U						< 0.014 U					< 0.0072 U	< 0.0072 U		
Football Field	SSHS-FB5	B23407T3	8/14/2000	855.33	1 - 1.5 ft	NA	Excavated	< 0.006 U						< 0.012 U					< 0.006 U	< 0.006 U		
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0069 U						< 0.014 U					< 0.0069 U	< 0.0069 U		
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0074 U						< 0.015 U					< 0.0074 U	< 0.0074 U		
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-1.5	7/21/2014	855.47	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00075 U	< 0.0013 U	< 0.00081 U	< 0.0008 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00076 U	< 0.00088 U	< 0.00083 UJ	< 0.00084 U	< 0.0008 U	< 0.00085 U	< 0.00099 U	< 0.001 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-1.5	7/21/2014	855.39	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.0006 U	< 0.001 U	< 0.00064 U	< 0.00063 U	< 0.00084 U	< 0.00068 U	< 0.00082 U	< 0.00061 U	< 0.0007 U	< 0.00066 U	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00079 U	< 0.00082 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-1.5	7/21/2014	855.97	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00073 U	< 0.0012 U	< 0.00078 U	< 0.00077 U	< 0.001 U	< 0.00082 U	< 0.00099 U	< 0.00074 U	< 0.00084 U	< 0.0008 U	< 0.00081 U	< 0.00077 U	< 0.00082 U	< 0.00095 U	< 0.001 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-1.5	7/21/2014	855.49	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00047 U	< 0.00079 U	< 0.00051 U	< 0.0005 U	< 0.00066 U	< 0.00053 U	< 0.00065 U	< 0.00048 U	< 0.00055 U	< 0.00052 U	< 0.00053 U	< 0.0005 U	< 0.00054 U	< 0.00062 U	< 0.00065 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-1.5	7/21/2014	855.42	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00064 U	< 0.0011 U	< 0.00069 U	< 0.00068 U	< 0.0009 U	< 0.00072 U	< 0.00088 U	< 0.00065 U	< 0.00074 U	< 0.0007 U	< 0.00072 U	< 0.00068 U	< 0.00073 U	< 0.00084 U	< 0.00088 U
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	< 0.006 U						< 0.012 U					0.025	< 0.006 U		
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated															
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated															
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	< 0.0061 U						< 0.012 U					< 0.0061 U	< 0.0061 U		
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	< 0.0056 U						0.035					0.017	< 0.0056 U		
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	< 0.0062 U						< 0.012 U					0.03	< 0.0062 U		
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0076 U						< 0.015 U					0.082	< 0.0076 U		
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					< 0.0065 U	< 0.0065 U		
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0067 U						< 0.013 U					< 0.0067 U	< 0.0067 U		
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0056 U	< 0.0056 U	0.027	< 0.0056 U		< 0.37 U
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.37 U
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U						< 0.014 U					0.023	< 0.0071 U		
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					< 0.0065 U	< 0.0065 U		
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0066 U						< 0.013 U					< 0.0066 U	< 0.0066 U		
Northern Athletic Field	SSHS-SS3	SS3_10 May 00_0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.007 U						< 0.014 U					0.0036 J	< 0.007 U		
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.0065 U						< 0.013 U					0.004 J	< 0.0065 U		
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0068 U	< 0.0068 U	0.0079	< 0.0068 U		< 0.45 U
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U		< 0.47 U
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.013 U				< 0.013 U	< 0.013 U		< 0.0067 U	< 0.0067 U	0.036	< 0.0067 U		< 0.44 U
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0071 U	< 0.0071 U	0.01	< 0.0071 U		< 0.47 U
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.014 U				< 0.014 U	< 0.014 U		< 0.0068 U	< 0.0068 U	0.037	< 0.0068 U		< 0.45 U

DRAFT

TABLE 5-5D
Shallow Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B66	SSHS-B66-0.17-2 (1)	8/14/2014	851.94	0 - 2 ft	180-35818-1	Excavated	< 0.00045 U	< 0.00077 U	0.0024 J	< 0.00086 U	< 0.00044 U	< 0.0014 U	< 0.00073 U	
Rear Parking Lot	SSHS-B67	SSHS-B67-0.17-2 (1)	8/14/2014	850.45	0 - 2 ft	180-35818-1	Excavated	< 0.00054 U	< 0.00092 U	0.0025 J	< 0.001 U	< 0.00052 U	< 0.0016 U	< 0.00086 U	
Rear Parking Lot	SSHS-B68	SSHS-B68-0.17-2 (1)	8/14/2014	852.07	0 - 2 ft	180-35818-1	Excavated	< 0.0005 U	< 0.00085 U	0.0015 J	< 0.00094 U	< 0.00048 U	< 0.0015 U	< 0.0008 U	
Rear Parking Lot	SSHS-B69	SSHS-B69-0.17-2 (1)	8/14/2014	850.53	0 - 2 ft	180-35818-1	Excavated	< 0.00041 U	< 0.0007 U	< 0.00055 U	< 0.00077 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	0 - 2.5 ft	NA	Not Excavated			0.0051 J					
Football Field	SSHS-B70	081514 01:15 SSHS-B70-0.17-2 (1)	8/14/2014	855.98	0.17 - 2 ft	180-35818-2	Excavated	< 0.00058 U,*	< 0.00099 U	< 0.00078 U	< 0.0011 U	< 0.00056 U	< 0.0017 U	< 0.00093 U	
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	8/15/2014	856.19	0.17 - 2 ft	180-35858-1	Excavated	< 0.00052	< 0.00088	< 0.0007	< 0.00097	< 0.0005		< 0.00083	
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	8/14/2014	856.08	0.17 - 2 ft	180-35818-2	Excavated	< 0.00054	< 0.00091	< 0.00072	< 0.001	< 0.00052		< 0.00086	
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	8/14/2014	856.25	0.17 - 2 ft	180-35818-1	Excavated	< 0.00046	< 0.00078	< 0.00062	< 0.00087	< 0.00044		< 0.00073	
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00048	< 0.00081	< 0.00064	< 0.0009	< 0.00046		< 0.00076	
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00052 U	< 0.00089 U	< 0.0007 U	< 0.00098 U	< 0.0005 U	< 0.0016 U	< 0.00083 U	
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	0 - 2 ft	NA	Not Excavated			0.0051 J					
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0005 U	< 0.00086 U	< 0.00068 U	< 0.00095 U	< 0.00048 U	< 0.0015 U	< 0.0008 U	
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00047 U	< 0.00081 U	< 0.00064 U	< 0.00089 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00051 U	< 0.00088 U	0.0008 J	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00045 U	< 0.00077 U	< 0.00061 U	< 0.00085 U	< 0.00043 U	< 0.0014 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00048 U	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00047 U	< 0.0015 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00055 U	< 0.00094 U	< 0.00074 U	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.00088 U	
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00053 U	< 0.00091 U	< 0.00072 U	< 0.001 U	< 0.00052 U	< 0.0016 U	< 0.00085 U	
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00044 U	< 0.00075 U	< 0.00059 U	< 0.00082 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0005 U	< 0.00085 U	< 0.00068 U	< 0.00094 U	< 0.00048 U	< 0.0015 U	< 0.0008 U	
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-0-2	1/12/2018	850.62	0 - 2 ft	180-74164-1	Excavated	< 0.0025 U	< 0.0024 U	0.0024 J	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00042 U	< 0.00072 U	< 0.00057 U	< 0.0008 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	0 - 2.2 ft	NA	Not Excavated			< U					
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-0-2	1/16/2018	852.30	0 - 2 ft	180-74203-2	Excavated	< 0.0028 U	< 0.0027 U	0.016	< 0.0016 U	< 0.0041 U		< 0.0027 U	< 0.0048 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-0-2	1/18/2018	850.94	0 - 2 ft	180-74307-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U		< 0.0026 U	< 0.0045 U
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	0 - 2.2 ft	NA	Not Excavated			< U					
Football Field	SSHS-FB1	B23493	6/29/2000	857.00	0.5 - 2 ft	NA	Excavated	< 0.0057 U		0.024		< 0.0057 U	< 0.0057 U	< 0.0057 U	
Football Field	SSHS-FB2	B23496	6/29/2000	856.72	0.5 - 1 ft	NA	Excavated	0.0017 J		0.007		< 0.006 U	0.0013 J	< 0.006 U	
Football Field	SSHS-FB5	B23403T3	8/14/2000	855.33	0 - 0.25 ft	NA	Excavated	< 0.0072 U		< 0.0072 U		< 0.0072 U	< 0.0072 U	< 0.0072 U	
Football Field	SSHS-FB5	B23407T3	8/14/2000	855.33	1 - 1.5 ft	NA	Excavated	< 0.006 U		< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	
Football Field	SSHS-FB5-3N	B23404T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0069 U		< 0.0069 U		< 0.0069 U	< 0.0069 U	< 0.0069 U	
Football Field	SSHS-FB5-4N	B23408T3	8/14/2000	855.33	0 - 0.5 ft	NA	Excavated	< 0.0074 U		< 0.0074 U		< 0.0074 U	< 0.0074 U	< 0.0074 U	
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-1.5	7/21/2014	855.47	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00057 U	< 0.00097 U	0.02	< 0.0011 U	< 0.00055 U	< 0.0017 U	< 0.00091 U	
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-1.5	7/21/2014	855.39	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00045 U	< 0.00078 U	0.015	< 0.00086 U	< 0.00044 U	< 0.0014 U	< 0.00073 U	
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-1.5	7/21/2014	855.97	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00055 U	< 0.00094 U	0.19	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.00088 U	
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-1.5	7/21/2014	855.49	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00036 U	< 0.00061 U	0.069	< 0.00068 U	< 0.00035 U	< 0.0011 U	< 0.00057 U	
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-1.5	7/21/2014	855.42	1.5 - 1.5 ft	180-35053-1	Excavated	< 0.00048 U	< 0.00083 U	0.0028 J	< 0.00091 U	< 0.00047 U	< 0.0015 U	< 0.00078 U	
Football Field	SSHS-FB6	B23401	6/29/2000	856.63	1 - 2 ft	NA	Excavated	0.011		0.14		< 0.006 U	< 0.006 U	< 0.006 U	
Football Field	SSHS-FB6	B23406T3	8/14/2000	856.63	1 - 1.5 ft	NA	Excavated								
Football Field	SSHS-FB6	B23402T3	8/14/2000	856.63	0 - 0.5 ft	NA	Excavated								
Football Field	SSHS-FB7	B23403	6/29/2000	856.66	1 - 3 ft	NA	Excavated	< 0.0061 U		< 0.0061 U		< 0.0061 U	< 0.0061 U	< 0.0061 U	
Football Field	SSHS-FB8	B23404	6/29/2000	856.63	1 - 3 ft	NA	Excavated	< 0.0056 U		0.011		< 0.0056 U	< 0.0056 U	< 0.0056 U	
Football Field	SSHS-FB9	B23406	6/29/2000	855.29	1 - 2 ft	NA	Excavated	< 0.0062 U		< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	
Football Field	SSHS-SS1	B23456	5/10/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0076 U		< 0.0076 U		< 0.0076 U	< 0.0076 U	< 0.0076 U	
Football Field	SSHS-SS1	B23406T2	7/11/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-SS1	B23406T2-1	7/27/2000	856.57	0 - 0.5 ft	NA	Excavated	< 0.0067 U		< 0.0067 U		< 0.0067 U	< 0.0067 U	< 0.0067 U	
Northern Athletic Field	SSHS-SS10	12 Sep 00SS10 -	9/12/2000	856.05	0 - 0.5 ft	NA	Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	
Northern Athletic Field	SSHS-SS11	12 Sep 00SS11 -	9/12/2000	855.98	0 - 0.5 ft	NA	Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	
Football Field	SSHS-SS2	B23458	5/10/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0071 U		< 0.0071 U		< 0.0071 U	< 0.0071 U	< 0.0071 U	
Football Field	SSHS-SS2	B23407T2	7/11/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-SS2	B23407T2-1	7/27/2000	856.23	0 - 0.5 ft	NA	Excavated	< 0.0066 U		< 0.0066 U		< 0.0066 U	< 0.0066 U	< 0.0066 U	
Northern Athletic Field	SSHS-SS3	SS3 10 May 00 0-0.25	5/10/2000	851.17	0 - 0.5 ft	NA	Excavated	< 0.007 U		< 0.007 U		< 0.007 U	< 0.007 U	< 0.007 U	
Football Field	SSHS-SS4	B23483	5/11/2000		0 - 0.5 ft	NA	Excavated	< 0.0065 U		< 0.0065 U		< 0.0065 U	< 0.0065 U	< 0.0065 U	
Football Field	SSHS-SS5	SS5	9/12/2000	856.43	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	
Football Field	SSHS-SS6	SS6	9/12/2000	856.00	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	
Football Field	SSHS-SS7	SS7	9/12/2000	857.07	0 - 0.5 ft	NA	Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	
Football Field	SSHS-SS8	SS8	9/12/2000	856.32	0 - 0.5 ft	NA	Excavated	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	< 0.0071 U	
Football Field	SSHS-SS9	SS9	9/12/2000	856.01	0 - 0.5 ft	NA	Excavated	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	< 0.0068 U	

								Emerging C									
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	856.20	0 - 2 ft	180-80252-1	Not Excavated			< 44 U									
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	856.45	0 - 2 ft	180-57995-1	Not Excavated			< 42									
Rear Parking Lot	SSHS-B568	092316 08:45 SSHS-B568-SUB-0-2	SSHS-B568-SUB-0-2	851.24	0 - 2 ft	180-59020-1	Not Excavated			< 39 U									
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-0.17-2 (1)	SSHS-B68-0.17-2 (1)	852.07	0 - 2 ft	180-35818-1	Not Excavated			< 41 U									
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-0.17-2 (1)	SSHS-B69-0.17-2 (1)	850.53	0 - 2 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	855.66	0 - 2 ft	180-66622-2	Not Excavated			< 55 U									
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	856.80	0.17 - 1 ft	180-123985-1	Not Excavated			< 120 U									
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	855.65	0.17 - 1 ft	180-57995-1	Not Excavated			< 84 U									
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	855.97	0.17 - 1 ft	180-57995-1	Not Excavated			< 44 U									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-0.17-2-20230118	SSHS-PDI6-B5105-SUB-0.17-2	855.73	0.17-2	1801508222	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.032 U	< 0.051 U	< 0.040 U	< 0.030 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-0.17-2-20230118	SSHS-PDI6-B5106-SUB-0.17-2	851.23	0.17-2	1801508221	Not Excavated	< 110 U											
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	852.78	0.17 - 2 ft	1801518942	Not Excavated	< 110 U											
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	854.72	0.17 - 2 ft	180-80157-3	Not Excavated			< 18 U									
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	856.74	0.17 - 2 ft	180-101084-3	Not Excavated			< 120 U									
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	855.50	0.17 - 2 ft	180-108826-2	Not Excavated			< 560 U									
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	855.34	0.17 - 2 ft	180-108826-1	Not Excavated			< 110 U									
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	855.68	0.17 - 2 ft	180-108826-1	Not Excavated			< 220 U									
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 630 U			< 0.43 U	< 0.029 U	0.46 B	< 0.045 U	< 0.025 U	< 0.077 U	< 0.040 U	0.050 J	< 0.036 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	856.42	0.17 - 2 ft	180-127595-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.05 U	< 0.039 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	855.97	0.17 - 2 ft	180-127140-1	Not Excavated			< 1100 U									
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	855.73	0.17 - 2 ft	180-127066-2	Not Excavated			< 110 U	< 0.047 U	< 0.038 U	< 0.046 U	< 0.051 U	< 0.047 U	< 0.03 U	< 0.048 U	< 0.038 U	< 0.029 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	855.88	0.17 - 2 ft	180-35818-1	Not Excavated			< 40									
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	855.75	0.17 - 2 ft	180-35818-2	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	855.92	0.17 - 2 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	856.60	0.17 - 2 ft	180-35776-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15 SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	854.77	0.17 - 2 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	856.00	0.17 - 2 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	855.54	0.17 - 2 ft	180-35776-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	854.20	0.17 - 2 ft	180-35776-1	Not Excavated			< 41 U									
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	855.86	0.17 - 2 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	855.00	0.17 - 2 ft	180-35776-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	853.90	0.17 - 2 ft	180-35776-1	Not Excavated			< 41 U									
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	856.80	1 - 2 ft	180-123985-1	Not Excavated			< 120 U									
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	855.65	1 - 2 ft	180-57995-1	Not Excavated			< 40 U									
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	855.97	1 - 2 ft	180-57995-1	Not Excavated			< 42 U									
Football Field	SSHS-B2763	042819 10:00 PS-FD-17	PS-FD-17	855.33	0.17 - 2 ft	180-89521-1	Not Excavated			< 110 U									
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 PS-FD-18	PS-FD-18	854.78	0.17 - 2 ft	180-89521-1	Not Excavated			< 470 U									
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	852.51	0 - 2 ft	1801219031	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.031 U	< 0.034 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	858.31	0.17 - 2 ft	180-119815-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	0.04 J	< 0.04 U	< 0.022 U	< 0.068 U	< 0.035 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	855.23	0.17 - 2 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.034 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	852.51	0 - 2 ft	1801164042	Not Excavated	< 130 U			< 0.46 U	< 0.031 U	0.67 B	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U	< 0.036 U	< 0.038 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	853.96	0 - 2 ft	1801239851	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	0.087 J	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U	0.034 J	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 DUP-09	DUP-09	855.16	0.17 - 2 ft	180-35776-2	Not Excavated			< 45 U									
Football Field	SSHS-B3870	042021 09:30 DUP-09	DUP-09	855.16	0.17 - 2 ft	180-120245-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.027 U	< 0.084 U	< 0.044 U	< 0.036 U	< 0.039 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 DUP-13	DUP-13	855.33	0.17 - 2 ft	180-35818-2	Not Excavated			< 41 U									
Northern Athletic Field	SSHS-B4020	DUP-2-20210701	DUP-2	852.51	0 - 2 ft	1801239851	Excavated	< 120 U			< 0.40 U	0.037 J	0.19 J	0.13 J	0.30	0.15 J	< 0.038 U	0.14 J	< 0.033 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-0.17-2 (1)	SSHS-B101-0.17-2 (1)	852.95	0 - 2 ft	180-35818-2	Excavated			< 41 U									
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-0-2	SSHS-B2185-SUB-0-2	855.07	0 - 2 ft	180-80106-3	Excavated			< 84 U									
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-0-2	SSHS-B2186-SUB-0-2	854.94	0 - 2 ft	180-80106-2	Excavated			< 86 U									
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-0-2	SSHS-B2187-SUB-0-2	856.10	0 - 2 ft	180-80106-1	Excavated			< 17 U									
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-0-2	SSHS-B2188-SUB-0-2	855.99	0 - 2 ft	180-80106-2	Excavated			< 67 U									
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-0-2	SSHS-B2189-SUB-0-2	855.74	0 - 2 ft	180-80105-3	Excavated			< 40 U									
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-0-2	SSHS-B2190-SUB-0-2	856.06	0 - 2 ft	180-80252-1	Excavated			< 15 U									
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-0-2	SSHS-B2191-SUB-0-2	856.18	0 - 2 ft	180-80105-3	Excavated			< 79 U									
Football Field	SSHS-B2196	072518 09:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-80106-2	Excavated			< 34 U									
Football Field	SSHS-B2196	072518 09:00 SSHS-B2196-SUB-0-2	SSHS-B2196-SUB-0-2	855.03	0 - 2 ft	180-80106-2	Excavated			< 44 U									
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-0-2	SSHS-B2197-SUB-0-2	854.99	0 - 2 ft	180-80105-1	Excavated			< 68 U									
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-0-2	SSHS-B2198-SUB-0-2	855.05	0 - 2 ft	180-80105-2	Excavated			< 330 U									
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-0-2	SSHS-B2245-SUB-0-2	855.25	0 - 2 ft	180-80106-1	Excavated			< 17 U									
Football Field	SSHS-B2246	072718 09:00 PS-FD-36	PS-FD-36	855.24	0 - 2 ft	180-80225-3	Excavated			< 17 U									
Football Field	SSHS-B2246	072718 09:00 SSHS-B2246-SUB-0-2	SSHS-B2246-SUB-0-2	855.24	0 - 2 ft	180-80225-1	Excavated			< 35 U									
Tennis Courts / Main Parking Lot	SSHS-B402	090616 09:00 SSHS-B402-SUB-0-2	SSHS-B402-SUB-0-2	855.98	0 - 2 ft	180-58129-1	Excavated			< 420 U									
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	SSHS-B404-SUB-0-2	856.65	0 - 2 ft	180-57995-1	Excavated			< 400									
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-0-2	SSHS-B410-SUB-0-2	856.77	0 - 2 ft	180-57995-1	Excavated			< 46 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	856.20	0 - 2 ft	180-80252-1	Not Excavated												
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	856.45	0 - 2 ft	180-57995-1	Not Excavated												
Rear Parking Lot	SSHS-B568	092316 08:45 SSHS-B568-SUB-0-2	SSHS-B568-SUB-0-2	851.24	0 - 2 ft	180-59020-1	Not Excavated												
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-0.17-2 (1)	SSHS-B68-0.17-2 (1)	852.07	0 - 2 ft	180-35818-1	Not Excavated												
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-0.17-2 (1)	SSHS-B69-0.17-2 (1)	850.53	0 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	855.66	0 - 2 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	856.80	0.17 - 1 ft	180-123985-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	855.65	0.17 - 1 ft	180-57995-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	855.97	0.17 - 1 ft	180-57995-1	Not Excavated												
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-0.17-2-20230118	SSHS-PDI6-B5105-SUB-0.17-2	855.73	0.17-2	1801508222	Not Excavated	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-0.17-2-20230118	SSHS-PDI6-B5106-SUB-0.17-2	851.23	0.17-2	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	852.78	0.17 - 2 ft	1801518942	Not Excavated												
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	854.72	0.17 - 2 ft	180-80157-3	Not Excavated												
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	856.74	0.17 - 2 ft	180-101084-3	Not Excavated												
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	855.50	0.17 - 2 ft	180-108826-2	Not Excavated												
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	855.34	0.17 - 2 ft	180-108826-1	Not Excavated												
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	855.68	0.17 - 2 ft	180-108826-1	Not Excavated												
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	858.46	0.17 - 2 ft	1801164622	Not Excavated	< 0.048 U	0.059 J	< 0.095 U	1.2 BT	0.18 J	0.41	< 0.062 U	< 0.059 U	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	856.42	0.17 - 2 ft	180-127595-2	Not Excavated	< 0.032 U	< 0.023 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	855.97	0.17 - 2 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	855.73	0.17 - 2 ft	180-127066-2	Not Excavated	< 0.031 U	< 0.022 U	< 34 U	< 0.043 U	< 0.052 U	< 0.041 U	< 0.037 U	< 34 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	855.88	0.17 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	855.75	0.17 - 2 ft	180-35818-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	855.92	0.17 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	856.60	0.17 - 2 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15 SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	854.77	0.17 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	856.00	0.17 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	855.54	0.17 - 2 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	854.20	0.17 - 2 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	855.86	0.17 - 2 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	855.00	0.17 - 2 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	853.90	0.17 - 2 ft	180-35776-1	Not Excavated												
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	856.80	1 - 2 ft	180-123985-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	855.65	1 - 2 ft	180-57995-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	855.97	1 - 2 ft	180-57995-1	Not Excavated												
Football Field	SSHS-B2763	042819 10:00 PS-FD-17	PS-FD-17	855.33	0.17 - 2 ft	180-89521-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 PS-FD-18	PS-FD-18	854.78	0.17 - 2 ft	180-89521-1	Not Excavated												
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	852.51	0 - 2 ft	1801219031	Not Excavated	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.059 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	858.31	0.17 - 2 ft	180-119815-1	Not Excavated	< 0.043 U	< 0.036 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.4 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	855.23	0.17 - 2 ft	1801213101	Not Excavated	< 0.046 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	852.51	0 - 2 ft	1801164042	Not Excavated	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	853.96	0 - 2 ft	1801239851	Not Excavated	0.075 J	< 0.038 U	< 0.086 U	0.25 J	0.11 J	< 0.081 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 DUP-09	DUP-09	855.16	0.17 - 2 ft	180-35776-2	Not Excavated												
Football Field	SSHS-B3870	042021 09:30 DUP-09	DUP-09	855.16	0.17 - 2 ft	180-120245-1	Not Excavated	< 0.052 U	< 0.045 U	< 34 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.067 U	< 34 U	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 DUP-13	DUP-13	855.33	0.17 - 2 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B4020	DUP-2-20210701	DUP-2	852.51	0 - 2 ft	1801239851	Excavated	0.18 J	0.19 J	< 0.089 U	0.80	0.32	0.10 J	< 0.058 U	< 0.055 U	0.12 J	< 0.27 U	< 0.16 U	< 0.42 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-0.17-2 (1)	SSHS-B101-0.17-2 (1)	852.95	0 - 2 ft	180-35818-2	Excavated												
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-0-2	SSHS-B2185-SUB-0-2	855.07	0 - 2 ft	180-80106-3	Excavated												
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-0-2	SSHS-B2186-SUB-0-2	854.94	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-0-2	SSHS-B2187-SUB-0-2	856.10	0 - 2 ft	180-80106-1	Excavated												
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-0-2	SSHS-B2188-SUB-0-2	855.99	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-0-2	SSHS-B2189-SUB-0-2	855.74	0 - 2 ft	180-80105-3	Excavated												
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-0-2	SSHS-B2190-SUB-0-2	856.06	0 - 2 ft	180-80252-1	Excavated												
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-0-2	SSHS-B2191-SUB-0-2	856.18	0 - 2 ft	180-80105-3	Excavated												
Football Field	SSHS-B2196	072518 09:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2196	072518 09:00 SSHS-B2196-SUB-0-2	SSHS-B2196-SUB-0-2	855.03	0 - 2 ft	180-80106-2	Excavated												
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-0-2	SSHS-B2197-SUB-0-2	854.99	0 - 2 ft	180-80105-1	Excavated												
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-0-2	SSHS-B2198-SUB-0-2	855.05	0 - 2 ft	180-80105-2	Excavated												
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-0-2	SSHS-B2245-SUB-0-2	855.25	0 - 2 ft	180-80106-1	Excavated												
Football Field	SSHS-B2246	072718 09:00 PS-FD-36	PS-FD-36	855.24	0 - 2 ft	180-80225-3	Excavated												
Football Field	SSHS-B2246	072718 09:00 SSHS-B2246-SUB-0-2	SSHS-B2246-SUB-0-2	855.24	0 - 2 ft	180-80225-1	Excavated												
Tennis Courts / Main Parking Lot	SSHS-B402	090616 09:00 SSHS-B402-SUB-0-2	SSHS-B402-SUB-0-2	855.98	0 - 2 ft	180-58129-1	Excavated												
Northern Athletic Field	SSHS-B404	SSHS-B404-SUB-0-2	SSHS-B404-SUB-0-2	856.65	0 - 2 ft	180-57995-1	Excavated												
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-0-2	SSHS-B410-SUB-0-2	856.77	0 - 2 ft	180-57995-1	Excavated												

DRAFT

								Emerging C									
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B424	082316 09:15_SSHS-B424-SUB-0-2	SSHS-B424-SUB-0-2	856.17	0 - 2 ft	180-57858-1	Excavated			< 44 U									
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-0-2	SSHS-B432-SUB-0-2	855.16	0 - 2 ft	180-57858-1	Excavated			< 47 U									
Football Field	SSHS-B434	082316 09:15_SSHS-B434-SUB-0-2	SSHS-B434-SUB-0-2	855.08	0 - 2 ft	180-57858-1	Excavated			< 45 U									
Football Field	SSHS-B448	082616 09:00_SSHS-B448-SUB-0-2	SSHS-B448-SUB-0-2	856.23	0 - 2 ft	180-57995-1	Excavated			< 44 U									
Football Field	SSHS-B449	090616 09:00_SSHS-B449-SUB-0-2	SSHS-B449-SUB-0-2	855.21	0 - 2 ft	180-58129-1	Excavated			< 42 U									
Football Field	SSHS-B450	082616 09:00_SSHS-B450-SUB-0-2	SSHS-B450-SUB-0-2	856.21	0 - 2 ft	180-57995-1	Excavated			< 43 U									
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	SSHS-B572-SUB-0-2	852.49	0 - 2 ft	180-58129-1	Excavated			< 41									
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-0.17-2 (1)	SSHS-B64-0.17-2 (1)	851.65	0 - 2 ft	180-35818-2	Excavated			< 40 U									
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-0.17-2 (1)	SSHS-B65-0.17-2 (1)	850.41	0 - 2 ft	180-35818-1	Excavated			< 41 U									
Rear Parking Lot	SSHS-B66	081514 01:15_SSHS-B66-0.17-2 (1)	SSHS-B66-0.17-2 (1)	851.94	0 - 2 ft	180-35818-1	Excavated			< 41 U									
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-0.17-2 (1)	SSHS-B67-0.17-2 (1)	850.45	0 - 2 ft	180-35818-1	Excavated			< 43 U									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1-20210701	SSHS-B4018-SUB-0.17-1	857.47	0.17 - 1 ft	180123985l	Excavated	< 120 U			< 0.43 U	< 0.029 U	0.081 J	< 0.046 U	0.033 J	< 0.079 U	< 0.041 U	0.040 J	< 0.036 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-0.17-1	SSHS-B4019-SUB-0.17-1	856.76	0.17 - 1 ft	180-123985-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B2024	072718 09:00_SSHS-B2024-SUB-0.17-2	SSHS-B2024-SUB-0.17-2	852.76	0.17 - 2 ft	180-80225-2	Excavated			< 34 U									
Football Field	SSHS-B2025	072718 09:00_PS-FD-40	PS-FD-40	854.55	0.17 - 2 ft	180-80227-3	Excavated			< 19 U									
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-0.17-2	SSHS-B2025-SUB-0.17-2	854.55	0.17 - 2 ft	180-80225-2	Excavated			< 17 U									
Football Field	SSHS-B2027	072718 09:00_SSHS-B2027-SUB-0.17-2	SSHS-B2027-SUB-0.17-2	855.22	0.17 - 2 ft	180-80227-1	Excavated			< 18 U									
Football Field	SSHS-B2028	072718 09:00_PS-FD-41	PS-FD-41	855.23	0.17 - 2 ft	180-80227-3	Excavated			< 18 U									
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-0.17-2	SSHS-B2028-SUB-0.17-2	855.23	0.17 - 2 ft	180-80227-3	Excavated			< 19 U									
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-0.17-2	SSHS-B2031-SUB-0.17-2	855.50	0.17 - 2 ft	180-80251-2	Excavated			< 18 U									
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-0.17-2	SSHS-B2032-SUB-0.17-2	854.88	0.17 - 2 ft	180-80251-1	Excavated			< 17 U									
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-0.17-2	SSHS-B2033-SUB-0.17-2	854.70	0.17 - 2 ft	180-80251-1	Excavated			< 16 U									
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-0.17-2	SSHS-B2050-SUB-0.17-2	855.45	0.17 - 2 ft	180-80225-1	Excavated			< 18 U									
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-0.17-2	SSHS-B2051-SUB-0.17-2	855.08	0.17 - 2 ft	180-80251-1	Excavated			< 21 U									
Football Field	SSHS-B2052	072618 08:50_SSHS-B2052-SUB-0.17-2	SSHS-B2052-SUB-0.17-2	855.59	0.17 - 2 ft	180-80154-2	Excavated			< 17 U									
Football Field	SSHS-B2053	072618 08:50_SSHS-B2053-SUB-0.17-2	SSHS-B2053-SUB-0.17-2	855.00	0.17 - 2 ft	180-80157-1	Excavated			< 18 U									
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-0.17-2	SSHS-B2071-SUB-0.17-2	856.16	0.17 - 2 ft	180-80251-2	Excavated			< 17 U									
Football Field	SSHS-B2072	072618 08:50_SSHS-B2072-SUB-0.17-2	SSHS-B2072-SUB-0.17-2	856.82	0.17 - 2 ft	180-80154-2	Excavated			< 36 U									
Football Field	SSHS-B2073	072618 08:50_PS-FD-28	PS-FD-28	856.99	0.17 - 2 ft	180-80157-2	Excavated			< 17 U									
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-0.17-2	SSHS-B2073-SUB-0.17-2	856.99	0.17 - 2 ft	180-80157-3	Excavated			< 18 U									
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-0.17-2	SSHS-B2089-SUB-0.17-2	855.40	0.17 - 2 ft	180-80157-3	Excavated			< 18 U									
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-0.17-2	SSHS-B2090-SUB-0.17-2	855.97	0.17 - 2 ft	180-80251-2	Excavated			< 72 U									
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-0.17-2	SSHS-B2091-SUB-0.17-2	856.61	0.17 - 2 ft	180-80154-1	Excavated			< 36 U									
Football Field	SSHS-B2092	072618 08:50_SSHS-B2092-SUB-0.17-2	SSHS-B2092-SUB-0.17-2	856.77	0.17 - 2 ft	180-80157-3	Excavated			< 17 U									
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-0.17-2	SSHS-B2108-SUB-0.17-2	855.64	0.17 - 2 ft	180-80154-2	Excavated			< 18 U									
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-0.17-2	SSHS-B2109-SUB-0.17-2	855.25	0.17 - 2 ft	180-80154-1	Excavated			< 18 U									
Football Field	SSHS-B2110	072618 08:50_PS-FD-18	PS-FD-18	854.78	0.17 - 2 ft	180-80157-2	Excavated			< 170 U									
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-0.17-2	SSHS-B2110-SUB-0.17-2	854.78	0.17 - 2 ft	180-80154-1	Excavated			< 170 U									
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-0.17-2	SSHS-B2127-SUB-0.17-2	855.91	0.17 - 2 ft	180-80154-3	Excavated			< 18 U									
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-0.17-2	SSHS-B2128-SUB-0.17-2	856.01	0.17 - 2 ft	180-80154-3	Excavated			< 18 U									
Football Field	SSHS-B2129	072618 08:50_PS-FD-17	PS-FD-17	855.33	0.17 - 2 ft	180-80157-2	Excavated			< 19 U									
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-0.17-2	SSHS-B2129-SUB-0.17-2	855.33	0.17 - 2 ft	180-80157-1	Excavated			< 18 U									
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-0.17-2	SSHS-B2143-SUB-0.17-2	856.56	0.17 - 2 ft	180-80154-3	Excavated			< 18 U									
Football Field	SSHS-B2193	072718 09:00_SSHS-B2193-SUB-0.17-2	SSHS-B2193-SUB-0.17-2	857.04	0.17 - 2 ft	180-80225-1	Excavated			< 18 U									
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-0.17-2	SSHS-B2195-SUB-0.17-2	855.94	0.17 - 2 ft	180-80225-1	Excavated			< 18 U									
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-0.17-2	SSHS-B2213-SUB-0.17-2	855.06	0.17 - 2 ft	180-80225-2	Excavated			< 18 U									
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-0.17-2	SSHS-B2214-SUB-0.17-2	855.14	0.17 - 2 ft	180-80227-3	Excavated			< 36 U									
Football Field	SSHS-B2215	072718 09:00_PS-FD-43	PS-FD-43	855.11	0.17 - 2 ft	180-80227-3	Excavated			< 17 U									
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-0.17-2	SSHS-B2215-SUB-0.17-2	855.11	0.17 - 2 ft	180-80227-2	Excavated			< 350 U									
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-0.17-2	SSHS-B2217-SUB-0.17-2	855.08	0.17 - 2 ft	180-80251-3	Excavated			< 45 U									
Football Field	SSHS-B2221	072518 09:00_SSHS-B2221-SUB-0.17-2	SSHS-B2221-SUB-0.17-2	855.38	0.17 - 2 ft	180-80106-1	Excavated			< 17 U									
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-0.17-2	SSHS-B2224-SUB-0.17-2	854.93	0.17 - 2 ft	180-80227-2	Excavated			< 91 U									
Football Field	SSHS-B2225	072518 09:00_SSHS-B2225-SUB-0.17-2	SSHS-B2225-SUB-0.17-2	857.03	0.17 - 2 ft	180-80105-3	Excavated			< 18 U									
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-0.17-2	SSHS-B2226-SUB-0.17-2	856.56	0.17 - 2 ft	180-80227-1	Excavated			< 19 U									
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-0.17-2	SSHS-B2227-SUB-0.17-2	856.55	0.17 - 2 ft	180-80227-1	Excavated			< 17 U									
Football Field	SSHS-B2228	072818 11:30_PS-FD-53	PS-FD-53	855.33	0.17 - 2 ft	180-80252-2	Excavated			< 18 U									
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-0.17-2	SSHS-B2228-SUB-0.17-2	855.33	0.17 - 2 ft	180-80251-3	Excavated			< 34 U									
Football Field	SSHS-B2229	072818 11:30_SSHS-B2229-SUB-0.17-2	SSHS-B2229-SUB-0.17-2	855.28	0.17 - 2 ft	180-80252-1	Excavated			< 120 U									
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-0.17-2	SSHS-B2230-SUB-0.17-2	856.03	0.17 - 2 ft	180-80091-4	Excavated			< 18 U									
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-0.17-2	SSHS-B2231-SUB-0.17-2	856.14	0.17 - 2 ft	180-80091-2	Excavated			< 18 U									
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-0.17-2	SSHS-B2232-SUB-0.17-2	856.82	0.17 - 2 ft	180-80105-1	Excavated			< 18 U									
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-0.17-2	SSHS-B2233-SUB-0.17-2	854.83	0.17 - 2 ft	180-80105-1	Excavated			< 18 U									
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-0.17-2	SSHS-B2235-SUB-0.17-2	855.30	0.17 - 2 ft	180-80091-1	Excavated			< 17 U									
Football Field	SSHS-B2236	072818 11:30_SSHS-B2236-SUB-0.17-2	SSHS-B2236-SUB-0.17-2	855.25	0.17 - 2 ft	180-80251-3	Excavated			< 17 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B424	082316 09:15_SSHS-B424-SUB-0-2	SSHS-B424-SUB-0-2	856.17	0 - 2 ft	180-57858-1	Excavated												
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-0-2	SSHS-B432-SUB-0-2	855.16	0 - 2 ft	180-57858-1	Excavated												
Football Field	SSHS-B434	082316 09:15_SSHS-B434-SUB-0-2	SSHS-B434-SUB-0-2	855.08	0 - 2 ft	180-57858-1	Excavated												
Football Field	SSHS-B448	082616 09:00_SSHS-B448-SUB-0-2	SSHS-B448-SUB-0-2	856.23	0 - 2 ft	180-57995-1	Excavated												
Football Field	SSHS-B449	090616 09:00_SSHS-B449-SUB-0-2	SSHS-B449-SUB-0-2	855.21	0 - 2 ft	180-58129-1	Excavated												
Football Field	SSHS-B450	082616 09:00_SSHS-B450-SUB-0-2	SSHS-B450-SUB-0-2	856.21	0 - 2 ft	180-57995-1	Excavated												
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-0-2	SSHS-B572-SUB-0-2	852.49	0 - 2 ft	180-58129-1	Excavated												
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-0.17-2 (1)	SSHS-B64-0.17-2 (1)	851.65	0 - 2 ft	180-35818-2	Excavated												
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-0.17-2 (1)	SSHS-B65-0.17-2 (1)	850.41	0 - 2 ft	180-35818-1	Excavated												
Rear Parking Lot	SSHS-B66	081514 01:15_SSHS-B66-0.17-2 (1)	SSHS-B66-0.17-2 (1)	851.94	0 - 2 ft	180-35818-1	Excavated												
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-0.17-2 (1)	SSHS-B67-0.17-2 (1)	850.45	0 - 2 ft	180-35818-1	Excavated												
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-0.17-1-20210701	SSHS-B4018-SUB-0.17-1	857.47	0.17 - 1 ft	180123985l	Excavated	0.066 J	< 0.042 U	< 0.096 U	0.24 J	0.10 J	< 0.090 U	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-0.17-1	SSHS-B4019-SUB-0.17-1	856.76	0.17 - 1 ft	180-123985-1	Excavated												
Northern Athletic Field	SSHS-B2024	072718 09:00_SSHS-B2024-SUB-0.17-2	SSHS-B2024-SUB-0.17-2	852.76	0.17 - 2 ft	180-80225-2	Excavated												
Football Field	SSHS-B2025	072718 09:00_PS-FD-40	PS-FD-40	854.55	0.17 - 2 ft	180-80227-3	Excavated												
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-0.17-2	SSHS-B2025-SUB-0.17-2	854.55	0.17 - 2 ft	180-80225-2	Excavated												
Football Field	SSHS-B2027	072718 09:00_SSHS-B2027-SUB-0.17-2	SSHS-B2027-SUB-0.17-2	855.22	0.17 - 2 ft	180-80227-1	Excavated												
Football Field	SSHS-B2028	072718 09:00_PS-FD-41	PS-FD-41	855.23	0.17 - 2 ft	180-80227-3	Excavated												
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-0.17-2	SSHS-B2028-SUB-0.17-2	855.23	0.17 - 2 ft	180-80227-3	Excavated												
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-0.17-2	SSHS-B2031-SUB-0.17-2	855.50	0.17 - 2 ft	180-80251-2	Excavated												
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-0.17-2	SSHS-B2032-SUB-0.17-2	854.88	0.17 - 2 ft	180-80251-1	Excavated												
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-0.17-2	SSHS-B2033-SUB-0.17-2	854.70	0.17 - 2 ft	180-80251-1	Excavated												
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-0.17-2	SSHS-B2050-SUB-0.17-2	855.45	0.17 - 2 ft	180-80225-1	Excavated												
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-0.17-2	SSHS-B2051-SUB-0.17-2	855.08	0.17 - 2 ft	180-80251-1	Excavated												
Football Field	SSHS-B2052	072618 08:50_SSHS-B2052-SUB-0.17-2	SSHS-B2052-SUB-0.17-2	855.59	0.17 - 2 ft	180-80154-2	Excavated												
Football Field	SSHS-B2053	072618 08:50_SSHS-B2053-SUB-0.17-2	SSHS-B2053-SUB-0.17-2	855.00	0.17 - 2 ft	180-80157-1	Excavated												
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-0.17-2	SSHS-B2071-SUB-0.17-2	856.16	0.17 - 2 ft	180-80251-2	Excavated												
Football Field	SSHS-B2072	072618 08:50_SSHS-B2072-SUB-0.17-2	SSHS-B2072-SUB-0.17-2	856.82	0.17 - 2 ft	180-80154-2	Excavated												
Football Field	SSHS-B2073	072618 08:50_PS-FD-28	PS-FD-28	856.99	0.17 - 2 ft	180-80157-2	Excavated												
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-0.17-2	SSHS-B2073-SUB-0.17-2	856.99	0.17 - 2 ft	180-80157-3	Excavated												
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-0.17-2	SSHS-B2089-SUB-0.17-2	855.40	0.17 - 2 ft	180-80157-3	Excavated												
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-0.17-2	SSHS-B2090-SUB-0.17-2	855.97	0.17 - 2 ft	180-80251-2	Excavated												
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-0.17-2	SSHS-B2091-SUB-0.17-2	856.61	0.17 - 2 ft	180-80154-1	Excavated												
Football Field	SSHS-B2092	072618 08:50_SSHS-B2092-SUB-0.17-2	SSHS-B2092-SUB-0.17-2	856.77	0.17 - 2 ft	180-80157-3	Excavated												
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-0.17-2	SSHS-B2108-SUB-0.17-2	855.64	0.17 - 2 ft	180-80154-2	Excavated												
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-0.17-2	SSHS-B2109-SUB-0.17-2	855.25	0.17 - 2 ft	180-80154-1	Excavated												
Football Field	SSHS-B2110	072618 08:50_PS-FD-18	PS-FD-18	854.78	0.17 - 2 ft	180-80157-2	Excavated												
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-0.17-2	SSHS-B2110-SUB-0.17-2	854.78	0.17 - 2 ft	180-80154-1	Excavated												
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-0.17-2	SSHS-B2127-SUB-0.17-2	855.91	0.17 - 2 ft	180-80154-3	Excavated												
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-0.17-2	SSHS-B2128-SUB-0.17-2	856.01	0.17 - 2 ft	180-80154-3	Excavated												
Football Field	SSHS-B2129	072618 08:50_PS-FD-17	PS-FD-17	855.33	0.17 - 2 ft	180-80157-2	Excavated												
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-0.17-2	SSHS-B2129-SUB-0.17-2	855.33	0.17 - 2 ft	180-80157-1	Excavated												
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-0.17-2	SSHS-B2143-SUB-0.17-2	856.56	0.17 - 2 ft	180-80154-3	Excavated												
Football Field	SSHS-B2193	072718 09:00_SSHS-B2193-SUB-0.17-2	SSHS-B2193-SUB-0.17-2	857.04	0.17 - 2 ft	180-80225-1	Excavated												
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-0.17-2	SSHS-B2195-SUB-0.17-2	855.94	0.17 - 2 ft	180-80225-1	Excavated												
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-0.17-2	SSHS-B2213-SUB-0.17-2	855.06	0.17 - 2 ft	180-80225-2	Excavated												
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-0.17-2	SSHS-B2214-SUB-0.17-2	855.14	0.17 - 2 ft	180-80227-3	Excavated												
Football Field	SSHS-B2215	072718 09:00_PS-FD-43	PS-FD-43	855.11	0.17 - 2 ft	180-80227-3	Excavated												
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-0.17-2	SSHS-B2215-SUB-0.17-2	855.11	0.17 - 2 ft	180-80227-2	Excavated												
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-0.17-2	SSHS-B2217-SUB-0.17-2	855.08	0.17 - 2 ft	180-80251-3	Excavated												
Football Field	SSHS-B2221	072518 09:00_SSHS-B2221-SUB-0.17-2	SSHS-B2221-SUB-0.17-2	855.38	0.17 - 2 ft	180-80106-1	Excavated												
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-0.17-2	SSHS-B2224-SUB-0.17-2	854.93	0.17 - 2 ft	180-80227-2	Excavated												
Football Field	SSHS-B2225	072518 09:00_SSHS-B2225-SUB-0.17-2	SSHS-B2225-SUB-0.17-2	857.03	0.17 - 2 ft	180-80105-3	Excavated												
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-0.17-2	SSHS-B2226-SUB-0.17-2	856.56	0.17 - 2 ft	180-80227-1	Excavated												
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-0.17-2	SSHS-B2227-SUB-0.17-2	856.55	0.17 - 2 ft	180-80227-1	Excavated												
Football Field	SSHS-B2228	072818 11:30_PS-FD-53	PS-FD-53	855.33	0.17 - 2 ft	180-80252-2	Excavated												
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-0.17-2	SSHS-B2228-SUB-0.17-2	855.33	0.17 - 2 ft	180-80251-3	Excavated												
Football Field	SSHS-B2229	072818 11:30_SSHS-B2229-SUB-0.17-2	SSHS-B2229-SUB-0.17-2	855.28	0.17 - 2 ft	180-80252-1	Excavated												
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-0.17-2	SSHS-B2230-SUB-0.17-2	856.03	0.17 - 2 ft	180-80091-4	Excavated												
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-0.17-2	SSHS-B2231-SUB-0.17-2	856.14	0.17 - 2 ft	180-80091-2	Excavated												
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-0.17-2	SSHS-B2232-SUB-0.17-2	856.82	0.17 - 2 ft	180-80105-1	Excavated												
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-0.17-2	SSHS-B2233-SUB-0.17-2	854.83	0.17 - 2 ft	180-80105-1	Excavated												
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-0.17-2	SSHS-B2235-SUB-0.17-2	855.30	0.17 - 2 ft	180-80091-1	Excavated												
Football Field	SSHS-B2236	072818 11:30_SSHS-B2236-SUB-0.17-2	SSHS-B2236-SUB-0.17-2	855.25	0.17 - 2 ft	180-80251-3	Excavated												

DRAFT

								Emerging C											
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2237	072818 11:30_PS-FD-54	PS-FD-54	855.30	0.17 - 2 ft	180-80252-2	Excavated			< 350 U									
Football Field	SSHS-B2237	072818 11:30_SSHS-B2237-SUB-0.17-2	SSHS-B2237-SUB-0.17-2	855.30	0.17 - 2 ft	180-80252-1	Excavated			< 440 U									
Football Field	SSHS-B2238	072418 08:50_SSHS-B2238-SUB-0.17-2	SSHS-B2238-SUB-0.17-2	855.07	0.17 - 2 ft	180-80091-1	Excavated			< 16 U									
Football Field	SSHS-B2693	052119 08:40_SSHS-B2693-SUB-0.17-2	SSHS-B2693-SUB-0.17-2	857.04	0.17 - 2 ft	180-90324-1	Excavated			< 380 U									
Northern Athletic Field	SSHS-B2704	051719 09:00_SSHS-B2704-SUB-0.17-2	SSHS-B2704-SUB-0.17-2	855.37	0.17 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2705	051719 09:00_PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2705	051719 09:00_SSHS-B2705-SUB-0.17-2	SSHS-B2705-SUB-0.17-2	855.37	0.17 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2706	051719 09:00_SSHS-B2706-SUB-0.17-2	SSHS-B2706-SUB-0.17-2	854.96	0.17 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2707	051719 09:00_SSHS-B2707-SUB-0.17-2	SSHS-B2707-SUB-0.17-2	854.89	0.17 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2708	052219 08:40_SSHS-B2708-SUB-0.17-2	SSHS-B2708-SUB-0.17-2	855.05	0.17 - 2 ft	180-90380-1	Excavated			< 130 U									
Football Field	SSHS-B2709	052119 08:40_SSHS-B2709-SUB-0.17-2	SSHS-B2709-SUB-0.17-2	855.26	0.17 - 2 ft	180-90324-1	Excavated			< 110 U									
Football Field	SSHS-B2710	051719 09:00_SSHS-B2710-SUB-0.17-2	SSHS-B2710-SUB-0.17-2	855.48	0.17 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2711	051619 09:00_SSHS-B2711-SUB-0.17-2	SSHS-B2711-SUB-0.17-2	855.87	0.17 - 2 ft	180-90165-1	Excavated			< 130 U									
Football Field	SSHS-B2712	051619 09:00_SSHS-B2712-SUB-0.17-2	SSHS-B2712-SUB-0.17-2	856.23	0.17 - 2 ft	180-90165-1	Excavated			< 130 U									
Football Field	SSHS-B2713	051619 09:00_SSHS-B2713-SUB-0.17-2	SSHS-B2713-SUB-0.17-2	856.92	0.17 - 2 ft	180-90165-1	Excavated			< 130 U									
Football Field	SSHS-B2714	051619 09:00_SSHS-B2714-SUB-0.17-2	SSHS-B2714-SUB-0.17-2	857.01	0.17 - 2 ft	180-90165-1	Excavated			< 130 U									
Football Field	SSHS-B2715	051619 09:00_SSHS-B2715-SUB-0.17-2	SSHS-B2715-SUB-0.17-2	857.02	0.17 - 2 ft	180-90165-1	Excavated			< 130 U									
Football Field	SSHS-B2716	051619 09:00_SSHS-B2716-SUB-0.17-2	SSHS-B2716-SUB-0.17-2	856.77	0.17 - 2 ft	180-90165-1	Excavated			< 130 U									
Football Field	SSHS-B2717	051819 10:00_SSHS-B2717-SUB-0.17-2	SSHS-B2717-SUB-0.17-2	856.13	0.17 - 2 ft	180-90275-1	Excavated			< 620 U									
Football Field	SSHS-B2718	051719 09:00_SSHS-B2718-SUB-0.17-2	SSHS-B2718-SUB-0.17-2	855.30	0.17 - 2 ft	180-90231-1	Excavated			< 120 U									
Football Field	SSHS-B2719	051519 08:45_SSHS-B2719-SUB-0.17-2	SSHS-B2719-SUB-0.17-2	854.79	0.17 - 2 ft	180-90048-1	Excavated			< 120 U									
Football Field	SSHS-B2720	051519 08:45_SSHS-B2720-SUB-0.17-2	SSHS-B2720-SUB-0.17-2	854.80	0.17 - 2 ft	180-90048-1	Excavated			< 110 U									
Football Field	SSHS-B2721	051519 08:45_SSHS-B2721-SUB-0.17-2	SSHS-B2721-SUB-0.17-2	855.15	0.17 - 2 ft	180-90048-1	Excavated			< 120 U									
Football Field	SSHS-B2900	110719 09:00_SSHS-B2900-SUB-0.17-2	SSHS-B2900-SUB-0.17-2	855.76	0.17 - 2 ft	180-98355-2	Excavated			< 130 U									
Football Field	SSHS-B2901	110719 09:00_DUP-02	DUP-02	856.05	0.17 - 2 ft	180-98355-3	Excavated			< 130 U									
Football Field	SSHS-B2901	110719 09:00_SSHS-B2901-SUB-0.17-2	SSHS-B2901-SUB-0.17-2	856.05	0.17 - 2 ft	180-98355-2	Excavated			< 120 U									
Football Field	SSHS-B2911	110719 09:00_SSHS-B2911-SUB-0.17-2	SSHS-B2911-SUB-0.17-2	854.88	0.17 - 2 ft	180-98355-2	Excavated			< 120 U									
Football Field	SSHS-B2912	110719 09:00_DUP-04	DUP-04	855.19	0.17 - 2 ft	180-98355-3	Excavated			< 480 U									
Football Field	SSHS-B2912	110719 09:00_SSHS-B2912-SUB-0.17-2	SSHS-B2912-SUB-0.17-2	855.19	0.17 - 2 ft	180-98355-1	Excavated			< 990 U									
Football Field	SSHS-B2938	110719 09:00_SSHS-B2938-SUB-0.17-2	SSHS-B2938-SUB-0.17-2	855.53	0.17 - 2 ft	180-98355-3	Excavated			< 120 U									
Football Field	SSHS-B2939	110719 09:00_SSHS-B2939-SUB-0.17-2	SSHS-B2939-SUB-0.17-2	855.56	0.17 - 2 ft	180-98355-3	Excavated			< 370 U									
Football Field	SSHS-B2940	110719 09:00_SSHS-B2940-SUB-0.17-2	SSHS-B2940-SUB-0.17-2	855.06	0.17 - 2 ft	180-98355-3	Excavated			< 120 U									
Football Field	SSHS-B2941	110719 09:00_SSHS-B2941-SUB-0.17-2	SSHS-B2941-SUB-0.17-2	855.17	0.17 - 2 ft	180-98355-3	Excavated			< 230 U									
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-0.17-2	SSHS-B3001-SUB-0.17-2	853.35	0.17 - 2 ft	180-95155-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-0.17-2	SSHS-B3002-SUB-0.17-2	853.09	0.17 - 2 ft	180-95155-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-0.17-2	SSHS-B3003-SUB-0.17-2	851.95	0.17 - 2 ft	180-95047-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-0.17-2	SSHS-B3007-SUB-0.17-2	852.58	0.17 - 2 ft	180-94824-3	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-0.17-2	SSHS-B3009-SUB-0.17-2	853.88	0.17 - 2 ft	180-95155-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-0.17-2	SSHS-B3010-SUB-0.17-2	854.13	0.17 - 2 ft	180-95155-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-0.17-2	SSHS-B3011-SUB-0.17-2	853.85	0.17 - 2 ft	180-95047-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-0.17-2	SSHS-B3012-SUB-0.17-2	853.28	0.17 - 2 ft	180-95047-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-0.17-2	SSHS-B3013-SUB-0.17-2	852.90	0.17 - 2 ft	180-94981-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3014	083019 09:00_SSHS-B3014-SUB-0.17-2	SSHS-B3014-SUB-0.17-2	853.35	0.17 - 2 ft	180-94981-2	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3015	082919 09:10_SSHS-B3015-SUB-0.17-2	SSHS-B3015-SUB-0.17-2	853.51	0.17 - 2 ft	180-94902-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-0.17-2	SSHS-B3016-SUB-0.17-2	853.54	0.17 - 2 ft	180-94981-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-0.17-2	SSHS-B3017-SUB-0.17-2	853.78	0.17 - 2 ft	180-94900-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-0.17-2	SSHS-B3018-SUB-0.17-2	853.82	0.17 - 2 ft	180-94829-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-0.17-2	SSHS-B3019-SUB-0.17-2	854.09	0.17 - 2 ft	180-94824-3	Excavated			< 240 U									
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-0.17-2	SSHS-B3020-SUB-0.17-2	853.86	0.17 - 2 ft	180-94824-2	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	082719 09:30_SSHS-B3021-SUB-0.17-2	853.71	0.17 - 2 ft	180-94752-2	Excavated			< 570 U									
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-0.17-2	SSHS-B3022-SUB-0.17-2	853.76	0.17 - 2 ft	180-94754-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-0.17-2	SSHS-B3023-SUB-0.17-2	854.48	0.17 - 2 ft	180-95155-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-0.17-2	SSHS-B3025-SUB-0.17-2	854.59	0.17 - 2 ft	180-95047-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-0.17-2	SSHS-B3026-SUB-0.17-2	854.13	0.17 - 2 ft	180-94981-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-0.17-2	SSHS-B3028-SUB-0.17-2	854.60	0.17 - 2 ft	180-94981-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-0.17-2	SSHS-B3030-SUB-0.17-2	855.22	0.17 - 2 ft	180-94902-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-0.17-2	SSHS-B3031-SUB-0.17-2	855.08	0.17 - 2 ft	180-94824-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-0.17-2	SSHS-B3033-SUB-0.17-2	855.17	0.17 - 2 ft	180-94824-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-0.17-2	SSHS-B3034-SUB-0.17-2	855.10	0.17 - 2 ft	180-94752-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-0.17-2	SSHS-B3035-SUB-0.17-2	854.81	0.17 - 2 ft	180-94752-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-0.17-2	SSHS-B3036-SUB-0.17-2	855.09	0.17 - 2 ft	180-95155-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3037	090419 03:44_SSHS-B3037-SUB-0.17-2	SSHS-B3037-SUB-0.17-2	855.60	0.17 - 2 ft	180-95155-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-0.17-2	SSHS-B3038-SUB-0.17-2	855.76	0.17 - 2 ft	180-95162-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-0.17-2	SSHS-B3039-SUB-0.17-2	855.85	0.17 - 2 ft	180-95047-1	Excavated			< 120 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2237	072818 11:30_PS-FD-54	PS-FD-54	855.30	0.17 - 2 ft	180-80252-2	Excavated												
Football Field	SSHS-B2237	072818 11:30_SSHS-B2237-SUB-0.17-2	SSHS-B2237-SUB-0.17-2	855.30	0.17 - 2 ft	180-80252-1	Excavated												
Football Field	SSHS-B2238	072418 08:50_SSHS-B2238-SUB-0.17-2	SSHS-B2238-SUB-0.17-2	855.07	0.17 - 2 ft	180-80091-1	Excavated												
Football Field	SSHS-B2693	052119 08:40_SSHS-B2693-SUB-0.17-2	SSHS-B2693-SUB-0.17-2	857.04	0.17 - 2 ft	180-90324-1	Excavated												
Northern Athletic Field	SSHS-B2704	051719 09:00_SSHS-B2704-SUB-0.17-2	SSHS-B2704-SUB-0.17-2	855.37	0.17 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2705	051719 09:00_PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2705	051719 09:00_SSHS-B2705-SUB-0.17-2	SSHS-B2705-SUB-0.17-2	855.37	0.17 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2706	051719 09:00_SSHS-B2706-SUB-0.17-2	SSHS-B2706-SUB-0.17-2	854.96	0.17 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2707	051719 09:00_SSHS-B2707-SUB-0.17-2	SSHS-B2707-SUB-0.17-2	854.89	0.17 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2708	052219 08:40_SSHS-B2708-SUB-0.17-2	SSHS-B2708-SUB-0.17-2	855.05	0.17 - 2 ft	180-90380-1	Excavated												
Football Field	SSHS-B2709	052119 08:40_SSHS-B2709-SUB-0.17-2	SSHS-B2709-SUB-0.17-2	855.26	0.17 - 2 ft	180-90324-1	Excavated												
Football Field	SSHS-B2710	051719 09:00_SSHS-B2710-SUB-0.17-2	SSHS-B2710-SUB-0.17-2	855.48	0.17 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2711	051619 09:00_SSHS-B2711-SUB-0.17-2	SSHS-B2711-SUB-0.17-2	855.87	0.17 - 2 ft	180-90165-1	Excavated												
Football Field	SSHS-B2712	051619 09:00_SSHS-B2712-SUB-0.17-2	SSHS-B2712-SUB-0.17-2	856.23	0.17 - 2 ft	180-90165-1	Excavated												
Football Field	SSHS-B2713	051619 09:00_SSHS-B2713-SUB-0.17-2	SSHS-B2713-SUB-0.17-2	856.92	0.17 - 2 ft	180-90165-1	Excavated												
Football Field	SSHS-B2714	051619 09:00_SSHS-B2714-SUB-0.17-2	SSHS-B2714-SUB-0.17-2	857.01	0.17 - 2 ft	180-90165-1	Excavated												
Football Field	SSHS-B2715	051619 09:00_SSHS-B2715-SUB-0.17-2	SSHS-B2715-SUB-0.17-2	857.02	0.17 - 2 ft	180-90165-1	Excavated												
Football Field	SSHS-B2716	051619 09:00_SSHS-B2716-SUB-0.17-2	SSHS-B2716-SUB-0.17-2	856.77	0.17 - 2 ft	180-90165-1	Excavated												
Football Field	SSHS-B2717	051819 10:00_SSHS-B2717-SUB-0.17-2	SSHS-B2717-SUB-0.17-2	856.13	0.17 - 2 ft	180-90275-1	Excavated												
Football Field	SSHS-B2718	051719 09:00_SSHS-B2718-SUB-0.17-2	SSHS-B2718-SUB-0.17-2	855.30	0.17 - 2 ft	180-90231-1	Excavated												
Football Field	SSHS-B2719	051519 08:45_SSHS-B2719-SUB-0.17-2	SSHS-B2719-SUB-0.17-2	854.79	0.17 - 2 ft	180-90048-1	Excavated												
Football Field	SSHS-B2720	051519 08:45_SSHS-B2720-SUB-0.17-2	SSHS-B2720-SUB-0.17-2	854.80	0.17 - 2 ft	180-90048-1	Excavated												
Football Field	SSHS-B2721	051519 08:45_SSHS-B2721-SUB-0.17-2	SSHS-B2721-SUB-0.17-2	855.15	0.17 - 2 ft	180-90048-1	Excavated												
Football Field	SSHS-B2900	110719 09:00_SSHS-B2900-SUB-0.17-2	SSHS-B2900-SUB-0.17-2	855.76	0.17 - 2 ft	180-98355-2	Excavated												
Football Field	SSHS-B2901	110719 09:00_DUP-02	DUP-02	856.05	0.17 - 2 ft	180-98355-3	Excavated												
Football Field	SSHS-B2901	110719 09:00_SSHS-B2901-SUB-0.17-2	SSHS-B2901-SUB-0.17-2	856.05	0.17 - 2 ft	180-98355-2	Excavated												
Football Field	SSHS-B2911	110719 09:00_SSHS-B2911-SUB-0.17-2	SSHS-B2911-SUB-0.17-2	854.88	0.17 - 2 ft	180-98355-2	Excavated												
Football Field	SSHS-B2912	110719 09:00_DUP-04	DUP-04	855.19	0.17 - 2 ft	180-98355-3	Excavated												
Football Field	SSHS-B2912	110719 09:00_SSHS-B2912-SUB-0.17-2	SSHS-B2912-SUB-0.17-2	855.19	0.17 - 2 ft	180-98355-1	Excavated												
Football Field	SSHS-B2938	110719 09:00_SSHS-B2938-SUB-0.17-2	SSHS-B2938-SUB-0.17-2	855.53	0.17 - 2 ft	180-98355-3	Excavated												
Football Field	SSHS-B2939	110719 09:00_SSHS-B2939-SUB-0.17-2	SSHS-B2939-SUB-0.17-2	855.56	0.17 - 2 ft	180-98355-3	Excavated												
Football Field	SSHS-B2940	110719 09:00_SSHS-B2940-SUB-0.17-2	SSHS-B2940-SUB-0.17-2	855.06	0.17 - 2 ft	180-98355-3	Excavated												
Football Field	SSHS-B2941	110719 09:00_SSHS-B2941-SUB-0.17-2	SSHS-B2941-SUB-0.17-2	855.17	0.17 - 2 ft	180-98355-3	Excavated												
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-0.17-2	SSHS-B3001-SUB-0.17-2	853.35	0.17 - 2 ft	180-95155-1	Excavated												
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-0.17-2	SSHS-B3002-SUB-0.17-2	853.09	0.17 - 2 ft	180-95155-1	Excavated												
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-0.17-2	SSHS-B3003-SUB-0.17-2	851.95	0.17 - 2 ft	180-95047-3	Excavated												
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-0.17-2	SSHS-B3007-SUB-0.17-2	852.58	0.17 - 2 ft	180-94824-3	Excavated												
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-0.17-2	SSHS-B3009-SUB-0.17-2	853.88	0.17 - 2 ft	180-95155-3	Excavated												
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-0.17-2	SSHS-B3010-SUB-0.17-2	854.13	0.17 - 2 ft	180-95155-2	Excavated												
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-0.17-2	SSHS-B3011-SUB-0.17-2	853.85	0.17 - 2 ft	180-95047-3	Excavated												
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-0.17-2	SSHS-B3012-SUB-0.17-2	853.28	0.17 - 2 ft	180-95047-2	Excavated												
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-0.17-2	SSHS-B3013-SUB-0.17-2	852.90	0.17 - 2 ft	180-94981-1	Excavated												
Northern Athletic Field	SSHS-B3014	083019 09:00_SSHS-B3014-SUB-0.17-2	SSHS-B3014-SUB-0.17-2	853.35	0.17 - 2 ft	180-94981-2	Excavated												
Northern Athletic Field	SSHS-B3015	082919 09:10_SSHS-B3015-SUB-0.17-2	SSHS-B3015-SUB-0.17-2	853.51	0.17 - 2 ft	180-94902-3	Excavated												
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-0.17-2	SSHS-B3016-SUB-0.17-2	853.54	0.17 - 2 ft	180-94981-2	Excavated												
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-0.17-2	SSHS-B3017-SUB-0.17-2	853.78	0.17 - 2 ft	180-94900-2	Excavated												
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-0.17-2	SSHS-B3018-SUB-0.17-2	853.82	0.17 - 2 ft	180-94829-1	Excavated												
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-0.17-2	SSHS-B3019-SUB-0.17-2	854.09	0.17 - 2 ft	180-94824-3	Excavated												
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-0.17-2	SSHS-B3020-SUB-0.17-2	853.86	0.17 - 2 ft	180-94824-2	Excavated												
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-0.17-2	082719 09:30_SSHS-B3021-SUB-0.17-2	853.71	0.17 - 2 ft	180-94752-2	Excavated												
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-0.17-2	SSHS-B3022-SUB-0.17-2	853.76	0.17 - 2 ft	180-94754-3	Excavated												
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-0.17-2	SSHS-B3023-SUB-0.17-2	854.48	0.17 - 2 ft	180-95155-2	Excavated												
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-0.17-2	SSHS-B3025-SUB-0.17-2	854.59	0.17 - 2 ft	180-95047-1	Excavated												
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-0.17-2	SSHS-B3026-SUB-0.17-2	854.13	0.17 - 2 ft	180-94981-3	Excavated												
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-0.17-2	SSHS-B3028-SUB-0.17-2	854.60	0.17 - 2 ft	180-94981-2	Excavated												
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-0.17-2	SSHS-B3030-SUB-0.17-2	855.22	0.17 - 2 ft	180-94902-1	Excavated												
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-0.17-2	SSHS-B3031-SUB-0.17-2	855.08	0.17 - 2 ft	180-94824-2	Excavated												
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-0.17-2	SSHS-B3033-SUB-0.17-2	855.17	0.17 - 2 ft	180-94824-1	Excavated												
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-0.17-2	SSHS-B3034-SUB-0.17-2	855.10	0.17 - 2 ft	180-94752-2	Excavated												
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-0.17-2	SSHS-B3035-SUB-0.17-2	854.81	0.17 - 2 ft	180-94752-1	Excavated												
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-0.17-2	SSHS-B3036-SUB-0.17-2	855.09	0.17 - 2 ft	180-95155-2	Excavated												
Northern Athletic Field	SSHS-B3037	090419 03:44_SSHS-B3037-SUB-0.17-2	SSHS-B3037-SUB-0.17-2	855.60	0.17 - 2 ft	180-95155-1	Excavated												
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-0.17-2	SSHS-B3038-SUB-0.17-2	855.76	0.17 - 2 ft	180-95162-1	Excavated												
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-0.17-2	SSHS-B3039-SUB-0.17-2	855.85	0.17 - 2 ft	180-95047-1	Excavated												

DRAFT

								Emerging C										
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorodecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-0.17-2	SSHS-B3040-SUB-0.17-2	855.10	0.17 - 2 ft	180-94981-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-0.17-2	SSHS-B3041-SUB-0.17-2	855.17	0.17 - 2 ft	180-94981-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3042	082919 09:10_SSHS-B3042-SUB-0.17-2	SSHS-B3042-SUB-0.17-2	855.23	0.17 - 2 ft	180-94902-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-0.17-2	SSHS-B3043-SUB-0.17-2	855.78	0.17 - 2 ft	180-94902-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-0.17-2	SSHS-B3044-SUB-0.17-2	856.00	0.17 - 2 ft	180-94900-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-0.17-2	SSHS-B3045-SUB-0.17-2	856.03	0.17 - 2 ft	180-94900-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-0.17-2	SSHS-B3046-SUB-0.17-2	856.22	0.17 - 2 ft	180-94824-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-0.17-2	SSHS-B3047-SUB-0.17-2	856.24	0.17 - 2 ft	180-94819-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-0.17-2	SSHS-B3048-SUB-0.17-2	856.08	0.17 - 2 ft	180-94819-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-0.17-2	SSHS-B3049-SUB-0.17-2	856.17	0.17 - 2 ft	180-94754-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-0.17-2	SSHS-B3050-SUB-0.17-2	855.60	0.17 - 2 ft	180-94752-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-0.17-2	SSHS-B3051-SUB-0.17-2	855.15	0.17 - 2 ft	180-95165-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-0.17-2	SSHS-B3052-SUB-0.17-2	855.98	0.17 - 2 ft	180-95155-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-0.17-2	SSHS-B3053-SUB-0.17-2	856.41	0.17 - 2 ft	180-95155-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-0.17-2	SSHS-B3054-SUB-0.17-2	856.01	0.17 - 2 ft	180-95024-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-0.17-2	SSHS-B3055-SUB-0.17-2	856.20	0.17 - 2 ft	180-95006-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-0.17-2	SSHS-B3056-SUB-0.17-2	855.88	0.17 - 2 ft	180-94981-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-0.17-2	SSHS-B3057-SUB-0.17-2	856.09	0.17 - 2 ft	180-94900-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-0.17-2	SSHS-B3058-SUB-0.17-2	856.47	0.17 - 2 ft	180-94902-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-0.17-2	SSHS-B3059-SUB-0.17-2	856.71	0.17 - 2 ft	180-94902-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-B3060-SUB-0.17-2	SSHS-B3060-SUB-0.17-2	856.96	0.17 - 2 ft	180-94900-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-0.17-2	SSHS-B3061-SUB-0.17-2	857.02	0.17 - 2 ft	180-94824-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-0.17-2	SSHS-B3062-SUB-0.17-2	856.91	0.17 - 2 ft	180-94819-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-0.17-2	SSHS-B3063-SUB-0.17-2	856.95	0.17 - 2 ft	180-94819-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-0.17-2	SSHS-B3064-SUB-0.17-2	856.77	0.17 - 2 ft	180-94754-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-0.17-2	SSHS-B3065-SUB-0.17-2	856.77	0.17 - 2 ft	180-94752-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-0.17-2	SSHS-B3066-SUB-0.17-2	855.86	0.17 - 2 ft	180-95165-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-0.17-2	SSHS-B3067-SUB-0.17-2	856.40	0.17 - 2 ft	180-95162-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-0.17-2	SSHS-B3068-SUB-0.17-2	856.38	0.17 - 2 ft	180-95050-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-0.17-2	SSHS-B3071-SUB-0.17-2	856.76	0.17 - 2 ft	180-94900-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	082919 09:10_SSHS-DUP-27	857.14	0.17 - 2 ft	180-94903-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	SSHS-B3073-SUB-0.17-2	857.14	0.17 - 2 ft	180-94900-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-0.17-2	SSHS-B3074-SUB-0.17-2	857.18	0.17 - 2 ft	180-94824-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-0.17-2	SSHS-B3076-SUB-0.17-2	856.92	0.17 - 2 ft	180-94819-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3077	082719 09:30_SSHS-B3077-SUB-0.17-2	SSHS-B3077-SUB-0.17-2	856.86	0.17 - 2 ft	180-94752-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-0.17-2	SSHS-B3079-SUB-0.17-2	856.36	0.17 - 2 ft	180-95024-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-0.17-2	SSHS-B3080-SUB-0.17-2	856.58	0.17 - 2 ft	180-95165-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-0.17-2	SSHS-B3081-SUB-0.17-2	856.96	0.17 - 2 ft	180-95165-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-0.17-2	SSHS-B3082-SUB-0.17-2	856.73	0.17 - 2 ft	180-95047-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-0.17-2	SSHS-B3083-SUB-0.17-2	857.13	0.17 - 2 ft	180-95024-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-0.17-2	SSHS-B3084-SUB-0.17-2	856.55	0.17 - 2 ft	180-95006-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-0.17-2	SSHS-B3085-SUB-0.17-2	857.12	0.17 - 2 ft	180-95165-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-0.17-2	SSHS-B3086-SUB-0.17-2	857.77	0.17 - 2 ft	180-95165-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-0.17-2	SSHS-B3087-SUB-0.17-2	857.68	0.17 - 2 ft	180-95047-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-0.17-2	SSHS-B3095-SUB-0.17-2	857.12	0.17 - 2 ft	180-94902-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-0.17-2	SSHS-B3096-SUB-0.17-2	855.86	0.17 - 2 ft	180-94819-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-0.17-2	SSHS-B3097-SUB-0.17-2	856.19	0.17 - 2 ft	180-94819-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-0.17-2	SSHS-B3098-SUB-0.17-2	855.97	0.17 - 2 ft	180-94754-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-0.17-2	SSHS-B3100-SUB-0.5-2	856.74	0.17 - 2 ft	180-100985-1	Excavated			< 2800 UJ									
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	SSHS-B3100-SUB-0.5-2	856.74	0.17 - 2 ft	180-100985-1	Excavated			< 2800 UJ									
Northern Athletic Field	SSHS-B3101	011420 09:00_DUP-02	DUP-02	856.05	0.17 - 2 ft	180-100985-2	Excavated			< 2400 UJ									
Northern Athletic Field	SSHS-B3104	011420 09:00_DUP-04	DUP-04	855.19	0.17 - 2 ft	180-100985-2	Excavated			< 2900 UJ									
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-0.17-2	SSHS-B3107-SUB-0.17-2	857.05	0.17 - 2 ft	180-101084-1	Excavated			< 1200 U									
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-0.17-2	SSHS-B3108-SUB-0.17-2	857.55	0.17 - 2 ft	180-101038-3	Excavated			< 120 UJ									
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-0.17-2	SSHS-B3109-SUB-0.17-2	857.26	0.17 - 2 ft	180-101084-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-0.17-2	SSHS-B3110-SUB-0.17-2	856.32	0.17 - 2 ft	180-101084-2	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-0.17-2	SSHS-B3111-SUB-0.17-2	857.08	0.17 - 2 ft	180-101084-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-0.17-2	SSHS-B3112-SUB-0.17-2	856.71	0.17 - 2 ft	180-101084-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-0.17-2	SSHS-B3113-SUB-0.17-2	856.36	0.17 - 2 ft	180-101038-2	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-0.17-2	SSHS-B3181-SUB-0.17-2	857.57	0.17 - 2 ft	180-95006-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-0.17-2	SSHS-B3182-SUB-0.17-2	857.45	0.17 - 2 ft	180-95024-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-0.17-2	SSHS-B3184-SUB-0.17-2	856.85	0.17 - 2 ft	180-101038-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-0.17-2	SSHS-B3214-SUB-0.17-2	855.06	0.17 - 2 ft	180-95050-1	Excavated			< 150 U									
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-0.17-2	SSHS-B3220-SUB-0.17-2	857.44	0.17 - 2 ft	180-95165-3	Excavated			< 120 U									

DRAFT

TABLE 5-5E
Shallow Subsurface Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Contaminants											
								Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-0.17-2	SSHS-B3040-SUB-0.17-2	855.10	0.17 - 2 ft	180-94981-3	Excavated												
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-0.17-2	SSHS-B3041-SUB-0.17-2	855.17	0.17 - 2 ft	180-94981-1	Excavated												
Northern Athletic Field	SSHS-B3042	082919 09:10_SSHS-B3042-SUB-0.17-2	SSHS-B3042-SUB-0.17-2	855.23	0.17 - 2 ft	180-94902-1	Excavated												
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-0.17-2	SSHS-B3043-SUB-0.17-2	855.78	0.17 - 2 ft	180-94902-2	Excavated												
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-0.17-2	SSHS-B3044-SUB-0.17-2	856.00	0.17 - 2 ft	180-94900-1	Excavated												
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-0.17-2	SSHS-B3045-SUB-0.17-2	856.03	0.17 - 2 ft	180-94900-3	Excavated												
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-0.17-2	SSHS-B3046-SUB-0.17-2	856.22	0.17 - 2 ft	180-94824-1	Excavated												
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-0.17-2	SSHS-B3047-SUB-0.17-2	856.24	0.17 - 2 ft	180-94819-1	Excavated												
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-0.17-2	SSHS-B3048-SUB-0.17-2	856.08	0.17 - 2 ft	180-94819-2	Excavated												
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-0.17-2	SSHS-B3049-SUB-0.17-2	856.17	0.17 - 2 ft	180-94754-2	Excavated												
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-0.17-2	SSHS-B3050-SUB-0.17-2	855.60	0.17 - 2 ft	180-94752-1	Excavated												
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-0.17-2	SSHS-B3051-SUB-0.17-2	855.15	0.17 - 2 ft	180-95165-1	Excavated												
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-0.17-2	SSHS-B3052-SUB-0.17-2	855.98	0.17 - 2 ft	180-95155-3	Excavated												
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-0.17-2	SSHS-B3053-SUB-0.17-2	856.41	0.17 - 2 ft	180-95155-3	Excavated												
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-0.17-2	SSHS-B3054-SUB-0.17-2	856.01	0.17 - 2 ft	180-95024-2	Excavated												
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-0.17-2	SSHS-B3055-SUB-0.17-2	856.20	0.17 - 2 ft	180-95006-1	Excavated												
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-0.17-2	SSHS-B3056-SUB-0.17-2	855.88	0.17 - 2 ft	180-94981-1	Excavated												
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-0.17-2	SSHS-B3057-SUB-0.17-2	856.09	0.17 - 2 ft	180-94900-3	Excavated												
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-0.17-2	SSHS-B3058-SUB-0.17-2	856.47	0.17 - 2 ft	180-94902-2	Excavated												
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-0.17-2	SSHS-B3059-SUB-0.17-2	856.71	0.17 - 2 ft	180-94902-1	Excavated												
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-B3060-SUB-0.17-2	SSHS-B3060-SUB-0.17-2	856.96	0.17 - 2 ft	180-94900-2	Excavated												
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-0.17-2	SSHS-B3061-SUB-0.17-2	857.02	0.17 - 2 ft	180-94824-1	Excavated												
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-0.17-2	SSHS-B3062-SUB-0.17-2	856.91	0.17 - 2 ft	180-94819-3	Excavated												
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-0.17-2	SSHS-B3063-SUB-0.17-2	856.95	0.17 - 2 ft	180-94819-1	Excavated												
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-0.17-2	SSHS-B3064-SUB-0.17-2	856.77	0.17 - 2 ft	180-94754-1	Excavated												
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-0.17-2	SSHS-B3065-SUB-0.17-2	856.77	0.17 - 2 ft	180-94752-3	Excavated												
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-0.17-2	SSHS-B3066-SUB-0.17-2	855.86	0.17 - 2 ft	180-95165-1	Excavated												
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-0.17-2	SSHS-B3067-SUB-0.17-2	856.40	0.17 - 2 ft	180-95162-1	Excavated												
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-0.17-2	SSHS-B3068-SUB-0.17-2	856.38	0.17 - 2 ft	180-95050-1	Excavated												
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-0.17-2	SSHS-B3071-SUB-0.17-2	856.76	0.17 - 2 ft	180-94900-2	Excavated												
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-27	082919 09:10_SSHS-DUP-27	857.14	0.17 - 2 ft	180-94903-1	Excavated												
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-0.17-2	SSHS-B3073-SUB-0.17-2	857.14	0.17 - 2 ft	180-94900-1	Excavated												
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-0.17-2	SSHS-B3074-SUB-0.17-2	857.18	0.17 - 2 ft	180-94824-2	Excavated												
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-0.17-2	SSHS-B3076-SUB-0.17-2	856.92	0.17 - 2 ft	180-94819-2	Excavated												
Northern Athletic Field	SSHS-B3077	082719 09:30_SSHS-B3077-SUB-0.17-2	SSHS-B3077-SUB-0.17-2	856.86	0.17 - 2 ft	180-94752-2	Excavated												
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-0.17-2	SSHS-B3079-SUB-0.17-2	856.36	0.17 - 2 ft	180-95024-1	Excavated												
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-0.17-2	SSHS-B3080-SUB-0.17-2	856.58	0.17 - 2 ft	180-95165-1	Excavated												
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-0.17-2	SSHS-B3081-SUB-0.17-2	856.96	0.17 - 2 ft	180-95165-2	Excavated												
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-0.17-2	SSHS-B3082-SUB-0.17-2	856.73	0.17 - 2 ft	180-95047-3	Excavated												
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-0.17-2	SSHS-B3083-SUB-0.17-2	857.13	0.17 - 2 ft	180-95024-1	Excavated												
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-0.17-2	SSHS-B3084-SUB-0.17-2	856.55	0.17 - 2 ft	180-95006-1	Excavated												
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-0.17-2	SSHS-B3085-SUB-0.17-2	857.12	0.17 - 2 ft	180-95165-3	Excavated												
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-0.17-2	SSHS-B3086-SUB-0.17-2	857.77	0.17 - 2 ft	180-95165-2	Excavated												
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-0.17-2	SSHS-B3087-SUB-0.17-2	857.68	0.17 - 2 ft	180-95047-2	Excavated												
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-0.17-2	SSHS-B3095-SUB-0.17-2	857.12	0.17 - 2 ft	180-94902-1	Excavated												
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-0.17-2	SSHS-B3096-SUB-0.17-2	855.86	0.17 - 2 ft	180-94819-3	Excavated												
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-0.17-2	SSHS-B3097-SUB-0.17-2	856.19	0.17 - 2 ft	180-94819-3	Excavated												
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-0.17-2	SSHS-B3098-SUB-0.17-2	855.97	0.17 - 2 ft	180-94754-1	Excavated												
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-0.17-2	SSHS-B3100-SUB-0.5-2	856.74	0.17 - 2 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-0.5-2	SSHS-B3100-SUB-0.5-2	856.74	0.17 - 2 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3101	011420 09:00_DUP-02	DUP-02	856.05	0.17 - 2 ft	180-100985-2	Excavated												
Northern Athletic Field	SSHS-B3104	011420 09:00_DUP-04	DUP-04	855.19	0.17 - 2 ft	180-100985-2	Excavated												
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-0.17-2	SSHS-B3107-SUB-0.17-2	857.05	0.17 - 2 ft	180-101084-1	Excavated												
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-0.17-2	SSHS-B3108-SUB-0.17-2	857.55	0.17 - 2 ft	180-101038-3	Excavated												
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-0.17-2	SSHS-B3109-SUB-0.17-2	857.26	0.17 - 2 ft	180-101084-2	Excavated												
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-0.17-2	SSHS-B3110-SUB-0.17-2	856.32	0.17 - 2 ft	180-101084-2	Excavated												
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-0.17-2	SSHS-B3111-SUB-0.17-2	857.08	0.17 - 2 ft	180-101084-1	Excavated												
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-0.17-2	SSHS-B3112-SUB-0.17-2	856.71	0.17 - 2 ft	180-101084-2	Excavated												
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-0.17-2	SSHS-B3113-SUB-0.17-2	856.36	0.17 - 2 ft	180-101038-2	Excavated												
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-0.17-2	SSHS-B3181-SUB-0.17-2	857.57	0.17 - 2 ft	180-95006-3	Excavated												
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-0.17-2	SSHS-B3182-SUB-0.17-2	857.45	0.17 - 2 ft	180-95024-1	Excavated												
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-0.17-2	SSHS-B3184-SUB-0.17-2	856.85	0.17 - 2 ft	180-101038-2	Excavated												
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-0.17-2	SSHS-B3214-SUB-0.17-2	855.06	0.17 - 2 ft	180-95050-1	Excavated												
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-0.17-2	SSHS-B3220-SUB-0.17-2	857.44	0.17 - 2 ft	180-95165-3	Excavated												

DRAFT

								Emerging C											
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-0.17-2	SSHS-B3221-SUB-0.17-2	857.92	0.17 - 2 ft	180-95165-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-0.17-2	SSHS-B3222-SUB-0.17-2	858.28	0.17 - 2 ft	180-95047-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-0.17-2	SSHS-B3223-SUB-0.17-2	858.27	0.17 - 2 ft	180-95006-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-0.17-2	SSHS-B3224-SUB-0.17-2	858.38	0.17 - 2 ft	180-95050-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3225	122119 10:30_SSHS-B3225-SUB-0.17-2	SSHS-B3225-SUB-0.17-2	853.42	0.17 - 2 ft	180-100361-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3226	122119 10:30_SSHS-B3226-SUB-0.17-2	SSHS-B3226-SUB-0.17-2	853.22	0.17 - 2 ft	180-100362-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3227	122119 10:30_SSHS-B3227-SUB-0.17-2	SSHS-B3227-SUB-0.17-2	853.19	0.17 - 2 ft	180-100361-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3228	122119 10:30_SSHS-B3228-SUB-0.17-2	SSHS-B3228-SUB-0.17-2	853.57	0.17 - 2 ft	180-100362-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-0.17-2	SSHS-B3244-SUB-0.17-2	857.74	0.17 - 2 ft	180-100363-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-0.17-2	SSHS-B3245-SUB-0.17-2	857.37	0.17 - 2 ft	180-100363-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-0.17-2	SSHS-B3246-SUB-0.17-2	858.13	0.17 - 2 ft	180-100363-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3247	122119 10:30_SSHS-B-3247-SUB-0.17-2	SSHS-B-3247-SUB-0.17-2	857.57	0.17 - 2 ft	180-100363-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3249	122119 10:30_SSHS-B3249-SUB-0.17-2	SSHS-B3249-SUB-0.17-2	857.44	0.17 - 2 ft	180-100363-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-0.17-2	SSHS-B3250-SUB-0.17-2	858.02	0.17 - 2 ft	180-100363-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-0.17-2	SSHS-B3252-SUB-0.17-2	857.46	0.17 - 2 ft	180-100363-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-0.17-2	SSHS-B3253-SUB-0.17-2	858.40	0.17 - 2 ft	180-100363-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-0.17-2	SSHS-B3255-SUB-0.17-2	857.06	0.17 - 2 ft	180-100363-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3256	122119 10:30_SSHS-B3256-SUB-0.17-2	SSHS-B3256-SUB-0.17-2	858.14	0.17 - 2 ft	180-100363-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3257	122119 10:30_SSHS-B3257-SUB-0.17-2	SSHS-B3257-SUB-0.17-2	858.41	0.17 - 2 ft	180-100363-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3259	122119 10:30_SSHS-B3259-SUB-0.17-2	SSHS-B3259-SUB-0.17-2	857.33	0.17 - 2 ft	180-100363-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-0.17-2	SSHS-B3260-SUB-0.17-2	858.57	0.17 - 2 ft	180-100363-1	Excavated			< 420 U									
Northern Athletic Field	SSHS-B3261	122119 10:30_SSHS-B3261-SUB-0.17-2	SSHS-B3261-SUB-0.17-2	856.31	0.17 - 2 ft	180-100380-2	Excavated			< 370 U									
Northern Athletic Field	SSHS-B3262	122119 10:30_SSHS-B3262-SUB-0.17-2	SSHS-B3262-SUB-0.17-2	857.03	0.17 - 2 ft	180-100380-2	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3263	122119 10:30_SSHS-B3263-SUB-0.17-2	SSHS-B3263-SUB-0.17-2	857.52	0.17 - 2 ft	180-100380-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3265	122119 10:30_SSHS-B3265-SUB-0.17-2	SSHS-B3265-SUB-0.17-2	854.04	0.17 - 2 ft	180-100380-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3268	122119 10:30_SSHS-B3268-SUB-0.17-2	SSHS-B3268-SUB-0.17-2	854.73	0.17 - 2 ft	180-100380-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3269	122119 10:30_SSHS-B3269-SUB-0.17-2	SSHS-B3269-SUB-0.17-2	854.73	0.17 - 2 ft	180-100380-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-0.17-2	SSHS-B3272-SUB-0.17-2	856.00	0.17 - 2 ft	180-100380-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3274	122119 10:30_SSHS-B3274-SUB-0.17-2	SSHS-B3274-SUB-0.17-2	855.80	0.17 - 2 ft	180-100380-1	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-0.17-2	SSHS-B3275-SUB-0.17-2	856.25	0.17 - 2 ft	180-100380-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-0.17-2	SSHS-B3276-SUB-0.17-2	856.44	0.17 - 2 ft	180-100380-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3278	122119 10:30_SSHS-B3278-SUB-0.17-2	SSHS-B3278-SUB-0.17-2	856.22	0.17 - 2 ft	180-100380-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-0.17-2	SSHS-B3280-SUB-0.17-2	856.56	0.17 - 2 ft	180-100380-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-0.17-2	SSHS-B3281-SUB-0.17-2	856.88	0.17 - 2 ft	180-100380-2	Excavated			< 140 U									
Northern Athletic Field	SSHS-B3282	122119 10:30_SSHS-B3282-SUB-0.17-2	SSHS-B3282-SUB-0.17-2	856.89	0.17 - 2 ft	180-100380-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-0.17-2	SSHS-B3283-SUB-0.17-2	856.35	0.17 - 2 ft	180-100380-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-0.17-2	SSHS-B3284-SUB-0.17-2	855.54	0.17 - 2 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3285	121819 10:30_SSHS-B3285-SUB-0.17-2	SSHS-B3285-SUB-0.17-2	856.21	0.17 - 2 ft	180-100148-5	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3286	121819 10:30_SSHS-B3286-SUB-0.17-2	SSHS-B3286-SUB-0.17-2	856.34	0.17 - 2 ft	180-100148-5	Excavated			< 1300 U									
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-0.17-2	SSHS-B3288-SUB-0.17-2	856.90	0.17 - 2 ft	180-100148-6	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3291	121819 10:30_SSHS-B3291-SUB-0.17-2	SSHS-B3291-SUB-0.17-2	857.22	0.17 - 2 ft	180-100148-6	Excavated			< 360 U									
Northern Athletic Field	SSHS-B3292	121819 10:30_SSHS-B3292-SUB-0.17-2	SSHS-B3292-SUB-0.17-2	857.35	0.17 - 2 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3293	121819 10:30_SSHS-B3293-SUB-0.17-2	SSHS-B3293-SUB-0.17-2	857.15	0.17 - 2 ft	180-100148-5	Excavated			< 240 U									
Northern Athletic Field	SSHS-B3295	121819 10:30_SSHS-B3295-SUB-0.17-2	SSHS-B3295-SUB-0.17-2	855.96	0.17 - 2 ft	180-100148-4	Excavated			< 650 U									
Northern Athletic Field	SSHS-B3296	121819 10:30_SSHS-B3296-SUB-0.17-2	SSHS-B3296-SUB-0.17-2	856.22	0.17 - 2 ft	180-100148-2	Excavated			< 490 U									
Northern Athletic Field	SSHS-B3297	121819 10:30_SSHS-B3297-SUB-0.17-2	SSHS-B3297-SUB-0.17-2	857.02	0.17 - 2 ft	180-100148-5	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3298	121819 10:30_SSHS-B3298-SUB-0.17-2	SSHS-B3298-SUB-0.17-2	857.20	0.17 - 2 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3300	121819 10:30_SSHS-B3300-SUB-0.17-2	SSHS-B3300-SUB-0.17-2	856.38	0.17 - 2 ft	180-100148-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3301	121819 10:30_SSHS-B3301-SUB-0.17-2	SSHS-B3301-SUB-0.17-2	856.13	0.17 - 2 ft	180-100148-2	Excavated			< 260 U									
Northern Athletic Field	SSHS-B3302	121819 10:30_SSHS-B3302-SUB-0.17-2	SSHS-B3302-SUB-0.17-2	856.19	0.17 - 2 ft	180-100148-5	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3303	121819 10:30_SSHS-B3303-SUB-0.17-2	SSHS-B3303-SUB-0.17-2	856.73	0.17 - 2 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3304	121819 10:30_SSHS-B3304-SUB-0.17-2	SSHS-B3304-SUB-0.17-2	856.97	0.17 - 2 ft	180-100148-4	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3306	121819 10:30_SSHS-B3306-SUB-0.17-2	SSHS-B3306-SUB-0.17-2	855.94	0.17 - 2 ft	180-100148-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3307	121819 10:30_SSHS-B3307-SUB-0.17-2	SSHS-B3307-SUB-0.17-2	856.00	0.17 - 2 ft	180-100148-6	Excavated			< 260 U									
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-0.17-2	SSHS-B3308-SUB-0.17-2	855.68	0.17 - 2 ft	180-100148-4	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3309	121819 10:30_SSHS-B3309-SUB-0.17-2	SSHS-B3309-SUB-0.17-2	856.31	0.17 - 2 ft	180-100148-4	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3314	121819 10:30_SSHS-B3314-SUB-0.17-2	SSHS-B3314-SUB-0.17-2	856.94	0.17 - 2 ft	180-100148-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-0.17-2	SSHS-B3315-SUB-0.17-2	856.43	0.17 - 2 ft	180-100148-6	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3325	121819 10:30_SSHS-B3325-SUB-0.17-2	SSHS-B3325-SUB-0.17-2	853.99	0.17 - 2 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3326	121819 10:30_SSHS-B3326-SUB-0.17-2	SSHS-B3326-SUB-0.17-2	854.39	0.17 - 2 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-0.17-2	SSHS-B3327-SUB-0.17-2	853.34	0.17 - 2 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3328	121819 10:30_SSHS-B3328-SUB-0.17-2	SSHS-B3328-SUB-0.17-2	854.14	0.17 - 2 ft	180-100148-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-0.17-2	SSHS-B3329-SUB-0.17-2	852.74	0.17 - 2 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-0.17-2	SSHS-B3330-SUB-0.17-2	851.73	0.17 - 2 ft	180-100148-1	Excavated			< 130 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-0.17-2	SSHS-B3221-SUB-0.17-2	857.92	0.17 - 2 ft	180-95165-2	Excavated												
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-0.17-2	SSHS-B3222-SUB-0.17-2	858.28	0.17 - 2 ft	180-95047-1	Excavated												
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-0.17-2	SSHS-B3223-SUB-0.17-2	858.27	0.17 - 2 ft	180-95006-2	Excavated												
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-0.17-2	SSHS-B3224-SUB-0.17-2	858.38	0.17 - 2 ft	180-95050-1	Excavated												
Northern Athletic Field	SSHS-B3225	122119 10:30_SSHS-B3225-SUB-0.17-2	SSHS-B3225-SUB-0.17-2	853.42	0.17 - 2 ft	180-100361-1	Excavated												
Northern Athletic Field	SSHS-B3226	122119 10:30_SSHS-B3226-SUB-0.17-2	SSHS-B3226-SUB-0.17-2	853.22	0.17 - 2 ft	180-100362-1	Excavated												
Northern Athletic Field	SSHS-B3227	122119 10:30_SSHS-B3227-SUB-0.17-2	SSHS-B3227-SUB-0.17-2	853.19	0.17 - 2 ft	180-100361-1	Excavated												
Northern Athletic Field	SSHS-B3228	122119 10:30_SSHS-B3228-SUB-0.17-2	SSHS-B3228-SUB-0.17-2	853.57	0.17 - 2 ft	180-100362-1	Excavated												
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-0.17-2	SSHS-B3244-SUB-0.17-2	857.74	0.17 - 2 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-0.17-2	SSHS-B3245-SUB-0.17-2	857.37	0.17 - 2 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-0.17-2	SSHS-B3246-SUB-0.17-2	858.13	0.17 - 2 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3247	122119 10:30_SSHS-B-3247-SUB-0.17-2	SSHS-B-3247-SUB-0.17-2	857.57	0.17 - 2 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3249	122119 10:30_SSHS-B3249-SUB-0.17-2	SSHS-B3249-SUB-0.17-2	857.44	0.17 - 2 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-0.17-2	SSHS-B3250-SUB-0.17-2	858.02	0.17 - 2 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-0.17-2	SSHS-B3252-SUB-0.17-2	857.46	0.17 - 2 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-0.17-2	SSHS-B3253-SUB-0.17-2	858.40	0.17 - 2 ft	180-100363-2	Excavated												
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-0.17-2	SSHS-B3255-SUB-0.17-2	857.06	0.17 - 2 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3256	122119 10:30_SSHS-B3256-SUB-0.17-2	SSHS-B3256-SUB-0.17-2	858.14	0.17 - 2 ft	180-100363-2	Excavated												
Northern Athletic Field	SSHS-B3257	122119 10:30_SSHS-B3257-SUB-0.17-2	SSHS-B3257-SUB-0.17-2	858.41	0.17 - 2 ft	180-100363-2	Excavated												
Northern Athletic Field	SSHS-B3259	122119 10:30_SSHS-B3259-SUB-0.17-2	SSHS-B3259-SUB-0.17-2	857.33	0.17 - 2 ft	180-100363-2	Excavated												
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-0.17-2	SSHS-B3260-SUB-0.17-2	858.57	0.17 - 2 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3261	122119 10:30_SSHS-B3261-SUB-0.17-2	SSHS-B3261-SUB-0.17-2	856.31	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3262	122119 10:30_SSHS-B3262-SUB-0.17-2	SSHS-B3262-SUB-0.17-2	857.03	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3263	122119 10:30_SSHS-B3263-SUB-0.17-2	SSHS-B3263-SUB-0.17-2	857.52	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3265	122119 10:30_SSHS-B3265-SUB-0.17-2	SSHS-B3265-SUB-0.17-2	854.04	0.17 - 2 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3268	122119 10:30_SSHS-B3268-SUB-0.17-2	SSHS-B3268-SUB-0.17-2	854.73	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3269	122119 10:30_SSHS-B3269-SUB-0.17-2	SSHS-B3269-SUB-0.17-2	854.73	0.17 - 2 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-0.17-2	SSHS-B3272-SUB-0.17-2	856.00	0.17 - 2 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3274	122119 10:30_SSHS-B3274-SUB-0.17-2	SSHS-B3274-SUB-0.17-2	855.80	0.17 - 2 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-0.17-2	SSHS-B3275-SUB-0.17-2	856.25	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-0.17-2	SSHS-B3276-SUB-0.17-2	856.44	0.17 - 2 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3278	122119 10:30_SSHS-B3278-SUB-0.17-2	SSHS-B3278-SUB-0.17-2	856.22	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-0.17-2	SSHS-B3280-SUB-0.17-2	856.56	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-0.17-2	SSHS-B3281-SUB-0.17-2	856.88	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3282	122119 10:30_SSHS-B3282-SUB-0.17-2	SSHS-B3282-SUB-0.17-2	856.89	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-0.17-2	SSHS-B3283-SUB-0.17-2	856.35	0.17 - 2 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-0.17-2	SSHS-B3284-SUB-0.17-2	855.54	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3285	121819 10:30_SSHS-B3285-SUB-0.17-2	SSHS-B3285-SUB-0.17-2	856.21	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3286	121819 10:30_SSHS-B3286-SUB-0.17-2	SSHS-B3286-SUB-0.17-2	856.34	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-0.17-2	SSHS-B3288-SUB-0.17-2	856.90	0.17 - 2 ft	180-100148-6	Excavated												
Northern Athletic Field	SSHS-B3291	121819 10:30_SSHS-B3291-SUB-0.17-2	SSHS-B3291-SUB-0.17-2	857.22	0.17 - 2 ft	180-100148-6	Excavated												
Northern Athletic Field	SSHS-B3292	121819 10:30_SSHS-B3292-SUB-0.17-2	SSHS-B3292-SUB-0.17-2	857.35	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3293	121819 10:30_SSHS-B3293-SUB-0.17-2	SSHS-B3293-SUB-0.17-2	857.15	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3295	121819 10:30_SSHS-B3295-SUB-0.17-2	SSHS-B3295-SUB-0.17-2	855.96	0.17 - 2 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3296	121819 10:30_SSHS-B3296-SUB-0.17-2	SSHS-B3296-SUB-0.17-2	856.22	0.17 - 2 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3297	121819 10:30_SSHS-B3297-SUB-0.17-2	SSHS-B3297-SUB-0.17-2	857.02	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3298	121819 10:30_SSHS-B3298-SUB-0.17-2	SSHS-B3298-SUB-0.17-2	857.20	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3300	121819 10:30_SSHS-B3300-SUB-0.17-2	SSHS-B3300-SUB-0.17-2	856.38	0.17 - 2 ft	180-100148-3	Excavated												
Northern Athletic Field	SSHS-B3301	121819 10:30_SSHS-B3301-SUB-0.17-2	SSHS-B3301-SUB-0.17-2	856.13	0.17 - 2 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3302	121819 10:30_SSHS-B3302-SUB-0.17-2	SSHS-B3302-SUB-0.17-2	856.19	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3303	121819 10:30_SSHS-B3303-SUB-0.17-2	SSHS-B3303-SUB-0.17-2	856.73	0.17 - 2 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3304	121819 10:30_SSHS-B3304-SUB-0.17-2	SSHS-B3304-SUB-0.17-2	856.97	0.17 - 2 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3306	121819 10:30_SSHS-B3306-SUB-0.17-2	SSHS-B3306-SUB-0.17-2	855.94	0.17 - 2 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3307	121819 10:30_SSHS-B3307-SUB-0.17-2	SSHS-B3307-SUB-0.17-2	856.00	0.17 - 2 ft	180-100148-6	Excavated												
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-0.17-2	SSHS-B3308-SUB-0.17-2	855.68	0.17 - 2 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3309	121819 10:30_SSHS-B3309-SUB-0.17-2	SSHS-B3309-SUB-0.17-2	856.31	0.17 - 2 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3314	121819 10:30_SSHS-B3314-SUB-0.17-2	SSHS-B3314-SUB-0.17-2	856.94	0.17 - 2 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-0.17-2	SSHS-B3315-SUB-0.17-2	856.43	0.17 - 2 ft	180-100148-6	Excavated												
Northern Athletic Field	SSHS-B3325	121819 10:30_SSHS-B3325-SUB-0.17-2	SSHS-B3325-SUB-0.17-2	853.99	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3326	121819 10:30_SSHS-B3326-SUB-0.17-2	SSHS-B3326-SUB-0.17-2	854.39	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-0.17-2	SSHS-B3327-SUB-0.17-2	853.34	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3328	121819 10:30_SSHS-B3328-SUB-0.17-2	SSHS-B3328-SUB-0.17-2	854.14	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-0.17-2	SSHS-B3329-SUB-0.17-2	852.74	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-0.17-2	SSHS-B3330-SUB-0.17-2	851.73	0.17 - 2 ft	180-100148-1	Excavated												

DRAFT

								Emerging C									
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-0.17-2	SSHS-B3331-SUB-0.17-2	852.38	0.17 - 2 ft	180-100148-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3332	121819 10:30 SSHS-B3332-SUB-0.17-2	SSHS-B3332-SUB-0.17-2	853.06	0.17 - 2 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3333	121819 10:30 SSHS-B3333-SUB-0.17-2	SSHS-B3333-SUB-0.17-2	853.75	0.17 - 2 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3342	121819 10:30 SSHS-B3342-SUB-0.17-2	SSHS-B3342-SUB-0.17-2	853.63	0.17 - 2 ft	180-100148-5	Excavated			< 120 U									
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-0.17-2	SSHS-B3459-SUB-0.17-2	856.30	0.17 - 2 ft	180-108826-2	Excavated			< 120 U									
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-0.17-2	SSHS-B3461-SUB-0.17-2	856.51	0.17 - 2 ft	180-108826-2	Excavated			< 130 U									
Football Field	SSHS-B3463	072920 09:00 SSHS-B3463-SUB-0.17-2	SSHS-B3463-SUB-0.17-2	856.64	0.17 - 2 ft	180-108872-3	Excavated			< 120 U									
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-0.17-2	SSHS-B3464-SUB-0.17-2	856.28	0.17 - 2 ft	180-108826-2	Excavated			< 240 U									
Football Field	SSHS-B3473	072820 09:00 DUP15	DUP15	855.34	0.17 - 2 ft	180-108826-1	Excavated			< 130 U									
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-0.17-2	SSHS-B3473-SUB-0.17-2	855.34	0.17 - 2 ft	180-108826-2	Excavated			< 580 U									
Northern Athletic Field	SSHS-B3481	072920 09:00 SSHS-B3481-SUB-0.17-2	SSHS-B3481-SUB-0.17-2	858.23	0.17 - 2 ft	180-108872-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	SSHS-B3481-SUB-0.17-2	858.23	0.17 - 2 ft	180-108872-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3484	072920 09:00 SSHS-B3484-SUB-0.17-2	SSHS-B3484-SUB-0.17-2	858.45	0.17 - 2 ft	180-108872-1	Excavated			< 570 U									
Northern Athletic Field	SSHS-B3485	072920 09:00 SSHS-B3485-SUB-0.17-2	SSHS-B3485-SUB-0.17-2	858.43	0.17 - 2 ft	180-108872-1	Excavated			< 1100 U									
Northern Athletic Field	SSHS-B3486	072920 09:00 SSHS-B3486-SUB-0.17-2	SSHS-B3486-SUB-0.17-2	858.58	0.17 - 2 ft	180-108872-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3487	072920 09:00 SSHS-B3487-SUB-0.17-2	SSHS-B3487-SUB-0.17-2	856.51	0.17 - 2 ft	180-108872-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3488	072920 09:00 SSHS-B3488-SUB-0.17-2	SSHS-B3488-SUB-0.17-2	857.00	0.17 - 2 ft	180-108872-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3489	072920 09:00 SSHS-B3489-SUB-0.17-2	SSHS-B3489-SUB-0.17-2	856.50	0.17 - 2 ft	180-108872-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3490	072920 09:00 SSHS-B3490-SUB-0.17-2	SSHS-B3490-SUB-0.17-2	858.42	0.17 - 2 ft	180-108872-1	Excavated			< 1100 U									
Northern Athletic Field	SSHS-B3494	012721 08:30 DUP-19	DUP-19	858.31	0.17 - 2 ft	180-116462-2	Excavated			< 120 U	< 0.42 U	< 0.028 U	0.41 J+	< 0.044 U	< 0.025 U	< 0.076 U	< 0.04 U	0.051 J	0.037 J
Northern Athletic Field	SSHS-B3494	012721 08:30 SSHS-B3494-SUB-0.17-2	SSHS-B3494-SUB-0.17-2	858.31	0.17 - 2 ft	180-116462-2	Excavated			< 130 U	< 0.45 U	< 0.03 U	0.33 J+	< 0.047 U	0.033 J	< 0.081 U	< 0.042 U	0.043 J	< 0.037 U
Northern Athletic Field	SSHS-B3496	012721 08:30 SSHS-B3496-SUB-0.17-2	SSHS-B3496-SUB-0.17-2	858.30	0.17 - 2 ft	180-116462-2	Excavated			< 120 U	< 0.44 U	< 0.03 U	0.31 J+	< 0.046 U	0.027 J	< 0.079 U	< 0.041 U	0.049 J	< 0.037 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-0.17-2	SSHS-B3498-SUB-0.17-2	858.39	0.17 - 2 ft	180-116462-1	Excavated			< 620 U									
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-0.17-2	SSHS-B3499-SUB-0.17-2	858.31	0.17 - 2 ft	180-116462-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3503A	012221 08:30 SSHS-B3503-SUB-0.17-2	SSHS-B3503-SUB-0.17-2	854.30	0.17 - 2 ft	180-116310-1	Excavated			< 380 U									
Northern Athletic Field	SSHS-B3504A	012721 08:30 SSHS-B3504-SUB-0.17-2	SSHS-B3504-SUB-0.17-2	853.98	0.17 - 2 ft	180-116404-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3505A	012721 08:30 SSHS-B3505-SUB-0.17-2	SSHS-B3505-SUB-0.17-2	853.31	0.17 - 2 ft	180-116404-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3507A	012721 08:30 SSHS-B3507-SUB-0.17-2	SSHS-B3507-SUB-0.17-2	855.31	0.17 - 2 ft	180-116462-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3508A	011421 08:45 SSHS-B3508-SUB-0.17-2	SSHS-B3508-SUB-0.17-2	856.03	0.17 - 2 ft	180-115927-1	Excavated			< 590 U									
Northern Athletic Field	SSHS-B3509A	011421 08:45 SSHS-B3509-SUB-0.17-2	SSHS-B3509-SUB-0.17-2	855.93	0.17 - 2 ft	180-115927-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3510A	011421 08:45 SSHS-B3510-SUB-0.17-2	SSHS-B3510-SUB-0.17-2	855.32	0.17 - 2 ft	180-115927-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3594	DUP-13-20210126	DUP-13	855.33	0.17 - 2 ft	1801164621	Excavated	< 130 U											
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2-20210126	SSHS-B3594-SUB-0.17-2	858.38	0.17 - 2 ft	1801164622	Excavated	< 130 U			< 0.46 U	< 0.031 U	0.44 B	< 0.048 U	0.046 J	< 0.083 U	< 0.043 U	0.077 J	0.040 J
Northern Athletic Field	SSHS-B3595	020221 09:00 SSHS-B3595-SUB-0.17-2	SSHS-B3595-SUB-0.17-2	856.70	0.17 - 2 ft	180-116686-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-0.17-2	SSHS-B3613-SUB-0.17-2	856.82	0.17 - 2 ft	180-116404-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3614	012721 08:30 SSHS-B3614-SUB-0.17-2	SSHS-B3614-SUB-0.17-2	857.48	0.17 - 2 ft	180-116404-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-0.17-2	SSHS-B3615-SUB-0.17-2	857.88	0.17 - 2 ft	180-116404-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-0.17-2	SSHS-B3616-SUB-0.17-2	858.03	0.17 - 2 ft	180-116404-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-0.17-2	SSHS-B3620-SUB-0.17-2	856.26	0.17 - 2 ft	180-116404-1	Excavated			< 590 U									
Northern Athletic Field	SSHS-B3625	012721 08:30 SSHS-B3625-SUB-0.17-2	SSHS-B3625-SUB-0.17-2	855.69	0.17 - 2 ft	180-116404-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3626	012821 08:30 SSHS-B3626-SUB-0.17-2	SSHS-B3626-SUB-0.17-2	855.81	0.17 - 2 ft	180-116529-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3627	020221 09:00 SSHS-B3627-SUB-0.17-2	SSHS-B3627-SUB-0.17-2	856.45	0.17 - 2 ft	180-116686-1	Excavated			< 250 U									
Northern Athletic Field	SSHS-B3628	012721 08:30 SSHS-B3628-SUB-0.17-2	SSHS-B3628-SUB-0.17-2	857.05	0.17 - 2 ft	180-116404-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3639	012821 08:30 SSHS-B3639-SUB-0.17-2	SSHS-B3639-SUB-0.17-2	856.65	0.17 - 2 ft	180-116529-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3640	020321 09:45 SSHS-B3640-SUB-0.17-2	SSHS-B3640-SUB-0.17-2	856.10	0.17 - 2 ft	180-116723-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3643	012821 08:30 SSHS-B3643-SUB-0.17-2	SSHS-B3643-SUB-0.17-2	856.99	0.17 - 2 ft	180-116529-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2-20210202	SSHS-B3645-SUB-0.17-2	856.82	0.17 - 2 ft	1801167231	Excavated	< 110 U			< 0.39 U	< 0.026 U	0.073 BJ	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-0.17-2	SSHS-B3852-SUB-0.17-2	856.07	0.17 - 2 ft	180-127205-2	Excavated			< 110 U	< 0.048 U	< 0.038 U	0.13 J	0.089 J	0.11 J	0.062 J	< 0.049 U	0.079 J	< 0.029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2-20210512	SSHS-B3917-SUB-0.17-2	853.71	0.17 - 2 ft	1801215482	Excavated	< 120 U			< 0.41 U	< 0.027 U	0.20 J	< 0.043 U	0.035 J	< 0.074 U	< 0.038 U	0.053 J	< 0.034 U
Football Field	SSHS-B429	082716 09:00 SSHS-B429-SUB-0.17-2	SSHS-B429-SUB-0.17-2	854.95	0.17 - 2 ft	180-58029-1	Excavated			< 44 U									
Football Field	SSHS-B70	081514 01:15 SSHS-B70-0.17-2 (1)	081514 01:15 SSHS-B70-0.17-2 (1)	855.98	0.17 - 2 ft	180-35818-2	Excavated			< 43 U									
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	SSHS-B71-0.17-2 (1.5)	856.19	0.17 - 2 ft	180-35858-1	Excavated			< 42									
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	SSHS-B75-0.17-2 (1.5)	856.08	0.17 - 2 ft	180-35818-2	Excavated			< 420									
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	SSHS-B76-0.17-2 (1.5)	856.25	0.17 - 2 ft	180-35818-1	Excavated			< 43									
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-0.17-2	SSHS-B3101-SUB-0.5-2	856.75	0.5 - 2 ft	180-100985-1	Excavated			< 4700 UJ									
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	SSHS-B3101-SUB-0.5-2	856.75	0.5 - 2 ft	180-100985-1	Excavated			< 4700 UJ									
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-0.17-2	SSHS-B3102-SUB-0.17-2	856.74	0.5 - 2 ft	180-100985-1	Excavated			< 230 UJ									
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-0.5-2	SSHS-B3104-SUB-0.5-2	856.82	0.5 - 2 ft	180-100985-2	Excavated			< 3000 UJ									
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-0.17-2	SSHS-B3105-SUB-0.17-2	856.73	0.5 - 2 ft	180-101038-1	Excavated			< 560 U									
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-0.17-2	SSHS-B3106-SUB-0.17-2	856.72	0.5 - 2 ft	180-101038-1	Excavated			< 230 U									
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-0.5-2	SSHS-B3183-SUB-0.5-2	856.70	0.5 - 2 ft	180-101038-1	Excavated			< 1700 U									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2-20210701	SSHS-B4018-SUB-1-2	857.47	1 - 2 ft	1801239851	Excavated	< 120 U			< 0.40 U	< 0.027 U	0.094 J	0.062 J	0.040 J	< 0.072 U	< 0.037 U	0.045 J	0.038 J
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-1-2	SSHS-B4019-SUB-1-2	856.76	1 - 2 ft	180-123985-1	Excavated			< 120 U									
Football Field	SSHS-B2762	042819 10:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-89521-1	Excavated			< 240 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-0.17-2	SSHS-B3331-SUB-0.17-2	852.38	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3332	121819 10:30 SSHS-B3332-SUB-0.17-2	SSHS-B3332-SUB-0.17-2	853.06	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3333	121819 10:30 SSHS-B3333-SUB-0.17-2	SSHS-B3333-SUB-0.17-2	853.75	0.17 - 2 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3342	121819 10:30 SSHS-B3342-SUB-0.17-2	SSHS-B3342-SUB-0.17-2	853.63	0.17 - 2 ft	180-100148-5	Excavated												
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-0.17-2	SSHS-B3459-SUB-0.17-2	856.30	0.17 - 2 ft	180-108826-2	Excavated												
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-0.17-2	SSHS-B3461-SUB-0.17-2	856.51	0.17 - 2 ft	180-108826-2	Excavated												
Football Field	SSHS-B3463	072920 09:00 SSHS-B3463-SUB-0.17-2	SSHS-B3463-SUB-0.17-2	856.64	0.17 - 2 ft	180-108872-3	Excavated												
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-0.17-2	SSHS-B3464-SUB-0.17-2	856.28	0.17 - 2 ft	180-108826-2	Excavated												
Football Field	SSHS-B3473	072820 09:00 DUP15	DUP15	855.34	0.17 - 2 ft	180-108826-1	Excavated												
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-0.17-2	SSHS-B3473-SUB-0.17-2	855.34	0.17 - 2 ft	180-108826-2	Excavated												
Northern Athletic Field	SSHS-B3481	072920 09:00 SSHS-B3481-SUB-0.17-2	SSHS-B3481-SUB-0.17-2	858.23	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3481	SSHS-B3481-SUB-0.17-2	SSHS-B3481-SUB-0.17-2	858.23	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3484	072920 09:00 SSHS-B3484-SUB-0.17-2	SSHS-B3484-SUB-0.17-2	858.45	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3485	072920 09:00 SSHS-B3485-SUB-0.17-2	SSHS-B3485-SUB-0.17-2	858.43	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3486	072920 09:00 SSHS-B3486-SUB-0.17-2	SSHS-B3486-SUB-0.17-2	858.58	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3487	072920 09:00 SSHS-B3487-SUB-0.17-2	SSHS-B3487-SUB-0.17-2	856.51	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3488	072920 09:00 SSHS-B3488-SUB-0.17-2	SSHS-B3488-SUB-0.17-2	857.00	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3489	072920 09:00 SSHS-B3489-SUB-0.17-2	SSHS-B3489-SUB-0.17-2	856.50	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3490	072920 09:00 SSHS-B3490-SUB-0.17-2	SSHS-B3490-SUB-0.17-2	858.42	0.17 - 2 ft	180-108872-1	Excavated												
Northern Athletic Field	SSHS-B3494	012721 08:30 DUP-19	DUP-19	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.071 J	< 0.041 U	< 0.093 U	0.32	0.16 J	0.096 J	< 0.061 U	< 0.058 U	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3494	012721 08:30 SSHS-B3494-SUB-0.17-2	SSHS-B3494-SUB-0.17-2	858.31	0.17 - 2 ft	180-116462-2	Excavated	0.054 J	0.052 J	< 0.099 U	0.25	0.11 J	< 0.093 U	< 0.065 U	< 0.062 U	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3496	012721 08:30 SSHS-B3496-SUB-0.17-2	SSHS-B3496-SUB-0.17-2	858.30	0.17 - 2 ft	180-116462-2	Excavated	0.062 J	0.048 J	< 0.097 U	0.87	0.18 J	0.14 J	< 0.064 U	< 0.06 U	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-0.17-2	SSHS-B3498-SUB-0.17-2	858.39	0.17 - 2 ft	180-116462-1	Excavated												
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-0.17-2	SSHS-B3499-SUB-0.17-2	858.31	0.17 - 2 ft	180-116462-1	Excavated												
Northern Athletic Field	SSHS-B3503A	012221 08:30 SSHS-B3503-SUB-0.17-2	SSHS-B3503-SUB-0.17-2	854.30	0.17 - 2 ft	180-116310-1	Excavated												
Northern Athletic Field	SSHS-B3504A	012721 08:30 SSHS-B3504-SUB-0.17-2	SSHS-B3504-SUB-0.17-2	853.98	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3505A	012721 08:30 SSHS-B3505-SUB-0.17-2	SSHS-B3505-SUB-0.17-2	853.31	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3507A	012721 08:30 SSHS-B3507-SUB-0.17-2	SSHS-B3507-SUB-0.17-2	855.31	0.17 - 2 ft	180-116462-1	Excavated												
Northern Athletic Field	SSHS-B3508A	011421 08:45 SSHS-B3508-SUB-0.17-2	SSHS-B3508-SUB-0.17-2	856.03	0.17 - 2 ft	180-115927-1	Excavated												
Northern Athletic Field	SSHS-B3509A	011421 08:45 SSHS-B3509-SUB-0.17-2	SSHS-B3509-SUB-0.17-2	855.93	0.17 - 2 ft	180-115927-1	Excavated												
Northern Athletic Field	SSHS-B3510A	011421 08:45 SSHS-B3510-SUB-0.17-2	SSHS-B3510-SUB-0.17-2	855.32	0.17 - 2 ft	180-115927-1	Excavated												
Northern Athletic Field	SSHS-B3594	DUP-13-20210126	DUP-13	855.33	0.17 - 2 ft	1801164621	Excavated												
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-0.17-2-20210126	SSHS-B3594-SUB-0.17-2	858.38	0.17 - 2 ft	1801164622	Excavated	0.074 J	0.083 J	< 0.10 U	0.90 BT	0.23 J	0.11 J	< 0.067 U	< 0.063 U	0.054 J	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B3595	020221 09:00 SSHS-B3595-SUB-0.17-2	SSHS-B3595-SUB-0.17-2	856.70	0.17 - 2 ft	180-116686-1	Excavated												
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-0.17-2	SSHS-B3613-SUB-0.17-2	856.82	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3614	012721 08:30 SSHS-B3614-SUB-0.17-2	SSHS-B3614-SUB-0.17-2	857.48	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-0.17-2	SSHS-B3615-SUB-0.17-2	857.88	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-0.17-2	SSHS-B3616-SUB-0.17-2	858.03	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-0.17-2	SSHS-B3620-SUB-0.17-2	856.26	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3625	012721 08:30 SSHS-B3625-SUB-0.17-2	SSHS-B3625-SUB-0.17-2	855.69	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3626	012821 08:30 SSHS-B3626-SUB-0.17-2	SSHS-B3626-SUB-0.17-2	855.81	0.17 - 2 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3627	020221 09:00 SSHS-B3627-SUB-0.17-2	SSHS-B3627-SUB-0.17-2	856.45	0.17 - 2 ft	180-116686-1	Excavated												
Northern Athletic Field	SSHS-B3628	012721 08:30 SSHS-B3628-SUB-0.17-2	SSHS-B3628-SUB-0.17-2	857.05	0.17 - 2 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3639	012821 08:30 SSHS-B3639-SUB-0.17-2	SSHS-B3639-SUB-0.17-2	856.65	0.17 - 2 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3640	020321 09:45 SSHS-B3640-SUB-0.17-2	SSHS-B3640-SUB-0.17-2	856.10	0.17 - 2 ft	180-116723-1	Excavated												
Northern Athletic Field	SSHS-B3643	012821 08:30 SSHS-B3643-SUB-0.17-2	SSHS-B3643-SUB-0.17-2	856.99	0.17 - 2 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-0.17-2-20210202	SSHS-B3645-SUB-0.17-2	856.82	0.17 - 2 ft	1801167231	Excavated	< 0.044 U	< 0.038 U	< 0.087 U	0.38 J	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-0.17-2	SSHS-B3852-SUB-0.17-2	856.07	0.17 - 2 ft	180-127205-2	Excavated	0.069 J	0.14 J	< 0.033 U	0.75 J	0.24	0.072 J	0.046 J	0.064 J	0.097 J	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-0.17-2-20210512	SSHS-B3917-SUB-0.17-2	853.71	0.17 - 2 ft	1801215482	Excavated	0.072 J	0.065 J	< 0.090 U	0.69	0.25	< 0.085 U	< 0.059 U	< 0.056 U	< 0.040 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B429	082716 09:00 SSHS-B429-SUB-0.17-2	SSHS-B429-SUB-0.17-2	854.95	0.17 - 2 ft	180-58029-1	Excavated												
Football Field	SSHS-B70	081514 01:15 SSHS-B70-0.17-2 (1)	081514 01:15 SSHS-B70-0.17-2 (1)	855.98	0.17 - 2 ft	180-35818-2	Excavated												
Northern Athletic Field	SSHS-B71	SSHS-B71-0.17-2 (1.5)	SSHS-B71-0.17-2 (1.5)	856.19	0.17 - 2 ft	180-35858-1	Excavated												
Northern Athletic Field	SSHS-B75	SSHS-B75-0.17-2 (1.5)	SSHS-B75-0.17-2 (1.5)	856.08	0.17 - 2 ft	180-35818-2	Excavated												
Northern Athletic Field	SSHS-B76	SSHS-B76-0.17-2 (1.5)	SSHS-B76-0.17-2 (1.5)	856.25	0.17 - 2 ft	180-35818-1	Excavated												
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-0.17-2	SSHS-B3101-SUB-0.5-2	856.75	0.5 - 2 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-0.5-2	SSHS-B3101-SUB-0.5-2	856.75	0.5 - 2 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-0.17-2	SSHS-B3102-SUB-0.17-2	856.74	0.5 - 2 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-0.5-2	SSHS-B3104-SUB-0.5-2	856.82	0.5 - 2 ft	180-100985-2	Excavated												
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-0.17-2	SSHS-B3105-SUB-0.17-2	856.73	0.5 - 2 ft	180-101038-1	Excavated												
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-0.17-2	SSHS-B3106-SUB-0.17-2	856.72	0.5 - 2 ft	180-101038-1	Excavated												
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-0.5-2	SSHS-B3183-SUB-0.5-2	856.70	0.5 - 2 ft	180-101038-1	Excavated												
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-1-2-20210701	SSHS-B4018-SUB-1-2	857.47	1 - 2 ft	1801239851	Excavated	0.072 J	0.053 J	< 0.088 U	0.62	0.19 J	< 0.082 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-1-2	SSHS-B4019-SUB-1-2	856.76	1 - 2 ft	180-123985-1	Excavated												
Football Field	SSHS-B2762	042819 10:00 PS-FD-15	PS-FD-15	855.03	0 - 2 ft	180-89521-1	Excavated												

DRAFT

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	ND	< 0.0060 UJ	< 0.0065 UJ	< 0.0045 UJ	< 0.0027 UJ	< 0.0044 UJ	< 0.0055 UJ	< 0.0052 UJ	< 0.0065 UJ	< 0.0025 UJ
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	0.044	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	0.044	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	0.0096	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0096 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	0.016	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.016 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	15.89-17.89 ft	1801782961	Not Excavated	0.062	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.062	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	ND	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U		
Rear Parking Lot	SSHS-B1004	SSHS-B1004-SUB-4-6	3/3/2018	850.31	4 - 6 ft	180-75511-1	Excavated	2.016	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.43 J	0.086 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1005	SSHS-B1005-SUB-4-6	3/3/2018	851.75	4 - 6 ft	180-75511-1	Excavated	3.52	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.6 J	0.77 J	0.15 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1006	SSHS-B1006-SUB-10-12	3/3/2018	851.67	10 - 12 ft	180-75511-1	Not Excavated	0.1652	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11 J	0.046 J	0.0092 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1007	PS-FD-7	3/3/2018	851.90	12 - 14 ft	180-75511-1	Not Excavated	31.5	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	24 J	6 J	1.5 J	< 0.14 U	< 0.095 U
Rear Parking Lot	SSHS-B1007	SSHS-B1007-SUB-12-14	3/3/2018	851.90	12 - 14 ft	180-75511-1	Not Excavated	40.2	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	31 J	7.6 J	1.6 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B1008	SSHS-B1008-SUB-12-14	3/3/2018	852.10	12 - 14 ft	180-75511-1	Not Excavated	36	< 0.071 U	< 0.14 U	< 0.13 U	< 0.13 U	24 J	9.8 J	2.2 J	< 0.15 U	< 0.11 U
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-14-16	4/24/2018	852.00	14 - 16 ft	180-77059-1	Not Excavated	0.616	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.45	0.14	0.026	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	0.014	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	0.014 J	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	ND	< 0.003 U	< 0.0039 U	< 0.0035 U	< 0.0033 U	< 0.0019 U	< 0.0029 U	< 0.0029 U	< 0.0044 U	< 0.0026 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	0.543	< 0.0031 U	< 0.0039 U	< 0.0035 U	< 0.0034 U	0.5	< 0.0029 U	0.043	< 0.0045 U	< 0.0026 U
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Rear Parking Lot	SSHS-B1010	SSHS-B1010-SUB-10-12	4/24/2018	851.50	10 - 12 ft	180-77059-1	Not Excavated	0.082	< 0.0078 U	< 0.016 U	< 0.014 U	< 0.014 U	0.061	0.021 J	< 0.0068 U	< 0.017 U	< 0.012 U
Rear Parking Lot	SSHS-B1010	SSHS-B1010-SUB-12-14	4/24/2018	851.50	12 - 14 ft	180-77059-1	Not Excavated	5.62	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4.3	1.1	0.22	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1015	SSHS-B1015-SUB-12-14	4/25/2018	853.20	12 - 14 ft	180-77123-3	Not Excavated	0.782	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.24	0.072	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1016	SSHS-B1016-SUB-10-12	4/24/2018	849.90	10 - 12 ft	180-77059-1	Not Excavated	0.036	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.036	< 0.013 U	< 0.0055 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1017	SSHS-B1017-SUB-8-10	4/24/2018	853.03	8 - 10 ft	180-77059-1	Not Excavated	1.32	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.59	0.56	0.17	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1017	SSHS-B1017-SUB-10-12	4/24/2018	853.03	10 - 12 ft	180-77059-1	Not Excavated	2.82	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	1.2	0.32	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1018	SSHS-B1018-SUB-8-10	4/24/2018	852.50	8 - 10 ft	180-77059-1	Not Excavated	1.289	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.81	0.39	0.089	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1018	SSHS-B1018b-SUB-10-12	4/26/2018	852.50	10 - 12 ft	180-77189-1	Excavated	2.959	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.3	0.59	0.069	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1018	SSHS-B1018-SUB-10-12	4/24/2018	852.50	10 - 12 ft	180-77059-1	Not Excavated	2.109	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	1.6	0.44	0.069	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1020	PS-FD-04	4/26/2018	851.20	8 - 10 ft	180-77189-1	Not Excavated	1.71	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.3	0.35	0.06	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1020	SSHS-B1020-SUB-8-10	4/26/2018	851.20	8 - 10 ft	180-77189-1	Not Excavated	1.724	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	0.36	0.064	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1023b	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	12 - 14 ft	180-77189-1	Not Excavated	5	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	3.6	1.2	0.2	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1024	SSHS-B1024-SUB-2-4	4/25/2018	852.60	2 - 4 ft	180-77123-2	Excavated	0.836	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.49	0.27	0.076	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1025	SSHS-B1025-SUB-14-16	4/26/2018	852.50	14 - 16 ft	180-77189-1	Not Excavated	0.373	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.24	0.11	0.023	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1026	SSHS-B1026-SUB-14-16	4/24/2018	852.10	14 - 16 ft	180-77059-1	Not Excavated	33.2	< 0.07 U	< 0.14 U	< 0.13 U	< 0.13 U	21	10	2.2	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B103	PS-FD-#21	7/22/2015	849.40	2 - 4 ft	180-46170-1	Excavated	837	< 0.78 U	< 0.95 U	< 1.3 U	< 0.96 U	560 J	250 J	27 J	< 1.4 U	< 0.77 U
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-2-4	7/22/2015	849.40	2 - 4 ft	180-46170-1	Excavated	377	< 0.19 U	< 0.23 U	< 0.32 U	< 0.24 U	270 J	95 J	12 J	< 0.34 U	< 0.19 U
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-4-6	7/22/2015	849.40	4 - 6 ft	180-46170-1	Excavated	32.8	< 0.04 U	< 0.049 U	< 0.068 U	< 0.05 U	23 J	8.7 J	1.1 J	< 0.073 U	< 0.04 U
Rear Parking Lot	SSHS-B103	SSHS-B103-SUB-6-8	7/22/2015	849.40	6 - 8 ft	180-46170-1	Excavated	0.011	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.011 J	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-2-4	7/22/2015	849.32	2 - 4 ft	180-46170-1	Excavated	150.8	< 0.37 U	< 0.46 U	< 0.63 U	< 0.46 U	110 J	36 J	4.8 J	< 0.68 U	< 0.37 U
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-4-6	7/22/2015	849.32	4 - 6 ft	180-46170-1	Excavated	49.2	< 0.039 U	< 0.048 U	< 0.066 U	< 0.049 U	33 J	14 J	2.2 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B104	SSHS-B104-SUB-6-8	7/22/2015	849.32	6 - 8 ft	180-46170-1	Excavated	0.031	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.031	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-2-4	7/22/2015	849.26	2 - 4 ft	180-46170-1	Excavated	327.9	< 0.81 U	< 0.99 U	< 1.4 U	< 1 U	240 J	80 J	7.9 J	< 1.5 U	< 0.8 U
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-4-6	7/22/2015	849.26	4 - 6 ft	180-46170-1	Excavated	21.54	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	15 J	5.7 J	0.84 J	< 0.07 U	< 0.038 U
Rear Parking Lot	SSHS-B105	SSHS-B105-SUB-6-8	7/22/2015	849.26	6 - 8 ft	180-46170-1	Excavated	ND	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.0051 U	< 0.005 U	< 0.0048 U	< 0.0044 U	< 0.0074 U	< 0.004 U
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-2-4	7/22/2015	849.39	2 - 4 ft	180-46170-1	Excavated	229.6	< 0.77 U	< 0.95 U	< 1.3 U	< 0.96 U	170 J	53 J	6.6 J	< 1.4 U	< 0.76 U
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-4-6	7/22/2015	849.39	4 - 6 ft	180-46170-1	Excavated	245.1	< 0.79 U	< 0.97 U	< 1.3 U	< 0.98 U	170 J	67 J	8.1 J	< 1.4 U	< 0.78 U
Rear Parking Lot	SSHS-B106	SSHS-B106-SUB-6-8	7/22/2015	849.39	6 - 8 ft	180-46170-1	Excavated	23.69	< 0.081 U	< 0.1 U	< 0.14 U	< 0.1 U	18 J	5.1 J	0.59 J	< 0.15 U	< 0.08 U
Rear Parking Lot	SSHS-B1064	SSHS-B1064-SUB-4-6	6/29/2018	850.52	4 - 6 ft	180-79432-1	Not Excavated	3.58	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.4 J	0.98 J	0.2 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-4-6	7/1/2018	850.40	4 - 6 ft	180-79440-1	Excavated	14.67	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	9.1 J	4.9 J	0.67 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-10-12	7/1/2018	850.17	10 - 12 ft	180-79440-2	Not Excavated	2.56	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	2 J	0.56 J		< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B106A	CS-FD-#21	8/3/2015	849.39	8 - 10 ft	180-46601-1	Not Excavated	11.43	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	9 J	2.1 J	0.33 J	< 0.069 U	< 0.037 U
Rear Parking Lot	SSHS-B106A	SSHS-B106A-SUB-8-10	8/3/2015	849.39	8 - 10 ft	180-46601-1	Not Excavated	4.494	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	3.1 J	1.3 J	0.094 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-2-4	7/22/2015	849.10	2 - 4 ft	180-46170-1	Not Excavated	182.9	< 0.39 U	< 0.47 U	< 0.65 U	< 0.48 U	130 J	48 J	4.9 J	< 0.7 U	< 0.38 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-4-6	7/22/2015	849.10	4 - 6 ft	180-46170-1	Not Excavated	5.2	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	3.7 J	1.3 J	0.2 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-6-8	7/22/2015	849.10	6 - 8 ft	180-46170-1	Not Excavated	0.015	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.015 J	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B1073	SSHS-B1073-SUB-2-4	6/24/2018	852.50	2 - 4 ft	200-44046-1	Not Excavated	0.995	< 0.013 UJ	< 0.013 UJ	< 0.013 UJ	< 0.013 UJ	0.61 J	0.33 J	0.055 J	< 0.013 UJ	< 0.013 UJ
Rear Parking Lot	SSHS-B1074	PS-FD-5	6/29/2018	851.08	2 - 4 ft	180-79432-1	Not Excavated	0.46	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24 J	0.22 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1074	SSHS-B1074-SUB-2-4	6/29/2018	851.08	2 - 4 ft	180-79432-1	Not Excavated	0.212	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.12 J	0.092 J	< 0.0057 U	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1075	SSHS-B1075-SUB-2-4	7/2/2018	852.95	2 - 4 ft	180-79440-1	Excavated	4.27	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.6 J	1.5 J	0.17 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1076	SSHS-B1076-SUB-2-4	6/29/2018	851.75	2 - 4 ft	180-79432-1	Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1076	SSHS-B1076-SUB-4-6	7/6/2018	851.75	4 - 6 ft	180-79550-1	Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1076	SSHS-B1076-SUB-4-6-DUP	7/6/2018	851.75	4 - 6 ft	180-79550-1	Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1077	SSHS-B1077-SUB-2-4	6/30/2018	851.36	2 - 4 ft	180-79440-1	Excavated	0.45	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.28 J	0.17 J	< 0.0059 U	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B1079	PS-FD-7	6/30/2018	850.74	4 - 6 ft	180-79440-1	Excavated	8.48	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.2 J	3.8 J	0.48 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1079	SSHS-B1079-SUB-4-6	6/30/2018	850.74	4 - 6 ft	180-79440-1	Excavated	9.77	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.3 J	4.9 J	0.57 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-2-4	7/22/2015	849.57	2 - 4 ft	180-46170-1	Not Excavated	4.9	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	3.8 J	0.99 J	0.11 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B108	PS-FD-#22	7/22/2015	849.57	4 - 6 ft	180-46170-1	Not Excavated	0.712	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.51 J	0.17 J	0.032 J	< 0.0073 U	< 0.004 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-4-6	7/22/2015	849.57	4 - 6 ft	180-46170-1	Not Excavated	2.194	< 0.0042 U	< 0.0051 U	< 0.007 U	< 0.0051 U	1.6 J	0.53 J	0.064 J	< 0.0075 U	< 0.0041 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-6-8	7/22/2015	849.57	6 - 8 ft	180-46170-1	Not Excavated	0.44	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.28 J	0.13 J	0.03 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B1080	SSHS-B1080B-SUB-6-8	6/29/2018	852.94	6 - 8 ft	180-79432-1	Excavated	1.3	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	1.3	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1081	SSHS-B1081-SUB-6-8	7/6/2018	851.28	6 - 8 ft	180-79550-1	Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1082	SSHS-B1082-SUB-6-8	7/28/2018	850.01	6 - 8 ft	180-80273-1	Excavated	116.1	< 0.31 U	< 0.61 U	< 0.56 U	< 0.56 U	88 J	24 J	4.1 J	< 0.66 U	< 0.46 U
Rear Parking Lot	SSHS-B1082	SSHS-B1082-SUB-8-10	7/28/2018	850.01	8 - 10 ft	180-80273-1	Excavated	32.1	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	6.8 J	1.3 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B1084	SSHS-B1084-SUB-8-10	6/28/2018	853.50	8 - 10 ft	180-79394-1	Not Excavated	1.156	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38 J	0.71 J	0.066 J	< 0.013 U	< 0.009 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B1086	SSHS-B1086-SUB-10-12	7/6/2018	850.69	10 - 12 ft	180-79550-1	Not Excavated	0.923	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.48 J	0.37 J	0.073 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1088	SSHS-B1088-SUB-6-8	6/28/2018	853.97	6 - 8 ft	180-79394-1	Excavated	2.958	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2 J	0.87 J	0.088 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-2-4	7/21/2015	850.20	2 - 4 ft	180-46139-1	Excavated	44.7	< 0.074 U	< 0.091 U	< 0.12 U	< 0.091 U	30 J	13 J	1.7 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-4-6	7/21/2015	850.20	4 - 6 ft	180-46139-1	Excavated	1.839	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	1.3 J	0.48 J	0.059 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B109	SSHS-B109-SUB-6-8	7/21/2015	850.20	6 - 8 ft	180-46139-1	Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B1091	SSHS-B1091-SUB-14-16	7/6/2018	851.86	14 - 16 ft	180-79550-1	Not Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16	7/6/2018	852.20	14 - 16 ft	180-79550-1	Not Excavated	0.022	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.022	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	14 - 16 ft	180-79550-1	Not Excavated	0.183	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.089 J	0.094 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16	7/6/2018	851.97	14 - 16 ft	180-79550-1	Not Excavated	0.173	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.096 J	0.058 J	0.019 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	14 - 16 ft	180-79550-1	Not Excavated	0.075	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	0.049 J	0.026 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1094	SSHS-B1094-SUB-14-16	7/6/2018	851.75	14 - 16 ft	180-79550-1	Not Excavated	0.037	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-2-4	7/21/2015	850.42	2 - 4 ft	180-46139-1	Excavated	244.6	< 0.77 U	< 0.95 U	< 1.3 U	< 0.96 U	170 J	67 J	7.6 J	< 1.4 U	< 0.76 U
Rear Parking Lot	SSHS-B110	PS-FD-#14	7/21/2015	850.42	4 - 6 ft	180-46139-1	Excavated	110.5	< 0.4 U	< 0.49 U	< 0.67 U	< 0.49 U	79 J	27 J	4.5 J	< 0.72 U	< 0.39 U
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-4-6	7/21/2015	850.42	4 - 6 ft	180-46139-1	Excavated	104.3	< 0.081 U	< 0.099 U	< 0.14 U	< 0.1 U	75 J	26 J	3.3 J	< 0.15 U	< 0.08 U
Rear Parking Lot	SSHS-B110	SSHS-B110-SUB-6-8	7/21/2015	850.42	6 - 8 ft	180-46139-1	Excavated	0.892	< 0.0043 U	< 0.0053 U	< 0.0073 U	< 0.0054 U	0.58 J	0.26 J	0.052 J	< 0.0078 U	< 0.0043 U
Rear Parking Lot	SSHS-B1104	SSHS-B1104-SUB-4-6	7/5/2018	851.81	4 - 6 ft	180-79550-1	Excavated	5.78	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6 J	1.7 J	0.48 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1104	SSHS-B1104-SUB-12-14	7/6/2018	851.32	12 - 14 ft	180-79550-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1105	SSHS-B1105-SUB-4-6	6/30/2018	851.18	4 - 6 ft	180-79440-1	Not Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1109	SSHS-B1109-SUB-8-10	6/29/2018	851.50	8 - 10 ft	180-79432-1	Not Excavated	0.138	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.093 J	0.033 J	0.012 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-2-4	7/21/2015	850.45	2 - 4 ft	180-46139-1	Excavated	8.71	< 0.018 U	< 0.022 U	< 0.03 U	< 0.022 U	6.2 J	2.1 J	0.41 J	< 0.032 U	< 0.017 U
Rear Parking Lot	SSHS-B111	PS-FD-#15	7/21/2015	850.45	4 - 6 ft	180-46139-1	Excavated	88	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	65 J	20 J	3 J	< 0.35 U	< 0.19 U
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-4-6	7/21/2015	850.45	4 - 6 ft	180-46139-1	Excavated	41.7	< 0.038 U	< 0.047 U	< 0.065 U	< 0.048 U	30 J	10 J	1.7 J	< 0.07 U	< 0.038 U
Rear Parking Lot	SSHS-B111	SSHS-B111-SUB-6-8	7/21/2015	850.45	6 - 8 ft	180-46139-1	Excavated	0.0085	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.0085 J	< 0.0046 U	< 0.0042 U	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-2-4	7/22/2015	850.70	2 - 4 ft	180-46170-1	Excavated	0.296	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	0.2 J	0.084 J	0.012 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-4-6	7/22/2015	850.70	4 - 6 ft	180-46170-1	Excavated	0.596	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.38 J	0.19 J	0.026 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-6-7	7/22/2015	850.70	6 - 7 ft	180-46170-1	Excavated	8.64	< 0.02 U	< 0.024 U	< 0.033 U	< 0.024 U	6 J	2.4 J	0.24 J	< 0.035 U	< 0.019 U
Rear Parking Lot	SSHS-B1122	SSHS-B1122-SUB-10-12	7/6/2018	851.50	10 - 12 ft	180-79550-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-2-4	7/21/2015	850.38	2 - 4 ft	180-46139-1	Excavated	0.055	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	0.036 J	0.019 J	< 0.0039 U	< 0.0067 U	< 0.0036 U
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-4-6	7/21/2015	850.38	4 - 6 ft	180-46139-1	Excavated	3.72	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	2.6 J	1 J	0.12 J	< 0.0074 U	< 0.004 U
Rear Parking Lot	SSHS-B115	SSHS-B115-SUB-6-8	7/21/2015	850.38	6 - 8 ft	180-46139-1	Excavated	0.0058	< 0.0041 U	< 0.005 U	< 0.007 U	< 0.0051 U	0.0058 J	< 0.0048 U	< 0.0044 U	< 0.0074 U	< 0.0041 U
Rear Parking Lot	SSHS-B1158	SSHS-B1158-SUB-8-10	7/6/2018	850.44	8 - 10 ft	180-79550-1	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-2-4	7/20/2015	850.54	2 - 4 ft	180-46139-1	Excavated	334	< 0.76 U	< 0.94 U	< 1.3 U	< 0.95 U	240 J	83 J	11 J	< 1.4 U	< 0.75 U
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-4-6	7/20/2015	850.54	4 - 6 ft	180-46139-1	Excavated	6.62	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	4.5 J	1.8 J	0.32 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B116	SSHS-B116-SUB-6-8	7/20/2015	850.54	6 - 8 ft	180-46139-1	Excavated	0.303	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.21 J	0.079 J	0.014 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B1160	SSHS-B1160-SUB-10-12	6/30/2018	851.49	10 - 12 ft	180-79440-1	Not Excavated	0.017	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.017 J	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1162	SSHS-B1162-SUB-8-10	7/5/2018	850.38	8 - 10 ft	180-79550-1	Not Excavated	0.353	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.25 J	0.089 J	0.014 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-2-4	7/20/2015	850.60	2 - 4 ft	180-46139-1	Excavated	2.76	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	0.26 J	2.5 J		< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B117	PS-FD-#20	7/20/2015	850.60	4 - 6 ft	180-46139-1	Excavated	51.2	< 0.072 U	< 0.088 U	< 0.12 U	< 0.089 U	34 J	15 J	2.2 J	< 0.13 U	< 0.071 U
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-4-6	7/20/2015	850.60	4 - 6 ft	180-46139-1	Excavated	53.2	< 0.074 U	< 0.091 U	< 0.13 U	< 0.092 U	35 J	16 J	2.2 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B117	SSHS-B117-SUB-6-8	7/20/2015	850.60	6 - 8 ft	180-46139-1	Excavated	302	< 0.82 U	< 1 U	< 1.4 U	< 1 U	190 J	99 J	13 J	< 1.5 U	< 0.81 U
Rear Parking Lot	SSHS-B117A	SSHS-B117A-SUB-8-10	8/3/2015	850.60	8 - 10 ft	180-46601-2	Not Excavated	22.14	< 0.039 U	< 0.048 U	< 0.066 U	< 0.049 U	14 J	7.3 J	0.84 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-2-4	7/20/2015	850.73	2 - 4 ft	180-46075-1	Excavated	657	< 2 U	< 2.4 U	< 3.4 U	< 2.5 U	460 J	170 J	27 J	< 3.6 U	< 2 U
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-4-6	7/20/2015	850.73	4 - 6 ft	180-46075-1	Excavated	509	< 1.9 U	< 2.4 U	< 3.3 U	< 2.4 U	360 J	130 J	19 J	< 3.5 U	< 1.9 U
Rear Parking Lot	SSHS-B118	PS-FD-#13	7/20/2015	850.73	6 - 8 ft	180-46075-1	Excavated	15.43	< 0.02 U	< 0.025 U	< 0.034 U	< 0.025 U	11 J	3.6 J	0.83 J	< 0.036 U	< 0.02 U
Rear Parking Lot	SSHS-B118	SSHS-B118-SUB-6-8	7/20/2015	850.73	6 - 8 ft	180-46075-1	Excavated	8.08	< 0.0042 U	< 0.0051 U	< 0.0071 U	< 0.0052 U	5.9 J	1.8 J	0.38 J	< 0.0076 U	< 0.0041 U
Rear Parking Lot	SSHS-B1189	SSHS-B1189-SUB-4-6	6/24/2018	853.90	4 - 6 ft	200-44046-1	Not Excavated	1.96	< 0.03 UJ	< 0.03 UJ	< 0.03 UJ	< 0.03 UJ	0.61 J	1.2 J	0.15 J	< 0.03 UJ	< 0.03 UJ
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-2-4	7/21/2015	850.77	2 - 4 ft	180-46139-1	Excavated	100	< 0.77 U	< 0.94 U	< 1.3 U	< 0.95 U	67 J	30 J	3 J	< 1.4 U	< 0.76 U
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-4-6	7/21/2015	850.77	4 - 6 ft	180-46139-1	Excavated	197.9	< 0.76 U	< 0.93 U	< 1.3 U	< 0.94 U	140 J	53 J	4.9 J	< 1.4 U	< 0.75 U
Rear Parking Lot	SSHS-B119	SSHS-B119-SUB-6-8	7/21/2015	850.77	6 - 8 ft	180-46139-1	Excavated	19.58	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	14 J	4.8 J	0.78 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-2-4	7/28/2018	851.62	2 - 4 ft	180-80273-1	Excavated	0.1884	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.14 J	0.041 J	0.0074 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-4-6	7/6/2018	851.75	4 - 6 ft	180-79550-1	Not Excavated	0.103	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.073 J	0.03 J	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1194	SSHS-B1194-SUB-4-6	6/29/2018	852.03	4 - 6 ft	180-79432-1	Not Excavated	0.127	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.084 J	0.043 J	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-8-10	7/6/2018	851.80	8 - 10 ft	180-79550-1	Not Excavated	0.57	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17 J	0.4 J	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-10-12	7/6/2018	851.80	10 - 12 ft	180-79550-1	Not Excavated	3.11	< 0.0073 U	< 0.014 U	< 0.013 U	< 0.013 U	2.2 J	0.91 J	< 0.0063 U	< 0.016 U	< 0.011 U
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-12-14	7/6/2018	851.80	12 - 14 ft	180-79550-1	Not Excavated	0.073	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.048 J	0.025 J	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B119A	SSHS-B119A-SUB-8-10	8/3/2015	850.77	8 - 10 ft	180-46601-1	Excavated	15.13	< 0.043 U	< 0.052 U	< 0.072 U	< 0.053 U	11 J	3.7 J	0.43 J	< 0.077 U	< 0.042 U
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-2-4	7/21/2015	850.98	2 - 4 ft	180-46139-1	Excavated	39.5	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	28 J	10 J	1.5 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-4-6	7/21/2015	850.98	4 - 6 ft	180-46139-1	Excavated	25.2	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	19 J	5.2 J	1 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B120	SSHS-B120-SUB-6-8	7/21/2015	850.98	6 - 8 ft	180-46139-1	Excavated	0.0151	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.0091 J	0.006 J	< 0.0042 U	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B1202	SSHS-B1202-SUB-2-4	6/29/2018	852.10	2 - 4 ft	180-79432-1	Not Excavated	2.09	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4 J	0.55 J	0.14 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1202	SSHS-B1202-SUB-4-6	6/29/2018	852.10	4 - 6 ft	180-79432-1	Not Excavated	0.327	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.24 J	0.069 J	0.018 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1203	SSHS-B1203-SUB-2-4	6/30/2018	851.27	2 - 4 ft	180-79440-2	Excavated	373	< 0.62 U	< 1.2 U	< 1.1 U	< 1.1 U	240 J	120 J	13 J	< 1.3 U	< 0.93 U
Rear Parking Lot	SSHS-B1203	SSHS-B1203-SUB-4-6	7/6/2018	851.27	4 - 6 ft	180-79550-1	Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1204	SSHS-B1204-SUB-2-4	7/1/2018	850.64	2 - 4 ft	180-79440-1	Excavated	4.42	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7 J	2.4 J	0.32 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1204	SSHS-B1204-SUB-10-12	7/28/2018	850.73	10 - 12 ft	180-80273-1	Not Excavated	2.12	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.62 J		< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1205	SSHS-B1205-SUB-2-4	7/5/2018	851.33	2 - 4 ft	180-79550-1	Excavated	ND	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1205	SSHS-B1205-SUB-12-14	7/5/2018	851.11	12 - 14 ft	180-79550-1	Not Excavated	ND	< 0.0068 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0059 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1206	SSHS-B1206-SUB-2-4	7/2/2018	852.54	2 - 4 ft	180-79440-1	Excavated	0.55	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.31 J	0.24 J		< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1206	SSHS-B1206-SUB-4-6	7/2/2018	852.30	4 - 6 ft	180-79440-1	Not Excavated	1.126	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.49 J	0.55 J	0.086 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-2-4	7/24/2015	851.01	2 - 4 ft	180-46251-1	Excavated	127.7	< 0.38 U	< 0.47 U	< 0.64 U	< 0.47 U	90 J	34 J	3.7 J	< 0.69 U	< 0.38 U
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-4-6	7/24/2015	851.01	4 - 6 ft	180-46251-1	Excavated	90.4	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	65 J	21 J	4.4 J	< 0.34 U	< 0.18 U
Rear Parking Lot	SSHS-B121	PS-FD-#33	7/24/2015	851.01	6 - 7 ft	180-46251-2	Excavated	1.17	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.7 J	0.38 J	0.09 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-6-7	7/24/2015	851.01	6 - 7 ft	180-46251-1	Excavated	1.035	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.61 J	0.34 J	0.085 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B1212	SSHS-B1212-SUB-4-6	6/27/2018	853.67	4 - 6 ft	200-44116-1	Excavated	100	< 3.2 U	< 3.2 U	< 3.2 U	< 3.2 U	100	< 3.2 U	< 3.2 U	< 3.2 U	< 3.2 U
Rear Parking Lot	SSHS-B1214	PS-FD-4	6/29/2018	852.25	4 - 6 ft	180-79432-1	Excavated	16.47	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	11 J	4.8 J	0.67 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B1214	SSHS-B1214-SUB-4-6	6/29/2018	852.25	4 - 6 ft	180-79432-1	Excavated	20.09	< 0.12 U	< 0.23 U	< 0.21 U	< 0.22 U	13 J	6.3 J	0.79 J	< 0.25 U	< 0.18 U
Rear Parking Lot	SSHS-B1215	PS-FD-6	6/30/2018	851.81	4 - 6 ft	180-79440-1	Excavated	0.802	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.28 J	0.45 J	0.072 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1215	SSHS-B1215-SUB-4-6	6/30/2018	851.81	4 - 6 ft	180-79440-1	Excavated	0.48	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.15 J	0.33 J	< 0.0051 U	< 0.013 U	< 0.0088 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B1216	SSHS-B1216-SUB-4-6	6/29/2018	852.51	4 - 6 ft	180-79432-1	Excavated	1.8	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1 J	0.59 J	0.21 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1218	SSHS-B1218-SUB-4-6	7/28/2018	849.34	4 - 6 ft	180-80273-1	Excavated	60.4	< 0.12 U	< 0.25 U	< 0.22 U	< 0.23 U	45 J	13 J	2.4 J	< 0.27 U	< 0.18 U
Rear Parking Lot	SSHS-B1219	SSHS-B1219-SUB-4-6	7/1/2018	850.09	4 - 6 ft	180-79440-2	Excavated	16.74	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	9.5 J	6.5 J	0.74 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B1219	SSHS-B1219-SUB-10-12	7/1/2018	850.00	10 - 12 ft	180-79440-2	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-2-4	7/22/2015	851.00	2 - 4 ft	180-46170-1	Excavated	2.705	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	2 J	0.64 J	0.065 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-4-6	7/22/2015	851.00	4 - 6 ft	180-46170-1	Excavated	7.51	< 0.019 U,F1,F2	< 0.023 U	< 0.032 U	< 0.023 U	5.3 J	2 J	0.21 J	< 0.034 U	< 0.018 U
Rear Parking Lot	SSHS-B122	PS-FD-#24	7/22/2015	851.00	6 - 7 ft	180-46170-1	Excavated	6.32	< 0.02 U	< 0.024 U	< 0.033 U	< 0.024 U	4.6 J	1.5 J	0.22 J	< 0.035 U	< 0.019 U
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-6-7	7/22/2015	851.00	6 - 7 ft	180-46170-1	Excavated	3.93	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	2.7 J	1.1 J	0.13 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B1220	SSHS-B1220-SUB-6-8	7/2/2018	852.30	6 - 8 ft	180-79440-2	Not Excavated	0.61	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.61	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1221	SSHS-B1221-SUB-6-8	6/30/2018	851.57	6 - 8 ft	180-79440-1	Excavated	0.502	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.092 J	0.41 J	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1223	SSHS-B1223-SUB-6-8	7/2/2018	850.41	6 - 8 ft	180-79440-2	Excavated	0.961	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.68 J	0.23 J	0.051 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1223	7-2-FD-1	7/2/2018	850.41	6 - 8 ft	180-79440-2	Not Excavated	1.412	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	1 J	0.34 J	0.072 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B1224	SSHS-B1224-SUB-6-8	7/1/2018	850.57	6 - 8 ft	180-79440-2	Excavated	0.093	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.071 J	0.022 J	< 0.0061 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1224	SSHS-B1224-SUB-8-10	7/1/2018	850.64	8 - 10 ft	180-79440-2	Not Excavated	14.44	< 0.057 U	< 0.11 U	< 0.1 U	< 0.1 U	8.9 J	5.1 J	0.44 J	< 0.12 U	< 0.085 U
Rear Parking Lot	SSHS-B1228	SSHS-B1228-SUB-2-4	7/6/2018	851.50	2 - 4 ft	180-79550-1	Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1229	SSHS-B1229-SUB-2-4	6/28/2018	853.00	2 - 4 ft	180-79394-1	Excavated	63.1	< 0.25 U	< 0.49 U	< 0.45 U	< 0.45 U	45 J	17 J	1.1 J	< 0.53 U	< 0.37 U
Rear Parking Lot	SSHS-B1230	SSHS-B1230-SUB-2-4	6/30/2018	852.63	2 - 4 ft	180-79440-1	Excavated	56.92	< 0.12 U	< 0.25 U	< 0.23 U	< 0.23 U	40 J	16 J	0.92 J	< 0.27 U	< 0.19 U
Rear Parking Lot	SSHS-B1231	SSHS-B1231-SUB-4-6	6/29/2018	851.94	4 - 6 ft	180-79432-1	Excavated	0.458	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.39 J	0.068 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1232	SSHS-B1232-SUB-4-6	6/29/2018	851.94	4 - 6 ft	180-79432-1	Excavated	15.6	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	7.4 J	5.2 J	1 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-B1233	SSHS-B1233-SUB-4-6	7/2/2018	852.40	4 - 6 ft	180-79440-1	Not Excavated	0.393	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.15 J	0.21 J	0.033 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1234	SSHS-B1234-SUB-4-6	6/28/2018	852.82	4 - 6 ft	180-79394-1	Excavated	7.76	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.5 J	3.8 J	0.46 J	< 0.013 UJ	< 0.0091 UJ
Rear Parking Lot	SSHS-B1234	SSHS-B1234-SUB-8-10	6/28/2018	852.60	8 - 10 ft	180-79394-1	Not Excavated	3.9	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	3.6 J	0.3 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1235	SSHS-B1235-SUB-4-6	7/2/2018	848.02	4 - 6 ft	180-79440-1	Not Excavated	0.132	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.076 J	0.044 J	0.012 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1236	SSHS-B1236-SUB-4-6	7/2/2018	850.26	4 - 6 ft	180-79440-1	Not Excavated	2.6	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.6 J	0.9 J	0.1 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1236	SSHS-B1236-SUB-6-8	7/2/2018	850.26	6 - 8 ft	180-79440-1	Not Excavated	0.755	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47 J	0.26 J	0.025 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1237	SSHS-B1237-SUB-4-6	7/2/2018	850.26	4 - 6 ft	180-79440-1	Excavated	1.7	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.68 J	0.73 J	0.29 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1237	SSHS-B1237-SUB-8-10	7/2/2018	849.85	8 - 10 ft	180-79440-2	Not Excavated	3.52	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	1.1 J	0.22 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1238	SSHS-B1238-SUB-4-6	7/28/2018	848.61	4 - 6 ft	180-80273-1	Excavated	3.12	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	0.77 J	0.15 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1238	SSHS-B1238-SUB-8-10	7/28/2018	848.61	8 - 10 ft	180-80273-1	Excavated	0.125	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.092 J	0.033 J	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1239	SSHS-B1239-SUB-4-6	7/28/2018	847.52	4 - 6 ft	180-80273-1	Excavated	64.3	< 0.3 U	< 0.6 U	< 0.55 U	< 0.56 U	49 J	13 J	2.3 J	< 0.65 U	< 0.45 U
Rear Parking Lot	SSHS-B1239	SSHS-B1239-SUB-6-8	7/28/2018	847.52	6 - 8 ft	180-80273-1	Excavated	26.5	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	21 J	4.5 J	1 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-2-4	8/3/2015	851.17	2 - 4 ft	180-46601-1	Excavated	10.88	< 0.04 U	< 0.049 U	< 0.067 U	< 0.049 U	7 J	3.5 J	0.38 J	< 0.072 U	< 0.039 U
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-4-6	8/3/2015	851.17	4 - 6 ft	180-46601-1	Excavated	20.48	< 0.075 U	< 0.092 U	< 0.13 U	< 0.093 U	13 J	6.5 J	0.98 J	< 0.14 U	< 0.074 U
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-6-8	8/3/2015	851.17	6 - 8 ft	180-46601-1	Excavated	32.7	< 0.083 U	< 0.1 U	< 0.14 U	< 0.1 U	21 J	10 J	1.7 J	< 0.15 U	< 0.082 U
Rear Parking Lot	SSHS-B124	SSHS-B124-SUB-8-10	8/3/2015	851.17	8 - 10 ft	180-46601-2	Excavated	25.97	< 0.042 U	< 0.052 U	< 0.071 U	< 0.052 U	16 J	9.1 J	0.87 J	< 0.076 U	< 0.042 U
Rear Parking Lot	SSHS-B1242	SSHS-B1242-SUB-6-8	6/29/2018	851.78	6 - 8 ft	180-79432-1	Not Excavated	1.94	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2 J	0.55 J	0.19 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1243	SSHS-B1243-SUB-6-8	6/29/2018	851.53	6 - 8 ft	180-79432-1	Not Excavated	0.92	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.42 J	0.36 J	0.14 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1244	SSHS-B1244-SUB-6-8	7/1/2018	848.20	6 - 8 ft	180-79440-1	Not Excavated	0.095	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	0.065 J	0.03 J	< 0.0055 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1245	SSHS-B1245-SUB-4-6	7/28/2018	849.10	4 - 6 ft	180-80273-1	Not Excavated	20.2	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	16 J	4.2 J		< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B1245	SSHS-B1245-SUB-6-8	7/28/2018	849.10	6 - 8 ft	180-80273-1	Not Excavated	19.31	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	15 J	3.7 J	0.61 J	< 0.14 U	< 0.095 U
Rear Parking Lot	SSHS-B1247	SSHS-B1247-SUB-10-12	7/6/2018	851.72	10 - 12 ft	180-79550-1	Not Excavated	4	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	4	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1249	SSHS-B1249-SUB-10-12	7/6/2018	851.72	10 - 12 ft	180-79550-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1249	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	10 - 12 ft	180-79550-1	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B125	CS-FD-#18	7/31/2015	850.91	2 - 4 ft	180-46444-1	Excavated	0.056	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.043 J	0.013 J	< 0.0043 U	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-2-4	7/31/2015	850.91	2 - 4 ft	180-46444-1	Excavated	0.0069	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	0.0069 J	< 0.0042 U	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-4-6	7/31/2015	850.91	4 - 6 ft	180-46444-1	Not Excavated	0.939	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	0.68 J	0.22 J	0.039 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-6-8	7/31/2015	850.91	6 - 8 ft	180-46444-1	Not Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B1251	SSHS-B1251-SUB-10-12	7/1/2018	849.70	10 - 12 ft	180-79440-3	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-6-8	7/28/2018	849.24	6 - 8 ft	180-80273-1	Excavated	42.9	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	32 J	9.3 J	1.6 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-10-12	7/1/2018	849.20	10 - 12 ft	180-79440-3	Not Excavated	0.076	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U		0.017 J	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1253	SSHS-B1253-SUB-6-8	7/28/2018	851.00	8 - 10 ft	180-80273-1	Not Excavated	14.8	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	11 J	3.2 J	0.6 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-10-12	7/1/2018	849.77	10 - 12 ft	180-79440-3	Not Excavated	1.7	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U		0.43 J	0.07 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-12-14	7/1/2018	849.77	12 - 14 ft	180-79440-3	Not Excavated	0.44	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U		0.11 J	0.02 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B1255	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	4 - 6 ft	180-79581-1	Not Excavated	7.56	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	4.9 J	2.4 J	0.26 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1257	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	6 - 8 ft	180-79670-1	Not Excavated	63.3	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	45 J	17 J	1.3 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-2-4	7/31/2015	850.94	2 - 4 ft	180-46444-1	Excavated	ND	< 0.0039 U	< 0.0047 U	< 0.0066 U	< 0.0048 U	< 0.0047 U	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B126	CS-FD-#19	7/31/2015	850.94	4 - 6 ft	180-46444-1	Not Excavated	0.852	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	0.62 J	0.2 J	0.032 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-4-6	7/31/2015	850.94	4 - 6 ft	180-46444-1	Not Excavated	0.566	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.4 J	0.14 J	0.026 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-6-8	7/31/2015	850.94	6 - 8 ft	180-46444-1	Not Excavated	0.007	< 0.0041 U	< 0.0051 U	< 0.007 U	< 0.0051 U	< 0.0051 U	< 0.0048 U	0.007 J	< 0.0075 U	< 0.0041 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-8-10	7/31/2015	850.94	8 - 10 ft	180-46444-1	Not Excavated	4.9	< 0.0042 U	< 0.0051 U	< 0.0071 U	< 0.0052 U	3.6 J	1.3 J		< 0.0075 U	< 0.0041 U
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-2-4	7/31/2015	850.97	2 - 4 ft	180-46444-1	Excavated	34.3	< 0.074 U	< 0.091 U	< 0.13 U	< 0.092 U	23 J	9.6 J	1.7 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-4-6	7/31/2015	850.97	4 - 6 ft	180-46444-1	Excavated	171.8	< 0.38 U	< 0.47 U	< 0.64 U	< 0.47 U	120 J	46 J	5.8 J	< 0.69 U	< 0.38 U
Rear Parking Lot	SSHS-B127	SSHS-B127-SUB-6-8	7/31/2015	850.97	6 - 8 ft	180-46444-1	Excavated	ND	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	< 0.0049 U	< 0.0047 U	< 0.0043 U	< 0.0073 U	< 0.004 U
Rear Parking Lot	SSHS-B129	CS-FD-#17	7/31/2015	851.20	2 - 4 ft	180-46444-1	Excavated	25	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	17 J	6.8 J	1.2 J	< 0.067 U	< 0.037 U
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-2-4	7/31/2015	851.20	2 - 4 ft	180-46444-1	Excavated	20.6	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	14 J	5.6 J	1 J	< 0.067 U	< 0.037 U
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-4-6	7/31/2015	851.20	4 - 6 ft	180-46444-1	Excavated	18.36	< 0.019 U	< 0.023 U	< 0.032 U	< 0.023 U	13 J	4.7 J	0.66 J	< 0.034 U	< 0.018 U
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-6-8	7/31/2015	851.20	6 - 8 ft	180-46444-1	Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	< 0.0048 U	< 0.0046 U	< 0.0042 U,F2	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B129	SSHS-B129-SUB-8-10	7/31/2015	851.20	8 - 10 ft	180-46444-1	Excavated	15.23	< 0.038 U	< 0.047 U	< 0.065 U	< 0.048 U	11 J	3.8 J	0.43 J	< 0.07 U	< 0.038 U
Rear Parking Lot	SSHS-B130	PS-FD-#16	7/21/2015	851.31	2 - 4 ft	180-46139-1	Excavated	103.2	< 0.2 U	< 0.24 U	< 0.34 U	< 0.25 U	76 J	25 J	2.2 J	< 0.36 U	< 0.2 U
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-2-4	7/21/2015	851.31	2 - 4 ft	180-46139-1	Excavated	108.1	< 0.19 U	< 0.24 U	< 0.33 U	< 0.24 U	77 J	27 J	4.1 J	< 0.35 U	< 0.19 U
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-4-6	7/21/2015	851.31	4 - 6 ft	180-46139-1	Excavated	35.2	< 0.039 U	< 0.048 U	< 0.066 U	< 0.049 U	27 J	7 J	1.3 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B130	SSHS-B130-SUB-6-8	7/21/2015	851.31	6 - 8 ft	180-46139-1	Excavated	0.0205	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	0.014 J	0.0065 J	< 0.0041 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-2-4	7/24/2015	851.52	2 - 4 ft	180-46251-1	Excavated	33.28	< 0.074 U	< 0.091 U	< 0.13 U	< 0.092 U	23 J	9.3 J	0.98 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-4-6	7/24/2015	851.52	4 - 6 ft	180-46251-1	Excavated	6.67	< 0.0038 U,F1	< 0.0046 U	< 0.0064 U	< 0.0047 U	4.3 J	2 J	0.37 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B131	SSHS-B131-SUB-6-8	7/24/2015	851.52	6 - 8 ft	180-46251-1	Excavated	1.217	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.82 J	0.34 J	0.057 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-2-4	7/22/2015	851.41	2 - 4 ft	180-46170-1	Excavated	36.4	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	27 J	8 J	1.4 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-4-6	7/22/2015	851.41	4 - 6 ft	180-46170-1	Excavated	29.4	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	21 J	7.2 J	1.2 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-6-7	7/22/2015	851.41	6 - 7 ft	180-46170-1	Excavated	5.48	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.7 J	1.5 J	0.28 J	< 0.0069 U	< 0.0038 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B1325	SSHS-B1325-SUB-2-4	7/24/2018	852.59	2 - 4 ft	180-80110-1	Excavated	1.05	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.65 J	0.31 J	0.09 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-2-4	8/3/2015	852.64	2 - 4 ft	180-46601-1	Not Excavated	2.7	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	1.5 J	1.2 J		< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-4-6	8/3/2015	852.64	4 - 6 ft	180-46601-1	Not Excavated	3.34	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.1 J	1.1 J	0.14 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-6-8	8/3/2015	852.64	6 - 8 ft	180-46601-1	Not Excavated	ND	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	< 0.0047 U	< 0.0045 U	< 0.0041 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B1346	SSHS-B1346-SUB-4-6	8/3/2018	851.99	4 - 6 ft	180-80462-1	Not Excavated	1.96	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	0.53 J	0.13 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1373	SSHS-B1373-SUB-8-10	7/24/2018	852.50	8 - 10 ft	180-80110-1	Not Excavated	2.5	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	2.5	< 0.0058 U	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-2-4	8/3/2015	851.34	2 - 4 ft	180-46601-1	Excavated	2.653	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	1.7 J	0.87 J	0.083 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-4-6	8/3/2015	851.34	4 - 6 ft	180-46601-1	Excavated	0.2434	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	0.18 J	0.057 J	0.0064 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-6-8	8/3/2015	851.34	6 - 8 ft	180-46601-1	Not Excavated	ND	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	< 0.0045 U	< 0.0043 U	< 0.004 U	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B1390	SSHS-B1390-SUB-8-10	8/4/2018	851.82	8 - 10 ft	180-80511-1	Excavated	0.345	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.22 J	0.1 J	0.025 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1396	B1396-6FT	7/21/2018	852.20	4 - 6 ft	180-80092-1	Excavated	3.72	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.4	1	0.32	< 0.013 U	< 0.0088 U
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Rear Parking Lot	SSHS-B140	SSHS-B140-SUB-2-4	7/31/2015	851.74	2 - 4 ft	180-46444-1	Excavated	ND	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	< 0.0046 U	< 0.0044 U	< 0.004 U	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-2-4	7/21/2015	851.79	2 - 4 ft	180-46139-1	Excavated	6.92	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	4.7 J	2 J	0.22 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B141	PS-FD-#18	7/21/2015	851.79	4 - 6 ft	180-46139-1	Excavated	1.91	< 0.0036 U	< 0.0044 U	< 0.006 U	< 0.0044 U	1.3 J	0.55 J	0.06 J	< 0.0064 U	< 0.0035 U
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-4-6	7/21/2015	851.79	4 - 6 ft	180-46139-1	Excavated	1.117	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.75 J	0.33 J	0.037 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B141	SSHS-B141-SUB-6-8	7/21/2015	851.79	6 - 8 ft	180-46139-1	Excavated	0.2428	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	0.17 J	0.066 J	0.0068 J	< 0.0066 U	< 0.0036 U
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-2-4	7/21/2015	851.86	2 - 4 ft	180-46139-1	Excavated	14.73	< 0.037 U	< 0.045 U	< 0.063 U	< 0.046 U	10 J	4.3 J	0.43 J	< 0.067 U	< 0.037 U
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-4-6	7/21/2015	851.86	4 - 6 ft	180-46139-1	Excavated	2.578	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	1.8 J	0.71 J	0.068 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B142	SSHS-B142-SUB-6-8	7/21/2015	851.86	6 - 8 ft	180-46139-1	Excavated	0.006	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.006 J	< 0.0043 U	< 0.004 U	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-2-4	7/21/2015	851.71	2 - 4 ft	180-46139-1	Excavated	31.8	< 0.039 U	< 0.048 U	< 0.066 U	< 0.049 U	23 J	7.3 J	1.5 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-4-6	7/21/2015	851.71	4 - 6 ft	180-46139-1	Excavated	10.12	< 0.037 U,F1	< 0.045 U	< 0.063 U	< 0.046 U	6.9 J	2.9 J	0.32 J	< 0.067 U	< 0.036 U
Rear Parking Lot	SSHS-B144	PS-FD-#17	7/21/2015	851.71	6 - 8 ft	180-46139-1	Excavated	0.0293	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	0.023 J	0.0063 J	< 0.0041 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B144	SSHS-B144-SUB-6-8	7/21/2015	851.71	6 - 8 ft	180-46139-1	Excavated	0.035	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.023 J	0.012 J	< 0.0041 U	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-2-4	7/24/2015	851.85	2 - 4 ft	180-46251-1	Excavated	54.7	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	39 J	14 J	1.7 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-4-6	7/24/2015	851.85	4 - 6 ft	180-46251-1	Excavated	1.36	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.91 J	0.4 J	0.05 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B145	PS-FD-#32	7/24/2015	851.85	6 - 8 ft	180-46251-1	Excavated	9.26	< 0.018 U	< 0.022 U	< 0.031 U	< 0.022 U	6.5 J	2.4 J	0.36 J	< 0.033 U	< 0.018 U
Rear Parking Lot	SSHS-B145	SSHS-B145-SUB-6-8	7/24/2015	851.85	6 - 8 ft	180-46251-1	Excavated	5.47	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	4 J	1.3 J	0.17 J	< 0.0065 U	< 0.0036 U
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-2-4	7/22/2015	851.73	2 - 4 ft	180-46170-1	Excavated	4.22	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.8 J	1.2 J	0.22 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B146	PS-FD-#25	7/22/2015	851.73	4 - 6 ft	180-46170-1	Excavated	13.13	< 0.018 U	< 0.023 U	< 0.031 U	< 0.023 U	9.5 J	3 J	0.63 J	< 0.033 U	< 0.018 U
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-4-6	7/22/2015	851.73	4 - 6 ft	180-46170-1	Excavated	25.7	< 0.038 U	< 0.047 U	< 0.065 U	< 0.048 U	19 J	5.6 J	1.1 J	< 0.07 U	< 0.038 U
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-6-8	7/22/2015	851.73	6 - 8 ft	180-46170-1	Excavated	6.27	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	4.1 J	1.8 J	0.37 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B147	PS-FD-#31	7/23/2015	852.20	2 - 4 ft	180-46218-1	Excavated	40.4	< 0.037 U	< 0.045 U	< 0.062 U	< 0.045 U	28 J	11 J	1.4 J	< 0.066 U	< 0.036 U
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-2-4	7/23/2015	852.20	2 - 4 ft	180-46218-1	Excavated	33.35	< 0.073 U	< 0.09 U	< 0.12 U	< 0.091 U	23 J	9.4 J	0.95 J	< 0.13 U	< 0.072 U
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-4-6	7/23/2015	852.20	4 - 6 ft	180-46218-1	Excavated	14.15	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	9.7 J	4 J	0.45 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B147	SSHS-B147-SUB-6-8	7/23/2015	852.20	6 - 8 ft	180-46218-1	Excavated	0.782	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	0.38 J	0.34 J	0.062 J	< 0.0073 U	< 0.004 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-2-4	8/3/2015	852.19	2 - 4 ft	180-46601-1	Not Excavated	0.772	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.38 J	0.31 J	0.082 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-4-6	8/3/2015	852.19	4 - 6 ft	180-46601-1	Not Excavated	0.197	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.088 J	0.085 J	0.024 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-6-8	8/3/2015	852.19	6 - 8 ft	180-46601-1	Not Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-2-4	7/21/2015	852.27	2 - 4 ft	180-46139-1	Excavated	11.67	< 0.037 U	< 0.045 U	< 0.062 U	< 0.046 U	8.1 J	3.2 J	0.37 J	< 0.067 U	< 0.036 U
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-4-6	7/21/2015	852.27	4 - 6 ft	180-46139-1	Excavated	3.5	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	2.4 J	0.98 J	0.12 J	< 0.0065 U	< 0.0035 U
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-6-8	7/21/2015	852.27	6 - 8 ft	180-46139-1	Not Excavated	1.53	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	< 0.0047 U	1.2 J	0.33 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	80.1	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	74	< 0.039 U	6.1		
Football Field	SSHS-B150	SSHS-B150-SUB-2-4	7/27/2015	855.84	2 - 4 ft	180-46300-1	Excavated	32.9	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	21 J	9.8 J	2.1 J	< 0.069 U	< 0.037 U
Football Field	SSHS-B150	SSHS-B150-SUB-4-6	7/27/2015	855.84	4 - 6 ft	180-46300-2	Excavated	13	< 0.039 U	< 0.048 U	< 0.066 U	< 0.049 U	9.4 J	3 J	0.6 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B1500	SSHS-B1500 (6-8) 20180821	8/21/2018	-	6 - 8 ft	180-81125-1	Not Excavated	0.136	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.098	0.038	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1502	SSHS-B1502 (10-12) 20180821	8/21/2018	-	10 - 12 ft	180-81125-1	Not Excavated	0.029	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.029	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B156	SSHS-B156-SUB-2-4	8/3/2015	852.91	2 - 4 ft	180-46601-1	Excavated	0.745	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	0.4 J	0.31 J	0.035 J	< 0.0067 U	< 0.0036 U
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-2-4	7/31/2015	852.12	2 - 4 ft	180-46444-1	Excavated	26.98	< 0.038 U	< 0.046 U	< 0.064 U	< 0.046 U	19 J	7 J	0.98 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-4-6	7/31/2015	852.12	4 - 6 ft	180-46444-1	Excavated	5.77	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.7 J	1.7 J	0.37 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B157	SSHS-B157-SUB-6-8	7/31/2015	852.12	6 - 8 ft	180-46444-1	Excavated	0.51	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.13 J	0.28 J	0.1 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-2-4	7/21/2015	852.02	2 - 4 ft	180-46139-1	Excavated	34.5	< 0.18 U	< 0.23 U	< 0.31 U	< 0.23 U	26 J	8.5 J	< 0.2 U	< 0.33 U	< 0.18 U
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-4-6	7/21/2015	852.02	4 - 6 ft	180-46139-1	Excavated	42.82	< 0.074 U	< 0.09 U	< 0.12 U	< 0.091 U	31 J	11 J	0.82 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B158	SSHS-B158-SUB-6-8	7/21/2015	852.02	6 - 8 ft	180-46139-1	Excavated	0.958	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.52 J	0.36 J	0.078 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-2-4	8/3/2015	852.33	2 - 4 ft	180-46601-1	Excavated	47.5	< 0.073 U	< 0.09 U	< 0.12 U	< 0.091 U	32 J	14 J	1.5 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-4-6	8/3/2015	852.33	4 - 6 ft	180-46601-1	Not Excavated	61.4	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	46 J	14 J	1.4 J	< 0.34 U	< 0.19 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-6-8	8/3/2015	852.33	6 - 8 ft	180-46601-1	Not Excavated	21.92	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	15 J	6.2 J	0.72 J	< 0.071 U	< 0.039 U
Football Field	SSHS-B15A	SSHS-B15A-SUB-4-6	7/11/2017	856.90	4 - 6 ft	180-68095-1	Excavated	0.482	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.29	0.17	0.022	< 0.013 U	< 0.0055 U
Football Field	SSHS-B15A	SSHS-B15A-SUB-6-8	7/11/2017	856.90	6 - 8 ft	180-68095-1	Excavated	ND	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B15-A	SSHS-B15-A-2-3	7/22/2014	856.92	2 - 3 ft	180-35079-1	Excavated	0.205	< 0.0013 U	< 0.0017 U	< 0.0015 U	< 0.0015 U	0.13 J	0.063 J	< 0.0013 U	0.012 J	< 0.0012 U
Football Field	SSHS-B15-AA	SSHS-B15-AA-SUB-4-6	7/20/2015	856.92	4 - 6 ft	180-46075-1	Excavated	44.3	< 0.078 U	< 0.096 U	< 0.13 U	< 0.097 U	26 J	16 J	2.3 J	< 0.14 U	< 0.077 U
Football Field	SSHS-B15-AA	SSHS-B15-AA-SUB-6-8	7/20/2015	856.92	6 - 8 ft	180-46075-1	Excavated	0.0941	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.061 J	0.027 J	0.0061 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B15-B	SSHS-B15-B-2-3	7/22/2014	856.80	2 - 3 ft	180-35079-1	Excavated	0.31	< 0.0014 U	< 0.0017 U	< 0.0016 U	< 0.0015 U	0.2 J	0.11 J	< 0.0013 U	< 0.002 U	< 0.0012 U
Football Field	SSHS-B15-B	SSHS-B15-DUP8	7/22/2014	856.80	2 - 3 ft	180-35079-1	Excavated	0.273	< 0.0014 U	< 0.0017 U	< 0.0016 U	< 0.0015 U	0.16 J	0.097 J	< 0.0013 U	0.016 J	< 0.0012 U
Football Field	SSHS-B15-C	SSHS-B15-C-2-3	7/22/2014	856.91	2 - 3 ft	180-35079-1	Excavated	22	< 0.027 U	< 0.035 U	< 0.032 U	< 0.03 U	15 J	7 J	< 0.026 U	< 0.04 U	< 0.024 U
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-2-4	8/3/2015	852.12	2 - 4 ft	180-46601-1	Excavated	26.62	< 0.074 U	< 0.09 U	< 0.12 U	< 0.091 U	19 J	6.7 J	0.92 J	< 0.13 U	< 0.073 U
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-4-6	8/3/2015	852.12	4 - 6 ft	180-46601-1	Excavated	15.75	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	9.9 J	5.1 J	0.75 J	< 0.068 U	< 0.037 U
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-6-8	8/3/2015	852.12	6 - 8 ft	180-46601-1	Not Excavated	13.07	< 0.036 U	< 0.044 U	< 0.061 U	< 0.045 U	9.2 J	3.4 J	0.47 J	< 0.065 U	< 0.036 U
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-8-10	8/3/2015	852.12	8 - 10 ft	180-46601-2	Not Excavated	12.13	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	8.1 J	3.5 J	0.53 J	< 0.067 U	< 0.037 U
Rear Parking Lot	SSHS-B161	CS-FD-#24	8/3/2015	852.38	2 - 4 ft	180-46601-1	Excavated	145.1	< 0.38 U	< 0.46 U	< 0.64 U	< 0.47 U	97 J	43 J	5.1 J	< 0.68 U	< 0.37 U
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-2-4	8/3/2015	852.38	2 - 4 ft	180-46601-1	Excavated	120.1	< 0.37 U	< 0.46 U	< 0.63 U	< 0.46 U	120 J	44 J	6.1 J	< 0.67 U	< 0.37 U
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-4-6	8/3/2015	852.38	4 - 6 ft	180-46601-1	Excavated	7.84	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	5.3 J	2.3 J	0.24 J	< 0.069 U	< 0.038 U
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-6-8	8/3/2015	852.38	6 - 8 ft	180-46601-1	Not Excavated	1.13	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.29 J	0.84 J		< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-2-4	8/3/2015	852.38	2 - 4 ft	180-46601-1	Excavated	14.32	< 0.072 U	< 0.089 U	< 0.12 U	< 0.09 U	9.9 J	3.9 J	0.52 J	< 0.13 U	< 0.071 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-4-6	8/3/2015	852.38	4 - 6 ft	180-46601-1	Not Excavated	4.12	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.9 J	1.1 J	0.12 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-6-8	8/3/2015	852.38	6 - 8 ft	180-46601-1	Not Excavated	4.15	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	1.3 J	2.4 J	0.45 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B164	SSHS-B164-SUB-2-4	7/27/2015	855.84	2 - 4 ft	180-46300-1	Excavated	4.66	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	2.8 J	1.5 J	0.36 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B168	SSHS-B168-SUB-2-4	7/27/2015	855.64	2 - 4 ft	180-46300-1	Excavated	20.8	< 0.019 U	< 0.023 U	< 0.032 U	< 0.023 U	13 J	6.5 J	1.3 J	< 0.034 U	< 0.019 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B168	SSHS-B168-SUB-4-6	7/27/2015	855.64	4 - 6 ft	180-46300-2	Excavated	2.47	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	1.7 J	0.63 J	0.14 J	< 0.0068 U	< 0.0037 U
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-2-4	7/26/2018	852.76	2 - 4 ft	180-80225-2	Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-8-10	7/26/2018	852.76	8 - 10 ft	180-80225-2	Excavated	0.023	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.023	< 0.0053 U	< 0.013 U	< 0.009 U
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-10-12	7/26/2018	852.76	10 - 12 ft	180-80225-2	Not Excavated	0.022	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.022	< 0.0055 U	< 0.013 U	< 0.0093 U
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2025	PS-FD-37	7/26/2018	854.55	2 - 4 ft	180-80225-3	Not Excavated	0.456	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.068	0.29	0.098	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-2-4	7/26/2018	854.55	2 - 4 ft	180-80225-2	Not Excavated	0.444	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.1	0.27	0.074	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-4-6	7/26/2018	854.55	4 - 6 ft	180-80225-2	Not Excavated	0.1	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	0.1	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-6-8	7/26/2018	854.55	6 - 8 ft	180-80225-2	Not Excavated	0.237	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.17	0.067	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-8-10	7/26/2018	854.55	8 - 10 ft	180-80225-2	Not Excavated	0.021	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.021	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-10-12	7/26/2018	854.55	10 - 12 ft	180-80225-3	Not Excavated	0.043	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.043	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated	0.46	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.26	0.2	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2026	PS-FD-38	7/26/2018	855.26	4 - 6 ft	180-80225-3	Not Excavated	1.21	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.17	0.89	0.15	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-4-6	7/26/2018	855.26	4 - 6 ft	180-80225-3	Not Excavated	0.73	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.62	0.11	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-6-8	7/26/2018	855.26	6 - 8 ft	180-80225-3	Not Excavated	0.018	< 0.0061 U	0.018 J,p	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-8-10	7/26/2018	855.26	8 - 10 ft	180-80225-3	Not Excavated	0.31	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.27	0.04	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-10-12	7/26/2018	855.26	10 - 12 ft	180-80227-1	Not Excavated	0.688	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.19	0.43	0.068	< 0.015 U	< 0.01 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	4.03	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	2.5	0.23	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-2-4	7/26/2018	855.22	2 - 4 ft	180-80227-1	Excavated	0.509	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.15	0.28	0.079	< 0.013 U	< 0.009 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-4-6	7/26/2018	855.22	4 - 6 ft	180-80227-1	Excavated	0.227	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.077	0.15	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2027	PS-FD-39	7/26/2018	855.22	6 - 8 ft	180-80227-3	Excavated	1.4	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.71	0.58	0.11	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-6-8	7/26/2018	855.22	6 - 8 ft	180-80227-1	Excavated	2.048	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.85	0.098	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-2-4	7/26/2018	855.23	2 - 4 ft	180-80227-3	Excavated	0.76	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.33	0.3	0.13	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-4-6	7/26/2018	855.23	4 - 6 ft	180-80227-3	Excavated	0.383	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17	0.16	0.053	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-6-8	7/26/2018	855.23	6 - 8 ft	180-80227-3	Not Excavated	0.448	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17	0.19	0.088	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-8-10	7/26/2018	855.23	8 - 10 ft	180-80227-3	Not Excavated	0.045	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.023	0.022	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-10-12	7/26/2018	855.23	10 - 12 ft	180-80227-3	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-2-4	7/27/2018	856.20	2 - 4 ft	180-80252-1	Not Excavated	0.545	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.19	0.27	0.085	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-4-6	7/27/2018	856.20	4 - 6 ft	180-80252-1	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-6-8	7/27/2018	856.20	6 - 8 ft	180-80252-1	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-8-10	7/27/2018	856.20	8 - 10 ft	180-80252-1	Not Excavated	0.061	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.031	0.03	< 0.0051 U	< 0.012 U	< 0.0086 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-10-12	7/27/2018	856.20	10 - 12 ft	180-80252-1	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0086 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-2-4	7/27/2018	855.50	2 - 4 ft	180-80251-2	Not Excavated	6.2	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.2	2		< 0.013 U	< 0.0089 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-4-6	7/27/2018	855.50	4 - 6 ft	180-80251-2	Not Excavated	0.4	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.23	0.13	0.04	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-6-8	7/27/2018	855.50	6 - 8 ft	180-80251-2	Not Excavated	0.175	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.1	0.059	0.016 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-8-10	7/27/2018	855.50	8 - 10 ft	180-80251-2	Not Excavated	0.148	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.089	0.047	0.012 J	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2031	PS-FD-48	7/27/2018	855.50	10 - 12 ft	180-80252-2	Not Excavated	0.071	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.047	0.024	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-10-12	7/27/2018	855.50	10 - 12 ft	180-80251-2	Not Excavated	0.14	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.086	0.041	0.013 J	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-10-12	7/27/2018	854.88	10 - 12 ft	180-80251-1	Not Excavated	0.045	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.026	0.019	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-2-4	7/26/2018	855.45	2 - 4 ft	180-80225-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-4-6	7/26/2018	855.45	4 - 6 ft	180-80225-1	Not Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	< 0.014 U	< 0.006 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-6-8	7/26/2018	855.45	6 - 8 ft	180-80225-1	Not Excavated	ND	< 0.0073 U	< 0.015 U	< 0.013 U	< 0.013 U	< 0.018 U	< 0.015 U	< 0.0064 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-8-10	7/26/2018	855.45	8 - 10 ft	180-80225-2	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-10-12	7/26/2018	855.45	10 - 12 ft	180-80225-2	Not Excavated	ND	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	ND	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.01 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-2-4	7/27/2018	855.08	2 - 4 ft	180-80251-1	Excavated	0.024	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	0.024	< 0.006 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2051	PS-FD-45	7/27/2018	855.08	4 - 6 ft	180-80252-2	Excavated	3.42	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.8	1.4	0.22	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-4-6	7/27/2018	855.08	4 - 6 ft	180-80251-1	Excavated	0.62	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.39	0.23		< 0.014 U	< 0.0095 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-6-8	7/27/2018	855.08	6 - 8 ft	180-80251-1	Not Excavated	ND	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	< 0.016 U	< 0.0065 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-8-10	7/27/2018	855.08	8 - 10 ft	180-80251-1	Not Excavated	ND	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-10-12	7/27/2018	855.08	10 - 12 ft	180-80251-1	Not Excavated	0.159	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.084	0.061	0.014 J,p	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	ND	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated	2.041	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4	0.61	0.031	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-4-6	7/25/2018	855.59	4 - 6 ft	180-80154-2	Excavated	5.3	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	4	1.1	0.2	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2052	PS-FD-24	7/25/2018	855.59	6 - 8 ft	180-80157-2	Excavated	3.019	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.3	0.66	0.059	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-6-8	7/25/2018	855.59	6 - 8 ft	180-80154-2	Excavated	3.7	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	2.8	0.83	0.07	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-2-4	7/25/2018	855.00	2 - 4 ft	180-80157-1	Excavated	0.968	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.33	0.57	0.068	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	2.499	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.6	0.84	0.059	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-6-8	7/25/2018	855.00	6 - 8 ft	180-80157-1	Excavated	0.4	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.2	0.2	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2053	PS-FD-26	7/25/2018	855.00	8 - 10 ft	180-80157-2	Excavated	0.184	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.09	0.094	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-8-10	7/25/2018	855.00	8 - 10 ft	180-80157-1	Excavated	0.219	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.099	0.12	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-10-12	7/25/2018	855.00	10 - 12 ft	180-80157-1	Excavated	0.278	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.1	0.16	0.018 J	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	0.25	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.12	0.13	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-4-6	7/25/2018	854.72	4 - 6 ft	180-80157-3	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-6-8	7/25/2018	854.72	6 - 8 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-8-10	7/25/2018	854.72	8 - 10 ft	180-80157-3	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-10-12	7/25/2018	854.72	10 - 12 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-2-4	7/27/2018	856.16	2 - 4 ft	180-80251-2	Excavated	0.088	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.054	0.034	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-4-6	7/27/2018	856.16	4 - 6 ft	180-80251-2	Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-6-8	7/27/2018	856.16	6 - 8 ft	180-80251-2	Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2071	SSHS-B2071-SUB-8-10	7/27/2018	856.16	8 - 10 ft	180-80251-2	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2071	PS-FD-47	7/27/2018	856.16	10 - 12 ft	180-80252-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-10-12	7/27/2018	856.16	10 - 12 ft	180-80251-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2072	PS-FD-22	7/25/2018	856.82	2 - 4 ft	180-80157-2	Excavated	0.885	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.46	0.4	0.025	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-2-4	7/25/2018	856.82	2 - 4 ft	180-80154-2	Excavated	1.352	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.83	0.5	0.022	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-4-6	7/25/2018	856.82	4 - 6 ft	180-80154-2	Excavated	0.144	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	0.081	0.063	< 0.0059 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-6-8	7/25/2018	856.82	6 - 8 ft	180-80154-2	Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-8-10	7/25/2018	856.82	8 - 10 ft	180-80154-2	Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-10-12	7/25/2018	856.82	10 - 12 ft	180-80154-2	Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-2-4	7/25/2018	856.99	2 - 4 ft	180-80157-3	Excavated	0.73	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.34	0.29	0.1	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-4-6	7/25/2018	856.99	4 - 6 ft	180-80157-3	Excavated	0.87	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.29	0.11	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-6-8	7/25/2018	856.99	6 - 8 ft	180-80157-3	Excavated	0.451	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.19	0.19	0.071	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-8-10	7/25/2018	856.99	8 - 10 ft	180-80157-3	Excavated	0.452	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.16	0.21	0.082	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-10-12	7/25/2018	856.99	10 - 12 ft	180-80157-3	Not Excavated	0.184	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.063	0.089	0.032	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	0.096	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.035	0.044	0.017 J	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-2-4	7/25/2018	855.40	2 - 4 ft	180-80157-3	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-4-6	7/25/2018	855.40	4 - 6 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-6-8	7/25/2018	855.40	6 - 8 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-8-10	7/25/2018	855.40	8 - 10 ft	180-80157-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-10-12	7/25/2018	855.40	10 - 12 ft	180-80157-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-2-4	7/27/2018	855.97	2 - 4 ft	180-80251-2	Excavated	3.09	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.79	2.3	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2090	PS-FD-49	7/27/2018	855.97	4 - 6 ft	180-80252-2	Excavated	0.357	< 0.0071 U	< 0.014 U	< 0.013 U	< 0.013 U	0.089	0.19	0.078	< 0.015 U	< 0.011 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-4-6	7/27/2018	855.97	4 - 6 ft	180-80251-2	Excavated	1	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.6	0.29	0.11	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-6.8	7/27/2018	855.97	6 - 8 ft	180-80251-2	Not Excavated	1.12	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.34	0.78	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-8-10	7/27/2018	855.97	8 - 10 ft	180-80251-2	Not Excavated	0.106	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.018 J	0.062	0.026	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-10-12	7/27/2018	855.97	10 - 12 ft	180-80251-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	0.1	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.034	0.054	0.012 J,p	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-4-6	7/25/2018	856.61	4 - 6 ft	180-80154-1	Not Excavated	0.1078	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.061	0.038	0.0088 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-6-8	7/25/2018	856.61	6 - 8 ft	180-80154-1	Not Excavated	0.101	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.042	0.045	0.014 J	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-8-10	7/25/2018	856.61	8 - 10 ft	180-80154-1	Not Excavated	0.0611	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.029	0.024	0.0081 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-10-12	7/25/2018	856.61	10 - 12 ft	180-80154-1	Not Excavated	0.016	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.016 J	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	0.0452	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.021	0.018 J	0.0062 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2092	PS-FD-27	7/25/2018	856.77	2 - 4 ft	180-80157-2	Excavated	1.355	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.71	0.59	0.055	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2092	SSHS-B2092-SUB-2-4	7/25/2018	856.77	2 - 4 ft	180-80157-3	Excavated	2.68	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.4	0.99	0.29	< 0.013 U	< 0.009 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-2-4	7/25/2018	855.64	2 - 4 ft	180-80154-2	Not Excavated	0.035	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	0.035	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-4-6	7/25/2018	855.64	4 - 6 ft	180-80154-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-6-8	7/25/2018	855.64	6 - 8 ft	180-80154-3	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-8-10	7/25/2018	855.64	8 - 10 ft	180-80154-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-10-12	7/25/2018	855.64	10 - 12 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-2-4	7/25/2018	855.25	2 - 4 ft	180-80154-1	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-4-6	7/25/2018	855.25	4 - 6 ft	180-80154-1	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-6-8	7/25/2018	855.25	6 - 8 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-8-10	7/25/2018	855.25	8 - 10 ft	180-80154-1	Not Excavated	0.221	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.13	0.068	0.023	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-10-12	7/25/2018	855.25	10 - 12 ft	180-80154-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-2-4	7/25/2018	854.78	2 - 4 ft	180-80154-1	Excavated	ND	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-4-6	7/25/2018	854.78	4 - 6 ft	180-80154-1	Excavated	ND	< 0.0074 U	< 0.015 U	< 0.013 U	< 0.014 U	< 0.018 U	< 0.016 U	< 0.0065 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-6-8	7/25/2018	854.78	6 - 8 ft	180-80154-1	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-8-10	7/25/2018	854.78	8 - 10 ft	180-80154-1	Not Excavated	0.017	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.017 J	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-10-12	7/25/2018	854.78	10 - 12 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B212	SSHS-B212-SUB-2-4	7/28/2015	855.42	2 - 4 ft	180-46310-1	Excavated	75.2	< 0.19 U	< 0.23 U	< 0.32 U	< 0.24 U	46 J	23 J	6.2 J	< 0.35 U	< 0.19 U
Football Field	SSHS-B212	SSHS-B212-SUB-4-6	7/28/2015	855.42	4 - 6 ft	180-46310-1	Excavated	9.34	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	6.1 J	2.6 J	0.64 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B212	SSHS-B212-SUB-6-8	7/28/2015	855.42	6 - 8 ft	180-46310-1	Not Excavated	0.154	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.069 J	0.059 J	0.026 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-2-4	7/25/2018	855.91	2 - 4 ft	180-80154-3	Not Excavated	1.04	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.52	0.38	0.14	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-4-6	7/25/2018	855.91	4 - 6 ft	180-80154-3	Not Excavated	0.0556	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.027	0.02	0.0086 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-6-8	7/25/2018	855.91	6 - 8 ft	180-80154-3	Not Excavated	0.062	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.028	0.023	0.011 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-8-10	7/25/2018	855.91	8 - 10 ft	180-80154-3	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-10-12	7/25/2018	855.91	10 - 12 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2128	PS-FD-19	7/25/2018	856.01	2 - 4 ft	180-80157-2	Not Excavated	0.605	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.32	0.23	0.055	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-2-4	7/25/2018	856.01	2 - 4 ft	180-80154-3	Not Excavated	0.163	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.093	0.056	0.014 J	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-4-6	7/25/2018	856.01	4 - 6 ft	180-80157-1	Not Excavated	0.02	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.02	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-6-8	7/25/2018	856.01	6 - 8 ft	180-80157-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-8-10	7/25/2018	856.01	8 - 10 ft	180-80157-1	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-10-12	7/25/2018	856.01	10 - 12 ft	180-80157-1	Not Excavated	0.089	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.052	0.037	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	0.114	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.067	0.047	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-2-4	7/25/2018	855.33	2 - 4 ft	180-80157-1	Not Excavated	0.158	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.091	0.067	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-4-6	7/25/2018	855.33	4 - 6 ft	180-80157-1	Not Excavated	0.041	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.024	0.017 J	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-6-8	7/25/2018	855.33	6 - 8 ft	180-80157-1	Not Excavated	0.037	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.021	0.016 J	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-8-10	7/25/2018	855.33	8 - 10 ft	180-80157-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-10-12	7/25/2018	855.33	10 - 12 ft	180-80157-1	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	0.034	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.019	0.015 J	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B214	CS-FD-#7	7/28/2015	855.97	2 - 4 ft	180-46310-1	Excavated	4.45	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	2.4 J	1.8 J	0.25 J	< 0.007 U	< 0.0038 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B214	SSHS-B214-SUB-2-4	7/28/2015	855.97	2 - 4 ft	180-46310-1	Excavated	4.22	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	2.3 J	1.7 J	0.22 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B214	SSHS-B214-SUB-4-6	7/28/2015	855.97	4 - 6 ft	180-46310-1	Excavated	1.079	< 0.0043 U	< 0.0053 U	< 0.0073 U	< 0.0053 U	0.55 J	0.46 J	0.069 J	< 0.0078 U	< 0.0042 U
Football Field	SSHS-B214	SSHS-B214-SUB-6-8	7/28/2015	855.97	6 - 8 ft	180-46310-1	Excavated	0.0087	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.0087 J	< 0.0046 U	< 0.0043 U	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-2-4	7/25/2018	856.56	2 - 4 ft	180-80154-3	Not Excavated	0.167	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.047	0.083	0.037	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-4-6	7/25/2018	856.56	4 - 6 ft	180-80154-3	Not Excavated	0.0293	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.022	< 0.013 U	0.0073 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2143	PS-FD-21	7/25/2018	856.56	6 - 8 ft	180-80157-2	Not Excavated	0.071	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.04	0.031	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-6-8	7/25/2018	856.56	6 - 8 ft	180-80154-3	Not Excavated	0.019	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.019	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-8-10	7/25/2018	856.56	8 - 10 ft	180-80154-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-10-12	7/25/2018	856.56	10 - 12 ft	180-80154-3	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B216	SSHS-B216-SUB-2-4	7/16/2015	855.82	2 - 4 ft	180-46033-1	Excavated	88.8	< 0.19 U	< 0.24 U	< 0.33 U	< 0.24 U	58 J	25 J	5.8 J	< 0.35 U	< 0.19 U
Football Field	SSHS-B216	SSHS-B216-SUB-4-6	7/16/2015	855.82	4 - 6 ft	180-46033-1	Excavated	8.78	< 0.0041 U	< 0.0051 U	< 0.007 U	< 0.0051 U	6.2 J	2.3 J	0.28 J	< 0.0075 U	< 0.0041 U
Football Field	SSHS-B216	SSHS-B216-SUB-6-8	7/16/2015	855.82	6 - 8 ft	180-46033-1	Not Excavated	ND	< 0.0043 U	< 0.0052 U	< 0.0072 U	< 0.0053 U	< 0.0052 U	< 0.005 U	< 0.0046 U	< 0.0077 U	< 0.0042 U
Football Field	SSHS-B217	SSHS-B217-SUB-2-4	7/16/2015	856.26	2 - 4 ft	180-46033-1	Excavated	8.67	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	5.4 J	2.6 J	0.67 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B217	SSHS-B217-SUB-4-6	7/16/2015	856.26	4 - 6 ft	180-46033-1	Excavated	1.429	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.93 J	0.45 J	0.049 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B217	SSHS-B217-SUB-6-8	7/16/2015	856.26	6 - 8 ft	180-46033-1	Excavated	ND	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	< 0.005 U	< 0.0047 U	< 0.0043 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B218	SSHS-B218-SUB-2-4	7/16/2015	856.58	2 - 4 ft	180-46033-1	Excavated	5.44	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	3.2 J	1.8 J	0.44 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B218	PS-FD-#4	7/16/2015	856.58	4 - 6 ft	180-46033-1	Excavated	4.39	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	3 J	1.2 J	0.19 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B218	SSHS-B218-SUB-4-6	7/16/2015	856.58	4 - 6 ft	180-46033-1	Excavated	2.72	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	1.8 J	0.74 J	0.18 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B218	SSHS-B218-SUB-6-8	7/16/2015	856.58	6 - 8 ft	180-46033-1	Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	< 0.0048 U	< 0.0046 U	< 0.0042 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated	0.19	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.096	0.068	0.026	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2185	PS-FD-16	7/24/2018	855.07	4 - 6 ft	180-80106-3	Not Excavated	0.527	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.34	0.15	0.037	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-4-6	7/24/2018	855.07	4 - 6 ft	180-80106-3	Not Excavated	0.492	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.34	0.12	0.032	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-6-8	7/24/2018	855.07	6 - 8 ft	180-80106-3	Not Excavated	0.459	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.28	0.14	0.039	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-8-10	7/24/2018	855.07	8 - 10 ft	180-80106-3	Not Excavated	0.406	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.25	0.12	0.036	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-10-12	7/24/2018	855.07	10 - 12 ft	180-80106-3	Not Excavated	0.0622	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.032	0.022	0.0082 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	0.135	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.053	0.052	0.03	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated	0.777	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.36	0.36	0.057	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-4-6	7/24/2018	854.94	4 - 6 ft	180-80106-2	Not Excavated	0.344	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.16	0.16	0.024	< 0.013 U	< 0.009 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-6-8	7/24/2018	854.94	6 - 8 ft	180-80106-2	Not Excavated	0.182	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.093	0.067	0.022	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-8-10	7/24/2018	854.94	8 - 10 ft	180-80106-2	Not Excavated	0.0675	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.039	0.022	0.0065 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-10-12	7/24/2018	854.94	10 - 12 ft	180-80106-2	Not Excavated	0.0893	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051	0.03	0.0083 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-4-6	7/24/2018	856.10	4 - 6 ft	180-80106-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-6-8	7/24/2018	856.10	6 - 8 ft	180-80106-2	Not Excavated	0.214	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.14	0.074	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-8-10	7/24/2018	856.10	8 - 10 ft	180-80106-2	Not Excavated	0.202	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.13	0.072	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-10-12	7/24/2018	856.10	10 - 12 ft	180-80106-2	Not Excavated	0.073	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.046	0.027	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	0.06	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.038	0.022	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated	0.187	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	0.043	0.12	0.024	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-4-6	7/24/2018	855.99	4 - 6 ft	180-80106-2	Excavated	0.414	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.16	0.22	0.034	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-6-8	7/24/2018	855.99	6 - 8 ft	180-80106-2	Not Excavated	0.29	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13	0.16	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2188	PS-FD-14	7/24/2018	855.99	8 - 10 ft	180-80106-2	Not Excavated	0.014	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.014 J	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-8-10	7/24/2018	855.99	8 - 10 ft	180-80106-2	Not Excavated	0.014	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	0.014 J	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-10-12	7/24/2018	855.99	10 - 12 ft	180-80106-2	Not Excavated	0.047	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.018	0.029	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated	0.47	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.27	0.2	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-4-6	7/24/2018	855.74	4 - 6 ft	180-80105-3	Excavated	0.58	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.34	0.24	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-6-8	7/24/2018	855.74	6 - 8 ft	180-80105-3	Not Excavated	0.29	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17	0.12	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-8-10	7/24/2018	855.74	8 - 10 ft	180-80105-3	Not Excavated	0.2	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11	0.09	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2189	PS-FD-12	7/24/2018	855.74	10 - 12 ft	180-80106-1	Not Excavated	0.066	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.04	0.026	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-10-12	7/24/2018	855.74	10 - 12 ft	180-80105-3	Not Excavated	0.079	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.049	0.03	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	0.119	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.073	0.046	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated	0.082	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.04	0.031	0.011 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated	0.141	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.072	0.053	0.016 J	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-4-6	7/27/2018	856.06	4 - 6 ft	180-80252-1	Excavated	0.44	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24	0.16	0.04	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-6-8	7/27/2018	856.06	6 - 8 ft	180-80252-1	Not Excavated	0.276	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.15	0.097	0.029	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-8-10	7/27/2018	856.06	8 - 10 ft	180-80252-2	Not Excavated	0.167	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.086	0.061	0.02	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated	0.169	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.069	0.1	< 0.0055 U	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-4-6	7/24/2018	856.18	4 - 6 ft	180-80105-3	Excavated	0.27	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17	0.1	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-6-8	7/24/2018	856.18	6 - 8 ft	180-80105-3	Not Excavated	1.273	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.62	0.58	0.073	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-8-10	7/24/2018	856.18	8 - 10 ft	180-80105-3	Not Excavated	0.666	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.3	0.32	0.046	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-10-12	7/24/2018	856.18	10 - 12 ft	180-80105-3	Not Excavated	0.123	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.075	0.048	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	0.073	< 0.0058 U	< 0.011 U	< 0.011 U	< 0.011 U	0.044	0.029	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2192	PS-FD-34	7/26/2018	855.49	4 - 6 ft	180-80225-3	Not Excavated	0.22	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.12	0.1	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-4-6	7/26/2018	855.49	4 - 6 ft	180-80225-1	Not Excavated	0.142	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.076	0.066	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-6-8	7/26/2018	855.49	6 - 8 ft	180-80225-1	Not Excavated	0.415	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.15	0.23	0.035	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-8-10	7/26/2018	855.49	8 - 10 ft	180-80225-1	Not Excavated	0.075	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	0.038	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-10-12	7/26/2018	855.49	10 - 12 ft	180-80225-1	Not Excavated	0.049	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.024	0.025	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	0.152	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.059	0.093	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2193	PS-FD-33	7/26/2018	857.04	2 - 4 ft	180-80225-3	Excavated	2.59	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	1.5	0.98	0.11	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2193	SSHS-B2193-SUB-2-4	7/26/2018	857.04	2 - 4 ft	180-80225-1	Excavated	3.54	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	2.2	1.2	0.14	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-2-4	7/25/2018	856.19	2 - 4 ft	180-80157-3	Excavated	3.35	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	1.5	1.5	0.35	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-4-6	7/25/2018	856.19	4 - 6 ft	180-80157-3	Not Excavated	0.425	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.2	0.17	0.055	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2194	PS-FD-30	7/25/2018	856.19	6 - 8 ft	180-80157-2	Not Excavated	0.145	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.058	0.077	0.01 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-6-8	7/25/2018	856.19	6 - 8 ft	180-80157-3	Not Excavated	0.18	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.074	0.079	0.027	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-8-10	7/25/2018	856.19	8 - 10 ft	180-80157-3	Not Excavated	0.105	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.039	0.046	0.02	< 0.013 U	< 0.009 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-10-12	7/25/2018	856.19	10 - 12 ft	180-80157-3	Not Excavated	0.097	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.041	0.04	0.016 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-2-4	7/26/2018	855.94	2 - 4 ft	180-80225-1	Excavated	2.87	< 0.0079 U	< 0.016 U	< 0.014 U	< 0.015 U	1.8	0.96	0.11	< 0.017 U	< 0.012 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-4-6	7/26/2018	855.94	4 - 6 ft	180-80225-1	Not Excavated	0.04	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.04	< 0.0058 U	< 0.014 U	< 0.0099 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2195	SSHS-B2195-SUB-6-8	7/26/2018	855.94	6 - 8 ft	180-80225-1	Not Excavated	0.28	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.23	0.05	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2195	PS-FD-31	7/26/2018	855.94	8 - 10 ft	180-80225-3	Not Excavated	0.023	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.023	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-8-10	7/26/2018	855.94	8 - 10 ft	180-80225-1	Not Excavated	0.013	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.013 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-10-12	7/26/2018	855.94	10 - 12 ft	180-80225-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated	1.169	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.72	0.41	0.039	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-4-6	7/24/2018	854.99	4 - 6 ft	180-80105-1	Not Excavated	0.41	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.26	0.15	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-6-8	7/24/2018	854.99	6 - 8 ft	180-80105-1	Not Excavated	0.63	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.4	0.23	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-8-10	7/24/2018	854.99	8 - 10 ft	180-80105-1	Not Excavated	0.59	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38	0.21	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-10-12	7/24/2018	854.99	10 - 12 ft	180-80105-1	Not Excavated	0.176	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11	0.066	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	0.09	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.058	0.032	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated	0.478	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.27	0.19	0.018 J	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-4-6	7/24/2018	855.05	4 - 6 ft	180-80105-2	Excavated	0.43	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.28	0.15	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-6-8	7/24/2018	855.05	6 - 8 ft	180-80105-2	Excavated	0.091	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.058	0.033	< 0.0055 U	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-8-10	7/24/2018	855.05	8 - 10 ft	180-80105-2	Excavated	0.035	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.021	0.014 J	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B220	SSHS-B220-SUB-2-4	7/28/2015	855.52	2 - 4 ft	180-46310-1	Excavated	11.73	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	7.5 J	3.5 J	0.73 J	< 0.069 U	< 0.037 U
Football Field	SSHS-B220	SSHS-B220-SUB-4-6	7/28/2015	855.52	4 - 6 ft	180-46310-1	Excavated	4.84	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	3.2 J	1.3 J	0.34 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B220	SSHS-B220-SUB-6-8	7/28/2015	855.52	6 - 8 ft	180-46310-1	Not Excavated	0.214	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.047 J	0.047 J	0.12 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B221	SSHS-B221-SUB-2-4	7/15/2015	855.95	2 - 4 ft	180-45961-1	Excavated	69.4	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	46 J	19 J	4.4 J	< 0.35 U	< 0.19 U
Football Field	SSHS-B221	SSHS-B221-SUB-4-6	7/15/2015	855.95	4 - 6 ft	180-45961-1	Excavated	8.01	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	5.6 J	2.2 J	0.21 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B221	SSHS-B221-SUB-6-8	7/15/2015	855.95	6 - 8 ft	180-45961-1	Not Excavated	0.039	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	0.039	< 0.0043 U	< 0.0039 U	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-2-4	7/26/2018	855.06	2 - 4 ft	180-80225-2	Not Excavated	0.32	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.32	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-4-6	7/26/2018	855.06	4 - 6 ft	180-80225-2	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-6-8	7/26/2018	855.06	6 - 8 ft	180-80225-2	Not Excavated	0.014	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.014 J	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-8-10	7/26/2018	855.06	8 - 10 ft	180-80225-2	Not Excavated	0.501	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	0.45	0.051	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2213	PS-FD-35	7/26/2018	855.06	10 - 12 ft	180-80225-3	Not Excavated	0.062	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.062	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-10-12	7/26/2018	855.06	10 - 12 ft	180-80225-2	Not Excavated	0.14	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	0.14	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-4-6	7/26/2018	855.14	4 - 6 ft	180-80227-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-6-8	7/26/2018	855.14	6 - 8 ft	180-80227-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-8-10	7/26/2018	855.14	8 - 10 ft	180-80227-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-10-12	7/26/2018	855.14	10 - 12 ft	180-80227-3	Not Excavated	0.055	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.04	0.015 J	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-2-4	7/26/2018	855.11	2 - 4 ft	180-80227-2	Not Excavated	ND	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0059 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-4-6	7/26/2018	855.11	4 - 6 ft	180-80227-2	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-6-8	7/26/2018	855.11	6 - 8 ft	180-80227-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-8-10	7/26/2018	855.11	8 - 10 ft	180-80227-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-10-12	7/26/2018	855.11	10 - 12 ft	180-80227-2	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2216	PS-FD-25	7/25/2018	855.16	2 - 4 ft	180-80157-2	Not Excavated	0.042	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.025	0.017 J,p	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-2-4	7/25/2018	855.16	2 - 4 ft	180-80154-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-4-6	7/25/2018	855.16	4 - 6 ft	180-80154-2	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-6-8	7/25/2018	855.16	6 - 8 ft	180-80154-2	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-8-10	7/25/2018	855.16	8 - 10 ft	180-80154-2	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-10-12	7/25/2018	855.16	10 - 12 ft	180-80154-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-2-4	7/27/2018	855.08	2 - 4 ft	180-80251-3	Excavated	0.543	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.49	0.053	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2217	PS-FD-51	7/27/2018	855.08	4 - 6 ft	180-80252-2	Not Excavated	0.865	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.49	0.31	0.065	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-4-6	7/27/2018	855.08	4 - 6 ft	180-80251-3	Not Excavated	0.31	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.14	0.17	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-6-8	7/27/2018	855.08	6 - 8 ft	180-80251-3	Not Excavated	1.6	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	1.4	0.2	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-8-10	7/27/2018	855.08	8 - 10 ft	180-80251-3	Not Excavated	2.26	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	2	0.26	< 0.013 U	< 0.009 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-10-12	7/27/2018	855.08	10 - 12 ft	180-80251-3	Not Excavated	0.561	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.5	0.061	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	1.12	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	1	0.12	< 0.013 U	< 0.0088 U
Football Field	SSHS-B222	SSHS-B222-SUB-2-4	7/16/2015	856.64	2 - 4 ft	180-46033-1	Excavated	2.65	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	1.7 J	0.81 J	0.14 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B222	SSHS-B222-SUB-4-6	7/16/2015	856.64	4 - 6 ft	180-46033-1	Excavated	4.35	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	3 J	1.2 J	< 0.005 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B222	SSHS-B222-SUB-6-8	7/16/2015	856.64	6 - 8 ft	180-46033-1	Excavated	ND	< 0.0037 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	< 0.0046 U	< 0.0044 U	< 0.004 U	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-4-6	7/24/2018	855.38	4 - 6 ft	180-80106-1	Excavated	1.874	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2	0.62	0.054	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-6-8	7/24/2018	855.38	6 - 8 ft	180-80106-1	Excavated	0.15	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.097	0.053	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-8-10	7/24/2018	855.38	8 - 10 ft	180-80106-1	Excavated	0.204	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.14	0.064	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-10-12	7/24/2018	855.38	10 - 12 ft	180-80106-1	Excavated	0.52	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.32	0.2	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2223	PS-FD-42	7/26/2018	856.38	8 - 10 ft	180-80227-3	Excavated	2.349	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.6	0.67	0.079	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	2.051	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4	0.59	0.061	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	0.66	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.19	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-4-6	7/26/2018	854.93	4 - 6 ft	180-80227-2	Not Excavated	1.38	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.98	0.29	0.11	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-6-8	7/26/2018	854.93	6 - 8 ft	180-80227-2	Not Excavated	0.181	< 0.0071 U	< 0.014 U	< 0.013 U	< 0.013 U	0.13	0.038	0.013 J	< 0.015 U	< 0.011 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-8-10	7/26/2018	854.93	8 - 10 ft	180-80227-2	Not Excavated	0.33	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24	0.068	0.022	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2224	PS-FD-44	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	0.108	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.069	0.039	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	0.163	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.12	0.032	0.011 J	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	4.176	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	3	1.1	0.076	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	0.046	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.046	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-8-10	7/26/2018	856.55	8 - 10 ft	180-80227-2	Not Excavated	3.568	< 0.0063 U,F1	< 0.013 U	< 0.012 U	< 0.012 U	2.5	0.99	0.078	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-10-12	7/26/2018	856.55	10 - 12 ft	180-80227-2	Not Excavated	6.47	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.5	1.8	0.17	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-4-6	7/27/2018	855.33	4 - 6 ft	180-80251-3	Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-6-8	7/27/2018	855.33	6 - 8 ft	180-80252-1	Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.012 U	< 0.017 U	< 0.014 U	< 0.0059 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-8-10	7/27/2018	855.33	8 - 10 ft	180-80252-1	Not Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	< 0.014 U	< 0.006 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-10-12	7/27/2018	855.33	10 - 12 ft	180-80252-1	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2229	SSHS-B2229-SUB-2-4	7/27/2018	855.28	2 - 4 ft	180-80252-1	Excavated	1.24	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.61	0.47	0.16	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2229	SSHS-B2229-SUB-4-6	7/27/2018	855.28	4 - 6 ft	180-80252-1	Excavated	0.3	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.15	0.15	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B223	SSHS-B223-SUB-2-4	7/28/2015	856.68	2 - 4 ft	180-46310-1	Excavated	0.717	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	0.43 J	0.24 J	0.047 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B223	SSHS-B223-SUB-4-6	7/28/2015	856.68	4 - 6 ft	180-46310-1	Excavated	5.1	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	3.7 J	1.3 J	0.1 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B223	SSHS-B223-SUB-6-8	7/28/2015	856.68	6 - 8 ft	180-46310-1	Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	< 0.0048 U	< 0.0046 U	< 0.0042 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-2-4	7/23/2018	856.03	2 - 4 ft	180-80091-4	Excavated	37.2	< 0.13 U	< 0.25 U	< 0.23 U	< 0.23 U	28	9.2		< 0.27 U	< 0.19 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-4-6	7/23/2018	856.03	4 - 6 ft	180-80091-4	Excavated	19.4	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	14	5.4		< 0.14 U	< 0.097 U
Football Field	SSHS-B2230	PS-FD-7	7/23/2018	856.03	6 - 8 ft	180-80091-4	Excavated	1.668	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.53	0.038	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-6-8	7/23/2018	856.03	6 - 8 ft	180-80091-4	Excavated	2.62	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.9	0.72		< 0.013 U	< 0.0093 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-8-10	7/23/2018	856.03	8 - 10 ft	180-80091-4	Not Excavated	6.43	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6	2.6	0.23	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-10-12	7/23/2018	856.03	10 - 12 ft	180-80091-4	Not Excavated	0.118	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.067	0.051	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	0.724	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.4	0.3	0.024	< 0.013 U	< 0.009 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-2-4	7/23/2018	856.14	2 - 4 ft	180-80091-2	Excavated	33.25	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	23	9.7	0.55	< 0.14 U	< 0.097 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-4-6	7/23/2018	856.14	4 - 6 ft	180-80091-2	Excavated	1.252	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.85	0.35	0.052	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-6-8	7/23/2018	856.14	6 - 8 ft	180-80091-2	Excavated	3.67	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	2.6	0.92	0.15	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-8-10	7/23/2018	856.14	8 - 10 ft	180-80091-2	Not Excavated	0.552	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.4	0.14	0.012 J,p	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-10-12	7/23/2018	856.14	10 - 12 ft	180-80091-2	Not Excavated	0.64	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.17		< 0.013 U	< 0.0092 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	1.47	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.37		< 0.013 U	< 0.009 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-2-4	7/24/2018	856.82	2 - 4 ft	180-80105-1	Excavated	9.21	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	5.2	3.7	0.31	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-4-6	7/24/2018	856.82	4 - 6 ft	180-80105-1	Excavated	0.413	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.27	0.12	0.023	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-6-8	7/24/2018	856.82	6 - 8 ft	180-80105-1	Not Excavated	0.249	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18	0.057	0.012 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-8-10	7/24/2018	856.82	8 - 10 ft	180-80105-1	Not Excavated	0.07	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.039	0.031	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2232	PS-FD-9	7/24/2018	856.82	10 - 12 ft	180-80105-2	Not Excavated	0.66	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.48	0.18	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-10-12	7/24/2018	856.82	10 - 12 ft	180-80105-1	Not Excavated	0.66	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.48	0.18	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	1.593	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.45	0.043	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2233	PS-FD-8	7/24/2018	854.83	2 - 4 ft	180-80105-2	Excavated	0.45	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.24	0.21	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-2-4	7/24/2018	854.83	2 - 4 ft	180-80105-1	Excavated	1.048	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.52	0.46	0.068	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-4-6	7/24/2018	854.83	4 - 6 ft	180-80105-1	Excavated	0.49	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.28	0.21	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-6-8	7/24/2018	854.83	6 - 8 ft	180-80105-1	Not Excavated	0.42	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.17	0.25	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-8-10	7/24/2018	854.83	8 - 10 ft	180-80105-1	Not Excavated	0.061	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.032	0.029	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-10-12	7/24/2018	854.83	10 - 12 ft	180-80105-1	Not Excavated	0.07	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	0.033	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	0.041	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.02	0.021	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-2-4	7/23/2018	855.41	2 - 4 ft	180-80091-1	Excavated	2.31	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2	1	0.11	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2234	PS-FD-5	7/23/2018	855.41	4 - 6 ft	180-80091-1	Excavated	0.233	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.14	0.093	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-4-6	7/23/2018	855.41	4 - 6 ft	180-80091-1	Excavated	0.29	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.17	0.12	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-6-8	7/23/2018	855.41	6 - 8 ft	180-80091-1	Excavated	0.052	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.031	0.021	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-8-10	7/23/2018	855.41	8 - 10 ft	180-80091-1	Not Excavated	0.65	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.46	0.19	< 0.0055 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-10-12	7/23/2018	855.41	10 - 12 ft	180-80091-2	Not Excavated	0.3	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.19	0.11	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	0.206	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.13	0.076	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-2-4	7/23/2018	855.30	2 - 4 ft	180-80091-1	Excavated	1.653	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.51	0.043	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-4-6	7/23/2018	855.30	4 - 6 ft	180-80091-1	Excavated	0.57	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.41	0.16	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-6-8	7/23/2018	855.30	6 - 8 ft	180-80091-1	Excavated	0.292	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.21	0.082	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2235	PS-FD-3	7/23/2018	855.30	8 - 10 ft	180-80091-1	Not Excavated	0.143	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.1	0.043	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-8-10	7/23/2018	855.30	8 - 10 ft	180-80091-1	Not Excavated	0.189	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13	0.059	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-10-12	7/23/2018	855.30	10 - 12 ft	180-80091-1	Not Excavated	0.13	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.09	0.04	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	0.133	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.091	0.042	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-2-4	7/27/2018	855.25	2 - 4 ft	180-80251-3	Excavated	2.86	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.9	0.85	0.11	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2236	PS-FD-52	7/27/2018	855.25	4 - 6 ft	180-80252-2	Excavated	6.6	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	4.9	1.4	0.3	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2236	SSHS-B2236-SUB-4-6	7/27/2018	855.25	4 - 6 ft	180-80251-3	Excavated	1.757	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.49	0.067	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-10-12	7/23/2018	855.07	10 - 12 ft	180-80091-1	Excavated	1562	< 3 U	< 6 U	< 5.5 U	< 5.6 U	1100	440	22	< 6.5 U	< 4.5 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	1395	< 3 U	< 5.9 U	< 5.4 U	< 5.4 U	1000	370	25	< 6.4 U	< 4.4 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-2-4	7/23/2018	855.51	2 - 4 ft	180-80091-3	Excavated	18.7	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	14	4.7		< 0.13 U	< 0.09 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-4-6	7/23/2018	855.51	4 - 6 ft	180-80091-3	Excavated	0.962	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.66	0.25	0.052	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-6-8	7/23/2018	855.51	6 - 8 ft	180-80091-3	Excavated	4.11	< 0.006 U,F1	< 0.012 U	< 0.011 U	< 0.011 U	2.8	1.1	0.21	< 0.013 U	< 0.009 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-8-10	7/23/2018	855.85	8 - 10 ft	180-80091-2	Excavated	0.558	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.4	0.14	0.018 J,p	< 0.013 U	< 0.009 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	0.056	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.042	0.014 J	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-8-10	7/23/2018	856.09	8 - 10 ft	180-80091-3	Excavated	32	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	24	8		< 0.14 U	< 0.095 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-10-12	7/23/2018	856.09	10 - 12 ft	180-80091-3	Excavated	0.831	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.56	0.22	0.051	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	39.4	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	30	9.4		< 0.26 U	< 0.18 U
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	4.24	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3.2	0.83	0.21	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-10-12	7/23/2018	856.09	10 - 12 ft	180-80091-3	Not Excavated	0.57	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.27	0.3		< 0.013 U	< 0.0091 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	0.51	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24	0.27		< 0.013 U	< 0.0089 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated	1.24	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.45	0.67	0.12	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-4-6	7/24/2018	855.25	4 - 6 ft	180-80106-1	Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-6-8	7/24/2018	855.25	6 - 8 ft	180-80106-1	Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-8-10	7/24/2018	855.25	8 - 10 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-10-12	7/24/2018	855.25	10 - 12 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated	3.46	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	2.1	1.2	0.16	< 0.014 U	< 0.0093 U
Football Field	SSHS-B225	CS-FD-#6	7/28/2015	855.94	2 - 4 ft	180-46310-1	Excavated	84.9	< 0.2 U	< 0.24 U	< 0.34 U	< 0.25 U	61 J	20 J	3.9 J	< 0.36 U	< 0.2 U
Football Field	SSHS-B225	SSHS-B225-SUB-2-4	7/28/2015	855.94	2 - 4 ft	180-46310-1	Excavated	79.4	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	56 J	19 J	4.4 J	< 0.36 U	< 0.19 U
Football Field	SSHS-B225	SSHS-B225-SUB-4-6	7/28/2015	855.94	4 - 6 ft	180-46310-1	Excavated	6.19	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	4.6 J	1.4 J	0.19 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B226	SSHS-B226-SUB-2-3	7/15/2015	856.35	2 - 3 ft	180-45961-1	Excavated	30.6	< 0.078 U	< 0.096 U	< 0.13 U	< 0.097 U	22 J	8.6 J	< 0.084 U	< 0.14 U	< 0.077 U
Football Field	SSHS-B227	SSHS-B227-SUB-2-4	7/15/2015	856.71	2 - 4 ft	180-45961-1	Excavated	4.66	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	3.1 J	1.4 J	0.16 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B227	SSHS-B227-SUB-4-6	7/15/2015	856.71	4 - 6 ft	180-45961-1	Excavated	123.4	< 0.38 U	< 0.47 U	< 0.65 U	< 0.48 U	120	< 0.45 U	3.4	< 0.69 U	< 0.38 U
Football Field	SSHS-B227	SSHS-B227-SUB-6-8	7/15/2015	856.71	6 - 8 ft	180-45961-1	Excavated	11.18	< 0.041 U	< 0.051 U	< 0.07 U	< 0.051 U	11	< 0.048 U	0.18 J	< 0.075 U	< 0.041 U
Football Field	SSHS-B227A	SSHS-B227A-SUB-8-10	7/28/2015	856.71	8 - 10 ft	180-46310-1	Not Excavated	5.62	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	4.2 J	1.3 J	0.12 J	< 0.0073 U	< 0.004 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B228	SSHS-B228-SUB-2-4	7/15/2015	856.95	2 - 4 ft	180-45961-1	Excavated	22.81	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	22	< 0.044 U	0.81	< 0.069 U	< 0.037 U
Football Field	SSHS-B228	SSHS-B228-SUB-4-6	7/15/2015	856.95	4 - 6 ft	180-45961-1	Excavated	35.71	< 0.076 U	< 0.093 U	< 0.13 U	< 0.094 U	35	< 0.089 U	0.71	< 0.14 U	< 0.075 U
Football Field	SSHS-B228	PS-FD-#2	7/15/2015	856.95	6 - 8 ft	180-45961-1	Excavated	0.23	< 0.004 U	< 0.005 U	< 0.0068 U	< 0.005 U	0.23	< 0.0047 UJ	< 0.0043 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B228	SSHS-B228-SUB-6-8	7/15/2015	856.95	6 - 8 ft	180-45961-1	Excavated	0.36	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.28 J	0.08 J	< 0.0043 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B229	SSHS-B229-SUB-2-4	7/15/2015	857.03	2 - 4 ft	180-45961-1	Excavated	117	< 0.39 U	< 0.48 U	< 0.67 U	< 0.49 U	82 J	35 J	< 0.42 U	< 0.71 U	< 0.39 U
Football Field	SSHS-B229	SSHS-B229-SUB-4-6	7/15/2015	857.03	4 - 6 ft	180-45961-1	Excavated	233	< 0.77 U,F1	< 0.95 U	< 1.3 U	< 0.95 U	170 J	63 J	< 0.83 U,F1	< 1.4 U	< 0.76 U
Football Field	SSHS-B229	SSHS-B229-SUB-6-8	7/15/2015	857.03	6 - 8 ft	180-45961-1	Excavated	0.194	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.15 J	0.044 J	< 0.0042 U	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B230	SSHS-B230-SUB-2-4	7/28/2015	857.08	2 - 4 ft	180-46310-1	Excavated	56.2	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	40 J	15 J	1.2 J	< 0.36 U	< 0.19 U
Football Field	SSHS-B230	SSHS-B230-SUB-4-6	7/28/2015	857.08	4 - 6 ft	180-46310-1	Excavated	28.04	< 0.038 U,F1	< 0.047 U	< 0.065 U	< 0.047 U	20 J	7.6 J	0.44 J	< 0.069 U	< 0.038 U
Football Field	SSHS-B230	CS-FD-#8	7/28/2015	857.08	6 - 8 ft	180-46310-1	Excavated	ND	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	< 0.0049 U	< 0.0046 U	< 0.0043 U	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B230	SSHS-B230-SUB-6-8	7/28/2015	857.08	6 - 8 ft	180-46310-1	Excavated	0.0215	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.012 J	0.0051 J	0.0044 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B2300	SSHS-B2300-SUB-2-4	8/29/2018	855.68	2 - 4 ft	180-81403-1	Excavated	6.589	< 0.0062 U,F2,F1	< 0.012 U	< 0.011 U	< 0.011 U	4.6	1.9	0.089	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2301	SSHS-B2301-SUB-2-4	8/28/2018	855.09	2 - 4 ft	180-81347-1	Excavated	4.33	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8	1.3	0.23	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2305	SSHS-B2305-SUB-2-4	8/29/2018	857.26	2 - 4 ft	180-81403-1	Excavated	17	< 0.031 U	< 0.063 U	< 0.057 U	< 0.058 U	8.7	7.7	0.6	< 0.068 U	< 0.047 U
Football Field	SSHS-B2306	SSHS-B2306-SUB-2-4	8/29/2018	857.17	2 - 4 ft	180-81403-1	Excavated	0.1419	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.089	0.043	0.0099 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2307	SSHS-B2307-SUB-2-4	8/29/2018	857.15	2 - 4 ft	180-81403-1	Excavated	0.686	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.36	0.3	0.026	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2309	SSHS-B2309-SUB-2-4	8/28/2018	856.61	2 - 4 ft	180-81347-1	Excavated	59.8	< 0.25 U	< 0.5 U	< 0.46 U	< 0.46 U	41	18	0.8	< 0.54 U	< 0.38 U
Football Field	SSHS-B2309	SSHS-B2309-SUB-4-6	8/28/2018	856.61	4 - 6 ft	180-81347-1	Excavated	0.093	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.071	0.022	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B231	CS-FD-#3	7/27/2015	856.10	2 - 4 ft	180-46300-1	Excavated	521	< 0.77 U	< 0.94 U	< 1.3 U	< 0.95 U	370 J	140 J	11 J	< 1.4 U	< 0.76 U
Football Field	SSHS-B231	SSHS-B231-SUB-2-4	7/27/2015	856.10	2 - 4 ft	180-46300-1	Excavated	631	< 0.77 U	< 0.95 U	< 1.3 U	< 0.96 U	460 J	160 J	11 J	< 1.4 U	< 0.76 U
Football Field	SSHS-B231	SSHS-B231-SUB-4-6	7/27/2015	856.10	4 - 6 ft	180-46300-1	Excavated	10.77	< 0.038 U,F1	< 0.047 U	< 0.065 U	< 0.048 U	8.1 J	2.4 J	0.27 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B231	CS-FD-#4	7/27/2015	856.10	6 - 8 ft	180-46300-1	Excavated	0.128	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.079 J	0.03 J	0.019 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B231	SSHS-B231-SUB-6-8	7/27/2015	856.10	6 - 8 ft	180-46300-1	Excavated	0.084	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.04 J	0.024 J	0.02 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B2310	SSHS-B2310-SUB-2-4	8/27/2018	856.81	2 - 4 ft	180-81330-1	Excavated	4.94	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	3	1.8	0.14	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2310	SSHS-B2310-SUB-4-6	8/27/2018	856.81	4 - 6 ft	180-81330-1	Excavated	7.59	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	5.1	2.3	0.19	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2314	SSHS-B2314-SUB-2-4	8/28/2018	854.73	2 - 4 ft	180-81347-1	Excavated	0.061	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.038	0.023	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2315	SSHS-B2315-SUB-2-4	8/29/2018	854.95	2 - 4 ft	180-81403-1	Excavated	7.48	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	4.7	2.4	0.38	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2316	SSHS-B2316-SUB-2-4	8/29/2018	855.71	2 - 4 ft	180-81403-1	Excavated	30.6	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	20	8.9	1.7	< 0.13 U	< 0.089 U
Football Field	SSHS-B2317	SSHS-B2317-SUB-2-4	8/29/2018	855.56	2 - 4 ft	180-81403-1	Excavated	5.95	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	3.1	2.3	0.55	< 0.014 U	< 0.0095 U
Football Field	SSHS-B232	SSHS-B232-SUB-2-4	7/27/2015	856.44	2 - 4 ft	180-46300-1	Excavated	102.5	< 0.19 U	< 0.23 U	< 0.32 U	< 0.24 U	70 J	29 J	3.5 J	< 0.35 U	< 0.19 U
Football Field	SSHS-B232	CS-FD-#2	7/27/2015	856.44	4 - 6 ft	180-46300-1	Excavated	0.005	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.005 J	< 0.0046 U	< 0.0042 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B232	SSHS-B232-SUB-4-6	7/27/2015	856.44	4 - 6 ft	180-46300-1	Excavated	0.0065	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	0.0065 J	< 0.0045 U	< 0.0041 U	< 0.007 U	< 0.0038 U
Football Field	SSHS-B232	SSHS-B232-SUB-6-8	7/27/2015	856.44	6 - 8 ft	180-46300-1	Not Excavated	0.0269	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.019 J	0.0079 J	< 0.0043 U	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B232	SSHS-B232-SUB-8-10	7/27/2015	856.44	8 - 10 ft	180-46300-1	Not Excavated	0.116	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U		0.096 J	0.02 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B2320	SSHS-B2320-SUB-2-4	8/29/2018	856.53	2 - 4 ft	180-81403-1	Excavated	9.37	< 0.03 U	< 0.061 U	< 0.055 U	< 0.056 U	6.7	2.5	0.17	< 0.066 U	< 0.045 U
Football Field	SSHS-B2321	SSHS-B2321-SUB-2-4	8/29/2018	856.67	2 - 4 ft	180-81403-1	Excavated	1.516	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.98	0.46	0.076	< 0.013 U	< 0.009 U
Football Field	SSHS-B2321	PS-FD-10	8/30/2018	856.67	2 - 4 ft	180-81525-1	Excavated	0.5193	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.4	0.11	0.0093 J,p	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2326	SSHS-B2326-SUB-2-4	8/29/2018	856.97	2 - 4 ft	180-81403-1	Excavated	31.41	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	23	7.7	0.71	< 0.13 U	< 0.091 U
Football Field	SSHS-B2329	SSHS-B2329-SUB-6-8	8/28/2018	856.92	6 - 8 ft	180-81347-1	Not Excavated	0.13	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.093	0.037	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B233	SSHS-B233-SUB-2-4	7/28/2015	856.93	2 - 4 ft	180-46310-1	Excavated	106.7	< 0.38 U	< 0.47 U	< 0.65 U	< 0.48 U	77 J	28 J	1.7 J	< 0.7 U	< 0.38 U
Football Field	SSHS-B233	CS-FD-#5	7/28/2015	856.93	4 - 6 ft	180-46310-1	Excavated	24.9	< 0.077 U	< 0.095 U	< 0.13 U	< 0.096 U	18 J	6.3 J	0.6 J	< 0.14 U	< 0.076 U
Football Field	SSHS-B233	SSHS-B233-SUB-4-6	7/28/2015	856.93	4 - 6 ft	180-46310-1	Excavated	36.1	< 0.078 U	< 0.096 U	< 0.13 U	< 0.097 U	26 J	9.4 J	0.7 J	< 0.14 U	< 0.077 U
Football Field	SSHS-B233	SSHS-B233-SUB-6-8	7/28/2015	856.93	6 - 8 ft	180-46310-1	Excavated	0.02	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	0.015 J	< 0.0048 U	0.005 J	< 0.0074 U	< 0.004 U
Football Field	SSHS-B233	SSHS-B233-SUB-8-10	7/28/2015	856.93	8 - 10 ft	180-46310-1	Not Excavated	5.81	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	4.3 J	1.4 J	0.11 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B2330	PS-FD-5	8/28/2018	856.50	4 - 6 ft	180-81347-1	Excavated	10.35	< 0.031 U	< 0.063 U	< 0.057 U	< 0.058 U	7.1	3.1	0.15	< 0.068 U	< 0.047 U
Football Field	SSHS-B2330	SSHS-B2330-SUB-4-6	8/28/2018	856.50	4 - 6 ft	180-81347-1	Excavated	7.94	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	5.6	2.2	0.14	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2331	SSHS-B2331-SUB-2-4	8/29/2018	856.68	2 - 4 ft	180-81403-1	Excavated	3.28	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2	1.1	0.18	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2333	SSHS-B2333-SUB-2-4	8/29/2018	856.57	2 - 4 ft	180-81403-1	Excavated	2.19	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	0.75	0.14	< 0.013 U	< 0.009 U
Football Field	SSHS-B2333	SSHS-B2333-SUB-4-6	8/29/2018	856.57	4 - 6 ft	180-81403-1	Excavated	2.03	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.7	0.13	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2334	SSHS-B2334-SUB-2-4	8/29/2018	856.31	2 - 4 ft	180-81403-1	Excavated	7.14	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	4.5	2.2	0.44	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2335	SSHS-B2335-SUB-2-4	8/29/2018	855.82	2 - 4 ft	180-81403-1	Excavated	11.87	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	7.6	3.6	0.67	< 0.065 U	< 0.045 U
Football Field	SSHS-B2336	SSHS-B2336-SUB-2-4	8/28/2018	856.32	2 - 4 ft	180-81347-1	Excavated	37.2	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	25	11	1.2	< 0.13 U	< 0.093 U
Football Field	SSHS-B2337	SSHS-B2337-SUB-2-4	8/29/2018	855.56	2 - 4 ft	180-81403-1	Excavated	6.81	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	4	2.2	0.61	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2338	SSHS-B2338-SUB-2-4	8/28/2018	855.87	2 - 4 ft	180-81347-1	Excavated	5.37	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	3.3	1.7	0.37	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2339	SSHS-B2339-SUB-2-4	8/28/2018	855.51	2 - 4 ft	180-81347-1	Excavated	2.69	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	1.6	0.92	0.17	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2340	SSHS-B2340-SUB-2-4	8/28/2018	856.24	2 - 4 ft	180-81347-1	Excavated	6.81	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	3.3	3	0.51	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2341	SSHS-B2341-SUB-2-4	8/30/2018	855.26	2 - 4 ft	180-81525-1	Excavated	2.12	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	1.4	0.6	0.12	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2341	SSHS-B2341-SUB-6-8	8/30/2018	855.26	6 - 8 ft	180-81525-1	Excavated	6.21	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	4.2	1.7	0.31	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2341	SSHS-B2341-SUB-8-10	8/30/2018	855.26	8 - 10 ft	180-81525-1	Excavated	3.05	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	2.1	0.81	0.14	< 0.014 U	< 0.01 U
Football Field	SSHS-B2343	SSHS-B2343-SUB-2-4	8/27/2018	855.24	2 - 4 ft	180-81330-1	Excavated	191	< 0.61 U	< 1.2 U	< 1.1 U	< 1.1 U	140	49	2	< 1.3 U	< 0.91 U
Football Field	SSHS-B2343	SSHS-B2343-SUB-4-6	8/27/2018	855.24	4 - 6 ft	180-81330-1	Excavated	5.12	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	3.2	1.8	0.12	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2344	SSHS-B2344-SUB-2-4	8/27/2018	854.98	2 - 4 ft	180-81330-1	Excavated	21.31	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	15	6	0.31	< 0.13 U	< 0.092 U
Football Field	SSHS-B2344	SSHS-B2344-SUB-4-6	8/27/2018	854.98	4 - 6 ft	180-81330-1	Excavated	0.064	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.044	0.02	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2346	PS-FD-6	8/28/2018	855.12	2 - 4 ft	180-81347-1	Excavated	99.6	< 0.3 U	< 0.61 U	< 0.56 U	< 0.56 U	79	19	1.6	< 0.66 U	< 0.45 U
Football Field	SSHS-B2346	SSHS-B2346-SUB-2-4	8/28/2018	855.12	2 - 4 ft	180-81347-1	Excavated	65.2	< 0.32 U	< 0.64 U	< 0.59 U	< 0.59 U	51	13	1.2	< 0.69 U	< 0.48 U
Football Field	SSHS-B234A	SSHS-B234A-SUB-2-4	7/28/2015	857.08	2 - 4 ft	180-46310-1	Excavated	0.85	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	0.39 J	0.35 J	0.11 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B234A	SSHS-B234A-SUB-4-6	7/28/2015	857.08	4 - 6 ft	180-46310-1	Excavated	60.4	< 0.19 U	< 0.24 U	< 0.33 U	< 0.24 U	42 J	17 J	1.4 J	< 0.35 U	< 0.19 U
Football Field	SSHS-B234A	SSHS-B234A-SUB-6-8	7/28/2015	857.08	6 - 8 ft	180-46310-1	Not Excavated	285.3	< 0.44 U	< 0.54 U	< 0.75 U	< 0.55 U	200 J	78 J	7.3 J	< 0.8 U	< 0.43 U
Football Field	SSHS-B2350	SSHS-B2350-SUB-2-4	8/27/2018	856.25	2 - 4 ft	180-81330-1	Excavated	94.6	< 0.25 U	< 0.51 U	< 0.46 U	< 0.47 U	66	27	1.6	< 0.55 U	< 0.38 U
Football Field	SSHS-B2352	SSHS-B2352-SUB-2-4	8/27/2018	855.74	2 - 4 ft	180-81330-1	Excavated	0.158	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.12	0.038	< 0.013 U	< 0.009 U
Football Field	SSHS-B2352	SSHS-B2352-SUB-4-6	8/27/2018	855.74	4 - 6 ft	180-81330-1	Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2353	SSHS-B2353-SUB-2-4	8/27/2018	855.66	2 - 4 ft	180-81330-1	Excavated	11.93	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	8.1	3.6	0.22	< 0.065 U	< 0.045 U
Football Field	SSHS-B2353	SSHS-B2353-SUB-4-6	8/27/2018	855.66	4 - 6 ft	180-81330-1	Excavated	0.042	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.024	0.018 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2354	SSHS-B2354-SUB-2-4	8/27/2018	855.52	2 - 4 ft	180-81330-1	Excavated	24.37	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	15	9.5	0.87	< 0.13 U	< 0.091 U
Football Field	SSHS-B2354	PS-FD-3	8/27/2018	855.52	4 - 6 ft	180-81330-1	Excavated	0.46	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.29	0.17	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2354	SSHS-B2354-SUB-4-6	8/27/2018	855.52	4 - 6 ft	180-81330-1	Excavated	0.55	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.35	0.2	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2356	SSHS-B2356-SUB-2-4	8/28/2018	856.24	2 - 4 ft	180-81347-1	Excavated	16.96	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	12	4.6	0.36	< 0.066 U	< 0.045 U
Football Field	SSHS-B2356	SSHS-B2356-SUB-4-6	8/28/2018	856.24	4 - 6 ft	180-81347-1	Excavated	6.75	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	4.7	1.9	0.15	< 0.014 U	< 0.0098 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2357	SSHS-B2357-SUB-2-4	8/28/2018	856.39	2 - 4 ft	180-81347-1	Excavated	14.56	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	11	3	0.56	< 0.14 U	< 0.098 U
Football Field	SSHS-B2358	SSHS-B2358-SUB-4-6	8/29/2018	855.79	4 - 6 ft	180-81403-1	Excavated	0.027	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.027	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2360	PS-FD-4	8/27/2018	855.86	2 - 4 ft	180-81330-1	Excavated	29.45	< 0.063 U	< 0.13 U	< 0.12 U	< 0.12 U	21	8.2	0.25	< 0.14 U	< 0.094 U
Football Field	SSHS-B2360	SSHS-B2360-SUB-2-4	8/27/2018	855.86	2 - 4 ft	180-81330-1	Excavated	18.6	< 0.062 U	< 0.12 U	< 0.11 U	< 0.12 U	13	5.4	0.2	< 0.13 U	< 0.093 U
Football Field	SSHS-B2360	SSHS-B2360-SUB-4-6	8/27/2018	855.86	4 - 6 ft	180-81330-1	Excavated	1.961	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	1.4	0.54	0.021	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2362	SSHS-B2362-SUB-4-6	8/28/2018	855.13	4 - 6 ft	180-81347-1	Not Excavated	22.07	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	18	3.7	0.37	< 0.14 U	< 0.094 U
Football Field	SSHS-B2367	SSHS-B2367-SUB-6-8	8/29/2018	856.08	6 - 8 ft	180-81403-1	Excavated	0.128	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.089	0.039	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2368	SSHS-B2368-SUB-6-8	8/29/2018	856.48	6 - 8 ft	180-81403-1	Not Excavated	0.069	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	0.046	0.023	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2369	SSHS-B2369-SUB-6-8	8/29/2018	856.80	6 - 8 ft	180-81403-1	Not Excavated	0.68	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.49	0.19	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B237	SSHS-B237-SUB-2-4	7/27/2015	857.09	2 - 4 ft	180-46300-1	Excavated	2.777	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	1.9 J	0.79 J	0.087 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B2385	SSHS-B2385-SUB-2-4	8/30/2018	855.00	2 - 4 ft	180-81525-1	Not Excavated	0.466	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.38	0.086	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2386	SSHS-B2386-SUB-2-4	8/30/2018	855.18	2 - 4 ft	180-81525-1	Not Excavated	7.45	< 0.032 U	< 0.063 U	< 0.058 U	< 0.058 U	5.3	1.8	0.35	< 0.068 U	< 0.047 U
Football Field	SSHS-B239A	SSHS-B239A-SUB-2-4	7/27/2015	856.99	2 - 4 ft	180-46300-1	Excavated	165	< 0.2 U	< 0.24 U	< 0.33 U	< 0.24 U	120 J	45 J		< 0.36 U	< 0.19 U
Football Field	SSHS-B239A	SSHS-B239A-SUB-4-6	7/27/2015	856.99	4 - 6 ft	180-46300-2	Excavated	4.14						3.3 J	0.84 J		
Football Field	SSHS-B240	SSHS-B240-SUB-2-4	7/27/2015	857.39	2 - 4 ft	180-46300-1	Excavated	12.35	< 0.019 U	< 0.024 U	< 0.033 U	< 0.024 U	7.5 J	4.2 J	0.65 J	< 0.035 U	< 0.019 U
Football Field	SSHS-B2411	SSHS-B2411-SUB-6-8	8/27/2018	855.01	6 - 8 ft	180-81330-1	Excavated	0.257	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18	0.077	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2411	SSHS-B2411-SUB-8-10	8/27/2018	855.01	8 - 10 ft	180-81330-1	Excavated	0.73	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.51	0.22	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B242	SSHS-B242-SUB-2-4	7/27/2015	857.07	2 - 4 ft	180-46300-1	Excavated	290.1	< 0.4 U	< 0.49 U	< 0.67 U	< 0.49 U	210 J	73 J	7.1 J	< 0.72 U	< 0.39 U
Football Field	SSHS-B246	SSHS-B246-SUB-2-4	7/30/2015	856.12	2 - 4 ft	180-46426-1	Excavated	0.126	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	0.065 J	0.049 J	0.012 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B248	SSHS-B248-SUB-2-4	7/20/2015	856.87	2 - 4 ft	180-46075-1	Excavated	0.261	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.14 J	0.1 J	0.021 J	< 0.0069 U	< 0.0037 U
Football Field	SSHS-B248	SSHS-B248-SUB-4-6	7/20/2015	856.87	4 - 6 ft	180-46075-1	Excavated	5.5	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	3.2 J	1.8 J	0.5 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B248	SSHS-B248-SUB-6-8	7/20/2015	856.87	6 - 8 ft	180-46075-1	Excavated	0.915	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.085 J	0.25 J	0.58 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B248A	PS-FD-3	7/11/2017	856.87	4 - 6 ft	180-68095-1	Excavated	6.23	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	4.1	1.9	0.23	< 0.013 U	< 0.0056 U
Football Field	SSHS-B248A	SSHS-B248A-SUB-4-6	7/11/2017	856.87	4 - 6 ft	180-68095-1	Excavated	6.95	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	4.6	2.1	0.25	< 0.013 U	< 0.0057 U
Football Field	SSHS-B249	CS-FD-#14	7/30/2015	856.83	2 - 4 ft	180-46426-1	Excavated	0.343	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.17 J	0.14 J	0.033 J	< 0.0069 U	< 0.0037 U
Football Field	SSHS-B249	SSHS-B249-SUB-2-4	7/30/2015	856.83	2 - 4 ft	180-46426-1	Excavated	0.487	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.28 J	0.17 J	0.037 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B250	SSHS-B250-SUB-2-4	7/30/2015	856.50	2 - 4 ft	180-46426-1	Excavated	14.94	< 0.018 U	< 0.022 U	< 0.03 U	< 0.022 U	9.8 J	4.4 J	0.74 J	< 0.033 U	< 0.018 U
Football Field	SSHS-B2507	SSHS-B2507-SUB-2-4	10/31/2018	857.07	2 - 4 ft	180-83573-1	Excavated	1.127	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.43 J	0.61 J	0.087 J	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2508	PS-FD-5	10/31/2018	857.23	2 - 4 ft	180-83573-1	Excavated	23.35	< 0.031 U	< 0.061 U	< 0.056 U	< 0.056 U	16 J	7 J	0.35 J	< 0.066 U	< 0.046 U
Football Field	SSHS-B2508	SSHS-B2508-SUB-2-4	10/31/2018	857.23	2 - 4 ft	180-83573-1	Excavated	13.89	< 0.031 U	< 0.062 U	< 0.056 U	< 0.057 U	9.3 J	4.3 J	0.29 J	< 0.067 U	< 0.046 U
Football Field	SSHS-B2509	SSHS-B2509-SUB-2-4	10/31/2018	857.13	2 - 4 ft	180-83573-1	Excavated	1.216	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.63 J	0.51 J	0.076 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B251	SSHS-B251-SUB-2-3	7/20/2015	856.76	2 - 3 ft	180-46075-1	Excavated	8.35	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	6 J	2 J	0.35 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B2510	SSHS-B2510-SUB-2-4	10/31/2018	857.09	2 - 4 ft	180-83573-1	Excavated	1.367	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.74 J	0.56 J	0.067 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2511	SSHS-B2511-SUB-2-4	10/31/2018	855.29	2 - 4 ft	180-83573-1	Excavated	1.761	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2 J	0.51 J	0.051 J	< 0.013 U	< 0.009 U
Football Field	SSHS-B2512	SSHS-B2512-SUB-2-4	10/31/2018	854.87	2 - 4 ft	180-83573-1	Excavated	1.45	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.6 J	0.75 J	0.1 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2513	PS-FD-1	10/29/2018	855.10	4 - 6 ft	180-83541-1	Excavated	1.032	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.71 J	0.24 J	0.082 J	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2513	SSHS-B2513-SUB-4-6	10/29/2018	855.10	4 - 6 ft	180-83541-1	Excavated	0.524	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.37 J	0.12 J	0.034 J	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2514	SSHS-B2514-SUB-2-4	10/31/2018	855.32	2 - 4 ft	180-83573-1	Excavated	0.634	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.35 J	0.25 J	0.034 J	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2515	SSHS-B2515-SUB-2-4	10/31/2018	855.58	2 - 4 ft	180-83573-1	Excavated	97.7	< 0.25 U	< 0.5 U	< 0.46 U	< 0.46 U	70 J	26 J	1.7 J	< 0.54 U	< 0.37 U
Football Field	SSHS-B2516	SSHS-B2516-SUB-2-4	10/31/2018	855.89	2 - 4 ft	180-83573-1	Excavated	5.36	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.5 J	1.7 J	0.16 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2517	SSHS-B2517-SUB-2-4	10/31/2018	855.67	2 - 4 ft	180-83573-1	Excavated	2.81	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	1.3 J	0.21 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2518	SSHS-B2518-SUB-2-4	10/31/2018	856.30	2 - 4 ft	180-83573-1	Excavated	0.224	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.078 J	0.11 J	0.036 J	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2519	SSHS-B2519-SUB-2-4	10/30/2018	854.99	2 - 4 ft	180-83544-1	Excavated	48.1	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	33 J	14 J	1.1 J	< 0.26 U	< 0.18 U
Football Field	SSHS-B252	SSHS-B252-SUB-2-4	7/20/2015	856.86	2 - 4 ft	180-46075-1	Excavated	0.118	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	0.059 J	0.047 J	0.012 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B252	SSHS-B252-SUB-4-6	7/20/2015	856.86	4 - 6 ft	180-46075-1	Excavated	0.732	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	0.42 J	0.26 J	0.052 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B252	SSHS-B252-SUB-6-8	7/20/2015	856.86	6 - 8 ft	180-46075-1	Excavated	ND	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	< 0.0044 U	< 0.0042 U	< 0.0039 U	< 0.0065 U	< 0.0035 U
Football Field	SSHS-B2520	SSHS-B2520-SUB-2-4	10/29/2018	854.94	2 - 4 ft	180-83541-1	Excavated	0.282	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.18 J	0.082 J	0.02 J	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2521	SSHS-B2521-SUB-2-4	10/29/2018	855.39	2 - 4 ft	180-83541-1	Excavated	1.31	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.61 J	0.53 J	0.17 J	< 0.013 U	< 0.009 U
Football Field	SSHS-B2522	PS-FD-2	10/29/2018	855.42	2 - 4 ft	180-83541-1	Excavated	0.78	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.53 J	0.2 J	0.05 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2522	SSHS-B2522-SUB-2-4	10/29/2018	855.42	2 - 4 ft	180-83541-1	Excavated	0.508	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.35 J	0.13 J	0.028 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2522	SSHS-B2522-SUB-4-6	10/29/2018	855.42	4 - 6 ft	180-83541-1	Excavated	0.845	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.63 J	0.18 J	0.035 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2523	SSHS-B2523-SUB-2-4	10/29/2018	855.03	2 - 4 ft	180-83541-1	Excavated	2.41	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	0.85 J	0.26 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2523	SSHS-B2523-SUB-4-6	10/29/2018	855.03	4 - 6 ft	180-83541-1	Not Excavated	0.073	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051 J	0.022 J	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2524	SSHS-B2524-SUB-2-4	10/29/2018	855.20	2 - 4 ft	180-83541-1	Excavated	0.797	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.5 J	0.23 J	0.067 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2525	SSHS-B2525-SUB-4-6	10/31/2018	856.41	4 - 6 ft	180-83573-1	Excavated	1.078	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.43 J	0.55 J	0.098 J	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2526	PS-FD-6	10/31/2018	856.84	4 - 6 ft	180-83573-1	Excavated	0.348	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.14 J	0.18 J	0.028 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2526	SSHS-B2526-SUB-4-6	10/31/2018	856.84	4 - 6 ft	180-83573-1	Excavated	3.82	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	2.6 J	1.1 J	0.12 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2527	SSHS-B2527-SUB-6-8	10/30/2018	855.17	6 - 8 ft	180-83544-1	Excavated	0.903	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.56 J	0.31 J	0.033 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2527	SSHS-B2527-SUB-8-10	10/30/2018	855.17	8 - 10 ft	180-83544-1	Excavated	0.752	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.48 J	0.25 J	0.022 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2527	SSHS-B2527-SUB-10-12	10/30/2018	855.17	10 - 12 ft	180-83544-1	Excavated	0.591	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.43 J	0.15 J	0.011 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2527	SSHS-B2527-SUB-12-14	10/30/2018	855.17	12 - 14 ft	180-83544-1	Excavated	1.245	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.83 J	0.38 J	0.035 J	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2527	SSHS-B2527-SUB-14-16	10/30/2018	855.17	14 - 16 ft	180-83544-1	Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2529	SSHS-B2529-SUB-4-6	10/29/2018	855.04	4 - 6 ft	180-83541-1	Excavated	10.64	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	7.6 J	2.4 J	0.64 J	< 0.067 U	< 0.046 U
Football Field	SSHS-B253	SSHS-B253-SUB-2-4	7/30/2015	856.85	2 - 4 ft	180-46426-1	Excavated	0.128	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.046 J	0.063 J	0.019 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B2530	SSHS-B2530-SUB-4-6	10/29/2018	855.06	4 - 6 ft	180-83541-1	Excavated	2.86	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.9 J	0.69 J	0.27 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-2-4	10/29/2018	855.29	2 - 4 ft	180-83541-1	Excavated	0.096	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.078 J	0.018 J	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-4-6	10/29/2018	855.29	4 - 6 ft	180-83541-1	Excavated	0.04	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.04	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-6-8	10/29/2018	855.29	6 - 8 ft	180-83541-1	Excavated	0.198	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.16 J	0.038 J	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-8-10	10/29/2018	855.29	8 - 10 ft	180-83541-1	Excavated	0.136	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11 J	0.026 J	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-10-12	10/29/2018	855.29	10 - 12 ft	180-83541-1	Excavated	0.021	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.021	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-14-16	10/29/2018	855.29	14 - 16 ft	180-83541-1	Not Excavated	0.015	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.015 J	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2533	SSHS-B2533-SUB-10-12	10/30/2018	855.10	10 - 12 ft	180-83544-1	Excavated	0.073	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.04 J	0.033 J	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2533	SSHS-B2533-SUB-12-14	10/30/2018	855.10	12 - 14 ft	180-83544-1	Excavated	0.0733	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037 J	0.031 J	0.0053 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2533	SSHS-B2533-SUB-14-16	10/30/2018	855.10	14 - 16 ft	180-83544-1	Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2534	SSHS-B2534-SUB-10-12	10/30/2018	855.61	10 - 12 ft	180-83544-1	Excavated	1.287	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.58 J	0.61 J	0.097 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2534	SSHS-B2534-SUB-12-14	10/30/2018	855.61	12 - 14 ft	180-83544-1	Not Excavated	0.458	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.2 J	0.22 J	0.038 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2534	SSHS-B2534-SUB-14-16	10/30/2018	855.61	14 - 16 ft	180-83544-1	Not Excavated	0.126	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051 J	0.062 J	0.013 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2535	SSHS-B2535-SUB-10-12	10/30/2018	854.97	10 - 12 ft	180-83544-1	Excavated	2.702	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.8 J	0.83 J	0.072 J	< 0.013 U	< 0.0089 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2535	SSHS-B2535-SUB-12-14	10/30/2018	854.97	12 - 14 ft	180-83544-1	Excavated	0.1111	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.067 J	0.037 J	0.0071 J	< 0.013 U	< 0.009 U
Football Field	SSHS-B2535	SSHS-B2535-SUB-14-16	10/30/2018	854.97	14 - 16 ft	180-83544-1	Not Excavated	0.2334	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.16 J	0.066 J	0.0074 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2536	PS-FD-3	10/30/2018	855.12	12 - 14 ft	180-83544-1	Excavated	4.197	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.7 J	1.4 J	0.097 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2536	SSHS-B2536-SUB-12-14	10/30/2018	855.12	12 - 14 ft	180-83544-1	Excavated	6.16	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	3.8 J	2.2 J	0.16 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2539	SSHS-B2539-SUB-2-4	10/31/2018	854.77	2 - 4 ft	180-83573-1	Excavated	7.39	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	4.6 J	2.5 J	0.29 J	< 0.014 U	< 0.0096 U
Football Field	SSHS-B254	SSHS-B254-SUB-2-4	7/30/2015	856.06	2 - 4 ft	180-46426-1	Excavated	6.91	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	4.7 J	1.9 J	0.31 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B2540	SSHS-B2540-SUB-2-4	10/30/2018	854.91	2 - 4 ft	180-83544-1	Excavated	10.8	< 0.031 U	< 0.063 U	< 0.057 U	< 0.058 U	7.7 J	3.1 J		< 0.068 U	< 0.047 U
Football Field	SSHS-B255	SSHS-B255-SUB-2-4	7/30/2015	856.67	2 - 4 ft	180-46426-1	Excavated	0.0478	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	0.0088 J	0.024 J	0.015 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B255	SSHS-B255-SUB-4-6	7/30/2015	856.67	4 - 6 ft	180-46426-1	Excavated	0.297	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.18 J	0.098 J	0.019 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B255	SSHS-B255-SUB-6-8	7/30/2015	856.67	6 - 8 ft	180-46426-1	Excavated	0.005	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	0.005 J	< 0.0042 U	< 0.0039 U	< 0.0065 U	< 0.0036 U
Football Field	SSHS-B255A	SSHS-B255A-SUB-4-6	7/12/2017	856.67	4 - 6 ft	180-68139-1	Excavated	0.07	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.049	0.021	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B255A	SSHS-B255A-SUB-6-8	7/12/2017	856.67	6 - 8 ft	180-68139-1	Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B256	SSHS-B256-SUB-2-4	7/20/2015	856.85	2 - 4 ft	180-46075-1	Excavated	1.218	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	0.81 J	0.36 J	0.048 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B256	SSHS-B256-SUB-4-6	7/20/2015	856.85	4 - 6 ft	180-46075-1	Excavated	90.4	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	63 J	25 J	2.4 J	< 0.34 U	< 0.19 U
Football Field	SSHS-B256	SSHS-B256-SUB-6-8	7/20/2015	856.85	6 - 8 ft	180-46075-1	Excavated	0.0863	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0044 U	0.053 J	0.026 J	0.0073 J	< 0.0065 U	< 0.0035 U
Football Field	SSHS-B257	SSHS-B257-SUB-2-4	7/30/2015	856.92	2 - 4 ft	180-46426-1	Excavated	8.58	< 0.019 U,F1	< 0.023 U	< 0.032 U	< 0.023 U	8 J	< 0.022 U	0.58 J	< 0.034 U	< 0.019 U
Football Field	SSHS-B257	SSHS-B257-SUB-4-6	7/30/2015	856.92	4 - 6 ft	180-46426-1	Excavated	59.1	< 0.077 U	< 0.094 U	< 0.13 U	< 0.095 U	38 J	18 J	3.1 J	< 0.14 U	< 0.076 U
Football Field	SSHS-B257	SSHS-B257-SUB-6-8	7/30/2015	856.92	6 - 8 ft	180-46426-1	Excavated	25.3	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	16 J	8 J	1.3 J	< 0.068 U	< 0.037 U
Football Field	SSHS-B257	SSHS-B257-SUB-8-10	7/30/2015	856.92	8 - 10 ft	180-46426-2	Excavated	5.47	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	5 J		0.47 J	< 0.0067 U	< 0.0036 U
Football Field	SSHS-B259	SSHS-B259-SUB-2-4	7/29/2015	855.79	2 - 4 ft	180-46367-1	Excavated	44.1	< 0.08 U	< 0.098 U	< 0.13 U	< 0.099 U	35 J	7.7 J	1.4 J	< 0.14 U	< 0.079 U
Football Field	SSHS-B260	SSHS-B260-SUB-2-4	7/29/2015	856.02	2 - 4 ft	180-46367-1	Excavated	62.9	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	44 J	17 J	1.9 J	< 0.34 U	< 0.18 U
Football Field	SSHS-B260	SSHS-B260-SUB-4-6	7/29/2015	856.02	4 - 6 ft	180-46367-1	Excavated	98.8	< 0.38 U	< 0.47 U	< 0.65 U	< 0.47 U	83 J	12 J	3.8 J	< 0.69 U	< 0.38 U
Football Field	SSHS-B260	SSHS-B260-SUB-6-8	7/29/2015	856.02	6 - 8 ft	180-46367-1	Excavated	1167	< 0.81 U	< 0.99 U	< 1.4 U	< 1 U	1000 J	130 J	37 J	< 1.5 U	< 0.8 U
Football Field	SSHS-B2600	SSHS-B2600-SUB-2-4	5/17/2019	856.75	2 - 4 ft	180-90275-1	Excavated	1	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.42 J	0.48 J	0.1 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2602	PS-FD-20	5/17/2019	857.05	2 - 4 ft	180-90275-1	Excavated	34.23	< 0.13 U	< 0.14 U	< 0.098 U	< 0.059 U	25 J	8.3 J	0.93 J	< 0.14 U	< 0.054 U
Football Field	SSHS-B2602	SSHS-B2602-SUB-2-4	5/17/2019	857.05	2 - 4 ft	180-90275-1	Excavated	41.68	< 0.32 U	< 0.35 U	< 0.24 U	< 0.15 U	31 J	9.8 J	0.88 J	< 0.35 U	< 0.13 U
Football Field	SSHS-B2607	SSHS-B2607-SUB-4-6	5/15/2019	855.83	4 - 6 ft	180-90165-1	Excavated	2.8	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.7 J	0.75 J	0.35 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2608	PS-FD-25	5/19/2019	855.35	2 - 4 ft	180-90323-1	Excavated	0.132	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.079 J	0.053 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2608	SSHS-B2608-SUB-2-4	5/19/2019	855.35	2 - 4 ft	180-90323-1	Excavated	0.138	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.091 J	0.047 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2609	SSHS-B2609-SUB-2-4	5/18/2019	854.74	2 - 4 ft	180-90319-1	Excavated	129.5	< 0.25 U	< 0.28 U	< 0.19 U	< 0.11 U	100 J	23 J	6.5 J	< 0.27 U	< 0.1 U
Football Field	SSHS-B261	SSHS-B261-SUB-2-4	7/17/2015	855.83	2 - 4 ft	180-46045-1	Excavated	33.6	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	23 J	9.3 J	1.3 J	< 0.068 U	< 0.037 U
Football Field	SSHS-B261	SSHS-B261-SUB-4-6	7/17/2015	855.83	4 - 6 ft	180-46045-1	Excavated	5.09	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	3.6 J	1.3 J	0.19 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B261	SSHS-B261-SUB-6-8	7/17/2015	855.83	6 - 8 ft	180-46045-1	Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	< 0.0048 U	< 0.0046 U	< 0.0042 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B2610	SSHS-B2610-SUB-2-4	5/20/2019	857.15	2 - 4 ft	180-90324-1	Excavated	0.651	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.34 J	0.24 J	0.071 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2611	SSHS-B2611-SUB-2-4	5/20/2019	857.20	2 - 4 ft	180-90324-1	Excavated	0.86	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.44 J	0.29 J	0.13 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2612	SSHS-B2612-SUB-2-4	5/15/2019	855.13	2 - 4 ft	180-90165-1	Excavated	38.8	< 0.065 U	< 0.07 U	< 0.048 U	< 0.029 U	24 J	10 J	4.8 J	< 0.07 U	< 0.027 U
Football Field	SSHS-B2613	PS-FD-10	5/15/2019	855.07	6 - 8 ft	180-90165-1	Excavated	2.39	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.7 J	0.48 J	0.21 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2613	SSHS-B2613-SUB-6-8	5/15/2019	855.07	6 - 8 ft	180-90165-1	Excavated	1.82	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.2 J	0.43 J	0.19 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2614	SSHS-B2614-SUB-2-4	5/15/2019	855.06	2 - 4 ft	180-90165-1	Excavated	2.04	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	1.4 J	0.48 J	0.16 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-2-4	5/15/2019	855.13	2 - 4 ft	180-90165-1	Excavated	1.98	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.3 J	0.49 J	0.19 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2617	SSHS-B2617-SUB-2-4	5/15/2019	855.78	2 - 4 ft	180-90165-1	Excavated	0.91	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.56 J	0.25 J	0.1 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2618	PS-FD-18	5/17/2019	855.12	2 - 4 ft	180-90275-1	Excavated	17.3	< 0.061 U	< 0.067 U	< 0.046 U	< 0.028 U	12 J	4.2 J	1.1 J	< 0.066 U	< 0.025 U
Football Field	SSHS-B2618	SSHS-B2618-SUB-2-4	5/17/2019	855.12	2 - 4 ft	180-90275-1	Excavated	12.95	< 0.06 U	< 0.066 U	< 0.045 U	< 0.027 U	9 J	3.2 J	0.75 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B2618	SSHS-B2618-SUB-4-6	5/17/2019	855.12	4 - 6 ft	180-90275-1	Excavated	17.5	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	12 J	4.3 J	1.2 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B2619	SSHS-B2619-SUB-6-8	5/16/2019	855.10	6 - 8 ft	180-90231-1	Not Excavated	9.83	< 0.032 U	< 0.034 U	< 0.024 U	< 0.014 U	6.7 J	2.3 J	0.83 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B262	SSHS-B262-SUB-2-4	7/29/2015	855.62	2 - 4 ft	180-46367-1	Excavated	20.64	< 0.079 U	< 0.097 U	< 0.13 U	< 0.098 U	18 J	2.1 J	0.54 J	< 0.14 U	< 0.078 U
Football Field	SSHS-B262	CS-FD-#9	7/29/2015	855.62	4 - 6 ft	180-46367-1	Excavated	2.878	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0049 U	2 J	0.81 J	0.068 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B262	SSHS-B262-SUB-4-6	7/29/2015	855.62	4 - 6 ft	180-46367-1	Excavated	3.679	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	2.6 J	1 J	0.079 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B262	SSHS-B262-SUB-6-8	7/29/2015	855.62	6 - 8 ft	180-46367-1	Excavated	0.0237	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.016 J	0.0077 J	< 0.004 U	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B2620	PS-FD-17	5/16/2019	855.02	6 - 8 ft	180-90231-1	Not Excavated	8.06	< 0.03 U	< 0.033 UJ	< 0.023 U	< 0.014 U	6.1 J	1.5 J	0.46 J	< 0.033 U	< 0.012 UJ
Football Field	SSHS-B2620	SSHS-B2620-SUB-6-8	5/16/2019	855.02	6 - 8 ft	180-90231-1	Not Excavated	4.48	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.1 J	1 J	0.38 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-2-4	5/15/2019	855.04	2 - 4 ft	180-90165-2	Excavated	23.6	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	15 J	5.8 J	2.8 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-4-6	5/15/2019	855.04	4 - 6 ft	180-90165-1	Excavated	12.8	< 0.029 U	< 0.032 U	< 0.022 U	< 0.013 U	7.6 J	3.6 J	1.6 J	< 0.031 U	< 0.012 U
Football Field	SSHS-B2625	SSHS-B2625-SUB-2-4	5/16/2019	855.18	2 - 4 ft	180-90231-1	Excavated	5.62	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	3.5 J	1.6 J	0.52 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2625	PS-FD-14	5/16/2019	855.18	4 - 6 ft	180-90231-1	Excavated	0.237	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.17 J	0.067 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2625	SSHS-B2625-SUB-4-6	5/16/2019	855.18	4 - 6 ft	180-90231-1	Excavated	0.188	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.14 J	0.048 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2626	SSHS-B2626-SUB-4-6	5/17/2019	856.93	4 - 6 ft	180-90275-1	Excavated	0.044	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.028 J	0.016 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2627	SSHS-B2627-SUB-2-4	5/18/2019	854.90	2 - 4 ft	180-90319-1	Excavated	1.28	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.99 J	0.23 J	0.06 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-2-4	4/25/2019	855.32	2 - 4 ft	180-89522-1	Excavated	1.068	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.76 J	0.24 J	0.068 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2629	PS-FD-12	4/25/2019	855.32	4 - 6 ft	180-89522-1	Excavated	2.64	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2 J	0.49 J	0.15 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-4-6	4/25/2019	855.32	4 - 6 ft	180-89522-1	Excavated	4.67	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.5 J	0.89 J	0.28 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2629	PS-FD-9	4/25/2019	855.32	6 - 8 ft	180-89522-1	Excavated	0.116	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.083 J	0.033 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-6-8	4/25/2019	855.32	6 - 8 ft	180-89522-1	Excavated	7.23	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	5.2 J	1.5 J	0.53 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-8-10	4/25/2019	855.32	8 - 10 ft	180-89522-1	Excavated	2.47	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.8 J	0.51 J	0.16 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-10-12	4/25/2019	855.32	10 - 12 ft	180-89522-1	Excavated	13.66	< 0.029 U	< 0.032 U	< 0.022 U	< 0.013 U	9.4 J	3.3 J	0.96 J	< 0.031 U	< 0.012 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-14-16	4/25/2019	855.32	14 - 16 ft	180-89522-1	Not Excavated	4.05	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.9 J	0.86 J	0.29 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-12-14	5/20/2019	854.95	12 - 14 ft	180-90324-1	Excavated	1.43	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.1 J	0.27 J	0.06 J	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B2634	SSHS-B2634-SUB-6-8	4/24/2019	855.37	6 - 8 ft	180-89408-2	Excavated	20.64	< 0.06 U	< 0.066 U	< 0.045 U	< 0.027 U	15 J	4.7 J	0.94 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B2634	PS-FD-5	4/24/2019	855.37	12 - 14 ft	180-89408-1	Excavated	12.06	< 0.03 U	< 0.032 U	< 0.022 U	< 0.013 U	9.2 J	2.4 J	0.46 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B2634	SSHS-B2634-SUB-12-14	4/24/2019	855.37	12 - 14 ft	180-89408-1	Excavated	6.33	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	4.8 J	1.3 J	0.23 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2636	SSHS-B2636-SUB-2-4	5/15/2019	855.13	2 - 4 ft	180-90165-1	Excavated	12.7	< 0.029 U	< 0.032 U	< 0.022 U	< 0.013 U	8.6 J	3 J	1.1 J	< 0.031 U	< 0.012 U
Football Field	SSHS-B2637	SSHS-B2637-SUB-2-4	4/24/2019	855.39	2 - 4 ft	180-89408-1	Excavated	22.43	< 0.059 U	< 0.065 U	< 0.045 U	< 0.027 U	16 J	5.5 J	0.93 J	< 0.064 U	< 0.025 U
Football Field	SSHS-B2637	SSHS-B2637-SUB-4-6	4/24/2019	855.39	4 - 6 ft	180-89408-2	Excavated	120.4	< 0.6 U	< 0.65 U	< 0.45 U	< 0.27 U	88 J	28 J	4.4 J	< 0.65 U	< 0.25 U
Football Field	SSHS-B2637	PS-FD-6	4/24/2019	855.39	8 - 10 ft	180-89408-2	Excavated	21.3	< 0.059 U	< 0.064 U	< 0.044 U	< 0.026 U	15 J	5.1 J	1.2 J	< 0.063 U	< 0.024 U
Football Field	SSHS-B2637	SSHS-B2637-SUB-8-10	4/24/2019	855.39	8 - 10 ft	180-89408-2	Excavated	37.3	< 0.12 U	< 0.13 U	< 0.086 U	< 0.052 U	27 J	8.4 J	1.9 J	< 0.12 U	< 0.048 U
Football Field	SSHS-B2637	SSHS-B2637-SUB-12-14	4/24/2019	855.39	12 - 14 ft	180-89408-1	Excavated	12.56	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	9 J	2.9 J	0.66 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B2639	SSHS-B2639-SUB-2-4	5/19/2019	855.11	2 - 4 ft	180-90323-1	Not Excavated	23.2	< 0.031 U	< 0.033 U	< 0.023 U	< 0.014 U	18 J	4 J	1.2 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B264	SSHS-B264-SUB-2-3	7/17/2015	855.93	2 - 3 ft	180-46045-1	Excavated	23.15	< 0.036 U	< 0.044 U	< 0.061 U	< 0.045 U	15 J	7.3 J	0.85 J	< 0.065 U	< 0.036 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2642	SSHS-B2642-SUB-2-4	5/19/2019	855.14	2 - 4 ft	180-90323-1	Not Excavated	6.01	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	4.6 J	1.1 J	0.31 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2643	SSHS-B2643-SUB-2-4	5/19/2019	854.91	2 - 4 ft	180-90323-1	Not Excavated	0.61	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.09 J	0.35 J	0.17 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2644	SSHS-B2644-SUB-2-4	5/22/2019	856.70	2 - 4 ft	180-90524-1	Excavated	5.03	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	3.7 J	1 J	0.33 J	< 0.0078 U	< 0.003 U
Football Field	SSHS-B2645	SSHS-B2645-SUB-2-4	5/21/2019	855.03	2 - 4 ft	180-90380-1	Excavated	0.09	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U		0.07 J	0.02 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2646	SSHS-B2646-SUB-2-4	5/19/2019	854.76	2 - 4 ft	180-90323-1	Excavated	27.1	< 0.13 U	< 0.14 U	< 0.094 U	< 0.057 U	20 J	5.4 J	1.7 J	< 0.14 U	< 0.052 U
Football Field	SSHS-B2648	SSHS-B2648-SUB-4-6	5/16/2019	855.86	4 - 6 ft	180-90231-1	Excavated	0.53	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.41 J	0.12 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2648	SSHS-B2648-SUB-6-8	5/16/2019	855.86	6 - 8 ft	180-90231-1	Not Excavated	0.495	< 0.0067 U	< 0.0073 U	0.23 J	< 0.003 U	0.21 J	0.055 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2649	SSHS-B2649-SUB-2-4	5/17/2019	856.28	2 - 4 ft	180-90275-2	Excavated	35.4	< 0.12 U	< 0.13 U	< 0.092 U	< 0.055 U	26 J	8.1 J	1.3 J	< 0.13 U	< 0.051 U
Football Field	SSHS-B2649	SSHS-B2649-SUB-4-6	5/17/2019	856.28	4 - 6 ft	180-90275-1	Excavated	1.941	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	1.6 J	0.28 J	0.061 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2649	SSHS-B2649-SUB-6-8	5/17/2019	856.28	6 - 8 ft	180-90275-1	Not Excavated	2.301	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.9 J	0.34 J	0.061 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B265	SSHS-B265-SUB-2-4	7/17/2015	855.73	2 - 4 ft	180-46045-1	Excavated	32.3	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	23 J	8.2 J	1.1 J	< 0.067 U	< 0.037 U
Football Field	SSHS-B265	SSHS-B265-SUB-4-6	7/17/2015	855.73	4 - 6 ft	180-46045-1	Excavated	2.037	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	1.5 J	0.48 J	0.057 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B265	SSHS-B265-SUB-6-8	7/17/2015	855.73	6 - 8 ft	180-46045-1	Excavated	ND	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	< 0.0049 U	< 0.0047 U	< 0.0043 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B2650	SSHS-B2650-SUB-4-6	5/14/2019	855.84	4 - 6 ft	180-90048-1	Excavated	0.496	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.26 J	0.16 J	0.076 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2651	SSHS-B2651-SUB-4-6	5/18/2019	856.45	4 - 6 ft	180-90319-1	Excavated	6.55	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	4.8 J	1.4 J	0.35 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2652	SSHS-B2652-SUB-4-6	5/15/2019	856.40	4 - 6 ft	180-90165-1	Excavated	5.56	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	3.5 J	1.4 J	0.66 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2653	SSHS-B2653-SUB-4-6	5/19/2019	856.44	4 - 6 ft	180-90323-1	Excavated	10.51	< 0.034 U	< 0.037 U	< 0.025 U	< 0.015 U	7 J	2.7 J	0.81 J	< 0.036 U	< 0.014 U
Football Field	SSHS-B2654	PS-FD-21	5/18/2019	855.51	4 - 6 ft	180-90319-1	Excavated	119.7	< 0.25 U	< 0.28 U	< 0.19 U	< 0.11 U	96 J	20 J	3.7 J	< 0.28 U	< 0.11 U
Football Field	SSHS-B2654	SSHS-B2654-SUB-4-6	5/18/2019	855.51	4 - 6 ft	180-90319-1	Excavated	133.8	< 0.25 U	< 0.27 U	< 0.19 U	< 0.11 U	110 J	19 J	4.8 J	< 0.27 U	< 0.1 U
Football Field	SSHS-B2655	SSHS-B2655-SUB-4-6	5/18/2019	855.38	4 - 6 ft	180-90319-1	Excavated	0.233	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.18 J	0.053 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2656	SSHS-B2656-SUB-4-6	5/18/2019	854.90	4 - 6 ft	180-90319-1	Excavated	31.2	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	24 J	5.5 J	1.7 J	< 0.068 U	< 0.026 U
Football Field	SSHS-B2657	SSHS-B2657-SUB-4-6	5/18/2019	854.90	4 - 6 ft	180-90319-1	Excavated	16.1	< 0.032 U	< 0.035 U	< 0.024 U	< 0.015 U	11 J	3.9 J	1.2 J	< 0.035 U	< 0.013 U
Football Field	SSHS-B2658	SSHS-B2658-SUB-4-6	5/18/2019	854.89	4 - 6 ft	180-90319-1	Excavated	2.65	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	2 J	0.52 J	0.13 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2659	SSHS-B2659-SUB-4-6	5/18/2019	855.25	4 - 6 ft	180-90319-1	Excavated	0.198	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.15 J	0.048 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B266	SSHS-B266-SUB-2-4	7/17/2015	855.92	2 - 4 ft	180-46045-1	Excavated	11.92	< 0.02 U	< 0.025 U	< 0.034 U	< 0.025 U	8.5 J	3.1 J	0.32 J	< 0.037 U	< 0.02 U
Football Field	SSHS-B266	SSHS-B266-SUB-4-6	7/17/2015	855.92	4 - 6 ft	180-46045-1	Excavated	64.7	< 0.18 U	< 0.23 U	< 0.31 U	< 0.23 U	44 J	18 J	2.7 J	< 0.33 U	< 0.18 U
Football Field	SSHS-B266	SSHS-B266-SUB-6-8	7/17/2015	855.92	6 - 8 ft	180-46045-1	Excavated	247	< 0.39 U	< 0.47 U	< 0.65 U	< 0.48 U	170 J	66 J	11 J	< 0.7 U	< 0.38 U
Football Field	SSHS-B2660	SSHS-B2660-SUB-2-4	4/25/2019	855.76	2 - 4 ft	180-89522-2	Excavated	0.645	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.45 J	0.15 J	0.045 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B2660	SSHS-B2660-SUB-4-6	4/25/2019	855.76	4 - 6 ft	180-89522-1	Excavated	0.228	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.17 J	0.058 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2661	SSHS-B2661-SUB-4-6	4/25/2019	854.80	4 - 6 ft	180-89522-2	Excavated	15.69	< 0.032 U	< 0.034 U	< 0.024 U	< 0.014 U	11 J	3.9 J	0.79 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B2661	SSHS-B2661-SUB-10-12	4/25/2019	854.80	10 - 12 ft	180-89522-1	Excavated	86.1	< 0.3 U	< 0.33 U	< 0.23 U	< 0.14 U	65 J	19 J	2.1 J	< 0.33 U	< 0.13 U
Football Field	SSHS-B2663	PS-FD-28	5/20/2019	857.21	4 - 6 ft	180-90324-1	Excavated	0.914	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.68 J	0.19 J	0.044 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2663	SSHS-B2663-SUB-4-6	5/20/2019	857.21	4 - 6 ft	180-90324-1	Excavated	1.215	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.91 J	0.26 J	0.045 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2664	SSHS-B2664-SUB-4-6	5/20/2019	857.23	4 - 6 ft	180-90324-1	Excavated	2.131	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.7 J	0.39 J	0.041 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2665	SSHS-B2665-SUB-4-6	5/20/2019	857.21	4 - 6 ft	180-90324-1	Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2666	SSHS-B2666-SUB-4-6	5/20/2019	857.28	4 - 6 ft	180-90324-1	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2667	SSHS-B2667-SUB-4-6	5/17/2019	857.32	4 - 6 ft	180-90275-1	Excavated	0.44	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.23 J	0.18 J	0.03 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2668	SSHS-B2668-SUB-6-8	5/16/2019	855.01	6 - 8 ft	180-90231-1	Excavated	2.05	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.4 J	0.52 J	0.13 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B266A	SSHS-B266A-SUB-8-10	7/29/2015	855.92	8 - 10 ft	180-46367-1	Excavated	25.7	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	20 J	4.7 J	1 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B267	SSHS-B267-SUB-2-4	7/30/2015	855.57	2 - 4 ft	180-46426-1	Excavated	1.763	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	1.2 J	0.49 J	0.073 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B267	SSHS-B267-SUB-4-6	7/30/2015	855.57	4 - 6 ft	180-46426-1	Excavated	0.1932	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.13 J	0.054 J	0.0092 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B267	SSHS-B267-SUB-6-8	7/30/2015	855.57	6 - 8 ft	180-46426-1	Excavated	ND	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	< 0.0047 U	< 0.0044 U	< 0.0041 U	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B2671	SSHS-B2671-SUB-6-8	5/18/2019	855.78	6 - 8 ft	180-90319-1	Not Excavated	2.51	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.8 J	0.51 J	0.2 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2672	SSHS-B2672-SUB-2-4	5/19/2019	856.34	2 - 4 ft	180-90323-2	Excavated	26.18	< 0.061 U	< 0.067 U	< 0.046 U	< 0.028 U	21 J	4.5 J	0.68 J	< 0.066 U	< 0.025 U
Football Field	SSHS-B2672	SSHS-B2672-SUB-6-8	5/19/2019	856.34	6 - 8 ft	180-90323-1	Excavated	5.37	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	3.6 J	1.3 J	0.47 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2673	SSHS-B2673-SUB-2-4	5/18/2019	855.02	2 - 4 ft	180-90319-2	Excavated	254	< 0.64 U	< 0.69 U	< 0.48 U	< 0.29 U	200 J	43 J	11 J	< 0.69 U	< 0.26 U
Football Field	SSHS-B2673	PS-FD-23	5/18/2019	855.02	6 - 8 ft	180-90319-1	Excavated	12.29	< 0.03 U	< 0.032 U	< 0.022 U	< 0.013 U	9.1 J	2.5 J	0.69 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B2673	SSHS-B2673-SUB-6-8	5/18/2019	855.02	6 - 8 ft	180-90319-1	Excavated	5.22	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	4 J	1 J	0.22 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2674	SSHS-B2674-SUB-6-8	4/25/2019	854.92	6 - 8 ft	180-89522-1	Excavated	0.38	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.28 J	0.1 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2675	SSHS-B2675-SUB-4-6	5/17/2019	857.15	4 - 6 ft	180-90275-2	Excavated	54.3	< 0.31 U	< 0.33 U	< 0.23 U	< 0.14 U	41 J	12 J	1.3 J	< 0.33 U	< 0.13 U
Football Field	SSHS-B2675	SSHS-B2675-SUB-8-10	5/17/2019	857.15	8 - 10 ft	180-90275-1	Excavated	5.32	< 0.031 U	< 0.033 U	< 0.023 U	< 0.014 U	4.1 J	1.1 J	0.12 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B2676	SSHS-B2676-SUB-4-6	5/16/2019	856.26	4 - 6 ft	180-90231-1	Excavated	2.13	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.5 J	0.45 J	0.18 J	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B2676	SSHS-B2676-SUB-8-10	5/16/2019	856.26	8 - 10 ft	180-90231-1	Not Excavated	0.077	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.057 J	0.02 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2679	SSHS-B2679-SUB-4-6	4/24/2019	855.15	4 - 6 ft	180-89408-2	Excavated	487	< 1.2 U	< 1.3 U	< 0.88 U	< 0.53 U	360 J	110 J	17 J	< 1.3 U	< 0.49 U
Football Field	SSHS-B2679	SSHS-B2679-SUB-8-10	4/24/2019	855.15	8 - 10 ft	180-89408-2	Excavated	108.8	< 0.61 U	< 0.66 U	< 0.46 U	< 0.27 U	80 J	25 J	3.8 J	< 0.66 U	< 0.25 U
Football Field	SSHS-B2679	SSHS-B2679-SUB-10-12	4/24/2019	855.15	10 - 12 ft	180-89408-2	Excavated	119.2	< 0.29 U	< 0.31 U	< 0.22 U	< 0.13 U	87 J	28 J	4.2 J	< 0.31 U	< 0.12 U
Football Field	SSHS-B2679	SSHS-B2679-SUB-14-16	4/24/2019	855.15	14 - 16 ft	180-89408-2	Not Excavated	28.69	< 0.058 U	< 0.064 U	< 0.044 U	< 0.026 U	21 J	6.7 J	0.99 J	< 0.063 U	< 0.024 U
Football Field	SSHS-B268	SSHS-B268-SUB-2-4	7/29/2015	855.75	2 - 4 ft	180-46367-1	Excavated	11.55	< 0.037 U	< 0.045 U	< 0.063 U	< 0.046 U	10 J	1.1 J	0.45 J	< 0.067 U	< 0.036 U
Football Field	SSHS-B268	SSHS-B268-SUB-4-6	7/29/2015	855.75	4 - 6 ft	180-46367-1	Excavated	0.942	< 0.004 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.63 J	0.28 J	0.032 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B268	SSHS-B268-SUB-6-8	7/29/2015	855.75	6 - 8 ft	180-46367-1	Excavated	ND	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	< 0.0047 U	< 0.0045 U	< 0.0041 U	< 0.007 U	< 0.0038 U
Football Field	SSHS-B2682	SSHS-B2682-SUB-2-4	4/25/2019	854.91	2 - 4 ft	180-89522-2	Excavated	3080	< 6.1 U	< 6.7 U	< 4.6 U	< 2.8 U	2400 J	590 J	90 J	< 6.6 U	< 2.5 U
Tennis Courts / Main Parking Lot	SSHS-B2683	SSHS-B2683-SUB-12-14	4/27/2019	855.72	12 - 14 ft	180-89523-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2684	SSHS-B2684-SUB-2-4	4/26/2019	856.09	2 - 4 ft	180-89521-2	Excavated	1.59	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.98 J	0.46 J	0.15 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2684	SSHS-B2684-SUB-8-10	4/26/2019	856.09	8 - 10 ft	180-89521-2	Excavated	0.66	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.49 J	0.17 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2684	SSHS-B2684-SUB-10-12	4/26/2019	856.09	10 - 12 ft	180-89521-2	Excavated	0.151	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.11 J	0.041 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2684	SSHS-B2684-SUB-12-14	4/26/2019	856.09	12 - 12 ft	180-89521-1	Excavated	0.48	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.34 J	0.14 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2685	SSHS-B2685-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Not Excavated	0.238	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.18 J	0.046 J	0.012 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B269	SSHS-B269-SUB-2-3	7/17/2015	855.71	2 - 3 ft	180-46045-1	Excavated	11.17	< 0.019 U	< 0.023 U	< 0.031 U	< 0.023 U	7.3 J	3.3 J	0.57 J	< 0.033 U	< 0.018 U
Football Field	SSHS-B2691	SSHS-B2691-SUB-2-4	5/20/2019	857.08	2 - 4 ft	180-90324-1	Excavated	52.9	< 0.13 U	< 0.14 U	< 0.096 U	< 0.057 U	43 J	8 J	1.9 J	< 0.14 U	< 0.053 U
Football Field	SSHS-B2692	PS-FD-27	5/20/2019	857.33	2 - 4 ft	180-90324-1	Excavated	2.32	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.2 J	0.82 J	0.3 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2692	SSHS-B2692-SUB-2-4	5/20/2019	857.33	2 - 4 ft	180-90324-1	Excavated	1.5	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.72 J	0.57 J	0.21 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2693	SSHS-B2693-SUB-2-4	5/20/2019	857.04	2 - 4 ft	180-90324-1	Excavated	1.41	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.67 J	0.52 J	0.22 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2695	SSHS-B2695-SUB-2-4	5/16/2019	855.08	2 - 4 ft	180-90231-1	Excavated	14.8	< 0.059 U	< 0.065 UJ	< 0.045 U	< 0.027 U	11 J	3 J	0.8 J	< 0.064 U	< 0.025 UJ
Football Field	SSHS-B2696	PS-FD-5	5/14/2019	855.18	2 - 4 ft	180-90048-1	Excavated	12.7	< 0.03 U	< 0.032 U	< 0.022 U	< 0.013 U	8.4 J	3 J	1.3 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B2696	SSHS-B2696-SUB-2-4	5/14/2019	855.18	2 - 4 ft	180-90048-1	Excavated	6.54	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	4.5 J	1.5 J	0.54 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2697	SSHS-B2697-SUB-2-4	5/14/2019	855.16	2 - 4 ft	180-90048-1	Excavated	0.242	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.15 J	0.065 J	0.027 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2698	SSHS-B2698-SUB-2-4	5/14/2019	855.31	2 - 4 ft	180-90048-1	Excavated	0.173	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.12 J	0.039 J	0.014 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2698	SSHS-B2698-SUB-4-6	5/14/2019	855.31	4 - 6 ft	180-90048-1	Excavated	18.3	< 0.066 U	< 0.072 U	< 0.049 U	< 0.03 U	13 J	4.2 J	1.1 J	< 0.071 UJ	< 0.027 UJ

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2699	PS-FD-6	5/14/2019	856.14	4 - 6 ft	180-90048-1	Excavated	0.018	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.018 J	< 0.0056 UJ	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2699	SSHS-B2699-SUB-4-6	5/14/2019	856.14	4 - 6 ft	180-90048-1	Excavated	0.0238	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.014 J	0.0098 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B270	SSHS-B270-SUB-2-4	7/17/2015	855.94	2 - 4 ft	180-46045-1	Excavated	32.8	< 0.037 U	< 0.045 U	< 0.062 U	< 0.046 U	22 J	9.8 J	1 J	< 0.067 U	< 0.036 U
Football Field	SSHS-B270	SSHS-B270-SUB-4-5	7/17/2015	855.94	4 - 5 ft	180-46045-1	Excavated	20.48	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	14 J	5.8 J	0.68 J	< 0.068 U	< 0.037 U
Football Field	SSHS-B2700	SSHS-B2700-SUB-8-10	5/17/2019	856.68	8 - 10 ft	180-90275-1	Not Excavated	6.59	< 0.032 U	< 0.034 U	< 0.024 U	< 0.014 U	5 J	1.4 J	0.19 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B2703	SSHS-B2703-SUB-2-4	5/19/2019	854.92	2 - 4 ft	180-90323-1	Excavated	0.776	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.58 J	0.15 J	0.046 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B271	SSHS-B271-SUB-2-4	7/17/2015	855.95	2 - 4 ft	180-46045-1	Excavated	6.78	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	4.7 J	1.8 J	0.28 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B271	SSHS-B271-SUB-4-6	7/17/2015	855.95	4 - 6 ft	180-46045-1	Excavated	58.1	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	42 J	14 J	2.1 J	< 0.069 U	< 0.037 U
Football Field	SSHS-B271	SSHS-B271-SUB-6-8	7/17/2015	855.95	6 - 8 ft	180-46045-1	Excavated	8.83	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0046 U	5.9 J	2.5 J	0.43 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B2724	PS-FD-8	4/24/2019	855.34	2 - 4 ft	180-89408-2	Excavated	5.26	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.5 J	1.5 J	0.26 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2724	SSHS-B2724-SUB-2-4	4/24/2019	855.34	2 - 4 ft	180-89408-2	Excavated	5.89	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	3.8 J	1.8 J	0.29 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B2724	SSHS-B2724-SUB-4-6	4/24/2019	855.34	4 - 6 ft	180-89408-2	Excavated	15.19	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	11 J	3.6 J	0.59 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B2724	SSHS-B2724-SUB-6-8	4/24/2019	855.34	6 - 8 ft	180-89408-2	Excavated	18.35	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	13 J	4.6 J	0.75 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B2724	SSHS-B2724-SUB-12-14	4/24/2019	855.34	12 - 14 ft	180-89408-2	Not Excavated	0.15	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.11 J	0.04 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2725	SSHS-B2725-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-2	Excavated	21.9	< 0.029 U	< 0.032 U	< 0.022 U	< 0.013 U	11 J	9.1 J	1.8 J	< 0.031 U	< 0.012 U
Football Field	SSHS-B2725	SSHS-B2725-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-2	Excavated	16.02	< 0.03 U	< 0.033 U	< 0.023 U	< 0.014 U	8.3 J	6.8 J	0.92 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B273	SSHS-B273-SUB-2-4	7/29/2015	855.95	2 - 4 ft	180-46367-1	Excavated	862	< 7.5 U	< 9.2 U	< 13 U	< 9.3 U	600 J	200 J	62 J	< 14 U	< 7.4 U
Football Field	SSHS-B273	SSHS-B273-SUB-4-6	7/29/2015	855.95	4 - 6 ft	180-46367-1	Excavated	25.7	< 0.075 U	< 0.092 U	< 0.13 U	< 0.093 U	18 J	6.4 J	1.3 J	< 0.14 U	< 0.074 U
Football Field	SSHS-B273	SSHS-B273-SUB-6-8	7/29/2015	855.95	6 - 8 ft	180-46367-1	Excavated	0.202	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.084 J	0.099 J	0.019 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B274	SSHS-B274-SUB-2-4	7/29/2015	856.07	2 - 4 ft	180-46367-1	Excavated	108.5	< 0.38 U	< 0.47 U	< 0.64 U	< 0.47 U	78 J	27 J	3.5 J	< 0.69 U	< 0.37 U
Football Field	SSHS-B274	SSHS-B274-SUB-4-6	7/29/2015	856.07	4 - 6 ft	180-46367-1	Excavated	11.23	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	8.9 J	1.5 J	0.83 J	< 0.071 U	< 0.039 U
Football Field	SSHS-B274	SSHS-B274-SUB-6-8	7/29/2015	856.07	6 - 8 ft	180-46367-1	Excavated	0.0076	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	< 0.0047 U	< 0.0045 U	0.0076 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B275	SSHS-B275-SUB-2-4	7/17/2015	856.07	2 - 4 ft	180-46045-1	Excavated	79.9	< 0.039 U	< 0.047 U	< 0.065 U	< 0.048 U	55 J	22 J	2.9 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B275	SSHS-B275-SUB-4-5.5	7/17/2015	856.07	4 - 5.5 ft	180-46045-1	Excavated	168.7	< 0.36 U	< 0.44 U	< 0.61 U	< 0.45 U	120 J	43 J	5.7 J	< 0.65 U	< 0.35 U
Football Field	SSHS-B2752	SSHS-B2752-SUB-2-4	4/24/2019	856.83	2 - 4 ft	180-89408-2	Excavated	0.536	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.33 J	0.17 J	0.036 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2752	SSHS-B2752-SUB-8-10	4/24/2019	856.83	8 - 10 ft	180-89408-2	Excavated	6.03	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	4.4 J	1.4 J	0.23 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2752	SSHS-B2752-SUB-10-12	4/24/2019	856.83	10 - 12 ft	180-89408-2	Excavated	449	< 1.2 U	< 1.3 U	< 0.91 U	< 0.55 U	320 J	110 J	19 J	< 1.3 U	< 0.5 U
Football Field	SSHS-B2752	SSHS-B2752-SUB-12-14	4/24/2019	856.83	12 - 14 ft	180-89408-2	Excavated	209.1	< 0.6 U	< 0.65 U	< 0.45 U	< 0.27 U	150 J	50 J	9.1 J	< 0.65 U	< 0.25 U
Football Field	SSHS-B2752	SSHS-B2752-SUB-14-16	4/24/2019	856.83	14 - 16 ft	180-89408-2	Excavated	1.008	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.72 J	0.25 J	0.038 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B2753	SSHS-B2753-SUB-2-4	4/23/2019	856.56	2 - 4 ft	180-89344-2	Excavated	2.17	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.6 J	0.45 J	0.12 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2753	SSHS-B2753-SUB-4-6	4/23/2019	856.56	4 - 6 ft	180-89344-2	Excavated	0.336	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.25 J	0.068 J	0.018 J	< 0.0072 U	< 0.0028 U
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-10-12	4/27/2019	855.31	10 - 12 ft	180-89523-1	Excavated	5.66	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	4.2 J	1.2 J	0.26 J	< 0.0072 U	< 0.0028 U
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-12-14	4/27/2019	855.31	12 - 14 ft	180-89523-1	Excavated	102.2	< 0.29 U	< 0.32 U	< 0.22 U	< 0.13 U	77 J	21 J	4.2 J	< 0.32 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B2754	PS-FD-24	5/19/2019	855.32	14 - 16 ft	180-90323-1	Not Excavated	2.5	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.9 J	0.46 J	0.14 J	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-14-16	5/19/2019	855.32	14 - 16 ft	180-90323-3	Not Excavated	2.73	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	2 J	0.56 J	0.17 J	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	16.98	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	13 J	3.5 J	0.48 J	< 0.033 U	< 0.013 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	14.2	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	11 J	2.7 J	0.5 J	< 0.034 U	< 0.013 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	0.191	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.14 J	0.051 J	< 0.0052 UJ	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2756	PS-FD-14	4/26/2019	856.39	12 - 14 ft	180-89521-1	Not Excavated	0.3	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.08 J	0.22 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B2756	SSHS-B2756-SUB-12-14	4/26/2019	856.39	12 - 14 ft	180-89521-1	Not Excavated	0.168	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.048 J	0.12 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2757	SSHS-B2757-SUB-8-10	4/26/2019	856.35	8 - 10 ft	180-89521-2	Excavated	2.15	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.3 J	0.85 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2757	SSHS-B2757-SUB-12-14	4/26/2019	856.35	12 - 14 ft	180-89521-1	Excavated	1.031	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.73 J	0.27 J	0.031 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2758	SSHS-B2758-SUB-12-14	4/26/2019	856.25	12 - 14 ft	180-89521-1	Excavated	0.028	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.014 J	0.014 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2759	SSHS-B2759-SUB-12-14	4/26/2019	856.32	12 - 14 ft	180-89521-1	Not Excavated	0.098	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.04 J	0.058 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B276	SSHS-B276-SUB-2-4	7/29/2015	856.16	2 - 4 ft	180-46367-1	Excavated	19.79	< 0.039 U	< 0.047 U	< 0.066 U	< 0.048 U	16 J	3.2 J	0.59 J	< 0.07 U	< 0.038 U
Football Field	SSHS-B276	SSHS-B276-SUB-4-6	7/29/2015	856.16	4 - 6 ft	180-46367-1	Excavated	74.8	< 0.2 U	< 0.24 U	< 0.34 U	< 0.25 U	65 J	7.4 J	2.4 J	< 0.36 U	< 0.2 U
Football Field	SSHS-B276	SSHS-B276-SUB-6-8	7/29/2015	856.16	6 - 8 ft	180-46367-1	Excavated	73.6	< 0.19 U	< 0.24 U	< 0.33 U	< 0.24 U	62 J	9.4 J	2.2 J	< 0.35 U	< 0.19 U
Football Field	SSHS-B2760	SSHS-B2760-SUB-4-6	4/25/2019	856.06	4 - 6 ft	180-89522-2	Excavated	443	< 1.2 U	< 1.3 U	< 0.92 U	< 0.55 U	320 J	110 J	13 J	< 1.3 U	< 0.51 U
Football Field	SSHS-B2760	SSHS-B2760-SUB-6-8	4/25/2019	856.06	6 - 8 ft	180-89522-2	Excavated	166.3	< 0.62 U	< 0.68 U	< 0.47 U	< 0.28 U	120 J	41 J	5.3 J	< 0.67 U	< 0.26 U
Football Field	SSHS-B2760	SSHS-B2760-SUB-14-16	4/25/2019	856.06	14 - 16 ft	180-89522-1	Excavated	75.4	< 0.12 U	< 0.13 U	< 0.093 U	< 0.056 U	58 J	15 J	2.4 J	< 0.13 U	< 0.051 U
Football Field	SSHS-B2761	SSHS-B2761-SUB-12-14	4/25/2019	856.14	12 - 14 ft	180-89522-2	Excavated	29.3	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	20 J	7 J	2.3 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B2761	SSHS-B2761-SUB-14-16	4/25/2019	856.14	14 - 16 ft	180-89522-1	Not Excavated	20.4	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	13 J	5 J	2.4 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-2-4	4/26/2019	856.00	2 - 4 ft	180-89521-2	Excavated	4.94	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	2.9 J	1.7 J	0.34 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-4-6	4/26/2019	856.00	4 - 6 ft	180-89521-2	Excavated	0.16	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.16	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-10-12	4/27/2019	855.65	10 - 12 ft	180-89523-1	Excavated	4.8	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.5	3.3	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-12-14	4/27/2019	855.65	12 - 14 ft	180-89523-1	Excavated	13.1	< 0.03 U	< 0.033 U	< 0.023 U	< 0.014 U	4.5	8.6	< 0.026 U	< 0.033 U	< 0.013 U
Football Field	SSHS-B2766	SSHS-B2766-SUB-6-8	4/23/2019	855.84	6 - 8 ft	180-89344-2	Excavated	9.55	< 0.03 U	< 0.033 U	< 0.022 U	< 0.013 U	7.1 J	2.1 J	0.35 J	< 0.032 U	< 0.012 U
Football Field	SSHS-B277	SSHS-B277-SUB-2-4	7/29/2015	855.87	2 - 4 ft	180-46367-1	Excavated	0.834	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	0.63 J	0.15 J	0.054 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B277	SSHS-B277-SUB-4-6	7/29/2015	855.87	4 - 6 ft	180-46367-1	Excavated	5.89	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	4.4 J	1.3 J	0.19 J	< 0.0069 U	< 0.0038 U
Football Field	SSHS-B277	SSHS-B277-SUB-6-8	7/29/2015	855.87	6 - 8 ft	180-46367-1	Excavated	21.7	< 0.075 U	< 0.092 U	< 0.13 U	< 0.093 U	16 J	3.5 J	2.2 J	< 0.14 U	< 0.074 U
Football Field	SSHS-B2771	SSHS-B2771-SUB-6-8	5/13/2019	854.87	6 - 8 ft	180-90048-1	Excavated	0.013	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.013 J	< 0.0056 UJ	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2771	SSHS-B2771-SUB-8-10	5/13/2019	854.87	8 - 10 ft	180-90048-1	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 UJ	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B2771	SSHS-B2771-SUB-10-12	5/13/2019	854.87	10 - 12 ft	180-90048-1	Excavated	ND	< 0.0057 UJ	< 0.0062 UJ	< 0.0043 UJ	< 0.0026 UJ	< 0.0042 UJ	< 0.0052 UJ	< 0.005 UJ	< 0.0062 UJ	< 0.0024 UJ
Football Field	SSHS-B2773	SSHS-B2773-SUB-6-8	5/13/2019	854.27	6 - 8 ft	180-90048-2	Not Excavated	0.3	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	0.17 J	0.13 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2773	SSHS-B2773-SUB-8-10	5/13/2019	854.27	8 - 10 ft	180-90048-2	Not Excavated	0.51	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.29 J	0.22 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2774	SSHS-B2774-SUB-6-8	5/13/2019	854.02	6 - 8 ft	180-90048-2	Not Excavated	0.1501	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0061 J	0.076 J	0.068 J	< 0.0061 U	< 0.0024 U
Football Field	SSHS-B2774	SSHS-B2774-SUB-8-10	5/13/2019	854.02	8 - 10 ft	180-90048-2	Not Excavated	0.073	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.036 J	0.037 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B278	SSHS-B278-SUB-2-4	7/16/2015	855.94	2 - 4 ft	180-46033-1	Excavated	3.64	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.3 J	1.2 J	0.14 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B278	SSHS-B278-SUB-4-6	7/16/2015	855.94	4 - 6 ft	180-46033-1	Excavated	25.7	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	12 J	11 J	2.7 J	< 0.068 U	< 0.037 U
Football Field	SSHS-B278	SSHS-B278-SUB-6-8	7/16/2015	855.94	6 - 8 ft	180-46033-1	Excavated	29.3	< 0.073 U	< 0.09 U	< 0.12 U	< 0.091 U	14 J	12 J	3.3 J	< 0.13 U	< 0.072 U
Football Field	SSHS-B278A	SSHS-B278A-SUB-2-4	7/13/2017	855.94	2 - 4 ft	180-68203-1	Excavated	16.97	< 0.096 U	< 0.094 U	< 0.072 U	< 0.14 U	11	5.6	0.37	< 0.13 U	< 0.055 U
Football Field	SSHS-B278A	SSHS-B278A-SUB-8-10	7/29/2015	855.94	8 - 10 ft	180-46367-1	Excavated	5.31	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	4.4 J	0.76 J	0.15 J	< 0.0067 U	< 0.0037 U
Football Field	SSHS-B279	SSHS-B279-SUB-2-4	7/29/2015	856.14	2 - 4 ft	180-46367-1	Excavated	8	< 0.038 U	< 0.046 U	< 0.064 U	< 0.047 U	4.3 J	2 J	1.7 J	< 0.069 U	< 0.037 U
Football Field	SSHS-B279	SSHS-B279-SUB-4-6	7/29/2015	856.14	4 - 6 ft	180-46367-1	Excavated	41.7	< 0.078 U	< 0.096 U	< 0.13 U	< 0.097 U	27 J	7.9 J	6.8 J	< 0.14 U	< 0.077 U
Football Field	SSHS-B279	CS-FD-#11	7/29/2015	856.14	6 - 8 ft	180-46367-1	Excavated	0.11	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	< 0.0046 U	< 0.0044 U	0.11	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B279	SSHS-B279-SUB-6-8	7/29/2015	856.14	6 - 8 ft	180-46367-1	Excavated	0.088	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	< 0.0046 U	0.023 J	0.065 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B280	SSHS-B280-SUB-2-4	7/16/2015	855.92	2 - 4 ft	180-46033-1	Excavated	0.094	< 0.0036 U	< 0.0044 U	< 0.0061 U	< 0.0045 U	0.049 J	0.045 J	< 0.0039 U	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B280	SSHS-B280-SUB-4-6	7/16/2015	855.92	4 - 6 ft	180-46033-1	Excavated	960	< 0.77 U	< 0.95 U	< 1.3 U	< 0.95 U	760 J	150 J	50 J	< 1.4 U	< 0.76 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B280	SSHS-B280-SUB-6-8	7/16/2015	855.92	6 - 8 ft	180-46033-1	Excavated	6.46	< 0.0042 U	< 0.0052 U	< 0.0072 U	< 0.0053 U	4.1 J	2 J	0.36 J	< 0.0077 U	< 0.0042 U
Football Field	SSHS-B281	SSHS-B281-SUB-2-4	7/17/2015	856.15	2 - 4 ft	180-46045-1	Excavated	9.35	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	5.9 J	3.1 J	0.35 J	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B281	PA-FD-#7	7/17/2015	856.15	4 - 6 ft	180-46045-1	Excavated	19.8	< 0.019 U	< 0.024 U	< 0.033 U	< 0.024 U	6.3 J	11 J	2.5 J	< 0.035 U	< 0.019 U
Football Field	SSHS-B281	SSHS-B281-SUB-4-6	7/17/2015	856.15	4 - 6 ft	180-46045-1	Excavated	19.6	< 0.04 U	< 0.049 U	< 0.067 U	< 0.049 U	6.4 J	11 J	2.2 J	< 0.072 U	< 0.039 U
Football Field	SSHS-B281	SSHS-B281-SUB-6-8	7/17/2015	856.15	6 - 8 ft	180-46045-1	Excavated	0.329	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	< 0.0047 U	0.25 J	0.079 J	< 0.007 U	< 0.0038 U
Football Field	SSHS-B2811	SSHS-B2811-SUB-14-16	5/18/2019	856.01	14 - 16 ft	180-90319-3	Not Excavated	0.253	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.18 J	0.073 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2812	SSHS-B2812-SUB-14-16	5/18/2019	856.10	14 - 16 ft	180-90319-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2813	SSHS-B2813-SUB-14-16	5/18/2019	856.22	14 - 16 ft	180-90319-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2814	SSHS-B2814-SUB-14-16	5/18/2019	856.31	14 - 16 ft	180-90319-3	Not Excavated	2.13	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.3 J	0.57 J	0.26 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2815	SSHS-B2815-SUB-14-16	5/18/2019	856.40	14 - 16 ft	180-90319-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2816	SSHS-B2816-SUB-14-16	5/18/2019	856.38	14 - 16 ft	180-90319-3	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2817	SSHS-B2817-SUB-14-16	5/18/2019	856.07	14 - 16 ft	180-90319-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2818	SSHS-B2818-SUB-14-16	5/18/2019	856.15	14 - 16 ft	180-90319-3	Not Excavated	0.0071	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.0071 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B282	SSHS-B282-SUB-2-4	7/29/2015	855.62	2 - 4 ft	180-46367-1	Excavated	2.64	< 0.0038 U	< 0.0046 U	< 0.0064 U	< 0.0047 U	1.9 J	0.62 J	0.12 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B282	SSHS-B282-SUB-4-5	7/29/2015	855.62	4 - 5 ft	180-46367-1	Excavated	83.1	< 0.18 U	< 0.22 U	< 0.31 U	< 0.23 U	61 J	20 J	2.1 J	< 0.33 U	< 0.18 U
Football Field	SSHS-B283	SSHS-B283-SUB-2-4	7/16/2015	855.95	2 - 4 ft	180-46033-1	Excavated	1.098	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.64 J	0.4 J	0.058 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B283	PS-FD-#5	7/16/2015	855.95	4 - 6 ft	180-46033-1	Excavated	21.54	< 0.076 U	< 0.094 U	< 0.13 U	< 0.094 U	14 J	6.9 J	0.64 J	< 0.14 U	< 0.075 U
Football Field	SSHS-B283	SSHS-B283-SUB-4-6	7/16/2015	855.95	4 - 6 ft	180-46033-1	Excavated	28.3	< 0.076 U	< 0.093 U	< 0.13 U	< 0.094 U	19 J	7.9 J	1.4 J	< 0.14 U	< 0.075 U
Football Field	SSHS-B283	SSHS-B283-SUB-6-8	7/16/2015	855.95	6 - 8 ft	180-46033-1	Excavated	47.6	< 0.077 U	< 0.095 U	< 0.13 U	< 0.096 U	31 J	15 J	1.6 J	< 0.14 U	< 0.076 U
Football Field	SSHS-B283A	SSHS-B283A-SUB-8-10	7/29/2015	855.95	8 - 10 ft	180-46367-1	Excavated	24.4	< 0.076 U	< 0.093 U	< 0.13 U	< 0.094 U	14 J	6.6 J	3.8 J	< 0.14 U	< 0.075 U
Football Field	SSHS-B284	SSHS-B284-SUB-2-4	7/29/2015	856.13	2 - 4 ft	180-46367-1	Excavated	3.81	< 0.0036 U	< 0.0045 U	< 0.0062 U	< 0.0045 U	2.6 J	0.88 J	0.33 J	< 0.0066 U	< 0.0036 U
Football Field	SSHS-B284	SSHS-B284-SUB-4-6	7/29/2015	856.13	4 - 6 ft	180-46367-1	Excavated	9.2	< 0.037 U	< 0.045 U	< 0.063 U	< 0.046 U	6.6 J	2 J	0.6 J	< 0.067 U	< 0.037 U
Football Field	SSHS-B284	SSHS-B284-SUB-6-8	7/29/2015	856.13	6 - 8 ft	180-46367-1	Excavated	3.51	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.3 J	0.81 J	0.4 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B284A	SSHS-B284A-SUB-4-6	7/10/2017	856.13	4 - 6 ft	180-68038-1	Excavated	6.32	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	2.6 J	3 J	0.72 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B284A	PS-FD-1	7/10/2017	856.13	6 - 8 ft	180-68038-1	Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B284A	SSHS-B284A-SUB-6-8	7/10/2017	856.13	6 - 8 ft	180-68038-1	Excavated	ND	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B2915	SSHS-B2915-SUB-2-4	11/7/2019	856.44	2 - 4 ft	180-98520-1	Excavated	109	< 3.1 U	< 3.4 U	< 2.3 U	< 1.4 U	83 J	26 J	< 2.7 U	< 3.3 U	< 1.3 U
Football Field	SSHS-B2916	SSHS-B2916-SUB-2-4	11/7/2019	856.41	2 - 4 ft	180-98520-1	Not Excavated	0.94	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.94	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2917	DUP-06	11/4/2019	855.04	2 - 4 ft	180-98355-3	Excavated	0.64	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.64	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2917	SSHS-B2917-SUB-2-4	11/4/2019	855.04	2 - 4 ft	180-98355-1	Excavated	0.95	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.95	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2918	SSHS-B2918-SUB-2-4	11/4/2019	854.96	2 - 4 ft	180-98355-1	Excavated	1.3	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	1.3	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2919	SSHS-B2919-SUB-2-4	11/4/2019	854.98	2 - 4 ft	180-98355-1	Excavated	1.2	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	1.2	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2920	SSHS-B2920-SUB-2-4	11/4/2019	854.85	2 - 4 ft	180-98355-1	Excavated	22.9	< 0.06 U	< 0.066 U	< 0.045 U	< 0.027 U	16 J	5.2 J	1.7 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B2921	SSHS-B2921-SUB-2-4	11/6/2019	855.12	2 - 4 ft	180-98355-2	Excavated	13.8	< 0.061 U	< 0.067 U	< 0.046 U	< 0.028 U	9.1 J	3.3 J	1.4 J	< 0.066 U	< 0.025 U
Football Field	SSHS-B2921	SSHS-B2921-SUB-4-6	11/6/2019	855.12	4 - 6 ft	180-98355-2	Excavated	5.56	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	3.7 J	1.3 J	0.56 J	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B2922	SSHS-B2922-SUB-2-4	11/4/2019	855.21	2 - 4 ft	180-98355-1	Excavated	13.6	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	10 J	2.7 J	0.9 J	< 0.068 U	< 0.026 U
Football Field	SSHS-B2923	SSHS-B2923-SUB-4-6	11/5/2019	855.19	4 - 6 ft	180-98355-1	Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B2924	DUP-07	11/5/2019	855.27	4 - 6 ft	180-98355-3	Excavated	3.92	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	2.2 J	1.3 J	0.42 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2924	SSHS-B2924-SUB-4-6	11/5/2019	855.27	4 - 6 ft	180-98355-1	Excavated	5.09	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.1 J	1.4 J	0.59 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2925	SSHS-B2925-SUB-4-6	11/5/2019	855.34	4 - 6 ft	180-98355-1	Not Excavated	0.44	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.29 J	0.1 J	0.05 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2926	DUP-08	11/5/2019	855.61	4 - 6 ft	180-98355-3	Excavated	0.089	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	0.056 J	0.033 J	< 0.0057 UJ	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B2926	SSHS-B2926-SUB-4-6	11/5/2019	855.61	4 - 6 ft	180-98355-1	Excavated	0.229	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.15 J	0.059 J	0.02 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2943	SSHS-B2943-SUB-4-6	11/4/2019	854.94	4 - 6 ft	180-98355-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2944	SSHS-B2944-SUB-2-4	11/7/2019	856.50	2 - 4 ft	180-98520-1	Excavated	0.0379	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0089 J	0.018 J	0.011 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2955	SSHS-B2955-SUB-4-6	11/5/2019	855.11	4 - 6 ft	180-98355-1	Excavated	14.4	< 0.029 U	< 0.031 U	< 0.021 U	< 0.013 U	10 J	3.1 J	1.3 J	< 0.031 U	< 0.012 U
Football Field	SSHS-B2956	SSHS-B2956-SUB-2-4	11/7/2019	854.88	2 - 4 ft	180-98520-1	Excavated	6.38	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	3.5 J	2.2 J	0.68 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2956	SSHS-B2956-SUB-4-6	11/7/2019	854.88	4 - 6 ft	180-98520-1	Excavated	0.637	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.39 J	0.19 J	0.057 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2958	SSHS-B2958-SUB-4-6	11/7/2019	855.63	4 - 6 ft	180-98520-1	Excavated	0.0229	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.015 J	0.0079 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2959	SSHS-B2959-SUB-10-12	11/7/2019	855.25	10 - 12 ft	180-98520-1	Excavated	3.61	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.7 J	0.72 J	0.19 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2960	SSHS-B2960-SUB-10-12	11/7/2019	855.17	10 - 12 ft	180-98520-1	Excavated	13920	< 61 U	< 66 U	< 45 U	< 27 U	11000 J	2200 J	720 J	< 65 U	< 25 U
Football Field	SSHS-B2961	SSHS-B2961-SUB-10-12	11/5/2019	855.28	10 - 12 ft	180-98355-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2962	SSHS-B2962-SUB-12-14	11/6/2019	855.36	12 - 14 ft	180-98355-3	Excavated	0.016	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0065 J	0.0095 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated	0.154	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	0.11 J	0.032 J	0.012 J	< 0.017 U	< 0.017 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated	13.33	< 0.061 U	< 0.066 U	< 0.046 U	< 0.027 U	10 J	2.6 J	0.73 J	< 0.066 U	< 0.025 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated	2.74	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2 J	0.59 J	0.15 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2989	SSHS-B2989-SUB-4-6	11/5/2019	855.59	4 - 6 ft	180-98355-1	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated	ND	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U	< 0.042 U		
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-2-4	9/3/2019	853.35	2 - 4 ft	180-95155-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-4-6	9/3/2019	853.35	4 - 6 ft	180-95155-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-6-8	9/3/2019	853.35	6 - 8 ft	180-95155-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-8-10	9/3/2019	853.35	8 - 10 ft	180-95155-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-10-12	9/3/2019	855.74	10 - 12 ft	180-95155-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	0.042	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.015 J	0.027	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	0.036	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	0.036	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-2-4	9/3/2019	853.09	2 - 4 ft	180-95155-1	Excavated	1.7	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	1.7	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-4-6	9/3/2019	853.09	4 - 6 ft	180-95155-1	Not Excavated	0.19	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.19 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-6-8	9/3/2019	853.09	6 - 8 ft	180-95155-1	Not Excavated	0.37	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.37	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-8-10	9/3/2019	853.09	8 - 10 ft	180-95155-1	Not Excavated	0.09	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	0.09	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	0.53	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.53	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-2-4	8/30/2019	851.95	2 - 4 ft	180-95047-3	Not Excavated	0.16	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.16	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-4-6	8/30/2019	851.95	4 - 6 ft	180-95047-3	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-6-8	8/30/2019	851.95	6 - 8 ft	180-95047-3	Not Excavated	0.42	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.42	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-8-10	8/30/2019	851.95	8 - 10 ft	180-95047-3	Not Excavated	0.34	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.34	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-10-12	8/30/2019	851.95	10 - 12 ft	180-95047-3	Not Excavated	0.14	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.14	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	0.181	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.089 J	0.092 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-2-4	8/29/2019	852.25	2 - 4 ft	180-94981-2	Not Excavated	0.179	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.092 J	0.087 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-4-6	8/29/2019	852.25	4 - 6 ft	180-94981-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-6-8	8/29/2019	852.25	6 - 8 ft	180-94981-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-8-10	8/29/2019	852.25	8 - 10 ft	180-94981-2	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.011 J	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	0.054	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.036 J	0.018 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-2-4	8/29/2019	852.31	2 - 4 ft	180-94981-3	Not Excavated	0.36	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.36	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-4-6	8/29/2019	852.31	4 - 6 ft	180-94981-3	Not Excavated	0.16	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.16	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-6-8	8/29/2019	852.31	6 - 8 ft	180-94981-3	Not Excavated	0.033	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.033	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-8-10	8/29/2019	852.31	8 - 10 ft	180-94981-3	Not Excavated	0.052	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.052	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-10-12	8/29/2019	852.31	10 - 12 ft	180-94981-3	Not Excavated	0.1	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.1	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	0.11	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.11	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-2-4	8/27/2019	852.36	2 - 4 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-4-6	8/27/2019	852.36	4 - 6 ft	180-94824-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-6-8	8/27/2019	852.36	6 - 8 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-8-10	8/27/2019	852.36	8 - 10 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-10-12	8/27/2019	852.36	10 - 12 ft	180-94829-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-2-4	8/27/2019	852.58	2 - 4 ft	180-94824-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UJ	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-4-6	8/27/2019	852.58	4 - 6 ft	180-94824-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-6-8	8/27/2019	852.58	6 - 8 ft	180-94824-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-8-10	8/27/2019	852.58	8 - 10 ft	180-94824-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-10-12	8/27/2019	852.58	10 - 12 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-2-4	8/26/2019	852.37	2 - 4 ft	180-94752-1	Not Excavated	0.62	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.35 J	0.27 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-4-6	8/26/2019	852.37	4 - 6 ft	180-94752-1	Not Excavated	0.109	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.062 J	0.047 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-6-8	8/26/2019	852.37	6 - 8 ft	180-94752-1	Not Excavated	0.66	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.38 J	0.28 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-8-10	8/26/2019	852.37	8 - 10 ft	180-94752-1	Not Excavated	0.36	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.2 J	0.16 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-10-12	8/26/2019	852.37	10 - 12 ft	180-94752-1	Not Excavated	0.41	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.23 J	0.18 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	0.62	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.34 J	0.28 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-2-4	9/3/2019	853.88	2 - 4 ft	180-95155-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-4-6	9/3/2019	853.88	4 - 6 ft	180-95155-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-6-8	9/3/2019	853.88	6 - 8 ft	180-95155-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-8-10	9/3/2019	853.88	8 - 10 ft	180-95155-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-10-12	9/3/2019	853.88	10 - 12 ft	180-95155-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-4-6	9/3/2019	854.13	4 - 6 ft	180-95155-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-6-8	9/3/2019	854.13	6 - 8 ft	180-95155-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-8-10	9/3/2019	854.13	8 - 10 ft	180-95155-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-10-12	9/3/2019	854.13	10 - 12 ft	180-95155-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-2-4	8/30/2019	853.85	2 - 4 ft	180-95047-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-4-6	8/30/2019	853.85	4 - 6 ft	180-95047-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-6-8	8/30/2019	853.85	6 - 8 ft	180-95047-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-8-10	8/30/2019	853.85	8 - 10 ft	180-95047-3	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-10-12	8/30/2019	853.85	10 - 12 ft	180-95050-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-2-4	8/30/2019	853.28	2 - 4 ft	180-95047-2	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-4-6	8/30/2019	853.28	4 - 6 ft	180-95047-2	Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-6-8	8/30/2019	853.28	6 - 8 ft	180-95047-2	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-8-10	8/30/2019	853.28	8 - 10 ft	180-95047-2	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-10-12	8/30/2019	853.28	10 - 12 ft	180-95047-2	Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	0.029	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.029	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3012A	SSHS-B3012A-SUB-14-16	7/26/2021	853.25	14 - 16 ft	180-124973-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-2-4	8/29/2019	852.90	2 - 4 ft	180-94981-1	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-4-6	8/29/2019	852.90	4 - 6 ft	180-94981-1	Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-6-8	8/29/2019	852.90	6 - 8 ft	180-94981-1	Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-8-10	8/29/2019	852.90	8 - 10 ft	180-94981-1	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-10-12	8/29/2019	852.90	10 - 12 ft	180-94981-1	Not Excavated	0.022	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.022	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013A	SSHS-B3013A-SUB-14-16	7/26/2021	852.88	14 - 16 ft	180-124973-1	Not Excavated	0.033	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.033	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-2-4	8/29/2019	853.35	2 - 4 ft	180-94981-2	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-4-6	8/29/2019	853.35	4 - 6 ft	180-94981-2	Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-6-8	8/29/2019	853.35	6 - 8 ft	180-94981-2	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-8-10	8/29/2019	853.35	8 - 10 ft	180-94981-2	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-2-4	8/28/2019	853.51	2 - 4 ft	180-94902-3	Excavated	0.093	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.059 J	0.034 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-4-6	8/28/2019	853.51	4 - 6 ft	180-94902-3	Excavated	0.063	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.04 J	0.023 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-6-8	8/28/2019	853.51	6 - 8 ft	180-94902-3	Excavated	0.0201	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.011 J	0.0091 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-8-10	8/28/2019	853.51	8 - 10 ft	180-94902-3	Excavated	0.034	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.021 J	0.013 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-10-12	8/28/2019	853.51	10 - 12 ft	180-94902-3	Excavated	0.0256	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.017 J	0.0086 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	1.691	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.5 J	0.18 J	0.011 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	0.062	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.045	0.017	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	0.046	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.034	0.012 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated	0.72	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.57	0.15	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-14-16	1/23/2021	853.60	14 - 16 ft	1801164041	Not Excavated	2.79	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	2.4	0.39	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-2-4	8/29/2019	853.54	2 - 4 ft	180-94981-2	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-4-6	8/29/2019	853.54	4 - 6 ft	180-94981-2	Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-6-8	8/29/2019	853.54	6 - 8 ft	180-94981-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-8-10	8/29/2019	853.54	8 - 10 ft	180-94981-2	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-10-12	8/29/2019	853.54	10 - 12 ft	180-94981-2	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-2-4	8/28/2019	853.78	2 - 4 ft	180-94900-2	Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-4-6	8/28/2019	853.78	4 - 6 ft	180-94900-2	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-6-8	8/28/2019	853.78	6 - 8 ft	180-94900-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-8-10	8/28/2019	853.78	8 - 10 ft	180-94900-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	10 - 12 ft	180-123398-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	0.2	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.13 J	0.056 J	0.014 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	14 - 16 ft	180-123398-1	Not Excavated	0.274	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.17 J	0.08 J	0.024 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-2-4	8/27/2019	853.82	2 - 4 ft	180-94829-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UJ	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-4-6	8/27/2019	853.82	4 - 6 ft	180-94829-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-6-8	8/27/2019	853.82	6 - 8 ft	180-94829-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UJ	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-8-10	8/27/2019	853.82	8 - 10 ft	180-94829-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-10-12	8/27/2019	853.82	10 - 12 ft	180-94829-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-2-4	8/27/2019	854.09	2 - 4 ft	180-94824-3	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-4-6	8/27/2019	854.09	4 - 6 ft	180-94824-3	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-6-8	8/27/2019	854.09	6 - 8 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-8-10	8/27/2019	854.09	8 - 10 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-10-12	8/27/2019	854.09	10 - 12 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-2-4	8/27/2019	853.86	2 - 4 ft	180-94824-2	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-4-6	8/27/2019	853.86	4 - 6 ft	180-94824-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-6-8	8/27/2019	853.86	6 - 8 ft	180-94824-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-8-10	8/27/2019	853.86	8 - 10 ft	180-94824-2	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-10-12	8/27/2019	853.86	10 - 12 ft	180-94824-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-2-4	8/26/2019	853.71	2 - 4 ft	180-94752-2	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-DUP5	8/26/2019	853.71	2 - 4 ft	180-94754-3	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-4-6	8/26/2019	853.71	4 - 6 ft	180-94752-2	Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-6-8	8/26/2019	853.71	6 - 8 ft	180-94752-2	Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-8-10	8/26/2019	853.71	8 - 10 ft	180-94752-2	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.004 U	< 0.005 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-10-12	8/26/2019	853.71	10 - 12 ft	180-94752-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-12-14	8/26/2019	853.71	12 - 14 ft	180-94752-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-2-4	8/26/2019	853.76	2 - 4 ft	180-94754-3	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-4-6	8/26/2019	853.76	4 - 6 ft	180-94754-3	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-6-8	8/26/2019	853.76	6 - 8 ft	180-94754-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-8-10	8/26/2019	853.76	8 - 10 ft	180-94754-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-10-12	8/26/2019	853.76	10 - 12 ft	180-94754-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-2-4	9/3/2019	854.48	2 - 4 ft	180-95155-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-4-6	9/3/2019	854.48	4 - 6 ft	180-95155-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-6-8	9/3/2019	854.48	6 - 8 ft	180-95155-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-8-10	9/3/2019	854.48	8 - 10 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-10-12	9/3/2019	854.48	10 - 12 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-2-4	9/3/2019	855.00	2 - 4 ft	180-95155-1	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-4-6	9/3/2019	855.00	4 - 6 ft	180-95155-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-6-8	9/3/2019	855.00	6 - 8 ft	180-95155-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-8-10	9/3/2019	855.00	8 - 10 ft	180-95155-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-10-12	9/3/2019	855.00	10 - 12 ft	180-95155-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-2-4	8/30/2019	854.59	2 - 4 ft	180-95047-1	Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-4-6	8/30/2019	854.59	4 - 6 ft	180-95047-1	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-6-8	8/30/2019	854.59	6 - 8 ft	180-95047-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-8-10	8/30/2019	854.59	8 - 10 ft	180-95047-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-10-12	8/30/2019	854.59	10 - 12 ft	180-95047-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-12-14	8/30/2019	854.59	12 - 14 ft	180-95047-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-2-4	8/29/2019	854.13	2 - 4 ft	180-94981-3	Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-4-6	8/29/2019	854.13	4 - 6 ft	180-94981-3	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-6-8	8/29/2019	854.13	6 - 8 ft	180-94981-3	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-8-10	8/29/2019	854.13	8 - 10 ft	180-94981-3	Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-10-12	8/29/2019	854.13	10 - 12 ft	180-94981-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-2-4	8/28/2019	854.13	2 - 4 ft	180-94902-3	Excavated	0.085	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.052 J	0.033 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-4-6	8/28/2019	854.13	4 - 6 ft	180-94902-3	Excavated	0.027	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.019 J	0.008 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-6-8	8/28/2019	854.13	6 - 8 ft	180-94902-3	Excavated	0.131	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.079 J	0.052 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-8-10	8/28/2019	854.13	8 - 10 ft	180-94902-3	Excavated	0.0789	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0099 J	0.041 J	0.028 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-10-12	8/28/2019	854.13	10 - 12 ft	180-94902-3	Excavated	0.071	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.035 J	0.022 J	0.014 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-4	Excavated	44	< 0.28 U	< 0.31 U	< 0.21 U	< 0.13 U	34	10	< 0.25 U	< 0.31 U	< 0.12 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-2-4	8/29/2019	854.60	2 - 4 ft	180-94981-3	Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-4-6	8/29/2019	854.60	4 - 6 ft	180-94981-3	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-6-8	8/29/2019	854.60	6 - 8 ft	180-94981-3	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-8-10	8/29/2019	854.60	8 - 10 ft	180-94981-3	Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-10-12	8/29/2019	854.60	10 - 12 ft	180-94981-3	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-2-4	8/28/2019	854.97	2 - 4 ft	180-94902-3	Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-6-8	8/28/2019	854.97	6 - 8 ft	180-94902-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-8-10	8/28/2019	854.97	8 - 10 ft	180-94902-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-10-12	8/28/2019	854.97	10 - 12 ft	180-94902-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-2-4	8/28/2019	855.22	2 - 4 ft	180-94902-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-4-6	8/28/2019	855.22	4 - 6 ft	180-94902-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-6-8	8/28/2019	855.22	6 - 8 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-8-10	8/28/2019	855.22	8 - 10 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-10-12	8/28/2019	855.22	10 - 12 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	ND	< 0.0057 UJ	< 0.0062 UJ	< 0.0043 UJ	< 0.0026 UJ	< 0.0042 UJ	< 0.0053 UJ	< 0.005 UJ	< 0.0062 UJ	< 0.0024 UJ
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-2-4	8/27/2019	855.08	2 - 4 ft	180-94824-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-4-6	8/27/2019	855.08	4 - 6 ft	180-94824-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-6-8	8/27/2019	855.08	6 - 8 ft	180-94824-2	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-8-10	8/27/2019	855.08	8 - 10 ft	180-94824-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-10-12	8/27/2019	855.08	10 - 12 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-2-4	8/27/2019	855.25	2 - 4 ft	180-94819-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-4-6	8/27/2019	855.25	4 - 6 ft	180-94819-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-6-8	8/27/2019	855.25	6 - 8 ft	180-94819-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-8-10	8/27/2019	855.25	8 - 10 ft	180-94819-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-10-12	8/27/2019	855.25	10 - 12 ft	180-94819-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-2-4	8/27/2019	855.17	2 - 4 ft	180-94824-1	Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-4-6	8/27/2019	855.17	4 - 6 ft	180-94824-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-6-8	8/27/2019	855.17	6 - 8 ft	180-94824-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-8-10	8/27/2019	855.17	8 - 10 ft	180-94824-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-10-12	8/27/2019	855.17	10 - 12 ft	180-94824-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-2-4	8/26/2019	855.10	2 - 4 ft	180-94752-2	Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-4-6	8/26/2019	855.10	4 - 6 ft	180-94752-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-6-8	8/26/2019	855.10	6 - 8 ft	180-94752-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-8-10	8/26/2019	855.10	8 - 10 ft	180-94752-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-10-12	8/26/2019	855.10	10 - 12 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-12-14	8/26/2019	855.10	12 - 14 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-2-4	8/26/2019	854.81	2 - 4 ft	180-94752-1	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-4-6	8/26/2019	854.81	4 - 6 ft	180-94752-1	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-6-8	8/26/2019	854.81	6 - 8 ft	180-94752-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-8-10	8/26/2019	854.81	8 - 10 ft	180-94752-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-10-12	8/26/2019	854.81	10 - 12 ft	180-94752-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-2-4	9/3/2019	855.09	2 - 4 ft	180-95155-2	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-4-6	9/3/2019	855.09	4 - 6 ft	180-95155-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-6-8	9/3/2019	855.09	6 - 8 ft	180-95155-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-8-10	9/3/2019	855.09	8 - 10 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-10-12	9/3/2019	855.09	10 - 12 ft	180-95155-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	2 - 4 ft	180-116404-1	Not Excavated	5.91	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	3.8 J	1.6 J	0.51 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	4 - 6 ft	180-116404-3	Not Excavated	3.93	< 0.0081 U	< 0.0088 U	< 0.0061 U	< 0.0036 U	2.4 J	1.3 J	0.23 J	< 0.0088 U	< 0.0033 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-2-4	9/3/2019	855.76	2 - 4 ft	180-95162-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-4-6	9/3/2019	855.76	4 - 6 ft	180-95162-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-6-8	9/3/2019	855.76	6 - 8 ft	180-95162-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-8-10	9/3/2019	855.76	8 - 10 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-10-12	9/3/2019	855.76	10 - 12 ft	180-95162-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-2-4	8/30/2019	855.85	2 - 4 ft	180-95047-1	Not Excavated	0.368	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.28 J	0.088 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-4-6	8/30/2019	855.85	4 - 6 ft	180-95047-1	Not Excavated	0.095	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.067 J	0.028 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-6-8	8/30/2019	855.85	6 - 8 ft	180-95047-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-8-10	8/30/2019	855.85	8 - 10 ft	180-95047-1	Not Excavated	0.072	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.046 J	0.026 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-10-12	8/30/2019	855.85	10 - 12 ft	180-95047-1	Not Excavated	0.242	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.16 J	0.082 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	0.045	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.029 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-2-4	8/29/2019	855.10	2 - 4 ft	180-95006-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-4-6	8/29/2019	855.10	4 - 6 ft	180-95006-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-6-8	8/29/2019	855.10	6 - 8 ft	180-95006-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-8-10	8/29/2019	855.10	8 - 10 ft	180-95006-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-10-12	8/29/2019	855.10	10 - 12 ft	180-95006-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-2-4	8/29/2019	855.17	2 - 4 ft	180-94981-1	Excavated	0.037	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.037	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-4-6	8/29/2019	855.17	4 - 6 ft	180-94981-1	Excavated	0.017	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.0095 J	0.0075 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-6-8	8/29/2019	855.17	6 - 8 ft	180-94981-1	Not Excavated	0.0243	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.016 J	0.0083 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-8-10	8/29/2019	855.17	8 - 10 ft	180-94981-1	Not Excavated	0.01	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.01 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-10-12	8/29/2019	855.17	10 - 12 ft	180-94981-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-2-4	8/28/2019	855.23	2 - 4 ft	180-94902-1	Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-4-6	8/28/2019	855.23	4 - 6 ft	180-94902-1	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-6-8	8/28/2019	855.23	6 - 8 ft	180-94902-1	Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-8-10	8/28/2019	855.23	8 - 10 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-2-4	8/28/2019	855.78	2 - 4 ft	180-94902-2	Not Excavated	0.0081	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.0081 J	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-4-6	8/28/2019	855.78	4 - 6 ft	180-94902-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-6-8	8/28/2019	855.78	6 - 8 ft	180-94902-2	Not Excavated	0.011	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-8-10	8/28/2019	855.78	8 - 10 ft	180-94902-2	Not Excavated	0.035	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.024 J	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-10-12	8/28/2019	855.78	10 - 12 ft	180-94902-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	0.034	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.021 J	0.013 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-2-4	8/28/2019	856.00	2 - 4 ft	180-94900-1	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-4-6	8/28/2019	856.00	4 - 6 ft	180-94900-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-6-8	8/28/2019	856.00	6 - 8 ft	180-94900-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-8-10	8/28/2019	856.00	8 - 10 ft	180-94900-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-10-12	8/28/2019	856.00	10 - 12 ft	180-94900-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-2-4	8/28/2019	856.03	2 - 4 ft	180-94900-3	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-4-6	8/28/2019	856.03	4 - 6 ft	180-94900-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-6-8	8/28/2019	856.03	6 - 8 ft	180-94900-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-8-10	8/28/2019	856.03	8 - 10 ft	180-94900-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-10-12	8/28/2019	856.03	10 - 12 ft	180-94900-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-4-6	8/27/2019	856.22	4 - 6 ft	180-94824-1	Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-6-8	8/27/2019	856.22	6 - 8 ft	180-94824-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-8-10	8/27/2019	856.22	8 - 10 ft	180-94824-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-10-12	8/27/2019	856.22	10 - 12 ft	180-94824-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-2-4	8/27/2019	856.24	2 - 4 ft	180-94819-1	Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-4-6	8/27/2019	856.24	4 - 6 ft	180-94819-1	Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-6-8	8/27/2019	856.24	6 - 8 ft	180-94819-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-8-10	8/27/2019	856.24	8 - 10 ft	180-94819-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-10-12	8/27/2019	856.24	10 - 12 ft	180-94819-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-2-4	8/27/2019	856.08	2 - 4 ft	180-94819-2	Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-4-6	8/27/2019	856.08	4 - 6 ft	180-94819-2	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-6-8	8/27/2019	856.08	6 - 8 ft	180-94819-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-8-10	8/27/2019	856.08	8 - 10 ft	180-94819-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-10-12	8/27/2019	856.08	10 - 12 ft	180-94819-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-2-4	8/26/2019	856.17	2 - 4 ft	180-94754-2	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-4-6	8/26/2019	856.17	4 - 6 ft	180-94754-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-6-8	8/26/2019	856.17	6 - 8 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-8-10	8/26/2019	856.17	8 - 10 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-10-12	8/26/2019	856.17	10 - 12 ft	180-94754-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-12-14	8/26/2019	856.17	12 - 14 ft	180-94754-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-2-4	8/26/2019	855.60	2 - 4 ft	180-94752-1	Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-4-6	8/26/2019	855.60	4 - 6 ft	180-94752-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-6-8	8/26/2019	855.60	6 - 8 ft	180-94752-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-8-10	8/26/2019	855.60	8 - 10 ft	180-94752-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-2-4	9/4/2019	855.15	2 - 4 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-4-6	9/4/2019	855.15	4 - 6 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-6-8	9/4/2019	855.15	6 - 8 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-8-10	9/4/2019	855.15	8 - 10 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-10-12	9/4/2019	855.15	10 - 12 ft	180-95165-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-2-4	9/3/2019	855.98	2 - 4 ft	180-95155-3	Excavated	3.54	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.9 J	1.3 J	0.34 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-4-6	9/3/2019	855.98	4 - 6 ft	180-95155-3	Excavated	2.24	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.2 J	0.82 J	0.22 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-6-8	9/3/2019	855.98	6 - 8 ft	180-95155-3	Excavated	16.5	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	11 J	4.9 J	0.6 J	< 0.064 U	< 0.025 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-8-10	9/3/2019	855.98	8 - 10 ft	180-95155-3	Not Excavated	2.83	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.8 J	0.9 J	0.13 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-10-12	9/3/2019	855.98	10 - 12 ft	180-95155-3	Not Excavated	0.216	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.13 J	0.071 J	0.015 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	1.89	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.2 J	0.56 J	0.13 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-2-4	9/3/2019	856.41	2 - 4 ft	180-95155-3	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-4-6	9/3/2019	856.41	4 - 6 ft	180-95155-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-6-8	9/3/2019	856.41	6 - 8 ft	180-95155-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-8-10	9/3/2019	856.41	8 - 10 ft	180-95155-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-10-12	9/3/2019	856.41	10 - 12 ft	180-95155-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-2-4	8/29/2019	856.01	2 - 4 ft	180-95024-2	Not Excavated	0.0185	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.0095 J	0.009 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-4-6	8/29/2019	856.01	4 - 6 ft	180-95024-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-6-8	8/29/2019	856.01	6 - 8 ft	180-95024-2	Not Excavated	0.074	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.048 J	0.026 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-8-10	8/29/2019	856.01	8 - 10 ft	180-95024-2	Not Excavated	0.0279	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.018 J	0.0099 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-10-12	8/29/2019	856.01	10 - 12 ft	180-95024-2	Not Excavated	0.0068	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0068 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-2-4	8/29/2019	856.20	2 - 4 ft	180-95006-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-4-6	8/29/2019	856.20	4 - 6 ft	180-95006-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-6-8	8/29/2019	856.20	6 - 8 ft	180-95006-1	Not Excavated	0.0177	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0086 J	0.0091 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-8-10	8/29/2019	856.20	8 - 10 ft	180-95006-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-10-12	8/29/2019	856.20	10 - 12 ft	180-95006-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-2-4	8/29/2019	855.88	2 - 4 ft	180-94981-1	Not Excavated	0.065	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.041 J	0.024 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-4-6	8/29/2019	855.88	4 - 6 ft	180-94981-1	Not Excavated	0.0203	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.013 J	0.0073 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-6-8	8/29/2019	855.88	6 - 8 ft	180-94981-1	Not Excavated	0.23	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14 J	0.078 J	0.012 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-8-10	8/29/2019	855.88	8 - 10 ft	180-94981-1	Not Excavated	0.172	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.11 J	0.062 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-10-12	8/29/2019	855.88	10 - 12 ft	180-94981-1	Not Excavated	0.016	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.016 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-2-4	8/28/2019	856.09	2 - 4 ft	180-94900-3	Not Excavated	0.007	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.007 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-4-6	8/28/2019	856.09	4 - 6 ft	180-94900-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-6-8	8/28/2019	856.09	6 - 8 ft	180-94900-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-8-10	8/28/2019	856.09	8 - 10 ft	180-94900-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-10-12	8/28/2019	856.09	10 - 12 ft	180-94900-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-2-4	8/28/2019	856.47	2 - 4 ft	180-94902-2	Not Excavated	0.116	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.038 J	0.05 J	0.028 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-4-6	8/28/2019	856.47	4 - 6 ft	180-94902-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-6-8	8/28/2019	856.47	6 - 8 ft	180-94902-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-8-10	8/28/2019	856.47	8 - 10 ft	180-94902-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-10-12	8/28/2019	856.47	10 - 12 ft	180-94902-2	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-2-4	8/28/2019	856.71	2 - 4 ft	180-94902-1	Excavated	0.64	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.38 J	0.26 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-4-6	8/28/2019	856.71	4 - 6 ft	180-94902-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-6-8	8/28/2019	856.71	6 - 8 ft	180-94902-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-8-10	8/28/2019	856.71	8 - 10 ft	180-94902-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-10-12	8/28/2019	856.71	10 - 12 ft	180-94902-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-2-4	8/28/2019	856.96	2 - 4 ft	180-94900-2	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-4-6	8/28/2019	856.96	4 - 6 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-6-8	8/28/2019	856.96	6 - 8 ft	180-94900-2	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-8-10	8/28/2019	856.96	8 - 10 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-10-12	8/28/2019	856.96	10 - 12 ft	180-94900-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-12-14	8/28/2019	856.96	12 - 14 ft	180-94900-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-2-4	8/27/2019	857.02	2 - 4 ft	180-94824-1	Excavated	0.154	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.093 J	0.061 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-4-6	8/27/2019	857.02	4 - 6 ft	180-94824-1	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-6-8	8/27/2019	857.02	6 - 8 ft	180-94824-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-8-10	8/27/2019	857.02	8 - 10 ft	180-94824-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-10-12	8/27/2019	857.02	10 - 12 ft	180-94824-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-2-4	8/27/2019	856.91	2 - 4 ft	180-94819-3	Excavated	0.219	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.072 J	0.077 J	0.07 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-4-6	8/27/2019	856.91	4 - 6 ft	180-94819-3	Not Excavated	0.516	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.056 J	0.26 J	0.2 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-6-8	8/27/2019	856.91	6 - 8 ft	180-94819-3	Not Excavated	0.0434	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0054 J	0.023 J	0.015 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-8-10	8/27/2019	856.91	8 - 10 ft	180-94819-3	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-2-4	8/27/2019	856.95	2 - 4 ft	180-94819-1	Excavated	0.06	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.029	0.02	0.011 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-4-6	8/27/2019	856.95	4 - 6 ft	180-94819-1	Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-6-8	8/27/2019	856.95	6 - 8 ft	180-94819-1	Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-8-10	8/27/2019	856.95	8 - 10 ft	180-94819-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-10-12	8/27/2019	856.95	10 - 12 ft	180-94819-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-2-4	8/26/2019	856.77	2 - 4 ft	180-94754-1	Excavated	1.77	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.76 J	0.71 J	0.3 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-4-6	8/26/2019	856.77	4 - 6 ft	180-94754-1	Excavated	0.105	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.056 J	0.036 J	0.013 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-6-8	8/26/2019	856.77	6 - 8 ft	180-94754-2	Not Excavated	0.321	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.14 J	0.13 J	0.051 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-8-10	8/26/2019	856.77	8 - 10 ft	180-94754-2	Not Excavated	0.085	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.036 J	0.034 J	0.015 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-10-12	8/26/2019	856.77	10 - 12 ft	180-94754-2	Not Excavated	0.163	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.076 J	0.062 J	0.025 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated	0.013	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.013 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-2-4	8/26/2019	856.77	2 - 4 ft	180-94752-3	Excavated	0.067	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.011 J	0.029 J	0.027 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-4-6	8/26/2019	856.77	4 - 6 ft	180-94752-3	Not Excavated	0.091	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.025 J	0.04 J	0.026 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-6-8	8/26/2019	856.77	6 - 8 ft	180-94752-3	Not Excavated	0.0216	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0058 J	0.0085 J	0.0073 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-8-10	8/26/2019	856.77	8 - 10 ft	180-94752-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-10-12	8/26/2019	856.77	10 - 12 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-2-4	9/4/2019	855.86	2 - 4 ft	180-95165-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-4-6	9/4/2019	855.86	4 - 6 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-6-8	9/4/2019	855.86	6 - 8 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-8-10	9/4/2019	855.86	8 - 10 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-10-12	9/4/2019	855.86	10 - 12 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-2-4	9/3/2019	856.40	2 - 4 ft	180-95162-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-4-6	9/3/2019	856.40	4 - 6 ft	180-95162-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-6-8	9/3/2019	856.40	6 - 8 ft	180-95162-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-8-10	9/3/2019	856.40	8 - 10 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-10-12	9/3/2019	856.40	10 - 12 ft	180-95162-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-12-14	9/3/2019	856.40	12 - 14 ft	180-95162-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-2-4	8/30/2019	856.38	2 - 4 ft	180-95050-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-4-6	8/30/2019	856.38	4 - 6 ft	180-95050-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-6-8	8/30/2019	856.38	6 - 8 ft	180-95050-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-8-10	8/30/2019	856.38	8 - 10 ft	180-95050-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-10-12	8/30/2019	856.38	10 - 12 ft	180-95050-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-6-8	8/29/2019	855.92	6 - 8 ft	180-95006-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-8-10	8/29/2019	855.92	8 - 10 ft	180-95006-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-10-12	8/29/2019	855.92	10 - 12 ft	180-95006-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-2-4	8/28/2019	856.51	2 - 4 ft	180-94900-1	Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 UJ	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-4-6	8/28/2019	856.51	4 - 6 ft	180-94900-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-6-8	8/28/2019	856.51	6 - 8 ft	180-94900-1	Not Excavated	ND	< 0.0068 U	< 0.0073 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-8-10	8/28/2019	856.51	8 - 10 ft	180-94900-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-10-12	8/28/2019	856.51	10 - 12 ft	180-94900-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-2-4	8/28/2019	856.76	2 - 4 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-4-6	8/28/2019	856.76	4 - 6 ft	180-94900-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-6-8	8/28/2019	856.76	6 - 8 ft	180-94900-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-8-10	8/28/2019	856.76	8 - 10 ft	180-94900-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-10-12	8/28/2019	856.76	10 - 12 ft	180-94900-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-2-4	8/28/2019	856.89	2 - 4 ft	180-94900-3	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-4-6	8/28/2019	856.89	4 - 6 ft	180-94900-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-6-8	8/28/2019	856.89	6 - 8 ft	180-94900-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-8-10	8/28/2019	856.89	8 - 10 ft	180-94900-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-10-12	8/28/2019	856.89	10 - 12 ft	180-94900-3	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-2-4	8/28/2019	857.14	2 - 4 ft	180-94900-1	Excavated	0.128	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.043 J	0.053 J	0.032 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-4-6	8/28/2019	857.14	4 - 6 ft	180-94900-1	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 UJ	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	6 - 8 ft	180-94903-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	8/28/2019	857.14	6 - 8 ft	180-94900-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 UJ	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	8/28/2019	857.14	8 - 10 ft	180-94900-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 UJ	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	8/28/2019	857.14	10 - 12 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 UJ	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 UJ	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated	0.28	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.085	0.15	0.045	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	0.135	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.052	0.068	0.015 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-2-4	8/27/2019	857.18	2 - 4 ft	180-94824-2	Excavated	6.3	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	3.8 J	1.8 J	0.7 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-4-6	8/27/2019	857.18	4 - 6 ft	180-94824-2	Not Excavated	0.035	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.021 J	0.014 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-6-8	8/27/2019	857.18	6 - 8 ft	180-94824-2	Not Excavated	0.825	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	0.3 J	0.085 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-8-10	8/27/2019	857.18	8 - 10 ft	180-94824-2	Not Excavated	0.538	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.31 J	0.18 J	0.048 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	0.541	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.29 J	0.2 J	0.051 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-2-4	8/27/2019	856.99	2 - 4 ft	180-94819-2	Excavated	1.12	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.38 J	0.46 J	0.28 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-4-6	8/27/2019	856.99	4 - 6 ft	180-94819-2	Excavated	0.74	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.35 J	0.26 J	0.13 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-6-8	8/27/2019	856.99	6 - 8 ft	180-94819-2	Excavated	0.55	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.19 J	0.23 J	0.13 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-8-10	8/27/2019	856.99	8 - 10 ft	180-94819-2	Excavated	0.125	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.042 J	0.054 J	0.029 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-10-12	8/27/2019	856.99	10 - 12 ft	180-94819-2	Not Excavated	0.185	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.062 J	0.078 J	0.045 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	0.164	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.065 J	0.069 J	0.03 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-2-4	8/27/2019	856.92	2 - 4 ft	180-94819-2	Excavated	0.04	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.014 J	0.015 J	0.011 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-4-6	8/27/2019	856.92	4 - 6 ft	180-94819-2	Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-6-8	8/27/2019	856.92	6 - 8 ft	180-94819-2	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-8-10	8/27/2019	856.92	8 - 10 ft	180-94819-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-10-12	8/27/2019	856.92	10 - 12 ft	180-94819-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-2-4	8/26/2019	856.86	2 - 4 ft	180-94752-2	Excavated	0.72	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.34 J	0.26 J	0.12 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-4-6	8/26/2019	856.86	4 - 6 ft	180-94752-2	Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-6-8	8/26/2019	856.86	6 - 8 ft	180-94752-2	Excavated	0.111	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.052 J	0.04 J	0.019 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-8-10	8/26/2019	856.86	8 - 10 ft	180-94752-2	Excavated	0.0064	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0064 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-10-12	8/26/2019	856.86	10 - 12 ft	180-94752-2	Excavated	0.0148	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0095 J	0.0053 J	< 0.005 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	0.0145	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0085 J	0.006 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-2-4	8/26/2019	856.70	2 - 4 ft	180-94752-3	Not Excavated	0.451	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.19 J	0.18 J	0.081 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-4-6	8/26/2019	856.70	4 - 6 ft	180-94752-3	Not Excavated	0.0307	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.015 J	0.0097 J	0.006 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-6-8	8/26/2019	856.70	6 - 8 ft	180-94752-3	Not Excavated	0.0461	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022 J	0.016 J	0.0081 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-8-10	8/26/2019	856.70	8 - 10 ft	180-94752-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-10-12	8/26/2019	856.70	10 - 12 ft	180-94752-3	Not Excavated	0.0132	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0059 J	0.0073 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	0.026	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.0096 J	0.01 J	0.0064 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-2-4	8/29/2019	856.36	2 - 4 ft	180-95024-1	Not Excavated	0.089	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.045 J	0.044 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-4-6	8/29/2019	856.36	4 - 6 ft	180-95024-1	Not Excavated	0.023	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-6-8	8/29/2019	856.36	6 - 8 ft	180-95024-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-8-10	8/29/2019	856.36	8 - 10 ft	180-95024-1	Not Excavated	0.046	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.022 J	0.024 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-10-12	8/29/2019	856.36	10 - 12 ft	180-95024-1	Not Excavated	0.0191	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0081 J	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B308	SSHS-B308-SUB-2-4	3/2/2016	857.14	2 - 4 ft	180-52664-1	Excavated	0.285	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.17 J	0.092 J	0.023 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B308	SSHS-B308-SUB-4-6	3/2/2016	857.14	4 - 6 ft	180-52664-1	Excavated	ND	< 0.009 U,F2	< 0.014 U	< 0.0049 U	< 0.0072 U	< 0.0046 U	< 0.0072 U	< 0.0067 U,F2	< 0.0061 U	< 0.0037 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-2-4	9/4/2019	856.58	2 - 4 ft	180-95165-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-4-6	9/4/2019	856.58	4 - 6 ft	180-95165-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-6-8	9/4/2019	856.58	6 - 8 ft	180-95165-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-8-10	9/4/2019	856.58	8 - 10 ft	180-95165-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-10-12	9/4/2019	856.58	10 - 12 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-12-14	9/4/2019	856.58	12 - 14 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-2-4	9/4/2019	856.96	2 - 4 ft	180-95165-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-4-6	9/4/2019	856.96	4 - 6 ft	180-95165-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-8-10	9/4/2019	856.96	8 - 10 ft	180-95165-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-10-12	9/4/2019	856.96	10 - 12 ft	180-95165-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-2-4	8/30/2019	856.73	2 - 4 ft	180-95047-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-4-6	8/30/2019	856.73	4 - 6 ft	180-95047-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-6-8	8/30/2019	856.73	6 - 8 ft	180-95047-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-8-10	8/30/2019	856.73	8 - 10 ft	180-95047-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-10-12	8/30/2019	856.73	10 - 12 ft	180-95047-3	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-12-14	8/30/2019	856.73	12 - 14 ft	180-95047-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-2-4	8/29/2019	857.13	2 - 4 ft	180-95024-1	Not Excavated	0.619	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.32 J	0.23 J	0.069 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-4-6	8/29/2019	857.13	4 - 6 ft	180-95024-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-6-8	8/29/2019	857.13	6 - 8 ft	180-95024-2	Not Excavated	0.0089	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0089 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-8-10	8/29/2019	857.13	8 - 10 ft	180-95024-2	Not Excavated	0.032	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.018 J	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-10-12	8/29/2019	857.13	10 - 12 ft	180-95024-2	Not Excavated	0.042	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.026 J	0.016 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	0.0553	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.029 J	0.02 J	0.0063 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-2-4	8/29/2019	856.55	2 - 4 ft	180-95006-1	Not Excavated	0.093	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.042 J	0.051 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-4-6	8/29/2019	856.55	4 - 6 ft	180-95006-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-6-8	8/29/2019	856.55	6 - 8 ft	180-95006-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-8-10	8/29/2019	856.55	8 - 10 ft	180-95006-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-10-12	8/29/2019	856.55	10 - 12 ft	180-95006-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-2-4	9/4/2019	857.12	2 - 4 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-4-6	9/4/2019	857.12	4 - 6 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-6-8	9/4/2019	857.12	6 - 8 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-8-10	9/4/2019	857.12	8 - 10 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-10-12	9/4/2019	857.12	10 - 12 ft	180-95165-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-2-4	9/4/2019	857.77	2 - 4 ft	180-95165-2	Not Excavated	0.06	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.031 J	0.029 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-4-6	9/4/2019	857.77	4 - 6 ft	180-95165-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-6-8	9/4/2019	857.77	6 - 8 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-8-10	9/4/2019	857.77	8 - 10 ft	180-95165-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-10-12	9/4/2019	857.77	10 - 12 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-12-14	9/4/2019	857.77	12 - 14 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-2-4	8/30/2019	857.68	2 - 4 ft	180-95047-2	Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-4-6	8/30/2019	857.68	4 - 6 ft	180-95047-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-6-8	8/30/2019	857.68	6 - 8 ft	180-95047-2	Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-8-10	8/30/2019	857.68	8 - 10 ft	180-95047-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-10-12	8/30/2019	857.68	10 - 12 ft	180-95047-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-12-14	8/30/2019	857.68	12 - 14 ft	180-95047-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-14-16	8/30/2019	857.68	14 - 16 ft	180-95047-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B309	SSHS-B309-SUB-2-4	3/2/2016	855.88	2 - 4 ft	180-52664-1	Excavated	19.55	< 0.089 U	< 0.14 U	< 0.049 U	< 0.072 U	13 J	6 J	0.55 J	< 0.06 U	< 0.036 U
Football Field	SSHS-B309	SSHS-B309-SUB-4-6	3/2/2016	855.88	4 - 6 ft	180-52664-1	Excavated	6.63	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	4 J	2.3 J	0.33 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B3094	SSHS-DUP-56	8/30/2019	857.26	6 - 8 ft	180-95050-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 UJ	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-2-4	8/28/2019	857.12	2 - 4 ft	180-94902-2	Excavated	0.132	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.077 J	0.044 J	0.011 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-4-6	8/28/2019	857.12	4 - 6 ft	180-94902-2	Excavated	0.0167	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	0.0057 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-6-8	8/28/2019	857.12	6 - 8 ft	180-94902-2	Not Excavated	0.026	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-8-10	8/28/2019	857.12	8 - 10 ft	180-94902-2	Not Excavated	0.076	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.053 J	0.023 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-10-12	8/28/2019	857.12	10 - 12 ft	180-94902-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	0.008	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.008 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-2-4	8/27/2019	855.86	2 - 4 ft	180-94819-3	Excavated	0.057	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.022 J	0.023 J	0.012 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-4-6	8/27/2019	855.86	4 - 6 ft	180-94819-3	Not Excavated	0.0073	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.0073 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-6-8	8/27/2019	855.86	6 - 8 ft	180-94819-3	Not Excavated	0.0238	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.0072 J	0.0099 J	0.0067 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-8-10	8/27/2019	855.86	8 - 10 ft	180-94819-3	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-10-12	8/27/2019	855.86	10 - 12 ft	180-94819-3	Not Excavated	0.0271	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.018 J	0.0091 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-12-14	8/27/2019	855.86	12 - 14 ft	180-94819-3	Not Excavated	0.0161	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0071 J	0.009 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-2-4	8/27/2019	856.19	2 - 4 ft	180-94819-3	Excavated	0.199	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.074 J	0.074 J	0.051 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-4-6	8/27/2019	856.19	4 - 6 ft	180-94819-3	Excavated	0.065	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.029 J	0.024 J	0.012 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-6-8	8/27/2019	856.19	6 - 8 ft	180-94819-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-8-10	8/27/2019	856.19	8 - 10 ft	180-94819-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-10-12	8/27/2019	856.19	10 - 12 ft	180-94819-3	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-2-4	8/26/2019	855.97	2 - 4 ft	180-94754-1	Excavated	0.0271	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	0.0097 J	0.0064 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-4-6	8/26/2019	855.97	4 - 6 ft	180-94754-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-6-8	8/26/2019	855.97	6 - 8 ft	180-94754-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-8-10	8/26/2019	855.97	8 - 10 ft	180-94754-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-10-12	8/26/2019	855.97	10 - 12 ft	180-94754-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-2-4	8/26/2019	856.40	2 - 4 ft	180-94754-1	Not Excavated	0.013	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-4-6	8/26/2019	856.40	4 - 6 ft	180-94754-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-6-8	8/26/2019	856.40	6 - 8 ft	180-94754-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-8-10	8/26/2019	856.40	8 - 10 ft	180-94754-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-10-12	8/26/2019	856.40	10 - 12 ft	180-94754-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B310	SSHS-B310-SUB-2-4	3/2/2016	854.81	2 - 4 ft	180-52664-1	Excavated	22.4	< 0.082 U	< 0.13 U	< 0.045 U	< 0.066 U	15 J	5.4 J	2 J	< 0.056 U	< 0.034 U
Football Field	SSHS-B310	SSHS-B310-SUB-4-6	3/2/2016	854.81	4 - 6 ft	180-52664-1	Excavated	23.5	< 0.084 U	< 0.13 U	< 0.046 U	< 0.068 U	13 J	8 J	2.5 J	< 0.057 U	< 0.034 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	0.032	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.019 J	0.013 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-4-6	1/13/2020	856.74	4 - 6 ft	180-100985-1	Not Excavated	0.039	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.023 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-6-8	1/13/2020	856.74	6 - 8 ft	180-100985-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-8-10	1/13/2020	856.74	8 - 10 ft	180-100985-1	Not Excavated	0.0214	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.012 J	0.0094 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-10-12	1/13/2020	856.74	10 - 12 ft	180-100985-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated	0.025	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.014 J	0.011 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-4-6	1/13/2020	856.75	4 - 6 ft	180-100985-1	Excavated	0.074	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.042 J	0.032 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-6-8	1/13/2020	856.75	6 - 8 ft	180-100985-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-8-10	1/13/2020	856.75	8 - 10 ft	180-100985-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-10-12	1/13/2020	856.75	10 - 12 ft	180-100985-1	Not Excavated	0.016	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.016 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	0.0465	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.02 J	0.017 J	0.0095 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-4-6	1/13/2020	856.74	4 - 6 ft	180-100985-1	Excavated	0.013	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.013 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-6-8	1/13/2020	856.74	6 - 8 ft	180-100985-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-8-10	1/13/2020	856.74	8 - 10 ft	180-100985-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-10-12	1/13/2020	856.74	10 - 12 ft	180-100985-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-4-6	1/13/2020	856.47	4 - 6 ft	180-100985-2	Excavated	0.103	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.052 J	0.037 J	0.014 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-6-8	1/13/2020	856.47	6 - 8 ft	180-100985-2	Excavated	0.26	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.15 J	0.084 J	0.026 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-8-10	1/13/2020	856.47	8 - 10 ft	180-100985-2	Excavated	0.07	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.035 J	0.024 J	0.011 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-10-12	1/13/2020	856.47	10 - 12 ft	180-100985-2	Excavated	0.041	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.025 J	0.016 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-12-14	1/13/2020	856.47	12 - 14 ft	180-100985-2	Excavated	0.015	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.015 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	0.029	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.017 J	0.012 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated	0.068	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.04 J	0.028 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-4-6	1/13/2020	856.82	4 - 6 ft	180-100985-2	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-6-8	1/13/2020	856.82	6 - 8 ft	180-100985-2	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-8-10	1/13/2020	856.82	8 - 10 ft	180-100985-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-10-12	1/13/2020	856.82	10 - 12 ft	180-100985-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-4-6	1/14/2020	856.73	4 - 6 ft	180-101038-1	Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-6-8	1/14/2020	856.73	6 - 8 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-8-10	1/14/2020	856.73	8 - 10 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-10-12	1/14/2020	856.73	10 - 12 ft	180-101038-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-4-6	1/14/2020	856.72	4 - 6 ft	180-101038-1	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-6-8	1/14/2020	856.72	6 - 8 ft	180-101038-1	Not Excavated	0.012	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	0.012 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-8-10	1/14/2020	856.72	8 - 10 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-10-12	1/14/2020	856.72	10 - 12 ft	180-101038-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-2-4	1/15/2020	857.05	2 - 4 ft	180-101084-1	Excavated	0.053	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.031 J	0.022 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-4-6	1/15/2020	857.05	4 - 6 ft	180-101084-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-6-8	1/15/2020	857.05	6 - 8 ft	180-101084-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-8-10	1/15/2020	857.05	8 - 10 ft	180-101084-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-10-12	1/15/2020	857.05	10 - 12 ft	180-101084-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-2-4	1/14/2020	857.55	2 - 4 ft	180-101038-3	Excavated	0.36	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.097 J	0.17 J	0.093 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-4-6	1/14/2020	857.55	4 - 6 ft	180-101038-3	Not Excavated	0.066	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	0.029 J	0.025 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-6-8	1/14/2020	857.55	6 - 8 ft	180-101038-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-8-10	1/14/2020	857.55	8 - 10 ft	180-101038-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-10-12	1/14/2020	857.55	10 - 12 ft	180-101038-3	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-2-4	1/15/2020	857.26	2 - 4 ft	180-101084-2	Excavated	0.197	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.043 J	0.088 J	0.066 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-4-6	1/15/2020	857.26	4 - 6 ft	180-101084-2	Excavated	0.182	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.051 J	0.077 J	0.054 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-6-8	1/15/2020	857.26	6 - 8 ft	180-101084-2	Not Excavated	0.05	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.03 J	0.02 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-8-10	1/15/2020	857.26	8 - 10 ft	180-101084-2	Not Excavated	0.0091	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.0091 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-10-12	1/15/2020	857.26	10 - 12 ft	180-101084-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B311	SSHS-B311-SUB-2-4	3/2/2016	854.93	2 - 4 ft	180-52664-1	Excavated	7.47	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.0068 U	5.5 J	1.6 J	0.37 J	< 0.0057 U	< 0.0034 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-2-4	1/15/2020	856.32	2 - 4 ft	180-101084-2	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-4-6	1/15/2020	856.32	4 - 6 ft	180-101084-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-6-8	1/15/2020	856.32	6 - 8 ft	180-101084-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-8-10	1/15/2020	856.32	8 - 10 ft	180-101084-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-10-12	1/15/2020	856.32	10 - 12 ft	180-101084-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-2-4	1/15/2020	857.08	2 - 4 ft	180-101084-1	Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-4-6	1/15/2020	857.08	4 - 6 ft	180-101084-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-6-8	1/15/2020	857.08	6 - 8 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-8-10	1/15/2020	857.08	8 - 10 ft	180-101084-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-10-12	1/15/2020	857.08	10 - 12 ft	180-101084-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated	0.116	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.025 J	0.052 J	0.039 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-4-6	1/15/2020	856.71	4 - 6 ft	180-101084-2	Excavated	0.291	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.18 J	0.088 J	0.023 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-6-8	1/15/2020	856.71	6 - 8 ft	180-101084-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-8-10	1/15/2020	856.71	8 - 10 ft	180-101084-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-10-12	1/15/2020	856.71	10 - 12 ft	180-101084-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-2-4	1/14/2020	856.36	2 - 4 ft	180-101038-2	Excavated	0.111	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.041 J	0.045 J	0.025 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-4-6	1/14/2020	856.36	4 - 6 ft	180-101038-2	Not Excavated	0.129	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.049 J	0.051 J	0.029 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-6-8	1/14/2020	856.36	6 - 8 ft	180-101038-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-8-10	1/14/2020	856.36	8 - 10 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-10-12	1/14/2020	856.36	10 - 12 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-2-4	1/15/2020	856.51	2 - 4 ft	180-101084-1	Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-4-6	1/15/2020	856.51	4 - 6 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-6-8	1/15/2020	856.51	6 - 8 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-8-10	1/15/2020	856.51	8 - 10 ft	180-101084-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-10-12	1/15/2020	856.51	10 - 12 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-2-4	1/14/2020	856.54	2 - 4 ft	180-101038-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-4-6	1/14/2020	856.54	4 - 6 ft	180-101038-2	Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-6-8	1/14/2020	856.54	6 - 8 ft	180-101038-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-10-12	1/14/2020	856.54	10 - 12 ft	180-101038-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-2-4	1/15/2020	856.74	2 - 4 ft	180-101084-3	Not Excavated	0.037	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-4-6	1/15/2020	856.74	4 - 6 ft	180-101084-3	Not Excavated	0.04	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.024 J	0.016 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-6-8	1/15/2020	856.74	6 - 8 ft	180-101084-3	Not Excavated	0.054	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.032 J	0.022 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-8-10	1/15/2020	856.74	8 - 10 ft	180-101084-3	Not Excavated	0.03	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.018 J	0.012 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-10-12	1/15/2020	856.74	10 - 12 ft	180-101084-3	Not Excavated	ND	< 0.0056 U		< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B312	SSHS-B312-SUB-2-4	3/2/2016	857.49	2 - 4 ft	180-52664-1	Excavated	0.276	< 0.0092 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.18 J	0.078 J	0.018 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B312	SSHS-B312-SUB-4-6	3/2/2016	857.49	4 - 6 ft	180-52664-1	Excavated	2.73	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.7 J	0.83 J	0.2 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B312	SSHS-B312-SUB-6-8	3/2/2016	857.49	6 - 8 ft	180-52664-1	Not Excavated	ND	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	< 0.0044 U	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B313	SSHS-B313-SUB-4-6	3/2/2016	857.14	4 - 6 ft	180-52664-1	Excavated	9.85	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	6 J	3.2 J	0.65 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B313	PS-FD-4	3/2/2016	857.14	6 - 8 ft	180-52664-1	Excavated	ND	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	< 0.0045 U	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B313	SSHS-B313-SUB-6-8	3/2/2016	857.14	6 - 8 ft	180-52664-1	Excavated	0.0071	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.0071 J	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B314	SSHS-B314-SUB-2-4	3/2/2016	856.85	2 - 4 ft	180-52664-1	Excavated	68.3	< 0.18 U	< 0.28 U	< 0.098 U	< 0.14 U	50 J	17 J	1.3 J	< 0.12 U	< 0.073 U
Football Field	SSHS-B314	PS-FD-6	3/2/2016	856.85	4 - 6 ft	180-52664-1	Excavated	2.878	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	2 J	0.8 J	0.078 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B314	SSHS-B314-SUB-4-6	3/2/2016	856.85	4 - 6 ft	180-52664-1	Excavated	3.7	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	2.6 J	1 J	0.1 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B314	SSHS-B314-SUB-6-8	3/2/2016	856.85	6 - 8 ft	180-52664-1	Not Excavated	ND	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	< 0.0045 U	< 0.0072 U	< 0.0067 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B316	SSHS-B316-SUB-2-4	3/2/2016	856.16	2 - 4 ft	180-52664-1	Excavated	53.8	< 0.18 U	< 0.28 U	< 0.096 U	< 0.14 U	39 J	12 J	2.8 J	< 0.12 U	< 0.072 U
Football Field	SSHS-B316	SSHS-B316-SUB-4-6	3/2/2016	856.16	4 - 6 ft	180-52664-1	Excavated	0.448	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.3 J	0.11 J	0.038 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B318	SSHS-B318-SUB-2-4	3/2/2016	856.20	2 - 4 ft	180-52664-1	Excavated	0.478	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.3 J	0.15 J	0.028 J	< 0.0056 U	< 0.0033 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-2-4	8/29/2019	857.57	2 - 4 ft	180-95006-3	Excavated	0.85	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.41 J	0.44 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-4-6	8/29/2019	857.57	4 - 6 ft	180-95006-3	Excavated	0.051	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.025 J	0.026 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-6-8	8/29/2019	857.57	6 - 8 ft	180-95006-3	Not Excavated	0.059	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.031 J	0.028 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-8-10	8/29/2019	857.57	8 - 10 ft	180-95006-3	Not Excavated	0.02	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.01 J	0.01 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-10-12	8/29/2019	857.57	10 - 12 ft	180-95006-3	Not Excavated	0.036	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.019 J	0.017 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-12-14	8/29/2019	857.57	12 - 14 ft	180-95024-1	Not Excavated	0.022	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.011 J	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	0.024	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.012 J	0.012 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated	1.62	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.71	0.91	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	1.61	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.85	0.76	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-2-4	8/29/2019	857.45	2 - 4 ft	180-95024-1	Not Excavated	0.197	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.043 J	0.088 J	0.066 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-4-6	8/29/2019	857.45	4 - 6 ft	180-95024-1	Not Excavated	0.0273	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0083 J	0.019 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-6-8	8/29/2019	857.45	6 - 8 ft	180-95024-1	Not Excavated	0.0069	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0069 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-8-10	8/29/2019	857.45	8 - 10 ft	180-95024-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-10-12	8/29/2019	857.45	10 - 12 ft	180-95024-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-12-14	8/29/2019	857.45	12 - 14 ft	180-95024-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated	0.343	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.18 J	0.12 J	0.043 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-4-6	1/14/2020	856.70	4 - 6 ft	180-101038-1	Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-6-8	1/14/2020	856.70	6 - 8 ft	180-101038-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-8-10	1/14/2020	856.70	8 - 10 ft	180-101038-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-10-12	1/14/2020	856.70	10 - 12 ft	180-101038-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-2-4	1/14/2020	856.85	2 - 4 ft	180-101038-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 UJ	< 0.0055 UJ	< 0.0052 UJ	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-4-6	1/14/2020	856.85	4 - 6 ft	180-101038-2	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-6-8	1/14/2020	856.85	6 - 8 ft	180-101038-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-8-10	1/14/2020	856.85	8 - 10 ft	180-101038-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-10-12	1/14/2020	856.85	10 - 12 ft	180-101038-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B319	SSHS-B319-SUB-4-6	3/2/2016	857.02	4 - 6 ft	180-52664-1	Excavated	7.59	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	5.9 J	1.4 J	0.29 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B319	SSHS-B319-SUB-8-10	3/2/2016	857.02	8 - 10 ft	180-52664-1	Not Excavated	3.75	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	2.9 J	0.7 J	0.15 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B320	SSHS-B320-SUB-4-6	3/2/2016	856.57	4 - 6 ft	180-52664-1	Excavated	3.36	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	2.2 J	1 J	0.16 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B321	SSHS-B321-SUB-4-6	3/3/2016	854.91	4 - 6 ft	180-52706-1	Excavated	27820	< 43 U	< 69 U	< 24 U	< 35 U	22000 J	5100 J	720 J	< 29 U	< 18 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-2-4	8/30/2019	855.06	2 - 4 ft	180-95050-1	Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-4-6	8/30/2019	855.06	4 - 6 ft	180-95050-2	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-6-8	8/30/2019	855.06	6 - 8 ft	180-95050-2	Not Excavated	ND	< 0.0056 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-8-10	8/30/2019	855.06	8 - 10 ft	180-95050-2	Not Excavated	0.057	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.03 J	0.027 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-10-12	8/30/2019	855.06	10 - 12 ft	180-95050-2	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B322	SSHS-B322-SUB-8-10	3/2/2016	857.31	8 - 10 ft	180-52664-1	Not Excavated	2.23	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	1.6 J	0.49 J	0.14 J	< 0.0058 U	< 0.0035 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-2-4	9/4/2019	857.44	2 - 4 ft	180-95165-3	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-4-6	9/4/2019	857.44	4 - 6 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-6-8	9/4/2019	857.44	6 - 8 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-8-10	9/4/2019	857.44	8 - 10 ft	180-95165-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-10-12	9/4/2019	857.44	10 - 12 ft	180-95165-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-12-14	9/4/2019	857.44	12 - 14 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-2-4	9/4/2019	857.92	2 - 4 ft	180-95165-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-4-6	9/4/2019	857.92	4 - 6 ft	180-95165-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-6-8	9/4/2019	857.92	6 - 8 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-8-10	9/4/2019	857.92	8 - 10 ft	180-95165-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-10-12	9/4/2019	857.92	10 - 12 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-12-14	9/4/2019	857.92	12 - 14 ft	180-95165-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-2-4	8/30/2019	858.28	2 - 4 ft	180-95047-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-4-6	8/30/2019	858.28	4 - 6 ft	180-95047-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-6-8	8/30/2019	858.28	6 - 8 ft	180-95047-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-8-10	8/30/2019	858.28	8 - 10 ft	180-95047-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-10-12	8/30/2019	858.28	10 - 12 ft	180-95047-2	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-12-14	8/30/2019	858.28	12 - 14 ft	180-95047-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-14-16	8/30/2019	858.28	14 - 16 ft	180-95047-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-2-4	8/29/2019	858.27	2 - 4 ft	180-95006-2	Not Excavated	1.208	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.72 J	0.44 J	0.048 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-4-6	8/29/2019	858.27	4 - 6 ft	180-95006-2	Not Excavated	1.13	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.77 J	0.3 J	0.06 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-6-8	8/29/2019	858.27	6 - 8 ft	180-95006-2	Not Excavated	0.937	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.57 J	0.33 J	0.037 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-8-10	8/29/2019	858.27	8 - 10 ft	180-95006-2	Not Excavated	0.039	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.025 J	0.014 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-10-12	8/29/2019	858.27	10 - 12 ft	180-95006-2	Not Excavated	0.0076	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	0.0076 J	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-12-14	8/29/2019	858.27	12 - 14 ft	180-95006-2	Not Excavated	0.052	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.032 J	0.02 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	0.043	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.028 J	0.015 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-2-4	8/30/2019	858.38	2 - 4 ft	180-95050-1	Not Excavated	0.31	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.12 J	0.19 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-4-6	8/30/2019	858.38	4 - 6 ft	180-95050-1	Not Excavated	0.109	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.05 J	0.059 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-6-8	8/30/2019	858.38	6 - 8 ft	180-95050-1	Not Excavated	0.015	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.015 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-8-10	8/30/2019	858.38	8 - 10 ft	180-95050-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-10-12	8/30/2019	858.38	10 - 12 ft	180-95050-1	Not Excavated	0.037	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.021 J	0.016 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-12-14	8/30/2019	858.38	12 - 14 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16	8/30/2019	858.38	14 - 16 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3229	SSHS-B3229-SUB-2-4	12/20/2019	855.55	2 - 4 ft	180-100362-1	Not Excavated	0.23	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.13 J	0.07 J	0.03 J	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B323	SSHS-B323-SUB-8-10	3/2/2016	856.59	8 - 10 ft	180-52664-1	Excavated	5.4	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	4.3 J	0.91 J	0.19 J	< 0.0059 U	< 0.0035 U
Northern Athletic Field	SSHS-B3230	SSHS-B3230-SUB-2-4	12/20/2019	855.45	2 - 4 ft	180-100362-1	Not Excavated	0.193	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.044 J	0.081 J	0.068 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3231	SSHS-B3231-SUB-2-4	12/20/2019	855.72	2 - 4 ft	180-100362-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated	1.64	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.89 J	0.53 J	0.22 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated	1.05	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.53 J	0.36 J	0.16 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Excavated	5.33	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	2.9 J	1.7 J	0.73 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-6-8	12/20/2019	855.71	6 - 8 ft	180-100362-1	Not Excavated	0.357	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.18 J	0.12 J	0.057 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-8-10	12/20/2019	855.71	8 - 10 ft	180-100362-1	Not Excavated	0.85	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.39 J	0.34 J	0.12 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3234	SSHS-B3234-SUB-2-4	12/20/2019	855.92	2 - 4 ft	180-100362-1	Excavated	1.55	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.78 J	0.58 J	0.19 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-2-4	12/20/2019	856.44	2 - 4 ft	180-100362-1	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-6-8	12/20/2019	856.44	6 - 8 ft	180-100362-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-8-10	12/20/2019	856.44	8 - 10 ft	180-100362-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-2-4	12/20/2019	856.32	2 - 4 ft	180-100362-1	Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-6-8	12/20/2019	856.32	6 - 8 ft	180-100362-1	Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-8-10	12/20/2019	856.32	8 - 10 ft	180-100362-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3237	SSHS-B3237-SUB-2-4	12/20/2019	856.01	2 - 4 ft	180-100361-1	Not Excavated	0.51	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.39 J	0.12 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3238	SSHS-B3238-SUB-2-4	12/20/2019	855.23	2 - 4 ft	180-100361-1	Not Excavated	0.082	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.06 J	0.022 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3239	SSHS-B3239-SUB-2-4	12/20/2019	855.81	2 - 4 ft	180-100362-1	Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3240	SSHS-B3240-SUB-2-4	12/20/2019	856.04	2 - 4 ft	180-100362-1	Not Excavated	0.083	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.05 J	0.033 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3241	SSHS-B3241-SUB-2-4	12/19/2019	856.35	2 - 4 ft	180-100363-3	Not Excavated	0.045	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.035 J	0.01 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-2-4	12/19/2019	856.23	2 - 4 ft	180-100363-2	Not Excavated	0.151	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.072 J	0.068 J	0.011 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-4-6	12/19/2019	856.23	4 - 6 ft	180-100363-2	Not Excavated	0.045	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.018 J	0.027 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-2-4	12/19/2019	857.57	2 - 4 ft	180-100363-3	Excavated	1.48	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.92 J	0.45 J	0.11 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3248	SSHS-B3248-SUB-2-4	12/19/2019	857.19	2 - 4 ft	180-100363-2	Excavated	0.022	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.022	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-2-4	12/19/2019	857.44	2 - 4 ft	180-100363-1	Excavated	0.39	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.13 J	0.26 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B325	SSHS-B325-SUB-2-4	3/1/2016	855.99	2 - 4 ft	180-52611-1	Excavated	0.8	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.26 J	0.38 J	0.16 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	2 - 4 ft	180-100363-1	Not Excavated	3.17	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	2.1 J	0.97 J	0.1 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3251	SSHS-B3251-SUB-2-4	12/19/2019	858.34	2 - 4 ft	180-100363-2	Not Excavated	0.58	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.42 J	0.16 J	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	2 - 4 ft	180-100363-1	Not Excavated	0.4	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.21 J	0.19 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	2 - 4 ft	180-100363-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-2-4	12/19/2019	856.34	2 - 4 ft	180-100363-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	2 - 4 ft	180-100363-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-2-4	12/19/2019	858.14	2 - 4 ft	180-100363-2	Excavated	0.0302	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.0082 J	0.022 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3258	SSHS-B3258-SUB-2-4	12/18/2019	856.41	2 - 4 ft	180-100380-1	Not Excavated	0.0254	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.016 J	0.0094 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	2 - 4 ft	180-100363-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B326	SSHS-B326-SUB-2-4	3/2/2016	854.91	2 - 4 ft	180-52664-1	Excavated	84.8	< 0.17 U	< 0.27 U	< 0.092 U	< 0.14 U	50 J	27 J	7.8 J	< 0.11 U	< 0.069 U
Football Field	SSHS-B326	SSHS-B326-SUB-4-6	3/2/2016	854.91	4 - 6 ft	180-52664-1	Excavated	4.02	< 0.0083 U,F2,F1	< 0.013 U	< 0.0045 U	< 0.0067 U	2.5 J	1.2 J	0.32 J	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	854.30	14 - 16 ft	180-100380-1	Not Excavated	266	< 2.9 U	< 3.2 U	< 2.2 U	< 1.3 U	200 J	66 J	< 2.6 U	< 3.2 U	< 1.2 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-12-14	12/18/2019	854.04	12 - 14 ft	180-100380-1	Excavated	612	< 0.57 U	< 0.62 U	< 0.43 U	< 0.26 U	430 J	160 J	22 J	< 0.62 U	< 0.24 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-14-16	12/18/2019	854.04	14 - 16 ft	180-100380-1	Not Excavated	1.094	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.79 J	0.27 J	0.034 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-2-4	1/22/2021	854.14	2 - 4 ft	1801163651	Excavated	0.41	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.22	0.19	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-4-6	1/22/2021	854.14	4 - 6 ft	1801163651	Excavated	1.15	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.84	0.31	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-6-8	1/22/2021	854.14	6 - 8 ft	1801163651	Excavated	0.383	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.3	0.083 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	132.2	< 0.57 U	< 0.62 U	< 0.43 U	< 0.26 U	100	30	2.2	< 0.61 U	< 0.23 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	117	< 0.59 U	< 0.64 U	< 0.44 U	< 0.26 U	86	29	2	< 0.63 U	< 0.24 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	306.7	< 2.9 U	< 3.2 U	< 2.2 U	< 1.3 U	230	71	5.7 JT	< 3.1 U	< 1.2 U
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-12-14	12/18/2019	853.76	12 - 14 ft	180-100380-1	Not Excavated	25.06	< 0.059 U	< 0.064 U	< 0.044 U	< 0.027 U	17 J	7.2 J	0.86 J	< 0.064 U	< 0.024 U
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-14-16	12/18/2019	853.76	14 - 16 ft	180-100380-2	Not Excavated	156	< 0.59 U	< 0.64 U	< 0.44 U	< 0.27 U	92 J	57 J	7 J	< 0.64 U	< 0.24 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-10-12	1/21/2021	853.76	10 - 12 ft	180-116310-1	Excavated	17.61	< 0.057 U	< 0.062 U	< 0.042 U	< 0.026 U	13 J	3.8 J	0.81 J	< 0.061 U	< 0.023 U
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-12-14	12/18/2019	854.51	12 - 14 ft	180-100380-2	Not Excavated	1.364	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.85 J	0.45 J	0.064 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-14-16	12/18/2019	854.51	14 - 16 ft	180-100380-1	Not Excavated	0.672	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.42 J	0.21 J	0.042 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-12-14	12/18/2019	854.73	12 - 14 ft	180-100380-1	Excavated	0.66	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.46 J	0.2 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-14-16	12/18/2019	854.73	14 - 16 ft	180-100380-1	Not Excavated	0.472	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.26 J	0.16 J	0.052 J	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B327	SSHS-B327-SUB-2-4	3/3/2016	855.58	2 - 4 ft	180-52706-1	Excavated	1.121	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.81 J	0.28 J	0.031 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B327	SSHS-B327-SUB-4-6	3/3/2016	855.58	4 - 6 ft	180-52706-1	Excavated	0.249	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.19 J	0.059 J	< 0.0068 U	< 0.0062 U	< 0.0037 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-2-4	12/18/2019	855.88	2 - 4 ft	180-100380-1	Not Excavated	ND	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	< 0.0053 U	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-2-4	12/18/2019	855.39	2 - 4 ft	180-100380-1	Not Excavated	0.059	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.043 J	0.016 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	2 - 4 ft	180-100380-1	Not Excavated	0.122	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.034 J	0.052 J	0.036 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-2-4	12/18/2019	856.15	2 - 4 ft	180-100380-2	Not Excavated	0.076	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.052 J	0.024 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B328	SSHS-B328-SUB-2-4	3/3/2016	855.04	2 - 4 ft	180-52706-1	Excavated	93.2	< 0.41 U	< 0.65 U	< 0.23 U	< 0.33 U	64 J	25 J	4.2 J	< 0.28 U	< 0.17 U
Football Field	SSHS-B328	SSHS-B328-SUB-4-6	3/3/2016	855.04	4 - 6 ft	180-52706-1	Excavated	1.86	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.2 J	0.59 J	0.07 J	< 0.0059 U	< 0.0036 U
Northern Athletic Field	SSHS-B3287	SSHS-B3287-SUB-2-4	12/17/2019	857.65	2 - 4 ft	180-100148-6	Excavated	0.055	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.04 J	0.015 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	2 - 4 ft	180-100148-6	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.026 J	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3289	SSHS-B3289-SUB-2-4	12/17/2019	857.03	2 - 4 ft	180-100148-6	Not Excavated	0.039	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.013 J	0.016 J	0.01 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B329	SSHS-B329-SUB-2-4	3/3/2016	855.91	2 - 4 ft	180-52706-1	Excavated	0.014	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.014 J	< 0.0068 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B329	SSHS-B329-SUB-4-6	3/3/2016	855.91	4 - 6 ft	180-52706-1	Excavated	0.062	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	0.049 J	0.013 J	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B329	SSHS-B329-SUB-6-8	3/3/2016	855.91	6 - 8 ft	180-52706-1	Excavated	ND	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	< 0.0045 U	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B329	SSHS-B329-SUB-8-10	3/3/2016	855.91	8 - 10 ft	180-52706-1	Excavated	0.132	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.11 J	0.022 J	< 0.0063 U	< 0.0057 U	< 0.0034 U
Northern Athletic Field	SSHS-B3290	SSHS-B3290-SUB-2-4	12/17/2019	857.23	2 - 4 ft	180-100148-6	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-2-4	12/17/2019	857.15	2 - 4 ft	180-100148-5	Excavated	0.0198	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.01 J	0.0098 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3294	SSHS-B3294-SUB-2-4	12/17/2019	856.87	2 - 4 ft	180-100148-5	Excavated	0.117	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.071 J	0.033 J	0.013 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-2-4	12/17/2019	857.20	2 - 4 ft	180-100148-5	Excavated	0.13	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.028 J	0.058 J	0.044 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3299	SSHS-B3299-SUB-2-4	12/17/2019	857.10	2 - 4 ft	180-100148-4	Excavated	0.325	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.21	0.07	0.045	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B329A	SSHS-B329A-SUB-10-12	7/11/2017	855.91	10 - 12 ft	180-68095-1	Excavated	ND	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	< 0.009 U	< 0.0083 U	< 0.013 U	< 0.014 U	< 0.0057 U
Football Field	SSHS-B330	SSHS-B330-SUB-2-4	3/9/2016	856.86	2 - 4 ft	180-52876-1	Excavated	11.88	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	8.5 J	3.1 J	0.28 J	< 0.029 U	< 0.017 U
Football Field	SSHS-B330	SSHS-B330-SUB-4-6	3/9/2016	856.86	4 - 6 ft	180-52876-1	Excavated	1.95	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	1.2 J	0.59 J	0.16 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B330	SSHS-B330-SUB-6-8	3/9/2016	856.86	6 - 8 ft	180-52876-1	Excavated	42.3	< 0.17 U	< 0.27 U	< 0.094 U	< 0.14 U	30 J	11 J	1.3 J	< 0.12 U	< 0.07 U
Football Field	SSHS-B330	SSHS-B330-SUB-8-10	3/9/2016	856.86	8 - 10 ft	180-52876-1	Excavated	42.1	< 0.17 U	< 0.27 U	< 0.094 U	< 0.14 U	31 J	10 J	1.1 J	< 0.12 U	< 0.07 U
Football Field	SSHS-B330	SSHS-B330B-SUB-10-12	3/9/2016	856.86	10 - 12 ft	180-52876-2	Excavated	267.4	< 0.87 U	< 1.4 U	< 0.47 U	< 0.7 U	180 J	78 J	9.4 J	< 0.59 U	< 0.35 U
Football Field	SSHS-B330	SSHS-B330B-SUB-12-14	3/9/2016	856.86	12 - 14 ft	180-52876-2	Excavated	3.85	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0067 U	2.2 J	1.4 J	0.25 J	< 0.0057 U	< 0.0034 U
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-2-4	12/17/2019	856.38	2 - 4 ft	180-100148-3	Excavated	0.029	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.016 J	0.013 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-2-4	12/17/2019	857.04	2 - 4 ft	180-100148-3	Excavated	0.5	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.17 J	0.21 J	0.12 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B330A	SSHS-B330A-SUB-6-8	7/13/2017	856.86	6 - 8 ft	180-68203-1	Excavated	4.69	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	2.9	1.6	0.19	< 0.013 U	< 0.0055 U
Football Field	SSHS-B330A	SSHS-B330A-SUB-8-10	7/13/2017	856.86	8 - 10 ft	180-68203-1	Excavated	2.627	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	1.7	0.83	0.097	< 0.013 U	< 0.0055 U
Football Field	SSHS-B331	SSHS-B331-SUB-2-4	3/3/2016	855.61	2 - 4 ft	180-52706-1	Excavated	0.613	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.36 J	0.2 J	0.053 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B331	PS-FD-9	3/3/2016	855.61	4 - 6 ft	180-52706-1	Excavated	1.9	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.51 J	0.96 J	0.43 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B331	SSHS-B331-SUB-4-6	3/3/2016	855.61	4 - 6 ft	180-52706-1	Excavated	2.52	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.62 J	1.3 J	0.6 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B331	SSHS-B331-SUB-6-8	3/3/2016	855.61	6 - 8 ft	180-52706-1	Excavated	3.35	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.9 J	1.8 J	0.65 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B331	SSHS-B331-SUB-8-10	3/3/2016	855.61	8 - 10 ft	180-52706-1	Excavated	0.294	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	0.12 J	0.13 J	0.044 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B332	SSHS-B332-SUB-4-6	3/3/2016	855.09	4 - 6 ft	180-52706-1	Excavated	0.381	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	0.25 J	0.11 J	0.021 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B332	SSHS-B332-SUB-6-8	3/3/2016	855.09	6 - 8 ft	180-52706-1	Excavated	0.01	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.01 J	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B332	SSHS-B332-SUB-8-10	3/3/2016	855.09	8 - 10 ft	180-52706-1	Excavated	0.313	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.2 J	0.095 J	0.018 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B333	SSHS-B333-SUB-2-4	3/3/2016	856.15	2 - 4 ft	180-52706-1	Excavated	4.78	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	2.5 J	1.8 J	0.48 J	< 0.0061 U	< 0.0037 U
Football Field	SSHS-B333	SSHS-B333-SUB-4-6	3/3/2016	856.15	4 - 6 ft	180-52706-1	Excavated	60.2	< 0.18 U	< 0.28 U	< 0.098 U	< 0.14 U	43 J	16 J	1.2 J	< 0.12 U	< 0.073 U
Football Field	SSHS-B333	SSHS-B333-SUB-6-8	3/3/2016	856.15	6 - 8 ft	180-52706-1	Excavated	242	< 0.86 U	< 1.4 U	< 0.47 U	< 0.7 U	180 J	52 J	10 J	< 0.59 U	< 0.35 U
Football Field	SSHS-B333	SSHS-B333-SUB-8-10	3/3/2016	856.15	8 - 10 ft	180-52706-2	Excavated	78	< 0.44 U	< 0.7 U	< 0.24 U	< 0.36 U	57 J	19 J	2 J	< 0.3 U	< 0.18 U
Football Field	SSHS-B334	PS-FD-10	3/3/2016	856.23	2 - 4 ft	180-52706-1	Excavated	4.64	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.007 U	2.5 J	1.7 J	0.44 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B334	SSHS-B334-SUB-2-4	3/3/2016	856.23	2 - 4 ft	180-52706-1	Excavated	3.23	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1.8 J	1.1 J	0.33 J	< 0.0056 U	< 0.0033 U
Football Field	SSHS-B334	SSHS-B334-SUB-4-6	3/3/2016	856.23	4 - 6 ft	180-52706-1	Excavated	1.31	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.72 J	0.47 J	0.12 J	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B334	SSHS-B334-SUB-6-8	3/3/2016	856.23	6 - 8 ft	180-52706-1	Excavated	0.022	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	0.022	< 0.0067 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B334	SSHS-B334-SUB-8-10	3/3/2016	856.23	8 - 10 ft	180-52706-1	Excavated	1.63	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1 J	0.52 J	0.11 J	< 0.0056 U	< 0.0033 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated	0.021	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.013 J	0.008 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated	0.041	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.03 J	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated	0.059	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.034 J	0.025 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	0.0074	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0074 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B335	SSHS-B335-SUB-2-4	3/3/2016	856.16	2 - 4 ft	180-52706-1	Excavated	7.16	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	5.1 J	1.7 J	0.36 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B335	SSHS-B335-SUB-4-6	3/3/2016	856.16	4 - 6 ft	180-52706-1	Excavated	1.24	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.61 J	0.47 J	0.16 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B335	PS-FD-11	3/3/2016	856.16	4 - 6 ft	180-52706-1	Excavated	0.851	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.41 J	0.37 J	0.071 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B335	SSHS-B335-SUB-8-10	3/3/2016	856.16	8 - 10 ft	180-52706-1	Not Excavated	4.88	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	2.3 J	2.2 J	0.38 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B336	SSHS-B336-SUB-2-4	3/3/2016	856.00	2 - 4 ft	180-52706-1	Excavated	3.14	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	2 J	0.94 J	0.2 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B336	SSHS-B336-SUB-4-6	3/3/2016	856.00	4 - 6 ft	180-52706-1	Excavated	0.298	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	0.19 J	0.09 J	0.018 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B336	SSHS-B336-SUB-6-8	3/3/2016	856.00	6 - 8 ft	180-52706-1	Excavated	0.046	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.031 J	0.015 J	< 0.0065 U	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B336	SSHS-B336-SUB-8-10	3/3/2016	856.00	8 - 10 ft	180-52706-1	Not Excavated	0.225	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.15 J	0.064 J	0.011 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B336A	SSHS-B336A-SUB-2-4	7/10/2017	856.00	2 - 4 ft	180-68038-1	Excavated	13.69	< 0.048 U	< 0.047 U	< 0.036 U	< 0.073 U	8.9 J	4.3 J	0.49 J	< 0.066 U	< 0.028 U
Football Field	SSHS-B337	SSHS-B337-SUB-4-6	3/9/2016	856.65	4 - 6 ft	180-52876-1	Excavated	0.027	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.027	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B337	SSHS-B337-SUB-8-10	3/9/2016	856.65	8 - 10 ft	180-52876-1	Not Excavated	0.09	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.064 J	0.026 J	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B338	SSHS-B338-SUB-2-4	3/9/2016	855.82	2 - 4 ft	180-52876-1	Excavated	13.82	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	10 J	3.5 J	0.32 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B338	SSHS-B338-SUB-4-6	3/9/2016	855.82	4 - 6 ft	180-52876-1	Excavated	3.31	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0067 U	2.3 J	0.89 J	0.12 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B338	SSHS-B338-SUB-6-8	3/9/2016	855.82	6 - 8 ft	180-52876-1	Excavated	21.11	< 0.087 U	< 0.14 U	< 0.048 U	< 0.07 U	15 J	5.7 J	0.41 J	< 0.059 U	< 0.036 U
Football Field	SSHS-B338	SSHS-B338-SUB-8-10	3/9/2016	855.82	8 - 10 ft	180-52876-1	Excavated	2.76	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	1.8 J	0.86 J	0.1 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B339	SSHS-B339-SUB-2-4	3/9/2016	856.05	2 - 4 ft	180-52876-1	Excavated	9.17	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	6.6 J	2.4 J	0.17 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B340	SSHS-B340-SUB-2-4	3/9/2016	855.78	2 - 4 ft	180-52876-1	Excavated	204.6	< 0.44 U	< 0.69 U	< 0.24 U	< 0.35 U	140 J	58 J	6.6 J	< 0.29 U	< 0.18 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B341	SSHS-B341-SUB-8-10	3/3/2016	855.99	8 - 10 ft	180-52706-1	Excavated	7.14	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	4.8 J	2.1 J	0.24 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B342	PS-FD-7	3/3/2016	855.80	8 - 10 ft	180-52706-1	Excavated	10	< 0.043 U	< 0.069 U	< 0.024 U	< 0.035 U	7.3 J	2.5 J	0.2 J	< 0.029 U	< 0.018 U
Football Field	SSHS-B342	SSHS-B342-SUB-8-10	3/3/2016	855.80	8 - 10 ft	180-52706-1	Excavated	5.82	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	4.4 J	1.3 J	0.12 J	< 0.0059 U	< 0.0036 U
Football Field	SSHS-B344	SSHS-B344-SUB-4-6	3/3/2016	855.69	4 - 6 ft	180-52706-1	Excavated	3.7	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	2.6 J	0.96 J	0.14 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B344	PS-FD-8	3/3/2016	855.69	6 - 8 ft	180-52706-1	Excavated	0.016	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.016 J	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B344	SSHS-B344-SUB-6-8	3/3/2016	855.69	6 - 8 ft	180-52706-1	Excavated	0.013	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.013 J	< 0.0072 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B344	SSHS-B344-SUB-8-10	3/3/2016	855.69	8 - 10 ft	180-52706-1	Excavated	1.839	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	1.3 J	0.47 J	0.069 J	< 0.0058 U	< 0.0035 U
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	42.58	< 0.058 U	< 0.063 U	< 0.043 U	< 0.026 U	32	9.8	0.78	< 0.062 U	< 0.024 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	27.85	< 0.057 U	< 0.062 U	< 0.042 U	< 0.025 U	21	6.3	0.55	< 0.061 U	< 0.023 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	30.2	< 0.057 UT	< 0.062 U	< 0.042 U	< 0.025 U	21	8.8	0.4	< 0.061 U	< 0.023 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated	4.38	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	3.4	0.81	0.17	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-10-12	1/23/2021	853.86	10 - 12 ft	180-116404-1	Not Excavated	2.988	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	2.2 J	0.73 J	0.058 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-12-14	1/23/2021	853.86	12 - 14 ft	180-116404-1	Not Excavated	2.735	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2 J	0.69 J	0.045 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-14-16	1/23/2021	853.86	14 - 16 ft	180-116404-1	Not Excavated	17.05	< 0.059 U	< 0.064 U	< 0.044 U	< 0.027 U	13 J	3.7 J	0.35 J	< 0.064 U	< 0.024 U
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	7/28/2020	855.34	2 - 4 ft	180-108872-2	Excavated	5.84	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.4 J	2.2 J	0.24 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3457	SSHS-B3457-SUB-2-4	7/28/2020	855.82	2 - 4 ft	180-108872-2	Excavated	0.616	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.3 J	0.25 J	0.066 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3458	DUP10	7/28/2020	856.14	2 - 4 ft	180-108872-2	Excavated	0.534	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.37 J	0.14 J	0.024 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3458	SSHS-B3458-SUB-2-4	7/28/2020	856.14	2 - 4 ft	180-108872-2	Excavated	0.1863	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.13 J	0.047 J	0.0093 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated	0.473	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.078 J	0.31 J	0.085 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-4-6	7/27/2020	856.30	4 - 6 ft	180-108826-2	Excavated	0.201	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.095 J	0.085 J	0.021 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-6-8	7/27/2020	856.30	6 - 8 ft	180-108826-2	Not Excavated	0.248	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.12 J	0.1 J	0.028 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-8-10	7/27/2020	856.30	8 - 10 ft	180-108826-2	Not Excavated	0.245	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.12 J	0.1 J	0.025 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-10-12	7/27/2020	856.30	10 - 12 ft	180-108826-2	Not Excavated	0.113	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056 J	0.047 J	0.01 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	0.132	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.06 J	0.057 J	0.015 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3460	SSHS-B3460-SUB-2-4	7/28/2020	855.83	2 - 4 ft	180-108872-2	Excavated	0.044	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.034 J	0.01 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated	2.48	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.67 J	1.5 J	0.31 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	0.849	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.52 J	0.28 J	0.049 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-6-8	7/27/2020	856.51	6 - 8 ft	180-108826-2	Not Excavated	1.336	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.8 J	0.45 J	0.086 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-8-10	7/27/2020	856.51	8 - 10 ft	180-108826-2	Not Excavated	0.4	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.24 J	0.16 J		< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	0.273	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.16 J	0.096 J	0.017 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	0.509	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.29 J	0.18 J	0.039 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3462	SSHS-B3462-SUB-2-4	7/28/2020	855.77	2 - 4 ft	180-108872-2	Excavated	0.2	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.12 J	0.068 J	0.012 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3463	SSHS-B3463-SUB-2-4	7/28/2020	856.64	2 - 4 ft	180-108872-2	Excavated	0.94	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.32 J	0.48 J	0.14 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	0.665	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.36 J	0.25 J	0.055 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	0.36	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.21 J	0.15 J		< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-6-8	7/27/2020	856.28	6 - 8 ft	180-108826-2	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.023 J	0.014 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	0.0914	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.052 J	0.031 J	0.0084 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3465	DUP12	7/28/2020	855.46	2 - 4 ft	180-108872-2	Excavated	0.897	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.43 J	0.38 J	0.087 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3465	SSHS-B3465-SUB-2-4	7/28/2020	855.46	2 - 4 ft	180-108872-2	Excavated	1.34	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.71 J	0.51 J	0.12 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3466	SSHS-B3466-SUB-2-4	7/28/2020	855.76	2 - 4 ft	180-108872-2	Excavated	1.967	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.4 J	0.49 J	0.077 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated	1.11	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.54 J	0.45 J	0.12 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3468	DUP13	7/28/2020	855.93	2 - 4 ft	180-108872-2	Excavated	0.16	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.08 J	0.061 J	0.019 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3468	SSHS-B3468-SUB-2-4	7/28/2020	855.93	2 - 4 ft	180-108872-2	Excavated	0.353	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.22 J	0.11 J	0.023 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3469	SSHS-B3469-SUB-2-4	7/28/2020	855.50	2 - 4 ft	180-108872-2	Excavated	0.546	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.28 J	0.22 J	0.046 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3470	SSHS-B3470-SUB-2-4	7/28/2020	855.73	2 - 4 ft	180-108872-2	Excavated	5.55	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	4.1 J	1.3 J	0.15 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3471	SSHS-B3471-SUB-2-4	7/28/2020	856.03	2 - 4 ft	180-108872-2	Excavated	1.42	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.77 J	0.45 J	0.2 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-4-6	7/27/2020	855.50	4 - 6 ft	180-108826-2	Not Excavated	0.1475	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.092 J	0.047 J	0.0085 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-6-8	7/27/2020	855.50	6 - 8 ft	180-108826-2	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-8-10	7/27/2020	855.50	8 - 10 ft	180-108826-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	12.43	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	7.7 J	4.1 J	0.63 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-4-6	7/27/2020	855.34	4 - 6 ft	180-108826-2	Excavated	2.86	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.2 J	1.4 J	0.26 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-6-8	7/27/2020	855.34	6 - 8 ft	180-108826-2	Not Excavated	0.04	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.023 J	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	5.36	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	3.4 J	1.7 J	0.26 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	0.061	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022 J	0.039 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	0.167	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.06 J	0.077 J	0.03 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	2 - 4 ft	1801164621	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	2 - 4 ft	180-116462-3	Not Excavated	0.145	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.099 J	0.046 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	4 - 6 ft	180-116462-3	Not Excavated	0.057	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.036 J	0.021 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-10-12	1/21/2021	854.61	10 - 12 ft	180-116310-1	Excavated	0.544	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.4 J	0.12 J	0.024 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-12-14	1/21/2021	854.61	12 - 14 ft	180-116310-1	Not Excavated	1.308	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.97 J	0.28 J	0.058 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-14-16	1/21/2021	854.61	14 - 16 ft	180-116310-1	Not Excavated	1.771	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.3 J	0.39 J	0.081 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	0.087	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.056 J	0.031 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	1/14/2021	858.31	4 - 6 ft	180-116002-2	Not Excavated	0.0489	0.0058	0.0063	0.0043	0.0026	0.011	0.0053	0.005	0.0062	0.0024
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	0.113	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.077 J	0.036 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	4 - 6 ft	180-116002-2	Not Excavated	0.0587	0.0062	0.0067	0.0046	0.0028	0.018	0.0057	0.0054	0.0067	0.0026
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	0.05	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.031	0.019	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	0.6	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.43	0.17	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3500A	SSHS-B3500-SUB-2-4	1/25/2021	855.38	2 - 4 ft	180-116404-3	Not Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3501A	SSHS-B3501-SUB-2-4	1/25/2021	855.77	2 - 4 ft	180-116404-3	Not Excavated	0.093	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.065 J	0.028 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-2-4	1/25/2021	855.86	2 - 4 ft	180-116404-3	Not Excavated	0.59	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.42 J	0.17 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3505	SSHS-B3505-SUB-2-4	8/31/2020	853.31	2 - 4 ft	180-110264-2	Excavated	0.6	< 0.0068 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.37 J	0.23 J		< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3506	SSHS-B3506-SUB-2-4	8/31/2020	856.17	2 - 4 ft	180-110264-2	Excavated	0.263	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.14 J	0.099 J	0.024 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3508	SSHS-B3508-SUB-2-4	8/31/2020	856.03	2 - 4 ft	180-110264-2	Excavated	4.8	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	3.4 J	1.4 J		< 0.0066 U	< 0.0025 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3509	SSHS-B3509-SUB-2-4	8/31/2020	855.93	2 - 4 ft	180-110264-2	Excavated	0.437	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.23 J	0.16 J	0.047 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3511	DUP-18	8/31/2020	855.66	2 - 4 ft	180-110264-1	Excavated	0.58	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12 J	0.35 J	0.11 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3511	SSHS-B3511-SUB-2-4	8/31/2020	855.66	2 - 4 ft	180-110264-1	Excavated	0.9	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12 J	0.6 J	0.18 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3512	SSHS-B3512-SUB-2-4	8/31/2020	855.72	2 - 4 ft	180-110264-1	Excavated	0.341	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.19 J	0.12 J	0.031 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3521	SSHS-B3521-SUB-6-8	1/25/2021	855.79	6 - 8 ft	180-116404-1	Not Excavated	0.683	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.36 J	0.26 J	0.063 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3521	SSHS-B3521-SUB-8-10	1/25/2021	855.79	8 - 10 ft	180-116404-3	Not Excavated	0.177	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.1 J	0.077 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3526	DUP-7	6/22/2021	855.55	8 - 10 ft	180-123547-1	Not Excavated	2.83	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	2.1 J	0.73 J	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3526	SSHS-B3526-SUB-8-10	6/22/2021	855.55	8 - 10 ft	180-123547-1	Not Excavated	2.02	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.6 J	0.42 J		< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3527	DUP-8	6/22/2021	855.96	8 - 10 ft	180-123547-1	Not Excavated	0.055	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.044 J	0.011 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3527	SSHS-B3527-SUB-8-10	6/22/2021	855.96	8 - 10 ft	180-123547-1	Not Excavated	0.082	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.066 J	0.016 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-2-4	1/20/2021	854.07	2 - 4 ft	1801162471	Excavated	21.94	< 0.065 U	< 0.071 U	< 0.049 U	< 0.029 U	16	5.5	0.44	< 0.07 U	< 0.027 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-4-6	1/20/2021	854.07	4 - 6 ft	1801162471	Excavated	3.409	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	2.6	0.73	0.079	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-6-8	1/20/2021	854.07	6 - 8 ft	1801162471	Excavated	2.161	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.6	0.51	0.051	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	DUP-12	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	1.814	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.3	0.46	0.054	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	1.032	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.74	0.27	0.022	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	0.38	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.28	0.1	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	1.748	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	1.3	0.41	0.038	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated	1.646	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.2	0.41	0.036	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	14 - 16 ft	180-115999-1	Not Excavated	2.624	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.9 J	0.69 J	0.034 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-8-10	1/12/2021	855.28	8 - 10 ft	180-115861-1	Excavated	166.7	< 0.61 U	< 0.66 U	< 0.46 U	< 0.27 U	120 J	41 J	5.7 J	< 0.66 U	< 0.25 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-10-12	1/12/2021	855.28	10 - 12 ft	180-115861-1	Excavated	1.465	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1 J	0.4 J	0.065 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-12-14	1/12/2021	855.28	12 - 14 ft	180-115861-1	Not Excavated	6.06	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	4.2 J	1.6 J	0.26 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-14-16	1/12/2021	855.28	14 - 16 ft	180-115861-1	Not Excavated	0.864	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.58 J	0.24 J	0.044 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-8-10	1/12/2021	855.39	8 - 10 ft	180-115861-1	Excavated	19.55	< 0.3 U	< 0.33 U	< 0.23 U	< 0.14 U	12 J	6.7 J	0.85 J	< 0.33 U	< 0.12 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-10-12	1/12/2021	855.39	10 - 12 ft	180-115861-1	Excavated	3.54	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.2 J	1.2 J	0.14 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-12-14	1/12/2021	855.39	12 - 14 ft	180-115861-1	Not Excavated	1.36	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.89 J	0.4 J	0.07 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	3.39	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2.4 J	0.83 J	0.16 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	0.054	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.024	0.03	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.019	0.01 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3603	SSHS-B3603-SUB-2-4	1/25/2021	855.89	2 - 4 ft	180-116404-3	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3604	SSHS-B3604-SUB-2-4	1/25/2021	855.40	2 - 4 ft	180-116404-3	Not Excavated	0.199	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.14 J	0.059 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3605	SSHS-B3605-SUB-2-4	1/25/2021	855.99	2 - 4 ft	180-116404-3	Not Excavated	3.353	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	2.4 J	0.92 J	0.033 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3606	SSHS-B3606-SUB-2-4	1/25/2021	855.37	2 - 4 ft	180-116404-3	Not Excavated	0.024	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.024	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3607	SSHS-B3607-SUB-2-4	1/25/2021	855.19	2 - 4 ft	180-116404-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3608	SSHS-B3608-SUB-2-4	1/25/2021	856.10	2 - 4 ft	180-116404-3	Not Excavated	0.016	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.016	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3609	SSHS-B3609-SUB-2-4	1/25/2021	855.67	2 - 4 ft	180-116404-3	Not Excavated	0.061	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.042 J	0.019 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3610	SSHS-B3610-SUB-2-4	1/25/2021	856.08	2 - 4 ft	180-116404-3	Not Excavated	0.359	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.26 J	0.099 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3611	SSHS-B3611-SUB-2-4	1/25/2021	856.16	2 - 4 ft	180-116404-3	Not Excavated	0.41	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.28 J	0.13 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3612	SSHS-B3612-SUB-2-4	1/25/2021	856.56	2 - 4 ft	180-116404-3	Not Excavated	0.087	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.06 J	0.027 J	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3617	SSHS-B3617-SUB-2-4	1/25/2021	856.07	2 - 4 ft	180-116404-3	Not Excavated	0.444	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.19 J	0.22 J	0.034 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3618	SSHS-B3618-SUB-2-4	1/25/2021	856.15	2 - 4 ft	180-116404-3	Not Excavated	0.175	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.11 J	0.065 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3619	SSHS-B3619-SUB-2-4	1/25/2021	856.42	2 - 4 ft	180-116404-3	Excavated	108	< 0.31 U	< 0.34 U	< 0.24 U	< 0.14 U	50 J	58 J	< 0.27 U	< 0.34 U	< 0.13 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	2 - 4 ft	180-116404-3	Not Excavated	0.209	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.15 J	0.059 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3621	SSHS-B3621-SUB-2-4	1/25/2021	856.33	2 - 4 ft	180-116404-3	Not Excavated	0.017	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.017 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3622	SSHS-B3622-SUB-2-4	1/25/2021	856.17	2 - 4 ft	180-116404-3	Not Excavated	1.43	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1 J	0.43 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3623	SSHS-B3623-SUB-2-4	1/23/2021	855.47	2 - 4 ft	180-116404-3	Not Excavated	0.113	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.064 J	0.049 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3624	SSHS-B3624-SUB-2-4	1/23/2021	855.26	2 - 4 ft	180-116404-3	Not Excavated	0.127	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.083 J	0.044 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	0.071	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.04	0.031	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3648	SSHS-B3648-SUB-2-4	1/29/2021	856.51	2 - 4 ft	180-116665-3	Excavated	0.35	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.2 J	0.11 J	0.04 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3649	SSHS-B3649-SUB-2-4	1/29/2021	856.47	2 - 4 ft	180-116665-3	Excavated	0.159	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.11 J	0.049 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	0.288	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.21	0.078	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	0.288	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.21	0.078	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated	0.49	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.36	0.13	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated	0.153	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.11 J	0.043 J	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated	0.248	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.18 J	0.068 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated	0.082	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.059 J	0.023 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	0.081	< 0.035 U	< 0.035 U	< 0.035 U	< 0.035 U	0.046	< 0.035 U	0.035		
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-2-4	3/8/2016	852.79	2 - 4 ft	180-52813-1	Excavated	14.03	< 0.082 U	< 0.13 U	< 0.045 U	< 0.066 U	11 J	2.5 J	0.53 J	< 0.056 U	< 0.033 U
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-4-6	3/8/2016	852.79	4 - 6 ft	180-52813-1	Not Excavated	5.22	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	3.7 J	1.3 J	0.22 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-6-8	3/8/2016	852.79	6 - 8 ft	180-52813-1	Not Excavated	8.1	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.007 U	3 J	4 J	1.1 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-8-10	3/8/2016	852.79	8 - 10 ft	180-52813-1	Not Excavated	8.25	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	4.4 J	3.1 J	0.75 J	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-2-4	3/8/2016	852.92	2 - 4 ft	180-52813-2	Excavated	29.8	< 0.083 U	< 0.13 U	< 0.045 U	< 0.067 U	21 J	7.7 J	1.1 J	< 0.056 U	< 0.034 U
Rear Parking Lot	SSHS-B372	SSHS-B372-SUB-4-6	3/8/2016	852.92	4 - 6 ft	180-52813-2	Excavated	2.38	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	1.7 J	0.57 J	0.11 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B373	PS-FD-24	3/10/2016	852.56	2 - 4 ft	180-52921-1	Excavated	1.8	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	1.1 J	0.54 J	0.16 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-2-4	3/10/2016	852.56	2 - 4 ft	180-52921-1	Excavated	1.91	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1.2 J	0.57 J	0.14 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-4-6	3/10/2016	852.56	4 - 6 ft	180-52921-1	Not Excavated	0.369	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.22 J	0.12 J	0.029 J	< 0.006 U	< 0.0036 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-6-8	3/10/2016	852.56	6 - 8 ft	180-52921-1	Not Excavated	2.54	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.87 J	1.3 J	0.37 J	< 0.0063 U	< 0.0038 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-8-10	3/10/2016	852.56	8 - 10 ft	180-52921-1	Not Excavated	2.08	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.83 J	0.97 J	0.28 J	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-2-4	3/10/2016	852.41	2 - 4 ft	180-52921-1	Not Excavated	0.374	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.22 J	0.12 J	0.034 J	< 0.0053 U	< 0.0032 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-4-6	3/10/2016	852.41	4 - 6 ft	180-52921-1	Not Excavated	0.008	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.008 J	< 0.0066 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-6-8	3/10/2016	852.41	6 - 8 ft	180-52921-1	Not Excavated	0.234	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.099 J	0.1 J	0.035 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B376	SSHS-B376-SUB-2-4	3/8/2016	851.45	2 - 4 ft	180-52813-1	Not Excavated	0.265	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.17 J	0.075 J	0.02 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B377	SSHS-B377-SUB-8-10	3/8/2016	850.78	8 - 10 ft	180-52813-1	Excavated	52.6	< 0.087 U	< 0.14 U	< 0.047 U	< 0.07 U	42 J	8.7 J	1.9 J	< 0.059 U	< 0.035 U
Rear Parking Lot	SSHS-B377	SSHS-B377B-SUB-10-12	3/8/2016	850.78	10 - 12 ft	180-52813-2	Excavated	0.744	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.53 J	0.18 J	0.034 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-2-4	3/8/2016	850.73	2 - 4 ft	180-52813-1	Excavated	81.8	< 0.42 U	< 0.67 U	< 0.23 U	< 0.34 U	63 J	15 J	3.8 J	< 0.29 U	< 0.17 U
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-4-6	3/8/2016	850.73	4 - 6 ft	180-52813-1	Excavated	2.16	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0073 U	1.6 J	0.46 J	0.1 J	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-8-10	3/8/2016	850.73	8 - 10 ft	180-52813-1	Not Excavated	6.15	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	4.7 J	1.2 J	0.25 J	< 0.0058 U	< 0.0035 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B379	SSHS-B379-SUB-2-4	3/8/2016	851.22	2 - 4 ft	180-52813-1	Excavated	2.16	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	1.6 J	0.45 J	0.11 J	< 0.0065 U	< 0.0039 U
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-2-4	3/9/2016	850.28	2 - 4 ft	180-52876-1	Not Excavated	ND	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	< 0.0044 U	< 0.007 U	< 0.0065 U	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	2 - 4 ft	180-124920-2	Not Excavated	0.084	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.084 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	2.35	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.4 J	0.75 J	0.2 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	0.25	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.15 J	0.081 J	0.019 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	0.188	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.11 J	0.062 J	0.016 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	0.027	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.014 J	0.013 J	< 0.0054 UJ	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	0.092	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.064 J	0.028 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	0.066	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.043 J	0.023 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	0.135	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.088 J	0.047 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Rear Parking Lot	SSHS-B386	PS-FD-20	3/8/2016	852.82	2 - 4 ft	180-52813-1	Not Excavated	2.26	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1 J	0.99 J	0.27 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-2-4	3/8/2016	852.82	2 - 4 ft	180-52813-1	Not Excavated	2.39	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	1 J	1.1 J	0.29 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-4-6	3/8/2016	852.82	4 - 6 ft	180-52813-1	Not Excavated	0.81	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.3 J	0.4 J	0.11 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B388	SSHS-B388-SUB-6-8	3/10/2016	850.40	6 - 8 ft	180-52921-1	Excavated	1.47	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.66 J	0.42 J	0.39 J	< 0.0059 U	< 0.0035 U
Northern Athletic Field	SSHS-B3882	DUP-1	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	0.03	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.03	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-14-16	5/11/2021	853.49	14 - 16 ft	180-121474-1	Not Excavated	121	< 0.29 U	< 0.31 U	< 0.22 U	< 0.13 U	100 J	21 J	< 0.25 U	< 0.31 U	< 0.12 U
Northern Athletic Field	SSHS-B3884A	SSHS-B3884A-SUB-12-14	6/18/2021	853.49	12 - 14 ft	180-123449-1	Excavated	3.533	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2.5 J	1 J	0.033 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-14-16	9/22/2021	854.12	14 - 16 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-14-16	5/18/2021	854.47	14 - 16 ft	180-121822-1	Not Excavated	0.11	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.11	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-14-16	5/15/2021	855.62	14 - 16 ft	180-121747-1	Not Excavated	0.015	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-14-16	5/14/2021	855.59	14 - 16 ft	180-121705-1	Not Excavated	0.01	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.01 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated	0.039	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.039 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Rear Parking Lot	SSHS-B389	SSHS-B389-SUB-8-10	3/10/2016	851.50	8 - 10 ft	180-52921-1	Excavated	22.79	< 0.089 U	< 0.14 U	< 0.049 U	< 0.072 U	17 J	5 J	0.79 J	< 0.061 U	< 0.036 U
Rear Parking Lot	SSHS-B389	SSHS-B389-SUB-10-12	3/10/2016	851.50	10 - 12 ft	180-52921-2	Not Excavated	0.0084	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.0084 J	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-14-16	5/12/2021	856.79	14 - 16 ft	180-121548-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	0.051	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.051	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-14-16	5/14/2021	856.33	14 - 16 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-14-16	5/13/2021	856.49	14 - 16 ft	180-121704-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-14-16	5/11/2021	852.98	14 - 16 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-14-16	5/15/2021	854.53	14 - 16 ft	180-121747-1	Not Excavated	0.0094	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0094 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-14-16	5/16/2021	855.21	14 - 16 ft	180-121747-1	Not Excavated	0.101	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.077 J	0.024 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	DUP-20	5/18/2021	856.45	14 - 16 ft	180-121822-1	Not Excavated	0.016	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-14-16	5/18/2021	856.45	14 - 16 ft	180-121822-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 UJ	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	0.0097	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0097 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Rear Parking Lot	SSHS-B390	PS-FD-25	3/10/2016	851.95	8 - 10 ft	180-52921-1	Not Excavated	10.67	< 0.043 U	< 0.069 U	< 0.024 U	< 0.035 U	7.7 J	2.5 J	0.47 J	< 0.029 U	< 0.018 U
Rear Parking Lot	SSHS-B390	SSHS-B390-SUB-8-10	3/10/2016	851.95	8 - 10 ft	180-52921-1	Not Excavated	13.07	< 0.043 U	< 0.069 U	< 0.024 U	< 0.035 U	9.2 J	3.3 J	0.57 J	< 0.029 U	< 0.018 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-14-16	5/14/2021	856.30	14 - 16 ft	180-121705-1	Not Excavated	0.198	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.15 J	0.048 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-14-16	5/13/2021	857.53	14 - 16 ft	180-121704-1	Not Excavated	0.059	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.043 J	0.016 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-14-16	5/12/2021	856.44	14 - 16 ft	180-121548-2	Not Excavated	0.015	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.015 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16	5/19/2021	856.98	14 - 16 ft	1801219031	Not Excavated	0.017	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.017 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-14-16	5/7/2021	857.27	14 - 16 ft	180-121355-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-14-16	5/10/2021	856.83	14 - 16 ft	180-121424-1	Not Excavated	1.585	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	1.2 J	0.33 J	0.055 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-14-16	5/10/2021	856.60	14 - 16 ft	180-121424-1	Not Excavated	0.088	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.088	< 0.0052 UJ	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-14-16	5/11/2021	856.72	14 - 16 ft	180-121474-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 UJ	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-14-16	5/7/2021	857.06	14 - 16 ft	180-121355-1	Not Excavated	0.079	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.052 J	0.027 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Rear Parking Lot	SSHS-B391	SSHS-B391-SUB-8-10	3/10/2016	849.56	8 - 10 ft	180-52921-1	Not Excavated	1.642	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1.2 J	0.38 J	0.062 J	< 0.0059 U	< 0.0035 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-14-16	6/10/2021	856.20	14 - 16 ft	180-123098-2	Not Excavated	2.01	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.4 J	0.47 J	0.14 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-14-16	6/11/2021	855.61	14 - 16 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-14-16	5/15/2021	855.68	14 - 16 ft	180-121747-1	Not Excavated	0.224	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.18 J	0.044 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-14-16	6/11/2021	855.12	14 - 16 ft	180-123134-1	Not Excavated	0.583	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	0.13 J	0.013 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	0.025	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.025	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	0.023	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.023	< 0.0064 U	< 0.0060 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	0.078	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.054	0.024	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-14-16	5/12/2021	852.53	14 - 16 ft	180-121548-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 UJ	< 0.0058 UJ	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	0.283	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.14	0.12	0.023 P	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	0.129	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.059	0.059	0.011 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	68.8	< 0.13 U	< 0.14 U	< 0.1 U	< 0.06 U	51	15	2.8	< 0.14 U	< 0.055 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	35.8	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	27	7.4	1.4	< 0.068 U	< 0.026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	22.61	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	17	5	0.61	< 0.067 U	< 0.026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	18.85	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	15	3.3	0.55	< 0.067 U	< 0.025 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	0.679	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.51	0.14	0.029	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-2-4	5/12/2021	854.82	2 - 4 ft	180-121548-2	Not Excavated	0.307	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.23 J	0.066 J	0.011 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-4-6	5/12/2021	854.82	4 - 6 ft	180-121548-2	Not Excavated	0.08	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.059 J	0.021 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-6-8	5/12/2021	854.82	6 - 8 ft	180-121548-2	Not Excavated	0.208	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.16 J	0.048 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-8-10	5/12/2021	854.82	8 - 10 ft	180-121548-2	Not Excavated	0.019	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.019	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-10-12	5/12/2021	854.82	10 - 12 ft	180-121548-2	Not Excavated	0.073	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.054 J	0.019 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-12-14	5/12/2021	854.82	12 - 14 ft	180-121548-2	Not Excavated	0.075	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.055 J	0.02 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-14-16	5/12/2021	854.82	14 - 16 ft	180-121548-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-14-16	5/16/2021	852.79	14 - 16 ft	180-121747-1	Not Excavated	0.12	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.12	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	SSHS-B392	SSHS-B392-SUB-8-10	3/10/2016	850.00	8 - 10 ft	180-52921-1	Not Excavated	1.395	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1 J	0.34 J	0.055 J	< 0.0059 U	< 0.0035 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-14-16	7/1/2021	853.40	14 - 16 ft	180-123985-1	Not Excavated	4.3	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	4.3	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	0.049	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	0.049	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-12-14	6/18/2021	854.11	12 - 14 ft	180-123449-1	Not Excavated	0.093	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.075 J	0.018 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-14-16	6/18/2021	854.11	14 - 16 ft	180-123449-1	Not Excavated	0.041	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.03 J	0.011 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-12-14	6/18/2021	854.03	12 - 14 ft	180-123449-1	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-14-16	6/18/2021	854.03	14 - 16 ft	180-123449-1	Not Excavated	0.024	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.024 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-12-14	6/18/2021	853.31	12 - 14 ft	180-123449-1	Excavated	0.069	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.069 J	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-14-16	6/18/2021	853.31	14 - 16 ft	180-123449-1	Not Excavated	8.7	< 0.064 U	< 0.07 U	< 0.048 U	< 0.029 U	8.7 J	< 0.059 U	< 0.056 U	< 0.069 U	< 0.027 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-12-14	6/18/2021	853.29	12 - 14 ft	180-123449-1	Not Excavated	0.44	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-14-16	6/18/2021	853.29	14 - 16 ft	180-123449-1	Not Excavated	0.56	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.56 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-4-6	6/17/2021	854.13	4 - 6 ft	180-123398-1	Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 UJ	< 0.0053 UJ	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-6-8	6/17/2021	854.13	6 - 8 ft	180-123398-1	Excavated	0.2983	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.21 J	0.08 J	0.0083 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-8-10	6/17/2021	854.13	8 - 10 ft	180-123398-1	Excavated	0.0044	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	0.0044 J	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-10-12	6/17/2021	854.13	10 - 12 ft	180-123398-1	Excavated	0.34	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.21 J	0.098 J	0.032 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-12-14	6/17/2021	854.13	12 - 14 ft	180-123398-1	Excavated	0.491	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.31 J	0.14 J	0.041 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3927	SSHS-B3927-SUB-14-16	6/17/2021	854.13	14 - 16 ft	180-123398-1	Excavated	0.055	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.038 J	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-4-6	6/18/2021	853.07	4 - 6 ft	180-123449-1	Excavated	0.062	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.043 J	0.019 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-6-8	6/18/2021	853.07	6 - 8 ft	180-123449-1	Excavated	0.24	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.14 J	0.08 J	0.02 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-8-10	6/18/2021	853.07	8 - 10 ft	180-123449-1	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-10-12	6/18/2021	853.07	10 - 12 ft	180-123449-1	Excavated	0.02	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.02 J	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-12-14	6/18/2021	853.07	12 - 14 ft	180-123449-1	Not Excavated	0.104	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.071 J	0.033 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-14-16	6/18/2021	853.07	14 - 16 ft	180-123449-1	Not Excavated	0.118	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.073 J	0.045 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-4-6	6/18/2021	854.16	4 - 6 ft	180-123449-1	Excavated	0.1797	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.12 J	0.05 J	0.0097 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-6-8	6/18/2021	854.16	6 - 8 ft	180-123449-1	Excavated	3.15	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	2.1 J	0.88 J	0.17 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-8-10	6/18/2021	854.16	8 - 10 ft	180-123449-1	Excavated	0.102	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.068 J	0.034 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-10-12	6/18/2021	854.16	10 - 12 ft	180-123449-1	Excavated	1.659	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.1 J	0.46 J	0.099 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-12-14	6/18/2021	854.16	12 - 14 ft	180-123449-1	Not Excavated	1.108	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.68 J	0.35 J	0.078 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-14-16	6/18/2021	854.16	14 - 16 ft	180-123449-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	SSHS-B393	SSHS-B393-SUB-8-10	3/10/2016	849.93	8 - 10 ft	180-52921-1	Excavated	2.61	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1.9 J	0.58 J	0.13 J	< 0.0056 U	< 0.0033 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	0.035	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.035	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	0.062	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.044	0.018	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	0.016	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.016 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	0.015	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-2-4	3/8/2016	851.52	2 - 4 ft	180-52813-1	Excavated	1.494	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	1.1 J	0.32 J	0.074 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-4-6	3/8/2016	851.52	4 - 6 ft	180-52813-1	Excavated	4.26	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	3.4 J	0.72 J	0.14 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B394	PS-FD-18	3/8/2016	851.52	8 - 10 ft	180-52813-1	Not Excavated	2.497	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	2 J	0.41 J	0.087 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-8-10	3/8/2016	851.52	8 - 10 ft	180-52813-1	Not Excavated	3.125	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	2.5 J	0.54 J	0.085 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B395	SSHS-B395-SUB-8-10	3/10/2016	851.50	8 - 10 ft	180-52921-1	Not Excavated	2.83	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	2 J	0.69 J	0.14 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B396	SSHS-B396-SUB-8-10	3/10/2016	850.83	8 - 10 ft	180-52921-1	Not Excavated	0.362	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.25 J	0.095 J	0.017 J	< 0.006 U	< 0.0036 U
EHS Building	SSHS-B3S	B3-C2-Composite	7/25/2007	855.70	2 - 2.9 ft	NA	Not Excavated	87	< U	< U	< U	< U	87	< U	< U		
Football Field	SSHS-B4015	SSHS-B4015-SUB-14-16	6/30/2021	855.88	14 - 16 ft	180-123901-2	Not Excavated	1.98	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	1.4 J	0.47 J	0.11 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	0.249	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	0.19 J	0.059 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	0.22	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.16	0.06	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	0.219	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14	0.079	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-12-14	7/26/2021	853.87	12 - 14 ft	180-124973-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-14-16	7/26/2021	853.87	14 - 16 ft	180-124973-1	Not Excavated	0.31	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.31	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B407	SSHS-B407-SUB-2-4	8/25/2016	857.28	2 - 4 ft	180-57995-1	Excavated	0.017	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.034 U	0.017 J	< 0.0067 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B407	PS-FD-8	8/25/2016	857.28	4 - 6 ft	180-57995-1	Excavated	0.294	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.034 U	0.18 J	0.1 J	0.014 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B407	SSHS-B407-SUB-4-6	8/25/2016	857.28	4 - 6 ft	180-57995-1	Excavated	0.371	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.034 U	0.21 J	0.14 J	0.021 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B407	SSHS-B407-SUB-6-8	8/25/2016	857.28	6 - 8 ft	180-57995-1	Not Excavated	ND	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	< 0.0046 U	< 0.0072 U	< 0.0067 U	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B408	SSHS-B408-SUB-2-4	8/25/2016	857.31	2 - 4 ft	180-57995-1	Excavated	9.92	< 0.043 U	< 0.069 U	< 0.024 U	< 0.034 U	7.3 J	2.5 J	0.12 J	< 0.029 U	< 0.018 U
Football Field	SSHS-B410	SSHS-B410-SUB-2-4	8/25/2016	856.77	2 - 4 ft	180-57995-1	Not Excavated	0.386	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.034 U	0.2 J	0.14 J	0.046 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B412	SSHS-B412-SUB-2-4	8/25/2016	856.86	2 - 4 ft	180-57995-1	Excavated	24.89	< 0.085 U	< 0.13 U	< 0.047 U	< 0.034 U	18 J	6.3 J	0.59 J	< 0.058 U	< 0.035 U
Football Field	SSHS-B412	SSHS-B412-SUB-4-6	8/25/2016	856.86	4 - 6 ft	180-57995-1	Excavated	2.441	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.034 U	1.6 J	0.75 J	0.091 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B412	SSHS-B412-SUB-6-8	8/25/2016	856.86	6 - 8 ft	180-57995-1	Not Excavated	ND	< 0.0096 U	< 0.015 U	< 0.0053 U	< 0.034 U	< 0.0049 U	< 0.0078 U	< 0.0072 U	< 0.0065 U	< 0.0039 U
Football Field	SSHS-B413	SSHS-B413-SUB-2-4	8/26/2016	856.37	2 - 4 ft	180-58029-1	Excavated	40.3	< 0.17 UJ	< 0.27 U	< 0.094 U	< 0.034 U	28 J	11 J	1.5 J	< 0.12 U	< 0.07 U
Football Field	SSHS-B415	PS-FD-2	8/22/2016	856.17	2 - 4 ft	180-57858-1	Excavated	4.36	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.034 U	2.3 J	1.7 J	0.36 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B415	SSHS-B415-SUB-2-4	8/22/2016	856.17	2 - 4 ft	180-57858-1	Excavated	7.28	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.034 U	4 J	2.7 J	0.58 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B416	SSHS-B416-SUB-2-4	8/22/2016	855.45	2 - 4 ft	180-57858-1	Excavated	74	< 0.42 U	< 0.66 U	< 0.23 U	< 0.034 U	54 J	20 J		< 0.28 U	< 0.17 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	0.048	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.027 J	0.021 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	0.0082	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0082 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	0.0083	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.0083 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 UJ	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	0.227	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	0.086	0.11	0.031	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	0.029	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	0.016 J	0.013 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 UJ	< 0.0057 UJ	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	ND	< 0.0092 U	< 0.01 U	< 0.0069 U	< 0.034 U	< 0.0068 U	< 0.0084 U	< 0.008 U	< 0.0099 U	< 0.0038 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	0.024	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	0.024	< 0.0052 U	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	0.0061	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.034 U	< 0.0042 U	0.0061 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B417	SSHS-B417-SUB-2-4	8/22/2016	854.89	2 - 4 ft	180-57858-1	Excavated	ND	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.034 U	< 0.0042 U	< 0.0067 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	0.881	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	0.48 J	0.31 J	0.091 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	1.17	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.58 J	0.47 J	0.12 J	< 0.0067 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	0.32	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	0.17 J	0.11 J	0.04 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	0.191	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	0.096 J	0.073 J	0.022 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	0.797	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.49 J	0.25 J	0.057 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	0.214	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.034 U	0.13 J	0.084 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	0.36	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.21 J	0.12 J	0.03 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B418	SSHS-B418-SUB-2-4	8/23/2016	855.15	2 - 4 ft	180-57888-1	Excavated	0.185	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.11 J	0.062 J	0.013 J	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B419	SSHS-B419-SUB-2-4	8/23/2016	855.07	2 - 4 ft	180-57888-1	Excavated	9.77	< 0.04 U	< 0.064 U	< 0.022 U	< 0.033 U	5.7 J	3.3 J	0.77 J	< 0.027 U	< 0.016 U
Football Field	SSHS-B420	SSHS-B420-SUB-2-4	8/23/2016	855.20	2 - 4 ft	180-57888-1	Excavated	2.46	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	1.3 J	0.91 J	0.25 J	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B421	SSHS-B421-SUB-2-4	8/23/2016	854.90	2 - 4 ft	180-57888-1	Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0058 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B421	SSHS-B421-SUB-4-6	8/23/2016	854.90	4 - 6 ft	180-57888-1	Not Excavated	0.33	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	0.16 J	0.14 J	0.03 J	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B422	SSHS-B422-SUB-2-4	8/23/2016	855.04	2 - 4 ft	180-57888-1	Excavated	0.181	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.099 J	0.064 J	0.018 J	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B422	SSHS-B422-SUB-4-6	8/23/2016	855.04	4 - 6 ft	180-57888-1	Not Excavated	0.417	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.27 J	0.12 J	0.027 J	< 0.0056 U	< 0.0033 U
Football Field	SSHS-B424	SSHS-B424-SUB-2-4	8/22/2016	856.17	2 - 4 ft	180-57858-1	Excavated	6.39	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.034 U	3.9 J	2.1 J	0.39 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B425	SSHS-B425-SUB-2-4	8/22/2016	855.58	2 - 4 ft	180-57858-1	Excavated	10.11	< 0.044 U	< 0.069 U	< 0.024 U	< 0.034 U	7.1 J	2.6 J	0.41 J	< 0.03 U	< 0.018 U
Football Field	SSHS-B431	SSHS-B431-SUB-2-4	8/22/2016	855.61	2 - 4 ft	180-57858-1	Excavated	8.79	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.034 U	4.6 J	3.3 J	0.89 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B432	SSHS-B432-SUB-2-4	8/22/2016	855.16	2 - 4 ft	180-57858-1	Excavated	14.95	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	10 J	4.2 J	0.75 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B432	PS-FD-1	8/22/2016	855.16	4 - 6 ft	180-57858-1	Not Excavated	2.86	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	2 J	0.73 J	0.13 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B432	SSHS-B432-SUB-4-6	8/22/2016	855.16	4 - 6 ft	180-57858-1	Not Excavated	1.91	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.3 J	0.51 J	0.1 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B433	SSHS-B433-SUB-2-4	8/23/2016	855.58	2 - 4 ft	180-57888-1	Excavated	19.4	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	13 J	5.3 J	1.1 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B433	SSHS-B433-SUB-4-6	8/23/2016	855.58	4 - 6 ft	180-57888-1	Not Excavated	1.761	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.034 U	1.2 J	0.47 J	0.091 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B434	SSHS-B434-SUB-2-4	8/22/2016	855.08	2 - 4 ft	180-57858-1	Excavated	5.92	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	3.5 J	1.9 J	0.52 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B435	SSHS-B435-SUB-6-8	8/23/2016	856.34	6 - 8 ft	180-57888-1	Excavated	20.9	< 0.045 U	< 0.072 U	< 0.025 U	< 0.034 U	13 J	6 J	1.9 J	< 0.031 U	< 0.018 U
Football Field	SSHS-B436	SSHS-B436-SUB-4-6	8/22/2016	855.26	4 - 6 ft	180-57858-1	Excavated	2.99	< 0.0081 U,F2	< 0.013 U	< 0.0045 U	< 0.0066 U	1.8 J	0.93 J	0.26 J	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B438	SSHS-B438-SUB-2-4	8/26/2016	854.99	2 - 4 ft	180-58029-3	Excavated	71.6	< 0.16 U	< 0.26 U	< 0.09 U	< 0.034 U	53 J	17 J	1.6 J	< 0.11 U	< 0.067 U
Football Field	SSHS-B438	SSHS-B438-SUB-4-6	8/26/2016	854.99	4 - 6 ft	180-58029-3	Excavated	36.83	< 0.082 U	< 0.13 U	< 0.045 U	< 0.034 U	26 J	9.9 J	0.93 J	< 0.056 U	< 0.034 U
Football Field	SSHS-B438	SSHS-B438-SUB-6-8	8/26/2016	854.99	6 - 8 ft	180-58029-3	Excavated	36.8	< 0.084 U	< 0.13 U	< 0.046 U	< 0.034 U	26 J	10 J	0.8 J	< 0.057 U	< 0.034 U
Football Field	SSHS-B438	SSHS-B438-SUB-8-10	8/26/2016	854.99	8 - 10 ft	180-58029-2	Excavated	231.5	< 0.82 U	< 1.3 U	< 0.45 U	< 0.034 U	170 J	56 J	5.5 J	< 0.56 U	< 0.34 U
Football Field	SSHS-B439	SSHS-B439-SUB-2-4	8/26/2016	855.06	2 - 4 ft	180-58029-3	Excavated	57.7	< 0.16 U	< 0.26 U	< 0.089 U	< 0.13 U	39 J	17 J	1.7 J	< 0.11 U	< 0.066 U
Football Field	SSHS-B439	SSHS-B439-SUB-6-8	9/15/2016	855.06	6 - 8 ft	180-58722-1	Excavated	374	< 0.86 U	< 1.4 U	< 0.47 U	< 0.7 U	270 J	89 J	15 J	< 0.59 U	< 0.35 U
Football Field	SSHS-B439	SSHS-B439-SUB-8-10	9/15/2016	855.06	8 - 10 ft	180-58722-2	Excavated	144.8	< 0.85 U	< 1.3 U	< 0.46 U	< 0.68 U	110 J	31 J	3.8 J	< 0.58 U	< 0.35 U
Football Field	SSHS-B440	SSHS-B440-SUB-2-4	8/26/2016	855.30	2 - 4 ft	180-58029-1	Excavated	19.84	< 0.082 UJ	< 0.13 U	< 0.045 U	< 0.066 U	14 J	5.1 J	0.74 J	< 0.056 U	< 0.034 U
Football Field	SSHS-B440	SSHS-B440-SUB-4-6	8/26/2016	855.30	4 - 6 ft	180-58029-1	Excavated	26.1	< 0.086 UJ	< 0.14 U	< 0.047 U	< 0.069 U	18 J	7 J	1.1 J	< 0.058 U	< 0.035 U
Football Field	SSHS-B440	SSHS-B440-SUB-6-8	8/26/2016	855.30	6 - 8 ft	180-58029-1	Excavated	440	< 0.83 UJ	< 1.3 U	< 0.45 U	< 0.67 U	340 J	86 J	14 J	< 0.56 U	< 0.34 U
Football Field	SSHS-B440	SSHS-B440-SUB-8-10	8/26/2016	855.30	8 - 10 ft	180-58029-2	Excavated	39.6	< 0.17 U	< 0.27 U	< 0.094 U	< 0.14 U	29 J	9.4 J	1.2 J	< 0.12 U	< 0.07 U
Football Field	SSHS-B441	SSHS-B441-SUB-2-4	8/24/2016	854.89	2 - 4 ft	180-57932-1	Excavated	458	< 0.86 U	< 1.4 U	< 0.47 U	< 0.69 U	350 J	91 J	17 J	< 0.58 U	< 0.35 U
Football Field	SSHS-B441	SSHS-B441-SUB-4-6	8/24/2016	854.89	4 - 6 ft	180-57932-1	Excavated	20.84	< 0.045 U	< 0.071 U	< 0.025 U	< 0.036 U	15 J	5.4 J	0.44 J	< 0.03 U	< 0.018 U
Football Field	SSHS-B441	SSHS-B441-SUB-6-8	8/24/2016	854.89	6 - 8 ft	180-57932-1	Excavated	0.014	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.014 J	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B442	SSHS-B442-SUB-2-4	8/24/2016	855.06	2 - 4 ft	180-57932-1	Excavated	4.41	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.007 U	3.3 J	0.96 J	0.15 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B442	SSHS-B442-SUB-4-6	8/24/2016	855.06	4 - 6 ft	180-57932-1	Excavated	1.172	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.86 J	0.26 J	0.052 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B442	SSHS-B442-SUB-6-8	8/24/2016	855.06	6 - 8 ft	180-57932-1	Excavated	0.49	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	0.36 J	0.11 J	0.02 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B443	SSHS-B443-SUB-2-4	9/14/2016	855.30	2 - 4 ft	180-58722-1	Excavated	292	< 0.83 U	< 1.3 U	< 0.45 U	< 0.67 U	210 J	72 J	10 J	< 0.56 U	< 0.34 U
Football Field	SSHS-B443	PS-FD-25	9/14/2016	855.30	4 - 6 ft	180-58722-1	Excavated	359	< 0.84 U	< 1.3 U	< 0.46 U	< 0.67 U	260 J	86 J	13 J	< 0.57 U	< 0.34 U
Football Field	SSHS-B443	SSHS-B443-SUB-4-6	9/14/2016	855.30	4 - 6 ft	180-58722-1	Excavated	2061	< 4.1 U	< 6.5 U	< 2.3 U	< 3.3 U	1500 J	510 J	51 J	< 2.8 U	< 1.7 U
Football Field	SSHS-B443	SSHS-B443-SUB-6-8	9/14/2016	855.30	6 - 8 ft	180-58722-1	Excavated	101.5	< 0.42 U	< 0.67 U	< 0.23 U	< 0.34 U	74 J	24 J	3.5 J	< 0.29 U	< 0.17 U
Football Field	SSHS-B443	SSHS-B443-SUB-8-10	9/15/2016	855.30	8 - 10 ft	180-58722-2	Excavated	271.6	< 0.84 U	< 1.3 U	< 0.46 U	< 0.68 U	200 J	65 J	6.6 J	< 0.57 U	< 0.34 U
Football Field	SSHS-B444	SSHS-B444-SUB-2-4	8/26/2016	855.07	2 - 4 ft	180-58029-1	Excavated	53.2	< 0.17 UJ	< 0.26 U	< 0.09 U	< 0.13 U	37 J	14 J	2.2 J	< 0.11 U	< 0.067 U
Football Field	SSHS-B444	PS-FD-11	8/26/2016	855.07	4 - 6 ft	180-58029-1	Excavated	6.59	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	4.3 J	1.8 J	0.49 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B444	SSHS-B444-SUB-4-6	8/26/2016	855.07	4 - 6 ft	180-58029-1	Excavated	8.92	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.0068 U	5.5 J	2.7 J	0.72 J	< 0.0057 U	< 0.0035 U
Football Field	SSHS-B444	SSHS-B444-SUB-6-8	8/26/2016	855.07	6 - 8 ft	180-58029-1	Excavated	23	< 0.087 UJ	< 0.14 U	< 0.047 U	< 0.07 U	< 0.044 U	23	< 0.065 U	< 0.059 U	< 0.035 U
Football Field	SSHS-B444	SSHS-B444-SUB-8-10	8/26/2016	855.07	8 - 10 ft	180-58029-2	Excavated	33.6	< 0.085 U	< 0.13 U	< 0.046 U	< 0.068 U	24 J	8.2 J	1.4 J	< 0.057 U	< 0.034 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B451	SSHS-B451-SUB-2-4	9/27/2016	854.61	2 - 4 ft	180-59163-1	Excavated	0.39	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.21 J	0.18 J	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B451	SSHS-B451-SUB-4-6	9/27/2016	854.61	4 - 6 ft	180-59163-1	Not Excavated	0.23	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.12 J	0.11 J	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B451	SSHS-B451-SUB-6-8	9/27/2016	854.61	6 - 8 ft	180-59163-1	Not Excavated	ND	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0066 U	< 0.0041 U	< 0.0066 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B451	SSHS-B451-SUB-8-10	9/27/2016	854.61	8 - 10 ft	180-59163-1	Not Excavated	ND	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	< 0.0064 U	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-10-12	9/27/2016	854.61	10 - 12 ft	180-59163-1	Not Excavated	ND	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	< 0.0064 U	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-12-14	9/27/2016	854.61	12 - 14 ft	180-59163-1	Not Excavated	0.0088	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	0.0088 J	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-14-16	9/27/2016	854.61	14 - 16 ft	180-59163-1	Not Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B452	SSHS-B452-SUB-2-4	9/27/2016	854.99	2 - 4 ft	180-59163-1	Excavated	0.032	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	0.032	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B452	SSHS-B452-SUB-4-6	9/27/2016	854.99	4 - 6 ft	180-59163-1	Not Excavated	0.013	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	0.013 J	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B452	SSHS-B452-SUB-6-8	9/27/2016	854.99	6 - 8 ft	180-59163-1	Not Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0058 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B452	DUP2103	9/27/2016	854.99	8 - 10 ft	180-59163-1	Not Excavated	ND	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	< 0.0041 U	< 0.0064 U	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B452	SSHS-B452-SUB-8-10	9/27/2016	854.99	8 - 10 ft	180-59163-1	Not Excavated	ND	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	< 0.0041 U	< 0.0064 U	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B455	SSHS-B455-SUB-4-6	8/30/2016	855.84	4 - 6 ft	180-58129-1	Excavated	ND	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.0074 U	< 0.0047 U	< 0.0074 U	< 0.0069 U	< 0.0062 U	< 0.0038 U
Football Field	SSHS-B455	PS-FD-16	8/30/2016	855.84	6 - 8 ft	180-58129-1	Excavated	ND	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	< 0.0043 U	< 0.0068 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B455	SSHS-B455-SUB-6-8	8/30/2016	855.84	6 - 8 ft	180-58129-1	Excavated	ND	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	< 0.0042 U	< 0.0067 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B455	SSHS-B455-SUB-8-10	8/30/2016	855.84	8 - 10 ft	180-58129-1	Excavated	0.295	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.21 J	0.085 J	< 0.0063 U	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B455A	SSHS-B455A-SUB-8-10	7/10/2017	855.84	8 - 10 ft	180-68038-1	Excavated	0.138	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.087 J	0.051 J	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B456	SSHS-B456-SUB-4-6	8/30/2016	855.99	4 - 6 ft	180-58129-1	Not Excavated	ND	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	< 0.0042 U	< 0.0066 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B461	PS-FD-17	8/31/2016	855.42	2 - 3 ft	180-58236-1	Excavated	11.28	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	8.6 J	2.3 J	0.38 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B461	SSHS-B461-SUB-2-3	8/31/2016	855.42	2 - 3 ft	180-58236-1	Excavated	8.63	< 0.041 U	< 0.064 U	< 0.022 U	< 0.033 U	6.6 J	1.7 J	0.33 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B462	SSHS-B462-SUB-2-3	8/31/2016	855.34	2 - 3 ft	180-58236-1	Excavated	52.9	< 0.085 U	< 0.13 U	< 0.047 U	< 0.069 U	38 J	13 J	1.9 J	< 0.058 U	< 0.035 U
Football Field	SSHS-B463	SSHS-B463-SUB-2-3	8/31/2016	854.92	2 - 3 ft	180-58236-1	Excavated	15.58	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	11 J	3.9 J	0.68 J	< 0.029 U	< 0.017 U
Football Field	SSHS-B464	SSHS-B464-SUB-2-4	8/29/2016	856.94	2 - 4 ft	180-58133-1	Excavated	0.303	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.19 J	0.079 J	0.034 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B464	SSHS-B464-SUB-4-6	8/29/2016	856.94	4 - 6 ft	180-58133-1	Excavated	109.3	< 0.43 U	< 0.67 U	< 0.23 U	< 0.34 U	79 J	27 J	3.3 J	< 0.29 U	< 0.17 U
Football Field	SSHS-B464	SSHS-B464-SUB-6-8	8/29/2016	856.94	6 - 8 ft	180-58133-1	Excavated	1056	< 1.7 U	< 2.7 U	< 0.95 U	< 1.4 U	750 J	270 J	36 J	< 1.2 U	< 0.7 U
Football Field	SSHS-B467	SSHS-B467-SUB-2-4	8/29/2016	856.10	2 - 4 ft	180-58133-1	Excavated	3765	< 4.2 U	< 6.6 U	< 2.3 U	< 3.4 U	2800 J	900 J	65 J	< 2.9 U	< 1.7 U
Football Field	SSHS-B467	SSHS-B467-SUB-4-6	8/29/2016	856.10	4 - 6 ft	180-58133-2	Excavated	308.3	< 0.41 U	< 0.64 U	< 0.22 U	< 0.33 U	220 J	83 J	5.3 J	< 0.28 U	< 0.17 U
Football Field	SSHS-B467	SSHS-B467-SUB-6-8	8/29/2016	856.10	6 - 8 ft	180-58133-2	Excavated	0.025	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.025	< 0.0064 U	< 0.006 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B468	SSHS-B468-SUB-2-4	8/24/2016	855.90	2 - 4 ft	180-57932-1	Excavated	109.7	< 0.41 U	< 0.65 U	< 0.23 U	< 0.33 U	82 J	24 J	3.7 J	< 0.28 U	< 0.17 U
Football Field	SSHS-B468	SSHS-B468-SUB-4-6	8/24/2016	855.90	4 - 6 ft	180-57932-1	Excavated	2.667	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	2 J	0.58 J	0.087 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B469	PS-FD-12	8/29/2016	856.87	2 - 4 ft	180-58133-1	Excavated	0.375	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.14 J	0.19 J	0.045 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B469	SSHS-B469-SUB-2-4	8/29/2016	856.87	2 - 4 ft	180-58133-1	Excavated	0.222	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.17 J	0.052 J	< 0.0064 UJ	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B469	SSHS-B469-SUB-6-8	8/29/2016	856.87	6 - 8 ft	180-58133-1	Excavated	7.9	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	5.6 J	2 J	0.3 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B469	SSHS-B469-SUB-8-10	8/29/2016	856.87	8 - 10 ft	180-58133-1	Excavated	87.9	< 0.44 U	< 0.69 U	< 0.24 U	< 0.35 U	63 J	22 J	2.9 J	< 0.3 U	< 0.18 U
Football Field	SSHS-B469	SSHS-B469-SUB-10-12	8/29/2016	856.87	10 - 12 ft	180-58133-1	Excavated	1032	< 1.8 U	< 2.8 U	< 0.98 U	< 1.4 U	750 J	250 J	32 J	< 1.2 U	< 0.73 U
Football Field	SSHS-B469	SSHS-B469-SUB-12-14	8/29/2016	856.87	12 - 14 ft	180-58133-2	Excavated	555	< 0.86 U	< 1.4 U	< 0.47 U	< 0.69 U	410 J	130 J	15 J	< 0.58 U	< 0.35 U
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Football Field	SSHS-B470	SSHS-B470-SUB-6-8	8/29/2016	856.79	6 - 8 ft	180-58133-1	Excavated	0.298	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	0.18 J	0.1 J	0.018 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B470	SSHS-B470-SUB-8-10	8/29/2016	856.79	8 - 10 ft	180-58133-1	Excavated	174.1	< 0.44 U	< 0.7 U	< 0.24 U	< 0.36 U	120 J	48 J	6.1 J	< 0.3 U	< 0.18 U
Football Field	SSHS-B470	SSHS-B470-SUB-10-12	8/29/2016	856.79	10 - 12 ft	180-58133-1	Excavated	0.494	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.34 J	0.13 J	0.024 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B470	SSHS-B470-SUB-12-14	8/29/2016	856.79	12 - 14 ft	180-58133-2	Excavated	11.4	< 0.042 U	< 0.067 U	< 0.023 U	< 0.034 U	7.6 J	3.3 J	0.5 J	< 0.029 U	< 0.017 U
Football Field	SSHS-B471	PS-FD-6	8/24/2016	855.65	6 - 8 ft	180-57932-1	Excavated	75	< 0.42 U	< 0.67 U	< 0.23 U	< 0.34 U	41 J	34 J		< 0.29 U	< 0.17 U
Football Field	SSHS-B471	SSHS-B471-SUB-6-8	8/24/2016	855.65	6 - 8 ft	180-57932-1	Excavated	81	< 0.41 U	< 0.65 U	< 0.22 U	< 0.33 U	43 J	38 J		< 0.28 U	< 0.17 U
Football Field	SSHS-B471	SSHS-B471-SUB-8-10	8/24/2016	855.65	8 - 10 ft	180-57932-1	Excavated	320	< 0.84 U	< 1.3 U	< 0.46 U	< 0.68 U	< 0.43 U	320 J		< 0.57 U	< 0.34 U
Football Field	SSHS-B472	SSHS-B472-SUB-8-10	8/24/2016	856.11	8 - 10 ft	180-57932-1	Excavated	0.65	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	0.41 J	0.24 J		< 0.0056 U	< 0.0034 U
Football Field	SSHS-B473	SSHS-B473-SUB-4-6	8/30/2016	856.07	4 - 6 ft	180-58129-1	Excavated	0.193	< 0.0089 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.14 J	0.053 J	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B473	PS-FD-15	8/30/2016	856.07	6 - 8 ft	180-58129-1	Excavated	ND	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0067 U	< 0.0043 U	< 0.0067 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B473	SSHS-B473-SUB-6-8	8/30/2016	856.07	6 - 8 ft	180-58129-1	Excavated	ND	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	< 0.0042 U	< 0.0067 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B473	SSHS-B473-SUB-8-10	8/30/2016	856.07	8 - 10 ft	180-58129-1	Excavated	ND	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	< 0.0045 U	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B474	SSHS-B474-SUB-8-10	8/24/2016	856.01	8 - 10 ft	180-57932-1	Excavated	378	< 0.82 U	< 1.3 U	< 0.45 U	< 0.66 U	300 J	67 J	11 J	< 0.56 U	< 0.33 U
Football Field	SSHS-B474	SSHS-B474-SUB-10-12	8/24/2016	856.01	10 - 12 ft	180-57932-2	Excavated	2.298	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	1.5 J	0.71 J	0.088 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B475	PS-FD-13	8/29/2016	856.87	8 - 10 ft	180-58133-1	Excavated	0.9	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.54 J	0.31 J	0.05 J	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B475	SSHS-B475-SUB-8-10	8/29/2016	856.87	8 - 10 ft	180-58133-1	Excavated	0.994	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.6 J	0.34 J	0.054 J	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B475	SSHS-B475-SUB-10-12	8/29/2016	856.87	10 - 12 ft	180-58133-1	Excavated	0.092	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.061 J	0.031 J	< 0.006 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B476	SSHS-B476-SUB-6-8	8/29/2016	855.82	6 - 8 ft	180-58133-1	Excavated	ND	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	< 0.0042 U	< 0.0066 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B477	PS-FD-14	8/29/2016	856.06	2 - 4 ft	180-58133-1	Excavated	2.32	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	1.5 J	0.71 J	0.11 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B477	SSHS-B477-SUB-2-4	8/29/2016	856.06	2 - 4 ft	180-58133-1	Excavated	3.74	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	2.5 J	1.1 J	0.14 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B477	SSHS-B477-SUB-4-6	8/29/2016	856.06	4 - 6 ft	180-58133-1	Excavated	94.1	< 0.41 U	< 0.65 U	< 0.23 U	< 0.33 U	67 J	25 J	2.1 J	< 0.28 U	< 0.17 U
Football Field	SSHS-B477	SSHS-B477-SUB-6-8	8/29/2016	856.06	6 - 8 ft	180-58133-2	Excavated	135.7	< 0.43 U	< 0.67 U	< 0.23 U	< 0.34 U	98 J	35 J	2.7 J	< 0.29 U	< 0.17 U
Football Field	SSHS-B478	SSHS-B478-SUB-6-8	8/25/2016	856.15	6 - 8 ft	180-57995-1	Excavated	31.5	< 0.087 U	< 0.14 U	< 0.048 U	< 0.07 U	21 J	9.4 J	1.1 J	< 0.059 U	< 0.036 U
Football Field	SSHS-B478	SSHS-B478-SUB-8-10	8/25/2016	856.15	8 - 10 ft	180-57995-1	Excavated	21.9	< 0.085 U	< 0.13 U	< 0.047 U	< 0.069 U	13 J	7.7 J	1.2 J	< 0.058 U	< 0.035 U
Football Field	SSHS-B478	SSHS-B478-SUB-10-12	8/25/2016	856.15	10 - 12 ft	180-57995-2	Excavated	0.682	< 0.0085 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.43 J	0.18 J	0.072 J	< 0.0057 U	< 0.0035 U
Football Field	SSHS-B478	SSHS-B478-SUB-12-14	8/25/2016	856.15	12 - 14 ft	180-57995-2	Excavated	13.47	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	7.8 J	5 J	0.67 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B479	SSHS-B479-SUB-4-6	8/29/2016	856.39	4 - 6 ft	180-58133-1	Excavated	14.48	< 0.042 U	< 0.066 U	< 0.023 U	< 0.034 U	9.3 J	4.7 J	0.48 J	< 0.028 U	< 0.017 U
Football Field	SSHS-B479	SSHS-B479-SUB-6-8	8/29/2016	856.39	6 - 8 ft	180-58133-1	Excavated	ND	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	< 0.0042 U	< 0.0066 U	< 0.0061 U	< 0.0056 U	< 0.0033 U
Football Field	SSHS-B479	SSHS-B479-SUB-10-12	8/29/2016	856.39	10 - 12 ft	180-58133-1	Excavated	ND	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	< 0.0042 U	< 0.0066 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B480	SSHS-B480-SUB-10-12	8/29/2016	856.90	10 - 12 ft	180-58133-1	Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0058 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B482	PS-FD-7	8/24/2016	856.12	10 - 12 ft	180-57932-1	Excavated	1.3	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.87 J	0.32 J	0.11 J	< 0.0057 U	< 0.0034 U
Football Field	SSHS-B482	SSHS-B482-SUB-10-12	8/24/2016	856.12	10 - 12 ft	180-57932-1	Excavated	1.96	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	1.4 J	0.41 J	0.15 J	< 0.0055 U	< 0.0033 U
EHS Building	SSHS-B4S	B4-C2-Composite	7/25/2007	-	2 - 2.9 ft	-	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	-	
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	ND	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U	< 0.036 U		
Rear Parking Lot	SSHS-B525	SSHS-B525-SUB-2-4	9/16/2016	853.93	2 - 4 ft	180-58783-1	Excavated	2.91	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	1.6 J	0.98 J	0.33 J	< 0.0054 U	< 0.0033 U
Rear Parking Lot	SSHS-B526	SSHS-B526-SUB-2-4	9/16/2016	853.95	2 - 4 ft	180-58783-1	Excavated	134.5	< 0.42 U	< 0.67 U	< 0.23 U	< 0.34 U	94 J	34 J	6.5 J	< 0.29 U	< 0.17 U
Rear Parking Lot	SSHS-B527	SSHS-B527-SUB-2-4	9/16/2016	853.71	2 - 4 ft	180-58783-1	Excavated	178.9	< 0.43 U	< 0.67 U	< 0.23 U	< 0.34 U	130 J	42 J	6.9 J	< 0.29 U	< 0.17 U
Rear Parking Lot	SSHS-B528	SSHS-B528-SUB-2-4	9/16/2016	853.01	2 - 4 ft	180-58783-1	Excavated	97	< 0.42 U	< 0.67 U	< 0.23 U	< 0.34 U	70 J	23 J	4 J	< 0.29 U	< 0.17 U
Rear Parking Lot	SSHS-B530	PS-FD-35	9/22/2016	851.85	2 - 4 ft	180-59029-1	Excavated	1.51	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.98 J	0.42 J	0.11 J	< 0.0058 U	< 0.0035 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B530	SSHS-B530-SUB-2-4	9/22/2016	851.85	2 - 4 ft	180-59020-1	Excavated	0.675	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	0.43 J	0.21 J	0.035 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B533	SSHS-B533-SUB-8-10	9/22/2016	852.02	8 - 10 ft	180-59029-1	Not Excavated	3.14	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	2.3 J	0.74 J	0.1 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B534	SSHS-B534-SUB-4-6	9/22/2016	852.33	4 - 6 ft	180-59029-1	Not Excavated	11.52	< 0.04 U	< 0.063 U	< 0.022 U	< 0.032 U	8.8 J	2.4 J	0.32 J	< 0.027 U	< 0.016 U
Rear Parking Lot	SSHS-B534	SSHS-B534-SUB-8-10	9/22/2016	852.33	8 - 10 ft	180-59029-1	Not Excavated	5.97	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	4.6 J	1.2 J	0.17 J	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B535	SSHS-B535-SUB-8-10	9/22/2016	851.76	8 - 10 ft	180-59029-1	Not Excavated	0.474	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	0.35 J	0.11 J	0.014 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-4-6	9/21/2016	852.47	4 - 6 ft	180-59020-1	Not Excavated	1.919	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	1.4 J	0.46 J	0.059 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-6-8	9/21/2016	852.47	6 - 8 ft	180-59020-1	Not Excavated	0.297	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.19 J	0.088 J	0.019 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B536	PS-FD-32	9/21/2016	852.47	8 - 10 ft	180-59020-1	Not Excavated	1.549	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	1 J	0.46 J	0.089 J	< 0.0063 U	< 0.0038 U
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-8-10	9/21/2016	852.47	8 - 10 ft	180-59020-1	Not Excavated	1.89	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.0074 U	1.2 J	0.58 J	0.11 J	< 0.0062 U	< 0.0038 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-8-10	9/22/2016	850.44	8 - 10 ft	180-59029-1	Excavated	24.7	< 0.088 U	< 0.14 U	< 0.048 U	< 0.071 U	17 J	6.8 J	0.9 J	< 0.06 U	< 0.036 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-10-12	9/22/2016	850.44	10 - 12 ft	180-59029-1	Not Excavated	ND	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	< 0.0044 U	< 0.007 U	< 0.0065 U	< 0.0059 U	< 0.0036 U
Rear Parking Lot	SSHS-B538	SSHS-B538-SUB-8-10	9/21/2016	851.14	8 - 10 ft	180-59020-1	Excavated	5.87	< 0.0089 U	< 0.014 U	< 0.0048 U	< 0.0071 U	3.9 J	1.5 J	0.17 J	< 0.006 U	< 0.0036 U
Rear Parking Lot	SSHS-B538	SSHS-B538-SUB-10-12	9/21/2016	851.14	10 - 12 ft	180-59020-1	Not Excavated	ND	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	< 0.0047 U	< 0.0073 U	< 0.0068 U	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B539	SSHS-B539-SUB-6-8	9/21/2016	850.60	6 - 8 ft	180-59020-1	Excavated	4.66	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	3.3 J	1.2 J	0.16 J	< 0.006 U	< 0.0036 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	ND	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U		
Rear Parking Lot	SSHS-B540	SSHS-B540-SUB-8-10	9/22/2016	851.56	8 - 10 ft	180-59029-1	Not Excavated	1.864	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	1.3 J	0.49 J	0.074 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B541	SSHS-B541-SUB-8-10	9/21/2016	850.88	8 - 10 ft	180-59020-1	Excavated	2.539	< 0.01 U	< 0.016 U	< 0.0055 U	< 0.0081 U	1.9 J	0.57 J	0.069 J	< 0.0068 U	< 0.0041 U
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-8-10	9/22/2016	850.47	8 - 10 ft	180-59029-1	Excavated	2.112	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	1.6 J	0.44 J	0.072 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-10-12	9/22/2016	850.47	10 - 12 ft	180-59029-1	Not Excavated	ND	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	< 0.0043 U	< 0.0068 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B543	SSHS-B543-SUB-8-10	9/21/2016	851.17	8 - 10 ft	180-59020-1	Not Excavated	10.92	< 0.046 U	< 0.072 U	< 0.025 U	< 0.037 U	8 J	2.5 J	0.42 J	< 0.031 U	< 0.019 U
Rear Parking Lot	SSHS-B543	SSHS-B543-SUB-10-12	9/21/2016	851.17	10 - 12 ft	180-59020-1	Not Excavated	ND	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	< 0.0049 U	< 0.0077 U	< 0.0071 U	< 0.0065 U	< 0.0039 U
Rear Parking Lot	SSHS-B544	SSHS-B544-SUB-4-6	9/22/2016	851.21	4 - 6 ft	180-59029-1	Excavated	0.325	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.22 J	0.09 J	0.015 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B544	SSHS-B544-SUB-8-10	9/22/2016	851.21	8 - 10 ft	180-59029-1	Not Excavated	0.12	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.089 J	0.031 J	< 0.0065 U	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B545	SSHS-B545-SUB-8-10	9/22/2016	850.94	8 - 10 ft	180-59029-1	Not Excavated	0.11	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0073 U	0.11 J	< 0.0073 U	< 0.0067 U	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B545	SSHS-B545-SUB-10-12	9/22/2016	850.94	10 - 12 ft	180-59029-1	Not Excavated	ND	< 0.0086 U	< 0.013 U	< 0.0047 U	< 0.0069 U	< 0.0044 U	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B546	SSHS-B546-SUB-6-8	9/21/2016	850.62	6 - 8 ft	180-59020-1	Excavated	0.139	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.12 J	0.019 J	< 0.0062 U	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B547	SSHS-B547-SUB-6-8	9/21/2016	850.68	6 - 8 ft	180-59020-1	Excavated	ND	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	< 0.0045 U	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	22.85	< 0.052 U	< 0.082 U	< 0.028 U	< 0.042 U	16 J	6 J	0.85 J	< 0.035 U	< 0.021 U
Rear Parking Lot	SSHS-B548	SSHS-B548-SUB-6-8	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	37.5	< 0.092 U	< 0.14 U	< 0.05 U	< 0.074 U	26 J	10 J	1.5 J	< 0.062 U	< 0.037 U
Rear Parking Lot	SSHS-B549	SSHS-B549-SUB-6-8	9/21/2016	850.17	6 - 8 ft	180-59020-1	Not Excavated	0.453	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.3 J	0.13 J	0.023 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-4-6	9/22/2016	851.35	4 - 6 ft	180-59029-1	Not Excavated	3.037	< 0.0086 U	< 0.013 U	< 0.0047 U	< 0.0069 U	2.3 J	0.66 J	0.077 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-6-8	9/22/2016	851.35	6 - 8 ft	180-59029-1	Not Excavated	ND	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	< 0.0043 U	< 0.0068 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-8-10	9/22/2016	851.35	8 - 10 ft	180-59029-1	Not Excavated	0.822	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0076 U	0.64 J	0.16 J	0.022 J	< 0.0064 U	< 0.0039 U
Rear Parking Lot	SSHS-B551	SSHS-B551-SUB-4-6	9/21/2016	851.74	4 - 6 ft	180-59020-1	Excavated	0.339	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	0.17 J	0.14 J	0.029 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-4-6	9/21/2016	853.01	4 - 6 ft	180-59020-1	Not Excavated	68.8	< 0.17 U	< 0.28 U	< 0.095 U	< 0.14 U	53 J	14 J	1.8 J	< 0.12 U	< 0.071 U
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-6-8	9/21/2016	853.01	6 - 8 ft	180-59020-1	Not Excavated	1.23	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.83 J	0.34 J	0.06 J	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-8-10	9/21/2016	853.01	8 - 10 ft	180-59020-1	Not Excavated	1.494	< 0.0094 U	< 0.015 U	< 0.0052 U	< 0.0076 U	1.1 J	0.34 J	0.054 J	< 0.0064 U	< 0.0038 U
Rear Parking Lot	SSHS-B553	SSHS-B553-SUB-4-6	9/21/2016	850.30	4 - 6 ft	180-59020-1	Excavated	10.13	< 0.043 U	< 0.068 U	< 0.024 U	< 0.035 U	7.2 J	2.5 J	0.43 J	< 0.029 U	< 0.018 U
Rear Parking Lot	SSHS-B554	SSHS-B554-SUB-2-4	9/16/2016	852.21	2 - 4 ft	180-58783-1	Not Excavated	0.419	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	0.18 J	0.16 J	0.079 J	< 0.0064 U	< 0.0038 U
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-2-4	8/30/2016	852.49	2 - 4 ft	180-58129-1	Excavated	ND	< 0.008	< 0.013	< 0.0044	< 0.0065	< 0.0041	< 0.0065	< 0.006	< 0.0054	< 0.0033
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-4-6	8/30/2016	852.49	4 - 6 ft	180-58129-1	Excavated	ND	< 0.0082	< 0.013	< 0.0045	< 0.0066	< 0.0042	< 0.0066	< 0.0061	< 0.0055	< 0.0033
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	8/30/2016	852.49	6 - 8 ft	180-58129-1	Not Excavated	ND	< 0.008	< 0.013	< 0.0044	< 0.0064	< 0.0041	< 0.0064	< 0.006	< 0.0054	< 0.0033
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	8/30/2016	852.49	8 - 10 ft	180-58129-1	Not Excavated	ND	< 0.008	< 0.013	< 0.0044	< 0.0065	< 0.0041	< 0.0065	< 0.006	< 0.0054	< 0.0033
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	ND	< 0.0081	< 0.013	< 0.0045	< 0.0066	< 0.0042	< 0.0066	< 0.0061	< 0.0055	< 0.0033
Rear Parking Lot	SSHS-B577	SSHS-B577-SUB-2-4	2/10/2017	856.11	2 - 4 ft	180-63389-1	Excavated	1.3	< 0.0096	< 0.0094	< 0.0071	< 0.014	0.73	0.42	0.15	< 0.013	< 0.0055
Tennis Courts / Main Parking Lot	SSHS-B578	SSHS-B578-SUB-2-4	2/15/2017	856.31	2 - 4 ft	180-63517-1	Not Excavated	1.18	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.4 J	0.53 J	0.25 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B579	SSHS-B579-SUB-2-4	2/15/2017	856.16	2 - 4 ft	180-63517-1	Not Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	2/10/2017	856.11	2 - 4 ft	180-63389-1	Not Excavated	0.697	< 0.0097	< 0.0095	< 0.0072	< 0.015	0.43	0.18	0.087	< 0.013	< 0.0056
Tennis Courts / Main Parking Lot	SSHS-B581	SSHS-B581-SUB-2-4	2/14/2017	856.09	2 - 4 ft	180-63507-1	Not Excavated	0.132	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.086 J	0.046 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B582	SSHS-B582-SUB-2-4	2/14/2017	856.23	2 - 4 ft	180-63507-1	Not Excavated	0.407	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.24 J	0.12 J	0.047 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B583	SSHS-B583-SUB-2-4	2/14/2017	856.19	2 - 4 ft	180-63507-1	Not Excavated	0.122	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.053 J	0.045 J	0.024 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B584	SSHS-B584-SUB-2-4	2/14/2017	855.99	2 - 4 ft	180-63507-1	Not Excavated	2.74	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	1.7 J	0.69 J	0.35 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B584	PS-FD-19	2/14/2017	855.99	2 - 4 ft	180-63507-1	Not Excavated	0.83	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.45 J	0.27 J	0.11 J	< 0.013 U	< 0.0057 U
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	2/10/2017	856.14	2 - 4 ft	180-63389-1	Not Excavated	0.231	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.13	0.068	0.033	< 0.013	< 0.0056
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-2-4	2/10/2017	855.97	2 - 4 ft	180-63389-2	Excavated	0.699	< 0.0095	< 0.0093	< 0.0071	< 0.014	0.46	0.16	0.079	< 0.013	< 0.0055
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	2/10/2017	855.97	4 - 6 ft	180-63389-2	Not Excavated	0.095	< 0.0093	< 0.0091	< 0.0069	< 0.014	0.07	0.025	< 0.012	< 0.013	< 0.0053
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-4-6	2/15/2017	856.06	4 - 6 ft	180-63517-1	Not Excavated	ND	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	< 0.0091 U	< 0.0084 U	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B594	SSHS-B594-SUB-2-4	2/15/2017	856.17	2 - 4 ft	180-63517-2	Not Excavated	0.72	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.36	0.24	0.12	< 0.013 U	< 0.0056 U
Football Field	SSHS-B619	PS-FD-14	2/14/2017	855.58	2 - 4 ft	180-63507-1	Excavated	2.072	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	1.5 J	0.49 J	0.082 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B619	SSHS-B619-SUB-2-4	2/14/2017	855.58	2 - 4 ft	180-63507-1	Excavated	2.52	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.8 J	0.61 J	0.11 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B619	SSHS-B619-SUB-4-6	2/14/2017	855.58	4 - 6 ft	180-63507-1	Excavated	1.026	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.71 J	0.27 J	0.046 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B619	SSHS-B619-SUB-6-8	2/14/2017	855.58	6 - 8 ft	180-63507-1	Excavated	0.125	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.082 J	0.043 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B619	SSHS-B619-SUB-8-10	2/14/2017	855.58	8 - 10 ft	180-63507-1	Excavated	0.607	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.42 J	0.16 J	0.027 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B619	SSHS-B619-SUB-10-12	2/14/2017	855.58	10 - 12 ft	180-63507-1	Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B620	SSHS-B620-SUB-2-4	2/13/2017	855.29	2 - 4 ft	180-63507-1	Excavated	30.8	< 0.097 U	< 0.095 U	< 0.073 U	< 0.15 U	21 J	8.2 J	1.6 J	< 0.13 U	< 0.056 U
Football Field	SSHS-B620	SSHS-B620-SUB-4-6	2/13/2017	855.29	4 - 6 ft	180-63507-1	Excavated	13.2	< 0.1 U	< 0.099 U	< 0.076 U	< 0.15 U	9.2 J	3.4 J	0.6 J	< 0.14 U	< 0.059 U
Football Field	SSHS-B620	PS-FD-13	2/13/2017	855.29	6 - 8 ft	180-63507-1	Excavated	4.92	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	3.2 J	1.4 J	0.32 J	< 0.014 U	< 0.0059 U
Football Field	SSHS-B620	SSHS-B620-SUB-6-8	2/13/2017	855.29	6 - 8 ft	180-63507-1	Excavated	2.33	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	1.6 J	0.58 J	0.15 J	< 0.014 U	< 0.0058 U
Football Field	SSHS-B620	SSHS-B620-SUB-8-10	2/13/2017	855.29	8 - 10 ft	180-63507-1	Excavated	4.83	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	3.4 J	1.2 J	0.23 J	< 0.013 U	< 0.0057 U
Football Field	SSHS-B620	SSHS-B620-SUB-10-12	2/13/2017	855.29	10 - 12 ft	180-63507-1	Excavated	0.017	< 0.0093 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.017	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0053 U
Football Field	SSHS-B621	PS-FD-12	2/13/2017	854.74	6 - 8 ft	180-63507-1	Excavated	0.034	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.025 J	0.009 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-6-8	2/13/2017	854.74	6 - 8 ft	180-63507-1	Excavated	0.0354	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.026 J	0.0094 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-8-10	2/13/2017	854.74	8 - 10 ft	180-63507-1	Excavated	0.434	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.31 J	0.099 J	0.025 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-10-12	2/13/2017	854.74	10 - 12 ft	180-63507-1	Not Excavated	0.826	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.62 J	0.17 J	0.036 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-12-14	2/13/2017	854.74	12 - 14 ft	180-63507-2	Not Excavated	0.268	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.18	0.088	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-14-16	2/13/2017	854.74	14 - 16 ft	180-63507-2	Not Excavated	0.056	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.029	0.027	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B622	SSHS-B622-SUB-4-6	2/16/2017	856.13	4 - 6 ft	180-63593-1	Excavated	22.78	< 0.097 U	< 0.095 U	< 0.073 U	< 0.15 U	17 J	4.9 J	0.88 J	< 0.13 U	< 0.056 U
Football Field	SSHS-B622	SSHS-B622-SUB-6-8	2/16/2017	856.13	6 - 8 ft	180-63593-2	Excavated	2.7	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	1.7	0.87	0.13	< 0.013 U	< 0.0056 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B622	SSHS-B622-SUB-8-10	2/16/2017	856.13	8 - 10 ft	180-63593-2	Not Excavated	6.92	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	4.7	2.1	0.12	< 0.013 U	< 0.0055 U
Football Field	SSHS-B622	SSHS-B622-SUB-10-12	2/16/2017	856.13	10 - 12 ft	180-63593-1	Not Excavated	0.058	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.042 J	0.016 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B624	SSHS-B624-SUB-2-4	2/9/2017	855.38	2 - 4 ft	180-63367-1	Excavated	2.376	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	1.6 J	0.68 J	0.096 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B624	SSHS-B624-SUB-4-6	2/9/2017	855.38	4 - 6 ft	180-63367-1	Excavated	0.47	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.29 J	0.16 J	0.02 J	< 0.014 U	< 0.0058 U
Football Field	SSHS-B624	SSHS-B624-SUB-6-8	2/9/2017	855.38	6 - 8 ft	180-63367-1	Excavated	0.024	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.013 J	0.011 J	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B624	SSHS-B624-SUB-8-10	2/9/2017	855.38	8 - 10 ft	180-63367-1	Excavated	1.701	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	1 J	0.61 J	0.091 J	< 0.013 U	< 0.0057 U
Football Field	SSHS-B624	SSHS-B624-SUB-10-12	2/9/2017	855.38	10 - 12 ft	180-63367-1	Excavated	ND	< 0.011 U	< 0.011 U	< 0.008 U	< 0.016 U	< 0.0097 U	< 0.0089 U	< 0.014 U	< 0.015 U	< 0.0062 U
Football Field	SSHS-B624	SSHS-B624-SUB-12-14	2/9/2017	855.38	12 - 14 ft	180-63367-2	Not Excavated	0.532	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.37	0.13	0.032	< 0.013 U	< 0.0055 U
Football Field	SSHS-B624	SSHS-B624-SUB-14-16	2/9/2017	855.38	14 - 16 ft	180-63367-2	Not Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0082 U	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B625	SSHS-B625-SUB-10-12	2/8/2017	856.01	10 - 12 ft	180-63367-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B625	SSHS-B625-SUB-12-14	2/8/2017	856.01	12 - 14 ft	180-63367-1	Not Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B625A	SSHS-B625A-SUB-10-12	7/11/2017	856.01	10 - 12 ft	180-68095-1	Not Excavated	0.06	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.03	0.03	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B626	SSHS-B626-SUB-10-12	2/9/2017	856.11	10 - 12 ft	180-63367-1	Excavated	0.032	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0087 U	< 0.008 U	0.032	< 0.013 U	< 0.0055 U
Football Field	SSHS-B626	PS-FD-2	2/9/2017	856.11	12 - 14 ft	180-63367-1	Excavated	2.25	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	1.4 J	0.76 J	0.09 J	< 0.013 U	< 0.0054 U
Football Field	SSHS-B626	SSHS-B626-SUB-12-14	2/9/2017	856.11	12 - 14 ft	180-63367-1	Excavated	1.57	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	1.1 J	0.39 J	0.08 J	< 0.013 U	< 0.0054 U
Football Field	SSHS-B627	SSHS-B627-SUB-12-14	2/8/2017	856.12	12 - 14 ft	180-63367-1	Not Excavated	0.66	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.3 J	0.25 J	0.11 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B628	SSHS-B628-SUB-12-14	2/9/2017	855.84	12 - 14 ft	180-63367-1	Not Excavated	0.675	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.32 J	0.29 J	0.065 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B629	SSHS-B629-SUB-6-8	2/9/2017	855.95	6 - 8 ft	180-63367-1	Not Excavated	ND	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B629	SSHS-B629-SUB-8-10	2/9/2017	855.95	8 - 10 ft	180-63367-1	Not Excavated	0.03	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.017 J	0.013 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B629	SSHS-B629-SUB-12-14	2/9/2017	855.95	12 - 14 ft	180-63367-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B629A	SSHS-B629A-SUB-6-8	7/10/2017	855.95	6 - 8 ft	180-68038-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B629A	SSHS-B629A-SUB-8-10	7/10/2017	855.95	8 - 10 ft	180-68038-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B630	PS-FD-17	2/14/2017	855.88	8 - 10 ft	180-63507-1	Excavated	1091	< 5.3 U	< 5.2 U	< 3.9 U	< 7.9 U	860 J	190 J	41 J	< 7.1 U	< 3 U
Football Field	SSHS-B630	SSHS-B630-SUB-8-10	2/14/2017	855.88	8 - 10 ft	180-63507-1	Excavated	1303	< 5.2 U	< 5.1 U	< 3.9 U	< 7.8 U	1000 J	250 J	53 J	< 7.1 U	< 3 U
Football Field	SSHS-B630	SSHS-B630-SUB-10-12	2/14/2017	855.88	10 - 12 ft	180-63507-1	Excavated	59.2	< 0.5 U	< 0.49 U	< 0.37 U	< 0.75 U	46 J	11 J	2.2 J	< 0.67 U	< 0.29 U
Football Field	SSHS-B630	SSHS-B630-SUB-12-14	2/14/2017	855.88	12 - 14 ft	180-63507-1	Excavated	228.7	< 0.98 U	< 0.96 U	< 0.73 U	< 1.5 U	180 J	40 J	8.7 J	< 1.3 U	< 0.56 U
Football Field	SSHS-B630	SSHS-B630-SUB-14-16	2/14/2017	855.88	14 - 16 ft	180-63507-2	Not Excavated	0.216	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.17	0.046	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B630A	SSHS-B630A-SUB-14-16	7/12/2017	855.88	14 - 16 ft	180-68139-1	Not Excavated	2.201	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.7	0.45	0.051	< 0.013 U	< 0.0055 U
Football Field	SSHS-B631	SSHS-B631-SUB-12-14	2/16/2017	856.86	12 - 14 ft	180-63593-1	Excavated	0.128	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.092 J	0.036 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B631	SSHS-B631-SUB-14-16	2/16/2017	856.86	14 - 16 ft	180-63593-2	Excavated	ND	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	< 0.0082 U	< 0.0075 U	< 0.011 U	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-4-6	2/10/2017	855.37	4 - 6 ft	180-63389-1	Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-6-8	2/10/2017	855.37	6 - 8 ft	180-63389-1	Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-8-10	2/10/2017	855.37	8 - 10 ft	180-63389-1	Excavated	0.053	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.033 J	0.02 J	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-10-12	2/10/2017	855.37	10 - 12 ft	180-63389-1	Excavated	ND	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	< 0.0091 U	< 0.0084 U	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B632	SSHS-B632-SUB-12-14	2/10/2017	855.37	12 - 14 ft	180-63389-1	Excavated	0.035	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.023 J	0.012 J	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B632A	PS-FD-2	7/11/2017	855.37	4 - 6 ft	180-68095-1	Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-4-6	7/11/2017	855.37	4 - 6 ft	180-68095-1	Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-6-8	7/11/2017	855.37	6 - 8 ft	180-68095-1	Excavated	ND	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.015 U	< 0.0091 U	< 0.0083 U	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-8-10	7/11/2017	855.37	8 - 10 ft	180-68095-1	Excavated	ND	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	< 0.0091 U	< 0.0084 U	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-10-12	7/11/2017	855.37	10 - 12 ft	180-68095-1	Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B632A	SSHS-B632A-SUB-12-14	7/11/2017	855.37	12 - 14 ft	180-68095-1	Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B632B	SSHS-B632B-SUB-6-8	7/13/2017	855.37	6 - 8 ft	180-68203-1	Excavated	ND	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.015 U	< 0.0091 U	< 0.0083 U	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B632B	SSHS-B632B-SUB-10-12	7/13/2017	855.37	10 - 12 ft	180-68203-1	Excavated	0.01	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.01 J	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-2-4	2/10/2017	855.17	2 - 4 ft	180-63389-1	Excavated	14.93	< 0.09 U	< 0.088 U	< 0.068 U	< 0.14 U	11 J	3.3 J	0.63 J	< 0.12 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B633	PS-FD-5	2/10/2017	855.17	4 - 6 ft	180-63389-1	Excavated	10.47	< 0.048 U	< 0.047 U	< 0.036 U	< 0.071 U	7.3 J	2.8 J	0.37 J	< 0.064 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-4-6	2/10/2017	855.17	4 - 6 ft	180-63389-1	Excavated	4.6	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	3.6 J	0.82 J	0.18 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-6-8	2/10/2017	855.17	6 - 8 ft	180-63389-1	Excavated	0.244	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.16 J	0.084 J	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-8-10	2/10/2017	855.17	8 - 10 ft	180-63389-1	Excavated	3.027	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	2.2 J	0.73 J	0.097 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-10-12	2/10/2017	855.17	10 - 12 ft	180-63389-1	Excavated	373	< 1 U	< 0.98 U	< 0.75 U	< 1.5 U	240 J	120 J	13 J	< 1.4 U	< 0.58 U
Tennis Courts / Main Parking Lot	SSHS-B633	SSHS-B633-SUB-12-14	2/10/2017	855.17	12 - 14 ft	180-63389-1	Excavated	16.45	< 0.049 U	< 0.048 U	< 0.037 U	< 0.074 U	11 J	4.7 J	0.75 J	< 0.067 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-2-4	2/10/2017	855.22	2 - 4 ft	180-63389-2	Excavated	0.274	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.16	0.094	0.02	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-4-6	2/10/2017	855.22	4 - 6 ft	180-63389-2	Excavated	0.00207	< 0.0001 U	< 0.0001 U	< 0.000078 U	< 0.00016 U	0.0015	0.00057	< 0.00013 U	< 0.00014 U	< 0.00006 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-8-10	2/10/2017	855.22	8 - 10 ft	180-63389-1	Excavated	0.154	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.11 J	0.044 J	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-12-14	2/10/2017	855.23	12 - 14 ft	180-63389-1	Not Excavated	0.133	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.087 J	0.046 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B635	SSHS-B635-SUB-8-10	2/16/2017	856.83	8 - 10 ft	180-63593-1	Excavated	17.6	< 0.096 U	< 0.094 U	< 0.072 U	< 0.14 U	12 J	4.7 J	0.9 J	< 0.13 U	< 0.055 U
Football Field	SSHS-B635	SSHS-B635-SUB-12-14	2/16/2017	856.83	12 - 14 ft	180-63593-1	Excavated	1.59	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	1.1 J	0.39 J	0.1 J	< 0.014 U	< 0.0058 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	0.051	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	0.051	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	0.13	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	0.13	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0042 U	< 0.0025 U
Football Field	SSHS-B644	PS-FD-4	2/9/2017	855.30	10 - 12 ft	180-63367-1	Excavated	24.02	< 0.099 U	< 0.097 U	< 0.074 U	< 0.15 U	16 J	7.3 J	0.72 J	< 0.13 U	< 0.057 U
Football Field	SSHS-B644	SSHS-B644-SUB-10-12	2/9/2017	855.30	10 - 12 ft	180-63367-1	Excavated	14.64	< 0.097 U	< 0.095 U	< 0.073 U	< 0.15 U	10 J	4.2 J	0.44 J	< 0.13 U	< 0.056 U
Football Field	SSHS-B644	SSHS-B644-SUB-12-14	2/9/2017	855.30	12 - 14 ft	180-63367-2	Excavated	0.078	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.061	0.017 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B644	SSHS-B644-SUB-14-16	2/9/2017	855.30	14 - 16 ft	180-63367-2	Excavated	22.84	< 0.092 U	< 0.089 U	< 0.068 U	< 0.14 U	16	6.1	0.74	< 0.12 U	< 0.053 U
Football Field	SSHS-B645	SSHS-B645-SUB-10-12	2/13/2017	855.01	10 - 12 ft	180-63507-1	Excavated	9.39	< 0.046 U	< 0.045 U	< 0.035 U	< 0.069 U	5.8 J	2.7 J	0.89 J	< 0.063 U	< 0.027 U
Football Field	SSHS-B645	SSHS-B645-SUB-12-14	2/13/2017	855.01	12 - 14 ft	180-63507-2	Excavated	6.27	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	4.2	1.7	0.37	< 0.013 U	< 0.0054 U
Football Field	SSHS-B645	SSHS-B645-SUB-14-16	2/13/2017	855.01	14 - 16 ft	180-63507-2	Not Excavated	0.078	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.046	0.032	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B646	SSHS-B646-SUB-10-12	2/13/2017	854.99	10 - 12 ft	180-63507-1	Excavated	0.099	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.081 J	0.018 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B646	SSHS-B646-SUB-12-14	2/13/2017	854.99	12 - 14 ft	180-63507-2	Excavated	323	< 4.8 U	< 4.7 U	< 3.6 U	< 7.1 U	220	90	13	< 6.4 U	< 2.7 U
Football Field	SSHS-B646	SSHS-B646-SUB-14-16	2/13/2017	854.99	14 - 16 ft	180-63507-2	Not Excavated	0.96	< 0.0095 U	< 0.0093 U	< 0.0071 U	0.96	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B647	PS-FD-24	2/16/2017	856.87	14 - 16 ft	180-63593-1	Excavated	14.29	< 0.094 U	< 0.092 U	< 0.07 U	< 0.14 U	11 J	2.7 J	0.59 J	< 0.13 U	< 0.054 U
Football Field	SSHS-B647	SSHS-B647-SUB-14-16	2/16/2017	856.87	14 - 16 ft	180-63593-1	Excavated	14.33	< 0.047 U	< 0.046 U	< 0.035 U	< 0.07 U	11 J	2.8 J	0.53 J	< 0.064 U	< 0.027 U
Football Field	SSHS-B649	SSHS-B649-SUB-2-4	2/9/2017	855.70	2 - 4 ft	180-63367-1	Excavated	3.48	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	2.6 J	0.88 J		< 0.014 U	< 0.0058 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	76.4	< 0.14 U	< 0.18 U	< 0.16 U	< 0.15 U	71	< 0.13 U	5.4	< 0.2 U	< 0.12 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	2.17	< 0.0031 U	< 0.004 U	< 0.0036 U	< 0.0034 U	2	< 0.003 U	0.17	< 0.0046 U	< 0.0027 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Football Field	SSHS-B650	SSHS-B650-SUB-2-4	2/14/2017	855.56	2 - 4 ft	180-63507-1	Excavated	16.87	< 0.098 U	< 0.095 U	< 0.073 U	< 0.15 U	12 J	3.9 J	0.77 J	< 0.13 U	< 0.056 U
Football Field	SSHS-B650	SSHS-B650-SUB-4-6	2/14/2017	855.56	4 - 6 ft	180-63507-1	Excavated	2.92	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	2 J	0.78 J	0.14 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B650	SSHS-B650-SUB-6-8	2/14/2017	855.56	6 - 8 ft	180-63507-1	Excavated	20.99	< 0.1 U	< 0.1 U	< 0.077 U	< 0.15 U	15 J	5.1 J	0.89 J	< 0.14 U	< 0.059 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B650	SSHS-B650-SUB-8-10	2/14/2017	855.56	8 - 10 ft	180-63507-1	Excavated	1.936	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	1.4 J	0.45 J	0.086 J	< 0.013 U	< 0.0057 U
Football Field	SSHS-B650	SSHS-B650-SUB-10-12	2/14/2017	855.56	10 - 12 ft	180-63507-1	Excavated	0.039	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.023 J	0.016 J	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B650	SSHS-B650-SUB-12-14	2/14/2017	855.56	12 - 14 ft	180-63507-2	Excavated	1.787	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	1.3	0.4	0.087	< 0.013 U	< 0.0054 U
Football Field	SSHS-B650	SSHS-B650-SUB-14-16	2/14/2017	855.56	14 - 16 ft	180-63507-2	Not Excavated	ND	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B651	SSHS-651-SUB-2-4	2/14/2017	855.56	2 - 4 ft	180-63507-1	Excavated	0.606	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.39 J	0.18 J	0.036 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B651	SSHS-B651-SUB-4-6	2/14/2017	855.56	4 - 6 ft	180-63507-1	Excavated	0.64	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.42 J	0.19 J	0.03 J	< 0.013 U	< 0.0054 U
Football Field	SSHS-B651	PS-FD-15	2/14/2017	855.56	6 - 8 ft	180-63507-1	Excavated	ND	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	< 0.0096 U	< 0.0088 U	< 0.013 U	< 0.014 U	< 0.0061 U
Football Field	SSHS-B651	SSHS-B651-SUB-6-8	2/14/2017	855.56	6 - 8 ft	180-63507-1	Excavated	ND	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.016 U	< 0.0098 U	< 0.009 U	< 0.014 U	< 0.015 U	< 0.0063 U
Football Field	SSHS-B651	SSHS-B651-SUB-8-10	2/14/2017	855.56	8 - 10 ft	180-63507-1	Excavated	0.979	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.016 U	0.64 J	0.29 J	0.049 J	< 0.014 U	< 0.006 U
Football Field	SSHS-B651	SSHS-B651-SUB-10-12	2/14/2017	855.56	10 - 12 ft	180-63507-1	Excavated	ND	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	< 0.0095 U	< 0.0087 U	< 0.013 U	< 0.014 U	< 0.0061 U
Football Field	SSHS-B651	SSHS-B651-SUB-12-14	2/14/2017	855.56	12 - 14 ft	180-63507-2	Not Excavated	0.069	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.05	0.019	< 0.012 U	< 0.013 U	< 0.0053 U
Football Field	SSHS-B651	SSHS-B651-SUB-14-16	2/14/2017	855.56	14 - 16 ft	180-63507-2	Not Excavated	ND	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.014 U	< 0.0081 U	< 0.0075 U	< 0.011 U	< 0.012 U	< 0.0052 U
Football Field	SSHS-B652	SSHS-B652-SUB-2-4	2/14/2017	855.55	2 - 4 ft	180-63507-1	Excavated	5.83	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	4.5 J	1.1 J	0.23 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B652	SSHS-B652-SUB-4-6	2/14/2017	855.55	4 - 6 ft	180-63507-1	Excavated	195.7	< 1 U	< 0.98 U	< 0.75 U	< 1.5 U	150 J	39 J	6.7 J	< 1.4 U	< 0.58 U
Football Field	SSHS-B652	PS-FD-16	2/14/2017	855.55	6 - 8 ft	180-63507-1	Excavated	52.9	< 0.49 U	< 0.48 U	< 0.37 U	< 0.74 U	40 J	11 J	1.9 J	< 0.67 U	< 0.28 U
Football Field	SSHS-B652	SSHS-B652-SUB-6-8	2/14/2017	855.55	6 - 8 ft	180-63507-1	Excavated	101.6	< 0.99 U	< 0.96 U	< 0.74 U	< 1.5 U	77 J	21 J	3.6 J	< 1.3 U	< 0.57 U
Football Field	SSHS-B652	SSHS-B652-SUB-8-10	2/14/2017	855.55	8 - 10 ft	180-63507-1	Excavated	108.7	< 0.97 U	< 0.95 U	< 0.72 U	< 1.5 U	84 J	21 J	3.7 J	< 1.3 U	< 0.56 U
Football Field	SSHS-B652	SSHS-B652-SUB-10-12	2/14/2017	855.55	10 - 12 ft	180-63507-1	Excavated	0.075	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.056 J	0.019 J	< 0.011 U	< 0.012 U	< 0.0052 U
Football Field	SSHS-B652	SSHS-B652-SUB-12-14	2/14/2017	855.55	12 - 14 ft	180-63507-2	Not Excavated	19.24	< 0.094 U	< 0.092 U	< 0.07 U	< 0.14 U	15	3.6	0.64	< 0.13 U	< 0.054 U
Football Field	SSHS-B652	SSHS-B652-SUB-14-16	2/14/2017	855.55	14 - 16 ft	180-63507-2	Not Excavated	0.45	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.33	0.12	< 0.012 U	< 0.012 U	< 0.0053 U
Football Field	SSHS-B653	SSHS-B653-SUB-4-6	2/14/2017	855.63	4 - 6 ft	180-63507-1	Excavated	13.22	< 0.099 U	< 0.097 U	< 0.074 U	< 0.15 U	9.9 J	2.8 J	0.52 J	< 0.13 U	< 0.057 U
Football Field	SSHS-B653	SSHS-B653-SUB-6-8	2/14/2017	855.63	6 - 8 ft	180-63507-1	Excavated	22.9	< 0.1 U	< 0.099 U	< 0.076 U	< 0.15 U	17 J	5.9 J		< 0.14 U	< 0.058 U
Football Field	SSHS-B653	SSHS-B653-SUB-8-10	2/14/2017	855.63	8 - 10 ft	180-63507-1	Excavated	11.91	< 0.1 U	< 0.098 U	< 0.075 U	< 0.15 U	8.9 J	2.5 J	0.51 J	< 0.14 U	< 0.058 U
Football Field	SSHS-B653	SSHS-B653-SUB-10-12	2/14/2017	855.63	10 - 12 ft	180-63507-1	Excavated	7.4	< 0.1 U	< 0.1 U	< 0.076 U	< 0.15 U	5.6 J	1.5 J	0.3 J	< 0.14 U	< 0.059 U
Football Field	SSHS-B653	SSHS-B653-SUB-12-14	2/14/2017	855.63	12 - 14 ft	180-63507-2	Not Excavated	5.41	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	4.1	1.1	0.21	< 0.013 U	< 0.0055 U
Football Field	SSHS-B653	SSHS-B653-SUB-14-16	2/14/2017	855.63	14 - 16 ft	180-63507-2	Not Excavated	0.354	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.28	0.074	< 0.012 U	< 0.013 U	< 0.0053 U
Football Field	SSHS-B654	SSHS-B654-SUB-4-6	2/16/2017	855.76	4 - 6 ft	180-63593-1	Excavated	0.951	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.68 J	0.23 J	0.041 J	< 0.013 U	< 0.0057 U
Football Field	SSHS-B654	SSHS-B654-SUB-8-10	2/16/2017	855.76	8 - 10 ft	180-63593-1	Excavated	0.207	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.15 J	0.057 J	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B654	SSHS-B654-SUB-10-12	2/16/2017	855.76	10 - 12 ft	180-63593-1	Not Excavated	0.0316	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.022 J	0.0096 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B655	SSHS-B655-SUB-4-6	2/13/2017	855.38	4 - 6 ft	180-63507-1	Excavated	7.26	< 0.048 U	< 0.047 U	< 0.036 U	< 0.072 U	5 J	1.9 J	0.36 J	< 0.065 U	< 0.028 U
Football Field	SSHS-B655	SSHS-B655-SUB-6-8	2/13/2017	855.38	6 - 8 ft	180-63507-1	Excavated	0.025	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.016 U	0.025	< 0.0086 U	< 0.013 U	< 0.014 U	< 0.006 U
Football Field	SSHS-B655	SSHS-B655-SUB-8-10	2/13/2017	855.38	8 - 10 ft	180-63507-2	Excavated	7.07	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	4.1	2.4	0.57	< 0.013 U	< 0.0057 U
Football Field	SSHS-B656	SSHS-B656-SUB-10-12	2/14/2017	855.93	10 - 12 ft	180-63507-1	Excavated	0.047	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.036 J	0.011 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B656	SSHS-B656-SUB-12-14	2/14/2017	855.93	12 - 14 ft	180-63507-1	Not Excavated	0.618	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.45 J	0.15 J	0.018 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B657	SSHS-B657-SUB-14-16	2/10/2017	856.13	14 - 16 ft	180-63389-1	Not Excavated	0.045	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.023 J	0.022 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B657A	SSHS-B657A-SUB-14-16	7/12/2017	856.13	14 - 16 ft	180-68139-1	Not Excavated	0.0189	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.01 J	0.0089 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B658	SSHS-B658-SUB-14-16	2/16/2017	856.80	14 - 16 ft	180-63593-1	Excavated	0.028	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.013 U	0.017 J	0.011 J	< 0.011 U	< 0.012 U	< 0.0052 U
Football Field	SSHS-B659	SSHS-B659-SUB-8-10	2/16/2017	856.83	8 - 10 ft	180-63593-1	Excavated	0.65	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.54 J	0.11 J	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B659	PS-FD-27	2/16/2017	856.83	12 - 14 ft	180-63593-1	Excavated	0.885	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.58 J	0.28 J	0.025 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B659	SSHS-B659-SUB-12-14	2/16/2017	856.83	12 - 14 ft	180-63593-1	Excavated	0.867	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.58 J	0.26 J	0.027 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B659	SSHS-B659-SUB-14-16	2/16/2017	856.83	14 - 16 ft	180-63593-2	Not Excavated	0.0188	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.0094 J	0.0094 J	< 0.012 U	< 0.013 U	< 0.0054 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	27.2	< 0.054 U	< 0.07 U	< 0.063 U	< 0.06 U	26	< 0.052 U	1.2	< 0.08 U	< 0.047 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	0.91	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	0.91	< 0.0025 U		< 0.0038 U	< 0.0023 U
Football Field	SSHS-B660	SSHS-B660-SUB-4-6	2/15/2017	856.21	4 - 6 ft	180-63517-1	Excavated	2.09	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	1.5 J	0.48 J	0.11 J	< 0.014 U	< 0.0058 U
Football Field	SSHS-B661	SSHS-B661-SUB-4-6	2/13/2017	855.41	4 - 6 ft	180-63507-1	Excavated	3.44	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	2.4 J	0.82 J	0.22 J	< 0.014 U	< 0.006 U
Football Field	SSHS-B662	021617 08:35_PS-FD-23	2/15/2017	855.93	4 - 6 ft	180-63517-1	Excavated	0.739	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.54 J	0.16 J	0.039 J	< 0.013 U	< 0.0057 U
Football Field	SSHS-B662	021617 08:35_SSHS-B662-SUB-4-6	2/15/2017	855.93	4 - 6 ft	180-63517-1	Excavated	1.645	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	1.2 J	0.36 J	0.085 J	< 0.014 U	< 0.0057 U
Northern Athletic Field	SSHS-B664	SSHS-B664-SUB-2-4	2/15/2017	856.32	2 - 4 ft	180-63517-1	Excavated	0.521	< 0.01	< 0.0097	< 0.0074	< 0.015	0.25	0.21	0.061	< 0.013	< 0.0057
Football Field	SSHS-B666	021617 08:35_SSHS-B666-SUB-8-10	2/13/2017	855.57	8 - 10 ft	180-63507-1	Excavated	1.627	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.2 J	0.36 J	0.067 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B667	021117 09:30_SSHS-B667-SUB-10-12	2/10/2017	855.94	10 - 12 ft	180-63389-1	Excavated	30.1	< 0.1 U	< 0.1 U	< 0.078 U	< 0.16 U	20 J	8.1 J	2 J	< 0.14 U	< 0.06 U
Football Field	SSHS-B667	021117 09:30_SSHS-B667-SUB-12-14	2/10/2017	855.94	12 - 14 ft	180-63389-2	Excavated	8.86	< 0.011 U	< 0.011 U	< 0.0083 U	< 0.017 U	6.6	1.9	0.36	< 0.015 U	< 0.0064 U
Football Field	SSHS-B667	021117 09:30_SSHS-B667-SUB-14-16	2/10/2017	855.94	14 - 16 ft	180-63389-2	Excavated	0.997	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.71	0.24	0.047	< 0.013 U	< 0.0056 U
Football Field	SSHS-B668	021017 09:20_SSHS-B668-SUB-10-12	2/9/2017	855.60	10 - 12 ft	180-63367-1	Excavated	223	< 0.96 U	< 0.94 U	< 0.72 U	< 1.4 U	150 J	55 J	18 J	< 1.3 U	< 0.55 U
Football Field	SSHS-B668	021017 09:20_SSHS-B668-SUB-12-14	2/9/2017	855.60	12 - 14 ft	180-63367-2	Excavated	100.3	< 0.49 U	< 0.48 U	< 0.37 U	< 0.74 U	49	43	8.3	< 0.66 U	< 0.28 U
Football Field	SSHS-B669	021617 08:35_SSHS-B669-SUB-10-12	2/13/2017	855.09	10 - 12 ft	180-63507-1	Excavated	0.605	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.013 U	0.49 J	0.093 J	0.022 J	< 0.012 U	< 0.0052 U
Football Field	SSHS-B669	021617 08:35_SSHS-B669-SUB-12-14	2/13/2017	855.09	12 - 14 ft	180-63507-2	Excavated	33.9	< 0.098 U	< 0.096 U	< 0.073 U	< 0.15 U	22	9.9	2	< 0.13 U	< 0.056 U
Football Field	SSHS-B669	021617 08:35_SSHS-B669-SUB-14-16	2/13/2017	855.09	14 - 16 ft	180-63507-2	Excavated	0.345	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.22	0.11	0.015 J	< 0.013 U	< 0.0055 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	168.3	< 0.59 U	< 0.75 U	< 0.68 U	< 0.64 U	160	< 0.56 U	8.3	< 0.86 U	< 0.51 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	0.522	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	0.5	< 0.0026 U	0.022	< 0.004 U	< 0.0023 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	0.065	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	0.065	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Football Field	SSHS-B670	021617 08:35_PS-FD-18	2/14/2017	855.88	14 - 16 ft	180-63507-1	Excavated	0.129	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.083 J	0.046 J	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B670	021617 08:35_SSHS-B670-SUB-14-16	2/14/2017	855.88	14 - 16 ft	180-63507-1	Excavated	0.097	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.067 J	0.03 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B671	021117 09:30_SSHS-B671-SUB-10-12	2/10/2017	856.12	10 - 12 ft	180-63389-1	Excavated	ND	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	< 0.009 U	< 0.0083 U	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B671	021117 09:30_PS-FD-6	2/10/2017	856.12	14 - 16 ft	180-63389-1	Excavated	ND	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B671	021117 09:30_SSHS-B671-SUB-14-16	2/10/2017	856.12	14 - 16 ft	180-63389-1	Excavated	ND	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B671A	071117 08:30_SSHS-B671A-SUB-10-12	7/10/2017	856.12	10 - 12 ft	180-68038-1	Excavated	0.28	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	< 0.0092 U	0.17 J	0.11 J	< 0.014 U	< 0.0059 U
Football Field	SSHS-B671A	071317 07:30_SSHS-B671A-SUB-14-16	7/12/2017	856.12	14 - 16 ft	180-68139-1	Excavated	0.026	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.014 J	0.012 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B672	021817 08:50_PS-FD-26	2/16/2017	856.89	6 - 8 ft	180-63593-1	Excavated	0.028	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.018 J	0.01 J	< 0.012 U	< 0.013 U	< 0.0053 U
Football Field	SSHS-B672	021817 08:50_SSHS-B672-SUB-6-8	2/16/2017	856.89	6 - 8 ft	180-63593-1	Excavated	0.075	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.05 J	0.025 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B673	021817 08:50_SSHS-B673-SUB-8-10	2/16/2017	855.92	8 - 10 ft	180-63593-1	Excavated	0.446	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.35 J	0.096 J	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B673	021817 08:50_SSHS-B673-SUB-10-12	2/16/2017	855.92	10 - 12 ft	180-63593-1	Excavated	0.057	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.046 J	0.011 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B674	032217 08:50_SSHS-B674-SUB-2-4	3/21/2017	856.28	2 - 4 ft	180-64494-3	Excavated	0.241	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.015 U	< 0.0091 U	0.17	0.071	< 0.014 U	< 0.0058 U
Northern Athletic Field	SSHS-B677	SSHS-B677-SUB-2-4	3/21/2017	856.08	2 - 4 ft	180-64494-3	Excavated	ND	< 0.0099	< 0.0096	< 0.0074	< 0.015	< 0.0089	< 0.0081	< 0.012	< 0.013	< 0.0057
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-2-4	3/21/2017	855.48	2 - 4 ft	180-64494-3	Excavated	11.85	< 0.049 U,F1	< 0.048 U	< 0.037 U	< 0.073 U	8.8	2.4	0.65	< 0.066 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-4-6	3/21/2017	855.48	4 - 6 ft	180-64494-2	Excavated	1.788	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.3	0.4	0.088	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_PS-FD-5	3/21/2017	855.48	10 - 12 ft	180-64494-2	Excavated	0.329	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.016 U	0.2	0.096	0.033	< 0.014 U	< 0.006 U
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-10-12	3/21/2017	855.48	10 - 12 ft	180-64494-1	Excavated	0.365	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.24	0.093	0.032	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-12-14	3/21/2017	855.48	12 - 14 ft	180-64494-3	Excavated	1.014	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.74	0.22	0.054	< 0.013 U	< 0.0056 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B679	032217 08:50_SSHS-B679-SUB-14-16	3/21/2017	855.48	14 - 16 ft	180-64494-2	Excavated	1.456	< 0.01 U,F1	< 0.0099 U	< 0.0076 U	< 0.015 U	1.1	0.3	0.056	< 0.014 U	< 0.0058 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	63	< 0.13 U	< 0.17 U	< 0.16 U	< 0.15 U	60	< 0.13 U	3	< 0.2 U	< 0.12 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	0.59	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	0.49	< 0.0026 U	0.1	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-2-4	3/20/2017	855.39	2 - 4 ft	180-64445-3	Excavated	0.259	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.19	0.054	0.015 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-4-6	3/20/2017	855.39	4 - 6 ft	180-64445-2	Excavated	0.127	< 0.0094 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.095	0.032	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-10-12	3/20/2017	855.39	10 - 12 ft	180-64445-1	Excavated	0.969	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.75	0.17	0.049	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-12-14	3/20/2017	855.39	12 - 14 ft	180-64445-3	Excavated	0.243	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.18	0.049	0.014 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B680	032117 09:20_SSHS-B680-SUB-14-16	3/20/2017	855.39	14 - 16 ft	180-64445-2	Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-2-4	3/20/2017	855.30	2 - 4 ft	180-64445-3	Excavated	0.258	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.17	0.068	0.02	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-4-6	3/20/2017	855.30	4 - 6 ft	180-64445-2	Excavated	0.133	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.076	0.043	0.014 J	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_PS-FD-2	3/20/2017	855.30	8 - 10 ft	180-64445-2	Excavated	0.154	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.11	0.044	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-8-10	3/20/2017	855.30	8 - 10 ft	180-64445-1	Excavated	0.156	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.099	0.041	0.016 J	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-10-12	3/20/2017	855.30	10 - 12 ft	180-64445-1	Excavated	0.619	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.47	0.11	0.039	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-12-14	3/20/2017	855.30	12 - 14 ft	180-64445-3	Excavated	0.157	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.11	0.033	0.014 J	< 0.014 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B681	032117 09:20_SSHS-B681-SUB-14-16	3/20/2017	855.30	14 - 16 ft	180-64445-2	Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	10 - 12 ft	180-64526-1	Not Excavated	0.2	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.2	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-12-14	3/22/2017	855.02	12 - 14 ft	180-64526-1	Not Excavated	0.887	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.52	0.27	0.097	< 0.013 U	< 0.0056 U
Football Field	SSHS-B684	032317 09:00_SSHS-B684-SUB-10-12	3/22/2017	855.71	10 - 12 ft	180-64526-1	Excavated	200	< 0.98 U	< 0.96 U	< 0.73 U	< 1.5 U	< 0.88 U	200	< 1.2 U	< 1.3 U	< 0.56 U
Football Field	SSHS-B684	032317 09:00_SSHS-B684-SUB-12-14	3/22/2017	855.71	12 - 14 ft	180-64526-1	Excavated	410	< 0.97 U	< 0.95 U	< 0.72 U	< 1.5 U	< 0.87 U	410	< 1.2 U	< 1.3 U	< 0.56 U
Football Field	SSHS-B685	032417 08:45_SSHS-B685-SUB-10-12	3/23/2017	855.54	10 - 12 ft	180-64584-1	Excavated	ND	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B685	032417 08:45_SSHS-B685-SUB-12-14	3/23/2017	855.54	12 - 14 ft	180-64584-1	Excavated	0.541	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.4	0.12	0.021	< 0.013 U	< 0.0057 U
Football Field	SSHS-B685	032417 08:45_SSHS-B685-SUB-14-16	3/23/2017	855.54	14 - 16 ft	180-64584-2	Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B685A	071317 07:30_SSHS-B685A-SUB-14-16	7/12/2017	855.54	14 - 16 ft	180-68139-1	Excavated	7.04	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.016 U	4.8	2	0.24	< 0.014 U	< 0.006 U
Football Field	SSHS-B686	032317 09:00_SSHS-B686-SUB-10-12	3/22/2017	855.76	10 - 12 ft	180-64526-3	Excavated	0.021	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.021	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B686	032317 09:00_SSHS-B686-SUB-12-14	3/22/2017	855.76	12 - 14 ft	180-64526-1	Excavated	0.737	< 0.0093 U,F2,F1	< 0.009 U	< 0.0069 U	< 0.014 U	0.56	0.15	0.027	< 0.013 U	< 0.0053 U
Football Field	SSHS-B686A	071117 08:30_SSHS-B686A-SUB-10-12	7/10/2017	855.76	10 - 12 ft	180-68038-1	Excavated	4.91	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	3.5 J	1.3 J	0.11 J	< 0.013 U	< 0.0057 U
Football Field	SSHS-B687	032317 09:00_SSHS-B687-SUB-10-12	3/22/2017	855.95	10 - 12 ft	180-64526-3	Excavated	ND	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	408	< 0.59 U	< 0.75 U	< 0.68 U	< 0.64 U	390	< 0.56 U	18	< 0.87 U	< 0.51 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	63.7	< 0.14 U	< 0.18 U	< 0.16 U	< 0.15 U	61	< 0.13 U	2.7	< 0.2 U	< 0.12 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	50.2	< 0.14 U	< 0.17 U	< 0.16 U	< 0.15 U	48	< 0.13 U	2.2	< 0.2 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B694	032217 08:50_SSHS-B694-SUB-10-12	3/21/2017	855.61	10 - 12 ft	180-64494-1	Excavated	ND	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	< 0.009 U	< 0.0083 U	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-2-4	3/20/2017	855.50	2 - 4 ft	180-64445-1	Excavated	2.1	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	1.3	0.52	0.28	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-4-6	3/20/2017	855.50	4 - 6 ft	180-64445-2	Excavated	2.65	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	1.6	0.86	0.19	< 0.014 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_PS-FD-1	3/20/2017	855.50	10 - 12 ft	180-64445-2	Excavated	0.183	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.096	0.07	0.017 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-10-12	3/20/2017	855.50	10 - 12 ft	180-64445-1	Excavated	0.27	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.13	0.09	0.05	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B696	032117 09:20_SSHS-B696-SUB-12-14	3/20/2017	855.50	12 - 14 ft	180-64445-1	Excavated	0.605	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.55		0.055	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-2-4	3/21/2017	855.71	2 - 4 ft	180-64494-1	Excavated	153.5	< 1 U	< 0.98 U	< 0.75 U	< 1.5 U	110	38	5.5	< 1.4 U	< 0.58 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	4 - 6 ft	180-64494-2	Not Excavated	4.54	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	3.5	0.88	0.16	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	10 - 12 ft	180-64494-1	Not Excavated	1.22	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.74	0.36	0.12	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	12 - 14 ft	180-64494-1	Not Excavated	2.66	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	2.1	0.46	0.1	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	14 - 16 ft	180-64494-2	Not Excavated	0.023	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.023	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	4.1	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	3.9	< 0.0026 U	0.2	< 0.004 U	< 0.0023 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	41.3	< 0.14 U	< 0.18 U	< 0.16 U	< 0.15 U	39	< 0.13 U	2.3	< 0.2 U	< 0.12 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	3.3	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	3.3	< 0.0026 U	< 0.0041 U	< 0.0024 U
Football Field	SSHS-B700	032317 09:00_SSHS-B700-SUB-6-8	3/22/2017	855.42	6 - 8 ft	180-64526-2	Excavated	0.0254	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.017	0.0084 J	< 0.012 U	< 0.012 U	< 0.0053 U
Football Field	SSHS-B700	032317 09:00_SSHS-B700-SUB-10-12	3/22/2017	855.42	10 - 12 ft	180-64526-1	Excavated	ND	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	< 0.0092 U	< 0.0084 U	< 0.013 U	< 0.014 U	< 0.0059 U
Football Field	SSHS-B700	032317 09:00_PS-FD-7	3/22/2017	855.42	12 - 14 ft	180-64526-2	Excavated	0.322	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.24	0.064	0.018	< 0.013 U	< 0.0056 U
Football Field	SSHS-B700	032317 09:00_SSHS-B700-SUB-12-14	3/22/2017	855.42	12 - 14 ft	180-64526-1	Excavated	0.482	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.34	0.11	0.032	< 0.014 U	< 0.0059 U
Football Field	SSHS-B701	032417 08:45_SSHS-B701-SUB-8-10	3/23/2017	855.93	8 - 10 ft	180-64584-2	Excavated	0.152	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.11	0.042	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B701	032417 08:45_SSHS-B701-SUB-10-12	3/23/2017	855.93	10 - 12 ft	180-64584-1	Excavated	ND	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.009 U	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B701	032417 08:45_SSHS-B701-SUB-12-14	3/23/2017	855.93	12 - 14 ft	180-64584-1	Excavated	0.271	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.2	0.058	0.013 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B704	032117 09:20_SSHS-B704-SUB-2-4	3/20/2017	855.70	2 - 4 ft	180-64445-1	Excavated	0.661	< 0.01 U,F1	< 0.01 U	< 0.0078 U	< 0.016 U	0.49	0.12	0.051	< 0.014 U	< 0.006 U
Football Field	SSHS-B706	032317 09:00_SSHS-B706-SUB-10-12	3/22/2017	855.85	10 - 12 ft	180-64526-1	Excavated	0.094	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.048	0.022	0.024	< 0.013 U	< 0.0056 U
Football Field	SSHS-B707	032317 09:00_SSHS-B707-SUB-4-6	3/22/2017	855.86	4 - 6 ft	180-64526-2	Excavated	11.49	< 0.049 U	< 0.048 U	< 0.037 U	< 0.074 U	8.3	2.7	0.49	< 0.066 U	< 0.028 U
Football Field	SSHS-B707	032317 09:00_PS-FD-8	3/22/2017	855.86	4 - 6 ft	180-64526-2	Excavated	7.53	< 0.052 U	< 0.05 U	< 0.039 U	< 0.077 U	5.4	1.8	0.33	< 0.07 U	< 0.03 U
Football Field	SSHS-B707	032317 09:00_SSHS-B707-SUB-10-12	3/22/2017	855.86	10 - 12 ft	180-64526-1	Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B709	032317 09:00_SSHS-B709-SUB-6-8	3/22/2017	855.37	6 - 8 ft	180-64526-2	Excavated	0.037	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.026	0.011 J	< 0.012 U	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	ND	< 0.0027	< 0.0034	< 0.0031	< 0.0029	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0023
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0016	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Football Field	SSHS-B710	032417 08:45_SSHS-B710-SUB-6-8	3/23/2017	856.19	6 - 8 ft	180-64584-2	Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B711	032417 08:45_SSHS-B711-SUB-6-8	3/23/2017	856.17	6 - 8 ft	180-64584-2	Excavated	1.318	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.015 U	0.86	0.38	0.078	< 0.014 U	< 0.0058 U
Football Field	SSHS-B712	032317 09:00_SSHS-B712-SUB-10-12	3/22/2017	856.16	10 - 12 ft	180-64526-2	Excavated	0.0249	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.015 J	0.0099 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B712A	071117 08:30_SSHS-B712A-SUB-10-12	7/10/2017	856.16	10 - 12 ft	180-68038-1	Excavated	1.2	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	< 0.0088 U	1.2 J		< 0.013 U	< 0.0056 U
Football Field	SSHS-B714	032317 09:00_SSHS-B714-SUB-12-14	3/22/2017	856.03	12 - 14 ft	180-64526-2	Excavated	0.203	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.14	0.049	0.014 J	< 0.014 U	< 0.0059 U
Football Field	SSHS-B715	032317 09:00_PS-FD-6	3/22/2017	855.86	8 - 10 ft	180-64526-2	Excavated	2.277	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.8	0.4	0.077	< 0.013 U	< 0.0055 U
Football Field	SSHS-B715	032317 09:00_SSHS-B715-SUB-8-10	3/22/2017	855.856	8 - 10 ft	180-64526-2	Excavated	2.591	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	2	0.5	0.091	< 0.014 U	< 0.0059 U
Football Field	SSHS-B715	032317 09:00_SSHS-B715-SUB-12-14	3/22/2017	855.86	12 - 14 ft	180-64526-2	Excavated	0.237	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.18	0.045	0.012 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B716	032117 09:20_SSHS-B716-SUB-14-16	3/20/2017	855.07	14 - 16 ft	180-64445-2	Excavated	0.369	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.23	0.12	0.019	< 0.013 U	< 0.0054 U
Football Field	SSHS-B717	032417 08:45_SSHS-B717-SUB-14-16	3/23/2017	855.76	14 - 16 ft	180-64584-2	Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B717A	071317 07:30_SSHS-B717A-SUB-14-16	7/12/2017	855.76	14 - 16 ft	180-68139-1	Excavated	0.027	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.027	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B718	032217 08:50_SSHS-B718-SUB-14-16	3/21/2017	855.73	14 - 16 ft	180-64494-2	Excavated	0.0096	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.0096 J	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B718A	071317 07:30_SSHS-B718A-SUB-14-16	7/12/2017	855.73	14 - 16 ft	180-68139-1	Excavated	0.012	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.012 J	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B719	SSHS-B719-SUB-14-16	3/22/2017	855.53	14 - 16 ft	180-64526-2	Excavated	4.23	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	1.9	1.7	0.63	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B720	SSHS-B720-SUB-2-4	4/12/2017	855.48	2 - 4 ft	180-65174-1	Not Excavated	0.112	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.056	0.04	0.016 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B720	SSHS-B720-SUB-4-6	4/12/2017	855.48	4 - 6 ft	180-65174-1	Not Excavated	0.135	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.077	0.045	0.013 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B722	SSHS-B722-SUB-2-4	4/12/2017	855.14	2 - 4 ft	180-65174-1	Not Excavated	0.046	< 0.0093 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.028	0.018	< 0.012 U	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B722	SSHS-B722-SUB-4-6	4/12/2017	855.14	4 - 6 ft	180-65174-1	Not Excavated	0.083	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.055	0.028	< 0.012 U	< 0.013 U	< 0.0054 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B723	SSHS-B723-SUB-6-8	4/13/2017	856.74	6 - 8 ft	180-65226-1	Excavated	2090	< 10 U	< 9.9 U	< 7.6 U	< 15 U	1500	480	110	< 14 U	< 5.8 U
Football Field	SSHS-B724	SSHS-B724-SUB-10-12	4/12/2017	855.97	10 - 12 ft	180-65174-1	Excavated	ND	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.009 U	< 0.0083 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B724	SSHS-B724-SUB-12-14	4/12/2017	855.97	12 - 14 ft	180-65174-1	Not Excavated	0.014	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.014 J	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B730	SSHS-B730-SUB-14-16	4/12/2017	855.90	14 - 16 ft	180-65174-1	Excavated	ND	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	< 0.0083 U	< 0.0076 U	< 0.012 U	< 0.012 U	< 0.0053 U
Football Field	SSHS-B739	SSHS-B739-SUB-2-4	4/12/2017	855.57	2 - 4 ft	180-65174-1	Excavated	117.4	< 0.5 U	< 0.49 U	< 0.37 U	< 0.75 U	77	36	4.4	< 0.67 U	< 0.29 U
Football Field	SSHS-B739	SSHS-B739-SUB-4-6	4/12/2017	855.57	4 - 6 ft	180-65174-2	Excavated	3.95	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	2.7	1.1	0.15	< 0.014 U	< 0.0059 U
Football Field	SSHS-B739	PS-FD-3	4/12/2017	855.57	6 - 8 ft	180-65174-1	Excavated	0.011	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.011 J	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B739	SSHS-B739-SUB-6-8	4/12/2017	855.57	6 - 8 ft	180-65174-1	Excavated	ND	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B740	PS-FD-4	4/13/2017	855.83	2 - 4 ft	180-65226-1	Excavated	9.89	< 0.047 U	< 0.046 U	< 0.035 U	< 0.071 U	6	3.2	0.69	< 0.064 U	< 0.027 U
Football Field	SSHS-B740	SSHS-B740-SUB-2-4	4/13/2017	855.83	2 - 4 ft	180-65226-1	Excavated	8.85	< 0.047 U	< 0.045 U	< 0.035 U	< 0.07 U	5.8	2.5	0.55	< 0.063 U	< 0.027 U
Football Field	SSHS-B741	SSHS-B741-SUB-8-10	4/12/2017	856.11	8 - 10 ft	180-65174-1	Excavated	4.55	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	3.2	1.1	0.25	< 0.013 U	< 0.0056 U
Football Field	SSHS-B742	SSHS-B742-SUB-10-12	4/12/2017	855.72	10 - 12 ft	180-65174-1	Excavated	ND	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B742	SSHS-B742-SUB-12-14	4/12/2017	855.72	12 - 14 ft	180-65174-1	Excavated	4.07	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	3.1	0.84	0.13	< 0.014 U	< 0.0059 U
Football Field	SSHS-B742A	SSHS-B742A-SUB-10-12	7/13/2017	855.72	10 - 12 ft	180-68203-1	Excavated	0.0319	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.022	0.0099 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B743	SSHS-B743-SUB-6-8	4/13/2017	855.75	6 - 8 ft	180-65226-1	Not Excavated	0.017	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.017 J	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B744	SSHS-B744-SUB-2-4	4/13/2017	856.21	2 - 4 ft	180-65226-1	Excavated	0.312	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.18	0.1	0.032	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B747	SSHS-B747-SUB-2-4	5/22/2017	856.07	2 - 4 ft	180-66618-2	Not Excavated	0.39	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0086 U	0.39	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B748	SSHS-B748-SUB-2-4	5/22/2017	856.15	2 - 4 ft	180-66618-2	Not Excavated	0.556	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	0.25	0.26	0.046	< 0.014 U	< 0.0058 U
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	ND	< 0.0027	< 0.0035	< 0.0032	< 0.003	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0024
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	0.147	< 0.0028	< 0.0036	< 0.0032	< 0.003	0.13	< 0.0026	0.017	< 0.0041	< 0.0024
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	ND	< 0.0027	< 0.0035	< 0.0031	< 0.0029	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0023
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Tennis Courts / Main Parking Lot	SSHS-B750	SSHS-B750-SUB-2-4	5/22/2017	856.17	2 - 4 ft	180-66618-2	Not Excavated	0.36	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.0089 U	0.36	< 0.012 U	< 0.013 U	< 0.0057 U
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-2-4	5/22/2017	856.21	2 - 4 ft	180-66618-2	Excavated	0.216	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.12	0.073	0.023	< 0.014 U	< 0.0059 U
Northern Athletic Field	SSHS-B751	SSHS-B751-SUB-2-4	5/22/2017	856.21	2 - 4 ft	180-66618-2	Excavated	0.216	< 0.01	< 0.01	< 0.0076	< 0.015	0.12	0.073	0.023	< 0.014	< 0.0059
Tennis Courts / Main Parking Lot	SSHS-B752	SSHS-B752-SUB-2-4	5/22/2017	856.15	2 - 4 ft	180-66618-2	Not Excavated	0.01	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	< 0.0085 U	0.01 J	< 0.012 U	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B753	SSHS-B753-SUB-2-4	5/23/2017	856.28	2 - 4 ft	180-66622-1	Excavated	2.3	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	1.3	0.78	0.22	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B754	SSHS-B754-SUB-2-4	5/23/2017	856.12	2 - 4 ft	180-66622-1	Not Excavated	2.32	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	1.3	0.79	0.23	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B755	SSHS-B755-SUB-2-4	5/23/2017	856.01	2 - 4 ft	180-66622-1	Not Excavated	1.77	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.97	0.62	0.18	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B756	SSHS-B756-SUB-2-4	5/22/2017	856.09	2 - 4 ft	180-66618-1	Not Excavated	0.399	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.2	0.15	0.049	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B757	SSHS-B757-SUB-2-4	5/22/2017	856.25	2 - 4 ft	180-66618-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B758	SSHS-B758-SUB-2-4	5/22/2017	856.30	2 - 4 ft	180-66618-2	Not Excavated	1.06	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.46	0.47	0.13	< 0.012 U	< 0.0052 U
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	ND	< 0.0028	< 0.0036	< 0.0032	< 0.0031	< 0.0018	< 0.0027	< 0.0027	< 0.0041	< 0.0024
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0023
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	ND	< 0.0027	< 0.0034	< 0.0031	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B760	SSHS-B760-SUB-2-4	5/23/2017	856.25	2 - 4 ft	180-66622-1	Excavated	0.419	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.22	0.15	0.049	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B761	SSHS-B761-SUB-2-4	5/22/2017	856.13	2 - 4 ft	180-66618-1	Not Excavated	0.014	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.014 J	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B762	SSHS-B762-SUB-2-4	5/23/2017	856.41	2 - 4 ft	180-66622-1	Excavated	1.11	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.52	0.43	0.16	< 0.013 U	< 0.0053 U
Northern Athletic Field	SSHS-B763	SSHS-B763-SUB-2-4	5/23/2017	856.04	2 - 4 ft	180-66622-1	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B765	SSHS-B765-SUB-2-4	5/22/2017	856.08	2 - 4 ft	180-66618-2	Not Excavated	ND	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B766	SSHS-B766-SUB-2-4	5/22/2017	856.26	2 - 4 ft	180-66618-2	Not Excavated	0.39	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	< 0.0092 U	0.29	0.1	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B768	SSHS-B768-SUB-2-4	5/22/2017	855.82	2 - 4 ft	180-66618-2	Not Excavated	0.286	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.058	0.2	0.028	< 0.014 U	< 0.0059 U
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	ND	< 0.0027	< 0.0035	< 0.0031	< 0.003	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0023
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0023
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-2-4	5/22/2017	856.31	2 - 4 ft	180-66618-2	Not Excavated	0.102	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	0.09	0.012 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B772	SSHS-B772-SUB-2-4	5/22/2017	856.30	2 - 4 ft	180-66618-2	Not Excavated	0.188	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.051	0.11	0.027	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B773	SSHS-B773-SUB-2-4	5/22/2017	856.38	2 - 4 ft	180-66618-2	Not Excavated	0.114	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0087 U	0.088	0.026	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-2-4	5/23/2017	855.99	2 - 4 ft	180-66622-1	Not Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0082 U	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B778	SSHS-B778-SUB-2-4	5/22/2017	855.75	2 - 4 ft	180-66618-2	Not Excavated	0.0098	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	0.0098 J	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	ND	< 0.0026 U	< 0.0033 U	< 0.003 U	< 0.0028 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0038 U	< 0.0022 U
Northern Athletic Field	SSHS-B781	SSHS-B781-SUB-2-4	5/23/2017	856.09	2 - 4 ft	180-66622-1	Not Excavated	2.53	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	1.4	0.89	0.24	< 0.013 U	< 0.0054 U
Football Field	SSHS-B782	SSHS-B782-SUB-2-4	5/16/2017	856.06	2 - 4 ft	180-66369-1	Excavated	306.3	< 1 U	< 1 U	< 0.78 U	< 1.6 U	230	69	7.3	< 1.4 U	< 0.6 U
Football Field	SSHS-B782A	SSHS-B782A-SUB-2-4	7/12/2017	856.06	2 - 4 ft	180-68139-1	Excavated	151.9	< 0.49 U	< 0.48 U	< 0.37 U	< 0.74 U	110	38	3.9	< 0.67 U	< 0.28 U
Tennis Courts / Main Parking Lot	SSHS-B783	SSHS-B783-SUB-2-4	5/17/2017	855.31	2 - 4 ft	180-66432-1	Not Excavated	0.292	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.2 J	0.078 J	0.014 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B785	SSHS-B785-SUB-6-8	5/17/2017	855.88	6 - 8 ft	180-66432-1	Excavated	0.0443	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.035 J	0.0093 J	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B786	PS-FD-7	5/17/2017	855.98	6 - 8 ft	180-66432-1	Excavated	0.226	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.18 J	0.046 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B786	SSHS-B786-SUB-6-8	5/17/2017	855.98	6 - 8 ft	180-66432-1	Excavated	0.438	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.34 J	0.098 J	< 0.013 U	< 0.014 U	< 0.0059 U
Football Field	SSHS-B787	SSHS-B787-SUB-8-10	5/15/2017	855.70	8 - 10 ft	180-66369-1	Excavated	0.907	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.62	0.25	0.037	< 0.013 U	< 0.0054 U
Football Field	SSHS-B788	SSHS-B788-SUB-10-12	5/16/2017	855.67	10 - 12 ft	180-66369-2	Excavated	4.14	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	2.9	1.1	0.14	< 0.014 U	< 0.0058 U
Football Field	SSHS-B790	SSHS-B790-SUB-2-4	5/17/2017	855.88	2 - 4 ft	180-66432-1	Excavated	989	< 10 U	< 9.9 U	< 7.6 U	< 15 U	730 J	240 J	19 J	< 14 U	< 5.8 U
Football Field	SSHS-B791	SSHS-B791-SUB-2-4	5/16/2017	856.12	2 - 4 ft	180-66369-1	Excavated	53	< 0.099 U	< 0.096 U	< 0.074 U	< 0.15 U	41	11	1	< 0.13 U	< 0.057 U
Football Field	SSHS-B791	PS-FD-2	5/16/2017	856.12	2 - 4 ft	180-66369-1	Excavated	32.57	< 0.098 U	< 0.096 U	< 0.073 U	< 0.15 U	24	7.8	0.77	< 0.13 U	< 0.057 U
Football Field	SSHS-B791	SSHS-B791-SUB-4-6	5/16/2017	856.12	4 - 6 ft	180-66369-2	Excavated	31.05	< 0.1 U	< 0.098 U	< 0.075 U	< 0.15 U	23	7.1	0.95	< 0.14 U	< 0.057 U
Football Field	SSHS-B791	PS-FD-16	5/23/2017	856.12	6 - 8 ft	180-66622-1	Excavated	34.06	< 0.19 U	< 0.19 U	< 0.15 U	< 0.29 U	26	7.4	0.66	< 0.26 U	< 0.11 U
Football Field	SSHS-B791	SSHS-B791-SUB-6-8	5/23/2017	856.12	6 - 8 ft	180-66622-1	Excavated	31.13	< 0.19 U	< 0.18 U	< 0.14 U	< 0.28 U	24	6.6	0.53	< 0.25 U	< 0.11 U
Football Field	SSHS-B792	SSHS-B792-SUB-8-10	5/16/2017	855.95	8 - 10 ft	180-66369-1	Excavated	122.6	< 0.98 U	< 0.95 U	< 0.73 U	< 1.5 U	130	38	4.6	< 1.3 U	< 0.56 U
Football Field	SSHS-B792	SSHS-B792-SUB-10-12	5/16/2017	855.95	10 - 12 ft	180-66369-1	Excavated	0.782	< 0.011 U	< 0.01 U	< 0.008 U	< 0.016 U	0.47	0.25	0.062	< 0.014 U	< 0.0061 U
Football Field	SSHS-B792	SSHS-B792-SUB-12-14	5/16/2017	855.95	12 - 14 ft	180-66369-1	Excavated	51	< 0.57 U	< 0.56 U	< 0.42 U	< 0.85 U	63	16	2	< 0.77 U	< 0.33 U
Football Field	SSHS-B792	SSHS-B792-SUB-14-16	5/16/2017	855.95	14 - 16 ft	180-66369-2	Not Excavated	0.342	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.23	0.093	0.019	< 0.013 U	< 0.0057 U
Football Field	SSHS-B793	SSHS-B793-SUB-4-6	5/15/2017	855.93	4 - 6 ft	180-66369-1	Excavated	1308	< 5.1 U	< 5 U	< 3.8 U	< 7.6 U	990	260	58	< 6.9 U	< 2.9 U
Football Field	SSHS-B793	SSHS-B793-SUB-6-8	5/15/2017	855.93	6 - 8 ft	180-66369-1	Excavated	3730	< 5 U	< 4.8 U	< 3.7 U	< 7.4 U	2800	760	170	< 6.7 U	< 2.8 U
Football Field	SSHS-B794	SSHS-B794-SUB-2-4	5/16/2017	856.09	2 - 4 ft	180-66369-1	Excavated	5.63	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	2.8	2.3	0.53	< 0.014 U	< 0.0057 U
Football Field	SSHS-B794	SSHS-B794-SUB-4-6	5/16/2017	856.09	4 - 6 ft	180-66369-1	Excavated	27.9	< 0.095 U	< 0.093 U	< 0.071 U	< 0.14 U	17	7.9	3	< 0.13 U	< 0.054 U
Football Field	SSHS-B794	PS-FD-6	5/16/2017	856.09	6 - 8 ft	180-66369-1	Excavated	0.83	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	< 0.0095 U	0.83	< 0.013 U	< 0.014 U	< 0.006 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B794	SSHS-B794-SUB-6-8	5/16/2017	856.09	6 - 8 ft	180-66369-1	Excavated	1.19	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	< 0.0092 U	0.78	0.41	< 0.014 U	< 0.0059 U
Football Field	SSHS-B795	SSHS-B795-SUB-2-4	5/16/2017	856.02	2 - 4 ft	180-66369-1	Excavated	0.882	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.67	0.19	0.022	< 0.014 U	< 0.0059 U
Football Field	SSHS-B795	SSHS-B795-SUB-4-6	5/16/2017	856.02	4 - 6 ft	180-66369-1	Excavated	0.352	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	0.28	0.072	< 0.013 U	< 0.014 U	< 0.0059 U
Football Field	SSHS-B795	PS-FD-3	5/16/2017	856.02	6 - 8 ft	180-66369-1	Excavated	ND	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	< 0.0092 U	< 0.0085 U	< 0.013 U	< 0.014 U	< 0.0059 U
Football Field	SSHS-B795	SSHS-B795-SUB-6-8	5/16/2017	856.02	6 - 8 ft	180-66369-1	Excavated	ND	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.016 U	< 0.0093 U	< 0.0086 U	< 0.013 U	< 0.014 U	< 0.0059 U
Football Field	SSHS-B795	SSHS-B795-SUB-8-10	5/16/2017	856.02	8 - 10 ft	180-66369-1	Excavated	0.211	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.16	0.051	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B795A	SSHS-B795A-SUB-2-4	7/12/2017	856.02	2 - 4 ft	180-68139-1	Excavated	1.336	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.91	0.38	0.046	< 0.013 U	< 0.0056 U
Football Field	SSHS-B796	SSHS-B796-SUB-4-6	5/16/2017	856.33	4 - 6 ft	180-66369-1	Excavated	14.02	< 0.051 U	< 0.05 U	< 0.038 U	< 0.076 U	10	3.6	0.42	< 0.069 U	< 0.029 U
Football Field	SSHS-B796	SSHS-B796-SUB-6-8	5/16/2017	856.33	6 - 8 ft	180-66369-1	Excavated	0.199	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.11	0.073	0.016 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B797	SSHS-B797-SUB-4-6	5/16/2017	856.11	4 - 6 ft	180-66369-1	Excavated	11.45	< 0.1 U	< 0.097 U	< 0.074 U	< 0.15 U	6.5	4	0.95	< 0.13 U	< 0.057 U
Football Field	SSHS-B797	PS-FD-5	5/16/2017	856.11	6 - 8 ft	180-66369-1	Excavated	184	< 0.99 U	< 0.97 U	< 0.74 U	< 1.5 U	69	88	27	< 1.3 U	< 0.57 U
Football Field	SSHS-B797	SSHS-B797-SUB-6-8	5/16/2017	856.11	6 - 8 ft	180-66369-1	Excavated	154	< 0.99 U	< 0.97 U	< 0.74 U	< 1.5 U	52	79	23	< 1.3 U	< 0.57 U
Football Field	SSHS-B797A	SSHS-B797A-SUB-4-6	7/13/2017	856.11	4 - 6 ft	180-68203-1	Excavated	59	< 0.19 U	< 0.18 U	< 0.14 U	< 0.28 U	17	42	< 0.24 U	< 0.25 U	< 0.11 U
Football Field	SSHS-B797A	DS-PD-7	7/13/2017	856.11	6 - 8 ft	180-68203-1	Excavated	0.158	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.067	0.07	0.021	< 0.013 U	< 0.0056 U
Football Field	SSHS-B797A	SSHS-B797A-SUB-6-0	7/13/2017	856.11	6 - 8 ft	180-68203-1	Excavated	0.086	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.015 U	0.042	0.044	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B798	SSHS-B798-SUB-2-4	5/16/2017	855.61	2 - 4 ft	180-66369-1	Excavated	0.086	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.054	0.032	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B798	SSHS-B798-SUB-8-10	5/16/2017	855.61	8 - 10 ft	180-66369-1	Excavated	0.38	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.2	0.15	0.03	< 0.013 U	< 0.0057 U
Football Field	SSHS-B798	SSHS-B798-SUB-10-12	5/16/2017	855.61	10 - 12 ft	180-66369-1	Excavated	4.6	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	3.7	0.77	0.13	< 0.013 U	< 0.0056 U
Football Field	SSHS-B798A	PS-FD-6	7/12/2017	855.61	2 - 4 ft	180-68139-1	Excavated	0.238	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.17	0.068	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B798A	SSHS-B798A-SUB-2-4	7/12/2017	855.61	2 - 4 ft	180-68139-1	Excavated	0.215	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.15	0.065	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-2-4	5/17/2017	855.37	2 - 4 ft	180-66432-1	Excavated	0.112	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.079 J	0.033 J	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B799	PS-FD-8	5/17/2017	855.37	10 - 12 ft	180-66432-1	Excavated	1.679	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	1.2 J	0.42 J	0.059 J	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-10-12	5/17/2017	855.37	10 - 12 ft	180-66432-1	Excavated	2.341	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	1.7 J	0.57 J	0.071 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-12-14	5/17/2017	855.37	12 - 14 ft	180-66432-1	Not Excavated	0.196	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	0.13 J	0.066 J	< 0.013 U	< 0.014 U	< 0.0061 U
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-14-16	5/17/2017	855.37	14 - 16 ft	180-66432-2	Not Excavated	0.047	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.033	0.014 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B800	SSHS-B800-SUB-2-4	5/17/2017	855.92	2 - 4 ft	180-66432-1	Excavated	45.2	< 0.19 U	< 0.19 U	< 0.14 U	< 0.28 U	34 J	10 J	1.2 J	< 0.26 U	< 0.11 U
Football Field	SSHS-B800	SSHS-B800-SUB-4-6	5/17/2017	855.92	4 - 6 ft	180-66432-1	Excavated	695	< 4.9 U	< 4.8 U	< 3.6 U	< 7.3 U	540 J	140 J	15 J	< 6.6 U	< 2.8 U
Football Field	SSHS-B800	SSHS-B800-SUB-6-8	5/17/2017	855.92	6 - 8 ft	180-66432-1	Excavated	3409	< 10 U	< 10 U	< 7.7 U	< 15 U	2700 J	630 J	79 J	< 14 U	< 5.9 U
Football Field	SSHS-B800	SSHS-B800-SUB-8-10	5/17/2017	855.92	8 - 10 ft	180-66432-1	Excavated	1075	< 10 U	< 10 U	< 7.7 U	< 15 U	850 J	200 J	25 J	< 14 U	< 5.9 U
Football Field	SSHS-B800	SSHS-B800-SUB-10-12	5/17/2017	855.92	10 - 12 ft	180-66432-2	Excavated	91.3	< 0.51 U	< 0.5 U	< 0.38 U	< 0.76 U	71	18	2.3	< 0.69 U	< 0.29 U
Football Field	SSHS-B800	SSHS-B800-SUB-12-14	5/17/2017	855.92	12 - 14 ft	180-66432-1	Excavated	216.1	< 0.96 U	< 0.94 U	< 0.72 U	< 1.4 U	170 J	41 J	5.1 J	< 1.3 U	< 0.55 U
Football Field	SSHS-B800	SSHS-B800-SUB-14-16	5/17/2017	855.92	14 - 16 ft	180-66432-2	Not Excavated	0.206	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.16	0.046	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B801	SSHS-B801-SUB-4-6	5/17/2017	856.98	4 - 6 ft	180-66432-1	Excavated	64.4	< 0.1 U	< 0.099 U	< 0.076 U	< 0.15 U	43 J	19 J	2.4 J	< 0.14 U	< 0.058 U
Football Field	SSHS-B801	SSHS-B801-SUB-8-10	5/17/2017	856.98	8 - 10 ft	180-66432-1	Excavated	0.77	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.53 J	0.21 J	0.03 J	< 0.013 U	< 0.0054 U
Football Field	SSHS-B801	PS-FD-9	5/17/2017	856.98	10 - 12 ft	180-66432-1	Excavated	0.13	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.11 J	0.02 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B801	SSHS-B801-SUB-10-12	5/17/2017	856.98	10 - 12 ft	180-66432-1	Excavated	0.095	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.079 J	0.016 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B801	SSHS-B801-SUB-12-14	5/17/2017	856.98	12 - 14 ft	180-66432-1	Excavated	2.693	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	1.9 J	0.7 J	0.093 J	< 0.013 U	< 0.0054 U
Football Field	SSHS-B802	SSHS-B802-SUB-8-10	5/17/2017	856.55	8 - 10 ft	180-66432-1	Excavated	21.08	< 0.1 U	< 0.098 U	< 0.075 U	< 0.15 U	16 J	4.5 J	0.58 J	< 0.14 U	< 0.057 U
Football Field	SSHS-B802	SSHS-B802-SUB-12-14	5/17/2017	856.55	12 - 14 ft	180-66432-1	Excavated	17.06	< 0.093 U	< 0.091 U	< 0.07 U	< 0.14 U	13 J	3.6 J	0.46 J	< 0.13 U	< 0.054 U
Football Field	SSHS-B803	SSHS-B803-SUB-4-6	5/16/2017	855.86	4 - 6 ft	180-66369-1	Excavated	3.92	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	2.8	1	0.12	< 0.013 U	< 0.0057 U
Football Field	SSHS-B803	SSHS-B803-SUB-6-8	5/16/2017	855.86	6 - 8 ft	180-66369-1	Excavated	0.866	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.62	0.22	0.026	< 0.013 U	< 0.0057 U
Football Field	SSHS-B803	SSHS-B803-SUB-8-10	5/16/2017	855.86	8 - 10 ft	180-66369-2	Excavated	4.26	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	3.1	1	0.16	< 0.013 U	< 0.0057 U
Football Field	SSHS-B803	SSHS-B803-SUB-10-12	5/16/2017	855.86	10 - 12 ft	180-66369-2	Excavated	0.569	< 0.0098 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.39	0.15	0.029	< 0.013 U	< 0.0057 U
Football Field	SSHS-B803	SSHS-B803-SUB-12-14	5/16/2017	855.86	12 - 14 ft	180-66369-2	Excavated	0.565	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.39	0.15	0.025	< 0.013 U	< 0.0054 U
Football Field	SSHS-B803	SSHS-B803-SUB-14-16	5/16/2017	855.86	14 - 16 ft	180-66369-2	Not Excavated	0.011	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.011 J	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B803A	SSHS-B803A-SUB-8-10	7/11/2017	855.86	8 - 10 ft	180-68095-1	Excavated	ND	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B803A	SSHS-B803A-SUB-10-12	7/11/2017	855.86	10 - 12 ft	180-68095-1	Excavated	ND	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B803A	SSHS-B803A-SUB-14-16	7/12/2017	855.86	14 - 16 ft	180-68139-1	Not Excavated	0.086	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.067	0.019	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B804	SSHS-B804-SUB-4-6	5/16/2017	855.75	4 - 6 ft	180-66369-1	Excavated	0.232	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.17	0.062	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B804	SSHS-B804-SUB-8-10	5/16/2017	855.75	8 - 10 ft	180-66369-1	Excavated	0.1	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.068	0.032	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B804	SSHS-B804-SUB-10-12	5/16/2017	855.75	10 - 12 ft	180-66369-1	Excavated	544	< 4.9 U	< 4.8 U	< 3.6 U	< 7.3 U	410	120	14	< 6.6 U	< 2.8 U
Football Field	SSHS-B804	SSHS-B804-SUB-12-14	5/16/2017	855.75	12 - 14 ft	180-66369-1	Excavated	115.7	< 0.51 U	< 0.5 U	< 0.38 U	< 0.76 U	80	32	3.7	< 0.69 U	< 0.29 U
Football Field	SSHS-B804	SSHS-B804-SUB-14-16	5/16/2017	855.75	14 - 16 ft	180-66369-2	Not Excavated	3.34	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	2.3	0.93	0.11	< 0.013 U	< 0.0056 U
Football Field	SSHS-B804A	SSHS-B804A-SUB-4-6	7/11/2017	855.75	4 - 6 ft	180-68095-1	Excavated	0.129	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	0.08	0.049	< 0.013 U	< 0.014 U	< 0.0059 U
Football Field	SSHS-B804A	SSHS-B804A-SUB-14-16	7/12/2017	855.75	14 - 16 ft	180-68139-1	Not Excavated	0.211	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.15	0.061	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B805	SSHS-B805-SUB-4-6	5/17/2017	856.95	4 - 6 ft	180-66432-1	Excavated	0.983	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.016 U	0.72 J	0.24 J	0.023 J	< 0.014 U	< 0.006 U
Football Field	SSHS-B805	PS-FD-4	5/16/2017	856.95	8 - 10 ft	180-66369-1	Excavated	0.224	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.12	0.085	0.019	< 0.013 U	< 0.0056 U
Football Field	SSHS-B805	SSHS-B805-SUB-10-12	5/17/2017	856.95	10 - 12 ft	180-66432-1	Excavated	27.26	< 0.096 U	< 0.094 U	< 0.072 U	< 0.14 U	20 J	6.4 J	0.86 J	< 0.13 U	< 0.055 U
Football Field	SSHS-B805A	SSHS-B805A-SUB-4-6	7/12/2017	856.95	4 - 6 ft	180-68139-1	Excavated	2.81	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	2	0.71	0.1	< 0.013 U	< 0.0057 U
Football Field	SSHS-B805A	SSHS-B805A-SUB-10-12	7/12/2017	856.95	10 - 12 ft	180-68139-1	Excavated	4.62	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.016 U	2.8	1.6	0.22	< 0.014 U	< 0.0059 U
Football Field	SSHS-B807	SSHS-B807-SUB-4-6	5/15/2017	855.87	4 - 6 ft	180-66369-2	Excavated	2.565	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.016 U	2	0.49	0.075	< 0.014 U	< 0.0059 U
Football Field	SSHS-B807	SSHS-B807-SUB-6-8	5/15/2017	855.87	6 - 8 ft	180-66369-2	Excavated	ND	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	< 0.0089 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B807	PS-FD-1	5/15/2017	855.87	8 - 10 ft	180-66369-1	Excavated	2.55	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	1.6	0.79	0.16	< 0.013 U	< 0.0054 U
Football Field	SSHS-B807	SSHS-B807-SUB-8-10	5/15/2017	855.87	8 - 10 ft	180-66369-1	Excavated	1.91	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	1.2	0.6	0.11	< 0.013 U	< 0.0054 U
Football Field	SSHS-B808	SSHS-B808-SUB-4-6	5/16/2017	856.14	4 - 6 ft	180-66369-2	Excavated	26.1	< 0.1 U	< 0.1 U	< 0.077 U	< 0.15 U	15	10	1.1	< 0.14 U	< 0.059 U
Football Field	SSHS-B809	SSHS-B809-SUB-2-4	5/15/2017	855.49	2 - 4 ft	180-66369-2	Excavated	1.472	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	1	0.39	0.082	< 0.014 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Football Field	SSHS-B811	SSHS-B811-SUB-12-14	5/16/2017	855.61	12 - 14 ft	180-66369-1	Excavated	124.2	< 0.51 U	< 0.5 U	< 0.38 U	< 0.77 U	89	31	4.2	< 0.69 U	< 0.29 U
Football Field	SSHS-B812	SSHS-B812-SUB-8-10	5/15/2017	855.82	8 - 10 ft	180-66369-1	Excavated	0.721	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.55	0.15	0.021	< 0.013 U	< 0.0054 U
Football Field	SSHS-B812	SSHS-B812-SUB-12-14	5/15/2017	855.82	12 - 14 ft	180-66369-1	Excavated	12.84	< 0.095 U	< 0.093 U	< 0.071 U	< 0.14 U	9.6	2.6	0.64	< 0.13 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Football Field	SSHS-B820	PS-FD-17	5/23/2017	856.20	4 - 6 ft	180-66622-1	Excavated	0.759	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.43	0.28	0.049	< 0.014 U	< 0.0058 U
Football Field	SSHS-B820	SSHS-B820-SUB-4-6	5/23/2017	856.20	4 - 6 ft	180-66622-1	Excavated	0.774	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.49	0.25	0.034	< 0.014 U	< 0.0058 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B820	SSHS-B820-SUB-6-8	5/23/2017	856.20	6 - 8 ft	180-66622-1	Excavated	ND	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	< 0.0093 U	< 0.0085 U	< 0.013 U	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	2 - 4 ft	180-66622-2	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	4 - 6 ft	180-66622-2	Not Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	6 - 8 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	8 - 10 ft	180-66622-2	Not Excavated	ND	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	< 0.0082 U	< 0.0075 U	< 0.011 U	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	10 - 12 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	12 - 14 ft	180-66622-2	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated	ND	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated	ND	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Rear Parking Lot	SSHS-B828	PS-FD-16	1/14/2018	851.95	2 - 4 ft	180-74210-1	Excavated	1.368	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.97 J	0.31 J	0.088 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B828	SSHS-B828-SUB-2-4	1/14/2018	851.95	2 - 4 ft	180-74210-1	Excavated	0.983	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.68 J	0.23 J	0.073 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-2-4	1/10/2018	852.37	2 - 4 ft	180-74125-2	Not Excavated	1.78	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.47	0.11	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-4-6	1/10/2018	852.37	4 - 6 ft	180-74125-2	Not Excavated	0.103	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.068	0.035	< 0.0051 U	< 0.013 U	< 0.0087 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0029 U	< 0.0038 U	< 0.0034 U	< 0.0032 U	< 0.0019 U	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-2-4	1/11/2018	854.01	2 - 4 ft	180-74124-1	Excavated	172	< 0.59 U	< 1.2 U	< 1.1 U	< 1.1 U	130 J	34 J	8 J	< 1.3 U	< 0.88 U
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-4-6	1/23/2018	854.01	4 - 6 ft	180-74397-3	Excavated	33.16	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	26	6.3	0.86	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-6-8	1/23/2018	854.01	6 - 8 ft	180-74397-2	Excavated	28.1	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	20	6.8	1.3	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-2-4	1/10/2018	852.87	2 - 4 ft	180-74125-1	Excavated	12.88	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	8.7 J	3.4 J	0.78 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-4-6	1/10/2018	852.79	4 - 6 ft	180-74125-2	Not Excavated	1.63	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.69	0.68	0.26	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B832	PS-FD-7	1/10/2018	854.16	2 - 4 ft	180-74125-1	Excavated	97.4	< 0.29 U	< 0.57 U	< 0.52 U	< 0.53 U	74 J	19 J	4.4 J	< 0.62 U	< 0.43 U
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-2-4	1/10/2018	854.16	2 - 4 ft	180-74125-1	Excavated	112.4	< 0.3 U	< 0.59 U	< 0.54 U	< 0.55 U	84 J	23 J	5.4 J	< 0.64 U	< 0.44 U
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-4-6	1/10/2018	854.16	4 - 6 ft	180-74125-2	Excavated	1.025	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.59	0.34	0.095	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B832	SSHS-B832-SUB-6-8	1/10/2018	854.16	6 - 8 ft	180-74125-2	Excavated	1.83	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.59	0.14	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-2-4	1/12/2018	853.08	2 - 4 ft	180-74207-1	Excavated	27.7	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	19 J	7.3 J	1.4 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B834	PS-FD-13	1/12/2018	853.08	4 - 6 ft	180-74207-1	Excavated	9.33	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	6.2 J	2.6 J	0.53 J	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-4-6	1/12/2018	853.08	4 - 6 ft	180-74207-1	Excavated	3.12	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	0.75 J	0.17 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B834	SSHS-B834-SUB-6-8	1/12/2018	853.08	6 - 8 ft	180-74207-1	Excavated	3.92	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	2.8 J	0.94 J	0.18 J	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-4-6	1/9/2018	852.50	4 - 6 ft	180-74014-1	Not Excavated	4.22	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3 J	1 J	0.22 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-6-8	1/9/2018	852.50	6 - 8 ft	180-74014-2	Not Excavated	6.06	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.1	1.7	0.26	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-2-4	1/12/2018	852.96	2 - 4 ft	180-74164-1	Excavated	17.9	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	12 J	4.9 J	1 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-4-6	1/12/2018	852.96	4 - 6 ft	180-74207-1	Excavated	12.84	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	8.3 J	3.7 J	0.84 J	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-6-8	1/12/2018	852.96	6 - 8 ft	180-74207-2	Excavated	14.5	< 0.063 U	< 0.12 U	< 0.11 U	< 0.12 U	10	4.5		< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B837	PS-FD-32	1/20/2018	852.83	2 - 4 ft	180-74390-1	Excavated	31.5	< 0.058 U	< 0.11 U	< 0.1 U	< 0.11 U	22 J	8.5 J	1 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-2-4	1/20/2018	852.83	2 - 4 ft	180-74390-1	Excavated	32.89	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	22 J	9.9 J	0.99 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-4-6	1/20/2018	852.37	4 - 6 ft	180-74390-1	Not Excavated	2.67	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	1.6 J	0.96 J	0.11 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-2-4	1/9/2018	851.95	2 - 4 ft	180-74014-1	Excavated	40	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	28 J	9.8 J	2.2 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-4-6	1/9/2018	851.95	4 - 6 ft	180-74014-1	Excavated	87.8	< 0.29 U	< 0.59 U	< 0.54 U	< 0.54 U	64 J	20 J	3.8 J	< 0.63 U	< 0.44 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-6-8	1/9/2018	851.95	6 - 8 ft	180-74014-1	Excavated	5.47	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3.7 J	1.4 J	0.37 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-10-12	1/9/2018	852.00	10 - 12 ft	180-74014-1	Not Excavated	6.16	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.6 J	1.3 J	0.26 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-12-14	1/9/2018	852.00	12 - 14 ft	180-74014-2	Not Excavated	0.546	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.38	0.14	0.026	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B839	PS-FD-25	1/18/2018	850.25	6 - 8 ft	180-74307-1	Excavated	0.242	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.19 J	0.052 J	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-6-8	1/18/2018	850.25	6 - 8 ft	180-74307-1	Excavated	0.535	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.39 J	0.12 J	0.025 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-8-10	1/18/2018	850.25	8 - 10 ft	180-74307-1	Not Excavated	0.083	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.063 J	0.02 J	< 0.0055 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-10-12	1/18/2018	850.25	10 - 12 ft	180-74307-1	Not Excavated	52	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	41 J	9.2 J	1.8 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-12-14	1/18/2018	850.25	12 - 14 ft	180-74307-3	Not Excavated	2.92	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	2.2	0.58	0.14	< 0.014 U	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0038 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0034 U	< 0.0031 U	< 0.0029 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.0039 U	< 0.0023 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-2-4	1/20/2018	850.15	2 - 4 ft	180-74390-1	Excavated	368	< 0.31 U	< 0.62 U	< 0.57 U	< 0.57 U	270 J	88 J	10 J	< 0.67 U	< 0.46 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-4-6	1/20/2018	850.15	4 - 6 ft	180-74390-1	Excavated	25	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	18 J	6.1 J	0.9 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-6-8	1/20/2018	850.15	6 - 8 ft	180-74390-1	Excavated	1.296	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.93 J	0.32 J	0.046 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-8-10	1/20/2018	850.15	8 - 10 ft	180-74390-1	Excavated	0.521	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38 J	0.13 J	0.011 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-10-12	1/20/2018	850.15	10 - 12 ft	180-74390-1	Excavated	4.13	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	3 J	0.99 J	0.14 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-12-14	1/20/2018	849.70	12 - 14 ft	180-74390-3	Not Excavated	2.523	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.9	0.55	0.073	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-2-4	1/20/2018	850.17	2 - 4 ft	180-74390-1	Excavated	72.2	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	51 J	19 J	2.2 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-4-6	1/20/2018	850.17	4 - 6 ft	180-74390-1	Excavated	68.8	< 0.12 U	< 0.25 U	< 0.22 U	< 0.23 U	47 J	19 J	2.8 J	< 0.27 U	< 0.18 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-6-8	1/20/2018	850.17	6 - 8 ft	180-74390-2	Excavated	0.177	< 0.0068 UJ	< 0.013 UJ	< 0.012 UJ	< 0.012 UJ	0.13 J	0.047 J	< 0.0059 UJ	< 0.015 UJ	< 0.01 UJ
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-8-10	1/20/2018	850.17	8 - 10 ft	180-74390-1	Excavated	2.147	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.57 J	0.077 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-10-12	1/20/2018	850.05	10 - 12 ft	180-74390-1	Not Excavated	0.069	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.048 J	0.021 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-12-14	1/20/2018	850.05	12 - 14 ft	180-74390-3	Not Excavated	1.727	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2	0.47	0.057	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-2-4	1/22/2018	851.80	2 - 4 ft	180-74331-1	Excavated	66	< 0.13 U	< 0.25 U	< 0.23 U	< 0.23 U	48 J	16 J	2 J	< 0.27 U	< 0.19 U
Rear Parking Lot	SSHS-B842	PS-FD-34	1/22/2018	851.80	4 - 6 ft	180-74331-1	Excavated	5.13	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6 J	1.2 J	0.33 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-4-6	1/22/2018	851.80	4 - 6 ft	180-74331-1	Excavated	7.79	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	5.4 J	2.1 J	0.29 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-6-8	1/22/2018	851.80	6 - 8 ft	180-74331-1	Not Excavated	33.2	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	7.5 J	1.7 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-8-10	1/22/2018	851.80	8 - 10 ft	180-74331-1	Not Excavated	5.91	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	4.3 J	1.3 J	0.31 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-10-12	1/22/2018	851.80	10 - 12 ft	180-74331-1	Not Excavated	9.37	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	6.8 J	2.1 J	0.47 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-2-4	1/19/2018	851.03	2 - 4 ft	180-74310-1	Excavated	25.32	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	19 J	5.6 J	0.72 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-4-6	1/19/2018	851.03	4 - 6 ft	180-74310-1	Excavated	205	< 0.62 U	< 1.2 U	< 1.1 U	< 1.1 U	150 J	49 J	6 J	< 1.3 U	< 0.93 U
Rear Parking Lot	SSHS-B843	PS-FD-29	1/19/2018	851.40	6 - 8 ft	180-74310-1	Not Excavated	20.34	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	15 J	4.7 J	0.64 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-6-8	1/19/2018	851.40	6 - 8 ft	180-74310-1	Not Excavated	26.9	< 0.063 U	< 0.12 U	< 0.11 U	< 0.12 U	20 J	6.1 J	0.8 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-8-10	1/19/2018	851.40	8 - 10 ft	180-74310-3	Not Excavated	11.37	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	8.3	2.7	0.37	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-10-12	1/19/2018	851.40	10 - 12 ft	180-74310-1	Not Excavated	7.95	< 0.063 U	< 0.13 U	< 0.12 U	< 0.12 U	5.8 J	1.9 J	0.25 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-2-4	1/19/2018	850.69	2 - 4 ft	180-74310-2	Excavated	28.94	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	22 J	6.2 J	0.74 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-4-6	1/19/2018	850.69	4 - 6 ft	180-74310-1	Excavated	14.43	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	11 J	3.1 J	0.33 J	< 0.13 U	< 0.089 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-6-8	1/19/2018	850.69	6 - 8 ft	180-74310-1	Excavated	17.73	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	13 J	4.2 J	0.53 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-4-6	1/24/2018	851.33	4 - 6 ft	180-74436-2	Excavated	0.611	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.39 J	0.18 J	0.041 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-6-8	1/24/2018	851.33	6 - 8 ft	180-74436-1	Excavated	0.306	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.21 J	0.079 J	0.017 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-10-12	1/18/2018	851.50	10 - 12 ft	180-74307-1	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-2-4	1/11/2018	851.20	2 - 4 ft	180-74124-1	Excavated	0.1611	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11 J	0.043 J	0.0081 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-4-6	1/23/2018	851.20	4 - 6 ft	180-74397-1	Excavated	1.37	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.86 J	0.41 J	0.1 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-6-8	1/11/2018	851.20	6 - 8 ft	180-74124-2	Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-2-4	1/20/2018	852.12	2 - 4 ft	180-74390-3	Excavated	71.5	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	52	18	1.5	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-4-6	1/20/2018	852.12	4 - 6 ft	180-74390-2	Excavated	95.5	< 0.3 U	< 0.6 U	< 0.55 U	< 0.55 U	68 J	26 J	1.5 J	< 0.65 U	< 0.45 U
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-6-8	1/20/2018	851.78	6 - 8 ft	180-74390-1	Not Excavated	25.56	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	19 J	5.9 J	0.66 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-B848	PS-FD-33	1/20/2018	851.52	2 - 4 ft	180-74390-1	Excavated	10.56	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	7 J	3.2 J	0.36 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-2-4	1/20/2018	851.52	2 - 4 ft	180-74390-1	Excavated	11.13	< 0.3 U	< 0.61 U	< 0.55 U	< 0.56 U	7.6 J	2.9 J	0.63 J	< 0.66 U	< 0.45 U
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-6-8	1/20/2018	851.19	6 - 8 ft	180-74390-1	Not Excavated	3	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	1.9 J	0.97 J	0.13 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-8-10	1/20/2018	851.19	8 - 10 ft	180-74390-1	Not Excavated	1.647	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	1 J	0.56 J	0.087 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-6-8	1/22/2018	850.73	6 - 8 ft	180-74331-1	Excavated	7.02	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	5.2 J	1.6 J	0.22 J	< 0.14 U	< 0.097 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0031 U	< 0.004 U	< 0.0036 U	< 0.0034 U	< 0.002 U	< 0.003 U	< 0.003 U	< 0.0046 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Rear Parking Lot	SSHS-B850	PS-FD-23	1/18/2018	850.33	2 - 4 ft	180-74307-1	Excavated	134.9	< 0.31 U	< 0.62 U	< 0.57 U	< 0.58 U	100 J	31 J	3.9 J	< 0.68 U	< 0.47 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-2-4	1/18/2018	850.33	2 - 4 ft	180-74307-1	Excavated	242.9	< 0.3 U	< 0.59 U	< 0.54 U	< 0.54 U	190 J	48 J	4.9 J	< 0.64 U	< 0.44 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-4-6	1/18/2018	850.33	4 - 6 ft	180-74307-1	Excavated	46.2	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	34 J	11 J	1.2 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-6-8	1/18/2018	850.33	6 - 8 ft	180-74307-1	Not Excavated	49.3	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	37 J	11 J	1.3 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-8-10	1/23/2018	850.33	8 - 10 ft	180-74397-3	Not Excavated	0.309	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.22	0.072	0.017 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-10-12	1/23/2018	850.33	10 - 12 ft	180-74397-1	Not Excavated	7.91	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	5.5 J	2 J	0.41 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-2-4	1/18/2018	851.45	2 - 4 ft	180-74307-3	Excavated	15.42	< 0.03 U	< 0.06 U	< 0.055 U	< 0.055 U	11	3.6	0.82	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-4-6	1/18/2018	851.45	4 - 6 ft	180-74307-2	Excavated	3.34	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	2.3 J	0.88 J	0.16 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-6-8	1/18/2018	851.45	6 - 8 ft	180-74307-1	Excavated	0.969	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.63 J	0.3 J	0.039 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-10-12	1/18/2018	851.29	10 - 12 ft	180-74307-1	Not Excavated	0.638	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.44 J	0.16 J	0.038 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-4-6	1/19/2018	851.29	4 - 6 ft	180-74310-1	Excavated	5.62	< 0.063 U	< 0.12 U	< 0.11 U	< 0.12 U	3.9 J	1.5 J	0.22 J	< 0.14 U	< 0.093 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-6-8	1/19/2018	851.29	6 - 8 ft	180-74310-1	Excavated	5.97	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	4.1 J	1.6 J	0.27 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-8-10	1/19/2018	851.29	8 - 10 ft	180-74310-1	Excavated	1.531	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	1.1 J	0.39 J	0.041 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-10-12	1/19/2018	851.20	10 - 12 ft	180-74310-1	Not Excavated	2.075	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.52 J	0.055 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-2-4	1/8/2018	852.22	2 - 4 ft	180-74016-1	Excavated	0.099	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.074 J	0.025 J	< 0.0051 U	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-4-6	1/8/2018	852.22	4 - 6 ft	180-74016-2	Not Excavated	0.026	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.026	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-2-4	1/9/2018	851.70	2 - 4 ft	180-74014-1	Not Excavated	8.12	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	5.4 J	2.2 J	0.52 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-4-6	1/9/2018	851.70	4 - 6 ft	180-74014-2	Not Excavated	0.741	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.44	0.25	0.051	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-2-4	1/10/2018	851.59	2 - 4 ft	180-74125-1	Excavated	61.9	< 0.31 U	< 0.62 U	< 0.57 U	< 0.57 U	47 J	12 J	2.9 J	< 0.67 U	< 0.47 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-6-8	1/10/2018	851.59	6 - 8 ft	180-74125-1	Excavated	11.31	< 0.032 U	< 0.064 U	< 0.059 U	< 0.06 U	8.1 J	2.4 J	0.81 J	< 0.07 U	< 0.048 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-8-10	1/10/2018	851.59	8 - 10 ft	180-74125-2	Excavated	2.28	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.5	0.62	0.16	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-10-12	1/10/2018	851.40	10 - 12 ft	180-74125-1	Not Excavated	1.495	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.1 J	0.3 J	0.095 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-12-14	1/10/2018	851.40	12 - 14 ft	180-74125-2	Not Excavated	0.1865	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13	0.049	0.0075 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-6-8	1/17/2018	850.70	6 - 8 ft	180-74241-1	Excavated	15.4	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	11 J	3.9 J	0.5 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-8-10	1/17/2018	850.70	8 - 10 ft	180-74241-1	Excavated	2.42	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	1.8 J	0.52 J	0.1 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-10-12	1/17/2018	850.56	10 - 12 ft	180-74241-1	Not Excavated	16.17	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	12 J	3.8 J	0.37 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-12-14	1/17/2018	850.56	12 - 14 ft	180-74241-1	Not Excavated	6.99	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4.8 J	1.9 J	0.29 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-2-4	1/20/2018	850.15	2 - 4 ft	180-74390-1	Excavated	143.5	< 0.6 U	< 1.2 U	< 1.1 U	< 1.1 U	100 J	39 J	4.5 J	< 1.3 U	< 0.89 U
Rear Parking Lot	SSHS-B857	SSHS-B857-SUB-4-6	1/20/2018	850.15	4 - 6 ft	180-74390-1	Excavated	2.47	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	1.6 J	0.75 J	0.12 J	< 0.13 U	< 0.092 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.003 U	< 0.0038 U	< 0.0034 U	< 0.0033 U	< 0.0019 U	< 0.0028 U	< 0.0028 U	< 0.0044 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0026 U	< 0.0026 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-2-4	1/9/2018	852.32	2 - 4 ft	180-74014-1	Not Excavated	13.99	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	10 J	3.3 J	0.69 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B864	PS-FD-2	1/9/2018	852.32	2 - 4 ft	180-74014-1	Not Excavated	7.11	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4.8 J	1.9 J	0.41 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-4-6	1/9/2018	852.32	4 - 6 ft	180-74014-1	Not Excavated	1.28	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.69 J	0.44 J	0.15 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-6-8	1/9/2018	852.32	6 - 8 ft	180-74014-2	Not Excavated	0.351	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.16	0.14	0.051	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B869	SSHS-B869-SUB-2-4	1/8/2018	852.60	2 - 4 ft	180-74016-1	Not Excavated	0.345	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.23 J	0.097 J	0.018 J	< 0.013 U	< 0.0087 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-2-4	1/11/2018	853.20	2 - 4 ft	180-74124-1	Not Excavated	1.7	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.97 J	0.54 J	0.19 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-4-6	1/11/2018	853.20	4 - 6 ft	180-74124-1	Not Excavated	4.23	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8 J	1.2 J	0.23 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-2-4	1/20/2018	853.66	2 - 4 ft	180-74390-1	Excavated	170	< 0.24 U	< 0.48 U	< 0.44 U	< 0.44 U	120 J	45 J	5 J	< 0.52 U	< 0.36 U
Rear Parking Lot	SSHS-B874	SSHS-B874-SUB-4-6	1/20/2018	853.66	4 - 6 ft	180-74390-1	Excavated	98.2	< 0.3 U	< 0.6 U	< 0.55 U	< 0.56 U	66 J	29 J	3.2 J	< 0.65 U	< 0.45 U
Rear Parking Lot	SSHS-B875	SSHS-B875-SUB-2-4	1/20/2018	852.93	2 - 4 ft	180-74390-2	Excavated	83.2	< 0.3 U	< 0.59 U	< 0.54 U	< 0.55 U	57	24	2.2	< 0.64 U	< 0.44 U
Rear Parking Lot	SSHS-B875	SSHS-B875-SUB-4-6	1/23/2018	852.93	4 - 6 ft	180-74397-1	Excavated	1.73	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	0.96 J	0.58 J	0.19 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-2-4	1/18/2018	851.27	2 - 4 ft	180-74307-1	Excavated	115.3	< 0.13 U	< 0.26 U	< 0.24 U	< 0.24 U	82 J	30 J	3.3 J	< 0.28 U	< 0.2 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-4-6	1/18/2018	851.27	4 - 6 ft	180-74307-1	Excavated	32.9	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	24 J	7.9 J	1 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-6-8	1/18/2018	851.27	6 - 8 ft	180-74307-1	Excavated	9.51	< 0.063 U	< 0.12 U	< 0.11 U	< 0.12 U	7 J	2.2 J	0.31 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-10-12	1/18/2018	851.10	10 - 12 ft	180-74307-3	Not Excavated	2.07	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5	0.47	0.1	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-6-8	1/20/2018	851.78	6 - 8 ft	180-74390-1	Excavated	0.437	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.29 J	0.13 J	0.017 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-8-10	1/20/2018	851.47	8 - 10 ft	180-74390-1	Not Excavated	0.331	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.22 J	0.096 J	0.015 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-10-12	1/20/2018	851.47	10 - 12 ft	180-74390-3	Not Excavated	0.127	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.086	0.041	< 0.0057 U	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B879	PS-FD-27	1/19/2018	851.64	2 - 4 ft	180-74310-1	Excavated	261.9	< 0.24 U	< 0.48 U	< 0.44 U	< 0.44 U	190 J	65 J	6.9 J	< 0.52 U	< 0.36 U
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-2-4	1/19/2018	851.64	2 - 4 ft	180-74310-1	Excavated	70.9	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	51 J	18 J	1.9 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-6-8	1/19/2018	851.64	6 - 8 ft	180-74310-1	Excavated	8.14	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	5.6 J	2.3 J	0.24 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-10-12	1/19/2018	851.30	10 - 12 ft	180-74310-1	Not Excavated	1.911	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4 J	0.46 J	0.051 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-12-14	1/19/2018	851.30	12 - 14 ft	180-74310-3	Not Excavated	2.48	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.8	0.61	0.07	< 0.014 U	< 0.0095 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-2-4	1/22/2018	850.01	2 - 4 ft	180-74331-1	Excavated	134.5	< 0.61 U	< 1.2 U	< 1.1 U	< 1.1 U	98 J	30 J	6.5 J	< 1.3 U	< 0.91 U
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-6-8	1/22/2018	850.01	6 - 8 ft	180-74331-1	Excavated	1.48	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.99 J	0.39 J	0.1 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B880	SSHS-B880-SUB-10-12	1/22/2018	850.01	10 - 12 ft	180-74331-1	Excavated	0.242	< 0.0068 U	< 0.013 U	< 0.012 U	< 0.012 U	0.17 J	0.072 J	< 0.0059 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-2-4	1/22/2018	849.63	2 - 4 ft	180-74331-1	Excavated	313	< 0.64 U	< 1.3 U	< 1.2 U	< 1.2 U	230 J	68 J	15 J	< 1.4 U	< 0.96 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-6-8	1/22/2018	848.90	6 - 8 ft	180-74331-1	Not Excavated	2.65	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.9 J	0.6 J	0.15 J	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-8-10	1/22/2018	848.90	8 - 10 ft	180-74331-3	Not Excavated	6.14	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	4.4	1.5	0.24	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B883	PS-FD-31	1/20/2018	852.06	6 - 8 ft	180-74390-1	Excavated	9.45	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	6.6 J	2.6 J	0.25 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-6-8	1/20/2018	852.06	6 - 8 ft	180-74390-1	Excavated	9.89	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	7.1 J	2.5 J	0.29 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-8-10	1/20/2018	852.06	8 - 10 ft	180-74390-1	Excavated	95	< 0.077 U	< 0.15 U	< 0.14 U	< 0.14 U	59 J	32 J	4 J	< 0.17 U	< 0.11 U
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-10-12	1/20/2018	851.96	10 - 12 ft	180-74390-3	Not Excavated	62.5	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	41	19	2.5	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-2-4	1/11/2018	851.07	2 - 4 ft	180-74124-2	Excavated	0.156	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.12 J	0.036 J	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-6-8	1/11/2018	851.07	6 - 8 ft	180-74124-1	Not Excavated	0.1715	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13 J	0.034 J	0.0075 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B885	PS-FD-21	1/17/2018	850.48	2 - 4 ft	180-74241-1	Excavated	47.2	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	35 J	11 J	1.2 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-2-4	1/17/2018	850.48	2 - 4 ft	180-74241-1	Excavated	33.22	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	25 J	7.3 J	0.92 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-6-8	1/17/2018	850.48	6 - 8 ft	180-74241-2	Excavated	8.65	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	6.1 J	2.1 J	0.45 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-10-12	1/17/2018	850.40	10 - 12 ft	180-74241-1	Not Excavated	5.57	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.9 J	1.3 J	0.37 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-2-4	1/19/2018	850.66	2 - 4 ft	180-74310-1	Excavated	565	< 0.62 U	< 1.2 U	< 1.1 U	< 1.1 U	420 J	130 J	15 J	< 1.3 U	< 0.93 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-4-6	1/19/2018	850.66	4 - 6 ft	180-74310-1	Excavated	84.6	< 0.12 U	< 0.23 U	< 0.21 U	< 0.22 U	62 J	20 J	2.6 J	< 0.25 U	< 0.18 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-6-8	1/19/2018	850.66	6 - 8 ft	180-74310-1	Excavated	40.5	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	30 J	9.4 J	1.1 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-10-12	1/19/2018	850.37	10 - 12 ft	180-74310-3	Not Excavated	11.51	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	8.4	2.7	0.41	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-12-14	1/19/2018	850.37	12 - 14 ft	180-74310-1	Not Excavated	5.5	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	3.9 J	1.4 J	0.2 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-6-8	1/12/2018	850.62	6 - 8 ft	180-74207-1	Excavated	9.45	< 0.033 U	< 0.065 U	< 0.059 U	< 0.06 U	6 J	2.8 J	0.65 J	< 0.07 U	< 0.049 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-8-10	1/24/2018	850.62	8 - 10 ft	180-74436-2	Excavated	16.9	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	11 J	4.7 J	1.2 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-10-12	1/24/2018	850.60	10 - 12 ft	180-74436-1	Not Excavated	2.93	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2 J	0.77 J	0.16 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	49.7	< 0.065 UJ	< 0.13 UJ	< 0.12 UJ	< 0.12 UJ	35 J	12 J	2.7 J	< 0.14 UJ	< 0.097 UJ
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-8-10	1/22/2018	850.02	8 - 10 ft	180-74331-1	Excavated	3.002	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	0.71 J	0.092 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-10-12	1/22/2018	849.80	10 - 12 ft	180-74331-1	Not Excavated	15.58	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	11 J	4 J	0.58 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-12-14	1/22/2018	849.80	12 - 14 ft	180-74331-3	Not Excavated	3.15	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	2.3	0.75	0.1	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-2-4	1/12/2018	852.37	2 - 4 ft	180-74207-1	Excavated	49.7	< 0.11 U	< 0.23 U	< 0.21 U	< 0.21 U	33 J	14 J	2.7 J	< 0.25 U	< 0.17 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-6-8	1/12/2018	851.80	6 - 8 ft	180-74207-1	Not Excavated	11.9	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	7.7 J	3.5 J	0.7 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-8-10	1/12/2018	851.80	8 - 10 ft	180-74207-1	Not Excavated	3.08	< 0.0058 U	< 0.011 U	< 0.011 U	< 0.011 U	2 J	0.87 J	0.21 J	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-10-12	1/12/2018	851.80	10 - 12 ft	180-74207-1	Not Excavated	4.15	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	2.7 J	1.2 J	0.25 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-12-14	1/12/2018	851.80	12 - 14 ft	180-74207-2	Not Excavated	4.42	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.1	1	0.32	< 0.013 U	< 0.0092 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Rear Parking Lot	SSHS-B890	PS-FD-38	1/23/2018	851.90	8 - 10 ft	180-74397-1	Not Excavated	2	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	0.55 J	0.15 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-8-10	1/23/2018	851.90	8 - 10 ft	180-74397-2	Not Excavated	3.05	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.1 J	0.76 J	0.19 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-10-12	1/23/2018	851.90	10 - 12 ft	180-74397-1	Not Excavated	116.4	< 0.3 U	< 0.6 U	< 0.55 U	< 0.55 U	87 J	24 J	5.4 J	< 0.65 U	< 0.45 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-2-4	1/19/2018	851.47	2 - 4 ft	180-74310-1	Excavated	18.19	< 0.062 U	< 0.12 U	< 0.11 U	< 0.12 U	13 J	4.6 J	0.59 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-4-6	1/19/2018	851.47	4 - 6 ft	180-74310-1	Excavated	7.98	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	5.7 J	2 J	0.28 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-6-8	1/19/2018	851.47	6 - 8 ft	180-74310-1	Excavated	1.209	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.89 J	0.28 J	0.039 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-10-12	1/19/2018	851.10	10 - 12 ft	180-74310-1	Not Excavated	0.078	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U		0.078 J	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-2-4	1/17/2018	850.94	2 - 4 ft	180-74241-3	Excavated	131.2	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	94	34	3.2	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B892	PS-FD-19	1/17/2018	850.94	4 - 6 ft	180-74241-1	Excavated	11.63	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	7.7 J	3.4 J	0.53 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-4-6	1/17/2018	850.94	4 - 6 ft	180-74241-1	Excavated	18.3	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	12 J	5.2 J	1.1 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-6-8	1/17/2018	850.94	6 - 8 ft	180-74241-1	Excavated	2.39	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.73 J	0.16 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-8-10	1/17/2018	850.94	8 - 10 ft	180-74241-1	Excavated	1.479	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	1 J	0.41 J	0.069 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-10-12	1/17/2018	850.94	10 - 12 ft	180-74241-2	Excavated	0.925	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.67 J	0.21 J	0.045 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-12-14	1/17/2018	850.89	12 - 14 ft	180-74241-1	Not Excavated	1.55	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.57 J	0.98 J	< 0.0056 UJ	< 0.014 UJ	< 0.0095 UJ
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-2-4	1/19/2018	851.16	2 - 4 ft	180-74310-1	Excavated	117.2	< 0.13 U	< 0.25 U	< 0.23 U	< 0.23 U	86 J	28 J	3.2 J	< 0.27 U	< 0.19 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-4-6	1/19/2018	851.16	4 - 6 ft	180-74310-1	Excavated	14.28	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	9.9 J	3.8 J	0.58 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-6-8	1/19/2018	851.16	6 - 8 ft	180-74310-1	Excavated	0.025	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.025	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-10-12	1/19/2018	850.90	10 - 12 ft	180-74310-3	Not Excavated	15.05	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	11	3.6	0.45	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-12-14	1/19/2018	850.90	12 - 14 ft	180-74310-1	Not Excavated	4.75	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	3.2 J	1.4 J	0.15 J	< 0.14 U	< 0.095 U
Rear Parking Lot	SSHS-B894	SSHS-B894-SUB-2-4	1/9/2018	853.78	2 - 4 ft	180-74014-1	Excavated	4.97	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	3.4 J	1.3 J	0.27 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B894	SSHS-B894-SUB-4-6	1/9/2018	853.55	4 - 6 ft	180-74014-1	Not Excavated	6.83	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.6 J	1.8 J	0.43 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B895	SSHS-B895-SUB-2-4	1/9/2018	851.78	2 - 4 ft	180-74014-1	Excavated	0.649	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.45 J	0.16 J	0.039 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B895	SSHS-B895-SUB-4-6	1/9/2018	851.80	4 - 6 ft	180-74014-2	Not Excavated	0.317	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.21	0.089	0.018 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-2-4	1/10/2018	850.26	2 - 4 ft	180-74125-1	Excavated	142.8	< 0.61 U	< 1.2 U	< 1.1 U	< 1.1 U	110 J	26 J	6.8 J	< 1.3 U	< 0.9 U
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-4-6	1/10/2018	850.26	4 - 6 ft	180-74125-1	Excavated	102.3	< 0.3 U	< 0.59 U	< 0.54 U	< 0.55 U	79 J	18 J	5.3 J	< 0.64 U	< 0.44 U
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-6-8	1/10/2018	849.98	6 - 8 ft	180-74125-1	Not Excavated	34.06	< 0.12 U	< 0.23 U	< 0.21 U	< 0.21 U	27 J	6.3 J	< 0.1 U	0.76	< 0.17 U
Rear Parking Lot	SSHS-B898	PS-FD-12	1/12/2018	852.40	2 - 4 ft	180-74207-1	Excavated	23.5	< 0.074 U	< 0.15 U	< 0.14 U	< 0.14 U	15 J	7 J	1.5 J	< 0.16 U	< 0.11 U
Rear Parking Lot	SSHS-B898	SSHS-B898-SUB-2-4	1/12/2018	852.40	2 - 4 ft	180-74207-1	Excavated	21	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	13 J	6.6 J	1.4 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B898	SSHS-B898-SUB-4-6	1/12/2018	852.40	4 - 6 ft	180-74207-1	Excavated	44.2	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	34 J	8.5 J	1.7 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B898	SSHS-B898-SUB-6-8	1/12/2018	852.40	6 - 8 ft	180-74207-1	Excavated	0.62	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.21 J	0.41 J	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	0.91	< U	< U	< U	< U	0.76	< U	0.15		
Rear Parking Lot	SSHS-B904	PS-FD-4	1/9/2018	852.71	2 - 4 ft	180-74014-1	Excavated	197.2	< 0.6 U	< 1.2 U	< 1.1 U	< 1.1 U	140 J	48 J	9.2 J	< 1.3 U	< 0.89 U
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-2-4	1/9/2018	852.71	2 - 4 ft	180-74014-1	Excavated	205.7	< 0.6 U	< 1.2 U	< 1.1 U	< 1.1 U	150 J	47 J	8.7 J	< 1.3 U	< 0.89 U
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-4-6	1/9/2018	852.71	4 - 6 ft	180-74014-1	Excavated	1.3	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.75 J	0.42 J	0.13 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-6-8	1/9/2018	852.40	6 - 8 ft	180-74014-1	Not Excavated	0.43	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18 J	0.25 J	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-8-10	1/9/2018	852.40	8 - 10 ft	180-74014-2	Not Excavated	9.05	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	6.1	2.4	0.55	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-4-6	1/17/2018	850.31	4 - 6 ft	180-74241-2	Excavated	3.8	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.7 J	0.89 J	0.21 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B905	PS-FD-20	1/17/2018	850.31	6 - 8 ft	180-74241-1	Excavated	13.05	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	9.3 J	3.3 J	0.45 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-6-8	1/17/2018	850.31	6 - 8 ft	180-74241-1	Excavated	42.8	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	29 J	12 J	1.8 J	< 0.14 U	< 0.096 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-8-10	1/17/2018	850.00	8 - 10 ft	180-74241-1	Not Excavated	5.53	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6 J	1.6 J	0.33 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-2-4	1/20/2018	852.09	2 - 4 ft	180-74390-1	Excavated	101.5	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	71 J	27 J	3.5 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-4-6	1/20/2018	852.09	4 - 6 ft	180-74390-1	Excavated	33.8	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	8.7 J	1.1 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-6-8	1/24/2018	851.60	6 - 8 ft	180-74436-2	Not Excavated	38.8	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	28 J	8.8 J	2 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B909	SSHS-909-SUB-2-4	1/11/2018	849.90	2 - 4 ft	180-74124-1	Excavated	4.02	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	2.7 J	0.96 J	0.36 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-2-4	1/11/2018	849.70	2 - 4 ft	180-74124-1	Not Excavated	0.095	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.077 J	0.018 J	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6	1/11/2018	849.70	4 - 6 ft	180-74124-3	Not Excavated	0.574	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.34	0.18	0.054	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6	1/11/2018	849.70	4 - 6 ft	180741243	Not Excavated	0.574	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.34	0.18	0.054	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-2-4	1/19/2018	850.80	2 - 4 ft	180-74310-1	Not Excavated	0.5	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38 J	0.12 J	< 0.0052 U	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-6-8	1/19/2018	850.80	6 - 8 ft	180-74310-1	Not Excavated	2.699	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	1.9 J	0.7 J	0.099 J	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-8-10	1/19/2018	850.80	8 - 10 ft	180-74310-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B912	SSHS-B912-SUB-2-4	1/20/2018	851.46	2 - 4 ft	180-74390-1	Excavated	43.4	< 0.069 U	< 0.14 U	< 0.13 U	< 0.13 U	29 J	13 J	1.4 J	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-2-4	1/23/2018	851.62	2 - 4 ft	180-74397-2	Excavated	23.01	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	17 J	5.3 J	0.71 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-6-8	1/22/2018	851.54	6 - 8 ft	180-74331-1	Not Excavated	5.52	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	3.8 J	1.5 J	0.22 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B914	SSHS-B914-SUB-2-4	1/22/2018	853.75	2 - 4 ft	180-74331-1	Excavated	0.97	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U		0.8 J	0.17 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B914	SSHS-B914-SUB-4-6	1/22/2018	853.70	4 - 6 ft	180-74331-3	Not Excavated	1.49	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.83	0.54	0.12	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B915	SSHS-B915-SUB-2-4	1/12/2018	852.83	2 - 4 ft	180-74207-1	Excavated	8.95	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	5.8 J	2.6 J	0.55 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B916	SSHS-B916-SUB-2-4	1/16/2018	852.30	2 - 4 ft	180-74203-1	Excavated	85.6	< 0.29 U	< 0.58 U	< 0.53 U	< 0.54 U	58 J	24 J	3.6 J	< 0.63 U	< 0.43 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-2-4	1/18/2018	850.94	2 - 4 ft	180-74307-1	Excavated	82.5	< 0.12 U	< 0.25 U	< 0.23 U	< 0.23 U	57 J	23 J	2.5 J	< 0.27 U	< 0.19 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-6-8	1/18/2018	850.94	6 - 8 ft	180-74307-1	Excavated	11.84	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	8.6 J	2.9 J	0.34 J	< 0.14 U	< 0.098 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-12-14	1/18/2018	850.56	12 - 14 ft	180-74307-1	Not Excavated	3.84	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	2.7 J	0.98 J	0.16 J	< 0.14 U	< 0.099 U
Rear Parking Lot	SSHS-B918	SSHS-B918-SUB-6-8	1/18/2018	850.41	6 - 8 ft	180-74307-1	Excavated	0.551	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.38 J	0.14 J	0.031 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B919	SSHS-B919-SUB-6-8	1/12/2018	851.13	6 - 8 ft	180-74207-1	Excavated	29.7	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	20 J	8.1 J	1.6 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B919	SSHS-B919-SUB-10-12	1/12/2018	851.30	10 - 12 ft	180-74207-1	Not Excavated	2.25	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.62 J	0.13 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-2-4	1/16/2018	850.75	2 - 4 ft	180-74203-2	Excavated	44.5	< 0.13 U	< 0.26 U	< 0.24 U	< 0.24 U	29 J	13 J	2.5 J	< 0.28 U	< 0.19 U
Rear Parking Lot	SSHS-B920	PS-FD-17	1/16/2018	850.75	4 - 6 ft	180-74203-1	Excavated	29.3	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	18 J	9.2 J	2.1 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-4-6	1/16/2018	850.75	4 - 6 ft	180-74203-1	Excavated	18.7	< 0.063 U	< 0.13 U	< 0.12 U	< 0.12 U	11 J	6.1 J	1.6 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-6-8	1/16/2018	850.75	6 - 8 ft	180-74203-1	Excavated	12.67	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	8.2 J	3.7 J	0.77 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-8-10	1/16/2018	850.75	8 - 10 ft	180-74203-1	Excavated	3.49	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.3 J	1 J	0.19 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-10-12	1/16/2018	850.90	10 - 12 ft	180-74203-1	Not Excavated	7.13	< 0.032 U	< 0.063 U	< 0.057 U	< 0.058 U	4.6 J	2.1 J	0.43 J	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B921	PS-FD-8	1/11/2018	852.39	2 - 4 ft	180-74124-1	Excavated	1.31	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.83 J	0.36 J	0.12 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B921	SSHS-B921-SUB-2-4	1/11/2018	852.39	2 - 4 ft	180-74124-1	Excavated	1.3	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.89 J	0.31 J	0.1 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B922	SSHS-B922-SUB-2-4	1/12/2018	852.19	2 - 4 ft	180-74207-1	Excavated	2.31	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4 J	0.71 J	0.2 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B924	SSHS-B924-SUB-2-4	1/19/2018	851.60	2 - 4 ft	180-74310-1	Not Excavated	2.45	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7 J	0.65 J	0.1 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B925	PS-FD-14	1/12/2018	852.88	2 - 4 ft	180-74207-1	Excavated	1.344	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.86 J	0.4 J	0.084 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B925	SSHS-B925-SUB-2-4	1/12/2018	852.88	2 - 4 ft	180-74207-1	Excavated	1.499	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1 J	0.41 J	0.089 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B925	SSHS-B925-SUB-4-6	1/12/2018	852.80	4 - 6 ft	180-74207-2	Not Excavated	1.68	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.37	0.11	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B926	SSHS-B926-SUB-2-4	1/18/2018	852.34	2 - 4 ft	180-74307-1	Not Excavated	2.34	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2 J	0.86 J	0.28 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B929	SSHS-B929-SUB-2-4	1/8/2018	852.73	2 - 4 ft	180-74016-1	Excavated	3.27	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	0.86 J	0.21 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B930	PS-FD-18	1/16/2018	851.77	2 - 4 ft	180-74203-1	Excavated	10.47	< 0.031 U	< 0.062 U	< 0.057 U	< 0.058 U	7 J	3 J	0.47 J	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-2-4	1/16/2018	851.77	2 - 4 ft	180-74203-1	Excavated	3.68	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.4 J	1.1 J	0.18 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-6-8	1/23/2018	851.77	6 - 8 ft	180-74397-1	Excavated	0.538	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.35 J	0.15 J	0.038 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-8-10	1/23/2018	851.68	8 - 10 ft	180-74397-3	Not Excavated	0.016	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.016 J	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B931	SSHS-B931-SUB-4-6	1/10/2018	850.20	4 - 6 ft	180-74125-1	Excavated	11.27	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	7.3 J	3.2 J	0.77 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B932	PS-FD-40	1/24/2018	850.54	2 - 4 ft	180-74436-1	Excavated	1518	< 6.5 U	< 13 U	< 12 U	< 12 U	1100 J	340 J	78 J	< 14 U	< 9.7 U
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-2-4	1/24/2018	850.54	2 - 4 ft	180-74436-1	Excavated	161.6	< 0.64 U	< 1.3 U	< 1.2 U	< 1.2 U	120 J	34 J	7.6 J	< 1.4 U	< 0.96 U
Rear Parking Lot	SSHS-B932	SSHS-B932-SUB-4-6	1/10/2018	850.54	4 - 6 ft	180-74125-1	Excavated	27.9	< 0.07 U	< 0.14 U	< 0.13 U	< 0.13 U	21 J	5.3 J	1.6 J	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B933	SSHS-B933-SUB-2-4	1/19/2018	850.91	2 - 4 ft	180-74310-1	Excavated	308.1	< 0.25 U	< 0.51 U	< 0.46 U	< 0.47 U	230 J	71 J	7.1 J	< 0.55 U	< 0.38 U
Rear Parking Lot	SSHS-B936	SSHS-B936-SUB-2-4	1/9/2018	853.76	2 - 4 ft	180-74014-1	Excavated	40	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	28 J	9.8 J	2.2 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B937	SSHS-B937-SUB-4-6	1/20/2018	851.90	4 - 6 ft	180-74390-1	Not Excavated	32.95	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	8.1 J	0.85 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B938	SSHS-B938-SUB-2-4	1/9/2018	851.97	2 - 4 ft	180-74014-1	Excavated	250	< 0.61 U	< 1.2 U	< 1.1 U	< 1.1 U	180 J	59 J	11 J	< 1.3 U	< 0.9 U
Rear Parking Lot	SSHS-B938	SSHS-B938-SUB-4-6	1/23/2018	851.97	4 - 6 ft	180-74397-1	Excavated	3.77	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	2.6 J	0.92 J	0.25 J	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B939	PS-FD-9	1/11/2018	850.20	2 - 4 ft	180-74124-1	Excavated	132.6	< 0.3 U	< 0.6 U	< 0.55 U	< 0.55 U	100 J	25 J	7.6 J	< 0.65 U	< 0.45 U
Rear Parking Lot	SSHS-B939	SSHS-939-SUB-2-4	1/11/2018	850.20	2 - 4 ft	180-74124-1	Excavated	114.8	< 0.3 U	< 0.61 U	< 0.56 U	< 0.56 U	88 J	21 J	5.8 J	< 0.66 U	< 0.46 U
Rear Parking Lot	SSHS-B939	SSHS-B939-SUB-6-8	1/23/2018	850.07	6 - 8 ft	180-74397-1	Not Excavated	2.98	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	2.1 J	0.7 J	0.18 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B940	SSHS-B940-SUB-2-4	1/22/2018	849.71	2 - 4 ft	180-74331-1	Excavated	259	< 0.63 U	< 1.3 U	< 1.1 U	< 1.2 U	190 J	56 J	13 J	< 1.4 U	< 0.94 U
Rear Parking Lot	SSHS-B941	SSHS-B941-SUB-2-4	1/14/2018	850.36	2 - 4 ft	180-74210-1	Excavated	41.9	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	29 J	11 J	1.9 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B941	SSHS-B941-SUB-4-6	1/14/2018	850.36	4 - 6 ft	180-74210-1	Excavated	16.04	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	11 J	4.3 J	0.74 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B942	SSHS-B942-SUB-2-4	1/14/2018	850.79	2 - 4 ft	180-74210-1	Excavated	4.8	< 0.029 U	< 0.057 U	< 0.052 U	< 0.053 U	3.2 J	1.6 J		< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B942	SSHS-B942-SUB-8-10	1/24/2018	851.00	8 - 10 ft	180-74436-1	Not Excavated	0.042	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.042	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B943	SSHS-B943-SUB-2-4	1/10/2018	850.06	2 - 4 ft	180-74125-1	Excavated	9.72	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	7.5 J	1.8 J	0.42 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B944	SSHS-B944-SUB-4-6	1/20/2018	850.11	4 - 6 ft	180-74390-1	Excavated	49.3	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	37 J	11 J	1.3 J	< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-2-4	1/22/2018	850.00	2 - 4 ft	180-74331-1	Excavated	377	< 0.63 U	< 1.3 U	< 1.2 U	< 1.2 U	280 J	79 J	18 J	< 1.4 U	< 0.94 U
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-4-6	1/22/2018	850.00	4 - 6 ft	180-74331-1	Excavated	1.168	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.79 J	0.3 J	0.078 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B945	SSHS-B945-SUB-6-8	1/22/2018	850.00	6 - 8 ft	180-74331-1	Excavated	10.6	< 0.033 U	< 0.066 U	< 0.06 U	< 0.061 U	7.8 J	2.3 J	0.5 J	< 0.072 U	< 0.049 U
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-2-4	1/22/2018	850.00	2 - 4 ft	180-74331-1	Excavated	183	< 0.67 U	< 1.3 U	< 1.2 U	< 1.2 U	130 J	43 J	10 J	< 1.4 U	< 1 U
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-4-6	1/22/2018	850.00	4 - 6 ft	180-74331-1	Excavated	40.9	< 0.063 U	< 0.12 U	< 0.11 U	< 0.12 U	30 J	8.9 J	2 J	< 0.14 U	< 0.093 U
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-6-8	1/22/2018	849.00	6 - 8 ft	180-74331-1	Not Excavated	0.227	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.17 J	0.057 J	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B947	SSHS-B947-SUB-6-8	1/22/2018	851.09	6 - 8 ft	180-74331-1	Excavated	0.08	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.057 J	0.023 J	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B948	PS-FD-39	1/23/2018	851.70	10 - 12 ft	180-74397-1	Not Excavated	0.057	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.041 J	0.016 J	< 0.0058 U	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B948	SSHS-B948-SUB-10-12	1/23/2018	851.70	10 - 12 ft	180-74397-1	Not Excavated	0.069	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.048 J	0.021 J	< 0.0055 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B950	SSHS-B950-SUB-2-4	3/4/2018	852.44	2 - 4 ft	180-75545-1	Not Excavated	2.32	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.4 J	0.77 J	0.15 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B951	SSHS-B951-SUB-2-4	2/28/2018	852.70	2 - 4 ft	180-75478-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B952	SSHS-B952-SUB-6-8	3/4/2018	850.25	6 - 8 ft	180-75545-1	Excavated	11.8	< 0.03 U	< 0.061 U	< 0.055 U	< 0.056 U	8.2 J	3.1 J	0.5 J	< 0.066 U	< 0.045 U
Rear Parking Lot	SSHS-B952	PS-FD-11	3/4/2018	850.25	10 - 12 ft	180-75545-1	Excavated	0.207	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.12 J	0.066 J	0.021 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B952	SSHS-B952-SUB-10-12	3/4/2018	850.25	10 - 12 ft	180-75545-1	Excavated	0.261	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.18 J	0.081 J	< 0.0056 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-6-8	3/4/2018	850.01	6 - 8 ft	180-75545-1	Excavated	8.29	< 0.031 U,F1	< 0.061 U	< 0.056 U	< 0.056 U	6.1 J	1.9 J	0.29 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-8-10	3/4/2018	850.01	8 - 10 ft	180-75545-2	Excavated	6.13	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.6	1.3	0.23	< 0.013 U	< 0.009 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-12-14	3/4/2018	849.70	12 - 14 ft	180-75545-1	Not Excavated	0.59	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.42 J	0.17 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B954	SSHS-B954-SUB-6-8	3/5/2018	851.89	6 - 8 ft	180-75545-1	Not Excavated	0.91	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11 J	0.48 J	0.32 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-2-4	2/27/2018	854.22	2 - 4 ft	180-75403-1	Excavated	17.15	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	12	4.3	0.85	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-4-6	2/28/2018	853.70	4 - 6 ft	180-75405-1	Not Excavated	0.526	< 0.0058 U	< 0.011 U	< 0.01 U	< 0.011 U	0.27	0.19	0.066	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-6-8	2/27/2018	853.70	6 - 8 ft	180-75403-1	Not Excavated	2.53	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.6	0.77	0.16	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-8-10	2/27/2018	853.70	8 - 10 ft	180-75403-2	Not Excavated	1.9	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.58	0.12	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B956	SSHS-B956-SUB-6-8	2/27/2018	852.97	6 - 8 ft	180-75403-1	Excavated	20.73	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	15	4.9	0.83	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B956	SSHS-B956-SUB-8-10	2/27/2018	852.70	8 - 10 ft	180-75403-2	Not Excavated	4.4	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	3.2	1	0.2	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-6-8	2/28/2018	852.88	6 - 8 ft	180-75403-1	Excavated	1.266	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.85	0.34	0.076	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-8-10	2/28/2018	852.80	8 - 10 ft	180-75403-2	Not Excavated	9.87	< 0.029 U	< 0.057 U	< 0.052 U	< 0.053 U	6.5	2.8	0.57	< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-12-14	2/28/2018	852.80	12 - 14 ft	180-75403-2	Not Excavated	7.86	< 0.03 U	< 0.06 U	< 0.055 U	< 0.055 U	5.1	2.3	0.46	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B958	SSHS-B958-SUB-6-8	3/4/2018	851.53	6 - 8 ft	180-75545-1	Excavated	19.37	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	14 J	4.7 J	0.67 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B958	PS-FD-13	3/4/2018	851.26	10 - 12 ft	180-75545-1	Not Excavated	0.561	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.38 J	0.15 J	0.031 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B958	SSHS-B958-SUB-10-12	3/4/2018	851.26	10 - 12 ft	180-75545-1	Not Excavated	0.52	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.4 J	0.12 J	< 0.0055 U	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-2-4	2/28/2018	851.25	2 - 4 ft	180-75403-1	Excavated	37	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	24	11	2	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-4-6	2/28/2018	851.25	4 - 6 ft	180-75403-2	Excavated	4.89	< 0.034 U	< 0.067 U	< 0.062 U	< 0.062 U	3.2	1.4	0.29	< 0.073 U	< 0.05 U
Rear Parking Lot	SSHS-B959	PS-FD-3	2/28/2018	851.40	6 - 8 ft	180-75403-1	Not Excavated	0.226	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.15	0.065	0.011 J	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-6-8	2/28/2018	851.40	6 - 8 ft	180-75403-1	Not Excavated	0.1209	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.077	0.035	0.0089 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-8-10	2/28/2018	851.40	8 - 10 ft	180-75403-1	Not Excavated	1.396	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	0.87	0.44	0.086 J	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B960	SSHS-B960-SUB-2-4	2/28/2018	850.88	2 - 4 ft	180-75403-1	Excavated	22.2	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	16	5.2	1	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B960	SSHS-B960-SUB-8-10	2/28/2018	850.97	8 - 10 ft	180-75403-1	Not Excavated	4.98	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	3.6	1.1	0.28	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B961	SSHS-B961-SUB-8-10	3/5/2018	850.20	8 - 10 ft	180-75545-1	Not Excavated	5.67	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	3.5 J	1.8 J	0.37 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B962	SSHS-B962-SUB-8-10	3/5/2018	850.09	8 - 10 ft	180-75545-1	Excavated	26.4	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	16 J	8.4 J	2 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B963	PS-FD-14	3/4/2018	853.05	4 - 6 ft	180-75545-1	Excavated	2.1	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	0.67 J	0.13 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B963	SSHS-B963-SUB-4-6	3/4/2018	853.05	4 - 6 ft	180-75545-1	Excavated	0.815	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.55 J	0.22 J	0.045 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B963	SSHS-B963-SUB-6-8	3/4/2018	853.05	6 - 8 ft	180-75545-2	Excavated	5.62	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	4.1	1.3	0.22	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B967	SSHS-B967-SUB-2-4	3/4/2018	851.89	2 - 4 ft	180-75545-1	Excavated	61.6	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	46 J	14 J	1.6 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B967	PS-FD-15	3/4/2018	851.89	2 - 4 ft	180-75545-1	Excavated	38.2	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	12 J	2.2 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B968	SSHS-B968-SUB-2-4	3/1/2018	851.52	2 - 4 ft	180-75478-1	Excavated	4.97	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	3.5	1.3	0.17	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B969	PS-FD-6	3/1/2018	850.19	2 - 4 ft	180-75478-1	Excavated	23.98	< 0.029 U	< 0.059 U	< 0.054 U	< 0.054 U	17	6.1	0.88	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B969	SSHS-B969-SUB-2-4	3/1/2018	850.19	2 - 4 ft	180-75478-1	Excavated	13.69	< 0.031 U	< 0.063 U	< 0.057 U	< 0.058 U	9.3	3.8	0.59	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B969	SSHS-B969-SUB-4-6	3/1/2018	850.19	4 - 6 ft	180-75478-1	Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	< 0.014 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B970	SSHS-B970-SUB-4-6	3/1/2018	850.71	4 - 6 ft	180-75501-1	Not Excavated	0.7	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.56 J	0.14 J		< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-4-6	3/1/2018	852.19	4 - 6 ft	180-75478-1	Not Excavated	0.949	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	0.62	0.28	0.049 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-6-8	3/1/2018	852.19	6 - 8 ft	180-75478-1	Not Excavated	0.71	< 0.03 U	< 0.059 U	< 0.054 U	< 0.055 U	0.27	0.32	0.12	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-8-10	3/1/2018	852.19	8 - 10 ft	180-75478-1	Not Excavated	2.6	< 0.031 U	< 0.062 U	< 0.056 U	< 0.057 U	1.5	0.97	0.13	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-10-12	3/1/2018	852.19	10 - 12 ft	180-75478-1	Not Excavated	1.3	< 0.032 U	< 0.064 U	< 0.059 U	< 0.059 U	0.54	0.62	0.14	< 0.07 U	< 0.048 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-12-14	3/1/2018	852.19	12 - 14 ft	180-75478-1	Not Excavated	0.594	< 0.033 U	< 0.066 U	< 0.061 U	< 0.061 U	0.31	0.24	0.044 J	< 0.072 U	< 0.05 U
Rear Parking Lot	SSHS-B974	PS-FD-9	3/3/2018	852.78	4 - 6 ft	180-75545-1	Excavated	1.02	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.44 J	0.45 J	0.13 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B974	SSHS-B974-SUB-4-6	3/3/2018	852.78	4 - 6 ft	180-75545-1	Excavated	0.508	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.32 J	0.16 J	0.028 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B975	SSHS-B975-SUB-4-6	3/5/2018	852.46	4 - 6 ft	180-75545-1	Excavated	1.093	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.61 J	0.42 J	0.063 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B975	SSHS-B975-SUB-6-8	3/5/2018	852.46	6 - 8 ft	180-75545-2	Excavated	1.48	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	1.3	0.18	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B976	SSHS-B976-SUB-6-8	3/4/2018	849.14	6 - 8 ft	180-75545-1	Excavated	12.2	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	8.6 J	3.1 J	0.5 J	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B976	PS-FD-10	3/4/2018	849.14	6 - 8 ft	180-75545-1	Excavated	1.088	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.69 J	0.33 J	0.068 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-4-6	3/1/2018	851.97	4 - 6 ft	180-75478-1	Excavated	1.036	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	0.62	0.34	0.076 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-6-8	3/1/2018	851.96	6 - 8 ft	180-75478-1	Not Excavated	0.681	< 0.031 U	< 0.062 U	< 0.057 U	< 0.058 U	0.37	0.24	0.071 J	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-8-10	3/1/2018	851.96	8 - 10 ft	180-75478-1	Not Excavated	1.314	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	0.76	0.48	0.074 J	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-10-12	3/1/2018	851.96	10 - 12 ft	180-75478-1	Not Excavated	5.58	< 0.035 U	< 0.071 U	< 0.065 U	< 0.065 U	2.7	2.5	0.38	< 0.076 U	< 0.053 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-12-14	3/1/2018	851.96	12 - 14 ft	180-75478-1	Not Excavated	6.46	< 0.033 U	< 0.067 U	< 0.061 U	< 0.062 U	3.5	2.5	0.46	< 0.072 U	< 0.05 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-6-8	3/5/2018	852.09	6 - 8 ft	180-75545-1	Not Excavated	3.2	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7 J	1.3 J	0.2 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-8-10	3/5/2018	852.09	8 - 10 ft	180-75545-2	Not Excavated	3.16	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.4	0.66	0.1	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B978	PS-FD-17	3/5/2018	852.09	10 - 12 ft	180-75545-1	Not Excavated	0.585	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.37 J	0.18 J	0.035 J	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-10-12	3/5/2018	852.09	10 - 12 ft	180-75545-1	Not Excavated	0.553	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.35 J	0.17 J	0.033 J	< 0.013 U	< 0.0086 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-12-14	3/5/2018	852.09	12 - 14 ft	180-75545-2	Not Excavated	3.81	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8	0.88	0.13	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B979	PS-FD-12	3/4/2018	849.85	10 - 12 ft	180-75545-1	Not Excavated	5.64	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	3.7 J	1.6 J	0.34 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B979	SSHS-B979-SUB-10-12	3/4/2018	849.85	10 - 12 ft	180-75545-1	Not Excavated	7.34	< 0.0072 U	< 0.014 U	< 0.013 U	< 0.013 U	5.5 J	1.6 J	0.24 J	< 0.016 U	< 0.011 U
Rear Parking Lot	SSHS-B980	SSHS-B980-SUB-12-14	3/4/2018	849.90	12 - 14 ft	180-75545-1	Not Excavated	1.396	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	1.1 J	0.26 J	0.036 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-2-4	2/28/2018	852.05	2 - 4 ft	180-75403-1	Excavated	59.1	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	45	12	2.1	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-4-6	2/28/2018	852.05	4 - 6 ft	180-75403-1	Excavated	6.43	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	4.5	1.7	0.23	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-8-10	2/28/2018	851.85	8 - 10 ft	180-75403-1	Not Excavated	1.43	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.83	0.45	0.15	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-10-12	2/28/2018	851.85	10 - 12 ft	180-75403-1	Not Excavated	0.688	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.43	0.21	0.048	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-12-14	2/28/2018	851.85	12 - 14 ft	180-75403-1	Not Excavated	0.323	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.21	0.094	0.019	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B982	SSHS-B982-SUB-2-4	2/28/2018	851.56	2 - 4 ft	180-75403-1	Excavated	6.42	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.1	2	0.32	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B982	SSHS-B982-SUB-4-6	2/28/2018	851.56	4 - 6 ft	180-75403-2	Excavated	1.396	< 0.031 U	< 0.062 U	< 0.056 U	< 0.057 U	0.95	0.38	0.066 J	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B983	PS-FD-1	2/28/2018	851.11	2 - 4 ft	180-75403-1	Excavated	34.3	< 0.063 U	< 0.13 U	< 0.12 U	< 0.12 U	24	8.7	1.6	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B983	SSHS-B983-SUB-2-4	2/28/2018	851.11	2 - 4 ft	180-75403-1	Excavated	30.2	< 0.062 U	< 0.12 U	< 0.11 U	< 0.12 U	21	7.5	1.7	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B984	SSHS-B984-SUB-4-6	3/1/2018	851.89	4 - 6 ft	180-75501-1	Excavated	0.229	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18 J	0.049 J	< 0.0052 U	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B985	SSHS-B985-SUB-4-6	2/28/2018	851.36	4 - 6 ft	180-75403-1	Excavated	3.59	< 0.028 U	< 0.055 U	< 0.051 U	< 0.051 U	2.4	0.99	0.2	< 0.06 U	< 0.042 U
Rear Parking Lot	SSHS-B985	SSHS-B985-SUB-6-8	2/28/2018	851.33	6 - 8 ft	180-75403-2	Not Excavated	6.82	< 0.034 U	< 0.068 U	< 0.062 U	< 0.063 U	4.5	1.9	0.42	< 0.073 U	< 0.051 U
Rear Parking Lot	SSHS-B986	SSHS-B986-SUB-6-8	3/5/2018	852.00	6 - 8 ft	180-75545-1	Not Excavated	0.458	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.22 J	0.18 J	0.058 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B989	PS-FD-16	3/5/2018	853.10	8 - 10 ft	180-75545-1	Not Excavated	8.31	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	5.5 J	2.4 J	0.41 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B989	SSHS-B989-SUB-8-10	3/5/2018	853.10	8 - 10 ft	180-75545-1	Not Excavated	6.1	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	4.3 J	1.6 J	0.2 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B989	SSHS-B989-SUB-10-12	3/5/2018	853.10	10 - 12 ft	180-75545-2	Not Excavated	4.91	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3.5	1.2	0.21	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B992	SSHS-B992-SUB-8-10	3/4/2018	852.95	8 - 10 ft	180-75545-1	Not Excavated	59.1	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	43 J	14 J	2.1 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B992	SSHS-B992-SUB-10-12	3/4/2018	852.95	10 - 12 ft	180-75545-2	Not Excavated	2.59	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	1.9	0.58	0.11	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B993	PS-FD-4	3/1/2018	851.75	10 - 12 ft	180-75478-1	Not Excavated	0.546	< 0.03 U	< 0.061 U	< 0.056 U	< 0.056 U	0.34	0.16	0.046 J	< 0.066 U	< 0.045 U
Rear Parking Lot	SSHS-B993	SSHS-B993-SUB-10-12	3/1/2018	851.75	10 - 12 ft	180-75478-1	Not Excavated	0.37	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	0.26	0.11	< 0.027 U	< 0.067 U	< 0.047 U
Rear Parking Lot	SSHS-B993	SSHS-B993-SUB-12-14	3/1/2018	851.75	12 - 14 ft	180-75478-1	Not Excavated	0.027	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	0.027	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U

TABLE 5-6A
Subsurface Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Rear Parking Lot	SSHS-B994	SSHS-B994-SUB-4-6	3/1/2018	852.12	4 - 6 ft	180-75478-1	Not Excavated	3.82	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8	0.92	0.1	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B995	PS-FD-5	3/1/2018	849.89	4 - 6 ft	180-75478-1	Not Excavated	12.88	< 0.032 U	< 0.063 U	< 0.058 U	< 0.058 U	8.8	3.6	0.48	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B995	SSHS-B995-SUB-4-6	3/1/2018	849.89	4 - 6 ft	180-75478-1	Not Excavated	2.28	< 0.032 U	< 0.063 U	< 0.058 U	< 0.059 U	1.3	0.83	0.15	< 0.069 U	< 0.048 U
Rear Parking Lot	SSHS-B998	SSHS-B998-SUB-8-10	2/28/2018	851.30	8 - 10 ft	180-75403-2	Not Excavated	1.2	< 0.03 U	< 0.06 U	< 0.055 U	< 0.055 U	0.72	0.36	0.12	< 0.065 U	< 0.045 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	0.095	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.06	0.035	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	ND	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U		
Football Field	SSHS-FB10AA	SSHS-FB10AA-SUB-2-4	7/28/2015	855.71	2 - 4 ft	180-46310-1	Excavated	7.54	< 0.04 U	< 0.05 U	< 0.069 U	< 0.05 U	4.5 J	2.6 J	0.44 J	< 0.073 U	< 0.04 U
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	0.48	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	0.33	< 0.038 U	0.15		
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	8.8	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	8.8	< 0.038 U	0.3		
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	ND	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U		
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	ND	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U	< 0.038 U		
Football Field	SSHS-FB7-A	SSHS-FB7-A-SUB-2-3	7/21/2014	856.41	2 - 3 ft	180-35053-1	Excavated	2.1	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	1.4 J	0.7 J	< 0.0013 U	< 0.002 U	< 0.0012 U
Football Field	SSHS-FB7-B	SSHS-FB7-B-SUB-2-3	7/21/2014	856.19	2 - 3 ft	180-35053-1	Excavated	9.9	< 0.014 U	< 0.018 U	< 0.016 U	< 0.015 U	7 J	2.9 J	< 0.013 U	< 0.02 U	< 0.012 U
Football Field	SSHS-FB7-BA	SSHS-FB7-BA-SUB-4-6	7/15/2015	856.25	4 - 6 ft	180-45961-1	Excavated	7.26	< 0.0041 U	< 0.005 U	< 0.0069 U	< 0.005 U	5.1 J	2 J	0.16 J	< 0.0074 U	< 0.004 U
Football Field	SSHS-FB7-BA	SSHS-FB7-BA-SUB-6-8	7/15/2015	856.25	6 - 8 ft	180-45961-1	Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	< 0.0045 U	< 0.0042 U	< 0.0071 U	< 0.0039 U
Football Field	SSHS-FB7-C	SSHS-FB7-C-SUB-2-3	7/21/2014	856.56	2 - 3 ft	180-35053-1	Excavated	1.61	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	1.2 J	0.41 J	< 0.0013 U	< 0.0021 U	< 0.0012 U
Football Field	SSHS-FB7-D	SSHS-FB7-D-SUB-2-3	7/21/2014	856.62	2 - 3 ft	180-35053-2	Excavated	690	< 0.69 U	< 0.88 U	< 0.79 U	< 0.75 U	540 J	150 J	< 0.65 U	< 1 U	< 0.59 U
Football Field	SSHS-FB7-D	SSHS-FB7-DUP2	7/21/2014	856.62	2 - 3 ft	180-35053-1	Excavated	13.8	< 0.013 U	< 0.017 U	< 0.016 U	< 0.015 U	9.7 J	4.1 J	< 0.013 U	< 0.02 U	< 0.012 U
Football Field	SSHS-FB7-DA	SSHS-FB7-DA-SUB-4-6	7/15/2015	856.68	4 - 6 ft	180-45961-1	Excavated	23.53	< 0.02 U	< 0.024 U	< 0.034 U	< 0.025 U	17 J	6.1 J	0.43 J	< 0.036 U	< 0.02 U
Football Field	SSHS-FB7-DA	SSHS-FB7-DA-SUB-6-8	7/15/2015	856.68	6 - 8 ft	180-45961-1	Excavated	0.042	< 0.0041 U	< 0.005 U	< 0.007 U	< 0.0051 U	0.029 J	0.013 J	< 0.0044 U	< 0.0074 U	< 0.0041 U
Football Field	SSHS-FB7-E	SSHS-FB7-E-SUB-2-3	7/21/2014	856.28	2 - 3 ft	180-35053-1	Excavated	8.3	< 0.0069 U	< 0.0089 U	< 0.008 U	< 0.0076 U	5.4 J	2.9 J	< 0.0066 U	< 0.01 U	< 0.006 U
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	ND	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U	< 0.039 U		
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-2-4	8/30/2016	850.92	2 - 4 ft	180-58275-1	Excavated	0.022	< 0.0092 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.022	< 0.0074 U	< 0.0069 U	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW-FD-2	8/30/2016	850.92	2 - 4 ft	180-58275-1	Excavated	0.023	< 0.011 U	< 0.017 U	< 0.0058 U	< 0.0085 U	0.023	< 0.0085 U	< 0.0079 U	< 0.0072 U	< 0.0043 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-4-6	8/30/2016	850.92	4 - 6 ft	180-58275-1	Excavated	98	< 0.47 U	< 0.73 U	< 0.25 U	< 0.38 U	69 J	25 J	4 J	< 0.32 U	< 0.19 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-6-8	8/30/2016	850.92	6 - 8 ft	180-58275-1	Excavated	ND	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	< 0.0045 U	< 0.007 U	< 0.0065 U	< 0.0059 U	< 0.0036 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-8-10	8/30/2016	850.92	8 - 10 ft	180-58275-1	Not Excavated	ND	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0076 U	< 0.0048 U	< 0.0076 U	< 0.0071 U	< 0.0064 U	< 0.0039 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-10-12	8/30/2016	850.92	10 - 12 ft	180-58275-1	Not Excavated	12.69	< 0.048 U	< 0.075 U	< 0.026 U	< 0.038 U	8.9 J	3.3 J	0.49 J	< 0.032 U	< 0.019 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-12-14	8/30/2016	850.92	12 - 14 ft	180-58275-1	Not Excavated	0.019	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	0.019 J	< 0.0077 U	< 0.0071 U	< 0.0064 U	< 0.0039 U
Football Field	SSHS-SS12-A	SSHS-SS12-A-2-3	7/22/2014	855.86	2 - 3 ft	180-35079-1	Excavated	11.5	< 0.0067 U	< 0.0086 U	< 0.0078 U	< 0.0074 U	8.2 J	3.3 J	< 0.0064 U	< 0.0099 U	< 0.0058 U
Football Field	SSHS-SS12-B	SSHS-SS12-B-2-3	7/22/2014	856.00	2 - 3 ft	180-35079-1	Excavated	32	< 0.034 U	< 0.043 U	< 0.039 U	< 0.037 U	20 J	12 J	< 0.032 U	< 0.05 U	< 0.029 U
Football Field	SSHS-SS12-C	SSHS-SS12-C-2-3	7/22/2014	855.81	2 - 3 ft	180-35079-1	Excavated	129	< 0.067 U	< 0.086 U	< 0.077 U	< 0.073 U	100 J	29 J	< 0.064 U	< 0.098 U	< 0.058 U
Football Field	SSHS-SS12-CA	SSHS-SS12-CA-SUB-4-6	7/17/2015	855.83	4 - 6 ft	180-46045-1	Excavated	12.48	< 0.02 U	< 0.024 U	< 0.034 U	< 0.025 U	8.6 J	3.3 J	0.58 J	< 0.036 U	< 0.02 U
Football Field	SSHS-SS12-CA	PS-FD-#10	7/17/2015	855.83	6 - 8 ft	180-46045-1	Excavated	ND	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	< 0.0047 U	< 0.0045 U	< 0.0041 U	< 0.007 U	< 0.0038 U
Football Field	SSHS-SS12-CA	SSHS-SS12-CA-SUB-6-8	7/17/2015	855.83	6 - 8 ft	180-46045-1	Excavated	ND	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	< 0.0049 U	< 0.0046 U	< 0.0043 U	< 0.0072 U	< 0.0039 U

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

							Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**	**Lead**	**Magnesium**	**Manganese**
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential									16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater									16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity									100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]														
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	6900	< 0.28 U	52	96	0.23 J	< 0.068 U	2500	9.7		3.4 J	18	29000	11	1700	230
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	5200	< 0.31 U	22	58	0.16 J	< 0.076 U	1100	8.1		3.2 J	32	20000	9.6	1700	110
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	5100	< 0.29 U	2.9	23	0.14 J	< 0.071 U	1800	15		3.7 J	17	15000	4.1	2000	180
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	3300		4.8 J	660 J	0.29 J	0.075 J	17000 J	6.7 J		4.8 J	23 J	12000	19 J	4200 J	310
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	3300	< 0.22 U	3.6	210	0.15 J	< 0.053 U	14000	6.4		3.4 J	21	10000	18	2900	210
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	6300	< 0.26 U	5.1	170	0.26 J	< 0.064 U	7000	9.2		5.2	19	14000	28	2900	260
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	3300	< 0.19 U	2.6	67	0.14 J	0.060 J	31000	4.8		3.7	11	8200	7.4	4400	170
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	3900	< 0.24 U	2.7	73	0.15 J	0.076 J	20000	5.6		3.7 J	15	9800	9.3	6800	280
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	4800	< 0.20 U	4.2	56	0.21 J	0.11 J	12000	7.2		4.9	18	12000	10	4200	520
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	1500	< 0.16 U	2.2	9.1 J	0.059 J	< 0.038 U	320	2.7		1.5 J	16	4100	2.1	670	71
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01	8/12/2024	850.65	4.65 - 6.65 ft	1801782961	Not Excavated	6400	0.83 J	20	59	0.35 J	0.41 J	24000	14		10	49	37000	110	4600	460
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	2.65-4.65 ft	1801782961	Not Excavated	5800	0.62 J	46	88	0.24 J	0.30 J	14000	19		5.0	55	45000	170	3000	180
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	4.65 - 6.65 ft	1801782961	Not Excavated	8600	0.49 J	14	64	0.38 J	0.52	18000	29		7.6	130	31000	130	3500	240
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	10000	0.40 J	7.7	83	0.49 J	0.21 J	8100	16		8.9	150	25000	44	2900	170
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated	5100	< 0.36 U	6.9	49	0.30 J	0.15 J	1400	11		6.3	70	12000	12	1200	690
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	12.65-14.65 ft	1801782961	Not Excavated	7400	< 0.38 U	7.7	73	0.40 J	0.41 J	15000	19		8.8	150	21000	31	5000	2000
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	13.63-15.63 ft	1801782961	Not Excavated	6400	0.70 J	6.8	58	0.29 J	0.17 J	6100	26		7.5	31	16000	14	2600	660
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	14.03-16.03 ft	1801782961	Not Excavated	8700	< 0.39 U	5.5	85	0.36 J	0.16 J	4900	33		7.8	31	20000	11	2700	480
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	7.21-9.21 ft	1801783741	Not Excavated	7300	< 0.39 U	16	92	0.45 J	0.22 J	34000	20		5.9	44	22000	64	3100	360
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	8000	< 0.31 U	6.6	88	0.32 J	0.15 J	17000	21		6.9	48	18000	26	4500	460
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	4.76-6.76 ft	1801783741	Not Excavated	8800	< 0.41 U	8.0	91	0.39 J	0.18 J	25000	15		7.2	35	19000	33	4500	430
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	11000	< 0.31 U	13	190	0.49	0.14 J	7200	19		8.6	49	21000	14	3000	2900
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	8.76-10.76 ft	1801783741	Not Excavated	7400	< 0.27 U	9.7	67	0.19 J	0.16 J	47000	16		6.0	27	18000	15	4700	300
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	14.26-16.26 ft	1801838841	Not Excavated			9.2												
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	12.12-14.12 ft	1801838841	Not Excavated			39												
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	14.12-16.12 ft	1801838842	Not Excavated			15												
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated			8.5	54.8	< 0.6 U	< 0.6 U		6.2			58		33.1		
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-12-14	4/24/2018	852.00	12 - 14 ft	180-77059-3	Excavated															
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	6800	< 0.2 U	5.6	62	0.35 J	0.11 J	22000	10		6.6	29	14000	9	5900	420
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	3100	4.6	20	110	0.81	< 0.016 U	2300	9.3		11	74	32000	120	390 J	200
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	3500	2.7	17	140	0.92	0.069 J	2000	9.3		7.2	70	29000	120	850	180
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	2800	0.36 J	26	210	0.61	< 0.017 U	11000	11		6.5	47	26000	26	2300	87
Rear Parking Lot	SSHS-B1014	SSHS-B1014-SUB-4-6	4/25/2018	853.67	4 - 6 ft	180-77123-1	Excavated															
Rear Parking Lot	SSHS-B1251	SSHS-B1251-SUB-10-12	7/1/2018	849.70	10 - 12 ft	180-79440-3	Not Excavated	6900	< 0.43 U	30	110	0.22 J	0.23 J	960	18		3.3 J	68	51000	15	1700	120
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-10-12	7/1/2018	849.20	10 - 12 ft	180-79440-3	Not Excavated	8200	< 0.39 U	17	98	0.29 J	0.15 J	950	16		5.1 J	36	36000	11	2100	150
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-10-12	7/1/2018	849.77	10 - 12 ft	180-79440-3	Not Excavated	6500	< 0.42 U	16	59	0.23 J	0.27 J	14000	16		3.9 J	80	32000	23	2600	150
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-12-14	7/1/2018	849.77	12 - 14 ft	180-79440-3	Not Excavated	6600	< 0.42 U	28	100	0.3 J	0.28 J	23000 J	24		4.5 J	120 J-	39000 J	34	2600	180
Rear Parking Lot	SSHS-B1346	SSHS-B1346-SUB-4-6	8/3/2018	851.99	4 - 6 ft	180-80462-1	Not Excavated	8000	< 0.39 U	8.1	150	0.4 J	0.11 J	16000	15		6.8	57	19000	40	3500	510
Rear Parking Lot	SSHS-B1390	SSHS-B1390-SUB-8-10	8/4/2018	851.82	8 - 10 ft	180-80511-1	Excavated	6400	< 0.38 U	7	65	0.3 J	< 0.04 U	16000	8.6		5.8	30	15000	27	3500	350
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated			5.1	48.8	< 0.54 U	< 0.54 U		8.3			24.4		24.2		
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated			9.1	< 611 U	< 0.57 U	< 0.57 U		21.4			85.2		149		
Rear Parking Lot	SSHS-B1500	SSHS-B1500 (6-8) 20180821	8/21/2018	-	6 - 8 ft	180-81125-1	Not Excavated	4900	< 0.39 U	33	79	0.15 J	0.17 J	140 J	8		1.9 J	20	39000	7.9	1100	73
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-2-4	7/26/2018	852.76	2 - 4 ft	180-80225-2	Excavated	6900	0.67 J	7.3	61	0.36 J	< 0.04 U	12000	11		6.9	43	21000	71	2900	580
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-8-10	7/26/2018	852.76	8 - 10 ft	180-80225-2	Excavated	6300	0.4 J	4.9	52	0.26 J	0.4 J	7800	11		5.5 J	30	18000	15	2000	310
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-10-12	7/26/2018	852.76	10 - 12 ft	180-80225-2	Not Excavated	5600	< 0.37 U	4.7	51	0.22 J	1.1	5800	10		5.1 J	20	15000	12	1900	300
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	5300	< 0.38 U	5.1	29	0.21 J	0.64	3600	7.5		4.9 J	22	14000	12	3000	380
Football Field	SSHS-B2025	SSHS-B2025-SUB-10-12	7/26/2018	854.55	10 - 12 ft	180-80225-3	Not Excavated	7300	< 0.37 U	5.5	79	0.27 J	< 0.039 U	80000	14		6.5	28	15000	29	5600	790
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	6100	< 0.38 U	5.1	58	0.26 J	< 0.041 U	3800	7.8		5.6 J	27	15000	9.4	3100	690
Football Field	SSHS-B2025	PS-FD-37	7/26/2018	854.55	2 - 4 ft	180-80225-3	Not Excavated	10000	< 0.41 U	7.8	120	0.47 J	< 0.044 U	7700	15		8.9	33	22000	43	3100	550
Football Field	SSHS-B2025	SSHS-B2025-SUB-2-4	7/26/2018	854.55	2 - 4 ft	180-80225-2	Not Excavated	9600	0.6 J	8.7	190	0.42 J	< 0.042 U	12000	21		8.6	88	33000	280	3400	580
Football Field	SSHS-B2025	SSHS-B2025-SUB-4-6	7/26/2018	854.55	4 - 6 ft	180-80225-2	Not Excavated	8800	0.76 J	6.6	110	0.35 J	< 0.043 U	42000	11		6.7	28	23000	89	5100	500
Football Field	SSHS-B2025	SSHS-B2025-SUB-6-8	7/26/2018	854.55	6 - 8 ft	180-80225-2	Not Excavated	8300	0.4 J	4.7	53	0.31 J	< 0.042 U	38000	9.5		5.8	26	15000	27	3900	310
Football Field	SSHS-B2025	SSHS-B2025-SUB-8-10	7/26/2018	854.55	8 - 10 ft	180-80225-2	Not Excavated	7700	< 0.39 U	5.9	58	0.29 J	< 0.041 U	23000	11		6.7	23	16000	16	3500	680
Football Field	SSHS-B2026	SSHS-B2026-SUB-10-12	7/26/2018	855.26	10 - 12 ft	180-80227-1	Not Excavated	11000	< 0.45 U	10	120	0.52 J	< 0.048 U	3800	20		10	67	27000	59	3200	620
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	10000	2.7	9.7	140	0.43 J	< 0.04 U	19000	36		11	540	52000	300	4100	850
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated	9400	0.7 J	6.1	96	0.4 J	0.17 J	12000	14		7.5	99	23000	74	3100	470
Football Field	SSHS-B2026	PS-FD-38	7/26/2018	855.26	4 - 6 ft	180-80225-3	Not Excavated	4500	1.4	9.9	130	0.38 J	< 0.043 U	4500	22		5.8 J	120	35000	140	860	260
Football Field	SSHS-B2026	SSHS-B2026-SUB-4-6	7/26/2018	855.26	4 - 6 ft	180-80225-3	Not Excavated	6700	2.3	11	140	0.47 J	0.54 J	5800	21		5.6 J	150	38000	170	1100	970
Football Field	SSHS-B2026	SSHS-B2026-SUB-6-8	7/26/2018	855.26	6 - 8 ft	180-80225-3	Not Excavated	5100	0.49 J	3.9	67	0.24 J	0.11 J	1200	8.8		3.4 J	22	14000	47	1000	180
Football Field	SSHS-B2026	SSHS-B2026-SUB-8-10	7/26/2018	855.26	8 - 10 ft	180-80225-3	Not Excavated	6800	< 0.38 U	4.6	65	0.29 J	0.12 J	3700	9.8		5.5	160	17000	29	2000	360
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	5100	< 0.38 U	3.5	31	0.22 J	< 0.041 U	27000	7.6		4.7 J	17	11000	14	5300	420
Football Field	SSHS-B2027	SSHS-B2027-SUB-2-4	7/26/2018	855.22	2 - 4 ft	180-80227-1	Excavated	7900	1.2	6.1	80	0.36 J	< 0.041 U	5600	13		6.5	56	19000	67	2600	490
Football Field	SSHS-B2027	SSHS-B2027-SUB-4-6	7/26/2018	855.22	4 - 6 ft	180-80227-1	Excavated	9400	< 0.39 U	7.4	74	0.4 J	< 0.042 U	14000	13		7.8	39	19000	30	7200	430
Football Field	SSHS-B2027	PS-FD-39	7/26/2018	855.22	6 - 8 ft	180-80227-3	Excavated	8800	< 0.38 U	5.1	66	0.37 J	0.1 J	4100	12		7.4	59	20000	47	2700	480
Football Field	SSHS-B2027	SSHS-B2027-SUB-6-8	7/26/2018	855.22	6 - 8 ft	180-80227-1	Excavated	11000	5.2	7.5	82	0.46	< 0.041 U	9700	17		8.2	100	23000	74	3200	870
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	6400	< 0.4 U	3.4	46	0.24 J	< 0.042 U	4600	9.2		5.9	20	13000	13	2300	370
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	5300	< 0.39 U	3.5	72	0.17 J	< 0.042 U	21000	7.5		4.6 J	16	11000	7.7	3900	310
Football Field	SSHS-B2028	SSHS-B2028-SUB-2-4	7/26/2018	855.23	2 - 4 ft	180-80227-3	Excavated	5100	1.8	7.2	79	0.36 J	< 0.043 U	6800	21		7	170	35000	130	1400	580
Football Field	SSHS-B2028	SSHS-B2028-SUB-4-6	7/26/2018	855.23	4 - 6 ft	180-80227-3	Excavated	8400	2.4	12	110	0.43 J	< 0.081 U	15000	41		13	340	71000	120	2500	1200
Football Field	SSHS-B2028	SSHS-B2028-SUB-10-12	7/26/2018	855.23	10 - 12 ft	180-80227-3	Not Excavated	6100	< 0.37 U	6.9	35	0.28 J	< 0.04 U	890	9.8		5.2 J	25	15000	19	1800	400
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	5300	< 0.36 U	4.1	32	0.22 J	0.092 J	13000	8.7		4.1 J	19	12000	7.2	5000	400
Football Field	SSHS-B2028	SSHS-B2028-SUB-6-8	7/26/2018	855.23	6 - 8 ft	180-80227-3	Not Excavated	7700	0.44 J	6.5	54	0.34 J	< 0.04 U	4600	18		7.5	64	23000	44	2100	420
Football Field	SSHS-B2028	SSHS-B2028-SUB-8-10	7/26/2018	855.23	8 - 10 ft	180-80227-3	Not Excavated	7300	< 0.38 U	5.5	42	0.31 J	0.11 J	1300	16		6.3	150	20000	25	2000	460
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-10-12	7/27/2018	856.20	10 - 12 ft	180-80252-1	Not Excavated	7000	< 0.36 U	5.3	51	0.27 J	0.068 J	22000	11		6	30	16000	9.4	8000	440

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.021 U	11	690	3.2	< 0.096 U	180 J		0.59 J		12	45
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.023 U	11	660	0.98 J	< 0.11 U	100 J		< 0.29 U		9.4	45
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.019 U	11	300 J	< 0.45 U	< 0.10 U	< 49 U		< 0.27 U		7.9	64
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.016 UT	14 J	360 J	< 0.37 UJ	< 0.084 UJ	650 J		< 0.23 UJ		9.8 J	41
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.015 U	10	250 J	< 0.33 U	< 0.075 U	310 J		< 0.20 U		6.6	35
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.015 U	15	540	< 0.40 U	< 0.090 U	310 J		< 0.25 U		10	48
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.022 U	9.2	250 J	0.34 J	< 0.064 U	180 J		< 0.18 U		5.7	26
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.021 U	9.8	320 J	< 0.37 U	< 0.084 U	120 J		< 0.23 U		6.0	39
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.017 U	24	520	< 0.31 U	< 0.070 U	140 J		< 0.19 U		8.1	63
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.020 U	3.5	150 J	< 0.24 U	< 0.054 U	< 27 U		< 0.15 U		2.5 J	16
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01	8/12/2024	850.65	4.65 - 6.65 ft	1801782961	Not Excavated	0.022 J	71	560	1.3 J	< 0.082 U	190 J		< 0.40 U		11	360
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	2.65-4.65 ft	1801782961	Not Excavated	0.041 J	67	680	2.7	< 0.080 U	290 J		< 0.40 U		15	77
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	4.65 - 6.65 ft	1801782961	Not Excavated	< 0.022 U	96	580	1.2 J	< 0.078 U	220 J		< 0.39 U		13	150
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.021 U	68	960	0.62 J	< 0.088 U	220 J		< 0.43 U		15	120
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated	< 0.025 U	27	680	< 0.47 U	0.19 BJ	< 140 U		< 0.40 U		9.3	96
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	12.65-14.65 ft	1801782961	Not Excavated	< 0.023 U	76	800	< 0.99 U	0.17 BJ	190 J		0.95 J		14	170
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	13.63-15.63 ft	1801782961	Not Excavated	< 0.019 U	22	880	< 0.56 U	0.16 BJ	< 170 U		< 0.48 U		12	82
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	14.03-16.03 ft	1801782961	Not Excavated	< 0.022 U	22	980	0.76 J	0.12 BJ	< 160 U		< 0.44 U		14	79
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	7.21-9.21 ft	1801783741	Not Excavated	0.23	43	610	1.7 J	< 0.087 U	270 J		< 0.43 U		16	73
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	0.036	28	750	0.46 J	< 0.069 U	< 120 U		< 0.34 U		14	82
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	4.76-6.76 ft	1801783741	Not Excavated	0.18	26	800	0.73 J	< 0.093 U	< 160 U		0.48 J		15	110
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	0.11	35	950	< 2.0 U	0.36 BJ	240 J		< 1.7 U		16	66
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	8.76-10.76 ft	1801783741	Not Excavated	0.27	21	810	0.66 J	< 0.060 U	240 J		0.38 J		14	65
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	14.26-16.26 ft	1801838841	Not Excavated											
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	12.12-14.12 ft	1801838841	Not Excavated											
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	14.12-16.12 ft	1801838842	Not Excavated											
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	< 0.06 U	7.3		1.2	< 1.2 U						8.5
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-12-14	4/24/2018	852.00	12 - 14 ft	180-77059-3	Excavated							27 J				
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	0.013 J	17	690	0.44 J	< 0.04 U	71 J		< 0.14 U		10	76
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	0.065	20	< 7 U	1.9	< 0.044 U	220 J		< 0.16 U		20	69
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	0.13	16	< 8.2 U	1.8	< 0.052 U	180 J		< 0.19 U		18	68
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	0.1	16	< 7.7 U	2.6	< 0.049 U	180 J		< 0.18 U		17	35
Rear Parking Lot	SSHS-B1014	SSHS-B1014-SUB-4-6	4/25/2018	853.67	4 - 6 ft	180-77123-1	Excavated							29 J				
Rear Parking Lot	SSHS-B1251	SSHS-B1251-SUB-10-12	7/1/2018	849.70	10 - 12 ft	180-79440-3	Not Excavated	< 0.0085 U	12	1800	1.3	< 0.13 U	1100		< 0.26 U		16	51
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-10-12	7/1/2018	849.20	10 - 12 ft	180-79440-3	Not Excavated	< 0.0089 U	15		0.87 J	< 0.12 U	460 J		< 0.24 U		15	51
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-10-12	7/1/2018	849.77	10 - 12 ft	180-79440-3	Not Excavated	0.094 =	23		1.1 J	< 0.13 U	420 J		< 0.26 U		13	70
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-12-14	7/1/2018	849.77	12 - 14 ft	180-79440-3	Not Excavated	0.069 =	32		2.3	< 0.13 U	540 J		< 0.26 U		15	83
Rear Parking Lot	SSHS-B1346	SSHS-B1346-SUB-4-6	8/3/2018	851.99	4 - 6 ft	180-80462-1	Not Excavated	0.036 J	41	850	< 0.6 U	< 0.12 U	430 J		0.33 J		16	140
Rear Parking Lot	SSHS-B1390	SSHS-B1390-SUB-8-10	8/4/2018	851.82	8 - 10 ft	180-80511-1	Excavated	0.031 J	18	800	< 0.57 U	< 0.12 U	140 J		0.25 J		11	80
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	< 0.05 U	14.1		< 0.54 U	< 1.1 U						121
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	< 0.06 U	38		0.89	< 1.1 U						205
Rear Parking Lot	SSHS-B1500	SSHS-B1500 (6-8) 20180821	8/21/2018	-	6 - 8 ft	180-81125-1	Not Excavated	0.021 J	5.8	760	0.92 J	< 0.12 U	150 J		< 0.37 U		15	31
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-2-4	7/26/2018	852.76	2 - 4 ft	180-80225-2	Excavated	0.046	14	690	< 0.56 U	< 0.12 U	71 J		0.3 J		17	69
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-8-10	7/26/2018	852.76	8 - 10 ft	180-80225-2	Excavated	0.062	12	620	< 0.58 U	0.12 J	45 J		< 0.23 U		13	68
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-10-12	7/26/2018	852.76	10 - 12 ft	180-80225-2	Not Excavated	0.042	11	610	< 0.56 U	< 0.11 U	45 J		0.32 J		11	67
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	0.014 J	11	550 J	< 0.58 U	< 0.12 U	58 J		< 0.24 U		9.7	63
Football Field	SSHS-B2025	SSHS-B2025-SUB-10-12	7/26/2018	854.55	10 - 12 ft	180-80225-3	Not Excavated	0.089	24	760	< 0.56 U	< 0.11 U	110 J		< 0.23 U		13	66
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	0.011 J	13	730	< 0.58 U	< 0.12 U	52 J		0.55 J		11	55
Football Field	SSHS-B2025	PS-FD-37	7/26/2018	854.55	2 - 4 ft	180-80225-3	Not Excavated	0.34	23	880	< 0.62 U	< 0.13 U	95 J		0.47 J		15	96
Football Field	SSHS-B2025	SSHS-B2025-SUB-2-4	7/26/2018	854.55	2 - 4 ft	180-80225-2	Not Excavated	0.25	32	760	0.83 J	< 0.12 U	100 J		0.36 J		21	320
Football Field	SSHS-B2025	SSHS-B2025-SUB-4-6	7/26/2018	854.55	4 - 6 ft	180-80225-2	Not Excavated	0.085	30	620	< 0.61 U	< 0.12 U	110 J		< 0.25 U		13	130
Football Field	SSHS-B2025	SSHS-B2025-SUB-6-8	7/26/2018	854.55	6 - 8 ft	180-80225-2	Not Excavated	0.061	20	680	< 0.59 U	< 0.12 U	110 J		0.32 J		13	54
Football Field	SSHS-B2025	SSHS-B2025-SUB-8-10	7/26/2018	854.55	8 - 10 ft	180-80225-2	Not Excavated	0.021 J	16	730	< 0.59 U	< 0.12 U	83 J		< 0.24 U		13	54
Football Field	SSHS-B2026	SSHS-B2026-SUB-10-12	7/26/2018	855.26	10 - 12 ft	180-80227-1	Not Excavated	0.092	43	990	< 0.68 U	< 0.14 U	52 J		0.46 J		18	100
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	0.061	180	810	< 0.57 U	0.22 J	110 J		< 0.23 U		19	160
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated	0.57	24	730	< 0.58 U	< 0.12 U	90 J		< 0.24 U		16	100
Football Field	SSHS-B2026	PS-FD-38	7/26/2018	855.26	4 - 6 ft	180-80225-3	Not Excavated	2.2	56	430 J	1.3	< 0.12 U	81 J		< 0.25 U		14	120
Football Field	SSHS-B2026	SSHS-B2026-SUB-4-6	7/26/2018	855.26	4 - 6 ft	180-80225-3	Not Excavated	0.81	47	490 J	1.2	< 0.13 U	150 J		< 0.26 U		15	140
Football Field	SSHS-B2026	SSHS-B2026-SUB-6-8	7/26/2018	855.26	6 - 8 ft	180-80225-3	Not Excavated	14	15	340 J	< 0.6 U	< 0.12 U	35 J		< 0.24 U		8.9	57
Football Field	SSHS-B2026	SSHS-B2026-SUB-8-10	7/26/2018	855.26	8 - 10 ft	180-80225-3	Not Excavated	0.21	15	510 J	< 0.57 U	< 0.12 U	39 J		< 0.23 U		9.9	81
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 0.0087 U	12	640	< 0.58 U,^	< 0.12 U	74 J		< 0.24 U		8.1	52
Football Field	SSHS-B2027	SSHS-B2027-SUB-2-4	7/26/2018	855.22	2 - 4 ft	180-80227-1	Excavated	0.093	20	630	< 0.57 U	< 0.12 U	55 J		0.44 J		15	95
Football Field	SSHS-B2027	SSHS-B2027-SUB-4-6	7/26/2018	855.22	4 - 6 ft	180-80227-1	Excavated	0.044	20	790	< 0.6 U,^	< 0.12 U	160 J		< 0.24 U		15	84
Football Field	SSHS-B2027	PS-FD-39	7/26/2018	855.22	6 - 8 ft	180-80227-3	Excavated	0.088	22	580	< 0.58 U	< 0.12 U	140 J		< 0.23 U		12	74
Football Field	SSHS-B2027	SSHS-B2027-SUB-6-8	7/26/2018	855.22	6 - 8 ft	180-80227-1	Excavated	0.28	24	880	< 0.58 U,^	< 0.12 U	370 J		0.52 J		19	120
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	0.015 J	17	680	< 0.6 U,^	< 0.12 U	47 J		0.35 J		9.8	70
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	< 0.0083 U	9.8	790	< 0.59 U,^	< 0.12 U	71 J		< 0.24 U		9.8	55
Football Field	SSHS-B2028	SSHS-B2028-SUB-2-4	7/26/2018	855.23	2 - 4 ft	180-80227-3	Excavated	0.26	42	650	1 J,^	< 0.13 U	130 J		0.39 J		19	140
Football Field	SSHS-B2028	SSHS-B2028-SUB-4-6	7/26/2018	855.23	4 - 6 ft	180-80227-3	Excavated	0.19	68	880	1.1	< 0.12 U	210 J		0.73 J		43	220
Football Field	SSHS-B2028	SSHS-B2028-SUB-10-12	7/26/2018	855.23	10 - 12 ft	180-80227-3	Not Excavated	0.014 J	14	690	< 0.56 U	< 0.12 U	44 J		0.25 J		11	57
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	< 0.0078 U	11	580	< 0.54 U	< 0.11 U	65 J		< 0.22 U		10	51
Football Field	SSHS-B2028	SSHS-B2028-SUB-6-8	7/26/2018	855.23	6 - 8 ft	180-80227-3	Not Excavated	0.055	33	620	< 0.56 U	< 0.11 U	87 J		0.4 J		15	76
Football Field	SSHS-B2028	SSHS-B2028-SUB-8-10	7/26/2018	855.23	8 - 10 ft	180-80227-3	Not Excavated	0.025 J	66	690	< 0.58 U	< 0.12 U	58 J		< 0.23 U		13	81
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-10-12	7/27/2018	856.20	10 - 12 ft	180-80252-1	Not Excavated	0.013 J	16	720	< 0.54 U	< 0.11 U	65 J		< 0.22 U		12	51

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
									mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential											16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater											16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity											100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-2-4	7/27/2018	856.20	2 - 4 ft	180-80252-1	Not Excavated	8100	< 0.36 U	87	72	0.37 J	0.27 J	31000	10		6.5	24	19000	25	4800	400
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-4-6	7/27/2018	856.20	4 - 6 ft	180-80252-1	Not Excavated	12000	< 0.4 U	7.6	58	0.53	0.059 J	4800	15		11	21	23000	16	3000	490
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-6-8	7/27/2018	856.20	6 - 8 ft	180-80252-1	Not Excavated	6800	< 0.37 U	4.3	56	0.26 J	0.075 J	3700	9.3		5.4	16	16000	7.8	2400	450
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-8-10	7/27/2018	856.20	8 - 10 ft	180-80252-1	Not Excavated	5100	< 0.36 U	4.5	40	0.2 J	0.056 J	62000	7.1		4.1 J	14	11000	6.2	32000	470
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	4600	< 0.36 U	4	52	0.16 J	0.054 J	28000	6.1		4.9 J	17	12000	4.4	6600	670
Football Field	SSHS-B2031	PS-FD-48	7/27/2018	855.50	10 - 12 ft	180-80252-2	Not Excavated	7300	1.1	5.4	65	0.26 J	< 0.038 U	39000	12		6.4	25	15000	140	7100	440
Football Field	SSHS-B2031	SSHS-B2031-SUB-10-12	7/27/2018	855.50	10 - 12 ft	180-80251-2	Not Excavated	8000	< 0.36 U	5.4	68	0.27 J	0.094 J	33000	12		6.3	29	18000	93	6100	410
Football Field	SSHS-B2031	SSHS-B2031-SUB-2-4	7/27/2018	855.50	2 - 4 ft	180-80251-2	Not Excavated	7400	1.1	12	190	0.41 J	1.1	14000	48		8.7	170	35000	330	4000	520
Football Field	SSHS-B2031	SSHS-B2031-SUB-4-6	7/27/2018	855.50	4 - 6 ft	180-80251-2	Not Excavated	9600	< 0.39 U	6.4	90	0.39 J	0.28 J	36000	15		6.4	37	17000	120	5700	490
Football Field	SSHS-B2031	SSHS-B2031-SUB-6-8	7/27/2018	855.50	6 - 8 ft	180-80251-2	Not Excavated	7400	< 0.36 U	8.6	63	0.3 J	0.14 J	42000	12		6.6	29	19000	56	6900	460
Football Field	SSHS-B2031	SSHS-B2031-SUB-8-10	7/27/2018	855.50	8 - 10 ft	180-80251-2	Not Excavated	6600	< 0.35 U	8.1	66	0.23 J	0.58	52000	11		5.5	21	14000	18	13000	470
Football Field	SSHS-B2032	SSHS-B2032-SUB-2-4	7/27/2018	854.88	2 - 4 ft	180-80251-1	Excavated	6400	< 0.36 U	5.1	44	0.27 J	0.11 J	32000	8.7		5.4	22	15000	19	3700	400
Football Field	SSHS-B2032	SSHS-B2032-SUB-10-12	7/27/2018	854.88	10 - 12 ft	180-80251-1	Not Excavated	6100	< 0.35 U	5.8	44	0.25 J	0.08 J	37000	10		5.3	21	15000	7.9	6900	300
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	5400	< 0.36 U	5.2	40	0.21 J	0.064 J	59000	8.8		4.8 J	22	13000	6.4	7600	340
Football Field	SSHS-B2032	SSHS-B2032-SUB-4-6	7/27/2018	854.88	4 - 6 ft	180-80251-1	Not Excavated	5300	< 0.37 U	3.4	33	0.21 J	0.063 J	58000	7.3		4.4 J	17	13000	6.1	9200	290
Football Field	SSHS-B2032	SSHS-B2032-SUB-6-8	7/27/2018	854.88	6 - 8 ft	180-80251-1	Not Excavated	5100	< 0.36 U	4.4	37	0.23 J	0.064 J	44000	8.4		4.8 J	19	14000	6.5	6700	340
Football Field	SSHS-B2032	PS-FD-46	7/27/2018	854.88	8 - 10 ft	180-80252-2	Not Excavated	6300	< 0.35 U	4.5	45	0.23 J	< 0.038 U	47000	12		5.5	18	15000	10	9000	340
Football Field	SSHS-B2032	SSHS-B2032-SUB-8-10	7/27/2018	854.88	8 - 10 ft	180-80251-1	Not Excavated	5900	< 0.36 U	4.7	47	0.23 J	0.047 J	36000	12		5 J	17	15000	8.6	7700	330
Football Field	SSHS-B2033	SSHS-B2033-SUB-2-4	7/27/2018	854.70	2 - 4 ft	180-80251-1	Excavated	5800	< 0.35 U	3.9	48	0.23 J	0.071 J	37000	8.6		5.1 J	20	15000	27	4500	370
Football Field	SSHS-B2033	SSHS-B2033-SUB-10-12	7/27/2018	854.70	10 - 12 ft	180-80251-1	Not Excavated	6800	< 0.35 U	5.3	50	0.23 J	0.068 J	43000	9.4		5.5	21	16000	9	5100	360
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	854.70	12 - 14 ft	180-80251-1	Not Excavated	4500	< 0.7 U	2.9	36	0.18 J	0.037 J	100000	6.5		3.8 J	17	10000	3.6	6700	330
Football Field	SSHS-B2033	SSHS-B2033-SUB-4-6	7/27/2018	854.70	4 - 6 ft	180-80251-1	Not Excavated	6700	< 0.36 U	6.5	50	0.23 J	0.1 J	42000	9.3		6	26	17000	7.5	5700	390
Football Field	SSHS-B2033	SSHS-B2033-SUB-6-8	7/27/2018	854.70	6 - 8 ft	180-80251-1	Not Excavated	5900	< 0.41 U	7.1	38	0.28 J	0.11 J	25000	9.7		6.2	20	17000	8.5	6300	380
Football Field	SSHS-B2033	SSHS-B2033-SUB-8-10	7/27/2018	854.70	8 - 10 ft	180-80251-1	Not Excavated	6600	< 0.36 U	5.4	64	0.25 J	0.082 J	50000	10		5.6	21	16000	9.5	5600	390
Football Field	SSHS-B2050	SSHS-B2050-SUB-10-12	7/26/2018	855.45	10 - 12 ft	180-80225-2	Not Excavated	7800	< 0.39 U	6	78	0.33 J	< 0.042 U	2300	9.9		6.7	20	16000	17	2200	470
Football Field	SSHS-B2050	SSHS-B2050-SUB-2-4	7/26/2018	855.45	2 - 4 ft	180-80225-1	Not Excavated	7400	0.62 J	6.9	79	0.34 J	< 0.041 U	15000	9.6		5.7	33	16000	360	4400	360
Football Field	SSHS-B2050	SSHS-B2050-SUB-4-6	7/26/2018	855.45	4 - 6 ft	180-80225-1	Not Excavated	4800	2.1	9	100	0.26 J	< 0.048 U	34000	10		8.4	140	58000	360	1400	590
Football Field	SSHS-B2050	SSHS-B2050-SUB-6-8	7/26/2018	855.45	6 - 8 ft	180-80225-1	Not Excavated	11000	1.9	17	150	0.64	< 0.051 U	3800	16		9.8	53	23000	150	2000	660
Football Field	SSHS-B2050	SSHS-B2050-SUB-8-10	7/26/2018	855.45	8 - 10 ft	180-80225-2	Not Excavated	8400	0.79 J	9.7	66	0.38 J	< 0.044 U	2800	12		5.8 J	26	18000	55	2000	380
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	13000	< 0.42 U	7.8	110	0.6	< 0.045 U	2400	15		11	17	22000	16	3400	550
Football Field	SSHS-B2051	SSHS-B2051-SUB-2-4	7/27/2018	855.08	2 - 4 ft	180-80251-1	Excavated	12000	14	6.7	100	0.5 J	0.15 J	9300	15		7.7	54	21000	240	3100	660
Football Field	SSHS-B2051	PS-FD-45	7/27/2018	855.08	4 - 6 ft	180-80252-2	Excavated	13000	27	6.9	120	0.52	0.27 J	13000	15		10	81	24000	950	5600	390
Football Field	SSHS-B2051	SSHS-B2051-SUB-4-6	7/27/2018	855.08	4 - 6 ft	180-80251-1	Excavated	9300	130	16	180	0.47 J	0.95	14000	18		6.8	120	31000	1600	3100	450
Football Field	SSHS-B2051	SSHS-B2051-SUB-10-12	7/27/2018	855.08	10 - 12 ft	180-80251-1	Not Excavated	8800	6.7	7.1	96	0.42 J	0.49 J	15000	12		7.3	95	23000	280	2700	460
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	7400	< 0.39 U	4.6	47	0.28 J	0.11 J	1100	9.8		5.9	28	18000	5.6	2500	650
Football Field	SSHS-B2051	SSHS-B2051-SUB-6-8	7/27/2018	855.08	6 - 8 ft	180-80251-1	Not Excavated	12000	6	7	160	0.49 J	1.1	4700	14		9.6	45	34000	370	2400	1400
Football Field	SSHS-B2051	SSHS-B2051-SUB-8-10	7/27/2018	855.08	8 - 10 ft	180-80251-1	Not Excavated	13000	< 0.42 U	7.2	110	0.6	0.16 J	7500	22		11	24	25000	16	6000	580
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated	6400	15	8	140	0.4 J	0.37 J	15000	18		7.1	510	31000	150	2200	650
Football Field	SSHS-B2052	SSHS-B2052-SUB-4-6	7/25/2018	855.59	4 - 6 ft	180-80154-2	Excavated	6100	5	9.3	250	0.44 J	0.32 J	12000	18		7.1	180	34000	400	1700	650
Football Field	SSHS-B2052	PS-FD-24	7/25/2018	855.59	6 - 8 ft	180-80157-2	Excavated	4600	17	16	77	0.3 J	0.11 J	3400	26		9.4	120	150000	79	1100	670
Football Field	SSHS-B2052	SSHS-B2052-SUB-6-8	7/25/2018	855.59	6 - 8 ft	180-80154-2	Excavated	9400	5.8	7	120	0.41 J	0.21 J	5700	15		7.5	160	33000	110	2600	580
Football Field	SSHS-B2053	SSHS-B2053-SUB-10-12	7/25/2018	855.00	10 - 12 ft	180-80157-1	Excavated	7200	< 0.39 U	7.8	58	0.36 J	0.12 J	24000	10		6	45	21000	35	2600	350
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	5700	< 0.37 U	5.6	63	0.34 J	0.095 J	15000	9.9		5.3 J	44	21000	32	2300	410
Football Field	SSHS-B2053	SSHS-B2053-SUB-2-4	7/25/2018	855.00	2 - 4 ft	180-80157-1	Excavated	7500	< 0.4 U	10	120	0.55	0.19 J	16000	14		7.7	150	57000	82	1800	260
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	7600	0.6 J	13	120	0.59	0.27 J	8800	29		11	170	56000	190	2200	830
Football Field	SSHS-B2053	SSHS-B2053-SUB-6-8	7/25/2018	855.00	6 - 8 ft	180-80157-1	Excavated	7500	< 0.41 U	7.9	78	0.41 J	0.1 J	7800	11		6.4	57	23000	41	2000	440
Football Field	SSHS-B2053	PS-FD-26	7/25/2018	855.00	8 - 10 ft	180-80157-2	Excavated	9300	< 0.4 U	6.2	57	0.4 J	0.065 J	4000	14		7.6	44	23000	44	2400	370
Football Field	SSHS-B2053	SSHS-B2053-SUB-8-10	7/25/2018	855.00	8 - 10 ft	180-80157-1	Excavated	9800	0.5 J	6.7	62	0.42 J	0.1 J	4000	14		7.8	49	27000	50	2300	370
Football Field	SSHS-B2070	SSHS-B2070-SUB-10-12	7/25/2018	854.72	10 - 12 ft	180-80157-3	Not Excavated	6000	< 0.78 U	5.1	37	0.22 J	0.059 J	63000	9.3		5.5 J	20	14000	6.8	13000	400
Football Field	SSHS-B2070	SSHS-B2070-SUB-4-6	7/25/2018	854.72	4 - 6 ft	180-80157-3	Not Excavated	6000	< 0.38 U	5.4	40	0.26 J	0.077 J	5800	11		5.6	20	15000	23	2200	410
Football Field	SSHS-B2070	SSHS-B2070-SUB-6-8	7/25/2018	854.72	6 - 8 ft	180-80157-3	Not Excavated	6800	< 0.37 U	5.2	33	0.25 J	0.071 J	21000	8.9		6.1	26	16000	11	7100	500
Football Field	SSHS-B2070	SSHS-B2070-SUB-8-10	7/25/2018	854.72	8 - 10 ft	180-80157-3	Not Excavated	4900	< 0.37 U	6.9	37	0.19 J	0.043 J	41000	8.1		4.6 J	16	12000	14	8400	320
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	5100	< 0.36 U	4.6	39	0.22 J	0.063 J	33000	8.4		4.6 J	19	13000	8.9	14000	490
Football Field	SSHS-B2071	SSHS-B2071-SUB-2-4	7/27/2018	856.16	2 - 4 ft	180-80251-2	Excavated	5900	0.52 J	6.3	64	0.43 J	0.092 J	6400	9.8		4.7 J	75	22000	28	1300	160
Football Field	SSHS-B2071	SSHS-B2071-SUB-4-6	7/27/2018	856.16	4 - 6 ft	180-80251-2	Excavated	8300	240	11	73	0.47	0.89	2800	15		8.7	310	36000	870	1900	450
Football Field	SSHS-B2071	SSHS-B2071-SUB-6-8	7/27/2018	856.16	6 - 8 ft	180-80251-2	Excavated	11000	1.1 J,F1	4.6	86	0.42 J	0.046 J	1400	13		6.2	13	17000	14	2200	450
Football Field	SSHS-B2071	PS-FD-47	7/27/2018	856.16	10 - 12 ft	180-80252-2	Not Excavated	8300	< 0.38 U	5.5	69	0.39 J	< 0.041 U	970	9.5		6.5	23	17000	9.7	2300	690
Football Field	SSHS-B2071	SSHS-B2071-SUB-10-12	7/27/2018	856.16	10 - 12 ft	180-80251-2	Not Excavated	6700	< 0.39 U	4.2	58	0.27 J	0.072 J	950	9.4		5.7	34	17000	7.9	2000	530
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	7200	< 0.37 U	5.2	59	0.31 J	0.081 J	2200	9.7		5.8	54	16000	13	2400	560
Football Field	SSHS-B2071	SSHS-B2071-SUB-8-10	7/27/2018	856.16	8 - 10 ft	180-80251-2	Not Excavated	11000	5.6	6.1	85	0.46 J	0.094 J	1800	16		7.1	25	20000	150	2500	520
Football Field	SSHS-B2072	SSHS-B2072-SUB-10-12	7/25/2018	856.82	10 - 12 ft	180-80154-2	Excavated	7500	0.69 J	7.4	57	0.29 J	0.095 J	790	11		5.6	240	21000	46	2000	530
Football Field	SSHS-B2072	PS-FD-22	7/25/2018	856.82	2 - 4 ft	180-80157-2	Excavated	5800	< 0.4 U	5.7	74	0.34 J	0.1 J	9600	11		5 J	140	18000	42	1700	200
Football Field	SSHS-B2072	SSHS-B2072-SUB-2-4	7/25/2018	856.82	2 - 4 ft	180-80154-2	Excavated	7500	< 0.39 U	8.3	110	0.43 J	0.13 J	15000	14		6.8	140	27000	62	2700	350
Football Field	SSHS-B2072	SSHS-B2072-SUB-4-6	7/25/2018	856.82	4 - 6 ft	180-80154-2	Excavated	6100	27	7.8	45	0.28 J	0.48 J	4400	14		5.6 J	720	28000	260	1400	270
Football Field	SSHS-B2072	SSHS-B2072-SUB-6-8	7/25/2018	856.82	6 - 8 ft	180-80154-2	Excavated	7500	20	11	74	0.41 J	0.3 J	1600	19		11	1200	78000	3300	1200	680
Football Field	SSHS-B2072	SSHS-B2072-SUB-8-10	7/25/2018	856.82	8 - 10 ft	180-80154-2	Excavated	11000	< 0.41 U	6	140	0.45 J	0.14 J	1400	13		7.5	170	20000	26	2200	1100
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	6200	< 0.39 U	5.7	35	0.25 J	0.059 J	750	14		4.7 J	210	16000	52	1800	270
Football Field	SSHS-B2073	SSHS-B2073-SUB-2-4	7/25/2018	856.99	2 - 4 ft	180-80157-3	Excavated	5800	9.6	10	130	0.45 J	< 0.042 U	7800	27		9.4	310	49000	240	1900	650
Football Field	SSHS-B2073	SSHS-B2073-SUB-4-6	7/25/2018	856.99	4 - 6 ft	180-80157-3	Excavated	6700	9.8	11	600	0.54	1.3	8200	58		9	470	45000	360	2400	530
Football Field	SSHS-B2073	SSHS-B2073-SUB-6-8	7/25/2018	856.99	6 - 8 ft	180-80157-3	Excavated	3500	2.3	8.1	170	0.22 J	< 0.044 U	2500	53		5.2 J	980	39000	180	820	250
Football Field	SSHS-B2073	SSHS-B2073-SUB-8-10	7/25/2018	856.99	8 - 10 ft	180-80157-3	Excavated	7000	2.3	7.5	160	0.33 J	< 0.041 U	2800	42		7	290	37000	99	1700	450
Football Field	SSHS-B2073	SSHS-B2073-SUB-10-12	7/25/2018	856.99	10 - 12 ft	180-80157-3	Not Excavated	11000	< 0.41 U	7.6	65	0.41 J	< 0.044 U	1500	20		9.2	72	23000	21	2800	520
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	9600	< 0.41 U	7.5	74	0.35 J	< 0.044 U	1500	18		8.2	130	25000	27	2600	330
Football Field	SSHS-B2089	SSHS-B2089-SUB-10-12	7/25/2018	855.40	10 - 12 ft	180-80157-3	Not Excavated	4300	< 1.9 U	4.4	38	0.19 J	< 0.04 U	140000	6.8		4.2 J	16	11000	4.7	6500	310

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-2-4	7/27/2018	856.20	2 - 4 ft	180-80252-1	Not Excavated	0.054	17	710	< 0.55 U	< 0.11 U	76 J		< 0.24 U		13	54
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-4-6	7/27/2018	856.20	4 - 6 ft	180-80252-1	Not Excavated	0.063	19	880	< 0.61 U	< 0.12 U	71 J		< 0.25 U		21	56
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-6-8	7/27/2018	856.20	6 - 8 ft	180-80252-1	Not Excavated	0.02 J	13	680	< 0.56 U	< 0.11 U	41 J		< 0.23 U		11	48
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-8-10	7/27/2018	856.20	8 - 10 ft	180-80252-1	Not Excavated	0.0089 J	11	600	< 0.54 U	< 0.11 U	94 J		< 0.22 U		9.7	30
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	< 0.008 U	11	480 J	< 0.54 U	< 0.11 U	54 J		< 0.22 U		8	37
Football Field	SSHS-B2031	PS-FD-48	7/27/2018	855.50	10 - 12 ft	180-80252-2	Not Excavated	0.012 J	16	860	< 0.54 U	< 0.11 U	81 J		< 0.22 U		13	76
Football Field	SSHS-B2031	SSHS-B2031-SUB-10-12	7/27/2018	855.50	10 - 12 ft	180-80251-2	Not Excavated	0.01 J	18	710	< 0.54 U	< 0.11 U	63 J		< 0.22 U		12	78
Football Field	SSHS-B2031	SSHS-B2031-SUB-2-4	7/27/2018	855.50	2 - 4 ft	180-80251-2	Not Excavated	0.3	140	650	1.1	< 0.12 U	82 J		< 0.23 U		15	380
Football Field	SSHS-B2031	SSHS-B2031-SUB-4-6	7/27/2018	855.50	4 - 6 ft	180-80251-2	Not Excavated	0.029 J	26	720	< 0.59 U	< 0.12 U	71 J		< 0.24 U		13	140
Football Field	SSHS-B2031	SSHS-B2031-SUB-6-8	7/27/2018	855.50	6 - 8 ft	180-80251-2	Not Excavated	0.016 J	19	720	< 0.54 U	< 0.11 U	71 J		< 0.22 U		13	75
Football Field	SSHS-B2031	SSHS-B2031-SUB-8-10	7/27/2018	855.50	8 - 10 ft	180-80251-2	Not Excavated	0.015 J	15	660	< 0.53 U	< 0.11 U	75 J		< 0.22 U		9.5	200
Football Field	SSHS-B2032	SSHS-B2032-SUB-2-4	7/27/2018	854.88	2 - 4 ft	180-80251-1	Excavated	0.0079 J	17	610	< 0.55 U	< 0.11 U	74 J		< 0.22 U		11	61
Football Field	SSHS-B2032	SSHS-B2032-SUB-10-12	7/27/2018	854.88	10 - 12 ft	180-80251-1	Not Excavated	< 0.008 U	14	710	< 0.53 U	< 0.11 U	72 J		< 0.22 U		10	55
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	< 0.0079 U	13	630	< 0.55 U	< 0.11 U	77 J		< 0.22 U		8.8	60
Football Field	SSHS-B2032	SSHS-B2032-SUB-4-6	7/27/2018	854.88	4 - 6 ft	180-80251-1	Not Excavated	< 0.0082 U	12	560	< 0.55 U	< 0.11 U	65 J		< 0.22 U		8.4	40
Football Field	SSHS-B2032	SSHS-B2032-SUB-6-8	7/27/2018	854.88	6 - 8 ft	180-80251-1	Not Excavated	< 0.0082 U	13	650	< 0.55 U	< 0.11 U	66 J		< 0.22 U		8.6	41
Football Field	SSHS-B2032	PS-FD-46	7/27/2018	854.88	8 - 10 ft	180-80252-2	Not Excavated	< 0.0076 U	14	840	< 0.54 U	< 0.11 U	85 J		< 0.22 U		12	47
Football Field	SSHS-B2032	SSHS-B2032-SUB-8-10	7/27/2018	854.88	8 - 10 ft	180-80251-1	Not Excavated	< 0.0076 U	14	690	< 0.54 U	< 0.11 U	74 J		< 0.22 U		9.4	44
Football Field	SSHS-B2033	SSHS-B2033-SUB-2-4	7/27/2018	854.70	2 - 4 ft	180-80251-1	Excavated	< 0.008 U	42	510 J	< 0.54 U	< 0.11 U	54 J		< 0.22 U		8.6	52
Football Field	SSHS-B2033	SSHS-B2033-SUB-10-12	7/27/2018	854.70	10 - 12 ft	180-80251-1	Not Excavated	< 0.0079 U	14	700	< 0.53 U	< 0.11 U	64 J		< 0.22 U		10	52
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	854.70	12 - 14 ft	180-80251-1	Not Excavated	< 0.008 U	10	610	1	< 0.11 U	86 J		< 0.22 U		9.2	36
Football Field	SSHS-B2033	SSHS-B2033-SUB-4-6	7/27/2018	854.70	4 - 6 ft	180-80251-1	Not Excavated	< 0.0072 U	16	590	< 0.54 U	< 0.11 U	72 J		< 0.22 U		9.7	53
Football Field	SSHS-B2033	SSHS-B2033-SUB-6-8	7/27/2018	854.70	6 - 8 ft	180-80251-1	Not Excavated	< 0.009 U	16	810	< 0.62 U	< 0.13 U	59 J		< 0.25 U		13	50
Football Field	SSHS-B2033	SSHS-B2033-SUB-8-10	7/27/2018	854.70	8 - 10 ft	180-80251-1	Not Excavated	< 0.0074 U	15	770	0.54 J	< 0.11 U	73 J		< 0.22 U		10	56
Football Field	SSHS-B2050	SSHS-B2050-SUB-10-12	7/26/2018	855.45	10 - 12 ft	180-80225-2	Not Excavated	0.044	15	780	< 0.59 U	< 0.12 U	88 J		< 0.24 U		12	58
Football Field	SSHS-B2050	SSHS-B2050-SUB-2-4	7/26/2018	855.45	2 - 4 ft	180-80225-1	Not Excavated	0.076	13	690	< 0.58 U	< 0.12 U	75 J		< 0.24 U		14	58
Football Field	SSHS-B2050	SSHS-B2050-SUB-4-6	7/26/2018	855.45	4 - 6 ft	180-80225-1	Not Excavated	0.34	14	720	1.3	< 0.14 U	310 J		< 0.28 U		17	170
Football Field	SSHS-B2050	SSHS-B2050-SUB-6-8	7/26/2018	855.45	6 - 8 ft	180-80225-1	Not Excavated	0.28	17	1000	1.3 J	< 0.15 U	140 J		0.75 J		21	120
Football Field	SSHS-B2050	SSHS-B2050-SUB-8-10	7/26/2018	855.45	8 - 10 ft	180-80225-2	Not Excavated	0.099	13	780	0.72 J	< 0.13 U	130 J		0.28 J		15	70
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	0.095	22	1200	< 0.63 U	< 0.13 U	33 J		0.33 J		18	61
Football Field	SSHS-B2051	SSHS-B2051-SUB-2-4	7/27/2018	855.08	2 - 4 ft	180-80251-1	Excavated	0.15	18		< 0.66 U	< 0.14 U	300 J		< 0.27 U		18	110
Football Field	SSHS-B2051	PS-FD-45	7/27/2018	855.08	4 - 6 ft	180-80252-2	Excavated	0.27	26		< 0.6 U	2.3	370 J		0.5 J		20	540
Football Field	SSHS-B2051	SSHS-B2051-SUB-4-6	7/27/2018	855.08	4 - 6 ft	180-80251-1	Excavated	0.57	110		< 0.63 U	< 0.13 U	400 J		< 0.26 U		20	510
Football Field	SSHS-B2051	SSHS-B2051-SUB-10-12	7/27/2018	855.08	10 - 12 ft	180-80251-1	Not Excavated	0.087	17		< 0.57 U	< 0.12 U	190 J		< 0.23 U		18	210
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	< 0.009 U	15		< 0.58 U	< 0.12 U	33 J		< 0.24 U		11	66
Football Field	SSHS-B2051	SSHS-B2051-SUB-6-8	7/27/2018	855.08	6 - 8 ft	180-80251-1	Not Excavated	0.047	18		< 0.72 U	< 0.15 U	100 J		< 0.29 U		17	930
Football Field	SSHS-B2051	SSHS-B2051-SUB-8-10	7/27/2018	855.08	8 - 10 ft	180-80251-1	Not Excavated	0.014 J	25		< 0.63 U	< 0.13 U	64 J		< 0.26 U		17	72
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated	0.22	39		0.83 J	0.14 J	150 J		< 0.25 U		18	360
Football Field	SSHS-B2052	SSHS-B2052-SUB-4-6	7/25/2018	855.59	4 - 6 ft	180-80154-2	Excavated	0.26	29		1.3	< 0.13 U	140 J		< 0.25 U		19	200
Football Field	SSHS-B2052	PS-FD-24	7/25/2018	855.59	6 - 8 ft	180-80157-2	Excavated	0.19	19 J		1.2	< 0.12 U	64 J		0.32 J		12 J	350
Football Field	SSHS-B2052	SSHS-B2052-SUB-6-8	7/25/2018	855.59	6 - 8 ft	180-80154-2	Excavated	0.24	25		< 0.6 U	< 0.12 U	100 J		< 0.24 U		17	850
Football Field	SSHS-B2053	SSHS-B2053-SUB-10-12	7/25/2018	855.00	10 - 12 ft	180-80157-1	Excavated	0.11	18	630	0.99 J	< 0.12 U	96 J		< 0.24 U		13	68
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	0.08	15	590	0.57 J	< 0.11 U	120 J		< 0.23 U		12	60
Football Field	SSHS-B2053	SSHS-B2053-SUB-2-4	7/25/2018	855.00	2 - 4 ft	180-80157-1	Excavated	0.37	29	1700	0.87 J	< 0.12 U	210 J		< 0.24 U		16	130
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	0.092	34	830	1.5	< 0.12 U	150 J		< 0.24 U		38	160
Football Field	SSHS-B2053	SSHS-B2053-SUB-6-8	7/25/2018	855.00	6 - 8 ft	180-80157-1	Excavated	0.18	39	690	0.73 J	< 0.13 U	93 J		< 0.25 U		15	75
Football Field	SSHS-B2053	PS-FD-26	7/25/2018	855.00	8 - 10 ft	180-80157-2	Excavated	0.051	19	730	< 0.6 U	< 0.12 U	67 J		< 0.24 U		15	92
Football Field	SSHS-B2053	SSHS-B2053-SUB-8-10	7/25/2018	855.00	8 - 10 ft	180-80157-1	Excavated	0.079	20	760	< 0.59 U	< 0.12 U	92 J		< 0.24 U		18	83
Football Field	SSHS-B2070	SSHS-B2070-SUB-10-12	7/25/2018	854.72	10 - 12 ft	180-80157-3	Not Excavated	0.013 J	13	670	< 0.59 U	< 0.12 U	97 J		< 0.24 U		9.4	46
Football Field	SSHS-B2070	SSHS-B2070-SUB-4-6	7/25/2018	854.72	4 - 6 ft	180-80157-3	Not Excavated	0.029 J	14	560	< 0.57 U	< 0.12 U	38 J		< 0.23 U		9	49
Football Field	SSHS-B2070	SSHS-B2070-SUB-6-8	7/25/2018	854.72	6 - 8 ft	180-80157-3	Not Excavated	0.081	15	620	< 0.56 U	< 0.11 U	78 J		< 0.23 U		11	51
Football Field	SSHS-B2070	SSHS-B2070-SUB-8-10	7/25/2018	854.72	8 - 10 ft	180-80157-3	Not Excavated	0.0094 J	11	590	< 0.56 U	< 0.11 U	81 J		< 0.23 U		9.1	38
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	0.012 J	12	630	< 0.54 U	< 0.11 U	82 J		< 0.22 U		8.3	47
Football Field	SSHS-B2071	SSHS-B2071-SUB-2-4	7/27/2018	856.16	2 - 4 ft	180-80251-2	Excavated	0.023 J	14		1.2	< 0.12 U	430 J		< 0.24 U		18	65
Football Field	SSHS-B2071	SSHS-B2071-SUB-4-6	7/27/2018	856.16	4 - 6 ft	180-80251-2	Excavated	0.091	19		0.61 J	< 0.12 U	110 J		< 0.24 U		20	540
Football Field	SSHS-B2071	SSHS-B2071-SUB-6-8	7/27/2018	856.16	6 - 8 ft	180-80251-2	Excavated	0.021 J	14		< 0.6 U	< 0.12 U	57 J		< 0.24 U		16	49
Football Field	SSHS-B2071	PS-FD-47	7/27/2018	856.16	10 - 12 ft	180-80252-2	Not Excavated	0.012 J	26		< 0.58 U	< 0.12 U	740		0.25 J		13	56
Football Field	SSHS-B2071	SSHS-B2071-SUB-10-12	7/27/2018	856.16	10 - 12 ft	180-80251-2	Not Excavated	0.017 J	28		< 0.59 U	< 0.12 U	68 J		< 0.24 U		11	51
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	< 0.0078 U	82		< 0.56 U	< 0.11 U	49 J		< 0.23 U		11	54
Football Field	SSHS-B2071	SSHS-B2071-SUB-8-10	7/27/2018	856.16	8 - 10 ft	180-80251-2	Not Excavated	0.048	17		< 0.62 U	< 0.13 U	69 J		< 0.25 U		17	76
Football Field	SSHS-B2072	SSHS-B2072-SUB-10-12	7/25/2018	856.82	10 - 12 ft	180-80154-2	Excavated	0.08	110		< 0.56 U	< 0.11 U	62 J		< 0.23 U		13	700
Football Field	SSHS-B2072	PS-FD-22	7/25/2018	856.82	2 - 4 ft	180-80157-2	Excavated	0.26	30		0.9 J	< 0.12 U	120 J		< 0.25 U		13	160
Football Field	SSHS-B2072	SSHS-B2072-SUB-2-4	7/25/2018	856.82	2 - 4 ft	180-80154-2	Excavated	0.27	47		< 0.6 U	< 0.12 U	130 J		< 0.24 U		14	180
Football Field	SSHS-B2072	SSHS-B2072-SUB-4-6	7/25/2018	856.82	4 - 6 ft	180-80154-2	Excavated	0.39	200		< 0.65 U	0.54 J	120 J		< 0.27 U		15	8800
Football Field	SSHS-B2072	SSHS-B2072-SUB-6-8	7/25/2018	856.82	6 - 8 ft	180-80154-2	Excavated	0.33	130		1.3	0.25 J	97 J		< 0.26 U		35	1000
Football Field	SSHS-B2072	SSHS-B2072-SUB-8-10	7/25/2018	856.82	8 - 10 ft	180-80154-2	Excavated	0.13	110		< 0.62 U	< 0.13 U	87 J		< 0.25 U		16	560
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	0.03 J	100		< 0.59 U	< 0.12 U	64 J		< 0.24 U		9.9	480
Football Field	SSHS-B2073	SSHS-B2073-SUB-2-4	7/25/2018	856.99	2 - 4 ft	180-80157-3	Excavated	0.17	53		1.1 J	0.23 J	120 J		< 0.24 U		25	220
Football Field	SSHS-B2073	SSHS-B2073-SUB-4-6	7/25/2018	856.99	4 - 6 ft	180-80157-3	Excavated	0.31	320		< 0.6 U	1.2	150 J		0.3 J		20	1000
Football Field	SSHS-B2073	SSHS-B2073-SUB-6-8	7/25/2018	856.99	6 - 8 ft	180-80157-3	Excavated	0.23	350		1.1 J	0.9	190 J		0.44 J		17	560
Football Field	SSHS-B2073	SSHS-B2073-SUB-8-10	7/25/2018	856.99	8 - 10 ft	180-80157-3	Excavated	0.073	140		< 0.58 U	0.64	310 J		0.36 J		16	310
Football Field	SSHS-B2073	SSHS-B2073-SUB-10-12	7/25/2018	856.99	10 - 12 ft	180-80157-3	Not Excavated	0.035 J	62		< 0.63 U	0.13 J	54 J		0.36 J		19	100
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	0.034 J	97		< 0.62 U	< 0.13 U	61 J		0.32 J		18	140
Football Field	SSHS-B2089	SSHS-B2089-SUB-10-12	7/25/2018	855.40	10 - 12 ft	180-80157-3	Not Excavated	< 0.0078 U	11	630	< 0.57 U	< 0.12 U	97 J		< 0.23 U		7	31

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2089	SSHS-B2089-SUB-2-4	7/25/2018	855.40	2 - 4 ft	180-80157-3	Not Excavated	7700	< 0.41 U	6.5	57	0.37 J	0.081 J	26000	11		6.7	27	18000	38	3400	410
Football Field	SSHS-B2089	SSHS-B2089-SUB-4-6	7/25/2018	855.40	4 - 6 ft	180-80157-3	Not Excavated	7400	< 0.39 U	6.4	53	0.35 J	0.15 J	3700	10		7.2	23	17000	12	2100	950
Football Field	SSHS-B2089	SSHS-B2089-SUB-6-8	7/25/2018	855.40	6 - 8 ft	180-80157-3	Not Excavated	10000	< 0.38 U	8.8	67	0.46	0.11 J	3300	12		9.3	25	21000	22	3000	780
Football Field	SSHS-B2089	SSHS-B2089-SUB-8-10	7/25/2018	855.40	8 - 10 ft	180-80157-3	Not Excavated	4500	< 0.73 U	3.4	31	0.19 J	0.039 J	76000	6.3		4.5 J	15	11000	6.3	9500	440
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	9900	< 0.41 U	8.6	88	0.45 J	0.085 J	8000	13		8.4	25	22000	12	4900	520
Football Field	SSHS-B2090	SSHS-B2090-SUB-2-4	7/27/2018	855.97	2 - 4 ft	180-80251-2	Excavated	5800	2.5 J	20	53	0.32 J	0.62	11000	39		7.9	530	150000	97	1800	750
Football Field	SSHS-B2090	PS-FD-49	7/27/2018	855.97	4 - 6 ft	180-80252-2	Excavated	11000	< 0.46 U	7.4	58	0.38 J	< 0.049 U	2200	16		8.2	110	25000	40	2900	460
Football Field	SSHS-B2090	SSHS-B2090-SUB-4-6	7/27/2018	855.97	4 - 6 ft	180-80251-2	Excavated	11000	< 0.4 U	7.5	39	0.37 J	0.065 J	1800	16		7	85	28000	28	2800	260
Football Field	SSHS-B2090	SSHS-B2090-SUB-10-12	7/27/2018	855.97	10 - 12 ft	180-80251-2	Not Excavated	5600	< 0.37 U	5.5	55	0.25 J	0.17 J	12000	8.8		7.6	110	15000	12	3700	850
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	7400	< 0.39 U	4.2	28	0.26 J	0.08 J	10000	30		6.2	200	19000	40	5700	450
Football Field	SSHS-B2090	SSHS-B2090-SUB-6-8	7/27/2018	855.97	6 - 8 ft	180-80251-2	Not Excavated	8400	< 0.41 U	6.8	51	0.28 J	0.079 J	21000	19		5.3 J	270	28000	41	3000	270
Football Field	SSHS-B2090	SSHS-B2090-SUB-8-10	7/27/2018	855.97	8 - 10 ft	180-80251-2	Not Excavated	6800	< 0.38 U	7.1	23	0.24 J	0.052 J	2300	20		3.8 J	120	19000	24	1900	150
Football Field	SSHS-B2091	SSHS-B2091-SUB-10-12	7/25/2018	856.61	10 - 12 ft	180-80154-1	Not Excavated	6600	< 0.39 U	5.5	42	0.44 J	0.18 J	17000	17		5.3 J	570	14000	53	5600	260
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	6900	< 0.4 U	5.7	56	0.33 J	0.15 J	13000	16		7.1	670	17000	35	5100	380
Football Field	SSHS-B2091	SSHS-B2091-SUB-4-6	7/25/2018	856.61	4 - 6 ft	180-80154-1	Not Excavated	10000	< 0.39 U	8.6	55	0.48	0.18 J	1300	13		8.2	220	23000	29	2600	430
Football Field	SSHS-B2091	SSHS-B2091-SUB-6-8	7/25/2018	856.61	6 - 8 ft	180-80154-1	Not Excavated	8200	0.57 J	7.9	75	0.36 J	0.2 J	1800	24		7.2	440	23000	70	2600	280
Football Field	SSHS-B2091	SSHS-B2091-SUB-8-10	7/25/2018	856.61	8 - 10 ft	180-80154-1	Not Excavated	8900	< 0.4 U	9.5	52	0.44 J	0.21 J	6600	30		6.8	280	21000	63	4100	280
Football Field	SSHS-B2092	PS-FD-27	7/25/2018	856.77	2 - 4 ft	180-80157-2	Excavated	8700	< 0.41 U	6.1	77	0.37 J	0.17 J	8300	17		8.2	75	17000	36	3500	470
Football Field	SSHS-B2092	SSHS-B2092-SUB-2-4	7/25/2018	856.77	2 - 4 ft	180-80157-3	Excavated	10000	< 0.41 U	6.5	90	0.42 J	< 0.044 U	9200	21		8	230	21000	49	4000	440
Football Field	SSHS-B2108	SSHS-B2108-SUB-10-12	7/25/2018	855.64	10 - 12 ft	180-80154-3	Not Excavated	6600	< 0.75 U	6.5	42 J	0.24 J	0.57 J	57000	8.3		5.8	21	13000	7.8	4900	330
Football Field	SSHS-B2108	SSHS-B2108-SUB-2-4	7/25/2018	855.64	2 - 4 ft	180-80154-2	Not Excavated	12000	< 0.39 U	7.1	110	0.47	0.16 J	24000	15		7.5	31	20000	56	3900	530
Football Field	SSHS-B2108	SSHS-B2108-SUB-4-6	7/25/2018	855.64	4 - 6 ft	180-80154-2	Not Excavated	9400	< 0.37 U	8.9	60	0.43 J	0.1 J	2900	11		10	28	20000	13	2600	780
Football Field	SSHS-B2108	SSHS-B2108-SUB-6-8	7/25/2018	855.64	6 - 8 ft	180-80154-3	Not Excavated	9100	< 0.39 U	6.1	76	0.36 J	0.089 J	12000	11		6.8	22	19000	14	2700	590
Football Field	SSHS-B2108	SSHS-B2108-SUB-8-10	7/25/2018	855.64	8 - 10 ft	180-80154-3	Not Excavated	5500	< 0.37 U	4	36	0.22 J	0.058 J	4200	7		4.7 J	18	13000	12	2600	320
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	6500	< 0.37 U	4.3	45	0.23 J	0.096 J	30000	8.5		6.2	20	14000	11	4800	470
Football Field	SSHS-B2109	SSHS-B2109-SUB-10-12	7/25/2018	855.25	10 - 12 ft	180-80154-1	Not Excavated	7500	0.67 J	13	53	0.35 J	0.092 J	5100	13		6.7	310	20000	69	2600	350
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	5300	< 0.38 U	5.3	40	0.22 J	0.065 J	1600	8.8		4.6 J	170	14000	33	1800	430
Football Field	SSHS-B2109	SSHS-B2109-SUB-2-4	7/25/2018	855.25	2 - 4 ft	180-80154-1	Not Excavated	13000	< 0.4 U	6	59	0.48	< 0.043 U	1300	14		8.6	17	21000	11	3100	240
Football Field	SSHS-B2109	SSHS-B2109-SUB-4-6	7/25/2018	855.25	4 - 6 ft	180-80154-1	Not Excavated	10000	190	8.8	130	0.44 J	0.45 J	11000	12		8.3	370	29000	520	2800	590
Football Field	SSHS-B2109	SSHS-B2109-SUB-6-8	7/25/2018	855.25	6 - 8 ft	180-80154-1	Not Excavated	7500	< 0.37 U	6.7	43	0.31 J	0.048 J	1100	12		6.5	240	18000	20	2300	310
Football Field	SSHS-B2109	SSHS-B2109-SUB-8-10	7/25/2018	855.25	8 - 10 ft	180-80154-1	Not Excavated	5400	1.9	4.5	43	0.25 J	0.12 J	1200	8.8		4.8 J	100	13000	38	1400	260
Football Field	SSHS-B2110	SSHS-B2110-SUB-2-4	7/25/2018	854.78	2 - 4 ft	180-80154-1	Excavated	5800	4.7	36	110	0.4 J	0.15 J	1900	51		8.4	220	76000	120	1400	370
Football Field	SSHS-B2110	SSHS-B2110-SUB-4-6	7/25/2018	854.78	4 - 6 ft	180-80154-1	Excavated	9100	4.9	36	89	0.87	1.2	1300	33		11	520	44000	210	1900	250
Football Field	SSHS-B2110	SSHS-B2110-SUB-10-12	7/25/2018	854.78	10 - 12 ft	180-80154-1	Not Excavated	7300	2.5	16	68	0.43 J	0.18 J	2700	35		9.4	790	45000	160	1800	500
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	8900	< 0.38 U	7	60	0.41 J	0.61	23000	11		8.8	68	20000	11	6100	600
Football Field	SSHS-B2110	SSHS-B2110-SUB-6-8	7/25/2018	854.78	6 - 8 ft	180-80154-1	Not Excavated	6000	3.4	19	60	0.38 J	0.19 J	950	32		7.1	720	49000	120	1400	400
Football Field	SSHS-B2110	SSHS-B2110-SUB-8-10	7/25/2018	854.78	8 - 10 ft	180-80154-1	Not Excavated	7100	1.1 J	12	71	0.36 J	0.28 J	1300	20		6.9	200	25000	64	2000	310
Football Field	SSHS-B2127	SSHS-B2127-SUB-2-4	7/25/2018	855.91	2 - 4 ft	180-80154-3	Not Excavated	7400	0.48 J	6.5	97	0.37 J	0.14 J	21000	21		6.4	39	17000	40	3300	380
Football Field	SSHS-B2127	SSHS-B2127-SUB-10-12	7/25/2018	855.91	10 - 12 ft	180-80154-3	Not Excavated	6200	< 0.36 U	4.9	56	0.22 J	0.039 J	23000	8.9		5.3	19	15000	5.8	4500	460
Football Field	SSHS-B2127	SSHS-B2127-SUB-4-6	7/25/2018	855.91	4 - 6 ft	180-80154-3	Not Excavated	9100	< 0.39 U	6.2	64	0.39 J	0.071 J	15000	12		7.1	22	17000	35	2500	510
Football Field	SSHS-B2127	SSHS-B2127-SUB-6-8	7/25/2018	855.91	6 - 8 ft	180-80154-3	Not Excavated	6800	< 0.4 U	7.3	40	0.3 J	0.06 J	2400	9.4		5.9	19	16000	10	1800	410
Football Field	SSHS-B2127	SSHS-B2127-SUB-8-10	7/25/2018	855.91	8 - 10 ft	180-80154-3	Not Excavated	6300	< 0.39 U	5.2	39	0.26 J	0.067 J	16000	8.9		5.9	15	15000	15	3300	430
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	5400	< 0.36 U	5	46	0.19 J	0.061 J	28000	7.1		4.7 J	20	13000	11	7400	510
Football Field	SSHS-B2128	SSHS-B2128-SUB-10-12	7/25/2018	856.01	10 - 12 ft	180-80157-1	Not Excavated	7900	< 0.4 U	25	62	0.4 J	0.25 J	19000	12		9.5	26	22000	12	4700	1500
Football Field	SSHS-B2128	PS-FD-19	7/25/2018	856.01	2 - 4 ft	180-80157-2	Not Excavated	7200	1.1 J	9.3	90	0.45 J	0.14 J	12000	12		6.3	55	18000	64	2500	370
Football Field	SSHS-B2128	SSHS-B2128-SUB-2-4	7/25/2018	856.01	2 - 4 ft	180-80154-3	Not Excavated	7600	0.53 J	8.2	120	0.49	0.12 J	34000	9.2		5.1 J	52	14000	69	2400	500
Football Field	SSHS-B2128	SSHS-B2128-SUB-4-6	7/25/2018	856.01	4 - 6 ft	180-80157-1	Not Excavated	9800	1.5	8	77	0.46	0.1 J	6200	20		7.3	34	20000	31	2800	360
Football Field	SSHS-B2128	SSHS-B2128-SUB-6-8	7/25/2018	856.01	6 - 8 ft	180-80157-1	Not Excavated	7100	< 0.38 U	6.5	48	0.31 J	0.062 J	980	9.5		6.8	26	17000	9.6	2000	820
Football Field	SSHS-B2128	SSHS-B2128-SUB-8-10	7/25/2018	856.01	8 - 10 ft	180-80157-1	Not Excavated	6500	< 0.35 U	5.4	49	0.24 J	0.061 J	32000	8.9		6.7	18	15000	7.7	13000	610
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	7700	< 0.38 U	5.8	98	0.29 J	0.079 J	53000	12		6.6	24	17000	12	8600	540
Football Field	SSHS-B2129	SSHS-B2129-SUB-10-12	7/25/2018	855.33	10 - 12 ft	180-80157-1	Not Excavated	5800	< 0.37 U	4.2	56	0.25 J	0.057 J	26000	8.9		5.2 J	24	15000	32	7400	360
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	7000	2.6	4.8	58	0.29 J	0.083 J	11000	15		6.4	37	17000	62	6500	340
Football Field	SSHS-B2129	SSHS-B2129-SUB-2-4	7/25/2018	855.33	2 - 4 ft	180-80157-1	Not Excavated	13000	0.75 J	8.1	60	0.58	0.064 J	7700	17		12	35	29000	57	5600	400
Football Field	SSHS-B2129	SSHS-B2129-SUB-4-6	7/25/2018	855.33	4 - 6 ft	180-80157-1	Not Excavated	8400	< 0.37 U	4.2	28	0.35 J	< 0.04 U	1900	11		7.9	15	18000	9.7	3300	350
Football Field	SSHS-B2129	SSHS-B2129-SUB-6-8	7/25/2018	855.33	6 - 8 ft	180-80157-1	Not Excavated	8900	< 0.38 U	5.5	43	0.36 J	0.051 J	1800	12		8.1	34	20000	15	2900	440
Football Field	SSHS-B2129	SSHS-B2129-SUB-8-10	7/25/2018	855.33	8 - 10 ft	180-80157-1	Not Excavated	7300	0.52 J	6.1	68	0.29 J	0.066 J	15000	9.9		6.4	120	18000	35	3200	370
Football Field	SSHS-B2143	SSHS-B2143-SUB-10-12	7/25/2018	856.56	10 - 12 ft	180-80154-3	Not Excavated	5600	< 0.37 U	4.7	39	0.21 J	0.058 J	37000	15		5.1 J	19	14000	12	10000	370
Football Field	SSHS-B2143	SSHS-B2143-SUB-2-4	7/25/2018	856.56	2 - 4 ft	180-80154-3	Not Excavated	6400	< 0.4 U	7	87	0.34 J	0.086 J	9200	12		6.5	46	31000	53	2100	430
Football Field	SSHS-B2143	SSHS-B2143-SUB-4-6	7/25/2018	856.56	4 - 6 ft	180-80154-3	Not Excavated	5900	< 0.39 U	6	72	0.3 J	0.081 J	5900	8.6		5.6 J	26	17000	27	1900	470
Football Field	SSHS-B2143	PS-FD-21	7/25/2018	856.56	6 - 8 ft	180-80157-2	Not Excavated	6300	< 0.41 U	6.1	53	0.25 J	0.05 J	1800	8.4		4.8 J	25	15000	14	1900	490
Football Field	SSHS-B2143	SSHS-B2143-SUB-6-8	7/25/2018	856.56	6 - 8 ft	180-80154-3	Not Excavated	6800	< 0.38 U	6.6	68	0.34 J	0.11 J	2000	10		5.9	37	21000	20	2100	660
Football Field	SSHS-B2143	SSHS-B2143-SUB-8-10	7/25/2018	856.56	8 - 10 ft	180-80154-3	Not Excavated	6000	< 0.39 U	5.2	36	0.25 J	0.066 J	4700	9.4		5.1 J	22	15000	7.5	3200	420
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	4900	< 0.36 U	5.1	34	0.18 J	0.042 J	40000	8.3		4.7 J	17	12000	6.8	14000	420
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	6800	< 0.38 U	5.8	48	0.27 J	0.9	62000	15		5.8	88	15000	51	6700	330
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated	5000	< 0.37 U	3.4	54	0.23 J	0.087 J	34000	8.9		4 J	22	10000	14	4600	290
Football Field	SSHS-B2185	SSHS-B2185-SUB-10-12	7/24/2018	855.07	10 - 12 ft	180-80106-3	Not Excavated	8300	0.82 J	7.5	92	0.45 J	0.94	16000	34		5.9	120	20000	120	3800	330
Football Field	SSHS-B2185	PS-FD-16	7/24/2018	855.07	4 - 6 ft	180-80106-3	Not Excavated	8600	1.2	7	180	0.44 J	0.21 J	32000	19		6.8	59	21000	110	4300	440
Football Field	SSHS-B2185	SSHS-B2185-SUB-4-6	7/24/2018	855.07	4 - 6 ft	180-80106-3	Not Excavated	9100	< 0.38 U	5.6	97	0.43 J	0.14 J	50000	13		6.6	36	17000	38	4000	350
Football Field	SSHS-B2185	SSHS-B2185-SUB-6-8	7/24/2018	855.07	6 - 8 ft	180-80106-3	Not Excavated	8600	2.2	7.4	230	0.5	0.25 J	28000	15		6.9	81	21000	89	3500	620
Football Field	SSHS-B2185	SSHS-B2185-SUB-8-10	7/24/2018	855.07	8 - 10 ft	180-80106-3	Not Excavated	6800	< 0.39 U	5.8	98	0.35 J	0.23 J	25000	11		4.8 J	41	15000	43	4100	340
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated	6200	< 0.41 U	8.1	78	0.36 J	0.17 J	5300	17		6.9	100	23000	46	2100	360
Football Field	SSHS-B2186	SSHS-B2186-SUB-10-12	7/24/2018	854.94	10 - 12 ft	180-80106-2	Not Excavated	7300	< 0.39 U	6.9	63	0.33 J	0.13 J	12000	13		7.5	49	20000	23	5500	680
Football Field	SSHS-B2186	SSHS-B2186-SUB-4-6	7/24/2018	854.94	4 - 6 ft	180-80106-2	Not Excavated	6700	< 0.37 U	5.7	49	0.3 J	0.073 J	2400	17		7.5	54	22000	30	2700	330
Football Field	SSHS-B2186	SSHS-B2186-SUB-6-8	7/24/2018	854.94	6 - 8 ft	180-80106-2	Not Excavated	5800	< 0.37 U	4.4	42	0.26 J	0.095 J	7200	10		6.3	43	17000	13	2800	460

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2089	SSHS-B2089-SUB-2-4	7/25/2018	855.40	2 - 4 ft	180-80157-3	Not Excavated	0.089	16	680	< 0.62 U	< 0.13 U	65 J		< 0.25 U		13	89
Football Field	SSHS-B2089	SSHS-B2089-SUB-4-6	7/25/2018	855.40	4 - 6 ft	180-80157-3	Not Excavated	0.02 J	17	690	< 0.59 U	< 0.12 U	38 J		< 0.24 U		12	55
Football Field	SSHS-B2089	SSHS-B2089-SUB-6-8	7/25/2018	855.40	6 - 8 ft	180-80157-3	Not Excavated	< 0.008 U	20	940	< 0.57 U	< 0.12 U	44 J		< 0.23 U		16	87
Football Field	SSHS-B2089	SSHS-B2089-SUB-8-10	7/25/2018	855.40	8 - 10 ft	180-80157-3	Not Excavated	< 0.0082 U	11	570	< 0.55 U	< 0.11 U	88 J		< 0.23 U		6.4	36
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	0.022 J	21	920	< 0.61 U	< 0.13 U	37 J		< 0.25 U		15	62
Football Field	SSHS-B2090	SSHS-B2090-SUB-2-4	7/27/2018	855.97	2 - 4 ft	180-80251-2	Excavated	0.028 J	630		1.1 J	0.19 J	520 J		< 0.26 U		11 J	330
Football Field	SSHS-B2090	PS-FD-49	7/27/2018	855.97	4 - 6 ft	180-80252-2	Excavated	< 0.01 U	180		< 0.7 U	< 0.14 U	98 J		0.52 J		19	81
Football Field	SSHS-B2090	SSHS-B2090-SUB-4-6	7/27/2018	855.97	4 - 6 ft	180-80251-2	Excavated	0.025 J	160		< 0.6 U	< 0.12 U	85 J		< 0.24 U		18	77
Football Field	SSHS-B2090	SSHS-B2090-SUB-10-12	7/27/2018	855.97	10 - 12 ft	180-80251-2	Not Excavated	< 0.0084 U	550		< 0.56 U	< 0.12 U	43 J		< 0.23 U		8.7	230
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	< 0.0094 U	180		< 0.6 U	< 0.12 U	74 J		< 0.24 U		13	110
Football Field	SSHS-B2090	SSHS-B2090-SUB-6-8	7/27/2018	855.97	6 - 8 ft	180-80251-2	Not Excavated	0.032 J	200		< 0.62 U	< 0.13 U	150 J		< 0.25 U		14	90
Football Field	SSHS-B2090	SSHS-B2090-SUB-8-10	7/27/2018	855.97	8 - 10 ft	180-80251-2	Not Excavated	< 0.0084 U	110		< 0.58 U	< 0.12 U	60 J		< 0.23 U		14	50
Football Field	SSHS-B2091	SSHS-B2091-SUB-10-12	7/25/2018	856.61	10 - 12 ft	180-80154-1	Not Excavated	0.027 J	550		< 0.59 U	< 0.12 U	73 J		< 0.24 U		8.4	720
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	0.042	660		< 0.6 U	< 0.12 U	70 J		< 0.24 U		10	590
Football Field	SSHS-B2091	SSHS-B2091-SUB-4-6	7/25/2018	856.61	4 - 6 ft	180-80154-1	Not Excavated	0.021 J	260		< 0.59 U	< 0.12 U	66 J		< 0.24 U		17	200
Football Field	SSHS-B2091	SSHS-B2091-SUB-6-8	7/25/2018	856.61	6 - 8 ft	180-80154-1	Not Excavated	0.049	450		< 0.65 U	< 0.13 U	78 J		< 0.26 U		15	1000
Football Field	SSHS-B2091	SSHS-B2091-SUB-8-10	7/25/2018	856.61	8 - 10 ft	180-80154-1	Not Excavated	0.027 J	380		< 0.6 U	< 0.12 U	72 J		< 0.25 U		13	860
Football Field	SSHS-B2092	PS-FD-27	7/25/2018	856.77	2 - 4 ft	180-80157-2	Excavated	0.11	63		< 0.62 U	< 0.13 U	67 J		< 0.25 U		12	160
Football Field	SSHS-B2092	SSHS-B2092-SUB-2-4	7/25/2018	856.77	2 - 4 ft	180-80157-3	Excavated	0.12	58		< 0.62 U	0.13 J	80 J		0.44 J		18	190
Football Field	SSHS-B2108	SSHS-B2108-SUB-10-12	7/25/2018	855.64	10 - 12 ft	180-80154-3	Not Excavated	0.026 J	15	910 J	< 1.1 U	< 0.23 U	220 J		< 0.23 U		9.5 J	57
Football Field	SSHS-B2108	SSHS-B2108-SUB-2-4	7/25/2018	855.64	2 - 4 ft	180-80154-2	Not Excavated	0.25	22	1000	< 0.59 U	< 0.12 U	370 J		< 0.24 U		18	90
Football Field	SSHS-B2108	SSHS-B2108-SUB-4-6	7/25/2018	855.64	4 - 6 ft	180-80154-2	Not Excavated	0.026 J	21	930	< 0.57 U	< 0.12 U	53 J		< 0.23 U		17	57
Football Field	SSHS-B2108	SSHS-B2108-SUB-6-8	7/25/2018	855.64	6 - 8 ft	180-80154-3	Not Excavated	0.089	18	840	< 0.59 U	< 0.12 U	85 J		< 0.24 U		12	60
Football Field	SSHS-B2108	SSHS-B2108-SUB-8-10	7/25/2018	855.64	8 - 10 ft	180-80154-3	Not Excavated	0.039	11	610	< 0.57 U	< 0.12 U	60 J		< 0.23 U		8.1	51
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	0.012 J	15	590	< 0.56 U	< 0.11 U	61 J		< 0.23 U		9.5	57
Football Field	SSHS-B2109	SSHS-B2109-SUB-10-12	7/25/2018	855.25	10 - 12 ft	180-80154-1	Not Excavated	< 0.0079 U	170		< 0.57 U	< 0.12 U	63 J		< 0.23 U		12	180
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	0.023 J	110		< 0.58 U	< 0.12 U	56 J		< 0.23 U		8.4	130
Football Field	SSHS-B2109	SSHS-B2109-SUB-2-4	7/25/2018	855.25	2 - 4 ft	180-80154-1	Not Excavated	0.18	18		< 0.61 U	< 0.12 U	84 J		< 0.25 U		18	56
Football Field	SSHS-B2109	SSHS-B2109-SUB-4-6	7/25/2018	855.25	4 - 6 ft	180-80154-1	Not Excavated	0.055	19		0.98 J	< 0.12 U	81 J		< 0.25 U		16	200
Football Field	SSHS-B2109	SSHS-B2109-SUB-6-8	7/25/2018	855.25	6 - 8 ft	180-80154-1	Not Excavated	0.018 J	130		< 0.57 U	< 0.12 U	55 J		< 0.23 U		11	120
Football Field	SSHS-B2109	SSHS-B2109-SUB-8-10	7/25/2018	855.25	8 - 10 ft	180-80154-1	Not Excavated	0.14	49		< 0.59 U	< 0.12 U	71 J		< 0.24 U		9	120
Football Field	SSHS-B2110	SSHS-B2110-SUB-2-4	7/25/2018	854.78	2 - 4 ft	180-80154-1	Excavated	0.17	1200		3.4	0.3 J	71 J		0.49 J		29	270
Football Field	SSHS-B2110	SSHS-B2110-SUB-4-6	7/25/2018	854.78	4 - 6 ft	180-80154-1	Excavated	0.5	2200		3	0.29 J	75 J		0.75 J		25	950
Football Field	SSHS-B2110	SSHS-B2110-SUB-10-12	7/25/2018	854.78	10 - 12 ft	180-80154-1	Not Excavated	0.088	980		1.3	0.29 J	61 J		0.3 J		18	270
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.0083 U	970		< 0.58 U	< 0.12 U	97 J		< 0.23 U		13	290
Football Field	SSHS-B2110	SSHS-B2110-SUB-6-8	7/25/2018	854.78	6 - 8 ft	180-80154-1	Not Excavated	0.04	770		1.9	0.46 J	59 J		0.31 J		19	220
Football Field	SSHS-B2110	SSHS-B2110-SUB-8-10	7/25/2018	854.78	8 - 10 ft	180-80154-1	Not Excavated	0.16	560		1 J	< 0.13 U	69 J		< 0.25 U		15	220
Football Field	SSHS-B2127	SSHS-B2127-SUB-2-4	7/25/2018	855.91	2 - 4 ft	180-80154-3	Not Excavated	0.53	18	640	< 0.56 U	13	75 J		< 0.23 U		15	73
Football Field	SSHS-B2127	SSHS-B2127-SUB-10-12	7/25/2018	855.91	10 - 12 ft	180-80154-3	Not Excavated	< 0.008 U	13	510 J	< 0.54 U	< 0.11 U	67 J		< 0.22 U		8.8	44
Football Field	SSHS-B2127	SSHS-B2127-SUB-4-6	7/25/2018	855.91	4 - 6 ft	180-80154-3	Not Excavated	0.082	16	700	< 0.59 U	0.21 J	64 J		< 0.24 U		14	58
Football Field	SSHS-B2127	SSHS-B2127-SUB-6-8	7/25/2018	855.91	6 - 8 ft	180-80154-3	Not Excavated	0.043	13	750	< 0.61 U	< 0.12 U	54 J		< 0.25 U		12	49
Football Field	SSHS-B2127	SSHS-B2127-SUB-8-10	7/25/2018	855.91	8 - 10 ft	180-80154-3	Not Excavated	0.01 J	13	670	< 0.59 U	< 0.12 U	64 J		< 0.24 U		11	48
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	0.0082 J	12	550	< 0.55 U	< 0.11 U	73 J		< 0.22 U		8.7	47
Football Field	SSHS-B2128	SSHS-B2128-SUB-10-12	7/25/2018	856.01	10 - 12 ft	180-80157-1	Not Excavated	0.018 J	21		< 0.6 U	< 0.12 U	60 J		< 0.24 U		13	86
Football Field	SSHS-B2128	PS-FD-19	7/25/2018	856.01	2 - 4 ft	180-80157-2	Not Excavated	0.23	17		0.88 J	< 0.12 U	140 J		< 0.25 U		16	87
Football Field	SSHS-B2128	SSHS-B2128-SUB-2-4	7/25/2018	856.01	2 - 4 ft	180-80154-3	Not Excavated	0.11	14		1.2	< 0.12 U	170 J		< 0.24 U		14	68
Football Field	SSHS-B2128	SSHS-B2128-SUB-4-6	7/25/2018	856.01	4 - 6 ft	180-80157-1	Not Excavated	0.093	19		< 0.58 U	< 0.12 U	90 J		< 0.24 U		17	69
Football Field	SSHS-B2128	SSHS-B2128-SUB-6-8	7/25/2018	856.01	6 - 8 ft	180-80157-1	Not Excavated	0.021 J	17		< 0.57 U	< 0.12 U	44 J		< 0.23 U		11	51
Football Field	SSHS-B2128	SSHS-B2128-SUB-8-10	7/25/2018	856.01	8 - 10 ft	180-80157-1	Not Excavated	0.01 J	15		< 0.54 U	< 0.11 U	87 J		< 0.22 U		10	55
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	0.036 J	17		0.92 J	< 0.12 U	82 J		< 0.23 U		12	60
Football Field	SSHS-B2129	SSHS-B2129-SUB-10-12	7/25/2018	855.33	10 - 12 ft	180-80157-1	Not Excavated	0.019 J	12		< 0.56 U	< 0.11 U	89 J		< 0.23 U		9.6	69
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	0.04	16		< 0.6 U	< 0.12 U	78 J		< 0.24 U		10	80
Football Field	SSHS-B2129	SSHS-B2129-SUB-2-4	7/25/2018	855.33	2 - 4 ft	180-80157-1	Not Excavated	0.19	29		0.62 J	< 0.12 U	74 J		< 0.24 U		16	89
Football Field	SSHS-B2129	SSHS-B2129-SUB-4-6	7/25/2018	855.33	4 - 6 ft	180-80157-1	Not Excavated	0.046	18		< 0.57 U	< 0.12 U	59 J		< 0.23 U		10	49
Football Field	SSHS-B2129	SSHS-B2129-SUB-6-8	7/25/2018	855.33	6 - 8 ft	180-80157-1	Not Excavated	0.05	20		< 0.58 U	< 0.12 U	50 J		< 0.24 U		12	56
Football Field	SSHS-B2129	SSHS-B2129-SUB-8-10	7/25/2018	855.33	8 - 10 ft	180-80157-1	Not Excavated	< 0.0082 U	17		< 0.56 U	< 0.11 U	61 J		< 0.23 U		13	64
Football Field	SSHS-B2143	SSHS-B2143-SUB-10-12	7/25/2018	856.56	10 - 12 ft	180-80154-3	Not Excavated	< 0.0081 U	13		< 0.56 U	< 0.12 U	77 J		< 0.23 U		9.1	48
Football Field	SSHS-B2143	SSHS-B2143-SUB-2-4	7/25/2018	856.56	2 - 4 ft	180-80154-3	Not Excavated	0.15	19		1.4	< 0.12 U	97 J		< 0.24 U		16	62
Football Field	SSHS-B2143	SSHS-B2143-SUB-4-6	7/25/2018	856.56	4 - 6 ft	180-80154-3	Not Excavated	0.069	14		< 0.6 U	< 0.12 U	77 J		< 0.24 U		11	58
Football Field	SSHS-B2143	PS-FD-21	7/25/2018	856.56	6 - 8 ft	180-80157-2	Not Excavated	0.045	13		< 0.63 U	< 0.13 U	44 J		< 0.25 U		9.1	48
Football Field	SSHS-B2143	SSHS-B2143-SUB-6-8	7/25/2018	856.56	6 - 8 ft	180-80154-3	Not Excavated	0.019 J	16		< 0.57 U	< 0.12 U	50 J		< 0.23 U		11	59
Football Field	SSHS-B2143	SSHS-B2143-SUB-8-10	7/25/2018	856.56	8 - 10 ft	180-80154-3	Not Excavated	0.0094 J	13		< 0.59 U	< 0.12 U	52 J		< 0.24 U		11	49
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	0.026 J	12		< 0.54 U	< 0.11 U	92 J		< 0.22 U		7.8	40
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	0.13	150		< 0.58 U	< 0.12 U	91 J		< 0.24 U		11	460
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated	0.12	16		< 0.56 U	< 0.11 U	150 J		< 0.23 U		12	52
Football Field	SSHS-B2185	SSHS-B2185-SUB-10-12	7/24/2018	855.07	10 - 12 ft	180-80106-3	Not Excavated	0.13	140		0.88 J	< 0.12 U	81 J		< 0.24 U		16	820
Football Field	SSHS-B2185	PS-FD-16	7/24/2018	855.07	4 - 6 ft	180-80106-3	Not Excavated	0.065	36		< 0.58 U	< 0.12 U	240 J		< 0.24 U		19	180
Football Field	SSHS-B2185	SSHS-B2185-SUB-4-6	7/24/2018	855.07	4 - 6 ft	180-80106-3	Not Excavated	0.059	31		0.67 J	< 0.12 U	300 J		< 0.23 U		19	91
Football Field	SSHS-B2185	SSHS-B2185-SUB-6-8	7/24/2018	855.07	6 - 8 ft	180-80106-3	Not Excavated	0.11	170		0.71 J	0.22 J	340 J		< 0.26 U		20	190
Football Field	SSHS-B2185	SSHS-B2185-SUB-8-10	7/24/2018	855.07	8 - 10 ft	180-80106-3	Not Excavated	0.071	49		< 0.59 U	< 0.12 U	170 J		< 0.24 U		13	240
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated	0.074	63		< 0.62 U	< 0.13 U	62 J		< 0.25 U		13	95
Football Field	SSHS-B2186	SSHS-B2186-SUB-10-12	7/24/2018	854.94	10 - 12 ft	180-80106-2	Not Excavated	< 0.0082 U	28		< 0.59 U	< 0.12 U	73 J		< 0.24 U		12	87
Football Field	SSHS-B2186	SSHS-B2186-SUB-4-6	7/24/2018	854.94	4 - 6 ft	180-80106-2	Not Excavated	0.03 J	41		0.65 J	< 0.12 U	62 J		< 0.23 U		11	63
Football Field	SSHS-B2186	SSHS-B2186-SUB-6-8	7/24/2018	854.94	6 - 8 ft	180-80106-2	Not Excavated	0.039	21		< 0.56 U	< 0.11 U	52 J		< 0.23 U		10	67

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2186	SSHS-B2186-SUB-8-10	7/24/2018	854.94	8 - 10 ft	180-80106-2	Not Excavated	5200	< 0.37 U	6.7	41	0.24 J	0.08 J	31000	8.4		5.8	35	16000	22	17000	670
Football Field	SSHS-B2187	SSHS-B2187-SUB-10-12	7/24/2018	856.10	10 - 12 ft	180-80106-2	Not Excavated	6400	< 0.36 U	7	51	0.23 J	0.058 J	51000	9.9		5.9	24	15000	10	15000	430
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	2 - 4 ft	180-80106-1	Not Excavated	8400	< 0.39 U	10	81	0.39 J	0.17 J	25000	13		7.6	55	20000	80	3800	430
Football Field	SSHS-B2187	SSHS-B2187-SUB-4-6	7/24/2018	856.10	4 - 6 ft	180-80106-1	Not Excavated	8700	< 0.39 U	12	90	0.53	0.13 J	1900	12		8.1	47	24000	18	2400	890
Football Field	SSHS-B2187	SSHS-B2187-SUB-6-8	7/24/2018	856.10	6 - 8 ft	180-80106-2	Not Excavated	5400	< 0.38 U	8.4	42	0.28 J	0.11 J	23000	8.3		4.9 J	22	16000	26	13000	740
Football Field	SSHS-B2187	SSHS-B2187-SUB-8-10	7/24/2018	856.10	8 - 10 ft	180-80106-2	Not Excavated	5600	< 0.38 U	6.4	37	0.23 J	0.085 J	39000	7.6		6.4	21	13000	13	17000	500
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	6300	< 0.39 U	6.3	76	0.23 J	0.074 J	34000	9		5.8	21	16000	8.7	11000	450
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated	5700	0.75 J	6.5	240	0.29 J	0.33 J	11000	25		4.9 J	220	20000	250	2400	330
Football Field	SSHS-B2188	SSHS-B2188-SUB-4-6	7/24/2018	855.99	4 - 6 ft	180-80106-2	Excavated	6700	0.81 J	7	360	0.45 J	0.37 J	20000	28		6.6	110	24000	320	3100	420
Football Field	SSHS-B2188	SSHS-B2188-SUB-10-12	7/24/2018	855.99	10 - 12 ft	180-80106-2	Not Excavated	6400	< 0.77 U	3.7	58	0.24 J	0.12 J	170000	9.7		4.2 J	26	12000	29	9700	450
Football Field	SSHS-B2188	SSHS-B2188-SUB-6-8	7/24/2018	855.99	6 - 8 ft	180-80106-2	Not Excavated	5400	0.66 J	8.8	350	0.37 J	0.28 J	14000	26		6.8	120	27000	480	2900	410
Football Field	SSHS-B2188	PS-FD-14	7/24/2018	855.99	8 - 10 ft	180-80106-2	Not Excavated	6200	< 0.36 U	3.4	46	0.23 J	0.065 J	38000	10		5.3	25	14000	17	6900	340
Football Field	SSHS-B2188	SSHS-B2188-SUB-8-10	7/24/2018	855.99	8 - 10 ft	180-80106-2	Not Excavated	5500	< 0.37 U	4.1	50	0.21 J	0.084 J	46000	11		4.6 J	24	14000	21	9000	360
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	8200	< 0.72 U	3.5	56	0.29 J	0.07 J	90000	11		5.1 J	22	14000	9.7	10000	330
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated	8000	< 0.37 U	6.5	71	0.34 J	0.11 J	12000	14		6.5	61	20000	56	3100	420
Football Field	SSHS-B2189	SSHS-B2189-SUB-4-6	7/24/2018	855.74	4 - 6 ft	180-80105-3	Excavated	8900	< 0.39 U	10	170	0.43 J	0.32 J	20000	21		8.4	130	37000	99	3400	570
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	8200	< 0.37 U	7	75	0.3 J	0.14 J	20000	15		7.8	40	29000	30	4800	550
Football Field	SSHS-B2189	PS-FD-12	7/24/2018	855.74	10 - 12 ft	180-80106-1	Not Excavated	6200	< 0.37 U	5.4	44	0.25 J	0.095 J	28000	11		6.1	29	21000	15	7100	410
Football Field	SSHS-B2189	SSHS-B2189-SUB-10-12	7/24/2018	855.74	10 - 12 ft	180-80105-3	Not Excavated	7200	< 0.35 U	5	53	0.28 J	0.11 J	38000	12		6.7	34	18000	18	8700	530
Football Field	SSHS-B2189	SSHS-B2189-SUB-6-8	7/24/2018	855.74	6 - 8 ft	180-80105-3	Not Excavated	8300	0.42 J	12	170	0.5	0.43 J	16000	25		10	560	41000	260	2900	480
Football Field	SSHS-B2189	SSHS-B2189-SUB-8-10	7/24/2018	855.74	8 - 10 ft	180-80105-3	Not Excavated	8200	0.76 J	7.5	80	0.49	0.31 J	20000	19		7.9	79	30000	83	2900	600
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated	7200	< 0.38 U	6.5	71	0.27 J	< 0.041 U	8500	9.9		5.6	32	15000	31	2300	460
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated	9600	< 0.37 U	6.2	96	0.38 J	0.14 J	12000	13		7.7	41	21000	44	3400	590
Football Field	SSHS-B2190	SSHS-B2190-SUB-4-6	7/27/2018	856.06	4 - 6 ft	180-80252-1	Excavated	8300	< 0.37 U	5.6	210	0.35 J	0.22 J	27000	15		6.3	120	23000	150	3300	460
Football Field	SSHS-B2190	SSHS-B2190-SUB-6-8	7/27/2018	856.06	6 - 8 ft	180-80252-1	Not Excavated	6700	3.3	10	230	0.26 J	< 0.082 U	94000	37		8.3	260	88000	160	3100	700
Football Field	SSHS-B2190	SSHS-B2190-SUB-8-10	7/27/2018	856.06	8 - 10 ft	180-80252-2	Not Excavated	8500	1.1	6.2	140	0.33 J	< 0.039 U	39000	27		7.7	110	38000	120	4600	560
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated	8100	< 0.4 U	7	110	0.37 J	0.16 J	8500	15		7.4	51	22000	82	3300	580
Football Field	SSHS-B2191	SSHS-B2191-SUB-4-6	7/24/2018	856.18	4 - 6 ft	180-80105-3	Excavated	8400	< 0.38 U	6.1	150	0.39 J	0.11 J	5000	13		5.7	93	20000	85	2200	560
Football Field	SSHS-B2191	SSHS-B2191-SUB-6-8	7/24/2018	856.18	6 - 8 ft	180-80105-3	Not Excavated	8200	< 0.37 U	6.2	120	0.37 J	0.15 J	37000	12		6.1	45	19000	62	3700	640
Football Field	SSHS-B2191	SSHS-B2191-SUB-10-12	7/24/2018	856.18	10 - 12 ft	180-80105-3	Not Excavated	7500	< 0.4 U	6.8	92	0.33 J	0.15 J	24000	21		6.5	51	23000	67	5100	540
Football Field	SSHS-B2191	SSHS-B2191-SUB-8-10	7/24/2018	856.18	8 - 10 ft	180-80105-3	Not Excavated	7700	< 0.39 U	5.7	130	0.33 J	0.22 J	58000	14		6.1	120	18000	86	5100	460
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	6000	< 0.38 U	7.6	54	0.29 J	0.11 J	10000	9.6		6	21	16000	16	3100	470
Football Field	SSHS-B2192	SSHS-B2192-SUB-10-12	7/26/2018	855.49	10 - 12 ft	180-80225-1	Not Excavated	3400	< 0.39 U	3	25	0.15 J	< 0.041 U	54000	4.8		3.2 J	52	8400	4.7	2200	230
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	6500	< 0.39 U	5.4	48	0.3 J	< 0.041 U	9300	9.2		6.4	69	18000	17	3500	420
Football Field	SSHS-B2192	PS-FD-34	7/26/2018	855.49	4 - 6 ft	180-80225-3	Not Excavated	7800	0.54 J	7.5	110	0.68	< 0.041 U	2700	10		8.3	36	29000	31	2000	730
Football Field	SSHS-B2192	SSHS-B2192-SUB-4-6	7/26/2018	855.49	4 - 6 ft	180-80225-1	Not Excavated	5800	0.48 J	5.5	68	0.44 J	0.12 J	2100	17		6.2	23	30000	24	1400	860
Football Field	SSHS-B2192	SSHS-B2192-SUB-6-8	7/26/2018	855.49	6 - 8 ft	180-80225-1	Not Excavated	8100	< 0.39 U	6.4	90	0.75	0.14 J	3900	11		8.7	41	23000	35	2000	510
Football Field	SSHS-B2192	SSHS-B2192-SUB-8-10	7/26/2018	855.49	8 - 10 ft	180-80225-1	Not Excavated	5800	< 0.37 U	7.1	49	0.31 J	0.11 J	2800	9.1		6.3	150	18000	14	2600	530
Football Field	SSHS-B2193	PS-FD-33	7/26/2018	857.04	2 - 4 ft	180-80225-3	Excavated	6900	1.5	7.1	150	0.33 J	0.29 J	15000	13		5.6	360	18000	140	2400	350
Football Field	SSHS-B2193	SSHS-B2193-SUB-2-4	7/26/2018	857.04	2 - 4 ft	180-80225-1	Excavated	7000	< 0.39 U	7.8	160	0.38 J	0.29 J	17000	14		5.9	74	19000	110	3000	420
Football Field	SSHS-B2194	SSHS-B2194-SUB-2-4	7/25/2018	856.19	2 - 4 ft	180-80157-3	Excavated	7100	< 0.41 U	7.5	190	0.38 J	0.59 J	8000	30		6.6	77	19000	290	2500	310
Football Field	SSHS-B2194	SSHS-B2194-SUB-10-12	7/25/2018	856.19	10 - 12 ft	180-80157-3	Not Excavated	6100	< 0.36 U	4.4	40	0.21 J	0.098 J	6800	10		5.6	27	15000	18	3700	410
Football Field	SSHS-B2194	SSHS-B2194-SUB-4-6	7/25/2018	856.19	4 - 6 ft	180-80157-3	Not Excavated	8400	< 0.4 U	8.6	110	0.4 J	0.27 J	11000	22		7.5	56	20000	71	2900	470
Football Field	SSHS-B2194	PS-FD-30	7/25/2018	856.19	6 - 8 ft	180-80157-2	Not Excavated	6800	< 0.4 U	7.2	47	0.32 J	0.15 J	2800	14		5.8 J	33	18000	58	2100	370
Football Field	SSHS-B2194	SSHS-B2194-SUB-6-8	7/25/2018	856.19	6 - 8 ft	180-80157-3	Not Excavated	8800	< 0.41 U	6.1	58	0.36 J	0.17 J	3600	17		6.9	36	20000	34	2700	400
Football Field	SSHS-B2194	SSHS-B2194-SUB-8-10	7/25/2018	856.19	8 - 10 ft	180-80157-3	Not Excavated	6000	< 0.38 U	5	31	0.26 J	0.092 J	17000	9.1		5.8	21	16000	10	4800	400
Football Field	SSHS-B2195	SSHS-B2195-SUB-2-4	7/26/2018	855.94	2 - 4 ft	180-80225-1	Excavated	5300	1.6	16	270	0.8	0.52 J	6100	30		7.1	72	25000	280	2000	180
Football Field	SSHS-B2195	SSHS-B2195-SUB-10-12	7/26/2018	855.94	10 - 12 ft	180-80225-1	Not Excavated	6000	< 0.37 U	4.8	59	0.3 J	0.23 J	4600	16		5.5	28	17000	69	2100	400
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	6200	< 0.39 U	5.3	40	0.27 J	0.11 J	1900	9.5		5.8	23	15000	18	2300	320
Football Field	SSHS-B2195	SSHS-B2195-SUB-4-6	7/26/2018	855.94	4 - 6 ft	180-80225-1	Not Excavated	9100	< 0.44 U	8.1	130	0.49 J	0.55 J	23000	36		7.5	63	25000	620	3100	460
Football Field	SSHS-B2195	SSHS-B2195-SUB-6-8	7/26/2018	855.94	6 - 8 ft	180-80225-1	Not Excavated	6600	0.69 J	6.9	68	0.36 J	0.32 J	10000	18		6.6	41	20000	150	2700	460
Football Field	SSHS-B2195	PS-FD-31	7/26/2018	855.94	8 - 10 ft	180-80225-3	Not Excavated	6100	< 0.38 U	6.9	46	0.29 J	< 0.041 U	5900	12		5.8	26	16000	63	2300	470
Football Field	SSHS-B2195	SSHS-B2195-SUB-8-10	7/26/2018	855.94	8 - 10 ft	180-80225-1	Not Excavated	6400	< 0.39 U	5.9	36	0.31 J	0.15 J	3700	11		5.9	24	17000	61	2500	510
Football Field	SSHS-B2197	SSHS-B2197-SUB-10-12	7/24/2018	854.99	10 - 12 ft	180-80105-1	Not Excavated	4600	< 0.38 U	4.9	37	0.2 J	0.054 J	27000	6.6		4.3 J	31	12000	9.7	4600	360
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	5200	< 0.38 U	3.5	30	0.21 J	0.062 J	19000	6.9		4.7 J	18	13000	8.1	4300	380
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated	8800	< 0.38 U	5.4	70	0.38 J	0.1 J	7300	12		7.2	25	17000	63	3100	360
Football Field	SSHS-B2197	SSHS-B2197-SUB-4-6	7/24/2018	854.99	4 - 6 ft	180-80105-1	Not Excavated	8600	< 0.38 U	5.6	49	0.37 J	0.058 J	4000	12		7	18	18000	15	2300	390
Football Field	SSHS-B2197	SSHS-B2197-SUB-6-8	7/24/2018	854.99	6 - 8 ft	180-80105-1	Not Excavated	7700	< 0.4 U	6.7	49	0.36 J	0.055 J	5500	11		6.9	21	18000	12	2800	400
Football Field	SSHS-B2197	SSHS-B2197-SUB-8-10	7/24/2018	854.99	8 - 10 ft	180-80105-1	Not Excavated	4500	< 0.37 U	3.7	42	0.2 J	0.081 J	9300	6.9		3.7 J	16	11000	12	4400	450
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	855.05	12 - 14 ft	180-80105-2	Not Excavated	6100	< 0.39 U	5.3	48	0.25 J	0.09 J	9600	8.5		6.1	29	17000	9	6100	470
Football Field	SSHS-B2198	SSHS-B2198-SUB-10-12	7/24/2018	855.05	10 - 12 ft	180-80105-2	Excavated	6100	< 0.39 U	4.8	46	0.26 J	0.084 J	11000	10		5.5 J	23	15000	9.4	5000	520
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated	12000	< 0.41 U	6.4	200	0.59	< 0.044 U	8700	14		18	32	23000	130	2700	380
Football Field	SSHS-B2198	SSHS-B2198-SUB-4-6	7/24/2018	855.05	4 - 6 ft	180-80105-2	Excavated	9800	< 0.41 U	9.2	63	0.53	0.05 J	4000	13		9.3	26	23000	34	2600	360
Football Field	SSHS-B2198	SSHS-B2198-SUB-6-8	7/24/2018	855.05	6 - 8 ft	180-80105-2	Excavated	9100	< 0.39 U	7.5	58	0.42 J	0.073 J	5500	11		8.2	20	20000	20	3300	600
Football Field	SSHS-B2198	SSHS-B2198-SUB-8-10	7/24/2018	855.05	8 - 10 ft	180-80105-2	Excavated	6300	< 0.38 U	4.8	35	0.27 J	0.084 J	17000	9.4		5.6	22	15000	10	6700	400
Football Field	SSHS-B2213	PS-FD-35	7/26/2018	855.06	10 - 12 ft	180-80225-3	Not Excavated	6700	0.74 J	12	55	0.28 J	< 0.041 U	1400	24		8.3	36	37000	17	1800	510
Football Field	SSHS-B2213	SSHS-B2213-SUB-10-12	7/26/2018	855.06	10 - 12 ft	180-80225-2	Not Excavated	7300	< 0.37 U	5.5	59	0.28 J	< 0.039 U	2000	14		6.5	21	16000	20	2100	510
Football Field	SSHS-B2213	SSHS-B2213-SUB-2-4	7/26/2018	855.06	2 - 4 ft	180-80225-2	Not Excavated	6500	0.69 J	7.3	130	0.41 J	< 0.044 U	26000	11		5.6 J	34	22000	48	1600	290
Football Field	SSHS-B2213	SSHS-B2213-SUB-4-6	7/26/2018	855.06	4 - 6 ft	180-80225-2	Not Excavated	9200	7	7.7	70	0.45 J	< 0.044 U	5500	15		7	39	24000	110	2200	500
Football Field	SSHS-B2213	SSHS-B2213-SUB-6-8	7/26/2018	855.06	6 - 8 ft	180-80225-2	Not Excavated	8500	0.44 J	5.1	85	0.35 J	< 0.041 U	1500	13		5.9	20	18000	34	1700	770
Football Field	SSHS-B2213	SSHS-B2213-SUB-8-10	7/26/2018	855.06	8 - 10 ft	180-80225-2	Not Excavated	11000	< 0.39 U	4.6	120	0.43 J	< 0.042 U	1200	76		7.3	41	18000	11	2200	600
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	12000	< 0.43 U	7.3	130	0.56	< 0.046 U	2000	15		10	16	21000	14	3100	600
Football Field	SSHS-B2214	SSHS-B2214-SUB-10-12	7/26/2018	855.14	10 - 12 ft	180-80227-3	Not Excavated	8000	< 0.37 U	6.2	50	0.31 J	< 0.04 U	1300	17		6.9	30	19000	10	2400	450
Football Field	SSHS-B2214	SSHS-B2214-SUB-4-6	7/26/2018	855.14	4 - 6 ft	180-80227-3	Not Excavated	4400	0.51 J	5.9	62	0.34 J	< 0.043 U	1600	9.2		4.3 J	28	24000	15	740	180

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2186	SSHS-B2186-SUB-8-10	7/24/2018	854.94	8 - 10 ft	180-80106-2	Not Excavated	0.012 J	19		< 0.56 U	< 0.12 U	74 J		< 0.23 U		9.3	57
Football Field	SSHS-B2187	SSHS-B2187-SUB-10-12	7/24/2018	856.10	10 - 12 ft	180-80106-2	Not Excavated	0.021 J	15		< 0.54 U	< 0.11 U	120 J		< 0.22 U		9.8	66
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	2 - 4 ft	180-80106-1	Not Excavated	0.18	24		< 0.59 U	< 0.12 U	140 J		< 0.24 U		14	120
Football Field	SSHS-B2187	SSHS-B2187-SUB-4-6	7/24/2018	856.10	4 - 6 ft	180-80106-1	Not Excavated	0.18	21		< 0.58 U	< 0.12 U	95 J		< 0.24 U		17	81
Football Field	SSHS-B2187	SSHS-B2187-SUB-6-8	7/24/2018	856.10	6 - 8 ft	180-80106-2	Not Excavated	0.038	14		< 0.57 U	< 0.12 U	110 J		< 0.23 U		12	46
Football Field	SSHS-B2187	SSHS-B2187-SUB-8-10	7/24/2018	856.10	8 - 10 ft	180-80106-2	Not Excavated	< 0.0079 U	13		0.68 J	< 0.12 U	190 J		< 0.24 U		14	39
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	< 0.0078 U	14		< 0.59 U	< 0.12 U	100 J		< 0.24 U		9.2	63
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated	0.12	72		< 0.6 U	< 0.12 U	87 J		< 0.24 U		13	230
Football Field	SSHS-B2188	SSHS-B2188-SUB-4-6	7/24/2018	855.99	4 - 6 ft	180-80106-2	Excavated	0.14	61		0.64 J	< 0.12 U	110 J		< 0.25 U		16	400
Football Field	SSHS-B2188	SSHS-B2188-SUB-10-12	7/24/2018	855.99	10 - 12 ft	180-80106-2	Not Excavated	0.1	17		0.97 J	< 0.12 U	160 J		< 0.47 U		10	82
Football Field	SSHS-B2188	SSHS-B2188-SUB-6-8	7/24/2018	855.99	6 - 8 ft	180-80106-2	Not Excavated	0.15	58		1.1 J	< 0.13 U	97 J		< 0.26 U		17	330
Football Field	SSHS-B2188	PS-FD-14	7/24/2018	855.99	8 - 10 ft	180-80106-2	Not Excavated	< 0.0076 U	16		< 0.55 U	< 0.11 U	100 J		< 0.22 U		9.5	73
Football Field	SSHS-B2188	SSHS-B2188-SUB-8-10	7/24/2018	855.99	8 - 10 ft	180-80106-2	Not Excavated	0.028 J	15		< 0.56 U	< 0.11 U	140 J		< 0.23 U		8.8	59
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	< 0.0078 U	16		0.75 J	< 0.11 U	230 J		< 0.22 U		9.5	55
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated	0.043	32		< 0.56 U	< 0.11 U	86 J		< 0.23 U		13	81
Football Field	SSHS-B2189	SSHS-B2189-SUB-4-6	7/24/2018	855.74	4 - 6 ft	180-80105-3	Excavated	0.12	50		0.97 J	< 0.12 U	240 J		< 0.24 U		23	170
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	0.021 J	26		< 0.55 U	< 0.11 U	150 J		< 0.23 U		14	94
Football Field	SSHS-B2189	PS-FD-12	7/24/2018	855.74	10 - 12 ft	180-80106-1	Not Excavated	0.019 J	17		< 0.55 U	< 0.11 U	130 J		< 0.23 U		12	62
Football Field	SSHS-B2189	SSHS-B2189-SUB-10-12	7/24/2018	855.74	10 - 12 ft	180-80105-3	Not Excavated	0.044	19		< 0.53 U	< 0.11 U	130 J		< 0.22 U		12	65
Football Field	SSHS-B2189	SSHS-B2189-SUB-6-8	7/24/2018	855.74	6 - 8 ft	180-80105-3	Not Excavated	0.15	110		1.1	< 0.12 U	250 J		< 0.23 U		19	230
Football Field	SSHS-B2189	SSHS-B2189-SUB-8-10	7/24/2018	855.74	8 - 10 ft	180-80105-3	Not Excavated	0.098	67		0.61 J	< 0.12 U	180 J		< 0.23 U		17	160
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated	0.029 J	18		< 0.58 U	< 0.12 U	46 J		< 0.24 U		12	60
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated	0.024 J	28		< 0.56 U	< 0.11 U	49 J		< 0.23 U		15	81
Football Field	SSHS-B2190	SSHS-B2190-SUB-4-6	7/27/2018	856.06	4 - 6 ft	180-80252-1	Excavated	0.028 J	57		0.58 J	< 0.12 U	160 J		< 0.23 U		16	120
Football Field	SSHS-B2190	SSHS-B2190-SUB-6-8	7/27/2018	856.06	6 - 8 ft	180-80252-1	Not Excavated	0.034 J	21		0.94 J	0.21 J	1200		< 0.47 U		20	190
Football Field	SSHS-B2190	SSHS-B2190-SUB-8-10	7/27/2018	856.06	8 - 10 ft	180-80252-2	Not Excavated	0.031 J	28		0.69 J	0.18 J	150 J		< 0.22 U		18	160
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated	0.05	37		< 0.6 U	< 0.12 U	80 J		< 0.24 U		13	94
Football Field	SSHS-B2191	SSHS-B2191-SUB-4-6	7/24/2018	856.18	4 - 6 ft	180-80105-3	Excavated	0.04	44		0.61 J	< 0.12 U	110 J		< 0.24 U		13	77
Football Field	SSHS-B2191	SSHS-B2191-SUB-6-8	7/24/2018	856.18	6 - 8 ft	180-80105-3	Not Excavated	0.03 J	32		< 0.56 U	< 0.12 U	180 J		< 0.23 U		11	100
Football Field	SSHS-B2191	SSHS-B2191-SUB-10-12	7/24/2018	856.18	10 - 12 ft	180-80105-3	Not Excavated	0.017 J	32		0.69 J	< 0.12 U	130 J		< 0.25 U		13	87
Football Field	SSHS-B2191	SSHS-B2191-SUB-8-10	7/24/2018	856.18	8 - 10 ft	180-80105-3	Not Excavated	0.025 J	40		0.8 J	< 0.12 U	210 J		< 0.24 U		11	160
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	< 0.0079 U	16		< 0.58 U	< 0.12 U	81 J		< 0.24 U		9.4	68
Football Field	SSHS-B2192	SSHS-B2192-SUB-10-12	7/26/2018	855.49	10 - 12 ft	180-80225-1	Not Excavated	< 0.0077 U	7.4		< 0.59 U	< 0.12 U	56 J		< 0.24 U		6.3	30
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	0.015 J	15		< 0.59 U	< 0.12 U	54 J		< 0.24 U		10	59
Football Field	SSHS-B2192	PS-FD-34	7/26/2018	855.49	4 - 6 ft	180-80225-3	Not Excavated	0.062	22		< 0.58 U	< 0.12 U	65 J		0.44 J		16	98
Football Field	SSHS-B2192	SSHS-B2192-SUB-4-6	7/26/2018	855.49	4 - 6 ft	180-80225-1	Not Excavated	0.064	16		< 0.58 U	< 0.12 U	54 J		< 0.23 U		26	62
Football Field	SSHS-B2192	SSHS-B2192-SUB-6-8	7/26/2018	855.49	6 - 8 ft	180-80225-1	Not Excavated	0.094	23		< 0.6 U	< 0.12 U	75 J		< 0.24 U		13	86
Football Field	SSHS-B2192	SSHS-B2192-SUB-8-10	7/26/2018	855.49	8 - 10 ft	180-80225-1	Not Excavated	0.013 J	15		< 0.57 U	< 0.12 U	50 J		< 0.23 U		12	94
Football Field	SSHS-B2193	PS-FD-33	7/26/2018	857.04	2 - 4 ft	180-80225-3	Excavated	0.86	31		< 0.58 U	< 0.12 U	130 J		0.25 J		15	160
Football Field	SSHS-B2193	SSHS-B2193-SUB-2-4	7/26/2018	857.04	2 - 4 ft	180-80225-1	Excavated	0.32	29		0.9 J	< 0.12 U	93 J		< 0.24 U		15	110
Football Field	SSHS-B2194	SSHS-B2194-SUB-2-4	7/25/2018	856.19	2 - 4 ft	180-80157-3	Excavated	0.1	150		< 0.62 U	< 0.13 U	85 J		< 0.25 U		14	250
Football Field	SSHS-B2194	SSHS-B2194-SUB-10-12	7/25/2018	856.19	10 - 12 ft	180-80157-3	Not Excavated	0.01 J	18		< 0.55 U	< 0.11 U	48 J		< 0.22 U		8.9	110
Football Field	SSHS-B2194	SSHS-B2194-SUB-4-6	7/25/2018	856.19	4 - 6 ft	180-80157-3	Not Excavated	0.038	61		0.63 J	< 0.12 U	100 J		< 0.25 U		15	130
Football Field	SSHS-B2194	PS-FD-30	7/25/2018	856.19	6 - 8 ft	180-80157-2	Not Excavated	0.021 J	31		< 0.61 U	< 0.12 U	68 J		< 0.25 U		11	87
Football Field	SSHS-B2194	SSHS-B2194-SUB-6-8	7/25/2018	856.19	6 - 8 ft	180-80157-3	Not Excavated	0.019 J	37		< 0.62 U	< 0.13 U	63 J		< 0.25 U		14	85
Football Field	SSHS-B2194	SSHS-B2194-SUB-8-10	7/25/2018	856.19	8 - 10 ft	180-80157-3	Not Excavated	0.0082 J	17		< 0.58 U	< 0.12 U	54 J		< 0.24 U		8.7	59
Football Field	SSHS-B2195	SSHS-B2195-SUB-2-4	7/26/2018	855.94	2 - 4 ft	180-80225-1	Excavated	0.12	45		1.7	0.21 J	180 J		< 0.3 U		20	190
Football Field	SSHS-B2195	SSHS-B2195-SUB-10-12	7/26/2018	855.94	10 - 12 ft	180-80225-1	Not Excavated	0.012 J	40		< 0.57 U	< 0.12 U	65 J		< 0.23 U		11	110
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.0086 U	21		< 0.59 U	< 0.12 U	60 J		< 0.24 U		9.9	60
Football Field	SSHS-B2195	SSHS-B2195-SUB-4-6	7/26/2018	855.94	4 - 6 ft	180-80225-1	Not Excavated	0.083	650		0.78 J	< 0.14 U	200 J		< 0.27 U		17	350
Football Field	SSHS-B2195	SSHS-B2195-SUB-6-8	7/26/2018	855.94	6 - 8 ft	180-80225-1	Not Excavated	0.033 J	170		< 0.63 U	< 0.13 U	87 J		< 0.26 U		11	170
Football Field	SSHS-B2195	PS-FD-31	7/26/2018	855.94	8 - 10 ft	180-80225-3	Not Excavated	0.01 J	69		< 0.58 U	< 0.12 U	78 J		< 0.24 U		11	85
Football Field	SSHS-B2195	SSHS-B2195-SUB-8-10	7/26/2018	855.94	8 - 10 ft	180-80225-1	Not Excavated	0.018 J	70		< 0.6 U	< 0.12 U	61 J		< 0.24 U		11	81
Football Field	SSHS-B2197	SSHS-B2197-SUB-10-12	7/24/2018	854.99	10 - 12 ft	180-80105-1	Not Excavated	0.013 J	12		< 0.58 U	< 0.12 U	56 J		< 0.24 U		7.9	49
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	< 0.0081 U	12		< 0.58 U	< 0.12 U	63 J		< 0.24 U		7.8	50
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated	0.037	22		< 0.58 U	< 0.12 U	77 J		< 0.23 U		15	61
Football Field	SSHS-B2197	SSHS-B2197-SUB-4-6	7/24/2018	854.99	4 - 6 ft	180-80105-1	Not Excavated	0.023 J	18		< 0.58 U	< 0.12 U	70 J		< 0.24 U		14	51
Football Field	SSHS-B2197	SSHS-B2197-SUB-6-8	7/24/2018	854.99	6 - 8 ft	180-80105-1	Not Excavated	0.022 J	18		< 0.6 U	< 0.12 U	60 J		< 0.25 U		13	50
Football Field	SSHS-B2197	SSHS-B2197-SUB-8-10	7/24/2018	854.99	8 - 10 ft	180-80105-1	Not Excavated	0.012 J	11		< 0.56 U	< 0.11 U	88 J		< 0.23 U		8.2	38
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	855.05	12 - 14 ft	180-80105-2	Not Excavated	0.017 J	16		< 0.59 U	< 0.12 U	50 J		< 0.24 U		9.9	58
Football Field	SSHS-B2198	SSHS-B2198-SUB-10-12	7/24/2018	855.05	10 - 12 ft	180-80105-2	Excavated	0.057	14		< 0.59 U	< 0.12 U	53 J		< 0.24 U		10	57
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated	0.079	33		< 0.62 U	< 0.13 U	120 J		< 0.25 U		18	67
Football Field	SSHS-B2198	SSHS-B2198-SUB-4-6	7/24/2018	855.05	4 - 6 ft	180-80105-2	Excavated	0.11	20		< 0.62 U	< 0.13 U	59 J		< 0.25 U		19	57
Football Field	SSHS-B2198	SSHS-B2198-SUB-6-8	7/24/2018	855.05	6 - 8 ft	180-80105-2	Excavated	0.034 J	17		0.64 J	< 0.12 U	55 J		< 0.24 U		15	65
Football Field	SSHS-B2198	SSHS-B2198-SUB-8-10	7/24/2018	855.05	8 - 10 ft	180-80105-2	Excavated	0.011 J	14		< 0.58 U	< 0.12 U	67 J		< 0.24 U		11	68
Football Field	SSHS-B2213	PS-FD-35	7/26/2018	855.06	10 - 12 ft	180-80225-3	Not Excavated	0.068	150	600	< 0.58 U	< 0.12 U	46 J		< 0.24 U		32	140
Football Field	SSHS-B2213	SSHS-B2213-SUB-10-12	7/26/2018	855.06	10 - 12 ft	180-80225-2	Not Excavated	0.11	180	560	< 0.56 U	< 0.11 U	37 J		< 0.23 U		12	190
Football Field	SSHS-B2213	SSHS-B2213-SUB-2-4	7/26/2018	855.06	2 - 4 ft	180-80225-2	Not Excavated	0.16	16	830	0.78 J	< 0.13 U	310 J		0.25 J		18	49
Football Field	SSHS-B2213	SSHS-B2213-SUB-4-6	7/26/2018	855.06	4 - 6 ft	180-80225-2	Not Excavated	0.063	16	930	< 0.62 U	< 0.13 U	69 J		0.54 J		20	110
Football Field	SSHS-B2213	SSHS-B2213-SUB-6-8	7/26/2018	855.06	6 - 8 ft	180-80225-2	Not Excavated	0.084	13	610	< 0.58 U	< 0.12 U	42 J		0.37 J		21	57
Football Field	SSHS-B2213	SSHS-B2213-SUB-8-10	7/26/2018	855.06	8 - 10 ft	180-80225-2	Not Excavated	0.028 J	920	760	< 0.59 U	< 0.12 U	41 J		0.39 J		18	1800
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	0.033 J	26	1100	< 0.65 U	< 0.13 U	33 J		0.29 J		16	64
Football Field	SSHS-B2214	SSHS-B2214-SUB-10-12	7/26/2018	855.14	10 - 12 ft	180-80227-3	Not Excavated	0.039	21		< 0.57 U	< 0.12 U	42 J		0.25 J		14	62
Football Field	SSHS-B2214	SSHS-B2214-SUB-4-6	7/26/2018	855.14	4 - 6 ft	180-80227-3	Not Excavated	0.067	7.8		1.1 J,^	< 0.12 U	110 J		0.3 J		14	27

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2214	SSHS-B2214-SUB-8-10	7/26/2018	855.14	8 - 10 ft	180-80227-3	Not Excavated	12000	< 0.41 U	7.8	44	0.49	< 0.043 U	1000	18		12	15	22000	12	2900	520
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	4900	< 0.36 U	4.9	62	0.19 J	< 0.038 U	9300	13		4.5 J	17	13000	6.9	4100	450
Football Field	SSHS-B2215	SSHS-B2215-SUB-10-12	7/26/2018	855.11	10 - 12 ft	180-80227-2	Not Excavated	4800	< 0.34 U	4.4	33	0.2 J	< 0.037 U	28000	8.6		4.9 J	18	13000	8.8	11000	470
Football Field	SSHS-B2215	SSHS-B2215-SUB-2-4	7/26/2018	855.11	2 - 4 ft	180-80227-2	Not Excavated	11000	0.56 J	5.4	130	0.59	< 0.048 U	2500	15		13	31	25000	20	2000	710
Football Field	SSHS-B2215	SSHS-B2215-SUB-4-6	7/26/2018	855.11	4 - 6 ft	180-80227-2	Not Excavated	13000	< 0.4 U	9.6	60	0.56	< 0.043 U	1400	16		11	30	25000	17	3100	320
Football Field	SSHS-B2215	SSHS-B2215-SUB-6-8	7/26/2018	855.11	6 - 8 ft	180-80227-2	Not Excavated	5800	< 0.38 U	5.5	42	0.29 J	< 0.04 U	1200	8.5		5.8	19	15000	9.4	1700	350
Football Field	SSHS-B2215	SSHS-B2215-SUB-8-10	7/26/2018	855.11	8 - 10 ft	180-80227-2	Not Excavated	5400	< 0.39 U	6.9	46	0.3 J	< 0.042 U	1800	10		6.1	25	17000	8	1900	610
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	6400	< 0.39 U	5.1	54	0.24 J	< 0.042 U	17000	9.8		6.4	25	16000	6.3	4800	670
Football Field	SSHS-B2216	SSHS-B2216-SUB-10-12	7/25/2018	855.16	10 - 12 ft	180-80154-2	Not Excavated	7100	< 0.38 U	5	61	0.26 J	0.15 J	20000	7.9		6.7	16	17000	6.3	8900	730
Football Field	SSHS-B2216	PS-FD-25	7/25/2018	855.16	2 - 4 ft	180-80157-2	Not Excavated	9700	< 0.38 U	7.5	64	0.45	0.09 J	8200	13		7.7	29	20000	28	2900	340
Football Field	SSHS-B2216	SSHS-B2216-SUB-2-4	7/25/2018	855.16	2 - 4 ft	180-80154-2	Not Excavated	10000	0.63 J	8.9	75	0.46	0.082 J	9300	14		8.4	35	22000	39	3100	490
Football Field	SSHS-B2216	SSHS-B2216-SUB-4-6	7/25/2018	855.16	4 - 6 ft	180-80154-2	Not Excavated	8900	1.2	8.1	74	0.44 J	0.12 J	3300	16		8.6	38	26000	56	2400	880
Football Field	SSHS-B2216	SSHS-B2216-SUB-6-8	7/25/2018	855.16	6 - 8 ft	180-80154-2	Not Excavated	9900	< 0.38 U	5.8	58	0.41 J	0.07 J	1200	13		8.1	21	20000	13	2600	410
Football Field	SSHS-B2216	SSHS-B2216-SUB-8-10	7/25/2018	855.16	8 - 10 ft	180-80154-2	Not Excavated	8600	< 0.37 U	5.4	73	0.37 J	0.091 J	4600	11		7.3	28	21000	10	3500	830
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	6200	< 0.36 U	4.3	50	0.21 J	0.059 J	32000	8.5		4.9 J	23	15000	21	16000	440
Football Field	SSHS-B2217	SSHS-B2217-SUB-2-4	7/27/2018	855.08	2 - 4 ft	180-80251-3	Excavated	9300	5.9	7.1	130	0.47	0.25 J	12000	14		6.7	110	20000	220	2000	270
Football Field	SSHS-B2217	SSHS-B2217-SUB-10-12	7/27/2018	855.08	10 - 12 ft	180-80251-3	Not Excavated	5900	< 0.38 U	4.2	45	0.23 J	0.069 J	19000	8.3		5 J	27	14000	8.5	6000	470
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	5200	0.38 J	6.6	41	0.21 J	0.073 J	5600	10		4.8 J	74	14000	24	2200	350
Football Field	SSHS-B2217	PS-FD-51	7/27/2018	855.08	4 - 6 ft	180-80252-2	Not Excavated	8700	16	7	96	0.4 J	< 0.043 U	17000	14		6.5	95	18000	160	2900	360
Football Field	SSHS-B2217	SSHS-B2217-SUB-4-6	7/27/2018	855.08	4 - 6 ft	180-80251-3	Not Excavated	8800	4.1	9.3	130	0.48	0.29 J	13000	18		9.2	110	25000	150	2600	460
Football Field	SSHS-B2217	SSHS-B2217-SUB-6-8	7/27/2018	855.08	6 - 8 ft	180-80251-3	Not Excavated	7400	4.3	7.1	70	0.37 J	0.1 J	3700	15		6.7	120	20000	67	2100	510
Football Field	SSHS-B2217	SSHS-B2217-SUB-8-10	7/27/2018	855.08	8 - 10 ft	180-80251-3	Not Excavated	6800	0.97 J	4.5	41	0.29 J	0.087 J	11000	11		6.4	84	16000	20	4200	420
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	4400	< 0.37 U	3.4	27	0.17 J	0.1 J	40000	92		3.3 J	270	11000	11	12000	570
Football Field	SSHS-B2221	SSHS-B2221-SUB-10-12	7/24/2018	855.38	10 - 12 ft	180-80106-1	Excavated	7100	< 0.39 U	7.3	62	0.29 J	0.14 J	3500	250		5.5 J	930	17000	28	2300	530
Football Field	SSHS-B2221	PS-FD-11	7/24/2018	855.38	2 - 4 ft	180-80106-1	Excavated	7800	< 0.41 U	7.1	110	0.42 J	0.31 J	38000	1100		5.2 J	2100	22000	150	4500	500
Football Field	SSHS-B2221	SSHS-B2221-SUB-2-4	7/24/2018	855.38	2 - 4 ft	180-80106-1	Excavated	7700	0.44 J	6.5	110	0.35 J	0.37 J	28000	800		5 J	3600	18000	260	3500	380
Football Field	SSHS-B2221	SSHS-B2221-SUB-4-6	7/24/2018	855.38	4 - 6 ft	180-80106-1	Excavated	8900	< 0.4 U	6.6	140	0.39 J	0.31 J	4200	1100		5.7 J	2100	17000	45	1400	1100
Football Field	SSHS-B2221	SSHS-B2221-SUB-6-8	7/24/2018	855.38	6 - 8 ft	180-80106-1	Excavated	8000	< 0.37 U	10	62	0.34 J	0.13 J	4700	500		5.1 J	1000	21000	35	2400	420
Football Field	SSHS-B2221	SSHS-B2221-SUB-8-10	7/24/2018	855.38	8 - 10 ft	180-80106-1	Excavated	6600	< 0.39 U	7.9	47	0.29 J	0.093 J	1200	180		4.3 J	1400	17000	21	1900	270
Football Field	SSHS-B2223	SSHS-B2223-SUB-2-4	7/26/2018	856.38	2 - 4 ft	180-80227-2	Excavated	8500	0.59 J	8.3	190	0.43 J	< 0.042 U	9000	20		6.9	56	19000	140	2900	360
Football Field	SSHS-B2223	SSHS-B2223-SUB-4-6	7/26/2018	856.38	4 - 6 ft	180-80227-2	Excavated	8400	13	5.2	260	0.35 J	< 0.043 U	26000	12		4.4 J	30	15000	420	2700	370
Football Field	SSHS-B2223	SSHS-B2223-SUB-6-8	7/26/2018	856.38	6 - 8 ft	180-80227-2	Excavated	8500	2.4	4.1	340	0.32 J	< 0.044 U	35000	13		4.4 J	22	15000	130	2700	620
Football Field	SSHS-B2223	PS-FD-42	7/26/2018	856.38	8 - 10 ft	180-80227-3	Excavated	8500	7.6	4.5	260	0.34 J	0.12 J	14000	13		5.2 J	26	17000	280	2800	680
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	9400	1.8	4	230	0.34 J	< 0.043 U	4600	12		5.8 J	29	18000	84	2700	580
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	8500	0.79 J	5.1	110	0.36 J	< 0.041 U	1800	12		6.3	23	18000	37	2300	520
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	6800	< 0.37 U	4.9	37	0.28 J	< 0.04 U	1200	8.8		5.6	28	15000	6.9	2300	360
Football Field	SSHS-B2224	SSHS-B2224-SUB-2-4	7/26/2018	854.93	2 - 4 ft	180-80227-2	Excavated	6000	< 0.37 U	6	69	0.25 J	< 0.04 U	8300	10		5.8	25	14000	28	1700	330
Football Field	SSHS-B2224	PS-FD-44	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	4500	< 0.35 U	4.3	21	0.18 J	0.064 J	30000	6		4.3 J	15	12000	5.4	3400	280
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	5200	< 0.36 U	4.5	24	0.21 J	< 0.039 U	31000	6.8		4.9 J	16	12000	5.9	4100	320
Football Field	SSHS-B2224	SSHS-B2224-SUB-4-6	7/26/2018	854.93	4 - 6 ft	180-80227-2	Not Excavated	5600	< 0.38 U	5.8	38	0.26 J	< 0.041 U	14000	8.2		6.1	20	15000	12	2400	340
Football Field	SSHS-B2224	SSHS-B2224-SUB-6-8	7/26/2018	854.93	6 - 8 ft	180-80227-2	Not Excavated	6700	< 0.44 U	6.7	32	0.3 J	< 0.048 U	5500	9.4		7.6	21	17000	9.7	2900	320
Football Field	SSHS-B2224	SSHS-B2224-SUB-8-10	7/26/2018	854.93	8 - 10 ft	180-80227-2	Not Excavated	5100	< 0.37 U	4.6	23	0.22 J	< 0.04 U	19000	7.2		5 J	18	13000	7.4	2700	290
Football Field	SSHS-B2225	SSHS-B2225-SUB-2-4	7/24/2018	857.03	2 - 4 ft	180-80105-3	Excavated	12000	< 0.42 U	6.7	260	0.54	0.42 J	35000	17		6.6	65	20000	100	4000	370
Football Field	SSHS-B2225	SSHS-B2225-SUB-4-6	7/24/2018	857.03	4 - 6 ft	180-80105-3	Excavated	8600	< 0.38 U	7.7	510	0.42 J	0.74	57000	31		9.2	390	30000	120	12000	450
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	7200	8.1	6.8	630	0.29 J	0.16 J	14000	27		5.2 J	96	17000	2000	2500	330
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	2500	19	4.9	870	0.11 J	0.33 J	43000	31		2.2 J	50	18000	2800	1300	350
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	5600	2.5	4.2	180	0.25 J	< 0.044 U	2800	11		3.6 J	20	11000	340	1200	420
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	6300	< 0.46 U	8.1	33	0.3 J	< 0.05 U	1400	8.8		6.5 J	22	17000	9.6	2200	370
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	6000	1.2	6.8	100	0.27 J	< 0.041 U	11000	11		5.9	25	15000	180	1900	530
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	8200	< 0.77 U	9.4	230	0.36 J	< 0.082 U	4500	340		9.6	53	69000	1100	2400	1200
Football Field	SSHS-B2227	SSHS-B2227-SUB-2-4	7/26/2018	856.55	2 - 4 ft	180-80227-1	Excavated	8900	0.41 J	13	150	0.55	< 0.043 U	18000	13		11	30	24000	53	3200	810
Football Field	SSHS-B2227	SSHS-B2227-SUB-4-6	7/26/2018	856.55	4 - 6 ft	180-80227-1	Excavated	6000	3.7	10	400	0.33 J	1.1	12000	16		5.7	49	18000	250	2300	430
Football Field	SSHS-B2227	SSHS-B2227-SUB-6-8	7/26/2018	856.55	6 - 8 ft	180-80227-1	Excavated	8500	< 0.38 U	6.8	210	0.35 J	0.44 J	4900	16		6.7	54	20000	180	2700	360
Football Field	SSHS-B2227	SSHS-B2227-SUB-10-12	7/26/2018	856.55	10 - 12 ft	180-80227-2	Not Excavated	8400	< 0.36 U	5.4	160	0.39 J	0.15 J	22000	12		6.8	32	17000	53	2700	720
Football Field	SSHS-B2227	SSHS-B2227-SUB-8-10	7/26/2018	856.55	8 - 10 ft	180-80227-2	Not Excavated	7800	< 0.41 U	6.4	110	0.35 J	0.089 J	6700	13		6.3	29	18000	59	2500	410
Football Field	SSHS-B2228	SSHS-B2228-SUB-4-6	7/27/2018	855.33	4 - 6 ft	180-80251-3	Excavated	6600	< 0.39 U	4.4	80	0.29 J	0.11 J	11000	16		5.1 J	20	15000	34	3700	350
Football Field	SSHS-B2228	SSHS-B2228-SUB-6-8	7/27/2018	855.33	6 - 8 ft	180-80252-1	Excavated	9400	< 0.43 U	6.9	34	0.41 J	0.078 J	800	11		7.2	25	19000	10	2300	210
Football Field	SSHS-B2228	SSHS-B2228-SUB-10-12	7/27/2018	855.33	10 - 12 ft	180-80252-1	Not Excavated	9400	< 0.39 U	5	82	0.4 J	0.088 J	1700	11		6.4	24	17000	28	2300	240
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	6600	< 0.39 U	5.7	73	0.3 J	0.12 J	12000	9.1		5.5 J	22	16000	27	3600	410
Football Field	SSHS-B2228	SSHS-B2228-SUB-8-10	7/27/2018	855.33	8 - 10 ft	180-80252-1	Not Excavated	8600	< 0.45 U	6.8	39	0.39 J	0.071 J	870	10		7.8	24	19000	11	2400	230
Football Field	SSHS-B2229	SSHS-B2229-SUB-2-4	7/27/2018	855.28	2 - 4 ft	180-80252-1	Excavated	7900	0.94 J	8.3	200	0.39 J	0.28 J	29000	14		6.4	57	32000	350	2000	520
Football Field	SSHS-B2229	SSHS-B2229-SUB-4-6	7/27/2018	855.28	4 - 6 ft	180-80252-1	Excavated	8200	66	6.5	180	0.37 J	0.24 J	32000	13		6.2	96	22000	1100	2400	430
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	6700	< 0.38 U	5.2	79	0.28 J	0.1 J	1900	12		6.1	26	18000	35	2500	300
Football Field	SSHS-B2230	SSHS-B2230-SUB-10-12	7/23/2018	856.03	10 - 12 ft	180-80091-4	Not Excavated	5700	< 0.39 U	5.4	38	0.25 J	< 0.042 U	930	7.8		5 J	22	14000	7.7	2000	250
Football Field	SSHS-B2230	SSHS-B2230-SUB-8-10	7/23/2018	856.03	8 - 10 ft	180-80091-4	Not Excavated	7500	< 0.39 U	5.5	160	0.3 J	0.1 J	4200	13		5 J	58	18000	290	2900	550
Football Field	SSHS-B2230	SSHS-B2230-SUB-2-4	7/23/2018	856.03	2 - 4 ft	180-80091-4	Excavated	5500	0.63 J	8.9	890	0.31 J	1.1	35000	22		5.2 J	98	24000	580	2200	450
Football Field	SSHS-B2230	SSHS-B2230-SUB-4-6	7/23/2018	856.03	4 - 6 ft	180-80091-4	Excavated	5900	< 0.42 U	9	380	0.34 J	0.47 J	19000	18		5.4 J	60	25000	260	3100	430
Football Field	SSHS-B2230	PS-FD-7	7/23/2018	856.03	6 - 8 ft	180-80091-4	Excavated	8000	< 0.39 U	6.7	190	0.37 J	0.19 J	11000	18		6	49	19000	160	3600	500
Football Field	SSHS-B2230	SSHS-B2230-SUB-6-8	7/23/2018	856.03	6 - 8 ft	180-80091-4	Excavated	7300	< 0.39 U	6.4	230	0.32 J	0.22 J	7700	15		5.9	42	22000	130	2700	500
Football Field	SSHS-B2231	SSHS-B2231-SUB-10-12	7/23/2018	856.14	10 - 12 ft	180-80091-2	Not Excavated	7200	< 0.39 U	8	52	0.32 J	0.087 J	1800	9.2		6.2	25	18000	13	2000	560
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	7000	< 0.37 U	5.4	100	0.31 J	0.21 J	3900	12		6.6	34	19000	35	2700	1300
Football Field	SSHS-B2231	SSHS-B2231-SUB-8-10	7/23/2018	856.14	8 - 10 ft	180-80091-2	Not Excavated	9700	< 0.39 U	6.9	190	0.41 J	0.17 J	17000	14		6.5	24	19000	100	2900	380
Football Field	SSHS-B2231	SSHS-B2231-SUB-2-4	7/23/2018	856.14	2 - 4 ft	180-80091-2	Excavated	7200	< 0.42 U	7.6	530	0.35 J	1	23000	15		5.7 J	82	21000	380	2700	400
Football Field	SSHS-B2231	SSHS-B2231-SUB-4-6	7/23/2018	856.14	4 - 6 ft	180-80091-2	Excavated	5200	3.8	24	640	0.33 J	0.76	61000	29		7.4	58	57000	380	1500	760

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2214	SSHS-B2214-SUB-8-10	7/26/2018	855.14	8 - 10 ft	180-80227-3	Not Excavated	0.035 J	21		< 0.62 U	< 0.13 U	52 J		0.45 J		19	52
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	0.012 J	11		< 0.54 U	< 0.11 U	49 J		0.3 J		8.5	47
Football Field	SSHS-B2215	SSHS-B2215-SUB-10-12	7/26/2018	855.11	10 - 12 ft	180-80227-2	Not Excavated	< 0.008 U	11		< 0.52 U	< 0.11 U	66 J		< 0.21 U		8.8	40
Football Field	SSHS-B2215	SSHS-B2215-SUB-2-4	7/26/2018	855.11	2 - 4 ft	180-80227-2	Not Excavated	0.032 J	18		0.8 J,^	< 0.14 U	56 J		0.57 J		22	56
Football Field	SSHS-B2215	SSHS-B2215-SUB-4-6	7/26/2018	855.11	4 - 6 ft	180-80227-2	Not Excavated	0.015 J	19		< 0.61 U	< 0.12 U	53 J		0.47 J		21	58
Football Field	SSHS-B2215	SSHS-B2215-SUB-6-8	7/26/2018	855.11	6 - 8 ft	180-80227-2	Not Excavated	0.0098 J	13		< 0.57 U	< 0.12 U	33 J		0.3 J		11	44
Football Field	SSHS-B2215	SSHS-B2215-SUB-8-10	7/26/2018	855.11	8 - 10 ft	180-80227-2	Not Excavated	0.0089 J	12		< 0.6 U	< 0.12 U	42 J		0.4 J		16	150
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	< 0.0083 U	15		< 0.59 U	< 0.12 U	58 J		0.31 J		11	59
Football Field	SSHS-B2216	SSHS-B2216-SUB-10-12	7/25/2018	855.16	10 - 12 ft	180-80154-2	Not Excavated	< 0.0079 U	16		< 0.57 U	< 0.12 U	66 J		< 0.23 U		10	57
Football Field	SSHS-B2216	PS-FD-25	7/25/2018	855.16	2 - 4 ft	180-80157-2	Not Excavated	0.073	18		< 0.58 U	< 0.12 U	65 J		< 0.24 U		16	63
Football Field	SSHS-B2216	SSHS-B2216-SUB-2-4	7/25/2018	855.16	2 - 4 ft	180-80154-2	Not Excavated	0.065	19		< 0.57 U	< 0.12 U	79 J		< 0.23 U		20	83
Football Field	SSHS-B2216	SSHS-B2216-SUB-4-6	7/25/2018	855.16	4 - 6 ft	180-80154-2	Not Excavated	0.068	20		0.6 J	< 0.12 U	62 J		< 0.24 U		22	140
Football Field	SSHS-B2216	SSHS-B2216-SUB-6-8	7/25/2018	855.16	6 - 8 ft	180-80154-2	Not Excavated	< 0.0086 U	19		< 0.57 U	< 0.12 U	47 J		< 0.23 U		15	66
Football Field	SSHS-B2216	SSHS-B2216-SUB-8-10	7/25/2018	855.16	8 - 10 ft	180-80154-2	Not Excavated	0.022 J	19		< 0.56 U	< 0.11 U	47 J		< 0.23 U		13	75
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	0.0081 J	12		< 0.54 U	< 0.11 U	91 J		< 0.22 U		9.1	58
Football Field	SSHS-B2217	SSHS-B2217-SUB-2-4	7/27/2018	855.08	2 - 4 ft	180-80251-3	Excavated	0.052	53		1.1 J	< 0.12 U	150 J		< 0.25 U		17	150
Football Field	SSHS-B2217	SSHS-B2217-SUB-10-12	7/27/2018	855.08	10 - 12 ft	180-80251-3	Not Excavated	< 0.0077 U	53		< 0.58 U	< 0.12 U	65 J		< 0.24 U		8.9	120
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	< 0.0082 U	120		< 0.58 U	< 0.12 U	42 J		< 0.23 U		8.2	120
Football Field	SSHS-B2217	PS-FD-51	7/27/2018	855.08	4 - 6 ft	180-80252-2	Not Excavated	0.03 J	67		< 0.62 U	< 0.13 U	200 J		< 0.25 U		15	120
Football Field	SSHS-B2217	SSHS-B2217-SUB-4-6	7/27/2018	855.08	4 - 6 ft	180-80251-3	Not Excavated	0.048	100		1.1 J	< 0.13 U	190 J		< 0.25 U		16	160
Football Field	SSHS-B2217	SSHS-B2217-SUB-6-8	7/27/2018	855.08	6 - 8 ft	180-80251-3	Not Excavated	< 0.0091 U	110		< 0.59 U	< 0.12 U	56 J		< 0.24 U		13	110
Football Field	SSHS-B2217	SSHS-B2217-SUB-8-10	7/27/2018	855.08	8 - 10 ft	180-80251-3	Not Excavated	< 0.0083 U	160		< 0.57 U	< 0.12 U	51 J		< 0.23 U		10	230
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	< 0.0074 U	15	500 J	< 0.56 U	< 0.11 U	99 J		< 0.23 U		7.1	56
Football Field	SSHS-B2221	SSHS-B2221-SUB-10-12	7/24/2018	855.38	10 - 12 ft	180-80106-1	Excavated	< 0.0085 U	21	660	< 0.58 U	< 0.12 U	110 J		< 0.24 U		11	77
Football Field	SSHS-B2221	PS-FD-11	7/24/2018	855.38	2 - 4 ft	180-80106-1	Excavated	0.1	38	720	0.79 J	< 0.13 U	200 J		< 0.25 U		13	170
Football Field	SSHS-B2221	SSHS-B2221-SUB-2-4	7/24/2018	855.38	2 - 4 ft	180-80106-1	Excavated	0.062	43	620	0.88 J	< 0.12 U	180 J		< 0.24 U		12	190
Football Field	SSHS-B2221	SSHS-B2221-SUB-4-6	7/24/2018	855.38	4 - 6 ft	180-80106-1	Excavated	0.031 J	22	600	1.1 J	< 0.12 U	170 J		< 0.25 U		13	170
Football Field	SSHS-B2221	SSHS-B2221-SUB-6-8	7/24/2018	855.38	6 - 8 ft	180-80106-1	Excavated	0.013 J	20	600	< 0.55 U	< 0.11 U	110 J		< 0.22 U		12	100
Football Field	SSHS-B2221	SSHS-B2221-SUB-8-10	7/24/2018	855.38	8 - 10 ft	180-80106-1	Excavated	< 0.0078 U	15	550 J	< 0.59 U	< 0.12 U	86 J		< 0.24 U		10	78
Football Field	SSHS-B2223	SSHS-B2223-SUB-2-4	7/26/2018	856.38	2 - 4 ft	180-80227-2	Excavated	0.13	72	830	< 0.59 U,^	< 0.12 U	120 J		0.31 J		17	96
Football Field	SSHS-B2223	SSHS-B2223-SUB-4-6	7/26/2018	856.38	4 - 6 ft	180-80227-2	Excavated	0.038	17	830	< 0.61 U,^	< 0.12 U	240 J		< 0.25 U		13	83
Football Field	SSHS-B2223	SSHS-B2223-SUB-6-8	7/26/2018	856.38	6 - 8 ft	180-80227-2	Excavated	0.037 J	20	730	< 0.63 U,^	< 0.13 U	270 J		0.46 J		13	66
Football Field	SSHS-B2223	PS-FD-42	7/26/2018	856.38	8 - 10 ft	180-80227-3	Excavated	0.059	23	650	< 0.61 U	< 0.12 U	190 J		< 0.25 U		12	80
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	0.042	22	720	< 0.61 U,^	< 0.12 U	230 J		0.37 J		14	68
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	0.017 J	19	840	< 0.58 U,^	< 0.12 U	290 J		0.27 J		14	68
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	0.0089 J	13	770	< 0.56 U,^	< 0.11 U	250 J		< 0.23 U		11	53
Football Field	SSHS-B2224	SSHS-B2224-SUB-2-4	7/26/2018	854.93	2 - 4 ft	180-80227-2	Excavated	0.029 J	24	590	< 0.56 U,^	< 0.11 U	63 J		< 0.23 U		12	55
Football Field	SSHS-B2224	PS-FD-44	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.0077 U	11	430 J	< 0.53 U	< 0.11 U	54 J		< 0.22 U		7.6	36
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.008 U	12	660	< 0.55 U,^	< 0.11 U	62 J		< 0.22 U		8.6	40
Football Field	SSHS-B2224	SSHS-B2224-SUB-4-6	7/26/2018	854.93	4 - 6 ft	180-80227-2	Not Excavated	0.011 J	16	740	< 0.58 U,^	< 0.12 U	50 J		0.3 J		11	51
Football Field	SSHS-B2224	SSHS-B2224-SUB-6-8	7/26/2018	854.93	6 - 8 ft	180-80227-2	Not Excavated	< 0.0097 U	17	910	< 0.67 U,^	< 0.14 U	50 J		0.4 J		13	61
Football Field	SSHS-B2224	SSHS-B2224-SUB-8-10	7/26/2018	854.93	8 - 10 ft	180-80227-2	Not Excavated	< 0.0084 U	12	670	< 0.56 U,^	< 0.12 U	65 J		0.26 J		9.8	44
Football Field	SSHS-B2225	SSHS-B2225-SUB-2-4	7/24/2018	857.03	2 - 4 ft	180-80105-3	Excavated	0.079	37	730	0.86 J	< 0.13 U	180 J		< 0.26 U		15	120
Football Field	SSHS-B2225	SSHS-B2225-SUB-4-6	7/24/2018	857.03	4 - 6 ft	180-80105-3	Excavated	0.2	160	660	1.1	0.39 J	200 J		< 0.23 U		18	250
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	0.071	52	880	< 0.59 U	0.12 J	310 J		0.26 J		12	150
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	0.026 J	31	490 J,B	< 0.57 U	0.24 J	310 J		< 0.23 U		6.2	130
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	0.039 J	12	770	< 0.62 U	< 0.13 U	100 J		< 0.25 U		9.8	60
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	< 0.01 U	15	1400	< 0.7 U	< 0.14 U	61 J		0.36 J		12	56
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	0.026 J	17	910	< 0.59 U	< 0.12 U	63 J		< 0.24 U		10	54
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	0.022 J	57	850	< 0.58 U	0.19 J	93 J		< 0.47 U		16	83
Football Field	SSHS-B2227	SSHS-B2227-SUB-2-4	7/26/2018	856.55	2 - 4 ft	180-80227-1	Excavated	0.035 J	140	860	< 0.61 U,^	< 0.12 U	140 J		0.43 J		16	62
Football Field	SSHS-B2227	SSHS-B2227-SUB-4-6	7/26/2018	856.55	4 - 6 ft	180-80227-1	Excavated	0.09	68	670	< 0.55 U,^	< 0.11 U	180 J		< 0.22 U		13	880
Football Field	SSHS-B2227	SSHS-B2227-SUB-6-8	7/26/2018	856.55	6 - 8 ft	180-80227-1	Excavated	0.037 J	35	730	< 0.57 U,^	< 0.12 U	190 J		0.43 J		15	450
Football Field	SSHS-B2227	SSHS-B2227-SUB-10-12	7/26/2018	856.55	10 - 12 ft	180-80227-2	Not Excavated	0.022 J	25	650	< 0.55 U,^	< 0.11 U	320 J		0.39 J		12	120
Football Field	SSHS-B2227	SSHS-B2227-SUB-8-10	7/26/2018	856.55	8 - 10 ft	180-80227-2	Not Excavated	0.024 J	28	700	< 0.63 U,^	< 0.13 U	240 J		0.29 J		14	210
Football Field	SSHS-B2228	SSHS-B2228-SUB-4-6	7/27/2018	855.33	4 - 6 ft	180-80251-3	Excavated	0.013 J	18	640	< 0.59 U	< 0.12 U	85 J		< 0.24 U		11	67
Football Field	SSHS-B2228	SSHS-B2228-SUB-6-8	7/27/2018	855.33	6 - 8 ft	180-80252-1	Excavated	0.031 J	18	700	< 0.65 U	< 0.13 U	46 J		< 0.26 U		15	56
Football Field	SSHS-B2228	SSHS-B2228-SUB-10-12	7/27/2018	855.33	10 - 12 ft	180-80252-1	Not Excavated	0.028 J	19	610	< 0.59 U	< 0.12 U	60 J		< 0.24 U		14	62
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	0.014 J	15	560 J	< 0.59 U	< 0.12 U	61 J		< 0.24 U		12	64
Football Field	SSHS-B2228	SSHS-B2228-SUB-8-10	7/27/2018	855.33	8 - 10 ft	180-80252-1	Not Excavated	0.024 J	19	690	< 0.68 U	< 0.14 U	35 J		< 0.27 U		13	57
Football Field	SSHS-B2229	SSHS-B2229-SUB-2-4	7/27/2018	855.28	2 - 4 ft	180-80252-1	Excavated	0.064	30	840	0.64 J	< 0.12 U	260 J		< 0.24 U		16	110
Football Field	SSHS-B2229	SSHS-B2229-SUB-4-6	7/27/2018	855.28	4 - 6 ft	180-80252-1	Excavated	0.032 J	28	630	< 0.59 U	< 0.12 U	130 J		< 0.24 U		15	110
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	< 0.0082 U	17	630	0.73 J	< 0.12 U	67 J		< 0.23 U		12	73
Football Field	SSHS-B2230	SSHS-B2230-SUB-10-12	7/23/2018	856.03	10 - 12 ft	180-80091-4	Not Excavated	0.0084 J	13	690	< 0.6 U	< 0.12 U	48 J		< 0.24 U		9.5	53
Football Field	SSHS-B2230	SSHS-B2230-SUB-8-10	7/23/2018	856.03	8 - 10 ft	180-80091-4	Not Excavated	0.025 J	16	560 J	0.6 J	< 0.12 U	82 J		< 0.24 U		13	73
Football Field	SSHS-B2230	SSHS-B2230-SUB-2-4	7/23/2018	856.03	2 - 4 ft	180-80091-4	Excavated	0.18	68	550 J	1.1 J	0.33 J	190 J		< 0.25 U		15	370
Football Field	SSHS-B2230	SSHS-B2230-SUB-4-6	7/23/2018	856.03	4 - 6 ft	180-80091-4	Excavated	0.076	34	630	0.89 J	0.14 J	190 J		< 0.26 U		14	190
Football Field	SSHS-B2230	PS-FD-7	7/23/2018	856.03	6 - 8 ft	180-80091-4	Excavated	0.03 J	23	680	< 0.58 U	< 0.12 U	120 J		< 0.24 U		16	110
Football Field	SSHS-B2230	SSHS-B2230-SUB-6-8	7/23/2018	856.03	6 - 8 ft	180-80091-4	Excavated	0.034 J	21	530 J	0.59 J	0.17 J	120 J		< 0.24 U		14	110
Football Field	SSHS-B2231	SSHS-B2231-SUB-10-12	7/23/2018	856.14	10 - 12 ft	180-80091-2	Not Excavated	< 0.0079 U	16	710	< 0.58 U	< 0.12 U	61 J		< 0.24 U		13	65
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	0.012 J	21	640	< 0.56 U	< 0.12 U	74 J		< 0.23 U		13	92
Football Field	SSHS-B2231	SSHS-B2231-SUB-8-10	7/23/2018	856.14	8 - 10 ft	180-80091-2	Not Excavated	0.05	22	550 J	< 0.6 U	< 0.12 U	440 J		< 0.24 U		16	88
Football Field	SSHS-B2231	SSHS-B2231-SUB-2-4	7/23/2018	856.14	2 - 4 ft	180-80091-2	Excavated	0.1	41	570 J	< 0.64 U	0.17 J	140 J		< 0.26 U		15	240
Football Field	SSHS-B2231	SSHS-B2231-SUB-4-6	7/23/2018	856.14	4 - 6 ft	180-80091-2	Excavated	0.059	83	610 J	1.6	< 0.13 U	730		< 0.26 U		27	260

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2231	SSHS-B2231-SUB-6-8	7/23/2018	856.14	6 - 8 ft	180-80091-2	Excavated	10000	0.88 J	8.4	280	0.46 J	0.27 J	37000	18		5.7 J	36	23000	150	3100	380
Football Field	SSHS-B2232	PS-FD-9	7/24/2018	856.82	10 - 12 ft	180-80105-2	Not Excavated	6200	< 0.38 U	5.1	36	0.29 J	0.074 J	1300	8.6		5.1 J	21	16000	15	2000	360
Football Field	SSHS-B2232	SSHS-B2232-SUB-10-12	7/24/2018	856.82	10 - 12 ft	180-80105-1	Not Excavated	6900	< 0.4 U	6.6	43	0.29 J	0.091 J	1100	8.8		6.5	18	17000	52	2200	440
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	6700	< 0.39 U	7	95	0.31 J	0.11 J	3200	10		6.2	40	18000	36	2500	310
Football Field	SSHS-B2232	SSHS-B2232-SUB-6-8	7/24/2018	856.82	6 - 8 ft	180-80105-1	Not Excavated	7300	< 0.38 U	3.6	34	0.28 J	0.051 J	1500	8.9		4.4 J	21	18000	11	2300	250
Football Field	SSHS-B2232	SSHS-B2232-SUB-8-10	7/24/2018	856.82	8 - 10 ft	180-80105-1	Not Excavated	5400	< 0.39 U	6.1	42	0.29 J	0.1 J	360 J	5.6		9.5	16	13000	10	1400	820
Football Field	SSHS-B2232	SSHS-B2232-SUB-2-4	7/24/2018	856.82	2 - 4 ft	180-80105-1	Excavated	8100	< 0.41 U	6.3	79	0.37 J	0.17 J	34000	16		7.2	91	19000	34	4400	590
Football Field	SSHS-B2232	SSHS-B2232-SUB-4-6	7/24/2018	856.82	4 - 6 ft	180-80105-1	Excavated	7100	0.92 J	8.8	110	0.5 J	0.14 J	7100	12		8.5	110	38000	210	1800	370
Football Field	SSHS-B2233	SSHS-B2233-SUB-10-12	7/24/2018	854.83	10 - 12 ft	180-80105-1	Not Excavated	5500	< 0.36 U	4.2	30	0.24 J	0.044 J	2300	8.3		4.8 J	15	14000	180	2100	320
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	5400	< 0.39 U	3.4	40	0.21 J	0.057 J	14000	7.4		5.2 J	17	14000	110	2200	340
Football Field	SSHS-B2233	SSHS-B2233-SUB-6-8	7/24/2018	854.83	6 - 8 ft	180-80105-1	Not Excavated	7800	< 0.42 U	5.9	68	0.35 J	0.078 J	10000	11		6.7	24	18000	1200	2300	390
Football Field	SSHS-B2233	SSHS-B2233-SUB-8-10	7/24/2018	854.83	8 - 10 ft	180-80105-1	Not Excavated	7700	< 0.41 U	6	53	0.34 J	0.1 J	3100	11		6.6	30	19000	240	2700	610
Football Field	SSHS-B2233	PS-FD-8	7/24/2018	854.83	2 - 4 ft	180-80105-2	Excavated	9200	< 40 U	5.8	120	0.41 J	0.15 J	10000	11		6.8	44	19000	39000	2300	320
Football Field	SSHS-B2233	SSHS-B2233-SUB-2-4	7/24/2018	854.83	2 - 4 ft	180-80105-1	Excavated	9100	< 3.8 U	5.6	160	0.45	0.15 J	73000	12		6.9	33	21000	7300	2900	360
Football Field	SSHS-B2233	SSHS-B2233-SUB-4-6	7/24/2018	854.83	4 - 6 ft	180-80105-1	Excavated	9200	< 0.81 U	6.1	92	0.42 J	0.088 J	21000	13		8.5	28	18000	1800	2900	630
Football Field	SSHS-B2234	SSHS-B2234-SUB-10-12	7/23/2018	855.41	10 - 12 ft	180-80091-2	Not Excavated	6300	2.7	6.5	75	0.31 J	0.1 J	5700	10		6.1	20	15000	390	2100	260
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	4700	< 0.38 U	5	28	0.21 J	0.095 J	1400	7.5		4.5 J	16	12000	25	1800	170
Football Field	SSHS-B2234	SSHS-B2234-SUB-8-10	7/23/2018	855.41	8 - 10 ft	180-80091-1	Not Excavated	6200	0.57 J	6.4	67	0.34 J	0.058 J	3300	7.6		4.2 J	16	12000	39	1500	290
Football Field	SSHS-B2234	SSHS-B2234-SUB-2-4	7/23/2018	855.41	2 - 4 ft	180-80091-1	Excavated	8500	46	8	250	0.39 J	0.4 J	23000	12		5.6 J	33	18000	3400	2600	440
Football Field	SSHS-B2234	PS-FD-5	7/23/2018	855.41	4 - 6 ft	180-80091-1	Excavated	6600	14	8.6	220	0.43 J	0.12 J	21000	11		5 J	26	15000	760	3200	290
Football Field	SSHS-B2234	SSHS-B2234-SUB-4-6	7/23/2018	855.41	4 - 6 ft	180-80091-1	Excavated	7100	23	8.2	200	0.43 J	0.14 J	15000	11		4.5 J	23	12000	1800	2600	230
Football Field	SSHS-B2234	SSHS-B2234-SUB-6-8	7/23/2018	855.41	6 - 8 ft	180-80091-1	Excavated	12000	0.95 J	7.4	88	0.58	0.048 J	6600	15		8	18	19000	25	2600	360
Football Field	SSHS-B2235	SSHS-B2235-SUB-10-12	7/23/2018	855.30	10 - 12 ft	180-80091-1	Not Excavated	7000	< 0.38 U	5.2	53	0.28 J	0.089 J	1900	9.3		5.4 J	21	16000	9.2	2200	680
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	4800	< 0.37 U	3.1	35	0.18 J	0.063 J	3300	6.2		4 J	13	11000	14	1900	410
Football Field	SSHS-B2235	PS-FD-3	7/23/2018	855.30	8 - 10 ft	180-80091-1	Not Excavated	7200	< 0.39 U	6.4	40	0.3 J	0.042 J	1400	8.6		6	17	15000	11	1800	460
Football Field	SSHS-B2235	SSHS-B2235-SUB-8-10	7/23/2018	855.30	8 - 10 ft	180-80091-1	Not Excavated	11000	< 0.41 U	7.3	51	0.4 J	0.047 J	2900	15		8.2	18	22000	14	3000	370
Football Field	SSHS-B2235	SSHS-B2235-SUB-2-4	7/23/2018	855.30	2 - 4 ft	180-80091-1	Excavated	8900	< 0.39 U	8.7	73	0.53	0.052 J	18000	15		7.8	24	24000	29	3700	390
Football Field	SSHS-B2235	SSHS-B2235-SUB-4-6	7/23/2018	855.30	4 - 6 ft	180-80091-1	Excavated	7600	0.69 J	5.3	48	0.32 J	0.061 J	17000	9.4		6	23	17000	100	3800	370
Football Field	SSHS-B2235	SSHS-B2235-SUB-6-8	7/23/2018	855.30	6 - 8 ft	180-80091-1	Excavated	10000	< 0.41 U	4.6	100	0.41 J	< 0.044 U	1700	12		6.1	12	19000	11	2500	500
Football Field	SSHS-B2236	SSHS-B2236-SUB-2-4	7/27/2018	855.25	2 - 4 ft	180-80251-3	Excavated	6700	< 0.36 U	7.1	110	0.34 J	0.16 J	14000	13		5.4	41	18000	180	2800	400
Football Field	SSHS-B2236	PS-FD-52	7/27/2018	855.25	4 - 6 ft	180-80252-2	Excavated	8100	< 0.37 U	6	190	0.38 J	< 0.039 U	14000	17		7	44	19000	230	4500	420
Football Field	SSHS-B2236	SSHS-B2236-SUB-4-6	7/27/2018	855.25	4 - 6 ft	180-80251-3	Excavated	8000	< 0.37 U	7.4	150	0.35 J	0.21 J	15000	19		6.4	38	20000	210	4500	510
Football Field	SSHS-B2237	SSHS-B2237-SUB-2-4	7/27/2018	855.30	2 - 4 ft	180-80252-1	Excavated	7000	3.4	7.1	11000	0.37 J	0.47 J	10000	26		4.2 J	660	42000	1600	2000	2200
Football Field	SSHS-B2238	SSHS-B2238-SUB-10-12	7/23/2018	855.07	10 - 12 ft	180-80091-1	Excavated	6400	< 1.9 U	5.4	460	0.27 J	1.1	17000	12		5.2 J	81	30000	2100	2800	380
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	6200	< 0.38 U	4.3	120	0.24 J	0.31 J	25000	10		5.1 J	32	15000	33	5400	460
Football Field	SSHS-B2238	SSHS-B2238-SUB-2-4	7/23/2018	855.07	2 - 4 ft	180-80091-1	Excavated	7600	< 0.37 U,F2,F1	6.3	110	0.32 J,F2,F1	0.22 J	28000	13		6.3	55	21000	140	5000	570
Football Field	SSHS-B2238	SSHS-B2238-SUB-4-6	7/23/2018	855.07	4 - 6 ft	180-80091-1	Excavated	8000	< 0.37 U	7.9	220	0.35 J	0.99	17000	12		7.2	78	23000	75	3700	550
Football Field	SSHS-B2238	SSHS-B2238-SUB-6-8	7/23/2018	855.07	6 - 8 ft	180-80091-1	Excavated	6900	< 0.38 U	6.7	320	0.3 J	1.3	44000	17		6.5	130	19000	100	5800	430
Football Field	SSHS-B2238	SSHS-B2238-SUB-8-10	7/23/2018	855.07	8 - 10 ft	180-80091-1	Excavated	6500	< 0.39 U	7.2	250	0.32 J	0.79	24000	13		6.3	81	21000	190	4600	380
Football Field	SSHS-B2239	SSHS-B2239-SUB-2-4	7/23/2018	855.51	2 - 4 ft	180-80091-3	Excavated	6000	0.77 J	8.9	490	0.29 J	0.32 J	42000	19		5.6	130	21000	180	4000	360
Football Field	SSHS-B2239	PS-FD-4	7/23/2018	855.51	10 - 12 ft	180-80091-4	Excavated	6400	< 0.38 U	4.3	110	0.27 J	0.12 J	66000	10		5.6	35	18000	44	4500	600
Football Field	SSHS-B2239	SSHS-B2239-SUB-10-12	7/23/2018	855.51	10 - 12 ft	180-80091-3	Excavated	8600	< 0.37 U	5.7	140	0.3 J	0.13 J	25000	13		7.3	44	22000	33	5600	560
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	855.51	12 - 14 ft	180-80091-3	Excavated	7100	< 0.38 U	5.3	110	0.26 J	0.09 J	41000	11		5.8	38	18000	29	7600	420
Football Field	SSHS-B2239	SSHS-B2239-SUB-4-6	7/23/2018	855.51	4 - 6 ft	180-80091-3	Excavated	7100	1.9	9.9	950	0.33 J	0.35 J	73000	29		7.7	220	26000	320	3900	480
Football Field	SSHS-B2239	SSHS-B2239-SUB-6-8	7/23/2018	855.51	6 - 8 ft	180-80091-3	Excavated	7300	0.73 J	6.7	620	0.32 J	0.21 J	22000	18		6	130	22000	150	4100	390
Football Field	SSHS-B2239	SSHS-B2239-SUB-8-10	7/23/2018	855.51	8 - 10 ft	180-80091-3	Excavated	8000	< 0.39 U	5.9	170	0.31 J	0.11 J	18000	25		7.8	53	21000	38	4300	650
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	6100	< 0.37 U	5.8	42	0.3 J	0.08 J	1900	7.8		5.5	20	16000	10	1800	530
Football Field	SSHS-B2240	SSHS-B2240-SUB-10-12	7/23/2018	855.85	10 - 12 ft	180-80091-2	Not Excavated	5700	< 0.36 U	4.5	39	0.24 J	0.083 J	47000	9.3		5.2 J	23	14000	9.7	9600	310
Football Field	SSHS-B2240	SSHS-B2240-SUB-2-4	7/23/2018	855.85	2 - 4 ft	180-80091-2	Excavated	4300	< 0.37 U	5.3	65	0.3 J	0.16 J	150000	7.6		5.5	29	12000	55	4700	360
Football Field	SSHS-B2240	SSHS-B2240-SUB-4-6	7/23/2018	855.85	4 - 6 ft	180-80091-2	Excavated	8600	< 0.39 U,F1	6	73	0.4 J	0.045 J	8700	11		7	64	18000	37	2600	440
Football Field	SSHS-B2240	SSHS-B2240-SUB-6-8	7/23/2018	855.85	6 - 8 ft	180-80091-2	Excavated	6100	< 0.39 U	6.3	130	0.35 J	0.16 J	34000	12		6.8	84	18000	96	1900	440
Football Field	SSHS-B2240	SSHS-B2240-SUB-8-10	7/23/2018	855.85	8 - 10 ft	180-80091-2	Excavated	5900	< 0.36 U	5	54	0.28 J	0.057 J	6800	9.1		5.5	39	14000	23	2200	370
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	855.46	12 - 14 ft	180-80091-4	Not Excavated	7300	< 0.38 U	5.1	45	0.31 J	0.058 J	7100	12		5.9	21	17000	10	3400	380
Football Field	SSHS-B2241	SSHS-B2241-SUB-10-12	7/23/2018	855.46	10 - 12 ft	180-80091-4	Excavated	6100	< 0.37 U	5.5	52	0.26 J	0.089 J	18000	9.9		5.5	24	15000	13	3000	450
Football Field	SSHS-B2241	PS-FD-6	7/23/2018	855.46	2 - 4 ft	180-80091-4	Excavated	9000	< 0.39 U	5.8	83	0.36 J	0.092 J	24000	13		6.9	40	18000	87	4900	380
Football Field	SSHS-B2241	SSHS-B2241-SUB-2-4	7/23/2018	855.46	2 - 4 ft	180-80091-4	Excavated	8600	< 0.38 U	7	110	0.4 J	0.14 J	17000	15		6.5	62	21000	74	4800	420
Football Field	SSHS-B2241	SSHS-B2241-SUB-4-6	7/23/2018	855.46	4 - 6 ft	180-80091-4	Excavated	9200	< 0.4 U	5.9	71	0.39 J	0.078 J	48000	16		6.6	27	18000	35	5400	640
Football Field	SSHS-B2241	SSHS-B2241-SUB-6-8	7/23/2018	855.46	6 - 8 ft	180-80091-4	Excavated	11000	< 0.41 U	5.7	50	0.44 J	< 0.044 U	2500	13		7.5	14	20000	11	2900	280
Football Field	SSHS-B2241	SSHS-B2241-SUB-8-10	7/23/2018	855.46	8 - 10 ft	180-80091-4	Excavated	6700	< 0.39 U	5.3	55	0.28 J	0.086 J	18000	9.9		5.5 J	21	15000	14	3700	350
Football Field	SSHS-B2242	SSHS-B2242-SUB-8-10	7/23/2018	856.09	8 - 10 ft	180-80091-3	Excavated	10000	< 0.39 U	4.3	140	0.45 J	0.1 J	15000	13		6.8	43	17000	34	2600	760
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	6400	< 0.36 U	6.4	73	0.28 J	0.16 J	39000	15		6.1	53	18000	110	7700	450
Football Field	SSHS-B2242	SSHS-B2242-SUB-10-12	7/23/2018	856.09	10 - 12 ft	180-80091-3	Excavated	7800	< 0.4 U	5.6	96	0.35 J	0.13 J	43000	19		5.9	45	17000	50	10000	450
Football Field	SSHS-B2242	SSHS-B2242-SUB-2-4	7/23/2018	856.09	2 - 4 ft	180-80091-3	Excavated	7700	< 0.38 U	6.2	93	0.33 J	0.12 J	27000	14		6.9	42	19000	50	7800	350
Football Field	SSHS-B2242	PS-FD-2	7/23/2018	856.09	4 - 6 ft	180-80091-3	Excavated	6300	< 0.41 U	6.8	170	0.35 J	0.17 J	41000	28		6.4	60	22000	95	9300	410
Football Field	SSHS-B2242	SSHS-B2242-SUB-4-6	7/23/2018	856.09	4 - 6 ft	180-80091-3	Excavated	7700	< 0.38 U	7.9	200	0.41 J	0.25 J	27000	22		7.8	75	29000	110	4800	410
Football Field	SSHS-B2242	SSHS-B2242-SUB-6-8	7/23/2018	856.09	6 - 8 ft	180-80091-3	Excavated	8300	< 0.39 U	7.2	220	0.41 J	0.35 J	37000	19		6.7	88	24000	130	4500	450
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	6100	< 0.37 U	5.8	57	0.27 J	0.12 J	33000	8.7		5.1 J	24	15000	19	7600	440
Football Field	SSHS-B2243	SSHS-B2243-SUB-10-12	7/23/2018	856.00	10 - 12 ft	180-80091-2	Excavated	7100	< 0.39 U	6.3	100	0.33 J	0.17 J	17000	14		7	38	19000	30	4900	710
Football Field	SSHS-B2243	SSHS-B2243-SUB-2-4	7/23/2018	856.00	2 - 4 ft	180-80091-2	Excavated	8200	< 0.38 U	7	180	0.39 J	0.18 J	31000	13		6.9	89	19000	68	3200	400
Football Field	SSHS-B2243	SSHS-B2243-SUB-4-6	7/23/2018	856.00	4 - 6 ft	180-80091-2	Excavated	12000	< 0.38 U	5	220	0.35 J	0.77	46000	24		8.2	180	18000	96	4500	480
Football Field	SSHS-B2243	SSHS-B2243-SUB-6-8	7/23/2018	856.00	6 - 8 ft	180-80091-2	Excavated	9100	< 0.81 U,F1	7.3	300	0.47 J,F2,F1	0.37 J,F2,F1	53000	20		11	110	21000	180	4500	440
Football Field	SSHS-B2243	SSHS-B2243-SUB-8-10	7/23/2018	856.00	8 - 10 ft	180-80091-2	Excavated	6200	< 0.4 U	3.3	110	0.28 J	1.2	58000	11		4.7 J	44	12000	37	8500	390
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	6500	< 0.38 U	4.8	55	0.28 J	0.09 J	18000	11		6.3	40	20000	31	3900	480
Football Field	SSHS-B2244	SSHS-B2244-SUB-10-12	7/23/2018	856.09	10 - 12 ft	180-80091-3	Not Excavated	7000	< 0.39 U	5.8	77	0.32 J	0.13 J	21000	15		6.7	68	22000	73	5300	400

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2231	SSHS-B2231-SUB-6-8	7/23/2018	856.14	6 - 8 ft	180-80091-2	Excavated	0.045	38	730	0.66 J	< 0.13 U	750		< 0.25 U		18	120
Football Field	SSHS-B2232	PS-FD-9	7/24/2018	856.82	10 - 12 ft	180-80105-2	Not Excavated	0.013 J	14	610	0.62 J	< 0.12 U	55 J		< 0.23 U		10	53
Football Field	SSHS-B2232	SSHS-B2232-SUB-10-12	7/24/2018	856.82	10 - 12 ft	180-80105-1	Not Excavated	0.0093 J	16	620	< 0.6 U	< 0.12 U	61 J		< 0.24 U		10	60
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	0.042	17	620	< 0.6 U	< 0.12 U	79 J		< 0.24 U		11	60
Football Field	SSHS-B2232	SSHS-B2232-SUB-6-8	7/24/2018	856.82	6 - 8 ft	180-80105-1	Not Excavated	0.021 J	13	440 J	< 0.57 U	< 0.12 U	50 J		< 0.23 U		10	45
Football Field	SSHS-B2232	SSHS-B2232-SUB-8-10	7/24/2018	856.82	8 - 10 ft	180-80105-1	Not Excavated	0.013 J	19	400 J	< 0.59 U	< 0.12 U	35 J		< 0.24 U		7.8	40
Football Field	SSHS-B2232	SSHS-B2232-SUB-2-4	7/24/2018	856.82	2 - 4 ft	180-80105-1	Excavated	0.036 J	40	560 J	0.64 J	< 0.13 U	120 J		< 0.25 U		16	76
Football Field	SSHS-B2232	SSHS-B2232-SUB-4-6	7/24/2018	856.82	4 - 6 ft	180-80105-1	Excavated	0.049	19	720	1.9	< 0.13 U	190 J		< 0.27 U		16	110
Football Field	SSHS-B2233	SSHS-B2233-SUB-10-12	7/24/2018	854.83	10 - 12 ft	180-80105-1	Not Excavated	< 0.0085 U	12	540	< 0.55 U	< 0.11 U	48 J		< 0.22 U		9.6	46
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	< 0.008 U	13	540 J	< 0.59 U	< 0.12 U	56 J		< 0.24 U		8.7	44
Football Field	SSHS-B2233	SSHS-B2233-SUB-6-8	7/24/2018	854.83	6 - 8 ft	180-80105-1	Not Excavated	0.11	17	670	< 0.64 U	< 0.13 U	66 J		< 0.26 U		12	60
Football Field	SSHS-B2233	SSHS-B2233-SUB-8-10	7/24/2018	854.83	8 - 10 ft	180-80105-1	Not Excavated	0.0097 J	19	670	< 0.62 U	< 0.13 U	55 J		< 0.25 U		12	63
Football Field	SSHS-B2233	PS-FD-8	7/24/2018	854.83	2 - 4 ft	180-80105-2	Excavated	0.031 J	19	860	0.73 J	2.5	100 J		< 0.24 U		15	54
Football Field	SSHS-B2233	SSHS-B2233-SUB-2-4	7/24/2018	854.83	2 - 4 ft	180-80105-1	Excavated	0.05	24	930	0.63 J	< 0.12 U	260 J		< 0.24 U		15	73
Football Field	SSHS-B2233	SSHS-B2233-SUB-4-6	7/24/2018	854.83	4 - 6 ft	180-80105-1	Excavated	0.021 J	19	700	< 0.61 U	< 0.13 U	88 J		< 0.25 U		14	75
Football Field	SSHS-B2234	SSHS-B2234-SUB-10-12	7/23/2018	855.41	10 - 12 ft	180-80091-2	Not Excavated	< 0.0086 U	16	640	< 0.59 U	< 0.12 U	97 J		< 0.24 U		13	73
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	< 0.0086 U	11	440 J	< 0.57 U	< 0.12 U	55 J		< 0.23 U		8.5	48
Football Field	SSHS-B2234	SSHS-B2234-SUB-8-10	7/23/2018	855.41	8 - 10 ft	180-80091-1	Not Excavated	0.021 J	11	720	< 0.61 U	< 0.13 U	76 J		< 0.25 U		10	35
Football Field	SSHS-B2234	SSHS-B2234-SUB-2-4	7/23/2018	855.41	2 - 4 ft	180-80091-1	Excavated	0.061	18	850	0.6 J	0.15 J	270 J		< 0.24 U		16	300
Football Field	SSHS-B2234	PS-FD-5	7/23/2018	855.41	4 - 6 ft	180-80091-1	Excavated	0.047	15	690	0.77 J	< 0.12 U	220 J		< 0.24 U		14	85
Football Field	SSHS-B2234	SSHS-B2234-SUB-4-6	7/23/2018	855.41	4 - 6 ft	180-80091-1	Excavated	0.022 J	19	600	< 0.62 U	< 0.13 U	370 J		< 0.25 U		14	66
Football Field	SSHS-B2234	SSHS-B2234-SUB-6-8	7/23/2018	855.41	6 - 8 ft	180-80091-1	Excavated	0.012 J	18	730	< 0.59 U	< 0.12 U	75 J		< 0.24 U		20	54
Football Field	SSHS-B2235	SSHS-B2235-SUB-10-12	7/23/2018	855.30	10 - 12 ft	180-80091-1	Not Excavated	< 0.009 U	14	600	< 0.58 U	< 0.12 U	43 J		< 0.23 U		12	69
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	< 0.0081 U	10	450 J	< 0.56 U	< 0.11 U	47 J		< 0.23 U		8	39
Football Field	SSHS-B2235	PS-FD-3	7/23/2018	855.30	8 - 10 ft	180-80091-1	Not Excavated	0.012 J	12	630	< 0.59 U	< 0.12 U	64 J		< 0.24 U		12	38
Football Field	SSHS-B2235	SSHS-B2235-SUB-8-10	7/23/2018	855.30	8 - 10 ft	180-80091-1	Not Excavated	< 0.0085 U	18	770	< 0.62 U	< 0.13 U	70 J		< 0.25 U		16	50
Football Field	SSHS-B2235	SSHS-B2235-SUB-2-4	7/23/2018	855.30	2 - 4 ft	180-80091-1	Excavated	0.046	18	900	0.68 J	< 0.12 U	190 J		< 0.24 U		23	46
Football Field	SSHS-B2235	SSHS-B2235-SUB-4-6	7/23/2018	855.30	4 - 6 ft	180-80091-1	Excavated	0.019 J	16	610	< 0.57 U	< 0.12 U	110 J		< 0.23 U		12	55
Football Field	SSHS-B2235	SSHS-B2235-SUB-6-8	7/23/2018	855.30	6 - 8 ft	180-80091-1	Excavated	0.01 J	15	570 J	< 0.63 U	< 0.13 U	80 J		< 0.25 U		14	48
Football Field	SSHS-B2236	SSHS-B2236-SUB-2-4	7/27/2018	855.25	2 - 4 ft	180-80251-3	Excavated	0.014 J	54	680	< 0.55 U	< 0.11 U	170 J		< 0.22 U		12	64
Football Field	SSHS-B2236	PS-FD-52	7/27/2018	855.25	4 - 6 ft	180-80252-2	Excavated	0.028 J	91	850	< 0.56 U	< 0.11 U	250 J		< 0.23 U		15	89
Football Field	SSHS-B2236	SSHS-B2236-SUB-4-6	7/27/2018	855.25	4 - 6 ft	180-80251-3	Excavated	0.025 J	70	750	< 0.57 U	< 0.12 U	110 J		< 0.23 U		13	81
Football Field	SSHS-B2237	SSHS-B2237-SUB-2-4	7/27/2018	855.30	2 - 4 ft	180-80252-1	Excavated	0.26	110	810	0.88 J	< 0.13 U	420 J		< 0.26 U		13	320
Football Field	SSHS-B2238	SSHS-B2238-SUB-10-12	7/23/2018	855.07	10 - 12 ft	180-80091-1	Excavated	0.031 J	29	570	< 0.58 U	< 0.12 U	150 J		< 0.24 U		13	120
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	< 0.0081 U	23	700	< 0.57 U	< 0.12 U	110 J		< 0.23 U		10	90
Football Field	SSHS-B2238	SSHS-B2238-SUB-2-4	7/23/2018	855.07	2 - 4 ft	180-80091-1	Excavated	0.021 J	62	670	< 0.55 U,F1	< 0.11 U	99 J,F2,F1		< 0.23 U,F1		13	100
Football Field	SSHS-B2238	SSHS-B2238-SUB-4-6	7/23/2018	855.07	4 - 6 ft	180-80091-1	Excavated	0.027 J	35	730	< 0.56 U	< 0.11 U	110 J		< 0.23 U		13	160
Football Field	SSHS-B2238	SSHS-B2238-SUB-6-8	7/23/2018	855.07	6 - 8 ft	180-80091-1	Excavated	0.034 J	61	780	< 0.57 U	< 0.12 U	140 J		< 0.23 U		13	240
Football Field	SSHS-B2238	SSHS-B2238-SUB-8-10	7/23/2018	855.07	8 - 10 ft	180-80091-1	Excavated	0.027 J	44	640	< 0.59 U	< 0.12 U	190 J		< 0.24 U		12	180
Football Field	SSHS-B2239	SSHS-B2239-SUB-2-4	7/23/2018	855.51	2 - 4 ft	180-80091-3	Excavated	0.062	50	550 J	0.8 J	< 0.12 U	290 J		< 0.23 U		12	160
Football Field	SSHS-B2239	PS-FD-4	7/23/2018	855.51	10 - 12 ft	180-80091-4	Excavated	0.012 J	39	600	0.59 J	< 0.12 U	100 J		< 0.23 U		10	70
Football Field	SSHS-B2239	SSHS-B2239-SUB-10-12	7/23/2018	855.51	10 - 12 ft	180-80091-3	Excavated	0.0087 J	25	580	< 0.56 U	< 0.11 U	75 J		< 0.23 U		13	98
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	855.51	12 - 14 ft	180-80091-3	Excavated	< 0.0088 U	26	630	< 0.57 U	< 0.12 U	93 J		< 0.23 U		12	70
Football Field	SSHS-B2239	SSHS-B2239-SUB-4-6	7/23/2018	855.51	4 - 6 ft	180-80091-3	Excavated	0.05	110	710	0.69 J	< 0.12 U	140 J		< 0.23 U		14	210
Football Field	SSHS-B2239	SSHS-B2239-SUB-6-8	7/23/2018	855.51	6 - 8 ft	180-80091-3	Excavated	0.037 J	56	610	0.74 J	< 0.11 U	110 J		< 0.23 U		13	150
Football Field	SSHS-B2239	SSHS-B2239-SUB-8-10	7/23/2018	855.51	8 - 10 ft	180-80091-3	Excavated	0.024 J	47	650	< 0.58 U	< 0.12 U	62 J		< 0.24 U		13	98
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	0.014 J	14	640	< 0.56 U	< 0.11 U	37 J		< 0.23 U		11	58
Football Field	SSHS-B2240	SSHS-B2240-SUB-10-12	7/23/2018	855.85	10 - 12 ft	180-80091-2	Not Excavated	< 0.0085 U	15	670	< 0.55 U	< 0.11 U	92 J		< 0.22 U		10	59
Football Field	SSHS-B2240	SSHS-B2240-SUB-2-4	7/23/2018	855.85	2 - 4 ft	180-80091-2	Excavated	0.023 J	19	740	0.88 J	< 0.11 U	130 J		< 0.23 U		8.7	41
Football Field	SSHS-B2240	SSHS-B2240-SUB-4-6	7/23/2018	855.85	4 - 6 ft	180-80091-2	Excavated	0.018 J	20	730	< 0.58 U	< 0.12 U	75 J		< 0.24 U		17	59
Football Field	SSHS-B2240	SSHS-B2240-SUB-6-8	7/23/2018	855.85	6 - 8 ft	180-80091-2	Excavated	0.035 J	46	570	0.6 J	< 0.12 U	160 J		< 0.24 U		13	85
Football Field	SSHS-B2240	SSHS-B2240-SUB-8-10	7/23/2018	855.85	8 - 10 ft	180-80091-2	Excavated	0.014 J	18	590	< 0.55 U	< 0.11 U	59 J		< 0.22 U		10	51
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	855.46	12 - 14 ft	180-80091-4	Not Excavated	0.0086 J	19	630	0.6 J	< 0.12 U	56 J		< 0.23 U		12	53
Football Field	SSHS-B2241	SSHS-B2241-SUB-10-12	7/23/2018	855.46	10 - 12 ft	180-80091-4	Excavated	< 0.0077 U	19	660	< 0.56 U	< 0.12 U	64 J		< 0.23 U		11	49
Football Field	SSHS-B2241	PS-FD-6	7/23/2018	855.46	2 - 4 ft	180-80091-4	Excavated	0.035 J	33	760	0.88 J	< 0.12 U	89 J		< 0.24 U		15	68
Football Field	SSHS-B2241	SSHS-B2241-SUB-2-4	7/23/2018	855.46	2 - 4 ft	180-80091-4	Excavated	0.036 J	74	740	0.88 J	< 0.12 U	140 J		< 0.24 U		14	86
Football Field	SSHS-B2241	SSHS-B2241-SUB-4-6	7/23/2018	855.46	4 - 6 ft	180-80091-4	Excavated	0.019 J	34	840	< 0.6 U	< 0.12 U	110 J		< 0.24 U		15	59
Football Field	SSHS-B2241	SSHS-B2241-SUB-6-8	7/23/2018	855.46	6 - 8 ft	180-80091-4	Excavated	0.019 J	18	790	0.65 J	< 0.13 U	73 J		< 0.25 U		17	47
Football Field	SSHS-B2241	SSHS-B2241-SUB-8-10	7/23/2018	855.46	8 - 10 ft	180-80091-4	Excavated	< 0.0083 U	19	670	< 0.59 U	< 0.12 U	78 J		< 0.24 U		11	62
Football Field	SSHS-B2242	SSHS-B2242-SUB-8-10	7/23/2018	856.09	8 - 10 ft	180-80091-3	Excavated	0.016 J	20	680	< 0.59 U	< 0.12 U	260 J		< 0.24 U		16	75
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	0.015 J	33	760	< 0.55 U	< 0.11 U	160 J		< 0.22 U		13	84
Football Field	SSHS-B2242	SSHS-B2242-SUB-10-12	7/23/2018	856.09	10 - 12 ft	180-80091-3	Excavated	0.0098 J	45	870	< 0.6 U	< 0.12 U	180 J		< 0.25 U		13	82
Football Field	SSHS-B2242	SSHS-B2242-SUB-2-4	7/23/2018	856.09	2 - 4 ft	180-80091-3	Excavated	0.027 J	44	690	< 0.57 U	< 0.12 U	120 J		< 0.23 U		14	83
Football Field	SSHS-B2242	PS-FD-2	7/23/2018	856.09	4 - 6 ft	180-80091-3	Excavated	0.053	100	690	0.73 J	< 0.13 U	200 J		< 0.25 U		13	88
Football Field	SSHS-B2242	SSHS-B2242-SUB-4-6	7/23/2018	856.09	4 - 6 ft	180-80091-3	Excavated	0.047	90	860	0.84 J	< 0.12 U	320 J		< 0.24 U		18	120
Football Field	SSHS-B2242	SSHS-B2242-SUB-6-8	7/23/2018	856.09	6 - 8 ft	180-80091-3	Excavated	0.041	69	800	< 0.59 U	< 0.12 U	250 J		< 0.24 U		15	160
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	< 0.0085 U	14	740	< 0.56 U	< 0.12 U	120 J		< 0.23 U		11	76
Football Field	SSHS-B2243	SSHS-B2243-SUB-10-12	7/23/2018	856.00	10 - 12 ft	180-80091-2	Excavated	0.038	30	710	< 0.59 U	< 0.12 U	110 J		< 0.24 U		14	100
Football Field	SSHS-B2243	SSHS-B2243-SUB-2-4	7/23/2018	856.00	2 - 4 ft	180-80091-2	Excavated	0.035 J	28	700	< 0.57 U	< 0.12 U	140 J		< 0.23 U		15	130
Football Field	SSHS-B2243	SSHS-B2243-SUB-4-6	7/23/2018	856.00	4 - 6 ft	180-80091-2	Excavated	0.04	28	710	< 0.58 U	< 0.12 U	160 J		< 0.24 U		15	220
Football Field	SSHS-B2243	SSHS-B2243-SUB-6-8	7/23/2018	856.00	6 - 8 ft	180-80091-2	Excavated	0.051	43	810	0.9 J,F2,F1	< 0.13 U,F2,F1	180 J		< 0.25 U,F2,F1		15	140
Football Field	SSHS-B2243	SSHS-B2243-SUB-8-10	7/23/2018	856.00	8 - 10 ft	180-80091-2	Excavated	0.022 J	15	710	< 0.6 U	< 0.12 U	170 J		< 0.24 U		9.4	710
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	0.014 J	22	630	< 0.57 U	< 0.12 U	54 J		< 0.23 U		12	74
Football Field	SSHS-B2244	SSHS-B2244-SUB-10-12	7/23/2018	856.09	10 - 12 ft	180-80091-3	Not Excavated	0.02 J	32	700	0.77 J	< 0.12 U	65 J		< 0.24 U		14	96

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2244	PS-FD-1	7/23/2018	856.09	12 - 14 ft	180-80091-4	Not Excavated	5000	< 0.38 U	4.3	210	0.22 J	0.065 J	78000	14		4.6 J	28	15000	59	3300	380
Football Field	SSHS-B2244	SSHS-B2244-SUB-2-4	7/23/2018	856.09	2 - 4 ft	180-80091-3	Excavated	7900	< 0.39 U	8.4	89	0.33 J	0.1 J	22000	16		6.5	46	23000	56	5700	390
Football Field	SSHS-B2244	SSHS-B2244-SUB-4-6	7/23/2018	856.09	4 - 6 ft	180-80091-3	Excavated	7200	1.1	13	970	0.37 J	0.82	7500	37		8.3	240	44000	390	3100	480
Football Field	SSHS-B2244	SSHS-B2244-SUB-6-8	7/23/2018	856.09	6 - 8 ft	180-80091-3	Excavated	7100	< 0.4 U	6.2	190	0.34 J	0.34 J	11000	24		6.4	130	21000	200	3300	410
Football Field	SSHS-B2244	SSHS-B2244-SUB-8-10	7/23/2018	856.09	8 - 10 ft	180-80091-3	Excavated	6900	< 0.44 U	5.6	110	0.32 J	0.12 J	4500	15		6.9	98	21000	140	2200	450
Football Field	SSHS-B2245	SSHS-B2245-SUB-10-12	7/24/2018	855.25	10 - 12 ft	180-80106-1	Not Excavated	5800	< 0.35 U	3.5	46	0.18 J	0.081 J	42000	15		4.8 J	28	13000	5.8	7600	420
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	3700	< 0.36 U	4.8	32	0.14 J	0.067 J	33000	16		3.4 J	19	10000	6.1	3800	250
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	4800	< 0.35 U	3.1	35	0.15 J	0.074 J	37000	17		3.8 J	20	11000	5.9	4500	530
Football Field	SSHS-B2245	SSHS-B2245-SUB-8-10	7/24/2018	855.25	8 - 10 ft	180-80106-1	Not Excavated	5100	< 0.38 U	4	49	0.17 J	0.089 J	43000	20		4.4 J	28	12000	10	12000	440
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated	10000	< 0.38 U	7.5	140	0.41 J	0.3 J	34000	86		7.6	77	21000	90	4500	530
Football Field	SSHS-B2245	SSHS-B2245-SUB-4-6	7/24/2018	855.25	4 - 6 ft	180-80106-1	Excavated	6400	< 0.38 U	5	40	0.25 J	0.12 J	47000	12		5.7	28	15000	10	11000	410
Football Field	SSHS-B2245	SSHS-B2245-SUB-6-8	7/24/2018	855.25	6 - 8 ft	180-80106-1	Excavated	6000	< 0.36 U	4.5	36	0.23 J	0.14 J	40000	28		5.1 J	32	14000	10	11000	420
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated	9200	1 J	6.3	88	0.51	< 0.04 U	6800	18		9.7	130	27000	87	2600	480
Football Field	SSHS-B2618	PS-FD-18	5/17/2019	855.12	2 - 4 ft	180-90275-1	Excavated	9500	0.46 J	9.3 J	270 J	0.4 J	0.2 J	31000 J	21		7.2	63	20000	60	4600	850 J
Football Field	SSHS-B2618	SSHS-B2618-SUB-2-4	5/17/2019	855.12	2 - 4 ft	180-90275-1	Excavated	7300	0.75 J	5.5 J	150 J	0.32 J	0.28 J	11000 J	27		5.9	82	18000	97	3000	370 J
Football Field	SSHS-B2618	SSHS-B2618-SUB-4-6	5/17/2019	855.12	4 - 6 ft	180-90275-1	Excavated	7900	0.99 J	7.1	240	0.38 J	0.58	26000	57		7.3	280	25000	250	5400	490
Football Field	SSHS-B2618	SSHS-B2618-SUB-6-8	5/17/2019	855.12	6 - 8 ft	180-90275-1	Excavated	7800	0.69 J	8.1	120	0.37 J	0.38 J	29000	82		6.8	250	20000	91	6800	520
Football Field	SSHS-B2618	PS-FD-19	5/17/2019	855.12	10 - 12 ft	180-90275-1	Not Excavated	3700	< 0.38 U	3	37 J	0.15 J	0.14 J	100000 J	31		2.8 J	220	8500	26 J	9000 J	230
Football Field	SSHS-B2618	SSHS-B2618-SUB-10-12	5/17/2019	855.12	10 - 12 ft	180-90275-1	Not Excavated	5700	< 0.37 U	4	62 J	0.23 J	0.16 J	23000 J	32		3.8 J	280	12000	44 J	5100 J	230
Football Field	SSHS-B2618	SSHS-B2618-SUB-8-10	5/17/2019	855.12	8 - 10 ft	180-90275-1	Not Excavated	5900	< 0.35 U	5	49	0.22 J	0.19 J	42000	38		4.8 J	360	14000	18	14000	440
Football Field	SSHS-B2621	SSHS-B2621-SUB-2-4	5/15/2019	855.04	2 - 4 ft	180-90165-2	Excavated															
Football Field	SSHS-B2625	SSHS-B2625-SUB-10-12	5/16/2019	855.18	10 - 12 ft	180-90231-1	Excavated	4400	< 0.35 U	4.3	31	0.18 J	0.11 J	56000	6.8		4 J	20	10000	5.3	8100	400
Football Field	SSHS-B2625	SSHS-B2625-SUB-2-4	5/16/2019	855.18	2 - 4 ft	180-90231-1	Excavated															
Football Field	SSHS-B2625	SSHS-B2625-SUB-6-8	5/16/2019	855.18	6 - 8 ft	180-90231-1	Excavated	8000	< 0.37 U	7	66	0.37 J	0.17 J	2900	13		6	31	20000	13	2200	790
Football Field	SSHS-B2625	SSHS-B2625-SUB-8-10	5/16/2019	855.18	8 - 10 ft	180-90231-1	Excavated	7000	0.39 J	6.8	61	0.3 J	0.24 J	9300	11		6	31	17000	21	3100	600
Football Field	SSHS-B2629	SSHS-B2629-SUB-2-4	4/25/2019	855.32	2 - 4 ft	180-89522-1	Excavated	6700	0.66 J	6.4	160	0.35 J	0.15 J	8700	12		6.3	48	21000	140	2100	480
Football Field	SSHS-B2634	SSHS-B2634-SUB-6-8	4/24/2019	855.37	6 - 8 ft	180-89408-2	Excavated															
Football Field	SSHS-B2637	SSHS-B2637-SUB-4-6	4/24/2019	855.39	4 - 6 ft	180-89408-2	Excavated															
Football Field	SSHS-B2637	PS-FD-6	4/24/2019	855.39	8 - 10 ft	180-89408-2	Excavated															
Football Field	SSHS-B2637	SSHS-B2637-SUB-8-10	4/24/2019	855.39	8 - 10 ft	180-89408-2	Excavated															
Football Field	SSHS-B2646	SSHS-B2646-SUB-4-6	5/19/2019	854.76	4 - 6 ft	180-90323-1	Excavated	8300	0.96 J	9.3	130	0.42 J	0.19 J	9800	14		6.8	50	22000	130	3200	510
Football Field	SSHS-B2649	SSHS-B2649-SUB-2-4	5/17/2019	856.28	2 - 4 ft	180-90275-2	Excavated															
Football Field	SSHS-B2660	SSHS-B2660-SUB-2-4	4/25/2019	855.76	2 - 4 ft	180-89522-2	Excavated															
Football Field	SSHS-B2661	SSHS-B2661-SUB-4-6	4/25/2019	854.80	4 - 6 ft	180-89522-2	Excavated															
Football Field	SSHS-B2672	SSHS-B2672-SUB-2-4	5/19/2019	856.34	2 - 4 ft	180-90323-2	Excavated															
Football Field	SSHS-B2673	SSHS-B2673-SUB-2-4	5/18/2019	855.02	2 - 4 ft	180-90319-2	Excavated															
Football Field	SSHS-B2675	SSHS-B2675-SUB-4-6	5/17/2019	857.15	4 - 6 ft	180-90275-2	Excavated															
Football Field	SSHS-B2676	SSHS-B2676-SUB-8-10	5/16/2019	856.26	8 - 10 ft	180-90231-1	Not Excavated	6800	< 0.39 U	4.9	92	0.24 J	0.056 J	1300	8.2		5.2 J	25	15000	17	1900	550
Football Field	SSHS-B2679	SSHS-B2679-SUB-10-12	4/24/2019	855.15	10 - 12 ft	180-89408-2	Excavated															
Football Field	SSHS-B2679	SSHS-B2679-SUB-4-6	4/24/2019	855.15	4 - 6 ft	180-89408-2	Excavated															
Football Field	SSHS-B2679	SSHS-B2679-SUB-8-10	4/24/2019	855.15	8 - 10 ft	180-89408-2	Excavated															
Football Field	SSHS-B2679	SSHS-B2679-SUB-14-16	4/24/2019	855.15	14 - 16 ft	180-89408-2	Not Excavated															
Football Field	SSHS-B2682	SSHS-B2682-SUB-2-4	4/25/2019	854.91	2 - 4 ft	180-89522-2	Excavated															
Football Field	SSHS-B2684	SSHS-B2684-SUB-2-4	4/26/2019	856.09	2 - 4 ft	180-89521-2	Excavated															
Football Field	SSHS-B2684	SSHS-B2684-SUB-10-12	4/26/2019	856.09	10 - 12 ft	180-89521-2	Excavated															
Football Field	SSHS-B2684	SSHS-B2684-SUB-8-10	4/26/2019	856.09	8 - 10 ft	180-89521-2	Excavated															
Football Field	SSHS-B2698	SSHS-B2698-SUB-4-6	5/14/2019	855.31	4 - 6 ft	180-90048-1	Excavated	8000	< 22 U	11	720	0.36 J	0.8	27000	15		7	74	33000	35000	2100	560
Football Field	SSHS-B2698	SSHS-B2698-SUB-2-4	5/14/2019	855.31	2 - 4 ft	180-90048-1	Excavated	9800	0.51 J	6.3	110	0.41 J	0.16 J	6000	15		8.2	52	21000	63	3000	470
Football Field	SSHS-B2700	SSHS-B2700-SUB-8-10	5/17/2019	856.68	8 - 10 ft	180-90275-1	Not Excavated	3000	0.81 J	3.8	120	0.15 J	1.9	27000	19		2.9 J	110	19000	240	1400	410
Football Field	SSHS-B2708	SSHS-B2708-SUB-6-8	5/21/2019	855.05	6 - 8 ft	180-90380-1	Excavated	8500	< 0.38 U	4.4	56	0.34 J	0.08 J	1500	9.8		6.6	16	15000	12	2100	420
Football Field	SSHS-B2709	SSHS-B2709-SUB-4-6	5/20/2019	855.26	4 - 6 ft	180-90324-1	Not Excavated	5300	1.2	8.2	61	0.4 J	0.098 J	4700	16		6.5	41	23000	42	1300	530
Football Field	SSHS-B2718	SSHS-B2718-SUB-10-12	5/16/2019	855.30	10 - 12 ft	180-90231-1	Excavated	7100	< 0.4 U	7.7	68	0.3 J	0.22 J	12000	13		6.1	250	26000	20	2900	860
Football Field	SSHS-B2718	PS-FD-13	5/16/2019	855.30	2 - 4 ft	180-90231-1	Excavated	8700	< 0.4 U	5.3	190	0.35 J	0.42 J	97000	23		5.3 J	630	16000	240 J	5400	370
Football Field	SSHS-B2718	SSHS-B2718-SUB-2-4	5/16/2019	855.30	2 - 4 ft	180-90231-1	Excavated	9600	< 0.41 U	5.2	180	0.36 J	0.39 J	83000	20		5.5 J	750	15000	97 J	6400	390
Football Field	SSHS-B2718	SSHS-B2718-SUB-4-6	5/16/2019	855.30	4 - 6 ft	180-90231-1	Excavated	9700	7.8	5.4	180	0.38 J	0.39 J	44000	25		6.2	460	18000	260	4300	580
Football Field	SSHS-B2718	SSHS-B2718-SUB-6-8	5/16/2019	855.30	6 - 8 ft	180-90231-1	Excavated	8300	0.41 J	5.4	120	0.31 J	0.26 J	52000	22		5.4	410	16000	66	10000	380
Football Field	SSHS-B2718	SSHS-B2718-SUB-8-10	5/16/2019	855.30	8 - 10 ft	180-90231-1	Excavated	10000	< 0.4 U	6.3	66	0.43 J	0.12 J	52000	17		6.3	370	17000	13	4400	480
Football Field	SSHS-B2724	SSHS-B2724-SUB-4-6	4/24/2019	855.34	4 - 6 ft	180-89408-2	Excavated															
Football Field	SSHS-B2724	SSHS-B2724-SUB-6-8	4/24/2019	855.34	6 - 8 ft	180-89408-2	Excavated															
Football Field	SSHS-B2724	PS-FD-8	4/24/2019	855.34	2 - 4 ft	180-89408-2	Excavated															
Football Field	SSHS-B2724	SSHS-B2724-SUB-2-4	4/24/2019	855.34	2 - 4 ft	180-89408-2	Excavated															
Football Field	SSHS-B2724	SSHS-B2724-SUB-12-14	4/24/2019	855.34	12 - 14 ft	180-89408-2	Not Excavated															
Football Field	SSHS-B2725	SSHS-B2725-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-2	Excavated															
Football Field	SSHS-B2725	SSHS-B2725-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-2	Excavated															
Football Field	SSHS-B2734	SSHS-B2734-SUB-2-4	5/18/2019	855.30	2 - 4 ft	180-90319-1	Excavated	1300	< 2.1 U	4.5	12000	0.088 J	0.93	5600	29		6.3	150	140000	240	1400	1400
Football Field	SSHS-B2739	SSHS-B2739-SUB-4-6	5/18/2019	855.28	4 - 6 ft	180-90319-1	Excavated	9400	0.62 J-	5.7	82	0.4 J	0.065 J	11000 J+	11		5.5 J	14	17000	86 J	2000	300
Football Field	SSHS-B2740	SSHS-B2740-SUB-6-8	5/18/2019	855.30	6 - 8 ft	180-90319-1	Excavated	7800	0.64 J	5.9	110	0.35 J	0.12 J	30000	13		5.8	31	21000	77	2500	400
Football Field	SSHS-B2741	SSHS-B2741-SUB-10-12	4/24/2019	855.31	10 - 12 ft	180-89408-1	Excavated	6800	0.57 J	6.1	250	0.3 J	0.15 J	22000	11		6.1	62	19000	170	5300	400
Football Field	SSHS-B2742	SSHS-B2742-SUB-10-12	4/25/2019	855.04	10 - 12 ft	180-89522-1	Excavated	6300	< 0.35 U	4.8	160	0.26 J	0.13 J	56000	9.1		6.2	34	18000	77	6500	480
Football Field	SSHS-B2743	SSHS-B2743-SUB-10-12	4/24/2019	855.11	10 - 12 ft	180-89408-1	Excavated	7900	4.8 J	6.7	260	0.33 J	0.31 J	41000	15		6.8	100	22000	5700	9300	620
Football Field	SSHS-B2744	SSHS-B2744-SUB-4-6	5/15/2019	855.45	4 - 6 ft	180-90165-1	Excavated	10000	0.44 J	6.7	85	0.43 J	0.38 J	7600	13		8.7	78	29000	140	2300	610
Football Field	SSHS-B2745	PS-FD-7	4/24/2019	855.30	10 - 12 ft	180-89408-1	Excavated	6700	< 0.39 UJ	5.7	110	0.29 J	0.15 J	44000	13		6.2	100	17000	490 J	11000	520
Football Field	SSHS-B2745	SSHS-B2745-SUB-10-12	4/24/2019	855.30	10 - 12 ft	180-89408-1	Excavated	7600	0.46 J	6.2	150	0.34 J	0.16 J	42000	14		7.1	85	18000	280 J	8300	520
Football Field	SSHS-B2747	SSHS-B2747-SUB-2-4	4/23/2019	856.08	2 - 4 ft	180-89344-1	Excavated	7200	< 0.4 U	7.9	110	0.36 J	0.12 J	26000	13		6.5	44	20000	66	7000	400

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2244	PS-FD-1	7/23/2018	856.09	12 - 14 ft	180-80091-4	Not Excavated	0.034 J	32	510 J	< 0.58 U	< 0.12 U	63 J		< 0.24 U		8.9	61
Football Field	SSHS-B2244	SSHS-B2244-SUB-2-4	7/23/2018	856.09	2 - 4 ft	180-80091-3	Excavated	0.042	42	750	< 0.59 U	< 0.12 U	84 J		< 0.24 U		16	80
Football Field	SSHS-B2244	SSHS-B2244-SUB-4-6	7/23/2018	856.09	4 - 6 ft	180-80091-3	Excavated	0.66	160	700	0.82 J	0.13 J	230 J		< 0.23 U		21	340
Football Field	SSHS-B2244	SSHS-B2244-SUB-6-8	7/23/2018	856.09	6 - 8 ft	180-80091-3	Excavated	0.12	45	680	< 0.61 U	< 0.12 U	82 J		< 0.25 U		13	180
Football Field	SSHS-B2244	SSHS-B2244-SUB-8-10	7/23/2018	856.09	8 - 10 ft	180-80091-3	Excavated	0.081	26	710	< 0.66 U	< 0.13 U	64 J		< 0.27 U		12	110
Football Field	SSHS-B2245	SSHS-B2245-SUB-10-12	7/24/2018	855.25	10 - 12 ft	180-80106-1	Not Excavated	< 0.0077 U	17	620	< 0.54 U	< 0.11 U	76 J		< 0.22 U		7.9	79
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0077 U	13	460 J	< 0.54 U	< 0.11 U	75 J		< 0.22 U		5.7	68
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0077 U	15	480 J	< 0.53 U	< 0.11 U	87 J		< 0.21 U		6.3	72
Football Field	SSHS-B2245	SSHS-B2245-SUB-8-10	7/24/2018	855.25	8 - 10 ft	180-80106-1	Not Excavated	< 0.0076 U	24	610	< 0.57 U	< 0.12 U	89 J		< 0.23 U		7.9	110
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated	0.14	90	770	0.75 J	< 0.12 U	96 J		< 0.24 U		18	220
Football Field	SSHS-B2245	SSHS-B2245-SUB-4-6	7/24/2018	855.25	4 - 6 ft	180-80106-1	Excavated	< 0.0077 U	28	670	< 0.57 U	< 0.12 U	94 J		< 0.23 U		9.5	130
Football Field	SSHS-B2245	SSHS-B2245-SUB-6-8	7/24/2018	855.25	6 - 8 ft	180-80106-1	Excavated	< 0.0079 U	20	670	0.85 J	< 0.11 U	100 J		< 0.22 U		9.9	130
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated	0.15	36	670	< 0.57 U	< 0.12 U	70 J		0.37 J		19	240
Football Field	SSHS-B2618	PS-FD-18	5/17/2019	855.12	2 - 4 ft	180-90275-1	Excavated	0.091	54	830	0.79 J	< 0.12 U	150 J		< 0.37 U		15	93 J
Football Field	SSHS-B2618	SSHS-B2618-SUB-2-4	5/17/2019	855.12	2 - 4 ft	180-90275-1	Excavated	0.086	48	710	< 0.59 UJ	< 0.12 U	87 J		< 0.37 U		13	190 J
Football Field	SSHS-B2618	SSHS-B2618-SUB-4-6	5/17/2019	855.12	4 - 6 ft	180-90275-1	Excavated	0.083	92	800	< 0.59 U	< 0.12 U	270 J		< 0.37 U		15	250
Football Field	SSHS-B2618	SSHS-B2618-SUB-6-8	5/17/2019	855.12	6 - 8 ft	180-90275-1	Excavated	0.043	66	700	0.67 J	< 0.13 U	110 J		< 0.39 U		13	400
Football Field	SSHS-B2618	PS-FD-19	5/17/2019	855.12	10 - 12 ft	180-90275-1	Not Excavated	0.012 J	15	470 J	1.6 J	< 0.12 U	98 J		< 0.36 U		6	84
Football Field	SSHS-B2618	SSHS-B2618-SUB-10-12	5/17/2019	855.12	10 - 12 ft	180-90275-1	Not Excavated	0.015 J	22	510 J	< 0.57 UJ	< 0.12 U	150 J		< 0.35 U		7.2	130
Football Field	SSHS-B2618	SSHS-B2618-SUB-8-10	5/17/2019	855.12	8 - 10 ft	180-90275-1	Not Excavated	0.024 J	52	600	0.62 J	< 0.11 U	96 J		< 0.33 U		9	220
Football Field	SSHS-B2621	SSHS-B2621-SUB-2-4	5/15/2019	855.04	2 - 4 ft	180-90165-2	Excavated							< 12 UJ				
Football Field	SSHS-B2625	SSHS-B2625-SUB-10-12	5/16/2019	855.18	10 - 12 ft	180-90231-1	Excavated	< 0.015 U	11	670	0.85 J	< 0.11 U	< 26 U		< 0.33 U		9.4	56
Football Field	SSHS-B2625	SSHS-B2625-SUB-2-4	5/16/2019	855.18	2 - 4 ft	180-90231-1	Excavated							12 J				
Football Field	SSHS-B2625	SSHS-B2625-SUB-6-8	5/16/2019	855.18	6 - 8 ft	180-90231-1	Excavated	< 0.016 U	19	770	< 0.57 U	< 0.12 U	< 29 U		< 0.35 U		17	190
Football Field	SSHS-B2625	SSHS-B2625-SUB-8-10	5/16/2019	855.18	8 - 10 ft	180-90231-1	Excavated	< 0.015 U	18	790	< 0.55 U	< 0.11 U	< 28 U		< 0.34 U		13	160
Football Field	SSHS-B2629	SSHS-B2629-SUB-2-4	4/25/2019	855.32	2 - 4 ft	180-89522-1	Excavated	0.1	38	600	< 0.56 U	< 0.11 U	210 J		< 0.35 U		13	72
Football Field	SSHS-B2634	SSHS-B2634-SUB-6-8	4/24/2019	855.37	6 - 8 ft	180-89408-2	Excavated							34				
Football Field	SSHS-B2637	SSHS-B2637-SUB-4-6	4/24/2019	855.39	4 - 6 ft	180-89408-2	Excavated							31 J				
Football Field	SSHS-B2637	PS-FD-6	4/24/2019	855.39	8 - 10 ft	180-89408-2	Excavated							24 J				
Football Field	SSHS-B2637	SSHS-B2637-SUB-8-10	4/24/2019	855.39	8 - 10 ft	180-89408-2	Excavated							27 J				
Football Field	SSHS-B2646	SSHS-B2646-SUB-4-6	5/19/2019	854.76	4 - 6 ft	180-90323-1	Excavated	0.15	29		< 0.63 U	< 0.13 U	120 J		< 0.39 U		15	100
Football Field	SSHS-B2649	SSHS-B2649-SUB-2-4	5/17/2019	856.28	2 - 4 ft	180-90275-2	Excavated							17 J				
Football Field	SSHS-B2660	SSHS-B2660-SUB-2-4	4/25/2019	855.76	2 - 4 ft	180-89522-2	Excavated							28 J				
Football Field	SSHS-B2661	SSHS-B2661-SUB-4-6	4/25/2019	854.80	4 - 6 ft	180-89522-2	Excavated							29 J				
Football Field	SSHS-B2672	SSHS-B2672-SUB-2-4	5/19/2019	856.34	2 - 4 ft	180-90323-2	Excavated							16 J				
Football Field	SSHS-B2673	SSHS-B2673-SUB-2-4	5/18/2019	855.02	2 - 4 ft	180-90319-2	Excavated							42				
Football Field	SSHS-B2675	SSHS-B2675-SUB-4-6	5/17/2019	857.15	4 - 6 ft	180-90275-2	Excavated							14 J				
Football Field	SSHS-B2676	SSHS-B2676-SUB-8-10	5/16/2019	856.26	8 - 10 ft	180-90231-1	Not Excavated	< 0.016 U	12		< 0.59 U	< 0.12 U	570 U		< 0.37 U		9.6	49
Football Field	SSHS-B2679	SSHS-B2679-SUB-10-12	4/24/2019	855.15	10 - 12 ft	180-89408-2	Excavated							24 J				
Football Field	SSHS-B2679	SSHS-B2679-SUB-4-6	4/24/2019	855.15	4 - 6 ft	180-89408-2	Excavated							26 J				
Football Field	SSHS-B2679	SSHS-B2679-SUB-8-10	4/24/2019	855.15	8 - 10 ft	180-89408-2	Excavated							22 J				
Football Field	SSHS-B2679	SSHS-B2679-SUB-14-16	4/24/2019	855.15	14 - 16 ft	180-89408-2	Not Excavated							25 J				
Football Field	SSHS-B2682	SSHS-B2682-SUB-2-4	4/25/2019	854.91	2 - 4 ft	180-89522-2	Excavated							40				
Football Field	SSHS-B2684	SSHS-B2684-SUB-2-4	4/26/2019	856.09	2 - 4 ft	180-89521-2	Excavated							43				
Football Field	SSHS-B2684	SSHS-B2684-SUB-10-12	4/26/2019	856.09	10 - 12 ft	180-89521-2	Excavated							20 J				
Football Field	SSHS-B2684	SSHS-B2684-SUB-8-10	4/26/2019	856.09	8 - 10 ft	180-89521-2	Excavated							21 J				
Football Field	SSHS-B2698	SSHS-B2698-SUB-4-6	5/14/2019	855.31	4 - 6 ft	180-90048-1	Excavated	0.086 J	70 J+		1.4	0.2 J	1700 J-		< 0.41 U		18	220
Football Field	SSHS-B2698	SSHS-B2698-SUB-2-4	5/14/2019	855.31	2 - 4 ft	180-90048-1	Excavated	0.017 J	62		< 0.56 U	< 0.11 U	110 J		< 0.35 U		15	88
Football Field	SSHS-B2700	SSHS-B2700-SUB-8-10	5/17/2019	856.68	8 - 10 ft	180-90275-1	Not Excavated	< 0.013 U	15		0.63 J	< 0.13 U	240 J		< 0.38 U		6	570
Football Field	SSHS-B2708	SSHS-B2708-SUB-6-8	5/21/2019	855.05	6 - 8 ft	180-90380-1	Excavated	0.038	15	520 J	< 0.57 U	< 0.12 U	53 J		< 0.35 U		12	58
Football Field	SSHS-B2709	SSHS-B2709-SUB-4-6	5/20/2019	855.26	4 - 6 ft	180-90324-1	Not Excavated	0.032	15		< 0.62 U	< 0.13 U	130 J		< 0.39 U		21	49
Football Field	SSHS-B2718	SSHS-B2718-SUB-10-12	5/16/2019	855.30	10 - 12 ft	180-90231-1	Excavated	< 0.016 U	20	690	< 0.61 U	< 0.12 U	< 31 U		< 0.38 U		12	120
Football Field	SSHS-B2718	PS-FD-13	5/16/2019	855.30	2 - 4 ft	180-90231-1	Excavated	0.048 J	32	980	1.2 J	< 0.12 U	< 31 U		< 0.38 U		13	170
Football Field	SSHS-B2718	SSHS-B2718-SUB-2-4	5/16/2019	855.30	2 - 4 ft	180-90231-1	Excavated	0.086 J	30	1100	1.1 J	< 0.13 U	< 31 U		< 0.39 U		13	170
Football Field	SSHS-B2718	SSHS-B2718-SUB-4-6	5/16/2019	855.30	4 - 6 ft	180-90231-1	Excavated	0.05	50	880	0.6 J	< 0.12 U	< 28 U		< 0.35 U		14	210
Football Field	SSHS-B2718	SSHS-B2718-SUB-6-8	5/16/2019	855.30	6 - 8 ft	180-90231-1	Excavated	0.039	23	770	0.88 J	< 0.11 U	< 28 U		< 0.35 U		12	150
Football Field	SSHS-B2718	SSHS-B2718-SUB-8-10	5/16/2019	855.30	8 - 10 ft	180-90231-1	Excavated	< 0.016 U	17	830	0.67 J	< 0.12 U	< 30 U		< 0.38 U		14	56
Football Field	SSHS-B2724	SSHS-B2724-SUB-4-6	4/24/2019	855.34	4 - 6 ft	180-89408-2	Excavated							26 J				
Football Field	SSHS-B2724	SSHS-B2724-SUB-6-8	4/24/2019	855.34	6 - 8 ft	180-89408-2	Excavated							25 J				
Football Field	SSHS-B2724	PS-FD-8	4/24/2019	855.34	2 - 4 ft	180-89408-2	Excavated							19 J				
Football Field	SSHS-B2724	SSHS-B2724-SUB-2-4	4/24/2019	855.34	2 - 4 ft	180-89408-2	Excavated							21 J				
Football Field	SSHS-B2724	SSHS-B2724-SUB-12-14	4/24/2019	855.34	12 - 14 ft	180-89408-2	Not Excavated							23 J				
Football Field	SSHS-B2725	SSHS-B2725-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-2	Excavated							23 J				
Football Field	SSHS-B2725	SSHS-B2725-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-2	Excavated							21 J				
Football Field	SSHS-B2734	SSHS-B2734-SUB-2-4	5/18/2019	855.30	2 - 4 ft	180-90319-1	Excavated	0.14	380	230 J	1.5	< 0.13 U	250 J		0.95 J		< 4.2 U	250
Football Field	SSHS-B2739	SSHS-B2739-SUB-4-6	5/18/2019	855.28	4 - 6 ft	180-90319-1	Excavated	0.024 J	14	630	< 0.59 U	< 0.12 U	190 J		< 0.37 U		13	51 J-
Football Field	SSHS-B2740	SSHS-B2740-SUB-6-8	5/18/2019	855.30	6 - 8 ft	180-90319-1	Excavated	< 0.017 U	20	690	0.63 J	< 0.12 U	170 J		< 0.37 U		12	60
Football Field	SSHS-B2741	SSHS-B2741-SUB-10-12	4/24/2019	855.31	10 - 12 ft	180-89408-1	Excavated	0.031 J	63	660	< 0.58 U	< 0.12 U	90 J		< 0.36 U		11	76
Football Field	SSHS-B2742	SSHS-B2742-SUB-10-12	4/25/2019	855.04	10 - 12 ft	180-89522-1	Excavated	0.033	28	590	1.1	< 0.11 U	100 J		< 0.33 U		10	57
Football Field	SSHS-B2743	SSHS-B2743-SUB-10-12	4/24/2019	855.11	10 - 12 ft	180-89408-1	Excavated	0.052	67	750	1.1	< 0.12 U	180 J		< 0.37 U		12	140
Football Field	SSHS-B2744	SSHS-B2744-SUB-4-6	5/15/2019	855.45	4 - 6 ft	180-90165-1	Excavated	0.56	18	680	0.63 J	< 0.13 U	140 J		< 0.39 U		16	160
Football Field	SSHS-B2745	PS-FD-7	4/24/2019	855.30	10 - 12 ft	180-89408-1	Excavated	0.033	37	670	1.2	< 0.12 U	94 J		< 0.37 U		14	68
Football Field	SSHS-B2745	SSHS-B2745-SUB-10-12	4/24/2019	855.30	10 - 12 ft	180-89408-1	Excavated	0.032 J	47	700	0.99 J	< 0.11 U	100 J		< 0.35 U		15	83
Football Field	SSHS-B2747	SSHS-B2747-SUB-2-4	4/23/2019	856.08	2 - 4 ft	180-89344-1	Excavated	0.025 J	26	730	0.79 J	< 0.12 U	92 J		< 0.37 U		14	65

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2747	SSHS-B2747-SUB-6-8	4/23/2019	856.08	6 - 8 ft	180-89344-1	Excavated	7800	< 0.37 U	5.6	58	0.29 J	0.091 J	19000	10		5.8	30	18000	22	2700	360
Football Field	SSHS-B2747	SSHS-B2747-SUB-10-12	4/23/2019	856.08	10 - 12 ft	180-89344-1	Not Excavated	8100	< 0.38 U	6.1	85	0.36 J	0.12 J	18000	11		6.3	40	21000	37	6800	520
Football Field	SSHS-B2747	SSHS-B2747-SUB-12-14	4/23/2019	856.08	12 - 14 ft	180-89344-1	Not Excavated	7200	< 0.39 U	5.2	67	0.3 J	0.11 J	46000	9		6.2	22	17000	17	17000	540
Football Field	SSHS-B2747	SSHS-B2747-SUB-8-10	4/23/2019	856.08	8 - 10 ft	180-89344-1	Not Excavated	7500	< 0.38 U	5.8	68	0.32 J	0.094 J	5900	9.7		5.9	23	18000	17	3700	550
Football Field	SSHS-B2752	SSHS-B2752-SUB-10-12	4/24/2019	856.83	10 - 12 ft	180-89408-2	Excavated															
Football Field	SSHS-B2752	SSHS-B2752-SUB-12-14	4/24/2019	856.83	12 - 14 ft	180-89408-2	Excavated															
Football Field	SSHS-B2752	SSHS-B2752-SUB-14-16	4/24/2019	856.83	14 - 16 ft	180-89408-2	Excavated															
Football Field	SSHS-B2752	SSHS-B2752-SUB-2-4	4/24/2019	856.83	2 - 4 ft	180-89408-2	Excavated															
Football Field	SSHS-B2752	SSHS-B2752-SUB-4-6	4/24/2019	856.83	4 - 6 ft	180-89408-1	Excavated	7200	< 0.41 U	7.6	82	0.37 J	0.11 J	8900	11		6.1	48	19000	50	2400	400
Football Field	SSHS-B2752	SSHS-B2752-SUB-6-8	4/24/2019	856.83	6 - 8 ft	180-89408-1	Excavated	7200	0.53 J	6.1	74	0.35 J	0.14 J	42000	14		6.6	71	19000	37	3900	440
Football Field	SSHS-B2752	SSHS-B2752-SUB-8-10	4/24/2019	856.83	8 - 10 ft	180-89408-2	Excavated															
Football Field	SSHS-B2753	SSHS-B2753-SUB-2-4	4/23/2019	856.56	2 - 4 ft	180-89344-2	Excavated															
Football Field	SSHS-B2753	SSHS-B2753-SUB-4-6	4/23/2019	856.56	4 - 6 ft	180-89344-2	Excavated															
Football Field	SSHS-B2753	SSHS-B2753-SUB-6-8	4/23/2019	856.56	6 - 8 ft	180-89344-1	Excavated	8000	< 0.37 U	6	68	0.33 J	0.11 J	12000	9.9		7	23	19000	14	5000	640
Football Field	SSHS-B2753	PS-FD-4	4/23/2019	856.56	8 - 10 ft	180-89344-1	Excavated	8900	< 0.36 U	7.6	110	0.37 J	0.073 J	3200 J	12		6.8	25	20000	30	2800 J	380
Football Field	SSHS-B2753	SSHS-B2753-SUB-8-10	4/23/2019	856.56	8 - 10 ft	180-89344-1	Excavated	12000	< 0.47 UJ	8.1	130	0.46 J	0.082 J	3900 J	16		9.5	37	30000	31 J	3900 J	540
Football Field	SSHS-B2753	SSHS-B2753-SUB-10-12	4/23/2019	856.56	10 - 12 ft	180-89344-1	Not Excavated	8700	0.38 J	6.3	110	0.36 J	0.09 J	8500	12		7	24	21000	53	3900	510
Football Field	SSHS-B2753	SSHS-B2753-SUB-12-14	4/23/2019	856.56	12 - 14 ft	180-89344-1	Not Excavated	6600	< 0.38 U	4.6	46	0.27 J	0.098 J	20000	8.7		5.7	21	16000	11	5000	440
Football Field	SSHS-B2757	SSHS-B2757-SUB-8-10	4/26/2019	856.35	8 - 10 ft	180-89521-2	Excavated															
Football Field	SSHS-B2760	SSHS-B2760-SUB-4-6	4/25/2019	856.06	4 - 6 ft	180-89522-2	Excavated															
Football Field	SSHS-B2760	SSHS-B2760-SUB-6-8	4/25/2019	856.06	6 - 8 ft	180-89522-2	Excavated															
Football Field	SSHS-B2761	SSHS-B2761-SUB-12-14	4/25/2019	856.14	12 - 14 ft	180-89522-2	Excavated															
Football Field	SSHS-B2763	SSHS-B2763-SUB-2-4	4/26/2019	856.00	2 - 4 ft	180-89521-2	Excavated															
Football Field	SSHS-B2763	SSHS-B2763-SUB-4-6	4/26/2019	856.00	4 - 6 ft	180-89521-2	Excavated															
Football Field	SSHS-B2765	SSHS-B2765-SUB-2-4	4/25/2019	855.77	2 - 4 ft	180-89522-1	Excavated	8000	0.74 J	8.3	130	0.38 J	0.42 J	11000	17		6.7	100	26000	98	4700	440
Football Field	SSHS-B2765	PS-FD-13	4/25/2019	855.77	4 - 6 ft	180-89522-1	Excavated	7600	0.56 J	7.4	200	0.36 J	0.18 J	23000	13		6	42 J	18000	93	4000	380
Football Field	SSHS-B2765	SSHS-B2765-SUB-4-6	4/25/2019	855.77	4 - 6 ft	180-89522-1	Excavated	8000	0.54 J	8.2	230	0.39 J	0.24 J	24000	14		6.3	98 J	19000	100	4300	400
Football Field	SSHS-B2765	SSHS-B2765-SUB-6-8	4/25/2019	855.77	6 - 8 ft	180-89522-1	Excavated	7600	< 0.38 U	6.9	120	0.35 J	0.32 J	55000	14		5.9	32	24000	83	8900	400
Football Field	SSHS-B2765	SSHB-B2765-SUB-8-10	4/25/2019	855.77	8 - 10 ft	180-89522-1	Excavated	8900	< 0.37 U	6.7	110	0.36 J	0.29 J	61000	15		6.7	32	23000	50	6800	410
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-12-14	4/27/2019	855.65	12 - 14 ft	180-89523-1	Excavated	7500	< 0.37 U	6.4	94	0.3 J	0.49 J	50000	11		5.3 J	35	20000	100	4800	680
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-10-12	4/27/2019	855.65	10 - 12 ft	180-89523-1	Excavated	7100	0.39 J	8.3	67	0.36 J	0.14 J	7200	8		5.6 J	29	17000	59	2000	490
Football Field	SSHS-B2766	SSHS-B2766-SUB-6-8	4/23/2019	855.84	6 - 8 ft	180-89344-2	Excavated															
Football Field	SSHS-B2767	PS-FD-3	4/23/2019	856.06	2 - 4 ft	180-89344-1	Excavated	9500	5.7 J	5.9	100	0.37 J	0.13 J	35000 J	16		7.3	28	20000	3800 J	6700 J	420
Football Field	SSHS-B2767	SSHS-B2767-SUB-2-4	4/23/2019	856.06	2 - 4 ft	180-89344-1	Excavated	8600	< 0.37 UJ	5.8	85	0.36 J	0.12 J	27000 J	15		7.1	27	19000	30	6300 J	480
Football Field	SSHS-B2767	SSHS-B2767-SUB-4-6	4/23/2019	856.06	4 - 6 ft	180-89344-1	Excavated	8300	5.6	8.2	320	0.35 J	0.41 J	39000	17		7.8	35	24000	230	4700	440
Football Field	SSHS-B2767	SSHS-B2767-SUB-10-12	4/23/2019	856.06	10 - 12 ft	180-89344-1	Not Excavated	7700	< 0.37 U	7.4	67	0.33 J	0.11 J	18000	10		7	31	19000	10	3800	470
Football Field	SSHS-B2767	SSHS-B2767-SUB-12-14	4/23/2019	856.06	12 - 14 ft	180-89344-1	Not Excavated	7000	< 0.38 U	5.3	65	0.28 J	0.13 J	56000	10		6.2	25	18000	14	10000	490
Football Field	SSHS-B2767	SSHS-B2767-SUB-6-8	4/23/2019	856.06	6 - 8 ft	180-89344-1	Not Excavated	8700	< 0.37 U	5.6	190	0.33 J	0.14 J	16000	13		7.4	24	21000	31	4400	920
Football Field	SSHS-B2767	SSHS-B2767-SUB-8-10	4/23/2019	856.06	8 - 10 ft	180-89344-1	Not Excavated	7800	< 0.39 U	5.7	100	0.3 J	0.11 J	11000	11		6.2	24	18000	21	4200	450
Football Field	SSHS-B2771	SSHS-B2771-SUB-10-12	5/13/2019	854.87	10 - 12 ft	180-90048-1	Excavated	5500	< 0.37 UJ	2.9	220 J	0.17 J	0.098 J	31000	8.1		5 J	19	12000	7	6300	340
Football Field	SSHS-B2771	SSHS-B2771-SUB-6-8	5/13/2019	854.87	6 - 8 ft	180-90048-1	Excavated	7500	< 0.4 U	5.7	79	0.33 J	0.099 J	47000	10		5.1 J	21	13000	72	4200	520
Football Field	SSHS-B2771	SSHS-B2771-SUB-8-10	5/13/2019	854.87	8 - 10 ft	180-90048-1	Excavated	5700	< 0.38 U	4	39	0.22 J	0.12 J	42000	8.3		5.2 J	23	13000	10	5300	400
Football Field	SSHS-B2773	SSHS-B2773-SUB-6-8	5/13/2019	854.27	6 - 8 ft	180-90048-2	Not Excavated	4600	< 0.37 U	17	54	0.24 J	0.14 J	65000	8.5		5 J	31	12000	9.8	9600	380
Football Field	SSHS-B2773	SSHS-B2773-SUB-8-10	5/13/2019	854.27	8 - 10 ft	180-90048-2	Not Excavated	5400	< 0.37 U	12	56	0.27 J	0.12 J	40000	9.4		4.8 J	31	13000	9.7	11000	390
Football Field	SSHS-B2774	SSHS-B2774-SUB-6-8	5/13/2019	854.02	6 - 8 ft	180-90048-2	Not Excavated	5000	< 0.38 U	5.9	53	0.19 J	0.089 J	43000	7.9		4.3 J	31	12000	6.2	10000	390
Football Field	SSHS-B2774	SSHS-B2774-SUB-8-10	5/13/2019	854.02	8 - 10 ft	180-90048-2	Not Excavated	4200	< 0.36 U	21	46	0.17 J	0.066 J	32000	6.3		3.8 J	21	10000	5.2	6100	250
Football Field	SSHS-B2776	SSHS-B2776-SUB-2-4	5/19/2019	855.72	2 - 4 ft	180-90323-1	Excavated	6700	0.62 J	7.2	120	0.43 J	0.11 J	21000	9.3		4.9 J	17	18000	84	2100	200
Football Field	SSHS-B2776	SSHS-B2776-SUB-4-6	5/19/2019	855.72	4 - 6 ft	180-90323-1	Excavated	7300	0.53 J	4.3	95	0.3 J	0.063 J	5500	8.5		5.6 J	12	15000	84	1600	190
Football Field	SSHS-B2777	SSHS-B2777-SUB-2-4	5/19/2019	854.82	2 - 4 ft	180-90323-1	Excavated	9600	< 2 U	9	120	0.51	0.14 J	9400	13		8.4	32	22000	3100	3400	510
Football Field	SSHS-B2777	SSHS-B2777-SUB-4-6	5/19/2019	854.82	4 - 6 ft	180-90323-1	Excavated	6900	< 0.4 U	7	43	0.35 J	0.073 J	1100	8.8		6.1	20	21000	8.6	1900	470
Football Field	SSHS-B2777	SSHS-B2777-SUB-6-8	5/19/2019	854.82	6 - 8 ft	180-90323-1	Not Excavated	8000	0.52 J	7.6	72	0.38 J	0.048 J	1100	9.4		5.8	22	18000	12	1900	360
Football Field	SSHS-B2778	SSHS-B2778-SUB-2-4	5/19/2019	855.64	2 - 4 ft	180-90323-1	Excavated	11000	0.66 J	7	80	0.44 J	0.051 J	1200	12		8.5	17	20000	19	2600	570
Football Field	SSHS-B2778	SSHS-B2778-SUB-4-6	5/19/2019	855.64	4 - 6 ft	180-90323-1	Excavated	11000	< 0.41 U	7.4	44	0.48 J	< 0.044 U	2100	14		10	19	21000	20	2900	420
Football Field	SSHS-B2778	SSHS-B2778-SUB-6-8	5/19/2019	855.64	6 - 8 ft	180-90323-1	Not Excavated	8900	< 0.4 U	7.5	58	0.45 J	0.079 J	1500	11		9.5	22	20000	11	2500	610
Football Field	SSHS-B2779	SSHS-B2779-SUB-2-4	5/19/2019	855.06	2 - 4 ft	180-90323-1	Excavated	8100	0.8 J	6.9	89	0.39 J	0.093 J	9000	10		6.3	26	18000	1200	2400	320
Football Field	SSHS-B2779	SSHS-B2779-SUB-4-6	5/19/2019	855.06	4 - 6 ft	180-90323-1	Excavated	8200	0.5 J	6.7	67	0.38 J	0.062 J	2300	10		7	27	19000	330	2200	510
Football Field	SSHS-B2779	SSHS-B2779-SUB-6-8	5/19/2019	855.06	6 - 8 ft	180-90323-1	Not Excavated	7400	< 0.39 U	6.9	46	0.35 J	0.093 J	1500	10		6.9	22	18000	99	2400	510
Football Field	SSHS-B2780	SSHS-B2780-SUB-10-12	5/16/2019	855.70	10 - 12 ft	180-90231-1	Excavated	5900	< 0.38 UJ	3.7	28 J	0.19 J	0.14 J	54000	9		5.8	17	14000	5.5	13000	480
Football Field	SSHS-B2780	PS-FD-12	5/16/2019	855.70	2 - 4 ft	180-90231-1	Excavated	7400	1.1 J	7.8	140	0.41 J	0.28 J	43000	57		6.1	130	23000	100	5200	560
Football Field	SSHS-B2780	SSHS-B2780-SUB-2-4	5/16/2019	855.70	2 - 4 ft	180-90231-1	Excavated	8500	1.4 J	8.5	110	0.48 J	0.27 J	28000	47		7.5	110	34000	100	4600	600
Football Field	SSHS-B2780	SSHS-B2780-SUB-4-6	5/16/2019	855.70	4 - 6 ft	180-90231-1	Excavated	8600	0.58 J	6.1	450	0.33 J	0.24 J	6700	13		5.5 J	37	20000	250	2200	400
Football Field	SSHS-B2780	SSHS-B2780-SUB-6-8	5/16/2019	855.70	6 - 8 ft	180-90231-1	Excavated	10000	0.52 J	8	69	0.42 J	0.082 J	1900	12		7.6	29	22000	16	2500	400
Football Field	SSHS-B2780	SSHS-B2780-SUB-8-10	5/16/2019	855.70	8 - 10 ft	180-90231-1	Excavated	6700	< 0.36 U	5.5	51	0.28 J	0.11 J	1400	9.9		5.5	22	16000	15	2100	440
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	7700	3.2 J	5.7	230	0.29 J	0.14 J	9600	24		5.9	87	25000	2400	2500	430
Football Field	SSHS-B2782	SSHS-B2782-SUB-4-6	5/20/2019	855.29	4 - 6 ft	180-90324-1	Excavated	9300	63	12	180	0.45 J	1.5	47000	22		8.9	110	27000	2800	4600	490
Football Field	SSHS-B2783	SSHS-B2783-SUB-4-6	5/19/2019	854.95	4 - 6 ft	180-90323-1	Excavated	5700	0.65 J	12	56	0.26 J	0.089 J	1400	16		7.4	26	40000	53	1400	520
Football Field	SSHS-B2784	SSHS-B2784-SUB-4-6	5/19/2019	855.04	4 - 6 ft	180-90323-1	Excavated	8800	< 0.4 UJ	6.5	64	0.39 J	0.084 J	2700	12		6.8	23	18000	15	2600	460
Football Field	SSHS-B2785	SSHS-B2785-SUB-6-8	5/20/2019	856.43	6 - 8 ft	180-90324-1	Excavated	6100	10	7	58	0.38 J	0.14 J	5200	15		8.6	220	42000	65	1300	900
Football Field	SSHS-B2786	SSHS-B2786-SUB-6-8	5/20/2019	856.97	6 - 8 ft	180-90324-1	Not Excavated	9400	3.5	8.4	130	0.43 J	0.24 J	4800	42		9.7	170	34000	930	2200	470
Football Field	SSHS-B2787	SSHS-B2787-SUB-6-8	5/20/2019	857.02	6 - 8 ft	180-90324-1	Not Excavated	10000	3.7	6.9	140	0.45 J	0.27 J	2000	15		7.7	240	27000	110	2300	560
Football Field	SSHS-B2788	PS-FD-26	5/20/2019	856.74	6 - 8 ft	180-90324-1	Not Excavated	5400	95 J	43 J	53	0.28 J	0.29 J	2300 J	45		31	9300 J	200000 J	940 J	1200 J	1200
Football Field	SSHS-B2788	SSHS-B2788-SUB-6-8	5/20/2019	856.74	6 - 8 ft	180-90324-1	Not Excavated	6600	49 J	16 J	73	0.34 J	0.3 J	4000 J	36		20	2600 J	95000 J	330 J	2100 J	820
Football Field	SSHS-B2789	SSHS-B2789-SUB-6-8	5/21/2019	855.23	6 - 8 ft	180-90380-1	Not Excavated	9700	< 0.41 U	3.5	65	0.4 J	0.11 J	1400	13		6.9	24	18000	47	2400	590
Football Field	SSHS-B2790	SSHS-B2790-SUB-6-8	5/21/2019	855.30	6 - 8 ft	180-90380-1	Not Excavated	7600	< 0.4 U	6.5	67	0.36 J	0.29 J	11000	20		7.4	150	27000	110	2700	760

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2747	SSHS-B2747-SUB-6-8	4/23/2019	856.08	6 - 8 ft	180-89344-1	Excavated	0.019 J	17	600	< 0.55 U	< 0.11 U	58 J		< 0.34 U		12	62
Football Field	SSHS-B2747	SSHS-B2747-SUB-10-12	4/23/2019	856.08	10 - 12 ft	180-89344-1	Not Excavated	0.015 J	20	670	0.67 J	< 0.12 U	97 J		< 0.36 U		12	75
Football Field	SSHS-B2747	SSHS-B2747-SUB-12-14	4/23/2019	856.08	12 - 14 ft	180-89344-1	Not Excavated	< 0.016 U	16	810	0.83 J	< 0.12 U	96 J		< 0.37 U		11	55
Football Field	SSHS-B2747	SSHS-B2747-SUB-8-10	4/23/2019	856.08	8 - 10 ft	180-89344-1	Not Excavated	< 0.019 U	16	700	< 0.58 U	< 0.12 U	58 J		< 0.36 U		12	73
Football Field	SSHS-B2752	SSHS-B2752-SUB-10-12	4/24/2019	856.83	10 - 12 ft	180-89408-2	Excavated							26 J				
Football Field	SSHS-B2752	SSHS-B2752-SUB-12-14	4/24/2019	856.83	12 - 14 ft	180-89408-2	Excavated							29 J				
Football Field	SSHS-B2752	SSHS-B2752-SUB-14-16	4/24/2019	856.83	14 - 16 ft	180-89408-2	Excavated							25 J				
Football Field	SSHS-B2752	SSHS-B2752-SUB-2-4	4/24/2019	856.83	2 - 4 ft	180-89408-2	Excavated							28 J				
Football Field	SSHS-B2752	SSHS-B2752-SUB-4-6	4/24/2019	856.83	4 - 6 ft	180-89408-1	Excavated	0.048	25	570 J	0.73 J	< 0.13 U	150 J		< 0.38 U		12	79
Football Field	SSHS-B2752	SSHS-B2752-SUB-6-8	4/24/2019	856.83	6 - 8 ft	180-89408-1	Excavated	0.09	25	610	0.87 J	< 0.12 U	140 J		< 0.37 U		12	73
Football Field	SSHS-B2752	SSHS-B2752-SUB-8-10	4/24/2019	856.83	8 - 10 ft	180-89408-2	Excavated							30 J				
Football Field	SSHS-B2753	SSHS-B2753-SUB-2-4	4/23/2019	856.56	2 - 4 ft	180-89344-2	Excavated							22 J				
Football Field	SSHS-B2753	SSHS-B2753-SUB-4-6	4/23/2019	856.56	4 - 6 ft	180-89344-2	Excavated							35 J				
Football Field	SSHS-B2753	SSHS-B2753-SUB-6-8	4/23/2019	856.56	6 - 8 ft	180-89344-1	Excavated	< 0.014 U	18	680	< 0.57 U	< 0.12 U	100 J		< 0.35 U		12	63
Football Field	SSHS-B2753	PS-FD-4	4/23/2019	856.56	8 - 10 ft	180-89344-1	Excavated	< 0.012 UJ	18	680	< 0.55 UJ	< 0.11 U	74 J		< 0.34 U		13	51
Football Field	SSHS-B2753	SSHS-B2753-SUB-8-10	4/23/2019	856.56	8 - 10 ft	180-89344-1	Excavated	< 0.018 UJ	24	830	< 0.71 U	< 0.15 UJ	130 J		< 0.44 U		17	69
Football Field	SSHS-B2753	SSHS-B2753-SUB-10-12	4/23/2019	856.56	10 - 12 ft	180-89344-1	Not Excavated	< 0.016 U	18	690	< 0.57 U	< 0.12 U	120 J		< 0.35 U		13	54
Football Field	SSHS-B2753	SSHS-B2753-SUB-12-14	4/23/2019	856.56	12 - 14 ft	180-89344-1	Not Excavated	< 0.015 U	15	680	< 0.58 U	< 0.12 U	72 J		< 0.36 U		10	52
Football Field	SSHS-B2757	SSHS-B2757-SUB-8-10	4/26/2019	856.35	8 - 10 ft	180-89521-2	Excavated							13 J				
Football Field	SSHS-B2760	SSHS-B2760-SUB-4-6	4/25/2019	856.06	4 - 6 ft	180-89522-2	Excavated							38				
Football Field	SSHS-B2760	SSHS-B2760-SUB-6-8	4/25/2019	856.06	6 - 8 ft	180-89522-2	Excavated							18 J				
Football Field	SSHS-B2761	SSHS-B2761-SUB-12-14	4/25/2019	856.14	12 - 14 ft	180-89522-2	Excavated							27 J				
Football Field	SSHS-B2763	SSHS-B2763-SUB-2-4	4/26/2019	856.00	2 - 4 ft	180-89521-2	Excavated							19 J				
Football Field	SSHS-B2763	SSHS-B2763-SUB-4-6	4/26/2019	856.00	4 - 6 ft	180-89521-2	Excavated							41				
Football Field	SSHS-B2765	SSHS-B2765-SUB-2-4	4/25/2019	855.77	2 - 4 ft	180-89522-1	Excavated	0.032 J	28	750	< 0.6 U	< 0.12 U	75 J		< 0.38 U		15	160
Football Field	SSHS-B2765	PS-FD-13	4/25/2019	855.77	4 - 6 ft	180-89522-1	Excavated	0.48 J	30	750	0.7 J	< 0.12 U	170 J		< 0.36 U		13	84
Football Field	SSHS-B2765	SSHS-B2765-SUB-4-6	4/25/2019	855.77	4 - 6 ft	180-89522-1	Excavated	0.074 J	34	840	1 J	< 0.12 U	150 J		< 0.36 U		14	96
Football Field	SSHS-B2765	SSHS-B2765-SUB-6-8	4/25/2019	855.77	6 - 8 ft	180-89522-1	Excavated	0.056	21	890	1.1	< 0.12 U	160 J		< 0.35 U		13	64
Football Field	SSHS-B2765	SSHB-B2765-SUB-8-10	4/25/2019	855.77	8 - 10 ft	180-89522-1	Excavated	0.054	21	960	1.2	< 0.12 U	160 J		< 0.35 U		13	64
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-12-14	4/27/2019	855.65	12 - 14 ft	180-89523-1	Excavated	0.1	26	640	0.92 J	< 0.11 U	130 J	20 J	< 0.35 U		12	99
Football Field	SSHS-B2765A	SSHS-B2765A-SUB-10-12	4/27/2019	855.65	10 - 12 ft	180-89523-1	Excavated	0.027 J	16	740	< 0.58 U	< 0.12 U	90 J	52	< 0.36 U		12	70
Football Field	SSHS-B2766	SSHS-B2766-SUB-6-8	4/23/2019	855.84	6 - 8 ft	180-89344-2	Excavated							24 J				
Football Field	SSHS-B2767	PS-FD-3	4/23/2019	856.06	2 - 4 ft	180-89344-1	Excavated	0.019 J	22	860	0.7 J	0.27 J	95 J		< 0.37 U		14	79
Football Field	SSHS-B2767	SSHS-B2767-SUB-2-4	4/23/2019	856.06	2 - 4 ft	180-89344-1	Excavated	0.02 J	23	720	0.91 J	< 0.11 U	85 J		< 0.35 U		14	73 J-
Football Field	SSHS-B2767	SSHS-B2767-SUB-4-6	4/23/2019	856.06	4 - 6 ft	180-89344-1	Excavated	0.069	26	850	0.59 J	< 0.12 U	160 J		< 0.35 U		13	160
Football Field	SSHS-B2767	SSHS-B2767-SUB-10-12	4/23/2019	856.06	10 - 12 ft	180-89344-1	Not Excavated	< 0.017 U	18	760	< 0.56 U	< 0.12 U	73 J		< 0.35 U		14	70
Football Field	SSHS-B2767	SSHS-B2767-SUB-12-14	4/23/2019	856.06	12 - 14 ft	180-89344-1	Not Excavated	< 0.016 U	34	700	1.2	< 0.12 U	92 J		< 0.36 U		11	64
Football Field	SSHS-B2767	SSHS-B2767-SUB-6-8	4/23/2019	856.06	6 - 8 ft	180-89344-1	Not Excavated	0.038	20	820	0.65 J	< 0.12 U	98 J		< 0.35 U		13	76
Football Field	SSHS-B2767	SSHS-B2767-SUB-8-10	4/23/2019	856.06	8 - 10 ft	180-89344-1	Not Excavated	0.018 J	17	760	< 0.59 U	< 0.12 U	94 J		< 0.37 U		14	69
Football Field	SSHS-B2771	SSHS-B2771-SUB-10-12	5/13/2019	854.87	10 - 12 ft	180-90048-1	Excavated	< 0.012 UJ	13	1200	< 0.56 U	< 0.11 U	75 J		< 0.35 U		11	53 J
Football Field	SSHS-B2771	SSHS-B2771-SUB-6-8	5/13/2019	854.87	6 - 8 ft	180-90048-1	Excavated	< 0.016 U	14	750	1.1 J	< 0.12 U	110 J		< 0.37 U		11	47
Football Field	SSHS-B2771	SSHS-B2771-SUB-8-10	5/13/2019	854.87	8 - 10 ft	180-90048-1	Excavated	< 0.015 U	15	550 J	< 0.57 U	< 0.12 U	87 J		< 0.36 U		10	90
Football Field	SSHS-B2773	SSHS-B2773-SUB-6-8	5/13/2019	854.27	6 - 8 ft	180-90048-2	Not Excavated	< 0.016 U	18	560	1.2	< 0.12 U	99 J		< 0.35 U		8.7	110
Football Field	SSHS-B2773	SSHS-B2773-SUB-8-10	5/13/2019	854.27	8 - 10 ft	180-90048-2	Not Excavated	< 0.011 U	15	610	0.58 J	< 0.12 U	81 J		< 0.35 U		8.5	60
Football Field	SSHS-B2774	SSHS-B2774-SUB-6-8	5/13/2019	854.02	6 - 8 ft	180-90048-2	Not Excavated	< 0.011 U	11	540 J	< 0.57 U	< 0.12 U	77 J		< 0.36 U		8.6	52
Football Field	SSHS-B2774	SSHS-B2774-SUB-8-10	5/13/2019	854.02	8 - 10 ft	180-90048-2	Not Excavated	< 0.01 U	10	490 J	< 0.54 U	< 0.11 U	73 J		< 0.34 U		6.5	49
Football Field	SSHS-B2776	SSHS-B2776-SUB-2-4	5/19/2019	855.72	2 - 4 ft	180-90323-1	Excavated	0.055	13	1100	< 0.65 U	< 0.13 U	670		< 0.4 U		13	37
Football Field	SSHS-B2776	SSHS-B2776-SUB-4-6	5/19/2019	855.72	4 - 6 ft	180-90323-1	Excavated	< 0.02 U	14	1300	< 0.68 U	< 0.14 U	1900		< 0.42 U		14	27
Football Field	SSHS-B2777	SSHS-B2777-SUB-2-4	5/19/2019	854.82	2 - 4 ft	180-90323-1	Excavated	0.034 J	22	930	< 0.6 U	< 0.12 U	97 J		< 0.37 U		15	83
Football Field	SSHS-B2777	SSHS-B2777-SUB-4-6	5/19/2019	854.82	4 - 6 ft	180-90323-1	Excavated	< 0.015 U	14	630	< 0.6 U	< 0.12 U	36 J		< 0.38 U		12	55
Football Field	SSHS-B2777	SSHS-B2777-SUB-6-8	5/19/2019	854.82	6 - 8 ft	180-90323-1	Not Excavated	< 0.011 U	16	720	< 0.6 U	< 0.12 U	33 J		< 0.37 U		13	53
Football Field	SSHS-B2778	SSHS-B2778-SUB-2-4	5/19/2019	855.64	2 - 4 ft	180-90323-1	Excavated	0.017 J	20	890	< 0.62 U	< 0.13 U	85 J		< 0.38 U		16	57
Football Field	SSHS-B2778	SSHS-B2778-SUB-4-6	5/19/2019	855.64	4 - 6 ft	180-90323-1	Excavated	< 0.012 U	18	850	< 0.63 U	< 0.13 U	72 J		< 0.39 U		16	55
Football Field	SSHS-B2778	SSHS-B2778-SUB-6-8	5/19/2019	855.64	6 - 8 ft	180-90323-1	Not Excavated	< 0.014 U	19	840	< 0.61 U	< 0.12 U	67 J		< 0.38 U		14	61
Football Field	SSHS-B2779	SSHS-B2779-SUB-2-4	5/19/2019	855.06	2 - 4 ft	180-90323-1	Excavated	0.032 J	17	620	< 0.64 U	< 0.13 U	67 J		< 0.4 U		13	67
Football Field	SSHS-B2779	SSHS-B2779-SUB-4-6	5/19/2019	855.06	4 - 6 ft	180-90323-1	Excavated	0.025 J	18	710	< 0.62 U	< 0.13 U	47 J		< 0.39 U		13	65
Football Field	SSHS-B2779	SSHS-B2779-SUB-6-8	5/19/2019	855.06	6 - 8 ft	180-90323-1	Not Excavated	< 0.014 U	19	660	< 0.6 U	< 0.12 U	42 J		< 0.37 U		12	60
Football Field	SSHS-B2780	SSHS-B2780-SUB-10-12	5/16/2019	855.70	10 - 12 ft	180-90231-1	Excavated	< 0.016 U	13	710	< 0.57 U	< 0.12 U	560 U		< 0.36 U		11	50 J+
Football Field	SSHS-B2780	PS-FD-12	5/16/2019	855.70	2 - 4 ft	180-90231-1	Excavated	0.082	33	830	1.5 J	< 0.13 U	590 U		< 0.38 U		17	120
Football Field	SSHS-B2780	SSHS-B2780-SUB-2-4	5/16/2019	855.70	2 - 4 ft	180-90231-1	Excavated	0.089	29	900	0.73 J	< 0.12 U	590 U		< 0.38 U		20	110
Football Field	SSHS-B2780	SSHS-B2780-SUB-4-6	5/16/2019	855.70	4 - 6 ft	180-90231-1	Excavated	0.023 J	35	670	< 0.57 U	< 0.12 U	560 U		< 0.36 U		14	150
Football Field	SSHS-B2780	SSHS-B2780-SUB-6-8	5/16/2019	855.70	6 - 8 ft	180-90231-1	Excavated	0.04	19	910	< 0.6 U	< 0.12 U	580 U		< 0.37 U		16	68
Football Field	SSHS-B2780	SSHS-B2780-SUB-8-10	5/16/2019	855.70	8 - 10 ft	180-90231-1	Excavated	< 0.015 U	14	780	< 0.54 U	< 0.11 U	530 U		< 0.34 U		12	61
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	0.43	21	700	0.63 J	< 0.12 U	140 J		< 0.36 U		12	86
Football Field	SSHS-B2782	SSHS-B2782-SUB-4-6	5/20/2019	855.29	4 - 6 ft	180-90324-1	Excavated	0.044	21	940	1 J	< 0.13 U	380 J		< 0.4 U		27	1300
Football Field	SSHS-B2783	SSHS-B2783-SUB-4-6	5/19/2019	854.95	4 - 6 ft	180-90323-1	Excavated	0.57	16	380 J	< 0.6 U	< 0.12 U	46 J		< 0.37 U		26	48
Football Field	SSHS-B2784	SSHS-B2784-SUB-4-6	5/19/2019	855.04	4 - 6 ft	180-90323-1	Excavated	0.082	16	650	< 0.6 U	< 0.12 U	48 J		< 0.37 U		13	55 J+
Football Field	SSHS-B2785	SSHS-B2785-SUB-6-8	5/20/2019	856.43	6 - 8 ft	180-90324-1	Excavated	0.12	17	880	< 0.62 U	< 0.13 U	120 J		< 0.39 U		25	85
Football Field	SSHS-B2786	SSHS-B2786-SUB-6-8	5/20/2019	856.97	6 - 8 ft	180-90324-1	Not Excavated	0.062	45	700	< 0.65 U	< 0.13 U	87 J		< 0.4 U		32	840
Football Field	SSHS-B2787	SSHS-B2787-SUB-6-8	5/20/2019	857.02	6 - 8 ft	180-90324-1	Not Excavated	0.17	130	700	< 0.64 U	< 0.13 U	100 J		< 0.4 U		18	1400
Football Field	SSHS-B2788	PS-FD-26	5/20/2019	856.74	6 - 8 ft	180-90324-1	Not Excavated	0.13 J	220	500 J	2.7 J	5.2 J	63 J		0.77 J		72 J	660
Football Field	SSHS-B2788	SSHS-B2788-SUB-6-8	5/20/2019	856.74	6 - 8 ft	180-90324-1	Not Excavated	0.24 J	220	670	1.1 J	1.5 J	56 J		0.57 J		35 J	540
Football Field	SSHS-B2789	SSHS-B2789-SUB-6-8	5/21/2019	855.23	6 - 8 ft	180-90380-1	Not Excavated	0.17	17	640	< 0.62 U	< 0.13 U	72 J		< 0.39 U		13	53
Football Field	SSHS-B2790	SSHS-B2790-SUB-6-8	5/21/2019	855.30	6 - 8 ft	180-90380-1	Not Excavated	0.052	26	590	< 0.6 U	< 0.12 U	70 J		< 0.37 U		12	130

DRAFT

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]	Aluminum mg/kg	Antimony mg/kg	Arsenic mg/kg	Barium mg/kg	Beryllium mg/kg	Cadmium mg/kg	Calcium mg/kg	Chromium (III+VI) mg/kg	Chromium, Hexavalent mg/kg	Cobalt mg/kg	Copper mg/kg	Iron mg/kg	Lead mg/kg	Magnesium mg/kg	Manganese mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	9600	0.40 J	5.1	74	0.40 J	0.082 J	1600	12		7.2	24	18000	15	2400	400
Football Field	SSHS-B2804	SSHS-B2804-SUB-4-6	5/19/2019	855.74	4 - 6 ft	180-90323-1	Excavated	9800	0.97 J	7.9	190	0.44 J	0.12 J	26000	11		5.9	17	18000	23	2100	830
Football Field	SSHS-B2805	PS-FD-11	5/16/2019	856.47	8 - 10 ft	180-90231-1	Not Excavated	8500	0.47 J	5.1	74	0.31 J	0.1 J	2500	11		7	32	18000	28	2500	910
Football Field	SSHS-B2805	SSHS-B2805-SUB-8-10	5/16/2019	856.47	8 - 10 ft	180-90231-1	Not Excavated	7600	0.53 J	4.8	89	0.28 J	0.066 J	3600	9.1		5.8	31	16000	20	2100	740
Football Field	SSHS-B2926	SSHS-B2926-SUB-2-4	11/5/2019	855.61	2 - 4 ft	180-98355-1	Excavated	7100	13	17	850	0.42 J	1.2	21000	98		13	700	82000	4900	2700	750
Football Field	SSHS-B2926	DUP-08	11/5/2019	855.61	4 - 6 ft	180-98355-3	Excavated	5600	1.7 J	3.2	270	0.31 J	0.18 J	18000	14 J+		5.6 J	200	69000 J	180 J	1800	1100 J
Football Field	SSHS-B2926	SSHS-B2926-SUB-4-6	11/5/2019	855.61	4 - 6 ft	180-98355-1	Excavated	6500	0.59 J	5.3	250	0.25 J	0.28 J	23000	13		5.1 J	200	28000 J	100 J	2900	350 J
Football Field	SSHS-B2928	SSHS-B2928-SUB-2-4	11/5/2019	855.83	2 - 4 ft	180-98355-1	Excavated	8700	2.5 J-	11	700	0.49	0.5 J	13000	20		6.9	110 J-	27000	1800	4300 J-	520
Football Field	SSHS-B2928	SSHS-B2928-SUB-4-6	11/5/2019	855.83	4 - 6 ft	180-98355-1	Excavated	9000	0.71 J	10	260	0.46	0.4 J	5300	17		7	56	22000	280	2700	540
Football Field	SSHS-B2929	DUP-10	11/4/2019	855.22	2 - 4 ft	180-98355-3	Excavated	12000	0.41 J	6.5	77	0.51	< 0.04 UJ	950 J	13 J+		9.1	15	19000	16	2800	430 J+
Football Field	SSHS-B2929	SSHS-B2929-SUB-2-4	11/4/2019	855.22	2 - 4 ft	180-98355-1	Excavated	12000	0.41 J	6.3	110	0.5	0.13 J	1600 J	13		7.8	14	19000	14	2800	640
Football Field	SSHS-B2930	SSHS-B2930-SUB-2-4	11/7/2019	855.06	2 - 4 ft	180-98520-1	Excavated	9200	0.64 J	6.3	190	0.43	0.067 J	4700	12 J+		7.1	23	20000	130	2700	390 J+
Football Field	SSHS-B2931	SSHS-B2931-SUB-4-6	11/6/2019	856.02	4 - 6 ft	180-98355-3	Excavated	6400	43	9.8	91	0.43	0.29 J	2700	18 J+		12	520	53000	270	1200	870 J+
Football Field	SSHS-B2932	SSHS-B2932-SUB-4-6	11/6/2019	855.47	4 - 6 ft	180-98355-3	Excavated	7800	6.7	12	120	0.49	0.17 J	8800	17 J+		9.2	85	37000	380	1900	630 J+
Football Field	SSHS-B2933	SSHS-B2933-SUB-4-6	11/6/2019	855.61	4 - 6 ft	180-98355-3	Excavated	13000	6.8 J-	140 J+	220 J+	1.1	0.8	23000	21 J+		13	570	34000	260 J-	5300 J-	500 J+
Football Field	SSHS-B2934	SSHS-B2934-SUB-8-10	11/5/2019	856.64	8 - 10 ft	180-98355-2	Excavated	12000	< 0.36 U	5.5	44	0.41 J	0.14 J	970	14		7.9	21	22000	8.7	3300	320
Football Field	SSHS-B2935	SSHS-B2935-SUB-8-10	11/5/2019	857.04	8 - 10 ft	180-98355-2	Excavated	4900	5.3	8.9	3700	0.24 J	5.8	78000	22		3.3 J	41	28000	570	25000	890
Football Field	SSHS-B2936	SSHS-B2936-SUB-8-10	11/5/2019	856.94	8 - 10 ft	180-98355-1	Not Excavated	9400	0.43 J	7.1	78	0.4 J	0.2 J	760	12		7.3	26	21000	11	2400	500
Football Field	SSHS-B2937	SSHS-B2937-SUB-8-10	11/5/2019	856.90	8 - 10 ft	180-98355-1	Not Excavated	8300	< 0.36 U	4.5	50	0.3 J	0.12 J	1200	10		4.8 J	41	15000	8.9	2100	500
Football Field	SSHS-B2942	DUP-11	11/5/2019	855.26	6 - 8 ft	180-98355-3	Not Excavated	10000	< 0.38 UJ	6.2	95	0.42 J	< 0.041 UJ	2400	17 J+		7.4	41	21000	42 J	2700	620 J
Football Field	SSHS-B2942	SSHS-B2942-SUB-6-8	11/5/2019	855.26	6 - 8 ft	180-98355-2	Not Excavated	9900	0.46 J	8.7	70 J	0.41	0.2 J	3300 J+	14		6.5	28 J+	19000	20 J	2600 J-	350 J
Football Field	SSHS-B2960	SSHS-B2960-SUB-10-12	11/7/2019	855.17	10 - 12 ft	180-98520-1	Excavated	7900	1.1	12	100	0.37 J	0.16 J	30000	12 J+		7	43	24000	50	5700	490 J+
Football Field	SSHS-B2963	DUP-14	11/5/2019	855.27	2 - 4 ft	180-98355-3	Excavated	6400	2.3	7.6	190 J	0.46	0.048 J	3100	15 J+		8.3	56	26000	100	1500	370 J+
Football Field	SSHS-B2963	SSHS-B2963-SUB-2-4	11/5/2019	855.27	2 - 4 ft	180-98355-1	Excavated	9500	1.4	11	100 J	0.52	0.3 J	4500	18		9.2	68	26000	90	2300	370
Football Field	SSHS-B2964	SSHS-B2964-SUB-10-12	11/7/2019	854.90	10 - 12 ft	180-98520-1	Excavated	7100	0.53 J	4.9	44	0.3 J	0.065 J	38000	9.9 J+		6.1	22	16000	8.7	8000	450 J+
Football Field	SSHS-B2965	SSHS-B2965-SUB-10-12	11/7/2019	854.88	10 - 12 ft	180-98520-1	Excavated	7800	< 0.33 U	4.4	44	0.34 J	< 0.035 U	1800	11 J+		6.6	30	17000	11	2400	460 J+
Football Field	SSHS-B2966	SSHS-B2966-SUB-4-6	11/5/2019	855.41	4 - 6 ft	180-98355-1	Excavated	11000	3.9	6.1	200	0.47	3.8	4900	100		6.9	1300	17000	57	1900	1300
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated	4400	< 0.94 U	4.3	32	0.18 J	0.039 J	40000	7.2 J+		4.5 J	15	10000	8.6	5100	450 J+
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated	9800	0.77 J	7.6	130	0.44	0.075 J	9700	15 J+		8.1	100	23000	76	4900	550 J+
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated	6900	0.47 J	6.7	75	0.29 J	0.099 J	54000	10 J+		6.2	56	15000	31	6600	540 J+
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated			5.7	92.4	< 0.61 U	< 0.61 U		23.5			27.4		31.8		
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-10-12	9/3/2019	855.74	10 - 12 ft	180-95155-1	Not Excavated	6000	< 0.37 U	5.6	45	0.25 J	0.14 J	80000	9.8		5.6	22	14000	7	8000	510
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	5600	< 0.36 U	4.5	48	0.21 J	0.087 J	34000	12		4.8 J	22	13000	11	8200	410
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-2-4	9/3/2019	853.35	2 - 4 ft	180-95155-1	Not Excavated	6500	0.48 J	7	74	0.32 J	0.095 J	5200	9.5		5 J	21	15000	28	1800	440
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-4-6	9/3/2019	853.35	4 - 6 ft	180-95155-1	Not Excavated	5700	< 0.34 UJ	5.1	39	0.24 J	0.085 J	26000	10		5	25	13000	26	5000	430
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-6-8	9/3/2019	853.35	6 - 8 ft	180-95155-1	Not Excavated	6800	< 0.4 U	4.9	47	0.24 J	0.087 J	35000	10		5.6 J	23	16000	11	8800	540
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-8-10	9/3/2019	853.35	8 - 10 ft	180-95155-1	Not Excavated	5100	< 0.35 U	4.2	42	0.19 J	0.11 J	46000	8.8		4.4 J	18	11000	11	15000	470
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	11000	1.1 J	9.5	110	0.54	0.13 J	3600	15		7.0	25	18000	32	2300	430
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	11000	1.1 J	12	140	0.62	0.16 J	5200	15		7.4	32	21000	46	2400	440
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-2-4	9/3/2019	853.09	2 - 4 ft	180-95155-1	Excavated	7000	1.1	9.1	91	0.45	0.83	12000	22		7	120	30000	59	5600	360
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	5900	0.95 J	8.1	79	0.29 J	0.55	22000	21		6.1	85	29000	56	5700	390
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-4-6	9/3/2019	853.09	4 - 6 ft	180-95155-1	Not Excavated	6300	< 0.37 UJ	6.1	55	0.32 J	0.37 J	30000 J	13		5.9	43	18000	23	7300 J	400
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-6-8	9/3/2019	853.09	6 - 8 ft	180-95155-1	Not Excavated	5300	< 0.37 U	5.8	45	0.23 J	0.34 J	49000	11		5.2 J	41	17000	19	9100	490
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-8-10	9/3/2019	853.09	8 - 10 ft	180-95155-1	Not Excavated	4800	< 0.37 U	5.2	39	0.19 J	0.18 J	47000	7.7		4.7 J	29	14000	15	7200	390
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-10-12	8/30/2019	851.95	10 - 12 ft	180-95047-3	Not Excavated	5900	1 J	7.9	56	0.39 J	0.42 J	26000	35 J		6.4	100 J	34000 J	38 J	7200 J	500
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	6600	0.6 J	6.7	59	0.31 J	0.31 J	48000	20		6.8	83	27000	41	15000	500
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-2-4	8/30/2019	851.95	2 - 4 ft	180-95047-3	Not Excavated	4600	0.59 J	6.1	39	0.33 J	0.32 J	43000	20		5.2 J	79 J	22000	28	18000	430
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-4-6	8/30/2019	851.95	4 - 6 ft	180-95047-3	Not Excavated	4900	< 0.36 U	3.2	41	0.21 J	0.11 J	43000	6.3		4.3 J	16	11000	4.2	8500	340
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-6-8	8/30/2019	851.95	6 - 8 ft	180-95047-3	Not Excavated	5600	1.4	9.9	62	0.47	0.77	38000	39		7.7	250	53000	67	8100	760
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-8-10	8/30/2019	851.95	8 - 10 ft	180-95047-3	Not Excavated	6100	1.6	16	90	0.4 J	0.78	43000	49		8.4	210	55000	79	4100	660
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	7300	< 0.36 U	4.7	65	0.27 J	0.22 J	25000	13		6	31	17000	13	7200	480
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-2-4	8/29/2019	852.25	2 - 4 ft	180-94981-2	Not Excavated	7100	1 J	13	84	0.46	0.59	3700	19		8.1	140	27000	98	2200	410
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-4-6	8/29/2019	852.25	4 - 6 ft	180-94981-2	Not Excavated	7100	< 0.35 U	5	45	0.25 J	0.18 J	28000	10		6.4	29	17000	12	6100	420
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-6-8	8/29/2019	852.25	6 - 8 ft	180-94981-2	Not Excavated	6600	< 0.37 UJ	5.6	45 J-	0.31 J	0.46 J	41000	11		6.6	40 J-	15000	21 J-	11000 J	550
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-8-10	8/29/2019	852.25	8 - 10 ft	180-94981-2	Not Excavated	5900	< 0.36 U	4.3	45	0.23 J	0.2 J	50000	11		5.3 J	27	13000	12	12000	410
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-10-12	8/29/2019	852.31	10 - 12 ft	180-94981-3	Not Excavated	6900	< 0.35 U	4.5	430	0.27 J	0.079 J	49000	11		5.7	21	16000	7.6	9500	390
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	7200	< 0.36 U	5.1	370	0.27 J	0.085 J	42000	12		5.7	19	16000	12	14000	430
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-2-4	8/29/2019	852.31	2 - 4 ft	180-94981-3	Not Excavated	7600	< 0.38 U	6.8	54	0.37 J	0.16 J	15000	11		7.3	23	18000	18	6000	590
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-4-6	8/29/2019	852.31	4 - 6 ft	180-94981-3	Not Excavated	6300	< 0.37 U	5.2	42	0.27 J	0.12 J	49000	9.2		6.5	20	16000	10	19000 J	390
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-6-8	8/29/2019	852.31	6 - 8 ft	180-94981-3	Not Excavated	4800	< 0.36 U	4.3	62	0.21 J	0.14 J	41000	8.1		4.9 J	14	12000	8	8300	360
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-8-10	8/29/2019	852.31	8 - 10 ft	180-94981-3	Not Excavated	5700	< 0.36 U	5	1200	0.2 J	0.096 J	49000	8		4.8 J	18	13000	8	12000	330
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-10-12	8/27/2019	852.36	10 - 12 ft	180-94829-1	Not Excavated	6100	< 0.35 U	4.6	45	0.22 J	0.19 J	62000	9.5		5.4	21	14000	8.1	11000	420
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	7100	< 0.35 U	5	43	0.28 J	0.11 J	35000	17		6.1	22	17000	12	6700	430
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-2-4	8/27/2019	852.36	2 - 4 ft	180-94824-3	Not Excavated	6700	< 0.36 U	6.2	35	0.32 J	0.12 J	7600 J	8.6		6.6	16	17000	11	4600	410
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-4-6	8/27/2019	852.36	4 - 6 ft	180-94824-3	Not Excavated	6400	0.53 J	4.5	43	0.24 J	0.11 J	37000	9.3		6	19	15000	8.9	4900	400
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-6-8	8/27/2019	852.36	6 - 8 ft	180-94824-3	Not Excavated	6100	< 0.36 U	4.9	41	0.25 J	0.12 J	82000	10		5.4	19	14000	8.8	20000	360
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-8-10	8/27/2019	852.36	8 - 10 ft	180-94824-3	Not Excavated	7300	< 0.35 U	4.7	46	0.29 J	0.1 J	38000	12		6.4	23	17000	12	8900	380
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-10-12	8/27/2019	852.58	10 - 12 ft	180-94824-3	Not Excavated	7600	0.71 J	7.6	92	0.36 J	0.16 J	3700	17		6.4	42	20000	97	2200	510
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	6600	< 0.37 UJ	6.1	65	0.26 J	0.16 J	18000	20		5.8	31	17000	59 J+	2800	620
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-2-4	8/27/2019	852.58	2 - 4 ft	180-94824-3	Not Excavated	7600	3.7	13	110	0.45	0.22 J	4100	26		7.1	55	29000	370	1600	350
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-4-6	8/27/2019	852.58	4 - 6 ft	180-94824-3	Not Excavated	8700	0.84 J	8.4	130	0.39 J	0.22 J	3300	40		6.4	38	25000	95	1700	800
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-6-8	8/27/2019	852.58	6 - 8 ft	180-94824-3	Not Excavated	8900	0.75 J	7.6	87	0.4 J	0.18 J	2700	15		6.5	42	22000	92	2100	450
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-8-10	8/27/2019	852.58	8 - 10 ft	180-94824-3	Not Excavated	7300	0.69 J	7.2	74	0.33 J	0.13 J	2000	16		6.8	32	20000	69	2100	480
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-10-12	8/26/2019	852.37	10 - 12 ft	180-94752-1	Not Excavated	6900	0.72 J	6.3	71	0.3 J	0.23 J	19000 J	19		6.3	30	17000	32	3400	510

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	0.043	18	560	< 0.58 U	< 0.12 U	62 J		< 0.36 U		14	61
Football Field	SSHS-B2804	SSHS-B2804-SUB-4-6	5/19/2019	855.74	4 - 6 ft	180-90323-1	Excavated	0.053	13	790	0.72 J	< 0.12 U	320 J		< 0.37 U		17	60
Football Field	SSHS-B2805	PS-FD-11	5/16/2019	856.47	8 - 10 ft	180-90231-1	Not Excavated	0.032 J	16	750	< 0.59 U	< 0.12 U	570 U		< 0.37 U		12	73
Football Field	SSHS-B2805	SSHS-B2805-SUB-8-10	5/16/2019	856.47	8 - 10 ft	180-90231-1	Not Excavated	0.022 J	13	650	< 0.6 U	< 0.12 U	580 U		< 0.37 U		11	54
Football Field	SSHS-B2926	SSHS-B2926-SUB-2-4	11/5/2019	855.61	2 - 4 ft	180-98355-1	Excavated	0.089	930	590	3.3	0.17 J	170 J		< 0.35 U		18 J	580
Football Field	SSHS-B2926	DUP-08	11/5/2019	855.61	4 - 6 ft	180-98355-3	Excavated	0.051	47	670	< 0.6 UJ	< 0.12 U	320 J		< 0.75 U		27 J	150
Football Field	SSHS-B2926	SSHS-B2926-SUB-4-6	11/5/2019	855.61	4 - 6 ft	180-98355-1	Excavated	0.057	51	640	0.91 J	< 0.11 U	230 J		< 0.34 U		12 J	130
Football Field	SSHS-B2928	SSHS-B2928-SUB-2-4	11/5/2019	855.83	2 - 4 ft	180-98355-1	Excavated	0.039	130 J-	860	0.64 J	< 0.11 U	160 J		< 0.34 U		16	140
Football Field	SSHS-B2928	SSHS-B2928-SUB-4-6	11/5/2019	855.83	4 - 6 ft	180-98355-1	Excavated	0.027 J	110	750	< 0.59 U	< 0.12 U	100 J		< 0.37 U		16	97
Football Field	SSHS-B2929	DUP-10	11/4/2019	855.22	2 - 4 ft	180-98355-3	Excavated	0.016 J	15	910	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		19	51
Football Field	SSHS-B2929	SSHS-B2929-SUB-2-4	11/4/2019	855.22	2 - 4 ft	180-98355-1	Excavated	0.019 J	16	850	< 0.6 U	< 0.12 U	< 71 U		< 0.38 U		18	54
Football Field	SSHS-B2930	SSHS-B2930-SUB-2-4	11/7/2019	855.06	2 - 4 ft	180-98520-1	Excavated	0.038	16	740	< 0.48 U	< 0.099 U	< 57 U		< 0.3 U		15	65
Football Field	SSHS-B2931	SSHS-B2931-SUB-4-6	11/6/2019	856.02	4 - 6 ft	180-98355-3	Excavated	0.88	19	1200	< 0.56 U	0.22 J	110 J		< 0.35 U		32	200
Football Field	SSHS-B2932	SSHS-B2932-SUB-4-6	11/6/2019	855.47	4 - 6 ft	180-98355-3	Excavated	0.053	14	1200	0.71 J	< 0.12 U	240 J		< 0.37 U		32	130
Football Field	SSHS-B2933	SSHS-B2933-SUB-4-6	11/6/2019	855.61	4 - 6 ft	180-98355-3	Excavated	0.058 J+	29	2100 J-	3.7	< 0.16 U	270 J		1 J		48	410
Football Field	SSHS-B2934	SSHS-B2934-SUB-8-10	11/5/2019	856.64	8 - 10 ft	180-98355-2	Excavated	0.018 J	20	580	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U		15	55
Football Field	SSHS-B2935	SSHS-B2935-SUB-8-10	11/5/2019	857.04	8 - 10 ft	180-98355-2	Excavated	0.06	52	730	1.4	< 0.13 U	250 J		< 0.39 U		9.7	1000
Football Field	SSHS-B2936	SSHS-B2936-SUB-8-10	11/5/2019	856.94	8 - 10 ft	180-98355-1	Not Excavated	< 0.017 U	18	950	< 0.55 U	< 0.11 U	250 J		< 0.34 U		15	65
Football Field	SSHS-B2937	SSHS-B2937-SUB-8-10	11/5/2019	856.90	8 - 10 ft	180-98355-1	Not Excavated	< 0.015 U	13	740	< 0.55 U	< 0.11 U	140 J		< 0.34 U		11	43
Football Field	SSHS-B2942	DUP-11	11/5/2019	855.26	6 - 8 ft	180-98355-3	Not Excavated	< 0.016 UJ	54 J	750	< 0.58 U	< 0.12 U	< 67 U		< 0.36 U		16	79
Football Field	SSHS-B2942	SSHS-B2942-SUB-6-8	11/5/2019	855.26	6 - 8 ft	180-98355-2	Not Excavated	0.028 J	29 J	820	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		15	57 J+
Football Field	SSHS-B2960	SSHS-B2960-SUB-10-12	11/7/2019	855.17	10 - 12 ft	180-98520-1	Excavated	< 0.024 U	16	740	< 0.51 U	< 0.1 U	130 J		< 0.32 U		19	94
Football Field	SSHS-B2963	DUP-14	11/5/2019	855.27	2 - 4 ft	180-98355-3	Excavated	0.06	42	580	< 0.59 UJ	< 0.12 U	120 J		< 0.37 U		17	62
Football Field	SSHS-B2963	SSHS-B2963-SUB-2-4	11/5/2019	855.27	2 - 4 ft	180-98355-1	Excavated	0.043	51	800	0.62 J	< 0.11 U	160 J		< 0.35 U		16	72
Football Field	SSHS-B2964	SSHS-B2964-SUB-10-12	11/7/2019	854.90	10 - 12 ft	180-98520-1	Excavated	< 0.024 U	14	740	< 0.52 U	< 0.11 U	67 J		< 0.32 U		12	65
Football Field	SSHS-B2965	SSHS-B2965-SUB-10-12	11/7/2019	854.88	10 - 12 ft	180-98520-1	Excavated	0.028 J	16	750	< 0.5 U	< 0.1 U	< 59 U		< 0.31 U		13	67
Football Field	SSHS-B2966	SSHS-B2966-SUB-4-6	11/5/2019	855.41	4 - 6 ft	180-98355-1	Excavated	0.16	20	860	3.9	< 0.12 U	200 J		< 0.38 U		40	1500
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated	< 0.034 U	9.4	460 J	< 0.94 U	< 0.47 U	83 J		< 1.9 U		7.8	44
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated	0.024 J	39	840	< 0.51 U	< 0.1 U	110 J		< 0.32 U		17	86
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated	< 0.025 U	25	730	< 0.51 U	< 0.1 U	100 J		< 0.32 U		12	56
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft		Excavated	0.11	13.3		< 0.61 U	< 1.2 U						75.5
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-10-12	9/3/2019	855.74	10 - 12 ft	180-95155-1	Not Excavated	< 0.014 U	14	910	1.1	< 0.11 U	98 J		< 0.35 U		10	49
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	< 0.013 U	12	840	< 0.55 U	< 0.11 U	84 J		< 0.34 U		10	49
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-2-4	9/3/2019	853.35	2 - 4 ft	180-95155-1	Not Excavated	0.051	12	650	< 0.61 U	< 0.12 U	65 J		< 0.38 U		12	61
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-4-6	9/3/2019	853.35	4 - 6 ft	180-95155-1	Not Excavated	0.015 J	12	740	< 0.52 U	< 0.11 U	67 J		< 0.32 U		9.9	49
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-6-8	9/3/2019	853.35	6 - 8 ft	180-95155-1	Not Excavated	< 0.014 U	14	760	< 0.6 U	< 0.12 U	81 J		< 0.37 U		10	58
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-8-10	9/3/2019	853.35	8 - 10 ft	180-95155-1	Not Excavated	< 0.015 U	12	670	< 0.54 U	< 0.11 U	94 J		< 0.33 U		8.2	42
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	0.073	18	780	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U		15	59
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	0.085	19	850	1.1 J	< 0.12 U	< 71 U		< 0.38 U		17	70
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-2-4	9/3/2019	853.09	2 - 4 ft	180-95155-1	Excavated	0.25	59	640	< 0.52 U	< 0.11 U	100 J		< 0.33 U		14	140
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	0.12	30	660	0.65 J	< 0.11 U	92 J		< 0.33 U		12	120
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-4-6	9/3/2019	853.09	4 - 6 ft	180-95155-1	Not Excavated	0.027 J	50 J	810	0.97 J	< 0.11 U	74 J		< 0.35 U		11	100 J
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-6-8	9/3/2019	853.09	6 - 8 ft	180-95155-1	Not Excavated	0.059	28	620	0.71 J	< 0.11 U	99 J		< 0.35 U		9.2	98
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-8-10	9/3/2019	853.09	8 - 10 ft	180-95155-1	Not Excavated	0.037	20	580	0.88 J	< 0.11 U	68 J		< 0.35 U		7.8	83
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-10-12	8/30/2019	851.95	10 - 12 ft	180-95047-3	Not Excavated	0.044	36	680	0.64 J	< 0.11 U	78 J		< 0.35 U		11	130
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	0.035	29	750	0.91 J	< 0.12 U	96 J		< 0.36 U		11	96
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-2-4	8/30/2019	851.95	2 - 4 ft	180-95047-3	Not Excavated	0.042 J	27	740	0.67 J	< 0.11 U	73 J		< 0.35 U		8.1	98
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-4-6	8/30/2019	851.95	4 - 6 ft	180-95047-3	Not Excavated	< 0.014 U	11	680	0.68 J	< 0.11 U	76 J		< 0.34 U		7.8	42
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-6-8	8/30/2019	851.95	6 - 8 ft	180-95047-3	Not Excavated	0.12	85	620	0.89 J	< 0.12 U	95 J		< 0.37 U		11	230
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-8-10	8/30/2019	851.95	8 - 10 ft	180-95047-3	Not Excavated	0.098	53	680	1.5	< 0.12 U	94 J		< 0.37 U		12	170
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	0.28	19	760	0.57 J	< 0.11 U	100 J		< 0.34 U		11	140
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-2-4	8/29/2019	852.25	2 - 4 ft	180-94981-2	Not Excavated	0.25	31	820	1 J	< 0.12 U	70 J		< 0.37 U		17	290
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-4-6	8/29/2019	852.25	4 - 6 ft	180-94981-2	Not Excavated	0.36	17	750	0.73 J	< 0.11 U	74 J		< 0.33 U		11	100
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-6-8	8/29/2019	852.25	6 - 8 ft	180-94981-2	Not Excavated	0.81	23	830	1.1	< 0.11 U	85 J		< 0.35 U		12	300
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-8-10	8/29/2019	852.25	8 - 10 ft	180-94981-2	Not Excavated	0.16	15	730	0.9 J	< 0.11 U	160 J		< 0.34 U		9	100
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-10-12	8/29/2019	852.31	10 - 12 ft	180-94981-3	Not Excavated	< 0.013 U	15	770	< 0.53 U	< 0.11 U	89 J		< 0.33 U		11	61
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	< 0.014 U	15	850	< 0.55 UJ	< 0.11 U	99 J		< 0.34 U		11	60
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-2-4	8/29/2019	852.31	2 - 4 ft	180-94981-3	Not Excavated	0.02 J	19	950	< 0.57 U	< 0.12 U	64 J		< 0.36 U		14	70
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-4-6	8/29/2019	852.31	4 - 6 ft	180-94981-3	Not Excavated	0.013 J	16	730	1.3 J	< 0.12 U	94 J		< 0.35 U		11	57
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-6-8	8/29/2019	852.31	6 - 8 ft	180-94981-3	Not Excavated	< 0.014 U	12	680	1	< 0.11 U	72 J		< 0.34 U		8.8	86
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-8-10	8/29/2019	852.31	8 - 10 ft	180-94981-3	Not Excavated	< 0.014 U	12	650	1.1	< 0.11 U	83 J		< 0.34 U		9	52
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-10-12	8/27/2019	852.36	10 - 12 ft	180-94829-1	Not Excavated	0.047	14	750	0.9 J	< 0.11 U	92 J		< 0.33 U		9.4	54
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	0.037	16	830	< 0.53 U	< 0.11 U	94 J		< 0.33 U		12	66
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-2-4	8/27/2019	852.36	2 - 4 ft	180-94824-3	Not Excavated	< 0.013 UJ	15	690	< 0.54 U	< 0.11 U	58 J		< 0.34 U		12	50
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-4-6	8/27/2019	852.36	4 - 6 ft	180-94824-3	Not Excavated	0.018 J	15	630	< 0.52 U	< 0.11 U	73 J		< 0.33 U		9.9	80
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-6-8	8/27/2019	852.36	6 - 8 ft	180-94824-3	Not Excavated	0.029 J	14	890	0.85 J	< 0.11 U	110 J		< 0.34 U		10	42
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-8-10	8/27/2019	852.36	8 - 10 ft	180-94824-3	Not Excavated	0.046	17	820	0.76 J	< 0.11 U	87 J		< 0.33 U		12	58
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-10-12	8/27/2019	852.58	10 - 12 ft	180-94824-3	Not Excavated	0.26	17	600	0.68 J	< 0.11 U	97 J		< 0.33 U		14	97
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	0.16	14	630	< 0.57 U	< 0.12 U	94 J		< 0.35 U		12	87
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-2-4	8/27/2019	852.58	2 - 4 ft	180-94824-3	Not Excavated	0.4	32	670	0.77 J	< 0.12 U	210 J		< 0.36 U		18	89
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-4-6	8/27/2019	852.58	4 - 6 ft	180-94824-3	Not Excavated	0.12	16	540	0.6 J	< 0.11 U	100 J		< 0.34 U		17	140
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-6-8	8/27/2019	852.58	6 - 8 ft	180-94824-3	Not Excavated	0.096	16	630	< 0.55 U	< 0.11 U	120 J		< 0.34 U		16	100
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-8-10	8/27/2019	852.58	8 - 10 ft	180-94824-3	Not Excavated	0.11	17	600	< 0.53 U	< 0.11 U	79 J		< 0.33 U		13	82
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-10-12	8/26/2019	852.37	10 - 12 ft	180-94752-1	Not Excavated	0.2	63	810	0.64 J	< 0.11 U	95 J		< 0.34 U		15	70

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	7300	2.3	7.3	75	0.34 J	0.27 J	7600	51		6.2	30	19000	49	3200	510
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-2-4	8/26/2019	852.37	2 - 4 ft	180-94752-1	Not Excavated	7400	1.8 J	8.8	75	0.38 J	0.27 J	29000	40		7	33	26000	69	13000	450
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-4-6	8/26/2019	852.37	4 - 6 ft	180-94752-1	Not Excavated	9100	1.6	10	95	0.49	0.19 J	15000	13		7.3	47	29000	76	2500	950
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-6-8	8/26/2019	852.37	6 - 8 ft	180-94752-1	Not Excavated	12000	0.82 J	7.8	130	0.46	0.17 J	6400 J-	24		7.3	22	20000	37 J	3000	620
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-8-10	8/26/2019	852.37	8 - 10 ft	180-94752-1	Not Excavated	9000	0.88 J	5.3	67	0.36 J	0.16 J	4400	21		5.8	20	18000	24	2900	460
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-10-12	9/3/2019	853.88	10 - 12 ft	180-95155-3	Not Excavated	5700	< 0.36 U	5.2	36	0.23 J	0.1 J	29000	8.8		5.3	17	14000	6	5000	350
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	3900	< 0.38 U	2.7	24	0.16 J	0.074 J	27000	6.4		3.5 J	11	9900	3.5	3900	240
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-2-4	9/3/2019	853.88	2 - 4 ft	180-95155-3	Not Excavated	8400	< 0.37 U	7.5	60	0.37 J	0.078 J	2100	10		7.6	24	19000	8.5	3000	440
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-4-6	9/3/2019	853.88	4 - 6 ft	180-95155-3	Not Excavated	5400	< 0.38 UJ	6.2	35	0.26 J	0.088 J	11000	7.8		5.2 J	19	14000	8.1	8000 J-	550
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-6-8	9/3/2019	853.88	6 - 8 ft	180-95155-3	Not Excavated	5300	< 0.34 U	4.1	29	0.25 J	0.11 J	38000	7.5		5 J	15	12000	5.7	4600	350
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-8-10	9/3/2019	853.88	8 - 10 ft	180-95155-3	Not Excavated	4300	< 0.35 U	3.3	30	0.18 J	0.075 J	31000	5.9		4.1 J	13	10000	4.2	2600	310
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-10-12	9/3/2019	854.13	10 - 12 ft	180-95155-2	Not Excavated	5600	< 0.36 U	5.8	59	0.2 J	0.11 J	37000	7.6		5.1 J	20	14000	6	6900	720
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	6100	< 0.4 U	5.5	49	0.28 J	0.22 J	21000	9		5.6 J	20	14000	14	6200	1000
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-4-6	9/3/2019	854.13	4 - 6 ft	180-95155-2	Not Excavated	4900	< 0.4 U	6	28	0.21 J	0.085 J	41000	6.8		4.8 J	36	12000	8.8	22000	410
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-6-8	9/3/2019	854.13	6 - 8 ft	180-95155-2	Not Excavated	4700	< 0.4 U	4.3	25	0.2 J	0.083 J	22000	7		4.3 J	16	12000	6.3	12000	390
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-8-10	9/3/2019	854.13	8 - 10 ft	180-95155-2	Not Excavated	5500	< 0.37 UJ	3.5	32 J	0.22 J	0.17 J	85000	7.3		4.8 J	19	12000	5	4900	370
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-10-12	8/30/2019	853.85	10 - 12 ft	180-95050-1	Not Excavated	5400	< 0.38 U	5.3	36	0.21 J	0.081 J	29000	8.2		4.7 J	16	13000	6.5	3900	340
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	6400	0.52 J	6.7	48	0.29 J	0.11 J	5600	9.6		6.2	21	17000	9.2	2800	490
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-2-4	8/30/2019	853.85	2 - 4 ft	180-95047-3	Not Excavated	11000	0.81 J	9.1	60	0.51	0.05 J	1200	14		7.5	40	23000	10	2600	620
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-4-6	8/30/2019	853.85	4 - 6 ft	180-95047-3	Not Excavated	12000	0.68 J	9	76	0.62	0.069 J	1500	16		12	29	26000	14	3800	690
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-6-8	8/30/2019	853.85	6 - 8 ft	180-95047-3	Not Excavated	6600	0.41 J	5.4	56	0.24 J	0.072 J	1300	8.1		5.6	19	17000	9	2100	590
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-8-10	8/30/2019	853.85	8 - 10 ft	180-95047-3	Not Excavated	6500	0.45 J	6	57	0.28 J	0.1 J	23000	11		6.1	24	16000	8.7	6000	520
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-10-12	8/30/2019	853.28	10 - 12 ft	180-95047-2	Excavated	4700	< 0.36 U	4.5	33	0.23 J	0.11 J	24000	6.5		4.7 J	16	11000	7.3	5700	220
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-2-4	8/30/2019	853.28	2 - 4 ft	180-95047-2	Excavated	11000	0.45 J	6.4	89	0.49	0.094 J	1300	14		7.8	17	17000	11	2500	430
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-4-6	8/30/2019	853.28	4 - 6 ft	180-95047-2	Excavated	5300	< 0.37 U	3.5	38	0.19 J	0.095 J	58000	7		4.2 J	18	12000	20	6900	350
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-6-8	8/30/2019	853.28	6 - 8 ft	180-95047-2	Excavated	5000	< 0.35 U	4.1	54	0.21 J	0.075 J	78000	6		4 J	22	11000	24	15000	280
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-8-10	8/30/2019	853.28	8 - 10 ft	180-95047-2	Excavated	5600	< 0.36 U	4.7	44	0.22 J	0.098 J	33000	9.4		5.1 J	20	13000	8.8	6300	520
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	6000	< 0.41 U	5.9	47	0.28 J	0.11 J	41000	8.7		5.4 J	24	14000	13	11000	420
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-2-4	8/29/2019	852.90	2 - 4 ft	180-94981-1	Excavated	9000	< 0.37 U	5.9	68	0.38 J	0.064 J	13000	12		7.8	29	19000	7.6	5200	560
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-4-6	8/29/2019	852.90	4 - 6 ft	180-94981-1	Excavated	5400	< 0.34 U	4.9	54	0.19 J	0.092 J	66000	6.3		5.2	13	13000	4.7	12000	530
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-6-8	8/29/2019	852.90	6 - 8 ft	180-94981-1	Excavated	4400	< 0.35 U	4.9	44	0.19 J	0.064 J	69000	6.4		4.6 J	18	10000	8.2	19000	450
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-10-12	8/29/2019	852.90	10 - 12 ft	180-94981-1	Not Excavated	5900	< 0.36 U	4.1	57	0.23 J	0.087 J	59000	10		5.2 J	17	14000	5.9	11000	440
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	5500	< 0.36 U	5.1	61	0.22 J	0.064 J	46000	12		5.2 J	17	14000	6.3	8400 J-	490
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-8-10	8/29/2019	852.90	8 - 10 ft	180-94981-1	Not Excavated	6500	< 0.35 U	4.8	67	0.27 J	0.089 J	40000	9.4		6.4	17	15000	6.8	9000	450
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	5000	< 0.36 U	5.5	68	0.18 J	0.11 J	36000	7.1		5.2 J	15	12000	11	10000	670
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-2-4	8/29/2019	853.35	2 - 4 ft	180-94981-2	Excavated	5900	< 0.35 U	5.9	49	0.28 J	0.14 J	77000	8.7		6.7 J	18	14000	7.9 J	13000	500
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-4-6	8/29/2019	853.35	4 - 6 ft	180-94981-2	Excavated	4800	< 0.34 U	3.2	110	0.2 J	0.097 J	71000	7.1		3.8 J	12	11000	4.3	24000	600
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-6-8	8/29/2019	853.35	6 - 8 ft	180-94981-2	Excavated	5800	< 0.35 U	3.8	74	0.22 J	0.11 J	43000	8.7		5.3	21	14000	5.8	17000	380
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-8-10	8/29/2019	853.35	8 - 10 ft	180-94981-2	Excavated	4900	< 0.38 U	4.5	89	0.19 J	0.086 J	62000	12		4.5 J	17	12000	5.2	22000	390
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	6100	< 0.36 U	4.4	51	0.22 J	0.1 J	43000	8.9		5.5	24	14000	5.7	16000	400
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-10-12	8/28/2019	853.51	10 - 12 ft	180-94902-3	Excavated	5400	< 0.36 U	4.3	51	0.19 J	0.096 J	51000	8.8		4.7 J	21	12000	7.1	15000	460
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-2-4	8/28/2019	853.51	2 - 4 ft	180-94902-3	Excavated	7700	0.42 J	6.4	83	0.34 J	0.082 J	1800	11		6.4	24	18000	7.6	2500	460
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-4-6	8/28/2019	853.51	4 - 6 ft	180-94902-3	Excavated	4300	< 0.36 U	3	37	0.19 J	0.11 J	56000	31		3.5 J	14	10000	5.6	20000	320
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-6-8	8/28/2019	853.51	6 - 8 ft	180-94902-3	Excavated	4700	< 0.38 U	3.1	42	0.18 J	0.3 J	56000	10		3.9 J	19	11000	7.6	19000	470
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-8-10	8/28/2019	853.51	8 - 10 ft	180-94902-3	Excavated	6300	< 0.37 U	4.4	60	0.23 J	0.065 J	45000	8.5		5.9	23	14000	5.5	11000	370
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	4600	< 0.35 U	3.4	56	0.17 J	0.097 J	51000	8.3		4.6 J	21	12000	4.8	5900	270
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	3900	< 0.34 U	3.7	57	0.15 J	0.096 J	70000	6.4		3.9 J	17	9900	4.4	8300	270
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated	5000	< 0.30 UT	5.3	58 T	0.19 J	0.13 J	37000 T	8.1		4.5	18	13000	9.0	6000 T	720
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-10-12	8/29/2019	853.54	10 - 12 ft	180-94981-2	Excavated	5300	< 0.34 U	4.8	39	0.21 J	0.12 J	40000	12		4.8 J	16	13000	11	6400	370
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-2-4	8/29/2019	853.54	2 - 4 ft	180-94981-2	Excavated	8700	< 0.39 U	9.5	46	0.4 J	0.12 J	1500	12		6.6	31	21000	22	2300	280
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-4-6	8/29/2019	853.54	4 - 6 ft	180-94981-2	Excavated	6900	< 0.44 U	5.1	44	0.26 J	0.081 J	25000	9.1		6.2 J	17	16000	8.2	8100	450
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-6-8	8/29/2019	853.54	6 - 8 ft	180-94981-2	Excavated	4200	< 0.38 U	4.4	31	0.18 J	0.06 J	30000	6.7		4.2 J	13	10000	4.6	6900	430
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-8-10	8/29/2019	853.54	8 - 10 ft	180-94981-2	Excavated	6800	< 0.34 U	4.8	41	0.25 J	0.11 J	45000	8.5		6.1	17	15000	8.4	7200	410
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	5600	< 0.37 U	4.4	52	0.2 J	0.11 J	33000	9.8		5.1 J	19	13000	7	7600	600
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-2-4	8/28/2019	853.78	2 - 4 ft	180-94900-2	Excavated	7400	< 0.39 U	6.2	40	0.32 J	< 0.042 U	590	9.3		6.2	19	17000	8	2000	460
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-4-6	8/28/2019	853.78	4 - 6 ft	180-94900-2	Excavated	5700	< 0.37 U	5.2	31	0.26 J	0.084 J	21000	8.3		5.4 J	15	13000	6.2	10000	380
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-6-8	8/28/2019	853.78	6 - 8 ft	180-94900-2	Not Excavated	4200	< 0.36 U	3	25	0.14 J	0.062 J	34000	6.1		3.8 J	18	10000	3.4	5400	260
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-8-10	8/28/2019	853.78	8 - 10 ft	180-94900-2	Not Excavated	7000	< 0.37 U	5.5	46	0.27 J	0.088 J	37000	10		6.5	20	15000	12	7300	500
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-10-12	8/27/2019	853.82	10 - 12 ft	180-94829-1	Not Excavated	7100	< 0.36 U	4.8	33	0.27 J	0.079 J	19000	11		6.4	19	15000	11 J	3000 J	460
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-2-4	8/27/2019	853.82	2 - 4 ft	180-94829-1	Not Excavated	8500	< 0.39 U	5.5	30	0.34 J	0.043 J	780	11		6.3	19	16000	8	2300	370
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-4-6	8/27/2019	853.82	4 - 6 ft	180-94829-1	Not Excavated	8900	0.39 J	6.7	53	0.36 J	0.065 J	920	12		7.9	22	20000	14	2800	420
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-6-8	8/27/2019	853.82	6 - 8 ft	180-94829-1	Not Excavated	8200	< 0.37 U	6.3	40	0.33 J	0.085 J	3600	11		7.4	23	17000	8.5	3200	380
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-8-10	8/27/2019	853.82	8 - 10 ft	180-94829-1	Not Excavated	5700	< 0.4 U	4.6	36	0.22 J	0.21 J	29000	7.6		5 J	16	13000	5.8	11000	450
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	6400	< 0.37 U	5.1	37	0.25 J	0.092 J	17000	9		5.7	21	15000	8.1	8800	420
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-2-4	8/27/2019	854.09	2 - 4 ft	180-94824-3	Excavated	6300	< 0.38 UJ	5.3	40	0.27 J	0.13 J	3000	8.8		5.9	22	15000	8.8	2400	680
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-4-6	8/27/2019	854.09	4 - 6 ft	180-94824-3	Excavated	5200	< 0.38 U	4.3	36	0.22 J	0.1 J	35000	8.6		5 J	18	12000	5.9	6900	370
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-10-12	8/27/2019	854.09	10 - 12 ft	180-94824-3	Not Excavated	5500	< 0.36 U	4.7	48	0.2 J	0.12 J	49000	11		5 J	17	13000	14	11000	380
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-6-8	8/27/2019	854.09	6 - 8 ft	180-94824-3	Not Excavated	6800	< 0.37 U	4.6	94	0.25 J	0.13 J	37000	10		5.7	23	17000	7.5	7800	500
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-8-10	8/27/2019	854.09	8 - 10 ft	180-94824-3	Not Excavated	6800	< 0.35 U	3.9	84	0.22 J	0.098 J	50000	8.7		5.5	23	15000	5.8	10000	370
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	6000	< 0.35 U	4.3	47	0.22 J	0.11 J	71000	11		5.5	21	14000	11	13000	480
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-2-4	8/27/2019	853.86	2 - 4 ft	180-94824-2	Excavated	7800	< 0.38 U	6.3	49	0.28 J	0.14 J	4700	10		7.1	20	19000	6.5	2500	1000
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-4-6	8/27/2019	853.86	4 - 6 ft	180-94824-2	Excavated	6400	< 0.38 U	6	39	0.26 J	0.098 J	21000	8.5		6.2	18	15000	8.2	8100	460
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-10-12	8/27/2019	853.86	10 - 12 ft	180-94824-2	Not Excavated	6100	< 0.35 U	4.3	59	0.23 J	0.089 J	47000	9		6.6	20	15000	5.9	7400	460
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-6-8	8/27/2019	853.86	6 - 8 ft	180-94824-2	Not Excavated	5800	< 0.35 U	4.6	34	0.23 J	0.11 J	43000	7.8		5.4	17	13000	5.1	4700	410

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	0.2	87	770	2.5	< 0.11 U	130 J		< 0.34 U		25	86
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-2-4	8/26/2019	852.37	2 - 4 ft	180-94752-1	Not Excavated	0.53	140	880	2.5	< 0.12 U	120 J		< 0.36 U		25	110
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-4-6	8/26/2019	852.37	4 - 6 ft	180-94752-1	Not Excavated	0.24	24	860	1.2	< 0.12 U	220 J		< 0.36 U		21	110
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-6-8	8/26/2019	852.37	6 - 8 ft	180-94752-1	Not Excavated	0.31 J	63	820	0.92 J	< 0.12 U	110 J		< 0.36 U		21	69 J+
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-8-10	8/26/2019	852.37	8 - 10 ft	180-94752-1	Not Excavated	0.27	44	720	0.64 J	< 0.12 U	120 J		< 0.35 U		17	60
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-10-12	9/3/2019	853.88	10 - 12 ft	180-95155-3	Not Excavated	< 0.014 U	13	700	< 0.55 U	< 0.11 U	68 J		< 0.34 U		9.4	47
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	< 0.015 U	8.9	480 J	< 0.58 U	< 0.12 U	54 J		< 0.36 U		6.8	37
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-2-4	9/3/2019	853.88	2 - 4 ft	180-95155-3	Not Excavated	< 0.016 U	18	740	< 0.56 U	< 0.11 U	41 J		< 0.35 U		12	69
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-4-6	9/3/2019	853.88	4 - 6 ft	180-95155-3	Not Excavated	< 0.016 U	12	660	< 0.58 U	< 0.12 U	66 J		< 0.36 U		9.6	49 J+
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-6-8	9/3/2019	853.88	6 - 8 ft	180-95155-3	Not Excavated	< 0.015 U	13	550	0.6 J	< 0.11 U	71 J		< 0.32 U		8.8	45
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-8-10	9/3/2019	853.88	8 - 10 ft	180-95155-3	Not Excavated	< 0.015 U	10	550	< 0.53 U	< 0.11 U	70 J		< 0.33 U		6.8	33
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-10-12	9/3/2019	854.13	10 - 12 ft	180-95155-2	Not Excavated	< 0.015 U	12	650	< 0.54 U	< 0.11 U	73 J		< 0.34 U		9.2	42
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	< 0.015 U	13	810	< 0.6 U	< 0.12 U	63 J		< 0.37 U		10	45
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-4-6	9/3/2019	854.13	4 - 6 ft	180-95155-2	Not Excavated	< 0.015 U	12	690	< 0.6 U	< 0.12 U	94 J		< 0.37 U		8.3	42
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-6-8	9/3/2019	854.13	6 - 8 ft	180-95155-2	Not Excavated	< 0.016 U	11	630	< 0.61 U	< 0.12 U	64 J		< 0.38 U		8.5	37
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-8-10	9/3/2019	854.13	8 - 10 ft	180-95155-2	Not Excavated	< 0.016 U	13	670	1.4	< 0.12 U	88 J		< 0.35 U		8.9	39
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-10-12	8/30/2019	853.85	10 - 12 ft	180-95050-1	Not Excavated	< 0.015 U	12	670	0.67 J	< 0.12 U	72 J		< 0.36 U		9.2	57
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	0.037	15	910	< 0.59 U	< 0.12 U	65 J		< 0.37 U		13	62
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-2-4	8/30/2019	853.85	2 - 4 ft	180-95047-3	Not Excavated	0.016 J	20	1100	< 0.61 U	< 0.12 U	39 J		< 0.38 U		18	63
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-4-6	8/30/2019	853.85	4 - 6 ft	180-95047-3	Not Excavated	0.029 J	33	1400	< 0.6 U	< 0.12 U	44 J		< 0.37 U		19	68
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-6-8	8/30/2019	853.85	6 - 8 ft	180-95047-3	Not Excavated	0.024 J	14	690	< 0.56 U	< 0.11 U	41 J		< 0.35 U		10	60
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-8-10	8/30/2019	853.85	8 - 10 ft	180-95047-3	Not Excavated	0.023 J	16	870	0.63 J	< 0.11 U	74 J		< 0.35 U		12	55
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-10-12	8/30/2019	853.28	10 - 12 ft	180-95047-2	Excavated	< 0.017 U	13	810	0.58 J	< 0.11 U	58 J		< 0.34 U		8.2	40
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-2-4	8/30/2019	853.28	2 - 4 ft	180-95047-2	Excavated	0.021 J	18	1000	< 0.58 U	< 0.12 U	38 J		< 0.36 U		15	50
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-4-6	8/30/2019	853.28	4 - 6 ft	180-95047-2	Excavated	< 0.015 U	11	660	0.66 J	< 0.12 U	75 J		< 0.35 U		8.1	47
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-6-8	8/30/2019	853.28	6 - 8 ft	180-95047-2	Excavated	< 0.016 U	10	660	1.1	< 0.11 U	84 J		< 0.33 U		7.4	43
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-8-10	8/30/2019	853.28	8 - 10 ft	180-95047-2	Excavated	< 0.015 U	14	700	< 0.54 U	< 0.11 U	71 J		< 0.34 U		8.6	89
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	< 0.017 U	13	840	< 0.62 U	< 0.13 U	83 J		< 0.39 U		9.8	50
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-2-4	8/29/2019	852.90	2 - 4 ft	180-94981-1	Excavated	< 0.015 U	20	1000	< 0.56 U	< 0.12 U	72 J		< 0.35 U		13	55
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-4-6	8/29/2019	852.90	4 - 6 ft	180-94981-1	Excavated	< 0.013 U	13	620	0.79 J	< 0.11 U	110 J		< 0.32 U		7.8	39
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-6-8	8/29/2019	852.90	6 - 8 ft	180-94981-1	Excavated	< 0.014 U	11	700	0.88 J	< 0.11 U	100 J		< 0.33 U		7.3	37
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-10-12	8/29/2019	852.90	10 - 12 ft	180-94981-1	Not Excavated	< 0.014 U	13	780	0.85 J	< 0.11 U	100 J		< 0.34 U		9.1	48
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	< 0.015 U	13	740	0.94 J	< 0.11 U	81 J		< 0.34 U		10	48 J-
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-8-10	8/29/2019	852.90	8 - 10 ft	180-94981-1	Not Excavated	< 0.014 U	15	690	0.61 J	< 0.11 U	98 J		< 0.33 U		10	52
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	< 0.013 U	13	540	< 0.54 U	< 0.11 U	70 J		< 0.34 U		8.2	42
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-2-4	8/29/2019	853.35	2 - 4 ft	180-94981-2	Excavated	< 0.014 U	15	640	1.4	< 0.11 U	75 J		< 0.33 U		11	57
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-4-6	8/29/2019	853.35	4 - 6 ft	180-94981-2	Excavated	< 0.015 U	10	740	0.88 J	< 0.11 U	130 J		< 0.32 U		7.6	37
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-6-8	8/29/2019	853.35	6 - 8 ft	180-94981-2	Excavated	< 0.013 U	13	710	0.97 J	< 0.11 U	87 J		< 0.33 U		10	45
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-8-10	8/29/2019	853.35	8 - 10 ft	180-94981-2	Excavated	< 0.014 U	12	680	1.4	< 0.12 U	140 J		< 0.36 U		8	42
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	< 0.014 U	13	750	0.68 J	< 0.11 U	110 J		< 0.34 U		9.9	54
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-10-12	8/28/2019	853.51	10 - 12 ft	180-94902-3	Excavated	< 0.015 U	12	660	0.69 J	< 0.11 U	86 J		< 0.34 U		8.6	48
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-2-4	8/28/2019	853.51	2 - 4 ft	180-94902-3	Excavated	< 0.014 U	16	780	< 0.59 U	< 0.12 U	61 J		< 0.37 U		14	60
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-4-6	8/28/2019	853.51	4 - 6 ft	180-94902-3	Excavated	< 0.013 U	11	630	< 0.55 U	< 0.11 U	99 J		< 0.34 U		9.8	47
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-6-8	8/28/2019	853.51	6 - 8 ft	180-94902-3	Excavated	< 0.014 U	10	660	0.85 J	< 0.12 U	96 J		< 0.36 U		8.7	92
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-8-10	8/28/2019	853.51	8 - 10 ft	180-94902-3	Excavated	< 0.015 U	14	770	0.62 J	< 0.11 U	92 J		< 0.35 U		10	52
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.020 U	16	900	0.75 J	< 0.11 U	70 J		< 0.33 U		27	34
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.021 U	13	820	< 0.51 U	< 0.10 U	78 J		< 0.32 U		21	27
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated	< 0.022 U	13	540	< 0.46 U	< 0.094 U	68 J		< 0.29 U		7.6	48
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-10-12	8/29/2019	853.54	10 - 12 ft	180-94981-2	Excavated	< 0.015 U	12	760	0.71 J	< 0.11 U	76 J		< 0.32 U		8.9	47
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-2-4	8/29/2019	853.54	2 - 4 ft	180-94981-2	Excavated	< 0.016 U	19	930	< 0.59 U	< 0.12 U	39 J		< 0.36 U		18	74
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-4-6	8/29/2019	853.54	4 - 6 ft	180-94981-2	Excavated	< 0.019 U	15	730	< 0.66 UJ	< 0.13 U	81 J		< 0.41 U		9.5	69
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-6-8	8/29/2019	853.54	6 - 8 ft	180-94981-2	Excavated	< 0.014 U	10	600	0.82 J	< 0.12 U	66 J		< 0.36 U		7.2	32
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-8-10	8/29/2019	853.54	8 - 10 ft	180-94981-2	Excavated	< 0.014 U	14	740	0.81 J	< 0.11 U	79 J		< 0.32 U		9.8	50
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	< 0.015 U	13	630	< 0.56 U	< 0.12 U	77 J		< 0.35 U		8.6	53
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-2-4	8/28/2019	853.78	2 - 4 ft	180-94900-2	Excavated	< 0.016 U	14	540 J	< 0.59 U	< 0.12 U	37 J		< 0.37 U		12	49
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-4-6	8/28/2019	853.78	4 - 6 ft	180-94900-2	Excavated	< 0.017 U	13	690	< 0.56 U	< 0.12 U	56 J		< 0.35 U		11	43
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-6-8	8/28/2019	853.78	6 - 8 ft	180-94900-2	Not Excavated	< 0.013 U	9	450 J	0.66 J	< 0.11 U	57 J		< 0.34 U		7.2	34
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-8-10	8/28/2019	853.78	8 - 10 ft	180-94900-2	Not Excavated	< 0.014 U	15	730	0.66 J	< 0.11 U	80 J		< 0.35 U		11	51
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-10-12	8/27/2019	853.82	10 - 12 ft	180-94829-1	Not Excavated	< 0.014 UJ	15	700	< 0.55 U	< 0.11 U	61 J		< 0.34 U		11	63
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-2-4	8/27/2019	853.82	2 - 4 ft	180-94829-1	Not Excavated	0.017 J	16	690	< 0.6 U	< 0.12 U	50 J		< 0.37 U		12	52
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-4-6	8/27/2019	853.82	4 - 6 ft	180-94829-1	Not Excavated	< 0.016 U	20	740	< 0.57 U	< 0.12 U	49 J		< 0.35 U		15	62
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-6-8	8/27/2019	853.82	6 - 8 ft	180-94829-1	Not Excavated	0.015 J	18	820	< 0.55 U	< 0.11 U	52 J		< 0.35 U		13	59
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-8-10	8/27/2019	853.82	8 - 10 ft	180-94829-1	Not Excavated	< 0.016 U	12	770	< 0.6 U	< 0.12 U	91 J		< 0.37 U		9.1	120
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	< 0.017 U	14	700	< 0.56 U	< 0.11 U	68 J		< 0.35 U		11	64
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-2-4	8/27/2019	854.09	2 - 4 ft	180-94824-3	Excavated	< 0.014 U	14	650	< 0.58 U	< 0.12 UJ	51 J		< 0.36 U		11	52 J
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-4-6	8/27/2019	854.09	4 - 6 ft	180-94824-3	Excavated	< 0.014 U	12	680	< 0.57 U	< 0.12 U	< 29 U		< 0.36 U		8.6	44
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-10-12	8/27/2019	854.09	10 - 12 ft	180-94824-3	Not Excavated	< 0.015 U	13	710	0.85 J	< 0.11 U	< 28 U		< 0.34 U		8.3	42
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-6-8	8/27/2019	854.09	6 - 8 ft	180-94824-3	Not Excavated	< 0.015 U	15	730	0.63 J	< 0.12 U	< 28 U		< 0.35 U		10	79
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-8-10	8/27/2019	854.09	8 - 10 ft	180-94824-3	Not Excavated	< 0.015 U	14	690	0.66 J	< 0.11 U	40 J		< 0.33 U		9.6	59
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	< 0.013 U	14	730	0.94 J	< 0.11 U	37 J		< 0.33 U		9	44
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-2-4	8/27/2019	853.86	2 - 4 ft	180-94824-2	Excavated	< 0.014 U	17	820	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U		12	54
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-4-6	8/27/2019	853.86	4 - 6 ft	180-94824-2	Excavated	< 0.015 U	15	780	< 0.57 U	< 0.12 U	< 29 U		< 0.36 U		10	65
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-10-12	8/27/2019	853.86	10 - 12 ft	180-94824-2	Not Excavated	< 0.014 U	15	690	0.58 J	< 0.11 U	28 J		< 0.33 U		9.1	45
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-6-8	8/27/2019	853.86	6 - 8 ft	180-94824-2	Not Excavated	< 0.014 U	13	730	0.95 J	< 0.11 U	< 26 U		< 0.33 U		10	49

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-8-10	8/27/2019	853.86	8 - 10 ft	180-94824-2	Not Excavated	5800	< 0.37 U	4.1	52	0.21 J	0.1 J	53000	7.5		5.3 J	20	14000	5.8	9000	370
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	6200	< 0.37 U	4.8	46	0.2 J	0.094 J	40000	9.5		5.6	22	14000	8	6500	400
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-2-4	8/26/2019	853.71	2 - 4 ft	180-94752-2	Excavated	8400	< 0.38 UJ	7	47	0.41 J	0.13 J	5000 J	13		6.6 J	26	20000	13	2700	870 J
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-DUP5	8/26/2019	853.71	2 - 4 ft	180-94754-3	Excavated	7600	0.58 J	7.8	50	0.39 J	0.11 J	1600 J	9.4		5.2 J	23	17000	9.5	1900	450 J
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-4-6	8/26/2019	853.71	4 - 6 ft	180-94752-2	Excavated	6200	< 0.34 UJ	4.7	33	0.26 J	0.11 J	21000	9.9		5.2	19	14000	6.3	2800	400
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-6-8	8/26/2019	853.71	6 - 8 ft	180-94752-2	Excavated	6200	< 0.35 U	4.4	49	0.24 J	0.097 J	30000	9.6		5.4	22	14000	7.5	7300	420
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	10 - 12 ft	180-94752-2	Not Excavated	5600	< 0.34 U	4.6	39	0.21 J	0.089 J	43000	8.4		4.6 J	18	13000	7	8900	320
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	8 - 10 ft	180-94752-2	Not Excavated	4900	< 0.35 U	3.5	39	0.2 J	0.075 J	31000	7.5		4.1 J	14	12000	5.4	5000	310
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	6000	< 0.37 U	6.3	35	0.34 J	0.12 J	53000	13		4.6 J	13	12000	4.7	36000	750
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	5400	< 0.31 U	3.7	39	0.22 J	0.18 J	43000	10		5.8	17	13000	8.6	15000	360
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-2-4	8/26/2019	853.76	2 - 4 ft	180-94754-3	Excavated	8300	< 0.4 U	6.2	77	0.44 J	0.097 J	3000	11		5.8	30	17000	40	2100	490
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-4-6	8/26/2019	853.76	4 - 6 ft	180-94754-3	Excavated	10000	0.62 J	6.5	65	0.44 J	0.073 J	990	12		7	20	19000	22	2400	330
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-10-12	8/26/2019	853.76	10 - 12 ft	180-94754-3	Not Excavated	5000	< 0.38 U	4.5	50	0.21 J	0.098 J	11000	7.1		4.3 J	19	12000	6.7	6300	560
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-6-8	8/26/2019	853.76	6 - 8 ft	180-94754-3	Not Excavated	6700	< 0.38 U	5.6	40	0.31 J	0.088 J	1100	8.7		5.7	21	16000	7.1	2100	400
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-8-10	8/26/2019	853.76	8 - 10 ft	180-94754-3	Not Excavated	7000	0.61 J	6.6	48	0.29 J	0.09 J	2600	11		5.8	20	17000	6.7	3100	410
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	5800	< 0.39 U	4.4	45	0.24 J	0.092 J	9600	14		4.9 J	21	14000	7.5	4000	430
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-10-12	9/3/2019	854.48	10 - 12 ft	180-95155-2	Not Excavated	4000	< 0.37 U	4.7	26	0.17 J	0.072 J	37000	5.8		3.8 J	13	11000	5.6	9700	300
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	4900	< 0.37 U	5.1	42	0.21 J	0.095 J	44000	7		4.6 J	16	12000	7.3	22000	330
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-2-4	9/3/2019	854.48	2 - 4 ft	180-95155-2	Not Excavated	9300	0.47 J	5.2	52	0.36 J	< 0.041 U	850	10		6	12	15000	28	1900	330
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-4-6	9/3/2019	854.48	4 - 6 ft	180-95155-2	Not Excavated	6800	< 0.37 UJ	4.2	40	0.29 J	0.063 J	900	9.1		6	16	14000	12 J	2000	600
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-6-8	9/3/2019	854.48	6 - 8 ft	180-95155-2	Not Excavated	5700	0.42 J	5.5	47	0.26 J	0.073 J	12000	7.6		5.2 J	17	14000	6.8	5600	400
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-8-10	9/3/2019	854.48	8 - 10 ft	180-95155-2	Not Excavated	5000	< 0.39 U	5	41	0.2 J	0.13 J	32000	6.8		4.8 J	13	12000	5.8	5100	420
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-2-4	9/3/2019	855.00	2 - 4 ft	180-95155-1	Excavated	11000	0.48 J	8.7	46 J	0.5	0.046 J	360 J	13		9	33	23000	20 J+	2500 J-	400
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-10-12	9/3/2019	855.00	10 - 12 ft	180-95155-1	Not Excavated	6600	< 0.36 U	4.2	48	0.23 J	0.065 J	35000	11		5.4	21	15000	9.2	11000	320
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	6600	< 0.39 U	4.8	55	0.24 J	0.093 J	36000	9.4		5.7 J	22	15000	8.8	9700	380
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-4-6	9/3/2019	855.00	4 - 6 ft	180-95155-1	Not Excavated	7800	< 0.37 U	5.5	56	0.33 J	0.13 J	1700	10		7	20	17000	9.5	2300	660
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-6-8	9/3/2019	855.00	6 - 8 ft	180-95155-1	Not Excavated	5800	< 0.36 U	4.2	46	0.22 J	0.077 J	46000	9		4.7 J	23	14000	11	23000	330
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-8-10	9/3/2019	855.00	8 - 10 ft	180-95155-1	Not Excavated	7000	< 0.35 U	5.3	60	0.3 J	0.11 J	35000	9.7		6.2	26	16000	12	7300	560
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-2-4	8/30/2019	854.59	2 - 4 ft	180-95047-1	Excavated	10000	< 0.4 U	8.1	52	0.41 J	< 0.043 UJ	570 J	12		8.8	23	20000	8.7	2700	540
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-4-6	8/30/2019	854.59	4 - 6 ft	180-95047-1	Excavated	7700	0.65 J	8.7	52	0.35 J	0.052 J	1000	11		7.5	21	18000	9.1	2400	400
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-10-12	8/30/2019	854.59	10 - 12 ft	180-95047-1	Not Excavated	7500	0.47 J	6.9	58	0.32 J	0.1 J	13000	9.8		6.9	22	18000	9.2	6000	500
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-12-14	8/30/2019	854.59	12 - 14 ft	180-95047-1	Not Excavated	7200	< 0.36 U	6.1	66	0.28 J	0.085 J	37000	9.8		6.6	21	16000	8	11000	500
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	7000	0.43 J	5.5	60	0.28 J	0.063 J	25000	11		6.5	21	16000	13	9300	470
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-6-8	8/30/2019	854.59	6 - 8 ft	180-95047-1	Not Excavated	5700	< 0.37 U	5.2	75	0.24 J	0.075 J	47000	9.1		4.9 J	18	14000	8	22000	600
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-8-10	8/30/2019	854.59	8 - 10 ft	180-95047-1	Not Excavated	5900	0.41 J	5.3	56	0.25 J	0.072 J	17000	10		5.5 J	18	14000	7.9	6000	500
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-2-4	8/29/2019	854.13	2 - 4 ft	180-94981-3	Excavated	8700	< 0.39 U	8.1	61	0.43 J	0.048 J	700	12		8.6	26	18000	12	2400	480
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-4-6	8/29/2019	854.13	4 - 6 ft	180-94981-3	Excavated	6900	< 0.37 UJ	5.4	46	0.29 J	0.1 J	27000	11		6.1	19	16000	18	15000	850
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-6-8	8/29/2019	854.13	6 - 8 ft	180-94981-3	Excavated	7000	< 0.36 U	4.5	41	0.24 J	0.12 J	43000	10		6.5	23	16000	7.4	5800	700
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-8-10	8/29/2019	854.13	8 - 10 ft	180-94981-3	Excavated	4300	< 0.36 U	3.8	32	0.21 J	0.07 J	34000	8.7		4 J	16	10000	4	7100	320
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-10-12	8/29/2019	854.13	10 - 12 ft	180-94981-3	Not Excavated	4600	< 0.36 U	7.5	36	0.22 J	0.056 J	40000	7.8		4.6 J	15	11000	6	10000	380
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	5600	< 0.36 U	4.9	45	0.21 J	0.049 J	31000	13		5.3	20	14000	6.2	7300	420
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-10-12	8/28/2019	854.13	10 - 12 ft	180-94902-3	Excavated	5600	< 0.36 U	4.7	43	0.22 J	0.11 J	35000	8.7		5 J	20	13000	8	5200	450
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-2-4	8/28/2019	854.13	2 - 4 ft	180-94902-3	Excavated	10000	< 0.37 U	6.4	63	0.41 J	0.077 J	2200	13		8.6	25	22000	10	2900	570
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-4-6	8/28/2019	854.13	4 - 6 ft	180-94902-3	Excavated	7700	< 0.37 U	5.8	54	0.29 J	0.087 J	36000	11		6.1	32	16000	8.2	3600	450
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-6-8	8/28/2019	854.13	6 - 8 ft	180-94902-3	Excavated	5900	< 0.37 U	7	48	0.24 J	0.097 J	22000	9		5.3 J	19	14000	9	5400	320
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-8-10	8/28/2019	854.13	8 - 10 ft	180-94902-3	Excavated	6100	< 0.38 U	4.7	55	0.23 J	0.1 J	40000	9.7		5 J	17	14000	10	11000	400
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	5100	< 0.36 U	3.8	40	0.19 J	0.1 J	62000	9.8		4.4 J	18	12000	6.9	6600	340
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-10-12	8/29/2019	854.60	10 - 12 ft	180-94981-3	Excavated	5200	< 0.35 U	4.9	50	0.19 J	0.23 J	55000	9.1		4.7 J	18	12000	7.3	14000	480
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-2-4	8/29/2019	854.60	2 - 4 ft	180-94981-3	Excavated	9500	< 0.84 U	9.3	240	1.5	0.16 J	2300	16		17	32	32000	18	3000	1600
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-4-6	8/29/2019	854.60	4 - 6 ft	180-94981-3	Excavated	7300	< 0.39 U	6.2	49	0.36 J	0.14 J	10000	8.5		6.5	21	17000	8	6800	430
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-6-8	8/29/2019	854.60	6 - 8 ft	180-94981-3	Excavated	5200	< 0.34 U	5.2	39	0.19 J	0.11 J	53000	7.3		4.5 J	18	12000	4.8	13000	470
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-8-10	8/29/2019	854.60	8 - 10 ft	180-94981-3	Excavated	5300	< 0.37 U	4.3	44	0.19 J	0.099 J	31000	6.3		4.4 J	14	12000	5.9	5200	310
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	5800	< 0.35 U	4.3	54	0.21 J	0.13 J	31000	8.1		5.2	17	14000	6.1	9700	560
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-2-4	8/28/2019	854.97	2 - 4 ft	180-94902-3	Excavated	6900	< 0.38 U	4.7	37	0.25 J	0.18 J	30000	11		5.8	23	16000	9.1	6400	440
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-10-12	8/28/2019	854.97	10 - 12 ft	180-94902-3	Not Excavated	6200	< 0.34 U	5	51	0.23 J	0.1 J	53000	11		6.7	23	15000	6.4	11000	550
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-6-8	8/28/2019	854.97	6 - 8 ft	180-94902-3	Not Excavated	6200	< 0.34 U	3.3	49	0.22 J	0.12 J	35000	8.4		5.4	13	14000	7.9	7500	640
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-8-10	8/28/2019	854.97	8 - 10 ft	180-94902-3	Not Excavated	5600	< 0.35 U	4.1	55	0.21 J	0.12 J	57000	11		5.1	18	12000	6.3	10000	420
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	6700	< 0.41 U	4	70	0.23 J	0.17 J	59000	11		6.3	23	17000	6.4	8200	770
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-10-12	8/28/2019	855.22	10 - 12 ft	180-94902-1	Not Excavated	5700	< 0.37 U	5.2	53	0.19 J	0.12 J	62000	9		5.1 J	22	13000	9.5	6900	430
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-2-4	8/28/2019	855.22	2 - 4 ft	180-94902-1	Not Excavated	10000	< 0.39 U	7.5	79	0.4 J	0.093 J	810	13		7.1	27	19000	15	2300	690
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-4-6	8/28/2019	855.22	4 - 6 ft	180-94902-1	Not Excavated	11000	0.46 J	10	87	0.57	0.21 J	1900	14		9.3	29	22000	29	2700	1200
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-6-8	8/28/2019	855.22	6 - 8 ft	180-94902-1	Not Excavated	5900	< 0.37 U	3.7	39	0.21 J	0.09 J	45000	8		4.9 J	21	14000	26	11000	360
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-8-10	8/28/2019	855.22	8 - 10 ft	180-94902-1	Not Excavated	7400	< 0.35 U	5.2	51	0.27 J	0.093 J	42000	10		6	22	16000	11	11000	440
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	5400	< 0.36 UJ	4.5	45	0.21 J	0.098 J	49000	8.9 J		5 J	18	12000	17	8100 J-	620
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-10-12	8/27/2019	855.08	10 - 12 ft	180-94824-3	Not Excavated	5400	< 0.36 U	3.9	39	0.2 J	0.095 J	52000	7.9		5 J	15	13000	5.9	19000	400
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-2-4	8/27/2019	855.08	2 - 4 ft	180-94824-2	Not Excavated	10000	< 0.38 U	5.8	41	0.36 J	< 0.041 U	520 J	11		7.6	16	15000	8.7	2100	440
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-4-6	8/27/2019	855.08	4 - 6 ft	180-94824-2	Not Excavated	6100	< 0.37 U	4.4	43	0.25 J	0.044 J	490 J	10		5.7	16	13000	7.3	1700	470
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-6-8	8/27/2019	855.08	6 - 8 ft	180-94824-2	Not Excavated	6500	< 0.39 UJ	6.4	47	0.3 J	0.13 J	9800 J-	9.8		5.8	22	16000	11	6000 J-	660
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-8-10	8/27/2019	855.08	8 - 10 ft	180-94824-2	Not Excavated	6000	< 0.35 U	4.3	44	0.24 J	0.11 J	23000	11		5.4	17	14000	7.7	5300	390
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	5200	< 0.35 U	4.9	57	0.19 J	0.098 J	77000	9.7		4.8 J	17	12000	5.5	9500	290
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-10-12	8/27/2019	855.25	10 - 12 ft	180-94819-1	Not Excavated	7500	0.45 J	5.2	74	0.31 J	0.086 J	17000	11		5.9	16	15000	9.9	7000	540
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-2-4	8/27/2019	855.25	2 - 4 ft	180-94819-1	Not Excavated	5400	< 0.39 UJ	4.2	33	0.23 J	0.069 J	5600 J	7.5		4.3 J	15	12000	8.8 J	2200 J-	300 J
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-4-6	8/27/2019	855.25	4 - 6 ft	180-94819-1	Not Excavated	12000	0.58 J	6.6	61	0.49	0.063 J	4200	15		11	14	20000	13	3800	460
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-6-8	8/27/2019	855.25	6 - 8 ft	180-94819-1	Not Excavated	7300	0.46 J	6.2	48	0.37 J	0.089 J	5800	16		6.6	20	17000	8.4	4800	510

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-8-10	8/27/2019	853.86	8 - 10 ft	180-94824-2	Not Excavated	< 0.014 U	13	660	0.97 J	< 0.11 U	29 J		< 0.35 U		9	46
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	< 0.014 U	14	630	0.98 J	< 0.11 U	28 J		< 0.35 U		8.8	50
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-2-4	8/26/2019	853.71	2 - 4 ft	180-94752-2	Excavated	0.035	15		< 0.58 U	< 0.12 U	47 J		< 0.36 U		15	57
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-DUP5	8/26/2019	853.71	2 - 4 ft	180-94754-3	Excavated	0.05	14		< 0.56 U	< 0.11 U	48 J		< 0.35 U		13	51
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-4-6	8/26/2019	853.71	4 - 6 ft	180-94752-2	Excavated	< 0.015 U	13		< 0.52 U	< 0.11 U	67 J		< 0.32 U		10	47
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-6-8	8/26/2019	853.71	6 - 8 ft	180-94752-2	Excavated	< 0.013 U	14		0.53 J	< 0.11 U	66 J		< 0.33 U		10	57
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	10 - 12 ft	180-94752-2	Not Excavated	< 0.014 U	12		0.75 J	< 0.11 U	74 J		< 0.32 U		8.6	45
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	8 - 10 ft	180-94752-2	Not Excavated	0.014 J	10		< 0.54 U	< 0.11 U	67 J		< 0.33 U		8.9	39
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	0.024 J	13		0.79 J	< 0.11 U	150 J		< 0.35 U		12	45
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.020 U	14	530	< 0.48 U	< 0.097 U	75 J		0.44 J		9.7	48
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-2-4	8/26/2019	853.76	2 - 4 ft	180-94754-3	Excavated	0.097	14	540 J	< 0.6 U	< 0.12 U	48 J		< 0.38 U		14	72
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-4-6	8/26/2019	853.76	4 - 6 ft	180-94754-3	Excavated	0.11	15	640	< 0.6 U	< 0.12 U	42 J		< 0.37 U		15	55
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-10-12	8/26/2019	853.76	10 - 12 ft	180-94754-3	Not Excavated	< 0.015 U	11	560	< 0.58 U	< 0.12 U	66 J		< 0.36 U		8.3	55
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-6-8	8/26/2019	853.76	6 - 8 ft	180-94754-3	Not Excavated	< 0.014 U	14	580	< 0.58 U	< 0.12 U	41 J		< 0.36 U		10	55
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-8-10	8/26/2019	853.76	8 - 10 ft	180-94754-3	Not Excavated	< 0.015 U	15	610	< 0.54 U	< 0.11 U	49 J		< 0.33 U		10	49
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	0.038	12	640	< 0.58 U	< 0.12 U	59 J		< 0.36 U		9.1	54
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-10-12	9/3/2019	854.48	10 - 12 ft	180-95155-2	Not Excavated	< 0.014 U	9.5	550	< 0.55 U	< 0.11 U	67 J		< 0.34 U		7.8	35
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	< 0.013 U	11	680	0.65 J	< 0.12 U	83 J		< 0.35 U		8	48
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-2-4	9/3/2019	854.48	2 - 4 ft	180-95155-2	Not Excavated	0.022 J	12	600	< 0.58 U	< 0.12 U	40 J		< 0.36 U		14	43
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-4-6	9/3/2019	854.48	4 - 6 ft	180-95155-2	Not Excavated	0.015 J	14	670	< 0.56 U	< 0.11 U	40 J		< 0.35 U		11	44
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-6-8	9/3/2019	854.48	6 - 8 ft	180-95155-2	Not Excavated	0.016 J	12	860	< 0.56 U	< 0.11 U	55 J		< 0.35 U		10	56
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-8-10	9/3/2019	854.48	8 - 10 ft	180-95155-2	Not Excavated	< 0.015 U	11	600	< 0.6 U	< 0.12 U	66 J		< 0.37 U		7.8	42
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-2-4	9/3/2019	855.00	2 - 4 ft	180-95155-1	Excavated	0.044	20	850	< 0.57 U	< 0.12 U	39 J		< 0.35 U		18	63 J-
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-10-12	9/3/2019	855.00	10 - 12 ft	180-95155-1	Not Excavated	0.015 J	15	750	0.55 J	< 0.11 U	77 J		< 0.34 U		9.9	49
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	< 0.015 U	14	800	0.65 J	< 0.12 U	110 J		< 0.37 U		11	56
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-4-6	9/3/2019	855.00	4 - 6 ft	180-95155-1	Not Excavated	< 0.014 U	19	960	< 0.56 U	< 0.12 U	48 J		< 0.35 U		13	61
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-6-8	9/3/2019	855.00	6 - 8 ft	180-95155-1	Not Excavated	0.02 J	12	830	0.75 J	< 0.11 U	88 J		< 0.34 U		12	36
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-8-10	9/3/2019	855.00	8 - 10 ft	180-95155-1	Not Excavated	< 0.015 U	15	790	0.67 J	< 0.11 U	82 J		< 0.33 U		11	51
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-2-4	8/30/2019	854.59	2 - 4 ft	180-95047-1	Excavated	< 0.015 UJ	19	860	< 0.61 U	< 0.12 U	42 J		< 0.38 U		15	62
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-4-6	8/30/2019	854.59	4 - 6 ft	180-95047-1	Excavated	< 0.016 U	21	780	< 0.61 U	< 0.12 U	40 J		< 0.38 U		13	60
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-10-12	8/30/2019	854.59	10 - 12 ft	180-95047-1	Not Excavated	< 0.015 U	20	760	< 0.56 U	< 0.11 U	58 J		< 0.35 U		12	59
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-12-14	8/30/2019	854.59	12 - 14 ft	180-95047-1	Not Excavated	< 0.015 U	17	790	0.77 J	< 0.11 U	70 J		< 0.34 U		12	67
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	< 0.017 U	16	770	< 0.6 U	< 0.12 U	70 J		< 0.37 U		11	58
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-6-8	8/30/2019	854.59	6 - 8 ft	180-95047-1	Not Excavated	< 0.015 U	13	700	1 J	< 0.12 U	91 J		< 0.35 U		10	42
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-8-10	8/30/2019	854.59	8 - 10 ft	180-95047-1	Not Excavated	< 0.015 U	15	720	< 0.58 U	< 0.12 U	74 J		< 0.36 U		9.5	52
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-2-4	8/29/2019	854.13	2 - 4 ft	180-94981-3	Excavated	0.015 J	19	970	< 0.59 U	< 0.12 U	39 J		< 0.37 U		14	67
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-4-6	8/29/2019	854.13	4 - 6 ft	180-94981-3	Excavated	< 0.015 U	16	780	0.74 J	< 0.11 U	110 J		< 0.35 U		11	59
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-6-8	8/29/2019	854.13	6 - 8 ft	180-94981-3	Excavated	< 0.014 U	17	610	0.86 J	< 0.11 U	83 J		< 0.34 U		11	84
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-8-10	8/29/2019	854.13	8 - 10 ft	180-94981-3	Excavated	< 0.014 U	10	620	< 0.55 U	< 0.11 U	81 J		< 0.34 U		7.6	37
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-10-12	8/29/2019	854.13	10 - 12 ft	180-94981-3	Not Excavated	< 0.014 U	11	590	< 0.55 U	< 0.11 U	84 J		< 0.34 U		7.9	38
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	< 0.015 U	14	570	0.7 J	< 0.11 U	71 J		< 0.34 U		8.7	48
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-10-12	8/28/2019	854.13	10 - 12 ft	180-94902-3	Excavated	< 0.014 U	13	770	0.78 J	< 0.11 U	72 J		< 0.34 U		9.8	52
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-2-4	8/28/2019	854.13	2 - 4 ft	180-94902-3	Excavated	0.045	19	830	< 0.56 U	< 0.11 U	54 J		< 0.35 U		16	66
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-4-6	8/28/2019	854.13	4 - 6 ft	180-94902-3	Excavated	< 0.015 U	15	880	< 0.56 U	< 0.11 U	68 J		< 0.35 U		12	61
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-6-8	8/28/2019	854.13	6 - 8 ft	180-94902-3	Excavated	0.069 J	13	760	< 0.56 UJ	< 0.11 U	65 J		< 0.35 U		10	50
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-8-10	8/28/2019	854.13	8 - 10 ft	180-94902-3	Excavated	0.066	13	820	0.77 J	< 0.12 U	92 J		< 0.35 U		9.9	54
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	0.058	12		0.65 J	< 0.11 U	83 J		< 0.34 U		9.2	49
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-10-12	8/29/2019	854.60	10 - 12 ft	180-94981-3	Excavated	< 0.014 U	12	680	1	< 0.11 U	100 J		< 0.33 U		7.8	55
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-2-4	8/29/2019	854.60	2 - 4 ft	180-94981-3	Excavated	0.019 J	34	1200	< 1.3 U	< 0.26 U	< 64 U		< 0.4 U		19	43
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-4-6	8/29/2019	854.60	4 - 6 ft	180-94981-3	Excavated	< 0.016 U	16	710	< 0.59 U	< 0.12 U	61 J		< 0.37 U		12	74
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-6-8	8/29/2019	854.60	6 - 8 ft	180-94981-3	Excavated	< 0.015 U	11	600	0.89 J	< 0.11 U	97 J		< 0.32 U		7.5	46
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-8-10	8/29/2019	854.60	8 - 10 ft	180-94981-3	Excavated	< 0.014 U	11	580	0.81 J	< 0.11 U	56 J		< 0.34 U		6.9	55
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	< 0.015 U	13	550	< 0.53 U	< 0.11 U	69 J		< 0.33 U		8.4	59
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-2-4	8/28/2019	854.97	2 - 4 ft	180-94902-3	Excavated	< 0.013 U	15	680	< 0.58 U	< 0.12 U	67 J		< 0.36 U		10	69
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-10-12	8/28/2019	854.97	10 - 12 ft	180-94902-3	Not Excavated	< 0.014 U	15	710	0.75 J	< 0.11 U	83 J		< 0.32 U		12	65
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-6-8	8/28/2019	854.97	6 - 8 ft	180-94902-3	Not Excavated	< 0.015 U	14	630	0.67 J	< 0.11 U	77 J		< 0.33 U		8.8	53
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-8-10	8/28/2019	854.97	8 - 10 ft	180-94902-3	Not Excavated	< 0.015 U	13	690	0.82 J	< 0.11 U	96 J		< 0.33 U		8.5	43
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	< 0.016 U	16	710	< 0.62 U	< 0.13 U	88 J		< 0.38 U		11	61
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-10-12	8/28/2019	855.22	10 - 12 ft	180-94902-1	Not Excavated	< 0.013 U	13	720	1.1	< 0.11 U	81 J		< 0.35 U		8.8	45
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-2-4	8/28/2019	855.22	2 - 4 ft	180-94902-1	Not Excavated	0.03 J	17	910	< 0.59 U	< 0.12 U	42 J		< 0.37 U		18	67
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-4-6	8/28/2019	855.22	4 - 6 ft	180-94902-1	Not Excavated	< 0.016 U	25	1300	< 0.62 U	< 0.13 U	46 J		< 0.39 U		20	69
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-6-8	8/28/2019	855.22	6 - 8 ft	180-94902-1	Not Excavated	< 0.016 U	12	730	0.77 J	< 0.12 U	79 J		< 0.35 U		8.8	43
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-8-10	8/28/2019	855.22	8 - 10 ft	180-94902-1	Not Excavated	< 0.016 U	15	890	0.7 J	< 0.11 U	80 J		< 0.33 U		11	57
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	< 0.014 U	12	630	< 0.55 U	< 0.11 U	91 J		< 0.34 U		8.6	53
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-10-12	8/27/2019	855.08	10 - 12 ft	180-94824-3	Not Excavated	< 0.014 U	12	690	0.61 J	< 0.11 U	40 J		< 0.34 U		9.6	40
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-2-4	8/27/2019	855.08	2 - 4 ft	180-94824-2	Not Excavated	< 0.016 U	14	630	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U		15	42
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-4-6	8/27/2019	855.08	4 - 6 ft	180-94824-2	Not Excavated	< 0.014 U	12	570	< 0.55 U	< 0.11 U	< 28 U		< 0.34 U		9.6	42
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-6-8	8/27/2019	855.08	6 - 8 ft	180-94824-2	Not Excavated	0.019 J	15	790	< 0.58 UJ	< 0.12 UJ	< 29 U		< 0.36 U		12	53 J-
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-8-10	8/27/2019	855.08	8 - 10 ft	180-94824-2	Not Excavated	< 0.015 U	13	730	0.54 J	< 0.11 U	< 27 U		< 0.33 U		11	51
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	< 0.014 U	11	700	1.2	< 0.11 U	54 J		< 0.33 U		7.6	42
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-10-12	8/27/2019	855.25	10 - 12 ft	180-94819-1	Not Excavated	< 0.016 U	13	770	< 0.58 U	< 0.12 U	66 J		< 0.36 U		12	53
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-2-4	8/27/2019	855.25	2 - 4 ft	180-94819-1	Not Excavated	0.33 J	10	540 J	< 0.59 U	< 0.12 U	53 J		< 0.37 U		8.7	42 J+
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-4-6	8/27/2019	855.25	4 - 6 ft	180-94819-1	Not Excavated	0.024 J	18	860	< 0.61 U	< 0.12 U	72 J		< 0.38 U		16	54
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-6-8	8/27/2019	855.25	6 - 8 ft	180-94819-1	Not Excavated	< 0.016 U	15	680	< 0.59 U	< 0.12 U	54 J		< 0.37 U		16	49

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-8-10	8/27/2019	855.25	8 - 10 ft	180-94819-1	Not Excavated	9100	< 0.41 U	5.5	86	0.36 J	0.096 J	15000	13		7.4	19	17000	10	5600	770
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	6000	< 0.39 U	4.9	570	0.25 J	0.1 J	76000	9.8		5.6 J	21	14000	9.7	13000	550
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-2-4	8/27/2019	855.17	2 - 4 ft	180-94824-1	Excavated	13000	< 0.41 U	8.3	38	0.5	< 0.044 U	390 J	14		9.2	16	23000	12	3100	270
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-10-12	8/27/2019	855.17	10 - 12 ft	180-94824-1	Not Excavated	8000	< 0.4 U	6.7	69	0.35 J	0.089 J	1500	11		6.5	21	17000	10	2300	530
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-4-6	8/27/2019	855.17	4 - 6 ft	180-94824-1	Not Excavated	8300	< 0.39 U	5.3	36	0.39 J	0.059 J	410 J	10		7.4	18	18000	11	2200	760
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-6-8	8/27/2019	855.17	6 - 8 ft	180-94824-1	Not Excavated	8800	< 0.41 U	8.8	49	0.39 J	0.075 J	910	11		8.1	25	20000	12	2300	400
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-8-10	8/27/2019	855.17	8 - 10 ft	180-94824-1	Not Excavated	10000	< 0.45 U	6.2	97	0.43 J	0.076 J	1900	14		7.5	19	19000	17	2600	540
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	8300	< 0.41 U	6.7	63	0.37 J	0.098 J	1800	12		8.1	24	18000	13	2700	740
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-10-12	8/26/2019	855.10	10 - 12 ft	180-94752-3	Not Excavated	6200	< 0.38 U	5.4	55	0.25 J	0.16 J	9800	8.2		5.7	18	16000	7.8	3400	620
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-12-14	8/26/2019	855.10	12 - 14 ft	180-94752-3	Not Excavated	6600	< 0.38 U	4.9	45	0.26 J	0.11 J	14000	8.6		5.8	25	16000	6.7	7600	450
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-4-6	8/26/2019	855.10	4 - 6 ft	180-94752-3	Not Excavated	10000	< 0.39 U	8.3	46	0.5	0.044 J	970	11		8.4	19	20000	15	2500	600
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-6-8	8/26/2019	855.10	6 - 8 ft	180-94752-3	Not Excavated	6900	0.55 J	6	50	0.31 J	0.069 J	1100	8.5		5.9 J	18	15000	11	1900	640
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-8-10	8/26/2019	855.10	8 - 10 ft	180-94752-3	Not Excavated	7300	< 0.39 U	6.2	46	0.33 J	0.1 J	2200	10		6.6	19	17000	14	2100	620
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	6700	< 0.36 UJ	4.7	43	0.27 J	0.12 J	17000	9.9		6.1	22	16000	8.1	4600	440
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-2-4	8/26/2019	855.10	2 - 4 ft	180-94752-2	Excavated	12000	0.56 J	5.4	66	0.43 J	0.062 J	1100	13		7.8	13	19000	14	2700	400
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-10-12	8/26/2019	854.81	10 - 12 ft	180-94752-1	Not Excavated	5600	< 0.37 U	5	27	0.23 J	0.082 J	17000	8.3		4.7 J	16	14000	6.2	5400	290
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-6-8	8/26/2019	854.81	6 - 8 ft	180-94752-1	Not Excavated	6800	< 0.36 U	5.6	41	0.31 J	0.098 J	11000	9.4		5.6	19	15000	7.9	2500	400
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-8-10	8/26/2019	854.81	8 - 10 ft	180-94752-1	Not Excavated	6900	< 0.35 U	4.5	41	0.26 J	0.13 J	46000	9.8		5.5	21	14000	7.6	5300	410
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	6500	< 0.38 U	5	52	0.28 J	0.12 J	34000	9.8		5.8	21	15000	8.4	6600	820
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-2-4	8/26/2019	854.81	2 - 4 ft	180-94752-1	Excavated	8500	< 0.39 U	6.4	51	0.37 J	0.11 J	4700	12		6.4	24	18000	13	3100	480
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-4-6	8/26/2019	854.81	4 - 6 ft	180-94752-1	Excavated	7600	< 0.38 U	7	110	0.35 J	0.094 J	12000	9.9		6.1	21	16000	14	3400	510
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-10-12	9/3/2019	855.09	10 - 12 ft	180-95155-2	Not Excavated	4600	< 0.37 U	6.2	27	0.19 J	0.085 J	47000	6.2		4.1 J	18	10000	4.8	16000	290
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	5400	< 0.36 U	4.4	40	0.2 J	0.069 J	42000	8.8		5 J	13	12000	6.5	13000	390
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-2-4	9/3/2019	855.09	2 - 4 ft	180-95155-2	Not Excavated	10000	0.49 J	6.1	77	0.36 J	0.063 J	340 J	10		7.2	10	15000	12	1800	600
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-4-6	9/3/2019	855.09	4 - 6 ft	180-95155-2	Not Excavated	11000	0.41 J	6.2	53	0.42 J	0.044 J	260 J	11		7.7	11	18000	8.7	2200	320
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-6-8	9/3/2019	855.09	6 - 8 ft	180-95155-2	Not Excavated	7800	< 0.37 U	6.3	99	0.32 J	0.074 J	900	10		7	19	16000	7.9	2300	440
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-8-10	9/3/2019	855.09	8 - 10 ft	180-95155-2	Not Excavated	8600	0.38 J	7.6	71	0.4 J	0.07 J	4600	12		7	18	18000	11	3000	620
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-10-12	9/3/2019	855.76	10 - 12 ft	180-95162-1	Not Excavated	5100	< 0.35 U	4.2	54	0.19 J	0.075 J	34000	8.1		4.4 J	18	12000	6.9	11000	360
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	5400	< 0.36 U	4.1	41	0.21 J	0.077 J	30000	9.1		4.7 J	16	12000	6.7	7700	340
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-2-4	9/3/2019	855.76	2 - 4 ft	180-95162-1	Not Excavated	12000	0.42 J	7.1	56	0.48 J	0.049 J	470 J	13		7.5	16	20000	12	2500	280
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-4-6	9/3/2019	855.76	4 - 6 ft	180-95162-1	Not Excavated	9900	0.48 J	9.1	39	0.45 J	0.05 J	560 J	12		7.9	22	22000	11	2400	280
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-6-8	9/3/2019	855.76	6 - 8 ft	180-95162-1	Not Excavated	8600	< 0.4 UJ	7.7	63	0.38 J	0.072 J	3400 J	11		7.4	21	19000 J	10	3500 J	520 J
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-8-10	9/3/2019	855.76	8 - 10 ft	180-95162-1	Not Excavated	7700	< 0.35 UJ	4.7	52	0.29 J	0.079 J	28000	10		6.4	28	17000	7.5	7300	540
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-10-12	8/30/2019	855.85	10 - 12 ft	180-95047-1	Not Excavated	8100	0.61 J	7.7	54	0.37 J	0.082 J	1100	11		7.7	22	20000	13	2400	790
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	7800	0.52 J	6.8	59	0.36 J	0.1 J	4600	10		6.6	20	17000	9.6	4400	590
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-2-4	8/30/2019	855.85	2 - 4 ft	180-95047-1	Not Excavated	10000	8.8	8.4	70	0.47 J	0.096 J	2200	13		8.5	20	20000	47	2700	400
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-4-6	8/30/2019	855.85	4 - 6 ft	180-95047-1	Not Excavated	7700	< 0.39 U	6.1 J	64	0.32 J	0.1 J	23000	9.9		6.9 J	23	17000	9.3 J	12000	590
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-6-8	8/30/2019	855.85	6 - 8 ft	180-95047-1	Not Excavated	4800	0.53 J	4.4	35	0.2 J	0.078 J	20000	6.4		4.4 J	15	12000	5.2	4300	310
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-8-10	8/30/2019	855.85	8 - 10 ft	180-95047-1	Not Excavated	8700	0.61 J	7.2	39 J	0.39 J	0.054 J	1300	12		6.7	19	18000	14	2300	360
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-10-12	8/29/2019	855.10	10 - 12 ft	180-95006-1	Not Excavated	5800	< 0.38 U	4.1	98	0.25 J	0.051 J	53000	73		5.5	42	16000	6.6	13000	400
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	5900	< 0.36 U	5	95	0.27 J	0.06 J	34000	11		5.2 J	21	14000	8	9800	370
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-2-4	8/29/2019	855.10	2 - 4 ft	180-95006-1	Not Excavated	11000	< 0.41 U	6.4	62	0.45 J	< 0.044 U	810	12		8.3	13	18000	8.8	2300	280
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-4-6	8/29/2019	855.10	4 - 6 ft	180-95006-1	Not Excavated	7800	0.35 J	5.9	68	0.33 J	0.046 J	1100	10		6.2	24	17000	7	2300	490
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-6-8	8/29/2019	855.10	6 - 8 ft	180-95006-1	Not Excavated	7000	< 0.38 U	5.6	73	0.29 J	0.13 J	27000	9.5		6.2	23	17000	6.8	11000	680
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-8-10	8/29/2019	855.10	8 - 10 ft	180-95006-1	Not Excavated	5700	< 0.38 U	4.5	180	0.23 J	0.063 J	63000	9.6		4.8 J	17	13000	4.9	17000	420
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-2-4	8/29/2019	855.17	2 - 4 ft	180-94981-1	Excavated	10000	0.49 J	7.9	52	0.48	0.065 J	1200	13		8	21	20000	12	2500	900
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-4-6	8/29/2019	855.17	4 - 6 ft	180-94981-1	Excavated	7700	< 0.39 U	6.9	52	0.38 J	0.051 J	1100	12		6.6	21	17000	9.1	2000	560
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-10-12	8/29/2019	855.17	10 - 12 ft	180-94981-1	Not Excavated	6100	< 0.36 U	4.6	96	0.25 J	0.074 J	56000	8.9		5.2 J	17	13000	14	12000	420
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	6300	< 0.35 U	5.5	47	0.23 J	0.063 J	24000	8.7		5.6	34	15000	6.4	7600	420
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-6-8	8/29/2019	855.17	6 - 8 ft	180-94981-1	Not Excavated	5700	< 0.4 U	4.3	54	0.25 J	0.054 J	5300	10		4.8 J	16	13000	6.5	2900	560
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-8-10	8/29/2019	855.17	8 - 10 ft	180-94981-1	Not Excavated	7700	< 0.36 U	5.3	57	0.34 J	0.11 J	4400	12		6.6	22	17000	9.7	3200	610
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-2-4	8/28/2019	855.23	2 - 4 ft	180-94902-1	Excavated	4800	< 0.36 U	4.3	37	0.19 J	0.096 J	37000	6.8		4.7 J	14	11000	5.3	6500	650
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-4-6	8/28/2019	855.23	4 - 6 ft	180-94902-1	Excavated	7100	< 0.38 U	6.7	48	0.32 J	0.13 J	1200	19		6.6	28	17000	17	2100	900
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-6-8	8/28/2019	855.23	6 - 8 ft	180-94902-1	Excavated	11000	< 0.4 U	7.6	58	0.44 J	0.044 J	320 J	12		8.1	25	20000	11	2300	520
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-8-10	8/28/2019	855.23	8 - 10 ft	180-94902-1	Not Excavated	5900	< 0.36 U	4.8	44	0.23 J	0.085 J	14000	11		5.5	23	14000	8.2	3700	380
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-10-12	8/28/2019	855.78	10 - 12 ft	180-94902-2	Not Excavated	4600	< 0.39 U	12	46	0.2 J	0.14 J	30000	7.6		4.7 J	17	13000	5.7	4500	340
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-2-4	8/28/2019	855.78	2 - 4 ft	180-94902-2	Not Excavated	10000	< 0.4 U	5.5	130	0.43 J	0.07 J	1400	11		6	11	17000	14	2000	420
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-4-6	8/28/2019	855.78	4 - 6 ft	180-94902-2	Not Excavated	8200	< 0.39 U	5.3	54	0.32 J	0.084 J	6300	11		6	23	17000	7.4	5200	350
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-6-8	8/28/2019	855.78	6 - 8 ft	180-94902-2	Not Excavated	6600	< 0.36 U	5.1	65	0.26 J	0.1 J	27000	9.2		6.1	20	17000	9.5	9200	690
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-8-10	8/28/2019	855.78	8 - 10 ft	180-94902-2	Not Excavated	6400	< 0.36 U	5.4	90	0.23 J	0.12 J	23000	9.1		6	21	16000	6.5	5500	620
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	5800	< 0.36 U	4.5	59	0.27 J	0.14 J	20000	9		5.4	18	15000	6.9	5000	260
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-2-4	8/28/2019	856.00	2 - 4 ft	180-94900-1	Excavated	9500	< 0.38 U	5.4	72	0.38 J	0.08 J	5700	11		5.7	25	15000	16	2100	460
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-10-12	8/28/2019	856.00	10 - 12 ft	180-94900-1	Not Excavated	8100	< 0.37 U	5.7	69	0.32 J	0.1 J	24000	11		7.1	21	18000	13	6500	750
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-4-6	8/28/2019	856.00	4 - 6 ft	180-94900-1	Not Excavated	7200	< 0.35 U	5.6	41	0.3 J	0.062 J	1000	9.4		6.2	19	16000	7.4	2100	350
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-6-8	8/28/2019	856.00	6 - 8 ft	180-94900-1	Not Excavated	5600	< 0.38 U	5.4	38	0.26 J	0.25 J	1300	7.4		4.6 J	14	12000	5.9	1700	730
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-8-10	8/28/2019	856.00	8 - 10 ft	180-94900-1	Not Excavated	6900	< 0.41 U	5.7	50	0.3 J	0.12 J	3600	10		6	24	17000	8.9	3000	660
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	6600	< 0.39 U	6.1	56	0.27 J	0.08 J	19000	11		5.1 J	18	14000	9.5	2600	380
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-2-4	8/28/2019	856.03	2 - 4 ft	180-94900-3	Excavated	11000	< 0.41 U	5.1	150	0.4 J	0.069 J	2700	16		6.6	13	14000	17	1900	930
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-10-12	8/28/2019	856.03	10 - 12 ft	180-94900-3	Not Excavated	4800	< 0.33 U	3.8	38	0.2 J	0.057 J	20000	6.5		4.6 J	11	10000	8.7	3200	390
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-4-6	8/28/2019	856.03	4 - 6 ft	180-94900-3	Not Excavated	8600	< 0.4 U	8.2	41	0.4 J	0.076 J	1500	11		6.6	23	18000	9.9	2100	520
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-6-8	8/28/2019	856.03	6 - 8 ft	180-94900-3	Not Excavated	8400	< 0.39 U	5.5	44	0.36 J	0.089 J	17000	9.3		5.6 J	22	16000	9	2500	460
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-8-10	8/28/2019	856.03	8 - 10 ft	180-94900-3	Not Excavated	5900	< 0.37 U	4.1	36	0.23 J	0.13 J	42000	8.1		5.1 J	16	13000	6.5	6800	500
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	7100	< 0.38 U	3.2 J	45	0.24 J	< 0.041 UJ	24000	9		5.6	30	16000	10	5100 J	370
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-4-6	8/27/2019	856.22	4 - 6 ft	180-94824-1	Excavated	10000	< 0.39 U	5.6	88	0.39 J	0.072 J	1100	13		7	18	17000	14	2300	580

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-8-10	8/27/2019	855.25	8 - 10 ft	180-94819-1	Not Excavated	< 0.015 U	16	780	< 0.62 U	< 0.13 U	67 J		< 0.39 U		13	63
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	0.017 J	15	800	0.71 J	< 0.12 U	110 J		< 0.36 U		10	47
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-2-4	8/27/2019	855.17	2 - 4 ft	180-94824-1	Excavated	0.022 J	18	970	< 0.62 U	< 0.13 U	< 31 U		< 0.39 U		18	55
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-10-12	8/27/2019	855.17	10 - 12 ft	180-94824-1	Not Excavated	0.033 J	16	800	< 0.61 U	< 0.12 U	< 30 U		< 0.38 U		12	61
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-4-6	8/27/2019	855.17	4 - 6 ft	180-94824-1	Not Excavated	0.014 J	14	670	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U		12	58
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-6-8	8/27/2019	855.17	6 - 8 ft	180-94824-1	Not Excavated	< 0.017 U	19	910	< 0.62 U	< 0.13 U	< 31 U		< 0.39 U		15	73
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-8-10	8/27/2019	855.17	8 - 10 ft	180-94824-1	Not Excavated	< 0.018 U	16	880	< 0.67 U	< 0.14 U	< 34 U		< 0.42 U		15	65
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	0.017 J	17	900	< 0.63 U	< 0.13 U	< 32 U		< 0.39 U		14	74
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-10-12	8/26/2019	855.10	10 - 12 ft	180-94752-3	Not Excavated	< 0.013 U	14	830	< 0.57 U	< 0.12 U	57 J		< 0.36 U		11	67
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-12-14	8/26/2019	855.10	12 - 14 ft	180-94752-3	Not Excavated	< 0.014 U	13	820	< 0.58 U	< 0.12 U	64 J		< 0.36 U		11	57
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-4-6	8/26/2019	855.10	4 - 6 ft	180-94752-3	Not Excavated	0.02 J	16	840	< 0.58 U	< 0.12 U	48 J		< 0.36 U		17	52
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-6-8	8/26/2019	855.10	6 - 8 ft	180-94752-3	Not Excavated	0.017 J	13	750	< 0.61 U	< 0.13 U	43 J		< 0.38 U		11	57
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-8-10	8/26/2019	855.10	8 - 10 ft	180-94752-3	Not Excavated	0.042	15	760	< 0.6 U	< 0.12 U	45 J		< 0.37 U		13	57
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	< 0.015 U	15	920	< 0.55 U	< 0.11 U	59 J		< 0.34 U		11	60 J-
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-2-4	8/26/2019	855.10	2 - 4 ft	180-94752-2	Excavated	0.018 J	16	< 63 U	< 0.6 U	< 0.12 U	49 J		< 0.37 U		18	56
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-10-12	8/26/2019	854.81	10 - 12 ft	180-94752-1	Not Excavated	< 0.015 U	12	620	< 0.56 U	< 0.11 U	65 J		< 0.35 U		10	43
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-6-8	8/26/2019	854.81	6 - 8 ft	180-94752-1	Not Excavated	< 0.016 U	14	810	< 0.54 U	< 0.11 U	82 J		< 0.34 U		12	48
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-8-10	8/26/2019	854.81	8 - 10 ft	180-94752-1	Not Excavated	0.019 J	14	810	0.63 J	< 0.11 U	100 J		< 0.33 U		11	47
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	< 0.014 U	15	760	< 0.57 U	< 0.12 U	89 J		< 0.36 U		10	59
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-2-4	8/26/2019	854.81	2 - 4 ft	180-94752-1	Excavated	0.023 J	15	770	< 0.59 U	< 0.12 U	53 J		< 0.36 U		14	78
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-4-6	8/26/2019	854.81	4 - 6 ft	180-94752-1	Excavated	0.066	15	750	< 0.58 U	< 0.12 U	66 J		< 0.36 U		11	57
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-10-12	9/3/2019	855.09	10 - 12 ft	180-95155-2	Not Excavated	< 0.014 U	10	710	0.96 J	< 0.11 U	84 J		< 0.35 U		7.1	45
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	< 0.015 U	12	760	< 0.55 U	< 0.11 U	81 J		< 0.34 U		9	43
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-2-4	9/3/2019	855.09	2 - 4 ft	180-95155-2	Not Excavated	0.029 J	12	570 J	< 0.63 U	< 0.13 U	< 32 U		< 0.39 U		15	49
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-4-6	9/3/2019	855.09	4 - 6 ft	180-95155-2	Not Excavated	0.027 J	15	670	< 0.61 U	< 0.13 U	31 J		< 0.38 U		17	51
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-6-8	9/3/2019	855.09	6 - 8 ft	180-95155-2	Not Excavated	0.019 J	17	860	< 0.55 U	< 0.11 U	40 J		< 0.35 U		13	55
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-8-10	9/3/2019	855.09	8 - 10 ft	180-95155-2	Not Excavated	< 0.015 U	17	1000	< 0.56 U	< 0.11 U	50 J		< 0.35 U		14	60
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-10-12	9/3/2019	855.76	10 - 12 ft	180-95162-1	Not Excavated	< 0.016 U	11	660	0.72 J	< 0.11 U	34 J		< 0.33 U		8.3	43
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	< 0.014 U	11	730	< 0.55 U	< 0.11 U	42 J		< 0.34 U		9.1	42
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-2-4	9/3/2019	855.76	2 - 4 ft	180-95162-1	Not Excavated	0.022 J	16	780	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U		18	51
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-4-6	9/3/2019	855.76	4 - 6 ft	180-95162-1	Not Excavated	< 0.014 U	17	850	< 0.62 U	< 0.13 U	< 31 U		< 0.39 U		18	55
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-6-8	9/3/2019	855.76	6 - 8 ft	180-95162-1	Not Excavated	< 0.016 U	18	970	< 0.6 U	< 0.12 U	< 30 U		< 0.37 U		15	60
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-8-10	9/3/2019	855.76	8 - 10 ft	180-95162-1	Not Excavated	< 0.015 U	17	820	< 0.53 UJ	< 0.11 U	27 J		< 0.33 U		12	52
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-10-12	8/30/2019	855.85	10 - 12 ft	180-95047-1	Not Excavated	< 0.017 U	17	790	< 0.55 U	< 0.11 U	41 J		< 0.35 U		14	54
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	< 0.017 U	17	830	< 0.6 U	< 0.12 U	66 J		< 0.38 U		13	66
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-2-4	8/30/2019	855.85	2 - 4 ft	180-95047-1	Not Excavated	0.05	18	860	< 0.61 U	< 0.13 U	39 J		< 0.38 U		17	58
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-4-6	8/30/2019	855.85	4 - 6 ft	180-95047-1	Not Excavated	< 0.017 U	17	830	< 0.58 U	< 0.12 U	65 J		< 0.36 U		13	63
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-6-8	8/30/2019	855.85	6 - 8 ft	180-95047-1	Not Excavated	< 0.014 U	11	510 J	< 0.54 U	< 0.11 U	63 J		< 0.34 U		8.3	43
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-8-10	8/30/2019	855.85	8 - 10 ft	180-95047-1	Not Excavated	< 0.016 U	16	640	< 0.6 U	< 0.12 U	44 J		< 0.37 U		16	51
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-10-12	8/29/2019	855.10	10 - 12 ft	180-95006-1	Not Excavated	< 0.013 U	17	720	0.81 J	< 0.12 U	99 J		< 0.36 U		15	40
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	< 0.014 U	13	700	0.7 J	< 0.11 U	78 J		< 0.34 U		9.6	51
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-2-4	8/29/2019	855.10	2 - 4 ft	180-95006-1	Not Excavated	0.031 J	14	610	< 0.62 U	< 0.13 U	62 J		< 0.39 U		17	45
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-4-6	8/29/2019	855.10	4 - 6 ft	180-95006-1	Not Excavated	< 0.017 U	16	710	< 0.53 U	< 0.11 U	48 J		< 0.33 U		12	57
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-6-8	8/29/2019	855.10	6 - 8 ft	180-95006-1	Not Excavated	< 0.015 U	16	690	< 0.57 U	< 0.12 U	69 J		< 0.36 U		10	63
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-8-10	8/29/2019	855.10	8 - 10 ft	180-95006-1	Not Excavated	< 0.016 U	12	780	0.89 J	< 0.12 U	100 J		< 0.35 U		8.9	38
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-2-4	8/29/2019	855.17	2 - 4 ft	180-94981-1	Excavated	0.019 J	17	770	< 0.61 U	< 0.12 U	48 J		< 0.38 U		17	57
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-4-6	8/29/2019	855.17	4 - 6 ft	180-94981-1	Excavated	< 0.016 U	15	810	< 0.58 U	< 0.12 U	61 J		< 0.36 U		14	60
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-10-12	8/29/2019	855.17	10 - 12 ft	180-94981-1	Not Excavated	< 0.014 U	14	810	0.88 J	< 0.11 U	110 J		< 0.34 U		9.6	45
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	< 0.014 U	13	640	0.63 J	< 0.11 U	79 J		< 0.33 U		9.5	50
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-6-8	8/29/2019	855.17	6 - 8 ft	180-94981-1	Not Excavated	< 0.015 U	11	680	< 0.6 U	< 0.12 U	73 J		< 0.37 U		9.4	46
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-8-10	8/29/2019	855.17	8 - 10 ft	180-94981-1	Not Excavated	< 0.014 U	16	750	< 0.54 U	< 0.11 U	67 J		< 0.34 U		12	65
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-2-4	8/28/2019	855.23	2 - 4 ft	180-94902-1	Excavated	< 0.014 U	11	570	0.71 J	< 0.11 U	67 J		< 0.34 U		8.1	39
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-4-6	8/28/2019	855.23	4 - 6 ft	180-94902-1	Excavated	< 0.014 U	19	680	< 0.57 U	< 0.12 U	42 J		< 0.35 U		11	63
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-6-8	8/28/2019	855.23	6 - 8 ft	180-94902-1	Excavated	< 0.016 U	16	620	< 0.61 U	< 0.12 U	44 J		< 0.38 U		17	54
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-8-10	8/28/2019	855.23	8 - 10 ft	180-94902-1	Not Excavated	< 0.015 U	13	570	< 0.54 U	< 0.11 U	66 J		< 0.34 U		9.4	44
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-10-12	8/28/2019	855.78	10 - 12 ft	180-94902-2	Not Excavated	< 0.016 U	13	620	< 0.59 U	< 0.12 U	56 J		< 0.37 U		8.6	47
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-2-4	8/28/2019	855.78	2 - 4 ft	180-94902-2	Not Excavated	0.038	13	550 J	< 0.61 U	< 0.12 U	46 J		< 0.38 U		16	47
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-4-6	8/28/2019	855.78	4 - 6 ft	180-94902-2	Not Excavated	0.025 J	16	850	< 0.59 U	< 0.12 U	52 J		< 0.37 U		13	52
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-6-8	8/28/2019	855.78	6 - 8 ft	180-94902-2	Not Excavated	< 0.014 U	15	660	< 0.54 U	< 0.11 U	68 J		< 0.34 U		10	49
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-8-10	8/28/2019	855.78	8 - 10 ft	180-94902-2	Not Excavated	< 0.014 U	15	710	< 0.54 U	< 0.11 U	59 J		< 0.34 U		11	60
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	< 0.014 U	14	780	< 0.55 U	< 0.11 U	60 J		< 0.34 U		10	55
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-2-4	8/28/2019	856.00	2 - 4 ft	180-94900-1	Excavated	0.036	13	640	< 0.57 U	< 0.12 U	50 J		< 0.36 U		14	50
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-10-12	8/28/2019	856.00	10 - 12 ft	180-94900-1	Not Excavated	0.02 J	17	760	< 0.56 U	< 0.11 U	82 J		< 0.35 U		12	68
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-4-6	8/28/2019	856.00	4 - 6 ft	180-94900-1	Not Excavated	0.015 J	16	710	< 0.53 U	< 0.11 U	41 J		< 0.33 U		12	59
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-6-8	8/28/2019	856.00	6 - 8 ft	180-94900-1	Not Excavated	0.015 J	13	770	< 0.58 U	< 0.12 U	43 J		< 0.36 U		9.2	49
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-8-10	8/28/2019	856.00	8 - 10 ft	180-94900-1	Not Excavated	0.016 J	15	790	< 0.62 U	< 0.13 U	50 J		< 0.38 U		12	66
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	< 0.016 U	13	900	< 0.59 U	< 0.12 U	110 J		< 0.37 U		11	48
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-2-4	8/28/2019	856.03	2 - 4 ft	180-94900-3	Excavated	0.067	12	620	< 0.63 U	< 0.13 U	59 J		< 0.39 U		17	57
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-10-12	8/28/2019	856.03	10 - 12 ft	180-94900-3	Not Excavated	< 0.014 U	9.7	590	< 0.5 U	< 0.1 U	77 J		< 0.31 U		7.7	38
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-4-6	8/28/2019	856.03	4 - 6 ft	180-94900-3	Not Excavated	< 0.013 U	15	960	< 0.6 U	< 0.12 U	47 J		< 0.38 U		15	51
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-6-8	8/28/2019	856.03	6 - 8 ft	180-94900-3	Not Excavated	< 0.015 U	13	930	< 0.59 U	< 0.12 U	97 J		< 0.37 U		15	55
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-8-10	8/28/2019	856.03	8 - 10 ft	180-94900-3	Not Excavated	< 0.014 U	13	620	0.63 J	< 0.11 U	77 J		< 0.34 U		8.9	87
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	< 0.013 U	14	620	< 0.58 U	< 0.12 U	78 J		< 0.36 U		10	60
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-4-6	8/27/2019	856.22	4 - 6 ft	180-94824-1	Excavated	0.021 J	17	720	< 0.59 U	< 0.12 U	73 J		< 0.37 U		14	57

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-10-12	8/27/2019	856.22	10 - 12 ft	180-94824-2	Not Excavated	6400	< 0.39 U	5.6	110	0.3 J	0.092 J	7300	9.3		5.6 J	23	14000	7.9	3000	520
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	10000	0.47 J	5.6	130	0.4 J	0.11 J	2500	11		5.8 J	22	14000	37	1800	560
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-6-8	8/27/2019	856.22	6 - 8 ft	180-94824-1	Not Excavated	8300	< 0.37 U	5.8	88	0.35 J	0.068 J	810	12		7.6	27	17000	9.9	2300	760
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-8-10	8/27/2019	856.22	8 - 10 ft	180-94824-1	Not Excavated	8600	< 0.4 U	7.2	56	0.41 J	0.076 J	2000	10		6.6	21	17000	9.7	2700	390
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	6300	< 0.36 U	6.6	58	0.24 J	0.086 J	25000	8.8		5.6	28	14000	8.3	8400	580
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-2-4	8/27/2019	856.24	2 - 4 ft	180-94819-1	Excavated	12000	0.69 J	12	140	0.59	0.5 J	3400	12		10	21	20000	33	2100	300
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-4-6	8/27/2019	856.24	4 - 6 ft	180-94819-1	Excavated	12000	0.42 J	11	100	0.57	0.084 J	2100	14		10	26	24000	17	2600	1300
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-10-12	8/27/2019	856.24	10 - 12 ft	180-94819-1	Not Excavated	5700	< 0.36 U	3	38	0.19 J	0.15 J	72000	7.4		5 J	16	13000	4.3	11000	390
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-6-8	8/27/2019	856.24	6 - 8 ft	180-94819-1	Not Excavated	9800	< 0.72 U	11	120	0.6 J	0.27 J	2000	13		6.9	25	21000	14	2900	1100
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-8-10	8/27/2019	856.24	8 - 10 ft	180-94819-1	Not Excavated	6700	< 0.37 U	6.8	43	0.28 J	0.1 J	84000	9.2		6	18	15000	8.7	9200	410
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	5600	< 0.38 U	6.1	59	0.21 J	0.12 J	49000	8.6		4.9 J	19	14000	6.9	11000	690
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-2-4	8/27/2019	856.08	2 - 4 ft	180-94819-2	Excavated	11000	< 0.43 U	6.2	77	0.43 J	0.055 J	1100	12		7.8	14	18000	12	2700	380
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-4-6	8/27/2019	856.08	4 - 6 ft	180-94819-2	Excavated	9000	< 0.4 U	6.4	60	0.41 J	0.058 J	1000	12		7.1	17	17000	13	2100	470
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-10-12	8/27/2019	856.08	10 - 12 ft	180-94819-2	Not Excavated	6800	< 0.39 U	6.1	59	0.27 J	0.099 J	7500	11		5.9	20	15000	7.9	3100	470
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-6-8	8/27/2019	856.08	6 - 8 ft	180-94819-2	Not Excavated	7400	< 0.37 U	6.5	65	0.3 J	0.064 J	840	11		7.1	20	16000	14	2100	750
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-8-10	8/27/2019	856.08	8 - 10 ft	180-94819-2	Not Excavated	6600	< 0.38 U	5.2	47	0.25 J	0.11 J	63000	9.6		6.1	22	14000	9.4	17000	550
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	7500	< 0.34 U	4.8	62	0.27 J	0.1 J	45000	12		7	26	16000	7.7	8100	480
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-10-12	8/26/2019	856.17	10 - 12 ft	180-94754-2	Not Excavated	6200	< 0.34 U	4.6	71	0.24 J	0.12 J	42000	8.1		5.8	21	15000	11	7000	440
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-12-14	8/26/2019	856.17	12 - 14 ft	180-94754-2	Not Excavated	6400	< 0.34 U	4.7	60	0.23 J	0.13 J	41000	9.9		6	22	16000	7.3	7700	380
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-4-6	8/26/2019	856.17	4 - 6 ft	180-94754-2	Not Excavated	12000	< 0.4 U	6.2	59	0.47	0.054 J	1000	12		6.4	15	20000	12	2500	230
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-6-8	8/26/2019	856.17	6 - 8 ft	180-94754-2	Not Excavated	6400	0.47 J	6	41	0.36 J	0.074 J	810	9.1		5.5	18	17000	8.4	1900	410
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-8-10	8/26/2019	856.17	8 - 10 ft	180-94754-2	Not Excavated	6000	< 0.36 U	3.8	37	0.25 J	0.24 J	16000	7.8		5 J	16	14000	6.5	4800	460
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	7900	< 0.37 U	4.5	56	0.28 J	0.11 J	25000	12		6.6	24	18000	8.3	7000	430
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-2-4	8/26/2019	856.17	2 - 4 ft	180-94754-2	Excavated	11000	0.41 J	5.9	77	0.46	0.069 J	1200	12		6.2	16	18000	22	2100	350
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-4-6	8/26/2019	855.60	4 - 6 ft	180-94752-1	Not Excavated	10000	< 0.38 U	7.6	50	0.46	0.088 J	940	13		9.2	21	21000	13	2700	590
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-6-8	8/26/2019	855.60	6 - 8 ft	180-94752-1	Not Excavated	7800	< 0.35 U	5.5	53	0.32 J	0.095 J	19000	14		6.2	20	16000	8.7	4200	430
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-8-10	8/26/2019	855.60	8 - 10 ft	180-94752-2	Not Excavated	7600	< 0.38 U	5.1	55	0.35 J	0.13 J	44000	16		6.3	40	17000	9.3	6000	540
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	6300	< 0.35 U	4.5	46	0.22 J	0.1 J	33000	11		5.1 J	21	14000	7.5	8700	570
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-2-4	8/26/2019	855.60	2 - 4 ft	180-94752-1	Excavated	11000	0.42 J	7.4	68	0.5	0.073 J	1200	14		7.4	18	19000	33	2300	390
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-10-12	9/4/2019	855.15	10 - 12 ft	180-95165-2	Not Excavated	4700	< 0.42 U	4.6	53	0.21 J	0.11 J	35000	6.8		4.6 J	12	11000	6.4	10000 J+	540
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	5700	< 0.35 U	5	61	0.22 J	0.086 J	38000	9.4		5.1 J	14	13000	7.6	9500	450
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-2-4	9/4/2019	855.15	2 - 4 ft	180-95165-1	Not Excavated	8300	< 0.37 U	5.3	51	0.33 J	0.075 J	1100	11		6.4	20	17000	7.2	2500	410
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-4-6	9/4/2019	855.15	4 - 6 ft	180-95165-1	Not Excavated	7900	< 0.37 U	6	60	0.32 J	0.12 J	5200	9.4		6.2	25	17000	12	3100	520
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-6-8	9/4/2019	855.15	6 - 8 ft	180-95165-1	Not Excavated	5200	< 0.36 U	3.8	46	0.23 J	0.075 J	18000	15		4.3 J	15	13000	6.2	3800	340
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-8-10	9/4/2019	855.15	8 - 10 ft	180-95165-1	Not Excavated	4900	< 0.36 U	3.2	49	0.19 J	0.078 J	40000	6.6		4.2 J	14	11000	7.7	17000	350
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-6-8	9/3/2019	855.98	6 - 8 ft	180-95153-3	Excavated	8300	0.57 J	7.1	88	0.39 J	0.16 J	2500	11		7.5	22	18000	29	2100	570
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-2-4	9/3/2019	855.98	2 - 4 ft	180-95153-3	Excavated	10000	< 0.4 U	8.2	98	0.54	0.13 J	3500	13		7.9	23	21000	27	2700	480
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-4-6	9/3/2019	855.98	4 - 6 ft	180-95153-3	Excavated	8800	3.3	8.2	92	0.46 J	0.18 J	5000	12		6.6	25	19000	34	2300	390
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	5500	0.43 J	7.1	57	0.27 J	0.089 J	14000	7.1		5.6 J	20	14000	12	8500	770
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-8-10	9/3/2019	855.98	8 - 10 ft	180-95153-3	Not Excavated	7600	< 0.38 U	9.1	51	0.35 J	0.064 J	1200	9.6		6.1	20	17000	15	2000	350
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-10-12	9/3/2019	855.98	10 - 12 ft	180-95153-3	Not Excavated	5000	< 0.38 U	6.2	45	0.28 J	0.14 J	14000	7.4		5.6	15	13000	9.9	6600	690
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-10-12	9/3/2019	856.41	10 - 12 ft	180-95155-3	Not Excavated	5100	< 0.35 U	5.5	41	0.19 J	0.064 J	13000	8		5 J	13	13000	31	4600	350
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	4900	< 0.37 U	5.3	54	0.18 J	0.12 J	37000	7.2		4.8 J	19	11000	11	16000	480
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-2-4	9/3/2019	856.41	2 - 4 ft	180-95155-3	Not Excavated	10000	0.44 J	6	99	0.4 J	0.068 J	590 J	11		6.5 J	23	18000	20	2000	460
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-4-6	9/3/2019	856.41	4 - 6 ft	180-95155-3	Not Excavated	10000	0.44 J	7	55	0.43 J	0.059 J	370 J	12		7.3	19	21000	10	2400	310
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-6-8	9/3/2019	856.41	6 - 8 ft	180-95155-3	Not Excavated	8200	< 0.39 U	6.7	97	0.35 J	0.091 J	770	11		6.8	24	18000	11	2400	530
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-8-10	9/3/2019	856.41	8 - 10 ft	180-95155-3	Not Excavated	7100	< 0.38 U	6.7	74	0.32 J	0.1 J	1500	10		6.4	23	17000	23	2500	590
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-10-12	8/29/2019	856.01	10 - 12 ft	180-95024-2	Not Excavated	6400	< 0.35 U	5.6	55	0.23 J	0.1 J	38000	20		6.1	22	15000	12	16000	480
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	6400	< 0.37 U	4.3	53	0.23 J	0.09 J	43000	10		5.7	18	15000	12	14000	480
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-2-4	8/29/2019	856.01	2 - 4 ft	180-95024-2	Not Excavated	11000	< 0.42 U	6.9	71	0.42 J	0.07 J	1700	13		7.8	16	20000	14	2400	480
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-4-6	8/29/2019	856.01	4 - 6 ft	180-95024-2	Not Excavated	9200	< 0.37 U	6.3	50 J	0.37 J	0.072 J	2600	12		8.2	20	18000	11	3600	510
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-6-8	8/29/2019	856.01	6 - 8 ft	180-95024-2	Not Excavated	6500	< 0.38 U	3.4	62	0.24 J	0.083 J	34000	10		5.6	17	15000	6.2	7700	430
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-8-10	8/29/2019	856.01	8 - 10 ft	180-95024-2	Not Excavated	6200	< 0.37 U	4.5	49	0.24 J	0.084 J	25000	9.2		5.6	19	14000	6.6	7100	430
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-10-12	8/29/2019	856.20	10 - 12 ft	180-95006-1	Not Excavated	6200	< 0.36 U	5.1	48	0.24 J	0.083 J	34000	9		5.4	16	14000	6.8	6200	540
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	6400	< 0.36 U	13	46	0.25 J	0.073 J	33000	10		5.8	22	15000	6.9	4600	460
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-2-4	8/29/2019	856.20	2 - 4 ft	180-95006-1	Not Excavated	8800	0.53 J	7.2	75	0.45	0.086 J	1200	11		6	20	17000	37 J-	2000	410
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-4-6	8/29/2019	856.20	4 - 6 ft	180-95006-1	Not Excavated	10000	0.78 J	7.4	68	0.45 J	0.062 J	1100	11		7.6	17	18000	37	2200	450
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-6-8	8/29/2019	856.20	6 - 8 ft	180-95006-1	Not Excavated	12000	0.39 J	9.4	91	0.56	0.089 J	1900	14		8.6	23	23000	13	3500	490
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-8-10	8/29/2019	856.20	8 - 10 ft	180-95006-1	Not Excavated	7800	< 0.38 U	5.5	62	0.34 J	0.086 J	8000 J	10		6.4	19	16000	10 J	4800	560
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-10-12	8/29/2019	855.88	10 - 12 ft	180-94981-1	Not Excavated	7400	< 0.39 U	8	66	0.36 J	0.13 J	35000	15		11	27	20000	21	15000	550
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	6500	< 0.4 U	5.4	56	0.28 J	0.093 J	17000	8.4		5.1 J	22	14000	6.8	7800	500
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-2-4	8/29/2019	855.88	2 - 4 ft	180-94981-1	Not Excavated	11000	< 0.44 U	7	110	0.45 J	< 0.047 U	4900	12		7.2	19	17000	18	2400	670
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-4-6	8/29/2019	855.88	4 - 6 ft	180-94981-1	Not Excavated	10000	0.5 J	6.2	79	0.44 J	0.048 J	1800	13		7.2	14	17000	11	2300	600
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-6-8	8/29/2019	855.88	6 - 8 ft	180-94981-1	Not Excavated	7600	0.41 J	6.5	72	0.33 J	0.12 J	9200	11		6.1	18	15000	11	4300	670
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-8-10	8/29/2019	855.88	8 - 10 ft	180-94981-1	Not Excavated	7200	0.42 J	5.8	61	0.3 J	0.11 J	22000	17		6.4	21	16000	9.3	7900	710
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-10-12	8/28/2019	856.09	10 - 12 ft	180-94900-3	Not Excavated	6200	< 0.38 U	5.5	37	0.29 J	0.05 J	2000	9		5.5 J	17	15000	8.3	2200	400
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	6000	< 0.38 U	6.7	34	0.32 J	0.087 J	1900	8.4		5.6	16	15000	7.9	2200	320
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-2-4	8/28/2019	856.09	2 - 4 ft	180-94900-3	Not Excavated	9900	< 0.38 U	6.7	60	0.42 J	< 0.041 U	3800	11		7.7	19	18000	14	2300	600
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-4-6	8/28/2019	856.09	4 - 6 ft	180-94900-3	Not Excavated	13000	0.43 J	9.2	42	0.57	< 0.043 U	1100	14		10	23	24000	11	3000	500
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-6-8	8/28/2019	856.09	6 - 8 ft	180-94900-3	Not Excavated	12000	0.42 J	11	110 J-	0.55	0.1 J	12000	16 J-		10	33 J-	24000	16	2900 J-	760
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-8-10	8/28/2019	856.09	8 - 10 ft	180-94900-3	Not Excavated	11000	0.51 J	8.1	42	0.5	< 0.044 U	1200	12		9.3	19	20000	10	2400	410
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-10-12	8/28/2019	856.47	10 - 12 ft	180-94902-2	Not Excavated	6600	< 0.39 U	5.5	45	0.25 J	0.12 J	21000	9.8		6.8	27	17000	7.8	6100	510
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	6900	< 0.43 U	8.6	56	0.29 J	0.13 J	29000	10		6.5	21	16000	9.3	10000	520
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-2-4	8/28/2019	856.47	2 - 4 ft	180-94902-2	Not Excavated	6100 J	0.45 J	8.3	92	0.49 J	0.14 J	2500	11		7.2	61	20000	33	1600	210

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-10-12	8/27/2019	856.22	10 - 12 ft	180-94824-2	Not Excavated	< 0.017 U	14	680	< 0.58 U	< 0.12 U	78 J		< 0.36 U		10	57
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	0.074	14	580 J	< 0.62 U	< 0.13 U	68 J		< 0.38 U		15	66
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-6-8	8/27/2019	856.22	6 - 8 ft	180-94824-1	Not Excavated	0.019 J	17	780	< 0.56 U	< 0.11 U	51 J		< 0.35 U		13	54
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-8-10	8/27/2019	856.22	8 - 10 ft	180-94824-1	Not Excavated	< 0.016 U	17	1100	< 0.61 U	< 0.12 U	65 J		< 0.38 U		15	73
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	< 0.013 U	14	690	< 0.55 U	< 0.11 U	74 J		< 0.34 U		9	53
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-2-4	8/27/2019	856.24	2 - 4 ft	180-94819-1	Excavated	0.15	120	680	1.2	< 0.12 U	75 J		< 0.37 U		18	100
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-4-6	8/27/2019	856.24	4 - 6 ft	180-94819-1	Excavated	0.039	29	1100	< 0.62 U	< 0.13 U	63 J		< 0.38 U		19	70
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-10-12	8/27/2019	856.24	10 - 12 ft	180-94819-1	Not Excavated	< 0.015 U	13	580	0.84 J	< 0.11 U	110 J		< 0.34 U		8.4	55
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-6-8	8/27/2019	856.24	6 - 8 ft	180-94819-1	Not Excavated	0.15	250	1200	< 1.1 U	< 0.22 U	56 J		< 0.34 U		17	95
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-8-10	8/27/2019	856.24	8 - 10 ft	180-94819-1	Not Excavated	0.033 J	29	700	1.3	< 0.12 U	100 J		< 0.35 U		11	46
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	< 0.015 U	17	680	0.86 J	< 0.12 U	87 J		< 0.36 U		9.8	50
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-2-4	8/27/2019	856.08	2 - 4 ft	180-94819-2	Excavated	0.071	17	770	< 0.66 U	< 0.13 U	59 J		< 0.41 U		15	55
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-4-6	8/27/2019	856.08	4 - 6 ft	180-94819-2	Excavated	0.049	16	780	< 0.6 U	< 0.12 U	57 J		< 0.37 U		14	63
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-10-12	8/27/2019	856.08	10 - 12 ft	180-94819-2	Not Excavated	0.015 J	15	830	< 0.59 U	< 0.12 U	59 J		< 0.37 U		10	57
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-6-8	8/27/2019	856.08	6 - 8 ft	180-94819-2	Not Excavated	< 0.015 U	16	730	< 0.56 U	< 0.11 U	56 J		< 0.35 U		11	60
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-8-10	8/27/2019	856.08	8 - 10 ft	180-94819-2	Not Excavated	< 0.015 U	15	750	1.1	< 0.12 U	110 J		< 0.36 U		11	49
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	< 0.015 U	19	860	0.75 J	< 0.11 U	91 J		< 0.32 U		15	60
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-10-12	8/26/2019	856.17	10 - 12 ft	180-94754-2	Not Excavated	0.16	14	610	0.67 J	< 0.11 U	66 J		< 0.32 U		9	58
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-12-14	8/26/2019	856.17	12 - 14 ft	180-94754-2	Not Excavated	0.041	15	680	0.76 J	< 0.11 U	95 J		< 0.33 U		11	54
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-4-6	8/26/2019	856.17	4 - 6 ft	180-94754-2	Not Excavated	0.061	17	780	< 0.6 U	< 0.12 U	55 J		< 0.37 U		17	60
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-6-8	8/26/2019	856.17	6 - 8 ft	180-94754-2	Not Excavated	0.049	14	590	< 0.54 U	< 0.11 U	38 J		< 0.34 U		10	47
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-8-10	8/26/2019	856.17	8 - 10 ft	180-94754-2	Not Excavated	0.023 J	13	520	< 0.54 U	< 0.11 U	49 J		< 0.34 U		8.3	110
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	0.074	17	730	0.59 J	< 0.11 U	72 J		< 0.35 U		12	67
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-2-4	8/26/2019	856.17	2 - 4 ft	180-94754-2	Excavated	0.03 J	14	680	0.66 J	< 0.12 U	57 J		< 0.37 U		17	59
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-4-6	8/26/2019	855.60	4 - 6 ft	180-94752-1	Not Excavated	0.035 J	19	1100	< 0.58 U	< 0.12 U	54 J		< 0.36 U		17	63
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-6-8	8/26/2019	855.60	6 - 8 ft	180-94752-1	Not Excavated	0.053	16	970	< 0.53 U	< 0.11 U	72 J		< 0.33 U		13	50
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-8-10	8/26/2019	855.60	8 - 10 ft	180-94752-2	Not Excavated	0.039	16	< 62 U	0.81 J	< 0.12 U	93 J		< 0.36 U		12	60
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	< 0.014 U	13	810	< 0.54 U	< 0.11 U	89 J		< 0.33 U		10	50
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-2-4	8/26/2019	855.60	2 - 4 ft	180-94752-1	Excavated	0.15	21	790	< 0.59 U	< 0.12 U	74 J		< 0.37 U		18	57
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-10-12	9/4/2019	855.15	10 - 12 ft	180-95165-2	Not Excavated	< 0.016 U	11	760	< 0.63 U	< 0.13 U	90 J		< 0.39 U		8	38
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	< 0.015 U	12	760	0.6 J	< 0.11 U	110 J		< 0.33 U		8.3	42
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-2-4	9/4/2019	855.15	2 - 4 ft	180-95165-1	Not Excavated	0.034	15	680	< 0.56 U	< 0.11 U	43 J		< 0.35 U		13	54
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-4-6	9/4/2019	855.15	4 - 6 ft	180-95165-1	Not Excavated	< 0.014 U	16	710	< 0.56 U	< 0.11 U	50 J		< 0.35 U		11	100
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-6-8	9/4/2019	855.15	6 - 8 ft	180-95165-1	Not Excavated	< 0.013 U	11	660	< 0.55 U	< 0.11 U	62 J		< 0.34 U		9	45
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-8-10	9/4/2019	855.15	8 - 10 ft	180-95165-1	Not Excavated	< 0.015 U	9.7	540	< 0.55 U	< 0.11 U	98 J		< 0.34 U		6.8	50
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-6-8	9/3/2019	855.98	6 - 8 ft	180-95155-3	Excavated	0.032	17	640	< 0.56 U	< 0.12 U	61 J		< 0.35 U		14	58
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-2-4	9/3/2019	855.98	2 - 4 ft	180-95155-3	Excavated	0.017 J	19	750	< 0.61 U	< 0.12 U	54 J		< 0.38 U		17	64
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-4-6	9/3/2019	855.98	4 - 6 ft	180-95155-3	Excavated	0.035	17	650	< 0.6 U	< 0.12 U	86 J		< 0.37 U		15	60
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	< 0.016 U	13	640	< 0.6 U	< 0.12 U	< 30 U		< 0.38 U		10	48
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-8-10	9/3/2019	855.98	8 - 10 ft	180-95155-3	Not Excavated	< 0.015 U	15	620	< 0.57 U	< 0.12 U	40 J		< 0.36 U		13	56
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-10-12	9/3/2019	855.98	10 - 12 ft	180-95155-3	Not Excavated	< 0.015 U	13	650	< 0.58 U	< 0.12 U	62 J		< 0.36 U		9.1	62
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-10-12	9/3/2019	856.41	10 - 12 ft	180-95155-3	Not Excavated	< 0.014 U	11	730	< 0.53 U	< 0.11 U	47 J		< 0.33 U		9.6	42
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	< 0.014 U	11	620	0.75 J	< 0.11 U	160 J		< 0.35 U		8.6	63
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-2-4	9/3/2019	856.41	2 - 4 ft	180-95155-3	Not Excavated	0.065	14	550 J	< 0.66 U	< 0.14 U	35 J		< 0.41 U		17	60
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-4-6	9/3/2019	856.41	4 - 6 ft	180-95155-3	Not Excavated	< 0.014 U	18	670	< 0.59 U	< 0.12 U	33 J		< 0.37 U		21	55
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-6-8	9/3/2019	856.41	6 - 8 ft	180-95155-3	Not Excavated	< 0.015 U	16	940	< 0.59 U	< 0.12 U	42 J		< 0.37 U		14	75
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-8-10	9/3/2019	856.41	8 - 10 ft	180-95155-3	Not Excavated	< 0.015 U	15	740	< 0.58 U	< 0.12 U	46 J		< 0.36 U		11	64
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-10-12	8/29/2019	856.01	10 - 12 ft	180-95024-2	Not Excavated	< 0.015 U	15	640	< 0.54 U	< 0.11 U	72 J		< 0.33 U		9.5	49
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	< 0.014 U	14	710	0.62 J	< 0.12 U	81 J		< 0.35 U		11	55
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-2-4	8/29/2019	856.01	2 - 4 ft	180-95024-2	Not Excavated	0.032 J	17	650	< 0.63 U	< 0.13 U	41 J		< 0.39 U		20	56
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-4-6	8/29/2019	856.01	4 - 6 ft	180-95024-2	Not Excavated	0.016 J	19	910	< 0.57 U	< 0.12 U	40 J		< 0.35 U		14	65
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-6-8	8/29/2019	856.01	6 - 8 ft	180-95024-2	Not Excavated	< 0.014 U	12	770	< 0.58 U	< 0.12 U	69 J		< 0.36 U		11	44
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-8-10	8/29/2019	856.01	8 - 10 ft	180-95024-2	Not Excavated	< 0.014 U	13	730	< 0.57 U	< 0.12 U	64 J		< 0.35 U		10	44
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-10-12	8/29/2019	856.20	10 - 12 ft	180-95006-1	Not Excavated	< 0.017 U	13	720	0.76 J	< 0.11 U	78 J		< 0.34 U		9.7	43
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	< 0.014 U	15	660	0.66 J	< 0.11 U	74 J		< 0.34 U		9.7	55
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-2-4	8/29/2019	856.20	2 - 4 ft	180-95006-1	Not Excavated	0.1	14	640	< 0.58 U	< 0.12 U	49 J		< 0.36 U		14	60 J-
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-4-6	8/29/2019	856.20	4 - 6 ft	180-95006-1	Not Excavated	0.027 J	16	810	< 0.63 U	< 0.13 U	57 J		< 0.39 U		16	52
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-6-8	8/29/2019	856.20	6 - 8 ft	180-95006-1	Not Excavated	< 0.018 U	22	1300	< 0.59 U	< 0.12 U	53 J		< 0.37 U		19	88
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-8-10	8/29/2019	856.20	8 - 10 ft	180-95006-1	Not Excavated	0.026 J	16	740	< 0.58 U	< 0.12 U	56 J		< 0.36 U		12	55
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-10-12	8/29/2019	855.88	10 - 12 ft	180-94981-1	Not Excavated	< 0.016 U	24	1300	< 0.59 U	< 0.12 U	99 J		< 0.37 U		20	63
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	0.018 J	13	850	< 0.6 U	< 0.12 U	63 J		< 0.37 U		11	47
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-2-4	8/29/2019	855.88	2 - 4 ft	180-94981-1	Not Excavated	0.043	15	650	< 0.66 U	< 0.13 U	58 J		< 0.41 U		16	55
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-4-6	8/29/2019	855.88	4 - 6 ft	180-94981-1	Not Excavated	0.023 J	15	840	< 0.6 U	< 0.12 U	44 J		< 0.38 U		17	52
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-6-8	8/29/2019	855.88	6 - 8 ft	180-94981-1	Not Excavated	0.024 J	16	940	< 0.6 U	< 0.12 U	57 J		< 0.37 U		12	57
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-8-10	8/29/2019	855.88	8 - 10 ft	180-94981-1	Not Excavated	0.051	15	810	< 0.59 U	< 0.12 U	60 J		< 0.37 U		12	63
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-10-12	8/28/2019	856.09	10 - 12 ft	180-94900-3	Not Excavated	< 0.016 U	14	770	< 0.58 U	< 0.12 U	59 J		< 0.36 U		11	50
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	< 0.016 U	14	860	< 0.57 U	< 0.12 U	55 J		< 0.35 U		11	49
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-2-4	8/28/2019	856.09	2 - 4 ft	180-94900-3	Not Excavated	0.048	15	750	< 0.58 U	< 0.12 U	61 J		< 0.36 U		16	51
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-4-6	8/28/2019	856.09	4 - 6 ft	180-94900-3	Not Excavated	0.032 J	21	1100	< 0.61 U	< 0.12 U	64 J		< 0.38 U		20	61
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-6-8	8/28/2019	856.09	6 - 8 ft	180-94900-3	Not Excavated	< 0.015 U	24	1300 J-	< 0.58 U	< 0.12 U	75 J		< 0.36 U		21 J-	110 J-
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-8-10	8/28/2019	856.09	8 - 10 ft	180-94900-3	Not Excavated	< 0.015 U	17	920	< 0.62 U	< 0.13 U	69 J		< 0.39 U		17	49
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-10-12	8/28/2019	856.47	10 - 12 ft	180-94902-2	Not Excavated	< 0.015 U	14	840	< 0.59 U	< 0.12 U	74 J		< 0.37 U		15	67
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	< 0.016 U	17	840	< 0.65 U	< 0.13 U	93 J		< 0.4 U		12	62
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-2-4	8/28/2019	856.47	2 - 4 ft	180-94902-2	Not Excavated	0.067	18	580 J	0.76 J	< 0.12 U	65 J		< 0.35 U		15	65

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**	**Lead**	**Magnesium**	**Manganese**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-4-6	8/28/2019	856.47	4 - 6 ft	180-94902-2	Not Excavated	13000	< 0.41 U	5.8	51	0.44 J	0.051 J	600	13		7.2	12	20000	10	2700	240
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-6-8	8/28/2019	856.47	6 - 8 ft	180-94902-2	Not Excavated	9300	< 0.39 U	5.6	55	0.35 J	0.073 J	590	12		9	21	19000	9.9	2700	550
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-8-10	8/28/2019	856.47	8 - 10 ft	180-94902-2	Not Excavated	12000	< 0.42 U	13	88	0.62	0.08 J	1300	15		8.6	35	26000	22	2500	640
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-2-4	8/28/2019	856.71	2 - 4 ft	180-94902-1	Excavated	6900	2.8	12	120	0.36 J	0.42 J	2100	17		6.4	91	52000	83	1300	360
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-10-12	8/28/2019	856.71	10 - 12 ft	180-94902-1	Not Excavated	7900	< 0.4 U	4.2	47	0.26 J	0.097 J	17000	10		5.6 J	43	17000	8.1	7400	510
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	5400	< 0.34 U	5.1	46	0.19 J	0.081 J	12000	6.7		4.4 J	17	12000	7.5	6100	490
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-4-6	8/28/2019	856.71	4 - 6 ft	180-94902-1	Not Excavated	12000	0.42 J	4.9	95	0.44 J	0.067 J	1600	13		7.9	17	18000	11	2300	440
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-6-8	8/28/2019	856.71	6 - 8 ft	180-94902-1	Not Excavated	8400	< 0.4 U	5.5	52	0.34 J	0.078 J	14000	10		5.7 J	30	15000	10	6800	480
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-8-10	8/28/2019	856.71	8 - 10 ft	180-94902-1	Not Excavated	7000	< 0.36 U	5.5	49	0.28 J	0.11 J	11000	8.8		5.1 J	15	14000	8.7	5300	780
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-2-4	8/28/2019	856.96	2 - 4 ft	180-94900-2	Excavated	6400	0.58 J	5.9	65	0.38 J	0.12 J	3600	9.2		5 J	45	14000	59	1400	260
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-10-12	8/28/2019	856.96	10 - 12 ft	180-94900-2	Not Excavated	6100	< 0.35 U	4.4	75	0.23 J	0.086 J	53000	8.6		5.6	18	13000	12	5600	550
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-12-14	8/28/2019	856.96	12 - 14 ft	180-94900-2	Not Excavated	6200	< 0.38 U	7	44	0.25 J	0.12 J	44000	10		5.7 J	17	14000	9.2	5100 J	350
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-4-6	8/28/2019	856.96	4 - 6 ft	180-94900-2	Not Excavated	13000	< 0.39 U	6.9	60	0.5	< 0.042 U	1100	15		8.9	14	22000	10	2700	280
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-6-8	8/28/2019	856.96	6 - 8 ft	180-94900-2	Not Excavated	10000	< 0.38 U	7	70	0.42 J	0.072 J	1400	14		7.6	22	20000	12	2700	440
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-8-10	8/28/2019	856.96	8 - 10 ft	180-94900-2	Not Excavated	7600	< 0.4 U	7.2	70	0.33 J	0.095 J	17000	9.2		5.9	22	16000	8.5	9400	400
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	5700	< 0.36 U	5.3	51	0.22 J	0.08 J	38000	11		5 J	18	14000	14	7200	390
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-10-12	8/27/2019	857.02	10 - 12 ft	180-94824-1	Not Excavated	5900	< 0.37 U	5.2	50	0.25 J	0.12 J	25000	8.5		5.8	21	14000	9.2	9500	510
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-6-8	8/27/2019	857.02	6 - 8 ft	180-94824-1	Not Excavated	9200	< 0.42 U	6.4	64	0.4 J	0.095 J	3600	11		7.5	16	17000	12	3500	600
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-8-10	8/27/2019	857.02	8 - 10 ft	180-94824-1	Not Excavated	7000	< 0.37 U	6.4	61	0.3 J	0.083 J	5400	9.3		6.3	18	16000	9.2	3100	430
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	6000	< 0.37 U	5.4	45	0.21 J	0.17 J	44000	9.9		5.6	16	13000	13	9300	480
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-2-4	8/27/2019	857.02	2 - 4 ft	180-94824-1	Excavated	9400	0.41 J-	6.7	85	0.42 J	0.13 J	12000	11		6.3	25	17000	53 J-	2700	390
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-4-6	8/27/2019	857.02	4 - 6 ft	180-94824-1	Excavated	11000	< 0.42 U	5.2	75	0.44 J	< 0.045 U	1300	11		6.2	11	16000	12	2100	300
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-4-6	8/27/2019	856.91	4 - 6 ft	180-94819-3	Not Excavated	9000	0.65 J	9	120	0.51	0.2 J	14000	12		8.2	39	23000	83	2500	460
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-6-8	8/27/2019	856.91	6 - 8 ft	180-94819-3	Not Excavated	7300	< 0.38 UJ	7.2	49 J	0.35 J	0.059 J	2600	9.7		7	20	17000	12	2100	550
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-8-10	8/27/2019	856.91	8 - 10 ft	180-94819-3	Not Excavated	5500	< 0.37 U	4.5	33	0.22 J	0.1 J	31000	7.9		4.7 J	19	13000	8.3	17000	410
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	5600	< 0.39 U	5.3	30	0.2 J	0.11 J	63000	7.9		4.3 J	14	11000	19	13000	330
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-2-4	8/27/2019	856.91	2 - 4 ft	180-94819-3	Excavated	10000	< 0.41 U	7.7	130	0.58	0.18 J	33000	13		7.3	28	19000	52	4100	400
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-10-12	8/27/2019	856.95	10 - 12 ft	180-94819-1	Not Excavated	5700	< 0.34 UJ	4.5	42	0.21 J	0.12 J	40000	7.7		5.4	17	13000	6.4	8100 J-	410
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-8-10	8/27/2019	856.95	8 - 10 ft	180-94819-1	Not Excavated	8600	< 0.36 U	6	72	0.33 J	0.088 J	6300	11		7	25	19000	10	5000	720
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	4900	< 0.37 U	4.4	41	0.21 J	0.12 J	51000	9.1		4.8 J	17	12000	6.6	7800	390
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-2-4	8/27/2019	856.95	2 - 4 ft	180-94819-1	Excavated	9200	0.45 J	7.1	83	0.42 J	0.55 J	9100	12		7.6	20	20000	50	3500	570
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-4-6	8/27/2019	856.95	4 - 6 ft	180-94819-1	Excavated	12000	0.47 J	7.3	52	0.5	< 0.041 U	1200	14		9.1	17	21000	10	3000	350
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-6-8	8/27/2019	856.95	6 - 8 ft	180-94819-1	Excavated	8700	< 0.38 U	10	160	0.41 J	0.044 J	4700	12		6.3	27	19000	9.3	3700	380
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-10-12	8/26/2019	856.77	10 - 12 ft	180-94754-2	Not Excavated	5900	< 0.38 U	4.2	49	0.23 J	0.12 J	52000	8.5		5.3 J	28	14000	12	8800	480
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated	4000	0.38 J	4.2	37	0.18 J	0.1 J	59000	13		3.8 J	19	11000	7.1	22000	370
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-6-8	8/26/2019	856.77	6 - 8 ft	180-94754-2	Not Excavated	8300	1.8	9.6	84	0.43 J	0.2 J	6700	16		7.7	85	22000	76	2600	640
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-8-10	8/26/2019	856.77	8 - 10 ft	180-94754-2	Not Excavated	6300	< 0.37 U	4.5	48	0.28 J	0.12 J	35000	9.1		6.2	25	15000	10	5000	650
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-2-4	8/26/2019	856.77	2 - 4 ft	180-94754-1	Excavated	7400	4.3 J	8.3	87	0.41 J	0.34 J	9600 J	14		7.5	150 J+	26000	140 J	2300	490
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-4-6	8/26/2019	856.77	4 - 6 ft	180-94754-1	Excavated	8200	0.39 J	7	42	0.44 J	0.068 J	2700	10		6.8	20	17000	17	2300	310
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-10-12	8/26/2019	856.77	10 - 12 ft	180-94752-3	Not Excavated	5200	< 0.37 UJ	4.9	42	0.21 J	0.11 J	57000	7		5.4	29	12000	7	19000	500
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated	5700	< 0.37 U	4.4	62	0.22 J	0.09 J	38000	8.4		5.3 J	21	13000	5.9	13000	330
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-4-6	8/26/2019	856.77	4 - 6 ft	180-94752-3	Not Excavated	10000	0.57 J	5.9	800	0.41 J	0.074 J	7100	13		7	32	18000	33	2900	370
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-6-8	8/26/2019	856.77	6 - 8 ft	180-94752-3	Not Excavated	6100	0.47 J	3.8	57	0.25 J	0.076 J	32000	9.2		5 J	22	12000	11	4200	330
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-8-10	8/26/2019	856.77	8 - 10 ft	180-94752-3	Not Excavated	6500	0.45 J	5.6	42	0.27 J	0.11 J	39000	9.2		5.5	21	16000	8.7	13000	440
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-2-4	8/26/2019	856.77	2 - 4 ft	180-94752-3	Excavated	9700	0.81 J	7.5	97	0.46 J	0.13 J	8200	13		7.3	39	19000	47	2700	450
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-10-12	9/4/2019	855.86	10 - 12 ft	180-95165-1	Not Excavated	5300	< 0.36 U	4.5	43	0.21 J	0.12 J	39000	9.1		5 J	21	14000	10	9700	480
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	7100	< 0.36 U	4.5	46	0.27 J	0.076 J	26000	13		6	23	17000	7	6000	470
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-2-4	9/4/2019	855.86	2 - 4 ft	180-95165-1	Not Excavated	7000	< 0.39 U	4.4	46	0.28 J	0.045 J	1000	10		6	27	17000	6	2500	510
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-4-6	9/4/2019	855.86	4 - 6 ft	180-95165-1	Not Excavated	6000	< 0.37 U	4	58	0.22 J	0.14 J	44000	8.7		5.2 J	55	14000	4.2	4200	630
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-6-8	9/4/2019	855.86	6 - 8 ft	180-95165-1	Not Excavated	6400	< 0.39 UJ	4.1	46	0.26 J	0.089 J	38000	10		5.7	25	15000	6.6	8500 J	460
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-8-10	9/4/2019	855.86	8 - 10 ft	180-95165-1	Not Excavated	5600	< 0.35 U	5.3	39	0.23 J	0.22 J	24000	8.3		5.3	16	14000	6.8	4800	350
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-10-12	9/3/2019	856.40	10 - 12 ft	180-95162-1	Not Excavated	6300	< 0.39 U	6.2	36	0.29 J	0.13 J	22000	7.9		5.3 J	16	14000	8.1	4200	340
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-12-14	9/3/2019	856.40	12 - 14 ft	180-95162-1	Not Excavated	6800	< 0.39 U	5.5	42	0.29 J	0.15 J	32000	8.9		5.8	20	15000	9.9	5200	630
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	6200	< 0.36 U	5.5	46	0.26 J	0.062 J	15000	8.2		5.9	23	15000	6.6	4400	370
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-2-4	9/3/2019	856.40	2 - 4 ft	180-95162-1	Not Excavated	10000	0.38 J	6.3	51	0.4 J	0.047 J	240 J	11		6.7	16	17000	9.1	2100	310
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-4-6	9/3/2019	856.40	4 - 6 ft	180-95162-1	Not Excavated	9400	0.49 J	11	69	0.49	0.058 J	880	11		8.6	29	22000	17	2000	480
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-6-8	9/3/2019	856.40	6 - 8 ft	180-95162-1	Not Excavated	10000	0.47 J	7	51	0.43 J	0.074 J	1000	12		6.7	20	19000	10	2500	430
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-8-10	9/3/2019	856.40	8 - 10 ft	180-95162-1	Not Excavated	5800	< 0.38 U	6.4	33	0.29 J	0.12 J	8300	7.7		5.6	18	15000	34	3000	390
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-10-12	8/30/2019	856.38	10 - 12 ft	180-95050-1	Not Excavated	5700	< 0.36 U	6.3	25	0.29 J	0.11 J	6900	7.6		5.5	16	14000	7.5	2800	280
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	4300	< 0.36 U	3.7	26	0.15 J	0.078 J	36000	7.6		5.2 J	13	10000	8.8	14000	300
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-2-4	8/30/2019	856.38	2 - 4 ft	180-95050-1	Not Excavated	9000	< 0.37 U	7.8	75	0.4 J	0.069 J	560 J	11		6.8	24	18000	11	2000	380
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-4-6	8/30/2019	856.38	4 - 6 ft	180-95050-1	Not Excavated	9100	< 0.39 U	8.6	83	0.42 J	0.063 J	1100	11		7.1	22	19000	10	2200	460
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-6-8	8/30/2019	856.38	6 - 8 ft	180-95050-1	Not Excavated	4900	< 0.39 U	6.1	35	0.25 J	0.15 J	44000	7.1		5 J	16	13000	8.1	7600	460
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-8-10	8/30/2019	856.38	8 - 10 ft	180-95050-1	Not Excavated	5200	< 0.38 U	6.4	26	0.27 J	0.11 J	1700	6.9		5.1 J	14	14000	7.2	2100	260
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-10-12	8/29/2019	855.92	10 - 12 ft	180-95006-1	Not Excavated	6300	< 0.37 U	5.4	40	0.26 J	0.11 J	10000	9.6		6	34	16000	10	4100	570
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-6-8	8/29/2019	855.92	6 - 8 ft	180-95006-1	Not Excavated	7100	< 0.38 U	6.3	54	0.28 J	0.076 J	4100	11		6	31 J	17000	16	2300	500
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-8-10	8/29/2019	855.92	8 - 10 ft	180-95006-1	Not Excavated	5800	< 0.42 U	6.8	33	0.29 J	0.077 J	1800	8.4		5.5 J	19	15000	7.9	2100	300
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-10-12	8/28/2019	856.51	10 - 12 ft	180-94900-1	Not Excavated	5100	< 0.37 U	5.6	39	0.29 J	0.061 J	14000	8.8		5 J	28	14000	8.9	4000	430
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	5900	0.61 J	18	51	0.24 J	0.077 J	25000	12		6.8	19	27000	8.9	8800	560
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-4-6	8/28/2019	856.51	4 - 6 ft	180-94900-1	Not Excavated	11000	0.58 J	7	91	0.44 J	0.064 J	1100	13		7.7	19	20000	19	2400	650
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-6-8	8/28/2019	856.51	6 - 8 ft	180-94900-1	Not Excavated	9900	< 0.42 U	8.1	54	0.41 J	0.049 J	820	11		7.5	24	20000	12	2300	440
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-8-10	8/28/2019	856.51	8 - 10 ft	180-94900-1	Not Excavated	6400	< 0.41 U	7	36	0.33 J	0.056 J	1100	8.6		6.5	17	16000	8.7	1900	320
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-2-4	8/28/2019	856.51	2 - 4 ft	180-94900-1	Excavated	9200	0.61 J	5.9	15000	0.71	< 0.045 U	1600	13		5.1 J	31	28000	95	1200	440
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-10-12	8/28/2019	856.76	10 - 12 ft	180-94900-2	Not Excavated	7800	0.49 J	8.5	72	0.31 J	0.21 J	1400	16		7.1	33	48000	19	2300	1500

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-4-6	8/28/2019	856.47	4 - 6 ft	180-94902-2	Not Excavated	< 0.017 U	17	730	< 0.62 U	< 0.13 U	41 J		< 0.39 U		19	54
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-6-8	8/28/2019	856.47	6 - 8 ft	180-94902-2	Not Excavated	< 0.014 U	19	720	< 0.59 U	< 0.12 U	42 J		< 0.37 U		15	67
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-8-10	8/28/2019	856.47	8 - 10 ft	180-94902-2	Not Excavated	< 0.015 U	28	1100	< 0.64 U	< 0.13 U	47 J		< 0.4 U		20	120
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-2-4	8/28/2019	856.71	2 - 4 ft	180-94902-1	Excavated	0.086	26	560 J	1.3	< 0.13 U	68 J		< 0.39 U		22	130
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-10-12	8/28/2019	856.71	10 - 12 ft	180-94902-1	Not Excavated	< 0.016 U	14	660	< 0.61 U	< 0.12 U	54 J		< 0.38 U		12	61
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	< 0.014 U	11	530	< 0.52 U	< 0.11 U	46 J		< 0.32 U		8.4	45
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-4-6	8/28/2019	856.71	4 - 6 ft	180-94902-1	Not Excavated	0.026 J	15	720	< 0.64 U	< 0.13 U	45 J		< 0.4 U		19	56
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-6-8	8/28/2019	856.71	6 - 8 ft	180-94902-1	Not Excavated	< 0.016 U	14	780	< 0.6 U	< 0.12 U	67 J		< 0.38 U		14	44
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-8-10	8/28/2019	856.71	8 - 10 ft	180-94902-1	Not Excavated	0.017 J	13	760	< 0.55 U	< 0.11 U	54 J		< 0.34 U		11	46
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-2-4	8/28/2019	856.96	2 - 4 ft	180-94900-2	Excavated	0.29	17	570	0.77 J	< 0.11 U	190 J		< 0.35 U		12	63
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-10-12	8/28/2019	856.96	10 - 12 ft	180-94900-2	Not Excavated	< 0.014 U	13	710	0.83 J	< 0.11 U	74 J		< 0.33 U		9.7	51
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-12-14	8/28/2019	856.96	12 - 14 ft	180-94900-2	Not Excavated	< 0.017 U	14	770	0.6 J	< 0.12 U	74 J		< 0.36 U		10	59
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-4-6	8/28/2019	856.96	4 - 6 ft	180-94900-2	Not Excavated	< 0.016 U	17	780	< 0.59 U	< 0.12 U	47 J		< 0.37 U		21	56
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-6-8	8/28/2019	856.96	6 - 8 ft	180-94900-2	Not Excavated	0.051	21	850	< 0.57 U	< 0.12 U	57 J		< 0.36 U		15	59
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-8-10	8/28/2019	856.96	8 - 10 ft	180-94900-2	Not Excavated	< 0.016 U	14	860	< 0.61 U	< 0.12 U	72 J		< 0.38 U		12	77
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	0.042	13	670	0.85 J	< 0.11 U	82 J		< 0.34 U		9.3	46
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-10-12	8/27/2019	857.02	10 - 12 ft	180-94824-1	Not Excavated	< 0.013 U	14	740	< 0.56 U	< 0.11 U	78 J		< 0.35 U		9.6	62
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-6-8	8/27/2019	857.02	6 - 8 ft	180-94824-1	Not Excavated	0.014 J	17	790	< 0.63 U	< 0.13 U	66 J		< 0.4 U		15	63
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-8-10	8/27/2019	857.02	8 - 10 ft	180-94824-1	Not Excavated	< 0.015 U	15	690	< 0.57 U	< 0.12 U	63 J		< 0.35 U		11	56
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	< 0.013 U	14	740	0.61 J	< 0.11 U	98 J		< 0.35 U		10	57
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-2-4	8/27/2019	857.02	2 - 4 ft	180-94824-1	Excavated	0.3	18	700	< 0.6 U	< 0.12 U	130 J		< 0.37 U		15	76 J-
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-4-6	8/27/2019	857.02	4 - 6 ft	180-94824-1	Excavated	0.038 J	14	570 J	< 0.64 U	< 0.13 U	61 J		< 0.4 U		16	45
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-4-6	8/27/2019	856.91	4 - 6 ft	180-94819-3	Not Excavated	0.27	23	830	1.2	< 0.12 U	58 J		< 0.37 U		18	91
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-6-8	8/27/2019	856.91	6 - 8 ft	180-94819-3	Not Excavated	0.097	15	800	< 0.58 U	< 0.12 U	< 29 UJ		< 0.36 U		13	49
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-8-10	8/27/2019	856.91	8 - 10 ft	180-94819-3	Not Excavated	0.16	12	640	0.6 J	< 0.11 U	29 J		< 0.35 U		9.1	47
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	< 0.014 U	12	840	1 J	< 0.12 U	52 J		< 0.37 U		10	41
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-2-4	8/27/2019	856.91	2 - 4 ft	180-94819-3	Excavated	3.4	19	860	0.78 J	< 0.13 U	71 J		< 0.38 U		17	120
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-10-12	8/27/2019	856.95	10 - 12 ft	180-94819-1	Not Excavated	< 0.014 U	13	580	< 0.51 U	< 0.1 U	110 J		< 0.32 U		8.2	48
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-8-10	8/27/2019	856.95	8 - 10 ft	180-94819-1	Not Excavated	0.029 J	18	750	< 0.54 U	< 0.11 U	56 J		< 0.34 U		14	59
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	< 0.014 U	12	600	0.68 J	< 0.12 U	81 J		< 0.35 U		7.7	44
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-2-4	8/27/2019	856.95	2 - 4 ft	180-94819-1	Excavated	15	19	750	< 0.57 U	< 0.12 U	71 J		< 0.36 U		16	150
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-4-6	8/27/2019	856.95	4 - 6 ft	180-94819-1	Excavated	0.02 J	18	720	< 0.59 U	< 0.12 U	44 J		< 0.36 U		19	54
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-6-8	8/27/2019	856.95	6 - 8 ft	180-94819-1	Excavated	0.065	15	920	< 0.57 U	< 0.12 U	71 J		< 0.36 U		16	58
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-10-12	8/26/2019	856.77	10 - 12 ft	180-94754-2	Not Excavated	0.026 J	14	630	0.73 J	< 0.12 U	83 J		< 0.35 U		9.2	48
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated	< 0.015 U	11	500 J	1	< 0.11 U	89 J		< 0.34 U		7.9	39
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-6-8	8/26/2019	856.77	6 - 8 ft	180-94754-2	Not Excavated	0.14	23	770	< 0.57 U	< 0.12 U	71 J		< 0.35 U		15	96
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-8-10	8/26/2019	856.77	8 - 10 ft	180-94754-2	Not Excavated	0.054	16	690	0.7 J	< 0.12 U	75 J		< 0.35 U		9.9	53
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-2-4	8/26/2019	856.77	2 - 4 ft	180-94754-1	Excavated	0.19	40	630	< 0.57 U	< 0.12 U	91 J		< 0.36 U		16	130
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-4-6	8/26/2019	856.77	4 - 6 ft	180-94754-1	Excavated	0.024 J	16	550 J	< 0.59 U	< 0.12 U	52 J		< 0.37 U		12	52
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-10-12	8/26/2019	856.77	10 - 12 ft	180-94752-3	Not Excavated	0.018 J	13	650	0.95 J	< 0.11 U	110 J		< 0.35 U		8.3	49
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated	0.019 J	13	690	< 0.56 U	< 0.11 U	82 J		< 0.35 U		8.8	45
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-4-6	8/26/2019	856.77	4 - 6 ft	180-94752-3	Not Excavated	0.3	17	700	0.62 J	< 0.12 U	57 J		< 0.36 U		15	75
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-6-8	8/26/2019	856.77	6 - 8 ft	180-94752-3	Not Excavated	0.12	12	780	< 0.56 U	< 0.11 U	79 J		< 0.35 U		13	43
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-8-10	8/26/2019	856.77	8 - 10 ft	180-94752-3	Not Excavated	0.03 J	14	810	0.62 J	< 0.11 U	83 J		< 0.34 U		12	57
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-2-4	8/26/2019	856.77	2 - 4 ft	180-94752-3	Excavated	1.2	39	820	< 0.62 U	< 0.13 U	83 J		< 0.38 U		16	74
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-10-12	9/4/2019	855.86	10 - 12 ft	180-95165-1	Not Excavated	< 0.014 U	12	650	0.64 J	< 0.11 U	75 J		< 0.34 U		9.2	55
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	< 0.013 U	15	690	0.62 J	< 0.11 U	74 J		< 0.34 U		11	47
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-2-4	9/4/2019	855.86	2 - 4 ft	180-95165-1	Not Excavated	< 0.016 U	14	790	< 0.59 U	< 0.12 U	46 J		< 0.37 U		14	44
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-4-6	9/4/2019	855.86	4 - 6 ft	180-95165-1	Not Excavated	< 0.014 U	13	660	< 0.56 U	< 0.11 U	64 J		< 0.35 U		9.5	43
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-6-8	9/4/2019	855.86	6 - 8 ft	180-95165-1	Not Excavated	< 0.015 U	13	660	< 0.59 U	< 0.12 U	66 J		< 0.36 U		11	42 J-
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-8-10	9/4/2019	855.86	8 - 10 ft	180-95165-1	Not Excavated	< 0.015 U	12	680	0.68 J	< 0.11 U	68 J		< 0.33 U		8.3	89
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-10-12	9/3/2019	856.40	10 - 12 ft	180-95162-1	Not Excavated	< 0.016 U	14	810	0.62 J	< 0.12 U	< 30 U		< 0.37 U		11	47
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-12-14	9/3/2019	856.40	12 - 14 ft	180-95162-1	Not Excavated	< 0.015 U	14	760	< 0.59 U	< 0.12 U	< 29 U		< 0.36 U		11	60
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	< 0.013 U	14	670	< 0.55 U	< 0.11 U	< 28 U		< 0.34 U		10	52
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-2-4	9/3/2019	856.40	2 - 4 ft	180-95162-1	Not Excavated	< 0.014 U	15	660	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U		15	50 J
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-4-6	9/3/2019	856.40	4 - 6 ft	180-95162-1	Not Excavated	< 0.017 U	18	850	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U		18	71
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-6-8	9/3/2019	856.40	6 - 8 ft	180-95162-1	Not Excavated	< 0.014 U	16	740	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U		17	65
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-8-10	9/3/2019	856.40	8 - 10 ft	180-95162-1	Not Excavated	< 0.013 U	14	770	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U		10	48
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-10-12	8/30/2019	856.38	10 - 12 ft	180-95050-1	Not Excavated	< 0.015 U	13	830	< 0.55 U	< 0.11 U	45 J		< 0.34 U		10	46
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	< 0.015 U	10	520 J	0.66 J	< 0.11 U	76 J		< 0.34 U		7.1	32
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-2-4	8/30/2019	856.38	2 - 4 ft	180-95050-1	Not Excavated	0.022 J	17	650	< 0.57 U	< 0.12 U	< 29 UJ		< 0.35 U		14	55
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-4-6	8/30/2019	856.38	4 - 6 ft	180-95050-1	Not Excavated	0.025 J	18	770	< 0.58 U	< 0.12 U	53 J		< 0.36 U		15	66
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-6-8	8/30/2019	856.38	6 - 8 ft	180-95050-1	Not Excavated	< 0.014 U	13	680	0.6 J	< 0.12 U	68 J		< 0.37 U		8.8	40
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-8-10	8/30/2019	856.38	8 - 10 ft	180-95050-1	Not Excavated	< 0.016 U	13	790	< 0.58 U	< 0.12 U	39 J		< 0.36 U		9.8	47
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-10-12	8/29/2019	855.92	10 - 12 ft	180-95006-1	Not Excavated	< 0.016 U	18	660	< 0.56 U	< 0.12 U	55 J		< 0.35 U		10	58
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-6-8	8/29/2019	855.92	6 - 8 ft	180-95006-1	Not Excavated	< 0.013 U	18	690	< 0.58 U	< 0.12 U	45 J		< 0.36 U		11	59
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-8-10	8/29/2019	855.92	8 - 10 ft	180-95006-1	Not Excavated	< 0.017 U	15	750	< 0.63 U	< 0.13 U	43 J		< 0.39 U		11	48
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-10-12	8/28/2019	856.51	10 - 12 ft	180-94900-1	Not Excavated	< 0.015 U	14	610	< 0.56 U	< 0.11 U	91 J		< 0.35 U		9.1	56
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	< 0.015 U	15	680	< 0.54 U	< 0.11 U	100 J		< 0.34 U		16	50
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-4-6	8/28/2019	856.51	4 - 6 ft	180-94900-1	Not Excavated	0.028 J	18	760	< 0.64 U	< 0.13 U	59 J		< 0.4 U		17	58
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-6-8	8/28/2019	856.51	6 - 8 ft	180-94900-1	Not Excavated	0.033 J	18	930	< 0.63 U	< 0.13 U	58 J		< 0.39 U		16	61
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-8-10	8/28/2019	856.51	8 - 10 ft	180-94900-1	Not Excavated	0.016 J	15	790	< 0.62 U	< 0.13 U	50 J		< 0.38 U		12	49
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-2-4	8/28/2019	856.51	2 - 4 ft	180-94900-1	Excavated	0.075	18	740	< 0.63 U	< 0.13 U	580 J		< 0.39 U		21	40
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-10-12	8/28/2019	856.76	10 - 12 ft	180-94900-2	Not Excavated	0.36	15	670	< 0.6 U	< 0.12 U	55 J		< 0.38 U		26	85

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	7300	< 0.38 U	5.5	49	0.32 J	0.073 J	1700	9.2		6.7	18	16000	13	2400	420
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-2-4	8/28/2019	856.76	2 - 4 ft	180-94900-2	Not Excavated	8100	0.79 J	11	100	0.41 J	0.19 J	3200	14		6	67	22000	96	1800	480
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-4-6	8/28/2019	856.76	4 - 6 ft	180-94900-2	Not Excavated	13000	1.5	7	71	0.47	0.066 J	1300	14		8	17	22000	20	2600	550
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-6-8	8/28/2019	856.76	6 - 8 ft	180-94900-2	Not Excavated	11000	< 0.39 UJ	6.7	49	0.46	0.078 J	1200	14		7.3	20	20000	16	2600	340
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-8-10	8/28/2019	856.76	8 - 10 ft	180-94900-2	Not Excavated	6400	< 0.39 UJ	6.5 J	50 J-	0.27 J	0.093 J	2900 J	9.8 J-		5.6 J	19 J-	16000	44 J-	2200 J	540
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-10-12	8/28/2019	856.89	10 - 12 ft	180-94900-3	Not Excavated	6100	< 0.4 UJ	9.2	55	0.28 J	0.11 J	700	9.3		4.7 J	16	15000	9.6	1800	670
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	7400	< 0.37 U	6.4	120	0.34 J	0.09 J	1800	13		6.3	26	16000	14	2200	600
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-4-6	8/28/2019	856.89	4 - 6 ft	180-94900-3	Not Excavated	12000	0.43 J	5	89	0.44 J	< 0.045 U	1200	13		7.2	16	18000	18	2700	470
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-6-8	8/28/2019	856.89	6 - 8 ft	180-94900-3	Not Excavated	11000	< 0.4 U	6.3	48	0.45 J	< 0.043 U	710	13		7.1	20	19000	8.4	2700	400
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-8-10	8/28/2019	856.89	8 - 10 ft	180-94900-3	Not Excavated	9100	< 0.37 U	6.6	81	0.38 J	0.045 J	980	11		7	31	18000	11	2200	590
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-2-4	8/28/2019	856.89	2 - 4 ft	180-94900-3	Excavated	8800	< 0.37 U	5.7	61	0.36 J	0.04 J	1400	11		5.7	19	17000	11	2200	350
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	8/28/2019	857.14	10 - 12 ft	180-94900-1	Not Excavated	7700	< 0.38 U	6.8	82	0.33 J	0.33 J	1200	9.5		6.1	21	16000	22	1900	780
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-28	8/28/2019	857.14	6 - 8 ft	180-94903-1	Not Excavated	11000	0.55 J	6	62	0.44 J	0.067 J	960	13		7.2	25	19000	11	2600	520
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	8/28/2019	857.14	6 - 8 ft	180-94900-1	Not Excavated	11000	0.46 J	6.8	42	0.44 J	0.05 J	640	13		8.2	33	19000	12	2700	360
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	8/28/2019	857.14	8 - 10 ft	180-94900-1	Not Excavated	6500	0.46 J	10	93	0.44 J	0.34 J	810	9.8		6.6	39	18000	25	1400	980
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	6700	< 0.4 U	6.8	61	0.29 J	0.2 J	5300	9.1		5.9	24	16000	11	4400	1000
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-2-4	8/28/2019	857.14	2 - 4 ft	180-94900-1	Excavated	6900	0.81 J	8.7	140	0.43 J	0.39 J	2800	15		6.4	52	20000	100	1700	320
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-4-6	8/28/2019	857.14	4 - 6 ft	180-94900-1	Excavated	11000	0.56 J	5.5	69	0.4 J	0.12 J	1400	12		6.3	15	16000	20	2300	390
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated	7400	0.83 J	7.7	140	0.46	0.26 J	3800	19		6.5	66	22000	99	2000	250
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	6800	0.98	7.9	150	0.41	0.33 J	5900	17		6.9	54	21000	93	2600	310
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-4-6	8/27/2019	857.18	4 - 6 ft	180-94824-2	Not Excavated	12000	< 0.41 UJ	8.1	110	0.47 J	0.16 J	2600 J	12		6.8	16	16000	21	2200	590
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-6-8	8/27/2019	857.18	6 - 8 ft	180-94824-2	Not Excavated	8700	< 0.38 U	7.8	58	0.42 J	0.1 J	6900	11		7.1	27	17000	28	2300	440
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-8-10	8/27/2019	857.18	8 - 10 ft	180-94824-2	Not Excavated	9400	< 0.43 U	12	89	0.47 J	0.13 J	2400	11		8.5	27	20000	25	1900	1300
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	6600	< 0.37 U	6.8	61	0.32 J	0.12 J	3000	10		5.7	20	15000	25	1900	700
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-2-4	8/27/2019	857.18	2 - 4 ft	180-94824-2	Excavated	10000	0.57 J	6.5	100	0.6	0.17 J	40000	18		7.7	62	18000	58	3800	360
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-10-12	8/27/2019	856.99	10 - 12 ft	180-94819-2	Not Excavated	7200	< 0.37 U	5.7	88	0.32 J	0.13 J	40000	13		6.1	23	14000	23	11000	500
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	6600	< 0.36 U	6.6	81	0.29 J	0.15 J	61000	12		5.9	25	13000	37	14000	480
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-2-4	8/27/2019	856.99	2 - 4 ft	180-94819-2	Excavated	8500	< 0.37 U	6.1	170	0.37 J	0.28 J	76000	12		5.6	24	16000	70	4600	390
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-4-6	8/27/2019	856.99	4 - 6 ft	180-94819-2	Excavated	8900	< 0.37 U	7	230	0.36 J	0.18 J	50000	15		6.4	28	16000	40	4400	410
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-6-8	8/27/2019	856.99	6 - 8 ft	180-94819-2	Excavated	10000	0.47 J	8.2	140	0.45	0.26 J	16000	15		8.5	33	21000	53 J+	5100 J-	490
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-8-10	8/27/2019	856.99	8 - 10 ft	180-94819-2	Excavated	7700	0.55 J	6.9	86	0.36 J	0.12 J	17000	9.8		6.5	24	16000	16	6300	490
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-10-12	8/27/2019	856.92	10 - 12 ft	180-94819-2	Not Excavated	5500	< 0.38 U	6.1	36	0.24 J	0.12 J	35000	8.1		5.6	16	14000	11	9400	550
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-8-10	8/27/2019	856.92	8 - 10 ft	180-94819-2	Not Excavated	9100	0.52 J	11	98	0.47 J	0.13 J	5000	12		7.4	32	22000	18	4000	460
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	4600	< 0.36 U	4.4	36	0.19 J	0.085 J	31000	7		4.4 J	15	12000	6.8	7800	350
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-2-4	8/27/2019	856.92	2 - 4 ft	180-94819-2	Excavated	6400	0.85 J	6.1	64	0.3 J	0.098 J	7000	8.7		5.8	19	15000	31	3800	530
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-4-6	8/27/2019	856.92	4 - 6 ft	180-94819-2	Excavated	11000	< 0.39 U	6	51	0.44 J	0.063 J	1400	12		7.3	17	18000	10	2700	340
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-6-8	8/27/2019	856.92	6 - 8 ft	180-94819-2	Excavated	9100	0.64 J	12	66	0.49 J	0.096 J	1300 J	11		7.7	33	22000	13	2300	620
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	5800	< 0.37 U	3.9	45	0.21 J	0.099 J	43000	13		5.4	20	14000	6.9	13000	420
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-10-12	8/26/2019	856.86	10 - 12 ft	180-94752-2	Excavated	5800	< 0.35 U	4.5	35	0.23 J	0.13 J	33000	8.6		5.3	20	14000	8.1	9200	590
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-2-4	8/26/2019	856.86	2 - 4 ft	180-94752-2	Excavated	8500	0.93 J	8.9	79	0.36 J	34	17000	13		7.4	33	25000	180	6200	550
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-4-6	8/26/2019	856.86	4 - 6 ft	180-94752-2	Excavated	12000	0.47 J	5.7	42	0.46 J	0.067 J	830	13		7.5	22	20000	10	2800	380
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-6-8	8/26/2019	856.86	6 - 8 ft	180-94752-2	Excavated	9300	< 0.42 U	7	68	0.4 J	0.2 J	5000	13		7	23	19000	17	3300	480
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-8-10	8/26/2019	856.86	8 - 10 ft	180-94752-2	Excavated	5300	< 0.35 U	7.1	45	0.27 J	0.16 J	15000	7.6		7.5	20	14000	12	2800	760
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-10-12	8/26/2019	856.70	10 - 12 ft	180-94752-3	Not Excavated	4500	< 0.38 U	5.5	36	0.21 J	0.1 J	21000	6.8		4.4 J	18	13000	8.4	10000	520
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-2-4	8/26/2019	856.70	2 - 4 ft	180-94752-3	Not Excavated	8400	0.59 J	6.4	130	0.42 J	0.18 J	28000	19		6.3	39	17000	48	3200	440
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-4-6	8/26/2019	856.70	4 - 6 ft	180-94752-3	Not Excavated	14000	0.44 J	6.5	65	0.52	0.064 J	1900	15		9.3	14	21000	15	2900	810
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-6-8	8/26/2019	856.70	6 - 8 ft	180-94752-3	Not Excavated	9100	0.41 J	7.3	71	0.43 J	0.084 J	2400	12		8.6	20	20000	14	2400	630
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-8-10	8/26/2019	856.70	8 - 10 ft	180-94752-3	Not Excavated	5300	< 0.4 U	6.3	49	0.3 J	0.095 J	3100	7.4		5.9	20	14000	10	2200	650
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	5000	< 0.35 U	5.7	32	0.22 J	0.087 J	40000	8		5 J	17	13000	9.5	10000	360
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-10-12	8/29/2019	856.36	10 - 12 ft	180-95024-1	Not Excavated	5700	< 0.38 U	5	37	0.24 J	0.18 J	24000	8.4		4.9 J	17	13000	7.7	3700	440
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	6100	< 0.36 UJ	5.6	43	0.25 J	0.11 J	27000	12		5.3	17	14000	7.8	5300 J+	550
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-2-4	8/29/2019	856.36	2 - 4 ft	180-95024-1	Not Excavated	9800	< 0.39 U	4.9	53	0.36 J	< 0.042 U	1100	11		6	19	17000	9.1	2400	390
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-4-6	8/29/2019	856.36	4 - 6 ft	180-95024-1	Not Excavated	6900	< 0.38 U	5.9	41	0.31 J	0.096 J	2800	8.8		5.8	18	16000	8.7	2800	440
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-6-8	8/29/2019	856.36	6 - 8 ft	180-95024-1	Not Excavated	4900	< 0.35 U	5.5	24	0.23 J	0.064 J	17000	6.8		4.2 J	13	12000	5.4	7400	320
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-8-10	8/29/2019	856.36	8 - 10 ft	180-95024-1	Not Excavated	6300	< 0.36 U	5.6	36	0.28 J	0.11 J	14000	9.1		5.8	17	16000	13	2400	490
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-10-12	9/4/2019	856.58	10 - 12 ft	180-95165-1	Not Excavated	5800	< 0.36 U	5	43	0.21 J	0.061 J	35000	16		5.4	21	14000	5.1	9500	330
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-12-14	9/4/2019	856.58	12 - 14 ft	180-95165-1	Not Excavated	6600	< 0.38 U	4.9	57	0.28 J	0.15 J	50000	10		5.9	22	16000	6.5	14000	470
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	6100	< 0.34 U	4.1	69	0.24 J	0.098 J	36000	9.8		5.3	21	15000	6.1	11000	380
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-2-4	9/4/2019	856.58	2 - 4 ft	180-95165-1	Not Excavated	8300	0.52 J	7	60	0.38 J	0.13 J	630	11		6.7	23	19000	11	2600	540
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-4-6	9/4/2019	856.58	4 - 6 ft	180-95165-1	Not Excavated	7600	0.47 J	8	57	0.4 J	0.14 J	1300	9.3		5.9	27	19000	9.8	2300	640
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-6-8	9/4/2019	856.58	6 - 8 ft	180-95165-1	Not Excavated	5800	0.59 J	6.2	39	0.25 J	0.1 J	11000	9.4		5.4 J	17	15000	6.7	2700	510
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-8-10	9/4/2019	856.58	8 - 10 ft	180-95165-1	Not Excavated	4300	< 0.39 U	3	30	0.16 J	0.053 J	35000	5.4		3.8 J	13	10000	4.1	6200	290
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-10-12	9/4/2019	856.96	10 - 12 ft	180-95165-2	Not Excavated	4900	< 0.35 U	3.7	45	0.19 J	0.075 J	38000	6.3		4.6 J	25	12000	3.5	6200	530
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	6500	< 0.35 U	5	110	0.23 J	0.12 J	60000	8		5.8	23	15000	5.4	8000	370
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-2-4	9/4/2019	856.96	2 - 4 ft	180-95165-2	Not Excavated	9100	0.54 J	7.7	65	0.4 J	0.091 J	3500	11		6.7	24	19000	11	3700	590
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-4-6	9/4/2019	856.96	4 - 6 ft	180-95165-2	Not Excavated	5300	< 0.35 U	5.5	32	0.25 J	0.12 J	28000	7.1		5 J	17	13000	6.3	9400 J-	380
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	4500	< 0.35 U	7.3	33	0.33 J	0.1 J	25000	6.3		4.9 J	15	13000	7.2	9400	430
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-8-10	9/4/2019	856.96	8 - 10 ft	180-95165-2	Not Excavated	3900	< 0.36 U	4.1	26	0.16 J	0.12 J	52000	5.2		4 J	16	9700	4.3	10000	330
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-10-12	8/30/2019	856.73	10 - 12 ft	180-95047-3	Not Excavated	4100	< 0.4 U	3	31	0.14 J	0.065 J	31000	4.6		3.9 J	12	9200	15	9900	320
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-12-14	8/30/2019	856.73	12 - 14 ft	180-95047-3	Not Excavated	4800	< 0.39 U	3.5	53	0.18 J	0.07 J	42000	7.5		3.9 J	20	11000	4.1	5900	450
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	5500	< 0.34 U	4.1	54	0.19 J	0.087 J	57000	8.2		5.2	22	13000	7.5	11000	450
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-2-4	8/30/2019	856.73	2 - 4 ft	180-95047-3	Not Excavated	7900	0.42 J	4.9	46	0.31 J	0.093 J	980	9.3		5.8	26	16000	11	2300	450
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-4-6	8/30/2019	856.73	4 - 6 ft	180-95047-3	Not Excavated	7800	0.45 J	7.3	50	0.35 J	0.079 J	1300	11		7	20	19000	9.3	2400	510
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-6-8	8/30/2019	856.73	6 - 8 ft	180-95047-3	Not Excavated	5200	< 0.38 U	5.2	35	0.24 J	0.095 J	23000	16		4.7 J	15	14000	8	7000	400

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	0.1	14	700	< 0.58 U	< 0.12 U	43 J		< 0.36 U		11	49
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-2-4	8/28/2019	856.76	2 - 4 ft	180-94900-2	Not Excavated	0.17	24	620	0.66 J	< 0.12 U	77 J		< 0.37 U		18	90
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-4-6	8/28/2019	856.76	4 - 6 ft	180-94900-2	Not Excavated	0.26	17	780	< 0.59 U	< 0.12 U	52 J		< 0.37 U		20	67
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-6-8	8/28/2019	856.76	6 - 8 ft	180-94900-2	Not Excavated	0.17	17	830	< 0.59 U	< 0.12 U	47 J		< 0.37 U		17	62
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-8-10	8/28/2019	856.76	8 - 10 ft	180-94900-2	Not Excavated	0.053	13 J	640	< 0.6 UJ	< 0.12 UJ	49 J		< 0.37 U		11 J-	58 J
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-10-12	8/28/2019	856.89	10 - 12 ft	180-94900-3	Not Excavated	< 0.016 U	13	860	< 0.61 U	< 0.12 U	48 J		< 0.38 U		12	45
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	< 0.015 U	16	740	< 0.57 U	< 0.12 U	77 J		< 0.35 U		12	56
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-4-6	8/28/2019	856.89	4 - 6 ft	180-94900-3	Not Excavated	0.00044	17	740	< 0.63 U	< 0.13 U	68 J		< 0.4 U		16	66
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-6-8	8/28/2019	856.89	6 - 8 ft	180-94900-3	Not Excavated	0.023 J	17	830	< 0.6 U	< 0.12 U	61 J		< 0.37 U		16	49
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-8-10	8/28/2019	856.89	8 - 10 ft	180-94900-3	Not Excavated	< 0.015 U	16	860	< 0.56 U	< 0.11 U	53 J		< 0.35 U		14	53
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-2-4	8/28/2019	856.89	2 - 4 ft	180-94900-3	Excavated	0.021 J	15	680	< 0.56 U	< 0.11 U	61 J		< 0.35 U		14	52
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	8/28/2019	857.14	10 - 12 ft	180-94900-1	Not Excavated	0.039	17	940	< 0.57 U	< 0.12 U	50 J		< 0.36 U		12	74
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	6 - 8 ft	180-94903-1	Not Excavated	0.069	17	830	< 0.61 U	< 0.12 U	76 J		< 0.38 U		16	55
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	8/28/2019	857.14	6 - 8 ft	180-94900-1	Not Excavated	0.073	17	810	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U		16	66
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	8/28/2019	857.14	8 - 10 ft	180-94900-1	Not Excavated	0.095	19	1100	< 0.62 U	< 0.13 U	43 J		< 0.39 U		12	75
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	0.084	16	810	< 0.6 U	< 0.12 U	50 J		< 0.38 U		12	70
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-2-4	8/28/2019	857.14	2 - 4 ft	180-94900-1	Excavated	0.28	24	560 J	< 0.61 U	< 0.11 U	< 31 U		< 0.38 U		14	130
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-4-6	8/28/2019	857.14	4 - 6 ft	180-94900-1	Excavated	0.093	15	760	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U		15	63
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated	0.23	23	510 J	0.62 J	0.16 J	81 J		< 0.34 U		15	110
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	0.16	67	470	0.49 J	< 0.092 U	80 J		< 0.28 U		14	110
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-4-6	8/27/2019	857.18	4 - 6 ft	180-94824-2	Not Excavated	0.077	15	700	0.81 J	< 0.13 U	68 J		< 0.39 U		16	89
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-6-8	8/27/2019	857.18	6 - 8 ft	180-94824-2	Not Excavated	0.061	24	870	< 0.58 U	< 0.12 U	63 J		< 0.36 U		13	59
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-8-10	8/27/2019	857.18	8 - 10 ft	180-94824-2	Not Excavated	0.037 J	19	1000	< 0.65 U	< 0.13 U	62 J		< 0.4 U		17	120
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	< 0.015 U	15	790	< 0.57 U	< 0.12 U	57 J		< 0.35 U		11	80
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-2-4	8/27/2019	857.18	2 - 4 ft	180-94824-2	Excavated	0.098	43	820	1.4	< 0.12 U	120 J		< 0.36 U		16	85
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-10-12	8/27/2019	856.99	10 - 12 ft	180-94819-2	Not Excavated	0.15	17	820	0.78 J	< 0.12 U	130 J		< 0.35 U		11	73
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	0.13	17	830	1.2	< 0.11 U	140 J		< 0.34 U		10	79
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-2-4	8/27/2019	856.99	2 - 4 ft	180-94819-2	Excavated	0.68	17	1200	1.5	< 0.11 U	200 J		< 0.35 U		14	100
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-4-6	8/27/2019	856.99	4 - 6 ft	180-94819-2	Excavated	0.72	18	850	0.7 J	< 0.12 U	160 J		< 0.35 U		13	84
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-6-8	8/27/2019	856.99	6 - 8 ft	180-94819-2	Excavated	0.56 J	23	860	< 0.55 U	< 0.11 U	97 J		< 0.34 U		17	120
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-8-10	8/27/2019	856.99	8 - 10 ft	180-94819-2	Excavated	0.076	15	1100	< 0.59 U	< 0.12 U	91 J		< 0.37 U		13	61
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-10-12	8/27/2019	856.92	10 - 12 ft	180-94819-2	Not Excavated	< 0.014 U	13	650	< 0.58 U	< 0.12 U	67 J		< 0.36 U		9.2	46
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-8-10	8/27/2019	856.92	8 - 10 ft	180-94819-2	Not Excavated	0.027 J	22	890	< 0.62 U	< 0.13 U	59 J		< 0.38 U		17	68
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	< 0.014 U	11	580	< 0.55 U	< 0.11 U	67 J		< 0.34 U		7.5	42
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-2-4	8/27/2019	856.92	2 - 4 ft	180-94819-2	Excavated	0.34	16	630	< 0.59 U	< 0.12 U	57 J		< 0.37 U		11	55
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-4-6	8/27/2019	856.92	4 - 6 ft	180-94819-2	Excavated	< 0.016 U	18	620	< 0.59 U	< 0.12 U	43 J		< 0.37 U		14	54
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-6-8	8/27/2019	856.92	6 - 8 ft	180-94819-2	Excavated	< 0.016 UJ	21	890	< 0.57 U	< 0.12 U	39 J		< 0.36 U		16	74
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	0.029 J	14	< 59 U	0.93 J	< 0.11 U	93 J		< 0.34 U		12	49
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-10-12	8/26/2019	856.86	10 - 12 ft	180-94752-2	Excavated	0.014 J	14	< 57 U	< 0.53 U	< 0.11 U	72 J		< 0.33 U		10	55
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-2-4	8/26/2019	856.86	2 - 4 ft	180-94752-2	Excavated	0.43	26	< 60 U	< 0.56 U	< 0.11 U	85 J		< 0.35 U		15	12000
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-4-6	8/26/2019	856.86	4 - 6 ft	180-94752-2	Excavated	0.034	17	< 65 U	< 0.62 U	< 0.13 U	53 J		< 0.38 U		17	59
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-6-8	8/26/2019	856.86	6 - 8 ft	180-94752-2	Excavated	0.057	16	< 67 U	< 0.63 U	< 0.13 U	56 J		< 0.39 U		17	120
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-8-10	8/26/2019	856.86	8 - 10 ft	180-94752-2	Excavated	0.023 J	12	< 56 U	< 0.53 U	< 0.11 U	53 J		< 0.33 U		11	67
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-10-12	8/26/2019	856.70	10 - 12 ft	180-94752-3	Not Excavated	0.027 J	11	630	< 0.58 U	< 0.12 U	61 J		< 0.36 U		7.4	53
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-2-4	8/26/2019	856.70	2 - 4 ft	180-94752-3	Not Excavated	0.85	18	890	< 0.59 U	1.1	96 J		< 0.36 U		15	84
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-4-6	8/26/2019	856.70	4 - 6 ft	180-94752-3	Not Excavated	0.038	18	960	< 0.63 U	< 0.13 U	54 J		< 0.39 U		20	55
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-6-8	8/26/2019	856.70	6 - 8 ft	180-94752-3	Not Excavated	0.031 J	19	840	< 0.58 U	< 0.12 U	43 J		< 0.36 U		16	54
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-8-10	8/26/2019	856.70	8 - 10 ft	180-94752-3	Not Excavated	< 0.016 U	13	800	< 0.6 U	< 0.12 U	44 J		< 0.38 U		9.9	50
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	0.027 J	15	630	< 0.53 U	< 0.11 U	74 J		< 0.33 U		8.7	50
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-10-12	8/29/2019	856.36	10 - 12 ft	180-95024-1	Not Excavated	< 0.015 U	12	680	< 0.57 U	< 0.12 U	66 J		< 0.35 U		9.6	68
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	< 0.015 U	13	640	< 0.54 U	< 0.11 U	61 J		< 0.34 U		9.8	46
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-2-4	8/29/2019	856.36	2 - 4 ft	180-95024-1	Not Excavated	0.023 J	15	620	< 0.59 U	< 0.12 U	53 J		< 0.37 U		15	53
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-4-6	8/29/2019	856.36	4 - 6 ft	180-95024-1	Not Excavated	< 0.016 U	15	780	< 0.58 U	< 0.12 U	43 J		< 0.36 U		12	62
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-6-8	8/29/2019	856.36	6 - 8 ft	180-95024-1	Not Excavated	< 0.012 U	11	580	< 0.52 U	< 0.11 U	49 J		< 0.33 U		9.2	36
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-8-10	8/29/2019	856.36	8 - 10 ft	180-95024-1	Not Excavated	< 0.016 U	14	700	< 0.54 U	< 0.11 U	59 J		< 0.34 U		11	54
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-10-12	9/4/2019	856.58	10 - 12 ft	180-95165-1	Not Excavated	< 0.014 U	13	570	0.75 J	< 0.11 U	78 J		< 0.34 U		9.9	49
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-12-14	9/4/2019	856.58	12 - 14 ft	180-95165-1	Not Excavated	< 0.015 U	14	740	1.2	< 0.12 U	160 J		< 0.35 U		11	92
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	< 0.014 U	13	620	0.8 J	< 0.11 U	110 J		< 0.32 U		8.8	59
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-2-4	9/4/2019	856.58	2 - 4 ft	180-95165-1	Not Excavated	0.022 J	19	700	< 0.6 U	< 0.12 U	41 J		< 0.38 U		13	70
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-4-6	9/4/2019	856.58	4 - 6 ft	180-95165-1	Not Excavated	< 0.014 U	16	800	< 0.61 U	< 0.12 U	41 J		< 0.38 U		12	82
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-6-8	9/4/2019	856.58	6 - 8 ft	180-95165-1	Not Excavated	< 0.015 U	13	660	< 0.63 U	< 0.13 U	47 J		< 0.39 U		11	52
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-8-10	9/4/2019	856.58	8 - 10 ft	180-95165-1	Not Excavated	< 0.017 U	9.4	500 J	0.79 J	< 0.12 U	62 J		< 0.37 U		5.6 J	80
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-10-12	9/4/2019	856.96	10 - 12 ft	180-95165-2	Not Excavated	< 0.015 U	11	560	0.64 J	< 0.11 U	69 J		< 0.33 U		7.5	45
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	< 0.014 U	14	670	0.92 J	< 0.11 U	86 J		< 0.33 U		9.3	56
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-2-4	9/4/2019	856.96	2 - 4 ft	180-95165-2	Not Excavated	< 0.015 U	18	730	< 0.57 U	< 0.12 U	42 J		< 0.36 U		14	68
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-4-6	9/4/2019	856.96	4 - 6 ft	180-95165-2	Not Excavated	< 0.014 U	13	690	< 0.54 U	< 0.11 U	68 J		< 0.33 U		8.7	41
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.014 U	11	610	< 0.53 U	< 0.11 U	59 J		< 0.33 U		9.8	39
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-8-10	9/4/2019	856.96	8 - 10 ft	180-95165-2	Not Excavated	< 0.014 U	9.3	510 J	0.8 J	< 0.11 U	76 J		< 0.34 U		6.7	38
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-10-12	8/30/2019	856.73	10 - 12 ft	180-95047-3	Not Excavated	< 0.016 U	9.2	500 J	0.65 J	< 0.12 U	63 J		< 0.38 U		5.9	35
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-12-14	8/30/2019	856.73	12 - 14 ft	180-95047-3	Not Excavated	< 0.017 U	10	590	0.83 J	< 0.12 U	81 J		< 0.37 U		7.6	35
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	< 0.015 U	13	600	1.1	< 0.11 U	100 J		< 0.32 U		8.2	45
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-2-4	8/30/2019	856.73	2 - 4 ft	180-95047-3	Not Excavated	0.043	15	580	< 0.59 U	< 0.12 U	42 J		< 0.36 U		11	64
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-4-6	8/30/2019	856.73	4 - 6 ft	180-95047-3	Not Excavated	0.018 J	17	750	< 0.6 U	< 0.12 U	50 J		< 0.37 U		14	58
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-6-8	8/30/2019	856.73	6 - 8 ft	180-95047-3	Not Excavated	< 0.017 U	12	610	< 0.57 U	< 0.12 U	60 J		< 0.36 U		12	41

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-8-10	8/30/2019	856.73	8 - 10 ft	180-95047-3	Not Excavated	5600	< 0.38 U	4.3	33	0.22 J	0.095 J	48000	8.3		5 J	21	13000	5.6	9600	450
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-10-12	8/29/2019	857.13	10 - 12 ft	180-95024-2	Not Excavated	7400	< 0.34 U	5.4	60	0.27 J	0.097 J	21000	12		6.2	27	16000	8	6100	490
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	7300	< 0.37 U	5.9	46	0.29 J	0.096 J	14000 J	12		6.1	20	16000	9.8	4100 J	480
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-2-4	8/29/2019	857.13	2 - 4 ft	180-95024-1	Not Excavated	8800	0.64 J	6.3	54	0.36 J	0.078 J	1400	12		6.7	22	17000	17	2300	590
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-4-6	8/29/2019	857.13	4 - 6 ft	180-95024-1	Not Excavated	5600	< 0.35 U	5.5	34	0.25 J	0.1 J	24000	7.7		5.3	16	13000	6.9	3700	400
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-6-8	8/29/2019	857.13	6 - 8 ft	180-95024-2	Not Excavated	6100	< 0.38 U	6.3	36	0.28 J	0.09 J	950	8.7		5.1 J	17	14000	16	1900	410
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-8-10	8/29/2019	857.13	8 - 10 ft	180-95024-2	Not Excavated	5800	< 0.35 U	5.3	39	0.23 J	0.078 J	27000	11		5.2	16	13000	7.1	8600	440
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-10-12	8/29/2019	856.55	10 - 12 ft	180-95006-2	Not Excavated	5300	< 0.35 U	4.8	54	0.22 J	0.085 J	43000	10		4.8 J	29	12000	5.9	8400	410
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	5500	< 0.34 U	5.2	48	0.21 J	0.07 J	36000	13		5.2	22	13000	6.3	12000	380
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-2-4	8/29/2019	856.55	2 - 4 ft	180-95006-1	Not Excavated	9200	0.4 J	7.5	73	0.43 J	0.12 J	1400	13		6.9	27	18000	19	2200	440
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-4-6	8/29/2019	856.55	4 - 6 ft	180-95006-1	Not Excavated	5100	< 0.42 U	4.1	56	0.24 J	0.066 J	560 J	6.5		4.2 J	11	12000	4.5	1300	200
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-6-8	8/29/2019	856.55	6 - 8 ft	180-95006-1	Not Excavated	5500	< 0.38 U	5.1	33	0.24 J	0.09 J	34000	7.2		5 J	17	13000	7.8	9100	330
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-8-10	8/29/2019	856.55	8 - 10 ft	180-95006-2	Not Excavated	5600	< 0.38 U	5.2	62	0.19 J	0.11 J	50000	8.9		6.4	18	13000	5.2	10000	480
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-10-12	9/4/2019	857.12	10 - 12 ft	180-95165-3	Not Excavated	5300	< 0.39 U	6.7	37	0.21 J	0.14 J	64000	8.1		5.1 J	18	13000	6.4	10000	480
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	4500	< 0.37 U	3.7	39	0.19 J	0.13 J	55000	9.3		4.2 J	17	11000	5.6	13000	320
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-2-4	9/4/2019	857.12	2 - 4 ft	180-95165-3	Not Excavated	8400	< 0.37 U	6.8	52	0.35 J	0.093 J	1000	10		6.8	24	18000	11	2400	640
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-4-6	9/4/2019	857.12	4 - 6 ft	180-95165-3	Not Excavated	4900	< 0.37 U	4.6	34	0.23 J	0.076 J	1500	7		4 J	14	11000	20	1500	650
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-6-8	9/4/2019	857.12	6 - 8 ft	180-95165-3	Not Excavated	6600	< 0.37 U	5.2	51	0.26 J	0.11 J	42000	8.4		6	24	15000	7.5	12000	480
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-8-10	9/4/2019	857.12	8 - 10 ft	180-95165-3	Not Excavated	4900	< 0.37 U	3.9	35	0.22 J	0.12 J	39000	10		4.5 J	15	11000	6.7	5800	460
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-10-12	9/4/2019	857.77	10 - 12 ft	180-95165-2	Not Excavated	4600	< 0.34 U	3.2	39	0.16 J	0.098 J	40000	6.7		4.1 J	15	11000	5	12000	340
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-12-14	9/4/2019	857.77	12 - 14 ft	180-95165-2	Not Excavated	5600	< 0.36 U	3.6	63	0.19 J	0.14 J	77000	7.9		5.4	21	13000	5.3	11000	350
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	6300	< 0.36 U	4.1	57	0.24 J	0.12 J	49000	9.4		5.3	23	15000	6.2	12000	640
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-2-4	9/4/2019	857.77	2 - 4 ft	180-95165-2	Not Excavated	8700	< 0.39 UJ	8.1	67	0.42 J	0.11 J	2900 J	10		6.8	26	18000	20	2300	510
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-4-6	9/4/2019	857.77	4 - 6 ft	180-95165-2	Not Excavated	5800	< 0.37 U	5.9	49	0.26 J	0.14 J	26000	7.2		5 J	17	13000	9.3	15000	600
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-6-8	9/4/2019	857.77	6 - 8 ft	180-95165-2	Not Excavated	5700	< 0.35 U	4.5	39	0.22 J	0.095 J	45000	7		5.1 J	20	13000	13	11000	380
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-8-10	9/4/2019	857.77	8 - 10 ft	180-95165-2	Not Excavated	5100	< 0.36 U	3.9	42	0.22 J	0.1 J	42000	7.8		5 J	16	12000	7.4	13000	430
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-2-4	8/30/2019	857.68	2 - 4 ft	180-95047-2	Excavated	7600	< 0.47 U	7	74	0.37 J	0.25 J	3000	12		5.4 J	29	17000	28	1500	390
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-4-6	8/30/2019	857.68	4 - 6 ft	180-95047-2	Excavated	5100	< 0.39 UJ	3.2	27	0.21 J	0.058 J	13000	7.2		4.1 J	15	12000	6.1	7500 J-	330
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-6-8	8/30/2019	857.68	6 - 8 ft	180-95047-2	Excavated	9800	3.6 J	6.9	100	0.48 J	0.12 J	1800	12		6.8	23	17000	2400	2300	440
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-10-12	8/30/2019	857.68	10 - 12 ft	180-95047-2	Not Excavated	4400	< 0.4 U	6.7	30	0.22 J	0.068 J	870	6.4		4.7 J	12	12000	8.7	1300	350
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-12-14	8/30/2019	857.68	12 - 14 ft	180-95047-2	Not Excavated	7300	< 0.4 U	5.7	56	0.33 J	0.089 J	13000	9.6		6.6	19	17000	8.3	6000	460
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-14-16	8/30/2019	857.68	14 - 16 ft	180-95047-2	Not Excavated	5300	< 0.36 U	4.3	48	0.22 J	0.077 J	30000	7		4.5 J	15	12000	5.6	7000	340
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-8-10	8/30/2019	857.68	8 - 10 ft	180-95047-2	Not Excavated	11000	< 0.4 U	6	77	0.45 J	0.068 J	1300	14		6.7	26	18000	33	2500	400
Football Field	SSHS-B3094	SSHS-DUP-56	8/30/2019	857.26	6 - 8 ft	180-95050-2	Not Excavated	6300	< 0.41 UJ	5	38	0.28 J	0.12 J	6300 J	8.2		5.6 J	24 J-	15000	7.6	2700 J-	500
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-10-12	8/28/2019	857.12	10 - 12 ft	180-94902-2	Not Excavated	5100	< 0.37 U	4.7	35	0.22 J	0.097 J	33000	6.9		5 J	16	12000	9.7	9700	480
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	5800	< 0.39 U	5.4	39	0.23 J	0.065 J	18000	8.3		5.2 J	29	15000	9	5100	360
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-6-8	8/28/2019	857.12	6 - 8 ft	180-94902-2	Not Excavated	6700	< 0.39 U	4.8	53	0.28 J	0.057 J	800	8.2		5.6 J	14	14000	7.4	1700	540
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-8-10	8/28/2019	857.12	8 - 10 ft	180-94902-2	Not Excavated	6900	< 0.36 U	6.7	61	0.3 J	0.083 J	2000	13		5.9	22	15000	14	2300	420
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-2-4	8/28/2019	857.12	2 - 4 ft	180-94902-2	Excavated	9000	0.59 J	6.5	89	0.41 J	0.11 J	4000	12		6.9	61	17000	36	2400	610
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-4-6	8/28/2019	857.12	4 - 6 ft	180-94902-2	Excavated	10000	< 0.41 U	6.1	110	0.41 J	0.07 J	2700	12		6	17	16000	24	2400	470
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-10-12	8/27/2019	855.86	10 - 12 ft	180-94819-3	Not Excavated	6600	0.39 J	6.4	42	0.3 J	0.12 J	1500	9.8		5.9	20	15000	8.9	2100	500
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-12-14	8/27/2019	855.86	12 - 14 ft	180-94819-3	Not Excavated	5900	< 0.38 U	7.9	48	0.24 J	0.12 J	15000	8.8		6.4	16	14000	12	4200	530
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	6000	< 0.37 U	5.8	42	0.26 J	0.11 J	25000	16		5.6	20	14000	9	7600	420
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-4-6	8/27/2019	855.86	4 - 6 ft	180-94819-3	Not Excavated	12000	< 0.38 U	6.6	51	0.47	0.07 J	2100	14		7.7	15	19000	11	2300	310
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-6-8	8/27/2019	855.86	6 - 8 ft	180-94819-3	Not Excavated	7400	< 0.38 U	6.6	43	0.32 J	0.069 J	1200	10		6.5	20	16000	10	2000	430
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-8-10	8/27/2019	855.86	8 - 10 ft	180-94819-3	Not Excavated	9800	< 0.41 UJ	8.9	86	0.46 J	0.11 J	1700	14		7.9	29	20000	10	2700	570
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-2-4	8/27/2019	855.86	2 - 4 ft	180-94819-3	Excavated	9800	< 0.41 U	7.1	110	0.41 J	0.069 J	3800	13		6.1	16	15000	19	1800	620
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-10-12	8/27/2019	856.19	10 - 12 ft	180-94819-3	Not Excavated	6800	< 0.4 U	6.4	42	0.32 J	0.097 J	13000	10		6.1	21	16000	10	5100	430
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-6-8	8/27/2019	856.19	6 - 8 ft	180-94819-3	Not Excavated	8300	< 0.38 U	7	60	0.4 J	0.1 J	6500	11		7.7	22	18000	12	2300	520
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-8-10	8/27/2019	856.19	8 - 10 ft	180-94819-3	Not Excavated	5700	< 0.41 U	6.9	35	0.26 J	0.11 J	50000	7.6		5.3 J	18	13000	11	29000	400
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	5700	< 0.38 U	5.3	36	0.24 J	0.086 J	29000	9.8		5.3 J	19	14000	7.7	10000	380
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-2-4	8/27/2019	856.19	2 - 4 ft	180-94819-3	Excavated	8100	0.45 J	8.3	99	0.41 J	0.16 J	8100	15		7	42	18000	46	2400	540
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-4-6	8/27/2019	856.19	4 - 6 ft	180-94819-3	Excavated	8200	< 0.4 U	6.9	71	0.41 J	0.099 J	14000	11		7.1	31	18000	21	2700	450
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-10-12	8/26/2019	855.97	10 - 12 ft	180-94754-1	Not Excavated	6000	< 0.34 U	4.2	49	0.26 J	0.087 J	23000	8.1		5.5	17	14000	7.1	3200	340
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-4-6	8/26/2019	855.97	4 - 6 ft	180-94754-1	Not Excavated	8800	< 0.4 U	7.4	67	0.44 J	0.082 J	8900	11		7.6	20	17000	16	4100	490
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-6-8	8/26/2019	855.97	6 - 8 ft	180-94754-1	Not Excavated	7700	< 0.39 U	7.7	110	0.56	0.1 J	9800	13		8.7	15	15000	10	6300	560
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-8-10	8/26/2019	855.97	8 - 10 ft	180-94754-1	Not Excavated	8300	< 0.37 U	6.5	57	0.37 J	0.076 J	10000	11		7.5	17	17000	9.7	6500	410
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	4800	< 0.37 U	4.1	44	0.21 J	0.082 J	41000	9.4		4.5 J	15	12000	7.9	12000	410
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-2-4	8/26/2019	855.97	2 - 4 ft	180-94754-1	Excavated	7800	< 0.4 U	5.6	84	0.39 J	0.12 J	21000	11		6	25	16000	20	7300	480
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-10-12	8/26/2019	856.40	10 - 12 ft	180-94754-1	Not Excavated	4600	< 0.36 U	4.2	33	0.18 J	0.095 J	37000	10		4.4 J	17	12000	14	11000	380
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-2-4	8/26/2019	856.40	2 - 4 ft	180-94754-1	Not Excavated	8900	< 0.36 U	6.1	59	0.4 J	0.16 J	30000	14		6.8	20	18000	14	5500	480
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-4-6	8/26/2019	856.40	4 - 6 ft	180-94754-1	Not Excavated	6900	< 0.37 U	6.5	55	0.34 J	0.12 J	14000	13		6.2	35	17000	9.6	4900	550
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-6-8	8/26/2019	856.40	6 - 8 ft	180-94754-1	Not Excavated	5200	< 0.35 U	5	34	0.22 J	0.11 J	34000	8.2		5.1	19	14000	9.6	12000	480
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-8-10	8/26/2019	856.40	8 - 10 ft	180-94754-1	Not Excavated	5500	< 0.36 U	5.8	45	0.22 J	0.12 J	42000	12		5.1 J	21	14000	10	11000	430
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	5000	< 0.38 U	5.2	47	0.22 J	0.1 J	36000	9.7		4.9 J	17	13000	7.3	9000	400
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	3700	< 0.3 U	2.8	35	0.13 J	0.085 J	31000	5.8		3.6 J	14	9800	6	4400	350
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-10-12	1/13/2020	856.74	10 - 12 ft	180-100985-1	Not Excavated	5200	< 0.33 U	4.1	36	0.21 J	0.11 J	28000	8.7		4.7 J	18	13000	6.8	6500	380
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	6000	< 0.35 U	8.1	39	0.24 J	0.13 J	25000	11		5.4	16	15000	6.9	5600	320
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-4-6	1/13/2020	856.74	4 - 6 ft	180-100985-1	Not Excavated	5300	< 0.37 U	4	38	0.23 J	0.088 J	7900	11		4.7 J	16	13000	7.6	2100	430
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-6-8	1/13/2020	856.74	6 - 8 ft	180-100985-1	Not Excavated	4800	< 0.38 U	4.6	33	0.21 J	0.15 J	28000	7.4		4.7 J	17	12000	9.4	7600	630
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-8-10	1/13/2020	856.74	8 - 10 ft	180-100985-1	Not Excavated	4900	< 0.35 U	3.9	36	0.18 J	0.22 J	31000	6.7		4.6 J	15	13000	9.3	6400	420
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated	6200	< 0.3 U	5	43	0.28 J	0.13 J	7200	9.5		4.7	15	13000	25	3100	310
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-4-6	1/13/2020	856.75	4 - 6 ft	180-100985-1	Excavated	5800	< 0.28 U	4.7	75	0.28 J	0.089 J	2300	11		4.8	16	13000	13	1900	300
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-10-12	1/13/2020	856.75	10 - 12 ft	180-100985-1	Not Excavated	5500	< 0.36 U	5.1	33	0.25 J	0.15 J	35000	7.6		5.5	20	14000	7.3	3900	420

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-8-10	8/30/2019	856.73	8 - 10 ft	180-95047-3	Not Excavated	0.016 J	13	680	0.94 J	< 0.12 U	78 J		< 0.36 U		9.2	45
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-10-12	8/29/2019	857.13	10 - 12 ft	180-95024-2	Not Excavated	< 0.015 U	16	810	< 0.52 U	< 0.11 U	72 J		< 0.32 U		12	58
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	< 0.015 U	15	760	< 0.56 UJ	< 0.11 U	71 J		< 0.35 U		12	55
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-2-4	8/29/2019	857.13	2 - 4 ft	180-95024-1	Not Excavated	0.016 J	18	690	< 0.62 U	< 0.13 U	52 J		< 0.39 U		13	54
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-4-6	8/29/2019	857.13	4 - 6 ft	180-95024-1	Not Excavated	< 0.013 U	13	690	< 0.53 U	< 0.11 U	63 J		< 0.33 U		9.6	57
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-6-8	8/29/2019	857.13	6 - 8 ft	180-95024-2	Not Excavated	0.018 J	13	690	< 0.57 U	< 0.12 U	44 J		< 0.36 U		11	44
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-8-10	8/29/2019	857.13	8 - 10 ft	180-95024-2	Not Excavated	< 0.015 U	13	710	0.61 J	< 0.11 U	71 J		< 0.33 U		10	41
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-10-12	8/29/2019	856.55	10 - 12 ft	180-95006-2	Not Excavated	< 0.013 U	12	660	0.94 J	< 0.11 U	73 J		< 0.33 U		8.7	42
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	< 0.014 U	13	620	< 0.52 U	< 0.11 U	72 J		< 0.32 U		9.5	48
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-2-4	8/29/2019	856.55	2 - 4 ft	180-95006-1	Not Excavated	< 0.016 U	19	790	< 0.58 U	< 0.12 U	46 J		< 0.36 U		14	62
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-4-6	8/29/2019	856.55	4 - 6 ft	180-95006-1	Not Excavated	< 0.016 U	9.5	520 J	< 0.63 U	< 0.13 U	34 J		< 0.39 U		9.3	63
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-6-8	8/29/2019	856.55	6 - 8 ft	180-95006-1	Not Excavated	< 0.017 U	12	680	0.59 J	< 0.12 U	72 J		< 0.36 U		9.8	48
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-8-10	8/29/2019	856.55	8 - 10 ft	180-95006-2	Not Excavated	< 0.013 U	15	570	1 J	< 0.12 U	74 J		< 0.36 U		9.5	50
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-10-12	9/4/2019	857.12	10 - 12 ft	180-95165-3	Not Excavated	< 0.015 U	13	730	0.82 J	< 0.12 U	96 J		< 0.37 U		9.7	40
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	< 0.014 U	11	650	0.84 J	< 0.11 U	79 J		< 0.35 U		7.7	38
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-2-4	9/4/2019	857.12	2 - 4 ft	180-95165-3	Not Excavated	< 0.015 U	17	710	< 0.56 U	< 0.11 U	41 J		< 0.35 U		13	58
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-4-6	9/4/2019	857.12	4 - 6 ft	180-95165-3	Not Excavated	< 0.014 U	9.9	630	< 0.56 U	< 0.11 U	39 J		< 0.35 U		8	37
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-6-8	9/4/2019	857.12	6 - 8 ft	180-95165-3	Not Excavated	< 0.014 U	15	790	< 0.55 U	< 0.11 U	78 J		< 0.35 U		10	52
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-8-10	9/4/2019	857.12	8 - 10 ft	180-95165-3	Not Excavated	< 0.014 U	11	780	< 0.56 U	< 0.11 U	79 J		< 0.35 U		8	46
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-10-12	9/4/2019	857.77	10 - 12 ft	180-95165-2	Not Excavated	< 0.013 U	9.9	560	0.56 J	< 0.11 U	92 J		< 0.32 U		7.4	40
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-12-14	9/4/2019	857.77	12 - 14 ft	180-95165-2	Not Excavated	< 0.015 U	13	650	1.1	< 0.11 U	86 J		< 0.34 U		11	52
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	< 0.015 U	14	740	0.74 J	< 0.11 U	87 J		< 0.34 U		9.1	52
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-2-4	9/4/2019	857.77	2 - 4 ft	180-95165-2	Not Excavated	0.28 J	16	610	< 0.59 U	< 0.12 U	57 J		< 0.37 U		14	59
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-4-6	9/4/2019	857.77	4 - 6 ft	180-95165-2	Not Excavated	< 0.014 U	12	650	< 0.56 U	< 0.11 U	87 J		< 0.35 U		9.6	62
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-6-8	9/4/2019	857.77	6 - 8 ft	180-95165-2	Not Excavated	< 0.013 U	13	600	0.58 J	< 0.11 U	98 J		< 0.33 U		8.2	44
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-8-10	9/4/2019	857.77	8 - 10 ft	180-95165-2	Not Excavated	< 0.014 U	12	640	0.67 J	< 0.11 U	93 J		< 0.34 U		9.3	44
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-2-4	8/30/2019	857.68	2 - 4 ft	180-95047-2	Excavated	0.022 J	15	720	< 0.71 U	< 0.14 U	120 J		< 0.44 U		14	47
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-4-6	8/30/2019	857.68	4 - 6 ft	180-95047-2	Excavated	< 0.015 U	11	650	< 0.59 U	< 0.12 U	54 J		< 0.37 U		7	40
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-6-8	8/30/2019	857.68	6 - 8 ft	180-95047-2	Excavated	< 0.016 U	16	920	< 0.64 U	< 0.13 U	48 J		< 0.4 U		14	51
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-10-12	8/30/2019	857.68	10 - 12 ft	180-95047-2	Not Excavated	< 0.018 U	12	610	< 0.6 U	< 0.12 U	56 J		< 0.37 U		7.4	33
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-12-14	8/30/2019	857.68	12 - 14 ft	180-95047-2	Not Excavated	< 0.017 U	16	920	< 0.6 U	< 0.12 U	60 J		< 0.37 U		12	61
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-14-16	8/30/2019	857.68	14 - 16 ft	180-95047-2	Not Excavated	< 0.016 U	11	610	< 0.55 U	< 0.11 U	69 J		< 0.34 U		7.9	41
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-8-10	8/30/2019	857.68	8 - 10 ft	180-95047-2	Not Excavated	< 0.016 U	15	770	< 0.61 U	< 0.13 U	52 J		< 0.38 U		17	53
Football Field	SSHS-B3094	SSHS-DUP-56	8/30/2019	857.26	6 - 8 ft	180-95050-2	Not Excavated	< 0.018 U	14	660 J	< 0.63 U	< 0.13 U	66 J		< 0.39 U		11	56
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-10-12	8/28/2019	857.12	10 - 12 ft	180-94902-2	Not Excavated	< 0.013 U	12	680	0.64 J	< 0.11 U	80 J		< 0.35 U		8.7	43
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	< 0.016 U	12	710	< 0.6 U	< 0.12 U	72 J		< 0.37 U		9.1	52
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-6-8	8/28/2019	857.12	6 - 8 ft	180-94902-2	Not Excavated	0.019 J	12	490 J	< 0.6 U	< 0.12 U	64 J		< 0.37 U		10	46
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-8-10	8/28/2019	857.12	8 - 10 ft	180-94902-2	Not Excavated	0.022 J	15	730	< 0.55 U	< 0.11 U	63 J		< 0.34 U		11	58
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-2-4	8/28/2019	857.12	2 - 4 ft	180-94902-2	Excavated	0.065	24	910	< 0.63 U	< 0.13 U	67 J		< 0.4 U		14	67
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-4-6	8/28/2019	857.12	4 - 6 ft	180-94902-2	Excavated	0.074	15	650	0.62 J	< 0.13 U	67 J		< 0.38 U		15	58
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-10-12	8/27/2019	855.86	10 - 12 ft	180-94819-3	Not Excavated	0.02 J	15	790	< 0.52 U	< 0.11 U	51 J		< 0.32 U		12	69
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-12-14	8/27/2019	855.86	12 - 14 ft	180-94819-3	Not Excavated	< 0.015 U	14	700	< 0.58 U	< 0.12 U	59 J		< 0.36 U		9	71
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	< 0.014 U	14	800	< 0.56 U	< 0.12 U	85 J		< 0.35 U		11	54
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-4-6	8/27/2019	855.86	4 - 6 ft	180-94819-3	Not Excavated	< 0.015 U	16	780	< 0.57 U	< 0.12 U	43 J		< 0.35 U		18	59
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-6-8	8/27/2019	855.86	6 - 8 ft	180-94819-3	Not Excavated	< 0.016 U	15	740	< 0.58 U	< 0.12 U	47 J		< 0.36 U		12	56
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-8-10	8/27/2019	855.86	8 - 10 ft	180-94819-3	Not Excavated	< 0.015 U	21	1000	< 0.62 U	< 0.13 U	50 J		< 0.39 U		16	90
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-2-4	8/27/2019	855.86	2 - 4 ft	180-94819-3	Excavated	0.033 J	13	680	< 0.63 U	< 0.13 U	50 J		< 0.39 U		15	59
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-10-12	8/27/2019	856.19	10 - 12 ft	180-94819-3	Not Excavated	0.019 J	15	850	< 0.61 U	< 0.12 U	< 31 U		< 0.38 U		12	52
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-6-8	8/27/2019	856.19	6 - 8 ft	180-94819-3	Not Excavated	0.021 J	18	810	< 0.57 U	< 0.12 U	< 29 U		< 0.36 U		13	59
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-8-10	8/27/2019	856.19	8 - 10 ft	180-94819-3	Not Excavated	< 0.015 U	13	850	0.76 J	< 0.13 U	56 J		< 0.38 U		10	48
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	< 0.015 U	13	820	0.66 J	< 0.12 U	< 29 U		< 0.36 U		9.4	47
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-2-4	8/27/2019	856.19	2 - 4 ft	180-94819-3	Excavated	0.2	31	760	0.58 J	< 0.12 U	< 29 U		< 0.36 U		15	78
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-4-6	8/27/2019	856.19	4 - 6 ft	180-94819-3	Excavated	0.076	17	810	< 0.6 U	< 0.12 U	< 30 UJ		< 0.37 U		14	54
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-10-12	8/26/2019	855.97	10 - 12 ft	180-94754-1	Not Excavated	< 0.013 U	13	650	< 0.52 U	< 0.11 U	67 J		< 0.32 U		8.7	55
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-4-6	8/26/2019	855.97	4 - 6 ft	180-94754-1	Not Excavated	0.05	15	710	< 0.61 U	< 0.13 U	63 J		< 0.38 U		12	60
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-6-8	8/26/2019	855.97	6 - 8 ft	180-94754-1	Not Excavated	0.036	20	1200	< 0.6 U	< 0.12 U	93 J		< 0.37 U		12	63
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-8-10	8/26/2019	855.97	8 - 10 ft	180-94754-1	Not Excavated	0.023 J	18	860	< 0.56 U	< 0.11 U	61 J		< 0.35 U		14	51
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	0.015 J	11	590	0.59 J	< 0.11 U	95 J		< 0.35 U		7.7	45
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-2-4	8/26/2019	855.97	2 - 4 ft	180-94754-1	Excavated	0.051	14	730	0.81 J	< 0.12 U	88 J		< 0.38 U		13	63
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-10-12	8/26/2019	856.40	10 - 12 ft	180-94754-1	Not Excavated	< 0.014 U	11	580	0.55 J	< 0.11 U	79 J		< 0.34 U		7.1	41
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-2-4	8/26/2019	856.40	2 - 4 ft	180-94754-1	Not Excavated	0.037	16	720	0.86 J	< 0.11 U	80 J		< 0.34 U		13	58
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-4-6	8/26/2019	856.40	4 - 6 ft	180-94754-1	Not Excavated	0.023 J	17	660	< 0.55 U	< 0.11 U	72 J		< 0.35 U		11	51
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-6-8	8/26/2019	856.40	6 - 8 ft	180-94754-1	Not Excavated	< 0.015 U	13	630	< 0.53 U	< 0.11 U	90 J		< 0.33 U		8.6	44
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-8-10	8/26/2019	856.40	8 - 10 ft	180-94754-1	Not Excavated	< 0.013 U	13	680	0.88 J	< 0.11 U	110 J		< 0.34 U		8	49
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	< 0.014 U	12	590	< 0.57 U	< 0.12 U	97 J		< 0.36 U		7.9	48
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	0.1	11	240 J	0.63 J	< 0.093 U	< 54 U		< 0.28 U		10	40
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-10-12	1/13/2020	856.74	10 - 12 ft	180-100985-1	Not Excavated	< 0.023 U	12	490	0.71 J	< 0.1 U	60 J		< 0.31 U		8.5	49
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	< 0.021 U	14	570	< 0.53 U	< 0.11 U	62 J		< 0.33 U		10	47
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-4-6	1/13/2020	856.74	4 - 6 ft	180-100985-1	Not Excavated	0.028 J	12	460 J	< 0.56 U	< 0.11 U	< 66 U		< 0.35 U		9.5	42
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-6-8	1/13/2020	856.74	6 - 8 ft	180-100985-1	Not Excavated	0.06	12	520 J	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U		9.8	40
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-8-10	1/13/2020	856.74	8 - 10 ft	180-100985-1	Not Excavated	< 0.024 U	12	480 J	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U		7.8	57
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated	0.085	12	480	< 0.45 U	< 0.093 U	< 53 U		< 0.28 U		12	61
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-4-6	1/13/2020	856.75	4 - 6 ft	180-100985-1	Excavated	0.041	13	480	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U		9.6	50
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-10-12	1/13/2020	856.75	10 - 12 ft	180-100985-1	Not Excavated	< 0.024 U	14	650	< 0.55 U	< 0.11 U	73 J		< 0.34 U		10	49

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	5900	< 0.33 U	4.6	45	0.24 J	0.12 J	22000	9.6		5.4	22	14000	7.2	5700	370
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-6-8	1/13/2020	856.75	6 - 8 ft	180-100985-1	Not Excavated	4200	< 0.36 U	5.3	27	0.22 J	0.13 J	2600	6		4.5 J	15	12000	6.6	1800	320
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-8-10	1/13/2020	856.75	8 - 10 ft	180-100985-1	Not Excavated	5100	< 0.36 U	4.5	37	0.25 J	0.11 J	7500	8.1		5 J	17	14000	6.7	2800	340
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	6300	< 0.3 U	4.5	41	0.32 J	0.087 J	6100	9.1		5.3	15	14000	14	1900	330
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-4-6	1/13/2020	856.74	4 - 6 ft	180-100985-1	Excavated	7100	< 0.36 U	5.6	39	0.32 J	0.093 J	17000	11		5.9	19	15000	12	3000	360
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-10-12	1/13/2020	856.74	10 - 12 ft	180-100985-1	Not Excavated	4900	< 0.32 U	4	40	0.2 J	0.18 J	40000	8.5		4.5 J	15	11000	10	7700	310
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	5000	< 0.29 U	4.6	40	0.21 J	0.11 J	37000	14		4.7	17	12000	8.6	12000	400
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-6-8	1/13/2020	856.74	6 - 8 ft	180-100985-1	Not Excavated	4400	< 0.36 U	4.5	24	0.22 J	0.09 J	8800	6		4.5 J	15	12000	6.6	2300	350
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-8-10	1/13/2020	856.74	8 - 10 ft	180-100985-1	Not Excavated	5300	< 0.34 U	4	57	0.22 J	0.13 J	42000	9.6		4.8 J	16	12000	6.2	4600	350
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-10-12	1/13/2020	856.47	10 - 12 ft	180-100985-2	Excavated	3600	< 0.3 U	4.1	26	0.15 J	0.091 J	35000	5.1		3.6 J	17	9300	7.8	11000	270
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-12-14	1/13/2020	856.47	12 - 14 ft	180-100985-2	Excavated	5000	< 0.33 U	5.1	31	0.22 J	0.13 J	30000	7		4.8 J	16	12000	8.4	4100	370
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-4-6	1/13/2020	856.47	4 - 6 ft	180-100985-2	Excavated	5800	< 0.37 U	5.1	50	0.23 J	0.082 J	15000	8.4		4.4 J	13	13000	45	3200	390
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-6-8	1/13/2020	856.47	6 - 8 ft	180-100985-2	Excavated	8000	< 0.29 UJ	15	47 J-	0.34	0.14 J	7300 J-	10		7.2	22 J-	17000	23	2800 J-	480
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-8-10	1/13/2020	856.47	8 - 10 ft	180-100985-2	Excavated	6800	< 0.24 U	8.2	39	0.27 J	0.1 J	8400	8.9		6	17	15000	18	2600	370
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	5000	< 0.33 U	6.6	32	0.2 J	0.13 J	20000	8.4		5	18	13000	10	5600	430
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated	7000	< 0.35 U	6.9	64	0.33 J	0.13 J	9100	9.3		6.4	24	16000	36	2700	400
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-10-12	1/13/2020	856.82	10 - 12 ft	180-100985-2	Not Excavated	6100	< 0.36 U	4.1	49	0.22 J	0.14 J	37000	11		5.1 J	19	14000	6.1	8500	450
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	5400	< 0.31 U	3.4	41	0.22 J	0.11 J	29000	10		4.7	14	12000	5.4	6100	350
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-4-6	1/13/2020	856.82	4 - 6 ft	180-100985-2	Not Excavated	5400	< 0.33 U	3.9	26	0.2 J	0.091 J	4100	7.9		4.2 J	16	13000	6.4	2500	250
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-6-8	1/13/2020	856.82	6 - 8 ft	180-100985-2	Not Excavated	3900	< 0.36 U	3.3	30	0.15 J	0.083 J	29000	6.5		3.3 J	13	9000	6.2	4800	230
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-8-10	1/13/2020	856.82	8 - 10 ft	180-100985-2	Not Excavated	5700	< 0.35 U	4.7	43	0.23 J	0.13 J	38000	11		4.8 J	16	13000	6.5	4800	410
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated	5800	< 0.36 U	8.3	68	0.27 J	0.16 J	20000	8.8		5.1 J	23	14000	54	2900	570
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-4-6	1/14/2020	856.73	4 - 6 ft	180-101038-1	Excavated	5900	< 0.3 U	6	49	0.25 J	0.12 J	3500	8.6		6.2	15	14000	10	2400	820
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-10-12	1/14/2020	856.73	10 - 12 ft	180-101038-1	Not Excavated	4500	< 0.26 U	3.4	54	0.18 J	0.1 J	40000	7.9		6	17	13000	4.7	7000	380
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	5100	< 0.23 U	3.4	45	0.17 J	0.093 J	29000	8.4		4.9	14	12000	6	9600	350
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-6-8	1/14/2020	856.73	6 - 8 ft	180-101038-1	Not Excavated	4700	< 0.29 U	4.1	36	0.18 J	0.11 J	31000	7.4		4.3	14	11000	11	8800	390
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-8-10	1/14/2020	856.73	8 - 10 ft	180-101038-1	Not Excavated	4600	< 0.34 U	4.2	37	0.19 J	0.1 J	29000	8.6		4.2 J	16	13000	8.6	6400	480
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated	6700	< 0.23 U	5.2	35	0.3	0.081 J	1900	8		5.8	16	14000	13	2100	330
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-4-6	1/14/2020	856.72	4 - 6 ft	180-101038-1	Excavated	7100	< 0.37 U	7.6	44	0.31 J	0.15 J	19000	11		6.1	21	16000	14	6500	470
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-10-12	1/14/2020	856.72	10 - 12 ft	180-101038-1	Not Excavated	4000	< 0.37 U	5.2	23	0.19 J	0.098 J	4600	6.7		3.4 J	24	11000	8.3	1800	290
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	4300	< 0.29 U	4.1	26	0.19 J	0.11 J	17000	6.6		4 J	14	10000	10	4200	310
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-6-8	1/14/2020	856.72	6 - 8 ft	180-101038-1	Not Excavated	4400	< 0.32 U	4.7	30	0.18 J	0.1 J	8000	7.8		3.7 J	17	11000	9.6	2300	340
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-8-10	1/14/2020	856.72	8 - 10 ft	180-101038-1	Not Excavated	5500	< 0.28 U	5.5	26	0.25 J	0.11 J	8500	8		5.2	19	13000	8.8	3000	350
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-2-4	1/15/2020	857.05	2 - 4 ft	180-101084-1	Excavated	5100	< 0.33 U	4.4	40	0.22 J	0.089 J	26000	6.9		4.4 J	17	12000	18	2000	340
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-10-12	1/15/2020	857.05	10 - 12 ft	180-101084-1	Not Excavated	4400	< 0.34 U	3.5	36	0.15 J	0.1 J	46000	7.6		4.4 J	17	11000	6.5	6100	330
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	3900	< 0.34 U	3.1	41	0.15 J	0.13 J	48000	8.4		3.8 J	18	10000	6.2	12000	390
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-4-6	1/15/2020	857.05	4 - 6 ft	180-101084-1	Not Excavated	4600	< 0.37 U	5.1	29	0.2 J	0.15 J	2000	7.2		4.1 J	17	12000	7.9	1800	460
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-6-8	1/15/2020	857.05	6 - 8 ft	180-101084-1	Not Excavated	5200	< 0.32 U	5.5	35	0.21 J	0.12 J	19000	12		5	16	13000	11	5500	430
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-8-10	1/15/2020	857.05	8 - 10 ft	180-101084-1	Not Excavated	4100	< 0.35 U	4.2	42	0.15 J	0.11 J	58000	5.6		4 J	14	11000	12	19000	340
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-2-4	1/14/2020	857.55	2 - 4 ft	180-101038-3	Excavated	7900	< 0.39 U	6.5	82	0.38 J	0.17 J	7300	10		6.4	40	16000	50	2600	590
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-10-12	1/14/2020	857.55	10 - 12 ft	180-101038-3	Not Excavated	4700	< 0.4 U	5	29	0.22 J	0.13 J	27000	6.2		4.7 J	15	12000	6.4	4800	240
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	5100	< 0.35 U	4.2	54	0.23 J	0.18 J	40000	8		5.3	22	13000	8.3	7200	510
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-4-6	1/14/2020	857.55	4 - 6 ft	180-101038-3	Not Excavated	6100	< 0.37 U	4.9	46	0.24 J	0.12 J	21000	9.2		5.2 J	130	14000	17	6700	360
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-6-8	1/14/2020	857.55	6 - 8 ft	180-101038-3	Not Excavated	4900	< 0.33 U	5	38	0.22 J	0.13 J	36000	6.9		4.6 J	22	12000	9.8	11000	340
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-8-10	1/14/2020	857.55	8 - 10 ft	180-101038-3	Not Excavated	5200	< 0.3 U	4	47	0.19 J	0.098 J	36000	7.7		4.9	18	12000	7.1	13000	310
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-2-4	1/15/2020	857.26	2 - 4 ft	180-101084-2	Excavated	7800	< 0.38 U	6.7	76	0.37 J	0.15 J	7700	10		6.3	26	17000	48	2600	430
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-4-6	1/15/2020	857.26	4 - 6 ft	180-101084-2	Excavated	5600	< 0.33 U	4.2	43	0.24 J	0.1 J	2400	7.9		5.1	21	13000	14	2000	310
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-10-12	1/15/2020	857.26	10 - 12 ft	180-101084-2	Not Excavated	6900	< 0.37 U	5.4	67	0.29 J	0.12 J	25000	12		6.1	21	16000	16	5300	390
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	3900	< 0.35 U	4	42	0.16 J	0.094 J	38000	5.9		4 J	13	10000	6.5	5900	290
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-6-8	1/15/2020	857.26	6 - 8 ft	180-101084-2	Not Excavated	7100	< 0.35 U	5.5	69	0.35 J	0.16 J	23000	12		6.2	27	15000	31	4000	470
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-8-10	1/15/2020	857.26	8 - 10 ft	180-101084-2	Not Excavated	5000	< 0.32 U	4.9	56	0.2 J	0.12 J	46000	7.7		4.9	18	12000	16	9800	480
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-2-4	1/15/2020	856.32	2 - 4 ft	180-101084-2	Excavated	6800	< 0.37 U	6.2	51	0.32 J	0.12 J	3400	9.2		6.5	25	17000	9.2	2200	620
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-10-12	1/15/2020	856.32	10 - 12 ft	180-101084-2	Not Excavated	4800	< 0.36 U	4.4	34	0.21 J	0.11 J	28000	6.7		4.6 J	15	12000	5.7	3500	290
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	4800	< 0.36 U	3.8	34	0.2 J	0.13 J	43000	7.6		4.6 J	18	12000	6.4	6600	360
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-4-6	1/15/2020	856.32	4 - 6 ft	180-101084-2	Not Excavated	5400	< 0.36 U	4.7	31	0.23 J	0.11 J	14000	7.9		4.7 J	20	14000	7.2	4700	490
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-6-8	1/15/2020	856.32	6 - 8 ft	180-101084-2	Not Excavated	5900	< 0.31 U	4.1	41	0.22 J	0.15 J	21000	8.9		5.4	23	14000	6.4	3900	440
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-8-10	1/15/2020	856.32	8 - 10 ft	180-101084-2	Not Excavated	4800	< 0.33 UJ	4.6	37	0.19 J	0.15 J	39000 J	7		5.1	13	13000 J	6.9	5500	500 J
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-2-4	1/15/2020	857.08	2 - 4 ft	180-101084-1	Excavated	4900	< 0.33 U	6.9	30	0.22 J	0.092 J	11000	9		3.9 J	14	11000	12	3400	290
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-10-12	1/15/2020	857.08	10 - 12 ft	180-101084-1	Not Excavated	6000	< 0.36 U	4.4	41	0.21 J	0.13 J	34000	10		5.7	21	15000	9	7500	360
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	4400	< 0.33 U	3.3	66	0.16 J	0.093 J	44000	7.4		4.4 J	15	12000	5.5	4500	310
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-4-6	1/15/2020	857.08	4 - 6 ft	180-101084-1	Not Excavated	5900	< 0.33 U	5.8	40	0.26 J	0.091 J	1500	8.1		5.2	19	14000	11	1900	430
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-6-8	1/15/2020	857.08	6 - 8 ft	180-101084-1	Not Excavated	6100	< 0.35 U	4.8	41	0.24 J	0.14 J	6100	8.5		5.4	16	14000	8.1	3100	550
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-8-10	1/15/2020	857.08	8 - 10 ft	180-101084-1	Not Excavated	3600	< 0.35 UJ	3.3	22	0.12 J	0.11 J	45000	5.4		3.3 J	11	8900	5.3	5300 J	290
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated	8000	< 0.37 U	6.8	74	0.37 J	0.15 J	5100	11		6.4	21	17000	33	2700	590
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-4-6	1/15/2020	856.71	4 - 6 ft	180-101084-2	Excavated	4800	< 0.36 U	2.7	33	0.2 J	0.11 J	9200	6.5		4.4 J	15	12000	4.7	2000	420
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-10-12	1/15/2020	856.71	10 - 12 ft	180-101084-3	Not Excavated	5500	< 0.34 U	5	42	0.2 J	0.17 J	39000	7.7		5.7	14	14000	10	7800	610
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	1900	< 0.32 U	2.1	25	0.071 J	0.13 J	84000	7.5		2 J	8.3	5700	3.9	11000	210
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-6-8	1/15/2020	856.71	6 - 8 ft	180-101084-2	Not Excavated	6600	< 0.36 U	3.7	37	0.23 J	0.092 J	9100	10		5.2 J	18	15000	9.1	3200	340
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-8-10	1/15/2020	856.71	8 - 10 ft	180-101084-2	Not Excavated	5200	< 0.35 U	4.9	33	0.19 J	0.12 J	53000	7.5		4.8 J	16	13000	8.8	18000	370
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-2-4	1/14/2020	856.36	2 - 4 ft	180-101038-2	Excavated	6600	< 0.32 U	4.5	62	0.26 J	0.13 J	28000	10		4.9	18	13000	31	4900	360
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-10-12	1/14/2020	856.36	10 - 12 ft	180-101038-2	Not Excavated	4900	< 0.33 U	5.1	31	0.18 J	0.22 J	34000	7.4		4.1 J	19	13000	33	5300	290
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-4-6	1/14/2020	856.36	4 - 6 ft	180-101038-2	Not Excavated	8200	< 0.33 U	15	65	0.37 J	0.34 J	15000	11		6.7	33	22000	440	3400	530
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-6-8	1/14/2020	856.36	6 - 8 ft	180-101038-2	Not Excavated	5700	< 0.33 U	6.1	38	0.25 J	0.17 J	5700	8		4.5 J	19	13000	39	1900	340
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-8-10	1/14/2020	856.36	8 - 10 ft	180-101038-2	Not Excavated	5100	< 0.34 U	5.5	37	0.21 J	0.11 J	12000	7.8		4.5 J	23	12000	26	2500	390

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	< 0.023 U	15	640	< 0.49 U	< 0.1 U	60 J		< 0.31 U		11	51
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-6-8	1/13/2020	856.75	6 - 8 ft	180-100985-1	Not Excavated	< 0.025 U	11	520 J	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		8.4	41
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-8-10	1/13/2020	856.75	8 - 10 ft	180-100985-1	Not Excavated	< 0.023 U	12	620	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		11	41
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	0.13	13	460	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U		11	40
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-4-6	1/13/2020	856.74	4 - 6 ft	180-100985-1	Excavated	0.098 J	16	700	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		11	43
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-10-12	1/13/2020	856.74	10 - 12 ft	180-100985-1	Not Excavated	< 0.023 U	12	640	0.49 J	< 0.098 U	68 J		< 0.3 U		7.6	50
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	< 0.023 U	13	570	0.66 J	< 0.09 U	68 J		< 0.27 U		8.3	41
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-6-8	1/13/2020	856.74	6 - 8 ft	180-100985-1	Not Excavated	< 0.024 U	11	610	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U		8.1	34
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-8-10	1/13/2020	856.74	8 - 10 ft	180-100985-1	Not Excavated	0.031 J	13	630	< 0.51 U	< 0.1 U	75 J		< 0.32 U		9	54
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-10-12	1/13/2020	856.47	10 - 12 ft	180-100985-2	Excavated	< 0.025 U	8.2	600	0.77 J	< 0.091 U	60 J		< 0.28 U		7	31
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-12-14	1/13/2020	856.47	12 - 14 ft	180-100985-2	Excavated	0.041	12	610	0.7 J	< 0.1 U	64 J		< 0.31 U		8.7	41
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-4-6	1/13/2020	856.47	4 - 6 ft	180-100985-2	Excavated	0.039	11	430 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		10	44
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-6-8	1/13/2020	856.47	6 - 8 ft	180-100985-2	Excavated	< 0.026 U	16	680 J-	< 0.44 U	< 0.089 U	57 J		< 0.27 U		13	80 J+
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-8-10	1/13/2020	856.47	8 - 10 ft	180-100985-2	Excavated	0.11	15	520	< 0.36 U	< 0.073 U	47 J		< 0.22 U		10	64
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	< 0.023 U	13	500	< 0.51 U	< 0.1 U	< 59 U		< 0.31 U		8.9	49
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated	0.2 J+	19	580	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		14	62
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-10-12	1/13/2020	856.82	10 - 12 ft	180-100985-2	Not Excavated	< 0.021 U	14	770	< 0.54 U	< 0.11 U	82 J		< 0.34 U		11	45
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	< 0.024 U	13	590	< 0.47 U	< 0.096 U	68 J		< 0.29 U		8.9	43
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-4-6	1/13/2020	856.82	4 - 6 ft	180-100985-2	Not Excavated	0.073	12	400 J	< 0.5 U	< 0.1 U	< 59 U		< 0.31 U		9.7	40
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-6-8	1/13/2020	856.82	6 - 8 ft	180-100985-2	Not Excavated	0.036	8.7	430 J	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U		7.2	31
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-8-10	1/13/2020	856.82	8 - 10 ft	180-100985-2	Not Excavated	< 0.021 U	13	680	0.87 J	< 0.11 U	73 J		< 0.33 U		9.7	47
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated	0.58	13	520 J	< 0.55 U	0.28 J	< 65 U		< 0.34 U		14	72
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-4-6	1/14/2020	856.73	4 - 6 ft	180-101038-1	Excavated	< 0.025 U	14	520	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U		10	54
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-10-12	1/14/2020	856.73	10 - 12 ft	180-101038-1	Not Excavated	< 0.021 U	12	650	0.61 J	< 0.081 U	59 J		< 0.25 U		8.5	42
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	0.025 J	12	490	0.37 J	< 0.071 U	59 J		< 0.22 U		8.5	49
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-6-8	1/14/2020	856.73	6 - 8 ft	180-101038-1	Not Excavated	0.043	11	500	< 0.44 U	< 0.09 U	63 J		< 0.28 U		9.5	41
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-8-10	1/14/2020	856.73	8 - 10 ft	180-101038-1	Not Excavated	0.029 J	11	560	< 0.51 U	< 0.11 U	62 J		< 0.32 U		8.9	35
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated	0.18	15	480	< 0.35 U	< 0.071 U	< 41 U		< 0.22 U		10	47
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-4-6	1/14/2020	856.72	4 - 6 ft	180-101038-1	Excavated	0.05	15	590	< 0.56 U	< 0.11 U	< 66 U		< 0.35 U		13	59
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-10-12	1/14/2020	856.72	10 - 12 ft	180-101038-1	Not Excavated	< 0.025 U	9.2	470 J	< 0.57 U	< 0.12 U	< 66 U		< 0.35 U		7.7	54
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	0.028 J	10	470	< 0.44 U	< 0.089 U	< 51 U		< 0.27 U		8.1	43
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-6-8	1/14/2020	856.72	6 - 8 ft	180-101038-1	Not Excavated	0.072	10	430 J	< 0.48 U	< 0.098 U	< 56 U		< 0.3 U		10	49
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-8-10	1/14/2020	856.72	8 - 10 ft	180-101038-1	Not Excavated	0.026 J	14	530	< 0.43 U	< 0.088 U	< 51 U		< 0.27 U		10	46
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-2-4	1/15/2020	857.05	2 - 4 ft	180-101084-1	Excavated	0.041	11	430 J	< 0.5 U	< 0.1 U	< 58 U		< 0.31 U		8.9	45
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-10-12	1/15/2020	857.05	10 - 12 ft	180-101084-1	Not Excavated	< 0.023 U	11	510	0.64 J	< 0.1 U	75 J		< 0.32 U		7.3	40
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	< 0.022 U	9.3	510	0.68 J	< 0.1 U	78 J		< 0.32 U		7.2	44
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-4-6	1/15/2020	857.05	4 - 6 ft	180-101084-1	Not Excavated	< 0.023 U	12	530 J	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U		7.9	49
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-6-8	1/15/2020	857.05	6 - 8 ft	180-101084-1	Not Excavated	< 0.022 U	13	550	< 0.48 U	< 0.099 U	< 57 U		< 0.3 U		8.9	48
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-8-10	1/15/2020	857.05	8 - 10 ft	180-101084-1	Not Excavated	< 0.021 U	9.9	500 J	0.83 J	< 0.11 U	80 J		< 0.33 U		7.3	43
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-2-4	1/14/2020	857.55	2 - 4 ft	180-101038-3	Excavated	0.62	28	660	< 0.59 U	< 0.12 U	72 J		< 0.37 U		13	100
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-10-12	1/14/2020	857.55	10 - 12 ft	180-101038-3	Not Excavated	< 0.026 U	11	660	< 0.6 U	< 0.12 U	< 71 U		< 0.38 U		8.7	41
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	< 0.022 U	13	600	< 0.52 U	< 0.11 U	72 J		< 0.33 U		8.4	100
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-4-6	1/14/2020	857.55	4 - 6 ft	180-101038-3	Not Excavated	0.14	14	600	< 0.56 U	< 0.11 U	83 J		< 0.35 U		9.6	49
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-6-8	1/14/2020	857.55	6 - 8 ft	180-101038-3	Not Excavated	< 0.024 U	11	740	< 0.5 U	< 0.1 U	88 J		< 0.31 U		9	45
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-8-10	1/14/2020	857.55	8 - 10 ft	180-101038-3	Not Excavated	< 0.021 U	12	580	< 0.46 U	< 0.094 U	89 J		< 0.29 U		9	43
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-2-4	1/15/2020	857.26	2 - 4 ft	180-101084-2	Excavated	0.056	17	580	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		13	69
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-4-6	1/15/2020	857.26	4 - 6 ft	180-101084-2	Excavated	< 0.024 U	14	480 J	< 0.5 U	< 0.1 U	< 59 U		< 0.31 U		8.7	42
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-10-12	1/15/2020	857.26	10 - 12 ft	180-101084-2	Not Excavated	< 0.023 U	16	630	0.66 J	< 0.11 U	< 66 U		< 0.35 U		11	52
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	< 0.022 U	9.7	460 J	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U		6.6	36
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-6-8	1/15/2020	857.26	6 - 8 ft	180-101084-2	Not Excavated	0.065	18	620	0.59 J	< 0.11 U	< 62 U		< 0.33 U		13	63
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-8-10	1/15/2020	857.26	8 - 10 ft	180-101084-2	Not Excavated	< 0.022 U	12	520	0.99	< 0.099 U	60 J		< 0.3 U		7.8	43
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-2-4	1/15/2020	856.32	2 - 4 ft	180-101084-2	Excavated	< 0.019 U	14	630	< 0.56 U	< 0.11 U	< 66 U		< 0.35 U		11	47
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-10-12	1/15/2020	856.32	10 - 12 ft	180-101084-2	Not Excavated	< 0.023 U	12	540	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		7.2	38
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	< 0.023 U	11	600	< 0.54 U	< 0.11 U	70 J		< 0.34 U		8.3	46
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-4-6	1/15/2020	856.32	4 - 6 ft	180-101084-2	Not Excavated	< 0.024 U	12	560	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U		8.7	42
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-6-8	1/15/2020	856.32	6 - 8 ft	180-101084-2	Not Excavated	< 0.023 U	13	550	0.66 J	< 0.094 U	< 54 U		< 0.29 U		9.2	74
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-8-10	1/15/2020	856.32	8 - 10 ft	180-101084-2	Not Excavated	< 0.022 U	12	580	0.68 J	< 0.1 U	< 59 U		< 0.32 U		7.7	45
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-2-4	1/15/2020	857.08	2 - 4 ft	180-101084-1	Excavated	< 0.023 U	9.1	420 J	< 0.5 U	< 0.1 U	< 58 U		< 0.31 U		8.9	44
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-10-12	1/15/2020	857.08	10 - 12 ft	180-101084-1	Not Excavated	< 0.022 U	14	560	0.55 J	< 0.11 U	68 J		< 0.34 U		10	60
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	< 0.023 U	10	470 J	0.69 J	< 0.1 U	64 J		< 0.31 U		7.8	40
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-4-6	1/15/2020	857.08	4 - 6 ft	180-101084-1	Not Excavated	< 0.025 U	12	540	< 0.5 U	< 0.1 U	< 59 U		< 0.31 U		9.6	51
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-6-8	1/15/2020	857.08	6 - 8 ft	180-101084-1	Not Excavated	< 0.022 U	13	590	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		10	61
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-8-10	1/15/2020	857.08	8 - 10 ft	180-101084-1	Not Excavated	< 0.023 U	7.8	370 J	0.61 J	< 0.11 U	< 63 U		< 0.33 U		6.1	30 J+
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated	0.031 J	17	670	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		13	62
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-4-6	1/15/2020	856.71	4 - 6 ft	180-101084-2	Excavated	0.12	11	390 J	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		8.4	89
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-10-12	1/15/2020	856.71	10 - 12 ft	180-101084-3	Not Excavated	< 0.022 U	13	660	0.87 J	< 0.11 U	71 J		< 0.33 U		8.6	44
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	< 0.024 U	5.9	350 J	1	< 0.098 U	67 J		< 0.3 U		3.6 J	17
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-6-8	1/15/2020	856.71	6 - 8 ft	180-101084-2	Not Excavated	< 0.023 U	14	540	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U		11	45
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-8-10	1/15/2020	856.71	8 - 10 ft	180-101084-2	Not Excavated	< 0.022 U	12	610	0.9 J	< 0.11 U	83 J		< 0.33 U		8.6	46
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-2-4	1/14/2020	856.36	2 - 4 ft	180-101038-2	Excavated	0.29	13	640	0.65 J	< 0.098 U	69 J		< 0.3 U		11	56
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-10-12	1/14/2020	856.36	10 - 12 ft	180-101038-2	Not Excavated	< 0.023 U	11	560	< 0.5 U	< 0.1 U	61 J		< 0.31 U		7.5	63
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-4-6	1/14/2020	856.36	4 - 6 ft	180-101038-2	Not Excavated	0.12	17	660	1	< 0.1 U	< 59 U		0.31 J		14	160
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-6-8	1/14/2020	856.36	6 - 8 ft	180-101038-2	Not Excavated	0.028 J	12	560	< 0.51 U	< 0.1 U	< 59 U		< 0.32 U		8.8	62
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-8-10	1/14/2020	856.36	8 - 10 ft	180-101038-2	Not Excavated	< 0.025 U	11	620	< 0.51 U	< 0.1 U	< 60 U		< 0.32 U		9.2	48

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	4500	< 0.35 U	3.7	30	0.18 J	0.12 J	29000	7.8		4 J	22	11000	13	11000	340
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-2-4	1/15/2020	856.51	2 - 4 ft	180-101084-1	Excavated	5600	< 0.34 UJ	4.5	37	0.23 J	0.062 J	1500 J-	7.1 J-		4.7 J	17 J-	12000	11	1700 J-	340
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-10-12	1/15/2020	856.51	10 - 12 ft	180-101084-1	Not Excavated	5400	< 0.3 U	4.9	30	0.22 J	0.13 J	32000	8.4		6	20	13000	7.8	5000	380
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	5000	< 0.32 U	3.8	28	0.16 J	0.097 J	24000	7.7		4.5 J	42	13000	5	6500	330
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-4-6	1/15/2020	856.51	4 - 6 ft	180-101084-1	Not Excavated	6100	< 0.35 U	4.8	38	0.26 J	0.1 J	1000	8.1		5.5	24	15000	8.8	1800	460
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-6-8	1/15/2020	856.51	6 - 8 ft	180-101084-1	Not Excavated	5800	< 0.27 U	5.7	35	0.25 J	0.1 J	16000	8.4		5.4	31	14000	12	8900	430
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-8-10	1/15/2020	856.51	8 - 10 ft	180-101084-1	Not Excavated	5800	< 0.36 U	4.8	34	0.26 J	0.31 J	24000 J	9		5.2 J	19	14000	8	5100	380
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-2-4	1/14/2020	856.54	2 - 4 ft	180-101038-2	Excavated	7700	< 0.32 U	5.6	34	0.31 J	0.076 J	5900	9.3		5.9	19	15000	12	2700	350
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-4-6	1/14/2020	856.54	4 - 6 ft	180-101038-2	Excavated	8400	< 0.36 UJ	7.4	51 J-	0.37 J	0.1 J	3300 J	11		8.1	23 J-	19000	13	2600 J	560
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-10-12	1/14/2020	856.54	10 - 12 ft	180-101038-2	Not Excavated	4400	< 0.35 U	3.6	26	0.18 J	0.091 J	43000	6.2		4 J	14	11000	6.6	12000	360
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	5800	< 0.35 U	5.2	32	0.22 J	0.14 J	31000	9.1		5.6	18	14000	9.6	9000	470
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-6-8	1/14/2020	856.54	6 - 8 ft	180-101038-2	Not Excavated	5600	< 0.31 U	4.5	37	0.24 J	0.094 J	4700	9.9		4.9	17	14000	8.1	2100	560
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-6-8	1/15/2020	856.74	6 - 8 ft	180-101084-3	Not Excavated	3900	< 0.36 U	5.3	100	0.22 J	0.14 J	27000	6.5		4.1 J	26	10000	7.5	14000	2300
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-10-12	1/15/2020	856.74	10 - 12 ft	180-101084-3	Not Excavated	5500	< 0.34 U	5.7	42	0.21 J	0.13 J	35000	8		5.2	17	14000	8.4	6300	430
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	5300	< 0.34 U	6	33	0.25 J	0.12 J	24000	7.2		5.3	17	14000	7.1	3900	230
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-2-4	1/15/2020	856.74	2 - 4 ft	180-101084-3	Not Excavated	7000	< 0.36 U	6.6	38	0.31 J	0.13 J	3000	11		6.4	18	17000	11	2500	610
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-4-6	1/15/2020	856.74	4 - 6 ft	180-101084-3	Not Excavated	7000	< 0.35 U	4.9	52	0.31 J	0.14 J	8400	9.4		6	19	17000	8.9	4300	480
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-8-10	1/15/2020	856.74	8 - 10 ft	180-101084-3	Not Excavated	5400	< 0.37 U	4.3	45	0.2 J	0.13 J	58000	7.7		5.3 J	13	13000	6.7	9300	410
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-10-12	8/29/2019	857.57	10 - 12 ft	180-95006-3	Not Excavated	5300	< 0.37 U	4.2	39	0.21 J	0.1 J	63000	8		4.6 J	16	12000	7.3	20000	360
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-12-14	8/29/2019	857.57	12 - 14 ft	180-95024-1	Not Excavated	5000	< 0.36 U	3.9	45	0.2 J	0.05 J	46000	7.9		4.3 J	14	11000	5.4	9600	320
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	6000	< 0.36 U	3.7	51	0.2 J	0.064 J	44000	7.9		5.4	14	14000	5.4	7500	290
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-6-8	8/29/2019	857.57	6 - 8 ft	180-95006-3	Not Excavated	6400	< 0.36 U	4.5	40	0.26 J	0.064 J	18000	9.4		6.5	18	15000	33	6300	510
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-8-10	8/29/2019	857.57	8 - 10 ft	180-95006-3	Not Excavated	3700	< 0.36 UJ	4.5	26	0.18 J	0.091 J	18000	6.7		3.6 J	12	10000	5.4	3900 J	230
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-2-4	8/29/2019	857.57	2 - 4 ft	180-95006-3	Excavated	7300	0.55 J	7.1	54	0.36 J	0.062 J	1100	9.2		5.7	22	17000	10	1800	580
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-4-6	8/29/2019	857.57	4 - 6 ft	180-95006-3	Excavated	6700	< 0.37 U	8.5	42	0.26 J	0.068 J	27000	9.2		6	21	16000	7.7	16000	640
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated	8300	0.40 J	6.8	85	0.39	0.23 J	2800	11		6.4	26	17000	28	1700	510
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	8300	0.60 J	7.4	85	0.42 J	0.18 J	2600	12		7.1	22	17000	31	1800	430
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-10-12	8/29/2019	857.45	10 - 12 ft	180-95024-1	Not Excavated	6600	< 0.37 U	4.9	46	0.26 J	0.084 J	31000	8.8		6.1	17	18000	6.2	11000	410
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-12-14	8/29/2019	857.45	12 - 14 ft	180-95024-1	Not Excavated	7000	< 0.37 U	4.9	50	0.28 J	0.088 J	58000	8.9		6	19	15000	15	11000	440
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	4600	< 0.38 U	4.6	47	0.18 J	0.084 J	89000	11		4.1 J	14	11000	5.6	9600	270
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-2-4	8/29/2019	857.45	2 - 4 ft	180-95024-1	Not Excavated	8300	0.55 J	7.2	69	0.37 J	0.075 J	760	10		5.7	21	16000	19	1700	470
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-4-6	8/29/2019	857.45	4 - 6 ft	180-95024-1	Not Excavated	7300	0.54 J	6.6	58	0.35 J	0.071 J	810	15		6.2	22	17000	11	2000	520
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-6-8	8/29/2019	857.45	6 - 8 ft	180-95024-1	Not Excavated	6100	< 0.37 U	5.4	61	0.26 J	0.051 J	4100	7.7		5.2 J	14	15000	6.4	3000	390
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-8-10	8/29/2019	857.45	8 - 10 ft	180-95024-1	Not Excavated	4400	< 0.38 U	3.8	40	0.19 J	0.11 J	65000	6		4.5 J	14	11000	9.3	4400	650
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated	5300	< 0.32 U	4.4	45	0.2 J	0.1 J	33000	8.9		4.3 J	19	13000	22 J	7200	360
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-4-6	1/14/2020	856.70	4 - 6 ft	180-101038-1	Excavated	2800	< 0.38 U	2.8	23	0.13 J	0.056 J	5400	4.1		2.3 J	8.9	7600	5.3	2300	250
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-10-12	1/14/2020	856.70	10 - 12 ft	180-101038-1	Not Excavated	4500	< 0.3 U	4	31	0.18 J	0.097 J	28000	8.5		4 J	16	11000	7	5000	290
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-6-8	1/14/2020	856.70	6 - 8 ft	180-101038-1	Not Excavated	5100	< 0.4 U	2.9	39	0.2 J	0.11 J	20000	6.7		4.8 J	14	13000	8	3600	540
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-8-10	1/14/2020	856.70	8 - 10 ft	180-101038-1	Not Excavated	6300	< 0.38 U	6.8	40	0.28 J	0.18 J	38000	12		6.5	21	17000	20	8800	440
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	3000	< 0.29 U	2.7	21	0.11 J	0.059 J	29000	6.4		2.8 J	9.6	8000	5.3	4300	270
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-2-4	1/14/2020	856.85	2 - 4 ft	180-101038-2	Excavated	4600	< 0.37 U	4.4	34	0.2 J	0.21 J	130000 J	6		4.7 J	20	13000	6.2 J	6100	570
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-4-6	1/14/2020	856.85	4 - 6 ft	180-101038-2	Excavated	5100	< 0.28 U	4.5	33	0.22 J	0.13 J	6100	8.3		4.8	20	13000	6.9	3200	670
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-10-12	1/14/2020	856.85	10 - 12 ft	180-101038-2	Not Excavated	5800	< 0.31 U	6.2	37	0.23 J	0.12 J	28000	9.2		5.6	18	14000	9	4800	390
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-6-8	1/14/2020	856.85	6 - 8 ft	180-101038-2	Not Excavated	6700	< 0.32 U	4.7	30	0.25 J	0.11 J	23000	8.8		5.7	39	16000	6.6	11000	390
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-8-10	1/14/2020	856.85	8 - 10 ft	180-101038-2	Not Excavated	4900	< 0.29 U	4.7	32	0.21 J	0.12 J	29000	6.7		5	16	12000	6.8	4500	320
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	5200	< 0.32 U	4.5	37	0.19 J	0.12 J	42000	10		4.7 J	19	13000	8	12000	430
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-10-12	8/30/2019	855.06	10 - 12 ft	180-95050-2	Not Excavated	5500	< 0.35 U	6.1	46	0.2 J	0.11 J	50000	9.6		4.9 J	16	13000	8	12000	390
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	6400	< 0.37 U	4.9	56	0.23 J	0.092 J	31000	8.3		5.8	20	15000	10	9200	470
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-4-6	8/30/2019	855.06	4 - 6 ft	180-95050-2	Not Excavated	11000	0.55 J	9.1	110	0.56	0.12 J	6400	14		8.7	45	22000	13	4900	520
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-6-8	8/30/2019	855.06	6 - 8 ft	180-95050-2	Not Excavated	6900	< 0.35 U	4.6	67	0.26 J	0.17 J	42000	10		6.4	20	15000	9	10000	720
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-8-10	8/30/2019	855.06	8 - 10 ft	180-95050-2	Not Excavated	6500	< 0.35 U	5.2	62	0.24 J	0.15 J	41000	11		6.2	33	19000	11	15000	740
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-2-4	8/30/2019	855.06	2 - 4 ft	180-95050-1	Excavated	9000	< 0.4 U	6.9	72	0.42 J	0.062 J	590	11		9	21	18000	11	2300	630
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-10-12	9/4/2019	857.44	10 - 12 ft	180-95165-3	Not Excavated	7200	< 0.37 U	5.2	40	0.29 J	0.096 J	8400	12		6.5	15	16000	18	3900	400
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-12-14	9/4/2019	857.44	12 - 14 ft	180-95165-3	Not Excavated	6600	< 0.34 U	5.9	47	0.26 J	0.083 J	21000	8.7		5.7	19	15000	7.3	5800	420
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	7700	< 0.37 U	10	47	0.3 J	0.098 J	26000	14		7.2	32	17000	14	5900	630
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-2-4	9/4/2019	857.44	2 - 4 ft	180-95165-3	Not Excavated	8300	< 0.39 U	5.8	51	0.35 J	0.099 J	7700	10		6.8	18	17000	10	2300	780
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-4-6	9/4/2019	857.44	4 - 6 ft	180-95165-3	Not Excavated	6700	< 0.37 U	5.3	49	0.27 J	0.14 J	24000	12		5.8	25	16000	7.3	5500	570
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-6-8	9/4/2019	857.44	6 - 8 ft	180-95165-3	Not Excavated	6100	< 0.37 U	5.7	46	0.28 J	0.095 J	27000	9.5		5.8	23	14000	7.1	8300	520
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-8-10	9/4/2019	857.44	8 - 10 ft	180-95165-3	Not Excavated	6000	< 0.36 U	4.9	38	0.25 J	0.078 J	22000	8.7		5.3	16	13000	8.2	4900	390
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-10-12	9/4/2019	857.92	10 - 12 ft	180-95165-3	Not Excavated	4400	< 0.38 U	3.7	56	0.17 J	0.14 J	88000	6.3		4.1 J	24	11000	5	6600	370
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-12-14	9/4/2019	857.92	12 - 14 ft	180-95165-3	Not Excavated	5600	< 0.34 U	3.7	51	0.21 J	0.19 J	56000	7.6		5.3	20	13000	5.8	7900	420
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	5000	< 0.37 U	5.2	50	0.2 J	0.14 J	44000	6.4		4.6 J	17	12000	6.6	6000	440
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-2-4	9/4/2019	857.92	2 - 4 ft	180-95165-2	Not Excavated	7900	1 J	7.9	62	0.37 J	0.13 J	2100	9.4		6.5	22	17000	38	2400	420
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-4-6	9/4/2019	857.92	4 - 6 ft	180-95165-2	Not Excavated	7600	< 0.44 U	7.4	45	0.39 J	0.11 J	1200	10		6.5	26	19000	13	2100	560
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-6-8	9/4/2019	857.92	6 - 8 ft	180-95165-3	Not Excavated	5600	< 0.38 U	5.7	41	0.24 J	0.13 J	32000	7.3		5.5 J	17	13000	7.6	4400	540
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-8-10	9/4/2019	857.92	8 - 10 ft	180-95165-3	Not Excavated	5000	< 0.39 U	3.7	37	0.19 J	0.094 J	51000	6.5		4.2 J	17	12000	5.1	13000	470
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-10-12	8/30/2019	858.28	10 - 12 ft	180-95047-2	Not Excavated	6000	< 0.34 U	4.1	74	0.23 J	0.097 J	52000	8.4		5.8	20	14000	9.6	13000	450
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-12-14	8/30/2019	858.28	12 - 14 ft	180-95047-2	Not Excavated	5800	< 0.36 U	5	51	0.2 J	0.11 J	54000	7.9		5.1 J	19	14000	5.1	16000	450
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-14-16	8/30/2019	858.28	14 - 16 ft	180-95047-2	Not Excavated	4900	< 0.35 U	4.1	46	0.19 J	0.053 J	36000	6.6		4.6 J	13	11000	8.2	9100	440
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-2-4	8/30/2019	858.28	2 - 4 ft	180-95047-1	Not Excavated	11000	0.58 J	6.8	130	0.49 J	0.066 J	2200	13		7.7	17	18000	20 J	2500	590
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-4-6	8/30/2019	858.28	4 - 6 ft	180-95047-1	Not Excavated	6500	0.69 J	6	43	0.29 J	0.068 J	1000	8.4		5.7	21	15000	9.8	1800	460
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-6-8	8/30/2019	858.28	6 - 8 ft	180-95047-1	Not Excavated	5300	< 0.38 U	4.4	30	0.2 J	0.093 J	72000	7.3		4.8 J	20	13000	6.7	25000	500
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-8-10	8/30/2019	858.28	8 - 10 ft	180-95047-1	Not Excavated	6000	< 0.34 U	3.6	83	0.18 J	0.071 J	37000	15		4.7 J	21	15000	5.5	10000	620
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-2-4	8/29/2019	858.27	2 - 4 ft	180-95006-2	Not Excavated	7900	0.46 J	14	72	0.39 J	0.19 J	2300	9.9		8.6	19	18000	17	1500	1400

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	< 0.024 U	10	570	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U		7.5	41
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-2-4	1/15/2020	856.51	2 - 4 ft	180-101084-1	Excavated	0.044	12	400 J	< 0.51 UJ	< 0.11 UJ	< 60 UJ		< 0.32 U		8.9 J-	37 J+
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-10-12	1/15/2020	856.51	10 - 12 ft	180-101084-1	Not Excavated	< 0.023 U	14	530	< 0.45 U	< 0.092 U	< 53 U		< 0.28 U		9.2	47
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	< 0.023 U	10	430 J	< 0.48 U	< 0.099 U	< 57 U		< 0.3 U		8	47
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-4-6	1/15/2020	856.51	4 - 6 ft	180-101084-1	Not Excavated	< 0.025 U	13	550	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		9.8	41
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-6-8	1/15/2020	856.51	6 - 8 ft	180-101084-1	Not Excavated	< 0.022 U	14	520	< 0.41 U	< 0.083 U	53 J		< 0.25 U		9.7	48
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-8-10	1/15/2020	856.51	8 - 10 ft	180-101084-1	Not Excavated	< 0.023 U	13	630	< 0.55 UJ	< 0.11 U	< 64 UJ		< 0.34 U		8.8	66
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-2-4	1/14/2020	856.54	2 - 4 ft	180-101038-2	Excavated	0.022 J	14	600	< 0.49 U	< 0.1 U	< 58 U		< 0.31 U		12	48
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-4-6	1/14/2020	856.54	4 - 6 ft	180-101038-2	Excavated	< 0.026 U	18 J-	800 J-	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U		14 J-	56 J
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-10-12	1/14/2020	856.54	10 - 12 ft	180-101038-2	Not Excavated	< 0.023 U	10	530	< 0.53 U	< 0.11 U	73 J		< 0.33 U		7.7	34
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	< 0.022 U	13	630	< 0.54 U	< 0.11 U	74 J		< 0.33 U		10	48
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-6-8	1/14/2020	856.54	6 - 8 ft	180-101038-2	Not Excavated	0.082	11	530	< 0.47 U	< 0.096 U	< 55 U		0.29 J		9.2	42
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-6-8	1/15/2020	856.74	6 - 8 ft	180-101084-3	Not Excavated	< 0.022 U	9.9	640	< 1.1 U	< 0.22 U	87 J		< 0.68 U		7.3	36
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-10-12	1/15/2020	856.74	10 - 12 ft	180-101084-3	Not Excavated	< 0.021 U	13	620	< 0.52 U	< 0.11 U	65 J		< 0.32 U		8.6	49
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	< 0.021 U	14	670	< 0.51 U	< 0.11 U	< 60 U		< 0.32 U		8.8	43
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-2-4	1/15/2020	856.74	2 - 4 ft	180-101084-3	Not Excavated	< 0.024 U	15	660	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U		11	53
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-4-6	1/15/2020	856.74	4 - 6 ft	180-101084-3	Not Excavated	< 0.024 U	15	620	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U		11	57
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-8-10	1/15/2020	856.74	8 - 10 ft	180-101084-3	Not Excavated	< 0.024 U	13	580	0.93 J	< 0.11 U	69 J		< 0.35 U		8.4	40
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-10-12	8/29/2019	857.57	10 - 12 ft	180-95006-3	Not Excavated	< 0.014 U	12	750	1.3	< 0.12 U	100 J		< 0.35 U		8.9	46
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-12-14	8/29/2019	857.57	12 - 14 ft	180-95024-1	Not Excavated	< 0.016 U	10	920	0.58 J	< 0.11 U	88 J		< 0.34 U		8.7	34
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	< 0.012 U	12	660	0.94 J	< 0.11 U	85 J		< 0.34 U		8.7	46
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-6-8	8/29/2019	857.57	6 - 8 ft	180-95006-3	Not Excavated	< 0.015 U	14	670	< 0.54 U	< 0.11 U	81 J		< 0.34 U		13	50
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-8-10	8/29/2019	857.57	8 - 10 ft	180-95006-3	Not Excavated	< 0.014 U	8.7	570	< 0.55 U	< 0.11 U	64 J		< 0.34 U		8.3	35
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-2-4	8/29/2019	857.57	2 - 4 ft	180-95006-3	Excavated	< 0.018 U	13	680	< 0.59 U	< 0.12 U	43 J		< 0.37 U		12	48
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-4-6	8/29/2019	857.57	4 - 6 ft	180-95006-3	Excavated	< 0.016 U	15	660	0.56 J	< 0.11 U	72 J		< 0.35 U		11	53
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated	0.022 J	16	600	< 0.49 U	< 0.10 U	100 J		< 0.31 U		14	56
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	0.089	16	620	< 0.58 U	< 0.12 U	73 J		< 0.36 U		14	60
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-10-12	8/29/2019	857.45	10 - 12 ft	180-95024-1	Not Excavated	< 0.016 U	14	730	0.56 J	< 0.11 U	72 J		< 0.35 U		12	75
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-12-14	8/29/2019	857.45	12 - 14 ft	180-95024-1	Not Excavated	< 0.016 U	16	900	1.2	< 0.12 U	87 J		< 0.35 U		9.7	60
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	< 0.015 U	10	700	1.6	< 0.12 U	89 J		< 0.36 U		8.8	46
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-2-4	8/29/2019	857.45	2 - 4 ft	180-95024-1	Not Excavated	0.024 J	13	610	< 0.57 U	< 0.12 U	39 J		< 0.36 U		14	48
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-4-6	8/29/2019	857.45	4 - 6 ft	180-95024-1	Not Excavated	0.012 J	16	730	< 0.57 U	< 0.12 U	58 J		< 0.36 U		13	50
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-6-8	8/29/2019	857.45	6 - 8 ft	180-95024-1	Not Excavated	< 0.015 U	12	730	< 0.57 U	< 0.12 U	52 J		< 0.35 U		11	69
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-8-10	8/29/2019	857.45	8 - 10 ft	180-95024-1	Not Excavated	< 0.016 U	10	710	0.8 J	< 0.12 U	80 J		< 0.36 U		7.8	40
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated	0.055 J	13	440 J	0.76 J	< 0.098 U	60 J		< 0.3 U		13	48
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-4-6	1/14/2020	856.70	4 - 6 ft	180-101038-1	Excavated	0.039 J	6.6	350 J	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		5.8	22
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-10-12	1/14/2020	856.70	10 - 12 ft	180-101038-1	Not Excavated	0.025 J	11	530	< 0.46 U	< 0.093 U	56 J		< 0.28 U		9.2	35
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-6-8	1/14/2020	856.70	6 - 8 ft	180-101038-1	Not Excavated	< 0.025 U	12	450 J	< 0.6 U	< 0.12 U	< 71 U		< 0.37 U		10	43
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-8-10	1/14/2020	856.70	8 - 10 ft	180-101038-1	Not Excavated	< 0.023 U	16	750	0.57 J	< 0.12 U	94 J		< 0.36 U		13	55
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	< 0.022 U	7.4	340 J	< 0.44 U	< 0.09 U	< 52 U		< 0.27 U		6.6	25
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-2-4	1/14/2020	856.85	2 - 4 ft	180-101038-2	Excavated	0.036 J	13	560	1.6 J	< 0.11 U	100 J		< 0.35 U		8.8	55
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-4-6	1/14/2020	856.85	4 - 6 ft	180-101038-2	Excavated	< 0.023 U	13	550	< 0.43 U	< 0.087 U	< 50 U		< 0.27 U		9	39
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-10-12	1/14/2020	856.85	10 - 12 ft	180-101038-2	Not Excavated	< 0.022 U	14	650	0.72 J	< 0.097 U	61 J		< 0.3 U		9.8	45
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-6-8	1/14/2020	856.85	6 - 8 ft	180-101038-2	Not Excavated	< 0.021 U	15	640	< 0.49 U	< 0.1 U	63 J		< 0.31 U		11	54
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-8-10	1/14/2020	856.85	8 - 10 ft	180-101038-2	Not Excavated	< 0.024 U	13	600	0.6 J	< 0.09 U	55 J		< 0.27 U		8.2	41
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	< 0.021 U	12	640	< 0.49 U	< 0.1 U	74 J		< 0.31 U		8.6	43
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-10-12	8/30/2019	855.06	10 - 12 ft	180-95050-2	Not Excavated	< 0.014 U	12	550	0.63 J	< 0.11 U	70 J		< 0.33 U		8.4	45
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	< 0.015 U	14	550	0.84 J	< 0.11 U	56 J		< 0.35 U		9	55
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-4-6	8/30/2019	855.06	4 - 6 ft	180-95050-2	Not Excavated	< 0.018 U	21	1300	< 0.62 U	< 0.13 U	59 J		< 0.39 U		18	99
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-6-8	8/30/2019	855.06	6 - 8 ft	180-95050-2	Not Excavated	< 0.015 U	15	690	< 0.53 U	< 0.11 U	67 J		< 0.33 U		10	60
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-8-10	8/30/2019	855.06	8 - 10 ft	180-95050-2	Not Excavated	< 0.014 U	19	590	0.69 J	< 0.11 U	72 J		< 0.33 U		11	62
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-2-4	8/30/2019	855.06	2 - 4 ft	180-95050-1	Excavated	0.04	18	800	< 0.6 U	< 0.12 U	36 J		< 0.38 U		13	58
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-10-12	9/4/2019	857.44	10 - 12 ft	180-95165-3	Not Excavated	< 0.014 U	16	760	< 0.57 U	< 0.12 U	60 J		< 0.35 U		11	52
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-12-14	9/4/2019	857.44	12 - 14 ft	180-95165-3	Not Excavated	< 0.014 U	14	740	0.76 J	< 0.11 U	70 J		< 0.33 U		10	53
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	< 0.015 U	16	970	0.64 J	< 0.11 U	84 J		< 0.35 U		12	58
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-2-4	9/4/2019	857.44	2 - 4 ft	180-95165-3	Not Excavated	< 0.015 U	15	690	< 0.59 U	< 0.12 U	59 J		< 0.37 U		13	52
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-4-6	9/4/2019	857.44	4 - 6 ft	180-95165-3	Not Excavated	< 0.015 U	14	820	< 0.56 U	< 0.11 U	75 J		< 0.35 U		11	73
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-6-8	9/4/2019	857.44	6 - 8 ft	180-95165-3	Not Excavated	< 0.013 U	13	860	0.79 J	< 0.12 U	80 J		< 0.35 U		10	45
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-8-10	9/4/2019	857.44	8 - 10 ft	180-95165-3	Not Excavated	0.05	13	890	0.73 J	< 0.11 U	79 J		< 0.34 U		8.9	44
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-10-12	9/4/2019	857.92	10 - 12 ft	180-95165-3	Not Excavated	< 0.015 U	11	620	1.2	< 0.12 U	100 J		< 0.36 U		6.6	36
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-12-14	9/4/2019	857.92	12 - 14 ft	180-95165-3	Not Excavated	< 0.013 U	12	680	0.71 J	< 0.1 U	100 J		< 0.32 U		9.7	60
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	< 0.014 U	11	670	0.68 J	< 0.11 U	80 J		< 0.35 U		7.7	54
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-2-4	9/4/2019	857.92	2 - 4 ft	180-95165-2	Not Excavated	0.033 J	18	620	0.63 J	< 0.13 U	54 J		< 0.39 U		12	51
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-4-6	9/4/2019	857.92	4 - 6 ft	180-95165-2	Not Excavated	< 0.016 U	17	820	< 0.66 U	< 0.14 U	49 J		< 0.41 U		13	62
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-6-8	9/4/2019	857.92	6 - 8 ft	180-95165-3	Not Excavated	< 0.015 U	13	790	< 0.58 U	< 0.12 U	78 J		< 0.36 U		10	51
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-8-10	9/4/2019	857.92	8 - 10 ft	180-95165-3	Not Excavated	< 0.016 U	11	670	0.78 J	< 0.12 U	82 J		< 0.37 U		8.8	33
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-10-12	8/30/2019	858.28	10 - 12 ft	180-95047-2	Not Excavated	< 0.014 U	14	680	1.2	< 0.11 U	110 J		< 0.32 U		8.8	49
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-12-14	8/30/2019	858.28	12 - 14 ft	180-95047-2	Not Excavated	< 0.013 U	13	620	0.76 J	< 0.11 U	79 J		< 0.34 U		9.4	67
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-14-16	8/30/2019	858.28	14 - 16 ft	180-95047-2	Not Excavated	< 0.015 U	12	590	< 0.53 U	< 0.11 U	86 J		< 0.33 U		7.5	36
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-2-4	8/30/2019	858.28	2 - 4 ft	180-95047-1	Not Excavated	0.032 J	18	780	< 0.61 U	< 0.12 U	60 J		< 0.38 U		16	59
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-4-6	8/30/2019	858.28	4 - 6 ft	180-95047-1	Not Excavated	< 0.015 U	14	710	< 0.57 U	< 0.12 U	44 J		< 0.36 U		11	51
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-6-8	8/30/2019	858.28	6 - 8 ft	180-95047-1	Not Excavated	< 0.015 U	12	690	0.95 J	< 0.12 U	110 J		< 0.35 U		9.1	41
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-8-10	8/30/2019	858.28	8 - 10 ft	180-95047-1	Not Excavated	< 0.016 U	13	710	0.62 J	< 0.11 U	100 J		< 0.32 U		10	43
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-2-4	8/29/2019	858.27	2 - 4 ft	180-95006-2	Not Excavated	0.031 J	14	610	< 0.59 U	< 0.12 U	89 J		< 0.37 U		14	150

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-4-6	8/29/2019	858.27	4 - 6 ft	180-95006-2	Not Excavated	8300	< 0.37 U	8	60	0.41 J	0.1 J	1100	12		7.9	27	18000	14	2100	760
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-10-12	8/29/2019	858.27	10 - 12 ft	180-95006-2	Not Excavated	5600	< 0.36 U	6.2	38	0.23 J	0.13 J	38000	9.8		4.9 J	18	13000	7	14000	460
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-12-14	8/29/2019	858.27	12 - 14 ft	180-95006-2	Not Excavated	6600	< 0.37 U	5.2	51	0.24 J	0.11 J	41000	10		5.5	18	15000	7.3	8600	460
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	6000	< 0.37 U	6	47	0.24 J	0.13 J	30000	9.4		5.4	23	14000	9.6	12000	510
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-6-8	8/29/2019	858.27	6 - 8 ft	180-95006-2	Not Excavated	6400	0.39 J	6.7	44	0.26 J	0.11 J	3300	9		5.5	16	16000	9.5	2300	580
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-8-10	8/29/2019	858.27	8 - 10 ft	180-95006-2	Not Excavated	5000	< 0.37 U	5.8	29	0.22 J	0.13 J	31000	6.8		4.7 J	16	13000	6.4	5800 J	380
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-10-12	8/30/2019	858.38	10 - 12 ft	180-95050-1	Not Excavated	4000	< 0.38 U	3.2	54	0.15 J	0.062 J	35000	6.3		3.6 J	13	10000	4.4	5200	240
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-12-14	8/30/2019	858.38	12 - 14 ft	180-95050-1	Not Excavated	4500	< 0.38 U	4.5	43	0.22 J	0.11 J	43000	9.7		5.3 J	16	13000	5.4	7300	320
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16	8/30/2019	858.38	14 - 16 ft	180-95050-1	Not Excavated	4200	< 0.37 U	4.3	53	0.16 J	0.079 J	32000	5.5		4.2 J	15	10000	6	5700	310
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-2-4	8/30/2019	858.38	2 - 4 ft	180-95050-1	Not Excavated	8200	1.2	18	140	0.5	0.31 J	5600	16		5.5 J	34	34000	51	1200	320
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-4-6	8/30/2019	858.38	4 - 6 ft	180-95050-1	Not Excavated	7600	0.51 J	7.1	48	0.37 J	0.13 J	790	10		7.2	21	19000	12	2100	810
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-6-8	8/30/2019	858.38	6 - 8 ft	180-95050-1	Not Excavated	5100	< 0.37 U	5.4	30	0.21 J	0.13 J	13000 J	7.4		5.5	16	14000	6.8	3300	520
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-8-10	8/30/2019	858.38	8 - 10 ft	180-95050-1	Not Excavated	4200	< 0.37 U	5.1	29	0.2 J	0.094 J	18000	5.5		5.1 J	15	11000	6.1	3100	260
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated	8700	< 0.39 U	8.1	85	0.43 J	0.17 J	10000	12		6.7	23	16000	33	3000	420
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated	9400 J	< 0.4 U	7.3	73	0.42 J	0.13 J	10000 J	12		7.1 J	21	17000	23	2700 J	290
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-2-4	12/19/2019	856.23	2 - 4 ft	180-100363-2	Not Excavated	9300	< 0.35 U	6.9	80	0.37 J	0.15 J	1100	10		5.4	17	14000	17	1900	400
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-4-6	12/19/2019	856.23	4 - 6 ft	180-100363-2	Not Excavated	10000	< 0.39 U	6.4	65	0.41 J	0.072 J	180 J	13		8.2	20	19000	11	3000	280
Northern Athletic Field	SSHS-B3243	SSHS-B3243-SUB-2-4	12/19/2019	856.13	2 - 4 ft	180-100363-2	Not Excavated	11000	< 0.36 U	9.1	67	0.47	0.13 J	2500	14		9.5	26	24000	26	3500	440
Northern Athletic Field	SSHS-B3243	SSHS-B3243-SUB-4-6	12/19/2019	856.13	4 - 6 ft	180-100363-2	Not Excavated	11000	< 0.37 U	7.8	91	0.45	0.095 J	1500	13		7.7	18	19000	15	2600	440
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-6-8	12/19/2019	857.74	6 - 8 ft	180-100363-3	Not Excavated	6100	< 0.36 UJ	5.8	37	0.27 J	0.23 J	6100	9.2		5.9	17	15000	13	3200	410
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-8-10	12/19/2019	857.74	8 - 10 ft	180-100363-3	Not Excavated	4800	< 0.31 U	4.1	30	0.19 J	0.11 J	29000	6.4		4.3 J	13	11000	5.6	5700	330
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-6-8	12/19/2019	857.37	6 - 8 ft	180-100363-3	Excavated	5400	< 0.35 U	4.9	34	0.24 J	0.17 J	21000	7.6		5.2	15	13000	9	5000	360
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-8-10	12/19/2019	857.37	8 - 10 ft	180-100363-3	Not Excavated	5000	< 0.32 U	5.2	33	0.24 J	0.13 J	18000	9.2		5	16	12000	7.1	5800	370
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-6-8	12/19/2019	858.13	6 - 8 ft	180-100363-3	Excavated	6800	< 0.35 U	5.8	51	0.31 J	0.14 J	4400	11		6	21	16000	13	3100	600
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-8-10	12/19/2019	858.13	8 - 10 ft	180-100363-3	Not Excavated	4000	< 0.35 U	3.7	35	0.16 J	0.13 J	60000	5.4		3.8 J	11	9700	6.1	22000	390
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-6-8	12/19/2019	857.57	6 - 8 ft	180-100363-3	Excavated	5300	< 0.34 U	4.9	32	0.24 J	0.42 J	45000	21		6.1	23	14000	8.6	15000	570
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-8-10	12/19/2019	857.57	8 - 10 ft	180-100363-3	Excavated	5200	< 0.34 U	4.7	31	0.21 J	0.13 J	26000	130		5.2	19	15000	14	5600	360
Northern Athletic Field	SSHS-B3247A	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	10 - 12 ft	180-116462-1	Not Excavated	6700	< 0.34 U	4.7	47	0.23 J	0.099 J	41000	8.9		6	20	16000	15	10000	410
Northern Athletic Field	SSHS-B3247A	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	12 - 14 ft	180-116462-3	Not Excavated	6600	< 0.34 U	4.5	53	0.23 J	0.16 J	90000	8		5.9	18	14000	5.8	8700	400
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-2-4	12/19/2019	856.34	2 - 4 ft	180-100363-1	Not Excavated	9700	< 0.39 UJ	6.2	80	0.38 J	0.11 J	560 J	11		5.9	17	16000	11	2100	420
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	5900	< 0.37 U	4.9	66	0.26 J	0.14 J	17000	9.5		5.7	19	15000	15	4500	430
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	6600	< 0.35 U	5.0	67	0.27 J	0.11 J	16000	9.1		5.9	18	16000	16	5700	420
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	5600	< 0.35 UT	4.4	41	0.23 J	0.13 J	28000 T	8.7		4.9 J	19	13000	9.6	6500 T	330
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	4 - 6 ft	180-100380-1	Not Excavated	11000	< 0.39 U	7.9	46	0.5	0.1 J	980	16		8.7	49	23000	15	2800	390
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	856.44	2 - 4 ft	180-100380-1	Excavated	5900	< 0.34 U	5	63 J	0.27 J	0.12 J	1600 J	33		5.1 J	100 J	22000	48	1300	310
Northern Athletic Field	SSHS-B3277	SSHS-B3277-SUB-4-6	12/18/2019	856.31	4 - 6 ft	180-100380-2	Not Excavated	9600	1.8	5.9	85	0.64	0.77	8800	11		7.6	440	17000	81	1400	420
Northern Athletic Field	SSHS-B3277	SSHS-B3277-SUB-2-4	12/18/2019	856.31	2 - 4 ft	180-100380-2	Excavated	5400	0.91 J	9.3	93	0.17 J	0.1 J	1400	11		3.1 J	320	45000	95	1300	110
Northern Athletic Field	SSHS-B3279	SSHS-B3279-SUB-2-4	12/18/2019	856.57	2 - 4 ft	180-100380-1	Not Excavated	5600	< 0.39 U	5.9	86	0.35 J	0.17 J	1700	8.2		4.7 J	22	14000	28	1400	400
Northern Athletic Field	SSHS-B3279	SSHS-B3279-SUB-4-6	12/18/2019	856.57	4 - 6 ft	180-100380-1	Not Excavated	6600	< 0.35 U	4.6	50	0.35 J	0.098 J	820	7.8		4.9 J	16	13000	11	1400	370
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	4 - 6 ft	180-100380-2	Not Excavated	11000	< 0.41 U	6.2	58	0.45 J	0.1 J	1000	13		6.9	26	18000	20	2300	320
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	856.56	2 - 4 ft	180-100380-2	Excavated	6200	< 0.35 UJ	7	83	0.38 J	0.32 J	2000 J	9.5		6	86 J-	14000	160 J-	1300	330
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	856.97	2 - 4 ft	180-100148-4	Excavated	9500	0.51 J	8.2	160	0.57	0.23 J	19000	12		6.9	36	19000	110	2600	400
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-2-4	12/17/2019	857.04	2 - 4 ft	180-100148-3	Excavated	9900	< 0.32 UJ	7.1	170	0.4	0.27 J	46000	13		6.5	26	18000	63	6300	420
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-2-4	12/17/2019	856.64	2 - 4 ft	180-100148-4	Excavated	6500	0.27 J	4.5 J-	41	0.28 J	0.071 J	6500 J	8.1 J-		5 J-	14 J-	13000	15	2700 J-	220
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-2-4	12/16/2019	856.96	2 - 4 ft	180-100148-2	Excavated	7100	< 0.36 U	7	78	0.35 J	0.15 J	4200	9.4		6.7	32	17000	11	3400	1200
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-4-6	12/16/2019	856.96	4 - 6 ft	180-100148-2	Excavated	11000	0.42 J	8.1	47	0.55	0.095 J	1100	12		13	27	22000	14	2500	570
Northern Athletic Field	SSHS-B3313	SSHS-B3313-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-3	Excavated	7400	< 0.31 UJ	5.8	100	0.41	0.15 J	17000	9.9		5.7	22	16000	37	2300	360
Northern Athletic Field	SSHS-B3313	SSHS-B3313-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-3	Excavated	8900	< 0.26 UJ	5.2	80	0.47	0.26 J	43000	12		5.5	24	15000	21	3500	300
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-2	Excavated	5900	0.87 J-	7.8	74	0.41 J	0.13 J	10000 J-	13		5.8	36	18000	100 J-	1800	350
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-2	Excavated	9900	0.75 J	8.5	76	0.47 J	0.12 J	2200	12		10	32	18000	49	2300	420
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-2-4	12/17/2019	856.17	2 - 4 ft	180-100148-4	Excavated	12000	< 0.28 U	6.2	110	0.49	0.066 J	3800	12		7.2	15	17000	18	2700	520
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-2-4	12/16/2019	856.62	2 - 4 ft	180-100148-2	Excavated	7300	< 0.37 U	6.8	62	0.38 J	0.14 J	7800	9.3		5.7	22	16000	32	2100	500
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-4-6	12/16/2019	856.62	4 - 6 ft	180-100148-2	Excavated	8800	0.42 J	8.9	73	0.46 J	0.12 J	2000	10		6.9	19	17000	24	2100	510
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-2-4	12/16/2019	856.86	2 - 4 ft	180-100148-3	Excavated	9000	< 0.33 UJ	5.6	97	0.42	0.12 J	1900	11		7.4	11	16000	11	2700	470
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-4-6	12/16/2019	856.86	4 - 6 ft	180-100148-3	Excavated	5600	< 0.26 UJ	4.6	61	0.29 J	0.15 J	11000	8.9		4.6	26	13000	45	2200	250
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-2-4	12/16/2019	856.76	2 - 4 ft	180-100148-3	Excavated	6600	< 0.27 UJ	11	170	0.33	0.67	22000	300		7.1	560	28000	140	2500	2000
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-4-6	12/16/2019	856.76	4 - 6 ft	180-100148-3	Excavated	6400	< 0.33 UJ	5.6	83	0.28 J	0.68	16000	33		4.9	120	20000	75	2600	360
Northern Athletic Field	SSHS-B3320	SSHS-B3320-SUB-2-4	12/16/2019	856.83	2 - 4 ft	180-100148-2	Excavated	5100	< 0.37 U	4.5	53	0.23 J	0.13 J	14000	12		4.2 J	24	12000	23	2600	270
Northern Athletic Field	SSHS-B3320	SSHS-B3320-SUB-4-6	12/16/2019	856.83	4 - 6 ft	180-100148-2	Excavated	12000	0.54 J	9.8	56	0.61	0.076 J	1400	14		11	24	23000	16	3100	460
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-2-4	12/16/2019	855.76	2 - 4 ft	180-100148-2	Excavated	10000	< 0.41 U	4.6	83	0.44 J	0.077 J	4200	12		6.9	16	18000	11	2400	630
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-2-4	12/16/2019	856.21	2 - 4 ft	180-100148-3	Excavated	8000	< 0.26 UJ	5.9	44	0.33	0.06 J	1300	9		5.3	14	12000	22	1800	240
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-2-4	12/16/2019	856.48	2 - 4 ft	180-100148-3	Excavated	8900	< 0.26 UJ	7.4	79	0.47	0.18 J	16000	12		7.2	33	19000	590	3800	390
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-2-4	12/16/2019	855.88	2 - 4 ft	180-100148-3	Excavated	6600	< 0.27 UJ	5.6	35	0.27 J	0.098 J	19000	7.8		5	15	13000	16	2800	340
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated	6200	< 0.36 U	4.7	56	0.25 J	0.12 J	22000	8.1		5.3	21	14000	11	8300	500
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	4700	< 0.34 U	3.8	31	0.18 J	0.14 J	58000	7.1		4 J	19	11000	5.4	6600	410
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated	8300	< 0.35 U	6.2	99	0.38 J	0.12 J	7400	9.6		6.3	21	16000	16	4200	590
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated	7500	< 0.36 U	6.5	79	0.33 J	0.13 J	3600	11		6.2	23	16000	11	2800	570
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	6200	< 0.35 U	4.3	53	0.25 J	0.13 J	47000	11		5.6	20	14000	8.5	19000	360
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	6200	< 0.71 U	4.5	54	0.22 J	0.14 J	80000	12		5.7	22	14000	8.3	18000	520
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	6800	< 0.35 UT	4.9	57	0.27 J	0.17 J	36000	12		5.9	31	17000	8.1	11000	650
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated	6600	< 0.35 U	4.7	47	0.24 J	0.17 J	47000	28		5.7	86	15000	13	5600	450
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	7/28/2020	855.34	2 - 4 ft	180-108872-2	Excavated	7500	0.72 J	9.3	83	0.38	0.23 J	14000	38		7.9	120	57000	230	2400	710
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	8/31/2020	855.34	2 - 4 ft	180-110264-1	Excavated								80	0.31 J						
Football Field	SSHS-B3457	SSHS-B3457-SUB-2-4	7/28/2020	855.82	2 - 4 ft	180-108872-2	Excavated	8600	1.7	14	140	0.52	0.32 J	5200	19		9.6	110	24000	140	2100	1100

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-4-6	8/29/2019	858.27	4 - 6 ft	180-95006-2	Not Excavated	0.022 J	15	730	< 0.56 U	< 0.12 U	49 J		< 0.35 U		17	66
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-10-12	8/29/2019	858.27	10 - 12 ft	180-95006-2	Not Excavated	< 0.015 U	12	720	0.62 J	< 0.11 U	82 J		< 0.34 U		9.8	48
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-12-14	8/29/2019	858.27	12 - 14 ft	180-95006-2	Not Excavated	< 0.014 U	14	740	0.85 J	< 0.11 U	93 J		< 0.35 U		11	49
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	< 0.014 U	13	710	< 0.56 U	< 0.11 U	83 J		< 0.35 U		9.9	52
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-6-8	8/29/2019	858.27	6 - 8 ft	180-95006-2	Not Excavated	< 0.018 U	13	640	< 0.55 U	< 0.11 U	40 J		< 0.34 U		10	50
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-8-10	8/29/2019	858.27	8 - 10 ft	180-95006-2	Not Excavated	< 0.016 U	12	570	< 0.57 UJ	< 0.12 U	58 J		< 0.35 U		9	46
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-10-12	8/30/2019	858.38	10 - 12 ft	180-95050-1	Not Excavated	< 0.016 U	9	420 J	0.81 J	< 0.12 U	53 J		< 0.36 U		6.2	31
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-12-14	8/30/2019	858.38	12 - 14 ft	180-95050-1	Not Excavated	< 0.015 U	25	510 J	0.68 J	< 0.12 U	67 J		< 0.36 U		8.2	47
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16	8/30/2019	858.38	14 - 16 ft	180-95050-1	Not Excavated	< 0.015 U	11	420 J	< 0.57 U	< 0.12 U	54 J		< 0.35 U		6.4	42
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-2-4	8/30/2019	858.38	2 - 4 ft	180-95050-1	Not Excavated	0.062	16	470 J	1.8	< 0.12 U	160 J		< 0.38 U		25	57
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-4-6	8/30/2019	858.38	4 - 6 ft	180-95050-1	Not Excavated	0.026 J	16	670	< 0.57 U	< 0.12 U	42 J		< 0.36 U		13	84
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-6-8	8/30/2019	858.38	6 - 8 ft	180-95050-1	Not Excavated	< 0.016 U	13	510 J	< 0.56 U	< 0.11 U	79 J		< 0.35 U		8.2	42
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-8-10	8/30/2019	858.38	8 - 10 ft	180-95050-1	Not Excavated	< 0.017 U	11	460 J	< 0.56 U	< 0.11 U	41 J		< 0.35 U		7.3	39
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated	0.073	22	740	0.9 J	< 0.12 U	71 J		< 0.37 U		13	68
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated	0.075	19	770 J	< 0.61 UJ	< 0.12 U	73 J		< 0.38 U		14	60
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-2-4	12/19/2019	856.23	2 - 4 ft	180-100363-2	Not Excavated	0.051	13	490 J	0.66 J	< 0.11 U	< 62 U		< 0.33 U		14	49
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-4-6	12/19/2019	856.23	4 - 6 ft	180-100363-2	Not Excavated	< 0.025 U	19	770	< 0.59 U	< 0.12 U	< 69 U		< 0.37 U		15	52
Northern Athletic Field	SSHS-B3243	SSHS-B3243-SUB-2-4	12/19/2019	856.13	2 - 4 ft	180-100363-2	Not Excavated	0.045	23	720	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		15	87
Northern Athletic Field	SSHS-B3243	SSHS-B3243-SUB-4-6	12/19/2019	856.13	4 - 6 ft	180-100363-2	Not Excavated	0.029 J	18	930	< 0.56 U	< 0.11 U	< 66 U		0.35 J		17	52
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-6-8	12/19/2019	857.74	6 - 8 ft	180-100363-3	Not Excavated	< 0.022 U	13	610	< 0.54 U	< 0.11 U	92 J		< 0.34 U		12	56
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-8-10	12/19/2019	857.74	8 - 10 ft	180-100363-3	Not Excavated	< 0.023 U	11	580	< 0.47 U	< 0.097 U	70 J		< 0.3 U		7.7	35
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-6-8	12/19/2019	857.37	6 - 8 ft	180-100363-3	Excavated	< 0.025 U	13	560	< 0.53 U	< 0.11 U	66 J		< 0.33 U		8.3	45
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-8-10	12/19/2019	857.37	8 - 10 ft	180-100363-3	Not Excavated	< 0.022 U	12	660	< 0.48 U	< 0.098 U	95 J		< 0.3 U		8.4	45
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-6-8	12/19/2019	858.13	6 - 8 ft	180-100363-3	Excavated	0.029 J	15	770	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		11	80
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-8-10	12/19/2019	858.13	8 - 10 ft	180-100363-3	Not Excavated	< 0.023 U	8.9	650	1.1	< 0.11 U	92 J		< 0.33 U		6.4	33
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-6-8	12/19/2019	857.57	6 - 8 ft	180-100363-3	Excavated	< 0.022 U	15	700	0.85 J	< 0.1 U	76 J		< 0.32 U		11	45
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-8-10	12/19/2019	857.57	8 - 10 ft	180-100363-3	Excavated	< 0.023 U	22	670	< 0.51 U	< 0.1 U	64 J		< 0.32 U		15	50
Northern Athletic Field	SSHS-B3247A	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	10 - 12 ft	180-116462-1	Not Excavated	< 0.023 U	15	800	< 0.51 U	< 0.1 U	70 J		< 0.32 U		12	47
Northern Athletic Field	SSHS-B3247A	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	12 - 14 ft	180-116462-3	Not Excavated	< 0.022 U	14	880	0.71 J	< 0.11 U	340 J		< 0.32 U		9.8	45
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-2-4	12/19/2019	856.34	2 - 4 ft	180-100363-1	Not Excavated	0.034 J	14	560 J	< 0.6 U	< 0.12 U	< 70 U		< 0.37 U		13	59
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	0.025 J	13	820	< 0.56 U	< 0.11 U	90 J		< 0.35 U		12	57
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	0.032	15	910	< 0.53 U	< 0.11 U	74 J		< 0.33 U		13	59
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.022 U	13	790	< 0.53 U	< 0.11 U	84 J		< 0.33 U		9.8	46
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	4 - 6 ft	180-100380-1	Not Excavated	< 0.026 UJ	43	800	< 0.59 U	< 0.12 U	< 69 U		0.37 J		15	62
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	856.44	2 - 4 ft	180-100380-1	Excavated	0.062	100 J	400 J	< 0.51 U	< 0.1 U	67 J		< 0.32 UJ		8.8	45
Northern Athletic Field	SSHS-B3277	SSHS-B3277-SUB-4-6	12/18/2019	856.31	4 - 6 ft	180-100380-2	Not Excavated	0.082	57	440 J	1 J	< 0.11 U	290 J		< 0.35 U		10	200
Northern Athletic Field	SSHS-B3277	SSHS-B3277-SUB-2-4	12/18/2019	856.31	2 - 4 ft	180-100380-2	Excavated	0.25	37	940	0.77 J	< 0.11 U	2100		0.54 J		13	77
Northern Athletic Field	SSHS-B3279	SSHS-B3279-SUB-2-4	12/18/2019	856.57	2 - 4 ft	180-100380-1	Not Excavated	0.083	12	540 J	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U		11	51
Northern Athletic Field	SSHS-B3279	SSHS-B3279-SUB-4-6	12/18/2019	856.57	4 - 6 ft	180-100380-1	Not Excavated	< 0.026 U	11	490 J	< 0.53 U	< 0.11 U	450 J		< 0.33 U		10	34
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	4 - 6 ft	180-100380-2	Not Excavated	0.029 J	17	680	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U		16	56
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	856.56	2 - 4 ft	180-100380-2	Excavated	0.099	23	490 J	0.74 J	< 0.11 U	110 J		< 0.33 U		12	76 J+
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	856.97	2 - 4 ft	180-100148-4	Excavated	0.73 J	22	940	0.87	< 0.079 U	160 J		< 0.24 U		17	96
Northern Athletic Field	SSHS-B3305	SSHS-B3305-SUB-2-4	12/17/2019	857.04	2 - 4 ft	180-100148-3	Excavated	0.15	18	1000	1	< 0.098 U	130 J		0.31 J		15	130
Northern Athletic Field	SSHS-B3310	SSHS-B3310-SUB-2-4	12/17/2019	856.64	2 - 4 ft	180-100148-4	Excavated	0.16	15 J-	440 J-	0.4 J	< 0.075 UJ	48 J		< 0.23 UJ		9.8	42
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-2-4	12/16/2019	856.96	2 - 4 ft	180-100148-2	Excavated	< 0.024 U	17	610	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U		12	67
Northern Athletic Field	SSHS-B3312	SSHS-B3312-SUB-4-6	12/16/2019	856.96	4 - 6 ft	180-100148-2	Excavated	0.028 J	21	890	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		18	63
Northern Athletic Field	SSHS-B3313	SSHS-B3313-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-3	Excavated	8.9	15	970	< 0.47 U	< 0.095 U	79 J		0.34 J		13	68
Northern Athletic Field	SSHS-B3313	SSHS-B3313-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-3	Excavated	2	15	960	0.9	< 0.079 U	140 J		< 0.24 U		14	85
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-2	Excavated	0.59 J-	15	770	1.2	1.6	120 J		< 0.35 U		14	72 J
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-2	Excavated	0.21	15	700	< 0.63 U	< 0.13 U	78 J		< 0.39 U		16	71
Northern Athletic Field	SSHS-B3316	SSHS-B3316-SUB-2-4	12/17/2019	856.17	2 - 4 ft	180-100148-4	Excavated	0.043	15	820	< 0.42 U	< 0.086 U	76 J		0.34 J		17	48
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-2-4	12/16/2019	856.62	2 - 4 ft	180-100148-2	Excavated	0.32	130	650	< 0.56 U	< 0.11 U	< 66 U		< 0.35 U		12	57
Northern Athletic Field	SSHS-B3317	SSHS-B3317-SUB-4-6	12/16/2019	856.62	4 - 6 ft	180-100148-2	Excavated	0.099	22	710	< 0.61 U	< 0.13 U	< 72 U		< 0.38 U		14	63
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-2-4	12/16/2019	856.86	2 - 4 ft	180-100148-3	Excavated	0.077	16	1100	< 0.5 U	< 0.1 U	< 59 U		0.34 J		12	46
Northern Athletic Field	SSHS-B3318	SSHS-B3318-SUB-4-6	12/16/2019	856.86	4 - 6 ft	180-100148-3	Excavated	1.6	34	660	0.4 J	< 0.079 U	65 J		0.33 J		11	62
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-2-4	12/16/2019	856.76	2 - 4 ft	180-100148-3	Excavated	0.24 J	68	820	1.1 J	< 0.17 U	87 J		< 0.52 U		15	210
Northern Athletic Field	SSHS-B3319	SSHS-B3319-SUB-4-6	12/16/2019	856.76	4 - 6 ft	180-100148-3	Excavated	0.051	24	910	< 0.5 U	< 0.1 U	80 J		0.53 J		11	290
Northern Athletic Field	SSHS-B3320	SSHS-B3320-SUB-2-4	12/16/2019	856.83	2 - 4 ft	180-100148-2	Excavated	0.73	11	470 J	< 0.56 U	1.1	< 66 U		< 0.35 U		10	52
Northern Athletic Field	SSHS-B3320	SSHS-B3320-SUB-4-6	12/16/2019	856.83	4 - 6 ft	180-100148-2	Excavated	0.096	21	920	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U		18	69
Northern Athletic Field	SSHS-B3321	SSHS-B3321-SUB-2-4	12/16/2019	855.76	2 - 4 ft	180-100148-2	Excavated	0.044	16	580 J	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U		14	51
Northern Athletic Field	SSHS-B3322	SSHS-B3322-SUB-2-4	12/16/2019	856.21	2 - 4 ft	180-100148-3	Excavated	0.17	12	740	< 0.39 U	< 0.08 U	< 46 U		0.27 J		12	42
Northern Athletic Field	SSHS-B3323	SSHS-B3323-SUB-2-4	12/16/2019	856.48	2 - 4 ft	180-100148-3	Excavated	0.87	31	840	0.58 J	< 0.081 U	80 J		0.3 J		16	89
Northern Athletic Field	SSHS-B3324	SSHS-B3324-SUB-2-4	12/16/2019	855.88	2 - 4 ft	180-100148-3	Excavated	0.046	11	870	< 0.42 U	< 0.085 U	57 J		< 0.26 U		11	44
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated	< 0.023 U	13	570	< 0.54 U	< 0.11 U	66 J		< 0.34 U		9.6	69
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	< 0.026 U	12	530	1.1	< 0.11 U	75 J		< 0.32 U		7.6	66
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated	0.037	14	700	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		13	75
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated	0.032 J	15	720	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		12	86
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.021 U	15	800	0.57 J	< 0.11 U	99 J		< 0.33 U		9.8	95
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.021 U	15	890	1.0	< 0.11 U	110 J		< 0.33 U		11	78
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.023 U	16	810	< 0.53 U	< 0.11 U	84 J		< 0.33 U		12	64 T
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated	< 0.021 U	16	950	0.99 J	< 0.11 U	110 J		< 0.33 U		12	93
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	7/28/2020	855.34	2 - 4 ft	180-108872-2	Excavated	0.12	230	570	1.2	< 0.089 U	62 J		< 0.27 U		15	91
Football Field	SSHS-B3456	SSHS-B3456-SUB-2-4	8/31/2020	855.34	2 - 4 ft	180-110264-1	Excavated											
Football Field	SSHS-B3457	SSHS-B3457-SUB-2-4	7/28/2020	855.82	2 - 4 ft	180-108872-2	Excavated	0.42	48	540	0.84	< 0.077 U	80 J		< 0.24 U		18	150

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3458	DUP10	7/28/2020	856.14	2 - 4 ft	180-108872-2	Excavated	9600	0.89 J	25 J	89	0.35	0.069 J	4600 J	11		6.9	18	15000	50	2800	550
Football Field	SSHS-B3458	SSHS-B3458-SUB-2-4	7/28/2020	856.14	2 - 4 ft	180-108872-2	Excavated	7200	< 0.32 UJ	11 J	60	0.29 J	0.1 J	15000 J	10		5.3	25	15000	46	3100	440
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated	8300	0.58 J	7.9	86	0.4	0.18 J	9300	23		7.6	160	25000	75	4100	400
Football Field	SSHS-B3459	SSHS-B3459-SUB-4-6	7/27/2020	856.30	4 - 6 ft	180-108826-2	Excavated	9800	< 0.77 U	6	53	0.41 J	0.69	36000	19		8.1	45	22000	2900	6900	410
Football Field	SSHS-B3459	SSHS-B3459-SUB-10-12	7/27/2020	856.30	10 - 12 ft	180-108826-2	Not Excavated	8000	< 0.3 U	5.3	49	0.32 J	0.29 J	26000	15		7	31	18000	14	6400	380
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	8400	< 0.22 U	6.4	45	0.32	0.18 J	37000	26	< 0.22 U	8.4	29	19000	12	6900	350
Football Field	SSHS-B3459	SSHS-B3459-SUB-6-8	7/27/2020	856.30	6 - 8 ft	180-108826-2	Not Excavated	7800	< 0.38 U	5.9	57	0.35 J	0.2 J	21000	15		7.1	48	19000	26	4200	410
Football Field	SSHS-B3459	SSHS-B3459-SUB-8-10	7/27/2020	856.30	8 - 10 ft	180-108826-2	Not Excavated	8100	< 0.24 U	4.6	63	0.3	0.17 J	20000	15		7.2	34	18000	15	5100	420
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	8/31/2020	856.30	12 - 14 ft	180-110264-1	Not Excavated								7.2	< 0.23 U						
Football Field	SSHS-B3460	SSHS-B3460-SUB-2-4	7/28/2020	855.83	2 - 4 ft	180-108872-2	Excavated	7800	1.8	8.1	38	0.47	0.064 J	1600	10		7.5	31	21000	42	1900	330
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated	9000	1.2 J	7.6	110	0.4	0.24 J	8500 J+	13		7.1	74 J-	22000	82	2900	480
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	4900	< 0.29 U	4.2	49	0.2 J	0.11 J	37000	7.7		4.9	19	12000	12	9200	360
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	4800	< 0.3 U	3.7	47	0.19 J	0.12 J	27000	8.1		4.2 J	23	12000	16	7600	320
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	7400	1.8	10	200	0.39	0.35 J	12000	29		8.1	88	40000	100	2500	520
Football Field	SSHS-B3461	SSHS-B3461-SUB-6-8	7/27/2020	856.51	6 - 8 ft	180-108826-2	Not Excavated	8200	0.69 J	5.7	99	0.33 J	0.17 J	34000	15		6.9	44	20000	42	5300	450
Football Field	SSHS-B3461	SSHS-B3461-SUB-8-10	7/27/2020	856.51	8 - 10 ft	180-108826-2	Not Excavated	5300	0.48 J	5.1	44	0.23 J	0.09 J	17000	8.8		5.1	18	13000	17	9600	360
Football Field	SSHS-B3462	SSHS-B3462-SUB-2-4	7/28/2020	855.77	2 - 4 ft	180-108872-2	Excavated	9400	< 0.3 U	7.4	120	0.36	0.15 J	53000	14		5.6	28	24000	250	8200	510
Football Field	SSHS-B3463	SSHS-B3463-SUB-2-4	7/28/2020	856.64	2 - 4 ft	180-108872-2	Excavated	7900	< 0.23 UJ	7.6	120 J	0.35	0.22 J	13000	14 J-		6.9	120 J	22000	100 J-	3200	400
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	8500	< 0.31 U	6.7	82	0.35 J	0.23 J	23000	15		6.7	39	18000	59	5200	440
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	7900	< 0.29 U	6.6	61	0.3 J	0.2 J	25000	15		7.1	48	16000	30	4400	750
Football Field	SSHS-B3464	SSHS-B3464-SUB-6-8	7/27/2020	856.28	6 - 8 ft	180-108826-2	Not Excavated	6800	< 0.33 U	6.4	59	0.31 J	0.22 J	17000	22		5.5	40	43000	52	2200	420
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	7900	< 0.29 U	6.9	71	0.31 J	0.17 J	19000	20		6	45	17000	35	2800	390
Football Field	SSHS-B3465	DUP12	7/28/2020	855.46	2 - 4 ft	180-108872-2	Excavated	6600	< 0.22 U	5.6	67	0.29	0.14 J	18000	8.7		5.6	62 J	15000	250 J	3400	390
Football Field	SSHS-B3465	SSHS-B3465-SUB-2-4	7/28/2020	855.46	2 - 4 ft	180-108872-2	Excavated	7300	< 0.25 U	6.2	86	0.32	0.16 J	14000	10		5.9	37 J	17000	110 J	3200	370
Football Field	SSHS-B3466	SSHS-B3466-SUB-2-4	7/28/2020	855.76	2 - 4 ft	180-108872-2	Excavated	10000	< 0.29 U	4.4	83	0.47	0.095 J	3600	14		8.1	18	18000	15	2800	360
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated	5600	1.3 J	17 J-	370	0.33	1.2	6400 J	48 J		7.3	850	74000	170	910 J	360
Football Field	SSHS-B3468	DUP13	7/28/2020	855.93	2 - 4 ft	180-108872-2	Excavated	8600	< 0.26 U	6.4	67	0.37	0.12 J	13000	11		7.1	26	18000	22	4200	440
Football Field	SSHS-B3468	SSHS-B3468-SUB-2-4	7/28/2020	855.93	2 - 4 ft	180-108872-2	Excavated	9100	0.47 J	6.4	110	0.39 J	0.16 J	5300	16		7.4	69	23000	89	2800	370
Football Field	SSHS-B3469	SSHS-B3469-SUB-2-4	7/28/2020	855.50	2 - 4 ft	180-108872-2	Excavated	10000	1.1	6.2	120	0.38	0.19 J	22000	14		6.5	45	19000	110	3800	370
Football Field	SSHS-B3470	SSHS-B3470-SUB-2-4	7/28/2020	855.73	2 - 4 ft	180-108872-2	Excavated	9200	< 0.28 U	6	80	0.49	0.14 J	57000	13		5.8	43	17000	28	5600	590 J
Football Field	SSHS-B3471	SSHS-B3471-SUB-2-4	7/28/2020	856.03	2 - 4 ft	180-108872-2	Excavated	7400	< 0.29 U	6	94	0.32 J	0.15 J	8500	13		5.8	38	17000	67	3300	340
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated	9800	3.5	8.3	140	0.44	0.29 J	9700	12		5.8	75	18000	76	2000	470
Football Field	SSHS-B3472	SSHS-B3472-SUB-4-6	7/27/2020	855.50	4 - 6 ft	180-108826-2	Not Excavated	8200	1.6	5.3	61	0.29 J	0.099 J	14000	13		5.4	31	15000	24	2700	330
Football Field	SSHS-B3472	SSHS-B3472-SUB-6-8	7/27/2020	855.50	6 - 8 ft	180-108826-2	Not Excavated	7000	0.96 J	6.4	59	0.32 J	0.08 J	3900 J-	10		5.8	25	15000	22	1900	470
Football Field	SSHS-B3472	SSHS-B3472-SUB-8-10	7/27/2020	855.50	8 - 10 ft	180-108826-2	Not Excavated	4500	0.6 J	4.8	34	0.22 J	0.12 J	3600	6.7		4.7 J	16	11000	9.5	2100	460
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	5600	< 0.3 U	5.9	51	0.23 J	0.12 J	15000	7.8		5.8	19	14000	9.2	6300	580
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	8400	0.4 J	8.4	130	0.34 J	0.6	19000	17		6.5	93	25000	72	4300	390
Football Field	SSHS-B3473	SSHS-B3473-SUB-4-6	7/27/2020	855.34	4 - 6 ft	180-108826-2	Excavated	9000	< 0.33 U	7.8	77	0.4	0.15 J	18000	13		7.5	27	21000	31	3200	390
Football Field	SSHS-B3473	SSHS-B3473-SUB-6-8	7/27/2020	855.34	6 - 8 ft	180-108826-2	Not Excavated	7000	< 0.31 U	5	82	0.29 J	0.052 J	3300	9.3		5.7	16	14000	8.7	1900	340
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	14000	0.7 J	10	290	0.44	0.84	11000	33		7.8	450	24000	120	3000	540
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	6800	< 0.21 U	5.2	78	0.26	0.17 J	69000	12		4.9	31	13000	27	7800	280
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	7400	0.47 J	8.4	58	0.34	0.25 J	11000	14		8	690	22000	140	4200	570
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	7300	0.92	8.4	47	0.35	0.17 J	4000	11		6.6	30	18000	22	2300	350
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	7800	0.67 J	6.8	66	0.32 J	0.16 J	22000	12		5.9	52	17000	55	3000	400
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	9000	0.34 J	5.8	66	0.36 J	0.086 J	860	11		5.9	15	15000	12	1900	390
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	9600	0.54 J	8	60	0.37 J	0.11 J	12000	11		6.8	30	18000	17	5900	460
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	7400	60	11	320	0.42 J	0.89	4500	13		5.3 J	34	17000	710	1700	340
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	8600	0.55 J	6.1	50	0.33 J	0.11 J	1000	10		5.8	17	16000	20	2200	370
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	9100	0.56 J	8.2	57	0.37 J	0.11 J	1000	13		7.1	28	20000	13	2500	520
Football Field	SSHS-B3502	DUP-16	8/31/2020	856.09	4 - 6 ft	180-110264-1	Excavated													56		
Football Field	SSHS-B3502	SSHS-B3502-SUB-4-6	8/31/2020	856.09	4 - 6 ft	180-110264-1	Excavated													65		
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-2-4	1/25/2021	855.86	2 - 4 ft	180-116404-3	Not Excavated	9600	1.2	7.1	86	0.39 J	0.18 J	4900	25	< 0.24 U	8.8	170	25000	52	3000	940
Football Field	SSHS-B3503	SSHS-B3503-SUB-4-6	8/31/2020	856.71	4 - 6 ft	180-110264-1	Not Excavated													7.4		
Football Field	SSHS-B3504	SSHS-B3504-SUB-4-6	8/31/2020	856.71	4 - 6 ft	180-110264-1	Excavated													16		
Northern Athletic Field	SSHS-B3516	SSHS-B3516-SUB-2-4	1/25/2021	856.33	2 - 4 ft	180-116404-1	Not Excavated	5800	0.84 J	12	75	0.42	0.15 J	1400	11		5.6	55	17000	80	1300	300
Northern Athletic Field	SSHS-B3516	SSHS-B3516-SUB-4-6	1/25/2021	856.33	4 - 6 ft	180-116404-3	Not Excavated	10000	0.61 J	7.1	36	0.44	0.064 J	800	11		6.9	20	19000	9	2500	310
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	2 - 4 ft	180-116002-1	Not Excavated	7400	< 0.33 UJ	6.2	43	0.29 J	0.076 J	480	8.3 J		5.4	15	14000	11	1600	470 J
Football Field	SSHS-B3520	SSHS-B3520-SUB-2-4	1/13/2021	856.69	2 - 4 ft	180-115927-1	Excavated	6400	2.1	6.9	180	0.31 J	0.71	17000	27	0.26 J	5.7	350	28000	280	3100	440
Northern Athletic Field	SSHS-B3522A	SSHS-B3522-SUB-8-10	1/14/2021	857.57	8 - 10 ft	180-116002-1	Not Excavated	4700	< 0.28 U	4.2	40	0.18 J	0.12 J	46000	7.2		4.4	17	11000	5.2	8300	390
Northern Athletic Field	SSHS-B3523A	SSHS-B3523-SUB-8-10	1/14/2021	858.01	8 - 10 ft	180-116002-1	Not Excavated	4700	< 0.33 U	4.3	26	0.19 J	0.12 J	24000	7.1		4.7 J	18	12000	5.6	4900	380
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	5700	< 0.68 U	5.3	71	0.22 J	0.21 J	53000	9.5		4.9 J	22	13000	17	9900	530
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	4500	< 0.36 U	4.0	42	0.19 J	0.10 J	26000	6.2		4.2 J	14	12000	5.1	3500 T	310
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	5100	< 0.34 U	4.3	62	0.18 J	0.12 J	75000	7.8		4.8 J	16	12000	5.1	10000	310
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated	3700	< 1.8 U	3.0	32	0.12 J	0.17 J	160000	6.2		4.4 J	14	8900	3.7	5800	280
Football Field	SSHS-B3563	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	14 - 16 ft	180-115999-1	Not Excavated	5800	< 0.37 UJ	4.2	40	0.24 J	0.065 J	32000	11		5.2 J	17	13000 J	6.5	9900	360
Football Field	SSHS-B3566	SSHS-B3566-SUB-12-14	1/12/2021	855.28	12 - 14 ft	180-115861-1	Not Excavated	8400	< 0.36 U	6.5	1000	0.34 J	0.16 J	12000	14		10	34	21000	27	7500	320
Football Field	SSHS-B3566	SSHS-B3566-SUB-14-16	1/12/2021	855.28	14 - 16 ft	180-115861-1	Not Excavated	4800	< 0.34 U	4.5	42	0.19 J	0.099 J	26000	6.4		4.3 J	14	11000	8.4	9200	330
Football Field	SSHS-B3566	SSHS-B3566-SUB-8-10	1/12/2021	855.28	8 - 10 ft	180-115861-1	Excavated	7900	< 0.35 UJ	10	5700	0.39 J	0.22 J	26000	48 J-		6	80	22000	1100 J	8500 J	670
Football Field	SSHS-B3566	SSHS-B3566-SUB-10-12	1/12/2021	855.28	10 - 12 ft	180-115861-1	Excavated	5800	< 0.37 U	4.4	71	0.24 J	0.11 J	26000	6.8		4.9 J	18	13000	8.3	15000	640
Football Field	SSHS-B3567	SSHS-B3567-SUB-12-14	1/12/2021	855.39	12 - 14 ft	180-115861-1	Not Excavated	6400	< 0.36 U	4.5	56	0.25 J	0.099 J	37000	9		5.4	22	14000	8.6	6300	380
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	3800	< 0.35 U	3.6	41	0.16 J	0.074 J	33000	6.1		3.6 J	14	10000	12	13000	450
Football Field	SSHS-B3567	SSHS-B3567-SUB-8-10	1/12/2021	855.39	8 - 10 ft	180-115861-1	Excavated	8000	< 0.36 UJ	6.9	79 J+	0.35 J	0.11 J	21000	15		7	27 J	19000	28 J	5200	430 J
Football Field	SSHS-B3567	SSHS-B3567-SUB-10-12	1/12/2021	855.39	10 - 12 ft	180-115861-1	Excavated	8300	< 0.35 U	6.2	77	0.34 J	0.1 J	19000	11		6.9	24	19000	26	5600	380
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	12000	0.48 J	6.1	110	0.45	0.11 J	1100	13		7.6	13	18000	15	2300	520

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3458	DUP10	7/28/2020	856.14	2 - 4 ft	180-108872-2	Excavated	0.19	17	500	< 0.31 U	< 0.062 U	57 J		< 0.19 U		15	66
Football Field	SSHS-B3458	SSHS-B3458-SUB-2-4	7/28/2020	856.14	2 - 4 ft	180-108872-2	Excavated	0.13	17	490	< 0.48 U	< 0.099 U	57 J		< 0.3 U		13	77
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated	0.071	61	730	1.1	0.11 J	130 J		< 0.2 U		15	110
Football Field	SSHS-B3459	SSHS-B3459-SUB-4-6	7/27/2020	856.30	4 - 6 ft	180-108826-2	Excavated	0.024 J	29	1000	0.85 J	< 0.12 U	120 J		< 0.36 U		14	76
Football Field	SSHS-B3459	SSHS-B3459-SUB-10-12	7/27/2020	856.30	10 - 12 ft	180-108826-2	Not Excavated	0.028 J	22	900	< 0.46 U	< 0.094 U	100 J		< 0.29 U		11	69
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	< 0.022 U	27	810	0.8	< 0.069 U	92 J		< 0.21 U		12	62
Football Field	SSHS-B3459	SSHS-B3459-SUB-6-8	7/27/2020	856.30	6 - 8 ft	180-108826-2	Not Excavated	0.037	23	940	< 0.57 U	< 0.12 U	85 J		< 0.36 U		12	74
Football Field	SSHS-B3459	SSHS-B3459-SUB-8-10	7/27/2020	856.30	8 - 10 ft	180-108826-2	Not Excavated	0.025 J	22	770	0.45 J	< 0.073 U	95 J		< 0.22 U		11	71
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	8/31/2020	856.30	12 - 14 ft	180-110264-1	Not Excavated											
Football Field	SSHS-B3460	SSHS-B3460-SUB-2-4	7/28/2020	855.83	2 - 4 ft	180-108872-2	Excavated	1.4	18	580	< 0.41 U	< 0.084 U	< 48 U		< 0.26 U		14	69
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated	0.08	30	780	< 0.47 U	< 0.097 U	110 J		< 0.3 U		15	140
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	0.022 J	14	640	0.67 J	< 0.09 U	100 J		< 0.27 U		8.1	52
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	0.031 J	13	580	0.66 J	< 0.093 U	84 J		< 0.28 U		8.4	48
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	0.11	43	710	0.94	< 0.094 U	150 J		< 0.29 U		26	170
Football Field	SSHS-B3461	SSHS-B3461-SUB-6-8	7/27/2020	856.51	6 - 8 ft	180-108826-2	Not Excavated	0.062	24	810	0.71 J	< 0.096 U	150 J		< 0.29 U		15	84
Football Field	SSHS-B3461	SSHS-B3461-SUB-8-10	7/27/2020	856.51	8 - 10 ft	180-108826-2	Not Excavated	0.022 J	15	660	< 0.43 U	< 0.087 U	85 J		< 0.27 U		12	46
Football Field	SSHS-B3462	SSHS-B3462-SUB-2-4	7/28/2020	855.77	2 - 4 ft	180-108872-2	Excavated	0.11	15	740	1.3	< 0.093 U	270 J		< 0.28 U		14	59
Football Field	SSHS-B3463	SSHS-B3463-SUB-2-4	7/28/2020	856.64	2 - 4 ft	180-108872-2	Excavated	0.13 J+	55 J-	570	0.62 J	< 0.07 U	100 J		< 0.21 U		14 J-	130
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	0.91	50	840	0.49 J	0.66	130 J		< 0.3 U		13	110
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	0.51	47	870	0.48 J	1.6	140 J		< 0.27 U		13	83
Football Field	SSHS-B3464	SSHS-B3464-SUB-6-8	7/27/2020	856.28	6 - 8 ft	180-108826-2	Not Excavated	1.1	49	740	0.76 J	3.5	110 J		< 0.31 U		14	90
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	0.45	46	810	< 0.44 U	1.3	130 J		< 0.27 U		13	100
Football Field	SSHS-B3465	DUP12	7/28/2020	855.46	2 - 4 ft	180-108872-2	Excavated	0.11	20	510	0.5 J	< 0.067 U	64 J		< 0.2 U		11	70
Football Field	SSHS-B3465	SSHS-B3465-SUB-2-4	7/28/2020	855.46	2 - 4 ft	180-108872-2	Excavated	0.083	23	660	0.42 J	< 0.078 U	69 J		< 0.24 U		13	84
Football Field	SSHS-B3466	SSHS-B3466-SUB-2-4	7/28/2020	855.76	2 - 4 ft	180-108872-2	Excavated	0.085	20	720	< 0.44 U	< 0.09 U	< 51 U		< 0.27 U		15	55
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated	0.23 J	130 J	320 J	1.4	< 0.079 U	110 J		0.26 J		25 J-	1100
Football Field	SSHS-B3468	DUP13	7/28/2020	855.93	2 - 4 ft	180-108872-2	Excavated	0.032 J	22	660	< 0.39 UJ	< 0.079 U	< 45 UJ		< 0.24 U		14	69
Football Field	SSHS-B3468	SSHS-B3468-SUB-2-4	7/28/2020	855.93	2 - 4 ft	180-108872-2	Excavated	0.056	53	680	0.69 J	< 0.1 U	< 60 U		< 0.32 U		15	100
Football Field	SSHS-B3469	SSHS-B3469-SUB-2-4	7/28/2020	855.50	2 - 4 ft	180-108872-2	Excavated	0.1	32	850	0.86	< 0.086 U	100 J		< 0.26 U		17	120
Football Field	SSHS-B3470	SSHS-B3470-SUB-2-4	7/28/2020	855.73	2 - 4 ft	180-108872-2	Excavated	0.16 J	46	700	1.1	< 0.086 U	170 J		< 0.26 U		18	76
Football Field	SSHS-B3471	SSHS-B3471-SUB-2-4	7/28/2020	856.03	2 - 4 ft	180-108872-2	Excavated	0.13	25	630	< 0.45 U	< 0.091 U	63 J		< 0.28 U		13	88
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated	0.039	19	780	0.98	< 0.098 U	1100		< 0.3 U		16	200
Football Field	SSHS-B3472	SSHS-B3472-SUB-4-6	7/27/2020	855.50	4 - 6 ft	180-108826-2	Not Excavated	0.03 J	17	720	< 0.51 U	< 0.1 U	450 J		< 0.31 U		14	87
Football Field	SSHS-B3472	SSHS-B3472-SUB-6-8	7/27/2020	855.50	6 - 8 ft	180-108826-2	Not Excavated	0.023 J	16	670	< 0.59 U	< 0.12 U	530 J		< 0.37 U		12	71 J-
Football Field	SSHS-B3472	SSHS-B3472-SUB-8-10	7/27/2020	855.50	8 - 10 ft	180-108826-2	Not Excavated	0.027 J	12	600	< 0.59 U	< 0.12 U	350 J		< 0.37 U		8.5	46
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	< 0.023 U	15	630	0.52 J	< 0.092 U	330 J		< 0.28 U		9.3	55
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	0.14	57	720	1.1	0.15 J	170 J		< 0.3 U		14	160
Football Field	SSHS-B3473	SSHS-B3473-SUB-4-6	7/27/2020	855.34	4 - 6 ft	180-108826-2	Excavated	0.091	23	890	< 0.5 U	< 0.1 U	120 J		< 0.31 U		14	710
Football Field	SSHS-B3473	SSHS-B3473-SUB-6-8	7/27/2020	855.34	6 - 8 ft	180-108826-2	Not Excavated	0.032	15	700	< 0.48 U	< 0.097 U	< 56 U		< 0.3 U		11	45
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	0.15	84	730	0.73 J	0.16 J	90 J		< 0.27 U		16	250
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	0.036	17	670	0.97	< 0.066 U	110 J		< 0.2 U		13	69
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	0.044	25	680	0.4 J	< 0.079 U	76 J		< 0.24 U		13	200
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	0.043	18	640	0.41 J	< 0.065 U	210 J		< 0.2 U		14	100
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	0.041	33	630	0.7 J	< 0.097 U	200 J		< 0.3 U		13	80
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.023 U	14	610	< 0.49 U	< 0.099 U	< 57 U		< 0.30 U		14	49
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	0.023 J	17	720	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U		15	57
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	0.088	17	620 J	< 0.67 U	0.14 J	< 78 U		< 0.42 U		17	140
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.021 U	15	460 J	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U		14	54
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.022 U	20	840	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U		14	60
Football Field	SSHS-B3502	DUP-16	8/31/2020	856.09	4 - 6 ft	180-110264-1	Excavated											
Football Field	SSHS-B3502	SSHS-B3502-SUB-4-6	8/31/2020	856.09	4 - 6 ft	180-110264-1	Excavated											
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-2-4	1/25/2021	855.86	2 - 4 ft	180-116404-3	Not Excavated	< 0.022 U	74	750	< 0.56 U	< 0.12 U	79 J		< 0.35 U		15	110
Football Field	SSHS-B3503	SSHS-B3503-SUB-4-6	8/31/2020	856.71	4 - 6 ft	180-110264-1	Not Excavated											
Football Field	SSHS-B3504	SSHS-B3504-SUB-4-6	8/31/2020	856.71	4 - 6 ft	180-110264-1	Excavated											
Northern Athletic Field	SSHS-B3516	SSHS-B3516-SUB-2-4	1/25/2021	856.33	2 - 4 ft	180-116404-1	Not Excavated	0.11	29	470 J	0.51 J	< 0.1 U	< 60 U		< 0.32 U		12	77
Northern Athletic Field	SSHS-B3516	SSHS-B3516-SUB-4-6	1/25/2021	856.33	4 - 6 ft	180-116404-3	Not Excavated	< 0.022 U	18	800	< 0.57 U	< 0.12 U	< 66 U		< 0.35 U		15	51 J-
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	2 - 4 ft	180-116002-1	Not Excavated	< 0.023 U	11	430 J	< 0.49 U	< 0.1 U	< 58 U		< 0.31 U		11	47 J+
Northern Athletic Field	SSHS-B3520	SSHS-B3520-SUB-2-4	1/13/2021	856.69	2 - 4 ft	180-115927-1	Excavated	0.096	92	670	0.8 J	< 0.11 U	120 J		< 0.34 U		12	280
Northern Athletic Field	SSHS-B3522A	SSHS-B3522-SUB-8-10	1/14/2021	857.57	8 - 10 ft	180-116002-1	Not Excavated	< 0.021 U	11	610	0.56 J	< 0.087 U	68 J		< 0.26 U		8.1	51
Northern Athletic Field	SSHS-B3523A	SSHS-B3523-SUB-8-10	1/14/2021	858.01	8 - 10 ft	180-116002-1	Not Excavated	< 0.021 U	12	610	< 0.51 U	< 0.1 U	< 59 U		< 0.32 U		9	41
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.022 U	13	780	0.70 J	< 0.10 U	100 J		< 0.32 U		9.3	91
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.022 U	10	570	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		8.1	36
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.019 U	12	680	0.64 J	< 0.10 U	99 J		< 0.32 U		10	41
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated	< 0.021 U	10	500 J	1.2	< 0.11 U	86 J		< 0.34 U		6.3	31
Football Field	SSHS-B3563	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	14 - 16 ft	180-115999-1	Not Excavated	< 0.021 U	14	770	< 0.56 U	< 0.11 U	88 J		< 0.35 U		8.9	49 J-
Football Field	SSHS-B3566	SSHS-B3566-SUB-12-14	1/12/2021	855.28	12 - 14 ft	180-115861-1	Not Excavated	< 0.02 U	140	930	< 0.55 U	< 0.11 U	130 J		< 0.34 U		14	82
Football Field	SSHS-B3566	SSHS-B3566-SUB-14-16	1/12/2021	855.28	14 - 16 ft	180-115861-1	Not Excavated	< 0.022 U	57	720	< 0.52 U	< 0.11 U	100 J		< 0.32 U		7.6	48
Football Field	SSHS-B3566	SSHS-B3566-SUB-8-10	1/12/2021	855.28	8 - 10 ft	180-115861-1	Excavated	0.075	130	1000	0.55 J	< 0.11 U	190 J		< 0.33 U		15	140
Football Field	SSHS-B3566	SSHS-B3566-SUB-10-12	1/12/2021	855.28	10 - 12 ft	180-115861-1	Excavated	< 0.023 U	38	750	< 0.55 U	< 0.11 U	72 J		< 0.35 U		8.9	53
Football Field	SSHS-B3567	SSHS-B3567-SUB-12-14	1/12/2021	855.39	12 - 14 ft	180-115861-1	Not Excavated	< 0.02 U	35	800	< 0.55 U	< 0.11 U	81 J		< 0.34 U		9.7	52
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	< 0.019 U	21	610	< 0.53 U	< 0.11 U	87 J		< 0.33 U		7.4	35
Football Field	SSHS-B3567	SSHS-B3567-SUB-8-10	1/12/2021	855.39	8 - 10 ft	180-115861-1	Excavated	0.022 J	25	850	< 0.54 U	< 0.11 U	83 J		< 0.34 U		12	64 J+
Football Field	SSHS-B3567	SSHS-B3567-SUB-10-12	1/12/2021	855.39	10 - 12 ft	180-115861-1	Excavated	< 0.02 U	23	910	< 0.52 U	< 0.11 U	69 J		< 0.33 U		12	65
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	0.026 J	17	660	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U		17	61

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	8500	0.74 J	9.6	45	0.33 J	0.11 J	8500	10		7.0	29	19000	9.4	3700	510
Northern Athletic Field	SSHS-B3631	SSHS-B3631-SUB-4-6	1/25/2021	856.31	4 - 6 ft	180-116404-3	Not Excavated	11000	0.7 J	7.6	70	0.43	0.11 J	1100	22	< 0.25 U	6.9	42	26000	33	2100	430
Northern Athletic Field	SSHS-B3631	SSHS-B3631-SUB-2-4	1/25/2021	856.31	2 - 4 ft	180-116404-1	Excavated	5900	2.4	18	130	0.5	0.75	4300	110	< 0.25 U	10	460	87000	440	2600	650
Northern Athletic Field	SSHS-B3632	SSHS-B3632-SUB-2-4	1/27/2021	856.69	2 - 4 ft	180-116529-1	Excavated	8200	0.57 J	7	68	0.5	0.16 J	8600	12		6.4	29	17000	67	2800	480
Northern Athletic Field	SSHS-B3632	SSHS-B3632-SUB-4-6	1/27/2021	856.69	4 - 6 ft	180-116529-3	Excavated	12000	0.72 J	5.7	76	0.42 J	0.088 J	3400	13		7.7	13	21000	10	2600	460
Northern Athletic Field	SSHS-B3633	SSHS-B3633-SUB-2-4	1/27/2021	856.94	2 - 4 ft	180-116529-1	Excavated	8200	0.58 J	6.2	96	0.45	0.17 J	11000	13		5.9	31	19000	57	2500	410
Northern Athletic Field	SSHS-B3633	SSHS-B3633-SUB-4-6	1/27/2021	856.94	4 - 6 ft	180-116529-3	Excavated	12000	0.76 J	9.4	100	0.49	0.12 J	4300	14		6.9	21	19000	33	2500	560
Northern Athletic Field	SSHS-B3634	SSHS-B3634-SUB-6-8	1/26/2021	857.44	6 - 8 ft	180-116462-1	Not Excavated	5600	< 0.29 U	5.7	34	0.21 J	0.095 J	25000	9		5.4	19	14000	6.8	6600	490
Northern Athletic Field	SSHS-B3634	SSHS-B3634-SUB-8-10	1/26/2021	857.44	8 - 10 ft	180-116462-3	Not Excavated	4200	< 0.34 U	4.3	31	0.15 J	0.15 J	51000	5.9		3.9 J	18	11000	5.1	9700	430
Northern Athletic Field	SSHS-B3635	SSHS-B3635-SUB-6-8	1/26/2021	857.87	6 - 8 ft	180-116462-1	Not Excavated	6400	0.35 J	5.1	40	0.28 J	0.092 J	1300	8.7		5.6	19	14000	8.3	2000	540
Northern Athletic Field	SSHS-B3635	SSHS-B3635-SUB-8-10	1/26/2021	857.87	8 - 10 ft	180-116462-3	Not Excavated	5600	< 0.35 U	4.4	34	0.21 J	0.11 J	12000	7.4		5.5	17	14000	14	5600	560
Northern Athletic Field	SSHS-B3636	SSHS-B3636-SUB-6-8	1/26/2021	857.79	6 - 8 ft	180-116462-1	Excavated	4500	< 0.31 U	4.5	40	0.19 J	0.13 J	44000	6.7		4.5 J	15	13000	7.3	18000	690
Northern Athletic Field	SSHS-B3636	SSHS-B3636-SUB-8-10	1/26/2021	857.79	8 - 10 ft	180-116462-3	Not Excavated	5200	< 0.33 U	5	36	0.19 J	0.14 J	40000	6.9		4.7 J	23	13000	4.5	8200	460
Northern Athletic Field	SSHS-B3637	SSHS-B3637-SUB-10-12	1/26/2021	857.63	10 - 12 ft	180-116462-3	Not Excavated	6500	< 0.34 U	5	45	0.24 J	0.2 J	52000	8.9		6.2	25	16000	6.2	17000	470
Northern Athletic Field	SSHS-B3637	SSHS-B3637-SUB-8-10	1/26/2021	857.63	8 - 10 ft	180-116462-1	Not Excavated	6300	< 0.24 U	4.2	38	0.23 J	0.085 J	14000	9.1		5.3	21	15000	6	4100	400
Northern Athletic Field	SSHS-B3638	SSHS-B3638-SUB-10-12	1/26/2021	857.95	10 - 12 ft	180-116462-3	Not Excavated	8200	< 0.35 U	7.5	79	0.29 J	0.14 J	47000	11		7.9	25	19000	9	14000	430
Northern Athletic Field	SSHS-B3638	SSHS-B3638-SUB-8-10	1/26/2021	857.95	8 - 10 ft	180-116462-1	Not Excavated	4600	< 0.33 U	3.9	32	0.16 J	0.16 J	39000	6.3		4.6 J	15	11000	4.6	8400	350
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	7400	0.39 J	5.6	120	0.32 J	0.094 J	13000	11		5.5	24	16000	42	2800	430
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-2-4	2/2/2021	856.82	2 - 4 ft	1801167231	Excavated	5800	< 0.35 U	3.7	34	0.23 J	0.043 J	1200	7.1		3.3 J	11	10000	6.2	1400	190
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-2-4	1/29/2021	856.79	2 - 4 ft	180-116665-3	Excavated	8400	0.53 J	7.9	46	0.36 J	0.079 J	4000	17		6.5	22	18000	17	2600	320
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-2-4	1/29/2021	856.79	2 - 4 ft	180-116665-3	Excavated	8400	0.53 J	7.9	46	0.36 J	0.079 J	4000	17		6.5	22	18000	17	2600	320
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	5200	< 0.034 U	3.9	86 J	0.2 J	0.1 J	24000 J	10		4.5	16	12000	7	7800 J+	540
Northern Athletic Field	SSHS-B3647	SSHS-B3647-SUB-2-4	1/29/2021	856.70	2 - 4 ft	180-116665-3	Excavated	7600	< 0.35 U	5.7	55	0.27 J	0.14 J	69000	14		5.1	27	14000	4.9	5800	450
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	4700	< 0.34 U	4	30	0.17 J	0.11 J	47000	7.3		4.2 J	19	12000	8.7	6400	780
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated	3800	< 0.29 U	3.1	28	0.14 J	0.074 J	22000	8.8		3 J	14	9000	4.3	6700	350
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated	6000	< 0.34 U	4.5	60	0.29 J	0.1 J	1500	10		4.6 J	22	14000	8.3	1700	590
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated	7500	< 0.34 U	5.3	51	0.24 J	0.11 J	19000	10		6.6	35	21000	14	6900	500
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated	4100	< 0.24 U	4	19	0.14 J	0.084 J	24000	6		3.7	16	9300	7	7200	190
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated		< 1.06 U	3.55	42.2	< 0.532 U	< 0.532 U		7.49		5.87	15.9		6.02		
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	2 - 4 ft	180-124920-2	Not Excavated	6000	< 0.27 U	3.7	41	0.26 J	0.12 J	120000	7.8		6	17	13000	8.6	6400	500
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	4 - 6 ft	180-124920-1	Not Excavated	10000	0.3 J	15	140	0.46 J	0.035 J	4400 J	13		8.8	36	24000	27	2700	370
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	6 - 8 ft	180-124920-1	Not Excavated	9200	0.39 J	18	95	0.32 J	< 0.041 U	3300 J	15		7.7	38 J	34000	22	2900	540 J
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	8 - 10 ft	180-124920-1	Not Excavated	8600	< 0.36 U	10	79	0.25 J	< 0.039 U	1300	14		6.6	20	32000	12	2400	330
Rear Parking Lot	SSHS-B3840	SSHS-B3840	7/23/2021	847.79	10 - 12 ft	180-124920-1	Not Excavated	7100	0.3 J	10	58	0.17 J	< 0.026 U	1100	12		5	25	25000	7	2100	180
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	8200	< 0.36 U	7.1	83	0.36 J	0.091 J	16000	10		6.5	21	16000	30	5100	510
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	6700	< 0.32 U	5.2	52	0.26 J	0.084 J	34000	9.9		5.5	17	14000	15	3700	340
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	6600	< 0.32 U	4.8	49	0.22 J	0.048 J	7000 J	8		4.7 J	15	15000	8.8	2700 J	540
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	6100	< 0.25 U	5	37	0.23 J	0.058 J	36000	8		5.1	17	13000	8.4	12000	340
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	5400	< 0.28 U	4.6	61	0.17 J	0.049 J	47000	11		5.4	17	13000	9.9	20000	520
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	5700	< 0.3 U	4.5	39	0.23 J	0.05 J	13000	8.4		4.5	15	13000	9.8	2900	260
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	6000	< 0.37 U	6.8	33 J	0.27 J	0.069 J	20000	8		5 J	17	14000	7.7 J	3000	280 J
Northern Athletic Field	SSHS-B3853	SSHS-B3853-SUB-6-8	9/16/2021	856.30	6 - 8 ft	180-127205-2	Not Excavated	4900	< 0.33 U	3.7	59 J	0.2 J	< 0.036 UJ	8300 J	9.5		3.6 J	14	10000	7	3300 J	320
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	6500	< 0.33 U	5.6	150	0.28 J	0.13 J	55000	10		6.7	24	17000	16	7900	500
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	2700	0.66 J	4.3	23	0.11 J	0.12 J	130000	4.5		3.2 J	9.8	7600	9.0	3400	320
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	3900	5.2	3.7	27	0.15 J	0.11 J	45000	5.7		3.6 J	15	9500	4.9	8000	250
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated	6400	< 0.33 U	4.3	36	0.21 J	0.09 J	44000	7.8		5.4	17	15000	7	6600	290
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	6100	< 0.38 UT	6.7	51	0.30 J	0.17 J	1700	9.5		5.8	23 T	15000	8.8	2300	310
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	6400	< 0.41 U	5.1	47	0.25 J	0.081 J	15000	8.5		5.8 J	21	14000	11	3700	580
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	6200	< 0.30 U	3.9	48	0.21 J	0.16 J	43000	7.9		5.3	19	14000	6.0	12000	330
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	6900	0.63 J	4.6	47	0.23 J	0.26 J	71000	10		6.0	19	15000	7.8	18000	400
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	4600	< 0.27 U	4.9	31	0.23 J	0.089 J	22000	6.1		4.6	13	12000	6.3	4000	230
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	4500	< 0.38 U	3.3	41	0.17 J	0.082 J	32000	7.4		3.8 J	14	11000	5.9	7000	240
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	5000	< 0.38 U	3.5	41	0.18 J	0.079 J	38000	7.0		4.1 J	14	12000	5.3	5400	280
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	5000	< 0.35 U	3.4	42	0.18 J	0.095 J	41000	13		4.0 J	27	13000	7.5	5300	320
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	7200	< 0.35 U	7.8	65	0.36 J	0.67	22000	11		6.3	28	17000	28	5600	340
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	6300	< 0.37 U	4.1	40	0.23 J	0.091 J	13000	8.1		4.7 J	18	15000	8.0	4900	190
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	9200	< 0.36 U	6.5	100	0.46	0.15 J	11000	12		6.6	29	19000	44	2500	410
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	7000	< 0.37 U	4.3	58	0.34 J	0.090 J	16000	12		6.8	22	17000	17	2300	280
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	4900	< 0.37 U	5.6	54	0.30 J	2.8	15000	7.6		3.9 J	24	14000	24	2100	330
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	5700	< 0.39 U	4.2	53	0.28 J	3.9	28000	9.9		3.8 J	21	12000	19	3600	310
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	7600	0.41 JT	5.7 T	78 T	0.36 JT	0.83	12000	12 T		5.5	38 T	18000 T	34 T	2500 T	360
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	5200	0.43 JT	9.0	48	0.21 J	0.19 J	35000	8.5		5.1	16	13000	15 T	13000 T	390
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	5100	0.49 J	4.9	45	0.20 J	0.18 J	45000	7.1		5.0	19	12000	8.4	12000	410
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	5000	0.47 J	4.1	49	0.18 J	0.20 J	35000	7.9		4.7	15	12000	7.9	9300	480
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	9000	< 0.69 U	7.6	61	0.42 J	0.38 J	1900	11		5.6	27	18000	15	1900	420
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	6500	0.44 J	6.0	42	0.24 J	0.17 J	10000	10		5.4	20	14000	15	4800	400
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	5500	0.66 J	6.9	41	0.22 J	0.20 J	48000	7.6		4.9	19	13000	12	22000	420
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	8100	0.37 J	5.0	47	0.31 J	0.12 J	8900	9.8		4.8	15	13000	9.3	1800	240
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	7000	0.36 J	7.3	36	0.28 J	0.12 J	9700	8.9		5.2	19	14000	9.3	1900	270
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	6200	0.43 J	5.4	43	0.24 J	0.16 J	18000	9.2		5.4	23	14000	7.0	6900	520
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	5900	< 0.30 U	5.0	34	0.24 J	0.14 J	6400	8.0		5.1	21	13000	8.3	3000	250
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	5800	0.35 J	5.5	36	0.23 J	0.17 J	21000	9.3		5.2	21	13000	7.2	6000	320
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	4700	0.24 JT	4.5	38 T	0.20 JT	0.14 JT	19000	6.7 T		4.3	14	11000	6.5	7400	350 T

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.020 U	18	590	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U		11	51
Northern Athletic Field	SSHS-B3631	SSHS-B3631-SUB-4-6	1/25/2021	856.31	4 - 6 ft	180-116404-3	Not Excavated	0.037	54	690	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		18	60
Northern Athletic Field	SSHS-B3631	SSHS-B3631-SUB-2-4	1/25/2021	856.31	2 - 4 ft	180-116404-1	Excavated	0.11	380	480 J	1.8	< 0.12 U	68 J		0.41 J		17	250
Northern Athletic Field	SSHS-B3632	SSHS-B3632-SUB-2-4	1/27/2021	856.69	2 - 4 ft	180-116529-1	Excavated	1.1	22	630	< 0.52 U	< 0.11 U	77 J		< 0.32 U		14	71
Northern Athletic Field	SSHS-B3632	SSHS-B3632-SUB-4-6	1/27/2021	856.69	4 - 6 ft	180-116529-3	Excavated	< 0.023 U	17	720	< 0.6 U	< 0.12 U	< 70 U		< 0.37 U		19	51
Northern Athletic Field	SSHS-B3633	SSHS-B3633-SUB-2-4	1/27/2021	856.94	2 - 4 ft	180-116529-1	Excavated	0.77	18	670	< 0.56 U	0.81	150 J		< 0.35 U		14	110
Northern Athletic Field	SSHS-B3633	SSHS-B3633-SUB-4-6	1/27/2021	856.94	4 - 6 ft	180-116529-3	Excavated	0.16	16	810	< 0.61 U	< 0.12 U	< 71 U		< 0.38 U		18	70
Northern Athletic Field	SSHS-B3634	SSHS-B3634-SUB-6-8	1/26/2021	857.44	6 - 8 ft	180-116462-1	Not Excavated	< 0.021 U	13	610	< 0.44 U	< 0.089 U	79 J		< 0.27 U		10	45
Northern Athletic Field	SSHS-B3634	SSHS-B3634-SUB-8-10	1/26/2021	857.44	8 - 10 ft	180-116462-3	Not Excavated	< 0.018 U	10	600	< 0.52 U	< 0.11 U	72 J		< 0.32 U		6.9	40
Northern Athletic Field	SSHS-B3635	SSHS-B3635-SUB-6-8	1/26/2021	857.87	6 - 8 ft	180-116462-1	Not Excavated	< 0.022 U	15	910	< 0.53 U	< 0.11 U	< 63 U		< 0.33 U		10	53
Northern Athletic Field	SSHS-B3635	SSHS-B3635-SUB-8-10	1/26/2021	857.87	8 - 10 ft	180-116462-3	Not Excavated	< 0.019 U	13	800	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U		9.6	54
Northern Athletic Field	SSHS-B3636	SSHS-B3636-SUB-6-8	1/26/2021	857.79	6 - 8 ft	180-116462-1	Excavated	< 0.021 U	12	630	0.62 J	< 0.096 U	75 J		< 0.29 U		8.9	44
Northern Athletic Field	SSHS-B3636	SSHS-B3636-SUB-8-10	1/26/2021	857.79	8 - 10 ft	180-116462-3	Not Excavated	< 0.019 U	12	760	< 0.5 U	< 0.1 U	63 J		< 0.31 U		9.2	50
Northern Athletic Field	SSHS-B3637	SSHS-B3637-SUB-10-12	1/26/2021	857.63	10 - 12 ft	180-116462-3	Not Excavated	< 0.019 U	16	800	0.53 J	< 0.11 U	90 J		< 0.32 U		10	66
Northern Athletic Field	SSHS-B3637	SSHS-B3637-SUB-8-10	1/26/2021	857.63	8 - 10 ft	180-116462-1	Not Excavated	< 0.022 U	13	580	< 0.36 U	< 0.074 U	100 J		< 0.23 U		11	46
Northern Athletic Field	SSHS-B3638	SSHS-B3638-SUB-10-12	1/26/2021	857.95	10 - 12 ft	180-116462-3	Not Excavated	< 0.02 U	19	960	< 0.53 U	< 0.11 U	91 J		< 0.33 U		16	70
Northern Athletic Field	SSHS-B3638	SSHS-B3638-SUB-8-10	1/26/2021	857.95	8 - 10 ft	180-116462-1	Not Excavated	< 0.021 U	11	590	0.67 J	< 0.1 U	66 J		< 0.31 U		7.7	87
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	0.072	16	710	< 0.54 U	< 0.11 U	64 J		< 0.34 U		14	64
Northern Athletic Field	SSHS-B3645	SSHS-B3645-SUB-2-4	2/2/2021	856.82	2 - 4 ft	1801167231	Excavated	0.021 J	8.9	520	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		9.7	31
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-2-4	1/29/2021	856.79	2 - 4 ft	180-116665-3	Excavated	0.043	17	740	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U		14	57
Northern Athletic Field	SSHS-B3646	SSHS-B3646-SUB-2-4	1/29/2021	856.79	2 - 4 ft	180-116665-3	Excavated	0.043	17	740	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U		14	57
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	< 0.034 U	11	650	0.71 J	< 0.034 U	66 J		< 0.034 U		9.5	40 J-
Northern Athletic Field	SSHS-B3647	SSHS-B3647-SUB-2-4	1/29/2021	856.70	2 - 4 ft	180-116665-3	Excavated	< 0.021 U	15	940	< 0.53 U	< 0.11 U	190 J		< 0.33 U		12	47
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.021 U	11	490 J	0.52 J	< 0.11 U	< 61 U		< 0.33 U		7.7	48
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.021 U	11	490 J	0.52 J	< 0.11 U	< 61 U		< 0.33 U		7.7	48
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated	< 0.021 U	8.3	450	< 0.44 U	< 0.091 U	95 J		< 0.28 U		6.3	34
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated	< 0.023 U	13	600	< 0.51 U	< 0.1 U	< 60 U		< 0.32 U		9.8	62
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated	0.026 J	15	630	< 0.51 U	< 0.1 U	62 J		< 0.32 U		12	67
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated	< 0.023 U	9.3	420	0.51 J	< 0.074 U	64 J		< 0.22 U		6.4	46
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.053 U	13.9		1.32	< 1.06 U			< 1.06 U	< 53 U	113	44.8
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	2 - 4 ft	180-124920-2	Not Excavated	0.025 J	16	650	1.2	< 0.083 U	130 J		< 0.25 U		9	47
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	4 - 6 ft	180-124920-1	Not Excavated	0.043	43	620	0.63 J	< 0.086 U	150 J		< 0.26 U		15	81
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	6 - 8 ft	180-124920-1	Not Excavated	0.034 J	23	780	0.76 J	< 0.12 U	110 J		< 0.36 U		16	74
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	8 - 10 ft	180-124920-1	Not Excavated	< 0.019 U	16	850	< 0.55 U	< 0.11 U	100 J		< 0.34 U		14	65
Rear Parking Lot	SSHS-B3840	SSHS-B3840	7/23/2021	847.79	10 - 12 ft	180-124920-1	Not Excavated	< 0.02 U	13	710	0.39 J	< 0.076 U	170 J		< 0.23 U		13	46
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	0.043	16	790	0.74 J	< 0.11 U	110 J		< 0.34 U		15	71
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	0.02 J	15	620	0.48 J	< 0.099 U	71 J		< 0.3 U		14	60
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	0.024 J	12	610	< 0.49 UJ	< 0.1 U	< 58 UJ		< 0.31 U		10	41
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.018 U	13	830	0.47 J	< 0.076 U	72 J		< 0.23 U		12	43
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.02 U	13	780	0.74 J	< 0.087 U	95 J		< 0.26 U		13	39
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.025 U	13	550	< 0.46 U	< 0.093 U	< 54 U		< 0.28 U		9.4	44
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.015 UJ	13	840	< 0.56 UJ	< 0.12 U	< 66 UJ		< 0.35 U		11 J	41
Northern Athletic Field	SSHS-B3853	SSHS-B3853-SUB-6-8	9/16/2021	856.30	6 - 8 ft	180-127205-2	Not Excavated	< 0.019 U	9.2	740	< 0.5 U	< 0.1 U	65 J		< 0.31 U		9.3	34
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	< 0.021 U	18	700	0.66 J	< 0.10 U	85 J		< 0.31 U		10	68
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.020 U	8.0	400	< 0.36 U	< 0.073 U	77 J		< 0.22 U		5.3	31
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.020 U	8.8	360 J	< 0.47 U	< 0.096 U	72 J		0.55 J		7.0	38
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated	0.028 J	15	520	< 0.49 U	< 0.1 U	70 J		< 0.31 U		8.8	49
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.025 U	13	830	< 0.58 U	< 0.12 U	< 68 U		0.86 J		12	54
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.028 U	15	620	< 0.62 UT	< 0.13 U	< 73 U		< 0.39 U		9.1	50
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.019 U	14	590	< 0.46 U	< 0.094 U	68 J		< 0.29 U		9.0	80
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.019 U	15	590	< 0.50 U	< 0.10 U	82 J		0.48 J		11	97
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.022 U	12	620	< 0.40 U	< 0.082 U	49 J		< 0.25 U		8.6	36
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.024 U	10	590	< 0.58 U	< 0.12 U	77 J		< 0.36 U		8.0	42
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.022 U	11	600	< 0.58 U	< 0.12 U	76 J		< 0.36 U		7.9	47
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	0.025 J	15	490 J	< 0.53 U	< 0.11 U	81 J		< 0.33 U		8.2	47
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	0.13	21	850	< 0.53 U	< 0.11 U	76 J		< 0.33 U		13	60
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.023 U	13	640	< 0.55 U	< 0.11 U	< 65 U		< 0.35 U		10	59
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	0.27 T	23	850	< 0.55 U	< 0.11 U	64 J		< 0.34 U		15	71
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	0.11	17	680	0.56 J	< 0.11 U	< 65 U		< 0.35 U		12	42
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	3.1	18	490 J	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U		9.6	61
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	1.2	17	580	< 0.60 U	< 0.12 U	< 70 U		< 0.37 U		13	47
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	0.14	23 T	610	< 0.55 UT	< 0.11 U	92 J		< 0.34 UT		12	67
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.018 U	12	540	< 0.48 U	< 0.098 U	64 J		0.53 J		9.3	45
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.022 U	12	610	< 0.47 U	< 0.097 U	81 J		0.45 J		8.5	50
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.020 U	11	570	< 0.47 U	< 0.096 U	61 J		0.46 J		8.3	47
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	0.032 J	18	740 J	< 1.1 U	< 0.21 U	< 120 U		0.64 J		15	220
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	0.020 J	14	610	< 0.48 U	< 0.098 U	< 56 U		0.59 J		11	47
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.020 U	12	670	< 0.50 U	< 0.10 U	95 J		0.50 J		9.7	64
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	0.027 J	17	490	< 0.45 U	< 0.092 U	64 J		0.75 J		13	54
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	0.028 J	16	500	< 0.42 U	< 0.086 U	< 49 U		0.74 J		12	46
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.021 U	15	570	< 0.54 U	< 0.11 U	< 63 U		0.66 J		10	47
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.021 U	13	550	< 0.45 U	< 0.092 U	< 53 U		0.66 J		11	50
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	0.027 J	13	690	< 0.40 U	< 0.082 U	57 J		0.62 J		11	47
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.022 U	10	620 T	< 0.31 UT	< 0.063 U	60 J		0.38 J		9.1	37

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	3800	< 0.37 U	2.5	32	0.18 J	0.039 J	13000	5.5		4.3 J	8.9	8700	6.7	4300	230
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	5400	< 0.37 U	3.6	38	0.26 J	0.075 J	7700	7.8		6.1	17	12000	5.1	3500	280
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	3800	< 0.31 U	3.5	29	0.19 J	0.072 J	17000	7.3		4.5	10	9500	4.1	4200	300
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	3100	< 0.37 U	2.6	27	0.18 J	0.051 J	13000	5.6		3.7 J	7.6	7600	4.1	4700	170
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	5100	< 0.38 U	4.6	31	0.25 J	0.079 J	21000	7.9		4.7 J	15	12000	6.0	5500	270
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	4000	0.36 J	3.2	25	0.16 J	0.059 J	17000	6.2		3.8 J	12	9400	6.8	4000	310
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	4100	0.46 J	2.9	33	0.15 J	0.078 J	18000	6.5		3.9 J	16	10000	4.6	3900	350
EHS Building	SSHS-B3S	B3-C2-Composite	7/25/2007	855.70	2 - 2.9 ft	NA	Not Excavated															
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	4000	< 0.034 U	2.5	20	0.12 J	0.045 J	42000	4.5		3.3 J	11	9000	3.8	3900	210
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	2 - 4 ft	180-123985-1	Not Excavated	9800	< 0.35 UJ	9.2	170	0.48	0.11 J	2400	15		7.2	31	18000	130	1800	640
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	9800	0.44 J	6.5	120	0.42	0.12 J	2400	13		6.8	23	17000	49	2100	560
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	9900	0.36 J	6.8	110	0.42	0.10 J	2000	12		6.8	22	17000	56	2100	570
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	8400	0.34 J	6.7	48	0.35 J	< 0.033 U	370 J	9.4		6.1	20	16000	9.3	1900	320
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	10 - 12 ft	180-127265-2	Not Excavated	5700	< 0.034 U	7.2	33	0.26 J	0.084 J	16000	7.4		5.9	16	14000	7.4	6100	270
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	858.24	12 - 14 ft	180-127265-2	Not Excavated	5400	< 0.034 U	4.5	48	0.18 J	0.075 J	52000	11		4.6	16	13000	8.8	9600	510
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	14 - 16 ft	180-127265-2	Not Excavated	5000	< 0.034 U	5.6	46	0.2 J	0.059 J	33000	9.9		5.7	18	13000	9.5	5800	420
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	2 - 4 ft	180-127265-2	Not Excavated	8000	0.39 J	6.8	70	0.34 J	0.066 J	21000	11		6.1	23	16000	49	5600	350
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	858.24	4 - 6 ft	180-127265-2	Not Excavated	7700	< 0.034 U	6.8	39	0.34 J	0.053 J	3900	10		6.7	24	18000	8.4	2600	350
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	6 - 8 ft	180-127265-2	Not Excavated	5600	< 0.034 U	5.2	34	0.22 J	0.036 J	23000	7.4		4.9	17	14000	6.6	3300	380
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	858.24	8 - 10 ft	180-127265-2	Not Excavated	9900	0.4 J	7.3	53	0.43	0.09 J	16000	13		10	23	22000	11	5300	430
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	5000	< 0.33 U	4.7	35	0.22 J	0.12 J	53000	10		5	14	14000	8.7	6400	340
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	5800	< 0.3 U	4.2	36	0.21 J	0.12 J	38000	9		5.3	17	14000	6.5	8600	330
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	4000	< 0.27 U	4.5	39	0.19 J	0.21 J	69000	7.4		3.9 J	14	9700	7.5	9400	390
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	7500	< 0.35 U	5.5	56	0.33 J	0.11 J	51000	12		7.1	25	17000	15	6700	640
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	5100	< 0.28 U	4.6	31	0.18 J	0.086 J	54000	7		4.7	14	13000	7.9	17000	390
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	4700	< 0.35 U	5.5	29	0.18 J	0.081 J	60000	6.7		4.5 J	14	11000	6.2	14000	350
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	5400	< 0.35 UJ	6.4	36	0.22 J	0.17 J	38000	10		5.2	17	13000 J	9.2	6900 J-	340 J
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	8700	0.32 J	5.4	49	0.32 J	0.046 J	40000 J	12		6.1	20	16000	10	4300	390
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	6200	< 0.32 U	4.9	81	0.24 J	< 0.035 U	24000	9.1		5.5	22	14000	17	6200	480
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	6600	< 0.33 U	4.3	42	0.24 J	0.058 J	39000	12		5.6	21	15000	8	6700	510
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	6400	< 0.31 U	4.9	49	0.24 J	0.055 J	29000	15		5.7	21	15000	9.6	6400	420
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	7600	< 0.35 UJ	5.7	60	0.31 J	0.094 J	59000 J	10		5.9	21	15000	15	8200 J	400
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	7800	< 0.33 U	5.2	40	0.31 J	< 0.035 U	13000	14		5.7	20	15000	8.4	4000	440
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	7800	< 0.31 U	5.8	63	0.32 J	< 0.033 U	5100	10		5.9	23	17000	9.4	3000	420
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	6800	< 0.034 U	4.4	40	0.24 J	0.094 J	37000	10		5.8	21	15000	8.5	9300	450
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	9000	0.39 J	7	58	0.32 J	0.072 J	40000	13		6.7	23	19000	11	6900	540
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	7800	0.3 J	5.1	47	0.27 J	0.037 J	43000	12		6.5	23	16000	16	9400	420
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	9700	< 0.034 U	4.4	94	0.35 J	< 0.034 U	5300	11		5.4	15	14000	17	2400	440
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	8000	< 0.034 U	5.3	56	0.3 J	0.042 J	16000	11		5.5	19	15000	15	3200	420
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	9600	< 0.034 U	5.7	78	0.38 J	0.038 J	13000	12		6	17	16000	22	2700	600
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	12000	< 0.034 U	8.2	79	0.46 J	< 0.034 U	17000	21		8.6	30	24000	44	4800	490
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	7200	< 0.034 U	5.6	96	0.32 J	0.06 J	33000	9.3		6.1	19	15000	9.3	9400 J	710
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	8300	< 0.034 U	6	71	0.31 J	0.094 J	30000	12		6.4	21	16000	11	5300 J	440
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	6600	< 0.034 U	6.8	67	0.25 J	0.06 J	15000	10		5.8	24	17000	15	5600	940
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	5800	< 0.034 U	5	63	0.22 J	0.079 J	69000 J	10		5.2 J	27	13000	12	13000	420
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	6100	< 0.034 U	9.3 J	43	0.22 J	0.054 J	37000	13		5.6	26	15000	11	7700	700 J
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	7500	< 0.034 U	5.6	59	0.26 J	0.071 J	32000	16		6	50	17000	17	8400	420
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	8200	< 0.034 U	6.8	72	0.35 J	0.15 J	31000	12		5.9	71	23000	42	4300	400
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	8000	< 0.034 U	7	53	0.33 J	0.11 J	7500 J	12		7.1	93 J+	25000 J	27	3200	590
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	8800	0.38 J	7.9	60	0.38 J	0.081 J	7800	13		7.5	130	21000	47	3400	490
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	6200	< 0.034 U	5.2	38	0.26 J	0.054 J	8800	15		5.5	28	16000	14	2700	410
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	7500	< 0.034 U	5.8	71	0.64	0.039 J	49000	8.3		7.3	26	22000	12	7300	170
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	7500	< 0.034 U	6.3	67	0.33 J	0.081 J	38000	14		6	30	16000	25	5300	310
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	8400	< 0.034 U	6	83 J	0.35 J	0.11 J	19000 J	13		6.3	40 J-	18000	57 J	4200 J+	440 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	7300	0.36 J	5.9	86	0.3 J	0.11 J	85000	13		5.9	31	15000	28	23000	520 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	8800	< 0.034 U	5.7	77	0.36	0.097 J	33000	12		7.1	23	18000	20	9500	400
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	7500	0.4 J	6.4	71	0.35 J	0.059 J	14000 J	11		5.6	30	17000	26 J+	2700	300 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	8400	< 0.034 U	6.3	76	0.33 J	0.12 J	56000	26		6.6	29	20000	27	7900	760
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated		< 1.04	4.51	34.1	< 0.518	< 0.518		6.26		5.78	16.5		9.84		
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated		< 1.08	5.22	26.8	< 0.539	< 0.539		6.7		5.59	16.8		6.15		
EHS Building	SSHS-B4S	B4-C2-Composite	7/25/2007	-	2 - 2.9 ft	-	Not Excavated															
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated		< 1.13 U	6.46	65.9	< 0.566 U	< 0.566 U		9.17		6.48	24.5		7.97		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated		< 1.08 U	2.33	24.3	< 0.538 U	< 0.538 U		4.63		< 5.38 U	12.6		3.27		
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-10-12	9/22/2016	850.44	10 - 12 ft	180-59029-1	Not Excavated	4700	0.56 J	53	71	0.15 J	< 0.12 U	340 J	9.2		2.4 J	25	41000	7.7	1300	67
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-12-14	9/22/2016	850.44	12 - 14 ft	180-59029-1	Not Excavated	5900	< 0.4 U	38	80	0.2 J	< 0.13 U	4700	15		3.5 J	30	34000	22	2300	130
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-8-10	9/22/2016	850.44	8 - 10 ft	180-59029-1	Excavated	3600	0.72 J	110	73	0.24 J	< 0.12 U	2000	9.8		2.5 J	28	45000	27	1200	82
Northern Athletic Field	SSHS-B54	13 Sep 00B54 4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated		< 1.15 U	3.82	47.1	< 0.575 U	< 0.575 U		7.77		6.28	16.1		8.9		
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-10-12	9/22/2016	850.47	10 - 12 ft	180-59029-1	Not Excavated	3500	1.1	61	76	0.13 J	< 0.12 U	1100	13		2.4 J	95	51000	2100	880	83
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-12-14	9/22/2016	850.47	12 - 14 ft	180-59029-1	Not Excavated	5500	0.62 J	57	110	0.25 J	< 0.13 U	9000	17		4.4 J	79	47000	130	5400	170
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-8-10	9/22/2016	850.47	8 - 10 ft	180-59029-1	Excavated	2000	210	71	100	0.23 J	< 0.11 U	16000	8		4.6 J	110	32000	36000	1400	120
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	12000	< 0.24 U	9	72	0.55	0.062 J	5200	14		9.8	15	23000	12	4000	440
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	4800	< 0.23 U	8.7	63	0.54	0.059 J	17000	9.1		5.5 J	36	21000	28	2400	130
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	1300	1.6	20	92	0.37 J	< 0.017 U	5700	9		4.3 J	35	22000	60	430 J	44
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	3500	< 0.23 U	32	150	0.31 J	< 0.017 U	9000	15		4.3 J	65	30000	78	1800	300

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.021 U	9.0	400 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		6.0	33
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.020 U	11	640	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		8.9	34
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.023 U	8.7	570	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U		7.2	28
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.024 U	6.1	360 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U		5.3 J	20
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.021 U	12	690	< 0.58 U	< 0.12 U	< 67 U		< 0.36 U		9.6	43
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.021 U	9.2	490 J	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U		6.8	31
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.021 U	9.9	480 J	< 0.58 U	< 0.12 U	< 67 U		< 0.36 U		6.9	37
EHS Building	SSHS-B3S	B3-C2-Composite	7/25/2007	855.70	2 - 2.9 ft	NA	Not Excavated							< U				
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.034 U	16	320 J	0.47 J	< 0.034 U	81 J		< 0.034 U		6.9	61
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	2 - 4 ft	180-123985-1	Not Excavated	0.18	18	620	< 0.53 U	< 0.11 U	69 J		< 0.33 UJ		21	250
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	0.13	20	670	0.61 J	< 0.10 U	< 59 U		< 0.32 U		17	100
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	0.13	20	630	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U		16	87
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.024 U	16	660	< 0.47 U	< 0.096 U	< 55 U		< 0.29 U		14	56
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	10 - 12 ft	180-127265-2	Not Excavated	< 0.034 U	14	830	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		10	44
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	858.24	12 - 14 ft	180-127265-2	Not Excavated	< 0.034 U	12	610	0.61 J	< 0.034 U	140 J		< 0.034 U		8.7	40
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	14 - 16 ft	180-127265-2	Not Excavated	< 0.034 U	13	650	< 0.034 U	< 0.034 U	74 J		< 0.034 U		8.4	45
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	2 - 4 ft	180-127265-2	Not Excavated	0.039	17	890	0.81 J	< 0.034 U	96 J		< 0.034 U		16	80
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	858.24	4 - 6 ft	180-127265-2	Not Excavated	0.022 J	17	870	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		14	77
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	6 - 8 ft	180-127265-2	Not Excavated	< 0.034 U	12	670	< 0.034 U	< 0.034 U	71 J		< 0.034 U		9.2	61
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	858.24	8 - 10 ft	180-127265-2	Not Excavated	0.021 J	25	1300	0.74 J	< 0.034 U	67 J		< 0.034 U		16	62
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	< 0.017 U	12	640	1.1	< 0.1 U	69 J		< 0.31 U		7.9	43
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.019 U	13	650	0.62 J	< 0.091 U	74 J		< 0.28 U		9.4	90
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	< 0.02 U	10	620	0.94	< 0.084 U	88 J		< 0.26 U		7.7	35
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	0.025 J	19	820	0.95 J	< 0.11 U	93 J		< 0.33 U		13	65
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.017 U	12	550	0.84	< 0.088 U	85 J		< 0.27 U		8.6	44
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.019 U	12	570	0.98 J	< 0.11 U	74 J		< 0.33 U		7.9	35
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	< 0.018 U	13	730	0.88 J	< 0.11 U	77 J		< 0.33 U		9.3	43 J-
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	< 0.019 U	16	760	0.56 J	< 0.094 U	71 J		< 0.29 U		13	47
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.017 U	14	720	< 0.49 U	< 0.1 U	62 J		< 0.3 U		10	53
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.016 U	14	770	0.7 J	< 0.1 U	90 J		< 0.31 U		11	53
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.021 U	15	750	< 0.48 U	< 0.097 U	67 J		< 0.3 U		11	55
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	0.031 J	16	900	0.73 J	< 0.11 U	90 J		< 0.33 U		12	58
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.016 U	15	780	< 0.5 U	< 0.1 U	< 58 U		< 0.31 U		12	50
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.022 U	16	790	0.65 J	< 0.095 U	< 54 U		< 0.29 U		12	59
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	15	750	< 0.034 U	< 0.034 U	91 J		< 0.034 U		11	60
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.034 U	20	790	0.6 J	< 0.034 U	91 J		< 0.034 U		14	69
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	17	790	0.53 J	< 0.034 U	110 J		< 0.034 U		11	54
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	0.095	14	810	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		15	58
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	0.035	17	630	< 0.034 U	< 0.034 U	66 J		< 0.034 U		13	58
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	0.026 J	14	700	0.64 J	< 0.034 U	62 J		< 0.034 U		15	59
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.034 U	23	1000	< 0.034 U	< 0.034 U	93 J		< 0.034 U		21	110
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	16	850	< 0.034 U	< 0.034 U	86 J		< 0.034 U		14	52
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	18	850	< 0.034 U	< 0.034 U	100 J		< 0.034 U		13	63
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	15	780	< 0.034 U	< 0.034 U	67 J		< 0.034 U		12	56
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.034 U	17	730	0.88 J	< 0.034 U	140 J		< 0.034 U		11	41
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 0.034 U	17	670	0.95 J	< 0.034 U	120 J		< 0.034 U		11	47
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 0.034 U	23	830	0.56 J	< 0.034 U	150 J		< 0.034 U		14	66
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	0.027 J	38	770	0.74 J	< 0.034 U	240 J		< 0.034 U		16	80
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.034 U	23	790	0.64 J	< 0.034 U	160 J		< 0.034 U		16	96 J
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.034 U	29	810	< 0.034 U	< 0.034 U	160 J		< 0.034 U		18	140
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	0.028 J	19	740	< 0.034 U	< 0.034 U	120 J		< 0.034 U		14	57
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	0.028 J	20	820	1.6	< 0.034 U	300 J		< 0.034 U		13	29
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	0.024 J	19	870	1.1	< 0.034 U	270 J		< 0.034 U		13	60
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	0.083 J-	26	770	< 0.034 U	< 0.034 U	140 J		< 0.034 U		13	75 J+
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	0.043 J-	18	890	1.5	< 0.034 U	290 J		< 0.034 U		12	57 J+
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	0.071	20	890	0.54 J	< 0.034 U	120 J		< 0.034 U		15	68
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	0.02 J	19	840	0.72 J	< 0.034 U	310 J		< 0.034 U		13	59 J+
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	0.036	20	870	1.6	< 0.034 U	200 J		< 0.034 U		14	130
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.0518	12		0.518	< 1.04			< 1.04	< 51.8	11.1	41.5
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.0539	12.9		< 0.539	< 1.08			< 1.08	< 53.9	11.6	98.8
EHS Building	SSHS-B4S	B4-C2-Composite	7/25/2007	-	2 - 2.9 ft	-	Not Excavated							< U				
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.0566 U	15.4		0.68	< 1.13 U			< 1.13 U	< 56.6 U	14.3	61.5
Northern Athletic Field	SSHS-B52	13 Sep 00B52 4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.0538 U	8.39		1.4	< 1.08 U			< 1.08 U	< 53.8 U	7.84	27.3
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-10-12	9/22/2016	850.44	10 - 12 ft	180-59029-1	Not Excavated	< 0.008 U	10	1000	1.3	< 0.18 U	510 J		< 0.54 U		14	31
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-12-14	9/22/2016	850.44	12 - 14 ft	180-59029-1	Not Excavated	0.69	15	960	1.2	< 0.19 U	410 J		< 0.56 U		15	53
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-8-10	9/22/2016	850.44	8 - 10 ft	180-59029-1	Excavated	0.67	12	1100	5.5	< 0.18 U	1000		< 0.54 U		19	29
Northern Athletic Field	SSHS-B54	13 Sep 00B54 4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.0575 U	14.6		1.56	< 1.15 U			< 1.15 U	< 57.5 U	11.7	72.2
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-10-12	9/22/2016	850.47	10 - 12 ft	180-59029-1	Not Excavated	0.046	24	890	2.6	< 0.18 U	850		< 0.53 U		13	55
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-12-14	9/22/2016	850.47	12 - 14 ft	180-59029-1	Not Excavated	0.043	20	1200	1.7	< 0.19 U	880		< 0.56 U		15	54
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-8-10	9/22/2016	850.47	8 - 10 ft	180-59029-1	Excavated	0.058	27	530	12	1.6	760		< 0.49 U		10	50
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	0.017 J	19	1700	0.56 J	< 0.049 U	88 J		< 0.18 U		18	56
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	0.027 J	17	790	1.2	< 0.046 U	200 J		< 0.17 U		16	30
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	0.065	10	700	2.8	< 0.048 U	320 J		0.2 J		18	7.2
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	0.73	67	870	4.9	0.091 J	1000		0.83 J		14	42

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	6000	< 0.22 U	51	93	0.15 J	< 0.015 U	< 1.6 U	11		3.5 J	22	44000	15	1700	130
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	6400	< 0.26 U	63	140	0.22 J	< 0.018 U	6000	14		4 J	33	42000	28	2500	200
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	7000	< 0.22 U	12	100	0.35 J	< 0.016 U	13000	17		6.4	100	26000	89	3300	430
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	7700	< 0.2 U	7.2	61	0.31 J	< 0.015 U	31000	12		6.4	31	18000	19	6100	320
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	4900	< 0.22 UJ	83 J	160	0.45	< 0.016 U	6100 J	29 J		5.8	210	39000	220 J	2000 J	290
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	6400	< 0.21 U	49	82	0.22 J	< 0.015 U	990	11		3.3 J	41	51000	7.2	1600	110
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	5900	< 0.23 U	43	58	0.2 J	< 0.016 U	1500	11		3.5 J	28	49000	11	1500	100
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	7600	< 0.23 U	8.9	120	0.37 J	< 0.016 U	18000	17		6.6	74	20000	330	3800	350
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	9800	< 0.22 U	7.6	57	0.42 J	< 0.016 U	8100	12		7.8	35	20000	40	3500	430
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	6800	1.6 J	28	240	0.47 J	< 0.018 U	7500	40		7.8	340	44000	1800	1900	470
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	7200	0.51 J	17	120	0.38 J	< 0.015 U	8700	47 J		6.4	130	27000	320 J	3500	410
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	7100	0.23 J	19	100	0.36 J	< 0.015 U	7600	16 J		6.2	100	25000	72 J	2900	340
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	7200	0.61 J	8.1	190	0.38 J	< 0.016 U	19000	39		6.2	75	20000	160	3300	430
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	5800	0.28 J	5.5	74	0.26 J	< 0.015 U	17000	7.5		5.5	18	14000	23	4500	360
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	7600	< 0.22 U	8.3	92	0.39 J	< 0.016 U	11000	11		6.2	26	17000	35	3300	450
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	9100	< 0.21	11	55	0.4	0.034	2300	11		7.1	27	19000	16	2100	590
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	5400	< 0.2	5.2	49	0.21	0.058	34000	8.6		4.7	17	13000	7.6	9900	380
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	5300	< 0.2	12	42	0.21	0.015	36000	8		4.5	16	13000	7.2	11000	420
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	4200	< 0.19	4.2	33	0.15	0.039	39000	7.1		3.9	21	11000	7	14000	300
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	6900	1.1	7	53	0.32	0.53	4700	8.4		6.6	31	17000	45	1800	510
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	8800	< 0.24	9.4	50	0.38	0.038	6500	9.7		7.9	23	20000	15	2500	610
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	6300	< 0.23	6.8	42	0.27	0.08	6800	8		5.3	18	16000	6.2	2900	440
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	6000	0.28	5.7	47	0.23	< 0.014	33000	6.8		5.7	18	15000	6.4	8800	480
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	6300	< 0.21	6.7	33	0.32	< 0.015	1300	8.3		5.7	17	15000	7.4	1900	320
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	4400	0.29	3.2	28	0.17	< 0.015	23000	5.5		4.1	16	11000	4.4	5800	350
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	4300	< 0.38	4.6	31	0.17	0.03	54000	5.8		4	13	11000	16	20000	330
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	5700	< 0.2	6.1	34	0.26	0.51	4000	8.3		5.5	17	15000	6.9	2700	450
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	5400	< 0.21	5.2	33	0.22	0.53	30000	6.3		5.9	12	13000	5.1	4300	280
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	4200	< 0.22	4.9	30	0.18	0.047	31000	5.7		4	14	11000	4.9	4700	300
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	4900	0.39 J	4.7	36	0.24 J	< 0.013 U	71000	5.5		3.8 J	16	9700	4.2	8500	360
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	7900	2.6	7.6	60	0.38 J	< 0.015 U	5900	9.8		5.7	45	18000	93 J	2000	510
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	9400	0.67 J	4	56	0.32 J	< 0.015 U	73000	8.8		5.4	20	13000	8.2	8500	450
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	5700	< 0.22 U	5.8	37	0.28 J	< 0.016 U	1200	8.1		6.7	19	15000	8.7	1900	710
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	7700	0.38 J	7.4	66	0.34 J	< 0.015 U	2500 J	8.8		5.6	27 J	16000	13	1900	470
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	7600	0.27 J	6.8	72	0.34 J	< 0.015 U	5500	9.7		5.3 J	39	17000	16	1700	340
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	5800	< 0.24 U	3.8	27	0.3 J	< 0.017 U	880	7.6		5.4 J	16	15000	6.3	1700	290
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	4800	< 0.21 U	4.8	42	0.2 J	0.06 J	85000	5.9		4.6 J	17	12000	5.6	8300	420
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	6000	< 0.22 U	7.2	43	0.28 J	0.071 J	8800	7.7		4.8 J	18	14000	9.3	4400	520
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	5100	< 0.21 U	4.6	27	0.21 J	0.055 J	44000	6.1		4.6 J	16	12000	5	16000	310
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	4800	< 0.22 U	6.4	47	0.23 J	0.068 J	2700	7.4		4.9 J	15	14000	6.7	1900	490
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	11000	< 0.21 U	8.4	96	0.54	0.054 J	1700	13		9.3	16	21000	16	2700	480
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	11000	< 0.22 U	8.9	71	0.49	0.044 J	1200	12		9	16	21000	16	2700	450
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	5000	< 0.22 U	6.4	69	0.25 J	0.064 J	8200	6.4		4.5 J	13	12000	6.1	5000	460
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-6-8	1/23/2018	854.01	6 - 8 ft	180-74397-2	Excavated															
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-2-4	1/12/2018	852.96	2 - 4 ft	180-74164-1	Excavated															
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-2-4	1/18/2018	850.25	2 - 4 ft	180-74307-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	4900	0.32 J	4.9	35	0.23 J	< 0.014 U	37000	6.4		4.9	15	12000	6	11000	370
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	7200	0.32 J	6.1	47	0.31 J	< 0.015 U	1700	8.8		5.9	31	24000	14	1500	460
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	5200	< 0.21 U	5.4	32	0.21 J	< 0.015 U	56000 J	6.7		5.1 J	18	13000	8	17000	410
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	5800	0.3 J	7.3	37	0.25 J	< 0.015 U	28000 J	8		5.9	19	15000	11	13000	450
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-6-8	1/20/2018	850.17	6 - 8 ft	180-74390-2	Excavated															
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-2-4	1/19/2018	850.69	2 - 4 ft	180-74310-2	Excavated															
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-4-6	1/24/2018	851.33	4 - 6 ft	180-74436-2	Excavated															
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-6-8	1/11/2018	851.20	6 - 8 ft	180-74124-2	Excavated															
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-4-6	1/20/2018	852.12	4 - 6 ft	180-74390-2	Excavated															
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	6800	< 0.21 U	7.9	72	0.3 J	0.11 J	1200	8.9		6.6	22	17000	14	2300	420
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	6800	< 0.22 U	6.9	96	0.3 J	0.1 J	1500	9.2		7.1	18	17000	9.3	2300	410
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	5500	< 0.24 U	4.8	150	0.25 J	0.052 J	57000	6.3		3.6 J	14	11000	11	1300	400
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	7300	< 0.21 U	6.5	34	0.33 J	0.04 J	500 J	7.8		5.7	14	15000	7.5	2100	290
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-4-6	1/18/2018	851.45	4 - 6 ft	180-74307-2	Excavated															
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-2-4	1/19/2018	851.29	2 - 4 ft	180-74310-2	Excavated															
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	6100	< 0.22 U	6.5	59	0.27 J	1.2	2400	7.8		5.8	18	16000	7.8	2800	830
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	12000	0.36 J	6.8	120	0.51	0.08 J	1400	12		8.6	13	19000	15	2700	620
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	8800	< 0.22 U	9.5	100	0.38 J	0.092 J	1100	11		8.5	22	20000	11	2400	550
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	5100	0.27 J	6	41	0.23 J	< 0.015 U	19000	6.7		5 J	17	14000	5.9	8500	360
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	6900	0.32 J	6.7	45	0.45	< 0.016 U	1800	9.3		6.4	57	15000	30	1900	330
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	7000	< 0.23 U	7.6	72	0.34 J	< 0.016 U	1300	8.9		6.6	21	17000	9	2000	590
Rear Parking Lot	SSHS-B875	SSHS-B875-SUB-2-4	1/20/2018	852.93	2 - 4 ft	180-74390-2	Excavated															
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-8-10	1/18/2018	851.27	8 - 10 ft	180-74307-2	Excavated															
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-8-10	1/19/2018	851.30	8 - 10 ft	180-74310-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	7900	< 0.23 U	9.8	87	0.37 J	0.065 J	1300	11		6.6	24	20000	13	2300	550

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	0.026 J	8.8	1400	2.7	< 0.044 U	580		< 0.16 U		15	45
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	0.032 J	35	1200	4	< 0.052 U	670		< 0.19 U		20	39
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	0.082	48	640	1.1	< 0.045 U	130 J		< 0.16 U		15	110
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	0.029 J	22	740	0.56 J	< 0.041 U	160 J		< 0.15 U		13	56
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	0.85	160 J	680	5.1	< 0.045 U	340 J		0.32 J		18	120 J
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.012 U	8.7	810	1 J	< 0.043 U	550		0.24 J		13	37
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.012 U	9	890	1.3	< 0.046 U	270 J		< 0.17 U		14	34
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	0.08	53	600	0.61 J	< 0.046 U	170 J		< 0.17 U		13	96
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	0.032 J	26	700	0.65 J	< 0.045 U	220 J		< 0.16 U		15	63
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	0.39	160	650	2.5	0.26 J	520 J		0.3 J		18	200
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	0.13	57	700	1.5	< 0.043 U	230 J		< 0.16 U		17	100
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	0.11	49	660	1.6	0.046 J	220 J		0.15 J		14	110
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	0.099	100	730	0.73 J	< 0.044 U	150 J		< 0.16 U		14	98
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	0.11	13	660	0.31 J	< 0.043 U	87 J		< 0.16 U		11	53
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	0.046	28	630	0.61 J	< 0.045 U	63 J		< 0.16 U		15	66
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.012	17	1000	0.49	< 0.042	43		< 0.15		17	55
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.011	11	760	< 0.26	< 0.04	78		< 0.14		10	44
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.011	11	780	0.64	< 0.041	89		< 0.15		9.6	43
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.011	9.4	510	< 0.25	< 0.038	65		< 0.14		7.7	42
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	0.047	14	540	0.47	< 0.043	110		< 0.15		11	63
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	0.031	17	620	< 0.32	< 0.048	40		< 0.17		14	55
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.012	13	630	0.33	< 0.046	49		< 0.17		11	54
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.012	14	520	0.99	< 0.04	60		< 0.15		9.8	73
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	0.017	13	580	1	< 0.042	30		< 0.15		11	46
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.011	9.3	530	1.1	< 0.043	42		< 0.16		7.4	36
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.011	9.7	510	< 0.26	< 0.039	64		< 0.14		7.1	36
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.012	13	550	1	< 0.041	33		< 0.15		11	48
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.011	12	580	0.65	< 0.042	55		< 0.15		8.9	44
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.011	9.8	540	< 0.29	< 0.044	48		< 0.16		7.8	43
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.011 U	9.3	520	0.48 J	< 0.038 U	180 J		< 0.14 U		7.5	36
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	0.058	14	680	0.73 J	< 0.043 U	120 J		< 0.16 U		15	100
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	0.012 J	12	660	0.36 J	< 0.042 U	130 J		< 0.15 U		11	41
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.012 U	14	< 6.9 U	< 0.29 U	< 0.044 U	90 J		< 0.16 U		10	77
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	0.015 J	17	630	0.58 J	< 0.041 U	180 J		< 0.15 U		12	45
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	0.018 J	14	650	< 0.29 U	< 0.044 U	210 J		< 0.16 U		13	55
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.012 U	12	610	< 0.32 U	< 0.049 U	94 J		< 0.18 U		11	42
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.011 U	12	500 J	0.5 J	< 0.042 U	110 J		< 0.15 U		8.2	49
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	0.017 J	12	530 J	0.3 J	< 0.044 U	130 J		< 0.16 U		9.9	53
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.011 U	11	550	0.43 J	< 0.042 U	100 J		< 0.15 U		8.3	39
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.012 U	12	490 J	0.5 J	< 0.044 U	76 J		< 0.16 U		7.8	53
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	0.056	18	780	0.82 J	< 0.043 U	< 1.1 U		< 0.16 U		17	56
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	0.06	18	690	0.58 J	< 0.045 U	150 J		0.19 J		16	54
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	0.016 J	11	570	< 0.3 U	< 0.045 U	90 J		< 0.16 U		8.2	39
Rear Parking Lot	SSHS-B830	SSHS-B830-SUB-6-8	1/23/2018	854.01	6 - 8 ft	180-74397-2	Excavated							52				
Rear Parking Lot	SSHS-B836	SSHS-B836-SUB-2-4	1/12/2018	852.96	2 - 4 ft	180-74164-1	Excavated							22 J				
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-2-4	1/18/2018	850.25	2 - 4 ft	180-74307-2	Excavated							< 12 U				
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.012 U	12	560	< 0.26 U	< 0.04 U	130 J		< 0.15 U		8.6	42
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	0.023 J	12	< 6.7 U	< 0.28 U	< 0.042 U	230 J		< 0.15 U		12	39
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.011 U	12	< 6.6 U	0.85 J	< 0.042 U	130 J		< 0.15 U		9.4	59
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.012 U	14	610	< 0.29 U	< 0.043 U	130 J		< 0.16 U		11	72
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-6-8	1/20/2018	850.17	6 - 8 ft	180-74390-2	Excavated							< 13 U				
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-2-4	1/19/2018	850.69	2 - 4 ft	180-74310-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-4-6	1/24/2018	851.33	4 - 6 ft	180-74436-2	Excavated							11 J				
Rear Parking Lot	SSHS-B846	SSHS-B846-SUB-6-8	1/11/2018	851.20	6 - 8 ft	180-74124-2	Excavated							260				
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-4-6	1/20/2018	852.12	4 - 6 ft	180-74390-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated							< 12 U				
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	0.017 J	15	790	< 0.28 U	< 0.042 U	< 1.1 U		< 0.15 U		13	56
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	0.015 J	16	720	0.48 J	< 0.045 U	110 J		< 0.16 U		12	55
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	0.018 J	8.9	440 J	1.1 J	< 0.048 U	720		< 0.17 U		10	34
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	0.02 J	13	590	0.45 J	< 0.042 U	110 J		< 0.15 U		11	37
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-4-6	1/18/2018	851.45	4 - 6 ft	180-74307-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-2-4	1/19/2018	851.29	2 - 4 ft	180-74310-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated							12 J				
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.012 U	16	510 J	0.52 J	< 0.044 U	110 J		0.23 J		9.9	350
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	0.019 J	17	580	0.62 J	< 0.044 U	350 J		0.24 J		16	59
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	0.024 J	20	680	0.31 J	< 0.045 U	260 J		0.26 J		13	72
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.012 U	12	550	< 0.28 U	< 0.042 U	94 J		< 0.15 U		9.7	120
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	0.019 J	15	700	1.2	< 0.045 U	240 J		< 0.16 U		15	52
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	0.019 J	15	680	< 0.3 U	< 0.046 U	170 J		< 0.17 U		13	63
Rear Parking Lot	SSHS-B875	SSHS-B875-SUB-2-4	1/20/2018	852.93	2 - 4 ft	180-74390-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-8-10	1/18/2018	851.27	8 - 10 ft	180-74307-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-8-10	1/19/2018	851.30	8 - 10 ft	180-74310-2	Excavated							< 12 U,F1				
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	0.013 J	18	670	0.3 J	< 0.046 U	350 J		0.24 J		13	59

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	7300	0.44 J	5.2	41	0.29 J	0.034 J	3700	11		4.9 J	15	14000	10	2300	260
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	8500	< 0.2 U	6.5	48	0.32 J	0.049 J	1100	8.9		7.3	19	19000	8.1	2500	490
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-4-6	1/22/2018	849.63	4 - 6 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-2-4	1/20/2018	852.06	2 - 4 ft	180-74390-2	Excavated															
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-2-4	1/11/2018	851.07	2 - 4 ft	180-74124-2	Excavated															
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-6-8	1/17/2018	850.48	6 - 8 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-8-10	1/17/2018	850.48	8 - 10 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-8-10	1/19/2018	850.66	8 - 10 ft	180-74310-2	Excavated															
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-6-8	1/24/2018	850.66	6 - 8 ft	180-74436-2	Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated															
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-8-10	1/24/2018	850.62	8 - 10 ft	180-74436-2	Excavated															
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-4-6	1/22/2018	850.02	4 - 6 ft	180-74331-2	Excavated															
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	4400	< 0.2 U	4.9	35	0.21 J	0.058 J	1700	5.6		4.2 J	20	12000	5.4	1700	380
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	11000	< 0.24 U	8.4	90	0.5	0.032 J	1300	12		7.9	17	21000	13	2500	530
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	9400	< 0.22 U	7	90	0.45	0.062 J	1200	10		7.2	14	19000	13	2300	560
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	5900	< 0.22 U	6.3	49	0.24 J	0.06 J	47000	7		5.4 J	21	15000	7.2	26000	460
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-8-10	1/23/2018	851.90	8 - 10 ft	180-74397-2	Not Excavated															
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-10-12	1/17/2018	850.94	10 - 12 ft	180-74241-2	Excavated															
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated			7.4	486	< U	0.7		21.3			79		165		
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-4-6	1/17/2018	850.31	4 - 6 ft	180-74241-2	Excavated															
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-6-8	1/24/2018	851.60	6 - 8 ft	180-74436-2	Not Excavated															
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-4-6	1/22/2018	851.62	4 - 6 ft	180-74331-2	Excavated															
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-2-4	1/23/2018	851.62	2 - 4 ft	180-74397-2	Excavated															
Rear Parking Lot	SSHS-B918	SSHS-B918-SUB-8-10	1/18/2018	850.41	8 - 10 ft	180-74307-2	Excavated															
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-2-4	1/16/2018	850.75	2 - 4 ft	180-74203-2	Excavated															
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-4-6	2/28/2018	853.70	4 - 6 ft	180-75405-1	Not Excavated															
Rear Parking Lot	SSHS-B965	SSHS-B965-SUB-6-8	3/1/2018	851.00	6 - 8 ft	180-75480-1	Excavated															
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	5600	< 0.3 U	6.8	54	0.22 J	0.17 J	26000	8.5	< 0.23 U	5	21	14000	6.1	5900	970
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	5400	< 0.32 U	4.9	30	0.2 J	< 0.079 U	5500	10		4.6 J	13	14000	6.4	3500	270
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	8500	< 0.27 U	6	58	0.29 J	0.087 J	3800	14		6.1	18	16000	9.8	2700	570
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	5000	< 0.31 U	5.9	59	0.2 J	0.17 J	6500	8.1		5.6	17	13000	7.2	3400	760
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	5200	0.31 J	4.9	51	0.2 J	0.089 J	1200	7.4	< 0.24 U	4.7 J	15	13000	5.4	1900	500
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	11000	< 0.31 U	7	51	0.42	< 0.075 U	610	13		7.2	15	19000	9.3	2600	250
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	3400	< 0.28 U	4.2	33	0.17 J	< 0.068 U	640	6		2.6 J	11	7900	5.4	830	260
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	8500	0.36 J	6.4	71	0.34 J	0.13 J	3100	9.3		6.8	24	17000	38	2800	640
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	5000	2	58	69	0.17 J	0.6	20000	470	< 0.22 U	11	170	63000	92	7300	960
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	5100	< 0.3 U	5.4	41	0.2 J	0.09 J	25000	9.3		4.7 J	18	12000	14	8900	440
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	3800	< 0.29 U	6.5	38	0.13 J	0.13 J	32000	6.9		3.7 J	15	10000	7.4	9400	420
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	4800	< 0.25 U	8.3	49	0.19 J	0.12 J	18000	26	< 0.23 U	4.7	16	13000	7.6	8100	400
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	6600	0.34 J	8.8	49	0.33 J	0.12 J	8800	10		7.3	19	15000	16	1900	590
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	4300	0.29 J	5.4	38	0.17 J	0.099 J	21000	16		3.8 J	14	10000	9.5	5600	320
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	5200	< 0.3 U	4.6	38	0.21 J	0.081 J	15000	9.1	< 0.22 U	5.6	16	13000	11	3100	440
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	5000	< 0.21 U	4	36	0.19 J	0.081 J	22000	13	< 0.23 U	4.3	17	13000	7.8	4800	330
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	4400	< 0.3 U	6.3	34	0.15 J	0.13 J	44000	8		4.2 J	15	12000	9.1	8500	580
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	4800	< 0.32 U	4.3	39	0.15 J	< 0.078 U	15000	9.2		4.8 J	17	12000	6.5	5200	370
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	6400	< 0.3 U	5.8	44	0.2 J	0.11 J	20000	11		5.7	33	16000	11	9400	500
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	5600	< 0.28 U	4.8	55	0.2 J	0.11 J	24000	9.1		4.7	15	13000	7	5900	420
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	4400	< 0.31 U	4.1	25	0.15 J	0.13 J	56000	7.3		4.3 J	19	11000	6.5	26000	350
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	5100	< 0.3 U	4.5	48	0.18 J	0.11 J	30000	7.4		4.7 J	22	7900	5.5	6600	350
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated			9	< 66.6 U	< 0.6 U	< 0.6 U		6.3			32.5		64		
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated			9.9	73.9	< 0.58 U	< 0.58 U		14.6			142		125		
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated			7.9	187	< 0.56 U	< 0.56 U		12.2			49		76		
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated			6.3	63	< 0.58 U	< 0.58 U		6.5			30.6		24.4		
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated			3.7	93.9	< 0.55 U	< 0.55 U		9.9			15.1		23.3		
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated			2.3	245	< 0.58 U	< 0.58 U		9.7			103		144		
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	8 - 10 ft	1801512611	Not Excavated	3400	< 0.20 U	20	210	0.15 J	< 0.049 U	1500	9.0		2.6 J	23	28000	8.2	940	87
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	10 - 12 ft	1801512611	Not Excavated	3100	< 0.39 UT	53 T	81 T	0.11 JT	0.049 JT	560 T	8.2 T		2.1 JT	29 T	49000 T	20 T	860 T	160 T
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	12 - 14 ft	1801512611	Not Excavated	3500	< 0.44 U	30	130	0.16 J	< 0.053 U	2700	12		2.9 J	43	47000	14	1200	110
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	14 - 16 ft	1801512611	Not Excavated	3900	< 0.36 U	31	73	0.19 J	< 0.044 U	4900	13		3.3	34	41000	11	1200	130

TABLE5-6B
Subsurface Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**	**Tin**	**Vanadium**	**Zinc**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	0.018 J	12	360 J	0.42 J	< 0.044 U	170 J		< 0.16 U		12	44
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.012 U	16	440 J	0.39 J	< 0.04 U	180 J		0.19 J		12	52
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-4-6	1/22/2018	849.63	4 - 6 ft	180-74331-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-2-4	1/20/2018	852.06	2 - 4 ft	180-74390-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-2-4	1/11/2018	851.07	2 - 4 ft	180-74124-2	Excavated							< 0.014 U				
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-6-8	1/17/2018	850.48	6 - 8 ft	180-74241-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-8-10	1/17/2018	850.48	8 - 10 ft	180-74241-2	Excavated							30 J				
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-8-10	1/19/2018	850.66	8 - 10 ft	180-74310-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-6-8	1/24/2018	850.66	6 - 8 ft	180-74436-2	Excavated							12 J				
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated							< 12 U				
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-8-10	1/24/2018	850.62	8 - 10 ft	180-74436-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-4-6	1/22/2018	850.02	4 - 6 ft	180-74331-2	Excavated							< 11 U				
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.012 U	11	440 J	< 0.27 U	< 0.04 U	84 J		< 0.15 U		7.3	46
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	0.029 J	16	840	0.55 J	< 0.048 U	< 1.3 U		0.18 J		16	59
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	0.02 J	15	590	0.68 J	< 0.045 U	160 J		0.24 J		14	52
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.012 U	13	590	0.41 J	< 0.045 U	180 J		< 0.16 U		10	47
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-8-10	1/23/2018	851.90	8 - 10 ft	180-74397-2	Not Excavated							< 11 U				
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-10-12	1/17/2018	850.94	10 - 12 ft	180-74241-2	Excavated							11 J				
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	0.07	71		0.77	< U						306
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-4-6	1/17/2018	850.31	4 - 6 ft	180-74241-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-6-8	1/24/2018	851.60	6 - 8 ft	180-74436-2	Not Excavated							< 11 U				
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-4-6	1/22/2018	851.62	4 - 6 ft	180-74331-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-2-4	1/23/2018	851.62	2 - 4 ft	180-74397-2	Excavated							< 11 U				
Rear Parking Lot	SSHS-B918	SSHS-B918-SUB-8-10	1/18/2018	850.41	8 - 10 ft	180-74307-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-2-4	1/16/2018	850.75	2 - 4 ft	180-74203-2	Excavated							< 12 U				
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-4-6	2/28/2018	853.70	4 - 6 ft	180-75405-1	Not Excavated							< 11 U				
Rear Parking Lot	SSHS-B965	SSHS-B965-SUB-6-8	3/1/2018	851.00	6 - 8 ft	180-75480-1	Excavated							< 12 U				
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.021 U	14	550	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U		7.8	61
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	0.022	12	500 J	0.51 J	< 0.11 U	< 55 U		< 0.3 U		7.3	50
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	0.046	14	670	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U		12	49
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	0.087	14	560	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U		8.4	51
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.016 U	12	530	< 0.45 U	< 0.1 U	< 50 U		< 0.28 U		7.7	49
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	0.04	17	770	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U		14	53
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	0.026 J	7.3	500	< 0.43 U	< 0.097 U	65 J		< 0.26 U		5.1	52
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	0.19	17	530	< 0.46 U	< 0.1 U	< 52 U		< 0.29 U		12	72
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	0.95	100	510	4	0.2 J	71 J		0.56 J		11	98
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	0.038	12	610	< 0.45 U	< 0.1 U	52 J		< 0.28 U		8	38
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	0.041	9.3	480	< 0.44 U	< 0.1 U	57 J		< 0.27 U		5.9	37
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	0.12	14	500	< 0.38 U	< 0.085 U	61 J		< 0.23 U		7.8	42
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	0.052	14	770	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U		10	52
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	0.051	12	570	< 0.39 U	< 0.089 U	51 J		< 0.24 U		7.2	35
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	0.058	13	630	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U		8.3	36
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.019 U	12	580	< 0.32 U	< 0.073 U	56 J		< 0.2 U		7.4	36
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	0.031	10	530	< 0.46 U	< 0.1 U	56 J		< 0.28 U		6.3	39
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	0.025 J	12	500 J	< 0.49 U	< 0.11 U	< 54 U		< 0.3 U		6.6	56
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	0.059	15	500	< 0.45 U	< 0.1 U	59 J		< 0.28 U		9.2	65
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	0.025	12	610	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U		8.5	43
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	0.027 J	10	510 J	< 0.48 U	< 0.11 U	100 J		< 0.3 U		6.7	100
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	0.023 J	12	560	< 0.45 U	< 0.1 U	55 J		< 0.28 U		7.8	46
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	0.21	11.9		1.4	< 1.19 U						62.1
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	0.07	23.4		0.67	< 1.16 U						117
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	1	28.1		< 0.55 U	< 1.12 U						138
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	0.07	9.9		0.85	< 1.15 U						18.5
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	0.74	14.1		< 0.55 U	< 1.11 U						64.7
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	< 0.06 U	12.4		< 0.57 U	< 1.15 U						110
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	8 - 10 ft	1801512611	Not Excavated	0.079	8.3	620	1.4	< 0.069 U	200 J		0.42 J		9.9	32
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	10 - 12 ft	1801512611	Not Excavated	0.24 T	6.7 T	1400 T	1.5 T	< 0.067 UT	360 T		0.31 JT		8.2 T	26 T
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	12 - 14 ft	1801512611	Not Excavated	0.16	9.8	630	2.2	< 0.075 U	230 J		0.50 J		15	30
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	14 - 16 ft	1801512611	Not Excavated	0.066	9.9	710	1.6	< 0.062 U	240 J		0.42 J		12	35

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated			0.02	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated			0.036	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U		< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated			0.029	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated			0.019	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated			0.311	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.035 J	< 0.033 U	0.033 J	< 0.023 U	0.066 J	< 0.14 U	< 0.024 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated			0.9	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.23	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.025 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated			2.13	< 0.021 U	0.044 J	< 0.13 U	0.07 J	< 0.16 U	< 0.13 U	< 0.045 U	0.18	0.15	0.19	0.069 J	0.17	< 0.13 U	< 0.022 U	< 0.027 U	0.66 J	< 0.15 U	< 0.25 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated			0.922	< 0.023 U	< 0.017 U	< 0.14 U	0.03 J	< 0.17 U	< 0.15 U	< 0.049 U	0.079 J	0.074 J	0.082	0.044 J	0.083	< 0.15 U	< 0.025 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated			1.214	< 0.4 U	< 0.4 U		< 0.4 U				0.12 J	0.11 J	0.092 J	0.099 J	0.093 J						
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated			ND	< 0.0073 U	< 0.0088 U	< 0.031 U	< 0.0075 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0096 U	< 0.0077 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.033 U	< 0.052 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated			1.476	< 0.0075 U	< 0.0089 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.035 U	0.1 J	0.087	0.048 J	0.14	0.035 J	0.14	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated			2.18	< 0.0078 U	< 0.0093 U	0.094 J	0.033 J	< 0.04 U	0.045 J	0.14 J	0.11	0.084	0.15	0.037 J	0.14	< 0.027 U	< 0.011 U	< 0.0088 U	< 0.066 U	< 0.035 U	< 0.056 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated			1.228	< 0.0079 U	< 0.0094 U	0.057 J	0.014 J	< 0.04 U	< 0.037 U	0.1 J	0.055 J	0.052 J	0.089	< 0.017 U	0.087	< 0.027 U	< 0.011 U	< 0.0089 U	< 0.067 U	< 0.036 U	< 0.056 U
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	2 - 4 ft	180-116404-1	Not Excavated			12.789	< 0.022 U	0.61	< 0.021 U	0.41	< 0.17 U	0.038 J	< 0.048 U	1.2	1.2	1.5	0.6	1.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	4 - 6 ft	180-116404-3	Not Excavated			3.872	0.027 J	0.12	< 0.021 U	0.13	< 0.17 U	0.017 J	< 0.047 U	0.32	0.33	0.41	0.17	0.28	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated			ND	< 0.36 U	< 0.36 U		< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U						
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated			12.41	< 0.39 U	0.22 J		0.26 J				0.96	1.3	1.9	1.2	0.96						
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated			0.367	< 0.00085 U	0.012	< 0.012 U	0.01	< 0.04 U	< 0.019 U	< 0.026 U	0.032	0.035	0.048	0.022	< 0.00039 U	< 0.013 U	< 0.013 U	< 0.011 U	0.07 J	< 0.016 U	< 0.024 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated			ND	< 0.017 U	< 0.0077 U	< 0.24 U	< 0.017 U	< 0.79 U	< 0.37 U	< 0.5 U	< 0.014 U	< 0.014 U	< 0.013 U	< 0.015 U	< 0.0077 U	< 0.26 U	< 0.26 U	< 0.22 U	< 1.1 U	< 0.31 U	< 0.48 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated			0.48	< 0.017 U	< 0.0079 U	< 0.25 U	< 0.018 U	< 0.81 U	< 0.38 U	< 0.52 U	< 0.014 U	< 0.014 U	< 0.013 U	< 0.015 U	< 0.0079 U	< 0.27 U	< 0.27 U	< 0.23 U	< 1.2 U	< 0.32 U	< 0.5 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated			12.485	0.085 J	0.22	< 0.26 U	0.28	< 0.86 U	< 0.41 U	< 0.55 U	0.86	0.94	1.4	0.52	1	< 0.29 U	< 0.29 U	< 0.24 U	< 1.2 U	< 0.33 U	< 0.53 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated			3.446	< 0.0093 U	0.14	0.16 J	0.096	< 0.44 U	< 0.21 U	< 0.28 U	0.22	0.26	0.34	0.084	0.21	< 0.15 U	< 0.15 U	< 0.12 U	< 0.63 U	< 0.17 U	< 0.27 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated			0.6381	< 0.00087 U	< 0.0004 U	< 0.013 U	< 0.00089 U	< 0.041 U	< 0.019 U	< 0.026 U	0.15	0.021	0.02	< 0.00078 U	0.0091	< 0.014 U	< 0.014 U	< 0.011 U	0.077 J	< 0.016 U	< 0.025 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated			10.426	0.033	0.24	< 0.025 U	0.28	< 0.083 U	< 0.039 U	< 0.053 U	0.92	0.81	1.1	0.45	0.54	< 0.028 U	< 0.028 U	< 0.023 U	< 0.12 U	< 0.032 U	< 0.051 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated			1.45	< 0.0034 U	0.024 J	< 0.05 U	0.036	< 0.16 U	< 0.077 U	< 0.1 U	0.12	0.094	0.13	< 0.0031 U	0.075	< 0.054 U	< 0.054 U	< 0.045 U	< 0.23 U	< 0.063 U	< 0.1 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	2 - 4 ft	180-80106-1	Not Excavated			2.69	< 0.0021 U	0.063	< 0.031 U	0.049	< 0.1 U	< 0.048 U	< 0.065 U	0.24	0.23	0.35	0.1	0.13	< 0.034 U	< 0.034 U	< 0.028 U	< 0.14 U	< 0.04 U	< 0.062 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated			6.336	< 0.0022 U	0.3	0.04 J	0.16	< 0.1 U	< 0.049 U	0.15 J	0.61	0.78	1.2	0.4	0.4	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.04 U	< 0.063 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated			1.414	0.014	0.029	< 0.012 U	0.032	< 0.04 U	0.023 J	< 0.025 U	0.1	0.099	0.17	0.035	0.058	< 0.013 U	< 0.013 U	< 0.011 U	< 0.056 U	< 0.016 U	< 0.024 U
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated			2.135	< 0.00084 U	0.026	< 0.012 U	0.02	< 0.04 U	< 0.019 U	< 0.026 U	0.15	0.35	0.38	0.19	0.13	< 0.013 U	< 0.013 U	< 0.011 U	< 0.057 U	< 0.016 U	< 0.024 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated			1.0015	0.0075	0.021	< 0.012 U	0.026	< 0.039 U	< 0.019 U	< 0.025 U	0.086	0.081	0.13	0.051	0.046	< 0.013 U	< 0.013 U	< 0.011 U	< 0.056 U	< 0.015 U	< 0.024 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated			7.813	< 0.0018 U	0.19	< 0.026 U	0.11	< 0.084 U	< 0.04 U	< 0.054 U	0.7	0.5	1	0.34	0.21	< 0.028 U	< 0.028 U	< 0.023 U	< 0.12 U	< 0.033 U	< 0.051 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated			ND	< 0.0018 U	< 0.00082 U	< 0.026 U	< 0.0018 U	< 0.084 U	< 0.04 U	< 0.054 U	< 0.0015 U	< 0.0015 U	< 0.0014 U	< 0.0016 U	< 0.00082 U	< 0.028 U	< 0.028 U	< 0.023 U	< 0.12 U	< 0.033 U	< 0.051 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated			0.037	< 0.00084 U	< 0.00039 U	< 0.012 U	< 0.00086 U	< 0.04 U	< 0.019 U	< 0.026 U	< 0.0007 U	< 0.00071 U	< 0.00065 U	< 0.00075 U	< 0.00039 U	< 0.013 U	< 0.013 U	< 0.011 U	0.064 J	< 0.016 U	< 0.024 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated			0.6236	0.0041 J	0.014	< 0.013 U	0.015	< 0.041 U	< 0.019 U	< 0.026 U	0.051	0.056	0.083	0.032	0.028	< 0.014 U	< 0.014 U	< 0.011 U	0.062 J	< 0.016 U	< 0.025 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated			1.7129	0.0099	0.036	< 0.013 U	0.044	< 0.042 U	< 0.02 U	< 0.027 U	0.12	0.15	0.24	0.099	0.062	< 0.014 U	< 0.014 U	< 0.012 U	< 0.059 U	< 0.016 U	< 0.026 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated			0.168	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.05 U	0.018 J	0.023 J	0.02 J	< 0.024 U	0.021 J	< 0.019 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated			3.83	< 0.018 U	< 0.0083 U	< 0.26 U	< 0.018 U	< 0.85 U	< 0.4 U	< 0.54 U	0.45	0.23	0.39	< 0.016 U	< 0.0083 U	< 0.28 U	< 0.28 U	< 0.24 U	< 1.2 U	< 0.33 U	< 0.52 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated			0.89	< 0.018 U	< 0.0081 U	< 0.25 U	< 0.018 U	< 0.83 U	< 0.39 U	< 0.53 U	< 0.015 U	< 0.015 U	< 0.014 U	< 0.016 U	< 0.0081 U	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.32 U	< 0.51 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated			1.5	< 0.041 U	< 0.019 U	< 0.6 U	< 0.042 U	< 2 U	< 0.92 U	< 1.2 U	< 0.034 U	< 0.035 U	< 0.032 U	< 0.037 U	< 0.019 U	< 0.65 U	< 0.65 U	< 0.54 U	< 2.8 U	< 0.76 U	< 1.2 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated			0.0175	< 0.0008 U	< 0.00037 U	< 0.012 U	< 0.00082 U	< 0.038 U	< 0.018 U	< 0.024 U	< 0.00066 U	< 0.00067 U	< 0.00062 U	< 0.00072 U	< 0.00037 U	< 0.013 U	< 0.013 U	< 0.011 U	< 0.054 U	< 0.015 U	< 0.023 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated			8.85	0.22	0.071 J	< 0.13 U	0.31	< 0.42 U	< 0.2 U	< 0.27 U	0.53	0.44	0.6	0.17	0.33	< 0.14 U	< 0.14 U	< 0.12 U	< 0.59 U	< 0.16 U	< 0.26 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated			7.03	< 0.018 U	< 0.0081 U	< 0.26 U	0.28	< 0.84 U	< 0.39 U	< 0.53 U	0.46	0.12 J	0.21	< 0.016 U	< 0.0081 U	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.32 U	< 0.51 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated			26.2	0.09	0.22	< 0.068 U	0.46	< 0.22 U	< 0.1 U	< 0.14 U	2.4	3	3.2	1.4	2	< 0.074 U	< 0.074 U	< 0.061 U	< 0.31 U	< 0.086 U	< 0.14 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated			2.278	< 0.0035 U	0.042	< 0.05 U	< 0.0035 U	< 0.16 U	< 0.077 U	< 0.1 U	0.17	0.23	0.27	0.12	0.15	< 0.055 U	< 0.055 U	< 0.045 U	< 0.23 U	< 0.064 U	< 0.1 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated			26.55	< 0.018 U	0.55	< 0.26 U	1.2	< 0.84 U	< 0.4 U	< 0.54 U	2	2.1	2.5	0.91	0.91	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.33 U	< 0.51 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated			19.19	0.31	0.04	< 0.049 U	0.86	< 0.16 U	< 0.076 U	< 0.1 U	1.7	1.2	1.5	0.57	0.57	< 0.054 U	< 0.054 U	< 0.045 U	< 0.23 U	< 0.063 U	< 0.099 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated			409.3	5.2	4.2	< 1.3 U	22	< 4.1 U	< 1.9 U	< 2.6 U	29	13	35	16	5.1	< 1.4 U	< 1.4 U	< 1.1 U	< 5.8 U	< 1.6 U	< 2.5 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/21/2019	855.13	4 - 6 ft	180-90380-1	Excavated			1.326	< 0.022 U	0.051 J	< 0.02 U	0.051 J	< 0.16 U	< 0.016 U		0.11	0.1	0.14	0.057 J	0.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2621	PS-FD-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated			0.679	< 0.022 U	0.038 J	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U		0.076	0.056 J	0.062 J	0.025 J	0.041 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated			0.486	< 0.022 U	0.021 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		0.069 J	0.031 J	0.053 J	< 0.023 U	0.034 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated			0.714	0.041 J	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 R	0.13	0.017 J	0.02 J	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	6 - 8 ft	180-90380-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U		< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	14 - 16 ft	180-90275-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 R	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated			2.129	< 0.023 U	0.046 J	< 0.021 U	0.051 J	< 0.17 U	< 0.016 U		0.2	0.17	0.2	0.077 J	0.14	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated			77.25	0.63	1.3	< 0.041 U	2.7	< 0.33 U	0.59 J	< 0.093 U	4.8	3.6	4.9	2.4	4.6	< 0.036 U	< 0.027 U	< 0.056 U	< 0.8 U	< 0.052 U	< 0.52 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated			78.65	0.74 J	1.6 J	< 0.083 U	2.9 J	< 0.67 U	0.84 J	< 0.19 U	5.7 J	4.8 J	5.4 J	1.4 J	2.8 J	< 0.073 U	< 0.055 U	< 0.11 U	< 1.6 U	< 0.11 U	< 1 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated			7.28	0.038 J	0.13 J	< 0.02 U	0.29 J	< 0.16 U	0.052 J	< 0.045 U	0.48 J	0.42 J	0.52 J	0.2 J	0.38 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated			0.208	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	0.027 J	0.022 J	0.026 J	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated			1.467	< 0.044 U	< 0.033 U	< 0.041 U	< 0.039 U	< 0.33 U	< 0.032 U	< 0.094 U	0.12 J	0.1 J	0.15	0.064 J	0.2 J	< 0.036 U	< 0.028 U	< 0.056 U	< 0.81 U	< 0.053 U	< 0.52 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated			1.193	< 0.021 U	< 0.016 U	< 0.02 U	0.028 J	< 0.16 U	< 0.015 U	< 0.046 U	0.11	0.1	0.15	0.03 J	0.093 J	< 0.018 U	< 0.014 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated			14.17	< 0.043 U	0.44	< 0.04 U	0.32	< 0.33 U	< 0.031 U	< 0.092 U	1.2	1.5	2.1	0.41	1.4	< 0.035 U	< 0.027 U	< 0.055 U	< 0.79 U	< 0.052 U	< 0.51 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	0.28 J	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.3 J	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.048 J	< 0.049 U	< 0.14 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.43 U	< 0.8 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.41	< 0.052 U	< 0.15 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.45 U	< 0.85 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.23 U	0.024 JT	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.19	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.4 U	< 0.75 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.26 U	< 0.019 UT	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.084	< 0.051 U	< 0.15 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.44 U	< 0.83 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated								0.13 J	< 0.4 U	< 0.4 U										
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.007 U	< 0.031 U	< 0.035 U	< 0.008 U	< 0.031 U	< 0.042 U	< 0.0091 U	< 0.0085 U	< 0.038 U	< 0.04 U	< 0.0077 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.46 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.0072 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	0.23	< 0.0087 U	0.072 J	< 0.041 U	< 0.0078 U	< 0.043 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.31 U	< 0.0075 U	< 0.033 U	< 0.037 U	< 0.0085 U	< 0.033 U	< 0.045 U	0.31	0.041 J	0.13 J	< 0.043 U	< 0.0082 U	< 0.044 U	< 0.064 U	< 0.044 U	< 0.051 U	< 0.043 U	< 0.16 U	< 0.042 U	< 0.48 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.31 U	< 0.0076 U	< 0.033 U	< 0.038 U	< 0.0086 U	< 0.034 U	< 0.046 U	0.19	< 0.0092 U	0.079 J	< 0.044 U	< 0.0083 U	0.077 J	< 0.064 U	< 0.045 U	< 0.052 U	< 0.043 U	< 0.17 U	< 0.042 U	< 0.49 U
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	2 - 4 ft	180-116404-1	Not Excavated	< 0.25 U	0.086	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	1.2	0.28	0.065 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	4 - 6 ft	180-116404-3	Not Excavated	< 0.25 U	0.033 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.33	0.065 J	0.03 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated								< 0.36 U	< 0.36 U	< 0.36 U										
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated								1.5	0.36 J	< 0.39 U										
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	0.037	< 0.00073 U	< 0.014 U	< 0.048 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.016 U	< 0.024 U	< 0.031 U	< 0.089 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 1.6 U	< 0.42 U	< 0.66 U	< 0.99 U	< 0.31 U	< 0.22 U	< 0.31 U	< 0.024 U	< 0.014 U	< 0.29 U	< 0.94 U	< 0.97 U	< 0.68 U	< 0.88 U	< 0.31 U	< 0.48 U	< 0.61 U	< 1.8 U	< 1.2 U	< 3.1 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	< 1.7 U	< 0.43 U	< 0.68 U	< 1 U	< 0.32 U	< 0.23 U	< 0.32 U	0.22	< 0.015 U	< 0.29 U	< 0.97 U	< 0.99 U	< 0.7 U	< 0.9 U	< 0.32 U	< 0.5 U	< 0.63 U	< 1.8 U	< 1.3 U	< 3.2 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated	< 1.8 U	< 0.45 U	< 0.72 U	< 1.1 U	< 0.33 U	< 0.24 U	< 0.33 U	1.1	0.35	< 0.31 U	< 1 U	< 1.1 U	< 0.74 U	< 0.96 U	< 0.33 U	< 0.53 U	< 0.67 U	< 1.9 U	< 1.3 U	< 3.4 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	< 0.92 U	< 0.23 U	< 0.37 U	< 0.55 U	< 0.17 U	< 0.12 U	< 0.17 U	0.26	< 0.0081 U	< 0.16 U	< 0.53 U	< 0.54 U	< 0.38 U	< 0.49 U	< 0.17 U	< 0.27 U	< 0.34 U	< 0.98 U	< 0.69 U	< 1.7 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.086 U	< 0.022 U	< 0.034 U	< 0.052 U	< 0.016 U	< 0.011 U	< 0.016 U	0.26	< 0.00076 U	< 0.015 U	< 0.049 U	< 0.05 U	< 0.035 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.064 U	< 0.16 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated	< 0.17 U	0.066 J	< 0.069 U	< 0.1 U	< 0.032 U	< 0.023 U	< 0.032 U	0.88	0.14	0.1 J	< 0.099 U	< 0.1 U	< 0.072 U	< 0.092 U	< 0.032 U	< 0.051 U	< 0.065 U	< 0.18 U	< 0.13 U	< 0.33 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated	< 0.34 U	< 0.086 U	< 0.14 U	< 0.2 U	< 0.063 U	< 0.045 U	< 0.063 U	0.21	< 0.003 U	< 0.059 U	< 0.19 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.063 U	< 0.1 U	< 0.13 U	< 0.36 U	< 0.25 U	< 0.64 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	2 - 4 ft	180-80106-1	Not Excavated	< 0.21 U	< 0.054 U	< 0.085 U	< 0.13 U	< 0.04 U	< 0.028 U	< 0.04 U	0.33	0.046	< 0.037 U	< 0.12 U	< 0.12 U	< 0.088 U	< 0.11 U	< 0.04 U	< 0.062 U	< 0.079 U	< 0.23 U	< 0.16 U	< 0.4 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated	< 0.22 U	< 0.055 U	< 0.086 U	< 0.13 U	< 0.04 U	< 0.029 U	< 0.04 U	0.61	0.15	< 0.037 U	< 0.12 U	< 0.13 U	< 0.089 U	< 0.12 U	< 0.04 U	< 0.063 U	< 0.081 U	< 0.23 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	0.12	0.015	0.039 J	< 0.048 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.016 U	< 0.024 U	< 0.031 U	< 0.089 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	0.21	< 0.00073 U	< 0.014 U	< 0.048 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.016 U	< 0.024 U	< 0.031 U	< 0.089 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated	< 0.082 U	< 0.021 U	< 0.033 U	< 0.049 U	< 0.015 U	< 0.011 U	< 0.015 U	0.11	< 0.00072 U	< 0.014 U	< 0.047 U	< 0.048 U	< 0.034 U	< 0.044 U	< 0.015 U	< 0.024 U	< 0.031 U	< 0.088 U	< 0.061 U	< 0.16 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated	< 0.17 U	< 0.044 U	< 0.07 U	< 0.1 U	< 0.033 U	< 0.023 U	< 0.033 U	0.8	0.088	< 0.03 U	< 0.1 U	< 0.1 U	< 0.072 U	< 0.093 U	< 0.033 U	< 0.051 U	< 0.065 U	< 0.19 U	< 0.13 U	< 0.33 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.18 U	< 0.044 U	< 0.07 U	< 0.11 U	< 0.033 U	< 0.023 U	< 0.033 U	< 0.0026 U	< 0.0015 U	< 0.03 U	< 0.1 U	< 0.1 U	< 0.072 U	< 0.093 U	< 0.033 U	< 0.051 U	< 0.065 U	< 0.19 U	< 0.13 U	< 0.33 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.0012 U	< 0.00073 U	< 0.014 U	< 0.048 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.016 U	< 0.024 U	< 0.031 U	< 0.089 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated	< 0.086 U	< 0.022 U	< 0.034 U	< 0.052 U	< 0.016 U	< 0.011 U	< 0.016 U	0.063	< 0.00076 U	< 0.015 U	< 0.049 U	< 0.05 U	< 0.035 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.064 U	< 0.16 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated	< 0.087 U	< 0.022 U	< 0.035 U	< 0.052 U	< 0.016 U	< 0.012 U	< 0.016 U	0.19	< 0.00077 U	0.03 J	< 0.05 U	< 0.051 U	< 0.036 U	< 0.047 U	< 0.016 U	< 0.026 U	< 0.033 U	< 0.093 U	< 0.065 U	< 0.17 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.021 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	< 1.8 U	< 0.45 U	< 0.71 U	< 1.1 U	< 0.33 U	< 0.24 U	< 0.33 U	0.63	< 0.016 U	< 0.31 U	< 1 U	< 1 U	< 0.73 U	< 0.94 U	< 0.33 U	< 0.52 U	< 0.66 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	< 1.7 U	< 0.44 U	< 0.69 U	< 1 U	< 0.32 U	< 0.23 U	< 0.32 U	< 0.025 U	< 0.015 U	< 0.3 U	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.32 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	< 4.1 U	< 1 U	< 1.6 U	< 2.4 U	< 0.76 U	< 0.54 U	< 0.76 U	< 0.06 U	< 0.036 U	< 0.71 U	< 2.3 U	< 2.4 U	< 1.7 U	< 2.2 U	< 0.76 U	< 1.2 U	< 1.5 U	< 4.3 U	< 3 U	< 7.7 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.079 U	< 0.02 U	< 0.032 U	< 0.047 U	< 0.015 U	< 0.011 U	< 0.015 U	< 0.0012 U	< 0.0007 U	< 0.014 U	< 0.045 U	< 0.046 U	< 0.033 U	< 0.042 U	< 0.015 U	< 0.023 U	< 0.03 U	< 0.084 U	< 0.059 U	< 0.15 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	< 0.87 U	< 0.22 U	< 0.35 U	< 0.52 U	< 0.16 U	< 0.12 U	< 0.16 U	0.78	0.12	< 0.15 U	< 0.5 U	< 0.51 U	< 0.36 U	< 0.47 U	< 0.16 U	< 0.26 U	< 0.33 U	< 0.93 U	< 0.65 U	< 1.7 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	< 1.7 U	< 0.44 U	< 0.7 U	< 1 U	< 0.32 U	< 0.23 U	< 0.32 U	0.72	< 0.015 U	< 0.3 U	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.32 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	< 0.46 U	< 0.12 U	< 0.18 U	< 0.28 U	< 0.086 U	< 0.061 U	< 0.086 U	2.3	0.39	0.16 J	< 0.26 U	< 0.27 U	< 0.19 U	< 0.25 U	< 0.086 U	< 0.14 U	< 0.17 U	< 0.49 U	< 0.34 U	< 0.87 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	< 0.34 U	< 0.086 U	< 0.14 U	< 0.2 U	< 0.064 U	< 0.045 U	< 0.064 U	0.22	< 0.003 U	< 0.059 U	< 0.2 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.064 U	< 0.1 U	< 0.13 U	< 0.36 U	< 0.25 U	< 0.64 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	< 1.7 U	0.45 J	< 0.7 U	< 1 U	< 0.33 U	< 0.23 U	< 0.33 U	2.1	< 0.015 U	< 0.3 U	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.33 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated	< 0.34 U	0.3	< 0.13 U	< 0.2 U	< 0.063 U	< 0.045 U	< 0.063 U	1.6	0.2	0.23	< 0.19 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.063 U	< 0.099 U	< 0.13 U	< 0.36 U	< 0.25 U	< 0.64 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated	< 8.5 U	7.3	< 3.4 U	< 5.1 U	< 1.6 U	< 1.1 U	< 1.6 U	28	< 0.075 U	8.3	< 4.9 U	< 5 U	< 3.5 U	< 4.6 U	< 1.6 U	< 2.5 U	< 3.2 U	< 9.1 U	< 6.4 U	< 16 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/21/2019	855.13	4 - 6 ft	180-90380-1	Excavated	< 0.24 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.12	0.033 J	0.019 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2621	PS-FD-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.16	< 0.017 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.11	< 0.017 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.21	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	6 - 8 ft	180-90380-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	14 - 16 ft	180-90275-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.96 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.22	0.048 J	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	< 0.49 U	0.71	< 0.025 U	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	5.1	0.92	2.5	< 0.7 U	< 0.058 U	< 0.26 U	0.074 J	< 0.027 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.046 U	< 2 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.99 U	0.8 J	< 0.051 U	< 0.072 U	< 0.07 U	< 0.071 U	< 0.092 U	5.6 J	0.71 J	3.2 J	< 1.4 U	< 0.12 U	< 0.53 U	< 0.094 U	< 0.055 U	< 0.67 U	< 0.88 U	< 2.6 U	< 0.094 U	< 4.1 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.24 U	0.086 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.55 J	0.092 J	0.15 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 0.98 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated	< 0.24 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.027 J	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.49 U	< 0.036 U	< 0.025 U	< 0.036 U	< 0.035 U	< 0.035 U	< 0.046 U	0.2	< 0.034 U	< 0.033 U	< 0.71 U	< 0.059 U	< 0.27 U	< 0.047 U	< 0.028 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.047 U	< 2 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.14	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated	< 0.48 U	0.064 J	< 0.025 U	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	1.2	0.31	0.083 J	< 0.69 U	< 0.057 U	< 0.26 U	< 0.046 U	< 0.027 U	< 0.33 U	< 0.43 U	< 1.3 U	< 0.046 U	< 2 U

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.23 U	< 0.12 UT			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.23 U		< 0.24 U		0.024 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.1 U	< 0.14 U	< 0.038 U	< 0.11 U		< 0.14 U	0.045 J
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated	< 0.24 U		< 0.26 U		< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.11 U	< 0.14 U	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.21 U		< 0.23 U		0.38	0.029 J	< 0.026 U	< 0.021 U	< 0.097 U	< 0.13 U	0.13	< 0.1 U		< 0.13 U	0.025 J
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.24 U		< 0.25 U		0.15	< 0.016 U	< 0.029 U	< 0.023 U	< 0.11 U	< 0.14 U	0.059 J	< 0.11 U		< 0.15 U	< 0.019 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated					0.19 J	< 0.4 U	< 0.4 U				0.076 J	< 0.4 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.044 U	< 0.0082 U	< 0.01 U	< 0.0081 U	< 0.0086 U	< 0.041 U	< 0.027 U	< 0.0079 U	< 0.027 U		< 0.029 U	< 0.0069 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.045 U	0.14	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U	0.046 J	< 0.027 U		< 0.029 U	0.2
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.033 U			< 0.047 U	0.16	< 0.011 U	< 0.0087 U	< 0.0091 U	< 0.044 U	< 0.029 U	0.065 J	< 0.028 U		< 0.031 U	0.37
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.033 U			< 0.047 U	0.077 J	< 0.011 U	< 0.0088 U	< 0.0092 U	< 0.044 U	< 0.03 U	0.025 J	< 0.029 U		< 0.031 U	0.25
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	2 - 4 ft	180-116404-1	Not Excavated	< 0.059 U			< 0.12 U	1.6	0.059 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.94	< 0.11 U	< 0.11 U	< 0.02 U	0.14
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	4 - 6 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.56	0.033 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.23	< 0.11 U	< 0.11 U	< 0.019 U	0.05 J
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated					< 0.36 U	< 0.36 U	< 0.36 U				< 0.36 U	< 0.36 U			
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated					1.1	< 0.39 U	< 0.39 U				0.87	< 0.39 U			
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated	< 0.069 U			< 0.017 U	0.064	< 0.00059 U	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U	0.015	< 0.034 U	< 0.032 U	< 0.013 U	0.023
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 1.4 U			< 0.33 U	< 0.012 U	< 0.012 U	< 0.046 U	< 0.26 U	< 1.4 U	< 0.2 U	< 0.0077 U	< 0.68 U	< 0.64 U	< 0.26 U	< 0.011 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	< 1.4 U			< 0.34 U	< 0.012 U	< 0.012 U	< 0.047 U	< 0.27 U	< 1.4 U	< 0.2 U	< 0.0079 U	< 0.7 U	< 0.66 U	< 0.27 U	< 0.011 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated	< 1.5 U			< 0.36 U	1.4	0.2	< 0.05 U	< 0.29 U	< 1.5 U	< 0.22 U	0.81	< 0.74 U	< 0.69 U	< 0.29 U	0.29
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	< 0.76 U			< 0.18 U	0.48	0.096	< 0.026 U	< 0.15 U	< 0.76 U	< 0.11 U	0.17	< 0.38 U	< 0.36 U	< 0.15 U	0.22
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.071 U			< 0.017 U	< 0.00063 U	< 0.00061 U	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	< 0.0004 U	< 0.035 U	< 0.033 U	< 0.014 U	< 0.00057 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated	< 0.14 U			< 0.035 U	2	0.053	< 0.0048 U	< 0.028 U	< 0.14 U	< 0.021 U	0.49	< 0.072 U	< 0.067 U	< 0.028 U	0.07
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated	< 0.28 U			< 0.068 U	0.2	0.018 J	< 0.0095 U	< 0.054 U	< 0.28 U	< 0.041 U	0.06	< 0.14 U	< 0.13 U	< 0.054 U	0.12
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	2 - 4 ft	180-80106-1	Not Excavated	< 0.18 U			< 0.042 U	0.43	0.013 J	< 0.0059 U	< 0.034 U	< 0.18 U	< 0.025 U	0.12	< 0.088 U	< 0.082 U	< 0.034 U	0.062
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated	< 0.18 U			< 0.043 U	0.68	0.024	< 0.0061 U	< 0.035 U	< 0.18 U	< 0.026 U	0.45	< 0.089 U	< 0.084 U	< 0.035 U	0.036
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated	< 0.069 U			< 0.017 U	0.28	0.013	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U	0.054	< 0.034 U	< 0.032 U	< 0.013 U	0.1
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated	< 0.069 U			< 0.017 U	0.2	< 0.00059 U	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U	0.14	< 0.034 U	< 0.032 U	< 0.013 U	0.015
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated	< 0.068 U			< 0.016 U	0.17	0.008	< 0.0023 U	< 0.013 U	< 0.068 U	< 0.0099 U	0.041	< 0.034 U	< 0.032 U	< 0.013 U	0.018
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated	< 0.14 U			< 0.035 U	1.9	< 0.0012 U	< 0.0049 U	< 0.028 U	< 0.14 U	< 0.021 U	0.23	< 0.072 U	< 0.068 U	< 0.028 U	0.039
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.14 U			< 0.035 U	< 0.0013 U	< 0.0012 U	< 0.0049 U	< 0.028 U	< 0.14 U	< 0.021 U	< 0.00082 U	< 0.072 U	< 0.068 U	< 0.028 U	< 0.0012 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	< 0.069 U			< 0.017 U	< 0.00061 U	< 0.00059 U	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U	< 0.00039 U	< 0.034 U	< 0.032 U	< 0.013 U	< 0.00055 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated	< 0.071 U			< 0.017 U	0.097	0.0085	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U	0.026	< 0.035 U	< 0.033 U	< 0.014 U	0.018
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated	< 0.072 U			< 0.017 U	0.24	< 0.00062 U	< 0.0024 U	< 0.014 U	< 0.072 U	< 0.01 U	0.058	< 0.036 U	< 0.034 U	< 0.014 U	0.078
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	< 0.02 U			< 0.12 U	0.021 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.016 U	< 0.11 U		< 0.02 U	< 0.019 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	< 1.5 U			< 0.35 U	0.58	< 0.012 U	< 0.05 U	< 0.28 U	< 1.5 U	< 0.21 U	0.11 J	< 0.73 U	< 0.68 U	< 0.28 U	0.26
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	< 1.4 U			< 0.35 U	< 0.013 U	< 0.012 U	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U	< 0.0081 U	< 0.72 U	< 0.67 U	< 0.28 U	1.5
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	< 3.4 U			< 0.81 U	< 0.03 U	< 0.029 U	< 0.11 U	< 0.65 U	< 3.4 U	< 0.49 U	< 0.019 U	< 1.7 U	< 1.6 U	< 0.65 U	1.6
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.065 U			< 0.016 U	< 0.00058 U	< 0.00056 U	< 0.0022 U	< 0.013 U	< 0.065 U	< 0.0095 U	< 0.00037 U	< 0.033 U	< 0.031 U	< 0.013 U	< 0.00053 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	< 0.72 U			< 0.17 U	0.99	0.22	< 0.024 U	< 0.14 U	< 0.72 U	< 0.1 U	0.28	< 0.36 U	< 0.34 U	< 0.14 U	0.43
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	< 1.4 U			< 0.35 U	0.76	< 0.012 U	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U	< 0.0081 U	< 0.72 U	0.78 J	< 0.28 U	0.62
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	< 0.38 U			< 0.092 U	3.1	0.21	< 0.013 U	< 0.074 U	< 0.38 U	< 0.055 U	1.5	< 0.19 U	0.21 J	< 0.074 U	0.35
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	< 0.28 U			< 0.068 U	0.27	< 0.0024 U	< 0.0095 U	< 0.055 U	< 0.28 U	< 0.041 U	0.13	< 0.14 U	< 0.13 U	< 0.055 U	0.076
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	< 1.4 U			< 0.35 U	4.7	0.54	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U	0.87	< 0.72 U	< 0.67 U	< 0.28 U	0.38
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated	< 0.28 U			< 0.067 U	3.5	0.34	< 0.0094 U	< 0.054 U	< 0.28 U	< 0.04 U	0.54	< 0.14 U	< 0.13 U	< 0.054 U	0.15
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated	< 7.1 U			< 1.7 U	89	14	< 0.24 U	< 1.4 U	< 7.1 U	< 1 U	5.9	< 3.5 U	< 3.3 U	< 1.4 U	3
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/21/2019	855.13	4 - 6 ft	180-90380-1	Excavated	< 0.019 U			< 0.12 U	0.18	0.016 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.084	< 0.11 U	< 0.11 U	< 0.019 U	0.072 J
Football Field	SSHS-B2621	PS-FD-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated	< 0.019 U			< 0.12 U	0.065 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.048 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated	< 0.019 U			< 0.12 U	0.043 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.025 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	< 0.018 U			< 0.11 U	0.066 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	6 - 8 ft	180-90380-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	14 - 16 ft	180-90275-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.02 U			< 0.12 U	0.3	0.016 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.12	< 0.11 U		< 0.02 U	< 0.019 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	< 0.037 U			< 0.23 U	17	2	< 0.054 U	< 0.044 U	< 0.077 U	< 0.039 U	4	< 0.22 U	< 0.22 U	< 0.038 U	1.3
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.076 U			< 0.47 U	19 J	2.5 J	< 0.11 U	< 0.089 U	< 0.16 U	< 0.078 U	2.3 J	< 0.44 U	< 0.45 U	< 0.078 U	1.6 J
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.018 U			< 0.11 U	1.4 J	0.15 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.3 J	< 0.1 U	< 0.11 U	< 0.019 U	0.26 J
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated	< 0.019 U			< 0.12 U	0.037 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.038 U			< 0.24 U	0.2	< 0.03 U	< 0.054 U	< 0.044 U	< 0.078 U	< 0.039 U	0.093 J	< 0.22 U	< 0.22 U	< 0.039 U	< 0.036 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.018 U			< 0.11 U	0.18	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.073 J	< 0.11 U	< 0.11 U	< 0.019 U	0.026 J
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated	< 0.037 U			< 0.23 U	1.9	< 0.029 U	< 0.053 U	< 0.044 U	< 0.076 U	< 0.038 U	1.2	< 0.21 U	< 0.22 U	< 0.038 U	0.058 J

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.02 J	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.036 J	< 0.12 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.029 J	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.019 J		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.11 U	0.03 J	< 0.18 U	< 0.098 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.034 J	< 0.12 U	0.041 J		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	0.26		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.11 U	0.072	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.13	< 0.11 U	0.37		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.12 U	0.032 J	< 0.18 U	< 0.1 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.065 J	< 0.12 U	0.14		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	< 0.4 U	< 0.4 U										< 0.97 U	0.094 J	< 0.4 U	0.21 J					
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.037 U	< 0.0066 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.009 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U		< 0.029 U	< 0.025 U	< 0.041 U	< 0.057 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.038 U	0.1	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	0.4 J	< 0.0092 U	0.11		< 0.03 U	< 0.025 U	< 0.042 U	< 0.058 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.04 U	0.14	< 0.18 U	< 0.17 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0095 U	< 0.038 U	< 0.036 U	0.77 J	< 0.0096 U	0.14		< 0.031 U	< 0.026 U	< 0.043 U	< 0.061 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.04 U	0.11	< 0.18 U	< 0.17 U	< 0.17 U	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0097 U	< 0.038 U	< 0.037 U	0.44	< 0.0097 U	0.089		< 0.031 U	< 0.026 U	< 0.044 U	< 0.062 U
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	2 - 4 ft	180-116404-1	Not Excavated		0.32	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.58	< 0.12 U	1.8		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	4 - 6 ft	180-116404-3	Not Excavated		0.097	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.34	< 0.12 U	0.55		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	< 0.36 U	< 0.36 U										< 0.88 U	< 0.36 U	< 0.36 U	< 0.36 U					
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	< 0.39 U	0.06 J										< 0.93 U	0.24 J	< 0.39 U	1.7					
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	2 - 4 ft	180-80225-3	Not Excavated		0.026	< 0.044 U	< 0.055 U	< 0.067 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.065 U	0.036	< 0.0089 U	0.042		< 0.016 U	< 0.33 U	< 0.077 U	< 0.071 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated		< 0.018 U	< 0.88 U	< 1.1 U	< 1.3 U	< 0.29 U	< 0.29 U	< 2.1 U		< 0.24 U	< 0.26 U	< 1.3 U	< 0.016 U	< 0.18 U	< 0.0097 U		< 0.31 U	< 6.4 U	< 1.5 U	< 1.4 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated		< 0.019 U	< 0.9 U	< 1.1 U	< 1.4 U	< 0.29 U	< 0.29 U	< 2.1 U		< 0.25 U	< 0.27 U	< 1.3 U	< 0.016 U	< 0.18 U	0.26		< 0.32 U	< 6.6 U	< 1.6 U	< 1.4 U
Football Field	SSHS-B2052	SSHS-B2052-SUB-2-4	7/25/2018	855.59	2 - 4 ft	180-80154-2	Excavated		0.64	< 0.96 U	< 1.2 U	< 1.4 U	< 0.31 U	< 0.31 U	< 2.2 U		< 0.26 U	< 0.29 U	< 1.4 U	1.3	< 0.19 U	1.6		< 0.33 U	< 7 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated		0.4	< 0.49 U	< 0.6 U	< 0.74 U	< 0.16 U	< 0.16 U	< 1.2 U		< 0.14 U	< 0.15 U	< 0.71 U	0.43	0.21 J	0.4		< 0.17 U	< 3.6 U	< 0.85 U	< 0.79 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated		< 0.00094 U	< 0.046 U	< 0.056 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.018	< 0.0092 U	0.16		< 0.016 U	< 0.34 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-2-4	7/24/2018	855.07	2 - 4 ft	180-80106-3	Excavated		0.23	< 0.092 U	< 0.11 U	< 0.14 U	< 0.03 U	< 0.03 U	< 0.22 U		< 0.025 U	< 0.028 U	< 0.13 U	1.1	< 0.018 U	1.4		< 0.032 U	< 0.68 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-2-4	7/24/2018	854.94	2 - 4 ft	180-80106-2	Excavated		0.087	< 0.18 U	< 0.22 U	< 0.27 U	< 0.059 U	< 0.059 U	< 0.43 U		< 0.05 U	< 0.054 U	< 0.26 U	0.25	< 0.036 U	0.17		< 0.063 U	< 1.3 U	< 0.31 U	< 0.29 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	2 - 4 ft	180-80106-1	Not Excavated		0.072	< 0.11 U	< 0.14 U	< 0.17 U	< 0.037 U	< 0.037 U	< 0.27 U		< 0.031 U	< 0.034 U	< 0.16 U	0.21	< 0.023 U	0.37		< 0.04 U	< 0.83 U	< 0.19 U	< 0.18 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-2-4	7/24/2018	855.99	2 - 4 ft	180-80106-2	Excavated		0.072	< 0.12 U	< 0.14 U	< 0.17 U	< 0.037 U	< 0.037 U	< 0.27 U		< 0.032 U	< 0.035 U	< 0.17 U	0.22	< 0.023 U	0.58		< 0.04 U	< 0.84 U	< 0.2 U	< 0.18 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-2-4	7/24/2018	855.74	2 - 4 ft	180-80105-3	Excavated		0.094	< 0.044 U	< 0.054 U	< 0.066 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.064 U	0.15	< 0.0089 U	0.18		< 0.016 U	< 0.32 U	< 0.076 U	< 0.071 U
Football Field	SSHS-B2190	PS-FD-55	7/27/2018	856.06	2 - 4 ft	180-80252-2	Excavated		< 0.00091 U	< 0.044 U	< 0.054 U	< 0.067 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.064 U	0.055	< 0.0089 U	0.31		< 0.016 U	< 0.33 U	< 0.077 U	< 0.071 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-2-4	7/27/2018	856.06	2 - 4 ft	180-80252-1	Excavated		0.025	< 0.044 U	< 0.054 U	< 0.066 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.063 U	0.1	< 0.0088 U	0.12		< 0.015 U	< 0.32 U	< 0.076 U	< 0.07 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-2-4	7/24/2018	856.18	2 - 4 ft	180-80105-3	Excavated		0.055	< 0.093 U	< 0.11 U	< 0.14 U	< 0.03 U	< 0.03 U	< 0.22 U		< 0.026 U	< 0.028 U	< 0.14 U	0.68	< 0.019 U	1.2		< 0.033 U	< 0.68 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated		< 0.0019 U	< 0.093 U	< 0.11 U	< 0.14 U	< 0.03 U	< 0.03 U	< 0.22 U		< 0.026 U	< 0.028 U	< 0.14 U	< 0.0017 U	< 0.019 U	< 0.001 U		< 0.033 U	< 0.68 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated		< 0.00091 U	< 0.044 U	< 0.054 U	< 0.067 U	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.064 U	< 0.00081 U	< 0.0089 U	0.037		< 0.016 U	< 0.32 U	< 0.077 U	< 0.071 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	2 - 4 ft	180-80105-1	Not Excavated		0.013	< 0.046 U	< 0.056 U	< 0.069 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.063	< 0.0092 U	0.084		< 0.016 U	< 0.34 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-2-4	7/24/2018	855.05	2 - 4 ft	180-80105-2	Excavated		0.1	< 0.047 U	< 0.057 U	< 0.07 U	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.068 U	0.18	< 0.0093 U	0.22		< 0.016 U	< 0.34 U	< 0.08 U	< 0.075 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.024 J	< 0.12 U	0.02 J		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated		0.11 J	< 0.94 U	< 1.2 U	< 1.4 U	< 0.31 U	< 0.31 U	< 2.2 U		< 0.26 U	< 0.28 U	< 1.4 U	0.63	< 0.19 U	0.7		< 0.33 U	< 6.9 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated		< 0.019 U	< 0.93 U	< 1.1 U	< 1.4 U	< 0.3 U	< 0.3 U	< 2.2 U		< 0.25 U	< 0.28 U	< 1.3 U	0.58	< 0.19 U	0.31		< 0.32 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated		< 0.044 U	< 2.2 U	< 2.7 U	< 3.3 U	< 0.71 U	< 0.71 U	< 5.1 U		< 0.6 U	< 0.65 U	< 3.1 U	1.5	< 0.43 U	< 0.024 U		< 0.76 U	< 16 U	< 3.7 U	< 3.5 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated		< 0.00086 U	< 0.042 U	< 0.052 U	< 0.063 U	< 0.014 U	< 0.014 U	< 0.099 U		< 0.012 U	< 0.013 U	< 0.061 U	0.0055 J	< 0.0084 U	0.012		< 0.015 U	< 0.31 U	< 0.073 U	< 0.067 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated		0.26	< 0.47 U	< 0.57 U	< 0.7 U	< 0.15 U	< 0.15 U	< 1.1 U		< 0.13 U	< 0.14 U	< 0.68 U	2	< 0.093 U	1.6		< 0.16 U	< 3.4 U	< 0.8 U	< 0.75 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated		0.28	< 0.93 U	< 1.1 U	< 1.4 U	< 0.3 U	< 0.3 U	< 2.2 U		< 0.26 U	< 0.28 U	< 1.3 U	2.2	< 0.19 U	2		< 0.32 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated		0.75	< 0.25 U	< 0.3 U	< 0.37 U	< 0.08 U	< 0.08 U	< 0.58 U		< 0.068 U	< 0.074 U	< 0.36 U	1.6	0.13 J	3.8		< 0.086 U	< 1.8 U	< 0.42 U	< 0.39 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated		0.098	< 0.18 U	< 0.22 U	< 0.27 U	< 0.059 U	< 0.059 U	< 0.43 U		< 0.05 U	< 0.055 U	< 0.26 U	0.27	< 0.036 U	0.35		< 0.064 U	< 1.3 U	< 0.31 U	< 0.29 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated		0.52	< 0.93 U	< 1.1 U	< 1.4 U	< 0.3 U	< 0.3 U	< 2.2 U		< 0.26 U	< 0.28 U	< 1.3 U	4	< 0.19 U	4.2		< 0.33 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-2-4	7/24/2018	855.25	2 - 4 ft	180-80106-1	Excavated		0.2	< 0.18 U	< 0.22 U	< 0.27 U	< 0.058 U	< 0.058 U	< 0.42 U		< 0.049 U	< 0.054 U	< 0.26 U	3.3	< 0.036 U	2.8		< 0.063 U	< 1.3 U	< 0.31 U	< 0.29 U
Football Field	SSHS-B2246	SSHS-B2246-SUB-2-4	7/26/2018	855.24	2 - 4 ft	180-80225-1	Excavated		2.1	< 4.6 U	< 5.6 U	< 6.8 U	< 1.5 U	< 1.5 U	< 11 U		< 1.3 U	< 1.4 U	< 6.6 U	96	< 0.91 U	49		< 1.6 U	< 33 U	< 7.9 U	< 7.3 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/21/2019	855.13	4 - 6 ft	180-90380-1	Excavated		0.045 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.13	< 0.11 U	0.16		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2621	PS-FD-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.036 J	< 0.11 U	0.11		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/17/2019	855.04	6 - 8 ft	180-90275-1	Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.036 J	< 0.11 U	0.085		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.23		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	6 - 8 ft	180-90380-1	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	14 - 16 ft	180-90275-1	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.12 U	0.017 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.19	< 0.12 U	0.38		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated		3.9	< 0.34 U	< 0.19 U	< 0.036 U	< 0.27 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	8.7	< 0.23 U	12		< 0.032 U	< 0.31 U	< 0.054 U	< 0.041 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated		4.4 J	< 0.69 U	< 0.39 U	< 0.074 U	< 0.56 U	< 0.24 U	< 1.1 U		< 0.1 U	< 0.51 U	< 2.4 U	8.4 J	< 0.46 U	12 J		< 0.066 U	< 0.63 U	< 0.11 U	< 0.083 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated		0.38 J	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.88 J	< 0.11 U	1.2 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.033 J	< 0.11 U	0.036 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated		< 0.03 U	< 0.35 U	< 0.19 U	< 0.037 U	< 0.28 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	0.13 J	< 0.23 U	0.21		< 0.033 U	< 0.32 U	< 0.054 U	< 0.042 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated		0.019 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.1	< 0.11 U	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated		0.23	< 0.34 U	< 0.19 U	< 0.036 U	< 0.27 U	< 0.12 U	< 0.52 U		< 0.05 U	< 0.25 U	< 1.2 U	0.6	< 0.23 U	1.8		< 0.032 U	< 0.31 U	< 0.053 U	< 0.041 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 R	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated			6.33	< 0.042 U	0.22	< 0.039 U	0.19	< 0.32 U	< 0.03 U	< 0.09 U	0.59	0.53	0.71	0.24	0.51	< 0.035 U	< 0.026 U	< 0.054 U	< 0.77 U	< 0.051 U	< 0.5 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated			0.543	< 0.02 U	< 0.015 U	< 0.019 U	0.032 J	< 0.15 U	< 0.015 U	< 0.043 U	0.047 J	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.013 U	< 0.016 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.015 U	< 0.017 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated			1.438	< 0.021 U	0.058 J	< 0.02 U	0.044 J	< 0.16 U	0.015 J	< 0.045 R	0.11	0.094	0.13	0.049 J	0.094	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated			4.475	0.053 J	0.062 J	< 0.021 U	0.053 J	< 0.17 U	0.018 J	< 0.048 UT	0.45	< 0.017 U	0.34	< 0.023 U	0.11	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated			4.732	0.04 J	0.045 J	< 0.021 U	0.047 J	< 0.17 U	0.016 J	< 0.047 UT	0.69	0.21	0.17	0.24	0.16	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated			13.919	0.034 J	0.44	< 0.02 U	0.32	< 0.16 U	0.092 J	< 0.047 R	0.75	1	1.3	0.38	1.3	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated			16.66	0.1 J	0.1 J	< 0.06 U	0.36	< 0.48 U	< 0.046 U		0.64	0.62	0.74	0.31	0.45	< 0.052 U	< 0.04 U	< 0.081 U	< 1.2 U	< 0.077 U	< 0.76 U
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated			14.94	0.1	0.1	< 0.021 U	0.33	< 0.17 U	0.033 J		0.59	0.52	0.62	0.27	0.4	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Football Field	SSHS-B2914	DUP-05	11/6/2019	855.30	2 - 4 ft	180-98355-3	Excavated			0.456	< 0.06 U	< 0.045 U	< 0.056 U	< 0.054 U	< 0.45 U	< 0.044 U	< 0.13 U	0.051 J	< 0.045 UJ	0.057 J	< 0.062 U	0.073 J	< 0.05 U	< 0.038 U	< 0.077 U	< 1.1 U	< 0.073 U	< 0.71 U
Football Field	SSHS-B2914	SSHS-B2914-SUB-2-4	11/6/2019	855.30	2 - 4 ft	180-98355-2	Excavated			0.579	< 0.041 U	< 0.031 U	< 0.039 U	< 0.037 U	< 0.31 U	< 0.03 U	< 0.089 U	0.059 J	0.047 J	0.063 J	< 0.043 U	0.067 J	< 0.034 U	< 0.026 U	< 0.053 U	< 0.76 U	< 0.05 U	< 0.49 U
Football Field	SSHS-B2952	SSHS-B2952-SUB-2-4	11/6/2019	855.18	2 - 4 ft	180-98355-2	Excavated			11.756	< 0.064 U	0.11 J	< 0.061 U	0.2 J	< 0.49 U	< 0.047 U	< 0.14 U	0.52	0.48	0.52	0.21 J	0.37	< 0.053 U	< 0.041 U	< 0.083 U	< 1.2 U	< 0.078 U	< 0.77 U
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 0.34 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated			2.005	< 0.022 U	0.041 J	< 0.021 U	0.063 J	< 0.17 U	< 0.016 U	< 0.047 U	0.2	0.18	0.22	0.07 J	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated			0.489	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	0.046 J	0.044 J	0.051 J	< 0.023 U	0.041 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated			3.118	< 0.42 U	0.06 J		0.06 J				0.28 J	0.29 J	0.29 J	0.24 J	0.25 J						
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated			1.065	< 0.024 U	0.037 J	< 0.023 U	0.022 J	< 0.18 U	< 0.018 U	< 0.052 U	0.12	0.1	0.12	0.06 J	0.081 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated			0.43	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	0.04 J	0.042 J	0.06 J	< 0.025 U	0.034 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	4 - 6 ft	1801164043	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	120																				
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	42 J																				
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	< 37 UJ																				
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	41 J																				
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	120																				
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	< 39 U																				
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated			ND	< 0.019 U	0.035 J	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated			ND	< 0.02 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 UT	< 0.032 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	790																				
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated			0.16	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	92																				
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	51 J																				
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	< 41 U																				
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	76																				
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	150																				
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	960																				
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	140																				
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	50 J																				
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	< 37 U																				

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 0.95 UJ
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated	< 0.47 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.044 U	0.68	< 0.032 U	0.057 J	< 0.68 U	< 0.056 U	< 0.25 U	< 0.045 U	< 0.026 U	< 0.32 U	< 0.42 U	< 1.3 U	< 0.045 U	< 2 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.073	< 0.015 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 0.93 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.96 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.015 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 0.93 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.016 U	< 0.018 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.2	0.034 J	0.02 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 0.98 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.6	< 0.017 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.1	0.058 J	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.25 U	0.17	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.85	0.27	0.29 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.72 U	0.15 J	< 0.037 U	< 0.052 U	< 0.05 U	< 0.051 U	< 0.067 U	0.71	0.19 J	0.079 J	< 1 U	< 0.085 U	< 0.39 U	< 0.068 U	< 0.04 U	< 0.48 U	< 0.64 U	< 1.9 U	< 0.068 U	< 3 U
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.26 U	0.13	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.57	0.13	0.11 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Football Field	SSHS-B2914	DUP-05	11/6/2019	855.30	2 - 4 ft	180-98355-3	Excavated	< 0.68 U	< 0.049 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.048 U	< 0.063 U	0.077 J	< 0.046 U	< 0.045 U	< 0.97 U	< 0.08 U	< 0.36 U	< 0.065 U	< 0.038 U	< 0.45 U	< 0.6 U	< 1.8 U	< 0.064 U	< 2.8 U
Football Field	SSHS-B2914	SSHS-B2914-SUB-2-4	11/6/2019	855.30	2 - 4 ft	180-98355-2	Excavated	< 0.47 U	< 0.033 U	< 0.024 U	< 0.034 U	< 0.033 U	< 0.033 U	< 0.043 U	0.062 J	< 0.032 U	< 0.031 U	< 0.67 U	< 0.055 U	< 0.25 U	< 0.044 U	< 0.026 U	< 0.31 U	< 0.42 U	< 1.2 U	< 0.044 U	< 1.9 U
Football Field	SSHS-B2952	SSHS-B2952-SUB-2-4	11/6/2019	855.18	2 - 4 ft	180-98355-2	Excavated	< 0.73 U	0.085 J	< 0.037 U	< 0.053 U	< 0.051 U	< 0.052 U	< 0.068 U	0.76	0.1 J	0.094 J	< 1 U	< 0.086 U	< 0.39 U	< 0.069 U	< 0.041 U	< 0.49 U	< 0.65 U	< 1.9 U	< 0.069 U	< 3 U
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated	< 0.25 U	0.019 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.22	0.034 J	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated	< 0.24 U	< 0.018 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.086	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B3	B3_12 May 00 4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated								0.27 J	0.078 J	< 0.42 U										
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated																				
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.11	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	0.058 J	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	4 - 6 ft	1801164043	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated																				
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated																				
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated																				
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated																				
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated																				
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated																				
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated																				
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated																				
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated																				
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated																				
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated																				
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated																				
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated																				
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated																				
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.02 U	< 0.037 U	< 0.043 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated																				
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated																				
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated																				
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated																				
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated																				
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated																				
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated																				
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated																				
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated																				
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated																				
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated																				
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated																				
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated																				
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated																				
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated																				
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated																				
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated																				
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated																				
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated																				
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated																				
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated																				
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated																				
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated																				
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated																				

DRAFT

								2,4-Dinitrotoluene	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**	**Hexachloroethane**	**Indeno (1,2,3-cd)pyrene**	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated	< 0.036 U			< 0.23 U	0.99	< 0.029 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U	0.39	< 0.21 U	< 0.21 U	< 0.037 U	0.054 J
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated	< 0.017 U			< 0.11 U	0.15	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	0.023 J
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.017 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated	< 0.02 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.016 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	< 0.018 U			< 0.11 U	0.19	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.079	< 0.1 U	< 0.11 U	< 0.019 U	0.046 J
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	< 0.019 U	< 0.12 U			0.29	0.071 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.12	< 0.11 U		< 0.02 U	0.063 J
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	< 0.019 U	< 0.12 U			0.43	0.088	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.14	< 0.11 U		< 0.019 U	0.064 J
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.019 U			< 0.12 U	1.6	0.075 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	1.1	< 0.11 U		< 0.019 U	0.53
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.055 U			< 0.34 U	1.4	0.12 J	< 0.079 U	< 0.064 U	< 0.11 U	< 0.057 U	0.4	< 0.32 U		< 0.056 U	0.11 J
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.02 U			< 0.12 U	1.3	0.12	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.37	< 0.11 U		< 0.02 U	0.15
Football Field	SSHS-B2914	DUP-05	11/6/2019	855.30	2 - 4 ft	180-98355-3	Excavated	< 0.052 U			< 0.32 U	0.062 J	< 0.041 U	< 0.074 U	< 0.061 U	< 0.11 U	< 0.054 U	< 0.042 U	< 0.3 U	< 0.31 U	< 0.053 U	< 0.05 U
Football Field	SSHS-B2914	SSHS-B2914-SUB-2-4	11/6/2019	855.30	2 - 4 ft	180-98355-2	Excavated	< 0.036 U			< 0.22 U	0.084 J	< 0.028 U	< 0.051 U	< 0.042 U	< 0.073 U	< 0.037 U	0.032 J	< 0.21 U	< 0.21 U	< 0.036 U	< 0.034 U
Football Field	SSHS-B2952	SSHS-B2952-SUB-2-4	11/6/2019	855.18	2 - 4 ft	180-98355-2	Excavated	< 0.056 U			< 0.35 U	0.74	0.098 J	< 0.08 U	< 0.065 UJ	< 0.11 U	< 0.058 U	0.32	< 0.32 U		< 0.057 U	0.12 J
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated	< 0.34 U	< 0.7 U			< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated	< 0.019 U			< 0.12 U	0.27	0.016 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.11	< 0.11 U	< 0.11 U	< 0.019 U	0.027 J
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated	< 0.019 U			< 0.12 U	0.06 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.037 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated					0.57	< 0.42 U	< 0.42 U				0.22 J	< 0.42 U			
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated															
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.063 U	< 0.13 U			0.15	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	0.073 J	< 0.12 U		< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.063 U	< 0.13 U			0.073 J	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	4 - 6 ft	1801164043	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated															
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated															
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated															
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated															
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated															
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated															
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated															
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated															
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated															
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated															
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated															
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated															
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated															
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated															
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.051 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.017 U	< 0.034 U	< 0.097 U		< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.051 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.098 U		< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated															
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	< 0.052 U			< 0.11 U	0.043 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated															
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated															
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated															
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated															
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated															
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated															
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated															
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated															
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated															
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated															
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated															
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated															
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated															
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated															
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated															
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated															
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated															
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated															
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated															
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated															
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated															
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated															
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated															

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated		0.11 J	< 0.33 U	< 0.18 U	< 0.035 U	< 0.27 U	< 0.12 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.49	< 0.22 U	0.9		< 0.031 U	< 0.3 U	< 0.052 U	< 0.04 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated		0.041 J	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.11	< 0.1 U	0.09		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated		0.044 J	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.17	< 0.11 U	0.2		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	< 0.11 U	0.068 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.39	< 0.12 U	0.93		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	< 0.11 U	0.049 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.52	< 0.11 U	0.79		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.11 U	2.4	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.94	< 0.11 U	1.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.32 U	0.09 J	< 0.5 U	< 0.28 U	0.14 J	< 0.4 U	< 0.18 U	< 0.77 U		< 0.075 U	< 0.37 U	< 1.8 U	1.1	< 0.33 U	1.1		< 0.048 U	< 0.46 U	< 0.079 U	< 0.06 U
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.12 U	0.16	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	1	< 0.12 U	0.99		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B2914	DUP-05	11/6/2019	855.30	2 - 4 ft	180-98355-3	Excavated		< 0.041 U	< 0.47 U	< 0.26 U	< 0.05 U	< 0.38 U	< 0.17 U	< 0.73 UJ		< 0.07 U	< 0.35 U	< 1.7 U	0.071 J	< 0.31 U	0.065 J		< 0.045 U	< 0.43 U	< 0.074 U	< 0.057 U
Football Field	SSHS-B2914	SSHS-B2914-SUB-2-4	11/6/2019	855.30	2 - 4 ft	180-98355-2	Excavated		< 0.028 U	< 0.33 U	< 0.18 U	< 0.035 U	< 0.26 U	< 0.11 U	< 0.5 UJ		< 0.049 U	< 0.24 U	< 1.2 U	0.083 J	< 0.22 U	0.082 J		< 0.031 U	< 0.3 U	< 0.051 U	< 0.039 U
Football Field	SSHS-B2952	SSHS-B2952-SUB-2-4	11/6/2019	855.18	2 - 4 ft	180-98355-2	Excavated	< 0.33 U	0.19 J	< 0.51 U	< 0.28 U	< 0.054 U	< 0.41 U	< 0.18 U	< 0.78 UJ		< 0.076 U	< 0.37 U	< 1.8 U	0.57	< 0.34 U	0.8		< 0.048 U	< 0.47 U	< 0.08 U	< 0.061 U
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	12 - 14 ft	180-98520-1	Not Excavated	< 0.34 U	< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.7 U	< 0.34 U	< 1.8 UJ		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	10 - 12 ft	180-98520-1	Not Excavated		0.032 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 UJ		< 0.026 U	< 0.13 U	< 0.61 U	0.15	< 0.12 U	0.31		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	12 - 14 ft	180-98520-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 UJ		< 0.025 U	< 0.12 U	< 0.6 U	0.048 J	< 0.11 U	0.076		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated	< 0.42 U	< 0.42 U										< 1 U	0.15 J	< 0.42 U	0.42 J					
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated																				
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.049 J	< 0.13 U	0.18		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.05 J	< 0.13 U	0.073 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	4 - 6 ft	1801164043	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated																				
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated																				
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated																				
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated																				
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated																				
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated																				
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated																				
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated																				
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated																				
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated																				
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated																				
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated																				
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated																				
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated																				
Northern Athletic Field	SSHS-B3015A	DUP-3	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12	1/23/2021	853.60	10 - 12 ft	1801164042	Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14	1/23/2021	853.60	12 - 14 ft	1801164042	Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated																				
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated		0.036 J	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	0.029 J	< 0.1 U	0.052 J		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated																				
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated																				
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated																				
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated																				
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated																				
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated																				
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated																				
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated																				
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated																				
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated																				
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated																				
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated																				
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated																				
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated																				
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated																				
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated																				
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated																				
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated																				
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated																				
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated																				
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated																				
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated																				
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated																				

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3042A	SSHS-B3042A-SUB-2-4	1/27/2021	855.17	2 - 4 ft	180-116529-1	Excavated	< 40 U	< 40 U																			
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	550																				
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	94																				
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	120 J																				
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated			6.27	0.35	0.39	< 0.021 U	0.23	< 0.17 U	0.14 J	< 0.048 U	< 0.015 U	< 0.017 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	87																				
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	540																				
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	350																				
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	52 J																				
Northern Athletic Field	SSHS-B3049A	SSHS-B3049A-SUB-2-4	1/28/2021	857.14	2 - 4 ft	180-116609-1	Excavated	6500	6500																			
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	< 39 U																				
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	2 - 4 ft	180-116404-1	Not Excavated			2.926	< 0.022 U	0.049 J	< 0.021 U	0.066 J	< 0.17 U	< 0.016 U	< 0.047 U	0.3	0.32	0.37	0.11	0.24	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	4 - 6 ft	180-116404-3	Not Excavated			1.775	< 0.021 U	0.035 J	< 0.02 U	0.038 J	< 0.16 U	< 0.016 U	< 0.046 U	0.17	0.18	0.2	0.085	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	< 40 U																				
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	52 J																				
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-2-4	1/27/2021	857.02	2 - 4 ft	180-116529-1	Excavated			9.84	< 0.044 U	0.49	< 0.041 U	0.31	< 0.33 U	< 0.032 U	< 0.094 U	0.65	0.94	1.1	0.48	1.3	< 0.036 U	< 0.028 U	< 0.056 U	< 0.81 U	< 0.053 U	< 0.52 U
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-4-6	1/27/2021	857.02	4 - 6 ft	180-116529-3	Excavated			4.619	< 0.023 U	0.18	< 0.021 U	0.17	< 0.17 U	< 0.016 U	< 0.049 U	0.32	0.43	0.57	0.12	0.49	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated	40 J																				
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	2 - 4 ft	180-116404-1	Not Excavated			1.541	< 0.019 U	0.068	< 0.018 U	0.038 J	< 0.15 U	0.02 J	< 0.042 U	0.11	0.13	0.19	0.059 J	0.16	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U	< 0.23 U
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	4 - 6 ft	180-116404-3	Not Excavated			3.719	< 0.022 U	0.088	< 0.021 U	0.074 J	< 0.17 U	< 0.016 U	< 0.047 U	0.34	0.42	0.44	0.19	0.31	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	6900 J+																				
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated			61.76	0.17	2.1	< 0.02 U	2.5	< 0.16 U	0.075 J	< 0.046 U	5.4	5.4	5.8	2.1	4.3	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6	1/27/2021	857.14	4 - 6 ft	1801165293	Excavated			971.8	3.2	16	< 0.32 U	41	< 2.6 U	< 0.25 U	< 0.73 U	81	75	80	31	51	< 0.28 U	< 0.21 U	< 0.43 U	< 6.2 U	< 0.41 U	< 4 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated			30.48	< 0.043 U	0.89	< 0.041 U	1	< 0.33 U	< 0.031 U	< 0.093 U	2.8	2.7	3.3	0.94	2.2	< 0.036 U	< 0.027 U	< 0.055 U	< 0.8 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-10-12	1/29/2021	857.14	10 - 12 ft	1801166651	Excavated		< 44 U																			
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-14-16	1/29/2021	857.14	14 - 16 ft	1801166651	Excavated		< 37 U																			
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	390																				
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	1100																				
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-10-12	7/19/2021	856.99	10 - 12 ft	180-124670-1	Excavated	160 J																				
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-14-16	7/19/2021	856.99	14 - 16 ft	180-124670-1	Excavated	140																				
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	40 J																				
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	< 34 U																				
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-2-4	1/25/2021	857.70	2 - 4 ft	180-116404-1	Excavated			17.836	< 0.022 U	0.81	< 0.021 U	0.45	< 0.17 U	< 0.016 U	< 0.047 U	1.7	1.7	2.2	0.96	1.6	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-4-6	1/25/2021	857.70	4 - 6 ft	180-116404-3	Excavated			0.928	< 0.021 U	0.044 J	< 0.02 U	0.021 J	< 0.16 U	< 0.016 U	< 0.046 U	0.09	0.1	0.13	0.051 J	0.099	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	< 40 U																				
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	< 39 U																				
Northern Athletic Field	SSHS-B3096A	SSHS-B3096A-SUB-2-4	7/19/2021	855.86	2 - 4 ft	180-124670-1	Excavated			6.223	0.05 J	0.08	< 0.02 U	0.16	< 0.16 U	< 0.016 U	< 0.046 U	0.55	0.49	0.58	0.3	0.36	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	< 35 U																				

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3042A	SSHS-B3042A-SUB-2-4	1/27/2021	855.17	2 - 4 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated																				
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated																				
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated																				
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.015 U	< 0.017 U	0.28 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated																				
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated																				
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated																				
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated																				
Northern Athletic Field	SSHS-B3049A	SSHS-B3049A-SUB-2-4	1/28/2021	857.14	2 - 4 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated																				
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated																				
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated																				
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated																				
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated																				
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated																				
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated																				
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated																				
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	2 - 4 ft	180-116404-1	Not Excavated	< 0.25 U	0.022 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.27	< 0.049 U	0.018 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	4 - 6 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.16	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated																				
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated																				
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated																				
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated																				
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-2-4	1/27/2021	857.02	2 - 4 ft	180-116529-1	Excavated	< 0.49 U	0.11 J	< 0.052 U	< 0.036 U	< 0.035 U	< 0.035 U	< 0.046 U	0.62	0.33	0.16 J	< 0.71 U	< 0.058 U	< 0.27 U	< 0.047 U	< 0.056 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.047 U	< 4.2 U
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-4-6	1/27/2021	857.02	4 - 6 ft	180-116529-3	Excavated	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.39	0.16	0.035 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated																				
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated																				
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated																				
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated																				
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated																				
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated																				
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated																				
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated																				
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated																				
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	2 - 4 ft	180-116404-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	0.15	0.044 J	0.04 J	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	4 - 6 ft	180-116404-3	Not Excavated	< 0.25 U	0.019 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.34	0.078	0.023 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated																				
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated																				
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated	< 0.24 U	0.44	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	5.1	1	0.51	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6	1/27/2021	857.14	4 - 6 ft	1801165293	Excavated	< 3.8 U	4.3	< 0.4 U	< 0.28 U	< 0.27 U	< 0.27 U	< 0.35 U	64	13	8	< 5.5 U	< 0.45 U	< 2.1 U	< 0.36 U	< 0.43 U	< 2.6 U	< 3.4 U	< 10 U	< 0.36 U	< 32 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	< 0.49 U	0.15	< 0.051 U	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	2.4	0.59	0.21 J	< 0.7 U	< 0.058 U	< 0.26 U	< 0.046 U	< 0.055 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.046 U	< 4.2 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-10-12	1/29/2021	857.14	10 - 12 ft	1801166651	Excavated																				
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-14-16	1/29/2021	857.14	14 - 16 ft	1801166651	Excavated																				
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated																				
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated																				
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-10-12	7/19/2021	856.99	10 - 12 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-14-16	7/19/2021	856.99	14 - 16 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated																				
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated																				
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated																				
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated																				
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated																				
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated																				
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.015 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.012 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 0.92 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated																				
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated																				
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated																				
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated																				
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated																				
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-2-4	1/25/2021	857.70	2 - 4 ft	180-116404-1	Excavated	< 0.25 U	0.075 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.8	0.43	0.042 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-4-6	1/25/2021	857.70	4 - 6 ft	180-116404-3	Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.092	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated																				
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated																				
Northern Athletic Field	SSHS-B3096A	SSHS-B3096A-SUB-2-4	7/19/2021	855.86	2 - 4 ft	180-124670-1	Excavated	< 0.24 U	0.056 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.58	0.099	0.034 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated																				
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated																				

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3042A	SSHS-B3042A-SUB-2-4	1/27/2021	855.17	2 - 4 ft	180-116529-1	Excavated															
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated															
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated															
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated															
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	< 0.019 U			< 0.12 U	1	0.29	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.016 U	< 0.11 U	0.11 J	< 0.02 U	0.63
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated															
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated															
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated															
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated															
Northern Athletic Field	SSHS-B3049A	SSHS-B3049A-SUB-2-4	1/28/2021	857.14	2 - 4 ft	180-116609-1	Excavated															
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated															
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated															
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated															
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated															
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated															
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated															
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated															
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated															
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	2 - 4 ft	180-116404-1	Not Excavated	< 0.057 U			< 0.12 U	0.44	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.22	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	4 - 6 ft	180-116404-3	Not Excavated	< 0.056 U			< 0.12 U	0.28	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.11	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated															
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated															
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated															
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated															
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-2-4	1/27/2021	857.02	2 - 4 ft	180-116529-1	Excavated	< 0.11 U			< 0.24 U	0.97	< 0.03 U	< 0.054 U	< 0.044 U	< 0.078 U	< 0.039 U	1	< 0.22 U	< 0.22 U	< 0.039 U	0.21
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-4-6	1/27/2021	857.02	4 - 6 ft	180-116529-3	Excavated	< 0.059 U			< 0.12 U	0.53	0.039 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.4	< 0.11 U	< 0.11 U	< 0.02 U	0.078 J
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated															
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated															
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated															
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated															
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated															
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated															
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated															
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated															
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated															
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	2 - 4 ft	180-116404-1	Not Excavated	< 0.051 U			< 0.1 U	0.13	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U	0.1	< 0.096 U	< 0.099 U	< 0.017 U	0.18
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	4 - 6 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.47	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.26	< 0.11 U	< 0.11 U	< 0.019 U	0.07 J
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated															
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated															
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated	< 0.056 U	< 0.12 U			10	0.69	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	3.7	< 0.11 U		< 0.019 U	0.31
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6	1/27/2021	857.14	4 - 6 ft	1801165293	Excavated	< 0.88 U	< 1.8 U			190	14	< 0.42 U	< 0.34 U	< 0.6 U	< 0.3 U	45	< 1.7 U		< 0.3 U	1.6
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	< 0.11 U	< 0.23 U			5	0.27	< 0.054 U	< 0.044 U	< 0.077 U	< 0.039 U	2	< 0.21 U		< 0.038 U	0.19
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-10-12	1/29/2021	857.14	10 - 12 ft	1801166651	Excavated															
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-14-16	1/29/2021	857.14	14 - 16 ft	1801166651	Excavated															
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated															
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated															
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-10-12	7/19/2021	856.99	10 - 12 ft	180-124670-1	Excavated															
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-14-16	7/19/2021	856.99	14 - 16 ft	180-124670-1	Excavated															
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated															
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated															
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated															
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated															
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated															
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated															
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.017 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.016 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated															
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated															
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated															
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated															
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated															
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-2-4	1/25/2021	857.70	2 - 4 ft	180-116404-1	Excavated	< 0.057 U			< 0.12 U	2.2	0.076	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	1.3	< 0.11 U	< 0.11 U	< 0.019 U	0.12
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-4-6	1/25/2021	857.70	4 - 6 ft	180-116404-3	Excavated	< 0.056 U			< 0.12 U	0.096	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.078	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated															
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated															
Northern Athletic Field	SSHS-B3096A	SSHS-B3096A-SUB-2-4	7/19/2021	855.86	2 - 4 ft	180-124670-1	Excavated	< 0.056 U			< 0.12 U	1	0.055 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.34	< 0.11 U	< 0.11 U	< 0.019 U	0.048 J
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated															
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated															

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3042A	SSHS-B3042A-SUB-2-4	1/27/2021	855.17	2 - 4 ft	180-116529-1	Excavated																				
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated																				
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated																				
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated																				
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated		1.5	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	1.1	< 0.12 U	1.8		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated																				
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated																				
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated																				
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated																				
Northern Athletic Field	SSHS-B3049A	SSHS-B3049A-SUB-2-4	1/28/2021	857.14	2 - 4 ft	180-116609-1	Excavated																				
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated																				
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated																				
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated																				
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated																				
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated																				
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated																				
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated																				
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated																				
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	2 - 4 ft	180-116404-1	Not Excavated		0.04 J	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.18	< 0.12 U	0.37		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	4 - 6 ft	180-116404-3	Not Excavated		0.059 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.093	< 0.11 U	0.27		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated																				
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated																				
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated																				
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated																				
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-2-4	1/27/2021	857.02	2 - 4 ft	180-116529-1	Excavated		0.61	< 0.35 U	< 0.19 U	< 0.037 U	< 0.28 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	0.53	< 0.23 U	1		< 0.033 U	< 0.32 U	< 0.054 U	< 0.042 U
Northern Athletic Field	SSHS-B3061A	SSHS-B3061A-SUB-4-6	1/27/2021	857.02	4 - 6 ft	180-116529-3	Excavated		0.19	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.27	< 0.12 U	0.54		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated																				
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated																				
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94754-2	Not Excavated																				
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	12 - 14 ft	180-94752-3	Not Excavated																				
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated																				
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated																				
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated																				
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated																				
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated																				
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	2 - 4 ft	180-116404-1	Not Excavated		0.13	< 0.15 U	< 0.086 U	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.14	< 0.1 U	0.16		< 0.015 U	< 0.14 U	< 0.024 U	< 0.018 U
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	4 - 6 ft	180-116404-3	Not Excavated		0.077	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.18	< 0.12 U	0.54		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated																				
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated																				
Northern Athletic Field	SSHS-B3073A	DUP-4	1/27/2021	857.14	2 - 4 ft	1801165291	Excavated	< 0.11 U	0.5	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	5.6	< 0.11 U	9.5		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6	1/27/2021	857.14	4 - 6 ft	1801165293	Excavated	< 1.7 U	3.6	< 2.7 U	< 1.5 U	< 0.28 U	< 2.1 U	< 0.93 U	< 4.1 U		< 0.4 U	< 1.9 U	< 9.4 U	130	< 1.8 U	150		< 0.25 U	< 2.4 U	< 0.42 U	< 0.32 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	< 0.22 U	0.28	< 0.34 U	< 0.19 U	< 0.036 U	< 0.27 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	2.4	< 0.23 U	4.6		< 0.032 U	< 0.31 U	< 0.053 U	< 0.041 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-10-12	1/29/2021	857.14	10 - 12 ft	1801166651	Excavated																				
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-14-16	1/29/2021	857.14	14 - 16 ft	1801166651	Excavated																				
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated																				
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated																				
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-10-12	7/19/2021	856.99	10 - 12 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3075A	SSHS-B3075A-SUB-14-16	7/19/2021	856.99	14 - 16 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated																				
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated																				
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated																				
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated																				
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated																				
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated																				
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated																				
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated																				
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated																				
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated																				
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated																				
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-2-4	1/25/2021	857.70	2 - 4 ft	180-116404-1	Excavated		0.15	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.67	< 0.11 U	2.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3087A	SSHS-B3087A-SUB-4-6	1/25/2021	857.70	4 - 6 ft	180-116404-3	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.021 J	< 0.11 U	0.15		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated																				
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated																				
Northern Athletic Field	SSHS-B3096A	SSHS-B3096A-SUB-2-4	7/19/2021	855.86	2 - 4 ft	180-124670-1	Excavated		0.099	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.63	< 0.11 U	0.93		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated																				
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated																				

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benzo(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-2-4	1/27/2021	855.96	2 - 4 ft	180-116529-1	Excavated			3.132	< 0.022 U	0.088	< 0.02 U	0.068 J	< 0.16 U	< 0.016 U	< 0.047 U	0.26	0.29	0.35	0.12	0.25	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	4 - 6 ft	180-116529-3	Not Excavated			0.805	< 0.023 U	< 0.017 U	< 0.021 U	0.02 J	< 0.17 U	< 0.017 U	< 0.049 U	0.081	0.07 J	0.082	0.033 J	0.052 J	< 0.019 U	< 0.014 U	< 0.029 U	0.46 J	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated			3.76	< 0.51 U	< 0.39 U	< 0.48 U	< 0.46 U	< 3.9 U	< 0.37 U	< 1.1 U	0.4 J	0.38 J	< 0.43 U	< 0.53 U	< 0.38 U	< 0.42 U	< 0.32 U	< 0.65 U	< 9.4 U	< 0.62 U	< 6.1 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated			4.99	< 0.54 U	< 0.41 U	< 0.51 U	< 0.48 U	< 4.1 U	< 0.39 U	< 1.2 U	0.52 J	0.47 J	0.58 J	< 0.56 U	0.44 J	< 0.44 U	< 0.34 U	< 0.69 U	< 9.9 U	< 0.65 U	< 6.4 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated			4.83	< 0.063 U	< 0.048 U	< 0.06 U	0.14 J	< 0.48 U	< 0.046 U	< 0.14 U	0.37	0.34	0.47	0.11 J	0.34	< 0.052 U	< 0.04 U	< 0.081 U	< 1.2 U	< 0.077 U	< 0.75 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	65																				
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated			17.01	< 0.55 U	< 0.42 U	< 0.52 U	0.64 J	< 4.2 U	< 0.4 U	< 1.2 U	1.4 J	1.2 J	1.4 J	0.68 J	0.95 J	< 0.46 U	< 0.35 U	< 0.71 U	< 10 U	< 0.67 U	< 6.6 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	110																				
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated			6.65	0.15 J	< 0.08 U	< 0.099 U	0.23 J	< 0.8 U	< 0.077 U	< 0.23 U	0.44	0.42	0.46	0.18 J	0.49	< 0.087 U	< 0.066 U	< 0.14 U	< 2 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	53																				
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated			1.357	0.02 J	0.022 J	< 0.019 U	0.044 J	< 0.15 U	< 0.015 U	< 0.044 U	0.1	0.095	0.1	0.044 J	0.1	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	83																				
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated			2.931	< 0.044 U	0.12 J	< 0.042 U	0.086 J	< 0.34 U	< 0.032 U	< 0.095 U	0.33	0.29	0.34	0.1 J	0.24	< 0.037 U	< 0.028 U	< 0.057 U	< 0.82 U	< 0.054 U	< 0.53 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	53																				
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	< 35 U																				
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	< 38 U																				
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated			39.947	0.057 J	2.3	< 0.021 U	1.4	< 0.17 U	0.026 J	< 0.047 U	3.8	3.8	5.1	1.6	3.4	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated			26.05	< 0.022 U	1.2	< 0.02 U	0.63	< 0.16 U	< 0.016 U	< 0.047 U	2.4	2.6	3.9	0.97	2.5	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6	1/26/2021	857.57	4 - 6 ft	1801164623	Excavated			0.918	< 0.022 U	0.054 J	< 0.02 U	0.02 J	< 0.16 U	< 0.016 U	< 0.046 U	0.085	0.097	0.13	0.05 J	0.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated			8.437	< 0.022 U	0.46	< 0.021 U	0.28	< 0.17 U	< 0.016 U	< 0.048 U	0.79	0.77	0.99	0.37	0.66	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated			8.437	< 0.022 U	0.46	< 0.021 U	0.28	< 0.17 U	< 0.016 U	< 0.048 U	0.79	0.77	0.99	0.37	0.66	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated			0.741	< 0.022 U	0.052 J	< 0.02 U	0.028 J	< 0.16 U	< 0.016 U	< 0.046 U	0.07 J	0.076	0.1	0.033 J	0.067 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated			0.741	< 0.022 U	0.052 J	< 0.02 U	0.028 J	< 0.16 U	< 0.016 U	< 0.046 U	0.07 J	0.076	0.1	0.033 J	0.067 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated			2.84	< 0.54 U	< 0.41 U	< 0.51 U	< 0.48 U	< 4.1 U	< 0.39 U	< 1.2 U	0.41 J	< 0.4 U	< 0.46 U	< 0.56 U	< 0.4 U	< 0.44 U	< 0.34 U	< 0.69 U	< 9.9 U	< 0.65 U	< 6.4 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	210																				
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	2 - 4 ft	180-116462-1	Not Excavated	440	440 J	64.15	< 0.087 UJ	2.6 J	< 0.082 U	1.4	< 0.66 U	< 0.064 UJ	< 0.19 U	5.9 J	5.5 J	7.3 J	2.7 J	4.7 J	< 0.072 U	< 0.055 U	< 0.11 U	< 1.6 U	< 0.11 U	< 1 U
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	4 - 6 ft	180-116462-3	Not Excavated	< 38 U	< 38 U	1.787	< 0.022 U	0.1	< 0.021 U	0.042 J	< 0.17 U	< 0.016 U	< 0.047 U	0.15	0.18	0.21	0.12	0.16	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	2 - 4 ft	180-100361-1	Not Excavated			0.969	< 0.022 U	0.11	< 0.02 U	0.051 J	< 0.16 U	< 0.016 U	< 0.047 U	0.065 J	0.096	0.16	0.036 J	0.11	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	2 - 4 ft	180-100362-1	Not Excavated			6.565	0.026 J	0.38	< 0.022 U	0.21	< 0.17 U	0.017 J	< 0.049 U	0.53	0.58	0.7	0.25	0.7	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	2 - 4 ft	180-101497-4	Not Excavated			0.282	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	0.032 J	0.03 J	0.03 J	< 0.026 U	0.042 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	2 - 4 ft	180-100362-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated			5.374	< 0.022 UJ	0.25	< 0.021 U	0.15	< 0.17 U	< 0.016 U	< 0.047 U	0.57	0.47	0.57	0.21	0.42	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated			5.812	< 0.091 U	0.29 J	< 0.085 U	0.16 J	< 0.69 U	< 0.066 U	< 0.2 U	0.54	0.44 J	0.61 J	0.24 J	0.44 J	< 0.075 U	< 0.057 U	< 0.12 U	< 1.7 U	< 0.11 U	< 1.1 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-2-4	12/19/2019	857.74	2 - 4 ft	180-100363-3	Excavated			0.524	< 0.021 U	0.037 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.048 J	0.047 J	0.061 J	0.024 J	0.048 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-2-4	12/19/2019	857.37	2 - 4 ft	180-100363-3	Excavated			0.197	< 0.023 U	0.02 J	< 0.021 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.022 J	0.024 J	0.027 J	< 0.024 U	0.022 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-2-4	12/19/2019	858.13	2 - 4 ft	180-100363-3	Excavated			0.276	< 0.021 U	0.022 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U		0.034 J	0.029 J	0.036 J	< 0.022 U	0.024 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-2-4	12/19/2019	857.57	2 - 4 ft	180-100363-3	Excavated			8.511	< 0.022 UJ	0.5	< 0.021 U	0.22	< 0.17 U	< 0.016 U		0.77	0.86	1.2	0.38	0.74	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-2-4	12/19/2019	857.44	2 - 4 ft	180-100363-1	Excavated			0.719	< 0.022 U	0.05 J	< 0.021 U	0.023 J	< 0.17 U	< 0.016 U	< 0.047 U	0.065 J	0.076 J	0.1	0.041 J	0.061 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	2 - 4 ft	180-100363-1	Not Excavated			1.387	< 0.022 U	0.099	< 0.021 U	0.045 J	< 0.17 U	< 0.016 U	< 0.048 U	0.12	0.13	0.19	0.048 J	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	2 - 4 ft	180-100363-1	Not Excavated			8.576	0.027 J	0.46 J	< 0.021 UJ	0.24 J	< 0.17 U	< 0.016 UJ	< 0.047 U	0.72 J	0.8 J	0.99 J	0.42 J	0.69 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	2 - 4 ft	180-100363-2	Not Excavated			4.107	< 0.022 U	0.18	< 0.021 U	0.094	< 0.17 U	< 0.016 U	< 0.048 U	0.36	0.4	0.58	0.16	0.35	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	2 - 4 ft	180-100363-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-2-4	12/19/2019	858.14	2 - 4 ft	180-100363-2	Excavated			3.483	< 0.022 U	0.16 J	< 0.021 UJ	0.092	< 0.17 U	< 0.016 U	< 0.047 U	0.3	0.32	0.49	0.16	0.29	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	2 - 4 ft	180-100363-2	Not Excavated			12.513	0.037 J	0.62	< 0.022 U	0.32	< 0.18 U	0.017 J	< 0.05 U	1.1	1.2	1.6	0.64	1.1	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	2 - 4 ft	180-100363-2	Not Excavated			0.316	< 0.022 U	0.043 J	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.031 J	0.047 J	0.047 J	0.024 J	0.034 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	2 - 4 ft	180-100363-1	Not Excavated			98.42	0.2 J	4.6	< 0.063 U	2.6	< 0.51 U	< 0.049 U	< 0.14 U	8.8	6.9	11	3.1	6.6	< 0.055 U	< 0.042 U	< 0.086 U	< 1.2 U	< 0.081 U	< 0.79 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	4 - 6 ft	180-116462-1	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	6 - 8 ft	180-116462-3	Not Excavated			0.247	< 0.021 U	0.024 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	0.037 J	0.05 J	0.022 J	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	2 - 4 ft	180-116404-1	Not Excavated			7.546	< 0.023 U	0.3	< 0.021 U	0.14	< 0.17 U	< 0.017 U	< 0.049 U	0.74	0.83	1.1	0.27	0.63	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-2-4	1/27/2021	855.96	2 - 4 ft	180-116529-1	Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.28	0.084	0.039 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	4 - 6 ft	180-116529-3	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.074 J	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated																				
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	< 5.7 U	< 0.41 U	< 0.29 U	< 0.42 U	< 0.41 U	< 0.41 U	< 0.54 U	0.4 J	< 0.39 U	< 0.39 U	< 8.2 U	< 0.68 U	< 3.1 U	< 0.55 U	< 0.32 U	< 3.9 U	< 5.1 U	< 15 U	< 0.55 U	< 24 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated																				
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated	< 6.1 U	< 0.44 U	< 0.31 U	< 0.44 U	< 0.43 U	< 0.43 U	< 0.57 U	0.44 J	< 0.42 U	< 0.41 U	< 8.7 U	< 0.72 U	< 3.3 U	< 0.58 U	< 0.34 U	< 4.1 U	< 5.4 U	< 16 U	< 0.58 U	< 25 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated																				
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	< 0.71 U	0.083 J	< 0.037 U	< 0.052 U	< 0.05 U	< 0.051 U	< 0.067 U	0.39	0.063 J	0.056 J	< 1 U	< 0.085 U	< 0.39 U	< 0.068 U	< 0.04 U	< 0.48 U	< 0.64 U	< 1.9 U	< 0.068 U	< 3 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated																				
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated																				
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated	< 6.3 U	< 0.45 U	< 0.32 U	< 0.45 U	< 0.44 U	< 0.45 U	< 0.58 U	1.3 J	< 0.43 U	< 0.42 U	< 9 U	< 0.74 U	< 3.4 U	< 0.6 U	< 0.35 U	< 4.2 U	< 5.6 U	< 17 U	< 0.59 U	< 26 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated																				
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated	< 1.2 U	0.16 J	< 0.061 U	< 0.086 U	< 0.084 U	< 0.085 U	< 0.11 U	0.45	< 0.082 U	0.098 J	< 1.7 U	< 0.14 U	< 0.64 U	< 0.11 U	< 0.066 U	< 0.8 U	< 1.1 U	< 3.2 U	< 0.11 U	< 4.9 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated																				
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated	< 0.23 U	0.022 J	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.1	0.021 J	0.02 J	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 0.95 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated																				
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated																				
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated																				
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated																				
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated																				
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated																				
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated	< 0.5 U	< 0.036 U	< 0.026 U	< 0.036 U	< 0.035 U	< 0.036 U	< 0.046 U	0.31	0.062 J	< 0.034 U	< 0.72 U	< 0.059 U	< 0.27 U	< 0.048 U	< 0.028 U	< 0.34 U	< 0.45 U	< 1.3 U	< 0.047 U	< 2.1 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated																				
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated																				
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated																				
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated																				
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated																				
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated																				
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated	< 0.25 U	0.19	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	4.4	0.87	0.064 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.24 U	0.11	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	2.7	0.64	0.047 J	< 0.35 U	< 0.029 U	0.19 J	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6	1/26/2021	857.57	4 - 6 ft	1801164623	Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.087	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	0.15 J	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated																				
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated	< 0.25 U	0.035 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.9	0.17	0.019 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated	< 0.25 U	0.035 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.9	0.17	0.019 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.081	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.081	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated	< 6.1 U	< 0.44 U	< 0.31 U	< 0.44 U	< 0.43 U	< 0.43 U	< 0.56 U	< 0.37 U	< 0.42 U	< 0.41 U	< 8.7 U	< 0.72 U	< 3.3 U	< 0.58 U	< 0.34 U	< 4.1 U	< 5.4 U	< 16 U	< 0.57 U	< 25 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated																				
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated																				
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated																				
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated																				
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated																				
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated																				
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	2 - 4 ft	180-116462-1	Not Excavated	< 0.99 U	0.3 J	< 0.1 U	< 0.071 U	< 0.07 U	< 0.071 U	< 0.092 U	6.5 J	1.3 J	0.19 J	< 1.4 U	< 0.12 U	< 0.53 U	< 0.094 U	< 0.11 U	< 0.66 U	< 0.88 U	< 2.6 U	< 0.094 U	< 8.4 U
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	4 - 6 ft	180-116462-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.19	0.061 J	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	2 - 4 ft	180-100361-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.086	0.03 J	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	2 - 4 ft	180-100362-1	Not Excavated	< 0.26 U	0.054 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.55	0.21	0.05 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	2 - 4 ft	180-101497-4	Not Excavated	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.034 J	< 0.019 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U	< 1.2 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	2 - 4 ft	180-100362-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated	< 0.25 U	0.038 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.57	0.17	0.019 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated	< 1 U	< 0.074 UJ	< 0.052 U	< 0.074 U	< 0.072 U	< 0.073 U	< 0.095 U	0.55 J	0.37	< 0.069 U	< 1.5 U	< 0.12 U	< 0.55 U	< 0.098 U	< 0.057 U	< 0.69 U	< 0.91 U	< 2.7 U	< 0.097 U	< 4.2 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-2-4	12/19/2019	857.74	2 - 4 ft	180-100363-3	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.047 J	0.074 J	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-2-4	12/19/2019	857.37	2 - 4 ft	180-100363-3	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.026 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-2-4	12/19/2019	858.13	2 - 4 ft	180-100363-3	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.036 J	< 0.017 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-2-4	12/19/2019	857.57	2 - 4 ft	180-100363-3	Excavated	< 0.25 U	0.042 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.85	0.23	0.024 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-2-4	12/19/2019	857.44	2 - 4 ft	180-100363-1	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.079	< 0.017 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	2 - 4 ft	180-100363-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.15	< 0.017 U	0.019 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	2 - 4 ft	180-100363-1	Not Excavated	< 0.25 U	0.05 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.86 J	0.21 J	0.026 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	2 - 4 ft	180-100363-2	Not Excavated	< 0.25 U	0.027 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.43	0.095	0.022 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	2 - 4 ft	180-100363-1	Not Excavated	< 0.23 UJ	< 0.017 U	< 0.012 UJ	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-2-4	12/19/2019	858.14	2 - 4 ft	180-100363-2	Excavated	< 0.25 U	0.024 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.36	0.091	0.02 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	2 - 4 ft	180-100363-2	Not Excavated	< 0.26 U	0.086	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	1.3	0.29	0.042 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	2 - 4 ft	180-100363-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.032 J	< 0.017 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	2 - 4 ft	180-100363-1	Not Excavated	< 0.75 U	0.74	< 0.039 U	< 0.054 U	< 0.053 U	< 0.054 U	< 0.07 U	10	1.7	0.46 J	< 1.1 U	< 0.089 U	< 0.41 U	< 0.072 U	< 0.042 U	< 0.51 U	< 0.67 U	< 2 U	< 0.071 U	< 3.1 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	4 - 6 ft	180-116462-1	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	6 - 8 ft	180-116462-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.041 J	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	2 - 4 ft	180-116404-1	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.74	0.19	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U

DRAFT

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33					0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-2-4	1/27/2021	855.96	2 - 4 ft	180-116529-1	Excavated	< 0.057 U			< 0.12 U	0.44	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.21	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	4 - 6 ft	180-116529-3	Not Excavated	< 0.059 U			< 0.12 U	0.13	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.042 J	< 0.11 U	< 0.12 U	< 0.02 U	0.034 J
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated															
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	< 0.44 U			< 2.8 UJ	0.99 J	< 0.35 U	< 0.63 U	< 0.52 U	< 0.9 U	< 0.46 U	< 0.36 U	< 2.5 U	< 2.6 U	< 0.45 U	< 0.42 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated															
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated	< 0.46 U			< 2.9 UJ	0.93 J	< 0.37 U	< 0.67 U	< 0.55 U	< 0.95 U	< 0.48 U	< 0.38 U	< 2.7 U	< 2.7 U	< 0.48 U	< 0.45 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated															
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated	< 0.055 U			< 0.34 UJ	0.87	0.071 J	< 0.079 U	< 0.064 U	< 0.11 U	< 0.057 U	0.23	< 0.31 U	< 0.32 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated															
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated															
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated	< 0.48 U			< 3 UJ	3.3	< 0.38 U	< 0.69 U	< 0.56 U	< 0.98 U	< 0.5 U	0.74 J	< 2.8 U	< 2.8 U	< 0.49 U	< 0.46 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated															
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated	< 0.091 U			< 0.57 U	1.1	0.16 J	< 0.13 U	< 0.11 U	< 0.19 U	< 0.095 U	0.33 J	< 0.53 U	< 0.54 U	< 0.093 U	< 0.088 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated															
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated	< 0.018 U			< 0.11 U	0.21	0.022 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.081	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated															
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated															
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated															
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated															
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated															
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated															
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated	< 0.038 U			< 0.24 U	0.41	< 0.03 U	< 0.055 U	< 0.045 U	< 0.078 U	< 0.04 U	0.2	< 0.22 U	< 0.23 U	< 0.039 U	< 0.037 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated															
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated															
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated															
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated															
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated															
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated															
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated	< 0.057 U	< 0.12 U			5.1	0.17	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	2.7	< 0.11 U		< 0.019 U	0.17
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.057 U	< 0.12 U			3	0.1	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	2	< 0.11 U		< 0.019 U	0.12
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6	1/26/2021	857.57	4 - 6 ft	1801164623	Excavated	< 0.056 U	< 0.12 U			0.1	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.089	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated															
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	1.2	0.041 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.54	< 0.11 U	< 0.11 U	< 0.02 U	0.045 J
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	1.2	0.041 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.54	< 0.11 U		< 0.02 U	0.045 J
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.056 U			< 0.12 U	0.094	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.055 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.056 U			< 0.12 U	0.094	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.055 J	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated	< 0.46 U			< 2.9 U	0.99 J	< 0.37 U	< 0.67 U	< 0.54 U	< 0.95 U	< 0.48 U	< 0.38 U	< 2.7 U	< 2.7 U	< 0.47 U	< 0.45 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated															
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated															
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated															
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated															
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated															
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated															
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	2 - 4 ft	180-116462-1	Not Excavated	< 0.23 U			< 0.47 U	9 J	0.36 J	< 0.11 U	< 0.089 U	< 0.16 U	< 0.078 U	4.1 J	< 0.44 U	< 0.45 U	< 0.077 U	0.37 J
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	4 - 6 ft	180-116462-3	Not Excavated	< 0.057 U			< 0.12 U	0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.14	< 0.11 U	< 0.11 U	< 0.019 U	0.026 J
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	2 - 4 ft	180-100361-1	Not Excavated	< 0.019 U			< 0.12 U	0.093	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.088	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	2 - 4 ft	180-100362-1	Not Excavated	< 0.02 U			< 0.12 U	0.8	0.049 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.58	< 0.11 U	< 0.12 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	2 - 4 ft	180-101497-4	Not Excavated	< 0.022 U			< 0.13 U	0.045 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.032 J	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	2 - 4 ft	180-100362-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated	< 0.019 U			< 0.12 U	0.74	0.032 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.38	< 0.11 U	< 0.11 U	< 0.019 U	0.066 J
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated	< 0.078 U			< 0.49 U	0.8 J	< 0.062 UJ	< 0.11 U	< 0.092 U	< 0.16 U	< 0.081 U	0.39 J	< 0.45 U	< 0.46 U	< 0.08 U	< 0.075 UJ
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-2-4	12/19/2019	857.74	2 - 4 ft	180-100363-3	Excavated	< 0.018 U			< 0.12 U	0.049 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.043 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-2-4	12/19/2019	857.37	2 - 4 ft	180-100363-3	Excavated	< 0.02 U			< 0.12 U	0.028 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.018 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-2-4	12/19/2019	858.13	2 - 4 ft	180-100363-3	Excavated	< 0.018 U			< 0.12 U	0.044 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.021 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-2-4	12/19/2019	857.57	2 - 4 ft	180-100363-3	Excavated	< 0.019 U			< 0.12 U	0.98	0.041 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.66	< 0.11 U	< 0.11 U	< 0.02 U	0.086
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-2-4	12/19/2019	857.44	2 - 4 ft	180-100363-1	Excavated	< 0.019 U			< 0.12 U	0.076 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.053 J	< 0.11 U	< 0.11 U	< 0.019 U	0.024 J
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	2 - 4 ft	180-100363-1	Not Excavated	< 0.019 U			< 0.12 U	0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.095	< 0.11 U	< 0.11 U	< 0.02 U	0.074 J
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	2 - 4 ft	180-100363-1	Not Excavated	< 0.019 U			< 0.12 U	1.1 J	0.067 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.63 J	< 0.11 U	< 0.11 U	< 0.019 U	0.045 J
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	2 - 4 ft	180-100363-2	Not Excavated	< 0.019 U			< 0.12 U	0.52	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.29	< 0.11 U	< 0.11 U	< 0.02 U	0.086
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	2 - 4 ft	180-100363-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.015 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-2-4	12/19/2019	858.14	2 - 4 ft	180-100363-2	Excavated	< 0.019 U			< 0.12 U	0.42	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.24	< 0.11 U	< 0.11 U	< 0.019 U	0.05 J
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	2 - 4 ft	180-100363-2	Not Excavated	< 0.02 U			< 0.12 U	1.5	0.066 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.88	< 0.11 U	< 0.12 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	2 - 4 ft	180-100363-2	Not Excavated	< 0.019 U			< 0.12 U	0.035 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.028 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	2 - 4 ft	180-100363-1	Not Excavated	< 0.058 U			< 0.36 U	15	0.5	< 0.083 U	< 0.068 U	< 0.12 U	< 0.06 U	5.6	< 0.33 U	< 0.34 U	< 0.059 U	0.35
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	4 - 6 ft	180-116462-1	Not Excavated	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	6 - 8 ft	180-116462-3	Not Excavated	< 0.056 U			< 0.12 U	0.041 J	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	2 - 4 ft	180-116404-1	Not Excavated	< 0.06 U			< 0.12 U	0.85	0.029 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.57	< 0.11 U	< 0.12 U	< 0.02 U	0.049 J

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-2-4	1/27/2021	855.96	2 - 4 ft	180-116529-1	Excavated		0.11	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.26	< 0.11 U	0.41		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	4 - 6 ft	180-116529-3	Not Excavated		0.041 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.07 J	< 0.12 U	0.11		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated																				
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated		< 0.34 U	< 4 U	< 2.2 U	< 0.43 U	< 3.2 U	< 1.4 U	< 6.2 U		< 0.6 U	< 2.9 U	< 14 U	0.71 J	< 2.7 U	0.88 J		< 0.38 U	< 3.7 U	< 0.63 U	< 0.48 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated																				
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-2-4	1/13/2020	856.75	2 - 4 ft	180-100985-1	Excavated		< 0.36 U	< 4.3 U	< 2.4 U	< 0.45 U	< 3.4 U	< 1.5 U	< 6.5 U		< 0.63 U	< 3.1 U	< 15 U	0.77 J	< 2.8 U	0.84 J		< 0.4 U	< 3.9 U	< 0.67 U	< 0.51 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated																				
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-2-4	1/13/2020	856.74	2 - 4 ft	180-100985-1	Excavated		0.076 J	< 0.5 U	< 0.28 U	< 0.053 U	< 0.4 U	< 0.17 U	< 0.77 U		< 0.074 U	< 0.37 U	< 1.8 U	0.54	< 0.33 U	0.82		< 0.047 U	< 0.46 U	< 0.078 U	< 0.06 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated																				
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated																				
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-2-4	1/13/2020	856.82	2 - 4 ft	180-100985-2	Excavated		< 0.38 U	< 4.4 U	< 2.4 U	< 0.47 U	< 3.5 U	< 1.5 U	< 6.8 U		< 0.65 U	< 3.2 U	< 15 U	2.6	< 2.9 U	2.8		< 0.42 U	< 4 U	< 0.69 U	< 0.53 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated																				
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-2-4	1/14/2020	856.73	2 - 4 ft	180-101038-1	Excavated		0.14 J	< 0.84 U	< 0.47 U	< 0.089 U	< 0.67 U	< 0.29 U	< 1.3 U		< 0.12 U	< 0.61 U	< 2.9 U	1.1	< 0.55 U	1		< 0.079 U	< 0.76 U	< 0.13 U	< 0.1 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated																				
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-2-4	1/14/2020	856.72	2 - 4 ft	180-101038-1	Excavated		0.05 J	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.18	< 0.11 U	0.19		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated																				
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated																				
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated																				
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated																				
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated																				
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated																				
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-2-4	1/15/2020	856.71	2 - 4 ft	180-101084-2	Excavated		0.063 J	< 0.35 U	< 0.2 U	< 0.037 U	< 0.28 U	< 0.12 U	< 0.54 U		< 0.052 U	< 0.26 U	< 1.2 U	0.11 J	< 0.23 U	0.39		< 0.033 U	< 0.32 U	< 0.055 U	< 0.042 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated																				
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated																				
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated																				
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated																				
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated																				
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated																				
Northern Athletic Field	SSHS-B3181A	DUP-5	1/26/2021	857.57	2 - 4 ft	1801164621	Excavated	< 0.11 U	0.25	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.4	< 0.12 U	5.9		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.11 U	0.18	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.6 U	0.83	< 0.11 U	3.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6	1/26/2021	857.57	4 - 6 ft	1801164623	Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.03 J	< 0.11 U	0.13		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated																				
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated		0.056 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.37	< 0.12 U	1.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	2 - 4 ft	180-116462-1	Not Excavated	< 0.11 U	0.056 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.37	< 0.12 U	1.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.027 J	< 0.11 U	0.11		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.027 J	< 0.11 U	0.11		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-2-4	1/14/2020	856.70	2 - 4 ft	180-101038-1	Excavated		< 0.36 U	< 4.2 U	< 2.4 U	< 0.45 U	< 3.4 U	< 1.5 U	< 6.5 U		< 0.63 U	< 3.1 U	< 15 U	0.67 J	< 2.8 U	0.77 J		< 0.4 U	< 3.9 U	< 0.66 U	< 0.51 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated																				
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated																				
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated																				
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated																				
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated																				
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated																				
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	2 - 4 ft	180-116462-1	Not Excavated		0.59 J	< 0.69 U	< 0.39 U	< 0.074 U	< 0.56 U	< 0.24 U	< 1.1 U		< 0.1 U	< 0.51 U	< 2.4 U	4.8 J	< 0.46 U	10 J		< 0.066 U	< 0.63 U	< 0.11 U	< 0.083 U
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	4 - 6 ft	180-116462-3	Not Excavated		0.033 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.061 J	< 0.11 U	0.24		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	2 - 4 ft	180-100361-1	Not Excavated		0.017 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.11 U	0.11		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	2 - 4 ft	180-100362-1	Not Excavated		0.19	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.36	< 0.12 U	0.83		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	2 - 4 ft	180-101497-4	Not Excavated		< 0.017 U	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	0.037 J		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	2 - 4 ft	180-100362-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	2 - 4 ft	180-100362-1	Not Excavated		0.062 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.21	< 0.11 U	0.82		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	4 - 6 ft	180-100362-1	Not Excavated		0.072 J	< 0.72 U	< 0.4 U	< 0.076 U	< 0.58 U	< 0.25 U	< 1.1 U		< 0.11 U	< 0.52 U	< 2.5 U	0.35 J	< 0.48 U	0.85 J		< 0.068 U	< 0.66 U	< 0.11 U	< 0.086 U
Northern Athletic Field	SSHS-B3244	SSHS-B3244-SUB-2-4	12/19/2019	857.74	2 - 4 ft	180-100363-3	Excavated		0.022 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.061 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3245	SSHS-B3245-SUB-2-4	12/19/2019	857.37	2 - 4 ft	180-100363-3	Excavated		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.03 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-2-4	12/19/2019	858.13	2 - 4 ft	180-100363-3	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.052 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3247	SSHS-B3247-SUB-2-4	12/19/2019	857.57	2 - 4 ft	180-100363-3	Excavated		0.13	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.25	< 0.12 U	1.2		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3249	SSHS-B3249-SUB-2-4	12/19/2019	857.44	2 - 4 ft	180-100363-1	Excavated		0.017 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.032 J	< 0.12 U	0.096		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	2 - 4 ft	180-100363-1	Not Excavated		0.052 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.077	< 0.12 U	0.2		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	2 - 4 ft	180-100363-1	Not Excavated		0.062 J	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.46	< 0.12 U	1.3 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	2 - 4 ft	180-100363-2	Not Excavated		0.078	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.17	< 0.12 U	0.58		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	2 - 4 ft	180-100363-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.092 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3256	SSHS-B3256-SUB-2-4	12/19/2019	858.14	2 - 4 ft	180-100363-2	Excavated		0.06 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.16 J	< 0.12 U	0.5		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	2 - 4 ft	180-100363-2	Not Excavated		0.14	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.54	< 0.12 U	1.8		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	2 - 4 ft	180-100363-2	Not Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.038 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	2 - 4 ft	180-100363-1	Not Excavated		0.42	< 0.53 U	< 0.29 U	< 0.056 U	< 0.42 U	< 0.18 U	< 0.81 U		< 0.078 U	< 0.39 U	< 1.9 U	11	< 0.35 U	15		< 0.05 U	< 0.48 U	< 0.083 U	< 0.064 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	4 - 6 ft	180-116462-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	6 - 8 ft	180-116462-3	Not Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.056 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	2 - 4 ft	180-116404-1	Not Excavated		0.067 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.29	< 0.12 U	1.1		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	4 - 6 ft	180-116404-3	Not Excavated			2.576	< 0.021 U	0.11	< 0.019 U	0.053 J	< 0.16 U	< 0.015 U	< 0.044 U	0.25	0.28	0.35	0.14	0.23	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-2-4	12/18/2019	854.04	2 - 4 ft	180-100380-1	Excavated			5.694	< 0.024 U	0.33	< 0.022 U	0.22	< 0.18 U	< 0.017 U	< 0.051 U	0.48	0.49	0.53	0.26	0.66	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated			0.5	< 0.02 U	0.068 J	< 0.019 U	0.037 J	< 0.15 U	< 0.015 U	< 0.043 U	0.04 J	0.041 J	0.063 J	0.025 J	0.062 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated			0.052	< 0.02 U	0.029 J	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	0.03 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated			0.719	< 0.02 U	0.084	< 0.019 U	0.048 J	< 0.15 U	< 0.015 U	< 0.043 UT	0.06 J	0.058 J	0.09	0.031 J	0.078	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-2	Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-2-4	1/27/2021	854.73	2 - 4 ft	180-116529-3	Excavated	< 41 U	< 41 U																			
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-1	Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	2 - 4 ft	180-100380-1	Not Excavated			0.366	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	0.054 J	< 0.018 U	0.054 J	0.026 J	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-2-4	12/18/2019	855.80	2 - 4 ft	180-100380-2	Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.015 U	< 0.018 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-2-4	2/2/2021	855.85	2 - 4 ft	180-116723-1	Excavated	53 J																				
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	2 - 4 ft	180-100380-2	Not Excavated			0.085	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	0.015 J	< 0.017 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	4 - 6 ft	180-100380-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.015 U	< 0.018 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	856.44	2 - 4 ft	180-100380-1	Excavated			1.817	< 0.024 U	0.045 J	< 0.022 U	0.057 J	< 0.18 U	< 0.017 U	< 0.051 U	0.17	0.14	0.15	0.067 J	0.18	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	4 - 6 ft	180-100380-2	Not Excavated			1.759	< 0.023 U	0.1	< 0.021 U	0.05 J	< 0.17 U	< 0.017 U	< 0.049 U	0.14	0.17	0.24	0.097	0.15	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	856.56	2 - 4 ft	180-100380-2	Excavated			27.044	0.064 J	1.6	< 0.021 U	0.77	< 0.17 U	0.047 J	< 0.049 U	2.6	2.5	3.4	1.2	2.3	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	2 - 4 ft	180-100380-2	Not Excavated			2.793	< 0.022 U	0.12	< 0.021 U	0.068 J	< 0.17 U	< 0.016 U	< 0.047 U	0.26	0.25	0.37	0.12	0.23	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-2-4	12/18/2019	856.89	2 - 4 ft	180-100380-2	Excavated			70.31	0.11	1.3	< 0.022 U	2.1	< 0.17 U	0.037 J	< 0.049 U	5.6	4.5	4.8	2.1	4	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	4 - 6 ft	180-116665-1	Not Excavated			0.335	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.037 J	0.039 J	0.045 J	< 0.023 U	0.036 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	6 - 8 ft	180-116665-3	Not Excavated			1.773	< 0.022 U	0.12	< 0.02 U	0.069 J	< 0.16 U	< 0.016 U	< 0.047 U	0.16	0.18	0.19	0.089	0.17	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	2 - 4 ft	180-100380-2	Not Excavated			1.76	< 0.022 U	0.044 J	< 0.02 U	0.076	< 0.16 U	< 0.016 U	< 0.047 U	0.16	0.14	0.17	0.058 J	0.094	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	2 - 4 ft	180-100148-5	Not Excavated			0.568	< 0.021 U	0.065 J	< 0.02 U	0.022 J	< 0.16 U	< 0.016 U		< 0.014 U	< 0.016 U	< 0.018 U	< 0.022 U	0.44	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-2-4	12/17/2019	856.21	2 - 4 ft	180-100148-5	Excavated			30.6	0.93	0.89	< 0.043 U	0.79	< 0.34 U	0.059 J		3.5	1.8	2.4	< 0.047 U	1.5	< 0.038 U	< 0.029 U	< 0.058 U	< 0.84 U	< 0.055 U	< 0.54 U
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-2-4	12/17/2019	856.34	2 - 4 ft	180-100148-5	Excavated			184.2	1.5 =	6.2 =	< 0.1 U	11 =	< 0.84 U	0.87 J	< 0.24 U	13 =	11 =	12 =	3.9 =	6.6 =	< 0.092 U	< 0.07 U	< 0.14 U	< 2.1 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	4 - 6 ft	180-116529-1	Not Excavated			0.155	< 0.021 U	0.02 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	0.031 J	< 0.022 U	0.036 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	6 - 8 ft	180-116529-3	Not Excavated			0.014	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	2 - 4 ft	180-100148-6	Not Excavated			0.669	< 0.022 U	0.021 J	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	0.068 J	0.062 J	0.076	0.028 J	0.044 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-2-4	12/17/2019	857.22	2 - 4 ft	180-100148-6	Excavated			2.876	< 0.023 U	0.13	< 0.021 U	0.071 J	< 0.17 U	0.016 J	< 0.049 U	0.24	0.28	0.36	0.12	0.28	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-2-4	12/17/2019	857.35	2 - 4 ft	180-100148-5	Excavated			12.448	< 0.022 U	0.2	< 0.021 U	0.21	< 0.17 U	0.049 J		1.3	1.3	1.5	0.48	0.99	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-2-4	12/17/2019	857.15	2 - 4 ft	180-100148-5	Excavated			11.324	< 0.043 U	0.4	< 0.04 U	0.26	< 0.33 U	< 0.031 U		1.1	1.1	1.3	0.5	1	< 0.035 U	< 0.027 U	< 0.055 U	< 0.79 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-2-4	12/17/2019	855.96	2 - 4 ft	180-100148-4	Excavated			52.86	0.07 J	1.1	< 0.066 U	1.7	< 0.53 U	0.058 J		4.8	4.2	4.7	2	3.6	< 0.058 U	< 0.044 U	< 0.09 U	< 1.3 U	< 0.085 U	< 0.84 U
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-2-4	12/16/2019	856.22	2 - 4 ft	180-100148-2	Excavated			1.601	< 0.025 U	0.084 J	< 0.023 U	0.042 J	< 0.19 U	< 0.018 U		0.14	0.14	0.18	0.067 J	0.14	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-2-4	12/17/2019	857.02	2 - 4 ft	180-100148-5	Excavated			9.507	< 0.023 U	0.23	< 0.021 U	0.18	< 0.17 U	0.037 J		0.9	0.93	1	0.36	0.87	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-2-4	12/17/2019	857.20	2 - 4 ft	180-100148-5	Excavated			50.15	< 0.12 U	1.9	< 0.11 U	1.1	< 0.88 U	0.16 J		3.7	4.2 J	5.4 J	1.7	4.9 J	< 0.096 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-2-4	12/17/2019	856.38	2 - 4 ft	180-100148-3	Excavated			4.789	0.061 J	0.032 J	< 0.02 U	0.16	< 0.16 U	< 0.016 U		0.43	0.34	0.35	0.16	0.21	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-2-4	12/16/2019	856.13	2 - 4 ft	180-100148-2	Excavated			0.645	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		0.053 J	0.054 J	0.065 J	0.025 J	0.055 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-2-4	12/17/2019	856.19	2 - 4 ft	180-100148-5	Excavated			0.816	< 0.023 U	0.084	< 0.022 U	0.038 J	< 0.17 U	0.017 J		0.045 J	0.032 J	0.048 J	< 0.024 U	0.2	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-2-4	12/17/2019	856.73	2 - 4 ft	180-100148-5	Excavated			14.14	< 0.091 U	0.68	< 0.086 U	0.42	< 0.69 U	0.13 J		1	0.93	1.2	0.35	1.6	< 0.075 U	< 0.057 U	< 0.12 U	< 1.7 U	< 0.11 U	< 1.1 U
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	856.97	2 - 4 ft	180-100148-4	Excavated			189.8	3.2	2.3	< 0.22 U	7.4	< 1.8 U	0.63 J		16	12	14	4.7	8.5	< 0.2 U	< 0.15 U	< 0.31 U	< 4.4 U	< 0.29 U	< 2.8 U
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-4-6	1/27/2021	857.13	4 - 6 ft	180-116529-1	Excavated			6.042	< 0.022 U	0.14	< 0.021 U	0.082	< 0.17 U	< 0.016 U	< 0.047 U	0.68	0.65	0.66	0.31	0.45	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-6-8	1/27/2021	857.13	6 - 8 ft	180-116529-3	Excavated			4.686	0.056 J	0.087	< 0.021 U	0.2	< 0.17 U	0.045 J	< 0.048 U	0.39	0.29	0.33	0.1	0.23	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-2-4	12/16/2019	855.94	2 - 4 ft	180-100148-2	Excavated			0.853	< 0.023 U	0.018 J	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U		0.076 J	0.076 J	0.089	0.031 J	0.055 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-2-4	12/17/2019	856.00	2 - 4 ft	180-100148-6	Excavated			2.977	0.049 J	0.036 J	< 0.02 U	0.12	< 0.16 U	< 0.016 U	< 0.047 U	0.25	0.18	0.25	0.064 J	0.17	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	2 - 4 ft	180-100148-4	Not Excavated			0.322	< 0.043 U	0.049 J	< 0.041 U	< 0.039 U	< 0.33 U	< 0.031 U		< 0.028 U	< 0.033 U	< 0.037 U	< 0.045 U	0.1 J	< 0.036 U	< 0.027 U	< 0.056 U	< 0.8 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-2-4	12/17/2019	856.31	2 - 4 ft	180-100148-4	Excavated			2.06	< 0.25 U	< 0.19 U	< 0.23 U	< 0.22 U	< 1.9 U	< 0.18 U		0.24 J	< 0.19 U	< 0.21 U	< 0.26 U	0.43 J	< 0.21 U	< 0.16 U	< 0.32 U	< 4.6 U	< 0.3 U	< 3 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-2	Excavated			10.647	0.034 J	0.28	< 0.022 U	0.39	< 0.17 U	0.037 J		0.86	0.75	0.88	0.35	0.71	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-2	Excavated			0.577	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U		0.045 J	0.037 J	0.052 J	< 0.025 U	0.041 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	2 - 4 ft	180-100148-6	Not Excavated			7.137	0.022 J	0.31	< 0.021 U	0.14	< 0.17 U	0.022 J	< 0.048 U	0.59	0.63	0.76	0.3	0.7	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-2-4	1/28/2021	856.22	2 - 4 ft	180-116609-2	Excavated	290	290																			
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-2-4	12/16/2019	853.99	2 - 4 ft	180-100148-1	Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.015 U	< 0.017 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-2-4	12/16/2019	854.39	2 - 4 ft	180-100148-2	Excavated			1.745	< 0.022 U	0.037 J	< 0.02 U	0.047 J	< 0.16 U	0.023 J		0.15	0.12	0.13	0.037 J	0.082	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	4 - 6 ft	180-100148-1	Not Excavated			0.033	< 0.043 U	< 0.033 U	< 0.041 U	< 0.039 U	< 0.33 U	< 0.031 U	< 0.093 U	< 0.028 U	< 0.033 U	< 0.037 U	< 0.045 U	< 0.032 U	< 0.036 U	< 0.027 U	< 0.055 U	< 0.8 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-2-4	12/16/2019	853.34	2 - 4 ft	180-100148-1	Excavated			0.028	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.014 U	< 0.016 U	< 0.018 U	< 0.021 U	0.028 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-2-4	12/16/2019	854.14	2 - 4 ft	180-100148-1	Excavated			23.37	< 0.047 U	1	< 0.045 U	0.72	< 0.36 U	0.082 J	< 0.1 U	1.6	2.1	2.6	1	2.9	< 0.039 U	< 0.03 U	< 0.061 U	< 0.88 U	< 0.057 U	< 0.56 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	4 - 6 ft	180-100148-1	Not Excavated			1.726	< 0.045 U	< 0.034 U	< 0.042 U	< 0.04 U	< 0.34 U	< 0.033 U	< 0.096 U	0.17	0.19	0.21	0.076 J	0.18	< 0.037 U	< 0.028 U	< 0.057 U	< 0.83 U	< 0.054 U	< 0.53 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-2-4	12/16/2019	852.74	2 - 4 ft	180-100148-1	Excavated			0.885	< 0.023 U	0.02 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	0.086	0.088	0.11	0.038 J	0.084	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	2 - 4 ft	180-100148-1	Not Excavated			1.123	< 0.022 U	0.029 J	< 0.021 U	0.028 J	< 0.17 U	< 0.016 U	< 0.048 U	0.08	0.077	0.12	0.048 J	0.075 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	2 - 4 ft	180-100148-1	Not Excavated			19.255	< 0.12 U	0.74	< 0.11 U	0.59	< 0.89 U	< 0.085 U	< 0.25 U	2	1.7	2.5	0.86	1.3	< 0.097 U	< 0.074 U	< 0.15 U	< 2.2 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-2-4	12/16/2019	853.06	2 - 4 ft	180-100148-1	Excavated			0.244	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.026 J	0.024 J	0.031 J	< 0.021 U	0.027 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-4-6	12/16/2019	853.06	4 - 6 ft	180-100148-1	Excavated			0.141	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.015 J	< 0.017 U	0.026 J	< 0.024 U	0.019 J	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-2-4	12/16/2019	853.75	2 - 4 ft	180-100148-1	Excavated			0.461	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.043 J	0.051 J	0.061 J	< 0.022 U	0.039 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-2-4	12/17/2019	853.63	2 - 4 ft	180-100148-6	Excavated			20.32	0.29 J	0.83	< 0.1 U	0.69	< 0.85 U	0.15 J	< 0.24 U	1.4	1.5	1.7	0.65	1.6	< 0.092 U	< 0.07 U	< 0.14 U	< 2.1 U	< 0.13 U	< 1.3 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	6200 J+		1.123	0.036 J	< 0.016 U	< 0.02 U	0.023 J	< 0.16 U	< 0.015 U	< 0.045 U	0.061 J	0.04 J	0.059 J	< 0.022 U	0.075	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated			0.016	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	0.016 J	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-10-12	7/19/2021	851.57	10 - 12 ft	180-124670-1	Excavated	18																				

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	4 - 6 ft	180-116404-3	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.28	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-2-4	12/18/2019	854.04	2 - 4 ft	180-100380-1	Excavated	< 0.27 U	0.043 J	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.53	0.16	0.036 J	< 0.38 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.045 J	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.23 U	< 0.016 U	< 0.024 UT	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.069 J	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 UT	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-2	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-2-4	1/27/2021	854.73	2 - 4 ft	180-116529-3	Excavated																				
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	2 - 4 ft	180-100380-1	Not Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.04 J	< 0.018 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-2-4	12/18/2019	855.80	2 - 4 ft	180-100380-2	Excavated	< 0.26 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.016 U	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-2-4	2/2/2021	855.85	2 - 4 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	2 - 4 ft	180-100380-2	Not Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.024 J	< 0.018 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	4 - 6 ft	180-100380-1	Not Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.016 U	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	856.44	2 - 4 ft	180-100380-1	Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.17	< 0.018 U	0.018 J	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	4 - 6 ft	180-100380-2	Not Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.19	0.048 J	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	856.56	2 - 4 ft	180-100380-2	Excavated	< 0.26 U	0.13	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	2.8	0.63	0.077 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	2 - 4 ft	180-100380-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.3	0.06 J	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-2-4	12/18/2019	856.89	2 - 4 ft	180-100380-2	Excavated	< 0.26 U	0.39	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	4.3	0.87	0.87	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	4 - 6 ft	180-116665-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.049 J	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	6 - 8 ft	180-116665-3	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.17	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	2 - 4 ft	180-100380-2	Not Excavated	< 0.25 U	0.018 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.14	0.031 J	0.029 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	2 - 4 ft	180-100148-5	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-2-4	12/17/2019	856.21	2 - 4 ft	180-100148-5	Excavated	< 0.51 U	< 0.037 U	< 0.026 U	< 0.037 U	< 0.036 U	< 0.037 U	< 0.048 U	5.3	0.5	0.33 J	< 0.73 U	< 0.061 U	< 0.28 U	< 0.049 U	< 0.029 U	< 0.34 U	< 0.46 U	< 1.4 U	< 0.049 U	< 2.1 U
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-2-4	12/17/2019	856.34	2 - 4 ft	180-100148-5	Excavated	< 1.3 U	2.5 =	< 0.064 U	< 0.091 U	< 0.088 U	< 0.09 U	< 0.12 U	11 =	1.9 =	4.1 =	< 1.8 U	< 0.15 U	< 0.68 U	< 0.12 U	< 0.07 U	< 0.84 U	< 1.1 U	< 3.3 U	< 0.12 U	< 5.2 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	4 - 6 ft	180-116529-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	0.16 J	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	6 - 8 ft	180-116529-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	2 - 4 ft	180-100148-6	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.068 J	< 0.017 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-2-4	12/17/2019	857.22	2 - 4 ft	180-100148-6	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.28	0.12	0.025 J	< 0.36 U	< 0.03 U	0.16 J	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-2-4	12/17/2019	857.35	2 - 4 ft	180-100148-5	Excavated	< 0.25 U	0.031 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.1	0.3	0.1 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-2-4	12/17/2019	857.15	2 - 4 ft	180-100148-5	Excavated	< 0.48 U	0.038 J	< 0.025 UJ	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	1.1	0.36	0.068 J	< 0.69 U	< 0.057 U	< 0.26 U	< 0.046 U	< 0.027 U	< 0.33 U	< 0.43 U	< 1.3 UJ	< 0.046 U	
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-2-4	12/17/2019	855.96	2 - 4 ft	180-100148-4	Excavated	< 0.79 U	0.34	< 0.041 UJ	< 0.057 U	< 0.056 U	< 0.057 U	< 0.074 U	4	1	0.36 J	< 1.1 U	< 0.094 U	< 0.43 U	< 0.076 U	< 0.044 U	< 0.53 U	< 0.71 U	< 2.1 U	< 0.075 U	< 3.3 U
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-2-4	12/16/2019	856.22	2 - 4 ft	180-100148-2	Excavated	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.15	0.1	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-2-4	12/17/2019	857.02	2 - 4 ft	180-100148-5	Excavated	< 0.26 U	0.057 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.82	0.24	0.074 J	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-2-4	12/17/2019	857.20	2 - 4 ft	180-100148-5	Excavated	< 1.3 UJ	0.43	< 0.067 UJ	< 0.094 U	< 0.092 U	< 0.093 U	< 0.12 U	4 J	1.3	0.41 J	< 1.9 U	< 0.15 U	< 0.7 U	< 0.12 U	< 0.073 U	< 0.88 U	< 1.2 U		< 0.12 U	
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-2-4	12/17/2019	856.38	2 - 4 ft	180-100148-3	Excavated	< 0.24 U	0.061 J	< 0.013 UJ	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.38	0.12	0.04 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 UJ	< 0.023 U	< 1 UJ
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-2-4	12/16/2019	856.13	2 - 4 ft	180-100148-2	Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.06 J	0.077 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-2-4	12/17/2019	856.19	2 - 4 ft	180-100148-5	Excavated	< 0.26 U	< 0.019 U	< 0.013 UJ	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.054 J	< 0.018 U	0.033 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-2-4	12/17/2019	856.73	2 - 4 ft	180-100148-5	Excavated	< 1 U	0.12 J	< 0.053 UJ	< 0.074 U	< 0.072 U	< 0.073 U	< 0.096 U	1.2	0.52	0.33 J	< 1.5 U	< 0.12 U	< 0.55 U	< 0.098 U	< 0.057 U	< 0.69 U	< 0.92 U	< 2.7 U	< 0.098 U	< 4.2 U
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	856.97	2 - 4 ft	180-100148-4	Excavated	< 2.7 U	3.4	< 0.14 UJ	< 0.19 U	< 0.19 U	< 0.19 U	< 0.25 U	14	2.9	2.6 J	< 3.8 U	< 0.32 U	< 1.4 U	< 0.26 U	< 0.15 U	< 1.8 U	< 2.4 U	< 7.1 U	< 0.25 U	< 11 U
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-4-6	1/27/2021	857.13	4 - 6 ft	180-116529-1	Excavated	< 0.25 U	0.026 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.6	0.11	0.032 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-6-8	1/27/2021	857.13	6 - 8 ft	180-116529-3	Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.33	< 0.049 U	0.12 J	< 0.36 U	< 0.029 U	0.13 J	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-2-4	12/16/2019	855.94	2 - 4 ft	180-100148-2	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.071 J	0.077 J	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-2-4	12/17/2019	856.00	2 - 4 ft	180-100148-6	Excavated	< 0.24 U	0.044 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.23	0.1	0.037 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	2 - 4 ft	180-100148-4	Not Excavated	< 0.49 U	< 0.035 U	< 0.025 UJ	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	0.11 J	< 0.033 U	< 0.033 U	< 0.7 U	< 0.058 U	< 0.26 U	< 0.047 U	< 0.027 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.046 U	< 2 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-2-4	12/17/2019	856.31	2 - 4 ft	180-100148-4	Excavated	< 2.8 U	< 0.2 U	< 0.14 UJ	< 0.2 U	< 0.2 U	< 0.2 U	< 0.26 U	0.65 J	< 0.19 U	< 0.19 U	< 4 U	< 0.33 U	< 1.5 U	< 0.27 U	< 0.16 U	< 1.9 U	< 2.5 U	< 7.4 U	< 0.27 U	< 12 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-2	Excavated	< 0.26 U	0.11	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.82	0.2	0.13 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-2	Excavated	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.058 J	0.077 J	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	2 - 4 ft	180-100148-6	Not Excavated	< 0.25 U	0.054 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.6	0.2	0.053 J	< 0.36 U	< 0.03 U	0.19 J	0.041 J	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-2-4	1/28/2021	856.22	2 - 4 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-2-4	12/16/2019	853.99	2 - 4 ft	180-100148-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.016 U	< 0.018 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-2-4	12/16/2019	854.39	2 - 4 ft	180-100148-2	Excavated	< 0.25 U	0.019 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.18	0.081	0.069 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	4 - 6 ft	180-100148-1	Not Excavated	< 0.49 U	< 0.035 U	< 0.025 U	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	< 0.029 U	< 0.033 U	< 0.033 U	< 0.7 U	< 0.058 U	< 0.26 U	< 0.046 U	< 0.027 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.046 U	< 2 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-2-4	12/16/2019	853.34	2 - 4 ft	180-100148-1	Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 UJ	< 0.016 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.96 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-2-4	12/16/2019	854.14	2 - 4 ft	180-100148-1	Excavated	< 0.54 U	0.34	< 0.027 U	< 0.039 U	< 0.038 U	< 0.038 U	< 0.05 U	1.7	0.48	0.24 J	< 0.77 U	< 0.063 U	< 0.29 U	< 0.051 U	< 0.03 U	< 0.36 U	< 0.48 U	< 1.4 U	< 0.051 U	< 2.2 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	4 - 6 ft	180-100148-1	Not Excavated	< 0.51 U	< 0.036 U	< 0.026 U	< 0.037 U	< 0.036 U	< 0.036 U	< 0.047 U	0.17	0.071 J	< 0.034 U	< 0.72 U	< 0.06 U	< 0.27 U	< 0.048 U	< 0.028 U	< 0.34 U	< 0.45 U	< 1.3 U	< 0.048 U	< 2.1 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-2-4	12/16/2019	852.74	2 - 4 ft	180-100148-1	Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.094	0.02 J	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	2 - 4 ft	180-100148-1	Not Excavated	< 0.25 U	0.02 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.11	0.027 J	0.017 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	2 - 4 ft	180-100148-1	Not Excavated	< 1.3 U	0.27 J	< 0.068 U	< 0.096 U	< 0.093 U	< 0.094 U	< 0.12 U	1.9	0.51	0.14 J	< 1.9 U	< 0.16 U	< 0.71 U	< 0.13 U	< 0.074 U	< 0.89 U	< 1.2 U	< 3.5 U	< 0.13 U	< 5.5 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-2-4	12/16/2019	853.06	2 - 4 ft	180-100148-1	Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.024 J	< 0.016 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 0.95 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-4-6	12/16/2019	853.06	4 - 6 ft	180-100148-1	Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.023 J	< 0.018 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-2-4	12/16/2019	853.75	2 - 4 ft	180-100148-1	Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.053 J	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-2-4	12/17/2019	853.63	2 - 4 ft	180-100148-6	Excavated	< 1.3 U	0.14 J	< 0.064 U	< 0.091 U	< 0.089 U	< 0.09 U	< 0.12 U	1.3	0.64	0.42 J	< 1.8 U	< 0.15 U	< 0.68 U	< 0.12 U	< 0.07 U	< 0.85 U	< 1.1 U	< 3.3 U	< 0.12 U	< 5.2 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.013 U	< 0.015 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.012 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 0.92 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	< 0.23 UJ	< 0.017 U	< 0.012 UJ	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.21	< 0.016 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 UJ
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 0.95 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 0.95 U
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-10-12	7/19/2021	851.57	10 - 12 ft	180-124670-1	Excavated																				

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	4 - 6 ft	180-116404-3	Not Excavated	< 0.054 U			< 0.11 U	0.3	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	0.18	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-2-4	12/18/2019	854.04	2 - 4 ft	180-100380-1	Excavated	< 0.02 U			< 0.13 U	0.61	0.059 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.47	< 0.12 U	< 0.12 U	< 0.021 U	0.098
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.052 U	< 0.11 U			0.043 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	0.05 J	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.053 U	< 0.11 U			0.071 T	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	0.07	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-2	Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-2-4	1/27/2021	854.73	2 - 4 ft	180-116529-3	Excavated															
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-1	Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	2 - 4 ft	180-100380-1	Not Excavated	< 0.021 U			< 0.13 U	0.056 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	0.039 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-2-4	12/18/2019	855.80	2 - 4 ft	180-100380-2	Excavated	< 0.02 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.016 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-2-4	2/2/2021	855.85	2 - 4 ft	180-116723-1	Excavated															
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	2 - 4 ft	180-100380-2	Not Excavated	< 0.02 U			< 0.12 U	0.026 J	< 0.016 U	< 0.028 UJ	< 0.023 U	< 0.04 U	< 0.02 U	< 0.016 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	4 - 6 ft	180-100380-1	Not Excavated	< 0.02 U			< 0.13 U	< 0.022 UJ	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.017 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	856.44	2 - 4 ft	180-100380-1	Excavated	< 0.02 U			< 0.13 U	0.27	0.019 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	0.14	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	4 - 6 ft	180-100380-2	Not Excavated	< 0.02 U			< 0.12 U	0.2	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.13	< 0.11 U	< 0.12 U	< 0.02 U	0.028 J
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	856.56	2 - 4 ft	180-100380-2	Excavated	< 0.02 U			< 0.12 U	3.4 J	0.17	< 0.028 UJ	< 0.023 U	< 0.04 U	< 0.02 U	1.8	< 0.11 U	< 0.12 U	< 0.02 U	0.21
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	2 - 4 ft	180-100380-2	Not Excavated	< 0.019 U			< 0.12 U	0.36	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.2	< 0.11 U	< 0.11 U	< 0.019 U	0.032 J
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-2-4	12/18/2019	856.89	2 - 4 ft	180-100380-2	Excavated	< 0.02 U			< 0.12 U	14	0.27	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	3.4	< 0.11 U	< 0.12 U	< 0.02 U	0.16
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	4 - 6 ft	180-116665-1	Not Excavated	< 0.058 U			< 0.12 U	0.054 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	6 - 8 ft	180-116665-3	Not Excavated	< 0.057 U			< 0.12 U	0.23	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.13	< 0.11 U	< 0.11 U	< 0.019 U	0.037 J
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	2 - 4 ft	180-100380-2	Not Excavated	< 0.019 U			< 0.12 U	0.28	0.034 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.081	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	2 - 4 ft	180-100148-5	Not Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.085	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-2-4	12/17/2019	856.21	2 - 4 ft	180-100148-5	Excavated	< 0.039 U			< 0.25 U	2.8	0.64	< 0.056 U	< 0.046 U	< 0.081 U	< 0.041 U	1.4	< 0.23 U	< 0.23 U	< 0.04 U	0.18
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-2-4	12/17/2019	856.34	2 - 4 ft	180-100148-5	Excavated	< 0.096 U			< 0.6 U	33 =	6.7 =	< 0.14 U	< 0.11 U	< 0.2 U	< 0.099 U	6.7 =	< 0.55 U	< 0.57 U	< 0.098 U	3.3 =
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	4 - 6 ft	180-116529-1	Not Excavated	< 0.056 U			< 0.12 U	0.03 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	6 - 8 ft	180-116529-3	Not Excavated	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	2 - 4 ft	180-100148-6	Not Excavated	< 0.019 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.049 J	< 0.11 U	< 0.11 U	< 0.019 U	0.024 J
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-2-4	12/17/2019	857.22	2 - 4 ft	180-100148-6	Excavated	< 0.019 U			< 0.12 U	0.28	0.015 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.23	< 0.11 U	< 0.11 U	< 0.02 U	0.083
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-2-4	12/17/2019	857.35	2 - 4 ft	180-100148-5	Excavated	< 0.019 U			< 0.12 U	1.7	0.038 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.94	< 0.11 U	< 0.11 U	< 0.019 U	0.15
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-2-4	12/17/2019	857.15	2 - 4 ft	180-100148-5	Excavated	< 0.037 U			< 0.23 U	1.4	0.094 J	< 0.053 U	< 0.043 U	< 0.076 U	< 0.038 U	0.91	< 0.21 U	< 0.22 U	< 0.038 U	0.12 J
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-2-4	12/17/2019	855.96	2 - 4 ft	180-100148-4	Excavated	< 0.061 U			< 0.38 U	9.5	0.26	< 0.087 U	< 0.071 U	< 0.12 U	< 0.063 U	3.5	< 0.35 U	< 0.36 U	< 0.062 U	0.19 J
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-2-4	12/16/2019	856.22	2 - 4 ft	180-100148-2	Excavated	< 0.021 U			< 0.13 U	0.18	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	0.12	< 0.12 U	< 0.13 U	< 0.022 U	0.027 J
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-2-4	12/17/2019	857.02	2 - 4 ft	180-100148-5	Excavated	< 0.02 U			< 0.12 U	1.3	0.037 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.74	< 0.11 U	< 0.12 U	< 0.02 U	0.14
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-2-4	12/17/2019	857.20	2 - 4 ft	180-100148-5	Excavated	< 0.1 U			< 0.62 U	7.3 J	0.25 J	< 0.14 U	< 0.12 U	< 0.2 U	< 0.1 U	4.1	< 0.57 U	< 0.59 U	< 0.1 U	0.61
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-2-4	12/17/2019	856.38	2 - 4 ft	180-100148-3	Excavated	< 0.019 U			< 0.12 U	0.88	0.056 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.21	< 0.11 U	< 0.11 U	< 0.019 U	0.028 J
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-2-4	12/16/2019	856.13	2 - 4 ft	180-100148-2	Excavated	< 0.019 U			< 0.12 U	0.076 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.048 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-2-4	12/17/2019	856.19	2 - 4 ft	180-100148-5	Excavated	< 0.02 U			< 0.12 U	0.077 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.07 J	< 0.11 U	< 0.12 U	< 0.02 U	0.053 J
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-2-4	12/17/2019	856.73	2 - 4 ft	180-100148-5	Excavated	< 0.079 U			< 0.49 U	1.6	0.22 J	< 0.11 U	< 0.092 U	< 0.16 U	< 0.081 U	1.1	< 0.45 U	< 0.46 U	< 0.081 U	0.49
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	856.97	2 - 4 ft	180-100148-4	Excavated	< 0.21 U			< 1.3 U	33	3.1	< 0.3 U	< 0.24 U	< 0.42 U	< 0.21 U	8.1	< 1.2 U	< 1.2 U	< 0.21 U	2.9
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-4-6	1/27/2021	857.13	4 - 6 ft	180-116529-1	Excavated	< 0.057 U			< 0.12 U	0.92	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.37	< 0.11 U	< 0.11 U	< 0.019 U	0.058 J
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-6-8	1/27/2021	857.13	6 - 8 ft	180-116529-3	Excavated	< 0.058 U			< 0.12 U	0.79	0.07 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.23	< 0.11 U	< 0.11 U	< 0.02 U	0.12
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-2-4	12/16/2019	855.94	2 - 4 ft	180-100148-2	Excavated	< 0.02 U			< 0.13 U	0.12	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.051 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-2-4	12/17/2019	856.00	2 - 4 ft	180-100148-6	Excavated	< 0.019 U			< 0.12 U	0.45	0.044 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.15	< 0.11 U	< 0.11 U	< 0.019 U	0.051 J
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	2 - 4 ft	180-100148-4	Not Excavated	< 0.037 U			< 0.23 U	< 0.04 U	< 0.029 U	< 0.054 U	< 0.044 U	< 0.077 U	< 0.039 U	0.08 J	< 0.21 U	< 0.22 U	< 0.038 U	< 0.036 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-2-4	12/17/2019	856.31	2 - 4 ft	180-100148-4	Excavated	< 0.22 U			< 1.3 U	< 0.23 U	< 0.17 U	< 0.31 U	< 0.25 U	< 0.44 U	< 0.22 U	0.29 J	< 1.2 U	< 1.3 U	< 0.22 U	< 0.21 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-2	Excavated	< 0.02 U			< 0.12 U	1.8	0.083	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	0.64	< 0.11 U	< 0.12 U	0.092 J	0.13
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-2	Excavated	< 0.021 U			< 0.13 U	0.073 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	0.037 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	2 - 4 ft	180-100148-6	Not Excavated	< 0.019 U			< 0.12 U	0.93	0.045 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.59	< 0.11 U	< 0.11 U	< 0.02 U	0.11
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-2-4	1/28/2021	856.22	2 - 4 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-2-4	12/16/2019	853.99	2 - 4 ft	180-100148-1	Excavated	< 0.02 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.016 U	< 0.12 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-2-4	12/16/2019	854.39	2 - 4 ft	180-100148-2	Excavated	< 0.019 U			< 0.12 U	0.17	0.024 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.064 J	< 0.11 U	< 0.11 U	< 0.019 U	0.079
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	4 - 6 ft	180-100148-1	Not Excavated	< 0.037 U			< 0.23 U	< 0.04 U	< 0.029 U	< 0.054 U	< 0.044 U	< 0.077 U	< 0.039 U	< 0.03 U	< 0.21 U	< 0.22 U	< 0.038 U	< 0.036 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-2-4	12/16/2019	853.34	2 - 4 ft	180-100148-1	Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-2-4	12/16/2019	854.14	2 - 4 ft	180-100148-1	Excavated	< 0.041 U			< 0.26 U	2.9	0.11 J	< 0.059 U	< 0.048 U	< 0.084 U	< 0.042 U	2.1	< 0.24 U	< 0.24 U	< 0.042 U	0.26
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	4 - 6 ft	180-100148-1	Not Excavated	< 0.039 U			< 0.24 U	0.23	< 0.03 U	< 0.056 U	< 0.045 U	< 0.079 U	< 0.04 U	0.14 J	< 0.22 U	< 0.23 U	< 0.04 U	< 0.037 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-2-4	12/16/2019	852.74	2 - 4 ft	180-100148-1	Excavated	< 0.02 U			< 0.12 U	0.13	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.067 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	2 - 4 ft	180-100148-1	Not Excavated	< 0.019 U			< 0.12 U	0.19	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.069 J	< 0.11 U	< 0.11 U	< 0.02 U	0.061 J
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	2 - 4 ft	180-100148-1	Not Excavated	< 0.1 U			< 0.63 U	2.9	0.095 J	< 0.15 U	< 0.12 U	< 0.21 U	< 0.1 U	1.1	< 0.58 U	< 0.6 U	< 0.1 U	0.33 J
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-2-4	12/16/2019	853.06	2 - 4 ft	180-100148-1	Excavated	< 0.018 U			< 0.11 U	0.037 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.021 J	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-4-6	12/16/2019	853.06	4 - 6 ft	180-100148-1	Excavated	< 0.02 U			< 0.13 U	0.022 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.016 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-2-4	12/16/2019	853.75	2 - 4 ft	180-100148-1	Excavated	< 0.018 U			< 0.11 U	0.066 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.032 J	< 0.11 U	< 0.11 U	< 0.019 U	0.018 J
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-2-4	12/17/2019	853.63	2 - 4 ft	180-100148-6	Excavated	< 0.096 U			< 0.6 U	2.8	0.45	< 0.14 U	< 0.11 U	< 0.2 U	< 0.1 U	1.3	< 0.55 U	< 0.57 U	< 0.098 U	0.7
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated	< 0.017 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.014 U	< 0.098 U	< 0.1 U	< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	< 0.018 U			< 0.11 U	0.19	0.12	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.049 J	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated	< 0.017 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-10-12	7/19/2021	851.57	10 - 12 ft	180-124670-1	Excavated															

FINAL

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	4 - 6 ft	180-116404-3	Not Excavated		0.021 J	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.092	< 0.11 U	0.4		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-2-4	12/18/2019	854.04	2 - 4 ft	180-100380-1	Excavated		0.085	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.41	< 0.12 U	0.73		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3265A	DUP-7	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.1 U	0.029 J	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.021 J	< 0.11 U	0.044 J		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.022 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.1 U	0.026 J	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.04 J	< 0.11 U	0.078		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-2	Excavated		< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3268A	SSHS-B3268A-SUB-2-4	1/27/2021	854.73	2 - 4 ft	180-116529-3	Excavated																				
Northern Athletic Field	SSHS-B3269	SSHS-B3269-SUB-2-4	12/18/2019	854.73	2 - 4 ft	180-100380-1	Excavated		< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	2 - 4 ft	180-100380-1	Not Excavated		< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.033 J	< 0.13 U	0.064 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3274	SSHS-B3274-SUB-2-4	12/18/2019	855.80	2 - 4 ft	180-100380-2	Excavated		< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.028 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3274A	SSHS-B3274A-SUB-2-4	2/2/2021	855.85	2 - 4 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	2 - 4 ft	180-100380-2	Not Excavated		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.02 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	4 - 6 ft	180-100380-1	Not Excavated		< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 UJ	< 0.12 U	< 0.019 UJ		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-2-4	12/18/2019	856.44	2 - 4 ft	180-100380-1	Excavated		0.024 J	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.18	< 0.12 U	0.25		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	4 - 6 ft	180-100380-2	Not Excavated		0.036 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.068 J	< 0.12 U	0.24		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-2-4	12/18/2019	856.56	2 - 4 ft	180-100380-2	Excavated		0.31	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	1.3	< 0.12 U	3.8		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	2 - 4 ft	180-100380-2	Not Excavated		0.035 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.13	< 0.11 U	0.41		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3282	SSHS-B3282-SUB-2-4	12/18/2019	856.89	2 - 4 ft	180-100380-2	Excavated		0.26	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	12	< 0.12 U	12		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	4 - 6 ft	180-116665-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.12 U	0.048 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	6 - 8 ft	180-116665-3	Not Excavated		0.045 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.1	< 0.11 U	0.24		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	2 - 4 ft	180-100380-2	Not Excavated		0.026 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.24	< 0.11 U	0.23		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	2 - 4 ft	180-100148-5	Not Excavated		0.021 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3285	SSHS-B3285-SUB-2-4	12/17/2019	856.21	2 - 4 ft	180-100148-5	Excavated		0.34	< 0.36 U	< 0.2 U	< 0.038 U	< 0.29 U	< 0.13 U	< 0.55 U		< 0.053 U	< 0.26 U	< 1.3 U	2.4	< 0.24 U	6.3		< 0.034 U	< 0.33 U	< 0.056 U	< 0.043 U
Northern Athletic Field	SSHS-B3286	SSHS-B3286-SUB-2-4	12/17/2019	856.34	2 - 4 ft	180-100148-5	Excavated		5.9 =	< 0.88 U	< 0.49 U	< 0.094 U	< 0.7 U	< 0.31 U	< 1.4 U		< 0.13 U	< 0.64 U	< 3.1 U	34 =	< 0.58 U	26 =		< 0.083 U	< 0.8 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	4 - 6 ft	180-116529-1	Not Excavated		0.028 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.03 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	6 - 8 ft	180-116529-3	Not Excavated		0.014 J	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	2 - 4 ft	180-100148-6	Not Excavated		0.017 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.047 J	< 0.11 U	0.1		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3291	SSHS-B3291-SUB-2-4	12/17/2019	857.22	2 - 4 ft	180-100148-6	Excavated		0.11	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.16	< 0.12 U	0.33		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3292	SSHS-B3292-SUB-2-4	12/17/2019	857.35	2 - 4 ft	180-100148-5	Excavated		0.44	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.55	< 0.12 U	1.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3293	SSHS-B3293-SUB-2-4	12/17/2019	857.15	2 - 4 ft	180-100148-5	Excavated		0.22	< 0.34 U	< 0.19 UJ	< 0.036 U	< 0.27 U	< 0.12 U	< 0.52 U		< 0.05 U	< 0.25 U	< 1.2 U	0.68	< 0.23 U	1.3		< 0.032 U	< 0.31 U	< 0.053 U	< 0.041 U
Northern Athletic Field	SSHS-B3295	SSHS-B3295-SUB-2-4	12/17/2019	855.96	2 - 4 ft	180-100148-4	Excavated		0.53	< 0.56 U	< 0.31 UJ	< 0.059 U	< 0.45 U	< 0.19 U	< 0.85 U		< 0.083 U	< 0.41 U	< 2 U	5.6	< 0.37 U	7.4		< 0.053 U	< 0.51 U	< 0.087 U	< 0.067 U
Northern Athletic Field	SSHS-B3296	SSHS-B3296-SUB-2-4	12/16/2019	856.22	2 - 4 ft	180-100148-2	Excavated		0.032 J	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.1	< 0.13 U	0.21		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3297	SSHS-B3297-SUB-2-4	12/17/2019	857.02	2 - 4 ft	180-100148-5	Excavated		0.32	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.51	< 0.12 U	1.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3298	SSHS-B3298-SUB-2-4	12/17/2019	857.20	2 - 4 ft	180-100148-5	Excavated		2.1	< 0.91 U	< 0.51 UJ	< 0.097 U	< 0.73 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	3.3	< 0.61 U	6.8 J		< 0.086 U	< 0.83 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3300	SSHS-B3300-SUB-2-4	12/17/2019	856.38	2 - 4 ft	180-100148-3	Excavated		0.032 J	< 0.17 U	< 0.096 UJ	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.6 U	0.69	< 0.11 U	0.71		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3301	SSHS-B3301-SUB-2-4	12/16/2019	856.13	2 - 4 ft	180-100148-2	Excavated		0.016 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.045 J	< 0.12 U	0.071 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3302	SSHS-B3302-SUB-2-4	12/17/2019	856.19	2 - 4 ft	180-100148-5	Excavated		0.11	< 0.18 U	< 0.1 UJ	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.09	< 0.12 U	0.052 J		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3303	SSHS-B3303-SUB-2-4	12/17/2019	856.73	2 - 4 ft	180-100148-5	Excavated		1.3	< 0.72 U	< 0.4 UJ	< 0.077 U	< 0.58 U	< 0.25 U	< 1.1 U		< 0.11 U	< 0.53 U	< 2.5 U	1.1	< 0.48 U	1.6		< 0.068 U	< 0.66 U	< 0.11 U	< 0.087 U
Northern Athletic Field	SSHS-B3304	SSHS-B3304-SUB-2-4	12/17/2019	856.97	2 - 4 ft	180-100148-4	Excavated		4.9	< 1.9 U	< 1 UJ	< 0.2 U	< 1.5 U	< 0.66 U	< 2.9 U		< 0.28 U	< 1.4 U	< 6.6 U	32	< 1.2 U	26		< 0.18 U	< 1.7 U	< 0.29 U	< 0.23 U
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-4-6	1/27/2021	857.13	4 - 6 ft	180-116529-1	Excavated		0.16	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.17	< 0.12 U	0.88		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3304A	SSHS-B3304A-SUB-6-8	1/27/2021	857.13	6 - 8 ft	180-116529-3	Excavated		0.18	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.78	< 0.12 U	0.71		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3306	SSHS-B3306-SUB-2-4	12/16/2019	855.94	2 - 4 ft	180-100148-2	Excavated		0.044 J	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.043 J	< 0.12 U	0.12		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3307	SSHS-B3307-SUB-2-4	12/17/2019	856.00	2 - 4 ft	180-100148-6	Excavated		0.07 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.6 U	0.43	< 0.11 U	0.42		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	2 - 4 ft	180-100148-4	Not Excavated		0.032 J	< 0.34 U	< 0.19 UJ	< 0.036 U	< 0.27 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	< 0.04 U	< 0.23 U	< 0.036 U		< 0.032 U	< 0.31 U	< 0.054 U	< 0.041 U
Northern Athletic Field	SSHS-B3309	SSHS-B3309-SUB-2-4	12/17/2019	856.31	2 - 4 ft	180-100148-4	Excavated		< 0.17 U	< 2 U	< 1.1 UJ	< 0.21 U	< 1.6 U	< 0.69 U	< 3 U		< 0.29 U	< 1.4 U	< 6.9 U	< 0.23 U	< 1.3 U	0.45 J		< 0.19 U	< 1.8 U	< 0.31 U	< 0.24 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-2-4	12/16/2019	856.94	2 - 4 ft	180-100148-2	Excavated		0.33	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	1.2	< 0.12 U	1.6		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3314	SSHS-B3314-SUB-4-6	12/16/2019	856.94	4 - 6 ft	180-100148-2	Excavated		0.023 J	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.062 J	< 0.13 U	0.072 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	2 - 4 ft	180-100148-6	Not Excavated		0.27	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.43	< 0.12 U	0.93		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3322A	SSHS-B3322A-SUB-2-4	1/28/2021	856.22	2 - 4 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3325	SSHS-B3325-SUB-2-4	12/16/2019	853.99	2 - 4 ft	180-100148-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3326	SSHS-B3326-SUB-2-4	12/16/2019	854.39	2 - 4 ft	180-100148-2	Excavated		0.21	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.21	< 0.11 U	0.24		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	4 - 6 ft	180-100148-1	Not Excavated		0.033 J	< 0.34 U	< 0.19 U	< 0.036 U	< 0.27 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	< 0.04 U	< 0.23 U	< 0.035 U		< 0.032 U	< 0.31 U	< 0.053 U	< 0.041 U
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-2-4	12/16/2019	853.34	2 - 4 ft	180-100148-1	Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3328	SSHS-B3328-SUB-2-4	12/16/2019	854.14	2 - 4 ft	180-100148-1	Excavated		0.96	< 0.37 U	< 0.21 U	< 0.04 U	< 0.3 U	< 0.13 U	< 0.58 U		< 0.056 U	< 0.27 U	< 1.3 U	1.4	< 0.25 U	2.8		< 0.036 U	< 0.34 U	< 0.059 U	< 0.045 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	4 - 6 ft	180-100148-1	Not Excavated		< 0.03 U	< 0.35 U	< 0.2 U	< 0.038 U	< 0.28 U	< 0.12 U	< 0.54 U		< 0.053 U	< 0.26 U	< 1.2 U	0.069 J	< 0.24 U	0.22		< 0.034 U	< 0.32 U	< 0.055 U	< 0.043 U
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-2-4	12/16/2019	852.74	2 - 4 ft	180-100148-1	Excavated		0.018 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.04 J	< 0.12 U	0.11		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	2 - 4 ft	180-100148-1	Not Excavated		0.059 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.1	< 0.12 U	0.14		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	2 - 4 ft	180-100148-1	Not Excavated		0.3 J	< 0.93 U	< 0.52 U	< 0.099 U	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.68 U	< 3.3 U	1.2	< 0.62 U	2.3		< 0.088 U	< 0.85 U	< 0.15 U	< 0.11 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-2-4	12/16/2019	853.06	2 - 4 ft	180-100148-1	Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.019 J	< 0.11 U	0.035 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3332	SSHS-B3332-SUB-4-6	12/16/2019	853.06	4 - 6 ft	180-100148-1	Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.02 J		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3333	SSHS-B3333-SUB-2-4	12/16/2019	853.75	2 - 4 ft	180-100148-1	Excavated		0.017 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.035 J	< 0.11 U	0.064 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3342	SSHS-B3342-SUB-2-4	12/17/2019	853.63	2 - 4 ft	180-100148-6	Excavated		1.1	< 0.88 U	< 0.49 U	< 0.094 U	< 0.71 U	< 0.31 U	< 1.4 U		< 0.13 U	< 0.64 U	< 3.1 U	2.3	< 0.58 U	2.6		< 0.083 U	< 0.8 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	10 - 12 ft	180-100361-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 UJ	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.26 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	6 - 8 ft	180-100361-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	8 - 10 ft	180-100361-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-10-12	7/19/2021	851.57	10 - 12 ft	180-124670-1	Excavated																				

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-14-16	7/19/2021	851.57	14 - 16 ft	180-124670-1	Excavated	12000																				
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated			0.383	< 0.02 U	0.098	< 0.019 U	0.049 J	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	0.061 J	0.027 J	0.075	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated			0.217	< 0.02 U	0.075	< 0.019 U	0.04 J	< 0.15 U	< 0.014 U	< 0.043 U	< 0.031 U	< 0.03 U	0.041 J	< 0.021 U	0.05 J	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 UT	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 UT	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated			0.547	< 0.019 U	0.083	< 0.018 U	0.04 J	< 0.15 U	< 0.014 U	< 0.042 U	0.033 J	0.051 J	0.067 J	< 0.02 U	0.096	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated			1.775	< 0.021 U	0.055 J	< 0.02 U	0.039 J	< 0.16 U	< 0.015 U	< 0.045 U	0.17	0.13	0.18	0.06 J	0.12	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated		57																			
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated			6.566	< 0.021 U	0.2	< 0.02 U	0.16	< 0.16 U	0.022 J	< 0.046 U	0.61	0.63	0.71	0.27	0.52	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated			0.751	< 0.02 U	0.025 J	< 0.019 U	0.019 J	< 0.15 U	< 0.015 U	< 0.044 U	0.076	0.066 J	0.073	0.032 J	0.054 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated		72																			
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated			1.159	< 0.022 U	0.021 J	0.028 J	0.02 J	< 0.16 U	0.029 J	< 0.046 U	0.075	0.056 J	0.082	0.044 J	0.07 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated			1.811	< 0.021 U	0.078	< 0.02 U	0.054 J	< 0.16 U	< 0.015 U	< 0.045 U	0.17	0.15	0.17	0.071 J	0.14	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated			1.026	< 0.021 U	0.036 J	< 0.02 U	0.038 J	< 0.16 U	< 0.015 U	< 0.046 U	0.11	0.084	0.087	0.038 J	0.068 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated		70																			
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated			5.23	< 0.19 U	< 0.14 U	< 0.18 U	< 0.17 U	< 1.4 U	0.15 J	< 0.4 U	< 0.29 U	< 0.28 U	< 0.16 U	< 0.19 U	< 0.14 U	< 0.15 U	< 0.12 U	< 0.24 U	< 3.5 U	< 0.23 U	< 2.2 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated			0.157	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	0.032 J	< 0.023 U	0.025 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated		< 39 U																			
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated			11.22	0.24	0.066 J	< 0.021 U	0.49	< 0.17 U	0.028 J	< 0.047 U	0.99	0.82	0.79	0.41	0.48	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	70																				
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated			19.314	0.039 J	0.036 J	< 0.019 U	0.29	< 0.16 U	< 0.015 U	< 0.044 U	2.2	1.2	1.4	0.44	1	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated			6.281	< 0.021 U	0.052 J	< 0.02 U	0.1	< 0.16 U	< 0.015 U	< 0.045 U	0.62	0.61	0.63	0.26	0.52	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated			0.262	< 0.022 U	< 0.017 U	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	0.034 J	0.036 J	< 0.023 U	0.029 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated			0.621	< 0.021 U	0.021 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.06 J	0.059 J	0.07 J	0.029 J	0.056 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	2 - 4 ft	1801164621	Not Excavated			0.425	< 0.023 U	0.025 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	0.047 J	0.045 J	0.053 J	0.024 J	0.032 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated			0.643	< 0.021 U	0.046 J	< 0.02 U	0.022 J	< 0.16 U	< 0.015 U	< 0.045 U	0.059 J	0.062 J	0.08	0.028 J	0.052 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	4 - 6 ft	1801164623	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	2 - 4 ft	180-116462-1	Not Excavated			16.408	< 0.022 U	0.58	< 0.021 U	0.36	< 0.17 U	< 0.016 U	< 0.048 U	1.5	1.4	2.1	0.55	1.2	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	4 - 6 ft	180-116462-3	Not Excavated			4.457	< 0.022 U	0.2	< 0.021 U	0.094	< 0.17 U	< 0.016 U	< 0.048 U	0.41	0.47	0.59	0.19	0.37	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	2 - 4 ft	180-116462-1	Not Excavated			150.45	< 0.12 U	6	< 0.11 U	3.5	< 0.88 U	< 0.084 U	< 0.25 U	14	13	17	6	12	< 0.096 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	4 - 6 ft	180-116462-3	Not Excavated			17.857	< 0.022 U	0.71	< 0.02 U	0.46	< 0.16 U	< 0.016 U	< 0.047 U	1.7	1.6	2.2	0.58	1.5	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated			3.401	< 0.022 U	0.17	< 0.021 U	0.088	< 0.17 U	< 0.016 U	< 0.048 U	0.33	0.34	0.43	0.18	0.27	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	4 - 6 ft	180-116002-2	Not Excavated			1.044	0.022	0.017	0.021	0.02	0.17	0.016	0.048	0.096	0.11	0.12	0.053	0.017	0.018	0.014	0.028	0.41	0.027	0.26
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated			9.228	< 0.024 U	0.29	< 0.023 U	0.23	< 0.19 U	0.023 J	< 0.053 U	0.82	0.81	1.1	0.39	0.8	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated			24.923	0.053 J	1.1	< 0.02 U	0.65	< 0.16 U	< 0.015 U	< 0.046 U	2.2	2.3	3.1	0.88	2.2	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated			1.237	< 0.021 U	0.081	< 0.02 U	0.036 J	< 0.16 U	< 0.016 U	< 0.046 U	0.11	0.12	0.18	0.032 J	0.12	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	2 - 4 ft	180-116462-1	Not Excavated	53 J	53 J	5.084	0.025 J	0.28	< 0.021 U	0.14	< 0.17 U	< 0.016 U	< 0.048 U	0.45	0.46	0.61	0.17	0.35	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	4 - 6 ft	180-116462-3	Not Excavated	< 39 U	< 39 U	0.731	< 0.022 U	0.055 J	< 0.021 U	0.025 J	< 0.17 U	< 0.016 U	< 0.047 U	0.067 J	0.07 J	0.088	0.034 J	0.053 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-1	Not Excavated	40 J	40 J	1.71	< 0.022 U	0.037 J	< 0.021 U	0.031 J	< 0.17 U	< 0.016 U	< 0.047 U	0.17	0.14	0.19	0.061 J	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	4 - 6 ft	180-116462-3	Not Excavated	< 41 U	< 41 U	0.887	< 0.022 U	0.043 J	< 0.021 U	0.024 J	< 0.17 U	< 0.016 U	< 0.048 U	0.082	0.087	0.11	0.038 J	0.081	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-2-4	1/23/2021	853.98	2 - 4 ft	180-116404-3	Excavated			1.428	< 0.021 U	0.063 J	< 0.019 U	0.048 J	< 0.16 U	< 0.015 U	< 0.045 U	0.1	0.13	0.16	0.053 J	0.16	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-2-4	1/23/2021	853.31	2 - 4 ft	180-116404-3	Excavated			5.122	< 0.022 U	0.19	< 0.021 U	0.15	< 0.17 U	0.03 J	< 0.047 U	0.39	0.47	0.53	0.22	0.43	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-2-4	1/26/2021	857.28	2 - 4 ft	180-116462-3	Excavated			17.283	0.063 J	1.6	< 0.041 U	0.78	< 0.33 U	< 0.032 U	< 0.095 U	1.4	1.7	2.3	0.76	1.8	< 0.036 U	< 0.028 U	< 0.057 U	< 0.81 U	< 0.053 U	< 0.52 U
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	2 - 4 ft	180-116002-1	Not Excavated			0.721	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.067 J	0.072 J	0.099	0.032 J	0.056 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-2-4	1/26/2021	856.64	2 - 4 ft	180-116462-1	Excavated			3.808	< 0.022 U	0.27	< 0.02 U	0.13	< 0.16 U	0.045 J	< 0.047 U	0.25	0.3	0.37	0.13	0.49	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-4-6	1/26/2021	856.64	4 - 6 ft	180-116462-3	Excavated			0.252	< 0.023 U	0.077 J	< 0.021 U	0.027 J	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	0.18	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-2-4	1/27/2021	856.72	2 - 4 ft	180-116529-1	Excavated			3.66	< 0.022 U	0.15	< 0.021 U	0.1	< 0.17 U	< 0.016 U	< 0.047 U	0.27	0.33	0.45	0.12	0.42	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	4 - 6 ft	180-116529-3	Not Excavated			0.643	< 0.023 U	0.062 J	< 0.021 U	0.028 J	< 0.17 U	< 0.017 U	< 0.049 U	0.05 J	0.059 J	0.078 J	0.025 J	0.078 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3554	DUP-12	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated			0.593	< 0.02 U	0.032 J	< 0.019 U	0.025 J	< 0.15 U	< 0.015 U	< 0.044 U	0.049 J	0.052 J	0.069 J	0.026 J	0.069 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated			0.566	< 0.02 U	0.035 J	< 0.019 U	0.027 J	< 0.15 U	< 0.015 U	< 0.043 U	0.047 J	0.054 J	0.066 J	0.023 J	0.063 J	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 UT	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated			0.083	< 0.019 U	< 0.015 U	< 0.018 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.041 U	< 0.03 U	< 0.029 U	0.023 J	< 0.02 U	0.019 J	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U	< 0.23 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated			1.667	< 0.022 U	0.1	< 0.021 U	0.051 J	< 0.17 U	< 0.016 U	< 0.048 U	0.15	0.16	0.22	0.07 J	0.13	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-2-4	2/1/2021	856.70	2 - 4 ft	180-116686-2	Excavated			68.71	0.13 J	3	< 0.08 U	1.9	< 0.65 U	< 0.062 U	< 0.18 U	6.4	5.3	7.8	2.1	4.9	< 0.07 U	< 0.054 U	< 0.11 U	< 1.6 U	< 0.1 U	< 1 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	2 - 4 ft	180-116404-3	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-2-4	1/25/2021	857.48	2 - 4 ft	180-116404-3	Excavated			0.412	< 0.021 U	0.039 J	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.033 J	0.044 J	0.064 J	0.026 J	0.05 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	2 - 4 ft	180-116404-3	Not Excavated			0.095	< 0.021 U	0.017 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	0.038 J	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	2 - 4 ft	180-116404-3	Not Excavated			2.766	< 0.022 U	0.12	< 0.021 U	0.06 J	< 0.17 U	< 0.016 U	< 0.047 U	0.26	0.27	0.41	0.11	0.22	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	2 - 4 ft	180-116404-3	Not Excavated			2.577	< 0.022 U	0.085	< 0.021 U	0.041 J	< 0.17 U	< 0.016 U	< 0.048 U	0.24	0.23	0.33	0.1	0.19	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-2-4	1/23/2021	855.69	2 - 4 ft	180-116404-3	Excavated			0.837	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-2-4	1/27/2021	855.81	2 - 4 ft	180-116529-3	Excavated			0.798	< 0.022 U	0.05 J	< 0.02 U	0.026 J	< 0.16 U	< 0.016 U	< 0.047 U	0.06 J	0.076	0.09	0.034 J	0.092	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-2-4	2/1/2021	856.45	2 - 4 ft	180-116686-2	Excavated			11.293	0.24	0.27	< 0.021 U	0.45	< 0.17 U	0.1 J	< 0.047 U	1.1	0.45	0.44	0.29	0.35	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-2-4	1/23/2021	857.05	2 - 4 ft	180-116404-3	Excavated			1.663	< 0.023 U	0.099	0.023 J	0.051 J	< 0.18 U	0.026 J	< 0.05 U	0.14	0.13	0.18	0.05 J	0.11	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-2-4	2/2/2021	856.66	2 - 4 ft	180-116723-1	Excavated			1.669	< 0.021 U	0.083	< 0.02 U	0.057 J	< 0.16 U	0.034 J	0.11 J	0.11	0.11	0.18	0.043 J	0.2	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	4 - 6 ft	180-116771-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-2-4	1/27/2021	857.15	2 - 4 ft	180-116529-1	Excavated			11.46	0.11	0.25	< 0.02 U	0.41	< 0.16 U	0.035 J	< 0.047 U	0.91	0.99	1.1	0.42	0.78	< 0.018 U	< 0.014 U	< 0.028 U	1.1 J	< 0.026 U	< 0.26 U

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-14-16	7/19/2021	851.57	14 - 16 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.039 J	< 0.045 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.23 U	< 0.017 U	< 0.024 UT	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	0.044 J	< 0.043 U	< 0.015 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U	< 1.9 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.23	0.088	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated																				
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated	< 0.24 U	0.043 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.56	0.17	0.037 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.081	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	< 0.24 U	0.026 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.11	< 0.048 U	0.043 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	< 0.24 U	0.018 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.17	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.61	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.097	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated	< 2.1 U	< 0.15 U	< 0.22 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.2 U	< 0.36 U	< 0.42 U	< 0.14 U	< 3 U	< 0.25 U	< 1.1 U	< 0.2 U	< 0.24 U	< 1.4 U	< 1.9 U	< 5.6 U	< 0.2 U	< 18 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	< 0.25 U	0.19	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.87	0.2	0.15 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	< 0.23 U	0.042 J	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	2.4	0.31	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.59	0.13	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.043 J	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.064 J	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	2 - 4 ft	1801164621	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.056 J	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.069 J	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	4 - 6 ft	1801164623	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	2 - 4 ft	180-116462-1	Not Excavated	< 0.25 U	0.091	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.6	0.29	0.046 J	< 0.36 U	< 0.03 U	0.14 J	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	4 - 6 ft	180-116462-3	Not Excavated	< 0.25 U	0.027 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.44	0.12	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	2 - 4 ft	180-116462-1	Not Excavated	< 1.3 U	0.72	< 0.14 U	< 0.095 U	< 0.092 U	< 0.093 U	< 0.12 U	15	3	0.23 J	< 1.9 U	< 0.15 U	< 0.71 U	< 0.12 U	< 0.15 U	< 0.88 U	< 1.2 U	< 3.5 U	< 0.12 U	< 11 U
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.25 U	0.068 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.8	0.4	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.25 U	0.02 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.34	0.1	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	4 - 6 ft	180-116002-2	Not Excavated	< 0.25	0.018	0.026	0.018	0.018	0.018	0.023	0.12	0.049	0.017	0.36	0.03	0.13	0.024	0.028	0.17	0.22	0.66	0.024	2.1
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.28 U	0.082 J	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.87	0.25	0.058 J	< 0.39 U	< 0.033 U	0.18 J	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.24 U	0.14	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	2.5	0.59	0.034 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	2 - 4 ft	180-116462-1	Not Excavated	< 0.25 U	0.034 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.53	0.096	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	4 - 6 ft	180-116462-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.08	< 0.049 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.16	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	4 - 6 ft	180-116462-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.095	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3504A	SSHS-B3504A-SUB-2-4	1/23/2021	853.98	2 - 4 ft	180-116404-3	Excavated	< 0.23 U	0.017 J	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.097	< 0.046 U	0.019 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3505A	SSHS-B3505A-SUB-2-4	1/23/2021	853.31	2 - 4 ft	180-116404-3	Excavated	< 0.25 U	0.042 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.39	0.092	0.055 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3507A	SSHS-B3507A-SUB-2-4	1/26/2021	857.28	2 - 4 ft	180-116462-3	Excavated	< 0.5 U	0.13 J	< 0.052 U	< 0.036 U	< 0.035 U	< 0.035 U	< 0.046 U	1.7	0.42	0.067 J	< 0.71 U	< 0.059 U	< 0.27 U	< 0.047 U	< 0.057 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.047 U	< 4.2 U
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	2 - 4 ft	180-116002-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.083	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-2-4	1/26/2021	856.64	2 - 4 ft	180-116462-1	Excavated	< 0.24 U	0.044 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.26	0.069 J	0.079 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-4-6	1/26/2021	856.64	4 - 6 ft	180-116462-3	Excavated	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	0.14 J	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-2-4	1/27/2021	856.72	2 - 4 ft	180-116529-1	Excavated	< 0.25 U	0.032 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.29	0.11	0.044 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	4 - 6 ft	180-116529-3	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.062 J	< 0.051 U	< 0.017 U	< 0.37 U	< 0.03 U	0.14 J	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3554	DUP-12	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.062 J	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.22 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.055 J	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.23 U	< 0.016 U	< 0.024 UT	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 UT	< 0.021 U	< 1.9 UT
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	< 0.037 U	< 0.043 U	< 0.015 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.18	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-2-4	2/1/2021	856.70	2 - 4 ft	180-116686-2	Excavated	< 0.96 U	0.35	< 0.1 U	< 0.069 U	< 0.068 U	< 0.069 U	< 0.089 U	7	1.3	0.14 J	< 1.4 U	< 0.11 U	< 0.52 U	< 0.092 U	< 0.11 U	< 0.65 U	< 0.86 U	< 2.5 U	< 0.091 U	< 8.2 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	2 - 4 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-2-4	1/25/2021	857.48	2 - 4 ft	180-116404-3	Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.044 J	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	2 - 4 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	2 - 4 ft	180-116404-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.28	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	2 - 4 ft	180-116404-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.27	0.051 J	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-2-4	1/23/2021	855.69	2 - 4 ft	180-116404-3	Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-2-4	1/27/2021	855.81	2 - 4 ft	180-116529-3	Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.063 J	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-2-4	2/1/2021	856.45	2 - 4 ft	180-116686-2	Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.4	0.073 J	0.25 J	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-2-4	1/23/2021	857.05	2 - 4 ft	180-116404-3	Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.21	< 0.051 U	0.042 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.2 U
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-2-4	2/2/2021	856.66	2 - 4 ft	180-116723-1	Excavated	< 0.24 U	0.019 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.15	< 0.048 U	0.084 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	4 - 6 ft	180-116771-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-2-4	1/27/2021	857.15	2 - 4 ft	180-116529-1	Excavated	< 0.24 U	0.16	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.9	0.17	0.11 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-14-16	7/19/2021	851.57	14 - 16 ft	180-124670-1	Excavated															
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.054 U	< 0.11 U			0.03 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.063 J	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.052 U	< 0.11 U			0.018 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	0.043 J	< 0.098 U		< 0.018 U	< 0.016 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated	< 0.051 U	< 0.11 U			0.052 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U	0.071	< 0.097 U		< 0.017 U	< 0.016 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated	< 0.055 U			< 0.11 U	0.24	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.1	< 0.1 U	< 0.11 U	< 0.019 U	0.033 J
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated															
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated	< 0.056 U			< 0.12 U	0.95	0.036 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.46	< 0.11 U	< 0.11 U	< 0.019 U	0.05 J
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	< 0.053 U			< 0.11 U	0.096	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.047 J	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated															
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	< 0.056 U			< 0.12 U	0.11	0.044 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.058 J	< 0.11 U	< 0.11 U	< 0.019 U	0.081
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	< 0.055 U			< 0.11 U	0.27	0.016 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.11	< 0.1 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	< 0.056 U			< 0.11 U	0.15	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.054 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated															
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated	< 0.49 U			< 1 U	0.24 J	< 0.13 U	< 0.23 U	< 0.19 U	< 0.33 U	< 0.17 U	< 0.32 U	< 0.93 U	< 0.95 U	< 0.17 U	1.1
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated	< 0.059 U			< 0.12 U	0.034 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated															
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	< 0.057 U			< 0.12 U	1.9	0.22	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.47	< 0.11 U	< 0.11 U	< 0.019 U	0.08
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated															
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	< 0.054 U			< 0.11 U	2.6	0.025 J	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U	0.71	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	< 0.055 U			< 0.11 U	1	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.4	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	< 0.057 U			< 0.12 U	0.044 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	< 0.056 U			< 0.12 U	0.081	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.049 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	2 - 4 ft	1801164621	Not Excavated	< 0.059 U	< 0.12 U			0.066 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.055 U	< 0.11 U			0.089	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.044 J	< 0.1 U		< 0.019 U	< 0.017 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	4 - 6 ft	1801164623	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	2 - 4 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	2.3	0.078	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	1	< 0.11 U	< 0.11 U	< 0.02 U	0.1
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	4 - 6 ft	180-116462-3	Not Excavated	< 0.058 U			< 0.12 U	0.53	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.32	< 0.11 U	< 0.11 U	< 0.02 U	0.038 J
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	2 - 4 ft	180-116462-1	Not Excavated	< 0.3 U			< 0.63 U	22	0.7	< 0.14 U	< 0.12 U	< 0.21 U	< 0.1 U	9.7	< 0.58 U	< 0.59 U	< 0.1 U	0.52
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	4 - 6 ft	180-116462-3	Not Excavated	< 0.057 U			< 0.12 U	2.5	0.076	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	1.2	< 0.11 U	< 0.11 U	< 0.019 U	0.06 J
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.058 U			< 0.12 U	0.41	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.25	< 0.11 U		< 0.02 U	0.063 J
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	4 - 6 ft	180-116002-2	Not Excavated	0.058			0.12	0.15	0.015	0.028	0.022	0.039	0.02	0.061	0.11		0.02	0.018
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.064 U			< 0.13 U	1.2	0.048 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	0.64	< 0.12 U		< 0.022 U	0.17
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.055 U	< 0.11 U			3.2	0.11	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	1.8	< 0.11 U		< 0.019 U	0.082
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.056 U	< 0.12 U			0.16	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.11	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	2 - 4 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	0.78	0.033 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	0.3	< 0.11 U	< 0.11 U	< 0.02 U	0.021 J
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	4 - 6 ft	180-116462-3	Not Excavated	< 0.057 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.047 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-1	Not Excavated	< 0.057 U			< 0.12 U	0.32	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.094	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	4 - 6 ft	180-116462-3	Not Excavated	< 0.058 U			< 0.12 U	0.12	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	0.068 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-2-4	1/23/2021	853.98	2 - 4 ft	180-116404-3	Excavated	< 0.054 U			< 0.11 U	0.18	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.11	< 0.1 U	< 0.11 U	< 0.018 U	0.036 J
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-2-4	1/23/2021	853.31	2 - 4 ft	180-116404-3	Excavated	< 0.057 U			< 0.12 U	0.73	0.03 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.34	< 0.11 U	< 0.11 U	< 0.019 U	0.11
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-2-4	1/26/2021	857.28	2 - 4 ft	180-116462-3	Excavated	< 0.12 U			< 0.24 U	1.8	0.11 J	< 0.055 U	< 0.045 U	< 0.078 U	< 0.039 U	1.4	< 0.22 U	< 0.22 U	< 0.039 U	0.17
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	2 - 4 ft	180-116002-1	Not Excavated	< 0.056 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.047 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-2-4	1/26/2021	856.64	2 - 4 ft	180-116462-1	Excavated	< 0.057 U			< 0.12 U	0.42	0.029 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.28	< 0.11 U	< 0.11 U	< 0.019 U	0.15
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-4-6	1/26/2021	856.64	4 - 6 ft	180-116462-3	Excavated	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-2-4	1/27/2021	856.72	2 - 4 ft	180-116529-1	Excavated	< 0.057 U			< 0.12 U	0.4	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.29	< 0.11 U	< 0.11 U	< 0.019 U	0.09
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	4 - 6 ft	180-116529-3	Not Excavated	< 0.06 U			< 0.12 U	0.068 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.065 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3554	DUP-12	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.053 U	< 0.11 U			0.06 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	0.05 J	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.052 U	< 0.11 U			0.057 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	0.054 J	< 0.099 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.052 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.099 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.05 U	< 0.1 U			0.019 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U	< 0.033 U	< 0.096 U		< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.058 U	< 0.12 U			0.24	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.11	< 0.11 U		< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-2-4	2/1/2021	856.70	2 - 4 ft	180-116686-2	Excavated	< 0.22 U			< 0.46 U	11	0.4	< 0.11 U	< 0.086 U	< 0.15 U	< 0.076 U	3.9	< 0.42 U	< 0.43 U	< 0.075 U	0.21 J
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	2 - 4 ft	180-116404-3	Not Excavated	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-2-4	1/25/2021	857.48	2 - 4 ft	180-116404-3	Excavated	< 0.054 U			< 0.11 U	0.045 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.04 J	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	2 - 4 ft	180-116404-3	Not Excavated	< 0.055 U			< 0.11 U	0.028 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	2 - 4 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.37	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.2	< 0.11 U	< 0.11 U	< 0.019 U	0.035 J
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	2 - 4 ft	180-116404-3	Not Excavated	< 0.059 U			< 0.12 U	0.36	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.15	< 0.11 U	< 0.11 U	< 0.02 U	0.03 J
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-2-4	1/23/2021	855.69	2 - 4 ft	180-116404-3	Excavated	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	0.029 J
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-2-4	1/27/2021	855.81	2 - 4 ft	180-116529-3	Excavated	< 0.057 U			< 0.12 U	0.096	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.065 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-2-4	2/1/2021	856.45	2 - 4 ft	180-116686-2	Excavated	< 0.058 U			< 0.12 U	1.8	0.46	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.26	< 0.11 U	< 0.11 U	< 0.019 U	0.22
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-2-4	1/23/2021	857.05	2 - 4 ft	180-116404-3	Excavated	< 0.061 U			< 0.13 U	0.17	0.017 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.086	< 0.12 U	< 0.12 U	< 0.02 U	0.13
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-2-4	2/2/2021	856.66	2 - 4 ft	180-116723-1	Excavated	< 0.056 U			< 0.12 U	0.17	0.019 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.1	< 0.11 U	< 0.11 U	< 0.019 U	0.1
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	4 - 6 ft	180-116771-1	Not Excavated	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-2-4	1/27/2021	857.15	2 - 4 ft	180-116529-1	Excavated	< 0.057 U			< 0.12 U	1.8	0.14	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.63	< 0.11 U	< 0.11 U	< 0.019 U	0.13

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3343A	SSHS-B3343A-SUB-14-16	7/19/2021	851.57	14 - 16 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3454	DUP-8	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.039 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.025 J		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	14 - 16 ft	1801163651	Not Excavated	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.03 J	< 0.1 U	0.063 J		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-2-4	7/27/2020	856.30	2 - 4 ft	180-108826-2	Excavated		0.058 J	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.15	< 0.11 U	0.21		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated																				
Football Field	SSHS-B3461	SSHS-B3461-SUB-2-4	7/27/2020	856.51	2 - 4 ft	180-108826-2	Excavated		0.15	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.44	< 0.11 U	0.9		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.077	< 0.11 U	0.13		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated		0.21	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.16	< 0.11 U	0.12		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated		0.04 J	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.15	< 0.11 U	0.3		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.12	< 0.11 U	0.18		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3467	SSHS-B3467-SUB-2-4	7/28/2020	855.68	2 - 4 ft	180-108872-2	Excavated		4.2 J	< 1.5 U	< 0.83 U	< 0.16 U	< 1.2 U	< 0.52 U	< 2.3 U		< 0.22 U	< 1.1 U	< 5.2 U	0.41 J	< 0.98 U	0.38 J		< 0.14 U	< 1.4 U	< 0.23 U	< 0.18 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	2 - 4 ft	180-108826-2	Not Excavated		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.026 J	< 0.12 U	0.04 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated		0.14	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.6	< 0.12 U	1.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated																				
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	2	< 0.11 U	4.7		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated		0.031 J	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.29	< 0.11 U	1.1		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.029 J	< 0.11 U	0.047 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated		0.018 J	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.04 J	< 0.11 U	0.095		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	2 - 4 ft	1801164621	Not Excavated	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.026 J	< 0.12 U	0.076 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.028 J	< 0.11 U	0.11		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	4 - 6 ft	1801164623	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	2 - 4 ft	180-116462-1	Not Excavated		0.13	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.2	< 0.12 U	2.7		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	4 - 6 ft	180-116462-3	Not Excavated		0.053 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.2	< 0.12 U	0.67		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	2 - 4 ft	180-116462-1	Not Excavated		0.75	< 0.92 U	< 0.51 U	< 0.098 U	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	9.8	< 0.61 U	24		< 0.087 U	< 0.84 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	4 - 6 ft	180-116462-3	Not Excavated		0.091	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.95	< 0.11 U	2.8		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.11 U	0.053 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.14	< 0.12 U	0.47		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	4 - 6 ft	180-116002-2	Not Excavated	0.11	0.015	0.17	0.098	0.019	0.14	0.061	0.27		0.026	0.13	0.62	0.046	0.12	0.15		0.017	0.16	0.027	0.021
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.12 U	0.16	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.61	< 0.13 U	1.3		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.11 U	0.14	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	1.3	< 0.11 U	3.9		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.049 J	< 0.11 U	0.19		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	2 - 4 ft	180-116462-1	Not Excavated		0.03 J	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.24	< 0.12 U	0.87		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	4 - 6 ft	180-116462-3	Not Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.037 J	< 0.12 U	0.12		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.094	< 0.11 U	0.32		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	4 - 6 ft	180-116462-3	Not Excavated		< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.042 J	< 0.12 U	0.14		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3504A	SSHS-B3504-SUB-2-4	1/23/2021	853.98	2 - 4 ft	180-116404-3	Excavated		0.11	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.11	< 0.11 U	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3505A	SSHS-B3505-SUB-2-4	1/23/2021	853.31	2 - 4 ft	180-116404-3	Excavated		0.35	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.36	< 0.12 U	0.64		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3507A	SSHS-B3507-SUB-2-4	1/26/2021	857.28	2 - 4 ft	180-116462-3	Excavated		0.2	< 0.35 U	< 0.19 U	< 0.037 U	< 0.28 U	< 0.12 U	< 0.54 U		< 0.052 U	< 0.25 U	< 1.2 U	0.55	< 0.23 U	2.3		< 0.033 U	< 0.32 U	< 0.054 U	< 0.042 U
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	2 - 4 ft	180-116002-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.035 J	< 0.11 U	0.12		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-2-4	1/26/2021	856.64	2 - 4 ft	180-116462-1	Excavated		0.45	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.24	< 0.11 U	0.39		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3518	SSHS-B3518-SUB-4-6	1/26/2021	856.64	4 - 6 ft	180-116462-3	Excavated		0.024 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.021 J	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-2-4	1/27/2021	856.72	2 - 4 ft	180-116529-1	Excavated		0.25	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.19	< 0.12 U	0.44		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	4 - 6 ft	180-116529-3	Not Excavated		0.026 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.029 J	< 0.12 U	0.075 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3554	DUP-12	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.041 J	< 0.11 U	0.09		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	0.039 J	< 0.1 U	0.081		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.016 U	< 0.12 U	< 0.053 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.022 J		< 0.014 U	< 0.14 U	< 0.024 U	< 0.018 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	14 - 16 ft	1801162471	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.076 J	< 0.12 U	0.28		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3595	SSHS-B3595-SUB-2-4	2/1/2021	856.70	2 - 4 ft	180-116686-2	Excavated		0.28 J	< 0.67 U	< 0.37 U	< 0.072 U	< 0.54 U	< 0.23 U	< 1 U		< 0.1 U	< 0.49 U	< 2.4 U	5.3	< 0.45 U	11		< 0.064 U	< 0.61 U	< 0.11 U	< 0.081 U
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	2 - 4 ft	180-116404-3	Not Excavated		< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3614	SSHS-B3614-SUB-2-4	1/25/2021	857.48	2 - 4 ft	180-116404-3	Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.066 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	2 - 4 ft	180-116404-3	Not Excavated		< 0.014 U	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	0.029 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	2 - 4 ft	180-116404-3	Not Excavated		0.026 J	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.11	< 0.12 U	0.45		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	2 - 4 ft	180-116404-3	Not Excavated		0.025 J	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.14	< 0.12 U	0.45		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3625	SSHS-B3625-SUB-2-4	1/23/2021	855.69	2 - 4 ft	180-116404-3	Excavated		0.017 J	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.34	< 0.11 U	0.48		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3626	SSHS-B3626-SUB-2-4	1/27/2021	855.81	2 - 4 ft	180-116529-3	Excavated		0.062 J	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.043 J	< 0.11 U	0.091		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3627	SSHS-B3627-SUB-2-4	2/1/2021	856.45	2 - 4 ft	180-116686-2	Excavated		0.48	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.9	< 0.12 U	1.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3628	SSHS-B3628-SUB-2-4	1/23/2021	857.05	2 - 4 ft	180-116404-3	Excavated		0.079 J	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.24	< 0.12 U	0.2		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-2-4	2/2/2021	856.66	2 - 4 ft	180-116723-1	Excavated		0.2	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.18	< 0.11 U	0.15		< 0.016 U	< 0.15 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	4 - 6 ft	180-116771-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-2-4	1/27/2021	857.15	2 - 4 ft	180-116529-1	Excavated		0.3	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	1.2	< 0.11 U	1.6		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-4-6	1/27/2021	857.15	4 - 6 ft	180-116529-3	Excavated			32.81	0.42	1	< 0.086 U	1.1	< 0.69 U	0.15 J	< 0.2 U	2.5	2.6	3	1.2	2.5	< 0.076 U	< 0.058 U	< 0.12 U	< 1.7 U	< 0.11 U	< 1.1 U
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-2-4	1/27/2021	856.65	2 - 4 ft	180-116529-3	Excavated			2.516	< 0.022 U	0.088	< 0.021 U	0.076 J	< 0.17 U	< 0.016 U	< 0.048 U	0.2	0.23	0.26	0.1	0.26	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-2-4	2/2/2021	856.10	2 - 4 ft	180-116723-1	Excavated			1.251	0.032 J	0.018 J	< 0.02 U	0.027 J	< 0.16 U	< 0.016 U	< 0.046 U	0.13	0.039 J	0.05 J	< 0.022 U	0.034 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-2-4	1/27/2021	856.99	2 - 4 ft	180-116529-3	Excavated			51.29	< 0.066 U	3	< 0.062 U	1.5	< 0.5 U	< 0.048 U	< 0.14 U	4.6	4.7	6.6	2	4.6	< 0.055 U	< 0.042 U	< 0.085 U	< 1.2 U	< 0.08 U	< 0.79 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated		470	3.87	< 0.21 U	< 0.16 U	< 0.2 U	< 0.19 U	< 1.6 U	< 0.15 U	< 0.46 U	0.47 J	0.42 J	0.46 J	< 0.22 U	0.41 J	< 0.18 U	< 0.13 U	< 0.27 U	< 3.9 U	< 0.26 U	< 2.5 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated			2.025	< 0.034 U	0.052 J	< 0.034 U	0.038 J	< 0.16 U	< 0.034 U	< 0.045 U	0.18	0.21	0.28	0.091	0.18	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated			0.073	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	0.026 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated			0.018	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	0.018 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	12 - 14 ft	180-127265-1	Not Excavated			0.055	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	0.017 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated			0.068	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	0.02 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated			0.27	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.044 U	0.045 J	0.031 J	0.05 J	< 0.021 U	0.023 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-2-4	1/27/2021	855.11	2 - 4 ft	180-116529-3	Excavated	< 41 U	< 41 U																			
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-2-4	1/27/2021	854.67	2 - 4 ft	180-116529-3	Excavated	< 42 U	< 42 U																			
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-2-4	1/28/2021	856.29	2 - 4 ft	180-116609-2	Excavated	670	670																			
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-2-4	1/28/2021	856.63	2 - 4 ft	180-116609-2	Excavated	740	740																			
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-10-12	1/29/2021	857.34	10 - 12 ft	180-116665-3	Excavated	< 40 U	< U																			
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-12-14	1/29/2021	857.34	12 - 14 ft	180-116665-1	Excavated	< 38 U	< U																			
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-14-16	1/29/2021	857.34	14 - 16 ft	180-116665-3	Excavated	45 J	45 J																			
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-10-12	1/29/2021	857.20	10 - 12 ft	180-116665-3	Excavated	< 40 U	< U																			
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-12-14	1/29/2021	857.20	12 - 14 ft	180-116665-1	Excavated	< 36 U	< U																			
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-14-16	1/29/2021	857.20	14 - 16 ft	180-116665-3	Excavated	< 41 U	< U																			
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-10-12	2/3/2021	856.90	10 - 12 ft	180-116771-1	Excavated	< 40 U	< 40 U																			
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-12-14	2/3/2021	856.90	12 - 14 ft	180-116771-1	Excavated	< 43 U	< 43 U																			
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-14-16	2/3/2021	856.90	14 - 16 ft	180-116771-1	Excavated	< 41 U	< 41 U																			
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-10-12	1/29/2021	857.15	10 - 12 ft	180-116665-3	Excavated	< 39 U	< U																			
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-12-14	1/29/2021	857.15	12 - 14 ft	180-116665-1	Excavated	59	59																			
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-14-16	1/29/2021	857.15	14 - 16 ft	180-116665-3	Excavated	< 37 U	< U																			
Northern Athletic Field	SSHS-B3663	SSHS-B3663-SUB-12-14	7/19/2021	857.05	12 - 14 ft	180-124670-1	Excavated	120																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-10-12	2/2/2021	856.55	10 - 12 ft	180-116723-1	Excavated	< 36 U																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-12-14	2/2/2021	856.55	12 - 14 ft	180-116723-1	Excavated	<36 U																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-14-16	2/2/2021	856.55	14 - 16 ft	180-116723-1	Excavated	< 37 U																				
Northern Athletic Field	SSHS-B3665	SSHS-B3665-SUB-12-14	7/19/2021	856.56	12 - 14 ft	180-124670-1	Excavated	31																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-10-12	2/1/2021	857.15	10 - 12 ft	180-116686-2	Excavated	< 41 U	< 41 U																			
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-12-14	2/1/2021	857.15	12 - 14 ft	180-116686-1	Excavated	< 39 U	< 39 U																			
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-14-16	2/1/2021	857.15	14 - 16 ft	180-116686-2	Excavated	< 39 U	< 39 U																			
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated	44 J	44 J																			
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated	44	44 J																			
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	3900	3900	0.487	0.036 J	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	0.051 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	3900	3900	0.487	0.036 J	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	0.051 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated	7100	7100 J+																			
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated	7100	7100 J+																			
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-10-12	1/28/2021	852.33	10 - 12 ft	180-116609-2	Excavated	< 37 U	< 37 U																			
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated	< 36 U	< 36 U	ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-14-16	1/28/2021	852.33	14 - 16 ft	180-116609-2	Excavated	4900	4900 J+																			
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	1/29/2021	851.67	10 - 12 ft	180-116665-3	Excavated	1100	1100 J+																			
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	1/29/2021	851.67	12 - 14 ft	180-116665-1	Excavated	1700	1700																			
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	1/29/2021	851.67	14 - 16 ft	180-116665-3	Excavated	4400	4400																			
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated			0.038	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated			0.571	< 0.021 U	0.032 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.088	< 0.032 U	< 0.018 U	< 0.022 U	0.11	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B37	_12 Sep 00B37_8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated			0.37	< 0.35 U	< 0.35 U		< 0.35 U				< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated			0.85	< 0.042 U	0.053 J	< 0.26 U	0.048 J	< 0.32 U	< 0.27 U	< 0.09 U	0.092 J	0.066 J	0.1 J	< 0.043 U	0.071 J	< 0.27 U	< 0.026 U	< 0.054 U	< 0.77 U	< 0.31 U	< 0.5 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated			1.4	< 0.08 U	< 0.061 U	< 0.5 U	< 0.072 U	< 0.61 U	< 0.51 U	< 0.17 U	0.18 J	0.15 J	0.16 J	< 0.084 U	0.1 J	< 0.51 U	< 0.051 U	< 0.1 U	< 1.5 U	< 0.59 U	< 0.96 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated			0.238	< 0.085 U	< 0.065 U	< 0.53 U	< 0.077 U	< 0.65 U	< 0.54 U	< 0.18 U	< 0.13 U	< 0.13 U	< 0.073 U	< 0.089 U	< 0.064 U	< 0.54 U	< 0.054 U	< 0.11 U	< 1.6 U	< 0.63 U	< 1 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated			0.018	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated			0.049	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated			0.026	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated			0.037	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U	< 0.038 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U

DRAFT

Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-4-6	1/27/2021	857.15	4 - 6 ft	180-116529-3	Excavated	< 1 U	0.34	< 0.11 U	< 0.075 U	< 0.073 U	< 0.074 U	< 0.096 U	2.6	0.74	0.48 J	< 1.5 U	< 0.12 U	< 0.56 U	< 0.098 U	< 0.12 U	< 0.69 U	< 0.92 U	< 2.7 U	< 0.098 U	< 8.8 U
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-2-4	1/27/2021	856.65	2 - 4 ft	180-116529-3	Excavated	< 0.25 U	0.029 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.21	< 0.05 U	0.025 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-2-4	2/2/2021	856.10	2 - 4 ft	180-116723-1	Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.18	< 0.048 U	0.039 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-2-4	1/27/2021	856.99	2 - 4 ft	180-116529-3	Excavated	< 0.74 U	0.3	< 0.078 U	< 0.054 U	< 0.052 U	< 0.053 U	< 0.069 U	4.7	1.2	0.16 J	< 1.1 U	< 0.088 U	< 0.4 U	< 0.071 U	< 0.085 U	< 0.5 U	< 0.67 U	< 2 U	< 0.071 U	< 6.3 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	< 2.4 U	< 0.17 U	< 0.25 U	< 0.17 U	< 0.17 U	< 0.17 U	< 0.22 U	0.46 J	< 0.47 U	< 0.16 U	< 3.4 U	< 0.28 U	< 1.3 U	< 0.23 U	< 0.27 U	< 1.6 U	< 2.1 U	< 6.4 U	< 0.23 U	< 20 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	0.05 J	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	12 - 14 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-2-4	1/27/2021	855.11	2 - 4 ft	180-116529-3	Excavated																				
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-2-4	1/27/2021	854.67	2 - 4 ft	180-116529-3	Excavated																				
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-2-4	1/28/2021	856.29	2 - 4 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-2-4	1/28/2021	856.63	2 - 4 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-10-12	1/29/2021	857.34	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-12-14	1/29/2021	857.34	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-14-16	1/29/2021	857.34	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-10-12	1/29/2021	857.20	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-12-14	1/29/2021	857.20	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-14-16	1/29/2021	857.20	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-10-12	2/3/2021	856.90	10 - 12 ft	180-116771-1	Excavated																				
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-12-14	2/3/2021	856.90	12 - 14 ft	180-116771-1	Excavated																				
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-14-16	2/3/2021	856.90	14 - 16 ft	180-116771-1	Excavated																				
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-10-12	1/29/2021	857.15	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-12-14	1/29/2021	857.15	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-14-16	1/29/2021	857.15	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3663	SSHS-B3663-SUB-12-14	7/19/2021	857.05	12 - 14 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-10-12	2/2/2021	856.55	10 - 12 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-12-14	2/2/2021	856.55	12 - 14 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-14-16	2/2/2021	856.55	14 - 16 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3665	SSHS-B3665-SUB-12-14	7/19/2021	856.56	12 - 14 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-10-12	2/1/2021	857.15	10 - 12 ft	180-116686-2	Excavated																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-12-14	2/1/2021	857.15	12 - 14 ft	180-116686-1	Excavated																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-14-16	2/1/2021	857.15	14 - 16 ft	180-116686-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-10-12	1/28/2021	852.33	10 - 12 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	0.16 J	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-14-16	1/28/2021	852.33	14 - 16 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	1/29/2021	851.67	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	1/29/2021	851.67	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	1/29/2021	851.67	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.29	< 0.047 U	< 0.016 U	< 0.35 U	< 0.029 U	0.14 J	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37_8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 1.8 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	< 0.47 U	< 0.034 U	< 0.19 U	< 0.25 U	< 0.033 U	< 0.27 U	< 0.24 U	0.1 J	< 0.093 U	< 0.27 U	< 0.68 U	< 0.056 U	< 0.25 U	< 0.24 U	< 0.29 U	< 0.32 U	< 0.42 U	< 1.2 U	< 0.28 U	< 4.5 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	< 0.91 U	< 0.065 U	< 0.37 U	< 0.49 U	< 0.064 U	< 0.52 U	< 0.46 U	< 0.15 U	< 0.18 U	< 0.52 U	< 1.3 U	< 0.11 U	< 0.49 U	< 0.47 U	< 0.55 U	< 0.61 U	< 0.81 U	< 2.4 U	< 0.54 U	< 8.7 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	< 0.96 U	< 0.069 U	< 0.39 U	< 0.52 U	< 0.068 U	< 0.55 U	< 0.49 U	< 0.16 U	< 0.19 U	< 0.55 U	< 1.4 U	< 0.11 U	< 0.52 U	< 0.5 U	< 0.59 U	< 0.65 U	< 0.86 U	< 2.6 U	< 0.58 U	< 9.2 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.28 U	< 0.02 U	< 0.03 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.056 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.027 U	< 2.4 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	0.34	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-4-6	1/27/2021	857.15	4 - 6 ft	180-116529-3	Excavated	< 0.24 U			< 0.49 U	4.6	0.45	< 0.11 U	< 0.093 U	< 0.16 U	< 0.082 U	2	< 0.45 U	< 0.47 U	< 0.081 U	0.61
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-2-4	1/27/2021	856.65	2 - 4 ft	180-116529-3	Excavated	< 0.058 U			< 0.12 U	0.3	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.19	< 0.11 U	< 0.11 U	< 0.02 U	0.057 J
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-2-4	2/2/2021	856.10	2 - 4 ft	180-116723-1	Excavated	< 0.056 U			< 0.12 U	0.12	0.049 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	0.094
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-2-4	1/27/2021	856.99	2 - 4 ft	180-116529-3	Excavated	< 0.17 U			< 0.36 U	6.4	0.28	< 0.082 U	< 0.067 U	< 0.12 U	< 0.059 U	3.8	< 0.33 U	< 0.34 U	< 0.058 U	0.37
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	< 0.56 U	< 1.2 U			0.66 J	< 0.15 U	< 0.26 U	< 0.22 U	< 0.38 U	< 0.19 U	< 0.37 U	< 1.1 U		< 0.19 U	< 0.18 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated	< 0.21 U			< 0.11 U	0.24	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.17	< 0.034 U	< 0.034 U	< 0.034 U	0.018 J
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated	< 0.21 U			< 0.11 U	0.024 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	12 - 14 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	0.019 J	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	0.023 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	0.05 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-2-4	1/27/2021	855.11	2 - 4 ft	180-116529-3	Excavated															
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-2-4	1/27/2021	854.67	2 - 4 ft	180-116529-3	Excavated															
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-2-4	1/28/2021	856.29	2 - 4 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-2-4	1/28/2021	856.63	2 - 4 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-10-12	1/29/2021	857.34	10 - 12 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-12-14	1/29/2021	857.34	12 - 14 ft	180-116665-1	Excavated															
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-14-16	1/29/2021	857.34	14 - 16 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-10-12	1/29/2021	857.20	10 - 12 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-12-14	1/29/2021	857.20	12 - 14 ft	180-116665-1	Excavated															
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-14-16	1/29/2021	857.20	14 - 16 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-10-12	2/3/2021	856.90	10 - 12 ft	180-116771-1	Excavated															
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-12-14	2/3/2021	856.90	12 - 14 ft	180-116771-1	Excavated															
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-14-16	2/3/2021	856.90	14 - 16 ft	180-116771-1	Excavated															
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-10-12	1/29/2021	857.15	10 - 12 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-12-14	1/29/2021	857.15	12 - 14 ft	180-116665-1	Excavated															
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-14-16	1/29/2021	857.15	14 - 16 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3663	SSHS-B3663-SUB-12-14	7/19/2021	857.05	12 - 14 ft	180-124670-1	Excavated															
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-10-12	2/2/2021	856.55	10 - 12 ft	180-116723-1	Excavated															
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-12-14	2/2/2021	856.55	12 - 14 ft	180-116723-1	Excavated															
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-14-16	2/2/2021	856.55	14 - 16 ft	180-116723-1	Excavated															
Northern Athletic Field	SSHS-B3665	SSHS-B3665-SUB-12-14	7/19/2021	856.56	12 - 14 ft	180-124670-1	Excavated															
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-10-12	2/1/2021	857.15	10 - 12 ft	180-116686-2	Excavated															
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-12-14	2/1/2021	857.15	12 - 14 ft	180-116686-1	Excavated															
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-14-16	2/1/2021	857.15	14 - 16 ft	180-116686-2	Excavated															
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.053 U			< 0.11 U	0.15	0.06 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.053 U			< 0.11 U	0.15	0.06 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-10-12	1/28/2021	852.33	10 - 12 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated	< 0.053 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-14-16	1/28/2021	852.33	14 - 16 ft	180-116609-2	Excavated															
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	1/29/2021	851.67	10 - 12 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	1/29/2021	851.67	12 - 14 ft	180-116665-1	Excavated															
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	1/29/2021	851.67	14 - 16 ft	180-116665-3	Excavated															
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated	< 0.053 U			< 0.11 U	0.019 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.083	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37_8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.35 U				< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U		< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	< 0.43 U			< 0.23 U	0.12 J	< 0.028 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.26 U	< 0.072 U	< 0.21 U	< 0.21 U	< 0.27 U	0.076 J
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	< 0.83 U			< 0.44 U	0.33	< 0.055 U	< 0.1 U	< 0.082 U	< 0.14 U	< 0.49 U	< 0.14 U	< 0.4 U	< 0.41 U	< 0.52 U	< 0.067 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	< 0.88 U			< 0.46 U	0.08 J	< 0.058 U	< 0.11 U	< 0.087 U	< 0.15 U	< 0.52 U	< 0.15 U	< 0.43 U	< 0.44 U	< 0.56 U	< 0.071 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.24 U			< 0.13 U	0.026 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.23 U			< 0.12 U	< 0.02 UJ	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.066 U	< 0.14 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.052 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.098 U		< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.052 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.098 U		< 0.017 U	< 0.016 U

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3630	SSHS-B3630-SUB-4-6	1/27/2021	857.15	4 - 6 ft	180-116529-3	Excavated		1.9	< 0.72 U	< 0.4 U	< 0.077 U	< 0.58 U	< 0.25 U	< 1.1 U		< 0.11 U	< 0.53 U	< 2.6 U	2.5	< 0.48 U	4.7		< 0.069 U	< 0.66 U	< 0.11 U	< 0.087 U
Northern Athletic Field	SSHS-B3639	SSHS-B3639-SUB-2-4	1/27/2021	856.65	2 - 4 ft	180-116529-3	Excavated		0.22	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.17	< 0.12 U	0.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3640	SSHS-B3640-SUB-2-4	2/2/2021	856.10	2 - 4 ft	180-116723-1	Excavated		0.24	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.16	< 0.11 U	0.19		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3643	SSHS-B3643-SUB-2-4	1/27/2021	856.99	2 - 4 ft	180-116529-3	Excavated		0.51	< 0.52 U	< 0.29 U	< 0.056 U	< 0.42 U	< 0.18 U	< 0.8 U		< 0.078 U	< 0.38 U	< 1.8 U	2.9	< 0.35 U	7.5		< 0.049 U	< 0.48 U	< 0.082 U	< 0.063 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	< 1.1 U	< 0.14 U	< 1.7 U	< 0.94 U	< 0.18 U	< 1.4 U	< 0.59 U	< 2.6 U		< 0.25 U	< 1.2 U	< 5.9 U	0.37 J	< 1.1 U	0.62 J		< 0.16 U	< 1.5 U	< 0.26 U	< 0.2 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated		0.056 J	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.11	< 0.11 U	0.24		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.023 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	12 - 14 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	0.019 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.025 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.021 J	< 0.11 U	0.05 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3650	SSHS-B3650-SUB-2-4	1/27/2021	855.11	2 - 4 ft	180-116529-3	Excavated																				
Northern Athletic Field	SSHS-B3651	SSHS-B3651-SUB-2-4	1/27/2021	854.67	2 - 4 ft	180-116529-3	Excavated																				
Northern Athletic Field	SSHS-B3657	SSHS-B3657-SUB-2-4	1/28/2021	856.29	2 - 4 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3658	SSHS-B3658-SUB-2-4	1/28/2021	856.63	2 - 4 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-10-12	1/29/2021	857.34	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-12-14	1/29/2021	857.34	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3659	SSHS-B3659-SUB-14-16	1/29/2021	857.34	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-10-12	1/29/2021	857.20	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-12-14	1/29/2021	857.20	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3660	SSHS-B3660-SUB-14-16	1/29/2021	857.20	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-10-12	2/3/2021	856.90	10 - 12 ft	180-116771-1	Excavated																				
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-12-14	2/3/2021	856.90	12 - 14 ft	180-116771-1	Excavated																				
Northern Athletic Field	SSHS-B3661	SSHS-B3661-SUB-14-16	2/3/2021	856.90	14 - 16 ft	180-116771-1	Excavated																				
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-10-12	1/29/2021	857.15	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-12-14	1/29/2021	857.15	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3662	SSHS-B3662-SUB-14-16	1/29/2021	857.15	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3663	SSHS-B3663-SUB-12-14	7/19/2021	857.05	12 - 14 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-10-12	2/2/2021	856.55	10 - 12 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-12-14	2/2/2021	856.55	12 - 14 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3664	SSHS-B3664-SUB-14-16	2/2/2021	856.55	14 - 16 ft	180-116723-1	Excavated																				
Northern Athletic Field	SSHS-B3665	SSHS-B3665-SUB-12-14	7/19/2021	856.56	12 - 14 ft	180-124670-1	Excavated																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-10-12	2/1/2021	857.15	10 - 12 ft	180-116686-2	Excavated																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-12-14	2/1/2021	857.15	12 - 14 ft	180-116686-1	Excavated																				
Northern Athletic Field	SSHS-B3666	SSHS-B3666-SUB-14-16	2/1/2021	857.15	14 - 16 ft	180-116686-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-10-12	1/28/2021	851.94	10 - 12 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.19		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	1/28/2021	851.94	12 - 14 ft	180-116609-1	Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.19		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-14-16	1/28/2021	851.94	14 - 16 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-10-12	1/28/2021	852.33	10 - 12 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-12-14	1/28/2021	852.33	12 - 14 ft	180-116609-1	Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3669	SSHS-B3669-SUB-14-16	1/28/2021	852.33	14 - 16 ft	180-116609-2	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	1/29/2021	851.67	10 - 12 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	1/29/2021	851.67	12 - 14 ft	180-116665-1	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	1/29/2021	851.67	14 - 16 ft	180-116665-3	Excavated																				
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-10-12	2/2/2021	851.67	10 - 12 ft	180-116723-1	Excavated		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-12-14	2/2/2021	851.67	12 - 14 ft	180-116723-1	Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.019 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3670	SSHS-B3670-SUB-14-16	2/2/2021	851.67	14 - 16 ft	180-116723-1	Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.35 U	< 0.35 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 0.35 U	0.37				< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated		0.049 J	< 0.33 U	< 0.18 U	< 0.27 U	< 0.27 U	< 0.27 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.084 J	< 0.22 U	0.12 J		< 0.29 U	< 0.3 U	< 0.25 U	< 0.24 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated		< 0.054 U	< 0.64 U	< 0.36 U	< 0.52 U	< 0.51 U	< 0.52 U	< 0.98 U		< 0.095 U	< 0.46 U	< 2.2 U	0.2 J	< 0.42 U	0.28		< 0.55 U	< 0.58 U	< 0.49 U	< 0.46 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated		< 0.058 U	< 0.68 U	< 0.38 U	< 0.55 U	< 0.54 U	< 0.55 U	< 1 U		< 0.1 U	< 0.49 U	< 2.4 U	0.081 J	< 0.45 U	0.077 J		< 0.59 U	< 0.62 U	< 0.52 U	< 0.49 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated		< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.018 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated		< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.023 J		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	14 - 16 ft	1801214241	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.026 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	14 - 16 ft	180-121474-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.13 U	0.037 J	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.31 U		< 0.029 U	< 0.14 U	< 0.7 U	< 0.023 U	< 0.13 U	< 0.021 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated			1.345	< 0.022 U	< 0.017 U	< 0.021 U	0.027 J	< 0.17 U	< 0.016 U	< 0.047 U	0.097	0.1	0.14	0.047 J	0.093	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated			3.76	< 0.022 U	0.11	< 0.02 U	0.1	< 0.16 U	< 0.016 U	< 0.046 U	0.27	0.27	0.39	0.1	0.31	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated			12.79	0.12	0.096	< 0.022 U	0.21	< 0.18 U	0.055 J	< 0.05 U	0.84	0.4	0.79	0.36	0.34	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated			18.207	< 0.022 U	0.73	< 0.021 U	0.52	< 0.17 U	0.085 J	< 0.048 U	1.3	1.7	2	0.86	2	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated			16.585	< 0.022 U	0.65	< 0.021 U	0.44	< 0.17 U	0.082 J	< 0.047 U	1.1	1.5	1.9	0.62	1.9	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated			22.58	0.21	0.21	< 0.022 U	0.36	< 0.18 U	0.14 J	< 0.05 U	1.4	0.73	1.4	0.52	0.77	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated			22.14	0.13	0.42	< 0.021 U	0.59	< 0.17 U	0.11 J	< 0.048 U	1.5	1.2	1.6	0.7	1.1	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated			8.226	0.049 J	0.21	< 0.02 U	0.18	< 0.16 U	0.038 J	< 0.046 U	0.61	0.57	0.78	0.32	0.69	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated			0.369	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.043 J	< 0.033 U	0.039 J	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated			0.235	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	0.035 J	< 0.03 U	0.027 J	0.024 J	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated			0.125	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated			0.097	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.028 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated			0.049	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated			0.078	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated			0.046	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated			0.056	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.034 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	2 - 4 ft	180-123985-1	Not Excavated			10.92	< 0.022 U	0.67	< 0.021 U	0.28	< 0.17 U	< 0.016 U	< 0.048 U	0.93	1	1.4	0.66	1.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	4 - 6 ft	180-123985-2	Not Excavated			1.27	< 0.021 U	0.085	< 0.02 U	0.037 J	< 0.16 U	< 0.015 U	< 0.045 U	0.1	0.11	0.17	0.089	0.14	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated			10.222	< 0.022 U	0.41	< 0.02 U	0.29	< 0.16 U	< 0.016 U	< 0.047 U	0.88	0.99	1.1	0.59	0.74	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated			1.219	< 0.022 U	0.06 J	< 0.021 U	0.026 J	< 0.17 U	< 0.016 U	< 0.047 U	0.13	0.12	0.17	0.06 J	0.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated			4.99	< 0.022 U	0.31	< 0.02 U	0.16	< 0.16 U	< 0.016 U	< 0.046 U	0.4	0.51	0.66	0.22	0.49	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	4 - 6 ft	180-123985-1	Not Excavated			1.171	< 0.023 U	0.06 J	< 0.021 U	0.031 J	< 0.17 U	< 0.017 U	< 0.049 U	0.088 J	0.13 J	0.13 J	0.078 J	0.12	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4027	SSHS-B4027-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Excavated			67.13	0.12	3.3	< 0.02 U	2	< 0.16 U	0.05 J	< 0.046 U	5.6	6.4	7.7	2.8	6.2	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated			0.046	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated			1.594	< 0.021 U	0.033 J	< 0.13 U	0.031 J	< 0.16 U	< 0.13 U	< 0.045 U	0.14	0.14	0.18	0.065 J	0.14	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U		< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated			0.098	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.03 U	0.025 J	< 0.021 U	0.015 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated			4.16	< 0.021 U	0.076 J	< 0.13 U	0.15	< 0.16 U	< 0.13 U	< 0.045 U	0.36 J	0.29 J	0.38 J	0.15 J	0.21	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated			11.195	0.26	0.019 J	< 0.034 U	0.5	< 0.16 U	< 0.034 U	< 0.046 U	0.88	0.55	0.71	0.27	0.42	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated			11.809	0.26	0.028 J	< 0.034 U	0.51	< 0.16 U	< 0.034 U	< 0.045 U	0.96	0.61	0.78	0.27	0.48	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated			20.06	0.45	0.056 J	< 0.034 U	0.89	< 0.16 U	< 0.034 U	< 0.046 U	1.6	1.1	1.3	0.55	0.79	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated			1614.2	39	< 0.84 U	< 0.034 U	76	< 8.4 U	< 0.034 U	< 2.4 U	140	76	100	33	47	< 7.1 U	< 0.7 U	< 1.4 U	< 21 U	< 8.2 U	< 0.034 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated			8.839	0.2	0.018 J	< 0.034 U	0.41 J	< 0.16 U	< 0.034 U	< 0.046 U	0.7	0.44	0.55	0.21 J	0.34	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated			14.404	0.25	0.075 J	< 0.034 U	0.74 J	< 0.17 U	< 0.034 U	< 0.048 U	1.1 J	0.72	0.82	0.42 J	0.46	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated			18.79	0.39	0.07 J	< 0.034 U	0.78	< 0.25 U	< 0.034 U	< 0.071 U	1.6	1.1	1.3	0.48	0.82	< 0.21 U	< 0.021 U	< 0.042 U	< 0.61 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.017 UJ	< 0.034 U	< 0.02 UJ	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U	< 0.034 U	< 0.019 UJ	< 0.023 UJ	< 0.017 UJ	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated			7.325	0.16 J	0.021 J	< 0.034 U	0.31 J	< 0.16 U	< 0.034 U	< 0.046 U	0.6 J	0.37 J	0.46 J	0.22 J	0.3 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated			0.914	< 0.034 U	0.017 J	< 0.034 U	0.026 J	< 0.16 U	< 0.034 U	< 0.046 U	0.076	0.041 J	0.074	0.023 J	0.053 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	12 - 14 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.024 U	< 0.2 U	< 0.034 U	< 0.057 U	< 0.034 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.19 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated			0.29	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.033 J	< 0.034 U	0.03 J	< 0.022 U	0.031 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.034 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 2.3 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.25 U	0.025 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.12	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.24 U	0.04 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.27	0.073 J	0.05 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.89	0.13	0.3 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.2 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.25 U	0.15	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.3	0.35	0.19 J	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.25 U	0.15	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.1	0.35	0.19 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.26 U	0.11	< 0.027 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	1.4	0.22	0.52	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U	< 2.2 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	< 0.25 U	0.21	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.5	0.25	0.39	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.24 U	0.068 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.58	0.13	0.11 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 UT
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.047 J	< 0.049 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 UT	< 0.023 U	< 2.1 UT
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	0.18 J	< 0.23 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	2 - 4 ft	180-123985-1	Not Excavated	< 0.25 U	0.057 J	< 0.026 U	< 0.018 UJ	< 0.018 U	< 0.018 U	< 0.024 U	1	0.26	0.038 J	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	4 - 6 ft	180-123985-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 UJ	< 0.017 U	< 0.017 U	< 0.022 U	0.12	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.24 U	0.068 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.87	0.17	0.056 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.13	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated	< 0.24 U	0.046 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.46	0.12	0.033 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	4 - 6 ft	180-123985-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.11 J	< 0.051 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 UJ
Northern Athletic Field	SSHS-B4027	SSHS-B4027-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Excavated	< 0.24 U	0.33	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	6	1.5	0.19 J	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.15	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 UJ
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	< 0.24 U	0.044 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.33 J	0.051 J	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.24 U	0.15	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.85	0.12	< 0.14 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.24 U	0.15	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.91	0.12	0.15 J	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.24 U	0.26	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.5	0.21	0.26 J	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	< 13 U	23	< 5.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	120	16	21	< 0.034 U	< 1.5 U	< 0.034 U	< 6.5 U	< 7.6 U	< 0.034 U	< 11 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.24 U	0.12	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.66	0.09	< 0.14 UJ	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.25 U	0.2	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.1 J	0.13	0.16 J	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.37 U	0.23	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.4	0.21	0.23 J	< 0.034 U	< 0.044 U	< 0.034 U	< 0.19 U	< 0.23 U	< 0.034 U	< 0.33 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 UJ	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.24 U	0.1 J	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.57 J	0.074 J	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated	< 0.24 U	< 0.034 U	< 0.097 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.065 J	< 0.034 U	< 0.14 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	12 - 14 ft	180-127595-2	Not Excavated	< 0.22 U	< 0.034 U	< 0.09 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.11 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.3 U	< 0.034 U	< 0.12 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.051 U	< 0.034 U	< 0.17 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.15 U	< 0.18 U	< 0.034 U	< 0.27 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.062 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.057 U	< 0.12 U			0.27	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	0.071 J	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.056 U	< 0.12 U			0.61	0.037 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.22	< 0.11 U		< 0.019 U	0.099
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.06 U	< 0.12 U			3	0.17	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	0.33	< 0.11 U		< 0.02 U	0.27
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.058 U	< 0.12 U			2.5	0.077	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U	1.3	< 0.11 U		< 0.02 U	0.35
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.057 U	< 0.12 U			2.1	0.075 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	1.3	< 0.11 U		< 0.019 U	0.34
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.061 U	< 0.13 U			5.1	0.19	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	0.62	< 0.12 U		< 0.021 U	0.79
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	< 0.058 U	< 0.12 U			4.6	0.25	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	1	< 0.11 U		< 0.02 U	0.59
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.056 U	< 0.12 U			1.4	0.067 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.48	< 0.11 U		< 0.019 U	0.19
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.057 U	< 0.12 U			0.088	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			0.068 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.059 U	< 0.12 U			0.042 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.055 U	< 0.11 U			0.029 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.056 U	< 0.12 U			0.027 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.055 U	< 0.11 U			0.032 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.056 U	< 0.11 U			0.026 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.056 U	< 0.12 U			< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.06 U		< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	2 - 4 ft	180-123985-1	Not Excavated	< 0.059 U		< 0.12 U	1.3	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.83	< 0.11 U	< 0.11 U	< 0.02 U	0.11
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	4 - 6 ft	180-123985-2	Not Excavated	< 0.054 U		< 0.11 U	0.14	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.11	< 0.1 U	< 0.11 U	< 0.018 U	0.018 J
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U		1.5	0.052 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.58	< 0.11 U		< 0.019 U	0.086
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U		0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.085	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U		< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated	< 0.056 U		< 0.12 U	0.57	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	0.39	< 0.11 U	< 0.11 U	< 0.019 U	0.11
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	4 - 6 ft	180-123985-1	Not Excavated	< 0.06 U		< 0.12 U	0.16 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	0.1 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Not Excavated	< 0.057 U		< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U
Northern Athletic Field	SSHS-B4027	SSHS-B4027-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Excavated	< 0.056 U		< 0.12 U	9.3	0.41	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	4.7	< 0.11 U	< 0.11 U	< 0.019 U	0.4
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	< 0.2 U		< 0.11 U	0.024 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.21 U		< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	< 0.21 U		< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	< 0.21 U		< 0.11 U	0.24	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	0.11	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.21 U		< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.2 U		< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	< 0.2 U		< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	< 0.21 U		< 0.11 U	0.03 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.21 U		< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.21 U		< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.21 U		< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	< 0.22 U		< 0.11 U	0.77 J	0.03 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	0.21	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.21 U		< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.21 U		< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.11 U	1.9	0.22	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.36	< 0.034 U	< 0.034 U	< 0.034 U	0.048 J
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.11 U	2	0.23	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.41	< 0.034 U	< 0.034 U	< 0.034 U	0.057 J
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.11 U	3.3	0.42	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.7	< 0.034 U	< 0.034 U	< 0.034 U	0.11
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	< 12 U		< 6 U	260	34	< 1.4 U	< 0.034 U	< 0.034 U	< 0.034 U	46	< 0.034 U	< 0.034 U	< 0.034 U	8.3
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.12 U	1.5 J	0.19	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	0.3	< 0.034 U	< 0.034 U	< 0.034 U	0.049 J
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.23 U		< 0.12 U	2.6 J	0.26	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	0.43	< 0.034 U	< 0.034 U	< 0.034 U	0.048 J
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.34 U		< 0.18 U	3.1	0.35	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	0.72	< 0.034 U	< 0.034 U	< 0.034 U	0.1 J
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.23 U		< 0.12 U	< 0.021 UJ	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 UJ	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.12 U	1.2 J	0.15 J	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	0.26 J	< 0.034 U	< 0.034 U	< 0.034 U	0.038 J
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.11 U	0.18	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.043 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	12 - 14 ft	180-127595-2	Not Excavated	< 0.2 U		< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.27 U		< 0.14 U	< 0.024 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.22 U		< 0.11 U	0.068 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.16	< 0.11 U	0.22		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.11 U	0.19	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.43	< 0.11 U	0.49		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.12 U	0.21	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	2.8	< 0.12 U	2.2		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.11 U	1.1	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.1	< 0.12 U	2.1		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.11 U	1.3	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.1	< 0.11 U	1.8		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.12 U	0.66	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	5.3	< 0.12 U	3.7		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	< 0.11 U	0.72	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	3.7	< 0.12 U	3.3		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.11 U	0.36	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.91	< 0.11 U	1.1		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.072 J	< 0.11 U	0.08		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.03 J	< 0.11 U	0.051 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.028 J	< 0.12 U	0.055 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.028 J	< 0.11 U	0.04 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.022 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.022 J	< 0.11 U	0.024 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.02 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.056 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	2 - 4 ft	180-123985-1	Not Excavated		0.2	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.36	< 0.12 U	1.6		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	4 - 6 ft	180-123985-2	Not Excavated		0.049 J	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.035 J	< 0.11 U	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.11 U	0.14	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.82	< 0.11 U	1.5		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.058 J	< 0.11 U	0.19		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated		0.11	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.27	< 0.11 U	0.63		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	4 - 6 ft	180-123985-1	Not Excavated		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.074 J	< 0.12 U	0.15 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4027	SSHS-B4027-SUB-4-6	7/1/2021	856.99	4 - 6 ft	180-123985-1	Excavated		0.6	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	4.1	< 0.11 U	9.7		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.022 J		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 UJ		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated		0.038 J	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.12	< 0.11 U	0.24		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 UJ	< 0.11 U	0.028 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated		0.059 J	< 0.17 U	< 0.092 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.48 J	< 0.11 U	0.69 J		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated		0.055 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	2.3	< 0.11 U	1.8		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated		0.069 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	2.3	< 0.11 U	1.9		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated		0.15	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	4	< 0.11 U	3.1		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated		7.2	< 0.034 U	< 0.034 U	< 7.2 U	< 0.034 U	< 0.034 U	< 14 U		< 0.034 U	< 0.034 U	< 0.034 U	350	< 5.8 U	270		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated		0.049 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	1.8	< 0.11 U	1.4		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated		0.074 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	3 J	< 0.12 U	2.3 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated		0.14	< 0.034 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.4 U		< 0.034 U	< 0.034 U	< 0.034 U	3.5	< 0.17 U	2.9		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 UJ		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated		0.051 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	1.4 J	< 0.11 U	1.2 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated		0.023 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.17	< 0.11 U	0.14		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	12 - 14 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	< 0.016 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.32 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.022 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.069 J	< 0.11 U	0.059 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated			2.435	< 0.034 U	0.048 J	< 0.034 U	0.068 J	< 0.16 U	< 0.034 U	< 0.046 U	0.2	0.16	0.22	0.076	0.17	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated			0.184	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	0.021 J	< 0.021 U	0.023 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated			1.821	< 0.034 U	< 0.061 UJ	< 0.034 U	< 0.072 UJ	< 0.61 U	< 0.034 U	< 0.17 U	0.15 J	0.14 J	0.23 J	< 0.084 UJ	0.21 J	< 0.51 U	< 0.051 U	< 0.1 U	< 1.5 U	< 0.59 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated			3.06	< 0.034 U	0.094 J	< 0.034 U	< 0.091 UJ	< 0.77 U	< 0.034 U	< 0.22 U	0.24 J	0.27 J	0.35	0.11 J	0.34 J	< 0.64 U	< 0.064 U	< 0.13 U	< 1.9 U	< 0.75 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated			3.656	< 0.034 U	0.11 J	< 0.034 U	0.096 J	< 0.78 U	< 0.034 U	< 0.22 U	0.3 J	0.3 J	0.42	0.13 J	0.38	< 0.65 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.76 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated			19.65	< 0.034 U	0.5 J	< 0.034 U	0.64	< 1.3 U	< 0.034 U	< 0.36 U	1.7	1.5	2	0.69	1.6	< 1.1 U	< 0.11 U	< 0.21 U	< 3.1 U	< 1.2 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated			1.556	< 0.034 U	0.055 J	< 0.034 U	0.052 J	< 0.31 U	< 0.034 U	< 0.088 U	0.13 J	0.11 J	0.17	0.052 J	0.18	< 0.26 U	< 0.026 U	< 0.052 U	< 0.75 U	< 0.3 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated			0.58	< 0.034 U	< 0.065 U	< 0.034 U	< 0.077 U	< 0.65 U	< 0.034 U	< 0.18 U	< 0.034 U	< 0.034 U	0.13 J	< 0.089 U	0.13 J	< 0.54 U	< 0.054 U	< 0.11 U	< 1.6 U	< 0.63 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated			2.618	< 0.034 U	0.076 J	< 0.034 U	< 0.076 U	< 0.64 U	< 0.034 U	< 0.18 U	0.21 J	0.22 J	0.29	0.11 J	0.3	< 0.53 U	< 0.053 U	< 0.11 U	< 1.6 U	< 0.62 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated			7.534	0.033 J	0.12	< 0.034 U	0.27	< 0.18 U	< 0.034 U	< 0.05 U	0.61	0.44	0.61	0.23	0.38	< 0.034 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated			3.303	< 0.034 U	0.062 J	< 0.034 U	0.12	< 0.17 U	< 0.034 U	< 0.048 U	0.28	0.21	0.3	0.099	0.17	< 0.034 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated			1.122	< 0.034 U	0.021 J	< 0.034 U	0.043 J	< 0.17 U	< 0.034 U	< 0.047 U	0.1	0.094	0.1	0.053 J	0.068 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated			8.578	0.027 J	0.12	< 0.034 U	0.3	< 0.17 U	< 0.034 U	< 0.034 U	0.66	0.45	0.62	0.25	0.34	< 0.034 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated			1.946	< 0.034 U	0.063 J	< 0.034 U	0.055 J	< 0.15 U	< 0.034 U	< 0.044 U	0.16	0.16	0.2	0.092	0.16	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated			1.247	< 0.034 U	0.021 J	< 0.034 U	0.038 J	< 0.16 U	< 0.034 U	< 0.045 U	0.098	0.076	0.11	0.043 J	0.062 J	< 0.034 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated			2.24	< 0.034 U	0.037 J	< 0.034 U	0.072 J	< 0.17 U	< 0.034 U	< 0.048 U	0.19	0.14	0.2	0.072 J	0.12	< 0.034 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.034 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated			ND	< 0.34	< 0.34		< 0.34				< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated			ND	< 0.36	< 0.36		< 0.36				< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated			< 0	< 0.36 U	< 0.36 U		< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-6-8	9/22/2016	850.44	6 - 8 ft	180-59029-1	Excavated			0.981	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	0.068 J	< 0.057 U	0.031 J	0.021 J	0.057 J	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated			1.29	0.027 J	< 0.01 U	< 0.038 U	0.031 J	< 0.045 U	0.043 J	< 0.069 U	0.071 J	0.046 J	0.08 J	0.028 J	0.047 J	< 0.03 U	< 0.012 U	< 0.0099 U	< 0.074 U	< 0.04 U	< 0.062 U
Rear Parking Lot	SSHS-B548	SSHS-B548-SUB-6-8	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated			0.7	< 0.0077 U	< 0.0092 U	< 0.033 U	0.01 J	< 0.039 U	< 0.036 U	< 0.06 U	0.032 J	0.021 J	0.054 J	< 0.016 U	0.03 J	< 0.026 U	< 0.011 U	< 0.0086 U	< 0.065 U	< 0.035 U	< 0.055 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated			0.686	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	0.068	0.055	0.068	0.037	0.061	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated			1.583	< 0.007	< 0.0083	< 0.03	< 0.0071	< 0.035	< 0.032	< 0.054	0.18	0.059	0.11	0.037	0.047	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated			0.932	< 0.0068	0.039	< 0.029	< 0.0069	< 0.034	< 0.031	< 0.053	0.088	0.065	0.088	0.037	0.071	< 0.023	< 0.0095	< 0.0076	< 0.057	< 0.031	< 0.048
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated			ND	< 0.0074 U	< 0.0089 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.035 U	< 0.058 U	< 0.0097 U	< 0.0078 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated			0.636	< 0.0074 U	< 0.0089 U	< 0.032 U	0.013 J	< 0.038 U	< 0.035 U	< 0.058 U	0.042 J	0.029 J	0.062 J	< 0.016 U	< 0.0077 U	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated			0.55	< 0.0074 U	< 0.0089 U	0.034 J	0.018 J	< 0.038 U	< 0.035 U	0.063 J	< 0.0097 U	< 0.0077 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.025 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated			2.078	0.034 J	0.024 J	0.072 J	0.037 J	< 0.036 U	0.07 J	< 0.056 U	0.1	0.082	0.14	0.052 J	0.099	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated			ND	< 0.0071 U	< 0.0085 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0093 U	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated			0.835	< 0.0081 U	0.025 J	< 0.035 U	0.022 J	< 0.041 U	< 0.038 U	< 0.063 U	0.081 J	0.056 J	0.077 J	0.029 J	0.068 J	< 0.028 U	< 0.011 U	< 0.0091 U	< 0.068 U	< 0.037 U	< 0.058 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated			1.413	< 0.007 U	0.018 J	< 0.03 U	0.026 J	< 0.036 U	< 0.033 U	< 0.055 U	0.097	0.088	0.14	0.047 J	0.099	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated			0.038	< 0.014 U	< 0.016 U	< 0.059 U	< 0.014 U	< 0.069 U	< 0.064 U	< 0.11 U	< 0.018 U	< 0.014 U	< 0.022 U	< 0.029 U	< 0.014 U	< 0.047 U	< 0.019 U	< 0.015 U	< 0.12 U	< 0.062 U	< 0.097 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated			26.16	0.68	0.048 J	0.077 J	1.2	< 0.039 U	0.12 J	< 0.06 UJ	1.8	1.6	1.8	0.78	1.3	< 0.026 U	< 0.011 U	< 0.0086 U	< 0.064 U	< 0.035 U	< 0.054 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated			ND	< 0.0069 U	< 0.0082 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.009 U	< 0.0072 U	< 0.011 U	< 0.015 U	< 0.0071 U	< 0.024 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U	< 0.049 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Not Excavated			0.088	< 0.007 U	< 0.0083 U	< 0.03 U	0.011 J	< 0.035 U	< 0.032 U	< 0.055 U	< 0.0091 U	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated			6.41	0.28	0.29	< 0.03 U	0.23	< 0.036 U	0.11 J	< 0.055 U	0.37	0.35	0.57	0.19	0.47	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated			0.238	< 0.007 U	0.013 J	< 0.03 U	0.017 J	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0092 U	< 0.0073 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	0.1 J	< 0.032 U	< 0.05 U
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated			5.735	0.074 J	0.12	0.13 J	0.17	< 0.039 U	0.14 J	< 0.06 U	0.38	0.32	0.48	0.2	0.34	< 0.026 U	< 0.011 U	< 0.0086 U	< 0.065 U	< 0.035 U	< 0.055 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated			2.816	< 0.036 U	< 0.043 U	< 0.15 U	0.086 J	< 0.18 U	< 0.17 U	< 0.28 R	0.24 J	0.19 J	0.22 J	0.2 J	0.19 J	< 0.12 U	< 0.05 U	< 0.04 U	< 0.3 U	< 0.16 U	< 0.25 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated			3.711	0.037 J	0.15	< 0.03 U	0.13	< 0.036 U	0.037 J	< 0.055 U	0.32	0.26	0.37	0.14	0.32	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated			65.33																		
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated			ND	< 0.0072 U	< 0.0085 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0093 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated			14.48	0.14	0.42	< 0.03 U	0.46	< 0.035 U	< 0.032 U	< 0.055 U	1.3	1.3	1.5	0.69	1.1	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)DL	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated			74.88	0.54	0.062 J	< 0.15 U	2.5	< 0.18 U	< 0.17 U	< 0.28 U	6.7	5.8	6.9	2.6	4.2	< 0.12 U	< 0.05 U	< 0.04 U	< 0.3 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated			0.041	< 0.0069	< 0.0082	< 0.03	< 0.007	< 0.035	< 0.032	< 0.054	< 0.009	< 0.0072	< 0.011	< 0.015	< 0.0071	< 0.024	< 0.0096	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated			ND	< 0.0068	< 0.0081	< 0.029	< 0.0069	< 0.034	< 0.031	< 0.053	< 0.0088	< 0.0071	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0095	< 0.0076	< 0.057	< 0.031	< 0.048
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated			ND	< 0.0067	< 0.0079	< 0.028	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0087	< 0.0069	< 0.011	< 0.014	< 0.0069	< 0.023	< 0.0093	< 0.0075	< 0.056	< 0.03	< 0.047
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0087	< 0.007	< 0.011	< 0.014	< 0.0069	< 0.023	< 0.0093	< 0.0075	< 0.056	< 0.03	< 0.048
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated			6.0561	0.0091	0.14	< 0.03	0.15	< 0.036	< 0.033	< 0.055	0.52	0.56	0.6	0.3	0.62	< 0.024	< 0.0098	< 0.0079	< 0.059	< 0.032	< 0.05
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated			0.333	< 0.0073	0.02	< 0.031	0.012	< 0.037	< 0.034	< 0.057	0.036	0.034	0.043	0.016	< 0.0075	< 0.025	< 0.01	< 0.0081	< 0.061	< 0.033	< 0.052
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated			ND	< 0.0071	< 0.0085	< 0.03	< 0.0072	< 0.036	< 0.033	< 0.055	< 0.0093	< 0.0074	< 0.012	< 0.015	< 0.0074	< 0.024	< 0.0099	< 0.008	< 0.06	< 0.032	< 0.05
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	< 0.0089	< 0.0071	< 0.011	< 0.014	< 0.0071	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated			ND	< 0.0072	< 0.0086	< 0.031	< 0.0074	< 0.037	< 0.034	< 0.057	< 0.0095	< 0.0076	< 0.012	< 0.015	< 0.0075	< 0.025	< 0.01	< 0.0081	< 0.061	< 0.033	< 0.052
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0088	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0075	< 0.056	< 0.03	< 0.048
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0088	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0075	< 0.056	< 0.03	< 0.048
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated			ND	< 0.0069	< 0.0083	< 0.03	< 0.0071	< 0.035	< 0.032	< 0.054	< 0.009	< 0.0072	< 0.011	< 0.015	< 0.0072	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated			ND	< 0.0068	< 0.0081	< 0.029	< 0.0069	< 0.034	< 0.032	< 0.053	< 0.0089	< 0.0071	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0095	< 0.0076	< 0.057	< 0.031	< 0.048
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	< 0.0089	< 0.0071	< 0.011	< 0.014	< 0.0071	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031	< 0.049
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated			ND	< 0.0067 U	< 0.008 U	< 0.029 U	< 0.0068 U	< 0.034 U	< 0.031 U	< 0.052 U	< 0.0088 U	< 0.007 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0094 U	< 0.0075 U	< 0.056 U	< 0.03 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated			8.138	0.013 J	0.17	< 0.03 U	0.26	< 0.036 U	< 0.033 U	< 0.055 U	0.7	0.75	0.82	0.34	0.79	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated			ND	< 0.007 U	< 0.0084 U	< 0.03 U	< 0.0071 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0091 U	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 UJ	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.0091 U	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated			ND	< 0.0071 U	< 0.0085 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 UJ	< 0.0093 U	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroani**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**	**3,3-Dichlorobenzidine**	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7																				
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated	< 0.24 U	0.029 J	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.2	< 0.034 U	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.91 U	< 0.034 U	< 0.37 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.15 J	< 0.034 U	< 0.51 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.47 U	< 0.55 U	< 0.034 U	< 0.81 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 1.1 U	< 0.034 U	< 0.46 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24 J	< 0.034 U	< 0.65 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.59 U	< 0.69 U	< 0.034 U	< 1 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 1.2 U	< 0.034 U	< 0.47 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.28 J	< 0.034 U	< 0.66 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.6 U	< 0.7 U	< 0.034 U	< 1 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	< 1.9 U	0.14 J	< 0.76 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.5	0.43 J	< 1.1 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.97 U	< 1.1 U	< 0.034 U	< 1.7 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.46 U	< 0.034 U	< 0.19 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.12 J	< 0.034 U	< 0.26 U	< 0.034 U	< 0.055 U	< 0.034 U	< 0.24 U	< 0.28 U	< 0.034 U	< 0.41 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.97 U	< 0.034 U	< 0.39 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.55 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.5 U	< 0.59 U	< 0.034 U	< 0.86 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	< 0.95 U	< 0.034 U	< 0.38 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21 J	< 0.034 U	< 0.54 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.49 U	< 0.58 U	< 0.034 U	< 0.85 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	< 0.26 U	0.087	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.54	0.091	0.15 J	< 0.034 U	< 0.031 U	< 0.034 U	< 0.14 U	< 0.16 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	< 0.25 U	0.031 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	< 0.25 U	< 0.034 U	< 0.099 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.098	< 0.034 U	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.25 U	0.062 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.68	0.091	0.2 J	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.23 U	0.018 J	< 0.092 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.24 U	0.017 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.1	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.25 U	0.027 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated		< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 1.8	< 0.34	< 1.8
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated		< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 1.8	< 0.36	< 1.8
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 1.8 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-6-8	9/22/2016	850.44	6 - 8 ft	180-59029-1	Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	0.14	< 0.0084 U	0.087 J	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 2 U
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	< 0.35 U	0.017 J	< 0.037 U	< 0.042 U	< 0.0095 U	< 0.037 U	< 0.051 U	0.15	< 0.01 U	0.075 J	< 0.048 U	< 0.0092 U	< 0.05 U	< 0.071 U	< 0.05 U	< 0.057 U	< 0.048 U	< 0.18 U	< 0.047 U	< 0.54 U
Rear Parking Lot	SSHS-B548	SSHS-B548-SUB-6-8	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	< 0.3 U	< 0.0074 U	< 0.032 U	< 0.037 U	< 0.0084 U	< 0.033 U	< 0.045 U	0.095	< 0.0089 U	0.049 J	< 0.042 U	< 0.008 U	< 0.044 U	< 0.063 U	< 0.044 U	< 0.05 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.48 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0074	< 0.029	< 0.04	0.093	0.011	< 0.035	< 0.038	< 0.0071	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	< 0.27	< 0.0067	< 0.029	< 0.033	< 0.0076	< 0.03	< 0.04	0.46	< 0.0081	< 0.036	< 0.038	< 0.0073	< 0.04	< 0.057	< 0.039	< 0.045	< 0.038	< 0.15	< 0.037	< 0.43
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.032	< 0.0074	< 0.029	< 0.039	0.16	< 0.0078	< 0.035	< 0.037	< 0.0071	< 0.039	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	< 0.038 U	< 0.041 U	< 0.0078 U	< 0.042 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	0.13	< 0.0086 U	< 0.038 U	< 0.041 U	< 0.0078 U	< 0.042 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	0.044 J	< 0.041 U	< 0.0078 U	< 0.042 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.28 U	0.025 J	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	0.22	0.039 J	0.16 J	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.44 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.32 U	< 0.0078 U	< 0.034 U	< 0.039 U	< 0.0088 U	< 0.035 U	< 0.047 U	0.11	< 0.0094 U	< 0.042 U	< 0.045 U	< 0.0085 U	< 0.046 U	< 0.066 U	< 0.046 U	< 0.053 U	< 0.045 U	< 0.17 U	< 0.044 U	< 0.5 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	0.14	0.025 J	0.051 J	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.54 U	< 0.013 U	< 0.057 U	< 0.066 U	< 0.015 U	< 0.058 U	< 0.079 U	< 0.017 U	< 0.016 U	< 0.07 U	< 0.075 U	< 0.014 U	< 0.078 U	< 0.11 U	< 0.078 U	< 0.089 U	< 0.075 U	< 0.29 U	< 0.073 U	< 0.85 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.3 U	0.37	< 0.032 U	< 0.037 U	< 0.0083 U	< 0.033 U	< 0.044 U	1.8	0.28	0.53	< 0.042 U	< 0.008 U	< 0.043 U	< 0.062 U	< 0.043 U	< 0.05 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.47 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0066 U	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	< 0.0085 U	< 0.008 U	< 0.035 U	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0087 U	< 0.0081 U	< 0.036 U	< 0.038 U	< 0.0073 U	0.047 J	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	< 0.28 U	0.21	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	0.45	0.12	0.54	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.28 U	0.03 J	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0081 U	< 0.036 U	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	< 0.3 U	0.066 J	< 0.032 U	< 0.037 U	< 0.0084 U	< 0.033 U	< 0.045 U	0.56	0.091	0.27 J	< 0.042 U	< 0.008 U	< 0.044 U	< 0.063 U	< 0.044 U	< 0.05 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.48 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 1.4 U	< 0.034 U	< 0.15 U	< 0.17 U	< 0.039 U	< 0.15 U	< 0.21 U	0.3 J	< 0.041 U	< 0.18 U	< 0.2 U	< 0.037 U	< 0.2 U	< 0.29 U	< 0.2 U	< 0.23 U	< 0.2 U	< 0.75 U	< 0.19 U	< 2.2 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.28 U	0.033 J	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	0.44	0.091	0.084 J	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated																				
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.03 U	< 0.041 U	< 0.0089 U	< 0.0083 U	< 0.037 U	< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	< 0.27 U	0.13	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	1.4	0.23	0.11 J	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)DL	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	< 1.4 U	0.64	< 0.15 U	< 0.17 U	< 0.039 U	< 0.15 U	< 0.21 U	6.4	0.93	0.32 J	< 0.2 U	< 0.037 U	< 0.2 U	< 0.29 U	< 0.2 U	< 0.23 U	< 0.2 U	< 0.75 U	< 0.19 U	< 2.2 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	< 0.0086	< 0.008	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.43
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.032	< 0.0074	< 0.029	< 0.039	< 0.0084	< 0.0078	< 0.035	< 0.037	< 0.0071	< 0.039	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0072	< 0.028	< 0.039	< 0.0083	< 0.0077	< 0.034	< 0.037	< 0.007	< 0.038	< 0.054	< 0.038	< 0.043	< 0.037	< 0.14	< 0.036	< 0.41
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.028	< 0.039	< 0.0083	< 0.0077	< 0.034	< 0.037	< 0.007	< 0.038	< 0.054	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.41
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.28	0.032	< 0.029	< 0.034	< 0.0077	< 0.03	< 0.041	0.51	0.14	0.045	< 0.039	< 0.0074	< 0.04	< 0.057	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.28	< 0.007	< 0.03	< 0.035	< 0.0079	< 0.031	< 0.042	0.036	< 0.0084	< 0.037	< 0.04	< 0.0076	< 0.041	< 0.059	< 0.041	< 0.047	< 0.04	< 0.15	< 0.039	< 0.45
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.28	< 0.0068	< 0.03	< 0.034	< 0.0077	< 0.03	< 0.041	< 0.0088	< 0.0082	< 0.036	< 0.039	< 0.0074	< 0.04	< 0.058	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.27	< 0.0066	< 0.028	< 0.033	< 0.0074	< 0.029	< 0.04	< 0.0085	< 0.0079	< 0.035	< 0.038	< 0.0071	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.28	< 0.007	< 0.03	< 0.035	< 0.0079	< 0.031	< 0.042	< 0.009	< 0.0084	< 0.037	< 0.04	< 0.0076	< 0.041	< 0.059	< 0.041	< 0.047	< 0.04	< 0.15	< 0.039	< 0.45
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0083	< 0.0078	< 0.034	< 0.037	< 0.007	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0083	< 0.0078	< 0.034	< 0.037	< 0.007	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	< 0.0086	< 0.008	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.43
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.033	< 0.0074	< 0.029	< 0.039	< 0.0084	< 0.0079	< 0.035	< 0.037	< 0.0071	< 0.039	< 0.055	< 0.039	< 0.044	< 0.037	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0074	< 0.029	< 0.04	< 0.0085	< 0.0079	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.42
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.26 U	< 0.0064 U	< 0.028 U	< 0.032 U	< 0.0073 U	< 0.029 U	< 0.039 U	< 0.0083 U	< 0.0078 U	< 0.034 U	< 0.037 U	< 0.007 U	< 0.038 U	< 0.055 U	< 0.038 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	< 0.28 U	0.061 J	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.68	0.17	0.057 J	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0081 U	< 0.036 U	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.041 U	< 0.0089 U	< 0.0083 U	< 0.037 U	< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0086 U	< 0.0081 U	< 0.036 U	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.12 U	0.43	0.029 J	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.034 U	< 0.034 U	< 0.034 U	0.032 J
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated	< 0.21 U			< 0.11 U	0.05 J	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.83 U			< 0.43 U	0.26 J	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	0.17 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 1 U			< 0.55 U	0.47	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.034 U	0.29 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 1.1 U			< 0.55 U	0.53	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.034 U	0.32 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	< 1.7 U			< 0.9 U	3.1	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U	1.4	< 0.034 U	< 0.034 U	< 0.034 U	0.19 J
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.42 U			< 0.22 U	0.23	< 0.034 U	< 0.051 U	< 0.034 U	< 0.034 U	< 0.034 U	0.13 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.89 U			< 0.46 U	0.14 J	< 0.034 U	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	< 0.87 U			< 0.45 U	0.37	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	< 0.24 U			< 0.13 U	1.6	0.1	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	0.36	< 0.034 U	< 0.034 U	< 0.034 U	0.1
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.12 U	0.66	0.034 J	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.034 U	< 0.034 U	< 0.034 U	0.027 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.12 U	0.18	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	0.057 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.034 U	2.3	0.08	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	0.36	< 0.034 U	< 0.034 U	< 0.034 U	0.082
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.21 U			< 0.11 U	0.31	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.034 U	< 0.034 U	< 0.034 U	0.028 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.22 U			< 0.11 U	0.23	0.023 J	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	0.057 J	< 0.034 U	< 0.034 U	< 0.034 U	0.018 J
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.12 U	0.4	0.042 J	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	0.11	< 0.034 U	< 0.034 U	< 0.034 U	0.034 J
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.34				< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34		< 0.34	< 0.34
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.36				< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36		< 0.36	< 0.36
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.36 U				< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U		< 0.36 U	< 0.36 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-6-8	9/22/2016	850.44	6 - 8 ft	180-59029-1	Excavated	< 0.031 U			< 0.043 U	0.09	0.081	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	< 0.0078 U	< 0.026 U		< 0.029 U	0.27
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U		< 0.38 U	< 0.38 U
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	< 0.037 U			< 0.052 U	0.14	0.037 J	< 0.0097 U	< 0.01 U	< 0.049 U	< 0.033 U	0.023 J	< 0.032 U		< 0.034 U	0.22
Rear Parking Lot	SSHS-B548	SSHS-B548-SUB-6-8	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	< 0.032 U			< 0.046 U	0.073 J	0.019 J	< 0.0085 U	< 0.009 U	< 0.043 U	< 0.029 U	0.021 J	< 0.028 U		< 0.03 U	0.16
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	< 0.029			< 0.041	0.11	< 0.0094	< 0.0076	< 0.008	< 0.038	< 0.026	0.043	< 0.025		< 0.027	0.0077
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	< 0.029			< 0.042	< 0.0077	0.16	< 0.0077	< 0.0081	< 0.039	< 0.026	0.05	< 0.025		< 0.027	< 0.0065
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	< 0.028			< 0.04	0.17	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025	0.045	< 0.025		< 0.027	0.0078
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.044 U	< 0.0083 U	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U	< 0.008 U	< 0.027 U		< 0.029 U	< 0.007 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.044 U	0.065 J	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U	0.025 J	< 0.027 U		< 0.029 U	0.078
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.031 U			< 0.044 U	0.085	< 0.01 U	< 0.0082 U	< 0.0087 U	< 0.042 U	< 0.028 U	< 0.008 U	< 0.027 U		< 0.029 U	0.12
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.03 U			< 0.043 U	0.23	0.06 J	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	0.065 J	< 0.026 U		< 0.028 U	0.5
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0097 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	< 0.0076 U	< 0.026 U		< 0.028 U	< 0.0067 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.034 U			< 0.048 U	0.11	< 0.011 U	< 0.009 U	< 0.0095 U	< 0.046 U	< 0.03 U	0.04 J	< 0.03 U		< 0.032 U	0.056 J
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.03 U			< 0.042 U	0.2	0.015 J	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U	0.076	< 0.026 U		< 0.028 U	0.17
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.058 U			< 0.082 U	0.02 J	< 0.019 U	< 0.015 U	< 0.016 U	< 0.077 U	< 0.051 U	< 0.015 U	< 0.05 U		< 0.054 U	0.025 J
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.032 U			< 0.046 U	4.9	0.66	< 0.0085 U	< 0.0089 U	< 0.043 U	< 0.029 U	1.1	< 0.028 U		< 0.03 U	0.73
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0077 U	< 0.0095 U	< 0.0076 U	< 0.008 U	< 0.039 U	< 0.026 U	< 0.0074 U	< 0.025 U		< 0.027 U	< 0.0065 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.029 U			< 0.042 U	0.03 J	< 0.0096 U	< 0.0078 U	< 0.0081 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.025 U		< 0.027 U	0.0096 J
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	< 0.029 U			< 0.042 U	0.88	0.3	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U	0.37	< 0.025 U		< 0.028 U	0.11
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.03 U			< 0.042 U	0.053 J	0.029 J	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.026 U		< 0.028 U	0.014 J
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	< 0.032 U			< 0.046 U	0.84	0.11	< 0.0085 U	< 0.009 U	< 0.043 U	< 0.029 U	0.25	< 0.028 U		< 0.03 U	0.88
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 0.15 U			< 0.21 U	0.33 J	< 0.049 U	< 0.04 U	< 0.042 U	< 0.2 U	< 0.13 U	0.18 J	< 0.13 U		< 0.14 U	0.33 J
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.03 U			< 0.042 U	0.44	0.053 J	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U	0.23	< 0.026 U		< 0.028 U	0.27
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated															
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0098 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0067 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	< 0.029 U			< 0.042 U	2	0.14	< 0.0078 U	< 0.0081 U	< 0.039 U	< 0.026 U	0.92	< 0.025 U	< 0.036 U	< 0.027 U	0.17
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)DL	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	< 0.15 U			< 0.21 U	15	0.65	< 0.04 U	< 0.042 U	< 0.2 U	< 0.13 U	3.7	< 0.13 U	< 0.18 U	< 0.14 U	0.2 J
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.029			< 0.041	0.015	< 0.0095	< 0.0077	< 0.008	< 0.039	< 0.026	< 0.0074	< 0.025		< 0.027	0.0096
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025	< 0.0073	< 0.025		< 0.027	< 0.0063
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.028			< 0.04	< 0.0074	< 0.0091	< 0.0074	< 0.0078	< 0.037	< 0.025	< 0.0071	< 0.024		< 0.026	< 0.0062
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.028			< 0.04	< 0.0074	< 0.0092	< 0.0074	< 0.0078	< 0.038	< 0.025	< 0.0072	< 0.024		< 0.026	< 0.0063
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.03			< 0.042	0.83	0.027	< 0.0078	< 0.0082	< 0.04	< 0.026	0.49	< 0.026		< 0.028	0.051
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.03			< 0.043	0.051	< 0.0099	< 0.008	< 0.0084	< 0.041	< 0.027	0.026	< 0.026		< 0.028	0.013
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.03			< 0.042	< 0.0079	< 0.0097	< 0.0079	< 0.0083	< 0.04	< 0.027	< 0.0076	< 0.026		< 0.028	< 0.0066
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.029			< 0.041	< 0.0076	< 0.0094	< 0.0076	< 0.008	< 0.038	< 0.026	< 0.0073	< 0.025		< 0.027	< 0.0064
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.03			< 0.043	< 0.0081	< 0.0099	< 0.008	< 0.0084	< 0.041	< 0.027	< 0.0078	< 0.026		< 0.028	< 0.0068
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0092	< 0.0074	< 0.0078	< 0.038	< 0.025	< 0.0072	< 0.024		< 0.026	< 0.0063
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0092	< 0.0074	< 0.0078	< 0.038	< 0.025	< 0.0072	< 0.024		< 0.026	< 0.0063
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.029			< 0.041	< 0.0077	< 0.0095	< 0.0077	< 0.0081	< 0.039	< 0.026	< 0.0074	< 0.025		< 0.027	< 0.0065
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.029			< 0.041	< 0.0076	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025	< 0.0073	< 0.025		< 0.027	< 0.0064
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.029			< 0.041	< 0.0076	< 0.0094	< 0.0076	< 0.008	< 0.038	< 0.026	< 0.0073	< 0.025		< 0.027	< 0.0064
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.028 U			< 0.04 U	< 0.0075 U	< 0.0092 U	< 0.0074 U	< 0.0078 U	< 0.038 U	< 0.025 U	< 0.0072 U	< 0.024 U	< 0.034 U	< 0.026 U	< 0.0063 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	< 0.03 U			< 0.042 U	1.2	0.035 J	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U	0.63	< 0.026 U	< 0.036 U	< 0.028 U	0.058 J
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0098 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.025 U	< 0.036 U	< 0.027 U	< 0.0065 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0098 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	< 0.0076 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0067 U

DRAFT

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated		0.092	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.27	< 0.11 U	0.38		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.049 J	< 0.11 U	0.041 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated		0.071 J	< 0.034 U	< 0.034 U	< 0.52 U	< 0.034 U	< 0.034 U	< 0.98 U		< 0.034 U	< 0.034 U	< 0.034 U	0.13 J	< 0.42 U	0.31 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated		0.09 J	< 0.034 U	< 0.034 U	< 0.65 U	< 0.034 U	< 0.034 U	< 1.2 U		< 0.034 U	< 0.034 U	< 0.034 U	0.23 J	< 0.53 U	0.43		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated		0.12 J	< 0.034 U	< 0.034 U	< 0.66 U	< 0.034 U	< 0.034 U	< 1.2 U		< 0.034 U	< 0.034 U	< 0.034 U	0.25 J	< 0.54 U	0.53		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated		0.69	< 0.034 U	< 0.034 U	< 1.1 U	< 0.034 U	< 0.034 U	< 2 U		< 0.034 U	< 0.034 U	< 0.034 U	1.5	< 0.88 U	2.9		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated		0.052 J	< 0.034 U	< 0.034 U	< 0.26 U	< 0.034 U	< 0.034 U	< 0.5 U		< 0.034 U	< 0.034 U	< 0.034 U	0.12 J	< 0.21 U	0.21		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.55 U	< 0.034 U	< 0.034 U	< 1 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.45 U	0.18 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated		0.098 J	< 0.034 U	< 0.034 U	< 0.54 U	< 0.034 U	< 0.034 U	< 1 U		< 0.034 U	< 0.034 U	< 0.034 U	0.17 J	< 0.44 U	0.39		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated		0.24	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	0.73	< 0.12 U	1.3		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated		0.08	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.4	< 0.12 U	0.54		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated		0.022 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.13	< 0.11 U	0.18		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated		0.24	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.38	< 0.12 U	1.8		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated		0.049 J	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.17	< 0.11 U	0.29		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated		0.04 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.11 U	0.21		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated		0.074 J	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.29	< 0.12 U	0.35		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.34	< 0.34	< 1.8	< 1.8	< 1.8	< 0.34	< 0.34	< 1.8	< 0.34	< 0.34	< 0.34	< 1.8	< 0.34	< 0.34	< 0.34				< 0.34	< 0.34
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.36	< 0.36	< 1.8	< 1.8	< 1.8	< 0.36	< 0.36	< 1.8	< 0.36	< 0.36	< 0.36	< 1.8	< 0.36	< 0.36	< 0.36				< 0.36	< 0.36
Northern Athletic Field	SSHS-B50	_13 Sep 00B50_4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B52	_13 Sep 00B52_4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.36 U	< 0.36 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 0.36 U	< 0.36 U	< 1.8 U	< 0.36 U	< 0.36 U	< 0.36 U				< 0.36 U	< 0.36 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-6-8	9/22/2016	850.44	6 - 8 ft	180-59029-1	Excavated	< 0.037 U	0.15	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	0.33	< 0.009 U	0.081		< 0.029 U	< 0.024 U	< 0.04 U	< 0.057 U
Northern Athletic Field	SSHS-B54	_13 Sep 00B54_4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.38 U	< 0.38 U	< 2 U	< 2 U	< 2 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2 U	< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	< 0.045 U	0.12	< 0.2 U	< 0.19 U	< 0.19 U	< 0.038 U	< 0.05 U	< 0.17 U		< 0.011 U	< 0.042 U	< 0.041 U	0.35	< 0.011 U	0.14		< 0.035 U	< 0.029 U	< 0.049 U	< 0.068 U
Rear Parking Lot	SSHS-B548	SSHS-B548-SUB-6-8	9/21/2016	850.36	6 - 8 ft	180-59020-1	Excavated	< 0.039 U	0.085	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.044 U	< 0.15 U		< 0.0094 U	< 0.037 U	< 0.036 U	0.2	< 0.0095 U	0.06 J		< 0.03 U	< 0.026 U	< 0.043 U	< 0.06 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084	0.14		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	< 0.035	< 0.0062	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0085	< 0.034	< 0.032	0.48	< 0.0086	< 0.0073		< 0.027	< 0.023	< 0.039	< 0.054
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	< 0.035	0.018	< 0.16	< 0.15	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0083	< 0.033	< 0.032	< 0.011	< 0.0083	0.19		< 0.027	< 0.023	< 0.038	< 0.053
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.038 U	< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0092 U	< 0.0078 U		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.038 U	0.044 J	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	0.17	< 0.0092 U	0.056 J		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.038 U	0.05 J	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	0.32	< 0.0091 U	0.077 J		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.037 U	0.3	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	0.44	< 0.0088 U	0.18		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.036 U	< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0075 U		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.041 U	0.045 J	< 0.19 U	< 0.17 U	< 0.17 U	< 0.035 U	< 0.047 U	< 0.15 U		< 0.0099 U	< 0.039 U	< 0.038 U	0.1	< 0.01 U	0.097		< 0.032 U	< 0.027 U	< 0.045 U	< 0.063 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.036 U	0.11	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.19	< 0.0086 U	0.16		< 0.028 U	< 0.023 U	< 0.039 U	< 0.055 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.07 U	< 0.012 U	< 0.32 U	< 0.29 U	< 0.29 U	< 0.059 U	< 0.079 U	< 0.26 U		< 0.017 U	< 0.066 U	< 0.064 U	< 0.023 U	< 0.017 U	0.018 J		< 0.054 U	< 0.046 U	< 0.076 U	< 0.11 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.039 U	0.66	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.044 U	< 0.15 U		< 0.0093 U	< 0.037 U	< 0.036 U	4.2	< 0.0094 U	3.4		< 0.03 U	< 0.026 U	< 0.042 U	< 0.06 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.035 U	< 0.0062 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0085 U	< 0.0073 U		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.036 U	< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.033 U	0.026 J	< 0.0086 U	0.021 J		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	< 0.036 U	0.63	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.54	< 0.0086 U	0.66		< 0.028 U	< 0.023 U	< 0.039 U	< 0.055 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.036 U	0.037 J	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.062 J	< 0.0086 U	0.04 J		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	< 0.039 U	0.58	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.044 U	< 0.15 U		< 0.0094 U	< 0.037 U	< 0.036 U	0.74	< 0.0095 U	0.6		< 0.03 U	< 0.026 U	< 0.043 U	< 0.06 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 0.18 U	0.26 J	< 0.83 U	< 0.77 U	< 0.75 U	< 0.16 U	< 0.21 U	< 0.68 U		< 0.044 U	< 0.17 U	< 0.17 U	0.3 J	< 0.044 U	0.32 J		< 0.14 U	< 0.12 U	< 0.2 U	< 0.28 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.036 U	0.19	< 0.16 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.31	< 0.0087 U	0.38		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated																				
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0075 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated		0.2	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.033 U	1.1	< 0.0086 U	2		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-6-10 (7.5)DL	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated		0.26 J	< 0.83 U	< 0.76 U	< 0.75 U	< 0.15 U	< 0.2 U	< 0.68 U		< 0.044 U	< 0.17 U	< 0.17 U	7.7	< 0.044 U	11		< 0.14 U	< 0.12 U	< 0.2 U	< 0.28 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.035	< 0.0062	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0084	< 0.033	< 0.032	0.013	< 0.0085	0.013		< 0.027	< 0.023	< 0.038	< 0.054
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0083	< 0.033	< 0.032	< 0.011	< 0.0083	< 0.0071		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14	< 0.029	< 0.038	< 0.13		< 0.0081	< 0.032	< 0.031	< 0.011	< 0.0082	< 0.007		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14	< 0.029	< 0.038	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0082	< 0.007		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.036	0.18	< 0.16	< 0.15	< 0.15	< 0.031	< 0.04	< 0.13		< 0.0086	< 0.034	< 0.033	0.37	< 0.0087	0.75		< 0.028	< 0.024	< 0.039	< 0.055
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.037	< 0.0065	< 0.17	< 0.16	< 0.15	< 0.031	< 0.042	< 0.14		< 0.0089	< 0.035	< 0.034	0.034	< 0.0089	0.045		< 0.029	< 0.024	< 0.04	< 0.057
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.036	< 0.0064	< 0.17	< 0.15	< 0.15	< 0.031	< 0.041	< 0.13		< 0.0087	< 0.034	< 0.033	< 0.012	< 0.0087	< 0.0075		< 0.028	< 0.024	< 0.039	< 0.055
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084	< 0.0072		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.037	< 0.0065	< 0.17	< 0.16	< 0.15	< 0.031	< 0.042	< 0.14		< 0.0089	< 0.035	< 0.034	< 0.012	< 0.0089	< 0.0076		< 0.029	< 0.024	< 0.04	< 0.056
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0083	< 0.0071		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0083	< 0.0071		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.035	< 0.0062	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0085	< 0.033	< 0.032	< 0.011	< 0.0085	< 0.0073		< 0.027	< 0.023	< 0.039	< 0.054
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0083	< 0.033	< 0.032	< 0.011	< 0.0084	< 0.0072		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084	< 0.0072		< 0.027	< 0.023	< 0.038	< 0.053
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated		< 0.006 U	< 0.16 U	< 0.14 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0082 U	< 0.032 U	< 0.031 U	< 0.011 U	< 0.0083 U	< 0.0071 U		< 0.026 U	< 0.022 U	< 0.037 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated		0.23	< 0.16 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.52	< 0.0087 U	1		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0086 U	< 0.0074 U		< 0.028 U	< 0.023 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0075 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	< 0.012 U	< 0.0086 U	< 0.0073 U		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0075 U		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated			ND	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 UJ	< 0.0095 U	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0084 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0092 U	< 0.0073 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	10 - 12 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.024 U	< 0.026 U	< 0.049 U	< 0.028 U	< 0.023 U	< 0.028 U	< 0.029 U	< 0.031 U	< 0.024 U	< 0.031 U	< 0.02 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	12 - 14 ft	180-66622-2	Not Excavated			1.415	< 0.024 U	< 0.024 U	< 0.024 U	0.04 J	< 0.048 U	< 0.028 U	< 0.023 U	0.13	0.11	0.13	0.07	0.063 J	< 0.02 U	< 0.021 U	< 0.023 U	< 0.23 U	< 0.033 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.024 U	< 0.026 U	< 0.048 U	< 0.028 U	< 0.023 U	< 0.028 U	< 0.029 U	< 0.03 U	< 0.024 U	< 0.03 U	< 0.02 U	< 0.021 U	< 0.023 U	< 0.23 U	< 0.033 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.025 U	< 0.026 U	< 0.049 U	< 0.028 U	< 0.023 U	< 0.028 U	< 0.03 U	< 0.031 U	< 0.025 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	2 - 4 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.025 U	< 0.025 U	< 0.027 U	< 0.05 U	< 0.029 U	< 0.024 U	< 0.029 U	< 0.03 U	< 0.031 U	< 0.025 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.024 U	< 0.24 U	< 0.034 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	4 - 6 ft	180-66622-2	Not Excavated			0.995	< 0.025 U	< 0.025 U	< 0.025 U	0.033 J	< 0.051 U	< 0.029 U	< 0.024 U	0.09	0.079	0.099	0.036 J	0.059 J	< 0.021 U	< 0.022 U	< 0.024 U	< 0.25 U	< 0.035 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	6 - 8 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.024 U	< 0.026 U	< 0.049 U	< 0.028 U	< 0.023 U	< 0.028 U	< 0.029 U	< 0.031 U	< 0.025 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	8 - 10 ft	180-66622-2	Not Excavated			2.011	< 0.024 U	0.032 J	< 0.024 U	0.076	< 0.049 U	< 0.028 U	< 0.023 U	0.18	0.15	0.18	0.079	0.093	< 0.02 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated			ND	< 0.0071 U	< 0.0084 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0092 U	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0099 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated			ND	< 0.0075 U	< 0.0089 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.035 U	< 0.058 U	< 0.0098 U	< 0.0078 U	< 0.012 U	< 0.016 U	< 0.0078 U	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated			0.051	< 0.0076 U	< 0.009 U	< 0.032 U	< 0.0077 U	< 0.038 U	< 0.035 U	< 0.059 U	< 0.0099 U	< 0.0079 U	< 0.012 U	< 0.016 U	< 0.0078 U	< 0.026 U	< 0.011 U	< 0.0085 U	< 0.064 U	< 0.034 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.0091 U	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.035 U	< 0.032 U	< 0.053 UJ	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.023 U	< 0.0095 U	< 0.0077 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated			0.045	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0095 U	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.053 U	< 0.0089 U	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.023 U	< 0.0095 U	< 0.0077 U	< 0.057 U	< 0.031 U	< 0.049 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated			ND	< 0.0069 U	< 0.0082 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.054 UJ	< 0.009 U	< 0.0072 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.024 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U	< 0.049 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated			ND																		
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated			ND																		
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0095 U	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-5-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.0079 U	< 0.0094 U	< 0.034 U	< 0.008 U	< 0.04 U	< 0.037 U	< 0.062 U	< 0.01 U	< 0.0082 U	< 0.013 U	< 0.017 U	< 0.0082 U	< 0.027 U	< 0.011 U	< 0.0089 U	< 0.066 U	< 0.036 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated			ND																		
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0071 U	< 0.0085 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0093 U	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.0077 U	< 0.0092 U	< 0.033 U	< 0.0078 U	< 0.039 U	< 0.036 U	< 0.06 U	< 0.01 U	< 0.008 U	< 0.013 U	< 0.016 U	< 0.008 U	< 0.026 U	< 0.011 U	< 0.0087 U	< 0.065 U	< 0.035 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.0072 U	< 0.0085 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated			ND	< 0.007 U	< 0.0084 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 UJ	< 0.0092 U	< 0.0073 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated			0.126	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 UJ	< 0.0095 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.037 U	< 0.033 U	< 0.056 UJ	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0075 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0096 U	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.062 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.0074 U	< 0.0088 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.034 U	< 0.058 U	< 0.0097 U	< 0.0077 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.034 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.033 U	< 0.055 U	< 0.0091 U	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated			ND																		
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated			ND																		
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated			ND	< 0.0076 U	< 0.009 U	< 0.032 U	< 0.0077 U	< 0.038 U	< 0.035 U	< 0.059 U	< 0.0099 U	< 0.0079 U	< 0.012 U	< 0.016 U	< 0.0078 U	< 0.026 U	< 0.011 U	< 0.0085 U	< 0.064 U	< 0.034 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.0074 U	< 0.0088 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.034 U	< 0.058 U	< 0.0097 U	< 0.0077 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.034 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.0091 U	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0098 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated			ND																		
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated			ND																		
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated			1.341	< U	< U		< U				0.099 J	0.098 J	0.14 J	0.14 J	0.076 J						
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated			0.705	< 0.02 U	< 0.015 U	< 0.12 U	0.023 J	< 0.15 U	< 0.13 U	< 0.043 U	0.053 J	0.051 J	0.064 J	0.028 J	0.05 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	12 - 14 ft	180-140136-1	Not Excavated			4.48	0.056 J	0.054 J	< 0.13 U	0.16	< 0.16 U	< 0.14 U	< 0.046 U	0.37	0.33	0.4	0.15	0.29	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated			0.176	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	0.029 J	< 0.021 U	0.019 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated			4.803	0.077	0.031 J	< 0.13 U	0.19	< 0.16 U	< 0.14 U	< 0.047 U	0.38	0.34	0.39	0.14	0.28	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated			6.366	0.11	0.051 J	< 0.13 U	0.25	< 0.16 U	< 0.14 U	< 0.046 U	0.52	0.45	0.56	0.18	0.36	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated			6.274	0.11	0.037 J	< 0.13 U	0.3	< 0.16 U	< 0.13 U	< 0.044 U	0.47	0.4	0.48	0.16	0.32	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	12 - 14 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated			9.324	0.026 J	0.2	< 0.14 U	0.26	< 0.17 U	< 0.14 U	< 0.048 U	0.74	0.7	0.92	0.38	0.57	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated			0.038	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U	< 0.031 U	0.021 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated			0.857	< 0.02 U	< 0.015 U	< 0.13 U	0.018 J	< 0.15 U	< 0.13 U	< 0.044 U	0.076	0.076	0.1	0.042 J	0.054 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	12 - 14 ft	180-139185-1	Not Excavated			0.055	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated			0.177	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.031 J	< 0.03 U	0.025 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	0.38 J	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	< 0.009 U	< 0.0084 U	< 0.037 U	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0082 U	< 0.036 U	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	10 - 12 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	< 0.028 U	< 0.029 U	< 0.028 U	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.025 U	< 0.028 U	< 0.042 U	< 0.65 U	< 0.024 U	< 0.71 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	12 - 14 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	0.1	< 0.029 U	< 0.028 U	< 0.15 U	< 0.028 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.041 U	< 0.65 U	< 0.024 U	< 0.71 U
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	< 0.027 U	< 0.029 U	< 0.028 U	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.041 U	< 0.65 U	< 0.024 U	< 0.71 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.031 U	< 0.02 U	< 0.038 U	< 0.023 U	< 0.026 U	< 0.026 U	< 0.028 U	< 0.03 U	< 0.029 U	< 0.15 U	< 0.029 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.028 U	< 0.042 U	< 0.66 U	< 0.025 U	< 0.72 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	2 - 4 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.031 U	< 0.02 U	< 0.038 U	< 0.024 U	< 0.026 U	< 0.026 U	< 0.028 U	< 0.03 U	< 0.029 U	< 0.15 U	< 0.029 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.043 U	< 0.67 U	< 0.025 U	< 0.73 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	4 - 6 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.031 U	< 0.021 U	< 0.039 U	< 0.024 U	< 0.026 U	< 0.026 U	0.069 J	< 0.03 U	< 0.029 U	< 0.15 U	< 0.03 U	< 0.033 U	< 0.028 U	< 0.026 U	< 0.029 U	< 0.044 U	< 0.68 U	< 0.025 U	< 0.74 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	6 - 8 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.026 U	< 0.025 U	< 0.028 U	< 0.029 U	< 0.028 U	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.025 U	< 0.028 U	< 0.042 U	< 0.66 U	< 0.025 U	< 0.72 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	8 - 10 ft	180-66622-2	Not Excavated	< 0.17 U	0.042 J	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	0.14	< 0.029 U	< 0.028 U	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.042 U	< 0.65 U	< 0.024 U	< 0.71 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	< 0.29 U	< 0.0072 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0093 U	< 0.0087 U	< 0.038 U	< 0.041 U	< 0.0078 U	< 0.043 U	< 0.061 U	< 0.043 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	< 0.3 U	< 0.0073 U	< 0.032 U	< 0.036 U	< 0.0082 U	< 0.032 U	< 0.044 U	< 0.0094 U	< 0.0088 U	< 0.039 U	< 0.042 U	< 0.0079 U	< 0.043 U	< 0.062 U	< 0.043 U	< 0.049 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0086 U	< 0.0081 U	< 0.036 U	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.045 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U	< 0.038 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	< 0.009 U	< 0.0084 U	< 0.037 U	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0085 U	< 0.0079 U	< 0.035 U	< 0.038 U	< 0.0071 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0066 U	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	< 0.0085 U	< 0.008 U	< 0.035 U	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated																				
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated																				
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0083 U	< 0.037 U	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	< 0.0091 U	< 0.0085 U	< 0.037 U	< 0.04 U	< 0.0076 U	< 0.042 U	< 0.059 U	< 0.041 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	< 0.31 U	< 0.0076 U	< 0.033 U	< 0.038 U	< 0.0086 U	< 0.034 U	< 0.046 U	< 0.0098 U	< 0.0091 U	< 0.04 U	< 0.043 U	< 0.0082 U	< 0.045 U	< 0.064 U	< 0.045 U	< 0.051 U	< 0.043 U	< 0.17 U	< 0.042 U	< 0.49 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0083 U	< 0.037 U	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.45 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated																				
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	< 0.3 U	< 0.0074 U	< 0.032 U	< 0.037 U	< 0.0084 U	< 0.033 U	< 0.045 U	< 0.0095 U	< 0.0089 U	< 0.039 U	< 0.042 U	< 0.008 U	< 0.044 U	< 0.063 U	< 0.044 U	< 0.05 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.48 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.041 U	< 0.0089 U	< 0.0083 U	< 0.037 U	< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0081 U	< 0.036 U	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	0.065 J	< 0.0084 U	< 0.037 U	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0084 U	< 0.037 U	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.031 U	< 0.035 U	< 0.008 U	< 0.031 U	< 0.042 U	< 0.0091 U	< 0.0085 U	< 0.038 U	< 0.04 U	< 0.0077 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	< 0.038 U	< 0.041 U	< 0.0078 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0087 U	< 0.0081 U	< 0.036 U	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated																				
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated																				
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0083 U	< 0.037 U	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	< 0.3 U	< 0.0072 U	< 0.031 U	< 0.036 U	< 0.0082 U	< 0.032 U	< 0.044 U	< 0.0094 U	< 0.0087 U	< 0.039 U	< 0.042 U	< 0.0079 U	< 0.043 U	< 0.061 U	< 0.043 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.041 U	< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	< 0.038 U	< 0.041 U	< 0.0077 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0087 U	< 0.0081 U	< 0.036 U	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated																				
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated																				
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated								0.18 J	< U	< U										
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.052 J	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	12 - 14 ft	180-140136-1	Not Excavated	< 0.24 U	0.052 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.38	0.051 J	< 0.14 U	< 0.34 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated	< 0.24 U	0.063 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.37	0.065 J	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated	< 0.24 U	0.093	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.47	0.084	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated	< 0.23 U	0.11	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.45	0.08	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	12 - 14 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated	< 0.25 U	0.044 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.75	0.14	< 0.14 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.099	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	12 - 14 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U

							2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential								13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater								0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]														
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0081 U	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	< 0.0078 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0068 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0078 U	< 0.0097 U	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U	< 0.0075 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	10 - 12 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.053 U	< 0.028 U	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U	< 0.027 U	< 0.031 U	< 0.031 U	< 0.02 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	12 - 14 ft	180-66622-2	Not Excavated	< 0.046 U			< 0.053 U	0.3	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U	0.062 J	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated	< 0.046 U			< 0.053 U	< 0.028 U	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U	< 0.027 U	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.054 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.023 U	< 0.03 U	< 0.026 U	< 0.028 U	< 0.032 U	< 0.032 U	< 0.02 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	2 - 4 ft	180-66622-2	Not Excavated	< 0.048 U			< 0.055 U	< 0.029 U	< 0.026 U	< 0.029 U	< 0.023 U	< 0.031 U	< 0.026 U	< 0.028 U	< 0.032 U	< 0.032 U	< 0.02 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	4 - 6 ft	180-66622-2	Not Excavated	< 0.049 U			< 0.055 U	0.15	< 0.026 U	< 0.03 U	< 0.023 U	< 0.031 U	< 0.026 U	0.05 J	< 0.032 U	< 0.033 U	< 0.02 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	6 - 8 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.054 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.022 U	< 0.03 U	< 0.026 U	< 0.027 U	< 0.031 U	< 0.031 U	< 0.02 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	8 - 10 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.053 U	0.34	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U	0.083	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0097 U	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U	< 0.0076 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	< 0.031 U			< 0.045 U	< 0.0083 U	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U	< 0.008 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.007 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	< 0.032 U			< 0.045 U	0.02 J	< 0.01 U	< 0.0084 U	< 0.0088 U	< 0.043 U	< 0.028 U	< 0.0081 U	< 0.028 U	< 0.039 U	< 0.03 U	< 0.0071 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0065 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0094 U	< 0.0076 U	< 0.0079 U	< 0.038 U	< 0.026 U	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	< 0.031 U			< 0.044 U	0.017 J	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	< 0.0078 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0068 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0094 U	< 0.0076 U	< 0.008 U	< 0.038 U	< 0.026 U	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0077 U	< 0.0095 U	< 0.0076 U	< 0.008 U	< 0.039 U	< 0.026 U	< 0.0074 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated	< 0.097 U						< 0.059 U	< 0.046 U		< 0.052 U		< 0.065 U			
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated	< 0.25 U						< 0.15 U	< 0.12 U		< 0.14 U		< 0.17 U			
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0081 U	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	< 0.0078 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0068 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	< 0.033 U			< 0.047 U	< 0.0088 U	< 0.011 U	< 0.0087 U	< 0.0092 U	< 0.044 U	< 0.03 U	< 0.0085 U	< 0.029 U	< 0.04 U	< 0.031 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated	< 0.1 U						< 0.061 U	< 0.048 U		< 0.054 U		< 0.067 U			
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0097 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U	< 0.0076 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	< 0.032 U			< 0.046 U	< 0.0086 U	< 0.011 U	< 0.0085 U	< 0.009 U	< 0.043 U	< 0.029 U	< 0.0083 U	< 0.028 U	< 0.039 U	< 0.03 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0098 U	< 0.0079 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0078 U	< 0.0097 U	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.043 U	0.015 J	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.041 U	< 0.027 U	< 0.0078 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0068 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0068 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0082 U	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U	< 0.0079 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0069 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0083 U	< 0.01 U	< 0.0082 U	< 0.0086 U	< 0.042 U	< 0.028 U	< 0.008 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.0069 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.025 U	< 0.036 U	< 0.027 U	< 0.0066 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated	< 0.1 U						< 0.062 U	< 0.048 U		< 0.055 U		< 0.068 U	< 0.068 U		
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	< 0.052 U						< 0.032 U	< 0.025 U		< 0.028 U		< 0.035 U			
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	< 0.032 U			< 0.045 U	< 0.0084 U	< 0.01 U	< 0.0084 U	< 0.0088 U	< 0.042 U	< 0.028 U	< 0.0081 U	< 0.027 U	< 0.038 U	< 0.03 U	< 0.0071 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0083 U	< 0.01 U	< 0.0082 U	< 0.0086 U	< 0.042 U	< 0.028 U	< 0.008 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.0069 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U	< 0.0075 U	< 0.025 U	< 0.036 U	< 0.027 U	< 0.0065 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated	< 0.097 U						< 0.059 U	< 0.046 U		< 0.052 U		< 0.065 U			
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated	< 0.095 U						< 0.058 U	< 0.045 U		< 0.052 U		< 0.063 U			
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated					0.28 J	< U	< U				0.07 J	< U			
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.12	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	0.047 J	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	12 - 14 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	0.72	0.053 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	0.24	< 0.11 U	< 0.11 U	< 0.14 U	0.042 J
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.046 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	0.73	0.067 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	0.23	< 0.11 U	< 0.11 U	< 0.14 U	0.036 J
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	1	0.091	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	0.3	< 0.11 U	< 0.11 U	< 0.14 U	0.048 J
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	1	0.1	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	0.28	< 0.1 U	< 0.1 U	< 0.13 U	0.048 J
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	12 - 14 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated	< 0.23 U			< 0.12 U	1.5	0.058 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U	0.54	< 0.11 U	< 0.11 U	< 0.15 U	0.53
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	< 0.21 U			< 0.11 U	0.13	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	0.049 J	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	12 - 14 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.11 U	0.028 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	0.048 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U		< 0.029 U	< 0.024 U	< 0.041 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	10 - 12 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.67 U	< 0.03 U	< 0.048 U	< 0.031 U		< 0.025 U	< 0.028 U	< 0.034 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	12 - 14 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.66 U	0.19	< 0.047 U	0.22		< 0.025 U	< 0.028 U	< 0.033 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.66 U	< 0.029 U	< 0.047 U	< 0.031 U		< 0.025 U	< 0.028 U	< 0.033 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	14 - 16 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.12 U	< 0.1 U	< 0.13 U	< 0.027 U	< 0.026 U	< 0.38 U		< 0.024 U	< 0.056 U	< 0.68 U	< 0.03 U	< 0.048 U	< 0.032 U		< 0.026 U	< 0.029 U	< 0.034 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	2 - 4 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.028 U	< 0.026 U	< 0.38 U		< 0.025 U	< 0.057 U	< 0.68 U	< 0.03 U	< 0.049 U	< 0.032 U		< 0.026 U	< 0.029 U	< 0.034 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	4 - 6 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.13 U	< 0.11 U	< 0.13 U	< 0.028 U	< 0.027 U	< 0.39 U		< 0.025 U	< 0.058 U	< 0.7 U	0.13	< 0.05 U	0.2		< 0.026 U	< 0.029 U	< 0.035 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	6 - 8 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.12 U	< 0.1 U	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.056 U	< 0.67 U	< 0.03 U	< 0.048 U	< 0.032 U		< 0.025 U	< 0.028 U	< 0.034 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	8 - 10 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.67 U	0.31	< 0.048 U	0.38		< 0.025 U	< 0.028 U	< 0.034 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated		< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0092 U	< 0.0079 U		< 0.03 U	< 0.025 U	< 0.042 U	< 0.058 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated		< 0.0068 U	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	0.015 J	< 0.0093 U	0.016 J		< 0.03 U	< 0.025 U	< 0.042 U	< 0.059 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	< 0.012 U	< 0.0086 U	< 0.0073 U		< 0.027 U	< 0.023 U	< 0.039 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	0.012 J	< 0.009 U	0.016 J		< 0.029 U	< 0.024 U	< 0.04 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated		< 0.0062 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0085 U	< 0.0072 U		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated	< 0.065 U					< 0.056 U						< 1.4 U				< 0.07 U			< 0.07 U	< 0.064 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated	< 0.17 U					< 0.14 U						< 3.6 U				< 0.18 U			< 0.18 U	< 0.17 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated		< 0.0065 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.0089 U	< 0.0076 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated		< 0.0066 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U		< 0.029 U	< 0.024 U	< 0.041 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated		< 0.0071 U	< 0.18 U	< 0.17 U	< 0.17 U	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0096 U	< 0.038 U	< 0.037 U	< 0.013 U	< 0.0097 U	< 0.0083 U		< 0.031 U	< 0.026 U	< 0.044 U	< 0.061 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated		< 0.0065 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0076 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated	< 0.067 U					< 0.058 U						< 1.4 U				< 0.073 U			< 0.072 U	< 0.066 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0075 U		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated		< 0.0069 U	< 0.18 U	< 0.17 U	< 0.16 U	< 0.033 U	< 0.044 U	< 0.15 U		< 0.0094 U	< 0.037 U	< 0.036 U	< 0.013 U	< 0.0095 U	< 0.0081 U		< 0.03 U	< 0.026 U	< 0.043 U	< 0.06 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0075 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.031 U	< 0.042 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	0.035 J	< 0.0089 U	0.011 J		< 0.029 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated		< 0.0065 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.0089 U	< 0.0076 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated		< 0.0066 U	< 0.17 U	< 0.16 U	< 0.15 U	< 0.032 U	< 0.042 U	< 0.14 U		< 0.009 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U		< 0.029 U	< 0.025 U	< 0.041 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated		< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0091 U	< 0.0078 U		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0086 U	< 0.0074 U		< 0.028 U	< 0.023 U	< 0.039 U	< 0.055 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated						< 0.059 U						< 1.4 U				< 0.073 U			< 0.073 U	< 0.067 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	< 0.035 U					< 0.03 U						< 0.75 U				< 0.038 U			< 0.038 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0076 U		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated		< 0.0068 U	< 0.18 U	< 0.16 U	< 0.16 U	< 0.033 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	< 0.013 U	< 0.0093 U	< 0.008 U		< 0.03 U	< 0.025 U	< 0.042 U	< 0.059 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated		< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0091 U	< 0.0078 U		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0086 U	< 0.0074 U		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated	< 0.065 U					< 0.056 U						< 1.4 U				< 0.07 U			< 0.069 U	< 0.064 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated	< 0.064 U					< 0.055 U						< 1.4 U				< 0.069 U			< 0.068 U	< 0.063 U
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	< U	< U										< U	0.038 J	< U	0.22 J					
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated		0.021 J	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.099	< 0.1 U	0.097		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	12 - 14 ft	180-140136-1	Not Excavated		0.05 J	< 0.17 U	< 0.094 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.56	< 0.11 U	0.67		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.037 J	< 0.11 U	0.045 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated		0.044 J	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.71	< 0.11 U	0.79		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated		0.061 J	< 0.17 U	< 0.094 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.93	< 0.11 U	1		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated		0.064 J	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	1.1	< 0.11 U	0.96		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	12 - 14 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated		0.39	< 0.18 U	< 0.099 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.95	< 0.12 U	1.4		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.017 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.093	< 0.11 U	0.12		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	12 - 14 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.027 J		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.03 J	< 0.1 U	0.043 J		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (D	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100						
Restricted - Residential											100	100		100				1	1	1	3.9	100						
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																					
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated			1.126	< 0.02 U	0.066 J	< 0.13 U	0.024 J	< 0.15 U	< 0.13 U	< 0.044 U	0.095	0.11	0.17	0.061 J	0.092	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	12 - 14 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated			0.585	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.057 J	0.049 J	0.097	< 0.021 U	0.038 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated			9.95	0.022 J	0.17	< 0.14 U	0.39	< 0.17 U	< 0.14 U	< 0.047 U	0.91	0.73	0.87	0.32	0.51	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated			0.466	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.042 J	0.041 J	0.047 J	< 0.022 U	0.032 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated			0.556	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	0.059 J	0.04 J	0.056 J	0.02 J	0.048 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	12 - 14 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated			1.139	< 0.02 U	< 0.015 U	< 0.12 U	0.03 J	< 0.15 U	< 0.12 U	< 0.042 U	0.12	0.083	0.12	0.042 J	0.068	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated			0.402	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.045 J	0.038 J	0.036 J	0.026 J	0.038 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated			0.283	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.037 J	0.031 J	0.041 J	< 0.021 U	0.026 J	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated			0.335	< 0.4 U	< 0.4 U		< 0.4 U				0.041 J	0.042 J	0.044 J	0.043 J	< 0.4 U						
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated			0.712	< 0.38 U	0.045 J		0.042 J				0.1 J	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U						
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated			34.77	< 1.1 U	1.4		1.4				3.3	3.4	2.6	2.8	1.9						
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated			0.867	< 0.39 U	< 0.39 U		< 0.39 U				0.05 J	< 0.39 U	0.047 J	< 0.39 U	< 0.39 U						
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated			ND	< 0.38 U	< 0.38 U		< 0.38 U				< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U						
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated			4.49	< 3.9 U	< 3.9 U		< 3.9 U				< 3.9 U	< 3.9 U	< 3.9 U	< 3.9 U	< 3.9 U						

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Caprolactam	Carbazole	4-Chloroaniline (p-Chloroani	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1	0.33	7										
Restricted - Residential															3.9	0.33	59										
Protection of Groundwater															1	1000	210										
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.13	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	12 - 14 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.066 J	< 0.046 U	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated	< 0.25 U	0.037 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.74	0.15	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.05 J	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.059 J	< 0.043 U	< 0.12 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	12 - 14 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.11	< 0.043 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.048 J	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated								0.052 J	< 0.4 U	< 0.4 U										
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated								0.23 J	< 0.38 U	< 0.38 U										
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated								3.6	0.68 J	< 1.1 U										
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated								0.09 J	< 0.39 U	< 0.39 U										
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated								< 0.38 U	< 0.38 U	< 0.38 U										
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated								0.89 J	< 3.9 U	< 3.9 U										

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted									0.1	0.1	0.1	100	30	0.33				0.5	0.33			
Restricted - Residential									13	13	13	100	100	1.2				0.5	100			
Protection of Groundwater									0.1	0.1	0.1	1000	386	3.2				8.2	0.33			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated	< 0.23 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.1 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U	< 0.033 U	< 0.096 U	< 0.098 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	0.13	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	0.076	< 0.1 U	< 0.1 U	< 0.13 U	0.02 J
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	12 - 14 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.035 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.092	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.1 U	< 0.13 U	0.034 J
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated	< 0.23 U			< 0.12 U	1.9	0.091	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	0.45	< 0.11 U	< 0.11 U	< 0.14 U	0.032 J
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	0.086	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	0.027 J
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	0.081	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	0.035 J	< 0.097 U	< 0.099 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	12 - 14 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	0.18	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	0.066 J	< 0.097 U	< 0.1 U	< 0.13 U	0.018 J
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.06 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	0.049 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated					0.053 J	< 0.4 U	< 0.4 U				< 0.4 U	< 0.4 U			
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated					0.12 J	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U			
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated					5.6	< 1.1 U	< 1.1 U				1.9	< 1.1 U			
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated					0.083 J	< 0.39 U	< 0.39 U				< 0.39 U	< 0.39 U			
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated					< 0.38 U	< 0.38 U	< 0.38 U				< 0.38 U	< 0.38 U			
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated					< 3.9 U	< 3.9 U	< 3.9 U				< 3.9 U	< 3.9 U			

DRAFT

TABLE 5-6C
Subsurface Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.33	12										0.8	100	0.33	100					
Restricted - Residential								100	100										6.7	100	100	100					
Protection of Groundwater								0.33	12										0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated		< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated		0.028 J	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.04 J	< 0.11 U	0.17		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	12 - 14 ft	180-140136-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated		0.037 J	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.058 J	< 0.11 U	0.091		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated		0.067 J	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.1	< 0.11 U	1.7		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated		0.03 J	< 0.17 U	< 0.094 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.062 J	< 0.11 U	0.076		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.069	< 0.1 U	0.089		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	12 - 14 ft	180-140136-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.14	< 0.1 U	0.18		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.048 J	< 0.11 U	0.063 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.044 J	< 0.1 U	0.055 J		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.086 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	< 0.4 U	< 0.4 U										< 2 U	< 0.4 U	< 0.4 U	0.06 J					
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	< 0.38 U	< 0.38 U										< 2 U	0.1 J	< 0.38 U	0.12 J					
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	< 1.1 U	0.37 J										< 5.8 U	1.5	< 1.1 U	4.8					
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	< 0.39 U	0.44										< 2 U	0.12 J	< 0.39 U	0.058 J					
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	< 0.38 U	< 0.38 U										< 2 U	< 0.38 U	< 0.38 U	< 0.38 U					
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	< 3.9 U	< 3.9 U										< 20 U	< 3.9 U	< 3.9 U	3.6 J					

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	0.0060 J	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 UT	< 0.0025 U	< 0.0033 UJ
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	0.025	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 UJ	< 0.0037 U	< 0.0019 U	< 0.0012 U	< 0.0023 U	< 0.0027 UJ	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 UT	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.0039 UJ	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UJ	< 0.0039 U	< 0.0020 UT	< 0.0013 U	< 0.0024 U	< 0.0029 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.0039 UJ	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UJ	< 0.0040 U	< 0.0020 UT	< 0.0013 U	< 0.0025 U	< 0.0029 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UJ	< 0.0041 U	< 0.0021 UT	< 0.0013 U	< 0.0026 U	< 0.0030 UJ	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT	< 0.0013 U	< 0.0025 U	< 0.0030 UJ	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.0036 UJ	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 UJ	< 0.0037 U	< 0.0019 UT	< 0.0012 U	< 0.0023 U	< 0.0027 UJ	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT	< 0.0013 U	< 0.0026 U	< 0.0030 UJ	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT	< 0.0013 U	< 0.0025 U	< 0.0030 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.01 U	< 0.0032 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 UT	< 0.0033 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0044 U	< 0.0037 U	< 0.0036 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 f	1801782961	Not Excavated	0.03	< 0.0034 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 UT	< 0.0047 U	< 0.0024 U	< 0.0034 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0046 U	< 0.0039 U	< 0.0038 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	0.019 J	< 0.0029 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U	< 0.0030 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0040 U	< 0.0034 U	< 0.0032 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	0.016 J	< 0.0032 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0033 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0044 U	< 0.0037 U	< 0.0036 U
Northern Athletic Field	SSHS-B10	B10 10 May 00 2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	< 0.024 U	< 0.006 U						< 0.006 U	< 0.006 U			< 0.006 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.0049 U	< 0.00067 U	< 0.00068 U	< 0.00055 U	< 0.00044 U	< 0.00073 U	< 0.0005 U	< 0.00044 U	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.01 U	< 0.0014 U	< 0.0014 U	< 0.0012 U	< 0.00092 U	< 0.0015 U	< 0.0011 U	< 0.00093 U	< 0.0016 U	< 0.0015 U	< 0.0032 U	< 0.0012 U	< 0.0018 U	< 0.00077 U	< 0.0016 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.0073 U	< 0.00098 U	< 0.001 U	< 0.00082 U	< 0.00064 U	< 0.0011 U	< 0.00074 U	< 0.00065 U	< 0.0011 U	< 0.001 U	< 0.0023 U	< 0.00085 U	< 0.0012 U	< 0.00054 U	< 0.0011 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.011 U	< 0.0014 U	< 0.0014 U	< 0.0012 U	< 0.00093 U	< 0.0016 U	< 0.0011 U	< 0.00094 U	< 0.0016 U	< 0.0015 U	< 0.0033 U	< 0.0012 U	< 0.0018 U	< 0.00078 U	< 0.0016 U
Northern Athletic Field	SSHS-B14	B14 10 May 00 5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	< 0.022 U	< 0.0055 U						< 0.0055 U	< 0.0055 U			0.0012 J			
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	< 0.023 U	< 0.0056 U						< 0.0058 U	< 0.0058 U			< 0.0058 U			
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	0.018 J	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	0.0091 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	0.0084 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	0.02 J	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U,*
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	0.008 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	854.70	12 - 14 ft	180-80251-1	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0021 U	< 0.0023 U	< 0.004 U	< 0.0027 U	< 0.0029 U	< 0.0014 U	< 0.0021 U	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	0.011 J	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	0.0069 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	0.0086 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	0.013 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	0.015 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	0.0055 J	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	0.0056 J	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	0.018 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	0.0064 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	0.012 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	0.016 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	0.007 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	0.089	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	0.016 J	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	0.028	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	0.11	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	0.011 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	0.005 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	0.025	0.0021 J	< 0.00041 U	< 0.00053 U	< 0.00028 U	< 0.0012 U	0.0013 J	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00078 U	< 0.00051 U	< 0.00039 U	0.0042 J	< 0.00053 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	855.05	12 - 14 ft	180-80105-2	Not Excavated	0.021	0.0036 J	< 0.00051 U	< 0.00066 U	< 0.00035 U	< 0.0015 U	0.0066	< 0.00073 U	< 0.00045 U	< 0.00041 U	< 0.00098 U	< 0.00064 U	< 0.00049 U	0.016	< 0.00067 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	< 0.004 U	< 0.0025 U	< 0.0024 U	< 0.003 U	< 0.0033 U	< 0.0057 U	< 0.0038 U	< 0.0042 U	< 0.002 U	< 0.003 U	< 0.0033 U	< 0.0027 U	< 0.0049 U	< 0.0015 U	< 0.0039 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	0.014 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	0.01 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	0.024 J,B	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	0.0055 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	0.012 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	0.015 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U,*
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	0.02	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	0.044	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	0.018 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U,*
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	0.0068 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	0.03	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U,*
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	0.055	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U,*
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U,*

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**	**1,1-Dichloroethene**	**1,2-Dichloroethene**	**cis-1,2-Dichloroethene**	**trans-1,2-Dichloroethene**	**1,2-Dichloropropane**	**cis-1,3-Dichloropropene**	**trans-1,3-Dichloropropene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.0046 U	< 0.0014 UJ	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 UT	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0030 UT	< 0.0015 UT	< 0.0016 U	< 0.0014 U	< 0.0022 UT	< 0.0040 UT	< 0.0015 UT	< 0.0017 UT	< 0.0013 U	< 0.0022 U	< 0.0022 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0014 U	< 0.0022 UT	< 0.0041 UT	< 0.0015 UT	< 0.0017 UT	< 0.0013 U	< 0.0022 U	< 0.0022 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U	< 0.0023 UT	< 0.0042 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U	< 0.0023 UT	< 0.0042 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 UT	< 0.0016 U	< 0.0029 UT	< 0.0014 UT	< 0.0015 U	< 0.0013 U	< 0.0021 UT	< 0.0038 UT	< 0.0014 UT	< 0.0016 UT	< 0.0012 U	< 0.0021 U	< 0.0021 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U	< 0.0023 UT	< 0.0042 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U	< 0.0023 UT	< 0.0041 UT	< 0.0015 UT	< 0.0018 UT	< 0.0013 U	< 0.0022 U	< 0.0023 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.0050 U	< 0.0029 U	< 0.0045 UT	< 0.0032 U	< 0.0034 U	< 0.0031 U	< 0.0028 U	< 0.0033 U	< 0.0043 U	< 0.0045 U	< 0.0028 U	< 0.0034 U	< 0.0027 U	< 0.0024 U	< 0.0025 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 f	1801782961	Not Excavated	< 0.0053 U	< 0.0030 U	< 0.0047 U	< 0.0033 U	< 0.0036 U	< 0.0032 U	< 0.0030 U	< 0.0035 U	< 0.0045 U	< 0.0048 U	< 0.0029 U	< 0.0036 U	< 0.0028 U	< 0.0026 U	< 0.0026 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.0045 U	< 0.0026 U	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0026 U	< 0.0030 U	< 0.0039 U	< 0.0041 U	< 0.0025 U	< 0.0031 U	< 0.0024 U	< 0.0022 U	< 0.0023 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.0050 U	< 0.0029 U	< 0.0045 U	< 0.0031 U	< 0.0034 U	< 0.0031 U	< 0.0028 U	< 0.0033 U	< 0.0043 U	< 0.0045 U	< 0.0028 U	< 0.0034 U	< 0.0027 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B10	B10 10 May 00 2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	0.0014 J			< 0.4 U	< 0.4 U	< 0.4 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.006 U	< 0.006 U			
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.0006 U	< 0.00084 U		< 0.00069 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0014 U	< 0.0017 U	< 0.0014 U	< 0.0013 U	< 0.0012 U	< 0.0013 U	< 0.0018 U		< 0.0015 U	< 0.0012 U	< 0.0011 U	< 0.0014 U	< 0.0012 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.00098 U	< 0.0013 U	< 0.00097 U	< 0.0012 U	< 0.00095 U	< 0.00093 U	< 0.00084 U	< 0.00089 U	< 0.0012 U		< 0.001 U	< 0.00087 U	< 0.00079 U	< 0.00099 U	< 0.00087 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0014 U	< 0.0017 U	< 0.0014 U	< 0.0013 U	< 0.0012 U	< 0.0013 U	< 0.0018 U		< 0.0015 U	< 0.0013 U	< 0.0011 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	SSHS-B14	B14 10 May 00 5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	< 0.0055 U			< 0.36 U	< 0.36 U	< 0.36 U	< 0.0055 U	< 0.0055 U	< 0.0055 U		< 0.0055 U	< 0.0055 U			
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	< 0.0058 U			< 0.39 U	< 0.39 U	< 0.39 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U			
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	0.0027 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 0.0026 U	< 0.003 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	< 0.0025 U	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	854.70	12 - 14 ft	180-80251-1	Not Excavated	< 0.0021 U	< 0.0024 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0009 U	< 0.0016 U	< 0.0013 U	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0022 U	< 0.0022 U	< 0.0014 U	< 0.0015 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	< 0.0028 U	< 0.0033 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	0.0026 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	0.0028 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	0.0028 J	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0034 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	0.0024 J	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	0.0024 J	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	0.0026 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	0.0012 J	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	< 0.0028 U	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	< 0.0019 U	< 0.00035 U	< 0.00036 U	< 0.00039 U	< 0.00064 U	< 0.00041 U	< 0.00057 U	< 0.00034 U	< 0.0007 U	< 0.00086 U	< 0.00044 U	< 0.00053 U	< 0.00042 U	< 0.00025 U	< 0.00031 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	855.05	12 - 14 ft	180-80105-2	Not Excavated	< 0.0024 U	< 0.00043 U	< 0.00045 U	< 0.00049 U	< 0.0008 U	< 0.00051 U	< 0.00071 U	< 0.00042 U	< 0.00088 U	< 0.0011 U	< 0.00055 U	< 0.00067 U	< 0.00053 U	< 0.00032 U	< 0.00038 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	< 0.003 U	< 0.0034 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0013 U	< 0.0023 U	< 0.0018 U	< 0.0036 U	< 0.005 U	< 0.002 U	< 0.0032 U	< 0.0031 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0038 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	0.0025 J	< 0.0029 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	0.0026 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	0.003 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	< 0.0028 U	< 0.0033 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.0022 U	< 0.0025 U	< 0.0027 U	< 0.0037 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	< 0.0027 U	< 0.0031 U	< 0.0034 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	< 0.0029 U	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.002 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	< 0.0029 U	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 UJ	< 0.0015 U	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U	< 0.0014 UJ	< 0.0019 UT	< 0.0013 U	< 0.0026 U	< 0.0024 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 UJ	< 0.0022 UT	< 0.0016 U	< 0.0030 U	< 0.0028 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.0018 UT	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0073 U	< 0.0024 UT	< 0.0025 UJ	< 0.0018 UJ	< 0.0015 UT	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.0018 UT	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0073 U	< 0.0024 UT	< 0.0025 UJ	< 0.0018 UJ	< 0.0015 U	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.0019 UT	< 0.0021 U	< 0.0016 UJ	< 0.0027 UT	< 0.0076 U	< 0.0025 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.0019 UT	< 0.0021 U	< 0.0016 UJ	< 0.0027 UT	< 0.0076 U	< 0.0025 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.0019 U	< 0.0015 UJ	< 0.0024 UT	< 0.0069 U	< 0.0023 UT	< 0.0024 UJ	< 0.0017 UJ	< 0.0014 U	< 0.0014 U	< 0.0014 UJ	< 0.0019 UT	< 0.0013 U	< 0.0026 U	< 0.0024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.0019 UT	< 0.0021 U	< 0.0016 UJ	< 0.0027 UT	< 0.0076 U	< 0.0025 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.0019 UT	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0075 U	< 0.0024 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.0042 U	< 0.0052 U	< 0.0046 U	< 0.0042 U	< 0.0081 U	< 0.0039 U	< 0.011 U	< 0.0032 U	< 0.0032 U	< 0.0037 U	< 0.0042 U	< 0.0042 U	< 0.0042 U	< 0.0030 U	< 0.0028 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 f	1801782961	Not Excavated	< 0.0044 U	< 0.0054 U	< 0.0049 U	< 0.0044 U	< 0.0086 U	< 0.0041 U	< 0.011 U	< 0.0034 U	< 0.0034 U	< 0.0039 U	< 0.0044 U	< 0.0044 U	< 0.0044 U	< 0.0032 U	< 0.0030 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.0038 U	< 0.0047 U	< 0.0042 U	< 0.0038 U	< 0.0074 U	< 0.0035 U	< 0.0098 U	< 0.0029 U	< 0.0029 U	< 0.0033 U	< 0.0038 U	< 0.0038 U	< 0.0038 U	< 0.0028 U	< 0.0025 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.0042 U	< 0.0051 U	< 0.0046 U	< 0.0042 U	< 0.0081 U	< 0.0039 U	< 0.011 U	< 0.0032 U	< 0.0032 U	< 0.0037 U	< 0.0042 U	< 0.0042 U	< 0.0042 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B10	B10 10 May 00 2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	< 0.006 U						< 0.012 U					0.01	< 0.006 U		
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.00063 U	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00071 U	< 0.00087 U	< 0.00064 U	< 0.00074 U	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.0013 U	< 0.0022 U	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0016 U	< 0.0015 U	< 0.0015 U	< 0.0014 U	< 0.0015 U	< 0.0018 U	< 0.0018 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.00093 U	< 0.0016 U	< 0.001 U	< 0.00099 U	< 0.0013 U	< 0.0011 U	< 0.0013 U	< 0.00095 U	< 0.0011 U	< 0.001 U	< 0.001 U	< 0.00099 U	< 0.0011 U	< 0.0012 U	< 0.0013 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0015 U	< 0.0014 U	< 0.0019 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0016 U	< 0.0015 U	< 0.0015 U	< 0.0014 U	< 0.0015 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B14	B14 10 May 00 5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	< 0.0055 U						< 0.011 U					0.0035 J	< 0.0055 U		
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	< 0.0058 U						< 0.012 U					0.012	< 0.0058 U		
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	854.70	12 - 14 ft	180-80251-1	Not Excavated	< 0.0019 U	< 0.0017 U	< 0.0037 U	< 0.002 U	< 0.0052 U	< 0.0019 U	< 0.0026 U	< 0.0016 U	< 0.0033 U	< 0.0012 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	0.0032 J	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	0.004 J	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	0.00066 J	< 0.00068 U	< 0.00072 U	< 0.00056 U	< 0.0033 U	0.0064 J	0.0033 J	< 0.00092 U	< 0.00038 U	< 0.00049 U	< 0.00037 U	< 0.00038 U	0.0071	< 0.00039 U	< 0.00052 U
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	855.05	12 - 14 ft	180-80105-2	Not Excavated	0.00077 J	< 0.00085 U	< 0.0009 U	< 0.0007 U	< 0.0041 U	0.026	< 0.00084 U	< 0.0011 U	< 0.00048 U	< 0.00061 U	< 0.00047 U	< 0.00048 U	0.007	< 0.00049 U	< 0.00065 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	< 0.0027 U	< 0.0024 U	< 0.0053 U	< 0.0029 U	< 0.0074 U	< 0.0026 U	< 0.0037 U	< 0.0023 U	< 0.0046 U	< 0.0017 U	< 0.0038 U	< 0.0025 U	< 0.0021 U	< 0.0026 U	< 0.002 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.002 U	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0027 U	< 0.0017 U	< 0.0034 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.0021 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	10 - 12 ft	1801508221	Not Excavated	< 0.0017 U	< 0.0010 UJ	0.0020 J	< 0.0043 UT	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0074 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	12 - 14 ft	1801508221	Not Excavated	< 0.0016 U	< 0.00093 UJ	< 0.0015 UT	< 0.0039 UJ	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	14 - 16 ft	1801519451	Not Excavated	< 0.0018 U	< 0.0011 UJ	< 0.0017 UT	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	2 - 4 ft	1801518942	Not Excavated	< 0.0016 UT	< 0.00098 UJ	< 0.0016 UT	< 0.0041 UJ	< 0.0036 UJ	< 0.0018 UT	< 0.0020 UT	< 0.0071 UT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	4 - 6 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.00098 U	< 0.0016 UT	< 0.0041 U	< 0.0036 U	< 0.0018 UT	< 0.0020 UT	< 0.0072 UT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	6 - 8 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.0010 U	< 0.0016 UT	< 0.0043 U	< 0.0037 U	< 0.0018 UT	< 0.0021 UT	< 0.0074 UT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	8 - 10 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.0010 U	< 0.0016 UT	< 0.0043 U	< 0.0037 U	< 0.0018 UT	< 0.0021 UT	< 0.0074 UT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	10 - 12 ft	1801518942	Not Excavated	< 0.0016 UT	< 0.00093 U	< 0.0015 UT	< 0.0039 U	< 0.0034 U	< 0.0017 UT	< 0.0019 UT	< 0.0067 UT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	12 - 14 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.0010 U	< 0.0016 UT	< 0.0043 U	< 0.0037 U	< 0.0018 UT	< 0.0021 UT	< 0.0074 UT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	14 - 16 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.0010 U	< 0.0016 UT	< 0.0042 U	< 0.0036 U	< 0.0018 UT	< 0.0020 UT	< 0.0073 UT
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	6.65-8.65 ft	1801782961	Not Excavated	< 0.0018 UT	< 0.0029 U	< 0.0030 U	< 0.0046 U	< 0.0040 UT	< 0.0043 U	< 0.0038 U	< 0.0080 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	10.65-12.65 ft	1801782961	Not Excavated	< 0.0020 U	< 0.0031 U	< 0.0032 U	< 0.0048 U	< 0.0042 U	< 0.0046 U	< 0.0040 U	< 0.0084 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0042 U	< 0.0036 U	< 0.0039 U	< 0.0035 U	< 0.0072 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	6.76-8.76 ft	1801783741	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0030 U	< 0.0046 U	< 0.0040 U	< 0.0043 U	< 0.0038 U	< 0.0080 U
Northern Athletic Field	SSHS-B10	B10_10 May 00_2-3	5/10/2000	856.23	2 - 3 ft	NA	Excavated	< 0.006 U		< 0.0022 U		< 0.006 U	< 0.006 U	< 0.006 U	
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	12 - 15.5 ft	180-35818-2	Not Excavated	< 0.00048 U	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.001 U	< 0.0017 U	0.0033 J	< 0.0019 U	< 0.00098 U	< 0.0031 U	< 0.0016 U	
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	3 - 6 ft	180-35818-2	Not Excavated	< 0.00071 U	< 0.0012 U	0.0034 J	< 0.0013 U	< 0.00068 U	< 0.0021 U	< 0.0011 U	
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	8 - 10 ft	180-35818-2	Not Excavated	< 0.001 U	< 0.0017 U	0.0087 J	< 0.0019 U	< 0.00099 U	< 0.0031 U	< 0.0016 U	
Northern Athletic Field	SSHS-B14	B14_10 May 00_5-6	5/10/2000	857.03	5 - 6 ft	NA	Excavated	< 0.0055 U		< 0.0055 U		< 0.0055 U	< 0.0055 U	< 0.0055 U	
Football Field	SSHS-B15	B23454	5/10/2000	856.90	4 - 5 ft	NA	Excavated	< 0.0058 U		< 0.0058 U		< 0.0058 U	< 0.0058 U	< 0.0058 U	
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	12 - 14 ft	180-80225-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	12 - 14 ft	180-80225-3	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	12 - 14 ft	180-80227-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-10-12	7/26/2018	855.22	10 - 12 ft	180-80227-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-8-10	7/26/2018	855.22	8 - 10 ft	180-80227-1	Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0025 U	< 0.0045 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	12 - 14 ft	180-80227-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	12 - 14 ft	180-80227-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	12 - 14 ft	180-80252-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	12 - 14 ft	180-80251-2	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2033	SSHS-B2033-SUB-12-14	7/27/2018	854.70	12 - 14 ft	180-80251-1	Not Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0038 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	12 - 14 ft	180-80225-2	Not Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-1	Not Excavated	< 0.0027 U	< 0.0026 U	0.0043 J	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-12-14	7/25/2018	855.00	12 - 14 ft	180-80157-1	Excavated	< 0.0025 U	< 0.0024 U	0.0062	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2053	SSHS-B2053-SUB-4-6	7/25/2018	855.00	4 - 6 ft	180-80157-1	Excavated	< 0.0027 U	< 0.0025 U	0.003 J	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	12 - 14 ft	180-80157-3	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	12 - 14 ft	180-80251-2	Not Excavated	< 0.0026 U	< 0.0025 U	0.024	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	12 - 14 ft	180-80154-2	Not Excavated	< 0.0026 U	< 0.0025 U	0.0047 J	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	12 - 14 ft	180-80157-3	Not Excavated	< 0.0029 U	< 0.0027 U	0.0045 J	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	12 - 14 ft	180-80157-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	12 - 14 ft	180-80251-3	Not Excavated	< 0.0026 U	< 0.0025 U	0.0059	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	12 - 14 ft	180-80154-1	Not Excavated	< 0.0029 U	< 0.0028 U	0.011	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	12 - 14 ft	180-80154-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	12 - 14 ft	180-80154-1	Not Excavated	< 0.0025 U	< 0.0024 U	0.0042 J	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	12 - 14 ft	180-80154-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0048 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	12 - 14 ft	180-80154-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	12 - 14 ft	180-80157-1	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	12 - 14 ft	180-80157-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	12 - 14 ft	180-80154-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	12 - 14 ft	180-80106-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	12 - 14 ft	180-80106-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	12 - 14 ft	180-80106-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	12 - 14 ft	180-80105-3	Not Excavated	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	12 - 14 ft	180-80105-3	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	12 - 14 ft	180-80225-1	Not Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	12 - 14 ft	180-80225-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	12 - 14 ft	180-80105-1	Not Excavated	< 0.00035 U	< 0.00057 U	< 0.0004 U	< 0.00087 U	< 0.00076 U	0.0066 J	0.0017 J	0.0083 J
Football Field	SSHS-B2198	SSHS-B2198-SUB-12-14	7/24/2018	855.05	12 - 14 ft	180-80105-2	Not Excavated	< 0.00043 U	< 0.00071 U	< 0.0005 U	< 0.0011 U	< 0.00094 U	0.0063 J	0.0024 J	0.0087 J
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	12 - 14 ft	180-80225-2	Not Excavated	< 0.0032 U	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0046 U	< 0.0024 U	< 0.0031 U	< 0.0054 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	12 - 14 ft	180-80227-3	Not Excavated	< 0.0024 U	< 0.0023 U	0.0043 J	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	12 - 14 ft	180-80227-2	Not Excavated	< 0.0024 U	< 0.0023 U	0.002 J	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	2 - 4 ft	180-90380-1	Not Excavated	< 0.003 U	< 0.0029 U	0.0051 J	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	12 - 14 ft	180-80154-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	12 - 14 ft	180-80251-3	Not Excavated	< 0.0028 U	< 0.0027 U	0.0019 J	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	12 - 14 ft	180-80106-1	Not Excavated	< 0.0026 U	< 0.0025 U	0.0024 J	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-8-10	7/26/2018	856.38	8 - 10 ft	180-80227-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	10 - 12 ft	180-80227-2	Not Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	12 - 14 ft	180-80227-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	10 - 12 ft	180-80227-3	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-2-4	7/26/2018	856.56	2 - 4 ft	180-80227-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-4-6	7/26/2018	856.56	4 - 6 ft	180-80227-1	Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-6-8	7/26/2018	856.56	6 - 8 ft	180-80227-1	Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	12 - 14 ft	180-80227-1	Not Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0052 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	10 - 12 ft	180-80227-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^{1} (ft amsl)	Sample depth at time of sampling^{5} (bgs)	Lab Report	Excavation Status^{7}															
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U,*
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	0.057	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	0.026	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	0.0051 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	0.014 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	0.043	< 0.00045 U	< 0.00041 U	< 0.00052 U	< 0.00028 U	< 0.0012 U	0.0026 J	< 0.00058 U	< 0.00035 U	< 0.00033 U	< 0.00078 U	0.00097 J	< 0.00039 U	< 0.00052 U	< 0.00053 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	0.0099 J	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	0.015 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	855.51	12 - 14 ft	180-80091-3	Excavated	0.013 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0022 U	< 0.0041 U	0.0017 J	< 0.0033 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	0.082	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	855.46	12 - 14 ft	180-80091-4	Not Excavated	0.011 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	0.036	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	0.07	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	0.09	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	0.0055 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/15/2019	855.13	4 - 6 ft	180-90165-1	Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 UJ	< 0.004 U	< 0.0013 UJ	< 0.0032 U
Football Field	SSHS-B2621	PS-FD-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 UJ	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 UJ	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	0.017 U	< 0.0017 U	< 0.0016 U	< 0.002 U	< 0.0022 U	< 0.0038 UJ	< 0.0025 U	< 0.0028 U	< 0.0013 U	< 0.002 U	< 0.0022 U	< 0.0018 U	< 0.0033 UJ	< 0.001 U	< 0.0026 U
Football Field	SSHS-B2686	PS-FD-9	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	< 0.0029 UJ	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0042 UJ	< 0.0028 U	< 0.0031 U	< 0.0015 U	< 0.0022 U	< 0.0024 U	< 0.002 U	< 0.0036 UJ	< 0.0011 U	< 0.0029 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	0.031 J	< 0.0017 U	< 0.0017 U	< 0.0021 U	< 0.0023 U	< 0.004 UJ	< 0.0027 U	< 0.003 U	< 0.0014 U	< 0.0021 U	< 0.0023 U	< 0.0019 U	< 0.0034 UJ	< 0.0011 U	< 0.0027 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/15/2019	854.80	14 - 16 ft	180-90165-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 UJ	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.0044 U	< 0.0028 U	< 0.0027 U	< 0.0033 U	< 0.0037 U	< 0.0063 U	< 0.0042 U	< 0.0047 U	< 0.0022 U	< 0.0034 U	< 0.0036 U	< 0.003 U	< 0.0054 U	< 0.0017 UJ	< 0.0043 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0035 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	0.0092 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	0.034 BJ	< 0.0026 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0059 U	< 0.0039 U	< 0.0043 U	< 0.0021 U	< 0.0031 U	< 0.0034 U	< 0.0028 U	< 0.0050 U	< 0.0016 U	< 0.0040 UT
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	0.045 B	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 UT
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.0036 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 UJ
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B3	B3 12 May 00 4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated	< 0.025 U	< 0.0064 U						< 0.0064 U	< 0.0064 U			0.006 J			
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0021 U	< 0.0023 U	< 0.004 U	< 0.0027 U	< 0.003 U	< 0.0014 U	< 0.0021 U	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	0.0081 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.002 UJ	< 0.0022 UJ	< 0.0038 U	< 0.0026 U	< 0.0028 U	< 0.0013 U	< 0.002 UJ	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.001 U	< 0.0026 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	< 0.28 U	< 0.024 U	< 0.028 U	< 0.019 U	< 0.24 U	< 0.033 U	< 0.028 U	< 0.094 U	< 0.024 U	< 0.094 U	< 0.047 U	< 0.028 U	< 0.028 U	< 0.024 U	< 0.047 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0021 UJ	< 0.0023 UJ	< 0.004 U	< 0.0027 U	< 0.003 U	< 0.0014 U	< 0.0021 UJ	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 UJ
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	0.0037 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	0.0041 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	< 0.0019 U	< 0.00035 U	< 0.00035 U	< 0.00039 U	< 0.00063 U	< 0.00041 U	< 0.00057 U	< 0.00034 U	< 0.0007 U	< 0.00085 U	< 0.00044 U	< 0.00053 U	< 0.00042 U	< 0.00025 U	< 0.0003 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	< 0.0025 U	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	855.51	12 - 14 ft	180-80091-3	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	0.0025 J	< 0.0029 U	< 0.0031 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	855.46	12 - 14 ft	180-80091-4	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	0.0037 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/15/2019	855.13	4 - 6 ft	180-90165-1	Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 UJ	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2621	PS-FD-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	0.0092 J	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0047 UJ	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	< 0.0032 U	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0013 U	< 0.00086 U	< 0.0015 UJ	< 0.0012 U	< 0.0024 U	< 0.0034 U	< 0.0013 U	< 0.0021 UJ	< 0.0021 U	< 0.0013 U	< 0.0015 UJ
Football Field	SSHS-B2686	PS-FD-9	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	0.0059 J	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.00095 U	< 0.0017 U	< 0.0013 U	< 0.0026 U	< 0.0037 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	< 0.0034 UJ	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00091 U	< 0.0016 U	< 0.0013 U	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0015 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/15/2019	854.80	14 - 16 ft	180-90165-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.0054 U	< 0.0038 U	< 0.0041 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U	< 0.004 U	< 0.0056 U	< 0.0022 U	< 0.0036 U	< 0.0034 U	< 0.0022 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	< 0.0050 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U	< 0.0037 U	< 0.0052 U	< 0.0021 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	< 0.0046 U	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0030 U	< 0.0029 U	< 0.0019 U	< 0.0020 U
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.0044 U	< 0.0031 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 UJ	< 0.0017 UJ	< 0.0011 UJ	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	0.014	0.013	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B3	B3 12 May 00 4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated	< 0.0064 U			< 0.42 U	< 0.42 U	< 0.42 U	< 0.0064 U	< 0.0064 U	< 0.0064 U		< 0.0064 U	< 0.0064 U			
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	< 0.0034 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00091 U	< 0.0016 U	< 0.0013 U	< 0.0025 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0015 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 UJ	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 UJ	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	< 0.0033 U	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00087 U	< 0.0015 U	< 0.0012 U	< 0.0024 U	< 0.0034 U	< 0.0013 U	< 0.0022 U	< 0.0021 U	< 0.0014 UJ	< 0.0015 UJ
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	< 0.094 U	< 0.019 U	< 0.028 U	< 0.024 U	< 0.024 U	< 0.019 U	< 0.024 U	< 0.028 U	< 0.024 U	< 0.047 U	< 0.024 U	< 0.024 U	< 0.024 U	< 0.019 U	< 0.024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	< 0.0034 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00091 U	< 0.0016 U	< 0.0013 U	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 UJ	< 0.0015 UJ
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	< 0.00048 U	< 0.00068 U	< 0.00072 U	< 0.00056 U	< 0.0032 U,*	0.00069 J	0.0057 J	< 0.00091 U	< 0.00038 U	< 0.00049 U	< 0.00037 U	< 0.00038 U	< 0.00048 U	< 0.00039 U	< 0.00052 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	855.51	12 - 14 ft	180-80091-3	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	855.46	12 - 14 ft	180-80091-4	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/15/2019	855.13	4 - 6 ft	180-90165-1	Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0061 U	< 0.0022 UJ	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 UJ	< 0.0037 U	< 0.0039 U
Football Field	SSHS-B2621	PS-FD-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 UJ	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0026 U	< 0.0023 U	< 0.0052 U	< 0.0028 U	< 0.0073 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0044 U	< 0.0046 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	< 0.0018 U	< 0.0016 U	< 0.0035 U	< 0.002 U	< 0.005 U	< 0.0018 U	< 0.0024 U	< 0.0016 UJ	< 0.0031 U	< 0.0011 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0031 U
Football Field	SSHS-B2686	PS-FD-9	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	< 0.002 U	< 0.0018 U	< 0.0039 U	< 0.0021 U	< 0.0055 U	< 0.002 U	< 0.0027 U	< 0.0017 UJ	< 0.0034 U	< 0.0012 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	< 0.0019 U	< 0.0017 U	< 0.0037 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 UJ	< 0.0033 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0033 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/15/2019	854.80	14 - 16 ft	180-90165-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.003 U	< 0.0027 U	< 0.0059 U	< 0.0033 U	< 0.0083 U	< 0.003 U	< 0.0041 U	< 0.0026 U	< 0.0052 U	< 0.0019 U	< 0.0042 U	< 0.0028 U	< 0.0024 U	< 0.005 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0043 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	< 0.0028 U	< 0.0025 U	< 0.0055 U	< 0.0030 U	< 0.0077 U	< 0.0027 U	0.0089	< 0.0024 U	< 0.0048 U	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0046 UT	< 0.0049 UT
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	< 0.0025 U	< 0.0023 U	< 0.0050 U	< 0.0027 U	< 0.0070 U	< 0.0025 U	0.011	< 0.0022 U	< 0.0044 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.0020 U	< 0.0042 UT	< 0.0044 UT
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 UJ	< 0.004 UJ
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Football Field	SSHS-B3	B3 12 May 00 4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated	< 0.0064 U						< 0.013 U					< 0.0064 U	< 0.0064 U		
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	< 0.0019 U	< 0.0017 U	< 0.0037 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0033 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	0.0032 J	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	< 0.0018 U	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.005 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0011 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0032 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	< 0.019 U	< 0.028 U	< 0.047 U	< 0.019 U	< 0.047 U	< 0.028 U	< 0.094 U	< 0.047 U	< 0.024 U	< 0.019 U	< 0.019 U	< 0.024 U	< 0.028 U	< 0.24 U	< 0.24 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	< 0.0019 U	< 0.0017 U	< 0.0037 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0033 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	**1,1,2-Trichloroethane**	**Trichloroethene**	**Trichlorofluoromethane**	**Vinyl chloride**	**Xylene (m)**	**Xylene (o)**	**Xylenes (Total)**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	8 - 10 ft	180-80227-1	Not Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	12 - 14 ft	180-80252-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	12 - 14 ft	180-80091-4	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	12 - 14 ft	180-80091-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	12 - 14 ft	180-80105-2	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	12 - 14 ft	180-80105-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	12 - 14 ft	180-80091-2	Not Excavated	< 0.00035 U	< 0.00057 U	< 0.0004 U	< 0.00086 U	< 0.00075 U	< 0.00051 U	< 0.00044 U	< 0.00084 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	12 - 14 ft	180-80091-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0025 U	< 0.0045 U
Football Field	SSHS-B2238	SSHS-B2238-SUB-12-14	7/23/2018	855.07	12 - 14 ft	180-80091-1	Excavated	< 0.0027 U	< 0.0026 U	0.002 J	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2239	SSHS-B2239-SUB-12-14	7/23/2018	855.51	12 - 14 ft	180-80091-3	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	12 - 14 ft	180-80091-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B2241	SSHS-B2241-SUB-12-14	7/23/2018	855.46	12 - 14 ft	180-80091-4	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2242	SSHS-B2242-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2243	SSHS-B2243-SUB-12-14	7/23/2018	856.00	12 - 14 ft	180-80091-3	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	12 - 14 ft	180-80091-3	Not Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0025 U	< 0.0024 U	0.0042 J	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	12 - 14 ft	180-80106-1	Not Excavated	< 0.0026 U	< 0.0025 U	0.01	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2615	SSHS-B2615-SUB-4-6	5/15/2019	855.13	4 - 6 ft	180-90165-1	Excavated	< 0.0026 UJ	< 0.0025 U	< 0.0016 U	< 0.0015 UJ	< 0.0038 U	< 0.002 U	< 0.0025 U	< 0.0045 U
Football Field	SSHS-B2621	PS-FD-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 UJ	< 0.0041 UJ	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2621	SSHS-B2621-SUB-6-8	5/15/2019	855.04	6 - 8 ft	180-90165-1	Excavated	< 0.0031 U	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	14 - 16 ft	180-90324-1	Not Excavated	< 0.0021 U	< 0.002 U	< 0.0013 U	< 0.0012 U	< 0.0031 UJ	< 0.0016 U	< 0.0021 U	< 0.0036 U
Football Field	SSHS-B2686	PS-FD-9	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0014 UJ	< 0.0034 UJ	< 0.0017 U	< 0.0023 U	< 0.004 U
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/15/2019	855.51	6 - 8 ft	180-90165-1	Not Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 UJ	< 0.0033 UJ	< 0.0017 U	< 0.0022 U	< 0.0038 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/15/2019	854.80	14 - 16 ft	180-90165-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2729	SSHS-B2729-SUB-4-6	5/21/2019	856.49	4 - 6 ft	180-90380-1	Excavated	< 0.0035 U	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0052 U	< 0.0026 U	< 0.0034 U	< 0.0061 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-10-12	4/26/2019	855.30	10 - 12 ft	180-89521-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	12 - 14 ft	180-89521-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-2-4	4/26/2019	856.14	2 - 4 ft	180-89521-1	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2762	PS-FD-15	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0029 U	< 0.0027 U	0.0066 J	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-4-6	4/26/2019	856.14	4 - 6 ft	180-89521-1	Excavated	< 0.0029 U	< 0.0028 U	0.0027 J	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-6-8	4/26/2019	856.14	6 - 8 ft	180-89521-1	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	10 - 12 ft	180-89521-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	12 - 14 ft	180-89521-1	Not Excavated	< 0.0028 U	< 0.0027 U	0.0024 J	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0048 U
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	8 - 10 ft	180-89521-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2763	PS-FD-17	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	10 - 12 ft	180-89521-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	6 - 8 ft	180-89521-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	8 - 10 ft	180-89521-1	Not Excavated	< 0.0028 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2781	SSHS-B2781-SUB-8-10	5/17/2019	856.99	8 - 10 ft	180-90275-1	Excavated	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	4 - 6 ft	180903801	Not Excavated	< 0.0033 U	< 0.0031 U	< 0.0020 U	< 0.0019 U	< 0.0048 U	< 0.0024 U	< 0.0032 U	< 0.0056 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	6 - 8 ft	180903801	Not Excavated	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2808	SSHS-B2808-SUB-2-4	5/17/2019	855.18	2 - 4 ft	180-90275-1	Excavated	< 0.0029 U	< 0.0028 U	0.0025 J	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2809	SSHS-B2809-SUB-4-6	5/17/2019	855.39	4 - 6 ft	180-90275-1	Excavated	< 0.0027 U	< 0.0026 U	0.029	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2810	SSHS-B2810-SUB-2-4	5/17/2019	855.11	2 - 4 ft	180-90275-1	Excavated	< 0.0029 U	< 0.0028 U	0.043	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B3	B3_12 May 00_4-8	5/12/2000	853.27	4 - 8 ft	-	Excavated	< 0.0064 U		0.0014 J		< 0.0064 U	< 0.0064 U	< 0.0064 U	
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	12 - 14 ft	180-95155-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	10 - 12 ft	180-95155-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	12 - 14 ft	180-95047-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	10 - 12 ft	180-94981-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	12 - 14 ft	180-94981-3	Not Excavated	< 0.0026 U	< 0.0025 U	0.0016 J	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	12 - 14 ft	180-94829-1	Not Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0038 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	12 - 14 ft	180-94824-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	12 - 14 ft	180-94752-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	12 - 14 ft	180-95155-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	12 - 14 ft	180-95155-2	Not Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	12 - 14 ft	180-95050-1	Not Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	12 - 14 ft	180-95047-2	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	12 - 14 ft	180-94981-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 UJ	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3014	SSHS-B3014-SUB-10-12	8/29/2019	853.35	10 - 12 ft	180-94981-2	Excavated	< 0.0025 U	< 0.0024 U	0.0034 J	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3015	SSHS-B3015-SUB-12-14	8/28/2019	853.51	12 - 14 ft	180-94902-3	Excavated	< 0.0021 U	< 0.002 U	< 0.0013 U	< 0.0012 U	< 0.0031 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	12 - 14 ft	180-94981-2	Not Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	12 - 14 ft	180-123398-1	Not Excavated	< 0.028 U	< 0.024 U	< 0.024 U	< 0.033 U	< 0.028 U	0.069 J	0.023 J	0.092 J
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	12 - 14 ft	180-94829-1	Not Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0038 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	12 - 14 ft	180-94824-3	Not Excavated	< 0.0026 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	12 - 14 ft	180-94824-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	14 - 16 ft	180-94752-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	12 - 14 ft	180-94754-3	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	12 - 14 ft	180-95155-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	12 - 14 ft	180-95155-1	Not Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	14 - 16 ft	180-95047-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.002 UJ	< 0.0023 UJ	< 0.0039 U	< 0.0026 U	< 0.0029 U	< 0.0014 U	< 0.0021 UJ	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.0011 U	< 0.0027 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 UJ	< 0.0024 UJ	< 0.0041 U	< 0.0027 U	< 0.003 U	< 0.0014 U	< 0.0022 UJ	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	< 0.002 U	< 0.0013 U	< 0.0012 U	< 0.0015 UJ	< 0.0017 UJ	< 0.0029 U	< 0.0019 U	< 0.0021 U	< 0.001 U	< 0.0016 UJ	< 0.0017 U	< 0.0014 U	< 0.0025 U	< 0.00079 U	< 0.002 UJ
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	0.0075 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0047 UJ	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	0.0053 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0022 U	< 0.0025 U	< 0.0042 U	< 0.0028 U	< 0.0031 U	< 0.0015 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0036 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 UJ	< 0.0025 UJ	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 UJ	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 UJ	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	0.02 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	0.0035 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	0.0069 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.002 UJ	< 0.0022 U	< 0.0039 U	< 0.0026 U	< 0.0028 UJ	< 0.0014 U	< 0.0021 UJ	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.001 U	< 0.0026 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 UJ	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0019 UJ	< 0.0021 UJ	< 0.0037 U	< 0.0025 U	< 0.0027 U	< 0.0013 U	< 0.002 UJ	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.001 U	< 0.0025 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0018 UJ	< 0.002 UJ	< 0.0034 U	< 0.0023 U	< 0.0025 U	< 0.0012 U	< 0.0018 UJ	< 0.002 U	< 0.0016 U	< 0.0029 U	< 0.00093 U	< 0.0023 UJ
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 UJ	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 UJ	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.002 U	< 0.0022 U	< 0.0039 U	< 0.0026 U	< 0.0029 U	< 0.0014 U	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.0011 U	< 0.0026 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 UJ	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 UJ	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	< 0.18 U	< 0.066 U	< 0.14 U	< 0.11 U	< 0.12 U	< 0.11 U	< 0.19 U	< 0.096 U	< 0.061 U	< 0.12 U	< 0.14 U	< 0.076 U	< 0.093 U	< 0.11 U	< 0.15 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	0.004 J	< 0.0018 U	< 0.0017 U	< 0.0021 U	< 0.0024 U	< 0.0041 U	< 0.0027 U	< 0.003 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	0.017 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	0.0046 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0019 UJ	< 0.0021 U	< 0.0037 U	< 0.0025 U	< 0.0027 U	< 0.0013 U	< 0.002 UJ	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.001 U	< 0.0025 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U	< 0.0019 U	< 0.0028 UJ	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 UJ	< 0.0027 UJ	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0024 UJ	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0021 U	< 0.0024 U	< 0.0041 U	< 0.0027 U	< 0.003 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0025 U	< 0.0042 U	< 0.0028 U	< 0.0031 U	< 0.0015 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0036 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00097 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	< 0.0033 U	< 0.0024 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00088 U	< 0.0016 U	< 0.0013 U	< 0.0025 U	< 0.0034 U	< 0.0014 U	< 0.0022 U	< 0.0021 U	< 0.0014 UJ	< 0.0015 UJ
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 UJ	< 0.0016 UJ
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	< 0.0025 U	< 0.0018 U	< 0.0019 U	< 0.0013 U	< 0.001 U	< 0.00066 U	< 0.0012 U	< 0.00094 U	< 0.0018 U	< 0.0026 U	< 0.001 U	< 0.0016 U	< 0.0016 U	< 0.001 UJ	< 0.0011 UJ
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	< 0.0047 U	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	< 0.0036 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00096 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 UJ	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 UJ	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0028 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 UJ	< 0.0017 UJ
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 UJ	< 0.0017 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	< 0.0033 U	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00088 U	< 0.0016 U	< 0.0012 U	< 0.0024 U	< 0.0034 U	< 0.0014 U	< 0.0022 U	< 0.0021 U	< 0.0014 UJ	< 0.0015 UJ
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 UJ	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 UJ	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	< 0.0032 U	< 0.0022 U	< 0.0024 U	< 0.0016 U	< 0.0013 U	< 0.00084 U	< 0.0015 U	< 0.0012 U	< 0.0023 U	< 0.0033 U	< 0.0013 U	< 0.0021 U	< 0.002 U	< 0.0013 UJ	< 0.0014 UJ
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	< 0.0029 U	< 0.0021 U	< 0.0022 U	< 0.0015 U	< 0.0012 U	< 0.00078 U	< 0.0014 U	< 0.0011 U	< 0.0022 U	< 0.003 U	< 0.0012 U	< 0.0019 U	< 0.0019 U	< 0.0012 UJ	< 0.0013 UJ
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	< 0.0033 U	< 0.0024 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00088 U	< 0.0016 U	< 0.0012 U	< 0.0025 U	< 0.0034 U	< 0.0014 U	< 0.0022 U	< 0.0021 U	< 0.0014 U	< 0.0015 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	0.55	< 0.065 U	< 0.12 U	< 0.079 U	< 0.15 U	< 0.071 U	< 0.075 U	< 0.068 U	< 0.11 U	< 0.19 U	< 0.071 U	< 0.082 U	< 0.063 U	< 0.1 U	< 0.11 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00093 U	< 0.0016 U	< 0.0013 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	< 0.0032 U	< 0.0022 U	< 0.0024 U	< 0.0016 U	< 0.0013 U	< 0.00084 U	< 0.0015 U	< 0.0012 U	< 0.0023 U	< 0.0033 U	< 0.0013 U	< 0.0021 U	< 0.002 U	< 0.0013 UJ	< 0.0014 UJ
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 UJ	< 0.002 UJ
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 UJ	< 0.0018 UJ
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00093 U	< 0.0016 U	< 0.0013 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0016 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	< 0.004 U	< 0.0029 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	0.0044 J	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	0.0042 J	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	0.0041 J	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	< 0.0036 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.00096 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0037 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	0.0039 J	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	< 0.0019 U	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.0051 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0032 U	< 0.0011 U	< 0.0026 U	< 0.0017 U	< 0.0015 U	< 0.0031 U	< 0.0032 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	< 0.002 U	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0034 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	< 0.0014 U	< 0.0012 U	< 0.0027 U	< 0.0015 U	< 0.0038 U	< 0.0014 U	< 0.0019 U	< 0.0012 U	< 0.0024 U	< 0.00086 U	< 0.0019 U	< 0.0013 U	< 0.0011 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0043 U	< 0.0046 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	< 0.002 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0027 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0021 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	< 0.0018 U	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.0051 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0032 U	< 0.0011 U	< 0.0026 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0032 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	< 0.0018 U	< 0.0016 U	< 0.0034 U	< 0.0019 U	< 0.0049 U	< 0.0017 U	< 0.0024 U	< 0.0015 U	< 0.003 U	< 0.0011 U	< 0.0025 U	< 0.0016 U	< 0.0014 U	< 0.0029 U	< 0.0031 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	< 0.0016 U	< 0.0015 U	< 0.0032 U	< 0.0018 U	< 0.0045 U	< 0.0016 U	< 0.0022 U	< 0.0014 U	< 0.0028 U	< 0.001 U	< 0.0023 U	< 0.0015 U	< 0.0013 U	< 0.0027 U	< 0.0028 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	< 0.0019 U	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.0051 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0032 U	< 0.0011 U	< 0.0026 U	< 0.0017 U	< 0.0015 U	< 0.003 U	< 0.0032 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	< 0.002 U	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0027 U	< 0.0017 U	< 0.0034 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	< 0.087 U	< 0.094 U	< 0.074 U	< 0.12 U	< 0.35 U	< 0.11 U	< 0.12 U	< 0.086 U	< 0.069 U	< 0.071 U	< 0.072 U	< 0.095 U	< 0.068 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	< 0.002 U	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.0035 U	< 0.0036 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	< 0.0018 U	< 0.0016 U	< 0.0035 U	< 0.0019 U	< 0.0049 U	< 0.0017 U	< 0.0024 U	< 0.0015 U	< 0.003 U	< 0.0011 U	< 0.0025 U	< 0.0016 U	< 0.0014 U	< 0.0029 U	< 0.0031 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	< 0.002 U	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0034 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	< 0.002 U	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	< 0.002 U	< 0.0018 U	< 0.0039 U	< 0.0022 U	< 0.0055 U	< 0.002 U	< 0.0027 U	< 0.0017 U	< 0.0035 U	< 0.0013 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	< 0.0021 U	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	12 - 14 ft	180-94981-3	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3027	SSHS-B3027-SUB-12-14	8/28/2019	854.13	12 - 14 ft	180-94902-3	Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	12 - 14 ft	180-94981-3	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	12 - 14 ft	180-94902-3	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	12 - 14 ft	180-94902-1	Not Excavated	< 0.0016 U	< 0.0015 U	< 0.00097 U	< 0.00094 U	< 0.0024 U	< 0.0012 U	< 0.0016 U	< 0.0028 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	12 - 14 ft	180-94824-3	Not Excavated	< 0.0026 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	12 - 14 ft	180-94819-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	12 - 14 ft	180-94824-1	Not Excavated	< 0.0031 U	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	14 - 16 ft	180-94752-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	12 - 14 ft	180-94752-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	12 - 14 ft	180-95155-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	12 - 14 ft	180-95162-1	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	12 - 14 ft	180-95047-1	Not Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	12 - 14 ft	180-95006-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	12 - 14 ft	180-94981-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	12 - 14 ft	180-94902-2	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	12 - 14 ft	180-94900-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	12 - 14 ft	180-94900-3	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-2-4	8/27/2019	856.22	2 - 4 ft	180-94824-1	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	12 - 14 ft	180-94824-2	Not Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	12 - 14 ft	180-94819-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	12 - 14 ft	180-94819-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	14 - 16 ft	180-94754-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	10 - 12 ft	180-94752-1	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	12 - 14 ft	180-95165-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	12 - 14 ft	180-95162-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	12 - 14 ft	180-95155-3	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	12 - 14 ft	180-95024-2	Not Excavated	< 0.0022 UJ	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	12 - 14 ft	180-95006-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	12 - 14 ft	180-94981-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	12 - 14 ft	180-94900-3	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	12 - 14 ft	180-94902-2	Not Excavated	< 0.0021 U	< 0.002 U	< 0.0012 U	< 0.0012 U	< 0.003 U	< 0.0015 U	< 0.002 U	< 0.0035 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	12 - 14 ft	180-94902-1	Not Excavated	< 0.0019 U	< 0.0018 U	< 0.0011 U	< 0.0011 U	< 0.0028 U	< 0.0014 U	< 0.0019 U	< 0.0033 U
Northern Athletic Field	SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	14 - 16 ft	180-94900-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	12 - 14 ft	180-94824-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	856.91	10 - 12 ft	180-94819-3	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	12 - 14 ft	180-94819-1	Not Excavated	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	12 - 14 ft	180-95165-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	14 - 16 ft	180-95162-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	12 - 14 ft	180-95050-1	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	12 - 14 ft	180-94900-1	Not Excavated	< 0.0028 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	12 - 14 ft	180-94900-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	12 - 14 ft	180-94900-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	12 - 14 ft	180-94900-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U		< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4	1/27/2021	857.14	2 - 4 ft	1801165292	Excavated	< 0.079 U	< 0.047 U	< 0.074 U	< 0.2 U	< 0.17 U	< 0.084 U	< 0.095 U	< 0.34 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	10 - 12 ft	180-94824-2	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	12 - 14 ft	180-94819-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	12 - 14 ft	180-94819-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	12 - 14 ft	180-94752-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	12 - 14 ft	180-94752-3	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	12 - 14 ft	180-95024-1	Not Excavated	< 0.0021 U	< 0.002 U	< 0.0012 U	< 0.0012 U	< 0.003 U	< 0.0015 U	< 0.002 U	< 0.0035 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	14 - 16 ft	180-95165-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	12 - 14 ft	180-95165-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	6 - 8 ft	180-95165-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	14 - 16 ft	180-95047-3	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	12 - 14 ft	180-95024-2	Not Excavated	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	12 - 14 ft	180-95006-2	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	12 - 14 ft	180-95165-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	14 - 16 ft	180-95165-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	12 - 14 ft	180-94902-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	14 - 16 ft	180-94819-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	12 - 14 ft	180-94824-1	Not Excavated	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	12 - 14 ft	180-94754-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	12 - 14 ft	180-94754-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	12 - 14 ft	180-100985-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	0.0022 J	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	12 - 14 ft	180-100985-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	14 - 16 ft	180-100985-2	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.004 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	12 - 14 ft	180-100985-2	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	12 - 14 ft	180-101038-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	12 - 14 ft	180-101038-1	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	12 - 14 ft	180-101084-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	12 - 14 ft	180-101038-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	12 - 14 ft	180-101084-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 UJ	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 UJ	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-14-16	12/20/2019	858.13	14 - 16 ft	180-100361-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	854.30	14 - 16 ft	180-100380-1	Not Excavated	0.0037 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	0.0049 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U	< 0.0016 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	0.01 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3473	DUP17	7/30/2020	855.34	2 - 4 ft	180-108931-1	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	< 0.19 U	< 0.07 U	< 0.15 U	< 0.12 U	< 0.12 U	< 0.11 U	< 0.2 U	< 0.1 U	< 0.064 U	< 0.12 U	< 0.14 U	< 0.08 U	< 0.098 U	< 0.12 U	< 0.16 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-10-12	2/4/2021	855.42	10 - 12 ft	180-116864-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-12-14	2/4/2021	855.42	12 - 14 ft	180-116864-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-2-4	2/4/2021	855.42	2 - 4 ft	180-116864-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-4-6	2/4/2021	855.42	4 - 6 ft	180-116864-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3572	DUP-30	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-6-8	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-8-10	2/4/2021	855.42	8 - 10 ft	180-116864-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-2-4	2/3/2021	855.66	2 - 4 ft	180-116773-1	Excavated	< 0.0047 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3573	DUP-28	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 UJ	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 UJ
Football Field	SSHS-B3573	SSHS-B3573-SUB-10-12	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-12-14	2/3/2021	855.66	12 - 14 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-4-6	2/3/2021	855.66	4 - 6 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-6-8	2/3/2021	855.66	6 - 8 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-8-10	2/3/2021	855.66	8 - 10 ft	180-116773-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.003 U	< 0.0033 U	< 0.003 U	< 0.0052 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-2-4	2/2/2021	854.85	2 - 4 ft	180-116724-1	Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 UJ	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-10-12	2/2/2021	854.85	10 - 12 ft	180-116724-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-12-14	2/2/2021	854.85	12 - 14 ft	180-116724-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UJ	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-14-16	2/2/2021	854.85	14 - 16 ft	180-116724-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 UJ	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 UJ
Football Field	SSHS-B3575	SSHS-B3575-SUB-4-6	2/2/2021	854.85	4 - 6 ft	180-116724-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 UJ	< 0.003 U	< 0.004 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-6-8	2/2/2021	854.85	6 - 8 ft	180-116724-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 UJ	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-8-10	2/2/2021	854.85	8 - 10 ft	180-116724-1	Not Excavated	< 0.23 U	< 0.083 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.13 U	< 0.24 U	< 0.12 U	< 0.077 U	< 0.15 U	< 0.17 U	< 0.095 U	< 0.12 U	< 0.14 U	< 0.19 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**	**1,1-Dichloroethene**	**1,2-Dichloroethene**	**cis-1,2-Dichloroethene**	**trans-1,2-Dichloroethene**	**1,2-Dichloropropane**	**cis-1,3-Dichloropropene**	**trans-1,3-Dichloropropene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	0.005	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	< 0.0037 U	< 0.0027 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 UJ	< 0.0017 UJ
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 UJ	< 0.0018 UJ
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	0.0042 J	< 0.0027 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-14-16	12/20/2019	858.13	14 - 16 ft	180-100361-1	Not Excavated	0.011	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	854.30	14 - 16 ft	180-100380-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	0.008	< 0.0029 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	0.008	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	0.0058	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	0.0087	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	0.0099	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	0.0077	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B3473	DUP17	7/30/2020	855.34	2 - 4 ft	180-108931-1	Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	0.0099	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	0.013	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	0.0081	< 0.0016 U	< 0.0028 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	0.0086	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	0.0069	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	0.33	< 0.068 U	< 0.12 U	< 0.083 U	< 0.15 U	< 0.074 U	< 0.079 U	< 0.071 U	< 0.11 U	< 0.2 U	< 0.075 U	< 0.087 U	< 0.066 U	< 0.11 U	< 0.11 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-10-12	2/4/2021	855.42	10 - 12 ft	180-116864-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-12-14	2/4/2021	855.42	12 - 14 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-2-4	2/4/2021	855.42	2 - 4 ft	180-116864-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-4-6	2/4/2021	855.42	4 - 6 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3572	DUP-30	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-6-8	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-8-10	2/4/2021	855.42	8 - 10 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-2-4	2/3/2021	855.66	2 - 4 ft	180-116773-1	Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0038 U	< 0.0018 U	< 0.0019 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3573	DUP-28	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-10-12	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-12-14	2/3/2021	855.66	12 - 14 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-4-6	2/3/2021	855.66	4 - 6 ft	180-116773-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-6-8	2/3/2021	855.66	6 - 8 ft	180-116773-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-8-10	2/3/2021	855.66	8 - 10 ft	180-116773-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.004 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U	< 0.0053 U	< 0.002 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-2-4	2/2/2021	854.85	2 - 4 ft	180-116724-1	Excavated	0.0083	< 0.0016 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-10-12	2/2/2021	854.85	10 - 12 ft	180-116724-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-12-14	2/2/2021	854.85	12 - 14 ft	180-116724-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-14-16	2/2/2021	854.85	14 - 16 ft	180-116724-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-4-6	2/2/2021	854.85	4 - 6 ft	180-116724-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-6-8	2/2/2021	854.85	6 - 8 ft	180-116724-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 UJ	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-8-10	2/2/2021	854.85	8 - 10 ft	180-116724-1	Not Excavated	< 0.27 U	< 0.081 U	< 0.15 U	< 0.099 U	< 0.18 U	< 0.089 U	< 0.095 U	< 0.085 U	< 0.13 U	< 0.24 U	< 0.089 U	< 0.1 U	< 0.079 U	< 0.13 U	< 0.13 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	< 0.0022 U	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.0035 U	< 0.0036 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0042 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-14-16	12/20/2019	858.13	14 - 16 ft	180-100361-1	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	854.30	14 - 16 ft	180-100380-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 UT	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 UT	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	0.0078	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	< 0.0021 U	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 UT	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 UT	0.0068	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 UT	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 UT	0.0025 J	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	< 0.0024 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	< 0.0023 U	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B3473	DUP17	7/30/2020	855.34	2 - 4 ft	180-108931-1	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	< 0.0023 U	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.0019 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0015 UT	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.0019 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0015 UT	0.0035 J	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 UT	0.0042 J	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	< 0.092 U	< 0.099 U	< 0.078 U	< 0.13 U	< 0.36 U	< 0.12 U	< 0.13 U	< 0.091 U	< 0.073 U	< 0.074 U	< 0.075 U	< 0.1 U	< 0.071 U	< 0.14 UJ	< 0.13 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-10-12	2/4/2021	855.42	10 - 12 ft	180-116864-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-12-14	2/4/2021	855.42	12 - 14 ft	180-116864-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-2-4	2/4/2021	855.42	2 - 4 ft	180-116864-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-4-6	2/4/2021	855.42	4 - 6 ft	180-116864-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3572	DUP-30	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-6-8	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-8-10	2/4/2021	855.42	8 - 10 ft	180-116864-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-2-4	2/3/2021	855.66	2 - 4 ft	180-116773-1	Excavated	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.009 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0019 U	< 0.0024 U	< 0.0018 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3573	DUP-28	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UJ	< 0.0026 UJ
Football Field	SSHS-B3573	SSHS-B3573-SUB-10-12	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-12-14	2/3/2021	855.66	12 - 14 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-4-6	2/3/2021	855.66	4 - 6 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-6-8	2/3/2021	855.66	6 - 8 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-8-10	2/3/2021	855.66	8 - 10 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0024 U	< 0.0026 U	< 0.002 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U	< 0.002 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-2-4	2/2/2021	854.85	2 - 4 ft	180-116724-1	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-10-12	2/2/2021	854.85	10 - 12 ft	180-116724-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-12-14	2/2/2021	854.85	12 - 14 ft	180-116724-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-14-16	2/2/2021	854.85	14 - 16 ft	180-116724-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UJ	< 0.0029 UJ
Football Field	SSHS-B3575	SSHS-B3575-SUB-4-6	2/2/2021	854.85	4 - 6 ft	180-116724-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-6-8	2/2/2021	854.85	6 - 8 ft	180-116724-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-8-10	2/2/2021	854.85	8 - 10 ft	180-116724-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.093 U	< 0.15 U	< 0.44 U	< 0.14 U	< 0.15 U	< 0.11 U	< 0.087 U	< 0.089 U	< 0.09 U	< 0.12 U	< 0.085 U	< 0.16 UJ	< 0.15 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	**1,1,2-Trichloroethane**	**Trichloroethene**	**Trichlorofluoromethane**	**Vinyl chloride**	**Xylene (m)**	**Xylene (o)**	**Xylenes (Total)**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	12 - 14 ft	180-101084-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	12 - 14 ft	180-101084-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	12 - 14 ft	180-101084-3	Not Excavated	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	12 - 14 ft	180-101038-2	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	12 - 14 ft	180-101084-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	12 - 14 ft	180-101038-3	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	12 - 14 ft	180-101084-3	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	14 - 16 ft	180-95024-1	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4	1/26/2021	857.57	2 - 4 ft	1801164622	Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	14 - 16 ft	180-95024-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	12 - 14 ft	180-101038-2	Not Excavated	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	12 - 14 ft	180-101038-2	Not Excavated	< 0.0025 U	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	12 - 14 ft	180-95050-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	14 - 16 ft	180-95165-3	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	14 - 16 ft	180-95165-3	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	14 - 16 ft	180-95006-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3246	SSHS-B3246-SUB-14-16	12/20/2019	858.13	14 - 16 ft	180-100361-1	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	854.30	14 - 16 ft	180-100380-1	Not Excavated	< 0.0025 U	< 0.0024 U	0.002 J	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10	1/22/2021	854.14	8 - 10 ft	1801163651	Excavated	< 0.0017 U	< 0.0010 U	0.011	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12	1/22/2021	854.14	10 - 12 ft	1801163651	Excavated	< 0.0018 U	< 0.0011 U	0.019	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	12 - 14 ft	180-100361-1	Not Excavated	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12	1/22/2021	853.65	10 - 12 ft	1801163651	Excavated	< 0.0017 U	< 0.0010 U	0.017	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14	1/22/2021	853.65	12 - 14 ft	1801163651	Excavated	< 0.0018 U	< 0.0011 U	0.0055	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	12 - 14 ft	180-108826-3	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	10 - 12 ft	180-108826-2	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	12 - 14 ft	180-108826-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	4 - 6 ft	180-108826-2	Not Excavated	< 0.0028 U	< 0.0026 U	0.003 J	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-2-4	7/27/2020	856.28	2 - 4 ft	180-108826-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-4-6	7/27/2020	856.28	4 - 6 ft	180-108826-2	Excavated	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0015 UJ	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	8 - 10 ft	180-108826-2	Not Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 UJ	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	10 - 12 ft	180-108826-2	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-2	Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B3473	DUP17	7/30/2020	855.34	2 - 4 ft	180-108931-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	8 - 10 ft	180-108826-2	Not Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	2 - 4 ft	180-108826-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	2 - 4 ft	180-108826-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	2 - 4 ft	180-108826-1	Not Excavated	< 0.0027 U	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	2 - 4 ft	180-108826-1	Not Excavated	< 0.0027 U	< 0.0025 U	0.0018 J	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U		< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U		< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10	1/20/2021	854.07	8 - 10 ft	1801162471	Excavated	< 0.0017 U	< 0.0010 U	0.0033 J	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12	1/20/2021	854.07	10 - 12 ft	1801162471	Excavated	< 0.0017 U	< 0.0010 U	0.0054	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.0017 U	< 0.0010 U	0.0096	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	14 - 16 ft	180-115861-1	Not Excavated	< 0.083 U	< 0.049 U	< 0.078 U	< 0.21 U	< 0.18 U	< 0.088 U	< 0.1 U	< 0.36 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-10-12	2/4/2021	855.42	10 - 12 ft	180-116864-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0034 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-12-14	2/4/2021	855.42	12 - 14 ft	180-116864-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-2-4	2/4/2021	855.42	2 - 4 ft	180-116864-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-4-6	2/4/2021	855.42	4 - 6 ft	180-116864-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3572	DUP-30	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.012 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-6-8	2/4/2021	855.42	6 - 8 ft	180-116864-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 UJ	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3572	SSHS-B3572-SUB-8-10	2/4/2021	855.42	8 - 10 ft	180-116864-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0036 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-2-4	2/3/2021	855.66	2 - 4 ft	180-116773-1	Excavated	< 0.002 U	< 0.0012 U	0.044	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Football Field	SSHS-B3573	DUP-28	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.001 U	0.065	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-10-12	2/3/2021	855.66	10 - 12 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.001 U	0.0074	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-12-14	2/3/2021	855.66	12 - 14 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-4-6	2/3/2021	855.66	4 - 6 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0042 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-6-8	2/3/2021	855.66	6 - 8 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0044 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3573	SSHS-B3573-SUB-8-10	2/3/2021	855.66	8 - 10 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0041 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0022 U	< 0.0013 U	0.11	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Excavated	< 0.002 U	< 0.0012 U	0.025	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.036	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0022 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.031	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3574	SSHS-B3574-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0023 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-2-4	2/2/2021	854.85	2 - 4 ft	180-116724-1	Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-10-12	2/2/2021	854.85	10 - 12 ft	180-116724-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0021 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-12-14	2/2/2021	854.85	12 - 14 ft	180-116724-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0037 J	< 0.0046 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-14-16	2/2/2021	854.85	14 - 16 ft	180-116724-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-4-6	2/2/2021	854.85	4 - 6 ft	180-116724-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-6-8	2/2/2021	854.85	6 - 8 ft	180-116724-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0034 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Football Field	SSHS-B3575	SSHS-B3575-SUB-8-10	2/2/2021	854.85	8 - 10 ft	180-116724-1	Not Excavated	< 0.099 U	< 0.059 U	< 0.093 U	< 0.25 U	< 0.21 U	< 0.11 U	< 0.12 U	< 0.43 U

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^{1} (ft amsl)	Sample depth at time of sampling^{5} (bgs)	Lab Report	Excavation Status^{7}															
Football Field	SSHS-B3576	SSHS-B3576-SUB-2-4	2/3/2021	855.76	2 - 4 ft	180-116773-1	Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3576	SSHS-B3576-SUB-10-12	2/3/2021	855.76	10 - 12 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3576	SSHS-B3576-SUB-12-14	2/3/2021	855.76	12 - 14 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 UJ	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3576	DUP-27	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-4-6	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.28 U	< 0.1 U	< 0.22 U	< 0.17 U	< 0.18 U	< 0.16 U	< 0.29 U	< 0.15 U	< 0.094 U	< 0.18 U	< 0.21 U	< 0.12 U	< 0.14 U	< 0.17 U	< 0.23 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-6-8	2/3/2021	855.76	6 - 8 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 UJ	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3576	SSHS-B3576-SUB-8-10	2/3/2021	855.76	8 - 10 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3577	SSHS-B3577-SUB-10-12	2/5/2021	856.15	10 - 12 ft	180-116914-1	Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-12-14	2/5/2021	856.15	12 - 14 ft	180-116914-1	Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-2-4	2/5/2021	856.15	2 - 4 ft	180-116914-1	Excavated	< 0.24 U	< 0.087 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.14 U	< 0.25 U	< 0.13 U	< 0.08 U	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-4-6	2/5/2021	856.15	4 - 6 ft	180-116914-1	Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-6-8	2/5/2021	856.15	6 - 8 ft	180-116914-1	Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-8-10	2/5/2021	856.15	8 - 10 ft	180-116914-1	Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-14-16	2/5/2021	856.15	14 - 16 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UJ	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UJ	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3578	DUP-29	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3578	SSHS-B3578-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UJ	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-10-12	2/5/2021	856.27	10 - 12 ft	180-116914-1	Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-12-14	2/5/2021	856.27	12 - 14 ft	180-116914-1	Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-2-4	2/5/2021	856.27	2 - 4 ft	180-116914-1	Excavated	0.0086 J	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.002 U	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-4-6	2/5/2021	856.27	4 - 6 ft	180-116914-1	Excavated	0.0095 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3579	DUP-31	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.26 U	< 0.094 U	< 0.2 U	< 0.16 U	< 0.17 U	< 0.15 U	< 0.27 U	< 0.14 U	< 0.086 U	< 0.16 U	< 0.19 U	< 0.11 U	< 0.13 U	< 0.16 U	< 0.22 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-6-8	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-8-10	2/5/2021	856.27	8 - 10 ft	180-116914-1	Excavated	0.0094 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-14-16	2/5/2021	856.27	14 - 16 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-2-4	2/5/2021	856.23	2 - 4 ft	180-116914-1	Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3580	DUP-32	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-10-12	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-12-14	2/5/2021	856.23	12 - 14 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-14-16	2/5/2021	856.23	14 - 16 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-4-6	2/5/2021	856.23	4 - 6 ft	180-116914-1	Not Excavated	< 0.2 U	< 0.073 U	< 0.16 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.21 U	< 0.11 U	< 0.067 U	< 0.13 U	< 0.15 U	< 0.083 U	< 0.1 U	< 0.12 U	< 0.17 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-6-8	2/5/2021	856.23	6 - 8 ft	180-116914-1	Not Excavated	< 0.23 U	< 0.083 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.13 U	< 0.24 U	< 0.12 U	< 0.077 U	< 0.15 U	< 0.17 U	< 0.095 U	< 0.12 U	< 0.14 U	< 0.19 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-8-10	2/5/2021	856.23	8 - 10 ft	180-116914-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-2-4	2/5/2021	856.18	2 - 4 ft	180-116914-1	Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-10-12	2/5/2021	856.18	10 - 12 ft	180-116914-1	Not Excavated	0.021 J	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-12-14	2/5/2021	856.18	12 - 14 ft	180-116914-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-14-16	2/5/2021	856.18	14 - 16 ft	180-116914-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3581	DUP-33	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-4-6	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-6-8	2/5/2021	856.18	6 - 8 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-8-10	2/5/2021	856.18	8 - 10 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-10-12	2/5/2021	855.93	10 - 12 ft	180-116914-1	Not Excavated	< 0.21 U	< 0.077 U	< 0.16 U	< 0.13 U	< 0.14 U	< 0.12 U	< 0.22 U	< 0.11 U	< 0.071 U	< 0.13 U	< 0.16 U	< 0.087 U	< 0.11 U	< 0.13 U	< 0.18 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-12-14	2/5/2021	855.93	12 - 14 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3582	DUP-35	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-14-16	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3582	DUP-34	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-2-4	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-4-6	2/5/2021	855.93	4 - 6 ft	180-116914-1	Not Excavated	< 0.23 U	< 0.085 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U	< 0.078 U	< 0.15 U	< 0.18 U	< 0.097 U	< 0.12 U	< 0.14 U	< 0.2 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-6-8	2/5/2021	855.93	6 - 8 ft	180-116914-1	Not Excavated	< 0.25 U	< 0.092 U	< 0.2 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.26 U	< 0.13 U	< 0.085 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.16 U	< 0.21 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-8-10	2/5/2021	855.93	8 - 10 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-10-12	2/5/2021	855.33	10 - 12 ft	180-116914-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-12-14	2/5/2021	855.33	12 - 14 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3583	DUP-36	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-14-16	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-2-4	2/5/2021	855.33	2 - 4 ft	180-116914-1	Not Excavated	< 0.24 U	< 0.087 U	< 0.18 U	< 0.14 U	< 0.16 U	< 0.14 U	< 0.25 U	< 0.13 U	< 0.08 U	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-4-6	2/5/2021	855.33	4 - 6 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-6-8	2/5/2021	855.33	6 - 8 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 UJ
Football Field	SSHS-B3583	SSHS-B3583-SUB-8-10	2/5/2021	855.33	8 - 10 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0033 U
Football Field	SSHS-B3593	SSHS-B3593-SUB-2-4	2/4/2021	854.95	2 - 4 ft	180-116864-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3598	SSHS-B3598-SUB-2-4	2/4/2021	854.90	2 - 4 ft	180-116864-1	Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3599	DUP-38	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.08 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U
Football Field	SSHS-B3599	SSHS-B3599-SUB-2-4	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00091 U	< 0.00089 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00097 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated	0.0047 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00067 U	< 0.00065 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated	0.012 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	0.0068 J	0.00037 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00088 U	< 0.00085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00094 U	< 0.00091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3576	SSHS-B3576-SUB-2-4	2/3/2021	855.76	2 - 4 ft	180-116773-1	Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-10-12	2/3/2021	855.76	10 - 12 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-12-14	2/3/2021	855.76	12 - 14 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3576	DUP-27	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-4-6	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.33 U	< 0.099 U	< 0.18 U	< 0.12 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.1 U	< 0.16 U	< 0.29 U	< 0.11 U	< 0.13 U	< 0.096 U	< 0.16 U	< 0.16 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-6-8	2/3/2021	855.76	6 - 8 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-8-10	2/3/2021	855.76	8 - 10 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-10-12	2/5/2021	856.15	10 - 12 ft	180-116914-1	Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-12-14	2/5/2021	856.15	12 - 14 ft	180-116914-1	Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-2-4	2/5/2021	856.15	2 - 4 ft	180-116914-1	Excavated	< 0.28 U	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.098 U	< 0.089 U	< 0.14 UJ	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-4-6	2/5/2021	856.15	4 - 6 ft	180-116914-1	Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-6-8	2/5/2021	856.15	6 - 8 ft	180-116914-1	Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-8-10	2/5/2021	856.15	8 - 10 ft	180-116914-1	Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-14-16	2/5/2021	856.15	14 - 16 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UJ	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B3578	DUP-29	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-10-12	2/5/2021	856.27	10 - 12 ft	180-116914-1	Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-12-14	2/5/2021	856.27	12 - 14 ft	180-116914-1	Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-2-4	2/5/2021	856.27	2 - 4 ft	180-116914-1	Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.003 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U	< 0.004 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-4-6	2/5/2021	856.27	4 - 6 ft	180-116914-1	Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3579	DUP-31	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.3 U	< 0.091 U	< 0.17 U	< 0.11 U	< 0.2 U	< 0.1 U	< 0.11 U	< 0.096 U	< 0.15 UJ	< 0.27 U	< 0.1 U	< 0.12 U	< 0.088 U	< 0.15 U	< 0.15 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-6-8	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-8-10	2/5/2021	856.27	8 - 10 ft	180-116914-1	Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-14-16	2/5/2021	856.27	14 - 16 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-2-4	2/5/2021	856.23	2 - 4 ft	180-116914-1	Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3580	DUP-32	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-10-12	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-12-14	2/5/2021	856.23	12 - 14 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-14-16	2/5/2021	856.23	14 - 16 ft	180-116914-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-4-6	2/5/2021	856.23	4 - 6 ft	180-116914-1	Not Excavated	< 0.23 U	< 0.071 U	< 0.13 U	< 0.087 U	< 0.16 U	< 0.078 U	< 0.083 U	< 0.075 U	< 0.12 UJ	< 0.21 U	< 0.078 U	< 0.091 U	< 0.069 U	< 0.11 U	< 0.12 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-6-8	2/5/2021	856.23	6 - 8 ft	180-116914-1	Not Excavated	< 0.27 U	< 0.081 U	< 0.15 U	< 0.099 U	< 0.18 U	< 0.089 U	< 0.094 U	< 0.085 U	< 0.13 UJ	< 0.24 U	< 0.089 U	< 0.1 U	< 0.079 U	< 0.13 U	< 0.13 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-8-10	2/5/2021	856.23	8 - 10 ft	180-116914-1	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-2-4	2/5/2021	856.18	2 - 4 ft	180-116914-1	Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-10-12	2/5/2021	856.18	10 - 12 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-12-14	2/5/2021	856.18	12 - 14 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 UJ	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-14-16	2/5/2021	856.18	14 - 16 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3581	DUP-33	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-4-6	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-6-8	2/5/2021	856.18	6 - 8 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-8-10	2/5/2021	856.18	8 - 10 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-10-12	2/5/2021	855.93	10 - 12 ft	180-116914-1	Not Excavated	< 0.25 U	< 0.074 U	< 0.14 U	< 0.091 U	< 0.17 U	< 0.081 U	< 0.087 U	< 0.078 U	< 0.12 UJ	< 0.22 U	< 0.082 U	< 0.095 U	< 0.072 U	< 0.12 U	< 0.12 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-12-14	2/5/2021	855.93	12 - 14 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 UJ	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3582	DUP-35	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-14-16	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3582	DUP-34	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-2-4	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0052 U	< 0.0016 UJ	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-4-6	2/5/2021	855.93	4 - 6 ft	180-116914-1	Not Excavated	< 0.27 U	< 0.083 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.09 U	< 0.096 U	< 0.087 U	< 0.14 UJ	< 0.25 U	< 0.091 U	< 0.11 U	< 0.08 U	< 0.13 U	< 0.14 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-6-8	2/5/2021	855.93	6 - 8 ft	180-116914-1	Not Excavated	< 0.29 U	< 0.089 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.098 U	< 0.1 U	< 0.094 U	< 0.15 UJ	< 0.27 U	< 0.098 U	< 0.11 U	< 0.087 U	< 0.14 U	< 0.15 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-8-10	2/5/2021	855.93	8 - 10 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0014 UJ	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-10-12	2/5/2021	855.33	10 - 12 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 UJ	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-12-14	2/5/2021	855.33	12 - 14 ft	180-116914-1	Not Excavated	< 0.0047 U	< 0.0014 UJ	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3583	DUP-36	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-14-16	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 UJ	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-2-4	2/5/2021	855.33	2 - 4 ft	180-116914-1	Not Excavated	< 0.28 U	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.099 U	< 0.089 U	< 0.14 UJ	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-4-6	2/5/2021	855.33	4 - 6 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 UJ	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-6-8	2/5/2021	855.33	6 - 8 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 UJ	< 0.0034 UJ	< 0.0017 UJ	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-8-10	2/5/2021	855.33	8 - 10 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0014 UJ	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3593	SSHS-B3593-SUB-2-4	2/4/2021	854.95	2 - 4 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	0.011	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	0.012	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3598	SSHS-B3598-SUB-2-4	2/4/2021	854.90	2 - 4 ft	180-116864-1	Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3599	DUP-38	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.034 U	< 0.084 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.092 U	< 0.034 U	< 0.088 U	< 0.034 U	< 0.034 U	< 0.093 U	< 0.11 U	< 0.034 U	< 0.14 U	< 0.14 U
Football Field	SSHS-B3599	SSHS-B3599-SUB-2-4	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	0.013	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated	0.0058 J	< 0.00089 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00097 U	< 0.034 U	< 0.00035 U	< 0.034 U	< 0.034 U	< 0.00089 U	< 0.00071 U	< 0.034 U	< 0.001 U	< 0.003 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated	< 0.034 U	< 0.00065 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.034 U	< 0.00025 U	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.00052 U	< 0.034 U	< 0.00073 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.00024 U	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.0005 U	< 0.034 U	< 0.0007 U	< 0.0021 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00033 U	< 0.034 U	< 0.034 U	< 0.00085 U	< 0.00069 U	< 0.034 U	< 0.034 U	< 0.0029 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00092 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U	< 0.00036 U	< 0.034 U	< 0.034 U	< 0.00091 U	< 0.00074 U	< 0.034 U	< 0.001 U	< 0.0031 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3576	SSHS-B3576-SUB-2-4	2/3/2021	855.76	2 - 4 ft	180-116773-1	Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 UJ	< 0.0027 UJ
Football Field	SSHS-B3576	SSHS-B3576-SUB-10-12	2/3/2021	855.76	10 - 12 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ
Football Field	SSHS-B3576	SSHS-B3576-SUB-12-14	2/3/2021	855.76	12 - 14 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ
Football Field	SSHS-B3576	DUP-27	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-4-6	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.13 U	< 0.14 U	< 0.11 U	< 0.19 U	< 0.53 U	< 0.17 U	< 0.18 U	< 0.13 U	< 0.11 U	< 0.11 U	< 0.11 U	< 0.15 U	< 0.1 U	< 0.2 UJ	< 0.18 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-6-8	2/3/2021	855.76	6 - 8 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ
Football Field	SSHS-B3576	SSHS-B3576-SUB-8-10	2/3/2021	855.76	8 - 10 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ
Football Field	SSHS-B3577	SSHS-B3577-SUB-10-12	2/5/2021	856.15	10 - 12 ft	180-116914-1	Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-12-14	2/5/2021	856.15	12 - 14 ft	180-116914-1	Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-2-4	2/5/2021	856.15	2 - 4 ft	180-116914-1	Excavated	< 0.11 U	< 0.12 U	< 0.097 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.09 U	< 0.092 U	< 0.093 U	< 0.12 U	< 0.089 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-4-6	2/5/2021	856.15	4 - 6 ft	180-116914-1	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-6-8	2/5/2021	856.15	6 - 8 ft	180-116914-1	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-8-10	2/5/2021	856.15	8 - 10 ft	180-116914-1	Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-14-16	2/5/2021	856.15	14 - 16 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3578	DUP-29	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ
Football Field	SSHS-B3578	SSHS-B3578-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-10-12	2/5/2021	856.27	10 - 12 ft	180-116914-1	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-12-14	2/5/2021	856.27	12 - 14 ft	180-116914-1	Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-2-4	2/5/2021	856.27	2 - 4 ft	180-116914-1	Excavated	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-4-6	2/5/2021	856.27	4 - 6 ft	180-116914-1	Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3579	DUP-31	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.12 U	< 0.13 U	< 0.1 U	< 0.17 U	< 0.49 U	< 0.16 U	< 0.17 U	< 0.12 U	< 0.098 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.096 U	< 0.18 U	< 0.17 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-6-8	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-8-10	2/5/2021	856.27	8 - 10 ft	180-116914-1	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-14-16	2/5/2021	856.27	14 - 16 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-2-4	2/5/2021	856.23	2 - 4 ft	180-116914-1	Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3580	DUP-32	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-10-12	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-12-14	2/5/2021	856.23	12 - 14 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-14-16	2/5/2021	856.23	14 - 16 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-4-6	2/5/2021	856.23	4 - 6 ft	180-116914-1	Not Excavated	< 0.096 U	< 0.1 U	< 0.081 U	< 0.13 U	< 0.38 U	< 0.13 U	< 0.13 U	< 0.095 U	< 0.076 U	< 0.078 U	< 0.079 U	< 0.1 U	< 0.075 U	< 0.14 U	< 0.13 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-6-8	2/5/2021	856.23	6 - 8 ft	180-116914-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.093 U	< 0.15 U	< 0.43 U	< 0.14 U	< 0.15 U	< 0.11 U	< 0.087 U	< 0.089 U	< 0.09 U	< 0.12 U	< 0.085 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-8-10	2/5/2021	856.23	8 - 10 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-2-4	2/5/2021	856.18	2 - 4 ft	180-116914-1	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-10-12	2/5/2021	856.18	10 - 12 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-12-14	2/5/2021	856.18	12 - 14 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-14-16	2/5/2021	856.18	14 - 16 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3581	DUP-33	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-4-6	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-6-8	2/5/2021	856.18	6 - 8 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-8-10	2/5/2021	856.18	8 - 10 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-10-12	2/5/2021	855.93	10 - 12 ft	180-116914-1	Not Excavated	< 0.1 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.4 U	< 0.13 U	< 0.14 U	< 0.099 U	< 0.08 U	< 0.081 U	< 0.083 U	< 0.11 U	< 0.078 U	< 0.15 U	< 0.14 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-12-14	2/5/2021	855.93	12 - 14 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3582	DUP-35	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ
Football Field	SSHS-B3582	SSHS-B3582-SUB-14-16	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3582	DUP-34	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 UJ	< 0.003 UJ
Football Field	SSHS-B3582	SSHS-B3582-SUB-2-4	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-4-6	2/5/2021	855.93	4 - 6 ft	180-116914-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.095 U	< 0.16 U	< 0.44 U	< 0.15 U	< 0.15 U	< 0.11 U	< 0.089 U	< 0.09 U	< 0.092 U	< 0.12 U	< 0.087 U	< 0.17 U	< 0.15 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-6-8	2/5/2021	855.93	6 - 8 ft	180-116914-1	Not Excavated	< 0.12 U	< 0.13 U	< 0.1 U	< 0.17 U	< 0.48 U	< 0.16 U	< 0.17 U	< 0.12 U	< 0.096 U	< 0.098 U	< 0.099 U	< 0.13 U	< 0.094 U	< 0.18 U	< 0.17 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-8-10	2/5/2021	855.93	8 - 10 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-10-12	2/5/2021	855.33	10 - 12 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-12-14	2/5/2021	855.33	12 - 14 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3583	DUP-36	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-14-16	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-2-4	2/5/2021	855.33	2 - 4 ft	180-116914-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.097 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.091 U	< 0.092 U	< 0.094 U	< 0.12 U	< 0.089 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-4-6	2/5/2021	855.33	4 - 6 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-6-8	2/5/2021	855.33	6 - 8 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 UJ	< 0.0028 UJ
Football Field	SSHS-B3583	SSHS-B3583-SUB-8-10	2/5/2021	855.33	8 - 10 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3593	SSHS-B3593-SUB-2-4	2/4/2021	854.95	2 - 4 ft	180-116864-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U
Football Field	SSHS-B3598	SSHS-B3598-SUB-2-4	2/4/2021	854.90	2 - 4 ft	180-116864-1	Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3599	DUP-38	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.11 U	< 0.09 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.088 U	< 0.034 U	< 0.16 U
Football Field	SSHS-B3599	SSHS-B3599-SUB-2-4	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated	< 0.00048 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.00068 U	< 0.00035 U	< 0.034 U	< 0.00093 U	< 0.00052 U	< 0.034 U	< 0.00042 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated	< 0.00035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U	< 0.0017 U	< 0.0005 U	< 0.00025 U	< 0.034 U	< 0.00068 U	< 0.00038 U	< 0.034 U	< 0.00031 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00088 J	< 0.034 U	< 0.0016 U	< 0.00048 U	< 0.00024 U	< 0.034 U	< 0.00065 U	0.0009 J	< 0.034 U	< 0.0003 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	< 0.00046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 UJ	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.034 U	< 0.034 U	< 0.0009 U	0.0014 J	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.00049 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.0007 U	< 0.00036 U	< 0.034 U	< 0.00096 U	< 0.00054 U	< 0.034 U	< 0.00043 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3576	SSHS-B3576-SUB-2-4	2/3/2021	855.76	2 - 4 ft	180-116773-1	Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-10-12	2/3/2021	855.76	10 - 12 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-12-14	2/3/2021	855.76	12 - 14 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3576	DUP-27	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-4-6	2/3/2021	855.76	4 - 6 ft	180-116773-1	Not Excavated	< 0.12 U	< 0.071 U	< 0.11 U	< 0.3 U	< 0.26 U	< 0.13 U	< 0.15 U	< 0.52 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-6-8	2/3/2021	855.76	6 - 8 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3576	SSHS-B3576-SUB-8-10	2/3/2021	855.76	8 - 10 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-10-12	2/5/2021	856.15	10 - 12 ft	180-116914-1	Excavated	< 0.0017 U	< 0.001 U	0.0016 J	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-12-14	2/5/2021	856.15	12 - 14 ft	180-116914-1	Excavated	< 0.0018 U	< 0.0011 U	0.0082	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-2-4	2/5/2021	856.15	2 - 4 ft	180-116914-1	Excavated	< 0.1 U	< 0.061 U	< 0.097 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-4-6	2/5/2021	856.15	4 - 6 ft	180-116914-1	Excavated	< 0.002 U	< 0.0012 U	0.015	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-6-8	2/5/2021	856.15	6 - 8 ft	180-116914-1	Excavated	< 0.0019 U	< 0.0011 U	0.0092	< 0.0048 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-8-10	2/5/2021	856.15	8 - 10 ft	180-116914-1	Excavated	< 0.0018 U	< 0.0011 U	0.004 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-14-16	2/5/2021	856.15	14 - 16 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-2-4	2/3/2021	855.72	2 - 4 ft	180-116773-1	Excavated	< 0.002 U	< 0.0012 U	0.022	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-10-12	2/3/2021	855.72	10 - 12 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.001 U	0.0084	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-12-14	2/3/2021	855.72	12 - 14 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0021 J	< 0.0048 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-4-6	2/3/2021	855.72	4 - 6 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-6-8	2/3/2021	855.72	6 - 8 ft	180-116773-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0036 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3578	DUP-29	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.001 U	0.0031 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3578	SSHS-B3578-SUB-8-10	2/3/2021	855.72	8 - 10 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0046 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-10-12	2/5/2021	856.27	10 - 12 ft	180-116914-1	Excavated	< 0.0019 U	< 0.0011 U	0.0024 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-12-14	2/5/2021	856.27	12 - 14 ft	180-116914-1	Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-2-4	2/5/2021	856.27	2 - 4 ft	180-116914-1	Excavated	< 0.0016 U	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.002 U	< 0.0071 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-4-6	2/5/2021	856.27	4 - 6 ft	180-116914-1	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Football Field	SSHS-B3579	DUP-31	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.11 U	< 0.066 U	< 0.1 U	< 0.28 U	< 0.24 U	< 0.12 U	< 0.13 U	< 0.48 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-6-8	2/5/2021	856.27	6 - 8 ft	180-116914-1	Excavated	< 0.0018 U	< 0.0011 U	0.0027 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-8-10	2/5/2021	856.27	8 - 10 ft	180-116914-1	Excavated	< 0.0019 U	< 0.0011 U	0.0072	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3579	SSHS-B3579-SUB-14-16	2/5/2021	856.27	14 - 16 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-2-4	2/5/2021	856.23	2 - 4 ft	180-116914-1	Excavated	< 0.0018 U	< 0.0011 U	0.037	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3580	DUP-32	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0089 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-10-12	2/5/2021	856.23	10 - 12 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.023 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-12-14	2/5/2021	856.23	12 - 14 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.017 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-14-16	2/5/2021	856.23	14 - 16 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0061	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-4-6	2/5/2021	856.23	4 - 6 ft	180-116914-1	Not Excavated	< 0.086 U	< 0.051 U	< 0.081 U	< 0.22 U	< 0.19 U	< 0.092 U	< 0.1 U	< 0.37 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-6-8	2/5/2021	856.23	6 - 8 ft	180-116914-1	Not Excavated	< 0.099 U	< 0.058 U	< 0.093 U	< 0.25 U	< 0.21 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-8-10	2/5/2021	856.23	8 - 10 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0012 U	0.0052 J	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-2-4	2/5/2021	856.18	2 - 4 ft	180-116914-1	Excavated	< 0.0019 U	< 0.0011 U	0.017	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-10-12	2/5/2021	856.18	10 - 12 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-12-14	2/5/2021	856.18	12 - 14 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.001 U	0.017	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-14-16	2/5/2021	856.18	14 - 16 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.003 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3581	DUP-33	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0083 J	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-4-6	2/5/2021	856.18	4 - 6 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0012 U	0.022 J	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-6-8	2/5/2021	856.18	6 - 8 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.018	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3581	SSHS-B3581-SUB-8-10	2/5/2021	856.18	8 - 10 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0055	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-10-12	2/5/2021	855.93	10 - 12 ft	180-116914-1	Not Excavated	< 0.091 U	< 0.054 U	< 0.085 U	< 0.23 U	< 0.2 U	< 0.097 U	< 0.11 U	< 0.39 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-12-14	2/5/2021	855.93	12 - 14 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.025	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3582	DUP-35	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.026	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-14-16	2/5/2021	855.93	14 - 16 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.017	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3582	DUP-34	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-2-4	2/5/2021	855.93	2 - 4 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-4-6	2/5/2021	855.93	4 - 6 ft	180-116914-1	Not Excavated	< 0.1 U	< 0.06 U	< 0.095 U	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-6-8	2/5/2021	855.93	6 - 8 ft	180-116914-1	Not Excavated	< 0.11 U	< 0.064 U	< 0.1 U	< 0.27 U	< 0.23 U	< 0.12 U	< 0.13 U	< 0.47 U
Football Field	SSHS-B3582	SSHS-B3582-SUB-8-10	2/5/2021	855.93	8 - 10 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.001 U	0.0032 J	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-10-12	2/5/2021	855.33	10 - 12 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.001 U	0.011	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-12-14	2/5/2021	855.33	12 - 14 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.001 U	0.0065	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3583	DUP-36	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.0055 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-14-16	2/5/2021	855.33	14 - 16 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0049 J	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-2-4	2/5/2021	855.33	2 - 4 ft	180-116914-1	Not Excavated	< 0.1 U	< 0.061 U	< 0.097 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-4-6	2/5/2021	855.33	4 - 6 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.005 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-6-8	2/5/2021	855.33	6 - 8 ft	180-116914-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.05	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3583	SSHS-B3583-SUB-8-10	2/5/2021	855.33	8 - 10 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.001 U	0.0051	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Football Field	SSHS-B3593	SSHS-B3593-SUB-2-4	2/4/2021	854.95	2 - 4 ft	180-116864-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3598	SSHS-B3598-SUB-2-4	2/4/2021	854.90	2 - 4 ft	180-116864-1	Excavated	< 0.0019 U	< 0.0012 U	0.032	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3599	DUP-38	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.44 U
Football Field	SSHS-B3599	SSHS-B3599-SUB-2-4	2/4/2021	855.25	2 - 4 ft	180-116864-1	Excavated	< 0.034 U	< 0.034 U	0.013	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4	1/29/2021	856.95	2 - 4 ft	1801166654	Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	0.0033 J	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-2-4	9/17/2021	856.64	2 - 4 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0012 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-4-6	9/17/2021	856.64	4 - 6 ft	180-127265-1	Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00085 U	< 0.034 U	< 0.00085 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	10 - 12 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0011 J	< 0.034 U	0.0011 J
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	14 - 16 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0012 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.00091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00099 U	< 0.034 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.021 U	< 0.0053 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	< 0.0048 UJ	< 0.00028 U	< 0.00041 U	< 0.00076 U	< 0.0028 U	< 0.00051 U	< 0.0028 U	< 0.00055 U	< 0.00075 U	< 0.00072 U	< 0.0013 U	< 0.00035 U	< 0.00034 U	< 0.00079 U	< 0.0028 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	< 0.0048 U	< 0.00028 U	< 0.00041 U	< 0.00077 U	< 0.0029 U	< 0.00052 U	< 0.0029 U	< 0.00056 U	< 0.00076 U	< 0.00074 U	< 0.0013 U	< 0.00036 U	< 0.00035 U	< 0.0008 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	0.026 J	< 0.00051 U	< 0.00076 U	< 0.0014 U	< 0.0053 U	< 0.00095 U	< 0.0053 U	< 0.001 U	< 0.0014 U	< 0.0013 U	< 0.0024 U	< 0.00065 U	< 0.00063 U	< 0.0015 U	< 0.0053 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.0036 U	< 0.00021 U	< 0.00031 U	< 0.00057 U	< 0.0021 U	< 0.00038 U	< 0.0021 U	< 0.00041 U	< 0.00056 U	< 0.00054 U	< 0.00096 U	< 0.00026 U	< 0.00026 U	< 0.00059 U	< 0.0021 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.006 U	< 0.00035 U	< 0.00052 U	< 0.00096 U	< 0.0036 U	< 0.00064 U	< 0.0036 U	< 0.00069 U	< 0.00094 U	< 0.00091 U	< 0.0016 U	< 0.00044 U	< 0.00043 U	< 0.001 U	< 0.0036 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.00024 U	< 0.00035 U	< 0.00064 U	< 0.0024 U	< 0.00043 U	< 0.0024 U	< 0.00047 U	< 0.00063 U	< 0.00062 U	< 0.0011 U	< 0.0003 U	< 0.00029 U	< 0.00067 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.00025 U	< 0.00036 U	< 0.00067 U	< 0.0025 U	< 0.00045 U	< 0.0025 U	< 0.00049 U	< 0.00066 U	< 0.00064 U	< 0.0011 U	< 0.00031 U	< 0.0003 U	< 0.0007 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	14 - 16 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0029 U	< 0.0052 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	0.0059 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.26 U	< 0.095 U	< 0.2 U	< 0.16 U	< 0.17 U	< 0.15 U	< 0.27 U	< 0.14 U	< 0.088 U	< 0.17 U	< 0.2 U	< 0.11 U	< 0.13 U	< 0.16 U	< 0.22 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 1.9 U	< 0.7 U	< 1.5 U	< 1.2 U	< 1.3 U	< 1.1 U	< 2 U	< 1 U	< 0.65 U	< 1.2 U	< 1.5 U	< 0.8 U	< 0.99 U	< 1.2 U	< 1.6 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 1.9 U	< 0.7 U	< 1.5 U	< 1.2 U	< 1.3 U	< 1.1 U	< 2 U	< 1 U	< 0.65 U	< 1.2 U	< 1.5 U	< 0.8 U	< 0.99 U	< 1.2 U	< 1.6 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	0.022	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3930A	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	8 - 10 ft	180-123399-1	Not Excavated	< 0.0065 U	< 0.00054 U	< 0.00065 U	< 0.00043 U	< 0.0054 U	< 0.00075 U	< 0.00065 U	< 0.00054 U	< 0.00054 U	< 0.00054 U	< 0.0011 U	< 0.00065 U	< 0.00065 U	< 0.00054 U	< 0.00054 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-4-6	6/17/2021	856.63	4 - 6 ft	180-123399-1	Excavated	0.0074 J	< 0.0004 U	< 0.00048 U	< 0.00032 U	< 0.004 U	< 0.00055 U	< 0.00048 U	< 0.0004 U	< 0.0004 U	< 0.0004 U	< 0.00079 U	< 0.00048 U	< 0.00048 U	< 0.0004 U	< 0.0004 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-10-12	6/17/2021	856.63	10 - 12 ft	180-123399-1	Not Excavated	0.015 J	< 0.00049 U	< 0.00059 U	< 0.0004 U	< 0.0049 U	< 0.00069 U	< 0.00059 U	< 0.00049 U	< 0.00049 U	< 0.00049 U	< 0.00099 U	< 0.00059 U	< 0.00059 U	< 0.00049 U	< 0.00049 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-6-8	6/17/2021	856.63	6 - 8 ft	180-123399-1	Not Excavated	< 0.0057 U	< 0.00047 U	< 0.00057 U	< 0.00038 U	< 0.0047 U	< 0.00066 U	< 0.00057 U	< 0.00047 U	< 0.00047 U	< 0.00047 U	< 0.00095 U	< 0.00057 U	< 0.00057 U	< 0.00047 U	< 0.00047 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-8-10	6/17/2021	856.63	8 - 10 ft	180-123399-1	Not Excavated	0.028	< 0.00052 U	< 0.00062 U	< 0.00041 U	< 0.0052 U	< 0.00072 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00062 U	< 0.00062 U	0.0008 J	< 0.00052 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-4-6	6/17/2021	857.09	4 - 6 ft	180-123399-1	Excavated	< 0.34 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.28 U	< 0.039 U,*+	< 0.034 U	< 0.11 U	< 0.028 U	< 0.11 U	< 0.056 U	< 0.034 U	< 0.034 U	< 0.028 U	< 0.056 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-10-12	6/17/2021	857.09	10 - 12 ft	180-123399-1	Not Excavated	< 0.0062 U	< 0.00052 U	< 0.00062 U	< 0.00041 U	< 0.0052 U	< 0.00073 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00062 U	< 0.00062 U	< 0.00052 U	< 0.00052 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-6-8	6/17/2021	857.09	6 - 8 ft	180-123399-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.032 U	< 0.021 U	< 0.27 U	< 0.038 U,*+	< 0.032 U	< 0.11 U	< 0.027 U	< 0.11 U	< 0.054 U	< 0.032 U	< 0.032 U	< 0.027 U	< 0.054 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-8-10	6/17/2021	857.09	8 - 10 ft	180-123399-1	Not Excavated	< 0.0063 U	< 0.00053 U	< 0.00063 U	< 0.00042 U	< 0.0053 U	< 0.00074 U	< 0.00063 U	< 0.00053 U	< 0.00053 U	< 0.00053 U	< 0.0011 U	< 0.00063 U	< 0.00063 U	< 0.00053 U	< 0.00053 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-10-12	6/17/2021	856.55	10 - 12 ft	180-123399-1	Not Excavated	0.13	< 0.00064 U	< 0.00077 U	< 0.00051 U	< 0.0064 U	< 0.0009 U	< 0.00077 U	< 0.00064 U	< 0.00064 U	< 0.00064 U	< 0.0013 U	< 0.00077 U	< 0.00077 U	< 0.00064 U	< 0.00064 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-4-6	6/17/2021	856.55	4 - 6 ft	180-123399-1	Not Excavated	< 0.55 U	< 0.046 U	< 0.055 U	< 0.037 U	< 0.46 U	< 0.064 U,*+	< 0.055 U	< 0.18 U	< 0.046 U	< 0.18 U	< 0.092 U	< 0.055 U	< 0.055 U	< 0.046 U	< 0.092 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-6-8	6/17/2021	856.55	6 - 8 ft	180-123399-1	Not Excavated	0.031 H	< 0.00049 U,H	< 0.00059 U,H	< 0.00039 U,H	< 0.0049 U,H	< 0.00069 U,H	< 0.00059 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00098 U,H	< 0.00059 U,H	< 0.00059 U,H	< 0.00049 U,H	< 0.00049 U,H
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-8-10	6/17/2021	856.55	8 - 10 ft	180-123399-1	Not Excavated	< 0.0062 U	< 0.00052 U	< 0.00062 U	< 0.00041 U	< 0.0052 U	< 0.00072 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00062 U	< 0.00062 U	< 0.00052 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-4-6	6/17/2021	856.72	4 - 6 ft	180-123399-1	Excavated	< 0.41 U	< 0.034 U	< 0.041 U	< 0.027 U	< 0.34 U	< 0.048 U	< 0.041 U	< 0.14 U	< 0.034 U	< 0.14 U	< 0.068 U	< 0.041 U	< 0.041 U	< 0.034 U	< 0.068 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-10-12	6/17/2021	856.72	10 - 12 ft	180-123399-1	Not Excavated	< 0.0063 U	< 0.00052 U	< 0.00063 U	< 0.00042 U	< 0.0052 U	< 0.00073 U	< 0.00063 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00063 U	< 0.00063 U	< 0.00052 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-6-8	6/17/2021	856.72	6 - 8 ft	180-123399-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.032 U	< 0.021 U	< 0.27 U	< 0.037 U,*+	< 0.032 U	< 0.11 U	< 0.027 U	< 0.11 U	< 0.053 U	< 0.032 U	< 0.032 U	< 0.027 U	< 0.053 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-8-10	6/17/2021	856.72	8 - 10 ft	180-123399-1	Not Excavated	< 0.0058 U	< 0.00048 U	< 0.00058 U	< 0.00039 U	< 0.0048 U	< 0.00068 U	< 0.00058 U	< 0.00048 U	< 0.00048 U	< 0.00048 U	< 0.00097 U	< 0.00058 U	< 0.00058 U	< 0.00048 U	< 0.00048 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-4-6	6/17/2021	856.53	4 - 6 ft	180-123399-1	Excavated	< 0.42 U	< 0.035 U	< 0.042 U	< 0.028 U	< 0.35 U	< 0.049 U	< 0.042 U	< 0.14 U	< 0.035 U	< 0.14 U	< 0.07 U	< 0.042 U	< 0.042 U	< 0.035 U	< 0.07 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-6-8	6/17/2021	856.53	6 - 8 ft	180-123399-1	Not Excavated	< 0.0077 U	< 0.00065 U	< 0.00077 U	< 0.00052 U	< 0.0065 U	< 0.0009 U	< 0.00077 U	< 0.00065 U	< 0.00065 U	< 0.00065 U	< 0.0013 U	< 0.00077 U	< 0.00077 U	< 0.00065 U	< 0.00065 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated	< 0.0043 UJ	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	10 - 12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00057 U	< 0.00055 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0006 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	858.24	12 - 14 ft	180-127265-2	Not Excavated	0.019 J	0.00033 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	14 - 16 ft	180-127265-2	Not Excavated	0.012 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00066 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	2 - 4 ft	180-127265-2	Not Excavated	0.024	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0005 U	< 0.00049 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00053 U	< 0.034 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00099 U	< 0.034 U	< 0.00035 U	< 0.034 U	< 0.034 U	< 0.00091 U	< 0.00073 U	< 0.034 U	< 0.001 U	< 0.0031 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.0053 U			< 0.35 U	< 0.35 U	< 0.35 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	< 0.0026 U	< 0.00073 U	< 0.00047 U	< 0.00044 U	< 0.00029 U	< 0.00079 U	< 0.00069 U	< 0.00028 U	< 0.00069 U	< 0.003 U	< 0.00072 U	< 0.00058 U	< 0.0028 U	< 0.00081 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	< 0.0026 U	< 0.00074 U	< 0.00047 U	< 0.00045 U	< 0.0003 U	< 0.0008 U	< 0.0007 U	< 0.00029 U	< 0.0007 U	< 0.003 U	< 0.00074 U	< 0.00059 U	< 0.0029 U	< 0.00083 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	< 0.0048 U	< 0.0013 U	< 0.00087 U	< 0.00082 U	< 0.00054 U	< 0.0015 U	< 0.0013 U	< 0.00053 U	< 0.0013 U	< 0.0055 U	< 0.0013 U	< 0.0011 U	< 0.0053 U	< 0.0015 U	< 0.0046 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.00055 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00059 U	< 0.00052 U	< 0.00021 U	< 0.00052 U	< 0.0022 U	< 0.00054 U	< 0.00044 U	< 0.0021 U	< 0.00061 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.0033 U	< 0.00092 U	< 0.00059 U	< 0.00056 U	< 0.00037 U	< 0.001 U	< 0.00087 U	< 0.00036 U	< 0.00087 U	< 0.0037 U	< 0.00091 U	< 0.00074 U	< 0.0036 U	< 0.001 U	< 0.0031 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.0022 U	< 0.00062 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00067 U	< 0.00059 U	< 0.00024 U	< 0.00059 U	< 0.0025 U	< 0.00062 U	< 0.0005 U	< 0.0024 U	< 0.00069 U	< 0.0021 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.0023 U	< 0.00065 U	< 0.00042 U	< 0.00039 U	< 0.00026 U	< 0.0007 U	< 0.00061 U	< 0.00025 U	< 0.00062 U	< 0.0026 U	< 0.00064 U	< 0.00052 U	< 0.0025 U	< 0.00072 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	14 - 16 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	0.0058	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.3 U	< 0.092 U	< 0.17 U	< 0.11 U	< 0.21 U	< 0.1 U	< 0.11 U	< 0.097 U	< 0.15 U	< 0.27 U	< 0.1 U	< 0.12 U	< 0.09 U	< 0.15 U	< 0.15 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 2.3 U	< 0.68 U	< 1.2 U	< 0.84 U	< 1.5 U	< 0.75 U	< 0.8 U	< 0.72 U	< 1.1 U	< 2 U	< 0.75 U	< 0.87 U	< 0.66 U	< 1.1 U	< 1.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 2.3 U	< 0.68 U	< 1.2 U	< 0.84 U	< 1.5 U	< 0.75 U	< 0.8 U	< 0.72 U	< 1.1 U	< 2 U	< 0.75 U	< 0.87 U	< 0.66 U	< 1.1 U	< 1.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930A	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	8 - 10 ft	180-123399-1	Not Excavated	< 0.0022 U	< 0.00043 U	< 0.00065 U	< 0.00054 U	< 0.00054 U	< 0.00043 U	< 0.00054 U	< 0.00065 U	< 0.00054 U	< 0.0011 U	< 0.00054 U	< 0.00054 U	< 0.00054 U	< 0.00043 U	< 0.00054 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-4-6	6/17/2021	856.63	4 - 6 ft	180-123399-1	Excavated	< 0.0016 U	< 0.00032 U	< 0.00048 U	< 0.0004 U	< 0.0004 U	< 0.00032 U	< 0.0004 U	< 0.00048 U	< 0.0004 U	< 0.00079 U	< 0.0004 U	< 0.0004 U	< 0.0004 U	< 0.00032 U	< 0.0004 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-10-12	6/17/2021	856.63	10 - 12 ft	180-123399-1	Not Excavated	< 0.002 U	< 0.0004 U	< 0.00059 U	< 0.00049 U	< 0.00049 U	< 0.0004 U	< 0.00049 U	< 0.00059 U	< 0.00049 U	< 0.00099 U	< 0.00049 U	< 0.00049 U	< 0.00049 U	< 0.0004 U	< 0.00049 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-6-8	6/17/2021	856.63	6 - 8 ft	180-123399-1	Not Excavated	< 0.0019 U	< 0.00038 U	< 0.00057 U	< 0.00047 U	< 0.00047 U	< 0.00038 U	< 0.00047 U	< 0.00057 U	< 0.00047 U	< 0.00095 U	< 0.00047 U	< 0.00047 U	< 0.00047 U	< 0.00038 U	< 0.00047 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-8-10	6/17/2021	856.63	8 - 10 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00041 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00062 U	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-4-6	6/17/2021	857.09	4 - 6 ft	180-123399-1	Excavated	< 0.11 U	< 0.023 U	< 0.034 U	< 0.028 U	< 0.028 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.028 U	< 0.056 U	< 0.028 U	< 0.028 U	< 0.028 U	< 0.023 U	< 0.028 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-10-12	6/17/2021	857.09	10 - 12 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00041 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00062 U	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-6-8	6/17/2021	857.09	6 - 8 ft	180-123399-1	Not Excavated	< 0.11 U	< 0.021 U	< 0.032 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U	< 0.032 U	< 0.027 U	< 0.054 U	< 0.027 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-8-10	6/17/2021	857.09	8 - 10 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00042 U	< 0.00063 U	< 0.00053 U	< 0.00053 U	< 0.00042 U	< 0.00053 U	< 0.00063 U	< 0.00053 U	< 0.0011 U	< 0.00053 U	< 0.00053 U	< 0.00053 U	< 0.00042 U	< 0.00053 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-10-12	6/17/2021	856.55	10 - 12 ft	180-123399-1	Not Excavated	< 0.0026 U	< 0.00051 U	< 0.00077 U	< 0.00064 U	< 0.00064 U	< 0.00051 U	< 0.00064 U	< 0.00077 U	< 0.00064 U	< 0.0013 U	< 0.00064 U	< 0.00064 U	< 0.00064 U	< 0.00051 U	< 0.00064 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-4-6	6/17/2021	856.55	4 - 6 ft	180-123399-1	Not Excavated	< 0.18 U	< 0.037 U	< 0.055 U	< 0.046 U	< 0.046 U	< 0.037 U	< 0.046 U	< 0.055 U	< 0.046 U	< 0.092 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-6-8	6/17/2021	856.55	6 - 8 ft	180-123399-1	Not Excavated	< 0.002 U,H	< 0.00039 U,H	< 0.00059 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00039 U,H	< 0.00049 U,H	< 0.00059 U,H	< 0.00049 U,H	< 0.00098 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00039 U,H	< 0.00049 U,H
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-8-10	6/17/2021	856.55	8 - 10 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00041 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00062 U	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-4-6	6/17/2021	856.72	4 - 6 ft	180-123399-1	Excavated	< 0.14 U	< 0.027 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.068 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.027 U	< 0.034 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-10-12	6/17/2021	856.72	10 - 12 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00042 U	< 0.00063 U	< 0.00052 U	< 0.00052 U	< 0.00042 U	< 0.00052 U	< 0.00063 U	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00042 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-6-8	6/17/2021	856.72	6 - 8 ft	180-123399-1	Not Excavated	< 0.11 U	< 0.021 U	< 0.032 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U	< 0.032 U	< 0.027 U	< 0.053 U	< 0.027 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-8-10	6/17/2021	856.72	8 - 10 ft	180-123399-1	Not Excavated	< 0.0019 U	< 0.00039 U	< 0.00058 U	< 0.00048 U	< 0.00048 U	< 0.00039 U	< 0.00048 U	< 0.00058 U	< 0.00048 U	< 0.00097 U	< 0.00048 U	< 0.00048 U	< 0.00048 U	< 0.00039 U	< 0.00048 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-4-6	6/17/2021	856.53	4 - 6 ft	180-123399-1	Excavated	< 0.14 U	< 0.028 U	< 0.042 U	< 0.035 U	< 0.035 U	< 0.028 U	< 0.035 U	< 0.042 U	< 0.035 U	< 0.07 U	< 0.035 U	< 0.035 U	< 0.035 U	< 0.028 U	< 0.035 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-6-8	6/17/2021	856.53	6 - 8 ft	180-123399-1	Not Excavated	< 0.0026 U	< 0.00052 U	< 0.00077 U	< 0.00065 U	< 0.00065 U	< 0.00052 U	< 0.00065 U	< 0.00077 U	< 0.00065 U	< 0.0013 U	< 0.00065 U	< 0.00065 U	< 0.00065 U	< 0.00052 U	< 0.00065 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	10 - 12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00055 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0006 U	< 0.034 U	< 0.00022 U	< 0.034 U	< 0.034 U	< 0.00055 U	< 0.00044 U	< 0.034 U	< 0.00062 U	< 0.0019 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	858.24	12 - 14 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U	< 0.00028 U	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.00057 U	< 0.034 U	< 0.0008 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	14 - 16 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U	< 0.00025 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.00051 U	< 0.034 U	< 0.00072 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	2 - 4 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00049 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00053 U	< 0.034 U	< 0.00019 U	< 0.034 U	< 0.034 U	< 0.00049 U	< 0.00039 U	< 0.034 U	< 0.00055 U	< 0.0017 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated	< 0.00049 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.00069 U	< 0.00035 U	< 0.034 U	< 0.00095 U	< 0.00053 U	< 0.034 U	< 0.00043 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		< 0.35 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	< 0.00039 U	< 0.0013 U	< 0.0028 U	< 0.00085 U	< 0.0034 UJ	< 0.00086 UJ	< 0.0021 U	< 0.0019 U	< 0.00055 U	< 0.00028 U	< 0.00092 U	< 0.00076 U	< 0.00043 U	< 0.0006 U	< 0.00034 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	< 0.0004 U	< 0.0013 U	< 0.0029 U	< 0.00087 U	< 0.0035 U	< 0.00087 U	< 0.0021 U	< 0.0019 U	< 0.00056 U	< 0.00029 U	< 0.00093 U	< 0.00077 U	< 0.00043 U	< 0.00061 U	< 0.00035 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	< 0.00072 U	< 0.0024 U	< 0.0053 U	< 0.0016 U	< 0.0063 U	< 0.0016 U	< 0.0038 U	< 0.0034 U	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.0014 U	< 0.00079 U	< 0.0011 U	< 0.00064 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.00029 U	< 0.00097 U	< 0.0021 U	< 0.00064 U	< 0.0026 U	< 0.00065 U	< 0.0016 U	< 0.0014 U	< 0.00042 U	< 0.00021 U	< 0.00069 U	< 0.00057 U	< 0.00032 U	< 0.00045 U	< 0.00026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.00049 U	< 0.0016 U	< 0.0036 U	< 0.0011 U	< 0.0043 U	< 0.0011 U	< 0.0026 U	< 0.0023 U	< 0.0007 U	< 0.00036 U	< 0.0012 U	< 0.00096 U	< 0.00054 U	< 0.00076 U	< 0.00043 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.00033 U	< 0.0011 U	< 0.0024 U	< 0.00072 U	< 0.0029 U	< 0.00073 U	< 0.0018 U	< 0.0016 U	< 0.00047 U	< 0.00024 U	< 0.00078 U	< 0.00064 U	0.00037 J	< 0.00051 U	< 0.00029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.00035 U	< 0.0011 U	< 0.0025 U	< 0.00076 U	< 0.003 U	< 0.00076 U	< 0.0018 U	< 0.0016 U	< 0.00049 U	< 0.00025 U	< 0.00082 U	< 0.00067 U	< 0.00038 U	< 0.00053 U	< 0.00031 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	14 - 16 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.12 U	< 0.13 U	< 0.11 U	< 0.18 U	< 0.5 U	< 0.16 U	< 0.17 U	< 0.12 U	< 0.099 U	< 0.1 U	< 0.1 U	< 0.14 U	< 0.097 U	< 0.19 U	< 0.17 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	1.8 J	< 1 U	< 0.78 U	< 1.3 UT	< 3.7 U	< 1.2 U	< 1.3 U	< 0.91 U	< 0.73 U	< 0.75 U	< 0.76 U	< 1 U	< 0.72 UT	< 1.4 U	< 1.3 UT
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	0.015	< 0.0022 U	< 0.0017 U	< 0.0029 U	0.018 J	0.0058	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	1.9 J	< 1 U	< 0.78 U	< 1.3 UT	< 3.7 U	< 1.2 U	< 1.3 U	< 0.91 U	< 0.73 U	< 0.75 U	< 0.76 U	< 1 U	< 0.72 UT	< 1.4 U	< 1.3 UT
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3930A	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	8 - 10 ft	180-123399-1	Not Excavated	< 0.00043 U	< 0.00065 U	< 0.0011 U	< 0.00043 U	< 0.0011 U,*+	< 0.00065 U	< 0.0022 U	< 0.0011 U	< 0.00054 U	< 0.00043 U	< 0.00043 U	< 0.00054 U	< 0.00065 U	< 0.0054 U	< 0.0054 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-4-6	6/17/2021	856.63	4 - 6 ft	180-123399-1	Excavated	< 0.00032 U	< 0.00048 U	< 0.00079 U	< 0.00032 U	< 0.00079 U,*+	< 0.00048 U	< 0.0016 U	< 0.00079 U	< 0.0004 U	< 0.00032 U	< 0.00032 U	< 0.0004 U	< 0.00048 U	< 0.004 U	< 0.004 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-10-12	6/17/2021	856.63	10 - 12 ft	180-123399-1	Not Excavated	< 0.0004 U	< 0.00059 U	< 0.00099 U	< 0.0004 U	< 0.00099 U	< 0.00059 U	< 0.002 U	< 0.00099 U	< 0.00049 U	< 0.0004 U	< 0.0004 U	< 0.00049 U	< 0.00059 U	< 0.0049 U	< 0.0049 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-6-8	6/17/2021	856.63	6 - 8 ft	180-123399-1	Not Excavated	< 0.00038 U	< 0.00057 U	< 0.00095 U	< 0.00038 U	< 0.00095 U	< 0.00057 U	< 0.0019 U	< 0.00095 U	< 0.00047 U	< 0.00038 U	< 0.00038 U	< 0.00047 U	< 0.00057 U	< 0.0047 U	< 0.0047 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-8-10	6/17/2021	856.63	8 - 10 ft	180-123399-1	Not Excavated	< 0.00041 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.001 U	0.0012 J	< 0.0021 U	< 0.001 U	< 0.00052 U	< 0.00041 U	< 0.00041 U	0.00082 J	0.00084 J	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-4-6	6/17/2021	857.09	4 - 6 ft	180-123399-1	Excavated	< 0.023 U	< 0.034 U	< 0.056 U	< 0.023 U	< 0.056 U	< 0.034 U	< 0.11 U	< 0.056 U	< 0.028 U	< 0.023 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.28 U	< 0.28 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-10-12	6/17/2021	857.09	10 - 12 ft	180-123399-1	Not Excavated	< 0.00041 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.001 U	< 0.00062 U	< 0.0021 U	< 0.001 U	< 0.00052 U	< 0.00041 U	< 0.00041 U	0.00066 J	< 0.00062 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-6-8	6/17/2021	857.09	6 - 8 ft	180-123399-1	Not Excavated	< 0.021 U	< 0.032 U	< 0.054 U	< 0.021 U	< 0.054 U	< 0.032 U	< 0.11 U	< 0.054 U	< 0.027 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.032 U	< 0.27 U	< 0.27 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-8-10	6/17/2021	857.09	8 - 10 ft	180-123399-1	Not Excavated	< 0.00042 U	< 0.00063 U	< 0.0011 U	< 0.00042 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0011 U	< 0.00053 U	< 0.00042 U	< 0.00042 U	< 0.00053 U	< 0.00063 U	< 0.0053 U	< 0.0053 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-10-12	6/17/2021	856.55	10 - 12 ft	180-123399-1	Not Excavated	< 0.00051 U	< 0.00077 U	< 0.0013 U	< 0.00051 U	0.042	< 0.00077 U	0.0056 J	< 0.0013 U	< 0.00064 U	< 0.00051 U	< 0.00051 U	< 0.00064 U	< 0.00077 U	< 0.0064 U	< 0.0064 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-4-6	6/17/2021	856.55	4 - 6 ft	180-123399-1	Not Excavated	< 0.037 U	< 0.055 U	< 0.092 U	< 0.037 U	< 0.092 U	< 0.055 U	< 0.18 U	< 0.092 U	< 0.046 U	< 0.037 U	< 0.037 U	< 0.046 U	< 0.055 U	< 0.46 U	< 0.46 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-6-8	6/17/2021	856.55	6 - 8 ft	180-123399-1	Not Excavated	< 0.00039 U,H	< 0.00059 U,H	< 0.00098 U,H	< 0.00039 U,H	< 0.00098 U,H	< 0.00059 U,H	0.0027 J	< 0.00098 U,H	< 0.00049 U,H	< 0.00039 U,H	< 0.00039 U,H	< 0.00049 U,H	< 0.00059 U,H	< 0.0049 U,H	< 0.0049 U,H
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-8-10	6/17/2021	856.55	8 - 10 ft	180-123399-1	Not Excavated	< 0.00041 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.001 U	< 0.00062 U	< 0.0021 U	< 0.001 U	< 0.00052 U	< 0.00041 U	< 0.00041 U	< 0.00052 U	< 0.00062 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-4-6	6/17/2021	856.72	4 - 6 ft	180-123399-1	Excavated	0.068 J	< 0.041 U	< 0.068 U	< 0.027 U	< 0.068 U	< 0.041 U	< 0.14 U	< 0.068 U	< 0.034 U	< 0.027 U	< 0.027 U	< 0.034 U	< 0.041 U	< 0.34 U	< 0.34 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-10-12	6/17/2021	856.72	10 - 12 ft	180-123399-1	Not Excavated	< 0.00042 U	< 0.00063 U	< 0.001 U	< 0.00042 U	< 0.001 U	< 0.00063 U	< 0.0021 U	< 0.001 U	< 0.00052 U	< 0.00042 U	< 0.00042 U	0.00074 J	< 0.00063 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-6-8	6/17/2021	856.72	6 - 8 ft	180-123399-1	Not Excavated	0.11 J	< 0.032 U	< 0.053 U	< 0.021 U	< 0.053 U	< 0.032 U	< 0.11 U	< 0.053 U	< 0.027 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.032 U	< 0.27 U	< 0.27 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-8-10	6/17/2021	856.72	8 - 10 ft	180-123399-1	Not Excavated	< 0.00039 U	< 0.00058 U	< 0.00097 U	< 0.00039 U	< 0.00097 U	0.00066 J	< 0.0019 U	< 0.00097 U	< 0.00048 U	< 0.00039 U	< 0.00039 U	< 0.00048 U	< 0.00058 U	< 0.0048 U	< 0.0048 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-4-6	6/17/2021	856.53	4 - 6 ft	180-123399-1	Excavated	< 0.028 U	< 0.042 U	< 0.07 U	< 0.028 U	< 0.07 U	< 0.042 U	< 0.14 U	< 0.07 U	< 0.035 U	< 0.028 U	< 0.028 U	< 0.035 U	< 0.042 U	< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-6-8	6/17/2021	856.53	6 - 8 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00077 U	< 0.0013 U	< 0.00052 U	< 0.0013 U	0.00087 J	< 0.0026 U	< 0.0013 U	< 0.00065 U	< 0.00052 U	< 0.00052 U	< 0.00065 U	0.00093 J	< 0.0065 U	< 0.0065 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 UJ	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	10 - 12 ft	180-127265-2	Not Excavated	< 0.0003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.034 U	< 0.0014 U	< 0.00042 U	< 0.00022 U	< 0.034 U	< 0.00058 U	< 0.00033 U	< 0.034 U	< 0.00026 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	858.24	12 - 14 ft	180-127265-2	Not Excavated	< 0.00038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.0018 U	< 0.00054 U	< 0.00028 U	< 0.034 U	< 0.00074 U	0.00067 J	< 0.034 U	< 0.00034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	14 - 16 ft	180-127265-2	Not Excavated	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.0016 U	< 0.00049 U	< 0.00025 U	< 0.034 U	< 0.00067 U	0.00044 J	< 0.034 U	< 0.0003 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	2 - 4 ft	180-127265-2	Not Excavated	< 0.00026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00058 U	< 0.034 U	< 0.0012 U	< 0.00037 U	< 0.00019 U	< 0.034 U	< 0.00051 U	< 0.00029 U	< 0.034 U	< 0.00023 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	8 - 10 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0012 U
Northern Athletic Field	SSHS-B37	12 Sep 00B37_8-10	9/12/2000	856.46	8 - 10 ft	NA	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-2-4	9/16/2021	856.07	2 - 4 ft	180-127205-2	Excavated	< 0.00041 U	< 0.00073 U	< 0.0012 U	< 0.00053 U	< 0.00069 U	< 0.00095 U	< 0.00074 U	< 0.00095 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-4-6	9/16/2021	856.07	4 - 6 ft	180-127205-2	Excavated	< 0.00042 U	< 0.00075 U	< 0.0013 U	< 0.00054 U	< 0.0007 U	< 0.00097 U	< 0.00075 U	< 0.00097 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-6-8	9/16/2021	856.07	6 - 8 ft	180-127205-2	Excavated	< 0.00076 U	< 0.0014 U	< 0.0023 U	< 0.00099 U	< 0.0013 U	< 0.0018 U	< 0.0014 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	10 - 12 ft	180-127205-2	Not Excavated	< 0.00031 U	< 0.00055 U	< 0.00093 U	< 0.0004 U	< 0.00052 U	< 0.00071 U	< 0.00055 U	< 0.00071 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	12 - 14 ft	180-127205-2	Not Excavated	< 0.00052 U	< 0.00093 U	< 0.0016 U	< 0.00068 U	< 0.00087 U	< 0.0012 U	< 0.00093 U	< 0.0012 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	14 - 16 ft	180-127205-2	Not Excavated	< 0.00035 U	< 0.00062 U	< 0.0011 U	< 0.00045 U	< 0.00059 U	< 0.00081 U	< 0.00063 U	< 0.00081 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	8 - 10 ft	180-127205-2	Not Excavated	< 0.00036 U	< 0.00065 U	< 0.0011 U	< 0.00048 U	< 0.00061 U	< 0.00084 U	< 0.00066 U	< 0.00084 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	14 - 16 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	14 - 16 ft	1801219031	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.0020 U	< 0.0054 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	14 - 16 ft	1801215481	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	14 - 16 ft	1801215482	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4	5/12/2021	853.71	2 - 4 ft	1801215482	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6	5/12/2021	853.71	4 - 6 ft	1801215482	Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8	5/12/2021	853.71	6 - 8 ft	1801215482	Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10	5/12/2021	853.71	8 - 10 ft	1801215482	Excavated	< 0.0019 U	< 0.0011 U	0.0018 J	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12	5/12/2021	853.71	10 - 12 ft	1801215482	Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	4 - 6 ft	1801218221	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	6 - 8 ft	1801218221	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.11 U	< 0.067 U	< 0.11 U	< 0.28 U	< 0.24 U	< 0.12 U	< 0.14 U	< 0.49 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.83 U	< 0.49 U	< 0.78 U	< 2.1 U	< 1.8 U	10	4	14
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	0.0090	0.0033 J	0.012
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	0.081	0.033	0.11
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.83 U	< 0.49 U	< 0.78 U	< 2.1 U	< 1.8 U	11	4.1	15
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	0.0038 J	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	0.0019 J	0.0041 J	< 0.0075 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	0.0053	0.0021 J	< 0.0076 U
Northern Athletic Field	SSHS-B3930A	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	8 - 10 ft	180-123399-1	Not Excavated	< 0.00065 U	< 0.00054 U	< 0.00054 U	< 0.00075 U	< 0.00065 U	0.0014 J	0.00056 J	0.002 J
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-4-6	6/17/2021	856.63	4 - 6 ft	180-123399-1	Excavated	< 0.00048 U	< 0.0004 U	< 0.0004 U	< 0.00055 U	< 0.00048 U	< 0.00079 U	< 0.00032 U	< 0.0011 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-10-12	6/17/2021	856.63	10 - 12 ft	180-123399-1	Not Excavated	< 0.00059 U	< 0.00049 U	< 0.00049 U	< 0.00069 U	< 0.00059 U	< 0.00099 U	< 0.0004 U	< 0.0014 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-6-8	6/17/2021	856.63	6 - 8 ft	180-123399-1	Not Excavated	< 0.00057 U	< 0.00047 U	< 0.00047 U	< 0.00066 U	< 0.00057 U	< 0.00095 U	< 0.00038 U	< 0.0013 U
Northern Athletic Field	SSHS-B3931	SSHS-B3931-SUB-8-10	6/17/2021	856.63	8 - 10 ft	180-123399-1	Not Excavated	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00072 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.0014 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-4-6	6/17/2021	857.09	4 - 6 ft	180-123399-1	Excavated	< 0.034 U	< 0.028 U	< 0.028 U	< 0.039 U	< 0.034 U	< 0.056 U	< 0.023 U	< 0.079 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-10-12	6/17/2021	857.09	10 - 12 ft	180-123399-1	Not Excavated	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00073 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.0015 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-6-8	6/17/2021	857.09	6 - 8 ft	180-123399-1	Not Excavated	< 0.032 U	< 0.027 U	< 0.027 U	< 0.038 U	< 0.032 U	< 0.054 U	< 0.021 U	< 0.075 U
Northern Athletic Field	SSHS-B3932	SSHS-B3932-SUB-8-10	6/17/2021	857.09	8 - 10 ft	180-123399-1	Not Excavated	< 0.00063 U	< 0.00053 U	< 0.00053 U	< 0.00074 U	< 0.00063 U	< 0.0011 U	< 0.00042 U	< 0.0015 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-10-12	6/17/2021	856.55	10 - 12 ft	180-123399-1	Not Excavated	< 0.00077 U	< 0.00064 U	< 0.00064 U	< 0.0009 U	< 0.00077 U	< 0.0013 U	< 0.00051 U	< 0.0018 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-4-6	6/17/2021	856.55	4 - 6 ft	180-123399-1	Not Excavated	< 0.055 U	< 0.046 U	< 0.046 U	< 0.064 U	< 0.055 U	< 0.092 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-6-8	6/17/2021	856.55	6 - 8 ft	180-123399-1	Not Excavated	< 0.00059 U,H	< 0.00049 U,H	0.00089 J	< 0.00069 U,H	< 0.00059 U,*+,H	< 0.00098 U,H	< 0.00039 U,H	< 0.0014 U,H
Northern Athletic Field	SSHS-B3933	SSHS-B3933-SUB-8-10	6/17/2021	856.55	8 - 10 ft	180-123399-1	Not Excavated	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00072 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.0014 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-4-6	6/17/2021	856.72	4 - 6 ft	180-123399-1	Excavated	< 0.041 U	< 0.034 U	< 0.034 U	< 0.048 U	< 0.041 U	0.31 J	0.088 J	0.4 J
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-10-12	6/17/2021	856.72	10 - 12 ft	180-123399-1	Not Excavated	< 0.00063 U	< 0.00052 U	< 0.00052 U	< 0.00073 U	< 0.00063 U	< 0.001 U	< 0.00042 U	< 0.0015 U
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-6-8	6/17/2021	856.72	6 - 8 ft	180-123399-1	Not Excavated	< 0.032 U	< 0.027 U	< 0.027 U	< 0.037 U	< 0.032 U	0.51	0.14 J	0.65
Northern Athletic Field	SSHS-B3934	SSHS-B3934-SUB-8-10	6/17/2021	856.72	8 - 10 ft	180-123399-1	Not Excavated	< 0.00058 U	< 0.00048 U	< 0.00048 U	< 0.00068 U	< 0.00058 U	< 0.00097 U	< 0.00039 U	< 0.0014 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-4-6	6/17/2021	856.53	4 - 6 ft	180-123399-1	Excavated	< 0.042 U	< 0.035 U	< 0.035 U	< 0.049 U	< 0.042 U	< 0.07 U	< 0.028 U	< 0.098 U
Northern Athletic Field	SSHS-B3935	SSHS-B3935-SUB-6-8	6/17/2021	856.53	6 - 8 ft	180-123399-1	Not Excavated	< 0.00077 U	< 0.00065 U	< 0.00065 U	< 0.0009 U	< 0.00077 U	< 0.0013 U	< 0.00052 U	< 0.0018 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	2 - 4 ft	1801239851	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	2 - 4 ft	180-123985-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	10 - 12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00072 U	< 0.034 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-12-14	9/17/2021	858.24	12 - 14 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	14 - 16 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	2 - 4 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.00064 U

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	858.24	4 - 6 ft	180-127265-2	Not Excavated	0.019 J	0.0011 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00085 U	< 0.00082 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0009 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	6 - 8 ft	180-127265-2	Not Excavated	0.0077 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00089 U	< 0.00086 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00094 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	858.24	8 - 10 ft	180-127265-2	Not Excavated	0.0043 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	0.018 J	0.00039 J	< 0.0003 U	< 0.00055 U	< 0.0021 U	< 0.00037 U	< 0.0021 U	< 0.0004 U	< 0.00054 U	< 0.00053 U	< 0.00093 U	< 0.00025 U	< 0.00025 U	0.00063 J	< 0.0021 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.0028 U	< 0.00017 U	< 0.00024 U	< 0.00045 U	< 0.0017 U	< 0.0003 U	< 0.0017 U	< 0.00033 U	< 0.00044 U	< 0.00043 U	< 0.00076 U	< 0.00021 U	< 0.0002 U	< 0.00047 U	< 0.0017 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	0.018 J	< 0.00032 U	< 0.00047 U	< 0.00086 U	< 0.0032 U	< 0.00058 U	< 0.0032 U	< 0.00062 U	< 0.00085 U	< 0.00082 U	< 0.0015 U	< 0.0004 U	< 0.00039 U	< 0.0009 U	< 0.0032 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	< 0.004 U	< 0.00023 U	< 0.00034 U	< 0.00064 U	< 0.0024 U	< 0.00043 U	< 0.0024 U	< 0.00046 U	< 0.00063 U	< 0.00061 U	< 0.0011 U	< 0.00029 U	< 0.00029 U	< 0.00066 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.0046 U	< 0.00027 U	< 0.00039 U	< 0.00073 U	< 0.0027 U	< 0.00049 U	< 0.0027 U	< 0.00053 U	< 0.00072 U	< 0.0007 U	< 0.0012 U	< 0.00034 U	< 0.00033 U	< 0.00076 U	< 0.0027 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.0041 U	< 0.00024 U	< 0.00035 U	< 0.00065 U	< 0.0024 U	< 0.00044 U	< 0.0024 U	< 0.00047 U	< 0.00064 U	< 0.00062 U	< 0.0011 U	< 0.0003 U	< 0.00029 U	< 0.00068 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	0.0058 J	< 0.00024 U	< 0.00035 U	< 0.00065 U	< 0.0024 U	< 0.00044 U	< 0.0024 U	< 0.00047 U	< 0.00065 U	< 0.00063 U	< 0.0011 U	< 0.0003 U	< 0.0003 U	< 0.00068 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	0.084 J	< 0.00067 U	< 0.0012 U	< 0.0015 U	< 0.0023 U	< 0.004 U	< 0.0011 U	< 0.0031 U	< 0.00089 U	< 0.0027 U	< 0.0026 U	< 0.00076 U	< 0.0022 U	< 0.0013 U	< 0.0035 UJ
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.018 U	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.001 U	< 0.0029 U	< 0.0008 U	< 0.0024 U	< 0.0024 U	< 0.00069 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.018 U	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.001 U	< 0.0029 U	< 0.0008 U	< 0.0024 U	< 0.0024 U	< 0.00069 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.02 U	< 0.00065 U	< 0.0012 U	< 0.0014 U	< 0.0022 U	< 0.0039 U	< 0.0011 U	< 0.003 U	< 0.00086 U	< 0.0026 U	< 0.0026 U	< 0.00074 U	< 0.0021 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	< 0.023 U	< 0.00076 U	< 0.0014 U	< 0.0016 U	< 0.0026 U	< 0.0045 U	< 0.0013 U	< 0.0035 U	< 0.001 U	< 0.003 U	< 0.003 U	< 0.00086 U	< 0.0025 U	< 0.0015 U	< 0.0039 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.24 U	< 0.041 U	< 0.051 U	< 0.06 U	< 0.23 U	< 0.16 U	< 0.11 U	< 0.1 U	< 0.035 U	< 0.12 U	< 0.15 U	< 0.053 U	< 0.065 U	< 0.16 U	< 0.22 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.019 U	< 0.00063 U	< 0.0011 U	< 0.0014 U	< 0.0022 U	< 0.0038 U	< 0.0011 U	< 0.0029 U	< 0.00083 U	< 0.0025 U	< 0.0025 U	< 0.00071 U	< 0.0021 U	< 0.0012 U	< 0.0033 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.004 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0039 U	< 0.034 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated	0.052	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.0037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0036 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-2-4	9/23/2021	856.00	2 - 4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	0.22 J+	0.0056 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0025 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	0.062	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0055	< 0.034 U	< 0.00088 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	0.036 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00074 U	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 UJ	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-2-4	11/1/2021	852.29	2 - 4 ft	180-129325-1	Excavated	< 0.031 U	< 0.001 U	< 0.0018 U	< 0.0022 U	< 0.0036 U	< 0.0062 U	< 0.0017 U	< 0.0048 U	< 0.0014 U	< 0.0041 U	< 0.0041 U	< 0.0012 U	< 0.0034 U	< 0.002 U	< 0.0053 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-10-12	11/1/2021	852.29	10 - 12 ft	180-129325-1	Not Excavated	< 0.017 U	< 0.00056 U	< 0.001 U	< 0.0012 U	< 0.0019 U	< 0.0033 U	< 0.00094 U	< 0.0026 U	< 0.00074 U	< 0.0022 U	< 0.0022 U	< 0.00063 U	< 0.0018 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-12-14	11/1/2021	852.29	12 - 14 ft	180-129325-1	Not Excavated	0.022 J-	< 0.0005 UJ	< 0.00088 UJ	< 0.0011 UJ	< 0.0017 UJ	< 0.003 UJ	< 0.00083 UJ	< 0.0023 UJ	< 0.00065 UJ	< 0.002 UJ	< 0.002 UJ	< 0.00056 UJ	< 0.0016 UJ	< 0.00098 UJ	< 0.0026 UJ
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-14-16	11/1/2021	852.29	14 - 16 ft	180-129325-1	Not Excavated	< 0.016 U	< 0.00052 U	< 0.00092 U	< 0.0011 U	< 0.0018 U	< 0.0031 U	< 0.00086 U	< 0.0024 U	< 0.00068 U	< 0.0021 U	< 0.002 U	< 0.00058 U	< 0.0017 U	0.0013 J	< 0.0027 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-4-6	11/1/2021	852.29	4 - 6 ft	180-129325-1	Not Excavated	< 0.018 U	0.0025 J	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.001 U	< 0.0028 U	< 0.00079 U	< 0.0024 U	< 0.0024 U	< 0.00068 U	< 0.002 U	0.0034 J	< 0.0031 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-6-8	11/1/2021	852.29	6 - 8 ft	180-129325-1	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.0007 U	< 0.002 U	< 0.0012 U	< 0.0032 UJ
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-8-10	11/1/2021	852.29	8 - 10 ft	180-129325-1	Not Excavated	< 0.018 U	< 0.00058 U	< 0.001 U	< 0.0013 U	< 0.002 U	< 0.0035 U	< 0.00097 U	< 0.0027 U	< 0.00077 U	< 0.0023 U	< 0.0023 U	< 0.00066 U	< 0.0019 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.021	< 0.0052		< 0.0052	< 0.0052	< 0.0052	< 0.01	< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052		
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.022	< 0.0054		< 0.0054	< 0.0054	< 0.0054	< 0.011	< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054		
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B52	13 Sep 00B52 4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.022 U	< 0.0054 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		
Northern Athletic Field	SSHS-B54	13 Sep 00B54 4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	< 0.01	< 0.003	< 0.0014	< 0.002	< 0.0045	< 0.0017	< 0.0021	< 0.0013	< 0.0022	< 0.0024	< 0.0021	< 0.0012	< 0.0026	< 0.0015	< 0.0045
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	< 0.0099	< 0.0029	< 0.0014	< 0.0019	< 0.0044	< 0.0017	< 0.002	< 0.0013	< 0.0021	< 0.0024	< 0.0021	< 0.0012	< 0.0025	< 0.0014	< 0.0044
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	< 0.013	< 0.0039	< 0.0018	< 0.0026	< 0.0059	< 0.0022	< 0.0027	< 0.0018	< 0.0029	< 0.0032	< 0.0027	< 0.0016	< 0.0034	< 0.0019	< 0.0058
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.0041 U	< 0.00055 U	< 0.00056 U	< 0.00046 U	< 0.00036 U	< 0.0006 U	< 0.00042 U	< 0.00036 U	< 0.00062 U	< 0.00058 U	< 0.0013 U	< 0.00048 U	< 0.00069 U	< 0.0003 U	< 0.00061 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.0081 U	< 0.0011 U	< 0.0011 U	< 0.00091 U	< 0.00072 U	< 0.0012 U	< 0.00083 U	< 0.00072 U	< 0.0012 U	< 0.0011 U	< 0.0025 U	< 0.00095 U	< 0.0014 U	< 0.0006 U	< 0.0012 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.0042 U	< 0.00056 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.0013 U	< 0.00049 U	< 0.00071 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.004 U	< 0.00054 U	< 0.00055 U	< 0.00045 U	< 0.00036 U	< 0.00059 U	< 0.00041 U	< 0.00036 U	< 0.00061 U	< 0.00057 U	< 0.0012 U	< 0.00047 U	< 0.00069 U	< 0.0003 U	< 0.0006 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00068 U	< 0.00055 U	< 0.00043 U	< 0.00073 U	< 0.0005 U	< 0.00044 U	< 0.00074 U	< 0.0007 U	< 0.0015 U	< 0.00057 U	< 0.00084 U	< 0.00036 U	< 0.00074 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.005 U	< 0.00067 U	< 0.00069 U	< 0.00056 U	< 0.00044 U	< 0.00074 U	< 0.00051 U	< 0.00045 U	< 0.00076 U	< 0.00071 U	< 0.0015 U	< 0.00058 U	< 0.00085 U	< 0.00037 U	< 0.00075 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00051 U	< 0.0004 U	< 0.00067 U	< 0.00047 U	< 0.00041 U	< 0.00069 U	< 0.00065 U	< 0.0014 U	< 0.00053 U	< 0.00078 U	< 0.00034 U	< 0.00068 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	0.0053 J	< 0.00065 U	< 0.00066 U	< 0.00054 U	< 0.00043 U	< 0.00071 U	< 0.00049 U	< 0.00043 U	< 0.00073 U	< 0.00068 U	< 0.0015 U	< 0.00056 U	< 0.00082 U	< 0.00036 U	< 0.00072 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.0053 U	< 0.00072 U	< 0.00073 U	< 0.0006 U	< 0.00047 U	< 0.00079 U	< 0.00055 U	< 0.00048 U	< 0.00081 U	< 0.00076 U	< 0.0017 U	< 0.00062 U	< 0.00091 U	< 0.0004 U	< 0.0008 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	0.0068 J	< 0.00073 U	< 0.00075 U	< 0.00061 U	< 0.00048 U	< 0.0008 U	< 0.00056 U	< 0.00048 U	< 0.00082 U	< 0.00077 U	< 0.0017 U	< 0.00063 U	< 0.00092 U	< 0.0004 U	< 0.00081 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.0047 U	< 0.00064 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.0007 U	< 0.00048 U	< 0.00042 U	< 0.00072 U	< 0.00067 U	< 0.0015 U	< 0.00055 U	< 0.00081 U	< 0.00035 U	< 0.00071 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**	**1,1-Dichloroethene**	**1,2-Dichloroethene**	**cis-1,2-Dichloroethene**	**trans-1,2-Dichloroethene**	**1,2-Dichloropropane**	**cis-1,3-Dichloropropene**	**trans-1,3-Dichloropropene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	858.24	4 - 6 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00082 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0009 U	< 0.034 U	< 0.00032 U	< 0.034 U	< 0.034 U	< 0.00082 U	< 0.00066 U	< 0.034 U	< 0.00092 U	< 0.0028 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	6 - 8 ft	180-127265-2	Not Excavated	0.0081	< 0.00086 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00094 U	< 0.034 U	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.00086 U	< 0.0007 U	< 0.034 U	< 0.00097 U	< 0.003 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	858.24	8 - 10 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U	< 0.00025 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.00051 U	< 0.034 U	< 0.00071 U	< 0.0022 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	< 0.0019 U	< 0.00053 U	< 0.00034 U	< 0.00032 U	< 0.00021 U	< 0.00058 U	< 0.0005 U	< 0.00021 U	< 0.0005 U	< 0.0022 U	< 0.00053 U	< 0.00043 U	< 0.0021 U	< 0.00059 U	< 0.0018 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.0015 U	< 0.00043 U	< 0.00028 U	< 0.00026 U	< 0.00017 U	< 0.00047 U	< 0.00041 U	< 0.00017 U	< 0.00041 U	< 0.0018 U	< 0.00043 U	< 0.00035 U	< 0.0017 U	< 0.00049 U	< 0.0015 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	< 0.003 U	< 0.00083 U	< 0.00053 U	< 0.0005 U	< 0.00033 U	< 0.0009 U	< 0.00079 U	< 0.00032 U	< 0.00079 U	< 0.0034 U	< 0.00082 U	< 0.00066 U	< 0.0032 U	< 0.00093 U	< 0.0028 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	< 0.0022 U	< 0.00061 U	< 0.00039 U	< 0.00037 U	< 0.00024 U	< 0.00066 U	< 0.00058 U	< 0.00024 U	< 0.00058 U	< 0.0025 U	< 0.00061 U	< 0.00049 U	< 0.0024 U	< 0.00068 U	< 0.0021 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.0025 U	< 0.0007 U	< 0.00045 U	< 0.00043 U	< 0.00028 U	< 0.00076 U	< 0.00067 U	< 0.00027 U	< 0.00067 U	< 0.0029 U	< 0.0007 U	< 0.00056 U	< 0.0027 U	< 0.00079 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.0022 U	< 0.00062 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00068 U	< 0.00059 U	< 0.00024 U	< 0.00059 U	< 0.0025 U	< 0.00062 U	< 0.0005 U	< 0.0024 U	< 0.0007 U	< 0.0021 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	< 0.0022 U	< 0.00063 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00068 U	< 0.0006 U	< 0.00025 U	< 0.0006 U	< 0.0026 U	< 0.00063 U	< 0.0005 U	< 0.0024 U	< 0.0007 U	< 0.0022 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	< 0.012 U	< 0.00074 U	< 0.00091 U	< 0.0011 UJ	< 0.00079 UJ	< 0.00085 UJ	< 0.00067 U	< 0.00075 U	< 0.0018 U	< 0.0011 U	< 0.0014 U	< 0.0014 U	< 0.00082 U	< 0.0028 U	< 0.0036 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00067 U	< 0.00083 U	< 0.00097 U	< 0.00072 U	< 0.00077 U	< 0.00061 U	< 0.00068 U	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0012 U	< 0.00075 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 UJ	< 0.00098 U	< 0.00072 U	< 0.00077 UJ	< 0.00061 U	< 0.00068 U	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0012 U	< 0.00075 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00072 U	< 0.00088 U	< 0.001 U	< 0.00076 U	< 0.00082 U	< 0.00065 U	< 0.00072 U	< 0.0017 U	< 0.0011 U	< 0.0014 U	< 0.0013 U	< 0.00079 U	< 0.0027 U	< 0.0035 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	< 0.013 U	< 0.00084 U	< 0.001 UJ	< 0.0012 U	< 0.00089 U	< 0.00096 UJ	< 0.00076 U	< 0.00084 U	< 0.002 U	< 0.0012 U	< 0.0016 U	< 0.0015 U	< 0.00093 U	< 0.0031 U	< 0.004 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.38 U	< 0.078 U	< 0.052 U	< 0.12 U	< 0.045 U	< 0.054 U	< 0.047 U	< 0.046 U	< 0.081 U	< 0.061 U	< 0.039 U	< 0.061 U	< 0.037 U	< 0.12 U	< 0.1 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.0007 U	< 0.00085 UJ	< 0.001 U	< 0.00074 U	< 0.0008 UJ	< 0.00063 U	< 0.0007 U	< 0.0016 U	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00077 U	< 0.0026 U	< 0.0034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.0029 U	< 0.034 U	< 0.0036 U	< 0.0037 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.0026 U	< 0.034 U	< 0.0033 U	< 0.0034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-2-4	9/23/2021	856.00	2 - 4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U	< 0.034 U	< 0.0028 U	< 0.0036 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00067 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00065 J	< 0.00067 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0012 U	< 0.034 U	< 0.0025 U	< 0.0032 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.003 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00084 UJ	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00096 UJ	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.034 U	< 0.0016 UJ	< 0.0016 UJ	< 0.034 U	< 0.0031 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-2-4	11/1/2021	852.29	2 - 4 ft	180-129325-1	Excavated	< 0.018 U	< 0.0011 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0013 U	< 0.001 U	< 0.0011 U	< 0.0027 U	< 0.0017 U	< 0.0022 U	< 0.0021 U	< 0.0013 U	< 0.0043 U	< 0.0055 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-10-12	11/1/2021	852.29	10 - 12 ft	180-129325-1	Not Excavated	< 0.0096 U	< 0.00062 U	< 0.00076 U	< 0.00089 U	< 0.00066 U	< 0.00071 U	< 0.00056 U	< 0.00062 U	< 0.0015 U	< 0.0009 U	< 0.0012 U	< 0.0011 U	< 0.00068 U	< 0.0023 U	< 0.003 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-12-14	11/1/2021	852.29	12 - 14 ft	180-129325-1	Not Excavated	< 0.0086 UJ	< 0.00055 UJ	< 0.00067 UJ	< 0.00079 UJ	< 0.00058 UJ	< 0.00063 UJ	< 0.00049 UJ	< 0.00055 UJ	< 0.0013 UJ	< 0.0008 UJ	< 0.0011 UJ	< 0.001 UJ	< 0.00061 UJ	< 0.0021 UJ	< 0.0026 UJ
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-14-16	11/1/2021	852.29	14 - 16 ft	180-129325-1	Not Excavated	< 0.0089 U	< 0.00057 U	< 0.0007 U	< 0.00082 U	< 0.0006 U	< 0.00065 U	< 0.00051 U	< 0.00057 U	< 0.0013 U	< 0.00083 U	< 0.0011 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0027 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-4-6	11/1/2021	852.29	4 - 6 ft	180-129325-1	Not Excavated	< 0.01 U	< 0.00067 U	< 0.00081 U	< 0.00096 U	< 0.0007 U	< 0.00076 U	< 0.0006 U	< 0.00067 U	< 0.0016 U	< 0.00097 U	< 0.0013 U	< 0.0012 U	< 0.00074 U	< 0.0025 U	< 0.0032 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-6-8	11/1/2021	852.29	6 - 8 ft	180-129325-1	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 U	< 0.00098 UJ	< 0.00072 UJ	< 0.00078 UJ	< 0.00061 U	< 0.00068 U	< 0.0016 U	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-8-10	11/1/2021	852.29	8 - 10 ft	180-129325-1	Not Excavated	< 0.01 U	< 0.00064 U	< 0.00079 U	< 0.00093 U	< 0.00068 U	< 0.00074 U	< 0.00058 U	< 0.00065 U	< 0.0015 U	< 0.00094 U	< 0.0012 U	< 0.0012 U	< 0.00071 U	< 0.0024 U	< 0.0031 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.0052			< 0.34	< 0.34	< 0.34	< 0.0052	< 0.0052	< 0.0052		< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.0054			< 0.36	< 0.36	< 0.36	< 0.0054	< 0.0054	< 0.0054		< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.0057 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.0054 U			< 0.36 U	< 0.36 U	< 0.36 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.0057 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	0.0049	< 0.0021	< 0.0029	< 0.0032	< 0.0029	< 0.0029	< 0.0011	< 0.0011	< 0.0014	< 0.0023	< 0.0013	< 0.001	< 0.0018	< 0.0022	< 0.0024
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	0.0074	< 0.0021	< 0.0028	< 0.0031	< 0.0029	< 0.0029	< 0.0011	< 0.0011	< 0.0014	< 0.0023	< 0.0013	< 0.00099	< 0.0018	< 0.0021	< 0.0023
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	0.0064	< 0.0027	< 0.0038	< 0.0042	< 0.0038	< 0.0038	< 0.0014	< 0.0014	< 0.0019	< 0.003	< 0.0017	< 0.0013	< 0.0024	< 0.0028	< 0.0031
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00048 U	< 0.00052 U	< 0.00072 U		< 0.00059 U	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.0005 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.00055 U	< 0.0007 U	< 0.00054 U	< 0.00065 U	< 0.00053 U	< 0.00052 U	< 0.00047 U	< 0.0005 U	< 0.00069 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00049 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.0011 U	< 0.0014 U	< 0.0011 U	< 0.0013 U	< 0.0011 U	< 0.001 U	< 0.00093 U	< 0.00099 U	< 0.0014 U		< 0.0011 U	< 0.00096 U	< 0.00088 U	< 0.0011 U	< 0.00097 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.00056 U	< 0.00072 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00053 U	< 0.00048 U	< 0.00051 U	< 0.00071 U		< 0.00059 U	< 0.0005 U	< 0.00045 U	< 0.00057 U	< 0.0005 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.00054 U	< 0.00069 U	< 0.00054 U	< 0.00064 U	< 0.00053 U	< 0.00051 U	< 0.00046 U	< 0.00049 U	< 0.00068 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00048 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00063 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00069 U	< 0.00059 U	< 0.00053 U	< 0.00067 U	< 0.00059 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00049 U	< 0.00052 U	< 0.00072 U		0.00072 J	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.0005 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.00067 U	< 0.00086 U	< 0.00067 U	< 0.0008 U	< 0.00066 U	< 0.00064 U	< 0.00057 U	< 0.00061 U	< 0.00085 U		< 0.0007 U	< 0.0006 U	< 0.00054 U	< 0.00068 U	< 0.0006 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.00061 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00058 U	< 0.00053 U	< 0.00056 U	< 0.00077 U		< 0.00064 U	< 0.00054 U	< 0.0005 U	< 0.00062 U	< 0.00055 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.00065 U	< 0.00083 U	< 0.00064 U	< 0.00077 U	< 0.00063 U	< 0.00061 U	< 0.00055 U	< 0.00059 U	< 0.00082 U		< 0.00068 U	< 0.00057 U	< 0.00052 U	< 0.00065 U	< 0.00058 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.00072 U	< 0.00092 U	< 0.00071 U	< 0.00085 U	< 0.0007 U	< 0.00068 U	< 0.00061 U	< 0.00065 U	< 0.00091 U		< 0.00075 U	< 0.00064 U	< 0.00058 U	< 0.00072 U	< 0.00064 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	< 0.00073 U	< 0.00094 U	< 0.00072 U	< 0.00087 U	< 0.00071 U	< 0.00069 U	< 0.00062 U	< 0.00067 U	< 0.00092 U		< 0.00076 U	< 0.00065 U	< 0.00059 U	< 0.00074 U	< 0.00065 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.00064 U	< 0.00082 U	< 0.00063 U	< 0.00075 U	< 0.00062 U	< 0.0006 U	< 0.00054 U	< 0.00058 U	< 0.0008 U		0.0034 J	< 0.00056 U	< 0.00051 U	< 0.00064 U	< 0.00057 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7															
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	858.24	4 - 6 ft	180-127265-2	Not Excavated	< 0.00044 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00097 U	< 0.034 U	< 0.0021 U	< 0.00063 U	< 0.00032 U	< 0.034 U	< 0.00086 U	< 0.00048 U	< 0.034 U	< 0.00039 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	6 - 8 ft	180-127265-2	Not Excavated	< 0.00046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U	< 0.0022 U	< 0.00066 U	< 0.00034 U	< 0.034 U	< 0.0009 U	< 0.00051 U	< 0.034 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	858.24	8 - 10 ft	180-127265-2	Not Excavated	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.0016 U	< 0.00049 U	< 0.00025 U	< 0.034 U	< 0.00067 U	< 0.00038 U	< 0.034 U	< 0.0003 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	< 0.00028 U	< 0.00094 U	< 0.0021 U	< 0.00062 U	< 0.0025 U	0.0013 J	< 0.0015 U	< 0.0014 U	< 0.0004 U	< 0.00021 U	< 0.00067 U	< 0.00055 U	0.00079 J	< 0.00044 U	< 0.00025 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.00023 U	< 0.00077 U	< 0.0017 U	< 0.00051 U	< 0.002 U	< 0.00051 U	< 0.0012 U	< 0.0011 U	< 0.00033 U	< 0.00017 U	< 0.00055 U	< 0.00045 U	0.00029 J	< 0.00036 U	< 0.0002 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	< 0.00044 U	< 0.0015 U	< 0.0032 U	< 0.00097 U	< 0.0039 U	< 0.00098 U	< 0.0024 U	< 0.0021 U	< 0.00063 U	< 0.00032 U	< 0.001 U	< 0.00086 U	< 0.00049 U	< 0.00068 U	< 0.00039 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	< 0.00033 U	< 0.0011 U	< 0.0024 U	< 0.00072 U	< 0.0029 U	< 0.00072 U	< 0.0017 U	< 0.0016 U	< 0.00047 U	< 0.00024 U	< 0.00077 U	< 0.00064 U	< 0.00036 U	< 0.0005 U	< 0.00029 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.00038 U	< 0.0012 U	< 0.0027 U	< 0.00082 U	< 0.0033 U	< 0.00083 U	< 0.002 U	< 0.0018 U	< 0.00054 U	< 0.00027 U	< 0.00088 U	< 0.00073 U	< 0.00041 U	< 0.00058 U	< 0.00033 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.00033 U	< 0.0011 U	< 0.0024 U	< 0.00073 UJ	< 0.0029 U	< 0.00074 U	< 0.0018 U	< 0.0016 U	< 0.00048 U	< 0.00024 U	< 0.00079 U	< 0.00065 U	< 0.00037 U	< 0.00052 U	< 0.00029 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	< 0.00034 U	< 0.0011 U	< 0.0024 U	< 0.00074 U	< 0.003 U	0.00086 J	< 0.0018 U	< 0.0016 U	< 0.00048 U	< 0.00024 U	< 0.00079 U	< 0.00066 U	0.00095 J	< 0.00052 U	< 0.0003 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.0012 U	< 0.0039 U	< 0.0019 U	< 0.0033 U	< 0.0012 U	< 0.0034 U	< 0.0036 U	< 0.0019 U	< 0.0011 U	< 0.0014 UJ	< 0.00071 U	0.0016 J	< 0.0029 UJ	< 0.0024 UJ
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.00092 U	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.003 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0017 U	< 0.001 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.00092 UJ	< 0.0011 U	< 0.0036 U	< 0.0017 UJ	< 0.003 U	0.0015 J	< 0.0031 U	< 0.0033 U	< 0.0017 U	< 0.001 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.00098 U	< 0.0012 U	< 0.0038 U	< 0.0018 U	< 0.0032 U	< 0.0011 U	< 0.0033 U	< 0.0035 U	< 0.0018 U	< 0.0011 U	< 0.0013 U	< 0.00068 U	0.00079 J	< 0.0028 U	< 0.0023 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	< 0.0011 UJ	< 0.0014 U	< 0.0045 U	< 0.0021 UJ	< 0.0037 U	< 0.0013 U	< 0.0039 U	< 0.004 U	< 0.0022 U	< 0.0013 U	< 0.0016 U	< 0.0008 U	< 0.00084 U	< 0.0032 U	< 0.0027 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.046 U	< 0.066 U	< 0.26 U	< 0.038 U	< 0.17 U	< 0.065 U	0.2 J	< 0.23 U	< 0.037 U	< 0.051 U	< 0.15 U	< 0.096 U	< 0.24 U	< 0.17 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.00095 UJ	< 0.0012 U	< 0.0037 U	< 0.0017 UJ	< 0.0031 U	< 0.0011 U	< 0.0032 U	< 0.0034 U	< 0.0018 U	< 0.001 U	< 0.0013 U	< 0.00066 U	< 0.0007 U	< 0.0027 U	< 0.0023 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0039 U	< 0.034 U	< 0.003 U	< 0.0024 U	< 0.0024 U	< 0.034 U	< 0.0033 U	< 0.0023 U	< 0.034 U	< 0.0041 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0036 U	< 0.034 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.034 U	< 0.003 U	< 0.0022 U	< 0.034 U	< 0.0038 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	0.018 J	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-2-4	9/23/2021	856.00	2 - 4 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 UJ
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.005 J	< 0.034 U	0.13 J+	< 0.034 U	0.066 J+	0.0046 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0043 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	< 0.001 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0022 J	0.0062 J	< 0.0036 U	< 0.0019 U	< 0.0011 U	< 0.034 U	< 0.0007 U	< 0.00074 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0071 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.15	< 0.0011 U	< 0.034 U	< 0.0032 U	< 0.0017 U	< 0.001 UJ	< 0.034 U	< 0.00064 U	0.0015 J	< 0.034 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.00084 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00099 U	< 0.034 U	< 0.003 U	< 0.0016 U	< 0.00093 U	< 0.034 U	< 0.00059 U	< 0.00062 U	< 0.034 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.0011 UJ	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 UJ	< 0.034 U	< 0.0041 U	< 0.0022 U	< 0.0013 UJ	< 0.034 U	< 0.0008 UJ	< 0.00085 UJ	< 0.034 U	< 0.0027 UJ
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.003 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-2-4	11/1/2021	852.29	2 - 4 ft	180-129325-1	Excavated	< 0.0016 U	< 0.0019 U	< 0.0061 U	< 0.0028 U	< 0.005 U	< 0.0018 U	< 0.0053 U	< 0.0055 U	< 0.0029 U	< 0.0017 U	< 0.0021 U	< 0.0011 U	< 0.0011 U	< 0.0044 U	< 0.0037 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-10-12	11/1/2021	852.29	10 - 12 ft	180-129325-1	Not Excavated	< 0.00084 U	< 0.001 U	< 0.0033 U	< 0.0015 U	< 0.0027 U	< 0.00099 U	< 0.0029 U	< 0.003 U	< 0.0016 U	< 0.00093 U	< 0.0012 U	0.00068 J	< 0.00062 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-12-14	11/1/2021	852.29	12 - 14 ft	180-129325-1	Not Excavated	< 0.00075 UJ	< 0.00091 UJ	< 0.0029 UJ	< 0.0014 UJ	0.0028 J	< 0.00088 UJ	< 0.0025 UJ	< 0.0026 UJ	< 0.0014 UJ	< 0.00083 UJ	< 0.001 UJ	< 0.00052 UJ	< 0.00055 UJ	< 0.0021 UJ	< 0.0018 UJ
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-14-16	11/1/2021	852.29	14 - 16 ft	180-129325-1	Not Excavated	< 0.00078 U	< 0.00095 U	< 0.003 U	< 0.0014 U	< 0.0025 U	0.0021 J	< 0.0026 U	< 0.0028 U	< 0.0015 U	< 0.00086 U	< 0.0011 U	0.0035 J	0.0014 J	< 0.0022 U	< 0.0019 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-4-6	11/1/2021	852.29	4 - 6 ft	180-129325-1	Not Excavated	0.00095 J	< 0.0011 U	< 0.0035 U	< 0.0017 U	< 0.0029 U	0.0065 J	< 0.0031 U	< 0.0032 U	< 0.0017 U	< 0.001 U	< 0.0012 U	< 0.00063 U	0.0073	< 0.0025 U	< 0.0022 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-6-8	11/1/2021	852.29	6 - 8 ft	180-129325-1	Not Excavated	< 0.00093 U	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.003 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0018 U	< 0.001 U	< 0.0013 UJ	< 0.00065 U	< 0.00068 U	< 0.0026 UJ	< 0.0022 UJ
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-8-10	11/1/2021	852.29	8 - 10 ft	180-129325-1	Not Excavated	< 0.00088 U	< 0.0011 U	< 0.0034 U	< 0.0016 U	< 0.0028 U	0.0011 J	< 0.003 U	< 0.0031 U	< 0.0017 U	< 0.00097 U	< 0.0012 U	< 0.00061 U	0.00075 J	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.0052	< 0.0052	< 0.01				< 0.01	< 0.01		< 0.0052	< 0.0052	< 0.0052	< 0.0052		< 0.34
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.0054	< 0.0054	< 0.011				< 0.011	< 0.011		< 0.0054	< 0.0054	< 0.0054	< 0.0054		< 0.36
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.37 U
Northern Athletic Field	SSHS-B52	13 Sep 00B52 4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.0054 U	< 0.0054 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U		< 0.36 U
Northern Athletic Field	SSHS-B54	13 Sep 00B54 4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.38 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	< 0.002	< 0.0014	< 0.004	< 0.0034	< 0.013	< 0.0018	< 0.0029	< 0.0035	< 0.0025	< 0.0023	< 0.0039	< 0.0012	< 0.0036	< 0.004	< 0.004
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	< 0.0019	< 0.0013	< 0.0039	< 0.0033	< 0.013	< 0.0017	< 0.0029	< 0.0034	< 0.0024	< 0.0023	< 0.0038	< 0.0012	< 0.0035	< 0.0039	< 0.0039
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	< 0.0026	< 0.0018	< 0.0052	< 0.0044	< 0.017	< 0.0023	< 0.0038	< 0.0046	< 0.0032	< 0.003	< 0.0051	< 0.0016	< 0.0047	< 0.0052	< 0.0052
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.00054 U	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.00059 U	< 0.00061 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.00052 U	< 0.00087 U	< 0.00056 U	< 0.00055 U	< 0.00073 U	< 0.00059 U	< 0.00072 U	< 0.00053 U	< 0.00061 U	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00069 U	< 0.00072 U
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.001 U	< 0.0017 U	< 0.0011 U	< 0.0011 U	< 0.0015 U	< 0.0012 U	< 0.0014 U	< 0.0011 U	< 0.0012 U	< 0.0011 U	< 0.0012 U	< 0.0011 U	< 0.0012 U	< 0.0014 U	< 0.0014 U
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.00054 U	< 0.00089 U	< 0.00058 U	< 0.00057 U	< 0.00075 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.00052 U	< 0.00086 U	< 0.00056 U	< 0.00055 U	< 0.00073 U	< 0.00058 U	< 0.00071 U	< 0.00052 U	< 0.0006 U	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00068 U	< 0.00071 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00071 U	< 0.00087 U	< 0.00064 U	< 0.00073 U	< 0.00069 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.00054 U	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U	< 0.0006 U	< 0.00061 U	< 0.00057 U	< 0.00062 U	< 0.00071 U	< 0.00074 U
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.00064 U	< 0.0011 U	< 0.00069 U	< 0.00068 U	< 0.0009 U	< 0.00072 U	< 0.00088 U	< 0.00065 U	< 0.00075 U	< 0.0007 U	< 0.00072 U	< 0.00068 U	< 0.00073 U	< 0.00084 U	< 0.00088 U
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.00059 U	< 0.00098 U	< 0.00063 U	< 0.00062 U	< 0.00082 U	< 0.00066 U	< 0.00081 U	< 0.0006 U	< 0.00068 U	< 0.00064 U	< 0.00066 U	< 0.00062 U	< 0.00067 U	< 0.00077 U	< 0.00081 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.001 U	< 0.00067 U	< 0.00065 U	< 0.00087 U	< 0.0007 U	< 0.00085 U	< 0.00063 U	< 0.00072 U	< 0.00068 U	< 0.00069 U	< 0.00066 U	< 0.0007 U	< 0.00081 U	< 0.00085 U
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.00069 U	< 0.0011 U	< 0.00074 U	< 0.00072 U	< 0.00096 U	< 0.00077 U	< 0.00094 U	< 0.0007 U	< 0.0008 U	< 0.00075 U	< 0.00077 U	< 0.00073 U	< 0.00078 U	< 0.0009 U	< 0.00094 U
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	< 0.0007 U	< 0.0012 U	< 0.00075 U	< 0.00074 U	< 0.00098 U	< 0.00079 U	0.0019 J	< 0.00071 U	< 0.00081 U	< 0.00077 U	< 0.00078 U	< 0.00074 U	< 0.00079 U	< 0.00092 U	< 0.00096 U
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.00061 U	< 0.001 U	< 0.00065 U	< 0.00064 U	< 0.00085 U	0.0013 J	< 0.00083 U	< 0.00062 U	< 0.00071 U	< 0.00067 U	< 0.00068 U	< 0.00064 U	< 0.00069 U	< 0.0008 U	< 0.00083 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-4-6	9/17/2021	858.24	4 - 6 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	6 - 8 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-8-10	9/17/2021	858.24	8 - 10 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00083 U	< 0.034 U	< 0.00083 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	10 - 12 ft	180-127265-2	Not Excavated	< 0.0003 U	< 0.00054 U	0.0012 J	< 0.00039 U	< 0.0005 U	< 0.00069 U	< 0.00054 U	< 0.00069 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	12 - 14 ft	180-127265-2	Not Excavated	< 0.00024 U	< 0.00044 U	< 0.00074 U	< 0.00032 U	< 0.00041 U	< 0.00057 U	< 0.00044 U	< 0.00057 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	14 - 16 ft	180-127265-2	Not Excavated	< 0.00047 U	< 0.00084 U	< 0.0014 U	< 0.00061 U	< 0.00079 U	< 0.0011 U	< 0.00084 U	< 0.0011 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	2 - 4 ft	180-127265-2	Not Excavated	< 0.00034 U	< 0.00062 U	< 0.001 U	< 0.00045 U	< 0.00058 U	< 0.0008 U	< 0.00062 U	< 0.0008 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.0004 U	< 0.00071 U	< 0.0012 U	< 0.00052 U	< 0.00067 U	< 0.00092 U	< 0.00071 U	< 0.00092 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.00035 U	< 0.00063 U	< 0.0011 U	< 0.00046 U	< 0.00059 U	< 0.00081 U	< 0.00063 U	< 0.00081 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	8 - 10 ft	180-127265-2	Not Excavated	< 0.00035 U	< 0.00064 U	< 0.0011 U	< 0.00046 U	< 0.0006 U	0.00097 J	< 0.00064 U	0.00097 J
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	4 - 6 ft	180-127415-1	Not Excavated	< 0.0017 U	< 0.0011 U	0.002 J	< 0.0026 U	< 0.0017 U	< 0.00076 U	< 0.00083 U	< 0.0015 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	10 - 12 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.00055 U	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00075 U	< 0.0014 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	12 - 14 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.00056 U	< 0.0024 U	< 0.0016 U	< 0.00069 UJ	< 0.00076 U	< 0.0014 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	14 - 16 ft	180-127415-1	Not Excavated	< 0.0017 U	< 0.0011 U	< 0.00059 U	< 0.0025 U	< 0.0017 U	0.00086 J	< 0.0008 U	< 0.0015 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	2 - 4 ft	180-127415-1	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.00069 U	< 0.0029 U	< 0.0019 U	< 0.00085 UJ	< 0.00094 U	< 0.0017 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	6 - 8 ft	180-127415-1	Not Excavated	< 0.077 U	< 0.056 U	< 0.14 U	< 0.14 U	< 0.12 U	< 0.052 U	< 0.042 U	< 0.09 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	8 - 10 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.00057 U	< 0.0024 U	< 0.0016 U	< 0.00071 UJ	< 0.00078 U	< 0.0014 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	12 - 14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	2 - 4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	6 - 8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.012 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	6 - 8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.011 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	14 - 16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-2-4	9/23/2021	856.00	2 - 4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0083 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	4 - 6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	8 - 10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	10 - 12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	12 - 14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	14 - 16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	2 - 4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	4 - 6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	6 - 8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	8 - 10 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	12 - 14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.0054 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	14 - 16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.0026 J	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	4 - 6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.0011 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.0013 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.0027 J	< 0.034 U	< 0.034 U	< 0.00086 UJ	< 0.034 U	< 0.0017 UJ
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-2-4	11/1/2021	852.29	2 - 4 ft	180-129325-1	Excavated	< 0.0026 U	< 0.0017 U	< 0.00094 U	< 0.004 U	< 0.0026 U	< 0.0012 U	< 0.0013 U	< 0.0024 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-10-12	11/1/2021	852.29	10 - 12 ft	180-129325-1	Not Excavated	< 0.0014 U	< 0.00091 U	0.0019 J	< 0.0022 U	< 0.0014 U	< 0.00063 U	< 0.00069 U	< 0.0013 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-12-14	11/1/2021	852.29	12 - 14 ft	180-129325-1	Not Excavated	< 0.0013 UJ	< 0.00081 UJ	0.0019 J	< 0.0019 UJ	< 0.0013 UJ	< 0.00056 UJ	< 0.00061 UJ	< 0.0011 UJ
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-14-16	11/1/2021	852.29	14 - 16 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.00084 U	0.0063	< 0.002 U	< 0.0013 U	0.0009 J	< 0.00064 U	< 0.0012 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-4-6	11/1/2021	852.29	4 - 6 ft	180-129325-1	Not Excavated	< 0.0015 U	< 0.00098 U	< 0.00055 U	< 0.0023 U	< 0.0015 U	0.0056 J	0.0019 J	0.0075 J
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-6-8	11/1/2021	852.29	6 - 8 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.001 U	0.0023 J	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00076 U	< 0.0014 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-8-10	11/1/2021	852.29	8 - 10 ft	180-129325-1	Not Excavated	< 0.0015 U	< 0.00095 U	0.00091 J	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00072 U	< 0.0013 U
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	8 - 10 ft	NA	Not Excavated	< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052		< 0.0052	
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	3 - 5 ft	NA	Not Excavated	< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054		< 0.0054	
Northern Athletic Field	SSHS-B50	13 Sep 00B50_4-7	9/13/2000	854.58	4 - 7 ft	NA	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B52	13 Sep 00B52_4-6	9/13/2000	855.39	4 - 6 ft	-	Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	
Northern Athletic Field	SSHS-B54	13 Sep 00B54_4-6	9/13/2000	855.33	4 - 6 ft	NA	Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	10 - 12 ft	180-58309-2	Not Excavated	< 0.0011	< 0.0028	< 0.0011	< 0.0029	< 0.0025		< 0.0029	< 0.0045
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	12 - 14 ft	180-58309-2	Not Excavated	< 0.001	< 0.0027	< 0.0011	< 0.0028	< 0.0025		< 0.0028	< 0.0044
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	14 - 16 ft	180-58309-2	Not Excavated	< 0.0014	< 0.0036	< 0.0014	< 0.0038	< 0.0033		< 0.0037	< 0.0058
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	10 - 12 ft	180-35818-2	Not Excavated	< 0.00041 U	< 0.0007 U	< 0.00055 U	< 0.00077 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	6 - 9 ft	180-35818-2	Not Excavated	< 0.0004 U	< 0.00068 U	< 0.00053 U	< 0.00075 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
Rear Parking Lot	SSHS-B64	SSHS-B64-4-6 (5)	8/14/2014	851.65	4 - 6 ft	180-35818-2	Excavated	< 0.00079 U	< 0.0013 U	< 0.0011 U	< 0.0015 U	< 0.00076 U	< 0.0024 U	< 0.0013 U	
Rear Parking Lot	SSHS-B65	SSHS-B65-4-6 (4)	8/14/2014	850.41	4 - 6 ft	180-35818-1	Excavated	< 0.00041 U	< 0.00069 U	0.0015 J	< 0.00077 U	< 0.00039 U	< 0.0012 U	< 0.00065 U	
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	10 - 12 ft	180-35818-1	Not Excavated	< 0.00039 U	< 0.00067 U	< 0.00053 U	< 0.00074 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	8 - 10 ft	180-35818-1	Not Excavated	< 0.00048 U	< 0.00082 U	< 0.00065 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Rear Parking Lot	SSHS-B66	SSHS-B66-2-4 (3)	8/14/2014	851.94	2 - 4 ft	180-35818-1	Excavated	< 0.00041 U	< 0.0007 U	0.0051	< 0.00078 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	
Rear Parking Lot	SSHS-B66	SSHS-B66-6-8R (7)	8/14/2014	851.94	6 - 8 ft	180-35818-1	Excavated	< 0.00049 U	< 0.00083 U	0.00074 J	< 0.00092 U	< 0.00047 U	< 0.0015 U	< 0.00078 U	
Rear Parking Lot	SSHS-B67	SSHS-B67-2-6 (4.5)	8/14/2014	850.45	2 - 6 ft	180-35818-1	Excavated	< 0.00044 U	< 0.00076 U	0.0006 J	< 0.00084 U	< 0.00043 U	< 0.0013 U	< 0.00071 U	
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	10 - 12 ft	180-35818-1	Not Excavated	< 0.00047 U	< 0.0008 U	< 0.00063 U	< 0.00089 U	< 0.00045 U	< 0.0014 U	< 0.00075 U	
Rear Parking Lot	SSHS-B67	SSHS-B67-8-10 (9)	8/14/2014	850.45	8 - 10 ft	180-35818-1	Excavated	< 0.00052 U	< 0.00089 U	< 0.0007 U	< 0.00098 U	< 0.0005 U	< 0.0016 U	< 0.00083 U	
Rear Parking Lot	SSHS-B68	SSHS-B68-2-6 (5.5)	8/14/2014	852.07	2 - 6 ft	180-35818-1	Excavated	< 0.00053 U	< 0.0009 U	< 0.00071 U	< 0.001 U	0.00056 J	< 0.0016 U	< 0.00085 U	
Rear Parking Lot	SSHS-B68	SSHS-B68-6-8R (6.5)	8/14/2014	852.07	6 - 8 ft	180-35818-1	Excavated	< 0.00046 U	< 0.00079 U	0.0057	< 0.00087 U	0.0043 J	< 0.0014 U	< 0.00074 U	

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^{1} (ft amsl)	Sample depth at time of sampling^{5} (bgs)	Lab Report	Excavation Status^{7}															
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	0.0069 J	< 0.00082 U	< 0.00084 U	< 0.00068 U	< 0.00054 U	< 0.0009 U	< 0.00062 U	< 0.00054 U	< 0.00092 U	< 0.00086 U	< 0.0019 U	< 0.00071 U	< 0.001 U	< 0.00045 U	< 0.00091 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 0.005 U	< 0.00067 U	< 0.00068 U	< 0.00056 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U	< 0.00075 U	< 0.00071 U	< 0.0015 U	< 0.00058 U	< 0.00085 U	< 0.00037 U	< 0.00074 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00051 U	< 0.0004 U	< 0.00068 U	< 0.00047 U	< 0.00041 U	< 0.00069 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00068 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	< 0.0053 U	< 0.00072 U	< 0.00073 U	< 0.0006 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	< 0.0043 U	< 0.00059 U	< 0.0006 U	< 0.00049 U	< 0.00038 U	< 0.00064 U	< 0.00044 U	< 0.00039 U	< 0.00066 U	< 0.00062 U	< 0.0013 U	< 0.00051 U	< 0.00074 U	< 0.00032 U	< 0.00065 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	< 0.0055 U	< 0.00074 U	< 0.00075 U	< 0.00062 U	< 0.00048 U	< 0.00081 U	< 0.00056 U	< 0.00049 U	< 0.00083 U	< 0.00078 U	< 0.0017 U	< 0.00064 U	< 0.00093 U	< 0.00041 U	< 0.00082 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.0052	< 0.00071	< 0.00072	< 0.00059	< 0.00046	< 0.00078	< 0.00054	< 0.00047	< 0.0008	< 0.00074	< 0.0016	< 0.00061	< 0.00089	< 0.00039	< 0.00079
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.0046	< 0.00061	< 0.00063	< 0.00051	< 0.0004	< 0.00067	< 0.00047	< 0.00041	< 0.00069	< 0.00065	< 0.0014	< 0.00053	< 0.00078	< 0.00034	< 0.00068
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.0047	< 0.00063	< 0.00064	< 0.00052	< 0.00041	< 0.00069	< 0.00048	< 0.00042	< 0.00071	< 0.00066	< 0.0014	< 0.00055	< 0.00079	< 0.00035	< 0.0007
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.0049	< 0.00067	< 0.00068	< 0.00055	< 0.00044	< 0.00073	< 0.0005	< 0.00044	< 0.00075	< 0.0007	< 0.0015	< 0.00058	< 0.00084	< 0.00037	< 0.00074
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.0065	< 0.00087	< 0.00089	< 0.00073	< 0.00057	< 0.00096	< 0.00066	< 0.00058	< 0.00098	< 0.00092	< 0.002	< 0.00076	< 0.0011	< 0.00048	< 0.00097
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.0052	< 0.0007	< 0.00071	< 0.00058	< 0.00046	< 0.00076	< 0.00053	< 0.00046	< 0.00078	< 0.00073	< 0.0016	< 0.00061	< 0.00088	< 0.00038	< 0.00077
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.0054	< 0.00073	< 0.00074	< 0.00061	< 0.00048	< 0.0008	< 0.00055	< 0.00048	< 0.00082	< 0.00077	< 0.0017	< 0.00063	< 0.00092	< 0.0004	< 0.00081
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.005	< 0.00067	< 0.00068	< 0.00056	< 0.00044	< 0.00074	< 0.00051	< 0.00044	< 0.00075	< 0.00071	< 0.0015	< 0.00058	< 0.00085	< 0.00037	< 0.00074
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.005	< 0.00068	< 0.00069	< 0.00056	< 0.00044	< 0.00074	< 0.00051	< 0.00045	< 0.00076	< 0.00071	< 0.0016	< 0.00059	< 0.00086	< 0.00037	< 0.00075
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.0051	< 0.00069	< 0.00071	< 0.00058	< 0.00045	< 0.00076	< 0.00053	< 0.00046	< 0.00078	< 0.00073	< 0.0016	< 0.0006	< 0.00088	< 0.00038	< 0.00077
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.0046	< 0.00063	< 0.00064	< 0.00052	< 0.00041	< 0.00068	< 0.00047	< 0.00041	< 0.0007	< 0.00066	< 0.0014	< 0.00054	< 0.00079	< 0.00034	< 0.00069
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.0047	< 0.00064	< 0.00065	< 0.00053	< 0.00042	< 0.0007	< 0.00049	< 0.00042	< 0.00072	< 0.00067	< 0.0015	< 0.00055	< 0.00081	< 0.00035	< 0.00071
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.0056	< 0.00076	< 0.00077	< 0.00063	< 0.0005	< 0.00083	< 0.00058	< 0.0005	< 0.00085	< 0.0008	< 0.0017	< 0.00066	< 0.00096	< 0.00042	< 0.00084
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.005	< 0.00067	< 0.00068	< 0.00056	< 0.00044	< 0.00073	< 0.00051	< 0.00044	< 0.00075	< 0.00071	< 0.0015	< 0.00058	< 0.00085	< 0.00037	< 0.00074
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.0053 U	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	< 0.0056 U	< 0.00076 U	< 0.00077 U	< 0.00063 U	< 0.0005 U	< 0.00083 U	< 0.00058 U	< 0.0005 U	< 0.00085 U	< 0.0008 U	< 0.0017 U	< 0.00066 U	< 0.00096 U	< 0.00042 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	< 0.0064 U	< 0.00087 U	< 0.00088 U	< 0.00072 U	< 0.00057 U	< 0.00095 U	< 0.00066 U	< 0.00057 U	< 0.00097 U	< 0.00091 U	< 0.002 U	< 0.00075 U	< 0.0011 U	< 0.00048 U	< 0.00096 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.0064 U	< 0.00086 U	< 0.00088 U	< 0.00071 U	< 0.00056 U	< 0.00094 U	< 0.00065 U	< 0.00057 U	< 0.00096 U	< 0.0009 U	< 0.002 U	< 0.00074 U	< 0.0011 U	< 0.00047 U	< 0.00095 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U	< 0.0007 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	< 0.0053 U	< 0.00072 U	< 0.00073 U	< 0.0006 U	< 0.00047 U	< 0.00079 U	< 0.00055 U	< 0.00048 U	< 0.00081 U	< 0.00076 U	< 0.0016 U	< 0.00062 U	< 0.00091 U	< 0.0004 U	< 0.0008 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.0049 U	< 0.00067 U	< 0.00068 U	< 0.00055 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.0042 U	< 0.00056 U	< 0.00057 U	< 0.00047 U	< 0.00037 U	< 0.00061 U	< 0.00043 U	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.0013 U	< 0.00049 U	< 0.00071 U	< 0.00031 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00044 U	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.004 U	< 0.00054 U	< 0.00055 U	< 0.00045 U	< 0.00036 U	< 0.00059 U	< 0.00041 U	< 0.00036 U	< 0.00061 U	< 0.00057 U	< 0.0012 U	< 0.00047 U	< 0.00068 U	< 0.0003 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00063 U	< 0.00051 U	< 0.0004 U	< 0.00067 U	< 0.00047 U	< 0.00041 U	< 0.00069 U	< 0.00064 U	< 0.0014 U	< 0.00053 U	< 0.00077 U	< 0.00034 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	< 0.0041 U	< 0.00055 U	< 0.00056 U	< 0.00046 U	< 0.00036 U	< 0.00061 U	< 0.00042 U	< 0.00037 U	< 0.00062 U	< 0.00058 U	< 0.0013 U	< 0.00048 U	< 0.0007 U	< 0.0003 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	0.0064 J	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00068 U	< 0.00055 U	< 0.00043 U	< 0.00073 U	< 0.0005 U	< 0.00044 U	< 0.00074 U	< 0.0007 U	< 0.0015 U	< 0.00057 U	< 0.00084 U	< 0.00036 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U	< 0.0007 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	< 0.0048 U	< 0.00065 U	< 0.00066 U	< 0.00054 U	< 0.00042 U	< 0.00071 U	< 0.00049 U	< 0.00043 U	< 0.00073 U	< 0.00068 U	< 0.0015 U	< 0.00056 U	< 0.00082 U	< 0.00036 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.0005 U	< 0.0004 U	< 0.00066 U	< 0.00046 U	< 0.0004 U	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00052 U	< 0.00076 U	< 0.00033 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated	< 0.16 U	< 0.098 U	< 0.096 U	< 0.12 U	< 0.13 U	< 0.22 U	< 0.15 U	< 0.17 U	< 0.078 U	< 0.12 U	< 0.13 U	< 0.11 U	< 0.19 U	< 0.061 U	< 0.15 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated	0.014 J	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0048 U	< 0.0015 U	< 0.0038 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.0005 U	< 0.0004 U	< 0.00066 U	< 0.00046 U	< 0.0004 U	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00052 U	< 0.00076 U	< 0.00033 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	< 0.0053 U	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	0.0007 J	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	< 0.0074 U	< 0.001 U	< 0.001 U	< 0.00083 U	< 0.00065 U	< 0.0011 U	< 0.00076 U	< 0.00066 U	< 0.0011 U	< 0.001 U	< 0.0023 U	< 0.00086 U	< 0.0013 U	< 0.00055 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	< 0.0044 U	< 0.00059 U	< 0.0006 U	< 0.00049 U	< 0.00039 U	< 0.00065 U	< 0.00045 U	< 0.00039 U	< 0.00066 U	< 0.00062 U	< 0.0014 U	< 0.00051 U	< 0.00075 U	< 0.00033 U	< 0.00066 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated	0.0061 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U,*	< 0.0048 U	< 0.0032 U	< 0.0035 U	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.0043 U	< 0.00059 U	< 0.0006 U	< 0.00049 U	< 0.00038 U	< 0.00064 U	< 0.00044 U	< 0.00039 U	< 0.00066 U	< 0.00062 U	< 0.0013 U	< 0.00051 U	< 0.00074 U	< 0.00032 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00043 U	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00044 U	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.0059 U	< 0.00079 U	< 0.00081 U	< 0.00066 U	< 0.00052 U	< 0.00087 U	< 0.0006 U	< 0.00052 U	< 0.00089 U	< 0.00083 U	< 0.0018 U	< 0.00069 U	< 0.001 U	< 0.00044 U	< 0.00088 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	< 0.0047 U	< 0.00064 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.0007 U	< 0.00049 U	< 0.00042 U	< 0.00072 U	< 0.00067 U	< 0.0015 U	< 0.00056 U	< 0.00081 U	< 0.00035 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00043 U	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	< 0.0047 U	< 0.00063 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.00069 U	< 0.00048 U	< 0.00042 U	< 0.00071 U	< 0.00067 U	< 0.0015 U	< 0.00055 U	< 0.0008 U	< 0.00035 U	< 0.0007 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	< 0.0034 U	< 0.00046 U	< 0.00047 U	< 0.00038 U	< 0.0003 U	< 0.0005 U	< 0.00035 U	< 0.0003 U	< 0.00051 U	< 0.00048 U	< 0.001 U	< 0.0004 U	< 0.00058 U	< 0.00025 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.00051 U	< 0.0004 U	< 0.00067 U	< 0.00046 U	< 0.0004 U	< 0.00069 U	< 0.00064 U	< 0.0014 U	< 0.00053 U	< 0.00077 U	< 0.00034 U	< 0.00068 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated	0.005 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00067 U	< 0.00068 U	< 0.00055 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	< 0.0043 U	< 0.00058 U	< 0.00059 U	< 0.00048 U	< 0.00038 U	< 0.00063 U	< 0.00044 U	< 0.00038 U	< 0.00065 U	< 0.00061 U	< 0.0013 U	< 0.0005 U	< 0.00073 U	< 0.00032 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	< 0.0046 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00069 U	< 0.00048 U	< 0.00041 U	< 0.0007 U	< 0.00066 U	< 0.0014 U	< 0.00054 U	< 0.00079 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.0047 U	< 0.00064 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.0007 U	< 0.00048 U	< 0.00042 U	< 0.00072 U	< 0.00067 U	< 0.0015 U	< 0.00055 U	< 0.0008 U	< 0.00035 U	< 0.00071 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U	< 0.0018 U	< 0.0027 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	< U	< U						< U	< U			0.0032 J			
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0032 J	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0028 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0026 J,B	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0026 J,B	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0022 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**	**1,1-Dichloroethene**	**1,2-Dichloroethene**	**cis-1,2-Dichloroethene**	**trans-1,2-Dichloroethene**	**1,2-Dichloropropane**	**cis-1,3-Dichloropropene**	**trans-1,3-Dichloropropene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	< 0.00082 U	< 0.001 U	< 0.00081 U	< 0.00097 U	< 0.0008 U	< 0.00077 U	< 0.0007 U	< 0.00074 U	< 0.001 U		< 0.00085 U	< 0.00072 U	< 0.00066 U	< 0.00082 U	< 0.00073 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 0.00067 U	< 0.00086 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U	< 0.00084 U		< 0.0007 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00058 U	< 0.00053 U	< 0.00056 U	< 0.00078 U		< 0.00064 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	< 0.00071 U	< 0.00092 U,*	< 0.00071 U	< 0.00085 U	< 0.0007 U	< 0.00068 U	< 0.00061 U	< 0.00065 U	< 0.0009 U		< 0.00075 U	< 0.00063 U	< 0.00058 U	< 0.00072 U,*	< 0.00063 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	< 0.00058 U	< 0.00075 U,*	< 0.00058 U	< 0.00069 U	< 0.00057 U	< 0.00055 U	< 0.0005 U	< 0.00053 U	< 0.00074 U		< 0.00061 U	< 0.00052 U	< 0.00047 U	< 0.00059 U,*	< 0.00052 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	< 0.00074 U	< 0.00095 U	< 0.00073 U	< 0.00087 U	< 0.00072 U	< 0.0007 U	< 0.00063 U	< 0.00067 U	< 0.00093 U		< 0.00077 U	< 0.00065 U	< 0.0006 U	< 0.00074 U	< 0.00066 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.00071	< 0.00091	< 0.0007	< 0.00084	< 0.00069	< 0.00067	< 0.0006	< 0.00064	< 0.00089		< 0.00074	< 0.00063	< 0.00057	< 0.00071	< 0.00063
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.00061	< 0.00079	< 0.00061	< 0.00073	< 0.0006	< 0.00058	< 0.00052	< 0.00056	< 0.00077		< 0.00064	< 0.00054	< 0.00049	< 0.00062	< 0.00054
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.00063	< 0.0008	< 0.00062	< 0.00074	< 0.00061	< 0.00059	< 0.00054	< 0.00057	< 0.00079		< 0.00066	< 0.00056	< 0.00051	< 0.00063	< 0.00056
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.00066	< 0.00085	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.0006	< 0.00084		< 0.00069	< 0.00059	< 0.00054	< 0.00067	< 0.00059
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.00087	< 0.0011	< 0.00086	< 0.001	< 0.00085	< 0.00083	< 0.00075	< 0.00079	< 0.0011		< 0.00091	< 0.00077	< 0.0007	< 0.00088	< 0.00077
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.0007	< 0.00089	< 0.00069	< 0.00083	< 0.00068	< 0.00066	< 0.0006	< 0.00063	< 0.00088		< 0.00073	< 0.00062	< 0.00056	< 0.0007	< 0.00062
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.00073	< 0.00093	< 0.00072	< 0.00086	< 0.00071	< 0.00069	< 0.00062	< 0.00066	< 0.00092		< 0.00076	< 0.00064	< 0.00059	< 0.00073	< 0.00065
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.00067	< 0.00086	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.00061	< 0.00084		< 0.0007	< 0.00059	< 0.00054	< 0.00067	< 0.00059
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.00068	< 0.00087	< 0.00067	< 0.0008	< 0.00066	< 0.00064	< 0.00058	< 0.00062	< 0.00085		< 0.00071	< 0.0006	< 0.00055	< 0.00068	< 0.0006
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.00069	< 0.00089	< 0.00068	< 0.00082	< 0.00067	< 0.00065	< 0.00059	< 0.00063	< 0.00087		< 0.00072	< 0.00061	< 0.00056	< 0.0007	< 0.00061
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.00062	< 0.0008	< 0.00062	< 0.00074	< 0.00061	< 0.00059	< 0.00053	< 0.00057	< 0.00079		< 0.00065	< 0.00055	< 0.0005	< 0.00063	< 0.00055
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.00064	< 0.00082	< 0.00063	< 0.00076	< 0.00062	< 0.0006	< 0.00055	< 0.00058	< 0.0008		< 0.00067	< 0.00057	< 0.00052	< 0.00064	< 0.00057
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.00076	< 0.00097	< 0.00075	< 0.0009	< 0.00074	< 0.00072	< 0.00065	< 0.00069	< 0.00095		< 0.00079	< 0.00067	< 0.00061	< 0.00076	< 0.00067
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.00067	< 0.00086	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.00061	< 0.00084		< 0.0007	< 0.00059	< 0.00054	< 0.00067	< 0.00059
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	< 0.00076 U	< 0.00097 U	< 0.00075 U	< 0.0009 U	< 0.00074 U	< 0.00072 U	< 0.00065 U	< 0.00069 U	< 0.00095 U		< 0.00079 U	< 0.00067 U	< 0.00061 U	< 0.00076 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	< 0.00086 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00084 U	< 0.00082 U	< 0.00074 U	< 0.00079 U	< 0.0011 U		< 0.0009 U	< 0.00076 U	< 0.0007 U	< 0.00087 U	< 0.00077 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.00086 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00083 U	< 0.00081 U	< 0.00073 U	< 0.00078 U	< 0.0011 U		< 0.00089 U	< 0.00076 U	< 0.00069 U	< 0.00086 U	< 0.00076 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00058 U	< 0.00053 U	< 0.00056 U	< 0.00078 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	< 0.00072 U	< 0.00092 U	< 0.00071 U	< 0.00085 U	< 0.0007 U	< 0.00068 U	< 0.00061 U	< 0.00065 U	< 0.0009 U		< 0.00075 U	< 0.00063 U	< 0.00058 U	< 0.00072 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U	< 0.00084 U		< 0.0007 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.00056 U	< 0.00072 U	< 0.00055 U	< 0.00066 U	< 0.00055 U	< 0.00053 U	< 0.00048 U	< 0.00051 U	< 0.0007 U		< 0.00058 U	< 0.0005 U	< 0.00045 U	< 0.00056 U	< 0.0005 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00069 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.00054 U	< 0.00069 U	< 0.00054 U	< 0.00064 U	< 0.00053 U	< 0.00051 U	< 0.00046 U	< 0.00049 U	< 0.00068 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00048 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.00078 U	< 0.0006 U	< 0.00072 U	< 0.0006 U	< 0.00058 U	< 0.00052 U	< 0.00056 U	< 0.00077 U		< 0.00064 U	< 0.00054 U	< 0.00049 U	< 0.00062 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	< 0.00055 U	< 0.00071 U	< 0.00055 U	< 0.00065 U	< 0.00054 U	< 0.00052 U	< 0.00047 U	< 0.0005 U	< 0.0007 U		< 0.00058 U	< 0.00049 U	< 0.00045 U	< 0.00056 U	< 0.00049 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00063 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00069 U	< 0.00059 U	< 0.00053 U	< 0.00067 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00059 U	< 0.00053 U	< 0.00056 U	< 0.00078 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.00083 U	< 0.00064 U	< 0.00076 U	< 0.00063 U	< 0.00061 U	< 0.00055 U	< 0.00059 U	< 0.00081 U		< 0.00067 U	< 0.00057 U	< 0.00052 U	< 0.00065 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.0006 U	< 0.00077 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U	< 0.00076 U		< 0.00063 U	< 0.00053 U	< 0.00049 U	< 0.00061 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00049 U	< 0.00052 U	< 0.00072 U		< 0.00059 U	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.00051 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.079 U	< 0.051 U	< 0.09 U	< 0.072 U	< 0.14 U	< 0.2 U	< 0.078 U	< 0.13 U	< 0.12 U	< 0.08 U	< 0.086 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated	< 0.0029 U	< 0.0034 U	< 0.0036 U	< 0.005 U	< 0.002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	< 0.0006 U	< 0.00077 U	< 0.0006 U	< 0.00071 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U	< 0.00076 U		< 0.00063 U	< 0.00053 U	< 0.00049 U	< 0.00061 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	< 0.00099 U	< 0.0013 U	< 0.00098 U	< 0.0012 U	< 0.00097 U	< 0.00094 U	< 0.00085 U	< 0.00091 U	< 0.0013 U		< 0.001 U	< 0.00088 U	< 0.0008 U	< 0.001 U	< 0.00088 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	< 0.00059 U	< 0.00076 U	< 0.00058 U	< 0.0007 U	< 0.00058 U	< 0.00056 U	< 0.0005 U	< 0.00054 U	< 0.00074 U		< 0.00062 U	< 0.00052 U	< 0.00048 U	< 0.00059 U	< 0.00052 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.00058 U	< 0.00075 U	< 0.00058 U	< 0.00069 U	< 0.00057 U	< 0.00055 U	< 0.0005 U	< 0.00053 U	< 0.00074 U		< 0.00061 U	< 0.00052 U	< 0.00047 U	< 0.00059 U	< 0.00052 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	< 0.00065 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00068 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00069 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.00079 U	< 0.001 U	< 0.00078 U	< 0.00094 U	< 0.00077 U	< 0.00075 U	< 0.00068 U	< 0.00072 U	< 0.001 U		< 0.00083 U	< 0.0007 U	< 0.00064 U	< 0.0008 U	< 0.0007 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.00082 U	< 0.00063 U	< 0.00076 U	< 0.00062 U	< 0.0006 U	< 0.00055 U	< 0.00058 U	< 0.00081 U		< 0.00067 U	< 0.00057 U	< 0.00052 U	< 0.00064 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	< 0.00065 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U	< 0.00083 U		< 0.00069 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.00081 U	< 0.00062 U	< 0.00075 U	< 0.00062 U	< 0.0006 U	< 0.00054 U	< 0.00058 U	< 0.0008 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00064 U	< 0.00056 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	< 0.00046 U	< 0.00058 U	< 0.00045 U	< 0.00054 U	< 0.00044 U	< 0.00043 U	< 0.00039 U	< 0.00042 U	< 0.00057 U		< 0.00048 U	< 0.0004 U	< 0.00037 U	< 0.00046 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.00078 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00058 U	< 0.00052 U	< 0.00055 U	< 0.00077 U		< 0.00064 U	< 0.00054 U	< 0.00049 U	< 0.00061 U	< 0.00054 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	< 0.0027 U	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U	< 0.00084 U		< 0.00069 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	< 0.00057 U	< 0.00074 U	< 0.00057 U	< 0.00068 U	< 0.00056 U	< 0.00054 U	< 0.00049 U	< 0.00052 U	< 0.00072 U		< 0.0006 U	< 0.00051 U	< 0.00046 U	< 0.00058 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	< 0.00062 U	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00053 U	< 0.00057 U	< 0.00079 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00063 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.00081 U	< 0.00063 U	< 0.00075 U	< 0.00062 U	< 0.0006 U	< 0.00054 U	< 0.00058 U	< 0.0008 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00064 U	< 0.00056 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated	< 0.0029 U	< 0.0033 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	< U			< U	< U	< U	< U	< U	< U		< U	< U			
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	< 0.00078 U	< 0.0013 U	< 0.00084 U	< 0.00082 U	< 0.0011 U	< 0.00088 U	< 0.0011 U	< 0.00079 U	< 0.00091 U	< 0.00086 U	< 0.00087 U	< 0.00083 U	< 0.00089 U	< 0.001 U	< 0.0011 U
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 0.00064 U	< 0.0011 U	< 0.00069 U	< 0.00067 U	< 0.0009 U	< 0.00072 U	< 0.00088 U	< 0.00065 U	< 0.00074 U	< 0.0007 U	< 0.00071 U	< 0.00068 U	< 0.00073 U	< 0.00084 U	< 0.00088 U
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.00059 U	< 0.00098 U	< 0.00063 U	< 0.00062 U	< 0.00082 U	< 0.00066 U	< 0.00081 U	< 0.0006 U	< 0.00068 U	< 0.00065 U	< 0.00066 U	< 0.00062 U	< 0.00067 U	< 0.00077 U	< 0.00081 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	< 0.00068 U	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00096 U	< 0.00077 U	< 0.00093 U	< 0.00069 U,*	< 0.00079 U	< 0.00075 U	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.0009 U	< 0.00094 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	< 0.00056 U	< 0.00093 U	< 0.0006 U	< 0.00059 U	< 0.00078 U	< 0.00063 U	< 0.00077 U	< 0.00057 U,*	< 0.00065 U	< 0.00061 U	< 0.00062 U	< 0.00059 U	< 0.00063 U	< 0.00073 U	< 0.00077 U
Football Field	SSHS-B70	081514 01:15 SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	< 0.0007 U	< 0.0012 U	< 0.00076 U	< 0.00074 U	< 0.00099 U	< 0.0008 U	< 0.00097 U	< 0.00072 U	< 0.00082 U	< 0.00077 U	< 0.00079 U	< 0.00075 U	< 0.0008 U	< 0.00093 U	< 0.00097 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.00067	< 0.0011	< 0.00072	< 0.00071	< 0.00095	< 0.00076	< 0.00093	< 0.00068	< 0.00078	< 0.00074	< 0.00075	< 0.00071	< 0.00077	< 0.00089	< 0.00093
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.00058	< 0.00097	< 0.00063	< 0.00062	< 0.00082	< 0.00066	< 0.0008	< 0.00059	< 0.00068	< 0.00064	< 0.00065	< 0.00062	< 0.00066	< 0.00077	< 0.0008
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.0006	< 0.00099	< 0.00064	< 0.00063	< 0.00084	< 0.00068	< 0.00082	< 0.00061	< 0.0007	< 0.00066	< 0.00067	< 0.00063	< 0.00068	< 0.00079	< 0.00082
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.00063	< 0.0011	< 0.00068	< 0.00067	< 0.00089	< 0.00071	< 0.00087	< 0.00064	< 0.00074	< 0.00069	< 0.00071	< 0.00067	< 0.00072	< 0.00083	< 0.00087
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.00083	< 0.0014	< 0.00089	< 0.00088	< 0.0012	< 0.00094	< 0.0011	< 0.00085	< 0.00097	< 0.00091	< 0.00093	< 0.00088	< 0.00095	< 0.0011	< 0.0011
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.00066	< 0.0011	< 0.00071	< 0.0007	< 0.00093	< 0.00075	< 0.00091	< 0.00068	< 0.00077	< 0.00073	< 0.00074	< 0.0007	< 0.00075	< 0.00087	< 0.00091
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.0007	< 0.0012	< 0.00075	< 0.00073	< 0.00098	< 0.00078	< 0.00095	< 0.00071	< 0.00081	< 0.00076	< 0.00078	< 0.00074	< 0.00079	< 0.00091	< 0.00095
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.00064	< 0.0011	< 0.00069	< 0.00068	< 0.0009	< 0.00072	< 0.00088	< 0.00065	< 0.00074	< 0.0007	< 0.00071	< 0.00068	< 0.00073	< 0.00084	< 0.00088
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.00065	< 0.0011	< 0.00069	< 0.00068	< 0.00091	< 0.00073	< 0.00089	< 0.00066	< 0.00075	< 0.00071	< 0.00072	< 0.00068	< 0.00073	< 0.00085	< 0.00089
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.00066	< 0.0011	< 0.00071	< 0.0007	< 0.00093	< 0.00075	< 0.00091	< 0.00067	< 0.00077	< 0.00073	< 0.00074	< 0.0007	< 0.00075	< 0.00087	< 0.00091
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.0006	< 0.00099	< 0.00064	< 0.00063	< 0.00084	< 0.00067	< 0.00082	< 0.0006	< 0.00069	< 0.00065	< 0.00067	< 0.00063	< 0.00068	< 0.00078	< 0.00082
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.00061	< 0.001	< 0.00065	< 0.00064	< 0.00085	< 0.00069	< 0.00084	< 0.00062	< 0.00071	< 0.00067	< 0.00068	< 0.00065	< 0.00069	< 0.0008	< 0.00084
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.00072	< 0.0012	< 0.00078	< 0.00076	< 0.001	< 0.00082	< 0.00099	< 0.00073	< 0.00084	< 0.00079	< 0.00081	< 0.00077	< 0.00082	< 0.00095	< 0.00099
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.00064	< 0.0011	< 0.00069	< 0.00068	< 0.0009	< 0.00072	< 0.00088	< 0.00065	< 0.00074	< 0.0007	< 0.00071	< 0.00068	< 0.00073	< 0.00084	< 0.00088
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.00068 U	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U	< 0.00074 U	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.00089 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	< 0.00072 U	< 0.0012 U	< 0.00078 U	< 0.00076 U	< 0.001 U	< 0.00082 U	< 0.00099 U	< 0.00073 U	< 0.00084 U	< 0.00079 U	< 0.00081 U	< 0.00077 U	< 0.00082 U	< 0.00095 U	< 0.00099 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	< 0.00082 U	< 0.0014 U	< 0.00089 U	< 0.00087 U	< 0.0012 U	< 0.00093 U	< 0.0011 U	< 0.00084 U	< 0.00096 U	< 0.00091 U	< 0.00092 U	< 0.00087 U	< 0.00094 U	< 0.0011 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.00082 U	< 0.0014 U	< 0.00088 U	< 0.00086 U	< 0.0011 U	< 0.00092 U	< 0.0011 U	< 0.00083 U	< 0.00095 U	< 0.0009 U	< 0.00091 U	< 0.00087 U	< 0.00093 U	< 0.0011 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	< 0.00059 U	< 0.00098 U	< 0.00063 U	< 0.00062 U	< 0.00083 U	< 0.00067 U	< 0.00081 U	< 0.0006 U	< 0.00069 U	< 0.00065 U	< 0.00066 U	< 0.00062 U	< 0.00067 U	< 0.00078 U	< 0.00081 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	< 0.00068 U	< 0.0011 U	< 0.00074 U	< 0.00072 U	< 0.00096 U	< 0.00077 U	< 0.00094 U	< 0.00069 U	< 0.0008 U	< 0.00075 U	< 0.00077 U	< 0.00072 U	< 0.00078 U	< 0.0009 U	< 0.00094 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00072 U	< 0.00087 U	< 0.00064 U	< 0.00074 U	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.00053 U	< 0.00089 U	< 0.00057 U	< 0.00056 U	< 0.00075 U	< 0.0006 U	< 0.00073 U	< 0.00054 U	< 0.00062 U	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.0007 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.00052 U	< 0.00086 U	< 0.00056 U	< 0.00055 U	< 0.00072 U	< 0.00058 U	< 0.00071 U	< 0.00052 U	< 0.0006 U	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00068 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00058 U	< 0.00097 U	< 0.00063 U	< 0.00062 U	< 0.00082 U	< 0.00066 U	< 0.0008 U	< 0.00059 U	< 0.00068 U	< 0.00064 U	< 0.00065 U	< 0.00062 U	< 0.00066 U	< 0.00077 U	< 0.0008 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	< 0.00053 U	< 0.00088 U	< 0.00057 U	< 0.00056 U	< 0.00074 U	< 0.00059 U	< 0.00072 U	< 0.00054 U	< 0.00061 U	< 0.00058 U	< 0.00059 U	< 0.00056 U	< 0.0006 U	< 0.00069 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	< 0.00068 U	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U	< 0.00074 U	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.00089 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00071 U	< 0.00087 U	< 0.00064 U	< 0.00073 U	< 0.00069 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.00059 U	< 0.00098 U	< 0.00064 U	< 0.00063 U	< 0.00083 U	< 0.00067 U	< 0.00081 U	< 0.0006 U	< 0.00069 U	< 0.00065 U	< 0.00066 U	< 0.00063 U	< 0.00067 U	< 0.00078 U	< 0.00081 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.001 U	< 0.00066 U	< 0.00065 U	< 0.00086 U	< 0.0007 U	< 0.00084 U	< 0.00063 U	< 0.00072 U	< 0.00068 U	< 0.00069 U	< 0.00065 U	< 0.0007 U	< 0.00081 U	< 0.00085 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.00058 U	< 0.00096 U	< 0.00062 U	< 0.00061 U	< 0.00081 U	< 0.00065 U	< 0.00079 U	< 0.00059 U	< 0.00067 U	< 0.00063 U	< 0.00064 U	< 0.00061 U	< 0.00065 U	< 0.00076 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.00054 U	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00075 U	< 0.00055 U	< 0.00063 U	< 0.0006 U	< 0.00061 U	< 0.00058 U	< 0.00062 U	< 0.00071 U	< 0.00075 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated	< 0.11	< 0.095 U	< 0.21 U	< 0.12 U	< 0.29 U	< 0.1 U	< 0.14 U	< 0.092 U	< 0.18 U	< 0.066	< 0.15 U	< 0.1 U	< 0.084 U	< 0.1 U	< 0.08 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated	< 0.0027	< 0.0024 U	< 0.0052 U	< 0.0029 U	< 0.0073 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U	< 0.0016	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0026 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	< 0.00058 U	< 0.00096 U	< 0.00062 U	< 0.00061 U	< 0.00081 U	< 0.00065 U	< 0.00079 U	< 0.00058 U	< 0.00067 U	< 0.00063 U	< 0.00064 U	< 0.00061 U	< 0.00065 U	< 0.00076 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	< 0.00068 U	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U	< 0.00074 U	< 0.00076 U	< 0.00072 U	0.00079 J	< 0.00089 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	< 0.00095 U	< 0.0016 U	< 0.001 U	< 0.001 U	< 0.0013 U	< 0.0011 U	< 0.0013 U	< 0.00096 U	< 0.0011 U	< 0.001 U	< 0.0011 U	< 0.001 U	< 0.0011 U	< 0.0012 U	< 0.0013 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	< 0.00056 U	< 0.00094 U	< 0.00061 U	< 0.0006 U	< 0.00079 U	< 0.00064 U	< 0.00077 U	< 0.00057 U	< 0.00066 U	< 0.00062 U	< 0.00063 U	< 0.0006 U	< 0.00064 U	< 0.00074 U	< 0.00077 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated	< 0.0023 U	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.00056 U	< 0.00093 U	< 0.0006 U	< 0.00059 U	< 0.00078 U	< 0.00063 U	< 0.00076 U	< 0.00057 U	< 0.00065 U	< 0.00061 U	< 0.00062 U	< 0.00059 U	< 0.00063 U	< 0.00073 U	< 0.00076 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00063 U	< 0.00073 U	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.00075 U	< 0.0013 U	< 0.00081 U	< 0.0008 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00077 U	< 0.00088 U	< 0.00083 U	< 0.00084 U	< 0.0008 U	< 0.00086 U	< 0.00099 U	< 0.001 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	< 0.00061 U	< 0.001 U	< 0.00066 U	< 0.00064 U	< 0.00086 U	< 0.00069 U	< 0.00084 U	< 0.00062 U	< 0.00071 U	< 0.00067 U	< 0.00068 U	< 0.00065 U	< 0.00069 U	< 0.0008 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	< 0.0006 U	< 0.001 U	< 0.00065 U	< 0.00064 U	< 0.00085 U	< 0.00068 U	< 0.00083 U	< 0.00061 U	< 0.0007 U	< 0.00066 U	< 0.00067 U	< 0.00064 U	< 0.00068 U	< 0.00079 U	< 0.00083 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	< 0.00044 U	< 0.00072 U	< 0.00047 U	< 0.00046 U	< 0.00061 U	< 0.00049 U	< 0.0006 U	< 0.00044 U	< 0.00051 U	< 0.00048 U	< 0.00049 U	< 0.00046 U	< 0.00049 U	< 0.00057 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.00058 U	< 0.00097 U	< 0.00062 U	< 0.00061 U	< 0.00082 U	< 0.00066 U	< 0.0008 U	< 0.00059 U	< 0.00068 U	< 0.00064 U	< 0.00065 U	< 0.00062 U	< 0.00066 U	< 0.00076 U	< 0.0008 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated	< 0.0024 U	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	< 0.0025	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0016	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0024 U	< 0.0019
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00072 U	< 0.00087 U	< 0.00064 U	< 0.00074 U	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	< 0.00055 U	< 0.00091 U	< 0.00059 U	< 0.00058 U	< 0.00077 U	< 0.00062 U	< 0.00075 U	< 0.00056 U	< 0.00064 U	< 0.0006 U	< 0.00061 U	< 0.00058 U	< 0.00062 U	< 0.00072 U	< 0.00075 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	< 0.0006 U	< 0.00099 U	< 0.00064 U	< 0.00063 U	< 0.00084 U	< 0.00067 U	< 0.00082 U	< 0.00061 U	< 0.00069 U	< 0.00065 U	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00078 U	< 0.00082 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.001 U	< 0.00065 U	< 0.00064 U	< 0.00085 U	< 0.00068 U	< 0.00083 U	< 0.00062 U	< 0.00071 U	< 0.00067 U	< 0.00068 U	< 0.00064 U	< 0.00069 U	< 0.0008 U	< 0.00083 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated	< 0.0026	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016	< 0.0036 U	< 0.0024 U	0.0028 J	< 0.0025 U	< 0.002 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated	< 0.0025	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	< U						< U					0.026	< U		
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	**1,1,2-Trichloroethane**	**Trichloroethene**	**Trichlorofluoromethane**	**Vinyl chloride**	**Xylene (m)**	**Xylene (o)**	**Xylenes (Total)**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B69	SSHS-B69-2-4 (4)	8/14/2014	850.53	2 - 4 ft	180-35818-1	Excavated	< 0.00059 U	< 0.001 U	0.0016 J	< 0.0011 U	< 0.00057 U	< 0.0018 U	< 0.00095 U	
Rear Parking Lot	SSHS-B69	DUP-18	8/14/2014	850.53	4 - 6 ft	180-35818-2	Excavated	< 0.00048 U	< 0.00083 U	< 0.00065 U	< 0.00091 U	< 0.00047 U	< 0.0015 U	< 0.00077 U	
Rear Parking Lot	SSHS-B69	SSHS-B69-4-6R (5)	8/14/2014	850.53	4 - 6 ft	180-35818-1	Excavated	< 0.00044 U	< 0.00076 U	< 0.0006 U	< 0.00084 U	< 0.00043 U	< 0.0013 U	< 0.00071 U	
Football Field	SSHS-B70	081514 01:15 SSHS-B70-6-10 (7.5)	8/14/2014	855.98	6 - 10 ft	180-35818-2	Excavated	< 0.00052 U	< 0.00088 U	< 0.0007 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00083 U	
Football Field	SSHS-B70	081514 01:15 SSHS-B70-10-14 (12.5)	8/14/2014	855.98	10 - 14 ft	180-35818-2	Excavated	< 0.00042 U	< 0.00072 U	< 0.00057 U	< 0.0008 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
Football Field	SSHS-B70	081514 01:15 SSHS-B70-2-6 (3.5)	8/14/2014	855.98	2 - 6 ft	180-35818-2	Excavated	< 0.00053 U	< 0.0009 U	< 0.00072 U	< 0.001 U	< 0.00051 U	< 0.0016 U	< 0.00085 U	
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated	< 0.00051	< 0.00087	< 0.00069	< 0.00096	< 0.00049		< 0.00082	
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.00044	< 0.00076	< 0.0006	< 0.00084	< 0.00043		< 0.00071	
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	6 - 9.5 ft	180-35858-1	Not Excavated	< 0.00045	< 0.00077	< 0.00061	< 0.00086	< 0.00044		< 0.00073	
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	10 - 15 ft	180-35818-2	Not Excavated	< 0.00048	< 0.00082	< 0.00065	< 0.00091	< 0.00046		< 0.00077	
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.00063	< 0.0011	< 0.00085	< 0.0012	< 0.00061		< 0.001	
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	2 - 6 ft	180-35818-2	Not Excavated	< 0.0005	< 0.00086	< 0.00068	< 0.00095	< 0.00049		< 0.00081	
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	6 - 10 ft	180-35818-2	Not Excavated	< 0.00053	< 0.0009	< 0.00071	< 0.00099	< 0.00051		< 0.00084	
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	10 - 15 ft	180-35818-1	Not Excavated	< 0.00048	< 0.00083	< 0.00065	< 0.00091	< 0.00047		< 0.00078	
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	2 - 6 ft	180-35818-1	Not Excavated	< 0.00049	< 0.00084	< 0.00066	< 0.00092	< 0.00047		< 0.00078	
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	6 - 10 ft	180-35818-1	Not Excavated	< 0.0005	< 0.00085	< 0.00068	< 0.00094	< 0.00048		< 0.0008	
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	10 - 15 ft	180-35818-1	Not Excavated	< 0.00045	< 0.00077	< 0.00061	< 0.00085	< 0.00043		< 0.00072	
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	2 - 6 ft	180-35818-1	Not Excavated	< 0.00046	< 0.00079	< 0.00062	< 0.00087	< 0.00045		< 0.00074	
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	8/14/2014	855.88	6 - 10 ft	180-35818-2	Not Excavated	< 0.00055	< 0.00094	< 0.00074	< 0.001	< 0.00053		< 0.00088	
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	6 - 10 ft	180-35818-1	Not Excavated	< 0.00048	< 0.00083	< 0.00065	< 0.00091	< 0.00047		< 0.00078	
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	10 - 15 ft	180-35818-2	Not Excavated	< 0.00051 U	< 0.00088 U	< 0.00069 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	2 - 6 ft	180-35818-2	Not Excavated	< 0.00055 U	< 0.00093 U	< 0.00074 U	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.00088 U	
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	6 - 10 ft	180-35818-2	Not Excavated	< 0.00062 U	< 0.0011 U	< 0.00084 U	< 0.0012 U	< 0.0006 U	< 0.0019 U	< 0.001 U	
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	10 - 13.5 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.0011 U	< 0.00084 U	< 0.0012 U	< 0.0006 U	< 0.0019 U	< 0.00099 U	
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	2 - 6 ft	180-35818-2	Not Excavated	< 0.00045 U	< 0.00076 U	< 0.0006 U	< 0.00084 U	< 0.00043 U	< 0.0013 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	2 - 6 ft	180-35818-1	Not Excavated	< 0.00052 U	< 0.00089 U	< 0.0007 U	< 0.00098 U	< 0.0005 U	< 0.0016 U	< 0.00083 U	
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	6 - 10 ft	180-35818-1	Not Excavated	< 0.00048 U	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00046 U	< 0.0015 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	10 - 15 ft	180-35776-1	Not Excavated	< 0.0004 U	< 0.00069 U	< 0.00055 U	< 0.00076 U	< 0.00039 U	< 0.0012 U	< 0.00065 U	
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	2 - 6 ft	180-35776-1	Not Excavated	< 0.00047 U	< 0.00081 U	< 0.00064 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	6 - 10 ft	180-35776-1	Not Excavated	< 0.00039 U	< 0.00067 U	< 0.00053 U	< 0.00074 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00044 U	< 0.00076 U	< 0.0006 U	< 0.00083 U	< 0.00043 U	< 0.0013 U	< 0.00071 U	
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	2 - 6 ft	180-35776-2	Not Excavated	< 0.0004 U	< 0.00068 U	< 0.00054 U	< 0.00075 U	< 0.00038 U	< 0.0012 U	< 0.00064 U	
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	2 - 6 ft	180-35776-1	Not Excavated	< 0.00051 U	< 0.00088 U	< 0.00069 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	6 - 10 ft	180-35776-1	Not Excavated	< 0.00048 U	< 0.00082 U	< 0.00065 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	10 - 14 ft	180-35818-1	Not Excavated	< 0.00045 U	< 0.00077 U	< 0.00061 U	< 0.00085 U	< 0.00043 U	< 0.0014 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	2 - 6 ft	180-35818-1	Not Excavated	< 0.00047 U	< 0.0008 U	< 0.00063 U	< 0.00088 U	< 0.00045 U	< 0.0014 U	< 0.00075 U	
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	6 - 10 ft	180-35818-2	Not Excavated	< 0.00044 U	< 0.00075 U	< 0.00059 U	< 0.00082 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	6 - 10 ft	180-35818-1	Not Excavated	< 0.00041 U	< 0.0007 U	< 0.00056 U	< 0.00078 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-2-4	1/22/2018	850.73	2 - 4 ft	180-74331-2	Excavated	< 0.13 U	< 0.12 U	0.54	< 0.073 U	< 0.18 U		< 0.12 U	< 0.21 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-4-6	1/22/2018	850.73	4 - 6 ft	180-74331-2	Excavated	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0045 U		< 0.003 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	10 - 15 ft	180-35776-2	Not Excavated	< 0.00044 U	< 0.00074 U	< 0.00059 U	< 0.00082 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	10 - 15 ft	180-35776-1	Not Excavated	< 0.00051 U	< 0.00088 U	< 0.00069 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	2 - 6 ft	180-35776-1	Not Excavated	< 0.00072 U	< 0.0012 U	< 0.00097 U	< 0.0014 U	< 0.00069 U	< 0.0022 U	< 0.0012 U	
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	6 - 10 ft	180-35776-1	Not Excavated	< 0.00043 U	< 0.00073 U	< 0.00058 U	< 0.00081 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-2-4	1/17/2018	850.70	2 - 4 ft	180-74241-2	Excavated	< 0.0027 U	< 0.0026 U	0.028	< 0.0015 U	< 0.0039 U		< 0.0026 U	< 0.0046 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	10 - 15 ft	180-35776-1	Not Excavated	< 0.00042 U	< 0.00072 U	< 0.00057 U	< 0.0008 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	2 - 6 ft	180-35776-1	Not Excavated	< 0.00047 U	< 0.00081 U	< 0.00064 U	< 0.00089 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	6 - 10 ft	180-35776-1	Not Excavated	< 0.00047 U	< 0.00081 U	< 0.00064 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	10 - 15 ft	180-35818-1	Not Excavated	< 0.00057 U	< 0.00098 U	< 0.00077 U	< 0.0011 U	< 0.00055 U	< 0.0017 U	< 0.00092 U	
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	2 - 6 ft	180-35818-1	Not Excavated	< 0.00046 U	< 0.00079 U	< 0.00062 U	< 0.00087 U	< 0.00045 U	< 0.0014 U	< 0.00074 U	
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	6 - 10 ft	180-35818-1	Not Excavated	< 0.00047 U	< 0.00081 U	< 0.00064 U	< 0.00089 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	10 - 15 ft	180-35776-1	Not Excavated	< 0.00046 U	< 0.00078 U	< 0.00062 U	< 0.00086 U	< 0.00044 U	< 0.0014 U	< 0.00073 U	
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	2 - 6 ft	180-35776-1	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00045 U	< 0.00062 U	< 0.00032 U	< 0.001 U	< 0.00053 U	
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	6 - 10 ft	180-35776-1	Not Excavated	< 0.00044 U	< 0.00075 U	< 0.0006 U	< 0.00083 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-4-6	1/12/2018	850.62	4 - 6 ft	180-74164-1	Excavated	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-2-4	1/22/2018	850.02	2 - 4 ft	180-74331-2	Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U		< 0.0028 U	< 0.005 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	10 - 15 ft	180-35776-1	Not Excavated	< 0.00048 U	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	2 - 6 ft	180-35776-2	Not Excavated	< 0.00041 U	< 0.00071 U	< 0.00056 U	< 0.00078 U	< 0.0004 U	< 0.0013 U	< 0.00066 U	
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	2 - 6 ft	180-35776-1	Not Excavated	< 0.00045 U	< 0.00077 U	< 0.00061 U	< 0.00085 U	< 0.00044 U	< 0.0014 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	6 - 10 ft	180-35776-1	Not Excavated	< 0.00046 U	< 0.00078 U	< 0.00062 U	< 0.00087 U	< 0.00044 U	< 0.0014 U	< 0.00074 U	
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-2-4	1/22/2018	852.03	2 - 4 ft	180-74331-2	Excavated	< 0.0031 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U		< 0.003 U	0.0074 J
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-4-6	1/22/2018	852.03	4 - 6 ft	180-74331-2	Excavated	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U		< 0.0028 U	< 0.0049 U
Football Field	SSHS-B9	B23482	5/11/2000	855.34	2 - 3 ft	NA	Excavated	< U		0.0041 J		< U	< U	< U	
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	10 - 12 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	14 - 16 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	4 - 6 ft	180-140136-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	6 - 8 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	8 - 10 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	10 - 12 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	14 - 16 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	6 - 8 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	8 - 10 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-4-6	6/4/2022	856.18	4 - 6 ft	180-139185-1	Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	10 - 12 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0021 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U	0.0027 J	< 0.0025 U	< 0.0029 U	0.0016 J	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	4 - 6 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0017 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0039 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0018 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0027 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0027 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0025 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0028 J,B	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0029 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	0.0029 J,B	< 0.002 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0028 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0025 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U	< 0.0013 U	< 0.0025 U	< 0.0029 U	0.0022 J,B	< 0.002 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	0.0019 J	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	0.0036 J,B	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0039 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	0.0032 J,B	< 0.002 U	< 0.0024 U	< 0.0033 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	0.0088 J	< 0.006 U						< 0.006 U	< 0.006 U			< 0.006 U			
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	0.01 J	< 0.0058 U						< 0.0058 U	< 0.0058 U			< 0.0058 U			
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	0.0077 J	< 0.0057 U						< 0.0057 U	< 0.0057 U			< 0.0057 U			
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	< 2.9 U	< 0.73 U						< 0.73 U	< 0.73 U			< 0.73 U			
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	< 0.12 U	< 0.029 U						< 0.029 U	< 0.029 U			< 0.029 U			
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-2.5	7/21/2014	855.47	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0041 U	< 0.00056 U	< 0.00057 U	< 0.00046 U	< 0.00036 U	< 0.00061 U	< 0.00042 U	< 0.00037 U	< 0.00062 U	< 0.00058 U	< 0.0013 U	< 0.00048 U	< 0.0007 U	< 0.00031 U	< 0.00062 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-2.5	7/21/2014	855.39	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0044 U	< 0.0006 U	< 0.00061 U	< 0.0005 U	< 0.00039 U	< 0.00065 U	< 0.00045 U	< 0.00039 U	< 0.00067 U	< 0.00063 U	< 0.0014 U	< 0.00052 U	< 0.00075 U	< 0.00033 U	< 0.00066 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-2.5	7/21/2014	855.97	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0081 U	< 0.0011 U	< 0.0011 U	< 0.00091 U	< 0.00072 U	< 0.0012 U	0.0066 J	< 0.00073 U	< 0.0012 U	< 0.0012 U	< 0.0025 U	< 0.00095 U	< 0.0014 U	< 0.0006 U	< 0.0012 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-2.5	7/21/2014	855.49	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0061 U	< 0.00082 U	< 0.00084 U	< 0.00069 U	< 0.00054 U	< 0.0009 U	< 0.00063 U	< 0.00055 U	< 0.00093 U	< 0.00087 U	< 0.0019 U	< 0.00071 U	< 0.001 U	< 0.00045 U	< 0.00091 U
Football Field	SSHS-FB5-E	SSHS-FB5-DUP1	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0086 U	< 0.0012 U	< 0.0012 U	< 0.00097 U	< 0.00076 U	< 0.0013 U	< 0.00088 UJ	< 0.00077 U	< 0.0013 U	< 0.0012 U	< 0.0027 U	< 0.001 U	< 0.0015 U	< 0.00064 U	< 0.0013 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-2.5	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.00051 U	< 0.0004 U	< 0.00067 U	0.0016 J	< 0.0004 U	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00053 U	< 0.00077 U	< 0.00034 U	< 0.00068 U
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	0.83	< 0.029 U						< 0.029 U	< 0.029 U			< 0.029 U			

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	4 - 6 ft	180-139185-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	< 0.006 U			< 0.4 U	< 0.4 U	< 0.4 U	< 0.006 U	< 0.006 U	< 0.006 U		< 0.006 U	< 0.006 U			
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	< 0.0058 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.0058 U	< 0.0058 U	< 0.0058 U		< 0.0058 U	< 0.0058 U			
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	< 0.0057 U			< 1.1 U	< 1.1 U	< 1.1 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.0057 U	< 0.0057 U			
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	< 0.73 U			< 0.39 U	< 0.39 U	< 0.39 U	< 0.73 U	< 0.73 U	< 0.73 U		< 0.73 U	< 0.73 U			
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	< 0.029 U			< 0.38 U	< 0.38 U	< 0.38 U	< 0.029 U	< 0.029 U	< 0.029 U		< 0.029 U	< 0.029 U			
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-2.5	7/21/2014	855.47	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00055 U	< 0.00071 U	< 0.00055 U	< 0.00066 U	< 0.00054 U	< 0.00052 U	< 0.00047 U	< 0.0005 U	< 0.0007 U		< 0.00058 U	< 0.00049 U	< 0.00045 U	< 0.00056 U	< 0.00049 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-2.5	7/21/2014	855.39	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00059 U	< 0.00076 U	< 0.00059 U	< 0.0007 U	< 0.00058 U	< 0.00056 U	< 0.00051 U	< 0.00054 U	< 0.00075 U		< 0.00062 U	< 0.00053 U	< 0.00048 U	< 0.0006 U	< 0.00053 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-2.5	7/21/2014	855.97	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0011 U	< 0.0014 U	< 0.0011 U	< 0.0013 U	< 0.0011 U	< 0.001 U	< 0.00093 U	< 0.001 U	< 0.0014 U		< 0.0011 U	< 0.00097 U	< 0.00088 U	< 0.0011 U	< 0.00097 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-2.5	7/21/2014	855.49	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00082 U	< 0.0011 U	< 0.00081 U	< 0.00097 U	< 0.0008 U	< 0.00078 U	< 0.0007 U	< 0.00075 U	< 0.001 U		< 0.00086 U	< 0.00073 U	< 0.00066 U	< 0.00083 U	< 0.00073 U
Football Field	SSHS-FB5-E	SSHS-FB5-DUP1	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0012 U	< 0.0015 U	< 0.0011 U	< 0.0014 U	< 0.0011 U	< 0.0011 U	< 0.00099 U	< 0.0011 U	< 0.0015 U		< 0.0012 U	< 0.001 U	< 0.00094 U	< 0.0012 U	< 0.001 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-2.5	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00061 U	< 0.00078 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00058 U	< 0.00052 U	< 0.00055 U	< 0.00077 U		< 0.00064 U	< 0.00054 U	< 0.00049 U	< 0.00061 U	< 0.00054 U
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	< 0.029 U			< 3.9 U	< 3.9 U	< 3.9 U	< 0.029 U	< 0.029 U	< 0.029 U		< 0.029 U	< 0.029 U			

DRAFT

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	4 - 6 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	< 0.006 U						0.0018 J					0.0035 J	< 0.006 U		
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	< 0.0058 U						< 0.012 U					0.0034 J	< 0.0058 U		
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	< 0.0057 U						< 0.011 U					< 0.027 U	< 0.0057 U		
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	< 0.73 U						< 1.5 U					< 0.73 U	< 0.73 U		
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	< 0.029 U						< 0.058 U					0.012 J	< 0.029 U		
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-2.5	7/21/2014	855.47	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00053 U	< 0.00088 U	< 0.00057 U	< 0.00056 U	< 0.00074 U	< 0.0006 U	< 0.00073 U	< 0.00054 U	< 0.00062 U	< 0.00058 U	< 0.00059 U	< 0.00056 U	< 0.0006 U	< 0.0007 U	< 0.00073 U
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-2.5	7/21/2014	855.39	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00057 U	< 0.00094 U	< 0.00061 U	< 0.0006 U	< 0.00079 U	< 0.00064 U	< 0.00078 U	< 0.00058 U	< 0.00066 U	< 0.00062 U	< 0.00063 U	< 0.0006 U	< 0.00064 U	< 0.00075 U	< 0.00078 U
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-2.5	7/21/2014	855.97	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.001 U	< 0.0017 U	< 0.0011 U	< 0.0011 U	< 0.0015 U	< 0.0012 U	< 0.0014 U	< 0.0011 U	< 0.0012 U	< 0.0011 U	< 0.0012 U	< 0.0011 U	< 0.0012 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-2.5	7/21/2014	855.49	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00079 U	< 0.0013 U	< 0.00084 U	< 0.00083 U	< 0.0011 U	< 0.00089 U	< 0.0011 U	< 0.0008 U	< 0.00091 U	< 0.00086 U	< 0.00088 U	< 0.00083 U	< 0.00089 U	< 0.001 U	< 0.0011 U
Football Field	SSHS-FB5-E	SSHS-FB5-DUP1	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0011 U	< 0.0018 U	< 0.0012 U	< 0.0012 U	< 0.0016 U	< 0.0013 U	< 0.0015 U	< 0.0011 U	< 0.0013 U	< 0.0012 U	< 0.0012 U	< 0.0012 U	< 0.0013 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-2.5	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00058 U	< 0.00097 U	< 0.00062 U	< 0.00061 U	< 0.00082 U	< 0.00066 U	< 0.0008 U	< 0.00059 U	< 0.00068 U	< 0.00064 U	< 0.00065 U	< 0.00062 U	< 0.00066 U	< 0.00076 U	< 0.0008 U
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	< 0.029 U						0.19					0.15	< 0.029 U		

TABLE 5-6D
Subsurface Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	12 - 14 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	14 - 16 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	6 - 8 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	8 - 10 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-4-6	6/4/2022	857.21	4 - 6 ft	180-139185-1	Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	10 - 12 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	14 - 16 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	4 - 6 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	6 - 8 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	8 - 10 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	10 - 12 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	12 - 14 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	14 - 16 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	4 - 6 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	6 - 8 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	8 - 10 ft	180-139185-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	10 - 12 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	14 - 16 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	4 - 6 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	6 - 8 ft	180-140136-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	8 - 10 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	10 - 12 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	14 - 16 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	4 - 6 ft	180-140136-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	6 - 8 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	8 - 10 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	10 - 12 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	12 - 14 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	14 - 16 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	4 - 6 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	6 - 8 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	8 - 10 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	6 - 8 ft	NA	Not Excavated	< 0.006 U		< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	
Football Field	SSHS-FB3	B23497	6/29/2000	856.72	3 - 4 ft	NA	Excavated	< 0.0058 U		0.0086		< 0.0058 U	< 0.0058 U	< 0.0058 U	
Football Field	SSHS-FB4	B23498	6/29/2000	856.18	3 - 4 ft	NA	Excavated	< 0.0057 U		0.14		< 0.0057 U	< 0.0057 U	< 0.0057 U	
Football Field	SSHS-FB5	B23499	6/29/2000	855.33	2 - 4 ft	NA	Excavated	< 0.73 U		110		< 0.73 U	< 0.73 U	< 0.73 U	
Football Field	SSHS-FB5	B23400	6/29/2000	855.33	6 - 8 ft	NA	Excavated	< 0.029 U		11		< 0.029 U	< 0.029 U	< 0.029 U	
Football Field	SSHS-FB5-A	SSHS-FB5-A-SUB-2.5	7/21/2014	855.47	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.0004 U	< 0.00068 U	0.029	< 0.00076 U	< 0.00039 U	< 0.0012 U	< 0.00064 U	
Football Field	SSHS-FB5-B	SSHS-FB5-B-SUB-2.5	7/21/2014	855.39	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00043 U	< 0.00073 U	0.029	< 0.00081 U	< 0.00041 U	< 0.0013 U	< 0.00069 U	
Football Field	SSHS-FB5-C	SSHS-FB5-C-SUB-2.5	7/21/2014	855.97	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00079 U	< 0.0014 U	0.28	< 0.0015 U	< 0.00076 U	< 0.0024 U	< 0.0013 U	
Football Field	SSHS-FB5-D	SSHS-FB5-D-SUB-2.5	7/21/2014	855.49	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00059 U	< 0.001 U	0.2	< 0.0011 U	< 0.00057 U	< 0.0018 U	< 0.00095 U	
Football Field	SSHS-FB5-E	SSHS-FB5-DUP1	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00084 U	< 0.0014 U	0.0052 J	< 0.0016 U	< 0.00081 U	< 0.0025 U	< 0.0013 U	
Football Field	SSHS-FB5-E	SSHS-FB5-E-SUB-2.5	7/21/2014	855.42	2.5 - 2.5 ft	180-35053-1	Excavated	< 0.00044 U	< 0.00075 U	0.0015 J	< 0.00083 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Football Field	SSHS-FB8	B23405	6/29/2000	856.63	4 - 6 ft	NA	Excavated	< 0.029 U		0.0073 J		< 0.029 U	0.0096 J	< 0.029 U	

DRAFT

								Emerging C									
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_PS-FD-39	PS-FD-39	855.22	6 - 8 ft	180-57995-1	Not Excavated			< 48 U									
Rear Parking Lot	PDI6-B5105	DUP-42-20230118	DUP-42	853.71	12 - 14 ft	1801508221	Not Excavated	< 100 U											
Rear Parking Lot	PDI6-B5105	DUP-42-20230118	DUP-42	853.71	12 - 14 ft	1801508222	Not Excavated				< 0.044 U	< 0.035 U	< 0.042 U	< 0.048 U	< 0.044 U	< 0.028 U	< 0.045 U	< 0.035 U	< 0.027 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-0.17-2-20230118	SSHS-PDI6-B5106-SUB-0.17-2	851.23	0.17-2	1801508222	Not Excavated				< 0.045 U	< 0.035 U	< 0.043 U	< 0.049 U	< 0.045 U	< 0.028 U	< 0.046 U	< 0.035 U	< 0.027 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	851.23	10 - 12 ft	1801508221	Not Excavated	< 110 U											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	851.23	10 - 12 ft	1801508222	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.029 U	< 0.047 U	< 0.036 U	< 0.028 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	852.78	10 - 12 ft	1801518942	Not Excavated	< 110 U											
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	850.65	10.65-12.65 ft	1801782961	Not Excavated		< 260 U										
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	856.38	10 - 12 ft	180-80227-2	Not Excavated			< 350 U									
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	854.93	10 - 12 ft	180-80227-3	Not Excavated			< 16 U									
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	856.56	10 - 12 ft	180-80227-1	Not Excavated			< 68 U									
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	856.14	10 - 12 ft	180-89521-1	Not Excavated			< 110 U									
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	856.00	10 - 12 ft	180-89521-1	Not Excavated			< 110 U									
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	855.35	10 - 12 ft	180-98520-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	851.57	10 - 12 ft	180-100361-1	Not Excavated			< 110 U									
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	856.51	10 - 12 ft	180-108826-2	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	856.64	10 - 12 ft	180-127265-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	856.07	10 - 12 ft	180-127205-2	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	856.37	10 - 12 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	855.95	10 - 12 ft	1801218221	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	856.50	10 - 12 ft	1801214741	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	858.24	10 - 12 ft	180-127265-2	Not Excavated				< 0.055 U	< 0.043 U	< 0.053 U	< 0.059 U	< 0.055 U	< 0.034 U	< 0.056 U	< 0.043 U	< 0.033 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	857.91	10 - 12 ft	180-127265-2	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	856.72	10 - 12 ft	180-127415-1	Not Excavated			< 110 U									
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	856.42	10 - 12 ft	180-127595-2	Not Excavated			< 110 U									
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	856.00	10 - 12 ft	180-127595-2	Not Excavated			< 140 U	< 0.062 U	< 0.049 U	< 0.06 U	< 0.067 U	< 0.062 U	< 0.039 U	< 0.063 U	< 0.049 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	855.97	10 - 12 ft	180-127140-1	Not Excavated			< 430 U									
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	855.73	10 - 12 ft	180-127066-2	Not Excavated			< 34 U	< 0.052 U	< 0.042 U	< 0.05 U	< 0.057 U	< 0.052 U	< 0.033 U	< 0.054 U	< 0.042 U	< 0.032 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	852.44	10 - 12 ft	180-58309-2	Not Excavated			< 41									
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	851.65	10 - 12 ft	180-35818-2	Not Excavated			< 44 U									
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	850.41	10 - 12 ft	180-35818-1	Not Excavated			< 42 U									
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	850.45	10 - 12 ft	180-35818-1	Not Excavated			< 41 U									
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	855.66	10 - 12 ft	180-66622-2	Not Excavated			< 53 U									
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	856.38	10 - 12 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	856.18	10 - 12 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	857.21	10 - 12 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	856.60	10 - 12 ft	180-139185-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	856.27	10 - 12 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	856.66	10 - 12 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	856.60	10 - 12 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	856.61	10 - 12 ft	180-139185-1	Not Excavated			< 110 U									
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	855.92	10 - 13.5 ft	180-35818-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	856.00	10 - 14 ft	180-35818-1	Not Excavated			< 41 U									
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	854.77	10 - 14.5 ft	180-35776-1	Not Excavated			< 42 U									
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	856.08	10 - 15 ft	180-35818-2	Not Excavated			< 40									
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	856.25	10 - 15 ft	180-35818-1	Not Excavated			< 41									
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	855.88	10 - 15 ft	180-35818-1	Not Excavated			< 40									
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	855.75	10 - 15 ft	180-35818-2	Not Excavated			< 40 U									
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	856.60	10 - 15 ft	180-35776-1	Not Excavated			< 41 U									
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	855.22	2 - 4 ft	180-35776-2	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	855.54	10 - 15 ft	180-35776-1	Not Excavated			< 44 U									
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	854.20	10 - 15 ft	180-35776-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	855.86	10 - 15 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	855.00	10 - 15 ft	180-35776-1	Not Excavated			< 44 U									
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	853.90	10 - 15 ft	180-35776-1	Not Excavated			< 43 U									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	851.23	12 - 14 ft	1801508221	Not Excavated	< 120 U											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	851.23	12 - 14 ft	1801508222	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.050 U	< 0.039 U	< 0.030 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	852.78	12 - 14 ft	1801518942	Not Excavated	< 110 U											
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	854.78	12 - 14 ft	180-80154-1	Not Excavated			< 17 U									
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	855.94	12 - 14 ft	180-80225-1	Not Excavated			< 35 U									
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	854.99	12 - 14 ft	180-80105-1	Not Excavated			< 17 U									
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	856.38	12 - 14 ft	180-80227-2	Not Excavated			< 810 U									
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	855.30	12 - 14 ft	180-89521-1	Not Excavated			< 110 U									
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	856.14	12 - 14 ft	180-89521-1	Not Excavated			< 230 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 PS-FD-39	PS-FD-39	855.22	6 - 8 ft	180-57995-1	Not Excavated												
Rear Parking Lot	PDI6-B5105	DUP-42-20230118	DUP-42	853.71	12 - 14 ft	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5105	DUP-42-20230118	DUP-42	853.71	12 - 14 ft	1801508222	Not Excavated	< 0.029 U	< 0.020 U	< 0.030 U	< 0.040 U	< 0.049 U	< 0.038 U	< 0.034 U	< 0.019 U	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-0.17-2-20230118	SSHS-PDI6-B5106-SUB-0.17-2	851.23	0.17-2	1801508222	Not Excavated	< 0.029 U	< 0.021 U	< 0.031 U	< 0.040 U	< 0.050 U	< 0.038 U	< 0.035 U	< 0.020 U	< 0.039 U	< 0.033 U	< 0.025 U	< 0.021 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	851.23	10 - 12 ft	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	851.23	10 - 12 ft	1801508222	Not Excavated	< 0.029 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	852.78	10 - 12 ft	1801518942	Not Excavated												
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	850.65	10.65-12.65 ft	1801782961	Not Excavated												
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	856.38	10 - 12 ft	180-80227-2	Not Excavated												
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	854.93	10 - 12 ft	180-80227-3	Not Excavated												
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	856.56	10 - 12 ft	180-80227-1	Not Excavated												
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	856.14	10 - 12 ft	180-89521-1	Not Excavated												
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	856.00	10 - 12 ft	180-89521-1	Not Excavated												
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	855.35	10 - 12 ft	180-98520-1	Not Excavated												
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	851.57	10 - 12 ft	180-100361-1	Not Excavated												
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	856.51	10 - 12 ft	180-108826-2	Not Excavated												
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	856.64	10 - 12 ft	180-127265-1	Not Excavated												
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	856.07	10 - 12 ft	180-127205-2	Not Excavated												
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	856.37	10 - 12 ft	1801217472	Not Excavated	< 0.042 U	< 0.036 U	< 0.081 U	< 0.20 U	< 0.085 U	< 0.076 U	< 0.054 U	< 0.051 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	855.95	10 - 12 ft	1801218221	Not Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	856.50	10 - 12 ft	1801214741	Not Excavated	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	858.24	10 - 12 ft	180-127265-2	Not Excavated	< 0.035 U	< 0.025 U	< 34 U	< 0.049 U	< 0.061 U	< 0.047 U	< 0.042 U	< 34 U	< 0.048 U	< 0.04 U	< 0.031 U	< 0.026 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	857.91	10 - 12 ft	180-127265-2	Not Excavated												
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	856.72	10 - 12 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	856.42	10 - 12 ft	180-127595-2	Not Excavated												
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	856.00	10 - 12 ft	180-127595-2	Not Excavated	< 0.04 U	< 0.029 U	< 34 U	< 0.056 U	< 0.069 U	< 0.053 U	< 0.048 U	< 34 U	< 0.054 U	< 0.045 U	< 0.035 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	855.97	10 - 12 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	855.73	10 - 12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.024 U	< 34 U	0.05 J	< 0.058 U	< 0.045 U	< 0.04 U	< 34 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	852.44	10 - 12 ft	180-58309-2	Not Excavated												
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	851.65	10 - 12 ft	180-35818-2	Not Excavated												
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	850.41	10 - 12 ft	180-35818-1	Not Excavated												
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	850.45	10 - 12 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	855.66	10 - 12 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	856.38	10 - 12 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	856.18	10 - 12 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	857.21	10 - 12 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	856.60	10 - 12 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	856.27	10 - 12 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	856.66	10 - 12 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	856.60	10 - 12 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	856.61	10 - 12 ft	180-139185-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	855.92	10 - 13.5 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	856.00	10 - 14 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	854.77	10 - 14.5 ft	180-35776-1	Not Excavated												
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	856.08	10 - 15 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	856.25	10 - 15 ft	180-35818-1	Not Excavated												
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	855.88	10 - 15 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	855.75	10 - 15 ft	180-35818-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	856.60	10 - 15 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 DUP-10	DUP-10	855.22	2 - 4 ft	180-35776-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	855.54	10 - 15 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	854.20	10 - 15 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	855.86	10 - 15 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	855.00	10 - 15 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	853.90	10 - 15 ft	180-35776-1	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	851.23	12 - 14 ft	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	851.23	12 - 14 ft	1801508222	Not Excavated	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	852.78	12 - 14 ft	1801518942	Not Excavated												
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	854.78	12 - 14 ft	180-80154-1	Not Excavated												
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	855.94	12 - 14 ft	180-80225-1	Not Excavated												
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	854.99	12 - 14 ft	180-80105-1	Not Excavated												
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	856.38	12 - 14 ft	180-80227-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	855.30	12 - 14 ft	180-89521-1	Not Excavated												
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	856.14	12 - 14 ft	180-89521-1	Not Excavated												

DRAFT

																				Emerging C
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100										
Restricted - Residential								13000	13000	13000										
Protection of Groundwater								100	100	100										
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status													
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	855.35	12 - 14 ft	180-98520-1	Not Excavated			< 120 U										
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	853.79	12 - 14 ft	180-123398-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	853.71	12 - 14 ft	1801217472	Not Excavated	< 110 U			< 0.36 U	< 0.024 U	< 0.027 U	< 0.038 U	< 0.021 U	< 0.065 U	< 0.034 U	< 0.028 U	< 0.030 U
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	851.57	12 - 14 ft	180-100361-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	854.07	12 - 14 ft	1801162471	Not Excavated	< 100 U			< 0.35 U	< 0.024 U	0.43 B	< 0.037 U	< 0.021 U	< 0.064 U	< 0.033 U	< 0.028 U	< 0.030 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	856.64	12 - 14 ft	180-127265-1	Not Excavated			< 110 U	< 0.046 U	< 0.037 U	< 0.044 U	< 0.05 U	< 0.046 U	< 0.029 U	< 0.047 U	< 0.037 U	< 0.028 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	856.07	12 - 14 ft	180-127205-2	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	853.71	12 - 14 ft	1801215482	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.066 J	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U	< 0.032 U	< 0.035 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	856.37	12 - 14 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.066 U	< 0.035 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	855.95	12 - 14 ft	1801218221	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.036 U	< 0.030 U	< 0.032 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	856.50	12 - 14 ft	1801214741	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U	< 0.030 U	< 0.032 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	857.91	12 - 14 ft	180-127265-2	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	856.72	12 - 14 ft	180-127415-1	Not Excavated			< 110 U										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	856.42	12 - 14 ft	180-127595-2	Not Excavated			< 110 U										
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	856.00	12 - 14 ft	180-127595-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.05 U	< 0.039 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	855.97	12 - 14 ft	180-127140-1	Not Excavated			< 550 U										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	855.73	12 - 14 ft	180-127066-2	Not Excavated			< 130 U	< 0.059 U	< 0.047 U	0.24 J	< 0.064 U	< 0.059 U	< 0.037 U	< 0.06 U	< 0.047 U	< 0.036 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	852.44	12 - 14 ft	180-58309-2	Not Excavated			< 42										
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	855.66	12 - 14 ft	180-66622-2	Not Excavated			< 53 U										
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	856.38	12 - 14 ft	180-140136-1	Not Excavated			< 120 U										
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	856.18	12 - 14 ft	180-139185-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	857.21	12 - 14 ft	180-139185-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	856.60	12 - 14 ft	180-139185-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	856.27	12 - 14 ft	180-139185-1	Not Excavated			< 100 U										
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	856.66	12 - 14 ft	180-140136-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	856.60	12 - 14 ft	180-140136-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	856.61	12 - 14 ft	180-139185-1	Not Excavated			< 110 U										
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	852.95	12 - 15.5 ft	180-35818-2	Not Excavated			< 44 U										
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	851.23	14 - 16 ft	1801519451	Not Excavated	< 120 U												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	851.23	14 - 16 ft	1801519452	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U	< 0.040 U	< 0.031 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	852.78	14 - 16 ft	1801518942	Not Excavated	< 110 U												
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	854.95	14 - 16 ft	180-90324-1	Not Excavated			< 110 U										
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	854.80	14 - 16 ft	180-90275-1	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	853.65	14 - 16 ft	1801163651	Not Excavated	< 110 U												
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	854.07	14 - 16 ft	1801162471	Not Excavated	< 110 U												
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	856.64	14 - 16 ft	180-127265-1	Not Excavated			< 34 U										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	856.07	14 - 16 ft	180-127205-2	Not Excavated			< 130 U										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	852.29	14 - 16 ft	1801214241	Not Excavated	< 120 U												
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	852.29	14 - 16 ft	1801217472	Not Excavated				< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	853.77	14 - 16 ft	1801218221	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	852.15	14 - 16 ft	180-121474-1	Not Excavated			< 120 U										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	856.89	14 - 16 ft	1801217041	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	853.37	14 - 16 ft	1801214241	Not Excavated	< 140 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U	< 0.036 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	857.50	14 - 16 ft	1801217051	Not Excavated	< 110 U			< 0.36 U	< 0.025 U	< 0.028 U	< 0.038 U	< 0.022 U	< 0.066 U	< 0.034 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	856.75	14 - 16 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	855.33	14 - 16 ft	1801215481	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U	< 0.042 U	< 0.034 U	< 0.037 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	852.28	14 - 16 ft	1801215481	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.080 U	< 0.042 U	< 0.035 U	< 0.037 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	852.20	14 - 16 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.039 J	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U	< 0.032 U	< 0.035 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	853.71	14 - 16 ft	1801215482	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.046 J	< 0.046 U	< 0.026 U	< 0.078 U	< 0.041 U	< 0.034 U	< 0.036 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	856.37	14 - 16 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	855.95	14 - 16 ft	1801218221	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	856.50	14 - 16 ft	1801214741	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U	< 0.030 U	< 0.032 U
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	855.99	14 - 16 ft	180-123901-2	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	0.38	0.028 J	< 0.079 U	< 0.041 U	< 0.034 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	858.24	14 - 16 ft	180-127265-2	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.05 U	< 0.039 U	< 0.03 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	857.91	14 - 16 ft	180-127265-2	Not Excavated			< 110 U										
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	856.72	14 - 16 ft	180-127415-1	Not Excavated			< 110 U										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	856.42	14 - 16 ft	180-127595-2	Not Excavated			< 110 U										
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	856.00	14 - 16 ft	180-127595-2	Not Excavated			< 110 U										
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	855.97	14 - 16 ft	180-127140-1	Not Excavated			< 550 U										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	855.73	14 - 16 ft	180-127066-2	Not Excavated			< 120 U	< 0.053 U	< 0.042 U	0.23	< 0.057 U	< 0.053 U	< 0.033 U	< 0.054 U	< 0.042 U	< 0.032 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	852.44	14 - 16 ft	180-58309-2	Not Excavated			< 40										
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_DW-FD-1	DW-FD-1	855.66	14 - 16 ft	180-66622-2	Not Excavated			< 53 U										
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	855.66	14 - 16 ft	180-66622-2	Not Excavated			< 54 U										
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	856.38	14 - 16 ft	180-140136-1	Not Excavated			< 110 U										

DRAFT

TABLE 5-6E
Subsurface Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	855.35	12 - 14 ft	180-98520-1	Not Excavated												
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	853.79	12 - 14 ft	180-123398-1	Not Excavated												
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	853.71	12 - 14 ft	1801217472	Not Excavated	< 0.041 U	< 0.035 U	< 0.080 U	< 0.19 U	< 0.084 U	< 0.075 U	< 0.053 U	< 0.050 U	< 0.035 U	< 0.24 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	851.57	12 - 14 ft	180-100361-1	Not Excavated												
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	854.07	12 - 14 ft	1801162471	Not Excavated	< 0.040 U	< 0.034 U	< 0.078 U	0.37 BJ	< 0.082 U	< 0.073 U	< 0.052 U	< 0.049 U	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	856.64	12 - 14 ft	180-127265-1	Not Excavated	< 0.03 U	< 0.021 U	< 34 U	< 0.041 U	< 0.051 U	< 0.04 U	< 0.036 U	< 34 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	856.07	12 - 14 ft	180-127205-2	Not Excavated												
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	853.71	12 - 14 ft	1801215482	Not Excavated	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	856.37	12 - 14 ft	1801217472	Not Excavated	< 0.042 U	< 0.036 U	< 0.081 U	< 0.20 U	< 0.085 U	< 0.076 U	< 0.053 U	< 0.050 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	855.95	12 - 14 ft	1801218221	Not Excavated	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	856.50	12 - 14 ft	1801214741	Not Excavated	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.079 U	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	857.91	12 - 14 ft	180-127265-2	Not Excavated												
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	856.72	12 - 14 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	856.42	12 - 14 ft	180-127595-2	Not Excavated												
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	856.00	12 - 14 ft	180-127595-2	Not Excavated	< 0.032 U	< 0.022 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	855.97	12 - 14 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	855.73	12 - 14 ft	180-127066-2	Not Excavated	< 0.038 U	< 0.027 U	< 34 U	< 0.053 U	< 0.065 U	< 0.05 U	< 0.045 U	< 34 U	< 0.052 U	< 0.043 U	0.039 J	< 0.028 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	852.44	12 - 14 ft	180-58309-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	855.66	12 - 14 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	856.38	12 - 14 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	856.18	12 - 14 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	857.21	12 - 14 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	856.60	12 - 14 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	856.27	12 - 14 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	856.66	12 - 14 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	856.60	12 - 14 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	856.61	12 - 14 ft	180-139185-1	Not Excavated												
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	852.95	12 - 15.5 ft	180-35818-2	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	851.23	14 - 16 ft	1801519451	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	851.23	14 - 16 ft	1801519452	Not Excavated	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	852.78	14 - 16 ft	1801518942	Not Excavated												
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	854.95	14 - 16 ft	180-90324-1	Not Excavated												
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	854.80	14 - 16 ft	180-90275-1	Not Excavated												
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	853.65	14 - 16 ft	1801163651	Not Excavated												
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	854.07	14 - 16 ft	1801162471	Not Excavated												
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	856.64	14 - 16 ft	180-127265-1	Not Excavated												
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	856.07	14 - 16 ft	180-127205-2	Not Excavated												
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	852.29	14 - 16 ft	1801214241	Not Excavated												
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	852.29	14 - 16 ft	1801217472	Not Excavated	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.054 U	< 0.051 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	853.77	14 - 16 ft	1801218221	Not Excavated	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	852.15	14 - 16 ft	180-121474-1	Not Excavated												
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	856.89	14 - 16 ft	1801217041	Not Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	853.37	14 - 16 ft	1801214241	Not Excavated	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	857.50	14 - 16 ft	1801217051	Not Excavated	< 0.041 U	< 0.035 U	< 0.081 U	0.36 J	< 0.085 U	< 0.076 U	< 0.053 U	< 0.050 U	< 0.035 U	< 0.25 U	0.25 J	< 0.38 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	856.75	14 - 16 ft	1801213101	Not Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	855.33	14 - 16 ft	1801215481	Not Excavated	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.064 U	< 0.061 U	< 0.043 U	< 0.30 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	852.28	14 - 16 ft	1801215481	Not Excavated	0.055 J	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.065 U	< 0.061 U	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	852.20	14 - 16 ft	1801213101	Not Excavated	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	853.71	14 - 16 ft	1801215482	Not Excavated	0.10 J	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	0.15 J	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	856.37	14 - 16 ft	1801217472	Not Excavated	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	855.95	14 - 16 ft	1801218221	Not Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	856.50	14 - 16 ft	1801214741	Not Excavated	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.080 U	< 0.056 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	855.99	14 - 16 ft	180-123901-2	Not Excavated	< 0.049 U	< 0.042 U	< 34 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 34 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	858.24	14 - 16 ft	180-127265-2	Not Excavated	0.071 J	< 0.023 U	< 34 U	< 0.044 U	< 0.054 U	0.061 J	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	857.91	14 - 16 ft	180-127265-2	Not Excavated												
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	856.72	14 - 16 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	856.42	14 - 16 ft	180-127595-2	Not Excavated												
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	856.00	14 - 16 ft	180-127595-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	855.97	14 - 16 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	855.73	14 - 16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.024 U	< 34 U	< 0.047 U	< 0.058 U	< 0.045 U	< 0.041 U	< 34 U	< 0.046 U	< 0.039 U	< 0.03 U	< 0.025 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	852.44	14 - 16 ft	180-58309-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_DW-FD-1	DW-FD-1	855.66	14 - 16 ft	180-66622-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	855.66	14 - 16 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	856.38	14 - 16 ft	180-140136-1	Not Excavated												

DRAFT

								Emerging C									
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	856.18	14 - 16 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	857.21	14 - 16 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	856.60	14 - 16 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	856.27	14 - 16 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	856.66	14 - 16 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	856.60	14 - 16 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	856.61	14 - 16 ft	180-139185-1	Not Excavated			< 110 U									
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	855.26	6 - 8 ft	180-120245-1	Not Excavated			< 110 U	< 0.39 UJ	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	855.66	10 - 12 ft	180-119861-1	Not Excavated			< 110 U	< 0.41 U	< 0.028 U	0.099 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	856.09	4 - 6 ft	1801214241	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Northern Athletic Field	A6-CB2-S1	SSHS-IRM5A2-A6-CB2-S1-20221208	SSHS-IRM5A2-A6-CB2-S1	854.40	2-4	1801490391	Not Excavated				< 0.046 U	< 0.037 U	0.14 J	< 0.050 U	< 0.046 U	< 0.029 U	< 0.047 U	< 0.037 U	< 0.028 U
Northern Athletic Field	A6-CB2-S2	SSHS-IRM5A2-A6-CB2-S2-20221208	SSHS-IRM5A2-A6-CB2-S2	854.26	2-4	1801490391	Not Excavated				< 0.055 U	< 0.043 U	0.098 J	< 0.059 U	< 0.055 U	< 0.034 U	< 0.056 U	< 0.043 U	< 0.033 U
Northern Athletic Field	A6-CB2-S3	SSHS-IRM5A2-A6-CB2-S3-20221208	SSHS-IRM5A2-A6-CB2-S3	854.23	2-4	1801490391	Not Excavated				< 0.053 U	< 0.042 U	0.23	< 0.058 U	< 0.053 U	< 0.033 U	< 0.054 U	0.12 J	< 0.032 U
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4-20230118	SSHS-PDI6-B5105-SUB-2.4	853.71	2-4	1801508221	Not Excavated	< 120 U											
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4-20230118	SSHS-PDI6-B5105-SUB-2.4	853.71	2-4	1801508222	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U	< 0.055 U	< 0.042 U	< 0.032 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-2.4-20230118	SSHS-PDI6-B5106-SUB-2.4	851.23	2-4	1801508221	Not Excavated	< 110 U											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-2.4-20230118	SSHS-PDI6-B5106-SUB-2.4	851.23	2-4	1801508222	Not Excavated				< 0.048 U	< 0.038 U	0.067 J	0.055 J	< 0.048 U	< 0.030 U	< 0.049 U	< 0.038 U	< 0.029 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2.4-20230209	SSHS-PDI6-B5109-SUB-2.4	852.78	2 - 4 ft	1801518942	Not Excavated	< 120 UT											
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	856.72	2 - 4 ft	180-116404-1	Not Excavated			< 120 U									
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	855.26	2 - 4 ft	180-80225-3	Not Excavated			< 17 U									
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	856.10	2 - 4 ft	180-80106-1	Not Excavated			< 42 U									
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	854.99	2 - 4 ft	180-80105-1	Not Excavated			< 17 U									
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	855.10	2 - 4 ft	180-90380-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	853.34	2 - 4 ft	1801164042	Not Excavated	< 130 U			< 0.43 U	< 0.029 U	0.13 BJ	< 0.046 U	< 0.026 U	< 0.078 U	< 0.041 U	0.039 J	< 0.036 U
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	856.06	2 - 4 ft	180-116404-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	856.76	2 - 4 ft	180-116404-1	Not Excavated			< 100 U									
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	857.46	2 - 4 ft	180-116462-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	857.46	2 - 4 ft	180-116462-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	858.35	2 - 4 ft	180-116462-1	Not Excavated			< 470 U									
Northern Athletic Field	SSHS-B3225	122119 10:30_SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	853.42	2 - 4 ft	180-100361-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3226	122119 10:30_SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	853.22	2 - 4 ft	180-100362-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3227	012520 10:00_SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	853.19	2 - 4 ft	180-101497-4	Not Excavated			< 130 U									
Northern Athletic Field	SSHS-B3228	122119 10:30_SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	853.57	2 - 4 ft	180-100362-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	855.71	2 - 4 ft	180-100362-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	858.02	2 - 4 ft	180-100363-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	857.46	2 - 4 ft	180-100363-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	858.40	2 - 4 ft	180-100363-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	857.06	2 - 4 ft	180-100363-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3257	122119 10:30_SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	858.41	2 - 4 ft	180-100363-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3259	122119 10:30_SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	857.33	2 - 4 ft	180-100363-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	858.57	2 - 4 ft	180-100363-1	Not Excavated			< 360 U									
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	856.35	2 - 4 ft	180-116404-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	856.00	2 - 4 ft	180-100380-1	Not Excavated			< 130 U									
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	856.25	2 - 4 ft	180-100380-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	856.88	2 - 4 ft	180-100380-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	856.35	2 - 4 ft	180-100380-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	855.54	2 - 4 ft	180-100148-5	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	856.90	2 - 4 ft	180-100148-6	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	855.68	2 - 4 ft	180-100148-4	Not Excavated			< 230 U									
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	856.43	2 - 4 ft	180-100148-6	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	851.73	2 - 4 ft	180-100148-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	852.38	2 - 4 ft	180-100148-1	Not Excavated			< 630 U									
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	855.50	2 - 4 ft	180-108826-2	Not Excavated			< 120 U									
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	855.64	2 - 4 ft	180-108826-1	Not Excavated			< 110 U									
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	855.34	2 - 4 ft	180-108826-1	Not Excavated			< 110 U									
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	855.25	2 - 4 ft	180-108826-1	Not Excavated			< 120 U									
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	855.68	2 - 4 ft	180-108826-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	858.11	2 - 4 ft	1801164621	Not Excavated	< 120 U											
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	858.11	2 - 4 ft	1801164622	Not Excavated	< 110 U			< 0.41 U	< 0.027 U	0.23 B	< 0.043 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	858.42	2 - 4 ft	180-116462-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	858.46	2 - 4 ft	180-116462-1	Not Excavated			< 630 U									
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	858.31	2 - 4 ft	180-116462-4	Not Excavated			< 120 U	< 0.42 U	< 0.028 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.04 U	< 0.033 U	< 0.035 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	858.30	2 - 4 ft	180-116462-4	Not Excavated			< 130 U	< 0.49 U	< 0.033 U	< 0.037 UJ	< 0.051 U	< 0.029 U	< 0.088 U	< 0.046 U	< 0.038 U	< 0.041 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	858.46	2 - 4 ft	1801164622	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	0.19 BJ	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U	< 0.031 U	< 0.033 U

TABLE 5-6E
Subsurface Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	856.18	14 - 16 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	857.21	14 - 16 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	856.60	14 - 16 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	856.27	14 - 16 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	856.66	14 - 16 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	856.60	14 - 16 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	856.61	14 - 16 ft	180-139185-1	Not Excavated												
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	855.26	6 - 8 ft	180-120245-1	Not Excavated	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 34 U	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 UJ
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	855.66	10 - 12 ft	180-119861-1	Not Excavated	0.049 J	< 0.04 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 UJ	< 0.06 U	< 0.056 U	< 0.04 U	< 0.28 UJ	< 0.17 UJ	< 0.43 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	856.09	4 - 6 ft	1801214241	Not Excavated	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	A6-CB2-S1	SSHS-IRM5A2-A6-CB2-S1-20221208	SSHS-IRM5A2-A6-CB2-S1	854.40	2-4	1801490391	Not Excavated	0.033 J	< 0.021 U	< 0.032 U	0.67	0.13 J	< 0.040 U	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-CB2-S2	SSHS-IRM5A2-A6-CB2-S2-20221208	SSHS-IRM5A2-A6-CB2-S2	854.26	2-4	1801490391	Not Excavated	< 0.035 U	< 0.025 U	< 0.038 U	0.47	0.22 J	< 0.047 U	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-CB2-S3	SSHS-IRM5A2-A6-CB2-S3-20221208	SSHS-IRM5A2-A6-CB2-S3	854.23	2-4	1801490391	Not Excavated	0.060 J	0.038 J	< 0.037 U	1.8	0.87	< 0.045 U	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4-20230118	SSHS-PDI6-B5105-SUB-2.4	853.71	2-4	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4-20230118	SSHS-PDI6-B5105-SUB-2.4	853.71	2-4	1801508222	Not Excavated	< 0.035 U	< 0.025 U	< 0.037 U	0.067 J	< 0.059 U	< 0.046 U	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	0.042 J
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-2.4-20230118	SSHS-PDI6-B5106-SUB-2.4	851.23	2-4	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-2.4-20230118	SSHS-PDI6-B5106-SUB-2.4	851.23	2-4	1801508222	Not Excavated	< 0.031 U	0.030 J	< 0.033 U	0.21	0.068 J	< 0.041 UJ	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2.4-20230209	SSHS-PDI6-B5109-SUB-2.4	852.78	2 - 4 ft	1801518942	Not Excavated												
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	856.72	2 - 4 ft	180-116404-1	Not Excavated												
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	855.26	2 - 4 ft	180-80225-3	Not Excavated												
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	856.10	2 - 4 ft	180-80106-1	Not Excavated												
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	854.99	2 - 4 ft	180-80105-1	Not Excavated												
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	855.10	2 - 4 ft	180-90380-1	Not Excavated												
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	853.34	2 - 4 ft	1801164042	Not Excavated	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	< 0.090 U	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	856.06	2 - 4 ft	180-116404-1	Not Excavated												
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	856.76	2 - 4 ft	180-116404-1	Not Excavated												
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	857.46	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	857.46	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	858.35	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3225	122119 10:30_SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	853.42	2 - 4 ft	180-100361-1	Not Excavated												
Northern Athletic Field	SSHS-B3226	122119 10:30_SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	853.22	2 - 4 ft	180-100362-1	Not Excavated												
Northern Athletic Field	SSHS-B3227	012520 10:00_SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	853.19	2 - 4 ft	180-101497-4	Not Excavated												
Northern Athletic Field	SSHS-B3228	122119 10:30_SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	853.57	2 - 4 ft	180-100362-1	Not Excavated												
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	855.71	2 - 4 ft	180-100362-1	Not Excavated												
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	858.02	2 - 4 ft	180-100363-1	Not Excavated												
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	857.46	2 - 4 ft	180-100363-1	Not Excavated												
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	858.40	2 - 4 ft	180-100363-2	Not Excavated												
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	857.06	2 - 4 ft	180-100363-1	Not Excavated												
Northern Athletic Field	SSHS-B3257	122119 10:30_SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	858.41	2 - 4 ft	180-100363-2	Not Excavated												
Northern Athletic Field	SSHS-B3259	122119 10:30_SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	857.33	2 - 4 ft	180-100363-2	Not Excavated												
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	858.57	2 - 4 ft	180-100363-1	Not Excavated												
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	856.35	2 - 4 ft	180-116404-1	Not Excavated												
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	856.00	2 - 4 ft	180-100380-1	Not Excavated												
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	856.25	2 - 4 ft	180-100380-2	Not Excavated												
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	856.88	2 - 4 ft	180-100380-2	Not Excavated												
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	856.35	2 - 4 ft	180-100380-2	Not Excavated												
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	855.54	2 - 4 ft	180-100148-5	Not Excavated												
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	856.90	2 - 4 ft	180-100148-6	Not Excavated												
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	855.68	2 - 4 ft	180-100148-4	Not Excavated												
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	856.43	2 - 4 ft	180-100148-6	Not Excavated												
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	851.73	2 - 4 ft	180-100148-1	Not Excavated												
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	852.38	2 - 4 ft	180-100148-1	Not Excavated												
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	855.50	2 - 4 ft	180-108826-2	Not Excavated												
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	855.64	2 - 4 ft	180-108826-1	Not Excavated												
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	855.34	2 - 4 ft	180-108826-1	Not Excavated												
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	855.25	2 - 4 ft	180-108826-1	Not Excavated												
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	855.68	2 - 4 ft	180-108826-1	Not Excavated												
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	858.11	2 - 4 ft	1801164621	Not Excavated												
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	858.11	2 - 4 ft	1801164622	Not Excavated	< 0.046 U	< 0.039 U	< 0.090 U	0.58 BT	< 0.094 U	< 0.084 U	< 0.059 U	< 0.056 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	858.42	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	858.46	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	858.31	2 - 4 ft	180-116462-4	Not Excavated	< 0.048 U	< 0.041 U	< 0.093 U	0.29 J	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	858.30	2 - 4 ft	180-116462-4	Not Excavated	< 0.055 U	< 0.047 U	< 0.11 U	0.98	0.16 J	< 0.1 U	< 0.071 U	< 0.067 U	< 0.047 U	< 0.33 U	< 0.2 U	< 0.51 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	858.46	2 - 4 ft	1801164622	Not Excavated	< 0.045 U	< 0.039 U	< 0.088 U	1.1 BT	< 0.092 U	< 0.083 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U

DRAFT

								Emerging C										
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	858.39	2 - 4 ft	180-116462-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	858.31	2 - 4 ft	180-116462-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	858.50	2 - 4 ft	180-116002-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	858.38	2 - 4 ft	1801164622	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.38 B	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U	0.042 J	0.038 J
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	856.82	2 - 4 ft	180-116404-3	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	857.88	2 - 4 ft	180-116404-3	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	858.03	2 - 4 ft	180-116404-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	856.26	2 - 4 ft	180-116404-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	856.80	2 - 4 ft	180-123985-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	857.47	2 - 4 ft	1801239851	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.088 J	< 0.043 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	856.76	2 - 4 ft	180-123985-1	Not Excavated			< 120 U									
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	858.24	2 - 4 ft	180-127265-2	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.05 U	< 0.039 U	< 0.029 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	857.91	2 - 4 ft	180-127265-2	Not Excavated			< 110 U	< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.03 U	< 0.049 U	< 0.038 U	< 0.029 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	856.72	2 - 4 ft	180-127415-1	Not Excavated			< 110 U									
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	856.42	2 - 4 ft	180-127595-2	Not Excavated			< 6000 U									
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	855.97	2 - 4 ft	180-127140-1	Not Excavated			< 900 U									
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	855.73	2 - 4 ft	180-127066-2	Not Excavated			< 110 U	< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.03 U	< 0.049 U	< 0.038 U	< 0.029 U
Rear Parking Lot	SSHS-B66	081514 01:15 SSHS-B66-2-4 (3)	SSHS-B66-2-4 (3)	851.94	2 - 4 ft	180-35818-1	Not Excavated			< 42 U									
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-2-4 (4)	SSHS-B69-2-4 (4)	850.53	2 - 4 ft	180-35818-1	Not Excavated			< 46 U									
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	855.66	2 - 4 ft	180-66622-2	Not Excavated			< 55 U									
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-2-6 (5.5)	SSHS-B68-2-6 (5.5)	852.07	2 - 6 ft	180-35818-1	Not Excavated			< 42 U									
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	856.08	2 - 6 ft	180-35818-2	Not Excavated			< 42									
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	856.08	2 - 6 ft	180-35818-2	Not Excavated			< 43									
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	856.25	2 - 6 ft	180-35818-1	Not Excavated			< 43									
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	855.88	2 - 6 ft	180-35818-1	Not Excavated			< 41									
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	855.75	2 - 6 ft	180-35818-2	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 DUP-12	DUP-12	854.07	8 - 10 ft	180-35818-2	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	855.92	2 - 6 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	856.60	2 - 6 ft	180-35776-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 DUP-11	DUP-11	855.26	6 - 8 ft	180-35776-2	Not Excavated			< 45 U									
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	854.77	2 - 6 ft	180-35776-1	Not Excavated			< 45 U									
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	856.00	2 - 6 ft	180-35818-1	Not Excavated			< 44 U									
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	855.54	2 - 6 ft	180-35776-1	Not Excavated			< 47 U									
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	854.20	2 - 6 ft	180-35776-1	Not Excavated			< 46 U									
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	855.86	2 - 6 ft	180-35818-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	855.00	2 - 6 ft	180-35776-1	Not Excavated			< 44 U									
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	853.90	2 - 6 ft	180-35776-1	Not Excavated			< 44 U									
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated			< 41									
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	854.07	8 - 10 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U	< 0.035 U	< 0.037 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	855.26	6 - 8 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.031 U	< 0.034 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	855.27	2 - 4 ft	180-119938-1	Not Excavated			< 120 U	< 0.41 U	< 0.027 U	0.032 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	853.60	10 - 12 ft	1801219031	Not Excavated	< 130 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U	< 0.032 U	< 0.035 U
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	852.95	3 - 6 ft	180-35818-2	Not Excavated			< 45 U									
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	852.95	3 - 6 ft	180-35818-2	Not Excavated			< 47 U									
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-DUP218-20220908	SSHS-IRM5A2-A6-DUP218	852.36	4-6	1801442122	Not Excavated				< 0.056 U	< 0.045 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U	< 0.058 U	< 0.045 U	< 0.034 U
Northern Athletic Field	A6-CB2-B1	SSHS-IRM5A2-A6-CB2-B1-20221208	SSHS-IRM5A2-A6-CB2-B1	852.88	4-6	1801490391	Not Excavated				< 0.052 U	< 0.041 U	0.080 J	< 0.056 U	< 0.052 U	< 0.032 U	< 0.053 U	< 0.041 U	< 0.031 U
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6-20230118	SSHS-PDI6-B5105-SUB-4-6	853.71	4-6	1801508221	Not Excavated	< 110 U											
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6-20230118	SSHS-PDI6-B5105-SUB-4-6	853.71	4-6	1801508222	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U	< 0.052 U	< 0.041 U	< 0.031 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-4-6-20230118	SSHS-PDI6-B5106-SUB-4-6	851.23	4-6	1801508221	Not Excavated	< 120 U											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-4-6-20230118	SSHS-PDI6-B5106-SUB-4-6	851.23	4-6	1801508222	Not Excavated				< 0.051 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U	< 0.040 U	< 0.031 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	852.78	4 - 6 ft	1801518942	Not Excavated	< 110 U											
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	856.72	4 - 6 ft	180-116404-3	Not Excavated			< 120 U									
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	854.92	4 - 6 ft	180903801	Not Excavated	< 120 U											
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	853.34	4 - 6 ft	1801164043	Not Excavated	< 110 U											
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	856.06	4 - 6 ft	180-116404-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	856.76	4 - 6 ft	180-116404-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	855.96	4 - 6 ft	180-116529-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	857.46	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	857.46	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	858.35	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	855.71	4 - 6 ft	180-100362-1	Not Excavated			< 490 U									
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	858.55	4 - 6 ft	180-116462-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	856.35	4 - 6 ft	180-116404-3	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	856.44	4 - 6 ft	180-100380-1	Not Excavated			< 130 U									

DRAFT

TABLE 5-6E
Subsurface Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	858.39	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	858.31	2 - 4 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	858.50	2 - 4 ft	180-116002-1	Not Excavated												
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	858.38	2 - 4 ft	1801164622	Not Excavated	< 0.049 U	0.042 J	< 0.096 U	0.95 BT	0.12 J	< 0.090 U	< 0.063 U	< 0.059 U	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	856.82	2 - 4 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	857.88	2 - 4 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	858.03	2 - 4 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	856.26	2 - 4 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	856.80	2 - 4 ft	180-123985-1	Not Excavated												
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	857.47	2 - 4 ft	1801239851	Not Excavated	0.089 J	< 0.039 U	< 0.089 U	0.26 J	0.11 J	< 0.084 U	< 0.059 U	< 0.056 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	856.76	2 - 4 ft	180-123985-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	858.24	2 - 4 ft	180-127265-2	Not Excavated	< 0.032 U	< 0.022 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	857.91	2 - 4 ft	180-127265-2	Not Excavated	0.096 J	< 0.022 U	< 0.033 U	0.079 J	< 0.053 U	0.08 J	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	856.72	2 - 4 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	856.42	2 - 4 ft	180-127595-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	855.97	2 - 4 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	855.73	2 - 4 ft	180-127066-2	Not Excavated	< 0.031 U	< 0.022 U	< 34 U	< 0.043 U	< 0.053 U	< 0.041 U	< 0.037 U	< 34 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Rear Parking Lot	SSHS-B66	081514 01:15 SSHS-B66-2-4 (3)	SSHS-B66-2-4 (3)	851.94	2 - 4 ft	180-35818-1	Not Excavated												
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-2-4 (4)	SSHS-B69-2-4 (4)	850.53	2 - 4 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	855.66	2 - 4 ft	180-66622-2	Not Excavated												
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-2-6 (5.5)	SSHS-B68-2-6 (5.5)	852.07	2 - 6 ft	180-35818-1	Not Excavated												
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	856.08	2 - 6 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	856.08	2 - 6 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	856.25	2 - 6 ft	180-35818-1	Not Excavated												
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	855.88	2 - 6 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	855.75	2 - 6 ft	180-35818-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 DUP-12	DUP-12	854.07	8 - 10 ft	180-35818-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	855.92	2 - 6 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	856.60	2 - 6 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 DUP-11	DUP-11	855.26	6 - 8 ft	180-35776-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	854.77	2 - 6 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	856.00	2 - 6 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	855.54	2 - 6 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	854.20	2 - 6 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	855.86	2 - 6 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	855.00	2 - 6 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	853.90	2 - 6 ft	180-35776-1	Not Excavated												
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	856.19	2.5 - 4.5 ft	180-35858-1	Not Excavated												
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	854.07	8 - 10 ft	180-120245-1	Not Excavated	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 0.061 U	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	855.26	6 - 8 ft	1801217041	Not Excavated	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U	< 0.059 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	855.27	2 - 4 ft	180-119938-1	Not Excavated	< 0.046 U	< 0.04 U	< 0.09 U	< 0.22 U	< 0.094 U	< 0.085 U	< 0.059 U	< 0.056 U	< 0.04 U	< 0.27 UJ	< 0.16 UJ	< 0.43 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	853.60	10 - 12 ft	1801219031	Not Excavated	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	852.95	3 - 6 ft	180-35818-2	Not Excavated												
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	852.95	3 - 6 ft	180-35818-2	Not Excavated												
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-DUP218-20220908	SSHS-IRM5A2-A6-DUP218	852.36	4-6	1801442122	Not Excavated	< 0.036 U	< 0.026 U	< 0.039 U	< 0.051 U	< 0.062 U	< 0.048 U	< 0.044 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A6-CB2-B1	SSHS-IRM5A2-A6-CB2-B1-20221208	SSHS-IRM5A2-A6-CB2-B1	852.88	4-6	1801490391	Not Excavated	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	0.082 J	< 0.044 U	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6-20230118	SSHS-PDI6-B5105-SUB-4-6	853.71	4-6	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6-20230118	SSHS-PDI6-B5105-SUB-4-6	853.71	4-6	1801508222	Not Excavated	< 0.033 U	0.025 J	< 0.035 U	0.15 J	0.057 J	< 0.044 U	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-4-6-20230118	SSHS-PDI6-B5106-SUB-4-6	851.23	4-6	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-4-6-20230118	SSHS-PDI6-B5106-SUB-4-6	851.23	4-6	1801508222	Not Excavated	< 0.033 U	0.024 J	< 0.035 U	0.16 J	< 0.056 U	< 0.043 U	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	852.78	4 - 6 ft	1801518942	Not Excavated												
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	856.72	4 - 6 ft	180-116404-3	Not Excavated												
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	854.92	4 - 6 ft	180903801	Not Excavated												
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	853.34	4 - 6 ft	1801164043	Not Excavated												
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	856.06	4 - 6 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	856.76	4 - 6 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	855.96	4 - 6 ft	180-116529-3	Not Excavated												
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	857.46	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	857.46	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	858.35	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	855.71	4 - 6 ft	180-100362-1	Not Excavated												
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	858.55	4 - 6 ft	180-116462-1	Not Excavated												
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	856.35	4 - 6 ft	180-116404-3	Not Excavated												
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	856.44	4 - 6 ft	180-100380-1	Not Excavated												

DRAFT

								Emerging C									
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	856.56	4 - 6 ft	180-100380-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	856.89	4 - 6 ft	180-116665-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	856.41	4 - 6 ft	180-116529-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	853.34	4 - 6 ft	180-100148-1	Not Excavated			< 230 U									
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	852.74	4 - 6 ft	180-100148-1	Not Excavated			< 240 U									
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	856.51	4 - 6 ft	180-108826-2	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	858.11	4 - 6 ft	1801164623	Not Excavated	< 120 U											
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	858.42	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	858.46	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	858.30	4 - 6 ft	180-116002-2	Not Excavated			120									
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	858.46	4 - 6 ft	1801164624	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.073 BJ	< 0.043 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	858.39	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	858.31	4 - 6 ft	180-116462-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	856.72	4 - 6 ft	180-116529-3	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	858.38	4 - 6 ft	1801164624	Not Excavated	< 110 U			< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3629	020421 09:30_SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	856.66	4 - 6 ft	180-116771-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	856.37	4 - 6 ft	1801217472	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U	< 0.032 U	< 0.034 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	855.95	4 - 6 ft	1801218221	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.037 J	< 0.046 U	0.026 J	< 0.078 U	< 0.041 U	< 0.034 U	< 0.036 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	856.50	4 - 6 ft	1801214741	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U	< 0.031 U	< 0.033 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	856.80	4 - 6 ft	180-123985-2	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	857.47	4 - 6 ft	1801239851	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U	< 0.030 U	< 0.032 U
Northern Athletic Field	SSHS-B4025	070221 09:00_SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	857.11	4 - 6 ft	180-123985-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-B4026	070221 09:00_SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	856.99	4 - 6 ft	180-123985-1	Not Excavated			< 120 UJ									
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	857.91	4 - 6 ft	180-127265-2	Not Excavated			< 110 U	< 0.05 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.05 U	< 0.031 U	< 0.051 U	< 0.039 U	< 0.03 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	856.72	4 - 6 ft	180-127415-1	Not Excavated			< 110 U									
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	856.42	4 - 6 ft	180-127595-2	Not Excavated			< 120 U									
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	856.00	4 - 6 ft	180-127595-2	Not Excavated			< 120 U									
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	855.97	4 - 6 ft	180-127140-1	Not Excavated			< 220 U									
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	855.73	4 - 6 ft	180-127066-2	Not Excavated			< 120 U	< 0.055 U	< 0.044 U	< 0.053 U	< 0.06 U	< 0.055 U	< 0.035 U	< 0.056 U	< 0.044 U	< 0.033 U
Rear Parking Lot	SSHS-B69	081514 01:15_DUP-18	DUP-18	855.66	2 - 4 ft	180-35818-2	Not Excavated			< 210 U									
Rear Parking Lot	SSHS-B69	081514 01:15_SSHS-B69-4-6R (5)	SSHS-B69-4-6R (5)	850.53	4 - 6 ft	180-35818-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	855.66	4 - 6 ft	180-66622-2	Not Excavated			< 55 U									
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	856.38	4 - 6 ft	180-140136-1	Not Excavated			< 120 U									
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	856.27	4 - 6 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	856.66	4 - 6 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	856.60	4 - 6 ft	180-140136-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-4-6	SSHS-DW-7_8-SUB-4-6	856.61	4 - 6 ft	180-139185-1	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	856.08	6 - 10 ft	180-35818-2	Not Excavated			< 42									
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	856.25	6 - 10 ft	180-35818-1	Not Excavated			< 40									
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	081514 01:15_DUP-19	855.88	6 - 10 ft	180-35818-2	Not Excavated			< 41									
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	855.88	6 - 10 ft	180-35818-1	Not Excavated			< 41									
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	855.75	6 - 10 ft	180-35818-2	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	855.92	6 - 10 ft	180-35818-1	Not Excavated			< 44 U									
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	856.60	6 - 10 ft	180-35776-1	Not Excavated			< 41 U									
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	854.77	6 - 10 ft	180-35776-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	856.00	6 - 10 ft	180-35818-1	Not Excavated			< 41 U									
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	855.54	6 - 10 ft	180-35776-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	854.20	6 - 10 ft	180-35776-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	855.86	6 - 10 ft	180-35818-1	Not Excavated			< 43 U									
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	855.00	6 - 10 ft	180-35776-1	Not Excavated			< 42 U									
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	853.90	6 - 10 ft	180-35776-1	Not Excavated			< 42 U									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8-20230118	SSHS-PDI6-B5105-SUB-6-8	853.71	6-8	1801508221	Not Excavated	< 120 U											
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8-20230118	SSHS-PDI6-B5105-SUB-6-8	853.71	6-8	1801508222	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.058 U	< 0.054 U	< 0.034 U	< 0.055 U	< 0.043 U	< 0.033 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-6-8-20230118	SSHS-PDI6-B5106-SUB-6-8	851.23	6-8	1801508221	Not Excavated	< 110 U											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-6-8-20230118	SSHS-PDI6-B5106-SUB-6-8	851.23	6-8	1801508222	Not Excavated				< 0.045 U	< 0.036 U	0.46	< 0.049 U	< 0.045 U	< 0.028 U	< 0.046 U	< 0.036 U	< 0.027 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	852.78	6 - 8 ft	1801518942	Not Excavated	< 120 U											
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	850.65	6.65-8.65 ft	1801782961	Not Excavated		< 240 U										
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	852.76	6.76-8.76 ft	1801783741	Not Excavated		< 250 U										
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	852.76	6.76-8.76 ft	1801783741	Not Excavated		< 230 U										
Football Field	SSHS-B2686	052219 08:40_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	855.51	6 - 8 ft	180-90380-1	Not Excavated			< 110 U									
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	856.00	6 - 8 ft	180-89521-1	Not Excavated			< 120 U									
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	854.92	6 - 8 ft	180903801	Not Excavated	< 120 U											
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	856.96	6 - 8 ft	180-95165-2	Not Excavated			< 110 U									
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	858.55	6 - 8 ft	180-116462-3	Not Excavated			< 120 U									

DRAFT

TABLE 5-6E
Subsurface Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	856.56	4 - 6 ft	180-100380-2	Not Excavated												
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	856.89	4 - 6 ft	180-116665-1	Not Excavated												
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	856.41	4 - 6 ft	180-116529-1	Not Excavated												
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	853.34	4 - 6 ft	180-100148-1	Not Excavated												
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	852.74	4 - 6 ft	180-100148-1	Not Excavated												
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	856.51	4 - 6 ft	180-108826-2	Not Excavated												
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	858.11	4 - 6 ft	1801164623	Not Excavated												
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	858.42	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	858.46	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	858.30	4 - 6 ft	180-116002-2	Not Excavated												
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	858.46	4 - 6 ft	1801164624	Not Excavated	< 0.046 U	< 0.039 U	< 0.089 U	0.34 J	< 0.094 U	< 0.084 U	< 0.059 U	< 0.056 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	858.39	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	858.31	4 - 6 ft	180-116462-3	Not Excavated												
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	856.72	4 - 6 ft	180-116529-3	Not Excavated												
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	858.38	4 - 6 ft	1801164624	Not Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.094 U	< 0.084 U	< 0.059 U	< 0.056 U	< 0.040 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	856.66	4 - 6 ft	180-116771-1	Not Excavated												
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	856.37	4 - 6 ft	1801217472	Not Excavated	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U	< 0.059 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	855.95	4 - 6 ft	1801218221	Not Excavated	0.068 J	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	< 0.090 U	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	856.50	4 - 6 ft	1801214741	Not Excavated	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	856.80	4 - 6 ft	180-123985-2	Not Excavated												
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	857.47	4 - 6 ft	1801239851	Not Excavated	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.080 U	< 0.056 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	857.11	4 - 6 ft	180-123985-1	Not Excavated												
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	856.99	4 - 6 ft	180-123985-1	Not Excavated												
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	857.91	4 - 6 ft	180-127265-2	Not Excavated	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.042 U	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	856.72	4 - 6 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	856.42	4 - 6 ft	180-127595-2	Not Excavated												
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	856.00	4 - 6 ft	180-127595-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	855.97	4 - 6 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	855.73	4 - 6 ft	180-127066-2	Not Excavated	< 0.036 U	< 0.025 U	< 34 U	< 0.049 U	< 0.061 U	< 0.047 U	< 0.043 U	< 34 U	< 0.048 U	< 0.04 U	< 0.031 U	< 0.026 U
Rear Parking Lot	SSHS-B69	081514 01:15 DUP-18	DUP-18	855.66	2 - 4 ft	180-35818-2	Not Excavated												
Rear Parking Lot	SSHS-B69	081514 01:15 SSHS-B69-4-6R (5)	SSHS-B69-4-6R (5)	850.53	4 - 6 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	855.66	4 - 6 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	856.38	4 - 6 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	856.27	4 - 6 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	856.66	4 - 6 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	856.60	4 - 6 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-4-6	SSHS-DW-7_8-SUB-4-6	856.61	4 - 6 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	856.08	6 - 10 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	856.25	6 - 10 ft	180-35818-1	Not Excavated												
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	855.88	6 - 10 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	855.88	6 - 10 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	855.75	6 - 10 ft	180-35818-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	855.92	6 - 10 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	856.60	6 - 10 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	854.77	6 - 10 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	856.00	6 - 10 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	855.54	6 - 10 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	854.20	6 - 10 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	855.86	6 - 10 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	855.00	6 - 10 ft	180-35776-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	853.90	6 - 10 ft	180-35776-1	Not Excavated												
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8-20230118	SSHS-PDI6-B5105-SUB-6-8	853.71	6-8	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8-20230118	SSHS-PDI6-B5105-SUB-6-8	853.71	6-8	1801508222	Not Excavated	< 0.035 U	< 0.025 U	< 0.037 U	0.070 J	< 0.060 U	< 0.046 U	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-6-8-20230118	SSHS-PDI6-B5106-SUB-6-8	851.23	6-8	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-6-8-20230118	SSHS-PDI6-B5106-SUB-6-8	851.23	6-8	1801508222	Not Excavated	0.037 J	< 0.021 U	< 0.031 U	0.088 J	< 0.050 U	0.17 J	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.025 U	< 0.022 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	852.78	6 - 8 ft	1801518942	Not Excavated												
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	850.65	6.65-8.65 ft	1801782961	Not Excavated												
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	852.76	6.76-8.76 ft	1801783741	Not Excavated												
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	852.76	6.76-8.76 ft	1801783741	Not Excavated												
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	855.51	6 - 8 ft	180-90380-1	Not Excavated												
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	856.00	6 - 8 ft	180-89521-1	Not Excavated												
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	854.92	6 - 8 ft	180903801	Not Excavated												
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	856.96	6 - 8 ft	180-95165-2	Not Excavated												
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	858.55	6 - 8 ft	180-116462-3	Not Excavated												

DRAFT

																					Emerging C
									1,4-Dioxane Lab Method SW8270D	**1,4-Dioxane Lab Method 8270E**	**1,4-Dioxane Lab Method 8270D**	**N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)**	**Perfluorobutanesulfonic acid (PFBS)**	**Perfluorobutanoic acid (PFBA)**	**Perfluorodecanesulfonic acid (PFDS)**	**Perfluorodecanoic acid (PFDA)**	**Perfluorododecanoic acid (PFDoA)**	**Perfluoroheptanesulfonic Acid (PFHpS)**	**Perfluoroheptanoic acid (PFHpA)**	**Perfluorohexanesulfonic acid (PFHxS)**
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100										
Restricted - Residential									13000	13000	13000										
Protection of Groundwater									100	100	100										
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status														
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	856.89	6 - 8 ft	180-116665-3	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	856.41	6 - 8 ft	180-116529-3	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	851.57	6 - 8 ft	180-100361-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	856.64	6 - 8 ft	180-127265-1	Not Excavated				< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.05 U	< 0.039 U	< 0.03 U	
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	856.37	6 - 8 ft	1801217472	Not Excavated	< 110 U				< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U	< 0.031 U	< 0.033 U	
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	855.95	6 - 8 ft	1801218221	Not Excavated	< 110 U				< 0.38 U	< 0.026 U	0.029 J	< 0.040 U	< 0.022 U	< 0.068 U	< 0.036 U	< 0.030 U	< 0.032 U	
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	856.50	6 - 8 ft	1801214741	Not Excavated	< 110 U				< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U	< 0.032 U	< 0.035 U	
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	858.24	6 - 8 ft	180-127265-2	Not Excavated					< 0.047 U	< 0.037 U	0.092 J	< 0.051 U	< 0.047 U	< 0.029 U	< 0.048 U	< 0.037 U	< 0.028 U	
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	857.91	6 - 8 ft	180-127265-2	Not Excavated				< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U	< 0.05 U	< 0.039 U	< 0.03 U	
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	856.72	6 - 8 ft	180-127415-1	Not Excavated				< 110 U										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	856.42	6 - 8 ft	180-127595-2	Not Excavated				< 180 U										
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	856.00	6 - 8 ft	180-127595-2	Not Excavated				< 110 U	< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.03 U	< 0.049 U	< 0.038 U	< 0.029 U	
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	855.97	6 - 8 ft	180-127140-1	Not Excavated				< 460 U										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	855.73	6 - 8 ft	180-127066-2	Not Excavated				< 110 U	< 0.051 U	< 0.041 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U	< 0.041 U	< 0.031 U	
Rear Parking Lot	SSHS-B548	092316 08:45_PS-FD-31	PS-FD-31	855.94	8 - 10 ft	180-59020-1	Not Excavated				< 52 U										
Rear Parking Lot	SSHS-B548	092316 08:45_SSHS-B548-SUB-6-8	SSHS-B548-SUB-6-8	850.36	6 - 8 ft	180-59020-1	Not Excavated				< 46 U										
Rear Parking Lot	SSHS-B66	081514 01:15_SSHS-B66-6-8R (7)	SSHS-B66-6-8R (7)	851.94	6 - 8 ft	180-35818-1	Not Excavated				< 82 U										
Rear Parking Lot	SSHS-B68	081514 01:15_SSHS-B68-6-8R (6.5)	SSHS-B68-6-8R (6.5)	852.07	6 - 8 ft	180-35818-1	Not Excavated				< 42 U										
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	855.66	6 - 8 ft	180-66622-2	Not Excavated				< 54 U										
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	856.38	6 - 8 ft	180-140136-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	856.18	6 - 8 ft	180-139185-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	857.21	6 - 8 ft	180-139185-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	856.60	6 - 8 ft	180-139185-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	856.27	6 - 8 ft	180-139185-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	856.66	6 - 8 ft	180-140136-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	856.60	6 - 8 ft	180-140136-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	856.61	6 - 8 ft	180-139185-1	Not Excavated				< 110 U										
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	851.65	6 - 9 ft	180-35818-2	Not Excavated				< 44 U										
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	856.19	6 - 9.5 ft	180-35858-1	Not Excavated				< 40										
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	856.19	6 - 9.5 ft	180-35858-1	Not Excavated				< 40										
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-8-10-20230118	SSHS-PDI6-B5106-SUB-8-10	851.23	8-10	1801508221	Not Excavated	< 110 U													
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-8-10-20230118	SSHS-PDI6-B5106-SUB-8-10	851.23	8-10	1801508222	Not Excavated					< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U	< 0.049 U	< 0.038 U	< 0.029 U	
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	852.78	8 - 10 ft	1801518942	Not Excavated	< 110 U													
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	852.95	8 - 10 ft	180-35818-2	Not Excavated				< 47 U										
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	856.56	8 - 10 ft	180-80227-1	Not Excavated				< 350 U										
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	856.14	8 - 10 ft	180-89521-1	Not Excavated				< 110 U										
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	856.00	8 - 10 ft	180-89521-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	851.57	8 - 10 ft	180-100361-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	856.64	8 - 10 ft	180-127265-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	856.07	8 - 10 ft	180-127205-2	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	856.37	8 - 10 ft	1801217472	Not Excavated	< 110 U				< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U	
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	855.95	8 - 10 ft	1801218221	Not Excavated	< 120 U				< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	0.031 J	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U	
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	856.50	8 - 10 ft	1801214741	Not Excavated	< 120 U				< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.036 U	< 0.030 U	< 0.032 U	
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	856.50	8 - 10 ft	1801214741	Not Excavated	< 110 U				< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.036 U	< 0.030 U	< 0.032 U	
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	857.91	8 - 10 ft	180-127265-2	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	856.72	8 - 10 ft	180-127415-1	Not Excavated				< 110 U										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	856.42	8 - 10 ft	180-127595-2	Not Excavated				< 120 U										
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	856.00	8 - 10 ft	180-127595-2	Not Excavated				< 110 U										
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-8-10	SSHS-B4168-SUB-8-10	855.97	8 - 10 ft	180-127140-1	Not Excavated				< 450 U										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-8-10	SSHS-B4170-SUB-8-10	855.73	8 - 10 ft	180-127066-2	Not Excavated				< 120 U	< 0.055 U	< 0.044 U	< 0.053 U	< 0.06 U	< 0.055 U	< 0.035 U	< 0.056 U	< 0.044 U	< 0.033 U	
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	850.41	8 - 10 ft	180-35818-1	Not Excavated				< 48 U										
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	855.66	8 - 10 ft	180-66622-2	Not Excavated				< 53 U										
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	856.38	8 - 10 ft	180-140136-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	856.18	8 - 10 ft	180-139185-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	857.21	8 - 10 ft	180-139185-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	856.60	8 - 10 ft	180-139185-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	856.27	8 - 10 ft	180-139185-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	856.66	8 - 10 ft	180-140136-1	Not Excavated				< 120 U										
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	856.60	8 - 10 ft	180-140136-1	Not Excavated				< 110 U										
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	856.61	8 - 10 ft	180-139185-1	Not Excavated				< 110 U										
Football Field	SSHS-B2708	052219 08:40_PS-FD-31	PS-FD-31	855.94	8 - 10 ft	180-90380-1	Excavated				< 130 U										
Football Field	SSHS-B2710	051719 09:00_PS-FD-16	PS-FD-16	855.07	4 - 6 ft	180-90231-1	Excavated				< 120 U										
Football Field	SSHS-B2027	072718 09:00_SSHS-B2027-SUB-10-12	SSHS-B2027-SUB-10-12	855.22	10 - 12 ft	180-80227-1	Excavated				< 330 U										
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-10-12	SSHS-B2755-SUB-10-12	855.30	10 - 12 ft	180-89521-1	Excavated				< 230 U										

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	856.89	6 - 8 ft	180-116665-3	Not Excavated												
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	856.41	6 - 8 ft	180-116529-3	Not Excavated												
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	851.57	6 - 8 ft	180-100361-1	Not Excavated												
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	856.64	6 - 8 ft	180-127265-1	Not Excavated	< 0.032 U	< 0.023 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	856.37	6 - 8 ft	1801217472	Not Excavated	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	855.95	6 - 8 ft	1801218221	Not Excavated	0.058 J	< 0.037 U	< 0.084 U	< 0.20 U	< 0.088 U	< 0.079 U	< 0.055 U	< 0.052 U	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	856.50	6 - 8 ft	1801214741	Not Excavated	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	858.24	6 - 8 ft	180-127265-2	Not Excavated	< 0.03 U	< 0.022 U	< 34 U	0.045 J	< 0.052 U	0.058 J	< 0.036 U	< 34 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	857.91	6 - 8 ft	180-127265-2	Not Excavated	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	856.72	6 - 8 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	856.42	6 - 8 ft	180-127595-2	Not Excavated												
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	856.00	6 - 8 ft	180-127595-2	Not Excavated	< 0.031 U	< 0.022 U	< 34 U	< 0.043 U	< 0.053 U	< 0.041 U	< 0.037 U	< 34 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	855.97	6 - 8 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	855.73	6 - 8 ft	180-127066-2	Not Excavated	< 0.033 U	< 0.023 U	< 34 U	0.12 J	< 0.057 U	< 0.044 U	< 0.039 U	< 34 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Rear Parking Lot	SSHS-B548	092316 08:45 PS-FD-31	PS-FD-31	855.94	8 - 10 ft	180-59020-1	Not Excavated												
Rear Parking Lot	SSHS-B548	092316 08:45 SSHS-B548-SUB-6-8	SSHS-B548-SUB-6-8	850.36	6 - 8 ft	180-59020-1	Not Excavated												
Rear Parking Lot	SSHS-B66	081514 01:15 SSHS-B66-6-8R (7)	SSHS-B66-6-8R (7)	851.94	6 - 8 ft	180-35818-1	Not Excavated												
Rear Parking Lot	SSHS-B68	081514 01:15 SSHS-B68-6-8R (6.5)	SSHS-B68-6-8R (6.5)	852.07	6 - 8 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	855.66	6 - 8 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	856.38	6 - 8 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	856.18	6 - 8 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	857.21	6 - 8 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	856.60	6 - 8 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	856.27	6 - 8 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	856.66	6 - 8 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	856.60	6 - 8 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	856.61	6 - 8 ft	180-139185-1	Not Excavated												
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	851.65	6 - 9 ft	180-35818-2	Not Excavated												
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	856.19	6 - 9.5 ft	180-35858-1	Not Excavated												
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	856.19	6 - 9.5 ft	180-35858-1	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-8-10-20230118	SSHS-PDI6-B5106-SUB-8-10	851.23	8-10	1801508221	Not Excavated												
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-8-10-20230118	SSHS-PDI6-B5106-SUB-8-10	851.23	8-10	1801508222	Not Excavated	< 0.031 U	< 0.022 U	< 0.033 U	0.052 J	< 0.053 U	< 0.041 U	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	852.78	8 - 10 ft	1801518942	Not Excavated												
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	852.95	8 - 10 ft	180-35818-2	Not Excavated												
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	856.56	8 - 10 ft	180-80227-1	Not Excavated												
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	856.14	8 - 10 ft	180-89521-1	Not Excavated												
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	856.00	8 - 10 ft	180-89521-1	Not Excavated												
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	851.57	8 - 10 ft	180-100361-1	Not Excavated												
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	856.64	8 - 10 ft	180-127265-1	Not Excavated												
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	856.07	8 - 10 ft	180-127205-2	Not Excavated												
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	856.37	8 - 10 ft	1801217472	Not Excavated	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	855.95	8 - 10 ft	1801218221	Not Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	856.50	8 - 10 ft	1801214741	Not Excavated	< 0.044 U	< 0.038 U	< 0.085 U	< 0.21 U	< 0.090 U	< 0.080 U	< 0.056 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	857.91	8 - 10 ft	180-127265-2	Not Excavated												
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	856.72	8 - 10 ft	180-127415-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	856.42	8 - 10 ft	180-127595-2	Not Excavated												
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	856.00	8 - 10 ft	180-127595-2	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-8-10	SSHS-B4168-SUB-8-10	855.97	8 - 10 ft	180-127140-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-8-10	SSHS-B4170-SUB-8-10	855.73	8 - 10 ft	180-127066-2	Not Excavated	< 0.036 U	< 0.025 U	< 34 U	0.29	< 0.061 U	< 0.047 U	< 0.043 U	< 34 U	< 0.048 U	< 0.04 U	< 0.031 U	< 0.027 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	850.41	8 - 10 ft	180-35818-1	Not Excavated												
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	855.66	8 - 10 ft	180-66622-2	Not Excavated												
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	856.38	8 - 10 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	856.18	8 - 10 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	857.21	8 - 10 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	856.60	8 - 10 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	856.27	8 - 10 ft	180-139185-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	856.66	8 - 10 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	856.60	8 - 10 ft	180-140136-1	Not Excavated												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	856.61	8 - 10 ft	180-139185-1	Not Excavated												
Football Field	SSHS-B2708	052219 08:40 PS-FD-31	PS-FD-31	855.94	8 - 10 ft	180-90380-1	Excavated												
Football Field	SSHS-B2710	051719 09:00 PS-FD-16	PS-FD-16	855.07	4 - 6 ft	180-90231-1	Excavated												
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-10-12	SSHS-B2027-SUB-10-12	855.22	10 - 12 ft	180-80227-1	Excavated												
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 SSHS-B2755-SUB-10-12	SSHS-B2755-SUB-10-12	855.30	10 - 12 ft	180-89521-1	Excavated												

DRAFT

								Emerging C										
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorodecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3015A	DUP-3-20210123	DUP-3	853.60	10 - 12 ft	1801164042	Excavated	< 110 U			< 0.38 U	< 0.026 U	0.55 B	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U	< 0.030 U	< 0.032 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12-20210123	SSHS-B3015A-SUB-10-12	853.60	10 - 12 ft	1801164042	Excavated	< 110 U			< 0.37 U	< 0.025 U	0.051 BJ	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U	< 0.029 U	< 0.031 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12-20210122	SSHS-B3265A-SUB-10-12	854.14	10 - 12 ft	1801163651	Excavated	< 110 U			< 0.39 U	< 0.026 U	0.52 B	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Northern Athletic Field	SSHS-B3454	DUP-8-20210122	DUP-8	853.65	10 - 12 ft	1801163651	Excavated	< 110 U											
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12-20210122	SSHS-B3454-SUB-10-12	853.65	10 - 12 ft	1801163651	Excavated	< 110 U			< 0.39 U	< 0.026 U	0.58 B	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U	< 0.030 U	< 0.032 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12-20210120	SSHS-B3554-SUB-10-12	854.07	10 - 12 ft	1801162471	Excavated	< 110 U			< 0.36 U	< 0.025 U	0.57 B	< 0.038 U	< 0.022 U	< 0.066 U	< 0.034 U	< 0.029 U	< 0.030 U
Northern Athletic Field	SSHS-B3670	020321 09:45_SSHS-B3670-SUB-10-12	SSHS-B3670-SUB-10-12	851.67	10 - 12 ft	180-116723-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12-20210512	SSHS-B3917-SUB-10-12	853.71	10 - 12 ft	1801215482	Excavated	< 120 U			< 0.39 U	< 0.027 U	0.043 J	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U	< 0.031 U	< 0.033 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	081514 01:15_SSHS-B70-10-14 (12.5)	855.98	10 - 14 ft	180-35818-2	Excavated			< 43 U									
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14-20210123	SSHS-B3015A-SUB-12-14	853.60	12 - 14 ft	1801164042	Excavated	< 110 U			< 0.38 U	< 0.026 U	0.046 BJ	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U	< 0.030 U	< 0.032 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14-20210122	SSHS-B3454-SUB-12-14	853.65	12 - 14 ft	1801163651	Excavated	< 110 U			< 0.40 U	< 0.027 U	0.23 B	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U	< 0.031 U	< 0.033 U
Northern Athletic Field	SSHS-B3668	012921 07:15_SSHS-B3668-SUB-12-14	SSHS-B3668-SUB-12-14	851.94	12 - 14 ft	180-116609-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	SSHS-B3668-SUB-12-14	851.94	12 - 14 ft	180-116609-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3669	012921 07:15_SSHS-B3669-SUB-12-14	SSHS-B3669-SUB-12-14	852.33	12 - 14 ft	180-116609-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3670	020321 09:45_SSHS-B3670-SUB-12-14	SSHS-B3670-SUB-12-14	851.67	12 - 14 ft	180-116723-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3670	020321 09:45_SSHS-B3670-SUB-14-16	SSHS-B3670-SUB-14-16	851.67	14 - 16 ft	180-116723-1	Excavated			< 120 U									
Football Field	SSHS-B2052	072618 08:50_SSHS-B2052-SUB-2-4	SSHS-B2052-SUB-2-4	855.59	2 - 4 ft	180-80154-2	Excavated			< 360 U									
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-2-4	SSHS-B2185-SUB-2-4	855.07	2 - 4 ft	180-80106-3	Excavated			< 35 U									
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-2-4	SSHS-B2186-SUB-2-4	854.94	2 - 4 ft	180-80106-2	Excavated			< 68 U									
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-2-4	SSHS-B2188-SUB-2-4	855.99	2 - 4 ft	180-80106-2	Excavated			< 43 U									
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-2-4	SSHS-B2189-SUB-2-4	855.74	2 - 4 ft	180-80105-3	Excavated			< 17 U									
Football Field	SSHS-B2190	072818 11:30_PS-FD-55	PS-FD-55	856.06	2 - 4 ft	180-80252-2	Excavated			< 17 U									
Football Field	SSHS-B2190	072818 11:30_SSHS-B2190-SUB-2-4	SSHS-B2190-SUB-2-4	856.06	2 - 4 ft	180-80252-1	Excavated			< 16 U									
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-2-4	SSHS-B2191-SUB-2-4	856.18	2 - 4 ft	180-80105-3	Excavated			< 35 U									
Football Field	SSHS-B2198	072518 09:00_SSHS-B2198-SUB-2-4	SSHS-B2198-SUB-2-4	855.05	2 - 4 ft	180-80105-2	Excavated			< 17 U									
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-2-4	SSHS-B2226-SUB-2-4	856.56	2 - 4 ft	180-80227-1	Excavated			< 170 U									
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-2-4	SSHS-B2245-SUB-2-4	855.25	2 - 4 ft	180-80106-1	Excavated			< 67 U									
Football Field	SSHS-B2246	072718 09:00_SSHS-B2246-SUB-2-4	SSHS-B2246-SUB-2-4	855.24	2 - 4 ft	180-80225-1	Excavated			< 1700 U									
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-2-4	SSHS-B2762-SUB-2-4	856.14	2 - 4 ft	180-89521-1	Excavated			< 120 U									
Football Field	SSHS-B2808	051819 10:00_SSHS-B2808-SUB-2-4	SSHS-B2808-SUB-2-4	855.18	2 - 4 ft	180-90275-1	Excavated			< 120 U									
Football Field	SSHS-B2810	051819 10:00_SSHS-B2810-SUB-2-4	SSHS-B2810-SUB-2-4	855.11	2 - 4 ft	180-90275-1	Excavated			< 120 U									
Football Field	SSHS-B2914	110719 09:00_DUP-05	DUP-05	855.30	2 - 4 ft	180-98355-3	Excavated			< 320 U									
Football Field	SSHS-B2914	110719 09:00_SSHS-B2914-SUB-2-4	SSHS-B2914-SUB-2-4	855.30	2 - 4 ft	180-98355-2	Excavated			< 220 U									
Football Field	SSHS-B2952	110719 09:00_SSHS-B2952-SUB-2-4	SSHS-B2952-SUB-2-4	855.18	2 - 4 ft	180-98355-2	Excavated			< 350 U									
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-2-4	SSHS-B3046-SUB-2-4	856.22	2 - 4 ft	180-94824-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3061A	012821 08:30_SSHS-B3061A-SUB-2-4	SSHS-B3061A-SUB-2-4	857.02	2 - 4 ft	180-116529-1	Excavated			< 240 U									
Northern Athletic Field	SSHS-B3073A	DUP-4-20210127	DUP-4	857.14	2 - 4 ft	1801165291	Excavated	< 120 U											
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4-20210127	SSHS-B3073A-SUB-2-4	857.14	2 - 4 ft	1801165292	Excavated	< 230 U			< 0.41 U	< 0.028 U	0.35 B	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U	< 0.032 U	0.041 J
Northern Athletic Field	SSHS-B3087A	012721 08:30_SSHS-B3087A-SUB-2-4	SSHS-B3087A-SUB-2-4	857.70	2 - 4 ft	180-116404-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3096A	072021 09:15_SSHS-B3096A-SUB-2-4	SSHS-B3096A-SUB-2-4	855.86	2 - 4 ft	180-124670-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-2-4	SSHS-B3098A-SUB-2-4	855.96	2 - 4 ft	180-116529-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-2-4	SSHS-B3100-SUB-2-4	856.74	2 - 4 ft	180-100985-1	Excavated			< 2800 UJ									
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-2-4	SSHS-B3101-SUB-2-4	856.75	2 - 4 ft	180-100985-1	Excavated			< 2900 UJ									
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-2-4	SSHS-B3102-SUB-2-4	856.74	2 - 4 ft	180-100985-1	Excavated			< 340 UJ									
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-2-4	SSHS-B3104-SUB-2-4	856.82	2 - 4 ft	180-100985-2	Excavated			< 3000 UJ									
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-2-4	SSHS-B3105-SUB-2-4	856.73	2 - 4 ft	180-101038-1	Excavated			< 570 U									
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-2-4	SSHS-B3106-SUB-2-4	856.72	2 - 4 ft	180-101038-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-2-4	SSHS-B3112-SUB-2-4	856.71	2 - 4 ft	180-101084-2	Excavated			< 240 U									
Northern Athletic Field	SSHS-B3181A	DUP-5-20210126	DUP-5	857.57	2 - 4 ft	1801164621	Excavated	< 120 U											
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4-20210126	SSHS-B3181A-SUB-2-4	857.57	2 - 4 ft	1801164622	Excavated	< 120 U			< 0.42 U	< 0.029 U	0.19 BJ	< 0.045 U	0.029 J	< 0.077 U	< 0.040 U	0.051 J	0.038 J
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-2-4	SSHS-B3183-SUB-2-4	856.70	2 - 4 ft	180-101038-1	Excavated			< 2900 U									
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-2-4	SSHS-B3244-SUB-2-4	857.74	2 - 4 ft	180-100363-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-2-4	SSHS-B3245-SUB-2-4	857.37	2 - 4 ft	180-100363-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-2-4	SSHS-B3246-SUB-2-4	858.13	2 - 4 ft	180-100363-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3247	122119 10:30_SSHS-B3247-SUB-2-4	SSHS-B3247-SUB-2-4	857.57	2 - 4 ft	180-100363-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3249	122119 10:30_SSHS-B3249-SUB-2-4	SSHS-B3249-SUB-2-4	857.44	2 - 4 ft	180-100363-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3256	122119 10:30_SSHS-B3256-SUB-2-4	SSHS-B3256-SUB-2-4	858.14	2 - 4 ft	180-100363-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3265	122119 10:30_SSHS-B3265-SUB-2-4	SSHS-B3265-SUB-2-4	854.04	2 - 4 ft	180-100380-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3268	122119 10:30_SSHS-B3268-SUB-2-4	SSHS-B3268-SUB-2-4	854.73	2 - 4 ft	180-100380-2	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3269	122119 10:30_SSHS-B3269-SUB-2-4	SSHS-B3269-SUB-2-4	854.73	2 - 4 ft	180-100380-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3274	122119 10:30_SSHS-B3274-SUB-2-4	SSHS-B3274-SUB-2-4	855.80	2 - 4 ft	180-100380-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-2-4	SSHS-B3276-SUB-2-4	856.44	2 - 4 ft	180-100380-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-2-4	SSHS-B3280-SUB-2-4	856.56	2 - 4 ft	180-100380-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3282	122119 10:30_SSHS-B3282-SUB-2-4	SSHS-B3282-SUB-2-4	856.89	2 - 4 ft	180-100380-2	Excavated			< 120 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3015A	DUP-3-20210123	DUP-3	853.60	10 - 12 ft	1801164042	Excavated	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.088 U	< 0.079 U	< 0.055 U	< 0.052 U	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-10-12-20210123	SSHS-B3015A-SUB-10-12	853.60	10 - 12 ft	1801164042	Excavated	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-10-12-20210122	SSHS-B3265A-SUB-10-12	854.14	10 - 12 ft	1801163651	Excavated	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U	< 0.038 UT	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3454	DUP-8-20210122	DUP-8	853.65	10 - 12 ft	1801163651	Excavated												
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-10-12-20210122	SSHS-B3454-SUB-10-12	853.65	10 - 12 ft	1801163651	Excavated	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-10-12-20210120	SSHS-B3554-SUB-10-12	854.07	10 - 12 ft	1801162471	Excavated	< 0.041 U	< 0.035 U	< 0.081 U	0.46 BJ	< 0.085 U	< 0.076 U	< 0.053 U	< 0.050 U	< 0.035 U	< 0.25 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B3670	020321 09:45_SSHS-B3670-SUB-10-12	SSHS-B3670-SUB-10-12	851.67	10 - 12 ft	180-116723-1	Excavated												
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-10-12-20210512	SSHS-B3917-SUB-10-12	853.71	10 - 12 ft	1801215482	Excavated	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.057 U	< 0.054 U	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B70	081514 01:15_SSHS-B70-10-14 (12.5)	081514 01:15_SSHS-B70-10-14 (12.5)	855.98	10 - 14 ft	180-35818-2	Excavated												
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-12-14-20210123	SSHS-B3015A-SUB-12-14	853.60	12 - 14 ft	1801164042	Excavated	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.16 U	< 0.40 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-12-14-20210122	SSHS-B3454-SUB-12-14	853.65	12 - 14 ft	1801163651	Excavated	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3668	012921 07:15_SSHS-B3668-SUB-12-14	SSHS-B3668-SUB-12-14	851.94	12 - 14 ft	180-116609-1	Excavated												
Northern Athletic Field	SSHS-B3668	SSHS-B3668-SUB-12-14	SSHS-B3668-SUB-12-14	851.94	12 - 14 ft	180-116609-1	Excavated												
Northern Athletic Field	SSHS-B3669	012921 07:15_SSHS-B3669-SUB-12-14	SSHS-B3669-SUB-12-14	852.33	12 - 14 ft	180-116609-1	Excavated												
Northern Athletic Field	SSHS-B3670	020321 09:45_SSHS-B3670-SUB-12-14	SSHS-B3670-SUB-12-14	851.67	12 - 14 ft	180-116723-1	Excavated												
Northern Athletic Field	SSHS-B3670	020321 09:45_SSHS-B3670-SUB-14-16	SSHS-B3670-SUB-14-16	851.67	14 - 16 ft	180-116723-1	Excavated												
Football Field	SSHS-B2052	072618 08:50_SSHS-B2052-SUB-2-4	SSHS-B2052-SUB-2-4	855.59	2 - 4 ft	180-80154-2	Excavated												
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-2-4	SSHS-B2185-SUB-2-4	855.07	2 - 4 ft	180-80106-3	Excavated												
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-2-4	SSHS-B2186-SUB-2-4	854.94	2 - 4 ft	180-80106-2	Excavated												
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-2-4	SSHS-B2188-SUB-2-4	855.99	2 - 4 ft	180-80106-2	Excavated												
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-2-4	SSHS-B2189-SUB-2-4	855.74	2 - 4 ft	180-80105-3	Excavated												
Football Field	SSHS-B2190	072818 11:30_PS-FD-55	PS-FD-55	856.06	2 - 4 ft	180-80252-2	Excavated												
Football Field	SSHS-B2190	072818 11:30_SSHS-B2190-SUB-2-4	SSHS-B2190-SUB-2-4	856.06	2 - 4 ft	180-80252-1	Excavated												
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-2-4	SSHS-B2191-SUB-2-4	856.18	2 - 4 ft	180-80105-3	Excavated												
Football Field	SSHS-B2198	072518 09:00_SSHS-B2198-SUB-2-4	SSHS-B2198-SUB-2-4	855.05	2 - 4 ft	180-80105-2	Excavated												
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-2-4	SSHS-B2226-SUB-2-4	856.56	2 - 4 ft	180-80227-1	Excavated												
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-2-4	SSHS-B2245-SUB-2-4	855.25	2 - 4 ft	180-80106-1	Excavated												
Football Field	SSHS-B2246	072718 09:00_SSHS-B2246-SUB-2-4	SSHS-B2246-SUB-2-4	855.24	2 - 4 ft	180-80225-1	Excavated												
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-2-4	SSHS-B2762-SUB-2-4	856.14	2 - 4 ft	180-89521-1	Excavated												
Football Field	SSHS-B2808	051819 10:00_SSHS-B2808-SUB-2-4	SSHS-B2808-SUB-2-4	855.18	2 - 4 ft	180-90275-1	Excavated												
Football Field	SSHS-B2810	051819 10:00_SSHS-B2810-SUB-2-4	SSHS-B2810-SUB-2-4	855.11	2 - 4 ft	180-90275-1	Excavated												
Football Field	SSHS-B2914	110719 09:00_DUP-05	DUP-05	855.30	2 - 4 ft	180-98355-3	Excavated												
Football Field	SSHS-B2914	110719 09:00_SSHS-B2914-SUB-2-4	SSHS-B2914-SUB-2-4	855.30	2 - 4 ft	180-98355-2	Excavated												
Football Field	SSHS-B2952	110719 09:00_SSHS-B2952-SUB-2-4	SSHS-B2952-SUB-2-4	855.18	2 - 4 ft	180-98355-2	Excavated												
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-2-4	SSHS-B3046-SUB-2-4	856.22	2 - 4 ft	180-94824-1	Excavated												
Northern Athletic Field	SSHS-B3061A	012821 08:30_SSHS-B3061A-SUB-2-4	SSHS-B3061A-SUB-2-4	857.02	2 - 4 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3073A	DUP-4-20210127	DUP-4	857.14	2 - 4 ft	1801165291	Excavated												
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-2-4-20210127	SSHS-B3073A-SUB-2-4	857.14	2 - 4 ft	1801165292	Excavated	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	0.21 J	< 0.061 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3087A	012721 08:30_SSHS-B3087A-SUB-2-4	SSHS-B3087A-SUB-2-4	857.70	2 - 4 ft	180-116404-1	Excavated												
Northern Athletic Field	SSHS-B3096A	072021 09:15_SSHS-B3096A-SUB-2-4	SSHS-B3096A-SUB-2-4	855.86	2 - 4 ft	180-124670-1	Excavated												
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-2-4	SSHS-B3098A-SUB-2-4	855.96	2 - 4 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-2-4	SSHS-B3100-SUB-2-4	856.74	2 - 4 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-2-4	SSHS-B3101-SUB-2-4	856.75	2 - 4 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-2-4	SSHS-B3102-SUB-2-4	856.74	2 - 4 ft	180-100985-1	Excavated												
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-2-4	SSHS-B3104-SUB-2-4	856.82	2 - 4 ft	180-100985-2	Excavated												
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-2-4	SSHS-B3105-SUB-2-4	856.73	2 - 4 ft	180-101038-1	Excavated												
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-2-4	SSHS-B3106-SUB-2-4	856.72	2 - 4 ft	180-101038-1	Excavated												
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-2-4	SSHS-B3112-SUB-2-4	856.71	2 - 4 ft	180-101084-2	Excavated												
Northern Athletic Field	SSHS-B3181A	DUP-5-20210126	DUP-5	857.57	2 - 4 ft	1801164621	Excavated												
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-2-4-20210126	SSHS-B3181A-SUB-2-4	857.57	2 - 4 ft	1801164622	Excavated	< 0.048 U	0.048 J	< 0.094 U	1.5 BT	0.17 J	0.15 J	< 0.062 U	< 0.058 U	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-2-4	SSHS-B3183-SUB-2-4	856.70	2 - 4 ft	180-101038-1	Excavated												
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-2-4	SSHS-B3244-SUB-2-4	857.74	2 - 4 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-2-4	SSHS-B3245-SUB-2-4	857.37	2 - 4 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-2-4	SSHS-B3246-SUB-2-4	858.13	2 - 4 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3247	122119 10:30_SSHS-B3247-SUB-2-4	SSHS-B3247-SUB-2-4	857.57	2 - 4 ft	180-100363-3	Excavated												
Northern Athletic Field	SSHS-B3249	122119 10:30_SSHS-B3249-SUB-2-4	SSHS-B3249-SUB-2-4	857.44	2 - 4 ft	180-100363-1	Excavated												
Northern Athletic Field	SSHS-B3256	122119 10:30_SSHS-B3256-SUB-2-4	SSHS-B3256-SUB-2-4	858.14	2 - 4 ft	180-100363-2	Excavated												
Northern Athletic Field	SSHS-B3265	122119 10:30_SSHS-B3265-SUB-2-4	SSHS-B3265-SUB-2-4	854.04	2 - 4 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3268	122119 10:30_SSHS-B3268-SUB-2-4	SSHS-B3268-SUB-2-4	854.73	2 - 4 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3269	122119 10:30_SSHS-B3269-SUB-2-4	SSHS-B3269-SUB-2-4	854.73	2 - 4 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3274	122119 10:30_SSHS-B3274-SUB-2-4	SSHS-B3274-SUB-2-4	855.80	2 - 4 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-2-4	SSHS-B3276-SUB-2-4	856.44	2 - 4 ft	180-100380-1	Excavated												
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-2-4	SSHS-B3280-SUB-2-4	856.56	2 - 4 ft	180-100380-2	Excavated												
Northern Athletic Field	SSHS-B3282	122119 10:30_SSHS-B3282-SUB-2-4	SSHS-B3282-SUB-2-4	856.89	2 - 4 ft	180-100380-2	Excavated												

DRAFT

								Emerging C										
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100									
Restricted - Residential								13000	13000	13000									
Protection of Groundwater								100	100	100									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3285	121819 10:30_SSHS-B3285-SUB-2-4	SSHS-B3285-SUB-2-4	856.21	2 - 4 ft	180-100148-5	Excavated			< 250 U									
Northern Athletic Field	SSHS-B3286	121819 10:30_SSHS-B3286-SUB-2-4	SSHS-B3286-SUB-2-4	856.34	2 - 4 ft	180-100148-5	Excavated			< 600 U									
Northern Athletic Field	SSHS-B3291	121819 10:30_SSHS-B3291-SUB-2-4	SSHS-B3291-SUB-2-4	857.22	2 - 4 ft	180-100148-6	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3292	121819 10:30_SSHS-B3292-SUB-2-4	SSHS-B3292-SUB-2-4	857.35	2 - 4 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3293	121819 10:30_SSHS-B3293-SUB-2-4	SSHS-B3293-SUB-2-4	857.15	2 - 4 ft	180-100148-5	Excavated			< 230 U									
Northern Athletic Field	SSHS-B3295	121819 10:30_SSHS-B3295-SUB-2-4	SSHS-B3295-SUB-2-4	855.96	2 - 4 ft	180-100148-4	Excavated			< 380 U									
Northern Athletic Field	SSHS-B3296	121819 10:30_SSHS-B3296-SUB-2-4	SSHS-B3296-SUB-2-4	856.22	2 - 4 ft	180-100148-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3297	121819 10:30_SSHS-B3297-SUB-2-4	SSHS-B3297-SUB-2-4	857.02	2 - 4 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3298	121819 10:30_SSHS-B3298-SUB-2-4	SSHS-B3298-SUB-2-4	857.20	2 - 4 ft	180-100148-5	Excavated			< 620 U									
Northern Athletic Field	SSHS-B3300	121819 10:30_SSHS-B3300-SUB-2-4	SSHS-B3300-SUB-2-4	856.38	2 - 4 ft	180-100148-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3301	121819 10:30_SSHS-B3301-SUB-2-4	SSHS-B3301-SUB-2-4	856.13	2 - 4 ft	180-100148-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3302	121819 10:30_SSHS-B3302-SUB-2-4	SSHS-B3302-SUB-2-4	856.19	2 - 4 ft	180-100148-5	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3303	121819 10:30_SSHS-B3303-SUB-2-4	SSHS-B3303-SUB-2-4	856.73	2 - 4 ft	180-100148-5	Excavated			< 490 U									
Northern Athletic Field	SSHS-B3304	121819 10:30_SSHS-B3304-SUB-2-4	SSHS-B3304-SUB-2-4	856.97	2 - 4 ft	180-100148-4	Excavated			< 1300 U									
Northern Athletic Field	SSHS-B3306	121819 10:30_SSHS-B3306-SUB-2-4	SSHS-B3306-SUB-2-4	855.94	2 - 4 ft	180-100148-2	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3307	121819 10:30_SSHS-B3307-SUB-2-4	SSHS-B3307-SUB-2-4	856.00	2 - 4 ft	180-100148-6	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3309	121819 10:30_SSHS-B3309-SUB-2-4	SSHS-B3309-SUB-2-4	856.31	2 - 4 ft	180-100148-4	Excavated			< 1300 U									
Northern Athletic Field	SSHS-B3314	121819 10:30_SSHS-B3314-SUB-2-4	SSHS-B3314-SUB-2-4	856.94	2 - 4 ft	180-100148-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3325	121819 10:30_SSHS-B3325-SUB-2-4	SSHS-B3325-SUB-2-4	853.99	2 - 4 ft	180-100148-1	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3326	121819 10:30_SSHS-B3326-SUB-2-4	SSHS-B3326-SUB-2-4	854.39	2 - 4 ft	180-100148-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-2-4	SSHS-B3327-SUB-2-4	853.34	2 - 4 ft	180-100148-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3328	121819 10:30_SSHS-B3328-SUB-2-4	SSHS-B3328-SUB-2-4	854.14	2 - 4 ft	180-100148-1	Excavated			< 260 U									
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-2-4	SSHS-B3329-SUB-2-4	852.74	2 - 4 ft	180-100148-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3332	121819 10:30_SSHS-B3332-SUB-2-4	SSHS-B3332-SUB-2-4	853.06	2 - 4 ft	180-100148-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3333	121819 10:30_SSHS-B3333-SUB-2-4	SSHS-B3333-SUB-2-4	853.75	2 - 4 ft	180-100148-1	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3342	121819 10:30_SSHS-B3342-SUB-2-4	SSHS-B3342-SUB-2-4	853.63	2 - 4 ft	180-100148-6	Excavated			< 600 U									
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-2-4	SSHS-B3459-SUB-2-4	856.30	2 - 4 ft	180-108826-2	Excavated			< 110 U									
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-2-4	SSHS-B3461-SUB-2-4	856.51	2 - 4 ft	180-108826-2	Excavated			< 120 U									
Football Field	SSHS-B3464	072820 09:00_SSHS-B3464-SUB-2-4	SSHS-B3464-SUB-2-4	856.28	2 - 4 ft	180-108826-2	Excavated			< 110 U									
Football Field	SSHS-B3467	072920 09:00_SSHS-B3467-SUB-2-4	SSHS-B3467-SUB-2-4	855.68	2 - 4 ft	180-108872-2	Excavated			< 1000 U									
Football Field	SSHS-B3473	072820 09:00_SSHS-B3473-SUB-2-4	SSHS-B3473-SUB-2-4	855.34	2 - 4 ft	180-108826-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3504A	012721 08:30_SSHS-B3504-SUB-2-4	SSHS-B3504-SUB-2-4	853.98	2 - 4 ft	180-116404-3	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3505A	012721 08:30_SSHS-B3505-SUB-2-4	SSHS-B3505-SUB-2-4	853.31	2 - 4 ft	180-116404-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3507A	012721 08:30_SSHS-B3507-SUB-2-4	SSHS-B3507-SUB-2-4	857.28	2 - 4 ft	180-116462-3	Excavated			< 240 U									
Northern Athletic Field	SSHS-B3518	012721 08:30_SSHS-B3518-SUB-2-4	SSHS-B3518-SUB-2-4	856.64	2 - 4 ft	180-116462-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-2-4	SSHS-B3519-SUB-2-4	856.72	2 - 4 ft	180-116529-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3595	020221 09:00_SSHS-B3595-SUB-2-4	SSHS-B3595-SUB-2-4	856.70	2 - 4 ft	180-116686-2	Excavated			< 460 U									
Northern Athletic Field	SSHS-B3614	012721 08:30_SSHS-B3614-SUB-2-4	SSHS-B3614-SUB-2-4	857.48	2 - 4 ft	180-116404-3	Excavated			< 110 U									
Northern Athletic Field	SSHS-B3625	012721 08:30_SSHS-B3625-SUB-2-4	SSHS-B3625-SUB-2-4	855.69	2 - 4 ft	180-116404-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3626	012821 08:30_SSHS-B3626-SUB-2-4	SSHS-B3626-SUB-2-4	855.81	2 - 4 ft	180-116529-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3627	020221 09:00_SSHS-B3627-SUB-2-4	SSHS-B3627-SUB-2-4	856.45	2 - 4 ft	180-116686-2	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3628	012721 08:30_SSHS-B3628-SUB-2-4	SSHS-B3628-SUB-2-4	857.05	2 - 4 ft	180-116404-3	Excavated			< 130 U									
Northern Athletic Field	SSHS-B3629	020321 09:45_SSHS-B3629-SUB-2-4	SSHS-B3629-SUB-2-4	856.66	2 - 4 ft	180-116723-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3630	012821 08:30_SSHS-B3630-SUB-2-4	SSHS-B3630-SUB-2-4	857.15	2 - 4 ft	180-116529-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3639	012821 08:30_SSHS-B3639-SUB-2-4	SSHS-B3639-SUB-2-4	856.65	2 - 4 ft	180-116529-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3640	020321 09:45_SSHS-B3640-SUB-2-4	SSHS-B3640-SUB-2-4	856.10	2 - 4 ft	180-116723-1	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3643	012821 08:30_SSHS-B3643-SUB-2-4	SSHS-B3643-SUB-2-4	856.99	2 - 4 ft	180-116529-3	Excavated			< 360 U									
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4-20210129	SSHS-B3644-SUB-2-4	856.95	2 - 4 ft	1801166654	Excavated	< 1200 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U	< 0.031 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-2-4	SSHS-B3646A-SUB-2-4	856.64	2 - 4 ft	180-127265-1	Excavated			< 110 U	< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U	< 0.048 U	< 0.037 U	< 0.028 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-2-4	SSHS-B3852-SUB-2-4	856.07	2 - 4 ft	180-127205-2	Excavated			< 230 U									
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4-20210512	SSHS-B3917-SUB-2-4	853.71	2 - 4 ft	1801215482	Excavated	< 120 U			< 0.40 U	< 0.027 U	0.17 J	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U	0.047 J	0.036 J
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-2-6 (4.5)	SSHS-B67-2-6 (4.5)	850.45	2 - 6 ft	180-35818-1	Excavated			< 46 U									
Football Field	SSHS-B70	081514 01:15_SSHS-B70-2-6 (3.5)	081514 01:15_SSHS-B70-2-6 (3.5)	855.98	2 - 6 ft	180-35818-2	Excavated			< 42 U									
Football Field	SSHS-B2053	072618 08:50_SSHS-B2053-SUB-4-6	SSHS-B2053-SUB-4-6	855.00	4 - 6 ft	180-80157-1	Excavated			< 180 U									
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-4-6	SSHS-B2226-SUB-4-6	856.56	4 - 6 ft	180-80227-1	Excavated			< 350 U									
Football Field	SSHS-B2615	052219 08:40_SSHS-B2615-SUB-4-6	SSHS-B2615-SUB-4-6	855.13	4 - 6 ft	180-90380-1	Excavated			< 120 U									
Football Field	SSHS-B2729	052219 08:40_SSHS-B2729-SUB-4-6	SSHS-B2729-SUB-4-6	856.49	4 - 6 ft	180-90380-1	Excavated			< 120 U									
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-4-6	SSHS-B2762-SUB-4-6	856.14	4 - 6 ft	180-89521-1	Excavated			< 110 U									
Football Field	SSHS-B2809	051819 10:00_SSHS-B2809-SUB-4-6	SSHS-B2809-SUB-4-6	855.39	4 - 6 ft	180-90275-1	Excavated			< 340 U									
Northern Athletic Field	SSHS-B3061A	012821 08:30_SSHS-B3061A-SUB-4-6	SSHS-B3061A-SUB-4-6	857.02	4 - 6 ft	180-116529-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6-20210127	SSHS-B3073A-SUB-4-6	857.14	4 - 6 ft	1801165293	Excavated	< 1800 U											
Northern Athletic Field	SSHS-B3087A	012721 08:30_SSHS-B3087A-SUB-4-6	SSHS-B3087A-SUB-4-6	857.70	4 - 6 ft	180-116404-3	Excavated			< 120 U									
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6-20210126	SSHS-B3181A-SUB-4-6	857.57	4 - 6 ft	1801164623	Excavated	< 120 U											
Northern Athletic Field	SSHS-B3304A	012821 08:30_SSHS-B3304A-SUB-4-6	SSHS-B3304A-SUB-4-6	857.13	4 - 6 ft	180-116529-1	Excavated			< 120 U									

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3285	121819 10:30 SSHS-B3285-SUB-2-4	SSHS-B3285-SUB-2-4	856.21	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3286	121819 10:30 SSHS-B3286-SUB-2-4	SSHS-B3286-SUB-2-4	856.34	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3291	121819 10:30 SSHS-B3291-SUB-2-4	SSHS-B3291-SUB-2-4	857.22	2 - 4 ft	180-100148-6	Excavated												
Northern Athletic Field	SSHS-B3292	121819 10:30 SSHS-B3292-SUB-2-4	SSHS-B3292-SUB-2-4	857.35	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3293	121819 10:30 SSHS-B3293-SUB-2-4	SSHS-B3293-SUB-2-4	857.15	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3295	121819 10:30 SSHS-B3295-SUB-2-4	SSHS-B3295-SUB-2-4	855.96	2 - 4 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3296	121819 10:30 SSHS-B3296-SUB-2-4	SSHS-B3296-SUB-2-4	856.22	2 - 4 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3297	121819 10:30 SSHS-B3297-SUB-2-4	SSHS-B3297-SUB-2-4	857.02	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3298	121819 10:30 SSHS-B3298-SUB-2-4	SSHS-B3298-SUB-2-4	857.20	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3300	121819 10:30 SSHS-B3300-SUB-2-4	SSHS-B3300-SUB-2-4	856.38	2 - 4 ft	180-100148-3	Excavated												
Northern Athletic Field	SSHS-B3301	121819 10:30 SSHS-B3301-SUB-2-4	SSHS-B3301-SUB-2-4	856.13	2 - 4 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3302	121819 10:30 SSHS-B3302-SUB-2-4	SSHS-B3302-SUB-2-4	856.19	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3303	121819 10:30 SSHS-B3303-SUB-2-4	SSHS-B3303-SUB-2-4	856.73	2 - 4 ft	180-100148-5	Excavated												
Northern Athletic Field	SSHS-B3304	121819 10:30 SSHS-B3304-SUB-2-4	SSHS-B3304-SUB-2-4	856.97	2 - 4 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3306	121819 10:30 SSHS-B3306-SUB-2-4	SSHS-B3306-SUB-2-4	855.94	2 - 4 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3307	121819 10:30 SSHS-B3307-SUB-2-4	SSHS-B3307-SUB-2-4	856.00	2 - 4 ft	180-100148-6	Excavated												
Northern Athletic Field	SSHS-B3309	121819 10:30 SSHS-B3309-SUB-2-4	SSHS-B3309-SUB-2-4	856.31	2 - 4 ft	180-100148-4	Excavated												
Northern Athletic Field	SSHS-B3314	121819 10:30 SSHS-B3314-SUB-2-4	SSHS-B3314-SUB-2-4	856.94	2 - 4 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3325	121819 10:30 SSHS-B3325-SUB-2-4	SSHS-B3325-SUB-2-4	853.99	2 - 4 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3326	121819 10:30 SSHS-B3326-SUB-2-4	SSHS-B3326-SUB-2-4	854.39	2 - 4 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-2-4	SSHS-B3327-SUB-2-4	853.34	2 - 4 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3328	121819 10:30 SSHS-B3328-SUB-2-4	SSHS-B3328-SUB-2-4	854.14	2 - 4 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-2-4	SSHS-B3329-SUB-2-4	852.74	2 - 4 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3332	121819 10:30 SSHS-B3332-SUB-2-4	SSHS-B3332-SUB-2-4	853.06	2 - 4 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3333	121819 10:30 SSHS-B3333-SUB-2-4	SSHS-B3333-SUB-2-4	853.75	2 - 4 ft	180-100148-1	Excavated												
Northern Athletic Field	SSHS-B3342	121819 10:30 SSHS-B3342-SUB-2-4	SSHS-B3342-SUB-2-4	853.63	2 - 4 ft	180-100148-6	Excavated												
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-2-4	SSHS-B3459-SUB-2-4	856.30	2 - 4 ft	180-108826-2	Excavated												
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-2-4	SSHS-B3461-SUB-2-4	856.51	2 - 4 ft	180-108826-2	Excavated												
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-2-4	SSHS-B3464-SUB-2-4	856.28	2 - 4 ft	180-108826-2	Excavated												
Football Field	SSHS-B3467	072920 09:00 SSHS-B3467-SUB-2-4	SSHS-B3467-SUB-2-4	855.68	2 - 4 ft	180-108872-2	Excavated												
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-2-4	SSHS-B3473-SUB-2-4	855.34	2 - 4 ft	180-108826-2	Excavated												
Northern Athletic Field	SSHS-B3504A	012721 08:30 SSHS-B3504-SUB-2-4	SSHS-B3504-SUB-2-4	853.98	2 - 4 ft	180-116404-3	Excavated												
Northern Athletic Field	SSHS-B3505A	012721 08:30 SSHS-B3505-SUB-2-4	SSHS-B3505-SUB-2-4	853.31	2 - 4 ft	180-116404-3	Excavated												
Northern Athletic Field	SSHS-B3507A	012721 08:30 SSHS-B3507-SUB-2-4	SSHS-B3507-SUB-2-4	857.28	2 - 4 ft	180-116462-3	Excavated												
Northern Athletic Field	SSHS-B3518	012721 08:30 SSHS-B3518-SUB-2-4	SSHS-B3518-SUB-2-4	856.64	2 - 4 ft	180-116462-1	Excavated												
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-2-4	SSHS-B3519-SUB-2-4	856.72	2 - 4 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3595	020221 09:00 SSHS-B3595-SUB-2-4	SSHS-B3595-SUB-2-4	856.70	2 - 4 ft	180-116686-2	Excavated												
Northern Athletic Field	SSHS-B3614	012721 08:30 SSHS-B3614-SUB-2-4	SSHS-B3614-SUB-2-4	857.48	2 - 4 ft	180-116404-3	Excavated												
Northern Athletic Field	SSHS-B3625	012721 08:30 SSHS-B3625-SUB-2-4	SSHS-B3625-SUB-2-4	855.69	2 - 4 ft	180-116404-3	Excavated												
Northern Athletic Field	SSHS-B3626	012821 08:30 SSHS-B3626-SUB-2-4	SSHS-B3626-SUB-2-4	855.81	2 - 4 ft	180-116529-3	Excavated												
Northern Athletic Field	SSHS-B3627	020221 09:00 SSHS-B3627-SUB-2-4	SSHS-B3627-SUB-2-4	856.45	2 - 4 ft	180-116686-2	Excavated												
Northern Athletic Field	SSHS-B3628	012721 08:30 SSHS-B3628-SUB-2-4	SSHS-B3628-SUB-2-4	857.05	2 - 4 ft	180-116404-3	Excavated												
Northern Athletic Field	SSHS-B3629	020321 09:45 SSHS-B3629-SUB-2-4	SSHS-B3629-SUB-2-4	856.66	2 - 4 ft	180-116723-1	Excavated												
Northern Athletic Field	SSHS-B3630	012821 08:30 SSHS-B3630-SUB-2-4	SSHS-B3630-SUB-2-4	857.15	2 - 4 ft	180-116529-1	Excavated												
Northern Athletic Field	SSHS-B3639	012821 08:30 SSHS-B3639-SUB-2-4	SSHS-B3639-SUB-2-4	856.65	2 - 4 ft	180-116529-3	Excavated												
Northern Athletic Field	SSHS-B3640	020321 09:45 SSHS-B3640-SUB-2-4	SSHS-B3640-SUB-2-4	856.10	2 - 4 ft	180-116723-1	Excavated												
Northern Athletic Field	SSHS-B3643	012821 08:30 SSHS-B3643-SUB-2-4	SSHS-B3643-SUB-2-4	856.99	2 - 4 ft	180-116529-3	Excavated												
Northern Athletic Field	SSHS-B3644	SSHS-B3644-SUB-2-4-20210129	SSHS-B3644-SUB-2-4	856.95	2 - 4 ft	1801166654	Excavated	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-2-4	SSHS-B3646A-SUB-2-4	856.64	2 - 4 ft	180-127265-1	Excavated	< 0.03 U	< 0.021 U	< 34 U	0.044 J	< 0.052 U	< 0.04 U	< 0.036 U	< 34 U	< 0.041 U	< 0.034 UJ	< 0.026 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-2-4	SSHS-B3852-SUB-2-4	856.07	2 - 4 ft	180-127205-2	Excavated												
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-2-4-20210512	SSHS-B3917-SUB-2-4	853.71	2 - 4 ft	1801215482	Excavated	0.11 J	< 0.039 U	< 0.089 U	< 0.22 U	0.13 J	< 0.083 U	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-2-6 (4.5)	SSHS-B67-2-6 (4.5)	850.45	2 - 6 ft	180-35818-1	Excavated												
Football Field	SSHS-B70	081514 01:15 SSHS-B70-2-6 (3.5)	081514 01:15 SSHS-B70-2-6 (3.5)	855.98	2 - 6 ft	180-35818-2	Excavated												
Football Field	SSHS-B2053	072618 08:50 SSHS-B2053-SUB-4-6	SSHS-B2053-SUB-4-6	855.00	4 - 6 ft	180-80157-1	Excavated												
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-4-6	SSHS-B2226-SUB-4-6	856.56	4 - 6 ft	180-80227-1	Excavated												
Football Field	SSHS-B2615	052219 08:40 SSHS-B2615-SUB-4-6	SSHS-B2615-SUB-4-6	855.13	4 - 6 ft	180-90380-1	Excavated												
Football Field	SSHS-B2729	052219 08:40 SSHS-B2729-SUB-4-6	SSHS-B2729-SUB-4-6	856.49	4 - 6 ft	180-90380-1	Excavated												
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-4-6	SSHS-B2762-SUB-4-6	856.14	4 - 6 ft	180-89521-1	Excavated												
Football Field	SSHS-B2809	051819 10:00 SSHS-B2809-SUB-4-6	SSHS-B2809-SUB-4-6	855.39	4 - 6 ft	180-90275-1	Excavated												
Northern Athletic Field	SSHS-B3061A	012821 08:30 SSHS-B3061A-SUB-4-6	SSHS-B3061A-SUB-4-6	857.02	4 - 6 ft	180-116529-3	Excavated												
Northern Athletic Field	SSHS-B3073A	SSHS-B3073A-SUB-4-6-20210127	SSHS-B3073A-SUB-4-6	857.14	4 - 6 ft	1801165293	Excavated												
Northern Athletic Field	SSHS-B3087A	012721 08:30 SSHS-B3087A-SUB-4-6	SSHS-B3087A-SUB-4-6	857.70	4 - 6 ft	180-116404-3	Excavated												
Northern Athletic Field	SSHS-B3181A	SSHS-B3181A-SUB-4-6-20210126	SSHS-B3181A-SUB-4-6	857.57	4 - 6 ft	1801164623	Excavated												
Northern Athletic Field	SSHS-B3304A	012821 08:30 SSHS-B3304A-SUB-4-6	SSHS-B3304A-SUB-4-6	857.13	4 - 6 ft	180-116529-1	Excavated												

DRAFT

																					Emerging C
								1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	Nethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted								100	100	100										
Restricted - Residential								13000	13000	13000										
Protection of Groundwater								100	100	100										
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status													
Northern Athletic Field	SSHS-B3314	121819 10:30 SSHS-B3314-SUB-4-6	SSHS-B3314-SUB-4-6	856.94	4 - 6 ft	180-100148-2	Excavated			< 130 U										
Northern Athletic Field	SSHS-B3332	121819 10:30 SSHS-B3332-SUB-4-6	SSHS-B3332-SUB-4-6	853.06	4 - 6 ft	180-100148-1	Excavated			< 130 U										
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-4-6	SSHS-B3464-SUB-4-6	856.28	4 - 6 ft	180-108826-2	Excavated			< 110 U										
Northern Athletic Field	SSHS-B3518	012721 08:30 SSHS-B3518-SUB-4-6	SSHS-B3518-SUB-4-6	856.64	4 - 6 ft	180-116462-3	Excavated			< 120 U										
Northern Athletic Field	SSHS-B3630	012821 08:30 SSHS-B3630-SUB-4-6	SSHS-B3630-SUB-4-6	857.15	4 - 6 ft	180-116529-3	Excavated			< 490 U										
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-4-6	SSHS-B3646A-SUB-4-6	856.64	4 - 6 ft	180-127265-1	Excavated			< 110 U										
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-4-6	SSHS-B3852-SUB-4-6	856.07	4 - 6 ft	180-127205-2	Excavated			< 440 U										
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6-20210512	SSHS-B3917-SUB-4-6	853.71	4 - 6 ft	1801215482	Excavated	< 120 U			< 0.42 U	< 0.028 U	0.17 J	< 0.044 U	< 0.025 U	< 0.076 U	< 0.039 U	< 0.033 U	< 0.035 U	
Northern Athletic Field	SSHS-B4027	070221 09:00 SSHS-B4027-SUB-4-6	SSHS-B4027-SUB-4-6	856.99	4 - 6 ft	180-123985-1	Excavated			< 120 U										
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-4-6 (5)	SSHS-B64-4-6 (5)	851.65	4 - 6 ft	180-35818-2	Excavated			< 44 U										
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-4-6 (4)	SSHS-B65-4-6 (4)	850.41	4 - 6 ft	180-35818-1	Excavated			< 43 U										
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-4-6	SSHS-DW-10 11-SUB-4-6	856.18	4 - 6 ft	180-139185-1	Excavated			< 110 U										
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-4-6	SSHS-DW-13 14-SUB-4-6	857.21	4 - 6 ft	180-139185-1	Excavated			< 110 U										
Football Field	SSHS-B70	081514 01:15 SSHS-B70-6-10 (7.5)DL	081514 01:15 SSHS-B70-6-10 (7.5)DL	855.98	6 - 10 ft	180-35818-2	Excavated			< 210 U										
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-6-8	SSHS-B2226-SUB-6-8	856.56	6 - 8 ft	180-80227-1	Excavated			< 92 U										
Football Field	SSHS-B2621	051819 10:00 PS-FD-8	PS-FD-8	854.83	2 - 4 ft	180-90275-1	Excavated			< 120 U										
Football Field	SSHS-B2621	051819 10:00 SSHS-B2621-SUB-6-8	SSHS-B2621-SUB-6-8	855.04	6 - 8 ft	180-90275-1	Excavated			< 120 U										
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-6-8	SSHS-B2762-SUB-6-8	856.14	6 - 8 ft	180-89521-1	Excavated			< 230 U										
Northern Athletic Field	SSHS-B3304A	012821 08:30 SSHS-B3304A-SUB-6-8	SSHS-B3304A-SUB-6-8	857.13	6 - 8 ft	180-116529-3	Excavated			< 120 U										
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-6-8	SSHS-B3852-SUB-6-8	856.07	6 - 8 ft	180-127205-2	Excavated			< 460 U										
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8-20210512	SSHS-B3917-SUB-6-8	853.71	6 - 8 ft	1801215482	Excavated	< 130 U			< 0.42 U	< 0.028 U	0.051 J	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U	< 0.033 U	< 0.035 U	
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-6-8	SSHS-B537-SUB-6-8	850.44	6 - 8 ft	180-59029-1	Excavated			< 43 U										
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-8-10	SSHS-B2027-SUB-8-10	855.22	8 - 10 ft	180-80227-1	Excavated			< 340 U										
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-8-10	SSHS-B2223-SUB-8-10	856.38	8 - 10 ft	180-80227-2	Excavated			< 350 U										
Football Field	SSHS-B2781	051819 10:00 SSHS-B2781-SUB-8-10	SSHS-B2781-SUB-8-10	856.99	8 - 10 ft	180-90275-1	Excavated			< 110 U										
Northern Athletic Field	SSHS-B3265A	DUP-7-20210122	DUP-7	854.14	8 - 10 ft	1801163651	Excavated	< 110 U												
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10-20210122	SSHS-B3265A-SUB-8-10	854.14	8 - 10 ft	1801163651	Excavated	< 110 U			< 0.38 U	< 0.025 U	0.48 B	< 0.040 U	< 0.022 U	< 0.068 U	< 0.035 U	< 0.029 U	< 0.031 U	
Northern Athletic Field	SSHS-B3554	DUP-12-20210120	DUP-12	854.07	8 - 10 ft	1801162471	Excavated	< 110 U												
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10-20210120	SSHS-B3554-SUB-8-10	854.07	8 - 10 ft	1801162471	Excavated	< 110 U			< 0.37 U	< 0.025 U	0.47 B	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U	< 0.029 U	< 0.031 U	
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10-20210512	SSHS-B3917-SUB-8-10	853.71	8 - 10 ft	1801215482	Excavated	< 120 U			< 0.41 U	< 0.028 U	0.034 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U	< 0.032 U	< 0.034 U	
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-8-10 (9)	SSHS-B67-8-10 (9)	850.45	8 - 10 ft	180-35818-1	Excavated			< 42 U										

DRAFT

								ontaminants											
								Perfluorohexanoic acid (PFHxA)	**Perfluorononanoic acid (PFNA)**	**Perfluorooctanesulfonamide (PFOSA)**	**Perfluorooctanesulfonic acid (PFOS)**	**Perfluorooctanoic acid (PFOA)**	**Perfluoropentanoic acid (PFPeA)**	**Perfluorotetradecanoic acid (PFTeA)**	**Perfluorotridecanoic acid (PFTriA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
								ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted											0.88	0.66							
Restricted - Residential											44	33							
Protection of Groundwater											3.7	1.1							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status												
Northern Athletic Field	SSHS-B3314	121819 10:30 SSHS-B3314-SUB-4-6	SSHS-B3314-SUB-4-6	856.94	4 - 6 ft	180-100148-2	Excavated												
Northern Athletic Field	SSHS-B3332	121819 10:30 SSHS-B3332-SUB-4-6	SSHS-B3332-SUB-4-6	853.06	4 - 6 ft	180-100148-1	Excavated												
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-4-6	SSHS-B3464-SUB-4-6	856.28	4 - 6 ft	180-108826-2	Excavated												
Northern Athletic Field	SSHS-B3518	012721 08:30 SSHS-B3518-SUB-4-6	SSHS-B3518-SUB-4-6	856.64	4 - 6 ft	180-116462-3	Excavated												
Northern Athletic Field	SSHS-B3630	012821 08:30 SSHS-B3630-SUB-4-6	SSHS-B3630-SUB-4-6	857.15	4 - 6 ft	180-116529-3	Excavated												
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-4-6	SSHS-B3646A-SUB-4-6	856.64	4 - 6 ft	180-127265-1	Excavated												
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-4-6	SSHS-B3852-SUB-4-6	856.07	4 - 6 ft	180-127205-2	Excavated												
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-4-6-20210512	SSHS-B3917-SUB-4-6	853.71	4 - 6 ft	1801215482	Excavated	< 0.047 U	< 0.041 U	< 0.092 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.058 U	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B4027	070221 09:00 SSHS-B4027-SUB-4-6	SSHS-B4027-SUB-4-6	856.99	4 - 6 ft	180-123985-1	Excavated												
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-4-6 (5)	SSHS-B64-4-6 (5)	851.65	4 - 6 ft	180-35818-2	Excavated												
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-4-6 (4)	SSHS-B65-4-6 (4)	850.41	4 - 6 ft	180-35818-1	Excavated												
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-4-6	SSHS-DW-10_11-SUB-4-6	856.18	4 - 6 ft	180-139185-1	Excavated												
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-4-6	SSHS-DW-13_14-SUB-4-6	857.21	4 - 6 ft	180-139185-1	Excavated												
Football Field	SSHS-B70	081514 01:15 SSHS-B70-6-10 (7.5)DL	081514 01:15 SSHS-B70-6-10 (7.5)DL	855.98	6 - 10 ft	180-35818-2	Excavated												
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-6-8	SSHS-B2226-SUB-6-8	856.56	6 - 8 ft	180-80227-1	Excavated												
Football Field	SSHS-B2621	051819 10:00 PS-FD-8	PS-FD-8	854.83	2 - 4 ft	180-90275-1	Excavated												
Football Field	SSHS-B2621	051819 10:00 SSHS-B2621-SUB-6-8	SSHS-B2621-SUB-6-8	855.04	6 - 8 ft	180-90275-1	Excavated												
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-6-8	SSHS-B2762-SUB-6-8	856.14	6 - 8 ft	180-89521-1	Excavated												
Northern Athletic Field	SSHS-B3304A	012821 08:30 SSHS-B3304A-SUB-6-8	SSHS-B3304A-SUB-6-8	857.13	6 - 8 ft	180-116529-3	Excavated												
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-6-8	SSHS-B3852-SUB-6-8	856.07	6 - 8 ft	180-127205-2	Excavated												
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-6-8-20210512	SSHS-B3917-SUB-6-8	853.71	6 - 8 ft	1801215482	Excavated	< 0.047 U	< 0.041 U	< 0.093 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.058 U	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-6-8	SSHS-B537-SUB-6-8	850.44	6 - 8 ft	180-59029-1	Excavated												
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-8-10	SSHS-B2027-SUB-8-10	855.22	8 - 10 ft	180-80227-1	Excavated												
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-8-10	SSHS-B2223-SUB-8-10	856.38	8 - 10 ft	180-80227-2	Excavated												
Football Field	SSHS-B2781	051819 10:00 SSHS-B2781-SUB-8-10	SSHS-B2781-SUB-8-10	856.99	8 - 10 ft	180-90275-1	Excavated												
Northern Athletic Field	SSHS-B3265A	DUP-7-20210122	DUP-7	854.14	8 - 10 ft	1801163651	Excavated												
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-8-10-20210122	SSHS-B3265A-SUB-8-10	854.14	8 - 10 ft	1801163651	Excavated	< 0.043 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3554	DUP-12-20210120	DUP-12	854.07	8 - 10 ft	1801162471	Excavated												
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-8-10-20210120	SSHS-B3554-SUB-8-10	854.07	8 - 10 ft	1801162471	Excavated	< 0.043 U	< 0.036 U	< 0.083 U	0.23 BJ	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-8-10-20210512	SSHS-B3917-SUB-8-10	853.71	8 - 10 ft	1801215482	Excavated	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-8-10 (9)	SSHS-B67-8-10 (9)	850.45	8 - 10 ft	180-35818-1	Excavated												

DRAFT

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B2760A	SSHS-B2760-SUB-16-18	5/18/2019	856.24	16 - 18 ft	180-90319-3	Not Excavated	0.025	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.025	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2761	SSHS-B2761-SUB-16-18	5/18/2019	856.14	16 - 18 ft	180-90319-3	Not Excavated	1.67	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	1.1 J	0.39 J	0.18 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3012A	SSHS-B3012A-SUB-16-18	7/26/2021	853.25	16 - 18 ft	180-124973-1	Not Excavated	0.45	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.45	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3013A	SSHS-B3013A-SUB-16-18	7/26/2021	852.88	16 - 18 ft	180-124973-1	Not Excavated	0.27	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.27	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	1.913	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.5	0.4	0.013 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-18-20	1/23/2021	853.60	18 - 20 ft	1801164041	Not Excavated	0.28	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.21	0.07	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-20-22	1/23/2021	853.60	20 - 22 ft	1801164041	Not Excavated	0.055	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.041	0.014 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-22-24	1/23/2021	853.60	22 - 24 ft	1801164043	Not Excavated	0.103	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.08	0.023	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-16-18	8/30/2019	858.28	16 - 18 ft	180-95047-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	16 - 18 ft	180-116310-1	Not Excavated	65.1	< 0.3 U	< 0.32 U	< 0.22 U	< 0.13 U	51 J	13 J	1.1 J	< 0.32 U	< 0.12 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-18-20	1/21/2021	854.31	18 - 20 ft	180-116310-1	Not Excavated	4.17	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	3.1 J	0.94 J	0.13 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-20-22	1/21/2021	854.31	20 - 22 ft	180-116310-1	Not Excavated	9.89	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	7.3 J	2.3 J	0.29 J	< 0.065 U	< 0.025 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-22-24	1/21/2021	854.31	22 - 24 ft	180-116310-2	Not Excavated	2.338	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.7 J	0.62 J	0.018 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	1.294	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1	0.26	0.034	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	0.68	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.53	0.13	0.02	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-20-22	1/22/2021	854.14	20 - 22 ft	1801163651	Not Excavated	0.28	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.23	0.05	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-16-18	1/21/2021	853.76	16 - 18 ft	180-116310-1	Not Excavated	117.4	< 0.59 U	< 0.64 U	< 0.44 U	< 0.27 U	85 J	30 J	2.4 J	< 0.64 U	< 0.24 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-18-20	1/21/2021	853.76	18 - 20 ft	180-116310-1	Not Excavated	0.973	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.73 J	0.21 J	0.033 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-20-22	1/21/2021	853.76	20 - 22 ft	180-116310-1	Not Excavated	2.173	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.6 J	0.48 J	0.093 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	2011	< 6.1 U	< 6.6 U	< 4.6 U	< 2.7 U	1600	380	31	< 6.6 U	< 2.5 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	853.65	18 - 20 ft	1801163651	Not Excavated	844	< 5.9 U	< 6.4 U	< 4.4 U	< 2.6 U	670	160	14 J	< 6.3 U	< 2.4 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	853.65	20 - 22 ft	1801163651	Not Excavated	26.44	< 0.063 U	< 0.069 U	< 0.047 U	< 0.028 U	21	5.1	0.34	< 0.068 U	< 0.026 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	853.65	22 - 24 ft	1801163652	Not Excavated	13000	< 64 U	< 69 U	< 48 U	< 29 U	9600	3400	< 56 U	< 69 U	< 26 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-16-18	1/23/2021	853.86	16 - 18 ft	180-116404-1	Not Excavated	1.74	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.4 J	0.34 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-18-20	1/23/2021	853.86	18 - 20 ft	180-116404-1	Not Excavated	0.61	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.45 J	0.16 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-20-22	1/23/2021	853.86	20 - 22 ft	180-116404-1	Not Excavated	0.8787	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.64 J	0.23 J	0.0087 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-22-24	1/23/2021	853.86	22 - 24 ft	180-116404-3	Not Excavated	0.122	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.089 J	0.033 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-16-18	1/21/2021	854.61	16 - 18 ft	180-116310-1	Not Excavated	0.431	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.32 J	0.095 J	0.016 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-18-20	1/22/2021	854.61	18 - 20 ft	180-116365-1	Not Excavated	0.729	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.55 J	0.15 J	0.029 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-20-22	1/22/2021	854.61	20 - 22 ft	180-116365-1	Not Excavated	0.087	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.07 J	0.017 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	0.63	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.47	0.16	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-18-20	1/20/2021	854.07	18 - 20 ft	1801162471	Not Excavated	4.31	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	3.1	1.1	0.11	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-20-22	1/20/2021	854.07	20 - 22 ft	1801162471	Not Excavated	4.52	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	3.3	1.1	0.12	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-22-23	1/20/2021	854.07	22 - 23 ft	1801162472	Not Excavated	3.626	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	2.6	0.93	0.096	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	0.123	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.09 J	0.033 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	0.052	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.039 J	0.013 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	0.056	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.04 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-20-22	1/11/2021	855.30	20 - 22 ft	180-115815-1	Not Excavated	0.035	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.035	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-22-24	1/11/2021	855.30	22 - 24 ft	180-115815-1	Not Excavated	0.0084	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0084 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3556	DUP-22	1/13/2021	855.33	16 - 18 ft	180-115925-1	Not Excavated	0.619	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.43 J	0.14 J	0.049 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-16-18	1/13/2021	855.33	16 - 18 ft	180-115925-1	Not Excavated	0.448	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.3 J	0.11 J	0.038 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	0.0426	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.036 J	0.0066 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-20-22	1/13/2021	855.33	20 - 22 ft	180-115925-1	Not Excavated	0.024	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.024	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-22-24	1/13/2021	855.33	22 - 24 ft	180-115925-1	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3557	DUP-23	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	0.063	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.046 J	0.017 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	0.021	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.021 J	< 0.0057 UJ	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	0.028	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.028	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-20-22	1/11/2021	855.18	20 - 22 ft	180-115815-1	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-22-24	1/11/2021	855.18	22 - 24 ft	180-115815-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	DUP-24	1/12/2021	855.27	16 - 18 ft	180-115861-2	Not Excavated	0.3407	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.27	0.062	0.0087 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	0.262	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.2 J	0.062 J	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	0.328	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.28 J	0.048 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	0.329	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.27 J	0.059 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-22-24	1/12/2021	855.27	22 - 24 ft	180-115861-1	Not Excavated	0.063	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.052 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3559	DUP-25	1/12/2021	855.35	16 - 18 ft	180-115861-2	Not Excavated	1.142	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.87	0.24	0.032	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	1.151	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.9 J	0.22 J	0.031 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	0.987	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.76 J	0.2 J	0.027 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-20-22	1/12/2021	855.35	20 - 22 ft	180-115861-1	Not Excavated	0.409	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.32 J	0.078 J	0.011 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-22-24	1/12/2021	855.35	22 - 24 ft	180-115861-1	Not Excavated	1.406	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.1 J	0.27 J	0.036 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3560	DUP-26	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	0.08	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.058 J	0.022 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	0.055	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.04 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-18-20	1/11/2021	855.32	18 - 20 ft	180-115815-1	Not Excavated	0.02	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.02	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-20-22	1/11/2021	855.32	20 - 22 ft	180-115815-1	Not Excavated	0.218	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.19 J	0.028 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-22-24	1/11/2021	855.32	22 - 24 ft	180-115815-1	Not Excavated	1.22	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	1 J	0.22 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	0.238	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.22 J	0.018 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	0.391	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.37 J	0.021 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-20-22	1/13/2021	855.17	20 - 22 ft	180-115925-1	Not Excavated	0.255	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.22 J	0.035 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-22-24	1/13/2021	855.17	22 - 24 ft	180-115925-1	Not Excavated	0.441	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.38 J	0.061 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	38.1	< 0.12 U	< 0.14 U	< 0.093 U	< 0.056 U	30 J	7.1 J	1 J	< 0.13 U	< 0.052 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-18-20	1/13/2021	855.07	18 - 20 ft	180-115925-1	Not Excavated	0.106	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.088 J	0.018 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-20-22	1/13/2021	855.07	20 - 22 ft	180-115925-1	Not Excavated	0.093	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.076 J	0.017 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-22-24	1/13/2021	855.07	22 - 24 ft	180-115925-1	Not Excavated	0.3439	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.27 J	0.064 J	0.0099 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-16-18	1/11/2021	855.01	16 - 18 ft	180-115815-1	Not Excavated	2.22	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.8 J	0.42 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	7.591	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	5.7 J	1.8 J	0.091 J	< 0.0064 U	< 0.0025 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3563	SSHS-B3563-SUB-20-22	1/11/2021	855.01	20 - 22 ft	180-115815-1	Not Excavated	14.63	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	11 J	3.5 J	0.13 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-22-24	1/11/2021	855.01	22 - 24 ft	180-115815-1	Not Excavated	547.8	< 2.9 U	< 3.2 U	< 2.2 U	< 1.3 U	400 J	140 J	7.8 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	24 - 26 ft	180-115999-1	Not Excavated	306.6	< 0.58 U	< 0.63 U	< 0.43 U	< 0.26 U	220 J	79 J	7.6 J	< 0.62 U	< 0.24 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	26 - 28 ft	180-115999-1	Not Excavated	581	< 1.2 U	< 1.3 U	< 0.86 U	< 0.52 U	420 J	150 J	11 J	< 1.2 U	< 0.48 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	28 - 30 ft	180-115999-1	Not Excavated	1411	< 1.2 U	< 1.3 U	< 0.93 U	< 0.56 U	1000 J	380 J	31 J	< 1.3 U	< 0.51 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	30 - 32 ft	180-115999-1	Not Excavated	14.64	< 0.067 U	< 0.073 U	< 0.05 U	< 0.03 U	11 J	3.5 J	0.14 J	< 0.072 U	< 0.028 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	32 - 34 ft	180-115999-1	Not Excavated	7.44	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	5.4 J	1.9 J	0.14 J	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	34 - 36 ft	180-115999-1	Not Excavated	96.9	< 0.7 U	< 0.76 U	< 0.53 U	< 0.32 U	69 J	25 J	2.9 J	< 0.76 U	< 0.29 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	36 - 37 ft	180-116070-1	Not Excavated	833	< 6.3 U	< 6.8 U	< 4.7 U	< 2.8 U	620 J	190 J	23 J	< 6.8 U	< 2.6 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-16-18	1/12/2021	855.22	16 - 18 ft	180-115861-1	Not Excavated	12100	< 60 U	< 65 U	< 45 U	< 27 U	9500 J	2300 J	300 J	< 65 U	< 25 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	3656	< 5.8 U	< 6.3 U	< 4.3 U	< 2.6 U	2900 J	680 J	76 J	< 6.3 U	< 2.4 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-20-22	1/12/2021	855.22	20 - 22 ft	180-115861-1	Not Excavated	2124	< 6.2 U	< 6.8 U	< 4.7 U	< 2.8 U	1700 J	380 J	44 J	< 6.7 U	< 2.6 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-22-24	1/12/2021	855.22	22 - 24 ft	180-115861-1	Not Excavated	1094	< 6 U	< 6.5 U	< 4.5 U	< 2.7 U	870 J	200 J	24 J	< 6.4 U	< 2.5 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	24 - 26 ft	180-116070-1	Not Excavated	19240	< 59 U	< 64 U	< 44 U	< 27 U	15000 J	3500 J	740 J	< 64 U	< 24 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	26 - 28 ft	180-116070-1	Not Excavated	6.59	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	5 J	1.4 J	0.19 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	28 - 30 ft	180-116070-1	Not Excavated	3.96	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	3 J	0.85 J	0.11 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	30 - 32 ft	180-116070-1	Not Excavated	3.29	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	2.4 J	0.74 J	0.15 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	32 - 34 ft	180-116070-1	Not Excavated	16.62	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	13 J	3.2 J	0.42 J	< 0.068 U	< 0.026 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	34 - 36 ft	180-116070-1	Not Excavated	1.581	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	1.1 J	0.46 J	0.021 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	36 - 37 ft	180-116070-1	Not Excavated	9596	< 67 U	< 73 U	< 51 U	< 30 U	7100 J	2400 J	96 J	< 73 U	< 28 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	0.057	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.045	0.012 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	4.43	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	3.4	0.89	0.14	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-20-22	1/12/2021	855.32	20 - 22 ft	180-115861-2	Not Excavated	0.347	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.27	0.067	0.01 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-22-24	1/13/2021	855.32	22 - 24 ft	180-115925-1	Not Excavated	0.014	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.014 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-16-18	1/12/2021	855.28	16 - 18 ft	180-115861-2	Not Excavated	5.74	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	3.9	1.6	0.24	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	0.128	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.091	0.037	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-20-22	1/12/2021	855.28	20 - 22 ft	180-115861-2	Not Excavated	0.188	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.15	0.038	< 0.0051 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-22-24	1/12/2021	855.28	22 - 24 ft	180-115861-2	Not Excavated	0.213	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.17	0.043	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	3.06	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	2.4 J	0.56 J	0.1 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	2.305	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.8 J	0.43 J	0.075 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-20-22	1/18/2021	855.08	20 - 22 ft	180-116109-1	Not Excavated	0.592	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.52 J	0.072 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-22-24	1/18/2021	855.08	22 - 24 ft	180-116109-1	Not Excavated	0.83	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.67 J	0.16 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-24-26	1/18/2021	855.08	24 - 26 ft	180-116109-1	Not Excavated	1.11	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.94 J	0.17 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-26-28	1/18/2021	855.08	26 - 28 ft	180-116109-1	Not Excavated	1.34	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1 J	0.34 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-28-30	1/18/2021	855.08	28 - 30 ft	180-116109-1	Not Excavated	1.59	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	1.3 J	0.29 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-30-32	1/18/2021	855.08	30 - 32 ft	180-116109-1	Not Excavated	4.07	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	3.7 J	0.37 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3568	DUP-30	1/18/2021	855.08	32 - 34 ft	180-116109-1	Not Excavated	2.54	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	2.1 J	0.44 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-32-34	1/18/2021	855.08	32 - 34 ft	180-116109-1	Not Excavated	1.69	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.003 U	1.4 J	0.29 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3568	DUP-31	1/18/2021	855.08	34 - 35 ft	180-116109-1	Not Excavated	0.963	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.89 J	0.073 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-34-35	1/18/2021	855.08	34 - 36 ft	180-116109-1	Not Excavated	1.94	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.8 J	0.14 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-16-18	1/19/2021	855.07	16 - 18 ft	180-116199-1	Not Excavated	0.321	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.27	0.051	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	0.171	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.14	0.031	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-20-22	1/19/2021	855.07	20 - 22 ft	180-116199-1	Not Excavated	0.189	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.14	0.049	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-22-24	1/19/2021	855.07	22 - 24 ft	180-116199-1	Not Excavated	0.159	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.12	0.039	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-24-26	1/19/2021	855.07	24 - 26 ft	180-116199-1	Not Excavated	0.116	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.092	0.024	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-26-28	1/19/2021	855.07	26 - 28 ft	180-116199-1	Not Excavated	0.121	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.089	0.032	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-28-30	1/19/2021	855.07	28 - 30 ft	180-116199-1	Not Excavated	0.03	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.03	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-30-32	1/19/2021	855.07	30 - 32 ft	180-116199-1	Not Excavated	0.028	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.028	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	DUP-32	1/19/2021	855.07	32 - 34 ft	180-116199-1	Not Excavated	0.053	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.039	0.014 J	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-32-34	1/19/2021	855.07	32 - 34 ft	180-116199-1	Not Excavated	0.089	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.066	0.023	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3569	DUP-33	1/19/2021	855.07	34 - 36 ft	180-116199-1	Not Excavated	0.026	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.026	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-16-18	1/19/2021	855.27	16 - 18 ft	180-116199-1	Not Excavated	5900	< 6 U	< 6.5 U	< 4.5 U	< 2.7 U	4600	1300	< 5.2 U	< 6.5 U	< 2.5 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	2440	< 5.8 U	< 6.3 U	< 4.3 U	< 2.6 U	1700	580	160	< 6.2 U	< 2.4 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	3990	< 5.9 U	< 6.4 U	< 4.4 U	< 2.7 U	3200	790	< 5.2 U	< 6.4 U	< 2.4 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-22-24	1/19/2021	855.27	22 - 24 ft	180-116199-1	Not Excavated	2850	< 6.1 U	< 6.7 U	< 4.6 U	< 2.8 U	2200	540	110	< 6.6 U	< 2.5 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-24-26	1/19/2021	855.27	24 - 26 ft	180-116199-1	Not Excavated	621	< 6 U	< 6.6 U	< 4.5 U	< 2.7 U	480	110	31	< 6.5 U	< 2.5 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-26-28	1/19/2021	855.27	26 - 28 ft	180-116199-1	Not Excavated	4560	< 6.1 U	< 6.7 U	< 4.6 U	< 2.8 U	3400	960	200	< 6.6 U	< 2.5 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-28-30	1/19/2021	855.27	28 - 30 ft	180-116199-1	Not Excavated	69.6	< 0.33 U	< 0.36 U	< 0.25 U	< 0.15 U	55	12	2.6	< 0.36 U	< 0.14 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-30-32	1/19/2021	855.27	30 - 32 ft	180-116199-1	Not Excavated	86.4	< 0.33 U	< 0.36 U	< 0.24 U	< 0.15 U	67	16	3.4	< 0.35 U	< 0.14 U
Football Field	SSHS-B3570	DUP-34	1/19/2021	855.27	32 - 34 ft	180-116199-1	Not Excavated	104.2	< 0.34 U	< 0.38 U	< 0.26 U	< 0.16 U	78	24	2.2	< 0.37 U	< 0.14 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-32-34	1/19/2021	855.27	32 - 34 ft	180-116199-1	Not Excavated	74.5	< 0.35 U	< 0.38 U	< 0.26 U	< 0.16 U	58	14	2.5	< 0.38 U	< 0.14 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-34-35	1/19/2021	855.27	34 - 36 ft	180-116199-1	Not Excavated	245.6	< 0.65 U	< 0.71 U	< 0.49 U	< 0.29 U	190	46	9.6	< 0.7 U	< 0.27 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-16-18	1/18/2021	855.21	16 - 18 ft	180-116109-1	Not Excavated	4.677	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	3.4 J	1.2 J	0.077 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-18-20	1/18/2021	855.21	18 - 20 ft	180-116109-1	Not Excavated	0.49	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.36 J	0.13 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-20-22	1/18/2021	855.21	20 - 22 ft	180-116109-1	Not Excavated	0.265	< 0.0085 U	< 0.0092 U	< 0.0063 U	< 0.0038 U	0.19 J	0.075 J	< 0.0074 U	< 0.0092 U	< 0.0035 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-22-24	1/18/2021	855.21	22 - 24 ft	180-116109-1	Not Excavated	0.07	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.051 J	0.019 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-24-26	1/18/2021	855.21	24 - 26 ft	180-116109-1	Not Excavated	0.66	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.48 J	0.18 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-26-28	1/18/2021	855.21	26 - 28 ft	180-116109-1	Not Excavated	0.061	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.044 J	0.017 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-28-30	1/18/2021	855.21	28 - 30 ft	180-116109-1	Not Excavated	0.0391	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.03 J	0.0091 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-30-32	1/18/2021	855.21	30 - 32 ft	180-116109-1	Not Excavated	0.048	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.037 J	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3571	DUP-35	1/18/2021	855.21	32 - 34 ft	180-116109-1	Not Excavated	0.025	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.025	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-32-34	1/18/2021	855.21	32 - 34 ft	180-116109-1	Not Excavated	0.022	< 0.0073 U	< 0.0079 U	< 0.0055 U	< 0.0033 U	0.022	< 0.0067 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Northern Athletic Field	SSHS-B3600	SSHS-B3600-SUB-16-18	1/28/2021	851.93	16 - 18 ft	180-116609-1	Not Excavated	0.289	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.21	0.079	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3600	SSHS-B3600-SUB-18-20	1/28/2021	851.93	18 - 20 ft	180-116609-2	Not Excavated	0.043	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.031 J	0.012 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3601	SSHS-B3601-SUB-16-18	1/28/2021	852.55	16 - 18 ft	180-116609-1	Not Excavated	0.3	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.22	0.08	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3601	SSHS-B3601-SUB-18-20	1/28/2021	852.55	18 - 20 ft	180-116609-2	Not Excavated	0.91	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.65 J	0.25 J	0.01 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3602	SSHS-B3602-SUB-16-18	7/19/2021	852.97	16 - 18 ft	180-124670-1	Not Excavated	0.017	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.034 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	0.189	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.11 J	0.079 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	0.055	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.034 J	0.021 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	0.0312	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022 J	0.0092 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	0.053	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.036 J	0.017 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	0.011	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.011 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	0.444	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.31 J	0.11 J	0.024 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	ND	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.0035 U	< 0.0057 U	< 0.0072 U	< 0.0068 U	< 0.0084 U	< 0.0032 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-20-22	4/12/2021	855.28	20 - 22 ft	180-119861-1	Not Excavated	0.07	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.054 J	0.016 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-22-24	4/12/2021	855.28	22 - 24 ft	180-119861-1	Not Excavated	0.09	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.072 J	0.018 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-24-26	4/12/2021	855.28	24 - 26 ft	180-119861-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-26-28	4/12/2021	855.28	26 - 28 ft	180-119861-1	Not Excavated	0.015	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.015 J	< 0.006 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-28-30	4/12/2021	855.28	28 - 30 ft	180-119861-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-30-32	4/13/2021	855.28	30 - 32 ft	180-119938-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-32-34	4/13/2021	855.28	32 - 34 ft	180-119938-2	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-16-18	4/7/2021	855.86	16 - 18 ft	180-119671-1	Not Excavated	0.025	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.025	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-18-20	4/7/2021	855.86	18 - 20 ft	180-119671-1	Not Excavated	0.161	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.13 J	0.031 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3856	DUP-10	4/7/2021	855.86	20 - 22 ft	180-119671-1	Not Excavated	0.074	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.048 J	0.026 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-20-22	4/7/2021	855.86	20 - 22 ft	180-119671-1	Not Excavated	0.222	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.17 J	0.052 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-22-24	4/7/2021	855.86	22 - 24 ft	180-119671-1	Not Excavated	0.017	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.017 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3856	DUP-36	4/7/2021	855.86	24 - 26 ft	180-119671-1	Not Excavated	0.021	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.021	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-24-26	4/7/2021	855.86	24 - 26 ft	180-119671-1	Not Excavated	0.02	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.02	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-26-28	4/7/2021	855.86	26 - 28 ft	180-119671-1	Not Excavated	0.022	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.022	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-28-30	4/7/2021	855.86	28 - 30 ft	180-119671-1	Not Excavated	0.047	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.047	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-30-32	4/8/2021	855.86	30 - 32 ft	180-119767-1	Not Excavated	0.098	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.078 J	0.02 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-32-34	4/8/2021	855.86	32 - 34 ft	180-119767-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-34-36	4/8/2021	855.86	34 - 36 ft	180-119767-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-16-18	4/7/2021	855.25	16 - 18 ft	180-119671-1	Not Excavated	0.185	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12 J	0.065 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-18-20	4/7/2021	855.25	18 - 20 ft	180-119671-1	Not Excavated	0.114	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.077 J	0.037 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-20-22	4/7/2021	855.25	20 - 22 ft	180-119671-1	Not Excavated	0.145	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.1 J	0.045 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-22-24	4/7/2021	855.25	22 - 24 ft	180-119671-1	Not Excavated	0.314	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.22 J	0.094 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-24-26	4/7/2021	855.25	24 - 26 ft	180-119671-1	Not Excavated	0.014	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	0.014 J	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-26-28	4/7/2021	855.25	26 - 28 ft	180-119671-2	Not Excavated	0.097	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.081 J	0.016 J	< 0.0065 U	< 0.008 U	< 0.003 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-16-18	4/10/2021	856.08	16 - 18 ft	180-119841-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3858	DUP-12	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	0.022	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.022 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 UJ	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3858	DUP-34	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	0.027	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.027	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	0.029	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.029	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	0.704	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.52	0.16	0.024	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-22-24	4/10/2021	856.08	22 - 24 ft	180-119841-1	Not Excavated	0.068	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.042 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-24-26	4/10/2021	856.08	24 - 26 ft	180-119841-1	Not Excavated	0.021	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.021	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-26-28	4/10/2021	856.08	26 - 28 ft	180-119841-1	Not Excavated	0.021	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.021	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-28-30	4/10/2021	856.08	28 - 30 ft	180-119841-1	Not Excavated	0.1042	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.038 J	0.058 J	0.0082 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-30-31	4/10/2021	856.08	30 - 31 ft	180-119841-1	Not Excavated	0.45	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.17 J	0.28 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-31-33	4/10/2021	856.08	31 - 33 ft	180-119841-1	Not Excavated	0.017	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.017 J	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-33-35	4/10/2021	856.08	33 - 35 ft	180-119841-2	Not Excavated	0.015	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.015 J	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3859	DUP-13	4/12/2021	857.14	16 - 18 ft	180-119861-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 UJ	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-16-18	4/12/2021	857.14	16 - 18 ft	180-119861-1	Not Excavated	0.013	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.013 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	0.059	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.045 J	0.014 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	0.021	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.021	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-24-26	4/12/2021	857.14	24 - 26 ft	180-119861-1	Not Excavated	0.0095	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0095 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	0.056	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.039 J	0.017 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3859	DUP-35	4/12/2021	857.14	28 - 30 ft	180-119861-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-28-30	4/12/2021	857.14	28 - 30 ft	180-119861-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0028 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-30-32	4/12/2021	857.14	30 - 32 ft	180-119861-1	Not Excavated	0.015	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.015 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-32-34	4/12/2021	857.14	32 - 34 ft	180-119861-1	Not Excavated	0.011	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.011 J	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-34-36	4/12/2021	857.14	34 - 36 ft	180-119861-2	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	0.061	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.061	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	0.109	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.082 J	0.027 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	0.02	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.02	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	0.022	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.022 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	0.014	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	0.021	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.021	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-16-18	4/14/2021	855.76	16 - 18 ft	180-120028-1	Not Excavated	0.062	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.045 J	0.017 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-18-20	4/14/2021	855.76	18 - 20 ft	180-120028-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-20-22	4/14/2021	855.76	20 - 22 ft	180-120028-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-22-24	4/14/2021	855.76	22 - 24 ft	180-120028-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-24-26	4/14/2021	855.76	24 - 26 ft	180-120028-1	Not Excavated	0.077	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.052 J	0.025 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-26-28	4/14/2021	855.76	26 - 28 ft	180-120028-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-28-30	4/14/2021	855.76	28 - 30 ft	180-120028-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-30-32	4/14/2021	855.76	30 - 32 ft	180-120028-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-32-34	4/14/2021	855.76	32 - 34 ft	180-120028-1	Not Excavated	0.147	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.11 J	0.037 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-34-36	4/14/2021	855.76	34 - 36 ft	180-120028-1	Not Excavated	0.023	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.023	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-36-38	4/14/2021	855.76	36 - 38 ft	180-120028-2	Not Excavated	0.013	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.013 J	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	2.642	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	2.1 J	0.51 J	0.032 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	0.166	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.13 J	0.036 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3863	DUP-18	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	0.056	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056	< 0.0052 UJ	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	0.109	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.083 J	0.026 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	0.094	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.072 J	0.022 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-24-26	4/9/2021	855.85	24 - 26 ft	180-119815-1	Not Excavated	0.13	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.1 J	0.03 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-26-28	4/9/2021	855.85	26 - 28 ft	180-119815-1	Not Excavated	0.092	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.092	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	0.103	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.08 J	0.023 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-30-32	4/9/2021	855.85	30 - 32 ft	180-119815-1	Not Excavated	0.166	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.13 J	0.036 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-32-34	4/9/2021	855.85	32 - 34 ft	180-119815-1	Not Excavated	0.047	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.047	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-34-36	4/9/2021	855.85	34 - 36 ft	180-119815-1	Not Excavated	0.102	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.071 J	0.031 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-36-37	4/10/2021	855.85	36 - 37 ft	180-119841-1	Not Excavated	0.143	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.11 J	0.033 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-37-39	4/10/2021	855.85	37 - 39 ft	180-119841-1	Not Excavated	0.026	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	0.026	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-39-41	4/10/2021	855.85	39 - 41 ft	180-119841-2	Not Excavated	ND	< 0.0082 U	< 0.009 U	< 0.0062 U	< 0.0037 U	< 0.0061 U	< 0.0076 U	< 0.0072 U	< 0.0089 U	< 0.0034 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	0.306	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.24 J	0.066 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	0.293	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.22 J	0.073 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	0.431	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.31 J	0.11 J	0.011 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	0.287	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.22 J	0.067 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	0.09	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.068 J	0.022 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	0.014	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.014 J	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	0.033	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.033	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	0.024	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.024	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	0.12	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.094 J	0.026 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	0.038	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.038	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	0.021	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.021	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	0.05	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.027 J	0.023 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	0.044	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.027 J	0.017 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	0.077	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.062 J	0.015 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	0.056	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.038 J	0.018 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	0.026	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.026	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 UJ	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	0.017	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.017 J	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-16-18	4/7/2021	855.09	16 - 18 ft	180-119671-1	Not Excavated	0.163	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.13 J	0.033 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3866	DUP-21	4/7/2021	855.09	18 - 20 ft	180-119671-1	Not Excavated	0.117	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.086 J	0.031 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-18-20	4/7/2021	855.09	18 - 20 ft	180-119671-1	Not Excavated	0.036	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.036 J	< 0.0058 UJ	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-20-22	4/7/2021	855.09	20 - 22 ft	180-119671-1	Not Excavated	0.077	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.062 J	0.015 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-22-23	4/7/2021	855.09	22 - 23 ft	180-119671-1	Not Excavated	0.045	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.045	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-23-25	4/7/2021	855.09	23 - 25 ft	180-119671-1	Not Excavated	0.064	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.049 J	0.015 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-25-27	4/7/2021	855.09	25 - 27 ft	180-119671-2	Not Excavated	0.0624	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.053 J	0.0094 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	0.122	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.098	0.024	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	0.019	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.019 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	0.048	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.037	0.011 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	0.108	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.085	0.023	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	0.067	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.055	0.012 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	0.033	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.033	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	0.031	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.031	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	ND	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-16-18	3/31/2021	855.62	16 - 18 ft	180-119460-1	Not Excavated	0.023	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.023	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-18-20	3/31/2021	855.62	18 - 20 ft	180-119460-1	Not Excavated	0.023	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.023	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-20-22	3/31/2021	855.62	20 - 22 ft	180-119460-1	Not Excavated	0.03	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.03	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3868	040321 10:45_DUP-23	3/31/2021	855.62	22 - 24 ft	180-119460-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-22-24	3/31/2021	855.62	22 - 24 ft	180-119460-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-24-26	3/31/2021	855.62	24 - 26 ft	180-119460-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-26-28	3/31/2021	855.62	26 - 28 ft	180-119460-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-28-29	3/31/2021	855.62	28 - 29 ft	180-119460-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-29-30	3/31/2021	855.62	29 - 30 ft	180-119460-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-30-32	4/1/2021	855.62	30 - 32 ft	180-119460-1	Not Excavated	0.068	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.05 J	0.018 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-32-33	4/1/2021	855.62	32 - 33 ft	180-119460-2	Not Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-16-18	3/31/2021	856.45	16 - 18 ft	180-119460-1	Not Excavated	0.268	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.22 J	0.048 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-18-20	3/31/2021	856.45	18 - 20 ft	180-119460-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-20-22	3/31/2021	856.45	20 - 22 ft	180-119460-1	Not Excavated	0.019	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.019	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-22-24	3/31/2021	856.45	22 - 24 ft	180-119460-1	Not Excavated	0.021	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.021	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-24-26	3/31/2021	856.45	24 - 26 ft	180-119460-1	Not Excavated	0.033	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.033	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-26-28	3/31/2021	856.45	26 - 28 ft	180-119460-1	Not Excavated	0.025	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.025	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-28-30	3/31/2021	856.45	28 - 30 ft	180-119460-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-30-32	3/31/2021	856.45	30 - 32 ft	180-119460-1	Not Excavated	0.03	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.03	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-32-34	3/31/2021	856.45	32 - 34 ft	180-119460-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-34-36	3/31/2021	856.45	34 - 36 ft	180-119460-2	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	175	< 0.58 U	< 0.63 U	< 0.43 U	< 0.034 U	110 J	53 J	12 J	< 0.62 U	< 0.24 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	930	< 3 U	< 3.2 U	< 2.2 U	< 0.034 U	750 J	150 J	30 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	175.6	< 0.61 U	< 0.66 U	< 0.45 U	< 0.034 U	140 J	30 J	5.6 J	< 0.65 U	< 0.25 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	148.5	< 0.68 U	< 0.74 U	< 0.51 U	< 0.034 U	120 J	24 J	4.5 J	< 0.73 U	< 0.28 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	215.5	< 0.68 U	< 0.74 U	< 0.51 U	< 0.034 U	170 J	38 J	7.5 J	< 0.74 U	< 0.28 U
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	25.6	< 0.07 U	< 0.076 U	< 0.052 U	< 0.034 U	19 J	5.6 J	1 J	< 0.075 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	21.04	< 0.064 U	< 0.07 U	< 0.048 U	< 0.034 U	16 J	4.5 J	0.54 J	< 0.07 U	< 0.027 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	14.5	< 0.034 U	< 0.074 U	< 0.051 U	< 0.034 U	11 J	3.1 J	0.4 J	< 0.074 U	< 0.028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	8.9	< 0.065 U	< 0.071 U	< 0.049 U	< 0.034 U	7 J	1.9 J	< 0.057 U	< 0.071 U	< 0.027 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	62.8	< 0.071 U	< 0.077 U	< 0.053 U	< 0.034 U	51 J	10 J	1.8 J	< 0.077 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	0.901	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.034 U	0.73 J	0.14 J	0.031 J	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	0.439	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.034 U	0.35 J	0.075 J	0.014 J	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated	0.982	< U	< U	< U	< U	0.79 J	0.16 J	0.032 J	< U	< U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	667	< 3 U	< 3.2 U	< 2.2 U	< 0.034 U	500 J	150 J	17 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	567	< 3 U	< 3.3 U	< 2.2 U	< 0.034 U	470 J	85 J	12 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	361.1	< 1.2 U	< 1.3 U	< 0.89 U	< 0.034 U	300 J	54 J	7.1 J	< 1.3 U	< 0.49 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	4.27	< 0.062 U	< 0.067 U	< 0.046 U	< 0.034 U	3.2 J	0.95 J	0.12 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	5.67	< 0.059 U	< 0.064 U	< 0.044 U	< 0.034 U	4.7 J	0.81 J	0.16 J	< 0.064 U	< 0.024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	2.36	< 0.058 U	< 0.063 U	< 0.043 U	< 0.034 U	2 J	0.36 J	< 0.05 U	< 0.062 U	< 0.024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	1.478	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.034 U	1.2 J	0.24 J	0.038 J	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	2.21	< 0.064 U	< 0.069 U	< 0.048 U	< 0.034 U	1.7 J	0.51 J	< 0.056 U	< 0.069 U	< 0.026 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	4.5	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	3.4 J	1.1 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	0.704	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.52 J	0.16 J	0.024 J	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	1.27	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.99 J	0.28 J	< 0.0054 UJ	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	2.554	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	2.2 J	0.31 J	0.044 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	5.976	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	5 J	0.89 J	0.086 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	1.475	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.034 U	1.1 J	0.33 J	0.045 J	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	3.443	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	2.6 J	0.75 J	0.093 J	< 0.008 U	< 0.003 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	0.682	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.034 U	0.5 J	0.16 J	0.022 J	< 0.0084 U	< 0.0032 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	0.618	< U	< U	< U	< U	0.47 J	0.13 J	0.018 J	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	15.16	< 0.058 U	< 0.063 U	< 0.043 U	< 0.034 U	14 J	0.99 J	0.17 J	< 0.062 U	< 0.024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	0.375	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	0.29 J	0.085 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	0.811	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.59 J	0.2 J	0.021 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	0.238	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.18 J	0.058 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	0.198	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.15 J	0.048 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	0.165	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	0.13 J	0.035 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	0.094	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	0.066 J	0.028 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	0.309	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	0.25 J	0.059 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	0.455	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	0.39 J	0.065 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3872	DUP-05	4/20/2021	855.35	34 - 36 ft	180-120434-1	Not Excavated	13.59	< 0.067 U	< 0.073 U	< 0.051 U	< 0.034 U	10 J	2.7 J	0.89 J	< 0.073 U	< 0.028 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-34-36	4/20/2021	855.35	34 - 36 ft	180-120434-1	Not Excavated	41	< 0.13 U	< 0.14 U	< 0.099 U	< 0.034 U	30 J	11 J	< 0.12 UJ	< 0.14 U	< 0.054 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-36-38	4/20/2021	855.35	36 - 38 ft	180-120434-1	Not Excavated	30.94	< 0.07 U	< 0.076 U	< 0.052 U	< 0.034 U	24 J	6 J	0.94 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-38-40	4/20/2021	855.35	38 - 40 ft	180-120434-1	Not Excavated	0.244	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.034 U	0.18 J	0.064 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-40-42	4/20/2021	855.35	40 - 42 ft	180-120434-1	Not Excavated	0.438	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.034 U	0.36 J	0.078 J	< 0.0062 U	< 0.0077 U	< 0.003 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-42-44	4/20/2021	855.35	42 - 44 ft	180-120434-1	Not Excavated	0.61	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.5 J	0.11 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	4.74	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	3.5 J	1.1 J	0.14 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3873	DUP-06	4/19/2021	854.94	18 - 20 ft	180-120434-1	Not Excavated	1.222	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	1 J	0.2 J	0.022 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-18-20	4/19/2021	854.94	18 - 20 ft	180-120434-1	Not Excavated	1.55	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	1.2 J	0.35 J	< 0.0053 UJ	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-20-22	4/19/2021	854.94	20 - 22 ft	180-120434-1	Not Excavated	6.02	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	4.5 J	1.3 J	0.22 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-22-24	4/19/2021	854.94	22 - 24 ft	180-120434-1	Not Excavated	0.34	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	0.27 J	0.07 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	1.885	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	1.4 J	0.43 J	0.055 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-26-28	4/19/2021	854.94	26 - 28 ft	180-120434-1	Not Excavated	0.94	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.72 J	0.22 J		< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-28-30	4/19/2021	854.94	28 - 30 ft	180-120434-1	Not Excavated	0.61	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.48 J	0.13 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-30-32	4/19/2021	854.94	30 - 32 ft	180-120434-1	Not Excavated	0.345	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	0.27 J	0.075 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-32-34	4/19/2021	854.94	32 - 34 ft	180-120434-1	Not Excavated	8.1	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.034 U	6.5 J	1.6 J	< 0.0057 U	< 0.007 U	< 0.0027 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	3.87	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.034 U	3.1 J	0.77 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	0.144	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.034 U	0.11 J	0.034 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	0.42	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.034 U	0.31 J	0.11 J	< 0.0063 U	< 0.0077 U	< 0.003 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	0.029	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.034 U	0.029	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	0.034	< 0.0074 U	< 0.0081 U	< 0.0056 U	< 0.034 U	0.034	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	0.014	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	0.0091	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0091 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	ND	< 0.0074 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0080 U	< 0.0030 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.0030 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-16-18	4/2/2021	854.82	16 - 18 ft	180-119462-1	Not Excavated	0.02	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.02	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-18-20	4/2/2021	854.82	18 - 20 ft	180-119462-1	Not Excavated	0.025	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.025	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-20-22	4/2/2021	854.82	20 - 22 ft	180-119462-1	Not Excavated	0.02	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.02	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-22-23	4/2/2021	854.82	22 - 23 ft	180-119462-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-23-24	4/2/2021	854.82	23 - 24 ft	180-119462-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-24-26	4/2/2021	854.82	24 - 26 ft	180-119462-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-26-27	4/2/2021	854.82	26 - 27 ft	180-119462-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3876	DUP-27	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-22-24	4/2/2021	855.09	22 - 24 ft	180-119462-1	Not Excavated	0.279	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.083 J	0.12 J	0.076 J	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-24-26	4/2/2021	855.09	24 - 26 ft	180-119462-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-26-28	4/2/2021	855.09	26 - 28 ft	180-119462-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-28-30	4/2/2021	855.09	28 - 30 ft	180-119462-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-30-32	4/2/2021	855.09	30 - 32 ft	180-119462-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-32-33	4/2/2021	855.09	32 - 33 ft	180-119462-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-33-34	4/2/2021	855.09	33 - 34 ft	180-119462-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-34-36	4/2/2021	855.09	34 - 36 ft	180-119462-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-36-37	4/2/2021	855.09	36 - 37 ft	180-119462-2	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	0.713	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.39 J	0.26 J	0.063 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	0.866	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.59 J	0.23 J	0.046 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	0.07	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.051 J	0.019 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	0.047	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.032 J	0.015 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	0.0305	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.022 J	0.0085 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	0.065	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.052 J	0.013 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	0.018	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	0.018 J	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	0.066	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.053 J	0.013 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	0.043	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.043	< 0.0063 UJ	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	0.028	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.028	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	ND	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-16-18	4/5/2021	854.82	16 - 18 ft	180-119510-1	Not Excavated	0.0293	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.023 J	0.0063 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	0.073	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.058 J	0.015 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	0.053	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.042 J	0.011 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-38-40	4/5/2021	854.82	38 - 40 ft	180-119510-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	0.146	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	0.12 J	0.026 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-42-43	4/5/2021	854.82	42 - 43 ft	180-119510-1	Not Excavated	0.018	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.018 J	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-43-45	4/5/2021	854.82	43 - 45 ft	180-119510-1	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	< 0.0055 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-45-47	4/5/2021	854.82	45 - 47 ft	180-119510-2	Not Excavated	ND	< 0.0077 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	< 0.0057 U	< 0.0071 U	< 0.0067 U	< 0.0083 U	< 0.0032 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	0.076	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.06 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	0.451	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.32 J	0.11 J	0.021 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3880	DUP-07	4/17/2021	855.20	20 - 22 ft	180-120257-1	Not Excavated	0.683	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.62 J	0.063 J	< 0.0052 UJ	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-20-22	4/17/2021	855.20	20 - 22 ft	180-120257-1	Not Excavated	0.608	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.51 J	0.086 J	0.012 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-22-24	4/17/2021	855.20	22 - 24 ft	180-120257-1	Not Excavated	2.081	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.6 J	0.42 J	0.061 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-24-26	4/17/2021	855.20	24 - 26 ft	180-120257-1	Not Excavated	1.09	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.96 J	0.13 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-26-28	4/17/2021	855.20	26 - 28 ft	180-120257-1	Not Excavated	0.121	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.092 J	0.029 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-28-30	4/17/2021	855.20	28 - 30 ft	180-120257-1	Not Excavated	0.06	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	0.046 J	0.014 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-30-32	4/17/2021	855.20	30 - 32 ft	180-120257-1	Not Excavated	0.262	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.21 J	0.052 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-32-34	4/17/2021	855.20	32 - 34 ft	180-120257-1	Not Excavated	0.15	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.15	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-34-36	4/17/2021	855.20	34 - 36 ft	180-120257-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-36-38	4/17/2021	855.20	36 - 38 ft	180-120257-1	Not Excavated	0.021	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.021 J	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.003 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-38-40	4/19/2021	855.20	38 - 40 ft	180-120245-1	Not Excavated	0.16	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.034 U	0.13 J	0.03 J	< 0.0068 U	< 0.0084 U	< 0.0032 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-40-42	4/19/2021	855.20	40 - 42 ft	180-120245-2	Not Excavated	0.064	< U	< U	< U	< U	0.051 J	0.013 J	< U	< U	< U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	2.295	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.6 J	0.65 J	0.045 J	< 0.0067 U	< 0.0026 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	0.04	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.04	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	0.07	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.044 J	0.026 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-22-24	4/18/2021	855.29	22 - 24 ft	180-120245-1	Not Excavated	0.277	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.2 J	0.077 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-24-26	4/18/2021	855.29	24 - 26 ft	180-120245-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-26-28	4/18/2021	855.29	26 - 28 ft	180-120245-1	Not Excavated	0.074	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.074	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3881	DUP-08	4/14/2021	855.29	28 - 30 ft	180-120028-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3881	DUP-08	4/18/2021	855.29	28 - 30 ft	180-120245-1	Not Excavated	0.089	< 0.0073 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	0.071 J	0.018 J	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-28-30	4/18/2021	855.29	28 - 30 ft	180-120245-1	Not Excavated	0.086	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.086	< 0.006 UJ	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-30-32	4/18/2021	855.29	30 - 32 ft	180-120245-1	Not Excavated	0.246	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.22 J	0.026 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-32-34	4/18/2021	855.29	32 - 34 ft	180-120245-1	Not Excavated	0.365	< 0.0073 U	< 0.0079 U	< 0.0055 U	< 0.0033 U	0.3 J	0.065 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-34-35	4/18/2021	855.29	34 - 35 ft	180-120245-1	Not Excavated	0.179	< 0.0074 U	< 0.0081 U	< 0.0055 U	< 0.0033 U	0.13 J	0.049 J	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-35-37	4/18/2021	855.29	35 - 36 ft	180-120245-1	Not Excavated	0.103	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.084 J	0.019 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-37-39	4/18/2021	855.29	37 - 39 ft	180-120245-2	Not Excavated	0.03	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.03	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0060 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	0.039	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.039	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	0.018	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.018	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	0.037	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.037	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	0.026	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.026	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	0.01	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.01 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-16-18	5/11/2021	853.49	16 - 18 ft	180-121474-1	Not Excavated	32.1	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	27 J	5.1 J	< 0.054 U	< 0.067 U	< 0.025 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-18-20	5/11/2021	853.49	18 - 20 ft	180-121474-1	Not Excavated	1.48	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.2 J	0.28 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-20-22	5/11/2021	853.49	20 - 22 ft	180-121474-1	Not Excavated	0.47	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.36 J	0.11 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-22-24	5/11/2021	853.49	22 - 24 ft	180-121474-1	Not Excavated	2.27	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.9 J	0.37 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-24-25	5/11/2021	853.49	24 - 25 ft	180-121474-1	Not Excavated	1.52	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	1.3 J	0.22 J	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-25-27	5/11/2021	853.49	25 - 27 ft	180-121474-1	Not Excavated	0.119	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	0.1 J	0.019 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-16-18	9/22/2021	854.12	16 - 18 ft	180-127488-1	Not Excavated	0.01	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-18-20	9/22/2021	854.12	18 - 20 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-20-22	11/1/2021	854.12	20 - 22 ft	180-129378-1	Not Excavated	0.08	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.054 J	0.026 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-22-24	9/22/2021	854.12	22 - 24 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-24-25	9/22/2021	854.12	24 - 25 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-25-27	9/22/2021	854.12	25 - 27 ft	180-127488-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-27-29	9/22/2021	854.12	27 - 29 ft	180-127488-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-16-18	5/19/2021	854.47	16 - 18 ft	180-121903-1	Not Excavated	0.31	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.31	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-18-20	5/19/2021	854.47	18 - 20 ft	180-121903-1	Not Excavated	0.14	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-20-22	5/19/2021	854.47	20 - 22 ft	180-121903-1	Not Excavated	0.077	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.077	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-22-24	5/19/2021	854.47	22 - 24 ft	180-121903-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-24-26	5/19/2021	854.47	24 - 26 ft	180-121903-1	Not Excavated	0.017	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.017 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-26-28	5/19/2021	854.47	26 - 28 ft	180-121903-1	Not Excavated	0.01	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.01 J	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-16-18	5/15/2021	855.62	16 - 18 ft	180-121747-1	Not Excavated	0.0091	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0091 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-18-20	5/15/2021	855.62	18 - 20 ft	180-121747-1	Not Excavated	0.029	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.029	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-20-22	5/15/2021	855.62	20 - 22 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-22-24	5/15/2021	855.62	22 - 24 ft	180-121747-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-24-26	5/15/2021	855.62	24 - 26 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-26-28	5/16/2021	855.62	26 - 28 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-28-30	5/16/2021	855.62	28 - 30 ft	180-121747-1	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-16-18	5/14/2021	855.59	16 - 18 ft	180-121705-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-18-20	5/14/2021	855.59	18 - 20 ft	180-121705-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-20-22	5/14/2021	855.59	20 - 22 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-22-24	5/14/2021	855.59	22 - 24 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-24-26	5/14/2021	855.59	24 - 26 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-26-27	5/14/2021	855.59	26 - 27 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-27-29	5/14/2021	855.59	27 - 29 ft	180-121705-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated	0.0095	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0095 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated	0.092	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.076 J	0.016 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated	0.013	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.013 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-16-18	5/12/2021	856.79	16 - 18 ft	180-121548-1	Not Excavated	0.014	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-18-20	5/12/2021	856.79	18 - 20 ft	180-121548-1	Not Excavated	0.015	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.015 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-20-22	5/12/2021	856.79	20 - 22 ft	180-121548-1	Not Excavated	0.051	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.051	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-22-24	5/12/2021	856.79	22 - 24 ft	180-121548-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-24-26	5/12/2021	856.79	24 - 26 ft	180-121548-1	Not Excavated	0.015	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.015 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-26-28	5/12/2021	856.79	26 - 28 ft	180-121548-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-28-30	5/12/2021	856.79	28 - 30 ft	180-121548-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-30-32	5/12/2021	856.79	30 - 32 ft	180-121548-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-32-34	5/12/2021	856.79	32 - 34 ft	180-121548-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	0.108	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.084	0.024	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	0.014	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.014 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	0.013	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.013 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	0.22	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.16	0.06	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-16-18	5/14/2021	856.33	16 - 18 ft	180-121705-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 UJ	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-18-20	5/14/2021	856.33	18 - 20 ft	180-121705-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-20-22	5/14/2021	856.33	20 - 22 ft	180-121705-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-22-24	5/14/2021	856.33	22 - 24 ft	180-121705-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-24-26	5/14/2021	856.33	24 - 26 ft	180-121705-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-26-28	5/14/2021	856.33	26 - 28 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-28-30	5/14/2021	856.33	28 - 30 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-30-31	5/14/2021	856.33	30 - 31 ft	180-121705-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-31-33	5/14/2021	856.33	31 - 33 ft	180-121705-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-16-18	5/13/2021	856.49	16 - 18 ft	180-121704-1	Not Excavated	0.032	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.032	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-18-20	5/13/2021	856.49	18 - 20 ft	180-121704-1	Not Excavated	0.039	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.039	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-20-22	5/13/2021	856.49	20 - 22 ft	180-121704-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-22-24	5/13/2021	856.49	22 - 24 ft	180-121704-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-24-26	5/13/2021	856.49	24 - 26 ft	180-121704-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-26-28	5/13/2021	856.49	26 - 28 ft	180-121704-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-28-30	5/13/2021	856.49	28 - 30 ft	180-121704-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-16-18	5/11/2021	852.98	16 - 18 ft	180-121474-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-18-20	5/11/2021	852.98	18 - 20 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-20-22	5/11/2021	852.98	20 - 22 ft	180-121474-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-22-24	5/11/2021	852.98	22 - 24 ft	180-121474-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-24-25	5/11/2021	852.98	24 - 25 ft	180-121474-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-25-27	5/11/2021	852.98	25 - 27 ft	180-121474-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	0.0086	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0086 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	0.0094	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0094 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-16-18	5/15/2021	854.53	16 - 18 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-18-20	5/15/2021	854.53	18 - 20 ft	180-121747-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-20-22	5/15/2021	854.53	20 - 22 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-22-23	5/15/2021	854.53	22 - 23 ft	180-121747-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-23-25	5/15/2021	854.53	23 - 25 ft	180-121747-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-16-18	5/16/2021	855.21	16 - 18 ft	180-121747-1	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-18-20	5/16/2021	855.21	18 - 20 ft	180-121747-1	Not Excavated	0.015	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.015 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-20-22	5/16/2021	855.21	20 - 22 ft	180-121747-1	Not Excavated	0.0098	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0098 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-22-23	5/16/2021	855.21	22 - 23 ft	180-121747-1	Not Excavated	0.016	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.016 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-23-25	5/16/2021	855.21	23 - 25 ft	180-121747-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-16-18	5/18/2021	856.45	16 - 18 ft	180-121822-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-18-20	5/18/2021	856.45	18 - 20 ft	180-121822-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-20-22	5/18/2021	856.45	20 - 22 ft	180-121822-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-22-24	5/18/2021	856.45	22 - 24 ft	180-121822-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-24-26	5/18/2021	856.45	24 - 26 ft	180-121822-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-26-28	5/18/2021	856.45	26 - 28 ft	180-121822-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	0.047	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.047	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	0.017	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.017 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	0.041	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.041	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	0.012	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.012 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	ND	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.0070 U	< 0.0066 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-16-18	5/14/2021	856.30	16 - 18 ft	180-121705-1	Not Excavated	0.034	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.034	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-18-20	5/14/2021	856.30	18 - 20 ft	180-121705-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-20-22	5/14/2021	856.30	20 - 22 ft	180-121705-1	Not Excavated	0.0098	< 0.0058 UJ	< 0.0063 UJ	< 0.0043 UJ	< 0.0026 UJ	0.0098 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-22-24	5/14/2021	856.30	22 - 24 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-24-25	5/14/2021	856.30	24 - 25 ft	180-121705-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-25-27	5/14/2021	856.30	25 - 27 ft	180-121705-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-16-18	5/13/2021	857.53	16 - 18 ft	180-121704-1	Not Excavated	0.101	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.077 J	0.024 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-18-20	5/13/2021	857.53	18 - 20 ft	180-121704-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-20-22	5/13/2021	857.53	20 - 22 ft	180-121704-1	Not Excavated	0.069	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.053 J	0.016 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-22-24	5/13/2021	857.53	22 - 24 ft	180-121704-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-24-26	5/13/2021	857.53	24 - 26 ft	180-121704-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-16-18	5/12/2021	856.44	16 - 18 ft	180-121548-2	Not Excavated	0.033	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.033	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-18-20	5/12/2021	856.44	18 - 20 ft	180-121548-2	Not Excavated	0.049	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.038 J	0.011 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-20-22	5/12/2021	856.44	20 - 22 ft	180-121548-2	Not Excavated	0.111	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.085 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-22-24	5/12/2021	856.44	22 - 24 ft	180-121548-2	Not Excavated	0.049	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.037 J	0.012 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-24-26	5/12/2021	856.44	24 - 26 ft	180-121548-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-26-28	5/12/2021	856.44	26 - 28 ft	180-121548-2	Not Excavated	0.073	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.058 J	0.015 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-28-30	5/12/2021	856.44	28 - 30 ft	180-121548-2	Not Excavated	0.034	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.034	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-30-32	5/12/2021	856.44	30 - 32 ft	180-121548-2	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18	5/19/2021	856.98	16 - 18 ft	1801219031	Not Excavated	0.011	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.011 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-18-20	5/19/2021	856.98	18 - 20 ft	1801219031	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-20-22	5/19/2021	856.98	20 - 22 ft	1801219031	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-22-24	5/19/2021	856.98	22 - 24 ft	1801219031	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-24-26	5/19/2021	856.98	24 - 26 ft	1801219031	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-26-28	5/19/2021	856.98	26 - 28 ft	1801219031	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-28-30	5/19/2021	856.98	28 - 30 ft	1801219031	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-30-31	5/19/2021	856.98	30 - 31 ft	1801219031	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	ND	< 0.0067 UT	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 UT	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-16-18	5/7/2021	857.27	16 - 18 ft	180-121355-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-18-20	5/7/2021	857.27	18 - 20 ft	180-121355-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-20-22	5/7/2021	857.27	20 - 22 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-22-24	5/7/2021	857.27	22 - 24 ft	180-121355-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-24-26	5/7/2021	857.27	24 - 26 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-26-28	5/7/2021	857.27	26 - 28 ft	180-121355-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-28-30	5/7/2021	857.27	28 - 30 ft	180-121355-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-30-32	5/7/2021	857.27	30 - 32 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-32-33	5/7/2021	857.27	32 - 33 ft	180-121355-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-33-35	5/7/2021	857.27	33 - 35 ft	180-121355-1	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-16-18	5/10/2021	856.83	16 - 18 ft	180-121424-1	Not Excavated	0.577	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.43 J	0.12 J	0.027 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-18-20	5/10/2021	856.83	18 - 20 ft	180-121424-1	Not Excavated	0.075	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.057 J	0.018 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-20-22	5/10/2021	856.83	20 - 22 ft	180-121424-1	Not Excavated	0.702	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.51 J	0.16 J	0.032 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-22-24	5/10/2021	856.83	22 - 24 ft	180-121424-1	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.037	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-24-26	5/10/2021	856.83	24 - 26 ft	180-121424-1	Not Excavated	0.111	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.087 J	0.024 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-26-28	5/10/2021	856.83	26 - 28 ft	180-121424-1	Not Excavated	0.12	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.095 J	0.025 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-28-30	5/10/2021	856.83	28 - 30 ft	180-121424-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-30-32	5/10/2021	856.83	30 - 32 ft	180-121424-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U		< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-32-34	5/10/2021	856.83	32 - 34 ft	180-121424-1	Not Excavated	0.176	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.14 J	0.036 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-34-36	5/10/2021	856.83	34 - 36 ft	180-121424-1	Not Excavated	0.028	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.028	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-36-38	5/10/2021	856.83	36 - 38 ft	180-121424-1	Not Excavated	0.026	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.026	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-16-18	5/10/2021	856.60	16 - 18 ft	180-121424-1	Not Excavated	0.562	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.43 J	0.11 J	0.022 J	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-18-20	5/10/2021	856.60	18 - 20 ft	180-121424-1	Not Excavated	0.08	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.065 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-20-22	5/10/2021	856.60	20 - 22 ft	180-121424-1	Not Excavated	0.122	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.1 J	0.022 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-22-24	5/10/2021	856.60	22 - 24 ft	180-121424-1	Not Excavated	0.07	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056 J	0.014 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-24-26	5/10/2021	856.60	24 - 26 ft	180-121424-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-26-28	5/11/2021	856.60	26 - 28 ft	180-121474-1	Not Excavated	0.146	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.12 J	0.026 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-28-30	5/11/2021	856.60	28 - 30 ft	180-121474-1	Not Excavated	0.023	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.023	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-30-32	5/11/2021	856.60	30 - 32 ft	180-121474-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-32-34	5/11/2021	856.60	32 - 34 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-34-36	5/11/2021	856.60	34 - 36 ft	180-121474-1	Not Excavated	0.012	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.012 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-36-38	5/11/2021	856.60	36 - 38 ft	180-121474-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-38-40	5/11/2021	856.60	38 - 40 ft	180-121474-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-40-41	5/11/2021	856.60	40 - 41 ft	180-121474-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-41-43	5/11/2021	856.60	41 - 43 ft	180-121474-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-16-18	5/11/2021	856.72	16 - 18 ft	180-121474-1	Not Excavated	0.076	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.05 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-18-20	5/11/2021	856.72	18 - 20 ft	180-121474-1	Not Excavated	0.019	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.019	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-20-22	5/11/2021	856.72	20 - 22 ft	180-121474-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.012 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-22-24	5/11/2021	856.72	22 - 24 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-24-26	5/12/2021	856.72	24 - 26 ft	180-121548-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-26-28	5/12/2021	856.72	26 - 28 ft	180-121548-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-28-29	5/12/2021	856.72	28 - 29 ft	180-121548-1	Not Excavated	0.029	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.029	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-29-31	5/12/2021	856.72	29 - 31 ft	180-121548-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-16-18	5/7/2021	857.06	16 - 18 ft	180-121355-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-18-20	5/7/2021	857.06	18 - 20 ft	180-121355-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-20-22	5/7/2021	857.06	20 - 22 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-22-24	5/7/2021	857.06	22 - 24 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-24-26	5/7/2021	857.06	24 - 26 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-26-28	5/7/2021	857.06	26 - 28 ft	180-121355-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-28-30	5/7/2021	857.06	28 - 30 ft	180-121355-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-30-32	5/7/2021	857.06	30 - 32 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-32-34	5/7/2021	857.06	32 - 34 ft	180-121355-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-16-18	6/10/2021	856.20	16 - 18 ft	180-123098-2	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.014 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-18-20	6/10/2021	856.20	18 - 20 ft	180-123098-2	Not Excavated	0.111	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.078 J	0.033 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-20-22	6/10/2021	856.20	20 - 22 ft	180-123098-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-22-24	6/10/2021	856.20	22 - 24 ft	180-123098-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-24-26	6/10/2021	856.20	24 - 26 ft	180-123098-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-26-28	6/10/2021	856.20	26 - 28 ft	180-123098-2	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-16-18	6/11/2021	855.61	16 - 18 ft	180-123134-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-18-20	6/11/2021	855.61	18 - 20 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-20-22	6/11/2021	855.61	20 - 22 ft	180-123134-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-22-24	6/11/2021	855.61	22 - 24 ft	180-123134-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-24-26	6/11/2021	855.61	24 - 26 ft	180-123134-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-26-28	6/11/2021	855.61	26 - 28 ft	180-123134-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-28-30	6/11/2021	855.61	28 - 30 ft	180-123134-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-16-18	5/15/2021	855.68	16 - 18 ft	180-121747-1	Not Excavated	0.011	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-18-20	5/15/2021	855.68	18 - 20 ft	180-121747-1	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-20-22	5/15/2021	855.68	20 - 22 ft	180-121747-1	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.014 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-22-24	5/15/2021	855.68	22 - 24 ft	180-121747-1	Not Excavated	0.061	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.05 J	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-24-25	5/15/2021	855.68	24 - 25 ft	180-121747-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-25-27	5/15/2021	855.68	25 - 27 ft	180-121747-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-16-18	6/11/2021	855.12	16 - 18 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-18-20	6/11/2021	855.12	18 - 20 ft	180-123134-1	Not Excavated	0.082	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.06 J	0.022 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-20-22	6/11/2021	855.12	20 - 22 ft	180-123134-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-22-24	6/11/2021	855.12	22 - 24 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-24-26	6/11/2021	855.12	24 - 26 ft	180-123134-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-26-28	6/11/2021	855.12	26 - 28 ft	180-123134-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	0.011	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	0.022	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.022	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	0.018	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.018 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-16-18	5/12/2021	852.53	16 - 18 ft	180-121548-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-18-20	5/12/2021	852.53	18 - 20 ft	180-121548-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-20-22	5/12/2021	852.53	20 - 22 ft	180-121548-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-22-24	5/12/2021	852.53	22 - 24 ft	180-121548-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-24-26	5/12/2021	852.53	24 - 26 ft	180-121548-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-26-28	5/12/2021	852.53	26 - 28 ft	180-121548-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-28-30	5/12/2021	852.53	28 - 30 ft	180-121548-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-16-18	5/13/2021	853.71	16 - 18 ft	1801217042	Not Excavated	1.21	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.92	0.26	0.03	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-18-20	5/13/2021	853.71	18 - 20 ft	1801217044	Not Excavated	0.111	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.083	0.028	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-16-18	5/16/2021	852.79	16 - 18 ft	180-121747-1	Not Excavated	0.21	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.21	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-18-20	5/16/2021	852.79	18 - 20 ft	180-121747-1	Not Excavated	0.12	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.12	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-20-22	5/16/2021	852.79	20 - 22 ft	180-121747-1	Not Excavated	0.013	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.013 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-22-24	5/16/2021	852.79	22 - 24 ft	180-121747-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-24-26	5/16/2021	852.79	24 - 26 ft	180-121747-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-16-18	7/1/2021	853.40	16 - 18 ft	180-123985-1	Not Excavated	3.3	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	3.3	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-18-20	7/1/2021	853.40	18 - 20 ft	180-123985-1	Not Excavated	7.2	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	7.2	< 0.055 U	< 0.052 U	< 0.065 U	< 0.025 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-20-22	7/1/2021	853.40	20 - 22 ft	180-123985-1	Not Excavated	0.034	< 0.0064 UJ	< 0.007 UJ	< 0.0048 UJ	< 0.0029 UJ	0.034 J	< 0.0059 UJ	< 0.0056 UJ	< 0.0069 UJ	< 0.0027 UJ
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-22-24	7/1/2021	853.40	22 - 24 ft	180-123985-1	Not Excavated	0.224	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.19 J	0.034 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	2430	< 6 U	< 6.6 U	< 4.5 U	< 2.7 U	1700 J	730 J	< 5.3 U	< 6.5 U	< 2.5 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	930	< 6.5 U	< 7.1 U	< 4.9 U	< 2.9 U	650 J	280 J	< 5.7 U	< 7.1 U	< 2.7 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	176.6	< 0.64 U	< 0.7 U	< 0.48 U	< 0.29 U	120 J	53 J	3.6 J	< 0.69 U	< 0.26 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	12.9	< 0.068 U	< 0.075 U	< 0.051 U	< 0.031 U	9.9 J	2.7 J	0.3 J	< 0.074 U	< 0.028 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-16-18	6/18/2021	854.11	16 - 18 ft	180-123449-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-18-20	6/18/2021	854.11	18 - 20 ft	180-123449-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-16-18	6/18/2021	854.03	16 - 18 ft	180-123449-1	Not Excavated	0.032	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.032 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-18-20	6/18/2021	854.03	18 - 20 ft	180-123449-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-16-18	6/18/2021	853.31	16 - 18 ft	180-123449-1	Not Excavated	2.7	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.7 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-18-20	6/18/2021	853.31	18 - 20 ft	180-123449-1	Not Excavated	1.3	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.3 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-20-22	6/18/2021	853.31	20 - 22 ft	180-123449-2	Not Excavated	0.265	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.23 J	0.035 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3925A	SSHS-B3925A-SUB-16-18	7/26/2021	853.31	16 - 18 ft	180-124973-1	Not Excavated	2.57	< 0.0068 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	2.3 J	0.27 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-16-18	6/18/2021	853.29	16 - 18 ft	180-123449-1	Not Excavated	1.4	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.4 J	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-18-20	6/18/2021	853.29	18 - 20 ft	180-123449-1	Not Excavated	0.35	< 0.0061 U	< 0.0066 U	< 0.0045 U	0.35 J	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-16-18	6/18/2021	853.07	16 - 18 ft	180-123449-2	Not Excavated	0.0233	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.015 J	0.0083 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-16-18	6/18/2021	854.16	16 - 18 ft	180-123449-2	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-16-18	5/20/2021	855.17	16 - 18 ft	180-121981-1	Not Excavated	0.682	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	0.44 J	0.2 J	0.042 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4009	DUP-200	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	0.358	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.28 J	0.078 J	< 0.0059 UJ	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-24-26	5/20/2021	855.17	24 - 26 ft	180-121981-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-26-28	5/20/2021	855.17	26 - 28 ft	180-121981-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-28-30	5/20/2021	855.17	28 - 30 ft	180-121981-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-30-32	5/20/2021	855.17	30 - 32 ft	180-121981-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-34-36	5/20/2021	855.17	34 - 36 ft	180-121981-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.034 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-36-38	5/20/2021	855.17	36 - 38 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-38-40	5/20/2021	855.17	38 - 40 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-40-42	5/20/2021	855.17	40 - 42 ft	180-121981-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.034 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	0.053	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	0.033 J	0.02 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
							Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted							0.1									
Restricted - Residential							1									
Protection of Groundwater							3.2									
NYS Hazardous Waste							50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4010	DUP-201	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	0.093	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	0.068 J	0.025 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-28-30	5/20/2021	855.47	28 - 30 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-30-32	5/20/2021	855.47	30 - 32 ft	180-121981-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-32-33	5/20/2021	855.47	32 - 33 ft	180-121981-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-37-39	5/20/2021	855.47	37 - 39 ft	180-121981-1	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.008 U	< 0.003 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-39-41	5/20/2021	855.47	39 - 41 ft	180-121981-1	Not Excavated	ND	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-16-18	5/19/2021	855.31	16 - 18 ft	180-121899-1	Not Excavated	0.072	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.052 J	0.02 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	0.022	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	0.022	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-20-22	5/19/2021	855.31	20 - 22 ft	180-121899-1	Not Excavated	0.031	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.031	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-22-24	5/19/2021	855.31	22 - 24 ft	180-121899-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-24-26	5/19/2021	855.31	24 - 26 ft	180-121899-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B4011	DUP-203	5/19/2021	855.31	26 - 28 ft	180-121899-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-26-28	5/19/2021	855.31	26 - 28 ft	180-121899-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4011	DUP-204	5/19/2021	855.31	28 - 30 ft	180-121899-1	Not Excavated	0.022	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.034 U	0.022 J	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-28-30	5/19/2021	855.31	28 - 30 ft	180-121899-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	< 0.0049 UJ	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-30-32	5/20/2021	855.31	30 - 32 ft	180-121981-1	Not Excavated	2.35	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	1.6 J	0.65 J	0.1 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-32-34	5/20/2021	855.31	32 - 34 ft	180-121981-1	Not Excavated	88.1	< 0.14 U	< 0.16 U	< 0.11 U	< 0.034 U	55 J	27 J	6.1 J	< 0.16 U	< 0.059 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-34-36	5/20/2021	855.31	34 - 36 ft	180-121981-1	Not Excavated	0.221	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.034 U	0.16 J	0.061 J	< 0.0066 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-36-38	5/20/2021	855.31	36 - 38 ft	180-121981-1	Not Excavated	0.105	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.077 J	0.028 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-30-32	5/21/2021	855.04	30 - 32 ft	180-122085-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4012	DUP-205	5/21/2021	855.04	32 - 34 ft	180-122085-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.034 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-32-34	5/21/2021	855.04	32 - 34 ft	180-122085-1	Not Excavated	ND	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	0.015	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0055 UJ	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	0.065	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.051 J	0.014 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-18-20	5/19/2021	855.81	18 - 20 ft	180-121899-1	Not Excavated	0.05	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.039 J	0.011 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-28-30	5/19/2021	855.81	28 - 30 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4013	SSHS-B4013-SUB-30-32	5/19/2021	855.81	30 - 32 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4013	SSHS-B4013-SUB-32-34	5/19/2021	855.81	32 - 34 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4013	SSHS-B4013-SUB-34-36	5/19/2021	855.81	34 - 36 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	0.06	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.037 J	0.023 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	0.0072	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.0072 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-20-22	6/30/2021	855.88	20 - 22 ft	180-123901-2	Not Excavated	0.036	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.026 J	0.01 J	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-22-24	6/30/2021	855.88	22 - 24 ft	180-123901-2	Not Excavated	0.402	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.29 J	0.089 J	0.023 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	0.0083	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	0.0083 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-26-28	6/30/2021	855.88	26 - 28 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-28-30	6/30/2021	855.88	28 - 30 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-30-32	6/30/2021	855.88	30 - 32 ft	180-123901-2	Not Excavated	0.016	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.016 J	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-32-34	6/30/2021	855.88	32 - 34 ft	180-123901-2	Not Excavated	ND	< 0.034 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0062 U	< 0.034 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-34-36	6/30/2021	855.88	34 - 36 ft	180-123901-2	Not Excavated	ND	< 0.0077 U	< 0.0084 U	< 0.0058 U	< 0.034 U	< 0.0057 U	< 0.0071 U	< 0.0067 U	< 0.0083 U	< 0.0032 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-36-38	6/30/2021	855.88	36 - 38 ft	180-123901-2	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.034 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-38-40	6/30/2021	855.88	38 - 40 ft	180-123901-2	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.003 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-40-42	6/30/2021	855.88	40 - 42 ft	180-123901-2	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0055 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	1.43	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	1.1 J	0.33 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	0.023	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.023	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	0.037	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.034 U	0.037	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-16-18	7/26/2021	853.87	16 - 18 ft	180-124973-1	Not Excavated	0.3	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.3	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	ND	< 0.0095 U	< 0.01 U	< 0.0071 U	< 0.034 U	< 0.007 U	< 0.0088 U	< 0.0083 U	< 0.01 U	< 0.0039 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.034 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B4165	DUP-39	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	0.04	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	0.027 J	0.013 J	< 0.0053 U	< 0.0066 U	< 0.0025 U

TABLE 5-7A
Deep Soil Results - Remedial Investigation - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								PCBs								
								Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.1									
Restricted - Residential								1									
Protection of Groundwater								3.2									
NYS Hazardous Waste								50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	0.011	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	0.011 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B451	DUP2102	9/27/2016	854.61	16 - 18 ft	180-59163-1	Not Excavated	ND	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	< 0.0065 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B451	SSHS-B451-SUB-16-18	9/27/2016	854.61	16 - 18 ft	180-59163-1	Not Excavated	ND	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	< 0.0065 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B451	SSHS-B451-SUB-18-20	9/27/2016	854.61	18 - 20 ft	180-59163-1	Not Excavated	ND	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	< 0.0045 U	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	0.017	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.017 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	ND	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	3.23	< 0.041	< 0.065	< 0.023	< 0.033	2.5	0.64	0.09	< 0.028	< 0.017
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-18-20	1/28/2021	852.44	18 - 20 ft	180-116609-1	Not Excavated	0.085	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.061	0.024	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-20-22	2/1/2021	852.44	20 - 22 ft	180-116686-2	Not Excavated	0.111	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.081 J	0.03 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	29.4	< 0.059 U	< 0.065 U	< 0.045 U	< 0.027 U	22 J	6.3 J	1.1 J	< 0.064 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	33.98	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	28 J	5.1 J	0.88 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	6.04	< 0.059 U	< 0.065 U	< 0.045 U	< 0.027 U	4.9 J	0.96 J	0.18 J	< 0.064 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	0.679	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.42 J	0.21 J	0.049 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-22-24	4/18/2021	854.96	22 - 24 ft	180-120245-1	Not Excavated	100.3	< 0.68 U	< 0.74 U	< 0.51 U	< 0.31 U	80 J	17 J	3.3 J	< 0.73 U	< 0.28 U
Football Field	SSHS-B645A	DUP-02	4/18/2021	854.96	24 - 26 ft	180-120245-1	Not Excavated	823	< 3.2 U	< 3.5 U	< 2.4 U	< 1.4 U	590 J	200 J	33 J	< 3.5 U	< 1.3 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-24-26	4/18/2021	854.96	24 - 26 ft	180-120245-1	Not Excavated	715	< 3 U	< 3.3 U	< 2.3 U	< 1.4 U	570 J	120 J	25 J	< 3.3 U	< 1.3 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-26-28	4/18/2021	854.96	26 - 28 ft	180-120245-1	Not Excavated	22.6	< 0.07 U	< 0.076 U	< 0.053 U	< 0.032 U	18 J	3.9 J	0.7 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-28-30	4/18/2021	854.96	28 - 30 ft	180-120245-1	Not Excavated	3.92	< 0.065 U	< 0.071 U	< 0.049 U	< 0.029 U	3.3 J	0.62 J	< 0.057 U	< 0.071 U	< 0.027 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-32-34	4/18/2021	854.96	32 - 34 ft	180-120245-1	Not Excavated	27.77	< 0.064 U	< 0.07 U	< 0.048 U	< 0.029 U	21 J	6 J	0.77 J	< 0.07 U	< 0.027 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-34-36	4/18/2021	854.96	34 - 36 ft	180-120245-1	Not Excavated	513	< 3.4 U	< 3.7 U	< 2.5 U	< 1.5 U	420 J	79 J	14 J	< 3.7 U	< 1.4 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-36-38	4/18/2021	854.96	36 - 38 ft	180-120245-1	Not Excavated	18.19	< 0.068 U	< 0.074 U	< 0.051 U	< 0.031 U	15 J	2.7 J	0.49 J	< 0.074 U	< 0.028 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-38-40	4/18/2021	854.96	38 - 40 ft	180-120245-1	Not Excavated	14.48	< 0.07 U	< 0.076 U	< 0.052 U	< 0.031 U	12 J	2.1 J	0.38 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-40-42	4/18/2021	854.96	40 - 42 ft	180-120245-2	Not Excavated	4.1	< 0.07 U	< 0.076 U	< 0.052 U	< 0.032 U	3.4 J	0.55 J	0.15 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B723	SSHS-B723-SUB-16-18	4/13/2017	856.74	16 - 18 ft	180-65226-1	Not Excavated	16.7	< 0.096 U	< 0.093 U	< 0.071 U	< 0.14 U	11	4.7	1	< 0.13 U	< 0.055 U
Football Field	SSHS-B723	SSHS-B723-SUB-18-20	4/13/2017	856.74	18 - 20 ft	180-65226-1	Not Excavated	0.263	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.19	0.06	0.013 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated	ND	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U		
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		

DRAFT

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	5200	< 0.18 U	11	46	0.19 J	0.063 J	10000	7.4		3.8	15	15000	6.4	1800	270
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	3800	< 0.32 U	7.0	27	0.17 J	< 0.077 U	940	7.0		4.1 J	16	11000	11	1400	200
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-836-834	8/12/2024	852.03	16.03-18.03 ft	1801782961	Not Excavated	5600	< 0.42 U	5.6	55	0.28 J	0.17 J	2000	8.4		5.4	22	15000	7.9	2000	690
Rear Parking Lot	SPA4-B5507	SSHS-SPA4-B5507-ELEV-834-832	8/13/2024	850.07	16.07-18.07 ft	1801783741	Not Excavated	5500	< 0.42 UT	8.0	65	0.17 J	0.075 J	890	12		3.3	27	23000	7.1	2000	350 T
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	4800	0.41 J	3.0	34	0.16 J	0.12 J	30000	9.7		4.2 J	14	12000	3.5	4800	510
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	5100	< 0.41 U	5.5	36	0.24 J	0.097 J	37000	7.5		4.9 J	17	13000	6.7	6500	360
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-16-18	8/30/2019	858.28	16 - 18 ft	180-95047-2	Not Excavated	5000	< 0.36 U	4.1	63	0.19 J	0.091 J	85000	6.1		4.5 J	15	12000	4	12000	390
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	3100	< 0.43 U	3.2	46	0.14 J	0.073 J	40000	5.2		3.2 J	12	8700	4.9	3400	300
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	4200	< 0.35 U	4.6	26	0.17 J	0.097 J	30000	6.9		4.0 J	19	11000	7.4	7000	250
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	6300	< 0.39 U	4.7	48	0.22 J	0.15 J	32000	9.4		5.9	22	17000	6.8	7100	410
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	6300	< 0.37 U	4.1	36	0.23 J	0.16 J	63000	9.7		5.4 J	22	14000	5.9	5200	310
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	4700	< 0.36 U	3.6	34	0.18 J	0.10 J	33000	7.2		4.0 J	19	12000	6.7	3100	240
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	5200	< 0.37 U	3.9	31	0.19 J	0.11 J	20000 J	9.3		5 J	19	14000	7	6100	460
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	4200	< 0.36 U	3.9	24	0.18 J	0.16 J	41000 J	9.2		4 J	16	11000	8.3	10000	620
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	3000	< 0.38 U	2.3	20 J	0.12 J	0.13 J	99000	4.9		2.7 J	15	8000	8.6	44000	760
Football Field	SSHS-B3555	SSHS-B3555-SUB-20-22	1/11/2021	855.30	20 - 22 ft	180-115815-1	Not Excavated	5000	< 0.37 U	6.4	31	0.18 J	0.12 J	52000	7.7		4.7 J	25	13000	5.8	8500	640
Football Field	SSHS-B3555	SSHS-B3555-SUB-22-24	1/11/2021	855.30	22 - 24 ft	180-115815-1	Not Excavated	7700	< 0.36 U	5.8	45	0.28 J	0.13 J	31000	13		7.2	33	18000	9.5	9400	410
Football Field	SSHS-B3556	DUP-22	1/13/2021	855.33	16 - 18 ft	180-115925-1	Not Excavated	5000	< 0.34 U	3.5	37 J	0.24 J	0.088 J	7200	8		4.2 J	18	10000	9.4	2200	200
Football Field	SSHS-B3556	SSHS-B3556-SUB-16-18	1/13/2021	855.33	16 - 18 ft	180-115925-1	Not Excavated	5100	< 0.37 U	4	87 J	0.23 J	0.076 J	5700	7.9		4.2 J	18	12000	12	3200	310
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	7000	< 0.36 U	4.4	29	0.29 J	0.18 J	26000	16		6.6	210	16000	9.2	4400	320
Football Field	SSHS-B3556	SSHS-B3556-SUB-20-22	1/13/2021	855.33	20 - 22 ft	180-115925-1	Not Excavated	5000	< 0.37 U	8	26	0.19 J	0.11 J	33000	7.3		10	16	32000	6.9	16000	950
Football Field	SSHS-B3556	SSHS-B3556-SUB-22-24	1/13/2021	855.33	22 - 24 ft	180-115925-1	Not Excavated	5100	< 0.34 U	3.4	21	0.19 J	0.1 J	35000	6.6		5.5	21	15000	5.8	8600	380
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	4000	< 0.34 U	2.9	26	0.17 J	0.11 J	83000	6.1		3.9 J	14	10000	7	6700	440
Football Field	SSHS-B3557	DUP-23	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	4200	< 0.34 U	3.3	22	0.18 J	0.1 J	19000 J	11		3.8 J	15	11000	9.5	5300 J	460 J
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	4400	< 0.37 U	3.2	30	0.21 J	0.14 J	40000 J	6.6		3.8 J	14	12000	11	9700 J	910 J
Football Field	SSHS-B3557	SSHS-B3557-SUB-20-22	1/11/2021	855.18	20 - 22 ft	180-115815-1	Not Excavated	5200	< 0.34 U	4	31	0.2 J	0.14 J	41000	8		5.2	20	12000	6.7	6300	550
Football Field	SSHS-B3557	SSHS-B3557-SUB-22-24	1/11/2021	855.18	22 - 24 ft	180-115815-1	Not Excavated	6100	< 0.34 U	4.2	37	0.22 J	0.13 J	44000	8.1		5.3	20	13000	6.5	7700	350
Football Field	SSHS-B3558	DUP-24	1/12/2021	855.27	16 - 18 ft	180-115861-2	Not Excavated	3300	< 0.35 U	3.3	20	0.16 J	0.11 J	44000	5.2		3 J	13	8100	9.7	15000	440
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	4000	< 0.36 U	3.8	23	0.17 J	0.11 J	49000	5.1		3.5 J	13	10000	13	14000	620
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	5500	< 0.36 U	5.8	43	0.23 J	0.1 J	31000	6.8		4.9 J	18	13000	7.2	5300	330
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	4000	< 0.36 U	3	24	0.17 J	0.072 J	23000	5.3		3.2 J	11	8400	14	5500	300
Football Field	SSHS-B3558	SSHS-B3558-SUB-22-24	1/12/2021	855.27	22 - 24 ft	180-115861-1	Not Excavated	4300	< 0.37 U	3.4	23	0.17 J	0.15 J	44000	6.6		3.7 J	15	9500	5.3	4900	350
Football Field	SSHS-B3559	DUP-25	1/12/2021	855.35	16 - 18 ft	180-115861-2	Not Excavated	6100	< 0.37 U	4.7	75	0.26 J	0.14 J	40000	10		5.1 J	37	13000	250	10000	560
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	4400	< 0.36 U	3.8	43 J	0.19 J	0.14 J	57000	6.7		4 J	20 J	12000	85 J	16000	730
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	5300	< 0.36 U	4.2	29	0.19 J	0.079 J	30000	6.2		4.3 J	19	13000	8.5	6700	350
Football Field	SSHS-B3559	SSHS-B3559-SUB-20-22	1/12/2021	855.35	20 - 22 ft	180-115861-1	Not Excavated	5100	< 0.34 U	3.5	33	0.19 J	0.089 J	29000	6.6		4 J	22	12000	4.9	4200	270
Football Field	SSHS-B3559	SSHS-B3559-SUB-22-24	1/12/2021	855.35	22 - 24 ft	180-115861-1	Not Excavated	4500	< 0.36 U	4.4	30	0.2 J	0.082 J	35000	6.4		3.8 J	17	12000	6.2	9500	360
Football Field	SSHS-B3560	DUP-26	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	5100	0.75 J	3.7	31	0.18 J	0.1 J	31000	12 J		6.4	21	13000	6.4	6900	350
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	4800	2.9 J	3.8	36	0.18 J	0.087 J	23000	25 J		6.6	30	13000	6.2	6500	300
Football Field	SSHS-B3560	SSHS-B3560-SUB-18-20	1/11/2021	855.32	18 - 20 ft	180-115815-1	Not Excavated	4200	1.2 J-	4.1	25	0.17 J	0.11 J	35000	7		3.7 J	16	9900	6	8800 J-	410
Football Field	SSHS-B3560	SSHS-B3560-SUB-20-22	1/11/2021	855.32	20 - 22 ft	180-115815-1	Not Excavated	5300	< 0.34 U	3.6	28	0.19 J	0.13 J	44000	6.9		4.7 J	18	12000	5.6	4200	230
Football Field	SSHS-B3560	SSHS-B3560-SUB-22-24	1/11/2021	855.32	22 - 24 ft	180-115815-1	Not Excavated	4600	< 0.38 U	3.5	29	0.18 J	0.11 J	49000	7.6		3.9 J	19	12000	5.6	6800	300
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	4900	< 0.38 U	4.9	25	0.21 J	0.12 J	28000	8.2		4.6 J	16	12000	9.2	7500	480
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	5100	< 0.38 UJ	4	33	0.18 J	0.11 J	44000 J	7.9		4.2 J	15	12000	8.9	16000 J	520
Football Field	SSHS-B3561	SSHS-B3561-SUB-20-22	1/13/2021	855.17	20 - 22 ft	180-115925-1	Not Excavated	6700	< 0.37 U	4.2	39	0.2 J	0.1 J	36000	14		6.4	18	16000	8.7	6400	440
Football Field	SSHS-B3561	SSHS-B3561-SUB-22-24	1/13/2021	855.17	22 - 24 ft	180-115925-1	Not Excavated	4900	< 0.35 U	3.5	29	0.19 J	0.16 J	52000	6.9		4.7 J	15	11000	5.7	5800	460
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	5700	< 0.37 U	5.1	44	0.23 J	0.099 J	22000	10		4.8 J	22	13000	120	3800	290
Football Field	SSHS-B3562	SSHS-B3562-SUB-18-20	1/13/2021	855.07	18 - 20 ft	180-115925-1	Not Excavated	5400	< 0.35 U	4.8	31	0.19 J	0.12 J	37000	7.5		5.2	21	13000	7.4	7000	320
Football Field	SSHS-B3562	SSHS-B3562-SUB-20-22	1/13/2021	855.07	20 - 22 ft	180-115925-1	Not Excavated	5100	< 0.35 U	3.8	32	0.17 J	0.08 J	29000	6.9		4.8 J	12	12000	9.3	5700	250
Football Field	SSHS-B3562	SSHS-B3562-SUB-22-24	1/13/2021	855.07	22 - 24 ft	180-115925-1	Not Excavated	6300	< 0.35 U	3.5	39	0.2 J	0.099 J	37000	11		4.7 J	21	14000	6.9	9500	410
Football Field	SSHS-B3563	SSHS-B3563-SUB-22-24	1/11/2021	855.01	22 - 24 ft	180-115815-1	Not Excavated	4200	< 0.34 U	3.7	40	0.17 J	0.1 J	48000	7.3		3.6 J	14	11000	4.9	5900	310
Football Field	SSHS-B3563	SSHS-B3563-SUB-20-22	1/11/2021	855.01	20 - 22 ft	180-115815-1	Not Excavated	6900	< 0.37 U	4.3	39	0.23 J	0.11 J	37000	18		5.8	27	16000	6	6500	460
Football Field	SSHS-B3563	SSHS-B3563-SUB-16-18	1/11/2021	855.01	16 - 18 ft	180-115815-1	Not Excavated	6100	< 0.34 U	4.9	32	0.22 J	0.12 J	29000	9.2		5.5	20	14000	11	8000	380
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	4500	< 0.37 U	3.6	29	0.16 J	0.11 J	38000	7.1		4 J	18	11000	9.1	10000	480
Football Field	SSHS-B3563	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	24 - 26 ft	180-115999-1	Not Excavated	5100	< 0.35 U	3.1	33	0.2 J	0.082 J	32000	6.7		4.6 J	19	12000	4.8	9000	460
Football Field	SSHS-B3563	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	26 - 28 ft	180-115999-1	Not Excavated	5400	< 0.36 U	3.9	43	0.21 J	0.087 J	29000	6.7		5.2	24	12000	3.9	3500	370
Football Field	SSHS-B3563	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	28 - 30 ft	180-115999-1	Not Excavated	4400	< 0.37 U	2.9	35	0.18 J	0.12 J	41000	5.3		4.2 J	15	10000	3.7	4700	400
Football Field	SSHS-B3563	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	34 - 36 ft	180-115999-1	Not Excavated	4700	< 0.44 U	4.3	31	0.23 J	0.083 J	37000	6.9		4.5 J	14	11000	5.5	4300	330
Football Field	SSHS-B3563	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	30 - 32 ft	180-115999-1	Not Excavated	4700	< 0.4 U	3.9	32	0.22 J	0.087 J	36000	6		4.2 J	15	11000	4.9	3700	330
Football Field	SSHS-B3563	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	32 - 34 ft	180-115999-1	Not Excavated	4100	< 0.39 U	4	26	0.21 J	0.067 J	39000	5.5		3.7 J	12	10000	4.5	4300	260
Football Field	SSHS-B3563	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	36 - 37 ft	180-116070-1	Not Excavated	4200	< 0.41 U	5.3	26	0.21 J	0.13 J	37000	6.7		4.3 J	15	13000	6.2	6400	280
Football Field	SSHS-B3564	SSHS-B3564-SUB-16-18	1/12/2021	855.22	16 - 18 ft	180-115861-1	Not Excavated	5700	< 0.36 U	4.6	34	0.24 J	0.13 J	28000	9		5 J	29	13000	10	10000	310
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	4600	< 0.35 U	3.2	33	0.19 J	0.096 J	37000	5.8		4 J	14	11000	6.9	14000	410
Football Field	SSHS-B3564	SSHS-B3564-SUB-20-22	1/12/2021	855.22	20 - 22 ft	180-115861-1	Not Excavated	4900	< 0.38 U	4.2	32	0.19 J	0.079 J	29000	7.4		4.9 J	16	12000	8.4	3600	300
Football Field	SSHS-B3564	SSHS-B3564-SUB-22-24	1/12/2021	855.22	22 - 24 ft	180-115861-1	Not Excavated	5800	< 0.37 U	4.1	32	0.21 J	0.098 J	32000	9.2		5 J	20	14000	5.6	4400	260
Football Field	SSHS-B3564	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	24 - 26 ft	180-116070-1	Not Excavated	5300	< 0.38 U	4.3	44	0.29 J	0.15 J	85000	28		4.7 J	18	14000	17	6000	510
Football Field	SSHS-B3564	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	36 - 37 ft	180-116070-1	Not Excavated	5000	< 0.41 U	5.7	32	0.24 J	0.097 J	42000	7.1		5 J	15	13000	6.5	6500	310
Football Field	SSHS-B3564	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	32 - 34 ft	180-116070-1	Not Excavated	5300	< 0.39 U	4.6	33	0.25 J	0.1 J	40000	7.1		5 J	16	13000	6	5900	310
Football Field	SSHS-B3564	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	26 - 28 ft	180-116070-1	Not Excavated	4200	< 0.34 U	4.4	29	0.16 J	0.13 J	58000	5.5		4.2 J	24	11000	5.3	22000	390
Football Field	SSHS-B3564	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	28 - 30 ft	180-116070-1	Not Excavated	3900	< 0.34 U	2.7	33	0.14 J	0.1 J	50000	4.4		3.7 J	16	9700	3.8	6500	650
Football Field	SSHS-B3564	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	30 - 32 ft	180-116070-1	Not Excavated	4300	< 0.41 U	4.1	26	0.2 J	0.1 J	39000	5.8		3.9 J	14	11000	5	5100	260
Football Field	SSHS-B3564	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	34 - 36 ft	180-116070-1	Not Excavated	5400	< 0.39 U	5	36	0.25 J	0.15 J	38000	7.2		5.1 J	16	14000	6.3	5400	380
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	3200	< 0.37 U	2.8	20 J	0.15 J	0.077 J	35000	4.3		3 J	10	7500	5.1	11000	310
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	6900	< 0.35 U	5.7	52	0.31 J	0.087 J	18000	8.5		6.2	18	18000	8.8	4300	320

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.017 U	11	380	0.42 J	< 0.061 U	87 J		< 0.17 U		8.5	42
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.021 U	9.9	400 J	< 0.49 U	< 0.11 U	54 J		< 0.30 U		7.1	51
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-836-834	8/12/2024	852.03	16.03-18.03 ft	1801782961	Not Excavated	< 0.024 U	16	630	< 0.55 U	0.12 BJ	< 170 U		< 0.47 U		10	74
Rear Parking Lot	SPA4-B5507	SSHS-SPA4-B5507-ELEV-834-832	8/13/2024	850.07	16.07-18.07 ft	1801783741	Not Excavated	< 0.019 U	11	700	0.75 J	< 0.095 U	< 170 U		< 0.47 U		11	43
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	0.022 J	11	510 J	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U		7.7	42
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	< 0.017 U	12	730	< 0.62 U	< 0.13 U	88 J		< 0.38 U		10	43
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-16-18	8/30/2019	858.28	16 - 18 ft	180-95047-2	Not Excavated	< 0.014 U	12	650	1.4	< 0.11 U	86 J		< 0.34 U		8.1	40
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	< 0.016 U	7.6	370 J	0.9 J	< 0.13 U	58 J		< 0.41 U		6.1 J	28
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.021 U	10	530	0.60 J	< 0.11 U	94 J		< 0.33 U		7.5	45
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.022 U	14	640	< 0.59 U	< 0.12 U	95 J		< 0.37 U		11	61
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.021 U	15	760	0.87 J	< 0.12 U	110 J		< 0.35 U		9.9	55
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.022 U	11	570	< 0.55 U	< 0.11 U	82 J		< 0.34 U		8.6	43
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.023 U	13	680	< 0.56 U	< 0.11 U	93 J		< 0.35 U		10	53
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.024 U	11	700	< 0.55 U	< 0.11 U	99 J		< 0.34 U		8.3	45
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	< 0.021 U	7.4	570	0.87 J	< 0.12 U	230 J		< 0.35 U		5.6	29
Football Field	SSHS-B3555	SSHS-B3555-SUB-20-22	1/11/2021	855.30	20 - 22 ft	180-115815-1	Not Excavated	< 0.022 U	13	580	< 0.56 U	< 0.11 U	96 J		< 0.35 U		8.8	46
Football Field	SSHS-B3555	SSHS-B3555-SUB-22-24	1/11/2021	855.30	22 - 24 ft	180-115815-1	Not Excavated	< 0.022 U	19	800	< 0.54 U	< 0.11 U	170 J		< 0.34 U		12	72
Football Field	SSHS-B3556	DUP-22	1/13/2021	855.33	16 - 18 ft	180-115925-1	Not Excavated	< 0.019 U	81	640	< 0.52 U	< 0.11 U	74 J		< 0.33 U		8.1	48
Football Field	SSHS-B3556	SSHS-B3556-SUB-16-18	1/13/2021	855.33	16 - 18 ft	180-115925-1	Not Excavated	< 0.019 U	56	630	< 0.56 U	< 0.11 U	76 J		< 0.35 U		8.2	47
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.023 U	210	550	0.59 J	< 0.11 U	73 J		< 0.34 U		8.3	45
Football Field	SSHS-B3556	SSHS-B3556-SUB-20-22	1/13/2021	855.33	20 - 22 ft	180-115925-1	Not Excavated	< 0.021 U	730	660	< 0.56 U	< 0.11 U	94 J		< 0.35 U		7.9	85
Football Field	SSHS-B3556	SSHS-B3556-SUB-22-24	1/13/2021	855.33	22 - 24 ft	180-115925-1	Not Excavated	< 0.022 U	190	590	0.8 J	< 0.11 U	89 J		< 0.33 U		7.8	51
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	< 0.021 U	9.9	660	0.78 J	< 0.11 U	110 J		< 0.32 U		6.5	47
Football Field	SSHS-B3557	DUP-23	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	< 0.021 U	11	590	< 0.52 U	< 0.11 U	80 J		< 0.32 U		7.6	41
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	< 0.019 U	11	840	< 0.56 U	< 0.11 U	120 J		< 0.35 U		9.2	45
Football Field	SSHS-B3557	SSHS-B3557-SUB-20-22	1/11/2021	855.18	20 - 22 ft	180-115815-1	Not Excavated	< 0.021 U	13	680	0.52 J	< 0.11 U	91 J		< 0.32 U		8.7	52
Football Field	SSHS-B3557	SSHS-B3557-SUB-22-24	1/11/2021	855.18	22 - 24 ft	180-115815-1	Not Excavated	< 0.018 U	14	710	< 0.52 U	< 0.11 U	120 J		< 0.32 U		8.6	67
Football Field	SSHS-B3558	DUP-24	1/12/2021	855.27	16 - 18 ft	180-115861-2	Not Excavated	< 0.021 U	8.1	640	< 0.52 U	< 0.11 U	86 J		< 0.33 U		6.7	35
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	< 0.019 U	9.4	710	0.57 J	< 0.11 U	82 J		< 0.34 U		7	39
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	< 0.021 U	12	910	< 0.55 U	< 0.11 U	100 J		< 0.34 U		11	52
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	< 0.02 U	9.6	620	< 0.54 U	< 0.11 U	88 J		< 0.34 U		6.4	34
Football Field	SSHS-B3558	SSHS-B3558-SUB-22-24	1/12/2021	855.27	22 - 24 ft	180-115861-1	Not Excavated	< 0.02 U	10	540	< 0.56 U	< 0.11 U	77 J		< 0.35 U		7	43
Football Field	SSHS-B3559	DUP-25	1/12/2021	855.35	16 - 18 ft	180-115861-2	Not Excavated	< 0.019 U	63	830	< 0.56 U	< 0.12 U	150 J		< 0.35 U		12	58
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	< 0.02 U	69	770	< 0.55 U	< 0.11 U	130 J		< 0.34 U		8.4	41
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	< 0.02 U	48	660	< 0.54 U	< 0.11 U	84 J		< 0.34 U		7.8	56
Football Field	SSHS-B3559	SSHS-B3559-SUB-20-22	1/12/2021	855.35	20 - 22 ft	180-115861-1	Not Excavated	< 0.019 U	19	630	< 0.52 U	< 0.11 U	81 J		< 0.33 U		8.2	48
Football Field	SSHS-B3559	SSHS-B3559-SUB-22-24	1/12/2021	855.35	22 - 24 ft	180-115861-1	Not Excavated	< 0.019 U	13	600	< 0.54 U	< 0.11 U	82 J		< 0.34 U		7.4	44
Football Field	SSHS-B3560	DUP-26	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	< 0.02 U	18	790	< 0.54 U	< 0.11 U	99 J		< 0.33 U		13	48
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	< 0.021 U	21	830	< 0.53 U	< 0.11 U	88 J		< 0.33 U		15	43
Football Field	SSHS-B3560	SSHS-B3560-SUB-18-20	1/11/2021	855.32	18 - 20 ft	180-115815-1	Not Excavated	< 0.018 U	9.6	680	< 0.54 U	< 0.11 U	96 J		< 0.34 U		7.6	44 J+
Football Field	SSHS-B3560	SSHS-B3560-SUB-20-22	1/11/2021	855.32	20 - 22 ft	180-115815-1	Not Excavated	< 0.019 U	13	680	0.55 J	< 0.11 U	93 J		< 0.32 U		8.5	51
Football Field	SSHS-B3560	SSHS-B3560-SUB-22-24	1/11/2021	855.32	22 - 24 ft	180-115815-1	Not Excavated	< 0.024 U	11	580	0.6 J	< 0.12 U	99 J		< 0.36 U		7.6	52
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	< 0.02 U	18	750	< 0.57 U	< 0.12 U	82 J		< 0.36 U		9	61
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	< 0.019 U	11	660	< 0.57 U	< 0.12 U	120 J		< 0.35 U		7.3	51 J
Football Field	SSHS-B3561	SSHS-B3561-SUB-20-22	1/13/2021	855.17	20 - 22 ft	180-115925-1	Not Excavated	< 0.023 U	19	570	0.62 J	< 0.12 U	85 J		< 0.35 U		11	60
Football Field	SSHS-B3561	SSHS-B3561-SUB-22-24	1/13/2021	855.17	22 - 24 ft	180-115925-1	Not Excavated	< 0.021 U	13	690	0.74 J	< 0.11 U	88 J		< 0.33 U		7.3	45
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	< 0.021 U	26	680	0.79 J	< 0.11 U	92 J		< 0.35 U		8.6	51
Football Field	SSHS-B3562	SSHS-B3562-SUB-18-20	1/13/2021	855.07	18 - 20 ft	180-115925-1	Not Excavated	< 0.018 U	14	580	< 0.54 U	< 0.11 U	76 J		< 0.33 U		7.7	58
Football Field	SSHS-B3562	SSHS-B3562-SUB-20-22	1/13/2021	855.07	20 - 22 ft	180-115925-1	Not Excavated	< 0.018 U	14	530	0.53 J	< 0.11 U	78 J		< 0.33 U		7	49
Football Field	SSHS-B3562	SSHS-B3562-SUB-22-24	1/13/2021	855.07	22 - 24 ft	180-115925-1	Not Excavated	< 0.02 U	25	850	< 0.52 U	< 0.11 U	95 J		< 0.33 U		18	58
Football Field	SSHS-B3563	SSHS-B3563-SUB-22-24	1/11/2021	855.01	22 - 24 ft	180-115815-1	Not Excavated	< 0.022 U	9.8	610	< 0.51 U	< 0.11 U	100 J		< 0.32 U		6.7	41
Football Field	SSHS-B3563	SSHS-B3563-SUB-20-22	1/11/2021	855.01	20 - 22 ft	180-115815-1	Not Excavated	< 0.02 U	16	830	< 0.57 U	< 0.12 U	110 J		< 0.35 U		10	64
Football Field	SSHS-B3563	SSHS-B3563-SUB-16-18	1/11/2021	855.01	16 - 18 ft	180-115815-1	Not Excavated	< 0.019 U	14	910	< 0.51 U	< 0.11 U	110 J		< 0.32 U		10	110
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	< 0.022 U	10	620	< 0.56 U	< 0.12 U	96 J		< 0.35 U		6.9	50
Football Field	SSHS-B3563	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	24 - 26 ft	180-115999-1	Not Excavated	< 0.021 U	21	510	< 0.53 U	< 0.11 U	82 J		< 0.33 U		6.8	53
Football Field	SSHS-B3563	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	26 - 28 ft	180-115999-1	Not Excavated	< 0.02 U	15	490 J	< 0.54 U	< 0.11 U	110 J		< 0.34 U		7.8	54
Football Field	SSHS-B3563	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	28 - 30 ft	180-115999-1	Not Excavated	< 0.023 U	12	520 J	< 0.57 U	< 0.12 U	84 J		< 0.35 U		6.3	43
Football Field	SSHS-B3563	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	34 - 36 ft	180-115999-1	Not Excavated	< 0.027 U	12	700	< 0.67 U	< 0.14 U	95 J		< 0.42 U		6.9	34
Football Field	SSHS-B3563	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	30 - 32 ft	180-115999-1	Not Excavated	< 0.026 U	12	710	< 0.61 U	< 0.12 U	91 J		< 0.38 U		7	38
Football Field	SSHS-B3563	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	32 - 34 ft	180-115999-1	Not Excavated	< 0.023 U	10	610	< 0.59 U	< 0.12 U	83 J		< 0.37 U		6.4	30
Football Field	SSHS-B3563	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	36 - 37 ft	180-116070-1	Not Excavated	< 0.023 U	11	710	< 0.62 U	< 0.13 U	85 J		< 0.38 U		10	38
Football Field	SSHS-B3564	SSHS-B3564-SUB-16-18	1/12/2021	855.22	16 - 18 ft	180-115861-1	Not Excavated	< 0.023 U	20	810	< 0.55 U	< 0.11 U	110 J		< 0.34 U		8.9	57
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	< 0.019 U	12	720	< 0.52 U	< 0.11 U	120 J		< 0.33 U		7.8	40
Football Field	SSHS-B3564	SSHS-B3564-SUB-20-22	1/12/2021	855.22	20 - 22 ft	180-115861-1	Not Excavated	< 0.024 U	13	550 J	< 0.58 U	< 0.12 U	89 J		< 0.36 U		7.5	46
Football Field	SSHS-B3564	SSHS-B3564-SUB-22-24	1/12/2021	855.22	22 - 24 ft	180-115861-1	Not Excavated	< 0.021 U	15	600	< 0.56 U	< 0.12 U	80 J		< 0.35 U		8.5	59
Football Field	SSHS-B3564	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	24 - 26 ft	180-116070-1	Not Excavated	< 0.023 U	16	900	0.73 J	< 0.12 U	160 J		< 0.36 U		9.1	46
Football Field	SSHS-B3564	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	36 - 37 ft	180-116070-1	Not Excavated	< 0.023 U	13	750	< 0.62 U	< 0.13 U	95 J		< 0.39 U		8.6	38
Football Field	SSHS-B3564	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	32 - 34 ft	180-116070-1	Not Excavated	< 0.023 U	13	820	< 0.59 U	< 0.12 U	93 J		< 0.37 U		9.1	45
Football Field	SSHS-B3564	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	26 - 28 ft	180-116070-1	Not Excavated	< 0.018 U	32	510	0.75 J	< 0.11 U	120 J		< 0.32 U		6.9	42
Football Field	SSHS-B3564	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	28 - 30 ft	180-116070-1	Not Excavated	< 0.022 U	26	420 J	< 0.52 U	< 0.11 U	84 J		< 0.32 U		8.1	49
Football Field	SSHS-B3564	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	30 - 32 ft	180-116070-1	Not Excavated	< 0.026 U	10	750	< 0.63 U	< 0.13 U	110 J		< 0.39 U		7.6	43
Football Field	SSHS-B3564	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	34 - 36 ft	180-116070-1	Not Excavated	< 0.023 U	13	790	< 0.58 U	< 0.12 U	95 J		< 0.36 U		8.8	42
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	< 0.023 U	7.4	610	< 0.56 U	< 0.11 U	91 J		< 0.35 U		6.2	35
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	< 0.022 U	16	790	< 0.53 U	< 0.11 U	82 J		< 0.33 U		11	47

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3565	SSHS-B3565-SUB-20-22	1/12/2021	855.32	20 - 22 ft	180-115861-2	Not Excavated	6300	< 0.36 U	4	37	0.24 J	0.12 J	37000	9.8		5.4	23	16000	6.4	5300	390
Football Field	SSHS-B3565	SSHS-B3565-SUB-22-24	1/13/2021	855.32	22 - 24 ft	180-115925-1	Not Excavated	5200	< 0.34 U	3.8	37	0.17 J	0.087 J	37000	7.9		4.3 J	17	12000	4.7	7600	450
Football Field	SSHS-B3566	SSHS-B3566-SUB-16-18	1/12/2021	855.28	16 - 18 ft	180-115861-2	Not Excavated	4400	< 0.34 U	4	54	0.18 J	0.075 J	19000	6.2		3.9 J	14	11000	8.6	4900	210
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	6600	< 0.33 U	6.2	45	0.23 J	0.097 J	20000	9.7		5.7	22	17000	18	5300	240
Football Field	SSHS-B3566	SSHS-B3566-SUB-20-22	1/12/2021	855.28	20 - 22 ft	180-115861-2	Not Excavated	5500	< 0.35 U	3.1	31	0.21 J	0.11 J	41000	7.2		4.8 J	19	13000	5.9	4900	330
Football Field	SSHS-B3566	SSHS-B3566-SUB-22-24	1/12/2021	855.28	22 - 24 ft	180-115861-2	Not Excavated	6800	< 0.36 U	3.3	35	0.24 J	0.12 J	60000	7.9		5.5	33	17000	5.3	3800	560
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	4800	< 0.28 U	2.9	32	0.18 J	0.068 J	21000	26		4.1 J	11	12000	5	4000	260
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	4200	< 0.27 U	3.3	31	0.18 J	0.13 J	71000	9.6		3.7 J	18	9600	8	20000	400
Football Field	SSHS-B3568	SSHS-B3568-SUB-20-22	1/18/2021	855.08	20 - 22 ft	180-116109-1	Not Excavated	3400	< 0.36 U	1.9	27	0.15 J	0.056 J	45000	5.3		3.8 J	14	9300	3.3	9300	970
Football Field	SSHS-B3568	SSHS-B3568-SUB-22-24	1/18/2021	855.08	22 - 24 ft	180-116109-1	Not Excavated	4100	< 0.27 U	2.7	24	0.14 J	0.065 J	15000	5.5		3.1 J	13	9500	3.4	5400	270
Football Field	SSHS-B3568	SSHS-B3568-SUB-24-26	1/18/2021	855.08	24 - 26 ft	180-116109-1	Not Excavated	2800	< 0.33 U	2.7	33	0.14 J	0.18 J	150000	4.6		2.4 J	12	7400	2.8	5800	290
Football Field	SSHS-B3568	SSHS-B3568-SUB-26-28	1/18/2021	855.08	26 - 28 ft	180-116109-1	Not Excavated	4400	< 0.26 U	3.1	29	0.18 J	0.11 J	80000	5.9		4.3	14	11000	3.7	5800	1500
Football Field	SSHS-B3568	SSHS-B3568-SUB-28-30	1/18/2021	855.08	28 - 30 ft	180-116109-1	Not Excavated	4400	< 0.35 U	4.2	33	0.21 J	0.14 J	39000	6.3		4.1 J	16	11000	5.2	5200	480
Football Field	SSHS-B3568	SSHS-B3568-SUB-30-32	1/18/2021	855.08	30 - 32 ft	180-116109-1	Not Excavated	5300	< 0.42 U	5	34	0.25 J	0.11 J	42000	7.7		4.9 J	16	13000	5.9	6000 J-	340
Football Field	SSHS-B3568	DUP-30	1/18/2021	855.08	32 - 34 ft	180-116109-1	Not Excavated	4700	< 0.4 U	5	31	0.24 J	0.11 J	42000	6.6		4.3 J	15	12000	5.7	5800	310
Football Field	SSHS-B3568	SSHS-B3568-SUB-32-34	1/18/2021	855.08	32 - 34 ft	180-116109-1	Not Excavated	4800	< 0.36 U	5.8	32	0.23 J	0.11 J	41000	6.7		4.4 J	15	12000	6.1	6000	330
Football Field	SSHS-B3568	DUP-31	1/18/2021	855.08	34 - 35 ft	180-116109-1	Not Excavated	5300	0.49 J	6.1	35	0.25 J	0.092 J	42000	7.2		5 J	16	13000	6.3	6400	390
Football Field	SSHS-B3568	SSHS-B3568-SUB-34-35	1/18/2021	855.08	34 - 36 ft	180-116109-1	Not Excavated	5000	< 0.39 UJ	8.3	31	0.24 J	0.09 J	40000	7.5		4.7 J	15	13000	6	5700	320
Football Field	SSHS-B3569	SSHS-B3569-SUB-16-18	1/19/2021	855.07	16 - 18 ft	180-116199-1	Not Excavated	4300	< 0.34 U	4.7	20	0.19 J	0.089 J	24000	6.7		4 J	14	9800	5.8	8500	410
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	2200	< 0.35 U	2	11 J	0.098 J	0.051 J	23000	3.9		1.8 J	7.8	5100	2.5	3500	270
Football Field	SSHS-B3569	SSHS-B3569-SUB-20-22	1/19/2021	855.07	20 - 22 ft	180-116199-1	Not Excavated	5700	< 0.39 U	3.3	29	0.2 J	0.07 J	21000	7.2		4.2 J	17	14000	3.6	6700	180
Football Field	SSHS-B3569	SSHS-B3569-SUB-22-24	1/19/2021	855.07	22 - 24 ft	180-116199-1	Not Excavated	4900	< 0.38 U	3.8	39	0.19 J	0.089 J	43000	7.3		4.3 J	20	12000	4.5	9400	420
Football Field	SSHS-B3569	SSHS-B3569-SUB-24-26	1/19/2021	855.07	24 - 26 ft	180-116199-1	Not Excavated	4700	0.38 J	4.4	73	0.21 J	0.11 J	26000	5.9		4.1 J	14	11000	5.3	5500	440
Football Field	SSHS-B3569	SSHS-B3569-SUB-26-28	1/19/2021	855.07	26 - 28 ft	180-116199-1	Not Excavated	5500	< 0.4 U	5.8	35	0.27 J	0.1 J	20000	7.5		5.3 J	14	14000	6.5	6700	210
Football Field	SSHS-B3569	SSHS-B3569-SUB-28-30	1/19/2021	855.07	28 - 30 ft	180-116199-1	Not Excavated	5800	< 0.38 U	5.9	39	0.31 J	0.12 J	33000	8		5.6	17	14000	7	6800	320
Football Field	SSHS-B3569	SSHS-B3569-SUB-30-32	1/19/2021	855.07	30 - 32 ft	180-116199-1	Not Excavated	5400	< 0.38 U	5.8	36	0.27 J	0.13 J	34000	7.4		5.2 J	16	13000	6.4	6400	300
Football Field	SSHS-B3569	DUP-32	1/19/2021	855.07	32 - 34 ft	180-116199-1	Not Excavated	5100	< 0.38 U	5.4	35	0.26 J	0.096 J	33000	7.2		4.9 J	15	13000	6	6200	290
Football Field	SSHS-B3569	SSHS-B3569-SUB-32-34	1/19/2021	855.07	32 - 34 ft	180-116199-1	Not Excavated	5000	< 0.38 U	5.4	31	0.23 J	0.086 J	39000	6.9		4.6 J	15	12000	5.2	5300	300
Football Field	SSHS-B3569	DUP-33	1/19/2021	855.07	34 - 36 ft	180-116199-1	Not Excavated	5500	< 0.39 U	5.9	35	0.26 J	0.11 J	39000	7.2		5.3 J	16	14000	6.8	6500	320
Football Field	SSHS-B3570	SSHS-B3570-SUB-16-18	1/19/2021	855.27	16 - 18 ft	180-116199-1	Not Excavated	6500	< 0.36 U	4.4	38	0.25 J	0.15 J	41000	13		5.7	19	16000	8.4	8900	550
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	6700	< 0.35 U	3.8	35	0.24 J	0.087 J	18000	9.3		5.2	20	16000	6.1	4600	340
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	6500	< 0.36 U	4.2	39	0.24 J	0.068 J	19000	9.6		5.5	19	15000	6.9	5800	230
Football Field	SSHS-B3570	SSHS-B3570-SUB-22-24	1/19/2021	855.27	22 - 24 ft	180-116199-1	Not Excavated	5200	< 0.36 U	3.8	30	0.19 J	0.11 J	39000	8.8		4.4 J	19	13000	5.1	6300	290
Football Field	SSHS-B3570	SSHS-B3570-SUB-24-26	1/19/2021	855.27	24 - 26 ft	180-116199-1	Not Excavated	4400	< 0.37 U	2.9	25	0.18 J	0.1 J	28000	7.7		3.6 J	17	11000	6.1	4200	280
Football Field	SSHS-B3570	SSHS-B3570-SUB-26-28	1/19/2021	855.27	26 - 28 ft	180-116199-1	Not Excavated	5600	< 0.36 U	2.6	34	0.18 J	0.11 J	22000	7.2		4.3 J	15	14000	9.5	6600	380
Football Field	SSHS-B3570	SSHS-B3570-SUB-28-30	1/19/2021	855.27	28 - 30 ft	180-116199-1	Not Excavated	5500	< 0.4 U	5.5	35	0.27 J	0.093 J	34000	7.2		5.2 J	17	14000	7.1	6300	300
Football Field	SSHS-B3570	SSHS-B3570-SUB-30-32	1/19/2021	855.27	30 - 32 ft	180-116199-1	Not Excavated	7400	< 0.41 U	6.9	53	0.34 J	0.097 J	38000	9.6		6.3	18	17000	8.6	6100	350
Football Field	SSHS-B3570	DUP-34	1/19/2021	855.27	32 - 34 ft	180-116199-1	Not Excavated	5400	< 0.42 U	5.3	35	0.28 J	0.1 J	33000	7.7		5.2 J	15	14000	7	6500	300
Football Field	SSHS-B3570	SSHS-B3570-SUB-32-34	1/19/2021	855.27	32 - 34 ft	180-116199-1	Not Excavated	5100	< 0.43 U	4.9	31	0.26 J	0.13 J	45000	6.7		4.6 J	15	12000	6.1	5700	310
Football Field	SSHS-B3570	SSHS-B3570-SUB-34-35	1/19/2021	855.27	34 - 36 ft	180-116199-1	Not Excavated	4500	< 0.41 U	5.1	29	0.23 J	0.1 J	58000	6.3		4.1 J	14	11000	5.4	6900	300
Football Field	SSHS-B3571	SSHS-B3571-SUB-16-18	1/18/2021	855.21	16 - 18 ft	180-116109-1	Not Excavated	4800	< 0.34 U	2.8	26	0.18 J	0.11 J	44000	8.5		4.2 J	15	12000	5.7	16000	420
Football Field	SSHS-B3571	SSHS-B3571-SUB-18-20	1/18/2021	855.21	18 - 20 ft	180-116109-1	Not Excavated	4600	< 0.34 U	3.3	19 J	0.17 J	0.081 J	25000	6.2		3.9 J	14	11000	12	5800	270
Football Field	SSHS-B3571	SSHS-B3571-SUB-20-22	1/18/2021	855.21	20 - 22 ft	180-116109-1	Not Excavated	2600	< 0.42 U	2.9	17 J	0.12 J	< 0.045 U	27000	4		2.7 J	11	7000	2.7	4400	240
Football Field	SSHS-B3571	SSHS-B3571-SUB-22-24	1/18/2021	855.21	22 - 24 ft	180-116109-1	Not Excavated	5900	< 0.3 U	2.9	35	0.19 J	0.061 J	19000	7.5		4.7	17	13000	3.9	5000	260
Football Field	SSHS-B3571	SSHS-B3571-SUB-24-26	1/18/2021	855.21	24 - 26 ft	180-116109-1	Not Excavated	5700	< 0.22 U	4.6	49	0.21 J	0.1 J	25000	7.6		5.1	18	13000	6.8	7200	480
Football Field	SSHS-B3571	SSHS-B3571-SUB-26-28	1/18/2021	855.21	26 - 28 ft	180-116109-1	Not Excavated	3100	< 0.25 U	3.8	20	0.15 J	0.1 J	87000	5.1		3.2 J	14	9400	5.8	30000	360
Football Field	SSHS-B3571	SSHS-B3571-SUB-28-30	1/18/2021	855.21	28 - 30 ft	180-116109-1	Not Excavated	3300	< 0.26 U	2.7	26	0.17 J	0.072 J	26000	4.4		3 J	11	8400	4.2	3800	320
Football Field	SSHS-B3571	SSHS-B3571-SUB-30-32	1/18/2021	855.21	30 - 32 ft	180-116109-1	Not Excavated	5300	< 0.23 U	4.5	43	0.22 J	0.13 J	40000	7.2		5.1	20	13000	6	6500	620
Football Field	SSHS-B3571	DUP-35	1/18/2021	855.21	32 - 34 ft	180-116109-1	Not Excavated	5800	0.43 J	5.1	41	0.27 J	0.099 J	34000	7.8		5.6	19	14000	6.7	5600	310
Football Field	SSHS-B3571	SSHS-B3571-SUB-32-34	1/18/2021	855.21	32 - 34 ft	180-116109-1	Not Excavated	6500	< 0.4 UJ	5.7	39	0.29 J	0.11 J	37000	8.8		6.2	21	16000	7.4	6300	320
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	6000	< 0.034 U	4.4	40	0.24 J	0.061 J	28000	8.2		5.2 J	20	14000	9.1	8100	370
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	6700	< 0.034 U	4.3	46	0.24 J	0.063 J	19000 J	10		5.5	28 J-	16000	14	5300	390
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	5100	< 0.034 U	4.9	60	0.2 J	0.085 J	59000	9.4		4.6 J	18	12000	8.9	6700	360
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	7000	< 0.034 U	4.5	42	0.27 J	0.054 J	23000	10		5.6 J	18	16000	6.4	5000	380
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	5200	< 0.034 U	3.3	35	0.21 J	0.049 J	16000	7		4.5 J	15	13000	5.3	3000	390
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	6700	< 0.034 U	4.8	43	0.23 J	0.035 J	26000	8.6		6.5	23	16000	7.1	5400	390
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	5600	< 0.034 U	3.3	30	0.18 J	< 0.034 U	20000	6.8		4.6	13	14000	7	3200	220
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated	7100	< 0.034 U	4.2	45	0.26 J	0.058 J	50000	8.6		6.2	21	15000	6.8	5300	330
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	6400	< 0.034 U	4.9	39	0.24 J	0.072 J	39000	7.9		5.5	22	15000	9	7800	380
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	5100	< 0.034 U	3.9	32	0.21 J	0.087 J	79000	6.6		4.6	17	12000	6.7	10000	340
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	5800	< 0.034 U	4.8	35	0.26 J	0.049 J	34000	7.6		5.2	18	14000	7.5	7300	250
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	19000	< 0.034 U	17	140	0.91	< 0.034 U	13000	26		17	25	36000	17	8600	630
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	6300	< 0.24 U	3.4	37	0.21 J	0.05 J	20000	7.3		5.7	18	14000	7.9	3900	340
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	6300	< 0.33 U	4.4	43	0.25 J	0.053 J	36000	8.9		5.3	21	14000	9.1	5500	410
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	6400	< 0.28 U	3.6	42	0.22 J	0.089 J	65000	8.1		5.5	15	15000	7	8100	390
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	8600	< 0.38 U	7.1	54	0.31 J	0.083 J	40000	11		7.9	30	20000	9.1	12000	430
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	5700	< 0.27 U	4.1	39	0.21 J	0.075 J	24000	7.6		5.5	29	14000	12	2800	900
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	7500	< 0.33 U	5.2	49	0.26 J	0.055 J	40000	9.5		6.7	25	17000	8	6200	400
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	3100	< 0.32 U	2.1	54	0.14 J	4.1	9200	93		2.9 J	40	6300	25	1400	130
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	6200	0.37 J	8.2	110	0.39	5.6	3900	490		6	220	15000	85	2100	140
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	6500	< 0.25 U	4.1	40	0.26 J	0.057 J	55000	8.5		6.1	20	15000	6.1	5300	330
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	5900	< 0.27 U	5	36	0.23 J	0.055 J	44000	8.1		5.6	19	14000	7.9	5600	320
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	5900	< 0.35 UJ	3.6	31	0.22 J	< 0.038 U	48000	7.4		5.1 J	18	14000	6.7	6100 J	270
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	7300	< 0.36 U	5.6	44	0.27 J	< 0.039 U	31000	9.9		5.9	17	16000	10	4300	310

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3565	SSHS-B3565-SUB-20-22	1/12/2021	855.32	20 - 22 ft	180-115861-2	Not Excavated	< 0.023 U	14	680	< 0.54 U	< 0.11 U	110 J		< 0.34 U		9.3	60
Football Field	SSHS-B3565	SSHS-B3565-SUB-22-24	1/13/2021	855.32	22 - 24 ft	180-115925-1	Not Excavated	< 0.02 U	39	530	0.77 J	< 0.11 U	89 J		< 0.32 U		6.9	56
Football Field	SSHS-B3566	SSHS-B3566-SUB-16-18	1/12/2021	855.28	16 - 18 ft	180-115861-2	Not Excavated	< 0.022 U	50	560	< 0.51 U	< 0.1 U	88 J		< 0.32 U		7.9	39
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	< 0.022 U	18	740	< 0.5 U	< 0.1 U	82 J		< 0.31 U		10	76
Football Field	SSHS-B3566	SSHS-B3566-SUB-20-22	1/12/2021	855.28	20 - 22 ft	180-115861-2	Not Excavated	< 0.017 U	13	670	0.68 J	< 0.11 U	100 J		< 0.33 U		8.2	57
Football Field	SSHS-B3566	SSHS-B3566-SUB-22-24	1/12/2021	855.28	22 - 24 ft	180-115861-2	Not Excavated	< 0.02 U	16	530	< 0.55 U	< 0.11 U	76 J		< 0.34 U		9.5	52
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	< 0.02 U	11	570	< 0.43 U	< 0.088 U	76 J		< 0.27 U		8.5	39
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	< 0.025 U	11	730	0.78 J	< 0.084 U	120 J		< 0.26 U		7.2	45
Football Field	SSHS-B3568	SSHS-B3568-SUB-20-22	1/18/2021	855.08	20 - 22 ft	180-116109-1	Not Excavated	< 0.023 U	9	420 J	< 0.55 U	< 0.11 U	79 J		< 0.34 U		5 J	32
Football Field	SSHS-B3568	SSHS-B3568-SUB-22-24	1/18/2021	855.08	22 - 24 ft	180-116109-1	Not Excavated	< 0.019 U	8.3	400	< 0.4 U	< 0.083 U	62 J		< 0.25 U		5.8	49
Football Field	SSHS-B3568	SSHS-B3568-SUB-24-26	1/18/2021	855.08	24 - 26 ft	180-116109-1	Not Excavated	< 0.022 U	7.4	550	1.3	< 0.1 U	120 J		< 0.31 U		5.1	45
Football Field	SSHS-B3568	SSHS-B3568-SUB-26-28	1/18/2021	855.08	26 - 28 ft	180-116109-1	Not Excavated	< 0.022 U	11	440	0.56 J	< 0.082 U	68 J		< 0.25 U		7.2	41
Football Field	SSHS-B3568	SSHS-B3568-SUB-28-30	1/18/2021	855.08	28 - 30 ft	180-116109-1	Not Excavated	< 0.024 U	11	710	< 0.52 U	< 0.11 U	91 J		< 0.33 U		8	42
Football Field	SSHS-B3568	SSHS-B3568-SUB-30-32	1/18/2021	855.08	30 - 32 ft	180-116109-1	Not Excavated	< 0.023 U	13	860	< 0.64 U	< 0.13 U	100 J		< 0.4 U		9.3	41
Football Field	SSHS-B3568	DUP-30	1/18/2021	855.08	32 - 34 ft	180-116109-1	Not Excavated	< 0.025 U	11	760	< 0.6 U	< 0.12 U	97 J		< 0.37 U		8.8	38
Football Field	SSHS-B3568	SSHS-B3568-SUB-32-34	1/18/2021	855.08	32 - 34 ft	180-116109-1	Not Excavated	< 0.025 U	11	780	< 0.54 U	< 0.11 U	100 J		< 0.34 U		9.1	39
Football Field	SSHS-B3568	DUP-31	1/18/2021	855.08	34 - 35 ft	180-116109-1	Not Excavated	< 0.026 U	13	830	< 0.62 UJ	< 0.13 U	92 J		< 0.39 U		9.5	39
Football Field	SSHS-B3568	SSHS-B3568-SUB-34-35	1/18/2021	855.08	34 - 36 ft	180-116109-1	Not Excavated	< 0.026 U	13	810	0.64 J	< 0.12 U	95 J		< 0.37 U		8.9	37
Football Field	SSHS-B3569	SSHS-B3569-SUB-16-18	1/19/2021	855.07	16 - 18 ft	180-116199-1	Not Excavated	< 0.022 U	10	650	< 0.52 U	< 0.11 U	75 J		< 0.32 U		6.8	42
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	< 0.023 U	5	420 J	0.63 J	< 0.11 U	< 62 U		< 0.33 U		3.9 J	22
Football Field	SSHS-B3569	SSHS-B3569-SUB-20-22	1/19/2021	855.07	20 - 22 ft	180-116199-1	Not Excavated	< 0.022 U	12	520 J	< 0.59 U	< 0.12 U	< 70 U		< 0.37 U		7.8	50
Football Field	SSHS-B3569	SSHS-B3569-SUB-22-24	1/19/2021	855.07	22 - 24 ft	180-116199-1	Not Excavated	< 0.024 U	10	840	0.66 J	< 0.12 U	97 J		< 0.36 U		10	44
Football Field	SSHS-B3569	SSHS-B3569-SUB-24-26	1/19/2021	855.07	24 - 26 ft	180-116199-1	Not Excavated	< 0.021 U	11	670	< 0.57 U	< 0.12 U	78 J		< 0.36 U		7.5	38
Football Field	SSHS-B3569	SSHS-B3569-SUB-26-28	1/19/2021	855.07	26 - 28 ft	180-116199-1	Not Excavated	< 0.027 U	13	820	< 0.61 U	< 0.13 U	94 J		< 0.38 U		9.3	40
Football Field	SSHS-B3569	SSHS-B3569-SUB-28-30	1/19/2021	855.07	28 - 30 ft	180-116199-1	Not Excavated	< 0.024 U	15	830	< 0.58 U	< 0.12 U	94 J		< 0.36 U		9.6	43
Football Field	SSHS-B3569	SSHS-B3569-SUB-30-32	1/19/2021	855.07	30 - 32 ft	180-116199-1	Not Excavated	< 0.022 U	14	770	< 0.58 U	< 0.12 U	88 J		< 0.36 U		9.1	39
Football Field	SSHS-B3569	DUP-32	1/19/2021	855.07	32 - 34 ft	180-116199-1	Not Excavated	< 0.023 U	13	730	< 0.58 U	< 0.12 U	88 J		< 0.36 U		8.5	38
Football Field	SSHS-B3569	SSHS-B3569-SUB-32-34	1/19/2021	855.07	32 - 34 ft	180-116199-1	Not Excavated	< 0.025 U	12	650	0.72 J	< 0.12 U	90 J		< 0.36 U		7.5	33
Football Field	SSHS-B3569	DUP-33	1/19/2021	855.07	34 - 36 ft	180-116199-1	Not Excavated	< 0.025 U	14	820	< 0.6 U	< 0.12 U	94 J		< 0.37 U		9.5	40
Football Field	SSHS-B3570	SSHS-B3570-SUB-16-18	1/19/2021	855.27	16 - 18 ft	180-116199-1	Not Excavated	< 0.023 U	17	810	0.63 J	< 0.11 U	120 J		< 0.34 U		11	62
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	< 0.022 U	14	700	< 0.52 U	< 0.11 U	73 J		< 0.33 U		10	51
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	< 0.021 U	14	690	< 0.54 U	< 0.11 U	78 J		< 0.34 U		8.8	61
Football Field	SSHS-B3570	SSHS-B3570-SUB-22-24	1/19/2021	855.27	22 - 24 ft	180-116199-1	Not Excavated	< 0.019 U	12	600	< 0.55 U	< 0.11 U	94 J		< 0.34 U		7.8	50
Football Field	SSHS-B3570	SSHS-B3570-SUB-24-26	1/19/2021	855.27	24 - 26 ft	180-116199-1	Not Excavated	< 0.02 U	10	560	0.65 J	< 0.12 U	75 J		< 0.35 U		6.5	46
Football Field	SSHS-B3570	SSHS-B3570-SUB-26-28	1/19/2021	855.27	26 - 28 ft	180-116199-1	Not Excavated	< 0.022 U	11	440 J	< 0.55 U	< 0.11 U	70 J		< 0.34 U		9.6	56
Football Field	SSHS-B3570	SSHS-B3570-SUB-28-30	1/19/2021	855.27	28 - 30 ft	180-116199-1	Not Excavated	< 0.024 U	13	820	< 0.6 U	< 0.12 U	95 J		< 0.37 U		9.2	40
Football Field	SSHS-B3570	SSHS-B3570-SUB-30-32	1/19/2021	855.27	30 - 32 ft	180-116199-1	Not Excavated	< 0.024 U	17	1000	< 0.63 U	< 0.13 U	100 J		< 0.39 U		11	42
Football Field	SSHS-B3570	DUP-34	1/19/2021	855.27	32 - 34 ft	180-116199-1	Not Excavated	< 0.024 U	13	890	0.75 J	< 0.13 U	100 J		< 0.4 U		10	41
Football Field	SSHS-B3570	SSHS-B3570-SUB-32-34	1/19/2021	855.27	32 - 34 ft	180-116199-1	Not Excavated	< 0.026 U	12	820	< 0.65 U	< 0.13 U	110 J		< 0.41 U		8	35
Football Field	SSHS-B3570	SSHS-B3570-SUB-34-35	1/19/2021	855.27	34 - 36 ft	180-116199-1	Not Excavated	< 0.023 U	11	740	0.67 J	< 0.13 U	110 J		< 0.38 U		7.3	31
Football Field	SSHS-B3571	SSHS-B3571-SUB-16-18	1/18/2021	855.21	16 - 18 ft	180-116109-1	Not Excavated	< 0.023 U	12	620	0.91 J	< 0.1 U	120 J		< 0.32 U		8.1	45
Football Field	SSHS-B3571	SSHS-B3571-SUB-18-20	1/18/2021	855.21	18 - 20 ft	180-116109-1	Not Excavated	< 0.02 U	9.8	560	< 0.51 U	< 0.1 U	75 J		< 0.32 U		7.6	55
Football Field	SSHS-B3571	SSHS-B3571-SUB-20-22	1/18/2021	855.21	20 - 22 ft	180-116109-1	Not Excavated	< 0.03 U	6.7	390 J	< 0.64 U	< 0.13 U	< 75 U		< 0.4 U		4 J	26
Football Field	SSHS-B3571	SSHS-B3571-SUB-22-24	1/18/2021	855.21	22 - 24 ft	180-116109-1	Not Excavated	< 0.023 U	13	520	< 0.45 U	< 0.092 U	66 J		< 0.28 U		7.6	65
Football Field	SSHS-B3571	SSHS-B3571-SUB-24-26	1/18/2021	855.21	24 - 26 ft	180-116109-1	Not Excavated	< 0.021 U	14	490	< 0.34 U	< 0.069 U	75 J		< 0.21 U		7.7	66
Football Field	SSHS-B3571	SSHS-B3571-SUB-26-28	1/18/2021	855.21	26 - 28 ft	180-116109-1	Not Excavated	< 0.023 U	8.1	470	0.71 J	< 0.078 U	100 J		< 0.24 U		6.4	38
Football Field	SSHS-B3571	SSHS-B3571-SUB-28-30	1/18/2021	855.21	28 - 30 ft	180-116109-1	Not Excavated	< 0.022 U	7.2	550	< 0.4 U	< 0.082 U	62 J		< 0.25 U		6.3	33
Football Field	SSHS-B3571	SSHS-B3571-SUB-30-32	1/18/2021	855.21	30 - 32 ft	180-116109-1	Not Excavated	< 0.022 U	14	650	< 0.36 U	< 0.073 U	83 J		< 0.22 U		8.8	56
Football Field	SSHS-B3571	DUP-35	1/18/2021	855.21	32 - 34 ft	180-116109-1	Not Excavated	< 0.023 U	14	770	< 0.55 U	< 0.11 U	89 J		< 0.34 U		9.2	55
Football Field	SSHS-B3571	SSHS-B3571-SUB-32-34	1/18/2021	855.21	32 - 34 ft	180-116109-1	Not Excavated	< 0.026 U	16	880	< 0.6 U	< 0.12 U	99 J		< 0.37 U		11	61
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	< 0.034 U	13	820	0.68 J	< 0.034 U	84 J		< 0.034 U		11	51
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	14	770	0.54 J	< 0.034 U	81 J		< 0.034 U		12	52 J-
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	12	640	1.3	< 0.034 U	87 J		< 0.034 U		8.1	55
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	15	840	< 0.034 U	< 0.034 U	86 J		< 0.034 U		11	54
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.034 U	11	590	0.8 J	< 0.034 U	71 J		< 0.034 U		7.8	52
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	17	630	0.79 J	< 0.034 U	74 J		< 0.034 U		9.6	52
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	< 0.034 U	12	390 J	< 0.034 U	< 0.034 U	54 J		< 0.034 U		7.7	42
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated	< 0.034 U	16	750	0.85	< 0.034 U	95 J		< 0.034 U		10	48
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.034 U	15	710	0.55 J	< 0.034 U	80 J		< 0.034 U		9.5	52
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.034 U	12	740	1.4	< 0.034 U	110 J		< 0.034 U		9.1	42
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	< 0.034 U	13	790	0.85 J	< 0.034 U	87 J		< 0.034 U		10	48
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	0.025 J	40	2900	< 0.034 U	< 0.034 U	140 J		< 0.034 U		28	81
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.019 U	12	430	0.67 J	< 0.073 U	42 J		< 0.22 U		9.1	39
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.021 U	13	720	< 0.49 U	< 0.1 U	81 J		< 0.31 U		10	45
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.018 U	14	650	0.96	< 0.086 U	85 J		< 0.26 U		9.8	49
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.021 U	20	770	0.59 J	< 0.12 U	72 J		< 0.36 U		13	70
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.018 U	13	490	0.56 J	< 0.085 U	< 49 U		< 0.26 U		7.9	48
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.019 U	17	680	0.86 J	< 0.1 U	75 J		< 0.31 U		11	51
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.014 U	140	680	0.5 J	0.43 J	< 56 U		< 0.3 U		4.7	230
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.019 U	330	550	0.79 J	1.3	< 58 U		< 0.31 U		11	370
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.02 U	16	660	0.98	< 0.077 U	85 J		< 0.23 U		9.7	51
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.024 U	14	690	0.55 J	< 0.082 U	83 J		< 0.25 U		9.7	47
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.021 U	13	680	1.3	< 0.11 U	78 J		< 0.33 U		9.2	46
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.019 U	14	760	< 0.55 U	< 0.11 U	91 J		< 0.34 U		12	49

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	11000	< 0.34 U	5	57	0.5	< 0.037 U	18000	15		9.7	51	23000	8.9	7200	320
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	5600	< 0.27 U	4.3	35	0.22 J	0.055 J	43000	7.8		4.8	16	13000	6.9	4000	280
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	11000	< 0.37 U	4.4	68	0.43	< 0.039 U	25000	14		9.7	19	24000	6.7	6800	580
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	15000	< 0.35 U	5.9	130	0.69	< 0.038 U	19000	18		11	18	25000	12	8400	360
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	8200	< 0.31 U	4.5	62	0.3 J	< 0.033 U	67000	9.7		7.1	15	16000	6.7	4600	360
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	6100	< 0.38 U	4.9	39	0.24 J	0.062 J	38000	8.7		5.4 J	17	14000	7.2	5100	280
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	5500	< 0.26 U	5	34	0.24 J	0.064 J	45000	7.6		5.3	17	14000	6.8	5500	300
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	6100	< 0.4 U	5.2	40	0.25 J	< 0.043 U	34000	8.3		5.5 J	18	15000	8	5200	280
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	4200	< 0.4 U	3.6	23 J	0.2 J	0.097 J	35000	5.8		4.1 J	16	11000	5	4200	240
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	5800	< 0.33 U	4.8	26	0.25 J	0.12 J	8600	7.7		5.6	19	13000	7.3	2600	390
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	4900	< 0.27 U	4.1	25	0.21 J	0.15 J	19000	7.6		4.7	14	12000	7	3500	620
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	7500	0.31 J	4.1	77	0.28 J	0.11 J	5800	9.9		5.7	23	15000	21	3200	390
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	3800	< 0.33 U	3.2	29	0.16 J	0.11 J	76000	6.4		3.8 J	15	9900	10	26000	420
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	3300	< 1.3 U	2.9	27 J	0.13 J	0.12 J	110000 J	4.9		3.7 J	12	8000	11	37000 J	510
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	5200	< 0.37 U	4.5	48 J	0.2 J	0.12 J	43000 J	7.8		5.8	18	13000	10	13000 J	590
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	5200	< 0.3 UJ	5.1	33	0.25 J	0.085 J	33000	6.8		5.2	14	13000	6.9	6100 J-	280
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	4900	< 0.34 U	4.7	33	0.23 J	0.097 J	34000	6.7		4.6 J	13	12000	6.4	5200	280
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	4800	< 0.37 U	5.3	31	0.23 J	0.11 J	35000	7.3		4.6 J	14	12000	6.4	5600	270
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	4700	< 0.31 U	5.7	30	0.23 J	0.11 J	36000	7.2		4.8	16	13000	7.2	6700	260
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	15000	< 0.31 U	10	97	0.68	0.066 J	14000	20		14	21	29000	14	8300	470
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	14000	< 0.36 U	8.4	97	0.67	0.059 J	8900	19		14	19	28000	14	6900	420
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	2900	< 0.32 UJ	2.9	22	0.13 J	0.084 J	27000	5		3 J	11	7000	6.3	11000	560
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	3600	0.57 J	3.1	25	0.16 J	0.12 J	19000	6.2		3.5 J	14	8300	6.1	8500	520
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	5700	0.34 J	4.6	62	0.25 J	0.13 J	15000	16		6.1	64	22000	47	5200	350
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	4500	0.54 J	3.3	26	0.17 J	0.083 J	11000	74		4 J	19	10000	6.6	2700	260
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	4300	< 0.26 U	3.7	23	0.16 J	0.085 J	17000	45		3.6 J	20	10000	7.2	4500	250
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	2900	< 0.25 U	2.7	18	0.11 J	0.068 J	50000	42		2.8 J	12	7200	4.2	6100	280
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	4800	< 0.32 U	4.5	44	0.21 J	0.098 J	36000	13		4.5 J	18	12000	6.5	6200	440
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	4600	< 0.31 U	6.9	29	0.21 J	0.11 J	41000	8.7		4.7	13	12000	6.6	6200	330
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	4300	< 0.3 UJ	4.3	26	0.2 J	0.087 J	36000 J	7.1		4 J	12	10000 J	5.4	3900 J	270
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	15000	< 0.37 U	11	90	0.7	0.072 J	14000	22		14	22	30000	16	8800	450
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	11000	< 0.35 U	7	61	0.5	< 0.038 U	8900	17		10	17	23000	11	6100	340
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	6000	0.74 J	4.9	30	0.26 J	0.12 J	1400	9.1		4.5 J	16	13000	11	2100	520
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	3100	< 0.25 U	2.3	32	0.12 J	0.085 J	26000	4.5		2.5 J	13	6800	5.4	4900	510
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	3800	< 0.29 U	2.8	29	0.14 J	0.13 J	57000	5.8		3.3 J	16	8700	7.3	3600	470
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	4700	< 0.25 U	8.6	31	0.16 J	0.18 J	35000	7		5.3	67	12000	13	3800	500
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	4900	< 0.3 U	3.2	34	0.17 J	0.16 J	37000	8.5		5	93	11000	5.7	8000	560
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	5300	0.69 J	3.5	30	0.2 J	0.14 J	38000	8.6		5	130	13000	6	8700	440
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	5400	< 0.33 U	4.5	29	0.23 J	0.11 J	38000	7.4		5.3	59	12000	6.5	5200	270
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	5700	< 0.38 U	5	31	0.25 J	0.14 J	46000	8.2		5.5 J	58	14000	7.4	6200	310
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	14000	< 0.37 UJ	9.7	130 J-	0.71	0.11 J	25000	18		12	27	26000	14	7500 J	390
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	12000	< 0.23 U	10	67	0.53	0.042 J	8600	17		12	19	24000	13	6700	390
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	10000	< 0.41 U	6.5	48	0.46 J	0.064 J	11000	14		10	16	23000	9.9	7200	350
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	3200	< 0.39 U	3.9	27	0.14 J	0.059 J	1700	6.1		3.0 J	11	9300	5.5	1500	460
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	5200	< 0.38 U	3.5	39	0.17 J	0.080 J	18000	7.7		4.8 J	21	12000	4.3	3000	480
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	4100 T	< 0.37 UT	3.3	31 T	0.16 J	0.070 J	36000 T	6.9 T		4.3 J	12	10000 T	4.6	14000 T	210 T
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	4300	< 0.35 U	5.4	26	0.15 J	0.060 J	53000	5.7		4.9 J	15	10000	5.9	24000	310
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	9600	< 0.38 U	7.7	89	0.43 J	0.044 J	11000	13		9.0	15	20000	9.4	5200	430
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	10000	< 0.42 U	6.6	56	0.48 J	0.047 J	11000	14		10	15	23000	10	6900	320
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	13000	< 0.43 U	12	81	0.59	0.046 J	10000	16		12	16	25000	12	6400	390
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	19000	< 0.39 U	10	170	1.0	0.065 J	3500	24		17	23	35000	20	6500	470
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	4200	< 0.034 U	1.9	30	0.15 J	0.13 J	130000	5.3		4.6 J	12	12000	3.5	3000	2100
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	3800	< 0.034 U	2.9	19 J	0.14 J	0.11 J	41000 J	5.1		3.3 J	13 J	8800	5.3	8100 J	420
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	2900	2	3.7	17 J	0.12 J	0.32 J	32000	4.3		2.8 J	10	7500	4.9	3100	230
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	420	< 0.034 U	0.76 J	4.4 J	< 0.034 U	0.11 J	220000	0.95		0.53 J	5.1	1100	< 0.034 U	2400	130
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	6400	< 0.034 U	5.9	44	0.29 J	0.11 J	25000	8.3		7.5	16	16000	7.7	6000	390
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	14000	< 0.034 U	10	84	0.6	0.067 J	14000	20		13	20	27000	12	8100	430
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	5400	< 0.034 U	4.1	31	0.23 J	0.071 J	28000	6.8		4.7 J	13	13000	5.6	3500	220
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	5400	< 0.034 U	4.3	32	0.23 J	0.093 J	30000	7		5.1	14	13000	6	4300	240
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	3900	< 0.034 U	3.9	24 J-	0.18 J	0.088 J	39000	5.3		3.6 J	11	9800	4.5	4900	240
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	8000	< 0.034 U	4.9	66	0.31 J	0.11 J	26000	10		6.7	16	18000	6.9	4400	330
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	13000	< 0.034 U	10	89	0.62	0.068 J	8200	17		12	17	25000	12	6400	360
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	13000	< 0.034 U	9.5	72	0.54	0.068 J	11000	17		12	17	26000	10	7300	390
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated	9900	< U	5.7	45	0.41 J	0.06 J	10000	14		9.9	14	21000	8.7	6800	350
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	5800	< 0.034 U	6.2 J	44	0.29 J	0.12 J	34000 J	7		6	24	15000	9.8	15000 J	720
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	7400	0.37 J	11 J	58	0.33 J	0.053 J	19000 J	9.3		7.3	18	17000	14	7100 J	460
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	5600	< 0.034 U	3.9	31	0.22 J	0.089 J	23000	7.5		5 J	14	13000	7.1	6100	330
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	3800	< 0.034 U	3.2	25	0.16 J	0.096 J	34000	5.5		3.4 J	13	9200	4.2	5400	270
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	4600	< 0.034 U	5.3	28	0.19 J	0.087 J	45000	6.6		4.7 J	12	11000	21	9500	400
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	4200	< 0.034 U	3.2	24	0.15 J	0.11 J	67000	5.6		4.3 J	12	10000	5	4000	390
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	3600	< 0.034 U	2.8	19 J	0.14 J	0.1 J	56000	5		3.6 J	13	8500	3.7	3500	280
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	4000	< 0.034 U	3.2	32	0.16 J	0.14 J	43000	5.4		4.3 J	16	11000	6.7	4100	450
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	5100	< 0.034 U	3.9	32	0.17 J	0.11 J	39000	7.5		5	21	12000	6.8	6600	350
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	4200	< 0.034 U	3.6	23 J	0.2 J	0.097 J	35000	5.8		4.1 J	16	11000	5	4200	240

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.027 U	23	1400	< 0.52 U	< 0.11 U	91 J		< 0.32 U		16	55
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.018 U	12	590	0.68 J	< 0.082 U	70 J		< 0.25 U		9.1	43
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.024 U	24	1200	< 0.56 U	< 0.11 U	87 J		< 0.35 U		16	73
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.016 U	26	2700	< 0.53 U	< 0.11 U	110 J		< 0.33 U		21	57
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.013 U	17	1100	0.95	< 0.095 U	83 J		< 0.29 U		11	43
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.021 U	14	860	< 0.58 U	< 0.12 U	81 J		< 0.36 U		10	49
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.017 U	13	650	0.5 J	< 0.081 U	79 J		< 0.25 U		11	45
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.021 U	14	780	< 0.61 U	< 0.12 U	< 71 U		< 0.38 U		10	51
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.021 U	10	580 J	< 0.61 U	< 0.12 U	73 J		< 0.38 U		7.7	41
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.024 U	15	650	< 0.5 U	< 0.1 U	230 J		< 0.31 U		9.4	61
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.023 U	12	580	< 0.4 U	< 0.082 U	210 J		< 0.25 U		8.7	40
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.018 U	15	650	< 0.45 U	< 0.092 U	200 J		< 0.28 U		11	58
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.019 U	11	520	0.56 J	< 0.1 U	120 J		< 0.32 U		6.6	33
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.019 U	9.3 J	480	0.94 J	< 0.081 U	190 J		< 1.2 U		5.8	30
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.02 U	14	700	< 0.56 UJ	< 0.11 U	110 J		< 0.35 U		8.7	48
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.025 U	13	730	< 0.45 U	< 0.092 U	85 J		< 0.28 U		9	41 J-
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.02 U	12	650	< 0.52 U	< 0.11 U	90 J		< 0.32 U		8.4	34
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.023 U	12	700	< 0.57 U	< 0.12 U	88 J		< 0.35 U		8.6	36
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.021 U	12	710	< 0.47 U	< 0.095 U	91 J		< 0.29 U		9.8	39
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.026 U	34	1800	< 0.47 U	< 0.097 U	120 J		< 0.29 U		20	64
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.027 U	33	1800	< 0.54 U	< 0.11 U	99 J		< 0.34 U		19	65
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.022 U	10	500	< 0.49 U	< 0.1 U	78 J		< 0.3 U		4.6 J	32
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.023 U	12	590	< 0.48 U	< 0.098 U	81 J		< 0.3 U		6.1 J	42
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.02 U	38	630	< 0.38 U	< 0.078 U	94 J		< 0.24 U		9.7	58
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.02 U	22	540	< 0.42 U	< 0.086 U	63 J		< 0.26 U		7.1	48
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.02 U	17	440	< 0.4 U	< 0.081 U	65 J		< 0.25 U		6.3	49
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.019 U	10	350 J	0.56 J	< 0.078 U	83 J		< 0.24 U		4.5	29
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.021 U	16	710	0.59 J	< 0.098 U	95 J		< 0.3 U		8.3	48
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.021 U	14	710	0.78 J	< 0.095 U	96 J		< 0.29 U		10	36
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.023 U	12	580	0.6 J	< 0.094 U	90 J		< 0.29 U		7.2	30
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.026 U	35	2000	< 0.56 U	< 0.11 U	130 J		< 0.35 U		20	68
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.018 U	26	1400	0.75 J	< 0.11 U	85 J		< 0.33 U		14	51
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.024 U	20	1100	< 0.51 U	< 0.1 U	< 60 U		< 0.32 U		8.8	84
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.018 U	23	500	0.44 J	< 0.078 U	63 J		< 0.24 U		4.9	32
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.019 U	20	660	0.68 J	< 0.091 U	74 J		< 0.28 U		6.3	45
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.017 U	200	500	0.53 J	< 0.077 U	69 J		< 0.23 U		7.8	200
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.022 U	180	610	0.51 J	< 0.094 U	99 J		< 0.29 U		7.3	120
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.02 U	170	650	0.48 J	< 0.093 U	85 J		< 0.28 U		8.8	85
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.024 U	170	690	0.74 J	< 0.1 U	89 J		< 0.31 U		8.5	63
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.021 U	140	870	0.7 J	< 0.12 U	98 J		< 0.36 U		9.7	63
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.022 U	41	2200	< 0.56 U	< 0.11 U	140 J		< 0.35 U		20	62 J-
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.025 U	34	1300	< 0.35 U	< 0.072 U	88 J		< 0.22 U		16	58
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	0.034 J	24	1200	< 0.62 U	< 0.13 U	85 J		< 0.38 U		14	52
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.025 U	7.7	330 J	< 0.59 U	< 0.12 U	< 70 U		< 0.37 U		5.7 J	40
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	0.025 J	13	560	< 0.58 U	< 0.12 U	76 J		< 0.36 U		8.6	58
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.024 U	11	400 J	0.60 J	< 0.12 U	74 J		< 0.35 U		7.1	45 T
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.022 U	11	550	0.70 J	< 0.11 U	120 J		< 0.33 U		7.6	37
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.022 U	21	1200	< 0.58 U	< 0.12 U	83 J		< 0.36 U		13	48
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	0.032 J	24	1200	< 0.63 U	< 0.13 U	81 J		< 0.39 U		13	51
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	0.030 J	27	1700	< 0.65 U	< 0.13 U	100 J		< 0.40 U		16	59
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.026 U	38	2900	< 0.59 U	< 0.12 U	120 J		< 0.36 U		25	75
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	11	560 J	1 J	< 0.034 U	87 J		< 0.034 U		11	37
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	8.7	490 J	< 0.034 U	< 0.034 U	110 J		< 0.034 U		6.1	38
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	7	390 J	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		4.1 J	30
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	2 J	180 J	2.2	< 0.034 U	68 J		< 0.034 U		1.2 J	4.1
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	16	850	< 0.034 U	< 0.034 U	92 J		< 0.034 U		11	48
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	30	1900	< 0.034 U	< 0.034 U	100 J		< 0.034 U		19	62
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	12	650	< 0.034 U	< 0.034 U	76 J		< 0.034 U		7.9	35
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	13	630	< 0.034 U	< 0.034 U	79 J		< 0.034 U		7.9	34
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	9.4	560 J	< 0.034 U	< 0.034 U	77 J		< 0.034 U		6.9	27
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	18	850	< 0.034 U	< 0.034 U	88 J		< 0.034 U		12	51
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	28	1900	< 0.034 U	< 0.034 U	96 J		< 0.034 U		18	57
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	< 0.034 U	28	1600	< 0.034 U	< 0.034 U	91 J		< 0.034 U		17	58
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated	< U	24	1100	< U	< U	80 J		< U		14	50
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	15	950	0.51 J	< 0.034 U	120 J		< 0.034 U		9.8	45
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	19	980	< 0.034 U	< 0.034 U	87 J		< 0.034 U		11	43
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	14	690	< 0.034 U	< 0.034 U	79 J		< 0.034 U		8.9	46
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	9	550 J	0.61 J	< 0.034 U	75 J		< 0.034 U		6.5	33
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	11	540	0.73 J	< 0.034 U	87 J		< 0.034 U		7.2	41
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	16	460 J	1	< 0.034 U	79 J		< 0.034 U		6	43
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	27	440 J	0.79 J	< 0.034 U	67 J		< 0.034 U		5.6	34
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	17	460 J	< 0.034 U	< 0.034 U	87 J		< 0.034 U		6	56
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	16	560	< 0.034 U	< 0.034 U	81 J		< 0.034 U		8.6	48
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	10	580 J	< 0.034 U	< 0.034 U	73 J		< 0.034 U		7.7	41

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	4100	< 0.034 U	4.5	23	0.18 J	0.089 J	34000	5.6		4.2 J	13	11000	5	4400	250
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	4000	< 0.034 U	4.1	23	0.18 J	0.083 J	31000	5.7		4.1 J	12	11000	5.2	4400	240
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	5000	< 0.034 U	4.6	31	0.21 J	0.1 J	40000	7		5.3 J	15	13000	6.4	4500	390
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	16000	< 0.034 U	12	87	0.69	0.083 J	13000	21		15	22	32000	14	8700	460
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	13000	< 0.034 U	10	90	0.6	0.051 J	9200	19		12	18	26000	12	6500	380
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	14000	< 0.034 U	12	83	0.62	0.055 J	10000	19		14	19	30000	13	7600	440
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	14000	< UJ	10	78 J-	0.61 J-	0.077 J	11000 J	20 J-		13	19	28000	13 J-	7800 J	440 J
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	13000	< 0.46 U	11	96	0.68	< 0.049 U	6800	17		12	17	27000	14	6400	400
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	13000	< 0.46 U	11	82	0.61	0.060 J	7800	17		12	17	28000	12	6800	430
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	3900	< 0.32 U	3.8	39	0.12 J	0.096 J	54000	6.3		3.8 J	12	11000	4.2	7400	600
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	3200	< 0.35 U	3.0	20	0.12 J	0.11 J	42000	5.3		2.8 J	15	8500	4.5	15000	370
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	3500	< 0.38 U	2.5	22	0.13 J	0.081 J	57000	5.5		3.1 J	13	8500	4.2	8000	280
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	5000	< 0.35 U	4.0	35	0.21 J	0.081 J	35000	7.1		4.5 J	13	12000	5.8	4400	290
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	8900	< 0.43 U	7.8	42	0.37 J	0.048 J	7500	11		8.7	14	20000	8.0	5500	310
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	13000	< 0.43 U	12	80	0.59	0.061 J	9100	17		13	18	28000	12	7300	450
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	4400	1.2	8.2	82	0.27 J	0.22 J	17000	17		4.9 J	78	31000	75	4200	360
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	4600	< 0.29 U	4.3	21	0.17 J	0.093 J	24000	19		3.9 J	40	10000	7.9	4500	310
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	4300	< 0.32 U	3.2	23	0.18 J	0.14 J	44000	11		3.7 J	39	9900	6.2	6300	350
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	3000	< 0.32 U	2.8	20	0.13 J	0.09 J	84000	6.4		2.5 J	21	6800	5.7	4800	230
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	4700	< 0.38 U	4.8	46	0.2 J	0.11 J	53000	6.9		4.8 J	29	13000	9.5	11000	480
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	5300	< 0.32 U	5	37	0.23 J	0.11 J	54000	10		4.8	25	13000	8	6000	300
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	4900	< 0.31 UJ	5.6	32	0.24 J	0.091 J	36000	7.1		4.8	14	13000	7.4	7000 J-	280
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	4500	< 0.42 U	5.8	31	0.23 J	0.098 J	39000	7.2		4.5 J	15	12000	7	7400	290
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	3800	< 0.25 U	4.2	25	0.18 J	0.078 J	28000	5.6		3.8	12	9200	5.4	4300	230
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	5200	< 0.38 U	5.7	33	0.26 J	0.098 J	32000	8.1		4.8 J	15	13000	7.4	6200	270
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	17000	< 0.36 U	7.8	110	0.81	0.094 J	17000	22		15	24	32000	16	10000	470
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	4000	1.9	12	110	0.28 J	0.31 J	13000	23		5.3	110	51000	94	3100	370
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	5100	< 0.31 U	4.9	32	0.25 J	0.09 J	32000	7.9		5	16	13000	7.4	6100	280
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	16000	< 0.42 U	12	100	0.74	0.051 J	10000	21		15	21	33000	15	8500	530
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	4000	< 0.32 U	4.5	92	0.22 J	0.12 J	39000	6.9		4.2 J	20	12000	12	8100	480
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	4900	< 0.34 U	3.9	54	0.20 J	0.090 J	30000	6.9		4.6 J	16	13000	7.1	5000	310
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	5800	< 0.33 U	3.5	37	0.19 J	0.091 J	52000	7.3		5.4	17	14000	6.5	5600	390
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	5100	< 0.31 U	4.0	27	0.18 J	0.13 J	73000	6.4		4.7	19	12000	4.3	7000	340
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	16000	< 0.39 UT	12	140 T	0.72	0.079 J	16000	20		15	22	32000	14	6700 T	620
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	4100	0.68 J	3.3	25	0.17 J	0.11 J	23000	5.9		3.6 J	13	9700	5.6	6000	240
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	3400	0.75	3.1	27	0.14 J	0.13 J	47000	4.9		3.4	11	8700	5.5	6700	530
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	5700	0.61 J	4.2	37	0.21 J	0.16 J	19000	7.4		5.5	27	14000	17	4900	350
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	11000	0.73 J	4.9	47	0.43	0.19 J	13000	14		9.9	16	20000	10	7700	270
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	4000	0.47 J	4.3	24	0.15 J	0.11 J	31000	8.7		3.5 J	14	9900	6.0	4300	190
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	5000	0.54 J	3.8	35	0.16 J	0.10 J	22000	6.9		4.6	30	11000	4.4	4000	240
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	4900	0.69 J	3.1	28	0.16 J	0.12 J	24000	7.7		4.4 J	17	12000	3.8	3400	190
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	13000	0.98 JT	9.3 T	94 T	0.54 T	0.21 JT	10000 T	17 T		12 T	17 T	25000	11 T	6600 T	510
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	3600	0.35 JT	4.1	23	0.16 J	0.16 JT	45000 T	5.3		3.3 J	13	9400	5.8	8100 T	240
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated	5300	< 0.34 UJ	3.5	37	0.19 J	0.085 J	46000	9.7		4.7 J	19	13000	4.9	4700 J+	270
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated	6000	< 0.31 U	5.1	40	0.21 J	0.092 J	63000	7.8		5.4	20	15000	7.1	10000	420
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated	6400	< 0.35 U	3.9	40	0.21 J	0.097 J	52000	7.7		5.6	16	16000	7.1	5200	350
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated	5700	< 0.34 U	3.4	37	0.19 J	0.11 J	39000	7.7		5.1	20	14000	5.2	6200	340
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated	10000	< 0.38 U	6.5	56	0.36 J	0.072 J	19000	14		9.1	23	23000	8	7100	350
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	6000	0.37 J	5.4	50	0.28 J	0.17 J	1800	13		6.1	21	14000	9.0	2300	550
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	5400	0.48 J	4.3	41	0.21 J	0.16 J	8600	7.5		4.9	19	13000	6.8	4800	370
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	4800	0.39 J	4.0	35	0.18 J	0.16 J	26000	6.1		4.4 J	15	13000	5.4	4100	330
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	5600	< 0.34 U	6.2	38	0.21 J	0.17 J	18000	8.6		5.0	15	14000	5.3	3600	330
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	4200	< 0.39 U	4.3	35	0.16 J	0.16 J	45000	5.4		3.8 J	12	10000	7.1	3500	360
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217043	Not Excavated									< 0.28 U						
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-32-34	5/13/2021	856.89	32 - 34 ft	1801217043	Not Excavated									< 0.27 U						
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	3200	< 0.38 U	1.1	23	0.099 J	0.082 J	18000	4.0		2.6 J	6.8	7200	2.1	3800	130
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	5100	0.62 J	2.7	29	0.17 J	0.15 J	37000	6.2		4.7 J	15	12000	3.4	5700	290
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	5700	0.45 J	3.5	43	0.18 J	0.23 J	54000	7.3		4.7 J	18	14000	6.2	4800	470
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	17000	0.78 J	7.8	83	0.71	0.34 J	16000	21		15	23	30000	15	9900	410
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	3000	< 0.35 U	2.1	24	0.12 J	0.044 J	14000	3.6		2.5 J	15	7300	4.0	3300	400
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	5500	< 0.31 U	3.5	43	0.20 J	0.088 J	30000	7.2		4.9	20	13000	5.9	3000	380
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	6500	< 0.33 U	3.9	43	0.23 J	0.071 J	21000	8.4		5.6	39	15000	7.1	3500	360
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	5600	< 0.36 U	5.7	38	0.22 J	0.064 J	55000	7.7		4.9 J	18	13000	6.0	9800	430
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	4000	< 0.32 U	3.9	25	0.16 J	0.053 J	35000	5.6		3.4 J	13	10000	7.3	6100	220
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	4600	< 0.36 U	2.9	28	0.19 J	0.059 J	39000	6.1		3.8 J	16	10000	5.0	7600	280
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	13000	< 0.41 UT	9.3 T	79	0.59 T	0.056 JT	9500 T	16 T		11 T	16 T	25000	12 T	7000	350
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	4800	0.68 J	7.1	40	0.22 J	0.17 J	21000	6.9		4.9 J	17	13000	7.0	3800	290
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	5800	0.55 J	5.3	36	0.25 J	0.17 J	29000	8.1		5.2 J	19	14000	7.2	4100	270
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	5100	0.83 J	2.7	35	0.19 J	0.16 J	38000	6.6		4.5 J	19	12000	4.8	4100	260
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	6400	0.90 J	3.1	46	0.21 J	0.17 J	34000	7.2		6.5	21	16000	4.8	12000	340
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	4700	1.1	3.1	39	0.18 J	0.15 J	74000	26		4.4 J	17	13000	5.9	10000	350
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	5700	< 0.31 UT	7.0	54 T	0.22 J	0.12 J	36000 T	7.3 T		6.2	23 T	17000 T	12 T	4700 T	530
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	13000	< 0.44 U	8.9	110	0.56	0.073 J	7400	18		13	16	27000	11	5300	460
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	14000	0.72 JT	6.6	88 T	0.62 T	0.20 JT	14000	19 T		12	18 T	26000	12 T	8400 T	400

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	10	560	< 0.034 U	< 0.034 U	73 J		< 0.034 U		7.3	43
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	10	530 J	< 0.034 U	< 0.034 U	69 J		< 0.034 U		7.5	36
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	14	560	0.62 J	< 0.034 U	81 J		< 0.034 U		8.1	37
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	36	1800	< 0.034 U	< 0.034 U	120 J		< 0.034 U		21	74
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.034 U	29	1600	< 0.034 U	< 0.034 U	87 J		< 0.034 U		17	60
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	32	1500	< 0.034 U	< 0.034 U	88 J		< 0.034 U		19	67
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	32	1700 J-	< UJ	< U	100 J		< UJ		19 J-	65 J-
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	0.032 J	28	2000	< 0.69 U	< 0.14 U	100 J		< 0.43 U		18	60
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	0.035 J	29	1700	< 0.69 U	< 0.14 U	97 J		< 0.43 U		17	63
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	0.025 J	9.6	520	0.82 J	< 0.099 U	110 J		< 0.30 U		7.3	44
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.023 U	7.8	440 J	< 0.53 U	< 0.11 U	90 J		< 0.33 U		5.8	40
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.023 U	8.3	530 J	0.80 J	< 0.12 U	82 J		< 0.36 U		6.3	39
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	0.023 J	12	640	< 0.52 U	< 0.11 U	85 J		< 0.33 U		7.6	42
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	0.034 J	20	910	< 0.65 U	< 0.13 U	< 76 U		< 0.41 U		11	48
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.024 U	30	1700	< 0.65 U	< 0.13 U	98 J		< 0.41 U		17	64
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	0.14	29	600	0.65 J	< 0.11 U	91 J		< 0.32 U		11	80
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.018 U	13	520	< 0.44 U	< 0.09 U	71 J		< 0.28 U		7.3	75
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.018 U	15	530	0.63 J	< 0.098 U	84 J		< 0.3 U		7	57
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	< 0.019 U	7.8	500	0.99	< 0.099 U	110 J		< 0.3 U		5.5	28
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	< 0.021 U	12	700	< 0.58 U	< 0.12 U	100 J		< 0.36 U		8	47
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	< 0.025 U	14	650	0.85 J	< 0.099 U	96 J		< 0.3 U		9.1	41
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	< 0.023 U	13	680	0.54 J	< 0.094 U	91 J		< 0.29 U		8.7	38 J-
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	< 0.025 U	12	690	< 0.63 U	< 0.13 U	97 J		< 0.39 U		9.1	36
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.017 U	10	510	< 0.38 U	< 0.078 U	73 J		< 0.24 U		5.8	30
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	< 0.022 U	13	870	< 0.57 U	< 0.12 U	100 J		< 0.36 U		9.2	39
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	< 0.024 U	38	2400	< 0.54 U	< 0.11 U	140 J		< 0.34 U		23	71
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	0.18	37	510	0.6 J	< 0.09 U	100 J		< 0.27 U		13	99
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.023 U	13	700	< 0.47 U	< 0.095 U	92 J		< 0.29 U		8.7	39
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	< 0.028 U	37	2000	< 0.64 U	< 0.13 U	110 J		< 0.4 U		21	75
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	< 0.018 U	15	460	0.50 J	< 0.098 U	65 J		< 0.30 U		6.7	45
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	< 0.020 U	12	490 J	< 0.52 U	< 0.11 U	62 J		< 0.32 U		7.3	49
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	0.027 J	14	490	0.59 J	< 0.10 U	72 J		< 0.31 U		8.3	55
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	< 0.022 U	13	470	0.65 J	< 0.097 U	81 J		< 0.29 U		7.2	50
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	< 0.028 U	34	1900 T	< 0.59 U	< 0.12 U	120 J		< 0.37 U		21	74 T
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.019 U	8.8	480	< 0.47 U	< 0.096 U	69 J		0.45 J		7.1	39
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.022 U	8.3	430	< 0.33 U	< 0.068 U	75 J		0.23 J		6.9	36
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.023 U	13	430 J	< 0.53 U	< 0.11 U	62 J		0.71 J		9.4	70
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	0.024 J	23	1200	< 0.39 U	< 0.079 U	83 J		0.95 J		15	48
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.022 U	8.8	440 J	< 0.51 U	< 0.10 U	78 J		0.39 J		6.9	51
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.020 U	10	450	< 0.41 U	< 0.083 U	76 J		0.49 J		7.8	47
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.021 U	10	410 J	< 0.48 U	< 0.098 U	64 J		0.63 J		9.4	44
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.026 U	27 T	1600 T	< 0.60 UT	< 0.12 UT	100 JT		0.97 JT		18 T	58 T
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.023 U	8.0	430	< 0.44 U	< 0.090 U	85 J		0.38 J		7.1	39
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated	< 0.021 U	12	460 J	< 0.51 U	< 0.1 U	64 J		< 0.32 U		7.8	46
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated	< 0.018 U	14	630	0.67 J	< 0.097 U	77 J		< 0.3 U		9.3	52
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated	< 0.021 U	15	480 J	0.54 J	< 0.11 U	69 J		< 0.33 U		8.9	56
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated	< 0.018 U	14	490 J	0.71 J	< 0.11 U	70 J		< 0.32 U		8.4	53
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated	< 0.025 U	22	880	< 0.58 U	< 0.12 U	74 J		< 0.36 U		13	65
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.019 U	14	730	< 0.51 U	< 0.10 U	73 J		0.78 J		11	57
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.023 U	11	570	< 0.49 U	< 0.10 U	73 J		0.62 J		9.6	49
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.023 U	10	450 J	< 0.50 U	< 0.10 U	< 59 U		0.48 J		8.9	45
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.023 U	12	510	< 0.52 U	< 0.11 U	68 J		0.49 J		9.2	52
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.020 U	8.8	390 J	< 0.59 U	< 0.12 U	82 J		0.43 J		6.8	41
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217043	Not Excavated											
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-32-34	5/13/2021	856.89	32 - 34 ft	1801217043	Not Excavated											
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.019 U	6.2	260 J	< 0.58 U	< 0.12 U	< 68 U		0.50 J		4.7 J	30
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.023 U	11	380 J	< 0.55 U	< 0.11 U	< 65 U		0.51 J		7.7	50
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.018 U	12	430 J	< 0.50 U	< 0.10 U	82 J		0.55 J		8.6	81
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.026 U	35	2000	< 0.54 U	< 0.11 U	120 J		1.2 J		23	73
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.023 U	7.0	300 J	< 0.53 UT	< 0.11 U	< 63 U		< 0.33 U		4.1 J	28
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.019 U	13	420 J	< 0.46 UT	< 0.095 U	< 54 U		< 0.29 U		7.9	50
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.021 U	15	400 J	< 0.50 UT	< 0.10 U	< 59 U		< 0.31 U		8.6	57
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.023 U	14	560	0.77 JT	< 0.11 U	78 J		< 0.34 U		7.8	45
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.022 U	9.3	390 J	< 0.49 UT	< 0.10 U	63 J		< 0.30 U		6.5	39
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.022 U	11	440 J	< 0.55 UT	< 0.11 U	< 65 U		< 0.34 U		6.8	42
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	0.033 J	27 T	1700	< 0.62 WARN	< 0.13 UT	96 JT		< 0.39 UT		17 T	57 T
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.024 U	12	580	< 0.55 U	< 0.11 U	< 64 U		0.77 J		9.4	47
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.024 U	13	790	< 0.56 U	< 0.11 U	92 J		0.70 J		11	47
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.018 U	11	560	< 0.49 U	< 0.10 U	74 J		0.56 J		9.3	43
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.020 U	10	600	< 0.57 U	< 0.12 U	160 J		0.67 J		27	45
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.020 U	12	430 J	< 0.49 U	< 0.10 U	88 J		0.38 J		7.8	38
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.021 U	15 T	530	< 0.48 U	< 0.097 U	65 J		< 0.30 U		9.8 T	49 T
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.029 U	30	1400	< 0.66 U	< 0.13 U	110 J		< 0.41 U		17	65
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.023 UT	29 T	1900 T	< 0.52 UT	< 0.11 UT	100 JT		1.1 JT		20 T	57 T

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted										13	350	7.2	2.5		30	1		50		63		1600
Restricted - Residential										16	400	72	4.3		110	110		270		400		2000
Protection of Groundwater										16	820	47	7.5		19	19		1720		450		2000
Potential to exhibit the characteristic of toxicity										100	2000		20		100					1000		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	3200	< 0.22 U	3.2	23	0.14 J	0.066 J	35000	4.8		3.3	11	8000	5.1	4800	250
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	5100	< 0.31 UT	4.3 T	33 T	0.24 JT	0.096 JT	15000	8.0 T		5.1	20 T	13000	7.2 T	3000 T	450
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	4000	< 0.30 U	3.3	25	0.17 J	0.091 J	50000	6.3		3.7 J	11	9800	4.8	3300	400
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	6400	< 0.32 U	3.5	38	0.23 J	0.081 J	41000	8.6		5.8	17	15000	6.2	4000	270
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	5400	< 0.30 U	2.8	32	0.20 J	0.095 J	33000	7.9		4.9	17	12000	4.8	5600	330
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	4900	< 0.31 U	2.8	25	0.13 J	0.087 J	110000	5.9		4.0 J	18	11000	3.8	3800	310
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	3100	< 0.28 U	2.8	23	0.13 J	0.087 J	27000	4.4		2.9 J	10	7700	4.8	3600	210
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	4400	< 0.36 U	3.1	32	0.17 J	0.070 J	42000	5.7		3.9 J	15	11000	5.3	3300	300
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	13000	< 0.36 U	8.0	78	0.60	0.074 J	11000	17		12	17	25000	12	7500	370
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	4300	< 0.40 U	2.9	24	0.15 J	0.065 J	16000	5.1		3.2 J	11	10000	4.9	3500	150
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	3800	< 0.35 U	10	23	0.15 J	0.092 J	31000	5.2		3.5 J	16	10000	5.2	4500	260
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	3600	< 0.35 U	4.9	25	0.15 J	0.056 J	36000	5.2		3.0 J	11	9000	4.5	4900	200
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	3900	< 0.37 U	3.6	24	0.14 J	0.10 J	41000	5.7		3.4 J	16	9900	4.7	4000	330
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	13000	< 0.37 U	9.6	130	0.56	0.086 J	12000	17		12	17	27000	11	6700	720
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	5300	< 0.36 U	3.1	39	0.19 J	0.087 J	33000	7.9		4.7 J	16	12000	5.2	6900	500
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	5200	< 0.38 U	3.0	43	0.16 J	0.078 J	25000	8.5		4.3 J	18	12000	6.1	6400	340
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	4000	< 0.31 U	3.2	31	0.15 J	0.091 J	77000	6.1		3.7 J	16	9900	4.2	12000	330
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	4600	< 0.36 U	4.3	45	0.18 J	0.10 J	43000	7.8		4.6 J	25	12000	5.0	4900	370
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	3600	< 0.37 U	3.3	21 J	0.14 J	0.30 J	32000	4.3		2.8 J	11	9000	62	5100	320
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	2900	< 0.34 U	2.7	22	0.10 J	0.079 J	55000	4.1		2.6 J	10	7200	3.8	5400	290
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	9900	< 0.32 U	6.1	69	0.46	0.073 J	15000	14		9.3	15	20000	9.5	7500	430
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	5700	< 0.33 U	4.1	44	0.21 J	0.20 J	57000	8.6		4.8	15	12000	7.2	6700	390
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	4700	< 0.034 U	3.4	34	0.16 J	0.064 J	33000	8.7		3.9 J	21	11000	6.5	13000	370
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	6000	< 0.034 U	3.5	29	0.2 J	< 0.034 U	38000	13		4.8 J	19	14000	8.5	8900	290
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	4400	< 0.034 U	4.3	25	0.16 J	0.13 J	30000	7		3.8 J	18	11000	12	11000	360
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	4300	< 0.034 U	4.7	28	0.18 J	0.92	48000	5.3		4.2 J	21	9900	6.2	6200	520
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	4200	< 0.034 U	4	54	0.17 J	0.04 J	13000	5.2		4.9 J	11	11000	4.2	1900	830
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	5900	< 0.034 U	3.2	48	0.2 J	0.049 J	38000	7.5		5.4	19	14000	10	12000	480
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	4000	< 0.034 U	3.8	27	0.18 J	0.039 J	37000	5.8		3.8 J	13	10000	5.6	7300	290
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	4000	< 0.034 U	2.7	23 J	0.14 J	0.068 J	51000	5.5		3.7 J	12	9400	6.6	9200 J	350
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	4300	< 0.034 U	4.3	28	0.16 J	< 0.034 U	31000	5.9		3.8 J	12	10000	5.4	4400 J	280
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	4700	< 0.034 U	4.4	31	0.17 J	0.044 J	29000	6.3		4.2 J	15	11000	5.5	5200	350
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	4300	0.39 J	3.3	27 J-	0.18 J	0.049 J	46000	5.4 J-		4 J	17 J-	9600	7.7	5600 J-	450
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	15000	0.61 J	9.8	88	0.63	< 0.044 U	16000	18		13	21	27000	14	9200	480
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	16000	0.48 J	11	120	0.74	< 0.034 U	8800	20		14	20	28000	16	7300	410
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	4700 J	< 0.034 U	4.2	68 J-	0.18 J	0.059 J	44000 J	8.1		4.5	16	11000	8.6	12000	370 J
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	4600	< 0.034 U	3.5	28	0.15 J	0.11 J	41000	6		4.5 J	18	11000	6.1	11000	310
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	4600	< 0.33 U	4.2	36	0.18 J	0.1 J	51000	6.3		4.2 J	12	12000	5.9	5800	360
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	4400	< 0.31 U	3.8	34	0.15 J	0.065 J	42000	6.1		3.9 J	15	10000	6.3	6100	350
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	4900	< 0.23 U	4	39	0.18 J	0.053 J	33000	7		5.3	15	12000	6	4200	380
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	5000	< 0.32 U	3.8	39	0.2 J	0.055 J	26000	8.9		4.4 J	16	12000	7.2	6500	420
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	13000	< 0.034 U	8.4	87	0.45 J	< 0.034 U	40000	16		9.5	35	27000	14	12000	720
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	8300	< 0.034 U	4	44	0.28 J	< 0.034 U	25000	11		5.5	20	15000	9.8	5000	310
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	6600	< 0.034 U	4.9	50	0.24 J	0.056 J	41000	8.4		5.4	22 J	15000	7.3	14000	570
Football Field	SSHS-B4165	DUP-39	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	5900	< 0.034 U	3.6	37 J	0.22 J	0.092 J	57000 J	7.5		5.1	17	12000	7.1	5600 J-	370 J
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	4400	< 0.034 U	4.1	44	0.21 J	0.1 J	55000	6.5		4.1	13 J	12000	7	8500	430
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	6300	< 0.034 U	3.8	41	0.23 J	0.044 J	22000 J	9		5.1	24	14000	7.2	4700	440
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	5900	< 0.034 U	5.5	60	0.2 J	0.067 J	14000	7.4		5.2	13	15000	7.6	4400	720
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	6300	< 0.034 U	6.3	61	0.3 J	0.064 J	7000	9.7		6.2	21	17000	12	3700	710
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	5500 T	< 0.24 U	3.5	39	0.15 J	< 0.059 U	38000	8.6		5.4	20	13000	4.8	5600	480 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	3500 T	< 0.16 U	4.6	24	0.14 J	0.085 J	45000	5.0		3.9	17	9600	5.9	5700	240 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	4800 T	< 0.27 U	5.2	30	0.14 J	< 0.065 U	28000	5.9		4.2 J	16	12000	6.2	4100	300 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	3900 T	< 0.29 U	2.8	23	0.14 J	< 0.070 U	28000	5.1		3.6 J	14	9600	3.8	2600	220 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	3500 T	< 0.21 U	3.4	29	0.12 J	< 0.052 U	28000	4.8		3.3 J	14	8500	4.3	3700	230 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	11000 T	< 0.34 U	13	70	0.48	< 0.081 U	14000	16		12	20	25000	12	7400	590 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	3900 T	< 0.35 U	3.9	30	0.16 J	0.10 J	56000	5.4		3.9 J	19	10000	11	5100	330 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	4500 T	< 0.25 U	5.8	30	0.21 J	0.097 J	32000	6.6		5.0	21	13000	7.9	7300	190 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	4200 T	< 0.18 U	3.7	31	0.15 J	< 0.044 U	23000	7.8		4.2	18	11000	7.2	4200	200 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	4300 T	< 0.22 U	4.9	32	0.16 J	< 0.053 U	40000	28		4.5	18	12000	7.7	8600	330 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508423	Not Excavated									< 0.25 U						
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	3300 T	< 0.23 U	3.1	22	0.13 J	< 0.055 U	30000	5.2		3.2 J	15	8300	4.6	4400	200 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	3800 T	< 0.25 U	4.0	26	0.16 J	< 0.061 U	34000	5.3		3.8 J	15	9400	5.4	5700	220 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	4000 T	< 0.22 U	3.2	21	0.14 J	< 0.053 U	36000	5.4		3.5 J	16	10000	5.2	9400	200 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	14000 T	< 0.30 UT	12	95 T	0.62	< 0.074 U	12000	20		15	21	31000	14	8200 T	500 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508423	Not Excavated									< 0.27 U						
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated			8.8	163	< 0.61 U	< 0.61 U		13.3			64.7		74.1		
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated			2.3	21.6	< 0.56 U	< 0.56 U		4.6			12.4		8.1		

TABLE 5-7B
Deep Soil Results - Remedial Investigation - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium	Tin	Vanadium	Zinc
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.18	30		3.9	2						109
Restricted - Residential								0.81	310		180	180						10000
Protection of Groundwater								0.73	130		4	8.3						2480
Potential to exhibit the characteristic of toxicity								4			20	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.023 U	8.3	410	0.35 J	< 0.069 U	76 J		< 0.21 U		6.2	31
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	0.026 J	13 T	620 T	< 0.46 UT	< 0.095 UT	< 54 U		< 0.29 UT		8.8 T	43 T
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	0.027 J	10	540	0.64 J	< 0.093 U	75 J		< 0.28 U		7.8	35
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	0.023 J	16	570	0.49 J	< 0.098 U	81 J		< 0.30 U		9.6	50
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	0.024 J	13	430 J	0.50 J	< 0.094 U	67 J		< 0.29 U		7.4	43
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	0.023 J	11	400 J	0.86 J	< 0.096 U	69 J		< 0.29 U		6.7	34
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	0.025 J	7.3	420	< 0.43 U	< 0.087 U	70 J		< 0.26 U		5.7	29
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	0.023 J	10	480 J	< 0.55 U	< 0.11 U	84 J		< 0.34 U		7.6	42
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	0.040	28	1800	< 0.55 U	< 0.11 U	98 J		< 0.34 U		18	56
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.023 U	8.6	420 J	< 0.61 U	< 0.12 U	88 J		< 0.38 U		6.7	37
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.024 U	9.3	390 J	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U		6.2	38
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.020 U	7.9	460 J	< 0.54 U	< 0.11 U	67 J		< 0.33 U		6.5	34
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.022 U	9.2	560	< 0.57 U	< 0.12 U	80 J		< 0.35 U		7.4	40
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.026 U	28	1600	< 0.57 U	< 0.12 U	97 J		< 0.35 U		17	65
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.022 U	13	560	< 0.54 U	< 0.11 U	82 J		< 0.34 U		8.5	46
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	0.023 J	12	480 J	< 0.58 U	< 0.12 U	68 J		< 0.36 U		7.7	48
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	0.022 J	10	490	0.84 J	< 0.097 U	70 J		< 0.30 U		7.3	32
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	0.023 J	13	450 J	< 0.54 U	< 0.11 U	71 J		< 0.34 U		7.8	46
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.022 U	7.5	400 J	< 0.55 U	< 0.11 U	67 J		< 0.35 U		5.3 J	76
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.023 U	7.2	390 J	0.80 J	< 0.11 U	68 J		< 0.32 U		5.2	32
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	0.029 J	23	1300	< 0.48 U	< 0.098 U	81 J		< 0.30 U		14	49
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	0.037	11	630	< 0.50 U	< 0.10 U	78 J		0.49 J		9.4	57
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	14	620	< 0.034 U	< 0.034 U	84 J		< 0.034 U		8.4	39
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	23	630	< 0.034 U	< 0.034 U	66 J		< 0.034 U		9.5	46
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	11	490	< 0.034 U	< 0.034 U	75 J		< 0.034 U		7.9	63
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	13	500 J	0.66 J	< 0.034 U	64 J		< 0.034 U		6.8	45
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	27	320 J	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U		6.1	57
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	21	640	0.58 J	< 0.034 U	82 J		< 0.034 U		9.7	44
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.034 U	9.4	610	0.73 J	< 0.034 U	83 J		< 0.034 U		7.7	35
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	13	410 J	< 0.034 U	< 0.034 U	87 J		< 0.034 U		7.1	34
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	13	590 J	< 0.034 U	< 0.034 U	76 J		< 0.034 U		7.5	35
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	15	560	< 0.034 U	< 0.034 U	75 J		< 0.034 U		7.9	42
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	11	530	< 0.034 U	< 0.034 U	63 J		< 0.034 U		6.8	39 J-
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.026 U	32	1800	< 0.62 U	< 0.13 U	97 J		< 0.38 U		20	62
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.034 U	34	2000	< 0.034 U	< 0.034 U	95 J		< 0.034 U		21	64
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	11	530	0.71 J	< 0.034 U	92 J		< 0.034 U		8.2	42 J
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.034 U	11	490 J	1	< 0.034 U	81 J		< 0.034 U		7.3	61
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.019 U	11	520	1	< 0.1 U	81 J		< 0.31 U		7.8	45
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.022 U	9.9	480	0.85 J	< 0.095 U	85 J		< 0.29 U		6.9	38
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.019 U	13	470	0.47 J	< 0.072 U	60 J		< 0.22 U		7.5	43
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.022 U	11	640	0.53 J	< 0.098 U	59 J		< 0.3 U		8.6	43
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	26	1300	< 0.034 U	< 0.034 U	240 J		< 0.034 U		20	95
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	15	740	< 0.034 U	< 0.034 U	250 J		< 0.034 U		13	48
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	15	690	0.66 J	< 0.034 U	89 J		< 0.034 U		10	55
Football Field	SSHS-B4165	DUP-39	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	14	730 J-	0.47 J	< 0.034 U	81 J		< 0.034 U		8.6	43 J
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	11	660	0.62 J	< 0.034 U	85 J		< 0.034 U		7.2	37
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	13	600	< 0.034 U	< 0.034 U	74 J		< 0.034 U		9.1	54
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	14	640	0.82 J	< 0.034 U	93 J		< 0.034 U		9.5	75
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	17	860	< 0.034 U	< 0.034 U	120 J		< 0.034 U		12	61
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	< 0.020 U	13	320 J	0.70 J	< 0.083 U	70 J		< 0.23 U		8.6	45 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.022 U	11	340	0.57	< 0.055 U	75 J		< 0.15 U		6.4	39 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.019 U	11	350 J	0.46 J	< 0.092 U	72 J		< 0.25 U		8.3	37 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.015 U	9.8	330 J	< 0.44 U	< 0.099 U	79 J		< 0.27 U		6.0	35 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.016 U	8.4	330 J	0.36 J	< 0.074 U	82 J		< 0.20 U		5.5	37 B
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.020 U	27	990	< 0.51 U	< 0.12 U	100 J		< 0.31 U		15	59 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.025 U	11	440 J	0.81 J	< 0.12 U	98 J		< 0.33 U		6.6	41 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.022 U	14	520	0.78 J	< 0.087 U	86 J		< 0.24 U		7.9	60 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.015 U	11	290 J	0.45 J	< 0.062 U	66 J		< 0.17 U		6.5	39 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.019 U	13	400	0.49 J	< 0.075 U	86 J		< 0.20 U		7.8	42 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508423	Not Excavated											
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.022 U	8.0	330 J	0.40 J	< 0.078 U	78 J		< 0.21 U		5.1	37 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	< 0.018 U	9.0	410 J	0.76 J	< 0.087 U	90 J		< 0.24 U		6.7	42 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.018 U	9.7	280 J	0.64 J	< 0.075 U	71 J		< 0.21 U		6.5	37 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.026 U	34	1300 T	< 0.46 U	< 0.10 U	120 J		< 0.29 U		19	70 BT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508423	Not Excavated											
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated	< 0.06 U	114		< 0.6 U	< 1.22 U						161
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated	< 0.05 U	9.7		< 0.55 U	< 1.12 U						37.3

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	< 42 U																			
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated	< 8.3 U																			
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	< 41 U																			
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3559	DUP-25	1/29/2021	855.35	16 - 18 ft	180-116665-1	Not Excavated	< 39 U	< U																		
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.39 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	< 0.034 U	< 0.034 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated			ND	< 0.027 U	< 0.021 U	< 0.17 U	< 0.024 U	< 0.21 U	< 0.17 U	< 0.058 U	< 0.042 U	< 0.041 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.2 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated			0.21	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 UJ	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated			0.267	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.049 J	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated			0.042	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated			0.344	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.074 J	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated			0.4	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	0.08	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated			0.244	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.045 J	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated			0.028	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated			0.15	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.054 J	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated			0.89	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	0.19	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.038 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated			0.387	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.052 J	0.034 J	0.046 J	< 0.021 U	0.037 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated			0.78	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.15	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated			0.73	< 0.019 U	< 0.015 U	< 0.018 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.042 U	0.14	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.038 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated			0.428	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.066 J	0.033 J	0.033 J	< 0.021 U	0.026 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7																			
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	0.22 J	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated																			
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated																			
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated																			
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B3559	DUP-25	1/29/2021	855.35	16 - 18 ft	180-116665-1	Not Excavated																			
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.092 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.097 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.15 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.14 U	< 0.17 U	< 0.034 U	< 0.24 U	< 0.034 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.16 U	< 0.052 U	< 0.06 U	< 0.17 U	< 0.44 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.19 U	< 0.21 U	< 0.27 U	< 0.81 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.048 U	< 0.055 U	< 0.16 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 UJ	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.078 J	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.14	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.079 J	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.096	< 0.047 U	< 0.016 U	< 0.34 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.38	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.019 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.085	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.31	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	0.29	< 0.043 U	< 0.015 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.097	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U

DRAFT

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.14 U	< 2.3 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.15 U	< 2.4 U	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	< 0.022 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated																			
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated																			
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated																			
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.022 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Football Field	SSHS-B3559	DUP-25	1/29/2021	855.35	16 - 18 ft	180-116665-1	Not Excavated																			
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.022 U	< 2.2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.23 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.23 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.23 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.025 U	< 2.5 U	< 0.06 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.3 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.2 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.13 U	< 2.1 U	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.3 U	< 0.22 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.13 U	< 2.1 U	< 0.21 U			< 0.11 UJ	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.013 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.2 U	< 0.21 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.15 U	< 2.4 U	< 0.23 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.15 U	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.3 U	< 0.22 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.15 U	< 2.4 U	< 0.23 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.15 U	< 2.4 U	< 0.23 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.18 U	< 2.9 U	< 0.28 U			< 0.15 UJ	< 0.025 U	< 0.018 U	< 0.034 U	< 0.027 U	< 0.048 U	< 0.17 U	< 0.047 U	< 0.13 U	< 0.14 U	< 0.18 U	< 0.022 U		< 0.018 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.15 U	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.15 U	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.17 U	< 2.7 U	< 0.26 U			< 0.13 UJ	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.16 U	< 0.021 U		< 0.017 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.14 U	< 2.2 U	< 0.21 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.16 U	< 2.5 U	< 0.24 U			< 0.12 UJ	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.15 U	< 0.019 U		< 0.016 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.16 U	< 2.5 U	< 0.24 U			< 0.13 UJ	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.019 U		< 0.016 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.16 U	< 2.6 U	< 0.25 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		< 0.016 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.036 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.023 U	< 2 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.025 U	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.025 U	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.026 U	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.022 U	< 1.9 U	< 0.053 U			< 0.11 U	0.056 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.051 U			< 0.1 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U	< 0.033 U	< 0.096 U	< 0.098 U	< 0.017 U	< 0.016 U		< 0.013 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.026 U	< 2.4 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.017 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.022 U	< 2 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.022 U	< 1.9 U	< 0.053 U			< 0.11 U	0.063 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.8	100	0.33	100					
Restricted - Residential																	6.7	100	100	100					
Protection of Groundwater																	0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																		
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.17 U	< 0.093 U	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.18 U	< 0.1 U	< 0.15 U	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated																		
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated																		
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated																		
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3559	DUP-25	1/29/2021	855.35	16 - 18 ft	180-116665-1	Not Excavated																		
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.093 U	< 0.14 U	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.092 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.087 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.094 U	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.088 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.094 U	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.097 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.097 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.094 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.21 U	< 0.12 U	< 0.17 U	< 0.17 U	< 0.17 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.75 U	< 0.025 U	< 0.14 U	< 0.022 U		< 0.19 U	< 0.2 U	< 0.16 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.096 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.095 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.2 U	< 0.11 U	< 0.16 U	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.18 U	< 0.1 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.18 U	< 0.1 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.19 U	< 0.1 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.02 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.21		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.14		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.042 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.13		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.19		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.12		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.028 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.32		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.031 U	< 0.023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.077		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.32		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.15 U	< 0.085 U	< 0.016 U	< 0.12 U	< 0.053 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.3		< 0.014 U	< 0.14 U	< 0.024 U	< 0.018 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.11		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**	**Benzo(a)pyrene (BaP)**	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated			0.438	< 0.02 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	0.098	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated			0.039	< 0.019 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated			9.8	< 0.11 U	< 0.082 U	< 0.1 U	< 0.097 U	< 0.82 U	< 0.078 U	< 0.23 U	0.51	< 0.16 U	< 0.092 U	< 0.11 U	< 0.081 U	< 0.089 U	< 0.068 U	< 0.14 U	< 2 U	< 0.13 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated			3.79	< 0.1 U	< 0.078 U	< 0.096 U	< 0.092 U	< 0.78 U	< 0.074 U	< 0.22 U	0.24 J	< 0.15 U	< 0.087 U	< 0.11 U	< 0.077 U	< 0.085 U	< 0.064 U	< 0.13 U	< 1.9 U	< 0.12 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated			3.129	< 0.1 U	< 0.078 U	< 0.097 U	< 0.092 U	< 0.78 U	< 0.075 U	< 0.22 U	0.28 J	< 0.15 U	< 0.088 U	< 0.11 U	< 0.077 U	< 0.085 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.12 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated			0.523	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	0.047 J	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated			0.082	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated			0.058	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 UT	< 0.017 U	< 0.013 U	< 0.027 UT	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	< 0.041 U	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated			1.131	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.05 U	0.11	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated			0.48	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	0.13	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated			0.34	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.044 U	0.07 J	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated			0.024	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated			0.697	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	0.097	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated			0.513	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	0.097	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	< 0.034 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.051 U	< 0.034 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated			0.293	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	0.06 J	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	< 0.034 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.051 U	< 0.034 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated			ND	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated			0.4	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.06 J	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated			0.37	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.11	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated			0.74	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	0.11	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	< 0.034 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.023 U	< 0.19 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.022 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.024 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.021 U	< 0.034 U	< 0.025 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.023 U	< 0.029 U	< 0.021 U	< 0.023 U	< 0.017 U	< 0.035 U	< 0.51 U	< 0.033 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated			ND	< U	< U	< U	< U	< U	< U		< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated			0.615	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	0.085	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated			0.73	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	0.17	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated			0.583	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	0.083	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.023 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.024 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.5 U	< 0.033 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.025 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	< 0.041 U	< 0.039 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ethe	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.16	< 0.044 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.02 U	< 0.037 U	< 0.043 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.043 U	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.25 U	< 0.73 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 1.3 U	< 1.2 U	< 0.087 U	< 0.13 U	< 0.088 U	< 0.086 U	< 0.087 U	< 0.11 U	2.8	< 0.24 U	< 0.082 U	< 1.7 U	< 0.14 U	< 0.65 U	< 0.12 U	< 0.14 U	< 0.82 U	< 1.1 U	< 3.2 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 1.2 U	< 1.2 U	< 0.083 U	< 0.12 U	< 0.084 U	< 0.081 U	< 0.082 U	< 0.11 U	1.3	< 0.23 U	< 0.078 U	< 1.7 U	< 0.14 U	< 0.62 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 1.2 U	< 1.2 U	< 0.083 U	< 0.12 U	< 0.084 U	< 0.082 U	< 0.083 U	< 0.11 U	1.2	< 0.23 U	< 0.078 U	< 1.7 U	< 0.14 U	< 0.62 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.21	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.051 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.25 U	< 0.73 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 UT
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	0.19 J	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.05 U	< 0.058 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.033 U	< 0.2 U	< 0.26 U	< 0.78 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.32	< 0.034 U	< 0.018 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.2	< 0.034 U	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.2 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.034 U	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.23	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.027 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.11	< 0.034 U	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.25 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18 J	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 UJ	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.26	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.034 U	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.015 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.021 U	< 0.025 U	< 0.034 U	< 0.2 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.027 U	< 0.033 U	< 0.034 U	< 0.26 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.05 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.26 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.31 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.053 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.03 U	< 0.035 U	< 0.034 U	< 0.28 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.021 U	< 0.025 U	< 0.034 U	< 0.2 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.3	< 0.034 U	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.19	< 0.034 U	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.021 U	< 0.026 U	< 0.034 U	< 0.2 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.05 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.028 U	< 0.033 U	< 0.034 U	< 0.26 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.026 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.3 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.052 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.27 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.05 U	< 0.058 U	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.034 U	< 0.2 U	< 0.26 U	< 0.78 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2,6-Dinitrotoluene	**2,4-Dinitrophenol**	**2,4-Dinitrotoluene**	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW827**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**	**Hexachloroethane**	**Indeno (1,2,3-cd)pyrene**	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.051 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.097 U	< 0.1 U	< 0.017 U	< 0.016 U		< 0.013 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.051 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.017 U	< 0.034 U	< 0.097 U	< 0.099 U	< 0.017 U	< 0.016 U		< 0.013 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.051 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.017 U	< 0.034 U	< 0.097 U	< 0.099 U	< 0.017 U	< 0.016 U		< 0.013 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.024 U	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.026 U	< 2.3 UJ	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.021 U	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.12 U	< 10 U	< 0.28 U			< 0.58 U	0.85	0.44	< 0.13 U	< 0.11 U	< 0.19 U	< 0.096 U	< 0.19 U	< 0.53 U	< 0.55 U	< 0.095 U	0.19 J		< 0.073 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.11 U	< 9.8 U	< 0.27 U			< 0.55 U	0.53	0.22 J	< 0.13 U	< 0.1 U	< 0.18 U	< 0.091 U	< 0.18 U	< 0.51 U	< 0.52 U	< 0.09 U	< 0.085 U		< 0.069 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.11 U	< 9.9 U	< 0.27 U			< 0.56 U	0.47	0.22 J	< 0.13 U	< 0.1 U	< 0.18 U	< 0.092 U	< 0.18 U	< 0.51 U	< 0.52 U	< 0.091 U	< 0.085 U		0.079 J
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.052 U			< 0.11 U	0.084	0.042 J	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	0.02 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	0.02 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.024 U	< 2.2 U	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.022 U	< 2 UT	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 UT	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.027 U	< 2.4 U	< 0.065 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.028 U	< 2.5 U	< 0.068 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	< 0.045 U	< 0.13 U		< 0.023 U	< 0.022 U	< 0.13 U	< 0.018 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.061 U			< 0.13 U	0.091	0.36	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	0.21	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.064 U			< 0.13 U	0.066 J	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.06 U			< 0.12 U	0.03 J	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated	< U	< U	< U			< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U		< U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	0.16 J	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.057 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.053 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.051 U			< 0.034 U	< 0.018 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.059 U			< 0.034 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.059 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.061 U			< 0.034 U	< 0.021 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.06 U			< 0.034 U	< 0.021 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.066 U			< 0.034 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.068 U			< 0.034 U	< 0.024 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.072 U			< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< U	< U			< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U		< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.052 U			< 0.034 U	< 0.018 U	0.12	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.052 U			< 0.034 U	< 0.018 U	0.1	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.062 U			< 0.034 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.062 U			< 0.034 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.068 U			< 0.034 U	< 0.024 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.064 U			< 0.034 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.07 U			< 0.034 U	< 0.025 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.027 U	< 2.4 U	< 0.065 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	< 0.017 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.028 U	< 2.5 U	< 0.068 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	< 0.045 U	< 0.13 U		< 0.023 U	< 0.022 U	< 0.13 U	< 0.018 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2-Nitroaniline	**3-Nitroaniline**	**4-Nitroaniline**	**Nitrobenzene**	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**	**Pyridine**	**1,2,4,5-Tetrachlorobenzene**	**2,3,4,6-Tetrachlorophenol**	**2,4,5-Trichlorophenol**	**2,4,6-Trichlorophenol**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.8	100	0.33	100					
Restricted - Residential																	6.7	100	100	100					
Protection of Groundwater																	0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																		
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.15 U	< 0.086 U	< 0.017 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.18		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.15 U	< 0.086 U	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.039 J		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.15 U	< 0.086 U	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.85 U	< 0.47 U	< 0.091 U	< 0.68 U	< 0.3 U	< 1.3 U		< 0.13 U	< 0.62 U	< 3 U	3.5	< 0.57 U	1.7		< 0.081 U	< 0.78 U	< 0.13 U	< 0.1 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.81 U	< 0.45 U	< 0.086 U	< 0.65 U	< 0.28 U	< 1.2 U		< 0.12 U	< 0.59 U	< 2.9 U	1.5	< 0.54 U	< 0.084 U		< 0.077 U	< 0.74 U	< 0.13 U	< 0.097 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.81 U	< 0.45 U	< 0.086 U	< 0.65 U	< 0.28 U	< 1.2 U		< 0.12 U	< 0.59 U	< 2.9 U	0.88	< 0.54 U	< 0.084 U		< 0.077 U	< 0.74 U	< 0.13 U	< 0.098 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.16 U	< 0.087 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.14		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.031 J	< 0.11 U	0.031 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.038 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.072 U	< 0.32 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.14 U	< 0.021 U		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.25		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.15		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.15		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.024 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	0.16		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	0.17		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.093		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	38 - 40 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U		< U	< U	< U	< U	< U	< U		< U	< U	< U	< U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.28		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	< 0.016 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.034 U	< 0.31 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.022 U	< 0.034 U	< 0.034 U	< 0.32 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.023 U	< 0.034 U	< 0.034 U	< 0.33 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.023 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U		< U	< U	< U	< U	< U	< U		< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	0.2		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.26		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	0.21		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.022 U	< 0.034 U	< 0.034 U	< 0.32 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.023 U	< 0.034 U	< 0.034 U	< 0.33 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.022 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	< 0.024 U	< 0.14 U	< 0.021 U		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated			0.248	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	0.068 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	< 0.04 U	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated			0.036	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated			2.28	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.42	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated			1.36	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	0.23	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated			3.241	0.032 J	0.041 J	< 0.02 U	0.081 J	< 0.16 U	< 0.015 U	< 0.046 U	0.29	0.26	0.35	0.12	0.18	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated			0.323	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.053 J	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated			0.443	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.073	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.055 U	< 0.04 U	< 0.038 U	< 0.022 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U	< 0.038 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated			2.779	< 0.021 UJ	0.032 J	< 0.02 U	0.063 J	< 0.16 U	< 0.015 U	< 0.045 U	0.23	0.21	0.3	0.079	0.18	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.057 U	< 0.041 U	< 0.04 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated			0.52	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.17	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated			0.4	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	0.12	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated			0.79	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.2	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated			0.452	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.092	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated			0.6	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.15	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated			0.415	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.095	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated			0.018	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Butylbenzyl phthalate	**Caprolactam**	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ethe**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**	**3,3-Dichlorobenzidine**	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	0.13 J	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.03 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.05 U	< 0.057 U	< 0.02 U	< 0.42 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.033 U	< 0.2 U	< 0.26 U	< 0.77 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 UJ	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	1.1	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.6	< 0.046 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	0.047 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.33	< 0.047 UJ	0.026 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.1	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.2	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.03 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	< 0.049 U	< 0.056 U	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.033 U	< 0.19 U	< 0.26 U	< 0.76 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.59 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.75 U
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	0.037 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.29	0.049 J	0.023 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	< 0.31 U	< 0.3 U	< 0.021 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.028 U	< 0.051 U	< 0.058 U	< 0.02 U	< 0.43 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.79 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.35	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.28	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.73 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.24	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.16	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.22	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.18	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	< 0.29 U	< 0.28 UT	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.019 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 UT
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.045 U	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.051 U	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 UT
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.24 J	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.42	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	0.35 J	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	0.44	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.18 J	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.05 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	0.28 J	< 0.23 U	< 0.67 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	< 0.014 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.022 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.022 U	< 1.9 U	< 0.053 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.028 U	< 2.5 U	< 0.067 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.023 U	< 0.045 U	< 0.13 U		< 0.023 U	< 0.021 U	< 0.13 U	< 0.017 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	0.036 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	0.14	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	0.17	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.023 U	< 2 U	< 0.056 U			< 0.11 U	0.5	0.024 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	0.14	< 0.11 U	< 0.11 U	< 0.019 U	0.031 J		0.034 J
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	< 0.025 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	< 0.025 U	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	< 0.025 U	< 2.3 UJ	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	< 0.027 U	< 2.4 U	< 0.066 U			< 0.14 U	< 0.023 U	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.023 U	< 0.044 U	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	< 0.027 U	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	< 0.027 U	< 2.4 U	< 0.065 U			< 0.14 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	0.43	< 0.014 UJ	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	0.13	< 0.1 U	< 0.11 U	< 0.019 U	0.036 J		0.048 J
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.026 U	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	< 0.028 U	< 2.5 U	< 0.069 U			< 0.14 U	< 0.024 U	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.024 U	< 0.045 U	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	< 0.021 U	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	< 0.025 U	< 2.3 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		< 0.016 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	< 0.025 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.027 U	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.023 U	< 2 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.023 U	< 2 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	< 0.023 U	< 2 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	< 0.026 U	< 2.3 UT	< 0.064 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.022 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.022 U	< 2 U	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.022 U	< 2 U	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.026 U	< 2.3 UT	< 0.062 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated	< 0.022 U	< 2 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated	< 0.023 U	< 2 U	< 0.056 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated	< 0.025 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.022 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.024 U	< 2.2 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U

DRAFT

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.8	100	0.33	100					
Restricted - Residential																	6.7	100	100	100					
Protection of Groundwater																	0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																		
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.18		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.2 U	< 0.11 U	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.14 U	< 0.021 U		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.62		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.36		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.39	< 0.11 U	0.51		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	< 0.024 U	< 0.13 U	< 0.021 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	< 0.023 U	< 0.13 U	< 0.021 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.33	< 0.11 U	0.44		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.031 U	< 0.023 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	< 0.21 U	< 0.12 U	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	< 0.024 U	< 0.14 U	< 0.022 U		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	< 0.16 U	< 0.088 U	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.35		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.2		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.23		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.14		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.16 U	< 0.09 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.17 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.018 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.18 U	< 0.099 U	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**	**Benzo(a)pyrene (BaP)**	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated			ND	< 0.027 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.02 U	< 0.058 U	< 0.042 U	< 0.04 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 UT	< 0.038 U	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated			0.523	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.044 J	0.042 J	0.06 J	< 0.022 U	0.04 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated			0.428	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	0.04 J	0.034 J	0.022 J	0.036 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated			0.125	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.035 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated			0.913	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.074 J	0.071 J	0.096	0.031 J	0.06 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated			0.199	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	0.03 J	< 0.025 U	0.021 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.038 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated			0.019	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated			0.044	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	0.39 J	< 0.05 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated			0.452	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	2.5	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	0.056 J	< 0.049 U	< 0.036 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated			0.41	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	0.11	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated			0.86	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	0.21	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated			0.73	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.051 U	0.18	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated			0.74	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.14	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated			0.101	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated			0.244	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	0.074 J	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated			1.399	< 0.034 U	0.034 J	< 0.034 U	0.037 J	< 0.17 U	< 0.034 U	< 0.049 U	0.13	0.11	0.12	0.054 J	0.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	< 0.034 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated			0.413	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.093	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated			0.372	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	0.082 J	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated			0.52	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	0.14	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated			0.745	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.18 J	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated			0.328	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.072 J	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated			0.758	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.15	0.058 J	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated			0.762	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.17	0.052 J	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated			0.098	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.041 J	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated			0.5	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.11	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated			0.387	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.074 J	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated			0.742	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.13	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.023 U	< 0.19 U	< 0.034 U	< 0.055 U	< 0.034 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated			2.389	< 0.034 U	0.023 J	< 0.034 U	0.085	< 0.15 U	< 0.034 U	< 0.043 U	0.22	0.16	0.21	0.077	0.1	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated			35	0.98	0.059 J	< 0.034 U	1.9	< 0.26 U	< 0.034 U	< 0.074 U	2.7	1.7	2	0.74	1.2	< 0.22 U	< 0.022 U	< 0.044 U	< 0.63 U	< 0.25 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated			42.11	0.76	0.32	< 0.034 U	1.8	< 0.16 U	< 0.034 U	< 0.045 U	3.3	2	2.5	0.98	1.4	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ethe	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7																			
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.21 J	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.22 J	< 0.22 U	< 0.64 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.032 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	< 0.052 U	< 0.06 U	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.8 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.29 U	< 0.27 UT	< 0.02 U	< 0.029 UT	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.25 U	< 0.73 UT
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.041 J	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	0.018 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.076	< 0.049 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	0.26 J	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.73 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.028 U	< 0.019 UJ	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 UJ	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 UJ	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 UJ	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.034 U	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.034 U	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24	< 0.034 U	< 0.018 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.32	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.046 J	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.094	< 0.034 U	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.15	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.025 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.026 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.034 U	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.027 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.29 J	< 0.048 U	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.17 J	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.27	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	0.18 J	< 0.21 U	< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.027 U	0.23 J	< 0.22 U	< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.057 J	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.3 J	< 0.22 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.23 J	< 0.22 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.24 J	< 0.22 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.024 U	< 0.028 U	0.17 J	< 0.22 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	0.16 J	< 0.21 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	0.27 J	< 0.23 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.028 U	< 0.033 U	< 0.034 U	< 0.26 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.22 U	0.032 J	< 0.09 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.19	< 0.034 U	< 0.13 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.39 U	0.51	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	2.3	0.33	0.56 J	< 0.034 U	< 0.046 U	< 0.034 U	< 0.2 U	< 0.24 U	< 0.034 U	< 0.35 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.24 U	0.48	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	2.9	0.39	0.48	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Lab Report	Excavation Status^7	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.022 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.029 U	< 2.6 U	< 0.07 U	< 0.15 U			< 0.025 U	< 0.018 U	< 0.033 U	< 0.027 U	< 0.048 U	< 0.024 U	< 0.046 U	< 0.13 U		< 0.024 U	< 0.022 U	< 0.14 U	< 0.018 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.026 U	< 2.3 UT	< 0.064 U	< 0.13 U			< 0.022 UT	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			0.12	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.024 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U	< 0.12 U			0.048 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	0.045 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U	< 0.13 U			0.063 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.025 U	< 2.3 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.026 U	< 2.4 U	< 0.064 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.022 U	< 0.02 U	< 0.13 U	< 0.017 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.023 U	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.024 U	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.023 U	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.026 U	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	< 0.025 U	< 2.2 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.021 U	0.041 J		0.044 J
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 0.024 U	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	0.3		0.39
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.024 U	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	< 0.026 U	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.022 U	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.06 U			< 0.12 U	0.21	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	0.084	< 0.034 U	< 0.034 U	< 0.034 U	0.019 J		0.044 J
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.064 U			< 0.13 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.025 U	< 2.3 U	< 0.061 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.023 U	< 2.1 U	< 0.056 U			< 0.12 U	0.065 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	< 0.019 UJ	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	0.043 J	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	0.082	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.056 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.027 U	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.067 U			< 0.14 U	< 0.023 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.2 U			< 0.11 U	0.48	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	0.097	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.02 J
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.14 U	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.14 U	< 2.3 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.14 U	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.14 U	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.36 U			< 0.19 U	5.9	0.97	< 0.043 U	< 0.034 U	< 0.034 U	< 0.034 U	1	< 0.034 U	< 0.034 U	< 0.034 U	0.27		0.38
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.11 U	7.9	0.87	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	1.3	< 0.034 U	< 0.034 U	< 0.034 U	0.19		0.21

DRAFT

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.8	100	0.33	100					
Restricted - Residential																	6.7	100	100	100					
Protection of Groundwater																	0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																		
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.17 U	< 0.094 U	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.21 U	< 0.12 U	< 0.023 U	< 0.17 U	< 0.074 U	< 0.33 U		< 0.032 U	< 0.15 U	< 0.75 U	< 0.025 U	< 0.14 U	< 0.022 U		< 0.02 U	< 0.19 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.19 U	< 0.11 UT	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.16 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.076	< 0.11 U	0.1		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.092	< 0.11 U	0.094		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.04 J	< 0.11 U	0.037 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.1	< 0.12 U	0.17		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.036 J	< 0.13 U	0.049 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.19 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	0.019 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.17 U	< 0.097 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.18 U	< 0.098 U	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.17 U	< 0.096 U	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 0.17 U	< 0.097 U	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.062 J	< 0.12 U	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.18 U	< 0.1 U	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	< 0.19 U	< 0.11 U	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.16 U	< 0.091 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.14		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.3		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.31		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.28		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.055 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.076 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.12 U	0.24		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.19 U	< 0.1 U	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.16		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	0.15		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	0.2		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.17 U	< 0.095 U	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.21 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.086 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.28		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.29		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.21		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.13		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.32		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.2 U	< 0.11 U	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.022 U	< 0.034 U	< 0.034 U	< 0.31 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.1 U	0.4		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.16 U	< 0.09 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.17 U	< 0.093 U	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.16 U	< 0.091 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.16 U	< 0.089 U	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.42 U		< 0.034 U	< 0.034 U	< 0.034 U	7.6	< 0.18 U	5.3		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	8.9	< 0.11 U	6.9		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											20	100		100				1	1	1	0.8	100					
Restricted - Residential											100	100		100				1	1	1	3.9	100					
Protection of Groundwater											98	107		1000				1	22	1.7	1.7	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																				
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated			0.28	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	0.04 J	< 0.034 U	0.04 J	< 0.023 U	0.024 J	< 0.034 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated			0.192	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	0.029 J	< 0.022 U	0.017 J	< 0.034 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.066 U	< 0.014 U	< 0.01 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U	< 0.0098 U	< 0.0096 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 U	< 0.014 U	< 0.069 U	< 0.014 U	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0075 U	< 0.022 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	0.023 J	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.069 U	< 0.015 U	< 0.011 U	< 0.011 U	< 0.0082 U	< 0.012 U	< 0.033 U	< 0.015 U	< 0.0076 U	< 0.022 U	< 0.017 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated			1.815	< 0.0069	< 0.0082	< 0.03	< 0.007	< 0.035	< 0.032	< 0.054	0.16	0.082	0.12	0.042	0.058	< 0.024	< 0.0096	< 0.0078	< 0.058	< 0.031
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated			0.437	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.097 J	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 UJ	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated			0.208	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.055 J	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated			ND	< 0.41 U	< 0.41 U		< 0.41 U				< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U					
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated			0.31	< 0.37 U	< 0.37 U		< 0.37 U				0.1 J	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U					

DRAFT

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																1	0.33	7								
Restricted - Residential																3.9	0.33	59								
Protection of Groundwater																1	1000	210								
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.09 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	< 0.019 U	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U	< 0.06 UT	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 UT
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 UT
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U	< 0.058 UT	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 UT
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.017 U	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 UT
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.018 U	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 UT
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.019 U	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	< 0.0069 U	< 0.018 U	< 0.014 U	< 0.062 UT	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.019 U	< 0.065 U	< 0.016 U	< 0.074 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0070 U	< 0.018 U	< 0.014 U	< 0.063 UT	< 0.027 U	< 0.013 U	< 0.05 U	< 0.094 U	< 0.016 U	< 0.022 U	< 0.17 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.019 U	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0069 U	< 0.018 U	< 0.014 U	< 0.062 UT	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.017 U	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U	< 0.054 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U	< 0.058 UT	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	< 0.018 U	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.018 U	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.02 U	< 0.065 U	< 0.016 U	< 0.074 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0071 U	< 0.018 U	< 0.014 U	< 0.063 UT	< 0.027 U	< 0.013 U	< 0.05 U	< 0.095 U	< 0.016 U	< 0.022 U	< 0.17 UT
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	< 0.049	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	0.47	< 0.008	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.2 J	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 UJ	< 0.047 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.085	< 0.046 U	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated									< 0.41 U	< 0.41 U	< 0.41 U								
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated									0.21 J	< 0.37 U	< 0.37 U								

DRAFT

TABLE 5-7C
Deep Soil Results - Remedial Investigation - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1	0.1	0.1	100	30	0.33				0.5	0.33				0.33	12
Restricted - Residential											13	13	13	100	100	1.2				0.5	100				100	100
Protection of Groundwater											0.1	0.1	0.1	1000	386	3.2				8.2	0.33				0.33	12
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																			
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.21 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.23 U			< 0.12 U	0.079	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.22 U			< 0.12 U	0.052 J	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.015 J
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	< 0.029 U	< 0.2 UT	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.028 U	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.028 U	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.027 U	< 0.18 UT	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.028 U	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0084 U	< 0.034 U	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.03 U	< 0.2 UT	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	< 0.0071 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.03 U	< 0.2 UT	< 0.045 U		< 0.036 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0088 U	< 0.036 U	< 0.014 U	< 0.016 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.03 U	< 0.2 UT	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.02 U	< 0.0087 U	< 0.036 U	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	< 0.0071 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.026 U	< 0.17 UT	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.028 U	< 0.19 UT	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.028 U	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	< 0.027 U	< 0.19 UT	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.027 U	< 0.19 UT	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.03 U	< 0.21 UT	< 0.045 U		< 0.037 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0089 U	< 0.037 U	< 0.014 U	< 0.016 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	< 0.037	< 0.43	< 0.029			< 0.041	0.42	< 0.0095	< 0.0076	< 0.008	< 0.039	< 0.026	0.053	< 0.025		< 0.027	< 0.0065	< 0.035	< 0.0062
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.022 U	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	< 0.022 U	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.022 U	< 2 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated							< 0.41 U	< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated							< 0.37 U	< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U

DRAFT

							2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
							mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.8	100	0.33	100					
Restricted - Residential																6.7	100	100	100					
Protection of Groundwater																0.8	1000	0.33	1000					
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]																	
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	< 0.016 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.035 J	< 0.12 U	0.062 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.033 J	< 0.11 U	0.046 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	< 0.03 U	< 0.095 U	< 0.046 U	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 UT	< 0.0070 U	< 0.015 U	< 0.0099 U		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.03 U	< 0.092 U	< 0.045 U	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 UT	< 0.0068 U	< 0.014 U	< 0.0097 U		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.029 U	< 0.092 U	< 0.044 U	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 UT	< 0.0068 U	< 0.014 U	< 0.0096 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.028 U	< 0.088 U	< 0.042 U	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 UT	< 0.0065 U	< 0.014 U	< 0.0092 U		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.03 U	< 0.093 U	< 0.045 U	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.08 UT	< 0.0069 U	< 0.014 U	< 0.0098 U		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.031 U	< 0.097 U	< 0.047 U	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 UT	< 0.0072 U	< 0.015 U	< 0.01 U		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.032 U	< 0.099 U	< 0.048 U	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.085 UT	< 0.0073 U	< 0.015 U	< 0.01 U		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.031 U	< 0.098 U	< 0.047 U	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 UT	< 0.0072 U	< 0.015 U	< 0.01 U		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.027 U	< 0.085 U	< 0.041 U	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 UT	< 0.0063 U	< 0.013 U	< 0.0089 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.029 U	< 0.091 U	< 0.044 U	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 UT	< 0.0068 U	< 0.014 U	< 0.0096 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.03 U	< 0.092 U	< 0.045 U	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 UT	< 0.0068 U	< 0.014 U	< 0.0097 U		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	< 0.029 U	< 0.09 U	< 0.044 U	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 UT	< 0.0067 U	< 0.014 U	< 0.0094 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.029 U	< 0.089 U	< 0.043 U	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 UT	< 0.0066 U	< 0.014 U	< 0.0094 U		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.032 U	< 0.099 U	< 0.048 U	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.086 UT	< 0.0074 U	< 0.015 U	< 0.01 U		< 0.013 U	< 0.028 U	< 0.043 U	< 0.054 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	< 0.16	< 0.15	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0085	0.41		< 0.027	< 0.023	< 0.038	< 0.054
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.17 U	< 0.092 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.14 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.17 U	< 0.093 U	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 UJ		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.068 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.16 U	< 0.089 U	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated										< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U					
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated										< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U					

DRAFT

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 UT	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT	< 0.0013 U	< 0.0025 U	< 0.0030 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U	< 0.0016 U	< 0.0025 UJ	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.004 U	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	16 - 18 ft	180-116310-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	0.012 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 UT	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	0.0044 J	< 0.0036 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	853.65	18 - 20 ft	1801163651	Not Excavated	0.0082 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	853.65	20 - 22 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	853.65	22 - 24 ft	1801163651	Not Excavated	< 0.26 U	< 0.094 U	< 0.2 U	< 0.16 U	< 0.17 U	< 0.15 U	< 0.27 U	< 0.14 U	< 0.087 U	< 0.17 U	< 0.2 U	< 0.11 U	< 0.13 U	0.71	< 0.22 U
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	26 - 28 ft	180-128986-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	24 - 26 ft	180-128986-1	Not Excavated	< 0.28 U	< 0.1 U	< 0.22 U	< 0.17 U	< 0.18 U	< 0.17 U	< 0.29 U	< 0.15 U	< 0.095 U	< 0.18 U	< 0.21 U	< 0.12 U	< 0.14 U	< 0.18 U	< 0.24 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.087 U	< 0.19 U	< 0.14 UJ	< 0.16 U	< 0.14 U	< 0.25 U	< 0.13 U	< 0.08 UJ	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.23 U	< 0.085 U	< 0.18 U	< 0.14 UJ	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U	< 0.078 UJ	< 0.15 U	< 0.18 U	< 0.097 U	< 0.12 U	< 0.14 U	< 0.19 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.086 U	< 0.18 U	< 0.14 UJ	< 0.15 U	< 0.14 U	< 0.25 U	< 0.13 U	< 0.08 UJ	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U
Football Field	SSHS-B3556	DUP-29	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	0.0091 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0034 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	0.0094 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	3.9	< 0.071 U	< 0.15 U	< 0.12 UJ	< 0.13 U	< 0.11 U	< 0.2 U	< 0.1 U	< 0.065 UJ	< 0.12 U	< 0.15 U	< 0.081 U	< 0.1 U	< 0.12 U	< 0.16 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.087 U	< 0.19 U	< 0.15 UJ	< 0.16 U	< 0.14 U	< 0.25 U	< 0.13 U	< 0.081 UJ	< 0.15 U	< 0.18 U	< 0.1 U	< 0.12 U	< 0.15 U	< 0.2 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	< 0.2 U	< 0.072 U	< 0.15 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.21 U	< 0.1 U	< 0.067 U	< 0.13 U	< 0.15 U	< 0.083 U	< 0.1 U	< 0.12 U	< 0.17 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	< 0.22 U	< 0.081 U	< 0.17 U	< 0.13 UJ	< 0.15 U	< 0.13 U	< 0.23 U	< 0.12 U	< 0.075 UJ	< 0.14 U	< 0.17 U	< 0.093 U	< 0.11 U	< 0.14 U	< 0.19 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	< 0.23 U	< 0.083 U	< 0.18 U	< 0.14 UJ	< 0.15 U	< 0.13 U	< 0.24 U	< 0.12 U	< 0.076 UJ	< 0.15 U	< 0.17 U	< 0.095 U	< 0.12 U	< 0.14 U	< 0.19 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	< 0.22 U	< 0.078 U	< 0.17 U	< 0.13 U	< 0.14 U	< 0.13 U	< 0.22 U	< 0.11 U	< 0.072 U	< 0.14 U	< 0.16 U	< 0.09 U	< 0.11 U	< 0.13 U	< 0.18 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	< 0.2 U	< 0.074 U	< 0.16 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.21 U	< 0.11 U	< 0.068 U	< 0.13 U	< 0.15 U	< 0.084 U	< 0.1 U	< 0.13 U	< 0.17 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	< 0.18 U	< 0.065 U	< 0.14 U	< 0.11 U	< 0.12 U	< 0.11 U	< 0.19 U	< 0.094 U	< 0.06 U	< 0.11 U	< 0.14 U	< 0.074 U	< 0.092 U	< 0.11 U	< 0.15 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	0.0093 J	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	0.012 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	0.0096	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	0.0018 J	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3571	DUP-35	1/19/2021	855.21	32 - 34 ft	180-116199-1	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.004 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0044 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-16-18	2/5/2021	856.15	16 - 18 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-16-18	2/5/2021	856.23	16 - 18 ft	180-116914-1	Not Excavated	< 0.24 U	< 0.086 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U	< 0.079 U	< 0.15 U	< 0.18 U	< 0.098 U	< 0.12 U	< 0.15 U	< 0.2 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	0.39	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.00061 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00067 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00078 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	0.012 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00058 U	< 0.00057 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0006 U	< 0.00058 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	0.0088 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00087 U	< 0.00084 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00092 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00066 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	0.0072 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00061 U	< 0.00059 U	< 0.034 U	0.00031 J	< 0.034 U	< 0.00064 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	0.0088 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00059 U	< 0.00057 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	30 - 32 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	0.0079 J	0.00035 J	< 0.0004 U	< 0.00074 U	< 0.0028 U	< 0.0005 U	< 0.0028 U	< 0.00054 U	< 0.00073 U	< 0.00071 U	< 0.0013 U	< 0.00034 U	< 0.00033 U	< 0.00078 U	< 0.0028 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.0037 U	< 0.00021 U	< 0.00031 U	< 0.00058 U	< 0.0022 U	< 0.00039 U	< 0.0022 U	< 0.00042 U	< 0.00057 U	< 0.00056 U	< 0.00098 U	< 0.00027 U	< 0.00026 U	< 0.00061 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	0.0049 J	< 0.00019 U	< 0.00028 U	< 0.00052 U	< 0.0019 U	< 0.00035 U	< 0.0019 U	< 0.00037 U	< 0.00051 U	< 0.00049 U	< 0.00087 U	< 0.00024 U	< 0.00023 U	< 0.00054 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.0036 U	< 0.00021 U	< 0.00031 U	< 0.00057 U	< 0.0021 U	< 0.00038 U	< 0.0021 U	< 0.00041 U	< 0.00056 U	< 0.00054 U	< 0.00096 U	0.00043 J	< 0.00026 U	< 0.00059 U	< 0.0021 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	0.0045 J	0.00024 J	< 0.00028 U	< 0.00052 U	< 0.0019 U	< 0.00035 U	< 0.0019 U	< 0.00038 U	< 0.00051 U	< 0.0005 U	< 0.00088 U	0.00043 J	< 0.00023 U	< 0.00054 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.088 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.14 U	< 0.25 UJ	< 0.13 U	< 0.081 U	< 0.15 U	< 0.18 U	< 0.1 U	< 0.12 U	< 0.15 U	< 0.2 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0021 U	< 0.0022 U	< 0.002 U	< 0.0035 U	< 0.0018 U	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.09 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.25 UJ	< 0.13 U	< 0.083 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.21 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.36 U	< 0.13 U	< 0.28 U	< 0.22 U	< 0.23 U	< 0.21 U	< 0.37 UJ	< 0.19 U	< 0.12 U	< 0.23 U	< 0.27 U	< 0.15 U	< 0.18 U	< 0.22 U	< 0.3 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	0.018 J	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.003 U	< 0.004 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 UT	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U	< 0.0023 UT	< 0.0041 UT	< 0.0015 UT	< 0.0018 UT	< 0.0014 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated	0.0041 J	< 0.0028 U	< 0.003 UJ	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	< 0.0047 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	16 - 18 ft	180-116310-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	853.65	18 - 20 ft	1801163651	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	853.65	20 - 22 ft	1801163651	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	853.65	22 - 24 ft	1801163651	Not Excavated	< 0.3 U	< 0.092 U	< 0.17 U	0.52	< 0.21 U	0.14 J	< 0.11 U	< 0.096 U	< 0.15 U	< 0.27 U	< 0.1 U	< 0.12 U	< 0.089 U	< 0.15 U	< 0.15 U
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	26 - 28 ft	180-128986-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	24 - 26 ft	180-128986-1	Not Excavated	< 0.33 U	< 0.1 U	< 0.18 U	< 0.12 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.11 U	< 0.17 U	< 0.3 U	< 0.11 U	< 0.13 U	< 0.097 U	< 0.16 U	< 0.17 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.28 UJ	< 0.085 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.093 U	< 0.099 U	< 0.089 U	< 0.14 U	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 UJ
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	0.41 J	< 0.082 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.09 U	< 0.096 U	< 0.087 U	< 0.14 U	< 0.25 U	< 0.091 U	< 0.11 U	< 0.08 U	< 0.13 U	< 0.14 UJ
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	0.93	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.098 U	< 0.088 U	< 0.14 U	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 UJ
Football Field	SSHS-B3556	DUP-29	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	< 0.23 U	< 0.069 U	< 0.13 U	< 0.085 U	< 0.16 U	< 0.076 U	< 0.081 U	< 0.072 U	< 0.11 U	< 0.21 U	< 0.076 U	< 0.088 U	< 0.067 U	< 0.11 U	< 0.11 UJ
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	1	< 0.085 U	< 0.16 U	< 0.1 U	< 0.19 U	< 0.093 U	< 0.099 U	< 0.089 U	< 0.14 U	< 0.25 U	< 0.094 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 UJ
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 UJ	< 0.0033 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	0.45	< 0.07 U	< 0.13 U	< 0.086 U	< 0.16 U	< 0.077 U	< 0.082 U	< 0.074 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.09 U	< 0.068 U	< 0.11 U	< 0.12 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	< 0.26 U	< 0.079 U	< 0.14 U	< 0.097 U	< 0.18 U	< 0.086 U	< 0.092 U	< 0.083 U	< 0.13 U	< 0.23 U	< 0.087 U	< 0.1 U	< 0.077 U	< 0.13 U	< 0.13 UJ
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	< 0.27 U	< 0.081 U	< 0.15 U	< 0.099 U	< 0.18 U	< 0.088 U	< 0.094 U	< 0.085 U	< 0.13 U	< 0.24 U	< 0.089 U	< 0.1 U	< 0.078 U	< 0.13 U	< 0.13 UJ
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	< 0.25 U	< 0.076 U	< 0.14 U	< 0.093 U	0.24 J	0.78	< 0.089 U	< 0.08 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.097 U	< 0.074 U	< 0.12 U	< 0.13 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	0.38	< 0.072 U	< 0.13 U	< 0.088 U	< 0.16 U	< 0.078 U	< 0.084 U	< 0.075 U	< 0.12 U	< 0.21 U	< 0.079 U	< 0.092 U	< 0.07 U	< 0.12 U	< 0.12 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	0.32	< 0.063 U	< 0.12 U	< 0.078 U	< 0.14 U	< 0.069 U	< 0.074 U	< 0.067 U	< 0.1 U	< 0.19 U	< 0.07 U	< 0.081 U	< 0.062 U	< 0.1 U	< 0.1 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	0.012	0.083	0.024	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	0.012	0.071	0.012	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3571	DUP-35	1/19/2021	855.21	32 - 34 ft	180-116199-1	Not Excavated	< 0.0061 U	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.002 U	< 0.0022 U	< 0.0019 U	< 0.0031 U	< 0.0055 U	< 0.002 U	< 0.0024 U	< 0.0018 U	< 0.003 U	< 0.003 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-16-18	2/5/2021	856.15	16 - 18 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-16-18	2/5/2021	856.23	16 - 18 ft	180-116914-1	Not Excavated	< 0.28 U	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.098 U	< 0.088 U	< 0.14 UJ	< 0.25 U	< 0.092 U	< 0.11 U	< 0.081 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	0.011	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00024 U	< 0.034 U	< 0.034 U	< 0.00061 U	< 0.00049 U	< 0.034 U	< 0.00069 U	< 0.0021 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.00024 U	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.0005 U	< 0.034 U	< 0.0007 U	< 0.0021 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00078 U	< 0.034 U	< 0.00028 U	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.00057 U	< 0.034 U	< 0.0008 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00057 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.00022 U	< 0.034 U	< 0.034 U	< 0.00057 U	< 0.00046 U	< 0.034 U	< 0.00064 U	< 0.0019 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00058 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.00023 U	< 0.034 U	< 0.034 U	< 0.00058 U	< 0.00047 U	< 0.034 U	< 0.00065 U	< 0.002 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	0.0034 J	< 0.00085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00092 U	< 0.034 U	< 0.00033 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.00068 U	< 0.034 U	< 0.00095 U	< 0.0029 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	0.0024 J	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U	< 0.00025 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.00052 U	< 0.034 U	< 0.00072 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00059 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.00023 U	< 0.034 U	< 0.034 U	< 0.00059 U	< 0.00047 U	< 0.034 U	< 0.00066 U	< 0.002 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	0.0039 J	< 0.00058 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.00023 U	< 0.034 U	< 0.034 U	< 0.00057 U	< 0.00046 U	< 0.034 U	< 0.00065 U	< 0.002 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U	< 0.00025 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.00051 U	< 0.034 U	< 0.00071 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	30 - 32 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.0026 U	< 0.00071 U	< 0.00046 U	< 0.00043 U	< 0.00028 U	< 0.00078 U	< 0.00068 U	< 0.00028 U	< 0.00068 U	< 0.0029 U	< 0.00071 U	< 0.00057 U	< 0.0028 U	< 0.0008 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.00056 U	< 0.00036 U	< 0.00034 U	< 0.00022 U	< 0.00061 U	< 0.00053 U	< 0.00022 U	< 0.00053 U	< 0.0023 U	< 0.00056 U	< 0.00045 U	< 0.0022 U	< 0.00063 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.00049 U	< 0.00032 U	< 0.0003 U	< 0.0002 U	< 0.00054 U	< 0.00047 U	< 0.00019 U	< 0.00047 U	< 0.002 U	< 0.00049 U	< 0.0004 U	< 0.0019 U	< 0.00055 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.00054 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00059 U	< 0.00052 U	< 0.00021 U	< 0.00052 U	< 0.0022 U	< 0.00054 U	< 0.00044 U	< 0.0021 U	< 0.00061 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0005 U	< 0.00032 U	< 0.0003 U	< 0.0002 U	< 0.00054 U	< 0.00047 U	< 0.00019 U	< 0.00047 U	< 0.002 U	< 0.0005 U	< 0.0004 U	< 0.0019 U	< 0.00056 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.28 U	< 0.085 U	< 0.16 U	< 0.1 U	< 0.19 U	< 0.093 U	< 0.1 U	< 0.09 U	< 0.14 UJ	< 0.25 U	< 0.094 U	< 0.11 U	< 0.083 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U	< 0.002 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.002 U	< 0.002 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.29 U	< 0.087 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.095 U	< 0.1 U	< 0.092 U	< 0.14 UJ	< 0.26 U	< 0.096 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.42 U	< 0.13 U	< 0.23 U	< 0.16 U	< 0.29 U	< 0.14 U	< 0.15 U	< 0.13 U	< 0.21 UJ	< 0.38 U	< 0.14 U	< 0.16 U	< 0.12 U	< 0.21 U	< 0.21 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.0019 UT	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0075 U	< 0.0024 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	< 0.0025 U	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated	< 0.0022 U	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	16 - 18 ft	180-116310-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 UT	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 UT	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 UT	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 UT	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	0.036	< 0.0028 UT	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 UT	0.0051 J	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	853.65	18 - 20 ft	1801163651	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	0.01	< 0.0027 UT	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 UT	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	853.65	20 - 22 ft	1801163651	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 UT	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 UT	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	853.65	22 - 24 ft	1801163651	Not Excavated	1	40	< 0.11 U	3.1	< 0.49 U	24	< 0.17 U	< 0.12 UT	< 0.098 UT	< 0.1 U	< 0.1 U	40	2	< 0.18 U	0.99
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	26 - 28 ft	180-128986-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	24 - 26 ft	180-128986-1	Not Excavated	< 0.14 U	< 0.15 U	< 0.11 U	< 0.19 U	< 0.54 U	< 0.18 U	< 0.19 U	< 0.13 U	< 0.11 U	< 0.11 U	< 0.11 U	0.36 J	0.12 J	< 0.2 U	< 0.19 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 UT	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.097 U	< 0.16 U	< 0.45 U	0.24 J	0.24 J	< 0.11 U	< 0.091 U	< 0.093 U	< 0.094 U	< 0.12 U	< 0.089 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.094 U	< 0.16 U	< 0.44 U	< 0.15 UJ	< 0.15 UJ	< 0.11 U	< 0.088 U	< 0.09 U	< 0.091 U	< 0.12 U	< 0.087 U	< 0.17 U	< 0.15 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.096 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.09 U	< 0.092 U	< 0.093 U	< 0.12 U	< 0.088 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B3556	DUP-29	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	< 0.093 U	< 0.1 U	< 0.079 U	< 0.13 U	< 0.37 U	< 0.12 U	< 0.13 U	< 0.092 U	< 0.074 U	< 0.076 U	< 0.077 U	< 0.1 U	< 0.072 U	< 0.14 U	< 0.13 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.097 U	< 0.16 U	< 0.46 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.091 U	< 0.093 U	< 0.094 U	< 0.13 U	< 0.089 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	0.0029 J	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	0.012	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	< 0.095 U	< 0.1 U	< 0.081 U	< 0.13 U	< 0.38 U	< 0.12 U	< 0.13 U	< 0.094 U	< 0.075 U	< 0.077 U	< 0.078 U	< 0.1 U	< 0.074 U	< 0.14 UJ	< 0.13 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.09 U	< 0.15 U	< 0.42 U	< 0.14 U	< 0.15 U	< 0.11 U	< 0.085 U	< 0.086 U	< 0.087 U	< 0.12 U	< 0.083 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	0.004 J	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.092 U	< 0.15 U	< 0.43 U	0.19 J	< 0.15 U	< 0.11 U	< 0.086 U	< 0.088 U	< 0.089 U	< 0.12 U	< 0.085 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	< 0.1 U	< 0.11 U	< 0.087 U	< 0.14 U	< 0.41 U	< 0.13 U	< 0.14 U	< 0.1 U	< 0.082 U	< 0.083 U	< 0.085 U	< 0.11 U	< 0.08 U	< 0.15 UJ	< 0.14 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	0.0034 J,F1	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	< 0.097 U	< 0.1 U	< 0.082 U	< 0.14 U	< 0.38 U	< 0.13 U	< 0.13 U	< 0.096 U	< 0.077 U	< 0.078 U	< 0.079 U	< 0.11 U	< 0.075 U	< 0.14 U	< 0.13 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	< 0.086 U	< 0.093 U	< 0.073 U	< 0.12 U	< 0.34 U	< 0.11 U	< 0.12 U	< 0.085 U	< 0.068 U	< 0.069 U	< 0.07 U	< 0.093 U	< 0.067 U	< 0.13 U	< 0.12 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	0.0074	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	0.026	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	0.0062	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	0.0074
Football Field	SSHS-B3571	DUP-35	1/19/2021	855.21	32 - 34 ft	180-116199-1	Not Excavated	< 0.0025 U	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.01 U	< 0.0033 U	< 0.0034 U	< 0.0025 U	< 0.002 U	< 0.002 U	< 0.0021 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-16-18	2/5/2021	856.15	16 - 18 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-16-18	2/5/2021	856.23	16 - 18 ft	180-116914-1	Not Excavated	< 0.11 U	< 0.12 U	< 0.096 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.09 U	< 0.092 U	< 0.093 U	< 0.12 U	< 0.088 U	< 0.17 U	< 0.16 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	< 0.00033 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.034 U	< 0.0016 U	< 0.00047 U	< 0.00024 U	< 0.034 U	< 0.00064 U	0.0017 J	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00058 J	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.0016 U	< 0.00048 U	< 0.00024 U	< 0.034 U	< 0.00065 U	< 0.00037 U	< 0.034 U	< 0.0003 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.00038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.0018 U	< 0.00054 U	< 0.00028 U	< 0.034 U	< 0.00074 U	< 0.00042 U	< 0.034 U	< 0.00034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.00031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00067 U	< 0.034 U	< 0.0015 U	< 0.00043 U	< 0.00022 U	< 0.034 U	< 0.00059 U	< 0.00033 U	< 0.034 U	< 0.00027 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.00031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U	< 0.0015 U	< 0.00044 U	< 0.00023 U	< 0.034 U	< 0.00061 U	< 0.00034 U	< 0.034 U	< 0.00027 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	< 0.00045 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U	< 0.0022 U	< 0.00065 U	< 0.00033 U	< 0.034 U	< 0.00088 U	< 0.0005 U	< 0.034 U	< 0.0004 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.00035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.0016 U	< 0.00049 U	< 0.00025 U	< 0.034 U	< 0.00067 U	< 0.00038 U	< 0.034 U	< 0.00031 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.00032 U	< 0.034 U	< 0.034 U	< 0.034 U	0.003 J	< 0.0007 U	< 0.034 U	< 0.0015 U	< 0.00045 U	< 0.00023 U	< 0.034 U	< 0.00062 U	0.00053 J	< 0.034 U	< 0.00028 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	< 0.00031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.0015 U	< 0.00044 U	< 0.00022 U	< 0.034 U	< 0.0006 U	< 0.00034 U	< 0.034 U	< 0.00027 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.0016 U	< 0.00048 U	< 0.00025 U	< 0.034 U	< 0.00066 U	< 0.00037 U	< 0.034 U	< 0.0003 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	30 - 32 ft	180-127595-2	Not Excavated	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0018 U	< 0.034 U	< 0.0032 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.00038 U	< 0.0013 U	< 0.0028 U	< 0.00084 U	< 0.0033 U	< 0.00084 U	< 0.002 U	< 0.0018 U	< 0.00054 U	< 0.00028 U	< 0.0009 U	< 0.00074 U	< 0.00042 U	< 0.00059 U	< 0.00034 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.0003 U	< 0.00099 U	< 0.0022 U	< 0.00066 U	< 0.0026 U	< 0.00066 U	< 0.0016 U	< 0.0014 U	< 0.00043 U	< 0.00022 U	< 0.00071 U	< 0.00058 U	0.0005 J	< 0.00046 U	< 0.00026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.00027 U	< 0.00088 U	< 0.0019 U	< 0.00058 U	< 0.0023 U	< 0.00058 U	< 0.0014 U	< 0.0013 U	< 0.00038 U	< 0.00019 U	< 0.00062 U	< 0.00052 U	< 0.00029 U	< 0.00041 U	< 0.00023 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.00029 U	< 0.00096 U	< 0.0021 U	< 0.00064 U	< 0.0026 U	< 0.00064 U	< 0.0015 U	< 0.0014 U	< 0.00042 U	< 0.00021 U	< 0.00069 U	< 0.00057 U	< 0.00032 U	< 0.00045 U	< 0.00026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.00027 U	< 0.00088 U	< 0.0019 U	< 0.00058 U	< 0.0023 U	0.0008 J	< 0.0014 U	< 0.0013 U	< 0.00038 U	< 0.00019 U	< 0.00063 U	0.00073 J	0.00053 J	< 0.00041 U	< 0.00024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.12 U	< 0.12 UJ	< 0.098 U	< 0.16 U	< 0.46 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.091 UJ	< 0.093 U	< 0.095 U	< 0.13 UJ	< 0.09 U	< 0.17 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.12 U	< 0.13 UJ	< 0.1 U	< 0.17 U	< 0.47 U	< 0.15 U	< 0.16 U	< 0.12 U	< 0.094 UJ	< 0.095 U	< 0.097 U	< 0.13 UJ	< 0.092 U	< 0.18 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.19 UJ	< 0.15 U	< 0.24 U	< 0.68 U	< 0.22 U	< 0.24 U	< 0.17 U	< 0.14 UJ	< 0.14 U	< 0.14 U	< 0.19 UJ	< 0.13 U	< 0.26 U	< 0.24 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 UJ

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 0.0017 U	< 0.00098 UJ	< 0.0016 UT	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 0.0017 UT	< 0.0010 U	< 0.0016 UT	< 0.0042 U	< 0.0037 U	< 0.0018 UT	< 0.0020 UT	< 0.0073 UT
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	16 - 18 ft	180-95047-2	Not Excavated	< 0.0029 U	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3092	SSHS-B3092-SUB-16-17	12/20/2019	858.31	16 - 17 ft	180-100361-1	Not Excavated	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0015 UJ	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	16 - 18 ft	180-95050-1	Not Excavated	< 0.003 U	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0052 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	16 - 18 ft	180-116310-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	853.65	18 - 20 ft	1801163651	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	853.65	20 - 22 ft	1801163651	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	853.65	22 - 24 ft	1801163651	Not Excavated	< 0.11 U	< 0.066 U	25	< 0.28 U	< 0.24 U	4.8	4	8.8
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	26 - 28 ft	180-128986-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-B3454A	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	24 - 26 ft	180-128986-1	Not Excavated	< 0.12 U	< 0.072 U	2.5	< 0.3 U	< 0.26 U	< 0.13 U	< 0.15 U	< 0.53 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.1 U	< 0.061 U	< 0.097 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.45 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	16 - 18 ft	180-115815-1	Not Excavated	< 0.1 U	< 0.059 U	< 0.094 U	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	18 - 20 ft	180-115815-1	Not Excavated	< 0.1 U	< 0.061 U	< 0.096 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	SSHS-B3556	DUP-29	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	18 - 20 ft	180-115925-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	18 - 20 ft	180-115815-1	Not Excavated	< 0.084 U	< 0.05 U	< 0.079 U	< 0.21 U	< 0.18 U	< 0.09 U	< 0.1 U	< 0.36 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	16 - 18 ft	180-115815-1	Not Excavated	< 0.1 U	< 0.061 U	< 0.097 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.13 U	< 0.45 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	16 - 18 ft	180-115861-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	18 - 20 ft	180-115861-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	20 - 22 ft	180-115861-1	Not Excavated	< 0.086 U	< 0.051 U	< 0.081 U	< 0.21 U	< 0.18 U	< 0.091 U	< 0.1 U	< 0.37 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	16 - 18 ft	180-115861-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	18 - 20 ft	180-115861-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	16 - 18 ft	180-115815-1	Not Excavated	< 0.096 U	< 0.057 U	< 0.09 U	< 0.24 U	< 0.21 U	< 0.1 U	< 0.12 U	< 0.42 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	16 - 18 ft	180-115925-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	18 - 20 ft	180-115925-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	16 - 18 ft	180-115925-1	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	18 - 20 ft	180-115815-1	Not Excavated	< 0.098 U	< 0.058 U	< 0.092 U	< 0.24 U	< 0.21 U	< 0.1 U	< 0.12 U	< 0.42 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	18 - 20 ft	180-115861-1	Not Excavated	< 0.093 U	< 0.055 U	< 0.087 U	< 0.23 U	< 0.2 U	< 0.099 U	< 0.11 U	< 0.4 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	16 - 18 ft	180-115861-2	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	18 - 20 ft	180-115861-2	Not Excavated	< 0.087 U	< 0.052 U	< 0.082 U	< 0.22 U	< 0.19 U	< 0.093 U	< 0.11 U	< 0.38 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	18 - 20 ft	180-115861-2	Not Excavated	< 0.077 U	< 0.046 U	< 0.073 U	< 0.19 U	< 0.17 U	< 0.082 U	< 0.093 U	< 0.33 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	16 - 18 ft	180-116109-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 UJ	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	18 - 20 ft	180-116109-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 UJ	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	18 - 20 ft	180-116199-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	18 - 20 ft	180-116199-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	20 - 22 ft	180-116199-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3571	DUP-35	1/19/2021	855.21	32 - 34 ft	180-116199-1	Not Excavated	< 0.0023 U	< 0.0013 U	< 0.0021 U	< 0.0056 U	< 0.0049 U	< 0.0024 U	< 0.0027 U	< 0.0098 U
Football Field	SSHS-B3577	SSHS-B3577-SUB-16-18	2/5/2021	856.15	16 - 18 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.004 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3580	SSHS-B3580-SUB-16-18	2/5/2021	856.23	16 - 18 ft	180-116914-1	Not Excavated	< 0.1 U	< 0.06 U	< 0.096 U	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00081 U	< 0.034 U	< 0.00081 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 UJ	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00082 U	< 0.034 U	< 0.00082 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U	< 0.00093 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.00074 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.00076 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.00084 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U	< 0.00077 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.00075 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00083 U	< 0.034 U	< 0.00083 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	30 - 32 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.009 U
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated	< 0.0004 U	< 0.00072 U	< 0.0012 U	< 0.00052 U	< 0.00068 U	< 0.00093 U	< 0.00072 U	< 0.00093 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated	< 0.00032 U	< 0.00057 U	< 0.00096 U	< 0.00041 U	< 0.00053 U	< 0.00073 U	< 0.00057 U	< 0.00073 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated	< 0.00028 U	< 0.0005 U	< 0.00085 U	< 0.00036 U	< 0.00047 U	< 0.00065 U	< 0.0005 U	< 0.00065 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated	< 0.00031 U	< 0.00055 U	< 0.00093 U	< 0.0004 U	< 0.00052 U	< 0.00071 U	< 0.00055 U	< 0.00071 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated	< 0.00028 U	< 0.0005 U	< 0.00085 U	< 0.00037 U	< 0.00047 U	< 0.00065 U	< 0.00051 U	< 0.00065 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated	< 0.1 U	< 0.062 U	< 0.098 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.13 U	< 0.45 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.00087 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated	< 0.11 U	< 0.063 U	< 0.1 U	< 0.26 U	< 0.23 U	< 0.11 U	< 0.13 U	< 0.46 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.092 U	< 0.15 U	< 0.39 U	< 0.33 U	< 0.17 U	< 0.19 U	< 0.67 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0028 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0028 U	< 0.0048 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.09 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.26 U	< 0.13 U	< 0.083 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.21 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 UJ	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 UJ	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 UJ
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3863	DUP-39	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 UJ	< 0.0035 UJ
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	0.0028 J	< 0.0036 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0032 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.003 U	< 0.004 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.002 U	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0032 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SSHS-B3864	DUP-37	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3864	DUP-38	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	0.012 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	0.0027 J	< 0.0036 UJ
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	0.003 J	< 0.0033 UJ
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	0.0041 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 UT	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 UT	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.02 U	< 0.0074 U	< 0.016 U	< 0.012 U	< 0.013 U	< 0.012 U	< 0.021 UT	< 0.011 U	< 0.0068 U	< 0.013 U	< 0.015 U	< 0.0084 U	< 0.01 U	< 0.013 U	< 0.017 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 UT	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 UT	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 UT	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0052 UT	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0029 J	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1.2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.29 U	< 0.087 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.096 U	< 0.1 U	< 0.092 U	< 0.14 U	< 0.26 U	< 0.096 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.14 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 UJ	< 0.0039 UJ	< 0.0019 UJ	< 0.002 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UJ	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3863	DUP-39	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 UJ	< 0.0033 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UJ	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UJ	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UJ	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U	< 0.004 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UJ	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3864	DUP-37	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.003 UJ	< 0.002 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3864	DUP-38	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0019 UJ	< 0.0034 UJ	< 0.0017 UJ	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 UJ	< 0.0032 UJ	< 0.0015 UJ	< 0.0016 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 UJ	< 0.0032 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.024 U	< 0.0072 U	< 0.013 U	< 0.0088 U	< 0.016 U	< 0.0079 U	< 0.0084 U	< 0.0075 U	< 0.012 U	< 0.021 U	< 0.0079 U	< 0.0092 U	< 0.0070 U	< 0.012 U	< 0.012 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	0.015	0.0027 J	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0017 U	< 0.034 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0018 U	< 0.034 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0021 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 UJ
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 UJ
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.12 U	< 0.13 U	< 0.1 U	< 0.17 U	< 0.47 U	< 0.15 U	< 0.16 U	< 0.12 UJ	< 0.094 U	< 0.096 UJ	< 0.097 U	< 0.13 U	< 0.092 U	< 0.18 U	< 0.16 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	0.024 J	< 0.0027 U	< 0.002 U	< 0.0016 UJ	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 UJ	< 0.0032 UJ
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3863	DUP-39	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	0.038	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0027 UJ
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	0.043	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	0.0055	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0025 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Football Field	SSHS-B3864	DUP-37	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.009 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3864	DUP-38	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	0.0056	< 0.0022 U	< 0.0017 U	0.013	< 0.0081 U	0.014	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	0.0017 J	0.0084 J+	< 0.0028 UJ
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	0.018	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UJ	< 0.0026 UJ
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	0.0075	< 0.0077 U	0.0092	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.0097 U	< 0.01 U	< 0.0082 U	< 0.014 U	< 0.039 U	< 0.013 U	< 0.013 U	< 0.0096 U	< 0.0077 U	< 0.0079 U	< 0.0080 U	< 0.011 U	< 0.0075 U	< 0.014 U	< 0.013 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U	< 0.034 U	< 0.0019 U	< 0.0014 U	< 0.034 U	< 0.0025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0052	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0015 U	< 0.034 U	< 0.002 U	< 0.0015 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U	< 0.034 U	< 0.0019 U	< 0.0014 U	< 0.034 U	< 0.0024 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	**1,1,2-Trichloroethane**	**Trichloroethene**	**Trichlorofluoromethane**	**Vinyl chloride**	**Xylene (m)**	**Xylene (o)**	**Xylenes (Total)**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	20 - 22 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated	< 0.11 U	< 0.063 U	< 0.1 U	< 0.27 UJ	< 0.23 U	< 0.11 U	< 0.13 U	< 0.46 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.002 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.002 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3863	DUP-39	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0072 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.002 U	< 0.0071 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0072 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3864	DUP-37	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	SSHS-B3864	DUP-38	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 UJ	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.0021 U	< 0.0012 U	0.002 J	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0021 J	< 0.0046 U	< 0.004 U	0.031	0.038	0.069
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.001 U	0.0024 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.0087 U	< 0.0052 U	< 0.0082 U	< 0.022 U	< 0.019 U	< 0.0093 U	< 0.011 U	< 0.038 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.007 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0073 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0068 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**	**Chlorobenzene**	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	0.013 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0034 U	< 0.034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< UJ	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0027 U	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0028 U	< 0.0018 U	< 0.0034 U	< 0.0040 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0044 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.25 U	< 0.09 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.26 U	< 0.13 U	< 0.083 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.21 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 WARN	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.0051 UHT	< 0.0019 UHT	< 0.0040 UHT	< 0.0031 UHT	< 0.0033 UHT	< 0.0030 UHT	< 0.0053 WARN	< 0.0027 UHT	< 0.0017 UHT	< 0.0033 UHT	< 0.0039 UHT	< 0.0021 UHT	< 0.0026 UHT	< 0.0032 UHT	< 0.0043 UHT
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	0.013 J	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	0.015 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	0.011 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.002 U	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	0.012 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	0.0095 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	0.0086 J	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	0.011 J	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.004 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	0.014 J	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.004 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	0.011 J	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	0.01 J	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	0.016 J	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.003 U	< 0.0033 U	< 0.003 U	< 0.0052 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	0.0036 J	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	0.0044 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.0054 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0035 U	< 0.0031 U	< 0.0055 U	< 0.0028 U	< 0.0018 U	< 0.0034 U	< 0.004 U	< 0.0022 U	< 0.0027 U	< 0.0033 U	< 0.0044 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.0055 U	< 0.002 U	< 0.0042 U	< 0.0033 U	< 0.0035 U	< 0.0032 U	< 0.0056 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0041 U	< 0.0023 U	< 0.0028 U	< 0.0034 U	< 0.0045 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1.2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.0025 U	< 0.034 U	< 0.0032 U	< 0.0032 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< UJ	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	0.0071	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	0.0065	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0013 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0022 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	0.0083	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	0.0077	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.0024 U	< 0.034 U	< 0.003 U	< 0.0031 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.0024 U	< 0.034 U	< 0.0031 U	< 0.0031 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U	< 0.0030 U	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0061 U	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0031 U	< 0.0055 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.0030 U	< 0.0031 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.29 U	< 0.087 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.096 U	< 0.1 U	< 0.092 U	< 0.14 U	< 0.26 U	< 0.096 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.14 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.0060 UHT	< 0.0018 UHT	< 0.0033 UHT	< 0.0022 UHT	< 0.0041 UHT	< 0.0020 UHT	< 0.0021 UHT	< 0.0019 UHT	< 0.0030 UHT	< 0.0054 UHT	< 0.0020 UHT	< 0.0023 UHT	< 0.0018 UHT	< 0.0029 UHT	< 0.0030 UHT
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 UJ	< 0.0034 UJ	< 0.0016 UJ	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 UJ	< 0.0034 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.004 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U	< 0.0053 U	< 0.002 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	0.0035 J	0.016	0.018	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	0.0025 J	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.0062 U	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.0021 U	< 0.0022 U	< 0.002 U	< 0.0031 U	< 0.0056 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.003 U	< 0.0031 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.0063 U	< 0.0019 U	< 0.0035 U	< 0.0024 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.002 U	< 0.0032 U	< 0.0057 U	< 0.0021 U	< 0.0025 U	< 0.0019 U	< 0.0031 U	< 0.0032 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	0.0059	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	0.0056	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	0.0069	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.0031 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0019 U	< 0.034 U	< 0.0026 U	< 0.0018 U	< 0.034 U	< 0.0032 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.0021 U	< 0.034 U	< 0.0029 U	< 0.0021 U	< 0.034 U	< 0.0036 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< UJ	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0028 J	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0018 U	< 0.034 U	< 0.0031 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.0018 U	< 0.0014 U	< 0.0015 U	< 0.034 U	< 0.002 U	< 0.0014 U	< 0.034 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.0025 U	< 0.002 U	< 0.002 U	< 0.034 U	< 0.0027 U	< 0.002 U	< 0.034 U	< 0.0035 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.0031 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.0025 U	< 0.002 U	< 0.0021 U	< 0.034 U	< 0.0028 U	< 0.002 U	< 0.034 U	< 0.0035 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0034 U	< 0.0096 U	< 0.0032 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0025 U	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.01 U	< 0.0033 U	< 0.0034 U	< 0.0025 U	< 0.0020 U	< 0.0020 U	< 0.0021 U	< 0.0027 U	< 0.0020 U	< 0.0037 U	< 0.0034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.12 U	< 0.13 U	< 0.1 U	< 0.17 U	< 0.47 U	< 0.15 U	< 0.16 U	< 0.12 U	< 0.094 U	< 0.096 U	< 0.097 U	< 0.13 U	< 0.092 U	< 0.18 U	< 0.16 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.0024 UHT	< 0.0026 UHT	< 0.0021 UHT	< 0.0034 UHT	< 0.0097 UHT	< 0.0032 UHT	< 0.0034 UHT	< 0.0024 UHT	< 0.0019 UHT	< 0.0020 UHT	< 0.0020 UHT	< 0.0027 UHT	< 0.0019 UHT	< 0.0036 UHT	< 0.0034 UHT
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	0.003 J	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	0.014	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	0.028	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	0.0049 J	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.009 U	< 0.003 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.002 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.002 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U	< 0.002 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	0.0055	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0033 U	< 0.0035 U	< 0.0025 U	< 0.002 U	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.002 U	< 0.0038 U	< 0.0035 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.0026 U	< 0.0028 U	< 0.0022 U	< 0.0037 U	< 0.01 U	< 0.0034 U	< 0.0036 U	< 0.0026 U	< 0.0021 U	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.002 U	< 0.0039 U	< 0.0036 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0087 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0092 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.01 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	43 - 45 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0074 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.0089 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0071 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.0098 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0087 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.01 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.0021 U	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0023 U	< 0.0013 U	< 0.0021 U	< 0.0056 U	< 0.0049 U	< 0.0024 U	< 0.0027 U	< 0.0098 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.11 U	< 0.063 U	< 0.1 U	< 0.27 U	< 0.23 U	< 0.11 U	< 0.13 U	< 0.46 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0020 U	< 0.0052 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.0022 UHT	< 0.0013 UHT	< 0.0021 UHT	< 0.0055 UHT	< 0.0048 UHT	< 0.0024 UHT	< 0.0027 UHT	< 0.0095 UHT
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0071	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.0016 U	< 0.00096 U	0.0026 J	< 0.004 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.007 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.002 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.002 U	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0022 U	< 0.0057 U	< 0.0049 U	< 0.0024 U	< 0.0028 U	< 0.0099 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0022 U	< 0.0058 U	< 0.0051 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.0017 U	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	0.0091 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0030 U	< 0.0040 UT
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0040 U	< 0.0031 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0039 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0043 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0052 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	40 J	< 5.3 U	< 11 U	< 8.7 U	< 9.4 U	< 8.5 U	< 15 U	< 7.6 U	< 4.9 U	< 9.3 U	< 11 U	< 6 U	< 7.4 U	< 9 U	< 12 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 250 U	< 91 U	< 190 U	< 150 U	< 160 U	< 150 U	< 260 U	< 130 U	< 84 U	< 160 U	< 190 U	< 100 U	< 130 U	< 160 U	< 210 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18	5/11/2021	856.50	16 - 18 ft	1801214742	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	0.0056 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.0058 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	< 17 U	< 5.1 U	< 9.3 U	< 6.3 U	< 12 U	< 5.6 U	< 6 U	< 5.4 U	< 8.4 U	< 15 U	< 5.6 U	< 6.5 U	< 5 U	< 8.3 U	< 8.4 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 290 U	< 89 U	< 160 U	< 110 U	< 200 U	< 97 U	< 100 U	< 93 U	< 150 U	< 260 U	< 98 U	< 110 U	< 86 U	< 140 U	< 150 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	0.013	< 0.0017 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18	5/11/2021	856.50	16 - 18 ft	1801214742	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0029 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	0.0054 J	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

								Ethylbenzene	**Freon 113**	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**	**Styrene**	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.0025 U	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.0099 U	< 0.0032 U	< 0.0034 U	< 0.0025 U	< 0.0020 U	< 0.0020 U	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.0024 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	< 6.9 U	< 7.5 U	< 5.9 U	< 9.7 U	< 27 U	< 9 U	< 9.5 U	< 6.8 U	< 5.5 U	< 5.6 U	< 5.7 U	< 7.5 U	19	< 10 U	< 9.5 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 120 U	< 130 U	< 100 U	< 170 U	< 480 U	< 160 U	< 160 U	< 120 U	< 95 U	< 97 U	< 99 U	< 130 U	< 93 U	< 180 U	< 160 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.0021 U	0.0045 J	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0018 U	0.0023 J	0.0076	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	< 0.0023 U	0.056	< 0.002 U	< 0.0033 U	< 0.0093 U	0.0042 J	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	0.0054 J	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18	5/11/2021	856.50	16 - 18 ft	1801214742	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0028 J	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0018 U	< 0.034 U	< 0.0032 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0032 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.0031 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.034 U	< 0.0026 U	< 0.0018 U	< 0.034 U	< 0.0033 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0033 J	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.0021 U	< 0.0056 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0097 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0020 U	< 0.0052 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated	< 6.2 U	< 3.7 U	130	< 16 U	< 13 U	< 6.6 U	< 7.5 U	< 27 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated	< 110 U	< 64 U	170 J	< 270 U	< 230 U	< 120 U	< 130 U	< 470 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.026	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated	0.0033 J	< 0.0013 U	0.022	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0012 U	0.0059	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3920A	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18	5/11/2021	856.50	16 - 18 ft	1801214742	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	0.0032 J	0.0030 J	< 0.0080 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0083 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0083 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	0.0038 J	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.0091 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0087 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0092 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05	0.06						0.76	1.1			0.37			
Restricted - Residential								100	4.8						2.4	100			49			
Protection of Groundwater								0.05	0.06						0.76	1.1			0.37			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.078 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	0.014 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	0.0087 J	0.00029 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00044 U	< 0.00042 U	< 0.034 U	0.0007 J	< 0.034 U	< 0.00046 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.0054 U	0.00068 J	< 0.00046 U	< 0.00086 U	< 0.0032 U	< 0.00058 U	< 0.0032 U	< 0.00062 U	< 0.00085 U	< 0.00082 U	< 0.0014 U	0.00043 J	< 0.00039 U	0.0012 J	< 0.0032 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	0.025 J	0.00052 J	< 0.00043 U	< 0.00079 U	< 0.003 U	< 0.00053 U	< 0.003 U	< 0.00057 U	< 0.00078 U	< 0.00076 U	< 0.0013 U	< 0.00037 U	< 0.00036 U	0.0011 J	< 0.003 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	0.076	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0042 U	< 0.0072 U	< 0.002 U	< 0.0057 U	< 0.0016 U	< 0.0048 U	< 0.0048 U	< 0.0014 U	< 0.004 U	< 0.0024 U	< 0.0063 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.0007 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.0046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0044 U	< 0.034 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	0.035 J+	0.0016 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.02 J+	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0022 J	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00089 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.034 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-20-22	10/25/2021	852.55	20 - 22 ft	180-128986-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-22-24	10/25/2021	852.55	22 - 24 ft	180-128986-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-24-26	10/25/2021	852.55	24 - 26 ft	180-128986-1	Not Excavated	< 0.005 U	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-26-28	10/25/2021	852.55	26 - 28 ft	180-128986-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-28-30	10/25/2021	852.55	28 - 30 ft	180-128986-1	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.004 U	< 0.0031 U	< 0.0034 U	< 0.003 U	< 0.0053 U	< 0.0027 U	< 0.0017 U	< 0.0033 U	< 0.0039 U	< 0.0021 U	< 0.0026 U	< 0.0032 U	< 0.0043 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-20-22	10/25/2021	854.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-22-24	10/25/2021	854.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-24-26	10/25/2021	854.31	24 - 26 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-26-28	10/26/2021	854.31	26 - 28 ft	180-129052-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-28-30	10/26/2021	854.31	28 - 30 ft	180-129052-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.002 U	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-20-22	10/25/2021	853.70	20 - 22 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-22-24	10/25/2021	853.70	22 - 24 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-24-26	10/25/2021	853.70	24 - 26 ft	180-128986-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-20-22	11/1/2021	854.60	20 - 22 ft	180-129325-1	Not Excavated	< 0.017 U	< 0.00057 U	< 0.001 U	< 0.0012 U	< 0.002 U	< 0.0034 U	0.0025 J	< 0.0026 U	< 0.00074 U	< 0.0023 U	< 0.0022 U	< 0.00064 U	< 0.0019 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-22-24	11/1/2021	854.60	22 - 24 ft	180-129325-1	Not Excavated	< 0.021 U	< 0.0007 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0042 U	< 0.0012 U	< 0.0033 U	< 0.00092 U	< 0.0028 U	< 0.0028 U	< 0.00079 U	< 0.0023 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-24-26	11/1/2021	854.60	24 - 26 ft	180-129325-1	Not Excavated	< 0.019 U	< 0.00064 U	< 0.0011 U	< 0.0014 U	< 0.0022 U	< 0.0038 U	< 0.0011 U	< 0.003 U	< 0.00084 U	< 0.0025 U	< 0.0025 U	< 0.00072 U	< 0.0021 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-26-28	11/1/2021	854.60	26 - 28 ft	180-129325-1	Not Excavated	< 0.02 U	< 0.00066 U	< 0.0012 U	< 0.0014 U	< 0.0023 U	< 0.0039 U	< 0.0011 U	< 0.0031 U	< 0.00086 U	< 0.0026 U	< 0.0026 U	< 0.00074 U	< 0.0021 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-16-18	11/1/2021	852.29	16 - 18 ft	180-129325-1	Not Excavated	< 0.025 U	< 0.00083 U	< 0.0015 U	< 0.0018 U	< 0.0028 U	< 0.0049 U	< 0.0014 U	< 0.0039 U	< 0.0011 U	< 0.0033 U	< 0.0032 U	< 0.00093 U	< 0.0027 U	< 0.0016 U	< 0.0043 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-18-20	11/1/2021	852.29	18 - 20 ft	180-129325-1	Not Excavated	< 0.029 U	< 0.00097 U	< 0.0017 U	< 0.0021 U	< 0.0033 U	< 0.0058 U	< 0.0016 U	< 0.0045 U	< 0.0013 U	< 0.0039 U	< 0.0038 U	< 0.0011 U	< 0.0032 U	< 0.0019 U	< 0.005 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-20-22	11/1/2021	852.29	20 - 22 ft	180-129325-1	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U	< 0.00082 U	< 0.0025 U	< 0.0024 U	< 0.0007 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-22-24	11/1/2021	852.29	22 - 24 ft	180-129325-1	Not Excavated	< 0.016 U	< 0.00052 U	< 0.00092 U	< 0.0011 U	< 0.0018 U	< 0.0031 U	< 0.00087 U	< 0.0024 U	< 0.00068 U	< 0.0021 U	< 0.002 U	< 0.00059 U	< 0.0017 U	< 0.001 U	< 0.0027 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-24-26	11/1/2021	852.29	24 - 26 ft	180-129325-1	Not Excavated	< 0.024 U	< 0.00079 U	< 0.0014 U	< 0.0017 U	< 0.0027 U	< 0.0047 U	< 0.0013 U	< 0.0037 U	< 0.001 U	< 0.0032 U	< 0.0031 U	< 0.00089 U	< 0.0026 U	< 0.0016 U	< 0.0041 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-26-28	11/1/2021	852.29	26 - 28 ft	180-129325-1	Not Excavated	0.022	< 0.00062 UJ	< 0.0011 U	< 0.0013 UJ	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U	< 0.00082 UJ	< 0.0025 U	< 0.0025 U	< 0.00071 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-20-22	10/26/2021	854.78	20 - 22 ft	180-129052-1	Not Excavated	< 0.0024 U	< 0.00088 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0025 U	< 0.0013 U	< 0.00081 U	< 0.0016 U	< 0.0018 U	< 0.001 U	< 0.0012 U	< 0.0015 U	< 0.002 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-22-24	10/26/2021	854.78	22 - 24 ft	180-129052-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-24-26	10/26/2021	854.78	24 - 26 ft	180-129052-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-26-28	10/26/2021	854.78	26 - 28 ft	180-129052-1	Not Excavated	< 0.0081 U	< 0.0029 U	< 0.0062 U	< 0.0048 U	< 0.0052 U	< 0.0047 U	< 0.0083 U	< 0.0042 U	< 0.0027 U	< 0.0052 U	< 0.0061 U	< 0.0033 U	< 0.0041 U	< 0.005 U	< 0.0067 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-28-30	10/26/2021	854.78	28 - 30 ft	180-129052-1	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.003 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-30-32	10/27/2021	854.78	30 - 32 ft	180-129169-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	0.016	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 UT	< 0.00048 U	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	0.00029 J	< 0.00057 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 UT	< 0.00035 U	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	0.00025 J	< 0.00041 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.0072 U	< 0.00033 U	< 0.00035 U	< 0.00032 U	< 0.00054 U	< 0.0013 U	< 0.00034 UT	< 0.00049 U	< 0.00022 U	< 0.00024 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	0.00056 J	< 0.00058 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	0.0097	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	0.00040 J	< 0.00042 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	0.00023 J	< 0.00043 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 UT	< 0.00037 U	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	0.00022 J	< 0.00042 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	0.0063	0.00064 J	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 UT	< 0.00032 U	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	0.0016	< 0.00038 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 UT	< 0.00034 U	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	0.00039 J	< 0.00040 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	0.0078	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	0.00032 JT	< 0.00031 U	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	0.00060 J	< 0.00037 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	0.01	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	0.00062 J	< 0.00043 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 UT	< 0.00037 U	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	< 0.0073	< 0.0022	< 0.001	< 0.0014	< 0.0033	< 0.0012	< 0.0015	< 0.00097	< 0.0016	< 0.0018	< 0.0015	< 0.00089	< 0.0019	< 0.0011	< 0.0032
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 UJ	< 0.0023 U	< 0.004 U	< 0.002 U	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0032 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	0.011 J	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 UJ	< 0.0025 U	< 0.0044 U	< 0.0022 U	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 UJ	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.003 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated	< 0.025 U	< 0.0062 U						< 0.0062 U	< 0.0062 U			< 0.0062 U			
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated	0.053 J	< 0.028 U						< 0.028 U	< 0.028 U			< 0.028 U			

								Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Restricted - Residential								100			100	49	13	26	3.1	100		100	100			
Protection of Groundwater								0.05			1.1	2.4	1.8	0.27	0.02	0.33		0.25	0.19			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	0.0058 J	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.082 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.089 U	< 0.034 U	< 0.086 U	< 0.034 U	< 0.034 U	< 0.09 U	< 0.1 U	< 0.034 U	< 0.13 U	< 0.13 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	0.0086	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.0023 U	< 0.034 U	< 0.0029 U	< 0.0029 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00046 U	< 0.034 U	< 0.00017 U	< 0.034 U	< 0.034 U	< 0.00042 U	< 0.00034 U	< 0.034 U	< 0.00048 U	< 0.0015 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.0029 U	< 0.00082 U	< 0.00053 U	< 0.0005 U	< 0.00033 U	< 0.0009 U	< 0.00078 U	< 0.00032 U	< 0.00078 U	< 0.0034 U	< 0.00082 U	< 0.00066 U	< 0.0032 U	< 0.00092 U	< 0.0028 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.0027 U	< 0.00076 U	< 0.00049 U	< 0.00046 U	< 0.0003 U	< 0.00083 U	< 0.00072 U	< 0.0003 U	< 0.00073 U	< 0.0031 U	< 0.00076 U	< 0.00061 U	< 0.003 U	< 0.00085 U	< 0.0026 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.021 U	< 0.0013 U	< 0.0016 UJ	< 0.0019 U	< 0.0014 U	< 0.0015 UJ	< 0.0012 U	< 0.0013 U	< 0.0032 U	< 0.002 U	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.005 U	< 0.0065 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 UJ	< 0.00098 U	< 0.00072 U	< 0.00078 UJ	< 0.00061 U	< 0.00068 U	< 0.0016 U	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.0032 U	< 0.034 U	< 0.0041 U	< 0.0042 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.001 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00085 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U	< 0.034 U	< 0.0028 U	< 0.0036 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-20-22	10/25/2021	852.55	20 - 22 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-22-24	10/25/2021	852.55	22 - 24 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-24-26	10/25/2021	852.55	24 - 26 ft	180-128986-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-26-28	10/25/2021	852.55	26 - 28 ft	180-128986-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-28-30	10/25/2021	852.55	28 - 30 ft	180-128986-1	Not Excavated	< 0.006 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0041 U	< 0.002 U	< 0.0021 U	< 0.0019 U	< 0.003 U	< 0.0054 U	< 0.002 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.003 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-20-22	10/25/2021	854.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-22-24	10/25/2021	854.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-24-26	10/25/2021	854.31	24 - 26 ft	180-128986-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-26-28	10/26/2021	854.31	26 - 28 ft	180-129052-1	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-28-30	10/26/2021	854.31	28 - 30 ft	180-129052-1	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-20-22	10/25/2021	853.70	20 - 22 ft	180-128986-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-22-24	10/25/2021	853.70	22 - 24 ft	180-128986-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 UJ	< 0.0026 U	< 0.0026 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-24-26	10/25/2021	853.70	24 - 26 ft	180-128986-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-20-22	11/1/2021	854.60	20 - 22 ft	180-129325-1	Not Excavated	< 0.0098 U	< 0.00063 U	< 0.00077 U	< 0.0009 U	< 0.00066 U	< 0.00072 U	< 0.00056 U	< 0.00063 U	< 0.0015 U	< 0.00091 U	< 0.0012 U	< 0.0012 U	< 0.00069 U	< 0.0023 U	< 0.003 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-22-24	11/1/2021	854.60	22 - 24 ft	180-129325-1	Not Excavated	< 0.012 U	< 0.00077 U	< 0.00095 U	< 0.0011 U	< 0.00082 U	< 0.00089 U	< 0.0007 U	< 0.00078 U	< 0.0018 U	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00086 U	< 0.0029 U	< 0.0037 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-24-26	11/1/2021	854.60	24 - 26 ft	180-129325-1	Not Excavated	< 0.011 U	< 0.0007 U	< 0.00086 U	< 0.001 U	< 0.00075 U	< 0.00081 U	< 0.00063 U	< 0.00071 U	< 0.0017 U	< 0.001 U	< 0.0014 U	< 0.0013 U	< 0.00078 U	< 0.0026 U	< 0.0034 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-26-28	11/1/2021	854.60	26 - 28 ft	180-129325-1	Not Excavated	< 0.011 U	< 0.00072 U	< 0.00089 U	< 0.001 U	< 0.00077 U	< 0.00083 U	< 0.00065 U	< 0.00073 U	< 0.0017 U	< 0.0011 U	< 0.0014 U	< 0.0013 U	< 0.0008 U	< 0.0027 U	< 0.0035 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-16-18	11/1/2021	852.29	16 - 18 ft	180-129325-1	Not Excavated	< 0.014 U	< 0.00091 U	< 0.0011 U	< 0.0013 U	< 0.00097 U	< 0.001 U	< 0.00082 U	< 0.00091 U	< 0.0022 U	< 0.0013 U	< 0.0018 U	< 0.0017 U	< 0.001 U	< 0.0034 U	< 0.0044 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-18-20	11/1/2021	852.29	18 - 20 ft	180-129325-1	Not Excavated	< 0.017 U	< 0.0011 U	< 0.0013 U	< 0.0015 U	< 0.0011 U	< 0.0012 U	< 0.00096 U	< 0.0011 U	< 0.0025 U	< 0.0016 U	< 0.0021 U	< 0.002 U	< 0.0012 U	< 0.004 U	< 0.0052 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-20-22	11/1/2021	852.29	20 - 22 ft	180-129325-1	Not Excavated	< 0.011 U	< 0.00069 U	< 0.00084 U	< 0.00099 U	< 0.00073 U	< 0.00079 U	< 0.00062 U	< 0.00069 U	< 0.0016 U	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00076 U	< 0.0026 U	< 0.0033 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-22-24	11/1/2021	852.29	22 - 24 ft	180-129325-1	Not Excavated	< 0.0089 U	< 0.00057 U	< 0.0007 U	< 0.00083 U	< 0.00061 U	< 0.00066 U	< 0.00052 U	< 0.00058 U	< 0.0014 U	< 0.00084 U	< 0.0011 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0028 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-24-26	11/1/2021	852.29	24 - 26 ft	180-129325-1	Not Excavated	< 0.014 U	< 0.00087 U	< 0.0011 U	< 0.0013 U	< 0.00092 U	< 0.001 U	< 0.00079 U	< 0.00087 U	< 0.0021 U	< 0.0013 U	< 0.0017 U	< 0.0016 U	< 0.00096 U	< 0.0033 U	< 0.0042 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-26-28	11/1/2021	852.29	26 - 28 ft	180-129325-1	Not Excavated	< 0.011 U	< 0.00069 UJ	< 0.00084 U	< 0.001 UJ	< 0.00073 UJ	< 0.00079 UJ	< 0.00062 U	< 0.00069 UJ	< 0.0016 U	< 0.001 U	< 0.0013 UJ	< 0.0013 U	< 0.00076 UJ	< 0.0026 UJ	< 0.0033 UJ
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-20-22	10/26/2021	854.78	20 - 22 ft	180-129052-1	Not Excavated	< 0.0028 U	< 0.00086 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.00094 U	< 0.001 U	< 0.0009 U	< 0.0014 U	< 0.0026 U	< 0.00094 U	< 0.0011 U	< 0.00083 U	< 0.0014 U	< 0.0014 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-22-24	10/26/2021	854.78	22 - 24 ft	180-129052-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-24-26	10/26/2021	854.78	24 - 26 ft	180-129052-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-26-28	10/26/2021	854.78	26 - 28 ft	180-129052-1	Not Excavated	< 0.0094 U	< 0.0028 U	< 0.0052 U	< 0.0035 U	< 0.0064 U	< 0.0031 U	< 0.0033 U	< 0.003 U	< 0.0047 U	< 0.0085 U	< 0.0031 U	< 0.0036 U	< 0.0028 U	< 0.0046 U	< 0.0047 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-28-30	10/26/2021	854.78	28 - 30 ft	180-129052-1	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-30-32	10/27/2021	854.78	30 - 32 ft	180-129169-1	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	0.0014 J	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00025 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	0.0011 J	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	0.0011 J	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	0.0011 J	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	0.0036	< 0.0015	< 0.0021	< 0.0023	< 0.0021	< 0.0021	< 0.0008	< 0.0008	< 0.001	< 0.0017	< 0.00096	< 0.00073	< 0.0013	< 0.0016	< 0.0017
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.0045 U	< 0.0014 UJ	< 0.0025 U	< 0.0017 U	< 0.003 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U	< 0.004 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	< 0.0049 U	< 0.0015 UJ	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.0042 U	< 0.0013 UJ	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated	< 0.0062 U			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0062 U	< 0.0062 U	< 0.0062 U		< 0.0062 U	< 0.0062 U			
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated	< 0.028 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.028 U	< 0.028 U	< 0.028 U		< 0.028 U	< 0.028 U			

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								1						0.12		0.93			1.3	0.7		
Restricted - Residential								41						100		100			19	100		
Protection of Groundwater								1						0.12		0.93			1.3	0.7		
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]															
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.11 U	< 0.088 U	< 0.089 U	< 0.034 U	< 0.12 U	< 0.086 U	< 0.034 U	< 0.15 UJ
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0032 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.0024 U	< 0.0019 U	< 0.0019 U	< 0.034 U	< 0.0026 U	< 0.0019 U	< 0.034 U	< 0.0033 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00046 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.00023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00071 J	< 0.034 U	< 0.0011 U	< 0.00032 U	< 0.00017 U	< 0.034 U	< 0.00044 U	0.00048 J	< 0.034 U	< 0.0002 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.00044 U	< 0.0015 U	< 0.0032 U	< 0.00097 UJ	< 0.0039 U	0.0023 J	< 0.0023 U	< 0.0021 U	< 0.00063 U	< 0.00032 U	< 0.001 U	< 0.00086 U	0.0019 J	< 0.00068 U	< 0.00039 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.00041 U	< 0.0014 U	< 0.003 U	< 0.00089 U	0.014 J	0.0018 J	< 0.0022 U	< 0.0019 U	< 0.00058 U	< 0.0003 U	< 0.00096 U	< 0.0008 U	0.0013 J	< 0.00063 U	< 0.00036 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.0018 UJ	< 0.0022 U	< 0.0071 U	< 0.0033 UJ	< 0.0059 U	< 0.0021 U	< 0.0062 U	< 0.0065 U	< 0.0034 U	< 0.002 U	< 0.0025 U	< 0.0013 U	< 0.0013 U	< 0.0051 U	< 0.0044 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.00093 UJ	< 0.0011 U	< 0.0036 U	< 0.0017 UJ	< 0.003 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0018 U	< 0.001 U	< 0.0013 U	< 0.00065 U	< 0.00068 U	< 0.0026 U	< 0.0022 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0045 U	< 0.034 U	< 0.0034 U	< 0.0027 U	< 0.0028 U	< 0.034 U	< 0.0037 U	< 0.0027 U	< 0.034 U	< 0.0047 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.017 J	0.0062 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0011 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.001 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0036 U	< 0.0019 U	< 0.0011 U	< 0.034 U	< 0.00071 U	< 0.00075 U	< 0.034 U	< 0.0024 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-20-22	10/25/2021	852.55	20 - 22 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-22-24	10/25/2021	852.55	22 - 24 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-24-26	10/25/2021	852.55	24 - 26 ft	180-128986-1	Not Excavated	< 0.0024 U	0.0039 J	< 0.002 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	0.0026 J	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-26-28	10/25/2021	852.55	26 - 28 ft	180-128986-1	Not Excavated	< 0.0019 U	0.0035 J	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-28-30	10/25/2021	852.55	28 - 30 ft	180-128986-1	Not Excavated	< 0.0025 U	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.0098 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.002 U	< 0.002 U	< 0.002 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-20-22	10/25/2021	854.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-22-24	10/25/2021	854.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.007 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-24-26	10/25/2021	854.31	24 - 26 ft	180-128986-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-26-28	10/26/2021	854.31	26 - 28 ft	180-129052-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-28-30	10/26/2021	854.31	28 - 30 ft	180-129052-1	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-20-22	10/25/2021	853.70	20 - 22 ft	180-128986-1	Not Excavated	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-22-24	10/25/2021	853.70	22 - 24 ft	180-128986-1	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-24-26	10/25/2021	853.70	24 - 26 ft	180-128986-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-20-22	11/1/2021	854.60	20 - 22 ft	180-129325-1	Not Excavated	< 0.00085 U	< 0.001 U	< 0.0033 U	< 0.0016 U	< 0.0028 U	0.0012 J	< 0.0029 U	< 0.003 U	< 0.0016 U	< 0.00094 U	< 0.0012 U	0.00098 J	0.00074 J	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-22-24	11/1/2021	854.60	22 - 24 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0013 U	< 0.0041 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0036 U	< 0.0037 U	< 0.002 U	< 0.0012 U	< 0.0014 U	< 0.00073 U	< 0.00078 U	< 0.003 U	< 0.0025 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-24-26	11/1/2021	854.60	24 - 26 ft	180-129325-1	Not Excavated	< 0.00096 U	< 0.0012 U	< 0.0037 U	< 0.0018 U	< 0.0031 U	< 0.0011 U	< 0.0033 U	< 0.0034 U	< 0.0018 U	< 0.0011 U	< 0.0013 U	< 0.00067 U	< 0.00071 U	< 0.0027 U	< 0.0023 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-26-28	11/1/2021	854.60	26 - 28 ft	180-129325-1	Not Excavated	< 0.00098 U	< 0.0012 U	< 0.0038 U	< 0.0018 U	< 0.0032 U	< 0.0012 U	< 0.0033 U	< 0.0035 U	< 0.0019 U	< 0.0011 U	< 0.0013 U	< 0.00069 U	< 0.00073 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-16-18	11/1/2021	852.29	16 - 18 ft	180-129325-1	Not Excavated	< 0.0012 U	< 0.0015 U	< 0.0048 U	< 0.0023 U	< 0.004 U	< 0.0015 U	< 0.0042 U	< 0.0044 U	< 0.0023 U	< 0.0014 U	< 0.0017 U	0.00091 J	< 0.00092 U	< 0.0035 U	< 0.003 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-18-20	11/1/2021	852.29	18 - 20 ft	180-129325-1	Not Excavated	< 0.0015 U	< 0.0018 U	< 0.0057 U	< 0.0027 U	< 0.0047 U	< 0.0017 U	< 0.0049 U	< 0.0052 U	< 0.0028 U	< 0.0016 U	< 0.002 U	0.005 J	< 0.0011 U	< 0.0041 U	< 0.0035 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-20-22	11/1/2021	852.29	20 - 22 ft	180-129325-1	Not Excavated	< 0.00093 U	0.0051	< 0.0036 U	< 0.0017 U	< 0.003 U	< 0.0011 U	< 0.0032 U	< 0.0033 U	< 0.0018 U	< 0.001 U	< 0.0013 U	0.0077	< 0.00069 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-22-24	11/1/2021	852.29	22 - 24 ft	180-129325-1	Not Excavated	< 0.00078 U	0.011	< 0.003 U	< 0.0014 U	< 0.0025 U	< 0.00091 U	< 0.0027 U	< 0.0028 U	< 0.0015 U	< 0.00086 U	< 0.0011 U	0.0098	< 0.00058 U	< 0.0022 U	< 0.0019 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-24-26	11/1/2021	852.29	24 - 26 ft	180-129325-1	Not Excavated	< 0.0012 U	< 0.0015 U	< 0.0046 U	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.004 U	< 0.0042 U	< 0.0022 U	< 0.0013 U	< 0.0016 U	< 0.00083 U	< 0.00088 U	< 0.0033 U	< 0.0028 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-26-28	11/1/2021	852.29	26 - 28 ft	180-129325-1	Not Excavated	< 0.00094 UJ	< 0.0011 U	< 0.0037 U	< 0.0017 UJ	< 0.003 U	< 0.0011 U	< 0.0032 U	< 0.0033 U	< 0.0018 U	< 0.001 UJ	< 0.0013 U	< 0.00065 UJ	< 0.00069 UJ	< 0.0026 UJ	< 0.0022 UJ
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-20-22	10/26/2021	854.78	20 - 22 ft	180-129052-1	Not Excavated	< 0.0012 U	< 0.0013 U	< 0.00098 U	< 0.0016 U	< 0.0046 U	< 0.0015 U	< 0.0016 U	< 0.0011 U	< 0.00092 U	< 0.00094 U	< 0.00095 U	< 0.0013 U	< 0.0009 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-22-24	10/26/2021	854.78	22 - 24 ft	180-129052-1	Not Excavated	< 0.0021 U	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-24-26	10/26/2021	854.78	24 - 26 ft	180-129052-1	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-26-28	10/26/2021	854.78	26 - 28 ft	180-129052-1	Not Excavated	< 0.0038 U	< 0.0042 U	< 0.0033 U	< 0.0054 U	< 0.015 U	< 0.005 U	< 0.0053 U	< 0.0038 U	< 0.0031 U	< 0.0031 U	< 0.0032 U	< 0.0042 U	< 0.003 U	< 0.0057 U	< 0.0053 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-28-30	10/26/2021	854.78	28 - 30 ft	180-129052-1	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-30-32	10/27/2021	854.78	30 - 32 ft	180-129169-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	< 0.00025 U	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U	< 0.00035 U	< 0.00027 U	0.00098 J	0.00042 J	< 0.00023 U	< 0.00045 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.00018 U	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U	< 0.00025 U	< 0.00019 U	0.00071 J	0.00022 J	< 0.00016 U	< 0.00032 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.00025 U	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0054 U	0.0012 J	< 0.00046 U	< 0.0020 U	< 0.00065 U	< 0.00035 U	< 0.00027 U	0.00079 J	0.00055 J	< 0.00023 U	< 0.00045 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.00018 U	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	0.00066 J	< 0.00033 U	< 0.0014 U	< 0.00046 U	< 0.00025 U	< 0.00019 U	0.00053 J	0.00032 J	< 0.00016 U	< 0.00032 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.00019 U	0.0011	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U	< 0.00026 U	< 0.00020 U	0.0012	0.00024 J	< 0.00017 U	< 0.00034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	< 0.00019 U	0.011	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U	< 0.00021 U	0.0057	< 0.00022 U	< 0.00017 U	< 0.00034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.00018 U	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U	< 0.00025 U	< 0.00020 U	0.00064 J	< 0.00021 U	< 0.00017 U	< 0.00033 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.00019 U	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U	< 0.00026 U	< 0.00020 U	0.00062 J	< 0.00022 U	< 0.00017 U	< 0.00034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	0.0033	< 0.00030 U	< 0.0013 U	< 0.00042 U	< 0.00023 U	< 0.00018 U	0.00053 J	0.0017	< 0.00015 U	< 0.00029 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	0.00069 J	< 0.00032 U	< 0.0014 U	< 0.00045 U	< 0.00024 U	< 0.00019 U	0.00051 J	0.00043 J	< 0.00016 U	< 0.00031 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	0.0012	< 0.00030 U	< 0.0013 U	< 0.00041 U	< 0.00022 U	< 0.00017 U	0.00044 J	0.00049 J	< 0.00015 U	< 0.00029 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	< 0.00019 U	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	0.0011	< 0.00034 U	< 0.0015 U	< 0.00048 U	< 0.00026 U	< 0.00020 U	0.00038 J	0.00038 J	< 0.00017 U	< 0.00034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.00018 U	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U	< 0.00025 U	< 0.00020 U	0.00029 J	< 0.00021 U	< 0.00017 U	< 0.00033 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.00019 U	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	< 0.0014	< 0.00098	< 0.0029	< 0.0025	< 0.0095	< 0.0013	< 0.0021	< 0.0025	< 0.0018	< 0.0017	< 0.0028	< 0.00088	< 0.0026	< 0.0029	< 0.0029
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0073 UJ	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0027 U	< 0.0025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	< 0.002 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 UJ	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 UJ	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated	< 0.0062 U						< 0.012 U					0.0052 J	< 0.0062 U		
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated	< 0.028 U						0.014 J					0.026 J	< 0.028 U		

TABLE 5-7D
Deep Soil Results - Remedial Investigation - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

								1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
								mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted								0.68		0.47		0.02			0.26
Restricted - Residential								100		21		0.9			100
Protection of Groundwater								0.68		0.47		0.02			1.6
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.43 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0093 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	0.00073 J	< 0.034 U	< 0.034 U	< 0.00056 U	< 0.034 U	< 0.00056 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated	< 0.00047 U	< 0.00083 U	< 0.0014 U	< 0.00061 U	< 0.00078 U	0.0014 J	< 0.00084 U	0.0014 J
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated	< 0.00043 U	< 0.00077 U	< 0.0013 U	< 0.00056 U	< 0.00072 U	0.0013 J	< 0.00077 U	0.0013 J
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0011 U	< 0.0047 U	< 0.0031 U	< 0.0014 UJ	< 0.0015 U	< 0.0028 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.00056 U	< 0.0024 U	< 0.0016 U	< 0.00069 UJ	< 0.00076 U	< 0.0014 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.013 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0083 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.002 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.0015 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-20-22	10/25/2021	852.55	20 - 22 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.0019 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-22-24	10/25/2021	852.55	22 - 24 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.001 U	< 0.0017 UJ	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-24-26	10/25/2021	852.55	24 - 26 ft	180-128986-1	Not Excavated	< 0.0021 U	< 0.0013 U	0.096	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-26-28	10/25/2021	852.55	26 - 28 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.001 U	0.087	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B4260	SSHS-B4260-SUB-28-30	10/25/2021	852.55	28 - 30 ft	180-128986-1	Not Excavated	< 0.0022 U	< 0.0013 U	< 0.0021 U	< 0.0055 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0096 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-20-22	10/25/2021	854.31	20 - 22 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-22-24	10/25/2021	854.31	22 - 24 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-24-26	10/25/2021	854.31	24 - 26 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-26-28	10/26/2021	854.31	26 - 28 ft	180-129052-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	SSHS-B4261	SSHS-B4261-SUB-28-30	10/26/2021	854.31	28 - 30 ft	180-129052-1	Not Excavated	< 0.0016 U	< 0.00096 U	< 0.0015 U	< 0.004 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.007 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-20-22	10/25/2021	853.70	20 - 22 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0012 U	0.0051 J	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-22-24	10/25/2021	853.70	22 - 24 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	SSHS-B4262	SSHS-B4262-SUB-24-26	10/25/2021	853.70	24 - 26 ft	180-128986-1	Not Excavated	< 0.0019 U	< 0.0011 U	0.004 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-20-22	11/1/2021	854.60	20 - 22 ft	180-129325-1	Not Excavated	< 0.0014 U	< 0.00092 U	0.0019 J	< 0.0022 U	< 0.0014 U	< 0.00064 U	< 0.0007 U	< 0.0013 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-22-24	11/1/2021	854.60	22 - 24 ft	180-129325-1	Not Excavated	< 0.0018 U	< 0.0011 U	0.00068 J	< 0.0027 U	< 0.0018 U	< 0.00079 U	< 0.00087 U	< 0.0016 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-24-26	11/1/2021	854.60	24 - 26 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.00058 U	< 0.0025 U	< 0.0016 U	< 0.00072 U	< 0.00079 U	< 0.0015 U
Northern Athletic Field	SSHS-B4263	SSHS-B4263-SUB-26-28	11/1/2021	854.60	26 - 28 ft	180-129325-1	Not Excavated	< 0.0017 U	< 0.0011 U	< 0.00059 U	< 0.0025 U	< 0.0017 U	< 0.00074 U	< 0.00081 U	< 0.0015 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-16-18	11/1/2021	852.29	16 - 18 ft	180-129325-1	Not Excavated	< 0.0021 U	< 0.0013 U	0.0041 J	< 0.0032 U	< 0.0021 U	< 0.00093 U	< 0.001 U	< 0.0019 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-18-20	11/1/2021	852.29	18 - 20 ft	180-129325-1	Not Excavated	< 0.0025 U	< 0.0016 U	0.0093	< 0.0037 U	< 0.0025 U	< 0.0011 U	< 0.0012 U	< 0.0022 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-20-22	11/1/2021	852.29	20 - 22 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.001 U	0.025	< 0.0024 U	< 0.0016 U	< 0.0007 U	< 0.00077 U	< 0.0014 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-22-24	11/1/2021	852.29	22 - 24 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.00084 U	0.041	< 0.002 U	< 0.0013 U	< 0.00058 U	< 0.00064 U	< 0.0012 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-24-26	11/1/2021	852.29	24 - 26 ft	180-129325-1	Not Excavated	< 0.002 U	< 0.0013 U	< 0.00072 U	< 0.003 U	< 0.002 U	< 0.00089 U	< 0.00098 U	< 0.0018 U
Northern Athletic Field	SSHS-B4264	SSHS-B4264-SUB-26-28	11/1/2021	852.29	26 - 28 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.00057 U	< 0.0024 U	< 0.0016 U	< 0.0007 UJ	< 0.00077 UJ	< 0.0014 UJ
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-20-22	10/26/2021	854.78	20 - 22 ft	180-129052-1	Not Excavated	< 0.001 U	< 0.00062 U	< 0.00098 U	< 0.0026 U	< 0.0023 U	< 0.0011 U	< 0.0013 U	< 0.0045 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-22-24	10/26/2021	854.78	22 - 24 ft	180-129052-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-24-26	10/26/2021	854.78	24 - 26 ft	180-129052-1	Not Excavated	< 0.0019 U	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-26-28	10/26/2021	854.78	26 - 28 ft	180-129052-1	Not Excavated	< 0.0035 U	< 0.0021 U	< 0.0033 U	< 0.0086 U	< 0.0075 U	< 0.0037 U	< 0.0042 U	< 0.015 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-28-30	10/26/2021	854.78	28 - 30 ft	180-129052-1	Not Excavated	< 0.0015 U	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	SSHS-B4265	SSHS-B4265-SUB-30-32	10/27/2021	854.78	30 - 32 ft	180-129169-1	Not Excavated	< 0.0021 U	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated	< 0.00029 U	< 0.00022 U	0.00075 J	< 0.00051 U	< 0.00068 U	0.00070 J	< 0.00024 U	0.00070 J
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated	< 0.00021 U	< 0.00016 U	0.00045 J	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated	< 0.00029 U	< 0.00022 U	0.00073 J	< 0.00051 U	< 0.00069 U	0.00039 J	< 0.00024 U	0.00039 J
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated	< 0.00021 U	< 0.00016 U	0.00035 J	< 0.00037 U	< 0.00050 U	0.00023 J	< 0.00018 U	0.00023 J
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00017 U	0.0035	< 0.00038 U	< 0.00051 U	0.00016 J	< 0.00018 U	0.00016 J
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated	0.00023 J	< 0.00017 U	0.028	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated	< 0.00021 U	< 0.00016 U	0.00035 J	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00017 U	0.00046 J	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated	< 0.00019 U	< 0.00015 U	0.00040 J	< 0.00033 U	< 0.00045 U	0.0011	0.00020 J	0.0013 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated	< 0.00020 U	< 0.00016 U	0.00031 J	< 0.00036 U	< 0.00048 U	0.00027 J	< 0.00017 U	0.00027 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated	< 0.00019 U	< 0.00014 U	0.00030 J	< 0.00033 U	< 0.00044 U	0.00047 J	< 0.00016 U	0.00047 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00017 U	0.00030 J	< 0.00038 U	< 0.00051 U	0.00027 J	< 0.00018 U	0.00027 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated	< 0.00021 U	< 0.00016 U	0.00036 J	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00017 U	0.00034 J	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated	< 0.00077	< 0.002	< 0.0008	< 0.0021	< 0.0018		< 0.0021	< 0.0032
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0071 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated	< 0.0016 U	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	16 - 18 ft	NA	Not Excavated	< 0.0062 U		< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	17 - 19 ft	NA	Not Excavated	< 0.028 U		< 0.028 U		< 0.028 U	< 0.028 U	< 0.028 U	

									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100							
Restricted - Residential									13000	13000	13000							
Protection of Groundwater									100	100	100							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	855.30	16 - 18 ft	1801217051	Not Excavated	< 110 U			< 0.36 U	< 0.025 U	< 0.027 U	< 0.038 U	< 0.022 U	< 0.066 U	< 0.034 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated	< 110 U									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519452	Not Excavated				< 0.21 UHT	< 0.17 UHT	< 0.20 U	< 0.23 UHT	< 0.21 UHT	< 0.13 UHT	< 0.22 UHT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	0.039 BJ	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 120 U			< 0.42 U	< 0.028 U	0.39 B	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 110 U			< 0.42 U	< 0.028 U	0.36 B	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	0.46 B	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated			< 34 U							
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated			< 110 U							
Football Field	SSHS-B3855	041321 09:30_DUP-03	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated			< 120 U							
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated			< 110 U							
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated			< 110 U	< 0.38 U	< 0.025 U	0.043 J	< 0.04 U	< 0.022 U	< 0.068 U	< 0.036 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated			< 580 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated			< 110 U	< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.07 U	< 0.036 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated			< 110 U	< 0.39 UJ	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.07 U	< 0.037 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 120 U			< 0.42 U	< 0.028 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.039 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated			< 110 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	< 0.028 UJ	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated			< 120 U							
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated				< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.072 U	< 0.037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.036 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.046 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated			< 130 U							
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated			< 120 U							
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated			< 110 U							
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated			< 120 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.022 U	< 0.068 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated			< 110 U							
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated			< 190 U							
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.03 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated			< 120 U	< 0.051 U	< 0.04 U	0.081 J	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated		< 35 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508422	Not Excavated				< 0.057 U	< 0.045 U	< 0.055 U	< 0.062 U	< 0.057 U	< 0.036 U	< 0.058 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated		< 36 U								
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated			< 41							
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated			< 110 U							

DRAFT

									Emerging Contaminants									
									Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted														0.88	0.66			
Restricted - Residential														44	33			
Protection of Groundwater														3.7	1.1			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	855.30	16 - 18 ft	1801217051	Not Excavated	< 0.028 U	< 0.030 U	< 0.041 U	< 0.035 U	< 0.080 U	< 0.20 U	< 0.084 U	< 0.076 U	< 0.053 U	< 0.050 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated										
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519452	Not Excavated	< 0.17 UHT	< 0.13 UHT	< 0.14 UHT	< 0.097 UHT	< 0.15 UHT	< 0.19 UHT	< 0.23 UHT	< 0.18 UHT	< 0.16 UHT	< 0.092 UHT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated										
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.082 U	< 0.20 U	< 0.086 U	< 0.077 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.061 U	< 0.057 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.093 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.058 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	0.49 BJ	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3855	041321 09:30_DUP-03	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated										
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.037 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	0.057 J	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	0.089 J	< 0.057 U	< 0.054 UT
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.044 U	< 0.038 U	< 34 U	< 0.21 U	< 0.09 U	< 0.08 U	< 0.056 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.044 U	< 0.038 U	< 34 U	< 0.21 U	< 0.09 U	< 0.081 U	< 0.056 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.041 U	< 0.092 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.057 UT
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 UJ	< 0.036 U	< 0.083 U	< 0.2 U	< 0.087 U	0.092 J	< 0.055 U	< 0.052 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated										
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.030 U	< 0.032 U	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.082 U	< 0.20 U	< 0.086 U	< 0.077 U	< 0.054 U	< 0.051 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated										
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated										
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 34 U	< 0.2 U	< 0.088 U	< 0.079 U	< 0.055 U	< 34 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated										
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated										
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 34 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.04 U	< 0.031 U	< 0.033 U	< 0.023 U	< 34 U	< 0.046 U	< 0.056 U	< 0.044 U	< 0.039 U	< 34 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508422	Not Excavated	< 0.045 U	< 0.034 U	0.047 J	< 0.026 U	< 0.039 U	< 0.051 U	< 0.063 U	0.12 J	< 0.044 U	< 0.025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated										
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated										

DRAFT

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
									ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												
Restricted - Residential												
Protection of Groundwater												
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status				
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	855.30	16 - 18 ft	1801217051	Not Excavated	< 0.035 U	< 0.25 U	< 0.15 U	< 0.38 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519451	Not Excavated				
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	16 - 18 ft	1801519452	Not Excavated	< 0.18 UHT	< 0.15 UHT	< 0.12 UHT	< 0.10 UHT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	16 - 18 ft	1801518942	Not Excavated				
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	16 - 18 ft	1801164042	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	16 - 18 ft	1801163651	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	16 - 18 ft	1801163651	Not Excavated	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	16 - 18 ft	1801162471	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	16 - 18 ft	180-125431-1	Not Excavated				
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	16 - 18 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	16 - 18 ft	180-125431-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	16 - 18 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3855	041321 09:30_DUP-03	DUP-03	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	16 - 18 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	16 - 18 ft	180-119938-1	Not Excavated				
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	16 - 18 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	16 - 18 ft	180-119815-1	Not Excavated	< 0.037 U	< 0.25 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	16 - 18 ft	180-119767-1	Not Excavated	< 0.039 U	< 0.27 UJ	< 0.16 UJ	< 0.42 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	16 - 18 ft	1801194601	Not Excavated	< 0.038 UT	< 0.27 UT	< 0.16 U	< 0.42 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	16 - 18 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	16 - 18 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 UJ
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	16 - 18 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	16 - 18 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	16 - 18 ft	1801194601	Not Excavated	< 0.041 UT	< 0.28 UT	< 0.17 U	< 0.44 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	16 - 18 ft	180-119462-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	16 - 18 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.25 UJ	< 0.15 UJ	< 0.39 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	16 - 18 ft	180-120257-1	Not Excavated				
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	16 - 18 ft	180-120245-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	16 - 18 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	16 - 18 ft	1801217472	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	16 - 18 ft	1801218221	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	16 - 18 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	16 - 18 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	16 - 18 ft	1801214241	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	16 - 18 ft	1801217051	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	16 - 18 ft	1801213101	Not Excavated	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	16 - 18 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	16 - 18 ft	1801217472	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	16 - 18 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated				
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	16 - 18 ft	180-121899-1	Not Excavated				
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	16 - 18 ft	180-123901-2	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	16 - 18 ft	180-123901-2	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	16 - 18 ft	180-127265-2	Not Excavated				
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	16 - 18 ft	180-127265-2	Not Excavated				
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	16 - 18 ft	180-127415-1	Not Excavated				
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	16 - 18 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	16 - 18 ft	180-127595-2	Not Excavated	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	16 - 18 ft	180-127066-2	Not Excavated	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	16 - 18 ft	1801508422	Not Excavated	< 0.050 U	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	16 - 18 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	16 - 18 ft	180-58309-2	Not Excavated				
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	16 - 18 ft	180-120245-1	Not Excavated				

DRAFT

									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100							
Restricted - Residential									13000	13000	13000							
Protection of Groundwater									100	100	100							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	0.47 B	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated			< 110 U							
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated			< 120 U							
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated			< 110 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated			< 120 U							
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated			< 110 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.023 U	< 0.069 U	< 0.036 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated			< 550 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.066 U	< 0.035 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated			< 110 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated			< 110 U	< 0.37 UJ	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated			< 110 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated			< 110 U	< 0.38 U	< 0.025 U	< 0.028 U	< 0.04 U	< 0.022 U	< 0.068 U	< 0.036 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated			< 110 U							
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated			< 110 U							
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated				< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 130 U			< 0.42 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	0.041 J	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4011	052021 09:30_SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated			< 110 U							
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated			< 130 U							
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated			< 120 U	< 0.38 U	< 0.025 U	< 0.028 U	0.066 J	< 0.022 U	< 0.068 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated			< 110 U							
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated			< 110 U							
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated			< 110 U							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated			< 120 U	< 0.051 U	< 0.04 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508422	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U	< 0.055 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated		< 36 U								
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated			< 110 U							
Rear Parking Lot	PDI6-B5106	DUP-43-20230118	DUP-43	1/18/2023	853.77	20 - 22 ft	1801508221	Not Excavated	< 110 U									
Rear Parking Lot	PDI6-B5106	DUP-43-20230118	DUP-43	1/18/2023	853.77	20 - 22 ft	1801508222	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 UJ	0.076 J	< 0.049 U	< 0.031 U	< 0.050 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated			< 110 U							
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated			< 120 U							
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	0.071 J	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated			< 100 U							

DRAFT

									Emerging Contaminants									
									Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted														0.88	0.66			
Restricted - Residential														44	33			
Protection of Groundwater														3.7	1.1			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.030 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.053 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated										
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.089 U	< 0.079 U	< 0.056 U	< 0.053 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.081 U	< 0.2 U	< 0.085 U	< 0.076 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 UT
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 34 U	< 0.2 U	< 0.086 U	< 0.077 U	< 0.054 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.053 UT
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.029 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated										
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.032 U	< 0.034 U	0.055 J	< 0.039 U	< 0.089 U	< 0.22 U	0.096 J	< 0.084 U	< 0.059 U	< 0.056 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.031 U	< 0.034 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4011	052021 09:30_SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated										
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated										
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.037 U	< 34 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 34 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated										
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated										
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.04 U	< 0.031 U	0.039 J	< 0.023 U	< 34 U	< 0.046 U	< 0.056 U	0.057 J	< 0.039 U	< 34 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508422	Not Excavated	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U	< 0.041 U	< 0.023 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated										
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated										
Rear Parking Lot	PDI6-B5106	DUP-43-20230118	DUP-43	1/18/2023	853.77	20 - 22 ft	1801508221	Not Excavated										
Rear Parking Lot	PDI6-B5106	DUP-43-20230118	DUP-43	1/18/2023	853.77	20 - 22 ft	1801508222	Not Excavated	< 0.039 U	< 0.030 U	< 0.032 U	0.034 J	< 0.034 U	0.24	0.074 J	0.044 J	< 0.038 U	< 0.022 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated										
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated										

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
									ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												
Restricted - Residential												
Protection of Groundwater												
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status				
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	18 - 20 ft	1801163651	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	18 - 20 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	18 - 20 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	18 - 20 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	18 - 20 ft	180-119841-1	Not Excavated				
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	18 - 20 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	18 - 20 ft	180-119938-1	Not Excavated	< 0.038 U	< 0.27 UJ	< 0.16 UJ	< 0.42 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	18 - 20 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	18 - 20 ft	180-119815-1	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	18 - 20 ft	180-119767-1	Not Excavated	< 0.036 U	< 0.25 UJ	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	18 - 20 ft	1801194601	Not Excavated	< 0.040 UT	< 0.28 UT	< 0.17 U	< 0.43 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	18 - 20 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 UJ
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	18 - 20 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 UJ
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	18 - 20 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	18 - 20 ft	1801194601	Not Excavated	< 0.038 UT	< 0.26 UT	< 0.16 U	< 0.41 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	18 - 20 ft	180-119462-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	18 - 20 ft	180-119861-1	Not Excavated	< 0.037 U	< 0.25 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	18 - 20 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	18 - 20 ft	180-120257-1	Not Excavated				
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	18 - 20 ft	180-120245-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	18 - 20 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	18 - 20 ft	1801217472	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	18 - 20 ft	1801218221	Not Excavated	< 0.037 U	< 0.26 U	< 0.16 U	< 0.40 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	18 - 20 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	18 - 20 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	18 - 20 ft	1801214241	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	18 - 20 ft	1801217051	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	18 - 20 ft	1801213101	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	18 - 20 ft	1801215481	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	18 - 20 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	18 - 20 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	18 - 20 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4011	052021 09:30_SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	18 - 20 ft	180-121899-1	Not Excavated				
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	18 - 20 ft	180-122085-1	Not Excavated				
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	18 - 20 ft	180-123901-2	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	18 - 20 ft	180-123901-2	Not Excavated	< 0.037 U	< 0.25 U	< 0.15 U	< 0.4 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	18 - 20 ft	180-127265-2	Not Excavated				
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	18 - 20 ft	180-127265-2	Not Excavated				
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	18 - 20 ft	180-127415-1	Not Excavated				
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	18 - 20 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	18 - 20 ft	180-127595-2	Not Excavated				
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	18 - 20 ft	180-127066-2	Not Excavated	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	18 - 20 ft	1801508422	Not Excavated	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	18 - 20 ft	1801508421	Not Excavated				
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	18 - 20 ft	180-120245-1	Not Excavated				
Rear Parking Lot	PDI6-B5106	DUP-43-20230118	DUP-43	1/18/2023	853.77	20 - 22 ft	1801508221	Not Excavated				
Rear Parking Lot	PDI6-B5106	DUP-43-20230118	DUP-43	1/18/2023	853.77	20 - 22 ft	1801508222	Not Excavated	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	20 - 22 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	20 - 22 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	20 - 22 ft	180-119841-1	Not Excavated				
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	20 - 22 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	20 - 22 ft	180-119938-1	Not Excavated	< 0.036 U	< 0.25 UJ	< 0.15 UJ	< 0.39 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	20 - 22 ft	180-119815-1	Not Excavated				

									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100							
Restricted - Residential									13000	13000	13000							
Protection of Groundwater									100	100	100							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.027 U	< 0.037 U	< 0.021 U	< 0.064 U	< 0.034 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated			< 560 U	< 0.35 U	< 0.024 U	< 0.026 U	< 0.037 U	< 0.021 U	< 0.063 U	< 0.033 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.04 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated			< 110 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated			< 110 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.023 U	< 0.069 U	< 0.036 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated			< 120 U							
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated				< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 110 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 120 U			< 0.42 U	< 0.029 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.035 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated			< 130 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated			< 120 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508422	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U	< 0.054 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated		< 31 U								
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated			< 110 UJ							
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated			< 130 U							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated			< 120 U	< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.07 U	< 0.037 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated			< 110 U							
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.026 U	< 0.037 U	< 0.021 U	< 0.063 U	< 0.033 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated			< 110 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 110 U			< 0.38 U	< 0.025 U	< 0.028 U	< 0.040 U	< 0.022 U	< 0.068 U	< 0.036 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated			< 120 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated			< 120 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated				< 0.43 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.040 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 130 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.031 J	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U

DRAFT

									Emerging Contaminants									
									Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted														0.88	0.66			
Restricted - Residential														44	33			
Protection of Groundwater														3.7	1.1			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.028 U	< 0.03 U	< 0.04 U	< 0.035 U	< 0.079 U	< 0.19 U	< 0.083 U	< 0.074 U	< 0.052 U	< 0.049 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.027 U	< 0.029 U	< 0.04 U	< 0.034 U	< 0.077 U	< 0.19 U	< 0.081 U	< 0.073 U	< 0.051 U	< 0.048 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 UT
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.036 U	< 34 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 UT
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.088 U	< 0.079 U	< 0.056 U	< 0.052 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated	< 0.030 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.090 U	< 0.22 U	< 0.094 U	< 0.084 U	< 0.059 U	< 0.056 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.032 U	< 0.034 UT	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 0.056 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.06 U	< 34 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508422	Not Excavated	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U	< 0.041 U	< 0.023 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated										
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.09 U	< 0.081 U	< 0.057 U	< 0.053 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.027 U	< 0.029 U	< 0.04 U	< 0.034 U	< 0.077 U	< 0.19 U	< 0.081 U	< 0.073 U	< 0.051 U	< 0.048 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.037 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 UT
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 UT
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.04 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.06 U	< 0.057 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated	< 0.033 U	< 0.036 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.099 U	< 0.088 U	< 0.062 U	< 0.059 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U	< 0.059 U	< 0.055 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.031 U	< 0.034 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 U

DRAFT

									Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
									ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												
Restricted - Residential												
Protection of Groundwater												
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	20 - 22 ft	180-119815-1	Not Excavated	< 0.035 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	20 - 22 ft	180-119767-1	Not Excavated	< 0.034 U	< 0.24 UJ	< 0.14 U	< 0.37 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	20 - 22 ft	1801194601	Not Excavated	< 0.039 UT	< 0.27 UT	< 0.16 UT	< 0.42 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	20 - 22 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	20 - 22 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	20 - 22 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	20 - 22 ft	1801194601	Not Excavated	< 0.038 UT	< 0.26 UT	< 0.16 U	< 0.41 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	20 - 22 ft	180-119462-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	20 - 22 ft	180-119861-1	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	20 - 22 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	20 - 22 ft	180-120245-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	20 - 22 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	20 - 22 ft	1801217472	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	20 - 22 ft	1801219031	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	20 - 22 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	20 - 22 ft	1801217041	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	20 - 22 ft	1801214241	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	20 - 22 ft	1801217051	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	20 - 22 ft	1801213101	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	20 - 22 ft	1801215481	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	20 - 22 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	20 - 22 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	20 - 22 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	20 - 22 ft	180-122085-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	20 - 22 ft	180-123901-2	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	20 - 22 ft	1801508422	Not Excavated	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	20 - 22 ft	1801508421	Not Excavated				
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	20 - 22 ft	180-120245-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	22 - 23 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	22 - 24 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	22 - 24 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	22 - 24 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	22 - 24 ft	180-119938-1	Not Excavated	< 0.038 U	< 0.26 UJ	< 0.16 UJ	< 0.41 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	22 - 24 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	22 - 24 ft	180-119815-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	22 - 24 ft	180-119767-1	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	22 - 24 ft	1801194601	Not Excavated	< 0.037 UT	< 0.25 UT	< 0.15 U	< 0.40 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	22 - 24 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	22 - 24 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	22 - 24 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	22 - 24 ft	1801194601	Not Excavated	< 0.038 UT	< 0.26 UT	< 0.16 U	< 0.41 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	22 - 24 ft	180-119861-1	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.44 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	22 - 24 ft	180-119510-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	22 - 24 ft	1801217472	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	22 - 24 ft	1801219031	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	22 - 24 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	22 - 24 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	22 - 24 ft	1801214241	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	22 - 24 ft	1801217051	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	22 - 24 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	22 - 24 ft	1801215481	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	22 - 24 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U

									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100							
Restricted - Residential									13000	13000	13000							
Protection of Groundwater									100	100	100							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated			< 110 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated		< 32 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508422	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U	< 0.054 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated	< 130 U									
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated			< 110 UJ							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated			< 120 U	< 0.39 U	< 0.027 U	0.032 J	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated			< 110 U	< 0.36 U	< 0.024 U	< 0.027 U	< 0.038 U	< 0.021 U	< 0.065 U	< 0.034 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated			< 110 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated			< 34 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	855.35	16 - 18 ft	1801194601	Not Excavated	< 130 U			< 0.47 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	855.07	34 - 36 ft	1801194601	Not Excavated	< 140 U			< 0.49 U	< 0.033 U	< 0.037 U	< 0.052 U	< 0.029 U	< 0.089 U	< 0.047 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 130 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated			< 130 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated				< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 120 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 110 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.040 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated			< 110 U							
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated			< 110 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated			< 110 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508422	Not Excavated				< 0.055 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.055 U	< 0.034 U	< 0.056 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.33	16 - 18 ft	1801194601	Not Excavated	< 130 U			< 0.45 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.027 U	< 0.081 U	< 0.043 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated			< 110 UJ							
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated			< 120 U	< 0.42 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.04 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated			< 120 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.026 U	< 0.037 U	< 0.021 U	< 0.063 U	< 0.033 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 130 U			< 0.45 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.082 U	< 0.043 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated			< 34 U	< 0.35 U	< 0.024 U	< 0.027 U	< 0.037 U	< 0.021 U	< 0.064 U	< 0.033 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated			< 130 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 140 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U

									Emerging Contaminants									
									Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted														0.88	0.66			
Restricted - Residential														44	33			
Protection of Groundwater														3.7	1.1			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.06 U	< 34 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508422	Not Excavated	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U	< 0.040 U	< 0.023 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 UT
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.028 U	< 0.03 U	< 0.041 U	< 0.035 U	< 0.079 U	< 0.19 U	< 0.083 U	< 0.075 U	< 0.052 U	< 0.049 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.091 U	< 0.064 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 34 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.054 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	855.35	16 - 18 ft	1801194601	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.097 U	< 0.068 U	< 0.064 UT
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	855.07	34 - 36 ft	1801194601	Not Excavated	< 0.039 U	< 0.041 U	< 0.056 U	< 0.048 U	< 0.11 U	< 0.27 U	< 0.11 U	< 0.10 U	< 0.072 U	< 0.068 UT
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.068 U	< 0.064 UT
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.1 U	< 0.089 U	< 0.063 U	< 0.059 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.033 U	< 0.036 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.099 U	< 0.089 U	< 0.062 U	< 0.059 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated										
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated										
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 34 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508422	Not Excavated	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.060 U	< 0.047 U	< 0.042 U	< 0.024 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.33	16 - 18 ft	1801194601	Not Excavated	< 0.035 U	< 0.038 U	< 0.051 U	< 0.044 U	< 0.10 U	< 0.24 U	< 0.10 U	< 0.094 U	< 0.066 U	< 0.062 UT
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.035 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.064 U	< 0.061 UT
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.035 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.064 U	< 0.061 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U	< 0.059 U	< 0.055 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.027 U	< 0.029 U	< 0.04 U	< 0.034 U	< 0.077 U	< 0.19 U	< 0.081 U	< 0.073 U	< 0.051 U	< 0.048 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.044 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.066 U	< 0.063 UT
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 34 U	< 0.23 U	< 0.1 U	< 0.089 U	< 0.063 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.028 U	< 0.029 U	< 0.04 U	< 0.034 U	< 34 U	< 0.19 U	< 0.082 U	< 0.073 U	< 0.051 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.068 U	< 0.064 UT
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.1 U	< 0.089 U	< 0.063 U	< 0.059 U

DRAFT

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
									ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												
Restricted - Residential												
Protection of Groundwater												
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	22 - 24 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	22 - 24 ft	180-121981-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	22 - 24 ft	180-123901-2	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	22 - 24 ft	1801508422	Not Excavated	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	22 - 24 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	23 - 25 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	24 - 24.5 ft	1801194601	Not Excavated	< 0.039 UT	< 0.27 UT	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	24 - 25 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	24 - 25 ft	1801214241	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	24 - 26 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	24 - 26 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	24 - 26 ft	180-119938-1	Not Excavated	< 0.038 U	< 0.27 UJ	< 0.16 UJ	< 0.42 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	24 - 26 ft	180-119815-1	Not Excavated	< 0.035 U	< 0.24 U	< 0.15 U	< 0.38 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	24 - 26 ft	180-119767-1	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	24 - 26 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	24 - 26 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	24 - 26 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	24 - 26 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	855.35	16 - 18 ft	1801194601	Not Excavated	< 0.045 UT	< 0.31 UT	< 0.19 U	< 0.49 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	855.07	34 - 36 ft	1801194601	Not Excavated	< 0.048 UT	< 0.33 UT	< 0.20 U	< 0.52 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	24 - 26 ft	1801194601	Not Excavated	< 0.045 UT	< 0.31 UT	< 0.19 U	< 0.49 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	24 - 26 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	24 - 26 ft	180-119510-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	24 - 26 ft	1801217472	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	24 - 26 ft	1801219031	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	24 - 26 ft	1801217041	Not Excavated	< 0.037 U	< 0.26 U	< 0.16 U	< 0.40 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	24 - 26 ft	1801217051	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	24 - 26 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	24 - 26 ft	1801215481	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	24 - 26 ft	1801213101	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	24 - 26 ft	180-123985-1	Not Excavated				
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	24 - 26 ft	180-121981-1	Not Excavated				
South of Athletic Stands	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	24 - 26 ft	180-123901-2	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	24 - 26 ft	180-123901-2	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	24 - 26 ft	1801508422	Not Excavated	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	24 - 26 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.33	16 - 18 ft	1801194601	Not Excavated	< 0.044 UT	< 0.30 UT	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	24.5 - 26 ft	1801194601	Not Excavated	< 0.043 UT	< 0.30 UT	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	25 - 27 ft	1801214241	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	26 - 28 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	26 - 28 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	26 - 28 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	26 - 28 ft	180-119938-1	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	26 - 28 ft	180-119815-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	26 - 28 ft	180-119767-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	26 - 28 ft	1801194601	Not Excavated	< 0.044 UT	< 0.31 UT	< 0.18 U	< 0.48 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	26 - 28 ft	180-120245-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	26 - 28 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	26 - 28 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	26 - 28 ft	1801194602	Not Excavated	< 0.045 UT	< 0.31 UT	< 0.19 U	< 0.49 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	26 - 28 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U

									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100							
Restricted - Residential									13000	13000	13000							
Protection of Groundwater									100	100	100							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 130 U			< 0.45 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.081 U	< 0.042 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated			< 130 U							
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated			< 120 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated		< 36 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508422	Not Excavated				< 0.059 U	< 0.046 U	< 0.056 U	< 0.063 U	< 0.059 U	< 0.037 U	< 0.060 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated		< 33 U								
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated			< 120 U	< 0.39 U	< 0.026 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 140 U			< 0.50 U	< 0.034 U	< 0.038 U	< 0.052 U	< 0.029 U	< 0.090 U	< 0.047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated			< 120 UJ							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated			< 130 U							
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated			< 34 U	< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated			< 130 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 130 U			< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 150 U			< 0.48 U	< 0.032 U	< 0.036 U	< 0.050 U	< 0.028 U	< 0.086 U	< 0.045 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	855.33	18 - 20 ft	1801213101	Not Excavated	< 130 U			< 0.42 U	< 0.029 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated			< 120 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated		< 33 U								
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated			< 120 UJ							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated			< 120 U	< 0.45 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.027 U	< 0.082 U	< 0.043 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated			< 130 U	< 0.47 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated			< 120 U	< 0.42 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.04 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated			< 140 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 130 U			< 0.47 U	< 0.032 U	< 0.036 U	< 0.050 U	< 0.028 U	< 0.085 U	< 0.045 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 130 U			< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated			< 130 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated			< 120 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated		< 37 U								
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated			< 110 UJ							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated			< 120 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.027 U	< 0.084 U	< 0.044 U

DRAFT

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Emerging Contaminants									
									Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted														0.88	0.66			
Restricted - Residential														44	33			
Protection of Groundwater														3.7	1.1			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated										
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.059 U	< 0.055 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.035 U	< 0.037 U	< 0.051 U	< 0.043 U	< 0.099 U	< 0.24 U	< 0.10 U	< 0.093 U	< 0.065 U	< 0.061 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.034 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.097 U	< 0.24 U	< 0.10 U	< 0.091 U	< 0.064 U	< 0.061 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated										
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 34 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508422	Not Excavated	< 0.046 U	< 0.035 U	< 0.038 U	< 0.027 U	< 0.040 U	< 0.052 U	< 0.065 U	< 0.050 U	< 0.045 U	< 0.026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated										
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.039 U	< 0.042 U	< 0.056 U	< 0.048 U	< 0.11 U	< 0.27 U	< 0.12 U	< 0.10 U	< 0.072 U	< 0.068 UT
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 0.06 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 0.061 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 0.061 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.094 U	< 0.085 U	< 0.059 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 0.06 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated										
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.10 U	< 0.089 U	< 0.063 U	< 0.059 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.088 U	< 0.079 U	< 0.055 U	< 0.052 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.037 U	< 0.040 U	< 0.054 U	< 0.046 U	< 0.11 U	< 0.26 U	< 0.11 U	< 0.099 U	< 0.069 U	< 0.066 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	855.33	18 - 20 ft	1801213101	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.093 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.035 U	< 0.038 U	< 0.051 U	< 0.044 U	< 0.1 U	< 0.24 U	< 0.1 U	< 0.094 U	< 0.066 U	< 0.062 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 0.061 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.037 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.097 U	< 0.068 U	< 0.064 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 34 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.045 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.037 U	< 0.040 U	< 0.054 U	< 0.046 U	< 0.10 U	< 0.26 U	< 0.11 U	< 0.098 U	< 0.069 U	< 0.065 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.10 U	< 0.089 U	< 0.063 U	< 0.059 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 34 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.035 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.065 U	< 0.061 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.04 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.06 U	< 0.057 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.036 U	< 0.039 U	< 0.052 U	< 0.045 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.067 U	< 0.064 U

DRAFT

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
									ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												
Restricted - Residential												
Protection of Groundwater												
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	26 - 28 ft	180-119510-1	Not Excavated				
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	26 - 28 ft	1801219031	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	26 - 28 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	26 - 28 ft	1801217051	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	26 - 28 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	26 - 28 ft	1801215481	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	26 - 28 ft	1801213101	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	26 - 28 ft	180-123985-1	Not Excavated				
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	26 - 28 ft	180-121981-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	26 - 28 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	26 - 28 ft	1801508422	Not Excavated	< 0.051 U	< 0.043 U	< 0.033 U	< 0.028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	26 - 28 ft	1801508421	Not Excavated				
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	28 - 28.5 ft	1801194602	Not Excavated	< 0.048 UT	< 0.34 UT	< 0.20 U	< 0.52 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	28 - 30 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	28 - 30 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	28 - 30 ft	180-119938-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	28 - 30 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	28 - 30 ft	180-119815-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	28 - 30 ft	180-119767-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	28 - 30 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	28 - 30 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	28 - 30 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	28 - 30 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	28 - 30 ft	180-119510-1	Not Excavated				
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	28 - 30 ft	1801219031	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	28 - 30 ft	1801217041	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	28 - 30 ft	1801217051	Not Excavated	< 0.046 U	< 0.32 U	< 0.19 U	< 0.50 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	855.33	18 - 20 ft	1801213101	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	28 - 30 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	28 - 30 ft	180-123985-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	28 - 30 ft	180-123901-2	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	28 - 30 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	30 - 32 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	30 - 32 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	30 - 32 ft	180-119938-1	Not Excavated	< 0.044 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	30 - 32 ft	180-119815-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	30 - 32 ft	180-119767-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	30 - 32 ft	180-120245-1	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	30 - 32 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	30 - 32 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	30 - 32 ft	180-119861-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	30 - 32 ft	180-119510-1	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	30 - 32 ft	1801217041	Not Excavated	< 0.046 U	< 0.32 U	< 0.19 U	< 0.50 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	30 - 32 ft	1801213101	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	30 - 32 ft	180-123985-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	30 - 32 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	30 - 32 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	31 - 33 ft	1801219031	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	32 - 34 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	32 - 34 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	32 - 34 ft	180-119938-1	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.43 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	32 - 34 ft	180-119815-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U

DRAFT

									1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted									100	100	100							
Restricted - Residential									13000	13000	13000							
Protection of Groundwater									100	100	100							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated			< 130 U	< 0.42 U	< 0.028 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated			< 130 U	< 0.45 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.081 U	< 0.042 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.07	32 - 34 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated			< 34 U	< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated			< 120 U							
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.33	18 - 20 ft	180-119861-1	Not Excavated			< 130 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.078 U	< 0.04 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated			< 120 UJ							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.027 U	< 0.037 U	< 0.021 U	< 0.064 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.027 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated			< 34 U	< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated			< 130 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated			< 110 U	< 0.39 U	< 0.026 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated			< 130 U							
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated			< 34 U	< 0.42 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated			< 120 UJ							
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated			< 130 U	< 0.44 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated			< 140 U	< 0.45 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.082 U	< 0.043 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated			< 130 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated			< 34 U	< 0.44 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated			< 120 UJ							
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated			< 140 U	< 0.5 U	< 0.034 U	< 0.038 U	< 0.052 U	< 0.029 U	< 0.09 U	< 0.047 U
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated			< 130 U	< 0.48 U	< 0.032 U	< 0.036 U	< 0.051 U	< 0.029 U	< 0.087 U	< 0.045 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated			< 34 U	< 0.5 U	< 0.034 U	< 0.038 U	< 0.052 U	< 0.03 U	< 0.09 U	< 0.047 U
Football Field	SSHS-B4164	092421 10:00_DUP-20	DUP-20	9/23/2021	856.13	28 - 30 ft	180-127595-2	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated			< 150 UJ							
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated			< 130 U							
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated			< 140 U	< 0.45 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.082 U	< 0.043 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated			< 34 U	< 0.52 U	< 0.035 U	< 0.039 U	< 0.055 U	< 0.031 U	< 0.094 U	< 0.049 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated			< 120 UJ							
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated			< 34 U							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated			< 130 UJ							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated			< 110 UJ							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated			< 130 UJ							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated			< 130 U							
Football Field	SSHS-B4164	092421 10:00_DUP-21	DUP-21	9/23/2021	855.30	16 - 18 ft	180-127595-2	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3917	DUP-39-20210512	DUP-39	5/12/2021	855.85	18 - 20 ft	1801215482	Excavated	< 120 U			< 0.44 U	< 0.030 U	0.20 J	< 0.046 U	0.044 J	< 0.080 U	< 0.042 U

DRAFT

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Emerging Contaminants									
									Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)
									ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted														0.88	0.66			
Restricted - Residential														44	33			
Protection of Groundwater														3.7	1.1			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.041 U	< 0.092 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.057 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.051 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.093 U	< 0.065 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.07	32 - 34 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 34 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.33	18 - 20 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 0.06 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.082 U	< 0.2 U	< 0.086 U	< 0.077 U	< 0.054 U	< 0.051 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 34 U	< 0.23 U	< 0.099 U	< 0.089 U	< 0.062 U	< 34 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated										
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.097 U	< 0.24 U	< 0.1 U	< 0.091 U	< 0.064 U	< 0.06 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.028 U	< 0.03 U	< 0.04 U	< 0.035 U	< 0.079 U	< 0.19 U	< 0.083 U	< 0.074 U	< 0.052 U	< 0.049 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.039 U	< 0.052 U	< 0.045 U	< 34 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.067 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 34 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.044 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.066 U	< 0.063 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.034 U	< 0.044 U	< 0.038 U	< 34 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 34 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.04 U	< 34 U	< 0.22 U	< 0.097 U	< 0.087 U	< 0.061 U	< 34 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.097 U	< 0.24 U	< 0.1 U	< 0.091 U	< 0.064 U	< 0.06 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 34 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.068 U	< 34 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.044 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.066 U	< 0.063 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	< 0.039 U	< 0.042 U	< 0.056 U	< 0.048 U	< 0.11 U	< 0.27 U	< 0.12 U	< 0.1 U	< 0.072 U	< 0.068 U
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.04 U	< 0.054 U	< 0.047 U	< 0.11 U	< 0.26 U	< 0.11 U	< 0.1 U	< 0.07 U	< 0.066 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.042 U	< 0.056 U	< 0.048 U	< 34 U	< 0.27 U	< 0.12 U	< 0.1 U	< 0.073 U	< 34 U
Football Field	SSHS-B4164	092421 10:00_DUP-20	DUP-20	9/23/2021	856.13	28 - 30 ft	180-127595-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated										
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.036 U	< 0.038 U	< 0.051 U	< 0.044 U	< 34 U	< 0.25 U	< 0.11 U	< 0.094 U	< 0.066 U	< 34 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.041 U	< 0.043 U	< 0.059 U	< 0.05 U	< 34 U	< 0.28 U	< 0.12 U	< 0.11 U	< 0.076 U	< 34 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated										
Football Field	SSHS-B4164	092421 10:00_DUP-21	DUP-21	9/23/2021	855.30	16 - 18 ft	180-127595-2	Not Excavated										
Northern Athletic Field	SSHS-B3917	DUP-39-20210512	DUP-39	5/12/2021	855.85	18 - 20 ft	1801215482	Excavated	0.048 J	< 0.037 U	0.050 J	0.054 J	< 0.098 U	0.69	0.20 J	< 0.092 U	< 0.064 U	< 0.061 U

DRAFT

TABLE 5-7E
Deep Soil Results - Remedial Investigation - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

									Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
									ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												
Restricted - Residential												
Protection of Groundwater												
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Sample depth at time of sampling[2] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	32 - 34 ft	180-119767-2	Not Excavated	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	32 - 34 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.07	32 - 34 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	32 - 34 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	32 - 34 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.33	18 - 20 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	32 - 34 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	32 - 34 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	32 - 34 ft	180-121981-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	32 - 34 ft	180-123901-2	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	33 - 35 ft	180-121981-1	Not Excavated				
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	34 - 36 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	34 - 36 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	34 - 36 ft	180-119938-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	34 - 36 ft	180-119815-2	Not Excavated	< 0.035 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	34 - 36 ft	180-120245-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	34 - 36 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	34 - 36 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	34 - 36 ft	180-119861-1	Not Excavated	< 0.044 U	< 0.31 U	< 0.18 U	< 0.48 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	34 - 36 ft	180-119510-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	34 - 36 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	35 - 37 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	36 - 37 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	36 - 38 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	36 - 38 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	36 - 38 ft	180-119938-2	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	36 - 38 ft	180-120245-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	36 - 38 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	36 - 38 ft	180-119861-1	Not Excavated	< 0.044 U	< 0.31 U	< 0.18 U	< 0.48 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	36 - 38 ft	180-119510-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	36 - 38 ft	180-123901-2	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	37 - 39 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	38 - 40 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	38 - 40 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	38 - 40 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	38 - 40 ft	180-119861-2	Not Excavated	< 0.048 U	< 0.34 U	< 0.2 U	< 0.52 U
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	38 - 40 ft	180-123901-2	Not Excavated	< 0.047 U	< 0.32 U	< 0.19 U	< 0.51 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	39 - 41 ft	180-120245-1	Not Excavated	< 0.048 U	< 0.34 U	< 0.2 U	< 0.52 U
Football Field	SSHS-B4164	092421 10:00_DUP-20	DUP-20	9/23/2021	856.13	28 - 30 ft	180-127595-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	40 - 42 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	40 - 42 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	40 - 42 ft	180-119510-1	Not Excavated				
South of Athletic Stands	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	40 - 42 ft	180-123901-2	Not Excavated	< 0.044 U	< 0.31 U	< 0.18 U	< 0.48 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	41 - 43 ft	180-120245-1	Not Excavated	< 0.05 U	< 0.35 U	< 0.21 U	< 0.55 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	42 - 44 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	42 - 44 ft	180-120434-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	44 - 46 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	46 - 48 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	48 - 50 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	50 - 52 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	52 - 54 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	54 - 56 ft	180-127205-2	Not Excavated				
Football Field	SSHS-B4164	092421 10:00_DUP-21	DUP-21	9/23/2021	855.30	16 - 18 ft	180-127595-2	Not Excavated				
Northern Athletic Field	SSHS-B3917	DUP-39-20210512	DUP-39	5/12/2021	855.85	18 - 20 ft	1801215482	Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.46 U

DRAFT

TABLE 5-8
Groundwater Results - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Groundwater Results - PCBs					PCBs									
					Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.09									
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-1	MW-1	D	7/14/2021	180-124487-1	ND	< 0.0053	< 0.0064	< 0.0059	< 0.004	< 0.0034	< 0.0051	< 0.0044	< 0.008	< 0.0051
MW-1	MW-1	T	2/17/2021	180-117387-1	0.225	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.15 B	0.058	0.017	< 0.007 U	< 0.0045 U
MW-1	MW-1	T	7/14/2021	180-124487-1	0.027	< 0.0053	< 0.0064	< 0.0059	< 0.004	0.027	< 0.0051	< 0.0044	< 0.008	< 0.0051
MW-10	MW-10	D	7/13/2021	180-124378-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-10	MW-10	T	8/21/2014	180-36053-1	ND	< 0.0025 U	< 0.0025 U	< 0.0029 U	< 0.0019 U	< 0.0023 U	< 0.0023 U	< 0.0014 U	< 0.0021 U	< 0.0027 U
MW-10	MW-10	T	2/24/2021	180-117542-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-10	MW-10	T	7/13/2021	180-124378-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-100I	SSHS-MW-100I-04082024	T	4/8/2024	1801720411	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-100I	SSHS-MW-100I-09142023	T	9/14/2023	1801625611	ND	< 0.048 U	< 0.057 U	< 0.052 U	< 0.036 U	< 0.080 U	< 0.046 U	< 0.039 U	< 0.071 U	< 0.046 U
MW-100S	SSHS-DUP-02-09142023	T	9/14/2023	1801625611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-100S	SSHS-MW-100S-04082024	T	4/8/2024	1801720411	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-100S	SSHS-MW-100S-09142023	T	9/14/2023	1801625611	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0081 U	< 0.0046 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-101I	SSHS-MW-101I-04102024	T	4/10/2024	1801721871	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-101I	SSHS-MW-101I-09132023	T	9/13/2023	1801624611	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-101S	SSHS-MW-101S-04102024	T	4/10/2024	1801721871	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-101S	SSHS-MW-101S-09132023	T	9/13/2023	1801624611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-102I	SSHS-MW-102I-04222024	T	4/22/2024	1801730541	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-102I	SSHS-MW-102I-09142023	T	9/14/2023	1801625611	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-102S	SSHS-MW-102S-04222024	T	4/22/2024	1801730541	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-102S	SSHS-MW-102S-09142023	T	9/14/2023	1801625611	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-103I	SSHS-MW-103I-04162024	T	4/16/2024	1801726651	7.99	< 0.047 U	< 0.057 U	< 0.052 U	< 0.035 U	5.9	1.7	0.39	< 0.070 U	< 0.045 U
MW-103I	SSHS-MW-103I-09122023	T	9/12/2023	1801624611	6	< 0.046 U	< 0.056 U	< 0.051 U	6.0	< 0.078 U	< 0.044 U	< 0.038 U	< 0.069 U	< 0.044 U
MW-103S	SSHS-MW-103S-04162024	T	4/16/2024	1801726651	1.6	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	1.6	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-103S	SSHS-MW-103S-09122023	T	9/12/2023	1801624611	2	< 0.0047 U	< 0.0056 U	< 0.0051 U	2.0	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-104I	SSHS-DUP-03-09122023	T	9/12/2023	1801624611	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-104I	SSHS-MW-104I-04162024	T	4/16/2024	1801726651	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-104I	SSHS-MW-104I-09122023	T	9/12/2023	1801624611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-104S	SSHS-MW-104S-04162024	T	4/16/2024	1801726651	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-104S	SSHS-MW-104S-09122023	T	9/12/2023	1801624611	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-105I	SSHS-MW-105I-04172024	T	4/17/2024	1801726651	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-105I	SSHS-MW-105I-09152023	T	9/15/2023	1801625611	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-105S	SSHS-MW-105S-04252024	T	4/25/2024	1801731401	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-105S	SSHS-MW-105S-09122023	T	9/12/2023	1801624611	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-106	SSHS-MW-106-01182024	T	1/18/2024	1801682891	0.044	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	0.044	< 0.0046 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-106	SSHS-MW-106-04102024	T	4/10/2024	1801721851	0.35	< 0.0052 U	< 0.0063 U	< 0.0057 U	< 0.0039 U	0.35	< 0.0050 U	< 0.0043 U	< 0.0078 U	< 0.0050 U
MW-106	SSHS-MW-106-05022023	T	5/2/2023	1801559471	0.48	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.48	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-106	SSHS-MW-106-09142023	T	9/14/2023	1801625601	0.32	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.32	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-106	SSHS-MW-106-11142023	T	11/14/2023	1801653531	0.57	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.57	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-108	SSHS-DUP-01-07112025	T	7/11/2025	1801931281	ND	< 0.19 U	< 0.23 U	< 0.21 U	< 0.14 U	< 0.32 U	< 0.18 U	< 0.16 U	< 0.28 U	< 0.18 U
MW-108	SSHS-MW-108-07112025	T	7/11/2025	1801931281	ND	< 0.18 U	< 0.22 U	< 0.20 U	< 0.14 U	< 0.31 U	< 0.18 U	< 0.15 U	< 0.27 U	< 0.18 U
MW-108	SSHS-MW-108-11132025	T	11/13/2025	1801985411	0.012	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	0.012	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-108	SSHS-DUP-01-11132025	T	11/13/2025	1801985411	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-11D	MW-11D	D	4/30/2021	180-120955-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-11D	MW-11D	T	2/23/2021	180-117459-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-11D	MW-11D	T	4/30/2021	180-120955-1	ND	< 0.0045 U,*3	< 0.0054 U,*3	< 0.0049 U,*3	< 0.0034 U,*3	< 0.0028 U,*3	< 0.0043 U,*3	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-11D	MW-11D-GW	T	11/1/2018	180-83607-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0093 U	< 0.0031 U	< 0.0097 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-11S	DUP-01	T	7/25/2019	180-93333-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0089 U	< 0.0029 U	< 0.0092 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-11S	FD-1	T	11/1/2018	180-83607-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0091 U	< 0.003 U	< 0.0095 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-11S	MW-11S	D	4/30/2021	180-120955-1	ND	< 0.0045 U,*3	< 0.0054 U,*3	< 0.005 U,*3	< 0.0034 U,*3	< 0.0028 U,*3	< 0.0043 U,*3	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-11S	MW-11S	T	7/25/2019	180-93333-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0091 U	< 0.003 U	< 0.0095 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-11S	MW-11S	T	2/23/2021	180-117459-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-11S	MW-11S	T	4/30/2021	180-120955-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-11S	MW-11S-GW	T	11/1/2018	180-83607-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0093 U	< 0.0031 U	< 0.0097 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-11S	SSHS-MW-11S	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-11S	SSHS-MW-11S_F	D	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-12	MW-12	D	7/14/2021	180-124487-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-12	MW-12	T	2/21/2021	180-117476-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-12	MW-12	T	7/14/2021	180-124487-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-13	DUP-02	T	2/21/2021	180-117476-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-13	MW-13	D	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.0049	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0067	< 0.0043
MW-13	MW-13	T	2/21/2021	180-117476-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-13	MW-13	T	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-13	SSHS-MW-13-04232024	D	4/23/2024	1801730461	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-13	SSHS-MW-13-04232024	T	4/23/2024	1801730461	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-15S	SSHS-MW-15S	D	9/27/2016	180-59149-1	0.594	< 0.0033 U	< 0.0089 U	< 0.0032 U	< 0.0091 U	0.53	0.064	< 0.0056 U	< 0.0065 U	< 0.0064 U
MW-15S	SSHS-MW-15S	T	9/27/2016	180-59149-1	0.48	< 0.0033 U	< 0.0089 U	< 0.0032 U	< 0.0091 U	0.39	0.079	0.011	< 0.0065 U	< 0.0064 U
MW-2	MW-2	D	7/14/2021	180-124487-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-2	MW-2	T	2/17/2021	180-117387-1	0.012	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.012 B	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-2	MW-2	T	7/14/2021	180-124487-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-20	MW-20	D	7/15/2021	180-124580-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-20	MW-20	T	2/23/2021	180-117459-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-20	MW-20	T	7/15/2021	180-124580-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-22	MW-22	D	7/15/2021	180-124580-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-22	MW-22	T	2/23/2021	180-117459-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-22	MW-22	T	7/15/2021	180-124580-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-26	MW-26	D	7/14/2021	180-124487-1	ND	< 0.0047	< 0.0057	< 0.0052	< 0.0035	< 0.003	< 0.0045	< 0.0039	< 0.007	< 0.0045
MW-26	MW-26	T	2/17/2021	180-117387-1	0.011	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.011 B	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-26	MW-26	T	7/14/2021	180-124487-1	ND	< 0.0047	< 0.0057	< 0.0052	< 0.0035	< 0.003	< 0.0045	< 0.0039	< 0.007	< 0.0045
MW-3	MW-3	D	7/14/2021	180-124487-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-3	MW-3	T	2/17/2021	180-117387-1	0.011	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.011 B	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-3	MW-3	T	7/14/2021	180-124487-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-3	DUP-4	D	7/14/2021	180-124487-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-3	DUP-4	T	7/14/2021	180-124487-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-30	MW-30	D	7/16/2021	180-124628-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-30	MW-30	T	7/26/2019	180-93333-1	39	< 0.24 U	< 0.29 U	< 0.26 U	< 0.46 U	39	< 0.48 U	< 0.2 U	< 0.36 U	< 0.23 U
MW-30	MW-30	T	2/19/2021	180-117476-1	1.102	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.73	0.3	0.072	< 0.007 U	< 0.0045 U
MW-30	MW-30	T	7/16/2021	180-124628-1	0.13	< 0.0068	< 0.0082	< 0.0074	< 0.0051	0.13	< 0.0065	< 0.0056	< 0.01	< 0.0065
MW-30	SSHS-MW-30-04302024	D	4/30/2024	1801733261	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-30	SSHS-MW-30-04302024	T	4/30/2024	1801733261	2.4	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	1.3	0.94	0.16	< 0.0071 U	< 0.0046 U
MW-31	GW-FD-1	T	3/22/2016	180-53281-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-31	SSHS-MW-31	T	3/22/2016	180-53281-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-31	SSHS-MW-31_F	D	3/22/2016	180-53281-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-32	MW-32	D	7/13/2021	180-124378-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-32	MW-32	T	2/22/2021	180-117425-1	0.048	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.038	0.01	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-32	MW-32	T	7/13/2021	180-124378-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-32	SSHS-MW-32	T	3/21/2016	180-53281-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-32	SSHS-MW-32_F	D	3/21/2016	180-53281-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-32	SSHS-MW-32-04042024	T	4/4/2024	1801719071	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-33	GW-FD-2	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-33	MW-33	D	7/13/2021	180-124378-1	ND	< 0.0045 U,F1	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U,F1	< 0.0067 U	< 0.0043 U
MW-33	MW-33	T	2/19/2021	180-117476-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-33	MW-33	T	7/13/2021	180-124378-1	ND	< 0.0045 U,F1	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U,F2,F1	< 0.0068 U	< 0.0043 U
MW-33	SSHS-MW-33	T	3/23/2016	180-53337-1	0.0089	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	0.0089 J	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-33	SSHS-MW-33_F	D	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-34	DUP-2	T	8/22/2014	180-36053-1	1.9	< 0.013 U	< 0.013 U	< 0.015 U	< 0.0094 U	1.9	< 0.012 U	< 0.0068 U	< 0.01 U	< 0.014 U
MW-34	GW-FD-4_F	D	3/23/2016	180-53337-1	0.33	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	0.33	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-34	MW-34	D	4/30/2021	180-120955-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-34	MW-34	T	8/22/2014	180-36053-1	1.4	< 0.013 U	< 0.013 U	< 0.015 U	< 0.0094 U	1.4	< 0.012 U	< 0.0068 U	< 0.01 U	< 0.014 U
MW-34	MW-34	T	2/24/2021	180-117542-1	0.59	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.59	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-34	MW-34	T	4/30/2021	180-120955-1	0.29	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.29	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-34	SSHS-MW-34	T	3/23/2016	180-53337-1	1.1	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	1.1	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-34	SSHS-MW-34_F	D	3/23/2016	180-53337-1	0.34	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	0.34	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-34	SSHS-MW-34-04302024	T	4/30/2024	1801733261	0.67	< 0.0046 U	< 0.0056 U	< 0.0051 U	0.67	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-36	MW-36	D	4/30/2021	180-120955-1	ND	< 0.0048 U,*3	< 0.0057 U,*3	< 0.0052 U,*3	< 0.0036 U,*3	< 0.003 U,*3	< 0.0046 U,*3	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-36	MW-36	T	3/23/2021	180-118872-1	ND	< 0.0052 U	< 0.0062 U	< 0.0057 U	< 0.0039 U	< 0.0033 U	< 0.005 U	< 0.0043 U,*3	< 0.0077 U,*3	< 0.0049 U,*3
MW-36	MW-36	T	4/30/2021	180-120955-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-36	SSHS-MW36	D	8/22/2018	180-81174-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0087 U	< 0.0028 U	< 0.0091 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-36	SSHS-MW36	T	8/22/2018	180-81174-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0086 U	< 0.0028 U	< 0.009 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-36	SSHS-MW-36	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-36	SSHS-MW-36_F	D	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-38	DUP-1	D	4/30/2021	180-120955-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-38	DUP-1	T	4/30/2021	180-120955-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-38	MW-38	D	4/30/2021	180-120955-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-38	MW-38	T	8/21/2014	180-36053-1	ND	< 0.0025 U	< 0.0025 U	< 0.0029 U	< 0.0019 U	< 0.0023 U	< 0.0023 U	< 0.0014 U	< 0.0021 U	< 0.0027 U
MW-38	MW-38	T	3/24/2021	180-119009-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-38	MW-38	T	4/30/2021	180-120955-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-38	PS-FD-1	D	8/24/2018	180-81247-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.009 U	< 0.0029 U	< 0.0093 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-38	PS-FD-1	T	8/24/2018	180-81247-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0087 U	< 0.0028 U	< 0.0091 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-38	SSHS-MW-38	D	8/23/2018	180-81247-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.009 U	< 0.003 U	< 0.0094 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-38	SSHS-MW-38	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-38	SSHS-MW-38	T	8/23/2018	180-81247-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0086 U	< 0.0028 U	< 0.009 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-38	SSHS-MW-38_F	D	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-39	SSHS-MW-39	D	8/23/2018	180-81247-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.009 U	< 0.0029 U	< 0.0093 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-39	SSHS-MW-39	T	3/23/2016	180-53337-1	0.043	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	0.043	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-39	SSHS-MW-39	T	8/23/2018	180-81247-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0088 U	< 0.0029 U	< 0.0092 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-39	SSHS-MW-39_F	D	3/23/2016	180-53337-1	0.015	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	0.015	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-40	MW-40	T	5/23/2019	180-90525-1	ND	< 0.0045 U,*	< 0.0054 U	< 0.005 U	< 0.0087 U	< 0.0028 U	< 0.0091 U	< 0.0037 U,*	< 0.0068 U	< 0.0043 U
MW-40	MW-40	T	2/23/2021	180-117459-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-41	DUP-03	T	2/20/2021	180-117476-1	0.323	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.28	0.043	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-41	MW-41	D	7/13/2021	180-124378-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-41	MW-41	T	3/26/2008		120	0	0	0		120	0	0		
MW-41	MW-41	T	8/22/2014	180-36053-1	23	< 0.13 U	< 0.12 U	< 0.15 U	< 0.093 U	23	< 0.11 U	< 0.068 U	< 0.1 U	< 0.14 U
MW-41	MW-41	T	2/20/2021	180-117476-1	0.481	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.43	0.051	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-41	MW-41	T	7/13/2021	180-124378-1	0.54	< 0.0047 U	< 0.0056 U	< 0.0051 U	0.54	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-41	SSHS-MW-41	T	3/23/2016	180-53337-1	17	< 0.035 U	< 0.056 U	< 0.057 U	< 0.032 U	17	< 0.042 U	< 0.027 U	< 0.025 U	< 0.023 U
MW-41	SSHS-MW-41_F	D	3/23/2016	180-53337-1	2	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	2	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-41	SSHS-MW-41-04112024	T	4/11/2024	1801722801	0.55	< 0.0052 U	< 0.0062 U	< 0.0057 U	< 0.0039 U	0.55	< 0.0050 U	< 0.0043 U	< 0.0077 U	< 0.0049 U
MW-42	SSHS-MW-42	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-42	SSHS-MW-42_F	D	3/23/2016	180-53337-1	0.018	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	0.018	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-43	MW-43	D	7/13/2021	180-124378-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-43	MW-43	T	2/16/2021	180-117390-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-43	MW-43	T	7/13/2021	180-124378-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-43	SSHS-MW-43	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-43	SSHS-MW-43_F	D	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-44	SSHS-MW-44	D	8/23/2018	180-81247-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0088 U	< 0.0029 U	< 0.0092 U	< 0.0038 U	< 0.0068 U	< 0.0044 U

TABLE 5-8
Groundwater Results - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Groundwater Results - PCBs					**PCBs**									
					Total PCBs	**Aroclor 1016**	**Aroclor 1221**	**Aroclor 1232**	**Aroclor 1242**	**Aroclor 1248**	**Aroclor 1254**	**Aroclor 1260**	**Aroclor 1262**	**Aroclor 1268**
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.09									
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-44	SSHS-MW-44	T	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-44	SSHS-MW-44	T	8/23/2018	180-81247-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0086 U	< 0.0028 U	< 0.009 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-44	SSHS-MW-44 F	D	3/23/2016	180-53337-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-46	SSHS-MW-46	D	9/27/2016	180-59149-1	ND	< 0.0033 U	< 0.0089 U	< 0.0032 U	< 0.0091 U	< 0.0067 U	< 0.0048 U	< 0.0056 U	< 0.0065 U	< 0.0064 U
MW-46	SSHS-MW-46	T	9/27/2016	180-59149-1	ND	< 0.0034 U	< 0.0092 U	< 0.0033 U	< 0.0093 U	< 0.0069 U	< 0.005 U	< 0.0057 U	< 0.0067 U	< 0.0066 U
MW-47	DUP-01	T	2/22/2021	180-117425-1	0.049	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.039	0.01	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-47	GW-FD-0927	D	9/27/2016	180-59149-1	ND	< 0.0034 U	< 0.0092 U	< 0.0033 U	< 0.0093 U	< 0.0069 U	< 0.005 U	< 0.0057 U	< 0.0067 U	< 0.0066 U
MW-47	GW-FD-0927	T	9/27/2016	180-59149-1	ND	< 0.0035 U	< 0.0093 U	< 0.0034 U	< 0.0094 U	< 0.0069 U	< 0.005 U	< 0.0058 U	< 0.0068 U	< 0.0067 U
MW-47	MW-47	D	7/12/2021	180-124354-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-47	MW-47	T	2/22/2021	180-117425-1	0.064	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.051	0.013	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-47	MW-47	T	7/12/2021	180-124354-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U,*3	< 0.0071 U,*3	< 0.0046 U,*3
MW-47I	DUP-01	D	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-47I	DUP-01	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-47I	MW-47I	D	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-47I	MW-47I	D	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-47I	MW-47I	T	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-47I	MW-47I	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-47I	SSHS-DUP-01-04252024	T	4/25/2024	1801731401	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-47I	SSHS-MW-47I-04252024	T	4/25/2024	1801731401	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-48	MW-48	D	4/26/2021	180-120679-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-48	MW-48	T	2/17/2021	180-117387-1	0.015	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.015 B	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-48R	DUP-01-01162024	T	1/16/2024	1801682361	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-48R	SSHS-DUP-01-11152023	T	11/15/2023	1801654471	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-48R	SSHS-DUP-02-04092024	T	4/9/2024	1801721201	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-48R	SSHS-MW-48R-01162024	T	1/16/2024	1801682361	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-48R	SSHS-MW-48R-04092024	T	4/9/2024	1801721201	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-48R	SSHS-MW-48R-09132023	T	9/13/2023	1801624601	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-48R	SSHS-MW-48R-11152023	T	11/15/2023	1801654471	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-49	DUP-04	T	2/17/2021	180-117387-1	0.0249	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.019 B	0.0059 J	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-49	MW-49	D	4/28/2021	180-120857-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-49	MW-49	T	2/17/2021	180-117387-1	0.015	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.015 B	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-49	MW-49	T	4/28/2021	180-120857-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-50I	MW-50I	D	4/28/2021	180-120857-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-50I	MW-50I	T	4/28/2021	180-120857-1	0.14	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.14	< 0.0043 U	< 0.0037 U,F2,F1	< 0.0068 U	< 0.0043 U
MW-50I	SSHS-RI-MW-50I	T	2/12/2021	180-117176-1	0.09	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.09	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-50R	SSHS-MW-50R-04082024	T	4/8/2024	1801720381	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0081 U	< 0.0046 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-50R	SSHS-MW-50R-09142023	T	9/14/2023	1801625611	0.044	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	0.044	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-50S	MW-50S	D	4/28/2021	180-120857-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-50S	MW-50S	T	4/28/2021	180-120857-1	2.3	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	2.3	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-50S	SSHS-RI-MW-50S	T	2/12/2021	180-117176-1	0.95	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.67	0.28	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-51	DUP-05	T	2/12/2021	180-117176-1	0.74	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.61	0.13	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-51	MW-51	D	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-51	MW-51	T	4/27/2021	180-120743-1	0.1	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	0.1	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-51	SSHS-DUP-04-09142023	T	9/14/2023	1801625601	0.13	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.13	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-51	SSHS-MW-51-01182024	T	1/18/2024	1801682891	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-51	SSHS-MW-51-04092024	T	4/9/2024	1801721201	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-51	SSHS-MW-51-05022023	T	5/2/2023	1801559471	0.074	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.074	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-51	SSHS-MW-51-09142023	T	9/14/2023	1801625601	0.091	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.091	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-51	SSHS-MW-51-11142023	T	11/14/2023	1801653531	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-51	SSHS-RI-MW-51	T	2/12/2021	180-117176-1	0.75	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.61	0.14	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-52	DUP-2	D	4/28/2021	180-120857-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-52	DUP-2	T	4/28/2021	180-120857-1	7.6	< 0.045 U	< 0.054 U	< 0.05 U	< 0.034 U	7.6	< 0.043 U	< 0.037 U	< 0.068 U	< 0.043 U
MW-52	MW-52	D	4/28/2021	180-120857-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-52	MW-52	T	4/28/2021	180-120857-1	5.2	< 0.045 U	< 0.054 U	< 0.05 U	< 0.034 U	5.2	< 0.043 U	< 0.037 U	< 0.068 U	< 0.043 U
MW-52	SSHS-RI-MW-52	T	2/12/2021	180-117176-1	12.5	< 0.047 U	< 0.057 U	< 0.052 U	< 0.035 U	11	1.5	< 0.039 U	< 0.07 U	< 0.045 U
MW-53	MW-53	D	4/26/2021	180-120679-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-53	MW-53	T	2/17/2021	180-117387-1	0.01	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.01 B	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-53	MW-53	T	4/26/2021	180-120679-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-53	SSHS-MW-53-09042023	T	9/4/2023	1801619191	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-54	MW-54	D	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-54	MW-54	T	2/16/2021	180-117390-1	0.015	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.015	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-54	MW-54	T	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-54R	SSHS-MW-54R-09142023	T	9/14/2023	1801625611	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-55	DUP-01-05022023	T	5/2/2023	1801559471	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-55	MW-55	T	2/16/2021	180-117390-1	0.0095	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.0095	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-55	SSHS-MW-55-01162024	T	1/16/2024	1801682361	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-55	SSHS-MW-55-04092024	T	4/9/2024	1801721201	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-55	SSHS-MW-55-05022023	T	5/2/2023	1801559471	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-55	SSHS-MW-55-09132023	T	9/13/2023	1801624601	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-55	SSHS-MW-55-11152023	T	11/15/2023	1801654471	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-56	MW-56	T	2/17/2021	180-117387-1	0.59	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.43 B	0.16	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-56	SSHS-MW-56-04082024	T	4/8/2024	1801720381	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-56	SSHS-MW-56-09142023	T	9/14/2023	1801625611	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-57	DUP-01	D	7/13/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-57	DUP-01	T	7/13/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-57	MW-57	D	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-57	MW-57	D	7/13/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-57	MW-57	T	2/18/2021	180-117476-1	40.9	< 0.093 U	< 0.11 U	< 0.1 U	< 0.07 U	31	9.9	< 0.077 U	< 0.14 U	< 0.089 U
MW-57	MW-57	T	4/29/2021	180-121010-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-57	MW-57	T	7/13/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-57R	SSHS-MW-57R-01172024	T	1/17/2024	1801682361	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 UT	< 0.0071 UT	< 0.0046 UT
MW-57R	SSHS-MW-57R-04092024	T	4/9/2024	1801721201	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-57R	SSHS-MW-57R-05022023	T	5/2/2023	1801559471	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-57R	SSHS-MW-57R-09142023	T	9/14/2023	1801625601	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-57R	SSHS-MW-57R-11132023	T	11/13/2023	1801653531	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-58	MW-58	D	4/30/2021	180-120955-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-58	MW-58	T	2/21/2021	180-117476-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-58	MW-58	T	4/30/2021	180-120955-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-58	SSHS-DUP-01-09142023	T	9/14/2023	1801625611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-58	SSHS-MW-58-09142023	T	9/14/2023	1801625611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-59I	MW-59I	D	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-59I	MW-59I	D	7/12/2022	1801412391	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-59I	MW-59I	T	2/19/2021	180-117476-1	0.031	< 0.0049 U	< 0.0059 U	< 0.0054 U	< 0.0037 U	0.031	< 0.0047 U	< 0.004 U	< 0.0073 U	< 0.0047 U
MW-59I	MW-59I	T	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-59I	MW-59I	T	7/12/2022	1801412391	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-59S	MW-59S	D	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-59S	MW-59S	D	7/13/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-59S	MW-59S	T	2/19/2021	180-117476-1	0.027	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.027	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-59S	MW-59S	T	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-59S	MW-59S	T	7/13/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-5I	SSHS-MW-5I-04102024	T	4/10/2024	1801721871	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-5I	SSHS-MW-5I-09132023	T	9/13/2023	1801624611	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-5S	MW-5	D	7/15/2021	180-124580-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-5S	MW-5	T	2/23/2021	180-117459-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-5S	MW-5	T	7/15/2021	180-124580-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-60	MW-60	D	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-60	MW-60	D	7/12/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-60	MW-60	T	2/18/2021	180-117476-1	0.152	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.096	0.056	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-60	MW-60	T	4/29/2021	180-121010-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-60	MW-60	T	7/12/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-61	MW-61	D	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-61	MW-61	D	7/12/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 UT	< 0.0037 UT	< 0.0068 UT	< 0.0043 UT
MW-61	MW-61	T	2/16/2021	180-117390-1	0.012	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	0.012	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-61	MW-61	T	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-61	MW-61	T	7/12/2022	1801412391	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-62	MW-62	D	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-62	MW-62	D	7/12/2022	1801412391	ND	< 0.0049 U	< 0.0059 U	< 0.0054 U	< 0.0037 U	< 0.0083 U	< 0.0047 U	< 0.0040 U	< 0.0073 U	< 0.0047 U
MW-62	MW-62	T	2/16/2021	180-117390-1	0.018	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.018	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-62	MW-62	T	4/27/2021	180-120743-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-62	MW-62	T	7/12/2022	1801412391	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-62R	SSHS-MW-62R-04042024	T	4/4/2024	1801719081	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-62R	SSHS-MW-62R-09142023	T	9/14/2023	1801625611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-63I	MW-63I	D	4/29/2021	180-121010-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-63I	MW-63I	T	2/18/2021	180-117476-1	0.53	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.39	0.14	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-63I	MW-63I	T	4/29/2021	180-121010-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-63I	SSHS-MW-63I-09132023	T	9/13/2023	1801624611	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-63S	MW-63S	D	4/29/2021	180-121010-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-63S	MW-63S	T	2/18/2021	180-117476-1	0.038	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.038	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-63S	MW-63S	T	4/29/2021	180-121010-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-63S	SSHS-MW-63S-09132023	T	9/13/2023	1801624611	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-64I	MW-64I	D	4/28/2021	180-120857-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-64I	MW-64I	T	2/20/2021	180-117476-1	0.041	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.041	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-64I	MW-64I	T	4/28/2021	180-120857-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-64I	SSHS-MW-64I-09122023	T	9/12/2023	1801624611	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-64S	MW-64S	D	4/28/2021	180-120857-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-64S	MW-64S	T	2/20/2021	180-117476-1	0.037	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.037	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-64S	MW-64S	T	4/28/2021	180-120857-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-64S	SSHS-MW-64S-09122023	T	9/12/2023	1801624611	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-65	DUP-3	D	4/26/2021	180-120679-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-65	DUP-3	T	4/26/2021	180-120679-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-65	MW-65	D	4/26/2021	180-120679-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-65	MW-65	T	2/20/2021	180-117476-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-65	MW-65	T	4/26/2021	180-120679-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-65	SSHS-DUP1-08152022	D	8/15/2022	1801429571	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-65	SSHS-DUP1-08152022	T	8/15/2022	1801429571	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-65	SSHS-MW-65-08152022	D	8/15/2022	1801429571	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-65	SSHS-MW-65-08152022	T	8/15/2022	1801429571	ND	< 0.0046 UT	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 UT	< 0.0069 U	< 0.0044 U
MW-65R	SSHS-MW-65R-04082024	T	4/8/2024	1801720411	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-65R	SSHS-MW-65R-09142023	T	9/14/2023	1801625611	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-66I	MW-66I	D	4/28/2021	180-120857-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-66I	MW-66I	T	2/20/2021	180-117476-1	0.027	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.027	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-66I	MW-66I	T	4/28/2021	180-120857-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-66I	SSHS-MW-66I-09122023	T	9/12/2023	1801624611	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-66S	MW-66S	D	4/28/2021	180-120857-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-66S	MW-66S	T	2/19/2021	180-117476-1	0.037	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.037	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U

TABLE 5-8
Groundwater Results - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Groundwater Results - PCBs					PCBs									
					Total PCBs	**Aroclor 1016**	**Aroclor 1221**	**Aroclor 1232**	**Aroclor 1242**	**Aroclor 1248**	**Aroclor 1254**	**Aroclor 1260**	**Aroclor 1262**	**Aroclor 1268**
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.09									
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-66S	MW-66S	T	4/28/2021	180-120857-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-66S	SSHS-MW-66S-09122023	T	9/12/2023	1801624611	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-67I	MW-67I	D	7/16/2021	180-124628-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-67I	MW-67I	D	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-67I	MW-67I	T	7/16/2021	180-124628-1	0.045	< 0.0048	< 0.0057	< 0.0052	< 0.0036	0.045	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-67I	MW-67I	T	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-67I	SSHS-MW-67I-04282024	T	4/28/2024	1801733271	0.0082	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	0.0082 J	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-67S	MW-67S	D	7/16/2021	180-124628-1	ND	< 0.0047	< 0.0057	< 0.0052	< 0.0035	< 0.003	< 0.0045	< 0.0039	< 0.007	< 0.0045
MW-67S	MW-67S	D	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-67S	MW-67S	T	7/16/2021	180-124628-1	ND	< 0.0048	< 0.0057	< 0.0052	< 0.0036	< 0.003	< 0.0046	< 0.0039	< 0.0071	< 0.0046
MW-67S	MW-67S	T	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-67S	SSHS-DUP-03-04282024	T	4/28/2024	1801733271	0.61	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.61	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-67S	SSHS-MW-67S-04282024	T	4/28/2024	1801733271	0.43	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.43	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-68S	DUP-2	D	9/9/2021	180-126905-1	0.11	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.11	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-68S	DUP-2	T	9/9/2021	180-126905-1	9	< 0.048 U	< 0.058 U	< 0.053 U	< 0.036 U	9	< 0.046 U	< 0.04 U	< 0.072 U	< 0.046 U
MW-68S	DUP-3	D	7/13/2021	180-124378-1	0.22	< 0.0045 U	< 0.0054 U	< 0.0049 U	0.22	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-68S	DUP-3	T	7/13/2021	180-124378-1	18	< 0.047 U	< 0.057 U	< 0.052 U	18	< 0.03 U	< 0.045 U	< 0.039 U	< 0.07 U	< 0.045 U
MW-68S	MW-68S	D	7/13/2021	180-124378-1	0.17	< 0.0046 U	< 0.0055 U	< 0.005 U	0.17	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-68S	MW-68S	D	9/9/2021	180-126905-1	0.12	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	0.12	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-68S	MW-68S	T	7/13/2021	180-124378-1	17	< 0.045 U	< 0.054 U	< 0.049 U	17	< 0.028 U	< 0.043 U	< 0.037 U	< 0.067 U	< 0.043 U
MW-68S	MW-68S	T	9/9/2021	180-126905-1	5.7	< 0.048 U	< 0.057 U	< 0.052 U	< 0.036 U	5.7	< 0.046 U	< 0.039 U	< 0.071 U	< 0.046 U
MW-68S	SSHS-MW-68S-04282024	T	4/28/2024	1801733271	16	< 0.092 UT	< 0.11 U	< 0.10 U	16	< 0.15 U	< 0.088 U	< 0.075 U	< 0.14 U	< 0.088 U
MW-69I	MW-69I	D	7/13/2021	180-124378-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-69I	MW-69I	D	9/3/2021	180-126702-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-69I	MW-69I	T	7/13/2021	180-124378-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-69I	MW-69I	T	9/3/2021	180-126702-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-69I	SSHS-MW-69I-04112024	T	4/11/2024	1801722811	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-70I	MW-70I	D	9/9/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-70I	MW-70I	D	10/27/2021	180-129230-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-70I	MW-70I	T	9/9/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-70I	MW-70I	T	10/27/2021	180-129230-1	ND	< 0.005 U	< 0.006 U	< 0.0054 U	< 0.0037 U	< 0.0031 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-70I	SSHS-MW-70I-04042024	T	4/4/2024	1801719081	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-70S	DUP-02	T	5/4/2023	1801561231	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-70S	MW-70S	D	9/7/2021	180-126846-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-70S	MW-70S	D	10/27/2021	180-129230-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-70S	MW-70S	T	9/7/2021	180-126846-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-70S	MW-70S	T	10/27/2021	180-129230-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-70S	SSHS-DUP-04-04042024	T	4/4/2024	1801719081	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0081 U	< 0.0046 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-70S	SSHS-MW-70S-04042024	T	4/4/2024	1801719081	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-70S	SSHS-MW-70S-05042023	T	5/4/2023	1801561231	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-70S	SSHS-MW-70S-09152023	T	9/15/2023	1801625621	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-71I	MW-71I	D	9/7/2021	180-126846-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-71I	MW-71I	D	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-71I	MW-71I	T	9/7/2021	180-126846-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-71I	MW-71I	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-71I	SSHS-MW-71I-04052024	T	4/5/2024	1801720031	ND	< 0.0050 U	< 0.0060 U	< 0.0055 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0075 U	< 0.0048 U
MW-71S	MW-71S	D	9/7/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-71S	MW-71S	D	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-71S	MW-71S	T	9/7/2021	180-126846-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-71S	MW-71S	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-71S	SSHS-MW-71S-04052024	T	4/5/2024	1801720031	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0081 U	< 0.0046 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-72I	DUP-02	D	10/27/2021	180-129155-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-72I	DUP-02	T	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-72I	MW-72I	D	9/8/2021	180-126846-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-72I	MW-72I	D	10/27/2021	180-129155-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-72I	MW-72I	T	9/8/2021	180-126846-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-72I	MW-72I	T	10/27/2021	180-129155-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-72I	SSHS-MW-72I-04042024	T	4/4/2024	1801719081	ND	< 0.0052 U	< 0.0063 U	< 0.0057 U	< 0.0039 U	< 0.0088 U	< 0.0050 U	< 0.0043 U	< 0.0078 U	< 0.0050 U
MW-72S	MW-72S	D	9/8/2021	180-126846-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-72S	MW-72S	D	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-72S	MW-72S	T	9/8/2021	180-126846-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-72S	MW-72S	T	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-72S	SSHS-MW-72S-04042024	T	4/4/2024	1801719081	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-72S	SSHS-MW-72S-05042023	T	5/4/2023	1801561231	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-72S	SSHS-MW-72S-09152023	T	9/15/2023	1801625621	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-73I	MW-73I	D	9/8/2021	180-126846-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-73I	MW-73I	D	10/27/2021	180-129230-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-73I	MW-73I	T	9/8/2021	180-126846-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-73I	MW-73I	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-73I	SSHS-MW-73I-04052024	T	4/5/2024	1801720031	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-73S	MW-73S	D	9/8/2021	180-126846-1	0.026	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.026	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-73S	MW-73S	D	10/26/2021	180-129230-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-73S	MW-73S	T	9/8/2021	180-126846-1	0.045	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	0.045	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-73S	MW-73S	T	10/26/2021	180-129230-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-73S	SSHS-MW-73S-04052024	T	4/5/2024	1801720031	ND	< 0.0051 U	< 0.0061 U	< 0.0055 U	< 0.0038 U	< 0.0085 U	< 0.0049 U	< 0.0042 U	< 0.0076 U	< 0.0048 U
MW-74I	MW-74I	D	9/8/2021	180-126846-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-74I	MW-74I	D	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-74I	MW-74I	T	9/8/2021	180-126846-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-74I	MW-74I	T	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-74I	SSHS-MW-74I-04052024	T	4/5/2024	1801720031	ND	< 0.0050 U	< 0.0060 U	< 0.0055 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0075 U	< 0.0048 U
MW-74S	MW-74S	D	9/8/2021	180-126846-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-74S	MW-74S	D	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-74S	MW-74S	T	9/8/2021	180-126846-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-74S	MW-74S	T	10/27/2021	180-129155-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-74S	SSHS-DUP-05-04052024	T	4/5/2024	1801720031	ND	< 0.0050 U	< 0.0060 U	< 0.0055 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0075 U	< 0.0048 U
MW-74S	SSHS-MW-74S-04052024	T	4/5/2024	1801720031	ND	< 0.0050 U	< 0.0060 U	< 0.0055 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0075 U	< 0.0048 U
MW-75I	MW-75I	D	9/9/2021	180-126905-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-75I	MW-75I	D	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-75I	MW-75I	T	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-75I	MW-75I	T	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-75I	SSHS-MW-75I-04112024	T	4/11/2024	1801722811	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-75S	MW-75S	D	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-75S	MW-75S	D	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-75S	MW-75S	T	9/9/2021	180-126905-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-75S	MW-75S	T	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-75S	SSHS-MW-75S-04112024	T	4/11/2024	1801722811	ND	< 0.0051 U	< 0.0062 U	< 0.0056 U	< 0.0038 U	< 0.0086 U	< 0.0049 U	< 0.0042 U	< 0.0076 U	< 0.0049 U
MW-76I	DUP-03	D	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-76I	DUP-03	T	10/28/2021	180-129230-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-76I	MW-76I	D	9/10/2021	180-126939-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-76I	MW-76I	D	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-76I	MW-76I	T	9/10/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-76I	MW-76I	T	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-76S	MW-76S	D	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-76S	MW-76S	D	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-76S	MW-76S	T	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-76S	MW-76S	T	10/28/2021	180-129230-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-76S	SSHS-MW-76S-04082024	T	4/8/2024	1801720411	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-76S	SSHS-MW-76S-04222024	T	4/22/2024	1801730541	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-77I	MW-77I	D	9/10/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-77I	MW-77I	D	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-77I	MW-77I	T	9/10/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-77I	MW-77I	T	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-77I	SSHS-MW-77I-04042024	T	4/4/2024	1801719081	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-77S	MW-77S	D	9/10/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-77S	MW-77S	D	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-77S	MW-77S	T	9/10/2021	180-126939-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-77S	MW-77S	T	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-77S	SSHS-MW-77S-04042024	T	4/4/2024	1801719081	0.03	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.030	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-78I	MW-78I	D	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78I	MW-78I	D	11/2/2021	180-129534-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-78I	MW-78I	T	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78I	MW-78I	T	11/2/2021	180-129534-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78I	SSHS-MW-78I-04052024	T	4/5/2024	1801720031	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-78S	DUP-5	D	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78S	DUP-5	T	9/10/2021	180-126939-1	0.021	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.021	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78S	MW-78S	D	9/10/2021	180-126939-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78S	MW-78S	D	11/2/2021	180-129534-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-78S	MW-78S	T	9/10/2021	180-126939-1	0.026	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.026	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-78S	MW-78S	T	11/2/2021	180-129534-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-78S	SSHS-MW-78S-04052024	T	4/5/2024	1801720031	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-79I	DUP-04	D	11/2/2021	180-129534-1	ND	< 0.0051 U	< 0.0062 U	< 0.0056 U	< 0.0038 U	< 0.0032 U	< 0.0049 U	< 0.0042 U	< 0.0076 U	< 0.0049 U
MW-79I	DUP-04	T	11/2/2021	180-129534-1	ND	< 0.0049 U	< 0.0059 U	< 0.0054 U	< 0.0037 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0073 U	< 0.0047 U
MW-79I	MW-79I	D	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-79I	MW-79I	D	11/2/2021	180-129534-1	ND	< 0.005 U	< 0.006 U	< 0.0054 U	< 0.0037 U	< 0.0031 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-79I	MW-79I	T	9/10/2021	180-126939-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-79I	MW-79I	T	11/2/2021	180-129534-1	ND	< 0.005 U	< 0.006 U	< 0.0054 U	< 0.0037 U	< 0.0031 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-79I	SSHS-MW-79I-04052024	T	4/5/2024	1801720031	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-79S	MW-79S	D	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-79S	MW-79S	D	11/2/2021	180-129534-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-79S	MW-79S	T	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-79S	MW-79S	T	11/2/2021	180-129534-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-79S	SSHS-DUP-06-04052024	T	4/5/2024	1801720031	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-79S	SSHS-MW-79S-04052024	T	4/5/2024	1801720031	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-81I	MW-81I	D	7/16/2021	180-124628-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-81I	MW-81I	D	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-81I	MW-81I	T	7/16/2021	180-124628-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-81I	MW-81I	T	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-81I	SSHS-MW-81I-04262024	T	4/26/2024	1801731401	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-82S	DUP-3	D	9/7/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-82S	DUP-3	T	9/7/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-82S	MW-82S	D	9/7/2021	180-126846-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-82S	MW-82S	D	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-82S	MW-82S	T	9/7/2021	180-126846-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-82S	MW-82S	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-82S	SSHS-MW-82S-05012024	T	5/1/2024	1801733271	0.046	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.046	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U

TABLE 5-8
Groundwater Results - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

Groundwater Results - PCBs					PCBs									
					Total PCBs	**Aroclor 1016**	**Aroclor 1221**	**Aroclor 1232**	**Aroclor 1242**	**Aroclor 1248**	**Aroclor 1254**	**Aroclor 1260**	**Aroclor 1262**	**Aroclor 1268**
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.09									
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-83I	MW-83I	D	9/8/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-83I	MW-83I	D	10/27/2021	180-129155-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-83I	MW-83I	T	9/8/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-83I	MW-83I	T	10/27/2021	180-129155-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-83I	SSHS-MW-83I-04102024	T	4/10/2024	1801721871	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-83S	MW-83S	D	9/8/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-83S	MW-83S	D	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-83S	MW-83S	T	9/8/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-83S	MW-83S	T	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-83S	SSHS-MW-83S-04102024	T	4/10/2024	1801721871	ND	< 0.0049 U	< 0.0059 U	< 0.0054 U	< 0.0037 U	< 0.0083 U	< 0.0047 U	< 0.0040 U	< 0.0073 U	< 0.0047 U
MW-84S	MW-84S	D	9/9/2021	180-126905-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-84S	MW-84S	D	10/27/2021	180-129155-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-84S	MW-84S	T	9/9/2021	180-126905-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-84S	MW-84S	T	10/27/2021	180-129155-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-84S	SSHS-DUP-07-04152024	T	4/15/2024	1801726651	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-84S	SSHS-MW-84S-04152024	T	4/15/2024	1801726651	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-85I	MW-85I	D	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-85I	MW-85I	D	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-85I	MW-85I	T	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-85I	MW-85I	T	9/2/2021	180-126608-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-85I	SSHS-MW-85I-04222024	T	4/22/2024	1801730541	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-86I	MW-86I	D	7/13/2021	180-124378-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-86I	MW-86I	D	9/1/2021	180-126593-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-86I	MW-86I	T	7/13/2021	180-124378-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-86I	MW-86I	T	9/1/2021	180-126593-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-86I	SSHS-MW-86I-04042024	T	4/4/2024	1801719081	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-87I	MW-87I	D	7/14/2021	180-124487-1	ND	< 0.0046	< 0.0055	< 0.005	< 0.0034	< 0.0029	< 0.0044	< 0.0038	< 0.0068	< 0.0044
MW-87I	MW-87I	D	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-87I	MW-87I	T	7/14/2021	180-124487-1	0.085	< 0.0045	< 0.0054	< 0.005	< 0.0034	0.085	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-87I	MW-87I	T	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-87I	SSHS-MW-87I-04112024	T	4/11/2024	1801722811	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-88I	MW-88I	D	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-88I	MW-88I	D	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-88I	MW-88I	T	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-88I	MW-88I	T	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-88I	SSHS-MW-88I-04112024	T	4/11/2024	1801722811	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-88S	MW-88S	D	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-88S	MW-88S	D	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-88S	MW-88S	T	7/15/2021	180-124580-1	ND	< 0.0045	< 0.0054	< 0.0049	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0067	< 0.0043
MW-88S	MW-88S	T	9/2/2021	180-126608-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-88S	SSHS-MW-88S-04112024	T	4/11/2024	1801722811	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-89I	MW-89I	D	7/12/2021	180-124354-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U,*3	< 0.0068 U,*3	< 0.0044 U,*3
MW-89I	MW-89I	D	9/1/2021	180-126593-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-89I	MW-89I	T	7/12/2021	180-124354-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-89I	MW-89I	T	9/1/2021	180-126593-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-89I	SSHS-MW-89I-04052024	T	4/5/2024	1801720031	ND	< 0.0053 U	< 0.0064 U	< 0.0058 U	< 0.0040 U	< 0.0089 U	< 0.0051 U	< 0.0044 U	< 0.0079 U	< 0.0051 U
MW-89S	MW-89S	D	7/12/2021	180-124354-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U,*3	< 0.0067 U,*3	< 0.0043 U,*3
MW-89S	MW-89S	D	9/1/2021	180-126593-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-89S	MW-89S	T	7/12/2021	180-124354-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U,*3	< 0.0067 U,*3	< 0.0043 U,*3
MW-89S	MW-89S	T	9/1/2021	180-126593-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-89S	SSHS-MW-89S-04302024	T	4/30/2024	1801733271	0.1	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.10	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-8I	DUP-1	D	8/30/2021	180-126485-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-8I	DUP-1	T	8/30/2021	180-126485-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-8I	MW-8I	D	7/1/2021	180-123971-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-8I	MW-8I	D	8/30/2021	180-126485-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-8I	MW-8I	T	7/1/2021	180-123971-1	0.043	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	0.043	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-8I	MW-8I	T	8/30/2021	180-126485-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-8I	SSHS-MW-8I-04302024	T	4/30/2024	1801733271	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-8S	GW-FD-3 F	D	3/22/2016	180-53281-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-8S	MW-8S	D	7/12/2021	180-124354-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-8S	MW-8S	T	2/18/2021	180-117476-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-8S	MW-8S	T	7/12/2021	180-124354-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-8S	SSHS-MW-8S	T	3/22/2016	180-53281-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-8S	SSHS-MW-8S F	D	3/22/2016	180-53281-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-90I	MW-90I	D	9/8/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-90I	MW-90I	D	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-90I	MW-90I	T	9/8/2021	180-126846-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-90I	MW-90I	T	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-90I	SSHS-MW-90I-04102024	T	4/10/2024	1801721871	0.028	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	0.028	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-90S	MW-90S	D	9/8/2021	180-126846-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-90S	MW-90S	D	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-90S	MW-90S	T	9/8/2021	180-126846-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-90S	MW-90S	T	10/28/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-90S	SSHS-MW-90S-04102024	T	4/10/2024	1801721871	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-91I	MW-91I	D	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-91I	MW-91I	D	11/2/2021	180-129534-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-91I	MW-91I	T	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-91I	MW-91I	T	11/2/2021	180-129534-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-91I	SSHS-MW-91I-04102024	T	4/10/2024	1801721871	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-91S	MW-91S	D	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-91S	MW-91S	D	11/2/2021	180-129534-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-91S	MW-91S	T	9/9/2021	180-126905-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-91S	MW-91S	T	11/2/2021	180-129534-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-91S	SSHS-MW-91S-04112024	T	4/11/2024	1801722811	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-92I	MW-92I	D	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-92I	MW-92I	D	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-92I	MW-92I	T	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-92I	MW-92I	T	10/28/2021	180-129230-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-92I	SSHS-MW-92I-04082024	T	4/8/2024	1801720411	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-92S	MW-92S	D	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-92S	MW-92S	D	10/28/2021	180-129230-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
MW-92S	MW-92S	T	9/10/2021	180-126939-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-92S	MW-92S	T	10/28/2021	180-129230-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-92S	SSHS-MW-92S-04052024	T	4/5/2024	1801720031	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-93I	DUP-4	D	9/9/2021	180-126905-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-93I	DUP-4	T	9/9/2021	180-126905-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-93I	MW-93I	D	9/9/2021	180-126905-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-93I	MW-93I	D	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-93I	MW-93I	T	9/9/2021	180-126905-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-93I	MW-93I	T	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-93I	SSHS-DUP-08-04112024	T	4/11/2024	1801722811	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-93I	SSHS-MW-93I-04112024	T	4/11/2024	1801722811	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-93S	MW-93S	D	9/9/2021	180-126905-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
MW-93S	MW-93S	D	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-93S	MW-93S	T	9/9/2021	180-126905-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-93S	MW-93S	T	10/29/2021	180-129376-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-93S	SSHS-MW-93S-04112024	T	4/11/2024	1801722811	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-94I	MW-94I	D	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-94I	MW-94I	D	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-94I	MW-94I	T	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-94I	MW-94I	T	10/27/2021	180-129230-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-94I	SSHS-MW-94I-04112024	T	4/11/2024	1801722811	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-94S	MW-94S	D	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-94S	MW-94S	D	10/27/2021	180-129230-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-94S	MW-94S	T	9/9/2021	180-126905-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-94S	MW-94S	T	10/27/2021	180-129230-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-94S	SSHS-MW-94S-04112024	T	4/11/2024	1801722811	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-95I	SSHS-MW-95I-01162024	T	1/16/2024	1801682361	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-95I	SSHS-MW-95I-04112024	T	4/11/2024	1801722791	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-95I	SSHS-MW-95I-09122023	T	9/12/2023	1801624601	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-95I	SSHS-MW-95I-11142023	T	11/14/2023	1801653531	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-95S	SSHS-MW-95S-01162024	T	1/16/2024	1801682361	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0039 U	< 0.0070 U	< 0.0045 U
MW-95S	SSHS-MW-95S-04112024	T	4/11/2024	1801722791	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-95S	SSHS-MW-95S-09122023	T	9/12/2023	1801624601	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-95S	SSHS-MW-95S-11142023	T	11/14/2023	1801653531	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
MW-96	SSHS-MW-96-01172024	T	1/17/2024	1801682361	0.69	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.69	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-96	SSHS-MW-96-04092024	T	4/9/2024	1801721201	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-96	SSHS-MW-96-05022023	T	5/2/2023	1801559471	0.35	< 0.0051 U	< 0.0061 U	< 0.0055 U	< 0.0038 U	0.35	< 0.0049 U	< 0.0042 U	< 0.0076 U	< 0.0048 U
MW-96	SSHS-MW-96-09152023	T	9/15/2023	1801625601	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-96	SSHS-MW-96-11142023	T	11/14/2023	1801653531	0.52	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	0.52	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-97	SSHS-MW-97-01172024	T	1/17/2024	1801682361	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-97	SSHS-MW-97-04092024	T	4/9/2024	1801721201	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.0080 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-97	SSHS-MW-97-05022023	T	5/2/2023	1801559471	ND	< 0.0050 U	< 0.0060 U	< 0.0054 U	< 0.0037 U	< 0.0084 U	< 0.0048 U	< 0.0041 U	< 0.0074 U	< 0.0047 U
MW-97	SSHS-MW-97-09152023	T	9/15/2023	1801625601	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-97	SSHS-MW-97-11142023	T	11/14/2023	1801653531	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-98I	DUP-01	D	9/1/2022	1801438881	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-98I	DUP-01	T	9/1/2022	1801438881	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-98I	MW-98I	D	9/1/2022	1801438881	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-98I	MW-98I	T	9/1/2022	1801438881	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-98I	SSHS-MW-98I-04102024	T	4/10/2024	1801721871	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-98I	SSHS-MW-98I-09132023	T	9/13/2023	1801624611	ND	< 0.0049 U	< 0.0059 U	< 0.0054 U	< 0.0037 U	< 0.0083 U	< 0.0047 U	< 0.0040 U	< 0.0073 U	< 0.0047 U
MW-98S	MW-98S	D	9/1/2022	1801438881	ND	< 0.0047 UT	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 UT	< 0.0070 U	< 0.0045 U
MW-98S	MW-98S	T	9/1/2022	1801438881	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-98S	SSHS-MW-98S-04102024	T	4/10/2024	1801721871	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0077 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
MW-98S	SSHS-MW-98S-09132023	T	9/13/2023	1801624611	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0079 U	< 0.0045 U	< 0.0038 U	< 0.0070 U	< 0.0045 U
MW-99I	SSHS-MW-99I-04102024	T	4/10/2024	1801721871	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
MW-99I	SSHS-MW-99I-09132023	T	9/13/2023	1801624611	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0078 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
MW-99S	SSHS-MW-99S-04102024	T	4/10/2024	1801721871	ND	< 0.0052 U	< 0.0063 U	< 0.0057 U	< 0.0039 U	< 0.0088 U	< 0.0050 U	< 0.0043 U	< 0.0078 U	< 0.0050 U
MW-99S	SSHS-MW-99S-09132023	T	9/13/2023	1801624611	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-9I	MW-9I	D	7/14/2021	180-124487-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-9I	MW-9I	D	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-9I	MW-9I	T	7/14/2021	180-124487-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-9I	MW-9I	T	8/31/2021	180-126501-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
MW-9I	SSHS-MW-9I-04292024	T	4/29/2024	1801733271	ND	< 0.0045 U	< 0.0054 U	< 0.0050 U	< 0.0034 U	< 0.0076 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
MW-9S	MW-9	D	7/14/2021	180-124487-1	ND	< 0.0045	< 0.0054	< 0.0049	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0067	< 0.0043

TABLE 5-8
Groundwater Results - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Groundwater Results - PCBs					PCBs									
					Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.09									
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-9S	MW-9	T	2/20/2021	180-117476-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
MW-9S	MW-9	T	7/14/2021	180-124487-1	ND	< 0.0045	< 0.0054	< 0.005	< 0.0034	< 0.0028	< 0.0043	< 0.0037	< 0.0068	< 0.0043
MW-9S	SSHS-MW-9	T	3/21/2016	180-53281-1	ND	< 0.0035 U	< 0.0055 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0024 U	< 0.0023 U
MW-9S	SSHS-MW-9_F	D	3/21/2016	180-53281-1	ND	< 0.0035 U	< 0.0056 U	< 0.0057 U	< 0.0032 U	< 0.003 U	< 0.0042 U	< 0.0027 U	< 0.0025 U	< 0.0023 U
MW-9S	SSHS-MW-9S-04052024	T	4/5/2024	1801720021	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0082 U	< 0.0047 U	< 0.0040 U	< 0.0072 U	< 0.0046 U
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	T	8/4/2021	1801253661	ND	< 0.0046 U	< 0.0055 U	< 0.0050 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
RO3-WATER	SSHS-IRM5A2-RO3-WATER	T	9/22/2022	1801449681	21.75	< 0.20 U	< 0.24 U	< 0.22 U	< 0.15 U	15	5.8	0.95	< 0.30 U	< 0.19 U
SSHS-B2544	SSHS-B2544-GW	T	10/30/2018	180-83544-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0091 U	< 0.003 U	< 0.0095 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B2629	SSHS-B2629	T	4/25/2019	180-89520-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.009 U	< 0.003 U	< 0.0094 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-B2752	SSHS-B2752	T	4/25/2019	180-89520-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0089 U	< 0.0029 U	< 0.0092 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-B29-A	SSHS-B29-A-GW-18-22	T	8/13/2014	180-35776-2	0.049	< 0.0024 U	< 0.0024 U	< 0.0028 U	< 0.0018 U	0.049	< 0.0022 U	< 0.0013 U	< 0.002 U	< 0.0026 U
SSHS-B3200A	DUP-01	T	9/15/2019	180-95745-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0091 U	< 0.003 U	< 0.0095 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3200A	SSHS-B3200a	T	9/15/2019	180-95745-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0091 U	< 0.003 U	< 0.0095 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3203A	SSHS-3203a	T	9/13/2019	180-95715-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0091 U	< 0.003 U	< 0.0095 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3555	SSHS-RI-B3555 TEMP	D	1/16/2021	180-116110-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-B3555	SSHS-RI-B3555 TEMP	T	1/16/2021	180-116110-1	0.044	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.044	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3556	SSHS-RI-B3556-TEMP	D	1/14/2021	180-116000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3556	SSHS-RI-B3556-TEMP	T	1/14/2021	180-116000-1	ND	< 0.0048 U,*3	< 0.0057 U,*3	< 0.0052 U,*3	< 0.0036 U,*3	< 0.003 U,*3	< 0.0046 U,*3	< 0.0039 U,*3	< 0.0071 U,*3	< 0.0046 U,*3
SSHS-B3557	SSHS-RI-B3557 TEMP	D	1/13/2021	180-115925-2	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3557	SSHS-RI-B3557 TEMP	T	1/13/2021	180-115925-2	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3558	SSHS-RI-B3558-TEMP	D	1/15/2021	180-116071-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3558	SSHS-RI-B3558-TEMP	T	1/15/2021	180-116071-1	0.286	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	0.22	0.066	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-B3559	SSHS-RI-B3559 TEMP	D	1/16/2021	180-116200-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-B3559	SSHS-RI-B3559 TEMP	T	1/16/2021	180-116200-1	0.065	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.065	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3560	SSHS-RI-B3560-TEMP	D	1/15/2021	180-116071-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3560	SSHS-RI-B3560-TEMP	T	1/15/2021	180-116071-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3561	SSHS-RI-B3561-TEMP	D	1/15/2021	180-116071-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3561	SSHS-RI-B3561-TEMP	T	1/15/2021	180-116071-1	0.2	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.2	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3561	SSHS-RI-B3561-TEMP	D	1/15/2021	180-116071-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-B3561	SSHS-RI-B3561-TEMP	T	1/15/2021	180-116071-1	0.345	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.29	0.055	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3562	DUP-28	D	1/14/2021	180-116000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3562	DUP-28	T	1/14/2021	180-116000-1	0.188	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.15	0.038	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3562	SSHS-RI-B3562-TEMP	D	1/14/2021	180-116000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3562	SSHS-RI-B3562-TEMP	T	1/14/2021	180-116000-1	0.306	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	0.23	0.076	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-B3563	SSHS-RI-B3563-TEMP	D	1/14/2021	180-116000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3563	SSHS-RI-B3563-TEMP	T	1/14/2021	180-116000-1	2.05	< 0.0047 U,F1	< 0.0057 U	< 0.0052 U	< 0.0035 U	1.7	0.35	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-B3563I	SSHS-RI-B3563I TEMP	D	1/16/2021	180-116110-1	0.1	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.1	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3563I	SSHS-RI-B3563I TEMP	T	1/16/2021	180-116110-1	32.85	< 0.098 U	< 0.12 U	< 0.11 U	< 0.073 U	24	8.1	0.75	< 0.15 U	< 0.094 U
SSHS-B3564	SSHS-RI-B3564-TEMP	D	1/15/2021	180-116071-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-B3564	SSHS-RI-B3564-TEMP	T	1/15/2021	180-116071-1	2.04	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	1.8	0.24	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-B3565	SSHS-RI-B3565-TEMP	D	1/14/2021	180-116000-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-B3565	SSHS-RI-B3565-TEMP	T	1/14/2021	180-116000-1	0.78	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.6	0.18	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3566	SSHS-RI-B3566-TEMP	D	1/15/2021	180-116071-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3566	SSHS-RI-B3566-TEMP	T	1/15/2021	180-116071-1	0.221	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.16	0.061	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3571	SSHS-RI-B3571 TEMP	D	1/16/2021	180-116110-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B3571	SSHS-RI-B3571 TEMP	T	1/16/2021	180-116110-1	0.097	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.097	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-B510	SSHS-B510	T	9/20/2016	180-58901-1	0.13	< 0.0034 U	< 0.0092 U	< 0.0033 U	0.13	< 0.0069 U	< 0.005 U	< 0.0057 U	< 0.0067 U	< 0.0066 U
SSHS-B572A	SSHS-B572A	T	9/2/2016	180-58309-2	ND	< 0.0033 U	< 0.0088 U	< 0.0032 U	< 0.009 U	< 0.0066 U	< 0.0048 U	< 0.0055 U	< 0.0064 U	< 0.0063 U
SSHS-B99	SSHS-99-GW-17-21	T	8/13/2014	180-35776-2	0.16	< 0.0024 U	< 0.0024 U	< 0.0028 U	< 0.0018 U	0.16	< 0.0022 U	< 0.0013 U	< 0.002 U	< 0.0026 U
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	D	7/1/2021	180-123971-1	0.15	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	0.15	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	T	7/1/2021	180-123971-1	9.8	< 0.091 U	< 0.11 U	< 0.099 U	< 0.068 U	8.4	1.4	< 0.075 U	< 0.14 U	< 0.087 U
SSHS-RI-B3855I TEMP	DUP-GW-01	D	4/15/2021	180-120162-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3855I TEMP	DUP-GW-01	T	4/15/2021	180-120162-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3855I TEMP	SSHS-RI-B3855I TEMP	D	4/15/2021	180-120162-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
SSHS-RI-B3855I TEMP	SSHS-RI-B3855I TEMP	T	4/15/2021	180-120162-1	ND	< 0.0057 U	< 0.0069 U	< 0.0063 U	< 0.0043 U	< 0.0036 U	< 0.0055 U	< 0.0047 U	< 0.0086 U	< 0.0055 U
SSHS-RI-B3855S TEMP	SSHS-RI-B3855S TEMP	D	4/16/2021	180-120163-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3855S TEMP	SSHS-RI-B3855S TEMP	T	4/16/2021	180-120163-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3856I TEMP	SSHS-RI-B3856I TEMP	D	4/8/2021	180-119734-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3856I TEMP	SSHS-RI-B3856I TEMP	T	4/8/2021	180-119734-1	0.12	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.12	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3856S TEMP	SSHS-RI-B3856S TEMP	D	4/8/2021	180-119734-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3856S TEMP	SSHS-RI-B3856S TEMP	T	4/8/2021	180-119734-1	0.035	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.035	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	D	4/9/2021	180-119810-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	T	4/9/2021	180-119810-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3858I TEMP	SSHS-RI-B3858I TEMP	D	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3858I TEMP	SSHS-RI-B3858I TEMP	T	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3858S TEMP	SSHS-RI-B3858S TEMP	D	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3858S TEMP	SSHS-RI-B3858S TEMP	T	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3859I TEMP	SSHS-RI-B3859I TEMP	D	4/16/2021	180-120163-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3859I TEMP	SSHS-RI-B3859I TEMP	T	4/16/2021	180-120163-1	0.043	< 0.0049 U	< 0.0059 U	< 0.0054 U	< 0.0037 U	0.043	< 0.0047 U	< 0.004 U	< 0.0073 U	< 0.0047 U
SSHS-RI-B3859S TEMP	SSHS-RI-B3859S TEMP	D	4/16/2021	180-120163-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
SSHS-RI-B3859S TEMP	SSHS-RI-B3859S TEMP	T	4/16/2021	180-120163-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-RI-B3860I TEMP	DUP-GW-02	D	4/15/2021	180-120162-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3860I TEMP	DUP-GW-02	T	4/15/2021	180-120162-1	0.19	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.19	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	D	4/15/2021	180-120162-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	T	4/15/2021	180-120162-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3860S TEMP	SSHS-RI-B3860S TEMP	D	4/15/2021	180-120162-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
SSHS-RI-B3860S TEMP	SSHS-RI-B3860S TEMP	T	4/15/2021	180-120162-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3861I TEMP	DUP-GW-03	D	4/21/2021	180-120413-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
SSHS-RI-B3861I TEMP	DUP-GW-03	T	4/21/2021	180-120413-1	ND	< 0.0045 U	< 0.0054 U	< 0.0049 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0067 U	< 0.0043 U
SSHS-RI-B3861I TEMP	SSHS-RI-B3861I TEMP	D	4/21/2021	180-120413-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3861I TEMP	SSHS-RI-B3861I TEMP	T	4/21/2021	180-120413-1	ND	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-RI-B3861S TEMP	SSHS-RI-B3861S TEMP	D	4/21/2021	180-120413-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3861S TEMP	SSHS-RI-B3861S TEMP	T	4/21/2021	180-120413-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-RI-B3862 TEMP	SSHS-RI-B3862 TEMP	D	4/7/2021	180-119649-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3862 TEMP	SSHS-RI-B3862 TEMP	T	4/7/2021	180-119649-1	0.069	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.069	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3863 TEMP	SSHS-RI-B3863 TEMP	D	4/14/2021	180-120029-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3863 TEMP	SSHS-RI-B3863 TEMP	T	4/14/2021	180-120029-1	0.072	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.072	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	D	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	T	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3864S TEMP	SSHS-RI-B3864S TEMP	D	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3864S TEMP	SSHS-RI-B3864S TEMP	T	4/13/2021	180-119930-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	D	4/9/2021	180-119810-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	T	4/9/2021	180-119810-1	ND	< 0.0045 U,F1	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	D	4/9/2021	180-119810-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	T	4/9/2021	180-119810-1	0.079	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.079	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3866 TEMP	DUP-GW-04 P	D	4/8/2021	180-119734-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3866 TEMP	DUP-GW-04 P	T	4/8/2021	180-119734-1	0.03	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.03	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3866 TEMP	SSHS-RI-B3866 TEMP	D	4/8/2021	180-119734-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3866 TEMP	SSHS-RI-B3866 TEMP	T	4/8/2021	180-119734-1	0.023	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.023	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	D	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	T	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3868I TEMP	SSHS-RI-B3868I TEMP	D	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3868I TEMP	SSHS-RI-B3868I TEMP	T	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3868S TEMP	SSHS-RI-B3868S TEMP	D	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3868S TEMP	SSHS-RI-B3868S TEMP	T	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3869I TEMP	SSHS-RI-B3869I TEMP	D	4/5/2021	180-119511-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3869I TEMP	SSHS-RI-B3869I TEMP	T	4/5/2021	180-119511-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3869S TEMP	SSHS-RI-B3869S TEMP	D	4/6/2021	180-119589-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3869S TEMP	SSHS-RI-B3869S TEMP	T	4/6/2021	180-119589-1	0.077	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.077	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	D	4/7/2021	180-119649-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	T	4/7/2021	180-119649-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3875 TEMP	SSHS-RI-B3875 TEMP	D	4/5/2021	180-119511-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3875 TEMP	SSHS-RI-B3875 TEMP	T	4/5/2021	180-119511-1	0.078	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.078	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3876 TEMP	040621 10:00 SSHS-RI-B3876 TEMP	D	4/5/2021	180-119511-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3876 TEMP	040621 10:00 SSHS-RI-B3876 TEMP	T	4/5/2021	180-119511-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	D	4/14/2021	180-120029-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	T	4/14/2021	180-120029-1	0.057	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.057	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	D	4/14/2021	180-120029-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	T	4/14/2021	180-120029-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3878 TEMP	SSHS-RI-B3878 TEMP	D	4/7/2021	180-119649-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3878 TEMP	SSHS-RI-B3878 TEMP	T	4/7/2021	180-119649-1	0.12	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	0.12	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3879 TEMP	SSHS-RI-B3879 TEMP	D	4/7/2021	180-119649-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3879 TEMP	SSHS-RI-B3879 TEMP	T	4/7/2021	180-119649-1	94.53	< 0.23 U	< 0.27 U	< 0.25 U	< 0.17 U	79	15	0.53	< 0.34 U	< 0.22 U
SSHS-RI-B3881I TEMP	SSHS-RI-B3881I TEMP	D	4/18/2021	180-120259-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3881I TEMP	SSHS-RI-B3881I TEMP	T	4/18/2021	180-120259-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	D	5/14/2021	180-121703-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	T	5/14/2021	180-121703-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3883-TEMP	SSHS-RI-B3883-TEMP	D	5/20/2021	180-122000-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3883-TEMP	SSHS-RI-B3883-TEMP	T	5/20/2021	180-122000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3885-TEMP	SSHS-RI-B3885-TEMP	D	9/23/2021	180-127582-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3885-TEMP	SSHS-RI-B3885-TEMP	T	9/23/2021	180-127582-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3886-TEMP	DUP-GW-01	D	5/19/2021	180-121897-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3886-TEMP	DUP-GW-01	T	5/19/2021	180-121897-1	0.033	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	0.033	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	D	5/19/2021	180-121897-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	T	5/19/2021	180-121897-1	0.027	< 0.0048 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	0.027	< 0.0046 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-RI-B3890I-TEMP	DUP-GW-02	D	5/14/2021	180-121703-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3890I-TEMP	DUP-GW-02	T	5/14/2021	180-121703-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3890I-TEMP	SSHS-RI-B3890I-TEMP	D	5/14/2021	180-121703-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3890I-TEMP	SSHS-RI-B3890I-TEMP	T	5/14/2021	180-121703-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3890S-TEMP	SSHS-RI-B3890S-TEMP	D	5/18/2021	180-121850-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3890S-TEMP	SSHS-RI-B3890S-TEMP	T	5/18/2021	180-121850-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3893I-TEMP	SSHS-RI-B3893I-TEMP	D	5/14/2021	180-121703-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3893I-TEMP	SSHS-RI-B3893I-TEMP	T	5/14/2021	180-121703-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3893S-TEMP	SSHS-RI-B3893S-TEMP	D	5/18/2021	180-121850-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3893S-TEMP	SSHS-RI-B3893S-TEMP	T	5/18/2021	180-121850-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3894-TEMP	SSHS-RI-B3894-TEMP	D	5/13/2021	180-121702-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3894-TEMP	SSHS-RI-B3894-TEMP	T	5/13/2021	180-121702-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3898-TEMP	DUP-GW-03	D	5/19/2021	180-121897-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3898-TEMP	DUP-GW-03	T	5/19/2021	180-121897-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3898-TEMP	SSHS-RI-B3898-TEMP	D	5/19/2021	180-121897-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3898-TEMP	SSHS-RI-B3898-TEMP	T	5/19/2021	180-121897-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3903I-TEMP	SSHS-RI-B3903I-TEMP	D	5/20/2021	180-122000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3903I-TEMP	SSHS-RI-B3903I-TEMP	T	5/20/2021	180-122000-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3903S-TEMP	SSHS-RI-B3903S-TEMP	D	5/20/2021	180-122000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3903S-TEMP	SSHS-RI-B3903S-TEMP	T	5/20/2021	180-122000-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U

Groundwater Results - PCBs					PCBs									
					Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.09									
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
SSHS-RI-B3904I-TEMP	SSHS-RI-B3904I-TEMP	D	5/11/2021	180-121472-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3904I-TEMP	SSHS-RI-B3904I-TEMP	T	5/11/2021	180-121472-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3904S-TEMP	SSHS-RI-B3904S-TEMP	D	5/11/2021	180-121472-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3904S-TEMP	SSHS-RI-B3904S-TEMP	T	5/11/2021	180-121472-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	D	5/11/2021	180-121472-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	T	5/11/2021	180-121472-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	D	5/11/2021	180-121472-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	T	5/11/2021	180-121472-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3909I-TEMP	SSHS-RI-B3909I-TEMP	D	5/12/2021	180-121546-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B3909I-TEMP	SSHS-RI-B3909I-TEMP	T	5/12/2021	180-121546-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3909S-TEMP	SSHS-RI-B3909S-TEMP	D	5/12/2021	180-121546-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B3909S-TEMP	SSHS-RI-B3909S-TEMP	T	5/12/2021	180-121546-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	D	5/13/2021	180-121702-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	T	5/13/2021	180-121702-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	D	5/12/2021	180-121546-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	T	5/12/2021	180-121546-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
SSHS-RI-B3916I-TEMP	SSHS-RI-B3916I-TEMP	D	5/13/2021	180-121702-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3916I-TEMP	SSHS-RI-B3916I-TEMP	T	5/13/2021	180-121702-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B3916S-TEMP	SSHS-RI-B3916S-TEMP	D	5/18/2021	180-121850-1	ND	< 0.0048 U,F1,F2	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U,F1,F2	< 0.0071 U	< 0.0046 U
SSHS-RI-B3916S-TEMP	SSHS-RI-B3916S-TEMP	T	5/18/2021	180-121850-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B4007-TEMP	SSHS-RI-B4007-TEMP	D	5/21/2021	180-122084-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4007-TEMP	SSHS-RI-B4007-TEMP	T	5/21/2021	180-122084-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4008I-TEMP	SSHS-RI-B4008I-TEMP	D	9/23/2021	180-127581-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B4008I-TEMP	SSHS-RI-B4008I-TEMP	T	9/23/2021	180-127581-1	ND	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	D	7/23/2021	180-124918-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	T	7/23/2021	180-124918-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	D	7/26/2021	180-124974-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	T	7/26/2021	180-124974-1	0.045	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.045	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	D	7/28/2021	180-125087-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	T	7/28/2021	180-125087-1	0.036	< 0.0046 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	0.036	< 0.0044 U	< 0.0038 U	< 0.0069 U	< 0.0044 U
SSHS-RI-B4152I-TEMP	DUP-01	D	7/28/2021	180-125087-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B4152I-TEMP	DUP-01	T	7/28/2021	180-125087-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	D	7/29/2021	180-125127-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	T	7/29/2021	180-125127-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	D	7/28/2021	180-125087-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	T	7/28/2021	180-125087-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	D	7/27/2021	180-125052-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	T	7/27/2021	180-125052-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	D	7/27/2021	180-125052-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	T	7/27/2021	180-125052-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	D	7/26/2021	180-124974-1	ND	< 0.0045 U	< 0.0054 U	< 0.005 U	< 0.0034 U	< 0.0028 U	< 0.0043 U	< 0.0037 U	< 0.0068 U	< 0.0043 U
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	T	7/26/2021	180-124974-1	ND	< 0.0046 U	< 0.0055 U	< 0.005 U	< 0.0034 U	< 0.0029 U	< 0.0044 U	< 0.0038 U	< 0.0068 U	< 0.0044 U
SSHS-RI-MW-55	SSHS-RI-MW-55	D	5/10/2021	180-121427-1	ND	< 0.0048 U	< 0.0057 U	< 0.0052 U	< 0.0036 U	< 0.003 U	< 0.0046 U	< 0.0039 U	< 0.0071 U	< 0.0046 U
SSHS-RI-MW-55	SSHS-RI-MW-55	T	5/10/2021	180-121427-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-MW-56	SSHS-RI-MW-56	D	5/12/2021	180-121547-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U
SSHS-RI-MW-56	SSHS-RI-MW-56	T	5/12/2021	180-121547-1	ND	< 0.0047 U	< 0.0056 U	< 0.0051 U	< 0.0035 U	< 0.0029 U	< 0.0045 U	< 0.0038 U	< 0.007 U	< 0.0045 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	D	7/29/2021	180-125127-1	ND	< 0.0049 U	< 0.0058 U	< 0.0053 U	< 0.0036 U	< 0.0031 U	< 0.0047 U	< 0.004 U	< 0.0072 U	< 0.0046 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	T	7/29/2021	180-125127-1	ND	< 0.0047 U	< 0.0057 U	< 0.0052 U	< 0.0035 U	< 0.003 U	< 0.0045 U	< 0.0039 U	< 0.007 U	< 0.0045 U

Notes

PCBs - Polychlorinated Biphenyls
ug/l = micrograms per liter
^+ = Continuing Calibration Verification (CCV) is outside acceptance limits, high biased
*+ = LCS and/or LCSD is outside acceptance limits, high biased
*1 = LCS/LCSD RPD exceeds control limits
*3 = ISTD response or retention time outside acceptable limits
B = Compound detected in method blank
E = Exceeds instrument calibration range
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab method used: 8082A/ SW8082A - PCBs
Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

DRAFT

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					2000	3	25	1000	3	5		50		200	300[1]	25	35000	300[1]
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report														
MW-1	MW1	T	5/11/2000		-	-	24.3	452	-	-	-	44.2	-	137	-	72.1	-	-
MW-1	MW1	T	7/27/2000		-	-	-	96.9	-	-	-	-	-	-	-	-	-	-
MW-1	MW-1	T	2/17/2021	180-117387-1	6100	< 3.4 U	15	310	< 0.33 U	0.74 J	210000	15	6.3 J	190	21000	36	35000	2600
MW-1	MW-1	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	4.6 J	290	< 0.33 U	< 0.28 U	170000	< 1.9 U	0.72 J	< 9.1 U	5300	< 2.9 U	24000	1400
MW-1	MW-1	T	7/14/2021	180-124487-1	180 J	< 3.4 U	5 J	300	< 0.33 U	< 0.28 U	180000	< 1.9 U	0.74 J	< 9.1 U	5900	3.4 J	24000	1500
MW-1	SSHS-MW-1-04112024	T	4/11/2024	1801722801	130 J	< 6.2 U	< 8.3 U	250	< 1.5 U	< 0.30 U	160000	< 3.1 U	< 3.4 U	< 2.2 U	1400	13	22000	850
MW-10	MW-10	T	2/24/2021	180-117542-1	590	< 3.4 U	< 4.1 U	250	< 0.33 U	0.89 J	120000	< 1.9 U	0.66 J	< 9.1 U	4300	< 2.9 U	16000	1500
MW-10	MW-10	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	5.6 J	240	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	1500	< 2.9 U	13000	1100
MW-10	MW-10	T	7/13/2021	180-124378-1	240	< 3.4 U	< 4.1 UJ	240	< 0.33 U	< 0.28 U	100000	< 1.9 U	0.6 J	< 9.1 U	1800	3.3 J	13000	1100
MW-100I	SSHS-MW-100I-04082024	T	4/8/2024	1801720411	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	90000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	11	15000	< 2.4 U
MW-100I	SSHS-MW-100I-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	120 J	< 0.60 UJ	< 0.45 U	81000	0.98 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	7.3 J
MW-100S	SSHS-DUP-02-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 UJ	< 0.45 U	100000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	190
MW-100S	SSHS-MW-100S-04082024	T	4/8/2024	1801720411	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	97000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	11	14000	14 J
MW-100S	SSHS-MW-100S-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 UJ	< 0.45 U	100000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	200
MW-101I	SSHS-MW-101I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	97000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-101I	SSHS-MW-101I-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 U	87000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	< 2.6 U
MW-101S	SSHS-MW-101S-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	98000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-101S	SSHS-MW-101S-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	120 J	< 0.60 U	< 0.45 U	86000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	< 2.6 U
MW-102I	SSHS-MW-102I-04222024	T	4/22/2024	1801730541	< 110 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	91000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	14000	32
MW-102I	SSHS-MW-102I-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	140 J	< 0.60 UJ	< 0.45 U	82000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	13000	78
MW-102S	SSHS-MW-102S-04222024	T	4/22/2024	1801730541	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	94000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	39
MW-102S	SSHS-MW-102S-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 UJ	< 0.45 U	83000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	37
MW-103I	SSHS-MW-103I-04162024	T	4/16/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	89000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	14000	42
MW-103I	SSHS-MW-103I-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 U	< 0.45 U	90000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	52
MW-103S	SSHS-MW-103S-04162024	T	4/16/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	84 J	< 1.5 U	< 0.30 U	75000	< 3.1 U	< 3.4 U	< 2.2 U	76 J	< 4.4 U	11000	150
MW-103S	SSHS-MW-103S-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	81 J	< 0.60 U	< 0.45 U	74000	0.90 J	< 0.75 U	< 3.5 U	100 J	< 2.8 U	10000	120
MW-104I	SSHS-DUP-03-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	98 J	< 0.60 U	< 0.45 U	83000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	4.5 J
MW-104I	SSHS-MW-104I-04162024	T	4/16/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	82000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	13000	37
MW-104I	SSHS-MW-104I-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	95 J	< 0.60 U	< 0.45 U	78000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	13000	17 J
MW-104S	SSHS-MW-104S-04162024	T	4/16/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	16000	82
MW-104S	SSHS-MW-104S-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 U	< 0.45 U	110000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	16000	90
MW-105I	SSHS-MW-105I-04172024	T	4/17/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	85000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	13000	2.9 J
MW-105I	SSHS-MW-105I-09152023	T	9/15/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	96 J	< 0.60 UJ	< 0.45 U	76000	0.87 J	< 0.75 U	< 3.5 U	260	< 2.8 U	12000	17
MW-105S	SSHS-MW-105S-04252024	T	4/25/2024	1801731401	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	89000	< 3.1 U	< 3.4 U	< 2.2 U	110	< 4.4 U	14000	8.1 J
MW-105S	SSHS-MW-105S-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	100 J	< 0.60 U	< 0.45 U	85000	1.1 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	15000	24
MW-106	SSHS-MW-106-01182024	T	1/18/2024	1801682891	< 110 U	< 6.2 UT	< 8.3 U	120 J	< 1.5 U	< 0.30 U	94000	< 3.1 U	< 3.4 U	< 2.2 UT	< 72 U	< 4.4 U	15000	< 2.4 U
MW-106	SSHS-MW-106-04102024	T	4/10/2024	1801721851	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	86000	< 3.1 U	< 3.4 U	< 2.2 U	110	9.4 J	13000	4.5 J
MW-106	SSHS-MW-106-05022023	T	5/2/2023	1801559471	50 J	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	110000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	18000	10 J
MW-106	SSHS-MW-106-09142023	T	9/14/2023	1801625601	< 47 U	< 7.5 U	4.7 J	130 J	< 0.60 U	< 0.45 U	84000	1.2 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	13000	< 2.6 U
MW-106	SSHS-MW-106-11142023	T	11/14/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	96000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	16000	< 2.4 U
MW-11D	MW-11D	T	2/23/2021	180-117459-1	270	< 3.4 U	7.9 J	120 J	< 0.33 U	< 0.28 U	46000	< 1.9 U	< 0.55 U	< 9.1 U	510	< 2.9 U	6900	16
MW-11D	MW-11D	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	7.6 J	110 J	< 0.33 U	< 0.28 U	45000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	6800	2.8 J
MW-11D	MW-11D	T	4/30/2021	180-120955-1	240	< 3.4 U	7.5 J	120 J	< 0.33 U	< 0.28 U	47000	< 1.9 U	< 0.55 U	< 9.1 U	420	< 2.9 U	7200	18
MW-11D	MW-11D-GW	T	11/1/2018	180-83607-1	550	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	80000	0.78 J	1.9 J	< 2.2 U	820	< 2.9 U	15000	190
MW-11S	MW-11S	T	2/23/2021	180-117459-1	160 J	< 3.4 U	< 4.1 U	300	< 0.33 U	< 0.28 U	170000	< 1.9 U	< 0.55 U	< 9.1 U	11000	< 2.9 U	17000	1700
MW-11S	MW-11S	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	290	< 0.33 U	< 0.28 U	160000	< 1.9 U	< 0.55 U	< 9.1 U	9600	2.9 J	17000	1800
MW-11S	MW-11S	T	4/30/2021	180-120955-1	400	< 3.4 U	< 4.1 U	270	< 0.33 U	< 0.28 U	160000	< 1.9 U	< 0.55 U	< 9.1 U	10000	3.7 J	15000	1700
MW-11S	DUP-01	D	7/25/2019	180-93333-1	< 36 U	< 3.4 U	< 4.1 UJ	320	< 0.33 U	< 0.28 U	140000	< 0.78 U	< 0.55 U	< 2.2 U	1800 J	< 2.9 U	16000	1400
MW-11S	DUP-01	T	7/25/2019	180-93333-1	< 36 U	< 3.4 U	< 4.1 UJ	320	< 0.33 UJ	< 0.28 UJ	140000	< 0.78 U	< 0.55 UJ	< 2.2 U	1900 J	< 2.9 U	17000	1400
MW-11S	MW-11S	D	7/25/2019	180-93333-1	< 36 U	< 3.4 U	5.4 J	290	< 0.33 U	< 0.28 U	140000	< 0.78 U	< 0.55 U	< 2.2 U	2900 J	< 2.9 U	16000	1300
MW-11S	MW-11S	T	7/25/2019	180-93333-1	< 36 U	< 3.4 U	6.2 J	300	0.44 J	0.46 J	140000	< 0.78 U	0.85 J	< 2.2 U	2900 J	< 2.9 U	16000	1300
MW-11S	FD-1	T	11/1/2018	180-83607-1	< 36 U	< 3.4 U	< 4.1 U	290	< 0.33 U	< 0.28 U	130000	< 0.78 U	< 0.55 U	< 2.2 U	4100	< 2.9 U	15000	1700
MW-11S	MW-11S-GW	T	11/1/2018	180-83607-1	< 36 U	< 3.4 U	< 4.1 U	280	< 0.33 U	< 0.28 U	130000	< 0.78 U	< 0.55 U	< 2.2 U	4100	< 2.9 U	14000	1700
MW-12	MW-12	T	5/17/2000		-	-	11	209	-	-	-	12.9	-	33.5	-	-	-	-
MW-12	MW12	T	9/20/2000		-	-	4 B	563	-	0.42 B	-	1.3 B	-	-	-	-	-	-
MW-12	MW-12	D	2/21/2021	180-117476-1	< 53 U	< 3.4 U	8.5 J	200	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	220	< 2.9 U	16000	360
MW-12	MW-12	T	2/21/2021	180-117476-1	4200	< 3.4 U	5.4 J	250	0.52 J	0.53 J	250000	4.1 J	3.6 J	23 J	7000	16	31000	1300
MW-12	MW-12	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	200	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	190	< 2.9 U	18000	280
MW-12	MW-12	T	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	200	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	560	< 2.9 U	17000	290
MW-13	DUP-02	T	2/21/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	46 J	< 0.33 U	0.36 J	430000	< 1.9 U	< 0.55 U	< 9.1 U	3300	< 2.9 U	19000	790
MW-13	MW-13	T	2/21/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	44 J	< 0.33 U	< 0.28 UJ	410000	< 1.9 U	< 0.55 U	< 9.1 U	3300	< 2.9 U	18000	760
MW-13	MW-13	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	59 J	< 0.33 U	0.28 J	270000	< 1.9 U	< 0.55 U	< 9.1 U	1000	< 2.9 U	17000	420
MW-13	MW-13	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	52 J	< 0.33 U	< 0.28 UJ	250000	< 1.9 U	< 0.55 U	< 9.1 U	1300	< 2.9 U	16000	430
MW-17	MW17	T	5/17/2000		-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-17	MW17	T	9/20/2000		-	-	3.8 B	127 B	-	-	-	1.4 B	-	-	-	-	-	-
MW-2	MW-2	T	2/17/2021	180-117387-1	190 J	< 3.4 U	< 4.1 U	250	< 0.33 U	< 0.28 U	150000	< 1.9 U	1 J	< 9.1 U	2500	< 2.9 U	27000	1100
MW-2	MW-2	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	270	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 U	< 9.1 U	3800	< 2.9 U	24000	850
MW-2	MW-2	T	7/14/2021	180-124487-1	< 53 U	< 3.4 U	5.3 J	270	< 0.33 U	< 0.28 U	150000	< 1.9 U	0.85 J	< 9.1 U	3900	< 2.9 U	24000	860
MW-20	MW20	T	5/17/2000		-	-	24	461	-	-	-	45.5	-	117	-	183	-	-
MW-20	MW20	T	9/20/2000		-	-	-	153 B	-	-	-	2.9 B	-	-	-	-	-	-
MW-20	MW-20	T	2/23/2021	180-117459-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 U	< 9.1 U	300	< 2.9 U	15000	< 2.7 U
MW-20	MW-20	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	140 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	< 2.7 U
MW-20	MW-20	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	140 J	< 0.33 U	< 0.28 U	98000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	< 2.7 U
MW-22	MW-22	T	2/23/2021	180-117459-1	< 53 U	< 3.4 U	< 4.1 U	210	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	980	< 2.9 U	17000	550
MW-22	MW-22	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	230	< 0.33 U	< 0.28 U	130000	< 1.9 U	< 0.55 U	< 9.1 U	1100	< 2.9 U	18000	550
MW-22	MW-22	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	230	< 0.33 U	< 0.28 U	130000	< 1.9 U	< 0.55 U	< 9.1 U	1100	< 2.9 U	18000	560
MW-26	MW-26	T	2/17/2021	180-117387-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	99000	< 1.9 U	0.91 J	13 J	1200	< 2.9 U	15000	240
MW-26	MW-26	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	260
MW-26	MW-26	T	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 U	< 9.1 U	110	< 2.9 U	15000	250
MW-3	MW-3	T	2/17/2021	180-117387-1	< 53 U	< 3.4 U	< 4.1 U	260	< 0.33 U	< 0.28 U	190000	< 1.9 U	0.83 J	< 9.1 U	3400	< 2.9 U	28000	1700
MW-3	MW-3	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	250	< 0.33 U	< 0.28 U	150000	< 1.9 U	0.56 J	< 9.1 U	2300	< 2.9 U	21000	1000
MW-3	MW-3	T	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	270	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 UJ	< 9.1 UJ	2400	< 2.9 U	21000	1100
MW-3	DUP-4	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	260	< 0.33 U	< 0.28 U	150000	< 1.9 U	0.64 J	< 9.1 U	2300	< 2.9 U	21000	1100
MW-3	DUP-4	T	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	260	< 0.33 U	< 0.28 U	150000	< 1.9 U	0.59 J	33 J	2500	< 2.9 U	20000	1100
MW-30	MW-30	T	2/19/2021	180-117476-1	600	< 3.4 U	12	190 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	2.6 J	10 J	1200	< 2.9 U	9400	260
MW-30	MW-30	D	7/16/2021	180-124628-1	< 53 U	< 3.4 U	9.8 J	110 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	1 J	< 9.1 U	630	< 2.9 U	17000	550
MW-30	MW-30	T	7/16/2021	180-124628-1	2400	< 3.4 U	15	160 J	< 0.33 U	< 0.28 U	170000	4.7 J	4.1 J	30	8000	19	28000	920
MW-30	MW-30	D	7/26/2019	180-93333-1	< 36 U	< 3.4 U	4.6 J	< 1.1 U	< 0.33 U	< 0.28 U	85000	< 0.78 U	0.95 J	< 2.2 U	370	< 2.9 U	10000	700
MW-30	MW-30	T	7/26/2019	180-93333-1	7900	< 3.4 U	12	< 1.1 U	< 0.33 U	0.3 J	97000	11	6.6 J	70	18000	42	15000	970
MW-30	SSHS-MW-30-04302024	T	4/30/2024	1801733261	9700	< 6.2 UT	19	300	< 1.5 U	1.4 J	84000	34	10 J	89	37000 B	39	18000	3000
MW-32	MW-32	T	2/22/2021	180-117425-1	< 53 U	< 3.4 U	< 4.1 U	220	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 U	< 9.1 U	660	< 2.9 U	17000	1300
MW-32	MW-32	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	4.8 J	200	< 0.33 U	< 0.28 U	110000	< 1.9 U	0.62 J	< 9.1 U	710	3.1 J	13000	950
MW-32	MW-32	T	7/13/2021	180-124378-1	110 J	< 3.4 U	7.9 J	200	< 0.33 U	< 0.28 U	110000	< 1.9 U	0.59 J	< 9.1 U	740	3.1 J	13000	900
MW-33	MW-33	T	2/19/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	310	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	3000	< 2.9 U	15000	1500
MW-33	MW-33	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	230	< 0.33 U	< 0.28 U	91000	< 1.9 U	< 0.55 U	< 9.1 U	1700	3.8 J	12000	990
MW-33	MW-33	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	230	< 0.33 U	< 0.28 U	90000	< 1.9 U	< 0.55 U	< 9.1 U	1700	< 2.9 UJ	12000	980
MW-34	MW-34	T	2/24/2021	180-117542-1	1700	< 3.4 U	< 4.1 U	320	< 0.33 U	< 0.28 U	160000	3.4 J	1.8 J	< 9.1 U	6400	9.8 J	23000	1700
MW-34	MW-34	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	220	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	1000	< 2.9 U	13000	1100
MW-34	MW-34	T	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	230	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	1100	< 2.9 U	14000	1100
MW-36	MW-36	T	3/23/2021	180-118872-1	1100	< 3.4 U	41	250	0.33 J	< 0.28 U	75000	2.9 J	6.7 J	170	5200	31	9400	1000
MW-36	MW-36	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	7.5 J	180 J	< 0.33 U	< 0.28 U	90000	< 1.9 U	7.1 J	< 9.1 U	2000	< 2.9 U	10000	1100
MW-36	MW-36	T	4/30/2021	180-120955-1	110 J	< 3.4 U	8.5 J	180 J	< 0.33 U	< 0.28 U	91000	< 1.9 U	7.3 J	11 J	2300	5 J	11000	1200
MW-36	SSHS-MW36	T	8/22/2018	180-81174-1	< 36 U	< 3.4 U	7.6 J	170 J	< 0.33 U	< 0.28 U	120000	< 0.78 U	1.9 J	2.7 J	8300	< 2.9 U	15000	3700
MW-38	MW-38	T	3/24/2021	180-119009-1	< 53 U	< 3.4 U	< 4.1 U	280	< 0.33 U	< 0.28 U	140000	< 1.9 U	0.83 J	< 9.1 U	1700	2.9 J	20000	1400
MW-38	DUP-1	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	240	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 U	< 9.1 U	650	< 2.9 U	22000	740
MW-38	DUP-1	T	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	240	< 0.33 U	< 0.28 U	150000	< 1.9 U	0.74 J	< 9.1 U	540	3.2 J	21000	720
MW-38	MW-38	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	240	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 U	< 9.1 U	570	< 2.9 U	22000	740
MW-38	MW-38	T	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	240	< 0.33 U	< 0.28 U	150000	< 1.9 U	0.7 J	< 9.1 U	570	< 2.9 UJ	21000	730
MW-38	PS-FD-1	T	8/24/2018	180-81247-1	< 36 U	< 3.4 U	< 4.1 U	300	< 0.33 U	< 0.28 U	160000	< 0.78 U	0.83 J	2.5 J	2300	< 2.9 U	24000	1700
MW-38	SSHS-MW-38	T	8/23/2018	180-81247-1	< 36 U	< 3.4 U	< 4.1 U	320	< 0.33 U	< 0.28 U	160000	< 0.78 U	0.81 J	2.6 J	2500	< 2.9 U	24000	1700
MW-39	SSHS-MW-39	T	8/23/2018	180-81247-1	< 36 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	140000	< 0.78 U	< 0.55 U	< 2.2 U	620	< 2.9 U	24000	110
MW-4	MW4	T	9/20/2000		-	-	-	145 B	-	1.2 B	-	6.8 B	-	15.4 B	-	5.1	-	-
MW-40	MW-40	T	2/23/2021	180-117459-1	510	< 3.4 U	5.4 J	230	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	4000	3.5 J	14000	660
MW-40	MW-40	D	5/23/2019	180-90525-1	< 36 U	< 3.4 U	4.4 J	280	< 0.33 U	0.29 J	110000	< 0.78 U	< 0.55 U	< 2.2 U	4200	< 2.9 U	16000	900
MW-40	MW-40	T	5/23/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	300	< 0.33 U	< 0.28 U	110000	< 0.78 U	< 0.55 U	< 2.2 U	4500	< 2.9 U	17000	930
MW-41	DUP-03	T	2/20/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	160000	< 1.9 U	< 0.55 U	< 9.1 U	610	< 2.9 U	13000	650
MW-41	MW-41	T	2/20/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 U	< 9.1 U	540	< 2.9 U	12000	620
MW-41	MW-41	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	140000	< 1.9 U	< 0.55 U	< 9.1 U	730 J	< 2.9 U	13000	630
MW-41	MW-41	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	150000	< 1.9 U	< 0.55 U	< 9.1 U	510 J	3.2 J	14000	630
MW-43	MW-43	T	2/16/2021	180-117390-1	< 53 U	< 3.4 U	< 4.1 U	470	< 0.33 U	0.28 J	160000	< 1.9 U	1.4 J	< 9.1 U	< 89 U	< 2.9 U	15000	15
MW-43	MW-43	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	3.3 J	15000	< 2.7 U
MW-43	MW-43	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	99000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	3.5 J	15000	100
MW-44	SSHS-MW-44	T	8/23/2018	180-81247-1	< 36 U	< 3.4 U	5.5 J	370	< 0.33 U	< 0.28 U	140000	< 0.78 U	< 0.55 U	< 2.2 U	5100	< 2.9 U	20000	1400

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Thallium (Method 6010)	Thallium (Method 6020)	Vanadium	Zinc
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.7	100		10	50		0.5[2]	0.5[2]		2000
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-1	MW1	T	5/11/2000		-	67.3	-	-	-	-	-	-	61.7	420
MW-1	MW1	T	7/27/2000		-	-	-	-	-	-	-	-	-	17.3
MW-1	MW-1	T	2/17/2021	180-117387-1	< 0.13 U	19 J	5800	3.8 J	< 0.85 U	250000	< 3.3 U	-	11 J	130
MW-1	MW-1	D	7/14/2021	180-124487-1	< 0.13 U	2.1 J	3200 J	< 3.6 U	< 0.85 U	230000	< 3.3 U	-	3.7 J	< 6 U
MW-1	MW-1	T	7/14/2021	180-124487-1	< 0.13 U	2.9 J	3300 J	< 3.6 U	< 0.85 U	230000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-1	SSHS-MW-1-04112024	T	4/11/2024	1801722801	< 0.13 U	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	230000	3.0 J	-	< 5.3 U	< 42 U
MW-10	MW-10	T	2/24/2021	180-117542-1	< 0.13 U	2 J	5700	< 3.6 U	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	7 J
MW-10	MW-10	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	5100	4 J	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-10	MW-10	T	7/13/2021	180-124378-1	< 0.13 U	2.5 J	5100	< 3.6 UJ	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-100I	SSHS-MW-100I-04082024	T	4/8/2024	1801720411	< 0.13 U	< 3.5 U	3500 J	< 3.7 UT	< 0.91 U	74000	< 3.0 U	-	< 5.3 U	< 42 U
MW-100I	SSHS-MW-100I-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3800 J	< 6.0 U	< 0.62 U	77000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-100S	SSHS-DUP-02-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3900 J	< 6.0 U	< 0.62 U	54000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-100S	SSHS-MW-100S-04082024	T	4/8/2024	1801720411	< 0.13 U	< 3.5 U	3500 J	< 3.7 UT	< 0.91 U	72000	< 3.0 U	-	< 5.3 U	< 42 U
MW-100S	SSHS-MW-100S-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	4100 J	< 6.0 U	< 0.62 U	56000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-101I	SSHS-MW-101I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3600 J	< 3.7 U	< 0.91 U	92000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-101I	SSHS-MW-101I-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	87000	3.5 J	-	< 5.6 U	< 23 U
MW-101S	SSHS-MW-101S-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3700 J	< 3.7 U	< 0.91 U	94000	3.9 BJ	< 0.47 U	< 5.3 U	< 42 U
MW-101S	SSHS-MW-101S-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	87000	4.3 J	-	< 5.6 U	< 23 U
MW-102I	SSHS-MW-102I-04222024	T	4/22/2024	1801730541	< 0.13 U	< 3.5 U	3900 J	< 3.7 U	< 0.91 U	79000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-102I	SSHS-MW-102I-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3800 J	< 6.0 U	< 0.62 U	78000	3.1 J	-	< 5.6 U	< 23 U
MW-102S	SSHS-MW-102S-04222024	T	4/22/2024	1801730541	< 0.13 U	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	79000	< 3.0 U	-	< 5.3 U	< 42 U
MW-102S	SSHS-MW-102S-09142023	T	9/14/2023	1801625611	< 0.13 U	2.5 J	3700 J	< 6.0 U	< 0.62 U	77000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-103I	SSHS-MW-103I-04162024	T	4/16/2024	1801726651	< 0.13 U	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	82000	< 3.0 U	-	< 5.3 U	< 42 U
MW-103I	SSHS-MW-103I-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	82000	< 2.7 U	-	< 5.6 U	< 23 U
MW-103S	SSHS-MW-103S-04162024	T	4/16/2024	1801726651	< 0.13 U	< 3.5 U	2800 J	< 3.7 U	< 0.91 U	59000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-103S	SSHS-MW-103S-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	6500 B	< 6.0 U	< 0.62 U	57000	3.4 J	-	8.8 J	< 23 U
MW-104I	SSHS-DUP-03-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	76000	4.3 J	-	< 5.6 U	< 23 U
MW-104I	SSHS-MW-104I-04162024	T	4/16/2024	1801726651	< 0.13 U	< 3.5 U	3000 J	< 3.7 U	< 0.91 U	74000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-104I	SSHS-MW-104I-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	76000	4.2 J	-	< 5.6 U	< 23 U
MW-104S	SSHS-MW-104S-04162024	T	4/16/2024	1801726651	< 0.13 U	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	87000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-104S	SSHS-MW-104S-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	93000	4.5 J	-	< 5.6 U	< 23 U
MW-105I	SSHS-MW-105I-04172024	T	4/17/2024	1801726651	< 0.13 U	< 3.5 U	3100 J	< 3.7 U	< 0.91 U	86000	< 3.0 U	-	< 5.3 U	< 42 U
MW-105I	SSHS-MW-105I-09152023	T	9/15/2023	1801625611	< 0.13 U	< 2.2 U	3200 J	< 6.0 U	< 0.62 U	82000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-105S	SSHS-MW-105S-04252024	T	4/25/2024	1801731401	< 0.13 U	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	96000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-105S	SSHS-MW-105S-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	93000	4.3 J	-	< 5.6 U	< 23 U
MW-106	SSHS-MW-106-01182024	T	1/18/2024	1801682891	< 0.13 U	< 3.5 U	3100 J	< 3.7 UT	< 0.91 U	64000	< 3.0 UT	-	< 5.3 U	< 42 U
MW-106	SSHS-MW-106-04102024	T	4/10/2024	1801721851	< 0.13 U	< 3.5 U	3000 J	< 3.7 U	< 0.91 U	60000	< 3.0 U	-	< 5.3 U	< 42 U
MW-106	SSHS-MW-106-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2900 J	< 3.7 U	< 0.91 U	77000	< 3.0 U	-	< 5.3 U	22 B
MW-106	SSHS-MW-106-09142023	T	9/14/2023	1801625601	< 0.13 U	< 2.2 U	3600 J	< 6.0 U	< 0.62 U	59000	< 2.7 U	-	< 5.6 U	< 23 U
MW-106	SSHS-MW-106-11142023	T	11/14/2023	1801653531	< 0.13 U	< 3.5 U	3600 J	< 3.7 U	< 0.91 U	73000	< 3.0 U	-	< 5.3 U	< 42 U
MW-11D	MW-11D	T	2/23/2021	180-117459-1	< 0.13 U	< 1.5 U	5400	3.6 J	< 0.85 U	38000	< 3.3 U	-	< 3.7 U	11 J
MW-11D	MW-11D	D	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	5100	< 3.6 U	< 0.85 U	37000	< 3.3 U	-	< 3.7 U	< 6 U
MW-11D	MW-11D	T	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	5400	< 3.6 U	< 0.85 U	38000	< 3.3 U	-	< 3.7 U	7.2 J
MW-11D	MW-11D-GW	T	11/1/2018	180-83607-1	< 0.065 U	< 1.5 U	2600 J	< 3.6 U	< 0.85 U	48000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-11S	MW-11S	T	2/23/2021	180-117459-1	< 0.13 U	1.5 J	8100	4.8 J	< 0.85 U	23000	< 3.3 U	-	< 3.7 U	< 6 U
MW-11S	MW-11S	D	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	7800	< 3.6 U	< 0.85 U	31000	< 3.3 U	-	< 3.7 U	< 6 U
MW-11S	MW-11S	T	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	7500	< 3.6 U	< 0.85 U	25000	< 3.3 U	-	< 3.7 U	6.3 J
MW-11S	DUP-01	D	7/25/2019	180-93333-1	< 0.1 U	< 1.5 U	8800	< 3.6 U	< 0.85 U	41000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-11S	DUP-01	T	7/25/2019	180-93333-1	< 0.1 U	< 1.5 UJ	8700	< 3.6 U	< 0.85 U	41000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-11S	MW-11S	D	7/25/2019	180-93333-1	< 0.1 U	< 1.5 U	8000	< 3.6 U	< 0.85 U	40000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-11S	MW-11S	T	7/25/2019	180-93333-1	< 0.1 U	2 J	8100	< 3.6 U	< 0.85 U	42000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-11S	FD-1	T	11/1/2018	180-83607-1	< 0.065 U	< 1.5 U	9100	< 3.6 U	< 0.85 U	47000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-11S	MW-11S-GW	T	11/1/2018	180-83607-1	< 0.065 U	< 1.5 U	9000	< 3.6 U	< 0.85 U	46000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-12	MW-12	T	5/17/2000		-	-	-	-	-	-	-	-	-	96.2
MW-12	MW12	T	9/20/2000		-	5.5 B	-	-	-	-	-	-	2.6 B	11.8 B
MW-12	MW-12	D	2/21/2021	180-117476-1	< 0.13 U	< 1.5 U	3100 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-12	MW-12	T	2/21/2021	180-117476-1	< 0.13 U	16 J	3400 J	5.3 J	< 0.85 U	78000	< 3.3 U	-	4.5 J	110
MW-12	MW-12	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	65000	< 3.3 U	-	< 3.7 U	< 6 U
MW-12	MW-12	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	64000	< 3.3 U	-	< 3.7 U	< 6 U
MW-13	DUP-02	T	2/21/2021	180-117476-1	< 0.13 U	2.4 J	4400 J	6.7 J	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-13	MW-13	T	2/21/2021	180-117476-1	< 0.13 U	2.3 J	4300 J	4.3 J	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-13	MW-13	D	7/15/2021	180-124580-1	< 0.13 U	5.6 J	3600 J	< 3.6 U	< 0.85 U	74000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-13	MW-13	T	7/15/2021	180-124580-1	< 0.13 U	5.5 J	3300 J	4.3 J	< 0.85 U	70000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-17	MW17	T	5/17/2000		-	-	-	-	-	-	-	-	-	46.4
MW-17	MW17	T	9/20/2000		-	-	-	-	-	-	-	-	-	5 B
MW-2	MW-2	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	200000	< 3.3 U	-	< 3.7 U	< 6 U
MW-2	MW-2	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	2100 J	< 3.6 U	< 0.85 U	180000	< 3.3 U	-	< 3.7 U	< 6 U
MW-2	MW-2	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	2100 J	< 3.6 U	< 0.85 U	180000	< 3.3 U	-	< 3.7 U	7.3 J
MW-20	MW20	T	5/17/2000		0.25	69.2	-	5.7	-	-	-	-	-	414
MW-20	MW20	T	9/20/2000		-	-	-	-	-	-	-	-	2.5 B	22.8
MW-20	MW-20	T	2/23/2021	180-117459-1	< 0.13 U	< 1.5 U	4100 J	< 3.6 U	< 0.85 U	83000	< 3.3 U	-	< 3.7 U	< 6 U
MW-20	MW-20	D	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	82000	5.3 J	-	< 3.7 U	< 6 U
MW-20	MW-20	T	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	82000	< 3.3 UJ	-	< 50 U	< 6 U
MW-22	MW-22	T	2/23/2021	180-117459-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	48000	< 3.3 U	-	< 3.7 U	< 6 U
MW-22	MW-22	D	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	45000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-22	MW-22	T	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	45000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-26	MW-26	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	92000	< 3.3 U	-	3.7 J	32
MW-26	MW-26	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	89000	4.2 J	-	< 3.7 U	18 J
MW-26	MW-26	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	89000	< 3.3 UJ	-	< 3.7 U	18 J
MW-3	MW-3	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	200000	< 3.3 U	-	< 3.7 U	< 6 U
MW-3	MW-3	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	2300 J	< 3.6 UJ	< 0.85 U	200000	< 3.3 U	-	4.3 J	< 6 U
MW-3	MW-3	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	2300 J	< 3.6 UJ	< 0.85 U	200000	< 3.3 U	-	4.3 J	< 6 U
MW-3	MW-3	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 UJ	2400 J	< 3.6 U	< 0.85 U	210000	< 3.3 U	-	< 3.7 UJ	21 J
MW-3	DUP-4	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	2300 J	4.6 J	< 0.85 U	200000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-3	DUP-4	T	7/14/2021	180-124487-1	< 0.13 U	11 J	2300 J	< 3.6 UJ	< 0.85 U	210000	< 3.3 U	-	< 3.7 U	< 6 UJ
MW-30	MW-30	T	2/19/2021	180-117476-1	< 0.13 U	6.1 J	8500	< 3.6 U	< 0.85 U	2000000	< 17 U	-	< 3.7 U	53
MW-30	MW-30	D	7/16/2021	180-124628-1	< 0.13 U	2.9 J	17000	< 3.6 U	< 0.85 U	88000	3.4 J	-	< 3.7 U	15 J
MW-30	MW-30	T	7/16/2021	180-124628-1	< 0.13 U	12 J	17000	4.7 J	< 0.85 U	90000	4.3 J	-	< 3.7 U	290
MW-30	MW-30	D	7/26/2019	180-93333-1	< 0.1 U	1.9 J	11000	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-30	MW-30	T	7/26/2019	180-93333-1	< 0.1 U	20 J	11000	< 3.6 U	< 0.85 U	84000	< 3.3 U	-	12 J	320
MW-30	SSHS-MW-30-04302024	T	4/30/2024	1801733261	< 0.13 U	30 J	22000	< 3.7 UT	< 0.91 U	21000	< 3.0 U	-	21 J	1300
MW-32	MW-32	T	2/22/2021	180-117425-1	< 0.13 U	< 1.5 U	5300	< 3.6 U	< 0.85 U	60000	< 3.3 U	-	< 3.7 U	< 6 U
MW-32	MW-32	D	7/13/2021	180-124378-1	< 0.13 U	2 J	5100	< 3.6 U	< 0.85 U	69000	< 3.3 U	-	3.7 J	< 6 U
MW-32	MW-32	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 UJ	5200	< 3.6 U	< 0.85 U	65000	< 3.3 U	-	< 3.7 U	7.2 J
MW-33	MW-33	T	2/19/2021	180-117476-1	< 0.13 U	< 1.5 U	5500	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-33	MW-33	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	4800 J	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	< 6 U
MW-33	MW-33	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	4700 J	< 3.6 U	< 0.85 U	67000	< 3.3 U	-	< 3.7 U	< 6 U
MW-34	MW-34	T	2/24/2021	180-117542-1	< 0.13 U	5.2 J	5500	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	4.6 J	65
MW-34	MW-34	D	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	4400 J	< 3.6 U	< 0.85 U	55000	< 3.3 U	-	< 3.7 U	< 6 U
MW-34	MW-34	T	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	4600 J	< 3.6 U	< 0.85 U	57000	< 3.3 U	-	3.7 J	< 6 U
MW-36	MW-36	T	3/23/2021	180-118872-1	0.17 J	19 J	7300	5.7 J	< 0.85 U	480000	< 3.3 U	-	21 J	39
MW-36	MW-36	D	4/30/2021	180-120955-1	< 0.13 U	7.4 J	7800	< 3.6 U	< 0.85 U	340000	< 3.3 U	-	4.3 J	16 J
MW-36	MW-36	T	4/30/2021	180-120955-1	< 0.13 U	8.8 J	8000	< 3.6 U	< 0.85 U	350000	< 3.3 U	-	4.4 J	19 J
MW-36	SSHS-MW36	T	8/22/2018	180-81174-1	< 0.065 U	1.9 J	7200	< 3.6 U	< 0.85 U	83000	< 3.3 U	-	< 3.7 U	5.7 J,B
MW-38	MW-38	T	3/24/2021	180-119009-1	< 0.13 U	1.5 J	8700	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	< 6 U
MW-38	DUP-1	D	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	7500	< 3.6 U	< 0.85 U	63000	< 3.3 U	-	< 3.7 U	< 6 U
MW-38	DUP-1	T	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	7400	< 3.6 U	< 0.85 U	62000	< 3.3 U	-	< 3.7 U	< 6 U
MW-38	MW-38	D	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	7600	< 3.6 U	< 0.85 U	63000	< 3.3 U	-	< 3.7 U	< 6 U
MW-38	MW-38	T	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	7400	< 3.6 U	< 0.85 U	62000	< 3.3 U	-	< 3.7 U	< 6 U
MW-38	PS-FD-1	T	8/24/2018	180-81247-1	< 0.065 U	< 1.5 U	8000	< 3.6 U	< 0.85 U	65000	< 3.3 U	-	< 3.7 U	4.2 J,B
MW-38	SSHS-MW-38	T	8/23/2018	180-81247-1	< 0.065 U	< 1.5 U	8400	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	4.3 J,B
MW-39	SSHS-MW-39	T	8/23/2018	180-81247-1	< 0.065 U	< 1.5 U	7600	< 3.6 U	< 0.85 U	41000	< 3.3 U	-	< 3.7 U	3.7 J,B
MW-4	MW4	T	9/20/2000		-	7.3 B	-	-	-	-	-	-	8 B	90
MW-40	MW-40	T	2/23/2021	180-117459-1	< 0.13 U	2 J	4300 J	< 3.6 U	< 0.85 U	67000	< 3.3 U	-	< 3.7 U	6.5 J
MW-40	MW-40	D	5/23/2019	180-90525-1	< 0.1 U	< 1.5 U	5100	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-40	MW-40	T	5/23/2019	180-90525-1	< 0.1 U	< 1.5 U	5200	< 3.6 U	< 0.85 U	80000 J+	< 3.3 U	-	< 3.7 U	< 1.8 U
MW-41	DUP-03	T	2/20/2021	180-117476-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-41	MW-41	T	2/20/2021	180-117476-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	< 6 U
MW-41	MW-41	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	< 6 U
MW-41	MW-41	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	< 6 U
MW-43	MW-43	T	2/16/2021	180-117390-1	< 0.13 U	1.5 J	11000	< 3.6 U	< 0.85 U	1500000	< 3.3 U	-	< 3.7 U	< 6 U
MW-43	MW-43	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	4400 J	< 3.6 U	< 0.85 U	120000	< 3.3 U	-	< 3.7 U	< 6 U
MW-43	MW-43	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	4400 J	< 3.6 U	< 0.85 U	120000	< 3.3 U	-	< 3.7 U	< 6 U
MW-44	SSHS-MW-44	T	8/23/2018	180-81247-1	< 0.065 U	< 1.5 U	6800	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	3.6 J,B

DRAFT

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

					Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					2000	3	25	1000	3	5		50		200	300[1]	25	35000	300[1]
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report														
MW-47	DUP-01	T	2/22/2021	180-117425-1	250 J	< 3.4 U	< 4.1 U	69 J	< 0.33 U	< 0.28 U	57000	< 1.9 U	0.58 J	< 9.1 U	500 J	< 2.9 U	9500	53 J
MW-47	MW-47	T	2/22/2021	180-117425-1	140 J	< 3.4 U	< 4.1 U	68 J	< 0.33 U	< 0.28 U	58000	< 1.9 U	< 0.55 UJ	< 9.1 U	240 J	< 2.9 U	9600	27 J
MW-47	MW-47	D	7/12/2021	180-124354-1	< 53 U	< 3.4 U	< 4.1 U	71 J	< 0.33 U	< 0.28 U	60000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9800	< 2.7 U
MW-47	MW-47	T	7/12/2021	180-124354-1	< 53 U	< 3.4 U	< 4.1 U	69 J	< 0.33 U	< 0.28 U	59000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9600	< 2.7 U
MW-47I	MW-47I	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	84 J	< 0.33 U	< 0.28 U	73000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	10000	36
MW-47I	MW-47I	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	84 J	< 0.33 U	< 0.28 U	74000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	11000	39
MW-47I	DUP-01	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	82 J	< 1.5 U	< 0.3 U	74000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	2.9 J
MW-47I	DUP-01	T	10/27/2021	180-129230-1	43 J	< 6.2 UJ	< 8.3 U	82 J	< 1.5 U	< 0.3 U	74000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	5.8 J
MW-47I	MW-47I	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	86 J	< 1.5 U	< 0.3 U	76000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	3.8 J
MW-47I	MW-47I	T	10/27/2021	180-129230-1	41 J	< 6.2 UJ	< 8.3 U	86 J	< 1.5 U	< 0.3 U	75000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	12 J
MW-47I	SSHS-DUP-01-04252024	T	4/25/2024	1801731401	340	< 6.2 U	< 8.3 U	87 J	< 1.5 U	< 0.30 U	72000	< 3.1 U	< 3.4 U	< 2.2 U	520	< 4.4 U	11000	64
MW-47I	SSHS-MW-47I-04252024	T	4/25/2024	1801731401	570	< 6.2 U	< 8.3 U	91 J	< 1.5 U	< 0.30 U	73000	< 3.1 U	< 3.4 U	< 2.2 U	820	< 4.4 U	11000	69
MW-48	MW-48	T	2/17/2021	180-117387-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	10 J
MW-48	MW-48	D	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	17000	< 2.7 U
MW-48	MW-48	T	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	< 2.7 U
MW-48R	DUP-01-01162024	T	1/16/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	98000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	16000	< 2.4 U
MW-48R	SSHS-DUP-01-11152023	T	11/15/2023	1801654471	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	92000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-48R	SSHS-DUP-02-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	97000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	13	16000	< 2.4 U
MW-48R	SSHS-MW-48R-01162024	T	1/16/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	97000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	16000	< 2.4 U
MW-48R	SSHS-MW-48R-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	93000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	14	15000	< 2.4 U
MW-48R	SSHS-MW-48R-09132023	T	9/13/2023	1801624601	99 J	< 7.5 U	5.2 J	150 J	< 0.60 U	< 0.45 UT	91000	1.0 J	< 0.75 U	< 3.5 U	< 83 U	4.6 J	15000	< 2.6 U
MW-48R	SSHS-MW-48R-11152023	T	11/15/2023	1801654471	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	90000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-49	DUP-04	T	2/17/2021	180-117387-1	< 53 UJ	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 UJ	< 2.9 U	14000	49
MW-49	MW-49	T	2/17/2021	180-117387-1	120 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	87000	< 1.9 U	< 0.55 U	< 9.1 U	210 J	< 2.9 U	14000	54
MW-49	MW-49	D	4/28/2021	180-120857-1	58 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	90 J	< 2.9 U	14000	15
MW-49	MW-49	T	4/28/2021	180-120857-1	75 J	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	140	< 2.9 U	15000	18
MW-50I	SSHS-RI-MW-50I	T	2/12/2021	180-117176-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	0.64 J	< 2.2 U	< 31 U	< 2.9 U	16000	330
MW-50I	MW-50I	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	95 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	0.74 J	< 9.1 U	< 89 U	< 2.9 U	16000	380
MW-50I	MW-50I	T	4/28/2021	180-120857-1	130 J	< 3.4 U	< 4.1 U	95 J	< 0.33 U	< 0.28 U	92000	< 1.9 U	1.1 J	< 9.1 U	180	< 2.9 U	16000	410
MW-50R	SSHS-MW-50R-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	120 J	< 0.60 UJ	< 0.45 U	98000	1.1 J	< 0.75 U	< 3.5 U	< 83 U	2.9 J	16000	< 2.6 U
MW-50S	SSHS-RI-MW-50S	T	2/12/2021	180-117176-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	97000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	15000	5.8 J
MW-50S	MW-50S	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-50S	MW-50S	T	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-51	DUP-05	T	2/12/2021	180-117176-1	< 53 U	< 3.4 U	< 4.1 U	180 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	17000	78
MW-51	SSHS-RI-MW-51	T	2/12/2021	180-117176-1	< 53 U	< 3.4 U	< 4.1 U	190 J	< 0.33 U	< 0.28 U	110000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	18000	80
MW-51	MW-51	D	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	180 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	18000	< 2.7 U
MW-51	MW-51	T	4/27/2021	180-120743-1	520	< 3.4 U	< 4.1 U	190 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	0.86 J	< 9.1 U	1100	< 2.9 U	19000	76
MW-51	SSHS-DUP-04-09142023	T	9/14/2023	1801625601	140 U	< 7.5 U	< 4.1 UJ	140 J	< 0.60 U	< 0.45 U	90000	1.3 J	< 0.75 U	< 3.5 U	150 J	< 2.8 U	14000	6.7 J
MW-51	SSHS-MW-51-01182024	T	1/18/2024	1801682891	350	< 6.2 UT	< 8.3 U	150 J	< 1.5 U	< 0.30 U	96000	4.0 J	< 3.4 U	< 2.2 UT	410	< 4.4 U	16000	14 J
MW-51	SSHS-MW-51-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	99000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	15	16000	4.1 J
MW-51	SSHS-MW-51-05022023	T	5/2/2023	1801559471	200	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	86000	< 1.6 U	< 1.9 U	< 2.2 U	200	< 4.4 U	14000	17
MW-51	SSHS-MW-51-09142023	T	9/14/2023	1801625601	130 J	< 7.5 U	6.5 J	140 J	< 0.60 U	< 0.45 UT	89000	0.98 J	< 0.75 U	< 3.5 U	110 J	< 2.8 U	14000	5.9 J
MW-51	SSHS-MW-51-11142023	T	11/14/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	97000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	16000	4.0 J
MW-52	SSHS-RI-MW-52	T	2/12/2021	180-117176-1	76 J	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	98000	< 0.78 U	< 0.55 U	< 2.2 U	110	< 2.9 U	16000	130
MW-52	DUP-2	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	94000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	13 J
MW-52	DUP-2	T	4/28/2021	180-120857-1	77 J	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	160	< 2.9 U	16000	28
MW-52	MW-52	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	9.6 J
MW-52	MW-52	T	4/28/2021	180-120857-1	< 53 UJ	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	94000	< 1.9 U	< 0.55 U	< 9.1 U	120	< 2.9 U	16000	26
MW-53	MW-53	T	2/17/2021	180-117387-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	91000	< 1.9 U	0.6 J	< 9.1 U	< 89 U	< 2.9 U	15000	6.3 J
MW-53	MW-53	D	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	91000	< 1.9 U	0.64 J	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-53	MW-53	T	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	16000	< 2.7 U
MW-53	SSHS-MW-53-09042023	T	9/4/2023	1801619191	< 41 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	96000	< 1.6 U	< 1.9 U	< 2.2 UT	< 72 U	< 4.4 U	16000	< 2.4 U
MW-54	MW-54	T	2/16/2021	180-117390-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	4.2 J
MW-54	MW-54	D	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-54	MW-54	T	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	2.8 J
MW-54R	SSHS-MW-54R-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 UJ	< 0.45 U	81000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	13000	< 2.6 U
MW-55	MW-55	T	2/16/2021	180-117390-1	1000	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	92000	< 1.9 U	1.4 J	< 9.1 U	2100	< 2.9 U	16000	85
MW-55	DUP-01-05022023	T	5/2/2023	1801559471	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	87000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-55	SSHS-MW-55-01162024	T	1/16/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-55	SSHS-MW-55-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	88000	< 3.1 U	< 3.4 U	< 2.2 U	150	13	14000	6.8 J
MW-55	SSHS-MW-55-05022023	T	5/2/2023	1801559471	49 J	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	92000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-55	SSHS-MW-55-09132023	T	9/13/2023	1801624601	120 J	< 7.5 U	7.2 J	120 J	< 0.60 U	< 0.45 UT	81000	0.86 J	< 0.75 U	< 3.5 U	99 J	< 2.8 U	13000	6.5 J
MW-55	SSHS-MW-55-11152023	T	11/15/2023	1801654471	240	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	88000	< 3.1 U	< 3.4 U	< 2.2 U	440	< 4.4 U	15000	19 J+
MW-56	MW-56	T	2/17/2021	180-117387-1	690	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	1.3 J	< 9.1 U	1500	< 2.9 U	18000	130
MW-56	SSHS-MW-56-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 UJ	< 0.45 U	81000	< 0.76 U	< 0.75 U	< 3.5 U	150 J	< 2.8 U	13000	17
MW-57	MW-57	T	2/18/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	95000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	94
MW-57	MW-57	D	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	6.1 J
MW-57	MW-57	T	4/29/2021	180-121010-1	69 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	96000	< 1.9 U	< 0.55 U	< 9.1 U	150	< 2.9 U	15000	12 J
MW-57	DUP-01	D	7/13/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	91000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-57	DUP-01	T	7/13/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	89000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	2.9 J
MW-57	MW-57	D	7/13/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	94000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-57	MW-57	T	7/13/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	89000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	3.7 J
MW-57R	SSHS-MW-57R-01172024	T	1/17/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	84000	7.0	< 3.4 U	< 2.2 U	160	< 4.4 U	13000	4.5 J
MW-57R	SSHS-MW-57R-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	9.6 J	13000	< 2.4 U
MW-57R	SSHS-MW-57R-05022023	T	5/2/2023	1801559471	46 J	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	94000 T	< 1.6 U	< 1.9 U	< 2.2 U	170	< 4.4 U	16000	160
MW-57R	SSHS-MW-57R-09142023	T	9/14/2023	1801625601	120 J	< 7.5 U	5.9 J	110 J	< 0.60 U	< 0.45 UT	76000	0.87 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	12000	3.2 J
MW-57R	SSHS-MW-57R-11132023	T	11/13/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	93000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	2.6 J
MW-58	MW-58	T	2/21/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	180 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	1300	< 2.9 U	16000	940
MW-58	MW-58	D	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	820	< 2.9 U	15000	730
MW-58	MW-58	T	4/30/2021	180-120955-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	770	3 J	14000	690
MW-58	SSHS-DUP-01-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	95 J	< 0.60 UJ	< 0.45 U	89000	< 0.76 UJ	< 0.75 U	< 3.5 U	660	2.9 J	9500	700
MW-58	SSHS-MW-58-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	98 J	< 0.60 UJ	< 0.45 U	91000	0.99 J	< 0.75 U	< 3.5 U	580	< 2.8 UJ	9900	720
MW-59I	MW-59I	T	2/19/2021	180-117476-1	130 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	240	< 2.9 U	14000	33
MW-59I	MW-59I	D	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-59I	MW-59I	T	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	79000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
MW-59I	MW-59I	D	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	82000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-59I	MW-59I	T	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	79000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-59S	MW-59S	T	2/19/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-59S	MW-59S	D	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-59S	MW-59S	T	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-59S	MW-59S	D	7/13/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	86000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-59S	MW-59S	T	7/13/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	79000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-5I	SSHS-MW-5I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	120000	< 3.1 U	< 3.4 U	2.2 J	820	< 4.4 U	16000	570
MW-5I	SSHS-MW-5I-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	160 J	< 0.60 U	< 0.45 U	130000	1.2 J	< 0.75 U	< 3.5 U	730	< 2.8 U	16000	540
MW-5S	MW5	T	5/16/2000		-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW5	T	9/20/2000		-	-	5.8 B	143 B	-	-	-	0.82 B	-	-	-	-	-	-
MW-5S	MW-5	T	2/23/2021	180-117459-1	< 53 U	< 3.4 U	< 4.1 U	190 J	< 0.33 U	< 0.28 U	130000	< 1.9 U	< 0.55 U	< 9.1 U	290	< 2.9 U	16000	490
MW-5S	MW-5	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	160 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	510	< 2.9 U	15000	580
MW-5S	MW-5	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	160 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	520	< 2.9 U	15000	570
MW-60	MW-60	T	2/18/2021	180-117476-1	63 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	100	< 2.9 U	14000	89
MW-60	MW-60	D	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-60	MW-60	T	4/29/2021	180-121010-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-60	MW-60	D	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	83000	< 1.6 U	< 1.9 U	< 2.2 U	120	< 4.4 U	14000	< 2.4 U
MW-60	MW-60	T	7/12/2022	1801412391	64 J	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	82000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	28
MW-61	MW-61	T	2/16/2021	180-117390-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	94000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	16
MW-61	MW-61	D	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	0.55 J	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-61	MW-61	T	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-61	MW-61	D	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	99000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	16000	< 2.4 U
MW-61	MW-61	T	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	91000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-62	MW-62	T	2/16/2021	180-117390-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-62	MW-62	D	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-62	MW-62	T	4/27/2021	180-120743-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-62	MW-62	D	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	89000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-62	MW-62	T	7/12/2022	1801412391	< 41 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	87000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-62R	SSHS-MW-62R-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	99000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	16	17000	36
MW-62R	SSHS-MW-62R-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	140 J	< 0.60 UJ	< 0.45 U	90000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	3.1 J	16000	41
MW-63I	MW-63I	T	2/18/2021	180-117476-1	77 J	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	100	< 2.9 U	14000	53
MW-63I	SSHS-MW-63I-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 U	< 0.45 U	85000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	15000	< 2.6 U
MW-63S	MW-63S	T	2/18/2021	180-117476-1	100 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	210	< 2.9 U	14000	27
MW-63S	SSHS-MW-63S-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 UT	82000	0.94 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	13000	< 2.6 U
MW-64I	MW-64I	T	2/20/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	79000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
MW-64I	MW-64I	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	78000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
MW-64I	MW-64I	T	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	78000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Thallium (Method 6010)	Thallium (Method 6020)	Vanadium	Zinc
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.7	100		10	50		0.5[2]	0.5[2]		2000
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-47	DUP-01	T	2/22/2021	180-117425-1	< 0.13 U	< 1.5 U	2600 J	< 3.6 U	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	< 6 U
MW-47	MW-47	T	2/22/2021	180-117425-1	< 0.13 U	< 1.5 U	2600 J	< 3.6 U	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
MW-47	MW-47	D	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-47	MW-47	T	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-47I	MW-47I	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	24 J
MW-47I	MW-47I	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	2800 J	< 3.6 U	< 0.85 U	73000	3.4 J	-	< 3.7 U	< 6 UJ
MW-47I	DUP-01	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	2800 J	< 3.7 U	< 0.91 U	69000	< 3 UJ	-	< 5.3 U	2.7 J
MW-47I	DUP-01	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	2800 J	< 3.7 UJ	< 0.91 U	70000	< 3 UJ	-	< 5.3 U	< 2.6 UJ
MW-47I	MW-47I	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	2900 J	< 3.7 U	< 0.91 U	72000	< 3 UJ	-	< 5.3 U	< 2.6 UJ
MW-47I	MW-47I	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	2900 J	4.9 J	< 0.91 U	72000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-47I	SSHS-DUP-01-04252024	T	4/25/2024	1801731401	< 0.13 U	< 3.5 U	2700 J	< 3.7 U	< 0.91 U	77000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-47I	SSHS-MW-47I-04252024	T	4/25/2024	1801731401	< 0.13 U	< 3.5 U	2900 J	< 3.7 U	< 0.91 U	79000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-48	MW-48	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
MW-48	MW-48	D	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3700 J	4.2 J,B	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
MW-48	MW-48	T	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
MW-48R	DUP-01-01162024	T	1/16/2024	1801682361	< 0.13 U	< 3.5 U	3900 J	< 3.7 UT	< 0.91 U	89000	3.9 BJ	-	< 5.3 U	< 42 U
MW-48R	SSHS-DUP-01-11152023	T	11/15/2023	1801654471	< 0.13 UJ	< 3.5 U	3500 J	< 3.7 UJ	< 0.91 U	85000	< 3.0 U	-	< 5.3 U	< 42 U
MW-48R	SSHS-DUP-02-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	83000	< 3.0 U	-	< 5.3 U	< 42 U
MW-48R	SSHS-MW-48R-01162024	T	1/16/2024	1801682361	< 0.13 U	< 3.5 U	3800 J	< 3.7 UT	< 0.91 U	88000	3.8 BJ	-	< 5.3 U	< 42 U
MW-48R	SSHS-MW-48R-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	78000	3.0 J	-	< 5.3 U	< 42 U
MW-48R	SSHS-MW-48R-09132023	T	9/13/2023	1801624601	< 0.13 U	2.2 J	4100 J	< 6.0 U	< 0.62 U	87000	< 2.7 U	-	< 5.6 U	< 23 UT
MW-48R	SSHS-MW-48R-11152023	T	11/15/2023	1801654471	0.20 J	< 3.5 U	3500 J	< 3.7 UJ	< 0.91 U	83000	< 3.0 U	-	< 5.3 U	< 42 U
MW-49	DUP-04	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-49	MW-49	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-49	MW-49	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3200 J	4.2 J	< 0.85 U	67000	< 3.3 U	-	< 3.7 U	< 6 U
MW-49	MW-49	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 UJ	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	< 6 U
MW-50I	SSHS-RI-MW-50I	T	2/12/2021	180-117176-1	< 0.13 U	< 1.5 U	4700 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-50I	MW-50I	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	7100	< 3.6 U	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
MW-50I	MW-50I	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	7900	5.5 J	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	< 6 U
MW-50R	SSHS-MW-50R-09142023	T	9/14/2023	1801625611	< 0.13 U	4.1 J	3700 J	< 6.0 U	< 0.62 U	72000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-50S	SSHS-RI-MW-50S	T	2/12/2021	180-117176-1	< 0.13 U	< 1.5 U	3900 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-50S	MW-50S	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-50S	MW-50S	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3500 J	3.8 J	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-51	DUP-05	T	2/12/2021	180-117176-1	< 0.13 U	< 1.5 U	4100 J	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	3.8 J	< 6 U
MW-51	SSHS-RI-MW-51	T	2/12/2021	180-117176-1	< 0.13 U	< 1.5 U	4300 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-51	MW-51	D	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3800 J	4.6 J	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
MW-51	MW-51	T	4/27/2021	180-120743-1	< 0.13 U	1.6 J	3900 J	< 3.6 UJ	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	6.4 J
MW-51	SSHS-DUP-04-09142023	T	9/14/2023	1801625601	< 0.13 U	< 2.2 U	3600 J	< 6.0 U	< 0.62 U	41000	< 2.7 U	-	< 5.6 U	47 J
MW-51	SSHS-MW-51-01182024	T	1/18/2024	1801682891	< 0.13 U	4.5 J	3200 J	< 3.7 UT	< 0.91 U	38000	< 3.0 UT	-	< 5.3 U	55
MW-51	SSHS-MW-51-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	2900 J	< 3.7 U	< 0.91 U	43000	3.9 J	< 0.47 U	< 5.3 U	< 42 U
MW-51	SSHS-MW-51-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2000 J	< 3.7 U	< 0.91 U	45000	< 3.0 U	-	< 5.3 U	36 B
MW-51	SSHS-MW-51-09142023	T	9/14/2023	1801625601	< 0.13 U	< 2.2 U	3800 J	< 6.0 U	< 0.62 U	40000	3.7 U	-	< 5.6 U	47 J
MW-51	SSHS-MW-51-11142023	T	11/14/2023	1801653531	0.13 J	< 3.5 U	3600 J	< 3.7 U	< 0.91 U	72000	< 3.0 U	-	< 5.3 U	< 42 U
MW-52	SSHS-RI-MW-52	T	2/12/2021	180-117176-1	< 0.13 U	< 1.5 U	4200 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-52	DUP-2	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 UJ	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-52	DUP-2	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 UJ	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-52	MW-52	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	3.9 J	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-52	MW-52	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	4.4 J	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-53	MW-53	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-53	MW-53	D	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3700 J	4.2 J,B	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
MW-53	MW-53	T	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-53	SSHS-MW-53-09042023	T	9/4/2023	1801619191	< 0.13 U	2.6 J	3900 J	< 3.7 U	< 0.91 U	89000	< 3.0 U	-	< 5.3 U	15 J
MW-54	MW-54	T	2/16/2021	180-117390-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
MW-54	MW-54	D	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	5.3 J	< 6 U
MW-54	MW-54	T	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-54R	SSHS-MW-54R-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3800 J	< 6.0 U	< 0.62 U	80000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-55	MW-55	T	2/16/2021	180-117390-1	< 0.13 U	1.9 J	3900 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	9.7 J
MW-55	DUP-01-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2400 J	< 3.7 U	< 0.91 U	82000	< 3.0 U	-	< 5.3 U	34 B
MW-55	SSHS-MW-55-01162024	T	1/16/2024	1801682361	< 0.13 U	< 3.5 U	2700 J	< 3.7 UT	< 0.91 U	54000	< 3.0 U	-	< 5.3 U	< 42 U
MW-55	SSHS-MW-55-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	2900 J	< 3.7 U	< 0.91 U	64000	< 3.0 U	-	< 5.3 U	< 42 U
MW-55	SSHS-MW-55-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2400 J	< 3.7 U	< 0.91 U	87000	< 3.0 U	-	< 5.3 U	20 B
MW-55	SSHS-MW-55-09132023	T	9/13/2023	1801624601	< 0.13 U	2.5 J	3800 J	< 6.0 U	< 0.62 U	77000	< 2.7 U	-	< 5.6 U	23 J
MW-55	SSHS-MW-55-11152023	T	11/15/2023	1801654471	0.44 J	< 3.5 U	3500 J	< 3.7 UJ	< 0.91 U	77000	< 3.0 U	-	< 5.3 U	< 42 U
MW-56	MW-56	T	2/17/2021	180-117387-1	< 0.13 U	< 1.5 U	4200 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	9 J
MW-56	SSHS-MW-56-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	4000 J	< 6.0 U	< 0.62 U	69000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-57	MW-57	T	2/18/2021	180-117476-1	< 0.13 U	< 1.5 U	4000 J	3.8 J	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-57	MW-57	D	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	< 6 U
MW-57	MW-57	T	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-57	DUP-01	D	7/13/2022	1801412391	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	73000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-57	DUP-01	T	7/13/2022	1801412391	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	74000	< 3.0 U	-	< 5.3 U	4.9 BJ
MW-57	MW-57	D	7/13/2022	1801412391	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	77000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-57	MW-57	T	7/13/2022	1801412391	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	74000	< 3.0 U	-	6.0 J	7.5 BJ
MW-57R	SSHS-MW-57R-01172024	T	1/17/2024	1801682361	< 0.13 U	5.3 J	3100 J	< 3.7 UT	< 0.91 U	57000	< 3.0 U	-	< 5.3 U	50
MW-57R	SSHS-MW-57R-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	2900 J	< 3.7 U	< 0.91 U	61000	< 3.0 U	-	< 5.3 U	57 B
MW-57R	SSHS-MW-57R-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2200 J	< 3.7 U	1.3 J	71000 T	< 3.0 U	-	< 5.3 U	45 B
MW-57R	SSHS-MW-57R-09142023	T	9/14/2023	1801625601	< 0.13 U	< 2.2 U	3700 J	< 6.0 U	< 0.62 U	53000	< 2.7 U	-	< 5.6 U	< 23 UT
MW-57R	SSHS-MW-57R-11132023	T	11/13/2023	1801653531	< 0.13 U	3.6 J	3700 J	< 3.7 U	< 0.91 U	71000	< 3.0 U	-	< 5.3 U	< 42 U
MW-58	MW-58	T	2/21/2021	180-117476-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	57000	< 3.3 U	-	< 3.7 U	< 6 U
MW-58	MW-58	D	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	39000	< 3.3 U	-	< 3.7 U	< 6 U
MW-58	MW-58	T	4/30/2021	180-120955-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	36000	< 3.3 U	-	< 3.7 U	< 6 U
MW-58	SSHS-DUP-01-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3600 J	< 6.0 U	< 0.62 U	14000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-58	SSHS-MW-58-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3700 J	< 6.0 U	< 0.62 U	15000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-59I	MW-59I	T	2/19/2021	180-117476-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-59I	MW-59I	D	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-59I	MW-59I	T	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-59I	MW-59I	D	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3300 J	< 3.7 U	< 0.91 U	72000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-59I	MW-59I	T	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	71000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-59S	MW-59S	T	2/19/2021	180-117476-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-59S	MW-59S	D	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-59S	MW-59S	T	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-59S	MW-59S	D	7/13/2022	1801412391	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	75000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-59S	MW-59S	T	7/13/2022	1801412391	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	71000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-5I	SSHS-MW-5I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	61000	3.4 J	< 0.47 U	< 5.3 U	< 42 U
MW-5I	SSHS-MW-5I-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	70000	4.6 J	-	< 5.6 U	< 23 U
MW-5S	MW5	T	5/16/2000		-	-	-	-	-	-	-	-	-	21.4
MW-5S	MW5	T	9/20/2000		-	-	-	-	-	-	-	-	-	6.7 B
MW-5S	MW-5	T	2/23/2021	180-117459-1	< 0.13 U	< 1.5 U	3600 J	4 J	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-5S	MW-5	D	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	63000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-5S	MW-5	T	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	63000	3.4 J	-	< 3.7 U	< 6 U
MW-60	MW-60	T	2/18/2021	180-117476-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-60	MW-60	D	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	4.5 J	12 J
MW-60	MW-60	T	4/29/2021	180-121010-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 UJ	18 J
MW-60	MW-60	D	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	74000	< 3.0 U	-	< 5.3 U	2.7 J
MW-60	MW-60	T	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	74000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-61	MW-61	T	2/16/2021	180-117390-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-61	MW-61	D	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	4 J	< 6 U
MW-61	MW-61	T	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3600 J	3.8 J	< 0.85 U	80000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-61	MW-61	D	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	89000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-61	MW-61	T	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	85000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-62	MW-62	T	2/16/2021	180-117390-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-62	MW-62	D	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-62	MW-62	T	4/27/2021	180-120743-1	< 0.13 U	< 1.5 U	3500 J	4.4 J	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-62	MW-62	D	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	74000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-62	MW-62	T	7/12/2022	1801412391	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	75000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-62R	SSHS-MW-62R-04042024	T	4/4/2024	1801719081	0.26 B	< 3.5 U	4600 J	< 3.7 U	< 0.91 U	72000	< 3.0 U	-	< 5.3 U	< 42 U
MW-62R	SSHS-MW-62R-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	4500 J	< 6.0 U	< 0.62 U	72000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-63I	MW-63I	T	2/18/2021	180-117476-1	< 0.13 U	< 1.5 U	3900 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-63I	SSHS-MW-63I-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	73000	3.2 J	-	< 5.6 U	< 23 U
MW-63S	MW-63S	T	2/18/2021	180-117476-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-63S	SSHS-MW-63S-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	3900 J	< 6.0 U	< 0.62 U	75000	< 2.7 U	-	< 5.6 U	< 23 UT
MW-64I	MW-64I	T	2/20/2021	180-117476-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	14 J
MW-64I	MW-64I	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	< 6 U
MW-64I	MW-64I	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	67000	< 3.3 U	-	< 3.7 U	< 6 U

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					2000	3	25	1000	3	5		50		200	300[1]	25	35000	300[1]
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report														
MW-64I	SSHS-MW-64I-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	120 J	< 0.60 U	< 0.45 U	82000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	< 2.6 U
MW-64S	MW-64S	T	2/20/2021	180-117476-1	64 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	7.9 J
MW-64S	MW-64S	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	91000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
MW-64S	MW-64S	T	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-64S	SSHS-MW-64S-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	120 J	< 0.60 U	< 0.45 U	83000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	3.4 J	13000	< 2.6 U
MW-65	MW-65	T	2/20/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	11 J
MW-65	DUP-3	D	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	3.9 J
MW-65	DUP-3	T	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 UJ
MW-65	MW-65	D	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-65	MW-65	T	4/26/2021	180-120679-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000	3.5 J	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-65	SSHS-DUP1-08152022	D	8/15/2022	1801429571	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-65	SSHS-DUP1-08152022	T	8/15/2022	1801429571	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	86000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-65	SSHS-MW-65-08152022	D	8/15/2022	1801429571	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-65	SSHS-MW-65-08152022	T	8/15/2022	1801429571	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	< 2.4 U
MW-65R	SSHS-MW-65R-04082024	T	4/8/2024	1801720411	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	77000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	10	12000	< 2.4 U
MW-65R	SSHS-MW-65R-09142023	T	9/14/2023	1801625611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 UJ	< 0.45 U	76000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	12000	< 2.6 U
MW-66I	MW-66I	T	2/20/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	21
MW-66I	MW-66I	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-66I	MW-66I	T	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-66I	SSHS-MW-66I-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 U	82000	1.2 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	< 2.6 U
MW-66S	MW-66S	T	2/19/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	80000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	28
MW-66S	MW-66S	D	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-66S	MW-66S	T	4/28/2021	180-120857-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-66S	SSHS-MW-66S-09122023	T	9/12/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 U	86000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	< 2.6 U
MW-67I	MW-67I	D	7/16/2021	180-124628-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	37
MW-67I	MW-67I	T	7/16/2021	180-124628-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	41
MW-67I	MW-67I	D	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	8.2 J
MW-67I	MW-67I	T	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	6.6 J
MW-67I	SSHS-MW-67I-04282024	T	4/28/2024	1801733271	130 J	< 6.2 UT	< 8.3 U	150 J	< 1.5 U	< 0.30 U	91000	< 3.1 U	< 3.4 U	< 2.2 U	500 B	< 4.4 U	15000	29
MW-67S	MW-67S	D	7/16/2021	180-124628-1	< 53 U	< 3.4 U	< 4.1 U	220	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	1200	< 2.9 U	15000	640
MW-67S	MW-67S	T	7/16/2021	180-124628-1	< 53 U	< 3.4 U	< 4.1 U	220	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	1200	< 2.9 U	16000	650
MW-67S	MW-67S	D	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	200	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 U	< 9.1 U	1300	< 2.9 U	14000	590
MW-67S	MW-67S	T	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	210	< 0.33 U	< 0.28 U	98000	< 1.9 U	< 0.55 U	< 9.1 U	1400	< 2.9 U	14000	600
MW-67S	SSHS-DUP-03-04282024	T	4/28/2024	1801733271	< 110 U	< 6.2 UT	< 8.3 U	210	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	1700 B	< 4.4 U	16000	680
MW-67S	SSHS-MW-67S-04282024	T	4/28/2024	1801733271	< 110 U	< 6.2 UT	< 8.3 U	210	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	1400 B	< 4.4 U	15000	660
MW-68S	DUP-3	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	6.6 J	190 J	< 0.33 U	< 0.28 U	130000	< 1.9 U	< 0.55 U	< 9.1 U	1700	< 2.9 U	15000	1100
MW-68S	DUP-3	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 UJ	190 J	< 0.33 U	< 0.28 U	130000	< 1.9 U	< 0.55 U	< 9.1 U	1700	3.9 J	15000	1100
MW-68S	MW-68S	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	4.8 J	190 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	1700	< 2.9 U	15000	1100
MW-68S	MW-68S	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 UJ	180 J	< 0.33 U	< 0.28 U	120000	< 1.9 U	< 0.55 U	< 9.1 U	1700	3.2 J	15000	1100
MW-68S	DUP-2	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	170 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 UJ	< 9.1 U	1500	< 2.9 U	13000	950
MW-68S	DUP-2	T	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	170 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	1500	< 2.9 U	13000	950
MW-68S	MW-68S	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	170 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	0.56 J	< 9.1 U	1400	< 2.9 U	13000	930
MW-68S	MW-68S	T	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	170 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 UJ	< 9.1 U	1500	< 2.9 U	13000	950
MW-68S	SSHS-MW-68S-04282024	T	4/28/2024	1801733271	< 110 U	< 6.2 UT	< 8.3 U	160 JT	< 1.5 U	< 0.30 U	110000	< 3.1 U	< 3.4 U	< 2.2 U	680 B	< 4.4 U	14000	910
MW-69I	MW-69I	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	120
MW-69I	MW-69I	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	120
MW-69I	MW-69I	D	9/3/2021	180-126702-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	4.9 J
MW-69I	MW-69I	T	9/3/2021	180-126702-1	65 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	0.55 J	< 9.1 U	120	< 2.9 U	14000	38
MW-69I	SSHS-MW-69I-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	98000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	430
MW-70I	MW-70I	D	9/9/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	88 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	11 J
MW-70I	MW-70I	T	9/9/2021	180-126939-1	160 J	< 3.4 U	< 4.1 U	93 J	< 0.33 U	< 0.28 U	87000	< 1.9 U	0.55 J	< 9.1 U	250	< 2.9 U	13000	20
MW-70I	MW-70I	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	120 J	< 1.5 U	< 0.3 U	89000	< 1.6 U	< 1.9 U	2.3 J	< 72 U	< 4.4 U	13000	6.8 J
MW-70I	MW-70I	T	10/27/2021	180-129230-1	91 J	< 6.2 UJ	< 8.3 U	120 J	< 1.5 U	< 0.3 U	88000	< 1.6 U	< 1.9 U	< 2.2 UJ	83 J	< 4.4 U	13000	10 J
MW-70I	SSHS-MW-70I-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	88000	< 3.1 U	< 3.4 U	< 2.2 U	77 J	12	13000	15
MW-70S	MW-70S	D	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	49 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	2.3 J	< 9.1 U	< 89 U	< 2.9 U	12000	1300
MW-70S	MW-70S	T	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	49 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	2.3 J	< 9.1 U	< 89 U	< 2.9 U	12000	1300
MW-70S	MW-70S	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	42 J	< 1.5 U	< 0.3 U	99000	< 1.6 U	< 1.9 U	< 2.2 U	480	< 4.4 U	10000	1000
MW-70S	MW-70S	T	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	44 J	< 1.5 U	< 0.3 U	100000	< 1.6 U	< 1.9 U	< 2.2 U	360	< 4.4 U	11000	1100
MW-70S	DUP-02	T	5/4/2023	1801561231	< 41 U	< 6.2 U	< 8.3 U	38 J	< 1.5 U	< 0.30 U	96000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	470
MW-70S	SSHS-DUP-04-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	41 J	< 1.5 U	< 0.30 U	81000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	9300	380
MW-70S	SSHS-MW-70S-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	42 J	< 1.5 U	< 0.30 U	83000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	9500	390
MW-70S	SSHS-MW-70S-05042023	T	5/4/2023	1801561231	< 41 U	< 6.2 U	< 8.3 U	36 J	< 1.5 U	< 0.30 U	91000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	450
MW-70S	SSHS-MW-70S-09152023	T	9/15/2023	1801625621	< 47 U	< 7.5 U	< 4.1 U	39 J	< 0.60 U	< 0.45 U	78000	1.5 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	10000	320
MW-71I	MW-71I	D	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	130
MW-71I	MW-71I	T	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	96000	< 1.9 U	0.72 J	< 9.1 U	< 89 U	< 2.9 U	15000	120
MW-71I	MW-71I	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	120 J	< 1.5 U	< 0.3 U	93000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	15000	26
MW-71I	MW-71I	T	10/27/2021	180-129230-1	220	< 6.2 UJ	< 8.3 U	120 J	< 1.5 U	< 0.3 U	94000	< 1.6 U	< 1.9 U	2.8 J	270	< 4.4 U	15000	84
MW-71I	SSHS-MW-71I-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	85000	< 3.1 U	< 3.4 U	< 2.2 U	130	11	13000	6.0 J
MW-71S	MW-71S	D	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	78 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	54
MW-71S	MW-71S	T	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	82 J	< 0.33 U	< 0.28 U	90000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	54
MW-71S	MW-71S	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	72 J	< 1.5 U	< 0.3 U	79000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	19
MW-71S	MW-71S	T	10/27/2021	180-129230-1	48 J	< 6.2 UJ	< 8.3 U	77 J	< 1.5 U	< 0.3 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	89 J	< 4.4 U	13000	72
MW-71S	SSHS-MW-71S-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	84 J	< 1.5 U	< 0.30 U	89000	< 3.1 U	< 3.4 U	< 2.2 U	110	11	14000	160
MW-72I	MW-72I	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	67000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	10000	510
MW-72I	MW-72I	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	67000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	10000	400
MW-72I	DUP-02	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	93 J	< 1.5 U	< 0.3 U	66000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	180
MW-72I	DUP-02	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	95 J	< 1.5 U	< 0.3 U	65000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9900	190
MW-72I	MW-72I	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	92 J	< 1.5 U	< 0.3 U	65000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9900	180
MW-72I	MW-72I	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	98 J	< 1.5 U	< 0.3 U	66000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	230
MW-72I	SSHS-MW-72I-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	70000	< 3.1 U	< 3.4 U	< 2.2 U	130	13	11000	55
MW-72S	MW-72S	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	73 J	< 0.33 U	< 0.28 U	59000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9200	28
MW-72S	MW-72S	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	71 J	< 0.33 U	< 0.28 U	58000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9100	27
MW-72S	MW-72S	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	75 J	< 1.5 U	< 0.3 U	60000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9500	6.1 J
MW-72S	MW-72S	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	74 J	< 1.5 U	< 0.3 U	60000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9400	9.9 J
MW-72S	SSHS-MW-72S-04042024	T	4/4/2024	1801719081	120 J	< 6.2 U	< 8.3 U	78 J	< 1.5 U	< 0.30 U	62000	< 3.1 U	< 3.4 U	< 2.2 U	220	10	9900	60
MW-72S	SSHS-MW-72S-05042023	T	5/4/2023	1801561231	51 J	< 6.2 U	< 8.3 U	74 J	< 1.5 U	< 0.30 U	63000	< 1.6 U	< 1.9 U	< 2.2 U	120	< 4.4 U	10000	53
MW-72S	SSHS-MW-72S-09152023	T	9/15/2023	1801625621	< 47 U	< 7.5 U	< 4.1 U	72 J	< 0.60 U	< 0.45 U	56000	0.85 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	9400	4.8 J
MW-73I	MW-73I	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	92 J	< 0.33 U	< 0.28 U	92000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	11 J
MW-73I	MW-73I	T	9/8/2021	180-126846-1	800	< 3.4 U	< 4.1 U	94 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	1.5 J	< 9.1 U	1400	< 2.9 U	14000	150
MW-73I	MW-73I	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	71 J	< 1.5 U	< 0.3 U	75000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	< 2.4 U
MW-73I	MW-73I	T	10/27/2021	180-129230-1	54 J	< 6.2 UJ	< 8.3 U	89 J	< 1.5 U	< 0.3 U	90000	< 1.6 U	< 1.9 U	< 2.2 U	83 J	< 4.4 U	14000	15
MW-73I	SSHS-MW-73I-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	83 J	< 1.5 U	< 0.30 U	91000	< 3.1 U	< 3.4 U	3.1 J	110	12	14000	56
MW-73S	MW-73S	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	89 J	< 0.33 U	< 0.28 U	71000	< 1.9 U	0.55 J	< 9.1 U	< 89 U	< 2.9 U	11000	10 J
MW-73S	MW-73S	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	90 J	< 0.33 U	< 0.28 U	72000	< 1.9 U	0.74 J	< 9.1 U	< 89 U	3.5 J	11000	12 J
MW-73S	MW-73S	D	10/26/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	81 J	< 1.5 U	< 0.3 U	68000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	12 J
MW-73S	MW-73S	T	10/26/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	79 J	< 1.5 U	< 0.3 U	67000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	11 J
MW-73S	SSHS-MW-73S-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	85 J	< 1.5 U	< 0.30 U	71000	< 3.1 U	< 3.4 U	< 2.2 U	79 J	13	11000	4.9 J
MW-74I	MW-74I	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	89 J	< 0.33 U	< 0.28 U	83000	2.3 J	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	110
MW-74I	MW-74I	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	89 J	< 0.33 U	0.74 J	84000	< 1.9 UJ	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	120
MW-74I	MW-74I	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	75 J	< 1.5 U	< 0.3 U	71000	3.6 J	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	13 J
MW-74I	MW-74I	T	10/27/2021	180-129155-1	150 J	< 6.2 U	< 8.3 U	85 J	< 1.5 U	< 0.3 U	80000	4.5 J	< 1.9 U	2.2 J	280	< 4.4 U	12000	36
MW-74I	SSHS-MW-74I-04052024	T	4/5/2024	1801720031	220	< 6.2 U	< 8.3 U	60 J	< 1.5 U	< 0.30 U	66000	3.5 J	< 3.4 U	2.3 J	390	9.1 J	8400	31
MW-74S	MW-74S	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	79 J	< 0.33 U	< 0.28 U	61000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9700	9.7 J
MW-74S	MW-74S	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	80 J	< 0.33 U	< 0.28 U	63000	< 1.9 U	0.58 J	< 9.1 U	< 89 U	< 2.9 U	10000	11 J
MW-74S	MW-74S	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	67 J	< 1.5 U	< 0.3 U	52000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	8200	< 2.4 U
MW-74S	MW-74S	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	76 J	< 1.5 U	< 0.3 U	59000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9300	3.9 J
MW-74S	SSHS-DUP-05-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	77 J	< 1.5 U	< 0.30 U	60000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	9.0 J	9700	29
MW-74S	SSHS-MW-74S-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	78 J	< 1.5 U	< 0.30 U	61000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	11	9900	25
MW-75I	MW-75I	D	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	38
MW-75I	MW-75I	T	9/9/2021	180-126905-1	67 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	130	< 2.9 U	14000	44
MW-75I	MW-75I	D	10/29/2021	180-129376-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	80000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	8.7 J
MW-75I	MW-75I	T	10/29/2021	180-129376-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	81000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	8.6 J
MW-75I	SSHS-MW-75I-04112024	T	4/11/2024	1801722811	160 J	< 6.2 U	< 8.3 U	99 J	< 1.5 U	< 0.30 U	82000	< 3.1 U	< 3.4 U	< 2.2 U	260	11	13000	12 J
MW-75S	MW-75S	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	91 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	17
MW-75S	MW-75S	T	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	92 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	23
MW-75S	MW-75S	D	10/29/2021	180-129376-1	< 41 U	< 6.2 U	< 8.3 U	91 J	< 1.5 U	< 0.3 U	76000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	3.4 J
MW-75S	MW-75S	T	10/29/2021	180-129376-1	< 41 U	< 6.2 U	< 8.3 U	91 J	< 1.5 U	< 0.3 U	75000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	6.6 J
MW-75S	SSHS-MW-75S-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	98 J	< 1.5 U	< 0.30 U	86000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	9.7 J	13000	4.3 J
MW-76I	MW-76I	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	0.56 J	< 9.1 U	< 89 U	< 2.9 U	12000	61
MW-76I	MW-76I	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	12000	67
MW-76I	DUP-03	D	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	81000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	6.6 J
MW-76I	DUP-03	T	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	82000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	11 J
MW-76I	MW-76I	D	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	82000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	7.1 J

DRAFT

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Thallium (Method 6010)	Thallium (Method 6020)	Vanadium	Zinc
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.7	100		10	50		0.5[2]	0.5[2]		2000
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-64I	SSHS-MW-64I-09122023	T	9/12/2023	1801624611	< 0.13 U	2.3 J	< 560 U	< 6.0 U	< 0.62 U	78000	< 2.7 U	-	< 5.6 U	< 23 U
MW-64S	MW-64S	T	2/20/2021	180-117476-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-64S	MW-64S	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	82000	< 3.3 U	-	3.7 J	< 6 U
MW-64S	MW-64S	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-64S	SSHS-MW-64S-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	79000	4.2 J	-	< 5.6 U	< 23 U
MW-65	MW-65	T	2/20/2021	180-117476-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-65	DUP-3	D	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-65	DUP-3	T	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-65	MW-65	D	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3400 J	4.2 J,B	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-65	MW-65	T	4/26/2021	180-120679-1	< 0.13 U	< 1.5 U	3400 J	4.1 J,B	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
MW-65	SSHS-DUP1-08152022	D	8/15/2022	1801429571	< 0.13 U	< 1.9 U	3400 J	4.7 J	< 0.91 U	77000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-65	SSHS-DUP1-08152022	T	8/15/2022	1801429571	< 0.13 U	< 1.9 U	3500 J	4.0 J	< 0.91 U	78000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-65	SSHS-MW-65-08152022	D	8/15/2022	1801429571	< 0.13 U	< 1.9 U	3400 J	3.9 J	< 0.91 U	76000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-65	SSHS-MW-65-08152022	T	8/15/2022	1801429571	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	76000	< 3.0 U	-	< 5.3 U	< 2.6 U
MW-65R	SSHS-MW-65R-04082024	T	4/8/2024	1801720411	< 0.13 U	< 3.5 U	3000 J	< 3.7 UT	< 0.91 U	70000	< 3.0 U	-	< 5.3 U	< 42 U
MW-65R	SSHS-MW-65R-09142023	T	9/14/2023	1801625611	< 0.13 U	< 2.2 U	3600 J	< 6.0 U	< 0.62 U	75000	< 2.7 UJ	-	< 5.6 U	< 23 U
MW-66I	MW-66I	T	2/20/2021	180-117476-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
MW-66I	MW-66I	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	3.7 J	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-66I	MW-66I	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 UJ	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-66I	SSHS-MW-66I-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	81000	< 2.7 U	-	< 5.6 U	< 23 U
MW-66S	MW-66S	T	2/19/2021	180-117476-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-66S	MW-66S	D	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-66S	MW-66S	T	4/28/2021	180-120857-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-66S	SSHS-MW-66S-09122023	T	9/12/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	81000	< 2.7 U	-	< 5.6 U	< 23 U
MW-67I	MW-67I	D	7/16/2021	180-124628-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	85000	5.5 J	-	< 50 U	< 6 U
MW-67I	MW-67I	T	7/16/2021	180-124628-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	84000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-67I	MW-67I	D	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
MW-67I	MW-67I	T	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	89000	< 3.3 U	-	< 3.7 U	< 6 U
MW-67I	SSHS-MW-67I-04282024	T	4/28/2024	1801733271	< 0.13 U	< 3.5 U	3700 J	< 3.7 UT	< 0.91 U	100000	< 3.0 U	-	< 5.3 U	< 42 U
MW-67S	MW-67S	D	7/16/2021	180-124628-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	90000	< 3.3 U	-	< 3.7 U	< 6 U
MW-67S	MW-67S	T	7/16/2021	180-124628-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	92000	< 3.3 U	-	< 50 U	< 6 U
MW-67S	MW-67S	D	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	96000	< 3.3 U	-	< 3.7 U	< 6 U
MW-67S	MW-67S	T	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	97000	< 3.3 U	-	< 3.7 U	< 6 U
MW-67S	SSHS-DUP-03-04282024	T	4/28/2024	1801733271	< 0.13 U	< 3.5 U	4000 J	< 3.7 UT	< 0.91 U	110000	< 3.0 U	-	< 5.3 U	< 42 U
MW-67S	SSHS-MW-67S-04282024	T	4/28/2024	1801733271	< 0.13 U	< 3.5 U	3800 J	< 3.7 UT	< 0.91 U	100000	< 3.0 U	-	< 5.3 U	< 42 U
MW-68S	DUP-3	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	5100	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-68S	DUP-3	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	5100	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-68S	MW-68S	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	5100	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-68S	MW-68S	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	5000	< 3.6 U	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
MW-68S	DUP-2	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	5000	< 3.6 U	< 0.85 U	63000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-68S	DUP-2	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	5000	< 3.6 U	< 0.85 U	64000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-68S	MW-68S	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	5000	< 3.6 U	< 0.85 U	62000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-68S	MW-68S	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	5100	< 3.6 U	< 0.85 U	63000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-68S	SSHS-MW-68S-04282024	T	4/28/2024	1801733271	< 0.13 U	< 3.5 U	4400 J	< 3.7 UT	< 0.91 U	50000	< 3.0 U	-	< 5.3 U	< 42 U
MW-69I	MW-69I	D	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-69I	MW-69I	T	7/13/2021	180-124378-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-69I	MW-69I	D	9/3/2021	180-126702-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	84000	< 3.3 U	-	< 3.7 U	< 6 U
MW-69I	MW-69I	T	9/3/2021	180-126702-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	83000	3.7 J	-	< 3.7 U	< 6 U
MW-69I	SSHS-MW-69I-04112024	T	4/11/2024	1801722811	0.13 J	< 3.5 U	3300 J	4.1 J	< 0.91 U	98000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-70I	MW-70I	D	9/9/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-70I	MW-70I	T	9/9/2021	180-126939-1	< 0.13 U	2.5 J	4000 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-70I	MW-70I	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3300 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-70I	MW-70I	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3300 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-70I	SSHS-MW-70I-04042024	T	4/4/2024	1801719081	0.26 B	< 3.5 U	3100 J	< 3.7 U	< 0.91 U	94000	< 3.0 U	-	< 5.3 U	< 42 U
MW-70S	MW-70S	D	9/7/2021	180-126846-1	< 0.13 U	2.2 J	6100	< 3.6 U	< 0.85 U	190000	< 3.3 U	-	< 3.7 U	< 6 U
MW-70S	MW-70S	T	9/7/2021	180-126846-1	< 0.13 U	1.5 J	5900	< 3.6 U	< 0.85 U	190000	< 3.3 U	-	< 3.7 U	< 6 U
MW-70S	MW-70S	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	5800	< 3.7 U	< 0.91 U	210000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-70S	MW-70S	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	6000	< 3.7 U	< 0.91 U	220000	< 3 UJ	-	5.6 J	< 2.6 U
MW-70S	DUP-02	T	5/4/2023	1801561231	< 0.13 U	2.2 J	9000 B	< 3.7 U	< 0.91 U	180000	< 3.0 U	-	< 5.3 U	3.8 BJ
MW-70S	SSHS-DUP-04-04042024	T	4/4/2024	1801719081	0.23 B	< 3.5 U	5100	< 3.7 U	< 0.91 U	170000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-70S	SSHS-MW-70S-04042024	T	4/4/2024	1801719081	0.27 B	< 3.5 U	5200	< 3.7 U	< 0.91 U	170000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-70S	SSHS-MW-70S-05042023	T	5/4/2023	1801561231	< 0.13 U	2.3 J	7400 B	< 3.7 U	< 0.91 U	170000	< 3.0 U	-	< 5.3 U	3.6 BJ
MW-70S	SSHS-MW-70S-09152023	T	9/15/2023	1801625621	< 0.13 U	< 2.2 U	5800	< 6.0 U	< 0.62 U	140000	2.7 J	-	< 5.6 U	< 23 U
MW-71I	MW-71I	D	9/7/2021	180-126846-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	83000	< 3.3 U	-	< 3.7 U	< 6 U
MW-71I	MW-71I	T	9/7/2021	180-126846-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-71I	MW-71I	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	89000	< 3 UJ	-	5.9 J	< 2.6 U
MW-71I	MW-71I	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3300 J	< 3.7 U	< 0.91 U	83000	< 3 UJ	-	< 5.3 UJ	3.5 J
MW-71I	SSHS-MW-71I-04052024	T	4/5/2024	1801720031	0.15 BJ	< 3.5 U	3100 J	< 3.7 U	< 0.91 U	87000	< 3.0 U	-	< 5.3 U	< 42 U
MW-71S	MW-71S	D	9/7/2021	180-126846-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	93000	< 3.3 U	-	< 3.7 U	< 6 U
MW-71S	MW-71S	T	9/7/2021	180-126846-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	98000	< 3.3 U	-	< 3.7 U	< 6 U
MW-71S	MW-71S	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3200 J	< 3.7 U	< 0.91 U	87000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-71S	MW-71S	T	10/27/2021	180-129230-1	0.2	< 1.9 U	3300 J	< 3.7 U	< 0.91 U	91000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-71S	SSHS-MW-71S-04052024	T	4/5/2024	1801720031	0.15 BJ	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	97000	3.4 BJ	-	< 5.3 U	< 42 U
MW-72I	MW-72I	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	66000	< 3.3 U	-	< 3.7 U	< 6 U
MW-72I	MW-72I	T	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	66000	< 3.3 U	-	< 3.7 U	< 6 U
MW-72I	DUP-02	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2600 J	< 3.7 U	< 0.91 U	68000	< 3 U	-	< 5.3 U	< 2.6 U
MW-72I	DUP-02	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2500 J	< 3.7 U	< 0.91 U	67000	< 3 U	-	< 5.3 U	< 2.6 U
MW-72I	MW-72I	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2500 J	< 3.7 U	< 0.91 U	68000	< 3 U	-	< 5.3 U	< 2.6 U
MW-72I	MW-72I	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2500 J	< 3.7 U	< 0.91 U	67000	< 3 U	-	< 5.3 U	< 2.6 U
MW-72I	SSHS-MW-72I-04042024	T	4/4/2024	1801719081	0.26 B	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	74000	< 3.0 U	-	< 5.3 U	< 42 U
MW-72S	MW-72S	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2600 J	< 3.6 U	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
MW-72S	MW-72S	T	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2600 J	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	< 6 U
MW-72S	MW-72S	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2600 J	< 3.7 U	< 0.91 U	70000	< 3 U	-	< 5.3 U	< 2.6 U
MW-72S	MW-72S	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2500 J	< 3.7 U	< 0.91 U	69000	< 3 U	-	< 5.3 U	< 2.6 U
MW-72S	SSHS-MW-72S-04042024	T	4/4/2024	1801719081	0.25 B	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	78000	< 3.0 U	-	< 5.3 U	< 42 U
MW-72S	SSHS-MW-72S-05042023	T	5/4/2023	1801561231	< 0.13 U	2.3 J	3100 BJ	< 3.7 U	< 0.91 U	80000	< 3.0 U	-	< 5.3 U	3.6 BJ
MW-72S	SSHS-MW-72S-09152023	T	9/15/2023	1801625621	< 0.13 U	< 2.2 U	2500 J	< 6.0 U	< 0.62 U	70000	< 2.7 U	-	< 5.6 U	< 23 U
MW-73I	MW-73I	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	83000	< 3.3 U	-	< 3.7 U	< 6 U
MW-73I	MW-73I	T	9/8/2021	180-126846-1	< 0.13 U	1.5 J	3600 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-73I	MW-73I	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	4200 J	< 3.7 U	< 0.91 U	75000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-73I	MW-73I	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	85000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-73I	SSHS-MW-73I-04052024	T	4/5/2024	1801720031	0.15 BJ	< 3.5 U	3200 J	< 3.7 U	< 0.91 U	86000	< 3.0 U	-	< 5.3 U	< 42 U
MW-73S	MW-73S	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	92000	< 3.3 U	-	< 3.7 U	< 6 U
MW-73S	MW-73S	T	9/8/2021	180-126846-1	< 0.13 U	1.9 J	3400 J	< 3.6 U	< 0.85 U	93000	< 3.3 U	-	< 3.7 U	< 6 U
MW-73S	MW-73S	D	10/26/2021	180-129230-1	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	75000	< 3 UJ	-	6.9 J	< 2.6 U
MW-73S	MW-73S	T	10/26/2021	180-129230-1	< 0.13 U	< 1.9 U	3300 J	< 3.7 U	< 0.91 U	74000	< 3 UJ	-	< 5.3 UJ	2.7 J
MW-73S	SSHS-MW-73S-04052024	T	4/5/2024	1801720031	0.15 BJ	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	93000	< 3.0 U	-	< 5.3 U	< 42 U
MW-74I	MW-74I	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2900 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
MW-74I	MW-74I	T	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	3000 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-74I	MW-74I	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2400 J	< 3.7 U	< 0.91 U	66000	< 3 U	-	< 5.3 U	2.6 J
MW-74I	MW-74I	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2800 J	< 3.7 U	< 0.91 U	73000	< 3 U	-	< 5.3 U	6.4 J
MW-74I	SSHS-MW-74I-04052024	T	4/5/2024	1801720031	0.16 BJ	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	85000	< 3.0 U	-	< 5.3 U	< 42 U
MW-74S	MW-74S	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-74S	MW-74S	T	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2800 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-74S	MW-74S	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2200 J	< 3.7 U	< 0.91 U	62000	< 3 U	-	< 5.3 U	4.6 J
MW-74S	MW-74S	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2600 J	< 3.7 U	< 0.91 U	70000	< 3 U	-	< 5.3 U	< 2.6 UJ
MW-74S	SSHS-DUP-05-04052024	T	4/5/2024	1801720031	0.15 BJ	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	80000	< 3.0 U	-	< 5.3 U	< 42 U
MW-74S	SSHS-MW-74S-04052024	T	4/5/2024	1801720031	0.16 BJ	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	81000	< 3.0 U	-	< 5.3 U	< 42 U
MW-75I	MW-75I	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	71000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-75I	MW-75I	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	73000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-75I	MW-75I	D	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	3000 J	5 J	< 0.91 U	69000	< 3 U	-	< 5.3 U	< 2.6 U
MW-75I	MW-75I	T	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	3100 J	5.6 J	< 0.91 U	70000	< 3 U	-	< 5.3 U	< 2.6 U
MW-75I	SSHS-MW-75I-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	69000	3.3 J	-	< 5.3 U	< 42 U
MW-75S	MW-75S	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	4200 J	< 3.6 U	< 0.85 U	84000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-75S	MW-75S	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	4300 J	< 3.6 U	< 0.85 U	84000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-75S	MW-75S	D	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	3200 J	< 3.7 U	< 0.91 U	74000	< 3 U	-	< 5.3 U	< 2.6 U
MW-75S	MW-75S	T	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	3200 J	< 3.7 U	< 0.91 U	74000	< 3 U	-	< 5.3 U	< 2.6 U
MW-75S	SSHS-MW-75S-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	110000	< 3.0 U	-	< 5.3 U	< 42 U
MW-76I	MW-76I	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
MW-76I	MW-76I	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	87000	3.5 J	-	< 3.7 U	< 6 U
MW-76I	DUP-03	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	78000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-76I	DUP-03	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-76I	MW-76I	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

					Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					2000	3	25	1000	3	5		50		200	300[1]	25	35000	300[1]
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report														
MW-76I	MW-76I	T	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	82000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	9 J
MW-76I	SSHS-MW-76I-04082024	T	4/8/2024	1801720412	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	MW-76S	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	130
MW-76S	MW-76S	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	140
MW-76S	MW-76S	D	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.3 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	54
MW-76S	MW-76S	T	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	82000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	54
MW-76S	SSHS-MW-76S-04082024	T	4/8/2024	1801720411	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	85000	< 3.1 U	< 3.4 U	2.6 J	< 72 U	9.7 J	13000	< 2.4 U
MW-76S	SSHS-MW-76S-04222024	T	4/22/2024	1801730541	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	91000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	14000	4.3 J
MW-77I	MW-77I	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	98 J	< 0.33 U	< 0.28 U	76000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	19
MW-77I	MW-77I	T	9/10/2021	180-126939-1	220	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	76000	< 1.9 U	< 0.55 U	< 9.1 U	420	< 2.9 U	12000	36
MW-77I	MW-77I	D	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	97 J	< 1.5 U	< 0.3 U	75000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	< 2.4 U
MW-77I	MW-77I	T	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	96 J	< 1.5 U	< 0.3 U	72000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	5.2 J
MW-77I	SSHS-MW-77I-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	99 J	< 1.5 U	< 0.30 U	78000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	12000	2.8 J
MW-77S	MW-77S	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	98 J	< 0.33 U	< 0.28 U	76000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	30
MW-77S	MW-77S	T	9/10/2021	180-126939-1	200	< 3.4 U	< 4.1 U	98 J	< 0.33 U	< 0.28 U	77000	< 1.9 U	0.6 J	< 9.1 U	< 89 U	< 2.9 U	12000	34
MW-77S	MW-77S	D	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	91 J	< 1.5 U	< 0.3 U	72000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	40 J
MW-77S	MW-77S	T	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	91 J	< 1.5 U	< 0.3 U	72000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000	17 J
MW-77S	SSHS-MW-77S-04042024	T	4/4/2024	1801719081	< 110 U	< 6.2 U	< 8.3 U	94 J	< 1.5 U	< 0.30 U	74000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	12000	13 J
MW-78I	MW-78I	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	0.71 J	< 9.1 U	< 89 U	< 2.9 U	14000	45
MW-78I	MW-78I	T	9/10/2021	180-126939-1	100 J	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 UJ	< 9.1 U	210	< 2.9 U	14000	48
MW-78I	MW-78I	D	11/2/2021	180-129534-1	68 J	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.3 U	87000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	8.6 J
MW-78I	MW-78I	T	11/2/2021	180-129534-1	< 41 UJ	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.3 U	87000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	8.6 J
MW-78I	SSHS-MW-78I-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	85000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	11	14000	8.3 J
MW-78S	DUP-5	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	8.5 J
MW-78S	DUP-5	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	8.7 J
MW-78S	MW-78S	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	8.5 J
MW-78S	MW-78S	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	13 J
MW-78S	MW-78S	D	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.3 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	< 2.4 U
MW-78S	MW-78S	T	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.3 U	85000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	< 2.4 U
MW-78S	SSHS-MW-78S-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	78000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	9.9 J	14000	< 2.4 U
MW-79I	MW-79I	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	92000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	41
MW-79I	MW-79I	T	9/10/2021	180-126939-1	120 J	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	92000	< 1.9 U	0.76 J	< 9.1 U	220	< 2.9 U	15000	50
MW-79I	DUP-04	D	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.3 U	90000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	2.4 J
MW-79I	DUP-04	T	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.3 U	92000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	7.7 J
MW-79I	MW-79I	D	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.3 U	93000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	2.4 J
MW-79I	MW-79I	T	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.3 U	92000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	14000	8.3 J
MW-79I	SSHS-MW-79I-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	92000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	10	14000	8.9 J
MW-79S	MW-79S	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	85
MW-79S	MW-79S	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	0.58 J	< 9.1 U	< 89 U	< 2.9 U	16000	87
MW-79S	MW-79S	D	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.3 U	110000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	16000	3 J
MW-79S	MW-79S	T	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.3 U	100000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	16000	6.8 J
MW-79S	SSHS-DUP-06-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	97000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	11	15000	< 2.4 U
MW-79S	SSHS-MW-79S-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	96000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	9.9 J	15000	4.8 J
MW-81I	MW-81I	D	7/16/2021	180-124628-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	23 J
MW-81I	MW-81I	T	7/16/2021	180-124628-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	91000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	14 J
MW-81I	MW-81I	D	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
MW-81I	MW-81I	T	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-81I	SSHS-MW-81I-04262024	T	4/26/2024	1801731401	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	15000	< 2.4 U
MW-82S	DUP-3	D	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	1.7 J	< 9.1 U	1700 J	< 2.9 U	13000	920
MW-82S	DUP-3	T	9/7/2021	180-126846-1	< 53 UJ	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	96000	< 1.9 U	1.6 J	< 9.1 U	2300 J	3.1 J	12000	990 J
MW-82S	MW-82S	D	9/7/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	99 J	< 0.33 U	< 0.28 U	90000	< 1.9 U	1.5 J	< 9.1 U	1200 J	< 2.9 U	12000	1000 J
MW-82S	MW-82S	T	9/7/2021	180-126846-1	81 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	0.68 J	< 9.1 U	330 J	< 2.9 UJ	12000	510 J
MW-82S	MW-82S	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	100 J	< 1.5 U	< 0.3 U	87000	< 1.6 U	< 1.9 U	< 2.2 U	620	< 4.4 U	12000	690
MW-82S	MW-82S	T	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	100 J	< 1.5 U	< 0.3 U	90000	< 1.6 U	< 1.9 U	< 2.2 U	1600	< 4.4 U	12000	790
MW-82S	SSHS-MW-82S-05012024	T	5/1/2024	1801733271	< 110 U	< 6.2 UT	< 8.3 U	140 JT	< 1.5 U	< 0.30 U	96000	< 3.1 U	< 3.4 U	< 2.2 U	750 B	< 4.4 U	13000	680
MW-83I	MW-83I	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	80 J	< 0.33 U	< 0.28 U	64000	< 1.9 U	0.56 J	< 9.1 U	< 89 U	< 2.9 U	10000	3.3 J
MW-83I	MW-83I	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	82 J	< 0.33 U	< 0.28 U	65000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	10000	3.6 J
MW-83I	MW-83I	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	73 J	< 1.5 U	< 0.3 U	58000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9200	< 2.4 U
MW-83I	MW-83I	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	77 J	< 1.5 U	< 0.3 U	62000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9800	< 2.4 U
MW-83I	SSHS-MW-83I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	83 J	< 1.5 U	< 0.30 U	65000	< 3.1 U	< 3.4 U	7.9 J	< 72 U	< 4.4 U	10000	< 2.4 U
MW-83S	MW-83S	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	79 J	< 0.33 U	< 0.28 U	60000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9500	18
MW-83S	MW-83S	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	80 J	< 0.33 U	< 0.28 U	62000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9800	21
MW-83S	MW-83S	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	74 J	< 1.5 U	< 0.3 U	58000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9100	< 2.4 U
MW-83S	MW-83S	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	72 J	< 1.5 U	< 0.3 U	54000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	8500	7.1 J
MW-83S	SSHS-MW-83S-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	77 J	< 1.5 U	< 0.30 U	60000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	9500	< 2.4 U
MW-84S	MW-84S	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	100 J	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
MW-84S	MW-84S	T	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	100 J	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
MW-84S	MW-84S	D	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	96 J	< 1.5 U	< 0.3 U	83000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	< 2.4 U
MW-84S	MW-84S	T	10/27/2021	180-129155-1	< 41 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.3 U	91000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	< 2.4 U
MW-84S	SSHS-DUP-07-04152024	T	4/15/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	97 J	< 1.5 U	< 0.30 U	85000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	13000	< 2.4 U
MW-84S	SSHS-MW-84S-04152024	T	4/15/2024	1801726651	< 110 U	< 6.2 U	< 8.3 U	99 J	< 1.5 U	< 0.30 U	85000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	13000	< 2.4 U
MW-85I	MW-85I	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	120 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	18
MW-85I	MW-85I	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	130 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	140	< 2.9 U	14000	31
MW-85I	MW-85I	D	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	0.59 J	< 9.1 U	< 89 U	< 2.9 U	13000	4.9 J
MW-85I	MW-85I	T	9/2/2021	180-126608-1	110 J	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	0.66 J	< 9.1 U	190	< 2.9 U	14000	15
MW-85I	SSHS-MW-85I-04222024	T	4/22/2024	1801730541	180 J	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	87000	3.9 J	< 3.4 U	< 2.2 U	310	< 4.4 U	14000	17
MW-86I	MW-86I	D	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	23
MW-86I	MW-86I	T	7/13/2021	180-124378-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	30
MW-86I	MW-86I	D	9/1/2021	180-126593-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	80000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	3.2 J
MW-86I	MW-86I	T	9/1/2021	180-126593-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	7.6 J
MW-86I	SSHS-MW-86I-04042024	T	4/4/2024	1801719081	280	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	88000	< 3.1 U	< 3.4 U	< 2.2 U	460	14	15000	43
MW-87I	MW-87I	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	8.9 J	87 J	< 0.33 U	< 0.28 U	71000	2 J	1.8 J	< 9.1 U	150	< 2.9 U	11000	350
MW-87I	MW-87I	T	7/14/2021	180-124487-1	130 J	< 3.4 U	9.6 J	84 J	< 0.33 U	< 0.28 U	68000	2.6 J	1.6 J	< 9.1 U	400	< 2.9 U	11000	340
MW-87I	MW-87I	D	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	1.3 J	< 9.1 U	260	< 2.9 U	13000	630
MW-87I	MW-87I	T	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	1.4 J	< 9.1 U	280	< 2.9 U	13000	600
MW-87I	SSHS-MW-87I-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	13000	23
MW-88I	MW-88I	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	120 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	17
MW-88I	MW-88I	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	110 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	0.58 J	< 9.1 U	< 89 U	< 2.9 U	15000	18
MW-88I	MW-88I	D	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	80000	< 1.9 U	0.61 J	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
MW-88I	MW-88I	T	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	79000	< 1.9 U	< 0.55 UJ	< 9.1 U	90 J	< 2.9 U	14000	19
MW-88I	SSHS-MW-88I-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	890	12	15000	200
MW-88S	MW-88S	D	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	17 J	< 0.33 U	< 0.28 U	380000	< 1.9 U	0.74 J	< 9.1 U	800	< 2.9 UJ	20000	2100
MW-88S	MW-88S	T	7/15/2021	180-124580-1	< 53 U	< 3.4 U	< 4.1 UJ	19 J	< 0.33 U	< 0.28 U	400000	< 1.9 U	1.1 J	< 9.1 U	7300 J	3.2 J	20000	2300
MW-88S	MW-88S	D	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	15 J	< 0.33 U	< 0.28 U	300000	< 1.9 U	0.72 J	< 9.1 U	1700	< 2.9 U	18000	1600
MW-88S	MW-88S	T	9/2/2021	180-126608-1	< 53 U	< 3.4 U	< 4.1 U	14 J	< 0.33 U	< 0.28 U	310000	< 1.9 U	0.83 J	< 9.1 U	1900	< 2.9 U	18000	1600
MW-88S	SSHS-MW-88S-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	< 27 U	< 1.5 U	< 0.30 U	500000	< 3.1 U	< 3.4 U	< 2.2 U	4600	14	29000	1800
MW-89I	MW-89I	D	7/12/2021	180-124354-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	3.8 J	13000	25
MW-89I	MW-89I	T	7/12/2021	180-124354-1	80 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	130	< 2.9 UJ	13000	32
MW-89I	MW-89I	D	9/1/2021	180-126593-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	6.9 J
MW-89I	MW-89I	T	9/1/2021	180-126593-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	24
MW-89I	SSHS-MW-89I-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	93000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	13	14000	2.8 J
MW-89S	MW-89S	D	7/12/2021	180-124354-1	< 53 U	< 3.4 U	< 4.1 U	92 J	< 0.33 U	< 0.28 U	81000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	12 J
MW-89S	MW-89S	T	7/12/2021	180-124354-1	82 J	< 3.4 U	< 4.1 U	96 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	190	< 2.9 U	13000	24
MW-89S	MW-89S	D	9/1/2021	180-126593-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	3.3 J
MW-89S	MW-89S	T	9/1/2021	180-126593-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	82000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	3.2 J
MW-89S	SSHS-MW-89S-04302024	T	4/30/2024	1801733271	250	< 6.2 UT	< 8.3 U	120 JT	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	360 B	< 4.4 U	14000	350
MW-8I	MW-8I	D	7/1/2021	180-123971-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	61
MW-8I	MW-8I	T	7/1/2021	180-123971-1	140 J	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	280 J	< 2.9 U	13000	76
MW-8I	DUP-1	D	8/30/2021	180-126485-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	90000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	11 J
MW-8I	DUP-1	T	8/30/2021	180-126485-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	14 J
MW-8I	MW-8I	D	8/30/2021	180-126485-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	11 J
MW-8I	MW-8I	T	8/30/2021	180-126485-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	20 J
MW-8I	SSHS-MW-8I-04302024	T	4/30/2024	1801733271	120 J	< 6.2 UT	< 8.3 U	150 JT	< 1.5 U	< 0.30 U	90000	< 3.1 U	< 3.4 U	< 2.2 U	230 B	< 4.4 U	15000	52
MW-8S	MW-8S	T	2/18/2021	180-117476-1	< 53 U	< 3.4 U	4.3 J	130 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	870	< 2.9 U	14000	370
MW-8S	MW-8S	D	7/12/2021	180-124354-1	< 53 U	< 3.4 U	< 4.1 U	49 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	1000	< 2.9 U	13000	470
MW-8S	MW-8S	T	7/12/2021	180-124354-1	< 53 U	< 3.4 U	4.6 J	49 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	1400	3.3 J	13000	500
MW-90I	MW-90I	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	85 J	< 0.33 U	< 0.28 U	78000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	69
MW-90I	MW-90I	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	84 J	< 0.33 U	< 0.28 U	78000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	94
MW-90I	MW-90I	D	10/28/2021	180-129230-1	< 41 U	< 6.2 U	< 8.3 U	79 J	< 1.5 U	< 0.3 U	64000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	10000	33
MW-90I	MW-90I	T	10/28/2021	180-129230-1	400	< 6.2 UJ	< 8.3 U	79 J	< 1.5 U	< 0.3 U	61000	< 1.6 U	< 1.9 U	< 2.2 U	540	< 4.4 U	9600	130
MW-90I	SSHS-MW-90I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	94 J	< 1.5 U	< 0.30 U	82000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	12000	10 J
MW-90S	MW-90S	D	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	59000	< 1.9 U	0.72 J	< 9.1 U	820	< 2.9 U	9100	930
MW-90S	MW-90S	T	9/8/2021	180-126846-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	60000	< 1.9 U	0.86 J	< 9.1 U	900	< 2.9 U	9300	980

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Thallium (Method 6010)	Thallium (Method 6020)	Vanadium	Zinc
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.7	100		10	50		0.5[2]	0.5[2]		2000
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-76I	MW-76I	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-76I	SSHS-MW-76I-04082024	T	4/8/2024	1801720412	-	-	-	-	-	-	< 0.47 U	-	-	-
MW-76S	MW-76S	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	82000	< 3.3 U	-	< 3.7 U	< 6 U
MW-76S	MW-76S	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	84000	< 3.3 U	-	< 3.7 U	< 6 U
MW-76S	MW-76S	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	81000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-76S	MW-76S	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-76S	SSHS-MW-76S-04082024	T	4/8/2024	1801720411	< 0.13 U	< 3.5 U	3200 J	< 3.7 UT	< 0.91 U	92000	< 3.0 U	-	< 5.3 U	< 42 U
MW-76S	SSHS-MW-76S-04222024	T	4/22/2024	1801730541	< 0.13 U	< 3.5 U	3700 J	< 3.7 UT	< 0.91 U	110000	< 3.0 U	-	< 5.3 U	< 42 U
MW-77I	MW-77I	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3100 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-77I	MW-77I	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	< 6 U
MW-77I	MW-77I	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3400 J	< 3.7 U	< 0.91 U	71000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-77I	MW-77I	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	72000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-77I	SSHS-MW-77I-04042024	T	4/4/2024	1801719081	0.27 B	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	76000	< 3.0 U	-	< 5.3 U	< 42 U
MW-77S	MW-77S	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	5.3 J	< 6 U
MW-77S	MW-77S	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 UJ	< 6 U
MW-77S	MW-77S	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	74000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-77S	MW-77S	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	73000	3.1 J	-	7 J	< 2.6 U
MW-77S	SSHS-MW-77S-04042024	T	4/4/2024	1801719081	0.25 B	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	80000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-78I	MW-78I	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-78I	MW-78I	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-78I	MW-78I	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3700 J	5.6 J	< 0.91 U	77000	< 3 U	-	< 5.3 U	5.4 J
MW-78I	MW-78I	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3500 J	< 3.7 UJ	< 0.91 U	77000	< 3 U	-	< 5.3 U	< 2.6 UJ
MW-78I	SSHS-MW-78I-04052024	T	4/5/2024	1801720031	0.15 BJ	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	77000	3.2 BJ	-	< 5.3 U	< 42 U
MW-78S	DUP-5	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-78S	DUP-5	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
MW-78S	MW-78S	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
MW-78S	MW-78S	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-78S	MW-78S	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3800 J	< 3.7 U	< 0.91 U	78000	< 3 U	-	< 5.3 U	5.1 J
MW-78S	MW-78S	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3800 J	< 3.7 U	< 0.91 U	78000	< 3 U	-	< 5.3 U	5 J
MW-78S	SSHS-MW-78S-04052024	T	4/5/2024	1801720031	0.16 BJ	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	80000	< 3.0 U	-	< 5.3 U	< 42 U
MW-79I	MW-79I	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3900 J	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 6 U
MW-79I	MW-79I	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3900 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
MW-79I	DUP-04	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3700 J	3.9 J	< 0.91 U	92000	< 3 U	-	< 5.3 U	< 2.6 U
MW-79I	DUP-04	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3800 J	< 3.7 UJ	< 0.91 U	94000	< 3 U	-	< 5.3 U	< 2.6 U
MW-79I	MW-79I	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3900 J	< 3.7 UJ	< 0.91 U	95000	< 3 U	-	< 5.3 U	< 2.6 U
MW-79I	MW-79I	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3800 J	< 3.7 U	< 0.91 U	94000	< 3 U	-	< 5.3 U	< 2.6 U
MW-79I	SSHS-MW-79I-04052024	T	4/5/2024	1801720031	0.18 BJ	< 3.5 U	3600 J	< 3.7 U	< 0.91 U	91000	< 3.0 U	-	< 5.3 U	< 42 U
MW-79S	MW-79S	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	5500	< 3.6 U	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
MW-79S	MW-79S	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	5400	< 3.6 U	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
MW-79S	MW-79S	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	5600	< 3.7 U	< 0.91 U	87000	< 3 U	-	< 5.3 U	< 2.6 U
MW-79S	MW-79S	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	5300	4.1 J	< 0.91 U	86000	< 3 U	-	< 5.3 U	< 2.6 U
MW-79S	SSHS-DUP-06-04052024	T	4/5/2024	1801720031	0.16 BJ	< 3.5 U	3900 J	< 3.7 U	< 0.91 U	88000	< 3.0 U	-	< 5.3 U	< 42 U
MW-79S	SSHS-MW-79S-04052024	T	4/5/2024	1801720031	< 0.13 U	< 3.5 U	3800 J	< 3.7 U	< 0.91 U	86000	4.6 BJ	-	< 5.3 U	< 42 U
MW-81I	MW-81I	D	7/16/2021	180-124628-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	90000	< 3.3 U	-	< 3.7 U	< 6 U
MW-81I	MW-81I	T	7/16/2021	180-124628-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	92000	< 3.3 U	-	< 50 U	< 6 U
MW-81I	MW-81I	D	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	95000	< 3.3 U	-	< 3.7 U	< 6 U
MW-81I	MW-81I	T	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	97000	< 3.3 U	-	< 3.7 U	< 6 U
MW-81I	SSHS-MW-81I-04262024	T	4/26/2024	1801731401	< 0.13 U	< 3.5 U	3600 J	< 3.7 U	< 0.91 U	93000	< 3.0 U	-	< 5.3 U	< 42 U
MW-82S	DUP-3	D	9/7/2021	180-126846-1	< 0.13 U	2.8 J	4400 J	< 3.6 U	< 0.85 U	95000	< 3.3 U	-	< 3.7 U	< 6 U
MW-82S	DUP-3	T	9/7/2021	180-126846-1	< 0.13 U	3.5 J	4500 J	< 3.6 U	< 0.85 U	96000	< 3.3 U	-	< 3.7 U	< 6 U
MW-82S	MW-82S	D	9/7/2021	180-126846-1	< 0.13 U	2.9 J	4200 J	< 3.6 U	< 0.85 U	90000	< 3.3 U	-	< 3.7 U	< 6 U
MW-82S	MW-82S	T	9/7/2021	180-126846-1	< 0.13 U	< 1.5 UJ	4100 J	< 3.6 U	< 0.85 U	83000	< 3.3 U	-	< 3.7 U	< 6 U
MW-82S	MW-82S	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	4000 J	< 3.7 U	< 0.91 U	85000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-82S	MW-82S	T	10/27/2021	180-129230-1	< 0.13 U	2.3 J	4100 J	< 3.7 U	< 0.91 U	90000	< 3 UJ	-	< 5.3 U	2.8 J
MW-82S	SSHS-MW-82S-05012024	T	5/1/2024	1801733271	< 0.13 U	3.7 J	4500 J	< 3.7 UT	< 0.91 U	120000	< 3.0 U	-	< 5.3 U	< 42 U
MW-83I	MW-83I	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	85000	< 3.3 U	-	< 3.7 U	< 6 U
MW-83I	MW-83I	T	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2700 J	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 6 U
MW-83I	MW-83I	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2400 J	< 3.7 U	< 0.91 U	72000	< 3 U	-	< 5.3 U	< 2.6 U
MW-83I	MW-83I	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	2500 J	< 3.7 U	< 0.91 U	77000	< 3 U	-	< 5.3 U	< 2.6 U
MW-83I	SSHS-MW-83I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	86000	< 3.0 U	-	< 5.3 U	< 42 U
MW-83S	MW-83S	D	9/8/2021	180-126846-1	< 0.13 U	9.3 J	2600 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
MW-83S	MW-83S	T	9/8/2021	180-126846-1	< 0.13 U	10 J	2800 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-83S	MW-83S	D	10/27/2021	180-129155-1	< 0.13 U	6.9 J	2500 J	< 3.7 U	< 0.91 U	69000	< 3 U	-	< 5.3 U	< 2.6 U
MW-83S	MW-83S	T	10/27/2021	180-129155-1	< 0.13 U	6.6 J	2400 J	< 3.7 U	< 0.91 U	65000	< 3 U	-	< 5.3 U	< 2.6 U
MW-83S	SSHS-MW-83S-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	< 2600 U	< 3.7 U	< 0.91 U	85000	< 3.0 U	-	< 5.3 U	< 42 U
MW-84S	MW-84S	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	4000 J	4 J	< 0.85 U	81000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-84S	MW-84S	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 UJ	< 0.85 U	80000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-84S	MW-84S	D	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	3900 J	< 3.7 U	< 0.91 U	70000	< 3 U	-	< 5.3 U	< 2.6 U
MW-84S	MW-84S	T	10/27/2021	180-129155-1	< 0.13 U	< 1.9 U	4100 J	< 3.7 U	< 0.91 U	77000	< 3 U	-	< 5.3 U	< 2.6 U
MW-84S	SSHS-DUP-07-04152024	T	4/15/2024	1801726651	< 0.13 U	< 3.5 U	3200 J	< 3.7 U	< 0.91 U	81000	< 3.0 U	-	< 5.3 U	< 42 U
MW-84S	SSHS-MW-84S-04152024	T	4/15/2024	1801726651	< 0.13 U	< 3.5 U	3200 J	< 3.7 U	< 0.91 U	81000	< 3.0 U	-	< 5.3 U	< 42 U
MW-85I	MW-85I	D	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	71000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-85I	MW-85I	T	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	72000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-85I	MW-85I	D	9/2/2021	180-126608-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
MW-85I	MW-85I	T	9/2/2021	180-126608-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
MW-85I	SSHS-MW-85I-04222024	T	4/22/2024	1801730541	< 0.13 U	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	75000	< 3.0 U	-	< 5.3 U	< 42 U
MW-86I	MW-86I	D	7/13/2021	180-124378-1	< 0.13 U	1.9 J	3300 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-86I	MW-86I	T	7/13/2021	180-124378-1	< 0.13 U	2 J	3200 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
MW-86I	MW-86I	D	9/1/2021	180-126593-1	< 0.13 U	1.7 J	3000 J	3.6 J	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	< 6 U
MW-86I	MW-86I	T	9/1/2021	180-126593-1	< 0.13 U	1.5 J	3100 J	< 3.6 U	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
MW-86I	SSHS-MW-86I-04042024	T	4/4/2024	1801719081	0.26 B	6.0 J	3500 J	< 3.7 U	< 0.91 U	80000	< 3.0 U	-	< 5.3 U	< 42 U
MW-87I	MW-87I	D	7/14/2021	180-124487-1	< 0.13 U	5.1 J	78000	< 3.6 U	< 0.85 U	26000 J	3.3 J	-	< 3.7 U	< 6 U
MW-87I	MW-87I	T	7/14/2021	180-124487-1	< 0.13 U	5 J	77000	< 3.6 U	< 0.85 U	17000 J	< 3.3 UJ	-	6.9 J	12 J
MW-87I	MW-87I	D	9/2/2021	180-126608-1	< 0.13 U	2.5 J	24000	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-87I	MW-87I	T	9/2/2021	180-126608-1	< 0.13 U	2.2 J	22000	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
MW-87I	SSHS-MW-87I-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3700 J	4.2 J	< 0.91 U	83000	< 3.0 U	-	< 5.3 U	< 42 U
MW-88I	MW-88I	D	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	80000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-88I	MW-88I	T	7/15/2021	180-124580-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	78000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-88I	MW-88I	D	9/2/2021	180-126608-1	< 0.13 U	< 1.5 U	3100 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-88I	MW-88I	T	9/2/2021	180-126608-1	< 0.13 U	< 1.5 U	3100 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-88I	SSHS-MW-88I-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	82000	< 3.0 U	-	< 5.3 U	< 42 U
MW-88S	MW-88S	D	7/15/2021	180-124580-1	< 0.13 U	21 J	3300 J	4.7 J	< 0.85 U	56000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-88S	MW-88S	T	7/15/2021	180-124580-1	< 0.13 U	24 J	3300 J	< 3.6 UJ	< 0.85 U	50000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-88S	MW-88S	D	9/2/2021	180-126608-1	< 0.13 U	8.4 J	3300 J	4 J	< 0.85 U	62000	< 3.3 U	-	< 3.7 U	< 6 U
MW-88S	MW-88S	T	9/2/2021	180-126608-1	< 0.13 U	8.4 J	3300 J	6.3 J	< 0.85 U	60000	< 3.3 U	-	< 3.7 U	< 6 U
MW-88S	SSHS-MW-88S-04112024	T	4/11/2024	1801722811	< 0.13 U	35 J	4200 J	< 3.7 U	< 0.91 U	83000	< 3.0 U	-	< 5.3 U	< 42 U
MW-89I	MW-89I	D	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	93000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89I	MW-89I	T	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	96000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89I	MW-89I	D	9/1/2021	180-126593-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89I	MW-89I	T	9/1/2021	180-126593-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	82000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89I	SSHS-MW-89I-04052024	T	4/5/2024	1801720031	0.19 BJ	< 3.5 U	3600 J	< 3.7 U	< 0.91 UT	100000	< 3.0 U	-	< 5.3 U	< 42 U
MW-89S	MW-89S	D	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	82000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89S	MW-89S	T	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	85000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89S	MW-89S	D	9/1/2021	180-126593-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	91000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89S	MW-89S	T	9/1/2021	180-126593-1	< 0.13 U	< 1.5 U	3100 J	3.7 J	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
MW-89S	SSHS-MW-89S-04302024	T	4/30/2024	1801733271	< 0.13 U	3.9 J	3900 J	< 3.7 UT	< 0.91 U	99000	< 3.0 U	-	< 5.3 U	< 42 U
MW-8I	MW-8I	D	7/1/2021	180-123971-1	< 0.13 U	< 1.5 U	3300 J	5.5 J	< 0.85 U	83000	3.6 J	-	< 3.7 U	< 6 U
MW-8I	MW-8I	T	7/1/2021	180-123971-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 UJ	< 0.85 U	84000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-8I	DUP-1	D	8/30/2021	180-126485-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	89000	< 3.3 U	-	< 3.7 U	< 6 U
MW-8I	DUP-1	T	8/30/2021	180-126485-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 6 U
MW-8I	MW-8I	D	8/30/2021	180-126485-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
MW-8I	MW-8I	T	8/30/2021	180-126485-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
MW-8I	SSHS-MW-8I-04302024	T	4/30/2024	1801733271	< 0.13 U	< 3.5 U	3800 J	< 3.7 UT	< 0.91 U	100000	< 3.0 U	-	< 5.3 U	< 42 U
MW-8S	MW-8S	T	2/18/2021	180-117476-1	< 0.13 U	2 J	3000 J	3.8 J	< 0.85 U	210000	< 3.3 U	-	< 3.7 U	< 6 U
MW-8S	MW-8S	D	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	2300 J	< 3.6 U	< 0.85 U	100000	< 3.3 U	-	< 3.7 U	< 6 U
MW-8S	MW-8S	T	7/12/2021	180-124354-1	< 0.13 U	< 1.5 U	2400 J	< 3.6 U	< 0.85 U	98000	< 3.3 U	-	< 3.7 U	< 6 U
MW-90I	MW-90I	D	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2800 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-90I	MW-90I	T	9/8/2021	180-126846-1	< 0.13 U	< 1.5 U	2800 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
MW-90I	MW-90I	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	2900 J	< 3.7 U	< 0.91 U	85000	3.2 J	-	< 5.3 U	< 2.6 U
MW-90I	MW-90I	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	2900 J	< 3.7 U	< 0.91 U	81000	< 3 UJ	-	< 5.3 U	3.2 J
MW-90I	SSHS-MW-90I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3000 J	< 3.7 U	< 0.91 U	88000	< 3.0 U	-	< 5.3 U	< 42 U
MW-90S	MW-90S	D	9/8/2021	180-126846-1	< 0.13 U	6.8 J	3300 J	< 3.6 U	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
MW-90S	MW-90S	T	9/8/2021	180-126846-1	< 0.13 U	7.8 J	3400 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U

DRAFT

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

					Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Cobalt	Copper	Iron	Lead	Magnesium	Manganese
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					2000	3	25	1000	3	5		50		200	300[1]	25	35000	300[1]
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report														
MW-90S	MW-90S	D	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	120 J	< 1.5 U	< 0.3 U	63000	< 1.6 U	< 1.9 U	< 2.2 U	130	< 4.4 U	9900	510
MW-90S	MW-90S	T	10/28/2021	180-129230-1	80 J	< 6.2 UJ	< 8.3 U	130 J	< 1.5 U	< 0.3 U	64000	< 1.6 U	< 1.9 U	< 2.2 U	490	< 4.4 U	10000	590
MW-90S	SSHS-MW-90S-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	65000	< 3.1 U	< 3.4 U	< 2.2 U	91 J	< 4.4 U	10000	200
MW-91I	MW-91I	D	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	0.58 J	< 9.1 U	< 89 U	< 2.9 U	13000	230
MW-91I	MW-91I	T	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	13000	240
MW-91I	MW-91I	D	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	97 J	< 1.5 U	< 0.3 U	80000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	150
MW-91I	MW-91I	T	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	96 J	< 1.5 U	< 0.3 U	79000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	170
MW-91I	SSHS-MW-91I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	88 J	< 4.4 U	13000	41
MW-91S	MW-91S	D	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	81 J	< 0.33 U	< 0.28 U	78000	< 1.9 U	0.65 J	< 9.1 U	< 89 U	< 2.9 U	11000	740
MW-91S	MW-91S	T	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	81 J	< 0.33 U	< 0.28 U	77000	< 1.9 U	< 0.55 UJ	< 9.1 U	100	< 2.9 U	11000	720
MW-91S	MW-91S	D	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	89 J	< 1.5 U	< 0.3 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	220
MW-91S	MW-91S	T	11/2/2021	180-129534-1	< 41 U	< 6.2 U	< 8.3 U	90 J	< 1.5 U	< 0.3 U	84000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	240
MW-91S	SSHS-MW-91S-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	89 J	< 1.5 U	< 0.30 U	89000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	13000	240
MW-92I	MW-92I	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	0.79 J	< 9.1 U	< 89 U	< 2.9 U	13000	16
MW-92I	MW-92I	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	13000	18
MW-92I	MW-92I	D	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	110 J	< 1.5 U	< 0.3 U	85000	< 1.6 U	< 1.9 U	2.5 J	< 72 U	< 4.4 U	13000	< 2.4 U
MW-92I	MW-92I	T	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	110 J	< 1.5 U	< 0.3 U	84000	< 1.6 U	< 1.9 U	< 2.2 UJ	< 72 U	< 4.4 U	13000	< 2.4 U
MW-92I	SSHS-MW-92I-04082024	T	4/8/2024	1801720411	< 110 U	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	88 BJ	11	13000	7.0 J
MW-92S	MW-92S	D	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	96 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	6.6 J
MW-92S	MW-92S	T	9/10/2021	180-126939-1	< 53 U	< 3.4 U	< 4.1 U	96 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	7.7 J
MW-92S	MW-92S	D	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	96 J	< 1.5 U	< 0.3 U	81000	< 1.6 U	< 1.9 U	2.3 J	< 72 U	< 4.4 U	12000	< 2.4 U
MW-92S	MW-92S	T	10/28/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	95 J	< 1.5 U	< 0.3 U	80000	< 1.6 U	< 1.9 U	< 2.2 UJ	< 72 U	< 4.4 U	12000	< 2.4 U
MW-92S	SSHS-MW-92S-04052024	T	4/5/2024	1801720031	< 110 U	< 6.2 U	< 8.3 U	95 J	< 1.5 U	< 0.30 U	82000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	12	13000	< 2.4 U
MW-93I	DUP-4	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	94 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	56
MW-93I	DUP-4	T	9/9/2021	180-126905-1	< 53 U	3.7 J	< 4.1 U	93 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	50
MW-93I	MW-93I	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	93 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	53
MW-93I	MW-93I	T	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	92 J	< 0.33 U	< 0.28 U	84000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	53
MW-93I	MW-93I	D	10/29/2021	180-129376-1	< 41 U	< 6.2 U	< 8.3 U	88 J	< 1.5 U	< 0.3 U	76000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	12000	13 J
MW-93I	MW-93I	T	10/29/2021	180-129376-1	< 41 U	< 6.2 U	< 8.3 U	94 J	< 1.5 U	< 0.3 U	80000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	13000	14 J
MW-93I	SSHS-DUP-08-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	92 J	< 1.5 U	< 0.30 U	82000	< 3.1 U	< 3.4 U	< 2.2 U	940	11	13000	9.4 J
MW-93I	SSHS-MW-93I-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	92 J	< 1.5 U	< 0.30 U	83000	< 3.1 U	< 3.4 U	< 2.2 U	85 J	12	13000	4.4 J
MW-93S	MW-93S	D	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	70 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	10000	89
MW-93S	MW-93S	T	9/9/2021	180-126905-1	< 53 U	< 3.4 UJ	< 4.1 U	72 J	< 0.33 U	< 0.28 U	83000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	11000	89
MW-93S	MW-93S	D	10/29/2021	180-129376-1	52 J	< 6.2 U	< 8.3 U	68 J	< 1.5 U	< 0.3 U	76000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9700	86
MW-93S	MW-93S	T	10/29/2021	180-129376-1	42 J	< 6.2 U	< 8.3 U	64 J	< 1.5 U	< 0.3 U	72000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	9100	78
MW-93S	SSHS-MW-93S-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	81 J	< 1.5 U	< 0.30 U	87000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	15	12000	60
MW-94I	MW-94I	D	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	92 J	< 0.33 U	< 0.28 U	75000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	11000	370
MW-94I	MW-94I	T	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	90 J	< 0.33 U	< 0.28 U	74000	< 1.9 U	0.73 J	< 9.1 U	< 89 U	< 2.9 U	11000	350
MW-94I	MW-94I	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	86 J	< 1.5 U	< 0.3 U	70000 J	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	11000 J	220 J
MW-94I	MW-94I	T	10/27/2021	180-129230-1	170 J	< 6.2 UJ	< 8.3 U	20 J	< 1.5 U	< 0.3 U	10000 J	12	< 1.9 U	< 2.2 U	210	< 4.4 U	7600 J	52 J
MW-94I	SSHS-MW-94I-04112024	T	4/11/2024	1801722811	140 J	< 6.2 U	< 8.3 U	93 J	< 1.5 U	< 0.30 U	76000	< 3.1 U	< 3.4 U	< 2.2 U	230	12	12000	52
MW-94S	MW-94S	D	9/9/2021	180-126905-1	< 53 U	< 3.4 U	< 4.1 U	82 J	< 0.33 U	< 0.28 U	66000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	10000	< 2.7 U
MW-94S	MW-94S	T	9/9/2021	180-126905-1	89 J	< 3.4 U	< 4.1 U	81 J	< 0.33 U	< 0.28 U	65000	< 1.9 U	< 0.55 U	< 9.1 U	100	< 2.9 U	10000	4.4 J
MW-94S	MW-94S	D	10/27/2021	180-129230-1	< 41 U	< 6.2 UJ	< 8.3 U	73 J	< 1.5 U	< 0.3 U	57000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	8900	< 2.4 U
MW-94S	MW-94S	T	10/27/2021	180-129230-1	160 J	< 6.2 UJ	< 8.3 U	74 J	< 1.5 U	< 0.3 U	57000	< 1.6 U	< 1.9 U	< 2.2 U	120	< 4.4 U	8800	< 2.4 U
MW-94S	SSHS-MW-94S-04112024	T	4/11/2024	1801722811	< 110 U	< 6.2 U	< 8.3 U	79 J	< 1.5 U	< 0.30 U	64000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	11	10000	2.5 J
MW-95I	SSHS-MW-95I-01162024	T	1/16/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	100000	75	< 3.4 U	< 2.2 U	130	< 4.4 U	17000	< 2.4 U
MW-95I	SSHS-MW-95I-04112024	T	4/11/2024	1801722791	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	100000	4.6 J	< 3.4 U	< 2.2 U	< 72 U	13	16000	< 2.4 U
MW-95I	SSHS-MW-95I-09122023	T	9/12/2023	1801624601	< 47 U	< 7.5 U	4.9 J	150 J	< 0.60 U	< 0.45 U	97000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	16000	< 2.6 U
MW-95I	SSHS-MW-95I-11142023	T	11/14/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	110000	10	< 3.4 U	< 2.2 U	110 J+	< 4.4 U	18000	< 2.4 U
MW-95S	SSHS-MW-95S-01162024	T	1/16/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	17000	< 2.4 U
MW-95S	SSHS-MW-95S-04112024	T	4/11/2024	1801722791	< 110 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	110000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	17000	< 2.4 U
MW-95S	SSHS-MW-95S-09122023	T	9/12/2023	1801624601	< 47 U	< 7.5 U	5.6 J	150 J	< 0.60 U	< 0.45 U	98000	0.82 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	16000	< 2.6 U
MW-95S	SSHS-MW-95S-11142023	T	11/14/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	110000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	17000	< 2.4 U
MW-96	SSHS-MW-96-01172024	T	1/17/2024	1801682361	< 110 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	98000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	17000	< 2.4 U
MW-96	SSHS-MW-96-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	120 J	< 1.5 U	< 0.30 U	96000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	13	16000	< 2.4 U
MW-96	SSHS-MW-96-05022023	T	5/2/2023	1801559471	41 J	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	100000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	17000	10 J
MW-96	SSHS-MW-96-09152023	T	9/15/2023	1801625601	72 U	< 7.5 U	5.7 J	120 J	< 0.60 U	< 0.45 U	86000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	14000	< 2.6 U
MW-96	SSHS-MW-96-11142023	T	11/14/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	96000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	16000	< 2.4 U
MW-97	SSHS-MW-97-01172024	T	1/17/2024	1801682361	140 J	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	100000	3.7 J	< 3.4 U	< 2.2 U	530	< 4.4 U	15000	16
MW-97	SSHS-MW-97-04092024	T	4/9/2024	1801721201	< 110 U	< 6.2 U	< 8.3 U	93 J	< 1.5 U	< 0.30 U	95000	< 3.1 U	< 3.4 U	< 2.2 U	120	11	14000	11 J
MW-97	SSHS-MW-97-05022023	T	5/2/2023	1801559471	49 J	< 6.2 U	< 8.3 U	110 J	< 1.5 U	< 0.30 U	110000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	16000	130
MW-97	SSHS-MW-97-09152023	T	9/15/2023	1801625601	120 U	< 7.5 U	4.4 J	94 J	< 0.60 U	< 0.45 U	88000	< 0.76 U	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	13000	10 J
MW-97	SSHS-MW-97-11142023	T	11/14/2023	1801653531	< 110 U	< 6.2 U	< 8.3 U	100 J	< 1.5 U	< 0.30 U	110000	< 3.1 U	< 3.4 U	< 2.2 U	390 J+	< 4.4 U	16000	140
MW-98I	DUP-01	T	9/1/2022	1801438881	< 41 U	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	120000	< 1.6 U	< 1.9 U	< 2.2 U	< 72 U	< 4.4 U	20000	41
MW-98I	MW-98I	T	9/1/2022	1801438881	69 J	< 6.2 U	< 8.3 U	160 J	< 1.5 U	< 0.30 U	110000	< 1.6 U	< 1.9 U	< 2.2 U	100	< 4.4 U	19000	42
MW-98I	SSHS-MW-98I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	110000	< 3.1 U	< 3.4 U	< 2.2 U	630	< 4.4 U	18000	4.8 J
MW-98I	SSHS-MW-98I-09132023	T	9/13/2023	1801624611	220 J+	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 U	100000	< 0.76 U	< 0.75 U	< 3.5 U	280	< 2.8 U	17000	9.7 J
MW-98S	MW-98S	T	9/1/2022	1801438881	48 J	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	120000	< 1.6 U	< 1.9 U	< 2.2 U	100	< 4.4 U	19000	200
MW-98S	SSHS-MW-98S-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	140 J	< 1.5 U	< 0.30 U	120000	< 3.1 U	< 3.4 U	2.6 J	120	< 4.4 U	18000	9.8 J
MW-98S	SSHS-MW-98S-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	110 J	< 0.60 U	< 0.45 U	97000	0.78 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	16000	8.0 J
MW-99I	SSHS-MW-99I-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	150 J	< 1.5 U	< 0.30 U	100000	< 3.1 U	< 3.4 U	< 2.2 U	< 72 U	< 4.4 U	17000	< 2.4 U
MW-99I	SSHS-MW-99I-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 U	94000	1.3 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	16000	4.3 J
MW-99S	SSHS-MW-99S-04102024	T	4/10/2024	1801721871	< 110 U	< 6.2 U	< 8.3 U	130 J	< 1.5 U	< 0.30 U	120000	< 3.1 U	< 3.4 U	2.4 J	150	< 4.4 U	16000	3.7 J
MW-99S	SSHS-MW-99S-09132023	T	9/13/2023	1801624611	< 47 U	< 7.5 U	< 4.1 U	130 J	< 0.60 U	< 0.45 U	110000	3.1 J	< 0.75 U	< 3.5 U	< 83 U	< 2.8 U	17000	< 2.6 U
MW-9I	MW-9I	D	7/14/2021	180-124487-1	< 53 U	3.8 J	< 4.1 U	120 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	82
MW-9I	MW-9I	T	7/14/2021	180-124487-1	< 53 U	< 3.4 UJ	< 4.1 U	120 J	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	110
MW-9I	MW-9I	D	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	12 J
MW-9I	MW-9I	T	8/31/2021	180-126501-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	32
MW-9I	SSHS-MW-9I-04292024	T	4/29/2024	1801733271	130 J	< 6.2 UT	< 8.3 U	150 JT	< 1.5 U	< 0.30 U	90000	< 3.1 U	< 3.4 U	< 2.2 U	450 B	< 4.4 U	15000	280
MW-9S	MW-9	T	2/20/2021	180-117476-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	210000	< 1.9 U	0.64 J	< 9.1 U	370	< 2.9 U	19000	570
MW-9S	MW-9	D	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	71 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	3.2 J
MW-9S	MW-9	T	7/14/2021	180-124487-1	< 53 U	< 3.4 U	< 4.1 U	72 J	< 0.33 U	< 0.28 U	110000	< 1.9 U	< 0.55 U	< 9.1 U	110	< 2.9 U	13000	24 J
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	T	8/4/2021	1801253661	< 53 U	< 3.4 U	< 4.1 U	79 J	< 0.33 U	< 0.28 U	63000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	9800	< 2.7 U
SSHS-B2090A	SSHS-B2090A	D	5/22/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	98000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	16000	28
SSHS-B2090A	SSHS-B2090A	T	5/22/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	95000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	16000	28
SSHS-B2221	SSHS-B2221A	D	5/22/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	160000	210	< 0.55 U	11 J	88 J	< 2.9 U	22000	15
SSHS-B2221	SSHS-B2221A	T	5/22/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	160000	200	< 0.55 U	13 J	130	< 2.9 U	22000	17
SSHS-B23	B23	T	5/9/2000		-	-	25	736	-	-	-	86.9	-	156	-	181	-	-
SSHS-B2541	SSHS-B2541-GW	T	10/29/2018	180-83541-1	< 36 U	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	120000	1.3 J	0.75 J	20 J	< 31 U	< 2.9 U	14000	35
SSHS-B2542	SSHS-B2542-GW	T	10/29/2018	180-83541-1	26000	< 3.4 U	20	660	1.6 J	1.4 J	120000	41	22 J	470	38000	66	24000	1300
SSHS-B2542A	SSHS-B2542A	D	5/22/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	0.76 J	< 2.2 U	< 31 U	< 2.9 U	13000	97
SSHS-B2542A	SSHS-B2542A	T	5/22/2019	180-90525-1	< 36 U	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 UJ	< 2.2 U	< 31 U	< 2.9 U	14000	100
SSHS-B2543	SSHS-B2543-GW	T	10/30/2018	180-83544-1	1000	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	100000	1.2 J	1.1 J	3.9 J	1500	6 J	16000	140
SSHS-B2544	SSHS-B2544-GW	T	10/30/2018	180-83544-1	950	< 3.4 U	< 4.1 U	260	< 0.33 U	< 0.28 U	150000	2.1 J	1.2 J	6.7 J	4200	< 2.9 U	22000	1500
SSHS-B2629	SSHS-B2629	D	4/25/2019	180-89520-1	< 36 U	< 3.4 U	< 4.1 U	200	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 U	< 2.2 U	380	< 2.9 U	15000	340
SSHS-B2629	SSHS-B2629	T	4/25/2019	180-89520-1	< 36 U	< 3.4 U	< 4.1 U	200	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 U	< 2.2 U	400	< 2.9 U	15000	330
SSHS-B2722	SSHS-B2722	D	5/21/2019	180-90380-2	< 36 U	< 3.4 U	< 4.1 U	94 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	16000	13 J
SSHS-B2722	SSHS-B2722	T	5/21/2019	180-90380-2	93 J	< 3.4 U	< 4.1 U	95 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 U	2.5 J	130	< 2.9 U	16000	38
SSHS-B2752	SSHS-B2752	D	4/25/2019	180-89520-1	< 36 U	< 3.4 U	< 4.1 U	98 J,B	< 0.33 U	< 0.28 U	84000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	1.3 J,B
SSHS-B2752	SSHS-B2752	T	4/25/2019	180-89520-1	< 36 U	< 3.4 U	< 4.1 U	99 J,B	< 0.33 U	< 0.28 U	85000	< 0.78 U	< 0.55 U	3.5 J	< 31 U	< 2.9 U	13000	1.3 J,B
SSHS-B3200A	DUP-01	D	9/15/2019	180-95745-1	< 36 U	< 3.4 U	< 4.1 U	77 J	< 0.33 U	< 0.28 U	61000	1.3 J	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	9000	5.9 J
SSHS-B3200A	DUP-01	T	9/15/2019	180-95745-1	290 J	< 3.4 U	< 4.1 U	79 J	< 0.33 U	< 0.28 U	61000	0.91 J	< 0.55 U	< 2.2 UJ	470	< 2.9 U	9000	28
SSHS-B3200A	SSHS-B3200a	D	9/15/2019	180-95745-1	< 36 U	< 3.4 U	< 4.1 U	75 J	< 0.33 U	< 0.28 U	60000	1 J	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	8900	6 J
SSHS-B3200A	SSHS-B3200a	T	9/15/2019	180-95745-1	400 J	< 3.4 U	< 4.1 U	80 J	< 0.33 U	< 0.28 U	61000	1.3 J	< 0.55 U	2.2 J	610	< 2.9 U	9100	36
SSHS-B3203A	SSHS-3203a	D	9/13/2019	180-95715-1	< 36 U	< 3.4 U	< 4.1 U	85 J	< 0.33 U	< 0.28 U	56000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	8800	14 J
SSHS-B3203A	SSHS-3203a	T	9/13/2019	180-95715-1	< 36 U	< 3.4 U	< 4.1 U	87 J	< 0.33 U	< 0.28 U	57000	< 0.78 U	< 0.55 U	< 2.2 U	36 J	< 2.9 U	9100	14 J
SSHS-B3555	SSHS-RI-B3555 TEMP	D	1/16/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	280	< 0.33 U	< 0.28 U	120000	< 0.78 U	< 0.55 U	< 2.2 U	3800	< 2.9 U	15000	1000
SSHS-B3555	SSHS-RI-B3555 TEMP	T	1/16/2021	180-116110-1	83 J	< 3.4 U	< 4.1 U	280	< 0.33 U	< 0.28 U	120000	< 0.78 U	< 0.55 U	< 2.2 U	3900	< 2.9 U	15000	1000
SSHS-B3556	SSHS-RI-B3556-TEMP	D	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	87000	< 0.78 U	< 0.55 U	< 2.2 U	160	< 2.9 U	13000	250
SSHS-B3556	SSHS-RI-B3556-TEMP	T	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	89000	< 0.78 U	< 0.55 U	< 2.2 U	250	< 2.9 U	13000	250
SSHS-B3557	SSHS-RI-B3557 TEMP	D	1/13/2021	180-115925-2	< 53 U	< 3.4 U	< 4.1 U	180 J	< 0.33 U	< 0.28 U	120000	< 0.78 U	< 0.55 U	< 2.2 U	450	< 2.9 U	15000	1200
SSHS-B3557	SSHS-RI-B3557 TEMP	T	1/13/2021	180-115925-2	70 J	< 3.4 U	< 4.1 U	180 J	< 0.33 U	< 0.28 U	120000	< 0.78 U	< 0.55 U	< 2.2 U	540	< 2.9 U	15000	1200
SSHS-B3558	SSHS-RI-B3558-TEMP	D	1/15/2021	180-116071-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	91000	< 0.78 U	< 0.55 U	3 J	< 31 U	< 2.9 U	14000	55
SSHS-B3558	SSHS-RI-B3558-TEMP	T	1/15/2021	180-116071-1	97 J	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	92000	0.81 J	< 0.55 U	2.7 J	140	< 2.9 U	14000	61
SSHS-B3559	SSHS-RI-B3559 TEMP	D	1/16/2021	180-116200-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	89000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	7.6 J
SSHS-B3559	SSHS-RI-B3559 TEMP	T	1/16/2021	180-116200-1	64 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	89000	0.82 J	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	8 J
SSHS-B3560	SSHS-RI-B3560R TEMP	D	1/19/2021	180-116200-1	< 53 U	< 3.4 U	< 4.1 U	160 J	< 0.33 U	< 0.28 U	120000	< 0.78 U	< 0.55 U	2.5 J	250	< 2.9 U	15000	860
SSHS-B3560	SSHS-RI-B3560R TEMP	T	1/19/2021	180-116200-1	< 53 U	< 3.4 U	< 4.1 U	150 J	< 0.33 U	< 0.28 U	120000	< 0.78 U	< 0.55 U	< 2.2 U	280	< 2.9 U	15000	840
SSHS-B3561	SSHS-RI-B3561R TEMP	D	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	90000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	2.2 J
SSHS-B3561	SSHS-RI-B3561R TEMP	T	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	89000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	2.4 J
SSHS-B3561	SSHS-RI-DUP27	D	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	88000	< 0.78 U	< 0.55 U	2.8 J	< 31 U	< 2.9 U	13000	2.5 J
SSHS-B3561	SSHS-RI-DUP27	T	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	90000	< 0.78 U	< 0.55 U	< 2.2 UJ	< 31 U	< 2.9 U	13000	2.3 J

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Thallium (Method 6010)	Thallium (Method 6020)	Vanadium	Zinc
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.7	100		10	50		0.5[2]	0.5[2]		2000
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
MW-90S	MW-90S	D	10/28/2021	180-129230-1	< 0.13 U	7.8 J	3100 J	< 3.7 U	< 0.91 U	81000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-90S	MW-90S	T	10/28/2021	180-129230-1	< 0.13 U	9.4 J	3200 J	< 3.7 U	< 0.91 U	82000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-90S	SSHS-MW-90S-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3100 J	< 3.7 U	< 0.91 U	95000	3.2 J	-	< 5.3 U	< 42 U
MW-91I	MW-91I	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	85000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-91I	MW-91I	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	86000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-91I	MW-91I	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3100 J	4.1 J	< 0.91 U	82000	< 3 U	-	< 5.3 U	< 2.6 U
MW-91I	MW-91I	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3000 J	< 3.7 UJ	< 0.91 U	81000	< 3 U	-	< 5.3 U	< 2.6 U
MW-91I	SSHS-MW-91I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	2900 J	< 3.7 U	< 0.91 U	80000	< 3.0 U	-	< 5.3 U	< 42 U
MW-91S	MW-91S	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	4200 J	< 3.6 U	< 0.85 U	82000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-91S	MW-91S	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	4300 J	< 3.6 U	< 0.85 U	82000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-91S	MW-91S	D	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3500 J	< 3.7 U	< 0.91 U	85000	< 3 U	-	< 5.3 U	< 2.6 U
MW-91S	MW-91S	T	11/2/2021	180-129534-1	< 0.13 U	< 1.9 U	3500 J	6.3 J	< 0.91 U	84000	< 3 U	-	< 5.3 U	< 2.6 U
MW-91S	SSHS-MW-91S-04112024	T	4/11/2024	1801722811	0.15 J	< 3.5 U	3200 J	< 3.7 U	< 0.91 U	81000	< 3.0 U	-	< 5.3 U	< 42 U
MW-92I	MW-92I	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	83000	< 3.3 U	-	< 3.7 U	< 6 U
MW-92I	MW-92I	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	84000	< 3.3 U	-	< 3.7 U	< 6 U
MW-92I	MW-92I	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	79000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-92I	MW-92I	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3600 J	< 3.7 U	< 0.91 U	78000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-92I	SSHS-MW-92I-04082024	T	4/8/2024	1801720411	< 0.13 U	< 3.5 U	3300 J	< 3.7 UT	< 0.91 U	86000	< 3.0 U	-	< 5.3 U	< 42 U
MW-92S	MW-92S	D	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-92S	MW-92S	T	9/10/2021	180-126939-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 6 U
MW-92S	MW-92S	D	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3800 J	< 3.7 U	< 0.91 U	77000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-92S	MW-92S	T	10/28/2021	180-129230-1	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	76000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-92S	SSHS-MW-92S-04052024	T	4/5/2024	1801720031	0.16 BJ	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	84000	< 3.0 U	-	< 5.3 U	< 42 U
MW-93I	DUP-4	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	80000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-93I	DUP-4	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	78000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-93I	MW-93I	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	79000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-93I	MW-93I	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	79000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-93I	MW-93I	D	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	3000 J	< 3.7 U	< 0.91 U	69000	< 3 U	-	< 5.3 U	< 2.6 U
MW-93I	MW-93I	T	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	3100 J	5.3 J	< 0.91 U	73000	< 3 U	-	< 5.3 U	< 2.6 U
MW-93I	SSHS-DUP-08-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3300 J	< 3.7 U	< 0.91 U	78000	< 3.0 U	-	< 5.3 U	< 42 U
MW-93I	SSHS-MW-93I-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3400 J	< 3.7 U	< 0.91 U	79000	< 3.0 U	-	< 5.3 U	< 42 U
MW-93S	MW-93S	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	5700	< 3.6 U	< 0.85 U	88000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-93S	MW-93S	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	5500	< 3.6 U	< 0.85 U	87000	< 3.3 UJ	-	3.8 J	< 6 U
MW-93S	MW-93S	D	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	6100	3.7 J	< 0.91 U	98000	< 3 U	-	6.4 J	< 2.6 U
MW-93S	MW-93S	T	10/29/2021	180-129376-1	< 0.13 U	< 1.9 U	6100	< 3.7 UJ	< 0.91 U	98000	< 3 U	-	< 5.3 UJ	< 2.6 U
MW-93S	SSHS-MW-93S-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	6200	< 3.7 U	< 0.91 U	120000	3.9 J	-	< 5.3 U	< 42 U
MW-94I	MW-94I	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	82000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-94I	MW-94I	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	79000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-94I	MW-94I	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	5800	< 3.7 U	< 0.91 U	78000	3.1 J	-	< 5.3 U	< 2.6 U
MW-94I	MW-94I	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	81000	< 3.7 U	< 0.91 U	130000	< 3 UJ	-	6.6 J	12 J
MW-94I	SSHS-MW-94I-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3200 J	< 3.7 U	< 0.91 U	76000	< 3.0 U	-	< 5.3 U	< 42 U
MW-94S	MW-94S	D	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	92000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-94S	MW-94S	T	9/9/2021	180-126905-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	90000	< 3.3 UJ	-	< 3.7 U	< 6 U
MW-94S	MW-94S	D	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3100 J	< 3.7 U	< 0.91 U	88000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-94S	MW-94S	T	10/27/2021	180-129230-1	< 0.13 U	< 1.9 U	3000 J	< 3.7 U	< 0.91 U	87000	< 3 UJ	-	< 5.3 U	< 2.6 U
MW-94S	SSHS-MW-94S-04112024	T	4/11/2024	1801722811	< 0.13 U	< 3.5 U	3000 J	< 3.7 U	< 0.91 U	100000	< 3.0 U	-	< 5.3 U	< 42 U
MW-95I	SSHS-MW-95I-01162024	T	1/16/2024	1801682361	< 0.13 U	9.3 J	3900 J	< 3.7 UT	< 0.91 U	86000	< 3.0 U	-	< 5.3 U	140
MW-95I	SSHS-MW-95I-04112024	T	4/11/2024	1801722791	< 0.13 U	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	78000	< 3.0 U	-	< 5.3 U	< 42 U
MW-95I	SSHS-MW-95I-09122023	T	9/12/2023	1801624601	< 0.13 U	< 2.2 U	4000 J	< 6.0 U	< 0.62 U	86000	< 2.7 U	-	< 5.6 U	< 23 U
MW-95I	SSHS-MW-95I-11142023	T	11/14/2023	1801653531	< 0.13 U	3.8 J	3900 J	< 3.7 U	< 0.91 U	93000	< 3.0 U	-	< 5.3 U	230
MW-95S	SSHS-MW-95S-01162024	T	1/16/2024	1801682361	< 0.13 U	< 3.5 U	3700 J	< 3.7 UT	< 0.91 U	87000	3.5 BJ	-	< 5.3 U	< 42 U
MW-95S	SSHS-MW-95S-04112024	T	4/11/2024	1801722791	< 0.13 U	< 3.5 U	3600 J	4.5 J	< 0.91 U	97000	3.4 BJ	< 0.47 U	< 5.3 U	< 42 U
MW-95S	SSHS-MW-95S-09122023	T	9/12/2023	1801624601	< 0.13 U	< 2.2 U	4100 J	< 6.0 U	< 0.62 U	89000	5.5 J	-	< 5.6 U	< 23 U
MW-95S	SSHS-MW-95S-11142023	T	11/14/2023	1801653531	< 0.13 U	< 3.5 U	3800 J	< 3.7 U	< 0.91 U	90000	< 3.0 U	-	< 5.3 U	< 42 U
MW-96	SSHS-MW-96-01172024	T	1/17/2024	1801682361	< 0.13 U	< 3.5 U	3400 J	< 3.7 UT	< 0.91 U	70000	< 3.0 U	-	< 5.3 U	< 42 U
MW-96	SSHS-MW-96-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	3000 J	< 3.7 U	< 0.91 U	61000	3.6 J	-	< 5.3 U	< 42 U
MW-96	SSHS-MW-96-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2900 J	< 3.7 U	< 0.91 U	75000	< 3.0 U	-	< 5.3 U	25 B
MW-96	SSHS-MW-96-09152023	T	9/15/2023	1801625601	< 0.13 U	< 2.2 U	3800 J	< 6.0 U	< 0.62 U	67000	< 2.7 U	-	< 5.6 U	< 23 U
MW-96	SSHS-MW-96-11142023	T	11/14/2023	1801653531	< 0.13 U	< 3.5 U	3700 J	< 3.7 U	< 0.91 U	76000	< 3.0 U	-	< 5.3 U	< 42 U
MW-97	SSHS-MW-97-01172024	T	1/17/2024	1801682361	< 0.13 U	3.9 J	3200 J	< 3.7 UT	< 0.91 U	64000	4.2 BJ	-	< 5.3 U	86
MW-97	SSHS-MW-97-04092024	T	4/9/2024	1801721201	< 0.13 U	< 3.5 U	2700 J	< 3.7 U	< 0.91 U	61000	4.6 J	-	< 5.3 U	< 42 U
MW-97	SSHS-MW-97-05022023	T	5/2/2023	1801559471	< 0.13 U	< 1.9 U	2200 J	< 3.7 U	< 0.91 U	67000	< 3.0 U	-	< 5.3 U	17 BJ
MW-97	SSHS-MW-97-09152023	T	9/15/2023	1801625601	< 0.13 U	< 2.2 U	3400 J	< 6.0 U	< 0.62 U	43000	< 2.7 U	-	< 5.6 U	< 23 U
MW-97	SSHS-MW-97-11142023	T	11/14/2023	1801653531	< 0.13 U	< 3.5 U	3500 J	< 3.7 U	< 0.91 U	63000	< 3.0 U	-	< 5.3 U	66
MW-98I	DUP-01	T	9/1/2022	1801438881	< 0.13 U	< 1.9 U	3700 J	< 3.7 U	< 0.91 U	62000	3.6 J	-	< 5.3 U	5.6 BJ
MW-98I	MW-98I	T	9/1/2022	1801438881	< 0.13 U	< 1.9 U	3700 J	4.6 J	< 0.91 U	61000	< 3.0 U	-	< 5.3 U	2.7 BJ
MW-98I	SSHS-MW-98I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3600 J	< 3.7 U	< 0.91 U	63000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-98I	SSHS-MW-98I-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	60000	5.2 J	-	8.4 J	< 23 U
MW-98S	MW-98S	T	9/1/2022	1801438881	< 0.13 U	< 1.9 U	4000 J	6.9 J	< 0.91 U	65000	3.4 J	-	< 5.3 U	4.6 BJ
MW-98S	SSHS-MW-98S-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3800 J	< 3.7 U	< 0.91 U	60000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-98S	SSHS-MW-98S-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	57000	4.0 J	-	< 5.6 U	< 23 U
MW-99I	SSHS-MW-99I-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	4000 J	< 3.7 U	< 0.91 U	75000	3.4 J	< 0.47 U	< 5.3 U	< 42 U
MW-99I	SSHS-MW-99I-09132023	T	9/13/2023	1801624611	< 0.13 U	< 2.2 U	< 560 U	< 6.0 U	< 0.62 U	69000	4.1 J	-	6.0 J	< 23 U
MW-99S	SSHS-MW-99S-04102024	T	4/10/2024	1801721871	< 0.13 U	< 3.5 U	3800 J	< 3.7 U	< 0.91 U	67000	< 3.0 U	< 0.47 U	< 5.3 U	< 42 U
MW-99S	SSHS-MW-99S-09132023	T	9/13/2023	1801624611	< 0.13 U	2.5 J	< 560 U	< 6.0 U	< 0.62 U	72000	4.8 J	-	< 5.6 U	< 23 U
MW-9I	MW-9I	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-9I	MW-9I	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3200 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
MW-9I	MW-9I	D	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	85000	< 3.3 U	-	< 3.7 U	< 6 U
MW-9I	MW-9I	T	8/31/2021	180-126501-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	85000	< 3.3 U	-	< 3.7 U	< 6 U
MW-9I	SSHS-MW-9I-04292024	T	4/29/2024	1801733271	< 0.13 U	< 3.5 U	3800 J	< 3.7 UT	< 0.91 U	91000	< 3.0 U	-	< 5.3 U	< 42 U
MW-9S	MW-9	T	2/20/2021	180-117476-1	< 0.13 U	1.7 J	4900 J	< 3.6 U	< 0.85 U	30000	< 3.3 U	-	< 3.7 U	< 6 U
MW-9S	MW-9	D	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	12000	< 3.3 U	-	< 3.7 U	< 6 U
MW-9S	MW-9	T	7/14/2021	180-124487-1	< 0.13 U	< 1.5 U	3900 J	< 3.6 U	< 0.85 U	11000	4 J	-	4 J	< 6 U
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	T	8/4/2021	1801253661	< 0.13 U	5.8 J	2500 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6.0 U
SSHS-B2090A	SSHS-B2090A	D	5/22/2019	180-90525-1	< 0.1 U	96	3800 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	25
SSHS-B2090A	SSHS-B2090A	T	5/22/2019	180-90525-1	< 0.1 U	95	3700 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	24
SSHS-B2221	SSHS-B2221A	D	5/22/2019	180-90525-1	< 0.1 U	4.7 J	11000	6.8 J	< 0.85 U	52000	< 3.3 U	-	< 3.7 U	6 J
SSHS-B2221	SSHS-B2221A	T	5/22/2019	180-90525-1	< 0.1 U	3.9 J	11000	5.4 J	< 0.85 U	52000	< 3.3 U	-	< 3.7 U	5.5 J
SSHS-B23	B23	T	5/9/2000		0.47	144	-	-	-	-	-	-	66.2	390
SSHS-B2541	SSHS-B2541-GW	T	10/29/2018	180-83541-1	< 0.065 U	120	5800	< 3.6 U	< 0.85 U	49000	< 3.3 U	-	< 3.7 U	90 =
SSHS-B2542	SSHS-B2542-GW	T	10/29/2018	180-83541-1	0.14 J	5000	14000	5 J	< 0.85 U	65000	< 3.3 U	-	41 J	1700 =
SSHS-B2542A	SSHS-B2542A	D	5/22/2019	180-90525-1	< 0.1 U	370	4400 J	< 3.6 UJ	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	52
SSHS-B2542A	SSHS-B2542A	T	5/22/2019	180-90525-1	< 0.1 U	380	4500 J	5 J	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	52
SSHS-B2543	SSHS-B2543-GW	T	10/30/2018	180-83544-1	< 0.065 U	2 J	5100	< 3.6 U	< 0.85 U	100000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B2544	SSHS-B2544-GW	T	10/30/2018	180-83544-1	< 0.065 U	26 J	14000	< 3.6 U	< 0.85 U	45000	< 3.3 U	-	< 3.7 U	36 =
SSHS-B2629	SSHS-B2629	D	4/25/2019	180-89520-1	< 0.1 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B2629	SSHS-B2629	T	4/25/2019	180-89520-1	< 0.1 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B2722	SSHS-B2722	D	5/21/2019	180-90380-2	< 0.1 U	< 1.5 U	4700 J	6.6 J	< 0.85 U	59000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B2722	SSHS-B2722	T	5/21/2019	180-90380-2	< 0.1 U	< 1.5 U	4700 J	5.7 J	< 0.85 U	59000	< 3.3 U	-	< 3.7 U	1.9 J
SSHS-B2752	SSHS-B2752	D	4/25/2019	180-89520-1	< 0.1 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B2752	SSHS-B2752	T	4/25/2019	180-89520-1	< 0.1 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	2.2 J,B
SSHS-B3200A	DUP-01	D	9/15/2019	180-95745-1	< 0.1 U	< 1.5 U	3300 J	3.9 J	< 0.85 U	82000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B3200A	DUP-01	T	9/15/2019	180-95745-1	< 0.1 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B3200A	SSHS-B3200a	D	9/15/2019	180-95745-1	< 0.1 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B3200A	SSHS-B3200a	T	9/15/2019	180-95745-1	< 0.1 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	81000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B3203A	SSHS-3203a	D	9/13/2019	180-95715-1	< 0.1 U	< 1.5 U	3000 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B3203A	SSHS-3203a	T	9/13/2019	180-95715-1	< 0.1 U	< 1.5 U	3100 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 1.8 U
SSHS-B3555	SSHS-RI-B3555 TEMP	D	1/16/2021	180-116110-1	< 0.13 U	< 1.5 U	4500 J	< 3.6 U	< 0.85 U	49000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3555	SSHS-RI-B3555 TEMP	T	1/16/2021	180-116110-1	< 0.13 U	< 1.5 U	4400 J	< 3.6 U	< 0.85 U	48000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3556	SSHS-RI-B3556-TEMP	D	1/14/2021	180-116000-1	< 0.13 U	7.3 J	3500 J	< 3.6 U	< 0.85 U	62000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3556	SSHS-RI-B3556-TEMP	T	1/14/2021	180-116000-1	< 0.13 U	8.3 J	3600 J	< 3.6 U	< 0.85 U	63000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3557	SSHS-RI-B3557 TEMP	D	1/13/2021	180-115925-2	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	39000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3557	SSHS-RI-B3557 TEMP	T	1/13/2021	180-115925-2	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	39000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3558	SSHS-RI-B3558-TEMP	D	1/15/2021	180-116071-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3558	SSHS-RI-B3558-TEMP	T	1/15/2021	180-116071-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3559	SSHS-RI-B3559 TEMP	D	1/16/2021	180-116200-1	< 0.13 U	2.4 J	3700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3559	SSHS-RI-B3559 TEMP	T	1/16/2021	180-116200-1	< 0.13 U	2.5 J	3700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3560	SSHS-RI-B3560R TEMP	D	1/19/2021	180-116200-1	< 0.13 U	< 1.5 U	4300 J	< 3.6 U	< 0.85 U	87000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3560	SSHS-RI-B3560R TEMP	T	1/19/2021	180-116200-1	< 0.13 U	< 1.5 U	4200 J	< 3.6 U	< 0.85 U	84000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3561	SSHS-RI-B3561R TEMP	D	1/18/2021	180-116110-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3561	SSHS-RI-B3561R TEMP	T	1/18/2021	180-116110-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3561	SSHS-RI-DUP27	D	1/18/2021	180-116110-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3561	SSHS-RI-DUP27	T	1/18/2021	180-116110-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U

DRAFT

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report	Aluminum ug/l	Antimony ug/l	Arsenic ug/l	Barium ug/l	Beryllium ug/l	Cadmium ug/l	Calcium ug/l	Chromium (III+VI) ug/l	Cobalt ug/l	Copper ug/l	Iron ug/l	Lead ug/l	Magnesium ug/l	Manganese ug/l
NYSDEC Guidance Values					2000	3	25	1000	3	5		50		200	300[1]	25	35000	300[1]
SSHS-B3562	DUP-28	D	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	85000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	41
SSHS-B3562	DUP-28	T	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 0.78 U	< 0.55 U	2.3 J	< 31 U	< 2.9 U	13000	38
SSHS-B3562	SSHS-RI-B3562-TEMP	D	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	83000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	41
SSHS-B3562	SSHS-RI-B3562-TEMP	T	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	89000	< 0.78 U	< 0.55 U	< 2.2 UJ	< 31 U	< 2.9 U	14000	40
SSHS-B3563	SSHS-RI-B3563-TEMP	D	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	85000	< 0.78 U	< 0.55 U	2.4 J	< 31 U	< 2.9 U	13000	3.6 J
SSHS-B3563	SSHS-RI-B3563-TEMP	T	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	83000 J+	< 0.78 U	< 0.55 U	< 2.2 UJ	< 31 U	< 2.9 U	13000	3.6 J
SSHS-B3563I	SSHS-RI-B3563I TEMP	D	1/16/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	90000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	14000	13 J
SSHS-B3563I	SSHS-RI-B3563I TEMP	T	1/16/2021	180-116110-1	130 J	< 3.4 U	< 4.1 U	120 J	0.57 J	< 0.28 U	91000	1.4 J	0.7 J	2.7 J	170	< 2.9 U	14000	18
SSHS-B3564	SSHS-RI-B3564R TEMP	D	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	89000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	5.8 J
SSHS-B3564	SSHS-RI-B3564R TEMP	T	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	89000	< 0.78 U	< 0.55 U	< 2.2 U	< 31 U	< 2.9 U	13000	5.7 J
SSHS-B3565	SSHS-RI-B3565-TEMP	D	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	88000	< 0.78 U	< 0.55 U	2.2 J	< 31 U	< 2.9 U	14000	5.8 J
SSHS-B3565	SSHS-RI-B3565-TEMP	T	1/14/2021	180-116000-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	91000	< 0.78 U	< 0.55 U	< 2.2 UJ	66 J	< 2.9 U	14000	8.1 J
SSHS-B3566	SSHS-RI-B3566R TEMP	D	1/18/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	120 J	0.36 J	< 0.28 U	89000	1.2 J	0.63 J	4.4 J	< 31 U	< 2.9 U	13000	14 J
SSHS-B3566	SSHS-RI-B3566R TEMP	T	1/18/2021	180-116110-1	60 J	< 3.4 U	< 4.1 U	120 J	< 0.33 UJ	< 0.28 U	90000	< 0.78 UJ	< 0.55 UJ	< 2.2 UJ	59 J	< 2.9 U	14000	13 J
SSHS-B3571	SSHS-RI-B3571 TEMP	D	1/16/2021	180-116110-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	100000	< 0.78 U	< 0.55 U	< 2.2 U	39 J	< 2.9 U	12000	240
SSHS-B3571	SSHS-RI-B3571 TEMP	T	1/16/2021	180-116110-1	390	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	100000	1.1 J	< 0.55 U	2.9 J	440	< 2.9 U	12000	240
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	D	7/1/2021	180-123971-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	0.71 J	< 9.1 U	< 89 U	< 2.9 U	14000	190
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	T	7/1/2021	180-123971-1	250	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	94000	2.3 J	1.3 J	< 9.1 U	690	< 2.9 U	16000	260
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	D	4/9/2021	180-119810-1	< 53 U	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	95000	3.3 J	0.6 J	16 J	< 89 U	< 2.9 U	15000	130
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	T	4/9/2021	180-119810-1	280	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	95000	5	1 J	78	590	< 2.9 U	16000	230
SSHS-RI-B3860I TEMP	DUP-GW-02	D	4/15/2021	180-120162-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	95
SSHS-RI-B3860I TEMP	DUP-GW-02	T	4/15/2021	180-120162-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	96000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	80
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	D	4/15/2021	180-120162-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	89
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	T	4/15/2021	180-120162-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	96000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	82
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	D	4/13/2021	180-119930-1	< 53 U	< 3.4 U	< 4.1 U	170 J	< 0.33 U	< 0.28 U	110000	34	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	17000	70
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	T	4/13/2021	180-119930-1	< 53 U	< 3.4 U	5 J	170 J	< 0.33 U	< 0.28 U	100000	32	< 0.55 U	< 9.1 U	100	< 2.9 U	16000	81
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	D	4/9/2021	180-119810-1	< 53 U	< 3.4 U	< 4.1 U	380	< 0.33 U	< 0.28 U	140000	< 1.9 U	1.9 J	< 9.1 U	3000	< 2.9 U	16000	1200
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	T	4/9/2021	180-119810-1	< 53 U	< 3.4 U	< 4.1 U	400	< 0.33 U	< 0.28 U	140000	< 1.9 U	1.7 J	< 9.1 U	3600	< 2.9 U	17000	1200
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	D	4/9/2021	180-119810-1	< 53 U	< 3.4 U	< 4.1 U	330	< 0.33 U	< 0.28 U	150000	< 1.9 U	4.4 J	< 9.1 U	7500	< 2.9 U	17000	3700
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	T	4/9/2021	180-119810-1	3400	< 3.4 U	4.8 J	360	< 0.33 U	< 0.28 U	150000	6.8	7.2 J	46	14000	11	20000	4000
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	D	4/6/2021	180-119589-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	70
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	T	4/6/2021	180-119589-1	340	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	0.92 J	< 9.1 U	770	< 2.9 U	16000	220
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	D	4/7/2021	180-119649-1	< 53 U	< 3.4 U	< 4.1 U	92 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	140
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	T	4/7/2021	180-119649-1	68 J	< 3.4 U	< 4.1 U	94 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	200	< 2.9 U	16000	170
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	D	4/14/2021	180-120029-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	96000	2.1 J	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	110
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	T	4/14/2021	180-120029-1	280	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	100000	4.1 J	0.8 J	< 9.1 U	700	< 2.9 U	16000	160
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	D	4/14/2021	180-120029-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	170000	< 1.9 U	2.6 J	< 9.1 U	160	< 2.9 U	21000	2000
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	T	4/14/2021	180-120029-1	410	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	170000	5.7	3 J	14 J	1200	< 2.9 U	21000	2300
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	D	5/14/2021	180-121703-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	87000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	4 J
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	T	5/14/2021	180-121703-1	71 J	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	88000	< 1.9 U	< 0.55 U	< 9.1 U	120	< 2.9 U	15000	9.6 J
SSHS-RI-B3886-TEMP	DUP-GW-01	D	5/19/2021	180-121897-1	< 53 U	< 3.4 U	4.5 J	110 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	0.68 J	< 9.1 U	< 89 U	< 2.9 U	16000	200
SSHS-RI-B3886-TEMP	DUP-GW-01	T	5/19/2021	180-121897-1	110 J	< 3.4 U	< 4.1 UJ	110 J	< 0.33 U	< 0.28 U	99000	< 1.9 U	0.71 J	< 9.1 U	140	< 2.9 U	16000	200
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	D	5/19/2021	180-121897-1	< 53 U	< 3.4 U	4.5 J	110 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	0.77 J	< 9.1 U	< 89 U	< 2.9 U	16000	230
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	T	5/19/2021	180-121897-1	100 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	0.84 J	< 9.1 U	120	< 2.9 U	16000	210
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	D	5/11/2021	180-121472-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	79000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	4.4 J
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	T	5/11/2021	180-121472-1	92 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	80000	< 1.9 U	< 0.55 U	< 9.1 U	130	< 2.9 U	13000	8.2 J
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	D	5/11/2021	180-121472-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	95000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	26
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	T	5/11/2021	180-121472-1	< 53 U	< 3.4 U	< 4.1 U	100 J	< 0.33 U	< 0.28 U	93000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	41
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	D	5/13/2021	180-121702-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	16000	< 2.7 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	T	5/13/2021	180-121702-1	97 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	120	2.9 J	16000	4 J
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	D	5/12/2021	180-121546-1	< 53 U	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	17000	47
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	T	5/12/2021	180-121546-1	69 J	< 3.4 U	< 4.1 U	140 J	< 0.33 U	< 0.28 U	99000	< 1.9 U	< 0.55 U	< 9.1 U	160	< 2.9 U	17000	56
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	D	7/23/2021	180-124918-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	91000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	77
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	T	7/23/2021	180-124918-1	540	< 3.4 U	4.1 J	110 J	< 0.33 U	< 0.28 U	92000	< 1.9 U	0.79 J	< 9.1 U	830	< 2.9 U	14000	130
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	D	7/26/2021	180-124974-1	< 53 U	< 3.4 U	< 4.1 U	91 J	< 0.33 U	< 0.28 U	96000	< 1.9 U	0.82 J	< 9.1 U	< 89 U	< 2.9 U	14000	29
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	T	7/26/2021	180-124974-1	< 53 U	< 3.4 U	< 4.1 U	89 J	< 0.33 U	< 0.28 U	97000	< 1.9 U	< 0.55 UJ	< 9.1 U	< 89 U	< 2.9 U	14000	27
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	D	7/28/2021	180-125087-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	44
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	T	7/28/2021	180-125087-1	110 J	< 3.4 U	5.2 J	120 J	< 0.33 U	< 0.28 U	89000	< 1.9 U	< 0.55 U	< 9.1 U	140	4.3 J	13000	59
SSHS-RI-B4152I-TEMP	DUP-01	D	7/28/2021	180-125087-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	44
SSHS-RI-B4152I-TEMP	DUP-01	T	7/28/2021	180-125087-1	8700 J	< 3.4 J	< 4.1 U	110 J	< 0.33 J	< 0.28 J	10000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	50 J	2700	560
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	D	7/29/2021	180-125127-1	260	< 3.4 U	< 4.1 U	29 J	< 0.33 U	< 0.28 U	140000	< 1.9 U	16 J	< 9.1 U	35000	9.2 J	16000	2600
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	T	7/29/2021	180-125127-1	590	< 3.4 U	5.1 J	38 J	< 0.33 U	< 0.28 U	140000	2 J	18 J	9.5 J	41000	44	17000	2900
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	D	7/28/2021	180-125087-1	< 53 U	< 3.4 U	< 4.1 U	77 J	< 0.33 U	< 0.28 U	87000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	12000	41
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	T	7/28/2021	180-125087-1	70 J	< 3.4 U	< 4.1 U	80 J	< 0.33 U	< 0.28 U	90000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	43
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	D	7/27/2021	180-125052-1	320	< 3.4 U	< 4.1 U	54 J	< 0.33 U	0.76 J	170000	< 1.9 U	21 J	< 9.1 U	54000	15	19000	3900
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	T	7/27/2021	180-125052-1	450	< 3.4 U	5.9 J	57 J	< 0.33 U	0.36 J	180000	< 1.9 U	20 J	< 9.1 U	54000	17	19000	4000
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	D	7/27/2021	180-125052-1	< 53 U	< 3.4 U	< 4.1 U	88 J	< 0.33 U	< 0.28 U	87000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	13000	< 2.7 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	T	7/27/2021	180-125052-1	2300 J	< 3.4 U	4.5 J	120 J	0.34 J	< 0.28 U	92000	3.1 J	6.2 J	11 J	3200 J	3.9 J	14000	640 J
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	D	7/26/2021	180-124974-1	1300	< 3.4 U	< 4.1 U	22 J	< 0.33 U	0.48 J	110000	< 1.9 U	14 J	12 J	42000	3.3 J	13000	2100
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	T	7/26/2021	180-124974-1	1400	< 3.4 U	< 4.1 U	22 J	< 0.33 U	0.44 J	110000	< 1.9 U	15 J	9.7 J	43000	3.1 J	13000	2100
SSHS-RI-MW-55	SSHS-RI-MW-55	D	5/10/2021	180-121427-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	3.6 J
SSHS-RI-MW-55	SSHS-RI-MW-55	T	5/10/2021	180-121427-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	85000	< 1.9 U	< 0.55 U	< 9.1 U	120	< 2.9 U	14000	7.5 J
SSHS-RI-MW-56	SSHS-RI-MW-56	D	5/12/2021	180-121547-1	68 J	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	95000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	15000	< 2.7 U
SSHS-RI-MW-56	SSHS-RI-MW-56	T	5/12/2021	180-121547-1	< 53 UJ	< 3.4 U	< 4.1 U	130 J	< 0.33 U	< 0.28 U	100000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	17000	10 J
SSHS-RI-MW-63I	SSHS-RI-MW-63I	D	5/10/2021	180-121427-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
SSHS-RI-MW-63I	SSHS-RI-MW-63I	T	5/10/2021	180-121427-1	< 53 U	< 3.4 U	< 4.1 U	120 J	< 0.33 U	< 0.28 U	86000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
SSHS-RI-MW-63S	SSHS-RI-MW-63S	D	5/10/2021	180-121427-1	< 53 U	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	90000	< 1.9 U	< 0.55 U	< 9.1 U	< 89 U	< 2.9 U	14000	< 2.7 U
SSHS-RI-MW-63S	SSHS-RI-MW-63S	T	5/10/2021	180-121427-1	54 J	< 3.4 U	< 4.1 U	110 J	< 0.33 U	< 0.28 U	94000	< 1.9 U	< 0.55 U	< 9.1 U	110	< 2.9 U	15000	7.4 J
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	D	7/29/2021	180-125127-1	< 53 U	< 3.4 U	< 4.1 U	79 J	< 0.33 U	< 0.28 U	66000	< 1.9 U	< 0.55 U	< 9.1 U	490	< 2.9 U	10000	< 2.7 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	T	7/29/2021	180-125127-1	< 53 U	< 3.4 U	< 4.1 U	80 J	< 0.33 U	< 0.28 U	67000	< 1.9 U	< 0.55 U	60	1100	33	10000	4.9 J

Notes

[1] - As presented in Section 4.3, geochemical modeling indicates that widely distributed and temporally limited exceedances of iron and manganese above TOGS groundwater standards observed at the Site are related to naturally fluctuating groundwater redox conditions and changing stability of iron- and manganese-bearing minerals. When assessed in tandem with observations of iron and manganese concentrations within solids at the Site sufficient to provide the concentrations observed, as well as the dispersed and transient nature of groundwater exceedances, multiple lines of evidence support the conclusion that iron and manganese TOGS groundwater standards exceedances are related to naturally occurring groundwater redox fluctuations within the uppermost aquifer that would be considered consistent with background, unimpacted regional groundwater characteristics.

[2] - Evaluation of thallium via EPA Method 6020 in addition to EPA Method 6010 effectively demonstrates that EPA Method 6010 results are likely false positives and biased high for thallium due to spectral interferences.

ug/l = micrograms per liter
^+ = Continuing Calibration Verification (CCV) is outside acceptance limits, high biased
*+ = LCS and/or LCSD is outside acceptance limits, high biased
*1 = LCS/LCSD RPD exceeds control limits
*3 = ISTD response or retention time outside acceptable limits
B = Compound detected in method blank
E = Exceeds instrument calibration range
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data

Lab method used: 6010C/SW6010C/SW6010D - Metals, SW6020B - Manganese, SW7470A/SW7471B - Mercury

Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

TABLE 5-9
Groundwater Results - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

					Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Thallium (Method 6010)	Thallium (Method 6020)	Vanadium	Zinc
					ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					0.7	100		10	50		0.5[2]	0.5[2]		2000
Location	Sample Name	Total (T) or Dissolved (D)	Sample Date	Lab Report										
SSHS-B3562	DUP-28	D	1/14/2021	180-116000-1	< 0.13 U	1.9 J	3600 J	< 3.6 U	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3562	DUP-28	T	1/14/2021	180-116000-1	< 0.13 U	1.5 J	3600 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3562	SSHS-RI-B3562-TEMP	D	1/14/2021	180-116000-1	< 0.13 U	2 J	3600 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3562	SSHS-RI-B3562-TEMP	T	1/14/2021	180-116000-1	< 0.13 U	1.5 J	3800 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3563	SSHS-RI-B3563-TEMP	D	1/14/2021	180-116000-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3563	SSHS-RI-B3563-TEMP	T	1/14/2021	180-116000-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	72000 J+	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3563I	SSHS-RI-B3563I TEMP	D	1/16/2021	180-116110-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3563I	SSHS-RI-B3563I TEMP	T	1/16/2021	180-116110-1	< 0.13 U	2.2 J	3700 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3564	SSHS-RI-B3564R TEMP	D	1/18/2021	180-116110-1	< 0.13 U	1.7 J	3600 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3564	SSHS-RI-B3564R TEMP	T	1/18/2021	180-116110-1	< 0.13 U	< 1.5 UJ	3600 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3565	SSHS-RI-B3565-TEMP	D	1/14/2021	180-116000-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3565	SSHS-RI-B3565-TEMP	T	1/14/2021	180-116000-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	78000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3566	SSHS-RI-B3566R TEMP	D	1/18/2021	180-116110-1	< 0.13 U	2 J	3700 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3566	SSHS-RI-B3566R TEMP	T	1/18/2021	180-116110-1	< 0.13 U	< 1.5 UJ	3700 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3571	SSHS-RI-B3571 TEMP	D	1/16/2021	180-116110-1	< 0.13 U	2.3 J	3600 J	< 3.6 U	< 0.85 U	110000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-B3571	SSHS-RI-B3571 TEMP	T	1/16/2021	180-116110-1	< 0.13 U	3.2 J	3700 J	< 3.6 U	< 0.85 U	110000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	D	7/1/2021	180-123971-1	< 0.13 U	1.9 J	3600 J	< 3.6 U	< 0.85 U	70000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	T	7/1/2021	180-123971-1	< 0.13 U	2.6 J	3900 J	3.8 J	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	D	4/9/2021	180-119810-1	< 0.13 U	81	3700 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	23
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	T	4/9/2021	180-119810-1	< 0.13 U	150	3800 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	61
SSHS-RI-B3860I TEMP	DUP-GW-02	D	4/15/2021	180-120162-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3860I TEMP	DUP-GW-02	T	4/15/2021	180-120162-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	89000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	D	4/15/2021	180-120162-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	86000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	T	4/15/2021	180-120162-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	89000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	D	4/13/2021	180-119930-1	< 0.13 U	< 1.5 U	4400 J	< 3.6 U	< 0.85 U	97000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	T	4/13/2021	180-119930-1	< 0.13 U	< 1.5 U	4200 J	< 3.6 U	< 0.85 U	91000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	D	4/9/2021	180-119810-1	< 0.13 U	200	6500	< 3.6 U	< 0.85 U	49000	< 3.3 U	-	< 3.7 U	140
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	T	4/9/2021	180-119810-1	< 0.13 U	180	6900	< 3.6 U	< 0.85 U	50000	< 3.3 U	-	< 3.7 U	120
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	D	4/9/2021	180-119810-1	< 0.13 U	95	23000	< 3.6 U	< 0.85 U	50000	< 3.3 U	-	< 3.7 U	28
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	T	4/9/2021	180-119810-1	< 0.13 U	170	24000	< 3.6 U	< 0.85 U	48000	< 3.3 U	-	5.8 J	120
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	D	4/6/2021	180-119589-1	< 0.13 U	< 1.5 U	4000 J	5.2 J	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	T	4/6/2021	180-119589-1	< 0.13 U	2 J	4000 J	< 3.6 UJ	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	6.9 J
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	D	4/7/2021	180-119649-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	T	4/7/2021	180-119649-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	D	4/14/2021	180-120029-1	< 0.13 U	< 1.5 U	4500 J	< 3.6 U	< 0.85 U	89000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	T	4/14/2021	180-120029-1	< 0.13 U	2.2 J	4700 J	5.1 J	< 0.85 U	89000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	D	4/14/2021	180-120029-1	< 0.13 U	11 J	9500	< 3.6 U	< 0.85 U	68000	< 3.3 U	-	< 3.7 U	8 J
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	T	4/14/2021	180-120029-1	< 0.13 U	13 J	9300	< 3.6 U	< 0.85 U	66000	< 3.3 U	-	< 3.7 U	16 J
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	D	5/14/2021	180-121703-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	T	5/14/2021	180-121703-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	4.1 J	< 6 U
SSHS-RI-B3886-TEMP	DUP-GW-01	D	5/19/2021	180-121897-1	< 0.13 U	2.4 J	4300 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3886-TEMP	DUP-GW-01	T	5/19/2021	180-121897-1	< 0.13 U	2.3 J	4300 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	D	5/19/2021	180-121897-1	< 0.13 U	2.3 J	4300 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	T	5/19/2021	180-121897-1	< 0.13 U	2.8 J	4300 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	D	5/11/2021	180-121472-1	< 0.13 U	< 1.5 U	3300 J	5.2 J	< 0.85 U	72000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	T	5/11/2021	180-121472-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 UJ	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	D	5/11/2021	180-121472-1	< 0.13 U	< 1.5 U	2400 J	< 3.6 U	< 0.85 U	59000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	T	5/11/2021	180-121472-1	< 0.13 U	< 1.5 U	2300 J	< 3.6 U	< 0.85 U	58000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	D	5/13/2021	180-121702-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	59000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	T	5/13/2021	180-121702-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	59000	< 3.3 U	-	5.8 J	< 6 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	D	5/12/2021	180-121546-1	< 0.13 U	< 1.5 U	4000 J	< 3.6 U	< 0.85 U	74000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	T	5/12/2021	180-121546-1	< 0.13 U	< 1.5 U	3900 J	< 3.6 U	< 0.85 U	71000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	D	7/23/2021	180-124918-1	< 0.13 U	< 1.5 U	3600 J	4.4 J	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	T	7/23/2021	180-124918-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 UJ	< 0.85 U	88000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	D	7/26/2021	180-124974-1	< 0.13 U	< 1.5 U	4600 J	< 3.6 U	< 0.85 U	100000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	T	7/26/2021	180-124974-1	< 0.13 U	< 1.5 U	4600 J	< 3.6 U	< 0.85 U	100000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	D	7/28/2021	180-125087-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	T	7/28/2021	180-125087-1	< 0.13 U	2.1 J	3300 J	< 3.6 U	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4152I-TEMP	DUP-01	D	7/28/2021	180-125087-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4152I-TEMP	DUP-01	T	7/28/2021	180-125087-1	< 0.13 U	26 J	810 J	< 3.6 U	< 0.85 U	-	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	D	7/29/2021	180-125127-1	< 0.13 U	68	6300	< 3.6 U	< 0.85 U	200000	< 3.3 U	-	< 3.7 U	110
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	T	7/29/2021	180-125127-1	< 0.13 U	77	6700	< 3.6 U	< 0.85 U	220000	< 3.3 U	-	< 3.7 U	130
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	D	7/28/2021	180-125087-1	< 0.13 U	< 1.5 U	3400 J	3.9 J	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	T	7/28/2021	180-125087-1	< 0.13 U	< 1.5 U	3400 J	< 3.6 UJ	< 0.85 U	79000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	D	7/27/2021	180-125052-1	< 0.13 U	80	9500	< 3.6 U	< 0.85 U	310000	< 3.3 U	-	< 3.7 U	230
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	T	7/27/2021	180-125052-1	< 0.13 U	78	10000	< 3.6 U	< 0.85 U	320000	4.7 J	-	< 3.7 U	230
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	D	7/27/2021	180-125052-1	< 0.13 U	< 1.5 U	3300 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	T	7/27/2021	180-125052-1	< 0.13 U	10 J	3800 J	< 3.6 U	< 0.85 U	77000	5.3 J	-	< 3.7 U	32
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	D	7/26/2021	180-124974-1	< 0.13 U	55	7900	< 3.6 U	< 0.85 U	280000	< 3.3 U	-	< 3.7 U	170
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	T	7/26/2021	180-124974-1	< 0.13 U	56	8000	4.1 J	< 0.85 U	290000	< 3.3 U	-	< 3.7 U	170
SSHS-RI-MW-55	SSHS-RI-MW-55	D	5/10/2021	180-121427-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	75000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-MW-55	SSHS-RI-MW-55	T	5/10/2021	180-121427-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-MW-56	SSHS-RI-MW-56	D	5/12/2021	180-121547-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	69000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-MW-56	SSHS-RI-MW-56	T	5/12/2021	180-121547-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-MW-63I	SSHS-RI-MW-63I	D	5/10/2021	180-121427-1	< 0.13 U	< 1.5 U	3600 J	< 3.6 U	< 0.85 U	76000	< 3.3 U	-	4 J	< 6 U
SSHS-RI-MW-63I	SSHS-RI-MW-63I	T	5/10/2021	180-121427-1	< 0.13 U	< 1.5 U	3500 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 UJ	< 6 U
SSHS-RI-MW-63S	SSHS-RI-MW-63S	D	5/10/2021	180-121427-1	< 0.13 U	< 1.5 U	3700 J	< 3.6 U	< 0.85 U	73000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-MW-63S	SSHS-RI-MW-63S	T	5/10/2021	180-121427-1	< 0.13 U	< 1.5 U	3800 J	< 3.6 U	< 0.85 U	77000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	D	7/29/2021	180-125127-1	< 0.13 U	5.8 J	2700 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	< 6 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	T	7/29/2021	180-125127-1	< 0.13 U	12 J	2500 J	< 3.6 U	< 0.85 U	80000	< 3.3 U	-	< 3.7 U	120

Notes

[1] - As presented in Section 4.3, geochemical modeling indicates that widely distributed and temporally limited exceedances of iron and manganese above TOGS groundwater standards observed at the Site are related to naturally fluctuating groundwater redox conditions and changing stability of iron- and manganese-bearing minerals. When assessed in tandem with observations of iron and manganese concentrations within solids at the Site sufficient to provide the concentrations observed, as well as the dispersed and transient nature of groundwater exceedances, multiple lines of evidence support the conclusion that iron and manganese TOGS groundwater standards exceedances are related to naturally occurring groundwater redox fluctuations within the uppermost aquifer that would be considered consistent with background, unimpacted regional groundwater characteristics.

[2] - Evaluation of thallium via EPA Method 6020 in addition to EPA Method 6010 effectively demonstrates that EPA Method 6010 results are likely false positives and biased high for thallium due to spectral interferences.

ug/l = micrograms per liter
^+ = Continuing Calibration Verification (CCV) is outside acceptance limits, high biased
*+ = LCS and/or LCSD is outside acceptance limits, high biased
*1 = LCS/LCSD RPD exceeds control limits
*3 = ISTD response or retention time outside acceptable limits
B = Compound detected in method blank
E = Exceeds instrument calibration range
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab method used: 6010C/SW6010C/SW6010D - Metals, SW6020B - Manganese, SW7470A/SW7471B - Mercu
Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (DEHP)	4-Bromophenyl phenyl ether	Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroaniline)	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				20			50				0.002		0.002	0.002		5	1		5^1		50			5		10			0.002			5	1	50	1	50	50	50
Location	Sample Name	Sample Date	Lab Report																																			
MW-1	MW1	5/11/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.6 BJ	-
MW-1	MW-1	2/17/2021	180-117387-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.7	< 0.63 U
MW-1	MW-1	7/14/2021	180-124487-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	12	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-10	MW-10	3/24/2021	180-119009-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.066 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	2.3	< 0.71 U
MW-10	MW-10	7/13/2021	180-124378-1	< 0.13 U	< 0.13 U	< 0.12 U	< 0.098 U	< 1.3 U	< 0.12 U	0.22 J	< 0.15 U	< 0.11 U	< 0.19 U	< 0.18 U	< 0.14 U	< 0.13 U	< 0.08 U	< 0.12 U	44	< 0.13 U	< 0.92 U	< 0.94 U	< 0.1 U	< 0.088 U	< 0.12 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.16 U	< 0.14 U	< 0.15 U	< 1.2 U	< 0.1 U	< 1.1 U	< 0.082 U	< 0.11 U	< 1.5 U	< 1.4 U
MW-100I	SSHS-MW-100I-04082024	4/8/2024	1801720411	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-100I	SSHS-MW-100I-09142023	9/14/2023	1801625611	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.10 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 0.55 U	1.1 J	< 0.061 U	< 0.45 U	< 0.33 U	< 0.070 U	< 0.15 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.20 U	< 0.24 U	< 0.88 U	< 0.82 UT
MW-100S	SSHS-MW-100S-04082024	4/8/2024	1801720411	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-100S	SSHS-MW-100S-09142023	9/14/2023	1801625611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	0.90 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	< 0.74 U	< 0.69 UT
MW-100S	SSHS-DUP-02-09142023	9/14/2023	1801625611	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	0.98 J	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	< 0.84 U	< 0.78 UT
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624611	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	1.7 J+	< 0.74 U
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721871	< 0.081 UT	< 0.081 UT	< 0.20 UT	< 0.061 UT	< 0.79 UT	< 0.18 UT	< 0.67 UT	< 0.094 UT	< 0.066 UT	< 0.12 UT	< 0.11 UT	< 0.086 UT	< 0.19 UT	< 0.050 UT	< 0.073 UT	< 7.8 U	< 0.40 UT	< 1.2 U	< 1.8 U	< 0.064 UT	< 0.47 UT	< 0.54 UT	< 0.074 UT	< 0.28 UT	< 0.28 UT	< 0.10 UT	< 0.090 UT	< 0.24 UT	< 0.73 UT	< 0.064 UT	< 0.71 UT	< 0.73 UT	< 0.25 UT	< 6.1 U	< 0.86 U
MW-101S	SSHS-MW-101S-09132023	9/13/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	0.57 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-101S	SSHS-MW-101S-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-102I	SSHS-MW-102I-09142023	9/14/2023	1801625611	< 0.063 UJ	< 0.063 UJ	< 0.15 UJ	< 0.047 UJ	< 0.61 UT	< 0.14 UJ	< 0.52 U	< 0.072 UJ	< 0.051 UJ	< 0.093 UJ	< 0.085 UJ	< 0.066 UJ	< 0.15 UJ	< 0.038 UJ	< 0.056 U	< 6.0 UT	< 0.31 UJ	< 0.44 UJ	0.95 J	< 0.049 UJ	< 0.36 UJ	< 0.27 UJ	< 0.057 UJ	< 0.12 UJ	< 0.21 UJ	< 0.078 UJ	< 0.069 UJ	< 0.18 UJ	< 0.56 UJ	< 0.049 UJ	< 0.55 UJ	< 0.16 UJ	< 0.19 UJ	< 0.71 UJ	< 0.66 UT
MW-102I	SSHS-MW-102I-04222024	4/22/2024	1801730541	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-102S	SSHS-MW-102S-04222024	4/22/2024	1801730541	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	0.093 J	< 0.053 U	0.11 J	0.11 J	0.10 J	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	1.4 J	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	0.11 J	0.12 J	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-102S	SSHS-MW-102S-09142023	9/14/2023	1801625611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	0.83 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	< 0.74 U	< 0.69 UT
MW-103I	SSHS-MW-103I-04162024	4/16/2024	1801726651	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-103I	SSHS-MW-103I-09122023	9/12/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 UJ	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 UT	< 0.21 U	1.8 J+	< 0.71 U
MW-103S	SSHS-MW-103S-04162024	4/16/2024	1801726651	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-103S	SSHS-MW-103S-09122023	9/12/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 UJ	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 UT	< 0.21 U	1.9 J+	< 0.71 U
MW-104I	SSHS-MW-104I-09122023	9/12/2023	1801624611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 UJ	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 UT	< 0.20 U	2.0 J+	< 0.69 U
MW-104I	SSHS-DUP-03-09122023	9/12/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 UJ	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 UT	< 0.21 U	1.6 J+	< 0.71 U
MW-104I	SSHS-MW-104I-04162024	4/16/2024	1801726651	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-104S	SSHS-MW-104S-09122023	9/12/2023	1801624611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	0.076 J	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 UJ	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	0.097 J	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 UT	< 0.20 U	1.9 J+	< 0.69 U
MW-104S	SSHS-MW-104S-04162024	4/16/2024	1801726651	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 1.1 U	< 1.6 U	< 0.058 U	< 0.43 U	< 0.49 U	< 0.067 U	< 0.26 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.66 U	< 0.23 U	< 5.6 U	< 0.78 U
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	3.9 J+	< 0.69 U
MW-105I	SSHS-MW-105I-04172024	4/17/2024	1801726651	< 0.071 UT	< 0.071 UT	< 0.17 UT	< 0.053 UT	< 0.69 UT	< 0.15 UT	< 0.58 U	< 0.082 UT	< 0.058 UT	< 0.11 UT	< 0.096 UT	< 0.075 UT	< 0.17 UT	< 0.043 UT	< 0.063 UT	< 6.8 U	< 0.35 UT	< 1.0 U	< 1.5 U	< 0.055 UT	< 0.41 UT	< 0.47 U	< 0.064 UT	< 0.24 UT	< 0.24 UT	< 0.088 U	< 0.078 UT	< 0.21 UT	< 0.63 UT	< 0.055 UT	< 0.62 UT	< 0.64 UT	< 0.22 UT	< 5.3 U	< 0.74 U
MW-105S	SSHS-MW-105S-04252024	4/25/2024	1801731401	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 UT	< 6.2 U	< 0.32 U	< 0.94 U	2.8 J	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-105S	SSHS-MW-105S-09122023	9/12/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 UJ	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 UT	< 0.21 U	1.6 J+	< 0.71 U
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	0.20	< 0.63 U	< 0.14 U	< 0.54 U	1.1	0.58	1.3	1.0	1.1	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	0.55 J	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	0.95	0.79	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	2.2	1.3
MW-106	SSHS-MW-106-09142023	9/14/2023	1801625601	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653531	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	4.8 J+	< 0.71 U
MW-106	SSHS-MW-106-04102024	4/10/2024	1801721851	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	0.11 J	< 0.058 U	0.12 J	0.14 J	0.10 J	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	1.7 J	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	0.17 J	0.091 J	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682891	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	2.3	< 0.78 U
MW-11D	MW-11D	7/15/2021	180-124580-1	< 0.014 U	< 0.015 U	< 0.07 U	< 0.025 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.016 U	< 0.022 U	< 0.024 U	< 0.028 U	< 0.035 U	< 0.076 U	< 0.045 U	< 0.066 U	15	< 0.072 U	< 0.53 U	1.6 J	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.03 U	< 0.02 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
MW-11D	MW-11D	2/23/2021	180-117459-1	< 0.058 U	< 0.058 U	< 0.055 U	< 0.044 U	< 0.57 U	< 0.053 U	< 0.099 U	< 0.067 U	< 0.047 U	< 0.087 U	< 0.079 U	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.056 U	< 0.41 U	< 0.42 U	< 0.046 U	< 0.039 U	< 0.054 U	< 0.053 U	< 0.057 U	< 0.054 U	< 0.072 U	< 0.064 U	< 0.065 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.037 U	< 0.05 U	1.2	< 0.61 U
MW-11D	MW-11D	4/30/2021	180-120955-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	0.14 J	0.12 J	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	0.12 J	0.11 J	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.4	< 0.66 U
MW-11D	MW-11D-GW	11/1/2018	180-83607-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.2 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 5 U	< 0.068 U	0.52 J	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 UJ	< 0.061 U	< 0.81 U	< 0.74 U
MW-11S	MW-11S-GW	11/1/2018	180-83607-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.17 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 4.3 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-11S	MW-11S	4/30/2021	180-120955-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.5	< 0.66 U
MW-11S	MW-11S	2/23/2021	180-117459-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.066 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	0.72 J	< 0.043 U	< 0.058 U	1.6	< 0.71 U
MW-11S	DUP-01	7/25/2019	180-93333-1	< 0.071 U	< 0.071 U	< 0.067 U	0.098 J	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	1.3 J	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-11S	MW-11S	7/25/2019	180-93333-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 UJ	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	1.5 J	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-11S	FD-1	11/1/2018	180-83607-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.21 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 5.2 U	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
MW-12	MW-12	5/17/2000	-	-	-	-	-	-	-	-	1.2 J	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.8 J	-	-	-	-	-	-	-	3.2 JB	-
MW-12	MW12	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 JB	-
MW-12	MW-12	7/14/2021	180-124487-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	6.1 J	< 0.061 U	< 0.44 U	0.8 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-12	MW-12	2/21/2021	180-117476-1	0.3	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	1	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	0.67 J	< 0.038 U	< 0.052 U	1.7	< 0.63 U
MW-13	DUP-02	2/21/2021	180-117476-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	0.96 J	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.4	< 0.59 U
MW-13	MW-13	2/21/2021	180-117476-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	1.8 J	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.4	< 0.63 U
MW-13	MW-13	7/15/2021	180-124580-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	3.1 J+	< 0.69 U
MW-17	MW17	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.1 JB	-
MW-17	MW17	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 JB	-
MW-2	MW-2	2/17/2021	180-117387-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	< 0.4 U	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.3	< 0.59 U
MW-2	MW-2	7/14/2021	180-124487-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-20	MW20	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.2 JB	-
MW-20	MW20	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 JB	-
MW-20	MW-20	2/23/2021	180-117459-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	0.72 J	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.1	< 0.63 U
MW-20	MW-20	7/15/2021	180-124580-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	10	< 0.066 U	< 0.48 U	1.2 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	< 0.77 U	< 0.71 U
MW-22	MW-22	2/23/2021	180-117459-1	< 0.058 U	< 0.058 U	< 0.055 U	< 0.044 U	< 0.57 U	< 0.053 U	< 0.099 U	< 0.067 U	< 0.047 U	< 0.087 U	< 0.079 U	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.056 U	0.48 J	< 0.42 U	< 0.046 U	< 0.039 U	< 0.054 U	< 0.053 U	< 0.057 U	< 0.054 U	< 0.072 U	< 0.064 U	< 0.065 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.037 U	< 0.05 U	1.7	< 0.61 U
MW-22	MW-22	7/15/2021	180-124580-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	14	< 0.068 U	< 0.5 U	0.84 J	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-26	MW-26	2/17/2021	180-117387-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	0.11 J	0.085 J	0.061 J	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	0.07 J	< 0.059 U	< 0.47 U	< 0.041 U	< 0.46 U	< 0.033 U	< 0.045 U	0.9	< 0.55 U
MW-26	SSHS-MW-26-04112024	4/11/2024	1801722801	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-26	MW-26	7/14/2021	180-124487-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	0.13 J	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	0.8 J	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	0.72 J	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-3	MW-3	2/17/2021	180-117387-1	< 0.058 U	< 0.058 U	< 0.055 U	< 0.044 U	< 0.57 U	< 0.053 U	< 0.099 U	< 0.067 U	< 0.047 U	< 0.087 U	< 0.079 U	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.056 U	< 0.41 U	< 0.42 U	< 0.046 U	< 0.039 U	< 0.054 U	< 0.053 U	< 0.057 U	< 0.054 U	< 0.072 U	< 0.064 U	< 0.065 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.037 U	< 0.05 U	1.4	< 0.61 U
MW-3	DUP-4	7/14/2021	180-124487-1	< 0.074 UJ	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 7.1 UJ	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
MW-3	MW-3	7/14/2021	180-124487-1	0.33 J	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	8.8 J	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
MW-30	MW-30	2/19/2021	180-117476-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	< 0.093 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	0.46 J	< 0.39 U	< 0.043 U	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	< 0.068 U	< 0.06 U	< 0.061 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.034 U	< 0.047 U	< 0.62 U	< 0.57 U
MW-30	MW-30	7/16/2021	180-124628-1	< 0.1 U	< 0.1 U	< 0.097 U	< 0.077 U	< 0.99 U	< 0.092 U	0.23 J	< 0.12 U	< 0.083 U	< 0.15 U	< 0.14 U	< 0.11 U	< 0.1 U	< 0.063 U	< 0.091 U	14 J	< 0.098 U	< 0.72 U	3.9 J	< 0.08 U	< 0.069 U	< 0.095 U	< 0.092 U	< 0.1 U	< 0.095 U	< 0.13 U	< 0.11 U	< 0.11 U	< 0.91 U	< 0.08 U	< 0.89 U	< 0.064 U	< 0.088 U	3.1	< 1.1 U
MW-30	MW-30	7/26/2019	180-93333-1	< 0.15 UJ	0.28 J	< 0.14 UJ	0.4 J	< 1.4 U	< 0.13 UJ	< 0.25 U	1.8 J	1.5 J	2.3 J	0.72 J	1.6	< 0.15 UJ	< 0.091 UJ	< 0.13 UJ	19 J	< 0.14 UJ	< 1.1 U	< 1.1 U	0.18 J	< 0.1 UJ	< 0.14 U	< 0.13 UJ	< 0.15 UJ	< 0.14 UJ	2.3 J	< 0.16 U	< 0.17 UJ	< 1.3 R	< 0.12 UJ	< 1.3 UJ	< 0.093 UJ	< 0.13 UJ	< 1.7 UJ	< 1.6 U
MW-32	MW-32	2/22/2021	180-117425-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	0.92 J	< 0.63 U
MW-32	MW-32	7/13/2021	180-124378-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	0.17 J	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	15	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-33	MW-33	2/19/2021	180-117476-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	0.77 J	< 0.63 U
MW-33	MW-33	7/13/2021	180-124378-1	0.19	< 0.063 U	0.11 J	0.072 J	< 0.61 U	< 0.057 U	0.21 J	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	8 J	< 0.061 U	< 0.44 U	1.7 J	< 0.049 U	< 0.042 UJ	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 R	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-34	MW-34	3/23/2021	180-118872-1	0.16 J	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	9.8 J	< 0.066 U	1.1	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	1.3	< 0.71 U
MW-34	MW-34	4/30/2021	180-120955-1	0.21 J	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	9.8 J	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	0.65 J	< 0.047 U	< 0.064 U	3	< 0.78 U
MW-36	MW-36	4/30/2021	180-120955-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	9.9 J	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	2.1	< 0.74 U
MW-36	MW-36	3/23/2021	180-118872-1	< 1 U	< 1 U	< 0.97 U	< 0.77 U	< 9.9 U	< 0.92 U	< 1.7 U	< 1.2 U	< 0.83 U	< 1.5 U	< 1.4 U	< 1.1 U	< 1 U	< 0.63 U	< 0.91 U	< 97 U	< 0.98 U	< 7.2 U	< 7.3 U	< 0.8 U	< 0.69 U	< 0.95 U	< 0.92 U	< 1 U	< 0.95 U	< 1.3 U	< 1.1 U	< 1.1 U	< 9.1 U	< 0.8 U	< 8.9 U	< 0.64 U	< 0.88 U	< 12 U	< 11 U
MW-36	SSHS-MW36	8/22/2018	180-81174-1	0.11 J	< 0.06 U	< 0.057 U	< 0.045 U	< 0.17 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	5.3 J	< 0.058 U	< 0.43 U	2.1 J	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-38	MW-38	4/30/2021	180-120955-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 6.5 UJ	< 0.066 U	0.97 J	1.7 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 UJ	< 0.043 U	< 0.058 U	2.3	< 0.71 U
MW-38	MW-38	3/24/2021	180-119009-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	1.7	< 0.74 U
MW-38	DUP-1	4/30/2021	180-120955-1	< 0.077 U	< 0.077 U	< 0.074 U	< 0.058 U	< 0.75 U	< 0.07 U	< 0.13 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.1 U	< 0.082 U	< 0.08 U	< 0.048 U	< 0.069 U	37 J	< 0.075 U	1.3 J	2.7 J	< 0.061 U	< 0.052 U	< 0.073 U	< 0.07 U	< 0.076 U	< 0.073 U	< 0.096 U	< 0.086 U	< 0.087 U	< 0.69 U	< 0.061 U	0.76 J	< 0.049 U	< 0.067 U	2.5	< 0.82 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	TPH-DRO	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	1	5	50	50	0.04	0.5	5	5	0.002		50			10	5	5	5	0.4				50	1	50	1	50					
Location	Sample Name	Sample Date	Lab Report																																	
MW-1	MW1	5/11/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-1	MW-1	2/17/2021	180-117387-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	7200	< 0.056 U	< 0.063 U
MW-1	MW-1	7/14/2021	180-124487-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	0.14 J	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	1800	< 0.066 U	< 0.074 U
MW-10	MW-10	3/24/2021	180-119009-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
MW-10	MW-10	7/13/2021	180-124378-1	< 2.9 U	< 0.12 U	< 3.1 U	< 0.1 U	< 0.12 U	< 0.14 U	< 0.11 U	< 0.14 U	< 0.99 U	< 0.12 U	< 0.17 U	< 0.6 U	< 0.11 U	< 0.12 U	< 0.74 U	< 0.12 U	< 1.1 U	< 0.13 U	< 0.12 U	< 1 U	< 0.12 U	< 0.28 U	< 0.14 U	< 0.24 U	< 1.7 U	0.2 J	< 0.97 U	< 0.11 U	< 0.1 U	< 0.09 U	-	< 0.12 U	< 0.14 U
MW-100I	SSHS-MW-100I-04082024	4/8/2024	1801720411	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-100I	SSHS-MW-100I-09142023	9/14/2023	1801625611	< 1.8 U	< 0.21 U	< 1.8 U	< 0.42 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.10 U	< 0.36 U	< 0.22 U	< 0.074 U	< 0.44 U	< 0.070 U	< 0.65 U	< 0.52 U	< 0.43 U	< 0.60 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1.0 U	< 0.065 U	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	-	< 0.30 U	< 0.27 U
MW-100S	SSHS-MW-100S-04082024	4/8/2024	1801720411	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-100S	SSHS-MW-100S-09142023	9/14/2023	1801625611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-100S	SSHS-DUP-02-09142023	9/14/2023	1801625611	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624611	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.060 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721871	< 1.8 UT	< 0.22 UT	< 4.1 U	< 0.44 UT	< 0.075 UT	< 0.086 UT	< 0.070 UT	< 0.086 UT	< 0.62 UT	< 0.17 UT	< 0.11 U	< 0.70 UT	< 0.24 UT	< 0.078 UT	< 0.47 UT	< 0.074 UT	< 0.69 U	< 0.55 UT	< 0.45 UT	< 0.63 UT	< 0.24 UT	< 1.2 U	< 0.089 UT	< 0.15 UT	< 1.1 U	< 0.20 UT	< 0.61 UT	< 0.068 UT	< 0.19 UT	< 0.41 UT	-	< 0.32 UT	< 0.28 UT
MW-101S	SSHS-MW-101S-09132023	9/13/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-101S	SSHS-MW-101S-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-102I	SSHS-MW-102I-09142023	9/14/2023	1801625611	< 1.4 UJ	< 0.17 UJ	< 1.5 UJ	< 0.34 UJ	< 0.058 UJ	< 0.066 UJ	< 0.054 UJ	< 0.066 UJ	< 0.48 UT	< 0.13 UJ	< 0.082 UJ	< 0.29 UJ	< 0.18 UJ	< 0.060 UJ	< 0.36 UJ	< 0.057 UJ	< 0.53 UJ	< 0.42 UJ	< 0.35 UJ	< 0.48 UJ	< 0.19 UJ	< 0.90 U	< 0.068 UJ	< 0.11 UJ	< 0.81 UJ	< 0.053 UJ	< 0.47 UJ	< 0.052 UJ	< 0.14 UJ	< 0.31 UJ	-	< 0.24 UJ	< 0.22 UJ
MW-102I	SSHS-MW-102I-04222024	4/22/2024	1801730541	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-102S	SSHS-MW-102S-04222024	4/22/2024	1801730541	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	0.10 J	< 0.56 U	< 0.19 U	0.16 J	< 0.37 U	0.32	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-102S	SSHS-MW-102S-09142023	9/14/2023	1801625611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-103I	SSHS-MW-103I-04162024	4/16/2024	1801726651	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	0.16 J	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-103I	SSHS-MW-103I-09122023	9/12/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 UT	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-103S	SSHS-MW-103S-04162024	4/16/2024	1801726651	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	0.065 J	< 0.37 U	0.33	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-103S	SSHS-MW-103S-09122023	9/12/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 UT	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-104I	SSHS-MW-104I-09122023	9/12/2023	1801624611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	0.12 J	< 0.55 U	< 0.44 U	< 0.36 UT	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-104I	SSHS-DUP-03-09122023	9/12/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 UT	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-104I	SSHS-MW-104I-04162024	4/16/2024	1801726651	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	0.11 J	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-104S	SSHS-MW-104S-09122023	9/12/2023	1801624611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	0.27 J+	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 UT	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.19 J+	< 0.49 U	0.19 J+	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-104S	SSHS-MW-104S-04162024	4/16/2024	1801726651	< 1.7 U	< 0.20 U	< 3.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.63 U	< 0.21 U	< 0.070 U	< 0.42 U	0.077 J	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.18 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-105I	SSHS-MW-105I-04172024	4/17/2024	1801726651	< 1.6 U	< 0.19 UT	< 3.5 U	< 0.38 UT	< 0.065 UT	< 0.075 UT	< 0.061 U	< 0.075 UT	< 0.54 UT	< 0.14 UT	< 0.092 UT	< 0.61 UT	< 0.20 UT	< 0.067 UT	< 0.40 UT	0.43 T	< 0.60 U	< 0.48 UT	< 0.39 UT	< 0.54 UT	< 0.21 UT	< 1.0 U	< 0.077 U	< 0.13 UT	< 0.92 U	< 0.17 UT	< 0.53 UT	< 0.059 U	< 0.16 UT	< 0.35 UT	-	< 0.27 UT	< 0.24 UT
MW-105S	SSHS-MW-105S-04252024	4/25/2024	1801731401	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-105S	SSHS-MW-105S-09122023	9/12/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 UT	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	0.34	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	1.1	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.16 J	< 0.49 U	0.36	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-106	SSHS-MW-106-09142023	9/14/2023	1801625601	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.058 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653531	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-106	SSHS-MW-106-04102024	4/10/2024	1801721851	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	0.11 J	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682891	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 UT	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	0.15 J	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-11D	MW-11D	7/15/2021	180-124580-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.039 U	< 0.012 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.036 UJ	< 0.34 U	< 0.061 U	< 0.07 U	< 0.42 U	< 0.12 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	0.053	< 0.55 U	< 0.031 U	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
MW-11D	MW-11D	2/23/2021	180-117459-1	< 1.3 U	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.055 U	< 0.076 U	< 0.27 U	< 0.048 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.06 U	< 0.052 U	< 0.45 U	< 0.054 U	< 0.13 U	< 0.063 U	< 0.11 U	< 0.76 U	< 0.049 U	< 0.43 U	< 0.048 U	< 0.046 U	< 0.04 U	< 230 U	< 0.054 U	< 0.061 U
MW-11D	MW-11D	4/30/2021	180-120955-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-11D	MW-11D-GW	11/1/2018	180-83607-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 UJ	< 0.067 U	< 0.092 U	< 0.12 U	< 0.059 U	< 0.067 U	< 0.46 U	< 0.064 U	< 0.23 U	< 0.073 U	< 0.063 U	< 0.18 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.26 U	< 0.06 U	< 0.11 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
MW-11S	MW-11S-GW	11/1/2018	180-83607-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	0.31	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.1 U	< 0.05 U	< 0.057 U	< 0.39 U	< 0.055 U	< 0.19 U	< 0.062 U	< 0.054 U	< 0.15 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.22 U	< 0.051 U	< 0.091 U	0.16 J	< 0.048 U	< 0.042 U	-	< 0.056 U	< 0.063 U
MW-11S	MW-11S	4/30/2021	180-120955-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	6200	< 0.059 U	< 0.065 U
MW-11S	MW-11S	2/23/2021	180-117459-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	6600	< 0.064 U	< 0.071 U
MW-11S	DUP-01	7/25/2019	180-93333-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 UJ	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
MW-11S	MW-11S	7/25/2019	180-93333-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	0.22 J	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
MW-11S	FD-1	11/1/2018	180-83607-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	0.34	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.12 U	< 0.061 U	< 0.07 U	< 0.48 U	< 0.067 U	< 0.24 U	< 0.076 U	< 0.066 U	< 0.19 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.28 U	0.12 J	< 0.11 U	0.14 J	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
MW-12	MW-12	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.8 J	-	-	-	-	-
MW-12	MW12	9/20/2000	-	-	-	-	-	-	1 J	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-12	MW-12	7/14/2021	180-124487-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.16 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	460 J	< 0.059 U	< 0.065 U
MW-12	MW-12	2/21/2021	180-117476-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	0.099 J	< 0.048 U	< 0.042 U	1300	< 0.056 U	< 0.063 U
MW-13	DUP-02	2/21/2021	180-117476-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	< 0.047 U	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	3800	< 0.053 U	< 0.059 U
MW-13	MW-13	2/21/2021	180-117476-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	3500	< 0.056 U	< 0.063 U
MW-13	MW-13	7/15/2021	180-124580-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.15 J	< 0.49 U	0.054 J	< 0.052 U	< 0.045 U	1500	< 0.061 U	< 0.068 U
MW-17	MW17	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-17	MW17	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-2	MW-2	2/17/2021	180-117387-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	< 0.047 U	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	2800	< 0.053 U	< 0.059 U
MW-2	MW-2	7/14/2021	180-124487-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	0.17 J	< 0.4 U	0.065 J	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	1700	< 0.066 U	< 0.074 U
MW-20	MW20	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW20	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW-20	2/23/2021	180-117459-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-20	MW-20	7/15/2021	180-124580-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	0.078 J	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.15 J	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	< 250 U	< 0.064 U	< 0.071 U
MW-22	MW-22	2/23/2021	180-117459-1	< 1.3 U	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.055 U	< 0.076 U	< 0.27 U	< 0.048 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.06 U	< 0.052 U	< 0.45 U	< 0.054 U	< 0.13 U	< 0.063 U	< 0.11 U	< 0.76 U	< 0.049 U	< 0.43 U	< 0.048 U	< 0.046 U	< 0.04 U	680	< 0.054 U	< 0.061 U
MW-22	MW-22	7/15/2021	180-124580-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.15 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	530 J	< 0.066 U	< 0.074 U
MW-26	MW-26	2/17/2021	180-117387-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	0.073 J	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	260 J	< 0.049 U	< 0.055 U
MW-26	SSHS-MW-26-04112024	4/11/2024	1801722801	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-26	MW-26	7/14/2021	180-124487-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.14 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	< 240 U	< 0.066 U	< 0.074 U
MW-3	MW-3	2/17/2021	180-117387-1	< 1.3 U	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.055 U	< 0.076 U	< 0.27 U	< 0.048 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.06 U	< 0.052 U	< 0.45 U	< 0.054 U	< 0.13 U	< 0.063 U	< 0.11 U	< 0.76 U	< 0.049 U	< 0.43 U	< 0.048 U	< 0.046 U	< 0.04 U	16000	< 0.054 U	< 0.061 U
MW-3	DUP-4	7/14/2021	180-124487-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	0.51 J	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	0.093 J	< 0.42 U	0.18 J	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
MW-3	MW-3	7/14/2021	180-124487-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	0.34 J	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	0.15 J	< 0.42 U	0.51 J	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	6400	< 0.069 U	< 0.077 U
MW-30	MW-30	2/19/2021	180-117476-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	< 0.071 U	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	0.046 J	< 0.41 U	0.047 J	< 0.043 U	< 0.038 U	2600	< 0.051 U	< 0.057 U
MW-30	MW-30	7/16/2021	180-124628-1	< 2.3 U	< 0.094 U	< 2.4 U	< 0.08 U	0.11 J	< 0.11 U	< 0.088 U	< 0.11 U	< 0.78 U	< 0.097 U	< 0.13 U	< 0.47 U	< 0.084 U	< 0.097 U	< 0.58 U	0.11 J	< 0.86 U	< 0.1 U	< 0.091 U	< 0.78 U	< 0.095 U	< 0.22 U	< 0.11 U	< 0.19 U	< 1.3 U	0.3	< 0.76 U	< 0.084 U	< 0.081 U	< 0.07 U	880	< 0.095 U	< 0.11 U
MW-30	MW-30	7/26/2019	180-93333-1	< 3.3 UJ	< 0.14 UJ	< 3.5 U	< 0.12 UJ	3.5 J	< 0.16 U	< 0.13 UJ	< 0.16 UJ	< 1.1 R	< 0.14 UJ	1.1	< 0.68 UJ	< 0.12 U	< 0.14 UJ	< 0.85 UJ	< 0.13 UJ	< 1.2 U	< 0.15 UJ	< 0.13 UJ	< 1.1 UJ	< 0.14 UJ	< 0.32 U	< 0.16 UJ	< 0.27 UJ	< 1.9 UJ	1.4 J	< 1.1 UJ	3.4 J	< 0.12 UJ	< 0.1 UJ	-	< 0.14 UJ	< 0.15 UJ
MW-32	MW-32	2/22/2021	180-117425-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	0.34	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	8000	< 0.056 U	< 0.063 U
MW-32	MW-32	7/13/2021	180-124378-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	0.34	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	7700	< 0.059 U	< 0.065 U
MW-33	MW-33	2/19/2021	180-117476-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	4100	< 0.056 U	< 0.063 U
MW-33	MW-33	7/13/2021	180-124378-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 UJ	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 UJ	< 0.056 UJ	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 UJ	< 0.11 UJ	< 0.81 U	0.18	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	3400	< 0.059 U	< 0.065 U
MW-34	MW-34	3/23/2021	180-118872-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
MW-34	MW-34	4/30/2021	180-120955-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 UJ	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	2500	< 0.069 U	< 0.077 U
MW-36	MW-36	4/30/2021	180-120955-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 UJ	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	17000	< 0.066 U	< 0.074 U
MW-36	MW-36	3/23/2021	180-118872-1	< 23 U	< 0.94 U	< 24 U	< 0.8 U	< 0.94 U	< 1.1 U	< 0.88 U	< 1.1 U	< 7.8 U	< 0.97 U	< 1.3 U	< 4.7 U	< 0.84 U	< 0.97 U	< 5.8 U	< 0.92 U	< 8.6 U	< 1 U	< 0.91 U	< 7.8 U	< 0.95 U	< 2.2 U	< 1.1 U	< 1.9 U	< 13 U	< 0.86 U	< 7.6 U	< 0.84 U	< 0.81 U	< 0.7 U	21000	< 0.95 U	< 1.1 U
MW-36	SSHS-MW36	8/22/2018	180-81174-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	0.17 J	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.1 U	< 0.05 U	< 0.057 U	< 0.39 U	< 0.055 U	< 0.19 U	< 0.062 U	< 0.054 U	< 0.15 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.22 U	< 0.051 U	< 0.091 U	< 0.05 U	< 0.048 U	< 0.042 U	-	< 0.056 U	< 0.063 U
MW-38	MW-38	4/30/2021	180-120955-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 UJ	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	2500	< 0.064 U	< 0.071 U
MW-38	MW-38	3/24/2021	180-119009-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	3100	< 0.066 U	< 0.074 U
MW-38	DUP-1	4/30/2021	180-120955-1	< 1.8 U	< 0.071 U	< 1.8 U	< 0.061 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.074 U	< 0.1 U	< 0.36 U	< 0.064 U	< 0.074 U	< 0.44 U	< 0.07 U	< 0.65 U	< 0.08 U	< 0.069 U	< 0.6 U	< 0.073 U	< 0.17 U	< 0.085 U	< 0.14 U	< 1 UJ	< 0.065 U	< 0.58 U	< 0.064 U	< 0.062 U	< 0.054 U	2300	< 0.073 U	< 0.081 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (DEHP)	4-Bromophenyl phenyl ether	Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroaniline)	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				20			50				0.002		0.002	0.002		5	1		5[1]		50			5		10			0.002			5	1	50	1	50	50	50
Location	Sample Name	Sample Date	Lab Report																																			
MW-38	SSHS-MW-38	8/23/2018	180-81247-1	0.092 J	< 0.063 U	< 0.06 U	< 0.047 U	< 0.18 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	6.6 J	< 0.061 U	0.54 J	2.7 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-38	PS-FD-1	8/24/2018	180-81247-1	0.13 J	< 0.065 U	< 0.062 U	< 0.049 U	< 0.18 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	6.4 J	< 0.063 U	< 0.46 U	3.3 J	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-39	SSHS-MW-39	8/23/2018	180-81247-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.18 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	11	< 0.063 U	< 0.46 U	2.3 J	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-4	MW4	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.2 J	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.4 JB	-
MW-4	MW4	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 JB	-
MW-40	MW-40	2/23/2021	180-117459-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	0.56 J	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.8	< 0.59 U
MW-40	MW-40	5/23/2019	180-90525-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 UJ	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 R	< 0.051 U	< 0.57 U	< 0.041 UJ	< 0.056 U	< 0.74 U	< 0.69 U
MW-41	MW-41	2/20/2021	180-117476-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.4 J	< 0.63 U
MW-41	DUP-03	2/20/2021	180-117476-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	3.1 J	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	0.56 J	< 0.039 U	< 0.054 U	2.5 J	< 0.66 U
MW-41	MW-41	7/13/2021	180-124378-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	0.18 J	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	12	< 0.063 U	< 0.46 U	1.4 J	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	0.67 J	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-43	MW-43	2/16/2021	180-117390-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	< 0.4 U	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.1	< 0.59 U
MW-43	MW-43	7/13/2021	180-124378-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	0.15 J	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	10 J	< 0.068 U	< 0.5 U	0.8 J	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	3.9	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-44	SSHS-MW-44	8/23/2018	180-81247-1	0.17 J	< 0.06 U	< 0.057 U	< 0.045 U	< 0.17 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 4.3 U	< 0.058 U	< 0.43 U	2.3 J	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-47	MW-47	2/22/2021	180-117425-1	< 0.058 UJ	< 0.058 UJ	< 0.055 U	< 0.044 UJ	< 0.57 U	< 0.053 UJ	< 0.099 U	< 0.067 U	< 0.047 UJ	< 0.087 UJ	< 0.079 UJ	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 UJ	< 5.6 U	< 0.056 UJ	< 0.41 U	< 0.42 U	< 0.046 U	< 0.039 UJ	< 0.054 UJ	< 0.053 UJ	< 0.057 UJ	< 0.054 UJ	< 0.072 U	< 0.064 U	< 0.065 UJ	< 0.52 UJ	< 0.046 UJ	< 0.51 U	< 0.037 UJ	< 0.05 U	1.1 J	< 0.61 U
MW-47	DUP-01	2/22/2021	180-117425-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.6 J	< 0.63 U
MW-47	MW-47	7/12/2021	180-124354-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.072 U	< 0.53 U	1.5 J	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
MW-47I	MW-47I	10/27/2021	180-129230-1	< 0.06 UJ	< 0.06 UJ	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 UJ	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 UJ	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 UJ	< 0.53 U	< 0.15 U	< 0.19 U	0.98	< 0.63 U
MW-47I	MW-47I	9/10/2021	180-126939-1	< 0.073 UJ	< 0.059 UJ	< 0.82 UJ	< 0.056 UJ	< 0.45 U	< 0.36 UJ	< 0.44 U	< 0.072 U	< 0.042 UJ	< 0.074 U	< 0.068 U	< 0.075 U	< 0.39 UJ	< 0.1 UJ	< 0.096 UJ	11 J	< 0.51 U	< 0.79 U	1.7 J	< 0.064 U	< 0.37 UJ	< 0.56 U	< 0.058 UJ	< 0.26 UJ	< 0.5 UJ	< 0.089 U	< 0.077 U	< 0.45 UJ	< 0.91 R	< 0.072 UJ	< 0.98 U	< 0.27 UJ	< 0.5 UJ	< 0.9 U	< 0.75 U
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731401	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 UT	< 7.1 U	< 0.36 U	< 1.1 U	< 1.6 U	< 0.058 U	< 0.43 U	< 0.49 U	< 0.067 U	< 0.26 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.66 U	< 0.23 U	< 5.6 U	< 0.78 U
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731401	0.080 J	0.42	< 0.18 U	0.088 J	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 UT	< 7.1 U	< 0.36 U	< 1.1 U	< 1.6 U	< 0.058 U	< 0.43 U	< 0.49 U	< 0.067 U	< 0.26 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.66 U	< 0.23 U	< 5.6 U	< 0.78 U
MW-47I	DUP-01	10/27/2021	180-129230-1	0.18 J	0.17 J	< 0.17 U	< 0.051 U	< 0.66 U	0.26 J	< 0.56 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	0.32 J	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.2 U	< 0.61 U	0.2 J	< 0.59 U	< 0.17 U	< 0.21 U	1.2	< 0.71 U
MW-48	MW-48	2/17/2021	180-117387-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	< 0.058 U	< 0.059 U	< 0.47 U	< 0.041 U	< 0.46 U	< 0.033 U	< 0.045 U	0.65 J	< 0.55 U
MW-48	MW-48	4/26/2021	180-120679-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	-	< 0.061 U	0.72 J	0.5 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721201	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721201	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-48R	SSHS-MW-48R-09132023	9/13/2023	1801624601	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	1.4	< 0.74 U
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654471	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	< 0.84 U	< 0.78 U
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654471	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	3.7 J+	< 0.78 U
MW-48R	DUP-01-01162024	1/16/2024	1801682361	< 0.081 U	< 0.081 U	< 0.20 U	< 0.061 U	< 0.79 U	< 0.18 U	< 0.67 U	< 0.094 U	< 0.066 U	< 0.12 U	< 0.11 U	< 0.086 U	< 0.19 U	< 0.050 U	< 0.073 U	< 7.8 U	< 0.40 U	< 0.58 U	< 0.59 U	< 0.064 U	< 0.47 U	< 0.35 U	< 0.074 U	< 0.16 U	< 0.28 U	< 0.10 U	< 0.090 U	< 0.24 U	< 0.73 U	< 0.064 U	< 0.71 U	< 0.21 U	< 0.25 U	1.1 J	< 0.86 U
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682361	0.090 J	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	0.56 J	< 0.055 U	< 0.41 U	< 0.30 U	0.075 J	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	< 0.81 U	< 0.74 U
MW-49	DUP-04	2/17/2021	180-117387-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	< 0.058 U	< 0.059 U	< 0.47 U	< 0.041 U	< 0.46 U	< 0.033 U	< 0.045 U	1.6	< 0.55 U
MW-49	MW-49	2/17/2021	180-117387-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	< 0.058 U	< 0.059 U	< 0.47 U	< 0.041 U	< 0.46 U	< 0.033 U	< 0.045 U	1.5	< 0.55 U
MW-49	MW-49	4/28/2021	180-120857-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.5	< 0.66 U
MW-50I	SSHS-RI-MW-50I	2/12/2021	180-117176-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.5	< 0.63 U
MW-50I	MW-50I	4/28/2021	180-120857-1	< 0.063 U	< 0.063 UJ	< 0.06 UJ	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 UJ	< 0.038 UJ	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 UJ	< 0.059 UJ	< 0.057 UJ	< 0.062 UJ	< 0.059 UJ	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 R	< 0.049 UJ	< 0.55 U	< 0.039 UJ	< 0.054 U	1.7	< 0.66 U
MW-50R	SSHS-MW-50R-04082024	4/8/2024	1801720381	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-50R	SSHS-MW-50R-09142023	9/14/2023	1801625611	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	0.99 J	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	< 0.84 U	< 0.78 UT
MW-50S	SSHS-RI-MW-50S	2/12/2021	180-117176-1	< 0.058 U	< 0.058 U	< 0.055 U	< 0.044 U	< 0.57 U	< 0.053 U	< 0.099 U	< 0.067 U	< 0.047 U	< 0.087 U	< 0.079 U	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.056 U	< 0.41 U	< 0.42 U	< 0.046 U	< 0.039 U	< 0.054 U	< 0.053 U	< 0.057 U	< 0.054 U	< 0.072 U	< 0.064 U	< 0.065 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.037 U	< 0.05 U	0.85 J	< 0.61 U
MW-50S	MW-50S	4/28/2021	180-120857-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	0.11 J	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	0.52 J	0.58 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.9	< 0.66 U
MW-51	DUP-05	2/12/2021	180-117176-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 UJ	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-51	SSHS-RI-MW-51	2/12/2021	180-117176-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	0.57 J	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	1.9	1.1 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	2.7	< 0.69 U
MW-51	SSHS-DUP-04-09142023	9/14/2023	1801625601	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	13 J	< 0.33 U	< 0.48 U	< 0.49 UJ	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721201	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-51	SSHS-MW-51-09142023	9/14/2023	1801625601	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 UJ	< 0.33 U	< 0.48 U	0.52 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-51	SSHS-MW-51-01182024	1/18/2024	1801682891	< 0.081 U	< 0.081 U	< 0.20 U	< 0.061 UT	< 0.79 UT	< 0.18 U	< 0.67 U	< 0.094 U	< 0.066 U	< 0.12 U	< 0.11 U	< 0.086 UT	< 0.19 U	< 0.050 U	< 0.073 U	< 7.8 U	< 0.40 U	< 0.58 U	< 0.59 U	< 0.064 UT	< 0.47 UT	< 0.35 U	< 0.074 U	< 0.16 UT	< 0.28 U	< 0.10 U	< 0.090 UT	< 0.24 U	< 0.73 U	< 0.064 UT	< 0.71 U	< 0.21 UT	< 0.25 U	1.0 JT	< 0.86 U
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653531	0.22 J	0.23 J	< 0.20 UJ	< 0.061 UJ	-	0.33 J	< 0.67 U	< 0.094 UJ	< 0.066 UT	< 0.12 UJ	< 0.11 UJ	< 0.086 UJ	< 0.19 UJ	< 0.050 UJ	< 0.073 UJ	< 7.8 U	< 0.40 UJ	< 0.58 U	< 0.59 UT	< 0.064 UJ	< 0.47 UJ	< 0.35 UJ	0.37 T	< 0.16 UJ	< 0.28 UJ	< 0.10 UJ	< 0.090 UJ	< 0.24 UJ	< 0.73 UJ	0.28 J	< 0.71 UJ	< 0.21 UJ	< 0.25 UJ	7.1 J	< 0.86 U
MW-52	SSHS-RI-MW-52	2/12/2021	180-117176-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-52	DUP-2	4/28/2021	180-120857-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 UJ	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	2.3	< 0.66 U
MW-52	MW-52	4/28/2021	180-120857-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	0.69 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.8	< 0.66 U
MW-53	MW-53	2/17/2021	180-117387-1	< 0.054 UJ	< 0.054 UJ	< 0.052 UJ	< 0.041 UJ	< 0.53 U	< 0.049 UJ	< 0.093 U	< 0.063 UJ	< 0.044 UJ	< 0.081 UJ	< 0.073 UJ	< 0.058 UJ	< 0.056 UJ	< 0.033 UJ	< 0.048 UJ	< 5.2 U	< 0.053 UJ	< 0.39 U	< 0.39 U	< 0.043 UJ	< 0.037 UJ	< 0.051 UJ	< 0.049 UJ	< 0.053 UJ	< 0.051 UJ	< 0.068 U	< 0.06 UJ	< 0.061 UJ	< 0.49 UJ	< 0.043 UJ	< 0.47 UJ	< 0.034 UJ	< 0.047 UJ	1.4 J	< 0.57 UJ
MW-53	MW-53	4/26/2021	180-120679-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	0.46 J	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-53	SSHS-MW-53-09042023	9/4/2023	1801619191	< 0.065 UT	< 0.065 UT	< 0.16 UT	< 0.049 UT	< 0.63 UT	< 0.14 UT	< 0.54 U	< 0.075 UT	< 0.053 UT	< 0.097 UT	< 0.088 UT	< 0.069 UT	< 0.15 UT	< 0.040 UT	< 0.058 U	< 6.2 U	< 0.32 UT	< 0.46 UT	1.6 JT	< 0.051 UT	< 0.38 UT	< 0.28 UT	< 0.059 UT	< 0.13 UT	< 0.22 UT	< 0.081 UT	< 0.072 UT	< 0.19 UT	< 0.58 UT	< 0.051 UT	< 0.57 UT	< 0.17 UT	< 0.20 UT	2.1 T	< 0.69 U
MW-54	MW-54	2/16/2021	180-117390-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	< 0.093 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	< 0.39 U	< 0.39 U	< 0.043 U	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	< 0.068 U	< 0.06 U	< 0.061 U	< 0.49 U	< 0.043 U	1.5	< 0.034 U	< 0.047 U	0.99	< 0.57 U
MW-54	MW-54	4/27/2021	180-120743-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	0.2	< 0.049 U	0.5	0.4	0.2	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	0.56 J	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	0.43	0.38	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	< 0.69 U	< 0.63 U
MW-54R	SSHS-MW-54R-04052024	4/5/2024	1801720021	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	1.0 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 UT
MW-55	MW-55	2/16/2021	180-117390-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	< 0.058 U	< 0.059 U	< 0.47 U	< 0.041 U	0.7 J	< 0.033 U	< 0.045 U	0.99	< 0.55 U
MW-55	MW-55	4/29/2021	180-121010-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	6.4 J	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1	< 0.66 U
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721201	< 0.063 UT	< 0.063 UT	< 0.15 UT	< 0.047 UT	< 0.61 UT	< 0.14 UT	< 0.52 U	< 0.072 UT	< 0.051 UT	< 0.093 UT	< 0.085 UT	< 0.066 UT	< 0.15 UT	< 0.038 UT	< 0.056 U	< 6.0 UT	< 0.31 UT	< 0.90 UT	< 1.4 UT	< 0.049 UT	< 0.36 UT	< 0.42 UT	< 0.057 UT	< 0.22 UT	< 0.21 UT	< 0.078 UT	< 0.069 UT	< 0.18 UT	< 0.56 UT	< 0.049 UT	< 0.55 UT	< 0.56 UT	< 0.19 UT	< 4.7 UT	< 0.66 UT
MW-55	DUP-01-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	1.4	< 0.69 U
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	2.2	< 0.69 U
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 UJ	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 UT	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 UJ	< 0.28 U	< 0.059 UT	< 0.13 UJ	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 UT	< 0.58 UJ	< 0.051 UT	< 0.57 U	< 0.17 UJ	< 0.20 U	< 0.74 U	< 0.69 U
MW-55	SSHS-MW-55-09132023	9/13/2023	1801624601	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	0.77 J	1.1 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	0.95 J	< 0.71 U
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682361	< 0.074 UT	< 0.074 UT	< 0.18 UT	< 0.056 UT	< 0.72 UT	< 0.16 UT	< 0.61 U	< 0.085 UT	< 0.060 UT	< 0.11 UT	< 0.10 UT	< 0.078 UT	< 0.17 UT	< 0.045 UT	< 0.066 U	< 7.1 U	< 0.36 UT	< 0.53 UT	< 0.53 U	< 0.058 UT	< 0.43 UT	< 0.32 U	< 0.067 UT	< 0.15 UT	< 0.25 UT	< 0.092 UT	< 0.082 UT	< 0.22 UT	< 0.66 UT	< 0.058 UT	< 0.64 UT	< 0.19 UT	< 0.23 UT	2.1 T	< 0.78 U
MW-56	MW-56	2/17/2021	180-117387-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	< 0.058 U	< 0.059 U	< 0.47 U	< 0.041 U	< 0.46 U	< 0.033 U	< 0.045 U	1.4	< 0.55 U
MW-56	MW-56	4/29/2021	180-121010-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	6.6 J	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	1	< 0.69 U
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	< 0.74 U	< 0.69 UT
MW-57	MW-57	2/18/2021	180-117476-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	< 0.093 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	< 0.39 U	< 0.39 U	< 0.043 U	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	< 0.068 U	< 0.06 U	< 0.061 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.034 U	< 0.047 U	1.3	< 0.57 U
MW-57	MW-57	4/29/2021	180-121010-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	0.76 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.4	< 0.66 U
MW-57	DUP-01	7/13/2022	1801412391	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	13	< 0.32 U	< 0.46 U	1.5 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	0.87 J	< 0.69 U
MW-57	MW-57	7/13/2022	1801412391	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	< 0.74 U	< 0.69 U
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	0.28	0.17 J	0.43	0.30	0.32	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 UT	< 0.051 U	< 0.38 UT	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	0.30	0.39	< 0.19 U	< 0.58 UT	< 0.051 U	< 0.57 U	< 0.17 UT	< 0.20 U	1.3	< 0.69 U
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653531	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	0.27 J	< 0.20 U	4.7 J+	< 0.69 U
MW-57R	SSHS-MW-57R-09142023	9/14/2023	1801625601	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682361	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	2.4	< 0.74 U
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721201	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-58	MW-58	2/21/2021	180-117476-1	< 0.056 UJ	< 0.056 UJ	< 0.053 UJ	< 0.042 UJ	< 0.55 U	< 0.051 UJ	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 UJ	< 0.076 U	< 0.059 U	< 0.058 UJ	< 0.034 UJ	< 0.05 UJ	< 5.4 U	< 0.054 UJ	2.4	< 0.41 U	< 0.044 U	< 0.038 UJ	< 0.053 UJ	< 0.051 UJ	< 0.055 UJ	< 0.053 UJ	< 0.07 U	< 0.062 U	< 0.063 UJ	< 0.5 R	< 0.044 UJ	< 0.49 U	< 0.035 UJ	< 0.048 UJ	1.9 J	< 0.59 U
MW-58	MW-58	4/30/2021	180-120955-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	2.6	< 0.66 U
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625611	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.10 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 0.55 U	< 0.56 U	< 0.061 U	< 0.45 U	< 0.33 U	< 0.070 U	< 0.15 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.20 U	< 0.24 U	1.2 J	< 0.82 UT
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625611	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.10 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 0.55 U	< 0.56 U	< 0.061 U	< 0.45 U	< 0.33 U	< 0.070 U	< 0.15 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.20 U	< 0.24 U	1.7 J	< 0.82 UT
MW-59I	MW-59I	2/19/2021	180-117476-1	< 0.058 U	< 0.058 U	< 0.055 U	< 0.044 U	< 0.57 U	< 0.053 U	< 0.099 U	< 0.067 U	< 0.047 U	< 0.087 U	< 0.079 U	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.056 U	0.52 J	< 0.42 U	< 0.046 U	< 0.039 U	< 0.054 U	< 0.053 U	< 0.057 U	< 0.054 U	< 0.072 U	< 0.064 U	< 0.065 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.037 U	< 0.05 U	0.88 J	< 0.61 U
MW-59I	MW-59I	4/29/2021	180-121010-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	0.87 J	< 0.66 U
MW-59I	MW-59I	7/12/2022	1801412391	< 0.074 UT	< 0.074 UT	< 0.18 UT	< 0.056 UT	< 0.72 UT	< 0.16 UT	< 0.61 UT	< 0.085 U	< 0.060 UT	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 UT	< 0.045 UT	< 0.066 UT	< 7.1 UT	< 0.36 UT	< 0.53 U	0.91 J	< 0.058 UT	< 0.43 UT	< 0.32 UT	< 0.067 UT	< 0.15 UT	< 0.25 UT	< 0.092 U	< 0.082 U	< 0.22 UT	< 0.66 UT	< 0.058 UT	< 0.64 UT	< 0.19 UT	< 0.23 UT	< 0.84 UT	< 0.78 UT

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	TPH-DRO	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	1	5	50	50	0.04	0.5	5	5	0.002		50			10	5	5	5	0.4				50	1	50	1	50					
Location	Sample Name	Sample Date	Lab Report																																	
MW-38	SSHS-MW-38	8/23/2018	180-81247-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	0.12 J	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.1 U	< 0.052 U	< 0.06 U	< 0.4 U	< 0.057 U	< 0.2 U	< 0.064 U	< 0.056 U	< 0.16 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.23 U	< 0.053 U	< 0.094 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
MW-38	PS-FD-1	8/24/2018	180-81247-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	0.14 J	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.11 U	< 0.054 U	< 0.062 U	< 0.42 U	< 0.059 U	< 0.21 U	< 0.067 U	< 0.058 U	< 0.17 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.24 U	0.16 J	< 0.098 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
MW-39	SSHS-MW-39	8/23/2018	180-81247-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.11 U	< 0.054 U	< 0.062 U	< 0.42 U	< 0.059 U	< 0.21 U	< 0.067 U	< 0.058 U	< 0.17 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.24 U	0.14 J	< 0.098 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
MW-4	MW4	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-4	MW4	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-40	MW-40	2/23/2021	180-117459-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	0.055 J	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	630	< 0.053 U	< 0.059 U
MW-40	MW-40	5/23/2019	180-90525-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	0.18 J	< 0.5 UJ	0.09 J	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 UJ	< 0.058 UJ	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	970	< 0.061 U	< 0.068 U
MW-41	MW-41	2/20/2021	180-117476-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	1200	< 0.056 U	< 0.063 U
MW-41	DUP-03	2/20/2021	180-117476-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	1100	< 0.059 U	< 0.065 U
MW-41	MW-41	7/13/2021	180-124378-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	0.15 J	< 0.37 U	0.6	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.18 J	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	1000	< 0.061 U	< 0.068 U
MW-43	MW-43	2/16/2021	180-117390-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	< 0.047 U	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	-	< 0.053 U	< 0.059 U
MW-43	MW-43	7/13/2021	180-124378-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.14 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	< 250 U	< 0.066 U	< 0.074 U
MW-44	SSHS-MW-44	8/23/2018	180-81247-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	0.08 J	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.1 U	< 0.05 U	< 0.057 U	< 0.39 U	< 0.055 U	< 0.19 U	< 0.062 U	< 0.054 U	< 0.15 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.22 U	0.11 J	< 0.091 U	< 0.05 U	< 0.048 U	< 0.042 U	-	< 0.056 U	< 0.063 U
MW-47	MW-47	2/22/2021	180-117425-1	< 1.3 UJ	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 UJ	< 0.062 U	< 0.05 UJ	< 0.062 UJ	< 0.44 UJ	< 0.055 UJ	< 0.076 U	< 0.27 UJ	< 0.048 U	< 0.055 UJ	< 0.33 UJ	< 0.053 UJ	< 0.49 U	< 0.06 UJ	< 0.052 UJ	< 0.45 U	< 0.054 UJ	< 0.13 U	< 0.063 U	< 0.11 UJ	< 0.76 UJ	< 0.049 UJ	< 0.43 UJ	< 0.048 U	< 0.046 UJ	< 0.04 UJ	< 230 U	< 0.054 UJ	< 0.061 UJ
MW-47	DUP-01	2/22/2021	180-117425-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	0.074 J	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-47	MW-47	7/12/2021	180-124354-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	1.2	< 0.061 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	0.095 J	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	< 250 U	< 0.069 U	< 0.077 U
MW-47I	MW-47I	10/27/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 UJ	< 0.34 U	< 0.055 UJ	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.12 J	< 0.45 U	< 0.05 U	< 0.14 UJ	< 0.3 U	< 220 U	< 0.23 U	< 0.21 U
MW-47I	MW-47I	9/10/2021	180-126939-1	< 1.4 U	< 0.57 U	< 6.2 U	< 0.75 UJ	< 0.097 U	< 0.084 UJ	< 0.078 U	< 0.1 UJ	< 0.42 R	< 0.34 UJ	< 0.069 U	< 0.36 UJ	< 0.42 UJ	< 0.085 UJ	< 0.32 UJ	< 0.1 UJ	< 0.63 U	< 0.49 UJ	< 0.46 UJ	< 0.45 UJ	< 0.42 UJ	< 1.2 U	< 0.14 UJ	< 0.29 UJ	< 2.3 U	< 0.13 U	< 0.27 UJ	< 0.063 U	< 0.36 UJ	< 0.58 U	250 J	< 0.5 UJ	< 0.38 UJ
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731401	< 1.7 U	< 0.20 U	< 3.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.63 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.18 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731401	< 1.7 U	< 0.20 U	< 3.7 U	< 0.40 U	0.18 J	0.15 J	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.63 U	< 0.21 U	0.12 J	< 0.42 U	0.13 J	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	0.86	< 0.55 U	0.32	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-47I	DUP-01	10/27/2021	180-129230-1	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.2 U	0.41 J	< 0.39 U	0.4 J	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.2 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.15 J	< 0.51 U	< 0.056 U	0.37 J	< 0.34 U	< 210 U	< 0.26 U	< 0.23 U
MW-48	MW-48	2/17/2021	180-117387-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	< 0.069 U	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	< 230 U	< 0.049 U	< 0.055 U
MW-48	MW-48	4/26/2021	180-120679-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721201	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721201	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-48R	SSHS-MW-48R-09132023	9/13/2023	1801624601	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	0.063 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654471	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654471	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-48R	DUP-01-01162024	1/16/2024	1801682361	< 1.8 U	< 0.22 U	< 1.9 U	< 0.44 U	0.12 J	< 0.086 U	< 0.070 U	< 0.086 U	< 0.62 U	< 0.17 U	< 0.11 U	< 0.38 U	< 0.24 U	< 0.078 U	< 0.47 U	< 0.074 U	< 0.69 U	< 0.55 U	< 0.45 U	< 0.63 U	< 0.24 U	< 1.2 U	< 0.089 U	< 0.15 U	< 1.1 U	0.25	< 0.61 U	0.087 J	< 0.19 U	< 0.41 U	-	< 0.32 U	< 0.28 U
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682361	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	0.093 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-49	DUP-04	2/17/2021	180-117387-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	< 0.069 U	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	< 230 U	< 0.049 U	< 0.055 U
MW-49	MW-49	2/17/2021	180-117387-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	< 0.069 U	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	< 230 U	< 0.049 U	< 0.055 U
MW-49	MW-49	4/28/2021	180-120857-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-50I	SSHS-RI-MW-50I	2/12/2021	180-117176-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-50I	MW-50I	4/28/2021	180-120857-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 UJ	< 0.48 R	< 0.06 UJ	< 0.082 U	< 0.29 UJ	< 0.052 U	< 0.06 UJ	< 0.36 UJ	< 0.057 UJ	< 0.53 U	< 0.064 U	< 0.056 UJ	< 0.48 U	< 0.059 UJ	< 0.14 U	< 0.068 UJ	< 0.11 UJ	< 0.81 UJ	< 0.053 U	< 0.47 UJ	< 0.052 U	< 0.05 UJ	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-50R	SSHS-MW-50R-04082024	4/8/2024	1801720381	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-50R	SSHS-MW-50R-09142023	9/14/2023	1801625611	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-50S	SSHS-RI-MW-50S	2/12/2021	180-117176-1	< 1.3 U	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.055 U	< 0.076 U	< 0.27 U	< 0.048 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.06 U	< 0.052 U	< 0.45 U	< 0.054 U	< 0.13 U	< 0.063 U	< 0.11 U	< 0.76 U	< 0.049 U	< 0.43 U	< 0.048 U	< 0.046 U	< 0.04 U	< 230 U	< 0.054 U	< 0.061 U
MW-50S	MW-50S	4/28/2021	180-120857-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-51	DUP-05	2/12/2021	180-117176-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-51	SSHS-RI-MW-51	2/12/2021	180-117176-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.075 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-51	SSHS-DUP-04-09142023	9/14/2023	1801625601	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	0.11 J	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.065 J	< 0.51 U	0.10 J	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721201	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-51	SSHS-MW-51-09142023	9/14/2023	1801625601	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 UJ	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.073 J	< 0.51 U	< 0.056 UJ	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-51	SSHS-MW-51-01182024	1/18/2024	1801682891	< 1.8 U	< 0.22 U	< 1.9 U	< 0.44 U	< 0.075 UT	< 0.086 UT	< 0.070 U	< 0.086 UT	< 0.62 UT	< 0.17 U	< 0.11 UT	< 0.38 UT	< 0.24 U	< 0.078 U	< 0.47 U	< 0.074 UT	< 0.69 U	< 0.55 U	< 0.45 U	< 0.63 U	< 0.24 U	< 1.2 U	< 0.089 U	< 0.15 U	< 1.1 U	< 0.069 U	< 0.61 U	< 0.068 U	< 0.19 U	< 0.41 UT	-	< 0.32 UT	< 0.28 U
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653531	< 1.8 UJ	< 0.22 UJ	< 1.9 UT	< 0.44 UJ	< 0.075 UJ	< 0.086 UJ	< 0.070 UJ	0.17 J	-	< 0.17 UJ	< 0.11 UJ	< 0.38 UJ	< 0.24 UJ	0.42 J	< 0.47 UJ	0.37 J	< 0.69 U	< 0.55 UJ	< 0.45 UJ	< 0.63 UJ	< 0.24 UJ	< 1.2 U	< 0.089 UJ	< 0.15 UJ	< 1.1 UJ	< 0.069 UJ	< 0.61 UJ	< 0.068 UJ	0.41 J	< 0.41 UJ	-	< 0.32 UJ	< 0.28 UJ
MW-52	SSHS-RI-MW-52	2/12/2021	180-117176-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-52	DUP-2	4/28/2021	180-120857-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-52	MW-52	4/28/2021	180-120857-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-53	MW-53	2/17/2021	180-117387-1	< 1.2 UJ	< 0.05 UJ	< 1.3 UJ	< 0.043 UJ	0.059 J	< 0.058 UJ	< 0.047 UJ	< 0.058 UJ	< 0.41 UJ	< 0.052 UJ	< 0.071 UJ	< 0.25 UJ	< 0.045 UJ	< 0.052 UJ	< 0.31 UJ	< 0.049 UJ	< 0.46 U	< 0.056 UJ	< 0.048 UJ	< 0.42 UJ	< 0.051 UJ	< 0.12 U	< 0.059 UJ	< 0.099 UJ	< 0.71 UJ	< 0.046 UJ	< 0.41 UJ	< 0.045 UJ	< 0.043 UJ	< 0.038 UJ	< 230 U	< 0.051 UJ	< 0.057 UJ
MW-53	MW-53	4/26/2021	180-120679-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-53	SSHS-MW-53-09042023	9/4/2023	1801619191	< 1.5 UT	< 0.17 UT	< 1.5 UT	< 0.35 UT	< 0.060 UT	< 0.069 UT	< 0.056 UT	< 0.069 UT	< 0.50 UT	< 0.13 UT	< 0.085 UT	< 0.30 UT	< 0.19 UT	< 0.062 UT	< 0.37 UT	< 0.059 UT	< 0.55 UT	< 0.44 UT	< 0.36 UT	< 0.50 UT	< 0.19 UT	< 0.94 U	< 0.071 UT	< 0.12 UT	< 0.85 UT	0.12 JT	< 0.49 UT	< 0.054 UT	< 0.15 UT	< 0.33 UT	-	< 0.25 UT	< 0.22 UT
MW-54	MW-54	2/16/2021	180-117390-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	< 0.071 U	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	< 0.046 U	< 0.41 U	< 0.045 U	< 0.043 U	< 0.038 U	-	< 0.051 U	< 0.057 U
MW-54	MW-54	4/27/2021	180-120743-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	0.071 J	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	0.31	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 UJ	< 0.051 U	< 0.45 U	0.063 J	< 0.048 U	< 0.042 U	< 210 U	< 0.056 U	< 0.063 U
MW-54R	SSHS-MW-54R-04052024	4/5/2024	1801720021	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-55	MW-55	2/16/2021	180-117390-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	< 0.069 U	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	-	< 0.049 U	< 0.055 U
MW-55	MW-55	4/29/2021	180-121010-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721201	< 1.4 UT	< 0.17 UT	< 3.1 U	< 0.34 UT	< 0.058 UT	< 0.066 UT	< 0.054 UT	< 0.066 UT	< 0.48 UT	< 0.13 UT	< 0.082 UT	< 0.54 UT	< 0.18 UT	< 0.060 UT	< 0.36 UT	< 0.057 UT	< 0.53 UT	< 0.42 UT	< 0.35 UT	< 0.48 UT	< 0.19 UT	< 0.90 UT	< 0.068 UT	< 0.11 UT	< 0.81 UT	< 0.15 UT	< 0.47 UT	< 0.052 UT	< 0.14 UT	< 0.31 UT	-	< 0.24 UT	< 0.22 UT
MW-55	DUP-01-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.080 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.094 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	-	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 UT	< 0.37 U	< 0.059 UJ	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 UT	< 0.94 U	< 0.071 U	< 0.12 UT	< 0.85 U	< 0.055 UT	< 0.49 U	< 0.054 U	< 0.15 UJ	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-55	SSHS-MW-55-09132023	9/13/2023	1801624601	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.074 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682361	< 1.7 UT	< 0.20 UT	< 1.7 U	< 0.40 UT	< 0.068 UT	< 0.078 UT	< 0.064 UT	< 0.078 UT	< 0.56 UT	< 0.15 UT	< 0.097 UT	< 0.34 UT	< 0.21 UT	0.11 JT	< 0.42 UT	3.0 T	< 0.62 U	< 0.50 UT	< 0.41 UT	< 0.57 UT	< 0.22 UT	< 1.1 U	< 0.081 U	< 0.14 UT	< 0.96 U	0.083 JT	< 0.55 UT	< 0.061 UT	< 0.17 UT	< 0.37 UT	-	< 0.29 UT	< 0.25 UT
MW-56	MW-56	2/17/2021	180-117387-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	< 0.069 U	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	< 230 U	< 0.049 U	< 0.055 U
MW-56	MW-56	4/29/2021	180-121010-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	< 220 U	< 0.061 U	< 0.068 U
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-57	MW-57	2/18/2021	180-117476-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	< 0.071 U	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	< 0.046 U	< 0.41 U	< 0.045 U	< 0.043 U	< 0.038 U	240 J	< 0.051 U	< 0.057 U
MW-57	MW-57	4/29/2021	180-121010-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 270 U	< 0.059 U	< 0.065 U
MW-57	DUP-01	7/13/2022	1801412391	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.14 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-57	MW-57	7/13/2022	1801412391	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.12 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	0.17 J	< 0.069 U	< 0.056 U	< 0.069 UT	< 0.50 UT	< 0.13 UT	0.40	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 UT	< 0.55 UT	< 0.44 UT	< 0.36 UT	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.12 J	< 0.49 U	0.17 J	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653531	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	1.7 J+	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-57R	SSHS-MW-57R-09142023	9/14/2023	1801625601	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.061 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682361	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	0.11 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721201	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-58	MW-58	2/21/2021	180-117476-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 UJ	< 0.048 UJ	< 0.059 UJ	< 0.43 R	< 0.053 UJ	< 0.073 U	< 0.26 UJ	< 0.047 UJ	< 0.053 UJ	< 0.32 UJ	< 0.051 UJ	< 0.47 U	< 0.058 UJ	< 0.05 UJ	< 0.43 UJ	< 0.053 UJ	< 0.12 U	< 0.061 UJ	< 0.1 UJ	< 0.73 U	< 0.047 UJ	< 0.42 UJ	< 0.047 U	< 0.045 UJ	< 0.039 U	1400	< 0.053 UJ	< 0.059 UJ
MW-58	MW-58	4/30/2021	180-120955-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	2300	< 0.059 U	< 0.065 U
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625611	< 1.8 U	< 0.21 U	< 1.8 U	< 0.42 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.10 U	< 0.36 U	< 0.22 U	< 0.074 U	< 0.44 U	< 0.070 U	< 0.65 U	< 0.52 U	< 0.43 U	< 0.60 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1.0 U	< 0.065 U	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	-	< 0.30 U	< 0.27 U
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625611	< 1.8 U	< 0.21 U	< 1.8 U	< 0.42 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.10 U	< 0.36 U	< 0.22 U	< 0.074 U	< 0.44 U	< 0.070 U	< 0.65 U	< 0.52 U	< 0.43 U	< 0.60 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1.0 U	< 0.065 U	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	-	< 0.30 U	< 0.27 U
MW-59I	MW-59I	2/19/2021	180-117476-1	< 1.3 U	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.055 U	< 0.076 U	< 0.27 U	< 0.048 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.06 U	< 0.052 U	< 0.45 U	< 0.054 U	< 0.13 U	< 0.063 U	< 0.11 U	< 0.76 U	< 0.049 U	< 0.43 U	< 0.048 U	< 0.046 U	< 0.04 U	< 230 U	< 0.054 U	< 0.061 U
MW-59I	MW-59I	4/29/2021	180-121010-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 260 U	< 0.059 U	< 0.065 U
MW-59I	MW-59I	7/12/2022	1801412391	< 1.7 UT	< 0.20 UT	< 1.7 U	< 0.40 UT	< 0.068 UT	< 0.078 UT	< 0.064 UT	< 0.078 UT	< 0.56 UT	< 0.15 UT	< 0.097 U	< 0.34 UT	< 0.21 UT	< 0.070 UT	< 0.42 UT	< 0.067 UT	< 0.62 UT	< 0.50 UT	< 0.41 UT	< 0.57 UT	< 0.22 UT	< 1.1 U	< 0.081 UT	< 0.14 UT	< 0.96 UT	0.15 JT	< 0.55 UT	< 0.061 UT	< 0.17 UT	< 0.37 UT	-	< 0.29 UT	< 0.25 UT

DRAFT

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (DEHP)	4-Bromophenyl phenyl ether	Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroaniline)	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				20			50				0.002		0.002	0.002		5	1		5[1]		50			5		10			0.002			5	1	50	1	50	50	50
Location	Sample Name	Sample Date	Lab Report																																			
MW-59S	MW-59S	2/19/2021	180-117476-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	0.55 J	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.2	< 0.59 U
MW-59S	MW-59S	4/29/2021	180-121010-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1	< 0.66 U
MW-59S	MW-59S	7/13/2022	1801412391	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-5I	SSHS-MW-5I-04102024	4/10/2024	1801721871	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	0.072 J	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-5I	SSHS-MW-5I-09132023	9/13/2023	1801624611	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	3.2 J+	< 0.78 U
MW-5S	MW5	5/16/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.2 JB	-
MW-5S	MW5	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1 JB	-
MW-5S	MW-5	2/23/2021	180-117459-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	1.5	< 0.63 U
MW-5S	MW-5	7/15/2021	180-124580-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	1.3 J	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	0.79 J	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-60	MW-60	2/18/2021	180-117476-1	< 0.058 U	< 0.058 U	< 0.055 U	< 0.044 U	< 0.57 U	< 0.053 U	< 0.099 U	< 0.067 U	< 0.047 U	< 0.087 U	< 0.079 U	< 0.062 U	< 0.06 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.056 U	0.57 J	< 0.42 U	< 0.046 U	< 0.039 U	< 0.054 U	< 0.053 U	< 0.057 U	< 0.054 U	< 0.072 U	< 0.064 U	< 0.065 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.037 U	< 0.05 U	0.77 J	< 0.61 U
MW-60	MW-60	4/29/2021	180-121010-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-60	MW-60	7/12/2022	1801412391	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	0.67 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-60IR	SSHS-MW-60IR-04052024	4/5/2024	1801720021	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-60SR	SSHS-MW-60SR-04052024	4/5/2024	1801720021	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-61	MW-61	2/16/2021	180-117390-1	< 0.052 U	< 0.052 U	< 0.05 U	< 0.04 U	< 0.51 U	< 0.048 U	< 0.09 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 U	< 0.032 U	< 0.047 U	< 5 U	< 0.051 U	< 0.37 U	< 0.38 U	< 0.041 U	< 0.035 U	< 0.049 U	< 0.048 U	< 0.052 U	< 0.049 U	< 0.065 U	< 0.058 U	< 0.059 U	< 0.47 U	< 0.041 U	1.7	< 0.033 U	< 0.045 U	1.3	< 0.55 U
MW-61	MW-61	4/27/2021	180-120743-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	0.13 J	0.095 J	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	0.58 J	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 UJ	< 0.059 U	0.097 J	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 UJ	< 0.55 U	< 0.039 UJ	< 0.054 U	< 0.71 U	< 0.66 U
MW-61	MW-61	7/12/2022	1801412391	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	0.079 J	< 0.055 U	0.11 J	0.12 J	0.11 J	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	0.12 J	0.13 J	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-62	MW-62	2/16/2021	180-117390-1	< 0.052 UJ	< 0.052 UJ	< 0.05 UJ	< 0.04 UJ	< 0.51 U	< 0.048 UJ	< 0.09 U	< 0.06 UJ	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.054 UJ	< 0.032 UJ	< 0.047 U	< 5 U	< 0.051 UJ	< 0.37 U	< 0.38 UJ	< 0.041 U	< 0.035 R	< 0.049 UJ	< 0.048 UJ	< 0.052 UJ	< 0.049 UJ	< 0.065 U	< 0.058 U	< 0.059 UJ	< 0.47 UJ	< 0.041 UJ	2.5	< 0.033 UJ	< 0.045 U	1 J	< 0.55 U
MW-62	MW-62	4/27/2021	180-120743-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	0.54 J	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-62	MW-62	7/12/2022	1801412391	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	< 0.81 U	< 0.74 U
MW-62R	SSHS-MW-62R-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-62R	SSHS-MW-62R-09142023	9/14/2023	1801625611	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	1.2 J+	< 0.74 UT
MW-63I	MW-63I	2/18/2021	180-117476-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	0.51 J	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	< 0.64 U	< 0.59 U
MW-63I	MW-63I	4/29/2021	180-121010-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	0.98	< 0.63 U
MW-63I	SSHS-MW-63I-09132023	9/13/2023	1801624611	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	1.7 J+	< 0.74 U
MW-63S	MW-63S	2/18/2021	180-117476-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	< 0.093 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	0.71 J	< 0.39 U	< 0.043 U	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	< 0.068 U	< 0.06 U	< 0.061 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.034 U	< 0.047 U	1.3	< 0.57 U
MW-63S	MW-63S	4/29/2021	180-121010-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-63S	SSHS-MW-63S-09132023	9/13/2023	1801624611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	1.8 J+	< 0.69 U
MW-64I	MW-64I	2/20/2021	180-117476-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	0.52 J	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	0.73 J	< 0.63 U
MW-64I	SSHS-MW-64I-04052024	4/5/2024	1801720021	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-64I	SSHS-MW-64I-09122023	9/12/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	0.087 J	< 0.055 U	0.12 J	0.15 J	0.076 J	< 0.16 U	< 0.042 UJ	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	0.11 J	0.12 J	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 UT	< 0.21 U	< 0.77 U	< 0.71 U
MW-64I	MW-64I	4/28/2021	180-120857-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	1.8	< 0.74 U
MW-64S	MW-64S	2/20/2021	180-117476-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	0.55 J	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	0.74 J	< 0.66 U
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	0.71 J	1.1 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 UT
MW-64S	MW-64S	4/28/2021	180-120857-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	1.9	< 0.78 U
MW-65	MW-65	2/20/2021	180-117476-1	< 0.056 U	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	1	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.3	< 0.59 U
MW-65	SSHS-MW-65-08152022	8/15/2022	1801429571	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 UT	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 UT	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 UT	< 0.31 U	0.61 JT	2.5 J	< 0.049 UT	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.069 UT	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	1.2 T	< 0.66 UT
MW-65	SSHS-DUP1-08152022	8/15/2022	1801429571	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	1.8 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	0.86 J	< 0.69 U
MW-65	MW-65	4/26/2021	180-120679-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	0.64 J	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-65	DUP-3	4/26/2021	180-120679-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.072 U	0.67 J	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
MW-65R	SSHS-MW-65R-04082024	4/8/2024	1801720411	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-65R	SSHS-MW-65R-09142023	9/14/2023	1801625611	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	0.90 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 UT
MW-66I	MW-66I	2/20/2021	180-117476-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-66I	SSHS-MW-66I-09122023	9/12/2023	1801624611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 UJ	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 UT	< 0.20 U	1.7 J+	< 0.69 U
MW-66I	MW-66I	4/28/2021	180-120857-1	< 0.077 U	< 0.077 U	< 0.074 U	< 0.058 U	< 0.75 U	< 0.07 U	< 0.13 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.1 U	< 0.082 U	< 0.08 U	< 0.048 U	< 0.069 U	7.8 J	< 0.075 U	0.73 J	< 0.56 U	< 0.061 U	< 0.052 U	< 0.073 U	< 0.07 U	< 0.076 U	< 0.073 U	< 0.096 U	< 0.086 U	< 0.087 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.049 U	< 0.067 U	2.5	< 0.82 U
MW-66S	MW-66S	2/19/2021	180-117476-1	< 0.06 U	< 0.06 U	< 0.057 U	< 0.045 U	< 0.59 U	< 0.055 U	< 0.1 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.058 U	0.52 J	< 0.44 U	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	< 0.075 U	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	0.72 J	< 0.63 U
MW-66S	SSHS-MW-66S-09122023	9/12/2023	1801624611	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 UJ	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 UT	< 0.20 U	1.5 J+	< 0.69 U
MW-66S	MW-66S	4/28/2021	180-120857-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.066 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	1.8	< 0.71 U
MW-67I	MW-67I	8/31/2021	180-126501-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	0.89 J	< 0.74 U
MW-67I	MW-67I	7/16/2021	180-124628-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 UJ	< 0.045 UJ	< 0.066 U	< 7.1 U	< 0.072 U	< 0.53 U	1.4 J	< 0.058 U	< 0.05 UJ	< 0.069 U	< 0.067 UJ	< 0.073 UJ	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 UJ	< 0.058 UJ	< 0.64 U	< 0.047 UJ	< 0.064 U	2.3	< 0.78 U
MW-67I	SSHS-MW-67I-04282024	4/28/2024	1801733271	0.097 J	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	1.3 J	1.6 J	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	12	< 0.71 U
MW-67S	MW-67S	8/31/2021	180-126501-1	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.1 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 0.55 U	< 0.56 U	< 0.061 U	< 0.45 U	< 0.33 U	< 0.07 U	< 0.15 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.2 U	< 0.24 U	1.4	< 0.82 U
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733271	0.18 J	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	1.2 J	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	0.44 J	14	< 0.74 U
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733271	0.21	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	1.5 J	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	0.088 J	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	17	< 0.74 U
MW-67S	MW-67S	7/16/2021	180-124628-1	0.26	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.066 U	0.54 J	2.5 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	3.8	< 0.71 U
MW-68S	DUP-3	7/13/2021	180-124378-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	0.19 J	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 UJ	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-68S	MW-68S	7/13/2021	180-124378-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	0.2 J	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	0.59 J	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-68S	MW-68S	9/9/2021	180-126905-1	0.098 J	< 0.059 U	< 0.82 U	< 0.056 U	< 0.45 U	< 0.36 U	< 0.44 U	< 0.072 U	< 0.042 U	< 0.074 U	< 0.068 U	< 0.075 U	< 0.39 U	< 0.1 U	< 0.096 U	< 5.5 UJ	< 0.51 U	< 0.79 U	< 1.6 UJ	< 0.064 U	< 0.37 U	< 0.56 U	< 0.058 U	< 0.26 U	< 0.5 U	< 0.089 U	< 0.077 U	< 0.45 U	< 0.91 U	< 0.072 U	< 0.98 U	< 0.27 U	< 0.5 U	< 0.9 U	< 0.75 U
MW-68S	SSHS-MW-68S-04282024	4/28/2024	1801733271	0.11 J	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	1.9 J	< 0.053 U	< 0.39 UT	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 UT	< 0.053 U	< 0.59 U	< 0.61 U	0.21 J	20 T	< 0.71 U
MW-68S	DUP-2	9/9/2021	180-126905-1	0.12 J	< 0.059 U	< 0.82 U	< 0.056 U	< 0.45 U	< 0.36 U	< 0.44 U	< 0.072 U	< 0.042 U	< 0.074 U	< 0.068 U	< 0.075 U	< 0.39 U	< 0.1 U	< 0.096 U	5.6 J	< 0.51 U	< 0.79 U	2.8 J	< 0.064 U	< 0.37 U	< 0.56 U	< 0.058 U	< 0.26 U	< 0.5 U	< 0.089 U	< 0.077 U	< 0.45 U	< 0.91 U	< 0.072 U	< 0.98 U	< 0.27 U	< 0.5 U	< 0.9 U	< 0.75 U
MW-69I	MW-69I	7/13/2021	180-124378-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	0.26 J	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	24	< 0.063 U	0.55 J	2.9 J	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	1.9	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-69I	MW-69I	9/3/2021	180-126702-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	13 J+	< 0.35 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	< 0.81 U	< 0.74 U
MW-69I	SSHS-MW-69I-04112024	4/11/2024	1801722811	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	0.091 J	< 0.058 U	0.17 J	0.22	0.16 J	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	0.22	0.19 J	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-70I	MW-70I	10/27/2021	180-129230-1	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6 U	< 0.31 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	0.77 J	< 0.66 U
MW-70I	SSHS-MW-70I-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-70I	MW-70I	9/9/2021	180-126939-1	< 0.07 U	< 0.057 U	< 0.79 U	< 0.054 U	< 0.43 U	< 0.35 U	< 0.42 U	< 0.069 U	< 0.04 U	< 0.071 U	< 0.065 U	< 0.072 U	< 0.38 U	< 0.1 U	< 0.092 U	5.3 J	< 0.49 U	< 0.76 U	< 1.5 U	< 0.061 U	< 0.35 U	< 0.53 U	< 0.056 U	< 0.25 U	< 0.48 U	< 0.085 U	< 0.074 U	< 0.43 U	< 0.87 U	< 0.069 U	< 0.94 U	< 0.26 U	< 0.48 U	< 0.87 U	< 0.72 U
MW-70S	MW-70S	10/27/2021	180-129230-1	< 0.058 U	< 0.058 U	< 0.14 U	< 0.044 U	< 0.57 U	< 0.13 U	< 0.48 U	0.078 J	0.047 J	0.14 J	0.15 J	0.11 J	< 0.14 U	< 0.036 U	< 0.052 U	< 5.6 U	< 0.28 U	< 0.41 U	< 0.42 U	< 0.046 U	< 0.34 U	< 0.25 U	< 0.053 U	< 0.12 U	< 0.2 U	0.14 J	0.14 J	< 0.17 U	< 0.52 U	< 0.046 U	< 0.51 U	< 0.15 U	< 0.18 U	0.81 J	< 0.61 U
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561231	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.44 U	1.1 J	< 0.049 U	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	1.5	< 0.66 U
MW-70S	DUP-02	5/4/2023	1801561231	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	2.2 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	1.8	< 0.69 U
MW-70S	SSHS-DUP-04-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-70S	SSHS-MW-70S-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625621	< 0.071 UT	< 0.071 UT	< 0.17 UT	< 0.053 UT	< 0.69 UT	< 0.15 UT	< 0.58 U	< 0.082 UT	< 0.058 UT	< 0.11 UT	< 0.096 U	< 0.075 UT	< 0.17 UT	< 0.043 UT	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 UT	< 0.51 U	< 0.055 UT	< 0.41 UT	< 0.30 U	< 0.064 UT	< 0.14 UT	< 0.24 UT	< 0.088 U	< 0.078 UT	< 0.21 UT	< 0.63 UT	< 0.055 UT	< 0.62 UT	< 0.18 UT	< 0.22 UT	2.3	< 0.74 U
MW-70S	MW-70S	9/7/2021	180-126846-1	0.081 J	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	8 J	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-71I	MW-71I	10/27/2021	180-129230-1	< 0.056 U	< 0.056 U	< 0.14 U	< 0.042 U	< 0.55 U	< 0.12 U	< 0.46 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.13 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.28 U	< 0.4 U	< 0.41 U	< 0.044 U	< 0.32 U	< 0.24 U	< 0.051 U	< 0.11 U	< 0.19 U	< 0.07 U	< 0.062 U	< 0.16 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.14 U	< 0.17 U	0.77 J	< 0.59 U
MW-71I	SSHS-MW-71I-04052024	4/5/2024	1801720031	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-71I	MW-71I	9/7/2021	180-126846-1	< 0.076 U	< 0.062 U	< 0.86 U	< 0.059 U	< 0.47 U	< 0.38 U	< 0.46 U	< 0.075 U	< 0.043 U	< 0.077 U	< 0.071 U	< 0.078 U	< 0.41 U	< 0.11 U	< 0.1 U	7.9 J	< 0.53 U	< 0.82 U	2.2 J	< 0.066 U	< 0.38 U	< 0.58 U	< 0.061 U	< 0.27 U	< 0.52 U	< 0.092 U	< 0.08 U	< 0.47 U	< 0.95 U	< 0.075 U	< 1 U	< 0.28 U	< 0.52 U	< 0.94 U	< 0.78 U
MW-71S	MW-71S	10/27/2021	180-129230-1	< 0.054 U	< 0.054 U	< 0.13 U	< 0.041 U	< 0.53 U	< 0.12 U	< 0.45 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.13 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.27 U	< 0.39 U	< 0.39 U	< 0.043 U	< 0.31 U	< 0.23 U	< 0.049 U	< 0.11 U	< 0.18 U	< 0.068 U	< 0.06 U	< 0.16 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.14 U	< 0.17 U	0.88	< 0.57 U
MW-71S	SSHS-MW-71S-04052024	4/5/2024	1801720031	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 1.1 U	< 1.6 U	< 0.058 U	< 0.43 U	< 0.49 U	< 0.067 U	< 0.26 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.66 U	< 0.23 U	< 5.6 U	< 0.78 U
MW-71S	MW-71S	9/7/2021	180-126846-1	< 0.076 U	< 0.062 U	< 0.86 U	< 0.059 U	< 0.47 U	< 0.38 U	< 0.46 U	< 0.075 U	< 0.043 U	< 0.077 U	< 0.071 U	< 0.078 U	< 0.41 U	< 0.11 U	< 0.1 U	9.9 J	< 0.53 U	< 0.82 U	< 1.7 U	< 0.066 U	< 0.38 U	< 0.58 U	< 0.061 U	< 0.27 U	< 0.52 U	< 0.092 U	< 0.08 U	< 0.47 U	< 0.95 U	< 0.075 U	< 1 U	< 0.28 U	< 0.52 U	< 0.94 U	< 0.78 U
MW-72I	DUP-02	10/27/2021	180-129155-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 UJ	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-72I	MW-72I	10/27/2021	180-129155-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	3 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-72I	SSHS-MW-72I-04042024	4/4/2024	1801719081	< 0.065 UT	< 0.065 UT	< 0.16 UT	< 0.049 UT	< 0.63 UT	< 0.14 UT	< 0.54 U	< 0.075 UT	< 0.053 UT	< 0.097 UT	< 0.088 UT	< 0.069 UT	< 0.15 UT	< 0.040 UT	< 0.058 U	< 6.2 U	< 0.32 UT	< 0.94 UT	< 1.4 UT	< 0.051 UT	< 0.38 UT	< 0.44 UT	< 0.059 UT	< 0.23 UT	< 0.22 UT	< 0.081 UT	< 0.072 UT	< 0.19 UT	< 0.58 UT	< 0.051 UT	< 0.57 UT	< 0.59 UT	< 0.20 UT	< 4.9 UT	< 0.69 UT
MW-72I	MW-72I	9/8/2021	180-126846-1	< 0.073 U	< 0.059 U	< 0.82 U	< 0.056 U	< 0.45 U	< 0.36 U	< 0.44 U	< 0.072 U	< 0.042 U	< 0.074 U	< 0.068 U	< 0.075 U	< 0.39 U	< 0.1 U	< 0.096 U	< 5.5 U	< 0.51 U	< 0.79 U	2 J	< 0.064 U	< 0.37 U	< 0.56 U	< 0.058 U	< 0.26 U	< 0.5 U	< 0.089 U	< 0.077 U	< 0.45 U	< 0.91 U	< 0.072 U	< 0.98 U	< 0.27 U	< 0.5 U	< 0.9 U	< 0.75 U
MW-72S	MW-72S	10/27/2021	180-129155-1	< 0.06 U	< 0.06 U	< 0.15 U	0.059 J	< 0.59 U	< 0.13 U	< 0.5 U	0.34 J	0.26	0.33	0.37 J	0.35 J	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	0.91 J	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	0.41 J	0.37 J	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 UJ	< 0.63 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	TPH-DRO	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	1	5	50	50	0.04	0.5	5	5	0.002		50			10	5	5	5	0.4				50	1	50	1	50					
Location	Sample Name	Sample Date	Lab Report																																	
MW-59S	MW-59S	2/19/2021	180-117476-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	< 0.047 U	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	< 230 U	< 0.053 U	< 0.059 U
MW-59S	MW-59S	4/29/2021	180-121010-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 260 U	< 0.059 U	< 0.065 U
MW-59S	MW-59S	7/13/2022	1801412391	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.10 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-5I	SSHS-MW-5I-04102024	4/10/2024	1801721871	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	0.073 J	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-5I	SSHS-MW-5I-09132023	9/13/2023	1801624611	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	0.076 J	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-5S	MW5	5/16/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW5	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	2/23/2021	180-117459-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	0.097 J	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	1800	< 0.056 U	< 0.063 U
MW-5S	MW-5	7/15/2021	180-124580-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	0.069 J	< 0.4 U	0.16 J	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.12 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	1000	< 0.066 U	< 0.074 U
MW-60	MW-60	2/18/2021	180-117476-1	< 1.3 U	< 0.054 U	< 1.4 U	< 0.046 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.055 U	< 0.076 U	< 0.27 U	< 0.048 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.06 U	< 0.052 U	< 0.45 U	< 0.054 U	< 0.13 U	< 0.063 U	< 0.11 U	< 0.76 U	< 0.049 U	< 0.43 U	< 0.048 U	< 0.046 U	< 0.04 U	< 230 U	< 0.054 U	< 0.061 U
MW-60	MW-60	4/29/2021	180-121010-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 260 U	< 0.059 U	< 0.065 U
MW-60	MW-60	7/12/2022	1801412391	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.11 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-60IR	SSHS-MW-60IR-04052024	4/5/2024	1801720021	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	0.12 J	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-60SR	SSHS-MW-60SR-04052024	4/5/2024	1801720021	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-61	MW-61	2/16/2021	180-117390-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.05 U	< 0.069 U	< 0.24 U	< 0.044 U	< 0.05 U	< 0.3 U	< 0.048 U	< 0.44 U	< 0.054 U	< 0.047 U	< 0.4 U	< 0.049 U	< 0.11 U	< 0.057 U	< 0.096 U	< 0.68 U	< 0.044 U	< 0.39 U	< 0.044 U	< 0.042 U	< 0.036 U	-	< 0.049 U	< 0.055 U
MW-61	MW-61	4/27/2021	180-120743-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 UJ	< 0.066 U	< 0.48 R	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 UJ	< 0.053 U	< 0.47 UJ	< 0.052 U	< 0.05 UJ	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-61	MW-61	7/12/2022	1801412391	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	0.11 J	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-62	MW-62	2/16/2021	180-117390-1	< 1.2 U	< 0.048 U	< 1.2 U	< 0.041 U	< 0.048 UJ	< 0.056 UJ	< 0.045 UJ	< 0.056 R	< 0.4 R	< 0.05 R	< 0.069 UJ	< 0.24 UJ	< 0.044 UJ	< 0.05 UJ	< 0.3 UJ	< 0.048 UJ	< 0.44 U	< 0.054 UJ	< 0.047 UJ	< 0.4 UJ	< 0.049 UJ	< 0.11 U	< 0.057 UJ	< 0.096 UJ	< 0.68 UJ	< 0.044 UJ	< 0.39 UJ	< 0.044 UJ	< 0.042 UJ	< 0.036 UJ	-	< 0.049 UJ	< 0.055 UJ
MW-62	MW-62	4/27/2021	180-120743-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 UJ	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	< 220 U	< 0.061 U	< 0.068 U
MW-62	MW-62	7/12/2022	1801412391	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.060 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-62R	SSHS-MW-62R-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-62R	SSHS-MW-62R-09142023	9/14/2023	1801625611	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.060 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-63I	MW-63I	2/18/2021	180-117476-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	< 0.047 U	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	< 230 U	< 0.053 U	< 0.059 U
MW-63I	MW-63I	4/29/2021	180-121010-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-63I	SSHS-MW-63I-09132023	9/13/2023	1801624611	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.060 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-63S	MW-63S	2/18/2021	180-117476-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	< 0.071 U	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	< 0.046 U	< 0.41 U	< 0.045 U	< 0.043 U	< 0.038 U	< 230 U	< 0.051 U	< 0.057 U
MW-63S	MW-63S	4/29/2021	180-121010-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-63S	SSHS-MW-63S-09132023	9/13/2023	1801624611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-64I	MW-64I	2/20/2021	180-117476-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	0.095 J	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-64I	SSHS-MW-64I-04052024	4/5/2024	1801720021	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-64I	SSHS-MW-64I-09122023	9/12/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	0.12 J	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 UT	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-64I	MW-64I	4/28/2021	180-120857-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 UJ	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	< 260 U	< 0.066 U	< 0.074 U
MW-64S	MW-64S	2/20/2021	180-117476-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-64S	MW-64S	4/28/2021	180-120857-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 UJ	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	< 260 U	< 0.069 U	< 0.077 U
MW-65	MW-65	2/20/2021	180-117476-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	0.065 J	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	< 230 U	< 0.053 U	< 0.059 U
MW-65	SSHS-MW-65-08152022	8/15/2022	1801429571	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	< 0.058 UT	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 UT	< 0.29 U	< 0.18 U	0.086 J	< 0.36 U	0.41	< 0.53 UT	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	0.26	0.71 J	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-65	SSHS-DUP1-08152022	8/15/2022	1801429571	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	0.069 J	< 0.37 U	2.8	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.17 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-65	MW-65	4/26/2021	180-120679-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	< 220 U	< 0.066 U	< 0.074 U
MW-65	DUP-3	4/26/2021	180-120679-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	< 220 U	< 0.069 U	< 0.077 U
MW-65R	SSHS-MW-65R-04082024	4/8/2024	1801720411	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-65R	SSHS-MW-65R-09142023	9/14/2023	1801625611	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-66I	MW-66I	2/20/2021	180-117476-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-66I	SSHS-MW-66I-09122023	9/12/2023	1801624611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 UT	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-66I	MW-66I	4/28/2021	180-120857-1	< 1.8 U	< 0.071 U	< 1.8 U	< 0.061 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.074 U	< 0.1 U	< 0.36 U	< 0.064 U	< 0.074 U	< 0.44 U	< 0.07 U	< 0.65 U	< 0.08 U	< 0.069 U	< 0.6 U	< 0.073 U	< 0.17 U	< 0.085 U	< 0.14 U	< 1 UJ	< 0.065 U	< 0.58 U	< 0.064 U	< 0.062 U	< 0.054 U	< 260 U	< 0.073 U	< 0.081 U
MW-66S	MW-66S	2/19/2021	180-117476-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	< 0.05 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.048 U	< 0.042 U	< 230 U	< 0.056 U	< 0.063 U
MW-66S	SSHS-MW-66S-09122023	9/12/2023	1801624611	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 UT	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-66S	MW-66S	4/28/2021	180-120857-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 UJ	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	< 270 U	< 0.064 U	< 0.071 U
MW-67I	MW-67I	8/31/2021	180-126501-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	0.094 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 260 U	< 0.27 U	< 0.24 U
MW-67I	MW-67I	7/16/2021	180-124628-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 UJ	0.56 R	< 0.07 UJ	< 0.097 U	< 0.34 UJ	< 0.061 U	< 0.07 UJ	< 0.42 UJ	< 0.067 UJ	< 0.62 U	< 0.076 UJ	< 0.066 UJ	< 0.57 UJ	< 0.069 UJ	< 0.16 U	< 0.081 UJ	< 0.14 UJ	< 0.96 U	0.16 J	< 0.55 UJ	< 0.061 U	< 0.059 UJ	< 0.051 U	< 250 U	< 0.069 U	< 0.077 U
MW-67I	SSHS-MW-67I-04282024	4/28/2024	1801733271	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	0.085 J	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-67S	MW-67S	8/31/2021	180-126501-1	< 1.8 U	< 0.21 U	< 1.8 U	< 0.42 U	< 0.071 U	0.15 J	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.1 U	< 0.36 U	< 0.22 U	< 0.074 U	< 0.44 U	0.21 J	< 0.65 U	< 0.52 U	< 0.43 U	< 0.6 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1 U	0.13 J	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	1200	< 0.3 U	< 0.27 U
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733271	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	0.070 J	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	0.10 J	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733271	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	0.075 J	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	0.11 J	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-67S	MW-67S	7/16/2021	180-124628-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	0.39	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.22	< 0.51 U	0.058 J	< 0.054 U	< 0.047 U	1200	< 0.064 U	< 0.071 U
MW-68S	DUP-3	7/13/2021	180-124378-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 UJ	< 0.37 U	< 0.059 UJ	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.14 J	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	5500	< 0.061 U	< 0.068 U
MW-68S	MW-68S	7/13/2021	180-124378-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	0.22 J	< 0.37 U	0.59 J	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.18 J	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	6300	< 0.061 U	< 0.068 U
MW-68S	MW-68S	9/9/2021	180-126905-1	< 1.4 U	< 0.57 U	< 6.2 U	< 0.75 U	< 0.097 U	< 0.084 U	< 0.078 U	< 0.1 U	< 0.42 U	< 0.34 U	< 0.069 U	< 0.36 U	< 0.42 U	< 0.085 U	< 0.32 U	< 0.1 U	< 0.63 U	< 0.49 U	< 0.46 U	< 0.45 U	< 0.42 U	< 1.2 U	< 0.14 U	< 0.29 U	< 2.3 U	< 0.13 U	< 0.27 U	< 0.063 U	< 0.36 U	< 0.58 U	3100	< 0.5 U	< 0.38 U
MW-68S	SSHS-MW-68S-04282024	4/28/2024	1801733271	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 UT	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-68S	DUP-2	9/9/2021	180-126905-1	< 1.4 U	< 0.57 U	< 6.2 U	< 0.75 U	< 0.097 U	< 0.084 U	< 0.078 U	< 0.1 U	< 0.42 U	< 0.34 U	< 0.069 U	< 0.36 U	< 0.42 U	< 0.085 U	< 0.32 U	< 0.1 U	< 0.63 U	< 0.49 U	< 0.46 U	< 0.45 U	< 0.42 U	< 1.2 U	< 0.14 U	< 0.29 U	< 2.3 U	< 0.13 U	< 0.27 U	< 0.063 U	< 0.36 U	< 0.58 U	3800	< 0.5 U	< 0.38 U
MW-69I	MW-69I	7/13/2021	180-124378-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	0.078 J	< 0.37 U	0.38	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.19	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	< 270 U	< 0.061 U	< 0.068 U
MW-69I	MW-69I	9/3/2021	180-126702-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.06 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 250 U	< 0.27 U	< 0.24 U
MW-69I	SSHS-MW-69I-04112024	4/11/2024	1801722811	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	0.17 J	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-70I	MW-70I	10/27/2021	180-129230-1	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.29 U	< 0.18 U	< 0.06 U	< 0.36 U	0.066 J	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.9 U	< 0.068 U	< 0.11 U	< 0.81 U	0.14 J	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	< 230 U	< 0.24 U	< 0.22 U
MW-70I	SSHS-MW-70I-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	0.12 J	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-70I	MW-70I	9/9/2021	180-126939-1	< 1.3 U	< 0.55 U	< 5.9 U	< 0.72 U	< 0.093 U	< 0.081 U	< 0.075 U	< 0.099 U	< 0.4 U	< 0.33 U	< 0.066 U	< 0.35 U	< 0.41 U	< 0.082 U	< 0.31 U	0.12 J	< 0.6 U	< 0.47 U	< 0.44 U	< 0.43 U	< 0.4 U	< 1.2 U	< 0.13 U	< 0.28 U	< 2.2 U	0.12 J	< 0.26 U	< 0.06 U	< 0.34 U	< 0.56 U	250 J	< 0.48 U	< 0.37 U
MW-70S	MW-70S	10/27/2021	180-129230-1	< 1.3 U	< 0.15 U	< 1.4 U	< 0.32 U	< 0.054 U	< 0.062 U	< 0.05 U	< 0.062 U	< 0.44 U	< 0.12 U	0.12 J	< 0.27 U	< 0.17 U	< 0.055 U	< 0.33 U	< 0.053 U	< 0.49 U	< 0.39 U	< 0.32 U	< 0.45 U	< 0.17 U	< 0.84 U	< 0.063 U	< 0.11 U	< 0.76 U	0.2	< 0.43 U	< 0.048 U	< 0.13 U	< 0.29 U	< 230 U	< 0.23 U	< 0.2 U
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561231	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.29 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	0.11 J	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-70S	DUP-02	5/4/2023	1801561231	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.16 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-70S	SSHS-DUP-04-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-70S	SSHS-MW-70S-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625621	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 UT	< 0.075 UT	< 0.061 U	< 0.075 UT	< 0.54 UT	< 0.14 UT	< 0.092 UT	< 0.33 UT	< 0.20 UT	< 0.067 UT	< 0.40 UT	< 0.064 UT	< 0.60 U	< 0.48 UT	< 0.39 UT	< 0.54 UT	< 0.21 UT	< 1.0 U	< 0.077 UT	< 0.13 UT	< 0.92 U	0.069 JT	< 0.53 UT	< 0.059 U	< 0.16 UT	< 0.35 U	-	< 0.27 UT	< 0.24 UT
MW-70S	MW-70S	9/7/2021	180-126846-1	< 1.3 UT	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	0.19	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	330 J	< 0.46 U	< 0.35 U
MW-71I	MW-71I	10/27/2021	180-129230-1	< 1.3 U	< 0.15 U	< 1.3 U	< 0.3 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.11 U	< 0.073 U	< 0.26 U	< 0.16 U	< 0.053 U	< 0.32 U	0.078 J	< 0.47 U	< 0.38 U	< 0.31 U	< 0.43 U	< 0.17 U	< 0.81 U	< 0.061 U	< 0.1 U	< 0.73 U	0.11 J	< 0.42 U	< 0.047 U	< 0.13 U	< 0.28 U	< 230 U	< 0.22 U	< 0.19 U
MW-71I	SSHS-MW-71I-04052024	4/5/2024	1801720031	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-71I	MW-71I	9/7/2021	180-126846-1	< 1.5 U	< 0.59 U	< 6.4 U	< 0.78 U	< 0.1 U	< 0.088 U	< 0.082 U	< 0.11 U	< 0.44 U	< 0.36 U	< 0.072 U	< 0.38 U	< 0.44 U	< 0.089 U	< 0.33 U	< 0.11 U	< 0.66 U	< 0.51 U	< 0.48 U	< 0.47 U	< 0.44 U	< 1.3 U	< 0.15 U	< 0.3 U	< 2.4 U	0.15 J	< 0.29 U	< 0.065 U	< 0.37 U	< 0.61 U	< 250 U	< 0.53 U	< 0.4 U
MW-71S	MW-71S	10/27/2021	180-129230-1	< 1.2 U	< 0.14 U	< 1.3 U	< 0.29 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.11 U	< 0.071 U	< 0.25 U	< 0.16 U	< 0.052 U	< 0.31 U	0.067 J	< 0.46 U	< 0.36 U	< 0.3 U	< 0.42 U	< 0.16 U	< 0.78 U	< 0.059 U	< 0.099 U	< 0.71 U	0.072 J	< 0.41 U	< 0.045 U	< 0.13 U	< 0.27 U	< 0.48 U	< 0.21 U	< 0.19 U
MW-71S	SSHS-MW-71S-04052024	4/5/2024	1801720031	< 1.7 U	< 0.20 U	< 3.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.63 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.18 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-71S	MW-71S	9/7/2021	180-126846-1	< 1.5 U	< 0.59 U	< 6.4 U	< 0.78 U	< 0.1 U	< 0.088 U	< 0.082 U	< 0.11 U	< 0.44 U	< 0.36 U	< 0.072 U	< 0.38 U	< 0.44 U	< 0.089 U	< 0.33 U	< 0.11 U	< 0.66 U	< 0.51 U	< 0.48 U	< 0.47 U	< 0.44 U	< 1.3 U	< 0.15 U	< 0.3 U	< 2.4 U	< 0.13 U	< 0.29 U	< 0.065 U	< 0.37 U	< 0.61 U	230 J	< 0.53 U	< 0.4 U
MW-72I	DUP-02	10/27/2021	180-129155-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 210 U	< 0.25 U	< 0.22 U
MW-72I	MW-72I	10/27/2021	180-129155-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 220 U	< 0.25 U	< 0.22 U
MW-72I	SSHS-MW-72I-04042024	4/4/2024	1801719081	< 1.5 UT	< 0.17 UT	< 3.3 UT	< 0.35 UT	< 0.060 UT	< 0.069 UT	< 0.056 UT	< 0.069 UT	< 0.50 UT	< 0.13 UT	< 0.085 UT	< 0.56 UT	< 0.19 UT	< 0.062 UT	< 0.37 UT	< 0.059 UT	< 0.55 U	< 0.44 UT	< 0.36 UT	< 0.50 U	< 0.19 UT	< 0.94 U	< 0.071 UT	< 0.12 UT	< 0.85 UT	< 0.16 UT	< 0.49 UT	< 0.054 UT	< 0.15 UT	< 0.33 UT	-	< 0.25 UT	< 0.22 UT
MW-72I	MW-72I	9/8/2021	180-126846-1	< 1.4 U	< 0.57 U	< 6.2 U	< 0.75 U	< 0.097 U	< 0.084 U	< 0.078 U	< 0.1 U	< 0.42 U	< 0.34 U	< 0.069 U	< 0.36 U	< 0.42 U	< 0.085 U	< 0.32 U	< 0.1 U	< 0.63 U	< 0.49 U	< 0.46 U	< 0.45 U	< 0.42 U	< 1.2 U	< 0.14 U	< 0.29 U	< 2.3 U	< 0.13 U	< 0.27 U	< 0.063 U	< 0.36 U	< 0.58 U	< 260 U	< 0.5 U	< 0.38 U
MW-72S	MW-72S	10/27/2021	180-129155-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	0.11 J	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 UJ	< 0.12 U	0.36 J	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 UJ	< 0.45 U	0.091 J	< 0.14 U	< 0.3 U	< 210 U	< 0.23 U	< 0.21 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (DEHP)	4-Bromophenyl phenyl ether	Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroaniline)	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				20			50				0.002		0.002	0.002		5	1		5[1]		50			5		10			0.002			5	1	50	1	50	50	50
Location	Sample Name	Sample Date	Lab Report																																			
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625621	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	2.9	< 0.66 U
MW-72S	SSHS-MW-72S-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561231	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	1.9	< 0.69 U
MW-72S	MW-72S	9/8/2021	180-126846-1	< 0.08 U	< 0.065 U	< 0.9 U	< 0.061 U	< 0.49 U	< 0.4 U	< 0.48 U	< 0.078 U	< 0.045 U	< 0.081 U	< 0.074 U	< 0.082 U	< 0.43 U	< 0.11 U	< 0.1 U	< 6 U	< 0.56 U	< 0.86 U	1.8 J	< 0.069 U	< 0.4 U	< 0.61 U	< 0.064 U	< 0.28 U	< 0.54 U	< 0.097 U	< 0.084 U	< 0.49 U	< 0.99 U	< 0.078 U	< 1.1 U	< 0.29 U	< 0.55 U	< 0.98 U	< 0.81 U
MW-73I	MW-73I	9/8/2021	180-126846-1	< 0.076 UJ	< 0.062 UJ	< 0.86 UJ	< 0.059 UJ	< 0.47 U	< 0.38 UJ	< 0.46 U	< 0.075 U	< 0.043 UJ	< 0.077 UJ	< 0.071 UJ	< 0.078 UJ	< 0.41 UJ	< 0.11 UJ	< 0.1 UJ	< 5.7 UJ	< 0.53 UJ	0.97 J	2.5 J	< 0.066 UJ	< 0.38 UJ	< 0.58 UJ	0.061 J	< 0.27 UJ	< 0.52 UJ	< 0.092 UJ	< 0.08 U	< 0.47 UJ	< 0.95 UJ	< 0.075 UJ	< 1 UJ	< 0.28 UJ	< 0.52 UJ	< 0.94 UJ	< 0.78 U
MW-73I	SSHS-MW-73I-04052024	4/5/2024	1801720031	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.10 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 1.1 U	< 1.7 U	< 0.061 U	< 0.45 U	< 0.52 U	< 0.070 U	< 0.27 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.70 U	< 0.24 U	< 5.8 U	< 0.82 U
MW-73I	MW-73I	10/27/2021	180-129230-1	0.18	0.16 J	< 0.15 U	< 0.045 U	< 0.59 U	0.2 J	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	0.071 J	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	0.1 J	0.083 J	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	0.95	< 0.63 U
MW-73S	MW-73S	10/26/2021	180-129230-1	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	0.12 J	0.15 J	0.28	0.096 J	0.34	< 0.15 U	< 0.038 U	< 0.056 U	< 6 U	< 0.31 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	0.16 J	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	0.75 J	< 0.66 U
MW-73S	MW-73S	9/8/2021	180-126846-1	< 0.07 U	< 0.057 U	< 0.79 U	< 0.054 U	< 0.43 U	< 0.35 U	< 0.42 U	< 0.069 U	< 0.04 U	< 0.071 U	< 0.065 U	< 0.072 U	< 0.38 U	< 0.1 U	< 0.092 U	< 5.3 U	< 0.49 U	0.84 J	1.9 J	< 0.061 U	< 0.35 U	< 0.53 U	< 0.056 U	< 0.25 U	< 0.48 U	< 0.085 U	< 0.074 U	< 0.43 U	< 0.87 U	< 0.069 U	< 0.94 U	< 0.26 U	< 0.48 U	< 0.87 U	< 0.72 U
MW-73S	SSHS-MW-73S-04052024	4/5/2024	1801720031	0.11 J	0.17 J	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	0.11 J	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-74I	MW-74I	10/27/2021	180-129155-1	< 0.06 U	< 0.06 U	0.15 J	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-74I	SSHS-MW-74I-04052024	4/5/2024	1801720031	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-74I	MW-74I	9/8/2021	180-126846-1	< 0.073 U	< 0.059 U	< 0.82 U	< 0.056 U	< 0.45 U	< 0.36 U	< 0.44 U	< 0.072 U	< 0.042 U	< 0.074 U	< 0.068 U	< 0.075 U	< 0.39 U	< 0.1 U	< 0.096 U	< 5.5 U	< 0.51 U	< 0.79 U	1.8 J	< 0.064 U	< 0.37 U	< 0.56 U	< 0.058 U	< 0.26 U	< 0.5 U	< 0.089 U	< 0.077 U	< 0.45 U	< 0.91 U	< 0.072 U	< 0.98 U	< 0.27 U	< 0.5 U	< 0.9 U	< 0.75 U
MW-74S	SSHS-DUP-05-04052024	4/5/2024	1801720031	< 0.068 U	0.10 J	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-74S	SSHS-MW-74S-04052024	4/5/2024	1801720031	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 1.1 U	< 1.6 U	< 0.058 U	< 0.43 U	< 0.49 U	< 0.067 U	< 0.26 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.66 U	< 0.23 U	< 5.6 U	< 0.78 U
MW-74S	MW-74S	9/8/2021	180-126846-1	< 0.076 U	< 0.062 U	< 0.86 U	< 0.059 U	< 0.47 U	< 0.38 U	< 0.46 U	< 0.075 U	< 0.043 U	< 0.077 U	< 0.071 U	< 0.078 U	< 0.41 U	< 0.11 U	< 0.1 U	< 5.7 U	< 0.53 U	< 0.82 U	2.2 J	< 0.066 U	< 0.38 U	< 0.58 U	< 0.061 U	< 0.27 U	< 0.52 U	< 0.092 U	< 0.08 U	< 0.47 U	< 0.95 U	< 0.075 U	< 1 U	< 0.28 U	< 0.52 U	< 0.94 U	< 0.78 U
MW-74S	MW-74S	10/27/2021	180-129155-1	0.095 J	0.1 J	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-75I	MW-75I	10/29/2021	180-129376-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	0.69 J	< 0.63 U
MW-75I	MW-75I	9/9/2021	180-126905-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722811	< 0.068 U	0.11 J	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-75S	MW-75S	10/29/2021	180-129376-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-75S	MW-75S	9/9/2021	180-126905-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	7.7 J	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722811	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-76I	MW-76I	10/28/2021	180-129230-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 UJ	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 UJ	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-76I	DUP-03	10/28/2021	180-129230-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	0.81 J	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	0.6 J	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-76I	MW-76I	9/10/2021	180-126939-1	< 0.07 U	< 0.057 U	< 0.79 U	< 0.054 U	< 0.43 U	< 0.35 U	< 0.42 U	< 0.069 U	< 0.04 U	< 0.071 U	< 0.065 U	< 0.072 U	< 0.38 U	< 0.1 U	< 0.092 U	< 5.3 U	< 0.49 U	< 0.76 U	< 1.5 U	< 0.061 U	< 0.35 U	< 0.53 U	< 0.056 U	< 0.25 U	< 0.48 U	< 0.085 U	< 0.074 U	< 0.43 U	< 0.87 U	< 0.069 U	< 0.94 U	< 0.26 U	< 0.48 U	< 0.87 U	< 0.72 U
MW-76S	MW-76S	10/28/2021	180-129230-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	0.68 J	0.94 J	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	0.75 J	< 0.63 U
MW-76S	SSHS-MW-76S-04082024	4/8/2024	1801720411	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	< 0.049 U	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-76S	MW-76S	9/10/2021	180-126939-1	0.071 J	0.071 J	< 0.73 U	< 0.05 U	< 0.4 U	< 0.32 U	< 0.39 U	< 0.064 U	< 0.037 U	< 0.066 U	< 0.06 U	< 0.067 U	< 0.35 U	< 0.093 U	< 0.085 U	7.1 J	< 0.45 U	< 0.7 U	1.4 J	< 0.056 U	< 0.33 U	< 0.49 U	0.17 J	< 0.23 U	< 0.44 U	< 0.079 U	< 0.069 U	< 0.4 U	< 0.81 U	0.26	< 0.87 U	< 0.24 U	< 0.45 U	< 0.8 U	< 0.66 U
MW-76S	SSHS-MW-76S-04222024	4/22/2024	1801730541	0.10 JT	< 0.068 UT	< 0.17 UT	< 0.051 UT	< 0.66 UT	< 0.15 UT	< 0.56 U	< 0.078 UT	< 0.055 UT	< 0.10 UT	< 0.092 UT	< 0.072 UT	< 0.16 UT	< 0.042 UT	< 0.060 U	< 6.5 U	< 0.33 UT	< 0.98 U	< 1.5 U	< 0.053 UT	< 0.39 UT	< 0.45 U	< 0.061 UT	< 0.23 UT	< 0.23 UT	< 0.084 UT	< 0.075 UT	< 0.20 UT	< 0.61 UT	< 0.053 UT	< 0.59 UT	< 0.61 UT	< 0.21 UT	< 5.1 U	< 0.71 U
MW-77I	MW-77I	10/28/2021	180-129230-1	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6 U	< 0.31 U	0.81 J	< 0.45 U	< 0.049 U	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	< 0.71 U	< 0.66 U
MW-77I	SSHS-MW-77I-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-77I	MW-77I	9/10/2021	180-126939-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-77S	SSHS-MW-77S-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-77S	MW-77S	10/28/2021	180-129230-1	< 0.068 UJ	< 0.068 UJ	< 0.17 U	< 0.051 UJ	< 0.66 U	< 0.15 UJ	< 0.56 U	< 0.078 U	< 0.055 UJ	< 0.1 UJ	< 0.092 UJ	< 0.072 U	< 0.16 U	< 0.042 UJ	< 0.06 UJ	< 6.5 U	< 0.33 U	1.1	1.2 J	< 0.053 U	< 0.39 UJ	< 0.29 U	< 0.061 UJ	< 0.13 UJ	< 0.23 UJ	< 0.084 U	< 0.075 U	< 0.2 UJ	< 0.61 UJ	< 0.053 UJ	< 0.59 U	< 0.17 UJ	< 0.21 U	< 0.77 U	< 0.71 U
MW-77S	MW-77S	9/10/2021	180-126939-1	0.071 J	0.063 J	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	1.8 J	< 0.059 U	< 0.34 U	< 0.51 U	0.1 J	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	0.086 J	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-78I	SSHS-MW-78I-04052024	4/5/2024	1801720031	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-78I	MW-78I	11/2/2021	180-129534-1	< 0.065 UJ	< 0.065 UJ	< 0.16 UJ	< 0.049 U	< 0.63 U	< 0.14 UJ	< 0.54 U	< 0.075 U	< 0.053 UJ	< 0.097 UJ	< 0.088 UJ	< 0.069 UJ	< 0.15 UJ	< 0.04 UJ	< 0.058 UJ	< 6.2 U	< 0.32 UJ	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 UJ	< 0.28 U	< 0.059 UJ	< 0.13 UJ	< 0.22 UJ	< 0.081 U	< 0.072 UJ	< 0.19 UJ	< 0.58 UJ	< 0.051 UJ	< 0.57 UJ	< 0.17 UJ	< 0.2 UJ	< 0.74 U	< 0.69 U
MW-78I	MW-78I	9/10/2021	180-126939-1	< 0.076 U	< 0.062 U	< 0.86 U	< 0.059 U	< 0.47 U	< 0.38 U	< 0.46 U	< 0.075 U	< 0.043 U	0.084 J	0.082 J	0.086 J	< 0.41 U	< 0.11 U	< 0.1 U	< 5.7 U	< 0.53 U	< 0.82 U	< 1.7 U	< 0.066 U	< 0.38 U	< 0.58 U	< 0.061 U	< 0.27 U	< 0.52 U	0.093 J	0.097 J	< 0.47 U	< 0.95 U	< 0.075 U	< 1 U	< 0.28 U	< 0.52 U	< 0.94 U	< 0.78 U
MW-78S	MW-78S	11/2/2021	180-129534-1	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.2 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-78S	SSHS-MW-78S-04052024	4/5/2024	1801720031	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-78S	MW-78S	9/10/2021	180-126939-1	< 0.076 U	< 0.062 U	< 0.86 U	< 0.059 U	< 0.47 U	< 0.38 U	< 0.46 U	< 0.075 UJ	< 0.043 UJ	< 0.077 UJ	< 0.071 UJ	< 0.078 UJ	< 0.41 U	< 0.11 U	< 0.1 U	< 5.7 U	< 0.53 U	< 0.82 U	< 1.7 U	< 0.066 U	< 0.38 U	< 0.58 U	< 0.061 U	< 0.27 U	< 0.52 U	< 0.092 UJ	< 0.08 UJ	< 0.47 U	< 0.95 U	< 0.075 U	< 1 U	< 0.28 U	< 0.52 U	< 0.94 U	< 0.78 U
MW-78S	DUP-5	9/10/2021	180-126939-1	< 0.08 U	< 0.065 U	< 0.9 U	< 0.061 U	< 0.49 U	< 0.4 U	< 0.48 U	0.095 J	0.064 J	0.15 J	0.17 J	0.17 J	< 0.43 U	< 0.11 U	< 0.1 U	< 6 U	< 0.56 U	< 0.86 U	< 1.7 U	< 0.069 U	< 0.4 U	< 0.61 U	< 0.064 U	< 0.28 U	< 0.54 U	0.16 J	0.17 J	< 0.49 U	< 0.99 U	< 0.078 U	< 1.1 U	< 0.29 U	< 0.55 U	< 0.98 U	< 0.81 U
MW-79I	DUP-04	11/2/2021	180-129534-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 UJ	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-79I	MW-79I	11/2/2021	180-129534-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	0.63 J	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-79I	SSHS-MW-79I-04052024	4/5/2024	1801720031	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-79I	MW-79I	9/10/2021	180-126939-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-79S	MW-79S	11/2/2021	180-129534-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-79S	SSHS-DUP-06-04052024	4/5/2024	1801720031	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	< 0.049 U	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-79S	SSHS-MW-79S-04052024	4/5/2024	1801720031	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	< 0.049 U	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-79S	MW-79S	9/10/2021	180-126939-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	2.1 J	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-81I	MW-81I	8/31/2021	180-126501-1	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.33 U	< 0.48 U	1.8 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.2 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731401	< 0.068 UT	< 0.068 UT	< 0.17 UT	< 0.051 UT	< 0.66 UT	< 0.15 UT	< 0.56 UT	< 0.078 UT	< 0.055 UT	< 0.10 UT	< 0.092 UT	< 0.072 UT	< 0.16 UT	< 0.042 UT	< 0.060 U	< 6.5 UT	< 0.33 UT	< 0.98 UT	2.2 JT	< 0.053 UT	< 0.39 UT	< 0.45 UT	< 0.061 UT	< 0.23 UT	< 0.23 UT	< 0.084 UT	< 0.075 UT	< 0.20 UT	< 0.61 UT	< 0.053 UT	< 0.59 UT	< 0.61 UT	< 0.21 UT	< 5.1 UT	< 0.71 U
MW-81I	MW-81I	7/16/2021	180-124628-1	0.16 J	< 0.063 U	0.062 J	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.6	< 0.66 U
MW-82S	MW-82S	10/27/2021	180-129230-1	< 0.052 U	< 0.052 U	< 0.13 U	< 0.04 U	< 0.51 U	< 0.11 U	< 0.43 U	< 0.06 U	< 0.043 U	< 0.078 U	< 0.071 U	< 0.056 U	< 0.12 U	< 0.032 U	< 0.047 U	< 5 U	< 0.26 U	< 0.37 U	0.65 J	< 0.041 U	< 0.3 U	< 0.22 U	< 0.048 U	< 0.1 U	< 0.18 U	< 0.065 U	< 0.058 U	< 0.15 U	< 0.47 U	< 0.041 U	< 0.46 U	< 0.13 U	< 0.16 U	0.63 J	< 0.55 U
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733271	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	2.0 J	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	13	< 0.69 U
MW-82S	DUP-3	9/7/2021	180-126846-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 UJ	< 0.47 U	< 0.73 U	2.3 J	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-82S	MW-82S	9/7/2021	180-126846-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	6.2 J	< 0.47 U	< 0.73 U	< 1.5 UJ	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-83I	MW-83I	10/27/2021	180-129155-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-83I	MW-83I	9/8/2021	180-126846-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	1	2.5 J	< 0.059 U	< 0.34 U	< 0.51 U	0.07 J	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-83S	MW-83S	10/27/2021	180-129155-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	0.7 J	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-83S	MW-83S	9/8/2021	180-126846-1	< 0.065 U	< 0.053 U	< 0.73 U	< 0.05 U	< 0.4 U	< 0.32 U	< 0.39 U	< 0.064 U	< 0.037 U	< 0.066 U	< 0.06 U	< 0.067 U	< 0.35 U	< 0.093 U	< 0.085 U	< 4.9 U	< 0.45 U	0.95	3.1 J	< 0.056 U	< 0.33 U	< 0.49 U	< 0.052 U	< 0.23 U	< 0.44 U	< 0.079 U	< 0.069 U	< 0.4 U	< 0.81 U	< 0.064 U	< 0.87 U	< 0.24 U	< 0.45 U	< 0.8 U	< 0.66 U
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721871	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-84S	MW-84S	9/9/2021	180-126905-1	< 0.067 UJ	< 0.055 UJ	< 0.76 UJ	< 0.052 U	< 0.42 U	< 0.34 UJ	< 0.41 U	< 0.066 U	< 0.038 UJ	< 0.068 UJ	< 0.063 UJ	< 0.069 U	< 0.36 UJ	< 0.096 UJ	< 0.088 UJ	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 UJ	< 0.51 U	< 0.054 UJ	< 0.24 UJ	< 0.46 UJ	< 0.082 U	< 0.071 U	< 0.41 UJ	< 0.84 UJ	< 0.066 UJ	< 0.9 U	< 0.25 UJ	< 0.46 U	< 0.83 U	< 0.69 U
MW-84S	MW-84S	10/27/2021	180-129155-1	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.2 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	< 0.77 U	< 0.71 U
MW-84S	SSHS-DUP-07-04152024	4/15/2024	1801726651	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	5.3 J	< 0.74 U
MW-84S	SSHS-MW-84S-04152024	4/15/2024	1801726651	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	2.9 J	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-85I	MW-85I	7/15/2021	180-124580-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	13	< 0.066 U	< 0.48 U	0.72 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	1.4	< 0.71 U
MW-85I	MW-85I	9/2/2021	180-126608-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 UJ	< 0.35 U	< 0.5 U	1.7 J	< 0.055 U	< 0.41 UJ	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	1 J	< 0.18 R	< 0.22 U	0.96 J	< 0.74 U
MW-85I	SSHS-MW-85I-04222024	4/22/2024	1801730541	0.15 J	0.091 J	< 0.17 U	< 0.053 U	< 0.69 U	0.20 J	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-86I	MW-86I	7/13/2021	180-124378-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-86I	SSHS-MW-86I-04042024	4/4/2024	1801719081	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-86I	MW-86I	9/1/2021	180-126593-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.5 U	1.7 J	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	0.81 J	< 0.74 U
MW-87I	MW-87I	7/14/2021	180-124487-1	< 0.065 U	< 0.065 U	0.18 J	< 0.049 U	< 0.63 U	< 0.059 U	0.19 J	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	13	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
MW-87I	SSHS-MW-87I-04112024	4/11/2024	1801722811	< 0.065 UT	< 0.065 UT	< 0.16 UT	< 0.049 UT	< 0.63 UT	< 0.14 UT	< 0.54 UT	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 UT	< 0.15 UT	< 0.040 UT	< 0.058 UT	< 6.2 U	< 0.32 UT	< 0.94 U	< 1.4 UT	< 0.051 UT	< 0.38 UT	< 0.44 UT	< 0.059 UT	< 0.23 UT	< 0.22 UT	< 0.081 U	< 0.072 U	< 0.19 UT	< 0.58 UT	< 0.051 UT	< 0.57 UT	< 0.59 UT	< 0.20 UT	< 4.9 U	< 0.69 U
MW-87I	MW-87I	9/2/2021	180-126608-1	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	21	< 0.36 U	0.68 J	3.3 J	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	0.96 J	< 0.19 U	< 0.23 U	1.1	< 0.78 U
MW-88I	MW-88I	7/15/2021	180-124580-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	0.8 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.7 J+	< 0.66 U
MW-88I	MW-88I	9/2/2021	180-126608-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.5 U	1.1 J	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	1.4	< 0.18 U	< 0.22 U	0.91 J	< 0.74 U
MW-88I	SSHS-MW-88I-04112024	4/11/2024	1801722811	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-88S	MW-88S	7/15/2021	180-124580-1	< 0.063 UJ	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 UJ	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	2.1 J+	< 0.66 U
MW-88S	SSHS-MW-88S-04112024	4/11/2024	1801722811	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-88S	MW-88S	9/2/2021	180-126608-1	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	2.1 J	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	1.1	< 0.19 U	< 0.23 U	1.4	< 0.78 U
MW-89I	MW-89I	7/12/2021	180-124354-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	1.2 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	TPH-DRO	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	1	5	50	50	0.04	0.5	5	5	0.002		50			10	5	5	5	0.4				50	1	50	1	50					
Location	Sample Name	Sample Date	Lab Report																																	
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625621	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.29 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	0.061 J	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-72S	SSHS-MW-72S-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561231	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.11 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-72S	MW-72S	9/8/2021	180-126846-1	< 1.5 U	< 0.62 U	< 6.7 U	< 0.81 U	< 0.11 U	< 0.092 U	< 0.085 U	< 0.11 U	< 0.46 U	< 0.38 U	< 0.075 U	< 0.4 U	< 0.46 U	< 0.093 U	< 0.35 U	< 0.11 U	< 0.69 U	< 0.54 U	< 0.5 U	< 0.49 U	< 0.46 U	< 1.3 U	< 0.15 U	< 0.31 U	< 2.5 U	< 0.14 U	< 0.3 U	< 0.068 U	< 0.39 U	< 0.63 U	< 260 U	< 0.55 U	< 0.42 U
MW-73I	MW-73I	9/8/2021	180-126846-1	< 1.5 U	< 0.59 UJ	< 6.4 U	< 0.78 UJ	< 0.1 UJ	< 0.088 UJ	< 0.082 UJ	< 0.11 UJ	< 0.44 UJ	< 0.36 UJ	< 0.072 U	< 0.38 UJ	< 0.44 UJ	< 0.089 UJ	< 0.33 UJ	< 0.11 UJ	< 0.66 UJ	< 0.51 UJ	< 0.48 UJ	< 0.47 UJ	< 0.44 UJ	< 1.3 UJ	< 0.15 UJ	< 0.3 UJ	< 2.4 U	0.15 J	< 0.29 UJ	< 0.065 UJ	< 0.37 UJ	< 0.61 UJ	< 250 U	< 0.53 UJ	< 0.4 UJ
MW-73I	SSHS-MW-73I-04052024	4/5/2024	1801720031	< 1.8 U	< 0.21 U	< 3.9 U	< 0.42 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.10 U	< 0.66 U	< 0.22 U	< 0.074 U	< 0.44 U	< 0.070 U	< 0.65 U	< 0.52 U	< 0.43 U	< 0.60 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1.0 U	< 0.19 U	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	-	< 0.30 U	< 0.27 U
MW-73I	MW-73I	10/27/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	0.082 J	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	0.081 J	< 0.28 U	< 0.17 U	0.25	< 0.34 U	0.2	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.18	< 0.45 U	< 0.05 U	0.24 J	< 0.3 U	< 220 U	< 0.23 U	< 0.21 U
MW-73S	MW-73S	10/26/2021	180-129230-1	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	0.1 J	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	0.29	< 0.29 U	< 0.18 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.9 U	< 0.068 U	< 0.11 U	< 0.81 U	0.2	< 0.47 U	0.082 J	< 0.14 U	< 0.31 U	< 230 U	< 0.24 U	< 0.22 U
MW-73S	MW-73S	9/8/2021	180-126846-1	< 1.3 U	< 0.55 U	< 5.9 U	< 0.72 U	< 0.093 U	< 0.081 U	< 0.075 U	< 0.099 U	< 0.4 U	< 0.33 U	< 0.066 U	< 0.35 U	< 0.41 U	< 0.082 U	< 0.31 U	< 0.099 U	< 0.6 U	< 0.47 U	< 0.44 U	< 0.43 U	< 0.4 U	< 1.2 U	< 0.13 U	< 0.28 U	< 2.2 U	< 0.12 U	< 0.26 U	< 0.06 U	< 0.34 U	< 0.56 U	< 240 U	< 0.48 U	< 0.37 U
MW-73S	SSHS-MW-73S-04052024	4/5/2024	1801720031	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	0.11 J	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	0.13 J	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	0.25	< 0.53 U	0.099 J	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-74I	MW-74I	10/27/2021	180-129155-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 210 U	< 0.23 U	< 0.21 U
MW-74I	SSHS-MW-74I-04052024	4/5/2024	1801720031	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-74I	MW-74I	9/8/2021	180-126846-1	< 1.4 U	< 0.57 U	< 6.2 U	< 0.75 U	< 0.097 U	< 0.084 U	< 0.078 U	< 0.1 U	< 0.42 U	< 0.34 U	< 0.069 U	< 0.36 U	< 0.42 U	< 0.085 U	< 0.32 U	< 0.1 U	< 0.63 U	< 0.49 U	< 0.46 U	< 0.45 U	< 0.42 U	< 1.2 U	< 0.14 U	< 0.29 U	< 2.3 U	< 0.13 U	< 0.27 U	< 0.063 U	< 0.36 U	< 0.58 U	< 260 U	< 0.5 U	< 0.38 U
MW-74S	SSHS-DUP-05-04052024	4/5/2024	1801720031	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.19 J	< 0.51 U	0.096 J	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-74S	SSHS-MW-74S-04052024	4/5/2024	1801720031	< 1.7 U	< 0.20 U	< 3.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.63 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.18 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-74S	MW-74S	9/8/2021	180-126846-1	< 1.5 U	< 0.59 U	< 6.4 U	< 0.78 U	< 0.1 U	< 0.088 U	< 0.082 U	< 0.11 U	< 0.44 U	< 0.36 U	< 0.072 U	< 0.38 U	< 0.44 U	< 0.089 U	< 0.33 U	< 0.11 U	< 0.66 U	< 0.51 U	< 0.48 U	< 0.47 U	< 0.44 U	< 1.3 U	< 0.15 U	< 0.3 U	< 2.4 U	< 0.13 U	< 0.29 U	< 0.065 U	< 0.37 U	< 0.61 U	< 250 U	< 0.53 U	< 0.4 U
MW-74S	MW-74S	10/27/2021	180-129155-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	0.15 J	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 240 U	< 0.25 U	< 0.22 U
MW-75I	MW-75I	10/29/2021	180-129376-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	0.083 J	< 0.34 U	0.083 J	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.14 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 210 U	< 0.23 U	< 0.21 U
MW-75I	MW-75I	9/9/2021	180-126905-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 230 U	< 0.46 U	< 0.35 U
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722811	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.24	< 0.51 U	0.064 J	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-75S	MW-75S	10/29/2021	180-129376-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.1 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 200 U	< 0.23 U	< 0.21 U
MW-75S	MW-75S	9/9/2021	180-126905-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 220 U	< 0.46 U	< 0.35 U
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722811	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-76I	MW-76I	10/28/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 UJ	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.11 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 240 U	< 0.23 U	< 0.21 U
MW-76I	DUP-03	10/28/2021	180-129230-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	0.072 J	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.12 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 230 U	< 0.25 U	< 0.22 U
MW-76I	MW-76I	9/10/2021	180-126939-1	< 1.3 U	< 0.55 U	< 5.9 U	< 0.72 U	< 0.093 U	< 0.081 U	< 0.075 U	< 0.099 U	< 0.4 U	< 0.33 U	< 0.066 U	< 0.35 U	< 0.41 U	< 0.082 U	< 0.31 U	< 0.099 U	< 0.6 U	< 0.47 U	< 0.44 U	< 0.43 U	< 0.4 U	< 1.2 U	< 0.13 U	< 0.28 U	< 2.2 U	0.12 J	< 0.26 U	< 0.06 U	< 0.34 U	< 0.56 U	310 J	< 0.48 U	< 0.37 U
MW-76S	MW-76S	10/28/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.14 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 230 U	< 0.23 U	< 0.21 U
MW-76S	SSHS-MW-76S-04082024	4/8/2024	1801720411	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-76S	MW-76S	9/10/2021	180-126939-1	< 1.2 U	< 0.51 U	< 5.5 U	< 0.66 U	< 0.086 U	< 0.075 U	< 0.069 U	0.3	< 0.37 U	< 0.31 U	< 0.061 U	< 0.32 U	< 0.38 U	0.32	< 0.29 U	0.5	< 0.56 U	< 0.44 U	< 0.41 U	< 0.4 U	< 0.37 U	< 1.1 U	< 0.12 U	< 0.25 U	< 2 U	< 0.11 U	< 0.24 U	< 0.056 U	< 0.32 U	< 0.52 U	380 J	< 0.45 U	< 0.34 U
MW-76S	SSHS-MW-76S-04222024	4/22/2024	1801730541	< 1.5 U	< 0.18 UT	< 3.4 U	< 0.37 UT	< 0.063 UT	< 0.072 UT	< 0.058 UT	< 0.072 UT	< 0.52 UT	< 0.14 UT	< 0.089 UT	< 0.58 UT	< 0.20 UT	0.47 T	< 0.39 UT	4.2 T	< 0.57 U	< 0.46 UT	< 0.38 UT	< 0.52 UT	< 0.20 UT	< 0.98 U	< 0.074 UT	< 0.12 UT	< 0.88 U	< 0.16 UT	< 0.51 UT	< 0.056 UT	< 0.16 UT	< 0.34 UT	-	< 0.26 UT	< 0.23 UT
MW-77I	MW-77I	10/28/2021	180-129230-1	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.29 U	< 0.18 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.9 U	< 0.068 U	< 0.11 U	< 0.81 U	0.11 J	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	< 230 U	< 0.24 U	< 0.22 U
MW-77I	SSHS-MW-77I-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	0.21	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-77I	MW-77I	9/10/2021	180-126939-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	0.14 J	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	260 J	< 0.46 U	< 0.35 U
MW-77S	SSHS-MW-77S-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-77S	MW-77S	10/28/2021	180-129230-1	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 UJ	< 0.058 U	< 0.072 UJ	< 0.52 R	< 0.14 UJ	< 0.089 U	< 0.31 UJ	< 0.2 U	< 0.065 UJ	< 0.39 UJ	< 0.061 UJ	< 0.57 U	< 0.46 UJ	< 0.38 UJ	< 0.52 U	< 0.2 UJ	< 0.98 U	< 0.074 UJ	< 0.12 UJ	< 0.88 U	0.19 J	< 0.51 UJ	< 0.056 U	< 0.16 UJ	< 0.34 UJ	< 250 U	< 0.26 U	< 0.23 UJ
MW-77S	MW-77S	9/10/2021	180-126939-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	0.1 J	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	0.16 J	< 0.3 U	0.19	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 230 UJ	< 0.46 U	< 0.35 U
MW-78I	SSHS-MW-78I-04052024	4/5/2024	1801720031	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-78I	MW-78I	11/2/2021	180-129534-1	< 1.5 U	< 0.17 UJ	< 1.5 U	< 0.35 UJ	< 0.06 U	< 0.069 UJ	< 0.056 UJ	< 0.069 UJ	< 0.5 R	< 0.13 UJ	< 0.085 UJ	< 0.3 UJ	< 0.19 UJ	< 0.062 UJ	< 0.37 UJ	< 0.059 UJ	< 0.55 U	< 0.44 UJ	< 0.36 UJ	< 0.5 UJ	< 0.19 UJ	< 0.94 U	< 0.071 UJ	< 0.12 UJ	< 0.85 UJ	< 0.055 U	< 0.49 UJ	< 0.054 U	< 0.15 UJ	< 0.33 UJ	< 230 U	< 0.25 UJ	< 0.22 UJ
MW-78I	MW-78I	9/10/2021	180-126939-1	< 1.5 U	< 0.59 U	< 6.4 U	< 0.78 U	< 0.1 U	< 0.088 U	< 0.082 U	< 0.11 U	< 0.44 U	< 0.36 U	0.073 J	< 0.38 U	< 0.44 U	< 0.089 U	< 0.33 U	< 0.11 U	< 0.66 U	< 0.51 U	< 0.48 U	< 0.47 U	< 0.44 U	< 1.3 U	< 0.15 U	< 0.3 U	< 2.4 U	< 0.13 U	< 0.29 U	< 0.065 U	< 0.37 U	< 0.61 U	< 260 UJ	< 0.53 U	< 0.4 U
MW-78S	MW-78S	11/2/2021	180-129534-1	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.2 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.2 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	< 230 U	< 0.26 U	< 0.23 U
MW-78S	SSHS-MW-78S-04052024	4/5/2024	1801720031	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-78S	MW-78S	9/10/2021	180-126939-1	< 1.5 U	< 0.59 U	< 6.4 U	< 0.78 U	< 0.1 U	< 0.088 U	< 0.082 U	< 0.11 U	< 0.44 U	< 0.36 U	< 0.072 UJ	< 0.38 U	< 0.44 U	< 0.089 U	< 0.33 U	< 0.11 U	< 0.66 U	< 0.51 U	< 0.48 U	< 0.47 U	< 0.44 U	< 1.3 U	< 0.15 U	< 0.3 U	< 2.4 U	< 0.13 U	< 0.29 U	< 0.065 U	< 0.37 U	< 0.61 U	250 J	< 0.53 U	< 0.4 U
MW-78S	DUP-5	9/10/2021	180-126939-1	< 1.5 U	< 0.62 U	< 6.7 U	< 0.81 U	< 0.11 U	< 0.092 U	< 0.085 U	< 0.11 U	< 0.46 U	< 0.38 U	0.15 J	< 0.4 U	< 0.46 U	< 0.093 U	< 0.35 U	< 0.11 U	< 0.69 U	< 0.54 U	< 0.5 U	< 0.49 U	< 0.46 U	< 1.3 U	< 0.15 U	< 0.31 U	< 2.5 U	< 0.14 U	< 0.3 U	< 0.068 U	< 0.39 U	< 0.63 U	270 J	< 0.55 U	< 0.42 U
MW-79I	DUP-04	11/2/2021	180-129534-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.19 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 230 UJ	< 0.25 U	< 0.22 U
MW-79I	MW-79I	11/2/2021	180-129534-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 UJ	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	390 J	< 0.25 U	< 0.22 U
MW-79I	SSHS-MW-79I-04052024	4/5/2024	1801720031	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-79I	MW-79I	9/10/2021	180-126939-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 220 U	< 0.46 U	< 0.35 U
MW-79S	MW-79S	11/2/2021	180-129534-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 220 U	< 0.23 U	< 0.21 U
MW-79S	SSHS-DUP-06-04052024	4/5/2024	1801720031	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-79S	SSHS-MW-79S-04052024	4/5/2024	1801720031	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-79S	MW-79S	9/10/2021	180-126939-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	0.12 J	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 230 U	< 0.46 U	< 0.35 U
MW-81I	MW-81I	8/31/2021	180-126501-1	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.2 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.2 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.1 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	< 240 U	< 0.26 U	< 0.23 U
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731401	< 1.5 UT	< 0.18 UT	< 3.4 U	< 0.37 UT	< 0.063 UT	< 0.072 UT	< 0.058 UT	< 0.072 UT	< 0.52 UT	< 0.14 UT	< 0.089 UT	< 0.58 UT	< 0.20 UT	< 0.065 UT	< 0.39 UT	< 0.061 UT	< 0.57 UT	< 0.46 UT	< 0.38 UT	< 0.52 UT	< 0.20 UT	< 0.98 UT	< 0.074 UT	< 0.12 UT	< 0.88 U	< 0.16 UT	< 0.51 UT	< 0.056 UT	< 0.16 UT	< 0.34 UT	-	< 0.26 UT	< 0.23 UT
MW-81I	MW-81I	7/16/2021	180-124628-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	0.15 J	< 0.36 U	0.24	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.096 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-82S	MW-82S	10/27/2021	180-129230-1	< 1.2 U	< 0.14 U	< 1.2 U	< 0.28 U	< 0.048 U	< 0.056 U	< 0.045 U	< 0.056 U	< 0.4 U	< 0.11 U	< 0.069 U	< 0.24 U	< 0.15 U	< 0.05 U	0.48 J	< 0.048 U	< 0.44 U	< 0.35 U	< 0.29 U	< 0.4 U	< 0.16 U	< 0.76 U	< 0.057 U	< 0.096 U	< 0.68 U	0.073 J	< 0.39 U	< 0.044 U	< 0.12 U	< 0.26 U	< 230 U	< 0.2 U	< 0.18 U
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733271	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-82S	DUP-3	9/7/2021	180-126846-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	0.14 J	0.46 J	< 0.058 U	< 0.33 U	< 0.54 U	< 230 UJ	< 0.46 U	< 0.35 U
MW-82S	MW-82S	9/7/2021	180-126846-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 UJ	< 0.25 UJ	< 0.058 U	< 0.33 U	< 0.54 U	230 J	< 0.46 U	< 0.35 U
MW-83I	MW-83I	10/27/2021	180-129155-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 230 U	< 0.25 U	< 0.22 U
MW-83I	MW-83I	9/8/2021	180-126846-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	0.094 J	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	0.31 J	< 0.058 U	< 0.33 U	< 0.54 U	< 220 U	< 0.46 U	< 0.35 U
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-83S	MW-83S	10/27/2021	180-129155-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	< 0.051 U	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 210 U	< 0.23 U	< 0.21 U
MW-83S	MW-83S	9/8/2021	180-126846-1	< 1.2 U	< 0.51 U	< 5.5 U	< 0.66 U	< 0.086 U	< 0.075 U	< 0.069 U	< 0.092 U	< 0.37 U	< 0.31 U	< 0.061 U	< 0.32 U	< 0.38 U	< 0.076 U	< 0.29 U	< 0.092 U	< 0.56 U	< 0.44 U	< 0.41 U	< 0.4 U	< 0.37 U	< 1.1 U	< 0.12 U	< 0.25 U	< 2 U	0.11 J	0.34 J	< 0.056 U	< 0.32 U	< 0.52 U	< 230 U	< 0.45 U	< 0.34 U
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721871	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-84S	MW-84S	9/9/2021	180-126905-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 UJ	< 0.072 U	< 0.095 UJ	< 0.39 R	< 0.32 UJ	< 0.063 U	< 0.34 UJ	< 0.39 U	< 0.079 UJ	< 0.3 UJ	< 0.095 UJ	< 0.58 U	< 0.45 UJ	< 0.43 UJ	< 0.41 UJ	< 0.39 UJ	< 1.1 U	< 0.13 UJ	< 0.26 UJ	< 2.1 U	< 0.12 U	< 0.25 UJ	< 0.058 U	< 0.33 UJ	< 0.54 UJ	< 220 U	< 0.46 U	< 0.35 UJ
MW-84S	MW-84S	10/27/2021	180-129155-1	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.2 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.2 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	< 220 U	< 0.26 U	< 0.23 U
MW-84S	SSHS-DUP-07-04152024	4/15/2024	1801726651	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-84S	SSHS-MW-84S-04152024	4/15/2024	1801726651	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-85I	MW-85I	7/15/2021	180-124580-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	0.12 J	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.083 J	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	< 220 U	< 0.064 U	< 0.071 U
MW-85I	MW-85I	9/2/2021	180-126608-1	< 1.6 U	< 0.19 U	< 1.7 R	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 UJ	< 0.14 UJ	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 UJ	< 0.92 U	0.14 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 250 U	< 0.27 U	< 0.24 U
MW-85I	SSHS-MW-85I-04222024	4/22/2024	1801730541	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	0.60	< 0.40 U	3.3	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-86I	MW-86I	7/13/2021	180-124378-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.079 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	2600	< 0.059 U	< 0.065 U
MW-86I	SSHS-MW-86I-04042024	4/4/2024	1801719081	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-86I	MW-86I	9/1/2021	180-126593-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	0.11 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 260 U	< 0.27 U	< 0.24 U
MW-87I	MW-87I	7/14/2021	180-124487-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.11 J	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	570	< 0.061 U	< 0.068 U
MW-87I	SSHS-MW-87I-04112024	4/11/2024	1801722811	< 1.5 U	< 0.17 UT	< 3.3 U	< 0.35 UT	< 0.060 UT	< 0.069 UT	< 0.056 U	< 0.069 UT	< 0.50 UT	< 0.13 UT	< 0.085 U	< 0.56 UT	< 0.19 UT	< 0.062 UT	< 0.37 UT	< 0.059 UT	< 0.55 UT	< 0.44 UT	< 0.36 UT	< 0.50 UT	< 0.19 UT	< 0.94 U	< 0.071 UT	< 0.12 UT	< 0.85 U	< 0.16 UT	< 0.49 UT	< 0.054 U	< 0.15 UT	< 0.33 UT	-	< 0.25 UT	< 0.22 UT
MW-87I	MW-87I	9/2/2021	180-126608-1	< 1.7 U	< 0.2 U	< 1.7 U	< 0.4 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.5 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	0.19 J	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	330 J	< 0.29 U	< 0.25 U
MW-88I	MW-88I	7/15/2021	180-124580-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	0.065 J	0.065 J	< 0.36 U	0.12 J	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.087 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-88I	MW-88I	9/2/2021	180-126608-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	0.097 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 270 U	< 0.27 U	< 0.24 U
MW-88I	SSHS-MW-88I-04112024	4/11/2024	1801722811	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-88S	MW-88S	7/15/2021	180-124580-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	0.1 J	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.084 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	3400	< 0.059 U	< 0.065 U
MW-88S	SSHS-MW-88S-04112024	4/11/2024	1801722811	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-88S	MW-88S	9/2/2021	180-126608-1	< 1.7 U	< 0.2 U	< 1.7 U	< 0.4 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.5 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	0.21 J	< 0.55 U	0.092 J	< 0.17 U	< 0.37 U	2200	< 0.29 U	< 0.25 U
MW-89I	MW-89I	7/12/2021	180-124354-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.07 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (DEHP)	4-Bromophenyl phenyl ether	Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroaniline)	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				20			50				0.002		0.002	0.002		5	1		5[1]		50			5		10			0.002			5	1	50	1	50	50	50
Location	Sample Name	Sample Date	Lab Report																																			
MW-89I	MW-89I	9/1/2021	180-126593-1	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	0.96 J	2 J	< 0.058 U	< 0.43 UJ	< 0.32 U	< 0.067 U	< 0.15 UJ	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 UJ	< 0.058 U	< 0.64 U	< 0.19 R	< 0.23 U	0.95 J	< 0.78 U
MW-89I	SSHS-MW-89I-04052024	4/5/2024	1801720031	< 0.081 UT	< 0.081 UT	< 0.20 UT	< 0.061 UT	< 0.79 UT	< 0.18 UT	< 0.67 U	< 0.094 UT	< 0.066 UT	< 0.12 UT	< 0.11 UT	< 0.086 UT	< 0.19 UT	< 0.050 UT	< 0.073 U	< 7.8 U	< 0.40 UT	< 1.2 UT	< 1.8 U	< 0.064 UT	< 0.47 UT	< 0.54 UT	< 0.074 UT	< 0.28 UT	< 0.28 UT	< 0.10 UT	< 0.090 UT	< 0.24 UT	< 0.73 UT	< 0.064 UT	< 0.71 UT	< 0.73 UT	< 0.25 UT	< 6.1 UT	< 0.86 U
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733271	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	1.8 J	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	20	< 0.74 U
MW-89S	MW-89S	9/1/2021	180-126593-1	< 0.081 U	< 0.081 U	< 0.2 U	< 0.061 U	< 0.79 U	< 0.18 U	< 0.67 U	< 0.094 U	< 0.066 U	< 0.12 U	< 0.11 U	< 0.086 U	< 0.19 U	< 0.05 U	< 0.073 U	< 7.8 U	< 0.4 U	< 0.58 U	1.7 J	< 0.064 U	< 0.47 U	< 0.35 U	< 0.074 U	< 0.16 U	< 0.28 U	< 0.1 U	< 0.09 U	< 0.24 U	< 0.73 U	< 0.064 U	< 0.71 U	< 0.21 U	< 0.25 U	0.98 J	< 0.86 U
MW-89S	MW-89S	7/12/2021	180-124354-1	0.11 J	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	1.2 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-8I	MW-8I	7/1/2021	180-123971-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	0.62 J	0.77 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	5.7	< 0.66 U
MW-8I	MW-8I	8/30/2021	180-126485-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	0.68 J	1.2 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	0.85 J	< 0.69 U
MW-8I	DUP-1	8/30/2021	180-126485-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.5 UJ	< 0.51 UJ	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	0.81 J	< 0.74 U
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733271	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	12	< 0.74 U
MW-8S	MW-8S	2/18/2021	180-117476-1	0.11 J	< 0.056 U	< 0.053 U	< 0.042 U	< 0.55 U	< 0.051 U	< 0.096 U	< 0.065 U	< 0.046 U	< 0.084 U	< 0.076 U	< 0.059 U	< 0.058 U	< 0.034 U	< 0.05 U	< 5.4 U	< 0.054 U	< 0.4 U	< 0.41 U	< 0.044 U	< 0.038 U	< 0.053 U	< 0.051 U	< 0.055 U	< 0.053 U	< 0.07 U	< 0.062 U	< 0.063 U	< 0.5 U	< 0.044 U	< 0.49 U	< 0.035 U	< 0.048 U	1.7	< 0.59 U
MW-8S	MW-8S	7/12/2021	180-124354-1	0.12 J	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
MW-90I	MW-90I	10/28/2021	180-129230-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	1.4 J	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-90I	MW-90I	9/8/2021	180-126846-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	0.34 J	< 5.3 U	< 0.74 U
MW-90S	MW-90S	10/28/2021	180-129230-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-90S	MW-90S	9/8/2021	180-126846-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	1.7 J	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721871	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	0.92 J	< 5.1 U	< 0.71 U
MW-91I	MW-91I	11/2/2021	180-129534-1	< 0.063 UJ	< 0.063 UJ	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 UJ	< 0.52 U	< 0.072 U	< 0.051 UJ	< 0.093 UJ	< 0.085 UJ	< 0.066 UJ	< 0.15 UJ	< 0.038 U	< 0.056 U	< 6 U	< 0.31 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.36 UJ	< 0.27 U	< 0.057 UJ	< 0.12 UJ	< 0.21 UJ	< 0.078 U	< 0.069 UJ	< 0.18 UJ	< 0.56 UJ	< 0.049 UJ	< 0.55 U	< 0.16 UJ	< 0.19 U	< 0.71 U	< 0.66 U
MW-91I	MW-91I	9/9/2021	180-126905-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-91S	MW-91S	11/2/2021	180-129534-1	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.2 U	< 0.74 U	< 0.69 U
MW-91S	MW-91S	9/9/2021	180-126905-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	2.1 J	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722811	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-92I	MW-92I	10/28/2021	180-129230-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-92I	SSHS-MW-92I-04082024	4/8/2024	1801720411	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	< 0.049 U	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-92I	MW-92I	9/10/2021	180-126939-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-92S	SSHS-MW-92S-04052024	4/5/2024	1801720031	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	< 0.049 U	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-92S	MW-92S	9/10/2021	180-126939-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	7.9 J	< 0.47 U	0.74 J	1.7 J	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-92S	MW-92S	10/28/2021	180-129230-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	0.9 J	< 0.74 U
MW-93I	MW-93I	10/29/2021	180-129376-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	1.3	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.15 U	< 0.19 U	< 0.69 U	< 0.63 U
MW-93I	DUP-4	9/9/2021	180-126905-1	< 0.067 U	< 0.055 U	< 0.76 U	< 0.052 U	< 0.42 U	< 0.34 U	< 0.41 U	< 0.066 U	< 0.038 U	< 0.068 U	< 0.063 U	< 0.069 U	< 0.36 U	< 0.096 U	< 0.088 U	< 5.1 U	< 0.47 U	< 0.73 U	< 1.5 U	< 0.059 U	< 0.34 U	< 0.51 U	< 0.054 U	< 0.24 U	< 0.46 U	< 0.082 U	< 0.071 U	< 0.41 U	< 0.84 U	< 0.066 U	< 0.9 U	< 0.25 U	< 0.46 U	< 0.83 U	< 0.69 U
MW-93I	SSHS-DUP-08-04112024	4/11/2024	1801722811	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-93I	SSHS-MW-93I-04112024	4/11/2024	1801722811	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-93I	MW-93I	9/9/2021	180-126905-1	< 0.07 U	< 0.057 U	< 0.79 U	< 0.054 U	< 0.43 U	< 0.35 U	< 0.42 U	< 0.069 U	< 0.04 U	< 0.071 U	< 0.065 U	< 0.072 U	< 0.38 U	< 0.1 U	< 0.092 U	< 5.3 U	< 0.49 U	< 0.76 U	< 1.5 U	< 0.061 U	< 0.35 U	< 0.53 U	< 0.056 U	< 0.25 U	< 0.48 U	< 0.085 U	< 0.074 U	< 0.43 U	< 0.87 U	< 0.069 U	< 0.94 U	< 0.26 U	< 0.48 U	< 0.87 U	< 0.72 U
MW-93S	SSHS-MW-93S-04112024	4/11/2024	1801722811	< 0.068 U	0.13 J	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-93S	MW-93S	9/9/2021	180-126905-1	0.088 J	< 0.065 U	< 0.9 U	< 0.061 U	< 0.49 U	< 0.4 U	< 0.48 U	< 0.078 U	< 0.045 U	< 0.081 U	< 0.074 U	< 0.082 U	< 0.43 U	< 0.11 U	< 0.1 U	< 6 U	< 0.56 U	< 0.86 U	1.8 J	< 0.069 U	< 0.4 U	< 0.61 U	< 0.064 U	< 0.28 U	< 0.54 U	< 0.097 U	< 0.084 U	< 0.49 U	< 0.99 U	< 0.078 U	< 1.1 U	< 0.29 U	< 0.55 U	< 0.98 U	< 0.81 U
MW-93S	MW-93S	10/29/2021	180-129376-1	0.13 J	< 0.06 UJ	< 0.15 U	< 0.045 UJ	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 UJ	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 UJ	< 0.037 UJ	< 0.054 U	< 5.8 U	< 0.3 U	0.67 J	< 0.44 U	0.16 J	< 0.35 R	< 0.26 U	< 0.055 UJ	< 0.12 UJ	< 0.2 UJ	< 0.075 U	< 0.067 UJ	< 0.18 UJ	< 0.54 R	< 0.047 UJ	< 0.53 U	< 0.15 UJ	< 0.19 U	< 0.69 U	< 0.63 U
MW-94I	MW-94I	10/27/2021	180-129230-1	< 0.06 U	< 0.06 U	< 0.15 U	< 0.045 U	< 0.59 U	< 0.13 U	< 0.5 U	< 0.069 U	< 0.049 U	< 0.09 U	< 0.081 U	< 0.064 U	< 0.14 U	< 0.037 U	< 0.054 U	< 5.8 U	< 0.3 U	< 0.43 U	< 0.44 U	< 0.047 U	< 0.35 U	< 0.26 U	< 0.055 U	< 0.12 U	< 0.2 U	< 0.075 U	< 0.067 U	< 0.18 U	< 0.54 U	< 0.047 U	1.7	< 0.15 U	< 0.19 U	0.98	< 0.63 U
MW-94I	MW-94I	9/9/2021	180-126905-1	< 0.065 U	< 0.053 U	< 0.73 U	< 0.05 U	< 0.4 U	< 0.32 U	< 0.39 U	< 0.064 U	< 0.037 U	< 0.066 U	< 0.06 U	< 0.067 U	< 0.35 U	< 0.093 U	< 0.085 U	< 4.9 U	< 0.45 U	< 0.7 U	< 1.4 U	< 0.056 U	< 0.33 U	< 0.49 U	< 0.052 U	< 0.23 U	< 0.44 U	< 0.079 U	< 0.069 U	< 0.4 U	< 0.81 U	< 0.064 U	< 0.87 U	< 0.24 U	< 0.45 U	< 0.8 U	< 0.66 U
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722811	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-94S	MW-94S	9/9/2021	180-126905-1	< 0.065 U	< 0.053 U	< 0.73 U	< 0.05 U	< 0.4 U	< 0.32 U	< 0.39 U	< 0.064 U	< 0.037 U	< 0.066 U	< 0.06 U	< 0.067 U	< 0.35 U	< 0.093 U	< 0.085 U	< 4.9 U	< 0.45 U	< 0.7 U	3.1 J	< 0.056 U	< 0.33 U	< 0.49 U	< 0.052 U	< 0.23 U	< 0.44 U	< 0.079 U	< 0.069 U	< 0.4 U	< 0.81 U	< 0.064 U	< 0.87 U	< 0.24 U	< 0.45 U	< 0.8 U	< 0.66 U
MW-94S	MW-94S	10/27/2021	180-129230-1	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.33 U	< 0.48 U	1.2 J	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.2 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	0.95 J	< 0.71 U
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722811	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-95I	SSHS-MW-95I-04112024	4/11/2024	1801722791	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.90 U	< 1.4 U	< 0.049 U	< 0.36 U	< 0.42 U	< 0.057 U	< 0.22 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.56 U	< 0.19 U	< 4.7 U	< 0.66 U
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624601	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	0.63 J	0.81 J	0.051 J	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	< 0.74 U	< 0.69 UT
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653531	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.39 U	< 0.29 U	< 0.061 U	< 0.13 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.17 U	< 0.21 U	5.2 J+	< 0.71 U
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682361	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.10 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 0.55 U	0.79 J	< 0.061 U	< 0.45 U	< 0.33 U	< 0.070 U	< 0.15 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.20 U	< 0.24 U	1.1 J	< 0.82 U
MW-95S	SSHS-MW-95S-04112024	4/11/2024	1801722791	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624601	< 0.071 UJ	< 0.071 UJ	< 0.17 UJ	< 0.053 UJ	< 0.69 UT	< 0.15 UJ	< 0.58 U	< 0.082 UJ	< 0.058 UT	< 0.11 UJ	< 0.096 UJ	< 0.075 UJ	< 0.17 UJ	< 0.043 UJ	< 0.063 UJ	< 6.8 U	< 0.35 UJ	0.75 J	1.2 JT	< 0.055 UJ	< 0.41 UJ	< 0.30 UJ	< 0.064 UJ	< 0.14 UJ	< 0.24 UJ	< 0.088 UJ	< 0.078 UJ	< 0.21 UJ	< 0.63 UJ	< 0.055 UJ	< 0.62 UJ	< 0.18 UJ	< 0.22 UJ	0.94 J	< 0.74 UT
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682361	< 0.074 U	< 0.074 U	< 0.18 U	0.059 J	< 0.72 U	< 0.16 U	< 0.61 U	0.087 J	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	1.1	< 0.78 U
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653531	< 0.086 U	< 0.086 U	< 0.21 U	< 0.064 U	< 0.83 U	< 0.19 U	< 0.71 U	< 0.099 U	< 0.070 U	< 0.13 U	< 0.12 U	< 0.091 U	< 0.20 U	< 0.053 U	< 0.076 U	< 8.2 U	< 0.42 U	< 0.61 U	< 0.62 U	< 0.067 U	< 0.49 U	< 0.37 U	< 0.078 U	< 0.17 U	< 0.29 U	< 0.11 U	< 0.095 U	< 0.25 U	< 0.77 U	< 0.067 U	< 0.75 U	< 0.22 U	< 0.26 U	3.7 J+	< 0.90 U
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721201	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.94 U	< 1.4 U	< 0.051 U	< 0.38 U	< 0.44 U	< 0.059 U	< 0.23 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.59 U	< 0.20 U	< 4.9 U	< 0.69 U
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	1.3	< 0.69 U
MW-96	SSHS-MW-96-09152023	9/15/2023	1801625601	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	7.0	< 0.74 U
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653531	< 0.077 U	< 0.077 U	< 0.19 U	< 0.058 U	< 0.75 U	< 0.17 U	< 0.64 U	< 0.089 U	< 0.063 U	< 0.12 U	< 0.10 U	< 0.082 U	< 0.18 U	< 0.048 U	< 0.069 U	< 7.4 U	< 0.38 U	< 0.55 U	< 0.56 U	< 0.061 U	< 0.45 U	< 0.33 U	< 0.070 U	< 0.15 U	< 0.26 U	< 0.096 U	< 0.086 U	< 0.23 U	< 0.69 U	< 0.061 U	< 0.68 U	< 0.20 U	< 0.24 U	< 0.88 U	< 0.82 U
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682361	< 0.096 U	< 0.096 U	< 0.23 U	< 0.072 U	< 0.93 U	< 0.21 U	< 0.79 U	< 0.11 U	< 0.078 U	< 0.14 U	< 0.13 U	< 0.10 U	< 0.22 U	< 0.059 U	< 0.085 U	< 9.2 U	< 0.47 U	< 0.68 U	12	< 0.075 U	< 0.55 U	< 0.41 U	< 0.087 U	< 0.19 U	< 0.33 U	< 0.12 U	< 0.11 U	< 0.28 U	< 0.86 U	< 0.075 U	< 0.83 U	< 0.25 U	< 0.29 U	2.8	< 1.0 U
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559471	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	2.1	< 0.69 U
MW-97	SSHS-MW-97-09152023	9/15/2023	1801625601	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	0.59 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	3.9	< 0.69 U
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721201	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653531	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	3.9 J+	< 0.74 U
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682361	< 0.086 U	< 0.086 U	< 0.21 U	< 0.064 U	< 0.83 U	< 0.19 U	< 0.71 U	< 0.099 U	< 0.070 U	< 0.13 U	< 0.12 U	< 0.091 U	< 0.20 U	< 0.053 U	< 0.076 U	< 8.2 U	< 0.42 U	< 0.61 U	< 0.62 U	< 0.067 U	< 0.49 U	< 0.37 U	< 0.078 U	< 0.17 U	< 0.29 U	< 0.11 U	< 0.095 U	< 0.25 U	< 0.77 U	< 0.067 U	< 0.75 U	< 0.22 U	< 0.26 U	2.2	< 0.90 U
MW-98I	DUP-01	9/1/2022	1801438881	< 0.063 U	< 0.063 U	< 0.15 U	< 0.047 U	< 0.61 U	< 0.14 U	< 0.52 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.15 U	< 0.038 U	< 0.056 U	< 6.0 U	< 0.31 U	< 0.44 U	1.8 J	< 0.049 U	< 0.36 U	< 0.27 U	< 0.057 U	< 0.12 U	< 0.21 U	< 0.078 U	< 0.069 U	< 0.18 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.16 U	< 0.19 U	0.74 J	< 0.66 U
MW-98I	MW-98I	9/1/2022	1801438881	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	1.2 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	0.76 J	< 0.69 U
MW-98I	SSHS-MW-98I-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624611	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	2.9 J+	< 0.78 U
MW-98S	MW-98S	9/1/2022	1801438881	< 0.065 U	< 0.065 U	< 0.16 U	< 0.049 U	< 0.63 U	< 0.14 U	< 0.54 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.15 U	< 0.040 U	< 0.058 U	< 6.2 U	< 0.32 U	< 0.46 U	1.1 J	< 0.051 U	< 0.38 U	< 0.28 U	< 0.059 U	< 0.13 U	< 0.22 U	< 0.081 U	< 0.072 U	< 0.19 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.17 U	< 0.20 U	< 0.74 U	< 0.69 U
MW-98S	SSHS-MW-98S-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624611	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.50 U	< 0.51 U	< 0.055 U	< 0.41 U	< 0.30 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	2.6 J+	< 0.74 U
MW-99I	SSHS-MW-99I-04102024	4/10/2024	1801721871	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	< 5.1 U	< 0.71 U
MW-99I	SSHS-MW-99I-09132023	9/13/2023	1801624611	< 0.074 U	< 0.074 U	< 0.18 U	< 0.056 U	< 0.72 U	< 0.16 U	< 0.61 U	< 0.085 U	< 0.060 U	< 0.11 U	< 0.10 U	< 0.078 U	< 0.17 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.36 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.43 U	< 0.32 U	< 0.067 U	< 0.15 U	< 0.25 U	< 0.092 U	< 0.082 U	< 0.22 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.19 U	< 0.23 U	1.5 J+	< 0.78 U
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721871	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 1.0 U	< 1.5 U	< 0.055 U	< 0.41 U	< 0.47 U	< 0.064 U	< 0.24 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.64 U	< 0.22 U	< 5.3 U	< 0.74 U
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624611	< 0.071 UJ	< 0.071 UJ	< 0.17 UJ	< 0.053 UJ	< 0.69 UT	< 0.15 UJ	< 0.58 U	< 0.082 UJ	< 0.058 UJ	< 0.11 UJ	< 0.096 UJ	< 0.075 UJ	< 0.17 UJ	< 0.043 UJ	< 0.063 U	< 6.8 U	< 0.35 UJ	0.79 J	0.98 J	< 0.055 UJ	< 0.41 UJ	< 0.30 UJ	< 0.064 UJ	< 0.14 UJ	< 0.24 UJ	< 0.088 UJ	< 0.078 UJ	< 0.21 UJ	< 0.63 UJ	< 0.055 UJ	< 0.62 UJ	< 0.18 UJ	< 0.22 UJ	1.7 J	< 0.74 U
MW-9I	MW-9I	7/14/2021	180-124487-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733271	< 0.068 U	< 0.068 U	< 0.17 U	< 0.051 U	< 0.66 U	< 0.15 U	< 0.56 U	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 U	< 0.072 U	< 0.16 U	< 0.042 U	< 0.060 U	< 6.5 U	< 0.33 U	< 0.98 U	< 1.5 U	< 0.053 U	< 0.39 U	< 0.45 U	< 0.061 U	< 0.23 U	< 0.23 U	< 0.084 U	< 0.075 U	< 0.20 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.61 U	< 0.21 U	16	< 0.71 U
MW-9I	MW-9I	8/31/2021	180-126501-1	< 0.071 U	< 0.071 U	< 0.17 U	< 0.053 U	< 0.69 U	< 0.15 U	< 0.58 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.17 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.35 U	< 0.5 U	0.78 J	< 0.055 U	< 0.41 U	< 0.3 U	< 0.064 U	< 0.14 U	< 0.24 U	< 0.088 U	< 0.078 U	< 0.21 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.18 U	< 0.22 U	1.2	< 0.74 U
MW-9S	MW-9	2/20/2021	180-117476-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	< 0.093 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	< 0.39 U	< 0.39 U	< 0.043 U	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	< 0.068 U	< 0.06 U	< 0.061 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.034 U	< 0.047 U	1.3	< 0.57 U
MW-9S	MW-9	7/14/2021	180-124487-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	7.2 J	< 0.061 U	< 0.44 U	0.96 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	8/4/2021	1801253661	0.073 J	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 UT	< 0.078 U	< 0.055 U	< 0.10 U	< 0.092 UT	< 0.072 U	< 0.070 U	< 0.042 UT	< 0.060 U	21	< 0.066 U	1.3	2.2 J	< 0.053 UT	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 UT	< 0.075 U	0.084 J	< 0.61 U	< 0.053 U	< 0.59 UT	< 0.043 U	< 0.058 U	3.6 B	< 0.71 U
SSHS-B23	B23	5/9/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.2 JB	-
SSHS-B2541	SSHS-B2541-GW	10/29/2018	180-83541-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.21 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 5.2 U	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
SSHS-B2542	SSHS-B2542-GW	10/29/2018	180-83541-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.19 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 4.8 U	< 0.066 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	< 0.77 U	< 0.71 U
SSHS-B2543	SSHS-B2543-GW	10/30/2018	180-83544-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.18 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 4.6 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 U
SSHS-B2544	SSHS-B2544-GW	10/30/2018	180-83544-1	< 0.071 U	< 0.071 U	< 0.067 U	0.18 J	< 0.2 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 5 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
SSHS-B2629	SSHS-B2629	4/25/2019	180-89520-1	0.32	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	TPH-DRO	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	1	5	50	50	0.04	0.5	5	5	0.002		50			10	5	5	5	0.4				50	1	50	1	50					
Location	Sample Name	Sample Date	Lab Report																																	
MW-89I	MW-89I	9/1/2021	180-126593-1	< 1.7 U	< 0.2 U	< 1.7 U	< 0.4 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 UJ	< 0.15 UJ	< 0.097 U	< 0.34 UJ	< 0.21 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.5 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 UJ	< 0.14 UJ	< 0.96 U	0.12 J	< 0.55 UJ	< 0.061 U	< 0.17 U	< 0.37 U	< 270 U	< 0.29 U	< 0.25 U
MW-89I	SSHS-MW-89I-04052024	4/5/2024	1801720031	< 1.8 UT	< 0.22 UT	< 4.1 U	< 0.44 UT	< 0.075 UT	< 0.086 UT	< 0.070 UT	< 0.086 UT	< 0.62 UT	< 0.17 UT	< 0.11 UT	< 0.70 UT	< 0.24 UT	< 0.078 UT	< 0.47 UT	< 0.074 UT	< 0.69 UT	< 0.55 UT	< 0.45 UT	< 0.63 UT	< 0.24 UT	< 1.2 U	< 0.089 UT	< 0.15 UT	< 1.1 UT	< 0.20 UT	< 0.61 UT	< 0.068 UT	< 0.19 UT	< 0.41 UT	-	< 0.32 UT	< 0.28 UT
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733271	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-89S	MW-89S	9/1/2021	180-126593-1	< 1.8 U	< 0.22 U	< 1.9 U	< 0.44 U	< 0.075 U	< 0.086 U	< 0.07 U	< 0.086 U	< 0.62 U	< 0.17 U	< 0.11 U	< 0.38 U	< 0.24 U	< 0.078 U	< 0.47 U	< 0.074 U	< 0.69 U	< 0.55 U	< 0.45 U	< 0.63 U	< 0.24 U	< 1.2 U	< 0.089 U	< 0.15 U	< 1.1 U	0.12 J	< 0.61 U	< 0.068 U	< 0.19 U	< 0.41 U	< 260 U	< 0.32 U	< 0.28 U
MW-89S	MW-89S	7/12/2021	180-124354-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.09 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-8I	MW-8I	7/1/2021	180-123971-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.084 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 220 U	< 0.059 U	< 0.065 U
MW-8I	MW-8I	8/30/2021	180-126485-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	0.087 J	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.23 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	< 240 U	< 0.25 U	< 0.22 U
MW-8I	DUP-1	8/30/2021	180-126485-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	0.13 J	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	0.16 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 250 U	< 0.27 U	< 0.24 U
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733271	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	0.13 J	< 0.40 U	0.18 J	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-8S	MW-8S	2/18/2021	180-117476-1	< 1.3 U	< 0.052 U	< 1.3 U	< 0.044 U	< 0.052 U	< 0.059 U	< 0.048 U	< 0.059 U	< 0.43 U	< 0.053 U	< 0.073 U	< 0.26 U	< 0.047 U	< 0.053 U	< 0.32 U	< 0.051 U	< 0.47 U	< 0.058 U	< 0.05 U	< 0.43 U	< 0.053 U	< 0.12 U	< 0.061 U	< 0.1 U	< 0.73 U	< 0.047 U	< 0.42 U	< 0.047 U	< 0.045 U	< 0.039 U	2600	< 0.053 U	< 0.059 U
MW-8S	MW-8S	7/12/2021	180-124354-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.13 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	1700	< 0.066 U	< 0.074 U
MW-90I	MW-90I	10/28/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.14 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 200 U	< 0.23 U	< 0.21 U
MW-90I	MW-90I	9/8/2021	180-126846-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 220 U	< 0.46 U	< 0.35 U
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-90S	MW-90S	10/28/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	0.11 J	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.11 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 220 U	< 0.23 U	< 0.21 U
MW-90S	MW-90S	9/8/2021	180-126846-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	0.13 J	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	340 J	< 0.46 U	< 0.35 U
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721871	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-91I	MW-91I	11/2/2021	180-129534-1	< 1.4 U	< 0.17 U	< 1.5 R	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 UJ	< 0.48 R	< 0.13 UJ	< 0.082 UJ	< 0.29 U	< 0.18 U	< 0.06 UJ	< 0.36 U	< 0.057 UJ	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 UJ	< 0.9 U	< 0.068 U	< 0.11 UJ	< 0.81 U	0.21 J+	< 0.47 U	< 0.052 U	< 0.14 UJ	< 0.31 U	< 210 U	< 0.24 UJ	< 0.22 UJ
MW-91I	MW-91I	9/9/2021	180-126905-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 220 U	< 0.46 U	< 0.35 U
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-91S	MW-91S	11/2/2021	180-129534-1	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.13 U	< 0.085 U	< 0.3 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.5 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.2 J+	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	540	< 0.25 U	< 0.22 U
MW-91S	MW-91S	9/9/2021	180-126905-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 210 U	< 0.46 U	< 0.35 U
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722811	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-92I	MW-92I	10/28/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.076 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 220 U	< 0.23 U	< 0.21 U
MW-92I	SSHS-MW-92I-04082024	4/8/2024	1801720411	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-92I	MW-92I	9/10/2021	180-126939-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 220 UJ	< 0.46 U	< 0.35 U
MW-92S	SSHS-MW-92S-04052024	4/5/2024	1801720031	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-92S	MW-92S	9/10/2021	180-126939-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	0.085 J	< 0.3 U	0.12 J	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 240 U	< 0.46 U	< 0.35 U
MW-92S	MW-92S	10/28/2021	180-129230-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	0.14 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 230 U	< 0.27 U	< 0.24 U
MW-93I	MW-93I	10/29/2021	180-129376-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.096 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	< 210 U	< 0.23 U	< 0.21 U
MW-93I	DUP-4	9/9/2021	180-126905-1	< 1.3 U	< 0.53 U	< 5.7 U	< 0.69 U	< 0.089 U	< 0.078 U	< 0.072 U	< 0.095 U	< 0.39 U	< 0.32 U	< 0.063 U	< 0.34 U	< 0.39 U	< 0.079 U	< 0.3 U	< 0.095 U	< 0.58 U	< 0.45 U	< 0.43 U	< 0.41 U	< 0.39 U	< 1.1 U	< 0.13 U	< 0.26 U	< 2.1 U	< 0.12 U	< 0.25 U	< 0.058 U	< 0.33 U	< 0.54 U	< 250 U	< 0.46 U	< 0.35 U
MW-93I	SSHS-DUP-08-04112024	4/11/2024	1801722811	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-93I	SSHS-MW-93I-04112024	4/11/2024	1801722811	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-93I	MW-93I	9/9/2021	180-126905-1	< 1.3 U	< 0.55 U	< 5.9 U	< 0.72 U	< 0.093 U	< 0.081 U	< 0.075 U	< 0.099 U	< 0.4 U	< 0.33 U	< 0.066 U	< 0.35 U	< 0.41 U	< 0.082 U	< 0.31 U	< 0.099 U	< 0.6 U	< 0.47 U	< 0.44 U	< 0.43 U	< 0.4 U	< 1.2 U	< 0.13 U	< 0.28 U	< 2.2 U	< 0.12 U	< 0.26 U	< 0.06 U	< 0.34 U	< 0.56 U	< 250 U	< 0.48 U	< 0.37 U
MW-93S	SSHS-MW-93S-04112024	4/11/2024	1801722811	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	0.075 J	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.38	< 0.51 U	0.12 J	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-93S	MW-93S	9/9/2021	180-126905-1	< 1.5 U	< 0.62 U	< 6.7 U	< 0.81 U	0.4	< 0.092 U	< 0.085 U	< 0.11 U	< 0.46 U	< 0.38 U	< 0.075 U	< 0.4 U	< 0.46 U	< 0.093 U	< 0.35 U	< 0.11 U	< 0.69 U	< 0.54 U	< 0.5 U	< 0.49 U	< 0.46 U	< 1.3 U	< 0.15 U	< 0.31 U	< 2.5 U	< 0.14 U	< 0.3 U	0.26	< 0.39 U	< 0.63 U	< 260 U	< 0.55 U	< 0.42 U
MW-93S	MW-93S	10/29/2021	180-129376-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	0.4	0.14 J	< 0.052 U	< 0.064 UJ	< 0.46 UJ	< 0.12 UJ	< 0.079 U	< 0.28 UJ	< 0.17 U	< 0.057 UJ	< 0.34 UJ	0.087 J	< 0.51 UJ	< 0.4 UJ	< 0.34 UJ	< 0.46 U	< 0.18 UJ	< 0.87 U	< 0.066 UJ	< 0.11 UJ	< 0.78 U	0.33	< 0.45 U	0.26	< 0.14 U	< 0.3 U	360 J	< 0.23 U	< 0.21 U
MW-94I	MW-94I	10/27/2021	180-129230-1	< 1.4 U	< 0.16 U	< 1.4 U	< 0.33 U	< 0.056 U	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.12 U	< 0.079 U	< 0.28 U	< 0.17 U	< 0.057 U	< 0.34 U	0.062 J	< 0.51 U	< 0.4 U	< 0.34 U	< 0.46 U	< 0.18 U	< 0.87 U	< 0.066 U	< 0.11 U	< 0.78 U	0.13 J	< 0.45 U	< 0.05 U	< 0.14 U	< 0.3 U	360 J	< 0.23 U	< 0.21 U
MW-94I	MW-94I	9/9/2021	180-126905-1	< 1.2 U	< 0.51 U	< 5.5 U	< 0.66 U	< 0.086 U	< 0.075 U	< 0.069 U	< 0.092 U	< 0.37 U	< 0.31 U	< 0.061 U	< 0.32 U	< 0.38 U	< 0.076 U	< 0.29 U	< 0.092 U	< 0.56 U	< 0.44 U	< 0.41 U	< 0.4 U	< 0.37 U	< 1.1 U	< 0.12 U	< 0.25 U	< 2 U	< 0.11 U	< 0.24 U	< 0.056 U	< 0.32 U	< 0.52 U	< 200 U	< 0.45 U	< 0.34 U
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722811	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-94S	MW-94S	9/9/2021	180-126905-1	< 1.2 U	< 0.51 U	< 5.5 U	< 0.66 U	< 0.086 U	< 0.075 U	< 0.069 U	< 0.092 U	< 0.37 U	< 0.31 U	< 0.061 U	< 0.32 U	< 0.38 U	< 0.076 U	< 0.29 U	< 0.092 U	< 0.56 U	< 0.44 U	< 0.41 U	< 0.4 U	< 0.37 U	< 1.1 U	< 0.12 U	< 0.25 U	< 2 U	< 0.11 U	0.4 J	< 0.056 U	< 0.32 U	< 0.52 U	< 210 U	< 0.45 U	< 0.34 U
MW-94S	MW-94S	10/27/2021	180-129230-1	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.2 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.2 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	0.095 J	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	< 220 U	< 0.26 U	< 0.23 U
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722811	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-95I	SSHS-MW-95I-04112024	4/11/2024	1801722791	< 1.4 U	< 0.17 U	< 3.1 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.54 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.15 U	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624601	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653531	< 1.5 U	< 0.18 U	< 1.6 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.31 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682361	< 1.8 U	< 0.21 U	< 1.8 U	< 0.42 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.10 U	< 0.36 U	< 0.22 U	< 0.074 U	< 0.44 U	< 0.070 U	< 0.65 U	< 0.52 U	< 0.43 U	< 0.60 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1.0 U	0.098 J	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	-	< 0.30 U	< 0.27 U
MW-95S	SSHS-MW-95S-04112024	4/11/2024	1801722791	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624601	< 1.6 UJ	< 0.19 UJ	< 1.7 UJ	< 0.38 UJ	< 0.065 UJ	< 0.075 UJ	< 0.061 UJ	< 0.075 UJ	< 0.54 UJ	< 0.14 UJ	< 0.092 UJ	< 0.33 UJ	< 0.20 UT	< 0.067 UJ	< 0.40 UJ	< 0.064 UJ	< 0.60 U	< 0.48 UJ	< 0.39 UJ	< 0.54 UJ	< 0.21 UJ	< 1.0 U	< 0.077 UJ	< 0.13 UJ	< 0.92 UJ	0.089 J	< 0.53 UJ	< 0.059 UJ	< 0.16 UJ	< 0.35 UJ	-	< 0.27 UJ	< 0.24 UJ
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682361	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	0.20 J	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	0.41	< 0.55 U	0.14 J	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653531	< 1.9 U	< 0.23 U	< 2.0 U	< 0.46 U	< 0.079 U	< 0.091 U	< 0.074 U	< 0.091 U	< 0.65 U	< 0.18 U	< 0.11 U	< 0.39 U	< 0.25 U	< 0.082 U	< 0.49 U	< 0.078 U	< 0.72 U	< 0.58 U	< 0.48 U	< 0.66 U	< 0.25 U	< 1.2 U	< 0.093 U	< 0.16 U	< 1.1 U	0.072 J	< 0.64 U	< 0.071 U	< 0.20 U	< 0.43 U	-	< 0.33 U	< 0.29 U
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721201	< 1.5 U	< 0.17 U	< 3.3 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.56 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.16 U	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.071 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-96	SSHS-MW-96-09152023	9/15/2023	1801625601	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.060 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653531	< 1.8 U	< 0.21 U	< 1.8 U	< 0.42 U	< 0.071 U	< 0.082 U	< 0.067 U	< 0.082 U	< 0.59 U	< 0.16 U	< 0.10 U	< 0.36 U	< 0.22 U	< 0.074 U	< 0.44 U	< 0.070 U	< 0.65 U	< 0.52 U	< 0.43 U	< 0.60 U	< 0.23 U	< 1.1 U	< 0.085 U	< 0.14 U	< 1.0 U	< 0.065 U	< 0.58 U	< 0.064 U	< 0.18 U	< 0.39 U	-	< 0.30 U	< 0.27 U
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682361	< 2.2 U	< 0.25 U	< 2.3 U	< 0.52 U	< 0.088 U	< 0.10 U	< 0.082 U	< 0.10 U	< 0.73 U	< 0.20 U	< 0.13 U	< 0.44 U	< 0.28 U	< 0.091 U	< 0.55 U	< 0.087 U	< 0.81 U	< 0.64 U	< 0.53 U	< 0.74 U	< 0.28 U	< 1.4 U	< 0.10 U	< 0.18 U	< 1.2 U	0.11 J	< 0.72 U	< 0.079 U	< 0.22 U	< 0.48 U	-	< 0.37 U	< 0.33 U
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559471	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.096 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-97	SSHS-MW-97-09152023	9/15/2023	1801625601	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.079 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721201	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653531	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	0.066 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682361	< 1.9 U	< 0.23 U	< 2.0 U	< 0.46 U	< 0.079 U	< 0.091 U	< 0.074 U	< 0.091 U	< 0.65 U	< 0.18 U	< 0.11 U	< 0.39 U	< 0.25 U	< 0.082 U	< 0.49 U	< 0.078 U	< 0.72 U	< 0.58 U	< 0.48 U	< 0.66 U	< 0.25 U	< 1.2 U	< 0.093 U	< 0.16 U	< 1.1 U	0.15 J	< 0.64 U	< 0.071 U	< 0.20 U	< 0.43 U	-	< 0.33 U	< 0.29 U
MW-98I	DUP-01	9/1/2022	1801438881	< 1.4 U	< 0.17 U	< 1.5 U	< 0.34 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.13 U	< 0.082 U	< 0.29 U	< 0.18 U	< 0.060 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.42 U	< 0.35 U	< 0.48 U	< 0.19 U	< 0.90 U	< 0.068 U	< 0.11 U	< 0.81 U	0.12 J	< 0.47 U	< 0.052 U	< 0.14 U	< 0.31 U	-	< 0.24 U	< 0.22 U
MW-98I	MW-98I	9/1/2022	1801438881	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.11 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-98I	SSHS-MW-98I-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624611	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-98S	MW-98S	9/1/2022	1801438881	< 1.5 U	< 0.17 U	< 1.5 U	< 0.35 U	< 0.060 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.50 U	< 0.13 U	< 0.085 U	< 0.30 U	< 0.19 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.44 U	< 0.36 U	< 0.50 U	< 0.19 U	< 0.94 U	< 0.071 U	< 0.12 U	< 0.85 U	0.16 J	< 0.49 U	< 0.054 U	< 0.15 U	< 0.33 U	-	< 0.25 U	< 0.22 U
MW-98S	SSHS-MW-98S-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624611	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.20 U	0.67	< 0.40 U	4.4	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.060 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-99I	SSHS-MW-99I-04102024	4/10/2024	1801721871	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-99I	SSHS-MW-99I-09132023	9/13/2023	1801624611	< 1.7 U	< 0.20 U	< 1.7 U	< 0.40 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.15 U	< 0.097 U	< 0.34 U	< 0.21 U	< 0.070 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.50 U	< 0.41 U	< 0.57 U	< 0.22 U	< 1.1 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.17 U	< 0.37 U	-	< 0.29 U	< 0.25 U
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721871	< 1.6 U	< 0.19 U	< 3.5 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.61 U	< 0.20 U	< 0.067 U	< 0.40 U	< 0.064 U	< 0.60 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1.0 U	< 0.077 U	< 0.13 U	< 0.92 U	< 0.17 U	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	-	< 0.27 U	< 0.24 U
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624611	< 1.6 UJ	< 0.19 UJ	< 1.7 UJ	< 0.38 UJ	< 0.065 UJ	< 0.075 UJ	< 0.061 UJ	< 0.075 UJ	< 0.54 UJ	< 0.14 UJ	< 0.092 UJ	< 0.33 UJ	< 0.20 UJ	< 0.067 UJ	< 0.40 UJ	< 0.064 UJ	< 0.60 U	< 0.48 UJ	< 0.39 UJ	< 0.54 UJ	< 0.21 UJ	< 1.0 UJ	< 0.077 UJ	< 0.13 UJ	< 0.92 UJ	< 0.060 UJ	< 0.53 UJ	< 0.059 UJ	< 0.16 UJ	< 0.35 UJ	-	< 0.27 UJ	< 0.24 UJ
MW-9I	MW-9I	7/14/2021	180-124487-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.11 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	< 230 U	< 0.059 U	< 0.065 U
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733271	< 1.5 U	< 0.18 U	< 3.4 U	< 0.37 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.14 U	< 0.089 U	< 0.58 U	< 0.20 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.46 U	< 0.38 U	< 0.52 U	< 0.20 U	< 0.98 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.16 U	< 0.51 U	< 0.056 U	< 0.16 U	< 0.34 U	-	< 0.26 U	< 0.23 U
MW-9I	MW-9I	8/31/2021	180-126501-1	< 1.6 U	< 0.19 U	< 1.7 U	< 0.38 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.14 U	< 0.092 U	< 0.33 U	< 0.2 U	< 0.067 U	< 0.4 U	0.07 J	< 0.6 U	< 0.48 U	< 0.39 U	< 0.54 U	< 0.21 U	< 1 U	< 0.077 U	< 0.13 U	< 0.92 U	0.15 J	< 0.53 U	< 0.059 U	< 0.16 U	< 0.35 U	< 250 U	< 0.27 U	< 0.24 U
MW-9S	MW-9	2/20/2021	180-117476-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	< 0.071 U	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	0.091 J	< 0.41 U	< 0.045 U	< 0.043 U	< 0.038 U	2100	< 0.051 U	< 0.057 U
MW-9S	MW-9	7/14/2021	180-124487-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.15 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	350 J	< 0.059 U	< 0.065 U
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	8/4/2021	1801253661	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 UT	< 0.058 U	< 0.072 UT	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	0.068 J	< 0.39 U	< 0.061 U	< 0.57 UT	< 0.070 U	< 0.060 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 UT	< 0.88 U	0.12 J	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-B23	B23	5/9/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2541	SSHS-B2541-GW	10/29/2018	180-83541-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.12 U	< 0.061 U	< 0.07 U	< 0.48 U	< 0.067 U	< 0.24 U	< 0.076 U	< 0.066 U	< 0.19 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.28 U	< 0.063 U	< 0.11 U	< 0.061 U	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
SSHS-B2542	SSHS-B2542-GW	10/29/2018	180-83541-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.11 U	< 0.056 U	< 0.065 U	< 0.44 U	< 0.061 U	< 0.22 U	< 0.07 U	< 0.06 U	< 0.17 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.25 U	< 0.057 U	< 0.1 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-B2543	SSHS-B2543-GW	10/30/2018	180-83544-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.11 U	< 0.054 U	< 0.062 U	< 0.42 U	< 0.059 U	< 0.21 U	< 0.067 U	< 0.058 U	< 0.17 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.24 U	< 0.055 U	< 0.098 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-B2544	SSHS-B2544-GW	10/30/2018	180-83544-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	0.26	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.12 U	< 0.059 U	< 0.067 U	< 0.46 U	< 0.064 U	< 0.23 U	< 0.073 U	< 0.063 U	< 0.18 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.26 U	0.53	< 0.11 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
SSHS-B2629	SSHS-B2629	4/25/2019	180-89520-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.1 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (DEHP)	4-Bromophenyl phenyl ether	Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroaniline)	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				20			50				0.002		0.002	0.002		5	1		5[1]		50			5		10			0.002			5	1	50	1	50	50	50
Location	Sample Name	Sample Date	Lab Report																																			
SSHS-B26-A	SSHS-B26-A-GW-18-22	8/14/2014	180-35818-2	< 0.014 U	< 0.015 U	< 0.077 U	< 0.015 U	< 0.086 U	< 0.04 U	< 0.14 U	3.7	0.59	< 0.015 U	< 0.053 U	< 0.015 U	< 0.056 U	< 0.024 U	< 0.019 U	< 1.2 U	< 0.061 U	< 0.14 UJ	< 1.1 U	< 0.015 U	< 0.085 U	< 0.073 U	< 0.015 U	< 0.16 U	< 0.048 U	7 J	< 0.015 U	< 0.059 U	< 0.11 U	< 0.032 U	< 0.14 U	< 0.082 UJ	< 0.074 U	< 0.12 U	< 0.2 U
SSHS-B2752	SSHS-B2752	4/25/2019	180-89520-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.072 U	< 0.53 U	0.93 J	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	< 0.84 U	< 0.78 U
SSHS-B29-A	SSHS-B29-A-GW-18-22	8/13/2014	180-35776-2	< 0.014 U	< 0.014 U	< 0.075 U	< 0.015 U	< 0.084 U	< 0.039 U	< 0.14 U	< 0.014 U	< 0.013 UJ	< 0.015 UJ	< 0.052 UJ	< 0.014 UJ	< 0.055 U	< 0.024 U	< 0.019 U	3.9	< 0.06 U	< 0.13 U	< 1.1 U	< 0.015 U	< 0.083 U	< 0.071 U	< 0.014 U	< 0.16 U	< 0.047 U	< 0.013 U	< 0.015 UJ	< 0.058 U	< 0.11 U	< 0.032 U	< 0.14 U	< 0.08 U	< 0.072 U	< 0.12 U	< 0.19 UJ
SSHS-B3200A	DUP-01	9/15/2019	180-95745-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	16 J	< 0.063 U	< 0.46 U	1.3 J	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	< 0.74 U	< 0.69 UJ
SSHS-B3200A	SSHS-B3200a	9/15/2019	180-95745-1	< 0.068 UJ	< 0.068 UJ	< 0.065 UJ	< 0.051 U	< 0.66 U	< 0.061 UJ	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 UJ	< 0.042 UJ	< 0.06 U	< 6.5 UJ	< 0.066 U	< 0.48 U	< 0.49 UJ	< 0.053 U	< 0.046 UJ	< 0.064 U	< 0.061 UJ	< 0.067 UJ	< 0.064 UJ	< 0.084 U	< 0.075 U	< 0.076 UJ	< 0.61 U	< 0.053 UJ	< 0.59 U	< 0.043 UJ	< 0.058 U	< 0.77 U	0.75 J
SSHS-B3203A	SSHS-3203a	9/13/2019	180-95715-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	6.6 J	< 0.066 U	< 0.48 U	0.6 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	< 0.77 U	< 0.71 U
SSHS-B510	SSHS-B510	9/20/2016	180-58901-1	0.24	< 0.015 U	< 0.077 U	< 0.015 U	< 0.086 U	0.046 J	< 0.14 U	< 0.014 U	< 0.013 U	< 0.015 U	< 0.053 U	< 0.015 U	< 0.056 U	< 0.024 U	< 0.019 U	2.3	< 0.061 U	0.49 J	< 1.1 U	< 0.015 U	< 0.085 U	< 0.073 U	< 0.015 U	< 0.16 U	< 0.048 U	< 0.013 U	< 0.015 U	0.069 J	< 0.11 U	< 0.032 U	< 0.14 U	< 0.082 U	< 0.074 U	< 0.12 U	< 0.2 U
SSHS-B572A	SSHS-B572A	9/2/2016	180-58309-2	< 0.03 U	< 0.022 U	< 0.12 U	< 0.02 U	< 0.23 U	< 0.11 U	< 0.11 U	< 0.038 U	< 0.029 U	< 0.051 U	< 0.031 U	< 0.03 U	< 0.14 U	< 0.033 U	< 0.025 U	3.9	< 0.12 U	0.45 J	< 1.5 U	< 0.028 U	< 0.3 U	< 0.18 U	< 0.032 U	< 0.23 U	< 0.083 U	< 0.032 U	< 0.028 U	< 0.1 U	< 0.15 U	< 0.07 U	< 0.31 U	< 0.18 U	< 0.19 U	< 0.25 U	< 0.21 U
SSHS-B575A	SSHS-B575A	9/19/2016	180-58899-1	< 0.015 U	< 0.016 U	< 0.082 U	< 0.016 U	< 0.092 U	< 0.043 U	< 0.15 U	< 0.015 U	< 0.014 U	< 0.016 U	< 0.056 U	< 0.016 U	< 0.06 U	< 0.026 U	< 0.02 U	2.1	< 0.065 U	0.74 J	< 1.2 U	< 0.016 U	< 0.091 U	< 0.078 U	< 0.016 U	< 0.17 U	< 0.052 U	< 0.014 U	< 0.016 U	< 0.064 U	< 0.12 U	< 0.034 U	< 0.15 U	< 0.088 U	< 0.079 U	< 0.13 U	< 0.21 U
SSHS-B575B	SSHS-B575B	9/19/2016	180-58899-1	< 0.014 U	< 0.014 U	< 0.076 U	< 0.015 U	< 0.085 U	< 0.04 U	< 0.14 U	0.13 J	< 0.013 U	0.29	0.29	0.21	< 0.055 U	< 0.024 U	< 0.019 U	1.8 J	< 0.06 U	0.53 J	< 1.1 U	< 0.015 U	< 0.084 U	< 0.072 U	< 0.014 U	< 0.16 U	< 0.048 U	0.29	0.26	< 0.059 U	< 0.11 U	< 0.032 U	< 0.14 U	< 0.081 U	< 0.073 U	< 0.12 U	< 0.2 U
SSHS-B575C	PS-FD-54	9/19/2016	180-58899-1	< 0.014 U	< 0.015 U	< 0.079 U	< 0.015 U	< 0.088 U	< 0.041 U	< 0.15 U	< 0.015 U	< 0.013 U	< 0.016 U	< 0.054 U	< 0.015 U	< 0.058 U	< 0.025 U	< 0.02 U	< 1.2 U	< 0.063 U	< 0.14 U	< 1.2 U	< 0.016 U	< 0.088 U	< 0.075 U	< 0.015 U	< 0.16 U	< 0.05 U	< 0.014 U	< 0.015 U	< 0.061 U	< 0.11 U	< 0.033 U	< 0.14 U	< 0.084 U	< 0.076 U	< 0.12 U	< 0.2 U
SSHS-B575C	SSHS-B575C	9/21/2016	180-58975-1	< 0.014 U	< 0.015 U	< 0.078 U	0.032 J	< 0.087 U	< 0.041 U	< 0.15 U	0.073 J	0.057 J	0.079 J	0.096 J	0.091 J	< 0.057 U	< 0.025 U	< 0.019 U	9.1	< 0.062 U	< 0.14 U	< 1.2 U	< 0.015 U	< 0.087 U	< 0.074 U	< 0.015 U	< 0.16 U	< 0.049 U	0.097 J	0.093 J	< 0.06 U	< 0.11 U	< 0.033 U	< 0.14 U	< 0.084 U	< 0.075 U	< 0.12 U	< 0.2 U
SSHS-B99	SSHS-99-GW-17-21	8/13/2014	180-35776-2	< 0.014 U	< 0.014 U	< 0.076 U	< 0.015 U	< 0.085 U	< 0.04 U	< 0.14 U	6.1	0.87 J	< 0.015 UJ	< 0.052 UJ	0.45 J	< 0.055 U	< 0.024 U	< 0.019 U	< 1.2 U	< 0.06 U	< 0.14 U	< 1.1 U	< 0.015 U	< 0.084 U	< 0.072 U	< 0.014 U	< 0.16 U	< 0.048 U	7.9	0.32 J	< 0.059 U	< 0.11 U	< 0.032 U	< 0.14 U	< 0.081 U	< 0.073 U	< 0.12 U	< 0.2 UJ
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	7/1/2021	180-123971-1	0.077 J	< 0.063 U	< 0.06 U	< 0.047 UJ	< 0.61 UJ	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 UJ	< 0.038 UJ	< 0.056 UJ	8.2 J	< 0.061 UJ	0.57 J	1 J	< 0.049 UJ	< 0.042 R	< 0.059 UJ	< 0.057 U	< 0.062 UJ	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 R	< 0.049 UJ	< 0.55 UJ	< 0.039 R	< 0.054 UJ	6.1	< 0.66 U
SSHS-RI-B3857	SSHS-RI-B3857 TEMP	4/9/2021	180-119810-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.2	< 0.66 U
SSHS-RI-B3860I	DUP-GW-02	4/15/2021	180-120162-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	2.5	< 0.69 U
SSHS-RI-B3860I	SSHS-RI-B3860I TEMP	4/15/2021	180-120162-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	1.9	< 0.69 U
SSHS-RI-B3864I	SSHS-RI-B3864I TEMP	4/13/2021	180-119930-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	< 0.71 U	< 0.66 U
SSHS-RI-B3865I	SSHS-RI-B3865I TEMP	4/9/2021	180-119810-1	< 0.063 U	< 0.063 UJ	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 UJ	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 UJ	< 6 U	< 0.061 UJ	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 UJ	< 0.059 U	< 0.057 UJ	< 0.062 UJ	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 R	< 0.049 UJ	< 0.55 U	< 0.039 UJ	< 0.054 U	0.77 J	< 0.66 U
SSHS-RI-B3865S	TEMP	4/9/2021	180-119810-1	< 0.063 U	< 0.063 U	< 0.06 U	0.28	< 0.61 U	< 0.057 U	< 0.11 U	0.19	< 0.051 U	0.14 J	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	0.61	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	0.82 J	< 0.66 U
SSHS-RI-B3867	SSHS-RI-B3867 TEMP	4/6/2021	180-119589-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	0.2 J	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	0.54 J	0.61 J	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	1.6	< 0.69 U
SSHS-RI-B3874	SSHS-RI-B3874 TEMP	4/7/2021	180-119649-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	0.11 J	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	0.49 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.6	< 0.66 U
SSHS-RI-B3877I	SSHS-RI-B3877I TEMP	4/14/2021	180-120029-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.5	< 0.66 U
SSHS-RI-B3877S	SSHS-RI-B3877S TEMP	4/14/2021	180-120029-1	0.28	< 0.063 U	< 0.06 U	0.095 J	< 0.61 U	< 0.057 U	< 0.11 U	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	< 6 U	< 0.061 U	< 0.44 U	< 0.45 U	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	1.1	< 0.66 U
SSHS-RI-B3882	SSHS-RI-B3882-TEMP	5/14/2021	180-121703-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	3.2	< 0.74 U
SSHS-RI-B3886	DUP-GW-01	5/19/2021	180-121897-1	< 0.068 U	< 0.068 U	0.071 J	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	13 J	< 0.066 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	1.8	< 0.71 U
SSHS-RI-B3886	SSHS-RI-B3886-TEMP	5/19/2021	180-121897-1	< 0.068 U	< 0.068 U	< 0.065 UJ	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	22 J	< 0.066 U	< 0.48 U	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	1.9	< 0.71 U
SSHS-RI-B3907I	SSHS-RI-B3907I-TEMP	5/11/2021	180-121472-1	< 0.068 U	< 0.068 U	0.096 J	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	< 6.5 U	< 0.066 U	0.53 J	< 0.49 U	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	< 0.77 U	< 0.71 U
SSHS-RI-B3907S	SSHS-RI-B3907S-TEMP	5/11/2021	180-121472-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	< 0.12 U	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 U	< 0.063 U	< 6.8 U	< 0.068 U	0.55 J	< 0.51 U	< 0.055 U	< 0.048 U	< 0.066 U	< 0.064 U	< 0.07 U	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 U	< 0.055 U	< 0.62 U	< 0.045 U	< 0.061 U	< 0.81 U	< 0.74 U
SSHS-RI-B3914	SSHS-RI-B3914-TEMP	5/13/2021	180-121702-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	3.3 J+	< 0.69 U
SSHS-RI-B3915	SSHS-RI-B3915-TEMP	5/12/2021	180-121546-1	< 0.065 U	< 0.065 U	< 0.062 U	< 0.049 U	< 0.63 U	< 0.059 U	< 0.11 U	< 0.075 U	< 0.053 U	< 0.097 U	< 0.088 U	< 0.069 U	< 0.067 U	< 0.04 U	< 0.058 U	< 6.2 U	< 0.063 U	< 0.46 U	< 0.47 U	< 0.051 U	< 0.044 U	< 0.061 U	< 0.059 U	< 0.064 U	< 0.061 U	< 0.081 U	< 0.072 U	< 0.073 U	< 0.58 U	< 0.051 U	< 0.57 U	< 0.041 U	< 0.056 U	2.6 J+	< 0.69 U
SSHS-RI-B4150I	SSHS-RI-B4150I-TEMP	7/23/2021	180-124918-1	< 0.074 U	< 0.074 U	0.83 J	0.14 J	< 0.72 U	0.47 J	< 0.13 U	0.25	0.15 J	0.16 J	< 0.1 U	0.11 J	< 0.076 U	< 0.045 U	< 0.066 U	< 7.1 U	< 0.072 U	< 0.53 U	1.2 J	0.17 J	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	0.32	< 0.082 U	1.4	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	6.9	< 0.78 U
SSHS-RI-B4150S	SSHS-RI-B4150S-TEMP	7/26/2021	180-124974-1	< 0.074 U	< 0.074 U	< 0.07 U	< 0.056 U	< 0.72 U	< 0.067 U	< 0.13 U	< 0.085 U	< 0.06 U	< 0.11 U	< 0.1 U	< 0.078 U	< 0.076 U	< 0.045 U	< 0.066 U	7.7 J	< 0.072 U	< 0.53 U	< 0.53 U	< 0.058 U	< 0.05 U	< 0.069 U	< 0.067 U	< 0.073 U	< 0.069 U	< 0.092 U	< 0.082 U	< 0.083 U	< 0.66 U	< 0.058 U	< 0.64 U	< 0.047 U	< 0.064 U	9.3	< 0.78 U
SSHS-RI-B4152I	DUP-01	7/28/2021	180-125087-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	< 0.093 U	< 0.063 U	< 0.044 U	< 0.081 U	< 0.073 U	< 0.058 U	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	< 0.39 U	1.4 J	< 0.043 U	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	< 0.068 U	< 0.06 U	< 0.061 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.034 U	< 0.047 U	4.9	< 0.57 U
SSHS-RI-B4152S	SSHS-RI-B4152S-TEMP	7/28/2021	180-125087-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	7.6 J	< 0.066 U	0.51 J	1.9 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	6.4	< 0.71 U
SSHS-RI-B4153I	SSHS-RI-B4153I-TEMP	7/28/2021	180-125087-1	< 0.063 U	< 0.063 U	< 0.06 U	< 0.047 U	< 0.61 U	< 0.057 U	0.13 J	< 0.072 U	< 0.051 U	< 0.093 U	< 0.085 U	< 0.066 U	< 0.064 U	< 0.038 U	< 0.056 U	7.1 J	< 0.061 U	0.49 J	2.7 J	< 0.049 U	< 0.042 U	< 0.059 U	< 0.057 U	< 0.062 U	< 0.059 U	< 0.078 U	< 0.069 U	< 0.07 U	< 0.56 U	< 0.049 U	< 0.55 U	< 0.039 U	< 0.054 U	10	< 0.66 U
SSHS-RI-B4153S	SSHS-RI-B4153S-TEMP	7/27/2021	180-125052-1	< 0.054 U	< 0.054 U	< 0.052 U	< 0.041 U	< 0.53 U	< 0.049 U	0.15 J	0.61	0.48	0.82	0.77	0.61	< 0.056 U	< 0.033 U	< 0.048 U	< 5.2 U	< 0.053 U	1.3	< 0.39 U	0.05 J	< 0.037 U	< 0.051 U	< 0.049 U	< 0.053 U	< 0.051 U	0.78	0.77	< 0.061 U	< 0.49 U	< 0.043 U	< 0.47 U	< 0.034 U	< 0.047 U	3.3	1.4
SSHS-RI-B4154I	SSHS-RI-B4154I-TEMP	7/27/2021	180-125052-1	< 0.071 U	< 0.071 U	< 0.067 U	< 0.053 U	< 0.69 U	< 0.064 U	0.16 J	< 0.082 U	< 0.058 U	< 0.11 U	< 0.096 U	< 0.075 U	< 0.073 U	< 0.043 UJ	< 0.063 U	< 6.8 U	< 0.068 U	< 0.5 U	< 0.51 U	< 0.055 U	< 0.048 UJ	< 0.066 U	< 0.064 UJ	< 0.07 UJ	< 0.066 U	< 0.088 U	< 0.078 U	< 0.079 U	< 0.63 UJ	< 0.055 U	< 0.62 U	< 0.045 UJ	< 0.061 U	5.1	< 0.74 U
SSHS-RI-B4154S	SSHS-RI-B4154S-TEMP	7/26/2021	180-124974-1	< 0.068 U	< 0.068 U	< 0.065 U	< 0.051 U	< 0.66 U	< 0.061 U	< 0.12 U	< 0.078 U	< 0.055 U	< 0.1 U	< 0.092 U	< 0.072 U	< 0.07 U	< 0.042 U	< 0.06 U	6.5 J	< 0.066 U	1	1.3 J	< 0.053 U	< 0.046 U	< 0.064 U	< 0.061 U	< 0.067 U	< 0.064 U	< 0.084 U	< 0.075 U	< 0.076 U	< 0.61 U	< 0.053 U	< 0.59 U	< 0.043 U	< 0.058 U	6	< 0.71 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	7/29/2021	180-125127-1	< 0.06 U	0.065 J	< 0.057 U	0.045 J	< 0.59 U	< 0.055 U	< 0.1 U	0.11 J	0.072 J	< 0.09 U	< 0.081 U	< 0.064 U	< 0.062 U	< 0.037 U	< 0.054 U	11	< 0.058 U	0.6 J	1.4 J	< 0.047 U	< 0.041 U	< 0.056 U	< 0.055 U	< 0.059 U	< 0.056 U	0.13 J	< 0.067 U	< 0.068 U	< 0.54 U	< 0.047 U	< 0.53 U	< 0.038 U	< 0.052 U	6.7	< 0.63 U

Notes
SVOCs = Semivolatile Organic Compounds
ug/l = micrograms per liter
[1] - DEHP is a common cross-contaminant and is not a Site COPC.The Wisconsin Department of Natural Resources recognizes DEHP as a common cross-contaminant due to its widespread use in plastics such as polyvinyl chloride (Wisconsin Department of Natural Resources 2002). At the Site, monitoring well casings are constructed of polyvinyl chloride and low-density polyethylene tubing is used for low-flow sample collection, both of which are potential sources of DEHP contamination. Historically, detections of DEHP at the Site have been infrequent and sporadic, with
* = LCS or LCSD is outside acceptance limits
*3 = ISTD response or retention time outside acceptable limits
B = Compound detected in method blank
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
I = Value is EMPC (estimated maximum possible concentration)
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab method used: 8015D - DRO
Lab method used: 8270D/SW8270D/8270D_LL/SW8270E/8270E-LL - SVOCs
Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

DRAFT

TABLE 5-10
Groundwater Results - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol	2,4-Dinitrotoluene	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	TPH-DRO	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	1	5	50	50	0.04	0.5	5	5	0.002		50			10	5	5	5	0.4					50	1	50	1	50					
Location	Sample Name	Sample Date	Lab Report																																		
SSHS-B26-A	SSHS-B26-A-GW-18-22	8/14/2014	180-35818-2	< 0.21 U	< 0.077 U	< 0.59 U	< 0.052 U	1.2	< 0.021 U	< 0.018 U	< 0.016 U	< 0.05 R	< 0.06 U	< 0.019 U	< 0.083 UJ	< 0.062 U	< 0.012 UJ	< 0.087 U	< 0.013 U	< 0.34 U	< 0.31 U	< 0.17 U	< 0.081 U	< 0.16 U	< 0.62 U	< 0.03 U	< 0.082 U	< 0.064 U	< 0.041 U	< 0.056 U	3.5 J	< 0.063 U	< 0.13 U	-	< 0.15 U	< 0.17 U
SSHS-B2752	SSHS-B2752	4/25/2019	180-89520-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
SSHS-B29-A	SSHS-B29-A-GW-18-22	8/13/2014	180-35776-2	< 0.21 U	< 0.075 U	< 0.58 U	< 0.051 U	< 0.015 U	< 0.02 U	< 0.017 U	< 0.016 U	< 0.049 U	< 0.059 U	< 0.019 UJ	< 0.081 U	< 0.061 U	< 0.012 U	< 0.085 U	< 0.013 U	< 0.33 U	< 0.3 U	< 0.16 U	< 0.08 U	< 0.16 U	< 0.61 U	< 0.029 U	< 0.08 U	< 0.063 U	< 0.04 U	< 0.055 U	< 0.015 U	< 0.061 U	< 0.13 U	-	< 0.14 U	< 0.17 U
SSHS-B3200A	DUP-01	9/15/2019	180-95745-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.087 J	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-B3200A	SSHS-B3200a	9/15/2019	180-95745-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 UJ	< 0.058 U	< 0.072 UJ	< 0.52 UJ	< 0.065 UJ	< 0.089 U	< 0.31 UJ	< 0.056 U	< 0.065 UJ	< 0.39 UJ	< 0.061 UJ	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 UJ	< 0.064 UJ	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.07 J	< 0.51 UJ	< 0.056 U	< 0.054 UJ	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-B3203A	SSHS-3203a	9/13/2019	180-95715-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-B510	SSHS-B510	9/20/2016	180-58901-1	< 0.21 U	< 0.077 U	< 0.59 U	< 0.052 U	< 0.016 U	0.3	< 0.018 U	< 0.016 U	< 0.05 U	< 0.06 U	< 0.019 U	< 0.083 U	< 0.062 U	0.21	< 0.087 U	0.76	< 0.34 U	< 0.31 U	< 0.17 U	< 0.081 U	< 0.16 U	< 0.62 U	< 0.03 U	< 0.082 U	< 0.064 U	< 0.041 U	< 0.056 U	< 0.015 U	< 0.063 U	< 0.13 U	-	< 0.15 U	< 0.17 U
SSHS-B572A	SSHS-B572A	9/2/2016	180-58309-2	< 1.6 U	< 0.14 U	< 2.6 U	< 0.22 U	0.051 J	< 0.025 U	< 0.064 U	< 0.098 U	< 0.14 U	< 0.14 U	< 0.045 U	< 0.19 U	< 0.077 U	< 0.02 U	< 0.22 U	< 0.024 U	< 0.7 U	< 0.84 U	< 0.81 U	< 0.16 U	< 0.12 U	< 0.84 U	< 0.052 U	< 0.13 U	< 0.52 U	< 0.043 U	< 0.058 U	0.03 J	< 0.08 U	< 0.11 U	-	< 0.13 U	< 0.31 U
SSHS-B575A	SSHS-B575A	9/19/2016	180-58899-1	< 0.23 U	< 0.082 U	< 0.63 U	< 0.055 U	< 0.017 U	< 0.022 U	< 0.019 U	< 0.017 U	< 0.053 U	< 0.065 U	< 0.021 U	< 0.089 U	< 0.066 U	< 0.013 U	< 0.093 U	< 0.014 U	< 0.36 U	< 0.33 U	< 0.18 U	< 0.087 U	< 0.18 U	< 0.67 U	< 0.032 U	< 0.088 U	< 0.068 U	< 0.044 U	< 0.06 U	< 0.016 U	< 0.067 U	< 0.14 U	-	< 0.16 U	< 0.18 U
SSHS-B575B	SSHS-B575B	9/19/2016	180-58899-1	< 0.21 U	< 0.076 U	< 0.58 U	< 0.051 U	0.056 J	< 0.021 U	< 0.017 U	< 0.016 U	< 0.049 U	< 0.06 U	< 0.019 U	< 0.082 U	< 0.061 U	< 0.012 U	< 0.086 U	< 0.013 U	< 0.33 U	< 0.31 U	< 0.16 U	< 0.08 U	< 0.16 U	< 0.62 U	< 0.029 U	< 0.081 U	< 0.063 U	< 0.041 U	< 0.055 U	0.11 J	< 0.062 U	< 0.13 U	-	< 0.15 U	< 0.17 U
SSHS-B575C	PS-FD-54	9/19/2016	180-58899-1	< 0.22 U	< 0.079 U	< 0.61 U	< 0.053 U	< 0.016 U	< 0.021 U	< 0.018 U	< 0.016 U	< 0.051 U	< 0.062 U	< 0.02 U	< 0.085 U	< 0.064 U	< 0.012 U	< 0.089 U	< 0.014 U	< 0.35 U	< 0.32 U	< 0.17 U	< 0.083 U	< 0.17 U	< 0.64 U	< 0.03 U	< 0.084 U	< 0.066 U	< 0.042 U	< 0.058 U	< 0.016 U	< 0.064 U	< 0.13 U	-	< 0.15 U	< 0.17 U
SSHS-B575C	SSHS-B575C	9/21/2016	180-58975-1	< 0.22 U	< 0.078 U	< 0.6 U	< 0.053 U	0.028 J	0.027 J	< 0.018 U	< 0.016 U	< 0.051 R	< 0.062 U	0.08 J	< 0.085 U	< 0.063 U	< 0.012 U	< 0.088 U	< 0.014 U	< 0.34 U	< 0.32 U	< 0.17 U	< 0.083 U	< 0.17 U	< 0.63 U	< 0.03 U	< 0.084 U	< 0.065 U	< 0.042 U	< 0.057 U	0.041 J	< 0.064 U	< 0.13 U	-	< 0.15 U	< 0.17 U
SSHS-B99	SSHS-99-GW-17-21	8/13/2014	180-35776-2	< 0.21 U	< 0.076 U	< 0.58 U	< 0.051 U	< 0.015 U	< 0.021 U	< 0.017 U	< 0.016 U	< 0.049 U	< 0.06 U	0.28 J	< 0.082 U	< 0.061 U	< 0.012 U	< 0.086 U	< 0.013 U	< 0.33 U	< 0.31 U	< 0.16 U	< 0.08 U	< 0.16 U	< 0.62 U	< 0.029 U	< 0.081 U	< 0.063 U	< 0.041 U	< 0.055 U	< 0.015 U	< 0.062 U	< 0.13 U	-	< 0.15 U	< 0.17 U
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	7/1/2021	180-123971-1	< 1.4 UJ	< 0.058 UJ	< 1.5 UJ	< 0.049 UJ	< 0.058 U	0.19	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 UJ	< 0.052 UJ	< 0.06 U	< 0.36 UJ	< 0.057 U	< 0.53 UJ	< 0.064 UJ	< 0.056 UJ	< 0.48 UJ	< 0.059 UJ	< 0.14 UJ	< 0.068 UJ	< 0.11 UJ	< 0.81 UJ	< 0.053 UJ	< 0.47 UJ	< 0.052 U	< 0.05 U	< 0.043 UJ	300 J	< 0.059 UJ	< 0.065 UJ
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	4/9/2021	180-119810-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3860I TEMP	DUP-GW-02	4/15/2021	180-120162-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	4/15/2021	180-120162-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	4/13/2021	180-119930-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	4/9/2021	180-119810-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 UJ	< 0.066 UJ	< 0.48 UJ	< 0.06 UJ	< 0.082 U	< 0.29 UJ	< 0.052 U	< 0.06 UJ	< 0.36 U	< 0.057 UJ	< 0.53 U	< 0.064 UJ	< 0.056 UJ	< 0.48 U	< 0.059 UJ	< 0.14 U	< 0.068 UJ	< 0.11 UJ	< 0.81 U	0.085 J	< 0.47 UJ	< 0.052 U	< 0.05 UJ	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	4/9/2021	180-119810-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	1	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	4/6/2021	180-119589-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	4/7/2021	180-119649-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	4/14/2021	180-120029-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	< 0.053 U	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	4/14/2021	180-120029-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	< 0.052 U	< 0.06 U	< 0.36 U	< 0.057 U	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.075 J	< 0.47 U	0.052 J	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	5/14/2021	180-121703-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.072 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
SSHS-RI-B3886-TEMP	DUP-GW-01	5/19/2021	180-121897-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	5/19/2021	180-121897-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	< 0.057 U	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	5/11/2021	180-121472-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.063 J	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	5/11/2021	180-121472-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 U	< 0.54 U	< 0.067 U	< 0.092 U	< 0.33 U	< 0.059 U	< 0.067 U	< 0.4 U	< 0.064 U	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 U	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.07 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	5/13/2021	180-121702-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	0.08 J	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	5/12/2021	180-121546-1	< 1.5 U	< 0.06 U	< 1.5 U	< 0.051 U	< 0.06 U	< 0.069 U	< 0.056 U	< 0.069 U	< 0.5 U	< 0.062 U	< 0.085 U	< 0.3 U	< 0.054 U	< 0.062 U	< 0.37 U	< 0.059 U	< 0.55 U	< 0.067 U	< 0.058 U	< 0.5 U	< 0.061 U	< 0.14 U	< 0.071 U	< 0.12 U	< 0.85 U	< 0.055 U	< 0.49 U	< 0.054 U	< 0.052 U	< 0.045 U	-	< 0.061 U	< 0.068 U
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	7/23/2021	180-124918-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	0.31	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	6.6	< 0.42 U	6.5	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	1.9	< 0.55 U	0.35	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	7/26/2021	180-124974-1	< 1.7 U	< 0.068 U	< 1.7 U	< 0.058 U	< 0.068 U	< 0.078 U	< 0.064 U	< 0.078 U	< 0.56 U	< 0.07 U	< 0.097 U	< 0.34 U	< 0.061 U	< 0.07 U	< 0.42 U	< 0.067 U	< 0.62 U	< 0.076 U	< 0.066 U	< 0.57 U	< 0.069 U	< 0.16 U	< 0.081 U	< 0.14 U	< 0.96 U	< 0.063 U	< 0.55 U	< 0.061 U	< 0.059 U	< 0.051 U	-	< 0.069 U	< 0.077 U
SSHS-RI-B4152I-TEMP	DUP-01	7/28/2021	180-125087-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	< 0.071 U	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	0.084 J	< 0.41 U	< 0.045 U	< 0.043 U	< 0.038 U	-	< 0.051 U	< 0.057 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	7/28/2021	180-125087-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	< 0.05 U	< 0.058 U	< 0.047 U	< 0.058 UJ	< 0.41 R	< 0.052 UJ	< 0.071 U	< 0.25 UJ	< 0.045 UJ	< 0.052 UJ	< 0.31 UJ	< 0.049 UJ	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 UJ	< 0.051 UJ	< 0.12 U	< 0.059 UJ	< 0.099 U	< 0.71 U	0.13 J	< 0.41 UJ	< 0.045 U	< 0.043 UJ	< 0.038 U	-	< 0.051 U	< 0.057 U
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	7/29/2021	180-125127-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.17 J	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	7/28/2021	180-125087-1	< 1.4 U	< 0.058 U	< 1.5 U	< 0.049 U	< 0.058 U	< 0.066 U	< 0.054 U	< 0.066 U	< 0.48 U	< 0.06 U	< 0.082 U	< 0.29 U	0.074 J	< 0.06 U	< 0.36 U	0.063 J	< 0.53 U	< 0.064 U	< 0.056 U	< 0.48 U	< 0.059 U	< 0.14 U	< 0.068 U	< 0.11 U	< 0.81 U	0.14 J	< 0.47 U	< 0.052 U	< 0.05 U	< 0.043 U	-	< 0.059 U	< 0.065 U
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	7/27/2021	180-125052-1	< 1.2 U	< 0.05 U	< 1.3 U	< 0.043 U	0.067 J	< 0.058 U	< 0.047 U	< 0.058 U	< 0.41 U	< 0.052 U	0.83	< 0.25 U	< 0.045 U	< 0.052 U	< 0.31 U	< 0.049 U	< 0.46 U	< 0.056 U	< 0.048 U	< 0.42 U	< 0.051 U	< 0.12 U	< 0.059 U	< 0.099 U	< 0.71 U	0.14 J	< 0.41 U	0.087 J	< 0.043 U	< 0.038 U	-	< 0.051 U	< 0.057 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	7/27/2021	180-125052-1	< 1.6 U	< 0.065 U	< 1.7 U	< 0.055 U	< 0.065 U	< 0.075 U	< 0.061 U	< 0.075 UJ	< 0.54 UJ	< 0.067 UJ	< 0.092 U	< 0.33 UJ	< 0.059 U	< 0.067 UJ	< 0.4 U	< 0.064 UJ	< 0.6 U	< 0.073 U	< 0.063 U	< 0.54 U	< 0.066 UJ	< 0.15 U	< 0.077 U	< 0.13 U	< 0.92 U	0.12 J	< 0.53 U	< 0.059 U	< 0.057 U	< 0.049 U	-	< 0.066 U	< 0.074 U
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	7/26/2021	180-124974-1	< 1.5 U	< 0.063 U	< 1.6 U	< 0.053 U	< 0.063 U	< 0.072 U	< 0.058 U	< 0.072 U	< 0.52 U	< 0.065 U	< 0.089 U	< 0.31 U	< 0.056 U	< 0.065 U	< 0.39 U	< 0.061 U	< 0.57 U	< 0.07 U	< 0.06 U	< 0.52 U	< 0.064 U	< 0.15 U	< 0.074 U	< 0.12 U	< 0.88 U	0.14 J	< 0.51 U	< 0.056 U	< 0.054 U	< 0.047 U	-	< 0.064 U	< 0.071 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	7/29/2021	180-125127-1	< 1.4 U	< 0.056 U	< 1.4 U	< 0.047 U	0.28	< 0.064 U	< 0.052 U	< 0.064 U	< 0.46 U	< 0.057 U	< 0.079 U	< 0.28 U	0.072 J	< 0.057 U	< 0.34 U	< 0.055 U	< 0.51 U	< 0.062 U	< 0.054 U	< 0.46 U	< 0.056 U	< 0.13 U	< 0.066 U	< 0.11 U	< 0.78 U	0.52	< 0.45 U	0.33	< 0.048 U	< 0.042 U	-	< 0.056 U	< 0.063 U

Notes
SVOCs = Semivolatile Organic Compounds
ug/l = micrograms per liter
[1] - DEHP is a common cross-contaminant and is not a Site COPC.The Wisconsin Department of Natural Resources recognizes DEHP as a common cross-contaminant due to its widespread use in plastics such as polyvinyl chloride (Wisconsin Department of Natural Resources 2002). At the Site, monitoring well casings are constructed of polyvinyl chloride and low-density polyethylene tubing is used for low-flow sample collection, both of which are potential sources of DEHP contamination. Historically, detections of DEHP at the Site have been infrequent and sporadic, with
* = LCS or LCSD is outside acceptance limits
*3 = ISTD response or retention time outside acceptable limits
B = Compound detected in method blank
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
I = Value is EMPC (estimated maximum possible concentration)
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab method used: 8015D - DRO
Lab method used: 8270D/SW8270D/8270D_LL/SW8270E/8270E-LL - SVOCs
Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1.2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-1	MW-1	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-1	MW-1	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-1	MW-1	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-1	MW-1	7/14/2021	180-124487-1	52	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-1	SSHS-MW-1-04112024	4/11/2024	1801722801	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-10	MW-10	2/24/2021	180-117542-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-10	MW-10	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-100I	SSHS-MW-100I-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-100I	SSHS-MW-100I-04082024	4/8/2024	1801720411	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.5	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-100S	SSHS-DUP-02-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-100S	SSHS-MW-100S-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-100S	SSHS-MW-100S-04082024	4/8/2024	1801720411	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 UT	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-101S	SSHS-MW-101S-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-101S	SSHS-MW-101S-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-102I	SSHS-MW-102I-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-102I	SSHS-MW-102I-04222024	4/22/2024	1801730541	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-102S	SSHS-MW-102S-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-102S	SSHS-MW-102S-04222024	4/22/2024	1801730541	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-103I	SSHS-MW-103I-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-103I	SSHS-MW-103I-04162024	4/16/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-103S	SSHS-MW-103S-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-103S	SSHS-MW-103S-04162024	4/16/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-104I	SSHS-DUP-03-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-104I	SSHS-MW-104I-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-104I	SSHS-MW-104I-04162024	4/16/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-104S	SSHS-MW-104S-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-104S	SSHS-MW-104S-04162024	4/16/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-105I	SSHS-MW-105I-04172024	4/17/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-105S	SSHS-MW-105S-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-105S	SSHS-MW-105S-04252024	4/25/2024	1801731401	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-106	SSHS-MW-106-09122023	9/12/2023	1801624601	35	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653531	6.9	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.93 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682891	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-106	SSHS-MW-106-04092024	4/9/2024	1801721201	3.5 J	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-107I	SSHS-MW-107I-07102025	7/11/2025	1801930781	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	0.55 J	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-107S	SSHS-MW-107S-07102025	7/11/2025	1801930781	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-107S	SSHS-MW-107S-11132025	11/13/2025	1801985411	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-108	SSHS-DUP-01-07112025	7/11/2025	1801931281	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-108	SSHS-MW-108-07112025	7/11/2025	1801931281	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 UT	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-108	SSHS-DUP-01-11132025	11/13/2025	1801985411	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-108	SSHS-MW-108-11132025	11/13/2025	1801985411	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 UT	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 UT	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 UT	< 0.30 U	< 0.30 U	< 0.70 UT	< 0.30 U	< 0.20 U
MW-11D	MW-11D	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-11D	MW-11D	9/24/2006	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-11D	MW-11D-GW	11/1/2018	180-83607-1	< 5.4 U	< 0.13 U	< 0.14 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.28 U	< 0.26 U	< 0.14 U	< 0.39 U	< 0.83 U	< 0.13 U	< 0.2 U	< 0.24 U	< 0.91 U	< 2.6 U	< 0.12 U	< 0.35 U	< 0.15 U	< 0.15 U	< 0.16 U	< 0.16 U	< 0.17 U	< 0.21 U	< 0.19 U	< 0.33 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.61 U
MW-11D	MW-11D	2/23/2021	180-117459-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-11D	MW-11D	4/30/2021	180-120955-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-11I	SSHS-MW-11I-07142025	7/14/2025	1801931281	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-11I	SSHS-MW-11I-11132025	11/13/2025	1801985411	< 0.70 U	< 0.30 U	< 0.20 U	< 0.20 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	0.62 J	< 0.55 U	< 1.0 U	< 0.30 U	< 0.30 U	< 0.20 U	< 0.30 U	< 0.20 U	< 0.68 U	< 0.30 U	-	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.70 U	< 0.30 U	< 0.20 U
MW-11S	MW-11S	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-11S	FD-1	11/1/2018	180-83607-1	< 5.4 U	< 0.13 U	< 0.14 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.28 U	< 0.26 U	< 0.14 U	< 0.39 U	< 0.83 U	0.18 J	< 0.2 U	< 0.24 U	< 0.91 U	< 2.6 U	< 0.12 U	< 0.35 U	< 0.15 U	< 0.15 U	< 0.16 U	< 0.16 U	< 0.17 U	< 0.21 U	< 0.19 U	< 0.33 U	0.25 J	< 0.19 U	< 0.15 U	< 0.61 U
MW-11S	MW-11S-GW	11/1/2018	180-83607-1	< 5.4 U	< 0.13 U	< 0.14 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.28 U	< 0.26 U	< 0.14 U	< 0.39 U	< 0.83 U	0.15 J	< 0.2 U	< 0.24 U	< 0.91 U	< 2.6 U	< 0.12 U	< 0.35 U	< 0.15 U	< 0.15 U	< 0.16 U	< 0.16 U	< 0.17 U	< 0.21 U	< 0.19 U	< 0.33 U	0.19 J	< 0.19 U	< 0.15 U	< 0.61 U
MW-11S	MW-11S	7/25/2019	180-93333-1	< 3.4 UJ	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-11S	DUP-01	7/25/2019	180-93333-1	5.7 J	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-11S	MW-11S	2/23/2021	180-117459-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-11S	MW-11S	4/30/2021	180-120955-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-12	MW-12	12/19/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 J	-	-	-
MW-12	MW-12	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	9	-	-	-
MW-12	MW-12	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	7/23/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	5/20/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-12	MW-12	9/24/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-1	MW-1	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-1	MW-1	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-1	MW-1	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-1	MW-1	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	6.5	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	-	< 0.41 U	< 0.89 U
MW-1	SSHS-MW-1-04112024	4/11/2024	1801722801	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-10	MW-10	2/24/2021	180-117542-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-10	MW-10	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-100I	SSHS-MW-100I-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-100I	SSHS-MW-100I-04082024	4/8/2024	1801720411	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-100S	SSHS-DUP-02-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-100S	SSHS-MW-100S-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-100S	SSHS-MW-100S-04082024	4/8/2024	1801720411	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 UT	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UT	< 0.77 UT	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-101S	SSHS-MW-101S-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-101S	SSHS-MW-101S-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-102I	SSHS-MW-102I-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 UJ	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-102I	SSHS-MW-102I-04222024	4/22/2024	1801730541	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-102S	SSHS-MW-102S-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-102S	SSHS-MW-102S-04222024	4/22/2024	1801730541	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-103I	SSHS-MW-103I-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-103I	SSHS-MW-103I-04162024	4/16/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-103S	SSHS-MW-103S-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-103S	SSHS-MW-103S-04162024	4/16/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-104I	SSHS-DUP-03-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-104I	SSHS-MW-104I-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-104I	SSHS-MW-104I-04162024	4/16/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-104S	SSHS-MW-104S-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-104S	SSHS-MW-104S-04162024	4/16/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-105I	SSHS-MW-105I-04172024	4/17/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-105S	SSHS-MW-105S-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-105S	SSHS-MW-105S-04252024	4/25/2024	1801731401	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-106	SSHS-MW-106-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653531	< 0.58 U	< 0.51 U	1.0	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.69 J	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.60 U	< 0.45 U	4.0 J+	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682891	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-106	SSHS-MW-106-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-107I	SSHS-MW-107I-07102025	7/11/2025	1801930781	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	1.3	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-107S	SSHS-MW-107S-07102025	7/11/2025	1801930781	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	0.48 J	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-107S	SSHS-MW-107S-11132025	11/13/2025	1801985411	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	0.76 J	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-108	SSHS-DUP-01-07112025	7/11/2025	1801931281	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-108	SSHS-MW-108-07112025	7/11/2025	1801931281	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-108	SSHS-DUP-01-11132025	11/13/2025	1801985411	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-108	SSHS-MW-108-11132025	11/13/2025	1801985411	< 0.20 U	< 0.40 U	< 0.30 UT	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 UT	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 UT	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-11D	MW-11D	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-11D	MW-11D	9/24/2006	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-11D	MW-11D-GW	11/1/2018	180-83607-1	< 0.67 U	< 0.11 U	< 0.41 U	< 0.54 U	< 0.09 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.42 U	< 0.07 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.14 U	< 0.54 U	< 0.26 U	< 0.24 U	< 0.09 U	< 0.1 U	< 0.45 U	< 0.2 U	< 0.08 U	< 0.09 U	< 0.15 U
MW-11D	MW-11D	2/23/2021	180-117459-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-11D	MW-11D	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-11I	SSHS-MW-11I-07142025	7/14/2025	1801931281	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	1.5	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-11I	SSHS-MW-11I-11132025	11/13/2025	1801985411	< 0.20 U	< 0.40 U	< 0.30 U	< 0.85 U	< 0.30 U	< 0.30 U	< 0.50 U	< 1.0 U	< 0.50 U	< 0.20 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.30 U	< 0.40 U	< 0.30 U	< 0.30 U	< 0.30 U	7.0	< 0.30 U	< 0.30 U	< 2.0 U	< 0.40 U	< 0.40 U
MW-11S	MW-11S	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-11S	FD-1	11/1/2018	180-83607-1	< 0.67 U	< 0.11 U	< 0.41 U	< 0.54 U	< 0.09 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.42 U	< 0.07 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.14 U	< 0.54 U	< 0.26 U	< 0.24 U	< 0.09 U	0.13 J	< 0.45 U	< 0.2 U	< 0.08 U	< 0.09 U	< 0.15 U
MW-11S	MW-11S-GW	11/1/2018	180-83607-1	< 0.67 U	< 0.11 U	< 0.41 U	< 0.54 U	< 0.09 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.42 U	< 0.07 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.14 U	< 0.54 U	< 0.26 U	< 0.24 U	< 0.09 U	0.11 J	< 0.45 U	< 0.2 U	< 0.08 U	< 0.09 U	< 0.15 U
MW-11S	MW-11S	7/25/2019	180-93333-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-11S	DUP-01	7/25/2019	180-93333-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-11S	MW-11S	2/23/2021	180-117459-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-11S	MW-11S	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-12	MW-12	12/19/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-12	MW-12	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	9 J	-	-	-	-	-
MW-12	MW-12	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	2	-	ND	-	-	-
MW-12	MW-12	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-12	MW-12	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-12	MW-12	7/23/2002	-	-	-	30	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	4.2 J	-	ND	-	-	-
MW-12	MW-12	5/20/2003	-	-	-	58	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-12	MW-12	5/20/2003	-	< 5 U	< 5 U	58	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-12	MW-12	9/24/2003	-	-	-	39	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-12	MW-12	9/24/2003	-	-	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-12	MW-12	6/1/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	12/30/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	6/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	12/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	0.82	-	-	-
MW-12	MW-12	7/12/2007	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-12	MW-12	2/21/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-12	MW-12	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-13	DUP-1	8/20/2014	180-36053-1	< 2.5 U	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
MW-13	MW-13	8/20/2014	180-36053-1	< 2.5 U	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
MW-13	DUP-02	2/21/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-13	MW-13	2/21/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-13	MW-13	7/15/2021	180-124580-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 UJ	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 UJ	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 UJ	< 0.66 U	< 0.59 U
MW-15D	MW-15D	4/29/2003	-	440	< 5 U	-	< 5 U	< 5 U	-	31 J	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-15D	MW-15D	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-15D	MW-15D	9/24/2006	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-15S	MW-15S	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-17	MW17	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-17	MW17	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-17	MW-17	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-2	MW-2	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-2	MW-2	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-2	MW-2	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-2	MW-2	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-20	MW20	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW-20	2/23/2021	180-117459-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-20	MW-20	7/15/2021	180-124580-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-22	MW-22	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-22	MW-22	2/23/2021	180-117459-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-22	MW-22	7/15/2021	180-124580-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-26	MW-26	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-26	MW-26	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-3	MW-3	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-3	MW-3	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-3	MW-3	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-3	MW-3	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-3	DUP-4	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-30	MW-30	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	631.8	-	-	-
MW-30	MW-30	6/19/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	940	-	-	-
MW-30	MW-30	7/23/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	670	-	-	-
MW-30	MW-30-D20	5/20/2003	-	< 20 U	< 100 U	-	< 100 U	< 100 U	-	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	-	-	< 100 U	-	-	-	-	-	-	< 100 U	< 100 U	< 100 U	-	740	< 100 U	< 100 U	< 100 U
MW-30	MW-30	5/20/2003	-	97	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	740	-	-	-
MW-30	MW-30	5/20/2003	-	97	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	6.3	-	-	6.8	< 5 U	< 5 U
MW-30	MW-30-D20	9/24/2003	-	< 400 U	< 100 U	-	< 100 U	< 100 U	-	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	-	-	< 100 U	-	-	-	-	-	-	< 100 U	< 100 U	< 100 U	-	360	< 100 U	< 100 U	< 100 U
MW-30	MW-30	9/24/2003	-	76	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	360	-	-	-
MW-30	MW-30	9/24/2003	-	76	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U
MW-30	MW-30	6/1/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	320	-	-	-
MW-30	MW-30	12/30/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	230	-	-	-
MW-30	MW-30	6/28/2005	-	84	-	-	-	-	-	-	-	-	-	-	-	-	-	-	20	-	-	-	-	-	-	-	-	-	-	200	-	-	-
MW-30	MW-30	12/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	120	-	-	-	-	-	-	-	-	-	-	520	-	-	-
MW-30	MW-30	5/25/2006	-	30	-	-	-	-	-	-	-	-	-	-	-	-	-	-	30	-	-	-	-	-	-	-	-	-	-	500	-	-	-
MW-30	MW-30	7/12/2007	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	550	-	-	-
MW-30	MW-30	8/21/2014	180-36053-1	< 31 U	< 1.3 U	< 2.3 U	< 1.6 U	< 2.4 U	< 3.9 U	< 2.7 U	< 1.7 U	< 1.7 U	< 1.7 U	< 2.7 U	< 2.1 U	< 3.5 U	< 3.2 U	< 1.8 U	< 1.6 U	< 2.3 U	< 2.4 U	< 1.9 U	< 1.3 U	< 2.6 U	-	< 1.5 U	< 2.6 U	< 3.7 U	-	350	< 2.1 U	< 1.2 U	< 2.3 U
MW-30	MW-30	8/21/2014	180-36053-1	14 J	< 0.53 U	< 0.9 U	< 0.65 U	< 0.96 U	< 1.6 U	< 1.1 U	< 0.68 U	< 0.68 U	< 0.68 U	< 1.1 U	< 0.85 U	< 1.4 U	< 1.3 U	< 0.7 U	< 0.63 U	< 0.9 U	< 0.96 U	< 0.76 U	< 0.53 U	< 1 U	-	< 0.58 U	< 1.1 U	< 1.5 U	-	-	1.1 J	< 0.47 U	< 0.93 U
MW-30	MW-30	7/26/2019	180-93333-1	11	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.8	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	20	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	5.6	5.6	< 0.67 U	< 0.66 U	< 0.59 U
MW-30	MW-30	2/19/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	21 J	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	15	15	< 0.67 U	< 0.66 U	< 0.59 U
MW-30	MW-30	7/16/2021	180-124628-1	19	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	6.6	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	19	19	< 0.67 U	< 0.66 U	< 0.59 U
MW-30	SSHS-MW-30-04302024	4/30/2024	1801733261	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	4.8	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	3.8	3.8	< 0.67 U	< 0.66 U	< 0.59 U
MW-31	MW-31	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-32	MW-32	2/22/2021	180-117425-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-32	MW-32	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-33	MW-33	2/19/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-33	MW-33	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 UJ	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 UJ	< 0.57 UJ	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-34	MW-34	2/24/2021	180-117542-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-34	MW-34	4/30/2021	180-120955-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-36	SSHS-MW36	8/22/2018	180-81174-1	4.1 J	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.36 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-36	SSHS-MW36	8/22/2018	180-81174-1	5	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.36 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-36	MW-36	3/23/2021	180-118872-1	9.8	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-12	MW-12	9/24/2003	-	< 5 U	< 5 U	39	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-12	MW-12	6/1/2004	-	-	-	160	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	6.8	-	ND	-	-	-
MW-12	MW-12	12/30/2004	-	-	-	49	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-12	MW-12	6/28/2005	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	2 J	-	ND	-	-	-
MW-12	MW-12	12/28/2005	-	-	-	16	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	1	-	ND	-	-	-
MW-12	MW-12	7/12/2007	-	-	-	6.1	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	0.96	-	ND	-	-	-
MW-12	MW-12	2/21/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-12	MW-12	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-13	DUP-1	8/20/2014	180-36053-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
MW-13	MW-13	8/20/2014	180-36053-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
MW-13	DUP-02	2/21/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-13	MW-13	2/21/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-13	MW-13	7/15/2021	180-124580-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	0.46 J	0.48	< 0.41 U	< 0.89 U
MW-15D	MW-15D	4/29/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	6.2 J	< 5 U	-
MW-15D	MW-15D	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-15D	MW-15D	9/24/2006	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-15S	MW-15S	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-17	MW17	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	6 J	-	-	-	-	-
MW-17	MW17	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4 J	-	-	-	-	-
MW-17	MW-17	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-2	MW-2	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-2	MW-2	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-2	MW-2	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-2	MW-2	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	0.48	< 0.41 U	< 0.89 U
MW-20	MW20	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 J	-	-	-	-	-
MW-20	MW-20	2/23/2021	180-117459-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-20	MW-20	7/15/2021	180-124580-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	0.48	< 0.41 U	< 0.89 U
MW-22	MW-22	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-22	MW-22	2/23/2021	180-117459-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-22	MW-22	7/15/2021	180-124580-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	0.48	< 0.41 U	< 0.89 U
MW-26	MW-26	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-26	MW-26	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-3	MW-3	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-3	MW-3	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-3	MW-3	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-3	MW-3	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-3	DUP-4	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	-	< 0.41 U	< 0.89 U
MW-30	MW-30	4/2/2002	-	-	-	5.8	-	-	-	-	-	-	-	-	-	52.8	-	-	-	4.7	-	58.6	-	ND	-	-	-
MW-30	MW-30	6/19/2002	-	-	-	21000 J	-	-	-	-	-	-	-	-	-	-	-	-	-	13	-	79	-	-	-	-	-
MW-30	MW-30	7/23/2002	-	-	-	3100	-	-	-	-	-	-	-	-	-	70 J	-	-	-	ND	-	78 J	-	ND	-	-	-
MW-30	MW-30-D20	5/20/2003	-	< 100 U	< 100 U	2800	< 200 U	-	-	-	< 200 U	< 200 U	-	< 100 U	< 100 U	< 100 U	< 100 U	-	-	< 100 U	< 100 U	< 100 U	-	< 20 U	< 100 U	< 100 U	-
MW-30	MW-30	5/20/2003	-	-	-	2800	-	-	-	-	-	-	-	-	-	90	-	-	-	10	-	92	-	1	-	-	-
MW-30	MW-30	5/20/2003	-	< 5 U	< 5 U	-	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	90	< 5 U	-	-	10	< 5 U	92	-	1	< 5 U	< 5 U	-
MW-30	MW-30-D20	9/24/2003	-	< 100 U	< 100 U	2400	< 200 U	-	-	-	< 200 U	< 200 U	-	< 100 U	< 100 U	< 100 U	< 100 U	-	-	< 100 U	< 100 U	< 100 U	-	< 20 U	< 100 U	< 100 U	-
MW-30	MW-30	9/24/2003	-	-	-	2400	-	-	-	-	-	-	-	-	-	84	-	-	-	-	-	88	-	ND	-	-	-
MW-30	MW-30	9/24/2003	-	< 5 U	< 5 U	-	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	84	< 5 U	-	-	< 5 U	< 5 U	88	-	< 1 U	< 5 U	< 5 U	-
MW-30	MW-30	6/1/2004	-	-	-	2200	-	-	-	-	-	-	-	-	-	60	-	-	-	ND	-	59	-	ND	-	-	-
MW-30	MW-30	12/30/2004	-	-	-	1200	-	-	-	-	-	-	-	-	-	55	-	-	-	ND	-	57	-	ND	-	-	-
MW-30	MW-30	6/28/2005	-	-	-	ND	-	-	-	-	-	-	-	-	-	35	-	-	-	ND	-	35	-	ND	-	-	-
MW-30	MW-30	12/28/2005	-	-	-	1400	-	-	-	-	-	-	-	-	-	60	-	-	-	5	-	87	-	ND	-	-	-
MW-30	MW-30	5/25/2006	-	-	-	-	-	-	-	-	-	-	-	-	-	42	-	-	-	30	-	50	-	20	-	-	-
MW-30	MW-30	7/12/2007	-	-	-	2100	-	-	-	-	-	-	-	-	-	51	-	-	-	6	-	61	-	0.87	-	-	-
MW-30	MW-30	8/21/2014	180-36053-1	< 1.9 U	< 2.8 U	250	< 2 U	< 2 U	< 1.7 U	< 3.3 U	< 6.8 U	< 6.6 U	< 2.3 U	< 1.2 U	< 2.5 U	27	< 1.9 U	< 1.9 U	< 3.4 U	< 3.6 U	< 2.5 U	24	< 2.5 U	< 2.8 U	< 5.1 U	< 1.4 U	-
MW-30	MW-30	8/21/2014	180-36053-1	< 0.74 U	< 1.1 U	180	< 0.8 U	< 0.82 U	< 0.69 U	< 1.3 U	< 2.7 U	< 2.6 U	< 0.92 U	< 0.48 U	< 1 U	24	< 0.75 U	< 0.77 U	< 1.4 U	< 1.4 U	< 1 U	17	< 0.99 U	< 1.1 U	< 2 U	< 0.55 U	-
MW-30	MW-30	7/26/2019	180-93333-1	< 0.58 UJ	< 0.51 U	35	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	5	< 0.59 U	< 0.47 U	< 0.6 U	2.3	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	0.87 J	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-30	MW-30	2/19/2021	180-117476-1	< 0.58 U	< 0.51 U	37	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	3.4	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	3.6	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-30	MW-30	7/16/2021	180-124628-1	< 0.58 U	< 0.51 U	28	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	1.8	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	1.2	< 0.87 U	4.7	0.48	< 0.41 U	< 0.89 U
MW-30	SSHS-MW-30-04302024	4/30/2024	1801733261	< 0.58 U	< 0.51 U	2.6	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.66 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-31	MW-31	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-32	MW-32	2/22/2021	180-117425-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-32	MW-32	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-33	MW-33	2/19/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-33	MW-33	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-34	MW-34	2/24/2021	180-117542-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-34	MW-34	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-36	SSHS-MW36	8/22/2018	180-81174-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-36	SSHS-MW36	8/22/2018	180-81174-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-36	MW-36	3/23/2021	180-118872-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	5.2	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1.2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-36	MW-36	4/30/2021	180-120955-1	6.1	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-38	SSHS-MW-38	8/23/2018	180-81247-1	5.8	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.36 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-38	PS-FD-1	8/24/2018	180-81247-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.36 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-38	MW-38	3/24/2021	180-119009-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-38	DUP-1	4/30/2021	180-120955-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-38	MW-38	4/30/2021	180-120955-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-39	SSHS-MW-39	8/23/2018	180-81247-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.36 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-4	MW-4	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-4	MW4	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-4	MW-4	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	1 J	ND	-	-
MW-4	MW-4	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-4	MW-4	7/23/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	-	-
MW-4	MW-4	6/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-4	MW-4	5/20/2006	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-40	MW-40	5/23/2019	180-90525-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 UJ	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-40	MW-40	2/23/2021	180-117459-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-41	MW-41	3/26/2008	-	ND	ND	-	ND	ND	ND	ND	ND	ND	ND	ND	ND	-	-	-	ND	-	-	-	-	-	-	ND	ND	ND	-	ND	ND	ND	ND
MW-41	DUP-03	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-41	MW-41	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-41	MW-41	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-43	MW-43	2/24/2021	180-117542-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-43	MW-43	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-44	SSHS-MW-44	8/23/2018	180-81247-1	6.1	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.36 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47	SSHS-MW-47	9/26/2016	180-59149-1	< 2.5 U	< 0.26 U	< 0.38 U	< 0.23 U	< 0.29 U	< 0.36 U	< 0.18 U	< 0.24 U	< 0.31 U	< 0.4 U	< 0.26 U	< 0.27 U	< 0.23 U	< 0.28 U	< 0.19 U	< 0.36 U	< 0.29 U	< 0.27 U	< 0.28 U	< 0.25 U	< 0.27 U	-	< 0.24 U	< 0.25 U	< 0.29 U	2.8	2.8	< 0.29 U	< 0.23 U	< 0.21 U
MW-47	DUP-01	2/22/2021	180-117425-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47	MW-47	2/22/2021	180-117425-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47	MW-47	7/12/2021	180-124354-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47I	MW-47I	9/10/2021	180-126939-1	< 5.4 U	1.5	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-47I	DUP-01	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47I	MW-47I	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731401	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731401	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48	MW-48	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48	MW-48	4/26/2021	180-120679-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	SSHS-MW-48R-09122023	9/12/2023	1801624601	38	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654471	6.0	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 UJ	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.61 J	< 0.90 UJ	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 UJ	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654471	6.3	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 UJ	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.67 J	< 0.90 UJ	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 UJ	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	DUP-01-01162024	1/16/2024	1801682361	5.2	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.62 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682361	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721201	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.66 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721201	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-49	DUP-04	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.61 J	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-49	MW-49	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.66 J	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-49	MW-49	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.71 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-50I	SSHS-RI-MW-50I	2/12/2021	180-117176-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.94 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-50I	MW-50I	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.68 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-50R	SSHS-MW-50R-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-50R	SSHS-MW-50R-04082024	4/8/2024	1801720381	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-50S	SSHS-RI-MW-50S	2/12/2021	180-117176-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.69 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-50S	MW-50S	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.83 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	DUP-05	2/12/2021	180-117176-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.68 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	2.8	2.8	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	SSHS-RI-MW-51	2/12/2021	180-117176-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.71 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	2.8	2.8	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	DUP-05 (Diluted)	2/12/2021	180-117176-1	< 34 U	< 6 U	< 6.3 U	< 6.4 U	< 9.8 U	< 8.9 U	< 8.8 U	< 8.8 U	< 5 U	< 8.4 U	< 9 U	< 6 U	< 9 U	< 6.3 U	< 8.9 U	< 8.9 U	< 5 U	< 8.3 U	< 3.6 U	< 5 U	< 5.4 U	-	< 3.1 U	< 5.7 U	< 5.5 U	< 13 U	< 7.1 U	< 6.7 U	< 6.6 U	< 5.9 U
MW-51	SSHS-RI-MW-51 (Diluted)	2/12/2021	180-117176-1	< 34 U	< 6 U	< 6.3 U	< 6.4 U	< 9.8 U	< 8.9 U	< 8.8 U	< 8.8 U	< 5 U	< 8.4 U	< 9 U	< 6 U	< 9 U	< 6.3 U	< 8.9 U	< 8.9 U	< 5 U	< 8.3 U	< 3.6 U	< 5 U	< 5.4 U	-	< 3.1 U	< 5.7 U	< 5.5 U	< 13 U	< 7.1 U	< 6.7 U	< 6.6 U	< 5.9 U
MW-51	MW-51	4/27/2021	180-120743-1	< 17 U	< 3 U	< 3.1 U	< 3.2 U	< 4.9 U	< 4.4 U	< 4.4 U	< 4.4 U	< 2.5 U	< 4.2 U	< 4.5 U	< 3 U	< 4.5 U	< 3.2 U	< 4.4 U	< 4.4 U	< 2.5 U	< 4.2 U	< 1.8 U	< 2.5 U	< 2.7 U	-	< 1.5 U	< 2.9 U	< 2.8 U	< 6.6 U	< 3.5 U	< 3.4 U	< 3.3 U	< 3 U
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	0.78 J	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	SSHS-MW-51-09122023	9/12/2023	1801624601	65	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653531	9.1	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.77 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	1.4 J	1.4	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	SSHS-MW-51-01172024	1/17/2024	1801682361	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721201	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.60 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-52	SSHS-RI-MW-52	2/12/2021	180-117176-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.81 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-52	DUP-2	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.6 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-52	MW-52	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.64 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-53	MW-53	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-53	MW-53	4/26/2021	180-120679-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-53	SSHS-MW-53-09042023	9/4/2023	1801619191	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-54	MW-54	2/25/2021	180-117621-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.74 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-54	MW-54	4/27/2021	180-120743-1	8.3 J+	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 UJ	< 0.57 U	< 0.55 U	< 1.3 UJ	< 0.71 UJ	< 0.67 UJ	< 0.66 U	< 0.59 U

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-36	MW-36	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-38	SSHS-MW-38	8/23/2018	180-81247-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-38	PS-FD-1	8/24/2018	180-81247-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-38	MW-38	3/24/2021	180-119009-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	1.7 J	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-38	DUP-1	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-38	MW-38	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-39	SSHS-MW-39	8/23/2018	180-81247-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-4	MW-4	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-4	MW4	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1 J	-	-	-	-	-
MW-4	MW-4	5/17/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-4	MW-4	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	ND	-	ND	-	-	-
MW-4	MW-4	7/23/2002	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	ND	1.4 J	-	ND	-	-	-
MW-4	MW-4	6/28/2005	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-4	MW-4	5/20/2006	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-40	MW-40	5/23/2019	180-90525-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-40	MW-40	2/23/2021	180-117459-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-41	MW-41	3/26/2008	-	ND	ND	-	ND	-	-	-	ND	ND	-	ND	ND	ND	ND	-	-	ND	ND	ND	-	ND	ND	ND	-
MW-41	DUP-03	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-41	MW-41	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-41	MW-41	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-43	MW-43	2/24/2021	180-117542-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-43	MW-43	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-44	SSHS-MW-44	8/23/2018	180-81247-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	1.3	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-47	SSHS-MW-47	9/26/2016	180-59149-1	< 0.24 U	< 0.27 U	< 0.27 U	< 0.74 U	< 0.27 U	< 1.5 U	< 0.26 U	< 1.2 U	< 0.59 U	< 0.24 U	< 0.26 U	< 0.35 U	0.29 J	< 0.28 U	< 0.19 U	< 0.27 U	< 0.22 U	< 0.35 U	3.9	< 0.31 U	< 0.32 U	< 0.27 U	< 0.24 U	< 0.48 U
MW-47	DUP-01	2/22/2021	180-117425-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-47	MW-47	2/22/2021	180-117425-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-47	MW-47	7/12/2021	180-124354-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	0.48	< 0.41 U	< 0.89 U
MW-47I	MW-47I	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-47I	DUP-01	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-47I	MW-47I	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731401	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731401	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-48	MW-48	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-48	MW-48	4/26/2021	180-120679-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-48R	SSHS-MW-48R-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.54 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 UJ	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 UJ	< 0.48 U	< 0.41 U	< 0.89 U
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.61 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 UJ	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 UJ	< 0.48 U	< 0.41 U	< 0.89 U
MW-48R	DUP-01-01162024	1/16/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.53 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-49	DUP-04	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-49	MW-49	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-49	MW-49	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-50I	SSHS-RI-MW-50I	2/12/2021	180-117176-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 UJ	< 0.6 U	0.63 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	6.5	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-50I	MW-50I	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	1.3	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	4.3 J	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-50R	SSHS-MW-50R-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	2.4	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-50R	SSHS-MW-50R-04082024	4/8/2024	1801720381	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	2.8	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-50S	SSHS-RI-MW-50S	2/12/2021	180-117176-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 UJ	< 0.6 U	1.9	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	4.4	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-50S	MW-50S	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	2.6	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	6.4	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-51	DUP-05	2/12/2021	180-117176-1	< 0.58 U	< 0.51 U	25	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 UJ	< 0.6 U	13	< 0.46 U	< 1.1 U	< 0.77 U	3.7	< 0.45 U	-	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-51	SSHS-RI-MW-51	2/12/2021	180-117176-1	< 0.58 U	< 0.51 U	29	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 UJ	< 0.6 U	14	< 0.46 U	< 1.1 U	< 0.77 U	4.1	< 0.45 U	-	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-51	DUP-05 (Diluted)	2/12/2021	180-117176-1	< 5.8 U	< 5.1 U	16	< 33 U	< 3.4 U	< 17 U	< 6.1 U	< 26 U	< 31 U	< 5.9 U	< 4.7 U	< 6 U	< 4.7 U	< 4.6 U	< 11 U	< 7.7 U	< 6 U	< 4.5 U	52 J	< 8.7 U	< 4.1 U	-	< 4.1 U	< 8.9 U
MW-51	SSHS-RI-MW-51 (Diluted)	2/12/2021	180-117176-1	< 5.8 U	< 5.1 U	28	< 33 U	< 3.4 U	< 17 U	< 6.1 U	< 26 U	< 31 U	< 5.9 U	< 4.7 U	< 6 U	8 J	< 4.6 U	< 11 U	< 7.7 U	< 6 U	< 4.5 U	75 J	< 8.7 U	< 4.1 U	-	< 4.1 U	< 8.9 U
MW-51	MW-51	4/27/2021	180-120743-1	< 2.9 U	< 2.5 U	28	< 16 U	< 1.7 U	< 8.4 U	< 3 U	< 13 U	< 15 U	< 3 U	< 2.4 U	< 3 U	12	< 2.3 U	< 5.3 U	< 3.9 U	4.4 J	< 2.3 U	87	< 4.4 U	< 2 U	-	< 2 U	< 4.5 U
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	14	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	5.3	< 0.46 U	< 1.1 U	< 0.77 U	2.5	< 0.45 U	63	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-51	SSHS-MW-51-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	6.3	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	3.9	< 0.46 U	< 1.1 U	< 0.77 U	1.0	< 0.45 U	27	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653531	< 0.58 U	< 0.51 U	34	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	10	< 0.46 U	< 1.1 UJ	< 0.77 UJ	4.3	< 0.45 U	94 J-	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-51	SSHS-MW-51-01172024	1/17/2024	1801682361	< 0.58 U	< 0.51 U	3.4	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	4.9	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	20	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	1.1	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	5.1	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	16	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-52	SSHS-RI-MW-52	2/12/2021	180-117176-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 UJ	< 0.6 U	0.65 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	3.3	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-52	DUP-2	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.95 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	2.5	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-52	MW-52	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.9 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	2.5	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-53	MW-53	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-53	MW-53	4/26/2021	180-120679-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.5 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-53	SSHS-MW-53-09042023	9/4/2023	1801619191	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-54	MW-54	2/25/2021	180-117621-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-54	MW-54	4/27/2021	180-120743-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.82 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	MW-55	2/24/2021	180-117542-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.77 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	MW-55	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.89 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	DUP-01-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.67 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.65 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	SSHS-DUP-06-09122023	9/12/2023	1801624601	23	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.89 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	SSHS-MW-55-09122023	9/12/2023	1801624601	22	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.70 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654471	8.7	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 UJ	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 UJ	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 UJ	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682361	4.0 JT	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.94 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721201	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 UT	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-56	MW-56	2/17/2021	180-117387-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.7 J	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-56	MW-56	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.87 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.72 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57	MW-57	2/18/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.87 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57	MW-57	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.92 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57	DUP-01	7/13/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	0.95 J	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57	MW-57	7/13/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 UT	< 0.64 U	< 0.98 UT	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UT	< 0.83 UT	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 UT	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 UT	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 UT	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57R	SSHS-MW-57R-09122023	9/12/2023	1801624601	34	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653531	8.7	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682361	13	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721201	8.9	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.0	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-58	MW-58	2/21/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-58	MW-58	4/30/2021	180-120955-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-59I	MW-59I	2/19/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-59I	MW-59I	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-59I	MW-59I	7/12/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-59S	MW-59S	2/19/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-59S	MW-59S	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.3	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-59S	MW-59S	7/13/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 UT	< 0.64 U	< 0.98 UT	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UT	< 0.83 UT	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 UT	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-5I	SSHS-MW-5I-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-5I	SSHS-MW-5I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-5S	MW-5	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	180	-	-	-
MW-5S	MW-5	12/19/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-5S	MW5	5/16/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	140	-	-	-
MW-5S	MW-5	5/16/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	140	-	-	-
MW-5S	MW5	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	170	-	-	-
MW-5S	MW-5	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	170	-	-	-
MW-5S	MW-5	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-5S	MW-5	7/23/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	380	-	-	-
MW-5S	MW-5	5/20/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	310	-	-	-
MW-5S	MW-5	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	310	< 5 U	< 5 U	< 5 U
MW-5S	MW-5	9/24/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-5S	MW-5	9/24/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-5S	MW-5	6/1/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	190	-	-	-
MW-5S	MW-5	12/30/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	170	-	-	-
MW-5S	MW-5	6/28/2005	-	11	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 J	-	-	-	-	-	-	-	-	-	110	-	-	-
MW-5S	MW-5	12/28/2005	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	48	-	-	-
MW-5S	MW-5	5/25/2006	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	91	-	-	-
MW-5S	MW-5	7/12/2007	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	36	-	-	-
MW-5S	MW-5	2/23/2021	180-117459-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-5S	MW-5	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	7/15/2021	180-124580-1	3.4 NV	0.6 NV	0.63 NV	0.64 NV	0.98 NV	0.89 NV	0.88 NV	0.88 NV	0.5 NV	0.84 NV	0.9 NV	0.6 NV	0.9 NV	0.63 NV	0.89 NV	0.89 NV	0.5 NV	0.83 NV	0.36 NV	0.5 NV	0.54 NV	-	0.31 NV	0.57 NV	0.55 NV	1.3 NV	0.71 NV	0.67 NV	0.66 NV	0.59 NV
MW-60	MW-60	2/18/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.92 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-60	MW-60	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-60	MW-60	7/12/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	1.2	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-61	MW-61	2/25/2021	180-117621-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-61	MW-61	4/27/2021	180-120743-1	10 J+	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 UJ	< 0.57 U	< 0.55 U	< 1.3 UJ	< 0.71 UJ	< 0.67 UJ	< 0.66 U	< 0.59 U
MW-61	MW-61	7/12/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	1.3	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-62	MW-62	2/24/2021	180-117542-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.6 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-62	MW-62	4/27/2021	180-120743-1	10 J+	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.66 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 UJ	< 0.57 U	< 0.55 U	< 1.3 UJ	< 0.71 UJ	< 0.67 UJ	< 0.66 U	< 0.59 U
MW-62	MW-62	7/12/2022	1801412391	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	1.2	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-62R	SSHS-MW-62R-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-62R	SSHS-MW-62R-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.66 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-63I	MW-63I	2/18/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-63I	MW-63I	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	MW-55	2/24/2021	180-117542-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-55	MW-55	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-55	DUP-01-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	SSHS-DUP-06-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	SSHS-MW-55-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.51 J	< 0.46 U	< 1.1 UT	< 0.77 U	< 0.60 UJ	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 UJ	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.54 J	< 0.46 U	< 1.1 UT	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-56	MW-56	2/17/2021	180-117387-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-56	MW-56	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57	MW-57	2/18/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-57	MW-57	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-57	DUP-01	7/13/2022	1801412391	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57	MW-57	7/13/2022	1801412391	< 0.58 UT	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 UT	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 UT	< 0.47 U	< 0.60 UT	< 0.47 U	< 0.46 UT	< 1.1 U	< 0.77 U	< 0.60 UT	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	< 0.86 UT	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 UT	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57R	SSHS-MW-57R-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653531	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-58	MW-58	2/21/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-58	MW-58	4/30/2021	180-120955-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-59I	MW-59I	2/19/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-59I	MW-59I	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-59I	MW-59I	7/12/2022	1801412391	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-59S	MW-59S	2/19/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.47 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-59S	MW-59S	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-59S	MW-59S	7/13/2022	1801412391	< 0.58 UT	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 UT	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 UT	< 0.47 U	< 0.60 UT	< 0.47 U	< 0.46 UT	< 1.1 U	< 0.77 U	< 0.60 UT	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-5I	SSHS-MW-5I-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-5I	SSHS-MW-5I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-5S	MW-5	9/26/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	63	-	-	-
MW-5S	MW-5	12/19/1997	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	550	-	ND	-	-	-
MW-5S	MW5	5/16/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	61	-	-	-
MW-5S	MW-5	5/16/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	61	-	-	-
MW-5S	MW5	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	66	-	-	-
MW-5S	MW-5	9/20/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	66	-	-	-
MW-5S	MW-5	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-5S	MW-5	7/23/2002	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	88	-	-	-
MW-5S	MW-5	5/20/2003	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	86	-	-	-
MW-5S	MW-5	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	86	< 5 U	< 5 U	-
MW-5S	MW-5	9/24/2003	-	-	-	35	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-5S	MW-5	9/24/2003	-	< 5 U	< 5 U	35	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-5S	MW-5	6/1/2004	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	78	-	-	-
MW-5S	MW-5	12/30/2004	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	71	-	-	-
MW-5S	MW-5	6/28/2005	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	36	-	-	-
MW-5S	MW-5	12/28/2005	-	-	-	5	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	18	-	-	-
MW-5S	MW-5	5/25/2006	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	35	-	-	-
MW-5S	MW-5	7/12/2007	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	27	-	-	-
MW-5S	MW-5	2/23/2021	180-117459-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-5S	MW-5	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	7/15/2021	180-124580-1	0.58 NV	0.51 NV	0.86 NV	3.3 NV	0.34 NV	1.7 NV	0.61 NV	2.6 NV	3.1 NV	0.59 NV	0.47 NV	0.6 NV	0.47 NV	0.46 NV	1.1 NV	0.77 NV	0.6 NV	0.45 NV	0.69 NV	0.87 NV	0.57 NV	0.48	0.41 NV	0.89 NV
MW-60	MW-60	2/18/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-60	MW-60	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-60	MW-60	7/12/2022	1801412391	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.53 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-61	MW-61	2/25/2021	180-117621-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-61	MW-61	4/27/2021	180-120743-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.5 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-61	MW-61	7/12/2022	1801412391	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-62	MW-62	2/24/2021	180-117542-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-62	MW-62	4/27/2021	180-120743-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-62	MW-62	7/12/2022	1801412391	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.67 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-62R	SSHS-MW-62R-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-62R	SSHS-MW-62R-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-63I	MW-63I	2/18/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-63I	MW-63I	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-63I	SSHS-MW-63I-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.98 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-63S	MW-63S	2/18/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.96 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-63S	MW-63S	4/29/2021	180-121010-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.91 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-63S	SSHS-MW-63S-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.3	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-64I	MW-64I	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.6 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-64I	MW-64I	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.64 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-64I	SSHS-MW-64I-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-64S	MW-64S	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.74 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-64S	MW-64S	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65	MW-65	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.76 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65	DUP-3	4/26/2021	180-120679-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.69 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65	MW-65	4/26/2021	180-120679-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.7 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65	SSHS-DUP1-08152022	8/15/2022	1801429571	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65	SSHS-MW-65-08152022	8/15/2022	1801429571	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65R	SSHS-MW-65R-09142023	9/14/2023	1801625611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.94 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-65R	SSHS-MW-65R-04082024	4/8/2024	1801720411	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.7	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-66I	MW-66I	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.72 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-66I	MW-66I	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.81 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-66I	SSHS-MW-66I-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-66S	MW-66S	2/19/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-66S	MW-66S	4/28/2021	180-120857-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.6 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-66S	SSHS-MW-66S-09122023	9/12/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-67I	MW-67I	7/16/2021	180-124628-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-67I	MW-67I	8/31/2021	180-126501-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-67I	SSHS-MW-67I-04282024	4/28/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-67S	MW-67S	7/16/2021	180-124628-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-67S	MW-67S	8/31/2021	180-126501-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	0.7 J	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	0.49 J	< 0.21 U	< 0.49 U	1.7	1.2	0.53 J	< 0.47 U	< 0.61 U
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-68S	DUP-3	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-68S	MW-68S	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-68S	DUP-2	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-68S	MW-68S	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-68S	SSHS-MW-68S-04282024	4/28/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-69I	MW-69I	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-69I	MW-69I	9/3/2021	180-126702-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-69I	SSHS-MW-69I-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-7	MW-7	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-7	MW-7	6/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 J	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-70I	MW-70I	9/9/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-70I	MW-70I	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70I	SSHS-MW-70I-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70S	MW-70S	9/7/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-70S	MW-70S	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70S	DUP-02	5/4/2023	1801561231	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561231	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625621	< 3.4 UT	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70S	SSHS-DUP-04-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-70S	SSHS-MW-70S-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-71I	MW-71I	9/7/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-71I	MW-71I	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-71I	SSHS-MW-71I-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-71S	MW-71S	9/7/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-71S	MW-71S	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-71S	SSHS-MW-71S-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72I	MW-72I	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-72I	DUP-02	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72I	MW-72I	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72I	SSHS-MW-72I-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 UT	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72S	MW-72S	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-72S	MW-72S	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561231	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625621	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-72S	SSHS-MW-72S-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-73I	MW-73I	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	0.52 J	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-73I	MW-73I	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-73I	SSHS-MW-73I-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-63I	SSHS-MW-63I-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-63S	MW-63S	2/18/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-63S	MW-63S	4/29/2021	180-121010-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-63S	SSHS-MW-63S-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-64I	MW-64I	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-64I	MW-64I	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-64I	SSHS-MW-64I-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-64S	MW-64S	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.51 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-64S	MW-64S	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.54 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-65	MW-65	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-65	DUP-3	4/26/2021	180-120679-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-65	MW-65	4/26/2021	180-120679-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-65	SSHS-DUP1-08152022	8/15/2022	1801429571	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-65	SSHS-MW-65-08152022	8/15/2022	1801429571	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.52 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-65R	SSHS-MW-65R-09142023	9/14/2023	1801625611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-65R	SSHS-MW-65R-04082024	4/8/2024	1801720411	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-66I	MW-66I	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.5 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-66I	MW-66I	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-66I	SSHS-MW-66I-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-66S	MW-66S	2/19/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.48 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-66S	MW-66S	4/28/2021	180-120857-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-66S	SSHS-MW-66S-09122023	9/12/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-67I	MW-67I	7/16/2021	180-124628-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-67I	MW-67I	8/31/2021	180-126501-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-67I	SSHS-MW-67I-04282024	4/28/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-67S	MW-67S	7/16/2021	180-124628-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	0.52 J	< 1.7 U	1.4	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	1.2	< 0.48 U	0.59 J	< 0.89 U
MW-67S	MW-67S	8/31/2021	180-126501-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	2.6	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	0.46 J	< 0.42 U	< 0.42 U	< 0.42 U
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-68S	DUP-3	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-68S	MW-68S	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-68S	DUP-2	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-68S	MW-68S	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-68S	SSHS-MW-68S-04282024	4/28/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UT	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-69I	MW-69I	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-69I	MW-69I	9/3/2021	180-126702-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-69I	SSHS-MW-69I-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-7	MW-7	5/20/2003	-	< 5 U	< 5 U	< 5 U	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	< 5 U	< 1 U	< 5 U	< 5 U	-
MW-7	MW-7	6/28/2005	-	-	-	ND	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-70I	MW-70I	9/9/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-70I	MW-70I	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-70I	SSHS-MW-70I-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-70S	MW-70S	9/7/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	0.48 J	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-70S	MW-70S	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-70S	DUP-02	5/4/2023	1801561231	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561231	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625621	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 UT	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-70S	SSHS-DUP-04-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-70S	SSHS-MW-70S-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-71I	MW-71I	9/7/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-71I	MW-71I	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-71I	SSHS-MW-71I-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-71S	MW-71S	9/7/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-71S	MW-71S	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-71S	SSHS-MW-71S-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-72I	MW-72I	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-72I	MW-72I	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-72I	SSHS-MW-72I-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UT	< 0.77 UT	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-72S	MW-72S	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-72S	MW-72S	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561231	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625621	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-72S	SSHS-MW-72S-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-73I	MW-73I	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-73I	MW-73I	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-73I	SSHS-MW-73I-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-73S	MW-73S	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-73S	MW-73S	10/26/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-73S	SSHS-MW-73S-04052024	4/5/2024	1801720031	< 3.4 UT	< 0.60 UT	< 0.63 UT	< 0.64 UT	< 0.98 UT	< 0.89 UT	< 0.88 UT	< 0.88 UT	< 0.50 UT	< 0.84 UT	< 0.90 UT	< 0.60 UT	< 0.90 UT	< 0.63 UT	< 0.89 UT	< 0.89 UT	< 0.50 UT	< 0.83 UT	< 0.36 UT	< 0.50 UT	< 0.54 UT	-	< 0.31 UT	< 0.57 UT	< 0.55 UT	< 1.3 UT	< 0.71 UT	< 0.67 UT	< 0.66 UT	< 0.59 UT
MW-74I	MW-74I	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-74I	MW-74I	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-74I	SSHS-MW-74I-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-74S	MW-74S	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-74S	MW-74S	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-74S	SSHS-DUP-05-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-74S	SSHS-MW-74S-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-75I	MW-75I	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-75I	MW-75I	10/29/2021	180-129376-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-75S	MW-75S	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-75S	MW-75S	10/29/2021	180-129376-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-76I	MW-76I	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	1.8	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-76I	DUP-03	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-76I	MW-76I	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-76S	MW-76S	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-76S	MW-76S	10/28/2021	180-129230-1	5	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-76S	SSHS-MW-76S-04082024	4/8/2024	1801720411	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-76S	SSHS-MW-76S-04222024	4/22/2024	1801730541	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 UT	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 UT	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-77I	MW-77I	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-77I	MW-77I	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-77I	SSHS-MW-77I-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-77S	MW-77S	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-77S	MW-77S	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-77S	SSHS-MW-77S-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-78I	MW-78I	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	1	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-78I	MW-78I	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-78I	SSHS-MW-78I-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-78S	DUP-5	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	2.3	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-78S	MW-78S	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	2.3	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-78S	MW-78S	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.6	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-78S	SSHS-MW-78S-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.64 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-79I	MW-79I	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	0.77 J	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-79I	DUP-04	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	1.9 J+	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-79I	MW-79I	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	2.1	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-79I	SSHS-MW-79I-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-79S	MW-79S	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	1.3	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-79S	MW-79S	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-79S	SSHS-DUP-06-04052024	4/5/2024	1801720031	< 3.4 UT	< 0.60 UT	< 0.63 UT	< 0.64 UT	< 0.98 UT	< 0.89 UT	< 0.88 UT	< 0.88 UT	< 0.50 UT	< 0.84 UT	< 0.90 UT	< 0.60 UT	< 0.90 UT	< 0.63 UT	< 0.89 UT	< 0.89 UT	< 0.50 UT	< 0.83 UT	< 0.36 UT	< 0.50 UT	< 0.54 UT	-	< 0.31 UT	< 0.57 UT	< 0.55 UT	< 1.3 UT	< 0.71 UT	< 0.67 UT	< 0.66 UT	< 0.59 UT
MW-79S	SSHS-MW-79S-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-81I	MW-81I	7/16/2021	180-124628-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-81I	MW-81I	8/31/2021	180-126501-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731401	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 UT	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-82S	DUP-3	9/7/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-82S	MW-82S	9/7/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-82S	MW-82S	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-83I	MW-83I	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-83I	MW-83I	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-83S	MW-83S	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-83S	MW-83S	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-84S	MW-84S	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-84S	MW-84S	10/27/2021	180-129155-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-84S	SSHS-DUP-07-04152024	4/15/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-84S	SSHS-MW-84S-04152024	4/15/2024	1801726651	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-85I	MW-85I	7/15/2021	180-124580-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-85I	MW-85I	9/2/2021	180-126608-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-85I	SSHS-MW-85I-04222024	4/22/2024	1801730541	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-86I	MW-86I	7/13/2021	180-124378-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-86I	MW-86I	9/1/2021	180-126593-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-86I	SSHS-MW-86I-04042024	4/4/2024	1801719081	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-87I	MW-87I	7/14/2021	180-124487-1	6.2	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-73S	MW-73S	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	0.99 J	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-73S	MW-73S	10/26/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	0.92 J	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-73S	SSHS-MW-73S-04052024	4/5/2024	1801720031	< 0.58 UT	< 0.51 UT	< 0.86 UT	< 3.3 UT	< 0.34 UT	< 1.7 UT	< 0.61 UT	< 2.6 UT	< 3.1 UT	< 0.59 UT	< 0.47 UT	< 0.60 UT	< 0.47 UT	< 0.46 UT	< 1.1 UT	< 0.77 UT	< 0.60 UT	< 0.45 UT	< 0.69 UT	< 0.87 UT	< 0.41 UT	< 0.48 UT	< 0.41 UT	< 0.89 UT
MW-74I	MW-74I	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-74I	MW-74I	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-74I	SSHS-MW-74I-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-74S	MW-74S	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-74S	MW-74S	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-74S	SSHS-DUP-05-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-74S	SSHS-MW-74S-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-75I	MW-75I	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-75I	MW-75I	10/29/2021	180-129376-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-75S	MW-75S	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-75S	MW-75S	10/29/2021	180-129376-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-76I	MW-76I	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-76I	DUP-03	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.53 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-76I	MW-76I	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 UJ	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-76S	MW-76S	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-76S	MW-76S	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	4.7 J	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-76S	SSHS-MW-76S-04082024	4/8/2024	1801720411	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-76S	SSHS-MW-76S-04222024	4/22/2024	1801730541	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UT	< 0.77 UT	< 0.60 U	< 0.45 U	< 0.69 UT	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-77I	MW-77I	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-77I	MW-77I	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.5 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-77I	SSHS-MW-77I-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-77S	MW-77S	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-77S	MW-77S	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.51 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-77S	SSHS-MW-77S-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-78I	MW-78I	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-78I	MW-78I	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.51 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-78I	SSHS-MW-78I-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-78S	DUP-5	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-78S	MW-78S	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-78S	MW-78S	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.53 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-78S	SSHS-MW-78S-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-79I	MW-79I	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	0.78 J	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-79I	DUP-04	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.5 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-79I	MW-79I	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-79I	SSHS-MW-79I-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-79S	MW-79S	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	0.66 J	< 0.48 U	0.81 J	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-79S	MW-79S	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-79S	SSHS-DUP-06-04052024	4/5/2024	1801720031	< 0.58 UT	< 0.51 UT	< 0.86 UT	< 3.3 UT	< 0.34 UT	< 1.7 UT	< 0.61 UT	< 2.6 UT	< 3.1 UT	< 0.59 UT	< 0.47 UT	< 0.60 UT	< 0.47 UT	< 0.46 UT	< 1.1 UT	< 0.77 UT	< 0.60 UT	< 0.45 UT	< 0.69 UT	< 0.87 UT	< 0.41 UT	< 0.48 UT	< 0.41 UT	< 0.89 UT
MW-79S	SSHS-MW-79S-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-81I	MW-81I	7/16/2021	180-124628-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-81I	MW-81I	8/31/2021	180-126501-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731401	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UT	< 0.77 UT	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-82S	DUP-3	9/7/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	1.2 J	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-82S	MW-82S	9/7/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	0.8 J	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-82S	MW-82S	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	1.2	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-83I	MW-83I	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-83I	MW-83I	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-83S	MW-83S	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-83S	MW-83S	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-84S	MW-84S	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	0.44 J	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-84S	MW-84S	10/27/2021	180-129155-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-84S	SSHS-DUP-07-04152024	4/15/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-84S	SSHS-MW-84S-04152024	4/15/2024	1801726651	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-85I	MW-85I	7/15/2021	180-124580-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-85I	MW-85I	9/2/2021	180-126608-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-85I	SSHS-MW-85I-04222024	4/22/2024	1801730541	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-86I	MW-86I	7/13/2021	180-124378-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-86I	MW-86I	9/1/2021	180-126593-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-86I	SSHS-MW-86I-04042024	4/4/2024	1801719081	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-87I	MW-87I	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	< 0.48 U	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-87I	MW-87I	9/2/2021	180-126608-1	10	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-87I	SSHS-MW-87I-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 UT	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-88I	MW-88I	7/15/2021	180-124580-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 UJ
MW-88I	MW-88I	9/2/2021	180-126608-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-88I	SSHS-MW-88I-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-88S	MW-88S	7/15/2021	180-124580-1	3.7 J	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 UJ	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 UJ	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 UJ	< 0.66 U	< 0.59 U
MW-88S	MW-88S	9/2/2021	180-126608-1	6.6 J	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-88S	SSHS-MW-88S-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-89I	MW-89I	7/12/2021	180-124354-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-89I	MW-89I	9/1/2021	180-126593-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-89I	SSHS-MW-89I-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 UT	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 UT	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-89S	MW-89S	7/12/2021	180-124354-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-89S	MW-89S	9/1/2021	180-126593-1	< 5.4 R	< 0.42 R	< 0.54 R	< 0.17 R	< 0.76 R	< 0.42 R	< 0.59 R	< 0.26 R	< 0.38 R	< 0.39 R	< 0.83 R	< 0.47 R	< 0.63 R	< 0.48 R	< 0.91 R	< 2.6 R	< 0.41 R	< 0.35 R	< 0.48 R	< 0.45 R	< 0.41 R	< 0.41 R	< 0.47 R	< 0.21 R	< 0.49 R	< 0.33 R	< 0.46 R	< 0.51 R	< 0.47 R	< 0.61 R
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-8I	MW-8I	7/1/2021	180-123971-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 UJ	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 UJ	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-8I	DUP-1	8/30/2021	180-126485-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-8I	MW-8I	8/30/2021	180-126485-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-8S	MW-8	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	461.9	-	-	-
MW-8S	MW-8	6/19/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2500	-	-	-
MW-8S	MW-8	7/23/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3000	-	-	-
MW-8S	MW-8	5/20/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2900	-	-	-
MW-8S	MW-8	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	2900	< 5 U	< 5 U	< 5 U
MW-8S	MW-8	9/24/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2800	-	-	-
MW-8S	MW-8	9/24/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U
MW-8S	MW-8-D20	9/24/2003	-	< 400 U	< 100 U	-	< 100 U	< 100 U	-	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	-	-	< 100 U	-	-	-	-	-	-	< 100 U	< 100 U	< 100 U	-	2800	< 100 U	< 100 U	< 100 U
MW-8S	MW-8	6/1/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4800	-	-	-
MW-8S	MW-8	12/30/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3200	-	-	-
MW-8S	MW-8	6/28/2005	-	72	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 J	-	-	-	-	-	-	-	-	-	-	220	-	-	-
MW-8S	MW-8	12/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	880	-	-	-	-	-	-	-	-	-	-	2900	-	-	-
MW-8S	MW-8	5/25/2006	-	300	-	-	-	-	-	-	-	-	-	-	-	-	-	-	300	-	-	-	-	-	-	-	-	-	-	4300	-	-	-
MW-8S	MW-8	7/12/2007	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	470	-	-	-
MW-8S	MW-8	8/20/2014	180-36053-1	< 13 U	< 0.53 U	< 0.9 U	< 0.65 U	< 0.96 U	< 1.6 U	< 1.1 U	< 0.68 U	< 0.68 U	< 0.68 U	< 1.1 U	< 0.85 U	< 1.4 U	< 1.3 U	< 0.7 U	1 J	< 0.9 U	< 0.96 U	< 0.76 U	< 0.53 U	< 1 U	-	< 0.58 U	< 1.1 U	< 1.5 U	-	77 J	< 0.85 U	< 0.47 U	< 0.93 U
MW-8S	MW-8	8/20/2014	180-36053-1	< 2.5 U	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	0.33 J	< 0.21 U	< 0.3 U	-	-	0.51 J	< 0.095 U	< 0.19 U
MW-8S	MW-8S	2/18/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	6.1 J	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	43	42	< 0.67 U	< 0.66 U	< 0.59 U
MW-8S	MW-8S	7/12/2021	180-124354-1	< 17 U	< 3 U	< 3.1 U	< 3.2 U	< 4.9 U	< 4.4 U	< 4.4 U	< 4.4 U	< 2.5 U	< 4.2 U	< 4.5 U	< 3 U	< 4.5 U	< 3.2 U	< 4.4 U	< 4.4 U	< 2.5 U	< 4.2 U	< 1.8 U	< 2.5 U	< 2.7 U	-	< 1.5 U	< 2.9 U	< 2.8 U	29	29	< 3.4 U	< 3.3 U	< 3 U
MW-8S	SSHS-MW-8S-04052024	4/5/2024	1801720021	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	3.2	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	10	10	< 0.67 U	< 0.66 U	< 0.59 U
MW-90I	MW-90I	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-90I	MW-90I	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-90S	MW-90S	9/8/2021	180-126846-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-90S	MW-90S	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-91I	MW-91I	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-91I	MW-91I	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-91S	MW-91S	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-91S	MW-91S	11/2/2021	180-129534-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-92I	MW-92I	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-92I	MW-92I	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-92I	SSHS-MW-92I-04082024	4/8/2024	1801720411	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-92S	MW-92S	9/10/2021	180-126939-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-92S	MW-92S	10/28/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-92S	SSHS-MW-92S-04052024	4/5/2024	1801720031	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-93I	DUP-4	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-93I	MW-93I	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-93I	MW-93I	10/29/2021	180-129376-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-93I	SSHS-DUP-08-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-93I	SSHS-MW-93I-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-93S	MW-93S	9/9/2021	180-126905-1	12	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-93S	MW-93S	10/29/2021	180-129376-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-93S	SSHS-MW-93S-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-94I	MW-94I	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	0.74 J	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-94I	MW-94I	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-94S	MW-94S	9/9/2021	180-126905-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 U	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-94S	MW-94S	10/27/2021	180-129230-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2			5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-87I	MW-87I	9/2/2021	180-126608-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-87I	SSHS-MW-87I-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-88I	MW-88I	7/15/2021	180-124580-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 1 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-88I	MW-88I	9/2/2021	180-126608-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-88I	SSHS-MW-88I-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-88S	MW-88S	7/15/2021	180-124580-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	0.47 J	< 0.48 U	< 0.41 U	< 0.89 U
MW-88S	MW-88S	9/2/2021	180-126608-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-88S	SSHS-MW-88S-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-89I	MW-89I	7/12/2021	180-124354-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 1 U	< 0.41 U	< 0.89 U
MW-89I	MW-89I	9/1/2021	180-126593-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-89I	SSHS-MW-89I-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 UT	< 0.48 U	< 0.41 U	< 0.89 U
MW-89S	MW-89S	7/12/2021	180-124354-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 1 U	< 0.41 U	< 0.89 U
MW-89S	MW-89S	9/1/2021	180-126593-1	< 0.67 R	< 0.42 R	< 0.41 R	< 1.1 R	< 0.49 R	< 1.7 R	< 0.33 R	< 1.2 R	< 0.99 R	< 0.47 R	< 0.45 R	< 0.6 R	< 0.44 R	< 0.44 R	< 0.54 R	< 0.77 R	< 0.48 R	< 0.48 R	< 0.44 R	< 0.45 R	< 0.45 R	< 0.42 R	< 0.42 R	< 0.42 R
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-8I	MW-8I	7/1/2021	180-123971-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-8I	DUP-1	8/30/2021	180-126485-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-8I	MW-8I	8/30/2021	180-126485-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	2.2	1.0	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-8S	MW-8	4/2/2002	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	2.1	-	ND	-	ND	-	-	-
MW-8S	MW-8	6/19/2002	-	-	-	14000 J	-	-	-	-	-	-	-	-	-	13	-	-	-	-	-	9	-	-	-	-	-
MW-8S	MW-8	7/23/2002	-	-	-	1900	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-8S	MW-8	5/20/2003	-	-	-	1300	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-8S	MW-8	5/20/2003	-	< 5 U	< 5 U	1300	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-8S	MW-8	9/24/2003	-	-	-	980	-	-	-	-	-	-	-	-	-	10	-	-	-	ND	-	ND	-	ND	-	-	-
MW-8S	MW-8	9/24/2003	-	< 5 U	< 5 U	-	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	10	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-8S	MW-8-D20	9/24/2003	-	< 100 U	< 100 U	980	< 200 U	-	-	-	< 200 U	< 200 U	-	< 100 U	< 100 U	< 100 U	< 100 U	-	-	< 100 U	< 100 U	< 100 U	-	< 20 U	< 100 U	< 100 U	-
MW-8S	MW-8	6/1/2004	-	-	-	700	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-8S	MW-8	12/30/2004	-	-	-	330	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-8S	MW-8	6/28/2005	-	-	-	ND	-	-	-	-	-	-	-	-	-	2 J	-	-	-	ND	-	3 J	-	ND	-	-	-
MW-8S	MW-8	12/28/2005	-	-	-	890	-	-	-	-	-	-	-	-	-	11	-	-	-	1.8	-	8.6	-	ND	-	-	-
MW-8S	MW-8	5/25/2006	-	-	-	-	-	-	-	-	-	-	-	-	-	300	-	-	-	300	-	300	-	200	-	-	-
MW-8S	MW-8	7/12/2007	-	-	-	670	-	-	-	-	-	-	-	-	-	4.2	-	-	-	0.55	-	5.8	-	ND	-	-	-
MW-8S	MW-8	8/20/2014	180-36053-1	< 0.74 U	< 1.1 U	1.7 J	< 0.8 U	< 0.82 U	< 0.69 U	< 1.3 U	< 2.7 U	< 2.6 U	< 0.92 U	< 0.48 U	< 1 U	1.2 J	< 0.75 U	< 0.77 U	< 1.4 U	< 1.4 U	< 1 U	< 0.72 U	< 0.99 U	1.2 J	< 2 U	< 0.55 U	-
MW-8S	MW-8	8/20/2014	180-36053-1	< 0.15 U	< 0.23 U	1.8	< 0.16 U	< 0.16 U	< 0.14 U	0.94 J	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	1.3	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	0.57 J	< 0.2 U	1.6	< 0.41 U	< 0.11 U	-
MW-8S	MW-8S	2/18/2021	180-117476-1	< 0.58 U	< 0.51 U	26	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	2.2	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	1.3	< 0.87 U	2.6	-	< 0.41 U	< 0.89 U
MW-8S	MW-8S	7/12/2021	180-124354-1	< 2.9 U	< 2.5 U	11	< 16 U	< 1.7 U	< 8.4 U	< 3 U	< 13 U	< 15 U	< 3 U	< 2.4 U	< 3 U	< 2.3 U	< 2.3 U	< 5.3 U	< 3.9 U	< 3 U	< 2.3 U	< 3.4 U	< 4.4 U	2.5 J	2.4	< 2 U	< 4.5 U
MW-8S	SSHS-MW-8S-04052024	4/5/2024	1801720021	< 0.58 U	< 0.51 U	9.2	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.50 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	0.78 J	< 0.48 U	< 0.41 U	< 0.89 U
MW-90I	MW-90I	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-90I	MW-90I	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-90S	MW-90S	9/8/2021	180-126846-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-90S	MW-90S	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-91I	MW-91I	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-91I	MW-91I	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-91S	MW-91S	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-91S	MW-91S	11/2/2021	180-129534-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-92I	MW-92I	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-92I	MW-92I	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	0.53 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-92I	SSHS-MW-92I-04082024	4/8/2024	1801720411	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-92S	MW-92S	9/10/2021	180-126939-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	0.46 J	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-92S	MW-92S	10/28/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-92S	SSHS-MW-92S-04052024	4/5/2024	1801720031	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-93I	DUP-4	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-93I	MW-93I	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-93I	MW-93I	10/29/2021	180-129376-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-93I	SSHS-DUP-08-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-93I	SSHS-MW-93I-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-93S	MW-93S	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-93S	MW-93S	10/29/2021	180-129376-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-93S	SSHS-MW-93S-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-94I	MW-94I	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-94I	MW-94I	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-94S	MW-94S	9/9/2021	180-126905-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	-	< 0.42 U	< 0.42 U
MW-94S	MW-94S	10/27/2021	180-129230-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1.2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722811	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624601	30	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653531	7.0	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682361	16	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95I	SSHS-MW-95I-04092024	4/9/2024	1801721201	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624601	54	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653531	8.9	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682361	17	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-95S	SSHS-MW-95S-04092024	4/9/2024	1801721201	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-96	SSHS-MW-96-09122023	9/12/2023	1801624601	16	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653531	9.1	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.91 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682361	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.63 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721201	4.4 J	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	1.2	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559471	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-97	SSHS-MW-97-09122023	9/12/2023	1801624601	27	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653531	11	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682361	14	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721201	3.7 J	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.74 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98I	DUP-01	9/1/2022	1801438881	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98I	MW-98I	9/1/2022	1801438881	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98I	SSHS-MW-98I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.60 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98S	MW-98S	9/1/2022	1801438881	< 3.4 UT	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-98S	SSHS-MW-98S-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-99I	SSHS-MW-99I-09132023	9/13/2023	1801624611	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-99I	SSHS-MW-99I-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.81 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624611	< 3.4 UT	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 UJ	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 UJ	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721871	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	0.88 J	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-9I	MW-9I	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-9I	MW-9I	8/31/2021	180-126501-1	< 5.4 U	< 0.42 U	< 0.54 U	< 0.17 U	< 0.76 UJ	< 0.42 U	< 0.59 U	< 0.26 U	< 0.38 U	< 0.39 U	< 0.83 U	< 0.47 U	< 0.63 U	< 0.48 U	< 0.91 UJ	< 2.6 U	< 0.41 U	< 0.35 U	< 0.48 U	< 0.45 U	< 0.41 U	< 0.41 U	< 0.47 U	< 0.21 U	< 0.49 U	< 0.33 U	< 0.46 U	< 0.51 U	< 0.47 U	< 0.61 U
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733271	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-9S	MW-9	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-9S	MW-9	2/20/2021	180-117476-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-9S	MW-9	7/14/2021	180-124487-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-9S	SSHS-MW-9S-04052024	4/5/2024	1801720021	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 U	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
MW-D	MW-D	5/5/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	20	-	-	-
MW-D	D1	5/5/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	20	< 5 U	< 5 U	< 5 U
MW-D	D1-D2.5	5/5/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	17	< 5 U	< 5 U	< 5 U
MW-D	D2	5/5/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	390	2.5 J	< 5 U	< 5 U
MW-D	D2-D10	5/5/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	420	< 5 U	< 5 U	< 5 U
MW-D	D3	5/5/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	56	< 5 U	< 5 U	< 5 U
MW-D	D4	5/5/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	1300	< 5 U	< 5 U	< 5 U
MW-D	MW-D	5/20/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	99	-	-	-
MW-D	MW-D	5/20/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	99	< 5 U	< 5 U	< 5 U
MW-D	MW-D-D2.5	5/20/2003	-	< 50 U	< 12.5 U	-	< 12.5 U	< 12.5 U	-	< 25 U	< 12.5 U	< 12.5 U	< 12.5 U	< 12.5 U	< 12.5 U	< 12.5 U	-	-	< 12.5 U	-	-	-	-	-	-	< 12.5 U	< 12.5 U	< 12.5 U	-	86	< 12.5 U	< 12.5 U	< 12.5 U
MW-D	MW-D	9/24/2003	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-D	MW-D	9/24/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
MW-D	MW-D	6/1/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-D	MW-D	12/30/2004	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-D	MW-D	12/28/2005	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	ND	-	-	-
MW-D	MW-D	7/12/2007	-	ND	-	-	-	-	-	-	-	-	-	-	-	-	-	-	ND	-	-	-	-	-	-	-	-	-	-	1	-	-	-
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	8/4/2021	1801253661	< 3.4 U	< 0.60 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.50 U	< 0.84 U	< 0.90 UT	< 0.60 U	< 0.90 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.50 U	< 0.83 U	< 0.36 U	< 0.50 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B2090A	SSHS-B2090A	5/22/2019	180-90525-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.7 J	< 0.9 U	< 0.63 UJ	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B23	B23	5/9/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1 J	-	-	-
SSHS-B2542A	SSHS-B2542A	5/22/2019	180-90525-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 UJ	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B2544	SSHS-B2544-GW	10/30/2018	180-83544-1	13	< 0.13 U	< 0.14 U	< 0.17 U	< 0.76 U	< 0.42 U	< 0.28 U	< 0.26 U	< 0.14 U	< 0.39 U	< 0.83 U	0.81 J	< 0.2 UJ	< 0.24 U	< 0.91 U	< 2.6 U	< 0.12 U	< 0.35 U	< 0.15 U	< 0.15 U	< 0.16 U	< 0.16 U	< 0.17 U	< 0.21 U	< 0.19 U	0.41 J	0.41 J	< 0.19 U	< 0.15 U	< 0.61 U
SSHS-B2544A	SSHS-B2544A	6/25/2019	180-91951-2	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 UJ	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B2629	SSHS-B2629	4/25/2019	180-89520-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B26-A	SSHS-B26-A-GW-18-22	8/14/2014	180-35818-2	4.7 J	0.11 J	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B2752	SSHS-B2752	4/25/2019	180-89520-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B2819	SSHS-B2819	5/22/2019	180-90525-1	6.3	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 UJ	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	5.2	4.5	0.73 J	< 0.66 U	< 0.59 U
SSHS-B2978b	DUP-03	11/12/2019	180-98730-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B2978b	SSHS-B2978b	11/12/2019	180-98730-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B29-A	SSHS-B29-A-GW-18-22	8/13/2014	180-35776-2	1200	< 2.6 U	< 4.5 U	< 3.3 U	< 4.8 U	< 7.8 U	< 5.3 U	< 3.4 U	< 3.4 U	< 3.4 U	< 5.4 U	< 4.3 U	< 7.1 U	< 6.4 U	< 3.5 U	< 3.1 U	< 4.5 U	< 4.8 U	< 3.8 U	< 2.6 U	< 5.2 U	-	< 2.9 U	< 5.3 U	< 7.4 U	-	< 5.9 U	< 4.2 U	< 2.4 U	< 4.7 U
SSHS-B3090	SSHS-B3090	8/8/2019	180-93940-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3092A	SSHS-B3092	8/8/2019	180-93940-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722811	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653531	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95I	SSHS-MW-95I-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653531	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-95S	SSHS-MW-95S-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	2.8	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	0.61 J	< 0.45 U	9.1	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-96	SSHS-MW-96-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	5.4	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	1.8	< 0.46 U	< 1.1 U	< 0.77 U	1.1	< 0.45 U	27	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653531	< 0.58 U	< 0.51 U	0.93 J	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.92 J	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.60 U	< 0.45 U	5.6 J+	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682361	< 0.58 U	< 0.51 U	13	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	2.4	< 0.46 U	< 1.1 U	< 0.77 U	1.9	< 0.45 U	47	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	13	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	3.3	< 0.46 U	< 1.1 U	< 0.77 U	2.3	< 0.45 U	56	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559471	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-97	SSHS-MW-97-09122023	9/12/2023	1801624601	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653531	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682361	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721201	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98I	DUP-01	9/1/2022	1801438881	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	2.5	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98I	MW-98I	9/1/2022	1801438881	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.56 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	2.6	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	2.8	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98I	SSHS-MW-98I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	0.70 J	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	4.1	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98S	MW-98S	9/1/2022	1801438881	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UT	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 UT	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	0.88 J	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	1.5	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-98S	SSHS-MW-98S-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	1.2	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-99I	SSHS-MW-99I-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	5.4	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-99I	SSHS-MW-99I-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	6.8	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624611	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 UJ	< 0.61 U	< 2.6 UJ	< 3.1 UJ	< 0.59 UJ	< 0.47 U	< 0.60 UJ	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 UJ	3.0	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721871	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	2.5	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-9I	MW-9I	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-9I	MW-9I	8/31/2021	180-126501-1	< 0.67 U	< 0.42 U	< 0.41 U	< 1.1 U	< 0.49 U	< 1.7 U	< 0.33 U	< 1.2 U	< 0.99 U	< 0.47 U	< 0.45 U	< 0.6 U	< 0.44 U	< 0.44 U	< 0.54 U	< 0.77 U	< 0.48 U	< 0.48 U	< 0.44 U	< 0.45 U	< 0.45 U	< 0.42 U	< 0.42 U	< 0.42 U
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733271	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-9S	MW-9	5/20/2003	-	< 5 U	< 5 U	5.4	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-9S	MW-9	2/20/2021	180-117476-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-9S	MW-9	7/14/2021	180-124487-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
MW-9S	SSHS-MW-9S-04052024	4/5/2024	1801720021	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
MW-D	MW-D	5/5/2003	-	-	-	370	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-D	D1	5/5/2003	-	< 5 U	< 5 U	-	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	1 J	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	1.1 J	1.1 J	-
MW-D	D1-D2.5	5/5/2003	-	< 5 U	< 5 U	370	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-D	D2	5/5/2003	-	< 5 U	< 5 U	-	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	3.3 J	3.9 J	-
MW-D	D2-D10	5/5/2003	-	< 5 U	< 5 U	1500	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	50 J	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-D	D3	5/5/2003	-	< 5 U	< 5 U	340	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-D	D4	5/5/2003	-	< 5 U	< 5 U	3400	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-D	MW-D	5/20/2003	-	-	-	310	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-D	MW-D	5/20/2003	-	< 5 U	< 5 U	-	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-D	MW-D-D2.5	5/20/2003	-	< 12.5 U	< 12.5 U	310	< 25 U	-	-	-	< 25 U	< 25 U	-	< 12.5 U	< 12.5 U	< 12.5 U	< 12.5 U	-	-	< 12.5 U	< 12.5 U	< 12.5 U	-	< 2.5 U	< 12.5 U	< 12.5 U	-
MW-D	MW-D	9/24/2003	-	-	-	35	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-D	MW-D	9/24/2003	-	< 5 U	< 5 U	35	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
MW-D	MW-D	6/1/2004	-	-	-	28	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-D	MW-D	12/30/2004	-	-	-	22	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	ND	-	ND	-	-	-
MW-D	MW-D	12/28/2005	-	-	-	2.4	-	-	-	-	-	-	-	-	-	0.37	-	-	-	ND	-	0.52	-	ND	-	-	-
MW-D	MW-D	7/12/2007	-	-	-	2.3	-	-	-	-	-	-	-	-	-	ND	-	-	-	ND	-	0.53	-	ND	-	-	-
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	8/4/2021	1801253661	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.60 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.60 U	< 0.45 U	< 0.69 U	< 0.87 UT	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B2090A	SSHS-B2090A	5/22/2019	180-90525-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	7.6	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B23	B23	5/9/2000	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2 J	-	-	-	-	-
SSHS-B2542A	SSHS-B2542A	5/22/2019	180-90525-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B2544	SSHS-B2544-GW	10/30/2018	180-83544-1	< 0.67 U	< 0.11 U	< 0.41 U	0.72 J	1.2	< 1.7 U	< 0.33 U	2.4 J	< 0.42 U	< 0.07 U	< 0.1 U	1.4	< 0.15 U	0.21 J	< 0.54 U	< 0.26 U	< 0.24 U	< 0.09 U	20	< 0.45 U	< 0.2 U	0.61 J	0.27 J	0.88 J
SSHS-B2544A	SSHS-B2544A	6/25/2019	180-91951-2	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	6.3	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B2629	SSHS-B2629	4/25/2019	180-89520-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B26-A	SSHS-B26-A-GW-18-22	8/14/2014	180-35818-2	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	0.18 J	< 0.14 U	0.58 J	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	< 0.15 U	0.24 J	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B2752	SSHS-B2752	4/25/2019	180-89520-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B2819	SSHS-B2819	5/22/2019	180-90525-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	25	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B2978b	DUP-03	11/12/2019	180-98730-1	< 0.58 U	-	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	10	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B2978b	SSHS-B2978b	11/12/2019	180-98730-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	10 J	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B29-A	SSHS-B29-A-GW-18-22	8/13/2014	180-35776-2	< 3.7 U	< 5.7 U	< 8 U	< 4 U	< 4.1 U	< 3.4 U	< 6.5 U	< 14 U	< 13 U	< 4.6 U	< 2.4 U	< 5 U	< 3.7 U	< 3.8 U	< 3.9 U	< 6.8 U	< 7.2 U	< 5 U	< 3.6 U	< 5 U	< 5.7 U	< 10 U	< 2.7 U	-
SSHS-B3090	SSHS-B3090	8/8/2019	180-93940-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	0.71 J	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3092A	SSHS-B3092	8/8/2019	180-93940-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	10	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
SSHS-B3093	B3093	7/27/2019	180-93333-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3094	SSHS-B3094	8/9/2019	180-93940-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3200A	DUP-01	9/15/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3200A	SSHS-B3200a	9/15/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3200B	SSHS-B3200b	9/15/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3201A	SSHS-B3201a	9/15/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3201B	SSHS-B3201b	9/14/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3202A	SSHS-B3202a	9/14/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3202B	SSHS-B3202b	9/14/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3203A	SSHS-3203a	9/13/2019	180-95715-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3203B	SSHS-3203b	9/13/2019	180-95715-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3204A	SSHS-3204a	9/13/2019	180-95715-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3204B	SSHS-3204b	9/13/2019	180-95715-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 UJ	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3205A	SSHS-B3205a	9/14/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3205B	SSHS-B3205b	9/14/2019	180-95745-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.63 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3555	SSHS-RI-B3555 TEMP	1/16/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3556	SSHS-RI-B3556-TEMP	1/14/2021	180-116000-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3557	SSHS-RI-B3557 TEMP	1/13/2021	180-115925-2	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3558	SSHS-RI-B3558-TEMP	1/15/2021	180-116071-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3559	SSHS-RI-B3559 TEMP	1/16/2021	180-116200-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3560	SSHS-RI-B3560R TEMP	1/19/2021	180-116200-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3561	SSHS-RI-B3561R TEMP	1/18/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3561	SSHS-RI-DUP27	1/18/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3562	DUP-28	1/14/2021	180-116000-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3562	SSHS-RI-B3562-TEMP	1/14/2021	180-116000-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3563	SSHS-RI-B3563-TEMP	1/14/2021	180-116000-1	< 3.4 U	< 0.6 U	< 0.63 UJ	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3563I	SSHS-RI-B3563I TEMP	1/16/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3564	SSHS-RI-B3564R TEMP	1/18/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3565	SSHS-RI-B3565-TEMP	1/14/2021	180-116000-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	0.91 J	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3566	SSHS-RI-B3566R TEMP	1/18/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B3571	SSHS-RI-B3571 TEMP	1/16/2021	180-116110-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-B510	SSHS-B510	9/20/2016	180-58901-1	< 25 U	< 2.6 U	< 3.8 U	< 2.3 U	< 2.9 U	< 3.6 U	< 1.8 U	< 2.4 U	< 3.1 U	< 4 U	< 2.6 U	< 2.7 U	< 2.3 U	< 2.8 U	< 1.9 U	< 3.6 U	< 2.9 U	6.7 J	< 2.8 U	< 2.5 U	< 2.7 U	-	< 2.4 U	< 2.5 U	< 2.9 U	15	15	< 2.9 U	< 2.3 U	< 2.1 U
SSHS-B572A	SSHS-B572A	9/2/2016	180-58309-2	< 2.5 U	< 0.26 U	< 0.38 U	< 0.23 U	< 0.29 U	< 0.36 U	< 0.18 UJ	< 0.24 U	< 0.31 U	< 0.4 U	< 0.26 U	0.88 J	< 0.23 U	< 0.28 U	< 0.19 U	< 0.36 U	< 0.29 U	< 0.27 U	< 0.28 U	< 0.25 U	< 0.27 U	-	< 0.24 U	< 0.25 U	< 0.29 U	< 0.55 U	< 0.29 U	< 0.29 U	< 0.23 U	< 0.21 U
SSHS-B575A	SSHS-B575A	9/19/2016	180-58899-1	< 2.5 U	< 0.26 U	< 0.38 U	< 0.23 U	< 0.29 U	< 0.36 U	< 0.18 U	< 0.24 U	< 0.31 U	< 0.4 U	< 0.26 U	< 0.27 U	< 0.23 U	< 0.28 U	< 0.19 U	< 0.36 U	< 0.29 U	< 0.27 U	< 0.28 U	< 0.25 U	< 0.27 U	-	< 0.24 U	< 0.25 U	< 0.29 U	< 0.55 U	< 0.29 U	< 0.29 U	< 0.23 U	< 0.21 U
SSHS-B575B	SSHS-B575B	9/19/2016	180-58899-1	11	< 0.26 U	< 0.38 U	< 0.23 U	< 0.29 U	< 0.36 U	< 0.18 U	< 0.24 U	< 0.31 U	< 0.4 U	< 0.26 U	< 0.27 U	< 0.23 U	< 0.28 U	< 0.19 U	< 0.36 U	< 0.29 U	< 0.27 U	< 0.28 U	< 0.25 U	< 0.27 U	-	< 0.24 U	< 0.25 U	< 0.29 U	< 0.55 U	< 0.29 U	< 0.29 U	< 0.23 U	< 0.21 U
SSHS-B575C	PS-FD-54	9/19/2016	180-58899-1	13	< 0.26 U	< 0.38 U	< 0.23 U	< 0.29 U	< 0.36 U	< 0.18 U	< 0.24 U	< 0.31 U	< 0.4 U	< 0.26 U	< 0.27 U	< 0.23 U	< 0.28 U	< 0.19 U	< 0.36 U	< 0.29 U	< 0.27 U	< 0.28 U	< 0.25 U	< 0.27 U	-	< 0.24 U	< 0.25 U	< 0.29 U	< 0.55 U	< 0.29 U	< 0.29 U	< 0.23 U	< 0.21 U
SSHS-B575C	SSHS-B575C	9/21/2016	180-58975-1	5.3 J	< 0.26 U	< 0.38 U	< 0.23 U	< 0.29 U	< 0.36 U	< 0.18 U	< 0.24 U	< 0.31 U	< 0.4 U	< 0.26 U	< 0.27 U	< 0.23 U	< 0.28 U	< 0.19 U	< 0.36 U	< 0.29 U	< 0.27 U	< 0.28 U	< 0.25 U	< 0.27 U	-	< 0.24 U	< 0.25 U	< 0.29 U	< 0.55 U	< 0.29 U	< 0.29 U	< 0.23 U	< 0.21 U
SSHS-B92	SSHS-B92-GW-18-22	8/12/2014	180-35729-1	< 2.5 U	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	1.8	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B93	DUP-3-GW	8/12/2014	180-35729-1	12	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B93	SSHS-B93-GW-18-22	8/12/2014	180-35729-1	6.8 J	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B94	SSHS-B94-GW-18-22	8/12/2014	180-35729-1	< 2.5 U	0.33 J	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	0.25 J	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B95	SSHS-B95-GW-18-22	8/12/2014	180-35729-1	6.7 J	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B96	SSHS-B96-GW-18-22	8/12/2014	180-35729-1	< 2.5 U	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B97	SSHS-B97-GW-18-22	8/13/2014	180-35776-2	32 J	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B98	SSHS-B98-GW-18-22	8/13/2014	180-35776-2	40 J	< 0.11 U	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-B99	SSHS-99-GW-17-21	8/13/2014	180-35776-2	33 J	0.26 J	< 0.18 U	< 0.13 U	< 0.19 U	< 0.31 U	< 0.21 U	< 0.14 U	< 0.14 U	< 0.14 U	< 0.21 U	< 0.17 U	< 0.28 U	< 0.25 U	< 0.14 U	< 0.13 U	< 0.18 U	< 0.19 U	< 0.15 U	< 0.11 U	< 0.21 U	-	< 0.12 U	< 0.21 U	< 0.3 U	-	< 0.24 U	< 0.17 U	< 0.095 U	< 0.19 U
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	7/1/2021	180-123971-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 UJ	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 UJ	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	4/9/2021	180-119810-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	0.95 J	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3860I TEMP	DUP-GW-02	4/15/2021	180-120162-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	4/15/2021	180-120162-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	4/13/2021	180-119930-1	< 3.4 U	< 0.6 UJ	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 UJ	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 UJ	< 1.3 UJ	< 0.71 UJ	< 0.67 UJ	< 0.66 U	< 0.59 U
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	4/9/2021	180-119810-1	5 J	< 0.6 UJ	< 0.63 UJ	< 0.64 U	< 0.98 U	< 0.89 R	< 0.88 R	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 R	< 0.6 U	< 0.9 R	< 0.63 U	< 0.89 U	< 0.89 UJ	< 0.5 U	< 0.83 R	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 UJ	< 0.57 U	< 0.55 UJ	< 1.3 UJ	< 0.71 U	< 0.67 UJ	< 0.66 U	< 0.59 U
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	4/9/2021	180-119810-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	4/6/2021	180-119589-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	4/7/2021	180-119649-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	4/14/2021	180-120029-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	4/14/2021	180-120029-1	6	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	1.1	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	5/14/2021	180-121703-1	< 3.4 R	< 0.6 R	< 0.63 R	< 0.64 R	< 0.98 R	< 0.89 R	< 0.88 R	< 0.88 R	< 0.5 R	< 0.84 R	< 0.9 R	< 0.6 R	< 0.9 R	< 0.63 R	< 0.89 R	< 0.89 R	< 0.5 R	< 0.83 R	< 0.36 R	< 0.5 R	< 0.54 R	-	< 0.31 R	< 0.57 R	< 0.55 R	< 1.3 R	< 0.71 R	< 0.67 R	< 0.66 R	< 0.59 R
SSHS-RI-B3886-TEMP	DUP-GW-01	5/19/2021	180-121897-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.62 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	5/19/2021	180-121897-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 UJ	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	5/11/2021	180-121472-1	< 3.4 U	< 0.6 U	< 0.63 UJ	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	0.73 J	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 UJ	< 1.3 U	< 0.71 U	< 0.67 UJ	< 0.66 U	< 0.59 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	5/11/2021	180-121472-1	< 3.4 U	< 0.6 U	< 0.63 UJ	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 UJ	< 1.3 U	< 0.71 U	< 0.67 UJ	< 0.66 U	< 0.59 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	5/13/2021	180-121702-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 UJ	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 UJ	< 0.57 UJ	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	5/12/2021	180-121546-1	< 3.4 UJ	< 0.6 UJ	< 0.63 UJ	< 0.64 UJ	< 0.98 UJ	< 0.89 UJ	< 0.88 UJ	< 0.88 UJ	< 0.5 UJ	< 0.84 UJ	< 0.9 UJ	< 0.6 UJ	< 0.9 UJ	< 0.63 UJ	< 0.89 UJ	< 0.89 UJ	< 0.5 UJ	< 0.83 UJ	< 0.36 UJ	< 0.5 UJ	< 0.54 UJ	-	< 0.31 UJ	< 0.57 UJ	< 0.55 UJ	< 1.3 UJ	< 0.71 UJ	< 0.67 UJ	< 0.66 UJ	< 0.59 UJ
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	7/23/2021	180-124918-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	7/26/2021	180-124974-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 UJ	< 0.89 U	< 0.88 U	< 0.88 UJ	< 0.5 U	< 0.84 UJ	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	7/28/2021	180-125087-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 UJ	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4152I-TEMP	DUP-01	7/28/2021	180-125087-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 UJ	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
SSHS-B3093	B3093	7/27/2019	180-93333-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3094	SSHS-B3094	8/9/2019	180-93940-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3200A	DUP-01	9/15/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3200A	SSHS-B3200a	9/15/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3200B	SSHS-B3200b	9/15/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3201A	SSHS-B3201a	9/15/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3201B	SSHS-B3201b	9/14/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3202A	SSHS-B3202a	9/14/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3202B	SSHS-B3202b	9/14/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3203A	SSHS-3203a	9/13/2019	180-95715-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3203B	SSHS-3203b	9/13/2019	180-95715-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3204A	SSHS-3204a	9/13/2019	180-95715-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3204B	SSHS-3204b	9/13/2019	180-95715-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3205A	SSHS-B3205a	9/14/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3205B	SSHS-B3205b	9/14/2019	180-95745-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 0.83 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.88 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3555	SSHS-RI-B3555 TEMP	1/16/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3556	SSHS-RI-B3556-TEMP	1/14/2021	180-116000-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3557	SSHS-RI-B3557 TEMP	1/13/2021	180-115925-2	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 UJ	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3558	SSHS-RI-B3558-TEMP	1/15/2021	180-116071-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3559	SSHS-RI-B3559 TEMP	1/16/2021	180-116200-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3560	SSHS-RI-B3560R TEMP	1/19/2021	180-116200-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3561	SSHS-RI-B3561R TEMP	1/18/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3561	SSHS-RI-DUP27	1/18/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3562	DUP-28	1/14/2021	180-116000-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3562	SSHS-RI-B3562-TEMP	1/14/2021	180-116000-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3563	SSHS-RI-B3563-TEMP	1/14/2021	180-116000-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3563I	SSHS-RI-B3563I TEMP	1/16/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	3.1 J	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3564	SSHS-RI-B3564R TEMP	1/18/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3565	SSHS-RI-B3565-TEMP	1/14/2021	180-116000-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3566	SSHS-RI-B3566R TEMP	1/18/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B3571	SSHS-RI-B3571 TEMP	1/16/2021	180-116110-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-B510	SSHS-B510	9/20/2016	180-58901-1	< 2.4 U	< 2.7 U	220	< 7.4 U	< 2.7 U	< 15 U	< 2.6 U	< 12 U	< 5.9 U	< 2.4 U	< 2.6 U	< 3.5 U	< 2.7 U	< 2.8 U	< 1.9 U	< 2.7 U	< 2.2 U	< 3.5 U	< 2.6 U	< 3.1 U	< 3.2 U	< 2.7 U	< 2.4 U	< 4.8 U
SSHS-B572A	SSHS-B572A	9/2/2016	180-58309-2	< 0.24 U	< 0.27 U	< 0.27 U	< 0.74 U	< 0.27 U	< 1.5 U	< 0.26 U	< 1.2 U	< 0.59 U	< 0.24 U	< 0.26 U	< 0.35 U	0.28 J	< 0.28 U	< 0.19 U	< 0.27 U	< 0.22 U	< 0.35 U	0.43 J	< 0.31 U	< 0.32 U	< 0.27 U	< 0.24 U	< 0.48 U
SSHS-B575A	SSHS-B575A	9/19/2016	180-58899-1	< 0.24 U	< 0.27 U	< 0.27 U	< 0.74 U	< 0.27 U	< 1.5 U	< 0.26 U	< 1.2 U	< 0.59 U	< 0.24 U	< 0.26 U	< 0.35 U	0.29 J	< 0.28 U	< 0.19 U	< 0.27 U	< 0.22 U	< 0.35 U	< 0.26 U	< 0.31 U	< 0.32 U	< 0.27 U	< 0.24 U	< 0.48 U
SSHS-B575B	SSHS-B575B	9/19/2016	180-58899-1	< 0.24 U	< 0.27 U	0.38 J	< 0.74 U	< 0.27 U	< 1.5 U	< 0.26 U	< 1.2 U	< 0.59 U	< 0.24 U	< 0.26 U	< 0.35 U	0.35 J	< 0.28 U	< 0.19 U	< 0.27 U	< 0.22 U	< 0.35 U	0.27 J	< 0.31 U	< 0.32 U	< 0.27 U	< 0.24 U	< 0.48 U
SSHS-B575C	PS-FD-54	9/19/2016	180-58899-1	< 0.24 U	< 0.27 U	0.35 J	< 0.74 U	< 0.27 U	< 1.5 U	< 0.26 U	< 1.2 U	< 0.59 U	< 0.24 U	< 0.26 U	< 0.35 U	0.41 J	< 0.28 U	< 0.19 U	< 0.27 U	< 0.22 U	< 0.35 U	< 0.26 U	< 0.31 U	< 0.32 U	< 0.27 U	< 0.24 U	< 0.48 U
SSHS-B575C	SSHS-B575C	9/21/2016	180-58975-1	< 0.24 U	< 0.27 U	< 0.27 U	< 0.74 U	< 0.27 U	< 1.5 U	< 0.26 U	< 1.2 U	< 0.59 U	< 0.24 U	< 0.26 U	< 0.35 U	0.39 J	< 0.28 U	< 0.19 U	< 0.27 U	< 0.22 U	< 0.35 U	< 0.26 U	< 0.31 U	< 0.32 U	< 0.27 U	< 0.24 U	< 0.48 U
SSHS-B92	SSHS-B92-GW-18-22	8/12/2014	180-35729-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.17 J	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	5.6	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B93	DUP-3-GW	8/12/2014	180-35729-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.27 J	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	0.62 J	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B93	SSHS-B93-GW-18-22	8/12/2014	180-35729-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.3 J	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	0.37 J	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B94	SSHS-B94-GW-18-22	8/12/2014	180-35729-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.22 J	0.36 J	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	8.9	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B95	SSHS-B95-GW-18-22	8/12/2014	180-35729-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.3 J	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	0.37 J	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B96	SSHS-B96-GW-18-22	8/12/2014	180-35729-1	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.23 J	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B97	SSHS-B97-GW-18-22	8/13/2014	180-35776-2	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	< 0.15 U	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B98	SSHS-B98-GW-18-22	8/13/2014	180-35776-2	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	< 0.55 U	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	0.18 J	< 0.15 U	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-B99	SSHS-99-GW-17-21	8/13/2014	180-35776-2	< 0.15 U	< 0.23 U	< 0.32 U	< 0.16 U	< 0.16 U	< 0.14 U	< 0.26 U	0.98 J	< 0.53 U	< 0.18 U	< 0.097 U	< 0.2 U	< 0.15 U	0.55 J	< 0.15 U	< 0.27 U	< 0.29 U	< 0.2 U	< 0.14 U	< 0.2 U	< 0.23 U	< 0.41 U	< 0.11 U	-
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	7/1/2021	180-123971-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	4/9/2021	180-119810-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	1.6	< 0.87 UJ	0.97 J	-	< 0.41 U	< 0.89 U
SSHS-RI-B3860I TEMP	DUP-GW-02	4/15/2021	180-120162-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	4/15/2021	180-120162-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	4/13/2021	180-119930-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 UJ	< 0.46 UJ	1.2 J	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 UJ	< 0.87 UJ	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	4/9/2021	180-119810-1	< 0.58 U	< 0.51 U	< 0.86 UJ	< 3.3 UJ	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 UJ	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 R	< 0.41 R	-	< 0.41 U	< 0.89 U
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	4/9/2021	180-119810-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	4/6/2021	180-119589-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 UJ	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 UJ	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 UJ	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	4/7/2021	180-119649-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 UJ	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	4/14/2021	180-120029-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	4/14/2021	180-120029-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	8.1	< 0.87 U	< 0.41 U	-	0.86 J	1.5 J
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	5/14/2021	180-121703-1	< 0.58 R	< 0.51 R	< 0.86 R	< 3.3 R	< 0.34 R	< 1.7 R	< 0.61 R	< 2.6 R	< 3.1 R	< 0.59 R	< 0.47 R	< 0.6 R	< 0.47 R	< 0.46 R	< 1.1 UJ	< 0.77 R	< 0.6 R	< 0.45 R	< 0.69 R	< 0.87 R	< 0.41 R	-	< 0.41 R	< 0.89 R
SSHS-RI-B3886-TEMP	DUP-GW-01	5/19/2021	180-121897-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	5/19/2021	180-121897-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	5/11/2021	180-121472-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 UJ	< 0.47 UJ	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	5/11/2021	180-121472-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 UJ	< 0.47 UJ	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	5/13/2021	180-121702-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	-	< 0.41 U	< 0.89 U
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	5/12/2021	180-121546-1	< 0.58 UJ	< 0.51 UJ	< 0.86 UJ	< 3.3 UJ	< 0.34 UJ	< 1.7 UJ	< 0.61 UJ	< 2.6 UJ	< 3.1 UJ	< 0.59 UJ	< 0.47 UJ	< 0.6 UJ	< 0.47 UJ	< 0.46 UJ	< 1.1 UJ	< 0.77 UJ	< 0.6 UJ	< 0.45 UJ	< 0.69 UJ	< 0.87 UJ	< 0.41 UJ	-	< 0.41 UJ	< 0.89 UJ
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	7/23/2021	180-124918-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 U	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	7/26/2021	180-124974-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	7/28/2021	180-125087-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4152I-TEMP	DUP-01	7/28/2021	180-125087-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values				50	1		50	50	5	60	5	5	50	5	7	5			5		5	3	3	3	3	5	0.6	5		5	5	1	
Location	Sample Name	Sample Date	Lab Report																														
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	7/29/2021	180-125127-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	7/28/2021	180-125087-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 UJ	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	7/27/2021	180-125052-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 UJ	< 0.89 U	< 0.88 U	< 0.88 UJ	< 0.5 U	< 0.84 UJ	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	7/27/2021	180-125052-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 UJ	< 0.89 U	< 0.88 U	< 0.88 UJ	< 0.5 U	< 0.84 UJ	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	7/26/2021	180-124974-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 UJ	< 0.89 U	< 0.88 U	< 0.88 UJ	< 0.5 U	< 0.84 UJ	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 UJ	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	7/29/2021	180-125127-1	< 3.4 U	< 0.6 U	< 0.63 U	< 0.64 U	< 0.98 U	< 0.89 U	< 0.88 U	< 0.88 U	< 0.5 U	< 0.84 U	< 0.9 U	< 0.6 U	< 0.9 U	< 0.63 U	< 0.89 U	< 0.89 U	< 0.5 U	< 0.83 U	< 0.36 U	< 0.5 U	< 0.54 U	-	< 0.31 U	< 0.57 U	< 0.55 U	< 1.3 U	< 0.71 U	< 0.67 U	< 0.66 U	< 0.59 U
SSHS-SB1	SB1	4/28/2003	-	< 20 U	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U
SSHS-SB2	SB2	4/28/2003	-	65 J	< 5 U	-	< 5 U	< 5 U	-	< 10 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	-	-	-	-	-	-	< 5 U	< 5 U	< 5 U	-	< 5 U	< 5 U	< 5 U	< 5 U

Notes
VOCs = Volatile Organic Compounds
ug/l = micrograms per liter
^+ - Continuing Calibration Verification (CCV) is outside acceptance limits, high biased.
* = LCS or LCSD is outside acceptance limits
*+ = LCS and/or LCSD is outside acceptance limits, high biased
*1 = LCS/LCSD RPD exceeds control limits
*3 = ISTD response or retention time oustide acceptable limits
B = Compound detected in method blank
E - Exceeds instrument calibration range.
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
I - Value is EMPC (estimated maximum possible concentration)
p - The %RPD between the primary and confirmation column/detector is >40%. The lower value
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value

R - The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab method used: 8260C/SW8260C/8260C_LL/SW8260D - VOCs

Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

DRAFT

TABLE 5-11
Groundwater Results - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

				trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
				ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
NYSDEC Guidance Values					5	5	50	5					10	5	5	5	5		5	5	1	5	5	2		5	5
Location	Sample Name	Sample Date	Lab Report																								
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	7/29/2021	180-125127-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	7/28/2021	180-125087-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 UJ	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	7/27/2021	180-125052-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	0.87 J	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	7/27/2021	180-125052-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	0.85 J	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	7/26/2021	180-124974-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	1.1	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	7/29/2021	180-125127-1	< 0.58 U	< 0.51 U	< 0.86 U	< 3.3 U	< 0.34 U	< 1.7 U	< 0.61 U	< 2.6 U	< 3.1 U	< 0.59 U	< 0.47 U	< 0.6 U	< 0.47 U	< 0.46 U	< 1.1 UJ	< 0.77 U	< 0.6 U	< 0.45 U	< 0.69 U	< 0.87 U	< 0.41 U	< 0.48 U	< 0.41 U	< 0.89 U
SSHS-SB1	SB1	4/28/2003	-	< 5 U	< 5 U	30 J	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-
SSHS-SB2	SB2	4/28/2003	-	< 5 U	< 5 U	12 J	< 10 U	-	-	-	< 10 U	< 10 U	-	< 5 U	< 5 U	< 5 U	< 5 U	-	-	< 5 U	< 5 U	< 5 U	-	< 1 U	< 5 U	< 5 U	-

Notes
VOCs = Volatile Organic Compounds
ug/l = micrograms per liter
^+ - Continuing Calibration Verification (CCV) is outside acceptance limits, high biased.
* = LCS or LCSD is outside acceptance limits
*+ = LCS and/or LCSD is outside acceptance limits, high biased
*1 = LCS/LCSD RPD exceeds control limits
*3 = ISTD response or retention time oustide acceptable limits
B = Compound detected in method blank
E - Exceeds instrument calibration range.
F1 = MS and/or MSD Recovery is outside acceptance limits
F2 = MS/MSD RPD exceeds control limits
I - Value is EMPC (estimated maximum possible concentration)
p - The %RPD between the primary and confirmation column/detector is >40%. The lower value
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value

R - The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab method used: 8260C/SW8260C/8260C_LL/SW8260D - VOCs

Analyte concentrations detected above NY TOGS Cleanup Objectives are presented in blue

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PERFLUORO(2-PROPOXYPROPANOIC) ACID	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7										
Location	Sample Name	Sample Date	Lab Report																														
MW-1	MW-1	2/17/2021	180-117387-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-1	MW-1	7/14/2021	180-124487-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-10	MW-10	3/24/2021	180-119009-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-10	MW-10	7/13/2021	180-124378-1	-	-	< 0.39 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100I	SSHS-MW-100I-04082024	4/8/2024	1801720411	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100I	SSHS-MW-100I-09142023	9/14/2023	1801625611	< 0.23 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100S	SSHS-DUP-02-09142023	9/14/2023	1801625611	< 0.22 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100S	SSHS-MW-100S-04082024	4/8/2024	1801720411	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100S	SSHS-MW-100S-09142023	9/14/2023	1801625611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721871	-	< 0.79 UT	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721872	-	-	-	-	< 1.1 U	3.2	< 2.0 U	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	0.68 J	1.4 J	1.6 J	-	< 0.23 U	< 0.83 U	0.46 J	1.8	-	2.0	< 0.62 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624611	< 0.21 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624612	-	-	-	-	< 1.2 U	2.6	< 2.3 U	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	2.2	1.2 J	5.2 B	-	< 0.25 U	< 0.92 U	0.79 J	4.1	-	6.5	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-101S	SSHS-MW-101S-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101S	SSHS-MW-101S-09132023	9/13/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102I	SSHS-MW-102I-04222024	4/22/2024	1801730541	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102I	SSHS-MW-102I-09142023	9/14/2023	1801625611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102S	SSHS-MW-102S-04222024	4/22/2024	1801730541	-	< 0.63 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102S	SSHS-MW-102S-09142023	9/14/2023	1801625611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103I	SSHS-MW-103I-04162024	4/16/2024	1801726651	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103I	SSHS-MW-103I-09122023	9/12/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103S	SSHS-MW-103S-04162024	4/16/2024	1801726651	-	< 0.63 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103S	SSHS-MW-103S-09122023	9/12/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104I	SSHS-DUP-03-09122023	9/12/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104I	SSHS-MW-104I-04162024	4/16/2024	1801726651	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104I	SSHS-MW-104I-09122023	9/12/2023	1801624611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104S	SSHS-MW-104S-04162024	4/16/2024	1801726651	-	< 0.71 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104S	SSHS-MW-104S-09122023	9/12/2023	1801624611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105I	SSHS-MW-105I-04172024	4/17/2024	1801726651	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625612	-	-	-	-	< 1.2 U	3.0	< 2.2 U	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.8 J	1.4 J	3.5	-	< 0.25 U	< 0.91 U	< 0.50 U	3.9	-	4.4	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-105S	SSHS-MW-105S-04252024	4/25/2024	1801731401	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105S	SSHS-MW-105S-09122023	9/12/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682891	-	< 0.22 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682892	-	-	-	-	< 1.3 U	2.4	2.6 J	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	1.6 J	0.96 J	3.8	-	< 0.28 U	< 1.0 U	< 0.55 U	3.4	-	3.4	< 0.75 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-04102024	4/10/2024	1801721851	-	< 0.68 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-04102024	4/10/2024	1801721852	-	-	-	-	< 1.3 U	4.0	3.9 J	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	1.7 J	1.3 J	4.2	-	< 0.27 U	< 0.98 U	< 0.54 U	2.9	-	3.9	< 0.73 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559472	-	-	-	-	< 1.2 U	2.5	< 2.3 U	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	1.3 J	< 0.54 U	3.0	-	< 0.25 U	< 0.92 U	< 0.51 U	2.8	-	3.6	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-09142023	9/14/2023	1801625601	< 0.20 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-09142023	9/14/2023	1801625602	-	-	-	-	< 1.4 U	2.0 J	2.6 J	< 0.34 U	< 0.33 U	< 0.58 U	< 0.20 U	1.4 J	1.1 J	2.9	-	< 0.28 U	< 1.0 U	< 0.57 U	2.8	-	2.8	< 0.77 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653531	-	< 0.20 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653532	-	-	-	-	< 1.3 U	3.1	2.9 J	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	1.2 J	1.2 J	2.4	-	< 0.28 U	< 1.0 U	0.59 J	2.9	-	3.1	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-11D	MW-11D	2/23/2021	180-117459-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11D	MW-11D	4/30/2021	180-120955-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11D	MW-11D-GW	11/1/2018	180-83607-1	-	-	< 0.21 U	< 13 U,*,F1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	MW-11S	2/23/2021	180-117459-1	-	-	< 0.2 U	-	< 12 U	< 1.9 U	< 22 U	< 3 U	< 2.9 U	< 5.1 U	< 1.8 U	< 2.3 U	< 5.3 U	< 5.4 U	-	< 2.5 U	< 9.2 U	< 5 U	< 7.9 U	-	< 4.6 U	< 6.8 U	< 12 U	< 10 U	-	-	-	-	-	-	-	-
MW-11S	MW-11S	4/30/2021	180-120955-1	-	-	< 0.19 U	-	< 1.2 U	< 0.18 U	< 2.1 U	< 0.28 U	0.34 J	< 0.49 U	< 0.17 U	0.95 J	< 0.51 U	< 0.52 U	-	0.4 J	< 0.87 U	1.9	2.6	-	< 0.44 U	< 0.65 U	< 1.2 U	< 0.98 U	-	-	-	-	-	-	-	-
MW-11S	MW-11S	4/30/2021	180-120955-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	DUP-01	7/25/2019	180-93333-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	MW-11S	7/25/2019	180-93333-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	FD-1	11/1/2018	180-83607-1	-	-	< 0.22 U	< 13 U,*	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	MW-11S-GW	11/1/2018	180-83607-1	-	-	< 0.18 U	< 13 U,*	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	TAC22_MW-11S (180-93333-4)	7/27/2019	2056373	-	-	-	-	< 1.2 U	7.4	< 5 U	< 1.2 U	< 1.2 U	< 1.2 U	< 1.2 U	< 1.2 U	< 1.2 U	< 1.2 U	-	< 1.2 U	< 1.2 U	< 1.2 U	2.2 J	-	< 1.2 U	< 1.2 U	< 1.2 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-12	MW-12	2/21/2021	180-117476-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-12	MW-12	7/14/2021	180-124487-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-13	DUP-02	2/21/2021	180-117476-1	-	-	< 0.17 U	-	< 1.2 U	3	< 2.3 U	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.9	2.8	2.6	-	< 0.25 U	< 0.92 U	3.5	6.7	-	2.8	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
MW-13	MW-13	2/21/2021	180-117476-1	-	-	< 0.18 U	-	< 1.2 U	5.4 I	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	0.86 J	1.3 J	1.5 J	-	< 0.25 U	< 0.91 U	1.2 J	1.4 J	-	7.6	< 0.67 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
MW-13	MW-13	7/15/2021	180-124580-1	-	-	< 0.19 U	-	< 1.1	6.1	24	< 0.27	< 0.26	< 0.46	< 0.16	1.2	1.8	2.3	-	< 0.23	< 0.83	< 0.45	2.2	-	1.3	< 0.61	< 1.1	< 0.93	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PEMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-1	MW-1	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-1	MW-1	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-10	MW-10	3/24/2021	180-119009-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-10	MW-10	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100I	SSHS-MW-100I-04082024	4/8/2024	1801720411	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100I	SSHS-MW-100I-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100S	SSHS-DUP-02-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100S	SSHS-MW-100S-04082024	4/8/2024	1801720411	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-100S	SSHS-MW-100S-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-04102024	4/10/2024	1801721872	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1.0 U	-	-	-
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101I	SSHS-MW-101I-09132023	9/13/2023	1801624612	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-101S	SSHS-MW-101S-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-101S	SSHS-MW-101S-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102I	SSHS-MW-102I-04222024	4/22/2024	1801730541	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102I	SSHS-MW-102I-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102S	SSHS-MW-102S-04222024	4/22/2024	1801730541	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-102S	SSHS-MW-102S-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103I	SSHS-MW-103I-04162024	4/16/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103I	SSHS-MW-103I-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103S	SSHS-MW-103S-04162024	4/16/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-103S	SSHS-MW-103S-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104I	SSHS-DUP-03-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104I	SSHS-MW-104I-04162024	4/16/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104I	SSHS-MW-104I-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104S	SSHS-MW-104S-04162024	4/16/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-104S	SSHS-MW-104S-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105I	SSHS-MW-105I-04172024	4/17/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105I	SSHS-MW-105I-09152023	9/15/2023	1801625612	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-105S	SSHS-MW-105S-04252024	4/25/2024	1801731401	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-105S	SSHS-MW-105S-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682891	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-01182024	1/18/2024	1801682892	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-106	SSHS-MW-106-04102024	4/10/2024	1801721851	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-04102024	4/10/2024	1801721852	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-05022023	5/2/2023	1801559472	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-106	SSHS-MW-106-09142023	9/14/2023	1801625601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-09142023	9/14/2023	1801625602	-	-	-	-	< 0.48 U	-	< 2.6 U	-	-	< 1.3 U	-	-	-
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-106	SSHS-MW-106-11142023	11/14/2023	1801653532	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-11D	MW-11D	2/23/2021	180-117459-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11D	MW-11D	4/30/2021	180-120955-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11D	MW-11D-GW	11/1/2018	180-83607-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	MW-11S	2/23/2021	180-117459-1	-	-	-	-	< 4.3 U	-	< 23 U	-	-	< 11 U	-	-	-
MW-11S	MW-11S	4/30/2021	180-120955-1	-	-	-	-	-	-	-	-	-	< 1.1 U	-	-	-
MW-11S	MW-11S	4/30/2021	180-120955-1	-	-	-	-	< 4.1 U	-	< 22 U	-	-	-	-	-	-
MW-11S	DUP-01	7/25/2019	180-93333-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	MW-11S	7/25/2019	180-93333-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	FD-1	11/1/2018	180-83607-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	MW-11S-GW	11/1/2018	180-83607-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-11S	TAC22_MW-11S (180-93333-4)	7/27/2019	2056373	-	-	-	-	< 2.5 U	-	< 5 U	-	-	< 1.5 U	-	-	-
MW-12	MW-12	2/21/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-12	MW-12	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-13	DUP-02	2/21/2021	180-117476-1	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-13	MW-13	2/21/2021	180-117476-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-13	MW-13	7/15/2021	180-124580-1	-	-	-	-	< 0.39	-	< 2.1	-	-	< 1	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3ONS)
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35															2.7	6.7											
Location	Sample Name	Sample Date	Lab Report																														
MW-2	MW-2	2/17/2021	180-117387-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-2	MW-2	7/14/2021	180-124487-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW-20	2/23/2021	180-117459-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW-20	7/15/2021	180-124580-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-22	MW-22	2/23/2021	180-117459-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-22	MW-22	7/15/2021	180-124580-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-26	MW-26	2/17/2021	180-117387-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-26	MW-26	7/14/2021	180-124487-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-26	SSHS-MW-26-04112024	4/11/2024	1801722801	-	< 0.63 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-3	MW-3	2/17/2021	180-117387-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-3	MW-3	7/14/2021	180-124487-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-3	DUP-4	7/14/2021	180-124487-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	MW-30	2/19/2021	180-117476-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	MW-30	7/16/2021	180-124628-1	-	-	< 0.3 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	MW-30	7/26/2019	180-93333-1	-	-	< 0.44 U,F1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	TAC22_MW-30 (180-93333-7)	7/26/2019	2056373	-	-	-	-	< 1.2 U	4.2 J	21	< 1.2 U	< 1.2 U	< 1.2 U	< 1.2 U	2.2 J	2.7 J	5.9	-	2.5 J	< 1.2 U	12	6.7	-	3.6 J	< 1.2 U	< 1.2 U	< 1.2 U	-	-	-	-	-	-	-
MW-32	MW-32	2/22/2021	180-117425-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-32	MW-32	7/13/2021	180-124378-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-33	MW-33	2/19/2021	180-117476-1	-	-	< 0.18 U	-	< 2.4 U	9.2 I	< 4.5 U	< 0.6 U	< 0.58 U	< 1 U	< 0.36 U	1.6 J	2.2 J,I	2.4 J	-	< 0.51 U	< 1.8 U	< 1 U	3.3 J	-	4.2	< 1.4 U	< 2.4 U	< 2.1 U	-	-	-	-	-	-	-
MW-33	MW-33	7/13/2021	180-124378-1	-	-	< 0.19 U	-	< 1.2 U	< 0.19 U,F1	35 F1	< 0.3 U	< 0.3 U	< 0.52 U	< 0.18 U	0.85 J	1.1 J	< 0.55 U	-	0.31 J	< 0.93 U	2.5	3.2	-	< 0.47 U	< 0.7 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-34	MW-34	2/24/2021	180-117542-1	-	-	-	-	< 1.3 U	< 0.19 U	< 29 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	0.87 J	1.1 J	< 4.8 U	-	< 0.26 U	< 0.95 U	1.3 J	3	-	< 13 U	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-34	MW-34	3/23/2021	180-118872-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-34	MW-34	4/30/2021	180-120955-1	-	-	< 0.22 U	-	< 1.2 U	< 0.19 U	36	< 0.3 U	0.37 J	< 0.52 U	< 0.18 U	2.2	2.1	2.6	-	0.31 J	< 0.92 U	2.1	4.6	-	< 0.46 U	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-36	MW-36	3/23/2021	180-118872-1	-	-	< 3 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-36	MW-36	4/30/2021	180-120955-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-36	SSHS-MW36	8/22/2018	180-81174-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	MW-38	3/24/2021	180-119009-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	DUP-1	4/30/2021	180-120955-1	-	-	< 0.23 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	MW-38	4/30/2021	180-120955-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	PS-FD-1	8/24/2018	180-81247-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	SSHS-MW-38	8/23/2018	180-81247-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-39	SSHS-MW-39	8/23/2018	180-81247-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-40	MW-40	2/23/2021	180-117459-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-40	MW-40	5/23/2019	180-90525-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-41	DUP-03	2/20/2021	180-117476-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-41	MW-41	2/20/2021	180-117476-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-41	MW-41	7/13/2021	180-124378-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-43	MW-43	2/16/2021	180-117390-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-43	MW-43	7/13/2021	180-124378-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-44	SSHS-MW-44	8/23/2018	180-81247-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-47	DUP-01	2/22/2021	180-117425-1	-	-	< 0.18 U	-	< 1.2 U	4.7	< 2.3 U	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.7 J	2	3	-	< 0.25 U	< 0.92 U	8.3	3.7	-	3.9	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-47	MW-47	2/22/2021	180-117425-1	-	-	< 0.17 U	-	< 1.2 U	4.3	< 2.3 U	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.5 J	1.9	3.1	-	< 0.25 U	< 0.92 U	7.2	3.4	-	4	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-47	MW-47	7/12/2021	180-124354-1	-	-	< 0.22 U	-	< 1.3 U	5.1	2.5 J	< 0.31 U	0.34 J	< 0.54 U	< 0.19 U	2	2.5	4.2	-	< 0.27 U	< 0.96 U	8.4	5.2	-	5	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-47	TAC22_MW-47 (180-93333-2)	7/27/2019	2056373	-	-	-	-	< 0.49 U	5.1	2.9 J	< 0.49 U	< 0.49 U	< 0.49 U	< 0.49 U	1.9 J	2.5	4.4	-	< 0.49 U	< 0.49 U	6.8	5.3	-	5.6	< 0.49 U	< 0.49 U	< 0.49 U	-	-	-	-	-	-	-
MW-47I	MW-47I	9/10/2021	180-126939-1	-	-	< 0.51 U	28 J	< 1.3 U	4.2	2.9 J	< 0.32 U	0.34 J,I	< 0.56 U	< 0.19 U	2.4	1.7 J	3.9	-	< 0.27 U	< 0.99 U	4.4	5.6	-	5.6	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-47I	DUP-01	10/27/2021	180-129230-1	-	-	< 0.2 U	-	< 1.1 U	3.1	2.9 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	1.8	1.5 J	4	-	< 0.23 U	< 0.83 U	3.1	3.9	-	5.1	< 0.62 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-
MW-47I	MW-47I	10/27/2021	180-129230-1	-	-	< 0.18 U	-	< 1.1 U	2.9	2.7 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	1.7	1.4 J	3.9	-	< 0.23 U	< 0.83 U	2.7	3.8	-	5.1	< 0.62 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731401	-	< 0.71 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731402	-	-	-	-	< 1.2 U	3.9	< 2.2 U	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.8 J	1.6 J	4.1	-	< 0.25 U	< 0.91 U	3.5	3.7	-	4.9	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731401	-	< 0.71 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731402	-	-	-	-	< 1.2 U	3.7	< 2.1 U	< 0.28 U	< 0.27 U	< 0.49 U	< 0.17 U	1.5 J	1.5 J	4.6	-	< 0.24 U	< 0.87 U	2.9	4.0	-	4.9	< 0.65 U	< 1.2 U	< 0.97 U	-	-	-	-	-	-	-
MW-48	MW-48	2/17/2021	180-117387-1	-	-	< 0.16 U	-	< 1.2 U	3.5	2.8 J	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.5 J	< 0.53 J	2.7	-	< 0.25 U	< 0.91 U	2.1	3.1	-	3.7	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-48	MW-48	4/26/2021	180-120679-1	-	-	-	-	< 1.2 U	3.1	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.8 J	1.6 J	3.2	-	< 0.25 U	< 0.91 U	2.9	3.9	-	3.8	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-48R	DUP-01-01162024	1/16/2024	1801682361	-	< 0.24 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	DUP-01-01162024	1/16/2024	1801682362	-	-	-	-	< 1.4 U	3.4	< 2.7 U	< 0.35 U	< 0.34 U	< 0.61 U	< 0.21 U	1.6 J	1.3 J	3.1	-	< 0.30 U	< 1.1 U	< 0.60 U	3.8	-	3.8	< 0.81 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654471	-	< 0.22 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654472	-	-	-	-	< 1.4 U	3.8	< 2.5 U	< 0.33 U	< 0.32 U	< 0.57 U	< 0.20 U	2.0 J	1.0 J	3.6	-	< 0.28 U	< 1.0 U	< 0.56 U	3.6	-	4.6	< 0.76 U	< 1.4 U	< 1.1 U	-	-	-	-	-	-	-
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721201	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721202	-	-	-	-	< 1.3 U	3.7	< 2.4 U	< 0.32 U	< 0.31 U	< 0.54 U	< 0.19 U	1.5 J	1.2 J	2.9	-	< 0.27 U	< 0.97 U	< 0.53 U	3.0	-	3.1	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-2	MW-2	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-2	MW-2	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW-20	2/23/2021	180-117459-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-20	MW-20	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-22	MW-22	2/23/2021	180-117459-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-22	MW-22	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-26	MW-26	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-26	MW-26	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-26	SSHS-MW-26-04112024	4/11/2024	1801722801		-	-	-	-	-	-	-	-	-	-	-	-
MW-3	MW-3	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-3	MW-3	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-3	DUP-4	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	MW-30	2/19/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	MW-30	7/16/2021	180-124628-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	MW-30	7/26/2019	180-93333-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-30	TAC22_MW-30 (180-93333-7)	7/26/2019	2056373	-	-	-	-	< 2.5 U	-	< 5 U	-	-	< 1.5 U	-	-	-
MW-32	MW-32	2/22/2021	180-117425-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-32	MW-32	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-33	MW-33	2/19/2021	180-117476-1	-	-	-	-	< 0.86 U	-	< 4.7 U	-	-	< 2.3 U	-	-	-
MW-33	MW-33	7/13/2021	180-124378-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-34	MW-34	2/24/2021	180-117542-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-34	MW-34	3/23/2021	180-118872-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-34	MW-34	4/30/2021	180-120955-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-36	MW-36	3/23/2021	180-118872-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-36	MW-36	4/30/2021	180-120955-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-36	SSHS-MW36	8/22/2018	180-81174-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	MW-38	3/24/2021	180-119009-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	DUP-1	4/30/2021	180-120955-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	MW-38	4/30/2021	180-120955-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	PS-FD-1	8/24/2018	180-81247-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-38	SSHS-MW-38	8/23/2018	180-81247-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-39	SSHS-MW-39	8/23/2018	180-81247-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-40	MW-40	2/23/2021	180-117459-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-40	MW-40	5/23/2019	180-90525-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-41	DUP-03	2/20/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-41	MW-41	2/20/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-41	MW-41	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-43	MW-43	2/16/2021	180-117390-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-43	MW-43	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-44	SSHS-MW-44	8/23/2018	180-81247-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-47	DUP-01	2/22/2021	180-117425-1	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-47	MW-47	2/22/2021	180-117425-1	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-47	MW-47	7/12/2021	180-124354-1	-	-	-	-	< 0.45 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-47	TAC22_MW-47 (180-93333-2)	7/27/2019	2056373	-	-	-	-	< 0.98 U	-	< 2 U	-	-	< 0.59 U	-	-	-
MW-47I	MW-47I	9/10/2021	180-126939-1	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-47I	DUP-01	10/27/2021	180-129230-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-47I	MW-47I	10/27/2021	180-129230-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731401	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-47I	SSHS-DUP-01-04252024	4/25/2024	1801731402	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731401	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-47I	SSHS-MW-47I-04252024	4/25/2024	1801731402	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
MW-48	MW-48	2/17/2021	180-117387-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-48	MW-48	4/26/2021	180-120679-1	-	-	-	-	< 0.43 U	-	3.3 J	-	-	< 1.1 U	-	-	-
MW-48R	DUP-01-01162024	1/16/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	DUP-01-01162024	1/16/2024	1801682362	-	-	-	-	< 0.51 U	-	< 2.8 U	-	-	< 1.3 U	-	-	-
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-DUP-01-11152023	11/15/2023	1801654472	-	-	-	-	< 0.48 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-DUP-02-04092024	4/9/2024	1801721202	-	-	-	-	< 0.45 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PERFLUORO(2-PROPOXYPROPANOIC) ACID	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7											
Location	Sample Name	Sample Date	Lab Report																															
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682361	-	< 0.21 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682362	-	-	-	-	< 1.5 U	3.5	< 2.7 U	< 0.36 U	< 0.35 U	< 0.62 U	< 0.21 U	1.8 J	1.1 J	3.2	-	< 0.30 U	< 1.1 U	< 0.61 U	3.8	-	4.0	< 0.82 U	< 1.5 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721201	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721202	-	-	-	-	< 1.2 U	3.3	2.7 J	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	1.3 J	1.2 J	2.8	-	< 0.25 U	< 0.90 U	< 0.49 U	2.8	-	3.1	< 0.67 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-09132023	9/13/2023	1801624601	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-09132023	9/13/2023	1801624602	-	-	-	-	< 1.4 U	3.2	< 2.6 U	< 0.34 U	< 0.33 U	< 0.59 U	< 0.20 U	1.9 J	1.3 J	3.8	-	< 0.29 U	< 1.0 U	< 0.58 U	3.5	-	4.3	< 0.78 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654471	-	< 0.22 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654472	-	-	-	-	< 1.4 U	3.9	< 2.6 U	< 0.34 U	< 0.33 U	< 0.59 U	< 0.20 U	1.9 J	1.1 J	3.7	-	< 0.29 U	< 1.0 U	< 0.58 U	3.7	-	5.0	< 0.78 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-49	DUP-04	2/17/2021	180-117387-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-49	MW-49	2/17/2021	180-117387-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-49	MW-49	4/28/2021	180-120857-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50I	SSHS-RI-MW-50I	2/12/2021	180-117176-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50I	MW-50I	4/28/2021	180-120857-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50R	SSHS-MW-50R-04082024	4/8/2024	1801720381	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50R	SSHS-MW-50R-09142023	9/14/2023	1801625611	< 0.22 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50S	SSHS-RI-MW-50S	2/12/2021	180-117176-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50S	MW-50S	4/28/2021	180-120857-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	DUP-05	2/12/2021	180-117176-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-RI-MW-51	2/12/2021	180-117176-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-DUP-04-09142023	9/14/2023	1801625601	< 0.20 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-DUP-04-09142023	9/14/2023	1801625602	-	-	-	-	< 1.3 U	1.9 J	2.7 J	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	0.77 J	0.95 J	< 0.59 J	-	< 0.28 U	< 1.0 U	< 0.55 U	1.8 J	-	1.5 J	< 0.75 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-01182024	1/18/2024	1801682891	-	< 0.24 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-01182024	1/18/2024	1801682892	-	-	-	-	< 1.5 U	1.5 J	< 2.7 U	< 0.36 U	< 0.35 U	< 0.63 U	< 0.22 U	0.64 J	0.77 J	1.2 J	-	< 0.31 U	< 1.1 U	< 0.61 U	1.5 J	-	1.3 J	< 0.83 U	< 1.5 U	< 1.3 U	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721201	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721202	-	-	-	-	< 1.2 U	2.8	10	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	2.5	1.1 J	6.4	-	< 0.25 U	< 0.92 U	< 0.51 U	4.2	-	5.7	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559472	-	-	-	-	< 1.4 U	2.0 J	2.9 J	< 0.34 U	< 0.33 U	< 0.59 U	< 0.20 U	0.99 J	< 0.61 U	1.8 J	-	< 0.29 U	< 1.0 U	< 0.58 U	1.7 J	-	2.6	< 0.78 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-09142023	9/14/2023	1801625601	< 0.20 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-09142023	9/14/2023	1801625602	-	-	-	-	< 1.3 U	1.8 J	2.8 J	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	0.81 J	0.87 J	< 0.59 J	-	< 0.28 U	< 1.0 U	0.61 J	1.7 J	-	1.6 J	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653531	-	< 0.24 UT	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653532	-	-	-	-	< 1.4 U	3.1	< 2.6 U	< 0.35 U	< 0.34 U	< 0.60 U	< 0.21 U	1.9 J	1.2 J	3.9	-	< 0.30 U	< 1.1 U	< 0.59 U	3.7	-	4.7	< 0.80 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-	-
MW-52	SSHS-RI-MW-52	2/12/2021	180-117176-1	-	-	< 0.18 U	-	< 1.3 U	2.7	2.4 J	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	1.6 J	1.2 J	4	-	< 0.27 U	< 0.99 U	0.8 J	2.6	-	5.5	< 0.73 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-52	DUP-2	4/28/2021	180-120857-1	-	-	< 0.19 U	-	< 1.2 U	2.7	2.3 J	< 0.3 U	0.3 J	< 0.51 U	< 0.18 U	1.9	0.93 J	4.3	-	< 0.25 U	< 0.91 U	0.91 J,I	2.8	-	5.5	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
MW-52	MW-52	4/28/2021	180-120857-1	-	-	< 0.19 U	-	< 1.3 U	2.7	< 2.3 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	1.7 J	0.91 J	4.4	-	< 0.26 U	< 0.95 U	< 0.52 U	2.7	-	5.1	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-53	MW-53	2/17/2021	180-117387-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-53	MW-53	4/26/2021	180-120679-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-53	SSHS-MW-53-09042023	9/4/2023	1801619191	< 0.19 UT	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54	MW-54	2/16/2021	180-117390-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54	MW-54	2/25/2021	180-117621-1	-	-	-	-	< 1.3 U	3	< 2.4 U	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	1.6 J	1.5 J	3.1	-	< 0.27 U	< 0.98 U	< 0.54 U	3	-	3.9	< 0.73 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-54	MW-54	4/27/2021	180-120743-1	-	-	< 0.18 U	-	< 1.1 U	3.1	< 2.1 U	< 0.27 U	0.28 J	< 0.47 U	< 0.16 U	1.7	1 J	3.7	-	< 0.23 U	< 0.84 U	< 0.46 U	3.2	-	4.4	< 0.63 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-	-
MW-54R	SSHS-MW-54R-04052024	4/5/2024	1801720021	-	< 0.65 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625612	-	-	-	-	< 1.2 U	3.0	< 2.2 U	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.6 J	1.2 J	3.5	-	< 0.25 U	< 0.91 U	< 0.50 U	3.3	-	3.6	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-55	MW-55	2/16/2021	180-117390-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	MW-55	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	DUP-01-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	DUP-01-05022023	5/2/2023	1801559472	-	-	-	-	< 1.2 U	2.9	< 2.2 U	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	1.7 J	1.2 J	3.0	-	< 0.25 U	< 0.90 U	< 0.49 U	3.2	-	3.7	< 0.67 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682361	-	< 0.22 UT	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682362	-	-	-	-	< 1.2 U	3.0	< 2.3 U	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	0.70 J	0.81 J	1.6 J	-	< 0.25 U	< 0.92 U	< 0.51 U	1.6 J	-	1.5 J	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721201	-	< 0.60 UT	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721202	-	-	-	-	< 1.1 U	3.3	2.2 J	< 0.28 U	< 0.27 U	< 0.47 U	< 0.16 U	1.0 J	1.0 J	2.8	-	< 0.23 U	< 0.84 U	< 0.46 U	2.2	-	2.8	< 0.63 U	< 1.1 U	< 0.95 UT	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559472	-	-	-	-	< 1.2 U	3.1	< 2.2 U	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	1.6 J	1.2 J	2.8	-	< 0.25 U	< 0.90 U	< 0.50 U	3.6	-	3.8	< 0.67 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-09132023	9/13/2023	1801624601	< 0.20 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-09132023	9/13/2023	1801624602	-	-	-	-	< 1.2 U	3.0	< 2.3 U	< 0.30 U	< 0.30 U	< 0.52 U	< 0.18 U	1.9	1.3 J	3.2	-	< 0.26 U	< 0.93 U	< 0.51 U	3.1	-	3.7	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654471	-	< 0.19 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654472	-	-	-	-	< 1.3 U	3.3	< 2.3 U	< 0.31 U	< 0.30 U	< 0.54 U	< 0.19 U	1.8 J	1.1 J	3.0	-	< 0.26 U	< 0.96 U	0.79 J	3.6	-	3.8	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-56	MW-56	2/17/2021	180-117387-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-56	MW-56	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-01162024	1/16/2024	1801682362	-	-	-	-	< 0.52 U	-	< 2.8 U	-	-	< 1.3 U	-	-	-
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-04092024	4/9/2024	1801721202	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-48R	SSHS-MW-48R-09132023	9/13/2023	1801624601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-09132023	9/13/2023	1801624602	-	-	-	-	< 0.49 U	-	< 2.7 U	-	-	< 1.3 U	-	-	-
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-48R	SSHS-MW-48R-11152023	11/15/2023	1801654472	-	-	-	-	< 0.49 U	-	< 2.7 U	-	-	< 1.3 U	-	-	-
MW-49	DUP-04	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-49	MW-49	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-49	MW-49	4/28/2021	180-120857-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50I	SSHS-RI-MW-50I	2/12/2021	180-117176-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50I	MW-50I	4/28/2021	180-120857-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50R	SSHS-MW-50R-04082024	4/8/2024	1801720381	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50R	SSHS-MW-50R-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50S	SSHS-RI-MW-50S	2/12/2021	180-117176-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-50S	MW-50S	4/28/2021	180-120857-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	DUP-05	2/12/2021	180-117176-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-RI-MW-51	2/12/2021	180-117176-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-DUP-04-09142023	9/14/2023	1801625601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-DUP-04-09142023	9/14/2023	1801625602	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-51	SSHS-MW-51-01182024	1/18/2024	1801682891	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-01182024	1/18/2024	1801682892	-	-	-	-	< 0.52 U	-	< 2.8 U	-	-	< 1.4 U	-	-	-
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-04092024	4/9/2024	1801721202	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-05022023	5/2/2023	1801559472	-	-	-	-	< 0.49 U	-	< 2.7 U	-	-	< 1.3 U	-	-	-
MW-51	SSHS-MW-51-09142023	9/14/2023	1801625601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-09142023	9/14/2023	1801625602	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-51	SSHS-MW-51-11142023	11/14/2023	1801653532	-	-	-	-	< 0.51 U	-	< 2.7 U	-	-	< 1.3 U	-	-	-
MW-52	SSHS-RI-MW-52	2/12/2021	180-117176-1	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-52	DUP-2	4/28/2021	180-120857-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-52	MW-52	4/28/2021	180-120857-1	-	-	-	-	< 0.45 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-53	MW-53	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-53	MW-53	4/26/2021	180-120679-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-53	SSHS-MW-53-09042023	9/4/2023	1801619191	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54	MW-54	2/16/2021	180-117390-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54	MW-54	2/25/2021	180-117621-1	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-54	MW-54	4/27/2021	180-120743-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-54R	SSHS-MW-54R-04052024	4/5/2024	1801720021	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-54R	SSHS-MW-54R-09142023	9/14/2023	1801625612	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-55	MW-55	2/16/2021	180-117390-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	MW-55	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	DUP-01-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	DUP-01-05022023	5/2/2023	1801559472	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-01162024	1/16/2024	1801682362	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-04092024	4/9/2024	1801721202	-	-	-	-	< 0.40 UT	-	< 2.1 U	-	-	< 1.0 U	-	-	-
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-05022023	5/2/2023	1801559472	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-55	SSHS-MW-55-09132023	9/13/2023	1801624601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-09132023	9/13/2023	1801624602	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-55	SSHS-MW-55-11152023	11/15/2023	1801654472	-	-	-	-	< 0.45 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-56	MW-56	2/17/2021	180-117387-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-56	MW-56	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3ONS)
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7										
Location	Sample Name	Sample Date	Lab Report																														
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625612	-	-	-	-	< 1.2 U	2.9	< 2.3 U	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	1.3 J	1.1 J	3.7	-	< 0.25 U	< 0.92 U	< 0.51 U	2.9	-	4.1	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-57	MW-57	2/18/2021	180-117476-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57	MW-57	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57	DUP-01	7/13/2022	1801412391	< 0.19 U	-	-	< 43 U	< 1.1 U	2.9	< 2.1 U	< 0.28 U	< 0.27 U	< 0.47 U	< 0.16 U	1.0 J	0.94 J	2.3	-	< 0.23 U	< 0.84 U	< 0.46 U	2.4	-	3.2	< 0.63 U	< 1.1 U	< 0.95 U	-	-	-	-	-	-	-
MW-57	MW-57	7/13/2022	1801412391	< 0.19 U	-	-	< 43 UT	< 1.1 U	3.2	< 2.1 U	< 0.28 U	< 0.27 U	< 0.48 U	< 0.17 U	0.91 J	0.97 J	2.2	-	< 0.24 U	< 0.86 U	< 0.47 U	2.2	-	3.0	< 0.64 U	< 1.1 U	< 0.96 U	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682361	-	< 0.21 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682362	-	-	-	-	< 1.3 U	2.7	3.8 J	< 0.33 U	< 0.32 U	< 0.57 U	< 0.20 U	1.7 J	1.1 J	3.1	-	< 0.28 U	< 1.0 U	1.7 JEMPC	4.2	-	3.7	< 0.75 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721201	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721202	-	-	-	-	< 1.1 U	4.4	6.7	< 0.28 U	< 0.27 U	< 0.48 U	< 0.17 U	1.6 J	1.4 J	4.0	-	< 0.24 U	< 0.85 U	< 0.47 U	3.5	-	5.1	< 0.64 U	< 1.1 U	< 0.96 U	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559472	-	-	-	-	< 1.3 U	2.4	< 2.4 U	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	0.70 J	< 0.57 U	1.7 J	-	< 0.27 U	< 0.97 U	< 0.54 U	1.5 J	-	2.3	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-09142023	9/14/2023	1801625601	< 0.20 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-09142023	9/14/2023	1801625602	-	-	-	-	< 1.4 U	4.0	4.2 J	< 0.34 U	< 0.33 U	< 0.58 U	< 0.20 U	1.6 J	1.9 J	3.3	-	< 0.28 U	< 1.0 U	< 0.57 U	4.4	-	3.9	< 0.77 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653531	-	< 0.19 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653532	-	-	-	-	< 1.2 U	3.1	3.5 J	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.4 J	0.92 J	2.9	-	< 0.25 U	< 0.91 U	< 0.50 U	2.5	-	3.8	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-58	MW-58	2/21/2021	180-117476-1	-	-	< 0.17 U	-	< 1.4 U	3.1 I	< 2.5 U	< 0.33 U	< 0.32 U	< 0.57 U	< 0.2 U	0.47 J,I	1.1 J	< 0.6 U	-	< 0.28 U	< 1 U	0.93 J,I	1.1 J	-	1.8 J	< 0.76 U	< 1.4 U	< 1.1 U	-	-	-	-	-	-	-
MW-58	MW-58	4/30/2021	180-120955-1	-	-	< 0.19 U	-	< 1.2 U	< 0.19 U	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	0.82 J,I	1.6 J	< 0.54 U	-	< 0.25 U	< 0.91 U	1.1 J	1.5 J	-	< 0.45 U	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625611	< 0.23 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625612	-	-	-	-	< 1.3 U	3.2	44	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	4.0	< 0.57 U	7.6	-	1.9 J	< 0.99 U	4.3	9.1	-	13	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625611	< 0.23 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625612	-	-	-	-	< 1.3 U	5.2	43	0.34 J	< 0.32 U	< 0.56 U	< 0.19 U	4.9	< 0.58 U	8.7	-	1.6 J	< 1.0 U	4.3	10	-	11	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-59I	MW-59I	2/19/2021	180-117476-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59I	MW-59I	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59I	MW-59I	7/12/2022	1801412391	< 0.22 UT	-	-	< 43 U	< 1.2 U	3.3	< 2.2 U	< 0.29 U	< 0.28 U	< 0.49 U	< 0.17 U	1.7 J	1.2 J	3.6	-	< 0.24 U	< 0.88 U	< 0.49 U	3.2	-	5.0	< 0.66 U	< 1.2 U	< 0.99 U	-	-	-	-	-	-	-
MW-59S	MW-59S	2/19/2021	180-117476-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59S	MW-59S	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59S	MW-59S	7/13/2022	1801412391	< 0.20 U	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5I	SSHS-MW-5I-04102024	4/10/2024	1801721871	-	< 0.60 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5I	SSHS-MW-5I-09132023	9/13/2023	1801624611	< 0.22 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	2/23/2021	180-117459-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	7/15/2021	180-124580-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60	MW-60	2/18/2021	180-117476-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60	MW-60	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60	MW-60	7/12/2022	1801412391	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60IR	SSHS-MW-60IR-04052024	4/5/2024	1801720021	-	< 0.68 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60SR	SSHS-MW-60SR-04052024	4/5/2024	1801720021	-	< 0.65 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-61	MW-61	2/16/2021	180-117390-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-61	MW-61	2/25/2021	180-117621-1	-	-	-	-	< 1.3 U	3.4	< 2.3 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	1.9	1.4 J	3.3	-	< 0.26 U	< 0.94 U	< 0.52 U	3.4	-	3.9	< 0.7 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-61	MW-61	4/27/2021	180-120743-1	-	-	< 0.19 U	-	< 1.1 U	3.6	2.2 J	< 0.28 U	< 0.27 U	< 0.48 U	< 0.17 U	1.9	1.5 J	3.6	-	< 0.24 U	< 0.85 U	< 0.47 U	3.7	-	4.4	< 0.64 U	< 1.1 U	< 0.96 U	-	-	-	-	-	-	-
MW-61	MW-61	7/12/2022	1801412391	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62	MW-62	2/16/2021	180-117390-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62	MW-62	4/27/2021	180-120743-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62	MW-62	7/12/2022	1801412391	< 0.21 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62R	SSHS-MW-62R-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62R	SSHS-MW-62R-09142023	9/14/2023	1801625611	< 0.21 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63I	MW-63I	2/18/2021	180-117476-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63I	MW-63I	4/29/2021	180-121010-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63I	SSHS-MW-63I-09132023	9/13/2023	1801624611	< 0.21 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63S	MW-63S	2/18/2021	180-117476-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63S	MW-63S	4/29/2021	180-121010-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63S	SSHS-MW-63S-09132023	9/13/2023	1801624611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	MW-64I	2/20/2021	180-117476-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	MW-64I	4/28/2021	180-120857-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	SSHS-MW-64I-04052024	4/5/2024	1801720021	-	< 0.65 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	SSHS-MW-64I-09122023	9/12/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64S	MW-64S	2/20/2021	180-117476-1	-	-	< 0.19 U	-	< 1.2 U	2.9	< 2.2 U	< 0.29 U	< 0.28 U	< 0.5 U	< 0.17 U	1.4 J	1.2 J	2.9	-	< 0.25 U	< 0.9 U	0.57 J,I	2.9	-	3.8	< 0.67 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-64S	MW-64S	4/28/2021	180-120857-1	-	-	< 0.22 U	-	< 1.2 U	3.1	2.3 J	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.7 J	1.2 J	3.6	-	< 0.25 U	< 0.92 U	0.92 J,I	3.3	-	4.3	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PEMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-56	SSHS-MW-56-09142023	9/14/2023	1801625612	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-57	MW-57	2/18/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57	MW-57	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57	DUP-01	7/13/2022	1801412391	-	-	-	-	< 0.40 U	-	< 2.2 U	-	-	< 1.0 U	-	-	-
MW-57	MW-57	7/13/2022	1801412391	-	-	-	-	< 0.40 U	-	< 2.2 U	-	-	< 1.0 U	-	-	-
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-01172024	1/17/2024	1801682362	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-04092024	4/9/2024	1801721202	-	-	-	-	< 0.40 U	-	< 2.2 U	-	-	< 1.0 U	-	-	-
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-05022023	5/2/2023	1801559472	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-57R	SSHS-MW-57R-09142023	9/14/2023	1801625601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-09142023	9/14/2023	1801625602	-	-	-	-	< 0.48 U	-	< 2.6 U	-	-	< 1.3 U	-	-	-
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-57R	SSHS-MW-57R-11132023	11/13/2023	1801653532	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-58	MW-58	2/21/2021	180-117476-1	-	-	-	-	< 0.48 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-58	MW-58	4/30/2021	180-120955-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-58	SSHS-DUP-01-09142023	9/14/2023	1801625612	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-58	SSHS-MW-58-09142023	9/14/2023	1801625612	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-59I	MW-59I	2/19/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59I	MW-59I	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59I	MW-59I	7/12/2022	1801412391	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
MW-59S	MW-59S	2/19/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59S	MW-59S	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-59S	MW-59S	7/13/2022	1801412391	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5I	SSHS-MW-5I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5I	SSHS-MW-5I-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	2/23/2021	180-117459-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-5S	MW-5	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60	MW-60	2/18/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60	MW-60	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60	MW-60	7/12/2022	1801412391	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60IR	SSHS-MW-60IR-04052024	4/5/2024	1801720021	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-60SR	SSHS-MW-60SR-04052024	4/5/2024	1801720021	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-61	MW-61	2/16/2021	180-117390-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-61	MW-61	2/25/2021	180-117621-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-61	MW-61	4/27/2021	180-120743-1	-	-	-	-	< 0.4 U	-	< 2.2 U	-	-	< 1 U	-	-	-
MW-61	MW-61	7/12/2022	1801412391	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62	MW-62	2/16/2021	180-117390-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62	MW-62	4/27/2021	180-120743-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62	MW-62	7/12/2022	1801412391	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62R	SSHS-MW-62R-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-62R	SSHS-MW-62R-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63I	MW-63I	2/18/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63I	MW-63I	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63I	SSHS-MW-63I-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63S	MW-63S	2/18/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63S	MW-63S	4/29/2021	180-121010-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-63S	SSHS-MW-63S-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	MW-64I	2/20/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	MW-64I	4/28/2021	180-120857-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	SSHS-MW-64I-04052024	4/5/2024	1801720021	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64I	SSHS-MW-64I-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-64S	MW-64S	2/20/2021	180-117476-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-64S	MW-64S	4/28/2021	180-120857-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3ONS)
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7										
Location	Sample Name	Sample Date	Lab Report																														
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624612	-	-	-	-	< 1.3 U	2.9	< 2.3 U	< 0.31 U	< 0.30 U	< 0.54 U	< 0.18 U	1.7 J	1.3 J	3.4 B	-	< 0.26 U	< 0.95 U	0.96 JEMPC	3.6	-	3.5	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-65	MW-65	2/20/2021	180-117476-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	DUP-3	4/26/2021	180-120679-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	MW-65	4/26/2021	180-120679-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	SSHS-DUP1-08152022	8/15/2022	1801429571	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	SSHS-MW-65-08152022	8/15/2022	1801429571	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65R	SSHS-MW-65R-04082024	4/8/2024	1801720411	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65R	SSHS-MW-65R-09142023	9/14/2023	1801625611	< 0.20 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66I	MW-66I	2/20/2021	180-117476-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66I	MW-66I	4/28/2021	180-120857-1	-	-	< 0.23 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66I	SSHS-MW-66I-09122023	9/12/2023	1801624611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66S	MW-66S	2/19/2021	180-117476-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66S	MW-66S	4/28/2021	180-120857-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66S	SSHS-MW-66S-09122023	9/12/2023	1801624611	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67I	MW-67I	7/16/2021	180-124628-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67I	MW-67I	8/31/2021	180-126501-1	-	-	< 0.21 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67I	SSHS-MW-67I-04282024	4/28/2024	1801733271	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	MW-67S	7/16/2021	180-124628-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	MW-67S	8/31/2021	180-126501-1	-	-	< 0.23 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733271	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733272	-	-	-	-	< 1.2 U	3.7	14	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	1.4 J	1.5 J	2.0	-	< 0.24 U	< 0.88 U	< 0.49 U	8.9	-	4.8	< 0.66 U	< 1.2 U	< 0.99 U	-	-	-	-	-	-	-
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733271	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733272	-	-	-	-	< 1.2 U	3.5	15	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	1.2 J	1.5 J	2.1	-	< 0.24 U	< 0.88 U	< 0.49 U	9.0	-	3.7	< 0.66 U	< 1.2 U	< 0.99 U	-	-	-	-	-	-	-
MW-68S	DUP-3	7/13/2021	180-124378-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	MW-68S	7/13/2021	180-124378-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	DUP-2	9/9/2021	180-126905-1	-	-	< 0.51 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	MW-68S	9/9/2021	180-126905-1	-	-	< 0.51 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	SSHS-MW-68S-04282024	4/28/2024	1801733271	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-69I	MW-69I	7/13/2021	180-124378-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-69I	MW-69I	9/3/2021	180-126702-1	-	-	< 0.21 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-69I	SSHS-MW-69I-04112024	4/11/2024	1801722811	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70I	MW-70I	9/9/2021	180-126939-1	-	-	< 0.49 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70I	MW-70I	10/27/2021	180-129230-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70I	SSHS-MW-70I-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	MW-70S	9/7/2021	180-126846-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	MW-70S	10/27/2021	180-129230-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	DUP-02	5/4/2023	1801561231	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	DUP-02	5/4/2023	1801561232	-	-	-	-	< 0.48 U	3.1	4.7 J	< 0.29 U	< 0.71 U	< 0.53 U	< 0.35 U	0.83 J	1.8	1.6 J	< 0.35 U	< 0.58 U	< 0.30 U	5.7	4.4	< 0.31 U	1.3 J	< 0.48 U	< 0.42 U	< 0.53 U	< 0.72 U	< 1.6 U	< 0.64 U	< 0.55 U	< 0.40 U	< 0.32 U	< 0.66 U
MW-70S	SSHS-DUP-04-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561231	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561232	-	-	-	-	< 0.50 U	3.0	4.9 J	< 0.29 U	< 0.73 U	< 0.54 U	< 0.35 U	0.81 J	1.8	1.2 J	< 0.36 U	< 0.59 U	< 0.31 U	6.1	4.2	< 0.32 U	1.4 J	< 0.50 U	< 0.43 U	< 0.55 U	< 0.74 U	< 1.7 U	< 0.66 U	< 0.57 U	< 0.41 U	< 0.33 U	< 0.68 U
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625621	< 0.21 U	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625622	-	-	-	-	< 0.53 U	3.9	4.4 J	< 0.31 U	< 0.78 U	< 0.58 U	< 0.38 U	0.65 J	1.7 J	0.93 J	< 0.39 U	< 0.63 U	< 0.33 U	6.4	4.4	< 0.34 U	< 0.53 U	< 0.53 U	< 0.46 U	< 0.58 U	< 0.78 U	< 1.8 U	< 0.70 U	< 0.60 U	< 0.43 U	< 0.35 U	< 0.73 U
MW-71I	MW-71I	9/7/2021	180-126846-1	-	-	< 0.54 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71I	MW-71I	10/27/2021	180-129230-1	-	-	< 0.17 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71I	SSHS-MW-71I-04052024	4/5/2024	1801720031	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71S	MW-71S	9/7/2021	180-126846-1	-	-	< 0.54 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71S	MW-71S	10/27/2021	180-129230-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71S	SSHS-MW-71S-04052024	4/5/2024	1801720031	-	< 0.71 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	MW-72I	9/8/2021	180-126846-1	-	-	< 0.51 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	DUP-02	10/27/2021	180-129155-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	MW-72I	10/27/2021	180-129155-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	SSHS-MW-72I-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	MW-72S	9/8/2021	180-126846-1	-	-	< 0.56 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	MW-72S	10/27/2021	180-129155-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561231	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561232	-	-	-	-	< 0.58 U	2.6	1.6 J	< 0.34 U	< 0.85 U	< 0.63 U	< 0.41 U	1.3 J	1.6 J	2.8	< 0.42 U	< 0.69 U	< 0.36 U	5.9	3.1	< 0.37 U	3.7 J	< 0.58 U	< 0.50 U	< 0.64 U	< 0.86 U	< 1.9 U	< 0.77 U	< 0.66 U	< 0.48 U	< 0.38 U	< 0.79 U

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PEMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-64S	SSHS-MW-64S-09122023	9/12/2023	1801624612	-	-	-	-	< 0.45 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-65	MW-65	2/20/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	DUP-3	4/26/2021	180-120679-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	MW-65	4/26/2021	180-120679-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	SSHS-DUP1-08152022	8/15/2022	1801429571	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65	SSHS-MW-65-08152022	8/15/2022	1801429571	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65R	SSHS-MW-65R-04082024	4/8/2024	1801720411	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-65R	SSHS-MW-65R-09142023	9/14/2023	1801625611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66I	MW-66I	2/20/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66I	MW-66I	4/28/2021	180-120857-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66I	SSHS-MW-66I-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66S	MW-66S	2/19/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66S	MW-66S	4/28/2021	180-120857-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-66S	SSHS-MW-66S-09122023	9/12/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67I	MW-67I	7/16/2021	180-124628-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67I	MW-67I	8/31/2021	180-126501-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67I	SSHS-MW-67I-04282024	4/28/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	MW-67S	7/16/2021	180-124628-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	MW-67S	8/31/2021	180-126501-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	SSHS-DUP-03-04282024	4/28/2024	1801733272	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-67S	SSHS-MW-67S-04282024	4/28/2024	1801733272	-	-	-	-	< 0.41 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-68S	DUP-3	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	MW-68S	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	DUP-2	9/9/2021	180-126905-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	MW-68S	9/9/2021	180-126905-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-68S	SSHS-MW-68S-04282024	4/28/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-69I	MW-69I	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-69I	MW-69I	9/3/2021	180-126702-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-69I	SSHS-MW-69I-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70I	MW-70I	9/9/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70I	MW-70I	10/27/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70I	SSHS-MW-70I-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	MW-70S	9/7/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	MW-70S	10/27/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	DUP-02	5/4/2023	1801561231	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	DUP-02	5/4/2023	1801561232	< 1.5 U	< 0.51 U	< 0.53 U	< 0.38 U	< 1.2 U	< 1.4 U	< 0.94 U	< 1.6 U	< 2.0 U	< 0.64 U	< 4.8 U	< 5.7 U	< 0.75 U
MW-70S	SSHS-DUP-04-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561231	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-05042023	5/4/2023	1801561232	< 1.5 U	< 0.52 U	< 0.55 U	< 0.39 U	< 1.3 U	< 1.5 U	< 0.96 U	< 1.7 U	< 2.1 U	< 0.66 U	< 5.0 U	< 5.9 U	< 0.77 U
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625621	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-70S	SSHS-MW-70S-09152023	9/15/2023	1801625622	< 1.6 U	< 0.55 U	< 0.58 U	< 0.41 U	< 1.4 U	< 1.6 U	< 1.0 U	< 1.8 U	< 2.2 U	< 0.70 U	< 5.3 U	< 6.3 U	< 0.82 U
MW-71I	MW-71I	9/7/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71I	MW-71I	10/27/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71I	SSHS-MW-71I-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71S	MW-71S	9/7/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71S	MW-71S	10/27/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-71S	SSHS-MW-71S-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	MW-72I	9/8/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	DUP-02	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	MW-72I	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72I	SSHS-MW-72I-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	MW-72S	9/8/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	MW-72S	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561231	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-05042023	5/4/2023	1801561232	< 1.8 U	< 0.61 U	< 0.64 U	< 0.45 U	< 1.5 U	< 1.7 U	< 1.1 U	< 2.0 U	< 2.4 U	< 0.77 U	< 5.8 U	< 6.8 U	< 0.90 U

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7										
Location	Sample Name	Sample Date	Lab Report																														
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625621	< 0.19 U	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625622	-	-	-	-	< 0.51 U	2.8	2.4 J	< 0.30 U	< 0.75 U	< 0.56 U	< 0.36 U	2.2	2.1	4.6	< 0.37 U	< 0.61 U	< 0.32 U	7.7	3.9	< 0.32 U	6.6	< 0.51 U	< 0.44 U	< 0.56 U	< 0.75 U	< 1.7 U	< 0.67 U	< 0.58 U	< 0.42 U	< 0.34 U	< 0.70 U
MW-73I	MW-73I	9/8/2021	180-126846-1	-	-	< 0.54 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73I	MW-73I	10/27/2021	180-129230-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73I	SSHS-MW-73I-04052024	4/5/2024	1801720031	-	< 0.75 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73S	MW-73S	9/8/2021	180-126846-1	-	-	< 0.49 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73S	MW-73S	10/26/2021	180-129230-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73S	SSHS-MW-73S-04052024	4/5/2024	1801720031	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74I	MW-74I	9/8/2021	180-126846-1	-	-	< 0.51 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74I	MW-74I	10/27/2021	180-129155-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74I	SSHS-MW-74I-04052024	4/5/2024	1801720031	-	< 0.63 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	MW-74S	9/8/2021	180-126846-1	-	-	< 0.54 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	MW-74S	10/27/2021	180-129155-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	SSHS-DUP-05-04052024	4/5/2024	1801720031	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	SSHS-MW-74S-04052024	4/5/2024	1801720031	-	< 0.71 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-75I	MW-75I	9/9/2021	180-126905-1	-	-	< 0.47 U	< 13 U	< 1.2 U	3.5	2.6 J	< 0.29 U	< 0.28 U	< 0.5 U	< 0.17 U	1.9	1.1 J	4.6	-	< 0.25 U	< 0.89 U	< 0.49 U	3.3	-	5.8	< 0.66 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-75I	MW-75I	10/29/2021	180-129376-1	-	-	< 0.18 U,*-	-	< 1.2 U	2.6	2.4 J	< 0.29 U	< 0.29 U	< 0.51 U	< 0.18 U	1.7 J	1.5 J	4.1	-	< 0.25 U	< 0.9 U	< 0.5 U	3.3	-	5.9	< 0.67 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722811	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722812	-	-	-	-	< 1.2 U	3.1	3.4 J	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.5 J	1.1 J	4.2	-	< 0.25 U	< 0.91 U	< 0.50 U	2.9	-	5.9	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-75S	MW-75S	9/9/2021	180-126905-1	-	-	< 0.47 U	< 13 U	< 1.2 U	4.1	2.3 J	< 0.29 U	< 0.29 U	< 0.51 U	< 0.18 U	1.7 J	1.9	3.6	-	< 0.24 U	< 0.88 U	4.7	5	-	4.8	< 0.65 U	< 1.2 U	< 0.98 U	-	-	-	-	-	-	-
MW-75S	MW-75S	10/29/2021	180-129376-1	-	-	< 0.18 U,*-	-	< 1.2 U	2.6	2.6 J	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.8	2.2	3.5	-	< 0.25 U	< 0.91 U	2.5	3.6	-	5.6	< 0.67 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722811	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722812	-	-	-	-	< 1.2 U	3.1	3.4 J	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.5 J	1.1 J	4.2	-	< 0.25 U	< 0.91 U	< 0.50 U	2.9	-	5.9	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-76I	MW-76I	9/10/2021	180-126939-1	-	-	< 0.49 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76I	DUP-03	10/28/2021	180-129230-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76I	MW-76I	10/28/2021	180-129230-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	MW-76S	9/10/2021	180-126939-1	-	-	< 0.46 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	MW-76S	10/28/2021	180-129230-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	SSHS-MW-76S-04082024	4/8/2024	1801720411	-	< 0.60 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	SSHS-MW-76S-04222024	4/22/2024	1801730541	-	< 0.65 UT	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77I	MW-77I	9/10/2021	180-126939-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77I	MW-77I	10/28/2021	180-129230-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77I	SSHS-MW-77I-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77S	MW-77S	9/10/2021	180-126939-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77S	MW-77S	10/28/2021	180-129230-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77S	SSHS-MW-77S-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78I	MW-78I	9/10/2021	180-126939-1	-	-	< 0.54 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78I	MW-78I	11/2/2021	180-129534-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78I	SSHS-MW-78I-04052024	4/5/2024	1801720031	-	< 0.63 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	DUP-5	9/10/2021	180-126939-1	-	-	< 0.56 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	MW-78S	9/10/2021	180-126939-1	-	-	< 0.54 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	MW-78S	11/2/2021	180-129534-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	SSHS-MW-78S-04052024	4/5/2024	1801720031	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	MW-79I	9/10/2021	180-126939-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	DUP-04	11/2/2021	180-129534-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	MW-79I	11/2/2021	180-129534-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	SSHS-MW-79I-04052024	4/5/2024	1801720031	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	MW-79S	9/10/2021	180-126939-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	MW-79S	11/2/2021	180-129534-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	SSHS-DUP-06-04052024	4/5/2024	1801720031	-	< 0.60 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	SSHS-MW-79S-04052024	4/5/2024	1801720031	-	< 0.60 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-81I	MW-81I	7/16/2021	180-124628-1	-	-	< 0.19 U	-	< 1.1	2.3	< 2.1	< 0.27	< 0.27	< 0.47	< 0.16	1	1.3	2.5	-	< 0.23	< 0.84	< 0.46	2.3	-	3.2	< 0.63	< 1.1	< 0.94	-	-	-	-	-	-	-
MW-81I	MW-81I	8/31/2021	180-126501-1	-	-	< 0.2 U	< 13 U	< 1.2 U	3.1	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.6 J	1.1 J	3.6	-	< 0.25 U	< 0.91 U	< 0.5 U	2.9	-	4.6	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731401	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731402	-	-	-	-	< 1.3 U	3.4	< 2.3 U	< 0.31 U	< 0.30 U	< 0.53 U	< 0.18 U	2.1	1.6 J	4.8	-	< 0.26 U	< 0.94 U	0.53 J	4.0	-	5.3	< 0.70 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-82S	DUP-3	9/7/2021	180-126846-1	-	-	< 0.47 U	< 13 U	< 1.2 U	4.2	2.5 J	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.3 J	1.5 J	2	-	< 0.26 U	< 0.93 U	4.3	4.3	-	3.1	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-82S	MW-82S	9/7/2021	180-126846-1	-	-	< 0.47 U	< 13 U	< 1.1 U	5	2.5 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	1.2 J	1.5 J	2	-	< 0.23 U	< 0.84 U	3	4	-	2.9	< 0.62 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-
MW-82S	MW-82S	10/27/2021	180-129230-1	-	-	< 0.16 U	-	< 1.1 U	2.9	3.5 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	1 J	1.3 J	1.9	-	< 0.23 U	< 0.84 U	2.1	3.2	-	3	< 0.62 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733271	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625621	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-72S	SSHS-MW-72S-09152023	9/15/2023	1801625622	< 1.5 U	< 0.53 U	< 0.56 U	< 0.40 U	< 1.3 U	< 1.5 U	< 0.99 U	< 1.7 U	< 2.1 U	< 0.68 U	< 5.1 U	< 6.0 U	< 0.79 U
MW-73I	MW-73I	9/8/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73I	MW-73I	10/27/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73I	SSHS-MW-73I-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73S	MW-73S	9/8/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73S	MW-73S	10/26/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-73S	SSHS-MW-73S-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74I	MW-74I	9/8/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74I	MW-74I	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74I	SSHS-MW-74I-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	MW-74S	9/8/2021	180-126846-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	MW-74S	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	SSHS-DUP-05-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-74S	SSHS-MW-74S-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-75I	MW-75I	9/9/2021	180-126905-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-75I	MW-75I	10/29/2021	180-129376-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-75I	SSHS-MW-75I-04112024	4/11/2024	1801722812	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-75S	MW-75S	9/9/2021	180-126905-1	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
MW-75S	MW-75S	10/29/2021	180-129376-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-75S	SSHS-MW-75S-04112024	4/11/2024	1801722812	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-76I	MW-76I	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76I	DUP-03	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76I	MW-76I	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	MW-76S	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	MW-76S	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	SSHS-MW-76S-04082024	4/8/2024	1801720411	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-76S	SSHS-MW-76S-04222024	4/22/2024	1801730541	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77I	MW-77I	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77I	MW-77I	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77I	SSHS-MW-77I-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77S	MW-77S	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77S	MW-77S	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-77S	SSHS-MW-77S-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78I	MW-78I	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78I	MW-78I	11/2/2021	180-129534-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78I	SSHS-MW-78I-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	DUP-5	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	MW-78S	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	MW-78S	11/2/2021	180-129534-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-78S	SSHS-MW-78S-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	MW-79I	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	DUP-04	11/2/2021	180-129534-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	MW-79I	11/2/2021	180-129534-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79I	SSHS-MW-79I-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	MW-79S	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	MW-79S	11/2/2021	180-129534-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	SSHS-DUP-06-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-79S	SSHS-MW-79S-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-81I	MW-81I	7/16/2021	180-124628-1	-	-	-	-	< 0.39	-	7.7	-	-	< 1	-	-	-
MW-81I	MW-81I	8/31/2021	180-126501-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731401	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-81I	SSHS-MW-81I-04262024	4/26/2024	1801731402	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-82S	DUP-3	9/7/2021	180-126846-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-82S	MW-82S	9/7/2021	180-126846-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-82S	MW-82S	10/27/2021	180-129230-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PERFLUORO(2-PROPOXYPROPANOIC) ACID		Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35															2.7	6.7											
Location	Sample Name	Sample Date	Lab Report																														
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733272	-	-	-	-	< 1.3 U	3.7	4.3 J	< 0.31 U	< 0.30 U	< 0.54 U	< 0.19 U	1.1 J	1.6 J	2.7	-	< 0.26 U	< 0.96 U	1.9 J	6.2	-	3.4	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-83I	MW-83I	9/8/2021	180-126846-1	-	-	< 0.47 U	< 13 U	< 1.1 U	4.2	2 J	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	2	2	4.7	-	< 0.23 U	< 0.82 U	8.9	5.6	-	6.3	< 0.61 U	< 1.1 U	< 0.92 U	-	-	-	-	-	-	-
MW-83I	MW-83I	10/27/2021	180-129155-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83I	MW-83I	10/28/2021	180-129230-1	-	-	-	-	< 1.1 U	3.1	2.1 J	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	1.9	2	4	-	0.27 J	< 0.83 U	7.8	4.4	-	5.2	< 0.62 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721872	-	-	-	-	< 1.2 U	3.7	< 2.2 U	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	1.9	1.6 J	4.5	-	< 0.25 U	< 0.89 U	6.3	4.7	-	5.5	< 0.66 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-83S	MW-83S	9/8/2021	180-126846-1	-	-	< 0.46 U	< 13 U	< 1.1 U	3.9	< 2 U	< 0.26 U	< 0.26 U	< 0.45 U	< 0.16 U	1.7	2	4.2	-	0.33 J	< 0.81 U	11	5.2	-	5.1	< 0.6 U	< 1.1 U	< 0.91 U	-	-	-	-	-	-	-
MW-83S	MW-83S	10/27/2021	180-129155-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83S	MW-83S	10/28/2021	180-129230-1	-	-	-	-	< 1.1 U	2.6	< 2 U	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	1.6 J	1.8	3.1	-	0.27 J	< 0.82 U	6.8	3.9	-	4.4	< 0.61 U	< 1.1 U	< 0.92 U	-	-	-	-	-	-	-
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721871	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721872	-	-	-	-	< 1.2 U	3.7	< 2.3 U	< 0.31 U	< 0.30 U	< 0.53 U	< 0.18 U	1.9	1.8 J	4.7	-	0.34 J	< 0.94 U	6.9	4.4	-	5.2	< 0.70 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-
MW-84S	MW-84S	9/9/2021	180-126905-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-84S	MW-84S	10/27/2021	180-129155-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-84S	SSHS-DUP-07-04152024	4/15/2024	1801726651	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-84S	SSHS-MW-84S-04152024	4/15/2024	1801726651	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-85I	MW-85I	7/15/2021	180-124580-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-85I	MW-85I	9/2/2021	180-126608-1	-	-	< 0.21 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-85I	SSHS-MW-85I-04222024	4/22/2024	1801730541	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-86I	MW-86I	7/13/2021	180-124378-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-86I	MW-86I	9/1/2021	180-126593-1	-	-	< 0.21 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-86I	SSHS-MW-86I-04042024	4/4/2024	1801719081	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-87I	MW-87I	7/14/2021	180-124487-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-87I	MW-87I	9/2/2021	180-126608-1	-	-	< 0.22 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-87I	SSHS-MW-87I-04112024	4/11/2024	1801722811	-	< 0.63 UT	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88I	MW-88I	7/15/2021	180-124580-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88I	MW-88I	9/2/2021	180-126608-1	-	-	< 0.21 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88I	SSHS-MW-88I-04112024	4/11/2024	1801722811	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88S	MW-88S	7/15/2021	180-124580-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88S	MW-88S	9/2/2021	180-126608-1	-	-	< 0.22 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88S	SSHS-MW-88S-04112024	4/11/2024	1801722811	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-89I	MW-89I	7/12/2021	180-124354-1	-	-	< 0.19 U	-	< 1.1 U	2.9	< 2 U	< 0.27 U	0.28 J	< 0.46 U	< 0.16 U	2	1.4 J	4.9	-	< 0.23 U	< 0.83 U	0.96 J	3.7	-	5.2	< 0.62 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-
MW-89I	MW-89I	9/1/2021	180-126593-1	-	-	< 0.22 U	< 13 U	< 1.2 U	3.4	2.4 J	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.5 J	1.5 J	2.6	-	< 0.26 U	< 0.93 U	1.7 J	3.4	-	4	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-89I	SSHS-MW-89I-04052024	4/5/2024	1801720031	-	< 0.79 UT	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-89S	MW-89S	7/12/2021	180-124354-1	-	-	< 0.19 U	-	< 1.1 U	3.3	2.7 J	< 0.27 U	0.35 J	< 0.47 U	< 0.16 U	2.1	1.6 J	4.5	-	< 0.23 U	< 0.83 U	2.3 I	3.9	-	5.4	< 0.62 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-
MW-89S	MW-89S	9/1/2021	180-126593-1	-	-	< 0.24 U	< 13 U	< 1.2 U	2.6	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.6 J	1.3 J	2.8	-	< 0.25 U	< 0.92 U	< 0.51 U	2.9	-	4.2	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733271	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733272	-	-	-	-	< 1.2 U	3.6	3.0 J	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	1.9	1.5 J	3.8	-	< 0.25 U	< 0.91 U	< 0.50 U	4.2	-	4.9	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-8I	MW-8I	7/1/2021	180-123971-1	-	-	< 0.19 U	-	< 1.3 U	3.7	2.8 J	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	1.8 J	1.3 J	3.9	-	< 0.26 U	< 0.95 U	< 0.52 U	3	-	4.5	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-8I	DUP-1	8/30/2021	180-126485-1	-	-	< 0.21 U	< 13 U	< 1.2 U	3.2	< 2.2 U	< 0.29 U	< 0.28 U	< 0.5 U	< 0.17 U	1.4 J	1.2 J	3.3	-	< 0.24 U	< 0.88 U	< 0.49 U	2.7	-	4.3	< 0.66 U	< 1.2 U	< 0.99 U	-	-	-	-	-	-	-
MW-8I	MW-8I	8/30/2021	180-126485-1	-	-	< 0.19 U	< 13 U	< 1.2 U	3.2	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.4 J	1.1 J	3.6	-	< 0.25 U	< 0.91 U	< 0.5 U	2.7	-	4.5	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733271	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733272	-	-	-	-	< 1.3 U	3.2	2.4 J	< 0.31 U	< 0.30 U	< 0.53 U	< 0.18 U	1.9	1.3 J	4.1	-	< 0.26 U	< 0.94 U	< 0.52 U	4.4	-	5.1	< 0.70 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-8S	MW-8S	2/18/2021	180-117476-1	-	-	< 0.17 U	-	< 1.2 U	2.6	< 2.3 U	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	1.3 J	1.6 J	1.8 J	-	< 0.25 U	< 0.92 U	1.2 J	3.5	-	5	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-8S	MW-8S	7/12/2021	180-124354-1	-	-	< 0.21 U	-	< 1.2 U	1.8 J	< 2.3 U	< 0.3 U	0.5 J	< 0.52 U	< 0.18 U	1.1 J	1.2 J	1.8 J	-	< 0.26 U	< 0.93 U	1.8 J,I	3.4	-	4.5	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
MW-90I	MW-90I	9/8/2021	180-126846-1	-	-	< 0.47 U	< 13 U	< 1.1 U	3.9	2.1 J	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	1.8	1.2 J	3.5	-	< 0.23 U	< 0.82 U	1.7	3.5	-	5	< 0.61 U	< 1.1 U	< 0.92 U	-	-	-	-	-	-	-
MW-90I	MW-90I	10/28/2021	180-129230-1	-	-	< 0.18 U	-	< 1.1 U	3.7	2.3 J	< 0.26 U	< 0.25 U	< 0.45 U	< 0.16 U	1.6	1.8	3.2	-	< 0.22 U	< 0.8 U	5.6	4.1	-	4.1	< 0.6 U	< 1.1 U	< 0.9 U	-	-	-	-	-	-	-
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721872	-	-	-	-	< 1.2 U	4.8	7.0	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	2.0	1.8 J	4.9	-	< 0.26 U	< 0.93 U	4.1	4.1	-	6.1	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-90S	MW-90S	9/8/2021	180-126846-1	-	-	< 0.47 U	< 13 U	< 1.1 U	6.6	3 J	< 0.26 U	< 0.25 U	< 0.45 U	< 0.16 U	1.6	2.4	1.9	-	0.28 J	< 0.8 U	10	5.2	-	3.4	< 0.6 U	< 1.1 U	< 0.9 U	-	-	-	-	-	-	-
MW-90S	MW-90S	10/28/2021	180-129230-1	-	-	< 0.18 U	-	< 1.1 U	4	2 J	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	1 J	2.1	1.7	-	< 0.23 U	< 0.83 U	6.7	2.7	-	2.1	< 0.61 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721871	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721872	-	-	-	-	< 1.2 U	5.6	4.1 J	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	2.2	2.4	6.3	-	0.49 J	< 0.92 U	13	7.8	-	7.0	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-91I	MW-91I	9/9/2021	180-126905-1	-	-	< 0.47 U	< 13 U	< 1.1 U	3.6	2.6 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	3.3	1.4 J	7.6	-	< 0.23 U	< 0.84 U	1.9	6	-	9.2	< 0.62 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-
MW-91I	MW-91I	11/2/2021	180-129534-1	-	-	< 0.19 U	-	< 1.2 U	2.8	< 2.3 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	0.67 J	1.3 J	1.3 J	-	< 0.26 U	< 0.94 U	1.2 J	2.2	-	1.5 J	< 0.7 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721872	-	-	-	-	< 1.2 U	3.9	2.7 J	< 0.30 U	< 0.29 U	< 0.52 U	< 0.18 U	1.4 J	1.4 J	3.4	-	< 0.25 U	< 0.92 U	1.5 J	3.0	-	4.4	< 0.69 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-91S	MW-91S	9/9/2021	180-126905-1	-	-	< 0.47 U	< 13 U	< 1.1 U	5.2	5.2	< 0.26 U	< 0.26 U	< 0.45 U	< 0.16 U	2.1	2	3.2	-	< 0.22 U	< 0.81 U	5.7	5.8	-	5.2	< 0.6 U	< 1.1 U	< 0.91 U	-	-	-	-	-	-	-
MW-91S	MW-91S	11/2/2021	180-129534-1	-	-	< 0.19 U	-	< 1.2 U	2.6	< 2.3 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	0.93 J	1.5 J	2.4	-	< 0.26 U	< 0.94 U	1.8 J	2	-	3.2	< 0.7 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722811	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-82S	SSHS-MW-82S-05012024	5/1/2024	1801733272	-	-	-	-	< 0.45 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-83I	MW-83I	9/8/2021	180-126846-1	-	-	-	-	< 0.38 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-83I	MW-83I	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83I	MW-83I	10/28/2021	180-129230-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83I	SSHS-MW-83I-04102024	4/10/2024	1801721872	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-83S	MW-83S	9/8/2021	180-126846-1	-	-	-	-	< 0.38 U	-	< 2.1 U	-	-	< 0.99 U	-	-	-
MW-83S	MW-83S	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83S	MW-83S	10/28/2021	180-129230-1	-	-	-	-	< 0.39 U	-	6.2	-	-	< 1 U	-	-	-
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-83S	SSHS-MW-83S-04102024	4/10/2024	1801721872	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-84S	MW-84S	9/9/2021	180-126905-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-84S	MW-84S	10/27/2021	180-129155-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-84S	SSHS-DUP-07-04152024	4/15/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-84S	SSHS-MW-84S-04152024	4/15/2024	1801726651	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-85I	MW-85I	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-85I	MW-85I	9/2/2021	180-126608-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-85I	SSHS-MW-85I-04222024	4/22/2024	1801730541	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-86I	MW-86I	7/13/2021	180-124378-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-86I	MW-86I	9/1/2021	180-126593-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-86I	SSHS-MW-86I-04042024	4/4/2024	1801719081	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-87I	MW-87I	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-87I	MW-87I	9/2/2021	180-126608-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-87I	SSHS-MW-87I-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88I	MW-88I	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88I	MW-88I	9/2/2021	180-126608-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88I	SSHS-MW-88I-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88S	MW-88S	7/15/2021	180-124580-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88S	MW-88S	9/2/2021	180-126608-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-88S	SSHS-MW-88S-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-89I	MW-89I	7/12/2021	180-124354-1	-	-	-	-	< 0.39 U	-	10	-	-	< 1 U	-	-	-
MW-89I	MW-89I	9/1/2021	180-126593-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-89I	SSHS-MW-89I-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-89S	MW-89S	7/12/2021	180-124354-1	-	-	-	-	< 0.39 U	-	5.6	-	-	< 1 U	-	-	-
MW-89S	MW-89S	9/1/2021	180-126593-1	-	-	-	-	< 0.43 U	-	3 J	-	-	< 1.1 U	-	-	-
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-89S	SSHS-MW-89S-04302024	4/30/2024	1801733272	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-8I	MW-8I	7/1/2021	180-123971-1	-	-	-	-	< 0.45 U	-	7.7	-	-	< 1.2 U	-	-	-
MW-8I	DUP-1	8/30/2021	180-126485-1	-	-	-	-	< 0.41 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-8I	MW-8I	8/30/2021	180-126485-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-8I	SSHS-MW-8I-04302024	4/30/2024	1801733272	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-8S	MW-8S	2/18/2021	180-117476-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-8S	MW-8S	7/12/2021	180-124354-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-90I	MW-90I	9/8/2021	180-126846-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-90I	MW-90I	10/28/2021	180-129230-1	-	-	-	-	< 0.38 U	-	< 2 U	-	-	< 0.98 U	-	-	-
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-90I	SSHS-MW-90I-04102024	4/10/2024	1801721872	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-90S	MW-90S	9/8/2021	180-126846-1	-	-	-	-	< 0.38 U	-	< 2.1 U	-	-	< 0.98 U	-	-	-
MW-90S	MW-90S	10/28/2021	180-129230-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-90S	SSHS-MW-90S-04102024	4/10/2024	1801721872	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-91I	MW-91I	9/9/2021	180-126905-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-91I	MW-91I	11/2/2021	180-129534-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-91I	SSHS-MW-91I-04102024	4/10/2024	1801721872	-	-	-	-	< 0.43 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-91S	MW-91S	9/9/2021	180-126905-1	-	-	-	-	< 0.38 U	-	< 2.1 U	-	-	< 0.99 U	-	-	-
MW-91S	MW-91S	11/2/2021	180-129534-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3ONS)
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7										
Location	Sample Name	Sample Date	Lab Report																														
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722812	-	-	-	-	< 1.2 U	4.4	< 2.2 U	< 0.30 U	< 0.29 U	< 0.51 U	< 0.18 U	0.89 J	1.2 J	1.2 J	-	< 0.25 U	< 0.91 U	2.0 EMPC	2.5	-	1.1 J	< 0.68 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-92I	MW-92I	9/10/2021	180-126939-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92I	MW-92I	10/28/2021	180-129230-1	-	-	< 0.18 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92I	SSHS-MW-92I-04082024	4/8/2024	1801720411	-	< 0.60 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92S	MW-92S	9/10/2021	180-126939-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92S	MW-92S	10/28/2021	180-129230-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92S	SSHS-MW-92S-04052024	4/5/2024	1801720031	-	< 0.60 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	DUP-4	9/9/2021	180-126905-1	-	-	< 0.47 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	MW-93I	9/9/2021	180-126905-1	-	-	< 0.49 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	MW-93I	10/29/2021	180-129376-1	-	-	< 0.18 U,*-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	SSHS-DUP-08-04112024	4/11/2024	1801722811	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	SSHS-MW-93I-04112024	4/11/2024	1801722811	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93S	MW-93S	9/9/2021	180-126905-1	-	-	< 0.56 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93S	MW-93S	10/29/2021	180-129376-1	-	-	< 0.18 U,F1,*-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93S	SSHS-MW-93S-04112024	4/11/2024	1801722811	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-94I	MW-94I	9/9/2021	180-126905-1	-	-	< 0.46 U	< 13 U	< 1.1 U	3.8	< 2 U	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	1.6 J	1.7	3.2	-	< 0.23 U	< 0.82 U	3	3.9	-	4.8	< 0.61 U	< 1.1 U	< 0.92 U	-	-	-	-	-	-	-
MW-94I	MW-94I	10/27/2021	180-129230-1	-	-	< 0.18 U	-	< 1.1 U	1.9	< 2.1 U	< 0.28 U	< 0.27 U	< 0.47 U	< 0.16 U	1.6 J	1.2 J	3	-	< 0.23 U	< 0.85 U	2.3	3.1	-	4.1	< 0.63 U	< 1.1 U	< 0.95 U	-	-	-	-	-	-	-
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722811	-	< 0.65 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722812	-	-	-	-	< 1.2 U	3.5	3.2 J	< 0.31 U	< 0.30 U	< 0.53 U	< 0.18 U	1.8 J	1.4 J	4.4	-	< 0.26 U	< 0.94 U	2.7	3.0	-	5.8	< 0.70 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-
MW-94S	MW-94S	9/9/2021	180-126905-1	-	-	< 0.46 U	< 13 U	< 1.1 U	3.6	2.1 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	2	1.7	3	-	< 0.23 U	< 0.83 U	8.7	4.6	-	4	< 0.62 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-
MW-94S	MW-94S	10/27/2021	180-126905-1	-	-	< 0.2 U	-	< 1.1 U	1.8	< 2.1 U	< 0.28 U	< 0.27 U	< 0.48 U	< 0.16 U	1.7	1.2 J	2.9	-	0.25 J	< 0.85 U	5.6	3.8	-	3.7	< 0.63 U	< 1.1 U	< 0.95 U	-	-	-	-	-	-	-
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722811	-	< 0.68 U	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722812	-	-	-	-	< 1.2 U	3.6	< 2.2 U	< 0.29 U	< 0.28 U	< 0.50 U	< 0.17 U	2.1	1.4 J	4.0	-	< 0.25 U	< 0.90 U	7.2	4.4	-	5.8	< 0.67 U	< 1.2 U	< 1.0 U	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682361	-	< 0.23 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682362	-	-	-	-	< 1.3 U	3.3	< 2.4 U	< 0.32 U	< 0.31 U	< 0.56 U	< 0.19 U	1.3 J	1.4 J	2.5	-	< 0.27 U	< 0.99 U	1.4 J	3.5	-	3.0	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-04112024	4/11/2024	1801722791	-	< 0.60 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-04112024	4/11/2024	1801722792	-	-	-	-	< 1.3 U	3.4	< 2.4 U	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	1.7 J	1.5 J	3.6	-	< 0.27 U	< 1.0 U	0.87 J	3.5	-	4.3	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624601	< 0.19 U	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624602	-	-	-	-	< 1.4 U	2.7	2.5 J	< 0.33 U	< 0.32 U	< 0.57 U	< 0.20 U	2.3	1.7 J	3.9	-	< 0.28 U	< 1.0 U	1.2 J	4.1	-	4.8	< 0.76 U	< 1.4 U	< 1.1 U	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653531	-	< 0.20 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653532	-	-	-	-	< 1.4 U	3.8	2.5 J	< 0.33 U	< 0.32 U	< 0.57 U	< 0.20 U	1.8 J	1.8 J	3.1	-	< 0.28 U	< 1.0 U	1.2 J	4.2	-	3.7	< 0.76 U	< 1.4 U	< 1.1 U	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682361	-	< 0.22 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682362	-	-	-	-	< 1.3 U	3.3	< 2.4 U	< 0.32 U	< 0.31 U	< 0.56 U	< 0.19 U	1.3 J	1.4 J	2.4	-	< 0.27 U	< 0.99 U	1.3 J	3.3	-	2.7	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-04112024	4/11/2024	1801722791	-	< 0.65 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-04112024	4/11/2024	1801722792	-	-	-	-	< 1.2 U	3.4	2.2 J	< 0.29 U	< 0.28 U	< 0.49 U	< 0.17 U	1.8	1.5 J	3.8	-	< 0.24 U	< 0.88 U	1.0 J	3.5	-	4.0	< 0.65 U	< 1.2 U	< 0.98 U	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624601	< 0.21 U	-	-	< 43 UT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624602	-	-	-	-	< 1.4 U	2.9	< 2.6 U	< 0.34 U	< 0.33 U	< 0.59 U	< 0.20 U	1.9 J	1.5 J	3.3	-	< 0.29 U	< 1.0 U	1.3 J	4.1	-	4.0	< 0.78 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653531	-	< 0.25 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653532	-	-	-	-	< 1.5 U	4.0	< 2.8 U	< 0.37 U	< 0.36 U	< 0.64 U	< 0.22 U	1.8 J	1.8 J	2.9	-	< 0.32 U	< 1.1 U	1.2 J	3.9	-	3.9	< 0.85 U	< 1.5 U	< 1.3 U	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682361	-	< 0.28 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682362	-	-	-	-	< 1.3 U	2.6	2.4 J	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	1.8 J	1.0 J	3.5	-	< 0.27 U	< 0.99 U	< 0.54 U	3.7	-	4.2	< 0.73 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721201	-	< 0.63 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721202	-	-	-	-	< 1.1 U	2.6	2.5 J	< 0.28 U	< 0.27 U	< 0.48 U	< 0.16 U	1.4 J	1.1 J	3.2	-	< 0.23 U	< 0.85 U	0.49 J	2.9	-	3.6	< 0.63 U	< 1.1 U	< 0.95 U	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559472	-	-	-	-	< 1.3 U	2.6	< 2.4 U	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	1.2 J	1.0 J	1.8 J	-	< 0.27 U	< 1.0 U	< 0.55 U	2.6	-	2.6	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-09152023	9/15/2023	1801625601	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-09152023	9/15/2023	1801625602	-	-	-	-	< 1.3 U	2.5	2.9 J	< 0.33 U	< 0.32 U	< 0.57 U	< 0.20 U	1.6 J	1.0 J	3.7	-	< 0.28 U	< 1.0 U	2.1	3.6	-	3.8	< 0.75 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653531	-	< 0.23 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653532	-	-	-	-	< 1.4 U	3.0	< 2.5 U	< 0.34 U	< 0.33 U	< 0.58 U	< 0.20 U	1.3 J	1.3 J	2.1	-	< 0.28 U	< 1.0 U	< 0.57 U	2.7	-	2.8	< 0.77 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682361	-	< 0.25 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682362	-	-	-	-	< 1.3 U	3.2	< 2.4 U	< 0.32 U	< 0.31 U	< 0.55 U	< 0.19 U	0.44 J	0.90 J	0.98 J	-	< 0.27 U	< 0.97 U	< 0.54 U	1.5 J	-	< 0.49 U	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721201	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721202	-	-	-	-	< 1.3 U	3.2	< 2.5 U	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	0.84 J	1.0 J	1.5 J	-	< 0.28 U	< 1.0 U	< 0.55 U	2.2	-	1.3 J	< 0.75 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559471	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559472	-	-	-	-	< 1.3 U	1.8 J	5.3	< 0.32 U	< 0.31 U	< 0.54 U	< 0.19 U	0.31 J	< 0.56 U	< 0.57 U	-	< 0.27 U	< 0.97 U	< 0.53 U	2.0	-	< 0.48 U	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-09152023	9/15/2023	1801625601	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-09152023	9/15/2023	1801625602	-	-	-	-	< 1.3 U	2.2	3.3 J	< 0.33 U	< 0.32 U	< 0.57 U	< 0.20 U	0.82 J	1.1 J	< 0.60 J	-	< 0.28 U	< 1.0 U	< 0.56 U	2.2	-	0.54 J	< 0.75 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653531	-	< 0.21 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653532	-	-	-	-	< 1.4 U	1.0 J	< 2.6 U	< 0.34 U	< 0.33 U	< 0.59 U	< 0.20 U	1.0 J	0.83 J	0.94 J	-	< 0.29 U	< 1.0 U	< 0.58 U	3.1	-	0.89 J	< 0.78 U	< 1.4 U	< 1.2 U	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-91S	SSHS-MW-91S-04112024	4/11/2024	1801722812	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-92I	MW-92I	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92I	MW-92I	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92I	SSHS-MW-92I-04082024	4/8/2024	1801720411	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92S	MW-92S	9/10/2021	180-126939-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92S	MW-92S	10/28/2021	180-129230-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-92S	SSHS-MW-92S-04052024	4/5/2024	1801720031	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	DUP-4	9/9/2021	180-126905-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	MW-93I	9/9/2021	180-126905-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	MW-93I	10/29/2021	180-129376-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	SSHS-DUP-08-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93I	SSHS-MW-93I-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93S	MW-93S	9/9/2021	180-126905-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93S	MW-93S	10/29/2021	180-129376-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-93S	SSHS-MW-93S-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-94I	MW-94I	9/9/2021	180-126905-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-94I	MW-94I	10/27/2021	180-129230-1	-	-	-	-	< 0.4 U	-	< 2.2 U	-	-	< 1 U	-	-	-
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-94I	SSHS-MW-94I-04112024	4/11/2024	1801722812	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-94S	MW-94S	9/9/2021	180-126905-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
MW-94S	MW-94S	10/27/2021	180-129230-1	-	-	-	-	< 0.4 U	-	< 2.2 U	-	-	< 1 U	-	-	-
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722811	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-94S	SSHS-MW-94S-04112024	4/11/2024	1801722812	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-01162024	1/16/2024	1801682362	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-95I	SSHS-MW-95I-04112024	4/11/2024	1801722791	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-04112024	4/11/2024	1801722792	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-09122023	9/12/2023	1801624602	-	-	-	-	< 0.48 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95I	SSHS-MW-95I-11142023	11/14/2023	1801653532	-	-	-	-	< 0.48 U	-	4.1 J	-	-	< 1.2 U	-	-	-
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-01162024	1/16/2024	1801682362	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-95S	SSHS-MW-95S-04112024	4/11/2024	1801722791	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-04112024	4/11/2024	1801722792	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-09122023	9/12/2023	1801624602	-	-	-	-	< 0.49 U	-	< 2.7 U	-	-	< 1.3 U	-	-	-
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-95S	SSHS-MW-95S-11142023	11/14/2023	1801653532	-	-	-	-	< 0.54 U	-	< 2.9 U	-	-	< 1.4 U	-	-	-
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-01172024	1/17/2024	1801682362	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-04092024	4/9/2024	1801721202	-	-	-	-	< 0.40 U	-	< 2.2 U	-	-	< 1.0 U	-	-	-
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-05022023	5/2/2023	1801559472	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-96	SSHS-MW-96-09152023	9/15/2023	1801625601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-09152023	9/15/2023	1801625602	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-96	SSHS-MW-96-11142023	11/14/2023	1801653532	-	-	-	-	< 0.49 U	-	< 2.6 U	-	-	< 1.3 U	-	-	-
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682361	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-01172024	1/17/2024	1801682362	-	-	-	-	< 0.46 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721201	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-04092024	4/9/2024	1801721202	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559471	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-05022023	5/2/2023	1801559472	-	-	-	-	< 0.45 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-97	SSHS-MW-97-09152023	9/15/2023	1801625601	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-09152023	9/15/2023	1801625602	-	-	-	-	< 0.47 U	-	< 2.6 U	-	-	< 1.2 U	-	-	-
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653531	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-97	SSHS-MW-97-11142023	11/14/2023	1801653532	-	-	-	-	< 0.49 U	-	< 2.7 U	-	-	< 1.3 U	-	-	-

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3ONS)
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35															2.7	6.7											
Location	Sample Name	Sample Date	Lab Report																														
MW-98I	DUP-01	9/1/2022	1801438881	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	MW-98I	9/1/2022	1801438881	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	SSHS-MW-98I-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624611	< 0.22 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624612	-	-	-	-	< 1.3 U	2.8	2.8 J	< 0.33 U	< 0.32 U	< 0.56 U	< 0.19 U	1.6 J	0.96 J	4.3 B	-	< 0.27 U	< 1.0 U	< 0.55 U	2.6	-	4.4	< 0.74 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-98S	MW-98S	9/1/2022	1801438881	< 0.19 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98S	SSHS-MW-98S-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624611	< 0.21 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624612	-	-	-	-	< 1.3 U	2.5	2.6 J	< 0.31 U	< 0.30 U	< 0.54 U	< 0.19 U	1.4 J	0.84 J	3.3 B	-	< 0.27 U	< 0.96 U	< 0.53 U	3.1	-	3.7	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-99I	SSHS-MW-99I-04102024	4/10/2024	1801721871	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99I	SSHS-MW-99I-09132023	9/13/2023	1801624611	< 0.22 U	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721871	-	< 0.68 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721872	-	-	-	-	< 1.2 U	2.7	< 2.1 U	< 0.28 U	< 0.27 U	0.69 J	< 0.17 U	1.1 J	0.81 J	2.8	-	< 0.24 U	< 0.87 U	< 0.48 U	2.1	-	3.4	< 0.65 U	< 1.2 U	< 0.97 U	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624611	< 0.21 UT	-	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624612	-	-	-	-	< 1.2 U	2.8	6.1	< 0.28 U	< 0.28 U	< 0.49 U	< 0.17 U	3.5	0.89 J	6.6 B	-	< 0.24 U	< 0.87 U	< 0.48 U	3.6	-	8.6	< 0.65 U	< 1.2 U	< 0.98 U	-	-	-	-	-	-	-	-
MW-9I	MW-9I	7/14/2021	180-124487-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9I	MW-9I	8/31/2021	180-126501-1	-	-	< 0.21 U	< 13 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733271	-	< 0.65 U	-	< 43 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733272	-	-	-	-	< 1.2 U	3.3	< 2.3 U	< 0.31 U	< 0.30 U	< 0.53 U	< 0.18 U	1.9	1.3 J	4.4	-	< 0.26 U	< 0.94 U	< 0.52 U	4.3	-	5.5	< 0.70 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-	-
MW-9S	MW-9	2/20/2021	180-117476-1	-	-	< 0.16 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9S	MW-9	7/14/2021	180-124487-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	8/12/2021	1801253661	-	-	< 0.20 U	-	< 1.1 U	2.8	2.0 J	< 0.26 U	< 0.25 U	< 0.45 U	< 0.16 U	1.9	1.6	4.6	-	< 0.22 U	0.83 J	5.2	3.5	-	5.4	< 0.60 U	< 1.1 U	< 0.90 U	-	-	-	-	-	-	-	-
SSHS-B2541	SSHS-B2541-GW	10/29/2018	180-83541-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2542	SSHS-B2542-GW	10/29/2018	180-83541-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2543	SSHS-B2543-GW	10/30/2018	180-83544-1	-	-	< 0.19 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2544	SSHS-B2544-GW	10/30/2018	180-83544-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2629	SSHS-B2629	4/25/2019	180-89520-1	-	-	< 0.21 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B26-A	SSHS-B26-A-GW-18-22	8/14/2014	180-35818-2	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2752	SSHS-B2752	4/25/2019	180-89520-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B29-A	SSHS-B29-A-GW-18-22	8/13/2014	180-35776-2	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B3088	TAC22_B3088 (180-93333-9)	7/27/2019	2056373	-	-	-	-	< 0.48 U	4.1	3.5 J	< 0.48 U	< 0.48 U	< 0.48 U	< 0.48 U	2	1.1 J	3.6	-	< 0.48 U	< 0.48 U	< 0.48 U	4.1	-	4.4	< 0.48 U	< 0.48 U	< 0.48 U	-	-	-	-	-	-	-	-
SSHS-B3089	TAC22_B3089 (180-93333-8)	7/26/2019	2056373	-	-	-	-	< 0.45 U	4.2	2.8 J	< 0.45 U	< 0.45 U	< 0.45 U	< 0.45 U	1.9	1.4 J	3.5	-	< 0.45 U	< 0.45 U	0.68 J	4.3	-	4.1	< 0.45 U	< 0.45 U	< 0.45 U	-	-	-	-	-	-	-	-
SSHS-B3200A	DUP-01	9/15/2019	180-95745-1	-	-	< 0.19 U	-	< 1.7 U	2.5	1.7 J	2.1	< 0.28 U	< 0.5 U	< 0.17 U	1.8	1.8 B	3.4	-	0.25 J	< 0.32 U	9.4 B	4.6	-	3.8	< 0.26 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-B3200A	SSHS-B3200a	9/15/2019	180-95745-1	-	-	< 0.2 U	-	< 1.8 U	2.5	1.7 J	1.8 J	< 0.29 U	< 0.52 U	< 0.18 U	1.8 J	< 0.16 J,B	3.2	-	0.29 J	< 0.33 U	8.7 B	4.3	-	3.6	< 0.27 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-B3200B	SSHS-B3200b	9/15/2019	180-95745-1	-	-	-	-	< 1.8 U	2.9	2.3	< 0.3 U	< 0.29 U	< 0.52 U	< 0.18 U	2.6	2.2 B	5	-	< 0.25 U	< 0.33 U	5.6 B	5.6	-	5.9	< 0.27 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-B3203A	SSHS-3203a	9/13/2019	180-95715-1	-	-	< 0.2 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B3205A	SSHS-B3205a	9/14/2019	180-95745-1	-	-	-	-	< 1.8 U	3	2	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.5 J	2.1 B	2.8	-	< 0.25 U	< 0.33 U	7.8 B	3.6	-	3.2	< 0.27 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-B3205B	SSHS-B3205b	9/14/2019	180-95745-1	-	-	-	-	< 1.9 U	3.2	2.3	0.35 J	< 0.31 U	< 0.55 U	< 0.19 U	2.1	2.4 B	4.2	-	0.47 J	< 0.35 U	11 B	5.4	-	5	< 0.29 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-	-
SSHS-B510	SSHS-B510	9/20/2016	180-58901-1	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B572A	SSHS-B572A	9/2/2016	180-58309-2	-	-	< 0.055 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575A	SSHS-B575A	9/19/2016	180-58899-1	-	-	< 0.15 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575B	SSHS-B575B	9/19/2016	180-58899-1	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575C	PS-FD-54	9/19/2016	180-58899-1	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575C	SSHS-B575C	9/21/2016	180-58975-1	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B99	SSHS-99-GW-17-21	8/13/2014	180-35776-2	-	-	< 0.14 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	7/1/2021	180-123971-1	-	-	< 0.19 U,F1	-	< 1.1 U	2.2	< 2.1 U	< 0.27 U	0.33 J	< 0.47 U	< 0.16 U	4.3	1.4 J	13	-	< 0.23 U	< 0.84 U	< 0.46 U	5.3	-	22	< 0.63 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-	-
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	4/9/2021	180-119810-1	-	-	< 0.19 U	-	< 1.1 U	3	3.1 J	< 0.27 U	< 0.26 U	< 0.47 U	< 0.16 U	1.8	1.2 J	4.8	-	< 0.23 U	1.5 J	< 0.46 U	3.4	-	6.6	< 0.62 U	< 1.1 U	< 0.94 U	-	-	-	-	-	-	-	-
SSHS-RI-B3860I TEMP	DUP-GW-02	4/15/2021	180-120162-1	-	-	< 0.19 U	-	< 1.2 U	3.1	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.1 J	1.3 J	2.9	-	< 0.25 U	< 0.91 U	0.55 J	2.2	-	3.9	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	4/15/2021	180-120162-1	-	-	< 0.19 U	-	< 1.2 U	2.8	< 2.2 U	< 0.29 U	< 0.28 U	< 0.5 U	< 0.17 U	1 J	1.4 J	2.8	-	< 0.24 U	< 0.89 U	0.71 J	2.6	-	4	< 0.66 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	4/13/2021	180-119930-1	-	-	< 0.19 U	-	< 1.2 U	3.1	11	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	0.57 J	1.4 J	1.4 J	-	< 0.25 U	< 0.91 U	3.3	2.5	-	4.3	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	4/9/2021	180-119810-1	-	-	< 0.19 U	-	< 11 U	5.3 J,F2,I	39 J,F2,F1	< 2.8 U,F2	< 2.7 U	< 4.8 U	< 1.7 U	< 2.2 U,F1	< 5 U	< 5.1 U	-	< 2.4 U	< 8.6 U	13 J	7.5 J	-	< 4.3 U,F2,F1	< 6.4 U	< 11 U	< 9.7 U	-	-	-	-	-	-	-	-
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	4/9/2021	180-119810-1	-	-	< 0.19 U	-	< 11 U	< 1.7 U	77	< 2.8 U	< 2.7 U	< 4.8 U	< 1.7 U	< 2.2 U	< 5 U	< 5.1 U	-	< 2.4 U	< 8.5 U	13 J	< 7.4 U	-	< 4.3 U	< 6.4 U	< 11 U	< 9.6 U	-	-	-	-	-	-	-	-
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	4/6/2021	180-119589-1	-	-	< 0.19 U	-	< 1.2 U	2.3 *+	2.4 J	< 0.29 U	< 0.29 U	< 0.51 U	< 0.17 U	3.2	0.75 J	6.2	-	0.5 J	< 0.9 U	1.8	6.4	-	9.1 *+	< 0.67 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	4/7/2021	180-119649-1	-	-	< 0.19 U	-	< 1.2 U	1.8 J	2.3 J	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	1.3 J	0.75 J	2.9	-	< 0.26 U	< 0.94 U	< 0.52 U	2	-	3.9	< 0.7 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	4/14/2021	180-120029-1	-	-	< 0.19 U	-	< 1.1 U	2.8	4.6	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	2.4	1.3 J	6.9	-	< 0.23 U	< 0.82 U	< 0.45 U	3.1	-	8.8	< 0.61 U	< 1.1 U	< 0.93 U	-	-	-	-	-	-	-	-
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	4/14/2021	180-120029-1	-	-	< 0.19 U	-	< 1.1 U	2.9 CI	33	< 0.27 U	< 0.26 U	< 0.46 U	< 0.16 U	0.56 J	1.8	1.2 J	-	< 0.22 U	< 0.82 U	5.7	2.4	-	0.93 J	< 0.61 U	< 1.1 U	< 0.92 U	-	-	-	-	-	-	-	-
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	5/14/2021	180-121703-1	-	-	< 0.21 U	-	< 1.2 U	2.8	< 2.2 U	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	1.9	0.96 J	3.8	-	< 0.25 U	< 0.92 U	< 0.5 U	3	-	4.8	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3886-TEMP	DUP-GW-01	5/19/2021	180-121897-1	-	-	< 0.2 U	-	< 1.2 U	3.4	3.2 J	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	3.4	1.1 J	8.2	-	< 0.25 U	< 0.91 U	1.1 J	7.1	-	10	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	5/19/2021	180-121897-1	-	-	< 0.2 U	-	< 1.2 U	3	3.6 J	< 0.3 U	< 0.29 U	< 0.51 U	< 0.18 U	3.9	1.1 J	7.6	-	< 0.25 U	< 0.91 U	< 0.5 U	7.2	-	11	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
MW-98I	DUP-01	9/1/2022	1801438881	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	MW-98I	9/1/2022	1801438881	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	SSHS-MW-98I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98I	SSHS-MW-98I-09132023	9/13/2023	1801624612	-	-	-	-	< 0.47 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-98S	MW-98S	9/1/2022	1801438881	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98S	SSHS-MW-98S-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-98S	SSHS-MW-98S-09132023	9/13/2023	1801624612	-	-	-	-	< 0.45 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
MW-99I	SSHS-MW-99I-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99I	SSHS-MW-99I-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721871	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-04102024	4/10/2024	1801721872	-	-	-	-	0.55 J	-	< 2.2 U	-	-	< 1.1 U	-	-	-
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624611	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-99S	SSHS-MW-99S-09132023	9/13/2023	1801624612	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
MW-9I	MW-9I	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9I	MW-9I	8/31/2021	180-126501-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733271	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9I	SSHS-MW-9I-04292024	4/29/2024	1801733272	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
MW-9S	MW-9	2/20/2021	180-117476-1	-	-	-	-	-	-	-	-	-	-	-	-	-
MW-9S	MW-9	7/14/2021	180-124487-1	-	-	-	-	-	-	-	-	-	-	-	-	-
RI-SUPPLY-WELL-EFF	SSHS-RI-SUPPLY-WELL-EFFLUENT	8/12/2021	1801253661	-	-	-	-	< 0.38 U	-	< 2.0 U	-	-	< 0.98 U	-	-	-
SSHS-B2541	SSHS-B2541-GW	10/29/2018	180-83541-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2542	SSHS-B2542-GW	10/29/2018	180-83541-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2543	SSHS-B2543-GW	10/30/2018	180-83544-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2544	SSHS-B2544-GW	10/30/2018	180-83544-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2629	SSHS-B2629	4/25/2019	180-89520-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B26-A	SSHS-B26-A-GW-18-22	8/14/2014	180-35818-2	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B2752	SSHS-B2752	4/25/2019	180-89520-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B29-A	SSHS-B29-A-GW-18-22	8/13/2014	180-35776-2	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B3088	TAC22_B3088 (180-93333-9)	7/27/2019	2056373	-	-	-	-	< 0.97 U	-	< 1.9 U	-	-	< 0.58 U	-	-	-
SSHS-B3089	TAC22_B3089 (180-93333-8)	7/26/2019	2056373	-	-	-	-	< 0.89 U	-	< 1.8 U	-	-	< 0.54 U	-	-	-
SSHS-B3200A	DUP-01	9/15/2019	180-95745-1	-	-	-	-	< 1.8 U	-	< 1.8 U	-	-	< 2.8 U	-	-	-
SSHS-B3200A	SSHS-B3200a	9/15/2019	180-95745-1	-	-	-	-	< 1.9 U	-	< 1.9 U	-	-	< 2.9 U	-	-	-
SSHS-B3200B	SSHS-B3200b	9/15/2019	180-95745-1	-	-	-	-	< 1.9 U	-	< 1.9 U	-	-	< 2.9 U	-	-	-
SSHS-B3203A	SSHS-3203a	9/13/2019	180-95715-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B3205A	SSHS-B3205a	9/14/2019	180-95745-1	-	-	-	-	< 1.9 U	-	< 1.9 U	-	-	< 2.9 U	-	-	-
SSHS-B3205B	SSHS-B3205b	9/14/2019	180-95745-1	-	-	-	-	< 2 U	-	< 2 U	-	-	< 3.1 U	-	-	-
SSHS-B510	SSHS-B510	9/20/2016	180-58901-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B572A	SSHS-B572A	9/2/2016	180-58309-2	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575A	SSHS-B575A	9/19/2016	180-58899-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575B	SSHS-B575B	9/19/2016	180-58899-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575C	PS-FD-54	9/19/2016	180-58899-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B575C	SSHS-B575C	9/21/2016	180-58975-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-B99	SSHS-99-GW-17-21	8/13/2014	180-35776-2	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-RI-B3120A TEMP	SSHS-RI-B3120A TEMP	7/1/2021	180-123971-1	-	-	-	-	< 0.4 U	-	10	-	-	< 1 U	-	-	-
SSHS-RI-B3857 TEMP	SSHS-RI-B3857 TEMP	4/9/2021	180-119810-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
SSHS-RI-B3860I TEMP	DUP-GW-02	4/15/2021	180-120162-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3860I TEMP	SSHS-RI-B3860I TEMP	4/15/2021	180-120162-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3864I TEMP	SSHS-RI-B3864I TEMP	4/13/2021	180-119930-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3865I TEMP	SSHS-RI-B3865I TEMP	4/9/2021	180-119810-1	-	-	-	-	< 4 U	-	< 22 U	-	-	< 11 U	-	-	-
SSHS-RI-B3865S TEMP	SSHS-RI-B3865S TEMP	4/9/2021	180-119810-1	-	-	-	-	< 4 U	-	< 22 U	-	-	< 10 U	-	-	-
SSHS-RI-B3867 TEMP	SSHS-RI-B3867 TEMP	4/6/2021	180-119589-1	-	-	-	-	< 0.42 U,*+	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3874 TEMP	SSHS-RI-B3874 TEMP	4/7/2021	180-119649-1	-	-	-	-	< 0.44 U	-	4.3 J	-	-	< 1.1 U	-	-	-
SSHS-RI-B3877I TEMP	SSHS-RI-B3877I TEMP	4/14/2021	180-120029-1	-	-	-	-	< 0.39 U	-	< 2.1 U	-	-	< 1 U	-	-	-
SSHS-RI-B3877S TEMP	SSHS-RI-B3877S TEMP	4/14/2021	180-120029-1	-	-	-	-	< 0.38 U	-	< 2.1 U	-	-	< 1 U	-	-	-
SSHS-RI-B3882-TEMP	SSHS-RI-B3882-TEMP	5/14/2021	180-121703-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3886-TEMP	DUP-GW-01	5/19/2021	180-121897-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3886-TEMP	SSHS-RI-B3886-TEMP	5/19/2021	180-121897-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D_LL	1,4-Dioxane Lab Method 8260	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanesulfonic acid (PFNS)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanesulfonic acid (PFPeS)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTriA)	Perfluoroundecanoic acid (PFUnA)	11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	PERFLUORO(2-PROPOXYPROPANOIC) ACID	Perfluoro(2-Ethoxyethane)Sulfonic Acid (PFEESA)	Nonafluoro-3,6-Dioxaheptanoic Acid (NFDHA)	N-Methyl Perfluorooctane Sulfonamide (NMeFOSA)	N-Ethyl Perfluorooctane Sulfonamide (NEtFOSA)	9-Chlorohexadecafluoro-3-Oxanone-1-Sulfonic Acid (9Cl-PF3
				ug/l	ug/l	ug/l		ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values				0.35	0.35	0.35																2.7	6.7										
Location	Sample Name	Sample Date	Lab Report																														
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	5/11/2021	180-121472-1	-	-	< 0.2 U	-	< 1.1 U	3	2.1 J	< 0.28 U	< 0.27 U	< 0.48 U	< 0.17 U	2	1.2 J	4.1	-	< 0.24 U	< 0.86 U	0.58 J	2.9	-	4.7	< 0.64 U	< 1.1 U	< 0.97 U	-	-	-	-	-	-	-
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	5/11/2021	180-121472-1	-	-	< 0.21 U	-	< 1.2 U	2.7	4.6 J	< 0.3 U	0.33 J	< 0.52 U	< 0.18 U	2.6	1.2 J	6	-	0.37 J	1 J	1.1 J,I	4.8	-	6.2	< 0.68 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	5/13/2021	180-121702-1	-	-	< 0.19 U	-	< 1.2 U	2.3	3.3 J	< 0.3 U	0.3 J	< 0.52 U	< 0.18 U	1.9	1.2 J	5.6	-	< 0.26 U	< 0.93 U	0.73 J	3.2	-	7.3	< 0.69 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	5/12/2021	180-121546-1	-	-	< 0.19 U	-	< 1.2 U	3.1	2.3 J	< 0.29 U	< 0.28 U	< 0.51 U	< 0.17 U	1.6 J	1.1 J	3.9	-	< 0.25 U	< 0.9 U	< 0.5 U	2.6	-	5.5	< 0.67 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	7/23/2021	180-124918-1	-	-	< 0.22 U	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	7/26/2021	180-124974-1	-	-	< 0.22 U	-	< 1.2 U	3	2.5 J	< 0.29 U	< 0.28 U	< 0.5 U	< 0.17 U	1.1 J	1.5 J	2.6	-	< 0.25 U	< 0.89 U	2.3	3	-	2.9	< 0.66 U	< 1.2 U	< 1 U	-	-	-	-	-	-	-
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	7/28/2021	180-125087-1	-	-	< 0.16 U	-	< 1.1 U	3.6	< 2.1 U	< 0.28 U	< 0.27 U	< 0.48 U	< 0.17 U	1.5 J	1.2 J	2.6	-	< 0.23 U	< 0.85 U	< 0.47 U	2.9	-	3.6	< 0.64 U	< 1.1 U	< 0.96 U	-	-	-	-	-	-	-
SSHS-RI-B4152I-TEMP	DUP-01	7/28/2021	180-125087-1	-	-	< 0.16 U	-	< 1.1 U	< 0.18	< 2.1 U	< 0.28 U	< 0.27 U	< 0.49 U	< 0.17 U	< 0.22 J	< 0.5 J	-	-	< 0.24 U	< 0.87 U	< 0.48 U	< 0.75	-	-	< 0.65 U	< 1.1 U	< 0.97 U	-	-	-	-	-	-	-
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	7/29/2021	180-125127-1	-	-	< 0.2 U	-	< 1.3 U	2	7.9	< 0.32 U	< 0.31 U	< 0.54 U	0.24 J	2	2.4	3.7	-	0.44 J	< 0.97 U	5.7	5.3	-	4.8	< 0.72 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	7/28/2021	180-125087-1	-	-	< 0.19 U	-	< 1.2 U	3.9	< 2.3 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	1.5 J	1.2 J	2.8	-	< 0.26 U	< 0.94 U	< 0.52 U	3.8	-	3.7	< 0.7 U	< 1.2 U	< 1.1 U	-	-	-	-	-	-	-
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	7/27/2021	180-125052-1	-	-	< 0.16 U	-	< 1.1 U	2.9	5.4	< 0.28 U	< 0.27 U	< 0.48 U	< 0.17 U	1.8	1.7	2.8	-	0.36 J	< 0.85 U	3.4	4	-	4.1	< 0.64 U	< 1.1 U	< 0.96 U	-	-	-	-	-	-	-
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	7/27/2021	180-125052-1	-	-	< 0.21 U	-	< 1.3 U	3	< 2.3 U	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	1.6 J	1.1 J	2.7	-	< 0.26 U	< 0.95 U	< 0.52 U	3.1	-	3.2	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	7/26/2021	180-124974-1	-	-	< 0.2 U	-	< 1.1 U	2.3	5.2	< 0.28 U	< 0.27 U	< 0.48 U	< 0.16 U	1.9	1.6 J	2.8	-	0.51 J	< 0.85 U	4.8	4.4	-	4.1	< 0.63 U	< 1.1 U	< 0.95 U	-	-	-	-	-	-	-
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	7/29/2021	180-125127-1	-	-	< 0.18 U	-	< 1.3 U	3.3	2.3 J	< 0.31 U	< 0.3 U	< 0.53 U	< 0.18 U	2.3	2.2	4.9	-	< 0.26 U	0.95 J	7.4 I	4.5	-	6.5	< 0.71 U	< 1.3 U	< 1.1 U	-	-	-	-	-	-	-

Notes
ug/l = micrograms per liter
ng/l = nanograms per liter
* = LCS or LCSD is outside acceptance limits
B = Compound detected in method blank
F1 = MS and/or MSD Recovery is outside acceptance limits
I = Value is EMPC (estimated maximum possible concentration)
EMPC = Estimated maximum possible concentration
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab Method used: SW8270D/8270E/8270D_LL/8260 - 1,4-Dioxane
Lab Method used: E537(M)/PFC_IDA - PFAS

Analyte concentrations detected above NYSDEC guidance values are presented in blue

DRAFT

TABLE 5-12
Groundwater Results - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

				4,8-Dioxa-3h-Perfluorononanoic Acid (ADONA)	Perfluoro-3-Methoxypropanoic Acid (PFMPA)	Perfluoro-4-Methoxybutanoic Acid (PFMBA)	Perfluorododecane Sulfonic Acid (PFDoDS)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorohexane Sulfonate (4:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-ethyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluoro-1-octanesulfonamido)-ethanol	2-(N-methyl perfluorooctanesulfonamido) acetic acid	2H,2H,3H,3H-Perfluorooctanoic acid	3-Perfluoroheptyl propanoic acid	3-Perfluoropropyl propanoic acid
				ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l	ng/l
NYSDEC Guidance Values																
Location	Sample Name	Sample Date	Lab Report													
SSHS-RI-B3907I-TEMP	SSHS-RI-B3907I-TEMP	5/11/2021	180-121472-1	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3907S-TEMP	SSHS-RI-B3907S-TEMP	5/11/2021	180-121472-1	-	-	-	-	< 0.43 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3914-TEMP	SSHS-RI-B3914-TEMP	5/13/2021	180-121702-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B3915-TEMP	SSHS-RI-B3915-TEMP	5/12/2021	180-121546-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B4150I-TEMP	SSHS-RI-B4150I-TEMP	7/23/2021	180-124918-1	-	-	-	-	-	-	-	-	-	-	-	-	-
SSHS-RI-B4150S-TEMP	SSHS-RI-B4150S-TEMP	7/26/2021	180-124974-1	-	-	-	-	< 0.42 U	-	< 2.3 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B4152I-TEMP	SSHS-RI-B4152I-TEMP	7/28/2021	180-125087-1	-	-	-	-	< 0.4 U	-	< 2.2 U	-	-	< 1 U	-	-	-
SSHS-RI-B4152I-TEMP	DUP-01	7/28/2021	180-125087-1	-	-	-	-	< 0.41 U	-	< 2.2 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B4152S-TEMP	SSHS-RI-B4152S-TEMP	7/29/2021	180-125127-1	-	-	-	-	< 0.45 U	-	< 2.5 U	-	-	< 1.2 U	-	-	-
SSHS-RI-B4153I-TEMP	SSHS-RI-B4153I-TEMP	7/28/2021	180-125087-1	-	-	-	-	< 0.44 U	-	< 2.4 U	-	-	< 1.1 U	-	-	-
SSHS-RI-B4153S-TEMP	SSHS-RI-B4153S-TEMP	7/27/2021	180-125052-1	-	-	-	-	< 0.4 U	-	< 2.2 U	-	-	< 1 U	-	-	-
SSHS-RI-B4154I-TEMP	SSHS-RI-B4154I-TEMP	7/27/2021	180-125052-1	-	-	-	-	< 0.45 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-
SSHS-RI-B4154S-TEMP	SSHS-RI-B4154S-TEMP	7/26/2021	180-124974-1	-	-	-	-	< 0.4 U	-	< 2.2 U	-	-	< 1 U	-	-	-
SSHS-RI-S-WELL-1	SSHS-RI-SUPPLY-WELL-1	7/29/2021	180-125127-1	-	-	-	-	< 0.45 U	-	< 2.4 U	-	-	< 1.2 U	-	-	-

Notes
ug/l = micrograms per liter
ng/l = nanograms per liter
* = LCS or LCSD is outside acceptance limits
B = Compound detected in method blank
F1 = MS and/or MSD Recovery is outside acceptance limits
I = Value is EMPC (estimated maximum possible concentration)
EMPC = Estimated maximum possible concentration
J = Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value
T = Indicates that a quality control parameter has exceeded laboratory limits
U = Non-detect at the value indicated
- = No data
Lab Method used: SW8270D/8270E/8270D_LL/8260 - 1,4-Dioxane
Lab Method used: E537(M)/PFC_IDA - PFAS

Analyte concentrations detected above NYSDEC guidance values are presented in blue

DRAFT

TABLE 5-13
FIS Fine-Grained Material Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

										Sample Name	SSHS-B2771-SUB-10-12	SSHS-B2771-SUB-6-8	SSHS-B2771-SUB-8-10	SSHS-B2772-SUB-6-8	SSHS-B2772-SUB-8-10	SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-8-10	SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-8-10
										Sample Date	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019
Group	**Chemical**	**Units**	**EQL**	**Unrestricted SCOs**	**Restricted Residential SCOs**	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)	NYS Hazardous Waste	***Protection of Groundwater***										
Metals	Aluminum	mg/kg	11								5500 F2	7500	5700	5900	6100	4600	5400	5000	4200
	Antimony	mg/kg	0.3								< 1.1 U,F1	< 1.2 U	< 1.1 U	< 1 U	< 1.1 U	< 1.1 U	< 1.1 U	< 1.1 U	< 1 U
	Arsenic	mg/kg	0.61	13	16	33	100		16		2.9	5.7	4	6.3	6.9	***17***	12	5.9	***21***
	Barium	mg/kg	11	350	400		2000		820		220 F2,F1	79	39	84	95	54	56	53	46
	Beryllium	mg/kg	0.22	7.2	72				47		0.17 J	0.33 J	0.22 J	0.24 J	0.24 J	0.24 J	0.27 J	0.19 J	0.17 J
	Cadmium	mg/kg	0.3	2.5	4.3	5	20		7.5		0.098 J	0.099 J	0.12 J	0.09 J	0.13 J	0.14 J	0.12 J	0.089 J	0.066 J
	Calcium	mg/kg	280								31000 F2	47000	42000	55000	43000	65000	40000	43000	32000
	Chromium (III+VI)	mg/kg	0.28	1	110	110	100		19		**8.1**	**10**	**8.3**	**8.3**	**12**	**8.5**	**9.4**	**7.9**	**6.3**
	Cobalt	mg/kg	2.6								5 J	5.1 J	5.2 J	5.3	5.6	5 J	4.8 J	4.3 J	3.8 J
	Copper	mg/kg	1.5	50	270	150			1720		19	21	23	24 B	39 B	31 B	31 B	31 B	21 B
	Iron	mg/kg	6.1								12000 F2	13000	13000	14000	15000	12000	13000	12000	10000
	Lead	mg/kg	0.66	63	400	130	1000		450		7	**72**	10	12	16	9.8	9.7	6.2	5.2
	Magnesium	mg/kg	280								6300	4200	5300	7300	5900	9600	11000	10000	6100
	Manganese	mg/kg	0.84	1600	2000				2000		340	520	400	360	400	380	390	390	250
	Mercury	mg/kg	0.013	0.18	0.81	1	4		0.73		< 0.027 U,F1	< 0.037 U	< 0.034 U	< 0.031 U	< 0.038 U	< 0.038 U	< 0.025 U	< 0.026 U	< 0.023 U
	Nickel	mg/kg	2.7	30	310	49			130		13	14	15	14	15	18	15	11	10
	Potassium	mg/kg	280								1200	750	550 J	620	740	560	610	540 J	490 J
	Selenium	mg/kg	0.34	3.9	180		20		4		< 1.1 U	1.1 J	< 1.1 U	0.57 J	0.67 J	1.2	0.58 J	< 1.1 U	< 1 U
	Sodium	mg/kg	78								75 J	110 J	87 J	86 J	87 J	99 J	81 J	77 J	73 J
	Silver	mg/kg	0.025	2	180	2.2	100		8.3		< 0.54 U	< 0.58 U	< 0.56 U	< 0.52 U	< 0.56 U	< 0.55 U	< 0.55 U	< 0.56 U	< 0.52 U
	Thallium	mg/kg	0.089								< 2.2 U	< 2.3 U	< 2.2 U	< 2.1 U	< 2.2 U	< 2.2 U	< 2.2 U	< 2.2 U	< 2.1 U
	Vanadium	mg/kg	2.8								11	11	10	9.5	10	8.7	8.5	8.6	6.5
	Zinc	mg/kg	1.2	109	10000	460			2480		53 F2,F1	47	90	52	63	110	60	52	49
Polychlorinated Biphenyls	Arochlor 1016	mg/kg	0.00053								< 0.017 U,F1	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.017 U
	Arochlor 1221	mg/kg	0.00065								< 0.017 U	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.017 U
	Arochlor 1232	mg/kg	0.0009								< 0.017 U	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.017 U
	Arochlor 1242	mg/kg	0.00066								< 0.017 U	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.017 U
	Arochlor 1248	mg/kg	0.00065								< 0.017 U	0.013 J	< 0.018 U	0.019	0.017 J,p	< 0.018 U	< 0.018 U	0.0061 J,p	< 0.017 U
	Arochlor 1254	mg/kg	0.0026								< 0.017 U	< 0.019 U	< 0.018 U	0.033	0.025	0.17	0.29	0.076	0.036
	Arochlor 1260	mg/kg	0.0026								< 0.017 U,F1,F2	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	0.13	0.22	0.068	0.037
	Arochlor 1268	mg/kg	0.00053								< 0.017 U	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.017 U
	Arochlor 1262	mg/kg	0.00096								< 0.017 U	< 0.019 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.017 U
	Total PCBs	mg/kg		0.1	1	1		50	3.2		ND	0.013	ND	0.052	0.042	**0.3**	**0.51**	**0.1501**	0.073
	Total PAHs	mg/kg				3.5	100				-	-	-	-	-	-	-	-	-
	1,1-Biphenyl	mg/kg	0.012								-	-	-	-	-	-	-	-	-
	1,2,4,5-tetrachlorobenzene	mg/kg	0.01			14					-	-	-	-	-	-	-	-	-
	1,4-Dioxane	mg/kg	0.016	0.1	13				0.1		-	-	-	-	-	-	-	-	-
	2,3,4,6-tetrachlorophenol	mg/kg	0.0089								-	-	-	-	-	-	-	-	-
	2,4,5-trichlorophenol	mg/kg	0.015				400000				-	-	-	-	-	-	-	-	-
	2,4,6-trichlorophenol	mg/kg	0.021				2000				-	-	-	-	-	-	-	-	-
	2,4-dichlorophenol	mg/kg	0.0028								-	-	-	-	-	-	-	-	-
	2,4-dimethylphenol	mg/kg	0.022								-	-	-	-	-	-	-	-	-
	2,4-dinitrophenol	mg/kg	0.16								-	-	-	-	-	-	-	-	-
	2,4-Dinitrotoluene	mg/kg	0.011				30130				-	-	-	-	-	-	-	-	-
	2,6-dinitrotoluene	mg/kg	0.014								-	-	-	-	-	-	-	-	-
	2-chloronaphthalene	mg/kg	0.0029								-	-	-	-	-	-	-	-	-
	2-chlorophenol	mg/kg	0.011								-	-	-	-	-	-	-	-	-
	2-methylnaphthalene	mg/kg	0.012								-	-	-	-	-	-	-	-	-
	2-methylphenol	mg/kg	0.0096		100		4200000				-	-	-	-	-	-	-	-	-
	2-nitroaniline	mg/kg	0.062								-	-	-	-	-	-	-	-	-
	2-nitrophenol	mg/kg	0.015								-	-	-	-	-	-	-	-	-
	3,3-Dichlorobenzidine	mg/kg	0.015								-	-	-	-	-	-	-	-	-
	3-nitroaniline	mg/kg	0.057								-	-	-	-	-	-	-	-	-
	4,6-Dinitro-2-methylphenol	mg/kg	0.055								-	-	-	-	-	-	-	-	-
	4-bromophenyl phenyl ether	mg/kg	0.012								-	-	-	-	-	-	-	-	-
	4-chloro-3-methylphenol	mg/kg	0.013								-	-	-	-	-	-	-	-	-
	4-chloroaniline	mg/kg	0.011								-	-	-	-	-	-	-	-	-
	4-chlorophenyl phenyl ether	mg/kg	0.015								-	-	-	-	-	-	-	-	-
	4-methylphenol	mg/kg	0.055				4200				-	-	-	-	-	-	-	-	-
	4-nitroaniline	mg/kg	0.022								-	-	-	-	-	-	-	-	-
	4-nitrophenol	mg/kg	0.05								-	-	-	-	-	-	-	-	-
	Acenaphthene	mg/kg	0.0026	20	100				98		-	-	-	-	-	-	-	-	-
	Acenaphthylene	mg/kg	0.0032	100	100				107		-	-	-	-	-	-	-	-	-
	Acetophenone	mg/kg	0.011								-	-	-	-	-	-	-	-	-
	Anthracene	mg/kg	0.0027		100				1000		-	-	-	-	-	-	-	-	-
	Atrazine	mg/kg	0.013								-	-	-	-	-	-	-	-	-

DRAFT

TABLE 5-13
FIS Fine-Grained Material Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

									Sample Name	SSHS-B2771-SUB-10-12	SSHS-B2771-SUB-6-8	SSHS-B2771-SUB-8-10	SSHS-B2772-SUB-6-8	SSHS-B2772-SUB-8-10	SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-8-10	SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-8-10
									Sample Date	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019	5/13/2019
Group	**Chemical**	**Units**	**EQL**	**Unrestricted SCOs**	**Restricted Residential SCOs**	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)	NYS Hazardous Waste	***Protection of Groundwater***									
SVOCs	Benz(a)anthracene	mg/kg	0.018	1	1				`	-	-	-	-	-	-	-	-	-
	Benzaldehyde	mg/kg	0.021							-	-	-	-	-	-	-	-	-
	Benzo(a) pyrene	mg/kg	0.02	1	1				22	-	-	-	-	-	-	-	-	-
	Benzo(b)fluoranthene	mg/kg	0.023	1	1				1.7	-	-	-	-	-	-	-	-	-
	Benzo(g,h,i)perylene	mg/kg	0.02	100	100				1000	-	-	-	-	-	-	-	-	-
	Benzo(k)fluoranthene	mg/kg	0.026	0.8	3.9				1.7	-	-	-	-	-	-	-	-	-
	Bis(2-chloroethoxy) methane	mg/kg	0.0091							-	-	-	-	-	-	-	-	-
	Bis(2-chloroethyl)ether	mg/kg	0.0037							-	-	-	-	-	-	-	-	-
	Bis(2-chloroisopropyl) ether	mg/kg	0.003							-	-	-	-	-	-	-	-	-
	Bis(2-ethylhexyl) phthalate	mg/kg	0.022							-	-	-	-	-	-	-	-	-
	Butyl benzyl phthalate	mg/kg	0.019							-	-	-	-	-	-	-	-	-
	Caprolactam	mg/kg	0.1							-	-	-	-	-	-	-	-	-
	Carbazole	mg/kg	0.0025							-	-	-	-	-	-	-	-	-
	Chrysene	mg/kg	0.019	1	3.9				1	-	-	-	-	-	-	-	-	-
	Dibenz(a,h)anthracene	mg/kg	0.0031	0.33	0.33				1000	-	-	-	-	-	-	-	-	-
	Dibenzofuran	mg/kg	0.014		59					-	-	-	-	-	-	-	-	-
	Diethylphthalate	mg/kg	0.015							-	-	-	-	-	-	-	-	-
	Dimethyl phthalate	mg/kg	0.015							-	-	-	-	-	-	-	-	-
	Di-n-butyl phthalate	mg/kg	0.017							-	-	-	-	-	-	-	-	-
	Di-n-octyl phthalate	mg/kg	0.015							-	-	-	-	-	-	-	-	-
	Fluoranthene	mg/kg	0.026	100	100				1000	-	-	-	-	-	-	-	-	-
	Fluorene	mg/kg	0.0036	30	100				386	-	-	-	-	-	-	-	-	-
	Hexachlorobenzene	mg/kg	0.0029		1.2		3000			-	-	-	-	-	-	-	-	-
	Hexachlorobutadiene	mg/kg	0.0031			12				-	-	-	-	-	-	-	-	-
	Hexachlorocyclopentadiene	mg/kg	0.015			8.1				-	-	-	-	-	-	-	-	-
	Hexachloroethane	mg/kg	0.0099							-	-	-	-	-	-	-	-	-
	Indeno(1,2,3-c,d)pyrene	mg/kg	0.019	0.5	0.5				8.2	-	-	-	-	-	-	-	-	-
	Isophorone	mg/kg	0.01							-	-	-	-	-	-	-	-	-
	Naphthalene	mg/kg	0.0097	12	100				12	-	-	-	-	-	-	-	-	-
	Nitrobenzene	mg/kg	0.011				2000			-	-	-	-	-	-	-	-	-
	N-nitrosodi-n-propylamine	mg/kg	0.0032							-	-	-	-	-	-	-	-	-
	n-Nitrosodiphenylamine	mg/kg	0.013							-	-	-	-	-	-	-	-	-
	Pentachlorophenol	mg/kg	0.012	0.8	6.7	19	100000		0.8	-	-	-	-	-	-	-	-	-
	Phenanthrene	mg/kg	0.0044	100	100				1000	-	-	-	-	-	-	-	-	-
	Phenol	mg/kg	0.0033	0.33	100				0.33	-	-	-	-	-	-	-	-	-
	Pyrene	mg/kg	0.023	100	100				1000	-	-	-	-	-	-	-	-	-

Notes:

EQL - Estimated Quantitation Limit

SVOCs - Semivolatile organic compounds

PAHs - Polycyclic Aromatic Hydrocarbons

TCLP - Toxicity characteristic leaching procedure

SCO - Soil Cleanup Objectives

J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

U - non-detect at value indicated

B - Compound was found in the blank and sample.

F1 - MS and/or MSD Recovery is outside acceptance limits.

F2 - MS/MSD RPD exceeds control limits

* LCS or LCSD is outside acceptance limits.

J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated QC or calibration data or matrix interference.

p - The %RPD between the primary and confirmation column/detector is >40%. The lower value has been reported.

mg/kg - milligrams per kilogram

a - Sample ID "Test Pit 3" was taken from the Test Pit 3b location.

Chemical concentrations detected above Unrestricted SCOs are presented in Bold.

Chemical concentrations detected above Protection of Groundwater are presented in Italics

Chemical concentrations detected above 20xTCLP (200xTCLP for lead) are presented with underlines

Chemical concentrations detected above Restricted SCOs are presented in dark gray.

Chemical concentrations detected above Class C Sediment Guidance Values are presented in light gray

Total PAHs did not exceed 100 mg/kg in any sample.

DRAFT

TABLE 5-13
FIS Fine-Grained Material Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

									Sample Name	CB-24	SSHS-CB-28o	Test Pit 2	Test Pit 3[a]	MH-1	MH-2	MH-3	CB-4	CB-5	SSHS-CB-11	SSHS-CB-13	SSHS-CB-20	SSHS-CB-25	SSHS-CB-26	SSHS-CB-27	SSHS-CB-31
									Sample Date	9/1/2016	6/25/2019	12/22/2019	12/23/2019	5/14/2019	11/7/2019	12/6/2019		5/28/2015	5/15/2019	6/25/2019	6/24/2019	6/24/2019	6/25/2019	6/25/2019	6/25/2019
Group	**Chemical**	**Units**	**EQL**	**Unrestricted SCOs**	**Restricted Residential SCOs**	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)	NYS Hazardous Waste	***Protection of Groundwater***																	
Metals	Aluminum	mg/kg	11							4700	11,000	16,000B	14,000B	8600	7600	8400J+	4200	3900	4700	10,000	8100	13,000	7700	8500	11,000
	Antimony	mg/kg	0.3							<0.99U	5.4	<0.45U	<0.46U	1.5J	0.79J	2.1	<0.13U	0.38J	<0.36U	0.6J	0.59J	2J	1.7	0.52J	1J
	Arsenic	mg/kg	0.61	13	16	33	100		16	**14**	***19***	**13**	12	6.4	2.7	4.5	8.2	4.8	2.3	5.6	5.8	8	5.5	4.4	5.7
	Barium	mg/kg	11	350	400		2000		820	230	**450**	240	220	120	110	140	29B	31B	21	100	75	110	63	70	100
	Beryllium	mg/kg	0.22	7.2	72				47	0.24	0.51J	0.82	0.77	0.42J	0.39J	0.42J	0.16J	0.095J	0.16J	0.52J	0.41J	0.65J	0.43J	0.41J	0.51J
	Cadmium	mg/kg	0.3	2.5	4.3	5	20		7.5	**3.2**	***130***	**2.9**	0.77	1.9	1.7	***17***	0.093J	0.15J	0.2J	0.12J	0.25J	1.2	0.48J	0.25J	0.16J
	Calcium	mg/kg	280							4000	9500	3300	3000	13,000	4100	11,000	54,000B	150,000B	32,000	9100	19,000	7900	4300	12,000	24,000J
	Chromium (III+VI)	mg/kg	0.28	1	110	110	100		19	***520***	***670***	***41***	***65***	***37***	***53J+***	***130J+***	**7.6**	***24***	**6.8**	**12**	**16**	***21***	***23***	**12**	**13**
	Cobalt	mg/kg	2.6							6.1	12	15	13	7.4J	5.6J	9.5J	3.8	3.8J	4.3J	8.9	6.9J	10J	7.1J	6.8J	9.5
	Copper	mg/kg	1.5	50	270	150			1720	***3100***	**550**	**380**	**270**	**120**	**160**	**250**	27	**56**	17	17	27	32	35	15	17
	Iron	mg/kg	6.1							36,000	63,000	30,000	31,000	21,000	17,000	20,000J+	14,000B	21,000B	12,000	19,000	17,000	23,000	26,000	15,000	19,000
	Lead	mg/kg	0.66	63	400	130	1000		450	***1600***	***600***	***790***	**190**	**220**	**210**	**280**	19	29	15	16	**420**	28	18	11	17
	Magnesium	mg/kg	280							1800	3700	4200	4100	5200	2400	4300	5300	14,000	10,000	3400	9700	4100	2500	3400	6400
	Manganese	mg/kg	0.84	1600	2000				2000	250	460	600	820	420	170J+	190J+	190	210	300	480	360	440	580	270	640J
	Mercury	mg/kg	0.013	0.18	0.81	1	4		0.73	**0.25**	***1.7***	0.11	0.09	**0.37**	**0.47**	**0.5**	<0.0073U	0.13	<0.013U	<0.02U	0.058	0.1	0.054J	0.025J	0.031J
	Nickel	mg/kg	2.7	30	310	49			130	***1100***	***340***	***1400***	***460***	25	23	**43**	18	17	12	27	21	24	17	16	21
	Potassium	mg/kg	280							290	1200	1200	1100	1100	970	960J	410	270J	330J	1600	800J	2000	880	1100	1600
	Selenium	mg/kg	0.34	3.9	180		20		4	0.63	2.9	<0.68U	<0.69U	1.2J	<0.77U	1.2J	0.68	0.88	0.73J	<0.75U	<0.85U	<1.2U	<0.84U	<0.74U	<0.76U
	Sodium	mg/kg	78							<78U	170J	100J	92J	170J	98J	250J	<0.027U	130J	73J	140J	79J	82J	72J	59J	110J
	Silver	mg/kg	0.025	2	180	2.2	100		8.3	**5.3**	**6.8**	0.53J	<0.14U	0.6J	0.95	**6.1**	**600**	<0.025U	<0.11U	<0.15U	<0.17U	<0.25U	<0.17U	<0.15U	<0.15U
	Thallium	mg/kg	0.089							<1.4U	<0.64U	0.6J	0.54J	<0.7U	<0.48U	<0.67U	<0.099U	<0.45U	<0.34U	<0.47U	<0.53U	<0.75U	<0.52U	<0.46U	<0.47U
	Vanadium	mg/kg	2.8							13	26	22	20	22	21	23	10B	15B	9.3	14	14	18	25	12	15
	Zinc	mg/kg	1.2	109	10000	460			2480	***3800***	***2700***	***2400***	**560**	**390**	**390**	**690**	58B	160B	98	58	**210**	**190**	**140**	72	59
Polychlorinated Biphenyls	Arochlor 1016	mg/kg	0.00053							-	<0.11U	<0.16U	<0.15U	<0.011U	<0.0091U	<0.014U	<0.0028U	<0.00053U	<0.0057U	<0.008U	<0.0085U	<0.013U	<0.009U	<0.0074U	<0.0076U
	Arochlor 1221	mg/kg	0.00065							<34U	<0.12U	<0.18U	<0.16U	<0.012U	<0.0099U	<0.015U	<0.0034U	<0.00065U	<0.0062U	<0.0087U	<0.0093U	<0.014U	<0.0098U	<0.008U	<0.0083U
	Arochlor 1232	mg/kg	0.0009							<12U	<0.079U	<0.12U	<0.11U	<0.0085U	<0.0068U	<0.01U	<0.0048U	<0.0009U	<0.0043U	<0.006U	<0.0064U	<0.0099U	<0.0068U	<0.0055U	<0.0057U
	Arochlor 1242	mg/kg	0.00066							<17U	<0.048U	<0.074U	<0.067U	<0.0051U	<0.0041U	<0.0062U	<0.0035U	<0.00066U	<0.0026U	<0.0036U	<0.0038U	<0.0059U	<0.0041U	<0.0033U	<0.0034U
	Arochlor 1248	mg/kg	0.00065							2400B	19J	29	63	0.076J	0.14J	<0.01U	1.2J	<0.00065U	0.19J	0.14J	0.96J	<0.0097U	0.042J	0.042J	0.75J
	Arochlor 1254	mg/kg	0.0026							<17U	7.9J	13	27	0.069J	0.08J	<0.013U	0.49J	0.024J	0.071J	0.092J	0.44J	<0.012U	0.025J	0.021J	0.36J
	Arochlor 1260	mg/kg	0.0026							-	1.7J	2.9	5.4	0.057J	0.075J	<0.012U	0.095J	0.0045J	0.012J	0.026J	0.12J	<0.012U	<0.0079U	<0.0065U	0.077J
	Arochlor 1268	mg/kg	0.00053							<8.8U	<0.044U	<0.068U	<0.062U	<0.0047U	<0.0038U	<0.0057U	<0.0028U	<0.00053U	<0.0024U	<0.0033U	<0.0035U	<0.0054U	<0.0037U	<0.0031U	<0.0031U
	Arochlor 1262	mg/kg	0.00096							<15U	<0.11U	<0.18U	<0.16U	<0.012U	<0.0099U	<0.015U	<0.0051U	<0.00096U	<0.0062U	<0.0086U	<0.0092U	<0.014U	<0.0098U	<0.008U	<0.0082U
	Total PCBs	mg/kg		0.1	1	1		50	3.2	***2400***	***28.6***	***44.9***	***95.4***	**0.202**	**0.295**	ND	**1.785**	0.0285	**0.273**	**0.258**	**1.52**	ND	0.067	0.063	**1.187**
	Total PAHs	mg/kg				3.5	100			2.565	19.92	5.246	1.087	40.18	32.71	ND	4.01	**156.9**	5.565	ND	1.232	0.644	0.23	0.276	0.744
	1,1-Biphenyl	mg/kg	0.012							<0.05U	<0.054U	<0.1U	<0.018U	<0.43U	<0.24U	<0.11U	<0.078U	<0.075U	<0.06U	<0.02U	<0.066U	<0.068U	<0.024U	<0.019U	<0.02U
	1,2,4,5-tetrachlorobenzene	mg/kg	0.01			14				<0.043U	<0.056U	<0.11U	<0.019U	<0.44U	<0.24U	<0.11U	<0.067U	<0.064U	<0.062U	<0.021U	<0.068U	<0.069U	<0.024U	<0.02U	<0.021U
	1,4-Dioxane	mg/kg	0.016	0.1	13				0.1	*<0.065U*	*<0.4U*	*<0.76U*	*<0.14U*	*<3.2U*	*<1.8U*	*<0.81U*	<0.1U	<0.096U	*<0.45U*	*<0.15U*	*<0.49U*	*<0.5U*	*<0.18U*	*<0.14U*	*<0.15U*
	2,3,4,6-tetrachlorophenol	mg/kg	0.0089							<0.036U	<0.54U	<1U	<0.18U	<4.3U	<2.3U	<1.1U	<0.057U	<0.054U	<0.6UJ	<0.2U	<0.65U	<0.67U	<0.24U	<0.19U	<0.2U
	2,4,5-trichlorophenol	mg/kg	0.015				400000			<0.06U	<0.092U	<0.17U	<0.031U	<0.73U	<0.4U	<0.19U	<0.094U	<0.089U	<0.1UJ	<0.035U	<0.11U	<0.11U	<0.04U	<0.033U	<0.034U
	2,4,6-trichlorophenol	mg/kg	0.021				2000			<0.085U	<0.071U	<0.13U	<0.024U	<0.56U	<0.31U	<0.14U	<0.13U	<0.13U	<0.079UJ	<0.027U	<0.086U	<0.088U	<0.031U	<0.025U	<0.026U
	2,4-dichlorophenol	mg/kg	0.0028							<0.011U	<0.099U	<0.19U	<0.034U	<0.79U	<0.43U	<0.2U	<0.018U	<0.017U	<0.11UJ	<0.037U	<0.12U	<0.12U	<0.044U	<0.036U	<0.037U
	2,4-dimethylphenol	mg/kg	0.022							<0.088U	<0.08U	<0.15U	<0.027U	<0.63U	<0.35U	<0.16U	<0.14U	<0.13U	<0.089UJ	<0.03U	<0.097U	<0.1U	<0.035U	<0.029U	<0.029U
	2,4-dinitrophenol	mg/kg	0.16							<0.67U	<3.5U	<6.5U	<1.2U	<27UJ	<15U	<7U	<1U	<1U	<3.9UJ	<1.3U	<4.2U	<4.3U	<1.5U	<1.2U	<1.3U
	2,4-Dinitrotoluene	mg/kg	0.011				30130			<0.046U	<0.064U	<0.12U	<0.022U	<0.51U	<0.28U	<0.13U	<0.071U	<0.068U	<0.072U	<0.024U	<0.078U	<0.08U	<0.028U	<0.023U	<0.024U
	2,6-dinitrotoluene	mg/kg	0.014							<0.058U	<0.079U	<0.15U	<0.027U	<0.63U	<0.35U	<0.16U	<0.091U	<0.086U	<0.089U	<0.03U	<0.097U	<0.099U	<0.035U	<0.028U	<0.029U
	2-chloronaphthalene	mg/kg	0.0029							<0.012U	<0.059U	<0.11U	<0.02U	<0.47U	<0.26U	<0.12U	<0.018U	<0.017U	<0.066U	<0.022U	<0.072U	<0.074U	<0.026U	<0.021U	<0.022U
	2-chlorophenol	mg/kg	0.011							<0.046U	<0.06U	<0.11U	<0.02U	<0.47U	<0.26U	<0.12U	<0.072U	<0.069U	<0.067UJ	<0.022U	<0.073U	<0.075U	<0.026U	<0.021U	<0.022U
	2-methylnaphthalene	mg/kg	0.012							0.023J	0.41	<0.12U	0.031J	<0.49U	<0.27U	<0.13U	<0.016U	0.2	<0.069U	<0.023U	<0.075U	<0.077U	<0.027U	<0.022U	0.025J
	2-methylphenol	mg/kg	0.0096		100		4200000			<0.039U	<0.37U	<0.7U	<0.12U	<2.9U	<1.6U	<0.75U	<0.061U	<0.059U	<0.41UJ	<0.14U	<0.45U	<0.46U	<0.16U	<0.13U	<0.14U
	2-nitroaniline	mg/kg	0.062							<0.25U	<0.59U	<1.1U	<0.2U	<4.7U	<2.6U	<1.2U	<0.39U	<0.38U	<0.66U	<0.22U	<0.71U	<0.73U	<0.26U	<0.21U	<0.22U
	2-nitrophenol	mg/kg	0.015							<0.062U	<0.2U	<0.39U	<0.069U	<1.6U	<0.89U	<0.42U	<0.097U	<0.092U	<0.23UJ	<0.077U	<0.25U	<0.26U	<0.09U	<0.073U	<0.076U
	3,3-Dichlorobenzidine	mg/kg	0.015							<0.06U	<1.2U	<2.3U	<0.41U	<9.5UJ	<5.2U	-	<0.093U	<0.089U	<1.3U	<0.45U	<1.5U	<1.5U	<0.53U	<0.43U	<0.44U
	3-nitroaniline	mg/kg	0.057							<0.23U	<0.33U	<0.62U	<0.11U	<2.6U	<1.4U	<0.66U	<0.36U	<0.35U	<0.37U	<0.12U	<0.4U	<0.41U	<0.14U	<0.12U	<0.12U
	4,6-Dinitro-2-methylphenol	mg/kg	0.055							<0.23U	<2.2U	<4.2U	<0.75U	<18U	<9.7U	<4.5U	<0.35U	<0.34U	<2.5UJ	<0.83U	<2.7U	<2.8U	<0.98U	<0.79U	<0.82U
	4-bromophenyl phenyl ether	mg/kg	0.012							<0.049U	<0.09U	<0.17U	<0.03U	<0.71U	<0.39U	<0.18U	<0.077U	<0.073U	<0.1U	<0.034U	<0.11U	<0.11U	<0.04U	<0.032U	<0.033U
	4-chloro-3-methylphenol	mg/kg	0.013							<0.052U	<0.061U	<0.11U	<0.02U	<0.48U	<0.26U	-	<0.081U	<0.077U	<0.068UJ	<0.023U	<0.074U	<0.076U	<0.027U	<0.022U	<0.022U
	4-chloroaniline	mg/kg	0.011							<0.045U	2.5	<0.081U	<0.014U	<0.34U	<0.19U	-	<0.07U	<0.067U	<0.048U	<0.016U	<0.052U	<0.054U	<0.019U	<0.015U	<0.016U
	4-chlorophenyl phenyl ether	mg/kg	0.015							<0.063U	<0.078U	<0.15U	<0.026U	<0.62U	<0.34U	-	<0.098U	<0.093U	<0.087U	<0.029U	<0.095U	<0.097U	<0.034U	<0.028U	<0.029U
	4-methylphenol	mg/kg	0.055				4200			<0.055U	<0.38U	<0.71U	<0.13U	<3U	<1.6U	-	0.2J	<0.082U	<0.42UJ	<0.14U	<0.46U	<0.47U	<0.17U	<0.14U	<0.14U
	4-nitroaniline	mg/kg	0.022							<0.23U	<0.062U	<0.12U	<0.021U	<0.5U	<0.27U	-	<0.36U	<0.34U	<0.07U	<0.023U	<0.076U	<0.078U	<0.028U	<0.022U	<0.023U
	4-nitrophenol	mg/kg	0.05							<0.21U	<0.9U	<1.7U	<0.31U	<7.2U	<3.9UJ	-	<0.32U	<0.31U	<1UJ	<0.34U	<1.1U	<1.1U	<0.4U	<0.32U	<0.33U
	Acenaphthene	mg/kg	0.0026	20	100				98	<0.011U	<0.074U	<0.14U	<0.025U	<0.59U	<0.32U	-	<0.017U	0.91	<0.083U	<0.028U	<0.09U	<0.093U	<0.033U	<0.027U	<0.027U
	Acenaphthylene	mg/kg	0.0032	100	100				107	0.075J	0.22J	0.21J	0.038J	<0.45U	<0.25U	-	<0.02U	0.9	<0.063U	<0.021U	<0.068U	<0.07U	<0.025U	<0.02U	<0.021U
	Acetophenone	mg/kg	0.011							<0.046U	<0.07U	<0.13U	<0.024U	<0.55U	<0.3U	-	<0.072U	<0.069U	<0.078U	<0.026U	<0.085U	<0.087U	<0.031U	<0.025U	<0.026U
	Anthracene	mg/kg	0.0027		100				1000	0.057J	0.34	0.13J	0.027J	<0.53U	0.44J	-	<0.017U	5.4	0.083J	<0.025U	<0.081U	<0.083U	<0.029U	<0.024U	<0.025U
	Atrazine	mg/kg	0.013							<0.055U	<0.56U	<1.1U	<0.19U	<4.5U	<2.5U	-	<0.086U	<0.082U	<0.63U	<0.21U	<0.68U	<0.7U	<0.25U	<0.2U	<0.21U

DRAFT

TABLE 5-13
FIS Fine-Grained Material Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

Group	Chemical	Units	EQL	Unrestricted SCOs	Restricted Residential SCOs	Class C Sediment Guidance Value	20x TCLP Screening (Lead = 1000 ppm)	NYS Hazardous Waste	Protection of Groundwater	Sample Name	CB-24	SSHS-CB-28o	Test Pit 2	Test Pit 3[a]	MH-1	MH-2	MH-3	CB-4	CB-5	SSHS-CB-11	SSHS-CB-13	SSHS-CB-20	SSHS-CB-25	SSHS-CB-26	SSHS-CB-27	SSHS-CB-31
										Sample Date	9/1/2016	6/25/2019	12/22/2019	12/23/2019	5/14/2019	11/7/2019	12/6/2019		5/28/2015	5/15/2019	6/25/2019	6/24/2019	6/24/2019	6/25/2019	6/25/2019	6/25/2019
SVOCs	Benz(a)anthracene	mg/kg	0.018	1	1				`		0.24	**1.3**	0.44J	0.077J	**2.7**	**2.3**	-	0.22	**12**	0.4	<0.018U	0.11J	0.08J	<0.021U	0.036J	0.068J
	Benzaldehyde	mg/kg	0.021								<0.085U	<0.16U	<0.3U,*	<0.054U,*	-	<0.7U	-	<0.13UJ	<0.13UJ	-	<0.06U	<0.19U	<0.2U	<0.07U	<0.057U	<0.059U
	Benzo(a) pyrene	mg/kg	0.02	1	1				22		0.23	**1.7**	0.41J	0.073J	**3.3**	**2.8**	-	0.28	**11**	0.38	<0.021U	0.12J	<0.07U	<0.025U	<0.02U	0.059J
	Benzo(b)fluoranthene	mg/kg	0.023	1	1				1.7		0.38	***2.4***	0.55	0.11	***5.5***	***4.3***	-	0.37	***13***	0.54	<0.024U	0.11J	<0.079U	<0.028U	<0.023U	0.068J
	Benzo(g,h,i)perylene	mg/kg	0.02	100	100				1000		0.26	2.5	0.5	0.083J	3.4	2.3	-	0.32	11	0.31	<0.021U	0.13J	<0.069U	<0.024U	<0.02U	0.058J
	Benzo(k)fluoranthene	mg/kg	0.026	0.8	3.9				1.7		0.12	0.79	0.23J	0.051J	***1.7J***	**1.4**	-	0.14J	***5.5***	0.25J	<0.029U	<0.094U	<0.096U	<0.034U	<0.028U	0.036J
	Bis(2-chloroethoxy) methane	mg/kg	0.0091								<0.037U	<0.061U	<0.12U	<0.021U	<0.49U	<0.27U	-	<0.058U	<0.055U	<0.069U	<0.023U	<0.075U	<0.077U	<0.027U	<0.022U	<0.023U
	Bis(2-chloroethyl)ether	mg/kg	0.0037								<0.015U	<0.047U	<0.088U	<0.016U	<0.37U	<0.2U	-	<0.024U	<0.022U	<0.052U	<0.018U	<0.057U	<0.058U	<0.021U	<0.017U	<0.017U
	Bis(2-chloroisopropyl) ether	mg/kg	0.003								<0.012U	<0.095U	<0.18U	<0.032U	<0.76U	<0.42U	-	<0.019U	<0.018U	<0.11U	<0.036U	<0.12U	<0.12U	<0.042U	<0.034U	<0.035U
	Bis(2-ethylhexyl) phthalate	mg/kg	0.022								0.8J	4.9J	<2.6U	<0.46U	<11U	<6U	-	<0.14U	2.8	<1.5U	<0.51U	<1.7U	<1.7U	<0.6U	<0.49U	<0.51U
	Butyl benzyl phthalate	mg/kg	0.019								<0.077U	2	<1.7U	<0.3U	<7U	<3.9U	-	<0.12U	<0.11U	<0.99U	<0.33U	<1.1U	<1.1U	<0.39U	<0.32U	<0.33U
	Caprolactam	mg/kg	0.1								<0.43U	<0.84U	<1.6U	<0.28U	<6.6U	<3.7U	-	<0.66U	<0.63U	<0.94U	<0.31U	<1U	<1U	<0.37U	<0.3U	<0.31U
	Carbazole	mg/kg	0.0025								<0.01U	0.22J	<0.11U	<0.02U	0.55J	0.5J	-	<0.016U	2.2	<0.067U	<0.023U	<0.073U	<0.075U	<0.027U	<0.022U	<0.022U
	Chrysene	mg/kg	0.019	1	3.9				1		0.36	***1.9***	0.48J	0.11	***3.7***	***3.4***	-	0.39	***13***	0.54	<0.019U	0.11J	<0.063U	<0.022U	0.036J	0.073J
	Dibenz(a,h)anthracene	mg/kg	0.0031	0.33	0.33				1000		0.061J	**0.45**	**0.51**	0.086J	**0.69J**	**0.62J**	-	<0.02U	**2.3**	0.084J	<0.022U	<0.07U	<0.072U	<0.025U	<0.021U	<0.021U
	Dibenzofuran	mg/kg	0.014		59						<0.056U	0.11J	<0.11U	<0.019U	<0.45U	<0.25U	-	<0.087U	0.58J	<0.063U	<0.021U	<0.068U	<0.07U	<0.025U	<0.02U	<0.021U
	Diethylphthalate	mg/kg	0.015								<0.062U	<0.45U	<0.85U	<0.15U	<3.6U	<2U	-	<0.096U	<0.091U	<0.51U	<0.17U	<0.55U	<0.56U	<0.2U	<0.16U	<0.17U
	Dimethyl phthalate	mg/kg	0.015								<0.062U	<0.047U	<0.088U	<0.016U	<0.37U	<0.2U	-	<0.096U	<0.091U	<0.052U	<0.018U	<0.057U	<0.058U	<0.021U	<0.017U	<0.017U
	Di-n-butyl phthalate	mg/kg	0.017								<0.071U	<0.56U	<1.1U	<0.19U	<4.5U	<2.5U	-	<0.11U	<0.1U	<0.63U	<0.21U	<0.68U	<0.7U	<0.25U	<0.2U	<0.21U
	Di-n-octyl phthalate	mg/kg	0.015								<0.06U	<0.75U	<1.4U	<0.25U	<5.9U	<3.3U	-	<0.093U	<0.088U	<0.84U	<0.28U	<0.91U	<0.94U	<0.33U	<0.27U	<0.28U
	Fluoranthene	mg/kg	0.026	100	100				1000		0.15	3	0.51	0.12	7.5	5.7	-	0.91	33	1.3	<0.026U	0.16J	<0.085U	0.03J	0.043J	0.092J
	Fluorene	mg/kg	0.0036	30	100				386		<0.015U	<0.051U	<0.096U	<0.017U	<0.4U	<0.22U	-	<0.023U	1.6	<0.057U	<0.019U	<0.061U	<0.063U	<0.022U	<0.018U	<0.019U
	Hexachlorobenzene	mg/kg	0.0029		1.2		3000				<0.012U	<0.092U	<0.17U	<0.031U	<0.73U	<0.4U	-	<0.019UJ	<0.018UJ	<0.1U	<0.035U	<0.11U	<0.12U	<0.041U	<0.033U	<0.034U
	Hexachlorobutadiene	mg/kg	0.0031			12					<0.013U	<0.075U	<0.14U	<0.025U	<0.6U	<0.33U	-	<0.02UJ	<0.019UJ	<0.084U	<0.028U	<0.091U	<0.094U	<0.033U	<0.027U	<0.028U
	Hexachlorocyclopentadiene	mg/kg	0.015			8.1					<0.061U	<0.13U	<0.25U	<0.044U	<1UJ	<0.57U	-	<0.095U	<0.09U	<0.15U	<0.049U	<0.16U	<0.16U	<0.058U	<0.047U	<0.049U
	Hexachloroethane	mg/kg	0.0099								<0.041U	<0.066U	<0.13U	<0.022U	<0.53U	<0.29U	-	<0.063U	<0.06U	<0.074U	<0.025U	<0.081U	<0.083U	<0.029U	<0.024U	<0.025U
	Indeno(1,2,3-c,d)pyrene	mg/kg	0.019	0.5	0.5				8.2		0.2	**1.8**	0.4J	0.072J	**2.9**	**2**	-	0.26	***9***	0.29	<0.02U	0.082J	<0.065U	<0.023U	<0.019U	0.045J
	Isophorone	mg/kg	0.01								<0.043U	<0.066U	<0.12U	<0.022U	<0.52U	<0.29U	-	<0.066U	<0.063U	<0.073U	<0.025U	<0.08U	<0.082U	<0.029U	<0.023U	<0.024U
	Naphthalene	mg/kg	0.0097	12	100				12		<0.0097U	0.29	<0.095U	0.028J	<0.4U	<0.22U	-	<0.015U	0.17	<0.056U	<0.019U	<0.061U	<0.063U	<0.022U	<0.018U	0.021J
	Nitrobenzene	mg/kg	0.011				2000				<0.047U	<0.47U	<0.89U	<0.16U	<3.7U	<2.1U	-	<0.073U	<0.07U	<0.53U	<0.18U	<0.57U	<0.59U	<0.21U	<0.17U	<0.17U
	N-nitrosodi-n-propylamine	mg/kg	0.0032								<0.013U	<0.087U	<0.16U	<0.029U	<0.69U	<0.38U	-	<0.021U	<0.02U	<0.098U	<0.033U	<0.11U	<0.11U	<0.038U	<0.031U	<0.032U
	n-Nitrosodiphenylamine	mg/kg	0.013								<0.052U	<0.43U	<0.81U	<0.14U	<3.4U	<1.9U	-	<0.081U	<0.078U	<0.48U	<0.16U	<0.52U	<0.54U	<0.19U	<0.15U	<0.16U
	Pentachlorophenol	mg/kg	0.012	0.8	6.7	19	100000		0.8		<0.051U	*<2.1U*	*<3.9U*	<0.7U	*<16UJ*	*<9U*	-	<0.079U	<0.075U	*<2.3UJ*	<0.78U	*<2.5U*	*<2.6U*	*<0.91U*	<0.74U	<0.76U
	Phenanthrene	mg/kg	0.0044	100	100				1000		0.11	1	0.25J	0.083J	2.8	2.7	-	0.51	19	0.4	<0.026U	<0.084U	<0.086U	<0.03U	<0.025U	0.071J
	Phenol	mg/kg	0.0033	0.33	100				0.33		<0.013U	*<0.39U*	*<0.74U*	<0.13U	*<3.1U*	*<1.7U*	-	<0.021U	<0.02U	*<0.44UJ*	<0.15U	*<0.47U*	*<0.49U*	<0.17U	<0.14U	<0.14U
	Pyrene	mg/kg	0.023	100	100				1000		0.31	2.2	0.53	0.12	5.1	4.4	-	0.61	20	0.9	<0.023U	0.15J	0.082J	0.035J	0.043J	0.11

Notes:

EQL - Estimated Quantitation Limit

SVOCs - Semivolatile organic compounds

PAHs - Polycyclic Aromatic Hydrocarbons

TCLP - Toxicity characteristic leaching procedure

SCO - Soil Cleanup Objectives

J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

U - non-detect at value indicated

B - Compound was found in the blank and sample.

F1 - MS and/or MSD Recovery is outside acceptance limits.

F2 - MS/MSD RPD exceeds control limits

* LCS or LCSD is outside acceptance limits.

J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated QC or calibration data or matrix interference.

p - The %RPD between the primary and confirmation column/detector is >40%. The lower value has been reported.

mg/kg - milligrams per kilogram

a - Sample ID "Test Pit 3" was taken from the Test Pit 3b location.

Chemical concentrations detected above Unrestricted SCOs are presented in Bold.

Chemical concentrations detected above Protection of Groundwater are presented in Italics

Chemical concentrations detected above 20xTCLP (200xTCLP for lead) are presented with underlines

Chemical concentrations detected above Restricted SCOs are presented in dark gray.

Chemical concentrations detected above Class C Sediment Guidance Values are presented in light gray

Total PAHs did not exceed 100 mg/kg in any sample.

DRAFT

TABLE 5-13
FIS Fine-Grained Material Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

									Sample Name	SSHS-CB-32	SSHS-CB-33	SSHS-CB-34	SSHS-CB-35	SSHS-CB-36	SSHS-CB-37	SSHS-CB-38
									Sample Date	6/24/2019	6/24/2019	5/15/2019	6/24/2019	6/24/2019	6/24/2019	5/15/2019
Group	**Chemical**	**Units**	**EQL**	**Unrestricted SCOs**	**Restricted Residential SCOs**	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)	NYS Hazardous Waste	***Protection of Groundwater***							
Metals	Aluminum	mg/kg	11							9300	13,000	3900	6100	9900	7200	4000
	Antimony	mg/kg	0.3							<0.6UJ	<0.54U	<0.68U	3.1J	0.48J	0.38J	<0.35U
	Arsenic	mg/kg	0.61	13	16	33	100		16	0.89J	1.9	<0.78U	4.3	5.3	5.4	2
	Barium	mg/kg	11	350	400		2000		820	33J	53	16J	52J	93	36	39
	Beryllium	mg/kg	0.22	7.2	72				47	0.14J	0.29J	0.066J	0.34J	0.5J	0.25J	0.23J
	Cadmium	mg/kg	0.3	2.5	4.3	5	20		7.5	0.19J	0.27J	0.15J	0.42J	0.14J	0.41J	0.13J
	Calcium	mg/kg	280							200,000	60,000	14,000	87,000	14,000	27,000J	48,000
	Chromium (III+VI)	mg/kg	0.28	1	110	110	100		19	**6.9**	**14**	**3**	**10**	**12**	**9.6**	**4.6**
	Cobalt	mg/kg	2.6							<2.6U	4J	0.81J	4.3J	8.5	5.7	2.2J
	Copper	mg/kg	1.5	50	270	150			1720	11	14	5.7	22	15	17	10
	Iron	mg/kg	6.1							4300	10,000	2400	16,000	19,000	15,000	12,000
	Lead	mg/kg	0.66	63	400	130	1000		450	<4.5U	11	4.7	17	13	17	4.9
	Magnesium	mg/kg	280							17,000J-	6200	1700	17,000	3000	3700	9300
	Manganese	mg/kg	0.84	1600	2000				2000	73	190	61	520	390	310	190
	Mercury	mg/kg	0.013	0.18	0.81	1	4		0.73	<0.026U	0.042J	0.041J	0.11J	0.098	<0.016UJ	<0.015U
	Nickel	mg/kg	2.7	30	310	49			130	5.6J	13	4J	24	20	18	7.7
	Potassium	mg/kg	280							1300	930	170J	1100J	1400	570	260J
	Selenium	mg/kg	0.34	3.9	180		20		4	2.2	0.95J	<1U	2.1J	<0.67U	0.69J	0.7J
	Sodium	mg/kg	78							170J	150J	89J	190J	61J	64J	160J
	Silver	mg/kg	0.025	2	180	2.2	100		8.3	<0.19U	<0.17U	<0.21U	<0.37U	<0.14U	<0.12U	<0.11U
	Thallium	mg/kg	0.089							<2.8U	<0.51U	<0.64U	<1.1U	<0.42U	<0.36U	<0.33U
	Vanadium	mg/kg	2.8							12	15	6.1J	14J	13	16	6.2
	Zinc	mg/kg	1.2	109	10000	460			2480	**330**	**220**	71	**210**	61	**510**	59
Polychlorinated Biphenyls	Arochlor 1016	mg/kg	0.00053							<0.0092U	<0.0081U	<0.011U	<0.02U	<0.0067U	<0.0059U	<0.0059U
	Arochlor 1221	mg/kg	0.00065							<0.01U	<0.0088U	<0.012U	<0.022U	<0.0073U	<0.0064U	<0.0064U
	Arochlor 1232	mg/kg	0.0009							<0.0069U	<0.006U	<0.0083U	<0.015U	<0.005U	<0.0044U	<0.0044U
	Arochlor 1242	mg/kg	0.00066							<0.0041U	<0.0036U	<0.005U	<0.0091U	<0.003U	<0.0026U	<0.0026U
	Arochlor 1248	mg/kg	0.00065							0.064J	0.039J	0.082J	0.48J	0.19J	0.061J	0.022
	Arochlor 1254	mg/kg	0.0026							0.028J	0.03J	0.047J	0.2J	0.085J	0.051J	<0.0054U
	Arochlor 1260	mg/kg	0.0026							<0.008U	<0.0071U	0.054J	0.052J	0.031J	0.02J	<0.0051U
	Arochlor 1268	mg/kg	0.00053							<0.0038U	<0.0033U	<0.0046U	<0.0083U	<0.0028U	<0.0024U	<0.0024U
	Arochlor 1262	mg/kg	0.00096							<0.0099U	<0.0087U	<0.012U	<0.022U	<0.0073U	<0.0064U	<0.0063U
	Total PCBs	mg/kg		0.1	1	1		50	3.2	0.092	0.069	**0.183**	**0.732**	**0.306**	**0.132**	0.022
	Total PAHs	mg/kg				3.5	100			1	0.67	2.91	3.405	13.06	7.395	**71.77**
	1,1-Biphenyl	mg/kg	0.012							<0.12U	<0.21U	<0.11U	<0.21U	0.14J	0.86J	<0.073U
	1,2,4,5-tetrachlorobenzene	mg/kg	0.01			14				<0.12U	<0.21U	<0.12U	<0.21U	<0.14U	<0.78U	<0.075U
	1,4-Dioxane	mg/kg	0.016	0.1	13				0.1	*<0.88U*	*<1.5U*	*<0.83U*	*<1.5U*	*<1U*	*<5.6U*	*<0.55U*
	2,3,4,6-tetrachlorophenol	mg/kg	0.0089							<1.2U	<2.1U	<1.1UJ	<2U	<1.4U	<7.5U	<0.73U
	2,4,5-trichlorophenol	mg/kg	0.015				400000			<0.2U	<0.35U	<0.19UJ	<0.35U	<0.24U	<1.3U	<0.12U
	2,4,6-trichlorophenol	mg/kg	0.021				2000			<0.16U	<0.27U	<0.15UJ	<0.27U	<0.18U	<0.99U	<0.096U
	2,4-dichlorophenol	mg/kg	0.0028							<0.22U	<0.38U	<0.21UJ	<0.38U	<0.26U	<1.4U	<0.13U
	2,4-dimethylphenol	mg/kg	0.022							<0.18U	<0.31U	<0.17UJ	<0.31U	<0.21U	<1.1U	<0.11U
	2,4-dinitrophenol	mg/kg	0.16							<7.6U	<13U	<7.2UJ	<13U	<8.9U	<49U	<4.7U
	2,4-Dinitrotoluene	mg/kg	0.011				30130			<0.14U	<0.25U	<0.13U	<0.24U	<0.17U	<0.9U	<0.087U
	2,6-dinitrotoluene	mg/kg	0.014							<0.17U	<0.31U	<0.16U	<0.3U	<0.2U	<1.1U	<0.11U
	2-chloronaphthalene	mg/kg	0.0029							<0.13U	<0.23U	<0.12U	<0.23U	<0.15U	<0.83U	<0.08U
	2-chlorophenol	mg/kg	0.011							<0.13U	<0.23U	<0.12UJ	<0.23U	<0.15U	<0.84U	<0.081U
	2-methylnaphthalene	mg/kg	0.012							<0.14U	<0.24U	<0.13U	<0.24U	<0.16U	<0.87U	<0.084U
	2-methylphenol	mg/kg	0.0096		100		4200000			<0.81U	<1.4U	<0.76UJ	<1.4U	<0.95U	<5.2U	<0.5U
	2-nitroaniline	mg/kg	0.062							<1.3U	<2.3U	<1.2U	<2.2U	<1.5U	<8.2U	<0.8U
	2-nitrophenol	mg/kg	0.015							<0.45U	<0.79U	<0.42UJ	<0.78U	<0.53U	<2.9U	<0.28U
	3,3-Dichlorobenzidine	mg/kg	0.015							<2.6U	<4.6U	<2.5U	<4.6U	<3.1U	<17U	<1.6U
	3-nitroaniline	mg/kg	0.057							<0.72U	<1.3U	<0.68U	<1.3U	<0.84U	<4.6U	<0.44U
	4,6-Dinitro-2-methylphenol	mg/kg	0.055							<4.9U	<8.6U	<4.6UJ	<8.5U	<5.7U	<31U	<3U
	4-bromophenyl phenyl ether	mg/kg	0.012							<0.2U	<0.35U	<0.19U	<0.34U	<0.23U	<1.3U	<0.12U
	4-chloro-3-methylphenol	mg/kg	0.013							<0.13U	<0.23U	<0.13UJ	<0.23U	<0.16U	<0.85U	<0.082U
	4-chloroaniline	mg/kg	0.011							1J	0.37J	<0.089U	<0.16U	<0.11U	<0.6U	<0.058U
	4-chlorophenyl phenyl ether	mg/kg	0.015							<0.17U	<0.3U	<0.16U	<0.3U	<0.2U	<1.1U	<0.11U
	4-methylphenol	mg/kg	0.055				4200			<0.83U	<1.5U	<0.78UJ	<1.4U	<0.97U	<5.3U	<0.51U
	4-nitroaniline	mg/kg	0.022							<0.14U	<0.24U	0.38J	<0.24U	<0.16U	<0.88U	<0.085U
	4-nitrophenol	mg/kg	0.05							<2U	<3.5U	<1.9UJ	<3.4U	<2.3U	<13U	<1.2U
	Acenaphthene	mg/kg	0.0026	20	100				98	<0.16U	<0.29U	<0.15U	<0.28U	<0.19U	<1U	0.13J
	Acenaphthylene	mg/kg	0.0032	100	100				107	<0.12U	<0.22U	<0.12U	<0.22U	0.31J	<0.79U	0.082J
	Acetophenone	mg/kg	0.011							<0.15U	<0.27U	<0.14U	<0.27U	<0.18U	<0.98U	<0.095U
	Anthracene	mg/kg	0.0027		100				1000	<0.15U	<0.26U	<0.14U	<0.26U	0.51J	<0.94U	2.4
	Atrazine	mg/kg	0.013							<1.2U	<2.2U	<1.2U	<2.2U	<1.5U	<7.9U	<0.77U

DRAFT

TABLE 5-13
FIS Fine-Grained Material Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

									Sample Name	SSHS-CB-32	SSHS-CB-33	SSHS-CB-34	SSHS-CB-35	SSHS-CB-36	SSHS-CB-37	SSHS-CB-38
									Sample Date	6/24/2019	6/24/2019	5/15/2019	6/24/2019	6/24/2019	6/24/2019	5/15/2019
Group	**Chemical**	**Units**	**EQL**	**Unrestricted SCOs**	**Restricted Residential SCOs**	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)	NYS Hazardous Waste	***Protection of Groundwater***							
SVOCs	Benz(a)anthracene	mg/kg	0.018	1	1				`	<0.11U	<0.19U	0.21J	0.25J	**1**	<0.68U	**5.7**
	Benzaldehyde	mg/kg	0.021							<0.35U	<0.62U	-	<0.61U	<0.41U	<2.2U	-
	Benzo(a) pyrene	mg/kg	0.02	1	1				22	<0.12U	<0.22U	0.26J	0.26J	0.77	<0.79U	**5**
	Benzo(b)fluoranthene	mg/kg	0.023	1	1				1.7	<0.14U	<0.24U	0.24J	0.31J	0.95	<0.89U	***6***
	Benzo(g,h,i)perylene	mg/kg	0.02	100	100				1000	<0.12U	<0.21U	0.23J	0.34J	0.61J	0.93J	3.4
	Benzo(k)fluoranthene	mg/kg	0.026	0.8	3.9				1.7	<0.17U	<0.3U	<0.16U	<0.29U	0.44J	<1.1U	***2.3***
	Bis(2-chloroethoxy) methane	mg/kg	0.0091							<0.13U	<0.24U	<0.13U	<0.23U	<0.16U	<0.86U	<0.083U
	Bis(2-chloroethyl)ether	mg/kg	0.0037							<0.1U	<0.18U	<0.097U	<0.18U	<0.12U	<0.66U	<0.063U
	Bis(2-chloroisopropyl) ether	mg/kg	0.003							<0.21U	<0.37U	<0.2U	<0.36U	<0.25U	<1.3U	<0.13U
	Bis(2-ethylhexyl) phthalate	mg/kg	0.022							<3U	<5.3U	<2.8U	<5.2U	<3.5U	<19U	<1.9U
	Butyl benzyl phthalate	mg/kg	0.019							<1.9U	<3.4U	<1.8U	<3.4U	<2.3U	<12U	<1.2U
	Caprolactam	mg/kg	0.1							<1.8U	<3.2U	<1.7U	<3.2U	<2.2U	<12U	<1.1U
	Carbazole	mg/kg	0.0025							<0.13U	<0.23U	0.14J	<0.23U	0.19J	<0.85U	0.2J
	Chrysene	mg/kg	0.019	1	3.9				1	<0.11U	<0.2U	0.24J	0.26J	0.8	<0.71U	***5.4***
	Dibenz(a,h)anthracene	mg/kg	0.0031	0.33	0.33				1000	<0.13U	<0.22U	<0.12U	<0.22U	0.19J	<0.81U	**0.93**
	Dibenzofuran	mg/kg	0.014		59					<0.12U	<0.22U	<0.12U	<0.22U	0.19J	<0.79U	0.09J
	Diethylphthalate	mg/kg	0.015							<0.99U	<1.7U	<0.94U	<1.7U	<1.2U	<6.3U	<0.61U
	Dimethyl phthalate	mg/kg	0.015							<0.1U	<0.18U	<0.097U	<0.18U	<0.12U	<0.66U	<0.063U
	Di-n-butyl phthalate	mg/kg	0.017							<1.2U	<2.2U	<1.2U	<2.2U	<1.5U	<7.9U	<0.77U
	Di-n-octyl phthalate	mg/kg	0.015							<1.6U	<2.9U	<1.6U	<2.9U	<1.9U	<11U	<1U
	Fluoranthene	mg/kg	0.026	100	100				1000	<0.15U	<0.26U	0.54	0.46J	2.4	<0.95U	18
	Fluorene	mg/kg	0.0036	30	100				386	<0.11U	<0.2U	<0.1U	<0.19U	<0.13U	<0.71U	0.42
	Hexachlorobenzene	mg/kg	0.0029		1.2		3000			<0.2U	<0.36U	<0.19U	<0.35U	<0.24U	<1.3U	<0.13U
	Hexachlorobutadiene	mg/kg	0.0031			12				<0.17U	<0.29U	<0.16U	<0.29U	<0.19U	<1.1U	<0.1U
	Hexachlorocyclopentadiene	mg/kg	0.015			8.1				<0.29U	<0.51U	<0.27U	<0.5U	<0.34U	<1.8U	<0.18U
	Hexachloroethane	mg/kg	0.0099							<0.15U	<0.26U	<0.14U	<0.25U	<0.17U	<0.93U	<0.09U
	Indeno(1,2,3-c,d)pyrene	mg/kg	0.019	0.5	0.5				8.2	<0.11U	<0.2U	0.17J	0.21J	**0.56J**	<0.73U	**3.2**
	Isophorone	mg/kg	0.01							<0.14U	<0.25U	<0.14U	<0.25U	<0.17U	<0.92U	<0.089U
	Naphthalene	mg/kg	0.0097	12	100				12	<0.11U	0.3J	<0.1U	<0.19U	0.35J	1J	<0.068U
	Nitrobenzene	mg/kg	0.011				2000			<1U	<1.8U	<0.98U	<1.8U	<1.2U	<6.6U	<0.64U
	N-nitrosodi-n-propylamine	mg/kg	0.0032							<0.19U	<0.34U	<0.18U	<0.33U	<0.22U	<1.2U	<0.12U
	n-Nitrosodiphenylamine	mg/kg	0.013							<0.94U	<1.7U	<0.89U	<1.6U	<1.1U	<6U	<0.58U
	Pentachlorophenol	mg/kg	0.012	0.8	6.7	19	100000		0.8	*<4.6U*	*<8U*	*<4.3UJ*	*<7.9U*	*<5.3U*	*<29U*	*<2.8U*
	Phenanthrene	mg/kg	0.0044	100	100				1000	<0.15U	<0.27U	0.22J	0.27J	2.2	<0.97U	7.9
	Phenol	mg/kg	0.0033	0.33	100				0.33	*<0.86U*	*<1.5U*	<0.81UJ	*<1.5U*	*<1U*	*<5.5U*	*<0.53U*
	Pyrene	mg/kg	0.023	100	100				1000	<0.13U	<0.24U	0.43J	0.36J	1.9	<0.86U	11

Notes:

EQL - Estimated Quantitation Limit

SVOCs - Semivolatile organic compounds

PAHs - Polycyclic Aromatic Hydrocarbons

TCLP - Toxicity characteristic leaching procedure

SCO - Soil Cleanup Objectives

J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

U - non-detect at value indicated

B - Compound was found in the blank and sample.

F1 - MS and/or MSD Recovery is outside acceptance limits.

F2 - MS/MSD RPD exceeds control limits

* LCS or LCSD is outside acceptance limits.

J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated QC or calibration data or matrix interference.

p - The %RPD between the primary and confirmation column/detector is >40%. The lower value has been reported.

mg/kg - milligrams per kilogram

a - Sample ID "Test Pit 3" was taken from the Test Pit 3b location.

Chemical concentrations detected above Unrestricted SCOs are presented in Bold.

Chemical concentrations detected above Protection of Groundwater are presented in Italics

Chemical concentrations detected above 20xTCLP (200xTCLP for lead) are presented with underlines

Chemical concentrations detected above Restricted SCOs are presented in dark gray.

Chemical concentrations detected above Class C Sediment Guidance Values are presented in light gray

Total PAHs did not exceed 100 mg/kg in any sample.

DRAFT

TABLE 5-14
EHS Stormwater Sewer Catch Basin Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

								Segment 1			Rear Parking Lot		Football Field Complex	
							Sample Name	MH-1	MH-2	MH-3	CB-7	CB-6	SSHS-CB-11	SSHS-CB-13
							Sample Date	5/14/2019	11/7/2019	12/6/2019	5/28/2015	5/28/2015	5/15/2019	6/25/2019
							Lab_Report_Number	180-90048-1	180-98520-1	180-99716-1		180-44568-1	180-90165-1	180-91951-1
Group	**Chemical**	**Units**	**Unrestricted Use SCOs**	**Restricted Residential SCOs**	***Protection of Groundwater***	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)							
Metals	Aluminum	mg/kg						8600	7600	8400J+	4200	3900	4700	10,000
	Antimony	mg/kg						1.5J	0.79J	2.1	<0.13U	0.38J	<0.36U	0.6J
	Arsenic	mg/kg	13	16	16	33	100	6.4	2.7	4.5	8.2	4.8	2.3	5.6
	Barium	mg/kg	350	400	820		2000	120	110	140	29B	31B	21	100
	Beryllium	mg/kg	7.2	72	47			0.42J	0.39J	0.42J	0.16J	0.095J	0.16J	0.52J
	Cadmium	mg/kg	2.5	4.3	7.5	5	20	1.9	1.7	***17***	0.093J	0.15J	0.2J	0.12J
	Calcium	mg/kg						13,000	4100	11,000	54,000B	150,000B	32,000	9100
	Chromium (III+VI)	mg/kg	1	110	19	110	100	***37***	***53J+***	***130J+***	**7.6**	***24***	**6.8**	**12**
	Cobalt	mg/kg						7.4J	5.6J	9.5J	3.8	3.8J	4.3J	8.9
	Copper	mg/kg	50	270	1720	150		**120**	**160**	**250**	27	**56**	17	17
	Iron	mg/kg						21,000	17,000	20,000J+	14,000B	21,000B	12,000	19,000
	Lead	mg/kg	63	400	450	130	1000	**220**	**210**	**280**	19	29	15	16
	Magnesium	mg/kg						5200	2400	4300	5300	14,000	10,000	3400
	Manganese	mg/kg	1600	2000	2000			420	170J+	190J+	190	210	300	480
	Mercury	mg/kg	0.18	0.81	0.73	1	4	**0.37**	**0.47**	**0.5**	<0.0073U	0.13	<0.013U	<0.02U
	Nickel	mg/kg	30	310	130	49		25	23	**43**	18	17	12	27
	Potassium	mg/kg						1100	970	960J	410	270J	330J	1600
	Selenium	mg/kg	3.9	180	4		20	1.2J	<0.77U	1.2J	0.68	0.88	0.73J	<0.75U
	Sodium	mg/kg						170J	98J	250J	<0.027U	130J	73J	140J
	Silver	mg/kg	2	180	8.3	2.2	100	0.6J	0.95	**6.1**	**600**	<0.025U	<0.11U	<0.15U
	Thallium	mg/kg						<0.7U	<0.48U	<0.67U	<0.099U	<0.45U	<0.34U	<0.47U
	Vanadium	mg/kg						22	21	23	10B	15B	9.3	14
	Zinc	mg/kg	109	10000	2480	460		**390**	**390**	**690**	58B	**160B**	98	58
Polychlorinated Biphenyls	Arochlor 1016	mg/kg						<0.011U	<0.0091U	<0.014U	<0.0028U	<0.00053U	<0.0057U	<0.008U
	Arochlor 1221	mg/kg						<0.012U	<0.0099U	<0.015U	<0.0034U	<0.00065U	<0.0062U	<0.0087U
	Arochlor 1232	mg/kg						<0.0085U	<0.0068U	<0.01U	<0.0048U	<0.0009U	<0.0043U	<0.006U
	Arochlor 1242	mg/kg						<0.0051U	<0.0041U	<0.0062U	<0.0035U	<0.00066U	<0.0026U	<0.0036U
	Arochlor 1248	mg/kg						0.076J	0.14J	<0.01U	1.2J	<0.00065U	0.19J	0.14J
	Arochlor 1254	mg/kg						0.069J	0.08J	<0.013U	0.49J	0.024J	0.071J	0.092J
	Arochlor 1260	mg/kg						0.057J	0.075J	<0.012U	0.095J	0.0045J	0.012J	0.026J
	Arochlor 1268	mg/kg						<0.0047U	<0.0038U	<0.0057U	<0.0028U	<0.00053U	<0.0024U	<0.0033U
	Arochlor 1262	mg/kg						<0.012U	<0.0099U	<0.015U	<0.0051U	<0.00096U	<0.0062U	<0.0086U
	Total PCBs	mg/kg	0.1	1	3.2	1		**0.202**	**0.295**	ND	**1.785**	0.0285	**0.273**	**0.258**
SVOCs	Total PAHs	mg/kg				35.0	100	40.18	32.71	ND	4.01	**156.9**	5.565	ND
	1,1-Biphenyl	mg/kg						<0.43U	<0.24U	<0.11U	<0.078U	<0.075U	<0.06U	<0.02U
	1,2,4,5-tetrachlorobenzene	mg/kg				8.5		<0.44U	<0.24U	<0.11U	<0.067U	<0.064U	<0.062U	<0.021U
	1,4-Dioxane	mg/kg	0.1	13	0.1			*<3.2U*	*<1.8U*	*<0.81U*	<0.1U	<0.096U	*<0.45U*	*<0.15U*
	2,3,4,6-tetrachlorophenol	mg/kg						<4.3U	<2.3U	<1.1U	<0.057U	<0.054U	<0.6UJ	<0.2U
	2,4,5-trichlorophenol	mg/kg					400000	<0.73U	<0.4U	<0.19U	<0.094U	<0.089U	<0.1UJ	<0.035U
	2,4,6-trichlorophenol	mg/kg					2000	<0.56U	<0.31U	<0.14U	<0.13U	<0.13U	<0.079UJ	<0.027U
	2,4-dichlorophenol	mg/kg						<0.79U	<0.43U	<0.2U	<0.018U	<0.017U	<0.11UJ	<0.037U
	2,4-dimethylphenol	mg/kg						<0.63U	<0.35U	<0.16U	<0.14U	<0.13U	<0.089UJ	<0.03U
	2,4-dinitrophenol	mg/kg						<27UJ	<15U	<7U	<1U	<1U	<3.9UJ	<1.3U
	2,4-Dinitrotoluene	mg/kg					30130	<0.51U	<0.28U	<0.13U	<0.071U	<0.068U	<0.072U	<0.024U
	2,6-dinitrotoluene	mg/kg						<0.63U	<0.35U	<0.16U	<0.091U	<0.086U	<0.089U	<0.03U
	2-chloronaphthalene	mg/kg						<0.47U	<0.26U	<0.12U	<0.018U	<0.017U	<0.066U	<0.022U
	2-chlorophenol	mg/kg						<0.47U	<0.26U	<0.12U	<0.072U	<0.069U	<0.067UJ	<0.022U
	2-methylnaphthalene	mg/kg						<0.49U	<0.27U	<0.13U	<0.016U	0.2	<0.069U	<0.023U
	2-methylphenol	mg/kg		100			4200000	<2.9U	<1.6U	<0.75U	<0.061U	<0.059U	<0.41UJ	<0.14U
	2-nitroaniline	mg/kg						<4.7U	<2.6U	<1.2U	<0.39U	<0.38U	<0.66U	<0.22U
	2-nitrophenol	mg/kg						<1.6U	<0.89U	<0.42U	<0.097U	<0.092U	<0.23UJ	<0.077U
	3,3-Dichlorobenzidine	mg/kg						<9.5UJ	<5.2U	-	<0.093U	<0.089U	<1.3U	<0.45U
	3-nitroaniline	mg/kg						<2.6U	<1.4U	<0.66U	<0.36U	<0.35U	<0.37U	<0.12U
	4,6-Dinitro-2-methylphenol	mg/kg						<18U	<9.7U	<4.5U	<0.35U	<0.34U	<2.5UJ	<0.83U
	4-bromophenyl phenyl ether	mg/kg						<0.71U	<0.39U	<0.18U	<0.077U	<0.073U	<0.1U	<0.034U
	4-chloro-3-methylphenol	mg/kg						<0.48U	<0.26U	-	<0.081U	<0.077U	<0.068UJ	<0.023U
	4-chloroaniline	mg/kg						<0.34U	<0.19U	-	<0.07U	<0.067U	<0.048U	<0.016U
	4-chlorophenyl phenyl ether	mg/kg						<0.62U	<0.34U	-	<0.098U	<0.093U	<0.087U	<0.029U
	4-methylphenol	mg/kg					4200	<3U	<1.6U	-	0.2J	<0.082U	<0.42UJ	<0.14U
	4-nitroaniline	mg/kg						<0.5U	<0.27U	-	<0.36U	<0.34U	<0.07U	<0.023U
	4-nitrophenol	mg/kg						<7.2U	<3.9UJ	-	<0.32U	<0.31U	<1UJ	<0.34U
	Acenaphthene	mg/kg	20	100	98			<0.59U	<0.32U	-	<0.017U	0.91	<0.083U	<0.028U
	Acenaphthylene	mg/kg	100	100	107			<0.45U	<0.25U	-	<0.02U	0.9	<0.063U	<0.021U
	Acetophenone	mg/kg						<0.55U	<0.3U	-	<0.072U	<0.069U	<0.078U	<0.026U
	Anthracene	mg/kg		100	1000			<0.53U	0.44J	-	<0.017U	5.4	0.083J	<0.025U
	Atrazine	mg/kg						<4.5U	<2.5U	-	<0.086U	<0.082U	<0.63U	<0.21U
	Benz(a)anthracene	mg/kg	1	1	`			**2.7**	**2.3**	-	0.22	**12**	0.4	<0.018U
	Benzaldehyde	mg/kg						-	<0.7U	-	<0.13UJ	<0.13UJ	-	<0.06U
	Benzo(a) pyrene	mg/kg	1	1	22			**3.3**	**2.8**	-	0.28	**11**	0.38	<0.021U
	Benzo(b)fluoranthene	mg/kg	1	1	1.7			***5.5***	***4.3***	-	0.37	***13***	0.54	<0.024U
	Benzo(g,h,i)perylene	mg/kg	100	100	1000			3.4	2.3	-	0.32	11	0.31	<0.021U
	Benzo(k)fluoranthene	mg/kg	0.8	3.9	1.7			***1.7J***	**1.4**	-	0.14J	***5.5***	0.25J	<0.029U
	Bis(2-chloroethoxy) methane	mg/kg						<0.49U	<0.27U	-	<0.058U	<0.055U	<0.069U	<0.023U
	Bis(2-chloroethyl)ether	mg/kg						<0.37U	<0.2U	-	<0.024U	<0.022U	<0.052U	<0.018U
	Bis(2-chloroisopropyl) ether	mg/kg						<0.76U	<0.42U	-	<0.019U	<0.018U	<0.11U	<0.036U
	Bis(2-ethylhexyl) phthalate	mg/kg						<11U	<6U	-	<0.14U	2.8	<1.5U	<0.51U
	Butyl benzyl phthalate	mg/kg						<7U	<3.9U	-	<0.12U	<0.11U	<0.99U	<0.33U
	Caprolactam	mg/kg						<6.6U	<3.7U	-	<0.66U	<0.63U	<0.94U	<0.31U
	Carbazole	mg/kg						0.55J	0.5J	-	<0.016U	2.2	<0.067U	<0.023U
	Chrysene	mg/kg	1	3.9	1			***3.7***	***3.4***	-	0.39	***13***	0.54	<0.019U
	Dibenz(a,h)anthracene	mg/kg	0.33	0.33	1000			**0.69J**	**0.62J**	-	<0.02U	**2.3**	0.084J	<0.022U
	Dibenzofuran	mg/kg		59				<0.45U	<0.25U	-	<0.087U	0.58J	<0.063U	<0.021U
	Diethylphthalate	mg/kg						<3.6U	<2U	-	<0.096U	<0.091U	<0.51U	<0.17U
	Dimethyl phthalate	mg/kg						<0.37U	<0.2U	-	<0.096U	<0.091U	<0.052U	<0.018U
	Di-n-butyl phthalate	mg/kg						<4.5U	<2.5U	-	<0.11U	<0.1U	<0.63U	<0.21U
	Di-n-octyl phthalate	mg/kg						<5.9U	<3.3U	-	<0.093U	<0.088U	<0.84U	<0.28U
	Fluoranthene	mg/kg	100	100	1000			7.5	5.7	-	0.91	33	1.3	<0.026U
	Fluorene	mg/kg	30	100	386			<0.4U	<0.22U	-	<0.023U	1.6	<0.057U	<0.019U
	Hexachlorobenzene	mg/kg		1.2			3000	<0.73U	<0.4U	-	<0.019UJ	<0.018UJ	<0.1U	<0.035U
	Hexachlorobutadiene	mg/kg				12		<0.6U	<0.33U	-	<0.02UJ	<0.019UJ	<0.084U	<0.028U
	Hexachlorocyclopentadiene	mg/kg				8.1		<1UJ	<0.57U	-	<0.095U	<0.09U	<0.15U	<0.049U
	Hexachloroethane	mg/kg						<0.53U	<0.29U	-	<0.063U	<0.06U	<0.074U	<0.025U
	Indeno(1,2,3-c,d)pyrene	mg/kg	0.5	0.5	8.2			**2.9**	**2**	-	0.26	***9***	0.29	<0.02U
	Isophorone	mg/kg						<0.52U	<0.29U	-	<0.066U	<0.063U	<0.073U	<0.025U
	Naphthalene	mg/kg	12	100	12			<0.4U	<0.22U	-	<0.015U	0.17	<0.056U	<0.019U
	Nitrobenzene	mg/kg					2000	<3.7U	<2.1U	-	<0.073U	<0.07U	<0.53U	<0.18U
	N-nitrosodi-n-propylamine	mg/kg						<0.69U	<0.38U	-	<0.021U	<0.02U	<0.098U	<0.033U
	n-Nitrosodiphenylamine	mg/kg						<3.4U	<1.9U	-	<0.081U	<0.078U	<0.48U	<0.16U
	Pentachlorophenol	mg/kg	0.8	6.7	0.8	19	100000	*<16UJ*	*<9U*	-	<0.079U	<0.075U	*<2.3UJ*	<0.78U
	Phenanthrene	mg/kg	100	100	1000			2.8	2.7	-	0.51	19	0.4	<0.026U
	Phenol	mg/kg	0.33	100	0.33			*<3.1U*	*<1.7U*	-	<0.021U	<0.02U	*<0.44UJ*	<0.15U
	Pyrene	mg/kg	100	100	1000			5.1	4.4	-	0.61	20	0.9	<0.023U

DRAFT

Notes:

SVOCs - Semivolatile organic compounds
PAHs - Polycyclic Aromatic Hydrocarbons
TCLP - Toxicity characteristic leaching procedure
SCO - Soil Cleanup Objectives
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at value indicated
B - Compound was found in the blank and sample.
F1 - MS and/or MSD Recovery is outside acceptance limits.
F2 - MS/MSD RPD exceeds control limits
* LCS or LCSD is outside acceptance limits.
J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated

mg/kg - milligrams per kilogram
a - Sample ID "UK-1" was taken from the MH-2 location and "Test Pit 3" was taken from the Test Pit 3b location.
SVOCs - semi volatile organic compounds
Chemical concentrations detected above Unrestricted SCOs are presented in Bold.
Chemical concentrations detected above 20xTCLP (200xTCLP for lead) are presented with underlines
Chemical concentrations detected above Restricted SCOs are presented in dark gray.
Chemical concentrations detected above Class C Sediment Guidance Values are presented in light gray

TABLE 5-14
EHS Stormwater Sewer Catch Basin Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

								Football Field Complex						
							Sample Name	SSHS-CB-20	SSHS-CB-25	SSHS-CB-26	SSHS-CB-27	SSHS-CB-31	SSHS-CB-32	SSHS-CB-33
							Sample Date	6/24/2019	6/24/2019	6/25/2019	6/25/2019	6/25/2019	6/24/2019	6/24/2019
							Lab_Report_Number	180-91951-1	180-91951-1	180-91951-1	180-91951-1	180-91951-1	180-91951-1	180-91951-1
Group	**Chemical**	**Units**	**Unrestricted Use SCOs**	**Restricted Residential SCOs**	***Protection of Groundwater***	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)							
Metals	Aluminum	mg/kg						8100	13,000	7700	8500	11,000	9300	13,000
	Antimony	mg/kg						0.59J	2J	1.7	0.52J	1J	<0.6UJ	<0.54U
	Arsenic	mg/kg	13	16	16	33	100	5.8	8	5.5	4.4	5.7	0.89J	1.9
	Barium	mg/kg	350	400	820		2000	75	110	63	70	100	33J	53
	Beryllium	mg/kg	7.2	72	47			0.41J	0.65J	0.43J	0.41J	0.51J	0.14J	0.29J
	Cadmium	mg/kg	2.5	4.3	7.5	5	20	0.25J	1.2	0.48J	0.25J	0.16J	0.19J	0.27J
	Calcium	mg/kg						19,000	7900	4300	12,000	24,000J	200,000	60,000
	Chromium (III+VI)	mg/kg	1	110	19	110	100	**16**	***21***	***23***	**12**	**13**	**6.9**	**14**
	Cobalt	mg/kg						6.9J	10J	7.1J	6.8J	9.5	<2.6U	4J
	Copper	mg/kg	50	270	1720	150		27	32	35	15	17	11	14
	Iron	mg/kg						17,000	23,000	26,000	15,000	19,000	4300	10,000
	Lead	mg/kg	63	400	450	130	1000	**420**	28	18	11	17	<4.5U	11
	Magnesium	mg/kg						9700	4100	2500	3400	6400	17,000J-	6200
	Manganese	mg/kg	1600	2000	2000			360	440	580	270	640J	73	190
	Mercury	mg/kg	0.18	0.81	0.73	1	4	0.058	0.1	0.054J	0.025J	0.031J	<0.026U	0.042J
	Nickel	mg/kg	30	310	130	49		21	24	17	16	21	5.6J	13
	Potassium	mg/kg						800J	2000	880	1100	1600	1300	930
	Selenium	mg/kg	3.9	180	4		20	<0.85U	<1.2U	<0.84U	<0.74U	<0.76U	2.2	0.95J
	Sodium	mg/kg						79J	82J	72J	59J	110J	170J	150J
	Silver	mg/kg	2	180	8.3	2.2	100	<0.17U	<0.25U	<0.17U	<0.15U	<0.15U	<0.19U	<0.17U
	Thallium	mg/kg						<0.53U	<0.75U	<0.52U	<0.46U	<0.47U	<2.8U	<0.51U
	Vanadium	mg/kg						14	18	25	12	15	12	15
	Zinc	mg/kg	109	10000	2480	460		**210**	**190**	**140**	72	59	**330**	**220**
Polychlorinated Biphenyls	Arochlor 1016	mg/kg						<0.0085U	<0.013U	<0.009U	<0.0074U	<0.0076U	<0.0092U	<0.0081U
	Arochlor 1221	mg/kg						<0.0093U	<0.014U	<0.0098U	<0.008U	<0.0083U	<0.01U	<0.0088U
	Arochlor 1232	mg/kg						<0.0064U	<0.0099U	<0.0068U	<0.0055U	<0.0057U	<0.0069U	<0.006U
	Arochlor 1242	mg/kg						<0.0038U	<0.0059U	<0.0041U	<0.0033U	<0.0034U	<0.0041U	<0.0036U
	Arochlor 1248	mg/kg						0.96J	<0.0097U	0.042J	0.042J	0.75J	0.064J	0.039J
	Arochlor 1254	mg/kg						0.44J	<0.012U	0.025J	0.021J	0.36J	0.028J	0.03J
	Arochlor 1260	mg/kg						0.12J	<0.012U	<0.0079U	<0.0065U	0.077J	<0.008U	<0.0071U
	Arochlor 1268	mg/kg						<0.0035U	<0.0054U	<0.0037U	<0.0031U	<0.0031U	<0.0038U	<0.0033U
	Arochlor 1262	mg/kg						<0.0092U	<0.014U	<0.0098U	<0.008U	<0.0082U	<0.0099U	<0.0087U
	Total PCBs	mg/kg	0.1	1	3.2	1		**1.52**	ND	0.067	0.063	**1.187**	0.092	0.069
SVOCs	Total PAHs	mg/kg				35.0	100	1.232	0.644	0.23	0.276	0.744	1	0.67
	1,1-Biphenyl	mg/kg						<0.066U	<0.068U	<0.024U	<0.019U	<0.02U	<0.12U	<0.21U
	1,2,4,5-tetrachlorobenzene	mg/kg				8.5		<0.068U	<0.069U	<0.024U	<0.02U	<0.021U	<0.12U	<0.21U
	1,4-Dioxane	mg/kg	0.1	13	0.1			*<0.49U*	*<0.5U*	*<0.18U*	*<0.14U*	*<0.15U*	*<0.88U*	*<1.5U*
	2,3,4,6-tetrachlorophenol	mg/kg						<0.65U	<0.67U	<0.24U	<0.19U	<0.2U	<1.2U	<2.1U
	2,4,5-trichlorophenol	mg/kg					400000	<0.11U	<0.11U	<0.04U	<0.033U	<0.034U	<0.2U	<0.35U
	2,4,6-trichlorophenol	mg/kg					2000	<0.086U	<0.088U	<0.031U	<0.025U	<0.026U	<0.16U	<0.27U
	2,4-dichlorophenol	mg/kg						<0.12U	<0.12U	<0.044U	<0.036U	<0.037U	<0.22U	<0.38U
	2,4-dimethylphenol	mg/kg						<0.097U	<0.1U	<0.035U	<0.029U	<0.029U	<0.18U	<0.31U
	2,4-dinitrophenol	mg/kg						<4.2U	<4.3U	<1.5U	<1.2U	<1.3U	<7.6U	<13U
	2,4-Dinitrotoluene	mg/kg					30130	<0.078U	<0.08U	<0.028U	<0.023U	<0.024U	<0.14U	<0.25U
	2,6-dinitrotoluene	mg/kg						<0.097U	<0.099U	<0.035U	<0.028U	<0.029U	<0.17U	<0.31U
	2-chloronaphthalene	mg/kg						<0.072U	<0.074U	<0.026U	<0.021U	<0.022U	<0.13U	<0.23U
	2-chlorophenol	mg/kg						<0.073U	<0.075U	<0.026U	<0.021U	<0.022U	<0.13U	<0.23U
	2-methylnaphthalene	mg/kg						<0.075U	<0.077U	<0.027U	<0.022U	0.025J	<0.14U	<0.24U
	2-methylphenol	mg/kg		100			4200000	<0.45U	<0.46U	<0.16U	<0.13U	<0.14U	<0.81U	<1.4U
	2-nitroaniline	mg/kg						<0.71U	<0.73U	<0.26U	<0.21U	<0.22U	<1.3U	<2.3U
	2-nitrophenol	mg/kg						<0.25U	<0.26U	<0.09U	<0.073U	<0.076U	<0.45U	<0.79U
	3,3-Dichlorobenzidine	mg/kg						<1.5U	<1.5U	<0.53U	<0.43U	<0.44U	<2.6U	<4.6U
	3-nitroaniline	mg/kg						<0.4U	<0.41U	<0.14U	<0.12U	<0.12U	<0.72U	<1.3U
	4,6-Dinitro-2-methylphenol	mg/kg						<2.7U	<2.8U	<0.98U	<0.79U	<0.82U	<4.9U	<8.6U
	4-bromophenyl phenyl ether	mg/kg						<0.11U	<0.11U	<0.04U	<0.032U	<0.033U	<0.2U	<0.35U
	4-chloro-3-methylphenol	mg/kg						<0.074U	<0.076U	<0.027U	<0.022U	<0.022U	<0.13U	<0.23U
	4-chloroaniline	mg/kg						<0.052U	<0.054U	<0.019U	<0.015U	<0.016U	1J	0.37J
	4-chlorophenyl phenyl ether	mg/kg						<0.095U	<0.097U	<0.034U	<0.028U	<0.029U	<0.17U	<0.3U
	4-methylphenol	mg/kg					4200	<0.46U	<0.47U	<0.17U	<0.14U	<0.14U	<0.83U	<1.5U
	4-nitroaniline	mg/kg						<0.076U	<0.078U	<0.028U	<0.022U	<0.023U	<0.14U	<0.24U
	4-nitrophenol	mg/kg						<1.1U	<1.1U	<0.4U	<0.32U	<0.33U	<2U	<3.5U
	Acenaphthene	mg/kg	20	100	98			<0.09U	<0.093U	<0.033U	<0.027U	<0.027U	<0.16U	<0.29U
	Acenaphthylene	mg/kg	100	100	107			<0.068U	<0.07U	<0.025U	<0.02U	<0.021U	<0.12U	<0.22U
	Acetophenone	mg/kg						<0.085U	<0.087U	<0.031U	<0.025U	<0.026U	<0.15U	<0.27U
	Anthracene	mg/kg		100	1000			<0.081U	<0.083U	<0.029U	<0.024U	<0.025U	<0.15U	<0.26U
	Atrazine	mg/kg						<0.68U	<0.7U	<0.25U	<0.2U	<0.21U	<1.2U	<2.2U
	Benz(a)anthracene	mg/kg	1	1	`			0.11J	0.08J	<0.021U	0.036J	0.068J	<0.11U	<0.19U
	Benzaldehyde	mg/kg						<0.19U	<0.2U	<0.07U	<0.057U	<0.059U	<0.35U	<0.62U
	Benzo(a) pyrene	mg/kg	1	1	22			0.12J	<0.07U	<0.025U	<0.02U	0.059J	<0.12U	<0.22U
	Benzo(b)fluoranthene	mg/kg	1	1	1.7			0.11J	<0.079U	<0.028U	<0.023U	0.068J	<0.14U	<0.24U
	Benzo(g,h,i)perylene	mg/kg	100	100	1000			0.13J	<0.069U	<0.024U	<0.02U	0.058J	<0.12U	<0.21U
	Benzo(k)fluoranthene	mg/kg	0.8	3.9	1.7			<0.094U	<0.096U	<0.034U	<0.028U	0.036J	<0.17U	<0.3U
	Bis(2-chloroethoxy) methane	mg/kg						<0.075U	<0.077U	<0.027U	<0.022U	<0.023U	<0.13U	<0.24U
	Bis(2-chloroethyl)ether	mg/kg						<0.057U	<0.058U	<0.021U	<0.017U	<0.017U	<0.1U	<0.18U
	Bis(2-chloroisopropyl) ether	mg/kg						<0.12U	<0.12U	<0.042U	<0.034U	<0.035U	<0.21U	<0.37U
	Bis(2-ethylhexyl) phthalate	mg/kg						<1.7U	<1.7U	<0.6U	<0.49U	<0.51U	<3U	<5.3U
	Butyl benzyl phthalate	mg/kg						<1.1U	<1.1U	<0.39U	<0.32U	<0.33U	<1.9U	<3.4U
	Caprolactam	mg/kg						<1U	<1U	<0.37U	<0.3U	<0.31U	<1.8U	<3.2U
	Carbazole	mg/kg						<0.073U	<0.075U	<0.027U	<0.022U	<0.022U	<0.13U	<0.23U
	Chrysene	mg/kg	1	3.9	1			0.11J	<0.063U	<0.022U	0.036J	0.073J	<0.11U	<0.2U
	Dibenz(a,h)anthracene	mg/kg	0.33	0.33	1000			<0.07U	<0.072U	<0.025U	<0.021U	<0.021U	<0.13U	<0.22U
	Dibenzofuran	mg/kg		59				<0.068U	<0.07U	<0.025U	<0.02U	<0.021U	<0.12U	<0.22U
	Diethylphthalate	mg/kg						<0.55U	<0.56U	<0.2U	<0.16U	<0.17U	<0.99U	<1.7U
	Dimethyl phthalate	mg/kg						<0.057U	<0.058U	<0.021U	<0.017U	<0.017U	<0.1U	<0.18U
	Di-n-butyl phthalate	mg/kg						<0.68U	<0.7U	<0.25U	<0.2U	<0.21U	<1.2U	<2.2U
	Di-n-octyl phthalate	mg/kg						<0.91U	<0.94U	<0.33U	<0.27U	<0.28U	<1.6U	<2.9U
	Fluoranthene	mg/kg	100	100	1000			0.16J	<0.085U	0.03J	0.043J	0.092J	<0.15U	<0.26U
	Fluorene	mg/kg	30	100	386			<0.061U	<0.063U	<0.022U	<0.018U	<0.019U	<0.11U	<0.2U
	Hexachlorobenzene	mg/kg		1.2			3000	<0.11U	<0.12U	<0.041U	<0.033U	<0.034U	<0.2U	<0.36U
	Hexachlorobutadiene	mg/kg				12		<0.091U	<0.094U	<0.033U	<0.027U	<0.028U	<0.17U	<0.29U
	Hexachlorocyclopentadiene	mg/kg				8.1		<0.16U	<0.16U	<0.058U	<0.047U	<0.049U	<0.29U	<0.51U
	Hexachloroethane	mg/kg						<0.081U	<0.083U	<0.029U	<0.024U	<0.025U	<0.15U	<0.26U
	Indeno(1,2,3-c,d)pyrene	mg/kg	0.5	0.5	8.2			0.082J	<0.065U	<0.023U	<0.019U	0.045J	<0.11U	<0.2U
	Isophorone	mg/kg						<0.08U	<0.082U	<0.029U	<0.023U	<0.024U	<0.14U	<0.25U
	Naphthalene	mg/kg	12	100	12			<0.061U	<0.063U	<0.022U	<0.018U	0.021J	<0.11U	0.3J
	Nitrobenzene	mg/kg					2000	<0.57U	<0.59U	<0.21U	<0.17U	<0.17U	<1U	<1.8U
	N-nitrosodi-n-propylamine	mg/kg						<0.11U	<0.11U	<0.038U	<0.031U	<0.032U	<0.19U	<0.34U
	n-Nitrosodiphenylamine	mg/kg						<0.52U	<0.54U	<0.19U	<0.15U	<0.16U	<0.94U	<1.7U
	Pentachlorophenol	mg/kg	0.8	6.7	0.8	19	100000	*<2.5U*	*<2.6U*	*<0.91U*	<0.74U	<0.76U	*<4.6U*	*<8U*
	Phenanthrene	mg/kg	100	100	1000			<0.084U	<0.086U	<0.03U	<0.025U	0.071J	<0.15U	<0.27U
	Phenol	mg/kg	0.33	100	0.33			*<0.47U*	*<0.49U*	<0.17U	<0.14U	<0.14U	*<0.86U*	*<1.5U*
	Pyrene	mg/kg	100	100	1000			0.15J	0.082J	0.035J	0.043J	0.11	<0.13U	<0.24U

Notes:

SVOCs - Semivolatile organic compounds
PAHs - Polycyclic Aromatic Hydrocarbons
TCLP - Toxicity characteristic leaching procedure
SCO - Soil Cleanup Objectives
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at value indicated
B - Compound was found in the blank and sample.
F1 - MS and/or MSD Recovery is outside acceptance limits.
F2 - MS/MSD RPD exceeds control limits
* LCS or LCSD is outside acceptance limits.
J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated

mg/kg - milligrams per kilogram
a - Sample ID "UK-1" was taken from the MH-2 location and "Test Pit 3" was taken from the Test Pit
SVOCs - semi volatile organic compounds
Chemical concentrations detected above Unrestricted SCOs are presented in Bold.
Chemical concentrations detected above 20xTCLP (200xTCLP for lead) are presented with underlines
Chemical concentrations detected above Restricted SCOs are presented in dark gray.
Chemical concentrations detected above Class C Sediment Guidance Values are presented in light gray

DRAFT

TABLE 5-14
EHS Stormwater Sewer Catch Basin Sampling Results

Former Sperry Remington – North Portion #c808022
Elmira, New Yok

								Football Field Complex				
							Sample Name	SSHS-CB-34	SSHS-CB-35	SSHS-CB-36	SSHS-CB-37	SSHS-CB-38
							Sample Date	5/15/2019	6/24/2019	6/24/2019	6/24/2019	5/15/2019
							Lab_Report_Number	180-90165-1	180-91951-1	180-91951-1	180-91951-1	180-90165-1
Group	**Chemical**	**Units**	**Unrestricted Use SCOs**	**Restricted Residential SCOs**	***Protection of Groundwater***	**Class C Sediment Guidance Value**	20x TCLP Screening (Lead = 1000 ppm)					
Metals	Aluminum	mg/kg						3900	6100	9900	7200	4000
	Antimony	mg/kg						<0.68U	3.1J	0.48J	0.38J	<0.35U
	Arsenic	mg/kg	13	16	16	33	100	<0.78U	4.3	5.3	5.4	2
	Barium	mg/kg	350	400	820		2000	16J	52J	93	36	39
	Beryllium	mg/kg	7.2	72	47			0.066J	0.34J	0.5J	0.25J	0.23J
	Cadmium	mg/kg	2.5	4.3	7.5	5	20	0.15J	0.42J	0.14J	0.41J	0.13J
	Calcium	mg/kg						14,000	87,000	14,000	27,000J	48,000
	Chromium (III+VI)	mg/kg	1	110	19	110	100	**3**	**10**	**12**	**9.6**	**4.6**
	Cobalt	mg/kg						0.81J	4.3J	8.5	5.7	2.2J
	Copper	mg/kg	50	270	1720	150		5.7	22	15	17	10
	Iron	mg/kg						2400	16,000	19,000	15,000	12,000
	Lead	mg/kg	63	400	450	130	1000	4.7	17	13	17	4.9
	Magnesium	mg/kg						1700	17,000	3000	3700	9300
	Manganese	mg/kg	1600	2000	2000			61	520	390	310	190
	Mercury	mg/kg	0.18	0.81	0.73	1	4	0.041J	0.11J	0.098	<0.016UJ	<0.015U
	Nickel	mg/kg	30	310	130	49		4J	24	20	18	7.7
	Potassium	mg/kg						170J	1100J	1400	570	260J
	Selenium	mg/kg	3.9	180	4		20	<1U	2.1J	<0.67U	0.69J	0.7J
	Sodium	mg/kg						89J	190J	61J	64J	160J
	Silver	mg/kg	2	180	8.3	2.2	100	<0.21U	<0.37U	<0.14U	<0.12U	<0.11U
	Thallium	mg/kg						<0.64U	<1.1U	<0.42U	<0.36U	<0.33U
	Vanadium	mg/kg						6.1J	14J	13	16	6.2
	Zinc	mg/kg	109	10000	2480	460		71	**210**	61	**510**	59
Polychlorinated Biphenyls	Arochlor 1016	mg/kg						<0.011U	<0.02U	<0.0067U	<0.0059U	<0.0059U
	Arochlor 1221	mg/kg						<0.012U	<0.022U	<0.0073U	<0.0064U	<0.0064U
	Arochlor 1232	mg/kg						<0.0083U	<0.015U	<0.005U	<0.0044U	<0.0044U
	Arochlor 1242	mg/kg						<0.005U	<0.0091U	<0.003U	<0.0026U	<0.0026U
	Arochlor 1248	mg/kg						0.082J	0.48J	0.19J	0.061J	0.022
	Arochlor 1254	mg/kg						0.047J	0.2J	0.085J	0.051J	<0.0054U
	Arochlor 1260	mg/kg						0.054J	0.052J	0.031J	0.02J	<0.0051U
	Arochlor 1268	mg/kg						<0.0046U	<0.0083U	<0.0028U	<0.0024U	<0.0024U
	Arochlor 1262	mg/kg						<0.012U	<0.022U	<0.0073U	<0.0064U	<0.0063U
	Total PCBs	mg/kg	0.1	1	3.2	1		**0.183**	**0.732**	**0.306**	**0.132**	0.022
SVOCs	Total PAHs	mg/kg				35.0	100	2.91	3.405	13.06	7.395	**71.77**
	1,1-Biphenyl	mg/kg						<0.11U	<0.21U	0.14J	0.86J	<0.073U
	1,2,4,5-tetrachlorobenzene	mg/kg				8.5		<0.12U	<0.21U	<0.14U	<0.78U	<0.075U
	1,4-Dioxane	mg/kg	0.1	13	0.1			*<0.83U*	*<1.5U*	*<1U*	*<5.6U*	*<0.55U*
	2,3,4,6-tetrachlorophenol	mg/kg						<1.1UJ	<2U	<1.4U	<7.5U	<0.73U
	2,4,5-trichlorophenol	mg/kg					400000	<0.19UJ	<0.35U	<0.24U	<1.3U	<0.12U
	2,4,6-trichlorophenol	mg/kg					2000	<0.15UJ	<0.27U	<0.18U	<0.99U	<0.096U
	2,4-dichlorophenol	mg/kg						<0.21UJ	<0.38U	<0.26U	<1.4U	<0.13U
	2,4-dimethylphenol	mg/kg						<0.17UJ	<0.31U	<0.21U	<1.1U	<0.11U
	2,4-dinitrophenol	mg/kg						<7.2UJ	<13U	<8.9U	<49U	<4.7U
	2,4-Dinitrotoluene	mg/kg					30130	<0.13U	<0.24U	<0.17U	<0.9U	<0.087U
	2,6-dinitrotoluene	mg/kg						<0.16U	<0.3U	<0.2U	<1.1U	<0.11U
	2-chloronaphthalene	mg/kg						<0.12U	<0.23U	<0.15U	<0.83U	<0.08U
	2-chlorophenol	mg/kg						<0.12UJ	<0.23U	<0.15U	<0.84U	<0.081U
	2-methylnaphthalene	mg/kg						<0.13U	<0.24U	<0.16U	<0.87U	<0.084U
	2-methylphenol	mg/kg		100			4200000	<0.76UJ	<1.4U	<0.95U	<5.2U	<0.5U
	2-nitroaniline	mg/kg						<1.2U	<2.2U	<1.5U	<8.2U	<0.8U
	2-nitrophenol	mg/kg						<0.42UJ	<0.78U	<0.53U	<2.9U	<0.28U
	3,3-Dichlorobenzidine	mg/kg						<2.5U	<4.6U	<3.1U	<17U	<1.6U
	3-nitroaniline	mg/kg						<0.68U	<1.3U	<0.84U	<4.6U	<0.44U
	4,6-Dinitro-2-methylphenol	mg/kg						<4.6UJ	<8.5U	<5.7U	<31U	<3U
	4-bromophenyl phenyl ether	mg/kg						<0.19U	<0.34U	<0.23U	<1.3U	<0.12U
	4-chloro-3-methylphenol	mg/kg						<0.13UJ	<0.23U	<0.16U	<0.85U	<0.082U
	4-chloroaniline	mg/kg						<0.089U	<0.16U	<0.11U	<0.6U	<0.058U
	4-chlorophenyl phenyl ether	mg/kg						<0.16U	<0.3U	<0.2U	<1.1U	<0.11U
	4-methylphenol	mg/kg					4200	<0.78UJ	<1.4U	<0.97U	<5.3U	<0.51U
	4-nitroaniline	mg/kg						0.38J	<0.24U	<0.16U	<0.88U	<0.085U
	4-nitrophenol	mg/kg						<1.9UJ	<3.4U	<2.3U	<13U	<1.2U
	Acenaphthene	mg/kg	20	100	98			<0.15U	<0.28U	<0.19U	<1U	0.13J
	Acenaphthylene	mg/kg	100	100	107			<0.12U	<0.22U	0.31J	<0.79U	0.082J
	Acetophenone	mg/kg						<0.14U	<0.27U	<0.18U	<0.98U	<0.095U
	Anthracene	mg/kg		100	1000			<0.14U	<0.26U	0.51J	<0.94U	2.4
	Atrazine	mg/kg						<1.2U	<2.2U	<1.5U	<7.9U	<0.77U
	Benz(a)anthracene	mg/kg	1	1	`			0.21J	0.25J	**1**	<0.68U	**5.7**
	Benzaldehyde	mg/kg						-	<0.61U	<0.41U	<2.2U	-
	Benzo(a) pyrene	mg/kg	1	1	22			0.26J	0.26J	0.77	<0.79U	**5**
	Benzo(b)fluoranthene	mg/kg	1	1	1.7			0.24J	0.31J	0.95	<0.89U	***6***
	Benzo(g,h,i)perylene	mg/kg	100	100	1000			0.23J	0.34J	0.61J	0.93J	3.4
	Benzo(k)fluoranthene	mg/kg	0.8	3.9	1.7			<0.16U	<0.29U	0.44J	<1.1U	***2.3***
	Bis(2-chloroethoxy) methane	mg/kg						<0.13U	<0.23U	<0.16U	<0.86U	<0.083U
	Bis(2-chloroethyl)ether	mg/kg						<0.097U	<0.18U	<0.12U	<0.66U	<0.063U
	Bis(2-chloroisopropyl) ether	mg/kg						<0.2U	<0.36U	<0.25U	<1.3U	<0.13U
	Bis(2-ethylhexyl) phthalate	mg/kg						<2.8U	<5.2U	<3.5U	<19U	<1.9U
	Butyl benzyl phthalate	mg/kg						<1.8U	<3.4U	<2.3U	<12U	<1.2U
	Caprolactam	mg/kg						<1.7U	<3.2U	<2.2U	<12U	<1.1U
	Carbazole	mg/kg						0.14J	<0.23U	0.19J	<0.85U	0.2J
	Chrysene	mg/kg	1	3.9	1			0.24J	0.26J	0.8	<0.71U	***5.4***
	Dibenz(a,h)anthracene	mg/kg	0.33	0.33	1000			<0.12U	<0.22U	0.19J	<0.81U	**0.93**
	Dibenzofuran	mg/kg		59				<0.12U	<0.22U	0.19J	<0.79U	0.09J
	Diethylphthalate	mg/kg						<0.94U	<1.7U	<1.2U	<6.3U	<0.61U
	Dimethyl phthalate	mg/kg						<0.097U	<0.18U	<0.12U	<0.66U	<0.063U
	Di-n-butyl phthalate	mg/kg						<1.2U	<2.2U	<1.5U	<7.9U	<0.77U
	Di-n-octyl phthalate	mg/kg						<1.6U	<2.9U	<1.9U	<11U	<1U
	Fluoranthene	mg/kg	100	100	1000			0.54	0.46J	2.4	<0.95U	18
	Fluorene	mg/kg	30	100	386			<0.1U	<0.19U	<0.13U	<0.71U	0.42
	Hexachlorobenzene	mg/kg		1.2			3000	<0.19U	<0.35U	<0.24U	<1.3U	<0.13U
	Hexachlorobutadiene	mg/kg				12		<0.16U	<0.29U	<0.19U	<1.1U	<0.1U
	Hexachlorocyclopentadiene	mg/kg				8.1		<0.27U	<0.5U	<0.34U	<1.8U	<0.18U
	Hexachloroethane	mg/kg						<0.14U	<0.25U	<0.17U	<0.93U	<0.09U
	Indeno(1,2,3-c,d)pyrene	mg/kg	0.5	0.5	8.2			0.17J	0.21J	**0.56J**	<0.73U	**3.2**
	Isophorone	mg/kg						<0.14U	<0.25U	<0.17U	<0.92U	<0.089U
	Naphthalene	mg/kg	12	100	12			<0.1U	<0.19U	0.35J	1J	<0.068U
	Nitrobenzene	mg/kg					2000	<0.98U	<1.8U	<1.2U	<6.6U	<0.64U
	N-nitrosodi-n-propylamine	mg/kg						<0.18U	<0.33U	<0.22U	<1.2U	<0.12U
	n-Nitrosodiphenylamine	mg/kg						<0.89U	<1.6U	<1.1U	<6U	<0.58U
	Pentachlorophenol	mg/kg	0.8	6.7	0.8	19	100000	*<4.3UJ*	*<7.9U*	*<5.3U*	*<29U*	*<2.8U*
	Phenanthrene	mg/kg	100	100	1000			0.22J	0.27J	2.2	<0.97U	7.9
	Phenol	mg/kg	0.33	100	0.33			<0.81UJ	*<1.5U*	*<1U*	*<5.5U*	*<0.53U*
	Pyrene	mg/kg	100	100	1000			0.43J	0.36J	1.9	<0.86U	11

Notes:

SVOCs - Semivolatile organic compounds
PAHs - Polycyclic Aromatic Hydrocarbons
TCLP - Toxicity characteristic leaching procedure
SCO - Soil Cleanup Objectives
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
U - non-detect at value indicated
B - Compound was found in the blank and sample.
F1 - MS and/or MSD Recovery is outside acceptance limits.
F2 - MS/MSD RPD exceeds control limits
* LCS or LCSD is outside acceptance limits.
J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated

mg/kg - milligrams per kilogram
a - Sample ID "UK-1" was taken from the MH-2 location and "Test Pit 3" was taken from the Test Pit
SVOCs - semi volatile organic compounds
Chemical concentrations detected above Unrestricted SCOs are presented in Bold.
Chemical concentrations detected above 20xTCLP (200xTCLP for lead) are presented with underlines
Chemical concentrations detected above Restricted SCOs are presented in dark gray.
Chemical concentrations detected above Class C Sediment Guidance Values are presented in light gray

DRAFT

Table 6-1A

ISMP Post-Mitigation Monitoring Results for Indoor and Outdoor Air
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

DRAFT

				Acetone	Benzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1.2-Dichlorobenzene	1,3-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Ethyl Ketone	4-Methyl-2-pentanone
				ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDOH VI MATRIX GUIDELINES										1							10							1	1										
Sample Location	Sample Name	Sample Date	Lab Report																																
Cafeteria	EHS-122619-IA-CAF-OCC	12/27/2019	1912741	8.4	1.1	< 1 U	< 1.6 U	< 3.1 U	< 2.5 U	0.5	< 0.73 U	< 1.3 U	< 0.21 U	0.23	< 1.6 U	< 0.54 U	< 1.1 U	< 0.24 U	2.9	< 0.95 U	< 0.95 U	< 0.13 U	< 0.13 U	< 0.063 U	< 0.12 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	1.2	< 1.2 U	< 3.2 U	0.88	< 2.3 U	< 0.65 U
Cafeteria	EHS-122920-IA-CAF	1/5/2021	2101097	17	0.69	< 2.4 U	< 3.8 U	< 7.1 U	< 5.7 U	< 0.46 U	< 1.7 U	< 3.1 U	< 0.48 U	< 0.36 U	< 3.8 U	< 6.3 U	< 2.5 U	< 0.56 U	4.5	< 2.2 U	< 2.2 U	< 0.3 U	< 0.3 U	< 0.14 U	< 0.29 U	< 1.4 U	< 1.7 U	< 1.6 U	< 1.6 U	< 0.32 U	< 2.8 U	< 7.5 U	< 1.8 U	< 5.4 U	< 1.5 U
Cafeteria	EHS-040521-IA-CAF (6L0665)	4/12/2021	2104300	10	0.42	< 0.79 U	< 1.2 U	< 2.3 U	< 1.8 U	0.48	< 0.54 U	< 1.0 U	< 0.16 U	0.36	< 1.2 U	< 2.0 U	< 0.82 U	< 0.18 U	3.4	< 0.71 U	< 0.71 U	< 0.096 U	< 0.096 U	< 0.047 U	< 0.094 U	< 0.47 U	< 0.54 U	< 0.54 U	< 0.54 U	0.65	< 0.90 U	< 2.4 U	< 0.58 U	< 1.7 U	< 0.48 U
Cafeteria	EHS-122221-IA-CAF	12/22/2021	2112771R2	23	0.65	< 2.3 U	< 3.5 U	< 6.6 UJ	< 5.3 U	< 0.43 U	< 1.6 U	< 2.9 U	< 0.45 U	1.2	< 3.5 U	< 5.9 U	< 2.4 U	< 0.52 U	2.7	< 2.0 U	< 2.0 U	< 0.28 U	< 0.28 U	< 0.14 U	< 0.27 U	< 1.4 U	< 1.6 U	< 1.5 U	< 1.5 U	0.47	< 2.6 U	< 7.0 U	< 1.7 U	< 5.0 U	< 1.4 U
Cafeteria	EHS-01022023-IA-CAFE	1/2/2023	2301092	16	0.52	< 0.94 U	< 1.4 U	< 27 U	< 2.2 U	0.40	< 0.64 U	< 1.2 U	< 0.18 U	0.15	< 1.4 U	< 2.4 U	< 0.97 U	< 0.22 U	2.4	< 0.84 U	< 0.84 U	< 0.11 U	< 0.11 U	< 0.056 U	< 0.11 U	< 0.56 U	< 0.65 U	< 0.64 U	< 0.64 U	0.30	< 1.1 U	< 2.9 U	< 0.69 U	< 2.1 U	< 0.57 U
Cafeteria	EHS-11102023-IA-CAFE	11/10/2023	L2367407	4.63	0.409	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.528	< 0.461 U	< 0.17 U	< 0.264 U	0.22	0.944	< 0.688 U	< 1.74 U	< 0.154 U	2.07	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.243	0.506	< 0.82 U	--	< 1.47 U	< 2.05 U
Cafeteria	EHS-11112024-IA-CAFE	11/11/2024	L2466343	10.3	0.403	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.428	< 0.461 U	< 0.17 U	< 0.264 U	0.259	0.909	< 0.688 U	< 1.74 U	< 0.154 U	2.94	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	0.097	< 0.091 U	< 0.091 U	0.456	0.437	< 0.82 U	--	< 1.47 U	< 2.05 U
Cafeteria	EHS-11112025-IA-CAFE	11/11/2025	L2573502	< 2.38 U	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.484	< 0.461 U	< 0.17 U	< 0.264 U	0.103	1.21	< 0.688 U	< 1.74 U	< 0.154 U	2.32	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	0.1	0.422	< 0.82 U	--	< 1.47 U	< 2.05 U
F-Wing Rooftop	EHS-1226-19-OA-F-OCC	12/27/2019	1912741	4.7	0.81	< 1 U	< 1.6 U	< 3.1 U	< 2.5 U	0.47	< 0.73 U	< 1.3 U	< 0.21 U	< 0.15 U	< 1.6 U	< 0.54 U	< 1.1 U	< 0.24 U	2.6	< 0.95 U	< 0.95 U	< 0.13 U	< 0.13 U	< 0.063 U	< 0.12 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	< 0.14 U	< 1.2 U	< 3.2 U	< 0.78 U	< 2.3 U	< 0.65 U
F-Wing Rooftop	EHS-122920-OA-F	1/5/2021	2101097	10	0.64	< 2.6 U	< 4 U	< 7.4 U	< 6 U	0.5	< 1.8 U	< 3.3 U	< 0.5 U	< 0.37 U	< 4 U	< 6.6 U	< 2.7 U	< 0.59 U	3	< 2.3 U	< 2.3 U	< 0.31 U	< 0.31 U	< 0.15 U	< 0.3 U	< 1.5 U	< 1.8 U	< 1.7 U	< 1.7 U	< 0.33 U	< 2.9 U	< 7.8 U	< 1.9 U	< 5.6 U	< 1.6 U
F-Wing Rooftop	EHS-040521-OA-F (6L2686)	4/12/2021	2104300	12	0.33	< 0.92 U	< 1.4 U	< 2.7 U	< 2.1 U	0.46	< 0.63 U	< 1.2 U	< 0.18 U	< 0.13 U	< 1.4 U	< 2.4 U	1.3	< 0.21 U	2.8	< 0.82 U	< 0.82 U	< 0.11 U	< 0.11 U	< 0.054 U	< 0.11 U	< 0.54 U	< 0.63 U	< 0.62 U	< 0.62 U	< 0.12 U	< 1.0 U	< 2.8 U	< 0.67 U	< 2.0 U	< 0.56 U
F-Wing Rooftop	EHS-072221-OA-F	7/29/2021	2107676	20	< 0.55 U	< 2.3 U	< 3.6 U	< 6.7 U	< 5.4 U	0.44	< 1.6 U	< 2.9 U	< 0.46 U	< 0.34 U	< 3.6 U	< 6.0 U	< 2.4 U	< 0.53 U	2.5	< 2.1 U	< 2.1 U	< 0.28 U	< 0.28 U	< 0.14 U	< 0.27 U	< 1.4 U	< 1.6 U	< 1.6 U	< 1.6 U	< 0.30 U	< 2.6 U	< 7.1 U	< 1.7 U	< 5.1 U	< 1.4 U
F-Wing Rooftop	EHS-122221-OA-F	12/22/2021	2112771R2	17	< 0.47 U	< 2.0 U	< 3.1 U	< 5.7 UJ	< 4.6 U	< 0.37 U	< 1.4 U	< 2.5 U	< 0.39 U	< 0.29 U	< 3.0 U	< 5.1 U	2.3	< 0.45 U	2.4	< 1.8 U	< 1.8 U	< 0.24 U	< 0.24 U	< 0.12 U	< 0.23 U	< 1.2 U	< 1.4 U	< 1.3 U	< 1.3 U	< 0.26 U	< 2.3 U	< 6.1 U	< 1.4 U	< 4.4 U	< 1.2 U
F-Wing Rooftop	EHS-01022023-OA-FWING-RF	1/2/2023	2301092	6.4	0.38	< 0.87 U	< 1.3 U	< 25 U	< 2.0 U	0.42	< 0.60 U	< 1.1 U	< 0.17 U	< 0.13 U	< 1.3 U	< 2.2 U	< 0.90 U	< 0.20 U	2.1	< 0.78 U	< 0.78 U	< 0.10 U	< 0.10 U	< 0.052 U	< 0.10 U	< 0.52 U	< 0.60 U	< 0.59 U	< 0.59 U	< 0.11 U	< 1.0 U	< 2.7 U	< 0.64 U	< 1.9 U	< 0.53 U
F-Wing Rooftop	EHS-11102023-OA-FWING-RF	11/10/2023	L2367407	4.04	0.431	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.516	< 0.461 U	< 0.17 U	< 0.264 U	< 0.098 U	0.931	< 0.688 U	< 1.74 U	< 0.154 U	1.8	< 0.12 U	< 0.12 U	< 0.081 U	0.081	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.126	0.475	< 0.82 U	--	< 1.47 U	< 2.05 U
F-Wing Rooftop	EHS-11112024-OA-FWING-RF	11/11/2024	L2466343	5.15	0.387	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.428	< 0.461 U	< 0.17 U	< 0.264 U	< 0.098 U	0.814	< 0.688 U	< 1.74 U	< 0.154 U	2.02	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.174	0.437	< 0.82 U	--	< 1.47 U	< 2.05 U
F-Wing Rooftop	EHS-11112025-OA-FWING-RF	11/11/2025	L2573502	2.38	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.535	< 0.461 U	< 0.17 U	< 0.264 U	< 0.098 U	1.18	< 0.688 U	< 1.74 U	< 0.154 U	2.34	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.452	< 0.82 U	--	< 1.47 U	< 2.05 U
Gymnasium	EHS-1226-19-IA-GYM-OCC	12/27/2019	1912741	15	0.9	1.9	< 1.7 U	< 3.3 U	< 2.6 U	0.55	< 0.77 U	< 1.4 U	< 0.22 U	14	< 1.7 U	< 0.58 U	< 1.2 U	< 0.26 U	4.4	< 1 U	< 1 U	< 0.14 U	< 0.14 U	< 0.067 U	< 0.13 U	< 0.67 U	< 0.78 U	< 0.76 U	< 0.76 U	2.4	< 1.3 U	< 3.4 U	< 0.82 U	2.6	< 0.69 U
Gymnasium	EHS-122920-IA-GYM	1/5/2021	2101097	18	< 0.64 U	< 2.7 U	< 4.2 U	< 7.8 U	< 6.2 U	< 0.5 U	< 1.8 U	< 3.4 U	< 0.53 U	1.8	< 4.2 U	< 6.9 U	< 2.8 U	< 0.62 U	3.5	< 2.4 U	< 2.4 U	< 0.32 U	< 0.32 U	< 0.16 U	< 0.32 U	< 1.6 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.35 U	< 3.1 U	< 8.2 U	< 2 U	< 5.9 U	< 1.6 U
Gymnasium	EHS-122221-IA-GYM (6L0297)	12/22/2021	2112771R2	30	0.48	< 0.88 U	< 1.4 U	< 2.5 UJ	< 2.0 U	0.41	< 0.60 U	< 1.1 U	< 0.17 U	19	< 1.4 U	< 2.2 U	< 0.91 U	< 0.20 U	4.0	< 0.79 U	< 0.79 U	< 0.11 U	< 0.11 U	< 0.052 U	< 0.10 U	< 0.52 U	< 0.60 U	< 0.59 U	< 0.59 U	0.12	< 1.0 U	< 2.7 U	< 0.64 U	< 1.9 U	< 0.54 U
Gymnasium	EHS-122221-IA-GYM (6L2114)	12/22/2021	2112771R2	37	0.47	< 0.90 U	< 1.4 U	< 2.6 UJ	< 2.1 U	0.39	< 0.62 U	< 1.1 U	< 0.18 U	19	< 1.4 U	< 2.3 U	< 0.93 U	< 0.20 U	3.9	< 0.80 U	< 0.80 U	< 0.11 U	< 0.11 U	< 0.053 U	< 0.11 U	< 0.53 U	< 0.62 U	< 0.61 U	< 0.61 U	< 0.12 U	< 1.0 U	< 2.7 U	< 0.66 U	< 2.0 U	< 0.55 U
Gymnasium	EHS-01022023-IA-GYM	1/2/2023	2301092	20	0.50	1.0 J	< 1.7 U	< 32 U	< 2.6 U	0.48	< 0.76 U	< 1.4 U	< 0.22 U	33	< 1.7 U	< 2.8 U	< 1.1 U	< 0.25 U	4.5	< 0.99 U	< 0.99 U	< 0.13 U	< 0.13 U	< 0.065 U	< 0.13 U	< 0.65 U	< 0.76 U	< 0.74 U	< 0.74 U	0.19	< 1.2 U	< 3.4 U	< 0.81 U	< 2.4 U	< 0.67 U
Gymnasium	EHS-11102023-IA-GYM	11/10/2023	L2367407	5.91	0.412	0.382	< 0.207 U	< 0.078 U	< 0.623 U	0.516	< 0.461 U	< 0.17 U	< 0.264 U	8.06	1.02	< 0.688 U	< 1.74 U	< 0.154 U	3.08	< 0.12 U	< 0.12 U	< 0.081 U	0.085 J	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.126	0.506	< 0.82 U	--	< 1.47 U	< 2.05 U
Gymnasium	EHS-11112024-IA-GYM	11/11/2024	L2466343	9.74	0.367	1.03	< 0.207 U	< 0.078 U	< 0.623 U	0.447	< 0.461 U	< 0.17 U	< 0.264 U	16.9	0.983	< 0.688 U	< 1.74 U	< 0.154 U	4.58	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.087	0.491	< 0.82 U	--	2.03	< 2.05 U
Gymnasium	EHS-11112025-IA-GYM	11/11/2025	L2573502	3.61	< 0.319 U	0.228	< 0.207 U	< 0.078 U	< 0.623 U	0.535	< 0.461 U	< 0.17 U	< 0.264 U	3.86	1.16	< 0.688 U	< 1.74 U	< 0.154 U	3.3	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.414	< 0.82 U	--	< 1.47 U	< 2.05 U
K-Wing Corridor	EHS-1226-19-IA-KWING-OCC	12/27/2019	1912741	8.2	0.89	< 1.1 U	< 1.8 U	< 3.3 U	< 2.7 U	0.49	< 0.79 U	< 1.4 U	< 0.22 U	< 0.17 U	< 1.8 U	< 0.59 U	< 1.2 U	< 0.26 U	2.8	< 1 U	< 1 U	< 0.14 U	0.14	< 0.068 U	< 0.14 U	< 0.68 U	< 0.79 U	< 0.78 U	< 0.78 U	0.15	< 1.3 U	< 3.5 U	< 0.84 U	< 2.5 U	< 0.7 U
K-Wing Corridor	EHS-122920-IA-KWING	1/5/2021	2101097	21	< 0.68 U	< 2.8 U	< 4.4 U	< 8.2 U	< 6.6 U	< 0.53 U	< 1.9 U	< 3.6 U	< 0.56 U	< 0.41 U	< 4.4 U	< 7.3 U	< 2.9 U	< 0.65 U	3.5	< 2.5 U	< 2.5 U	< 0.34 U	< 0.34 U	< 0.17 U	< 0.34 U	< 1.7 U	< 2 U	< 1.9 U	< 1.9 U	< 0.37 U	< 3.2 U	< 8.7 U	< 2.1 U	< 6.2 U	< 1.7 U
K-Wing Corridor	EHS-040521-IA-K-WING (6L2021)	4/12/2021	2104300	22	< 0.74 U	< 3.1 U	< 4.8 U	< 9.0 U	< 7.2 U	< 0.58 U	< 2.1 U	< 4.0 U	< 0.61 U	0.62	< 4.8 U	< 8.0 U	< 3.2 U	< 0.71 U	4.3	< 2.8 U	< 2.8 U	< 0.38 U	< 0.38 U	< 0.18 U	< 0.37 U	< 1.8 U	< 2.1 U	< 2.1 U	< 2.1 U	< 0.40 U	< 3.6 U	< 9.5 U	< 2.3 U	< 6.8 U	< 1.9 U
K-Wing Corridor	EHS-122221-IA-KWING	12/22/2021	2112771R2	31	< 0.54 U	< 2.3 U	< 3.5 U	< 6.6 UJ	< 5.3 U	1.5 J+	< 1.6 U	< 2.9 U	< 0.45 U	0.85	< 3.5 U	< 5.9 U	< 2.4 U	< 0.52 U	2.2	< 2.0 U	< 2.0 U	< 0.28 U	< 0.28 U	< 0.14 U	< 0.27 U	< 1.4 U	< 1.6 U	< 1.5 U	< 1.5 U	< 0.30 U	< 2.6 U	< 7.0 U	< 1.7 U	< 5.0 U	< 1.4 U
K-Wing Corridor	EHS-01022023-IA-KWING	1/2/2023	2301092	13	0.56	< 0.92 U	< 1.4 U	< 27 U	< 2.1 U	0.42	< 0.64 U	< 1.2 U	< 0.18 U	0.22	< 1.4 U	< 2.4 U	< 0.96 U	< 0.21 U	2.2	< 0.83 U	< 0.83 U	< 0.11 U	0.20	< 0.055 U	< 0.11 U	< 0.55 U	< 0.64 U	< 0.63 U	< 0.63 U	0.22	< 1.0 U	< 2.8 U	< 0.68 U	< 2.0 U	1.0
K-Wing Corridor	EHS-11102023-IA-KWING	11/10/2023	L2367407	6.77	0.406	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.522	< 0.461 U	< 0.17 U	< 0.264 U	1.35	0.989	< 0.688 U	2.44	< 0.154 U	2.25	< 0.12 U	< 0.12 U	< 0.081 U	0.093	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.143	0.514	< 0.82 U	--	< 1.47 U	< 2.05 U
K-Wing Corridor	EHS-11112024-IA-KWING	11/11/2024	L2466343	10.6	0.431	0.154	< 0.207 U	< 0.078 U	< 0.623 U	0.434	< 0.461 U	< 0.17 U	< 0.264 U	2.24	1.02	< 0.688 U	< 1.74 U	< 0.154 U	3.53	< 0.12 U	< 0.12 U	< 0.081 U	0.089	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.13	0.475	< 0.82 U	--	< 1.47 U	< 2.05 U
K-Wing Corridor	EHS-11112025-IA-KWING	11/11/2025	L2573502	3.85	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.447	< 0.461 U	< 0.17 U	< 0.264 U	0.703	1.29	< 0.688 U	< 1.74 U	< 0.154 U	2.61	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.46	< 0.82 U	--	< 1.47 U	< 2.05 U
K-Wing Rooftop	EHS-1226-19-OA-M-OCC	12/27/2019	1912741	5	0.88	< 1.1 U	< 1.7 U	< 3.2 U	< 2.6 U	0.48	< 0.76 U	< 1.4 U	< 0.22 U	0.16	< 1.7 U	< 0.56 U	< 1.1 U	< 0.25 U	2.7	< 0.99 U	< 0.99 U	< 0.13 U	< 0.13 U	< 0.065 U	< 0.13 U	< 0.65 U	< 0.76 U	< 0.74 U	< 0.74 U	0.31	< 1.2 U	< 3.4 U	< 0.81 U	< 2.4 U	< 0.67 U
K-Wing Rooftop	EHS-072221-OA-K	7/29/2021	2107676	24	< 0.58 U	< 2.4 U	< 3.7 U	< 7.0 U	< 5.6 U	0.45 J	< 1.7 U	< 3.1 U	< 0.48 U	< 0.35 U	< 3.7 U	< 6.2 U	< 2.5 U	< 0.55 U	2.3	< 2.2 U	< 2.2 U	< 0.29 U	< 0.29 U	< 0.14 U	< 0.29 U	< 1.4 U	< 1.7 U	< 1.6 U	< 1.6 U	< 0.31 U	< 2.8 U	< 7.4 U	< 1.8 U	< 5.3 U	< 1.5 U
K-Wing Rooftop	EHS-122221-OA-K	12/22/2021	2112771R2	13	< 0.47 U	< 2.0 U	< 3.1 U	< 5.7 UJ	< 4.6 U	5.9 J+	< 1.4 U	< 2.5 U	< 0.39 U	< 0.29 U	< 3.0 U	< 5.1 U	2.1	< 0.45 U	2.4	< 1.8 U	< 1.8 U	< 0.24 U	< 0.24 U	< 0.12 U	< 0.23 U	< 1.2 U	< 1.4 U	< 1.3 U	< 1.3 U	< 0.26 U	< 2.3 U	< 6.1 U	< 1.4 U	< 4.4 U	< 1.2 U
K-Wing Rooftop	EHS-01022023-OA-KWING-RF	1/2/2023	2301092	< 6.3 U	0.36	< 0.88 U	< 1.4 U	< 26 U	< 2.0 U	0.42	< 0.61 U	< 1.1 U	< 0.17 U	< 0.13 U	< 1.4 U	< 2.3 U	< 0.92 U	< 0.20 U	2.0	< 0.79 U	< 0.79 U	< 0.11 U	< 0.11 U	< 0.052 U	< 0.10 U	< 0.52 U	< 0.61 U	< 0.60 U	< 0.60 U	< 0.11 U	< 1.0 U	< 2.7 U	< 0.65 U	< 1.9 U	< 0.54 U
K-Wing Rooftop	EHS-11102023-OA-KWING-RF	11/10/2023	L2367407	3.33	0.39	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.503	< 0.461 U	< 0.17 U	< 0.264 U	< 0.098 U	0.919	< 0.688 U	2.19	< 0.154 U	1.79	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	< 0.087 U	0.72	< 0.82 U	--	< 1.47 U	< 2.05 U
K-Wing Rooftop	EHS-11112024-OA-KWING-RF	11/11/2024	L2466343	4.3	0.38	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.421	< 0.461 U	< 0.17 U	< 0.264 U	< 0.098 U	0.807	< 0.688 U	< 1.74 U	< 0.154 U	1.97	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.1	0.537	< 0.82 U	--	< 1.47 U	< 2.05 U
K-Wing Rooftop	EHS-11112025-OA-KWING	11/11/2025	L2573502	< 2.38 U	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.503	< 0.461 U	< 0.17 U	< 0.264 U	0.103	1.15	< 0.688 U	< 1.74 U	< 0.154 U	2.2	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.613	< 0.82 U	--	< 1.47 U	< 2.05 U
Music Room 148	EHS-122619-IA-148-OCC	12/27/2019	1912741	24	1	< 1.1 U	< 1.8 U	< 3.3 U	< 2.7 U	0.49	< 0.79 U	< 1.4 U	< 0.22 U	2.6	< 1.8 U	< 0.59 U	< 1.2 U	< 0.26 U	21	< 1 U	< 1 U	< 0.14 U	< 0.14 U	< 0.068 U	< 0.14 U	< 0.68 U	< 0.79 U	< 0.78 U	< 0.78 U	0.82	< 1.3 U	< 3.5 U	< 0.84 U	< 2.5 U	< 0.7 U
Music Room 148	EHS-122619-IA-148-OCC DUP	12/27/2019	1912741	23	1	< 1.2 U	< 1.9 U	< 3.6 U	< 2.8 U	0.48	< 0.84 U	< 1.6 U	< 0.24 U	2.6	< 1.9 U	< 0.63 U	< 1.3 U	< 0.28 U	22	< 1.1 U	< 1.1 U	< 0.15 U	< 0.15 U	< 0.072 U	< 0.14 U	< 0.72 U	< 0.84 U	< 0.83 U	< 0.83 U	0.82	< 1.4 U	< 3.7 U	< 0.9 U	< 2.7 U	< 0.75 U
Room 127	EHS-122619-IA-127-OCC	12/27/2019	1912741	14	1.1	< 1 U	< 1.6 U	< 3.1 U	< 2.5 U	0.49	< 0.73 U	< 1.3 U	< 0.21 U	1.4	< 1.6 U	< 0.54 U	< 1.1 U	< 0.24 U	19	< 0.95 U	< 0.95 U	< 0.13 U	1.2	< 0.063 U	< 0.12 U	< 0.63 U	< 0.73 U	< 0.72 U	< 0.72 U	0.42	< 1.2 U	< 3.2 U	< 0.78 U	< 2.3 U	< 0.65 U
Room 127	EHS-122920-IA-127	1/5/2021	2101097	34	0.5	< 1.1 U	< 1.8 U	< 3.3 U	< 2.7 U	0.4	< 0.79 U	< 1.4 U	< 0.22 U	< 0.17 U	< 1.8 U	< 2.9 U	< 1.2 U	< 0.26 U	10	< 1 U	< 1 U	< 0.14 U	0.6	< 0.068 U	< 0.14 U	< 0.68 U	< 0.79 U	< 0.78 U	< 0.78 U	< 0.15 U	< 1.3 U	< 3.5 U	< 0.84 U	< 2.5 U	< 0.7 U
Room 127	EHS-040521-IA-127 (6L2173)	4/12/2021	2104300	66	0.40	< 0.95 U	< 1.5 U	< 2.8 U	< 2.2 U	0.47	< 0.65 U	< 1.2 U	< 0.19 U	< 0.14 U	< 1.5 U	< 2.4 U	< 0.99 U	< 0.22 U	29	< 0.85 U	< 0.85 U	< 0.11 U	1.1	< 0.056 U	< 0.11 U	< 0.56 U	< 0.66 U	< 0.64 U	< 0.64 U	0.19	< 1.1 U	< 2.9 U	< 0.70 U	< 2.1 U	< 0.58 U
Room 127	EHS-072221-IA-127	7/29/2021	2107676	58	< 0.56 U	< 2.4 U	< 3.6 U	< 6.8 U	< 5.5 U	0.44	< 1.6 U	< 3.0 U	< 0.46 U	< 0.34 U	< 3.6 U	< 6.0 U	< 2.4 U	< 0.54 U	21	< 2.1 U	< 2.1 U	< 0.28 U	0.76	< 0.14 U	< 0.28 U	< 1.4 U	< 1.6 U	< 1.6 U	< 1.6 U	0.57	< 2.7 U	< 7.2 U	< 1.7 U	< 5.2 U	< 1.4 U
Room 127	EHS-122221-IA-127	12/22/2021	2112771R2	38	< 0.52 U	< 2.2 U	< 3.4 U	< 6.3 UJ	< 5.1 U	< 0.41 U	< 1.5 U	< 2.8 U	< 0.43 U	< 0.32 U	< 3.4 U	< 5.6 U	< 2.2 U	< 0.50 U	9.3	< 2.0 U	< 2.0 U	< 0.26 U	0.38	< 0.13 U	< 0.26 U	< 1.3 U	< 1.5 U	< 1.5 U	< 1.5 U	< 0.28 U	< 2.5 U	< 6.6 U	< 1.6 U	< 4.8 U	< 1.3 U
Room 127	EHS-01022023-IA-127	1/2/2023	2301092	20	0.60	< 0.94 U	< 1.4 U	< 27 U	< 2.2 U	0.41	< 0.64 U	< 1.2 U	< 0.18 U	< 0.14 U	< 1.4 U	< 2.4 U	< 0.97 U	< 0.22 U	14	< 0.84 U	< 0.84 U	< 0.11 U	0.27	< 0.056 U	< 0.11 U	< 0.56 U	< 0.65 U	< 0.64 U	< 0.64 U	0.17	< 1.1 U	< 2.9 U	< 0.69 U	< 2.1 U	< 0.57 U
Room 127	EHS-11102023-IA-127	11/10/2023	L2367407	6.82	0.444	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.522	< 0.461 U	< 0.17 U	< 0.264 U	0.103	0.915	< 0.688 U	< 1.74 U	< 0.154 U	3.43	< 0.12 U	< 0.12 U	< 0.081 U	0.117	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.139	0.475	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 127	EHS-11112024-IA-127	11/11/2024	L2466343	230	0.419	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.421	< 0.461 U	< 0.17 U	< 0.264 U	0.21	0.981	< 0.688 U	< 1.74 U	< 0.154 U	9.05	< 0.12 U	< 0.12 U	< 0.081 U	0.32	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.165	0.445	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 127	EHS-11112025-IA-127	11/11/2025	L2573502	7.98	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.554	< 0.461 U	< 0.17 U	< 0.264 U	0.2	1.13	0.909	< 1.74 U	< 0.154 U	4.35	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.414	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 148	EHS-122920-IA-148	1/5/2021	2101097	21	< 0.71 U	< 3 U	< 4.6 U	< 8.7 U	< 7 U	0.69 J	< 2 U	< 3.8 U	< 0.59 U	< 0.44 U	< 4.6 U	< 7.7 U	< 3.1 U	< 0.69 U	2.3	< 2.7 U	< 2.7 U	< 0.36 U	< 0.36 U	< 0.18 U	< 0.35 U	< 1.8 U	< 2.1 U	< 2 U	< 2 U	< 0.39 U	< 3.4 U	< 9.2 U	< 2.2 U	< 6.6 U	< 1.8 U
Room 148	EHS-122920-IA-148DUP	1/5/2021	2101097	16	< 0.62 U	< 2.6 U	< 4 U	< 7.6 U	< 6.1 U	< 0.49 UJ	< 1.8 U	< 3.3 U	< 0.52 U	< 0.38 U	< 4 U	< 6.7 U	< 2.7 U	< 0.6 U	2.1	< 2.4 U	< 2.4 U	< 0.32 U	< 0.32 U	< 0.16 U	< 0.31 U	< 1.6 U	< 1.8 U	< 1.8 U	< 1.8 U	< 0.34 U	< 3 U	< 8 U	< 1.9 U	< 5.8 U	< 1.6 U
Room 148	EHS-040521-IA-148 (6L1850)	4/12/2021	2104300	20	0.37	< 1.0 U	< 1.6 U	< 3.0 U	< 2.4 U	0.47	< 0.70 U	< 1.3 U	< 0.20 U	0.38	< 1.6 U	< 2.6 U	< 1.0 U	< 0.23 U	16	< 0.91 U	< 0.91 U	< 0.12 U	< 0.12 U	< 0.060 U	< 0.12 U	< 0.60 U	< 0.70 U	< 0.69 U	< 0.69 U	0.13	< 1.2 U	< 3.1 U	< 0.75 U	< 2.2 U	< 0.62 U
Room 148	EHS-040521-IA-148DUP (6L1167)	4/12/2021	2104300	22	0.38	< 0.96 U	< 1.5 U	< 2.8 U	< 2.2 U	0.47	< 0.66 U	< 1.2 U	< 0.19 U	0.37	< 1.5 U	< 2.5 U	< 1.0 U	< 0.22 U	16	< 0.86 U	< 0.86 U	< 0.12 U	< 0.12 U	< 0.057 U	< 0.11 U	< 0.57 U	< 0.66 U	< 0.65 U	< 0.65 U	0.13	< 1.1 U	< 2.9 U	< 0.71 U	< 2.1 U	< 0.59 U
Room 148	EHS-072221-IA-148	7/29/2021	2107676	48	< 0.59 U	< 2.5 U	< 3.8 U	< 7.2 U	< 5.7 U	0.45 J	< 1.7 U	< 3.1 U	< 0.49 U	0.38	< 3.8 U	< 6.4 U	< 2.6 U	< 0.57 U	14	< 2.2 U	< 2.2 U	< 0.30 U	< 0.30 U	< 0.15 U	< 0.29 U	< 1.5 U	< 1.7 U	< 1.7 U	< 1.7 U	< 0.32 UJ	< 2.8 U	< 7.6 U	< 1.8 U	< 5.4 U	< 1.5 U
Room 148	EHS-072221-IA-148 DUP	7/29/2021	2107676	48	< 0.56 U	< 2.4 U	< 3.6 U	< 6.8 U	< 5.5 U	0.44 J	< 1.6 U	< 3.0 U	< 0.46 U	0.37	< 3.6 U	< 6.1 U	< 2.4 U	< 0.54 U	15	< 2.1 U	< 2.1 U	< 0.28 U	< 0.28 U	< 0.14 U	< 0.28 U	< 1.4 U	< 1.6 U	< 1.6 U	< 1.6 U	0.38 J	< 2.7 U	< 7.2 U	< 1.7 U	< 5.2 U	< 1.4 U
Room 148	EHS-122221-IA-148	12/22/2021	2112771R2	12 J	0.40 J	< 0.79 U	< 1.2 U	< 2.3 UJ	< 1.8 U	0.36 J	< 0.54 U	< 1.0 U	< 0.16 U	0.25 J	< 1.2 U	< 2.0 U	< 0.82 U	< 0.18 U	10	< 0.71 U	< 0.71 U	< 0.096 U	< 0.096 U	< 0.047 U	< 0.094 U	< 0.47 U	< 0.54 U	< 0.54 U	< 0.54 U	< 0.10 U	< 0.90 U	< 2.4 U	< 0.58 U	< 1.7 U	< 0.48 U
Room 148	EHS-122221-IA-148DUP	12/22/2021	2112771R2	26 J	< 0.52 UJ	< 2.2 U	< 3.4 U	< 6.3 UJ	< 5.1 U	< 0.41 UJ	< 1.5 U	< 2.8 U	< 0.43 U	0.38 J	< 3.4 U	< 5.6 U	< 2.2 U	< 0.50 U	11	< 2.0 U	< 2.0 U	< 0.26 U	< 0.26 U	< 0.13 U	< 0.26 U	< 1.3 U	< 1.5 U	< 1.5 U	< 1.5 U	< 0.28 U	< 2.5 U	< 6.6 U	< 1.6 U	< 4.8 U	< 1.3 U
Room 148	EHS-01022023-IA-DUP	1/2/2023	2301092	17	0.55	< 0.90 U	< 1.4 U	< 26 U	< 2.1 U	0.43	< 0.62 U	< 1.1 U	< 0.18 U	0.96	< 1.4 U	< 2.3 U	< 0.93 U	< 0.20 U	15	< 0.80 U	< 0.80 U	< 0.11 U	< 0.11 U	< 0.053 U	< 0.11 U	< 0.53 U	< 0.62 U	< 0.61 U	< 0.61 U	0.19	< 1.0 U	< 2.7 U	< 0.66 U	< 2.0 U	< 0.55 U
Room 148	EHS-01022023-IA-148	1/2/2023	2301092	12	0.56	< 0.92 U	< 1.4 U	< 27 U	< 2.1 U	0.43	< 0.63 U	< 1.2 U	< 0.18 U	0.96	< 1.4 U	< 2.4 U	< 0.95 U	< 0.21 U	15	< 0.82 U	< 0.82 U	< 0.11 U	< 0.11 U	< 0.054 U	< 0.11 U	< 0.54 U	< 0.63 U	< 0.62 U	< 0.62 U	0.18	< 1.0 U	< 2.8 U	< 0.67 U	< 2.0 U	< 0.56 U
Room 148	EHS-11102023-IA-148	11/10/2023	L2367407	6.34	0.422	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.547	< 0.461 U	< 0.17 U	< 0.264 U	1.1	0.948	< 0.688 U	< 1.74 U	< 0.154 U	2.55	< 0.12 U	< 0.12 U	< 0.081 U	0.089 J	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.117	0.483	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 148	EHS-11102023-IA-DUP	11/10/2023	L2367407	6.18	0.399	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.503	< 0.461 U	< 0.17 U	< 0.264 U	1.03	0.919	< 0.688 U	< 1.74 U	< 0.154 U	2.52	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 UJ	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.117	0.498	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 148	EHS-11112024-IA-148	11/11/2024	L2466343	9.15	0.387	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.428	< 0.461 U	< 0.17 U	< 0.264 U	0.62	0.878	< 0.688 U	< 1.74 U	< 0.154 U	4.78	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.109	0.46	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 148	EHS-11112024-IA-DUP	11/11/2024	L2466343	10.5	0.374	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.421	< 0.461 U	< 0.17 U	< 0.264 U	0.606	0.834	< 0.688 U	< 1.74 U	< 0.154 U	4.47	< 0.12 U	< 0.12 U	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 U	< 0.091 U	0.109	0.452	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 148	EHS-11112025-IA-148	11/11/2025	L2573502	4.23	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.547	< 0.461 U	< 0.17 U	< 0.264 U	0.689	1.2	< 0.688 U	< 1.74 U	< 0.154 U	3.49	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.445	< 0.82 U	--	< 1.47 U	< 2.05 U
Room 148	EHS-11112025-IA-DUP	11/11/2025	L2573502	4.58	< 0.319 U	< 0.134 U	< 0.207 U	< 0.078 U	< 0.623 U	0.554	< 0.461 U	< 0.17 U	< 0.264 U	0.742	1.18	< 0.688 U	< 1.74 U	< 0.154 U	3.66	< 0.12 U	< 0.12 UJ	< 0.081 U	< 0.081 U	< 0.079 U	< 0.079 U	< 0.079 U	< 0.092 U	< 0.091 UJ	< 0.091 UJ	< 0.087 U	0.429	< 0.82 U	--	< 1.47 U	< 2.05 U

Notes

µg/m3: microgram per cubic meter

Samples were analyzed via method TO-15

U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.

J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

UJ: The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

Analyte concentrations detected above NYSDOH VI Matrix Guidelines are presented in light gray.

Table 6-1A
ISMP Post-Mitigation Monitoring Results for Indoor and Outdoor Air
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

				Methyl-tert-butyl ether	Styrene	Tertiary butyl alcohol (TBA)	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	1,2,4-Trimethylbenzene	1,3,5-Trimethylbenzene	Vinyl chloride	Xylene (m)	Xylene (o)	1,4-Dichlorobenzene
				ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
NYSDOH VI MATRIX GUIDELINES								10			10		1		10	10	0.2			
Sample Location	Sample Name	Sample Date	Lab Report																	
Cafeteria	EHS-122619-IA-CAF-OCC	12/27/2019	1912741	< 0.57 U	1.3	--	< 0.22 U	0.44	1.4	< 5.9 U	< 0.17 U	< 0.17 U	< 0.17 U	1.3	1.2	< 0.78 U	< 0.04 U	6.4	2.4	< 0.19 U
Cafeteria	EHS-122920-IA-CAF	1/5/2021	2101097	< 1.3 U	< 1.6 U	--	< 0.5 U	< 0.5 U	0.78	< 14 U	< 0.4 U	< 0.4 U	< 0.39 U	< 2 U	< 1.8 U	< 1.8 U	< 0.093 U	1.1	0.4	< 0.44 U
Cafeteria	EHS-040521-IA-CAF (6L0665)	4/12/2021	2104300	< 0.42 U	< 0.50 U	--	< 0.16 U	0.26	1.0	< 4.4 UJ	< 0.13 U	< 0.13 U	< 0.13 U	1.3	0.91	< 0.58 U	< 0.030 U	2.6	0.82	< 0.14 U
Cafeteria	EHS-122221-IA-CAF	12/22/2021	2112771R2	< 1.2 U	< 1.4 U	--	< 0.47 U	< 0.46 U	1.6	< 13 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 1.7 U	< 1.7 U	< 0.087 U	1.9	0.79	< 0.41 U
Cafeteria	EHS-01022023-IA-CAFE	1/2/2023	2301092	< 0.50 U	< 0.60 U	--	< 0.19 U	< 0.19 U	0.67	< 5.2 U	< 0.15 U	< 0.15 U	< 0.15 U	1.1	< 0.69 U	< 0.69 U	< 0.036 U	1.0	0.32	< 0.17 U
Cafeteria	EHS-11102023-IA-CAFE	11/10/2023	L2367407	< 0.721 U	0.243	< 1.52 U	< 0.137 U	< 0.136 U	0.584	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.24	0.29	< 0.098 U	< 0.051 U	0.895	0.295	< 0.12 U
Cafeteria	EHS-11112024-IA-CAFE	11/11/2024	L2466343	< 0.721 U	0.528	< 1.52 U	< 0.137 U	< 0.136 U	0.513	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.938	1.05	< 0.098 U	< 0.051 U	1.62	0.552	< 0.12 U
Cafeteria	EHS-11112025-IA-CAFE	11/11/2025	L2573502	< 0.721 U	0.094 J	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.899	0.147	< 0.098 U	< 0.051 U	0.339	0.113	< 0.12 U
F-Wing Rooftop	EHS-1226-19-OA-F-OCC	12/27/2019	1912741	< 0.57 U	< 0.67 U	--	< 0.22 U	< 0.21 U	1.4	< 5.9 U	< 0.17 U	< 0.17 U	< 0.17 U	1.3	< 0.78 U	< 0.78 U	< 0.04 U	0.3	< 0.14 U	< 0.19 U
F-Wing Rooftop	EHS-122920-OA-F	1/5/2021	2101097	< 1.4 U	< 1.6 U	--	< 0.52 U	< 0.52 U	< 0.72 U	< 14 U	< 0.42 U	< 0.42 U	< 0.41 U	< 2.2 U	< 1.9 U	< 1.9 U	< 0.098 U	< 0.66 U	< 0.33 U	< 0.46 U
F-Wing Rooftop	EHS-040521-OA-F (6L2686)	4/12/2021	2104300	< 0.49 U	< 0.58 U	--	< 0.19 U	< 0.18 U	0.59	< 5.1 UJ	< 0.15 U	< 0.15 U	< 0.15 U	1.2	< 0.67 U	< 0.67 U	< 0.035 U	0.24	< 0.12 U	< 0.16 U
F-Wing Rooftop	EHS-072221-OA-F	7/29/2021	2107676	< 1.2 U	< 1.5 U	--	< 0.48 U	< 0.47 U	0.88	< 13 U	< 0.38 U	< 0.38 U	< 0.37 U	< 1.9 U	< 1.7 U	< 1.7 U	< 0.088 U	< 0.60 U	< 0.30 U	< 0.42 U
F-Wing Rooftop	EHS-122221-OA-F	12/22/2021	2112771R2	< 1.1 U	< 1.3 U	--	< 0.41 U	< 0.40 U	4.2	< 11 U	< 0.32 U	< 0.32 U	< 0.32 U	< 1.7 U	< 1.4 U	< 1.4 U	< 0.076 U	< 0.51 U	< 0.26 U	< 0.36 U
F-Wing Rooftop	EHS-01022023-OA-FWING-RF	1/2/2023	2301092	< 0.47 U	< 0.55 U	--	< 0.18 U	< 0.18 U	0.35	< 4.8 U	< 0.14 U	< 0.14 U	< 0.14 U	0.90	< 0.64 U	< 0.64 U	< 0.033 U	< 0.22 U	< 0.11 U	< 0.16 U
F-Wing Rooftop	EHS-11102023-OA-FWING-RF	11/10/2023	L2367407	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.701	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.18	0.133	< 0.098 U	< 0.051 U	0.391	0.135	< 0.12 U
F-Wing Rooftop	EHS-11112024-OA-FWING-RF	11/11/2024	L2466343	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.916	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.961	0.61	< 0.098 U	< 0.051 U	0.573	0.213	< 0.12 U
F-Wing Rooftop	EHS-11112025-OA-FWING-RF	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.961	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U
Gymnasium	EHS-1226-19-IA-GYM-OCC	12/27/2019	1912741	< 0.6 U	< 0.72 U	--	< 0.23 U	< 0.23 U	1.3	< 6.2 U	< 0.18 U	< 0.18 U	< 0.18 U	1.4	1.7	< 0.82 U	< 0.043 U	7.6	2.1	< 0.2 U
Gymnasium	EHS-122920-IA-GYM	1/5/2021	2101097	< 1.4 U	< 1.7 U	--	< 0.55 U	< 0.54 U	1.4	< 15 U	< 0.44 U	< 0.44 U	< 0.43 U	< 2.2 U	< 2 U	< 2 U	< 0.1 U	< 0.7 U	< 0.35 U	< 0.48 U
Gymnasium	EHS-122221-IA-GYM (6L0297)	12/22/2021	2112771R2	< 0.47 U	< 0.56 U	--	< 0.18 U	< 0.18 U	1.1	< 4.9 U	< 0.14 U	< 0.14 U	< 0.14 U	1.2	< 0.64 U	< 0.64 U	< 0.033 U	0.30	0.12	< 0.16 U
Gymnasium	EHS-122221-IA-GYM (6L2114)	12/22/2021	2112771R2	< 0.48 U	< 0.57 U	--	< 0.18 U	< 0.18 U	0.97	< 5.0 U	< 0.15 U	< 0.15 U	< 0.14 U	1.2	< 0.66 U	< 0.66 U	< 0.034 U	0.26	< 0.12 U	< 0.16 U
Gymnasium	EHS-01022023-IA-GYM	1/2/2023	2301092	< 0.59 U	< 0.70 U	--	< 0.22 U	< 0.22 U	0.81	< 6.1 U	< 0.18 U	< 0.18 U	< 0.18 U	1.1	< 0.81 U	< 0.81 U	< 0.042 U	0.58	0.21	< 0.20 U
Gymnasium	EHS-11102023-IA-GYM	11/10/2023	L2367407	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.614	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.21	0.113	< 0.098 U	< 0.051 U	0.395	0.148	< 0.12 U
Gymnasium	EHS-11112024-IA-GYM	11/11/2024	L2466343	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.543	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.989	0.167	< 0.098 U	< 0.051 U	0.265	0.109	< 0.12 U
Gymnasium	EHS-11112025-IA-GYM	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.888	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U
K-Wing Corridor	EHS-1226-19-IA-KWING-OCC	12/27/2019	1912741	< 0.62 U	< 0.73 U	--	< 0.23 U	0.72	1.1	< 6.3 U	< 0.19 U	< 0.19 U	< 0.18 U	1.3	< 0.84 U	< 0.84 U	< 0.044 U	0.37	0.14 J	< 0.2 U
K-Wing Corridor	EHS-122920-IA-KWING	1/5/2021	2101097	< 1.5 U	< 1.8 U	--	< 0.58 U	< 0.57 U	0.86	< 16 U	< 0.46 U	< 0.46 U	< 0.45 U	< 2.4 U	< 2.1 U	< 2.1 U	< 0.11 U	< 0.73 U	< 0.37 U	< 0.51 U
K-Wing Corridor	EHS-040521-IA-K-WING (6L2021)	4/12/2021	2104300	< 1.7 U	< 2.0 U	--	< 0.64 U	< 0.63 U	1.4	< 17 UJ	< 0.51 U	< 0.51 U	< 0.50 U	< 2.6 U	< 2.3 U	< 2.3 U	< 0.12 U	< 0.80 U	< 0.40 U	< 0.56 U
K-Wing Corridor	EHS-122221-IA-KWING	12/22/2021	2112771R2	< 1.2 U	< 1.4 U	--	< 0.47 U	< 0.46 U	0.66	< 13 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 1.7 U	< 1.7 U	< 0.087 U	< 0.59 U	< 0.30 U	< 0.41 U
K-Wing Corridor	EHS-01022023-IA-KWING	1/2/2023	2301092	< 0.50 U	< 0.59 U	--	< 0.19 U	< 0.19 U	1.5	< 5.1 U	< 0.15 U	< 0.15 U	< 0.15 U	1.2	< 0.68 U	< 0.68 U	< 0.035 U	0.60	0.21	< 0.16 U
K-Wing Corridor	EHS-11102023-IA-KWING	11/10/2023	L2367407	< 0.721 U	0.094	< 1.52 U	< 0.137 U	< 0.136 U	0.95	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.2	0.123	< 0.098 U	< 0.051 U	0.447	0.161	< 0.12 U
K-Wing Corridor	EHS-11112024-IA-KWING	11/11/2024	L2466343	< 0.721 U	0.098	< 1.52 U	< 0.137 U	< 0.136 U	0.833	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.989	0.315	< 0.098 U	< 0.051 U	0.374	0.152	< 0.12 U
K-Wing Corridor	EHS-11112025-IA-KWING	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.933	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U
K-Wing Rooftop	EHS-1226-19-OA-M-OCC	12/27/2019	1912741	< 0.59 U	< 0.7 U	--	< 0.22 U	< 0.22 U	2.1	< 6.1 U	< 0.18 U	< 0.18 U	< 0.18 U	1.4	< 0.81 U	< 0.81 U	< 0.042 U	1.1	0.35	< 0.2 U
K-Wing Rooftop	EHS-072221-OA-K	7/29/2021	2107676	< 1.3 U	< 1.5 U	--	< 0.50 U	< 0.49 U	< 0.68 U	< 13 U	< 0.39 U	< 0.39 U	< 0.39 U	< 2.0 U	< 1.8 U	< 1.8 U	< 0.092 U	< 0.63 U	< 0.31 U	< 0.43 U
K-Wing Rooftop	EHS-122221-OA-K	12/22/2021	2112771R2	< 1.1 U	< 1.3 U	--	< 0.41 U	< 0.40 U	3.3	< 11 U	< 0.32 U	< 0.32 U	< 0.32 U	< 1.7 U	< 1.4 U	< 1.4 U	< 0.076 U	< 0.51 U	< 0.26 U	< 0.36 U
K-Wing Rooftop	EHS-01022023-OA-KWING-RF	1/2/2023	2301092	< 0.48 U	< 0.56 U	--	< 0.18 U	< 0.18 U	0.36	< 4.9 U	< 0.14 U	< 0.14 U	< 0.14 U	1.1	< 0.65 U	< 0.65 U	< 0.034 U	< 0.23 U	< 0.11 U	< 0.16 U
K-Wing Rooftop	EHS-11102023-OA-KWING-RF	11/10/2023	L2367407	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.445	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.16	< 0.098 U	< 0.098 U	< 0.051 U	0.243	0.091	< 0.12 U
K-Wing Rooftop	EHS-11112024-OA-KWING-RF	11/11/2024	L2466343	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.516	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.955	0.29	< 0.098 U	< 0.051 U	0.291	0.113	< 0.12 U
K-Wing Rooftop	EHS-11112025-OA-KWING	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	0.113	0.86	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U
Music Room 148	EHS-122619-IA-148-OCC	12/27/2019	1912741	< 0.62 U	< 0.73 U	--	< 0.23 U	0.28 J	2.7	< 6.3 U	< 0.19 U	< 0.19 U	< 0.18 U	1.3	< 0.84 U	< 0.84 U	< 0.044 U	3	0.96	< 0.2 U
Music Room 148	EHS-122619-IA-148-OCC DUP	12/27/2019	1912741	< 0.66 U	< 0.78 U	--	< 0.25 U	< 0.25 UJ	2.8	< 6.8 U	< 0.2 U	< 0.2 U	< 0.2 U	1.4	< 0.9 U	< 0.9 U	< 0.047 U	3	0.98	< 0.22 U
Room 127	EHS-122619-IA-127-OCC	12/27/2019	1912741	< 0.57 U	< 0.67 U	--	< 0.22 U	< 0.21 U	4	< 5.9 U	< 0.17 U	< 0.17 U	< 0.17 U	1.4	< 0.78 U	< 0.78 U	< 0.04 U	1.4	0.47	< 0.19 U
Room 127	EHS-122920-IA-127	1/5/2021	2101097	< 0.62 U	< 0.73 U	--	< 0.23 U	< 0.23 U	1.9	< 6.3 U	< 0.19 U	< 0.19 U	< 0.18 U	1.2	< 0.84 U	< 0.84 U	< 0.044 U	0.49	0.19	< 0.2 U
Room 127	EHS-040521-IA-127 (6L2173)	4/12/2021	2104300	< 0.51 U	< 0.60 U	--	< 0.19 U	< 0.19 U	3.0	< 5.3 UJ	< 0.15 U	< 0.15 U	< 0.15 U	1.2	< 0.70 U	< 0.70 U	< 0.036 U	0.59	0.21	< 0.17 U
Room 127	EHS-072221-IA-127	7/29/2021	2107676	< 1.3 U	< 1.5 U	--	< 0.48 U	< 0.48 U	2.9	< 13 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2.0 U	< 1.7 U	< 1.7 U	< 0.090 U	2.2	0.85	< 0.42 U
Room 127	EHS-122221-IA-127	12/22/2021	2112771R2	< 1.2 U	< 1.4 U	--	< 0.45 U	< 0.44 U	2.1	< 12 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 1.6 U	< 1.6 U	< 0.083 U	< 0.56 U	< 0.28 U	< 0.39 U
Room 127	EHS-01022023-IA-127	1/2/2023	2301092	< 0.50 U	< 0.60 U	--	< 0.19 U	0.24	1.5	< 5.2 U	< 0.15 U	< 0.15 U	< 0.15 U	1.2	< 0.69 U	< 0.69 U	< 0.036 U	0.46	0.16	< 0.17 U
Room 127	EHS-11102023-IA-127	11/10/2023	L2367407	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	0.852	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.16	0.123	< 0.098 U	< 0.051 U	0.434	0.161	< 0.12 U
Room 127	EHS-11112024-IA-127	11/11/2024	L2466343	< 0.721 U	< 0.085 U	< 1.52 U	< 0.137 U	< 0.136 U	1.61	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.922	0.551	< 0.098 U	< 0.051 U	0.491	0.182	< 0.12 U
Room 127	EHS-11112025-IA-127	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	0.441	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.894	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U
Room 148	EHS-122920-IA-148	1/5/2021	2101097	< 1.6 U	< 1.9 U	--	< 0.61 U	< 0.61 U	2 J	< 16 U	< 0.49 U	< 0.49 U	< 0.48 U	< 2.5 U	< 2.2 U	< 2.2 U	< 0.11 U	< 0.78 U	< 0.39 U	< 0.54 U
Room 148	EHS-122920-IA-148DUP	1/5/2021	2101097	< 1.4 U	< 1.7 U	--	< 0.54 U	< 0.53 U	0.8 J	< 14 U	< 0.43 U	< 0.43 U	< 0.42 U	< 2.2 U	< 1.9 U	< 1.9 U	< 0.1 U	< 0.68 U	< 0.34 U	< 0.47 U
Room 148	EHS-040521-IA-148 (6L1850)	4/12/2021	2104300	< 0.55 U	< 0.65 U	--	< 0.21 U	< 0.21 U	1.8	< 5.6 UJ	< 0.16 U	< 0.16 U	< 0.16 U	1.3	< 0.75 U	< 0.75 U	< 0.039 U	0.40	0.16	< 0.18 U
Room 148	EHS-040521-IA-148DUP (6L1167)	4/12/2021	2104300	< 0.52 U	< 0.61 U	--	< 0.20 U	< 0.20 U	1.8	< 5.3 UJ	< 0.16 U	< 0.16 U	< 0.15 U	1.3	< 0.71 U	< 0.71 U	< 0.037 U	0.42	0.16	< 0.17 U
Room 148	EHS-072221-IA-148	7/29/2021	2107676	< 1.3 U	< 1.6 U	--	< 0.51 U	< 0.50 U	3.8	< 14 U	< 0.40 U	< 0.40 U	< 0.40 U	< 2.1 U	< 1.8 U	< 1.8 U	< 0.094 U	0.66 J	< 0.32 UJ	< 0.44 U
Room 148	EHS-072221-IA-148 DUP	7/29/2021	2107676	< 1.3 U	< 1.5 U	--	< 0.48 U	< 0.48 U	4.4	< 13 U	< 0.38 U	< 0.38 U	< 0.38 U	< 2.0 U	< 1.7 U	< 1.7 U	< 0.090 U	1.1 J	0.47 J	< 0.42 U
Room 148	EHS-122221-IA-148	12/22/2021	2112771R2	< 0.42 U	< 0.50 U	--	< 0.16 U	< 0.16 U	1.1 J	< 4.4 U	< 0.13 U	< 0.13 U	< 0.13 U	1.2 J	< 0.58 U	< 0.58 U	< 0.030 U	0.24 J	< 0.10 U	< 0.14 U
Room 148	EHS-122221-IA-148DUP	12/22/2021	2112771R2	< 1.2 U	< 1.4 U	--	< 0.45 U	< 0.44 U	2.5 J	< 12 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 UJ	< 1.6 U	< 1.6 U	< 0.083 U	< 0.56 UJ	< 0.28 U	< 0.39 U
Room 148	EHS-01022023-IA-DUP	1/2/2023	2301092	< 0.48 U	< 0.57 U	--	< 0.18 U	0.61	1.6	< 5.0 U	< 0.15 U	< 0.15 U	< 0.14 U	1.1	< 0.66 U	< 0.66 U	< 0.034 U	0.54	0.18	< 0.16 U
Room 148	EHS-01022023-IA-148	1/2/2023	2301092	< 0.49 U	< 0.58 U	--	< 0.19 U	0.67	1.6	< 5.1 U	< 0.15 U	< 0.15 U	< 0.15 U	1.1	< 0.67 U	< 0.67 U	< 0.035 U	0.50	0.17	< 0.16 U
Room 148	EHS-11102023-IA-148	11/10/2023	L2367407	< 0.721 U	0.089	< 1.52 U	< 0.137 U	< 0.136 U	0.667	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.16	0.098	< 0.098 U	< 0.051 U	0.339	0.13	< 0.12 U
Room 148	EHS-11102023-IA-DUP	11/10/2023	L2367407	< 0.721 U	0.089	< 1.52 U	< 0.137 U	< 0.136 U	0.648	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	1.16	0.103	< 0.098 U	< 0.051 U	0.334	0.126	< 0.12 U
Room 148	EHS-11112024-IA-148	11/11/2024	L2466343	< 0.721 U	0.089	< 1.52 U	< 0.137 U	0.176	0.705	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.967	0.551	< 0.098 U	< 0.051 U	0.291	0.122	< 0.12 U
Room 148	EHS-11112024-IA-DUP	11/11/2024	L2466343	< 0.721 U	0.089	< 1.52 U	< 0.137 U	0.17	0.712	< 0.371 U	< 0.109 U	< 0.109 U	< 0.107 U	0.955	0.28	< 0.098 U	< 0.051 U	0.308	0.13	< 0.12 U
Room 148	EHS-11112025-IA-148	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.888	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U
Room 148	EHS-11112025-IA-DUP	11/11/2025	L2573502	< 0.721 U	< 0.085 UJ	< 1.52 U	< 0.137 U	< 0.136 U	< 0.377 U	< 0.371 UJ	< 0.109 U	< 0.109 U	< 0.107 U	0.933	< 0.098 U	< 0.098 U	< 0.051 U	< 0.174 U	< 0.087 U	< 0.12 U

Notes

µg/m3: microgram per cubic meter

Samples were analyzed via method TO-15

U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.

J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

UJ: The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

Analyte concentrations detected above NYSDOH VI Matrix Guidelines are presented in light gray.

Table 6-1B

Detected Concentrations for Sub-Slab Depressurization (SSD) Effluent - VOCs 2018

Former Sperry Remington Site-North Portion

Elmira, New York

NYSDOH Matrix A Compounds Detected in SSDS Stack Samples							
	Compound	Trichloroethene			cis-1,2-Dichloroethene		
Location	Sample ID	Reporting Limit (ug/m3)	Result (ug/m3)	Qualifier	Reporting Limit (ug/m3)	Result (ug/m3)	Qualifier
F Wing Stack	EHS-062818-EF-FWING	5.9	340		4.4	67	
Retrofit Stack	EHS-062818-EF-CAFR	6		ND	4.4		ND
Expansion Stack	EHS-062818-EF-CAFA	6.5	26		4.8		ND
K Wing Stack	EHS-062818-EF-KWING	6.2	31		4.5		ND
Gym Stack	EHS-062818-EF-GYM	5.9	19		4.4		ND

Music Wing SSDS Stack Sample Concentrations			
Sample ID	**Sample Date**	**COMPOUND NAME**	**Results ($\mu g/m^3$)**
EHS-083018-EF-M-OCC	8/30/2018	Freon 12	140
EHS-083018-EF-M-OCC	8/30/2018	Ethanol	21
EHS-083018-EF-M-OCC	8/30/2018	Acetone	430
EHS-083018-EF-M-OCC	8/30/2018	2-Butanone	190
EHS-083018-EF-M-OCC	8/30/2018	Tetrahydrofuran	830
EHS-083018-EF-M-OCC	8/30/2018	Trichloroethene	58
EHS-083018-EF-M-OCC	8/30/2018	Toluene	5
EHS-083018-EF-M-OCC	8/30/2018	m,p-Xylene	5.6

Notes: ND - non-detect

ug/m3 - micrograms per cubic meter

The Music Wing SSD System was sampled in August 2018 after installation. All other systems were sampled in June 2018.

DRAFT

Table 6-1C
ISMP Post-Mitigation Monitoring Results for SSD Effluent - VOCs
2020-2025
Former Sperry Remington Site - North Portion
Elmira, New York

					Acetone	alpha-Chlorotoluene	Benzene	Bromodichloromethane	Bromoform	Bromomethane	1,3-Butadiene	Carbon disulfide	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	3-Chloropropene	Cumene	Cyclohexane	Dichloromethane	Dibromochloromethane	1,2-Dibromoethane	Dichlorodifluoromethane
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample ID	Sample Name	Sample Location	Sample Date	Lab Report																					
EHS-EF-CAFAD	EHS-122920-EF-CAF-AD	Cafeteria (Addition)	12/29/2020		<25U	<5.5U	<3.4U	<7.1U	<11U	<41U	<2.4U	<13U	<6.7U	<4.9U	--	<11U	<5.2U	<22U	<13U	<5.2U	<3.7U	--	<9.1U	<4.6U	--
EHS-EF-CAFAD	EHS-040521-EF-CAF-AD	Cafeteria (Addition)	4/5/2021		<22U	<4.8U	<3.0U	<6.3U	<9.7U	<36U	<2.1U	<12U	<5.9U	<4.3U	--	<9.9U	<4.6U	<19U	<12U	<4.6U	<3.2U	--	<8.0U	<7.2U	--
EHS-EF-CAFAD	2107546 EHS-072221-EF-CAF-AD	Cafeteria (Addition)	7/22/2021		<95U	<21U	<13U	<27U	<42U	<160U	<8.9U	<50U	<25U	<18U	--	<42U	<20U	<83U	<50U	<20U	<14U	--	<34U	<31U	--
EHS-EF-CAFAD	EHS-122121-EF-CAFAD	Cafeteria (Addition)	12/21/2021		<21U	<4.6U	<2.8U	<5.9U	<9.1U	<34U	<1.9U	<11U	<5.5U	<4.0U	--	<9.3U	<4.3U	<18U	<11U	<4.3U	<3.0U	--	<7.5U	<6.8U	--
EHS-EF-CAFAD	EHS-11102023-EF-CAFAD	Cafeteria (Addition)	11/10/2023	L2367767	7.25	--	< 1.28 U	< 2.68 U	< 4.14 U	< 1.55 U	--	< 1.25 U	< 2.52 U	< 1.84 U	< 3.41 U	< 1.06 U	< 1.95 U	< 0.826 U	--	--	< 1.38 U	< 3.47 U	--	< 3.07 U	18.1
EHS-EF-CAFAD	EHS-11112024-EF-CAFAD	Cafeteria (Addition)	11/11/2024	L2466355	8.29	--	< 1.43 U	< 2.99 U	< 4.62 U	< 1.74 U	< 0.989 U	< 1.39 U	< 2.81 U	< 2.06 U	--	< 1.18 U	< 2.18 U	< 0.923 U	< 1.4 U	--	< 1.54 U	--	< 3.81 U	< 3.44 U	14.2
EHS-EF-CAFAD	EHS-11112025-EF-CAFAD	Cafeteria (Addition)	11/11/2025	L2573524	< 5.06 U	--	< 1.36 U	< 2.85 U	< 4.4 U	< 1.65 U	< 0.942 U	< 1.33 U	< 2.68 U	< 1.96 U	--	< 1.12 U	< 2.08 U	< 0.88 U	< 1.33 U	--	< 1.47 U	--	< 3.63 U	< 3.27 U	14.7
EHS-EF-CAFRET	EHS-122920-EF-CAF-RET	Cafeteria (Retrofit)	12/29/2020		<23UJ	<5.0UJ	<3.1UJ	<6.4UJ	<9.9UJ	<37UJ	<2.1UJ	<12UJ	<6.0UJ	<4.4UJ	--	<10UJ	<4.7UJ	<20UJ	<12UJ	<4.7UJ	<3.3UJ	--	<8.2UJ	<4.2UJ	--
EHS-EF-CAFRET	EHS-040521-EF-CAF RET	Cafeteria (Retrofit)	4/5/2021		<21U	<4.6U	<2.9U	<6.0U	<9.3U	<35U	<2.0U	<11U	<5.7U	<4.1U	--	<9.5U	<4.4U	<18U	<11U	<4.4U	<3.1U	--	<7.7U	<6.9U	--
EHS-EF-CAFRET	2107546 EHS-072221-EF-CAFRET	Cafeteria (Retrofit)	7/22/2021		30	<5.2U	<3.2U	<6.7U	<10U	<39U	<2.2U	<12U	<6.3U	<4.6U	--	<11U	<4.9U	<21U	<12U	<4.9U	<3.4U	--	<8.6U	<7.7U	--
EHS-EF-CAFRET	EHS-122121-EF-CAFRET	Cafeteria (Retrofit)	12/21/2021		<19UJ	<4.2UJ	<2.6UJ	<5.4UJ	<8.4UJ	<31UJ	<1.8UJ	<10UJ	<5.1UJ	<3.7UJ	--	<8.5UJ	17J	<17UJ	<10UJ	<4.0UJ	<2.8UJ	--	<6.9UJ	<6.2UJ	--
EHS-EF-CAFRET	EHS-11102023-EF-CAFRET	Cafeteria (Retrofit)	11/10/2023	L2367767	6.72	--	< 1.35 U	< 2.84 U	< 4.38 U	< 1.65 U	--	< 1.32 U	< 2.67 U	< 1.95 U	< 3.61 U	< 1.12 U	< 2.07 U	< 0.876 U	--	--	< 1.46 U	< 3.68 U	--	< 3.26 U	15.7
EHS-EF-CAFRET	EHS-11112024-EF-CAFRET	Cafeteria (Retrofit)	11/11/2024	L2466355	6.15	--	< 1.37 U	< 2.87 U	< 4.43 U	< 1.66 U	< 0.947 U	< 1.33 U	< 2.69 U	< 1.97 U	--	< 1.13 U	< 2.09 U	< 0.884 U	< 1.34 U	--	< 1.47 U	--	< 3.65 U	< 3.29 U	14.1
EHS-EF-CAFRET	EHS-11112025-EF-CAFRET	Cafeteria (Retrofit)	11/11/2025	L2573524	5.32	--	< 1.32 U	< 2.77 U	< 4.27 U	< 1.6 U	< 0.914 U	< 1.29 U	< 2.6 U	< 1.9 U	--	< 1.09 U	< 2.02 U	< 0.853 U	< 1.29 U	--	< 1.42 U	--	< 3.52 U	< 3.17 U	11.1
EHS-EF-FWING	EHS-122920-EF-FWING	F-Wing	12/29/2020		<25U	<5.4U	<3.4U	<7.0U	<11U	<41U	<2.3U	<13U	<6.6U	<4.8U	--	<11U	<5.1U	<22U	<13U	<5.2U	<3.6U	--	<8.9U	<4.6U	--
EHS-EF-FWING	EHS-040521-EF-FWING	F-Wing	4/5/2021		<22U	<4.8U	<3.0U	<6.3U	<9.7U	<36U	<2.1U	<12U	<5.9U	<4.3U	--	<9.9U	<4.6U	<19U	<12U	<4.6U	<3.2U	--	<8.0U	<7.2U	--
EHS-EF-FWING	2107546 EHS-072221-EF-FWING	F-Wing	7/22/2021		40	<5.2U	<3.2U	<6.8U	<10U	<39U	<2.2U	<12U	<6.4U	<4.6U	--	<11U	<4.9U	<21U	<13U	<5U	<3.5U	--	<8.6U	<7.9U	--
EHS-EF-FWING	EHS-122121-EF-FWING	F-Wing	12/21/2021		<23U	<5.0U	<3.1U	<6.4U	<9.9U	<37U	<2.1U	<12U	<6.0U	<4.4U	--	<10U	<4.7U	<20U	<12U	<4.7U	<3.3U	--	<8.2U	<7.4U	--
EHS-EF-FWING	EHS-11102023-EF-FWING	F-Wing	11/10/2023	L2367767	12.4	--	< 2.83 U	< 5.94 U	< 9.17 U	< 3.44 U	--	< 2.76 U	< 5.58 U	< 4.08 U	< 7.56 U	< 2.34 U	< 4.33 U	< 1.83 U	--	--	< 3.05 U	< 7.71 U	--	< 6.82 U	101
EHS-EF-FWING	EHS-11112024-EF-FWING	F-Wing	11/11/2024	L2466355	23.3	--	< 1.51 U	< 3.16 U	< 4.88 U	< 1.83 U	< 1.04 U	< 1.47 U	< 2.97 U	< 2.17 U	--	< 1.25 U	< 2.3 U	15.6	< 1.48 U	--	< 1.62 U	--	< 4.02 U	< 3.63 U	101
EHS-EF-FWING	EHS-11112025-EF-FWING	F-Wing	11/11/2025	L2573524	< 4.87 U	--	< 1.31 U	< 2.75 U	< 4.25 U	< 1.6 U	< 0.909 U	< 1.28 U	< 2.59 U	< 1.89 U	--	< 1.08 U	< 2.01 U	< 0.849 U	< 1.29 U	--	< 1.41 U	--	< 3.5 U	< 3.16 U	75.7
EHS-EF-GYM	EHS-122920-EF-GYM	Gymnasium	12/29/2020		<25U	<5.4U	<3.3U	<7.0U	<11U	<40U	<2.3U	<13U	<6.6U	<4.8U	--	<11U	<5.1U	<22U	<13U	<5.1U	<3.6U	--	<8.9U	<4.5U	--
EHS-EF-GYM	EHS-040521-EF-GYM	Gymnasium	4/5/2021		<23U	<5.0U	<3.1U	<6.5U	<10U	<38U	<2.1U	84	<6.1U	<4.5U	--	<10U	7.3	<20U	<12U	<4.8U	<3.3U	--	<8.3U	<7.4U	--
EHS-EF-GYM	2107546 EHS-072221-EF-GYM	Gymnasium	7/22/2021		<240U	<54U	<33U	<69U	<110U	<400U	<23U	<130U	<65U	<48U	--	<110U	<50U	<210U	<130U	<51U	<36U	--	<88U	<80U	--
EHS-EF-GYM	EHS-122121-EF-GYM	Gymnasium	12/21/2021		<23U	<5.0U	<3.1U	<6.4U	<9.9U	<37U	<2.1U	<12U	<6.0U	<4.4U	--	<10U	6.6	<20U	<12U	<4.7U	<3.3U	--	<8.2U	<7.4U	--
EHS-EF-GYM	EHS-11102023-EF-GYM	Gymnasium	11/10/2023	L2367767	16	--	< 1.37 U	< 2.87 U	< 4.43 U	< 1.66 U	--	< 1.33 U	< 2.69 U	< 1.97 U	< 3.65 U	< 1.13 U	8.01	< 0.884 U	--	--	< 1.47 U	< 3.72 U	--	< 3.29 U	15.2
EHS-EF-GYM	EHS-11112024-EF-GYM	Gymnasium	11/11/2024	L2466355	19.1	--	< 1.44 U	< 3.01 U	< 4.65 U	< 1.75 U	< 0.996 U	< 1.4 U	< 2.83 U	< 2.07 U	--	< 1.19 U	31.9	1.36	< 1.41 U	--	< 1.55 U	--	< 3.83 U	< 3.46 U	6.28
EHS-EF-GYM	EHS-11112025-EF-GYM	Gymnasium	11/11/2025	L2573524	29.5	--	< 1.39 U	< 2.92 U	< 4.51 U	< 1.69 U	< 0.965 U	< 1.36 U	< 2.74 U	< 2.01 U	--	< 1.15 U	3.32	< 0.9 U	< 1.36 U	--	< 1.5 U	--	< 3.71 U	< 3.35 U	84.6
EHS-EF-KWING	EHS-122920-EF-KWING	K-Wing	12/29/2020		<23UJ	<5.0UJ	<3.1UJ	<6.5UJ	<10UJ	<38UJ	<2.2UJ	<12UJ	<6.1UJ	<4.5UJ	--	<10UJ	<4.8UJ	<20UJ	<12UJ	<4.8UJ	<3.4UJ	--	<8.3UJ	<4.2UJ	--
EHS-EF-KWING	EHS-040521-EF-KWING	K-Wing	4/5/2021		<22U	<4.8U	<3.0U	<6.3U	<9.7U	<36U	<2.1U	<12U	<5.9U	<4.3U	--	<9.9U	<4.6U	<19U	<12U	<4.6U	<3.2U	--	<8.0U	<7.2U	--
EHS-EF-KWING	2107546 EHS-072221-EF-KWING	K-Wing	7/22/2021		40	<5.2U	<3.2U	<6.8U	<10U	<39U	<2.2U	<12U	<6.4U	<4.6U	--	<11U	<4.9U	<21U	<13U	<5U	<3.5U	--	<8.6U	<7.8U	--
EHS-EF-KWING	EHS-122121-EF-KWING	K-Wing	12/21/2021		<22U	<4.7U	<2.9U	<6.1U	<9.4U	<36U	<2.0U	<11U	<5.8U	<4.2U	--	<9.6U	<4.5U	<19U	<11U	<4.5U	<3.1U	--	<7.8U	<7.0U	--
EHS-EF-KWING	EHS-11102023-EF-KWING	K-Wing	11/10/2023	L2367767	< 9.91 U	--	< 2.67 U	< 5.59 U	< 8.63 U	< 3.24 U	--	< 2.6 U	< 5.25 U	< 3.85 U	< 7.11 U	< 2.2 U	< 4.08 U	< 1.72 U	--	--	< 2.87 U	< 7.26 U	--	< 6.42 U	8.85
EHS-EF-KWING	EHS-11112024-EF-KWING	K-Wing	11/11/2024	L2466355	11.3	--	< 1.49 U	< 3.12 U	< 4.81 U	< 1.81 U	< 1.03 U	< 1.45 U	< 2.93 U	< 2.14 U	--	< 1.23 U	< 2.27 U	2.56	< 1.46 U	--	< 1.6 U	--	< 3.96 U	< 3.57 U	11.1
EHS-EF-KWING	EHS-11112025-EF-KWING	K-Wing	11/11/2025	L2573524	5.01	--	< 1.32 U	< 2.77 U	< 4.27 U	< 1.6 U	< 0.914 U	< 1.29 U	< 2.6 U	< 1.9 U	--	< 1.09 U	< 2.02 U	< 0.853 U	< 1.29 U	--	< 1.42 U	--	< 3.52 U	< 3.17 U	5.79
EHS-EF-MUSIC	EHS-040521-EF-MUSIC	Music Wing	4/5/2021		35	<4.6U	<2.9U	<6.0U	<9.3U	<35U	<2.0U	<11U	<5.7U	<4.1U	--	<9.5U	<4.4U	<18U	<11U	<4.4U	<3.1U	--	<7.7U	<6.9U	--
EHS-EF-MUSIC	2107546 EHS-072221-EF-MUSIC	Music Wing	7/22/2021		<25U	<5.5U	<3.4U	<7.1U	<11U	<41U	<2.3U	<13U	<6.7U	<4.9U	--	<11U	<5.2U	<22U	<13U	<5.2U	<3.6U	--	<9U	<8.1U	--
EHS-EF-MUSIC	EHS-122121-EF-MUSIC	Music Wing	12/21/2021		<23U	<5.0U	<3.1U	<6.4U	<9.9U	<37U	<2.1U	<12U	<6.0U	<4.4U	--	<10U	<4.7U	<20U	<12U	<4.7U	<3.3U	--	<8.2U	<7.4U	--
EHS-EF-MUSIC	EHS-11102023-EF-MUSIC	Music Wing	11/10/2023	L2367767	11.1	--	< 1.38 U	< 2.89 U	< 4.46 U	< 1.67 U	--	< 1.34 U	< 2.71 U	< 1.98 U	< 3.67 U	< 1.14 U	< 2.1 U	< 0.89 U	--	--	< 1.48 U	< 3.75 U	--	< 3.31 U	28.9
EHS-EF-MUSIC	EHS-11112024-EF-MUSIC	Music Wing	11/11/2024	L2466355	18.1	--	< 1.44 U	< 3.01 U	< 4.65 U	< 1.75 U	< 0.996 U	< 1.4 U	< 2.83 U	< 2.07 U	--	< 1.19 U	< 2.2 U	< 0.929 U	< 1.41 U	--	< 1.55 U	--	< 3.83 U	< 3.46 U	35.1
EHS-EF-MUSIC	EHS-11112025-EF-MUSIC	Music Wing	11/11/2025	L2573524	5.61	--	< 1.3 U	< 2.73 U	< 4.22 U	< 1.58 U	< 0.903 U	< 1.27 U	< 2.57 U	< 1.88 U	--	< 1.08 U	< 1.99 U	< 0.843 U	< 1.28 U	--	< 1.4 U	--	< 3.48 U	< 3.14 U	26.7

Notes
µg/m3: microgram per cubic meter
Samples were analyzed via method TO-15
U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.
J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
UJ: The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

DRAFT

Table 6-1C
ISMP Post-Mitigation Monitoring Results for SSD Effluent - VOCs
2020-2025
Former Sperry Remington Site - North Portion
Elmira, New York

					1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	1,4-Dioxane	trans-1,3-Dichloropropene	Ethanol	Ethylbenzene	4-Ethyltoluene	Freon 11	Freon 113	Freon 114	Freon 12	Heptane	Hexachlorobutadiene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample ID	Sample Name	Sample Location	Sample Date	Lab Report																					
EHS-EF-CAFAD	EHS-122920-EF-CAF-AD	Cafeteria (Addition)	12/29/2020		<6.4U	<6.4U	<6.4U	<4.3U	<4.3U	<4.2U	<4.2U	<4.2U	<4.9U	<4.8U	<15U	<4.8U	<8.2U	32	<5.2U	<6.0U	<8.2U	<7.4U	11	<4.4U	<45U
EHS-EF-CAFAD	EHS-040521-EF-CAF-AD	Cafeteria (Addition)	4/5/2021		<5.6U	<5.6U	<5.6U	<3.8U	<3.8U	<3.7U	<3.7U	<3.7U	<4.3U	<4.2U	<13U	<4.2U	<18U	<4.0U	<4.6U	<5.2U	<7.2U	<6.5U	15	<3.8U	<40U
EHS-EF-CAFAD	2107546_EHS-072221-EF-CAF-AD	Cafeteria (Addition)	7/22/2021		<24U	<24U	<24U	<16U	<16U	<16U	<16U	<16U	<18U	<18U	<58U	<18U	<76U	<17U	<20U	<22U	<31U	<28U	38	<16U	<170U
EHS-EF-CAFAD	EHS-122121-EF-CAFAD	Cafeteria (Addition)	12/21/2021		<5.3U	<5.3U	<5.3U	<3.6U	<3.6U	<3.5U	<3.5U	<3.5U	<4.1U	<4.0U	<13U	<4.0U	<16U	<3.8U	<4.3U	<4.9U	<6.7U	<6.2U	14	<3.6U	<38U
EHS-EF-CAFAD	EHS-11102023-EF-CAFAD	Cafeteria (Addition)	11/10/2023	L2367767	< 2.4 U	< 2.4 U	< 2.4 U	< 1.62 U	< 1.62 U	< 1.59 U	< 1.59 U	< 1.59 U	< 1.85 U	< 1.82 U	--	< 1.82 U	--	5.08	--	--	< 3.07 U	--	--	--	--
EHS-EF-CAFAD	EHS-11112024-EF-CAFAD	Cafeteria (Addition)	11/11/2024	L2466355	< 2.69 U	< 2.69 U	< 2.69 U	< 1.81 U	< 1.81 U	< 1.77 U	< 1.77 U	< 1.77 U	< 2.07 U	< 2.03 U	< 1.61 U	< 2.03 U	23.7	< 1.94 U	< 2.2 U	--	< 3.43 U	< 3.12 U	--	< 1.83 U	< 4.77 U
EHS-EF-CAFAD	EHS-11112025-EF-CAFAD	Cafeteria (Addition)	11/11/2025	L2573524	< 2.56 U	< 2.56 U	< 2.56 U	< 1.72 U	< 1.72 U	< 1.69 U	< 1.69 U	< 1.69 U	< 1.97 U	< 1.93 U	< 1.54 U	< 1.93 U	< 20 U	< 1.85 U	< 2.09 U	--	< 3.27 U	< 2.98 U	--	< 1.75 U	< 4.54 U
EHS-EF-CAFRET	EHS-122920-EF-CAF-RET	Cafeteria (Retrofit)	12/29/2020		<5.8UJ	<5.8UJ	<5.8UJ	<3.9UJ	<3.9UJ	<3.8UJ	<3.8UJ	<3.8UJ	<4.4UJ	<4.4UJ	<14UJ	<4.4UJ	<7.4UJ	27J	<4.7UJ	<5.4UJ	<7.4UJ	<6.7UJ	8.8J	<3.9UJ	<41UJ
EHS-EF-CAFRET	EHS-040521-EF-CAF RET	Cafeteria (Retrofit)	4/5/2021		<5.4U	<5.4U	<5.4U	<3.6U	<3.6U	<3.6U	<3.6U	<3.6U	<4.2U	<4.1U	<13U	<4.1U	17	<3.9U	<4.4U	<5.0U	<6.9U	<6.3U	15	<3.7U	<38U
EHS-EF-CAFRET	2107546_EHS-072221-EF-CAFRET	Cafeteria (Retrofit)	7/22/2021		<6U	<6U	<6U	<4.1U	<4.1U	<4U	<4U	<4U	<4.6U	<4.6U	<14U	<4.6U	20	<4.4U	<4.9U	<5.6U	<7.7U	<7U	35	<4.1U	<43U
EHS-EF-CAFRET	EHS-122121-EF-CAFRET	Cafeteria (Retrofit)	12/21/2021		<4.9UJ	<4.9UJ	<4.9UJ	<3.3UJ	<3.3UJ	<3.2UJ	<3.2UJ	<3.2UJ	<3.7UJ	<3.7UJ	<12UJ	<3.7UJ	18J	<3.5UJ	<4.0UJ	<4.6UJ	<6.2UJ	<5.7UJ	9.3J	<3.3UJ	<34UJ
EHS-EF-CAFRET	EHS-11102023-EF-CAFRET	Cafeteria (Retrofit)	11/10/2023	L2367767	< 2.55 U	< 2.55 U	< 2.55 U	< 1.72 U	< 1.72 U	< 1.68 U	< 1.68 U	< 1.68 U	< 1.96 U	< 1.92 U	--	< 1.92 U	--	4.78	--	--	< 3.25 U	--	--	--	--
EHS-EF-CAFRET	EHS-11112024-EF-CAFRET	Cafeteria (Retrofit)	11/11/2024	L2466355	< 2.57 U	< 2.57 U	< 2.57 U	< 1.73 U	< 1.73 U	< 1.7 U	< 1.7 U	< 1.7 U	< 1.98 U	< 1.94 U	< 1.54 U	< 1.94 U	< 20.2 U	< 1.86 U	< 2.1 U	--	< 3.28 U	< 2.99 U	--	< 1.75 U	< 4.57 U
EHS-EF-CAFRET	EHS-11112025-EF-CAFRET	Cafeteria (Retrofit)	11/11/2025	L2573524	< 2.48 U	< 2.48 U	< 2.48 U	< 1.67 U	< 1.67 U	< 1.64 U	< 1.64 U	< 1.64 U	< 1.91 U	< 1.87 U	< 1.49 U	< 1.87 U	< 19.4 U	< 1.79 U	< 2.03 U	--	< 3.17 U	< 2.89 U	--	< 1.69 U	< 4.41 U
EHS-EF-FWING	EHS-122920-EF-FWING	F-Wing	12/29/2020		<6.3U	<6.3U	<6.3U	<4.2U	<4.2U	<4.2U	43	<4.2U	<4.8U	<4.8U	<15U	<4.8U	<8.1U	<20U	<5.2U	<5.9U	<8.0U	<7.3U	76	<4.3U	<45U
EHS-EF-FWING	EHS-040521-EF-FWING	F-Wing	4/5/2021		<5.6U	<5.6U	<5.6U	<3.8U	<3.8U	<3.7U	39	<3.7	<4.3U	<4.2U	<13U	<4.2	<18U	<4.0U	<4.6U	<5.2U	<7.2U	<6.5U	100	<3.8U	<40U
EHS-EF-FWING	2107546_EHS-072221-EF-FWING	F-Wing	7/22/2021		<6.1U	<6.1U	<6.1U	<4.1U	<4.1U	<4U	<4U	<4U	<4.7U	<4.6U	<14U	<4.6U	<19U	<4.4U	<5U	<5.7U	140	<7.1U	92	<4.1U	<43U
EHS-EF-FWING	EHS-122121-EF-FWING	F-Wing	12/21/2021		<5.8U	<5.8U	<5.8U	<3.9U	<3.9U	<3.8U	50	<3.8U	<4.4U	<4.4U	<14U	<4.4U	54	<4.2U	<4.7U	<5.4U	<7.4U	<6.7U	83	<3.9U	<41U
EHS-EF-FWING	EHS-11102023-EF-FWING	F-Wing	11/10/2023	L2367767	< 5.33 U	< 5.33 U	< 5.33 U	< 3.59 U	< 3.59 U	< 3.52 U	66.6	< 3.52 U	< 4.1 U	< 4.03 U	--	< 4.03 U	--	11.3	--	--	< 6.8 U	--	--	--	--
EHS-EF-FWING	EHS-11112024-EF-FWING	F-Wing	11/11/2024	L2466355	< 2.84 U	< 2.84 U	< 2.84 U	< 1.91 U	< 1.91 U	< 1.87 U	40.8	< 1.87 U	< 2.18 U	< 2.14 U	< 1.7 U	< 2.14 U	29.4	3.11	4.7	--	< 3.62 U	< 3.3 U	--	< 1.93 U	< 5.03 U
EHS-EF-FWING	EHS-11112025-EF-FWING	F-Wing	11/11/2025	L2573524	< 2.47 U	< 2.47 U	< 2.47 U	< 1.66 U	< 1.66 U	< 1.63 U	42	1.69	< 1.9 U	< 1.87 U	< 1.48 U	< 1.87 U	< 19.4 U	< 1.79 U	< 2.02 U	--	< 3.15 U	< 2.87 U	--	< 1.68 U	< 4.38 U
EHS-EF-GYM	EHS-122920-EF-GYM	Gymnasium	12/29/2020		<6.3U	<6.3U	<6.3U	<4.2U	<4.2U	<4.1U	<4.1U	<4.1U	<4.8U	<4.7U	<15U	<4.7U	<8.0U	<20U	<5.1U	<5.9U	190	<7.3U	<5.2U	<4.3U	<44U
EHS-EF-GYM	EHS-040521-EF-GYM	Gymnasium	4/5/2021		<5.8U	<5.8U	<5.8U	<3.9U	<3.9U	<3.8U	<3.8U	<3.8U	<4.5U	<4.4U	<14U	<4.4U	<18U	<4.2U	<4.8U	<5.4U	170	<6.8U	<4.8U	<4.0U	<41U
EHS-EF-GYM	2107546_EHS-072221-EF-GYM	Gymnasium	7/22/2021		<62U	<62U	<62U	<42U	<42U	<41U	<41U	<41U	<48U	<47U	<150U	<47U	<200U	<45U	<51U	<58U	250	<72U	180	<42U	<440U
EHS-EF-GYM	EHS-122121-EF-GYM	Gymnasium	12/21/2021		<5.8U	<5.8U	<5.8U	<3.9U	<3.9U	<3.8U	<3.8U	<3.8U	<4.4U	<4.4U	<14U	<4.4U	<18U	<4.2U	<4.7U	<5.4U	300	<6.7U	<4.7U	<3.9U	<41U
EHS-EF-GYM	EHS-11102023-EF-GYM	Gymnasium	11/10/2023	L2367767	< 2.57 U	< 2.57 U	< 2.57 U	< 1.73 U	< 1.73 U	< 1.7 U	< 1.7 U	< 1.7 U	< 1.98 U	< 1.94 U	--	< 1.94 U	--	6.91	--	--	108	--	--	--	--
EHS-EF-GYM	EHS-11112024-EF-GYM	Gymnasium	11/11/2024	L2466355	< 2.71 U	< 2.71 U	< 2.71 U	< 1.82 U	< 1.82 U	< 1.78 U	< 1.78 U	< 1.78 U	< 2.08 U	< 2.04 U	< 1.62 U	< 2.04 U	25.6	< 1.95 U	< 2.21 U	--	< 3.45 U	< 3.15 U	--	< 1.84 U	< 4.8 U
EHS-EF-GYM	EHS-11112025-EF-GYM	Gymnasium	11/11/2025	L2573524	< 2.62 U	< 2.62 U	< 2.62 U	< 1.76 U	< 1.76 U	< 1.73 U	< 1.73 U	< 1.73 U	< 2.02 U	< 1.98 U	< 1.57 U	< 1.98 U	< 20.5 U	< 1.89 U	< 2.14 U	--	68.7	< 3.05 U	--	< 1.79 U	< 4.65 U
EHS-EF-KWING	EHS-122920-EF-KWING	K-Wing	12/29/2020		<5.9UJ	<5.9UJ	<5.9UJ	<3.9UJ	<3.9UJ	<3.9UJ	<3.9UJ	<3.9UJ	<4.5UJ	<4.4UJ	<14UJ	<4.4UJ	<7.5UJ	19J	<4.8UJ	<5.5UJ	<7.5UJ	<6.8UJ	4.9J	<4.0UJ	<42UJ
EHS-EF-KWING	EHS-040521-EF-KWING	K-Wing	4/5/2021		<5.6U	<5.6U	<5.6U	<3.8U	<3.8U	<3.7U	<3.7U	<3.7U	<4.3U	<4.2U	<13U	<4.2U	<18U	<4.0U	22J	<5.2U	8.8	<6.5U	18	<3.8U	<40U
EHS-EF-KWING	2107546_EHS-072221-EF-KWING	K-Wing	7/22/2021		<6.1U	<6.1U	<6.1U	<4.1U	<4.1U	<4U	<4U	<4U	<4.7U	<4.6U	<14U	<4.6U	<19U	<4.4U	<5U	<5.7U	140	<7.1U	92	<4.1U	<43U
EHS-EF-KWING	EHS-122121-EF-KWING	K-Wing	12/21/2021		<5.5U	<5.5U	<5.5U	<3.7U	<3.7U	<3.6U	<3.6U	<3.6U	<4.2U	<4.2U	<13U	<4.2U	<17U	<4.0U	<4.5U	<5.1U	59	<6.4U	<4.5U	<3.7U	<39U
EHS-EF-KWING	EHS-11102023-EF-KWING	K-Wing	11/10/2023	L2367767	< 5.02 U	< 5.02 U	< 5.02 U	< 3.38 U	< 3.38 U	< 3.31 U	< 3.31 U	< 3.31 U	< 3.86 U	< 3.79 U	--	< 3.79 U	--	< 3.63 U	--	--	95	--	--	--	--
EHS-EF-KWING	EHS-11112024-EF-KWING	K-Wing	11/11/2024	L2466355	< 2.8 U	< 2.8 U	< 2.8 U	< 1.88 U	< 1.88 U	< 1.84 U	< 1.84 U	< 1.84 U	< 2.15 U	< 2.11 U	< 1.68 U	< 2.11 U	< 21.9 U	< 2.02 U	< 2.29 U	--	46.1	< 3.25 U	--	< 1.91 U	< 4.96 U
EHS-EF-KWING	EHS-11112025-EF-KWING	K-Wing	11/11/2025	L2573524	< 2.48 U	< 2.48 U	< 2.48 U	< 1.67 U	< 1.67 U	< 1.64 U	< 1.64 U	< 1.64 U	< 1.91 U	< 1.87 U	< 1.49 U	< 1.87 U	< 19.4 U	< 1.79 U	< 2.03 U	--	35.8	< 2.89 U	--	< 1.69 U	< 4.41 U
EHS-EF-MUSIC	EHS-040521-EF-MUSIC	Music Wing	4/5/2021		<5.4U	<5.4U	<5.4U	<3.6U	<3.6U	<3.6U	<3.6U	<3.6U	<4.2U	<4.1U	<13U	<4.1U	22	<3.9U	<4.4U	<5.0U	<6.9U	<6.3U	38	<3.7U	<38U
EHS-EF-MUSIC	2107546_EHS-072221-EF-MUSIC	Music Wing	7/22/2021		<6.4U	<6.4U	<6.4U	<4.3U	<4.3U	<4.2U	<4.2U	<4.2U	<4.9U	<4.8U	<15U	<4.8U	<20U	<4.6U	<5.2U	<6U	<8.1U	<7.4U	69	<4.3U	<45U
EHS-EF-MUSIC	EHS-122121-EF-MUSIC	Music Wing	12/21/2021		<5.8U	<5.8U	<5.8U	<3.9U	<3.9U	<3.8U	<3.8U	<3.8U	<4.4U	<4.4U	<14U	<4.4U	26	<4.2U	<4.7U	<5.4U	<7.4U	<6.7U	28	<3.9U	<41U
EHS-EF-MUSIC	EHS-11102023-EF-MUSIC	Music Wing	11/10/2023	L2367767	< 2.59 U	< 2.59 U	< 2.59 U	< 1.74 U	< 1.74 U	< 1.71 U	< 1.71 U	< 1.71 U	< 1.99 U	< 1.96 U	--	< 1.96 U	--	14.8	--	--	< 3.3 U	--	--	--	--
EHS-EF-MUSIC	EHS-11112024-EF-MUSIC	Music Wing	11/11/2024	L2466355	< 2.71 U	< 2.71 U	< 2.71 U	< 1.82 U	< 1.82 U	< 1.78 U	< 1.78 U	< 1.78 U	< 2.08 U	< 2.04 U	< 1.62 U	< 2.04 U	41.5	2.94	3.8	--	< 3.45 U	< 3.15 U	--	< 1.84 U	< 4.8 U
EHS-EF-MUSIC	EHS-11112025-EF-MUSIC	Music Wing	11/11/2025	L2573524	< 2.45 U	< 2.45 U	< 2.45 U	< 1.65 U	< 1.65 U	< 1.62 U	< 1.62 U	< 1.62 U	< 1.89 U	< 1.85 U	< 1.47 U	< 1.85 U	< 19.2 U	< 1.77 U	< 2.01 U	--	< 3.13 U	< 2.85 U	--	< 1.67 U	< 4.35 U

Notes
µg/m3: microgram per cubic meter
Samples were analyzed via method TO-15
U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.
J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
UJ: The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

DRAFT

Table 6-1C
ISMP Post-Mitigation Monitoring Results for SSD Effluent - VOCs
2020-2025
Former Sperry Remington Site - North Portion
Elmira, New York

					Hexane	2-Hexanone (MBK)	Methyl Ethyl Ketone	Methylene Chloride	4-Methyl-2-pentanone	Methyl-tert-butyl ether	2-Propanol	Propylbenzene	Naphthalene	Styrene	Tertiary butyl alcohol (TBA)	Tetrahydrofuran	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	1,2,4-Trimethylbenzene
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3		ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample ID	Sample Name	Sample Location	Sample Date	Lab Report																					
EHS-EF-CAFAD	EHS-122920-EF-CAF-AD	Cafeteria (Addition)	12/29/2020		<3.8U	<17U	<12U	<37U	<4.4U	<15U	<10U	<5.2U	--	<4.5U	--	<3.1U	<7.3U	<7.2U	<4.0U	<32U	<5.8U	<5.8U	13	--	<5.2U
EHS-EF-CAFAD	EHS-040521-EF-CAF-AD	Cafeteria (Addition)	4/5/2021		<3.3U	<15U	<11U	<32U	<3.8U	<13U	<9.2U	<4.6U	--	<4.0U	--	2.8	<6.4U	<6.3U	<3.5U	<28U	<5.1U	<5.1U	14	--	<4.6U
EHS-EF-CAFAD	2107546_EHS-072221-EF-CAF-AD	Cafeteria (Addition)	7/22/2021		<14U	<66U	<47U	<140U	<16U	<58U	<39U	<20U	--	<17U	--	<12U	<28U	<27U	<15U	<120U	<22U	<22U	26	--	<20U
EHS-EF-CAFAD	EHS-122121-EF-CAFAD	Cafeteria (Addition)	12/21/2021		<3.1U	<14U	<10U	<30U	<3.6U	<13U	9.2	<4.3U	--	<3.7U	--	<2.6U	<6.0U	<6.0U	<3.3U	<26U	<4.8U	<4.8U	18	--	<4.3U
EHS-EF-CAFAD	EHS-11102023-EF-CAFAD	Cafeteria (Addition)	11/10/2023	L2367767	--	< 1.64 U	< 2.95 U	--	< 4.1 U	< 1.44 U	--	--	--	< 1.7 U	< 3.03 U	--	< 2.75 U	< 2.71 U	3.99	< 2.97 U	< 2.18 U	< 2.18 U	2.27	< 2.25 U	--
EHS-EF-CAFAD	EHS-11112024-EF-CAFAD	Cafeteria (Addition)	11/11/2024	L2466355	< 1.58 UJ	< 1.83 U	< 3.3 U	< 3.89 U	< 4.59 U	< 1.61 U	4.06	--	< 2.34 U	< 1.9 U	< 3.4 U	< 3.3 U	< 3.07 U	< 3.03 U	< 1.68 U	< 3.32 U	< 2.44 U	< 2.44 U	< 2.4 U	< 2.51 U	< 2.2 U
EHS-EF-CAFAD	EHS-11112025-EF-CAFAD	Cafeteria (Addition)	11/11/2025	L2573524	1.77	< 1.75 U	< 3.13 U	< 3.68 U	< 4.34 U	< 1.54 U	5.97	--	< 2.12 U	< 1.81 U	< 3.21 U	< 3.13 U	< 2.93 U	< 2.89 U	< 1.61 U	< 3.16 U	< 2.32 U	< 2.32 U	< 2.29 U	< 2.39 U	< 2.09 U
EHS-EF-CAFRET	EHS-122920-EF-CAF-RET	Cafeteria (Retrofit)	12/29/2020		<3.4UJ	<16UJ	<11UJ	<33UJ	<3.9UJ	<14UJ	9.3J	<4.7UJ	--	<4.1UJ	--	<2.8UJ	<6.6UJ	8.7J	<3.6UJ	<28UJ	<5.2UJ	<5.2UJ	<5.2UJ	--	<4.7UJ
EHS-EF-CAFRET	EHS-040521-EF-CAF RET	Cafeteria (Retrofit)	4/5/2021		<3.2U	<15U	<11U	<31U	<3.7U	<13U	<8.8U	<4.4U	--	<3.8U	--	<2.6U	<6.2U	<6.1U	<3.4U	<27U	<4.9U	<4.9U	<4.8U	--	<4.4U
EHS-EF-CAFRET	2107546_EHS-072221-EF-CAFRET	Cafeteria (Retrofit)	7/22/2021		<3.5U	<16U	<12U	<35U	<4.1U	<14U	<9.9U	<4.9U	--	<4.3U	--	<3U	<6.9U	<6.8U	<3.8U	<30U	<5.5U	<5.5U	<5.4U	--	<4.9U
EHS-EF-CAFRET	EHS-122121-EF-CAFRET	Cafeteria (Retrofit)	12/21/2021		<2.8UJ	<13UJ	<9.6UJ	<28UJ	<3.3UJ	<12UJ	<8.0UJ	<4.0UJ	--	<3.4UJ	--	<2.4UJ	<5.6UJ	<5.5UJ	<3.0UJ	<24UJ	<4.4UJ	<4.4UJ	<4.4UJ	--	<4.0UJ
EHS-EF-CAFRET	EHS-11102023-EF-CAFRET	Cafeteria (Retrofit)	11/10/2023	L2367767	--	< 1.74 U	< 3.13 U	--	< 4.34 U	< 1.53 U	--	--	--	< 1.81 U	< 3.21 U	--	< 2.91 U	< 2.88 U	3.84	< 3.15 U	< 2.31 U	< 2.31 U	15.6	< 2.38 U	--
EHS-EF-CAFRET	EHS-11112024-EF-CAFRET	Cafeteria (Retrofit)	11/11/2024	L2466355	< 1.51 UJ	< 1.75 U	< 3.16 U	< 3.72 U	< 4.39 U	< 1.54 U	5.28	--	< 2.24 U	< 1.82 U	< 3.24 U	< 3.16 U	< 2.94 U	< 2.9 U	< 1.61 U	< 3.18 U	< 2.34 U	< 2.34 U	16	< 2.41 U	< 2.1 U
EHS-EF-CAFRET	EHS-11112025-EF-CAFRET	Cafeteria (Retrofit)	11/11/2025	L2573524	< 1.46 U	< 1.69 U	< 3.04 U	< 3.58 U	< 4.22 U	< 1.49 U	< 5.09 U	--	< 2.06 U	< 1.76 U	< 3.12 U	< 3.04 U	< 2.84 U	< 2.8 U	< 1.56 U	< 3.07 U	< 2.25 U	< 2.25 U	15.2	< 2.32 U	< 2.03 U
EHS-EF-FWING	EHS-122920-EF-FWING	F-Wing	12/29/2020		<3.7U	<17U	<12U	<36U	<4.3U	<15U	<10U	<5.2U	--	<4.5U	--	5.5	<7.2U	<7.1U	<4.0U	<31U	<5.7U	<5.7U	270	--	<5.2U
EHS-EF-FWING	EHS-040521-EF-FWING	F-Wing	4/5/2021		<3.3U	<15U	<11U	<32U	<3.8U	<13	<9.2U	<4.6	--	<4	--	3.6	<6.4U	<6.3U	<3.5	<28U	<5.1U	<5.1U	220	--	<4.6U
EHS-EF-FWING	2107546_EHS-072221-EF-FWING	F-Wing	7/22/2021		<3.6U	<16U	<12U	<35U	<4.1U	<14U	16	<5U	--	<4.3U	--	<3U	<6.9U	<6.8U	<3.8U	<30U	<5.5U	<5.5U	26	--	<5U
EHS-EF-FWING	EHS-122121-EF-FWING	F-Wing	12/21/2021		<3.4U	<16U	<11U	<33U	<3.9U	<14U	<9.4U	<4.7U	--	<4.1U	--	<2.8U	<6.6U	<6.5U	<3.6U	<28U	<5.2U	<5.2U	360	--	<4.7U
EHS-EF-FWING	EHS-11102023-EF-FWING	F-Wing	11/10/2023	L2367767	--	< 3.64 U	< 6.55 U	--	< 9.1 U	< 3.2 U	--	--	--	< 3.78 U	< 6.73 U	--	< 6.09 U	< 6.01 U	8.48	< 6.58 U	< 4.84 U	< 4.84 U	339	< 4.98 U	--
EHS-EF-FWING	EHS-11112024-EF-FWING	F-Wing	11/11/2024	L2466355	< 1.64 UJ	< 1.93 U	3.6	< 4.1 U	< 4.84 U	< 1.7 U	4.89	--	< 2.47 U	< 2.01 U	< 3.58 U	< 3.48 U	< 3.24 U	< 3.2 U	4.71	< 3.5 U	< 2.58 U	< 2.58 U	246	< 2.65 U	9.09
EHS-EF-FWING	EHS-11112025-EF-FWING	F-Wing	11/11/2025	L2573524	1.92	< 1.68 U	< 3.04 U	< 3.58 U	< 4.22 U	< 1.48 U	< 5.04 U	--	< 2.04 U	< 1.75 U	< 3.12 U	< 3.04 U	< 2.82 U	< 2.79 U	< 1.55 U	< 3.05 U	< 2.24 U	< 2.24 U	303	< 2.31 U	< 2.02 U
EHS-EF-GYM	EHS-122920-EF-GYM	Gymnasium	12/29/2020		<3.7U	<17U	<12U	<36U	<4.3U	<15U	16	<5.1U	--	<4.4U	--	<3.1U	<7.2U	<7.1U	<3.9U	<31U	<5.7U	<5.7U	11	--	<5.1U
EHS-EF-GYM	EHS-040521-EF-GYM	Gymnasium	4/5/2021		<3.4U	<16U	<11U	<34U	<4.0U	<14U	18	<4.8U	--	<4.1U	--	4.6	<6.6U	<6.6U	<3.6U	<29U	<5.3U	<5.3U	11	--	<4.8U
EHS-EF-GYM	2107546_EHS-072221-EF-GYM	Gymnasium	7/22/2021		<36U	<170U	<120U	<360U	<42U	<150U	<100U	<51U	--	<44U	--	<30U	<71U	<70U	<39U	<310U	<56U	<56U	<56U	--	<51U
EHS-EF-GYM	EHS-122121-EF-GYM	Gymnasium	12/21/2021		<3.4U	<16U	<11U	<33U	<3.9U	<14U	<9.4U	<4.7U	--	<4.1U	--	<2.8U	<6.6U	<6.5U	<3.6U	<28U	<5.2U	<5.2U	17	--	<4.7U
EHS-EF-GYM	EHS-11102023-EF-GYM	Gymnasium	11/10/2023	L2367767	--	< 1.75 U	4.63	--	< 4.39 U	< 1.54 U	--	--	--	< 1.82 U	< 3.24 U	--	< 2.94 U	< 2.9 U	6.26	< 3.18 U	< 2.34 U	< 2.34 U	3.44	< 2.41 U	--
EHS-EF-GYM	EHS-11112024-EF-GYM	Gymnasium	11/11/2024	L2466355	< 0.589 UJ	< 1.84 U	< 3.33 U	< 3.93 U	< 4.63 U	< 1.62 U	6.24	--	< 2.36 U	< 1.92 U	< 3.43 U	< 3.33 U	< 3.09 U	< 3.05 U	< 1.7 U	< 3.34 U	< 2.46 U	< 2.46 U	< 2.42 U	< 2.53 U	< 2.21 U
EHS-EF-GYM	EHS-11112025-EF-GYM	Gymnasium	11/11/2025	L2573524	< 1.54 U	< 1.79 U	9.08	< 3.79 U	< 4.47 U	< 1.57 U	< 5.36 U	--	< 2.17 U	< 1.86 U	< 3.3 U	< 3.21 U	< 2.99 U	< 2.96 U	3.67	< 3.24 U	< 2.38 U	< 2.38 U	98.9	< 2.45 U	< 2.14 U
EHS-EF-KWING	EHS-122920-EF-KWING	K-Wing	12/29/2020		<3.4UJ	<16UJ	<12UJ	<34UJ	<4.0UJ	<14UJ	<9.6UJ	<4.8UJ	--	<4.2UJ	--	<2.9UJ	<6.7UJ	<6.6UJ	<3.7UJ	<29UJ	<5.3UJ	<5.3UJ	7.5J	--	<4.8UJ
EHS-EF-KWING	EHS-040521-EF-KWING	K-Wing	4/5/2021		<3.3U	<15U	<11U	<32U	<3.8U	<13U	41	<4.6U	--	<4.0U	--	3	<6.4U	<6.3U	<3.5U	<28U	<5.1U	<5.1U	20	--	30
EHS-EF-KWING	2107546_EHS-072221-EF-KWING	K-Wing	7/22/2021		<3.6U	<16U	<12U	<35U	<4.1U	<14U	16	<5U	--	<4.3U	--	<3U	<6.9U	<6.8U	<3.8U	<30U	<5.5U	<5.5U	26	--	<5U
EHS-EF-KWING	EHS-122121-EF-KWING	K-Wing	12/21/2021		<3.2U	<15U	<11U	<32U	<3.7U	<13U	<9.0U	<4.5U	--	<3.9U	--	<2.7U	<6.3U	<6.2U	<3.4U	<27U	<5.0U	<5.0U	18	--	<4.5U
EHS-EF-KWING	EHS-11102023-EF-KWING	K-Wing	11/10/2023	L2367767	--	< 3.42 U	< 6.16 U	--	< 8.57 U	< 3.01 U	--	--	--	< 3.56 U	< 6.34 U	--	< 5.73 U	< 5.66 U	< 3.15 U	< 6.2 U	< 4.56 U	< 4.56 U	18.6	< 4.69 U	--
EHS-EF-KWING	EHS-11112024-EF-KWING	K-Wing	11/11/2024	L2466355	< 1.64 UJ	< 1.91 U	< 3.42 U	< 4.03 U	< 4.75 U	< 1.68 U	6.93	--	< 2.44 U	< 1.98 U	< 3.52 U	< 3.42 U	< 3.19 U	< 3.15 U	< 1.75 U	< 3.45 U	< 2.54 U	< 2.54 U	18.3	< 2.61 U	3.28
EHS-EF-KWING	EHS-11112025-EF-KWING	K-Wing	11/11/2025	L2573524	1.87	< 1.69 U	< 3.04 U	< 3.58 U	< 4.22 U	< 1.49 U	6.91	--	< 2.06 U	< 1.76 U	< 3.12 U	< 3.04 U	< 2.84 U	< 2.8 U	< 1.56 U	< 3.07 U	< 2.25 U	< 2.25 U	16.3	< 2.32 U	< 2.03 U
EHS-EF-MUSIC	EHS-040521-EF-MUSIC	Music Wing	4/5/2021		<3.2U	<15U	<11U	<31U	<3.7U	<13U	89	<4.4U	--	<3.8U	--	3.4	<6.2U	<6.1U	<3.4U	<27U	<4.9U	<4.9U	15	--	<4.4U
EHS-EF-MUSIC	2107546_EHS-072221-EF-MUSIC	Music Wing	7/22/2021		<3.7U	<17U	<12U	<37U	<4.3U	<15U	10	<5.2U	--	<4.5U	--	<3.1U	<7.3U	<7.2U	<4U	<31U	<5.8U	<5.8U	20	--	<5.2U
EHS-EF-MUSIC	EHS-122121-EF-MUSIC	Music Wing	12/21/2021		<3.4U	<16U	<11U	<33U	<3.9U	<14U	<9.4U	<4.7U	--	<4.1U	--	<2.8U	<6.6U	<6.5U	<3.6U	<28U	<5.2U	<5.2U	21	--	<4.7U
EHS-EF-MUSIC	EHS-11102023-EF-MUSIC	Music Wing	11/10/2023	L2367767	--	< 1.77 U	< 3.19 U	--	< 4.43 U	< 1.55 U	--	--	--	< 1.84 U	< 3.27 U	--	< 2.96 U	< 2.92 U	11.7	< 3.2 U	< 2.35 U	< 2.35 U	16.3	< 2.42 U	--
EHS-EF-MUSIC	EHS-11112024-EF-MUSIC	Music Wing	11/11/2024	L2466355	< 0.589 UJ	< 1.84 U	4.13	< 3.93 U	< 4.63 U	< 1.62 U	7.57	--	< 2.36 U	< 1.92 U	< 3.43 U	< 3.33 U	< 3.09 U	< 3.05 U	5.28	< 3.34 U	< 2.46 U	< 2.46 U	10.5	< 2.53 U	7.92
EHS-EF-MUSIC	EHS-11112025-EF-MUSIC	Music Wing	11/11/2025	L2573524	< 1.44 U	< 1.67 U	< 3.01 U	< 3.54 U	< 4.18 U	< 1.47 U	< 5.01 U	--	< 2.03 U	< 1.74 U	< 3.09 U	< 3.01 U	< 2.8 U	< 2.77 U	< 1.54 U	< 3.03 U	< 2.23 U	< 2.23 U	14.9	< 2.29 U	< 2.01 U

Notes
µg/m3: microgram per cubic meter
Samples were analyzed via method TO-15
U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.
J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
UJ: The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

DRAFT

Table 6-1C
ISMP Post-Mitigation Monitoring Results for SSD Effluent - VOCs
2020-2025
Former Sperry Remington Site - North Portion
Elmira, New York

					1,3,5-Trimethylbenzene	2,2,4-Trimethylpentane	Vinyl chloride	Xylene (m)	Xylene (o)
					ug/m3	ug/m3	ug/m3	ug/m3	ug/m3
Sample ID	Sample Name	Sample Location	Sample Date	Lab Report					
EHS-EF-CAFAD	EHS-122920-EF-CAF-AD	Cafeteria (Addition)	12/29/2020		<5.2U	62	<2.7U	<4.6U	<4.6U
EHS-EF-CAFAD	EHS-040521-EF-CAF-AD	Cafeteria (Addition)	4/5/2021		<4.6U	<4.4U	<2.4U	<4.1U	<4.1U
EHS-EF-CAFAD	2107546 EHS-072221-EF-CAF-AD	Cafeteria (Addition)	7/22/2021		<20U	<19U	<10U	<17U	<17U
EHS-EF-CAFAD	EHS-122121-EF-CAFAD	Cafeteria (Addition)	12/21/2021		<4.3U	<4.1U	<2.2U	<3.8U	<3.8U
EHS-EF-CAFAD	EHS-11102023-EF-CAFAD	Cafeteria (Addition)	11/10/2023	L2367767	--	--	< 1.02 U	25.7	10.6
EHS-EF-CAFAD	EHS-11112024-EF-CAFAD	Cafeteria (Addition)	11/11/2024	L2466355	< 2.2 U	< 2.09 U	< 1.14 U	< 3.88 U	< 1.94 U
EHS-EF-CAFAD	EHS-11112025-EF-CAFAD	Cafeteria (Addition)	11/11/2025	L2573524	< 2.09 U	< 1.99 U	< 1.09 U	< 3.7 U	< 1.85 U
EHS-EF-CAFRET	EHS-122920-EF-CAF-RET	Cafeteria (Retrofit)	12/29/2020		<4.7UJ	<4.5UJ	<2.4UJ	<4.2UJ	<4.2UJ
EHS-EF-CAFRET	EHS-040521-EF-CAF RET	Cafeteria (Retrofit)	4/5/2021		<4.4U	<4.2U	<2.3U	<3.9U	<3.9U
EHS-EF-CAFRET	2107546 EHS-072221-EF-CAF-RET	Cafeteria (Retrofit)	7/22/2021		<4.9U	<4.7U	<2.6U	<4.4U	<4.4U
EHS-EF-CAFRET	EHS-122121-EF-CAFRET	Cafeteria (Retrofit)	12/21/2021		<4.0UJ	<3.8UJ	<2.1UJ	<3.5UJ	<3.5UJ
EHS-EF-CAFRET	EHS-11102023-EF-CAFRET	Cafeteria (Retrofit)	11/10/2023	L2367767	--	--	< 1.08 U	24.2	9.82
EHS-EF-CAFRET	EHS-11112024-EF-CAFRET	Cafeteria (Retrofit)	11/11/2024	L2466355	< 2.1 U	< 2 U	< 1.09 U	< 3.71 U	< 1.86 U
EHS-EF-CAFRET	EHS-11112025-EF-CAFRET	Cafeteria (Retrofit)	11/11/2025	L2573524	< 2.03 U	< 1.93 U	< 1.06 U	< 3.59 U	< 1.79 U
EHS-EF-FWING	EHS-122920-EF-FWING	F-Wing	12/29/2020		<5.2U	<4.9U	<2.7U	<4.6U	<4.6U
EHS-EF-FWING	EHS-040521-EF-FWING	F-Wing	4/5/2021		<4.6U	<4.4U	<2.4U	<4.1	<4.1
EHS-EF-FWING	2107546 EHS-072221-EF-FWING	F-Wing	7/22/2021		<5U	<4.7U	<2.6U	<4.5U	<4.4U
EHS-EF-FWING	EHS-122121-EF-FWING	F-Wing	12/21/2021		<4.7U	<4.5U	<2.4U	<4.2U	<4.2U
EHS-EF-FWING	EHS-11102023-EF-FWING	F-Wing	11/10/2023	L2367767	--	--	< 2.27 U	56	21.5
EHS-EF-FWING	EHS-11112024-EF-FWING	F-Wing	11/11/2024	L2466355	< 2.32 U	13.4	< 1.21 U	12.6	6.47
EHS-EF-FWING	EHS-11112025-EF-FWING	F-Wing	11/11/2025	L2573524	< 2.02 U	< 1.92 U	< 1.05 U	< 3.57 U	< 1.79 U
EHS-EF-GYM	EHS-122920-EF-GYM	Gymnasium	12/29/2020		<5.1U	<4.9U	3.1	<4.5U	<4.5U
EHS-EF-GYM	EHS-040521-EF-GYM	Gymnasium	4/5/2021		<4.8U	<4.5U	<2.5U	<4.2U	<4.2U
EHS-EF-GYM	2107546 EHS-072221-EF-GYM	Gymnasium	7/22/2021		<51U	<48U	<26U	<45U	<45U
EHS-EF-GYM	EHS-122121-EF-GYM	Gymnasium	12/21/2021		<4.7U	<4.5U	<2.4U	<4.2U	<4.2U
EHS-EF-GYM	EHS-11102023-EF-GYM	Gymnasium	11/10/2023	L2367767	--	--	< 1.09 U	35.2	14
EHS-EF-GYM	EHS-11112024-EF-GYM	Gymnasium	11/11/2024	L2466355	< 2.21 U	< 2.1 U	< 1.15 U	< 3.91 U	< 1.95 U
EHS-EF-GYM	EHS-11112025-EF-GYM	Gymnasium	11/11/2025	L2573524	< 2.14 U	< 2.04 U	1.72	5.26	< 1.89 U
EHS-EF-KWING	EHS-122920-EF-KWING	K-Wing	12/29/2020		<4.8UJ	<4.6UJ	<2.5UJ	<4.2UJ	<4.2UJ
EHS-EF-KWING	EHS-040521-EF-KWING	K-Wing	4/5/2021		15	<4.4U	<2.4U	22	14
EHS-EF-KWING	2107546 EHS-072221-EF-KWING	K-Wing	7/22/2021		<5U	<4.7U	<2.6U	<4.4U	<4.4U
EHS-EF-KWING	EHS-122121-EF-KWING	K-Wing	12/21/2021		<4.5U	<4.3U	<2.3U	<4.0U	<4.0U
EHS-EF-KWING	EHS-11102023-EF-KWING	K-Wing	11/10/2023	L2367767	--	--	< 2.13 U	< 7.25 U	< 3.63 U
EHS-EF-KWING	EHS-11112024-EF-KWING	K-Wing	11/11/2024	L2466355	< 2.29 U	< 2.17 U	< 1.19 U	< 4.04 U	< 2.02 U
EHS-EF-KWING	EHS-11112025-EF-KWING	K-Wing	11/11/2025	L2573524	< 2.03 U	< 1.93 U	< 1.06 U	< 3.59 U	< 1.79 U
EHS-EF-MUSIC	EHS-040521-EF-MUSIC	Music Wing	4/5/2021		<4.4U	<4.2U	<2.3U	<3.9U	<3.9U
EHS-EF-MUSIC	2107546 EHS-072221-EF-MUSIC	Music Wing	7/22/2021		<5.2U	<5U	<2.7U	<4.6U	<4.6U
EHS-EF-MUSIC	EHS-122121-EF-MUSIC	Music Wing	12/21/2021		<4.7U	<4.5U	<2.4U	<4.2U	<4.2U
EHS-EF-MUSIC	EHS-11102023-EF-MUSIC	Music Wing	11/10/2023	L2367767	--	--	< 1.1 U	73.8	30.1
EHS-EF-MUSIC	EHS-11112024-EF-MUSIC	Music Wing	11/11/2024	L2466355	< 2.21 U	19.2	< 1.15 U	11.9	6.47
EHS-EF-MUSIC	EHS-11112025-EF-MUSIC	Music Wing	11/11/2025	L2573524	< 2.01 U	< 1.91 U	< 1.04 U	< 3.54 U	< 1.77 U

Notes
µg/m3: microgram per cubic meter
Samples were analyzed via method TO-15
U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.
J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
UJ: The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

DRAFT

TABLE 6-1D
ISMP Post-Mitigation Monitoring Results for SSD Effluent - PCBs
Former Sperry Remington Site - North Portion #c808022
Elmira, NY

		Location	Gymnasium Effluent		K Wing Effluent		Cafeteria Retrofit Effluent		Cafeteria Addition Effluent		F Wing Effluent		Music Room Effluent	
		Field ID	07/31/21_SSHS-EHS-GYM ROOF	EHS-12292021-EF-GYM	07/31/21_SSHS-EHS-K WING ROOF	EHS-12292021-EF-KWING	07/31/21_SSHS-EHS-CAF ROOF	EHS-12292021-EF-CAFRET	07/31/21_SSHS-EHS-WEST CAFE ROOF	EHS-12292021-EF-CAFAD	SSHS-IRM5-T1 Room 127	EHS-12292021-EF-FWING	SSHS-IRM5-T2 Room 148	EHS-12292021-EF-MUSIC
		Sample Date	7/31/2021	12/29/2021	7/31/2021	12/29/2021	7/31/2021	12/29/2021	7/31/2021	12/29/2021	8/8/2021	12/29/2021	8/8/2021	1/1/2022
Chemical	Units	USEPA Exposure Level for School Indoor Air*												
Aroclor 1016	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1221	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1232	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1242	µg/m^3 PUF	0.1	0.048J	<0.034U	<0.007J	<0.035U	<0.012J	<0.035U	0.052J	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1248	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1254	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1260	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1262	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U
Aroclor 1268	µg/m^3 PUF	0.1	<0.013U	<0.034U	<0.013U	<0.035U	<0.013U	<0.035U	<0.013U	<0.035U	<0.037UJ	<0.036U	<0.037UJ	<0.083U

Notes:

µg/m^3: microgram per cubic meter
Samples were analyzed via method TO-10A
U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.

J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
PCB: polychlorinated biphenyl

Effluent PCB data were reported by the laboratory as "PCB-XXXX" but are presented here as "Aroclor XXXX".

* source - Exposure Levels for Evaluating Polychlorinated Biphenyls (PCBs) in Indoor School Air | US EPA

DRAFT

TABLE 6-1E
Summary of Post-Mitigation PCB Monitoring Results for Indoor and Outdoor Air

Former Sperry Remington – North Portion #c808022
Elmira, New York

	Location	Cafeteria		Gymnasium		K Wing		Locker Room		Room 127		Room 148		Outdoor	
	Field ID	07/31/21_SSHS-EHS-CAF	200-61637-1_SSHS-CAFETERIA 01012022	07/31/21_SSHS-EHS-GYM	200-61637-1_SSHS-GYM 01012022	07/31/21_SSHS-EHS-K-WING	200-61637-1_SSHS-KWING 01012022	07/31/21_SSHS-EHS-BOYS LOCKER ROOM	200-61637-1_SSHS-LOCKER ROOM 01012022	07/31/21_SSHS-EHS-ROOM 127	200-61637-1_SSHS-ROOM 127 01012022	07/31/21_SSHS-EHS-ROOM 148	200-61637-1_SSHS-ROOM 148 01012022	07/31/21_SSHS-EHS-OUTDOOR	200-61637-1_SSHS-MAN LIFT 01012022
	Sample Date	7/31/2021	1/1/2022	7/31/2021	1/1/2022	7/31/2021	1/1/2022	7/31/2021	1/1/2022	7/31/2021	1/1/2022	7/31/2021	1/1/2022	7/31/2021	1/1/2022
Chemical ($\mu g/m^3$)	USEPA Exposure Level for School Indoor Air*														
Aroclor 1016	0.1	<0.00096U	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1221	0.1	<0.00096U	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1232	0.1	<0.00096U	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1242	0.1	0.0026J	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1248	0.1	<0.00096U	0.00068J	0.0011J	0.00076J	0.0023J	0.0013J	0.0035J	0.0024J	0.0030J	0.0011J	0.0018J	0.00042J	0.0010J	0.00035J
Aroclor 1254	0.1	<0.00096U	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1260	0.1	<0.00096U	<0.00096U	<0.00055J	<0.001U	0.0013J	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1262	0.1	<0.00096U	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U
Aroclor 1268	0.1	<0.00096U	<0.00096U	<0.00083U	<0.001U	<0.00093U	<0.00094U	<0.00098U	<0.001U	<0.001U	<0.00078U	<0.00082U	<0.00096U	<0.00092U	<0.00095U

Notes:
Samples were analyzed via method TO-4A.
Concentrations in micrograms per cubic meter ($\mu g/m^3$).
PCB: polychlorinated biphenyl
U: The analyte was analyzed for, but was not detected at or above the reported quantitation limit.
J: The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
Effluent PCB data were reported by the laboratory as "PCB-XXXX" but are presented here as "Aroclor XXXX".
* source - Exposure Levels for Evaluating Polychlorinated Biphenyls (PCBs) in Indoor School Air | US EPA

DRAFT

Notes

PCBs - Polychlorinated Biphenyls
SVOCs - Semivolatile Organic Compounds
VOCs - Volatile Organic Compounds
PAH - Polycyclic Aromatic Hydrocarbons
PFAS - Per- and Polyfluoroalkyl Substances
µg/kg - micrograms per kilogram
mg/kg - milligrams per kilogram
ft bgs - Feet Below Ground Surface
ft bfg - Feet Below Final Grade
-- Sample was not within Final Grade limits or located beneath field house and unable to be surveyed or verified
^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA, DLCK or MRL standard: Instrument related QC is outside acceptance limits.
^+ - Continuing Calibration Verification (CCV) is outside acceptance limits, high biased.
* - LCS or LCSD is outside acceptance limits
*+ - LCS and/or LCSD is outside acceptance limits, high biased
*1 - LCS/LCSD RPD exceeds control limits
*3 - ISTD response or retention time outside acceptable limits
B - Compound detected in method blank
E - Exceeds instrument calibration range.
F1 - MS and/or MSD Recovery is outside acceptance limits.
F2 - MS/MSD RPD exceeds control limits
H - Sample was received and analyzed past holding time.
I - Value is EMPC (estimated maximum possible concentration)
EMPC - Estimated maximum possible concentration
p - The %RPD between the primary and confirmation column/detector is >40%. The lower value has been reported
J- - The analyte was positively identified; however, the associated numerical value is likely to be lower than the concentration of the analyte in the sample due to negative bias of associated QC or calibration data or attributable to matrix interference
J+ - The analyte was positively identified; however, the associated numerical value is likely to be higher than the concentration of the analyte in the sample due to positive bias of associated QC or calibration data or attributable to matrix interference.
J - Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
R - The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence
T - Indicates that a quality control parameter has exceeded laboratory limits
U - non-detect at the value indicated
UJ - The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
Samples collected by NYSDEC in "May-October 2000 NYSDEC Sampling Report" included sample depths as "surface". These samples are assumed to have been collected from 0-0.5 ft bgs.

[1] - Ground surface elevation at the time of sampling is only provided for soil boring locations

[2] - Final grade elevation provided for samples remaining in place. Final grade elevations were not collected for samples outside of the BCP Boundary and are denoted as "--"

[3] - Change in surface elevation calculates for soil boring locations that have not been excavated. Positive values indicate net increase in ground surface elevation, negative values indicate net decrease in ground surface elevation.

[4] - Grab sample elevation provided for IRM and ISMP sample locations. Elevation represents point at which grab sample was collected.

[5] - Sample depth at time of sampling provided for grab samples and soil boring. For IRM/ISMP samples, sample depth at time of sampling represents the depth interval in which the associated grab sample was collected within. For soil borings, sample depth at time of sampling represents the depth interval from which a composite sample was collected.

[6] - Sample depth from final grade calculated for both IRM/ISMP and soil boring sample locations left in place (not excavated). Sample depth from final grade calculated for IRM/ISMP sample locations by comparing sample elevation to final grade elevation (i.e., final grade elevation of 857.18 ft amsl minus sample elevation of 847.44 ft amsl equals sample depth below final grade of 9.74 ft below final grade). Sample depth from final grade calculated for boring locations by comparing surface elevation at the time of sampling to the final grade elevation and correcting sample depths based on alterations to ground surface elevation (i.e., Surface elevation at time of sampling of 853.54 ft amsl and final grade elevation of 855.13 ft amsl indicates surface elevation increased 1.59 ft after sample collection. A sample previously collected at this location from 12-14 ft below ground surface [at the time of sampling] is now located 13.59-15.59 ft below final grade.)

[7] - For excavation status, soil boring samples that did not have their entire composite depth excavated are denoted as "Not Excavated" (i.e., sample depths only partially excavated are shown as left in place)
Lab method used: 8082A/ SW8082A - PCBs
Lab method used: 6010C/SW6010C/SW6010D - Metals, SW6020B - Manganese, SW7470A/SW7471B - Mercury
Lab method used: 8270D/SW8270D/8270D_LL/SW8270E/8270E-LL - SVOCs
Lab method used: 8260C/SW8260C/8260C_LL/SW8260D - VOCs
Lab Method used: E537(M)/PFC_IDA - PFAS
Soil Cleanup Objectives presented derived from 6 NYCRR PART 375 Table 375-6-8(b) (May 2023)
Analyte concentrations detected above Unrestricted Soil Cleanup Objectives are presented in light gray
Analyte concentrations detected above Restricted Residential Soil Cleanup Objectives are presented in dark gray
Analyte concentrations detected above Protection of Groundwater Soil Cleanup Objectives are presented in blue font
Analyte concentrations with potential to exhibit the characteristic of toxicity for metals are presented in black
Analyte concentrations detected above New York State Hazardous Waste Criteria are presented in black with red text

DRAFT

TABLE 6-2A
Shallow Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
EHS Building	SSHS-B4SS-A	SSHS-B4SS-A-SS	7/22/2014	855.50	-	-	-	0 - 0.17 ft	0 - 0.17 ft	180-35079-1	Not Excavated	ND	< 0.0014 U	< 0.0018 U	< 0.0016 U	< 0.0015 U	< 0.00088 U	< 0.0013 U	< 0.0013 U	< 0.002 U	< 0.0012 U
EHS Building	SSHS-B2SS	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated	14					14				
EHS Building	SSHS-B3SS	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated	14					14				
EHS Building	SSHS-B4SS	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	3.5					3.5				
EHS Building	SSHS-B7SS	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	11					11				
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	14					14				
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	14					14				
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	11					11				
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	11					11				
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	9.5					9.5				
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	8.4					8.4				
EHS Building	SSHS-B4S	B4-C1-Composite	7/25/2007	-	-	-	-	0.5 - 2 ft	0.5 - 2 ft	-	Not Excavated	3.5	< U	< U	< U	< U	3.5	< U	< U		
EHS Building	SSHS-B3S	B3-C1-Composite	7/25/2007	855.70	855.70	0.00	-	0.5 - 2 ft	0.5 - 2 ft	NA	Not Excavated	32	< U	< U	< U	< U	32	< U	< U		
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	0.23	< 0.0073 U	< 0.014 U	< 0.013 U	< 0.013 U	0.07	0.16	< 0.0064 U	< 0.016 U	< 0.011 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-Dup-05	3/12/2026	-	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-Dup-03	3/12/2026	-	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-09	3/12/2026	-	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-06	3/12/2026	-	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17	3/12/2026	-	855.634	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17	3/12/2026	-	855.477	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17	3/12/2026	-	855.432	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17	3/12/2026	-	855.487	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17	3/12/2026	-	855.149	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17	3/12/2026	-	854.854	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17	3/12/2026	-	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17	3/12/2026	-	855.093	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	ND	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17	3/12/2026	-	855.294	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17	3/12/2026	-	855.109	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17	3/12/2026	-	855.637	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17	3/12/2026	-	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17	3/12/2026	-	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17	3/12/2026	-	855.244	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17	3/12/2026	-	855.161	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17	3/12/2026	-	855.946	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17	3/12/2026	-	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13	3/13/2026	-	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11	3/13/2026	-	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17	3/13/2026	-	855.427	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	0.298	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	0.21	0.088	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17	3/13/2026	-	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17	3/13/2026	-	853.99	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17	3/13/2026	-	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17	3/13/2026	-	855.022	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17	3/13/2026	-	855.457	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	ND	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.021 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17	3/13/2026	-	856.04	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 UT	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17	3/13/2026	-	855.919	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17	3/13/2026	-	855.626	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	0.015	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	0.015 J	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17	3/13/2026	-	855.696	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	SSHS-B457	SSHS-B457-SUB-0-2	8/30/2016	855.74	855.74	0.00	-	0 - 2 ft	0-2 ft	180-58129-1	Not Excavated	0.038	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.022 J	0.016 J	< 0.0062 U	< 0.0056 U	< 0.0034 U
Football Field	IRM4-S018	SSHS-IRM4-S018-0-2	7/15/2020	-	855.71	-	854.07	0 - 2 ft	1.64 ft	1801083161	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4-S019	SSHS-IRM4-S019-0-2	7/15/2020	-	855.68	-	854.02	0 - 2 ft	1.66 ft	1801083161	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM4-S021	SSHS-IRM4-S021-0-2	7/15/2020	-	855.65	-	854.93	0 - 2 ft	0.73 ft	1801083161	Not Excavated	9.67	< 0.058 U	< 0.063 U	< 0.044 U	< 0.026 U	6.7	2.7	0.27	< 0.063 U	< 0.024 U
Football Field	IRM4-S183S	SSHS-IRM4-S183S	8/13/2020	-	855.60	-	853.95	0 - 2 ft	1.65 ft	1801095841	Not Excavated	4.86	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.3	1.4	0.16	< 0.0064 U	< 0.0024 U
Football Field	IRM4A-S033	SSHS-IRM4A-S033-0-2	11/18/2020	-	855.92	-	854.24	0 - 2 ft	1.68 ft	1801138131	Not Excavated	0.836	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.52	0.27	0.046	< 0.0064 U	< 0.0025 U
Football Field	IRM5-S018A	SSHS-IRM5-S018A	2/25/2021	-	856.34	-	854.42	0 - 2 ft	1.92 ft	1801176021	Not Excavated	0.449	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.19	0.2	0.059	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B082A	SSHS-IRM5-B082A	4/14/2021	-	854.82	-	853.13	0 - 2 ft	1.69 ft	1801199781	Not Excavated	0.018	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.018 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	0.173	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.06	0.092	0.021	< 0.0061 U	< 0.0023 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	0.071	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.048	0.023	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	0.67	< 0.0059	< 0.0064	< 0.0044	< 0.0027	0.29	0.26	0.12	< 0.0064	< 0.0024
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	ND	< 0.0056	< 0.0061	< 0.0042	< 0.0025	< 0.0041	< 0.0052	< 0.0049	< 0.0061	< 0.0023
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	0.099	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.055	0.044	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S008	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	0.112	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.057	0.038	0.017 J	< 0.0069 U	< 0.0026 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	0.214	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.14	0.074	< 0.0066 U	< 0.0025 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	1.01	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.34	0.47	0.2	< 0.0060 U	< 0.0023 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	8.44	< 0.057 U	< 0.062 U	< 0.043 U	< 0.026 U	5.9	2.2	0.34	< 0.061 U	< 0.023 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	1.047	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.54	0.43	0.077	< 0.0061 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	0.0251	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.017 J	0.0081 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	0.114	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.067	0.037	0.01 J	< 0.0060 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	0.165	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.089	0.059	0.017 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	0.064	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.044	0.02	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	0.03	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.03	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	0.232	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.083	0.11	0.039	< 0.0061 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	0.033	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.033	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	0.0126	< 0.00058 U	< 0.00063 U	< 0.00043 U	< 0.00026 U	0.0053	0.0073	< 0.00050 U	< 0.00062 U	< 0.00024 U

												PCBs							
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-10	3/12/2026	-	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV9	SSHS-IRM5-Dup-01	3/12/2026	-	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1	3/12/2026	-	855.634	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1	3/12/2026	-	855.477	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1	3/12/2026	-	855.432	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1	3/12/2026	-	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.012	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	0.012 J	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1	3/12/2026	-	855.149	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.049	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	0.018 J	0.031	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1	3/12/2026	-	854.854	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	0.03	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	0.018 J	0.012 J	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1	3/12/2026	-	855.217	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1	3/12/2026	-	855.093	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	0.046	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	0.046	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1	3/12/2026	-	855.294	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	-	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1	3/12/2026	-	855.637	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1	3/12/2026	-	855.502	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1	3/12/2026	-	855.412	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	0.602	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	0.4	0.16	0.042	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1	3/12/2026	-	855.244	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1	3/12/2026	-	855.161	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1	3/12/2026	-	855.946	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1	3/12/2026	-	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15	3/13/2026	-	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1	3/13/2026	-	855.427	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1	3/13/2026	-	855.257	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1	3/13/2026	-	853.99	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1	3/13/2026	-	853.847	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1	3/13/2026	-	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.0284	< 0.019 U	< 0.019 U	< 0.019 U	0.0062 JP	< 0.019 U	0.014 J	0.0082 JP	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1	3/13/2026	-	855.457	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1	3/13/2026	-	856.04	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	ND	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1	3/13/2026	-	855.919	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1	3/13/2026	-	855.626	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1	3/13/2026	-	855.696	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	ND	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2385	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated	1.51	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.012 U	< 0.017 U	1.2	0.31	< 0.015 U	< 0.01 U
Football Field	SSHS-B2386	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated	0.088	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.071	0.017 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	1.78	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.1 J	0.58 J	0.1 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated	0.031	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.016 J	0.015 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	0.15	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.075 J	0.055 J	0.02 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated	0.408	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.23 J	0.14 J	0.038 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	0.235	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.13 J	0.086 J	0.019 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3500	SSHS-B3500-SUB-0.17-2	8/31/2020	856.02	856.02	0.00	-	0.17 - 2 ft	0.17-2 ft	180-110264-1	Not Excavated	0.16	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.067 J	0.064 J	0.029 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3501	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-0.17-2	9/23/2021	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	0.012	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	0.012 J	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	0.0248	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	0.015 J	0.0098 J	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	0.611	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	0.34	0.23	0.041	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	0.0079	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	0.0079 J	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	ND	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	0.116	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	0.068	0.036	0.012 J	< 0.018 U	< 0.018 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	0.043	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	0.012 J	0.016 J	0.015 J	< 0.017 U	< 0.017 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	0.0063	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	0.0063 J	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	ND	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	ND	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.018 U
Football Field	SSHS-B410	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated	0.386	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.034 U	0.2 J	0.14 J	0.046 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0095 U

TABLE 6-2A
Shallow Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2025	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated	0.456	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.068	0.29	0.098	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated	0.444	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.1	0.27	0.074	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2916	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated	0.94	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.94	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	0.131	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.1	0.031	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	0.227	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.19	0.037	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	0.023	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.023	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	0.057	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.047	0.01 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	0.0092	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0092 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	0.094	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.04	0.039	0.015 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	0.012	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.012 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	0.0331	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.01 J	0.015 J	0.0081 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	ND	< 0.0070 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	0.173	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	0.12	0.053	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	0.006	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	0.0060 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	0.55	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	0.55	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	0.135	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.044	0.062	0.029	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	0.286	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.18	0.092	0.014 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	0.218	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.14	0.065	0.013 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated	0.877	< 0.0038	< 0.0046	< 0.0064	< 0.0047	0.51	0.29	0.077	< 0.0069	< 0.0037
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	0.415	< 0.0084	< 0.013	< 0.0046	< 0.0068	0.21	0.15	0.055	< 0.0057	< 0.0034
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated	0.551	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.38	0.11	0.061	< 0.013	< 0.0056
Northern Athletic Field	SSHS-B780	SSHS-B780-SUB-0-2	5/22/2017	857.31	857.29	-0.02	-	0 - 2 ft	0-1.98 ft	180-66618-2	Not Excavated	0.246	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.15	0.073	0.023	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.86	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.41	0.34	0.11	< 0.014 U	< 0.0095 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	0.014	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.014 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	0.78	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.51	0.27	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	0.112	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.049	0.046	0.017 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.083	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.066	0.017	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.096	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.077	0.019	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	0.0244	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0073 J	0.01 J	0.0071 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	0.032	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.019	0.013 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	0.384	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.16	0.17	0.054	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	0.179	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.071	0.087	0.021	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	0.0432	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.016 J	0.019	0.0082 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.031	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.019 P	0.012 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	0.084	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.028	0.039	0.017 J	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	0.0094	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	0.0094 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.013	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.013 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.057	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.01 J	0.024	0.023	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.046	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.034	0.012 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.042	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.031	0.011 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0064 U	< 0.0024 U

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.0254	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.017 J	0.0084 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.0307	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.021	0.0097 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	0.047	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.022	0.025	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	0.7	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.17	0.37	0.16	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	0.261	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.17	0.091	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	0.52	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.35 P	0.17	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	0.484	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.2	0.2	0.084	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	0.092	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.054	0.038	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	0.073	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	0.052	0.021	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	0.059	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.059	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	0.521	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.31	0.17	0.041	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	0.11	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	0.11	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	0.032	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	0.032	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	0.14	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	0.14	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	0.029	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.013 J	0.016 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	0.012	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.012 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	0.809	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.15 P	0.099 P	0.56	< 0.0075 UT	< 0.0028 UT
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	0.044	< 0.0083 U	< 0.0090 U	< 0.0062 U	< 0.0037 U	< 0.0061 U	0.044	< 0.0072 U	< 0.0089 U	< 0.0034 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	ND	< 0.0073 U	< 0.0079 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0067 U	< 0.0064 U	< 0.0079 U	< 0.0030 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	ND	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.0070 U	< 0.0066 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	0.0096	< 0.0073 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	0.0096 J	< 0.0079 U	< 0.0030 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	ND	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.0035 U	< 0.0057 U	< 0.0072 U	< 0.0068 U	< 0.0084 U	< 0.0032 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	ND	< 0.0077 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.0071 U	< 0.0067 U	< 0.0083 U	< 0.0032 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	0.161	< 0.0074 U	< 0.0081 U	< 0.0055 U	< 0.0033 U	< 0.0055 U	0.12	0.041	< 0.0080 U	< 0.0031 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0082 U	< 0.0090 U	< 0.0062 U	< 0.0037 U	< 0.0061 U	< 0.0076 U	< 0.0072 U	< 0.0089 U	< 0.0034 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0080 U	< 0.0087 U	< 0.0060 U	< 0.0036 U	< 0.0059 U	< 0.0074 U	< 0.0070 U	< 0.0086 U	< 0.0033 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0030 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	ND	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	ND	< 0.0074 U	< 0.0081 U	< 0.0056 U	< 0.0033 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0080 U	< 0.0031 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	0.014	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	0.218	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.11	0.081	0.027	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	0.0095	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	0.0095 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	0.13	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.057	0.05	0.023	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	0.77	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.42	0.25	0.1	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	0.047	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	0.027	0.02 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	0.616	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.32 J	0.23 J	0.066 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	0.059	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.012 J	0.027	0.02	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	0.021	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0067 U	0.021 J	< 0.0078 U	< 0.0030 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	0.0341	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.028	0.0061 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	0.0732	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.036	0.028	0.0092 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	0.058	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.037	0.021	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	0.0472	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.023	0.018 J	0.0062 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	0.055	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.018 J	0.027	0.01 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	0.0087	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.0087 J	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U

TABLE 6-2A
Shallow Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	0.2	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.13	0.059	0.011 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	0.011	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	0.011 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	0.053	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.053	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	0.33	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.18	0.11	0.04	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	0.0278	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.019	0.0088 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	0.181	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.076	0.073	0.032	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	0.01	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.01 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	0.011	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.011 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	0.0293	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.02	0.0093 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.031	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	0.031	< 0.0066 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated	0.06	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.031 J	0.029 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.026 J	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3289	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated	0.039	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.013 J	0.016 J	0.01 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3290	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3229	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated	0.23	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.13 J	0.07 J	0.03 J	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3231	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	1.64	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.89 J	0.53 J	0.22 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated	0.037	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated	5.91	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	3.8 J	1.6 J	0.51 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3603	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3608	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated	0.016	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.016	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III-VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008		-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	9510	0.25	8.2	89.3	0.42	1.9	19100	15.9 *E	< U		65.7	25500
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated												
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated												
EHS Building	SSHS-B4S	B4-C1-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C1-Composite	7/25/2007	-	-	-	-	0.5 - 2 ft	0.5 - 2 ft	-	Not Excavated												
EHS Building	SSHS-B3S	B3-C1-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C1-Composite	7/25/2007	855.70	855.70	0.00	-	0.5 - 2 ft	0.5 - 2 ft	NA	Not Excavated												
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	10000	< 0.48 U	6.8	110	0.5 J	0.17 J	2500	14		8.3	24	22000
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.50	855.50	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	12000	< 6.0 U	5.6 J	88	0.56 J	< 0.60 U	20000	16		8.1	23	23000
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.22	855.22	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	13000	< 5.4 U	6.2	95	0.61	0.30 J	18000	16		8.2	22	23000
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.89	855.89	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	13000	< 5.6 U	7.4	84	0.51 J	< 0.56 U	23000	18		8.2	25	23000
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.41	855.41	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	12000	< 5.7 U	7.7	88	0.52 J	< 0.57 U	24000	16		8.1	22	22000
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.63	855.63	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	11000	< 5.7 U	6.9	89	0.48 J	< 0.57 U	23000	15		7.4	19	20000
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.48	855.48	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	11000	< 5.5 U	6.5	91	0.49 J	< 0.55 U	20000	15		7.5	20	20000
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.43	855.43	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	12000	< 6.1 U	5.2 J	84	0.54 J	0.37 J	19000	16		7.8	21	20000
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.49	855.49	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	12000	< 5.2 U	7.5	85	0.55	< 0.52 U	20000	18		8.2	23	24000
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.15	855.15	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	13000	< 5.5 U	6.8	84	0.62	0.38 J	20000	17		8.5	24	23000
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.85	854.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	12000	< 5.6 U	7.7	80	0.56	0.13 J	17000	17		8.9	24	23000
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.22	855.22	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	11000	< 5.6 U	5.0 J	80	0.52 J	0.35 J	16000	14		7.6	20	21000
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.09	855.09	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	13000	< 6.0 U	6.7	100	0.59 J	0.39 J	22000	16		8.2	22	22000
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.29	855.29	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	13000	< 5.6 U	5.5 J	95	0.62	0.37 J	18000	17		8.0	22	21000
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.11	855.11	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	7700	< 5.6 U	8.5	150	0.33 J	< 0.56 U	7600	11		6.3	25	23000
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.64	855.64	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	10000	< 5.7 U	6.1	74	0.40 J	< 0.57 U	15000	13		7.0	22	19000
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.50	855.50	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	13000	< 5.6 U	5.9	96	0.61	0.39 J	22000	17		8.8	26	24000
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.41	855.41	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	15000	< 6.1 U	13	100	0.76	0.45 J	16000	20		11	25	31000
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.24	855.24	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	11000	< 5.9 UT	7.0	71 T	0.52 J	< 0.59 U	21000 T	15		8.4	25	22000
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.16	855.16	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	12000	< 5.4 U	4.9 J	85	0.53 J	0.31 J	19000	15		7.6	20	20000
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.95	855.95	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	12000	< 5.7 U	8.6	88	0.50 J	< 0.57 U	28000	17		7.9	28	23000
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.89	855.89	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	10000	< 5.4 U	7.8	76	0.41 J	< 0.54 U	27000	14		7.0	21	20000
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.85	853.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	10000	< 5.8 U	5.0 J	73	0.40 J	< 0.58 U	24000	16		7.2	20	17000
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.26	855.26	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	11000	< 5.7 U	5.9	87	0.44 J	< 0.57 U	21000	15		7.5	22	20000
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.43	855.43	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	9600	< 5.6 U	4.8 J	60	0.35 J	< 0.56 U	24000	12		6.3	18	17000
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.26	855.26	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	10000	< 6.1 U	5.5 J	74	0.40 J	< 0.61 U	16000	13		7.2	18	18000
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	11000	< 5.9 UT	5.4 J	81 T	0.43 J	< 0.59 U	20000	16		7.4	21	18000
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.85	853.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	10000	< 5.5 U	5.2 J	73	0.38 J	< 0.55 U	12000	15		6.8	20	17000
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.02	855.02	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	9200	< 5.8 U	3.6 J	68	0.31 J	< 0.58 U	19000	12		6.7	15	17000
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.46	855.46	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	14000	< 5.8 U	7.0	99	0.57 J	< 0.58 U	19000	19		8.5	25	23000
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	12000	< 6.1 UT	7.5	94 T	0.52 J	< 0.61 U	18000 T	17		8.3	24	22000 T
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.92	855.92	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	13000	< 5.8 U	7.0	92	0.53 J	< 0.58 U	18000	19		8.4	25	22000
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.63	855.63	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	13000	< 5.9 U	8.0	96	0.52 J	< 0.59 U	23000	18		8.6	24	21000
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.70	855.70	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	9700	< 5.4 U	5.0 J	62	0.38 J	< 0.54 U	23000	13		7.4	20	18000
Football Field	IRM4-S018	SSHS-IRM4-S018-0-2-20200715	SSHS-IRM4-S018-0-2	7/15/2020	-	855.71	-	854.07	0 - 2 ft	1.64 ft	1801083161	Not Excavated	6500	< 0.32 U	4.0	55	0.25 J	0.13 J	53000	8.7		6.1	19	16000
Football Field	IRM4-S019	SSHS-IRM4-S019-0-2-20200715	SSHS-IRM4-S019-0-2	7/15/2020	-	855.68	-	854.02	0 - 2 ft	1.66 ft	1801083161	Not Excavated	6000	< 0.29 U	4.0	41	0.22 J	0.14 J	66000	7.7		5.1	20	14000
Football Field	IRM4-S021	SSHS-IRM4-S021-0-2-20200715	SSHS-IRM4-S021-0-2	7/15/2020	-	855.65	-	854.93	0 - 2 ft	0.73 ft	1801083161	Not Excavated	5400	< 0.31 U	5.0	56	0.25 J	0.095 J	11000	9.4		4.6	23	14000
Football Field	IRM4-S183S	SSHS-IRM4-S183S-20200813	SSHS-IRM4-S183S	8/13/2020	-	855.60	-	853.95	0 - 2 ft	1.65 ft	1801095841	Not Excavated	7400	0.60 J	6.9	94	0.38	0.15 J	27000	14		6.6	50	18000
Football Field	IRM4A-S033	SSHS-IRM4A-S033-0-2-20201118	SSHS-IRM4A-S033-0-2	11/18/2020	-	855.92	-	854.24	0 - 2 ft	1.68 ft	1801138131	Not Excavated	6900	< 0.34 U	8.1	57	0.23 J	0.15 J	31000	10		6.2	37	17000
Football Field	IRM5-S018A	SSHS-IRM5-S018A-20210225	SSHS-IRM5-S018A	2/25/2021	-	856.34	-	854.42	0 - 2 ft	1.92 ft	1801176021	Not Excavated	9100	1.1	6.9	93	0.48	0.16 J	5700	12		8.8	29	17000
Football Field	IRM5-B082A	SSHS-IRM5-B082A-20210414	SSHS-IRM5-B082A	4/14/2021	-	854.82	-	853.13	0 - 2 ft	1.69 ft	1801199781	Not Excavated	7300	< 0.33 U	5.3	45	0.35 J	0.081 J	1100	8.6		6.7	19	14000
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	6700	< 0.29 U	5.3	69	0.18 J	0.092 J	45000	9.2		6.5	27	15000 B
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	6900	< 0.31 U	5.1	52	0.21 J	0.12 J	33000	9.1		6.5	23	16000 B
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	7800	0.39	6.5	110	0.39	0.17	22000	9.4		5.7	150	15000
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	6300	< 0.3	3.7	68	0.22	0.072	50000	9.5		5.3	21	14000
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	10000	< 0.29 U	6.7	99	0.51	0.031 J	3800	12		8.8	15	19000
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	6100	1.4	11	61	0.26 J	0.068 J	6200	12		6.1	29	31000
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	7300	< 0.31 U	6.2	87	0.33 J	0.14 J	18000	12		6.6	23	17000
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	6900	0.36 J	5.0	67	0.29 J	0.20 J	12000	9.4		5.9	22	14000
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	8100	0.51 J	7.1	220	0.35 J	0.58	8600	21		6.6	83	21000
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	5400	< 0.28 U	4.4	35	0.22 J	< 0.067 U	38000	6.7		4.4 J	20	12000 B
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	5500	0.35 J	4.5	39	0.24 J	< 0.072 U	14000	7.1		4.6 J	15	12000 B
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	3800	< 0.26 U	3.1	28	0.16 J	0.077 J	42000	5.0		3.3 J	14	8400 B
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	9000	0.48 J	9.8	66	0.40	< 0.072 U	1800	11		8.1	15	21000 B
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	5800	0.38 JT	4.9 T	54 T	0.27 JT	< 0.066 UT	20000 T	9.8 T		4.7 T	43 T	13000 B
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	3300	0.42 J	3.9	26	0.15 J	< 0.073 U	9400	4.7		2.9 J	14	8800
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	5200	0.37 J	3.8	37	0.16 J	0.057 J	34000	11		5.4	17	12000
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	7500	0.34 J	7.6	52	0.29	< 0.043 U	7200	9.5		7.7	18	19000
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	5500	0.41 J	4.7	35	0.24 J	0.079 J	35000	7.2		4.2 J	22	12000
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	6100	< 0.29 U	4.9	50	0.26 J	0.084 J	56000	8.0		5.5	21	14000

DRAFT

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated	70.5 NE	4400	267 *E	0.082	84 *E	494	1.3	< U	132		< U
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated	70.5 NE	4400	267 *E	0.082	84 *E	494	1.3	< U	132		< U
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	32 NE	4150	481 *E	0.0087	19.3 *E	682	1.7	< U	110		< U
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	171 NE	3760	379 *E	0.042	453 *E	900	1.8	< U	1270		< U
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	32 NE	4150	481 *E	0.0087	19.3 *E	682	1.7	< U	110		< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	32 NE	4150	481 *E	0.0087	19.3 *E	682	1.7	< U	110		< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	63.6 NE	5010	458 *E	0.14	44.4 *E	790	2.1	< U	207		< U
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	70.5 NE	4400	267 *E	0.082	84 *E	494	1.3	< U	132		< U
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	171 NE	3760	379 *E	0.042	453 *E	900	1.8	< U	1270		< U
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	171 NE	3760	379 *E	0.042	453 *E	900	1.8	< U	1270		< U
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated										< U	
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated										< U	
EHS Building	SSHS-B4S	B4-C1-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C1-Composite	7/25/2007	-	-	-	-	0.5 - 2 ft	0.5 - 2 ft	-	Not Excavated										< U	
EHS Building	SSHS-B3S	B3-C1-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C1-Composite	7/25/2007	855.70	855.70	0.00	-	0.5 - 2 ft	0.5 - 2 ft	NA	Not Excavated										< U	
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	30	2700	540	0.036 J	24	970	< 0.72 U	< 0.15 U	42 J		< 0.29 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.50	855.50	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	18	5700	480	0.034 J	20	1500	< 6.0 U	< 1.2 U	67 J		< 3.6 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.22	855.22	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	17	5400	450	0.034 J	20	1700	< 5.4 U	< 1.1 U	69 J		< 3.2 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.89	855.89	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	18	5600	430	0.024 J	21	1900	< 5.6 U	< 1.1 U	380		< 3.3 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.41	855.41	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	18	7700	450	0.031 J	20	1600	< 5.7 U	< 1.1 U	65 J		< 3.4 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.63	855.63	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	18	5400	420	0.031 J	18	1500	< 5.7 U	< 1.1 U	72 J		< 3.4 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.48	855.48	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	18	7000	460	0.044 J	18	1400	< 5.5 U	< 1.1 U	120		< 3.3 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.43	855.43	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	18	4900	390	0.043 J	19	1500	< 6.1 U	< 1.2 U	130		< 3.7 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.49	855.49	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	20	6200	510	0.037 J	20	1700	< 5.2 U	< 1.0 U	68 J		< 3.1 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.15	855.15	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	20	5900	440	0.034 J	21	1800	< 5.5 U	< 1.1 U	86 J		< 3.3 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.85	854.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	20	5500	480	0.031 J	21	1500	< 5.6 U	< 1.1 U	68 J		< 3.3 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.22	855.22	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	16	5200	400	0.037 J	19	1400	< 5.6 U	< 1.1 U	69 J		< 3.3 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.09	855.09	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	21	6700	560	0.038 J	20	1600	< 6.0 U	< 1.2 U	78 J		< 3.6 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.29	855.29	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	20	5400	450	0.028 J	19	1600	< 5.6 U	< 1.1 U	76 J		< 3.4 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.11	855.11	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	17	3600	1300	0.038 J	15	890	< 5.6 U	< 1.1 U	< 110 U		< 3.3 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.64	855.64	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	15	4700	360	0.025 J	17	1300	< 5.7 U	< 1.1 U	59 J		< 3.4 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.50	855.50	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	20	5900	490	0.038 J	22	1500	< 5.6 U	< 1.1 U	76 J		< 3.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.41	855.41	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	23	5500	540	0.027 J	26	1800	< 6.1 U	< 1.2 U	72 J		< 3.6 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.24	855.24	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	16 T	6100 B	440	0.030 J	21	1400 T	< 5.9 U	< 1.2 U	71 J		< 3.6 UT
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.16	855.16	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	18	5100	380	0.041 J	19	1500	< 5.4 U	< 1.1 U	86 J		< 3.2 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.95	855.95	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	18	5900	440	0.033 J	20	1700	< 5.7 U	< 1.1 U	92 J		< 3.4 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.89	855.89	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	15	6700	350	0.026 J	18	1400	< 5.4 U	< 1.1 U	250		< 3.2 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.85	853.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	18	6800	370	0.049 J	16	1400	< 5.8 U	< 1.2 U	75 J		< 3.5 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.26	855.26	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	17	4700	510	0.027 J	17	1300	< 5.7 U	< 1.1 U	63 J		< 3.4 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.43	855.43	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	12	4600	330	< 0.066 U	15	1300	< 5.6 U	< 1.1 U	78 J		< 3.3 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.26	855.26	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	23	4000	360	0.032 J	16	1300	< 6.1 U	< 1.2 U	71 J		< 3.6 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	19 T	4800	400	0.056 J	16	1500 T	< 5.9 UT	< 1.2 U	77 J		< 3.5 UT
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.85	853.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	17	4100	370	0.058 J	15	1300	< 5.5 U	< 1.1 U	52 J		< 3.3 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.02	855.02	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	14	7500	360	0.053 J	14	1100	< 5.8 U	< 1.2 U	64 J		< 3.5 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.46	855.46	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	23	6300 B	500	0.051 J	21	2300	2.3 J	< 1.2 U	100 J		< 3.5 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	22 T	5900 BT	490	0.062 J	20	1900 T	< 6.1 U	< 1.2 U	82 J		< 3.7 UT
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.92	855.92	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	21	5800 B	480	0.059 J	20	1900	< 5.8 U	< 1.2 U	77 J		< 3.5 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.63	855.63	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	22	5500 B	520	0.051 J	20	2100	< 5.9 U	< 1.2 U	83 J		< 3.6 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.70	855.70	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	12	5100	360	0.032 J	16	1200	< 5.4 U	< 1.1 U	64 J		< 3.3 U
Football Field	IRM4-S018	SSHS-IRM4-S018-0-2-20200715	SSHS-IRM4-S018-0-2	7/15/2020	-	855.71	-	854.07	0 - 2 ft	1.64 ft	1801083161	Not Excavated	6.7	6800	460	< 0.023 U	16	630	0.85 J	< 0.10 U	110 J		< 0.30 U
Football Field	IRM4-S019	SSHS-IRM4-S019-0-2-20200715	SSHS-IRM4-S019-0-2	7/15/2020	-	855.68	-	854.02	0 - 2 ft	1.66 ft	1801083161	Not Excavated	6.7	6900	340	< 0.020 U	15	570	0.78 J	< 0.091 U	110 J		< 0.28 U
Football Field	IRM4-S021	SSHS-IRM4-S021-0-2-20200715	SSHS-IRM4-S021-0-2	7/15/2020	-	855.65	-	854.93	0 - 2 ft	0.73 ft	1801083161	Not Excavated	31	2700	290	0.051	26	450 J	< 0.47 U	< 0.096 U	66 J		< 0.29 U
Football Field	IRM4-S183S	SSHS-IRM4-S183S-20200813	SSHS-IRM4-S183S	8/13/2020	-	855.60	-	853.95	0 - 2 ft	1.65 ft	1801095841	Not Excavated	86	4100	500	0.036	67	750	0.62 J	< 0.10 U	130 J		< 0.30 U
Football Field	IRM4A-S033	SSHS-IRM4A-S033-0-2-20201118	SSHS-IRM4A-S033-0-2	11/18/2020	-	855.92	-	854.24	0 - 2 ft	1.68 ft	1801138131	Not Excavated	27	6100	430	0.054 J	20	610	< 0.44 U	< 0.076 U	130 J		< 0.37 U
Football Field	IRM5-S018A	SSHS-IRM5-S018A-20210225	SSHS-IRM5-S018A	2/25/2021	-	856.34	-	854.42	0 - 2 ft	1.92 ft	1801176021	Not Excavated	25	2600	490	0.058	25	860	< 0.50 U	< 0.10 U	64 J		0.70 J
Football Field	IRM5-B082A	SSHS-IRM5-B082A-20210414	SSHS-IRM5-B082A	4/14/2021	-	854.82	-	853.13	0 - 2 ft	1.69 ft	1801199781	Not Excavated	19	1800	630	0.090	18	590	< 0.50 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	11	6900	580	0.023 J	23	630	< 0.38 U	< 0.065 U	75 J		< 0.32 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	10	6400	380	0.020 J	19	680	< 0.40 U	< 0.070 U	84 J		< 0.34 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	63	3500	390	< 0.02	26	720	0.95	< 0.085	82		< 0.26
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	7.9	12000	340	< 0.017	15	580	0.82	< 0.092	62		< 0.28
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	14 B	2900	480	0.040	22	920	< 0.44 U	< 0.090 U	< 52 U		< 0.28 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	41	2900	460	0.035	18	490	0.50 J	< 0.079 U	200 J		< 0.24 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	32	4600	380	0.54	35	620	0.69 J	< 0.11 U	59 J		< 0.29 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	19	3100	350	0.13 T	15	720	< 0.38 U	< 0.086 U	54 J		< 0.24 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	120	3500	490	0.049	100	710	0.92 J	< 0.11 U	95 J		< 0.29 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	9.2	15000	320	0.024	12	540	0.77 J	< 0.095 U	180 J		< 0.26 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	12	3200	280	0.020	12	540	< 0.45 U	< 0.10 U	98 J		< 0.28 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	7.3	3300	240	0.022	9.5	390 J	0.44 J	< 0.088 U	140 J		< 0.24 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	10	2700	370	0.012 J	17	940	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	40 T	7200 T	290	0.057	21 T	620 T	< 0.42 UT	< 0.094 UT	200 JT		< 0.26 UT
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	14	1700	260	0.058	7.6	330 J	0.47 J	< 0.10 U	230 J		< 0.28 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	15	8900	270	0.018 J	47	450	0.36 J	< 0.079 U	61 J		< 0.22 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	7.5	3400	310	0.0067 J	17	700	< 0.27 U	< 0.061 U	36 J		< 0.17 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	15	4500	280	0.082	15	590	< 0.45 U	< 0.10 U	54 J		< 0.28 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	13	5600	380	0.073	18	720	0.78 J	< 0.10 U	72 J		< 0.27 U

DRAFT

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-		-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated		9.4	103 NE
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated		9.4	103 NE
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated		13.3	68.5 NE
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated		14.7	111 NE
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated		13.3	68.5 NE
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated		13.3	68.5 NE
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		15	90.3 NE
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		9.4	103 NE
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		14.7	111 NE
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated		14.7	111 NE
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			
EHS Building	SSHS-B4S	B4-C1-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C1-Composite	7/25/2007	-	-	-	-	0.5 - 2 ft	0.5 - 2 ft	-	Not Excavated			
EHS Building	SSHS-B3S	B3-C1-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C1-Composite	7/25/2007	855.70	855.70	0.00	-	0.5 - 2 ft	0.5 - 2 ft	NA	Not Excavated			
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated		14	70
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.50	855.50	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		18	78
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.22	855.22	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		18	73
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.89	855.89	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		20	79
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.41	855.41	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		18	74
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.63	855.63	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		17	67
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.48	855.48	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		17	67
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.43	855.43	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		17	78
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.49	855.49	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		20	81
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.15	855.15	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		19	78
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.85	854.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		18	83
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.22	855.22	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		16	67
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.09	855.09	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		18	74
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.29	855.29	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		18	73
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.11	855.11	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		12	130
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.64	855.64	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		15	66
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.50	855.50	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		18	79
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.41	855.41	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		21	81
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.24	855.24	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		17	76
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.16	855.16	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		17	68
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.95	855.95	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		19	75
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.89	855.89	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		15	64
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.85	853.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		17	69
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.26	855.26	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		17	72
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.43	855.43	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		15	55
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.26	855.26	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		16	61
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		17	78
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.85	853.85	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		16	67
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.02	855.02	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		14	60
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.46	855.46	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		22	89
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		19	88
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.92	855.92	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		20	82
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.63	855.63	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		21	88
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.70	855.70	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated		15	61
Football Field	IRM4-S018	SSHS-IRM4-S018-0-2-20200715	SSHS-IRM4-S018-0-2	7/15/2020	-	855.71	-	854.07	0 - 2 ft	1.64 ft	1801083161	Not Excavated		14	63
Football Field	IRM4-S019	SSHS-IRM4-S019-0-2-20200715	SSHS-IRM4-S019-0-2	7/15/2020	-	855.68	-	854.02	0 - 2 ft	1.66 ft	1801083161	Not Excavated		9.6	65
Football Field	IRM4-S021	SSHS-IRM4-S021-0-2-20200715	SSHS-IRM4-S021-0-2	7/15/2020	-	855.65	-	854.93	0 - 2 ft	0.73 ft	1801083161	Not Excavated		9.3	53
Football Field	IRM4-S183S	SSHS-IRM4-S183S-20200813	SSHS-IRM4-S183S	8/13/2020	-	855.60	-	853.95	0 - 2 ft	1.65 ft	1801095841	Not Excavated		14	77
Football Field	IRM4A-S033	SSHS-IRM4A-S033-0-2-20201118	SSHS-IRM4A-S033-0-2	11/18/2020	-	855.92	-	854.24	0 - 2 ft	1.68 ft	1801138131	Not Excavated		11	84
Football Field	IRM5-S018A	SSHS-IRM5-S018A-20210225	SSHS-IRM5-S018A	2/25/2021	-	856.34	-	854.42	0 - 2 ft	1.92 ft	1801176021	Not Excavated		13	72
Football Field	IRM5-B082A	SSHS-IRM5-B082A-20210414	SSHS-IRM5-B082A	4/14/2021	-	854.82	-	853.13	0 - 2 ft	1.69 ft	1801199781	Not Excavated		12	43
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated		10	65
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated		10	64
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated		13	79
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated		9	55
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated		14	52
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated		17	82
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated		12	120
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated		9.1	98
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated		15	110
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated		8.3	41
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated		8.2	41
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated		5.9	31
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated		13	42
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated		9.9 T	56 T
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated		6.1	36
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated		8.6	50
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated		11	47
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated		9.3	55
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated		9.2	49

DRAFT

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III-VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	6100	0.99 T	5.3	69	0.34 J	< 0.071 U	7300 T	8.1		4.4 J	34	13000
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	6000	< 0.28 U	5.0	55	0.26 J	0.11 J	61000	8.2		5.1	23	13000
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	6700	< 0.24 U	4.9	45	0.27 J	0.078 J	60000	9.0		5.7	20	14000
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.33	855.33	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	370	< 5.4 U	< 5.4 U	1.5	< 0.54 U	< 0.54 U	40 J	1.5 J		< 0.54 U	< 2.2 U	1800
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.07	855.07	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	380	< 5.5 U	< 5.5 U	2.3	< 0.55 U	< 0.55 U	40 J	2.1		< 0.55 U	< 2.2 U	1800
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.89	855.89	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	10000	< 5.2 U	< 26 U	68	0.37 J	< 0.52 U	73000	14		6.6	22	20000
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.49	855.49	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	12000	< 5.2 U	7.9	87	0.55	< 0.52 U	15000	16		9.0	24	25000
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.63	855.63	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	11000	< 5.1 U	6.6	82	0.43 J	< 0.51 U	21000	14		7.9	22	21000
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.48	855.48	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	13000	< 5.8 U	5.8	97	0.61	0.37 J	24000	17		8.7	23	24000
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.43	855.43	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	12000	< 5.6 U	13	110	0.55 J	< 0.56 U	18000	15		8.9	19	26000
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.49	855.49	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	14000	< 5.0 U	12	91	0.57	< 0.50 U	17000	18		11	24	30000
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.15	855.15	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	13000	< 5.5 U	8.0	80	0.53 J	< 0.55 U	19000	17		8.2	24	23000
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.85	854.85	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	12000	< 5.4 U	7.6	85	0.53 J	< 0.54 U	27000	18		8.6	30	24000
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.22	855.22	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	13000	< 5.5 UT	6.5	92 T	0.59	0.37 J	19000 T	16		8.8	24	24000
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.09	855.09	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	12000	< 5.8 UT	7.0	92	0.54 J	< 0.58 U	19000	16		8.5	21	23000
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.29	855.29	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	12000	< 5.9 U	5.3 J	92	0.57 J	0.33 J	19000	17		8.2	21	22000
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.11	855.11	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	11000	< 6.0 U	6.7	87	0.50 J	< 0.60 U	19000	15		7.8	21	21000
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.64	855.64	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	11000	< 5.7 U	6.7	82	0.41 J	< 0.57 U	20000	14		7.3	19	20000
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.50	855.50	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	12000	< 5.4 U	4.5 J	73	0.48 J	0.39 J	35000	15		7.9	31	23000
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.41	855.41	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	11000	< 5.1 U	7.1	78	0.48 J	< 0.51 U	16000	14		8.6	18	23000
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.24	855.24	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	11000	< 5.9 U	6.2	70	0.47 J	< 0.59 U	27000	15		7.4	22	21000
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.16	855.16	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	9900	< 5.3 UJ	6.8	71	0.38 J	< 0.53 U	39000	13		5.9	23	19000
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.95	855.95	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	11000	< 5.7 U	6.7	73	0.40 J	< 0.57 U	25000	14		7.8	22	22000
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.89	855.89	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	12000	< 5.6 U	20	84	0.49 J	0.13 J	14000	14		9.3	22	25000
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.02	855.02	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	12000	< 5.6 U	6.5	83	0.49 J	< 0.56 U	21000	16		8.0	21	20000
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.43	855.43	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	8800	< 5.2 U	4.2 J	59	0.32 J	< 0.52 U	27000	12		6.1	18	16000
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.26	855.26	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	12000	< 5.9 U	5.8 J	92	0.46 J	< 0.59 U	19000	16		8.0	20	20000
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	10000	< 5.9 U	5.3 J	74	0.39 J	< 0.59 U	18000	16		6.9	24	18000
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.85	853.85	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	11000	< 5.8 U	5.7 J	85	0.45 J	< 0.58 U	15000	16		7.6	22	19000
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.02	855.02	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	12000	< 5.7 U	7.5	91	0.50 J	< 0.57 U	23000	17		8.0	21	20000
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.46	855.46	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	9400	< 5.9 U	9.2 J	130	0.36 J	< 0.59 U	140000	13		5.8	16	15000
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	12000	< 5.6 U	7.7	95	0.50 J	< 0.56 U	42000	17		7.9	22	20000
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.92	855.92	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	12000	< 5.4 U	7.0	98	0.51 J	< 0.54 U	14000	19		8.4	24	22000
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.63	855.63	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	12000	< 5.7 U	7.9	90	0.50 J	< 0.57 U	20000	18		8.1	24	21000
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.70	855.70	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	10000	< 5.5 U	5.4 J	69	0.40 J	< 0.55 U	31000	13		6.7	27	19000
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	11000	< 0.43 U	6.9	95	0.52	0.14 J	2100	14		9.1	18	20000
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	6400	7.7	4.9	54	0.32 J	0.22 J	60000	8.9		5.3	36	13000
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated	5100	< 0.22 U	3.4	39	0.22 J	0.093 J	25000	7.3		5.3	24	12000
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	7800	0.31 J	6.2	71	0.32	0.25 J	19000	13		6.4	52	22000
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated	7200	0.56 J	6.9	77	0.31 J	0.19 J	32000	16		6.2	53	20000
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	6100	0.82 J	4.6	45	0.25 J	0.16 J	35000	8.2		5.3	28	14000
Football Field	SSHS-B3501	090120 10:30 SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated												
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	8900	< 0.034 U	5.9	60	0.34 J	0.071 J	41000	11		7.9	26	19000
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.63	855.63	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	16000	< 4.9 U	12 J	140	0.65	< 0.49 U	9900	18		13	30	33000
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.48	855.48	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	14000	< 5.2 U	16 J	95	0.56	< 0.52 U	9000	17		11	26	32000
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.43	855.43	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	14000	< 4.9 U	9.3 J	100	0.63	< 0.49 U	5400	17		11	20	30000
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.49	855.49	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	13000	< 5.3 U	11 J	92	0.61	< 2.6 U	10000	16		11	24	29000
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.15	855.15	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	15000	< 5.0 U	11 J	170	0.73	< 2.5 U	7300	18		13	39	33000
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.85	854.85	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	17000	< 5.3 U	14 J	110	0.71	< 0.53 U	5300	20		12	24	33000
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.22	855.22	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	16000	< 5.4 U	11 J	120	0.71	< 2.7 U	15000	20		14	25	33000
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.09	855.09	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	13000	< 4.9 U	13 J	95	0.60	< 2.4 U	2500	16		12	18	32000
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.29	855.29	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	13000	< 5.4 U	11	110	0.60	< 0.54 U	2900	17		10	19	28000
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.11	855.11	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	14000	< 5.1 U	57	110	0.59	< 2.6 U	3000	18		13	29	40000
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.64	855.64	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	11000	< 4.9 U	7.3	74	0.39 J	< 0.49 U	38000	14		9.0	23	23000
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.50	855.50	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	11000	< 5.2 UT	8.1	76	0.38 J	< 0.52 U	31000 T	13		7.2	23	23000
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.41	855.41	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	12000	< 5.0 U	10	120	0.52	< 0.50 U	10000	18		8.7	38	25000
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.24	855.24	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	15000	< 5.0 U	16 J	120	0.59	< 0.50 U	2400	19		14	22	31000
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.16	855.16	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	15000	< 5.2 U	9.0 J	110	0.68	< 2.6 U	3700	19		13	20	33000
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.95	855.95	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	12000	< 4.9 U	6.9	73	0.44 J	< 0.49 U	21000	14		7.5	23	22000
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.89	855.89	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	15000	< 5.1 U	14 J	100	0.61	< 0.51 U	4300	17		11	30	32000
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.43	855.43	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	14000	< 5.0 U	13	100	0.61	< 0.50 U	3200	17		11	26	31000
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.26	855.26	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	13000	< 5.1 U	8.1	89	0.51	< 0.51 U	3400	15		9.8	17	26000
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	12000	< 4.9 U	7.5	84	0.49	< 0.49 U	7400	15		10	18	25000
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.85	853.85	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	12000	< 4.9 U	8.6	81	0.50	< 0.49 U	16000	15		8.4	18	23000
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.02	855.02	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	14000	< 5.7 U	8.8	88	0.56 J	< 0.57 U	46000	18		8.4	27	26000
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.46	855.46	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	13000	< 5.1 U	7.1	81	0.49 J	< 0.51 U	24000	16		10	20	26000
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	12000	< 5.1 U	8.6	86	0.44 J	< 0.51 U	38000	15		7.6	29	22000
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.92	855.92	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	16000	< 5.2 U	21 J	130	0.66	< 0.52 U	5400	19		13	21	35000
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.63	855.63	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	11000	< 4.9 U	6.9	92	0.47 J	< 0.49 U	7300	16		7.8	22	21000
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.70	855.70	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	12000	< 4.9 U	7.7	84	0.50	< 0.49 U	11000	15		8.9	21	25000
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	15000	< 5.1 U	44	110	0.59	0.16 J	7300	19		12	25	33000
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	14000	< 5.3 U	21 J	94	0.57	0.12 J	5900	17		12	23	31000
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.38	855.38	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	13000	< 5.6 U	9.8 J	74	0.44 J	< 0.56 U	63000	17		10	28	32000
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.80	854.80	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	10000	< 5.6 U	6.8	52	0.35 J	< 0.56 U	42000	13		8.0	23	23000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	39	1700 T	240 T	0.21 T	12	580	0.50 J	< 0.10 U	150 J		< 0.28 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	22	5000	330	0.050	19	600	1.2	< 0.097 U	70 J		< 0.26 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	11	8400	320	0.024	16	800	0.93	< 0.083 U	74 J		< 0.23 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.33	855.33	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	1.2 J	17 J	3.6	< 0.062 U	< 1.1 U	45 J	< 5.4 U	< 1.1 U	< 110 U		< 3.3 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.07	855.07	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	1.6	18 J	3.2	< 0.062 U	< 1.1 U	40 J	< 5.5 U	< 1.1 U	< 110 U		< 3.3 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.89	855.89	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	16	5700	500	0.027 J	16	1500	< 5.2 U	< 1.0 U	320		< 3.1 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.49	855.49	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	17	5300	580	0.032 J	21	1700	< 5.2 U	< 1.0 U	54 J		< 3.1 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.63	855.63	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	15	6100	390	0.021 J	19	1400	< 5.1 U	< 1.0 U	130		< 3.1 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.48	855.48	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	18	6400	470	0.036 J	21	1600	< 5.8 U	< 1.2 U	200		< 3.5 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.43	855.43	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	12	5200	390	< 0.064 U	21	1800	< 5.6 U	< 1.1 U	140		< 3.4 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.49	855.49	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	12	6500	480	< 0.061 U	24	1800	< 5.0 U	< 1.0 U	55 J		< 3.0 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.15	855.15	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	18	5800	420	0.030 J	20	2000	< 5.5 U	< 1.1 U	79 J		< 3.3 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.85	854.85	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	25	5300	610	0.031 J	20	1600	< 5.4 U	< 1.1 U	59 J		< 3.2 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.22	855.22	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	18 T	5900	460	< 0.067 U	21	1700 T	< 5.5 U	< 1.1 U	90 J		< 3.3 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.09	855.09	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	19 T	5500	470	0.028 J	20	1600 T	< 5.8 U	< 1.2 U	67 J		< 3.5 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.29	855.29	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	21	6400	410	0.038 J	20	1600	< 5.9 U	< 1.2 U	80 J		< 3.5 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.11	855.11	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	18	5400	410	0.045 J	19	1500	< 6.0 U	< 1.2 U	71 J		< 3.6 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.64	855.64	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	17	4700	410	0.026 J	18	1400	< 5.7 U	< 1.1 U	67 J		< 3.4 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.50	855.50	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	12	8800	410	< 0.063 U	22	1300	< 5.4 U	< 1.1 U	98 J		< 3.2 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.41	855.41	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	13	4700	460	0.021 J	20	1600	< 5.1 U	< 1.0 U	67 J		< 3.1 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.24	855.24	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	14	8800	420	0.027 J	18	1600	< 5.9 U	< 1.2 U	66 J		< 3.5 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.16	855.16	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	9.0 J	7900 T	380	< 0.060 U	16	1600 T	< 5.3 U	< 1.1 U	120		< 3.2 UJ
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.95	855.95	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	17	6200	380	0.028 J	19	1400	< 5.7 U	< 1.1 U	82 J		< 3.4 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.89	855.89	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	14	4800	440	< 0.063 U	22	1700	< 5.6 U	< 1.1 U	280		< 3.3 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.02	855.02	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	17	5400 B	430	0.051 J	19	1700	< 5.6 U	< 1.1 U	81 J		< 3.3 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.43	855.43	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	11	4800	330	< 0.065 U	14	1200	< 5.2 U	< 1.0 U	62 J		< 3.1 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.26	855.26	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	20	4700	420	0.033 J	18	1400	< 5.9 U	< 1.2 U	71 J		< 3.6 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	14	4300	390	0.040 J	16	1400	< 5.9 U	< 1.2 U	67 J		< 3.5 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.85	853.85	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	19	5000	440	0.047 J	17	1400	< 5.8 U	< 1.2 U	66 J		< 3.5 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.02	855.02	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	21	5200 B	460	0.053 J	19	1700	< 5.7 U	< 1.1 U	73 J		< 3.4 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.46	855.46	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	18	4900 B	510	0.054 J	14	1600	< 29 U	< 1.2 U	130		< 3.5 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	21	6100 B	640	0.063 J	18	2000	1.8 J	< 1.1 U	93 J		< 3.4 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.92	855.92	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	21	5500 B	530	0.052 J	21	1900	2.0 J	< 1.1 U	84 J		< 3.3 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.63	855.63	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	21	5400 B	450	0.053 J	20	1900	< 5.7 U	< 1.1 U	89 J		< 3.4 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.70	855.70	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	11	7600	390	< 0.062 U	17	1400	< 5.5 U	< 1.1 U	100 J		< 3.3 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	27	2800	530	0.18	20	920	< 0.65 U	< 0.13 U	33 J		< 0.26 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	36	5300	350	0.082	18	670	1.3	< 0.089 U	450		< 0.27 U
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated	14	4100	270	0.019 J	21	500	0.54 J	< 0.067 U	72 J		< 0.21 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	50	4300	450	0.041	28	630	< 0.41 U	< 0.084 U	84 J		< 0.25 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated	76	4200	350	0.065	120	690	0.81 J	< 0.11 U	290 J		< 0.34 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	27	4800	330	0.045	17	510	0.66 J	< 0.088 U	150 J		< 0.27 U
Football Field	SSHS-B3501	090120 10:30 SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated	9.5										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	9.5	7700	340	< 0.034 U	26	970	< 0.034 U	< 0.034 U	78 J		< 0.034 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.63	855.63	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	19	5400	870	< 0.061 U	29	2300	< 4.9 U	< 0.98 U	110		< 2.9 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.48	855.48	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	17	4600	560	< 0.060 U	25	2200	< 5.2 U	< 1.0 U	110		< 3.1 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.43	855.43	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	12	4700	510	< 0.060 U	23	2100	< 4.9 U	< 0.99 U	130		< 3.0 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.49	855.49	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	13	4100	500	< 0.062 U	23	2200	< 5.3 U	< 1.1 U	67 J		< 3.2 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.15	855.15	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	17	4700	1300	< 0.062 U	30	2100	< 5.0 U	< 1.0 U	66 J		< 3.0 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.85	854.85	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	13	4500	570	< 0.061 U	28	2800	< 5.3 U	< 1.1 U	74 J		< 3.2 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.22	855.22	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	18	5100	660	< 0.064 U	28	2500	< 5.4 U	< 1.1 U	77 J		< 3.2 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.09	855.09	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	12	3600	850	< 0.060 U	24	1800	< 4.9 U	< 0.98 U	51 J		< 2.9 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.29	855.29	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	15	3900	600	< 0.064 U	22	2000	< 5.4 U	< 1.1 U	53 J		< 3.2 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.11	855.11	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	36	3600	650	< 0.059 U	29	1900	< 5.1 U	< 1.0 U	58 J		< 3.1 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.64	855.64	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	11	5600	380	< 0.059 U	22	1500	< 4.9 U	< 0.97 U	77 J		< 2.9 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.50	855.50	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	11 T	6900	410	< 0.064 U	19	1300 T	< 5.2 U	< 1.0 U	82 J		< 3.1 UT
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.41	855.41	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	68	5500	520	0.069	39	1600	< 5.0 U	< 1.0 U	71 J		< 3.0 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.24	855.24	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	15	3900	750	< 0.065 U	26	2100	< 5.0 U	< 0.99 U	57 J		< 3.0 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.16	855.16	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	19	4400	760	< 0.061 U	27	2300	< 5.2 U	< 1.0 U	75 J		< 3.1 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.95	855.95	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	14	5900	410	0.025 J	18	1600	2.2 J	< 0.99 U	79 J		< 3.0 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.89	855.89	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	14	4000	570	< 0.062 U	24	2600	< 5.1 U	< 1.0 U	82 J		< 3.0 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.43	855.43	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	18	4100	500	< 0.065 U	24	2000	< 5.0 U	< 1.0 U	59 J		< 3.0 UT
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.26	855.26	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	13	3600	430	< 0.059 U	20	1800	< 5.1 U	< 1.0 U	69 J		< 3.1 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	9.8	3500	530	< 0.060 U	19	1800	< 4.9 U	< 0.99 U	57 J		< 3.0 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.85	853.85	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	12	4500	540	0.036 J	18	1800	< 4.9 U	< 0.97 U	66 J		< 2.9 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.02	855.02	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	14	9400 B	500	< 0.067 U	22	2500	< 5.7 U	< 1.1 U	110		< 3.4 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.46	855.46	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	10	8300 B	440	< 0.063 U	22	1900	< 5.1 U	< 1.0 U	88 J		< 3.0 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	11	8600 B	450	< 0.060 U	20	1900	< 5.1 U	< 1.0 U	100		< 3.1 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.92	855.92	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	20	4900 B	750	< 0.065 U	31	2400	< 5.2 U	< 1.0 U	70 J		< 3.1 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.63	855.63	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	29	3400	400	0.34	19	1600	< 4.9 U	< 0.99 U	61 J		< 3.0 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.70	855.70	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	10	4700	430	< 0.061 U	19	1800	< 4.9 U	< 0.99 U	69 J		< 3.0 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	18	4300	600	< 0.061 U	25	2100	< 5.1 U	< 1.0 U	65 J		< 3.1 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	17	4300	530	< 0.062 U	25	1900	< 5.3 U	< 1.1 U	65 J		< 3.2 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.38	855.38	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	13	9100	610	< 0.065 U	26	1300	< 5.6 U	< 1.1 U	92 J		< 3.3 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.80	854.80	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	11	8600	420	< 0.064 U	20	1000	< 5.6 U	< 1.1 U	77 J		< 3.4 U

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated		12	53 T
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated		10	53
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated		11	58
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.33	855.33	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated		2.4	6.8
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.07	855.07	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated		2.0	6.8
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.89	855.89	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		15	61
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.49	855.49	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		19	72
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.63	855.63	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		17	81
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.48	855.48	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		19	73
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.43	855.43	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		20	64
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.49	855.49	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		20	70
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.15	855.15	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		20	79
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.85	854.85	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		19	90
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.22	855.22	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		18	78 T
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.09	855.09	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		20	75
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.29	855.29	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		18	75
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.11	855.11	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		17	72
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.64	855.64	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		16	69
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.50	855.50	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		16	91
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.41	855.41	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		17	60
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.24	855.24	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		17	67
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.16	855.16	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		17	67
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.95	855.95	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		16	73
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.89	855.89	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		17	76
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.02	855.02	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		18	81
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.43	855.43	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		14	57
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.26	855.26	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		19	81
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		16	68
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.85	853.85	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		18	77
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.02	855.02	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		19	82
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.46	855.46	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		15	62
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		19	79
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.92	855.92	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		20	84
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.63	855.63	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		20	83
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.70	855.70	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated		16	75
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated		14	59
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated		12	89
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated		8.2	51
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated		14	180
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated		13	95
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated		11	72
Football Field	SSHS-B3501	090120 10:30 SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated			
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated		15	70
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.63	855.63	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		23	81
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.48	855.48	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		20	75
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.43	855.43	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		21	65
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.49	855.49	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		19	59
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.15	855.15	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		21	72
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.85	854.85	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		24	72
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.22	855.22	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		24	77
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.09	855.09	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		18	67
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.29	855.29	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		20	64
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.11	855.11	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		22	66
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.64	855.64	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		17	70
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.50	855.50	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		17	81
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.41	855.41	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		20	87
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.24	855.24	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		23	70
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.16	855.16	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		21	69
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.95	855.95	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		17	61
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.89	855.89	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		24	67
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.43	855.43	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		21	66
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.26	855.26	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		19	58
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		18	56
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.85	853.85	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		18	61
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.02	855.02	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		23	85
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.46	855.46	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		20	76
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		20	85
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.92	855.92	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		22	76
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.63	855.63	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated		18	77
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.70	855.70	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated		18	64
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		21	71
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		20	72
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.38	855.38	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated		19	80 B
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.80	854.80	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated		15	63 B

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III-VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.40	855.40	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	8000 T	< 5.1 U	8.2 J	60 T	0.23 J	0.19 J	100000 T	13		5.7	21	18000 T
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated	7700	< 0.41 U	6.5	57	0.37 J	0.081 J	26000	11		6.7	27	18000
Football Field	SSHS-B2025	072718 09:00_PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated	10000	< 0.41 U	7.8	120	0.47 J	< 0.044 U	7700	15		8.9	33	22000
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated	9600	0.6 J	8.7	190	0.42 J	< 0.042 U	12000	21		8.6	88	33000
Northern Athletic Field	SSHS-B3118	012120 08:10_SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	9800	< 0.37 U	7.2	120	0.48	0.18 J	12000	15		8.7	19	19000
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	8700	< 0.36 UJ	10	92	0.45	0.063 J	16000	14		7.3	17	16000
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	7800	< 0.32 U	6.3	77	0.34 J	0.066 J	22000	10		6.7	19	16000
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	9200	0.42 J	6.9	83	0.42	0.087 J	3000	11		7.8	15	17000
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	9500	0.35 J	6.5	94	0.45	0.075 J	4600	12		7.9	15	18000
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	9300	< 0.30 U	6.6	93	0.43	0.099 J	5700	11		8.3	16	18000
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	8300	0.59 J	5.8	91	0.42 J	0.18 J	5700	10		7.5	16	16000
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	8100	0.59 J	7.3	85	0.43	0.27 J	8100	14		6.6	16	18000
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	8200	0.60 J	5.7	92	0.36 J	0.20 J	6900	11		7.6	18	16000
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	8300	0.48 J	6.0	94	0.42 J	0.19 J	5800	10		7.7	16	16000
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	8800	0.65 J	6.9	94	0.43 J	0.48 J	5100	11		8.2	17	17000
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	7900	0.34 J	5.8	84	0.38	0.24 J	6400	10		7.6	15	15000
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	8100	0.78 JT	8.6	110	0.45 J	0.42 J	3000	11		7.6	22	15000
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	5900	< 0.36 U	4.2	65	0.29 J	0.15 J	2700	8.0		5.6	11	12000
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	6400	< 0.40 U	4.7	70	0.32 J	0.16 J	8500	8.8		6.3	15	13000
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	7500	< 0.36 U	5.9	83	0.36 J	0.26 J	5900	10		7.3	16	15000
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	7400	< 0.34 U	6.0	88	0.35 J	0.63	13000	10		7.1	19	16000
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	8400	< 0.33 U	5.6	89	0.41 J	0.18 J	5700	11		8.1	15	16000
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	9200	0.35 J	5.5	98	0.40	0.31 J	4800	11		5.2	18	16000
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	7700	0.34 J	6.3	98	0.38	< 0.068 U	12000	11		7.1	17	19000
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	8300	0.37 J	6.3	98	0.42	< 0.078 U	3900	12		7.4	19	21000
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	8100	0.44 J	9.5	100	0.42	< 0.073 U	14000	11		7.7	19	21000
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	7900	0.88 J	8.7	120	0.47	0.91	1800	14		6.8	47	30000
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	10000	< 0.38 U	7.8	84	0.47 J	0.20 J	7000	14		10	20	21000
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	7400	< 0.34 U	6.1	88	0.39 J	0.26 J	3000	10		7.2	20	14000
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	9100	< 0.35 U	6.8	100	0.42 J	0.32 J	2800	12		8.0	17	16000
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	7700	< 0.37 U	5.5	120	0.35 J	0.22 J	1900	10		6.8	15	14000
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	8900	0.40 J	6.9	130	0.42 J	0.17 J	1700	11		7.2	21	16000
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	7400	< 0.37 U	8.2	80	0.40 J	0.70	9500	12		6.4	23	16000
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	7300	< 0.33 U	5.2	67	0.34 J	0.19 J	9500	10		6.5	18	15000
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	8700	< 0.39 UT	6.3	65	0.40 J	0.090 J	8800 T	13		8.7	16	19000
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	7400	< 0.4 U	5.9	78	0.32 J	0.11 J	31000	11		6.1	24	17000
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	7200	0.84 J	6.6	73	0.28 J	0.26 J	21000	11		7.1	23	16000
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	5600	< 0.24 U	5.8	74	0.22 J	0.089 J	29000	8.8		5.4	32	14000
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	6600	< 0.23 U	4.9	42	0.28 J	< 0.055 U	3000	7.3		4.6	22	12000
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	5700	0.54 J	5.2	49	0.27 J	< 0.067 U	17000	6.7		5.1	19	12000
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	5700	0.40 J	3.8	38	0.25 J	0.076 J	44000	7.3		5.1	16	13000
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	3700	0.75 J	16	130	0.40	0.39 J	3100	11		5.6	42	27000
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	3500	0.47 J	13	110	0.37 J	0.30 J	3500	8.8		5.2	32	20000
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	6300	0.47 BJ	2.7	56	0.22 J	< 0.074 U	6100	6.6		4.2 J	9.3	10000
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	5800	0.47 BJ	4.5	28	0.22 J	< 0.059 U	1000	6.4		3.9 J	13	10000
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	6200	0.38 BJ	4.8	44	0.25 J	0.075 J	4500	7.1		3.7 J	15	11000
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	6500	0.76 BJ	6.3	76	0.27 J	0.26 J	4600	9.3		4.3 J	29	12000
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	5600	0.45 BJ	4.7	50	0.23 J	0.14 J	11000	6.8		3.8 J	18	9900
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	7300	0.50 BJ	3.3	62	0.25 J	< 0.074 U	1200	7.6		4.2 J	9.8	9500
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	8100	< 0.30 U	4.2	76	0.28 J	0.12 J	18000	8.9		5.3	19	15000
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	8700	< 0.30 UT	4.3	91 T	0.34 J	0.099 J	6800 T	9.4		4.9 J	12	15000
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	7600	< 0.32 U	5.0	74	0.31 J	0.13 J	16000	9.0		5.3	16	15000
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	8800	< 0.29 U	3.8	38	0.32 J	0.076 J	2200	9.3		4.8	12	15000
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	10000	0.38 J	8.6	92	0.51	0.25 J	6600	14		10	22	22000
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	7000	< 0.30 U	5.3	79	0.33 J	0.26 J	24000	9.0		5.1	28	13000
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	5700	< 0.32 U	6.1	51	0.26 J	0.21 J	45000	8.4		5.6	22	14000
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	8500	< 0.30 U	5.6	71	0.35 J	0.16 J	11000	11		5.6	26	15000
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	5800	< 0.26 U	3.4	33	0.21 J	0.15 J	33000	7.2		4.5	21	13000
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	6400	< 0.25 U	4.6	62	0.32 J	0.15 J	21000	7.8		5.6	11	12000
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	8600	1.0	17	150	0.54	1.2	2100	17		8.3	77	37000
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	11000	< 0.33 U	13	120	0.65	1.1	3800	23		10	120 B	24000
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	8400	< 0.26 U	14	210	0.48	2.0	4300	87		7.9	89	22000
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	7300	0.46 J	11	92	0.40	0.74	1900	18		7.3	340	24000
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	9800	< 0.29 U	11	85	0.41	2.5	3700	120		7.8	87	21000
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	11000	0.31 J	11	88	0.48	0.46	1600	13		7.4	41	18000
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	8600	0.32 J	15	110	0.47	0.63	2300	30		7.1	3600	19000
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	7400	< 0.31 U	9.8	68	0.38 J	1.5	2900	16		7.2	43	16000
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	8900	1.0	15	110	0.51	3.9	15000	24		8.5	56	27000
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	8300	0.68	14	140	0.48	0.54 J	2100	18		8.4	110	53000
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	8700	0.67 J	16	120	0.55	1.2	4900	18		8.2	74	24000
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	9300	0.47 J	11	94	0.47	0.99	3300	17		8.6	54	21000
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	12000	< 0.34 U	14	130	0.63	1.1	6700	21		11	44	24000
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	8500	< 1.5 U	20	160	0.78 J	0.78 J	3600	17		8.7 J	54	25000
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	9400	< 0.21 U	12	87	0.52	0.98	3600	22		9.3	76 B	21000

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.40	855.40	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	8.5 T	19000 T	470	< 0.063 U	14	1200 T	< 5.1 U	< 1.0 U	110		< 3.1 UT
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated	38	3400	410	0.089	16	680	< 0.62 U	< 0.13 U	65 J		< 0.25 U
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated	43	3100	550	0.34	23	880	< 0.62 U	< 0.13 U	95 J		0.47 J
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated	280	3400	580	0.25	32	760	0.83 J	< 0.12 U	100 J		0.36 J
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	21	4100	580	0.088	20	1200	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	20	7700	400	0.03 J	16	1500	< 0.55 U	< 0.11 U	< 65 U		< 0.34 UJ
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	16	4000	380	< 0.019 U	17	980	0.78 J	< 0.099 U	< 57 U		< 0.30 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	24	2600	470	0.033	17	1100	< 0.41 U	< 0.084 U	< 48 U		< 0.26 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	19	3200	450	< 0.023 U	18	1500	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	21	3600	510	< 0.023 U	19	1400	0.61 J	< 0.094 U	< 54 U		< 0.29 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	25	2900	430	0.046 J	18	1400	0.63 J	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	35	2300	390	0.051 J	16	1500	< 0.41 U	< 0.070 U	59 J		< 0.35 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	26	3400	420	0.046 J	18	900	0.51 J	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	29	2900	440	0.048 J	18	1400	0.44 J	< 0.073 U	61 J		< 0.36 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	33	2900	470	0.053 J	18	1600	0.70 J	< 0.080 U	69 J		< 0.39 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	24	3300	440	0.043 J	17	1300	< 0.36 U	< 0.062 U	57 J		< 0.31 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	84 T	2100	460	0.12	18	1200	0.75 J	0.12 J	74 J		< 0.38 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	14	2000	360	0.034 J	12	800	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	20	3200	410	0.039 J	14	760	0.69 J	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	27	3000	470	0.064 J	16	990	< 0.47 U	< 0.081 U	69 J		< 0.40 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	52	4000	490	0.095 J	17	990	0.61 J	< 0.076 U	69 J		< 0.38 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	21	3500	480	0.038 J	18	890	0.51 J	< 0.074 U	64 J		< 0.36 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	57	2200	420	0.086 B	13	820 B	0.63 J	< 0.099 U	< 49 U		0.88 J
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	24	4100	510	0.096	15	760	< 0.43 U	< 0.097 U	49 J		< 0.26 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	38	3000	490	0.038	16	1000	< 0.49 U	< 0.11 U	56 J		< 0.30 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	22	4300	530	0.11	16	790	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	110	1800	590	0.15	23	650	1.7	< 0.11 UT	< 56 U		< 0.31 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	35	4000	600	0.045 J	21	910	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	39	1900	400	0.093 J	17	930	0.78 J	< 0.077 U	86 J		< 0.38 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	41	2300	460	0.096 J	19	1300	0.58 J	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	40	2100	430	0.22	16	1200	0.60 J	< 0.083 U	66 J		< 0.41 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	45	2000	510	0.10 J	18	660	0.94 J	< 0.090 U	< 70 U		< 0.44 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	100	4200	410	0.12 J	16	860	1.1 J	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	40	3100	490	0.053 J	15	620	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	15	3400	450	0.031 J	20	690	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	30	14000	360	0.68	17	670	< 0.6 U	0.42 J	91 J		< 0.24 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	77	4600	400	0.058 J	22	780	< 0.37 U	< 0.064 U	70 J		< 0.31 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	13	4700	420	< 0.022 U	47	610	0.54 J	< 0.082 U	51 J		< 0.22 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	10	1800	290	0.033	12	440	< 0.35 U	< 0.078 U	< 39 U		< 0.21 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	20	3100	390	0.056	12	540	0.50 J	< 0.095 U	66 J		< 0.26 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	7.4	6400	260	0.039	14	530	1.1	< 0.10 U	63 J		< 0.28 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	88	900	150	0.12	190	440 J	1.5	< 0.093 U	64 J		0.36 J
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	72	960	120	0.18	17	450 J	1.4	< 0.11 U	62 J		< 0.29 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	14	2500	240	0.051	8.8	420 J	< 0.46 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	10	1500	210	0.073	10	410	0.37 J	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	23	2100	340	0.12	9.3	520	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	140	2600	240	0.31	11	540	0.58 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	51	2900	290	0.18	9.9	480	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	20	1500	210	0.051	9.3	400 J	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	17	4900	430	0.047	13	500	< 0.46 U	< 0.10 U	84 J		< 0.28 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	15	2900	330	0.025 J	12	550	< 0.46 U	< 0.10 U	110 J		< 0.29 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	16	5200	460	0.035	13	570	< 0.49 U	< 0.11 U	94 J		< 0.30 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	9.3	2400	210	0.10	12	420 J	< 0.44 U	< 0.099 U	91 J		< 0.27 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	42	2600	810	0.12	15	650	< 0.47 U	< 0.11 U	170 J		< 0.29 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	73	3200	280	0.95	15	590	< 0.46 U	< 0.10 U	230 J		< 0.28 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	47	6500	340	0.036	13	640	0.58 J	< 0.11 U	85 J		< 0.30 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	36	3300	390	0.069	14	590	< 0.46 U	< 0.10 U	73 J		< 0.28 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	9.0	4700	320	0.062	12	480	< 0.40 U	< 0.090 U	58 J		< 0.25 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	14	2400	330	< 0.019 U	12	660	< 0.38 U	< 0.085 U	100 J		< 0.23 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	100	1600	460	0.065	29	550	0.94 J	< 0.11 U	71 J		< 0.29 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	83	2900	570 B	0.27	24	1000	0.80 J	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	200	1800	540	0.12	51	700	1.1	0.14 J	67 J		< 0.25 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	91	1500	560	0.047	120	440 J	0.54 J	< 0.097 U	54 J		< 0.26 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	110	1600	500	0.070	70	530	0.66 J	< 0.10 U	52 J		< 0.28 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	23	2100	480	0.056	25	710	0.77 J	< 0.089 U	< 44 U		0.38 J
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	130	1600	410	0.061	43	460	0.49 J	0.24 J	81 J		< 0.26 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	41	1800	460	0.034	23	730	< 0.47 U	< 0.11 U	68 J		0.29 J
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	350	3100	630	0.22	21	990	0.52 J	< 0.096 U	67 J		< 0.26 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	120	1600	560	0.27	33	470	0.64 J	< 0.071 U	61 J		< 0.97 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	120	2100	540	0.11	33	710	0.77 J	< 0.10 U	61 J		< 0.28 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	77	2400	470	0.20	26	750	0.55 J	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	77	3600	620	0.078	26	1200	0.85 J	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	50	1900 J	450	0.11	22	840 J	3.1 J	< 0.52 U	< 260 U		< 1.4 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	80	2500	540	0.28	24	700	0.39 J	< 0.071 U	61 J		< 0.19 U

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.40	855.40	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated		12	63
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated		13	89
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated		15	96
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated		21	320
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated		13	61
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated		14	70
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated		12	61
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated		14	75
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated		13	70
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated		13	82
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated		12	110
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated		16	120
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated		12	130
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated		12	140
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated		13	310
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated		11	190
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated		13	200
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated		8.2	73
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated		9.0	82
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated		11	120
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated		11	500
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated		12	98
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated		15	300 B
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		12	59
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		13	81
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		12	63
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated		18	310
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated		16	91 T
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated		11	290
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated		15	160
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated		11	280
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated		13	250
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated		12	590
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated		12	83
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated		12	62
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated		14	74
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated		11	140
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated		9.9	52
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated		9.8	43
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated		9.4	53
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated		8.4	53
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		12	130
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		12	130
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		12	38
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated		8.2	41
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated		11	45
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		12	140
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		9.4	55
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		11	37
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		12	59
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated		12	52
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		11	55
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated		13	48
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated		18	80
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated		12	94
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated		11	69
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated		13	62
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated		8.2	53
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated		8.3	38
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated		18	250
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		21	800
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated		36	690
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated		16	220
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		16	1100
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated		18	74
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated		18	240
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		14	450
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated		17	1200
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated		17	270
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		24	360
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		17	380
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated		22	400
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated		27	180
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		19	570

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III-VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	8100	0.27 J	12	92	0.49	0.76	3300	14		7.9	51 B	18000
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	6400	0.27 J	7.4	47	0.32	0.37 J	6800	8.5		5.7	27 B	13000
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	8200	0.34 J	9.2	59	0.37	0.48	2100	12		7.1	35 B	18000
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	6900	< 0.31 U	10	40	0.35 J	0.39 J	1700	10		7.2	29 B	17000
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	9600	0.34 JT	8.7	90	0.49	0.60	22000	15		7.6	57	26000
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	6700	0.26 J	6.2	77	0.26 J	0.26 J	28000	11		5.9	33	16000
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	6800	< 0.26 U	5.9	68	0.28 J	0.25 J	32000	9.0		5.9	29	17000
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	6000	< 0.26 U	6.4	69	0.25 J	0.25 J	30000	8.9		5.8	27	15000
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	6400	< 0.18 U	5.8	68	0.23 J	0.31	71000	10		5.9	20	14000
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	7900	< 0.35 U	13	97	0.43 J	0.79	1900	14		7.5	44	31000
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	8000	< 0.34 U	7.7	190	0.35 J	< 0.083 U	2000	9.4		5.3 J	24	15000
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	9500	< 0.28 UT	6.4	110	0.13 J	< 0.068 U	860	10		6.6	15	18000
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	11000	< 0.30 U	6.0	78	0.43	< 0.074 U	950	11		7.5	11	18000
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	8600	< 0.28 U	6.0	140	0.35 J	< 0.068 U	2100	8.8		4.9	15	15000
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	4400	< 0.28 U	14	130	0.25 J	0.15 J	5900	11		4.5 J	130	17000
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	7700	< 0.33 U	12	110	0.28 J	1.6	5700	13		6.0	43	17000
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	7300	2.2	11	130	0.41 J	0.18 J	2000	9.5		5.5	31	13000
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	7200	< 0.23 U	6.4	94	0.27 J	0.17 J	1600	8.3		4.6	24	15000
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	7600	< 0.27 U	14	140	0.37	1.8	1800	11		5.5	41	25000
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	8700	< 0.28 U	8.1	100	0.34 J	0.33 J	2000	10		6.1	31	17000
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	8000	0.90 J	34	240	0.47	1.2 J	13000	20		11	85	110000
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	8900	0.54 J	5.6	140	0.38	0.096 J	500	9.8		4.0 J	23	13000
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	8000	0.83	9.3	82	0.44	0.26 J	2100	11		6.1	33	18000
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	9300	1.7	14	220	0.60	1.4	4000	18		6.9	76	18000
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	7500	0.36 J	3.6	120	0.31	< 0.052 U	340 J	7.9		2.9 J	16	12000
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	6900	1.2	9.9	100	0.40	0.48	1000	10		6.6	41	22000
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	8600	0.87 J	12	150	0.52	0.25 J	1900	12		6.2	36	15000
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	7700	2.1	15	620	0.55	1.0	3900	19		8.3	69	17000
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	7600	0.55 J	6.3	110	0.30 J	0.15 J	2000	10		3.8 J	20	12000
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	7100	1.6	13	290	0.47	2.0	16000	22		6.4	64	16000
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	6800	1.4	11	250	0.58	2.6	11000	14		6.3 J	260	13000
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	9500	1.0	11	160	0.53	1.1	7500	13		5.7	40	21000
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	9200	0.74 J	7.2	100	0.35 J	< 0.071 U	1200	9.3		4.8	29	17000
Northern Athletic Field	A8PH7-SCV15A	SSHS-IRM5A2-A8PH7-SCV15A-20240401	SSHS-IRM5A2-A8PH7-SCV15A	4/1/2024	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	8100	0.32 J	3.8	130	0.29 J	< 0.072 U	510	7.8		4.4 J	12	13000
Northern Athletic Field	A8PH7-SCV15C	SSHS-IRM5A2-A8PH7-SCV15C-20240401	SSHS-IRM5A2-A8PH7-SCV15C	4/1/2024	-	--	-	856.99	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	9700	< 0.34 U	5.1	51	0.31 J	< 0.082 U	460 J	10		4.9 J	16	16000
Northern Athletic Field	A8PH7-SCV15D	SSHS-IRM5A2-A8PH7-SCV15D-20240401	SSHS-IRM5A2-A8PH7-SCV15D	4/1/2024	-	--	-	854.97	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	10000	< 0.32 U	6.7	44	0.38 J	< 0.078 U	400 J	11		5.7	19	18000
Northern Athletic Field	A8PH7-SCV15E	SSHS-IRM5A2-A8PH7-SCV15E-20240401	SSHS-IRM5A2-A8PH7-SCV15E	4/1/2024	-	--	-	855.01	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	8300	< 0.31 U	5.1	40	0.31 J	< 0.076 U	410 J	9.1		5.3	19	17000
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	8300	< 0.29 U	16	180	0.40	0.56	2300	12		5.1	32	18000
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	7900	< 0.24 U	7.7	130	0.37	4.0	3700	16		5.2	37	20000
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	7100	< 0.43 U	8.7	250	0.41 J	1.4	27000	15		6.2 J	56	17000
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	9500	< 0.32 UT	4.8	140	0.38 J	0.16 J	530	10		4.3 J	13	17000
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	9100	0.60 J	8.4	370	0.48	2.5	4900	23		7.4	61	19000
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721834	Not Excavated												
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	8400	< 0.28 U	7.5	180	0.37	0.54	2000	13		4.6	28	16000
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	7800	8.7	26	1800	0.47	2.7	4200	38		9.1	460	86000
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721834	Not Excavated												
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	11000	< 0.28 U	3.2	110	0.39	0.080 J	1200	11		4.9	11	18000
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	5400	< 0.39 U	7.3	61	0.65	0.23 J	1600	11		5.8 J	35	6700
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	8900	0.29 J	6.3	120	0.47	0.51	2800	13		5.5	40	14000
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	8200	< 0.41 U	12	210	0.48 J	0.59 J	3800	13		5.7 J	26	31000
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	7800	< 0.34 U	9.1	240	0.47	0.66	3400	12		5.6	86	18000
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	6700	< 0.26 U	11	180	0.50	1.5	4900	11		6.9	45	31000
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	8800	< 0.30 U	6.3	98	0.39 J	0.53	1700	10		5.0	21	15000
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	8200	< 0.28 U	11	100	0.39	0.33 J	1900	9.3		3.8 J	21	14000
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	5200	0.47 JT	5.4 T	47 T	0.24 JT	0.10 JT	20000 T	7.3 T		6.9 T	16 T	12000
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	8100	< 0.36 UJ	7.1	66	0.36 J	0.046 J	17000	11		6.9	18	18000
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	7100	1.1 J	9.2	110	0.36 J	0.55	15000	16		7.4	48	19000
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	7400	0.56 J	10	110	0.40	0.47	8200	12		7.2	28	17000
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	9200	0.42 J	6.0	96	0.46 J	0.16 J	3900	11		8.5	15	17000
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	8100	0.74 J	6.3	89	0.39 J	0.18 J	9500	10		7.5	17	16000
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	8100	0.66 J	6.9	79	0.34 J	0.55	6500	10		5.3	30	15000
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	5300	< 0.33 U	4.6	83	0.32 J	0.15 J	24000	7.5		7.3	18	15000
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	6900	< 0.35 U	14	100	0.42 J	0.39 J	1400	9.9		5.4	37	12000
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	5500	< 0.31 U	4.3	43	0.22 J	0.10 J	26000	7.4		5.4	15	12000
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	6300	< 0.29 U	5.5	70	0.27 J	0.22 J	18000	8.6		5.4	21	13000
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	7300	< 0.33 U	6.7	49	0.27 J	0.085 J	34000	9.8		7.4	19	17000
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	5800	< 0.34 U	4.3	42	0.18 J	0.089 J	27000	7.6		5.3	15	13000
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	7900	0.54 J	6.6	70	0.34 J	0.13 J	7600	9.5		6.5	20	15000
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	9600	< 0.30 U	7.1	130	0.49	< 0.073 U	6800	13		8.3	18	22000
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	8300	0.66 J	6.7	69	0.30 J	< 0.074 U	58000	12		6.8	29	21000
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	5200	0.51 J	7.6	94	0.44	0.79	4300	10		6.0	36	17000
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	9300	0.39 J	4.2	150	0.40	0.40 J	1800	11		6.7	17	16000
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	8900	< 0.37 U	9	100	0.42 J	0.19 J	11000	11		8.6	22	20000
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated	12000	1.1 J	9.4	110	0.63	0.16 J	6600	17		9.8	41	25000

DRAFT

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	71	2100	440 B	2.7	20	550	0.59 J	< 0.082 U	40 J		< 0.22 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	100	3800	380 B	0.45	14	460	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	31	2600	460 B	0.14	19	530	< 0.43 U	< 0.096 U	< 47 U		0.26 BJ
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	17	2400	370 B	< 0.023 U	20	540	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	72	3700	820	0.094	22	690	< 0.49 UT	< 0.11 U	70 J		0.41 J
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	17	5500	380	< 0.023 U	49	550 B	< 0.37 U	< 0.083 U	58 J		< 0.23 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	20	5300	350	0.040	31	510 B	< 0.40 U	< 0.091 U	59 J		< 0.25 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	16	6400	470	0.034	44	470 B	< 0.40 U	< 0.091 U	69 J		< 0.25 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	13	8900	370	0.038	15	410 B	< 0.28 U	< 0.062 U	72 J		< 0.17 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	94	1800	530	0.085	17	450 J	< 0.54 U	0.24 J	< 59 U		< 0.33 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	57	1600	980	0.082	11	370 J	< 0.52 U	0.14 J	< 58 U		< 0.32 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	28 T	2000	500	0.069	14	320 J	< 0.43 U	0.15 J	< 47 U		< 0.26 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	15	2100	550	0.086	12	440 J	< 0.46 U	0.13 J	< 51 U		< 0.29 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	69	1500	680	0.067	9.9	320 J	< 0.43 U	0.14 J	< 48 U		< 0.26 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	110	1100	260	0.16	17	550	0.58 J	0.19 J	340 J		< 0.26 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	220	3100	450	0.19	17	880	< 0.50 U	0.18 J	65 J		< 0.31 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	230	1100	550	0.13	14	660	2.1	< 0.55 U	100 J		0.89 J
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	68	1700	370	0.10 B	12	960	< 0.36 U	0.11 J	61 J		< 0.22 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	200	1500	400	0.16 B	14	1100	< 0.41 U	0.30 J	80 J		0.58 J
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	150	1900	420	0.14 B	15	620	< 0.43 U	0.14 J	60 J		< 0.27 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	340	2300	1100	0.22	37 J	2500 J	< 5.3 U	< 0.23 U	120 J		< 0.33 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	140	1400	330	0.059	12	400 J	0.89 J	< 0.096 U	47 J		0.47 J
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	95	1600	430	0.16	14	480	0.86	< 0.16 U	46 J		0.57 J
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	450	1400	450	0.27	22	790	1.8	< 0.12 U	96 J		0.57 J
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	63	1200	300	0.048	8.8	280 J	0.67 J	< 0.15 U	< 36 U		0.34 J
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	200	1200	360	0.24	15	390 J	1.1	< 0.087 U	54 J		0.49 J
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	170	1100	440	0.076	15	530 J	1.2	< 0.12 U	99 J		0.78 J
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	2600	990	370	0.18	16	860	1.9	< 0.13 U	880		1.0 J
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	88	1200	380	0.070	9.3	360 J	< 0.41 U	< 0.092 U	47 J		0.62 J
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	1100	6300	460	1.1	16	920	2.7	< 0.12 U	91 J		0.50 J
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	460	1400	370	0.73	17	960	2.2	< 0.14 U	98 J		0.47 J
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	300	2100	440	0.19	16	1100	1.3	< 0.11 U	110 J		0.82 J
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	57	1800	430	0.086	13	690	0.88 J	< 0.10 U	< 49 U		0.64 J
Northern Athletic Field	A8PH7-SCV15A	SSHS-IRM5A2-A8PH7-SCV15A-20240401	SSHS-IRM5A2-A8PH7-SCV15A	4/1/2024	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	20	1200	810	0.051	8.4	310 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A8PH7-SCV15C	SSHS-IRM5A2-A8PH7-SCV15C-20240401	SSHS-IRM5A2-A8PH7-SCV15C	4/1/2024	-	--	-	856.99	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	9.5 J	2100	170	0.031 J	13	370 J	< 0.52 U	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	A8PH7-SCV15D	SSHS-IRM5A2-A8PH7-SCV15D-20240401	SSHS-IRM5A2-A8PH7-SCV15D	4/1/2024	-	--	-	854.97	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	11	2300	200	0.025 J	15	390 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A8PH7-SCV15E	SSHS-IRM5A2-A8PH7-SCV15E-20240401	SSHS-IRM5A2-A8PH7-SCV15E	4/1/2024	-	--	-	855.01	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated	12	2100	290	0.024 J	13	340 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	140	1500	660	0.37	13	600	0.54 J	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	380	1500	340	0.12	19	830	1.8	< 0.083 U	59 J		< 0.23 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	340	5000	500	0.29 T	21	1000	1.8	< 0.15 U	82 J		< 0.41 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	46 T	1400	640	0.043	10	390 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	240	2100	510	0.26	19	760	1.5	< 0.11 U	75 J		< 0.30 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721834	Not Excavated											
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	130	1500	330	0.30	13	500	0.57 J	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	38000	1600	770	0.92	32	860	1.6	17	140 J		< 1.5 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721834	Not Excavated											
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	21	1800	470	0.065	15	730	0.49 J	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	67	500 J	97	0.19	12	460 J	< 0.59 U	< 0.13 U	78 J		< 0.37 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	90	1500	350	0.14	14	750	0.76 J	< 0.090 U	57 J		< 0.25 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	160	1500	660	0.16	14	900	1.5	< 0.14 U	< 70 U		< 0.39 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	320	1300	500	0.26	15	800	1.6	< 0.12 U	77 J		< 0.32 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	180	1100	470	0.14	18	790	2.2	< 0.090 U	88 J		< 0.25 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	49	1500	460	0.077	12	700	0.81 J	< 0.10 U	54 J		< 0.28 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	39	1200	370	0.11	10	590	1.2	< 0.095 U	51 J		< 0.26 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	21 T	2600 T	420	0.087	11 T	430 JT	< 0.46 UT	< 0.10 UT	150 JT		< 0.28 UT
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	22	4100	380	< 0.024 U	17	880	< 0.54 U	< 0.11 U	< 63 U		< 0.34 UJ
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	130	2600	390	0.21	23	750	0.78 J	0.10 J	77 J		< 0.35 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	92	3000	380	0.11	20	760	0.91 J	< 0.063 U	83 J		< 0.31 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	17	3000	460	0.030 J	19	850	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	35	3700	430	0.058 J	18	1200	0.54 J	< 0.069 U	59 J		< 0.34 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	59	2900	320	0.095 J	15	690	0.48 J	< 0.067 U	63 J		< 0.33 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	11	5800	470	0.031 J	13	690	< 0.43 U	< 0.074 U	71 J		< 0.37 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	150	1100	330	0.30	13	530	2.6	< 0.078 U	110 J		< 0.39 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	10	6600	350	0.031 J	13	490	< 0.40 U	< 0.069 U	71 J		< 0.34 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	60	4400	370	0.17	13	550	0.46 J	< 0.066 U	64 J		< 0.33 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	12	4200	450	0.031 J	18	630	< 0.43 U	< 0.074 U	80 J		< 0.36 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	12	6700	330	< 0.018 U	13	480	< 0.44 U	< 0.076 U	80 J		< 0.37 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	30	3000	410	0.062 J	15	550	< 0.46 U	< 0.079 U	73 J		< 0.39 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	36	3600	590	0.053	18	770	< 0.46 U	< 0.10 U	130 J		< 0.28 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	20	13000	490	< 0.026 U	17	790	< 0.46 U	< 0.10 U	110 J		< 0.28 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	130	960	280	0.066	18	560	1.4	< 0.10 UT	110 J		< 0.28 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	27	1800	1100	0.026 J	14	540	1.2	< 0.10 UT	< 51 U		< 0.28 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	24	4500	720	0.047	20	820	< 0.56 U	< 0.11 U	< 65 UJ		< 0.35 U
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated	37	3800	530	0.29	27	1100	< 0.62 U	< 0.13 U	72 J		< 0.38 U

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		16	300
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		11	65
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		15	130
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		13	96
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated		21	230
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated		11	66
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated		10	64
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated		10	66
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated		10	52
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		16	750
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		13	210
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated		18	81
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		17	94
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		14	73
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		15	230
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		16	2000
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated		17	480
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		13	410
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated		16	650
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		15	600
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated		21 J	1500
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		16	85
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		16	100
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		23	440
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		14	58
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated		15	250
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated		34	140
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated		32	770
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated		19	100
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		17	850
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		16	1100
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		18	420
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		14	90
Northern Athletic Field	A8PH7-SCV15A	SSHS-IRM5A2-A8PH7-SCV15A-20240401	SSHS-IRM5A2-A8PH7-SCV15A	4/1/2024	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated		12	74
Northern Athletic Field	A8PH7-SCV15C	SSHS-IRM5A2-A8PH7-SCV15C-20240401	SSHS-IRM5A2-A8PH7-SCV15C	4/1/2024	-	--	-	856.99	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated		14	58
Northern Athletic Field	A8PH7-SCV15D	SSHS-IRM5A2-A8PH7-SCV15D-20240401	SSHS-IRM5A2-A8PH7-SCV15D	4/1/2024	-	--	-	854.97	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated		16	55
Northern Athletic Field	A8PH7-SCV15E	SSHS-IRM5A2-A8PH7-SCV15E-20240401	SSHS-IRM5A2-A8PH7-SCV15E	4/1/2024	-	--	-	855.01	0 - 2 ft	0 - 2 ft	1801716851	Not Excavated		14	91
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		16	280
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		14	270
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		16	740
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		16	92 T
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		19	1600
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721834	Not Excavated			
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		15	380
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		25	2600
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721834	Not Excavated			
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		17	86
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		21	120
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		18	190
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		16	460
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated		17	620
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		18	320
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		15	87
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		15	85
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated		9.8 T	66 T
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated		13	96
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated		15	280
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated		13	310
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated		13	88
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated		12	120
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated		13	350
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated		16	89
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated		17	160
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated		8.7	59
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated		10	120
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated		11	73
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated		8.6	68
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated		13	87
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated		15	88
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated		14	78
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated		14	260
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated		15	91
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated		13	92
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated		17	78

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III-VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	9000	0.83 J	9.7	110	0.47	0.58 J	4000	13		6.7	26	17000
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	8700	< 0.25 UT	5.9	90	0.41	0.35 J	11000	11		7.0	22	17000
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	6300	< 0.26 U	5.3	69	0.35 J	0.27 J	13000	12		6.3	19	14000
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	8300	< 0.34 U	5.1	92	0.44 J	0.25 J	7000	13		7.4	20	18000
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	8400	< 0.30 U	7.0	70	0.38	0.27 J	8300	11		6.3	13	19000
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	7900	< 0.21 U	5.9	100	0.49	0.27 J	7100	12		9.7	20	17000
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	11000	< 0.36 U	10	94	0.49 J	0.058 J	2700	14		13	20	25000
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	8700	< 0.43 UT	6.8	78	0.38 J	0.25 J	17000 T	12		7.6	22	18000
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	6700	< 0.32 U	5.1	53	0.30 J	0.076 J	13000	8.6		5.4	24	14000
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	8200	< 0.35 U	6.6	68	0.38 J	0.16 J	1500	10		7.4	21	17000
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	7900	< 0.36 U	5.8	70	0.37 J	0.15 J	4400	10		6.9	17	16000
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	7800	0.45 J	5.6	72	0.34 J	0.13 J	3000	9.9		6.9	16	16000
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	6400	< 0.28 U	8.8	81	0.37 J	0.26 J	11000	9.6		6.0	28	15000
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	7300	< 0.38 U	16	140	0.58	0.95	4100	13		7.1	45	19000
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	8400	0.50 J	8.3	130	0.43 J	0.30 J	1900	11		8.1	23	16000
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	8900	0.52 J	7.7	110	0.44 J	0.17 J	1400	11		6.6	22	17000
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	8600	< 0.37 U	6.3	81	0.39 J	0.14 J	3300	11		7.6	19	16000
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	9100	0.38 JT	5.3	96	0.40 J	0.097 J	1500	11		6.8	12	15000
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	7600	< 0.38 U	5.7	71	0.37 J	0.12 J	1700	9.2		6.7	17	15000
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	9500	< 0.35 U	5.1	38	0.35 J	0.068 J	580	10		7.3	23	18000
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	6800	< 0.37 U	6.2	86	0.36 J	0.20 J	2000	8.5		5.5	17	13000
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	6600	< 0.39 UT	5.1	95	0.31 J	1.0	8000 T	11		5.1	19	12000
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	8700	< 0.39 UT	6.3	65	0.40 J	0.090 J	8800 T	13		8.7	16	19000
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	8300	0.52 JT	6.5	68	0.34 J	0.19 J	25000	12		6.7	17	17000
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	8300	< 0.33 U	7.4	63	0.23 J	0.31 J	37000	11		6.5	18	18000
Northern Athletic Field	SSHS-B48	13 SEP 00B48_0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated		< 1.16	4.07	58.5	< 0.578	< 0.578		8.02		< 5.78	8.18	
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	7800	0.36 J	7.1	130	0.45	0.08 J	2800	11		7.1	29	18000
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	5700	< 0.34 U	4.5	58	0.21 J	0.099 J	29000	7.8		5.4	16	12000
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	5600	< 0.34 U	4.4	52	0.20 J	0.13 J	36000	7.7		5.2	17	13000
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	7800	0.69 J	9.9	130	0.48	0.55	6200	14		7.7	57	19000
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	5900	0.80 J	5.2	61	0.21 J	0.18 J	27000	8.0		5.2	16	13000
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	7900	0.67 J	6.2	63	0.33 J	0.37 J	4500	9.3		5.7	20	15000
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	7800	0.72 J	6.2	80	0.35 J	0.21 J	12000	9.7		7.4	16	15000
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	6900	< 0.29 U	12	130	0.43	0.47	2300	12		6.1	32	14000
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	5700	< 0.35 U	4.4	55	0.26 J	0.12 J	12000	7.7		5.4	13	12000
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	5100	< 0.26 U	4.2	54	0.21 J	0.15 J	42000	7.2		5.4	15	11000
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	8000	< 0.34 U	7.0	67	0.35 J	0.33 J	10000	11		7.6	21	17000
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	5400	< 0.30 U	3.9	51	0.18 J	0.14 J	32000	7.1		5.0	15	12000
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	7000	< 0.35 UT	5.0	68 T	0.30 J	0.12 J	8500 T	8.4		5.3	17	13000
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	11000	< 0.41 U	6.0	94	0.51 J	0.084 J	1400	12		8.7	13	18000
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	6600	< 0.38 U	5.9	34	0.32 J	0.059 J	590	7.6		5.8	16	14000
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	7700	< 0.36 U	4.9	80	0.33 J	0.097 J	6100	9.0		5.7	17	15000
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	9400	< 0.33 U	4.8	48	0.36 J	0.067 J	990	10		7.4	16	17000
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	7200	< 0.33 U	5.9	32	0.36 J	0.051 J	610	8.1		6.0	16	14000
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	7900	< 0.36 U	5.6	57	0.35 J	0.11 J	1600	9.5		6.5	17	15000
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	8900	< 0.35 UT	6.0	76	0.40 J	0.075 J	1300	9.4		6.0	15	15000
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	9500	< 0.33 U	5.4	83	0.44 J	0.10 J	1900	11		8.0	12	17000
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	7800	< 0.35 U	7.4	110	0.40 J	0.16 J	3400	11		7.5	15	17000
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	7600	< 0.34 U	5.5	74	0.39 J	0.14 J	4400	9.8		7.3	14	16000
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	7700	< 0.31 U	5.5	100	0.40 J	0.34 J	2200	10		7.4	180	16000
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	9100	0.46 J	7.5	110	0.48	0.87	1800	12		7.7	42	21000
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	6900	0.58 J	11	91	0.82	0.29 J	3000	11		9.7	46	8300
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	9500	0.42 JT	6.3	150	0.47	0.47 J	12000 T	12		12	24	18000
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated	10000	< 0.39 U	7.5	79	0.4 J	0.093 J	810	13		7.1	27	19000
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated	8100	0.79 J	11	100	0.41 J	0.19 J	3200	14		6	67	22000
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated	11000	0.58 J	6.8	130	0.49 J	0.066 J	2200	13		7.7	17	18000
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated	12000	0.42 J	7.1	56	0.48 J	0.049 J	470 J	13		7.5	16	20000
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated	10000	0.44 J	6	99	0.4 J	0.068 J	590 J	11		6.5 J	23	18000
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated	8700	< 0.39 UJ	8.1	67	0.42 J	0.11 J	2900 J	10		6.8	26	18000
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	8700	< 0.39 U	8.1	85	0.43 J	0.17 J	10000	12		6.7	23	16000
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated	7000	< 0.36 U	6.6	38	0.31 J	0.13 J	3000	11		6.4	18	17000
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	7400	< 0.33 UJ	6.2	43	0.29 J	0.076 J	480	8.3 J		5.4	15	14000
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	9600	0.54 J	8	60	0.37 J	0.11 J	12000	11		6.8	30	18000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	130	2300	500	0.089	17	660	0.75 J	< 0.12 U	< 71 U		< 0.38 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	62	5500	440	0.076 B	17	770	0.65 J	< 0.087 U	47 J		0.70 J
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	40	3400	410	0.026 J	17	640	0.59 J	< 0.088 U	72 J		< 0.27 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	43	8000	460	< 0.025 U	18	950	< 0.54 U	< 0.12 U	65 J		< 0.33 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	14	3800	380	< 0.024 U	16	590	< 0.42 U	< 0.10 U	< 47 U		< 0.26 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	15	3900	610	< 0.025 U	20	690	0.57 J	< 0.073 U	65 J		< 0.31 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	23	3600	570	0.023 J	25	1100	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	62 T	6900 T	480 T	0.050 J	19	890	< 0.56 U	< 0.096 U	< 74 U		< 0.47 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	26	2100	300	< 0.016 U	14	600	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	24	2300	500	0.066 J	18	700	0.76 J	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	23	3000	410	0.054 J	17	960	0.63 J	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	28	2400	430	0.054 J	16	810	0.56 J	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	54	5100	340	0.085 J	19	570	0.65 J	< 0.063 U	71 J		< 0.31 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	130	1500	370	0.24	24	480 J	0.92 J	< 0.086 U	67 J		< 0.42 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	52	1700	670	0.094 J	16	540 J	0.71 J	< 0.093 U	< 72 U		< 0.46 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	48	1800	550	0.092 J	15	640	0.97 J	< 0.095 U	< 73 U		< 0.47 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	32	2700	470	0.058 J	18	930	0.49 J	< 0.083 U	71 J		< 0.41 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	15	2000	480	0.058 J	15	600	0.68 J	< 0.070 U	140 J		< 0.35 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	23	2100	480	0.065 J	15	900	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	12	2700	320	0.030 J	18	710	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	70	1700	390	0.091 J	13	850	0.71 J	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	220 T	3000 T	420	0.086 J	12	950	1.0 J	< 0.089 U	100 BJ		< 0.44 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	15	3400	450	0.031 J	20	690	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	21 T	3200	440	0.040 T	16	640	0.88 J	< 0.10 U	72 J		< 0.33 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	13	6400	470	< 0.022 U	16	650	< 0.43 U	< 0.11 U	120 J		< 0.27 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	8.15			< 0.0578	12		< 0.578	< 1.16			< 1.16
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	44	2000	350	0.084	19	890	< 0.48 U	< 0.099 U	< 57 U		< 0.3 UJ
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	15	6200	370	0.048 J	13	440 J	< 0.45 U	< 0.077 U	69 J		< 0.38 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	20	6800	410	0.034 J	13	550	< 0.45 U	< 0.077 U	83 J		< 0.38 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	110	2800	390	0.14	23	790	0.73 J	< 0.064 U	85 J		< 0.32 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	36	6700	350	0.053 J	13	750	< 0.47 U	< 0.081 U	91 J		< 0.40 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	29	2600	330	0.058 J	15	910	0.59 J	< 0.070 U	58 J		< 0.35 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	20	4100	470	0.053 J	17	1200	< 0.43 U	< 0.074 U	64 J		< 0.37 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	170	1500	400	0.28	14	830	2.1	0.097 J	82 J		< 0.33 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	12	4300	350	0.035 J	13	610	< 0.46 U	< 0.080 U	62 J		< 0.39 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	20	4400	360	0.050 J	13	600	< 0.35 U	< 0.060 U	67 J		< 0.29 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	38	4300	420	0.075 J	18	750	0.59 J	< 0.076 U	69 J		< 0.37 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	17	6600	360	0.041 J	13	470	< 0.39 U	< 0.068 U	87 J		< 0.33 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	30 T	2600	410	0.055 J	13	390 J	< 0.45 U	< 0.078 U	75 J		< 0.39 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	11	2700	440	0.036 J	20	950	< 0.54 U	< 0.093 U	< 72 U		< 0.46 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	7.7	1600	350	0.034 J	13	520 J	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	22	3100	400	0.049 J	14	540	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	8.3	2200	430	0.048 J	17	530	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	7.4	1800	320	0.034 J	14	550	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	17	2000	360	0.051 J	15	750	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	15 T	1900	440	0.041 J	13	440 J	0.49 J	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	12	2800	390	0.032 J	18	830	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	41	2600	600	0.050 J	16	900	< 0.46 U	0.091 J	< 62 U		< 0.39 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	21	2200	420	0.037 J	17	840	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	38	2100	400	0.054 J	17	600	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	90	2000	590	0.081	24	660	1.1	< 0.089 UT	< 44 U		< 0.24 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	250	380 J	170	0.12	19	480 J	< 0.62 U	< 0.14 UT	220 J		< 0.38 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	66	5400 T	1200	0.13	15	610	1.6	< 0.10 UT	83 J		< 0.28 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated	15	2300	690	0.03 J	17	910	< 0.59 U	< 0.12 U	42 J		< 0.37 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated	96	1800	480	0.17	24	620	0.66 J	< 0.12 U	77 J		< 0.37 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated	20 J	2500	590	0.032 J	18	780	< 0.61 U	< 0.12 U	60 J		< 0.38 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated	12	2500	280	0.022 J	16	780	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated	20	2000	460	0.065	14	550 J	< 0.66 U	< 0.14 U	35 J		< 0.41 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated	20	2300	510	0.28 J	16	610	< 0.59 U	< 0.12 U	57 J		< 0.37 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	33	3000	420	0.073	22	740	0.9 J	< 0.12 U	71 J		< 0.37 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated	11	2500	610	< 0.024 U	15	660	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	11	1600	470 J	< 0.023 U	11	430 J	< 0.49 U	< 0.1 U	< 58 U		< 0.31 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	17	5900	460	0.023 J	17	720	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U

TABLE 6-2B
Shallow Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated		17	110
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated		13	100 B
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated		11	58
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated		12	55
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated		12	62
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated		10	58
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated		16	81 T
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated		13	120
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated		10	60
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated		12	85
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated		11	170
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated		12	94
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated		13	97
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated		19	150
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated		14	89
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated		14	79
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated		13	82
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated		14	58
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated		11	86
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated		13	62
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated		10	140
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated		11	590
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated		12	62
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated		11	66
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated		16	100
Northern Athletic Field	SSHS-B48	13 SEP 00B48_0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 57.8	14.2	39.4
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated		15	60
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated		9.2	57
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated		9.0	76
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated		16	340
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated		11	100
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated		12	240
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated		12	140
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated		15	190
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated		8.7	64
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated		8.3	81
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated		12	170
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated		9.2	76
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated		11	64
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated		14	58
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated		9.7	49
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated		11	68
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated		13	99
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated		11	50
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated		12	76
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated		13	52
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated		13	62
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated		11	130
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated		11	68
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated		11	160
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated		17	570
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated		25	130
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated		20	91 T
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated		18	67
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated		18	90
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated		16	59
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated		18	51
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated		17	60
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated		14	59
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated		13	68
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated		11	53
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated		11	47 J+
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated		15	57

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated			2.64		0.092 J		0.11 J				0.21 J
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated			2.64		0.092 J		0.11 J				0.21 J
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated			ND		< U		< U				< U
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated			2.28		< U		0.1 J				0.25 J
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated			2.69		0.092 J		0.11 J				0.21 J
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			5.37		< U		0.12 J				0.46
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated			1.4527	< 0.001 U	0.03	< 0.015 U	0.023	< 0.049 U	< 0.023 U	0.069 J	0.12
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated			0.138	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.38 U	< 0.78 U	< 0.078 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			0.75	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.4 U	< 0.8 U	0.071 J
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			0.182	< 0.082 U	< 0.082 U	< 0.82 U	< 0.082 U	< 0.82 U	< 0.4 U	< 0.82 U	< 0.082 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated			0.339	< 0.079 U	< 0.079 U	< 0.79 U	< 0.079 U	< 0.79 U	< 0.39 U	< 0.79 U	0.04 J
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated			0.09	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.38 U	< 0.78 UT	< 0.078 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated			0.499	< 0.079 U	< 0.079 U	< 0.79 U	< 0.079 U	< 0.79 U	< 0.39 U	< 0.79 U	0.052 J
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated			0.108	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.39 U	< 0.8 U	< 0.08 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated			1.504	< 0.077 U	< 0.077 U	< 0.77 U	0.029 J	< 0.77 U	< 0.38 U	< 0.77 U	0.14
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated			0.947	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.38 U	< 0.78 U	0.084
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated			1.683	< 0.076 U	< 0.076 U	< 0.76 U	< 0.076 U	< 0.76 U	< 0.37 U	< 0.76 U	0.14
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated			0.274	< 0.076 U	< 0.076 U	< 0.76 U	< 0.076 U	< 0.76 U	< 0.38 U	< 0.76 U	0.034 J
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated			0.332	< 0.082 U	< 0.082 U	< 0.82 U	< 0.082 U	< 0.82 U	< 0.4 U	< 0.82 U	0.042 J
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated			0.291	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 U	0.036 J
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			0.278	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.4 U	< 0.8 U	0.036 J
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated			0.385	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.39 U	< 0.8 U	0.046 J
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			0.186	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.4 U	< 0.8 U	< 0.08 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			0.362	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 U	0.04 J
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			0.164	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 UT	< 0.081 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated			2.321	0.034 J	< 0.078 U	< 0.78 U	0.071 J	< 0.78 U	< 0.38 U	< 0.78 U	0.18
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated			0.471	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	0.054 J
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated			0.107	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.39 U	< 0.78 U	< 0.078 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.115	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.39 U	< 0.8 U	< 0.08 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.568	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.39 U	< 0.78 U	0.053 J
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.093	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.38 U	< 0.78 U	< 0.078 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.146	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.39 U	< 0.8 U	< 0.08 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.775	< 0.082 U	< 0.082 U	< 0.82 U	< 0.082 U	< 0.82 U	< 0.4 U	< 0.82 UT	0.075 J
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.678	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 U	0.059 J
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated			0.407	< 0.079 U	< 0.079 U	< 0.79 U	< 0.079 U	< 0.79 U	< 0.39 U	< 0.79 U	0.04 J
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated			1.042	< 0.082 U	< 0.082 U	< 0.82 U	0.024 J	< 0.82 U	< 0.4 U	< 0.82 U	0.086
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated			0.525	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 UT	0.047 J
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated			0.512	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 U	0.044 J
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated			0.152	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 U	< 0.81 U	< 0.081 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated			0.065	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	< 0.077 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated			0.207	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated			0.618	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.052 J
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated			6.502	< 0.021	0.17	< 0.13	0.16	< 0.16	< 0.13	< 0.046	0.56
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated			0.259	< 0.02	< 0.015	< 0.12	< 0.018	< 0.15	< 0.13	< 0.043	0.04
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated			0.436	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.05 J
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated			2.1	< 0.023 U	0.037 J	< 0.14 U	0.036 J	< 0.17 U	< 0.14 U	< 0.049 U	0.24
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated			2.88	< 0.11 U	0.12 J	< 0.67 U	< 0.097 U	< 0.82 U	< 0.68 U	< 0.23 U	0.32 J
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated			10	< 0.04 U	0.26	< 0.25 U	0.24	< 0.31 U	< 0.26 U	< 0.087 U	0.81
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated			0.2386	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.025 J
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated			1.552	< 0.02 U	0.12	< 0.12 U	0.057 J	< 0.15 U	< 0.13 U	< 0.043 U	0.15
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated			1.528	< 0.02 U	0.13	< 0.12 U	0.054 J	< 0.15 U	< 0.13 U	< 0.043 U	0.14
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated			1.381	< 0.02 U	0.1	< 0.13 U	0.05 J	< 0.15 U	< 0.13 U	< 0.044 U	0.13
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated			3.441	0.03 J	0.027 J	< 0.13 U	0.11	< 0.15 U	< 0.13 U	< 0.044 UT	0.29
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated			1.352	< 0.021 U	0.028 J	< 0.13 U	0.027 J	< 0.16 U	< 0.13 U	< 0.045 U	0.13
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated			0.017	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated			5.311	< 0.02 U	0.053 J	< 0.13 U	0.11	< 0.16 U	< 0.13 U	< 0.044 U	0.43
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated			2.233	< 0.02 U	0.087	< 0.12 U	0.065 J	< 0.15 U	< 0.13 U	< 0.043 U	0.15
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated			7.398	< 0.021 U	0.18	< 0.13 U	0.13	< 0.16 U	< 0.13 U	< 0.045 UT	0.65
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated			4.058	< 0.02 U	0.18	< 0.13 U	0.097	< 0.15 U	< 0.13 U	< 0.044 U	0.26
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated			0.194	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated			ND	< 0.073 U	< 0.073 U	< 0.073 U	< 0.073 U	< 0.73 U	< 0.36 U	< 0.73 U	< 0.073 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated			ND	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.72 U	< 0.35 U	< 0.72 U	< 0.072 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated			1.108	< 0.076 U	< 0.076 U	< 0.76 U	< 0.076 U	< 0.76 U	< 0.37 U	< 0.76 U	0.1
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated			0.111	< 0.074 U	< 0.074 U	< 0.74 U	< 0.074 U	< 0.74 U	< 0.36 U	< 0.74 U	< 0.074 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated			0.084	< 0.074 U	< 0.074 U	< 0.74 U	< 0.074 U	< 0.74 U	< 0.36 U	< 0.74 U	< 0.074 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated			0.179	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.38 U	< 0.78 U	< 0.078 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated			ND	< 0.075 U	< 0.075 U	< 0.75 U	< 0.075 U	< 0.75 U	< 0.37 U	< 0.75 U	< 0.075 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated			0.493	< 0.073 U	< 0.073 U	< 0.73 U	< 0.073 U	< 0.73 U	< 0.36 U	< 0.73 U	0.049 J
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated			0.931	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.38 U	< 0.78 U	0.081

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated	0.29 J	0.47	0.18 J	0.23 J				0.53		
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	0.47	0.63	0.26 J	0.36				0.68		
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated	0.29 J	0.47	0.18 J	0.23 J				0.53		
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	< U	< U	< U	< U				1.1		
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U	< U	< U	< U				1.1		
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U	< U	< U	< U				1.1		
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.22 J	0.31 J	0.12 J	0.15 J				0.57		
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.47	0.63	0.26 J	0.36				0.68		
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.29 J	0.47	0.18 J	0.23 J				0.53		
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	0.47	0.63	0.26 J	0.36				0.68		
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	0.14	0.17	0.059	0.076	< 0.016 U	< 0.016 U	< 0.014 U	0.21	< 0.019 U	< 0.03 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.078 U	0.04 J	< 0.078 U	< 0.078 U	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	0.069 J	0.093	0.042 J	0.049 J	< 0.4 U	< 0.08 U	< 0.08 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.082 U	0.054 J	< 0.082 U	0.026 J	< 0.4 U	< 0.082 U	< 0.082 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	0.038 J	0.054 J	< 0.079 U	0.029 J	< 0.39 U	< 0.079 U	< 0.079 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.078 U	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	0.054 J	0.065 J	0.03 J	< 0.079 U	< 0.39 U	< 0.079 U	< 0.079 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.08 U	0.037 J	< 0.08 U	< 0.08 U	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	0.12	0.18	0.069 J	0.086	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	0.08	0.11	0.064 J	0.065 J	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	0.14	0.21	0.059 J	0.095	< 0.37 U	< 0.076 U	< 0.076 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	0.036 J	0.055 J	< 0.076 U	0.029 J	< 0.38 U	< 0.076 U	< 0.076 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	0.044 J	0.062 J	< 0.082 U	0.039 J	< 0.4 U	< 0.082 U	< 0.082 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	0.035 J	0.056 J	< 0.081 U	< 0.081 U	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.08 U	0.047 J	< 0.08 U	0.028 J	< 0.4 U	< 0.08 U	< 0.08 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.08 U	0.061 J	0.028 J	< 0.08 U	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.08 U	0.046 J	< 0.08 U	0.027 J	< 0.4 U	< 0.08 U	< 0.08 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	0.04 J	0.065 J	< 0.081 U	0.035 J	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.081 U	0.046 J	< 0.081 U	0.029 J	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	0.17	0.21	0.086	0.13	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	0.048 J	0.074 J	< 0.077 U	0.034 J	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.078 U	0.031 J	< 0.078 U	< 0.078 U	< 0.39 U	< 0.078 U	< 0.078 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.08 U	0.037 J	< 0.08 U	< 0.08 U	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	0.06 J	0.068 J	0.044 J	0.047 J	< 0.39 U	< 0.078 U	< 0.078 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.078 U	0.037 J	< 0.078 U	< 0.078 U	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.08 U	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	0.076 J	0.075 J	0.054 J	0.059 J	< 0.4 U	< 0.082 U	< 0.082 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	0.053 J	0.07 J	0.056 J	0.054 J	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	0.04 J	0.049 J	0.03 J	0.04 J	< 0.39 U	< 0.079 U	< 0.079 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	0.089	0.13	0.036 J	0.074 J	< 0.4 U	< 0.082 U	< 0.082 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	0.051 J	0.081	0.032 J	0.049 J	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	0.059 J	0.07 J	0.03 J	0.045 J	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.081 U	0.043 J	< 0.081 U	< 0.081 U	< 0.4 U	< 0.081 U	< 0.081 U	< 4 U	< 0.4 U	< 2 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.077 U	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.03 U	0.024 J	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	0.05 J	0.053 J	0.029 J	0.04 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	0.48	0.73	0.17	0.64	< 0.13	< 0.013	< 0.027	< 0.39	< 0.16	< 0.25
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.03	0.031	< 0.021	< 0.015	< 0.13	< 0.013	< 0.026	< 0.37	< 0.15	< 0.24
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	0.047 J	0.068 J	< 0.023 U	0.043 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	0.19	0.27	0.088	0.15	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	0.3 J	0.3 J	0.21 J	0.27 J	< 0.68 U	< 0.068 U	< 0.14 U	< 2 U	< 0.79 U	< 1.3 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	0.88	1.1	0.46	1	< 0.26 U	< 0.025 U	< 0.052 U	< 0.75 U	< 0.3 U	< 0.48 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	0.012 J	0.026 J	0.0071 J	0.014 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	0.16	0.21	0.077	0.17	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	0.16	0.23	0.07	0.17	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	0.14	0.2	0.06 J	0.13	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	0.25	0.32	0.13	0.21	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	0.16	0.17	0.055 J	0.12	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	0.4	0.55	0.18	0.35	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	0.16	0.26	0.063 J	0.26	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	0.69	0.93	0.32	0.66	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	0.35	0.5	0.15	0.48	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	0.036 J	0.043 J	< 0.021 U	0.034 J	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.073 U	< 0.073 U	< 0.073 U	< 0.073 U	< 0.36 U	< 0.073 U	< 0.073 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.072 U	< 0.072 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.11	0.13	0.082	< 0.076 U	< 0.37 U	< 0.076 U	< 0.076 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.074 U	0.033 J	< 0.074 U	< 0.074 U	< 0.36 U	< 0.074 U	< 0.074 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.074 U	< 0.074 U	< 0.074 U	< 0.074 U	< 0.36 U	< 0.074 U	< 0.074 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.078 U	0.047 J	0.025 J	< 0.078 U	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.075 U	< 0.075 U	< 0.075 U	< 0.075 U	< 0.37 U	< 0.075 U	< 0.075 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.044 J	0.066 J	0.028 J	< 0.073 U	< 0.36 U	< 0.073 U	< 0.073 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.082	0.11	0.056 J	0.057 J	< 0.38 U	< 0.078 U	< 0.078 U	< 3.8 U	< 0.38 U	< 1.9 U

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated								0.25 J		
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated								0.44		
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated								0.25 J		
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated								< U		
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								< U		
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								< U		
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.22 J		
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.44		
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.25 J		
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								0.44		
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	< 0.1 U	< 0.026 U	< 0.041 U	< 0.061 U	< 0.019 U	< 0.014 U	< 0.019 U	0.16	0.025	0.018 J
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 2 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.078 U	< 0.38 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.08 U	< 0.4 U	< 0.4 U	0.076 J	< 0.08 U	< 0.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2.1 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.082 U	< 0.082 U	< 0.4 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 2 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.079 U	< 0.079 U	< 0.39 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 2 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.078 U	< 0.38 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 2 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	0.061 J	< 0.079 U	< 0.39 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 1.9 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	0.14	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 2 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	0.1	< 0.078 U	< 0.38 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 1.9 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.076 U	< 0.37 U	< 0.37 U	0.15	< 0.076 U	< 0.37 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 1.9 U	< 0.076 U	< 0.38 U	< 0.38 U	< 0.076 U	< 0.38 U	< 0.38 U	< 0.076 U	< 0.076 U	< 0.38 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 2.1 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.082 U	< 0.082 U	< 0.4 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 2.1 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.08 U	< 0.08 U	< 0.4 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	0.056 J	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.08 U	< 0.08 U	< 0.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2.1 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	0.048 J	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 2 U	0.041 J	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	0.18	< 0.078 U	< 0.38 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 2 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	0.053 J	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 2 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.078 U	< 0.39 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	0.064 J	< 0.078 U	< 0.39 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.078 U	< 0.38 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2.1 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	0.086	< 0.082 U	< 0.4 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2.1 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	0.073 J	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 2 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	0.044 J	< 0.079 U	< 0.39 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 2.1 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	0.1	< 0.082 U	< 0.4 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 2.1 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	0.063 J	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 2.1 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	0.062 J	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 2 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 U	< 0.081 U	< 0.4 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 2 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.077 U	< 0.38 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.049 J	< 0.045 U	< 0.015 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.24	0.066	< 0.097	< 0.13	< 0.017	< 0.14	< 0.12	0.59	0.14	< 0.14
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.23	< 0.016	< 0.092	< 0.12	< 0.016	< 0.13	< 0.12	< 0.039	< 0.045	< 0.13
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.045 J	< 0.049 U	< 0.14 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.23	< 0.05 U	< 0.15 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 1.2 U	< 0.087 U	< 0.49 U	< 0.65 U	< 0.086 U	< 0.69 U	< 0.62 U	0.25 J	< 0.24 U	< 0.69 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.46 U	0.073 J	< 0.18 U	< 0.25 U	< 0.032 U	< 0.26 U	< 0.23 U	0.8	0.27	< 0.26 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.033 J	< 0.015 U	< 0.012 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.16	< 0.045 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.16	< 0.044 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.15	< 0.045 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.23 U	0.022 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.29	0.048 J	< 0.13 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.14	< 0.047 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.23 U	0.07 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.42	0.09	< 0.13 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.23 U	0.028 J	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.14	0.045 J	< 0.13 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.23 U	0.075	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.63	0.15	< 0.13 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.23 U	0.05 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.29	0.081	< 0.13 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.18 U	< 0.073 U	< 0.36 UT	< 0.36 U	< 0.073 U	< 0.36 U	< 0.36 U	< 0.073 U	< 0.073 U	< 0.36 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.18 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.072 U	< 0.35 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 1.9 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.076 U	< 0.37 U	< 0.37 U	0.12	< 0.076 U	< 0.37 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 1.9 U	< 0.074 U	< 0.36 U	< 0.36 U	< 0.074 U	< 0.36 U	< 0.36 U	< 0.074 U	< 0.074 U	< 0.36 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 1.9 U	< 0.074 U	< 0.36 U	< 0.36 U	< 0.074 U	< 0.36 U	< 0.36 U	< 0.074 U	< 0.074 U	< 0.36 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 2 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.078 U	< 0.38 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 1.9 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.075 U	< 0.075 U	< 0.37 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 1.9 U	< 0.073 U	< 0.36 U	< 0.36 U	< 0.073 U	< 0.36 U	< 0.36 U	0.06 J	< 0.073 U	< 0.36 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 2 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	0.1	< 0.078 U	< 0.38 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated										
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated										
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated										
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated										
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated										
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated										
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated										
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated										
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated										
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	< 0.058 U	< 0.06 U	< 0.042 U	< 0.054 U	< 0.019 U	< 0.03 U	< 0.038 U	< 0.11 U	< 0.076 U	< 0.19 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 U	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.8 U	< 4 U	< 0.4 U	< 2 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.82 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.79 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 UT	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.79 U	< 3.9 U	< 0.39 UT	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 UT	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 UT	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 UT	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.37 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.76 U	< 3.7 U	< 0.37 U	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.38 U	< 0.076 U	< 0.38 U	< 0.38 U	< 0.76 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.82 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.4 UT	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.8 U	< 4 U	< 0.4 U	< 2 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U	< 0.08 U	< 0.4 U	< 0.4 U	< 0.8 U	< 4 U	< 0.4 U	< 2 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 U	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.78 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 UT	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 UT	< 0.078 U	< 0.39 U	< 0.39 U	< 0.78 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.38 UT	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 U	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 UT	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.4 UT	< 0.082 U	< 0.4 U	< 0.4 UT	< 0.82 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.4 UT	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 UT	< 0.079 U	< 0.39 U	< 0.39 U	< 0.79 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U	< 0.082 U	< 0.4 U	< 0.4 U	< 0.82 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2.1 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 U	< 4 U	< 0.4 U	< 2 U	< 0.4 U	< 4 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 2 U	< 0.38 U	< 3.8 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 1.9 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.34	< 0.028	< 0.13	< 0.12	< 0.15	< 0.16	< 0.21	< 0.64	< 0.14	< 2.3
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.33	< 0.027	< 0.12	< 0.12	< 0.14	< 0.15	< 0.2	< 0.6	< 0.14	< 2.2
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 1.7 U	< 0.14 U	< 0.65 U	< 0.63 U	< 0.74 U	< 0.82 U	< 1.1 U	< 3.2 U	< 0.73 U	< 12 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.65 U	< 0.054 U	0.25 J	< 0.24 U	< 0.28 U	< 0.31 U	< 0.41 U	< 1.2 U	< 0.27 U	< 4.4 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 UT	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.26 J	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.16 J	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.19 J	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 UT
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.16 J	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	0.17 J	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.36 UT	< 0.073 U	< 0.36 U	< 0.36 U	< 0.73 U	< 3.6 U	< 0.36 U	< 1.8 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.72 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.37 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.76 U	< 3.7 U	< 0.37 UT	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.36 U	< 0.074 U	< 0.36 U	< 0.36 U	< 0.74 U	< 3.6 U	< 0.36 U	< 1.9 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.36 U	< 0.074 U	< 0.36 U	< 0.36 U	< 0.74 U	< 3.6 U	< 0.36 UT	< 1.9 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 UT	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.37 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.75 U	< 3.7 U	< 0.37 UT	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.36 U	< 0.073 U	< 0.36 U	< 0.36 U	< 0.73 U	< 3.6 U	< 0.36 UT	< 1.9 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.38 U	< 0.078 U	< 0.38 U	< 0.38 U	< 0.78 U	< 3.8 U	< 0.38 UT	< 2 U	< 0.38 U	< 3.8 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated					0.31 J					
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated					1					
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated					0.31 J					
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated					< U					
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					< U					
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					< U					
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					0.46					
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					1					
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					0.31 J					
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated					1					
Football Field	SSHS-B2026	073118 08:50 SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	< 0.084 U			< 0.02 U	0.24	0.0077 J	< 0.0028 U	< 0.016 U	< 0.084 U	< 0.012 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.38 U		< 0.78 U		0.053 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U		< 0.8 U		0.14	< 0.08 U	< 0.08 U	< 0.08 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U		< 0.82 U		0.055 J	< 0.082 U	< 0.082 U	< 0.082 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.39 U		< 0.79 U		0.08	< 0.079 U	< 0.079 U	< 0.079 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.38 U		< 0.78 U		0.038 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.39 U		< 0.79 U		0.078 J	< 0.079 U	< 0.079 U	< 0.079 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.39 U		< 0.8 U		0.032 J	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.38 U		< 0.77 U		0.24	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.38 U		< 0.78 U		0.15	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.37 U		< 0.76 U		0.35	< 0.076 U	< 0.076 U	< 0.076 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.38 U		< 0.76 U		0.065 J	< 0.076 U	< 0.076 U	< 0.076 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.4 U		< 0.82 U		0.078 J	< 0.082 U	< 0.082 U	< 0.082 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.4 U		< 0.81 U		0.065 J	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U		< 0.8 U		0.072 J	< 0.08 U	< 0.08 U	< 0.08 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.39 U		< 0.8 U		0.086	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U		< 0.8 U		0.061 J	< 0.08 U	< 0.08 U	< 0.08 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U		< 0.81 U		0.071 J	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.4 U		< 0.81 U		0.048 J	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.38 U		< 0.78 U		0.45	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.38 U		< 0.77 U		0.096	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.39 U		< 0.78 U		0.042 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 U		< 0.8 U		0.04 J	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 U		< 0.78 U		0.1	< 0.078 U	< 0.078 U	< 0.078 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.38 U		< 0.78 U		0.029 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 U		< 0.8 U		0.06 J	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.4 U		< 0.82 U		0.14	< 0.082 U	< 0.082 U	< 0.082 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.4 U		< 0.81 U		0.13	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.39 U		< 0.79 U		0.073 J	< 0.079 U	< 0.079 U	< 0.079 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U		< 0.82 U		0.19	< 0.082 U	< 0.082 U	< 0.082 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U		< 0.81 U		0.092	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U		< 0.81 U		0.098	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.4 U		< 0.81 U		0.065 J	< 0.081 U	< 0.081 U	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.38 U		< 0.77 U		0.029 J	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.052 U	< 0.11 U			0.033 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.053 U	< 0.11 U			0.11	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.22			< 0.12	0.7	0.022	< 0.026	< 0.022	< 0.038	< 0.13
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.21			< 0.11	0.071	< 0.014	< 0.025	< 0.02	< 0.036	< 0.12
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.23 U	< 0.12 UT			0.078	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.23 U	< 0.12 U			0.28	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 1.1 U	< 0.58 U			0.42	< 0.073 U	< 0.13 U	< 0.11 U	< 0.19 U	< 0.66 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.42 U	< 0.22 U			1.1	0.03 J	< 0.05 U	< 0.041 U	< 0.072 U	< 0.25 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.038 U		< 0.031 U		0.036 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.21 U	< 0.11 U			0.18	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.21 U	< 0.11 U			0.17	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.21 U	< 0.11 U			0.17	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.21 U	< 0.11 U			0.6	0.034 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.22 U	< 0.11 U			0.15	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.21 U	< 0.11 U			1.1	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.21 U	< 0.11 U			0.23	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.21 U	< 0.11 U			1.1	0.018 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.21 U	< 0.11 U			0.45	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.21 U	< 0.11 U			0.04 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.36 U		< 0.72 U		< 0.073 U	< 0.073 U	< 0.073 U	< 0.073 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.35 U		< 0.72 U		< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.37 U		< 0.76 U		0.18	< 0.076 U	< 0.076 U	< 0.076 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.36 U		< 0.74 U		0.043 J	< 0.074 U	< 0.074 U	< 0.074 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.36 U		< 0.74 U		0.037 J	< 0.074 U	< 0.074 U	< 0.074 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.38 U		< 0.78 U		0.047 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.37 U		< 0.75 U		< 0.075 U	< 0.075 U	< 0.075 U	< 0.075 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.36 U		< 0.73 U		0.091	< 0.073 U	< 0.073 U	< 0.073 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.38 U		< 0.78 U		0.15	< 0.078 U	< 0.078 U	< 0.078 U	< 0.38 U	< 0.38 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated	0.2 J									
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	0.31 J									
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated	0.2 J									
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated	< U									
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U									
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U									
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.14 J									
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.31 J									
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.2 J									
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	0.31 J									
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	0.069	< 0.042 U	< 0.039 U	< 0.016 U	0.022		0.059	< 0.054 U	< 0.066 U	< 0.081 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.078 U	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	0.045 J	< 0.4 U		< 0.4 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.082 U	< 0.4 U		< 0.4 U	< 0.082 U		< 0.082 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.079 U	< 0.39 U		< 0.39 U	< 0.079 U		< 0.079 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.078 U	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.079 U	< 0.39 U		< 0.39 U	< 0.079 U		< 0.079 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.08 U	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	0.07 J	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	0.053 J	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	0.089	< 0.37 U		< 0.37 U	< 0.076 U		< 0.076 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.076 U	< 0.38 U		< 0.38 U	< 0.076 U		< 0.076 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.082 U	< 0.4 U		< 0.4 U	< 0.082 U		< 0.082 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.08 U	< 0.4 U		< 0.4 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.08 U	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.08 U	< 0.4 U		< 0.4 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	0.1	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.077 U	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.078 U	< 0.39 U		< 0.39 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.08 U	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.078 U	< 0.39 U		< 0.39 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.078 U	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.08 U	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.082 U	< 0.4 U		< 0.4 U	< 0.082 U		< 0.082 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.079 U	< 0.39 U		< 0.39 U	< 0.079 U		< 0.079 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	0.064 J	< 0.4 U		< 0.4 U	0.033 J		< 0.082 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2.1 U	< 2.1 U	< 2.1 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.081 U	< 0.4 U		< 0.4 U	< 0.081 U		< 0.081 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.077 U	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 2 U	< 2 U	< 2 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.034 U	< 0.099 U		< 0.018 U	0.029 J	< 0.1 U	0.12	< 0.16 U	< 0.088 U	< 0.017 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	0.02 J	< 0.1 U	0.093	< 0.16 U	< 0.09 U	< 0.017 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	0.53	< 0.11		< 0.14	0.11	< 0.11	0.38	< 0.17	< 0.094	< 0.14
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.035	< 0.1		< 0.13	< 0.017	< 0.1	< 0.014	< 0.16	< 0.089	< 0.13
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	0.14	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.027 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	0.23 J	< 0.53 U		< 0.7 U	< 0.09 U	< 0.55 U	0.11 J	< 0.85 U	< 0.47 U	< 0.69 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	0.91	< 0.2 U		< 0.26 U	0.13 J	< 0.21 U	0.34	< 0.32 U	< 0.18 U	< 0.26 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	0.015 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0075 J	< 0.027 U	< 0.083 U	< 0.04 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	0.13	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.015 J	< 0.16 U	< 0.089 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	0.13	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	0.02 J	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	0.11	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	0.17	< 0.1 U		< 0.13 U	0.019 J	< 0.1 U	0.019 J	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	0.11	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	0.3	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.041 J	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	0.19	< 0.1 U		< 0.13 U	0.086	< 0.1 U	0.27	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	0.55	< 0.1 U		< 0.13 U	0.049 J	< 0.11 U	0.18	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	0.38	< 0.1 U		< 0.13 U	0.096	< 0.1 U	0.37	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.073 U	< 0.36 U		< 0.36 U	< 0.073 U		< 0.073 U	< 1.8 U	< 1.8 U	< 1.8 UT
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.072 U	< 0.35 U		< 0.35 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.059 J	< 0.37 U		< 0.37 U	< 0.076 U		< 0.076 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.074 U	< 0.36 U		< 0.36 U	< 0.074 U		< 0.074 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.074 U	< 0.36 U		< 0.36 U	< 0.074 U		< 0.074 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.078 U	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.075 U	< 0.37 U		< 0.37 U	< 0.075 U		< 0.075 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.073 U	< 0.36 U		< 0.36 U	< 0.073 U		< 0.073 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	0.051 J	< 0.38 U		< 0.38 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated								0.1 J		0.34 J
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated								0.47		0.84
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated								0.1 J		0.34 J
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated								< U		
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								< U		< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								< U		< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.31 J		
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.47		0.84
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.1 J		0.34 J
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								0.47		0.84
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated	< 0.018 U	< 0.018 U	< 0.13 U		< 0.015 U	< 0.016 U	< 0.079 U	0.094	0.025 J	0.21
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	< 0.078 U	< 0.38 U	0.045 J
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.8 U	< 0.4 U	< 2 U		< 0.08 U	< 0.4 U	< 2 U	0.055 J	< 0.4 U	0.11
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.82 U	< 0.4 U	< 2.1 U		< 0.082 U	< 0.4 U	< 2.1 U	< 0.082 U	< 0.4 U	0.047 J
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.79 U	< 0.39 U	< 2 U		< 0.079 U	< 0.39 U	< 2 U	0.032 J	< 0.39 U	0.066 J
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	< 0.078 U	< 0.38 U	0.052 JT
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.79 U	< 0.39 U	< 2 U		< 0.079 U	< 0.39 U	< 2 U	0.049 J	< 0.39 U	0.11 T
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	< 0.08 U	< 0.39 U	0.039 JT
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.77 U	< 0.38 U	< 1.9 U		< 0.077 U	< 0.38 U	< 1.9 U	0.15	< 0.38 U	0.28 T
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	0.071 J	< 0.38 U	0.17 T
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.76 U	< 0.37 U	< 1.9 U		< 0.076 U	< 0.37 U	< 1.9 U	0.19	< 0.37 U	0.26
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.76 U	< 0.38 U	< 1.9 U		< 0.076 U	< 0.38 U	< 1.9 U	< 0.076 U	< 0.38 U	0.055 J
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.82 U	< 0.4 U	< 2.1 U		< 0.082 U	< 0.4 U	< 2.1 U	< 0.082 U	< 0.4 U	0.067 J
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.81 U	< 0.4 U	< 2.1 U		< 0.081 U	< 0.4 U	< 2.1 U	0.031 J	< 0.4 U	0.068 J
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.8 U	< 0.4 U	< 2 U		< 0.08 U	< 0.4 U	< 2 U	0.036 J	< 0.4 U	0.059 J
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	0.037 J	< 0.39 U	0.071 J
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.8 U	< 0.4 U	< 2 U		< 0.08 U	< 0.4 U	< 2 U	< 0.08 U	< 0.4 U	0.052 J
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.81 U	< 0.4 U	< 2.1 U		< 0.081 U	< 0.4 U	< 2.1 U	< 0.081 U	< 0.4 U	0.063 J
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.81 U	< 0.4 U	< 2 U		< 0.081 U	< 0.4 U	< 2 U	< 0.081 U	< 0.4 U	0.041 J
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	0.34	< 0.38 U	0.37
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.77 U	< 0.38 U	< 2 U		< 0.077 U	< 0.38 U	< 2 U	0.034 J	< 0.38 U	0.078
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.78 U	< 0.39 U	< 2 U		< 0.078 U	< 0.39 U	< 2 U	< 0.078 U	< 0.39 U	0.034 J
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	< 0.08 U	< 0.39 U	0.038 J
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.78 U	< 0.39 U	< 2 U		< 0.078 U	< 0.39 U	< 2 U	0.038 J	< 0.39 U	0.094
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	< 0.078 U	< 0.38 U	0.027 J
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	0.029 J	< 0.39 U	0.057 J
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.82 U	< 0.4 U	< 2.1 U		< 0.082 U	< 0.4 U	< 2.1 U	0.07 J	< 0.4 U	0.14
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.81 U	< 0.4 U	< 2.1 U		< 0.081 U	< 0.4 U	< 2.1 U	0.073 J	< 0.4 U	0.11
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.79 U	< 0.39 U	< 2 U		< 0.079 U	< 0.39 U	< 2 U	0.028 J	< 0.39 U	0.063 J
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.82 U	< 0.4 U	< 2.1 U		< 0.082 U	< 0.4 U	< 2.1 U	0.099	< 0.4 U	0.15
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.81 U	< 0.4 U	< 2.1 U		< 0.081 U	< 0.4 U	< 2.1 U	0.034 J	< 0.4 U	0.076 J
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.81 U	< 0.4 U	< 2.1 U		< 0.081 U	< 0.4 U	< 2.1 U	0.029 J	< 0.4 U	0.075 J
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.81 U	< 0.4 U	< 2 U		< 0.081 U	< 0.4 U	< 2 U	< 0.081 U	< 0.4 U	0.044 J
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.77 U	< 0.38 U	< 2 U		< 0.077 U	< 0.38 U	< 2 U	< 0.077 U	< 0.38 U	0.036 J
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	0.03 J
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.057 J	< 0.11 U	0.085
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.13	< 0.14	< 0.26		< 0.025	< 0.12	< 0.59	0.5	< 0.11	0.9
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.13	< 0.13	< 0.25		< 0.024	< 0.12	< 0.56	0.055	< 0.11	0.062
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.03 J	< 0.12 U	0.075 J
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.079	< 0.12 U	0.37
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.68 U	< 0.69 U	< 1.3 U		< 0.13 U	< 0.62 U	< 3 U	< 0.1 U	< 0.57 U	0.47
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.26 U	< 0.26 U	< 0.49 U		< 0.048 U	< 0.23 U	< 1.1 U	0.66	< 0.21 U	1.4
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.03 J	< 0.013 U	0.033 J
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.043 J	< 0.11 U	0.2
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.034 J	< 0.1 U	0.19
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.051 J	< 0.11 U	0.19
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.4	< 0.11 U	0.54
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.05 J	< 0.11 U	0.24
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.017 J
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.47	< 0.11 U	0.87
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.14	< 0.11 U	0.26
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.39	< 0.11 U	1
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.2	< 0.11 U	0.45
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.041 J
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.72 U	< 0.36 U	< 1.8 U		< 0.073 U	< 0.36 U	< 1.8 U	< 0.073 U	< 0.36 U	< 0.073 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.72 U	< 0.35 U	< 1.8 U		< 0.072 U	< 0.35 U	< 1.8 U	< 0.072 U	< 0.35 U	< 0.072 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.76 U	< 0.37 U	< 1.9 U		< 0.076 U	< 0.37 U	< 1.9 U	0.087	< 0.37 U	0.24 T
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.74 U	< 0.36 U	< 1.9 U		< 0.074 U	< 0.36 U	< 1.9 U	< 0.074 U	< 0.36 U	0.035 J
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.74 U	< 0.36 U	< 1.9 U		< 0.074 U	< 0.36 U	< 1.9 U	< 0.074 U	< 0.36 U	0.047 JT
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	< 0.078 U	< 0.38 U	0.06 JT
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.75 U	< 0.37 U	< 1.9 U		< 0.075 U	< 0.37 U	< 1.9 U	< 0.075 U	< 0.37 U	< 0.075 UT
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.73 U	< 0.36 U	< 1.9 U		< 0.073 U	< 0.36 U	< 1.9 U	0.045 J	< 0.36 U	0.11 T
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.78 U	< 0.38 U	< 2 U		< 0.078 U	< 0.38 U	< 2 U	0.074 J	< 0.38 U	0.17 T

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																
Restricted - Residential																
Protection of Groundwater																
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated					
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated					
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated					
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated					
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated					
Football Field	SSHS-B2026	073118 08:50_SSHS-B2026-SS	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated		< 0.019 U	< 0.4 U	< 0.093 U	< 0.087 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-DUP-03-20260312	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-DUP-05-20260312	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-DUP-06-20260312	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-09-20260312	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17-20260312	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17-20260312	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17-20260312	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17-20260312	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17-20260312	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17-20260312	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17-20260312	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17-20260312	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17-20260312	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17-20260312	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17-20260312	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17-20260312	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17-20260312	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17-20260312	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17-20260312	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17-20260312	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17-20260312	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11-20260313	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13-20260313	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17-20260313	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17-20260313	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17-20260313	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17-20260313	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17-20260313	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17-20260313	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17-20260313	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17-20260313	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17-20260313	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 0.4 U	< 0.4 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17-20260313	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	0.00	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated		< 0.15	< 0.15	< 0.13	< 0.12
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated		< 0.14	< 0.15	< 0.12	< 0.12
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211212	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated		< 0.74 U	< 0.78 U	< 0.65 U	< 0.62 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated		< 0.28 U	< 0.29 U	< 0.24 U	< 0.23 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2-20260311	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2-20260311	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	0.00	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV9	SSHS-IRM5-DUP-01-20260312	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-DUP-10-20260312	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1-20260312	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1-20260312	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1-20260312	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1-20260312	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1-20260312	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated			0.766	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	0.066 J
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated			0.019	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	< 0.077 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated			0.271	< 0.081 U	< 0.081 U	< 0.81 U	< 0.081 U	< 0.81 U	< 0.4 UT	< 0.81 UT	0.036 JT
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated			2.354	0.026 J	< 0.076 U	< 0.76 U	0.06 J	< 0.76 U	< 0.38 U	< 0.76 U	0.19
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated			23.151	0.5	< 0.079 U	< 0.79 U	1.1	< 0.79 U	< 0.39 U	< 0.79 U	1.7
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated			0.109	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.39 U	< 0.78 U	< 0.078 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.35 U	< 0.7 UT	< 0.07 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated			0.513	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	0.055 J
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated			0.144	< 0.078 U	< 0.078 U	< 0.78 U	< 0.078 U	< 0.78 U	< 0.39 U	< 0.78 U	< 0.078 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated			0.211	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 UJ	0.032 J
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated			0.144	< 0.074 U	< 0.074 U	< 0.74 U	< 0.074 U	< 0.74 U	< 0.37 U	< 0.74 U	< 0.074 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated			0.092	< 0.073 U	< 0.073 U	< 0.73 U	< 0.073 U	< 0.73 U	< 0.36 U	< 0.73 U	< 0.073 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated			0.453	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	0.045 J
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated			0.046	< 0.075 U	< 0.075 U	< 0.75 U	< 0.075 U	< 0.75 U	< 0.37 U	< 0.75 U	< 0.075 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated			0.084	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.39 U	< 0.8 U	< 0.08 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated			0.063	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	< 0.077 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated			0.469	< 0.079 U	< 0.079 U	< 0.79 U	< 0.079 U	< 0.79 U	< 0.39 U	< 0.79 U	0.056 J
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated			2.986	0.064 J	< 0.077 U	< 0.77 U	0.13	< 0.77 U	< 0.38 U	< 0.77 U	0.22
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated			1.157	< 0.08 U	< 0.08 U	< 0.8 U	0.031 J	< 0.8 U	< 0.39 U	< 0.8 U	0.095
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated			0.423	< 0.08 U	< 0.08 U	< 0.8 U	< 0.08 U	< 0.8 U	< 0.39 U	< 0.8 U	0.042 J
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated			0.451	< 0.075 U	< 0.075 U	< 0.75 U	< 0.075 U	< 0.75 U	< 0.37 U	< 0.75 U	0.041 J
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated			0.182	< 0.077 U	< 0.077 U	< 0.77 U	< 0.077 U	< 0.77 U	< 0.38 U	< 0.77 U	< 0.077 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated			ND	< 0.074 U	< 0.074 U	< 0.74 U	< 0.074 U	< 0.74 U	< 0.37 U	< 0.74 U	< 0.074 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated			1.0195	< 0.00093 U	0.055	< 0.013 U	0.024	< 0.044 U	< 0.021 U	< 0.028 U	0.062
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated		150	3.46	< 0.1 U	0.1 J	< 0.097 U	< 0.092 U	< 0.78 U	< 0.075 U	< 0.22 U	0.31 J
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated			5.96	< 0.021 U	0.15	< 0.02 U	0.18	< 0.16 U	0.026 J	< 0.045 U	0.52
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated			2.459	< 0.042 U	0.084 J	< 0.039 U	0.055 J	< 0.32 U	< 0.03 U	< 0.09 U	0.23
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated			ND	< 0.072 U	< 0.072 U	< 0.72 U	< 0.072 U	< 0.72 U	< 0.35 U	< 0.72 U	< 0.072 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated			ND	< 0.072 U	< 0.072 U	< 0.72 U	< 0.072 U	< 0.72 U	< 0.36 U	< 0.72 U	< 0.072 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated			ND	< 0.072 U	< 0.072 U	< 0.72 U	< 0.072 U	< 0.72 U	< 0.35 U	< 0.72 U	< 0.072 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated			0.112	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.35 U	< 0.7 U	< 0.07 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated			1.554	< 0.072 U	< 0.072 U	< 0.72 U	< 0.072 U	< 0.72 U	< 0.36 U	< 0.72 U	0.15
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated			ND	< 0.072 U	< 0.072 U	< 0.72 U	< 0.072 U	< 0.72 U	< 0.35 U	< 0.72 U	< 0.072 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated			ND	< 0.071 U	< 0.071 U	< 0.71 U	< 0.071 U	< 0.71 U	< 0.35 U	< 0.71 U	< 0.071 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated			ND	< 0.069 U	< 0.069 U	< 0.69 U	< 0.069 U	< 0.69 U	< 0.34 U	< 0.69 U	< 0.069 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated			ND	< 0.068 U	< 0.068 U	< 0.68 U	< 0.068 U	< 0.68 U	< 0.34 U	< 0.68 U	< 0.068 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated			0.052	< 0.076 U	< 0.076 U	< 0.76 U	< 0.076 U	< 0.76 U	< 0.37 U	< 0.76 U	< 0.076 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated			ND	< 0.069 U	< 0.069 U	< 0.69 U	< 0.069 U	< 0.69 U	< 0.34 U	< 0.69 U	< 0.069 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated			ND	< 0.072 U	< 0.072 U	< 0.72 U	< 0.072 U	< 0.72 U	< 0.35 U	< 0.72 U	< 0.072 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated			0.662	< 0.07 U	< 0.07 U	< 0.7 U	0.02 J	< 0.7 U	< 0.35 U	< 0.7 U	0.068 J
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated			ND	< 0.068 U	< 0.068 U	< 0.68 U	< 0.068 U	< 0.68 U	< 0.34 U	< 0.68 U	< 0.068 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated			0.0735	< 0.018 U	< 0.018 U	< 0.053 U	< 0.018 U	< 0.18 U	< 0.039 U	< 0.18 U	0.0059 J
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated			0.115	< 0.018 U	< 0.018 U	< 0.053 U	0.0042 J	< 0.18 U	< 0.039 U	< 0.18 U	0.01 J
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated			0.0037	< 0.018 U	< 0.018 U	< 0.055 U	< 0.018 U	< 0.18 U	< 0.041 U	< 0.18 U	< 0.018 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated			ND	< 0.019 U	< 0.019 U	< 0.056 U	< 0.019 U	< 0.19 U	< 0.041 U	< 0.19 U	< 0.019 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated			0.0268	< 0.018 U	< 0.018 U	< 0.053 U	< 0.018 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.018 U
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated			1.706	< 0.023 U	< 0.018 U	< 0.022 U	0.046 J	< 0.18 U	< 0.017 U	< 0.05 U	0.16
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated			0.826	< 0.023 U	< 0.017 U	< 0.021 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.074 J
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated			0.583	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.05 J
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated			0.44	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.043 J
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated			0.312	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.034 J
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated			0.338	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.036 J
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated			0.2021	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.026 J
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated			0.4002	< 0.01 U	0.011 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	0.036
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated			0.098	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.016 J
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated			0.225	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.025 J
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated			0.342	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.031 J
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated			0.38	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.035 J
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated			0.3973	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.036
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated			0.077	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.016 J
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated			0.399	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.038

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**	**Butylbenzyl phthalate**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	0.066 J	0.091	0.034 J	0.045 J	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.077 U	0.019 J	< 0.077 U	< 0.077 U	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.081 U	0.061 J	< 0.081 U	< 0.081 U	< 0.4 UT	< 0.081 UT	< 0.081 U	< 4 UT	< 0.4 UT	< 2 UT
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	0.19	0.25	0.088	0.15	< 0.38 U	< 0.076 U	< 0.076 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	1.5	1.8	0.68	0.99	< 0.39 U	< 0.079 U	< 0.079 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.078 U	0.033 J	< 0.078 U	< 0.078 U	< 0.39 U	< 0.078 U	< 0.078 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.35 U	< 0.07 U	< 0.07 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	0.05 J	0.053 J	0.038 J	0.033 J	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.078 U	0.044 J	< 0.078 U	< 0.078 U	< 0.39 U	< 0.078 U	< 0.078 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.071 U	0.037 J	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 UT	< 0.35 U	< 1.8 UT
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.074 U	0.044 J	< 0.074 U	< 0.074 U	< 0.37 U	< 0.074 U	< 0.074 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.073 U	0.028 J	< 0.073 U	< 0.073 U	< 0.36 U	< 0.073 U	< 0.073 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.043 J	0.066 J	0.028 J	0.037 J	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.075 U	0.022 J	< 0.075 U	< 0.075 U	< 0.37 U	< 0.075 U	< 0.075 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.08 U	0.024 J	< 0.08 U	< 0.08 U	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.077 U	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	0.057 J	0.065 J	0.031 J	< 0.079 U	< 0.39 U	< 0.079 U	< 0.079 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.21	0.23	0.12	0.14	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.099	0.11	0.086	0.078 J	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.04 J	0.057 J	0.029 J	0.03 J	< 0.39 U	< 0.08 U	< 0.08 U	< 3.9 U	< 0.39 U	< 2 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.045 J	0.058 J	0.032 J	0.031 J	< 0.37 U	< 0.075 U	< 0.075 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.077 U	0.044 J	< 0.077 U	< 0.077 U	< 0.38 U	< 0.077 U	< 0.077 U	< 3.8 U	< 0.38 U	< 1.9 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	< 0.074 U	< 0.074 U	< 0.074 U	< 0.074 U	< 0.37 U	< 0.074 U	< 0.074 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	0.07	0.11	0.053	0.12	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	0.25 J	0.32 J	0.16 J	0.25 J	< 0.085 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.12 U	< 1.2 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	0.53	0.6	0.24	0.56	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	0.26	0.32	0.11 J	0.23	< 0.034 U	< 0.026 U	< 0.053 U	< 0.77 U	< 0.05 U	< 0.5 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.072 U	< 0.072 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.36 U	< 0.072 U	< 0.072 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.072 U	< 0.072 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.35 U	< 0.07 U	< 0.07 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	0.12	0.2	0.07 J	0.1	< 0.36 U	< 0.072 U	< 0.072 U	< 3.6 U	< 0.36 U	< 1.8 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.072 U	< 0.072 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.071 U	< 0.071 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.069 U	< 0.069 U	< 0.069 U	< 0.069 U	< 0.34 U	< 0.069 U	< 0.069 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.068 U	< 0.068 U	< 0.068 U	< 0.068 U	< 0.34 U	< 0.068 U	< 0.068 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.076 U	0.023 J	< 0.076 U	< 0.076 U	< 0.37 U	< 0.076 U	< 0.076 U	< 3.7 U	< 0.37 U	< 1.9 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.069 U	< 0.069 U	< 0.069 U	< 0.069 U	< 0.34 U	< 0.069 U	< 0.069 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.072 U	< 0.072 U	< 3.5 U	< 0.35 U	< 1.8 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	0.075	0.11	0.04 J	< 0.07 U	< 0.35 U	< 0.07 U	< 0.07 U	< 3.5 U	< 0.35 U	< 1.7 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.068 U	< 0.068 U	< 0.068 U	< 0.068 U	< 0.34 U	< 0.068 U	< 0.068 U	< 3.4 U	< 0.34 U	< 1.7 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0091 J	0.01 J	0.0036 J	0.0088 J	< 0.039 U	< 0.039 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0097 J	0.013 J	0.0048 J	0.0077 J	< 0.039 U	< 0.039 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 f	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.018 U	0.0037 J	< 0.018 U	< 0.018 U	< 0.041 U	< 0.041 U	< 0.048 U	< 0.18 U	< 0.041 U	< 0.18 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.041 U	< 0.041 U	< 0.049 U	< 0.19 U	< 0.041 U	< 0.19 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 f	1.879 - 2.486 ft	1802045921	Not Excavated	0.0051 J	0.0056 J	< 0.018 U	0.0054 J	< 0.039 U	< 0.039 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U
Northern Athletic Field	SSHS-B3118	012120 08:10_SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	0.13	0.15	0.063 J	0.1	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	0.3 J
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	0.082	0.11	0.038 J	0.061 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	0.062 J	0.086	0.031 J	0.052 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	0.046 J	0.061 J	0.028 J	0.045 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	0.046 J	< 0.018 U	< 0.022 U	0.039 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	0.043 J	0.055 J	0.028 J	0.039 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	0.019 JT	0.026 J	0.0091 J	0.013 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	0.041 T	0.064	0.022 J	0.025 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	0.011 JT	0.017 J	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	0.022 JT	0.031 J	0.011 J	0.013 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	0.034 JT	0.051	0.019 J	0.026 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	0.035 JT	0.051	0.022 J	0.022 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	0.034 JT	0.06	0.02 J	0.021 JT	< 0.028 U	< 0.012 U	< 0.0065 U	0.32 J	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	0.011 J	0.019 J	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	0.035 J	0.051	0.021 J	0.022 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 1.9 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	0.072 J	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 1.9 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 2 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.081 UT	< 0.4 U	< 0.4 UT	0.047 J	< 0.081 UT	< 0.4 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 1.9 U	< 0.076 U	< 0.38 U	< 0.38 U	< 0.076 U	< 0.38 U	< 0.38 U	0.2	< 0.076 U	< 0.38 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 2 U	0.56	< 0.39 U	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	1.6	0.26	0.22 J
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 2 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.078 U	< 0.39 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 1.8 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.07 U	< 0.07 U	< 0.35 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	0.053 J	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 2 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.078 U	< 0.078 U	< 0.39 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 1.8 UJ	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 1.9 U	< 0.074 U	< 0.37 U	< 0.37 U	< 0.074 U	< 0.37 U	< 0.37 U	< 0.074 U	< 0.074 U	< 0.37 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 1.9 U	< 0.073 U	< 0.36 U	< 0.36 U	< 0.073 U	< 0.36 U	< 0.36 U	< 0.073 U	< 0.073 U	< 0.36 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 2 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	0.05 J	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 1.9 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.075 U	< 0.075 U	< 0.37 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 1.9 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 2 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	0.054 J	< 0.079 U	< 0.39 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 1.9 U	0.052 J	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	0.22	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	0.099	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 2 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	0.048 J	< 0.08 U	< 0.39 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 1.9 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.075 U	< 0.37 U	< 0.37 U	0.052 J	< 0.075 U	< 0.37 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 1.9 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.077 U	< 0.077 U	< 0.38 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	< 1.9 U	< 0.074 U	< 0.37 U	< 0.37 U	< 0.074 U	< 0.37 U	< 0.37 U	< 0.074 U	< 0.074 U	< 0.37 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.083	< 0.00081 U	0.032 J
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 1.2 U	< 0.083 U	< 0.12 U	< 0.084 U	< 0.082 U	< 0.083 U	< 0.11 U	0.34 J	< 0.23 U	< 0.078 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.24 U	0.046 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.5	0.13	0.059 J
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.47 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.044 U	0.26	< 0.092 U	< 0.032 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.22 U	< 0.034 U	< 0.091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 1.8 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.072 U	< 0.35 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 1.8 U	< 0.072 U	< 0.36 U	< 0.36 U	< 0.072 U	< 0.36 U	< 0.36 U	< 0.072 U	< 0.072 U	< 0.36 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 1.8 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.072 U	< 0.35 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 1.8 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.07 U	< 0.07 U	< 0.35 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 1.8 U	< 0.072 U	< 0.36 U	< 0.36 U	< 0.072 U	< 0.36 U	< 0.36 U	0.16	< 0.072 U	< 0.36 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 1.8 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.072 U	< 0.35 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 1.8 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.071 U	< 0.071 U	< 0.35 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 1.8 U	< 0.069 U	< 0.34 U	< 0.34 U	< 0.069 U	< 0.34 U	< 0.34 U	< 0.069 U	< 0.069 U	< 0.34 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 1.7 U	< 0.068 U	< 0.34 U	< 0.34 U	< 0.068 U	< 0.34 U	< 0.34 U	< 0.068 U	< 0.068 U	< 0.34 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 1.9 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.076 U	< 0.076 U	< 0.37 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 1.8 U	< 0.069 U	< 0.34 U	< 0.34 U	< 0.069 U	< 0.34 U	< 0.34 U	< 0.069 U	< 0.069 U	< 0.34 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 1.8 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.072 U	< 0.072 U	< 0.35 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 1.8 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.07 U	< 0.35 U	< 0.35 U	0.073	< 0.07 U	< 0.35 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 1.7 U	< 0.068 U	< 0.34 U	< 0.34 U	< 0.068 U	< 0.34 U	< 0.34 U	< 0.068 U	< 0.068 U	< 0.34 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U	< 0.039 U	< 0.18 U	< 0.053 U	< 0.036 U	< 0.039 U	< 0.039 U	0.0073 J	< 0.018 U	< 0.039 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U	< 0.039 U	< 0.18 U	< 0.053 U	< 0.036 U	< 0.039 U	< 0.039 U	0.0090 J	< 0.018 U	< 0.039 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 f	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.18 U	< 0.041 U	< 0.18 U	< 0.055 U	< 0.037 U	< 0.041 U	< 0.041 U	< 0.018 U	< 0.018 U	< 0.041 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.19 U	< 0.041 U	< 0.19 U	< 0.056 U	< 0.037 U	< 0.041 U	< 0.041 U	< 0.019 U	< 0.019 U	< 0.041 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 f	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.18 U	< 0.039 U	< 0.18 U	< 0.053 U	< 0.035 U	< 0.039 U	< 0.039 U	< 0.018 U	< 0.018 U	< 0.039 U
Northern Athletic Field	SSHS-B3118	012120 08:10_SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	0.15	0.029 J	< 0.018 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 UJ	< 0.018 U	< 0.018 U	< 0.024 U	0.079	< 0.051 U	< 0.017 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.063 J	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.048 J	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.043 J	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.018 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.045 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.037 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.041 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 UT	< 0.013 U	0.044 J	< 0.016 UT	< 0.012 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.014 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.044 J	< 0.016 U	< 0.012 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.4 U	< 0.081 U	< 0.4 U	< 0.4 U	< 0.81 UT	< 4 UT	< 0.4 UT	< 2 UT	< 0.4 UT	< 4 UT
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.38 U	< 0.076 U	< 0.38 U	< 0.38 U	< 0.76 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.39 U	< 0.079 U	< 0.39 U	< 0.39 U	< 0.79 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.78 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.35 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.7 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.39 U	< 0.078 U	< 0.39 U	< 0.39 U	< 0.78 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.37 U	< 0.074 U	< 0.37 U	< 0.37 U	< 0.74 U	< 3.7 U	< 0.37 U	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.36 U	< 0.073 U	< 0.36 U	< 0.36 U	< 0.73 U	< 3.6 U	< 0.36 U	< 1.9 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 2 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.37 UT	< 0.075 U	< 0.37 U	< 0.37 U	< 0.75 U	< 3.7 U	< 0.37 U	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.39 UT	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.38 UT	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.39 UT	< 0.079 U	< 0.39 U	< 0.39 U	< 0.79 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.39 U	< 0.08 U	< 0.39 U	< 0.39 U	< 0.8 U	< 3.9 U	< 0.39 U	< 2 U	< 0.39 U	< 3.9 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.37 U	< 0.075 U	< 0.37 U	< 0.37 U	< 0.75 U	< 3.7 U	< 0.37 U	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.38 U	< 0.077 U	< 0.38 U	< 0.38 U	< 0.77 U	< 3.8 U	< 0.38 U	< 1.9 U	< 0.38 U	< 3.8 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	< 0.37 U	< 0.074 U	< 0.37 U	< 0.37 U	< 0.74 U	< 3.7 U	< 0.37 U	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 1.7 U	< 0.14 U	< 0.63 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U	< 0.11 U	< 9.9 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.67 U	< 0.056 U	< 0.25 U	< 0.045 U	< 0.053 U	< 0.32 U	< 0.42 U	< 1.2 U	< 0.045 U	< 4 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.72 U	< 3.5 U	< 0.35 UT	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 UT	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 UT	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 UT	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.36 U	< 0.072 U	< 0.36 U	< 0.36 U	< 0.72 U	< 3.6 U	< 0.36 U	< 1.8 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.7 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.72 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.35 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.7 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.7 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.36 U	< 0.072 U	< 0.36 U	< 0.36 U	< 0.72 U	< 3.6 U	< 0.36 U	< 1.8 U	< 0.36 U	< 3.6 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.72 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U	< 0.071 U	< 0.35 U	< 0.35 U	< 0.71 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 UT	< 0.07 U	< 0.34 U	< 0.34 U	< 0.7 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 UT	< 0.069 U	< 0.34 U	< 0.34 U	< 0.69 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 UT	< 0.07 U	< 0.34 U	< 0.34 U	< 0.7 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 UT	< 0.068 U	< 0.34 U	< 0.34 U	< 0.68 U	< 3.4 U	< 0.34 U	< 1.7 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.37 U	< 0.076 U	< 0.37 U	< 0.37 U	< 0.76 U	< 3.7 U	< 0.37 U	< 1.9 U	< 0.37 U	< 3.7 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.7 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.34 U	< 0.069 U	< 0.34 U	< 0.34 U	< 0.69 U	< 3.4 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.35 U	< 0.072 U	< 0.35 U	< 0.35 U	< 0.72 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.35 U	< 0.07 U	< 0.35 U	< 0.35 U	< 0.7 U	< 3.5 U	< 0.35 U	< 1.8 U	< 0.35 U	< 3.5 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.34 U	< 0.068 U	< 0.34 U	< 0.34 U	< 0.68 U	< 3.4 U	< 0.34 U	< 1.7 U	< 0.34 U	< 3.4 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.36 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.53 U	< 0.039 U	< 1.1 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.36 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.53 U	< 0.039 U	< 1.1 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 f	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.37 U	< 0.048 U	< 0.18 U	< 0.041 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.55 U	< 0.041 U	< 1.1 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.37 U	< 0.049 U	< 0.19 U	< 0.041 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.56 U	< 0.041 U	< 1.1 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 f	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.35 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.53 UT	< 0.039 U	< 1.1 UT
Northern Athletic Field	SSHS-B3118	012120 08:10_SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	0.18 J	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	0.019 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 UT	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.38 U		< 0.77 U		0.15	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.38 U		< 0.77 U		< 0.077 U	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.4 UT		< 0.81 U		0.067 J	< 0.081 U	< 0.081 UT	< 0.081 U	< 0.4 U	< 0.4 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.38 U		< 0.76 U		0.44	< 0.076 U	< 0.076 U	< 0.076 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.39 U		< 0.79 U		4.3	0.45	< 0.079 U	< 0.079 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.39 U		< 0.78 U		0.041 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.35 U		< 0.7 U		< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.35 U		< 0.71 U		0.097	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.39 U		< 0.78 U		0.054 J	< 0.078 U	< 0.078 U	< 0.078 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.35 U		< 0.71 U		0.065 J	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.37 U		< 0.74 U		0.055 J	< 0.074 U	< 0.074 U	< 0.074 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.36 U		< 0.73 U		0.035 J	< 0.073 U	< 0.073 U	< 0.073 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.38 U		< 0.77 U		0.077	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.37 U		< 0.75 U		0.024 J	< 0.075 U	< 0.075 U	< 0.075 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.39 U		< 0.8 U		0.03 J	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.38 U		< 0.77 U		0.034 J	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.39 U		< 0.79 U		0.094	< 0.079 U	< 0.079 U	< 0.079 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.38 U		< 0.77 U		0.52	0.082	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.39 U		< 0.8 U		0.2	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.39 U		< 0.8 U		0.084	< 0.08 U	< 0.08 U	< 0.08 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.37 U		< 0.75 U		0.09	< 0.075 U	< 0.075 U	< 0.075 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.38 U		< 0.77 U		0.066 J	< 0.077 U	< 0.077 U	< 0.077 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	< 0.37 U		< 0.74 U		< 0.074 U	< 0.074 U	< 0.074 U	< 0.074 U	< 0.37 U	< 0.37 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.076 U			< 0.018 U	0.11	0.0045 J	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.27 U			< 0.56 U	0.73	< 0.07 U	< 0.13 U	< 0.1 U	< 0.18 U	< 0.092 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.055 U			< 0.11 U	0.85	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.11 U			< 0.22 U	0.33	< 0.028 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U		< 0.72 U		< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.36 U		< 0.72 U		< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.34 U		< 0.7 U		< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.35 U		< 0.72 U		< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.35 U		< 0.7 U		0.04 J	< 0.07 U	< 0.07 U	< 0.07 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.34 U		< 0.7 U		< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.36 U		< 0.72 U		0.3	< 0.072 U	< 0.072 U	< 0.072 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U		< 0.72 U		< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.35 U		< 0.71 U		< 0.071 U	< 0.071 U	< 0.071 U	< 0.071 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 U		< 0.7 U		< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 U		< 0.69 U		< 0.069 U	< 0.069 U	< 0.069 U	< 0.069 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 U		< 0.7 U		< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.34 U		< 0.68 U		< 0.068 U	< 0.068 U	< 0.068 U	< 0.068 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.37 U		< 0.76 U		0.029 J	< 0.076 U	< 0.076 U	< 0.076 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.34 U		< 0.7 U		< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.34 U		< 0.69 U		< 0.069 U	< 0.069 U	< 0.069 U	< 0.069 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.35 U		< 0.72 U		< 0.072 U	< 0.072 U	< 0.072 U	< 0.072 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.35 U		< 0.7 U		0.11	< 0.07 U	< 0.07 U	< 0.07 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.34 U		< 0.68 U		< 0.068 U	< 0.068 U	< 0.068 U	< 0.068 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U		< 0.18 U		0.0091 J	< 0.018 U	< 0.036 U	< 0.053 U	< 0.53 U	< 0.18 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U		< 0.18 U		0.019	< 0.018 U	< 0.036 U	< 0.053 U	< 0.53 U	< 0.18 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.18 U		< 0.18 U		< 0.018 U	< 0.018 U	< 0.037 U	< 0.055 U	< 0.55 UT	< 0.18 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.19 U		< 0.19 U		< 0.019 U	< 0.019 U	< 0.037 U	< 0.056 U	< 0.56 UT	< 0.19 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.18 U		< 0.18 U		0.0046 J	< 0.018 U	< 0.035 U	< 0.053 U	< 0.53 UT	< 0.18 UT
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	< 0.02 U			< 0.13 U	0.27	0.016 J	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.06 U			< 0.12 U	0.14	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.053 U	< 0.11 U			0.09	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.055 U	< 0.11 U			0.074	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.056 U	< 0.12 U			0.069 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.058 U	< 0.12 U			0.075 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		0.029 J	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.039 U		< 0.031 U		0.054 J	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		0.018 J	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		0.034 J	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		0.049 J	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.039 U		< 0.032 U		0.065 J	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.039 U		< 0.031 U		0.069 J	< 0.01 U	< 0.017 UT	< 0.0076 UT	< 0.031 UT	< 0.012 UT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.04 U		< 0.032 U		0.066 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	0.042 J	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.077 U	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.081 UT	< 0.4 U		< 0.4 UT	< 0.081 U		< 0.081 U	< 2 UT	< 2 U	< 2 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	0.13	< 0.38 U		< 0.38 U	< 0.076 U		< 0.076 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	0.84	< 0.39 U		< 0.39 U	0.046 J		0.13	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.078 U	< 0.39 U		< 0.39 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.07 U	< 0.35 U		< 0.35 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.078 U	< 0.39 U		< 0.39 U	< 0.078 U		< 0.078 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.074 U	< 0.37 U		< 0.37 U	< 0.074 U		< 0.074 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.073 U	< 0.36 U		< 0.36 U	< 0.073 U		< 0.073 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.077 U	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.075 U	< 0.37 U		< 0.37 U	< 0.075 U		< 0.075 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.08 U	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.077 U	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.079 U	< 0.39 U		< 0.39 U	< 0.079 U		< 0.079 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.14	< 0.38 U		< 0.38 U	0.037 J		0.053 J	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	0.069 J	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.08 U	< 0.39 U		< 0.39 U	< 0.08 U		< 0.08 U	< 2 U	< 2 U	< 2 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.075 U	< 0.37 U		< 0.37 U	< 0.075 U		< 0.075 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.077 U	< 0.38 U		< 0.38 U	< 0.077 U		< 0.077 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	< 0.074 U	< 0.37 U		< 0.37 U	< 0.074 U		< 0.074 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	0.076	< 0.038 U	< 0.035 U	< 0.015 U	0.037		0.14	< 0.049 U	< 0.06 U	< 0.073 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	0.22 J	< 0.51 U	< 0.52 U	< 0.091 U	< 0.085 U		< 0.069 U	< 0.81 U	< 0.45 U	< 0.087 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	0.44	< 0.1 U	< 0.11 U	< 0.019 U	0.068 J		0.15	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	0.18	< 0.21 U	< 0.21 U	< 0.037 U	< 0.035 U		0.034 J	< 0.33 U	< 0.18 U	< 0.035 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.072 U	< 0.35 U		< 0.35 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.072 U	< 0.36 U		< 0.36 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.072 U	< 0.35 U		< 0.35 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.07 U	< 0.35 U		< 0.35 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	0.094	< 0.36 U		< 0.36 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.072 U	< 0.35 U		< 0.35 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.071 U	< 0.35 U		< 0.35 U	< 0.071 U		< 0.071 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.069 U	< 0.34 U		< 0.34 U	< 0.069 U		< 0.069 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.068 U	< 0.34 U		< 0.34 U	< 0.068 U		< 0.068 U	< 1.7 U	< 1.7 U	< 1.7 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.076 U	< 0.37 U		< 0.37 U	< 0.076 U		< 0.076 U	< 1.9 U	< 1.9 U	< 1.9 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U		< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.069 U	< 0.34 U		< 0.34 U	< 0.069 U		< 0.069 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.072 U	< 0.35 U		< 0.35 U	< 0.072 U		< 0.072 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.07 U	< 0.35 U		< 0.35 U	< 0.07 U		0.068 J	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.068 U	< 0.34 U		< 0.34 U	< 0.068 U		< 0.068 U	< 1.7 U	< 1.7 U	< 1.7 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0059 J	< 0.053 U		< 0.071 U	0.0060 J		0.0095 J	< 0.053 U	< 0.18 U	< 0.18 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0086 J	< 0.053 U		< 0.071 U	< 0.018 U		< 0.018 U	< 0.053 U	< 0.18 U	< 0.18 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 f	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.018 U	< 0.055 U		< 0.074 U	< 0.018 U		< 0.018 U	< 0.055 U	< 0.18 U	< 0.18 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.019 U	< 0.056 U		< 0.075 U	< 0.019 U		< 0.019 U	< 0.056 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 f	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.018 U	< 0.053 U		< 0.071 U	< 0.018 U		< 0.018 U	< 0.053 U	< 0.18 U	< 0.18 U
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	0.082	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	0.051 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	0.042 J	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.038 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	0.021 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	0.031 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.0082 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	0.021 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	0.033 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	0.029 J	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	0.025 JT	< 0.013 U		< 0.1 UT	< 0.01 U	< 0.022 U	0.0063 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	0.028 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.77 U	< 0.38 U	< 1.9 U		< 0.077 U	< 0.38 U	< 1.9 U	0.08	< 0.38 U	0.12
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.77 U	< 0.38 U	< 1.9 U		< 0.077 U	< 0.38 U	< 1.9 U	< 0.077 U	< 0.38 U	< 0.077 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.81 UT	< 0.4 UT	< 2 U		< 0.081 UT	< 0.4 UT	< 2 U	< 0.081 U	< 0.4 UT	0.06 J
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.76 U	< 0.38 U	< 1.9 U		< 0.076 U	< 0.38 U	< 1.9 U	0.28	< 0.38 U	0.35
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.79 U	< 0.39 U	< 2 U		< 0.079 U	< 0.39 U	< 2 U	3.8	< 0.39 U	3.5
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.78 U	< 0.39 U	< 2 U		< 0.078 U	< 0.39 U	< 2 U	< 0.078 U	< 0.39 U	0.035 J
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.7 U	< 0.35 U	< 1.8 U		< 0.07 U	< 0.35 U	< 1.8 U	< 0.07 U	< 0.35 U	< 0.07 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	0.047 J	< 0.35 U	0.087
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated	< 0.78 U	< 0.39 U	< 2 U		< 0.078 U	< 0.39 U	< 2 U	< 0.078 U	< 0.39 U	0.046 J
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	0.029 J	< 0.35 U	0.048 J
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.74 U	< 0.37 U	< 1.9 U		< 0.074 U	< 0.37 U	< 1.9 U	< 0.074 U	< 0.37 U	0.045 J
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.73 U	< 0.36 U	< 1.9 U		< 0.073 U	< 0.36 U	< 1.9 U	< 0.073 U	< 0.36 U	0.029 J
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.77 U	< 0.38 U	< 2 U		< 0.077 U	< 0.38 U	< 2 U	0.038 J	< 0.38 U	0.069 J
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.75 U	< 0.37 U	< 1.9 U		< 0.075 U	< 0.37 U	< 1.9 U	< 0.075 U	< 0.37 U	< 0.075 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	< 0.08 U	< 0.39 U	0.03 J
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.77 U	< 0.38 U	< 1.9 U		< 0.077 U	< 0.38 U	< 1.9 U	< 0.077 U	< 0.38 U	0.029 J
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.79 U	< 0.39 U	< 2 U		< 0.079 U	< 0.39 U	< 2 U	0.038 J	< 0.39 U	0.074 J
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.77 U	< 0.38 U	< 1.9 U		< 0.077 U	< 0.38 U	< 1.9 U	0.5	< 0.38 U	0.41
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	0.12	< 0.39 U	0.17
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.8 U	< 0.39 U	< 2 U		< 0.08 U	< 0.39 U	< 2 U	0.032 J	< 0.39 U	0.061 J
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.75 U	< 0.37 U	< 1.9 U		< 0.075 U	< 0.37 U	< 1.9 U	0.031 J	< 0.37 U	0.071 J
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.77 U	< 0.38 U	< 1.9 U		< 0.077 U	< 0.38 U	< 1.9 U	0.022 J	< 0.38 U	0.05 J
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated	< 0.74 U	< 0.37 U	< 1.9 U		< 0.074 U	< 0.37 U	< 1.9 U	< 0.074 U	< 0.37 U	< 0.074 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.079	0.015 J	0.088
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.65 U	< 0.28 U	< 1.3 U		< 0.12 U	< 0.59 U	< 2.9 U	0.23 J	< 0.54 U	0.65
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.42	< 0.11 U	0.84
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.26 U	< 0.11 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.11 J	< 0.22 U	0.34
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	< 0.016 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.72 U	< 0.35 U	< 1.8 U		< 0.072 U	< 0.35 U	< 1.8 U	< 0.072 U	< 0.35 U	< 0.072 UT
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 UT
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 UT
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 UT
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.72 U	< 0.36 U	< 1.8 U		< 0.072 U	< 0.36 U	< 1.8 U	< 0.072 U	< 0.36 U	< 0.072 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.7 U	< 0.34 U	< 1.8 U		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.72 U	< 0.35 U	< 1.8 U		< 0.072 U	< 0.35 U	< 1.8 U	< 0.072 U	< 0.35 U	< 0.072 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.7 U	< 0.35 U	< 1.8 U		< 0.07 U	< 0.35 U	< 1.8 U	0.039 J	< 0.35 U	0.033 J
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.7 U	< 0.34 U	< 1.8 U		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.72 U	< 0.36 U	< 1.8 U		< 0.072 U	< 0.36 U	< 1.8 U	0.1	< 0.36 U	0.26
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.72 U	< 0.35 U	< 1.8 U		< 0.072 U	< 0.35 U	< 1.8 U	< 0.072 U	< 0.35 U	< 0.072 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.71 U	< 0.35 U	< 1.8 U		< 0.071 U	< 0.35 U	< 1.8 U	< 0.071 U	< 0.35 U	< 0.071 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.7 U	< 0.34 U	< 1.8 U		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.69 U	< 0.34 U	< 1.8 U		< 0.069 U	< 0.34 U	< 1.8 U	< 0.069 U	< 0.34 U	< 0.069 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.7 U	< 0.34 U	< 1.8 U		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.68 U	< 0.34 U	< 1.7 U		< 0.068 U	< 0.34 U	< 1.7 U	< 0.068 U	< 0.34 U	< 0.068 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.76 U	< 0.37 U	< 1.9 U		< 0.076 U	< 0.37 U	< 1.9 U	< 0.076 U	< 0.37 U	< 0.076 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.7 U	< 0.34 U	< 1.8 U		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.69 U	< 0.34 U	< 1.8 U		< 0.069 U	< 0.34 U	< 1.8 U	< 0.069 U	< 0.34 U	< 0.069 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.72 U	< 0.35 U	< 1.8 U		< 0.072 U	< 0.35 U	< 1.8 U	< 0.072 U	< 0.35 U	< 0.072 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.7 U	< 0.35 U	< 1.8 U		< 0.07 U	< 0.35 U	< 1.8 U	0.056 J	< 0.35 U	0.11
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.68 U	< 0.34 U	< 1.7 U		< 0.068 U	< 0.34 U	< 1.7 U	< 0.068 U	< 0.34 U	< 0.068 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.039 U	< 0.053 U	< 0.53 U		< 0.071 U	< 0.039 U	< 0.18 U	0.0051 J	< 0.039 U	0.0087 J
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.039 U	< 0.053 U	< 0.53 U		< 0.071 U	< 0.039 U	< 0.18 U	0.012 J	< 0.039 U	0.017 J
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.041 U	< 0.055 U	< 0.55 U		< 0.074 U	< 0.041 U	< 0.18 U	< 0.018 U	< 0.041 U	< 0.018 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.041 U	< 0.056 U	< 0.56 U		< 0.075 U	< 0.041 U	< 0.19 U	< 0.019 U	< 0.041 U	< 0.019 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.039 U	< 0.053 U	< 0.53 U		< 0.071 U	< 0.039 U	< 0.18 U	< 0.018 U	< 0.039 U	0.0061 J
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.18	< 0.12 U	0.33
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.061 J	< 0.12 U	0.13
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.028 J	< 0.11 U	0.079
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.026 J	< 0.11 U	0.069 J
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.023 J	< 0.11 U	0.058 J
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.062 J
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.014 J	< 0.013 U	0.027 J
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.023 J	< 0.013 U	0.051 J
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0090 J	< 0.013 U	0.016 J
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.015 J	< 0.013 U	0.03 J
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.018 J	< 0.013 U	0.044 J
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.026 J	< 0.013 U	0.054 J
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 UT	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.031 J	< 0.013 UT	0.051 J
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	0.017 J
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.032 J	< 0.014 U	0.062 J

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1-20260312	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1-20260312	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1-20260312	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 0.4 UT	< 0.4 U	< 0.4 UT	< 0.4 UT
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1-20260312	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1-20260312	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1-20260312	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1-20260312	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1-20260312	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1-20260312	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1-20260312	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1-20260312	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1-20260312	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15-20260313	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1-20260313	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1-20260313	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1-20260313	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1-20260313	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1-20260313	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1-20260313	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1-20260313	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 0.39 U	< 0.39 U	< 0.39 U	< 0.39 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1-20260313	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1-20260313	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 0.38 U	< 0.38 U	< 0.38 U	< 0.38 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1-20260313	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	0.00	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated		< 0.077 U	< 0.74 U	< 0.13 U	< 0.098 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated		< 0.031 U	< 0.3 U	< 0.051 U	< 0.04 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2-20260312	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2-20260312	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2-20260312	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2-20260312	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	0.00	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2-20260312	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2-20260312	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2-20260312	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2-20260312	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2-20260312	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	0.00	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2-20260312	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2-20260312	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2-20260312	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2-20260312	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 0.36 U	< 0.36 U	< 0.36 U	< 0.36 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2-20260312	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	0.00	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2-20260312	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2-20260312	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2-20260312	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	0.00	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2-20260313	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2-20260313	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2-20260313	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2-20260313	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	0.00	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2-20260313	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2-20260313	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2-20260313	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2-20260313	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	0.00	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2-20260313	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2-20260313	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	0.00	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		< 0.039 U	< 0.18 U	< 0.039 U	< 0.039 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		< 0.039 U	< 0.18 U	< 0.039 U	< 0.039 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated		< 0.041 U	< 0.18 U	< 0.041 U	< 0.041 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated		< 0.041 U	< 0.19 U	< 0.041 U	< 0.041 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated		< 0.039 U	< 0.18 U	< 0.039 U	< 0.039 U
Northern Athletic Field	SSHS-B3118	012120 08:10 SSHS-B3118-SUB-0-0.17	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0-0.17	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated			1.519	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.13
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated			0.441	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.04
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated			0.268	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.029 J
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated			1.907	< 0.025 U	0.04 J	< 0.15 U	0.033 J	< 0.19 U	< 0.16 U	< 0.053 U	0.16
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated			0.451	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.048 J
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated			4.855	< 0.024 U	< 0.018 U	< 0.15 U	0.08 J	< 0.18 U	< 0.15 U	< 0.052 U	0.44
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated			0.713	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.076 J
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated			1.779	< 0.023 U	0.059 J	< 0.14 U	0.038 J	< 0.18 U	< 0.15 U	< 0.05 U	0.17
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated			1.672	< 0.011 U	0.036 J	< 0.019 U	0.018 J	< 0.022 U	< 0.013 U	< 0.063 U	0.15
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated			3.084	< 0.011 U	0.035 J	< 0.02 U	0.037 J	< 0.024 U	< 0.014 U	< 0.067 U	0.26
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated			0.623	< 0.012 U	0.012 J	< 0.02 U	0.017 J	< 0.024 U	< 0.014 U	< 0.067 U	0.054
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated			0.419	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.048
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated			0.232	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.069 U	0.029 J
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated			1.026	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.088
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated			0.619	< 0.011 U	0.019 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.048
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated			0.0183	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated			0.411	< 0.0071	0.039	< 0.03	0.02	< 0.036	< 0.033	< 0.055	0.058
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated			3.782	< 0.0022 U	0.13	< 0.032 U	0.062	< 0.11 U	< 0.05 U	< 0.067 U	0.32
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated			0.015	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated			0.04	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated			0.472	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.051 J
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated			1.947	< 0.0099 U	0.2 J	< 0.017 U	0.032 J	< 0.02 UT	0.019 J	< 0.058 UT	0.13
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated			2.14	< 0.01 U	0.22 J	0.026 J	0.047 J	< 0.021 UT	0.024 J	< 0.059 UT	0.13
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated			0.288	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.034 J
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	--	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated			1.0625	< 0.01 U	0.011 J	< 0.017 U	0.011 J	< 0.021 U	< 0.012 U	< 0.058 U	0.096
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	--	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated			0.657	0.011 J	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.078
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated			0.261	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	0.029 J
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated			0.1126	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.016 J
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated			1.3396	< 0.011 U	0.013 J	< 0.018 U	0.02 J	< 0.022 U	< 0.013 U	< 0.061 U	0.12
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated			0.0305	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.013 J
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated			1.14	< 0.011 U	0.035 J	< 0.018 U	0.015 J	< 0.022 U	< 0.013 U	< 0.061 U	0.093
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated			4.321	0.011 J	0.11 J	< 0.017 U	0.11 J	< 0.021 U	< 0.012 U	< 0.059 U	0.4
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated			0.1533	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.019 J
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated			0.518	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.051
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated			0.046	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.012 J
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated			0.148	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.019 J
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated			3.554	< 0.021 U	0.24	< 0.13 U	0.13	< 0.16 U	< 0.13 U	< 0.044 U	0.26
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	--	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated			1.387	< 0.022 U	0.044 J	< 0.14 U	0.35	< 0.17 U	< 0.14 U	< 0.048 U	0.077
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated			3.464	< 0.023 U	0.13	< 0.14 U	0.075 J	< 0.18 U	< 0.15 U	< 0.05 U	0.27
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated			2.79	< 0.021 U	0.16	< 0.13 U	0.078	< 0.16 U	< 0.14 U	< 0.046 U	0.23
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	--	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated			3.524	< 0.023 U	0.17	< 0.14 U	0.094	< 0.17 U	< 0.14 U	< 0.049 U	0.28
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated			0.392	< 0.022 U	0.02 J	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.038 J
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated			2.367	< 0.02 U	0.12	< 0.12 U	0.065 J	< 0.15 U	< 0.13 U	< 0.043 U	0.18
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated			1.939	< 0.02 U	0.077	< 0.12 U	0.052 J	< 0.15 U	< 0.13 U	< 0.043 U	0.16
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated			7.137	< 0.021 U	0.3	< 0.13 U	0.2	< 0.16 U	< 0.13 U	< 0.045 U	0.6
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated			4.24	< 0.021 U	0.34	< 0.13 U	0.2	< 0.16 U	< 0.13 U	< 0.044 U	0.29
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated			1.249	< 0.023 U	0.053 J	< 0.14 U	0.037 J	< 0.17 U	< 0.15 U	< 0.049 U	0.1
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated			5.95	< 0.023 U	0.18	< 0.14 U	0.15	< 0.17 U	< 0.14 U	< 0.049 U	0.62
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated			5.859	< 0.024 U	0.19	< 0.15 U	0.14	< 0.18 U	< 0.15 U	< 0.051 U	0.46
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated			1.309	< 0.022 U	0.026 J	< 0.14 U	0.045 J	< 0.17 U	< 0.14 U	0.054 J	0.1
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated			1.254	< 0.022 U	0.051 J	< 0.14 U	0.13	< 0.17 U	< 0.14 U	< 0.048 U	0.088
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated			1.069	< 0.021 U	0.033 J	< 0.13 U	0.14	< 0.16 U	< 0.13 U	< 0.046 U	0.076
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated			1.767	< 0.021 U	0.05 J	< 0.13 U	0.088	< 0.16 U	< 0.13 U	< 0.045 U	0.16
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated			0.132	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated			1.561	< 0.02 U	0.036 J	< 0.13 U	0.027 J	< 0.15 U	< 0.13 U	< 0.044 U	0.098
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated			0.854	< 0.02 U	0.038 J	< 0.12 U	0.025 J	< 0.15 U	< 0.13 U	< 0.043 U	0.065 J
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated			2.333	< 0.02 U	0.082	< 0.12 U	0.043 J	< 0.15 U	< 0.13 U	< 0.043 U	0.18
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated			0.739	< 0.02 U	0.035 J	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.058 J
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated			0.373	< 0.02 U	0.022 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.04 J
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated			1.61	< 0.022 U	0.06 J	< 0.14 U	0.036 J	< 0.17 U	< 0.14 U	< 0.048 U	0.13
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated			1.167	< 0.025 U	0.025 J	< 0.15 U	0.024 J	< 0.19 U	< 0.16 U	< 0.053 U	0.12
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated			4.237	< 0.02 U	0.12	< 0.12 U	0.053 J	< 0.15 U	< 0.13 U	< 0.043 U	0.42
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated			0.323	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	0.048 J
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated			0.986	< 0.025 U	0.035 J	< 0.15 U	0.022 J	< 0.19 U	< 0.16 U	< 0.053 U	0.083 J
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated			1.483	< 0.023 U	0.069 J	< 0.14 U	0.043 J	< 0.17 U	< 0.14 U	< 0.049 U	0.13
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated			15.033	0.053 J	0.84	< 0.15 U	0.44	< 0.19 U	< 0.16 U	< 0.053 U	1.3
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated			0.18	< 0.023 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated			2.252	< 0.02 U	0.07	< 0.12 U	0.054 J	< 0.15 U	< 0.13 U	< 0.042 U	0.2
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	856.65	--	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated			3.323	< 0.021 U	0.12	< 0.13 U	0.084	< 0.16 U	< 0.13 U	< 0.045 U	0.27
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated			1.913	< 0.021 U	0.098	< 0.13 U	0.057 J	< 0.16 U	< 0.14 U	< 0.046 U	0.16

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	0.13	0.22	0.086	0.1 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	0.041	0.064	0.022 J	0.029 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	0.028 J	0.052	< 0.0074 U	0.018 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	0.17	0.22	0.094	0.12	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	0.057 J	0.059 J	0.03 J	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	0.43	0.52	0.21	0.35	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	0.072 J	0.083	0.038 J	0.059 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	0.16	0.2	0.077 J	0.14	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	0.16	0.22	0.11	0.098 J	< 0.029 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	0.27	0.43	0.14	0.22 J	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	0.052	0.084	0.026 J	0.042 J	< 0.032 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	0.039	0.054	0.025 J	0.03 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	0.021 J	0.029 J	0.012 J	0.016 J	< 0.033 U	< 0.015 U	< 0.0076 U	< 0.022 U	< 0.017 U	< 0.02 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	0.093	0.14	0.058	0.06 J	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	0.066	0.097	0.034 J	0.057 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	0.07	< 0.012	< 0.015	< 0.0073	< 0.024	< 0.0099	< 0.0079	< 0.059	< 0.032	< 0.05
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.36	0.57	0.19	0.15	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.041 U	< 0.065 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	0.062 J	0.06 J	0.03 J	0.045 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.1	0.21	0.061	0.077 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.11	0.23	0.065	0.058 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	0.024 J	0.035	0.012 J	0.016 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	0.09	0.14	0.049	0.066 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	0.072	0.092	0.034 J	0.041 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	0.025 J	0.032 J	0.013 J	0.018 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	0.01 J	0.015 J	0.0075 J	0.011 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	0.12	0.15	0.05	0.077 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	0.11	0.16	0.06	0.089 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	0.39	0.48	0.2	0.21 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	0.012 J	0.019 J	0.0083 J	0.013 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	0.046	0.064	0.031 J	0.036 J	< 0.028 U	< 0.013 U	< 0.0066 U	0.049 J	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	0.016 J	0.022 J	0.01 J	0.011 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	0.3	0.4	0.17	0.37	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.086	0.12	0.04 J	0.093	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	0.34	0.4	0.24	0.25	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	0.26	0.37	0.096	0.22	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.35	0.5	0.14	0.3	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	0.045 J	0.052 J	0.034 J	0.034 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	0.22	0.33	0.085	0.19	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.17	0.22	0.1	0.15	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	0.73	0.86	0.42	0.53	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	0.36	0.48	0.19	0.52	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.11	0.16	0.065 J	0.12	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.66	0.68	0.29	0.52	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	0.54	0.68	0.33	0.44	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	0.089	0.11	0.042 J	0.062 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.096	0.12	0.035 J	0.097	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.089	0.096	0.048 J	0.081	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.19	0.18	0.096	0.1	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.031 U	0.035 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	0.13	0.22	0.096	0.26	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	0.089	0.1	0.044 J	0.11	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	0.2	0.28	0.08	0.27	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	0.066 J	0.088	0.035 J	0.089	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	0.044 J	0.047 J	0.022 J	0.044 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	0.15	0.23	0.1	0.13	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	0.12	0.14	0.076 J	0.073 J	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	0.43	0.57	0.19	0.27	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	0.042 J	0.047 J	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	0.1	0.11	0.059 J	0.07 J	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	0.14	0.18	0.083	0.12	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	1.4	1.7	0.8	1.1	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.035 U	0.044 J	< 0.024 U	0.024 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	0.21	0.26	0.11	0.16	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	0.31	0.43	0.16	0.27	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	0.18	0.24	0.098	0.16	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.15 J	0.037	< 0.013 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.046 J	< 0.016 U	< 0.013 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	< 0.016 U	< 0.013 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.28 U	0.02 J	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.22	< 0.055 U	< 0.16 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.053 J	< 0.049 U	< 0.14 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.27 U	0.042 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.48	0.095	< 0.15 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.08	< 0.05 U	< 0.15 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.19	< 0.052 U	< 0.15 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.16 J	0.021 J	< 0.013 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.063 U	0.024 J	< 0.071 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.3 J	0.043	0.015 J
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.058 J	< 0.018 U	< 0.014 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.04 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.065 U	< 0.016 U	< 0.074 U	< 0.024 U	< 0.019 U	< 0.015 U	< 0.015 U	0.025 J	< 0.018 U	< 0.014 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.11 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.054 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	0.0073 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.28	< 0.0068	< 0.029	< 0.034	< 0.0077	< 0.03	< 0.041	0.06	< 0.0082	< 0.036
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.22 U	< 0.056 U	< 0.088 U	< 0.13 U	< 0.041 U	< 0.029 U	< 0.041 U	0.44	< 0.0019 U	< 0.038 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 UT	< 0.02 U	0.065 J	< 0.012 U	< 0.012 U	0.21 J	0.036	0.019 J
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.055 U	0.014 J	< 0.063 UT	< 0.02 U	0.07 J	< 0.013 U	< 0.013 U	0.3 J	< 0.015 U	0.025 J
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.03 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.12 J	0.021 J	< 0.012 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.067 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.026 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.01 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.15 J	0.018 J	< 0.012 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0081 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.11 J	0.02 J	< 0.012 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.055 U	0.014 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.41	0.055	0.025 J
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.018 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.06 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.01 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.02 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.23 U	0.03 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.38	0.084	< 0.13 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.11	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.26 U	0.024 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.37	0.058 J	< 0.15 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.24 U	0.029 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.27	0.061 J	< 0.14 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.26 U	0.023 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.38	0.094	< 0.14 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.048 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.23	0.045 J	< 0.13 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.21	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.24 U	0.05 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.74	0.14	< 0.13 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.23 U	0.037 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.4	0.12	< 0.13 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.13	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.25 U	0.024 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.65	0.14	< 0.14 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.27 U	0.053 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.64	0.097	< 0.15 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.15	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.12	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.11	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.24 U	0.03 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.18	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.13	0.062 J	< 0.13 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.068 J	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.22 U	0.02 J	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.17	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.064 J	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.04 J	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.19	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.14	< 0.055 U	< 0.16 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.41	0.064 J	< 0.13 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.047 J	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.11	< 0.055 U	< 0.16 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.16	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.28 U	0.098	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	1.6	0.28	< 0.16 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.22 U	0.018 J	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.23	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.24 U	0.026 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.36	0.069 J	< 0.13 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.22	< 0.047 U	< 0.14 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

														3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																							
Restricted - Residential																							
Protection of Groundwater																							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated		< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated		< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated		< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated		< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 UT	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 UT	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 UT	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated		< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated		< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated		< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated		< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated		< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated		< 0.063 U	< 0.027 U	< 0.013 U	< 0.05 U	< 0.095 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.21 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated		< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 UT	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated		< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 UT
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated		< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 UT
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated		< 0.039	< 0.0074	0.041	< 0.057	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated		< 0.13 U	< 0.13 U	< 0.091 U	< 0.12 U	< 0.041 U	< 0.065 U	< 0.082 U	< 0.23 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated		< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated		< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated		< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated		< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated		< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated		< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated		< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated		< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	0.042 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated		< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated		< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated		< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated		< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated		< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated		< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated		< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated		< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.04 U		< 0.033 U		0.26 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.041 U		< 0.033 U		0.074 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.04 U		< 0.033 U		0.05 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.26 U	< 0.13 U			0.33	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.23 U		< 0.12 U		0.084	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.25 U		< 0.13 U		0.9	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.24 U		< 0.12 U		0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	< 0.24 U		< 0.13 U		0.29	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.041 U		< 0.033 U		0.22 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.043 U		< 0.035 U		0.49	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.044 U		< 0.035 U		0.09 J	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.036 U	< 0.014 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.042 U		< 0.034 U		0.065 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.045 U		< 0.037 U		0.037 J	< 0.012 U	< 0.02 U	< 0.0089 U	< 0.037 U	< 0.014 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.042 U		< 0.034 U		0.18 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.013 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.042 U		< 0.034 U		0.069 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.03			< 0.042	0.073	< 0.0097	< 0.0078	< 0.0082	< 0.04	< 0.026
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.18 U			< 0.044 U	0.5	0.03	< 0.0062 U	< 0.035 U	< 0.18 U	< 0.026 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.21 U	< 0.11 U			0.019 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.21 U	< 0.11 U			0.085	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.037 U		< 0.03 UT		0.21 J	0.021 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 UT
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.038 U		< 0.031 UT		0.23 J	0.02 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 UT
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		0.053 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		0.17 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		0.091 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.039 U		< 0.032 U		0.041 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.039 U		< 0.032 U		0.018 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.04 U		< 0.032 U		0.24 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.04 U		< 0.032 U		0.15 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.038 U		< 0.031 U		0.72	0.032 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.038 U		< 0.031 U		0.02 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.039 U		< 0.032 U		0.08 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.037 U		< 0.03 U		0.013 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.038 U		< 0.031 U		0.027 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.21 U	< 0.11 U			0.35	0.032 J	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.23 U	< 0.12 U			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.24 U	< 0.13 U			0.46	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.22 U	< 0.12 U			0.39	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.23 U	< 0.12 U			0.41	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.23 U	< 0.12 U			0.054 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.21 U	< 0.11 U			0.28	0.016 J	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.21 U	< 0.11 U			0.26	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.22 U	< 0.11 U			0.88	0.037 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.21 U	< 0.11 U			0.4	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.24 U	< 0.12 U			0.16	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.23 U	< 0.12 U			0.76	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.25 U	< 0.13 U			0.83	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.23 U	< 0.12 U			0.14	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.22 U	< 0.11 U			0.13	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.22 U	< 0.11 U			0.22	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.22 U	< 0.11 U			0.035 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.21 U	< 0.11 U			0.13	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.097	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.32	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.085	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.21 U	< 0.11 U			0.059 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.23 U		< 0.12 U		0.23	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.26 U		< 0.13 U		0.2	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.21 U		< 0.11 U		0.8	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.24 U		< 0.12 U		0.074 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.26 U		< 0.13 U		0.15	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.23 U		< 0.12 U		0.22	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.26 U		< 0.13 U		2.1	0.1	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.24 U		< 0.13 U		0.043 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.2 U		< 0.11 U		0.32	0.02 J	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.22 U		< 0.11 U		0.44	0.019 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.22 U		< 0.12 U		0.26	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	0.12	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	0.038	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	0.022 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	0.11	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	0.28	< 0.12 U		< 0.16 U	< 0.02 U	0.31 J	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	0.053 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	0.12	< 0.12 U		< 0.15 U	0.019 J	< 0.12 U	0.034 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	0.18	< 0.014 U		< 0.11 U	0.015 J	< 0.024 U	0.014 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	0.25	< 0.015 U		< 0.12 U	0.036 J	< 0.025 U	0.034 J	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	0.05	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.014 J	< 0.031 U	< 0.096 U	< 0.047 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	0.034 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.016 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U	< 0.032 U	< 0.099 U	< 0.048 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	0.068	< 0.015 U		< 0.11 U	0.018 J	< 0.025 U	0.013 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	0.066	< 0.015 U		< 0.11 U	0.013 J	< 0.024 U	0.015 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.0076	< 0.026		< 0.028	0.028	< 0.036	0.034	< 0.16	< 0.15	< 0.15
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.11	< 0.091 U	< 0.085 U	< 0.035 U	0.15		0.25	< 0.12 U	< 0.14 U	< 0.18 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	0.015 J	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	0.04 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.12	< 0.013 U		< 0.1 U	0.053 J	< 0.022 U	0.29 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.09	< 0.013 U		< 0.1 U	0.073 J	< 0.022 U	0.32 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	0.019 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	0.075	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0095 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	0.049	< 0.013 U		< 0.1 U	0.016 J	< 0.022 U	0.012 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	0.023 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	0.087	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0086 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	0.086	< 0.014 U		< 0.11 U	0.016 J	< 0.023 U	0.04 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	0.25	< 0.013 U		< 0.1 U	0.02 J	< 0.022 U	0.053 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	0.014 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	0.036	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	0.27	< 0.1 U		< 0.13 U	0.12	< 0.1 U	0.098	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.06 J	< 0.11 U		< 0.14 U	0.1	< 0.11 U	0.091	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	0.2	< 0.12 U		< 0.15 U	0.042 J	< 0.12 U	0.041 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	0.18	< 0.11 U		< 0.14 U	0.035 J	< 0.11 U	0.035 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.23	< 0.11 U		< 0.15 U	0.078 J	< 0.12 U	0.056 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	0.16	< 0.099 U		< 0.13 U	0.067 J	< 0.1 U	0.056 J	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.12	< 0.1 U		< 0.13 U	0.036 J	< 0.1 U	0.027 J	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	0.44	< 0.1 U		< 0.14 U	0.14	< 0.11 U	0.13	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	0.37	< 0.1 U		< 0.13 U	0.13	< 0.1 U	0.11	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.086	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.47	< 0.11 U		< 0.15 U	0.026 J	< 0.11 U	0.03 J	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	0.36	< 0.12 U		< 0.15 U	0.049 J	< 0.12 U	0.052 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	0.062 J	< 0.11 U		< 0.14 U	0.13	< 0.11 U	0.089	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.08	< 0.11 U		< 0.14 U	0.077	< 0.11 U	0.078	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.063 J	< 0.11 U		< 0.14 U	0.038 J	< 0.11 U	0.03 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	0.092	< 0.1 U		< 0.14 U	0.03 J	< 0.11 U	0.031 J	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	0.2	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.018 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	0.077	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	0.041 J	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	0.2	< 0.099 U		< 0.13 U	0.043 J	< 0.1 U	0.16	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	0.064 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.063 J	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	0.11	< 0.11 U		< 0.15 U	0.028 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	0.058 J	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	0.22	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	0.065 J	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	0.097	< 0.11 U		< 0.15 U	0.034 J	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	0.88	< 0.12 U		< 0.16 U	0.081 J	< 0.13 U	0.11	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.041 U	< 0.12 UT		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	0.12	< 0.098 U		< 0.13 U	0.02 J	< 0.1 U	0.028 J	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	0.21	< 0.1 U		< 0.14 U	0.067 J	< 0.11 U	0.051 J	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	0.13	< 0.11 U		< 0.14 U	0.027 J	< 0.11 U	0.028 J	< 0.17 U	< 0.094 U	< 0.14 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.076 J	< 0.014 U	0.21 J
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.026 J	< 0.014 U	0.061 J
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	0.039 J
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.14	< 0.13 U	0.31
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.043 J	< 0.12 U	0.077
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.37	< 0.13 U	0.7
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.047 J	< 0.12 U	0.095
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.12	< 0.12 U	0.24
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.081 J	< 0.014 U	0.24 J
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.15 J	< 0.015 U	0.46
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.022 U	< 0.041 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.049 J	< 0.015 U	0.087 J
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.023 J	< 0.014 U	0.061 J
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.086 U	0.027 J	< 0.015 U	0.036 J
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	0.076 J	< 0.014 U	0.14 J
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.038 J	< 0.014 U	0.075 J
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	0.011 J
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.031	< 0.04	< 0.13		< 0.0086	< 0.034	< 0.033	0.035	< 0.0087	0.061
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.038 U	< 0.038 U	< 0.28 U		< 0.032 U	< 0.035 U	< 0.17 U	0.29	< 0.023 U	0.51
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.021 J
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.029 J	< 0.11 U	0.07 J
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.21 J	< 0.013 U	0.24 J
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.28 J	< 0.013 U	0.26 J
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.023 J	< 0.013 U	0.042 J
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	--	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.065 J	< 0.013 U	0.15 J
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	--	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.028 J	< 0.013 U	0.082 J
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.075 U	0.018 J	< 0.013 U	0.036 J
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	0.0081 J	< 0.013 U	0.017 J
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.076 U	0.089 J	< 0.014 U	0.21 J
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 UT		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	0.0094 J
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.076 U	0.067 J	< 0.014 U	0.14 J
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 UT		< 0.026 U	< 0.029 U	< 0.073 U	0.36	< 0.013 U	0.64
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 UT		< 0.026 U	< 0.029 U	< 0.073 U	0.011 J	< 0.013 U	0.019 J
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	0.039 J	< 0.013 U	0.075 J
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.011 J
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 UT		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.023 J
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.18	< 0.11 U	0.53
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	--	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.1	< 0.12 U	0.13
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.23	< 0.12 U	0.53
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.2	< 0.11 U	0.4
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.17	< 0.12 U	0.52
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.029 J	< 0.11 U	0.058 J
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.14	< 0.1 U	0.37
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.15	< 0.11 U	0.32
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.33	< 0.11 U	1.1
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.17	< 0.11 U	0.63
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.081	< 0.12 U	0.2
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.15	< 0.12 U	0.83
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.29	< 0.12 U	1
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.22	< 0.12 U	0.19
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.16
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.076	< 0.11 U	0.13
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.15	< 0.11 U	0.28
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.021 J	< 0.11 U	0.041 J
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.06 J	< 0.11 U	0.13
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.045 J	< 0.1 U	0.093
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.12	< 0.1 U	0.31
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.04 J	< 0.11 U	0.087
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.025 J	< 0.11 U	0.052 J
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.094	< 0.12 U	0.21
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.056 J	< 0.13 U	0.16
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.12	< 0.11 U	0.69
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.065 J
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.067 J	< 0.13 U	0.15
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.11	< 0.12 U	0.2
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.87	< 0.13 U	2.3
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.025 J	< 0.12 U	0.044 J
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.2	< 0.1 U	0.34
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.21	< 0.11 U	0.44
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.11	< 0.11 U	0.27

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4-20240112	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated		< 0.013 U	< 0.028 U	< 0.043 U	< 0.054 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated		< 0.028	< 0.024	< 0.039	< 0.055
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated		< 0.041 U	< 0.86 U	< 0.2 U	< 0.19 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated			109.39	0.35	7.4	< 0.3 U	4.5	< 0.37 U	< 0.31 U	< 0.11 U	8.3
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated			0.576	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	0.057 J
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated			2.073	< 0.022 U	0.11	< 0.14 U	0.054 J	< 0.17 U	< 0.14 U	< 0.048 U	0.16
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated			15.163	0.032 J	0.71	< 0.18 U	0.35	< 0.22 U	< 0.18 U	< 0.061 U	1.2
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated			0.462	< 0.024 U	0.033 J	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.042 J
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated			37.2	< 0.026 U	1.5	< 0.16 U	0.73	< 0.2 U	< 0.16 U	< 0.056 U	3.3
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated			2.343	< 0.027 U	0.048 J	< 0.16 U	0.039 J	< 0.2 U	< 0.17 U	0.075 J	0.2
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated			8.089	< 0.026 U	0.26	< 0.16 U	0.13	< 0.2 U	< 0.17 U	0.96	0.73
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated			2.532	< 0.022 U	0.06 J	< 0.14 U	0.038 J	< 0.17 U	< 0.14 U	< 0.048 U	0.24
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated			16.804	0.053 J	0.44	< 0.17 U	0.44	< 0.21 U	< 0.17 U	0.11 J	1.4
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated			12.865	0.042 J	0.47	< 0.17 U	0.33	< 0.2 U	< 0.17 U	< 0.058 U	1.1
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated			369.41	0.61	13	< 0.16 U	10	< 0.2 U	0.22 J	< 0.057 U	31
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated			2.816	< 0.022 U	0.12	< 0.14 U	0.07 J	< 0.17 U	< 0.14 U	< 0.048 U	0.25
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.253	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			10.535	0.063 J	0.25	< 0.14 U	0.35	< 0.18 U	< 0.15 U	< 0.05 U	0.92
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			8.337	0.076 J	0.11	< 0.18 U	0.24	< 0.22 U	< 0.19 U	< 0.064 U	0.68
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			1.033	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.093
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			2.966	< 0.024 U	0.035 J	< 0.15 U	0.05 J	< 0.18 U	< 0.15 U	< 0.052 U	0.25
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.8	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.067 J
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			3627	120	< 0.27 U	< 2.2 U	210	< 2.7 U	15	< 0.77 U	240
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.074	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.192	< 0.029 U	< 0.022 U	< 0.18 U	< 0.026 U	< 0.22 U	< 0.18 U	< 0.062 U	< 0.045 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.735	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.054 U	0.063 J
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			2.09	< 0.026 U	0.061 J	< 0.16 U	0.043 J	< 0.2 U	< 0.17 U	< 0.057 U	0.17
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated			2.296	0.026 J	0.11	< 0.16 U	0.053 J	< 0.19 U	< 0.16 U	< 0.055 U	0.17
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			2.724	< 0.024 U	0.078 J	< 0.15 U	0.048 J	< 0.19 U	< 0.15 U	< 0.053 U	0.2
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.7	< 0.023 U	0.024 J	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.06 J
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.978	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.082
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			0.174	< 0.027 U	< 0.021 U	< 0.17 U	< 0.024 U	< 0.21 U	< 0.17 U	< 0.059 U	< 0.043 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated			2.273	< 0.026 U	< 0.02 U	< 0.16 U	0.023 J	< 0.2 U	< 0.16 U	< 0.056 UT	0.18
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated			5.899	< 0.026 U	0.066 J	< 0.16 U	0.089 J	< 0.2 U	< 0.17 U	< 0.057 U	0.45
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated			3.528	< 0.022 U	0.11	< 0.14 U	0.078	< 0.17 U	< 0.14 U	< 0.048 U	0.3
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated			33.584	0.047 J	< 0.035 U	< 0.29 U	0.26	< 0.35 U	< 0.3 U	< 0.1 U	2.3
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated			0.945	< 0.022 U	0.024 J	< 0.13 U	0.026 J	< 0.16 U	< 0.14 U	< 0.046 U	0.075
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated			3.978	< 0.023 U	0.11	< 0.14 U	0.085	< 0.17 U	< 0.14 U	< 0.049 U	0.36
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated			1.191	< 0.022 U	< 0.017 U	< 0.021 U	0.021 J	< 0.17 U	< 0.016 U	< 0.047 U	0.096
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated			0.918	< 0.01 U	0.032 J	< 0.017 U	0.013 J	< 0.021 U	< 0.012 U	< 0.059 U	0.072
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated			0.493	< 0.0096 U	0.017 J	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	0.049
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated			0.0383	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.013 J
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated			0.7313	< 0.0099 U	0.011 J	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.072
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated			0.401	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.04
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated			1.137	< 0.01 U	0.017 J	< 0.018 U	0.027 J	< 0.021 U	< 0.013 U	< 0.06 U	0.094
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated			0.128	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.018 J
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated			0.243	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.03 J
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated			0.297	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.031 J
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated			7.497	< 0.022 U	0.13	< 0.14 U	0.21	< 0.17 U	< 0.14 U	< 0.048 U	0.66
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated			0.976	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.088
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated			4.183	< 0.024 U	0.27	< 0.15 U	0.13	< 0.18 U	< 0.15 U	< 0.052 U	0.35
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated			0.162	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 41 UJ		2.908	< 0.022 U	0.051 J	< 0.02 U	0.081 J	< 0.17 U	< 0.016 U	< 0.047 U	0.28 J
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated		1000	186.99	0.47	7.8	< 0.11 U	4.9	< 0.88 U	< 0.084 U	< 0.25 U	37
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated			4.346	0.023 J	0.19	< 0.14 U	0.13	< 0.18 U	< 0.15 U	< 0.05 U	0.38
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated			2.203	0.078 J	< 0.018 U	< 0.14 U	0.044 J	< 0.18 U	< 0.15 U	< 0.05 U	0.13
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated			4.035	< 0.025 U	< 0.019 U	< 0.16 U	0.037 J	< 0.19 U	< 0.16 U	< 0.055 U	0.31
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated			0.833	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.071 J
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated			0.861	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.071 J
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated			0.5521	< 0.01 U	0.018 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.049
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated			0.387	< 0.011 U	0.011 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	0.038 J
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated			1.788	< 0.012 U	0.037 J	< 0.021 U	0.022 J	< 0.025 U	< 0.015 U	< 0.069 U	0.14
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated			0.239	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.025 J
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated			0.1161	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.024 J
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated			0.22	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated			4.121	< 0.011 U	< 0.011 U	< 0.019 U	0.03 J	< 0.023 U	< 0.014 U	< 0.066 U	0.31
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated			2.366	< 0.01 U	0.099 J	< 0.017 U	0.036 J	< 0.021 U	< 0.012 U	< 0.058 U	0.18
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated			4.849	0.015 J	0.16 J	0.023 J	0.076 J	< 0.021 U	0.027 J	< 0.06 U	0.39
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated			1.133	< 0.011 U	0.044 J	< 0.019 U	0.018 J	< 0.023 U	< 0.013 U	< 0.063 U	0.086
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated			0.413	< 0.011 U	0.012 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.038 J
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated			1.911	< 0.012 U	0.013 J	< 0.02 U	0.024 J	< 0.024 U	< 0.014 U	< 0.068 U	0.13
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated			0.668	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.066 U	0.052
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated			0.0449	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.014 J
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated			0.275	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.03 J

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	10	13	4.4	8.6	< 0.31 U	< 0.031 U	< 0.063 U	< 0.9 U	< 0.36 U	< 0.58 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	0.051 J	0.08	0.038 J	0.043 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	0.15	0.23	0.089	0.19	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	1.4	1.7	0.68	1.2	< 0.18 U	< 0.018 U	< 0.036 U	< 0.52 U	< 0.21 U	< 0.34 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	0.049 J	0.064 J	< 0.025 U	0.039 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	3.4	4.6	1.4	2.8	< 0.16 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	0.2	0.3	0.084 J	0.17	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	0.78	1.1	0.34	0.56	< 0.17 U	< 0.017 U	< 0.034 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	0.21	0.3	0.13	0.16	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	1.3	1.7	0.54	1.2	< 0.17 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	1	1.5	0.34	0.92	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	30	39	14	25	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	0.26	0.3	0.13	0.25	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.038 J	0.052 J	< 0.024 U	0.036 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.93	1.4	0.55	0.8	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	1
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.66	0.91	0.33	0.46	< 0.19 U	< 0.019 U	< 0.038 U	< 0.55 U	< 0.22 U	< 0.35 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.097	0.13	0.066 J	0.082 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.3	0.39	0.15	0.24	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.079	0.11	0.04 J	0.069 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	190	220	100	120	< 2.3 U	< 0.22 U	< 0.46 U	< 6.6 U	< 2.6 U	< 4.3 U
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.034 U	0.025 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.043 U	0.041 J	< 0.03 U	0.04 J	< 0.18 U	< 0.018 U	< 0.037 U	< 0.53 U	< 0.21 U	< 0.34 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.071 J	0.11	0.029 J	0.075 J	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.17	0.27	0.1	0.18	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	0.17	0.28	0.086 J	0.18	< 0.16 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.19 U	< 0.3 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.24	0.39	0.094	0.27	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.063 J	0.088	0.033 J	0.067 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.079 J	0.13	0.04 J	0.081	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.041 U	0.048 J	< 0.028 U	0.035 J	< 0.17 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.23	0.32	0.13	0.18	< 0.16 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	0.55	0.71	0.35	0.48	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	0.33	0.43	0.14	0.31	< 0.14 U	< 0.024 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	3.1	4.4	1.4	3.1	< 0.3 U	< 0.05 U	< 0.06 U	< 0.86 U	< 0.34 U	< 0.56 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	0.086	0.12	0.031 J	0.072 J	< 0.14 U	< 0.023 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	0.37	0.45	0.21	0.35	< 0.14 U	< 0.024 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	0.11	0.15	0.064 J	0.078	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	0.073 T	0.13	0.046	0.046 J	< 0.028 U	< 0.012 U	< 0.0064 U	0.061 J	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	0.048 T	0.078	0.025 J	0.029 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 UT	< 0.016 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.0090 UT	0.01 J	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 UT	< 0.016 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	0.073	0.11	0.04	0.039 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	0.04 T	0.056	0.021 J	0.025 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.0094 UT	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	0.084	0.14	0.048	0.061 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	0.015 J	0.026 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	0.024 J	0.035	0.017 J	0.015 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	0.028 J	0.04	0.014 J	0.019 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	0.64	0.64	0.34	0.48	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	0.11	0.12	0.055 J	0.1	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	0.34	0.44	0.21	0.33	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.034 U	0.031 J	< 0.024 U	0.023 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	0.27 J	0.32 J	0.094 J	0.23 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	16	21	6.9	15	< 0.096 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	0.4	0.58	0.15	0.32	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	0.13	0.13	0.1	0.093	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	0.35	0.52	0.18	0.31	< 0.16 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.19 U	< 0.3 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	0.078	0.099	0.051 J	0.059 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	0.075 J	0.11	0.043 J	0.06 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	0.054 T	0.086	0.03 J	0.032 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	0.033 J	0.051	0.017 J	0.026 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	0.16	0.26	0.099	0.1 J	< 0.033 U	< 0.015 U	< 0.0076 U	< 0.022 U	< 0.017 U	< 0.02 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	0.021 J	0.033 J	0.01 J	0.014 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	0.015 J	0.021 J	0.0093 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	0.024 J	0.041	< 0.0070 U	0.015 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	0.38	0.54	0.21	0.27 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 UT	< 0.019 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	0.22	0.34	0.11	0.19 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	0.41	0.62	0.25	0.32 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	0.099	0.15	0.049	0.075 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	0.036 J	0.053	0.024 J	0.029 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	0.18	0.27	0.09	0.14 J	< 0.032 U	< 0.014 U	< 0.0075 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	0.058	0.095	0.04	0.046 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.01 U	0.012 J	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	0.026 J	0.034 J	0.016 J	0.016 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.55 U	1.1	< 0.22 U	< 0.3 U	< 0.039 U	< 0.31 U	< 0.28 U	11	2.4	0.41 J
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.057 J	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.25 U	0.02 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.24	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.32 U	0.086 J	< 0.13 U	< 0.17 U	< 0.023 U	< 0.18 U	< 0.16 U	1.6	0.25	< 0.18 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.057 J	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.29 U	0.2	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	4	0.57	< 0.17 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.3 U	< 0.022 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.24	< 0.059 U	< 0.17 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.3 U	0.047 J	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.86	0.17	< 0.17 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.25 U	0.018 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.27	0.054 J	< 0.14 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.31 U	0.18	< 0.12 U	< 0.17 U	< 0.022 U	< 0.17 U	< 0.16 U	1.6	0.33	< 0.17 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.3 U	0.11	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	1.3	0.24	< 0.17 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.3 U	2.2	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	37	8.7	0.75
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.31	0.056 J	< 0.14 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.26 U	0.12	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	1.1	0.17	< 0.15 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.33 U	0.092 J	< 0.13 U	< 0.18 U	< 0.024 U	< 0.19 U	< 0.17 U	0.77	0.14	< 0.19 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.12	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.27 U	0.024 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	0.27	0.066 J	< 0.16 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.088	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 4 U	96	< 1.6 U	< 2.2 U	< 0.28 U	< 2.3 U	< 2.1 U	240	37	100
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.32 U	< 0.023 U	< 0.13 U	< 0.17 U	< 0.023 U	< 0.18 U	< 0.16 U	< 0.055 U	< 0.063 U	< 0.18 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.081 J	< 0.056 U	< 0.16 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.3 U	< 0.022 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.23	< 0.059 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	< 0.29 U	0.027 J	< 0.12 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	0.24	< 0.056 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.28 U	0.034 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	0.3	< 0.054 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.066 J	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.12	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.31 U	< 0.022 U	< 0.12 U	< 0.17 U	< 0.022 U	< 0.17 U	< 0.16 U	< 0.052 U	< 0.06 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.29 U	< 0.021 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.25	< 0.058 U	< 0.17 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.3 U	0.051 J	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.55	0.1	< 0.17 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.25 U	0.026 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.41	0.094	< 0.14 U
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.53 U	0.34	< 0.21 U	< 0.28 U	< 0.037 U	< 0.3 U	< 0.27 U	3.5	0.62	< 0.3 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.092	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.26 U	0.026 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.45	0.084	< 0.14 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 UJ	< 0.018 U	< 0.018 U	< 0.023 U	0.12	< 0.049 U	< 0.017 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.1 J	0.016 J	< 0.012 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.052 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.047 J	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0064 J	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.078 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.044 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.11 J	0.036	< 0.012 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.021 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.033 J	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.031 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.25 U	0.12	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.62	0.16	< 0.14 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.11	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.27 U	0.038 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.46	0.091	< 0.15 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.25 U	0.029 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.24 J	0.056 J	< 0.017 UJ
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 1.3 U	1	< 0.14 U	< 0.095 U	< 0.092 U	< 0.093 U	< 0.12 U	17	3.8	0.41 J
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.26 U	0.036 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.45	0.073 J	< 0.15 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.26 U	0.026 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.18	< 0.052 U	< 0.15 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.29 U	0.032 J	< 0.12 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	0.42	0.066 J	< 0.16 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.098	< 0.049 U	< 0.14 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.087	< 0.051 U	< 0.15 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.065 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.036 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.065 U	< 0.016 U	< 0.074 U	< 0.024 U	< 0.019 U	< 0.015 U	< 0.015 U	0.21 J	0.026 J	< 0.014 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.018 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.062 UT	0.038 J	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.4	0.059	< 0.013 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.055 U	0.017 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.23 J	0.04	0.031 J
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.056 U	0.037 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.46	0.078	0.075 J
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.11 J	0.02 J	0.022 J
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.041 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.064 U	0.019 J	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	0.19 J	0.028 J	< 0.014 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.068 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.0079 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	< 0.016 U	< 0.012 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.79 U	< 0.065 U	< 0.3 U	< 0.28 U	< 0.34 U	< 0.37 U	< 0.49 U	< 1.5 U	< 0.33 U	< 5.3 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.46 U	< 0.038 U	< 0.17 U	< 0.17 U	< 0.19 U	< 0.22 U	< 0.29 U	< 0.85 U	< 0.19 U	< 3.1 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.42 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.26 U	< 0.77 U	< 0.17 U	< 2.8 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.43 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.8 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.42 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.26 U	< 0.78 U	< 0.18 U	< 2.8 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.44 U	< 0.036 U	< 0.17 U	< 0.16 U	< 0.19 U	< 0.21 U	< 0.28 U	< 0.82 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.43 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.8 U	0.93	< 2.9 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.43 U	< 0.036 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.8 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 UT	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 UT	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.48 U	< 0.039 U	< 0.18 U	< 0.17 U	< 0.2 U	< 0.22 UT	< 0.3 U	< 0.88 U	< 0.2 U	< 3.2 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 UT	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 UT	< 0.25 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 UT	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 5.8 U	< 0.48 U	< 2.2 U	< 2.1 U	< 2.5 U	< 2.7 UT	< 3.6 U	< 11 U	< 2.4 U	< 38 U
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 UT	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.46 U	< 0.038 U	< 0.17 U	< 0.17 U	< 0.2 U	< 0.22 UT	< 0.29 U	< 0.85 U	< 0.19 U	< 3.1 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 UT	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.43 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 UT	< 0.27 U	< 0.79 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 UT	< 0.26 U	< 0.76 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.39 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 UT	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 UT	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 UT	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.44 U	< 0.036 U	< 0.17 U	< 0.16 U	< 0.19 U	< 0.21 UT	< 0.27 U	< 0.81 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.42 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 UT	< 0.26 UT	< 0.78 U	< 0.18 U	< 2.8 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.43 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.79 U	< 0.18 U	< 2.8 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.43 U	< 0.81 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.75 U	< 0.062 U	< 0.28 U	< 0.27 U	< 0.9 U	< 1.7 U	< 0.47 U	< 1.4 U	< 0.32 U	< 5 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.41 U	< 0.78 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.43 U	< 0.82 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.052 UT	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 UT	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 UT	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 1.9 U	< 0.16 U	< 0.71 U	< 0.12 U	< 0.15 U	< 0.88 U	< 1.2 U	< 3.5 U	< 0.12 U	< 11 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.26 U	< 0.76 U	< 0.17 U	< 2.7 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.063 U	< 0.027 U	< 0.014 U	< 0.05 U	< 0.095 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.21 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.063 U	< 0.027 U	< 0.013 U	< 0.049 U	< 0.094 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 UT
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 UT	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 UT	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 UT	< 0.15 U	< 0.026 U	< 0.18 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.51 U		< 0.26 U		16	0.74	< 0.061 U	< 0.05 U	< 0.087 U	< 0.3 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.24 U		< 0.12 U		0.089	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.23 U		< 0.12 U		0.33	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.29 U		< 0.15 U		2.4	0.071 J	< 0.035 U	< 0.029 U	< 0.05 U	< 0.17 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.25 U		< 0.13 U		0.088	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.27 U		< 0.14 U		5.7	0.15	< 0.032 U	< 0.026 U	< 0.046 U	< 0.16 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.28 U		< 0.14 U		0.36	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.27 U		< 0.14 U		1.2	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.23 U		< 0.12 U		0.42	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.28 U		< 0.15 U		2.7	0.1	< 0.034 U	< 0.028 U	< 0.048 U	< 0.17 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.28 U		< 0.14 U		1.9	0.093	< 0.033 U	< 0.027 U	< 0.048 U	< 0.16 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.28 U		< 0.14 U		59	1.6	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.23 U		< 0.12 U		0.38	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.23 U		< 0.12 U		0.042 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.24 U		< 0.12 U		1.5	0.054 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.31 U		< 0.16 U		1.2	0.089 J	< 0.037 U	< 0.03 U	< 0.052 U	< 0.18 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.25 U		< 0.13 U		0.13	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.25 U		< 0.13 U		0.37	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.23 U		< 0.12 U		0.081	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 3.7 U		< 1.9 U		520	130	< 0.44 U	< 0.36 U	< 0.63 U	< 2.2 U
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.23 U		< 0.12 U		< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.3 U		< 0.15 U		0.03 J	< 0.019 U	< 0.036 U	< 0.029 U	< 0.051 U	< 0.18 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.26 U		< 0.14 U		0.08 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.27 U		< 0.14 U		0.25	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	< 0.26 U		< 0.14 U		0.28	0.034 J	< 0.032 U	< 0.026 U	< 0.045 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.25 U		< 0.13 U		0.36	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.24 U		< 0.13 U		0.077 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.24 U		< 0.12 U		0.14	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.28 U		< 0.15 U		0.046 J	< 0.019 U	< 0.034 U	< 0.028 U	< 0.048 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.27 U		< 0.14 U		0.31 T	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 UT	< 0.16 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.27 U		< 0.14 U		1	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.23 U		< 0.24 U		0.45	< 0.015 U	< 0.028 U	< 0.023 U	< 0.11 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.48 U		< 0.51 U		5.8	0.057 J	< 0.058 U	< 0.047 U	< 0.22 U	< 0.29 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.22 U		< 0.23 U		0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.1 U	< 0.13 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.23 U		< 0.25 U		0.52	0.018 J	< 0.028 U	< 0.023 U	< 0.11 U	< 0.14 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.058 U			< 0.12 U	0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		0.15 J	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.036 U		< 0.029 U		0.077 J	< 0.0098 U	< 0.016 UT	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 UT	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.037 U		< 0.03 U		0.11 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.037 U		< 0.03 U		0.062 J	< 0.01 U	< 0.016 UT	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.039 U		< 0.032 U		0.19 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.038 U		< 0.03 U		0.026 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		0.048 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.039 U		< 0.032 U		0.048 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.23 U		< 0.12 U		1.4	0.027 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.24 U		< 0.13 U		0.12	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.25 U		< 0.13 U		0.57	0.032 J	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.23 U		< 0.12 U		0.049 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.019 U			< 0.12 U	0.48 J	< 0.015 UJ	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.3 U	< 0.63 U			28	1	< 0.14 U	< 0.12 U	< 0.21 U	< 0.1 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.24 U	< 0.13 U			0.62	0.031 J	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.24 U		< 0.13 U		0.36	0.085	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.26 U		< 0.14 U		0.73	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.16 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.23 U		< 0.12 U		0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.24 U		< 0.12 U		0.16	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.039 U		< 0.032 U		0.083 J	< 0.011 U	< 0.017 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.043 U		< 0.035 U		0.047 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.045 U		< 0.037 U		0.24 J	< 0.012 U	< 0.02 U	< 0.0089 U	< 0.037 U	< 0.014 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		0.027 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.037 U		< 0.03 U		0.018 J	< 0.01 U	< 0.016 UT	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.038 U		< 0.031 U		0.034 J	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.043 U		< 0.035 U		0.82	< 0.012 U	< 0.019 UT	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.038 U		< 0.031 U		0.27 J	0.013 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.039 U		< 0.031 U		0.62	0.03 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.041 U		< 0.034 U		0.14 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.042 U		< 0.034 U		0.05 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.045 U		< 0.036 U		0.32 J	< 0.012 U	< 0.02 U	< 0.0088 U	< 0.036 U	< 0.014 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.043 U		< 0.035 U		0.12 J	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.039 U		< 0.032 U		0.044 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	7.2	< 0.24 U		< 0.32 U	1.2	< 0.25 U	1.5	< 0.39 U	< 0.22 U	< 0.32 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	0.14	< 0.11 U		< 0.14 U	0.044 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	0.88	< 0.14 U		< 0.18 U	0.11	< 0.14 U	0.13	< 0.22 U	< 0.13 U	< 0.18 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	2.3	< 0.13 U		< 0.17 U	0.091	< 0.13 U	0.15	< 0.2 U	< 0.11 U	< 0.17 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	0.16	< 0.13 U		< 0.17 U	< 0.022 U	< 0.14 U	< 0.018 U	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	0.49	< 0.13 U		< 0.17 U	0.032 J	< 0.13 U	0.049 J	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	0.15	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	0.95	< 0.14 U		< 0.18 U	0.063 J	< 0.14 U	0.091 J	< 0.22 U	< 0.12 U	< 0.18 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	0.73	< 0.13 U		< 0.17 U	0.076 J	< 0.14 U	0.07 J	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	19	< 0.13 U		< 0.17 U	1.1	< 0.14 U	1.5	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	0.18	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.65	< 0.11 U		< 0.15 U	0.058 J	< 0.12 U	0.058 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.4	< 0.15 U		< 0.19 U	0.039 J	< 0.15 U	0.052 J	< 0.23 U	< 0.13 U	< 0.19 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.071 J	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.21	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.057 J	< 0.11 U		< 0.14 U	0.019 J	< 0.11 U	0.043 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	110	< 1.8 U		< 2.3 U	54	< 1.8 U	100	< 2.8 U	< 1.6 U	< 2.3 U
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.049 U	< 0.14 U		< 0.19 U	< 0.024 U	< 0.15 U	< 0.019 U	< 0.23 U	< 0.13 U	< 0.18 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.06 J	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.14	< 0.13 U		< 0.17 U	0.029 J	< 0.13 U	0.027 J	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	0.15	< 0.13 U		< 0.16 U	0.029 J	< 0.13 U	0.027 J	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.2	< 0.12 U		< 0.16 U	0.024 J	< 0.12 U	0.022 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.054 J	< 0.14 U		< 0.18 U	< 0.023 U	< 0.14 U	< 0.018 U	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.069 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.047 U	< 0.14 U		< 0.18 U	< 0.023 U	< 0.14 U	< 0.018 U	< 0.21 U	< 0.12 U	< 0.18 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	0.12	< 0.13 U		< 0.17 U	0.039 J	< 0.13 U	0.04 J	< 0.21 U	< 0.11 U	< 0.17 UT
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	0.38	< 0.13 U		< 0.17 U	0.027 J	< 0.13 U	< 0.018 U	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	0.23	< 0.11 U		< 0.15 U	0.03 J	< 0.11 U	0.026 J	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	2.4	< 0.23 U		< 0.3 U	< 0.039 U	< 0.24 U	< 0.032 U	< 0.37 U	< 0.21 U	< 0.3 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	0.065 J	< 0.11 U		< 0.14 U	0.091	< 0.11 U	0.058 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	0.24	< 0.11 U		< 0.15 U	0.028 J	< 0.12 U	0.031 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	0.062 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	0.054	< 0.013 U		< 0.1 U	0.017 J	< 0.022 U	0.024 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	0.032 J	< 0.013 U		< 0.097 U	0.015 J	< 0.021 U	0.013 J	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	0.046	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0083 J	< 0.026 U	< 0.082 UT	< 0.04 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	0.031 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	0.077	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	0.024 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	0.37	< 0.11 U		< 0.14 U	0.024 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	0.089	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	0.27	< 0.12 U		< 0.16 U	0.2	< 0.12 U	0.15	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	0.2 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 UJ		0.037 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	12	< 0.58 U		< 0.1 U	0.6	< 0.59 U	0.92	< 0.92 U	< 0.51 U	< 0.098 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	0.26	< 0.12 U		< 0.15 U	0.028 J	< 0.12 U	0.029 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	0.073 J	< 0.12 U		< 0.15 U	0.038 J	< 0.12 U	0.16	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	0.23	< 0.13 U		< 0.17 U	< 0.021 U	< 0.13 U	0.032 J	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	0.049 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	0.046 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.027 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	0.038	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0071 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	0.073	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	0.17	< 0.016 U		< 0.12 U	0.034 J	< 0.026 U	0.038 J	< 0.032 U	< 0.1 U	< 0.048 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	0.054	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	0.056	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	0.32	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	0.012 J	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	0.19	< 0.013 U		< 0.1 U	0.11 J	< 0.022 U	0.097 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	0.37	< 0.013 U		< 0.1 U	0.25 J	< 0.023 U	0.22 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	0.083	< 0.014 U		< 0.11 U	0.078 J	< 0.024 U	0.072 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	0.032 J	< 0.014 U		< 0.11 U	0.02 J	< 0.024 U	0.019 J	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	0.16	< 0.015 U		< 0.12 U	0.014 J	< 0.026 U	0.014 J	< 0.032 U	< 0.098 U	< 0.048 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	0.06 T	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.044 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	0.02 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.31 U	< 0.31 U	< 0.6 U		< 0.057 U	< 0.28 U	< 1.4 U	5.4	< 0.26 U	16
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.041 J	< 0.12 U	0.12
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.16	< 0.12 U	0.33
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.18 U	< 0.18 U	< 0.35 U		< 0.033 U	< 0.16 U	< 0.79 U	0.67	< 0.15 U	2.6
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.036 J	< 0.12 U	0.087
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.16 U	< 0.17 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	1.8	< 0.14 U	6.3
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.15	< 0.14 U	0.44
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.38	< 0.14 U	1.3
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.15	< 0.12 U	0.41
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.17 U	< 0.17 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.76 U	1.6	< 0.14 U	2.8
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.17 U	< 0.17 U	< 0.33 U		< 0.031 U	< 0.15 U	< 0.75 U	1.1	< 0.14 U	2.2
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	30	< 0.14 U	63
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.13	< 0.12 U	0.5
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.028 J	< 0.12 U	0.057 J
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.59	< 0.12 U	1.4
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.19 U	< 0.19 U	< 0.36 U		< 0.035 U	< 0.17 U	< 0.82 U	0.93	< 0.16 U	1.4
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.074 J	< 0.13 U	0.17
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.19	< 0.13 U	0.48
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.046 J	< 0.11 U	0.12
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 2.3 U	< 2.3 U	< 4.3 U		< 0.42 U	< 2.1 U	< 9.9 U	850	< 1.9 U	440
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.021 J	< 0.12 U	0.028 J
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.18 U	< 0.18 U	< 0.35 U		< 0.034 U	< 0.16 U	< 0.8 U	0.035 J	< 0.15 U	0.046 J
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	0.056 J	< 0.13 U	0.11
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.14	< 0.14 U	0.37
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.23	< 0.13 U	0.37
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.18	< 0.13 U	0.42
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.072 J	< 0.12 U	0.12
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.097	< 0.12 U	0.14
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.17 U	< 0.17 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.76 U	< 0.025 U	< 0.14 U	0.045 J
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated	< 0.16 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.72 U	0.14	< 0.14 U	0.35
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	0.32	< 0.14 U	0.92
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.18	< 0.12 U	0.55
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.3 U	< 0.3 U	< 0.57 U		< 0.055 U	< 0.27 U	< 1.3 U	1.5	< 0.25 U	5.1
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.09	< 0.11 U	0.12
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.21	< 0.12 U	0.6
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.11	< 0.12 U	0.18
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.074 J	< 0.013 U	0.12 J
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	0.031 J	< 0.012 U	0.064 J
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0060 U	< 0.012 U	0.0089 J
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.055 J	< 0.013 U	0.1 J
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.024 J	< 0.013 U	0.058 J
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.13 J	< 0.013 U	0.14 J
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	0.022 J
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.041 J
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	0.021 J	< 0.013 U	0.041 J
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.75	< 0.12 U	1.2
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.064 J	< 0.12 U	0.12
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.26	< 0.13 U	0.55
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.024 J	< 0.12 U	0.035 J
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.23 J	< 0.11 U	0.39 J
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	14	< 0.61 U	29
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.26	< 0.12 U	0.64
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.37	< 0.12 U	0.27
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.25	< 0.13 U	0.6
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.058 J	< 0.12 U	0.12
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.062 J	< 0.12 U	0.12
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.033 J	< 0.013 U	0.075 J
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	0.02 J	< 0.015 U	0.046 J
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.035 U	< 0.086 U	0.093 J	< 0.015 U	0.23 J
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.011 J	< 0.013 U	0.026 J
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.0068 J	< 0.013 U	0.022 J
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.012 J	< 0.013 U	0.038 J
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	0.2 J	< 0.015 U	0.57
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.14 J	< 0.013 U	0.31 J
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.33 J	< 0.013 U	0.66
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.081 J	< 0.014 U	0.15 J
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.035 J	< 0.014 U	0.056 J
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.085 U	0.085 J	< 0.015 U	0.28 J
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.033 J	< 0.015 U	0.096 J
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	0.011 J
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	0.021 J	< 0.013 U	0.038 J

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated		< 0.34 U	< 0.35 U	< 0.3 U	< 0.28 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 0.19 U	< 0.2 U	< 0.17 U	< 0.16 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 0.19 U	< 0.2 U	< 0.16 U	< 0.16 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341-20240410	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342-20240410	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1-20240410	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.2 U	< 0.21 U	< 0.18 U	< 0.17 U
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2-20240410	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3-20240410	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4-20240410	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5-20240410	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 2.5 U	< 2.6 U	< 2.2 U	< 2.1 U
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6-20240410	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7-20240410	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.2 U	< 0.21 U	< 0.17 U	< 0.16 U
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8-20240410	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9-20240410	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A-20240410	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B-20240410	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C-20240410	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D-20240410	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B-20240410	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.19 U	< 0.2 U	< 0.16 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C-20240410	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343-20240418	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D-20240418	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 0.32 U	< 0.34 U	< 0.28 U	< 0.27 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F-20240418	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G-20240418	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-0.17-1	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3-20240112	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7-20240112	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated		< 0.087 U	< 0.84 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated		< 0.013 U	< 0.028 U	< 0.043 U	< 0.054 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated			0.584	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.051
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated			0.0183	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated			1.084	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.089
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated			0.479	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.036 J
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated			ND	< 0.38	< 0.38		< 0.38				< 0.38
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated			5.147	< 0.021 U	0.33	< 0.02 U	0.13	< 0.16 U	< 0.016 U	< 0.046 U	0.41
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated			0.161	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.019 J
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated			0.528	< 0.01 U	0.016 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.049
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated			0.132	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.02 J
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated			0.473	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.041
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated			0.055	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.015 J
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated			0.698	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.059
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated			0.416	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.043
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated			0.1374	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.02 J
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated			0.0273	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated			0.208	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	0.024 J
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.59 ft	1801479561	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.014 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	0.091 J	< 0.013 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated			0.1139	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	0.76	0.018 J
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated			ND	< 0.011 UT	< 0.011 UT	< 0.018 UT	< 0.011 UT	< 0.022 UT	< 0.013 UT	< 0.062 UT	< 0.013 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated			0.538	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.053
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated			0.785	< 0.011 U	0.017 J	< 0.018 U	0.013 J	< 0.022 U	< 0.013 U	< 0.061 U	0.067
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated			1.125	< 0.011 U	0.036 J	< 0.019 U	0.015 J	< 0.023 U	< 0.013 U	< 0.063 U	0.097
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated			1.914	< 0.023 U	0.073 J	< 0.14 U	0.056 J	< 0.18 U	< 0.15 U	< 0.05 U	0.16
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated			1.244	< 0.027 U	0.06 J	< 0.17 U	0.034 J	< 0.21 U	< 0.17 U	< 0.059 U	0.11
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated			5.957	< 0.024 U	0.052 J	< 0.15 U	0.067 J	< 0.18 UT	< 0.15 U	< 0.052 U	0.72
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated			0.568	< 0.021 U	0.065 J	< 0.02 U	0.022 J	< 0.16 U	< 0.016 U		< 0.014 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated			0.669	< 0.022 U	0.021 J	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	0.068 J
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated			2.793	< 0.022 U	0.12	< 0.021 U	0.068 J	< 0.17 U	< 0.016 U	< 0.047 U	0.26
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated			4.107	< 0.022 U	0.18	< 0.021 U	0.094	< 0.17 U	< 0.016 U	< 0.048 U	0.36
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated			98.42	0.2 J	4.6	< 0.063 U	2.6	< 0.51 U	< 0.049 U	< 0.14 U	8.8
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated			5.374	< 0.022 UJ	0.25	< 0.021 U	0.15	< 0.17 U	< 0.016 U	< 0.047 U	0.57
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated			0.721	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.067 J
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated			1.541	< 0.019 U	0.068	< 0.018 U	0.038 J	< 0.15 U	0.02 J	< 0.042 U	0.11
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated			0.095	< 0.021 U	0.017 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated			2.766	< 0.022 U	0.12	< 0.021 U	0.06 J	< 0.17 U	< 0.016 U	< 0.047 U	0.26
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated			3.401	< 0.022 U	0.17	< 0.021 U	0.088	< 0.17 U	< 0.016 U	< 0.048 U	0.33
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	53 J	53 J	5.084	0.025 J	0.28	< 0.021 U	0.14	< 0.17 U	< 0.016 U	< 0.048 U	0.45
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	180116622	Not Excavated			1.667	< 0.022 U	0.1	< 0.021 U	0.051 J	< 0.17 U	< 0.016 U	< 0.048 U	0.15
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated			10.222	< 0.022 U	0.41	< 0.02 U	0.29	< 0.16 U	< 0.016 U	< 0.047 U	0.88
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated			1.219	< 0.022 U	0.06 J	< 0.021 U	0.026 J	< 0.17 U	< 0.016 U	< 0.047 U	0.13
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated			4.99	< 0.022 U	0.31	< 0.02 U	0.16	< 0.16 U	< 0.016 U	< 0.046 U	0.4
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated			0.1643	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.02 J
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated			0.377	< 0.021 U	0.018 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.034 J
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated			2.574	< 0.034 U	< 0.0096 U	< 0.034 U	0.024 J	< 0.041 U	< 0.034 U	< 0.063 U	0.19
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated			2.409	< 0.034 U	< 0.0098 U	< 0.034 U	0.028 J	< 0.042 U	< 0.034 U	< 0.064 U	0.18
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated			0.415	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.049 U	0.044 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated			63.72	0.28 J	0.38 J	< 0.2 U	0.88	< 1.6 U	< 0.16 U	< 0.46 U	5.7
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated			1.064	< 0.022 U	0.021 J	< 0.13 U	0.023 J	< 0.17 U	< 0.14 U	< 0.047 U	0.11
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated			0.122	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 UT	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 UT	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated			0.313	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 UT	0.033 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated			0.04	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated			0.041	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated			0.06	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated			0.297	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	0.034 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated			0.088	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated			2.622	< 0.034 U	0.13	< 0.034 U	0.069 J	< 0.038 U	< 0.034 U	< 0.058 U	0.23
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated			1.093	< 0.0072 U	0.017 J	< 0.031 U	0.017 J	< 0.036 U	< 0.033 U	< 0.056 U	0.09

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	0.049	0.071	0.034 J	0.053 J	< 0.03 U	< 0.013 U	< 0.0070 U	0.057 J	< 0.015 U	0.28 J
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	0.095	0.13	0.05 J	0.064 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	0.044 J	0.041 J	0.023 J	0.042 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	0.53	0.75	0.22	0.53	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	0.02 J	0.041	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	0.05 T	0.077	0.027 J	0.028 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	0.015 JT	0.023 J	< 0.0067 U	0.018 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 UT	< 0.016 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.0091 UT	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.0095 UT	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	0.039	0.062	0.025 J	0.029 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	0.064	0.097	0.04	0.046 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	0.04	0.059	0.027 J	0.025 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	0.016 J	0.023 J	0.0074 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.011 U	0.01 J	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	0.018 J	0.026 J	0.011 J	0.012 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	0.013 J	0.019 J	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.01 UT	< 0.0097 UT	< 0.0074 UT	< 0.011 UT	< 0.029 UT	< 0.013 UT	< 0.0068 UT	< 0.02 UT	< 0.015 UT	< 0.018 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.0099 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	0.05	0.075	0.028 J	0.03 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	0.06	0.087	0.03 J	0.043 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	0.095	0.14	0.053	0.075 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.16	0.22	0.071 J	0.13	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.11	0.16	0.061 J	0.11	< 0.17 U	< 0.017 U	< 0.035 U	< 0.51 U	< 0.2 U	< 0.33 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.71	0.8	0.34	0.39	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	0.44	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	0.062 J	0.076	0.028 J	0.044 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	0.25	0.37	0.12	0.23	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	0.4	0.58	0.16	0.35	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	6.9	11	3.1	6.6	< 0.055 U	< 0.042 U	< 0.086 U	< 1.2 U	< 0.081 U	< 0.79 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	0.47	0.57	0.21	0.42	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	0.072 J	0.099	0.032 J	0.056 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	0.13	0.19	0.059 J	0.16	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U	< 0.23 U
Northern Athletic Field	SSHS-B3615	012721 08:30_SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.032 U	0.038 J	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3616	012721 08:30_SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	0.27	0.41	0.11	0.22	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	0.34	0.43	0.18	0.27	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	0.46	0.61	0.17	0.35	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	0.16	0.22	0.07 J	0.13	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.99	1.1	0.59	0.74	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.12	0.17	0.06 J	0.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	0.51	0.66	0.22	0.49	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	0.012 J	0.021 J	0.0083 J	0.012 J	< 0.026 U	< 0.012 U	< 0.0061 U	0.023 J	< 0.013 U	< 0.016 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	0.041 J	0.058 J	0.024 J	0.038 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	0.24	0.35	0.12	0.24	< 0.027 U	< 0.011 U	< 0.009 U	0.4 J	< 0.036 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	0.21	0.28	0.15	0.18	< 0.028 U	< 0.011 U	< 0.0092 U	0.13 J	< 0.037 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	0.039 J	0.053 J	0.027 J	0.042 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30_SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	4.7	6.6	2.4	3.4	< 0.18 U	< 0.14 U	< 0.28 U	< 4 U	< 0.26 U	< 2.6 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	0.082	0.11	0.05 J	0.073 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.03 U	0.033 J	< 0.021 U	0.027 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	0.035 J	0.035 J	< 0.02 U	0.033 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.03 U	0.018 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	0.035 J	0.046 J	< 0.02 U	0.028 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.029 U	0.023 J	< 0.02 U	0.016 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated	0.27	0.34	0.097	0.26	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	0.083	0.11	0.036 J	0.086	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.055 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	0.0073 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.12	< 0.053 U	< 0.15 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.052 J	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated		< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 UJ	< 0.017 U	< 0.017 U	< 0.022 U	0.47	0.14	0.031 J
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.024 J	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.051 J	< 0.016 U	0.018 J
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.021 J	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.056 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.049 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.073 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.043 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.017 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.0073 J	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.014 J	< 0.016 U	< 0.013 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.059 UT	< 0.014 UT	< 0.067 UT	< 0.021 UT	< 0.017 UT	< 0.013 UT	< 0.013 UT	< 0.0064 UT	< 0.016 UT	< 0.013 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.056 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.076 J	< 0.016 U	< 0.012 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.11 J	0.017 J	< 0.013 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.26 U	0.019 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.2	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.31 U	< 0.022 U	< 0.12 U	< 0.17 U	< 0.022 U	< 0.18 U	< 0.16 U	0.14	< 0.061 U	< 0.18 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.65	0.12	< 0.15 U
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.068 J	< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.3	0.06 J	< 0.017 U
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.25 U	0.027 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.43	0.095	0.022 J
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 0.75 U	0.74	< 0.039 U	< 0.054 U	< 0.053 U	< 0.054 U	< 0.07 U	10	1.7	0.46 J
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.25 U	0.038 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.57	0.17	0.019 J
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.083	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	0.15	0.044 J	0.04 J
Northern Athletic Field	SSHS-B3615	012721 08:30_SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3616	012721 08:30_SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.28	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.25 U	0.02 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.34	0.1	< 0.017 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.25 U	0.034 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.53	0.096	< 0.017 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.18	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.24 U	0.068 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.87	0.17	0.056 J
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.13	< 0.048 U	< 0.017 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.24 U	0.046 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.46	0.12	0.033 J
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.018 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.051 J	< 0.048 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.32 U	0.018 J	< 0.033 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25	< 0.034 U	< 0.041 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.32 U	0.029 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.23	< 0.034 U	< 0.042 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30_SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 2.4 U	1.3	< 0.12 U	< 0.18 U	< 0.17 U	< 0.17 U	< 0.23 U	6.5	1	< 0.16 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.1	< 0.048 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.042 J	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated	< 0.29 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.22	< 0.034 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	0.15	< 0.0083 U	< 0.037 U

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	0.033 J	< 0.02 UT	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 2	< 0.38	< 2
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 UT	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 UT	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 UT	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 UT	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 UT	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 UT	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 UT	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.057 UT	< 0.024 UT	< 0.012 UT	< 0.045 UT	< 0.085 UT	< 0.014 UT	< 0.02 UT	< 0.15 UT	< 0.027 UT	< 0.18 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 UT	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 UT	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.025 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 UT
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 UT
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.44 U	< 0.037 U	< 0.17 U	< 0.16 U	< 0.19 U	< 0.21 U	< 0.28 U	< 0.82 U	< 0.19 U	< 3 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 UT	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 1.1 U	< 0.089 U	< 0.41 U	< 0.072 U	< 0.042 U	< 0.51 U	< 0.67 U	< 2 U	< 0.071 U	< 3.1 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3615	012721 08:30_SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3616	012721 08:30_SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.0084 U	< 0.034 U	< 0.065 U	< 0.045 U	0.054 J	< 0.044 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.0086 U	< 0.034 U	< 0.067 U	< 0.046 U	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30_SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 3.5 U	< 0.29 U	< 1.3 U	< 0.23 U	< 0.14 U	< 1.6 U	< 2.2 U	< 6.4 U	< 0.23 U	< 10 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.18 J	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.0078 U	< 0.034 U	< 0.061 U	< 0.042 U	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.45 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.041 U		< 0.034 U		0.097 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.25 U		< 0.13 U		0.18	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.23 U		< 0.12 U		0.072 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38				< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	< 0.056 U			< 0.12 U	0.6	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		0.03 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.039 U		< 0.031 U		0.062 J	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 UT	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.039 U		< 0.031 U		0.077 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		0.022 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.038 U		< 0.031 U		0.12 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.038 U		< 0.031 U		0.071 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.037 U		< 0.03 U		0.031 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.039 U		< 0.032 U		0.035 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.041 U		< 0.033 U		0.022 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.04 UT		< 0.033 UT		< 0.013 UT	< 0.011 UT	< 0.018 UT	< 0.0080 UT	< 0.033 UT	< 0.013 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.039 U		< 0.031 U		0.086 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.04 U		< 0.032 U		0.13 J	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.041 U		< 0.034 U		0.16 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.24 U		< 0.13 U		0.33	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.28 U		< 0.15 U		0.18	< 0.019 U	< 0.034 U	< 0.028 U	< 0.049 U	< 0.17 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.25 U		< 0.13 U		0.85	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 UT	< 0.15 U
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.019 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.019 U			< 0.12 U	0.36	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.019 U			< 0.12 U	0.52	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 0.058 U			< 0.36 U	15	0.5	< 0.083 U	< 0.068 U	< 0.12 U	< 0.06 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.019 U			< 0.12 U	0.74	0.032 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.056 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.051 U			< 0.1 U	0.13	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.055 U			< 0.11 U	0.028 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.37	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.058 U			< 0.12 U	0.41	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	0.78	0.033 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.058 U	< 0.12 U			0.24	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U			1.5	0.052 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U			0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.056 U			< 0.12 U	0.57	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.036 U		< 0.029 U		0.025 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.22 U	< 0.12 U			0.058 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.034 U			< 0.048 U	0.5	< 0.034 U	< 0.0089 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.034 U			< 0.049 U	0.47	< 0.034 U	< 0.0091 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.12 U	0.073 J	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.19 U			< 1.2 U	13	0.36 J	< 0.27 U	< 0.22 U	< 0.38 U	< 0.19 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.23 U	< 0.12 U			0.16	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.21 U	< 0.11 U			0.032 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.2 U	0.14 J			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.2 U	< 0.11 U			0.051 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.21 U	< 0.11 U			0.021 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.2 U	< 0.1 U			0.022 J	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.21 U	< 0.11 U			0.022 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.2 U	< 0.1 U			0.063 J	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.2 U	< 0.1 U			0.025 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated	< 0.031 U			< 0.044 U	0.38	< 0.034 U	< 0.0083 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	0.12	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	0.041	< 0.014 U		< 0.11 U	0.011 J	< 0.024 U	0.013 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	0.055 J	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	0.075 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.067 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38		< 0.38	< 0.38	< 0.38	< 0.38	< 2	< 2	< 2
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	0.39	< 0.11 U	< 0.11 U	< 0.019 U	0.087		0.097	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	0.032 J	< 0.013 U		< 0.1 U	0.057 J	< 0.022 U	0.045 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	0.017 J	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	0.037	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	0.055	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	0.033 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.013 UT	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 UT	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.016 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	0.014 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.044 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.015 UT	< 0.014 UT		< 0.11 UT	< 0.011 UT	< 0.024 UT	< 0.0065 UT	< 0.029 UT	< 0.089 UT	< 0.043 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	0.037	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.011 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	0.05	< 0.014 U		< 0.11 U	0.011 J	< 0.023 U	0.017 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	0.09	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.016 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.1	< 0.12 U		< 0.15 U	0.039 J	< 0.12 U	0.057 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.086 J	< 0.14 U		< 0.18 U	< 0.023 U	< 0.14 U	0.027 J	< 0.22 U	< 0.12 U	< 0.18 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	0.37	< 0.12 U		< 0.16 U	0.023 J	< 0.12 U	0.13	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	0.085	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.021 J	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	0.049 J	< 0.11 U	< 0.11 U	< 0.019 U	0.024 J		0.017 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	0.2	< 0.11 U	< 0.11 U	< 0.019 U	0.032 J		0.035 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	0.29	< 0.11 U	< 0.11 U	< 0.02 U	0.086		0.078	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	5.6	< 0.33 U	< 0.34 U	< 0.059 U	0.35		0.42	< 0.53 U	< 0.29 U	< 0.056 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	0.38	< 0.11 U	< 0.11 U	< 0.019 U	0.066 J		0.062 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	0.047 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	0.1	< 0.096 U	< 0.099 U	< 0.017 U	0.18		0.13	< 0.15 U	< 0.086 U	< 0.016 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	0.2	< 0.11 U	< 0.11 U	< 0.019 U	0.035 J		0.026 J	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	0.25	< 0.11 U		< 0.02 U	0.063 J	< 0.11 U	0.053 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	0.3	< 0.11 U	< 0.11 U	< 0.02 U	0.021 J		0.03 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	0.11	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.58	< 0.11 U		< 0.019 U	0.086	< 0.11 U	0.14	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.085	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	0.39	< 0.11 U	< 0.11 U	< 0.019 U	0.11		0.11	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	0.013 J	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	0.21	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.17 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	0.16	< 0.034 U	< 0.034 U	< 0.034 U	0.026 J		0.061 J	< 0.034 U	< 0.034 U	< 0.17 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	0.039 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	3.1	< 1.1 U		< 0.19 U	< 0.18 U	< 1.1 U	< 0.15 U	< 1.7 U	< 0.95 U	< 0.18 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	0.067 J	< 0.11 U		< 0.14 U	0.019 J	< 0.11 U	0.045 J	< 0.17 U	< 0.096 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.033 U	< 0.096 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.033 U	< 0.095 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated	0.21	< 0.034 U	< 0.034 U	< 0.034 U	0.029 J		0.096	< 0.034 U	< 0.034 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	0.083	< 0.026 U	< 0.037 U	< 0.028 U	0.034 J		0.068 J	< 0.17 U	< 0.15 U	< 0.15 U

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.043 J	< 0.014 U	0.077 J
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	0.011 J
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.076 J	< 0.12 U	0.15
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.039 J	< 0.11 U	0.063 J
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38	< 2	< 0.38	< 0.38	< 0.38	< 2	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.18	< 0.11 U	0.7
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.027 J
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.03 U	< 0.074 U	0.043 J	< 0.013 U	0.064 J
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	0.018 J
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.046 J	< 0.013 U	0.068 J
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.018 J
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.046 J	< 0.013 U	0.098 J
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.017 J	< 0.013 U	0.058 J
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.019 UT	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.023 J
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	0.01 J
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.017 J	< 0.013 U	0.031 J
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	0.0099 J	< 0.014 U	0.018 J
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.021 UT	< 0.038 UT	< 0.061 UT		< 0.027 UT	< 0.031 UT	< 0.077 UT	< 0.0066 UT	< 0.014 UT	< 0.0094 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.035 J	< 0.013 U	0.077 J
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.082 J	< 0.014 U	0.13 J
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.077 J	< 0.014 U	0.18 J
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.16	< 0.12 U	0.27
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.17 U	< 0.18 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.77 U	0.066 J	< 0.14 U	0.16
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.14	< 0.13 U	0.67
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.047 J	< 0.11 U	0.1
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.13	< 0.11 U	0.41
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.17	< 0.12 U	0.58
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 0.42 U	< 0.18 U	< 0.81 U		< 0.078 U	< 0.39 U	< 1.9 U	11	< 0.35 U	15
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.21	< 0.11 U	0.82
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.035 J	< 0.11 U	0.12
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.14	< 0.1 U	0.16
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	0.029 J
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.11	< 0.12 U	0.45
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.14	< 0.12 U	0.47
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.24	< 0.12 U	0.87
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.076 J	< 0.12 U	0.28
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.82	< 0.11 U	1.5
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.058 J	< 0.11 U	0.19
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.27	< 0.11 U	0.63
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 UT		< 0.024 U	< 0.028 U	< 0.069 U	0.012 J	< 0.012 U	0.023 J
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.022 J	< 0.11 U	0.051 J
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.15 U		< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.0099 U	0.33
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.16 U		< 0.034 U	< 0.034 U	< 0.034 U	0.15	< 0.01 U	0.31
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.031 J	< 0.12 U	0.067 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 1.4 U	< 0.59 U	< 2.6 U		< 0.25 U	< 1.2 U	< 6 U	5.8	< 1.1 U	10
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.084	< 0.11 U	0.16
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.03 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.031 J	< 0.1 U	0.053 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	0.019 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.019 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.02 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	0.036 J	< 0.1 U	0.055 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.024 J
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.0092 U	0.31
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	0.14	< 0.0088 U	0.11

DRAFT

													Pyridine	**1,2,4,5-Tetrachlorobenzene**	**2,3,4,6-Tetrachlorophenol**	**2,4,5-Trichlorophenol**	**2,4,6-Trichlorophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48_0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated				< 0.38	< 0.38
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-1-2	SSHS-B4017-SUB-1-2	7/1/2021	856.80	856.80	0.00	-	1 - 2 ft	1 - 2 ft	180-123985-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated		< 0.012 UT	< 0.025 UT	< 0.038 UT	< 0.048 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A8PH6-S1	SSHS-IRM5A2-A8PH6-S1-20240112	SSHS-IRM5A2-A8PH6-S1	1/12/2024	-	--	-	854.35	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH6-S5	SSHS-IRM5A2-A8PH6-S5-20240112	SSHS-IRM5A2-A8PH6-S5	1/12/2024	-	--	-	855.29	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated		< 0.19 U	< 0.2 U	< 0.17 U	< 0.16 U
Northern Athletic Field	A8PH6-S6	SSHS-IRM5A2-A8PH6-S6-20240112	SSHS-IRM5A2-A8PH6-S6	1/12/2024	-	--	-	854.83	1 - 2 ft	1 - 2 ft	1801681231	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated		< 0.05 U	< 0.48 U	< 0.083 U	< 0.064 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.018 U
Northern Athletic Field	SSHS-B3615	012721 08:30_SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3616	012721 08:30_SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_PS-FD-39	PS-FD-39	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SS	SSHS-B406-SS	8/25/2016	855.97	856.64	0.67	-	0 - 0.17 ft	0.67-0.84 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30_SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated		< 0.16 U	< 1.6 U	< 0.27 U	< 0.2 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211212	SSHS-ISMP-S007	12/12/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated		< 0.14 U	< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-0.17-1	SSHS-B406-SUB-0.17-1	8/25/2016	855.97	856.64	0.67	-	0.17 - 1 ft	0.84-1.67 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U

DRAFT

													Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated			0.129	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.037 U	< 0.033 U	< 0.056 U	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated			1.234	< 0.0069 U	0.023 J	< 0.03 U	0.02 J	< 0.035 U	< 0.032 U	< 0.054 U	0.1
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated			5.042	0.01 J	0.13	< 0.031 U	0.11	< 0.036 U	< 0.033 U	< 0.056 U	0.4
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated			0.3491	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	0.034 J
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated			13.285	0.043 J	0.37	< 0.031 U	0.39	< 0.037 U	0.043 J	< 0.056 U	1.2
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated			29.55	0.07 J	0.62	< 0.03 U	0.79	< 0.036 U	0.14 J	< 0.055 UJ	1.4
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated			0.099	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	0.021 J
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated			7.197	0.054 J	0.54	< 0.03 U	0.37	< 0.036 U	< 0.033 U	< 0.055 U	0.57
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated			4.093	< 0.0071 U	0.12	< 0.03 U	0.09	< 0.036 U	< 0.033 U	< 0.055 UJ	0.36
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated			0.715	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.064 J
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated			24.79	< 0.034 U	0.7	< 0.034 U	0.62 J	< 1.5 U	< 0.034 U	< 0.43 U	2.1
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated			3.154	0.029 J	0.065 J	< 0.034 U	0.1	< 0.036 U	< 0.034 U	< 0.055 U	0.26

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	0.096	0.13	0.057 J	0.12	< 0.024 U	< 0.0096 U	< 0.0078 U	< 0.058 U	< 0.031 U	< 0.049 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	0.44	0.56	0.17	0.57	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	0.031 J	0.037 J	0.018 J	0.032 J	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	1.1	1.3	0.54	1.2	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	1.9	2.3	0.83	2.1	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0072 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	0.65	0.9	0.31	0.81	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	0.31	0.46	0.18	0.33	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	0.054 J	0.084	0.03 J	0.053 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	2	2.8	0.93	2.3	< 1.3 U	< 0.12 U	< 0.25 U	< 3.7 U	< 1.5 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	0.25	0.3	0.13	0.23	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.034 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0084 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.27 U	0.0097 J	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	0.12	0.032 J	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.28 U	0.035 J	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.041 U	0.4	0.11	0.056 J
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	0.037 J	0.0081 J	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.28 U	0.086	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	1.2	0.23	0.12 J
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.28 U	0.14	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	1.7	0.45	0.65
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	0.022 J	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.28 U	0.06 J	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.64	0.2	0.042 J
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.44	0.091	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.07 J	< 0.034 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 2.2 U	0.2 J	< 0.9 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.9	0.5 J	< 1.3 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.28 U	0.042 J	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24	< 0.034 U	< 0.036 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.038 U	< 0.0072 U	0.05 J	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 1.2 U	< 1.4 U	< 0.034 U	< 2 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.0074 U	< 0.034 U	< 0.058 U	< 0.04 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	0.02 J	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	0.15	< 0.0095 U	< 0.0077 U	< 0.008 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	0.62	0.022 J	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	0.037 J	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.03 U			< 0.043 U	1.9	0.072 J	< 0.008 U	< 0.0084 U	< 0.041 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	4	0.61	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.042 U	0.033 J	< 0.0095 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	0.77	0.083	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	0.6	< 0.0097 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.21 U			< 0.11 U	0.13	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 2.1 U			< 1.1 U	3.8	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.03 U			< 0.042 U	0.57	0.027 J	< 0.0079 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	0.0073 J		0.085	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	0.099	< 0.025 U	< 0.035 U	< 0.027 U	0.031 J		0.075	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	0.47	< 0.026 U	< 0.037 U	< 0.028 U	0.059 J		0.24	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	0.028 J	< 0.025 U	< 0.035 U	< 0.027 U	0.0071 J		0.015 J	< 0.16 U	< 0.15 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	0.97	< 0.026 U	< 0.037 U	< 0.028 U	0.15		0.45	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	1.8	< 0.026 U	0.056 J	< 0.028 U	0.33		0.9	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0075 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0065 U		< 0.0062 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	0.64	< 0.026 U	< 0.036 U	< 0.028 U	0.076		0.1	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	0.27	< 0.026 U	< 0.036 U	< 0.028 U	0.026 J		0.052 J	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	0.042 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	2	< 0.034 U	< 0.034 U	< 0.034 U	0.22 J		0.84	< 0.034 U	< 0.034 U	< 1.3 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	0.19	< 0.034 U	< 0.034 U	< 0.034 U	0.037 J		0.078	< 0.034 U	< 0.034 U	< 0.15 U

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.0089 U	0.024 J
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	0.075	< 0.0085 U	0.16
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	0.32	< 0.0088 U	0.6
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	0.03 J	< 0.0084 U	0.042 J
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	0.99	< 0.0089 U	1.7
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	4.1	< 0.0087 U	6.6
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	< 0.012 U	< 0.0086 U	0.023 J
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	0.36	< 0.0087 U	0.74
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	0.27	< 0.0087 U	0.64
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.068 J	< 0.11 U	0.12
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 2.4 U		< 0.034 U	< 0.034 U	< 0.034 U	1.5	< 1 U	3.5
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.0087 U	0.4

DRAFT

TABLE 6-2C
Shallow Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.039 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated							
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated							
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0041	< 0.0015	< 0.0032	< 0.0024	< 0.0026	< 0.0024	< 0.0042	< 0.0021
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0034	< 0.0012	< 0.0026	< 0.002	< 0.0022	< 0.002	< 0.0035	< 0.0018
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	0.00033 J	< 0.00041 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	0.0042 BJ	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 UT	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.021 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.021 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.023 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.021 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	0.042 B	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	0.01 J	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.021 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.024 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.022 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.023 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	0.015 J	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.022 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.024 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.025 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.024 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	0.0058 J	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0089 U	< 0.0045 U	< 0.0045 U	< 0.0045 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	0.014 JT	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.021 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.02 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.021 UT	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	0.0079 J	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	0.0075 J	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.019 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	0.011 J	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.021 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.023 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	0.014 J	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.02 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	0.014 JT	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.024 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.024 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	0.01 J	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	0.029	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.023 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.022 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	0.011 J	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.022 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated							
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated							
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0014	< 0.0026	< 0.0031	< 0.0017	< 0.0021	< 0.0025	< 0.0034	< 0.0047
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0011	< 0.0022	< 0.0025	< 0.0014	< 0.0017	< 0.0021	< 0.0028	< 0.0039
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0030 U	< 0.0043 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U	< 0.0012 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U	< 0.0011 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U	< 0.0011 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U	< 0.0040 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U	< 0.0042 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 UT	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U	< 0.0042 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U	< 0.0043 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	0.0044 J
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0048 J
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U	< 0.0029 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	< 0.004 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U	< 0.0044 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U	< 0.0041 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	0.012
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0043 J
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	0.012
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	0.0041 J
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	0.0026 J
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	0.0068
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	0.0051 J
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	0.0035 J
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	0.0057
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	0.0064
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	0.0039 J
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	0.0086
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	0.0052
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 UT
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	0.0063
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	0.0058
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0045 JT
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	0.0047 J
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	0.0067
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	0.0046 J
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	0.0026 J
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	0.0055
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	0.0036 J
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0044 J
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	0.0046 J
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 UT
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	0.0029 J
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	0.0037 J
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	0.0061 J
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0021 J
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	0.0056 J
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	0.0052 J
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	0.0099
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	0.0097

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated							
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated							
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0014	< 0.0026	< 0.0018	< 0.0032	< 0.0016	< 0.0017	< 0.0015	< 0.0024
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0012	< 0.0022	< 0.0015	< 0.0027	< 0.0013	< 0.0014	< 0.0013	< 0.002
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U	< 0.00024 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 UT	< 0.0015 U	< 0.0024 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U	< 0.00021 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0028 U	< 0.0013 U	< 0.0014 U	< 0.0013 U	< 0.0020 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 UT	< 0.0015 UT	< 0.0023 UT
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.002 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0032 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 UT	< 0.0061 UT	< 0.0061 UT	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated							
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated							
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0043	< 0.0016	< 0.0018	< 0.0014	< 0.0023	< 0.0024	< 0.0019	< 0.0021
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0035	< 0.0013	< 0.0015	< 0.0012	< 0.0019	< 0.002	< 0.0016	< 0.0017
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0017 U	< 0.0019 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U	< 0.00032 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U	< 0.00028 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 UT	< 0.00019 U	< 0.00028 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	18014361911	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0041 UT	< 0.0015 UT	< 0.0018 UT	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U	< 0.0019 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U	< 0.0026 U	< 0.0023 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U	< 0.0022 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.002 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0089 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0089 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U

DRAFT

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated								
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated								
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated								
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated								
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0016	< 0.0027	< 0.0077	< 0.0025	< 0.0027	< 0.0019	< 0.0015	< 0.0016
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0014	< 0.0023	< 0.0064	< 0.0021	< 0.0022	< 0.0016	< 0.0013	< 0.0013
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U	< 0.00030 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U	< 0.00026 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U	< 0.00026 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.0014 U	< 0.0023 U	< 0.0066 U	< 0.0022 U	< 0.0023 U	< 0.0016 U	< 0.0013 U	< 0.0013 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0075 UT	< 0.0024 U	< 0.0026 UT	< 0.0019 U	< 0.0015 UT	< 0.0015 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.011 U	< 0.0053 U	0.0059	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.013 U	< 0.0067 U	0.013	< 0.0067 U	< 0.013 U	< 0.013 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.011 U	< 0.0054 U	0.012	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.011 U	< 0.0057 U	0.02	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.011 U	< 0.0056 U	< 0.0056 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.012 U	< 0.0060 U	0.016	< 0.0060 U	< 0.012 U	< 0.012 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.013 U	< 0.0063 U	0.021	< 0.0063 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.012 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0089 U	< 0.0045 U	0.0038 J	< 0.0045 U	< 0.0089 U	< 0.0089 U	< 0.0045 U	< 0.0045 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.012 UT	< 0.0060 U	0.0051 J	< 0.0060 U	< 0.012 UT	< 0.012 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.011 UT	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 UT	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.01 U	< 0.0051 U	0.0013 J	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U	< 0.0095 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.01 U	< 0.0051 U	0.0054	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.012 U	< 0.0058 U	0.0020 J	< 0.0058 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0098 U	< 0.0049 U	0.013	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.012 UT	< 0.0061 U	0.0029 J	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.012 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.013 U	< 0.0063 U	0.0062 J	< 0.0063 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.011 U	< 0.0053 U	0.0041 J	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.011 U	< 0.0055 U	< 0.0055 U

												1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated							
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated							
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							< U
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated							0.0051 J
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							0.0023 J
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							0.0051 J
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							0.0051 J
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0016	< 0.0021	< 0.0015	< 0.0029	< 0.0027	< 0.0018	< 0.001	< 0.0016
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0013	< 0.0017	< 0.0013	< 0.0024	< 0.0022	< 0.0015	< 0.00086	< 0.0014
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U	< 0.00093 U	< 0.0015 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U	< 0.00019 U	< 0.00034 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U	< 0.00016 U	0.00054 J
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	< 0.00030 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U	< 0.00089 U	< 0.0014 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U	< 0.00092 U	< 0.0015 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 UT	< 0.0010 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U	< 0.00091 U	< 0.0014 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U	< 0.00094 U	< 0.0015 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0025 U	< 0.002 U	< 0.0031 U	< 0.0029 U	< 0.0018 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U	< 0.0026 U	< 0.0016 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U	< 0.011 U	< 0.0056 U	< 0.0056 U	< 0.0056 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0089 U	< 0.0089 U	< 0.0045 U	< 0.0045 U	< 0.0045 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0060 UT	< 0.0060 U	< 0.0060 U	< 0.012 UT	< 0.012 UT	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 UT	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 UT	< 0.012 UT	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.0059 U	< 0.0059 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U	< 0.012 U	< 0.0060 U	< 0.0060 U	< 0.0060 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.0063 U	< 0.0063 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
EHS Building	SSHS-B2SS	B-2-3-5-COMP_SSHS-B2SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 1.8 ft	0 - 1.8 ft	-	Not Excavated	0.0051 J				
EHS Building	SSHS-B3SS	B-2-3-5-COMP_SSHS-B3SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	-	-	-	-	0 - 2 ft	0 - 2 ft	-	Not Excavated	0.0051 J				
EHS Building	SSHS-B4SS	B-4-8-9-COMP_SSHS-B4SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.50	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated					
EHS Building	SSHS-B7SS	B-1-6-7-COMP_SSHS-B7SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.51	-	-	-	0 - 2 ft	0 - 2 ft	NA	Not Excavated					
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	0.0051 J				
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4-20210510	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5-20210510	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated	< 0.0044	< 0.0038		< 0.0021	< 0.0076
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated	< 0.0036	< 0.0031		< 0.0017	< 0.0063
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603-20211007	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Football Field	ISMP-S008	SSHS-ISMP-S008-20211213	SSHS-ISMP-S008	12/13/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00069 U
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78-20220322	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1-20220505	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 0.00038 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3-20220801	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1-20220819	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3-20220819	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4-20220819	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2-20220819	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5-20220819	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8-20220822	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13-20220825	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3-20220826	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0065 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2-20220829	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3-20220829	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7-20220829	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 0.0042 U	< 0.0037 UT	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17-20220829	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0019 U	< 0.0066 U
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15-20220829	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	-	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	-	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-0.17-2	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated	< 0.0015 UJ	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-0.17-2	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0075 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV-Dup-08	SSHS-IRM5-SCV-Dup-08	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV-Dup-02	SSHS-IRM5-SCV-Dup-02	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV-Dup-04	SSHS-IRM5-SCV-Dup-04	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-07	SSHS-IRM5-SCV-Dup-07	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.5-1	SSHS-IRM5-SCV6-0.5-1	3/12/2026	-	855.634	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.5-1	SSHS-IRM5-SCV7-0.5-1	3/12/2026	-	855.477	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.5-1	SSHS-IRM5-SCV8-0.5-1	3/12/2026	-	855.432	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.5-1	SSHS-IRM5-SCV9-0.5-1	3/12/2026	-	855.487	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.5-1	SSHS-IRM5-SCV11-0.5-1	3/12/2026	-	855.149	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028431	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.5-1	SSHS-IRM5-SCV13-0.5-1	3/12/2026	-	854.854	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.0056 U	< 0.011 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.5-1	SSHS-IRM5-SCV14-0.5-1	3/12/2026	-	855.217	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.5-1	SSHS-IRM5-SCV15-0.5-1	3/12/2026	-	855.093	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.5-1	SSHS-IRM5-SCV16-0.5-1	3/12/2026	-	855.294	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028441	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.5-1	SSHS-IRM5-SCV17-0.5-1	3/12/2026	-	855.109	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0045 U	< 0.0089 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.5-1	SSHS-IRM5-SCV12-0.5-1	3/12/2026	-	855.637	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.5-1	SSHS-IRM5-SCV10-0.5-1	3/12/2026	-	855.502	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.5-1	SSHS-IRM5-SCV5-0.5-1	3/12/2026	-	855.412	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.5-1	SSHS-IRM5-SCV3-0.5-1	3/12/2026	-	855.244	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028451	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.5-1	SSHS-IRM5-SCV2-0.5-1	3/12/2026	-	855.161	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.5-1	SSHS-IRM5-SCV1-0.5-1	3/12/2026	-	855.946	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.5-1	SSHS-IRM5-SCV4-0.5-1	3/12/2026	-	855.892	-	-	0.5 - 1 ft	0.5 - 1 ft	1802028461	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP14	SSHS-IRM5-SCV-DUP14	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-12	SSHS-IRM5-SCV-DUP-12	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.5-1	SSHS-IRM5-SCV27-0.5-1	3/13/2026	-	855.427	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.5-1	SSHS-IRM5-SCV26-0.5-1	3/13/2026	-	855.257	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.5-1	SSHS-IRM5-SCV25-0.5-1	3/13/2026	-	853.99	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.5-1	SSHS-IRM5-SCV24-0.5-1	3/13/2026	-	853.847	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029281	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.5-1	SSHS-IRM5-SCV23-0.5-1	3/13/2026	-	855.022	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.0059 U	< 0.012 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.5-1	SSHS-IRM5-SCV22-0.5-1	3/13/2026	-	855.457	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.0060 U	< 0.012 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.5-1	SSHS-IRM5-SCV21-0.5-1	3/13/2026	-	856.04	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.0063 U	< 0.013 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.5-1	SSHS-IRM5-SCV20-0.5-1	3/13/2026	-	855.919	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.5-1	SSHS-IRM5-SCV19-0.5-1	3/13/2026	-	855.626	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029261	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.5-1	SSHS-IRM5-SCV18-0.5-1	3/13/2026	-	855.696	-	-	0.5 - 1 ft	0.5 - 1 ft	1802029271	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	SSHS-IRM5-SCV6-1-2	3/12/2026	-	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	SSHS-IRM5-SCV7-1-2	3/12/2026	-	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	0.011 J	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.026 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.013 U	< 0.0066 U	< 0.0066 U	< 0.0066 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.021 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.02 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.019 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.023 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.021 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.021 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.021 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.02 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.023 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.027 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	0.0084 J	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.024 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.021 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.019 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.021 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.021 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.022 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.02 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.022 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.02 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.01 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.02 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.022 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.025 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U	< 0.0062 U	< 0.0062 U	< 0.0062 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.021 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.025 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.023 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	0.0067 J	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.026 UT	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 UT	< 0.00028 U	< 0.00040 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 UT	< 0.00028 U	< 0.00041 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.0045 UT	< 0.00020 UT	< 0.00022 UT	< 0.00020 UT	< 0.00034 UT	< 0.00079 UT	< 0.00021 UT	< 0.00031 U
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00027 U	< 0.00064 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	0.0079	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00069 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	0.011	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00031 U	< 0.00044 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	0.0074	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00068 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	0.0057	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 UT	< 0.00069 U	< 0.00018 UT	< 0.00027 UT
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	0.0075	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	0.11	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.0048 UT	< 0.00022 UT	< 0.00024 UT	< 0.00022 UT	< 0.00036 UT	< 0.00084 UT	< 0.00022 UT	< 0.00032 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.008 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	0.013	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.0081 U	< 0.00036 U	< 0.00040 U	< 0.00036 U	< 0.00060 U	< 0.0014 U	< 0.00038 U	< 0.00055 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.0032 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00056 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	0.088	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	0.01	< 0.00031 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	0.0084	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	0.0091
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	0.012
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0064
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	0.0081
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	0.0024 J
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	0.0061
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	0.0033 J
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	0.0077
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0042 J
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	0.0082
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	0.0046 J
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	0.014
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	0.0064
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	0.0088
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0065
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	0.0026 J
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	0.0049 J
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	0.0040 J
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	0.0076
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	0.0046 J
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	0.0071
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	0.0036 J
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	0.0048 J
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	0.0032 J
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	0.0080
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	0.0026 J
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	0.0022 J
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	0.0025 J
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	0.0027 J
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 UT	0.0042 J
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	0.011
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U	< 0.0012 UT
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U	< 0.0011 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U	< 0.0012 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U	< 0.0012 UT
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 UT
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00038 U	< 0.00093 UT
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.00014 UT	< 0.00015 UT	< 0.00041 UT	< 0.00077 UT	< 0.00034 UT	< 0.00018 UT	< 0.00036 UT	< 0.00091 UT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U	< 0.00074 UT
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U	< 0.00079 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U	< 0.0012 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U	< 0.0013 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00066 U	< 0.00030 U	< 0.00015 U	< 0.00031 U	< 0.00078 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U	< 0.0056 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0043 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.00012 U	< 0.00013 UT	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U	< 0.00079 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U	< 0.0013 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00034 U	< 0.00017 U	< 0.00036 U	< 0.00091 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.000098 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00025 U	< 0.00063 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U	< 0.0011 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U	< 0.0012 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U	< 0.0013 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.00015 UT	< 0.00016 UT	< 0.00044 UT	< 0.00081 UT	< 0.00036 UT	< 0.00019 UT	< 0.00039 UT	< 0.00096 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U	< 0.0028 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U	< 0.0043 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U	< 0.0011 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U	< 0.0012 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00074 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00065 U	< 0.0016 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00029 U	< 0.00055 U	< 0.00025 U	< 0.00012 U	< 0.00026 U	< 0.00065 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U	< 0.00065 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00034 U	< 0.00084 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U	< 0.0013 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U	< 0.0014 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U	< 0.0012 U

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00022 U	< 0.00032 U	< 0.00025 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U	< 0.00024 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.00014 UT	< 0.00027 U	< 0.00029 UT	< 0.00029 UT	< 0.00018 UT	< 0.00016 UT	< 0.00023 U	< 0.00018 UT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00024 U	< 0.00014 U	< 0.00013 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U	< 0.00024 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.000099 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.00015 UT	< 0.00028 U	< 0.00030 UT	< 0.00031 UT	< 0.00019 UT	< 0.00017 UT	< 0.00025 UT	< 0.00019 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0032 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0034 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U	< 0.00022 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00025 U	< 0.00048 U	< 0.00051 U	< 0.00052 U	< 0.00032 U	< 0.00029 U	< 0.00042 U	< 0.00032 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U	< 0.00024 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U	< 0.00027 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U

DRAFT

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.013 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.013 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.01 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.01 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.012 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U	< 0.00032 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U	< 0.00031 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U	< 0.00025 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.00030 UT	< 0.00028 UT	< 0.00020 UT	< 0.00034 UT	< 0.00022 UT	< 0.00021 UT	< 0.00016 UT	< 0.00024 UT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00018 U	< 0.00017 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00029 UT	< 0.00019 U	< 0.00018 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 UT	< 0.00029 U	< 0.00028 U	< 0.00021 U	< 0.00032 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U	< 0.00035 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 UT	< 0.00019 U	< 0.00018 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U	< 0.00035 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00022 U	< 0.00021 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 UT	< 0.00025 U	< 0.00025 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 UT	< 0.00020 U	< 0.00031 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.00032 UT	< 0.00030 UT	< 0.00021 UT	< 0.00035 UT	< 0.00023 UT	< 0.00022 UT	< 0.00017 UT	< 0.00025 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U	< 0.0025 U	< 0.0023 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 UT
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 UT
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U	< 0.00029 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U	< 0.00031 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00054 U	< 0.00051 U	< 0.00035 U	< 0.00060 U	< 0.00039 U	< 0.00038 U	< 0.00028 U	< 0.00042 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U	< 0.00035 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U	< 0.00030 U

DRAFT

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.013 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.013 U	< 0.013 U	< 0.0066 U	< 0.0066 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0093 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.011 U	< 0.0054 U	0.0012 J	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.013 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U	< 0.0095 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0099 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.011 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.01 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.01 U	< 0.01 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.011 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.012 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U	< 0.012 U	< 0.0062 U	< 0.0062 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U	< 0.0083 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0099 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0093 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0094 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U	< 0.0094 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.01 UT	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 UT	< 0.01 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U	< 0.00030 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 UT	< 0.00053 UT	< 0.00029 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 UT	< 0.00048 UT	< 0.00026 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 UT	< 0.00054 UT	< 0.00029 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U	< 0.00029 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U	< 0.00023 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.0014 UT	< 0.00023 UT	< 0.0034 U	< 0.00040 UT	< 0.00029 U	< 0.0012 UT	< 0.00041 UT	< 0.00022 UT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U	< 0.00018 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U	< 0.00019 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U	< 0.00029 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U	< 0.00032 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U	< 0.00019 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.0012 U	< 0.00020 U	0.0030 J	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U	< 0.00019 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.0020 U	< 0.00033 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U	< 0.00033 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U	< 0.00022 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00020 U	< 0.00086 U	< 0.00028 U	< 0.00015 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U	< 0.00026 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.0019 U	< 0.00031 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U	< 0.00031 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.0014 UT	< 0.00024 UT	< 0.0036 UT	< 0.00042 UT	< 0.00031 UT	< 0.0013 UT	< 0.00043 UT	< 0.00023 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U	< 0.0016 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.0024 U	< 0.00040 U	< 0.0061 U	< 0.00070 U	< 0.00052 U	< 0.0022 U	< 0.00072 U	< 0.00039 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U	< 0.00016 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U	< 0.00016 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U	< 0.00020 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U	< 0.00032 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U	< 0.00029 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U	< 0.00033 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U	< 0.00028 U

DRAFT

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.013 U	< 0.013 U	< 0.0066 U	< 0.0066 U	< 0.0066 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.011 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.0058 U	< 0.0058 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U	< 0.013 U	< 0.0067 U	< 0.0067 U	< 0.0067 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U	< 0.0098 U	< 0.0049 U	< 0.0049 U	< 0.0049 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U	< 0.012 U	< 0.0061 U	< 0.0061 U	< 0.0061 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U	< 0.0095 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.011 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U	< 0.011 U	< 0.0054 U	< 0.0054 U	< 0.0054 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.01 U	< 0.01 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U	< 0.01 U	< 0.0051 U	< 0.0051 U	< 0.0051 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U	< 0.011 U	< 0.0055 U	< 0.0055 U	< 0.0055 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U	< 0.012 U	< 0.0062 U	< 0.0062 U	< 0.0062 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U	< 0.0094 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 UT	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00025 U	< 0.00019 U	< 0.00035 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.00022 U	< 0.00032 U	0.00040 J	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00019 U	< 0.00033 U
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.00020 U	< 0.00029 U	0.00029 J	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	< 0.00030 U
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00032 U	0.00026 J	< 0.00019 U	< 0.00038 U	< 0.00025 U	< 0.00019 U	< 0.00034 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.00017 U	< 0.00025 U	0.00065 J	< 0.00015 U	< 0.00029 U	< 0.00019 U	< 0.00015 U	< 0.00026 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.00017 UT	< 0.00024 UT	< 0.00019 UT	< 0.00014 UT	< 0.00028 UT	< 0.00018 U	< 0.00014 UT	< 0.00025 UT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U	< 0.00011 U	< 0.00021 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.00015 U	< 0.00021 U	0.00018 J	< 0.00013 U	< 0.00025 U	< 0.00016 U	< 0.00012 U	< 0.00022 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U	< 0.00019 U	< 0.00034 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.00025 U	< 0.00035 U	0.00030 J	< 0.00021 U	< 0.00041 U	< 0.00027 U	< 0.00020 U	< 0.00037 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.00015 U	< 0.00021 U	0.00020 J	< 0.00012 U	< 0.00024 U	< 0.00016 U	< 0.00012 U	< 0.00022 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U	< 0.00012 U	< 0.00022 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.00025 U	< 0.00036 U	0.00036 J	< 0.00021 U	< 0.00042 U	< 0.00027 U	< 0.00021 U	< 0.00038 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00028 U	< 0.00018 U	< 0.00014 U	< 0.00025 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U	< 0.000098 U	< 0.00018 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.00020 U	< 0.00028 U	0.00031 J	< 0.00017 U	< 0.00033 U	< 0.00022 U	< 0.00017 U	< 0.00030 U
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.00022 U	< 0.00031 U	0.00066 J	< 0.00018 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U	< 0.00020 U	< 0.00035 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.00018 UT	< 0.00026 UT	< 0.00020 UT	< 0.00015 UT	< 0.00030 UT	< 0.00020 UT	< 0.00015 UT	< 0.00027 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0024 U	< 0.0016 U	< 0.00095 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	< 0.00031 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00026 U	< 0.00051 U	< 0.00033 U	< 0.00025 U	< 0.00045 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U	< 0.00010 U	< 0.00018 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.00012 U	< 0.00017 U	0.00030 J	< 0.00010 U	< 0.00020 U	< 0.00013 U	< 0.00010 U	< 0.00018 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U	< 0.00013 U	< 0.00023 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U	< 0.00020 U	< 0.00037 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00019 U	< 0.00034 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00028 U	< 0.00021 U	< 0.00038 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U	< 0.00018 U	< 0.00032 U

DRAFT

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.02			0.26
Restricted - Residential													0.9			100
Protection of Groundwater													0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]				
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	SSHS-IRM5-SCV8-1-2	3/12/2026	-	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	SSHS-IRM5-SCV9-1-2	3/12/2026	-	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.0066 U	< 0.013 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	SSHS-IRM5-SCV11-1-2	3/12/2026	-	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	SSHS-IRM5-SCV13-1-2	3/12/2026	-	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	SSHS-IRM5-SCV14-1-2	3/12/2026	-	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	SSHS-IRM5-SCV15-1-2	3/12/2026	-	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	SSHS-IRM5-SCV16-1-2	3/12/2026	-	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	SSHS-IRM5-SCV17-1-2	3/12/2026	-	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	SSHS-IRM5-SCV12-1-2	3/12/2026	-	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	SSHS-IRM5-SCV10-1-2	3/12/2026	-	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	SSHS-IRM5-SCV5-1-2	3/12/2026	-	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.0058 U	< 0.012 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	SSHS-IRM5-SCV3-1-2	3/12/2026	-	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.0067 U	< 0.013 U
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	SSHS-IRM5-SCV2-1-2	3/12/2026	-	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0049 U	< 0.0098 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	SSHS-IRM5-SCV1-1-2	3/12/2026	-	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.0061 U	< 0.012 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	SSHS-IRM5-SCV4-1-2	3/12/2026	-	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	SSHS-IRM5-SCV27-1-2	3/13/2026	-	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0095 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	SSHS-IRM5-SCV26-1-2	3/13/2026	-	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	SSHS-IRM5-SCV25-1-2	3/13/2026	-	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	SSHS-IRM5-SCV24-1-2	3/13/2026	-	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.0054 U	< 0.011 U
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	SSHS-IRM5-SCV23-1-2	3/13/2026	-	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	SSHS-IRM5-SCV22-1-2	3/13/2026	-	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	SSHS-IRM5-SCV21-1-2	3/13/2026	-	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.01 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	SSHS-IRM5-SCV20-1-2	3/13/2026	-	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.0051 U	< 0.01 U
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	SSHS-IRM5-SCV19-1-2	3/13/2026	-	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.0055 U	< 0.011 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	SSHS-IRM5-SCV18-1-2	3/13/2026	-	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.0062 U	< 0.012 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	.678 - 2.028	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	.879 - 2.486	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17-20210701	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17-20210701	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17-20210701	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17-20210701	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.0048 U	< 0.0042 U	0.0022 J	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1-20221110	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17-20221110	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated	< 0.00042 UT	< 0.00057 U	0.00038 J	< 0.00020 U	0.00038 J
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17-20221110	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated	< 0.00038 UT	< 0.00051 U	0.00027 J	< 0.00018 U	0.00027 J
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17-20221110	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated	< 0.00043 UT	< 0.00057 U	0.00034 J	< 0.00020 U	0.00034 J
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17-20221110	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17-20221110	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17-20221110	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17-20221110	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated	< 0.00032 UT	< 0.00043 UT	0.00019 JT	< 0.00015 UT	0.00019 JT
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17-20221110	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17-20221110	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated	< 0.00028 U	< 0.00038 U	0.00019 J	< 0.00013 U	0.00019 J
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17-20221110	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17-20221110	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17-20221110	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated	< 0.00028 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV-DUP23-20230411	SSHS-IRM5A2-SCV-DUP23	4/11/2023	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801549191	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26-20231120	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17-20231120	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0053 UT	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17-20231120	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated	< 0.0050 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221027	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5-20221114	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated	< 0.00048 U	< 0.00064 U	0.00023 J	< 0.00023 U	0.00023 J
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5-20221114	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5-20221114	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated	< 0.0022 U	< 0.00030 U	< 0.000096 U	< 0.00011 U	< 0.000096 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5-20221114	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated	< 0.00038 U	< 0.00051 U	0.00019 J	< 0.00018 U	0.00019 J
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5-20221115	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated	< 0.00041 U	< 0.00056 U	0.00034 J	0.00029 J	0.00063 J
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5-20221115	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5-20221115	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated	< 0.00034 UT	< 0.00046 UT	< 0.00015 UT	< 0.00016 UT	< 0.00015 UT
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84-20220303	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9-20220311	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84-20220408	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.88	1801364891	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85-20220408	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146-20220701	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202-20220701	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147-20220705	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00057 U	< 0.00077 U	< 0.00025 U	< 0.00027 U	< 0.00025 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205-20220705	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated	< 0.00023 U	< 0.00031 U	< 0.000098 U	< 0.00011 U	< 0.000098 U
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206-20220705	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated	< 0.00023 U	< 0.00031 U	< 0.000098 U	< 0.00011 U	< 0.000098 U
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207-20220705	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208-20220705	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209-20220705	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170-20220725	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220-20220725	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U

DRAFT

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	0.018	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	0.01	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	0.0097	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.0049 UT	< 0.00022 UT	< 0.00024 U	< 0.00022 UT	< 0.00036 UT	< 0.00086 UT	< 0.00023 UT	< 0.00033 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	0.0054 J	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.0078 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	0.011 J	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	0.029	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0026 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 UT	< 0.0048 U	< 0.0025 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0058 U	< 0.0021 U	< 0.0045 U	< 0.0035 U	< 0.0038 U	< 0.0034 U	< 0.0060 U	< 0.0030 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0040 U	< 0.0031 U	< 0.0034 U	< 0.0030 U	< 0.0053 U	< 0.0027 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0054 U	< 0.0020 U	< 0.0042 U	< 0.0032 U	< 0.0035 U	< 0.0032 U	< 0.0055 U	< 0.0028 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0033 U	< 0.0036 U	< 0.0033 U	< 0.0057 U	< 0.0029 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0055 U	< 0.0020 U	< 0.0042 U	< 0.0033 U	< 0.0035 U	< 0.0032 U	< 0.0056 U	< 0.0028 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 UT	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.0077 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00057 U	< 0.0013 UT	< 0.00036 U	< 0.00052 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	0.025	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.0072 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0013 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	0.0059	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00070 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.0041 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00071 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	0.0064	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.0039 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00029 U	< 0.00067 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.0038 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	0.0073 J	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U	< 0.0013 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U	< 0.00099 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00093 U	< 0.00041 U	< 0.00021 U	< 0.00044 U	< 0.0011 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.00015 UT	< 0.00017 UT	< 0.00045 U	< 0.00083 U	< 0.00037 UT	< 0.00019 UT	< 0.00039 UT	< 0.00098 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U	< 0.0013 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U	< 0.0013 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U	< 0.0011 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U	< 0.0012 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0052 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U	< 0.0044 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0024 UT	< 0.0028 U	< 0.0038 U	< 0.0054 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0031 U	< 0.0018 U	< 0.0022 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0040 U	< 0.0056 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0055 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0032 U	< 0.0019 U	< 0.0022 U	< 0.0030 U	< 0.0042 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0043 U	< 0.0025 U	< 0.0030 U	< 0.0041 UT	< 0.0057 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 UT	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U	< 0.0054 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0019 U	< 0.0037 U	< 0.0043 UT	< 0.0050 U	< 0.0029 U	< 0.0036 U	< 0.0048 U	< 0.0067 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0039 UT	< 0.0045 U	< 0.0026 U	< 0.0032 U	< 0.0043 U	< 0.0060 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.0041 UT	< 0.0046 U	< 0.0027 U	< 0.0033 U	< 0.0045 U	< 0.0063 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0043 U	< 0.0025 U	< 0.0031 U	< 0.0041 U	< 0.0058 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0019 U	< 0.0036 U	< 0.0042 U	< 0.0048 U	< 0.0028 U	< 0.0034 U	< 0.0046 U	< 0.0065 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0018 U	< 0.0035 U	< 0.0041 U	< 0.0047 U	< 0.0028 U	< 0.0034 U	< 0.0045 U	< 0.0063 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0044 U	< 0.0026 U	< 0.0031 U	< 0.0042 U	< 0.0059 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00070 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00062 U	< 0.0015 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U	< 0.0012 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U	< 0.0012 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00058 U	< 0.0014 UT
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U	< 0.0013 UT
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U	< 0.00080 UT
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00037 U	< 0.00069 U	< 0.00031 U	< 0.00016 U	< 0.00033 U	< 0.00081 UT
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00034 U	< 0.00083 UT
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.000098 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00025 U	< 0.00063 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U	< 0.0013 UT
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U	< 0.0010 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00065 U	< 0.00029 U	< 0.00015 U	< 0.00031 U	< 0.00077 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0040 U	< 0.0056 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U	< 0.0046 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.00015 UT	< 0.00029 UT	< 0.00031 UT	< 0.00031 UT	< 0.00019 UT	< 0.00018 UT	< 0.00025 UT	< 0.00019 UT
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 UT	< 0.0039 UT	< 0.0019 UT	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0020 U	< 0.0037 U	< 0.0025 U	< 0.0046 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0034 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0041 U	< 0.0020 U	< 0.0021 U	< 0.0019 U	< 0.0030 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.0023 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0031 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0024 U	< 0.0044 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0032 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.0024 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0032 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U	< 0.0029 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.00024 U	< 0.00046 U	< 0.00049 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U	< 0.00030 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U	< 0.0034 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0017 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U	< 0.00034 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U	< 0.00026 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U	< 0.00029 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.00033 UT	< 0.00031 UT	< 0.00021 UT	< 0.00036 U	< 0.00023 UT	< 0.00023 UT	< 0.00017 UT	< 0.00026 U
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.00044 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U	< 0.00035 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U	< 0.00031 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 UT
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 UT
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 UT
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 UT	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 UT	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0017 U	< 0.0019 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0061 U	< 0.0022 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0033 U	< 0.0028 U	< 0.0030 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0054 U	< 0.0020 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0030 U	< 0.0025 U	< 0.0027 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0057 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0031 U	< 0.0026 U	< 0.0028 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0059 U	< 0.0022 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0032 U	< 0.0027 U	< 0.0029 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0057 U	< 0.0021 U	< 0.0025 U	< 0.0019 U	< 0.0031 U	< 0.0032 U	< 0.0026 U	< 0.0028 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 UT	< 0.0024 U	< 0.0026 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.00052 U	< 0.00048 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U	< 0.00041 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U	< 0.00030 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U	< 0.00033 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U	< 0.00038 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00023 UT	< 0.00015 U	< 0.00015 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U	< 0.00034 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 UT	< 0.00024 U	< 0.00023 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 UT	< 0.00018 U	< 0.00018 U	< 0.00013 U	< 0.00020 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U	< 0.0026 U	< 0.0023 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U	< 0.00031 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U	< 0.00024 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00026 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.0015 UT	< 0.00024 UT	< 0.0037 UT	< 0.00043 UT	< 0.00031 U	< 0.0013 UT	< 0.00044 UT	< 0.00024 UT
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U	< 0.00032 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U	< 0.00031 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U	< 0.00026 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 UT	< 0.0014 U	< 0.0014 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 UT	< 0.0019 U	< 0.0019 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0023 U	< 0.0039 U	< 0.011 U	< 0.0036 U	< 0.0038 U	< 0.0027 U	< 0.0022 U	< 0.0022 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0021 U	< 0.0035 U	< 0.0098 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0020 U	< 0.0020 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0033 U	< 0.0035 U	< 0.0025 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0023 U	< 0.0037 U	< 0.011 U	< 0.0035 U	< 0.0036 U	< 0.0026 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0034 U	< 0.0036 U	< 0.0026 U	< 0.0021 U	< 0.0021 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0020 U	< 0.0034 U	< 0.0096 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0020 UT
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.0023 U	< 0.00038 U	< 0.0058 U	< 0.00067 U	< 0.00050 U	< 0.0021 UT	< 0.00069 UT	< 0.00038 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	0.0059	< 0.0016 UT	< 0.00051 UT	< 0.00028 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 UT	< 0.00055 UT	< 0.00030 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.0021 U	< 0.00036 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U	< 0.00035 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00056 U	< 0.00042 U	< 0.0018 U	< 0.00058 U	< 0.00031 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U	< 0.00019 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.0031 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U	< 0.00020 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U	< 0.00020 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.00095 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00020 U	< 0.00086 U	< 0.00028 U	< 0.00015 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00042 U	< 0.0018 U	< 0.00058 U	< 0.00031 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U	< 0.00025 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0010 U	< 0.00035 U	< 0.00019 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U	< 0.0016 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U

												1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U	< 0.00020 U	< 0.00036 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U	< 0.00015 U	< 0.00028 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	< 0.00031 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.00018 UT	< 0.00026 UT	< 0.00020 UT	< 0.00015 UT	< 0.00031 UT	< 0.00020 U	< 0.00015 UT	< 0.00027 UT
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U	< 0.00021 U	< 0.00037 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U	< 0.00020 U	< 0.00036 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U	< 0.00017 U	< 0.00030 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.00097 U	< 0.0015 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U	< 0.00091 U	< 0.0014 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0020 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0020 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U	< 0.00093 U	< 0.0015 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 UT	< 0.0032 UT	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0023 U	< 0.0030 U	< 0.0021 U	< 0.0041 U	< 0.0038 U	< 0.0025 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0022 U	< 0.0013 U	< 0.0021 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0038 U	< 0.0035 U	< 0.0023 U	< 0.0014 U	< 0.0022 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0033 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0039 U	< 0.0036 U	< 0.0024 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0039 U	< 0.0036 U	< 0.0023 U	< 0.0014 U	< 0.0022 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.00029 U	< 0.00041 U	0.00042 J	< 0.00024 U	< 0.00048 U	< 0.00031 U	< 0.00024 U	< 0.00043 U
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.00021 U	< 0.00031 U	0.00032 J	< 0.00018 U	< 0.00036 U	< 0.00023 U	< 0.00018 U	< 0.00032 U
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00033 U	0.00083 J	< 0.00020 U	< 0.00039 U	< 0.00025 U	< 0.00019 U	< 0.00035 U
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U	< 0.00022 U	< 0.00040 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.00024 U	< 0.00034 U	0.00027 J	< 0.00020 U	< 0.00040 U	< 0.00026 U	< 0.00020 U	< 0.00036 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U	< 0.00012 U	< 0.00022 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.00015 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00025 U	< 0.00017 U	< 0.00013 U	< 0.00023 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U	< 0.00013 U	< 0.00023 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U	< 0.000098 U	< 0.00018 U
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.00024 U	< 0.00034 U	0.00031 J	< 0.00020 U	< 0.00040 U	< 0.00026 U	< 0.00020 U	< 0.00036 U
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.00019 U	< 0.00027 U	0.00060 J	< 0.00016 U	< 0.00032 U	< 0.00021 U	< 0.00016 U	< 0.00028 U
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.00014 U	< 0.00021 U	0.00018 J	< 0.00012 U	< 0.00024 U	< 0.00016 U	< 0.00012 U	< 0.00022 U
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U	< 0.003 U	< 0.0029 U	< 0.0018 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U

												Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.02			0.26
Restricted - Residential													0.9			100
Protection of Groundwater													0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]				
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221-20220725	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222-20220725	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224-20220725	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225-20220725	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated	< 0.00035 UT	< 0.00047 UT	< 0.00015 UT	< 0.00017 UT	< 0.00015 UT
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226-20220725	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated	< 0.00047 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227-20220725	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228-20220725	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229-20220725	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309-20230824	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312-20230824	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3-20230824	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4-20230824	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5-20230824	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6-20230824	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7-20230824	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8-20230824	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9-20230824	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10-20230824	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13-20230824	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14-20230824	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22-20230824	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0049 U	< 0.0043 UT	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23-20230824	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24-20230824	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25-20230824	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27-20230824	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29-20230824	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30-20230824	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65-20230906	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1-20230922	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2-20230922	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3-20230922	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7-20230925	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1-20231025	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3-20231025	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5-20231026	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7-20231027	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9-20231027	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15-20231101	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0044 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19-20231101	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated	< 0.0052 UT	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23-20231102	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated	< 0.0050 UT	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24-20231106	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27-20231106	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated	< 0.0041 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29-20231106	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30-20231107	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333-20231208	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0049 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4-20231208	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0048 UT	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6-20231208	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0062 UT	< 0.0054 U	< 0.0027 U	< 0.0030 U	< 0.011 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7-20231208	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated	< 0.0050 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9-20231211	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0055 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0096 U
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11-20231211	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated	< 0.0058 U	< 0.0050 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13-20231212	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15-20231212	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17-20231213	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0060 U	< 0.0052 U	< 0.0026 U	< 0.0029 U	< 0.01 U
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19-20231213	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0058 U	< 0.0051 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21-20231213	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23-20231213	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N-20240410	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1-20221110	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated	< 0.00055 UT	< 0.00074 U	0.00036 J	< 0.00026 U	0.00036 J
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1-20221110	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated	< 0.00041 UT	< 0.00055 U	0.00021 J	< 0.00019 U	0.00021 J
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1-20221110	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated	< 0.00044 UT	< 0.00059 U	0.00046 J	< 0.00021 U	0.00046 J
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1-20221110	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1-20221110	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1-20221110	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1-20221110	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated	< 0.00029 U	< 0.00039 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1-20221110	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1-20221110	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated	< 0.00022 U	< 0.00030 U	0.00011 J	< 0.00011 U	0.00011 J
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1-20221110	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated	< 0.00046 U	< 0.00062 U	0.00027 J	< 0.00022 U	0.00027 J
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1-20221110	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated	< 0.00036 U	< 0.00048 U	0.00028 J	< 0.00017 U	0.00028 J
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1-20221110	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated	< 0.00027 U	< 0.00037 U	0.00016 J	< 0.00013 U	0.00016 J
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1-20231120	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0049 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1-20231120	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated	< 0.0052 UT	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-0.17-2	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25-20230412	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U

DRAFT

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 UT	< 0.0013 U	0.00043 JT	< 0.00051 UT
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.0068 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 UT	< 0.0012 U	< 0.00031 UT	< 0.00046 UT
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00090 U	< 0.00024 UT	< 0.00035 UT
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 UT	< 0.00043 UT	< 0.0010 U	< 0.00027 UT	< 0.00039 UT
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 UT	< 0.00050 UT	< 0.0012 U	< 0.00031 UT	< 0.00045 UT
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.0039 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.0029 U	< 0.00069 UT	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.0024 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 U	< 0.00042 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.0088 U	< 0.00040 U	< 0.00043 U	< 0.00040 U	< 0.00065 U	< 0.0015 U	< 0.00041 U	< 0.00060 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.0058 UT	< 0.00026 UT	< 0.00028 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	0.016	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 UT	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	0.012	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 UT	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	0.0077 JT	< 0.00033 UT	< 0.00036 UT	< 0.00033 UT	< 0.00055 UT	< 0.0013 UT	< 0.00035 UT	< 0.00050 UT
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.0048 UT	< 0.00022 UT	< 0.00024 UT	< 0.00022 UT	< 0.00036 UT	< 0.00084 UT	< 0.00022 UT	< 0.00032 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.023	< 0.0058		< 0.0058	< 0.0058	< 0.0058	< 0.012	< 0.0058
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00058 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00079 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	0.029	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00044 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.0032 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.0041 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00071 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	0.0089	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00058 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00022 U	< 0.00053 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.0028 UT	< 0.00013 UT	< 0.00014 UT	< 0.00013 U	< 0.00021 UT	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 UT	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 UT	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 UT	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.0047 UT	< 0.00021 U	< 0.00023 U	< 0.00021 UT	< 0.00035 UT	< 0.00082 U	< 0.00022 U	< 0.00032 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 UT	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 UT	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0043 UJ	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	0.0077	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 UJ	< 0.0039 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.0047 U,*	< 0.0029 U	< 0.0028 U	< 0.0035 U	< 0.0039 U	< 0.0066 U	< 0.0044 U	< 0.0049 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	0.00026 J	< 0.00028 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	0.0045 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.00024 U	< 0.00026 UT	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U	< 0.0015 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00062 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U	< 0.0014 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U	< 0.0010 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U	< 0.0012 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U	< 0.0013 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U	< 0.00079 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.000086 U	< 0.000095 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U	< 0.00056 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.000075 U	< 0.000082 U	< 0.00022 U	< 0.00041 U	< 0.00018 U	< 0.000093 U	< 0.00019 U	< 0.00048 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00065 U	< 0.00029 U	< 0.00015 U	< 0.00031 U	< 0.00076 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.00027 U	< 0.00030 U	< 0.00080 U	< 0.0015 U	< 0.00067 U	< 0.00034 U	< 0.00071 U	< 0.0018 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.00018 UT	< 0.00020 UT	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 UT	< 0.0012 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.00023 U	< 0.00025 UT	< 0.00068 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00060 U	< 0.0015 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00021 UT	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U	< 0.0013 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U	< 0.0012 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00023 UT	< 0.00025 UT	< 0.00068 U	< 0.0013 UT	< 0.00056 U	< 0.00029 U	< 0.00060 UT	< 0.0015 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.00015 UT	< 0.00016 UT	< 0.00044 UT	< 0.00081 UT	< 0.00036 UT	< 0.00019 UT	< 0.00039 UT	< 0.00096 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058			< 0.0058
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U	< 0.00066 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U	< 0.00090 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U	< 0.0013 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 UT
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U	< 0.0015 UT
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U	< 0.00065 UT
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00037 U	< 0.00069 U	< 0.00031 U	< 0.00016 U	< 0.00033 U	< 0.00081 UT
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U	< 0.00066 UT
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.000093 U	< 0.00010 U	< 0.00027 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U	< 0.00060 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U	< 0.0011 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U	< 0.0010 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.000087 UT	< 0.000095 UT	< 0.00026 U	< 0.00048 U	< 0.00021 U	< 0.00011 U	< 0.00023 UT	< 0.00056 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U	< 0.0010 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U	< 0.0011 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00019 U	< 0.00039 U	< 0.00096 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U	< 0.0012 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00050 U	< 0.00093 U	< 0.00041 U	< 0.00021 U	< 0.00044 U	< 0.0011 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00021 UT	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U	< 0.0013 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.00015 UT	< 0.00016 UT	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 UT	< 0.00094 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00015 U	< 0.00017 UT	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U	< 0.0010 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 U	< 0.00079 U	< 0.00036 U	< 0.00018 U	< 0.00038 U	< 0.00093 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U	< 0.0012 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	0.0081
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U	0.011
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00044 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U	< 0.00098 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 UJ	< 0.0023 U	< 0.0031 U	< 0.0044 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.0023 U	< 0.0036 U	< 0.0038 U	< 0.0031 U	< 0.0057 U	< 0.0018 U	< 0.0045 U	< 0.0057 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00033 U	< 0.00083 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0024 U	< 0.0032 U	< 0.0044 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.0050 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U	< 0.0042 U

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00049 U	< 0.00030 U	< 0.00027 U	< 0.00039 U	< 0.00030 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U	< 0.00027 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U	< 0.00024 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.000076 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000095 U	< 0.000087 U	< 0.00012 U	< 0.000095 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.00028 U	< 0.00052 U	< 0.00056 U	< 0.00056 U	< 0.00035 U	< 0.00032 U	< 0.00046 U	< 0.00035 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.00018 UT	< 0.00034 U	< 0.00037 UT	< 0.00037 UT	< 0.00023 UT	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.00024 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00029 U	< 0.00027 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00023 UT	< 0.00044 U	< 0.00047 UT	< 0.00047 UT	< 0.00029 UT	< 0.00027 UT	< 0.00038 UT	< 0.00029 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.00015 UT	< 0.00028 U	< 0.00030 UT	< 0.00031 UT	< 0.00019 UT	< 0.00017 UT	< 0.00025 UT	< 0.00019 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated			< 0.38	< 0.38	< 0.38	< 0.0058	< 0.0058	< 0.0058
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00010 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00023 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U	< 0.00029 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00010 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.000095 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.000088 UT	< 0.00017 U	< 0.00018 UT	< 0.00018 UT	< 0.00011 UT	< 0.00010 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.00015 UT	< 0.00028 U	< 0.00030 UT	< 0.00030 UT	< 0.00018 UT	< 0.00017 U	< 0.00024 UT	< 0.00018 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0016 U	< 0.0028 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0024 UJ	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.004 U	< 0.0043 U	< 0.003 U	< 0.0024 U	< 0.0015 U	< 0.0027 U	< 0.0021 U	< 0.0042 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U	< 0.00016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.00051 U	< 0.00048 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U	< 0.00040 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U	< 0.00036 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U	< 0.00031 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U	< 0.00035 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.00026 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.00019 U	< 0.00017 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000097 U	< 0.00015 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00018 U	< 0.00011 U	< 0.00011 U	< 0.000084 U	< 0.00013 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U	< 0.00020 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.00059 U	< 0.00055 U	< 0.00038 U	< 0.00065 UT	< 0.00042 U	< 0.00041 U	< 0.00031 U	< 0.00046 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 UT	< 0.00027 UT	< 0.00020 UT	< 0.00030 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00055 U	< 0.00036 U	< 0.00035 UT	< 0.00026 U	< 0.00039 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 UT	< 0.00022 U	< 0.00033 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 UT	< 0.00020 U	< 0.00030 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00050 UT	< 0.00046 UT	< 0.00032 UT	< 0.00055 UT	< 0.00035 UT	< 0.00035 UT	< 0.00026 UT	< 0.00039 U
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.00032 UT	< 0.00030 UT	< 0.00021 UT	< 0.00035 UT	< 0.00023 UT	< 0.00022 UT	< 0.00017 UT	< 0.00025 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated		< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 UT	< 0.00016 U	< 0.00015 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 UT	< 0.00021 U	< 0.00021 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.00049 U	< 0.00046 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U	< 0.00038 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.00027 U	< 0.00025 U	< 0.00018 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00015 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 UT	< 0.00014 U	< 0.00014 U	< 0.00010 U	< 0.00016 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 UT	< 0.00027 U	< 0.00026 U	< 0.00020 U	< 0.00030 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 UT	< 0.00024 U	< 0.00023 U	< 0.00017 U	< 0.00026 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.00019 UT	< 0.00018 UT	< 0.00012 UT	< 0.00021 UT	< 0.00013 UT	< 0.00013 UT	< 0.000098 UT	< 0.00015 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 UT	< 0.00018 U	< 0.00028 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 UT	< 0.00019 U	< 0.00029 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 UT	< 0.00017 U	< 0.00025 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 UT	< 0.00020 U	< 0.00031 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 UT	< 0.00019 U	< 0.00029 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 UT	< 0.00022 U	< 0.00033 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.00031 UT	< 0.00029 UT	< 0.00020 UT	< 0.00035 U	< 0.00022 UT	< 0.00022 UT	< 0.00016 UT	< 0.00025 U
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 UT	< 0.00017 U	< 0.00026 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 UT	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U	< 0.00025 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.00033 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U	< 0.00026 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0041 UT	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 UT
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0019 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U	< 0.0023 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.0059 U	< 0.0023 U	< 0.0037 U	< 0.0036 U	< 0.0024 U	< 0.0026 U	< 0.0032 U	< 0.0028 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00014 U	< 0.00022 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	-	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U	< 0.0019 U

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U	< 0.00037 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U	< 0.00033 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U	< 0.00025 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U	< 0.00032 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 UT	< 0.00019 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U	< 0.00029 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.00084 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U	< 0.00014 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.00072 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00015 U	< 0.00065 U	< 0.00022 U	< 0.00012 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.0011 U	< 0.00019 U	< 0.0029 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U	< 0.00018 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.0026 U	< 0.00044 U	< 0.0066 U	< 0.00077 U	< 0.00057 U	< 0.0024 U	< 0.00079 U	< 0.00043 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.0017 UT	< 0.00029 UT	< 0.0044 U	< 0.00051 U	< 0.00037 UT	< 0.0016 UT	< 0.00052 U	< 0.00028 UT
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00067 U	< 0.00036 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U	< 0.00031 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.0017 U	< 0.00029 U	0.0044 J	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.0022 UT	< 0.00037 UT	< 0.0056 U	< 0.00065 UT	< 0.00048 UT	< 0.0020 UT	< 0.00066 UT	< 0.00036 UT
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.0014 UT	< 0.00024 UT	< 0.0036 UT	< 0.00042 UT	< 0.00031 UT	< 0.0013 UT	< 0.00043 UT	< 0.00023 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.012				< 0.012	< 0.012		< 0.0058
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U	< 0.00016 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U	< 0.00022 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	0.0099	< 0.0018 UT	< 0.00058 UT	< 0.00032 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U	< 0.00029 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00065 U	< 0.00036 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U	< 0.00016 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.0031 U	< 0.00036 U	< 0.00026 U	< 0.0011 U	< 0.00036 U	< 0.00020 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00099 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U	< 0.00016 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.00090 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00019 U	< 0.00082 U	< 0.00027 U	< 0.00015 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U	< 0.00028 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U	< 0.00024 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.00084 UT	< 0.00014 UT	< 0.0021 UT	< 0.00024 UT	< 0.00018 UT	< 0.00076 UT	< 0.00025 U	< 0.00014 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U	< 0.00025 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U	< 0.00023 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U	< 0.00028 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U	< 0.00031 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.0014 UT	< 0.00023 UT	< 0.0035 UT	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U	< 0.00023 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0014 U	< 0.00045 U	< 0.00024 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U	< 0.00029 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U	< 0.00023 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U	< 0.00029 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0017 UJ	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U	< 0.00024 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.0062 U	< 0.0034 U	< 0.0087 U	< 0.0031 U	< 0.0043 U,*	< 0.0027 U	< 0.0054 U	< 0.002 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U	< 0.00020 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U

													1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68		0.47
Restricted - Residential														19	100			100		21
Protection of Groundwater														1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.00028 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U	< 0.00024 U	< 0.00043 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00028 U	< 0.00021 U	< 0.00038 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U	< 0.00016 U	< 0.00029 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 UT	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 UT	< 0.00021 U	< 0.00037 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00025 U	< 0.00016 U	< 0.00012 U	< 0.00022 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00019 U	< 0.00034 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.00010 U	< 0.00015 U	0.00013 J	< 0.000088 U	< 0.00017 U	< 0.00011 U	< 0.000087 U	< 0.00016 U
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.000090 U	< 0.00013 U	< 0.000099 U	< 0.000076 U	< 0.00015 U	< 0.000098 U	< 0.000075 U	< 0.00014 U
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.00014 U	< 0.00020 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00015 U	< 0.00012 U	< 0.00021 U
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.00033 U	< 0.00047 U	0.00055 J	< 0.00028 U	< 0.00055 U	< 0.00036 U	< 0.00027 U	< 0.00049 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.00022 UT	< 0.00031 UT	< 0.00024 UT	< 0.00018 UT	< 0.00036 UT	< 0.00024 U	< 0.00018 UT	< 0.00032 UT
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U	< 0.00023 U	< 0.00042 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00024 U	< 0.00034 U	0.00066 J	< 0.00020 U	< 0.00039 U	< 0.00026 U	< 0.00020 U	< 0.00035 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U	< 0.00018 U	< 0.00032 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00028 UT	< 0.00040 UT	< 0.00030 UT	< 0.00023 UT	< 0.00046 UT	< 0.00030 UT	< 0.00023 UT	< 0.00042 UT
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.00018 UT	< 0.00026 UT	< 0.00020 UT	< 0.00015 UT	< 0.00030 UT	< 0.00020 UT	< 0.00015 UT	< 0.00027 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.0058		< 0.38	< 0.0058	< 0.0058	< 0.0058
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00018 U	0.00017 J	< 0.00010 U	< 0.00021 U	< 0.00013 U	< 0.00010 U	< 0.00019 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00017 U	< 0.00024 U	0.00030 J	< 0.00014 U	< 0.00028 U	< 0.00018 U	< 0.00014 U	< 0.00025 U
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.00024 U	< 0.00035 U	0.00029 J	< 0.00021 U	< 0.00041 U	< 0.00027 U	< 0.00020 U	< 0.00037 U
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00019 U	< 0.00033 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U	< 0.00023 U	< 0.00041 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U	< 0.00010 U	< 0.00018 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.00015 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00025 U	< 0.00017 U	< 0.00013 U	< 0.00023 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00012 U	< 0.00018 U	0.00031 J	< 0.00011 U	< 0.00021 U	< 0.00014 U	< 0.00010 U	< 0.00019 U
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000095 U	< 0.00019 U	< 0.00012 U	< 0.000094 U	< 0.00017 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.00021 U	< 0.00030 U	0.00039 J	< 0.00018 U	< 0.00036 U	< 0.00023 U	< 0.00018 U	< 0.00032 U
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U	< 0.00016 U	< 0.00028 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.00011 UT	< 0.00015 UT	< 0.00011 UT	< 0.000089 UT	< 0.00018 UT	< 0.00011 U	< 0.000087 UT	< 0.00016 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U	< 0.00016 U	< 0.00029 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00029 U	0.00050 J	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	< 0.00031 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U	< 0.00015 U	< 0.00027 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00020 U	< 0.00029 U	0.00043 J	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	< 0.00031 U
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U	< 0.00020 U	< 0.00035 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.00018 UT	< 0.00025 UT	0.00026 JT	< 0.00015 UT	< 0.00029 UT	< 0.00019 UT	< 0.00015 UT	< 0.00026 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U	< 0.00015 U	< 0.00028 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U	< 0.00015 U	< 0.00026 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.00022 U	< 0.00032 U	0.00056 J	< 0.00019 U	< 0.00037 U	< 0.00024 U	< 0.00018 U	< 0.00033 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U	< 0.00015 U	< 0.00027 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.00096 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0018 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.0044 U	< 0.003 U	< 0.0025 U	< 0.0052 U	< 0.0055 U	< 0.0037 U	< 0.0035 U	< 0.0022 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.00016 U	< 0.00022 U	0.00020 J	< 0.00013 U	< 0.00026 U	< 0.00017 U	< 0.00013 U	0.00088
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.00097 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.00092 U	< 0.0015 U

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.02			0.26
Restricted - Residential													0.9			100
Protection of Groundwater													0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]				
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92-20240130	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96-20240130	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340-20240130	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98-20240130	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5-20221027	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated	< 0.00054 U	< 0.00073 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5-20221027	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated	< 0.00048 U	< 0.00064 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5-20221027	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5-20221103	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5-20221103	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated	< 0.00047 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221107	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1-20221114	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1-20221114	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated	< 0.00020 U	< 0.00027 U	0.000091 J	< 0.000095 U	0.000091 J
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1-20221114	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated	< 0.00017 U	< 0.00023 U	0.000075 J	< 0.000082 U	0.000075 J
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1-20221114	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated	< 0.00027 U	< 0.00036 U	0.00014 J	< 0.00013 U	0.00014 J
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5-20221114	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated	< 0.00062 U	< 0.00084 U	0.00043 J	< 0.00030 U	0.00043 J
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5-20221114	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated	< 0.00041 U	< 0.00055 U	< 0.00018 UT	< 0.00020 UT	< 0.00018 UT
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5-20221115	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated	< 0.00053 U	< 0.00072 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5-20221115	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5-20221115	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5-20221115	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated	< 0.00053 U	< 0.00071 U	< 0.00023 UT	< 0.00025 UT	< 0.00023 UT
Northern Athletic Field	SCV6-0.5-1	SSHS-IRM5A2-SCV6-0.5-1-20221115	SSHS-IRM5A2-SCV6-0.5-1	11/15/2022	-	857.18	-	857.18	0.5 - 1 ft	0.91 ft	1801479571	Not Excavated	< 0.00034 UT	< 0.00046 UT	< 0.00015 UT	< 0.00016 UT	< 0.00015 UT
Northern Athletic Field	SCV93-0.5-1	SSHS-IRM5A2-SCV93-0.5-1-20240130	SSHS-IRM5A2-SCV93-0.5-1	1/30/2024	-	856.24	-	856.24	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SCV100-0.5-1	SSHS-IRM5A2-SCV100-0.5-1-20240130	SSHS-IRM5A2-SCV100-0.5-1	1/30/2024	-	855.43	-	855.43	0.5 - 1 ft	1 ft	1801687441	Not Excavated	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.0058		< 0.0058	
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV-DUP2-20221110	SSHS-IRM5A2-SCV-DUP2	11/10/2022	-	857.63	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00023 U	< 0.00032 U	0.00017 J	< 0.00011 U	0.00017 J
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV-DUP3-20221110	SSHS-IRM5A2-SCV-DUP3	11/10/2022	-	857.23	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00032 U	< 0.00043 U	0.00019 J	< 0.00015 U	0.00019 J
Northern Athletic Field	SCV83-1-2	SSHS-IRM5A2-SCV83-1-2-20221110	SSHS-IRM5A2-SCV83-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	1.91 ft	1801477511	Not Excavated	< 0.00046 UT	< 0.00062 U	0.00035 J	< 0.00022 U	0.00035 J
Northern Athletic Field	SCV85-1-2	SSHS-IRM5A2-SCV85-1-2-20221110	SSHS-IRM5A2-SCV85-1-2	11/10/2022	-	855.47	-	855.47	1 - 2 ft	1.92 ft	1801477511	Not Excavated	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV74-1-2	SSHS-IRM5A2-SCV74-1-2-20221110	SSHS-IRM5A2-SCV74-1-2	11/10/2022	-	855.78	-	855.78	1 - 2 ft	1.96 ft	1801477511	Not Excavated	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	SCV66-1-2	SSHS-IRM5A2-SCV66-1-2-20221110	SSHS-IRM5A2-SCV66-1-2	11/10/2022	-	855.98	-	855.98	1 - 2 ft	1.72 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00031 U	< 0.000099 U	< 0.00011 U	< 0.000099 U
Northern Athletic Field	SCV67-1-2	SSHS-IRM5A2-SCV67-1-2-20221110	SSHS-IRM5A2-SCV67-1-2	11/10/2022	-	856.09	-	856.09	1 - 2 ft	1.6 ft	1801477521	Not Excavated	< 0.00029 U	< 0.00039 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	SCV68-1-2	SSHS-IRM5A2-SCV68-1-2-20221110	SSHS-IRM5A2-SCV68-1-2	11/10/2022	-	855.77	-	855.77	1 - 2 ft	1.86 ft	1801477521	Not Excavated	< 0.00024 U	< 0.00032 U	0.00016 J	< 0.00011 U	0.00016 J
Northern Athletic Field	SCV69-1-2	SSHS-IRM5A2-SCV69-1-2-20221110	SSHS-IRM5A2-SCV69-1-2	11/10/2022	-	855.69	-	855.69	1 - 2 ft	1.91 ft	1801477521	Not Excavated	< 0.00021 U	< 0.00029 U	< 0.000092 U	< 0.00010 U	< 0.000092 U
Northern Athletic Field	SCV70-1-2	SSHS-IRM5A2-SCV70-1-2-20221110	SSHS-IRM5A2-SCV70-1-2	11/10/2022	-	855.36	-	855.36	1 - 2 ft	1.82 ft	1801477521	Not Excavated	< 0.00040 U	< 0.00054 U	0.00032 J	< 0.00019 U	0.00032 J
Northern Athletic Field	SCV71-1-2	SSHS-IRM5A2-SCV71-1-2-20221110	SSHS-IRM5A2-SCV71-1-2	11/10/2022	-	855.42	-	855.42	1 - 2 ft	1.81 ft	1801477521	Not Excavated	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	SCV72-1-2	SSHS-IRM5A2-SCV72-1-2-20221110	SSHS-IRM5A2-SCV72-1-2	11/10/2022	-	856.68	-	856.68	1 - 2 ft	1.65 ft	1801477521	Not Excavated	< 0.00020 U	< 0.00027 U	< 0.000085 UT	< 0.000095 UT	< 0.000085 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV-DUP7-20221115	SSHS-IRM5A2-SCV-DUP7	11/15/2022	-	858.10	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV-DUP6-20221115	SSHS-IRM5A2-SCV-DUP6	11/15/2022	-	855.61	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	SCV21-0.5-1	SSHS-IRM5A2-SCV21-0.5-1-20221115	SSHS-IRM5A2-SCV21-0.5-1	11/15/2022	-	853.76	-	853.76	1 - 2 ft	1.51 ft	1801479561	Not Excavated	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	SCV20-0.5-1	SSHS-IRM5A2-SCV20-0.5-1-20221115	SSHS-IRM5A2-SCV20-0.5-1	11/15/2022	-	853.98	-	853.98	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00041 U	< 0.00056 U	0.00018 J	< 0.00020 U	0.00018 J
Northern Athletic Field	SCV19-0.5-1	SSHS-IRM5A2-SCV19-0.5-1-20221115	SSHS-IRM5A2-SCV19-0.5-1	11/15/2022	-	854.19	-	854.19	1 - 2 ft	1.42 ft	1801479561	Not Excavated	< 0.00039 U	< 0.00052 U	0.00022 J	< 0.00019 U	0.00022 J
Northern Athletic Field	SCV18-0.5-1	SSHS-IRM5A2-SCV18-0.5-1-20221115	SSHS-IRM5A2-SCV18-0.5-1	11/15/2022	-	854.69	-	854.69	1 - 2 ft	1.39 ft	1801479561	Not Excavated	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	SCV17-0.5-1	SSHS-IRM5A2-SCV17-0.5-1-20221115	SSHS-IRM5A2-SCV17-0.5-1	11/15/2022	-	855.27	-	855.27	1 - 2 ft	1.48 ft	1801479561	Not Excavated	< 0.00033 U	< 0.00045 U	< 0.00014 UT	< 0.00016 UT	< 0.00014 UT
Northern Athletic Field	SCV13-0.5-1	SSHS-IRM5A2-SCV13-0.5-1-20221115	SSHS-IRM5A2-SCV13-0.5-1	11/15/2022	-	856.54	-	856.54	1 - 2 ft	1.55 ft	1801479561	Not Excavated	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	SCV12-0.5-1	SSHS-IRM5A2-SCV12-0.5-1-20221115	SSHS-IRM5A2-SCV12-0.5-1	11/15/2022	-	856.41	-	856.41	1 - 2 ft	1.73 ft	1801479561	Not Excavated	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV11-0.5-1	SSHS-IRM5A2-SCV11-0.5-1-20221115	SSHS-IRM5A2-SCV11-0.5-1	11/15/2022	-	856.47	-	856.47	1 - 2 ft	1.74 ft	1801479571	Not Excavated	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	SCV7-0.5-1	SSHS-IRM5A2-SCV7-0.5-1-20221115	SSHS-IRM5A2-SCV7-0.5-1	11/15/2022	-	857.14	-	857.14	1 - 2 ft	1.05 ft	1801479571	Not Excavated	< 0.00042 U	< 0.00057 U	0.00032 J	< 0.00020 U	0.00032 J
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0047 U	< 0.0041 U		< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	FL-S223	SSHS-IRM5A2-FL-S223-20220725	SSHS-IRM5A2-FL-S223	7/25/2022	-	854.86	-	854.86	2 - 4 ft	1.87 ft	1801418881	Not Excavated	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A8PH3-S40	SSHS-IRM5A2-A8PH3-S40-20230829	SSHS-IRM5A2-A8PH3-S40	8/29/2023	-	852.12	-	850.87	4 - 6 ft	1.25 ft	1801615841	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Rear Parking Lot	PDI6-B5109	DUP-45-20230209	DUP-45	2/9/2023	852.78	852.78	0.00	-	0.17 - 2 ft	0.17 - 2 ft	1801518942	Not Excavated	< 0.0040 U	< 0.0035 UJ	< 0.0017 U	< 0.0020 U	< 0.0070 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-0-0.17	SSHS-B4170-SUB-0-0.17	9/14/2021	855.73	855.73	0.00	-	0 - 0.17 ft	0-0.17 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.0088 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE20	080319 09:30 SSHS-IRM3-PIPE20-C	SSHS-IRM3-PIPE20-C	8/2/2019	-	855.61	-	855.03	0 - 2 ft	0.58 ft	180-93641-1	Not Excavated	< 0.0022 U	< 0.0054 U		< 0.0036 U	< 0.0064 U
Tennis Courts / Main Parking Lot	ISMP-S007	SSHS-ISMP-S007-20211213	SSHS-ISMP-S007	12/13/2021	-	854.87	-	853.71	0 - 2 ft	1.16	1801311521	Not Excavated	< 0.00030 U	< 0.00040 U	0.00013 J	< 0.00014 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S5	SSHS-ISMP-WS-S5-20220809	SSHS-ISMP-WS-S5	8/9/2022	-	--	-	857.16	0 - 2 ft	0 - 2 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S6	SSHS-ISMP-WS-S6-20220809	SSHS-ISMP-WS-S6	8/9/2022	-	857.55	-	856.68	0 - 2 ft	0.87	1801426851	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S7	SSHS-ISMP-WS-S7-20220809	SSHS-ISMP-WS-S7	8/9/2022	-	856.06	-	855.42	0 - 2 ft	0.64 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S8	SSHS-ISMP-WS-S8-20220809	SSHS-ISMP-WS-S8	8/9/2022	-	856.85	-	856.62	0 - 2 ft	0.23 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S9	SSHS-ISMP-WS-S9-20220809	SSHS-ISMP-WS-S9	8/9/2022	-	857.31	-	857.07	0 - 2 ft	0.24	1801426851	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S10	SSHS-ISMP-WS-S10-20220809	SSHS-ISMP-WS-S10	8/9/2022	-	857.55	-	857.48	0 - 2 ft	0.07	1801426851	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S13	SSHS-ISMP-WS-S13-20220809	SSHS-ISMP-WS-S13	8/9/2022	-	858.45	-	857.60	0 - 2 ft	0.85 ft	1801426851	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-DUP2-20220810	SSHS-ISMP-WS-DUP2	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S14	SSHS-ISMP-WS-S14-20220810	SSHS-ISMP-WS-S14	8/10/2022	-	857.81	-	857.79	0 - 2 ft	0.02	1801427641	Not Excavated	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S15	SSHS-ISMP-WS-S15-20220810	SSHS-ISMP-WS-S15	8/10/2022	-	858.20	-	857.46	0 - 2 ft	0.74 ft	1801427641	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S16	SSHS-ISMP-WS-S16-20220810	SSHS-ISMP-WS-S16	8/10/2022	-	858.65	-	858.15	0 - 2 ft	0.5 ft	1801427641	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-S17	SSHS-ISMP-WS-S17-20220810	SSHS-ISMP-WS-S17	8/10/2022	-	858.46	-	858.12	0 - 2 ft	0.34 ft	1801427641	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B1	SSHS-ISMP-WS-B1-20220810	SSHS-ISMP-WS-B1	8/10/2022	-	856.98	-	856.44	0 - 2 ft	0.54 ft	1801427641	Not Excavated	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-WS-B2	SSHS-ISMP-WS-B2-20220810	SSHS-ISMP-WS-B2	8/10/2022	-	858.54	-	857.70	0 - 2 ft	0.84 ft	1801427641	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-DUP1-20220826	SSHS-ISMP-TR-DUP1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S1	SSHS-ISMP-TR-S1-20220826	SSHS-ISMP-TR-S1	8/26/2022	-	855.78	-	853.79	0 - 2 ft	1.99	1801436191	Not Excavated	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0019 U	< 0.0067 U

DRAFT

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	0.0079 J	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00043 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0053 U	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.0056 U	< 0.00076 U	< 0.00078 U	< 0.00063 U	< 0.0005 U	< 0.00083 U	< 0.00058 U	< 0.0005 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.0055 U	< 0.00074 U	< 0.00076 U	< 0.00062 U	< 0.00049 U	< 0.00081 U	< 0.00056 U	< 0.00049 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.0051 U	< 0.00069 U	< 0.00071 U	< 0.00058 U	< 0.00046 U	< 0.00076 U	< 0.00053 U	< 0.00046 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0044 U	< 0.00059 U	< 0.0006 U	< 0.00049 U	< 0.00039 U	< 0.00064 U	< 0.00045 U	< 0.00039 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.0053 U	< 0.00072 U	< 0.00073 U	< 0.0006 U	< 0.00047 U	< 0.00079 U	< 0.00055 U	< 0.00048 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.0052 U	< 0.0007 U	< 0.00071 U	< 0.00058 U	< 0.00046 U	< 0.00076 U	< 0.00053 U	< 0.00046 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0046 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.005 U	< 0.00067 U	< 0.00068 U	< 0.00056 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.0005 U	< 0.0004 U	< 0.00066 U	< 0.00046 U	< 0.0004 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**	**Dichloromethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00086 U	< 0.0008 U	< 0.0017 U	< 0.00066 U	< 0.00096 U	< 0.00042 U	< 0.00085 U	< 0.00076 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00083 U	< 0.00078 U	< 0.0017 U	< 0.00064 U	< 0.00093 U	< 0.00041 U	< 0.00082 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00078 U	< 0.00073 U	< 0.0016 U	< 0.0006 U	< 0.00088 U	< 0.00038 U	< 0.00077 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00062 U	< 0.0014 U	< 0.00051 U	< 0.00074 U	< 0.00032 U	< 0.00065 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00081 U	< 0.00076 U	< 0.0017 U	< 0.00062 U	< 0.00091 U	< 0.0004 U	< 0.0008 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00078 U	< 0.00073 U	< 0.0016 U	< 0.0006 U	< 0.00088 U	< 0.00038 U	< 0.00077 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0007 U	< 0.00066 U	< 0.0014 U	< 0.00054 U	< 0.00079 U	< 0.00034 U	< 0.00069 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00052 U	< 0.00076 U	< 0.00033 U	< 0.00067 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U

DRAFT

													1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential															100	49	13	26	3.1	100
Protection of Groundwater															1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U	< 0.00083 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U	< 0.0009 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00097 U	< 0.00075 U	< 0.0009 U	< 0.00074 U	< 0.00072 U	< 0.00065 U	< 0.00069 U	< 0.00096 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00095 U	< 0.00073 U	< 0.00088 U	< 0.00072 U	< 0.0007 U	< 0.00063 U	< 0.00067 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00089 U	< 0.00068 U	< 0.00082 U	< 0.00067 U	< 0.00066 U	< 0.00059 U	< 0.00063 U	< 0.00087 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00075 U	< 0.00058 U	< 0.0007 U	< 0.00057 U	< 0.00056 U	< 0.0005 U	< 0.00053 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00092 U	< 0.00071 U	< 0.00085 U	< 0.0007 U	< 0.00068 U	< 0.00061 U	< 0.00065 U	< 0.00091 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00089 U	< 0.00069 U	< 0.00082 U	< 0.00068 U	< 0.00066 U	< 0.00059 U	< 0.00063 U	< 0.00087 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00053 U	< 0.00057 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00086 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00077 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U	< 0.00076 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

													1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.25	0.19				1	
Restricted - Residential														100	100				41	
Protection of Groundwater														0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated		< 0.00068 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U	< 0.00063 U	< 0.001 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U	< 0.00068 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated		< 0.00079 U	< 0.00067 U	< 0.00061 U	< 0.00077 U	< 0.00068 U	< 0.00073 U	< 0.0012 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated		< 0.00077 U	< 0.00065 U	< 0.0006 U	< 0.00074 U	< 0.00066 U	< 0.00071 U	< 0.0012 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated		< 0.00072 U	< 0.00061 U	< 0.00056 U	< 0.0007 U	< 0.00061 U	< 0.00066 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated		< 0.00061 U	< 0.00052 U	< 0.00047 U	< 0.00059 U	< 0.00052 U	< 0.00056 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated		< 0.00075 U	< 0.00064 U	< 0.00058 U	< 0.00072 U	< 0.00064 U	< 0.00069 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated		< 0.00072 U	< 0.00061 U	< 0.00056 U	< 0.0007 U	< 0.00062 U	< 0.00066 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00063 U	< 0.00055 U	< 0.0006 U	< 0.00099 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated		< 0.0007 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U	< 0.00064 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated		< 0.00063 U	< 0.00053 U	< 0.00049 U	< 0.00061 U	< 0.00054 U	< 0.00058 U	< 0.00096 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.034 U

DRAFT

													2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.12		0.93	
Restricted - Residential																	100		100	
Protection of Groundwater																	0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00078 U	< 0.00077 U	< 0.001 U	< 0.00082 U	< 0.001 U	< 0.00074 U	< 0.00084 U	< 0.0008 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00076 U	< 0.00074 U	< 0.00099 U	< 0.0008 U	< 0.00097 U	< 0.00072 U	< 0.00082 U	< 0.00077 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.0007 U	< 0.00093 U	< 0.00075 U	< 0.00091 U	< 0.00067 U	< 0.00077 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0006 U	< 0.00059 U	< 0.00079 U	< 0.00063 U	< 0.00077 U	< 0.00057 U	< 0.00065 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00074 U	< 0.00072 U	< 0.00096 U	< 0.00077 U	< 0.00094 U	< 0.0007 U	< 0.0008 U	< 0.00075 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00071 U	< 0.0007 U	< 0.00093 U	< 0.00075 U	< 0.00091 U	< 0.00067 U	< 0.00077 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.00063 U	< 0.00083 U	< 0.00067 U	< 0.00082 U	< 0.0006 U	< 0.00069 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00072 U	< 0.00087 U	< 0.00065 U	< 0.00074 U	< 0.0007 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.00061 U	< 0.00081 U	< 0.00065 U	< 0.00079 U	< 0.00059 U	< 0.00067 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U

DRAFT

													1,1,2,2-Tetrachloroethane	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**	**1,1,2-Trichloroethane**	**Trichloroethene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68		0.47
Restricted - Residential														19	100			100		21
Protection of Groundwater														1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U	< 0.00047 U	< 0.00081 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.00089 U	< 0.00093 U	< 0.00051 U	< 0.00088 U	0.0008 J
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00081 U	< 0.00077 U	< 0.00082 U	< 0.00095 U	< 0.001 U	< 0.00055 U	< 0.00094 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00079 U	< 0.00075 U	< 0.0008 U	< 0.00093 U	< 0.00097 U	< 0.00053 U	< 0.00091 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.0007 U	< 0.00075 U	< 0.00087 U	< 0.00091 U	< 0.0005 U	< 0.00085 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.00059 U	< 0.00064 U	< 0.00074 U	< 0.00077 U	< 0.00042 U	< 0.00072 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00077 U	< 0.00073 U	< 0.00078 U	< 0.0009 U	< 0.00094 U	< 0.00052 U	< 0.00089 U	< 0.0007 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00074 U	< 0.0007 U	< 0.00075 U	< 0.00087 U	< 0.00091 U	< 0.0005 U	< 0.00086 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00078 U	< 0.00082 U	< 0.00045 U	< 0.00077 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00084 U	< 0.00087 U	< 0.00048 U	< 0.00082 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.00061 U	< 0.00065 U	< 0.00076 U	< 0.00079 U	< 0.00044 U	< 0.00075 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 UJ	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-2D
Shallow Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Trichlorofluoromethane	**Vinyl chloride**	**Xylene (m)**	**Xylene (o)**	**Xylenes (Total)**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)RA	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00089 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-0.17-2 (1.5)	SSHS-B82-0.17-2 (1.5)	8/13/2014	856.60	856.60	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-0.17-2 (1)	SSHS-B85-0.17-2 (1)	8/13/2014	855.54	855.54	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.00088 U	
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-0.17-2 (1.5)	SSHS-B86-0.17-2 (1.5)	8/13/2014	854.20	854.20	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00052 U	< 0.0016 U	< 0.00085 U	
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-0.17-2 (1)	SSHS-B88-0.17-2 (1)	8/13/2014	855.00	855.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35776-1	Not Excavated	< 0.00094 U	< 0.00048 U	< 0.0015 U	< 0.0008 U	
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-0.17-2 (1)	SSHS-B89-0.17-2 (1)	8/13/2014	853.90	853.90	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35776-1	Not Excavated	< 0.0008 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-0.17-2 (1.5)	SSHS-B78-0.17-2 (1.5)	8/14/2014	855.75	855.75	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-2	Not Excavated	< 0.00098 U	< 0.0005 U	< 0.0016 U	< 0.00083 U	
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-0.17-2 (1.5)	SSHS-B81-0.17-2 (1.5)	8/14/2014	855.92	855.92	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00095 U	< 0.00048 U	< 0.0015 U	< 0.0008 U	
Tennis Courts / Main Parking Lot	SSHS-B83	081514 01:15_SSHS-B83-0.17-2 (1)	SSHS-B83-0.17-2 (1)	8/14/2014	854.77	854.77	0.00	-	0.17 - 2 ft	0.17 - 2 ft	180-35818-1	Not Excavated	< 0.00085 U	< 0.00043 U	< 0.0014 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-0.17-2 (1)	SSHS-B84-0.17-2 (1)	8/14/2014	856.00	856.00	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00091 U	< 0.00047 U	< 0.0015 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-0.17-2 (1.5)	SSHS-B87-0.17-2 (1.5)	8/14/2014	855.86	855.86	0.00	-	0.17 - 2 ft	0.17-2 ft	180-35818-1	Not Excavated	< 0.00082 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-0.17-2	SSHS-B4170-SUB-0.17-2	9/14/2021	855.73	855.73	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-0.17-2	SSHS-B4168-SUB-0.17-2	9/15/2021	855.97	855.97	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated			< 20 U						
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 800 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 780 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 790 U							
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 820 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	0.067 J	< 0.20 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 780 U							
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 790 U							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 800 U							
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 770 U							
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated		< 780 U							
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 760 U							
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 760 U		< 0.20 U	< 0.20 U	0.18 J	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 820 U							
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated		< 810 U							
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 800 U							
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 800 U							
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 800 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	0.059 J	< 0.20 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated		< 32 U							
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477512	Not Excavated				< 0.050 U	< 0.039 U	0.42	0.082 J	0.18 J	0.060 J
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 810 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	0.066 J	< 0.19 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 810 U							
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated		< 780 U							
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 770 U		< 0.20 U	< 0.20 U	0.099 J	< 0.20 U	0.059 J	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated		< 780 U							
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 780 U							
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 800 U							
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 780 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 800 U							
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 820 U							
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 810 U							
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated		< 790 U							
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 820 U		< 0.20 U	< 0.20 U	< 0.40 U	< 0.20 U	0.082 J	< 0.20 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 810 U							
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 810 U							
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated		< 810 U							
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated		< 770 U		< 0.20 U	< 0.20 U	< 0.40 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 110 U								
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated	< 110 U								
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated			< 120						
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated			< 110						
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated	< 120 UT								
Football Field	ISMP-S008	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated	< 120 U								
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated	< 580 U								
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated		< 31 U							
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432572	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	0.17 J	< 0.046 U	< 0.029 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432982	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	0.072 J	< 0.053 U	< 0.033 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435312	Not Excavated				< 0.050 UHT	< 0.040 UHT	< 0.048 UHT	< 0.054 UHT	< 0.050 UHT	< 0.031 UHT
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated	< 110 U								
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated		< 720 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated		< 720 U							
Football Field	SSHS-B645A	DUP-01	4/18/2021	-	856.71	-	856.02	0.17 - 1 ft	0.69 ft	180-120245-1	Not Excavated			< 110 U						

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated									
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	0.42	0.11 J	< 0.19 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.40	< 0.15 U	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.47	0.11 J	< 0.20 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.13 J	< 0.20 U	< 0.20 U	0.45	0.20	0.10 J
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.42	0.11 J	< 0.20 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477512	Not Excavated	< 0.051 U	0.13 J	< 0.030 U	0.10 J	0.18 J	< 0.034 U	0.77	0.26	0.076 J
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	0.49	0.19	< 0.19 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.38	< 0.20 U	< 0.20 U	0.40	0.17 J	0.21
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	0.30	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.63	0.18 J	< 0.20 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.28	0.093 J	< 0.20 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated									
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated									
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated									
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated									
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated									
Football Field	ISMP-S008	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated									
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated									
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated									
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated									
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated									
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432572	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.16 J	< 0.051 U	< 0.040 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated									
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated									
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated									
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated									
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432982	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	0.093 J	< 0.059 U	< 0.046 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated									
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435312	Not Excavated	< 0.051 UHT	< 0.040 UHT	< 0.030 UHT	< 0.032 UHT	< 0.023 UHT	< 0.034 UHT	< 0.045 UHT	< 0.055 UHT	< 0.043 UHT
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated									
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated									
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated									
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated									
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated									
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated									
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated									
Football Field	SSHS-B645A	DUP-01	4/18/2021	-	856.71	-	856.02	0.17 - 1 ft	0.69 ft	180-120245-1	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	SSHS-B2026	SSHS-B2026-SS	7/28/2018	855.26	855.47	0.21	-	0 - 0.17 ft	0.21-0.38 ft	180-80275-1	Not Excavated						
Football Field	IRM5-SCV10	SSHS-IRM5-SCV-Dup-05	3/12/2026	855.502	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV-Dup-03	3/12/2026	855.217	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-09	3/12/2026	855.892	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV5	SSHS-IRM5-SCV-Dup-06	3/12/2026	855.412	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0-0.17	3/12/2026	855.634	855.634	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0-0.17	3/12/2026	855.477	855.477	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0-0.17	3/12/2026	855.432	855.432	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0-0.17	3/12/2026	855.487	855.487	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0-0.17	3/12/2026	855.149	855.149	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0-0.17	3/12/2026	854.854	854.854	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0-0.17	3/12/2026	855.217	855.217	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0-0.17	3/12/2026	855.093	855.093	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0-0.17	3/12/2026	855.294	855.294	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0-0.17	3/12/2026	855.109	855.109	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0-0.17	3/12/2026	855.637	855.637	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0-0.17	3/12/2026	855.502	855.502	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV82-0-0.17	SSHS-IRM5A2-SCV82-0-0.17	11/10/2022	-	856.41	-	856.21	0 - 0.17 ft	0.40 ft	1801477512	Not Excavated	< 0.038 U	0.031 J	0.10 J	< 0.036 U	< 0.028 U	< 0.024 U
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0-0.17	3/12/2026	855.412	855.412	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0-0.17	3/12/2026	855.244	855.244	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0-0.17	3/12/2026	855.161	855.161	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0-0.17	3/12/2026	855.946	855.946	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0-0.17	3/12/2026	855.892	855.892	-	-	0 - 0.17 ft	0 - 0.17 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV24	SSHS-IRM5-SCV-DUP-13	3/13/2026	853.847	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV26	SSHS-IRM5-SCV-DUP-11	3/13/2026	855.257	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0-0.17	3/13/2026	855.427	855.427	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0-0.17	3/13/2026	855.257	855.257	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0-0.17	3/13/2026	853.99	853.99	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0-0.17	3/13/2026	853.847	853.847	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0-0.17	3/13/2026	855.022	855.022	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0-0.17	3/13/2026	855.457	855.457	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0-0.17	3/13/2026	856.04	856.04	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0-0.17	3/13/2026	855.919	855.919	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0-0.17	3/13/2026	855.626	855.626	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0-0.17	3/13/2026	855.696	855.696	-	-	0 - 0.17 ft	0 - 0.17 ft	1802029271	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	ISMP-FH BOT 4	SSHS-ISMP-FH BOT 4	5/10/2021	-	--	-	856.78	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated						
Football Field	ISMP-FH BOT 5	SSHS-ISMP-FH BOT 5	5/10/2021	-	--	-	854.60	0 - 2 ft	0 - 2 ft	1801213912	Not Excavated						
Football Field	ISMP-EUR-BOT1	SSHS-ISMP-EUR-BOT1	10/7/2021	-	855.94	-	854.33	0 - 2 ft	1.61 ft	180-128263-1	Not Excavated						
Football Field	ISMP-EUR-S01	SSHS-ISMP-EUR-S01	10/7/2021	-	855.93	-	854.74	0 - 2 ft	1.18 ft	180-128263-1	Not Excavated						
Football Field	SSHS-ISMP-S603	SSHS-ISMP-S603	10/7/2021	-	856.55	-	854.97	0 - 2 ft	1.58 ft	1801282631	Not Excavated						
Football Field	ISMP-S008	SSHS-ISMP-S008	12/12/2021	-	854.57	-	853.86	0 - 2 ft	0.70	1801311521	Not Excavated						
Football Field	MS-SLT-S78	SSHS-ISMP-MS-SLT-S78	3/22/2022	-	856.19	-	854.64	0 - 2 ft	1.55 ft	1801355361	Not Excavated						
Football Field	SSHS-IRM5A3-S3	SSHS-IRM5A3-S3	8/1/2022	-	--	-	853.34	0 - 2 ft	0 - 2 ft	1801422541	Not Excavated						
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-DUP1	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated						
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432571	Not Excavated						
Football Field	SSHS-ISMP-ES-S3	SSHS-ISMP-ES-S3	8/19/2022	-	855.77	-	854.35	0 - 2 ft	1.42 ft	1801432572	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Football Field	SSHS-ISMP-ES-S4	SSHS-ISMP-ES-S4	8/19/2022	-	855.69	-	853.97	0 - 2 ft	1.72 ft	1801432571	Not Excavated						
Football Field	SSHS-ISMP-ES-B2	SSHS-ISMP-ES-B2	8/19/2022	-	856.08	-	854.21	0 - 2 ft	1.87 ft	1801432571	Not Excavated						
Football Field	SSHS-ISMP-ES-S5	SSHS-ISMP-ES-S5	8/19/2022	-	855.42	-	853.58	0 - 2 ft	1.84 ft	1801432571	Not Excavated						
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432981	Not Excavated						
Football Field	SSHS-ISMP-ES-S8	SSHS-ISMP-ES-S8	8/22/2022	-	854.81	-	852.94	0 - 2 ft	1.87 ft	1801432982	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435311	Not Excavated						
Football Field	SSHS-ISMP-ES-S13	SSHS-ISMP-ES-S13	8/25/2022	-	856.00	-	854.08	0 - 2 ft	1.92 ft	1801435312	Not Excavated	< 0.039 UHT	< 0.022 UHT	< 0.044 UHT	< 0.036 UHT	< 0.028 UHT	< 0.024 UHT
Football Field	SSHS-ISMP-TR-S3	SSHS-ISMP-TR-S3	8/26/2022	-	855.83	-	854.58	0 - 2 ft	1.25 ft	1801436191	Not Excavated						
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-DUP2	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated						
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-DUP3	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated						
Football Field	SSHS-ISMP-ES-B7	SSHS-ISMP-ES-B7	8/29/2022	-	856.49	-	854.60	0 - 2 ft	1.89 ft	1801436521	Not Excavated						
Football Field	SSHS-ISMP-ES-S17	SSHS-ISMP-ES-S17	8/29/2022	-	856.61	-	854.62	0 - 2 ft	1.99 ft	1801436521	Not Excavated						
Football Field	SSHS-ISMP-ES-S15	SSHS-ISMP-ES-S15	8/29/2022	-	856.40	-	854.56	0 - 2 ft	1.83	1801436521	Not Excavated						
Football Field	IRM5-SND-SCV1	SSHS-IRM5-SND-SCV1-0-2	3/11/2026	855.325	855.325	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SND-SCV2	SSHS-IRM5-SND-SCV2-0-2	3/11/2026	855.072	855.072	-	-	0 - 2 ft	0 - 2 ft	1802027871	Not Excavated						
Football Field	SSHS-B645A	DUP-01	4/18/2021	-	856.71	-	856.02	0.17 - 1 ft	0.69 ft	180-120245-1	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 740 U							
Football Field	IRM5-SCV9	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 760 U							
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 740 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 780 U							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 750 U							
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 730 U							
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated		< 780 U		< 0.20 U	< 0.20 U	0.14 J	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 770 U							
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 770 U							
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 810 U		< 0.20 U	< 0.20 U	0.14 J	< 0.20 U	0.060 J	< 0.20 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated		< 760 U							
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 790 U							
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028452	Not Excavated		< 810 U							
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 780 U							
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 700 U							
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 710 U							
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated		< 780 U							
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 710 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 740 U							
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated		< 730 U							
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 770 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.24 U	< 0.19 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 750 U							
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 800 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 770 U							
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated		< 790 U							
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 770 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	0.11 J	< 0.19 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 800 U							
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 800 U							
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 750 U							
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated		< 770 U		< 0.20 U	< 0.20 U	0.11 J	< 0.20 U	0.068 J	< 0.20 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated		< 740 U							
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated			< 18 U						
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated			< 560 U						
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated			< 110 U						
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated			< 220 U						
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 720 U							
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 710 U							
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 710 U							
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated		< 710 U		< 0.20 U	< 0.20 U	< 0.40 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 720 U							
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 700 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 710 U							
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 710 U							
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated		< 720 U							
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 700 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 710 U							
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 700 U							
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 720 U							
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated		< 710 U							
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 710 U							
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 720 U		< 0.20 U	< 0.20 U	< 0.40 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated		< 710 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 700 U							
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 690 U							
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 700 U		< 0.19 U	< 0.19 U	< 0.39 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated		< 680 U							
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 760 U							
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 700 U							
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 690 U		< 0.20 U	< 0.20 U	< 0.39 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated		< 720 U							
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated		< 700 U							
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated		< 680 U							

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV9	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	0.15 J	0.094 J	< 0.19 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.17 J	< 0.20 U	< 0.20 U	0.40	0.20	0.22
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.19 J	< 0.20 U	< 0.20 U	0.48	0.28	0.14 J
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028452	Not Excavated									
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	0.10 J	< 0.19 U	< 0.19 U	0.11 J	0.082 J	< 0.19 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	0.78	0.19	< 0.19 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.17 J	0.080 J	< 0.20 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	0.11 J	< 0.19 U	< 0.19 U	0.74	0.29	0.099 J
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.18 J	< 0.20 U	< 0.20 U	0.60	0.28	0.12 J
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated									
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated									
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated									
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.05 U	< 0.039 U	< 0.03 U	< 0.032 U	< 0.023 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated									
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated									
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated									
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated									
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.15 J	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.15 J
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	0.11 J	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	0.10 J
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated									
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated									
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated									
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated									

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	IRM5-SCV4	SSHS-IRM5-SCV-Dup-10	3/12/2026	855.892	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV9	SSHS-IRM5-Dup-01	3/12/2026	855.487	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-0.17-1	3/12/2026	855.634	855.634	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-0.17-1	3/12/2026	855.477	855.477	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-0.17-1	3/12/2026	855.432	855.432	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-0.17-1	3/12/2026	855.487	855.487	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-0.17-1	3/12/2026	855.149	855.149	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028431	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-0.17-1	3/12/2026	854.854	854.854	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-0.17-1	3/12/2026	855.217	855.217	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-0.17-1	3/12/2026	855.093	855.093	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-0.17-1	3/12/2026	855.294	855.294	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-0.17-1	3/12/2026	855.109	855.109	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028452	Not Excavated						
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-0.17-1	3/12/2026	855.637	855.637	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-0.17-1	3/12/2026	855.502	855.502	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-0.17-1	3/12/2026	855.412	855.412	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-0.17-1	3/12/2026	855.244	855.244	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-0.17-1	3/12/2026	855.161	855.161	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-0.17-1	3/12/2026	855.946	855.946	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-0.17-1	3/12/2026	855.892	855.892	-	-	0.17 - 1 ft	0.17 - 1 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV23	SSHS-IRM5-SCV-DUP-15	3/13/2026	855.022	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-0.17-1	3/13/2026	855.427	855.427	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-0.17-1	3/13/2026	855.257	855.257	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-0.17-1	3/13/2026	853.99	853.99	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-0.17-1	3/13/2026	853.847	853.847	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-0.17-1	3/13/2026	855.022	855.022	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-0.17-1	3/13/2026	855.457	855.457	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-0.17-1	3/13/2026	856.04	856.04	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-0.17-1	3/13/2026	855.919	855.919	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-0.17-1	3/13/2026	855.626	855.626	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029261	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-0.17-1	3/13/2026	855.696	855.696	-	-	0.17 - 1 ft	0.17 - 1 ft	1802029271	Not Excavated						
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B3472	SSHS-B3472-SUB-0.17-2	7/27/2020	855.50	855.50	0.00	-	0.17 - 2 ft	0.17-2 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-0.17-2	9/23/2021	856.42	856.42	0.00	-	0.17 - 2 ft	0.17-2 ft	180-127595-2	Not Excavated	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Football Field	IRM5-SCV6	SSHS-IRM5-SCV6-1-2	3/12/2026	855.634	855.634	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV7	SSHS-IRM5-SCV7-1-2	3/12/2026	855.477	855.477	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV8	SSHS-IRM5-SCV8-1-2	3/12/2026	855.432	855.432	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated						
Football Field	IRM5-SCV9	SSHS-IRM5-SCV9-1-2	3/12/2026	855.487	855.487	-	-	1 - 2 ft	1 - 2 ft	1802028431	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SCV11	SSHS-IRM5-SCV11-1-2	3/12/2026	855.149	855.149	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV13	SSHS-IRM5-SCV13-1-2	3/12/2026	854.854	854.854	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV14	SSHS-IRM5-SCV14-1-2	3/12/2026	855.217	855.217	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV15	SSHS-IRM5-SCV15-1-2	3/12/2026	855.093	855.093	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV16	SSHS-IRM5-SCV16-1-2	3/12/2026	855.294	855.294	-	-	1 - 2 ft	1 - 2 ft	1802028441	Not Excavated						
Football Field	IRM5-SCV17	SSHS-IRM5-SCV17-1-2	3/12/2026	855.109	855.109	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV12	SSHS-IRM5-SCV12-1-2	3/12/2026	855.637	855.637	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV10	SSHS-IRM5-SCV10-1-2	3/12/2026	855.502	855.502	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV5	SSHS-IRM5-SCV5-1-2	3/12/2026	855.412	855.412	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV3	SSHS-IRM5-SCV3-1-2	3/12/2026	855.244	855.244	-	-	1 - 2 ft	1 - 2 ft	1802028451	Not Excavated						
Football Field	IRM5-SCV2	SSHS-IRM5-SCV2-1-2	3/12/2026	855.161	855.161	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated						
Football Field	IRM5-SCV1	SSHS-IRM5-SCV1-1-2	3/12/2026	855.946	855.946	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SCV4	SSHS-IRM5-SCV4-1-2	3/12/2026	855.892	855.892	-	-	1 - 2 ft	1 - 2 ft	1802028461	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV27	SSHS-IRM5-SCV27-1-2	3/13/2026	855.427	855.427	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV26	SSHS-IRM5-SCV26-1-2	3/13/2026	855.257	855.257	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV25	SSHS-IRM5-SCV25-1-2	3/13/2026	853.99	853.99	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated	< 0.19 U	< 0.19 U	< 0.19 U	< 0.39 U	< 0.39 U	< 0.19 U
Football Field	IRM5-SCV24	SSHS-IRM5-SCV24-1-2	3/13/2026	853.847	853.847	-	-	1 - 2 ft	1 - 2 ft	1802029281	Not Excavated						
Football Field	IRM5-SCV23	SSHS-IRM5-SCV23-1-2	3/13/2026	855.022	855.022	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV22	SSHS-IRM5-SCV22-1-2	3/13/2026	855.457	855.457	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV21	SSHS-IRM5-SCV21-1-2	3/13/2026	856.04	856.04	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.39 U	< 0.39 U	< 0.20 U
Football Field	IRM5-SCV20	SSHS-IRM5-SCV20-1-2	3/13/2026	855.919	855.919	-	-	1 - 2 ft	1 - 2 ft	1802029261	Not Excavated						
Football Field	IRM5-SCV19	SSHS-IRM5-SCV19-1-2	3/13/2026	855.626	855.626	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated						
Football Field	IRM5-SCV18	SSHS-IRM5-SCV18-1-2	3/13/2026	855.696	855.696	-	-	1 - 2 ft	1 - 2 ft	1802029271	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		< 180 U		< 0.20 U	< 0.20 U	< 0.40 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		< 180 U		< 0.20 U	< 0.20 U	< 0.40 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated		< 180 U							
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated		< 190 U							
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated		< 180 U							
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated			< 130 U						
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 110 U			< 0.36 U	< 0.024 U	0.15 J	< 0.038 U	0.075 J	< 0.066 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	0.20 J	< 0.041 U	0.11 J	< 0.071 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.17 J	< 0.042 U	0.10 J	< 0.073 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.27	< 0.045 U	0.085 J	< 0.077 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated		< 32 U							
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477512	Not Excavated				< 0.049 U	< 0.039 U	0.49	< 0.053 U	0.12 J	0.051 J
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated		< 31 U							
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated		< 32 U							
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477522	Not Excavated				< 0.053 U	< 0.042 U	0.27	< 0.057 U	0.12 J	0.042 J
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated		< 33 U							
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated		< 33 U							
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated		< 33 U							
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477522	Not Excavated				< 0.051 U	< 0.040 U	0.15 J	< 0.055 U	0.065 J	0.032 J
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 120 U							
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 130 U							
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated		< 120 U							
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated		< 130 U							
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated		< 33 U							
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated		< 35 U							
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479012	Not Excavated				< 0.053 U	< 0.042 U	0.55	< 0.058 U	0.14 J	0.055 J
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated		< 35 U							
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated		< 34 U							
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479012	Not Excavated				< 0.051 U	< 0.041 U	0.24	< 0.056 U	0.11 J	0.040 J
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated		< 37 U							
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated		< 34 U							
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated		< 34 U							
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated		< 33 U							
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated			< 42						
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated			< 44 U						
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.878	1801364891	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated	< 220 U								
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		< 30 UT							
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated		< 31 UT							
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407993	Not Excavated				< 0.049 U	< 0.039 U	0.063 J	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407993	Not Excavated				< 0.051 U	< 0.041 U	0.059 J	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418882	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated		< 31 U							
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418882	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.032 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated									
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated									
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated									
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated									
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated									
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.034 U	0.088 J	< 0.030 U	0.069 J	0.13 J	< 0.080 U	0.35 J	0.18 J	< 0.075 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.037 U	0.10 J	< 0.033 U	0.083 J	0.13 J	< 0.087 U	0.52 J	0.27	< 0.082 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.038 U	0.11 J	< 0.034 U	0.092 J	0.15 J	< 0.089 U	0.55	0.26	< 0.084 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.040 U	0.12 J	< 0.036 U	0.096 J	0.18 J	< 0.094 U	0.46 J	0.36	< 0.088 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477512	Not Excavated	< 0.050 U	0.18 J	< 0.030 U	0.14 J	0.21	< 0.034 U	0.71	0.51	0.12 J
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477522	Not Excavated	< 0.054 U	0.12 J	< 0.032 U	0.087 J	0.19 J	< 0.036 U	1.0	0.32	0.083 J
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477522	Not Excavated	< 0.052 U	0.073 J	< 0.031 U	0.062 J	0.10 J	< 0.035 U	0.80	0.23	0.051 J
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated									
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated									
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated									
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated									
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated									
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479012	Not Excavated	< 0.054 U	0.17 J	< 0.032 U	0.11 J	0.22	< 0.037 U	0.70	0.31	0.17 J
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479012	Not Excavated	< 0.052 U	0.077 J	< 0.031 U	0.054 J	0.21	< 0.035 U	0.54	0.24	0.072 J
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated									
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated									
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated									
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated									
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated									
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated									
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated									
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.878	1801364891	Not Excavated									
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated									
Northern Athletic Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated									
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407993	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.045 J	< 0.023 U	< 0.034 U	0.14 J	0.088 J	< 0.042 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407993	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	0.046 J	< 0.023 U	< 0.035 U	0.14 J	0.10 J	< 0.044 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418882	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.20 J	< 0.057 U	< 0.044 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418882	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	0.036 J	0.029 J	< 0.035 U	0.24	0.12 J	< 0.043 U

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.20 U	< 0.20 U	< 0.20 U	< 0.40 U	< 0.40 U	< 0.20 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated						
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated						
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated						
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0-0.17	1/19/2020	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	180-101269-1	Not Excavated						
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0-0.17	7/1/2021	856.80	856.80	0.00	-	0 - 0.17 ft	0 - 0.17 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4021	SSHS-B4021-SUB-0-0.17	7/1/2021	856.74	856.72	-0.02	-	0 - 0.17 ft	0-0.15 ft	1801239851	Not Excavated	< 0.053 U	< 0.050 U	0.081 J	< 0.24 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B4022	SSHS-B4022-SUB-0-0.17	7/1/2021	856.88	856.88	0.00	-	0 - 0.17 ft	0-0.17 ft	1801239851	Not Excavated	< 0.057 U	< 0.054 U	0.082 J	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B4023	SSHS-B4023-SUB-0-0.17	7/1/2021	857.18	857.19	0.01	-	0 - 0.17 ft	0.01-0.18 ft	1801239851	Not Excavated	< 0.059 U	< 0.056 U	0.12 J	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B4024	SSHS-B4024-SUB-0-0.17	7/1/2021	857.75	857.80	0.05	-	0 - 0.17 ft	0.05-0.22 ft	1801239851	Not Excavated	< 0.062 U	< 0.059 U	0.094 J	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV-DUP1	11/10/2022	-	857.35	-	857.10	0 - 0.17 ft	0.25 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV83-0-0.17	SSHS-IRM5A2-SCV83-0-0.17	11/10/2022	-	856.32	-	856.32	0 - 0.17 ft	0.31 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV84-0-0.17	SSHS-IRM5A2-SCV84-0-0.17	11/10/2022	-	857.01	-	857.01	0 - 0.17 ft	0.42 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV85-0-0.17	SSHS-IRM5A2-SCV85-0-0.17	11/10/2022	-	857.10	-	857.10	0 - 0.17 ft	0.29 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV74-0-0.17	SSHS-IRM5A2-SCV74-0-0.17	11/10/2022	-	857.28	-	857.28	0 - 0.17 ft	0.47 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV66-0-0.17	SSHS-IRM5A2-SCV66-0-0.17	11/10/2022	-	857.37	-	857.37	0 - 0.17 ft	0.33 ft	1801477512	Not Excavated	< 0.038 U	0.041 J	0.12 J	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SCV67-0-0.17	SSHS-IRM5A2-SCV67-0-0.17	11/10/2022	-	857.45	-	857.45	0 - 0.17 ft	0.24 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV68-0-0.17	SSHS-IRM5A2-SCV68-0-0.17	11/10/2022	-	857.40	-	857.40	0 - 0.17 ft	0.23 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV69-0-0.17	SSHS-IRM5A2-SCV69-0-0.17	11/10/2022	-	857.35	-	857.35	0 - 0.17 ft	0.24 ft	1801477522	Not Excavated	< 0.041 U	0.031 J	0.099 J	< 0.038 U	0.12 J	< 0.025 U
Northern Athletic Field	SCV70-0-0.17	SSHS-IRM5A2-SCV70-0-0.17	11/10/2022	-	856.97	-	856.97	0 - 0.17 ft	0.21 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV71-0-0.17	SSHS-IRM5A2-SCV71-0-0.17	11/10/2022	-	856.88	-	856.88	0 - 0.17 ft	0.34 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV72-0-0.17	SSHS-IRM5A2-SCV72-0-0.17	11/10/2022	-	858.14	-	858.14	0 - 0.17 ft	0.18 ft	1801477522	Not Excavated	< 0.039 U	< 0.022 U	0.051 J	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV-DUP26	11/20/2023	-	856.69	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated						
Northern Athletic Field	SCV101-0-0.17	SSHS-IRM5A2-SCV101-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated						
Northern Athletic Field	SCV102-0-0.17	SSHS-IRM5A2-SCV102-0-0.17	11/20/2023	-	856.52	-	856.52	0 - 0.17 ft	0.17 ft	1801656881	Not Excavated						
Northern Athletic Field	A8PH6-S4	SSHS-IRM5A2-A8PH6-S4	1/12/2024	-	--	-	855.55	0 - 0.17 ft	0 - 0.17 ft	1801681231	Not Excavated						
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	10/27/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801470201	Not Excavated						
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV26-0-0.5	SSHS-IRM5A2-SCV26-0-0.5	11/14/2022	-	854.53	-	854.53	0 - 0.5 ft	0.59 ft	1801479012	Not Excavated	< 0.041 U	0.053 J	0.12 J	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	SCV27-0-0.5	SSHS-IRM5A2-SCV27-0-0.5	11/14/2022	-	854.09	-	854.09	0 - 0.5 ft	0.74 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV28-0-0.5	SSHS-IRM5A2-SCV28-0-0.5	11/14/2022	-	854.00	-	854.00	0 - 0.5 ft	0.56 ft	1801479012	Not Excavated	< 0.040 U	0.030 J	0.092 J	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	SCV29-0-0.5	SSHS-IRM5A2-SCV29-0-0.5	11/14/2022	-	853.81	-	853.81	0 - 0.5 ft	0.52 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV12-0-0.5	SSHS-IRM5A2-SCV12-0-0.5	11/15/2022	-	857.67	-	857.67	0 - 0.5 ft	0.48 ft	1801479561	Not Excavated						
Northern Athletic Field	SCV7-0-0.5	SSHS-IRM5A2-SCV7-0-0.5	11/15/2022	-	857.78	-	857.78	0 - 0.5 ft	0.41 ft	1801479571	Not Excavated						
Northern Athletic Field	SCV6-0-0.5	SSHS-IRM5A2-SCV6-0-0.5	11/15/2022	-	857.77	-	857.77	0 - 0.5 ft	0.32 ft	1801479571	Not Excavated						
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated						
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated						
Northern Athletic Field	SLT-S84	SSHS-ISMP-SLT-S84	3/3/2022	-	856.53	-	855.01	0 - 2 ft	1.52 ft	1801346411	Not Excavated						
Northern Athletic Field	MS-SLT-S9	SSHS-ISMP-MS-SLT-S9	3/11/2022	-	856.54	-	854.56	0 - 2 ft	1.98	1801350892	Not Excavated						
Northern Athletic Field	MS-SLT-S84	SSHS-ISMP-MS-SLT-S84	4/8/2022	-	856.84	-	855.96	0 - 2 ft	0.878	1801364891	Not Excavated						
Northern Athletic Field	MS-SLT-S85	SSHS-ISMP-MS-SLT-S85	4/8/2022	-	856.66	-	854.86	0 - 2 ft	1.8 ft	1801364891	Not Excavated						
Northern Athletic Field	SLT-S89-BOT1	SSHS-ISMP-SLT-S89-BOT1	5/5/2022	-	856.07	-	854.56	0 - 2 ft	1.52 ft	1801376941	Not Excavated						
Northern Athletic Field	FL-S202	SSHS-IRM5A2-DUP146	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S202	SSHS-IRM5A2-FL-S202	7/1/2022	-	857.06	-	855.53	0 - 2 ft	1.53 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S209	SSHS-IRM5A2-DUP147	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407993	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-S205	SSHS-IRM5A2-FL-S205	7/5/2022	-	857.82	-	856.00	0 - 2 ft	1.82 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S206	SSHS-IRM5A2-FL-S206	7/5/2022	-	857.83	-	855.92	0 - 2 ft	1.91 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S207	SSHS-IRM5A2-FL-S207	7/5/2022	-	--	-	856.28	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S208	SSHS-IRM5A2-FL-S208	7/5/2022	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S209	SSHS-IRM5A2-FL-S209	7/5/2022	-	857.24	-	855.89	0 - 2 ft	1.35 ft	1801407993	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-DUP170	7/25/2022	-	857.09	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S220	SSHS-IRM5A2-FL-S220	7/25/2022	-	855.64	-	855.64	0 - 2 ft	1.61 ft	1801418882	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FL-S221	SSHS-IRM5A2-FL-S221	7/25/2022	-	855.63	-	855.63	0 - 2 ft	1.46 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S222	SSHS-IRM5A2-FL-S222	7/25/2022	-	855.42	-	855.42	0 - 2 ft	1.44 ft	1801418882	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418882	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418851	Not Excavated		< 31 U							
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated		< 31 U							
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated		< 30 U							
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated		< 31 U							
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418882	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	0.051 J	0.050 J	< 0.030 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613802	Not Excavated				< 0.050 U	< 0.040 U	0.55	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613802	Not Excavated				< 0.053 U	< 0.042 U	0.31	< 0.058 U	0.25	0.094 J
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613802	Not Excavated				< 0.049 U	< 0.039 U	0.55	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613812	Not Excavated				< 0.061 U	0.074 J	1.1	< 0.066 U	0.28	0.11 J
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613822	Not Excavated				< 0.052 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629182	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated	< 110 U								
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644032	Not Excavated				0.072 J	< 0.044 U	0.13 J	< 0.061 U	0.077 J	0.12 J
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645442	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648882	Not Excavated				< 0.049 U	< 0.039 U	0.26	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated		< 260 U							
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649722	Not Excavated				1.2	< 0.047 U	2.2	< 0.064 U	0.27	0.049 J
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666002	Not Excavated				< 0.056 U	< 0.044 U	0.14 J	< 0.060 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 150 U							
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated		< 130 U							
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated		< 140 U							
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated		< 140 U							
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated		< 140 U							
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667482	Not Excavated				< 0.060 U	< 0.047 U	0.59 B	< 0.065 U	0.067 J	0.043 J

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418882	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.18 J	< 0.058 U	< 0.045 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418851	Not Excavated									
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418882	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.030 U	0.071 J	< 0.032 U	0.42	0.14 J	< 0.040 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613802	Not Excavated	< 0.051 U	0.055 J	0.041 J	0.092 J	0.034 J	< 0.035 U	0.21	0.19 J	0.11 J
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613802	Not Excavated	< 0.055 U	0.20 J	0.035 J	0.11 J	0.49	< 0.037 U	2.5	0.86	0.12 J
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613802	Not Excavated	< 0.050 U	0.094 J	0.034 J	0.12 J	0.058 J	< 0.034 U	0.45	0.37	0.15 J
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613812	Not Excavated	< 0.062 U	0.19 J	< 0.037 U	0.16 J	0.38	< 0.042 U	1.5	0.54	0.15 J
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613822	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	0.034 J	< 0.036 U	1.7	< 0.057 U	< 0.044 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated									
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629182	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	0.056 BJ	< 0.021 U	< 0.032 U	0.046 J	< 0.051 U	< 0.040 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated									
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644032	Not Excavated	< 0.057 U	0.049 J	< 0.034 U	0.10 J	0.053 J	< 0.039 U	0.30	0.091 J	0.12 J
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated									
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645442	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	0.037 J	< 0.036 U	0.11 J	0.12 J	< 0.045 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648882	Not Excavated	< 0.050 U	0.14 J	< 0.030 U	0.23	< 0.023 U	< 0.034 U	0.11 JEMPC	0.31	0.24
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649722	Not Excavated	0.10 J	0.37	0.066 J	0.39	0.92	0.27	63 B	3.7	0.46
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666002	Not Excavated	< 0.057 U	0.061 J	< 0.034 U	0.091 J	0.20 J	< 0.038 U	1.4	0.22 J	0.14 J
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated									
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated									
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated									
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667482	Not Excavated	< 0.061 U	0.13 J	< 0.036 U	0.13 J	0.27	< 0.041 U	1.2	0.64	0.12 J

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S224	SSHS-IRM5A2-FL-S224	7/25/2022	-	855.14	-	855.14	0 - 2 ft	1.37 ft	1801418882	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FL-S225	SSHS-IRM5A2-FL-S225	7/25/2022	-	855.19	-	855.19	0 - 2 ft	1.34 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S226	SSHS-IRM5A2-FL-S226	7/25/2022	-	855.17	-	855.17	0 - 2 ft	1.45 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S227	SSHS-IRM5A2-FL-S227	7/25/2022	-	855.22	-	855.22	0 - 2 ft	1.4 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S228	SSHS-IRM5A2-FL-S228	7/25/2022	-	855.52	-	855.52	0 - 2 ft	1.14 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S229	SSHS-IRM5A2-FL-S229	7/25/2022	-	855.44	-	855.44	0 - 2 ft	1.09 ft	1801418882	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-DUP309	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613802	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-DUP312	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S3	SSHS-IRM5A2-A8PH3-S3	8/24/2023	-	853.97	-	853.28	0 - 2 ft	0.69 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S4	SSHS-IRM5A2-A8PH3-S4	8/24/2023	-	853.97	-	852.15	0 - 2 ft	1.82 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S5	SSHS-IRM5A2-A8PH3-S5	8/24/2023	-	--	-	852.92	0 - 2 ft	0 - 2 ft	1801613802	Not Excavated	< 0.041 U	0.090 J	0.26	< 0.039 U	0.035 J	< 0.026 U
Northern Athletic Field	A8PH3-S6	SSHS-IRM5A2-A8PH3-S6	8/24/2023	-	853.57	-	852.57	0 - 2 ft	1 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S7	SSHS-IRM5A2-A8PH3-S7	8/24/2023	-	853.57	-	851.99	0 - 2 ft	1.58 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S8	SSHS-IRM5A2-A8PH3-S8	8/24/2023	-	--	-	852.79	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S9	SSHS-IRM5A2-A8PH3-S9	8/24/2023	-	853.49	-	851.52	0 - 2 ft	1.97 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S10	SSHS-IRM5A2-A8PH3-S10	8/24/2023	-	853.16	-	851.79	0 - 2 ft	1.37 ft	1801613802	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	A8PH3-S13	SSHS-IRM5A2-A8PH3-S13	8/24/2023	-	--	-	850.68	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S14	SSHS-IRM5A2-A8PH3-S14	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S22	SSHS-IRM5A2-A8PH3-S22	8/24/2023	-	--	-	851.88	0 - 2 ft	0 - 2 ft	1801613812	Not Excavated	0.061 J	0.11 J	0.28	< 0.044 U	< 0.034 U	< 0.029 U
Northern Athletic Field	A8PH3-S23	SSHS-IRM5A2-A8PH3-S23	8/24/2023	-	--	-	850.37	0 - 2 ft	0 - 2 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S24	SSHS-IRM5A2-A8PH3-S24	8/24/2023	-	--	-	850.65	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S25	SSHS-IRM5A2-A8PH3-S25	8/24/2023	-	--	-	851.13	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S27	SSHS-IRM5A2-A8PH3-S27	8/24/2023	-	--	-	850.43	0 - 2 ft	0 - 2 ft	1801613822	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3-S29	SSHS-IRM5A2-A8PH3-S29	8/24/2023	-	--	-	850.75	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S30	SSHS-IRM5A2-A8PH3-S30	8/24/2023	-	--	-	850.20	0 - 2 ft	0 - 2 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S65	SSHS-IRM5A2-A8PH3-S65	9/6/2023	-	--	-	851.53	0 - 2 ft	0 - 2 ft	1801619371	Not Excavated						
Northern Athletic Field	NAF-EL-S1	SSHS-ISMP-NAF-EL-S1	9/22/2023	-	856.64	-	854.87	0 - 2 ft	1.78 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-S2	SSHS-ISMP-NAF-EL-S2	9/22/2023	-	856.64	-	854.82	0 - 2 ft	1.82 ft	1801629182	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	0.029 J	< 0.022 U
Northern Athletic Field	NAF-EL-S3	SSHS-ISMP-NAF-EL-S3	9/22/2023	-	856.52	-	854.91	0 - 2 ft	1.61 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-S7	SSHS-ISMP-NAF-EL-S7	9/25/2023	-	856.64	-	854.87	0 - 2 ft	1.77 ft	1801629871	Not Excavated						
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-S1	SSHS-IRM5A2-A8PH4-S1	10/25/2023	-	--	-	852.30	0 - 2 ft	0 - 2 ft	1801644032	Not Excavated	0.10 J	0.16 J	0.18 J	< 0.041 U	< 0.032 U	0.045 J
Northern Athletic Field	A8PH4-S3	SSHS-IRM5A2-A8PH4-S3	10/25/2023	-	--	-	852.05	0 - 2 ft	0 - 2 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-S5	SSHS-IRM5A2-A8PH4-S5	10/26/2023	-	--	-	852.37	0 - 2 ft	0 - 2 ft	1801644911	Not Excavated						
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-S7	SSHS-IRM5A2-A8PH4-S7	10/27/2023	-	--	-	852.60	0 - 2 ft	0 - 2 ft	1801645442	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A8PH4-S9	SSHS-IRM5A2-A8PH4-S9	10/27/2023	-	--	-	853.55	0 - 2 ft	0 - 2 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-S15	SSHS-IRM5A2-A8PH4-S15	11/1/2023	-	--	-	855.25	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-S19	SSHS-IRM5A2-A8PH4-S19	11/1/2023	-	--	-	855.63	0 - 2 ft	0 - 2 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-S23	SSHS-IRM5A2-A8PH4-S23	11/2/2023	-	--	-	854.01	0 - 2 ft	0 - 2 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S24	SSHS-IRM5A2-A8PH4-S24	11/6/2023	-	--	-	854.50	0 - 2 ft	0 - 2 ft	1801648882	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH4-S27	SSHS-IRM5A2-A8PH4-S27	11/6/2023	-	856.65	-	855.48	0 - 2 ft	1.17 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S29	SSHS-IRM5A2-A8PH4-S29	11/6/2023	-	--	-	854.92	0 - 2 ft	0 - 2 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-S30	SSHS-IRM5A2-A8PH4-S30	11/7/2023	-	--	-	855.58	0 - 2 ft	0 - 2 ft	1801649722	Not Excavated	< 0.046 U	0.037 J	0.18 J	< 0.043 U	< 0.033 U	< 0.028 U
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-DUP333	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH5-S4	SSHS-IRM5A2-A8PH5-S4	12/8/2023	-	--	-	853.73	0 - 2 ft	0 - 2 ft	1801666002	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A8PH5-S6	SSHS-IRM5A2-A8PH5-S6	12/8/2023	-	--	-	855.59	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH5-S7	SSHS-IRM5A2-A8PH5-S7	12/8/2023	-	--	-	854.16	0 - 2 ft	0 - 2 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH5-S9	SSHS-IRM5A2-A8PH5-S9	12/11/2023	-	--	-	855.79	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated						
Northern Athletic Field	A8PH5-S11	SSHS-IRM5A2-A8PH5-S11	12/11/2023	-	--	-	857.45	0 - 2 ft	0 - 2 ft	1801666341	Not Excavated						
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated						
Northern Athletic Field	A8PH5-S13	SSHS-IRM5A2-A8PH5-S13	12/12/2023	-	--	-	857.75	0 - 2 ft	0 - 2 ft	1801667482	Not Excavated	< 0.046 U	0.045 J	< 0.052 U	< 0.044 U	< 0.034 U	< 0.029 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 150 U							
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 140 U							
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 140 U							
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-SCV15A	SSHS-IRM5A2-A8PH7-SCV15A	4/1/2024	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801719061	Not Excavated				< 0.057 U	< 0.045 U	0.30	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 160 U							
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 130 U							
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 130 U							
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 1900 U							
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721832	Not Excavated				< 0.054 U	< 0.043 U	0.20 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 150 U							
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 140 U							
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 140 U							
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated		< 140 U							
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 130 U							
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 130 U							
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 150 U							
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated		< 140 U							
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated		< 140 U							
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 240 U							
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 510 U							
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726642	Not Excavated				< 0.057 U	< 0.045 U	0.13 J	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 230 U							
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated		< 250 U							
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated			< 120 U						
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated		< 29 U							
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated		< 30 U							
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated		< 30 U							
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477512	Not Excavated				< 0.047 U	< 0.037 U	0.30	< 0.051 U	0.089 J	0.049 J
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated		< 30 U							
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated		< 31 U							
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated		< 32 U							
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477522	Not Excavated				< 0.048 U	0.048 J	0.56	< 0.052 U	0.068 J	0.031 J
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated		< 30 U							
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated		< 30 U							
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated		< 30 U							
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated		< 29 U							
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated		< 32 U							
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated		< 120 U							
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated		< 130 U							
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated		< 130 U							
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated		< 120 U							
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 630 U			< 0.43 U	< 0.029 U	0.46 B	< 0.045 U	< 0.025 U	< 0.077 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated	< 130 U								
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated		< 130 U							
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated		< 140 U							
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated		< 120 U							
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated		< 120 U							
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated		< 35 U							
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated		< 37 U							
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470202	Not Excavated				< 0.048 U	< 0.038 U	0.29 B	< 0.051 U	< 0.048 U	< 0.030 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated		< 30 U							
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated		< 31 U							
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated		< 35 U							

DRAFT

TABLE 6-2E
Shallow Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated									
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH7-SCV15A	SSHS-IRM5A2-A8PH7-SCV15A	4/1/2024	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801719061	Not Excavated	< 0.059 U	0.10 J	< 0.035 U	0.075 J	0.12 J	< 0.039 U	0.45	0.22 J	< 0.049 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721832	Not Excavated	< 0.055 U	0.060 J	< 0.033 U	0.083 J	< 0.025 U	< 0.037 U	0.29 EMPC	0.24	< 0.046 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated									
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated									
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated									
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726642	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.037 U	0.081 J	< 0.039 U	0.56 EMPC	< 0.063 U	< 0.049 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated									
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated									
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated									
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477512	Not Excavated	< 0.048 U	0.13 J	< 0.028 U	0.095 J	0.15 J	< 0.032 U	0.53	0.30	0.094 J
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477522	Not Excavated	< 0.049 U	0.35	0.092 J	0.30	0.10 J	< 0.033 U	0.95	1.3	0.14 J
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated									
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated									
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated									
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated									
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated									
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated									
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.040 U	0.050 J	< 0.036 U	< 0.048 U	0.059 J	< 0.095 U	1.2 BT	0.18 J	0.41
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated									
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated									
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated									
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated									
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated									
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated									
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated									
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated									
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470202	Not Excavated	< 0.049 U	0.052 J	< 0.029 U	0.049 J	0.075 J	< 0.033 U	0.31	0.14 J	< 0.041 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated									
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated									
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated									

DRAFT

TABLE 6-2E
Shallow Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A8PH5-S15	SSHS-IRM5A2-A8PH5-S15	12/12/2023	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801667481	Not Excavated						
Northern Athletic Field	A8PH5-S17	SSHS-IRM5A2-A8PH5-S17	12/13/2023	-	--	-	858.29	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S19	SSHS-IRM5A2-A8PH5-S19	12/13/2023	-	--	-	858.49	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S21	SSHS-IRM5A2-A8PH5-S21	12/13/2023	-	--	-	857.94	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S23	SSHS-IRM5A2-A8PH5-S23	12/13/2023	-	--	-	856.80	0 - 2 ft	0 - 2 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH7-SCV15A	SSHS-IRM5A2-A8PH7-SCV15A	4/1/2024	-	--	-	857.21	0 - 2 ft	0 - 2 ft	1801719061	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-DUP341	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-DUP342	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S1	SSHS-IRM5A2-A8PH7-S1	4/10/2024	-	--	-	858.05	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S2	SSHS-IRM5A2-A8PH7-S2	4/10/2024	-	--	-	856.57	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S3	SSHS-IRM5A2-A8PH7-S3	4/10/2024	-	--	-	857.95	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S4	SSHS-IRM5A2-A8PH7-S4	4/10/2024	-	--	-	856.56	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S5	SSHS-IRM5A2-A8PH7-S5	4/10/2024	-	--	-	857.79	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S6	SSHS-IRM5A2-A8PH7-S6	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721832	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.040 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH7-S7	SSHS-IRM5A2-A8PH7-S7	4/10/2024	-	--	-	857.81	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S8	SSHS-IRM5A2-A8PH7-S8	4/10/2024	-	--	-	856.33	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-S9	SSHS-IRM5A2-A8PH7-S9	4/10/2024	-	--	-	856.35	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9A	SSHS-IRM5A2-A8PH7-SCV9A	4/10/2024	-	858.08	-	856.30	0 - 2 ft	1.78 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9B	SSHS-IRM5A2-A8PH7-SCV9B	4/10/2024	-	--	-	856.37	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9C	SSHS-IRM5A2-A8PH7-SCV9C	4/10/2024	-	--	-	856.19	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9D	SSHS-IRM5A2-A8PH7-SCV9D	4/10/2024	-	--	-	856.22	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25B	SSHS-IRM5A2-A8PH7-SCV25B	4/10/2024	-	--	-	853.14	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25C	SSHS-IRM5A2-A8PH7-SCV25C	4/10/2024	-	--	-	852.94	0 - 2 ft	0 - 2 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-DW-N	SSHS-IRM5A2-A8PH7-DW-N	4/10/2024	-	854.71	-	854.11	0 - 2 ft	0.6 ft	1801721821	Not Excavated						
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-DUP343	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25D	SSHS-IRM5A2-A8PH7-SCV25D	4/18/2024	-	--	-	854.15	0 - 2 ft	0 - 2 ft	1801726642	Not Excavated	< 0.044 U	< 0.025 U	0.064 J	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A8PH7-SCV25F	SSHS-IRM5A2-A8PH7-SCV25F	4/18/2024	-	--	-	854.23	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25G	SSHS-IRM5A2-A8PH7-SCV25G	4/18/2024	-	--	-	852.82	0 - 2 ft	0 - 2 ft	1801726641	Not Excavated						
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-0.17-1	7/1/2021	856.80	856.80	0.00	-	0.17 - 1 ft	0.17 - 1 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SCV82-0.17-1	SSHS-IRM5A2-SCV82-0.17-1	11/10/2022	-	856.41	-	855.40	0.17 - 1 ft	1.01 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV83-0.17-1	SSHS-IRM5A2-SCV83-0.17-1	11/10/2022	-	855.53	-	855.53	0.17 - 1 ft	1.1 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV84-0.17-1	SSHS-IRM5A2-SCV84-0.17-1	11/10/2022	-	856.32	-	856.32	0.17 - 1 ft	1.11 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV85-0.17-1	SSHS-IRM5A2-SCV85-0.17-1	11/10/2022	-	856.31	-	856.31	0.17 - 1 ft	1.08 ft	1801477512	Not Excavated	< 0.036 U	0.036 J	0.084 J	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	SCV74-0.17-1	SSHS-IRM5A2-SCV74-0.17-1	11/10/2022	-	856.49	-	856.49	0.17 - 1 ft	1.25 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV66-0.17-1	SSHS-IRM5A2-SCV66-0.17-1	11/10/2022	-	856.67	-	856.67	0.17 - 1 ft	1.03 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV67-0.17-1	SSHS-IRM5A2-SCV67-0.17-1	11/10/2022	-	856.76	-	856.76	0.17 - 1 ft	0.93 ft	1801477522	Not Excavated	< 0.037 U	0.024 J	0.058 J	< 0.035 U	0.035 J	< 0.023 U
Northern Athletic Field	SCV68-0.17-1	SSHS-IRM5A2-SCV68-0.17-1	11/10/2022	-	856.62	-	856.62	0.17 - 1 ft	1.01 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV69-0.17-1	SSHS-IRM5A2-SCV69-0.17-1	11/10/2022	-	856.55	-	856.55	0.17 - 1 ft	1.04 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV70-0.17-1	SSHS-IRM5A2-SCV70-0.17-1	11/10/2022	-	856.23	-	856.23	0.17 - 1 ft	0.95 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV71-0.17-1	SSHS-IRM5A2-SCV71-0.17-1	11/10/2022	-	856.02	-	856.02	0.17 - 1 ft	1.2 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV72-0.17-1	SSHS-IRM5A2-SCV72-0.17-1	11/10/2022	-	857.34	-	857.34	0.17 - 1 ft	0.98 ft	1801477521	Not Excavated						
Northern Athletic Field	SCV101-0.17-1	SSHS-IRM5A2-SCV101-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated						
Northern Athletic Field	SCV102-0.17-1	SSHS-IRM5A2-SCV102-0.17-1	11/20/2023	-	856.35	-	856.35	0.17 - 1 ft	1 ft	1801656881	Not Excavated						
Northern Athletic Field	A8PH6-S3	SSHS-IRM5A2-A8PH6-S3	1/12/2024	-	--	-	856.31	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated						
Northern Athletic Field	A8PH6-S7	SSHS-IRM5A2-A8PH6-S7	1/12/2024	-	--	-	854.93	0.17 - 1 ft	0.17 - 1 ft	1801681231	Not Excavated						
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-0.17-2	1/15/2020	856.74	856.72	-0.02	-	0.17 - 2 ft	0.15-1.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.062 U	< 0.059 U	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SCV92-0.50-0.75	SSHS-IRM5A2-SCV-DUP25	4/12/2023	-	858.60	-	857.98	0.5 - 0.75 ft	0.62 ft	1801549881	Not Excavated						
Northern Athletic Field	SCV96-0.5-0.92	SSHS-IRM5A2-SCV96-0.5-0.92	1/30/2024	-	855.94	-	855.94	0.5 - 0.92 ft	0.92 ft	1801687441	Not Excavated						
Northern Athletic Field	SCV95-0.5-0.96	SSHS-IRM5A2-SCV95-0.5-0.96	1/30/2024	-	855.89	-	855.89	0.5 - 0.96 ft	0.96 ft	1801687441	Not Excavated						
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-DUP340	1/30/2024	-	857.08	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated						
Northern Athletic Field	SCV94-0.5-0.98	SSHS-IRM5A2-SCV94-0.5-0.98	1/30/2024	-	856.05	-	857.03	0.5 - 0.98 ft	0.98 ft	1801687441	Not Excavated						
Northern Athletic Field	SCV11A-0-0.5	SSHS-IRM5A2-SCV11A-0-0.5	10/27/2022	-	857.29	-	857.29	0.5 - 1 ft	0.8 ft	1801470201	Not Excavated						
Northern Athletic Field	SCV13A-0-0.5	SSHS-IRM5A2-SCV13A-0-0.5	10/27/2022	-	857.42	-	857.42	0.5 - 1 ft	0.92 ft	1801470201	Not Excavated						
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470201	Not Excavated						
Northern Athletic Field	SCV17-0-0.5	SSHS-IRM5A2-SCV17-0-0.5	10/27/2022	-	855.90	-	855.90	0.5 - 1 ft	0.85 ft	1801470202	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SCV19-0-0.5	SSHS-IRM5A2-SCV19-0-0.5	11/3/2022	-	854.81	-	854.81	0.5 - 1 ft	0.8 ft	1801473871	Not Excavated						
Northern Athletic Field	SCV20A-0-0.5	SSHS-IRM5A2-SCV20A-0-0.5	11/3/2022	-	854.43	-	854.43	0.5 - 1 ft	0.79 ft	1801473871	Not Excavated						
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/7/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801475241	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated		< 31 U							
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated		< 31 U							
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated		< 34 U							
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated		< 34 U							
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated		< 36 U							
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated		< 35 U							
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479012	Not Excavated				< 0.054 U	< 0.042 U	0.075 J	< 0.058 U	< 0.054 U	< 0.033 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated		< 34 U							
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated		< 32 U							
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated		< 32 U							
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479562	Not Excavated				< 0.049 U	< 0.039 U	0.61	< 0.053 U	0.067 J	0.048 J
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated		< 34 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.32 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated									
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479012	Not Excavated	< 0.055 U	0.050 J	< 0.032 U	0.075 J	0.037 J	< 0.037 U	0.17 J	0.10 J	0.078 J
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated									
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated									
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated									
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479562	Not Excavated	< 0.050 U	0.17 J	< 0.030 U	0.15 J	0.18 J	< 0.034 U	0.50	0.45	0.13 J
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated									

DRAFT

TABLE 6-2E
Shallow Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	SCV26-0.5-1	SSHS-IRM5A2-SCV26-0.5-1	11/14/2022	-	853.56	-	853.56	0.5 - 1 ft	1.56 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV27-0.5-1	SSHS-IRM5A2-SCV27-0.5-1	11/14/2022	-	853.33	-	853.33	0.5 - 1 ft	1.5 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV28-0.5-1	SSHS-IRM5A2-SCV28-0.5-1	11/14/2022	-	853.09	-	853.09	0.5 - 1 ft	1.47 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV29-0.5-1	SSHS-IRM5A2-SCV29-0.5-1	11/14/2022	-	853.02	-	853.02	0.5 - 1 ft	1.52 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV21-0-0.5	SSHS-IRM5A2-SCV21-0-0.5	11/14/2022	-	854.30	-	854.30	0.5 - 1 ft	0.97 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479011	Not Excavated						
Northern Athletic Field	SCV22-0-0.5	SSHS-IRM5A2-SCV22-0-0.5	11/14/2022	-	854.21	-	854.21	0.5 - 1 ft	0.89 ft	1801479012	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	SCV20-0-0.5	SSHS-IRM5A2-SCV20-0-0.5	11/15/2022	-	854.56	-	854.56	0.5 - 1 ft	0.81 ft	1801479561	Not Excavated						
Northern Athletic Field	SCV18-0-0.5	SSHS-IRM5A2-SCV18-0-0.5	11/15/2022	-	855.35	-	855.35	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated						
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479561	Not Excavated						
Northern Athletic Field	SCV13-0-0.5	SSHS-IRM5A2-SCV13-0-0.5	11/15/2022	-	857.33	-	857.33	0.5 - 1 ft	0.77 ft	1801479562	Not Excavated	< 0.038 U	0.025 J	0.064 J	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SCV11-0-0.5	SSHS-IRM5A2-SCV11-0-0.5	11/15/2022	-	857.48	-	857.48	0.5 - 1 ft	0.73 ft	1801479561	Not Excavated						

DRAFT

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	ND	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U		
Football Field	SSHS-FB1	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	ND	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U	< 0.04 U		
Northern Athletic Field	SSHS-B37	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	0.081	< 0.035 U	< 0.035 U	< 0.035 U	< 0.035 U	0.046	< 0.035 U	0.035		
Northern Athletic Field	SSHS-B48	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B47	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
Northern Athletic Field	SSHS-B50	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U		
Northern Athletic Field	SSHS-B46	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	ND	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999	< 0.999		
EHS Building	SSHS-B4S	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U		
EHS Building	SSHS-B3S	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated	37	< U	< U	< U	< U	87	< U	< U		
EHS Building	SSHS-B8SS	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
EHS Building	SSHS-B9SS	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	3.5					3.5				
EHS Building	SSHS-B10SS	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	14					14				
EHS Building	SSHS-B5SS	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	14					14				
EHS Building	SSHS-B6SS	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	11					11				
EHS Building	SSHS-B1SS	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	11					11				
EHS Building	SSHS-B1SS	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	9.5					9.5				
EHS Building	SSHS-B1SS	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	8.4					8.4				
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B85	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0029 U	< 0.0038 U	< 0.0034 U	< 0.0032 U	< 0.0019 U	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	ND	< 0.0031 U	< 0.004 U	< 0.0036 U	< 0.0034 U	< 0.002 U	< 0.003 U	< 0.003 U	< 0.0046 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	ND	< 0.003 U	< 0.0038 U	< 0.0034 U	< 0.0033 U	< 0.0019 U	< 0.0028 U	< 0.0028 U	< 0.0044 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B89	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	ND	< 0.0028 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0026 U	< 0.0026 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	0.162	< 0.0026	< 0.0033	< 0.0029	< 0.0028	0.089	< 0.0024	0.073	< 0.0038	< 0.0022
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0016	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	ND	< 0.0027	< 0.0034	< 0.0031	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	ND	< 0.0027	< 0.0035	< 0.0032	< 0.003	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0024
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	0.147	< 0.0028	< 0.0036	< 0.0032	< 0.003	0.13	< 0.0026	0.017	< 0.0041	< 0.0024
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	ND	< 0.0028	< 0.0036	< 0.0032	< 0.0031	< 0.0018	< 0.0027	< 0.0027	< 0.0041	< 0.0024
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	ND	< 0.0027	< 0.0035	< 0.0031	< 0.003	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0023
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	ND	< 0.0027	< 0.0035	< 0.0031	< 0.0029	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0023
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0023
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0023
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	ND	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0042 U	< 0.0025 U
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	0.065	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	0.065	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	0.014	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	0.014 J	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	ND	< 0.003 U	< 0.0039 U	< 0.0035 U	< 0.0033 U	< 0.0019 U	< 0.0029 U	< 0.0029 U	< 0.0044 U	< 0.0026 U
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	0.13	< 0.0029 U	< 0.0037 U	< 0.0033 U	< 0.0032 U	0.13	< 0.0028 U	< 0.0028 U	< 0.0043 U	< 0.0025 U
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	0.543	< 0.0031 U	< 0.0039 U	< 0.0035 U	< 0.0034 U	0.5	< 0.0029 U	0.043	< 0.0045 U	< 0.0026 U
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	2.17	< 0.0031 U	< 0.004 U	< 0.0036 U	< 0.0034 U	2	< 0.003 U	0.17	< 0.0046 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.003 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0034 U	< 0.0031 U	< 0.0029 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.0039 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	ND	< 0.0026 U	< 0.0033 U	< 0.003 U	< 0.0028 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0038 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B81	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0032 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	ND	< 0.0027 U	< 0.0035 U	< 0.0031 U	< 0.003 U	< 0.0017 U	< 0.0026 U	< 0.0026 U	< 0.004 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0033 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0042 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B84	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0039 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	ND	< 0.0026 U	< 0.0034 U	< 0.003 U	< 0.0029 U	< 0.0017 U	< 0.0025 U	< 0.0025 U	< 0.0038 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	ND	< 0.0028 U	< 0.0036 U	< 0.0032 U	< 0.0031 U	< 0.0018 U	< 0.0027 U	< 0.0027 U	< 0.0041 U	< 0.0024 U
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	ND	< 0.0027	< 0.0034	< 0.0031	< 0.0029	< 0.0017	< 0.0026	< 0.0026	< 0.004	< 0.0023
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	ND	< 0.0026	< 0.0034	< 0.003	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0016	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated	0.877	< 0.0038	< 0.0046	< 0.0064	< 0.0047	0.51	0.29	0.077	< 0.0069	< 0.0037
Football Field	SSHS-B221	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated	0.039	< 0.0037 U	< 0.0045 U	< 0.0062 U	< 0.0046 U	0.039	< 0.0043 U	< 0.0039 U	< 0.0067 U	< 0.0036 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B216	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated	ND	< 0.0043 U	< 0.0052 U	< 0.0072 U	< 0.0053 U	< 0.0052 U	< 0.005 U	< 0.0046 U	< 0.0077 U	< 0.0042 U
Rear Parking Lot	SSHS-B149	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated	1.53	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	< 0.0047 U	1.2 J	0.33 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated	4.9	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	3.8 J	0.99 J	0.11 J	< 0.0071 U	< 0.0039 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated	5.2	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	3.7 J	1.3 J	0.2 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B108	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated	0.712	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.51 J	0.17 J	0.032 J	< 0.0073 U	< 0.004 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated	2.194	< 0.0042 U	< 0.0051 U	< 0.007 U	< 0.0051 U	1.6 J	0.53 J	0.064 J	< 0.0075 U	< 0.0041 U
Rear Parking Lot	SSHS-B122	SSHS-B122-SUB-6-7	7/22/2015	851.00	851.31	0.31	-	6 - 7 ft	6.31-7.31 ft	180-46170-1	Not Excavated	3.93	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	2.7 J	1.1 J	0.13 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B132	SSHS-B132-SUB-6-7	7/22/2015	851.41	851.70	0.29	-	6 - 7 ft	6.29-7.29 ft	180-46170-1	Not Excavated	5.48	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	3.7 J	1.5 J	0.28 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B112	SSHS-B112-SUB-6-7	7/22/2015	850.70	850.95	0.25	-	6 - 7 ft	6.25-7.25 ft	180-46170-1	Not Excavated	8.64	< 0.02 U	< 0.024 U	< 0.033 U	< 0.024 U	6 J	2.4 J	0.24 J	< 0.035 U	< 0.019 U
Rear Parking Lot	SSHS-B146	SSHS-B146-SUB-6-8	7/22/2015	851.73	852.11	0.38	-	6 - 8 ft	6.38-8.38 ft	180-46170-1	Not Excavated	6.27	< 0.004 U	< 0.0049 U	< 0.0067 U	< 0.0049 U	4.1 J	1.8 J	0.37 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B107	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated	0.015	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.015 J	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B108	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated	0.44	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	0.28 J	0.13 J	0.03 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B121	SSHS-B121-SUB-6-7	7/24/2015	851.01	851.23	0.22	-	6 - 7 ft	6.22-7.22 ft	180-46251-1	Not Excavated	1.035	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	0.61 J	0.34 J	0.085 J	< 0.0068 U	< 0.0037 U
Football Field	SSHS-B232	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated	0.0269	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	0.019 J	0.0079 J	< 0.0043 U	< 0.0072 U	< 0.0039 U
Football Field	SSHS-B232	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated	0.116	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U		0.096 J	0.02 U	< 0.0073 U	< 0.004 U
Football Field	SSHS-B212	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated	0.154	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.069 J	0.059 J	0.026 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B220	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated	0.214	< 0.0039 U	< 0.0048 U	< 0.0067 U	< 0.0049 U	0.047 J	0.047 J	0.12 J	< 0.0071 U	< 0.0039 U
Football Field	SSHS-B234A	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated	285.3	< 0.44 U	< 0.54 U	< 0.75 U	< 0.55 U	200 J	78 J	7.3 J	< 0.8 U	< 0.43 U
Football Field	SSHS-B227A	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated	5.62	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.005 U	4.2 J	1.3 J	0.12 J	< 0.0073 U	< 0.004 U
Football Field	SSHS-B233	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated	5.81	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	4.3 J	1.4 J	0.11 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated	0.939	< 0.004 U	< 0.0049 U	< 0.0068 U	< 0.0049 U	0.68 J	0.22 J	0.039 J	< 0.0072 U	< 0.0039 U
Rear Parking Lot	SSHS-B126	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated	0.852	< 0.0039 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	0.62 J	0.2 J	0.032 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated	0.566	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.4 J	0.14 J	0.026 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B125	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated	0.007	< 0.0041 U	< 0.0051 U	< 0.007 U	< 0.0051 U	< 0.0051 U	< 0.0048 U	0.007 J	< 0.0075 U	< 0.0041 U
Rear Parking Lot	SSHS-B126	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated	4.9	< 0.0042 U	< 0.0051 U	< 0.0071 U	< 0.0052 U	3.6 J	1.3 J		< 0.0075 U	< 0.0041 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated	2.7	< 0.0037 U	< 0.0045 U	< 0.0063 U	< 0.0046 U	1.5 J	1.2 J		< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated	0.772	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0047 U	0.38 J	0.31 J	0.082 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated	3.34	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.1 J	1.1 J	0.14 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated	0.197	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.088 J	0.085 J	0.024 J	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated	61.4	< 0.19 U	< 0.23 U	< 0.32 U	< 0.23 U	46 J	14 J	1.4 J	< 0.34 U	< 0.19 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated	4.12	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	2.9 J	1.1 J	0.12 J	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B133	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated	ND	< 0.0038 U	< 0.0047 U	< 0.0065 U	< 0.0048 U	< 0.0047 U	< 0.0045 U	< 0.0041 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B139	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated	ND	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	< 0.0045 U	< 0.0043 U	< 0.004 U	< 0.0067 U	< 0.0037 U
Rear Parking Lot	SSHS-B148	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated	ND	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	< 0.0048 U	< 0.0045 U	< 0.0042 U	< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B159	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated	21.92	< 0.039 U	< 0.048 U	< 0.066 U	< 0.048 U	15 J	6.2 J	0.72 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated	13.07	< 0.036 U	< 0.044 U	< 0.061 U	< 0.045 U	9.2 J	3.4 J	0.47 J	< 0.065 U	< 0.036 U
Rear Parking Lot	SSHS-B161	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated	1.13	< 0.0039 U	< 0.0048 U	< 0.0066 U	< 0.0048 U	0.29 J	0.84 J		< 0.007 U	< 0.0038 U
Rear Parking Lot	SSHS-B162	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated	4.15	< 0.0038 U	< 0.0047 U	< 0.0064 U	< 0.0047 U	1.3 J	2.4 J	0.45 J	< 0.0069 U	< 0.0038 U
Rear Parking Lot	SSHS-B106A	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated	11.43	< 0.038 U	< 0.047 U	< 0.064 U	< 0.047 U	9 J	2.1 J	0.33 J	< 0.069 U	< 0.037 U
Rear Parking Lot	SSHS-B106A	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated	4.494	< 0.0037 U	< 0.0046 U	< 0.0063 U	< 0.0046 U	3.1 J	1.3 J	0.094 J	< 0.0068 U	< 0.0037 U
Rear Parking Lot	SSHS-B117A	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated	22.14	< 0.039 U	< 0.048 U	< 0.066 U	< 0.049 U	14 J	7.3 J	0.84 J	< 0.071 U	< 0.039 U
Rear Parking Lot	SSHS-B160A	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated	12.13	< 0.037 U	< 0.046 U	< 0.063 U	< 0.046 U	8.1 J	3.5 J	0.53 J	< 0.067 U	< 0.037 U
Football Field	SSHS-B312	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated	ND	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	< 0.0044 U	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B314	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated	ND	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	< 0.0045 U	< 0.0072 U	< 0.0067 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B319	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated	3.75	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	2.9 J	0.7 J	0.15 J	< 0.0062 U	< 0.0037 U
Football Field	SSHS-B322	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated	2.23	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	1.6 J	0.49 J	0.14 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B335	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated	4.88	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	2.3 J	2.2 J	0.38 J	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B336	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated	0.225	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.15 J	0.064 J	0.011 J	< 0.006 U	< 0.0036 U
Rear Parking Lot	SSHS-B376	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated	0.265	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.17 J	0.075 J	0.02 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B386	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated	2.26	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1 J	0.99 J	0.27 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated	2.39	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	1 J	1.1 J	0.29 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated	5.22	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	3.7 J	1.3 J	0.22 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B386	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated	0.81	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.3 J	0.4 J	0.11 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated	8.1	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.007 U	3 J	4 J	1.1 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B371	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated	8.25	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	4.4 J	3.1 J	0.75 J	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B378	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated	6.15	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	4.7 J	1.2 J	0.25 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B394	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated	2.497	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	2 J	0.41 J	0.087 J	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B394	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated	3.125	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	2.5 J	0.54 J	0.085 J	< 0.0058 U	< 0.0035 U
Football Field	SSHS-B337	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated	0.09	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.064 J	0.026 J	< 0.0061 U	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B381	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated	0.124	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.081 J	0.034 J	0.009 J	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B381	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated	0.428	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.28 J	0.12 J	0.028 J	< 0.0054 U	< 0.0033 U
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated	0.0204	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	0.0094 J	0.011 J	< 0.0068 U	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B382	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated	ND	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	< 0.0044 U	< 0.007 U	< 0.0065 U	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B389	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated	0.0084	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.0084 J	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated	0.374	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.22 J	0.12 J	0.034 J	< 0.0053 U	< 0.0032 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated	0.369	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.22 J	0.12 J	0.029 J	< 0.006 U	< 0.0036 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated	0.008	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.008 J	< 0.0066 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated	2.54	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	0.87 J	1.3 J	0.37 J	< 0.0063 U	< 0.0038 U
Rear Parking Lot	SSHS-B374	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated	0.234	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.099 J	0.1 J	0.035 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B373	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated	2.08	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0074 U	0.83 J	0.97 J	0.28 J	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B390	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated	10.67	< 0.043 U	< 0.069 U	< 0.024 U	< 0.035 U	7.7 J	2.5 J	0.47 J	< 0.029 U	< 0.018 U
Rear Parking Lot	SSHS-B390	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated	13.07	< 0.043 U	< 0.069 U	< 0.024 U	< 0.035 U	9.2 J	3.3 J	0.57 J	< 0.029 U	< 0.018 U
Rear Parking Lot	SSHS-B391	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated	1.642	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1.2 J	0.38 J	0.062 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B392	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated	1.395	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	1 J	0.34 J	0.055 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B395	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated	2.83	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	2 J	0.69 J	0.14 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B396	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated	0.362	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	0.25 J	0.095 J	0.017 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B432	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated	2.86	< 0.0089 U	< 0.014 U	< 0.0049 U	< 0.0072 U	2 J	0.73 J	0.13 J	< 0.0061 U	< 0.0036 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B432	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated	1.91	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	1.3 J	0.51 J	0.1 J	< 0.006 U	< 0.0036 U
Football Field	SSHS-B421	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated	0.33	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	0.16 J	0.14 J	0.03 J	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B422	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated	0.417	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	0.27 J	0.12 J	0.027 J	< 0.0056 U	< 0.0033 U
Football Field	SSHS-B433	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated	1.761	< 0.0087 U	< 0.014 U	< 0.0047 U	< 0.034 U	1.2 J	0.47 J	0.091 J	< 0.0059 U	< 0.0035 U
Football Field	SSHS-B410	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated	0.386	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.034 U	0.2 J	0.14 J	0.046 J	< 0.0056 U	< 0.0034 U
Football Field	SSHS-B407	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated	ND	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.034 U	< 0.0046 U	< 0.0072 U	< 0.0067 U	< 0.0061 U	< 0.0036 U
Football Field	SSHS-B412	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated	ND	< 0.0096 U	< 0.015 U	< 0.0053 U	< 0.034 U	< 0.0049 U	< 0.0078 U	< 0.0072 U	< 0.0065 U	< 0.0039 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	0.415	< 0.0084	< 0.013	< 0.0046	< 0.0068	0.21	0.15	0.055	< 0.0057	< 0.0034
Football Field	SSHS-B456	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated	ND	< 0.0082 U	< 0.013 U	< 0.0045 U	< 0.0066 U	< 0.0042 U	< 0.0066 U	< 0.0062 U	< 0.0056 U	< 0.0034 U
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated	ND	< 0.008	< 0.013	< 0.0044	< 0.0064	< 0.0041	< 0.0064	< 0.006	< 0.0054	< 0.0033
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated	ND	< 0.008	< 0.013	< 0.0044	< 0.0065	< 0.0041	< 0.0065	< 0.006	< 0.0054	< 0.0033
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated	12.69	< 0.048 U	< 0.075 U	< 0.026 U	< 0.038 U	8.9 J	3.3 J	0.49 J	< 0.032 U	< 0.019 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated	0.019	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	0.019 J	< 0.0077 U	< 0.0071 U	< 0.0064 U	< 0.0039 U
Rear Parking Lot	SSHS-MW-46	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated	ND	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0076 U	< 0.0048 U	< 0.0076 U	< 0.0071 U	< 0.0064 U	< 0.0039 U
Rear Parking Lot	SSHS-B531	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated	0.269	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	0.17 J	0.076 J	0.023 J	< 0.0053 U	< 0.0032 U
Rear Parking Lot	SSHS-B531	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated	0.234	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	0.15 J	0.065 J	0.019 J	< 0.0054 U	< 0.0033 U
Rear Parking Lot	SSHS-B554	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated	0.419	< 0.0094 U	< 0.015 U	< 0.0051 U	< 0.0076 U	0.18 J	0.16 J	0.079 J	< 0.0064 U	< 0.0038 U
Rear Parking Lot	SSHS-B538	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated	ND	< 0.0091 U	< 0.014 U	< 0.005 U	< 0.0073 U	< 0.0047 U	< 0.0073 U	< 0.0068 U	< 0.0062 U	< 0.0037 U
Rear Parking Lot	SSHS-B543	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated	ND	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0077 U	< 0.0049 U	< 0.0077 U	< 0.0071 U	< 0.0065 U	< 0.0039 U
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated	1.919	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.0069 U	1.4 J	0.46 J	0.059 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated	68.8	< 0.17 U	< 0.28 U	< 0.095 U	< 0.14 U	53 J	14 J	1.8 J	< 0.12 U	< 0.071 U
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated	0.297	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	0.19 J	0.088 J	0.019 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B549	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated	0.453	< 0.0086 U	< 0.014 U	< 0.0047 U	< 0.007 U	0.3 J	0.13 J	0.023 J	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated	1.23	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0072 U	0.83 J	0.34 J	0.06 J	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B536	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated	1.549	< 0.0093 U	< 0.015 U	< 0.0051 U	< 0.0075 U	1 J	0.46 J	0.089 J	< 0.0063 U	< 0.0038 U
Rear Parking Lot	SSHS-B536	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated	1.89	< 0.0092 U	< 0.015 U	< 0.005 U	< 0.0074 U	1.2 J	0.58 J	0.11 J	< 0.0062 U	< 0.0038 U
Rear Parking Lot	SSHS-B543	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated	10.92	< 0.046 U	< 0.072 U	< 0.025 U	< 0.037 U	8 J	2.5 J	0.42 J	< 0.031 U	< 0.019 U
Rear Parking Lot	SSHS-B552	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated	1.494	< 0.0094 U	< 0.015 U	< 0.0052 U	< 0.0076 U	1.1 J	0.34 J	0.054 J	< 0.0064 U	< 0.0038 U
Rear Parking Lot	SSHS-B537	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated	ND	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	< 0.0044 U	< 0.007 U	< 0.0065 U	< 0.0059 U	< 0.0036 U
Rear Parking Lot	SSHS-B542	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated	ND	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	< 0.0043 U	< 0.0068 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B545	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated	ND	< 0.0086 U	< 0.013 U	< 0.0047 U	< 0.0069 U	< 0.0044 U	< 0.0069 U	< 0.0064 U	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B534	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated	11.52	< 0.04 U	< 0.063 U	< 0.022 U	< 0.032 U	8.8 J	2.4 J	0.32 J	< 0.027 U	< 0.016 U
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated	3.037	< 0.0086 U	< 0.013 U	< 0.0047 U	< 0.0069 U	2.3 J	0.66 J	0.077 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated	ND	< 0.0084 U	< 0.013 U	< 0.0046 U	< 0.0068 U	< 0.0043 U	< 0.0068 U	< 0.0063 U	< 0.0057 U	< 0.0034 U
Rear Parking Lot	SSHS-B533	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated	3.14	< 0.0085 U	< 0.013 U	< 0.0047 U	< 0.0069 U	2.3 J	0.74 J	0.1 J	< 0.0058 U	< 0.0035 U
Rear Parking Lot	SSHS-B534	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated	5.97	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	4.6 J	1.2 J	0.17 J	< 0.0054 U	< 0.0032 U
Rear Parking Lot	SSHS-B535	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated	0.474	< 0.0083 U	< 0.013 U	< 0.0045 U	< 0.0067 U	0.35 J	0.11 J	0.014 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B540	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated	1.864	< 0.0083 U	< 0.013 U	< 0.0046 U	< 0.0067 U	1.3 J	0.49 J	0.074 J	< 0.0056 U	< 0.0034 U
Rear Parking Lot	SSHS-B544	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated	0.12	< 0.0087 U	< 0.014 U	< 0.0048 U	< 0.007 U	0.089 J	0.031 J	< 0.0065 U	< 0.0059 U	< 0.0035 U
Rear Parking Lot	SSHS-B545	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated	0.11	< 0.009 U	< 0.014 U	< 0.0049 U	< 0.0073 U	0.11 J	< 0.0073 U	< 0.0067 U	< 0.0061 U	< 0.0037 U
Rear Parking Lot	SSHS-B550	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated	0.822	< 0.0095 U	< 0.015 U	< 0.0052 U	< 0.0076 U	0.64 J	0.16 J	0.022 J	< 0.0064 U	< 0.0039 U
Football Field	SSHS-B451	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated	ND	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	< 0.0064 U	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated	0.0088	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	0.0088 J	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated	0.23	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0065 U	0.12 J	0.11 J	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B452	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated	0.013	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	0.013 J	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated	ND	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0066 U	< 0.0041 U	< 0.0066 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B452	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0058 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B451	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated	ND	< 0.0079 U	< 0.012 U	< 0.0043 U	< 0.0064 U	< 0.004 U	< 0.0064 U	< 0.0059 U	< 0.0054 U	< 0.0032 U
Football Field	SSHS-B452	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated	ND	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	< 0.0041 U	< 0.0064 U	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B452	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated	ND	< 0.008 U	< 0.013 U	< 0.0044 U	< 0.0064 U	< 0.0041 U	< 0.0064 U	< 0.006 U	< 0.0054 U	< 0.0033 U
Football Field	SSHS-B625	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B625	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated	ND	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	< 0.0088 U	< 0.0081 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B627	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated	0.66	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.3 J	0.25 J	0.11 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B624	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated	0.532	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.37	0.13	0.032	< 0.013 U	< 0.0055 U
Football Field	SSHS-B628	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated	0.675	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.32 J	0.29 J	0.065 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B629	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B624	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0082 U	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B629	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated	ND	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B629	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated	0.03	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.017 J	0.013 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B657	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated	0.045	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.023 J	0.022 J	< 0.012 U	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated	0.697	< 0.0097	< 0.0095	< 0.0072	< 0.015	0.43	0.18	0.087	< 0.013	< 0.0056
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated	0.231	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.13	0.068	0.033	< 0.013	< 0.0056
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated	0.095	< 0.0093	< 0.0091	< 0.0069	< 0.014	0.07	0.025	< 0.012	< 0.013	< 0.0053
Tennis Courts / Main Parking Lot	SSHS-B595	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated	0.081	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.037 J	0.028 J	0.016 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B595	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated	0.063	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.037 J	0.026 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B596	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated	0.327	< 0.011 U	< 0.011 U	< 0.008 U	< 0.016 U	0.2 J	0.093 J	0.034 J	< 0.015 U	< 0.0062 U
Tennis Courts / Main Parking Lot	SSHS-B634	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated	0.133	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.087 J	0.046 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B621	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated	0.826	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.62 J	0.17 J	0.036 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated	0.268	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.18	0.088	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B621	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated	0.056	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.029	0.027	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B645	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated	0.078	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.046	0.032	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B646	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated	0.96	< 0.0095 U	< 0.0093 U	< 0.0071 U	0.96	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B651	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated	0.069	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.05	0.019	< 0.012 U	< 0.013 U	< 0.0053 U
Football Field	SSHS-B652	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated	19.24	< 0.094 U	< 0.092 U	< 0.07 U	< 0.14 U	15	3.6	0.64	< 0.13 U	< 0.054 U
Football Field	SSHS-B653	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated	5.41	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	4.1	1.1	0.21	< 0.013 U	< 0.0055 U
Football Field	SSHS-B656	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated	0.618	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.45 J	0.15 J	0.018 J	< 0.013 U	< 0.0055 U
Football Field	SSHS-B630	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated	0.216	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.17	0.046	< 0.012 U	< 0.013 U	< 0.0057 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B650	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated	ND	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B651	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated	ND	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.014 U	< 0.0081 U	< 0.0075 U	< 0.011 U	< 0.012 U	< 0.0052 U
Football Field	SSHS-B652	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated	0.45	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.33	0.12	< 0.012 U	< 0.012 U	< 0.0053 U
Football Field	SSHS-B653	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated	0.354	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	0.28	0.074	< 0.012 U	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B581	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated	0.132	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.086 J	0.046 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B582	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated	0.407	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.24 J	0.12 J	0.047 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B583	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated	0.122	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	0.053 J	0.045 J	0.024 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B584	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated	2.74	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	1.7 J	0.69 J	0.35 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B584	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated	0.83	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.45 J	0.27 J	0.11 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B587	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated	0.068	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.04 J	0.028 J	< 0.013 U	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B587	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated	0.104	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.063 J	0.041 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated	0.292	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.15 J	0.11 J	0.032 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B591	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated	0.018	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0086 U	0.018	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B592	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated	0.53	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.19 J	0.2 J	0.14 J	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B593	SSHS-B593-SUB-0-2	2/15/2017	856.22	856.93	0.71	-	0 - 2 ft	0.71-2.71 ft	180-63517-1	Not Excavated	0.223	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.045 J	0.12 J	0.058 J	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B578	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated	1.18	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.4 J	0.53 J	0.25 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B579	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B594	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated	0.72	< 0.0097 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.36	0.24	0.12	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B590	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated	ND	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	< 0.0091 U	< 0.0084 U	< 0.013 U	< 0.014 U	< 0.0058 U
Football Field	SSHS-B622	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated	0.058	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.042 J	0.016 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B654	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated	0.0316	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.022 J	0.0096 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B659	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated	0.0188	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.0094 J	0.0094 J	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B622	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated	6.92	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	4.7	2.1	0.12	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated	0.551	< 0.0097	< 0.0095	< 0.0073	< 0.015	0.38	0.11	0.061	< 0.013	< 0.0056
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated	1.22	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.015 U	0.74	0.36	0.12	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated	2.66	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	2.1	0.46	0.1	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated	0.023	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.023	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated	4.54	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	3.5	0.88	0.16	< 0.013 U	< 0.0056 U
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated	0.2	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.2	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated	0.887	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.52	0.27	0.097	< 0.013 U	< 0.0056 U
Football Field	SSHS-B724	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated	0.014	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.014 J	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B720	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated	0.112	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.056	0.04	0.016 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B722	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated	0.046	< 0.0093 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.028	0.018	< 0.012 U	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B720	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated	0.135	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.077	0.045	0.013 J	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B722	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated	0.083	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.055	0.028	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B743	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated	0.017	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	0.017 J	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B792	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated	0.342	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.23	0.093	0.019	< 0.013 U	< 0.0057 U
Football Field	SSHS-B803	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated	0.011	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.011 J	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B804	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated	3.34	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	2.3	0.93	0.11	< 0.013 U	< 0.0056 U
Football Field	SSHS-B800	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated	0.206	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.16	0.046	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated	0.196	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.016 U	0.13 J	0.066 J	< 0.013 U	< 0.014 U	< 0.0061 U
Tennis Courts / Main Parking Lot	SSHS-B799	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated	0.047	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.033	0.014 J	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B783	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated	0.292	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.2 J	0.078 J	0.014 J	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B745	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated	0.36	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.24	0.094	0.026	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B745	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated	0.421	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.28	0.11	0.031	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B746	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated	0.402	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.25	0.12	0.032	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B749	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated	0.676	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.29	0.29	0.096	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B749	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated	0.89	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.37	0.39	0.13	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B759	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated	1.07	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.55	0.39	0.13	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B759	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated	0.452	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.23	0.17	0.052	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B769	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated	0.863	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	0.53	0.26	0.073	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B770	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated	0.307	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.15	0.12	0.037	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated	0.404	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	< 0.0084 U	0.35	0.054	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B774	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated	0.359	< 0.0092 U	< 0.009 U	< 0.0069 U	< 0.014 U	0.16	0.15	0.049	< 0.012 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B747	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated	0.39	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0086 U	0.39	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B748	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated	0.556	< 0.01 U	< 0.0099 U	< 0.0076 U	< 0.015 U	0.25	0.26	0.046	< 0.014 U	< 0.0058 U
Tennis Courts / Main Parking Lot	SSHS-B750	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated	0.36	< 0.0099 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.0089 U	0.36	< 0.012 U	< 0.013 U	< 0.0057 U
Tennis Courts / Main Parking Lot	SSHS-B752	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated	0.01	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	< 0.0085 U	0.01 J	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B756	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated	0.399	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.2	0.15	0.049	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B757	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B758	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated	1.06	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.46	0.47	0.13	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B761	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated	0.014	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.014 J	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B765	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated	ND	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B766	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated	0.39	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.015 U	< 0.0092 U	0.29	0.1	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B768	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated	0.286	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.015 U	0.058	0.2	0.028	< 0.014 U	< 0.0059 U
Tennis Courts / Main Parking Lot	SSHS-B771	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated	0.102	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	0.09	0.012 J	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B772	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated	0.188	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.051	0.11	0.027	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B773	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated	0.114	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	< 0.0087 U	0.088	0.026	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B778	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated	0.0098	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	0.0098 J	< 0.012 U	< 0.013 U	< 0.0055 U
Northern Athletic Field	SSHS-B754	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated	2.32	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	1.3	0.79	0.23	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B755	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated	1.77	< 0.0098 U	< 0.0095 U	< 0.0073 U	< 0.015 U	0.97	0.62	0.18	< 0.013 U	< 0.0056 U
Northern Athletic Field	SSHS-B763	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Northern Athletic Field	SSHS-B781	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated	2.53	< 0.0094 U	< 0.0091 U	< 0.007 U	< 0.014 U	1.4	0.89	0.24	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated	0.301	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.17	0.097	0.034	< 0.013 U	< 0.0055 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B777	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0082 U	< 0.012 U	< 0.013 U	< 0.0057 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0053 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	ND	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	< 0.0087 U	< 0.008 U	< 0.012 U	< 0.013 U	< 0.0056 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	ND	< 0.0091 U	< 0.0089 U	< 0.0068 U	< 0.014 U	< 0.0082 U	< 0.0075 U	< 0.011 U	< 0.012 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-B822	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B822	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated	ND	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	< 0.009 U	< 0.0082 U	< 0.013 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B629A	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B629A	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated	ND	< 0.0094 U	< 0.0092 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B625A	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated	0.06	< 0.0098 U	< 0.0096 U	< 0.0073 U	< 0.015 U	0.03	0.03	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B630A	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated	2.201	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	1.7	0.45	0.051	< 0.013 U	< 0.0055 U
Football Field	SSHS-B657A	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated	0.0189	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.01 J	0.0089 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B803A	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated	0.086	< 0.0096 U	< 0.0094 U	< 0.0072 U	< 0.014 U	0.067	0.019	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B804A	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated	0.211	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.15	0.061	< 0.012 U	< 0.013 U	< 0.0055 U
Rear Parking Lot	SSHS-B869	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated	0.345	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.23 J	0.097 J	0.018 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B853	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated	0.026	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.026	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated	6.16	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.6 J	1.3 J	0.26 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated	0.546	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.38	0.14	0.026	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated	8.12	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	5.4 J	2.2 J	0.52 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated	13.99	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	10 J	3.3 J	0.69 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B864	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated	7.11	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4.8 J	1.9 J	0.41 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated	4.22	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3 J	1 J	0.22 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B854	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated	0.741	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.44	0.25	0.051	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated	1.28	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.69 J	0.44 J	0.15 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B894	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated	6.83	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.6 J	1.8 J	0.43 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B895	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated	0.317	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.21	0.089	0.018 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B838	SSHS-B838-SUB-6-8	1/9/2018	851.95	852.25	0.30	-	6 - 8 ft	6.30-8.30 ft	180-74014-1	Not Excavated	5.47	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3.7 J	1.4 J	0.37 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B835	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated	6.06	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.1	1.7	0.26	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B864	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated	0.351	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.16	0.14	0.051	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated	0.43	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18 J	0.25 J	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B904	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated	9.05	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	6.1	2.4	0.55	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated	ND	< 0.0055 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.013 U	< 0.012 U	< 0.0048 U	< 0.012 U	< 0.0082 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated	1.495	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.1 J	0.3 J	0.095 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B855	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated	0.1865	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13	0.049	0.0075 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated	1.78	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.47	0.11	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B829	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated	0.103	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.068	0.035	< 0.0051 U	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B831	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated	1.63	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.69	0.68	0.26	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B897	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated	34.06	< 0.12 U	< 0.23 U	< 0.21 U	< 0.21 U	27 J	6.3 J	< 0.1 U	0.76	< 0.17 U
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated	1.7	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.97 J	0.54 J	0.19 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated	0.095	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.077 J	0.018 J	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B873	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated	4.23	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8 J	1.2 J	0.23 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated	0.574	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.34	0.18	0.054	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B884	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated	0.1715	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13 J	0.034 J	0.0075 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated	0.574	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.34	0.18	0.054	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated	4.15	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	2.7 J	1.2 J	0.25 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B919	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated	2.25	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.62 J	0.13 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated	4.42	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.1	1	0.32	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B925	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated	1.68	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.37	0.11	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated	11.9	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	7.7 J	3.5 J	0.7 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B889	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated	3.08	< 0.0058 U	< 0.011 U	< 0.011 U	< 0.011 U	2 J	0.87 J	0.21 J	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B920	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated	7.13	< 0.032 U	< 0.063 U	< 0.057 U	< 0.058 U	4.6 J	2.1 J	0.43 J	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated	16.17	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	12 J	3.8 J	0.37 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B885	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated	5.57	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.9 J	1.3 J	0.37 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B856	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated	6.99	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4.8 J	1.9 J	0.29 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B892	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated	1.55	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.57 J	0.98 J	< 0.0056 UJ	< 0.014 UJ	< 0.0095 UJ
Rear Parking Lot	SSHS-B905	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated	5.53	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6 J	1.6 J	0.33 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated	52	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	41 J	9.2 J	1.8 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B845	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B851	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated	0.638	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.44 J	0.16 J	0.038 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B877	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated	2.07	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5	0.47	0.1	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated	2.92	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	2.2	0.58	0.14	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B917	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated	3.84	< 0.066 U	< 0.13 U	< 0.12 U	< 0.12 U	2.7 J	0.98 J	0.16 J	< 0.14 U	< 0.099 U
Rear Parking Lot	SSHS-B926	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated	2.34	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2 J	0.86 J	0.28 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated	49.3	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	37 J	11 J	1.3 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B839	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated	0.083	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.063 J	0.02 J	< 0.0055 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated	7.95	< 0.063 U	< 0.13 U	< 0.12 U	< 0.12 U	5.8 J	1.9 J	0.25 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B852	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated	2.075	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.52 J	0.055 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated	1.911	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4 J	0.46 J	0.051 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated	11.51	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	8.4	2.7	0.41	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B891	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated	0.078	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U		0.078 J	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated	15.05	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	11	3.6	0.45	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B879	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated	2.48	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.8	0.61	0.07	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B886	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated	5.5	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	3.9 J	1.4 J	0.2 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B893	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated	4.75	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	3.2 J	1.4 J	0.15 J	< 0.14 U	< 0.095 U
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated	0.5	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38 J	0.12 J	< 0.0052 U	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B924	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated	2.45	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7 J	0.65 J	0.1 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B844	SSHS-B844-SUB-6-8	1/19/2018	850.69	850.95	0.26	-	6 - 8 ft	6.26-8.26 ft	180-74310-1	Not Excavated	17.73	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	13 J	4.2 J	0.53 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B843	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated	20.34	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	15 J	4.7 J	0.64 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated	26.9	< 0.063 U	< 0.12 U	< 0.11 U	< 0.12 U	20 J	6.1 J	0.8 J	< 0.13 U	< 0.093 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated	2.699	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	1.9 J	0.7 J	0.099 J	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B843	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated	11.37	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	8.3	2.7	0.37	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-B911	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated	0.069	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.048 J	0.021 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated	0.127	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.086	0.041	< 0.0057 U	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated	62.5	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	41	19	2.5	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B840	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated	2.523	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.9	0.55	0.073	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B841	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated	1.727	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2	0.47	0.057	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B837	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated	2.67	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	1.6 J	0.96 J	0.11 J	< 0.13 U	< 0.092 U
Rear Parking Lot	SSHS-B937	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated	32.95	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	8.1 J	0.85 J	< 0.13 U	< 0.087 U
Rear Parking Lot	SSHS-B847	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated	25.56	< 0.058 U	< 0.12 U	< 0.11 U	< 0.11 U	19 J	5.9 J	0.66 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated	3	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	1.9 J	0.97 J	0.13 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B883	SSHS-B883-SUB-8-10	1/20/2018	852.06	852.1	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74390-1	Not Excavated	95	< 0.077 U	< 0.15 U	< 0.14 U	< 0.14 U	59 J	32 J	4 J	< 0.17 U	< 0.11 U
Rear Parking Lot	SSHS-B848	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated	1.647	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	1 J	0.56 J	0.087 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B878	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated	0.331	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.22 J	0.096 J	0.015 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated	9.37	< 0.031 U	< 0.061 U	< 0.056 U	< 0.057 U	6.8 J	2.1 J	0.47 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated	15.58	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	11 J	4 J	0.58 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-B888	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated	3.15	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	2.3	0.75	0.1	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B914	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated	1.49	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.83	0.54	0.12	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B849	SSHS-B849-SUB-6-8	1/22/2018	850.73	850.86	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74331-1	Not Excavated	7.02	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	5.2 J	1.6 J	0.22 J	< 0.14 U	< 0.097 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated	33.2	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	24 J	7.5 J	1.7 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated	2.65	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.9 J	0.6 J	0.15 J	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B913	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated	5.52	< 0.065 U	< 0.13 U	< 0.12 U	< 0.12 U	3.8 J	1.5 J	0.22 J	< 0.14 U	< 0.096 U
Rear Parking Lot	SSHS-B946	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated	0.227	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.17 J	0.057 J	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B842	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated	5.91	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	4.3 J	1.3 J	0.31 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B881	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated	6.14	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	4.4	1.5	0.24	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated	7.91	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	5.5 J	2 J	0.41 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated	116.4	< 0.3 U	< 0.6 U	< 0.55 U	< 0.55 U	87 J	24 J	5.4 J	< 0.65 U	< 0.45 U
Rear Parking Lot	SSHS-B948	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated	0.057	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.041 J	0.016 J	< 0.0058 U	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B948	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated	0.069	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.048 J	0.021 J	< 0.0055 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B939	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated	2.98	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	2.1 J	0.7 J	0.18 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B850	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated	0.309	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.22	0.072	0.017 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B890	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated	2	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	0.55 J	0.15 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B890	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated	3.05	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.1 J	0.76 J	0.19 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B930	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated	0.016	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.016 J	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B887	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated	2.93	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	2 J	0.77 J	0.16 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B906	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated	28.8	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	28 J	8.8 J	2 J	< 0.13 U	< 0.09 U
Rear Parking Lot	SSHS-B942	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated	0.042	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.042	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated	2.53	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.6	0.77	0.16	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated	1.9	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.2	0.58	0.12	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B956	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated	4.4	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	3.2	1	0.2	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated	0.688	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.43	0.21	0.048	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated	7.86	< 0.03 U	< 0.06 U	< 0.055 U	< 0.055 U	5.1	2.3	0.46	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated	0.323	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.21	0.094	0.019	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B951	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B955	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated	0.526	< 0.0058 U	< 0.011 U	< 0.01 U	< 0.011 U	0.27	0.19	0.066	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B959	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated	0.226	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.15	0.065	0.011 J	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated	0.1209	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.077	0.035	0.0089 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B985	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated	6.82	< 0.034 U	< 0.068 U	< 0.062 U	< 0.063 U	4.5	1.9	0.42	< 0.073 U	< 0.051 U
Rear Parking Lot	SSHS-B957	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated	9.87	< 0.029 U	< 0.057 U	< 0.052 U	< 0.053 U	6.5	2.8	0.57	< 0.062 U	< 0.043 U
Rear Parking Lot	SSHS-B959	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated	1.396	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	0.87	0.44	0.086 J	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B960	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated	4.98	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	3.6	1.1	0.28	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B981	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated	1.43	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.83	0.45	0.15	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B998	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated	1.2	< 0.03 U	< 0.06 U	< 0.055 U	< 0.055 U	0.72	0.36	0.12	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated	1.3	< 0.032 U	< 0.064 U	< 0.059 U	< 0.059 U	0.54	0.62	0.14	< 0.07 U	< 0.048 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated	5.58	< 0.035 U	< 0.071 U	< 0.065 U	< 0.065 U	2.7	2.5	0.38	< 0.076 U	< 0.053 U
Rear Parking Lot	SSHS-B993	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated	0.546	< 0.03 U	< 0.061 U	< 0.056 U	< 0.056 U	0.34	0.16	0.046 J	< 0.066 U	< 0.045 U
Rear Parking Lot	SSHS-B993	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated	0.37	< 0.031 U	< 0.062 U	< 0.057 U	< 0.057 U	0.26	0.11	< 0.027 U	< 0.067 U	< 0.047 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated	0.594	< 0.033 U	< 0.066 U	< 0.061 U	< 0.061 U	0.31	0.24	0.044 J	< 0.072 U	< 0.05 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated	6.46	< 0.033 U	< 0.067 U	< 0.061 U	< 0.062 U	3.5	2.5	0.46	< 0.072 U	< 0.05 U
Rear Parking Lot	SSHS-B993	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated	0.027	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	0.027	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B970	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated	0.7	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.56 J	0.14 J		< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated	0.949	< 0.029 U	< 0.058 U	< 0.053 U	< 0.054 U	0.62	0.28	0.049 J	< 0.063 U	< 0.044 U
Rear Parking Lot	SSHS-B994	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated	3.82	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8	0.92	0.1	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B995	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated	12.88	< 0.032 U	< 0.063 U	< 0.058 U	< 0.058 U	8.8	3.6	0.48	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B995	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated	2.28	< 0.032 U	< 0.063 U	< 0.058 U	< 0.059 U	1.3	0.83	0.15	< 0.069 U	< 0.048 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated	0.71	< 0.03 U	< 0.059 U	< 0.054 U	< 0.055 U	0.27	0.32	0.12	< 0.064 U	< 0.044 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated	0.681	< 0.031 U	< 0.062 U	< 0.057 U	< 0.058 U	0.37	0.24	0.071 J	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-B973	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated	2.6	< 0.031 U	< 0.062 U	< 0.056 U	< 0.057 U	1.5	0.97	0.13	< 0.067 U	< 0.046 U
Rear Parking Lot	SSHS-B977	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated	1.314	< 0.03 U	< 0.06 U	< 0.055 U	< 0.056 U	0.76	0.48	0.074 J	< 0.065 U	< 0.045 U
Rear Parking Lot	SSHS-B1006	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated	0.1652	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.11 J	0.046 J	0.0092 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1007	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated	31.5	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	24 J	6 J	1.5 J	< 0.14 U	< 0.095 U
Rear Parking Lot	SSHS-B1007	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated	40.2	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	31 J	7.6 J	1.6 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B1008	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated	36	< 0.071 U	< 0.14 U	< 0.13 U	< 0.13 U	24 J	9.8 J	2.2 J	< 0.15 U	< 0.11 U
Rear Parking Lot	SSHS-B958	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated	0.561	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.38 J	0.15 J	0.031 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B958	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated	0.52	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.4 J	0.12 J	< 0.0055 U	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-B979	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated	5.64	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	3.7 J	1.6 J	0.34 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B979	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated	7.34	< 0.0072 U	< 0.014 U	< 0.013 U	< 0.013 U	5.5 J	1.6 J	0.24 J	< 0.016 U	< 0.011 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B992	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated	2.59	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	1.9	0.58	0.11	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B953	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated	0.59	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.42 J	0.17 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B980	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated	1.396	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	1.1 J	0.26 J	0.036 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B950	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated	2.32	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.4 J	0.77 J	0.15 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B992	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated	59.1	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	43 J	14 J	2.1 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B978	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated	0.585	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	0.37 J	0.18 J	0.035 J	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated	0.553	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.35 J	0.17 J	0.033 J	< 0.013 U	< 0.0086 U
Rear Parking Lot	SSHS-B989	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated	4.91	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	3.5	1.2	0.21	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated	3.81	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8	0.88	0.13	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B954	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated	0.91	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11 J	0.48 J	0.32 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated	3.2	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.7 J	1.3 J	0.2 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B986	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated	0.458	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.22 J	0.18 J	0.058 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B961	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated	5.67	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	3.5 J	1.8 J	0.37 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B978	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated	3.16	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.4	0.66	0.1	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B989	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated	8.31	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	5.5 J	2.4 J	0.41 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B989	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated	6.1	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	4.3 J	1.6 J	0.2 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1010	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated	0.082	< 0.0078 U	< 0.016 U	< 0.014 U	< 0.014 U	0.061	0.021 J	< 0.0068 U	< 0.017 U	< 0.012 U
Rear Parking Lot	SSHS-B1016	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated	0.036	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.036	< 0.013 U	< 0.0055 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1017	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated	2.82	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	1.2	0.32	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1018	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated	2.109	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	1.6	0.44	0.069	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1010	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated	5.62	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	4.3	1.1	0.22	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated	0.616	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.45	0.14	0.026	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1026	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated	33.2	< 0.07 U	< 0.14 U	< 0.13 U	< 0.13 U	21	10	2.2	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B1017	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated	1.32	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.59	0.56	0.17	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1018	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated	1.289	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.81	0.39	0.089	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1015	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated	0.782	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.24	0.072	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1023b	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated	5	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	3.6	1.2	0.2	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1025	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated	0.373	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.24	0.11	0.023	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1020	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated	1.71	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.3	0.35	0.06	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1020	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated	1.724	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	0.36	0.064	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1063	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated	0.0081	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U	0.0081 J	< 0.0029 U	< 0.0029 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SSHS-B1073	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated	0.995	< 0.013 UJ	< 0.013 UJ	< 0.013 UJ	< 0.013 UJ	0.61 J	0.33 J	0.055 J	< 0.013 UJ	< 0.013 UJ
Rear Parking Lot	SSHS-B1189	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated	1.96	< 0.03 UJ	< 0.03 UJ	< 0.03 UJ	< 0.03 UJ	0.61 J	1.2 J	0.15 J	< 0.03 UJ	< 0.03 UJ
Rear Parking Lot	SSHS-B1084	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated	1.156	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38 J	0.71 J	0.066 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1234	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated	3.9	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	3.6 J	0.3 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1074	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated	0.46	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24 J	0.22 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1074	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated	0.212	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.12 J	0.092 J	< 0.0057 U	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1202	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated	2.09	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4 J	0.55 J	0.14 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1064	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated	3.58	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.4 J	0.98 J	0.2 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1194	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated	0.127	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.084 J	0.043 J	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1202	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated	0.327	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.24 J	0.069 J	0.018 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1242	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated	1.94	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2 J	0.55 J	0.19 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1243	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated	0.92	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.42 J	0.36 J	0.14 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1109	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated	0.138	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.093 J	0.033 J	0.012 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1160	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated	0.017	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.017 J	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1105	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1068	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated	2.56	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	2 J	0.56 J		< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-B1219	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1251	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated	0.076	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U		0.017 J	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated	1.7	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U		0.43 J	0.07 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1254	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated	0.44	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U		0.11 J	0.02 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B1244	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated	0.095	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	0.065 J	0.03 J	< 0.0055 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1224	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated	14.44	< 0.057 U	< 0.11 U	< 0.1 U	< 0.1 U	8.9 J	5.1 J	0.44 J	< 0.12 U	< 0.085 U
Rear Parking Lot	SSHS-B1206	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated	1.126	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.49 J	0.55 J	0.086 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1233	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated	0.393	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.15 J	0.21 J	0.033 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1235	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated	0.132	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.076 J	0.044 J	0.012 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1236	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated	2.6	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.6 J	0.9 J	0.1 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1220	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated	0.61	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.61	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1223	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated	1.412	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	1 J	0.34 J	0.072 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B1236	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated	0.755	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47 J	0.26 J	0.025 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1237	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated	3.52	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	1.1 J	0.22 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1205	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated	ND	< 0.0068 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0059 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1162	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated	0.353	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.25 J	0.089 J	0.014 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1086	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated	0.923	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.48 J	0.37 J	0.073 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-B1122	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated	3.11	< 0.0073 U	< 0.014 U	< 0.013 U	< 0.013 U	2.2 J	0.91 J	< 0.0063 U	< 0.016 U	< 0.011 U
Rear Parking Lot	SSHS-B1247	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated	4	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	4	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1249	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B1249	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-B1104	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated	0.073	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.048 J	0.025 J	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1091	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated	0.022	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.022	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated	0.183	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.089 J	0.094 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated	0.173	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.096 J	0.058 J	0.019 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated	0.075	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	0.049 J	0.026 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1094	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated	0.037	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B1193	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated	0.103	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.073 J	0.03 J	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1158	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-B1198	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated	0.57	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17 J	0.4 J	< 0.0053 U	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-B1255	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated	7.56	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	4.9 J	2.4 J	0.26 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1257	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated	63.3	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	45 J	17 J	1.3 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-SW-011	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated	40	< 0.13 U	< 0.26 U	< 0.24 U	< 0.24 U	28 J	11 J	1 J	< 0.28 U	< 0.19 U
Rear Parking Lot	SSHS-SW-003	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated	0.755	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.43 J	0.28 J	0.045 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-SW-005	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated	0.825	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.32 J	0.45 J	0.055 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-SW-006	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated	27.92	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	20 J	7.3 J	0.62 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-SW-007	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated	6.37	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4.5 J	1.7 J	0.17 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-SW-008	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated	5.9	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	2.2 J	3.7 J		< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-SW-009	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated	16.97	< 0.031 U	< 0.061 U	< 0.056 U	< 0.056 U	12 J	4.6 J	0.37 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-BSW-001	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	17.87	< 0.033 U	< 0.065 U	< 0.06 U	< 0.06 U	12 J	5.3 J	0.57 J	< 0.071 U	< 0.049 U
Rear Parking Lot	SSHS-SW-018	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated	54.5	< 0.12 U	< 0.23 U	< 0.21 U	< 0.21 U	37 J	16 J	1.5 J	< 0.25 U	< 0.17 U
Rear Parking Lot	SSHS-SW-021	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated	11.85	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	7.8 J	3.7 J	0.35 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-SW-019	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated	48.1	< 0.12 U	< 0.23 U	< 0.21 U	< 0.21 U	34 J	13 J	1.1 J	< 0.25 U	< 0.17 U
Rear Parking Lot	SSHS-SW-020	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated	8.45	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	5.5 J	2.7 J	0.25 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	106.3	< 0.23 U	< 0.47 U	< 0.43 U	< 0.43 U	72 J	32 J	2.3 J	< 0.51 U	< 0.35 U
Rear Parking Lot	SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	2.83	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	1.6 J	1.1 J	0.13 J	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-B1394	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated	0.16	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.068	0.064	0.028	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-WWS_7_21	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated	0.529	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.33	0.16	0.039	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-SS2_7_21	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated	4.41	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	2.8	1.3	0.31	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-SS1_7_21	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated	2.55	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	0.93	0.32	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-WWN_7_21	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated	1.22	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.64	0.45	0.13	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated	0.118	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.067	0.051	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated	0.64	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.17		< 0.013 U	< 0.0092 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated	0.3	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.19	0.11	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated	0.13	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.09	0.04	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated	0.57	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.27	0.3		< 0.013 U	< 0.0091 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	0.724	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.4	0.3	0.024	< 0.013 U	< 0.009 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	1.47	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.37		< 0.013 U	< 0.009 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	0.206	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.13	0.076	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	0.133	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.091	0.042	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2240	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	0.056	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.042	0.014 J	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2244	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	0.51	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24	0.27		< 0.013 U	< 0.0089 U
Football Field	SSHS-B2230	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated	6.43	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6	2.6	0.23	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2231	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated	0.552	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.4	0.14	0.012 J,p	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2234	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated	0.65	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.46	0.19	< 0.0055 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2235	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated	0.143	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.1	0.043	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2235	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated	0.189	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13	0.059	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated	0.0622	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.032	0.022	0.0082 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated	0.0893	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051	0.03	0.0083 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated	0.073	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.046	0.027	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated	0.047	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.018	0.029	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2189	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated	0.066	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.04	0.026	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated	0.079	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.049	0.03	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated	0.123	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.075	0.048	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated	0.176	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11	0.066	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2232	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated	0.66	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.48	0.18	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated	0.66	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.48	0.18	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated	0.07	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	0.033	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	0.135	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.053	0.052	0.03	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	0.06	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.038	0.022	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	0.119	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.073	0.046	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	0.073	< 0.0058 U	< 0.011 U	< 0.011 U	< 0.011 U	0.044	0.029	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	0.09	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.058	0.032	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2221	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	1.593	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1	0.45	0.043	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	0.041	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.02	0.021	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2245	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	1.169	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.72	0.41	0.039	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2185	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated	0.527	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.34	0.15	0.037	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated	0.492	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.34	0.12	0.032	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated	0.344	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.16	0.16	0.024	< 0.013 U	< 0.009 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated	0.41	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.26	0.15	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2185	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated	0.459	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.28	0.14	0.039	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated	0.182	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.093	0.067	0.022	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated	0.214	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.14	0.074	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated	0.29	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13	0.16	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated	0.29	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17	0.12	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated	1.273	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.62	0.58	0.073	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated	0.63	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.4	0.23	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated	0.249	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18	0.057	0.012 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated	0.42	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.17	0.25	< 0.0056 U	< 0.014 U	< 0.0095 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2185	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated	0.406	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.25	0.12	0.036	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2186	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated	0.0675	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.039	0.022	0.0065 J	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2187	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	0.202	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.13	0.072	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2188	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	0.014	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.014 J	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2188	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	0.014	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	0.014 J	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2189	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated	0.2	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11	0.09	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2191	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated	0.666	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.3	0.32	0.046	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated	0.59	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38	0.21	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2232	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated	0.07	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.039	0.031	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2233	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated	0.061	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.032	0.029	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2245	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-nat_gas_2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated	1.18	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.76 J	0.32 J	0.1 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-nat_gas_1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated	0.451	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.23 J	0.17 J	0.051 J	< 0.013 U	< 0.0087 U
Rear Parking Lot	SSHS-B1373	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated	2.5	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	2.5	< 0.0058 U	< 0.014 U	< 0.01 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	ND	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated	0.184	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.063	0.089	0.032	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated	0.016	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.016 J	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated	0.089	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.052	0.037	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated	0.097	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.041	0.04	0.016 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2072	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2073	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	0.096	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.035	0.044	0.017 J	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	0.0452	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.021	0.018 J	0.0062 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	0.114	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.067	0.047	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	0.034	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.019	0.015 J	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated	0.035	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	0.035	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	1.04	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.52	0.38	0.14	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2128	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated	0.605	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.32	0.23	0.055	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	0.163	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.093	0.056	0.014 J	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated	0.158	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.091	0.067	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	0.167	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.047	0.083	0.037	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2216	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated	0.042	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.025	0.017 J,p	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated	0.1078	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.061	0.038	0.0088 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated	ND	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated	0.0556	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.027	0.02	0.0086 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated	0.02	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.02	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated	0.041	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.024	0.017 J	< 0.0054 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated	0.0293	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.022	< 0.013 U	0.0073 J	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated	0.425	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.2	0.17	0.055	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2091	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated	0.101	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.042	0.045	0.014 J	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	0.062	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.028	0.023	0.011 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated	0.037	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.021	0.016 J	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2143	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated	0.071	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.04	0.031	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	0.019	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.019	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2194	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated	0.145	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.058	0.077	0.01 J	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated	0.18	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.074	0.079	0.027	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2070	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2089	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2091	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated	0.0611	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.029	0.024	0.0081 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2108	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2109	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated	0.221	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.13	0.068	0.023	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2110	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated	0.017	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.017 J	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2127	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2128	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2129	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2143	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2194	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated	0.105	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.039	0.046	0.02	< 0.013 U	< 0.009 U
Football Field	SSHS-B2216	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated	0.043	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.043	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated	0.688	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.19	0.43	0.068	< 0.015 U	< 0.01 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated	ND	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated	0.049	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.024	0.025	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2213	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated	0.062	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.062	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated	0.14	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	0.14	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated	0.055	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.04	0.015 J	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	0.66	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.47	0.19	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2224	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	0.108	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.069	0.039	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	0.163	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.12	0.032	0.011 J	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	4.176	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	3	1.1	0.076	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated	6.47	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.5	1.8	0.17	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	ND	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	4.03	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3	2.5	0.23	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2027	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	ND	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0058 U	< 0.014 U	< 0.01 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	0.152	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.059	0.093	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	ND	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2226	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	0.046	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.046	< 0.015 U	< 0.0061 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2025	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated	0.456	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.068	0.29	0.098	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated	0.444	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.1	0.27	0.074	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	0.46	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.26	0.2	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated	0.32	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.32	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated	ND	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0059 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated	0.1	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	0.1	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2026	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated	1.21	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.17	0.89	0.15	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated	0.73	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.62	0.11	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	< 0.014 U	< 0.006 U	< 0.015 U	< 0.01 U
Football Field	SSHS-B2192	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated	0.22	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.12	0.1	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated	0.142	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.076	0.066	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated	0.04	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.04	< 0.0058 U	< 0.014 U	< 0.0099 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated	1.38	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.98	0.29	0.11	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated	0.237	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.17	0.067	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated	0.018	< 0.0061 U	0.018 J,p	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated	0.448	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17	0.19	0.088	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated	ND	< 0.0073 U	< 0.015 U	< 0.013 U	< 0.013 U	< 0.018 U	< 0.015 U	< 0.0064 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated	0.415	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.15	0.23	0.035	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated	0.28	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.23	0.05	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated	0.014	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.014 J	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated	0.181	< 0.0071 U	< 0.014 U	< 0.013 U	< 0.013 U	0.13	0.038	0.013 J	< 0.015 U	< 0.011 U
Football Field	SSHS-B2025	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated	0.021	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.021	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2026	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated	0.31	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.27	0.04	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2028	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated	0.045	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.023	0.022	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2050	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2192	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated	0.075	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	0.038	< 0.0053 U	< 0.013 U	< 0.009 U
Football Field	SSHS-B2195	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated	0.023	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.023	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2195	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated	0.013	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.013 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2213	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated	0.501	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	0.45	0.051	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2214	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2215	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2224	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated	0.33	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.24	0.068	0.022	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2227	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated	3.568	< 0.0063 U,F1	< 0.013 U	< 0.012 U	< 0.012 U	2.5	0.99	0.078	< 0.014 U	< 0.0094 U
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated	0.022	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	0.022	< 0.0055 U	< 0.013 U	< 0.0093 U
Northern Athletic Field	SSHS-B2024	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-GS3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated	7.6	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	5.2 J	2.2 J	0.2 J	< 0.015 U	< 0.01 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-GS2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated	48	< 0.063 U	< 0.13 U	< 0.12 U	< 0.12 U	33 J	14 J	1 J	< 0.14 U	< 0.094 U
Rear Parking Lot	SSHS-EN5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated	3.18	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2 J	1.7 J	0.28 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-GS4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated	5.24	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	3.6 J	1.5 J	0.14 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-EN4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated	0.848	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.56 J	0.22 J	0.068 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-SN3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated	0.611	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.32 J	0.2 J	0.091 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-EN1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated	0.881	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.39 J	0.44 J	0.051 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-EN3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated	2.88	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	2 J	0.73 J	0.15 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-EN4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated	0.595	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.39 J	0.16 J	0.045 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-GS3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated	1.045	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.7 J	0.26 J	0.085 J	< 0.014 U	< 0.0093 U
Rear Parking Lot	SSHS-EN2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated	2.82	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.8 J	0.89 J	0.13 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-GS4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated	2.543	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	1.6 J	0.86 J	0.083 J	< 0.016 U	< 0.011 U
Rear Parking Lot	SSHS-SN5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated	0.194	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.11 J	0.059 J	0.025 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-EN3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated	4.07	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	2.9 J	0.97 J	0.2 J	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-GS2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated	3.45	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	2.3 J	1 J	0.15 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-ES5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated	5.83	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	3.6 J	2 J	0.23 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-ES3-2		7/26/2018	-	852.70	-	846.63	5.4 ft	6.07 ft	-	Not Excavated	1.413	<0.0064	<0.013	<0.012	<0.012	0.89	0.36	0.13	<0.0095	<0.014
Rear Parking Lot	SSHS-GS3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated	2.31	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1 J	1.2 J	0.11 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-ES4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated	2.31	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.77 J	1.4 J	0.14 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-SN4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated	0.9	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.46 J	0.31 J	0.13 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-EN3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated	1.9	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2 J	0.53 J	0.17 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-GS4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated	2.28	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	1.5 J	0.72 J	0.06 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-EN4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated	0.377	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.17 J	0.15 J	0.057 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-GS3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated	0.372	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.13 J	0.19 J	0.052 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-GS2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated	2.016	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.4 J	0.58 J	0.036 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-EN3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated	0.81	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.32 J	0.49 J	< 0.0056 U	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-EN2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated	4.89	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	3.2 J	1.3 J	0.39 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-BE-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated	7.51	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	5.2 J	1.8 J	0.51 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-BE-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated	1.48	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.66 J	0.59 J	0.23 J	< 0.015 U	< 0.01 U
Football Field	SSHS-B2031	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated	0.071	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.047	0.024	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated	0.14	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.086	0.041	0.013 J	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated	0.045	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	0.026	0.019	< 0.005 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated	0.159	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.084	0.061	0.014 J,p	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2071	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated	ND	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated	0.561	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.5	0.061	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2032	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	ND	< 0.0056 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.0049 U	< 0.012 U	< 0.0083 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	ND	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0093 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	0.1	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.034	0.054	0.012 J,p	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	1.12	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	1	0.12	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	ND	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0052 U	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated	6.2	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.2	2		< 0.013 U	< 0.0089 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated	0.4	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.23	0.13	0.04	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2217	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated	0.865	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.49	0.31	0.065	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated	0.31	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.14	0.17	< 0.0057 U	< 0.014 U	< 0.0097 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated	0.175	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.1	0.059	0.016 J	< 0.013 U	< 0.0087 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated	ND	< 0.0075 U	< 0.015 U	< 0.014 U	< 0.014 U	< 0.018 U	< 0.016 U	< 0.0065 U	< 0.016 U	< 0.011 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated	1.12	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.34	0.78	< 0.0056 U	< 0.014 U	< 0.0096 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated	0.276	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.15	0.097	0.029	< 0.013 U	< 0.0091 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated	1.6	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	1.4	0.2	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2031	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated	0.148	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.089	0.047	0.012 J	< 0.012 U	< 0.0085 U
Football Field	SSHS-B2051	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated	ND	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.014 U	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2071	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2090	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated	0.106	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.018 J	0.062	0.026	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2190	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated	0.167	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.086	0.061	0.02	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2217	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated	2.26	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.015 U	2	0.26	< 0.013 U	< 0.009 U
Football Field	SSHS-B2228	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	< 0.014 U	< 0.006 U	< 0.015 U	< 0.01 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.86	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.41	0.34	0.11	< 0.014 U	< 0.0095 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0086 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	ND	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	< 0.014 U	< 0.012 U	< 0.005 U	< 0.012 U	< 0.0085 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated	0.545	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.19	0.27	0.085	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated	ND	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.015 U	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated	ND	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	< 0.012 U	< 0.0051 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated	0.061	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.031	0.03	< 0.0051 U	< 0.012 U	< 0.0086 U
Rear Parking Lot	SSHS-W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated	3.71	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	2.3 J	1.2 J	0.21 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated	0.2059	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.15 J	0.048 J	0.0079 J	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated	0.18	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.1 J	0.07 J	0.01 J	< 0.013 U	< 0.0089 U
Rear Parking Lot	SSHS-W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated	1.7	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.79 J	0.65 J	0.26 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated	0.612	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.38 J	0.18 J	0.052 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated	1.68	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	1.1 J	0.44 J	0.14 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated	0.813	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.51 J	0.24 J	0.063 J	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated	0.239	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.14 J	0.076 J	0.023 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated	0.292	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.18 J	0.085 J	0.027 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated	1.28	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.99 J	0.23 J	0.06 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated	1.59	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.62 J	0.69 J	0.28 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated	1.95	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	1.2 J	0.58 J	0.17 J	< 0.015 U	< 0.01 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated	1.68	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	1.1 J	0.46 J	0.12 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated	1.26	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.54 J	0.57 J	0.15 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated	1.093	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.72 J	0.29 J	0.083 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated	0.84	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.27 J	0.41 J	0.16 J	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated	0.596	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	0.39 J	0.17 J	0.036 J	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-B1204	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated	2.12	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.5 J	0.62 J		< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1245	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated	20.2	< 0.06 U	< 0.12 U	< 0.11 U	< 0.11 U	16 J	4.2 J		< 0.13 U	< 0.089 U
Rear Parking Lot	SSHS-B1252	SSHS-B1252-SUB-6-8	7/28/2018	849.24	849.02	-0.22	-	6 - 8 ft	5.78-7.78 ft	180-80273-1	Not Excavated	42.9	< 0.12 U	< 0.24 U	< 0.22 U	< 0.22 U	32 J	9.3 J	1.6 J	< 0.26 U	< 0.18 U
Rear Parking Lot	SSHS-B1245	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated	19.31	< 0.064 U	< 0.13 U	< 0.12 U	< 0.12 U	15 J	3.7 J	0.61 J	< 0.14 U	< 0.095 U
Rear Parking Lot	SSHS-B1253	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated	14.8	< 0.059 U	< 0.12 U	< 0.11 U	< 0.11 U	11 J	3.2 J	0.6 J	< 0.13 U	< 0.088 U
Rear Parking Lot	SSHS-E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated	17.41	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	13 J	3.8 J	0.61 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated	6.8	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	4.8 J	2 J		< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated	258.2	< 0.31 U	< 0.61 U	< 0.56 U	< 0.57 U	200 J	51 J	7.2 J	< 0.66 U	< 0.46 U
Rear Parking Lot	SSHS-E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated	4.2	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	3 J	1 J	0.2 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated	19.26	< 0.061 U	< 0.12 U	< 0.11 U	< 0.11 U	14 J	4.5 J	0.76 J	< 0.13 U	< 0.091 U
Rear Parking Lot	SSHS-E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated	13.17	< 0.057 U	< 0.11 U	< 0.1 U	< 0.11 U	9.9 J	2.8 J	0.47 J	< 0.12 U	< 0.086 U
Rear Parking Lot	SSHS-B1346	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated	1.96	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.3 J	0.53 J	0.13 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated	1.12	< 0.006 U	< 0.012 U	< 0.011 U	< 0.011 U	0.59 J	0.4 J	0.13 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated	0.382	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	0.13 J	0.17 J	0.082 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated	0.384	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.24 J	0.11 J	0.034 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated	12.74	< 0.062 U	< 0.12 U	< 0.11 U	< 0.11 U	9.1 J	3 J	0.64 J	< 0.13 U	< 0.093 U
Rear Parking Lot	SSHS-B1299	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated	0.248	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.17 J	0.063 J	0.015 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-C-E-P-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated	0.1312	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.085 J	0.039 J	0.0072 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1303	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated	2.28	< 0.0063 U	< 0.013 U	< 0.012 U	< 0.012 U	1.5 J	0.62 J	0.16 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-C-E-S-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated	2.39	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	1.7 J	0.57 J	0.12 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-C-E-S-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated	0.088	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.069 J	0.019 J	< 0.0059 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-C-E-S-1	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated	4.25	< 0.007 U	< 0.014 U	< 0.013 U	< 0.013 U	3.7 J	0.46 J	0.09 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-RS-5		8/4/2018	-	851.79	-	845.15	6.6 ft	6.64 ft	-	Not Excavated	1.41	<0.0063U	<0.012U	<0.011U	<0.012U	0.83J	0.46J	0.088J	<0.0093U	<0.013U
Rear Parking Lot	SSHS-RS-3		8/4/2018	-	851.71	-	843.07	8.6 ft	8.64 ft	-	Not Excavated	1.16	<0.0062U	<0.012U	<0.011U	<0.011U	0.79J	0.26J	0.079J	<0.0093U	<0.013U
Rear Parking Lot	SSHS-B-F-E-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated	7.63	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	5.4 J	1.7 J	0.53 J	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-B-F-S-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated	0.642	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.39 J	0.21 J	0.042 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated	0.302	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.16 J	0.11 J	0.032 J	< 0.014 U	< 0.0097 U
Rear Parking Lot	SSHS-N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated	0.568	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.34 J	0.18 J	0.048 J	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated	0.863	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.61 J	0.21 J	0.043 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated	0.228	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.17 J	0.047 J	0.011 J	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated	13.71	< 0.031 U	< 0.061 U	< 0.056 U	< 0.056 U	10 J	2.8 J	0.91 J	< 0.066 U	< 0.046 U
Rear Parking Lot	SSHS-CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated	5.32	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	4 J	0.98 J	0.34 J	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated	0.1344	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.088 J	0.037 J	0.0094 J	< 0.013 U	< 0.009 U
Rear Parking Lot	SSHS-WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated	0.204	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.15 J	0.042 J	0.012 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated	0.916	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	0.66 J	0.2 J	0.056 J	< 0.012 U	< 0.0085 U
Rear Parking Lot	SSHS-WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated	1.542	< 0.0057 U	< 0.011 U	< 0.01 U	< 0.01 U	1.2 J	0.27 J	0.072 J	< 0.012 U	< 0.0084 U
Rear Parking Lot	SSHS-P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated	0.44	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.32 J	0.088 J	0.032 J	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated	0.188	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.15 J	0.038 J	< 0.0058 U	< 0.014 U	< 0.0099 U
Rear Parking Lot	SSHS-P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated	0.1987	< 0.0067 U	< 0.013 U	< 0.012 U	< 0.012 U	0.15 J	0.04 J	0.0087 J	< 0.014 U	< 0.01 U
Rear Parking Lot	SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated	0.029	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.029	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0093 U
Rear Parking Lot	SSHS-SS-07_8_20	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated	1.353	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.93	0.38	0.043	< 0.013 U	< 0.0088 U
Rear Parking Lot	SSHS-SS-12_8_20	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated	0.816	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.5	0.27	0.046	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-SS-14_8_20	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated	0.037	< 0.0063 U	< 0.012 U	< 0.011 U	< 0.012 U	0.037	< 0.013 U	< 0.0055 U	< 0.014 U	< 0.0094 U
Rear Parking Lot	SSHS-SS-16_8_20	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated	ND	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	< 0.014 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-SS-04_8_20	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated	12.29	< 0.032 U	< 0.063 U	< 0.058 U	< 0.058 U	8.2	3.7	0.39	< 0.068 U	< 0.047 U
Rear Parking Lot	SSHS-SS-03_8_20	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated	3.17	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	2.1	0.97	0.1	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-SS-05_8_20	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated	2.286	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	1.6	0.63	0.056	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-SS-02_8_20		8/20/2018	-	848.51	-	842.58	6-8 ft	5.93 ft	-	Not Excavated	12.45	<0.032U	<0.063U	<0.058U	<0.058U	8.2	3.7	0.39	<0.047U	<0.068U
Rear Parking Lot	SSHS-SS-06_8_20	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated	1.4	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.95	0.41	0.04	< 0.014 U	< 0.0095 U
Rear Parking Lot	SSHS-SS-13_8_20	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated	ND	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	< 0.013 U	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-SS-10_8_20	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated	22.35	< 0.18 U	< 0.18 U	< 0.18 U	< 0.18 U	16	5.7	0.65	< 0.18 U	< 0.18 U
Rear Parking Lot	SSHS-SS-11_8_20	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated	11.85	< 0.093 U	< 0.093 U	< 0.093 U	< 0.093 U	8.5	2.9	0.45	< 0.093 U	< 0.093 U
Rear Parking Lot	SSHS-SS-15_8_20	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated	1.069	< 0.02 U	< 0.02 U	< 0.02 U	< 0.02 U	0.74	0.3	0.029	< 0.02 U	< 0.02 U
Rear Parking Lot	SSHS-B1502	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated	0.029	< 0.0061 U	< 0.012 U	< 0.011 U	< 0.011 U	0.029	< 0.013 U	< 0.0053 U	< 0.013 U	< 0.0091 U
Rear Parking Lot	SSHS-B1500	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated	0.136	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.098	0.038	< 0.0054 U	< 0.013 U	< 0.0092 U
Football Field	SSHS-B2362	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated	22.07	< 0.063 U	< 0.13 U	< 0.11 U	< 0.12 U	18	3.7	0.37	< 0.14 U	< 0.094 U
Football Field	SSHS-B2329	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated	0.13	< 0.0065 U	< 0.013 U	< 0.012 U	< 0.012 U	0.093	0.037	< 0.0057 U	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2368	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated	0.069	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.012 U	0.046	0.023	< 0.0055 U	< 0.013 U	< 0.0093 U
Football Field	SSHS-B2369	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated	0.68	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	0.49	0.19	< 0.0056 U	< 0.014 U	< 0.0095 U
Football Field	SSHS-B2385	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated	1.51	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.012 U	< 0.017 U	1.2	0.31	< 0.015 U	< 0.01 U
Football Field	SSHS-B2386	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated	0.088	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	< 0.014 U	0.071	0.017 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2385	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated	0.466	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.38	0.086	< 0.014 U	< 0.0098 U
Football Field	SSHS-B2386	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated	7.45	< 0.032 U	< 0.063 U	< 0.058 U	< 0.058 U	5.3	1.8	0.35	< 0.068 U	< 0.047 U
Football Field	SSHS-B2532	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated	0.015	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.015 J	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2523	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated	0.073	< 0.0058 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051 J	0.022 J	< 0.0051 U	< 0.012 U	< 0.0086 U
Football Field	SSHS-B2534	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated	0.458	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.2 J	0.22 J	0.038 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2534	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated	0.126	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051 J	0.062 J	0.013 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2535	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated	0.2334	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.16 J	0.066 J	0.0074 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2724	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated	0.15	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.11 J	0.04 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2679	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated	28.69	< 0.058 U	< 0.064 U	< 0.044 U	< 0.026 U	21 J	6.7 J	0.99 J	< 0.063 U	< 0.024 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated	4.05	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.9 J	0.86 J	0.29 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2761	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated	20.4	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	13 J	5 J	2.4 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B2756	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated	0.3	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.08 J	0.22 J	< 0.005 U	< 0.0062 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2756	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated	0.168	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.048 J	0.12 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2759	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated	0.098	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.04 J	0.058 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B2755	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	14.2	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	11 J	2.7 J	0.5 J	< 0.034 U	< 0.013 U
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	0.191	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.14 J	0.051 J	< 0.0052 UJ	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B2683	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2773	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated	0.3	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	0.17 J	0.13 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2774	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated	0.1501	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0061 J	0.076 J	0.068 J	< 0.0061 U	< 0.0024 U
Football Field	SSHS-B2773	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated	0.51	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.29 J	0.22 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2774	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated	0.073	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.036 J	0.037 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B2619	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated	9.83	< 0.032 U	< 0.034 U	< 0.024 U	< 0.014 U	6.7 J	2.3 J	0.83 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B2620	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated	8.06	< 0.03 U	< 0.033 UJ	< 0.023 U	< 0.014 U	6.1 J	1.5 J	0.46 J	< 0.033 U	< 0.012 UJ
Football Field	SSHS-B2620	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated	4.48	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.1 J	1 J	0.38 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2648	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated	0.495	< 0.0067 U	< 0.0073 U	0.23 J	< 0.003 U	0.21 J	0.055 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B2676	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated	0.077	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.057 J	0.02 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2685	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated	0.238	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.18 J	0.046 J	0.012 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2649	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated	2.301	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.9 J	0.34 J	0.061 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2700	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated	6.59	< 0.032 U	< 0.034 U	< 0.024 U	< 0.014 U	5 J	1.4 J	0.19 J	< 0.034 U	< 0.013 U
Football Field	SSHS-B2811	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated	0.253	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.18 J	0.073 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2812	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B2813	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2814	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated	2.13	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.3 J	0.57 J	0.26 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2815	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2816	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2817	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B2818	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated	0.0071	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.0071 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2671	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated	2.51	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.8 J	0.51 J	0.2 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B2639	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated	23.2	< 0.031 U	< 0.033 U	< 0.023 U	< 0.014 U	18 J	4 J	1.2 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B2642	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated	6.01	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	4.6 J	1.1 J	0.31 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2643	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated	0.61	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.09 J	0.35 J	0.17 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B2754	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated	2.5	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.9 J	0.46 J	0.14 J	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B2754	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated	2.73	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	2 J	0.56 J	0.17 J	< 0.0065 U	< 0.0025 U
Rear Parking Lot	CS-01-19	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated	4.09	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.6	1.2	0.29	< 0.0063 U	< 0.0024 U
Rear Parking Lot	CS-02-19	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated	0.591	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.36	0.18	0.051	< 0.0073 U	< 0.0028 U
Rear Parking Lot	CS-03-19	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated	0.1462	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.097	0.041	0.0082 J	< 0.0063 U	< 0.0024 U
Rear Parking Lot	CS-04-19	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated	1.61	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.99	0.47	0.15	< 0.0067 U	< 0.0025 U
Rear Parking Lot	CS-05-19	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated	3.1	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.2	1.5	0.4	< 0.0067 U	< 0.0025 U
Rear Parking Lot	CS-06-19	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated	1.82	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.84	0.73	0.25	< 0.0069 U	< 0.0026 U
Rear Parking Lot	CS-06-19	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated	1.87	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.88	0.78	0.21	< 0.0069 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated	0.096	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.049 J	0.031 J	0.016 J	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated	0.15	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.089 J	0.04 J	0.021 J	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated	0.098	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.04 J	0.039 J	0.019 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated	0.039	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.022 J	0.017 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated	0.101	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.072 J	0.029 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated	0.99	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.58 J	0.27 J	0.14 J	< 0.006 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated	9.2	< 0.056 U	< 0.061 U	< 0.042 U	< 0.025 U	7.3 J	1.9 J	< 0.049 U	< 0.061 U	< 0.023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated	0.183	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.12 J	0.063 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated	0.209	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.11 J	0.064 J	0.035 J	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated	0.612	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.45 J	0.11 J	0.052 J	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated	0.62	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.4 J	0.17 J	0.05 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated	1.234	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.96 J	0.19 J	0.084 J	< 0.0067 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated	2.77	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	2.1 J	0.54 J	0.13 J	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated	0.229	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.12 J	0.08 J	0.029 J	< 0.0069 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated	0.024	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.024	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated	0.107	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.041 J	0.051 J	0.015 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-B010	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated	0.053	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.03 J	0.023 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated	0.014	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 UJ	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated	0.142	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.078 J	0.047 J	0.017 J	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated	0.1009	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.057 J	0.035 J	0.0089 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-B011	SSHS-IRM3-B011-C	7/24/2019	-	855.79	-	846.77	8 - 10 ft	9.02 ft	180-93173-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110	SSHS-IRM3-S110-C	7/24/2019	-	855.75	-	846.89	8 - 10 ft	8.86 ft	180-93173-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-IRM3-B016	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated	2.68	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.8 J	0.7 J	0.18 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-IRM3-B026	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated	1.33	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.79 J	0.39 J	0.15 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-IRM3-B027	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated	2.64	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.8 J	0.66 J	0.18 J	< 0.0068 U	< 0.0026 U
Football Field	SSHS-IRM3-S156C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated	0.087	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.06 J	0.027 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S188	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated	0.299	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.2 J	0.078 J	0.021 J	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated	0.144	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.096 J	0.048 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated	0.243	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.16 J	0.062 J	0.021 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated	2.54	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.96 J	1.2 J	0.38 J	< 0.0067 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S113	SSHS-IRM3-S113-C	7/26/2019	-	855.43	-	846.07	8 - 10 ft	9.36 ft	180-93321-1	Not Excavated	0.155	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.1 J	0.039 J	0.016 J	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S114	SSHS-IRM3-DUP1-07-26-2019-C	7/26/2019	-	855.50	-	846.50	8 - 10 ft	9 ft	180-93321-1	Not Excavated	1.088	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.66 J	0.35 J	0.078 J	< 0.0064 U	< 0.0024 U

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-IRM3-S114	SSHS-IRM3-S114-C	7/26/2019	-	855.57	-	846.48	8 - 10 ft	9.09 ft	180-93419-1	Not Excavated	0.1286	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.082 J	0.039 J	0.0076 J	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S112C	SSHS-IRM3-S112C-C	7/30/2019	-	855.55	-	846.60	8 - 10 ft	8.95 ft	180-93419-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S112D	SSHS-IRM3-S112D-C	7/30/2019	-	855.59	-	847.31	8 - 10 ft	8.28 ft	180-93419-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-IRM3-S201	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated	5.79	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	4.1 J	1.4 J	0.29 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	3.04	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	2.3 J	0.57 J	0.17 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated	5.92	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	4.3 J	1.2 J	0.42 J	< 0.0067 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 UJ	< 0.0051 UJ	< 0.0049 J	< 0.006 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated	0.39	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.28 J	0.086 J	0.024 J	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated	0.1309	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.087 J	0.036 J	0.0079 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM3-B108	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated	0.499	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.37 J	0.1 J	0.029 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-IRM3-B108	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated	1.534	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.2 J	0.27 J	0.064 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-IRM3-PIPE11	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	0.113	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.035	0.049	0.029	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S130	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated	0.225	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.14 J	0.064 J	0.021 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S152	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated	0.581	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.34 J	0.19 J	0.051 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-B009	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated	0.038	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.014 J	0.014 J	0.01 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-IRM3-S158	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated	4.17	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.2 J	1.4 J	0.57 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-IRM3-MH1DA	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated	0.348	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.23 J	0.096 J	0.022 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-PIPE10	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	0.32	< 0.0093 U	< 0.01 U	< 0.007 U	< 0.0042 U	0.14	0.12	0.06	< 0.01 U	< 0.0038 U
Football Field	SSHS-IRM3-S058	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated	0.166	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.11 J	0.039 J	0.017 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S084	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated	0.098	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.066 J	0.032 J	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S097	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated	1.236	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.78 J	0.36 J	0.096 J	< 0.0059 U	< 0.0023 U
Football Field	SSHS-IRM3-B107	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated	0.125	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.078 J	0.034 J	0.013 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-IRM3-B110	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated	0.074	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.054 J	0.02 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-IRM3-S098	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated	0.505	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.34 J	0.13 J	0.035 J	< 0.006 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	0.481	< 0.0082 U	< 0.009 U	< 0.0062 U	< 0.0037 U	0.3	0.12	0.061	< 0.0089 U,*	< 0.0034 U,*
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated	0.842	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.57 J	0.22 J	0.052 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated	0.027	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.018 J	0.009 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated	0.035	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.024 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	0.033	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated	0.0091	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.0091 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated	0.01	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.01 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated	0.079	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.056 J	0.023 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-IRM3-B014	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated	1.209	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.84 J	0.28 J	0.089 J	< 0.0059 U	< 0.0023 U
Football Field	SSHS-IRM3-B020	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated	1.588	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	1.1 J	0.39 J	0.098 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM3-B020	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated	2.7	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.9 J	0.65 J	0.15 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-B021	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated	0.543	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.38 J	0.13 J	0.033 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S141	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated	8.27	< 0.059 U	< 0.065 U	< 0.044 U	< 0.027 U	5.3 J	2.2 J	0.77 J	< 0.064 U	< 0.025 U
Football Field	SSHS-IRM3-S142	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S143	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated	0.038	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	0.027 J	0.011 J	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Football Field	SSHS-IRM3-S143	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated	0.19	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.13 J	0.046 J	0.014 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S144	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated	5.18	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	3.1 J	1.6 J	0.48 J	< 0.0059 U	< 0.0022 U
Football Field	SSHS-IRM3-S146	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated	1.89	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.3	0.48	0.11	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S148	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated	0.042	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.026	0.016 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-IRM3-S149	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U,F2	< 0.0064 U	< 0.0025 U
Football Field	SSHS-IRM3-S155	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated	1.088	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.72 J	0.28 J	0.088 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S159	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated	3.45	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	2.4 J	0.82 J	0.23 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S160	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated	0.91	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.32 J	0.35 J	0.24 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-IRM3-S161	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated	0.0087	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0087 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM3-S162	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated	0.015	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.015 J	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-IRM3-S150	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-IRM3-S156A	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated	0.237	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.16 J	0.065 J	0.012 J	< 0.0062 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-IRM3-S156B	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated	1.098	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.74 J	0.29 J	0.068 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-IRM3-S166	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated	0.154	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.079	0.055	0.02	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S167	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM3-S169	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM3-S170	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S172	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated	1.54	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.96	0.46	0.12	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM3-S174	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated	0.181	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.1 J	0.057 J	0.024 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-IRM3-S121	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM3-S127	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated	0.533	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	0.26	0.21	0.063	< 0.0076 U	< 0.0029 U
Football Field	SSHS-IRM3-S127	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated	0.025	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.025	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated	1.209	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.84 J	0.28 J	0.089 J	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated	0.186	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.12 J	0.051 J	0.015 J	< 0.006 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated	0.007	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.007 J	< 0.0051 UJ	< 0.0048 U	< 0.006 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated	0.418	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.29 J	0.093 J	0.035 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated	0.353	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.23 J	0.096 J	0.027 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated	1.206	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.74	0.37	0.096	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated	0.766	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.46 J	0.22 J	0.086 J	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated	0.58	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.45 J	0.099 J	0.031 J	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated	0.194	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.13 J	0.048 J	0.016 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated	0.755	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.51 J	0.2 J	0.045 J	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated	0.1182	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.075	0.034	0.0092 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated	0.171	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.1	0.059	0.012 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-IRM3-S058D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated	0.079	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.024 J	0.031 J	0.024 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-IRM3-S129F	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated	1.14	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.52 J	0.45 J	0.17 J	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022 J	0.007 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated	0.195	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.11 J	0.063 J	0.022 J	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated	0.034	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.024 J	0.01 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated	0.756	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.48 J	0.22 J	0.056 J	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated	0.956	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.63 J	0.26 J	0.066 J	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S132	SSHS-IRM3-S132-C	8/8/2019	-	855.57	-	846.91	8 - 10 ft	8.66 ft	180-93896-1	Not Excavated	0.042	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.027 J	0.015 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated	0.41	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.23 J	0.18 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated	0.163	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.076 J	0.062 J	0.025 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated	0.0132	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0059 J	0.0073 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	0.62	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.34 J	0.28 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated	0.013	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.013 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3077	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	0.0145	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0085 J	0.006 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	0.026	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.0096 J	0.01 J	0.0064 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated	0.62	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.35 J	0.27 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated	0.451	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.19 J	0.18 J	0.081 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated	0.013	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated	0.109	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.062 J	0.047 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated	0.091	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.025 J	0.04 J	0.026 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated	0.0307	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.015 J	0.0097 J	0.006 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated	0.66	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.38 J	0.28 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated	0.321	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.14 J	0.13 J	0.051 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated	0.0216	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0058 J	0.0085 J	0.0073 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated	0.0461	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022 J	0.016 J	0.0081 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated	0.36	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.2 J	0.16 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.004 U	< 0.005 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	SSHS-B3022	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3035	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3050	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3064	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated	0.085	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.036 J	0.034 J	0.015 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3065	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3078	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3098	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3099	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	0.541	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.29 J	0.2 J	0.051 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated	0.185	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.062 J	0.078 J	0.045 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated	0.0271	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.018 J	0.0091 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3075	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	0.164	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.065 J	0.069 J	0.03 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated	0.0161	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0071 J	0.009 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UJ	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UJ	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated	0.516	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.056 J	0.26 J	0.2 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated	0.035	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.021 J	0.014 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated	0.0073	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.0073 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UJ	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UJ	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 UJ	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated	0.0434	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0054 J	0.023 J	0.015 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated	0.825	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	0.3 J	0.085 J	< 0.0064 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated	0.0238	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.0072 J	0.0099 J	0.0067 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3006	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3018	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3019	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3020	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3031	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3032	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3033	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3046	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3047	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3048	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3061	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3062	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3063	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3074	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated	0.538	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.31 J	0.18 J	0.048 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3076	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3097	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 UJ	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 UJ	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	ND	< 0.0057 UJ	< 0.0062 UJ	< 0.0043 UJ	< 0.0026 UJ	< 0.0042 UJ	< 0.0053 UJ	< 0.005 UJ	< 0.0062 UJ	< 0.0024 UJ
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	0.034	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.021 J	0.013 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 UJ	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	0.008	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.008 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94902-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated	0.0081	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.0081 J	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated	0.007	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.007 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated	0.116	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.038 J	0.05 J	0.028 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94902-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated	0.011	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3060	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated	ND	< 0.0068 U	< 0.0073 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 UJ	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated	0.026	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3017	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3029	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3030	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3042	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3043	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated	0.035	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.024 J	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3044	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3045	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3057	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3058	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-S3060	SSHS-B3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3070	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3071	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3072	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 UJ	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3095	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated	0.076	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.053 J	0.023 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	0.054	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.036 J	0.018 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated	0.1	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.1	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated	0.022	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.022	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated	0.0068	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0068 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated	0.016	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.016 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated	0.0191	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0081 J	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated	0.042	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.026 J	0.016 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated	0.036	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.019 J	0.017 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated	0.0076	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	0.0076 J	< 0.0024 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	0.11	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.11	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3016	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3028	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	0.0553	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.029 J	0.02 J	0.0063 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated	0.022	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.011 J	0.011 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated	0.052	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.032 J	0.02 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	0.024	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.012 J	0.012 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	0.043	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.028 J	0.015 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated	0.179	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.092 J	0.087 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated	0.36	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.36	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated	0.0185	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.0095 J	0.009 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated	0.065	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.041 J	0.024 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated	0.089	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.045 J	0.044 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated	0.619	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.32 J	0.23 J	0.069 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated	0.093	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.042 J	0.051 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated	0.197	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.043 J	0.088 J	0.066 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated	1.208	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.72 J	0.44 J	0.048 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated	0.16	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.16	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated	0.0203	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.013 J	0.0073 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated	0.023	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated	0.0273	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0083 J	0.019 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated	1.13	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.77 J	0.3 J	0.06 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated	0.033	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.033	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated	0.0243	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.016 J	0.0083 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated	0.074	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.048 J	0.026 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated	0.0177	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0086 J	0.0091 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated	0.23	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14 J	0.078 J	0.012 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated	0.0089	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0089 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated	0.059	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.031 J	0.028 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated	0.0069	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0069 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated	0.937	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.57 J	0.33 J	0.037 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3004	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.011 J	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3005	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated	0.052	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.052	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated	0.01	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.01 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3054	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated	0.0279	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.018 J	0.0099 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated	0.172	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.11 J	0.062 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3069	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3079	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated	0.046	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.022 J	0.024 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3083	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated	0.032	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.018 J	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3084	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated	0.02	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.01 J	0.01 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated	0.039	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.025 J	0.014 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3094	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 UJ	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated	0.14	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.14	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated	0.242	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.16 J	0.082 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated	0.037	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.021 J	0.016 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	0.181	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.089 J	0.092 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	0.029	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.029	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	0.045	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.029 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated	0.16	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.16	< 0.0049 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated	0.368	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.28 J	0.088 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated	0.31	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.12 J	0.19 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated	0.095	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.067 J	0.028 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated	0.109	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.05 J	0.059 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated	0.42	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.42	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated	ND	< 0.0056 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated	0.015	< 0.006 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.015 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3003	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated	0.34	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.34	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3011	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3039	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated	0.072	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.046 J	0.026 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3068	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3214	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated	0.057	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.03 J	0.027 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	0.53	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.53	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated	0.216	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.13 J	0.071 J	0.015 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	1.89	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.2 J	0.56 J	0.13 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated	0.19	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.19 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated	0.37	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.37	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3002	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated	0.09	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	0.09	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3009	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3010	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3023	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3024	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3036	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3038	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3052	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated	2.83	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.8 J	0.9 J	0.13 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3053	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated	0.06	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.031 J	0.029 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3051	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3066	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3085	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3086	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B2943	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B2961	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B2925	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated	0.44	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.29 J	0.1 J	0.05 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	13.33	< 0.061 U	< 0.066 U	< 0.046 U	< 0.027 U	10 J	2.6 J	0.73 J	< 0.066 U	< 0.025 U
Football Field	SSHS-B2976	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	0.154	< 0.017 U	< 0.017 U	< 0.017 U	< 0.017 U	0.11 J	0.032 J	0.012 J	< 0.017 U	< 0.017 U
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	2.74	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2 J	0.59 J	0.15 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2916	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated	0.94	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.94	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.026 J	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3289	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated	0.039	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.013 J	0.016 J	0.01 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3290	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated	1.44	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.75 J	0.52 J	0.17 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated	25.06	< 0.059 U	< 0.064 U	< 0.044 U	< 0.027 U	17 J	7.2 J	0.86 J	< 0.064 U	< 0.024 U
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated	1.364	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.85 J	0.45 J	0.064 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3258	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated	0.0254	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.016 J	0.0094 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3270	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated	ND	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	< 0.0053 U	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3271	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated	0.059	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.043 J	0.016 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	0.122	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.034 J	0.052 J	0.036 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3273	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated	0.076	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.052 J	0.024 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3241	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated	0.045	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.035 J	0.01 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated	0.151	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.072 J	0.068 J	0.011 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	3.17	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	2.1 J	0.97 J	0.1 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3251	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated	0.58	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.42 J	0.16 J	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	0.4	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.21 J	0.19 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3254	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3242	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated	0.045	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.018 J	0.027 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	0.059	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.034 J	0.025 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	0.0074	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0074 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3229	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated	0.23	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.13 J	0.07 J	0.03 J	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3230	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated	0.193	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.044 J	0.081 J	0.068 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3231	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	1.64	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.89 J	0.53 J	0.22 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3237	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated	0.51	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.39 J	0.12 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3238	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated	0.082	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.06 J	0.022 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3240	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated	0.083	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.05 J	0.033 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	1.05	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.53 J	0.36 J	0.16 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated	0.357	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.18 J	0.12 J	0.057 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	0.021	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.013 J	0.008 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3233	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated	0.85	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.39 J	0.34 J	0.12 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3235	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3236	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	0.041	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.03 J	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated	0.016	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.016 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3103	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	0.029	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.017 J	0.012 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated	0.039	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.023 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3100	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated	0.0214	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.012 J	0.0094 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3101	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3102	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3104	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated	0.066	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	0.029 J	0.025 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated	0.129	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.049 J	0.051 J	0.029 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated	0.012	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	0.012 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3117	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3105	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3106	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3108	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3113	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3183	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3184	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated	ND	< 0.0056 U		< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.004 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated	0.037	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated	0.04	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.024 J	0.016 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated	0.05	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.03 J	0.02 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated	0.054	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.032 J	0.022 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3107	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3109	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated	0.0091	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.0091 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3110	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3111	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3112	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3116	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3118	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated	0.03	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.018 J	0.012 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated	1.367	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.9	0.37	0.097	< 0.0064 U	< 0.0025 U
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated	0.424	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.28	0.11	0.034	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated	0.036	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.023	0.013 J	< 0.0059 U	< 0.0074 U	< 0.0028 U
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated	0.975	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.66	0.26	0.055	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated	16.66	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	13	3.3	0.36	< 0.065 U	< 0.025 U
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated	251.2	< 0.66 U	< 0.72 U	< 0.49 U	< 0.3 U	200	47	4.2	< 0.71 U	< 0.27 U
Football Field	IRM4-B05	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated	4.1	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	2.7	1.2	0.2	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated	5.58	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	3.4	1.9	0.28	< 0.0062 U	< 0.0024 U
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated	4.47	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	2.6	1.7	0.17	< 0.0063 U	< 0.0024 U
Football Field	IRM4-B04	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated	0.074	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.051	0.023	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	0.089	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.067	0.022	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	0.1324	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.088	0.036	0.0084 J	< 0.0063 U	< 0.0024 U
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated	0.559	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.36	0.17	0.029	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated	50.6	< 0.32 U	< 0.35 U	< 0.24 U	< 0.14 U	34	14	2.6	< 0.35 U	< 0.13 U
Football Field	IRM4-B008	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated	0.16	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.097	0.049	0.014 J	< 0.0068 U	< 0.0026 U
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated	114.8	< 0.31 U	< 0.34 U	< 0.23 U	< 0.14 U	92	21	1.8	< 0.33 U	< 0.13 U
Football Field	IRM4-B014	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated	0.773	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.57	0.19	0.013 J	< 0.0066 U	< 0.0025 U
Football Field	IRM4-B013	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated	0.549	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.34	0.17	0.039	< 0.0068 U	< 0.0026 U
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated	19.2	< 0.061 U	< 0.067 U	< 0.046 U	< 0.028 U	16	3	0.3	< 0.066 U	< 0.025 U
Football Field	IRM4-B016	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated	2.496	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.8	0.64	0.056	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated	0.141	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.1	0.041	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4-B007	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated	14.86	< 0.061 U	< 0.066 U	< 0.045 U	< 0.027 U	12	2.7	0.16 J	< 0.065 U	< 0.025 U
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated	1.14	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.84	0.28	0.02	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated	0.031	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.016 J	0.015 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	0.15	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.075 J	0.055 J	0.02 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated	0.408	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.23 J	0.14 J	0.038 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	0.235	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.13 J	0.086 J	0.019 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated	0.113	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056 J	0.047 J	0.01 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	0.273	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.16 J	0.096 J	0.017 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	0.132	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.06 J	0.057 J	0.015 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	0.509	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.29 J	0.18 J	0.039 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	0.061	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022 J	0.039 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	0.167	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.06 J	0.077 J	0.03 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	0.849	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.52 J	0.28 J	0.049 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	0.1475	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.092 J	0.047 J	0.0085 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated	0.248	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.12 J	0.1 J	0.028 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated	1.336	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.8 J	0.45 J	0.086 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.023 J	0.014 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated	0.04	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.023 J	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3459	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated	0.245	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.12 J	0.1 J	0.025 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3461	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated	0.4	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.24 J	0.16 J		< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3464	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	0.0914	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.052 J	0.031 J	0.0084 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3472	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3473	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	5.36	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	3.4 J	1.7 J	0.26 J	< 0.0066 U	< 0.0025 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated	0.0358	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.026	0.0098 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM4-B009	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated	0.063	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.044	0.019	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated	4.73	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	3.3	1.3	0.13	< 0.0064 U	< 0.0025 U
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated	5.77	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	4.1	1.5	0.17	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated	3.71	< 0.0062 UT	< 0.0067 U	< 0.0046 U	< 0.0028 U	2.5	1.1	0.11	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated	0.1422	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.081	0.053	0.0082 J	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated	0.061	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.045	0.016 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S169	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated	0.896	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.48	0.32	0.096	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated	10.25	< 0.06 U	< 0.066 U	< 0.045 U	< 0.027 U	7.8	2.2	0.25	< 0.065 U	< 0.025 U
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated	1.682	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.2	0.43	0.052	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated	2.73	< 0.0062 UT	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.9	0.71	0.12	< 0.0067 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated	0.016	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.016 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated	1.046	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.7	0.3	0.046	< 0.0066 U	< 0.0025 U
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated	9.19	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	6.3	2.6	0.29	< 0.065 U	< 0.025 U
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated	0.487	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.35	0.12	0.017 J	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated	0.904	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.76	0.13	0.014 J	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated	4	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	2.7	1.2	0.1	< 0.0066 U	< 0.0025 U
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated	2.006	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.4	0.54	0.066	< 0.0061 U	< 0.0024 U
Football Field	IRM4-S123B	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated	6.291	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	4.5	1.7	0.091	< 0.0063 U	< 0.0024 U
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated	2.694	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.9	0.75	0.044	< 0.0063 U	< 0.0024 U
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated	0.219	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.16	0.059	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated	0.703	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.49	0.19	0.023	< 0.0067 U	< 0.0025 U
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated	1.453	< 0.0060 UT	< 0.0065 U	< 0.0045 U	< 0.0027 U	1	0.39	0.063	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated	2.621	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.8	0.75	0.071	< 0.0066 U	< 0.0025 U
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated	19.13	< 0.061 U	< 0.066 U	< 0.045 U	< 0.027 U	13	5.6	0.53	< 0.066 U	< 0.025 U
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated	5.58	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	3.7	1.7	0.18	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated	1.321	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.99	0.3	0.031	< 0.0062 U	< 0.0024 U
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated	0.0298	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.022	0.0078 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated	4.86	< 0.03 U	< 0.033 U	< 0.022 U	< 0.014 U	3.2	1.4	0.26	< 0.032 U	< 0.012 U
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated	2.044	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.5	0.5	0.044	< 0.0062 U	< 0.0024 U
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated	0.172	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.13	0.042	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated	5.91	< 0.031 U	< 0.034 U	< 0.024 U	< 0.014 U	3.9	1.7	0.31	< 0.034 U	< 0.013 U
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated	0.023	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.023	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated	12.09	< 0.057 U	< 0.063 U	< 0.043 U	< 0.026 U	8.4	3.3	0.39	< 0.062 U	< 0.024 U
Football Field	IRM4-S178B	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated	0.998	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.65	0.33	0.018	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S178A	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated	1.095	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.72	0.34	0.035	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated	101.6	< 0.3 U	< 0.32 U	< 0.22 U	< 0.13 U	77	23	1.6	< 0.32 U	< 0.12 U
Football Field	IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated	1.387	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.93	0.38	0.077	< 0.0067 U	< 0.0025 U
Football Field	IRM4-S197N	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated	3.77	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	2.5	1.1	0.17	< 0.0060 U	< 0.0023 U
Football Field	IRM4-S192N	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated	5.01	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.4	1.4	0.21	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S180S	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	IRM4-S181S	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated	1.095	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.69	0.31	0.095	< 0.0069 U	< 0.0027 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated	3.63	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	2.5	0.96	0.17	< 0.0067 U	< 0.0026 U
Football Field	IRM4-S184S	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated	1.565	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.2	0.3	0.065	< 0.0065 U	< 0.0025 U
Football Field	IRM4-S185S	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated	0.067	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.044	0.023	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	IRM4-S192N	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated	2.93	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2	0.76	0.17	< 0.0064 U	< 0.0024 U
Football Field	IRM4-S193N	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated	2.98	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	2.1	0.71	0.17	< 0.0059 U	< 0.0023 U
Football Field	IRM4-S194N	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated	2.78	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	1.9	0.71	0.17	< 0.0059 U	< 0.0023 U
Football Field	IRM4-S197N	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated	2.51	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	1.7	0.66	0.15	< 0.0058 U	< 0.0022 U
Football Field	IRM4-S196N	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated	2.36	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	1.7	0.54	0.12	< 0.0061 U	< 0.0023 U
Football Field	IRM4-B200	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated	0.205	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	0.17	0.035	< 0.0047 U	< 0.0058 U	< 0.0022 U
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated	0.478	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.34	0.12	0.018	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3501	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-S099	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	IRM4A-S096	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated	1.9	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.94	0.77	0.19	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S092	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated	0.68	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.46	0.19	0.03	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-S118	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated	0.253	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.14	0.096	0.017 J	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S119	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated	0.013	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-B008	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated	1.041	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.46	0.51	0.071 P	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-B009	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated	0.353	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.2	0.13	0.023 P	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-S143	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated	0.461	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.26	0.16	0.041	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S144	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated	1.003	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.35	0.57	0.083	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S165	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated	1.5	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	1.5	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S166	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM4A-S167	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-B016	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM4A-B017	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM4A-B018	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated	0.34	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.34	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S190	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated	1.2	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.34	0.86	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S189	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated	0.0307	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.0057 J	< 0.0058 U	0.025	< 0.0068 U	< 0.0026 U
Football Field	IRM4A-S188	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated	0.597	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.19	0.36	0.047	< 0.0067 U	< 0.0025 U
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated	0.109	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.055	0.038	0.016 J	< 0.0064 U	< 0.0024 U
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated	0.655	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.44	0.19	0.025	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-S147	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated	0.286	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.19	0.083	0.013 J	< 0.0067 U	< 0.0026 U
Football Field	IRM4A-S146	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated	0.144	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.074	0.055	0.015 J	< 0.0064 U	< 0.0024 U
Football Field	IRM4A-S187	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM4A-S168	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S169	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated	0.862	< 0.0069 UT	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.58	0.25	0.032	< 0.0074 U	< 0.0028 U
Football Field	IRM4A-S107	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated	0.071	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.041	0.03	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM4A-B036	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated	0.309	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.18	0.11	0.019	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated	1.89	< 0.0060 UT	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.3	0.49	0.1	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated	0.196	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.098	0.078	0.02	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated	0.419	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.25	0.14	0.029	< 0.0059 U	< 0.0022 U
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated	0.487	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.24	0.19	0.057	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated	0.498	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.24	0.21	0.048	< 0.0066 U	< 0.0025 U
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated	0.206	< 0.0059 UT	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.17	0.036	< 0.0052 U	< 0.0064 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated	9.45	< 0.0058 UT	< 0.0064 U	< 0.0044 U	< 0.0026 U	5.5	3.2	0.75	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	487	< 1.2 U	< 1.3 U	< 0.9 U	< 0.54 U	330	140	17	< 1.3 U	< 0.5 U
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated	7.23	< 0.0064 UT	< 0.0069 U	< 0.0048 U	< 0.0029 U	5.1	1.9	0.23	< 0.0069 U	< 0.0026 U
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated	1.362	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.93	0.37	0.062	< 0.0067 U	< 0.0025 U
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated	5.99	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	4.1	1.6	0.29	< 0.0067 U	< 0.0025 U
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated	1.156	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.85	0.27	0.036	< 0.0070 U	< 0.0027 U
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated	186	< 0.66 U	< 0.72 U	< 0.49 U	< 0.3 U	130	50	6	< 0.71 U	< 0.27 U
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated	43.3	< 0.063 U	< 0.069 U	< 0.047 U	< 0.028 U	31	11	1.3	< 0.068 U	< 0.026 U
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated	22	< 0.059 U	< 0.065 U	< 0.044 U	< 0.027 U	14	6.9	1.1	< 0.064 U	< 0.025 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	133	< 0.61 U	< 0.67 U	< 0.46 U	< 0.28 U	89	39	5	< 0.66 U	< 0.25 U
Football Field	IRM5-B255A	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B034	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Football Field	IRM5-B233	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated	4.16	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.5	2.2	0.46	< 0.0064 U	< 0.0025 U
Football Field	IRM5-S247	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated	0.478	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.23	0.21	0.038	< 0.0064 U	< 0.0024 U
Football Field	IRM5-B233	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated	1.2	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.19	0.77	0.24	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S246	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated	0.157	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.074	0.071	0.012 J	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S245	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated	0.141	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.071	0.07	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S244	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated	0.023	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.011 J	0.012 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B236	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated	0.532	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.17	0.27	0.092	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S243	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated	1.86	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.68	0.94	0.24	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated	6.06	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	4.2 J	1.6 J	0.26 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated	1.36	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.89 J	0.4 J	0.07 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated	0.864	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.58 J	0.24 J	0.044 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	3.39	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2.4 J	0.83 J	0.16 J	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S291	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated	0.728	< 0.0079 U	< 0.0086 U	< 0.0059 U	< 0.0036 U	0.42	0.28	0.028	< 0.0086 U	< 0.0033 U
Football Field	IRM5-S287	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated	0.127	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.081	0.046	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated	0.299	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	0.2	0.099	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated	2.624	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.9 J	0.69 J	0.034 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated	0.0489	0.0058	0.0063	0.0043	0.0026	0.011	0.0053	0.005	0.0062	0.0024
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.0587	0.0062	0.0067	0.0046	0.0028	0.018	0.0057	0.0054	0.0067	0.0026
Football Field	IRM5-B066	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated	0.052	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.034	0.018 J	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B040	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated	6.96	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	4.6	1.9	0.46	< 0.0071 U	< 0.0027 U
Football Field	IRM5-B053	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated	0.15	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.095	0.055	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-B079	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated	4.39	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	2.2	1.9	0.29	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	1.748	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	1.3	0.41	0.038	< 0.0060 U	< 0.0023 U
Football Field	IRM5-B013	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	2.52	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.7	0.66	0.16	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated	1.308	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.97 J	0.28 J	0.058 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated	2.988	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	2.2 J	0.73 J	0.058 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated	2.735	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2 J	0.69 J	0.045 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3623	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated	0.113	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.064 J	0.049 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3624	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated	0.127	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.083 J	0.044 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3607	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated	0.166	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.074 J	0.073 J	0.019 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3611	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated	0.42	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.2 J	0.22 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3001A	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	0.042	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.015 J	0.027	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated	5.91	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	3.8 J	1.6 J	0.51 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3500A	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3501A	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated	0.093	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.065 J	0.028 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3502A	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated	0.59	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.42 J	0.17 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3603	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3604	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated	0.199	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.14 J	0.059 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3605	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated	3.353	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	2.4 J	0.92 J	0.033 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3606	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated	0.024	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.024	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3607	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3608	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated	0.016	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.016	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3609	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated	0.061	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.042 J	0.019 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3610	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated	0.359	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.26 J	0.099 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3611	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated	0.41	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.28 J	0.13 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3612	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated	0.087	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.06 J	0.027 J	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3617	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated	0.444	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.19 J	0.22 J	0.034 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3618	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated	0.175	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.11 J	0.065 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	0.209	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.15 J	0.059 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3621	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated	0.017	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.017 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3622	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated	1.43	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1 J	0.43 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3037A	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated	3.93	< 0.0081 U	< 0.0088 U	< 0.0061 U	< 0.0036 U	2.4 J	1.3 J	0.23 J	< 0.0088 U	< 0.0033 U
Northern Athletic Field	SSHS-B3521	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated	0.683	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.36 J	0.26 J	0.063 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3521	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated	0.177	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.1 J	0.077 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	0.036	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	0.036	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	0.059	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.012 J	0.027	0.02	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated	0.145	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.099 J	0.046 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	0.087	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.056 J	0.031 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	0.113	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.077 J	0.036 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	0.05	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.031	0.019	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	0.054	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.024	0.03	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3491A	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated	0.057	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.036 J	0.021 J	< 0.0056 U	< 0.0069 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	0.6	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.43	0.17	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.019	0.01 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated	1.027	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.73	0.28	0.017 J	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated	0.69	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.51	0.18	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated	1.657	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.1	0.52	0.037	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated	1.46	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.1	0.3	0.06	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated	0.406	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.29	0.098	0.018	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated	1.236	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.95	0.25	0.036	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated	1.59	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1	0.49	0.1	< 0.0067 U	< 0.0026 U
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated	0.105	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.086	0.019	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated	9.692	< 0.066 U	< 0.072 U	< 0.05 U	< 0.03 U	7	2.6	0.092 J	< 0.072 U	< 0.027 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated	3.24	< 0.0070 UT	< 0.0077 U	< 0.0053 U	< 0.0032 U	2	1.1	0.14	< 0.0076 U	< 0.0029 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated	0.921	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.61	0.25	0.061	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated	0.039	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.019	0.02	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated	0.721	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.52	0.17	0.031	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated	2.68	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.6	0.91	0.17	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated	3.53	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	2	1.2	0.33	< 0.0068 U	< 0.0026 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	0.043	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.016 J	0.027	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	1.12	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.53	0.45	0.14	< 0.0075 U	< 0.0029 U
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated	0.59	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.22	0.28	0.09	< 0.0070 U	< 0.0027 U
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated	0.139	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.1	0.028	0.011 J	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated	0.248	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.092	0.11	0.046	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated	0.601	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.38	0.18	0.041	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated	0.734	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.46	0.22	0.054	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated	0.018	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.018 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated	0.446	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.16	0.21	0.076	< 0.0067 U	< 0.0026 U
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated	0.036	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.02	0.016 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated	0.088	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.035	0.053	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated	0.055	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.036	0.019 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated	0.112	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.087	0.025	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated	0.208	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.17	0.038	< 0.0050 U	< 0.0061 U	< 0.0024 U
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated	0.369	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.23	0.12	0.019	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated	0.999	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.53 P	0.38	0.089	< 0.0068 U	< 0.0026 U
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated	0.175	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.095	0.062	0.018 J	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated	1.15	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.51	0.52	0.12	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated	6.2	< 0.0060 UT	< 0.0066 U	< 0.0045 U	< 0.0027 U	4.7	1.5	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated	0.86	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.66	0.2	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated	0.845	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.58	0.23	0.035	< 0.0070 U	< 0.0027 U
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated	0.232	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.17	0.062	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated	0.676	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.5	0.15	0.026	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated	0.296	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.23	0.066	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated	0.159	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.12	0.039	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated	0.143	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.11	0.033	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated	0.646	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.48	0.15	0.016 J	< 0.0060 U	< 0.0023 U
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated	0.126	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.079	0.047	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated	0.31	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.2	0.086	0.024	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated	0.09	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.042	0.048	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated	6.39	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	4.5	1.6	0.29	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated	3.031	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	2.4	0.57	0.061	< 0.0070 U	< 0.0027 U
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated	1.64	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	1.3	0.31	0.03	< 0.0064 U	< 0.0025 U
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated	0.0232	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.0092 J	0.014 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated	0.0268	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.018 J	0.0088 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated	0.012	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated	0.643	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.41	0.2	0.033	< 0.0070 U	< 0.0027 U
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated	0.141	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.1	0.041	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0030 U
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated	0.217	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.14	0.062	0.015 J	< 0.0069 U	< 0.0027 U
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated	0.1692	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.12	0.042	0.0072 J	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated	0.0784	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.05	0.02	0.0084 J	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated	0.36	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.2	0.16	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated	0.585	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.32	0.19	0.075	< 0.0063 U	< 0.0024 U
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated	0.51	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.33	0.14	0.04	< 0.0060 U	< 0.0023 U
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated	0.755	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.47	0.23	0.055	< 0.0061 U	< 0.0023 U
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated	0.245	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.081	0.14	0.024	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated	0.681	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.46	0.19	0.031	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated	0.226	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.16	0.066	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated	0.037	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.024	0.013 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated	0.06	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	0.029	0.031	< 0.0065 U	< 0.0081 U	< 0.0031 U
Football Field	IRM5-B254	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-B254	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S269	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated	0.225	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.13	0.072	0.023	< 0.0064 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-S268	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated	0.029	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S266	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated	1.193	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.78	0.33	0.083	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S270	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated	0.252	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.17	0.082	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S217	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated	0.173	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.14	0.033	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated	0.04	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.027	0.013 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated	0.021	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.021	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated	0.063	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.049	0.014 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated	0.5	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.32	0.16	0.02	< 0.0067 U	< 0.0025 U
Football Field	IRM5-S235	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated	0.013	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.013 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated	0.066	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.066	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated	0.076	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.048 B	0.028	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	IRM5-B006	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated	0.195	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.13 B	0.065	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-B010	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated	1.78	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.1 B	0.54	0.14	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B006	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated	0.209	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.14 B	0.055	0.014 J	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B009	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated	0.23	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.12 B	0.081	0.029	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B007	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated	0.016	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.016 BJ	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-S196	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated	0.57	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.57	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-S197	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated	0.13	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.13	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-B226	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated	4.73	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	3.2	1.2	0.33	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated	0.41	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.25	0.16	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.011 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S270A	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated	0.205	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.16	0.045	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S271A	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated	0.334	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.26	0.063	0.011 J	< 0.0060 U	< 0.0023 U
Football Field	IRM5-S269A	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated	0.026	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.026	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S272A	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated	0.297	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.24	0.057	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated	9.57	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	5.7	2.9	0.97	< 0.0066 U	< 0.0025 U
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	11.08	< 0.062 U	< 0.068 U	< 0.046 U	< 0.028 U	8.8	2.1	0.18 J	< 0.067 U	< 0.026 U
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	2.027	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.7	0.31	0.017 J	< 0.0062 U	< 0.0024 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	15.7	< 0.063 U	< 0.069 U	< 0.047 U	< 0.028 U	15	3.4	0.3	< 0.068 U	< 0.026 U
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated	0.248	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.17 B	0.062	0.016 J	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated	0.027	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.027 B	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	ISMP-B001	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated	0.59	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.25 B	0.23	0.11	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B002	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated	0.181	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.13	0.051	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B061	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated	0.197	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.14	0.042	0.015 J	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B098	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated	0.87	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.41	0.35	0.11	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B085	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated	0.6	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.19	0.27	0.14	< 0.0072 U	< 0.0027 U
Football Field	IRM5-B061	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated	0.12	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.089	0.031	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated	0.042	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.024	0.018	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated	0.075	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.048	0.027	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated	4.63	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	3.3	1.1	0.23	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated	0.083	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.062	0.021	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated	0.858	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	0.6	0.22	0.038	< 0.0058 U	< 0.0022 U
Football Field	IRM5-S700	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated	0.568	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.38	0.15	0.038	< 0.0059 U	< 0.0022 U
Football Field	IRM5-B703	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated	0.389	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.28	0.098	0.011 J	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S702	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-S705	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated	0.046	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.046	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B704	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated	0.533	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.35	0.16	0.023	< 0.0060 U	< 0.0023 U
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated	1.82	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.85	0.97	< 0.0051 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated	0.071	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.054	0.017 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated	0.671	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.48	0.15	0.041	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated	2.327	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	1.9	0.37	0.057	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S706	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated	0.087	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.068	0.019	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-S704	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B800	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated	0.0367	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.029	0.0077 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B802	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated	0.442	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.31	0.11	0.022	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S803	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated	0.161	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12	0.041	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B805	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated	0.02	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.02	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S802	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated	0.5	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.36	0.12	0.02	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S804	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated	0.637	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.48	0.14	0.017 J	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S807	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated	0.191	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.15	0.041	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S900	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-B807	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated	0.105	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.073	0.032	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-B806	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated	0.103	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.063	0.04	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S813	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B900	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated	0.047	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.034	0.013 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S901	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated	0.025	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.025	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S900	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated	0.016	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-S907	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	ISMP-S103	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B100	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-S138	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated	1.768	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.3	0.41	0.058	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S104	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated	0.613	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.42	0.15	0.043	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S105	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S106	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S109	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated	0.216	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.079	0.093	0.044	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S110	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S111	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-S124	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B102	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S126	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated	0.149	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.098	0.039	0.012 J	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S132	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated	0.011	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.011 J	< 0.0052 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-S130	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated	0.147	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.069	0.056	0.022	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S136	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated	0.49	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.39	0.1	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S131	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated	0.826	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.54	0.22	0.066	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B105	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated	6.11	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	4.6	1.3	0.21	< 0.0061 U	< 0.0023 U
Football Field	ISMP-B106	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated	1.743	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	1.2	0.48	0.063	< 0.0059 U	< 0.0023 U
Football Field	ISMP-S140	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated	0.043	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.043	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S142	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated	5.89	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	3.3	2	0.59	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S141	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated	0.043	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.026	0.017 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B107	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated	1.179	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.9	0.22	0.059	< 0.0066 U	< 0.0025 U
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated	0.0211	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.014 J	0.0071 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated	0.147	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.12	0.027	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated	0.041	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.03	0.011 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.014 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S605	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated	0.121	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.055	0.048	0.018 J	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S610	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-B604	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated	0.021	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.021	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated	0.021	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.021	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated	0.11	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.083	0.027	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated	0.106	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.06	0.036	0.01 J	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated	0.107	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.084	0.023	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated	ND	< 0.0088 U	< 0.0096 U	< 0.0066 U	< 0.0040 U	< 0.0065 U	< 0.0081 U	< 0.0077 U	< 0.0095 U	< 0.0036 U
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated	0.041	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.026	0.015 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated	0.145	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.087	0.058	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated	0.201	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.11	0.078	0.013 J	< 0.0068 U	< 0.0026 U
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated	0.075	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.045	0.03	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B605	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated	0.048	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.038	0.01 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-S614	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated	0.571	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.44	0.1	0.031	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated	0.094	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.071	0.023	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated	4.41	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.2	1	0.21	< 0.0064 U	< 0.0024 U
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated	0.242	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.18	0.062	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B700D	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated	0.124	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.091	0.033	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-B071	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated	0.057	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.04	0.017 J	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B172	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated	1.8	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	1.8	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B173	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated	0.296	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.13	0.12	0.046	< 0.0078 U	< 0.0030 U
Football Field	IRM5-B109	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated	0.128	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.057	0.071	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B171	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated	0.067	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.067	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B095	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated	0.105	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.073	0.032	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B097	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated	0.0225	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.015 J	0.0075 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B125	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated	0.558	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.27	0.22	0.068	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B002A	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated	0.229	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.078	0.12	0.031	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B071	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-B005	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated	1.094	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.76	0.27	0.064	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B004	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B016	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B030	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated	0.209	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.13	0.064	0.015 J	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B044	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated	0.121	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.069	0.052	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B032	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated	0.394	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.23	0.12	0.044	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B113	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated	0.457	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.29	0.13	0.037	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B126	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated	0.32	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.32	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM5-B031	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated	7.16	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	5.8	1.4	0.16	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S163	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated	0.44	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.44	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-S169	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated	0.485	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.23	0.19	0.065	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S163	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S161	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated	0.11	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.11 T	< 0.0058 UT	< 0.0071 UT	< 0.0027 UT
Football Field	IRM5-B231	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated	0.096	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.055	0.041	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S068	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated	0.606	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.38	0.17	0.056	< 0.0066 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-B231A	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated	0.021	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.021	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	IRM5-B609	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated	0.206	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.12	0.086	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S072	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated	0.093	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.093	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B142	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated	0.034	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.017 J	0.017 J	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B195	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	0.0373	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.028	0.0093 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM5-S085	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	0.815	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.53	0.23	0.055	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B196	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	0.041	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.03	0.011 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	IRM5-S090	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	0.57	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.26	0.2	0.11	< 0.0068 U	< 0.0026 U
Football Field	IRM5-S089	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	0.168	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.1	0.051	0.017 J	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B168	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	0.098	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.074	0.024	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated	0.159	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.11	0.049	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B160	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated	0.014	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.014 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated	0.3	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.13	0.17	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	IRM5-B118A	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated	2.04	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.78	0.93	0.33	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B808D	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated	0.273	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.17	0.081	0.022	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated	0.076	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056	0.02	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B808A	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated	0.08	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.049	0.031	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B808B	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated	0.075	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.056	0.019	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated	0.134	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.1	0.034	< 0.0051 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B808C	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated	0.066	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.049	0.017	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated	0.303	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.24	0.049	0.014 J	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B801B	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated	0.255	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.18	0.055	0.02	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B801C	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated	0.048	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.038	0.01 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated	0.196	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.14	0.041	0.015 J	< 0.0075 U	< 0.0029 U
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated	0.105	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.077	0.028	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated	0.023	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.023	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated	0.021	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.021	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated	0.255	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.2	0.055	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated	0.347	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.25	0.082	0.015 J	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated	0.107	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.073	0.034	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated	0.145	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.12	0.025	< 0.0067 U	< 0.0026 U
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated	0.49	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.49	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated	0.357	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.22	0.11	0.027	< 0.0075 U	< 0.0029 U
Football Field	IRM5-B028	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated	0.718	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.44	0.22	0.058	< 0.0070 U	< 0.0027 U
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated	0.483	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.28	0.16	0.043	< 0.0072 U	< 0.0028 U
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated	0.2	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.13	0.051	0.019 J	< 0.0071 U	< 0.0027 U
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated	0.029	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.029	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B157	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated	0.466	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.33	0.11	0.026	< 0.0059 U	< 0.0023 U
Football Field	IRM5-B158	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	IRM5-B159	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-S201	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated	0.486	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.35	0.11	0.026	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S025A	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated	0.391	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.31	0.081	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S269A	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated	1.89	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.1	0.64	0.15	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B254A	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated	0.035	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.023	0.012 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated	1.396	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.97	0.36	0.066	< 0.0075 U	< 0.0028 U
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated	1.56	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.1	0.35	0.11	< 0.0063 U	< 0.0024 U
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated	0.588	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.39	0.15	0.048	< 0.0066 U	< 0.0025 U
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated	1.32	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.89	0.33	0.1	< 0.0063 U	< 0.0024 U
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated	0.0292	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.021	0.0082 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated	0.245	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.16	0.065	0.02	< 0.0070 U	< 0.0027 U
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated	1.85	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	1.2	0.45	0.2	< 0.0060 U	< 0.0023 U
Football Field	IRM5-S057A	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-S057C	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated	0.022	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.022	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated	0.121	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.073	0.048	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated	0.104	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.063	0.041	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated	1.49	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.67	0.64	0.18	< 0.0061 U	< 0.0023 U
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated	0.211	< 0.0073 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	0.043	0.15	0.018 J	< 0.0079 U	< 0.0030 U
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated	0.082	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.046	0.036	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated	0.067	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.037	0.03	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated	0.126	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.024	0.08	0.022	< 0.0070 U	< 0.0027 U
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated	0.117	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.065	0.052	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated	0.014	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.014 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated	0.018	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.018 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated	3.52	< 0.0064 UT	< 0.0070 U	< 0.0048 U	< 0.0029 U	2	1.2	0.32	< 0.0069 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-S655	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated	0.408	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.32	0.088	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B618	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated	0.225	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.15	0.075	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B619	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated	0.067	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.044	0.023	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-S652	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated	0.042	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.025	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated	0.057	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.035	0.022	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated	0.078	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.05	0.028	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated	0.02	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.02	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated	0.96	< 0.0068 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	0.73	0.23	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	ISMP-B200	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated	0.271	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.14	0.11	0.021	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B201	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated	2.67	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.5	0.98	0.19	< 0.0063 U	< 0.0024 U
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated	0.221	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.09	0.11	0.021	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated	0.175	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.13	0.045	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated	2.45	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.4	0.82	0.23	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated	2.26	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.5	0.63	0.13	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated	0.134	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.096	0.038	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated	1.429	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.94	0.41	0.079	< 0.0068 U	< 0.0026 U
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated	0.013	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.013 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated	2.84	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.8	0.84	0.2	< 0.0066 U	< 0.0025 U
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated	0.113	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.093	0.02	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated	0.288	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.2	0.088	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated	0.34	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.16	0.18	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.012 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated	0.131	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.052	0.079	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated	0.03	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	0.03	< 0.0066 U	< 0.0082 U	< 0.0031 U
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated	1.357	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.68	0.6	0.077	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	0.078	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.054	0.024	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated	0.016	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.016 J	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated	1.242	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.8	0.37	0.072	< 0.0066 U	< 0.0025 U
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated	1.83	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.3	0.43	0.1	< 0.0065 U	< 0.0025 U
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated	3.65	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	2.6	0.83	0.22	< 0.0071 U	< 0.0027 U
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated	0.088	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.066	0.022	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated	0.079	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.052 J	0.027 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated	3.18	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.8	1.3	0.28	< 0.0068 U	< 0.0026 U
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated	0.604	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.35	0.22	0.034	< 0.0065 U	< 0.0025 U
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated	4.79	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	3.1	0.92	0.27	< 0.0067 U	< 0.0026 U
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated	0.066	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.066	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated	0.307	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.26	0.047	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated	0.065	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.044	0.021	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated	0.41	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.3	0.11	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated	1.359	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	1.1	0.24	0.019 J	< 0.0070 U	< 0.0027 U
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated	0.017	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.017 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated	1.65	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.83	0.65	0.17	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated	3.81	< 0.0060 UT	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.9	0.73	0.18	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated	2.17	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.4	0.64	0.13	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated	0.934	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.37	0.48	0.084	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated	1.585	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	1.2 J	0.33 J	0.055 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated	0.088	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.088	< 0.0052 UJ	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated	0.577	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.43 J	0.12 J	0.027 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated	0.048	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.022	0.026	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	0.039	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.039 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 UJ	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated	0.076	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.05 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	0.035	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.035	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	0.062	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.044	0.018	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	0.016	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.016 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	0.015	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated	0.073	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.054 J	0.019 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated	0.075	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.055 J	0.02 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated	0.015	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.015 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated	0.014	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated	0.307	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.23 J	0.066 J	0.011 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated	0.08	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.059 J	0.021 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated	0.208	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.16 J	0.048 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated	0.019	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.019	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	0.025	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.025	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	0.023	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.023	< 0.0064 U	< 0.0060 U	< 0.0075 U	< 0.0029 U
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated	0.036	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.036	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	18.85	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	15	3.3	0.55	< 0.067 U	< 0.025 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	0.679	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.51	0.14	0.029	< 0.0072 U	< 0.0027 U
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated	0.578	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.39	0.16	0.028	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated	0.146	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.11	0.036	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated	0.096	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.068	0.028	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	0.051	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.051	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated	0.059	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.043 J	0.016 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	0.108	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.084	0.024	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated	0.081	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.057	0.024	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated	0.034	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.034	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13	5/13/2021	-	855.28	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated	0.715	< 0.0078 U	< 0.0085 U	< 0.0059 U	< 0.0035 U	0.51	0.16	0.045	< 0.0085 U	< 0.0032 U
Football Field	ISMP-B500	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated	2.17	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.1	0.84	0.23	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B500	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated	1.75	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.1	0.49	0.16	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B507	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated	0.93	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.37	0.39	0.17	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated	0.01	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.01 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	0.0097	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0097 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated	0.198	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.15 J	0.048 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B502	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated	3.57	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	1.7	1.5	0.37	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B507	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated	0.96	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.36	0.4	0.2	< 0.0067 U	< 0.0025 U
Football Field	ISMP-B512	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated	1.855	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.4	0.37	0.085	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B518	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated	3	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	2.2	0.64	0.16	< 0.0060 U	< 0.0023 U
Football Field	ISMP-B524	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated	0.184	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.1	0.084	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated	0.805	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.61	0.17	0.025	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated	0.015	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated	0.0094	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0094 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated	0.224	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.18 J	0.044 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated	0.0091	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0091 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated	1.09	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.44	0.52	0.13	< 0.0070 U	< 0.0027 U
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated	0.187	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	0.13	0.057	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated	1.737	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	1	0.65	0.087	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated	0.101	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.077 J	0.024 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated	0.11	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.11	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated	0.016	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 UJ	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	0.049	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	0.049	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	0.03	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.03	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	0.015	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0055 UJ	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	0.065	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.051 J	0.014 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated	0.017	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.017 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated	0.011	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.011 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated	0.82	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.82	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated	0.064	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.032 P	0.032	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated	0.011	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S500	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated	0.214	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.12	0.071	0.023	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B526	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated	0.04	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.04	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Football Field	ISMP-S500	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated	0.024	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.024	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Football Field	ISMP-B525	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated	0.485	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.33	0.13	0.025	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S503	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated	0.071	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.042	0.029	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated	ND	< 0.0056 UT	< 0.0061 UT	< 0.0042 UT	< 0.0025 UT	< 0.0041 UT	< 0.0052 UT	< 0.0049 UT	< 0.0061 UT	< 0.0023 UT
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated	ND	< 0.0060 UT	< 0.0065 UT	< 0.0045 UT	< 0.0027 UT	< 0.0044 UT	< 0.0055 UT	< 0.0052 UT	< 0.0065 UT	< 0.0025 UT
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated	0.022	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated	1.213	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.84	0.3	0.073	< 0.0060 U	< 0.0023 U
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated	0.1448	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.1	0.036	0.0088 J	< 0.0060 U	< 0.0023 U
Football Field	ISMP-B536	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S507	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated	0.46	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.33	0.13	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	1.72	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1	0.6	0.12	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S509	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated	0.117	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.083	0.034	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-S510	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	0.979	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.48	0.41	0.089	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B533	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated	0.019	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.019	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B532	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	1.058	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.62	0.37	0.068	< 0.0069 U	< 0.0026 U
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	0.056	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.034	0.022	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B535	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated	0.026	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	0.026	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	ISMP-S515	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B536	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated	0.02	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.02	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B537	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated	0.892	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.63	0.22	0.042	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	0.027	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	0.027	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	0.181	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.11	0.071	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	0.929	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.52	0.33	0.079	< 0.0063 U	< 0.0024 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	0.02	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.02	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	1.391	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.85	0.46	0.081	< 0.0061 U	< 0.0023 U
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	0.031	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.031	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	0.203	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.13	0.073	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	1.49	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.89	0.47	0.13	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	1.65	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.66	0.99	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	0.983	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.66	0.26	0.063	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	0.717	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.44	0.21	0.067	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	0.892	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.58	0.23	0.082	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	0.36	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.26	0.1	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	0.52	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.35	0.17	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	0.46	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.31	0.15	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	0.413	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.28	0.11	0.023	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	0.332	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.26	0.072	< 0.0053 U	< 0.0066 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16	6/2/2021	-	855.92	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	1.478	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.1	0.31	0.068	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	0.49	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.38	0.11	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	0.076	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.076	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	0.56	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.42	0.14	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	0.795	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.53	0.2	0.065	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	0.763	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.56	0.17	0.033	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	3.97	< 0.011 U	< 0.012 U	< 0.0079 U	< 0.0048 U	2.8	0.91	0.26	< 0.011 U	< 0.0044 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	1.6	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.1	0.39	0.11	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	0.469	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.3	0.14	0.029	< 0.0069 U	< 0.0026 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	2.04	< 0.0094 U	< 0.01 U	< 0.0070 U	< 0.0042 U	1.4	0.52	0.12	< 0.01 U	< 0.0039 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	3.64	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	2.6	0.85	0.19	< 0.0070 U	< 0.0027 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	0.369	< 0.0085 U	< 0.0092 U	< 0.0063 U	< 0.0038 U	0.24	0.098	0.031	< 0.0091 U	< 0.0035 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	1.096	< 0.0090 U	< 0.0098 U	< 0.0068 U	< 0.0041 U	0.81	0.22	0.066	< 0.0098 U	< 0.0037 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	1.4	< 0.0092 U	< 0.01 U	< 0.0069 U	< 0.0041 U	0.88	0.42	0.1	< 0.0099 U	< 0.0038 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	4.35	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	3.2	0.89	0.26	< 0.0078 U	< 0.0030 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	3.67	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.7	0.76	0.21	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B538	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	0.215	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.1	0.081	0.034	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S519	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	0.258	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.17	0.065	0.023	< 0.0069 U	< 0.0026 U
Football Field	ISMP-S520	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated	0.177	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.12	0.057	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-B539	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated	0.835	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.58	0.21	0.045	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B540	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated	0.571	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.35	0.16	0.061	< 0.0065 U	< 0.0025 U
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	0.017	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.017 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	0.204	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.13	0.059	0.015 J	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	0.131	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.083	0.037	0.011 J	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	0.296	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.2	0.079	0.017 J	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	0.147	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.083	0.05	0.014 J	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	1.405	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1	0.35	0.055	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	0.647	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.28	0.31	0.057	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	0.144	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.05	0.094	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated	0.0168	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.011 J	0.0058 J	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B541	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated	0.231	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.15	0.081	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-B542	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated	0.02	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.02	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B543	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated	0.303	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.23	0.073	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B544	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	0.228	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.13	0.098	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-S522	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	0.144	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.1	0.044	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-B545	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	0.0091	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.0091 J	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	ISMP-S523	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated	0.012	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.012 J	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	ISMP-S524	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Football Field	ISMP-S525	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated	2.01	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.4 J	0.47 J	0.14 J	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated	0.449	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.17	0.21	0.069	< 0.0070 U	< 0.0027 U
Football Field	ISMP-B546	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated	0.126	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.079	0.047	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S526	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated	0.42	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.3	0.12	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S527	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated	0.57	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.25 P	0.22	0.1	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated	0.583	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	0.13 J	0.013 J	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated	0.14	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.14	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated	0.082	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.037	0.027	0.018 J	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated	0.016	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.016 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated	0.114	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.075	0.023	0.016 J	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated	0.092	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.092	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated	0.512	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.31	0.16	0.042	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated	0.1523	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.1	0.046	0.0063 JP	< 0.0064 U	< 0.0025 U
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated	0.274	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.18	0.094	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated	0.094	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.063	0.031	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated	0.1863	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.11	0.068	0.0083 J	< 0.0061 U	< 0.0023 U
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated	1.171	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.79	0.33	0.051	< 0.0062 U	< 0.0024 U
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated	0.043	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.023	0.02	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated	0.084	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.049	0.035	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated	0.625	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.42	0.18	0.025	< 0.0064 U	< 0.0025 U
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated	1.031	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.68	0.31	0.041	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated	31.3	< 0.055 U	< 0.06 U	< 0.041 U	< 0.025 U	24	6.1	1.2	< 0.059 U	< 0.023 U
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated	0.272	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.082	0.19	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated	0.0269	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.018	0.0089 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated	0.0252	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.016 J	0.0092 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated	0.124	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.09	0.034	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated	0.047	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.031	0.016 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.014 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	0.012 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated	0.064	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.037	0.027	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated	0.372	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.11	0.17	0.092	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated	0.13	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.019 P	0.076	0.035	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated	0.093	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.075 J	0.018 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated	0.44	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated	0.104	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.071 J	0.033 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated	1.108	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.68 J	0.35 J	0.078 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated	0.118	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.073 J	0.045 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated	0.33	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	0.33	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated	0.051	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	0.051	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated	0.051	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	0.051	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated	1.34	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	1	0.34	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated	0.195	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.029	0.11	0.056	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated	0.255	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.17	0.078	0.0070 JP	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated	0.13	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	0.13	< 0.0070 U	< 0.0027 U
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated	0.049	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.034	0.015 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated	0.233	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.093	0.14	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated	0.988	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.59	0.34	0.058	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3526	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated	2.83	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	2.1 J	0.73 J	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3526	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated	2.02	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.6 J	0.42 J		< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3527	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated	0.055	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.044 J	0.011 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3527	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated	0.082	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.066 J	0.016 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated	2.16	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.8	0.36	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated	3.16	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	2.6	0.7	0.06	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated	0.21	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.21	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated	0.686	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.45	0.2	0.036	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated	0.5	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.12	0.38	< 0.0071 U	< 0.0027 U
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated	2.36	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.6	0.63	0.13	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated	0.25	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.25	< 0.0053 U	< 0.0066 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated	0.62	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.62	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated	2.2	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	2.2	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated	2.4	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	2.4	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated	0.671	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.4	0.24	0.031	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated	0.35	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.35	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated	0.301	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.21	< 0.0055 U	0.091	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated	0.256	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.19	0.066	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated	0.082	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.058	0.024	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated	0.172	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.13	0.042	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated	0.478	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.35	0.099	0.029	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated	0.329	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.23	0.076	0.023	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated	8.28	< 0.054 U	< 0.059 U	< 0.04 U	< 0.024 U	6.2	1.7	0.38	< 0.058 U	< 0.022 U
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated	7.25	< 0.055 U	< 0.06 U	< 0.041 U	< 0.025 U	5.6	1.4	0.25	< 0.059 U	< 0.023 U
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated	2.057	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	1.7	0.32	0.037	< 0.0059 U	< 0.0023 U
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated	0.183	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.15	0.033	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated	1.98	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	1.4 J	0.47 J	0.11 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	0.249	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	0.19 J	0.059 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated	4.3	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	4.3	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4018	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.22	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.16	0.06	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.219	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14	0.079	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated	0.32	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.14	0.18	< 0.0064 U	< 0.0025 U
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated	0.143	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.065 P	0.053	0.025	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated	0.174	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.13	0.044	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated	0.906	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.61	0.21	0.086	< 0.0075 U	< 0.0029 U
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated	0.051	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.051	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated	6.2	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	5	1.2	< 0.0052 UT	< 0.0064 U	< 0.0025 U
Rear Parking Lot	SSHS-B3824	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated	0.084	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.084 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated	0.038	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.02	0.018 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated	0.32	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.21	0.11	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated	0.145	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.11	0.035	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated	0.0297	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.02 J	0.0097 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated	0.044	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.028	0.016 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated	0.035	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.023	0.012 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated	0.198	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.13	0.068	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated	2.128	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	1.5	0.56	0.068	< 0.0075 U	< 0.0029 U
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated	0.232	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	0.086	0.092	0.054	< 0.0078 U	< 0.0030 U
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated	1.108	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.81	0.24	0.058	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated	0.282	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.19	0.075 P	0.017 J	< 0.0064 U	< 0.0024 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	0.149	< 0.0080 U	< 0.0087 U	< 0.0060 U	< 0.0036 U	0.097	0.052	< 0.0070 U	< 0.0086 U	< 0.0033 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	0.088	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.034	0.034	0.02	< 0.0072 U	< 0.0027 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	0.125	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.055	0.047	0.023	< 0.0064 U	< 0.0024 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	0.098	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.049	0.032	0.017 J	< 0.0064 U	< 0.0024 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	0.27	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.14	0.089	0.041	< 0.0065 U	< 0.0025 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	0.165	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.063	0.065	0.037	< 0.0070 U	< 0.0027 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	0.075	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.029	0.027	0.019 J	< 0.0074 U	< 0.0028 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	0.178	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.09	0.065	0.023	< 0.0063 U	< 0.0024 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	0.054	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.034	0.02	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	0.264	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.11	0.11	0.044	< 0.0064 U	< 0.0024 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	0.204	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.11	0.067	0.027	< 0.0065 U	< 0.0025 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	0.635	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.31	0.23	0.095	< 0.0063 U	< 0.0024 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	0.203	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.089	0.079	0.035	< 0.0064 U	< 0.0025 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	0.8	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.45	0.25	0.1	< 0.0065 U	< 0.0025 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	0.026	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.026	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	0.133	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.077	0.056	< 0.0052 U	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	0.797	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.49 J	0.25 J	0.057 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	0.214	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.034 U	0.13 J	0.084 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	0.36	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.21 J	0.12 J	0.03 J	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	0.881	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	0.48 J	0.31 J	0.091 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	1.17	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.58 J	0.47 J	0.12 J	< 0.0067 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	0.32	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	0.17 J	0.11 J	0.04 J	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	855.73	0.00	-	8 - 10 ft	8-10 ft	180-127066-2	Not Excavated	0.191	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	0.096 J	0.073 J	0.022 J	< 0.0068 U	< 0.0026 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	0.0061	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.034 U	< 0.0042 U	0.0061 J	< 0.005 U	< 0.0061 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	0.024	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	0.024	< 0.0052 U	< 0.0064 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	855.97	0.00	-	8 - 10 ft	8-10 ft	180-127140-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	0.092	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.064 J	0.028 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	0.066	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.043 J	0.023 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	0.135	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.088 J	0.047 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	0.027	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.014 J	0.013 J	< 0.0054 UJ	< 0.0067 U	< 0.0026 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated	0.018	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.018	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated	1.177	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.92	0.21	0.047	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated	0.214	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.16	0.054	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated	0.105	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.079	0.026	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated	0.013	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.013 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated	0.022	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated	0.026	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.026	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated	0.051	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.024	0.027	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated	0.038	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.038	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated	0.011	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.011 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated	0.022	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.022	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated	0.429	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.24	0.15	0.039	< 0.0064 U	< 0.0025 U
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated	0.013	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.013 J	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated	0.088	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.068	0.02	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated	0.034	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.034	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated	0.06	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.041	0.019	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated	5.22	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	4	1	0.22	< 0.0074 U	< 0.0028 U
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated	1.74	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.2	0.42	0.12	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	0.0082	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0082 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	0.0083	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.0083 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	0.048	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.027 J	0.021 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 UJ	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	0.227	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	0.086	0.11	0.031	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.029	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	0.016 J	0.013 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 UJ	< 0.0057 UJ	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	ND	< 0.0092 U	< 0.01 U	< 0.0069 U	< 0.034 U	< 0.0068 U	< 0.0084 U	< 0.008 U	< 0.0099 U	< 0.0038 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	0.034	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.015 J	0.019	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B606	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	0.376	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.16	0.14	0.076	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B607	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	0.048	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.032	0.016 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B608	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	0.0094	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0094 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S601	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	0.121	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.053	0.041	0.027	< 0.0070 U	< 0.0027 U
Football Field	ISMP-S602	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	4.2	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	2.6	1.6	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S604	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	0.138	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.065	0.073	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S605	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	0.198	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.088	0.11	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S606	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	0.105	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.067	0.038	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S608	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	0.082	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.036	0.046	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S609	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	0.099	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.05	0.049	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S611	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	0.562	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.39	0.13	0.042	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated	0.1062	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.079	0.02	0.0072 J	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated	0.184	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.14	0.033	0.011 J	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated	2.046	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	1.6	0.37	0.076	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated	0.195	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.097	0.068	0.03	< 0.0060 U	< 0.0023 U
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated	0.145	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.067	0.053	0.025	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated	0.123	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.099	0.024	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated	0.096	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.045	0.032	0.019	< 0.0062 U	< 0.0024 U
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated	0.274	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.18	0.078	0.016 J	< 0.0067 U	< 0.0026 U
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated	0.053	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.041	0.012 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated	0.0325	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.025	0.0075 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	0.011	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.011 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	0.0087	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.0087 J	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	0.198	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.085	0.061	0.052	< 0.0070 U	< 0.0027 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	0.067	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.03	0.037	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	0.0094	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.0094 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	0.073	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.054	0.019	< 0.0065 U	< 0.0025 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	0.041	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.026	0.015 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B780	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated	1.279	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.83	0.37	0.079	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated	1.56	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	1.1	0.46	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated	4.15	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	2.7	1.2	0.25	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	0.015	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.015 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	0.018	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.018 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated	0.988	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.59	0.31	0.088	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated	0.0057	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0057 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	0.115	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.055	0.039	0.021	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S437	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated	2.98	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.7	1	0.28	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S166	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated	0.079	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.041	0.021	0.017 J	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S436	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated	6.47	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	4.1	1.8	0.57	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated	0.065	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.031 P	0.02	0.014 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S164	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated	4.71	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2.6	1.6	0.51	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S434	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated	0.394	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.17	0.13	0.094	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S163	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S433	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S162	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S441	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S169	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated	0.0085	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.0085 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	S440	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	S168	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated	1.66	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.94	0.51	0.21	< 0.0067 U	< 0.0025 U
Northern Athletic Field	S439	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated	0.0224	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.013 J	0.0094 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated	0.098	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.077	0.021 P	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S438	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated	0.211	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.12	0.059	0.032	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated	0.478	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.078	0.18	0.22	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated	0.0078	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.0078 JP	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated	0.158	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.11	0.048	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	S238	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated	0.66	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.42	0.24	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S244	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S243	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S242	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated	0.626	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.41	0.19	0.026	< 0.0067 U	< 0.0025 U
Northern Athletic Field	B235	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated	0.689	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.37	0.26	0.059 P	< 0.0072 U	< 0.0027 U
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated	0.124	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.059	0.043	0.022	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated	0.358	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.22	0.095	0.043	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated	0.014	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	0.014 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated	0.0235	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	0.0075 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated	0.564	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.3	0.18	0.084	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated	0.78	< 0.0068 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.36	0.26	0.16	< 0.0074 U	< 0.0028 U
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated	0.0231	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.015 J	0.0081 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated	1.99	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.8	0.79	0.4	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated	ND	< 0.0056 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S425	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S426	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S427	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated	0.105	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.052	0.053	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S428	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	S430	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S431	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S432	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S422	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S423	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S424	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S155	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	S156	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated	0.065	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.035	0.03	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S157	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S158	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S159	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S160	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S161	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S152	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S153	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S154	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S206	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S207	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S208	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S209	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S210	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S211	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S212	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S203	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S204	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S205	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S568	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S569	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S570	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S593	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S566	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S567	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B561	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B556	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated	ND	< 0.0056 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B200	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated	0.25	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.25	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S444	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated	0.5	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.31	0.19	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S445	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated	0.5	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.36	0.14	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S446	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S447	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated	0.27	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.16	0.11	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	B420	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated	0.011	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.011 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S449	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B421	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated	0.216	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.16	0.056	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B419	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated	0.47	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.25	0.22	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B416	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated	0.0067	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0067 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S450	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated	3.9	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2	1.9	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated	0.142	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.079	0.063	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	S442	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated	0.59	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.37	0.22	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	S443	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated	0.82	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.51	0.31	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B417	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	0.106	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.051	0.034	0.021	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S519	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S517	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated	0.033	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.021	0.012 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S518	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	2.58	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	1.5	0.91	0.17	< 0.0070 U	< 0.0027 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	0.206	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.12	0.086	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	0.029	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.0035 U	< 0.0057 U	0.029	< 0.0068 U	< 0.0084 U	< 0.0032 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	4.08	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	2.5	1.4	0.18	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	0.9	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.9	< 0.0056 U	< 0.0069 U	< 0.0027 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	3.29	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	2	1.1	0.19	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated	0.013	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.013 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B782	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	B744	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated	0.043	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.026	0.017 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	0.068	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.068	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	0.06	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.06	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	0.46	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.24	0.22	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	0.214	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.13	0.084	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	0.192	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.11	0.082	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	0.58	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.32	0.26	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	0.039	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.039	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	0.053	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.033	0.02	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	5.1	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	3.7	1.4	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	1.37	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.72	0.65	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated	0.31	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.19	0.12	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated	0.12	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.12	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B781	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated	1.59	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.95	0.45	0.19	< 0.0071 U	< 0.0027 U
Northern Athletic Field	B762	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated	0.0057	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.0057 J	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-S612	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B609	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S614	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	0.34	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.22	0.12	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S615	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	0.22	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.22	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B794	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B791	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated	0.017	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S617	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	0.32	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.32	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B610	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	1.2	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	1.2	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	0.11	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.11	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	0.29	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.14	0.15	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	0.0084	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.0084 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	0.1	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.058	0.042	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	B784	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated	0.141	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.1	0.041	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	ND	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	ISMP-S621	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	0.011	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.011 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S625	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-S629	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	0.051	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.051	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	0.33	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.26	0.07	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S639	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B617	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	0.016	< 0.0070 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	0.016 J	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	ISMP-S640	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	ISMP-S641	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-S643	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	0.012	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	0.012 J	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	ISMP-S645	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	0.096	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.071	0.025	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B618	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	0.217	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.16	0.057	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S647	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	0.059	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.046	0.013 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	0.0084	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.0084 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B729	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	B738	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated	0.173	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.12	0.053	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	0.2	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.2	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B740	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B751	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated	0.049	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.049	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	0.1	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	0.1	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	ND	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	0.0211	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.012 J	0.0091 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	0.172	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.12	0.052	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.758	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.46	0.2	0.098	< 0.0065 U	< 0.0025 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	1.36	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.82	0.4	0.14	< 0.0063 U	< 0.0024 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.89	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.55	0.23	0.11	< 0.0064 U	< 0.0025 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	0.036	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.022	0.014 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	0.064	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.039	0.025	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	0.077	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.047	0.03	< 0.0054 U	< 0.0066 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	0.055	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.026	0.029	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	3	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	3	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S659	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	0.093	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.073	0.02	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	0.04	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.027 B	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S662	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	0.551	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.3 B	0.17	0.081	< 0.0067 U	< 0.0026 U
Football Field	ISMP-S667	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S663	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	0.056	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.034 B	0.022	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S664	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	0.279	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.16 B	0.083	0.036	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B623	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	0.082	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.064 B	0.018 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-S665	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	0.152	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.087 B	0.043	0.022	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S666	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	0.19	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.19	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	0.186	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.074	0.079	0.033	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	0.202	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.093	0.08	0.029	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S401	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-B400	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S405	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	0.015	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	0.012	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	0.0076	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.0076 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	0.04	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.028	0.012 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	0.42	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.42	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	0.37	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.37	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	0.089	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.089	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	0.088	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.054	0.034	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	0.264	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.17	0.094	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	0.089	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.057	0.032	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	0.252	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.11	0.11	0.032	< 0.0068 U	< 0.0026 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	0.0333	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.024	0.0093 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-S417	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S418	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S423	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-B410	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	0.233	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.18	0.053	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	0.013	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.013 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	0.043	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.031	0.012 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	0.079	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.046	0.033	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	0.11	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.08	0.03	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	0.093	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	0.071	0.022	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	0.024	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.014 J	0.01 J	< 0.0069 U	< 0.0026 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	0.077	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.025	0.028	0.024	< 0.0066 U	< 0.0025 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	0.014	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.014 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	0.0229	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.0099 J	0.013 J	< 0.0068 U	< 0.0026 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	0.071	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.043	0.028	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	0.234	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.12	0.073	0.041	< 0.0066 U	< 0.0025 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	0.355	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.2	0.1	0.055	< 0.0067 U	< 0.0026 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	0.031	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.017 J	0.014 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	0.054	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.041	0.013 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	0.011	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.011 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	0.092	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.071	0.021	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	0.024	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.024	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	0.015	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.015 J	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	0.025	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.025	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	0.0311	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.022	0.0091 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	0.09	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.064	0.026	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	0.013	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.013 J	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	0.016	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.016 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	0.041	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.031	0.01 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	0.0081	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0081 JP	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	0.053	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.026	0.027	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	6.53	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	4.5	1.4	0.63	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	0.616	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.37	0.17	0.076	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	2.4	< 0.022 U	< 0.023 U	< 0.016 U	< 0.0097 U	< 0.016 U	2.4	< 0.019 U	< 0.023 U	< 0.0089 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	4.26	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	3.1	0.84	0.32	< 0.0070 U	< 0.0027 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	0.131	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.088	0.029	0.014 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	0.034	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.013 J	0.021	< 0.0067 U	< 0.0026 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	0.01	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.01 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	0.398	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.18	0.18	0.038	< 0.0069 U	< 0.0026 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	0.016	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.016 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	0.081	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.042	0.039	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	0.169	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.13	0.039	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	0.0068	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.0068 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	0.63	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.36	0.27	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	0.085	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.043	0.042	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	0.26	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.16	0.1	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	0.19	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.19	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	0.141	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.11	0.031	< 0.0070 U	< 0.0027 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	0.249	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.16	0.089	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	0.23	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.12	0.11	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	0.204	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.1	0.084	0.02	< 0.0066 U	< 0.0025 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	0.095	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.061	0.034	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	0.023	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	0.023	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.011 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	0.071	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	0.038	0.033	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	0.095	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.063	0.032	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	0.316	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.21	0.068	0.038	< 0.0073 U	< 0.0028 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	0.073	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.04	0.033	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	0.038	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.02	0.018 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	0.271	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.17	0.061	0.04	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	0.0065	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.0065 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	0.012	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	0.012 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	0.245	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.15	0.095	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	0.88	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.67	0.21	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	2.1	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.6	0.5	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	1.64	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.96	0.68	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	0.69	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.41	0.28	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	3.5	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2.6	0.9	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	0.82	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.56	0.26	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	0.043	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.011 J	0.032	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	0.3	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.19	0.11	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	0.031	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.031	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	ND	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.011 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	0.086	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.072	0.014 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	0.86	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.66	0.2	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	0.01	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.01 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	0.262	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.2	0.062	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.011 J	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	0.14	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.14	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	0.12	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.12	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S671	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	0.0078	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.0078 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S674	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	0.0078	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0078 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S670	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	0.015	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S668	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	ISMP-S673	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	0.0268	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.017 J	0.0098 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	0.062	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.044	0.018 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S669	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-S679	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	0.041	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.018	0.023	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	ISMP-S689	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	0.372	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.15	0.14	0.082	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S680	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	0.933	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.6	0.24	0.093	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S690	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	0.351	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.13	0.14	0.081	< 0.0061 U	< 0.0023 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	0.78	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.64	0.14	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	ND	< 0.0084 U	< 0.0092 U	< 0.0063 U	< 0.0038 U	< 0.0062 U	< 0.0078 U	< 0.0074 U	< 0.0091 U	< 0.0035 U
Football Field	ISMP-S695	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-S697	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	ISMP-S701	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S703	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	0.0086	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.0086 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S704	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	0.495	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.25	0.19	0.055	< 0.0071 U	< 0.0027 U
Football Field	ISMP-S702	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	3.21	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.3	0.72	0.19	< 0.0064 U	< 0.0024 U
Football Field	IRM5-S424	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	IRM5-B411	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	0.0058	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.0058 J	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	0.011	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	0.039	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.029	0.01 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	0.089	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.065	0.024	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	0.013	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.013 J	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	0.143	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.086	0.057	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	0.0057	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0057 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	0.038	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.038	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	0.082	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.064	0.018 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	0.59	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.36	0.17	0.06	< 0.0068 U	< 0.0026 U
Football Field	IRM5-S425	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-B412	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-S426	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	IRM5-S435	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	0.099	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.067	0.032	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	ISMP-S706	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	ND	< 0.0070 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	IRM5-S429	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-S431	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	0.015	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.015 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-S433	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	IRM5-S432	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	0.021	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.021	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S73	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.011 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	0.086	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.066	0.02	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	0.164	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.11	0.054	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	0.016	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.016 J	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	4.97	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.1	1.3	0.57	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	0.086	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.047	0.024	0.015 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	0.535	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.27	0.18	0.085	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	0.019	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.019	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	0.122	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.067	0.055	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	0.232	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.14	0.092	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	0.014	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.014 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	0.03	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.03	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	0.062	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.046	0.016 JT	< 0.0066 UT	< 0.0025 UT
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	0.057	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.057	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	0.204	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.16	0.044	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	0.77	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.77	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	0.4	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.4	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	0.22	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.22	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	0.074	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.059	0.015 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	0.36	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.36	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	0.75	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.41	0.34	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	4.9	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	4.9	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	0.052	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.037	0.015 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	0.0076	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0076 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	0.02	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	0.0090 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	0.068	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.05	0.018	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	0.083	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.06	0.023	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	0.37	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.24	0.13	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	0.221	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.16	0.061	< 0.0050 U	< 0.0061 U	< 0.0023 U
Football Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	0.285	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.17	0.081	0.034	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	0.0076	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0076 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	0.021	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.021	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S2003	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	0.186	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.13	0.056	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	0.012	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.012 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	2	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	2	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	0.065	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.065	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	0.014	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.014 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	0.0573	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.029	0.019	0.0093 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	0.034	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.02	0.014 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	0.039	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.026	0.013 J	< 0.0066 U	< 0.0025 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	0.405	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.2	0.14	0.065	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	0.106	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.079	0.027	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	0.168	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.12	0.048	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	0.432	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.3	0.11	0.022	< 0.0064 U	< 0.0024 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	0.054	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.04	0.014 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	0.44	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.24	0.16	0.04	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	0.087	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.063	0.024	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.012 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	0.236	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.13	0.074	0.032	< 0.0064 U	< 0.0024 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	0.017	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.017 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.016 J	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	0.014	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.014 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	0.011	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.011 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	0.047	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	0.033	0.014 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	B704	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	0.117	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.096	0.021	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	0.084	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.065	0.019	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	0.521	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.33	0.14	0.051	< 0.0064 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	0.325	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.21	0.08	0.035	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	0.049	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.032	0.017 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	0.103	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.088	0.015 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	0.551	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.3	0.19	0.061	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	1.2	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1	0.2	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	0.013	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.013 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	0.192	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.16	0.032	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	0.0367	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.028	0.0087 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	0.176	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.14	0.036	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	0.025	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.025	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	1.9	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	1.5	0.4	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	0.039	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.039	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	0.046	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.046	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	0.012	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.012 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	0.041	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.041	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	0.065	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.052	0.013 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	0.03	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.03	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	0.016	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.016 J	< 0.0054 U	< 0.0052 UT	< 0.0064 U	< 0.0024 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	0.038	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.038	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	0.03	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.03	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.029	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	0.288	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.22	0.068 P	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	0.056	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.045	0.011 J	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	0.152	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.11	0.042	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	0.0098	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0098 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	0.6	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.47	0.13	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	0.328	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.26	0.068	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	0.178	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.097	0.081	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	0.96	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	0.96	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	0.021	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.021	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	ND	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0039 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	0.8	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.62	0.18	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	0.023	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.023	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	0.062	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.062	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	0.106	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.074	0.032	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	0.19	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.19	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	0.731	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.5	0.18	0.051	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	0.017	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.017 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	0.078	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.041	0.037	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	0.17	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.17	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	0.82	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.56	0.26	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	0.0323	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.023	0.0093 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	0.225	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.16	0.065	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	0.102	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.065	0.037	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	0.285	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.2	0.085	< 0.0063 U	< 0.0024 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	0.3	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.18	0.12	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	0.175	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.12	0.055	< 0.0066 U	< 0.0025 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	0.37	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.22	0.15	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	0.068	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.046	0.022	< 0.0062 U	< 0.0024 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	0.088	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.061	0.027	< 0.0064 U	< 0.0025 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	0.12	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.12	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	0.045	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.045	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	1.8	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	1.8	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	0.196	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.14	0.056	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	0.099	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.025	0.047	0.027	< 0.0065 U	< 0.0025 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	0.06	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.014 J	0.046	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	0.01	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.01 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	0.16	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.16	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	1.3	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.97	0.3	0.03	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	0.074	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.048	0.026	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	1.6	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	1.6	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	0.41	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.25	0.16	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	0.25	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.12	0.13	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	0.175	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.11	0.065	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	0.036	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.022	0.014 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	0.59	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.39	0.2	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	0.093	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.037	0.056	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	0.026	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.018	0.0080 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	0.093	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.051	0.042	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	0.72	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.36	0.36	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	0.024	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.024	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	0.0367	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.028	0.0087 J	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	0.116	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.068	0.048	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	0.086	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.055	0.031	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	0.128	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.083	0.045	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	0.116	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.073	0.043	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	0.121	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.083	0.038	< 0.0062 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	0.103	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.07	0.033	< 0.0064 U	< 0.0024 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	0.066	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.051	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	0.039	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.039	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	0.031	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.031	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	0.026	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.026	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	ND	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated	0.72	< 0.0086 U	< 0.0094 U	< 0.0064 U	< 0.0039 U	< 0.0063 U	0.4	0.32	< 0.0093 U	< 0.0036 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	0.166	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.1	0.066	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	0.255	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0032 U	0.13	0.1	0.025	< 0.0078 U	< 0.0030 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	0.077	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.046	0.031	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	0.227	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.15	0.077	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	0.113	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.07	0.043	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	0.0214	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.012 J	0.0094 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	0.047	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.02	0.027	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	0.034	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.02	0.014 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	0.027	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	0.014 J	0.013 J	< 0.0074 U	< 0.0028 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	0.043	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	0.016 J	0.027	< 0.0073 U	< 0.0028 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	0.012	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.012 J	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	0.028	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.016 J	0.012 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	0.0515	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.022	0.021	0.0085 J	< 0.0073 U	< 0.0028 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	0.046	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.017 J	0.017 J	0.012 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	0.069	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.053	0.016 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	0.12	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.041	0.049	0.03	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	0.03	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.017 J	0.013 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	0.069	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.048	0.021	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	0.057	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.019	0.022	0.016 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	0.213	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.13	0.061	0.022 T	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	0.346	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.16	0.13	0.056	< 0.0070 U	< 0.0027 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	0.214	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.062	0.091	0.061	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	0.085	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.033	0.035	0.017 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	0.075	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.035	0.026	0.014 J	< 0.0070 U	< 0.0027 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	0.476	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.2	0.19	0.086	< 0.0059 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	2.9	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	1.4	1.2	0.3	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	0.316	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.14	0.11	0.066	< 0.0059 U	< 0.0023 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	2.63	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	1.2	1.1	0.33	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	0.011	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	0.0095	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.0095 J	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	0.088	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.029	0.036	0.023	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	0.0226	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.014 J	0.0086 J	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	0.07	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.024	0.028	0.018	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	0.0219	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.012 J	0.0099 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	0.01	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.01 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	0.046	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.028	0.018 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	0.0514	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.022	0.022	0.0074 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	0.0167	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0082 J	0.0085 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	0.087	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.031	0.036	0.02	< 0.0067 U	< 0.0026 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	0.0099	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.0099 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	0.121	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.064	0.043	0.014 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	ND	< 0.0085 U	< 0.0093 U	< 0.0064 U	< 0.0038 U	< 0.0063 U	< 0.0079 U	< 0.0075 U	< 0.0092 U	< 0.0035 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	0.96	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.67	0.29	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	0.013	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.013 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	0.88	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.66	0.22	< 0.0063 U	< 0.0024 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	0.019	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	0.019	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	0.011	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.011 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	0.009	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0090 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	0.182	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.11	0.072	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	0.039	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.039	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	0.01	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.01 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	0.16	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.16	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	0.0071	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.0071 J	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	0.011	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.011 J	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	0.024	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.024	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	0.061	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.061	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	1.214	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.7	0.46	0.054	< 0.0065 U	< 0.0025 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	0.051	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.03	0.021	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	1.61	< 0.0079 U	< 0.0086 U	< 0.0059 U	< 0.0035 U	< 0.0058 U	0.98	0.63	< 0.0085 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	0.056	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.036	0.02	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	0.06	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.06	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	0.086	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.086	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	0.027	< 0.0056 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.016 J	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	0.0231	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.015 J	0.0081 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	0.13	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.13	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	0.047	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.031	0.016 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	0.0346	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.025	0.0096 J	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	0.193	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	0.14	0.053	< 0.0046 U	< 0.0057 U	< 0.0022 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	0.011	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.011 J	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	0.045	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.029	0.016 J	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	2.54	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.8	0.58	0.16	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	0.017	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.017 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	0.013	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.013 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	0.02	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.02	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	0.193	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14	0.053	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	0.017	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.017	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	0.009	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0090 J	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	0.194	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.13	0.064	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	0.53	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.28	0.25	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	0.029	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	0.029	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	0.091	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.045	0.046	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	1.16	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.55	0.43	0.18	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	0.0076	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.0076 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	ND	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0039 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	0.475	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.29	0.15	0.035	< 0.0064 U	< 0.0024 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	1.009	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.73	0.24	0.039	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	0.327	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.18	0.11	0.037	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	0.059	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.042	0.017 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	0.045	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.023	0.022	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	0.13	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.13	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	0.047	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.031	0.016 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	0.11	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.046	0.048	0.016 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	0.149	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.07	0.055	0.024	< 0.0067 U	< 0.0025 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	0.335	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.17	0.13	0.035	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.011 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	0.11	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.11	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	0.036	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.022	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	0.0269	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.017 J	0.0099 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	0.0926	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.054	0.029	0.0096 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	0.09	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.046	0.03	0.014 J	< 0.0073 U	< 0.0028 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	0.031	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.016 J	0.015 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	0.028	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.028	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	0.498	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.27	0.18	0.048	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	0.032	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.018	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	1.23	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.7	0.37	0.16	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	0.0619	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.032	0.022	0.0079 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	0.074	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.045	0.029	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	0.072	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.034	0.024	0.014 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	0.053	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.031	0.022	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	ND	< 0.0085 U	< 0.0092 U	< 0.0064 U	< 0.0038 U	< 0.0063 U	< 0.0078 U	< 0.0074 U	< 0.0092 U	< 0.0035 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	0.245	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.054	0.091	0.1	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	0.035	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.024	0.011 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	0.066	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.038	0.028	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	0.062	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.022	0.018	0.022	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	0.0332	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.016 J	0.0085 J	0.0087 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	ND	< 0.0089 U	< 0.0097 U	< 0.0067 U	< 0.0040 U	< 0.0066 U	< 0.0082 U	< 0.0078 U	< 0.0097 U	< 0.0037 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	0.0055	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0055 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	0.65	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.65	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	0.0054	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.0054 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	0.047	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.024	0.023	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	0.113	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.059	0.038	0.016 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	0.078	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.038	0.026	0.014 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	0.03	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.013 J	0.017 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	1.8	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	1.8	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	0.71	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.71	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	0.43	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.43	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.012 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	0.0097	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.0097 J	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	0.38	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.38	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	0.013	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.013 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	0.193	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.12	0.073	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	0.063	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.031	0.032	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	0.017	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.017	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	0.1238	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.078	0.037	0.0088 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	0.046	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.034	0.012 J	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	0.016	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.016 J	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	0.13	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.081	0.049	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	0.01	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.01 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	0.028	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.028	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	0.02	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.02	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	0.047	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.028	0.019	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	0.3	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.19	0.11	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	0.248	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12	0.1	0.028	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	0.26	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.26	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	0.117	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.064	0.053	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	0.81	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.81	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	0.094	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.044	0.05	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	0.206	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.13	0.062	0.014 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	0.24	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.15	0.09	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	0.095	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.06	0.035	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	0.74	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.74	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	0.047	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.024	0.023	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	0.0174	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.011 J	0.0064 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	0.02	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.02	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	0.042	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.042	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	0.023	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.023	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	0.44	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.44	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	0.033	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.014 J	0.019	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	0.046	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.046	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	0.221	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.03	0.12	0.071	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	0.134	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.042	0.092	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	0.191	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.058	0.083	0.05	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	0.044	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.013 J	0.031	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	0.23	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	0.23	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	0.038	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.019	0.019	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	0.087	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.069	0.018	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	0.563	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.4	0.14	0.023	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	0.084	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.06	0.024	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	0.0203	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.013 J	0.0073 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	0.0318	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.022	0.0098 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	0.008	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0080 J	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	0.043	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.03	0.013 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	0.0275	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.019	0.0085 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	0.078	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.06	0.018	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	0.025	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.01 J	0.015 J	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	0.011	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.011 J	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	0.04	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.021	0.019	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	0.87	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.63	0.21	0.03	< 0.0059 U	< 0.0023 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	0.187	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.13	0.046	0.011 J	< 0.0066 U	< 0.0025 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	0.512	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.37	0.12	0.022	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	0.136	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.093	0.043	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	0.051	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.034	0.017	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	0.01	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.01 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	0.35	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.19	0.11	0.05	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	0.645	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.34	0.23	0.075	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	0.0168	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0094 J	0.0074 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	0.242	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.15	0.092	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	0.0226	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.013 J	0.0096 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	0.037	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.019	0.018	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	0.023	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.01 J	0.013 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	0.0177	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0098 J	0.0079 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	0.371	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.19	0.14	0.041	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	0.031	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.014 J	0.017 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	0.05	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.029	0.021	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	0.041	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.02	0.021	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	ND	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	0.031	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.02	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	0.055	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.023	0.022	0.01 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	ND	< 0.0056 UT	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 UT	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	0.04	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.026	0.014 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	0.012	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.012 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	0.05	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.031	0.019	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	0.113	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.033	0.051	0.029	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	0.959	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.61	0.3	0.049	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	0.325	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.17	0.12	0.035	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	0.077	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.029	0.048	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	0.012	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	0.012 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	0.0444	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.022	0.016 J	0.0064 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	0.0082	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0082 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	0.012	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.012 J	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	0.071	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.071	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	0.073	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.032	0.024	0.017	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	0.014	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	0.014 J	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	0.0083	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0083 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	0.043	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.032	0.011 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	0.0097	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.0097 J	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.011 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	1.162	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.7	0.4	0.062	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	0.074	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.059	0.015 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	0.01	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	0.01 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	0.0097	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	0.0097 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	0.048	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	0.048	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	0.006	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	0.0060 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	0.0062	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.0062 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	0.041	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.023	0.018	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	0.0083	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0083 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	0.0194	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.01 J	0.0094 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	0.0508	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.024	0.021	0.0058 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	0.0077	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.0077 J	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	0.104	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.058	0.046	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	0.023	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.023	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	0.084	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.054	0.03	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	0.046	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.027	0.019	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	0.171	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.12	0.051	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	0.3	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.18	0.12	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	ND	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	0.079	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.04	0.027	0.012 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	0.133	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.077	0.044	0.012 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	0.0603	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.029	0.022	0.0093 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	0.017	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.017	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	ND	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0039 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	0.128	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.073	0.055	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	0.047	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.022	0.025	< 0.0070 U	< 0.0027 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	0.016	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	0.016 J	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	0.23	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.13	0.076	0.024	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	0.234	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.17	0.064	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	0.0082	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0082 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	0.0065	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0065 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	0.096	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056	0.028	0.012 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	0.407	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.25	0.12	0.037	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	0.183	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.098	0.063	0.022	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	0.135	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.067	0.05	0.018	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	0.316	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.19	0.094	0.032	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	0.021	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.0076 J	0.0065 J	0.0069 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	0.0344	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	0.015 J	0.0084 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	1.6	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.45	0.71	0.44	< 0.0070 U	< 0.0027 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	0.318	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.097	0.14	0.081	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	0.149	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.063	0.065	0.021	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	0.181	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	0.11	0.059	0.012 J	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	0.0819	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.044	0.029	0.0089 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	0.0614	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.032	0.023	0.0064 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	0.0157	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0091 J	0.0066 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	0.0289	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.02	0.0089 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	0.0482	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.023	0.019	0.0062 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	0.028	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.018	0.01 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	0.074	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.028	0.033	0.013 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	0.0451	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.018	0.019	0.0081 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	0.032	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.017 J	0.015 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	0.089	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.035	0.054	< 0.0068 U	< 0.0026 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	0.014	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.014 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	0.042	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.02	0.022	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.012 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	0.0089	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0089 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	0.01	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.01 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	0.052	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.027	0.025	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	0.0097	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.0097 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	0.035	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.015 J	0.02	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	0.028	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	0.014 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	0.0164	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.0079 J	0.0085 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	0.017	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	0.017	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	0.0096	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.0096 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	0.0217	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.013 J	0.0087 J	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	0.0154	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0084 J	0.0070 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	0.0142	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0069 J	0.0073 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	0.0156	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.0072 J	0.0084 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	0.0471	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.017 J	0.022	0.0081 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.018	0.011 J	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	ND	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	0.0098	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.0098 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	1.321	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.54	0.7	0.081	< 0.0061 U	< 0.0023 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	0.26	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.073	0.16	0.027	< 0.0063 U	< 0.0024 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	17.66	< 0.058 U	< 0.063 U	< 0.044 U	< 0.026 U	12	4.7	0.96	< 0.063 U	< 0.024 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	12.39	< 0.058 U	< 0.063 U	< 0.044 U	< 0.026 U	8.3	3.4	0.69	< 0.063 U	< 0.024 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	0.081	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.051	0.03	< 0.0049 UT	< 0.0061 UT	< 0.0023 UT
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	9.91	< 0.057 U	< 0.062 U	< 0.043 U	< 0.026 U	6.6	2.7	0.61	< 0.062 U	< 0.024 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	0.179	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.099	0.064	0.016 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	ND	< 0.0054 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	0.0813	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.045	0.029	0.0073 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	0.0065	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.0065 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	6.62	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	4.2	2	0.42	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	0.223	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.13	0.074	0.019	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	0.309	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.17	0.11	0.029	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	0.54	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.31	0.18	0.05	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	0.356	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.2	0.12	0.036	< 0.0062 U	< 0.0024 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	0.0184	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.012 J	0.0064 J	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	0.0079	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0079 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	0.116	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.065	0.04	0.011 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	0.032	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.032	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	ND	< 0.0059 UT	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 UT	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	ND	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0039 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	0.01	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	0.01 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	0.0249	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.017 J	0.0079 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	ND	< 0.0089 U	< 0.0096 U	< 0.0066 U	< 0.0040 U	< 0.0065 U	< 0.0082 U	< 0.0077 U	< 0.0096 U	< 0.0037 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	0.79	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.36	0.28	0.15	< 0.0069 U	< 0.0026 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	0.0175	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0077 J	0.0098 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	0.067	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.033	0.034	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	0.018	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.018	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	0.235	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.14	0.075	0.02	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	0.044	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.029	0.015 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	0.036	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.023	0.013 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	0.0088	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.0088 J	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	0.89	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.33	0.43	0.13	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	0.479	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.35	0.098	0.031	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	0.063	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.042	0.021	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	0.143	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.085	0.047	0.011 J	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	0.03	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.019	0.011 J	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	0.141	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.093	0.048	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	0.013	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.013 J	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	0.0273	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.018	0.0093 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	0.21	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.14	0.07 P	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	0.024	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.014 J	0.01 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	0.0082	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.0082 J	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	0.216	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.13	0.07	0.016 J	< 0.0061 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	0.0088	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.0088 J	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	0.041	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.022	0.019	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	0.0758	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	0.035	0.033	0.0078 J	< 0.0059 U	< 0.0022 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	ND	< 0.0053 U	< 0.0057 U	< 0.0040 U	< 0.0024 U	< 0.0039 U	< 0.0049 U	< 0.0046 U	< 0.0057 U	< 0.0022 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1802429561	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1802429561	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1802429561	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1802429561	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1802429561	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	0.09	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.049	0.041	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1802429561	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1802429561	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1802429561	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1802429561	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1802429561	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1802429561	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	0.023	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.012 J	0.011 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	0.06	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.033	0.027	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27	8/15/2022	-	-	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	0.165	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.11	0.044	0.011 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	0.0197	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.0099 J	0.0098 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	0.0323	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.023	0.0093 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	0.0551	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.028	0.021	0.0061 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	0.031	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.019	0.012 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	0.363	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.2	0.12	0.043	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	0.024	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.013 J	0.011 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	0.323	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.2	0.11	0.013 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	0.056	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.034	0.022	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	0.06	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.033	0.027	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	0.029	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.015 J	0.014 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	0.29	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	0.18	0.11	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	0.066	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	0.04	0.026	< 0.0047 U	< 0.0058 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	0.06	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.032	0.028	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	0.177	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.098	0.068	0.011 J	< 0.0072 U	< 0.0027 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	0.198	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.065	0.1	0.033	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	0.23	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.23	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	0.228	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.15	0.078	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	0.58	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.58	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	0.02	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.02	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	0.05	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.05	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	0.037	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.037	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	0.096	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.061	0.035	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	0.073	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.043	0.03	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	0.091	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.06	0.031	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	0.12	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.12	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	0.059	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.025	0.021	0.013 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	0.157	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.11	0.047	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	0.0087	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.0087 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	0.124	< 0.0087 U	< 0.0095 U	< 0.0065 U	< 0.0039 U	< 0.0064 U	0.08	0.044	< 0.0094 U	< 0.0036 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	0.11	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.051	0.041	0.018 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	0.106	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.05	0.038	0.018	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	0.04	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.022	0.018	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	0.084	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.037	0.03	0.017 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	0.0056	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	0.0056 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	0.034	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.02	0.014 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	0.0484	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.02	0.019	0.0094 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	0.22	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.22	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	0.035	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.024	0.011 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	0.009	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.0090 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	0.0219	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.014 J	0.0079 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	0.036	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.024	0.012 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	0.0052	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0052 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	ND	< 0.0053 U	< 0.0058 U	< 0.0040 U	< 0.0024 U	< 0.0039 U	< 0.0049 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	0.045	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.03	0.015 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	0.226	< 0.0090 U	< 0.0098 U	< 0.0068 U	< 0.0041 U	0.15	0.076	< 0.0079 U	< 0.0098 U	< 0.0037 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	0.024	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.024	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	0.102	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.041	0.061	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.2	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.2	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.95	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.95	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	0.31	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.31	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	0.11	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.11	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	0.026	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.026	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	0.16	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.16	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	0.38	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.38	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	0.24	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.24	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	0.0091	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.0091 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	0.046	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.046	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	0.022	< 0.0054 U	< 0.0059 U	< 0.0040 U	< 0.0024 U	0.022	< 0.0050 U	< 0.0047 U	< 0.0058 U	< 0.0022 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	0.0052	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.0052 J	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	0.02	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.02	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	0.014	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.014 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	0.264	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.19	0.074	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	0.12	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.12	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	0.0099	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0099 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	0.516	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.18	0.25	0.086	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	0.032	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.019	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	0.026	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.026	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	0.14	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.14	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	0.011	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	ND	< 0.0000065 U	< 0.0000071 U	< 0.0000049 U	< 0.0000029 U	< 0.0000048 U	< 0.0000060 U	< 0.0000057 U	< 0.0000070 U	< 0.0000027 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	0.77	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.39	0.38	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	0.108	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.057	0.051	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	1.3	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	1.3	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	0.12	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.12	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	0.0072	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.0072 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	0.035	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.02	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.037	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	0.024	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.024	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	0.0274	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.018 J	0.0094 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	ND	< 0.0074 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0080 U	< 0.0030 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	0.0092	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0092 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	0.049	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.034	0.015 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	0.013	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.013 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	0.0327	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.023	0.0097 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	0.094	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.066	0.028	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	0.0074	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.0074 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	0.0283	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.019	0.0093 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	0.017	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.017 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.013	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.013 J	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.0030 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	0.044	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.031	0.013 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.138	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.11	0.028	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	0.055	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.036	0.019	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	0.09	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.05	0.04	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	0.065	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.022	0.031	0.012 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	0.069	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.043	0.026	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	0.023	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.023	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	ND	< 0.0059 UT	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UT	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	7.96	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	5	2.5	0.46 P	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	0.27	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.13	0.14	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	0.0173	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.0073 J	0.01 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	0.029	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.029	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	0.051	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.017	0.034	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	0.076	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.041	0.035	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	0.113	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.052	0.061	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.45	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	0.0084	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0084 JP	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	0.012	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.012 JP	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	0.068	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.03	0.028	0.01 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	0.117	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.04	0.077	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	0.066	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.045	0.021 T	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	0.0069	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.0069 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	0.018	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.018	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	0.0073	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.0073 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	0.021	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	0.021	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	0.0079	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	0.0079 J	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	0.029	< 0.012 U	< 0.013 U	< 0.0089 U	< 0.0054 U	< 0.0088 U	< 0.011 U	0.029 J	< 0.013 U	< 0.0049 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	0.015	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	0.015 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	0.0077	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	0.0077 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	0.011	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	0.011 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	ND	< 0.012 U	< 0.013 U	< 0.0088 U	< 0.0053 U	< 0.0086 U	< 0.011 U	< 0.01 U	< 0.013 U	< 0.0048 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	ND	< 0.013 U	< 0.014 U	< 0.0097 U	< 0.0058 U	< 0.0096 U	< 0.012 U	< 0.011 U	< 0.014 U	< 0.0054 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	0.0245	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.019	0.0055 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	0.14	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	0.14	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	0.013	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.013 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	0.014	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	0.013	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	0.013 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	0.011	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	0.011	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	0.011 J	< 0.0067 U	< 0.0026 U

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	0.2574	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.18	0.068	0.0094 J	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	0.032	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.032	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	0.351	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.25	0.089	0.012 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	0.083	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.059	0.024	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	0.85	< 0.0070 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.58	0.23	0.04	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	0.062	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.041	0.021	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	0.118	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.054	0.049	0.015 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	0.031	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.016 J	0.015 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	0.079	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.048	0.031	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	0.049	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	0.049	< 0.0059 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	0.1	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.1	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	0.018	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.018	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	0.08	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.08	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	0.0094	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.0094 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	0.25	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.25	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	0.044	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.03	0.014 J	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	0.56	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.56	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	0.22	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	0.22	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	0.035	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.023	0.012 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	0.16	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.16	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	0.048	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.037	0.011 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	0.062	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.062	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	0.244	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.15	0.076	0.018 J	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	1.62	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.93	0.55	0.14	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	0.314	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.19	0.1	0.024	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	0.029	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.029	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	0.012	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.012 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	0.014	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.014 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	0.389	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.23	0.14	0.019 J	< 0.0070 U	< 0.0027 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	0.0092	< 0.0070 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	0.0092 J	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	0.013	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.013 J	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	0.032	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.021	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	0.0216	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	0.0096 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	0.012	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.012 J	< 0.0064 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	0.247	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.14	0.087	0.02	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	0.246	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.15	0.082	0.014 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0060 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	0.0521	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.025	0.02	0.0071 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	0.0096	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.0096 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	0.0907	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.056	0.028	0.0067 J	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	0.67	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.25	0.3	0.12	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	0.036	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.02	0.016 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	0.096	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.066	0.03	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	0.0086	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0086 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	0.01	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.01 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	0.047	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	0.047	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	0.0067	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0067 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	0.0078	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0078 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	0.282	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.2	0.082	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	0.095	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.051	0.044	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	0.033	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.033	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	0.064	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.064	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	0.0083	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.0083 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	1.17	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.49 P	0.51	0.17	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	0.0092	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.0092 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	0.0181	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.011 J	0.0071 J	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	0.817	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.35 P	0.37	0.097 P	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	0.0761	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.042	0.025	0.0091 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	2.96	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1.7	1	0.26	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	1.45	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.86	0.48	0.11	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	1.3	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.8	0.39	0.11	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.102	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.07	0.032	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	0.022	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.022	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.102	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.07	0.032	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	0.022	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.022	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	0.3	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.18	0.099	0.021	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.20	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	0.0074	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0074 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	0.03	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.02	0.01 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	0.043	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	0.043	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	0.181	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.12	0.061	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	0.147	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.1	0.047	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	0.056	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.039	0.017	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.071	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.051	0.02	< 0.0058 U	< 0.0071 U	< 0.0027 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	0.104	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.063	0.041	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	1.1	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	1.1	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	0.013	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.013 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	0.043	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	0.043	< 0.0051 U	< 0.0064 U	< 0.0024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	0.044	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	0.044	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	0.0096	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0096 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	0.016	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.016 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	ND	< 0.0060 UJ	< 0.0065 UJ	< 0.0045 UJ	< 0.0027 UJ	< 0.0044 UJ	< 0.0055 UJ	< 0.0052 UJ	< 0.0065 UJ	< 0.0025 UJ
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	0.013	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.013 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	0.017	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.017 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	0.059	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.037	0.022	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	0.47	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	0.47	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	0.022	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.022	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	1.6	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	1.6	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	0.24	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.24	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	0.77	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.77	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	0.016	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	0.038	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.028	0.01 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	0.0086	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.0086 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	0.0096	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.0096 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	ND	< 0.0074 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0065 U	< 0.0080 U	< 0.0031 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	0.019	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.019	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0024 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	ND	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	0.0071	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.0071 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	0.0071	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.0071 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	0.0228	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.014 J	0.0088 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	ND	< 0.0070 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	0.67	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.36	0.31	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	0.298	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.22	0.078	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	0.0184	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.012 J	0.0064 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	0.29	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	0.19	0.1	< 0.0067 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	0.084	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.055	0.029	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	0.025	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.013 J	0.012 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	0.54	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.29	0.25	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	0.406	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	0.31	0.096	< 0.0061 U	< 0.0023 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	LP2-2	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	LP2-3	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	LP2-5	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	LP1-1	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	LP1-3	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	LP1-4	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	LP1-5	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	0.082	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	0.054	0.028	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	0.011	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.011 J	< 0.0050 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	0.011	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.011 J	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.011 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0040 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	0.0079	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0079 JP	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	0.035	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.035	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	0.045	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.045	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	0.033	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.033	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	0.25	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.25	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	0.16	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.16	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	0.033	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.033	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	0.026	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	0.026	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	0.0094	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.0094 J	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	0.017	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.017 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	0.032	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.032	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	0.011	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	0.011 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	0.276	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.091	0.13	0.055	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	0.006	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	0.0060 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	0.013	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.013 J	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	0.016	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.016 J	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	0.027	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.027	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	0.044	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	0.025	0.019 J	< 0.0073 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	0.019	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.019	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	ND	< 0.0060 UT	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 UT	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	0.023	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.015 J	0.0080 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	0.01	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	0.01 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	0.01	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	0.01 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	0.072	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.072	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	0.069	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.045	0.024	< 0.0067 U	< 0.0026 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	0.011 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	0.171	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.082	0.089	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.0030 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.0030 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	0.105	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.05	0.055	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	ND	< 0.0068 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	0.096	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.03	0.066	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	0.056	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	0.025	0.031	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	ND	< 0.0068 U	< 0.0073 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	0.04	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	0.04	< 0.0068 U	< 0.0026 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	ND	< 0.0077 U	< 0.0084 U	< 0.0058 U	< 0.0035 U	< 0.0057 U	< 0.0071 U	< 0.0067 U	< 0.0083 U	< 0.0032 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	0.059	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	0.059	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	0.048	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	0.048	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	0.2	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	0.05 P	< 0.0073 U	0.15
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	0.049	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.03	0.019	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	0.092	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.045	0.032	0.015 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	0.017	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.017 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	0.016	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.016 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	0.028	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	0.028	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	0.058	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.035	0.023	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	0.041	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.02	0.021	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	0.14	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	0.061	< 0.0068 U	0.079
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	ND	< 0.0070 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	0.041	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.023	0.018 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	2	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	2	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	0.41	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.41	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	0.014	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	0.014 J	< 0.0076 U	< 0.0029 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	0.046	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.021	0.025	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.016	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	0.016 J	< 0.0062 U	< 0.0024 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	0.14	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.14	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	0.034	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.034	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0063 UT	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 UT	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.014 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	0.02	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.012 J	0.0080 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	0.046	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.033	0.013 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	0.0092	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.0092 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	0.52	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.32	0.2	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.042	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.031	0.011 J	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.397	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	0.2	0.17	0.027	< 0.0081 U	< 0.0031 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	0.364	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.17	0.14	0.054	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.0079	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.0079 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.0271	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	0.019 J	0.0081 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.019	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	0.019 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.122	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.059	0.046	0.017 J	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.05	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	0.035	0.015 J	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.31	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.17	0.11	0.03	< 0.0077 U	< 0.0029 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.97	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.61	0.32	0.04	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.018	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.018 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.341	< 0.0074 U	< 0.0081 U	< 0.0055 U	< 0.0033 U	0.18	0.13	0.031	< 0.0080 U	< 0.0031 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.179	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.1	0.065	0.014 J	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.505	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.31	0.15	0.045	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	0.08	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.044	0.026	0.01 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	0.028	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.028	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	0.016	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	0.016 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	0.029	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.029	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	0.186	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.11	0.076	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	0.14	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.086	0.054	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	0.86	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	0.5	0.36	< 0.0066 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	0.034	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022	0.012 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	0.047	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.029	0.018 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	0.197	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.12	0.077	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	0.027	< 0.0063 UT	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.027	< 0.0058 U	< 0.0055 UT	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	0.199	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.12	0.079	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	0.579	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.32	0.19	0.069	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	0.267	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.17	0.097	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	0.01	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.01 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	0.048	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.025	0.023	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	0.402	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.16	0.17	0.072	< 0.0061 U	< 0.0023 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	0.022	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.012 J	0.01 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	0.035	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.02	0.015 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	0.09	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.047	0.034	0.0090 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	1.07	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.42	0.49	0.16	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	0.371	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.081	0.18	0.11	< 0.0064 U	< 0.0025 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	0.257	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.096	0.11	0.051	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	0.108	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.06	0.048	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	0.53	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.18	0.24	0.11	< 0.0062 U	< 0.0024 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	0.288	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.19	0.098	< 0.0064 U	< 0.0024 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	0.288	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.1	0.13	0.058	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	0.113	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.074	0.039	< 0.0063 U	< 0.0024 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	0.172	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	0.11	0.062	< 0.0073 U	< 0.0028 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 UT	< 0.0068 UT	< 0.0026 UT
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 UT	< 0.0073 UT	< 0.0028 UT
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 UT	< 0.0026 UT
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 UT	< 0.0068 UT	< 0.0026 UT
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 UT	< 0.0064 UT	< 0.0024 UT
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 UT	< 0.0066 UT	< 0.0025 UT
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 UT	< 0.0071 UT	< 0.0027 UT
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 UT	< 0.0072 UT	< 0.0027 UT
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 UT	< 0.0067 UT	< 0.0026 UT
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 UT	< 0.0071 UT	< 0.0027 UT

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	0.116	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.085	0.031	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	0.033	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.022	0.011 J	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	0.127	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.1	0.027	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	0.141	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.099	0.042	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	0.079	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.055	0.024	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	0.015	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.015 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	0.13	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.13	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	0.23	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	0.23	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	0.01	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	0.01 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	0.013	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.013 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	0.228	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.14	0.072	0.016 J	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	0.014	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.014 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	0.0074	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	0.0074 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	0.0219	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.013 J	0.0089 J	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	ND	< 0.0074 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0080 U	< 0.0030 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	0.037	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	0.037	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	0.0244	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.015 J	0.0094 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	0.057	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.024	0.011 JP	0.022	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	0.27	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12	0.15	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	0.085	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.032	0.018	0.035	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.011 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.16	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.16	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	0.0288	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.019	0.0098 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.175	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.063	0.036	0.076	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	0.061	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.017 J	0.019	0.025	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	0.149	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.032 P	0.017 P	0.1	< 0.0061 UT	< 0.0023 UT
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	0.145	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.031 P	0.031	0.083	< 0.0073 UT	< 0.0028 UT
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	0.108	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.03	0.016 JP	0.062	< 0.0066 UT	< 0.0025 UT
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	0.079	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	0.024	0.011 JP	0.044	< 0.0071 UT	< 0.0027 UT
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	0.062	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.019	0.014 JP	0.029	< 0.0064 UT	< 0.0024 UT
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	0.112	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.028	0.037	0.047	< 0.0068 UT	< 0.0026 UT
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	0.068	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.016 J	0.017 J	0.035	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	0.048	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.012 J	0.015 J	0.021	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	0.33	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.33	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	0.25	< 0.0073 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	0.15	0.1	< 0.0064 U	< 0.0079 U	< 0.0030 U
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0024 U	< 0.0040 U	< 0.0050 U	< 0.0047 U	< 0.0059 U	< 0.0022 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.0093	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	0.0093 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.012	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	0.012 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.053	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	0.028	0.025	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.065	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	0.045	0.02	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.014	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.014 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.011	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	0.011 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.155	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.056	0.059	0.04	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.009	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	0.0090 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.013	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.013 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	0.026	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.026	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 6-3A
Subsurface Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	0.0088	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	0.0088 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	0.013	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	< 0.0052 U	0.013 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.0030 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	ND	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0060 U	< 0.0023 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	ND	< 0.0065 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.0050 U	< 0.0061 U	< 0.0023 U

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	8260	< U	6.2	58.3	0.34	1.5	9740	11.1 *E	< U		37.9	20600
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	9510	0.25	8.2	89.3	0.42	1.9	19100	15.9 *E	< U		65.7	25500
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	5620	0.14	5.8	111	0.24	1.8	22300	12.8 *E	< U		70	17300
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	9480	0.43	7.6	118	0.41	2.2	15600	20 *E	< U		244	28700
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated												
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated												
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated												
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated												
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	11000	< 0.43 U	6.9	95	0.52	0.14 J	2100	14		9.1	18	20000
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated	5100	< 0.22 U	3.4	39	0.22 J	0.093 J	25000	7.3		5.3	24	12000
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	7800	0.31 J	6.2	71	0.32	0.25 J	19000	13		6.4	52	22000
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated	7200	0.56 J	6.9	77	0.31 J	0.19 J	32000	16		6.2	53	20000
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	6100	0.82 J	4.6	45	0.25 J	0.16 J	35000	8.2		5.3	28	14000
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated												
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	15000	< 5.1 U	44	110	0.59	0.16 J	7300	19		12	25	33000
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	14000	< 5.3 U	21 J	94	0.57	0.12 J	5900	17		12	23	31000
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.38	855.38	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	13000	< 5.6 U	9.8 J	74	0.44 J	< 0.56 U	63000	17		10	28	32000
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.80	854.80	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	10000	< 5.6 U	6.8	52	0.35 J	< 0.56 U	42000	13		8.0	23	23000
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.40	855.40	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	8000 T	< 5.1 U	8.2 J	60 T	0.23 J	0.19 J	100000 T	13		5.7	21	18000 T
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated	5700	< 0.39 U	5.4	38	0.25 J	< 0.042 U	930	7.8		5 J	22	14000
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated	7200	< 0.39 U	8	52	0.32 J	0.087 J	1800	9.2		6.2	25	18000
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated	6300	2.7	6.5	75	0.31 J	0.1 J	5700	10		6.1	20	15000
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated	7000	< 0.38 U	5.2	53	0.28 J	0.089 J	1900	9.3		5.4 J	21	16000
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated	5700	< 0.36 U	4.5	39	0.24 J	0.083 J	47000	9.3		5.2 J	23	14000
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated	7000	< 0.39 U	5.8	77	0.32 J	0.13 J	21000	15		6.7	68	22000
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated	8300	0.82 J	7.5	92	0.45 J	0.94	16000	34		5.9	120	20000
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated	7300	< 0.39 U	6.9	63	0.33 J	0.13 J	12000	13		7.5	49	20000
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated	6400	< 0.36 U	7	51	0.23 J	0.058 J	51000	9.9		5.9	24	15000
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated	6400	< 0.77 U	3.7	58	0.24 J	0.12 J	170000	9.7		4.2 J	26	12000
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated	6200	< 0.37 U	5.4	44	0.25 J	0.095 J	28000	11		6.1	29	21000
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated	7200	< 0.35 U	5	53	0.28 J	0.11 J	38000	12		6.7	34	18000
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated	7500	< 0.4 U	6.8	92	0.33 J	0.15 J	24000	21		6.5	51	23000
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated	4600	< 0.38 U	4.9	37	0.2 J	0.054 J	27000	6.6		4.3 J	31	12000
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated	6200	< 0.38 U	5.1	36	0.29 J	0.074 J	1300	8.6		5.1 J	21	16000
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated	6900	< 0.4 U	6.6	43	0.29 J	0.091 J	1100	8.8		6.5	18	17000
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated	5500	< 0.36 U	4.2	30	0.24 J	0.044 J	2300	8.3		4.8 J	15	14000
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated	5800	< 0.35 U	3.5	46	0.18 J	0.081 J	42000	15		4.8 J	28	13000
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated	6000	< 0.78 U	5.1	37	0.22 J	0.059 J	63000	9.3		5.5 J	20	14000
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated	11000	< 0.41 U	7.6	65	0.41 J	< 0.044 U	1500	20		9.2	72	23000
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated	4300	< 1.9 U	4.4	38	0.19 J	< 0.04 U	140000	6.8		4.2 J	16	11000
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated	6600	< 0.39 U	5.5	42	0.44 J	0.18 J	17000	17		5.3 J	570	14000
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	6600	< 0.75 U	6.5	42 J	0.24 J	0.57 J	57000	8.3		5.8	21	13000
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated	7500	0.67 J	13	53	0.35 J	0.092 J	5100	13		6.7	310	20000
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated	7300	2.5	16	68	0.43 J	0.18 J	2700	35		9.4	790	45000
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	6200	< 0.36 U	4.9	56	0.22 J	0.039 J	23000	8.9		5.3	19	15000
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated	7900	< 0.4 U	25	62	0.4 J	0.25 J	19000	12		9.5	26	22000
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated	5800	< 0.37 U	4.2	56	0.25 J	0.057 J	26000	8.9		5.2 J	24	15000
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	5600	< 0.37 U	4.7	39	0.21 J	0.058 J	37000	15		5.1 J	19	14000
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated	6100	< 0.36 U	4.4	40	0.21 J	0.098 J	6800	10		5.6	27	15000
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated	7100	< 0.38 U	5	61	0.26 J	0.15 J	20000	7.9		6.7	16	17000
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated	7300	< 0.37 U	5.5	79	0.27 J	< 0.039 U	80000	14		6.5	28	15000
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated	11000	< 0.45 U	10	120	0.52 J	< 0.048 U	3800	20		10	67	27000
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated	6100	< 0.37 U	6.9	35	0.28 J	< 0.04 U	890	9.8		5.2 J	25	15000
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated	7800	< 0.39 U	6	78	0.33 J	< 0.042 U	2300	9.9		6.7	20	16000
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated	3400	< 0.39 U	3	25	0.15 J	< 0.041 U	54000	4.8		3.2 J	52	8400
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated	6000	< 0.37 U	4.8	59	0.3 J	0.23 J	4600	16		5.5	28	17000
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated	6700	0.74 J	12	55	0.28 J	< 0.041 U	1400	24		8.3	36	37000
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated	7300	< 0.37 U	5.5	59	0.28 J	< 0.039 U	2000	14		6.5	21	16000
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated	8000	< 0.37 U	6.2	50	0.31 J	< 0.04 U	1300	17		6.9	30	19000
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated	4800	< 0.34 U	4.4	33	0.2 J	< 0.037 U	28000	8.6		4.9 J	18	13000
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	8500	0.79 J	5.1	110	0.36 J	< 0.041 U	1800	12		6.3	23	18000
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	4500	< 0.35 U	4.3	21	0.18 J	0.064 J	30000	6		4.3 J	15	12000
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	5200	< 0.36 U	4.5	24	0.21 J	< 0.039 U	31000	6.8		4.9 J	16	12000
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	6000	1.2	6.8	100	0.27 J	< 0.041 U	11000	11		5.9	25	15000
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated	8400	< 0.36 U	5.4	160	0.39 J	0.15 J	22000	12		6.8	32	17000
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated	7300	1.1	5.4	65	0.26 J	< 0.038 U	39000	12		6.4	25	15000
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated	8000	< 0.36 U	5.4	68	0.27 J	0.094 J	33000	12		6.3	29	18000
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated	6100	< 0.35 U	5.8	44	0.25 J	0.08 J	37000	10		5.3	21	15000
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated	6800	< 0.35 U	5.3	50	0.23 J	0.068 J	43000	9.4		5.5	21	16000
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated	8800	6.7	7.1	96	0.42 J	0.49 J	15000	12		7.3	95	23000
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated	8300	< 0.38 U	5.5	69	0.39 J	< 0.041 U	970	9.5		6.5	23	17000
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated	6700	< 0.39 U	4.2	58	0.27 J	0.072 J	950	9.4		5.7	34	17000

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	32 NE	4150	481 *E	0.0087	19.3 *E	682	1.7	< U	110		< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	32 NE	4150	481 *E	0.0087	19.3 *E	682	1.7	< U	110		< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	63.6 NE	5010	458 *E	0.14	44.4 *E	790	2.1	< U	207		< U
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	70.5 NE	4400	267 *E	0.082	84 *E	494	1.3	< U	132		< U
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	171 NE	3760	379 *E	0.042	453 *E	900	1.8	< U	1270		< U
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	171 NE	3760	379 *E	0.042	453 *E	900	1.8	< U	1270		< U
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated										< U	
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated										< U	
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated										< U	
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated										< U	
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	27	2800	530	0.18	20	920	< 0.65 U	< 0.13 U	33 J		< 0.26 U
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated	14	4100	270	0.019 J	21	500	0.54 J	< 0.067 U	72 J		< 0.21 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	50	4300	450	0.041	28	630	< 0.41 U	< 0.084 U	84 J		< 0.25 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated	76	4200	350	0.065	120	690	0.81 J	< 0.11 U	290 J		< 0.34 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	27	4800	330	0.045	17	510	0.66 J	< 0.088 U	150 J		< 0.27 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated	9.5										
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	18	4300	600	< 0.061 U	25	2100	< 5.1 U	< 1.0 U	65 J		< 3.1 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	17	4300	530	< 0.062 U	25	1900	< 5.3 U	< 1.1 U	65 J		< 3.2 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.38	855.38	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	13	9100	610	< 0.065 U	26	1300	< 5.6 U	< 1.1 U	92 J		< 3.3 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.80	854.80	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	11	8600	420	< 0.064 U	20	1000	< 5.6 U	< 1.1 U	77 J		< 3.4 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.40	855.40	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	8.5 T	19000 T	470	< 0.063 U	14	1200 T	< 5.1 U	< 1.0 U	110		< 3.1 UT
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated	7.7	2000	250	0.0084 J	13	690	< 0.6 U	< 0.12 U	48 J		< 0.24 U
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated	13	2000	560	< 0.0079 U	16	710	< 0.58 U	< 0.12 U	61 J		< 0.24 U
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated	390	2100	260	< 0.0086 U	16	640	< 0.59 U	< 0.12 U	97 J		< 0.24 U
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated	9.2	2200	680	< 0.009 U	14	600	< 0.58 U	< 0.12 U	43 J		< 0.23 U
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated	9.7	9600	310	< 0.0085 U	15	670	< 0.55 U	< 0.11 U	92 J		< 0.22 U
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated	73	5300	400	0.02 J	32	700	0.77 J	< 0.12 U	65 J		< 0.24 U
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated	120	3800	330	0.13	140		0.88 J	< 0.12 U	81 J		< 0.24 U
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated	23	5500	680	< 0.0082 U	28		< 0.59 U	< 0.12 U	73 J		< 0.24 U
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated	10	15000	430	0.021 J	15		< 0.54 U	< 0.11 U	120 J		< 0.22 U
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated	29	9700	450	0.1	17		0.97 J	< 0.12 U	160 J		< 0.47 U
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated	15	7100	410	0.019 J	17		< 0.55 U	< 0.11 U	130 J		< 0.23 U
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated	18	8700	530	0.044	19		< 0.53 U	< 0.11 U	130 J		< 0.22 U
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated	67	5100	540	0.017 J	32		0.69 J	< 0.12 U	130 J		< 0.25 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated	9.7	4600	360	0.013 J	12		< 0.58 U	< 0.12 U	56 J		< 0.24 U
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated	15	2000	360	0.013 J	14	610	0.62 J	< 0.12 U	55 J		< 0.23 U
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated	52	2200	440	0.0093 J	16	620	< 0.6 U	< 0.12 U	61 J		< 0.24 U
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated	180	2100	320	< 0.0085 U	12	540	< 0.55 U	< 0.11 U	48 J		< 0.22 U
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated	5.8	7600	420	< 0.0077 U	17	620	< 0.54 U	< 0.11 U	76 J		< 0.22 U
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated	6.8	13000	400	0.013 J	13	670	< 0.59 U	< 0.12 U	97 J		< 0.24 U
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated	21	2800	520	0.035 J	62		< 0.63 U	0.13 J	54 J		0.36 J
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated	4.7	6500	310	< 0.0078 U	11	630	< 0.57 U	< 0.12 U	97 J		< 0.23 U
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated	53	5600	260	0.027 J	550		< 0.59 U	< 0.12 U	73 J		< 0.24 U
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	7.8	4900	330	0.026 J	15	910 J	< 1.1 U	< 0.23 U	220 J		< 0.23 U
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated	69	2600	350	< 0.0079 U	170		< 0.57 U	< 0.12 U	63 J		< 0.23 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated	160	1800	500	0.088	980		1.3	0.29 J	61 J		0.3 J
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	5.8	4500	460	< 0.008 U	13	510 J	< 0.54 U	< 0.11 U	67 J		< 0.22 U
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated	12	4700	1500	0.018 J	21		< 0.6 U	< 0.12 U	60 J		< 0.24 U
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated	32	7400	360	0.019 J	12		< 0.56 U	< 0.11 U	89 J		< 0.23 U
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated	12	10000	370	< 0.0081 U	13		< 0.56 U	< 0.12 U	77 J		< 0.23 U
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated	18	3700	410	0.01 J	18		< 0.55 U	< 0.11 U	48 J		< 0.22 U
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated	6.3	8900	730	< 0.0079 U	16		< 0.57 U	< 0.12 U	66 J		< 0.23 U
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated	29	5600	790	0.089	24	760	< 0.56 U	< 0.11 U	110 J		< 0.23 U
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated	59	3200	620	0.092	43	990	< 0.68 U	< 0.14 U	52 J		0.46 J
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated	19	1800	400	0.014 J	14	690	< 0.56 U	< 0.12 U	44 J		0.25 J
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated	17	2200	470	0.044	15	780	< 0.59 U	< 0.12 U	88 J		< 0.24 U
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated	4.7	2200	230	< 0.0077 U	7.4		< 0.59 U	< 0.12 U	56 J		< 0.24 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated	69	2100	400	0.012 J	40		< 0.57 U	< 0.12 U	65 J		< 0.23 U
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated	17	1800	510	0.068	150	600	< 0.58 U	< 0.12 U	46 J		< 0.24 U
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated	20	2100	510	0.11	180	560	< 0.56 U	< 0.11 U	37 J		< 0.23 U
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated	10	2400	450	0.039	21		< 0.57 U	< 0.12 U	42 J		0.25 J
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated	8.8	11000	470	< 0.008 U	11		< 0.52 U	< 0.11 U	66 J		< 0.21 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	37	2300	520	0.017 J	19	840	< 0.58 U,^	< 0.12 U	290 J		0.27 J
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	5.4	3400	280	< 0.0077 U	11	430 J	< 0.53 U	< 0.11 U	54 J		< 0.22 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	5.9	4100	320	< 0.008 U	12	660	< 0.55 U,^	< 0.11 U	62 J		< 0.22 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	180	1900	530	0.026 J	17	910	< 0.59 U	< 0.12 U	63 J		< 0.24 U
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated	53	2700	720	0.022 J	25	650	< 0.55 U,^	< 0.11 U	320 J		0.39 J
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated	140	7100	440	0.012 J	16	860	< 0.54 U	< 0.11 U	81 J		< 0.22 U
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated	93	6100	410	0.01 J	18	710	< 0.54 U	< 0.11 U	63 J		< 0.22 U
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated	7.9	6900	300	< 0.008 U	14	710	< 0.53 U	< 0.11 U	72 J		< 0.22 U
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated	9	5100	360	< 0.0079 U	14	700	< 0.53 U	< 0.11 U	64 J		< 0.22 U
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated	280	2700	460	0.087	17		< 0.57 U	< 0.12 U	190 J		< 0.23 U
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated	9.7	2300	690	0.012 J	26		< 0.58 U	< 0.12 U	740		0.25 J
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated	7.9	2000	530	0.017 J	28		< 0.59 U	< 0.12 U	68 J		< 0.24 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated		13.3	68.5 NE
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated		13.3	68.5 NE
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		15	90.3 NE
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		9.4	103 NE
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		14.7	111 NE
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated		14.7	111 NE
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated			
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated			
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated		14	59
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated		8.2	51
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated		14	180
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated		13	95
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated		11	72
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated			
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		21	71
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.60	855.60	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		20	72
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.38	855.38	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated		19	80 B
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.80	854.80	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated		15	63 B
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.40	855.40	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated		12	63
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated		9.5	53
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated		13	65
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated		13	73
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated		12	69
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated		10	59
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated		14	96
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated		16	820
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated		12	87
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated		9.8	66
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated		10	82
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated		12	62
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated		12	65
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated		13	87
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated		7.9	49
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated		10	53
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated		10	60
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated		9.6	46
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated		7.9	79
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated		9.4	46
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated		19	100
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated		7	31
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated		8.4	720
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated		9.5 J	57
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated		12	180
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated		18	270
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated		8.8	44
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated		13	86
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated		9.6	69
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated		9.1	48
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated		8.9	110
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated		10	57
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated		13	66
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated		18	100
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated		11	57
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated		12	58
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated		6.3	30
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated		11	110
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated		32	140
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated		12	190
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated		14	62
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated		8.8	40
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated		14	68
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated		7.6	36
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated		8.6	40
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated		10	54
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated		12	120
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated		13	76
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated		12	78
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated		10	55
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated		10	52
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated		18	210
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated		13	56
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated		11	51

														Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated	5600	< 0.37 U	5.5	55	0.25 J	0.17 J	12000	8.8		7.6	110	15000
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated	5900	< 0.38 U	4.2	45	0.23 J	0.069 J	19000	8.3		5 J	27	14000
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated	9400	< 0.39 U	5	82	0.4 J	0.088 J	1700	11		6.4	24	17000
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated	8100	< 0.38 U	6.1	85	0.36 J	0.12 J	18000	11		6.3	40	21000
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated	8700	0.38 J	6.3	110	0.36 J	0.09 J	8500	12		7	24	21000
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated	7700	< 0.37 U	7.4	67	0.33 J	0.11 J	18000	10		7	31	19000
Football Field	SSHS-B2618	051819 10:00 PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated	3700	< 0.38 U	3	37 J	0.15 J	0.14 J	100000 J	31		2.8 J	220	8500
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated	5700	< 0.37 U	4	62 J	0.23 J	0.16 J	23000 J	32		3.8 J	280	12000
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated	5800	< 0.4 U	7.7	40	0.27 J	0.14 J	17000	8.5		6.1	22	17000
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated	6100	< 0.42 U	5.9	33	0.3 J	0.15 J	18000	8.9		6.8	23	15000
Football Field	SSHS-IRM3-PIPE11	080319 09:30 SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	5900	< 0.39 U	6.6	58	0.27 J	0.13 J	15000	8.3		5.8	27	15000
Football Field	SSHS-IRM3-S130	080319 09:30 SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated	7300	< 0.32 U	5.3	50	0.32 J	0.075 J	1100	9.5		6.4	26	17000
Football Field	SSHS-IRM3-S152	080319 09:30 SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated	6400	< 0.35 U	4.9	40	0.28 J	0.089 J	10000	8.1		5.7	24	15000
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	9800	0.77 J	7.6	130	0.44	0.075 J	9700	15 J+		8.1	100	23000
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated	9800	< 0.31 U	7.1	86	0.41	0.10 J	2800	11		7.0	36	21000
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated	8700	< 0.33 U	9.7	110	0.38	0.13 J	9600	11		8.6	24	25000
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated	7800	< 0.31 U	6.4	81	0.34 J	0.14 J	2700	9.5		7.0	27	19000
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated	7800	< 0.33 U	7.1	580	0.35 J	0.11 J	13000	12		6.5	32	19000
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated	8400	< 0.31 U	8.2	67	0.40	0.18 J	1700	10		7.1	29	20000
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated	8000	< 0.3 U	5.3	49	0.32 J	0.29 J	26000	15		7	31	18000
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	4900	< 0.29 U	4.2	49	0.2 J	0.11 J	37000	7.7		4.9	19	12000
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	5600	< 0.3 U	5.9	51	0.23 J	0.12 J	15000	7.8		5.8	19	14000
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated	7900	< 0.37 U	5.7	71	0.28 J	0.12 J	24000	10		6.9	34	18000
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated	6800	< 0.34 U	5.5	81	0.29 J	0.14 J	19000	10		6.0	40	18000
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated	9100	0.62 JT	6.3	89 T	0.35	0.070 J	2100 T	12 T		8.7	28 T	19000
Football Field	IRM4-S169	080120 09:45 SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated	6300	< 0.51 U	5.1	89	0.27 J	0.1 J	7100	11		4.8	26	15000
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated	7900	< 0.39 U	7.9	56	0.40 J	0.13 J	3200 B	10		7.0	27	19000
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated	4400	< 0.31 U	4.1	140	0.21 J	0.10 J	4900 B	5.9		3.4 J	33	10000
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated	5500	< 0.38 U	5.2	46	0.24 J	0.13 J	120000 B	7.2		4.5 J	18	12000
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated	7900	< 0.33 U	6.6	89	0.33 J	0.099 J	1700	9.6 B		7.1	24	19000
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated	6300	< 0.33 UT	5.4	76	0.27 JT	0.078 JT	2200 T	8.1 B		5.2	17 T	15000
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated	7000	< 0.30 U	5.7	42	0.29 J	0.069 J	2200	8.6		7.5	20	17000
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated	6600	< 0.35 U	4.6	52	0.25 J	0.25 J	12000	8.3		6.6	21	16000
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated	8000	< 0.34 U	5.8	70	0.32 J	0.31 J	14000	10		6.7	24	18000
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated	4900	< 0.35 U	5.0	30	0.21 J	0.066 J	3300	6.2		4.7	16	13000
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated	5600	< 0.30 U	9.8	41	0.27 J	0.22 J	3300	7.1		5.4	22	14000
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated	5500	< 0.36 U	6.9	40	0.26 J	0.18 J	3200	7.0		4.9	19	14000
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated	6800	< 0.29 U	5.3	76	0.25 J	0.17 J	21000	13		6.4	29	16000
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated	8700	0.73 J	9.6	100	0.38 J	0.094 J	1000	9.6		7.0	22	19000
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated	8800	0.71 J	5.6	75	0.35 J	0.12 J	3800	11		6.8	31	18000
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated	7700	0.47 J	6.0	75	0.34 J	0.079 J	890	9.8		6.6	22	17000
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated	8900	0.51 J	7.7	58	0.35 J	0.11 J	1400	11		7.8	21	21000
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated	6300	0.37 JT	6.1	38	0.25 J	0.058 J	760	7.7		5.5	16	15000
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated	4200	< 0.37 U	3.0	31	0.18 J	0.10 J	3700	5.7		4.4 J	15	8900
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated	9300	0.67 J	8.3	140	0.41 J	1.7	9800	37		8.0	1300	23000
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated	4100	< 0.33 U	3.3	19	0.18 J	0.048 J	1100	7.9		2.8 J	140	9800
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated	4600	< 0.30 U	4.6	43	0.22 J	0.19 J	8500	14		4.0 J	470	12000
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated	4000	< 0.28 U	3.5	35	0.17 J	0.12 J	33000	16		3.4 J	33	9800
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated	10000	0.51 J	9.9	75	0.50	0.066 J	4900	13		10	17	25000
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated	7000	0.44 J	5.9	46	0.31 J	0.11 J	3600	8.8		6.2	24	16000
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated	6000	< 0.40 U	5.2	32	0.25 J	0.086 J	1700	7.7		5.3 J	17	15000
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated	8400	0.47 J	6.4	54	0.37	0.13 J	2600	10		7.5	32	19000
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated	4400	< 0.28 U	3.8	35	0.16 J	0.16 J	46000	26		3.7 J	380	11000 B
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated	7000	0.80 J	7.2	180	0.32 J	0.55	18000	13		6.6	43	25000
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated	7700	< 0.36 U	6.3	64	0.32 J	0.19 J	21000	10		6.1	39	16000
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated	3900	< 0.29 U	2.8	29	0.16 J	0.29 J	19000	28		4.0 J	130	11000
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated	2600	0.42 J	4.2	23	0.12 J	0.12 J	13000	6.9		2.7 J	320	5900
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated	3800	< 0.26 UT	3.3	33	0.15 J	0.080 J	35000 T	9.8		3.6 J	45 T	8400
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated	5700	< 0.32 UT	5.0	53	0.25 J	0.11 J	43000 T	6.9		6.1	19	13000
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated	6200	< 0.29 U	4.6	52	0.26 J	0.096 J	22000	7.7		5.6	20	15000
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated	4500	< 0.30 U	3.8	37	0.13 J	0.060 J	35000	5.7		4.4	16	12000
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated	8400	< 0.38 U	5.4	41	0.33 J	0.053 J	630	8.9		6.8	17	17000
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated	7700	< 0.35 U	6.0	55	0.30 J	0.060 J	770	9.1		7.1	20	17000
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated	8500	< 0.38 U	6.1	74	0.34 J	0.081 J	1000	10		7.6	22	19000
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated	5200	< 0.38 U	4.4	39	0.25 J	0.39 J	1500	6.8		4.6	22	12000
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated	8100	0.41 J	7.1	130	0.31 J	0.17 J	20000	15		7.5	36	20000
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated	4600	< 0.35 U	5.0	31	0.14 J	0.049 J	36000	6.1		4.5	15	11000
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated	7500 T	< 0.35 U	5.7	130	0.30 J	0.084 J	900	10		6.2	35	15000 B
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated	8200 T	< 0.40 U	5.3	51	0.29 J	0.071 J	540 J	10		5.2	14	16000 B
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated	5200	0.66 J	6.3	37	0.21 J	0.078 J	840	19		3.6	100	16000
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated	4600	< 0.35 U	3.5	30	0.16 J	0.049 J	26000	6.0		4.3	13	11000
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated	6400	3.0 T	8.4	54 T	0.40 J	0.30 J	3900	38		7.8	340 T	17000
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated	6900	< 0.37 U	6.7	57	0.25 J	0.070 J	980	13		5.9	65	17000 B
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated	6300	< 0.36 U	5.0	41	0.24 J	0.095 J	15000	11		6.2	31	15000

DRAFT

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated	12	3700	850	< 0.0084 U	550		< 0.56 U	< 0.12 U	43 J		< 0.23 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated	8.5	6000	470	< 0.0077 U	53		< 0.58 U	< 0.12 U	65 J		< 0.24 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated	28	2300	240	0.028 J	19	610	< 0.59 U	< 0.12 U	60 J		< 0.24 U
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated	37	6800	520	0.015 J	20	670	0.67 J	< 0.12 U	97 J		< 0.36 U
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated	53	3900	510	< 0.016 U	18	690	< 0.57 U	< 0.12 U	120 J		< 0.35 U
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated	10	3800	470	< 0.017 U	18	760	< 0.56 U	< 0.12 U	73 J		< 0.35 U
Football Field	SSHS-B2618	051819 10:00 PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated	26 J	9000 J	230	0.012 J	15	470 J	1.6 J	< 0.12 U	98 J		< 0.36 U
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated	44 J	5100 J	230	0.015 J	22	510 J	< 0.57 UJ	< 0.12 U	150 J		< 0.35 U
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated	8.3	4800	260	< 0.015 U	16		0.9 J	< 0.12 U	62 J		< 0.38 U
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated	8.9	5500	330	< 0.014 U	17		< 0.63 UJ	< 0.13 U	65 J		< 0.39 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30 SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	22	4300	380	< 0.014 U	15	700	< 0.6 U	< 0.12 U	95 J		< 0.37 U
Football Field	SSHS-IRM3-S130	080319 09:30 SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated	31	2100	350	< 0.015 U	28		< 0.49 U	< 0.1 U	140 J		< 0.31 U
Football Field	SSHS-IRM3-S152	080319 09:30 SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated	11	3100	350	< 0.016 U	16		< 0.53 U	< 0.11 U	110 J		< 0.33 U
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	76	4900	550 J+	0.024 J	39	840	< 0.51 U	< 0.1 U	110 J		< 0.32 U
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated	35	2600	650	0.041 T	20	680	< 0.47 U	< 0.095 U	65 J		< 0.29 U
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated	290	2400	580	< 0.025 U	22	790	< 0.49 U	< 0.10 U	190 J		< 0.31 U
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated	8.1	3200	870	< 0.020 U	19	730	< 0.46 U	< 0.095 U	54 J		< 0.29 U
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated	31	4100	480	0.075	25	870	< 0.51 U	< 0.10 U	97 J		< 0.31 U
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated	12	2500	830	< 0.023 U	20	730	< 0.48 U	< 0.097 U	< 56 U		< 0.30 U
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated	14	6400	380	0.028 J	22	900	< 0.46 U	< 0.094 U	100 J		< 0.29 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	12	9200	360	0.022 J	14	640	0.67 J	< 0.09 U	100 J		< 0.27 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	9.2	6300	580	< 0.023 U	15	630	0.52 J	< 0.092 U	330 J		< 0.28 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated	19	5700	380	0.032 J	23	670	0.60 J	< 0.11 U	110 J		< 0.35 U
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated	30	5200	390	0.024 J	30	590	< 0.51 U	< 0.10 U	72 J		< 0.32 U
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated	29 T	2700	370	< 0.024 U	21	690 T	< 0.37 U	< 0.075 U	120 J		< 0.23 U
Football Field	IRM4-S169	080120 09:45 SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated	350	2400	320	0.041	29	510	< 0.39 U	< 0.08 U	120 J		< 0.24 U
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated	15	2900	800	< 0.024 U	19	970	< 0.59 U	< 0.12 U	< 69 U		< 0.37 U
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated	150	1400	240	0.041	12	440 J	< 0.47 U	< 0.097 U	140 J		< 0.29 U
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated	12	3600	300	< 0.023 U	13	600	1.5	< 0.12 U	190 J		< 0.35 U
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated	44	2500	530	0.031	20	610	< 0.51 U	< 0.10 U	< 59 U		< 0.32 U
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated	12	2100	330 T	< 0.021 U	14	520	< 0.49 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated	18	2300	480	0.027 J	19	560	< 0.39 U	< 0.068 U	< 53 U		2.9
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated	18	3400	480	0.020 J	18	580	< 0.45 U	< 0.079 U	62 J		2.9
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated	31	4300	400	0.036 J	22	610	< 0.45 U	< 0.077 U	90 J		2.5
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated	13	2000	380	0.017 J	12	510	< 0.45 U	< 0.078 U	61 J		2.3
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated	9.4	2800	350	0.028 J	14	550	< 0.39 U	< 0.068 U	< 52 U		2.0
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated	10	2400	350	0.022 J	13	590	< 0.47 U	< 0.080 U	< 62 U		2.2
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated	33	4200	410	< 0.019 U	33	580	< 0.38 U	< 0.066 U	66 J		< 0.33 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated	12	2100	550	< 0.021 U	18	880	< 0.55 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated	36	2900	440	< 0.023 U	26	800	< 0.53 U	< 0.11 U	110 J		< 0.33 U
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated	10	2400	510	< 0.019 U	16	940	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated	11	2600	420	< 0.017 U	20	830	< 0.50 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated	7.7	1900	290	< 0.023 U	14	520	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated	9.8	2700	500	< 0.020 U	11	610	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated	210	3800	480	0.050	69	820	0.64 J	< 0.12 U	79 J		< 0.37 U
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated	4.6	1400	240	< 0.021 U	8.5	450 J	< 0.50 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated	14	3500	330	< 0.017 U	180	520	< 0.46 U	< 0.093 U	< 53 U		< 0.28 U
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated	9.9	3200	310	< 0.021 U	12	490	< 0.42 U	< 0.086 U	57 J		< 0.26 U
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated	12	3400	440	< 0.022 U	24	1200	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated	9.6	2400	420	< 0.021 U	16	720	< 0.49 U	< 0.10 U	58 J		< 0.30 U
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated	7.5	2000	310	< 0.023 U	13	670	< 0.60 U	< 0.12 U	< 70 U		< 0.37 U
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated	11	3000	550	< 0.019 U	20	790	< 0.45 U	< 0.093 U	54 J		< 0.28 U
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated	9.3	6300	330	0.024 J	110	410 J	0.86	< 0.087 U	55 J		< 0.27 U
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated	230	3900	490	< 0.018 U	25	790	< 0.52 U	< 0.11 U	97 J		< 0.32 U
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated	39	4400	440	< 0.020 U	28	870	< 0.55 U	< 0.11 U	110 J		< 0.34 U
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated	21	7400	200	< 0.017 U	350	520	< 0.45 U	< 0.091 U	57 J		< 0.28 U
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated	30	3400	71	< 0.023 U	460	440	< 0.44 U	< 0.090 U	86 J		< 0.27 U
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated	8.0	3700 T	260 T	< 0.019 U	43 T	530	0.54 J	< 0.082 U	60 J		< 0.25 U
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated	7.3	3600 T	440	0.024 J	13	720	< 0.49 U	< 0.10 U	84 J		< 0.31 U
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated	7.2	4000	400	0.023 J	14	670	0.53 J	< 0.090 U	60 J		< 0.27 U
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated	5.4	3100	300	< 0.019 U	12	460	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated	8.0	2600	500	< 0.022 U	17	620	< 0.49 U	< 0.085 U	94 J		< 0.42 U
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated	10	2200	390	0.024 J	17	640	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated	8.6	2400	490	0.023 J	20	660	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated	7.3	1700	760	< 0.021 U	14	480 J	< 0.50 U	< 0.086 U	70 J		< 0.42 U
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated	280	3000	540	0.031 J	59	780	< 0.50 U	< 0.086 U	140 J		< 0.42 U
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated	9.6	3000	280	< 0.020 U	13	470 J	< 0.45 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated	11	2100	560 B	0.035 J	20	580	< 0.46 U	< 0.080 U	200 J		< 0.39 U
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated	9.4	2300	280 B	< 0.023 U	16	630	< 0.52 U	< 0.090 U	940		< 0.45 U
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated	32	1500	130	0.024 J	330	630	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated	5.5	2700	260	< 0.021 U	13	440 J	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated	75	2500	360	0.055 J	1100 T	640	< 0.47 U	< 0.081 U	74 J		< 0.40 U
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated	17	1800	490	0.019 J	47	610	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated	17	4300	270	< 0.019 U	19	650	< 0.47 U	< 0.082 U	< 64 U		< 0.40 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated		8.7	230
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated		8.9	120
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated		14	62
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated		12	75
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated		13	54
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated		14	70
Football Field	SSHS-B2618	051819 10:00 PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated		6	84
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated		7.2	130
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated		11	63
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated		12	69
Football Field	SSHS-IRM3-PIPE11	080319 09:30 SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated		9.7	64
Football Field	SSHS-IRM3-S130	080319 09:30 SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated		11	53
Football Field	SSHS-IRM3-S152	080319 09:30 SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated		9.9	55
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated		17	86
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated		15	64
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated		15	170
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated		12	70
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated		13	78
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated		14	140
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated		11	69
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated		8.1	52
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated		9.3	55
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated		11	69
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated		11	73
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated		13 T	56 T
Football Field	IRM4-S169	080120 09:45 SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated		11	56
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated		14	59
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated		7.5	41
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated		8.6	69
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated		12	71
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated		11	53 T
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated		11	76 B
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated		10	120 B
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated		13	220 B
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated		8.6	64 B
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated		10 B	60
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated		10 B	56
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated		10	75
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated		15	63
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated		14	76
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated		13	72
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated		13	58
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated		9.5	43 T
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated		7.5	39
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated		15	730
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated		6.8	53
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated		8.1	380
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated		7.0	53
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated		15	54
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated		12	57
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated		11	55
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated		13	79
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated		6.9	260
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated		12	210
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated		12	100
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated		7.2	640
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated		5.5	600
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated		7.2	57 T
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated		9.3	42
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated		11	68
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated		6.5	66
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated		12	56
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated		11	72
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated		12	74
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated		7.6	79
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated		12 B	110
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated		7.9 B	38
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated		13	61 B
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated		13	89 B
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated		11	73
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated		8.0	45
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated		15	240 T
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated		11	280
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated		9.9	73

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated	5000	< 0.38 UT	3.5	57	0.16 J	0.071 J	39000 T	7.5		4.4	16	11000
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated	8200	< 0.37 U	7.0	39	0.35 J	0.11 J	550	11 B		7.6	29	18000
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated	11000	3.5	30	96	0.56 J	0.35 J	2200	94 B		8.4	430	28000
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated	4700	< 0.38 U	11	53	0.27 J	0.086 J	660	6.2		3.2	18	14000
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated	4000	0.54 J	4.1	30	0.18 J	0.098 J	28000	7.6		4.1	15	11000
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated	3900	0.37 J	3.2	32	0.16 J	0.070 J	29000	14		4.0	13	9400
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	5500	< 0.28 U	7.4	33	0.29 J	< 0.030 U	960	9.1		6.1	19	15000
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	5300	< 0.31 U	5.5	32	0.25 J	< 0.033 U	2700	6.8		4.7	16	13000
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	7800	1.0	13	81	0.46	0.076 J	7600	33		8.4	72	23000
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	11000	0.46 J	12	90	0.52	0.056 J	6900	16		11	33	26000 B
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	8500	0.74 J	5.1	69	0.36 J	0.14 J	4700	12		6.6	470	19000
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	10000	1.2	8.9	62	0.45	0.061 J	1700	13		9.2	42	22000
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	7900	2.9	9.5	87	0.37 J	0.11 J	8700	12		7.7	180	20000
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	10000	1.1	7.4	110	0.46	0.15 J	3800	18		7.7	75	24000
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	6600	1.2	6.9	90	0.32 J	< 0.033 U	22000	12		6.2	41	21000
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated	7900	1.1	7.9	89	0.35 J	0.059 J	33000	15		6.8	58	19000
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	9400	0.12 J	7.4	68	0.41	0.061 BJ	650 B	11 B		7.5	21	20000 B
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	9800	0.52 J	9.3	44	0.39 J	< 0.039 U	910	12		8.3	19	21000
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	8500	< 0.33 U	7.7	59	0.32 J	< 0.035 U	520	10		7.4	22	18000
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	8000	0.79	11	63	0.38	0.089 B	2300 B	24 B		6.9	350	20000 B
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	11000	0.51 J	5.5	86	0.49	< 0.042 U	770	15		6.0	16	20000
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated	5300	1.5 J	9.7	47	0.25 J	0.21 J	26000	14		8.6	59	37000
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated	6800	< 0.30 U	5.3	42	0.27 J	< 0.032 U	1100	9.0		5.1	26	16000
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated	6500	0.42 J	6.3	43	0.26 J	< 0.036 U	1900	8.2		5.0	20	15000
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated	4900	< 0.28 U	7.1	49	0.25 J	0.069 J	770	6.4		4.7	20	12000
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated	3800	< 0.36 U	7.6	54	0.17 J	0.14 J	11000	5.6		4.2	27	13000
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated	6300	0.43 J	5.8	50	0.27 J	0.059 J	2500	8.6		5.0 J	23	14000
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated	5500	0.95 J	6.0	97	0.29 J	0.070 J	18000	8.3		4.6 J	68	15000
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated	7000	0.47 J	6.6	72	0.28 J	0.042 J	1700	9.2		5.7	25	16000
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated	9000	0.40 J	10	59	0.34	< 0.029 U	3400	10		8.1	23	20000
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated	7700	< 0.34 UT	5.8	54	0.30 J	0.037 J	1200 T	8.9		5.5	24	18000
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated	4900	< 0.33 UT	5.0	37	0.22 J	0.071 J	38000	6.6		4.3 J	30	12000
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated	6100	< 0.32 U	4.2	47	0.31 J	0.13 J	38000	6.9		4.9	25	12000
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	10000	< 0.36 U	9.9	77	0.45	< 0.039 U	2800	13		10	34	24000
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated	3700	< 0.22 U	3.2	21	0.14 J	0.057 J	33000	5.1		3.6	16	8500
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated	4100	< 0.25 U	3.6	22	0.15 J	0.076 J	44000	5.2		4.1	15	10000
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated	5200	< 0.27 U	4.9	30	0.19 J	0.086 J	47000	7.5		5.0	26	12000
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated	4500	< 0.22 U	4.4	22	0.16 J	0.073 J	32000	5.9		4.2	17	11000
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated	4300	< 0.31 UT	2.9	28	0.15 J	0.11 J	29000	5.7		4.3 J	17	9700
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated	3800	< 0.22 U	3.1	39	0.14 J	0.10 J	52000	4.5		3.7	19	8100
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	6800	< 0.034 U	4.4	40	0.24 J	0.094 J	37000	10		5.8	21	15000
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated	4600	< 0.33 U	3.8	36	0.19 J	0.12 J	55000	6.2		4.0	20	9900
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated	6100	3.5	5.9	46	0.25 J	0.10 J	33000	8.2		5.5	26	15000
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	6700	< 0.38 U	5.2	79	0.28 J	0.1 J	1900	12		6.1	26	18000
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	7000	< 0.37 U	5.4	100	0.31 J	0.21 J	3900	12		6.6	34	19000
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	4700	< 0.38 U	5	28	0.21 J	0.095 J	1400	7.5		4.5 J	16	12000
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	4800	< 0.37 U	3.1	35	0.18 J	0.063 J	3300	6.2		4 J	13	11000
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	6100	< 0.37 U	5.8	42	0.3 J	0.08 J	1900	7.8		5.5	20	16000
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	7300	< 0.38 U	5.1	45	0.31 J	0.058 J	7100	12		5.9	21	17000
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	6500	< 0.38 U	4.8	55	0.28 J	0.09 J	18000	11		6.3	40	20000
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	5000	< 0.38 U	4.3	210	0.22 J	0.065 J	78000	14		4.6 J	28	15000
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	6800	< 0.38 U	5.8	48	0.27 J	0.9	62000	15		5.8	88	15000
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	6300	< 0.39 U	6.3	76	0.23 J	0.074 J	34000	9		5.8	21	16000
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	8200	< 0.72 U	3.5	56	0.29 J	0.07 J	90000	11		5.1 J	22	14000
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	8200	< 0.37 U	7	75	0.3 J	0.14 J	20000	15		7.8	40	29000
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	6000	< 0.38 U	7.6	54	0.29 J	0.11 J	10000	9.6		6	21	16000
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	5200	< 0.38 U	3.5	30	0.21 J	0.062 J	19000	6.9		4.7 J	18	13000
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	6100	< 0.39 U	5.3	48	0.25 J	0.09 J	9600	8.5		6.1	29	17000
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	4400	< 0.37 U	3.4	27	0.17 J	0.1 J	40000	92		3.3 J	270	11000
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	6700	< 0.39 U	7	95	0.31 J	0.11 J	3200	10		6.2	40	18000
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	5400	< 0.39 U	3.4	40	0.21 J	0.057 J	14000	7.4		5.2 J	17	14000
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	3700	< 0.36 U	4.8	32	0.14 J	0.067 J	33000	16		3.4 J	19	10000
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	4800	< 0.35 U	3.1	35	0.15 J	0.074 J	37000	17		3.8 J	20	11000
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	5100	< 0.36 U	4.6	39	0.22 J	0.063 J	33000	8.4		4.6 J	19	13000
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	6200	< 0.39 U	5.7	35	0.25 J	0.059 J	750	14		4.7 J	210	16000
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	9600	< 0.41 U	7.5	74	0.35 J	< 0.044 U	1500	18		8.2	130	25000
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	9900	< 0.41 U	8.6	88	0.45 J	0.085 J	8000	13		8.4	25	22000
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	6900	< 0.4 U	5.7	56	0.33 J	0.15 J	13000	16		7.1	670	17000
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	6500	< 0.37 U	4.3	45	0.23 J	0.096 J	30000	8.5		6.2	20	14000
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	5300	< 0.38 U	5.3	40	0.22 J	0.065 J	1600	8.8		4.6 J	170	14000
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	8900	< 0.38 U	7	60	0.41 J	0.61	23000	11		8.8	68	20000
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	5400	< 0.36 U	5	46	0.19 J	0.061 J	28000	7.1		4.7 J	20	13000
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	7700	< 0.38 U	5.8	98	0.29 J	0.079 J	53000	12		6.6	24	17000
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	7000	2.6	4.8	58	0.29 J	0.083 J	11000	15		6.4	37	17000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated	6.7	5900 T	210	< 0.020 U	12	580	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated	14	2200	430	0.036 J	37	650	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated	170	2200	330	0.29	450	1400	3.7	0.62 J	100 J		< 0.56 U
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated	8.5	1300	230	< 0.020 U	9.3	700	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated	8.4	3400	250	< 0.021 U	11	350 J	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated	5.6	2900	250	< 0.018 U	10	310 J	< 0.35 U	< 0.071 U	45 J		0.24 J
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	9.5	1700	510	< 0.019 U	15	490	< 0.42 U	< 0.086 U	< 49 U		0.30 BJ
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	7.0	1600	310	< 0.020 U	13	500	< 0.47 U	< 0.097 U	< 56 U		< 0.30 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	180	3200	400	0.091	110	760	< 0.50 U	< 0.10 U	66 J		0.45 BJ
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	36	3600	520	< 0.021 U	35	1100	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	58	2200	420	0.14	19	550	< 0.52 U	< 0.11 U	< 61 U		0.46 J
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	29	3000	400	0.062	22	980	< 0.58 U	< 0.12 U	< 67 U		0.45 J
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	55	5200	600	0.099	140	1200	< 0.53 U	< 0.11 U	65 J		< 0.33 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	85	2400	530	0.088	32	790	< 0.58 U	< 0.12 U	< 69 U		0.41 J
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	100	4100	260	0.10	25	730	< 0.47 U	< 0.095 U	180 J		< 0.29 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated	46	6200	490	0.084	41	910	< 0.52 U	< 0.11 U	180 J		< 0.32 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	10	2500	360	< 0.020 U	17	1300	< 0.13 U	< 0.028 U	48 J		0.080 J
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	10	2800	360	0.030	20	800	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	11	2300	380	0.020 J	16	1100	< 0.50 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	41	2200	330	0.062	200	630	0.22 J	0.052 J	41		0.17
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	12	3100	210	< 0.020 U	21	2100	< 0.59 U	< 0.12 U	70 J		< 0.37 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated	45	3000	380	0.068 J	22	430 J	0.54 J	1.1	73 J		< 0.39 U
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated	7.0	2000	390	0.020 J	13	600	< 0.45 U	< 0.093 U	< 53 U		< 0.28 U
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated	7.7	2000	310	< 0.020 U	13	640	< 0.50 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated	10	1300	420	0.039 J	12	500	< 0.37 U	< 0.064 U	< 50 U		< 0.32 U
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated	43	2200	570	0.020 J	10	400 J	< 0.47 U	< 0.081 U	63 J		< 0.40 U
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated	18	1900	480	0.043	13	490 J	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated	39	1700	370	0.034 J	13	550	< 0.52 U	< 0.11 U	170 J		< 0.33 U
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated	28	2200	440	0.080	15	470 J	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated	36	2900	400	< 0.023 U	19	780	< 0.42 U	< 0.085 U	< 49 U		< 0.26 U
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated	19 T	2100	200 T	0.023 J	17	490 J	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated	57	8100 T	290	< 0.021 U	36 T	530	0.51 J	< 0.10 U	68 J		< 0.31 U
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated	21	6400	410	< 0.023 U	16	600	< 0.49 U	< 0.10 U	64 J		< 0.30 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	16	3200	750	< 0.031 U	44	800	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated	3.9	3100	270	< 0.018 U	9.8	290 J	< 0.34 U	< 0.069 U	< 40 UT		< 0.21 U
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated	4.7	2800	420	< 0.021 U	11	320 J	0.40 J	< 0.078 U	< 45 UT		< 0.24 U
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated	6.3	8200	320	< 0.021 U	15	470	0.44 J	< 0.084 U	< 48 UT		< 0.26 U
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated	4.7	3100	420	< 0.021 U	11	320	< 0.33 U	< 0.068 U	< 39 UT		< 0.21 U
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated	6.3	3900 T	280 T	< 0.019 U	12	290 J	0.49 J	< 0.095 U	< 55 UT		< 0.29 U
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated	5.8	2900	330	< 0.015 U	9.7	330	0.57 J	< 0.069 U	< 40 UT		< 0.21 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	8.5	9300	450	< 0.034 U	15	750	< 0.034 U	< 0.034 U	91 J		< 0.034 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated	6.8	4200	360	< 0.022 U	16	520	< 0.44 U	< 0.075 U	100 J		< 0.37 U
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated	11	4400	320	< 0.021 U	15	750	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	35	2500	300	< 0.0082 U	17	630	0.73 J	< 0.12 U	67 J		< 0.23 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	35	2700	1300	0.012 J	21	640	< 0.56 U	< 0.12 U	74 J		< 0.23 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	25	1800	170	< 0.0086 U	11	440 J	< 0.57 U	< 0.12 U	55 J		< 0.23 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	14	1900	410	< 0.0081 U	10	450 J	< 0.56 U	< 0.11 U	47 J		< 0.23 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	10	1800	530	0.014 J	14	640	< 0.56 U	< 0.11 U	37 J		< 0.23 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	10	3400	380	0.0086 J	19	630	0.6 J	< 0.12 U	56 J		< 0.23 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	31	3900	480	0.014 J	22	630	< 0.57 U	< 0.12 U	54 J		< 0.23 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	59	3300	380	0.034 J	32	510 J	< 0.58 U	< 0.12 U	63 J		< 0.24 U
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	51	6700	330	0.13	150		< 0.58 U	< 0.12 U	91 J		< 0.24 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	8.7	11000	450	< 0.0078 U	14		< 0.59 U	< 0.12 U	100 J		< 0.24 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	9.7	10000	330	< 0.0078 U	16		0.75 J	< 0.11 U	230 J		< 0.22 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	30	4800	550	0.021 J	26		< 0.55 U	< 0.11 U	150 J		< 0.23 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	16	3100	470	< 0.0079 U	16		< 0.58 U	< 0.12 U	81 J		< 0.24 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	8.1	4300	380	< 0.0081 U	12		< 0.58 U	< 0.12 U	63 J		< 0.24 U
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	9	6100	470	0.017 J	16		< 0.59 U	< 0.12 U	50 J		< 0.24 U
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	11	12000	570	< 0.0074 U	15	500 J	< 0.56 U	< 0.11 U	99 J		< 0.23 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	36	2500	310	0.042	17	620	< 0.6 U	< 0.12 U	79 J		< 0.24 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	110	2200	340	< 0.008 U	13	540 J	< 0.59 U	< 0.12 U	56 J		< 0.24 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	6.1	3800	250	< 0.0077 U	13	460 J	< 0.54 U	< 0.11 U	75 J		< 0.22 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	5.9	4500	530	< 0.0077 U	15	480 J	< 0.53 U	< 0.11 U	87 J		< 0.21 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	8.9	14000	490	0.012 J	12	630	< 0.54 U	< 0.11 U	82 J		< 0.22 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	52	1800	270	0.03 J	100		< 0.59 U	< 0.12 U	64 J		< 0.24 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	27	2600	330	0.034 J	97		< 0.62 U	< 0.13 U	61 J		0.32 J
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	12	4900	520	0.022 J	21	920	< 0.61 U	< 0.13 U	37 J		< 0.25 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	35	5100	380	0.042	660		< 0.6 U	< 0.12 U	70 J		< 0.24 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	11	4800	470	0.012 J	15	590	< 0.56 U	< 0.11 U	61 J		< 0.23 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	33	1800	430	0.023 J	110		< 0.58 U	< 0.12 U	56 J		< 0.23 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	11	6100	600	< 0.0083 U	970		< 0.58 U	< 0.12 U	97 J		< 0.23 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	11	7400	510	0.0082 J	12	550	< 0.55 U	< 0.11 U	73 J		< 0.22 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	12	8600	540	0.036 J	17		0.92 J	< 0.12 U	82 J		< 0.23 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	62	6500	340	0.04	16		< 0.6 U	< 0.12 U	78 J		< 0.24 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated		7.5	120
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated		12	120
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated		24	1700
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated		8.2	61
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated		7.1	35
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated		6.2	29
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated		10	41
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated		9.3	40
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated		14	110
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated		17	86
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated		15	97
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated		17	78
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated		15	180
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated		20	110
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated		17	77
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated		15	180
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated		15	58
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated		15	45
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated		13	53
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated		14	330
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated		16	64
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated		16	93
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated		11	54
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated		12	61
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated		8.7	63
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated		8.2	73
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated		11	58
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated		11	100
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated		11	65
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated		14	68
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated		13	58 T
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated		8.4	60 T
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated		9.0	75
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated		15	74
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated		5.9	41
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated		7.1	43
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated		9.5	61
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated		6.9	70
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated		6.4	75 T
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated		5.7	48
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated		11	60
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated		6.8	91
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated		9.3	66
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated		12	73
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated		13	92
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated		8.5	48
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated		8	39
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated		11	58
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated		12	53
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated		12	74
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated		8.9	61
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated		11	460
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated		9.2	63
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated		9.5	55
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated		14	94
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated		9.4	68
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated		7.8	50
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated		9.9	58
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated		7.1	56
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated		11	60
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated		8.7	44
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated		5.7	68
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated		6.3	72
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated		8.3	47
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated		9.9	480
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated		18	140
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated		15	62
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated		10	590
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated		9.5	57
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated		8.4	130
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated		13	290
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated		8.7	47
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated		12	60
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated		10	80

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	4900	< 0.36 U	5.1	34	0.18 J	0.042 J	40000	8.3		4.7 J	17	12000
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	6200	< 0.36 U	4.3	50	0.21 J	0.059 J	32000	8.5		4.9 J	23	15000
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	6100	< 0.38 U	5.1	58	0.26 J	< 0.041 U	3800	7.8		5.6 J	27	15000
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	10000	2.7	9.7	140	0.43 J	< 0.04 U	19000	36		11	540	52000
Football Field	SSHS-B2027	072718 09:00_SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	5300	< 0.39 U	3.5	72	0.17 J	< 0.042 U	21000	7.5		4.6 J	16	11000
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	5300	< 0.36 U	4.1	32	0.22 J	0.092 J	13000	8.7		4.1 J	19	12000
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	13000	< 0.42 U	7.8	110	0.6	< 0.045 U	2400	15		11	17	22000
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	6500	< 0.39 U	5.4	48	0.3 J	< 0.041 U	9300	9.2		6.4	69	18000
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	6200	< 0.39 U	5.3	40	0.27 J	0.11 J	1900	9.5		5.8	23	15000
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	12000	< 0.43 U	7.3	130	0.56	< 0.046 U	2000	15		10	16	21000
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	4900	< 0.36 U	4.9	62	0.19 J	< 0.038 U	9300	13		4.5 J	17	13000
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	6400	< 0.39 U	5.1	54	0.24 J	< 0.042 U	17000	9.8		6.4	25	16000
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	6800	< 0.37 U	4.9	37	0.28 J	< 0.04 U	1200	8.8		5.6	28	15000
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	6300	< 0.46 U	8.1	33	0.3 J	< 0.05 U	1400	8.8		6.5 J	22	17000
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	5400	< 0.36 U	5.2	40	0.21 J	0.064 J	59000	8.8		4.8 J	22	13000
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	4500	< 0.7 U	2.9	36	0.18 J	0.037 J	100000	6.5		3.8 J	17	10000
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	7400	< 0.39 U	4.6	47	0.28 J	0.11 J	1100	9.8		5.9	28	18000
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	7200	< 0.37 U	5.2	59	0.31 J	0.081 J	2200	9.7		5.8	54	16000
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	7400	< 0.39 U	4.2	28	0.26 J	0.08 J	10000	30		6.2	200	19000
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	5200	0.38 J	6.6	41	0.21 J	0.073 J	5600	10		4.8 J	74	14000
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	6600	< 0.39 U	5.7	73	0.3 J	0.12 J	12000	9.1		5.5 J	22	16000
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated	7200	< 0.39 U	5.2	67	0.3 J	0.11 J	46000	9		6.2	22	17000
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated	6600	< 0.38 U	4.6	46	0.27 J	0.098 J	20000	8.7		5.7	21	16000
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated	7000	< 0.38 U	5.3	65	0.28 J	0.13 J	56000	10		6.2	25	18000
Football Field	SSHS-B2724	042519 08:35_SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated												
Football Field	SSHS-IRM3-B012	072019 09:15_SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated	5700	< 0.34 UJ	5	34	0.24 J	0.098 J	8800 J	7.4		5.2	20	14000
Football Field	SSHS-IRM3-B009	080319 09:30_SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated	6600	0.37 J	6.1	49	0.35 J	0.087 J	2600	8.4		6.9	22	17000
Football Field	SSHS-IRM3-S158	080319 09:30_SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated	7100	1.4	10	200	0.55	0.41 J	28000	17		8	48	39000
Football Field	SSHS-IRM3-B014	080619 09:00_SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated	6200	0.39 J	4.7	48	0.25 J	1.3	1400	7.9		5.9	21	15000
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated	7300	0.39 J	7.1	54	0.33 J	0.11 J	14000	9.5		6.5	23	18000
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated	6800	< 0.35 UJ	7.1	51	0.31 J	0.091 J	14000	8.9		6.2	21	17000
Football Field	SSHS-IRM3-B021	080619 09:00_SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated	6600	< 0.36 U	6.2	58	0.29 J	0.11 J	5400	8.4		6.2	22	17000
Football Field	SSHS-IRM3-S141	080619 09:00_SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated	6900	0.84 J	9.2	450	0.39	0.4 J	14000	16		7.9	70	23000
Football Field	SSHS-IRM3-S142	080619 09:00_SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated	8700	0.56 J	4.8	69	0.39 J	0.081 J	5400	11		8.4	21	20000
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated	7300	< 0.35 U	5.3	300 J	0.31 J	0.3 J	12000	9.9		8.1 J	33	18000
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated	4700	< 0.33 U	4	110 J	0.19 J	0.16 J	8400	6.8		4.7 J	20	12000
Football Field	SSHS-IRM3-S144	080619 09:00_SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated	5600	< 0.31 U	5.2	33	0.22 J	0.12 J	30000	7.6		5.8	20	13000
Football Field	SSHS-IRM3-S146	080619 09:00_SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated	10000	0.38 J	6.7	54	0.41 J	0.074 J	1500	12		7.1	33	21000
Football Field	SSHS-IRM3-S148	080619 09:00_SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated	6200	< 0.4 U	8.3	64	0.35 J	0.13 J	1600	10		5.9	23	19000
Football Field	SSHS-IRM3-S149	080619 09:00_SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated	5600	< 0.37 U	5.6	59	0.27 J	0.14 J	1800	7.6		5.8	28	14000
Football Field	SSHS-IRM3-S155	080619 09:00_SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated	7800	0.37 J	6.2	59	0.34 J	0.11 J	6600 J	10		6	26	17000
Football Field	SSHS-IRM3-S159	080619 09:00_SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated	8400	0.76 J	7.9	160	0.42	0.2 J	14000	15		7.4	99	24000
Football Field	SSHS-IRM3-S160	080619 09:00_SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated	7100	< 0.39 U	4.7	51	0.3 J	0.14 J	3300	11		6.6	39	17000
Football Field	SSHS-IRM3-S161	080619 09:00_SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated	6100	< 0.36 U	6.5	63	0.25 J	0.13 J	26000	8.6		5.3	25	15000
Football Field	SSHS-IRM3-S162	080619 09:00_SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated	6400	< 0.4 U	4.5	36	0.3 J	0.11 J	20000	8.4		6.1	22	14000
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	4400	< 0.94 U	4.3	32	0.18 J	0.039 J	40000	7.2 J+		4.5 J	15	10000
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	6900	0.47 J	6.7	75	0.29 J	0.099 J	54000	10 J+		6.2	56	15000
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated	9000	< 0.36 U	7.7	200	0.39 J	0.31 J	4000	29		7.0	500	25000
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated	8700	< 0.34 U	13	68	0.42	0.24 J	4000	11		7.9	34	28000
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated	5100	< 0.33 UT	5.2	110 T	0.16 J	< 0.036 U	2300 T	7.4		3.1 J	14	16000
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated	7800	< 0.31 U	7.2	110	0.34 J	0.18 J	13000	11 B		6.3	40	19000
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated	8200	< 0.36 U	7.6	470	0.38 J	0.58	8700	39 B		5.9	72	20000
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	8400	< 0.22 U	6.4	45	0.32	0.18 J	37000	26	< 0.22 U	8.4	29	19000
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	4800	< 0.3 U	3.7	47	0.19 J	0.12 J	27000	8.1		4.2 J	23	12000
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated	6400	< 0.28 U	5.8	38	0.27 J	0.086 J	2000	8.5		6.0	33	16000
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated	6800	< 0.31 U	6.9	49	0.27 J	0.11 J	24000	8.3		7.0	21	15000
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated	8600	< 0.33 U	9.1	86	0.39	0.080 J	1100	10		8.2	26	21000
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated	5600	< 0.35 U	4.8	54	0.24 J	0.095 J	33000 B	7.3		4.9 J	20	13000
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated	6700	< 0.37 U	5.0	92	0.24 J	0.18 J	16000 B	12		6.3	29	15000
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated	7400	< 0.34 U	6.1	56	0.33 J	0.11 J	16000 B	8.9		6.0	21	17000
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated	6800	< 0.35 U	5.3	110	0.27 J	0.10 J	27000	13		5.8	20	16000
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated	5900	< 0.35 U	4.7	76	0.24 J	0.10 J	48000	7.4		5.3	19	15000
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated	7000	< 0.36 U	5.6	30	0.28 J	0.16 J	33000	8.5		6.1	23	16000
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated	6300	< 0.36 U	7.2	32	0.27 J	0.072 J	2700	9.1		5.8	21	17000
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated	8900	< 0.36 UT	9.3	74	0.39 J	< 0.038 U	6500 T	11		8.4	18	21000
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated	7900	< 0.35 U	9.9	100	0.37 J	0.11 J	6600	10		7.2	41	19000
Football Field	SSHS-B3459	090120 10:30_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated								7.2	< 0.23 U			
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated	6000	< 0.37 U	6.2	43	0.26 J	0.13 J	7500	8.2		6.1	23	16000
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated	4600	< 0.41 U	5.5	24	0.21 J	0.065 J	1500	5.8		4.7	16	12000
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated	4700	< 0.30 U	6.5	38	0.21 J	0.064 J	1500	6.1		4.8	16	14000
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated	6000	< 0.39 U	5.6	44	0.27 J	0.12 J	2000	8.0		5.8	20	15000
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated	6200	< 0.33 U	5.2	39	0.27 J	0.17 J	13000	7.5		5.7	21	15000
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated	5600	0.47 J	7.3	37	0.29 J	0.21 J	16000	7.0		5.4	22	14000
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated	6500	< 0.35 U	4.9	47	0.27 J	0.14 J	1700	8.7		6.0	29	16000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	6.8	14000	420	0.026 J	12		< 0.54 U	< 0.11 U	92 J		< 0.22 U
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	21	16000	440	0.0081 J	12		< 0.54 U	< 0.11 U	91 J		< 0.22 U
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	9.4	3100	690	0.011 J	13	730	< 0.58 U	< 0.12 U	52 J		0.55 J
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	300	4100	850	0.061	180	810	< 0.57 U	0.22 J	110 J		< 0.23 U
Football Field	SSHS-B2027	072718 09:00_SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	7.7	3900	310	< 0.0083 U	9.8	790	< 0.59 U,^	< 0.12 U	71 J		< 0.24 U
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	7.2	5000	400	< 0.0078 U	11	580	< 0.54 U	< 0.11 U	65 J		< 0.22 U
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	16	3400	550	0.095	22	1200	< 0.63 U	< 0.13 U	33 J		0.33 J
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	17	3500	420	0.015 J	15		< 0.59 U	< 0.12 U	54 J		< 0.24 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	18	2300	320	< 0.0086 U	21		< 0.59 U	< 0.12 U	60 J		< 0.24 U
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	14	3100	600	0.033 J	26	1100	< 0.65 U	< 0.13 U	33 J		0.29 J
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	6.9	4100	450	0.012 J	11		< 0.54 U	< 0.11 U	49 J		0.3 J
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	6.3	4800	670	< 0.0083 U	15		< 0.59 U	< 0.12 U	58 J		0.31 J
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	6.9	2300	360	0.0089 J	13	770	< 0.56 U,^	< 0.11 U	250 J		< 0.23 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	9.6	2200	370	< 0.01 U	15	1400	< 0.7 U	< 0.14 U	61 J		0.36 J
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	6.4	7600	340	< 0.0079 U	13	630	< 0.55 U	< 0.11 U	77 J		< 0.22 U
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	3.6	6700	330	< 0.008 U	10	610	1	< 0.11 U	86 J		< 0.22 U
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	5.6	2500	650	< 0.009 U	15		< 0.58 U	< 0.12 U	33 J		< 0.24 U
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	13	2400	560	< 0.0078 U	82		< 0.56 U	< 0.11 U	49 J		< 0.23 U
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	40	5700	450	< 0.0094 U	180		< 0.6 U	< 0.12 U	74 J		< 0.24 U
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	24	2200	350	< 0.0082 U	120		< 0.58 U	< 0.12 U	42 J		< 0.23 U
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	27	3600	410	0.014 J	15	560 J	< 0.59 U	< 0.12 U	61 J		< 0.24 U
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated	17	17000	540	< 0.016 U	16	810	0.83 J	< 0.12 U	96 J		< 0.37 U
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated	11	5000	440	< 0.015 U	15	680	< 0.58 U	< 0.12 U	72 J		< 0.36 U
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated	14	10000	490	< 0.016 U	34	700	1.2	< 0.12 U	92 J		< 0.36 U
Football Field	SSHS-B2724	042519 08:35_SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated										23 J	
Football Field	SSHS-IRM3-B012	072019 09:15_SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated	9.6	3000 J+	430	< 0.015 U	13		< 0.51 U	< 0.1 U	110 J		< 0.32 U
Football Field	SSHS-IRM3-B009	080319 09:30_SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated	9.1	2000	580	< 0.017 U	17		< 0.53 U	< 0.11 U	41 J		< 0.33 U
Football Field	SSHS-IRM3-S158	080319 09:30_SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated	460	4500	400	0.051	23		1.1	< 0.12 U	430 J		< 0.35 U
Football Field	SSHS-IRM3-B014	080619 09:00_SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated	12	2200	370	< 0.015 U	14		< 0.49 U	< 0.1 U	< 25 U		< 0.31 U
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated	10	4100	440	< 0.013 U	17		< 0.55 U	< 0.11 U	270 J		< 0.34 U
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated	12	3800	390	< 0.014 UJ	15		< 0.54 U	< 0.11 U	330 J		< 0.33 U
Football Field	SSHS-IRM3-B021	080619 09:00_SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated	9.3	4300	680	< 0.014 U	15		< 0.55 U	< 0.11 U	270 J		< 0.34 U
Football Field	SSHS-IRM3-S141	080619 09:00_SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated	97	3300	430	0.11	30		0.56 J	< 0.1 U	220 J		< 0.31 U
Football Field	SSHS-IRM3-S142	080619 09:00_SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated	6.8	5000	450	< 0.015 U	19		< 0.55 U	< 0.11 U	54 J		< 0.34 U
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated	7.6	5500	3000 J	< 0.012 U	22 J		< 1.1 U	< 0.22 U	< 27 U		< 0.66 U
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated	4.7	5700	1200 J	< 0.014 U	12 J		< 0.5 U	< 0.1 U	< 25 U		< 0.31 U
Football Field	SSHS-IRM3-S144	080619 09:00_SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated	6.8	6500	480	< 0.015 U	13		< 0.46 U	< 0.095 U	< 23 U		< 0.29 U
Football Field	SSHS-IRM3-S146	080619 09:00_SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated	16	2700	380	< 0.015 U	19	710	< 0.56 U	< 0.11 U	65 J		< 0.35 U
Football Field	SSHS-IRM3-S148	080619 09:00_SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated	11	2100	600	< 0.014 U	16	780	< 0.6 U	< 0.12 U	51 J		< 0.37 U
Football Field	SSHS-IRM3-S149	080619 09:00_SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated	7.4	1900	830	< 0.015 U	15	840	< 0.56 U	< 0.11 U	44 J		< 0.35 U
Football Field	SSHS-IRM3-S155	080619 09:00_SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated	24	3400	370	< 0.014 U	19		< 0.55 U	< 0.11 U	190 J		< 0.34 U
Football Field	SSHS-IRM3-S159	080619 09:00_SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated	180	3200	410	0.053	69		1	< 0.11 U	230 J		< 0.32 U
Football Field	SSHS-IRM3-S160	080619 09:00_SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated	9.1	3100	350	< 0.016 U	18		< 0.59 U	< 0.12 U	110 J		< 0.37 U
Football Field	SSHS-IRM3-S161	080619 09:00_SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated	8.4	5300	630	< 0.015 U	15		< 0.54 U	< 0.11 U	77 J		< 0.34 U
Football Field	SSHS-IRM3-S162	080619 09:00_SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated	7.6	4200	430	< 0.017 U	15		< 0.61 U	< 0.12 U	< 31 U		< 0.38 U
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	8.6	5100	450 J+	< 0.034 U	9.4	460 J	< 0.94 U	< 0.47 U	83 J		< 1.9 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	31	6600	540 J+	< 0.025 U	25	730	< 0.51 U	< 0.1 U	100 J		< 0.32 U
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated	130	2600	430	0.030 J	46	670	< 0.55 U	< 0.11 U	140 J		< 0.34 U
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated	19	4700	1200	0.051	23	920	< 0.51 U	< 0.10 U	63 J		< 0.32 U
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated	29	1500	160 T	< 0.020 U	12	660	< 0.51 U	< 0.10 U	96 J		< 0.32 U
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated	110	5300	510	0.046	62	850	< 0.47 U	< 0.097 U	83 J		< 0.30 U
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated	95	2800	520	0.12	39	720	< 0.54 U	< 0.11 U	110 J		< 0.34 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	12	6900	350	< 0.022 U	27	810	0.8	< 0.069 U	92 J		< 0.21 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	16	7600	320	0.031 J	13	580	0.66 J	< 0.093 U	84 J		< 0.28 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated	7.2	2500	370	< 0.022 U	16	540	< 0.42 U	< 0.085 U	52 J		< 0.26 U
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated	10	6400	490	< 0.021 U	20	620	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated	12	2400	640	0.030 J	20	760	< 0.50 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated	10	6800	330	< 0.024 U	14	570	< 0.54 U	< 0.11 U	63 J		< 0.33 U
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated	8.6	11000	1500	< 0.023 U	17	1100	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated	14	4500	520	< 0.021 U	17	740	< 0.51 U	< 0.10 U	< 60 U		< 0.32 U
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated	16	6700	380	0.022 J	27	760	0.62 J	< 0.11 U	< 63 U		< 0.33 U
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated	9.1	7500	370	< 0.022 U	18	650	0.85 J	< 0.11 U	64 J		< 0.33 U
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated	14	9300	280	< 0.023 U	16	710	< 0.55 U	< 0.11 U	64 J		< 0.34 U
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated	10	2500	390	< 0.024 U	15	780	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated	13	3400 T	440 T	< 0.022 U	20	940	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated	48	2800	600	0.026 J	26	840	< 0.53 U	< 0.11 U	63 J		< 0.33 U
Football Field	SSHS-B3459	090120 10:30_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated											
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated	20	4000	580	< 0.019 U	17	600	< 0.48 U	< 0.084 U	< 65 U		3.5
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated	6.4	1800	250	< 0.020 U	12	640	< 0.53 U	< 0.092 U	< 71 U		1.4 J
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated	7.5	2000	400	< 0.018 U	13	480	< 0.40 U	< 0.069 U	< 53 U		2.3
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated	16	2000	570	0.028 J	16	790	< 0.51 U	< 0.089 U	< 69 U		3.4
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated	18	3400	400	< 0.021 U	16	570	< 0.44 U	< 0.076 U	< 59 U		2.4
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated	13	7500	440	< 0.021 U	14	610	0.66 J	< 0.088 U	< 68 U		2.8
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated	11	2600	650	< 0.022 U	17	540	< 0.46 U	< 0.079 U	< 61 U		3.7

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated		7.8	40
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated		9.1	58
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated		11	55
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated		19	160
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated		9.8	55
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated		10	51
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated		18	61
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated		10	59
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated		9.9	60
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated		16	64
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated		8.5	47
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated		11	59
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated		11	53
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated		12	56
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated		8.8	60
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated		9.2	36
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated		11	66
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated		11	54
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated		13	110
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated		8.2	120
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated		12	64
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated		11	55
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated		10	52
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated		11	64
Football Field	SSHS-B2724	042519 08:35 SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated			
Football Field	SSHS-IRM3-B012	072019 09:15 SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated		9.5	51
Football Field	SSHS-IRM3-B009	080319 09:30 SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated		13	56
Football Field	SSHS-IRM3-S158	080319 09:30 SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated		17	140
Football Field	SSHS-IRM3-B014	080619 09:00 SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated		10	610
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated		13	66
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated		12	59
Football Field	SSHS-IRM3-B021	080619 09:00 SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated		11	63
Football Field	SSHS-IRM3-S141	080619 09:00 SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated		15	220
Football Field	SSHS-IRM3-S142	080619 09:00 SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated		12	74
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated		11	79 J
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated		7.5	47 J
Football Field	SSHS-IRM3-S144	080619 09:00 SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated		9.5	48
Football Field	SSHS-IRM3-S146	080619 09:00 SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated		14	59
Football Field	SSHS-IRM3-S148	080619 09:00 SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated		14	71
Football Field	SSHS-IRM3-S149	080619 09:00 SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated		9.6	55
Football Field	SSHS-IRM3-S155	080619 09:00 SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated		12	64 J-
Football Field	SSHS-IRM3-S159	080619 09:00 SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated		15	110
Football Field	SSHS-IRM3-S160	080619 09:00 SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated		12	75
Football Field	SSHS-IRM3-S161	080619 09:00 SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated		11	58
Football Field	SSHS-IRM3-S162	080619 09:00 SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated		11	59
Football Field	SSHS-B2976	110919 09:30 SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated		7.8	44
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated		12	56
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated		14	220
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated		19	110
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated		9.2	40 T
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated		12	75
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated		14	240
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated		12	62
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated		8.4	48
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated		9.2	66
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated		9.7	60
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated		13	70
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated		8.9	50
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated		14	64
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated		11	59
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated		11	56
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated		9.4	52
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated		9.5	56
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated		15	55
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated		12	53 T
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated		14	71
Football Field	SSHS-B3459	090120 10:30 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated			
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated		11	78
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated		8.4	50
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated		8.3	56
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated		11	69
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated		9.8 B	66
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated		9.5 B	57
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated		10 B	76

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated	6400	0.47 JT	6.4	48	0.32 J	0.20 J	8100 T	7.9		6.3	23	16000
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated	8400	< 0.36 U	6.5	1000	0.34 J	0.16 J	12000	14		10	34	21000
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated	6400	< 0.36 U	4.5	56	0.25 J	0.099 J	37000	9		5.4	22	14000
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated	9900	0.45 J	7.8	80	0.43 J	0.11 J	3000	13		9.1	24	24000
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated	8000	0.80 J	6.0	76	0.37 J	0.14 J	10000	14		6.3	34	16000
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated	7800	< 0.34 U	5.4	56	0.32 J	0.17 J	4300	9.4		7.0	31	17000
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated	6800	< 0.31 U	5.5	73	0.30 J	0.17 J	2500	8.4		7.6	22	15000
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated	4800	< 0.39 U	4.3	29	0.23 J	0.19 J	8100	98		3.5 J	180	12000
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated	4300	< 0.28 U	3.7	30	0.19 J	0.15 J	2100	100		3.5 J	160	11000
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated	5900	0.42 J	4.7	40	0.27 J	0.12 J	1100	8.0		5.7	19	15000
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	6200	< 0.29 U	3.8	67	0.26 J	0.12 J	26000	8.0		6.2	21	15000
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated	10000	0.55 J	9.2	370	0.42	0.18 J	6200	23		7.7	44	23000
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated	6500	< 0.26 U	5.4	88	0.28 J	0.13 J	9200	18		5.8	26	15000
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated	8400	< 0.40 U	6.2	68	0.34 J	0.089 J	2900	16		7.4	24	19000
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated	7500	< 0.41 U	5.7	59	0.30 J	< 0.054 U	1600	9.3		6.2	20	16000
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated	5300	< 0.36 U	3.3	26	0.16 J	0.089 J	24000	8.5		4.5	19	12000
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated	6900	< 0.38 U	6.4	49	0.23 J	0.12 J	23000	10		7.3	22	17000
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated	4000	< 0.31 U	4.4	270	0.12 J	0.38 J	27000	50		4.7	43	10000
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated	4800	< 0.31 U	4.3	34	0.21 J	0.051 J	10000	33		4.9	17	12000
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated	5300	< 0.37 U	5.1	34	0.17 J	0.21 J	28000	18		4.9	55	15000
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated	6700	< 0.41 U	7.6	38	0.25 J	0.27 J	14000	18		6.9	72	17000
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated	5900	< 0.37 U	5.5	34	0.21 J	0.31 J	9300	18		8.6	100	14000
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated	5500	< 0.34 UT	4.7	26	0.21 J	0.094 J	1100	7.5		5.5	17	14000
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated	6000	< 0.38 U	4.4	27	0.21 J	0.073 J	1000	12		5.1	19	14000
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated	7600 B	< 0.38 UT	7.8	75 T	0.39 J	0.20 J	1100	9.2 T		7.0	28	21000
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated	4100	0.57 J	4.0	33	0.17 J	0.058 J	31000	5.4		4.2 J	17	11000
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated	3900	0.40 J	4.3	32	0.16 J	0.068 J	28000	4.9		4.2 J	11	9000
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	5500	< 0.25 U	6.2	36	0.29	< 0.027 U	1000	6.8		6.2	18	13000
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	5000	< 0.30 U	7.0	34	0.23 J	< 0.032 U	7500	7.3		4.9	21	14000
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	7200	0.59 J	9.9	83	0.36	0.16 J	13000	17		7.5	71	21000 B
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	5200	< 0.30 U	6.8	35	0.23 J	< 0.032 U	3200	7.2		5.0	19	14000
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	7000	0.59 J	9.2	84	0.36 J	0.12 J	8400	17		7.0	89	21000 B
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	5800	1.1	9.3	62	0.33 J	0.035 J	4100	8.6		6.2	31	16000
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	8600	< 0.36 U	4.7	66	0.33 J	0.075 J	4300	10		5.7	41	15000
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	8100	1.2	5.6	69	0.35 J	0.12 J	3700	11		6.0	84	17000
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	8600	4.3	6.1	71	0.35 J	0.097 J	4300	11		6.0	52	19000
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	10000	2.7	12	120	0.48 J	0.12 J	3600	19		9.0	210	24000
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	12000	2.3	12	71	0.53 J	0.11 J	6700	16		9.5	68	29000
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	7200	1.2	5.2	91	0.36 J	0.11 J	2900	14		5.6	63	18000
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated	7000	1.3 T	4.8	74	0.31 J	0.10 J	10000 T	12		5.5	49 T	17000
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	5200	0.085 J	4.4	42	0.29	0.11 B	1100 B	6.4 B		4.4	21	12000 B
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	9000	0.91	9.1	54	0.39	0.085 BJ	1200 B	20 B		6.8	220	21000 B
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	7900	0.41 J	5.7	41	0.37 J	< 0.038 U	1200	12		4.5 J	20	18000
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated	3700	0.091 J	3.5	27	0.18	0.18	34000	5.8 B		3.6 B	22	9600
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated	5700	< 0.33 U	5.3	37	0.18 J	0.12 J	28000	7.3		5.0	17	14000
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated	4700	< 0.32 U	3.3	26	0.15 J	0.078 J	31000	5.6		4.0 J	18	11000
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated	7400	< 0.39 U	5.9	70	0.30 J	0.094 J	4100	8.4		6.1	20	15000
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated	4400	< 0.28 U	4.6	33	0.14 J	0.095 J	39000	5.6		4.7	18	11000
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated	4000	< 0.20 U	3.2	34	0.14 J	0.060 J	57000	5.3		4.0	16	8900
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated	3300	< 0.23 U	8.4	44	0.12 J	0.056 J	45000	4.2		3.2 J	12	8500
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated	3500	< 0.22 U	3.5	26	0.14 J	0.098 J	49000	4.4		3.5	14	7900
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated	3500	< 0.28 U	3.4	25	0.15 J	0.12 J	73000	5.1		3.5 J	15	8200
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated	4500	< 0.30 U	3.7	29	0.16 J	0.10 J	37000	6.2		4.6	19	10000
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated	4000	< 0.24 U	3.3	52	0.16 J	0.079 J	40000	5.5		4.1	36	9000
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	9000	0.39 J	7	58	0.32 J	0.072 J	40000	13		6.7	23	19000
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated	4400	< 0.34 U	4.3	31	0.22 J	0.091 J	26000	8.5		4.4	24	10000
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated	4900	< 0.29 U	3.7	48	0.21 J	0.10 J	32000	8.0		4.7	25	11000
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated	3800	< 0.28 U	4.2	29	0.14 J	0.092 J	31000	6.8		3.9	23	9100
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated	3600	< 0.31 U	3.7	31	0.16 J	0.085 J	46000	6.2		3.8	76	8600
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated	4400	< 0.42 U	3.5	40	0.25 J	0.070 J	28000	6.2		3.7	15	10000
Football Field	SSHS-B2679	042519 08:35 SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated												
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated	6600	< 0.34 U	5.7	40	0.26 J	0.044 J	780	7.8		6.1	20	15000
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated	6500	< 0.39 U	7.5	39	0.28 J	0.072 J	830	8.3		6.2	20	16000
Football Field	SSHS-IRM3-B016	072719 09:00 SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated	6200	0.56 J	10	85	0.31 J	0.37 J	5600	8.7		8.3	26	20000
Football Field	SSHS-IRM3-B026	072719 09:00 SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated	8200	< 0.41 U	5.6	69	0.29 J	0.11 J	22000	11		7.4	26	19000
Football Field	SSHS-IRM3-B027	072719 09:00 SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated	6700	< 0.4 U	5.7	81	0.3 J	0.12 J	36000	9.3		5.7 J	26	15000
Football Field	SSHS-IRM3-S156C	072719 09:00 SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated	6700	< 0.38 U	6.8	59	0.34 J	0.11 J	4100	9		6.7	21	18000
Football Field	SSHS-IRM3-S188	072719 09:00 SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated	5400	< 0.38 U	4.7	33	0.24 J	0.11 J	22000	7.1		4.8 J	19	12000
Football Field	SSHS-IRM3-B022	073019 09:00 SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated	6500	< 0.43 U	9.4	33	0.32 J	0.12 J	8300	9		7.5	27	19000
Football Field	SSHS-IRM3-B023	073019 09:00 SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated	5400	< 0.34 U	4.4	20	0.23 J	0.11 J	6100	7.7		5.2	14	13000
Football Field	SSHS-IRM3-S175	073019 09:00 SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated	6500	< 0.32 U	5.8	38	0.27 J	0.078 J	1600	8.3		6	20	16000
Football Field	SSHS-IRM3-S176	073019 09:00 SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated	4800	< 0.31 U	3.7	26	0.19 J	0.072 J	10000	6.2		4.6	18	12000
Football Field	SSHS-IRM3-S177	073019 09:00 SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated	5100	< 0.35 U	4.3	40	0.21 J	0.066 J	1100	6.4		4.4 J	21	13000
Football Field	SSHS-IRM3-S179	073019 09:00 SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated	5400	< 0.33 U	5.1	61	0.23 J	0.078 J	12000	7		4.8 J	20	14000

DRAFT

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated	12 T	4400 T	590 T	< 0.024 U	17	590	< 0.49 U	< 0.085 U	< 66 U		3.6
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated	27	7500	320	< 0.02 U	140	930	< 0.55 U	< 0.11 U	130 J		< 0.34 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated	8.6	6300	380	< 0.02 U	35	800	< 0.55 U	< 0.11 U	81 J		< 0.34 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated	14	3400	490	< 0.019 U	23	940	< 0.56 U	< 0.12 U	< 66 U		< 0.35 U
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated	56	5100	440	0.040	27	1000	< 0.56 U	< 0.12 U	90 J		< 0.35 U
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated	9.3	4000	800	< 0.022 U	19	820	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated	11	2500	730	< 0.023 U	18	570	< 0.47 U	< 0.097 U	< 55 U		< 0.29 U
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated	6.8	5000	410	< 0.020 U	11	580	< 0.59 U	< 0.12 U	91 J		< 0.36 U
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated	5.6	2000	370	< 0.019 U	11	450	< 0.42 U	< 0.085 U	90 J		< 0.26 U
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated	6.8	2000	360	< 0.023 U	14	590	< 0.51 U	< 0.10 U	64 J		< 0.32 U
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	9.2	3100	420	< 0.019 U	180	590	< 0.44 U	< 0.090 U	60 J		< 0.27 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated	41	2900	430	0.042	40	1200	0.68 J	< 0.11 U	200 J		< 0.33 U
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated	24	5600	490	0.027 J	17	800	< 0.39 U	< 0.080 U	65 J		< 0.24 U
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated	9.2	3000	480	0.022 J	19	740	< 0.52 U	< 0.090 U	< 70 U		< 0.44 U
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated	9.3	2300	410	0.024 J	16	680	< 0.53 U	< 0.092 U	< 71 U		< 0.45 U
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated	5.5	3400	230	< 0.018 U	12	470 J	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated	14	4200	350	< 0.023 U	22	740	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated	120	2800	260	0.031 J	86	460	< 0.41 U	< 0.071 U	< 55 U		0.38 J
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated	5.7	2800	340	< 0.019 U	64	550	< 0.40 U	< 0.070 U	< 54 U		< 0.34 U
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated	58	3300	400	0.029 J	180	490 J	< 0.48 U	< 0.084 U	68 J		< 0.41 U
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated	12	7800	540	0.027 J	440	750	< 0.53 U	< 0.092 U	< 71 U		< 0.45 U
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated	9.8	2800	980	0.037 J	880	560	< 0.48 U	0.12 J	< 65 U		< 0.41 U
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated	6.6	2000	340 T	< 0.018 U	14	480	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated	6.0	2100	310	< 0.023 U	14	460 J	< 0.49 U	0.086 J	< 66 U		< 0.42 U
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated	22 T	1800	1200 T	0.018 JT	17	630	0.56 J	0.19 J	< 67 U		< 0.43 U
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated	4.9	2700	280	< 0.022 U	9.7	350 J	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated	5.0	2600	270	< 0.021 U	9.3	310 J	< 0.46 U	< 0.095 U	< 54 U		0.35 J
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	8.4	1700	490	< 0.021 U	15	560	< 0.38 U	< 0.077 U	< 44 U		0.34 BJ
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	12	4100	490	0.027 J	14	520	< 0.46 U	< 0.094 U	< 54 U		0.43 BJ
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	69	2900	510	0.066	59	630	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	11	2400	510	< 0.022 U	14	470	< 0.45 U	< 0.092 U	< 53 U		0.31 BJ
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	70	2700	430	0.086	55	650	< 0.50 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	86	2100	320	0.021 J	30	530	< 0.44 U	< 0.089 U	51 J		0.39 BJ
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	30	2200	470	0.092	15	510 J	< 0.55 U	< 0.11 U	< 64 U		0.42 J
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	55	2200	390	0.11	23	580	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	54	2200	400	0.064	16	580	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	62	3200	740	0.084	100	1600	< 0.80 U	< 0.16 U	< 94 U		< 0.50 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	84	3400	620	0.041 J	39	1100	< 0.79 U	< 0.16 U	< 92 U		0.68 J
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	54	1600	390	0.061	23	550	< 0.50 U	< 0.10 U	< 58 U		0.35 J
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated	80 T	3100	320	0.14	28	750	< 0.53 U	< 0.11 U	130 J		< 0.33 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	5.8	1600	470	< 0.024 U	14	540	< 0.086 U	< 0.019 U	49		0.076
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	39	2300	310	0.094	200	630	0.20 J	0.070 J	48 J		0.089 J
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	9.4	2400	200	< 0.024 U	17	1500	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated	13	3400	370	< 0.019 U	12	470	< 0.10 U	0.052 J	52		< 0.057 U
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated	6.8	4800	620	< 0.019 U	13	450 J	< 0.51 U	< 0.10 U	< 59 U		< 0.32 U
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated	7.1	2300	340	< 0.017 U	10	440 J	< 0.49 U	< 0.10 U	< 57 U		< 0.30 U
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated	13	1800	560	0.051 J	15	590	< 0.51 U	< 0.089 U	< 69 U		< 0.44 U
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated	5.3	7700	410	< 0.019 U	12	380 J	< 0.36 U	< 0.063 U	55 J		< 0.31 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated	12	6700	280	< 0.022 U	15	400	0.76	< 0.063 U	< 36 UT		< 0.19 U
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated	8.3	6000	680	< 0.019 U	8.8	310 J	0.56 J	< 0.070 U	< 40 UT		< 0.21 U
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated	6.4	2600	310	< 0.020 U	9.6	340	0.60 J	< 0.067 U	< 38 UT		< 0.20 U
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated	6.7	14000	350	< 0.018 U	9.7	330 J	0.93	< 0.086 U	< 50 UT		< 0.26 U
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated	7.5	7000	390	< 0.015 U	12	370 J	0.65 J	< 0.093 U	< 53 UT		< 0.28 U
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated	10	3800	350	< 0.027 U	51	370	0.41 J	< 0.074 U	< 43 UT		< 0.23 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	11	6900	540	< 0.034 U	20	790	0.6 J	< 0.034 U	91 J		< 0.034 U
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated	5.4	3300	300	< 0.020 U	18	520	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated	6.1	3800	360	< 0.017 U	20	510	< 0.37 U	< 0.065 U	< 50 U		< 0.32 U
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated	5.6	3300	260	< 0.017 U	18	420	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated	5.4	5900	370	< 0.020 U	21	430	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated	5.1	3600	250	< 0.019 U	10	560 J	< 0.55 U	< 0.096 U	< 74 U		< 0.47 U
Football Field	SSHS-B2679	042519 08:35 SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated										25 J	
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated	7.1	1900	350	< 0.016 U	15		< 0.52 U	< 0.11 U	38 J		< 0.32 U
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated	7.3	2000	400	< 0.014 U	15		< 0.6 U	< 0.12 U	41 J		< 0.37 U
Football Field	SSHS-IRM3-B016	072719 09:00 SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated	12	2700	1900	< 0.015 U	22		< 0.55 U	< 0.11 U	130 J		< 0.34 U
Football Field	SSHS-IRM3-B026	072719 09:00 SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated	12	9700	590	< 0.017 U	15		< 0.62 U	< 0.13 U	140 J		< 0.39 U
Football Field	SSHS-IRM3-B027	072719 09:00 SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated	17	6600	310	< 0.014 U	15		0.84 J	< 0.12 U	260 J		< 0.38 U
Football Field	SSHS-IRM3-S156C	072719 09:00 SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated	11	3500	520	< 0.016 U	17		< 0.57 U	< 0.12 U	250 J		< 0.35 U
Football Field	SSHS-IRM3-S188	072719 09:00 SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated	7.8	5700	370	< 0.015 U	13		< 0.58 U	< 0.12 U	73 J		< 0.36 U
Football Field	SSHS-IRM3-B022	073019 09:00 SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated	13	5600	240	0.019 J	18		< 0.65 U	< 0.13 U	96 J		< 0.41 U
Football Field	SSHS-IRM3-B023	073019 09:00 SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated	10	3700	170	< 0.013 U	13		< 0.52 U	< 0.11 U	83 J		< 0.32 U
Football Field	SSHS-IRM3-S175	073019 09:00 SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated	12	2100	410	< 0.015 U	15		< 0.49 U	< 0.1 U	170 J		< 0.3 U
Football Field	SSHS-IRM3-S176	073019 09:00 SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated	6.1	2000	320	< 0.012 U	12		< 0.47 U	< 0.097 U	110 J		< 0.29 U
Football Field	SSHS-IRM3-S177	073019 09:00 SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated	5.7	1900	330	< 0.012 U	11		< 0.53 U	< 0.11 U	80 J		< 0.33 U
Football Field	SSHS-IRM3-S179	073019 09:00 SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated	7	3000	260	< 0.015 U	13		< 0.51 U	< 0.1 U	61 J		< 0.32 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated		11 B	71
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated		14	82
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated		9.7	52
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated		15	110
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated		14	75
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated		12	64
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated		11	65
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated		8.8	85
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated		10	61
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated		11	67
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated		9.3	58
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated		20	80
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated		11	60
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated		13	79
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated		11	62
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated		8.3	59
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated		13 B	64
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated		7.0 B	130
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated		9.0	53
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated		8.5	200
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated		11	260
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated		9.0	480
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated		8.0	55
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated		7.8	56
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated		16 T	160
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated		6.2	35
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated		6.2	34
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated		11	56
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated		9.2	56
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated		14	140
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated		9.0	68
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated		14	120
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated		10	83
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated		14	66
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated		14	100
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated		16	91
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated		19	260
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated		22	110
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated		14	82
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated		13	95 T
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated		9.1	46
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated		15	400
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated		14	55
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated		7.1	44
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated		8.5	85
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated		6.8	52
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated		11	66
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated		6.9	52
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated		6.7	43
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated		5.2	45
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated		5.6	46
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated		6.6	52
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated		7.4	56
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated		6.9	500
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated		14	69
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated		6.5	57
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated		7.6	60
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated		5.6	63
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated		5.4	51
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated		6.5	43
Football Field	SSHS-B2679	042519 08:35 SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated			
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated		9.6	49
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated		10	52
Football Field	SSHS-IRM3-B016	072719 09:00 SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated		13	160
Football Field	SSHS-IRM3-B026	072719 09:00 SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated		16	78
Football Field	SSHS-IRM3-B027	072719 09:00 SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated		12	72
Football Field	SSHS-IRM3-S156C	072719 09:00 SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated		12	65
Football Field	SSHS-IRM3-S188	072719 09:00 SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated		8.8	57
Football Field	SSHS-IRM3-B022	073019 09:00 SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated		14	71
Football Field	SSHS-IRM3-B023	073019 09:00 SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated		8.6	54
Football Field	SSHS-IRM3-S175	073019 09:00 SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated		11	59
Football Field	SSHS-IRM3-S176	073019 09:00 SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated		7.6	59
Football Field	SSHS-IRM3-S177	073019 09:00 SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated		7.9	49
Football Field	SSHS-IRM3-S179	073019 09:00 SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated		9.7	53

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-IRM3-S180	073019 09:00 SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated	5500	< 0.35 U	6	40	0.24 J	0.094 J	2300	6.9		6.2	25	15000
Football Field	SSHS-IRM3-S181	073019 09:00 SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated	6800	< 0.33 U	5.1	38	0.28 J	0.078 J	1800	9.3		6.4	21	16000
Football Field	SSHS-IRM3-S182	073019 09:00 SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated	5700	0.44 J	5.3	48	0.25 J	0.092 J	20000	7.4		5.2	20	14000
Football Field	SSHS-IRM3-S183	073019 09:00 SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated	7100	0.45 J	6.1	66	0.3 J	0.13 J	16000	9.2		5.9	27	16000
Football Field	SSHS-IRM3-B024	073119 09:00 SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated	5800	< 0.42 U	7.3	57	0.28 J	0.1 J	5500	7.7		5.8 J	22	15000
Football Field	SSHS-IRM3-S201	080219 09:00 SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated	6500	< 0.38 U	5.8	53	0.28 J	0.11 J	5300	8.2		6.5	21	16000
Football Field	SSHS-IRM3-MH1DA	080319 09:30 SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated	5300	< 0.38 U	4.4	29	0.22 J	0.11 J	28000	7.1		4.8 J	17	13000
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1[1]	Not Excavated	430	7.6 J	< 0.44 U	48	0.042 J	0.58	6500	4.4		< 0.33 U	62	410000
Football Field	SSHS-IRM3-S150	080619 09:00 SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated	5800	< 0.39 U	4.9	35	0.25 J	0.095 J	1400	7.5		5.1 J	21	15000
Football Field	SSHS-IRM3-S156A	080619 09:00 SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated	5900	< 0.34 U	5.7	39	0.25 J	0.079 J	12000	7.2		5.1	19	14000
Football Field	SSHS-IRM3-S156B	080619 09:00 SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated	6800	< 0.37 U	7.5	54	0.34 J	0.091 J	1900	9.2		6.6	21	17000
Football Field	SSHS-IRM3-S166	080619 09:00 SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated	7000	< 0.38 U	7.4	49	0.33 J	0.11 J	4000	10		7.2	28	20000
Football Field	SSHS-IRM3-S167	080619 09:00 SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated	5400	< 0.35 U	6.1	47	0.24 J	0.077 J	21000	6.9		4.7 J	19	14000
Football Field	SSHS-IRM3-S169	080619 09:00 SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated	4700	< 0.35 U	4.6	40	0.21 J	0.075 J	7600	6.3		4.7 J	17	13000
Football Field	SSHS-IRM3-S170	080619 09:00 SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated	5600	0.53 J	6.8	38	0.27 J	0.071 J	10000	7.7		5.4 J	20	16000
Football Field	SSHS-IRM3-S172	080619 09:00 SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated	7500	0.43 J	5.9	99	0.32 J	0.093 J	9200	10		6.2	29	18000
Football Field	SSHS-IRM3-S174	080619 09:00 SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated	5800	< 0.34 U	5.7	73	0.29 J	0.13 J	6100	11		7.3	25	15000
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated	6800	< 0.31 U	6.6	51	0.26 J	0.065 J	7900	8.6		6.4	27	17000
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated	8800	< 0.32 U	8.1	84	0.37	0.13 J	10000	11		7.7	28	20000
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated	5900	< 0.27 U	4.9	78	0.25 J	0.13 J	19000	9.1		5.8	28	14000
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated	6400	< 0.31 U	4.1	25	0.26 J	0.091 J	1600	8.5		6.5	18	14000
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated	4700	< 0.30 U	7.0	25	0.19 J	0.11 J	40000	6.6		4.9	26	11000
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated	9300	< 0.34 U	7.2	66	0.42	0.073 J	14000	12		8.2	22	23000
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated	7800	< 0.34 U	5.2	84	0.30 J	0.12 J	23000	9.8		6.1	32	17000
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated	6600	< 0.36 U	5.5	29	0.25 J	0.094 J	33000	8.5		6.0	20	14000
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated	10000	< 0.30 U	7.4	73	0.43	0.098 J	22000	12		9.2	24	24000
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated	6800	< 0.31 U	4.8	54	0.28 J	0.11 J	33000	8.9		6.2	27	16000
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated	4100	< 0.38 U	6.2	54	0.28 J	0.078 J	5200	5.5		6.1	18	12000
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated	6500	< 0.32 U	6.6	37	0.28 J	0.079 J	5900	8.5		6.7	25	17000
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated	5000	0.74 J	5.1	53	0.26 J	0.13 J	62000	6.1		5.1	19	14000
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated	6200	< 0.35 U	5.6	44	0.26 J	0.072 J	15000	7.6		6.4	20	16000
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated	6000	< 0.39 U	4.7	89	0.31 J	0.096 J	48000	7.7		5.7	18	16000
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated	6200	< 0.28 U	4.0	35	0.26 J	0.10 J	14000	7.7		6.2	22	15000
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated	5100	< 0.28 U	4.9	34	0.24 J	0.13 J	4600	6.5		4.7	19	13000
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated	4200	1.4 J	3.6	33	0.12 J	< 0.053 U	680	7.3		2.4	9.3	17000
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	8700	< 0.35 U	7.7	100	0.44 J	0.069 J	10000	13		9.3	26	23000
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated	5700	< 0.35 UT	4.7	74 T	0.20 J	0.15 J	26000	9.2		5.1	29	12000
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated	4600	< 0.40 U	3.7	40	0.19 J	0.071 J	11000	7.1		4.7	19	12000
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated	5600	< 0.38 U	4.1	82	0.22 J	0.12 J	7500	11		5.3	36	15000
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated	3900	< 0.34 U	2.7	36	0.15 J	0.062 J	4200	6.0		4.1	15	10000
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated	7000	< 0.43 U	5.7	120	0.21 J	0.14 J	45000	15		6.4	36	17000
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated	8700	< 0.37 U	5.3	170	0.36 J	0.16 J	24000	9.9		7.8	34	20000
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated	5300	< 0.34 U	3.8	33	0.14 J	0.067 J	30000	7.7		5.3	22	12000
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated	4600	< 0.38 U	3.2	29	0.12 J	0.085 J	30000	7.5		4.9	17	10000
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	6800	< 0.35 U	6.9	66	0.33 J	0.082 J	16000	10		7.6	26	18000
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated	4800	< 0.34 U	4.5	42	0.19 J	0.099 J	26000	6.4		4.3 J	14	11000
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	3800	< 0.35 U	3.6	41	0.16 J	0.074 J	33000	6.1		3.6 J	14	10000
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated	5800	< 0.37 UJ	4.2	40	0.24 J	0.065 J	32000	11		5.2 J	17	13000 J
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated	7700	0.61 J	5.6	56	0.32 J	0.11 J	1700	9.2		6.4	25	16000
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated	8500	0.92 J	6.9	59	0.40	0.049 J	5100	10		8.0	20	20000
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated	3900	0.50 J	2.2	24	0.18 J	0.048 J	4400	5.2		3.5 J	14	8300
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated	7100	0.52 J	5.2	56	0.31 J	0.15 J	17000	9.3		7.1	28	16000
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated	8400	0.42 J	6.7	280	0.34 J	0.16 J	2800	12		6.5	25	17000
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated	7400	< 0.40 U	6.9	63	0.35 J	0.69	3700	11		8.0	35	14000
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated	7900	0.44 J	6.0	59	0.35 J	0.11 J	5200	9.6		7.4	23	16000
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated	5000	< 0.33 U	4.0	28	0.20 J	0.085 J	7300	6.5		4.5 J	17	11000
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated	4500	< 0.31 U	3.7	22	0.18 J	0.053 J	2800	5.8		4.0 J	17	11000
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated	5500	< 0.23 UT	4.0	32	0.22 J	0.086 J	18000 T	7.2		6.0	17	13000
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	7300	0.98	5.4	75	0.31	0.12 J	23000	9.4		6.9	35	16000
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	5900	< 0.33 U	4.9	770	0.26 J	0.12 J	23000	8.4		6.4	28	12000
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated	5500	< 0.34 U	5.5	57	0.18 J	0.093 J	19000	21 B		5.4	23	14000
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated	4600	< 0.37 U	4.2	24	0.14 J	0.083 J	15000	65 B		4.4	19	11000
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated	7400 T	< 0.41 U	5.4	49	0.29 J	0.16 J	3300	2200		7.1	110	17000
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated									19			
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated	4900 T	< 0.38 U	4.6	37	0.23 J	0.18 J	5000	760		4.8	94	12000
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated									13			
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	6700	0.35 J	8.9	61	0.33 J	0.31 J	3900	14		6.5	50	17000
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	5800	< 0.33 U	6.5	33	0.27 J	< 0.036 U	1500	7.5		5.2	18	14000
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	5100	< 0.24 U	6.6	49	0.23 J	0.028 J	4500	7.2		5.4	18	13000
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	7400	0.40 J	9.6	85	0.37 J	0.15 J	9000	18		7.2	73	22000 B
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	6300	1.3	9.1	52	0.31 J	< 0.039 U	4700	8.7		6.8	29	17000
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	9000	2.2	5.2	71	0.37 J	1.2	4900	13		6.9	150	20000
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	8100	1.4	5.5	63	0.35 J	0.12 J	3300	10		6.4	73	18000
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	7500	13	8.0	89	0.34 J	0.23 J	11000	13		6.8	130	25000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-IRM3-S180	073019 09:00_SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated	8.4	2500	520	< 0.016 U	17		< 0.52 U	< 0.11 U	42 J		< 0.32 U
Football Field	SSHS-IRM3-S181	073019 09:00_SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated	7.1	2600	200	< 0.015 U	17		< 0.5 U	< 0.1 U	50 J		< 0.31 U
Football Field	SSHS-IRM3-S182	073019 09:00_SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated	11	9500	400	< 0.014 U	14		0.59 J	< 0.098 U	76 J		< 0.3 U
Football Field	SSHS-IRM3-S183	073019 09:00_SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated	43	3000	370	< 0.016 U	20		< 0.46 U	< 0.093 U	160 J		< 0.28 U
Football Field	SSHS-IRM3-B024	073119 09:00_SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated	10	3700	520	< 0.018 U	14		< 0.64 U	< 0.13 U	140 J		< 0.4 U
Football Field	SSHS-IRM3-S201	080219 09:00_SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated	12	3600	560	< 0.016 U	16		< 0.57 U	< 0.12 U	200 J		< 0.36 U
Football Field	SSHS-IRM3-MH1DA	080319 09:30_SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated	7	5100	330	< 0.015 U	13		0.71 J	< 0.12 U	140 J		< 0.36 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	61	410 J	180	0.57	< 2.8 U	< 61 U	2.3	0.2 J	5300		1.8 J
Football Field	SSHS-IRM3-S150	080619 09:00_SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated	6	2000	490	< 0.014 U	13	730	< 0.59 U	< 0.12 U	49 J		< 0.36 U
Football Field	SSHS-IRM3-S156A	080619 09:00_SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated	13	4700	340	< 0.011 U	12		< 0.51 U	< 0.1 U	170 J		< 0.32 U
Football Field	SSHS-IRM3-S156B	080619 09:00_SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated	12	2600	380	< 0.013 U	18		< 0.56 U	< 0.11 U	350 J		< 0.35 U
Football Field	SSHS-IRM3-S166	080619 09:00_SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated	11	3400	480	< 0.015 U	17	730	< 0.57 U	< 0.12 U	54 J		< 0.35 U
Football Field	SSHS-IRM3-S167	080619 09:00_SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated	10	2800	230	< 0.015 U	12	690	< 0.53 U	< 0.11 U	69 J		< 0.33 U
Football Field	SSHS-IRM3-S169	080619 09:00_SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated	6.4	2800	330	< 0.015 U	11	650	< 0.53 U	< 0.11 U	49 J		< 0.33 U
Football Field	SSHS-IRM3-S170	080619 09:00_SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated	8.6	3200	350	< 0.014 U	13	790	< 0.58 U	< 0.12 U	58 J		< 0.36 U
Football Field	SSHS-IRM3-S172	080619 09:00_SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated	41	4100	510	0.015 J	18	780	< 0.55 U	< 0.11 U	220 J		< 0.34 U
Football Field	SSHS-IRM3-S174	080619 09:00_SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated	29	2400	660	< 0.014 U	18		< 0.51 U	< 0.1 U	83 J		< 0.32 U
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated	7.1	3200	270	< 0.021 U	130	500	< 0.47 U	< 0.096 U	< 55 U		< 0.29 U
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated	27	5200	430	0.13	66	830	< 0.48 U	< 0.098 U	82 J		< 0.30 U
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated	39	6900	570	< 0.020 U	22	610	0.69 J	< 0.084 U	86 J		< 0.26 U
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated	6.5	2600	150	< 0.022 U	17	640	< 0.48 U	< 0.097 U	< 56 U		< 0.30 U
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated	7.5	4800	380	< 0.021 U	13	470	0.71 J	< 0.094 U	64 J		< 0.29 U
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated	11	4300	480	< 0.020 U	20	950	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated	24	5200	470	< 0.019 U	21	700	< 0.51 U	< 0.10 U	140 J		< 0.32 U
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated	11	4500	450	< 0.021 U	46	630	< 0.55 U	< 0.11 U	80 J		< 0.34 U
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated	11	6200	460	< 0.021 U	23	950	< 0.45 U	< 0.092 U	81 J		< 0.28 U
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated	16	11000	410	0.016 J	35	690	< 0.48 U	< 0.097 U	130 J		< 0.30 U
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated	12	1900	660	< 0.024 U	14	660	< 0.49 U	< 0.085 U	< 66 U		4.1
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated	8.8	4000	480	< 0.019 U	19	610	< 0.42 U	< 0.073 U	< 56 U		2.8
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated	11	7900	760	< 0.017 U	14	560	< 0.39 U	< 0.068 U	76 J		4.8
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated	20	4200	420	0.021 J	16	560	< 0.46 U	< 0.079 U	< 61 U		2.6
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated	8.8	4300	650	< 0.021 U	16	620	< 0.51 U	< 0.088 U	< 68 U		3.6
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated	7.0	4000	340	< 0.017 U	17	550	< 0.36 U	< 0.063 U	< 49 U		1.9
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated	6.7	3900	270	< 0.019 U	13	510	< 0.36 U	< 0.063 U	< 49 U		1.5
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated	13	1500	95	< 0.020 U	14	580	< 0.52 U	< 0.090 U	98 J		0.51 J
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	41	5000	480	< 0.018 U	34	860	< 0.45 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated	100 T	4300	500	< 0.020 U	39	530	< 0.46 U	< 0.079 U	160 J		< 0.39 U
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated	25	5900	310	< 0.021 U	89	490 J	< 0.53 U	< 0.091 U	90 J		< 0.45 U
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated	44	3600	460	0.029 J	51	470 J	< 0.50 U	< 0.086 U	110 J		< 0.43 U
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated	13	2000	390	< 0.023 U	49	370 J	< 0.45 U	< 0.077 U	73 J		< 0.38 U
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated	360	6500	540	0.027 J	62	680	< 0.56 U	< 0.096 U	110 J		< 0.47 U
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated	130	6200	570	0.028 J	42	900	< 0.48 U	< 0.083 U	200 J		< 0.41 U
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated	6.0	4800	360	< 0.018 U	31	480	< 0.45 U	< 0.077 U	61 J		< 0.38 U
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated	5.8	4300	290	< 0.018 U	68	390 J	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	21	6100	370	< 0.022 U	74	570	< 0.46 U	< 0.079 U	< 62 U		< 0.39 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated	8.4	9200	330	< 0.022 U	57	720	< 0.52 U	< 0.11 U	100 J		< 0.32 U
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	12	13000	450	< 0.019 U	21	610	< 0.53 U	< 0.11 U	87 J		< 0.33 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated	6.5	9900	360	< 0.021 U	14	770	< 0.56 U	< 0.11 U	88 J		< 0.35 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated	10	2500	440	< 0.022 U	16	840	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated	13	3400	350	< 0.019 U	21	1100	< 0.52 U	< 0.11 U	83 J		< 0.32 U
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated	6.4	3400	180	< 0.023 U	8.9	550	< 0.55 U	< 0.11 U	70 J		< 0.34 U
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated	10	7600	910	< 0.025 U	19	800	< 0.60 U	< 0.12 U	70 J		< 0.37 U
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated	23	2500	650	0.043	23	940	< 0.52 U	< 0.11 U	120 J		< 0.32 U
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated	13	4000	2300	< 0.022 U	24	1000	< 0.60 U	< 0.12 U	< 71 U		< 0.38 U
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated	15	3500	610	< 0.020 U	18	880	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated	5.8	2600	420	< 0.018 U	12	530	< 0.51 U	< 0.10 U	130 J		< 0.31 U
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated	6.9	1900	270	< 0.023 U	11	450	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated	11	4400 T	300 T	< 0.020 U	16 T	470	< 0.35 U	< 0.072 U	63 J		< 0.22 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	37	5000	400	0.050	52	750	< 0.40 U	< 0.083 U	77 J		< 0.25 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	33	5900	360	0.021 J	100	780	0.54 J	< 0.10 U	110 J		< 0.31 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated	13	4100	320	0.032 J	18	540	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated	7.9	8100	320	0.027 J	12	470 J	< 0.49 U	< 0.084 U	70 J		< 0.41 U
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated	7.4	2900	190	< 0.019 U	180	490 J	< 0.54 U	< 0.093 U	< 72 U		0.74 J
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated											
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated	6.0	2400	230	0.025 J	240	450 J	< 0.50 U	0.10 J	< 66 U		< 0.42 U
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated											
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	56	2500	520	0.038	36	590	< 0.49 U	< 0.099 U	< 57 U		0.36 J
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	10	2000	340	< 0.021 U	14	550	< 0.51 U	< 0.10 U	< 59 U		0.34 BJ
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	9.9	3200	530	< 0.021 U	14	470	< 0.36 U	< 0.074 U	< 43 U		0.35 BJ
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	99	3800	420	0.096	56	650	< 0.49 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	47	3400	400	0.054	33	600	< 0.56 U	< 0.11 U	< 65 U		0.39 BJ
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	85	2600	520	0.15	25	580	< 0.49 U	< 0.10 U	57 J		0.34 J
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	53	2200	450	0.10	20	520	< 0.50 U	< 0.10 U	< 58 U		0.44 J
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	120	2200	420	0.13	20	620	< 0.49 U	< 0.10 U	69 J		0.45 J

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-IRM3-S180	073019 09:00 SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated		10	55
Football Field	SSHS-IRM3-S181	073019 09:00 SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated		11	67
Football Field	SSHS-IRM3-S182	073019 09:00 SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated		10	51
Football Field	SSHS-IRM3-S183	073019 09:00 SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated		12	64
Football Field	SSHS-IRM3-B024	073119 09:00 SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated		10	61
Football Field	SSHS-IRM3-S201	080219 09:00 SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated		11	65
Football Field	SSHS-IRM3-MH1DA	080319 09:30 SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated		8.4	62
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated		< 7.8 U	120
Football Field	SSHS-IRM3-S150	080619 09:00 SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated		10	56
Football Field	SSHS-IRM3-S156A	080619 09:00 SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated		9.5	47
Football Field	SSHS-IRM3-S156B	080619 09:00 SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated		12	58
Football Field	SSHS-IRM3-S166	080619 09:00 SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated		13	67
Football Field	SSHS-IRM3-S167	080619 09:00 SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated		9.7	56
Football Field	SSHS-IRM3-S169	080619 09:00 SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated		9.1	87
Football Field	SSHS-IRM3-S170	080619 09:00 SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated		11	59
Football Field	SSHS-IRM3-S172	080619 09:00 SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated		13	73
Football Field	SSHS-IRM3-S174	080619 09:00 SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated		11	68
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated		9.1	70
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated		13	76
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated		9.5	66
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated		10	66
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated		7.3	42
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated		13	59
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated		12	62
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated		10	58
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated		14	72
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated		12	62
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated		8.5	48
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated		11	74
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated		9.2	66
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated		10	89
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated		10	80
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated		9.1	69
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated		8.8 B	63
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated		8.3	27
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated		12	64
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated		10	64
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated		7.6	62
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated		10	66
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated		6.2	46
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated		12	75
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated		26	79
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated		8.2	56
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated		7.0	47
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated		9.8	69
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated		7.6	48
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated		7.4	35
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated		8.9	49 J-
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated		13	69
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated		13	53
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated		6.9	38
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated		12	64
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated		14	64
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated		14	87
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated		12	61
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated		8.5	45
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated		7.4	38
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated		8.4	48 T
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated		11	58
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated		9.1	59
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated		9.0	62
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated		8.0	55
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated		11	140
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated			
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated		7.7	180
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated			
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated		12	220
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated		9.9	51
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated		8.6	53
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated		14	130
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated		11	83
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated		16	140
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated		14	92
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated		18	130

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	7600	7.7	6.8	84	0.35 J	0.17 J	4600	12		6.1	110	21000
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	5100	< 0.28 U	4.0	32	0.20 J	< 0.029 U	830	6.4		4.9	23	8200 T
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	6600	3.1	7.0	44	0.32	< 0.029 U	890	15		7.5	540	14000
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated	3500	0.070 J	3.8	35	0.20	0.78	12000	5.8 B		4.2 B	36	8900
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated	5600	0.21	11	51	0.31	0.20	7700	8.6 B		6.1 B	29	15000
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated	5700	0.25	12	70	0.33	0.40	4400	11 B		5.5 B	43	15000
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated	4800	0.12 J	7.4	44	0.24	0.14	37000	10 B		4.5 B	24	13000
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated	6000	< 0.38 UT	5.5	49	0.22 J	0.76	8000 T	7.6		5.8	39	14000 T
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	4000	< 0.034 U	2.5	20	0.12 J	0.045 J	42000	4.5		3.3 J	11	9000
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated	3900	< 0.29 U	2.8	34	0.14 J	0.058 J	32000	4.7		3.6 J	16	9100
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated	3400	< 0.23 U	2.9	31	0.13 J	0.038 J	21000	4.6		3.1 J	18	7900
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated	4200	< 0.27 U	3.3	32	0.16 J	0.059 J	45000	7.5		3.9 J	22	9300
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated	3700	< 0.28 U	3.4	41	0.14 J	0.059 J	37000	4.7		3.7 J	27	8400
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	7800	0.3 J	5.1	47	0.27 J	0.037 J	43000	12		6.5	23	16000
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	6600	< 0.034 U	6.8	67	0.25 J	0.06 J	15000	10		5.8	24	17000
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated	3200	< 0.31 U	2.9	18	0.13 J	0.098 J	52000	6.4		3.2	40	7200
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated	4900	< 0.29 U	4.4	24	0.20 J	0.12 J	28000	8.5		5.1	71	11000
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated	3700 T	< 0.30 UT	3.5	36	0.14 J	0.16 J	40000 T	5.6		3.7	36	8600
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated	2900	< 0.34 U	2.4	32	0.12 J	0.062 J	27000	5.4		3.0	28	6600
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			8.8	163	< 0.61 U	< 0.61 U		13.3			64.7	
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	4700	< 0.034 U	3.4	34	0.16 J	0.064 J	33000	8.7		3.9 J	21	11000
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	8400	< 0.39 U	10	81	0.39 J	0.17 J	25000	13		7.6	55	20000
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	8800	< 0.38 U	5.4	70	0.38 J	0.1 J	7300	12		7.2	25	17000
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated	7700	< 0.41 U	6.5	57	0.37 J	0.081 J	26000	11		6.7	27	18000
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated	12000	< 0.39 U	7.1	110	0.47	0.16 J	24000	15		7.5	31	20000
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated	13000	< 0.4 U	6	59	0.48	< 0.043 U	1300	14		8.6	17	21000
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	7400	0.48 J	6.5	97	0.37 J	0.14 J	21000	21		6.4	39	17000
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated	7200	1.1 J	9.3	90	0.45 J	0.14 J	12000	12		6.3	55	18000
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	7600	0.53 J	8.2	120	0.49	0.12 J	34000	9.2		5.1 J	52	14000
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated	13000	0.75 J	8.1	60	0.58	0.064 J	7700	17		12	35	29000
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	6400	< 0.4 U	7	87	0.34 J	0.086 J	9200	12		6.5	46	31000
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated	9700	< 0.38 U	7.5	64	0.45	0.09 J	8200	13		7.7	29	20000
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated	10000	0.63 J	8.9	75	0.46	0.082 J	9300	14		8.4	35	22000
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated	10000	< 0.41 U	7.8	120	0.47 J	< 0.044 U	7700	15		8.9	33	22000
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated	9600	0.6 J	8.7	190	0.42 J	< 0.042 U	12000	21		8.6	88	33000
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	9400	0.7 J	6.1	96	0.4 J	0.17 J	12000	14		7.5	99	23000
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated	7400	0.62 J	6.9	79	0.34 J	< 0.041 U	15000	9.6		5.7	33	16000
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated	6500	0.69 J	7.3	130	0.41 J	< 0.044 U	26000	11		5.6 J	34	22000
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated	11000	0.56 J	5.4	130	0.59	< 0.048 U	2500	15		13	31	25000
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated	7400	1.1	12	190	0.41 J	1.1	14000	48		8.7	170	35000
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated	7200	< 0.38 UJ	7	52	0.29 J	0.12 J	40000	9.6		7.2	29	17000
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated	8100	< 0.29 U	8.2	76	0.37	0.12 J	1700	12		7.0	30	18000
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	9800	3.5	8.3	140	0.44	0.29 J	9700	12		5.8	75	18000
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	6800	< 0.21 U	5.2	78	0.26	0.17 J	69000	12		4.9	31	13000
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	7400	0.47 J	8.4	58	0.34	0.25 J	11000	14		8	690	22000
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	7300	0.92	8.4	47	0.35	0.17 J	4000	11		6.6	30	18000
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	7800	0.67 J	6.8	66	0.32 J	0.16 J	22000	12		5.9	52	17000
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated	10000	0.47 J	8.2	110	0.43 J	0.12 J	13000	24		7.8	36	24000
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated	8200	0.58 J	6.7	170	0.37	0.19 J	11000	18		6.8	69	21000
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated	2500	0.53 J	26	93	0.48 J	0.30 J	2600	13		4.5	47	21000
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated	7300	1.7	9.7	210	0.44	0.76	14000	24		7.1	300	23000
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated	7300	9.5	10	500	0.46	1.4	24000	55		8.4	480	36000
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	8400	1.9	9.0	200	0.41 J	0.34 J	23000	15		6.5	66	22000
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated	6300	< 0.28 U	5.1	37	0.27 J	0.15 J	29000	12		5.1	20	17000
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated	9300	0.98	8.0	94	0.47	0.21 J	13000	13		6.7	59	20000
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated	13000	1.0	9.0 T	110	0.41	0.33 J	2600	16		7.5	76	25000
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated	12000	7.1	7.7 T	130	0.45	0.17 J	9300	15		7.7	45	24000
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated	10000	< 0.38 U	11	420	0.55	0.21 J	23000	12		7.8	49	21000
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated	4600	14	21	160	0.54	2.5	3500	75		8.3	220	240000
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated	9500	12	11	230	0.49	0.47	8100	15		9.7	570	26000
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated	4800	0.81 JT	13	240 T	0.51	0.33 J	21000 T	20		5.9	140	28000
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated	9700	38	15	250	0.58	0.82	13000	14		12	790	28000
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated	8200	3.4	15	150	0.64	0.77	9100	16		8.1	92	27000
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated	12000	0.48 J	4.0	170	0.42	0.069 J	1800	11		5.6	15	16000
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated	2600	2.7	7.8	82	0.28 J	0.14 J	5800	9.0		5.1 J	45	28000
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated	5500	0.84	6.5	55	0.29 J	0.20 J	6700	11		5.2	91	21000
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated	7900	0.88	8.5	120	0.57	0.21 J	22000	13		7.1	55	21000
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated	2900	1.1	7.4	80	0.29 J	0.12 J	2400	8.0		4.1 J	64	30000
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated	9700	5.7	7.6	120	0.44	0.27 J	13000	16		8.1	130	22000
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated	8000	0.94 J	7.1	210	0.41	0.42 J	36000	14		7.2	80	21000
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated	5200	1.5	9.2	210	0.30 J	0.26 J	5800	25		6.2	66	28000 B
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated	8400	3.9	8.1	290	0.40 J	0.49 J	40000	31		6.6	81	25000
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated	8200	2.7 T	14	1100	0.54	0.52 J	9000 T	30 T		8.6	260 T	34000
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated	6000	3.7	19	110	0.63	0.21 J	5400	13		8.3	71	35000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	110	2200	400	0.12	20	670	< 0.53 U	< 0.11 U	67 J		0.36 J
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	5.2	1700	140 B	< 0.022 U	18	640	< 0.42 U	< 0.085 U	49 J		< 0.26 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	100	2100	460 B	0.17	140	910	< 0.42 U	0.25 J	50 J		< 0.26 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated	14	2600	220	< 0.022 U	13	420	< 0.083 U	0.32	48		0.070
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated	17	3100	540	0.032 J	15	660	0.10 J	0.060 J	66		0.096
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated	22	2500	580	0.028 J	16	660	0.13 J	1.0	45		0.11
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated	10	7400	570	0.020 J	19	500	< 0.088 U	0.029 J	66		0.054 J
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated	11	3100	530 T	0.042 J	22	470 J	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	3.8	3900	210	< 0.034 U	16	320 J	0.47 J	< 0.034 U	81 J		< 0.034 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated	6.5	2900	320	< 0.019 U	11	310 J	< 0.44 U	< 0.090 U	< 51 UT		< 0.27 U
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated	7.0	2400	220	< 0.018 U	9.0	280 J	< 0.35 U	< 0.072 U	< 41 UT		< 0.22 U
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated	6.8	6600	340	< 0.022 U	13	360 J	0.41 J	< 0.084 U	< 48 UT		< 0.26 U
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated	4.9	3000	270	< 0.022 U	31	310 J	0.43 J	< 0.085 U	< 49 UT		< 0.26 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	16	9400	420	< 0.034 U	17	790	0.53 J	< 0.034 U	110 J		< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	15	5600	940	< 0.034 U	15	780	< 0.034 U	< 0.034 U	67 J		< 0.034 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated	5.9	4700	200	< 0.020 U	110	440	< 0.40 U	< 0.070 U	64 J		< 0.34 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated	6.8	7700	240	< 0.017 U	190	510	< 0.37 U	< 0.064 U	59 J		< 0.32 U
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated	6.1	4800	380 T	< 0.020 U	21	480	< 0.39 U	< 0.068 U	< 53 U		< 0.34 U
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated	3.4	2600	250	< 0.018 U	12	460 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	74.1			< 0.06 U	114		< 0.6 U	< 1.22 U			
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	6.5	13000	370	< 0.034 U	14	620	< 0.034 U	< 0.034 U	84 J		< 0.034 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	80	3800	430	0.18	24		< 0.59 U	< 0.12 U	140 J		< 0.24 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	63	3100	360	0.037	22		< 0.58 U	< 0.12 U	77 J		< 0.23 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated	38	3400	410	0.089	16	680	< 0.62 U	< 0.13 U	65 J		< 0.25 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated	56	3900	530	0.25	22	1000	< 0.59 U	< 0.12 U	370 J		< 0.24 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated	11	3100	240	0.18	18		< 0.61 U	< 0.12 U	84 J		< 0.25 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	40	3300	380	0.53	18	640	< 0.56 U	13	75 J		< 0.23 U
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated	64	2500	370	0.23	17		0.88 J	< 0.12 U	140 J		< 0.25 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	69	2400	500	0.11	14		1.2	< 0.12 U	170 J		< 0.24 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated	57	5600	400	0.19	29		0.62 J	< 0.12 U	74 J		< 0.24 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated	53	2100	430	0.15	19		1.4	< 0.12 U	97 J		< 0.24 U
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.46	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated	28	2900	340	0.073	18		< 0.58 U	< 0.12 U	65 J		< 0.24 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated	39	3100	490	0.065	19		< 0.57 U	< 0.12 U	79 J		< 0.23 U
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated	43	3100	550	0.34	23	880	< 0.62 U	< 0.13 U	95 J		0.47 J
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated	280	3400	580	0.25	32	760	0.83 J	< 0.12 U	100 J		0.36 J
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	74	3100	470	0.57	24	730	< 0.58 U	< 0.12 U	90 J		< 0.24 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated	360	4400	360	0.076	13	690	< 0.58 U	< 0.12 U	75 J		< 0.24 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated	48	1600	290	0.16	16	830	0.78 J	< 0.13 U	310 J		0.25 J
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated	20	2000	710	0.032 J	18		0.8 J,^	< 0.14 U	56 J		0.57 J
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated	330	4000	520	0.3	140	650	1.1	< 0.12 U	82 J		< 0.23 U
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated	14	6800 J	330	< 0.015 U	18	690	< 0.58 U	< 0.12 U	110 J		< 0.36 U
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated	19	2300	430	< 0.023 U	20	820	< 0.44 U	< 0.089 U	< 51 U		< 0.27 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	76	2000	470	0.039	19	780	0.98	< 0.098 U	1100		< 0.3 U
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	27	7800	280	0.036	17	670	0.97	< 0.066 U	110 J		< 0.2 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	140	4200	570	0.044	25	680	0.4 J	< 0.079 U	76 J		< 0.24 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	22	2300	350	0.043	18	640	0.41 J	< 0.065 U	210 J		< 0.2 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	55	3000	400	0.041	33	630	0.7 J	< 0.097 U	200 J		< 0.3 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated	100	4300	550	0.077	38	930	< 0.60 U	< 0.12 U	89 J		< 0.38 U
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated	220	3400	400	0.030	88	700	0.57 J	< 0.093 U	89 J		< 0.28 U
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated	48	290 J	86	0.14 J	250	990	1.7 J	< 0.10 U	160 J		2.1 J
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated	220	2100	350	0.045	250	800	1.1	< 0.12 U	130 J		< 0.36 U
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated	500	6000	590	0.24	380	830	0.91 J	0.41 J	240 J		< 0.36 U
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	120	3000	420	0.13	34	840	< 0.56 U	< 0.11 U	130 J		< 0.35 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated	18	4200	270	0.021 J	17 B	800	< 0.43 U	< 0.087 U	81 J		< 0.27 U
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated	55	2700	430	0.13	28	750	< 0.47 U	< 0.096 U	96 J		0.69 J
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated	50	2600	320	0.028 J	26	950	< 0.51 U	< 0.10 U	96 J		< 0.32 U
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated	110	2600	500	0.11	33	820	< 0.58 U	< 0.12 U	100 J		< 0.36 U
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated	87	3100	380	0.036	26	830	< 0.58 U	< 0.12 U	130 J		< 0.36 U
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated	460	670	540	0.15	74	340 J	9.3	0.38 J	< 79 U		0.45 J
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated	480	3000	500	1.2	140	900	1.1	0.10 J	89 J		< 0.30 U
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated	430 T	6900 T	270	0.13	63	570	1.5	< 0.097 U	110 J		< 0.30 U
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated	600	2900	750	0.70	290	950	1.5	0.22 J	100 J		< 0.34 U
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated	180	2400	390	0.11	53	730	0.56 J	< 0.10 U	88 J		< 0.32 U
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated	13	2200	720	0.034	14	690	< 0.44 U	< 0.091 U	190 J		< 0.28 U
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated	180	510 J	77	0.11	17	730	1.3	< 0.12 U	230 J		< 0.36 U
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated	75	2800	360	0.29	21	430	0.41 J	< 0.083 U	55 J		< 0.25 U
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated	91	2500	300	0.33	27	870	0.57 J	< 0.091 U	160 J		< 0.28 U
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated	330	510 J	78	0.10	14	530	0.93 J	< 0.11 U	210 J		< 0.33 U
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated	100	3800	410	0.082	150	890	0.51 J	< 0.097 U	190 J		< 0.30 U
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated	78	3100	290	0.24	110	1000	1.0	0.17 J	240 J		< 0.30 U
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated	100	1600	260	0.074	92	570	1.2	< 0.10 U	93 J		< 0.32 U
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated	160	6000	320	0.11	70	720	0.87 J	< 0.11 U	180 J		< 0.34 U
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated	150 T	2700	420	0.16	45 T	890	1.3	< 0.12 U	150 J		< 0.35 U
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated	76	1600	360	0.11	42	560	1.2	< 0.11 U	68 J		< 0.33 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated		16	120
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated		7.9	60
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated		14	220
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated		7.5	180
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated		22	100
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated		12	140
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated		10	60
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated		9.7	250 T
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated		6.9	61
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated		5.8	51
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated		4.9	40
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated		7.0	42
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated		5.5	310
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated		11	54
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated		12	56
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated		5.1	160
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated		8.0	270
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated		5.9	51
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated		5.2	40
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			161
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated		8.4	39
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated		14	120
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated		15	61
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated		13	89
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated		18	90
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated		18	56
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated		15	73
Football Field	SSHS-B2128	072618 08:50_PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated		16	87
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated		14	68
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated		16	89
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated		16	62
Football Field	SSHS-B2216	072618 08:50_PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated		16	63
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated		20	83
Football Field	SSHS-B2025	072718 09:00_PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated		15	96
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated		21	320
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated		16	100
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated		14	58
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated		18	49
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated		22	56
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated		15	380
Football Field	SSHS-IRM3-S058D	080919 09:00_SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated		11	64 J+
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated		14	78
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated		16	200
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated		13	69
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated		13	200
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated		14	100
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated		13	80
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated		16	88
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated		13	100
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated		18	25
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated		16	250
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated		20	560
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated		15	170
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated		16	60
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated		17	100
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated		21	220
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated		18	95
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated		16	87
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated		39	1100
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated		20	270
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated		17	150
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated		21	390
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated		17	320
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated		16	49
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated		12	91
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated		12	88
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated		14	140
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated		12	100
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated		18	170
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated		18	210
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated		18	140
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated		18	190
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated		23	250 T
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated		18	120

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated	9400	0.42 J	4.5	84	0.42	0.10 J	3900	10		6.2	24	15000
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated	9800	0.55 J	12	110	0.49	0.27 J	7700	17		7.7	59	25000
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated	9400	< 0.30 U	8.1	85	0.46	0.18 J	3400	15		7.7	19	18000
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated	5600	< 0.32 U	5.1	52	0.28 J	0.093 J	23000	7.2		4.7	26	14000
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated	6900	0.68 J	6.9	120	0.34 J	0.24 J	32000	12		5.4	50	24000
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated	8100	< 0.37 U	5.2	67	0.34 J	0.14 J	16000	11		5.2 J	31	17000
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated	2000	< 0.36 U	5.5	77	0.41 J	< 0.039 U	2200	5.4		4.1 J	23	17000
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated	8400	< 0.32 U	6.6	86	0.36 J	0.15 J	5000	10		6.2	30	16000
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated	8800	< 0.31 U	5.6	93	0.44	0.21 J	5800	11		6.9	21	17000
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated	10000	< 0.41 U	4.4	160	0.40 J	< 0.044 U	2300	10		6.6	12	15000
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated	6700	2.3 T	6.5	120 T	0.34 J	0.17 J	6700 T	12		5.7	290 T	16000
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated	4500	< 0.32 U	7.7	50	0.43	0.098 J	18000	7.0		5.9	38	20000
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated	10000	< 0.32 U	4.4	120	0.41	0.057 J	1800	11		6.2	12	16000
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated	7300	< 0.39 U	6.1	76	0.37 J	0.16 J	7300	9.8		5.9	36	15000
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated	7600	1.2	6.3	81	0.39 J	0.11 J	8200	11		6.3	35	18000
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated	5100	< 0.31 U	7.3	49	0.26 J	0.12 J	18000	7.4		4.8	24	14000
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated	7900	8.1	7.0	96	0.35 J	0.22 J	6700	12		6.7	90	22000
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated	9000	0.74 J	10	88	0.44	0.41 J	2500	19		8.1	79	23000
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated	13000	< 0.36 U	13	100	0.65	0.10 J	9800	17		13	29	30000
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated	9900	< 0.34 U	6.6	100	0.50	0.19 J	3100	13 B		8.6	22	19000
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated	7400	0.74 J	5.7	73	0.34 J	0.41 J	7500	12		6.2	100	17000
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated	10000	< 0.40 UT	6.7	120	0.56	0.16 J	3000 T	13 B		9.4	15	20000
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated	7100	1.2 J	9.9	92	0.47 J	0.25 J	3900	20		8.3	61	33000
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated	6400	0.97 J	9.8	67	0.32 J	0.17 J	13000	10		7.4	45	25000
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated	3000	< 0.43 U	12	230	0.73	0.13 J	1800	13		7.2	180	29000
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated	4900	1.0 J	14	750	0.41 J	0.84	16000	57		6.1	320	53000
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated	8700	< 0.38 U	7.1	57	0.42 J	< 0.050 U	2400	9.5		7.6	16	21000
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated	11000	< 0.37 U	9.5	85	0.43 J	< 0.050 U	4100	13		11	15	24000
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated	13000	< 0.34 U	5.5	79	0.42 J	< 0.046 U	1200	13		9.0	10	19000
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated	7700	< 0.38 UT	6.6	66	0.39 J	0.10 J	6900 T	10		7.1	26	18000
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated	10000	< 0.30 UT	6.2	54	0.42	0.041 J	2700 T	12		8.5	17	18000
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated	9200	0.49 J	6.4	70	0.39 J	0.081 J	1700	13		8.0	57	21000
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated	8300	0.85 J	7.8	200	0.38 J	0.25 J	25000	13 B		10	61	41000 B
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated	7500	< 0.30 U	7.9	230	0.26 J	0.42	46000	17 B		7.1	82	22000 B
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated	5000 T	0.93 J	9.2	260 B	0.48 J	0.43 J	27000	13		5.9	99	30000 B
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated	4800 T	7.4 T	13	750 T	0.58	0.41 J	1800	23		6.1	800 T	28000 T
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated	7000 T	1.3 JT	7.9	450 T	0.40 J	0.39 J	18000 T	21		7.4	180	26000 T
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated	8500 T	1.2 J	9.5	200	0.41 J	0.52	20000	29		8.7	380	34000
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated	4600 T	< 0.35 U	5.2	110	0.23 J	0.41 J	10000	13		3.9	110	15000
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated	7600	0.88 J	3.1	71	0.29 J	0.21 J	15000	13		4.9 J	74	17000
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated	8000	< 0.34 U	6.5	69	0.31 J	0.075 J	480 J	16		5.8	18	17000
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated	8900	5.2	9.7	140	0.38 J	0.67	45000	13		6.0 J	130	38000
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated	4900	1.5 JT	21	750	0.38 J	0.46 J	5500	45		6.6	240 T	40000
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated	5900	0.42 J	9.9	370	0.43 J	0.48	12000	23		6.3	310	26000
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated	8000	2.7	10	100	0.41	0.39 J	9300	22		9.0	450	33000
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated	6200	1.4 J	13	220	0.39 J	0.44 J	12000	23 B		7.1	440	36000
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated	5500	1.7 J	12	220	0.39 J	0.52	9900	26 B		6.9	250	43000
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated	8100	18	12	200	0.44 J	0.66	14000	29 B		9.7	410	33000
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated	6700	3.5 J	13	1100	0.44 J	0.80 J	11000	62		8.9	300	67000
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated	7000	2.1	9.3	850	0.35 J	0.68	14000	37		8.5	350	26000
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated	9000	1.9 J	7.8	120	0.38 J	0.39 J	5600	20		7.6	230	23000
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated	8200	3.2	9.2	170	0.42 J	0.35 J	7000	24		7.9	170	23000
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated	6500	< 1.7 U	18	350	0.46 J	0.94 J	2500	29 B		7.9	1100	67000
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated	11000 T	< 0.27 U	11	82	0.52	0.044 J	4200	13		11	20	26000
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated	11000	0.81 J	13	82	0.52	0.23 J	6200	14		12	20	26000
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	7800	35	11	110	0.39 J	< 0.038 U	10000	15		7.7	170	28000
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	8200	7.6	5.5	46	0.33 J	0.037 J	1600	9.8		6.2	84	16000
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated	3700	0.99	4.4	170	0.16 J	< 0.035 U	120000	6.7		2.5 J	17	16000
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated	9900	0.68	7.1	78	0.48	0.14	8700	13 B		7.5 B	53	22000
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated	10000	0.44 J	10	99	0.47 J	0.14 J	16000	22		10	87	24000
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated	11000	< 0.33 U	12	83	0.52	< 0.043 U	5000	13		12	19	26000
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated	6900	3.7	66	170	0.83	0.22 J	8700	24		10	170	26000 B
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated	10000	1.1 T	7.8	110 T	0.45 T	0.079 J	15000 T	15 T		8.4	45 T	22000 B
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated	7800	2.0	15	90	0.44 J	0.42 J	5600	25		9.4	95	48000 B
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated	7000	0.61 J	4.5	46	0.28 J	< 0.036 U	14000	12		6.5	16	16000
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated	7400	0.69 J	9.2	83	0.39	0.099 J	15000	10		6.6	39	18000
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated	6500	< 0.42 U	6.9	55	0.28 J	0.42 J	32000	55		6.2	43	21000
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated	9600	< 0.41 U	9.1	67	0.41 J	< 0.044 U	33000	12		8.3	31	24000
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	7500	0.65 J	6.8	75	0.41	0.089 J	24000	13		6.5	61	19000
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	6600	0.34 J	4.3	44	0.23 J	0.062 J	21000	8.3		5.6	27	15000
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	9500	< 0.36 U	11	86	0.42	< 0.039 U	8600	12		9.7	30	23000
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	8700	< 0.33 UT	4.9	160	0.43	0.064 J	1500	9.0		5.4	19	14000
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	9700	< 0.034 U	4.4	94	0.35 J	< 0.034 U	5300	11		5.4	15	14000
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	7600	0.54 J	8.2	160	0.41	0.050 J	3900	10		6.4	39	18000

DRAFT

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated	26	1900	490	0.043	14	600	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated	140	3200	430	0.19	33	880	4.6	< 0.12 U	96 J		< 0.37 U
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated	29	2500	440	0.091	19	1200	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated	31	3100	360	0.12	13	490	< 0.49 U	< 0.10 U	57 J		< 0.30 U
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated	91	2100	320	1.3	21	740	0.70 J	< 0.095 U	320 J		< 0.29 U
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated	69	3100	300	0.75 T	14	620	< 0.56 U	< 0.12 U	76 J		< 0.35 U
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated	25	330 J	56	0.14	9.4	460 J	0.81 J	< 0.11 U	67 J		< 0.34 U
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated	73	2500	420	0.18	17	580	< 0.48 U	< 0.099 U	< 57 U		< 0.30 U
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated	35	2700	400	0.78	19	780	< 0.47 U	1.5	< 55 U		< 0.29 U
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated	9.8	2100	380	0.049	13	680	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated	150 T	2200 T	310	0.19	43 T	680	0.45 J	< 0.093 U	130 J		< 0.28 U
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated	19	1300	230	0.11	15	460 J	1.1	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated	45	1900	550	0.19 B	13	620	< 0.49 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated	56	2200	410	2.1 B	20	630	< 0.59 U	< 0.12 U	84 J		< 0.37 U
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated	53	2500	400	0.90 B	48	650	< 0.54 U	< 0.11 U	72 J		< 0.34 U
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated	26	3200	290	0.18	38	570	< 0.48 U	< 0.097 U	100 J		< 0.30 U
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated	93	2500	390	0.13	20	740	0.63 J	< 0.10 U	150 J		< 0.32 U
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated	87	2500	420	0.14	38	640	< 0.51 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated	31	4500	550	0.28 B	33	1400	< 0.54 U	< 0.11 U	80 J		< 0.34 U
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated	25 B	3200	520	0.055 J	22	690	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated	100	2200	400	0.25	22	470 J	< 0.49 U	< 0.084 U	< 65 U		< 0.42 U
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated	11 BT	2900	600	0.024 J	21	800	< 0.53 U	< 0.091 U	< 71 U		< 0.45 U
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated	92	1900	730	0.18	19	600	0.58 J	< 0.083 U	76 J		< 0.41 U
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated	44	3300	370	0.030 J	21	450	0.94 J	< 0.072 U	< 56 U		< 0.71 U
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated	330	330 J	120	0.042 J	32	260 J	< 0.56 U	< 0.097 U	170 J		< 0.48 U
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated	560	1900	530	0.16	270	420 J	1.7 J	0.19 J	140 J		1.3 J
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated	13	2700	300	< 0.021 U	18	820	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated	15	3400	550	< 0.023 U	24	930	< 0.49 U	< 0.084 U	< 65 U		0.46 J
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated	11	2500	480	0.038 J	17	690	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated	42 T	2500 T	390	0.053 J	17	600	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated	18	2700	390	0.033 J	17	630	< 0.39 U	< 0.068 U	< 53 U		< 0.33 U
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated	68	2000	570	0.035 J	18	680	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated	880	3000	490	0.13	35 B	840	< 0.41 U	0.17 J	120 J		0.38 J
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated	130	22000	710	0.12	52 B	570	< 0.39 U	0.17 J	87 J		0.51 J
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated	150	1700	190	0.16	43	930	< 0.52 U	0.16 J	290 J		< 0.44 U
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated	330 T	570	160 T	0.11	150 T	350 J	1.2 J	0.079 J	77 J		< 0.34 U
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated	210	2900	440	0.38 T	180 T	690	0.50 J	0.13 J	190 J		< 0.38 U
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated	190	3300	510	0.045 J	100	730	< 0.44 U	0.091 J	120 J		< 0.37 U
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated	130	1600	240	0.093 J	110	370 J	< 0.46 U	0.48 J	84 J		< 0.39 U
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated	100	2400	360	1.7	17	630	< 0.56 U	< 0.11 U	200 J		< 0.35 U
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated	8.9	2200	340	< 0.023 U	21	530	< 0.51 U	< 0.10 U	< 60 U		< 0.32 U
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated	670	1900	610	0.22	16	740	0.89 J	< 0.14 U	510 J		< 0.42 U
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated	580	1600	300 BT	0.30 T	270 T	560	2.2 B	0.20 J	180 J		< 0.43 U
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated	300	2400	260 B	0.20	210	580	0.74 BJ	0.21 J	100 J		< 0.38 U
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated	160	2700	700	0.20	76	660	1.6	0.071 J	130 J		< 0.32 U
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated	320	2100	340	0.16	73	600	0.94 J	0.16 J	130 J		< 0.42 U
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated	250	2100	460	0.16	100	500	0.62 J	0.24 J	99 J		< 0.40 U
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated	270	2500	610	0.22	170	750	0.95 J	0.17 J	120 J		< 0.41 U
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated	380	1600	850	0.21	300	640	1.3 J	0.35 J	230 J		< 0.91 U
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated	400	2500	610	0.21	290	630	0.73 J	0.29 J	100 J		0.51 J
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated	160	2800	440	0.43	220	720	0.50 J	0.17 J	130 J		< 0.39 U
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated	240	2600	400	0.15	320	700	0.62 J	0.13 J	150 J		< 0.40 U
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated	300	1100	320	0.22	110	480 J	1.5 J	0.11 J	230 J		< 1.9 U
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated	14	3600	520 B	< 0.017 U	24	1100	< 0.35 U	< 0.060 U	46 J		< 0.30 U
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated	13	3700	490	< 0.019 U	24	1300	< 0.48 U	< 0.099 U	< 57 U		1.0 J
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	170	4000	430	0.42	64	770	< 0.53 U	< 0.11 U	85 J		< 0.33 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	58	1800	310	0.034 J	19	530	< 0.51 U	< 0.10 U	< 59 U		< 0.32 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated	21	1100	170	< 0.021 U	8.1	470 J	< 0.50 U	< 0.10 U	1300		< 0.31 U
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated	63	2500	470	0.32	20	1200	0.27 J	0.032 J	130		0.16
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated	88	3600	430	0.085 J	94	1000	< 0.50 U	< 0.086 U	84 J		< 0.42 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated	13	3600	470	< 0.018 U	26	1200	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated	210	1400	630	0.28	35	620	1.6	< 0.11 U	83 J		< 0.34 U
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated	97 T	4300 T	420	0.23 T	42 T	960 T	< 0.47 UT	< 0.096 U	77 J		< 0.29 UT
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated	79	3300	670	0.097	99	770	0.86 J	< 0.13 U	< 71 U		< 0.38 U
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated	11	4800	350	< 0.017 U	15	740	< 0.51 U	< 0.10 U	< 59 U		< 0.32 U
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated	50	3700	420	0.042	20	860	0.62 J	< 0.10 U	< 59 U		< 0.31 U
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated	33	5600	440	0.069	26	620	0.73 J	< 0.13 U	74 J		< 0.39 U
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated	28	7900	460	0.019 J	22	790	< 0.63 U	< 0.13 U	< 74 U		< 0.39 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	56	3500	340	0.059	36	550	< 0.45 U	< 0.091 U	180 J		< 0.28 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	20	5200	330	0.074	16	470 J	0.70 J	< 0.10 U	120 J		< 0.31 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	31	3600	430	< 0.020 U	27	830	< 0.55 U	< 0.11 U	100 J		< 0.34 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	23	1600	430	0.048	12	510	0.64 J	< 0.10 U	440 J		< 0.31 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	17	2400	440	0.095	14	810	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	34	1900	410	0.097	15	470	0.65 J	< 0.070 U	42 J		< 0.21 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated		13	82
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated		18	140
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated		14	88
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated		10	56
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated		13	99
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated		13	82
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated		9.5	14
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated		13	74
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated		13	140
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated		15	46
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated		13	120
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated		12	40
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated		15	46
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated		12	89
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated		15	81
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated		9.8	130
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated		15	140
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated		16	120
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated		19	87
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated		13	75
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated		13	130
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated		13	58
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated		26	99
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated		16	82
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated		14	70
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated		23	440
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated		13	46
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated		14	57
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated		18 B	49
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated		14 B	83 T
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated		15 B	54
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated		19 B	73
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated		14	140
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated		13	230
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated		22 B	220 B
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated		14	350 T
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated		16	200 T
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated		18	260
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated		9.3	130
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated		15	86
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated		11	85
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated		18	120
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated		17	420 T
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated		13	300
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated		18	250
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated		16	260
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated		19	250
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated		22	380
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated		28	420
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated		21	490
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated		17	220
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated		17	210
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated		16 J	520
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated		15	60
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated		16	57
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated		16	310
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated		14	84
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated		8.3	47
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated		20	110
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated		16	120
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated		15	69
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated		25	350
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated		16 T	94 T
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated		21	420
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated		14	77
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated		13	100
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated		11	520
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated		14	78
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated		13	78
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated		9.5	69
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated		13	65
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated		13	50 T
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated		15	58
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated		14	53

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	10000	6.1	8.7	90	0.48	0.083 J	2800	13		6.8	57	20000
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	5900	< 0.36 U	7.0	78	0.34 J	0.051 J	5400	10		5.4	36	16000
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	6600	1.9 JT	11	120	0.51 J	0.24 J	2900	29		8.6	110	32000
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	12000	2.4	6.6	64	0.47	< 0.042 U	1400	13		9.0	22	19000
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	12000	0.90 J	5.6	61	0.42 J	< 0.042 U	1900	12		8.0	15	18000
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	6500	0.77 J	4.7	110	0.27 J	0.085 J	6800	7.8		4.8	65	16000
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	7700	6.0	6.5	87	0.34	0.079 J	2600	11		6.2	82	17000
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	6700	< 0.22 U	4.3	50	0.27	0.063 J	24000	8.2		5.6	26	14000
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	5500	1.3	6.2	84	0.36	0.088 J	5400	8.7		5.4	37	16000
Football Field	ISMP-S636-S3	SSHS-ISMP-DUP1-20211230	SSHS-ISMP-DUP1	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	7700	< 0.31 U	7.6	46	0.32 J	< 0.075 U	1000	9.9		6.8	19	18000
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	11000	< 0.30 U	5.4	61	0.42	< 0.074 U	1100	12		7.1	15	17000
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	6500	0.66	6.6	83	0.34	0.073 J	10000	8.7		5.6	33	16000
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	7000	2.1	13	89	0.45	0.070 J	8500	11		6.0	58	18000
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	7800	< 0.21 U	5.8	54	0.35	< 0.051 U	1200	8.7		7.3	34	16000
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	6200	2.6	7.7	70	0.33	0.30 J	6900	9.7		5.5	66	16000
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	7200	0.25 J	6.5	69	0.31	0.091 J	25000	9.4		5.8	23	16000
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	8000	0.82	7.8	79	0.33	< 0.055 U	11000	18		6.4	20	17000
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	9700	0.89	9.3	69	0.36	0.082 J	5900	11		6.6	19	20000
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	10000	0.60 J	5.8	65	0.44	< 0.059 U	860	12		9.5	25	19000
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	9400	1.4	4.4	74	0.33	0.10 J	1500	17		7.1	410	20000
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	9300	0.53 J	7.8	53	0.39	< 0.056 U	3100	13		8.2	50	19000
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	2800	1.2	4.8	29	0.26 J	< 0.077 U	1400	13		3.5 J	210	31000
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	5800	4.3	13	69	0.39 J	0.13 J	2800	11		7.0	76	25000
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	6200	9.2	9.5	83	0.34 J	0.20 J	7300	12		12	440	43000
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	6500	0.41 J	6.6	49	0.32 J	< 0.083 U	12000	8.9		5.8	30	16000
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	8600	0.56 J	9.1	73	0.42	< 0.074 U	6200	11		8.0	28	20000
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	7400	0.42 J	5.8	61	0.38 J	< 0.076 U	1900	9.7		6.7	38	16000
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	7400	3.0	6.6	28	0.21 J	< 0.059 U	1400	29		4.5	110	18000
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	7700	9.9	13	350	0.45	0.41	13000	13		7.2	140	19000 B
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	4500	4.2	11	42	0.21 J	1.3	34000	16		5.8	970	61000
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	6000	< 0.30 U	6.1	69	0.25 J	0.10 J	29000	9.9		5.9	29	16000
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	7700	< 0.27 U	7.8	66	0.37	< 0.065 U	2400	9.8		8.5	17	19000
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	8400	0.64 JT	7.1 T	90	0.36 T	0.088 JT	13000 T	10 T		7.1 T	24 T	17000
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	5700	< 0.24 U	3.0	34	0.22 J	< 0.058 U	3800	6.5		4.5	11	10000
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	9200	< 0.30 U	5.5	32	0.39 J	< 0.073 U	800	11		7.1	15	18000
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	4300	0.60 J	5.0	55	0.21 J	0.12 J	5500	5.6		3.9	22	11000
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	7300	0.80 J	7.5	74	0.34 J	0.11 J	10000	11		7.0	43	18000
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	6200 B	< 0.30 U	4.9	58	0.27 J	0.11 J	11000	8.3		4.9 J	19	12000
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	3100 B	< 0.31 U	3.9	34	0.21 J	< 0.076 U	6700	6.9		3.1 J	28	8900
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	7600	1.2	7.2	81	0.39 J	0.14 J	11000	11		6.9	37	18000
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	8800	< 0.31 U	5.1	95	0.39 J	0.082 J	1300	9.6		6.2	13	14000
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	8100	0.50 J	7.0	78	0.39 J	0.12 J	3500	10		6.5	41	19000
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	7300	0.60 JT	7.9 T	61 T	0.34 T	< 0.060 UT	6300 T	9.8 T		7.2 T	17 T	17000
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	6000	0.65 J	6.6	64	0.30 J	0.13 J	4400	8.2		5.5	41	17000
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	8400	0.80 J	8.9	69	0.40 J	< 0.079 U	4100	10		7.0	28	20000
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	5900	0.64 JT	8.0	110 T	0.40	0.25 J	16000	11		8.4	49 T	21000
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	8700	0.55 J	7.3	77	0.38 J	0.18 J	4500	12		6.9	27	18000
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	7900	0.80 J	7.9	990	0.33 J	0.95	13000	1300		6.1	61	32000
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	6500	0.40 J	5.6	81	0.27 J	0.33 J	10000	11		6.2	45	18000
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	7800	< 0.28 U	6.4	73	0.35 J	0.17 J	7100	9.6		6.4	19	18000
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	8300	< 0.29 U	7.6	130	0.36 J	0.27 J	6700	32		7.2	29	20000
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	4600	0.73 J	3.8	45	0.22 J	< 0.086 U	19000	8.3		4.0 J	33	11000
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	3700	< 0.34 U	2.6	23	0.13 J	< 0.082 U	72000	4.2		3.5 J	14	9600
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	6700	0.93	6.8	110	0.31 J	0.10 J	17000	9.7		5.6	36	17000
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	5500	2.4	6.0	59	0.27 J	< 0.070 U	7100	8.3		5.2	52	21000
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	4100	1.1	3.2	30	0.14 J	0.064 J	18000	6.9		3.6 J	22	11000
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	5800	0.36 J	4.4	34	0.22 J	< 0.050 U	1900	6.8		4.6	14	13000
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	8200	0.40 J	7.6	60	0.33	< 0.056 U	3900	10		8.2	13	21000
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	4600	< 0.27 U	3.7	30	0.14 J	< 0.066 U	23000	5.9		4.2 J	13	11000
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	4600	0.34 J	5.5	38	0.21 J	0.11 J	62000	6.3		4.8	21	11000
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	6800	0.35 J	5.1	50	0.26 J	0.065 J	55000	8.9		5.9	23	15000
Football Field	SSHS-B2185	072518 09:00 PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated	8600	1.2	7	180	0.44 J	0.21 J	32000	19		6.8	59	21000
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated	9100	< 0.38 U	5.6	97	0.43 J	0.14 J	50000	13		6.6	36	17000
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated	6700	< 0.37 U	5.7	49	0.3 J	0.073 J	2400	17		7.5	54	22000
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated	8700	< 0.39 U	12	90	0.53	0.13 J	1900	12		8.1	47	24000
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated	8600	< 0.38 U	5.6	49	0.37 J	0.058 J	4000	12		7	18	18000
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated	6000	< 0.38 U	5.4	40	0.26 J	0.077 J	5800	11		5.6	20	15000
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated	7400	< 0.39 U	6.4	53	0.35 J	0.15 J	3700	10		7.2	23	17000
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated	10000	< 0.39 U	8.6	55	0.48	0.18 J	1300	13		8.2	220	23000
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated	9400	< 0.37 U	8.9	60	0.43 J	0.1 J	2900	11		10	28	20000
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated	10000	190	8.8	130	0.44 J	0.45 J	11000	12		8.3	370	29000
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated	9100	< 0.39 U	6.2	64	0.39 J	0.071 J	15000	12		7.1	22	17000
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated	9800	1.5	8	77	0.46	0.1 J	6200	20		7.3	34	20000
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated	8400	< 0.37 U	4.2	28	0.35 J	< 0.04 U	1900	11		7.9	15	18000

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	270 B	2000	570	0.24	16	630	1.1	< 0.11 U	< 63 U		< 0.34 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	46 B	1900	280	0.37	18	670	< 0.54 U	< 0.11 U	110 J		< 0.34 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	250	1400	930	0.30	17	730	1.0 J	0.22 J	< 66 U		< 0.42 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	26	2600	540	0.035	18	900	< 0.59 U	< 0.12 U	< 70 U		< 0.37 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	20	2600	390	0.033 J	16	830	< 0.59 U	< 0.12 U	< 69 U		< 0.37 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	120	1900	260	0.46	36	460	0.47 JT	< 0.093 U	< 54 U		< 0.28 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	49	1900	340	0.11	14	490	0.60 J	< 0.064 U	< 37 U		< 0.19 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	8.0	5200	290	0.025 J	15	440	0.46 J	< 0.067 U	41 J		< 0.20 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	52	1600	270	0.45 BT	30	520	0.51 J	< 0.072 U	43 J		< 0.22 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	8.4	2100	330	0.037	17	650	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	11	2300	330	0.061	21	740	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	59	2100	250	0.21	15	500	0.59 J	< 0.069 U	66 J		< 0.19 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	56	1900	290	0.25	15	530	1.9	< 0.072 U	60 J		< 0.20 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	15	1700	450	0.038	16	490	< 0.32 U	< 0.072 U	< 35 U		< 0.20 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	100	1700	400	0.26	15	500	0.67 J	0.26 J	48 J		< 0.19 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	45	4300	300	0.43	20	520	0.71	< 0.069 U	130 J		< 0.19 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	35	2700	250	0.32 T	18	500	0.97	< 0.078 U	46 J		< 0.21 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	40	2100	290	0.19	14	490	< 0.40 U	< 0.091 U	50 J		< 0.25 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	21	2400	620	0.068	16	710	0.52 J	< 0.084 U	< 41 U		< 0.23 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	45	2000	400	0.032	530	530	0.62 J	< 0.077 U	95 J		< 0.21 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	34	2600	340	< 0.022 U	200	710	< 0.35 U	< 0.079 U	67 J		< 0.22 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	47	420 J	110	< 0.022 U	330	330 J	0.67 J	0.20 J	59 J		< 0.30 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	110	1300	410	0.13	14	530	1.5	< 0.11 U	67 J		< 0.30 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	130	2100	430	0.089	530	530	0.93 JT	< 0.098 U	95 J		< 0.27 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	23	2700	350	0.069	13	540 J	0.62 JT	< 0.12 U	< 58 U		< 0.32 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	29	2900	370	0.046	18	720	0.71 JT	< 0.10 U	< 51 U		< 0.28 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	22	1900	320	0.045	15	670	< 0.48 UT	< 0.11 U	< 53 U		< 0.29 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	18	1900	120	0.051	470	590	0.50 J	< 0.083 U	47 J		< 0.23 U
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	320	2600	330	0.097	280	710	1.2	< 0.086 U	170 J		< 0.23 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	65	3100	470	0.27	35	390 J	1.2	< 0.088 U	72 J		0.31 J
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	12	5000	360	0.10	99	520	0.61 J	< 0.10 U	52 J		< 0.28 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	9.0	2600	420	0.027	18	780	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	42 T	2800 T	380	0.61 T	20 T	710 T	< 0.38 UT	< 0.085 UT	74 JT		< 0.23 UT
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	8.1	1600	190	0.049	9.8	380 J	< 0.36 U	< 0.082 U	57 J		< 0.22 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	7.9	2600	220	0.021 J	16	650	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	50	2100	610	0.19	12	340 J	< 0.34 U	< 0.078 U	< 38 U		< 0.21 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	63	3100	420	0.29	22	690	0.71 J	< 0.096 U	52 J		< 0.26 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	20	2700	340	0.078	13	560	0.50 J	< 0.10 U	< 51 U		< 0.29 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	20	1300	150	0.14	9.0	470 J	0.82 J	< 0.11 U	97 J		< 0.29 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	120	3000	440	0.10	30	740	0.67 JBT	< 0.11 U	70 J		< 0.30 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	58	1900	490	0.053	13	510 J	0.72 JBT	< 0.11 U	< 53 U		< 0.29 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	45	2000	430	1.8	17	590	0.84 JBT	< 0.10 U	< 51 U		< 0.29 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	16 T	2400 T	340	0.099	20 T	670 T	< 0.38 UT	< 0.085 UT	< 42 UT		0.29 JT
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	60	1900	540	0.085	16	500	0.95 J	< 0.10 U	< 50 U		0.37 J
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	55	2400	390	0.88	23	700	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	100 T	1900	330	0.044	37	710	0.83 J	< 0.10 U	130 J		0.35 J
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	35	2700	480	< 0.019 U	26	720	0.49 J	< 0.10 U	< 51 U		< 0.28 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	750	2300	470	0.059	80	750	0.86 J	< 0.093 U	380 J		0.67 J
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	49	3900	320	0.27	300	680	< 0.43 U	< 0.096 U	87 J		< 0.26 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	18	2900	510	< 0.021 U	17	640	< 0.43 U	< 0.096 U	< 47 U		0.26 J
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	85	3400	470	0.026	27	850	< 0.44 U	< 0.10 U	68 J		< 0.27 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	32	5200	270	0.048	14	330 J	0.54 J	< 0.12 U	260 J		< 0.33 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	8.0	3200	240	0.023 J	9.1	250 J	1.4	< 0.12 U	100 J		< 0.32 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	130	3500	320	0.038	28	640	< 0.42 U	< 0.094 U	170 J		< 0.26 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	1300	1800	350	0.049	17	410 J	0.65 J	< 0.10 U	130 J		< 0.27 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	12	3400	240	0.014 J	16	330 J	< 0.34 U	< 0.078 U	65 J		< 0.21 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	10	1600	220	0.030	12	410	< 0.31 U	< 0.071 U	< 35 U		< 0.19 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	8.6	2900	350	0.0052 J	18	760	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	9.3	4200	220	0.074	10	330 J	< 0.41 U	< 0.094 U	< 46 U		< 0.26 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	17	4900	350	0.050	18	500	1.0	< 0.089 U	66 J		< 0.24 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	8.3	10000	310	0.039	18	710	0.90	< 0.087 U	73 J		< 0.24 U
Football Field	SSHS-B2185	072518 09:00 PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated	110	4300	440	0.065	36		< 0.58 U	< 0.12 U	240 J		< 0.24 U
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated	38	4000	350	0.059	31		0.67 J	< 0.12 U	300 J		< 0.23 U
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated	30	2700	330	0.03 J	41		0.65 J	< 0.12 U	62 J		< 0.23 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated	18	2400	890	0.18	21		< 0.58 U	< 0.12 U	95 J		< 0.24 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated	15	2300	390	0.023 J	18		< 0.58 U	< 0.12 U	70 J		< 0.24 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated	23	2200	410	0.029 J	14	560	< 0.57 U	< 0.12 U	38 J		< 0.23 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated	12	2100	950	0.02 J	17	690	< 0.59 U	< 0.12 U	38 J		< 0.24 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated	29	2600	430	0.021 J	260		< 0.59 U	< 0.12 U	66 J		< 0.24 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated	13	2600	780	0.026 J	21	930	< 0.57 U	< 0.12 U	53 J		< 0.23 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated	520	2800	590	0.055	19		0.98 J	< 0.12 U	81 J		< 0.25 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated	35	2500	510	0.082	16	700	< 0.59 U	0.21 J	64 J		< 0.24 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated	31	2800	360	0.093	19		< 0.58 U	< 0.12 U	90 J		< 0.24 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated	9.7	3300	350	0.046	18		< 0.57 U	< 0.12 U	59 J		< 0.23 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated		19	86
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated		13	66
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated		33	170
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated		18	55
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated		18	53
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated		11	86
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated		16	70
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated		10	52
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated		12	63
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated		14	53 B
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated		15	52
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated		13	82
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated		16	65
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated		13	66
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated		14	120
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated		12	65
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated		15	60
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated		16	69
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated		16	62
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated		13	72
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated		15	78
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated		8.8	59
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated		19	94
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated		20	2700
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated		12	61
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated		14	55
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	851.75	2 - 4 ft	3.07 ft	1801344461	Not Excavated		13	50
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated		15	60
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated		19	240
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated		9.9	450
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated		9.0	63
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated		9.8	41
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated		12 T	73 T
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated		8.2	31
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated		13	41
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated		8.1	53
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated		12	80
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated		9.2	84
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated		8.1	51
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated		12	76
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated		12	40
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated		13	83
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated		9.9 T	42
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated		11	100
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated		13	63
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated		12	64
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		13	52
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		14	150
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		10	68
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated		12	67
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated		13	71
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated		8.9	50
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated		6.5	73
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated		9.4	120
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated		11	73
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated		7.6	46
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated		9.6	40
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated		12	44
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated		7.2	40
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated		8.4	58
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated		10	61
Football Field	SSHS-B2185	072518 09:00 PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated		19	180
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated		19	91
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated		11	63
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated		17	81
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated		14	51
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated		9	49
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated		12	55
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated		17	200
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated		17	57
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated		16	200
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated		14	58
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated		17	69
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated		10	49

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated	5900	< 0.39 U	6	72	0.3 J	0.081 J	5900	8.6		5.6 J	26	17000
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated	8400	< 0.4 U	8.6	110	0.4 J	0.27 J	11000	22		7.5	56	20000
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated	8900	1.2	8.1	74	0.44 J	0.12 J	3300	16		8.6	38	26000
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated	8800	0.76 J	6.6	110	0.35 J	< 0.043 U	42000	11		6.7	28	23000
Football Field	SSHS-B2026	072718 09:00_PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated	4500	1.4	9.9	130	0.38 J	< 0.043 U	4500	22		5.8 J	120	35000
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated	6700	2.3	11	140	0.47 J	0.54 J	5800	21		5.6 J	150	38000
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated	4800	2.1	9	100	0.26 J	< 0.048 U	34000	10		8.4	140	58000
Football Field	SSHS-B2192	072718 09:00_PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated	7800	0.54 J	7.5	110	0.68	< 0.041 U	2700	10		8.3	36	29000
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated	5800	0.48 J	5.5	68	0.44 J	0.12 J	2100	17		6.2	23	30000
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated	9100	< 0.44 U	8.1	130	0.49 J	0.55 J	23000	36		7.5	63	25000
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated	9200	7	7.7	70	0.45 J	< 0.044 U	5500	15		7	39	24000
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated	4400	0.51 J	5.9	62	0.34 J	< 0.043 U	1600	9.2		4.3 J	28	24000
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated	13000	< 0.4 U	9.6	60	0.56	< 0.043 U	1400	16		11	30	25000
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated	5600	< 0.38 U	5.8	38	0.26 J	< 0.041 U	14000	8.2		6.1	20	15000
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated	9600	< 0.39 U	6.4	90	0.39 J	0.28 J	36000	15		6.4	37	17000
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated	5300	< 0.37 U	3.4	33	0.21 J	0.063 J	58000	7.3		4.4 J	17	13000
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated	6700	< 0.36 U	6.5	50	0.23 J	0.1 J	42000	9.3		6	26	17000
Football Field	SSHS-B2217	072818 11:30_PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated	8700	16	7	96	0.4 J	< 0.043 U	17000	14		6.5	95	18000
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated	8800	4.1	9.3	130	0.48	0.29 J	13000	18		9.2	110	25000
Football Field	SSHS-B2709	052119 08:40_SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated	5300	1.2	8.2	61	0.4 J	0.098 J	4700	16		6.5	41	23000
Football Field	SSHS-IRM3-S058	080319 09:30_SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated	7900	< 0.35 U	5.2	54	0.31 J	0.13 J	38000	10		6.7	24	17000
Football Field	SSHS-IRM3-S084	080319 09:30_SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated	7600	< 0.34 U	5.7	68	0.37 J	0.1 J	3700 J	8.8		6.4	25	16000
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated	7600	< 0.27 U	5.8	55	0.32	0.12 J	24000	9.3		6.3	23	16000
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	7400	1.8	10	200	0.39	0.35 J	12000	29		8.1	88	40000
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	8200	1.6	5.3	61	0.29 J	0.099 J	14000	13		5.4	31	15000
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated	7800	< 0.29 U	6.2	140	0.33 J	0.17 J	12000	16		6.7	42	19000
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated	11000	0.62 J	6.5	110	0.43	0.12 J	5800	19		8.1	43	22000
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated	7300	0.54 J	6.4	110	0.32	0.15 J	14000	19		6.3	38	19000
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated	6900	0.38 J	5.9	100	0.30	0.18 J	28000	14		6.1	36	16000
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated	8500	< 0.27 U	6.8	69	0.36	0.081 J	5700	14		6.8	22	17000
Football Field	SSHS-B3503	090120 10:30_SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated												
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated	6700 T	3.5	14	59	0.36 J	0.27 J	4600	17		9.6	61	50000
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated	10000	1.1 J	11	220	0.49 J	0.42 J	19000	65		10	200	48000
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated	7200	< 0.37 UT	9.9	89 T	0.39 J	0.26 J	3600 T	12		7.3	47 T	25000
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated	9500	< 0.35 U	8.5	30	0.71	0.050 J	790	12		7.4	14	23000
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated	9700	1.6	12	110	0.47 J	0.48 J	14000	21		7.6	60	45000
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated	10000	1.2 T	14	120 T	0.63	4.5	8000 T	14		8.7	38 T	29000 T
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated	13000	< 0.42 U	5.1	86	0.43 J	0.16 J	1100	15		7.4	21	19000
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated	7000	< 0.44 UT	7.5	320 T	0.30 J	0.45 J	99000 T	14		5.8 J	56 T	23000
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated	10000	1.1	8.0	100	0.41	0.30 J	11000	48		8.9	1000	39000
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated	8000	1.2	6.9	100	0.34 J	0.26 J	6900	22		6.9	110	28000
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated	8300	0.52 J	7.7 T	56	0.35 J	0.093 J	1100	10		6.9	23	18000
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated	5700	< 0.37 U	5.1 T	28	0.27 J	0.072 J	630	6.9		4.3 J	15	12000
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated	9500	29 T	10 T	640 T	0.39 J	0.50 J	11000 T	16		7.2	180 T	27000 T
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated	9900	1.2	8.1 T	65	0.45	0.092 J	1300	12		7.6	52	21000
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated	11000	6.8	10 T	180	0.56	0.22 J	5700	15		9.1	52	28000
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated	9500	0.35 J	7.5	52	0.45	0.10 J	1600	11		7.6	24	20000
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated	8400	3.5 T	12	150	0.49	2.9	3000 T	23		7.1	94 T	97000
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated	7100	2.8	11	150	0.36 J	0.43 J	8900	9.4		6.5	31	22000
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated	4500	1.1	4.0	58	0.25 J	0.16 J	4100	9.5		5.3	230	18000
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated	8800	11	7.7	100	0.41 J	0.23 J	1900	12		8.5	440	30000
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated	6700	3.0	14	290	0.50	0.74	9500	47		8.2	460	37000
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated	13000	< 0.34 U	5.4	73	0.47	0.072 J	1400	12		7.6	13	18000 B
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated	8600	1.1 JT	6.9	78	0.42	0.13 J	1600	15		9.3	71 T	32000 BT
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated	7200	0.80 J	7.6	150	0.43	0.50	8100	44		6.8	140	19000
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated	6400	0.51 J	6.1	46	0.29 J	0.14 J	7400	9.4		6.1	34	17000
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated	6300	0.83 T	6.6 T	70 T	0.29 T	0.38	12000	11 T		6.4	84 T	17000
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated	5900	0.55 J	5.6	38	0.25 J	0.31 J	4000	7.8		6.4	87	15000
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated	8200	< 0.29 U	5.9	31	0.36	0.048 J	760	10		8.1	40	17000
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated	5300	< 0.27 U	5.0	33	0.24 J	0.061 J	830	6.8		5.1	16	14000
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated	8000	0.58 J	6.3	110	0.37 J	0.14 J	21000	19		6.5	38	24000 B
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated	10000	1.2	11	120	0.51	0.24 J	8100	18		9.9	44	28000
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated	7900	15	9.1	130	0.41 J	0.42 J	8900	15		8.0	200	37000 B
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated	7900	< 0.24 UT	4.3	50	0.26 J	0.038 J	730	7.9		4.0	13	12000
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated	7800	2.3	17	85	0.65	0.27 J	12000	12		10	54	29000
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated	6200	1.6	9.6	170	0.36 J	0.15 J	5500	9.4		5.9	57	17000
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated	7100	< 0.27 U	5.8	80	0.28 J	0.19 J	34000	13		5.6	64	16000
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated	7600	1.1	32	97	0.59	0.14 J	16000	12		8.8	56	24000
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated	11000	0.66 J	6.0	50	0.43	0.12 J	1500	12		7.6	42	21000
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated	11000	9.0	24	1500	0.58	14	22000	67		130	1300	110000
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated	10000	0.86 J	11	49	0.34 J	0.084 J	950	71		6.8	1900	29000
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated	8400	0.51 J	7.3	58	0.37 J	0.088 J	2300	12		7.1	31	19000
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated	8400	3.4	14	77	0.54	0.25 J	12000	12		7.4	45	25000
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated	9200	< 0.35 U	8.2	520	0.44	0.039 J	940	12		8.3	22	21000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated	27	1900	470	0.069	14		< 0.6 U	< 0.12 U	77 J		< 0.24 U
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated	71	2900	470	0.038	61		0.63 J	< 0.12 U	100 J		< 0.25 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated	56	2400	880	0.068	20		0.6 J	< 0.12 U	62 J		< 0.24 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated	89	5100	500	0.085	30	620	< 0.61 U	< 0.12 U	110 J		< 0.25 U
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated	140	860	260	2.2	56	430 J	1.3	< 0.12 U	81 J		< 0.25 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated	170	1100	970	0.81	47	490 J	1.2	< 0.13 U	150 J		< 0.26 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated	360	1400	590	0.34	14	720	1.3	< 0.14 U	310 J		< 0.28 U
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated	31	2000	730	0.062	22		< 0.58 U	< 0.12 U	65 J		0.44 J
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated	24	1400	860	0.064	16		< 0.58 U	< 0.12 U	54 J		< 0.23 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated	620	3100	460	0.083	650		0.78 J	< 0.14 U	200 J		< 0.27 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated	110	2200	500	0.063	16	930	< 0.62 U	< 0.13 U	69 J		0.54 J
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated	15	740	180	0.067	7.8		1.1 J,^	< 0.12 U	110 J		0.3 J
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated	17	3100	320	0.015 J	19		< 0.61 U	< 0.12 U	53 J		0.47 J
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated	12	2400	340	0.011 J	16	740	< 0.58 U,^	< 0.12 U	50 J		0.3 J
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated	120	5700	490	0.029 J	26	720	< 0.59 U	< 0.12 U	71 J		< 0.24 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated	6.1	9200	290	< 0.0082 U	12	560	< 0.55 U	< 0.11 U	65 J		< 0.22 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated	7.5	5700	390	< 0.0072 U	16	590	< 0.54 U	< 0.11 U	72 J		< 0.22 U
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated	160	2900	360	0.03 J	67		< 0.62 U	< 0.13 U	200 J		< 0.25 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated	150	2600	460	0.048	100		1.1 J	< 0.13 U	190 J		< 0.25 U
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated	42	1300	530	0.032	15		< 0.62 U	< 0.13 U	130 J		< 0.39 U
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated	14	7600	370	< 0.013 U	18		1.1	< 0.11 U	97 J		< 0.33 U
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated	38 J	2300	540	< 0.016 U	17		< 0.52 U	< 0.11 U	170 J		< 0.32 U
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated	29	5200	380	< 0.022 U	19	610	< 0.41 U	< 0.084 U	120 J		< 0.26 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	100	2500	520	0.11	43	710	0.94	< 0.094 U	150 J		< 0.29 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	24	2700	330	0.03 J	17	720	< 0.51 U	< 0.1 U	450 J		< 0.31 U
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated	290	3400	400	0.040	71	660	0.45 J	< 0.089 U	92 J		< 0.27 U
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated	56	2800	590	0.091	28	820	< 0.56 U	< 0.11 U	120 J		< 0.35 U
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated	350	3900	400	0.037	70	660	< 0.37 U	< 0.076 U	98 J		< 0.23 U
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated	140	3400	330	0.029 J	52	640	0.57 J	< 0.066 U	85 J		< 0.20 U
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated	23	2900	400	0.033	19	620	< 0.41 U	< 0.084 U	< 48 U		< 0.25 U
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated	7.4										
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated	26	2300	550	0.039 J	23	650	< 0.52 U	< 0.089 U	140 J		< 0.44 U
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated	140	3400	740	0.12	150	910	0.91 J	< 0.14 U	110 J		< 0.44 U
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated	34 T	2100	390	0.026 JT	35 T	730	< 0.56 U	< 0.12 U	< 66 U		< 0.35 U
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated	11	2400	330	< 0.019 U	20	810	< 0.54 U	< 0.11 U	86 J		< 0.33 U
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated	95	2000	530	< 0.026 U	22	1300	< 0.63 U	< 0.13 U	330 J		< 0.39 U
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated	72 T	2700 T	420	0.039 T	38 T	840	0.97 J	< 0.12 U	140 J		< 0.38 U
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated	14	2700	390	< 0.026 U	27	1200	< 0.64 U	< 0.13 U	190 J		< 0.40 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated	110 T	3100 T	370 T	0.053 T	36	610 J	1.5	< 0.14 U	600 J		< 0.42 U
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated	120	3100	620	0.20	110	910	0.52 J	< 0.10 U	88 J		< 0.32 U
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated	200	2700	550	0.47	78	610	< 0.47 U	< 0.096 U	78 J		< 0.29 U
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated	8.9	2100	460	< 0.019 U	17	710	< 0.52 U	< 0.11 U	80 J		< 0.32 U
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated	6.5	1400	330	0.019 J	10	650	< 0.56 U	< 0.11 U	430 J		< 0.35 U
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated	270 T	2100	380	0.064	34	840	< 0.62 U	< 0.13 U	140 J		< 0.38 U
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated	12	2400	360	< 0.020 U	21	930	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated	130	2700	460	0.034 J	26	1000	< 0.59 U	< 0.12 U	110 J		< 0.37 U
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated	26	2200	370	0.044	18	800	< 0.50 U	< 0.10 U	59 J		< 0.31 U
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated	380	3400 T	390	0.11 T	62 T	820	< 0.62 U	< 0.13 U	94 J		< 0.38 U
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated	57	2000	300	0.054	17	800	< 0.52 U	< 0.11 U	160 J		< 0.32 U
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated	54	1700	130	0.061	280	580	< 0.52 U	0.43 J	120 J		< 0.32 U
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated	140	1700	500	0.26	100	790	0.61 J	0.18 J	72 J		< 0.35 U
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated	560	1700	330	0.27	150	630	1.4	0.21 J	88 J		< 0.36 U
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated	10	2600	430	0.051	17	800	< 0.52 U	< 0.11 U	67 J		< 0.32 U
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated	42 T	1700	860	< 0.024 U	20	900	< 0.45 U	< 0.092 U	95 J		< 0.28 U
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated	140	2300	370	0.20	62	690	< 0.47 U	< 0.095 U	110 J		< 0.29 U
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated	26	3600	380	0.066	95	660	< 0.52 U	< 0.11 U	< 60 U		< 0.32 U
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated	46 T	4600 T	390 T	0.18	130 T	640	< 0.34 UT	< 0.069 U	63 JT		< 0.21 UT
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated	9.7	2600	310	< 0.021 U	300	610	< 0.50 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated	54	2200	320	0.026 J	34	640	< 0.45 U	< 0.091 U	< 52 U		< 0.28 U
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated	9.3	1600	350	< 0.022 U	13	560	< 0.41 U	< 0.084 U	49 J		< 0.26 U
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated	54	2900	420	0.062	20	820	1.2	< 0.11 U	77 J		< 0.34 U
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated	97	2900	410	0.064	50	1000	< 0.52 U	< 0.11 U	100 J		< 0.32 U
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated	270	2600	510 B	0.21	21	800	< 0.57 U	< 0.12 U	93 J		< 0.35 U
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated	7.0	1500	200	0.024 JT	10	450	< 0.36 U	< 0.073 U	< 42 U		< 0.22 U
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated	160	2300	450	0.13	59	730	0.93 J	< 0.12 U	110 J		< 0.37 U
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated	99	2300	340	0.15	32	610	0.58 J	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated	55	2200	350	0.056	31	710	0.76 J	< 0.084 U	73 J		< 0.26 U
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated	77	2700	400	0.071	30	780	0.89 J	< 0.11 U	88 J		< 0.35 U
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated	28	2700	190	0.10	19	820	0.61 J	< 0.097 U	< 56 U		< 0.30 U
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated	330	3700	650	0.42	70000	680 J	< 0.74 U	57	150 J		< 0.46 U
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated	30	2400	250	0.29	770	950	0.58 J	< 0.11 U	< 63 U		< 0.33 U
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated	22	2200	320	0.085	37	800	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated	100	3100	410	0.099	21	860	0.56 J	< 0.11 U	73 J		< 0.32 U
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated	15	2200	320	0.025 J	20	870	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated		11	58
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated		15	130
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated		22	140
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated		13	130
Football Field	SSHS-B2026	072718 09:00_PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated		14	120
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated		15	140
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated		17	170
Football Field	SSHS-B2192	072718 09:00_PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated		16	98
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated		26	62
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated		17	350
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated		20	110
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated		14	27
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated		21	58
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated		11	51
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated		13	140
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated		8.4	40
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated		9.7	53
Football Field	SSHS-B2217	072818 11:30_PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated		15	120
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated		16	160
Football Field	SSHS-B2709	052119 08:40_SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated		21	49
Football Field	SSHS-IRM3-S058	080319 09:30_SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated		12	67
Football Field	SSHS-IRM3-S084	080319 09:30_SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated		12	51
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated		13	66
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated		26	170
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated		14	87
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated		13	92
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated		17	94
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated		11	76
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated		11	79
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated		12	180
Football Field	SSHS-B3503	090120 10:30_SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated			
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated		27	74
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated		20	550
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated		15	160 T
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated		18	54
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated		32	81
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated		18	1000 T
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated		18	100
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated		14	140
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated		17	130
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated		13	110
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated		13	63
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated		9.3	45
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated		20	240 T
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated		16	62
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated		19	110
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated		17	59
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated		18	1300
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated		14	150
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated		10	1900
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated		21	670
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated		17	330
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated		18	51
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated		29	51
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated		14	190
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated		10	93
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated		11 T	220 T
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated		13	530
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated		14	110
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated		11	42
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated		16	66
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated		21	130
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated		25	190
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated		13	38 T
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated		18	150
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated		12	110
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated		12	87
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated		16	110
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated		16	67
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated		20 J	8700
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated		20	180
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated		16	66
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated		18	160
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated		19	55

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated	6300	< 0.30 U	6.0	680	0.29 J	0.044 J	930	8.0		5.6	19	15000
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated	7600	< 0.28 U	6.4	250	0.34	0.071 J	3100	8.8		6.7	22	15000
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated	4700	1.4 J	25	110	0.49 J	0.40 J	1900	73 B		5.3	160	40000
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated	6400	1.0 J	13	87	0.41 J	0.23 J	1500	9.8		5.6	58	22000
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated	3800	< 0.36 U	9.7	180	0.58	0.45 J	1100	11		4.9	80	28000
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated	8400	< 0.36 U	4.4	67	0.34 J	0.40 J	19000	10 B		6.7	130	19000
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated	7900	0.53 J	9.8	99	0.41 J	0.30 J	11000	13		6.8	110	22000
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	6000	< 0.34 U	9.1	78	0.57	0.32 J	6500	11		8.4	60	21000
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	7200	< 0.31 U	7.1	94	0.35 J	0.18 J	1600	10		6.3	28	17000
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	5800	< 0.28 U	6.5	39	0.28 J	0.15 J	1200	9.3		5.6	24	24000
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated	7800	0.56 J	7.5	110	0.40 J	0.19 J	13000	12		7.6	72	20000
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated	8600	1.5 J	12	130	0.37 J	0.25 J	33000	12		7.6	91	21000
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated	4800	< 0.27 U	5.6	24	0.17 J	0.067 J	26000	6.7		5.2	18 B	13000 T
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated	5700	< 0.34 U	4.5	32	0.14 J	0.094 J	33000	6.8		5.0	20 B	13000 T
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated	4200	< 0.32 U	3.8	29	0.072 J	0.070 J	48000	5.4		4.1	14	10000
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated	6600	< 0.36 U	4.7	35	0.24 J	0.12 J	13000	8.4		5.8	26	16000 T
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated	6600	1.9 J	7.9	72	0.32 J	0.25 J	5900	16		6.4	89	22000
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated	7100	0.60 J	7.9	100	0.49 J	0.16 J	2900	11		6.9	110	18000
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated	7800	1.2 J	6.3	53	0.39 J	0.14 J	1900	17		6.0	120	15000
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated	5800	1.7 J	11	440	0.48 J	0.74	2000	32		5.4	160	30000
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated	8300 T	29	6.6	68 B	0.36 J	0.079 J	1900	11		8.0	210	21000 B
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated	4400 T	< 0.33 U	5.1	46	0.23 J	0.13 J	4400	8.2		3.9	62	14000
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated	11000	0.69 J	11	130	0.59	0.16 J	3900	17		8.0	33	41000
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated	5400	26	15	100	0.48 J	0.31 J	10000	14		8.5	300	34000
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated	6100	90	16	180	0.38 J	0.50 J	6900	21		18	1200	86000
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated	7700	1.3 J	9.8	110	0.38 J	0.33 J	11000	30		8.3	170	34000
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated	6900	1.9 JT	16	94 T	0.36 J	0.37 J	9700	45 T		12	200	48000
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated	6100	< 0.36 U	11	94	0.48 J	0.20 J	10000	15		8.7	50	18000
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated	4800	< 0.34 U	4.0	36	0.21 J	0.13 J	8100	6.9		4.8	21	13000
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated	8200 B	< 0.39 U	6.5	83	0.37 J	0.26 J	18000	10		6.8	34	17000
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated	8200 B	2.3 T	12	89	0.42 J	0.19 J	13000	11		9.0	45	23000
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated	8600 B	< 0.38 U	7.4	110	0.38 J	0.072 J	17000	10		5.5	22	16000
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated	5700 B	9.0	20	130	0.49	1.4	3500	17		12	300	33000
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated	5200 B	0.87 J	11	800	0.38 J	0.95	9800	77		6.0	450	32000
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated	10000	< 0.32 U	8.9	35	0.39 J	< 0.043 U	440 J	12		8.0	27	24000
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	5800 T	2.3 T	12 T	71 T	0.36 T	0.048 JT	4000 T	11 T		6.9	36 T	23000 T
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated	2600	1.7	12	70	0.41 J	0.64	8500	12		5.6	210	31000
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	6400	1.7	12	170	0.45	0.24 J	18000	36		7.5	180	30000 B
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated	11000	0.91 J	5.9	130	0.49	0.23 J	1600	12		7.9	69	20000
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated	10000	1.3 T	6.3	120 T	0.47	0.24 J	2100	12		6.5	67 T	18000 T
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	11000	< 0.29 U	7.6	48	0.45	< 0.031 U	2100	12		8.0	17	18000
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated	9400	3.1	8.3	140	0.41 J	0.56 J	8300	17		9.3	560	24000
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated	12000	1.3 J	7.6	140	0.45 J	0.26 J	3000	15		9.1	320	26000
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated	12000	< 0.34 U	9.8	31	0.42 J	< 0.045 U	420 J	14		10	27	26000
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated	12000	0.98 J	9.0	76	0.46 J	0.22 J	9300	40		9.8	240	28000
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	6700	0.75 J	4.6	83	0.29 J	0.23 J	34000	11		4.8	210	17000
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	8100	3.0	9.7	110	0.40 J	0.50 J	12000	21		7.7	250	31000
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	7700	1.4	6.1	70	0.36 J	0.14 J	3700	13		7.0	67	20000
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	4000	< 0.34 UT	2.9	25	0.16 JT	0.046 JT	33000	5.2		3.1 J	16	8200
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	7400	6.0	15	77	0.31 J	0.25 J	19000	18		8.3	210	56000
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	16000	3.3	14	180	0.78	0.26 J	13000	29		13	130	37000
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated	12000	0.31	7.8	66	0.55	0.069 BJ	1300 B	15 B		9.6	250	21000 B
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated	9500	7.2	18	88	0.53	0.36 B	3700 B	12 B		12	180	42000 B
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated	6300	1.0	9.8	20	0.25	0.051 BJ	1000 B	33 B		4.8	150	19000 B
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated	10000	0.93 T	8.6	120	0.52	0.19	5500	14 B		9.0	120 T	30000 T
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated	12000	0.16 J	11	93	0.59	0.040 J	3800	15 B		12	27	29000
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated	8800	0.70	8.8	110	0.45	9.4	3500	12 B		12	24	22000
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	8800	0.41 J	6.7	44	0.38	0.038 J	1200	11		7.5	94	17000
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated	7800	0.57 J	4.6	98	0.33	0.055 J	16000	9.1		5.7	48	13000
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated	6700	0.99 T	7.6	81	0.38	0.15	22000	11 B		5.4 B	60 T	20000
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated	6400	2.5	11	150	0.39	0.33	39000	39 B		6.7 B	210	48000
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	7500	0.19	7.6	36	0.40	0.052 J	760	9.4 B		6.6 B	19	17000
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated	8200	1.2	7.1	73	0.35 J	0.063 J	13000	14		6.6	120	33000
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated	9500	0.56 J	7.5	150	0.33 J	0.53	2300	9.4		4.5	9.3	13000
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated	9600	0.37 J	6.5	120	0.43	0.12 J	4800	12		7.6	25	18000
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated	6900	< 0.35 U	8.1	67	0.33 J	0.30 J	3200	12		6.5	45	16000
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated	10000	< 0.39 U	6.2	79	0.42 J	0.099 J	1700	12		8.4	25	18000
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated	8800	< 0.34 UT	7.1	35	0.39 J	< 0.046 U	830	12		8.4	20	19000
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated	9800	1.9 J	13	220	0.51 J	0.099 J	3700	27		12	86	34000
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated	11000	< 0.37 U	10	100	0.47 J	0.12 J	3800	14		11	37	27000
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated	6000	< 0.32 U	6.7	52	0.27 J	0.16 J	14000	8.1		5.8	34	14000
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated	5800	< 0.33 U	6.1	60	0.27 J	0.75	16000	13		5.6	280	22000
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated	3600	< 0.34 U	5.1	43	0.16 J	0.13 J	43000	5.6		3.3	16	9700
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated	6900	0.77 J	9.7	120	0.33 J	0.41 J	8600	23		8.5	110	40000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated	360	1800	350	0.067	15	610	< 0.46 U	< 0.093 U	< 54 U		< 0.28 U
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated	46	2000	610	0.024 J	15	680	< 0.42 U	< 0.086 U	52 J		< 0.26 U
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated	160 B	940	230	0.15	63	630	1.4 J	0.097 J	70 J		< 0.44 U
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated	54	1400	370	0.072 J	20	650	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated	120	660	200	0.048 J	53	250 J	< 0.47 U	< 0.081 U	< 62 U		< 0.40 U
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated	220 B	2700	380	0.37	24	490 J	< 0.47 U	< 0.081 U	70 J		< 0.40 U
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated	120	2400	520	1.0	21	550 J	< 0.52 U	< 0.090 U	180 J		< 0.44 U
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	60	1700	580	0.092 J	25	480	< 0.44 U	< 0.076 U	75 J		< 0.37 U
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	18	2200	450	0.027 J	20	630	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	13	1600	490	0.024 J	29	430	< 0.37 U	< 0.064 U	< 50 U		< 0.32 U
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated	54	1900	530	0.16	23	480 J	< 0.51 U	< 0.089 U	100 J		< 0.44 U
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated	50	2100	460	0.13	22	480 J	< 0.52 U	< 0.089 U	320 J		< 0.44 U
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated	7.3	4000	300	< 0.020 U	13	520	< 0.35 U	< 0.061 U	54 J		< 0.30 U
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated	5.8	3700	330	< 0.018 U	13	450 J	< 0.44 U	< 0.077 U	110 J		< 0.38 U
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated	5.7	8700	280	< 0.018 U	10	390 J	< 0.42 U	< 0.073 U	69 J		< 0.36 U
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated	8.8	2800	340	< 0.019 U	16	570	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated	75	2500	500	0.15	44	580	< 0.46 U	0.083 J	< 62 U		< 0.39 U
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated	74	1500	340	0.13	20	660	0.49 J	0.092 J	86 J		< 0.40 U
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated	450	1800	450	0.034 J	49	610	< 0.49 U	0.11 J	86 J		< 0.41 U
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated	420	1100	910	0.11 J	75	750	< 0.48 U	0.27 J	190 J		< 0.41 U
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated	40	1600	680	0.077 J	18	640	< 0.54 U	< 0.093 U	< 72 U		< 0.46 U
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated	94	980	170	0.069 J	85	440 J	< 0.44 U	< 0.075 U	61 J		< 0.37 U
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated	18	1800	820	< 0.027 U	20	1300	1.4	< 0.13 U	110 J		< 0.39 U
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated	200	1500	370 B	0.18	26	680	1.6 BJ	0.28 J	170 J		< 0.41 U
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated	770	2400	750 B	0.36	38	700	1.1 BJ	0.39 J	92 J		< 2.1 U
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated	140	2200	580	0.69	49	620	0.61 J	< 0.082 U	110 J		< 0.40 U
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated	600 T	2100	660	0.22 T	54	540	0.90 J	0.11 J	71 J		< 0.42 U
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated	59	2500	270	0.11 J	74	580	0.47 J	< 0.082 U	69 J		< 0.40 U
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated	12	1900	860	0.027 J	30	460 J	< 0.44 U	< 0.076 U	60 J		0.55 J
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated	44	2000	390	0.034 J	17	640	< 0.51 U	0.11 J	170 J		< 0.44 U
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated	68	2100	630	0.085 J	18	600	1.4 J	0.11 J	160 J		< 0.40 U
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated	33	1700	350	< 0.026 U	15	1900	< 0.49 U	0.088 J	360 J		< 0.42 U
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated	140	1000	570	0.093 J	37	590	1.4 J	0.19 J	78 J		< 0.36 U
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated	290	1400	340	0.086 J	93	610	< 0.44 U	0.19 J	280 J		< 0.37 U
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated	16	2700	350	0.036 J	210	720	0.46 J	< 0.073 U	< 56 U		< 0.36 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	97	1900 T	290 T	0.059	23 T	520 T	< 0.44 UT	< 0.090 UT	< 52 UT		< 0.27 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated	75	550	200	0.070	27	420 J	3.0	< 0.11 U	130 J		1.6 J
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	190	2700	390	0.097	100	630	0.70 J	< 0.12 U	140 J		< 0.35 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated	29	2100	470	0.051	17	800	0.84 J	< 0.11 U	76 J		1.2 J
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated	42 T	1900 T	640	0.073 T	17	730	1.3	< 0.11 U	96 J		0.96 J
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	12	2400	350	< 0.020 U	17	700	< 0.44 U	< 0.089 U	< 51 U		0.47 BJ
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated	310	3200	540	0.46	410	670	< 0.55 U	0.18 BJ	110 J		0.58 J
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated	130	2600	580	0.16	61	720	< 0.58 U	0.19 BJ	83 J		< 0.49 U
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated	16	3000	380	0.039 J	210	720	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated	72	3500	370	0.098 J	360	860	< 0.46 U	0.14 BJ	180 J		< 0.39 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	95	7100	420	0.28	19	550	< 0.46 U	< 0.095 U	76 J		< 0.29 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	120	2600	450	0.21	81	650	< 0.56 U	< 0.11 U	< 66 U		0.41 J
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	45	2300	480	0.022 J	34	660	< 0.52 U	< 0.11 U	< 61 U		0.40 J
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	7.2	1700 T	370	< 0.023 U	8.5	360 J	< 0.51 UT	< 0.10 U	< 60 U		< 0.32 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	580	2400	500	0.22	21	570	< 0.49 U	0.16 J	< 57 U		< 0.61 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	130	5200	810	0.25	100	1600	< 0.92 U	< 0.19 U	130 J		0.64 J
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated	24	2800	270	0.17	210	890	0.22 J	0.035 J	48 J		0.16
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated	240	2100	360	0.087	2000	760	1.3	0.12	96		0.20
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated	25	1900	140	0.14	63	620	0.42	0.35	41		0.10
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated	55 T	2700 T	400 T	0.069 T	26	860	0.57	0.054 J	190		0.15
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated	16	4000	440	< 0.018 U	29	1100	< 0.11 U	< 0.023 U	40 J		0.082 J
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated	61	2900	410	0.079	25	930	0.11 J	0.027 J	41 J		0.070 J
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	19	2100	310	< 0.018 U	240	690	< 0.45 U	< 0.092 U	< 53 U		< 0.28 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated	38	1400	280	0.070	18	580	< 0.38 U	< 0.078 U	140 J		< 0.24 U
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated	170	1900	410 T	0.12	14	660	0.45	0.033 J	160		0.11
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated	150	2100	710	1.9	23	770	0.41 J	0.089 J	340		0.13
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	9.2	2000	340	< 0.019 U	18	720	0.10 J	< 0.023 U	28 J		0.092
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated	32	2700	470	0.057	17	590	< 0.52 U	< 0.11 U	110 J		< 0.33 U
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated	17	1500	830	0.050	10	490	< 0.45 U	< 0.093 U	< 53 U		< 0.28 U
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated	30	2600	580	0.17	24	660	< 0.40 U	< 0.069 U	60 J		< 0.34 U
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated	33	2000	300	0.040 J	28	650	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated	14	2500	490	0.031 J	26	680	< 0.51 U	< 0.089 U	< 69 U		< 0.44 U
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated	8.7	2300	250 T	0.027 J	18	740	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated	66	3100	530	0.069 BJ	46	1100	0.59 J	< 0.091 U	96 J		< 0.45 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated	19	3700	500	< 0.021 U	29	1100	< 0.48 U	< 0.083 U	79 J		< 0.41 U
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated	20	3200	380 B	0.022 J	16	570	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated	54	7800	520	0.047 J	48	360 J	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated	8.3	3700	260	< 0.018 U	9.6	380 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated	72	3400	660	0.11	97	440	< 0.42 U	< 0.072 U	< 56 U		< 0.35 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated		9.8	45
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated		15	54
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated		17	200
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated		13	95
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated		8.7	170
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated		17	130
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated		16	150
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated		13	130
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated		11	75
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated		11	77
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated		14	130
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated		15	140
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated		9.9	48
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated		9.2	47
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated		6.8	39
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated		11	59
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated		14 B	140
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated		13	110
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated		13	160
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated		15	340
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated		16 B	68 B
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated		8.8	65
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated		31	52
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated		16	200
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated		35	440
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated		16	200
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated		17	190
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated		15	120
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated		8.1	66
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated		13	64
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated		17	110
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated		16	270
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated		25	140
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated		17	480
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated		18	64
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated		13 T	89
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated		15	150
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated		17	210
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated		17	66
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated		15	67 T
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated		17	44
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated		16	370
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated		18	180
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated		18	70
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated		21	210
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated		12	120
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated		17	240
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated		14	95
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated		6.7	36 T
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated		40	130
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated		28	190
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated		18	360
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated		19	2900
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated		15	200
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated		22	100
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated		17	67
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated		13	61
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated		15	66
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated		12	81
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated		17	94
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated		20	220
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated		15	83
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated		21	110
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated		13	1500
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated		15	120
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated		12	250
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated		15	110
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated		14	58
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated		21	110
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated		15	83
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated		9.7	100
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated		10	480
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated		6.4	61
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated		14	170

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1	50		
Restricted - Residential															16	400	72	4.3		110	110	270		
Protection of Groundwater															16	820	47	7.5		19	19	1720		
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated	9700	0.62 J	10	74	0.43	< 0.037 U	3400	12		10	18	23000 B
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated	7200	1.6	8.1	70	0.42	0.042 J	1400	11		8.3	41	26000
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated	4100	3.3 J	26	46	0.21 J	< 0.038 U	9700	31		6.3	37	160000 B
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated	8700	1.2	6.9	73	0.37	0.091 J	1800	11		6.3	33	21000 B
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated	8400	0.54 J	7.4	72	0.41	0.088 J	23000	12		6.6	34	23000 B
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated	8200	0.96 JT	7.0	110 T	0.39 J	0.11 J	8000	13		7.3	52 T	21000 B
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated	11000	0.81	9.4	83	0.42	< 0.029 U	5400	12		9.1	27	26000 B
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated	7900	2.7	9.4	86	0.48	0.14 J	12000	13		7.7	50	34000 B
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated	11000	0.41 J	7.5	110	0.54	0.085 J	2400	13		9.5	36	20000 B
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated	8000	1.2	21	74	0.37 J	0.081 J	2100	14		7.6	44	22000 B
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated	7700	4.2	16	100	0.62	0.18 J	3400	26		7.2	92	29000 B
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated	7300	0.77 J	6.2	78	0.38 J	0.092 J	5500	11		7.0	34	16000 B
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated	6500	1.7 J	15	99	0.37 J	0.30 J	6700	28		9.1	240	48000 B
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated	6700	0.41 J	7.4	220	0.29 J	0.056 J	21000	8.7		6.4	27	17000
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated	11000	0.43 J	8.0	98	0.47 J	0.080 J	4600	13		8.5	24	21000
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	8900	0.27 J	7.7	81	0.41	0.11 J	13000	11		7.0	61	20000
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	8800	< 0.24 U	6.7	72	0.39	0.063 J	7000	11		6.8	34	18000
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	8500	< 0.27 U	5.8	22	0.37	< 0.029 U	520	9.4		6.9	16	16000
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	13000	< 0.32 U	7.0	98	0.50	< 0.034 U	1600	13		13	15	20000
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	6600	< 0.32 U	7.4	62	0.30 J	0.071 J	12000	9.9		5.9	35	19000
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	8000	< 0.034 U	5.3	56	0.3 J	0.042 J	16000	11		5.5	19	15000
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	9600	< 0.034 U	5.7	78	0.38 J	0.038 J	13000	12		6	17	16000
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	12000	< 0.32 U	9.1	49	0.46	< 0.034 U	3100	14		10	38	25000
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	11000	< 0.23 U	7.7	70	0.46	0.030 J	6700	13		9.0	27	21000
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	12000	< 0.23 U	10	45	0.47	< 0.025 U	3700	16		12	25	28000
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	7300	< 0.28 U	7.7	46	0.31 J	< 0.030 U	2100	9.2		7.1	19	17000
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	7300	0.53 J	9.4	75	0.37	0.11 J	3400	27		6.2	39	21000
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	10000	< 0.28 U	8.5	77	0.46	0.030 J	6600	13		8.7	34	21000
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	7600	0.25 J	6.0	28	0.35	< 0.027 U	1300	8.5		5.9	19	17000
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	8200	< 0.28 U	7.4	55	0.37	0.053 J	8400	12		7.7	33	20000
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	8600	< 0.30 UT	7.6	63	0.37	< 0.032 U	2200 T	10		7.5	23	18000
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated	6100	0.39 J	7.3	49	0.28 J	0.18 J	7400	9.2		5.6	32	30000
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated	5500	< 0.38 U	8.1 B	50	0.25 J	0.28 J	24000	8.4		4.3	66	14000
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated	8000	0.44 J	6.7 B	89	0.39 J	0.71	2300	11		5.4	40	16000
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	8800	2.3	6.5	83	0.42 J	0.12 J	9100	11		6.8	36	17000
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	9600	< 0.35 UT	9.5	75	0.42 J	< 0.046 U	4900	12		10	25	23000
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	6700	3.3	14	130	0.49 J	0.16 J	2200	14		13	95	48000
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	11000	< 0.42 UT	7.0	47	0.45 J	< 0.056 U	1300	12		8.1	22	20000
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	10000	< 0.36 UT	5.8	78	0.43 J	0.097 J	1700	12		7.6	26	19000
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	10000	0.35 J	15	70	0.49	0.16 J	2300	12		20	80	46000
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	11000	0.49 JT	8.7	57	0.48 J	0.075 J	4300	14		8.9	30	22000
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	11000	< 0.35 UT	6.9	44	0.45 J	< 0.046 U	1100	13		9.4	19	19000
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	9500	< 0.42 UT	6.3	52	0.39 J	< 0.056 U	1300	11		6.6	16	17000
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	11000	< 0.34 UT	6.0	52	0.42 J	0.068 J	1200	12		7.8	18	18000
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	8200	< 0.28 UT	5.9	45	0.35 J	0.041 J	1400	10		7.8	18	16000
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	6700	< 0.34 UT	4.8	51	0.19 J	0.089 J	46000	9.5		6.5	22	16000
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	6500	< 0.28 UT	4.5	43	0.20 J	0.062 J	32000	8.7		5.9	19	15000
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	6600	< 0.31 UT	5.9	54	0.19 J	0.11 J	47000	9.1		7.1	23	17000
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	9300	< 0.35 UT	6.6	89	0.41 J	0.10 J	12000	12		8.3	19	18000
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	8800	1.1 JT	5.6	96	0.38 J	0.098 J	8600	11		6.5	40	16000
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	5800	< 0.28 U	4.9	35	0.26 J	0.065 J	600	7.0		5.6	13	13000
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	7200	0.62 J	7.4	44	0.38 J	0.17 J	2400	9.1		6.9	36	17000
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	9000	< 0.30 U	10	71	0.38	< 0.032 U	2200	11		8.3	15	21000
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	9300	< 0.29 U	8.8	74	0.41	< 0.031 U	2200	12		9.8	29	22000
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	9100	< 0.26 U	8.1	72	0.40	< 0.027 U	2600	11		9.2	16	20000
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	8500	1.5 T	7.6	73 T	0.37 T	0.067 JT	4600 T	13 T		8.2	61 T	23000 T
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	4200	0.54 J	9.5	45	0.51	0.076 J	13000	13		5.6	72	36000
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	4000	0.80 J	7.0	63	0.22 J	0.15 J	2100	49		4.0 J	75	26000
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	6200	0.66 J	6.4	53	0.31 J	0.10 J	2400	12		5.6	66	20000
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	6400	0.44 J	4.5	71	0.26 J	0.25 J	1100	6.8		5.5 J	23	13000
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	6200	1.7	10	59	0.34 J	0.13 J	4900	9.5		6.1	47	20000
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	8300 B	0.31 J	6.4	37	0.36	< 0.032 U	3300	10		6.7	20	18000
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	10000 B	< 0.33 U	5.0	47	0.37 J	< 0.036 U	930	11		6.8	13	20000
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	10000 B	< 0.34 U	7.4	49	0.45	< 0.037 U	1400	12		8.4	20	19000
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	12000 B	< 0.40 U	8.0	68	0.54	< 0.042 U	830	14		9.4	17	20000
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	11000 B	< 0.35 U	8.0	62	0.48	< 0.038 U	2300	14		9.2	20	20000
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	11000 B	< 0.38 U	6.8	45	0.48	< 0.040 U	770	12		8.4	20	26000
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	12000 B	< 0.30 U	8.6	37	0.47	< 0.033 U	750	12		10	21	21000
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	8800 B	< 0.37 U	6.8	79	0.39 J	< 0.039 U	3600	11		10	17	21000
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	11000 B	0.38 JT	7.4	47	0.48	< 0.041 U	1900 T	12		8.3	22	19000
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	6400	< 0.20 U	6.5	53	0.32	0.087 J	7000	9.1		6.0	34	16000
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	6800	< 0.20 U	6.6	83	0.30	0.096 J	16000	9.3		6.2	29	15000
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	6800	0.49 J	6.1	58	0.33	0.082 J	10000	11		6.3	31	17000
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	9300	< 0.23 U	7.8	52	0.43	0.039 J	1900	11		7.7	27	18000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated	13	3300	420	< 0.018 U	22	980	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated	43	1200	550	0.061	16	690	0.78 J	< 0.11 U	75 J		< 0.32 U
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated	54	950	910	0.13	21	390 J	1.1	< 0.11 U	92 J		< 0.34 U
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated	48	1900	450	0.067	14	740	< 0.45 U	< 0.093 U	160 J		< 0.28 U
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated	60	2500	440	0.15	20	870	< 0.50 U	< 0.10 U	150 J		< 0.31 U
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated	69	2700	420	0.27	26	800	< 0.56 U	< 0.12 U	< 66 U		< 0.35 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated	29	3400	430	0.10	25	1000	< 0.41 U	< 0.083 U	51 J		< 0.25 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated	160	1900	360	0.097	23	830	0.74 J	< 0.10 U	120 J		< 0.31 U
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated	18	2900	560	0.25	22	1100	< 0.59 U	< 0.12 U	< 64 U		< 0.37 U
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated	53	2000	350	0.17	19	700	0.64 J	< 0.10 U	44 J		< 0.30 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated	150	1700	310	0.17	31	800	1.9	< 0.11 U	62 J		< 0.32 U
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated	49	2400	390	0.26	24	720	< 0.54 U	< 0.11 U	44 J		< 0.34 U
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated	130	2100	870	0.25	71	510	1.3	< 0.11 U	74 J		< 0.33 U
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated	49	5000	360	< 0.022 U	17	610	< 0.50 U	< 0.10 U	67 J		< 0.31 U
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated	25	3300	540	< 0.027 U	21	830	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	44	3700	400	0.046	22	600	0.56 J	< 0.084 U	160 J		< 0.26 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	39	2600	380	0.046	38	470	0.45 J	< 0.074 U	220 J		< 0.23 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	8.1	2200	440	< 0.017 U	16	460	< 0.41 U	< 0.083 U	290 J		< 0.25 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	16	2500	710	< 0.018 U	19	630	< 0.48 U	< 0.098 U	330 J		< 0.30 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	32	2400	480	< 0.019 U	43	500	0.55 J	< 0.098 U	240 J		< 0.30 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	15	3200	420	0.035	17	630	< 0.034 U	< 0.034 U	66 J		< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	22	2700	600	0.026 J	14	700	0.64 J	< 0.034 U	62 J		< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	15 B	3900	410	0.034	25	900	< 0.48 U	< 0.099 U	< 57 U		< 0.30 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	22 B	3500	400	0.064	25	720	< 0.35 U	< 0.071 U	55 J		< 0.22 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	16 B	4300	480	0.031	29	810	< 0.35 U	< 0.071 U	< 41 U		< 0.22 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	10 B	2300	320	0.023 J	15	730	< 0.42 U	< 0.085 U	62 J		< 0.26 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	36 B	2000	350	0.10	30	610	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	19 B	3700	440	0.019 J	23	820	0.52 J	< 0.087 U	< 50 U		< 0.26 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	7.9 B	2200	310	0.051	15	490	< 0.38 U	< 0.077 U	57 J		< 0.24 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	25 B	2900	360	0.13	21	710	0.46 J	< 0.088 U	79 J		< 0.27 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	22 BT	2500	440	0.049 T	21	790	< 0.45 U	< 0.093 U	63 J		< 0.28 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated	35	3500	390	0.032 J	18	480 J	< 0.48 U	< 0.082 U	< 64 U		< 0.41 U
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated	92	5000	310	0.095 J	100	500 J	< 0.49 U	< 0.085 U	87 J		< 0.42 U
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated	42	2100	410	0.12	27	490	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	96	2500	450	0.16	18	700	< 0.45 U	< 0.078 U	77 J		< 0.38 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	11	3500	420	0.027 J	23	980	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	110	1400	720	0.17	20	770	0.80 J	0.17 J	120 J		< 0.40 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	15	2600	260	0.047 J	19	720	< 0.55 U	< 0.095 U	< 74 U		< 0.47 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	34	2500	360	0.061 J	18	490 J	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	41	2200	390	0.083 J	26	830	0.83 J	0.94 J	83 J		< 0.38 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	38	2800	240	0.063 J	21	770	< 0.55 U	< 0.095 U	< 73 U		< 0.47 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	9.7	2600	270	0.051 J	18	730	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	8.9	2300	350	0.032 J	16	660	< 0.55 U	< 0.095 U	< 73 U		< 0.47 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	15	2400	320	0.040 J	19	660	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	11	2200	330	0.025 J	17	600	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	8.2	5500	390	< 0.020 U	18	560	< 0.44 U	< 0.076 U	80 J		< 0.38 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	7.7	4700	350	< 0.019 U	17	540	< 0.37 U	< 0.064 U	63 J		< 0.31 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	7.4	6100	460	< 0.022 U	18	550	< 0.41 U	< 0.071 U	73 J		< 0.35 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	18	3800	410	0.12	22	680	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	36	2600	490	0.065 J	18	650	< 0.52 U	< 0.089 U	73 J		< 0.44 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	6.4	1700	280	0.023 J	16	450	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	82	1900	330	0.064 J	18	610	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	13	2900	390	< 0.017 U	18	860	< 0.45 U	< 0.092 U	< 53 U		< 0.28 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	17	2900	460	< 0.016 U	19	900	0.72 J	< 0.090 U	< 51 U		< 0.27 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	13	2700	460	< 0.015 U	18	850	< 0.39 U	< 0.079 U	< 45 U		< 0.24 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	56 T	2600	510	0.090	27 T	640 T	< 0.34 UT	< 0.069 UT	45 J		< 0.21 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	36	7000	350	1.1	36	420	1.7	< 0.088 U	68 J		< 0.27 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	46	950	370	0.21	50	310 J	0.78 J	< 0.088 U	50 J		0.29 J
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	38	1600	350	0.096	27	560	0.50 J	< 0.085 U	< 49 U		< 0.26 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	35	1200	640	0.050	12	390 J	1.0 JT	< 0.12 U	< 67 U		< 0.36 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	78	1600	330	0.14	13	570	< 0.53 UT	< 0.11 U	69 J		< 0.33 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	11	2600	230	< 0.017 U	17	620	0.49 J	< 0.094 U	< 54 U		< 0.29 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	8.0	2300	230	< 0.021 U	15	760	< 0.50 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	10	2800	230	0.026 J	19	860	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	12	2700	300	< 0.024 U	24	1100	< 0.60 U	< 0.12 U	< 70 U		< 0.37 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	18	2900	320	0.025 J	21	1100	0.53 J	< 0.11 U	< 63 U		< 0.33 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	12	2500	220	0.021 J	18	960	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	11	2600	420	0.028 J	19	820	0.83 J	< 0.094 U	< 54 U		< 0.29 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	13	2700	520	0.041	20	950	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	14	2700	340 T	0.028 J	20	850 T	0.65 JT	< 0.12 U	< 68 U		< 0.36 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	24	3200	330	0.50	17	410	< 0.30 U	< 0.061 U	39 J		< 0.18 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	29	4100	310	1.0	25	500	0.54 J	< 0.061 U	40 J		< 0.19 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	56	3300	380	0.54	17	490	0.82	< 0.066 U	48 J		< 0.20 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	18	2200	340	0.062	16	580	0.36 J	< 0.072 U	< 41 U		< 0.22 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated		13	51
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated		21	58
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated		70	54
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated		16	77
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated		17	62
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated		15	74 T
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated		14	66
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated		16	170
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated		15	78
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated		19	130
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated		22	140
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated		14	100
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated		20	220
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated		12	62
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated		17	73
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated		12	77
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated		13	63
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated		11	40
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated		17	51
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated		11	58
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated		13	58
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated		15	59
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated		15	68
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated		14	67
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated		16	73
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated		12	41
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated		13	79
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated		14	61
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated		11	44
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated		14	95
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated		12	71 T
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated		10	130
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated		17	310
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated		16	950
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated		15	97
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated		13	59
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated		25	110
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated		17	60
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated		15	87
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated		20	64
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated		20	77
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated		17	52
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated		15	52
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated		16	59
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated		13	66
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated		10	76
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated		9.6	59
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated		11	70
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated		13	71
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated		15	73
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated		8.5	41
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated		13	82
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated		12	45
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated		13	50
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated		13	52
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated		14	82
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated		13	96
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated		9.5	90
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated		15	81
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated		11	110
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated		15	87
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated		12	47
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated		14	42
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated		15	49
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated		17	53
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated		17	55
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated		16	49
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated		17	49
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated		13	47
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated		15	53
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated		12	84
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated		12	73
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated		16	65
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated		15	49

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	8500	0.33 J	7.3	36	0.41	0.042 J	2700	9.3		7.6	34	18000
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	8000	< 0.31 U	6.3	41	0.39	< 0.033 U	2600	9.8		7.5	17	18000
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	7600	0.38 J	5.2	38	0.32	0.038 J	8800	8.4		5.6	15	14000
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	7400	< 0.25 U	6.6	44	0.34	< 0.027 U	950	9.3		5.6	18	16000
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	7400	0.57 J	6.3	51	0.38	0.040 J	2800	8.6		6.0	28	16000
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	6800	0.89	6.5	60	0.41	0.051 J	2800	9.0		7.0	33	17000
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	7500	< 0.22 U	6.4	46	0.35	0.050 J	960	8.9		7.5	19	16000
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	7600	< 0.42 U	7.3	57	0.37 J	< 0.044 U	1000	9.3		6.0	20	17000
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	7500	0.40 J	6.1	52	0.37	0.034 J	2700	10		6.8	28	16000
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	6600	0.87 J	6.1	49	0.28 J	< 0.073 U	14000	8.2		5.3	28	16000 B
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	10000	< 0.31 U	6.0	32	0.37 J	< 0.076 U	2100	11		7.0	14	18000
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	12000	< 0.29 U	6.4	33	0.43	< 0.071 U	850	13		7.8	13	20000
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	8000	< 0.28 UT	6.7 T	44 T	0.33 JT	< 0.067 UT	2700 T	10 T		6.6	19 T	18000
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	8400	< 0.32 U	5.8	30	0.33 J	< 0.078 U	3800	9.4		5.6	16	16000
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	3200	0.53 J	3.2	35	0.14 J	< 0.079 U	9900	7.5		2.7 J	45	11000
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	9100	1.4	7.8	93	0.40 J	0.19 J	9500	16		7.5	200	29000
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	5100	1.3	3.5	32	0.23 J	0.11 J	900	7.2		3.5 J	35	10000
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	4100	< 0.28 U	2.6	17 J	0.15 J	0.078 J	860	5.1		3.3 J	16	8700
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	2700	0.46 J	2.4	18 J	< 0.12 U	< 0.084 U	1900	3.7		2.0 J	13	7600
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	3100	< 0.30 U	2.1	13 J	< 0.11 U	< 0.072 U	900	3.6		2.4 J	9.9	6800
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	9000 T	< 0.25 UT	5.8 T	26 T	0.36 T	< 0.060 UT	770 T	11 T		6.7 T	14 T	17000 T
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	9500	0.26 J	4.1	59	0.35	< 0.053 U	2400	10		5.6	11	14000
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	7000	< 0.21 U	5.6	68	0.31	0.062 J	1300	7.7		4.4	20	13000
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	10000	< 0.21 U	6.3	34	0.41	< 0.052 U	980	11		8.0	15	19000
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	6900	1.4	7.2	66	0.33	0.14 J	13000	8.7		6.2	88	17000
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	5800	1.7	7.2	59	0.33	0.073 J	16000	7.7		5.5	54	16000
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	8400	2.1	7.5	170	0.39	< 0.056 U	2200	14		7.5	37	45000
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	7300	0.35 J	5.3	79	0.32	0.068 J	7200	9.1		5.2	29	15000
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	6900	0.73	6.0	67	0.35	0.079 J	15000	8.9		5.8	43	18000
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	6200	< 0.18 U	4.4	32	0.25	< 0.042 U	630	6.7		5.1	14	13000
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	7200	< 0.22 U	5.2	35	0.30	< 0.054 U	590	8.1		7.6	14	15000
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	8800	0.71 J	5.8	64	0.38	< 0.059 U	2000	11		6.4	35	17000
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	9000	0.20 J	3.8	51	0.33	< 0.047 U	790	9.2		5.1	10	13000
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	5600	1.3 J	11	68	0.27 J	< 0.061 U	10000	16		11	66	67000
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	6700	0.29 J	4.5	55	0.28 J	0.058 J	6300	7.9		4.7	29	14000
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	7800	< 0.24 UT	5.2 T	32 T	0.32 T	< 0.057 UT	1000 T	8.6 T		7.4 T	12 T	14000
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	6000	< 0.25 U	5.4	67	0.29 J	0.080 J	16000	7.5		6.1	33	17000
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	6400	0.26 J	6.5	51	0.28	0.053 J	4500	8.3		5.5	150	14000
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	9100	0.34 J	7.4	47	0.37	0.059 J	9700	11		7.5	25	19000
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	8000	0.29 J	6.5	24	0.36	< 0.058 U	540	8.8		7.3	17	16000
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	7400	0.27 J	5.8	53	0.36	< 0.053 U	440	8.6		6.9	15	15000
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	7900	< 0.23 U	7.1	41	0.37	< 0.057 U	680	9.3		7.4	17	17000
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	13000	0.39 J	9.2	44	0.52	< 0.051 U	930	14		10	19	23000
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	8500	1.7	6.8	93	0.39	0.11 J	4200	17		7.2	310	21000
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	9400	0.65 J	9.6	84	0.73	< 0.10 U	2900	13		12	41	18000
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	10000	< 0.25 U	5.6	53	0.35	< 0.060 U	2100	25		8.0	16	17000
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	920	0.29 J	3.7	33	0.22 J	< 0.071 U	1100	11		2.6 J	17	15000
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	7800	2.1	9.6	110	0.39	0.17 J	7700	16		7.7	140	23000
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	7700	0.65 J	6.8	100	0.38	0.16 J	6500	13		7.1	46	17000
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	7500	< 0.20 U	4.7	38	0.31	< 0.048 U	1100	8.4		5.3	19	14000
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	8600	< 0.20 U	6.0	36	0.36	< 0.050 U	730	9.4		6.8	16	15000
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	7000	< 0.26 U	5.7	28	0.31 J	< 0.062 U	810	8.2		6.8	16	15000
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	7100	< 0.26 UT	6.6 T	81 T	0.37 T	0.16 JT	1600 T	8.2 T		7.6	22 T	15000
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	7000	1.0	5.7	45	0.36 J	< 0.076 U	2100	8.5		6.6	21	15000
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	7000	< 0.31 U	5.6	45	0.27 J	< 0.076 U	3200	8.7		6.6	15	16000
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	11000	< 0.30 U	6.5	49	0.44	< 0.074 U	1200	12		8.6	17	18000
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	7800	0.42 J	6.4	62	0.35 J	< 0.077 U	3600	9.6		8.0	22	16000
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	7900	< 0.29 U	7.0	29	0.39	< 0.070 U	880	10		7.9	20	19000
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	6900	< 0.24 U	5.6	29	0.31 J	0.074 J	1500	10		6.5	18	15000
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	6300	0.68 J	5.9	50	0.37 J	< 0.081 U	1500	8.4		5.9	32	14000
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	5500	< 0.22 U	4.2	55	0.26 J	0.080 J	2900	6.7		5.2	24	12000
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	6900	< 0.25 U	5.7	65	0.31 J	0.10 J	6800	11		6.1	32	15000
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	7800	3.2 T	9.0 T	95 T	0.41 T	0.14 JT	5800 T	14 T		9.0 T	120 T	27000 T
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	7800	1.3	7.8	170	0.44	0.21 J	2700	12		5.4	120	22000 B
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	7900	< 0.30 U	5.2	50	0.36 J	< 0.072 U	1200	8.9		6.1	18	15000
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	8700	< 0.31 U	5.4	57	0.37 J	< 0.076 U	980	9.3		6.1	14	15000
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	9400	< 0.23 U	4.5	76	0.38	< 0.056 U	1200	9.3		5.8	12	15000
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	7900	< 0.22 U	7.2	40	0.29	< 0.053 U	450	15		5.4	25	19000
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	9500	0.27 J	5.6	19	0.27 J	< 0.052 U	990	23		6.3	22	18000
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	10000	0.38 J	8.6	31	0.36	< 0.063 U	520	22		5.7	28	22000
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	5300	3.7	6.8	31	0.35	< 0.052 U	1200	41		5.5	68	16000
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	5800	2.0	7.1	24	0.18 J	< 0.062 U	3100	56		4.2 J	73	16000
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	6500	0.63 J	6.9	65	0.45	0.14 J	2500	10		6.0	41	19000 B
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	7900	0.47 J	5.5	85	0.34	< 0.061 U	1700	8.2		5.4	23	15000 B

DRAFT

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	16	2200	320	0.063	17	470	0.45 J	< 0.077 U	< 44 U		< 0.23 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	9.4	2300	370	0.017 J	16	610	< 0.46 U	< 0.095 U	< 54 U		< 0.29 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	11	2400	260	0.16 B	14	440	< 0.29 U	< 0.060 U	< 35 U		< 0.18 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	9.8	1800	240	0.031 BJ	14	500	< 0.38 U	< 0.077 U	< 44 U		< 0.23 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	21	1900	330	0.061 B	15	500	0.57 J	< 0.069 U	< 40 U		< 0.21 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	45	1800	360	0.21 B	18	480	0.58 J	< 0.065 U	< 37 U		< 0.20 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	17	1800	430	0.035 BJ	17	460	< 0.34 U	< 0.069 U	< 40 U		< 0.21 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	6.8	1900	350	0.026 BJ	17	640	< 0.63 U	< 0.13 U	< 74 U		< 0.20 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	21	1800	320	0.11 B	20	480	< 0.31 U	< 0.064 U	< 37 U		< 0.19 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	29	5500	480	0.072	12	490	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	9.7	2600	190	0.030 J	16	630	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	9.0	2800	180	0.031 J	17	820	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	9.8	2100 T	360 T	0.046	19 T	750 T	< 0.42 UT	< 0.095 UT	< 47 UT		< 0.26 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	7.0	2400	230	0.020 J	15	730	0.56 BJ	< 0.11 U	< 55 U		< 0.30 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	31	1200	160	0.36	14	290 J	0.56 BJ	< 0.11 U	< 55 U		0.36 J
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	98	3000	450	0.36	37	770	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	30	1200	140	0.051	18	380 J	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	100	1200	120	0.49	9.7	280 J	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	37	810	110	0.21	6.6	270 J	< 0.53 U	< 0.12 U	< 59 U		0.33 J
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	49	850	87	0.12	7.1	210 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	7.7 T	2300 T	170	< 0.016 UT	14 T	550 T	0.62 JT	< 0.085 UT	< 42 UT		< 0.23 UT
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	13	2100	230	0.057	13	530	0.46 J	< 0.075 U	46 J		< 0.20 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	91	1400	410	0.31	11	430	0.81	< 0.072 U	< 35 U		< 0.20 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	9.2	2300	270	0.025 J	16	620	0.37 J	< 0.074 U	< 36 U		< 0.20 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	87	2300	360	0.074	77	580	< 0.32 U	< 0.071 U	84 J		< 0.19 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	82	2200	310	0.081	17	510	0.54 J	< 0.068 U	82 J		< 0.19 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	20	1600	660	0.076	15	610	0.81	< 0.079 U	46 J		< 0.22 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	31	2600	300	0.12	15	390	< 0.29 U	< 0.066 U	41 J		< 0.18 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	41	4100	310	0.089	25	510	0.57 J	< 0.067 U	61 J		< 0.18 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	7.9	1600	310	0.023 J	11	350	0.32 J	< 0.060 U	< 30 U		< 0.16 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	8.0	2000	400	0.017 J	14	470	0.44 J	< 0.077 U	< 38 U		< 0.21 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	25	2100	330	0.081	15	530	0.70 J	< 0.084 U	< 41 U		< 0.23 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	7.5	1800	360	< 0.024 U	12	480	0.45 J	< 0.067 U	< 33 U		< 0.18 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	43	1700	500	0.21	22	430	0.68 J	< 0.086 U	53 J		< 0.23 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	21	2200	210	0.13	13	520	< 0.35 U	< 0.078 U	51 J		< 0.21 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	9.8 T	1900	360 T	0.065	12	500 T	< 0.36 UT	< 0.081 UT	< 40 UT		< 0.22 UT
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	36	4900	370	0.43	20	500	0.40 J	< 0.086 U	63 J		< 0.23 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	15	2900	400	0.15	13	570	< 0.31 U	< 0.071 U	< 35 U		< 0.19 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	31	2600	310	0.10	18	570	0.49 J	< 0.074 U	42 J		< 0.20 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	8.5	2000	310	0.035	14	480	< 0.36 U	< 0.082 U	< 40 U		< 0.22 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	8.7	1800	390	0.027	16	580	< 0.33 U	< 0.075 U	< 37 U		< 0.20 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	9.3	2000	440	0.032	16	620	< 0.36 U	< 0.080 U	< 40 U		< 0.22 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	12	3000	230	0.036 J	21	880	0.56 J	< 0.073 U	43 J		< 0.20 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	39	2400	360	0.089	160	740	0.54 J	< 0.083 U	85 J		< 0.23 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	80	1700	420	0.17	20	620 J	1.1 JT	< 0.15 U	< 72 U		< 0.40 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	8.4	4000	290	< 0.021 U	20	1100	< 0.38 UT	< 0.086 U	57 J		< 0.23 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	6.7	78 J	9.3	0.22	9.6	230 J	0.79 JT	< 0.10 U	120 J		< 0.27 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	140	2700	400	0.26	36	650	0.44 JT	< 0.097 U	69 J		< 0.27 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	81	2800	520	0.11	37	670	0.65 JT	< 0.088 U	59 J		< 0.24 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	28	1500	190	0.055	13	340	0.43 JT	< 0.068 U	< 34 U		< 0.19 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	7.8	1800	200	< 0.019 U	15	420	< 0.31 UT	< 0.070 U	< 35 U		< 0.19 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	8.4	1700	250	< 0.023 U	14	440	< 0.39 UT	< 0.088 U	< 43 U		< 0.24 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	14	1800	2100 T	0.063	15 T	520 T	0.86 JT	< 0.18 UT	< 44 U		< 0.49 UT
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	15	1800	370	0.020 J	14	600	0.52 JT	< 0.11 U	< 53 U		< 0.30 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	8.2	2500	270	< 0.024 U	15	680	< 0.48 UT	< 0.11 U	< 53 U		< 0.29 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	10	2600	250	< 0.023 U	17	720	< 0.46 UT	< 0.10 U	< 51 U		< 0.28 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	43	2100	330	0.19	15	640	0.70 JT	< 0.11 U	< 54 U		< 0.30 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	10	2000	400	< 0.022 U	18	660	< 0.44 UT	< 0.10 U	< 49 U		< 0.27 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	9.3	1800	280	< 0.016 U	14	460	< 0.37 UT	< 0.083 U	< 41 U		< 0.23 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	20	1600	290	0.037	13	590	< 0.51 UT	< 0.12 U	< 57 U		< 0.32 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	37	1600	420	0.12	12	400	0.43 JT	< 0.074 U	37 J		< 0.20 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	48	2300	320	0.095	15	560	0.41 JT	< 0.087 U	48 J		< 0.24 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	66 T	2600 T	470 T	0.093	30 T	830 T	0.52 J	< 0.083 UT	100 JBT		< 0.23 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	62	1400	500	0.082	13	820	0.72 J	< 0.094 U	100 BJ		< 0.26 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	9.9	2200	390	< 0.024 U	15	530	< 0.45 U	< 0.10 U	62 BJ		< 0.28 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	9.9	2000	360	0.025 J	14	520	< 0.47 U	< 0.11 U	79 BJ		< 0.29 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	9.3	1900	240	0.042	13	520	< 0.35 U	< 0.079 U	58 BJ		< 0.22 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	14	2100	260	< 0.019 U	27	540	< 0.33 U	< 0.075 U	< 37 U		< 0.21 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	15	2400	200	0.025 J	150	650	0.35 J	< 0.073 U	< 36 U		< 0.20 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	13	2300	200	< 0.019 U	120	660	0.80 J	< 0.089 U	< 44 U		< 0.24 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	22	1700	120	0.088	910	630	0.55 J	0.078 J	39 J		< 0.20 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	12	2300	120	0.043	850	620	0.44 J	< 0.088 U	< 44 U		< 0.24 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	41	1400	480	0.076	14	590	0.78	< 0.069 U	42 J		< 0.19 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	23	1600	490	0.048	13	500	0.75 J	< 0.086 U	< 42 U		< 0.23 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated		14	64
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated		14	51
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated		12	39
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated		14	41
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated		13	48
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated		14	58
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated		13	45
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated		13	48
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated		13	48
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated		12	51
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated		14	45 B
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated		16	46
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated		14 T	51 BT
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated		14	42 B
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated		6.2	61 B
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated		17	160 B
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated		7.8	73 B
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated		7.9	42 B
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated		4.7 J	25 B
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated		5.7	25 B
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated		15 T	42 T
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated		13	42
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated		12	51
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated		16	46
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated		13	100
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated		12	60
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated		25	46
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated		12	62
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated		11	65
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated		9.2	37
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated		11	39
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated		14	62
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated		13	38
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated		52	71
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated		12	54
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated		13 T	33 T
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated		10	67
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated		11	64
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated		16	60
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated		13	41
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated		12	48
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated		13	46
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated		19	52
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated		14	98
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated		16	72
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated		27	42
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated		8.3	6.7
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated		14	190
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated		12	72
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated		13	41
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated		15	38
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated		13	70
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated		11 T	44 T
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated		12	39
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated		9.4	40
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated		15	44
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated		12	55
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated		18	50
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated		14	43
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated		12	47
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated		8.3	53
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated		11	65
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated		20 T	100 T
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated		18	94
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated		12	48
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated		12	40
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated		13	37
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated		14	51
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated		15	42
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated		17	58
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated		12	96
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated		11	160
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated		16	79
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated		12	48

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	5600	6.0	9.1	38	0.23 J	< 0.051 U	5400	72		7.0	950	31000 B
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	8800	0.70 J	6.5	32	0.39	< 0.055 U	1100	10		8.5	39	17000
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	5300	< 0.30 U	5.5	64	0.23 J	0.074 J	23000	8.4		4.9	23	13000
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	6800 T	< 0.33 UT	5.7	46 T	0.32 J	< 0.079 U	830	10		5.9	35 T	15000
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	9800	< 0.31 U	8.9	45	0.44	< 0.074 U	820	14		7.4	81	22000
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	11000	< 0.31 U	8.6	43	0.41	< 0.075 U	1000	14		8.0	46	22000
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	9100	< 0.29 U	8.7	39	0.35 J	< 0.071 U	750	14		6.0	35	21000
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated			9	< 66.6 U	< 0.6 U	< 0.6 U		6.3			32.5	
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated	8600	2.2	7.4	230	0.5	0.25 J	28000	15		6.9	81	21000
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated	5800	< 0.37 U	4.4	42	0.26 J	0.095 J	7200	10		6.3	43	17000
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated	5400	< 0.38 U	8.4	42	0.28 J	0.11 J	23000	8.3		4.9 J	22	16000
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated	5400	0.66 J	8.8	350	0.37 J	0.28 J	14000	26		6.8	120	27000
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated	8300	0.42 J	12	170	0.5	0.43 J	16000	25		10	560	41000
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated	8200	< 0.37 U	6.2	120	0.37 J	0.15 J	37000	12		6.1	45	19000
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated	7700	< 0.4 U	6.7	49	0.36 J	0.055 J	5500	11		6.9	21	18000
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated	7300	< 0.38 U	3.6	34	0.28 J	0.051 J	1500	8.9		4.4 J	21	18000
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated	7800	< 0.42 U	5.9	68	0.35 J	0.078 J	10000	11		6.7	24	18000
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated	6800	< 0.37 U	5.2	33	0.25 J	0.071 J	21000	8.9		6.1	26	16000
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated	10000	< 0.38 U	8.8	67	0.46	0.11 J	3300	12		9.3	25	21000
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated	8200	0.57 J	7.9	75	0.36 J	0.2 J	1800	24		7.2	440	23000
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	9100	< 0.39 U	6.1	76	0.36 J	0.089 J	12000	11		6.8	22	19000
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated	7500	< 0.37 U	6.7	43	0.31 J	0.048 J	1100	12		6.5	240	18000
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated	6000	3.4	19	60	0.38 J	0.19 J	950	32		7.1	720	49000
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	6800	< 0.4 U	7.3	40	0.3 J	0.06 J	2400	9.4		5.9	19	16000
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated	7100	< 0.38 U	6.5	48	0.31 J	0.062 J	980	9.5		6.8	26	17000
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated	8900	< 0.38 U	5.5	43	0.36 J	0.051 J	1800	12		8.1	34	20000
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated	6300	< 0.41 U	6.1	53	0.25 J	0.05 J	1800	8.4		4.8 J	25	15000
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	6800	< 0.38 U	6.6	68	0.34 J	0.11 J	2000	10		5.9	37	21000
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated	6800	< 0.4 U	7.2	47	0.32 J	0.15 J	2800	14		5.8 J	33	18000
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated	8800	< 0.41 U	6.1	58	0.36 J	0.17 J	3600	17		6.9	36	20000
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated	9900	< 0.38 U	5.8	58	0.41 J	0.07 J	1200	13		8.1	21	20000
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated	8300	0.4 J	4.7	53	0.31 J	< 0.042 U	38000	9.5		5.8	26	15000
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated	5100	0.49 J	3.9	67	0.24 J	0.11 J	1200	8.8		3.4 J	22	14000
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated	7700	0.44 J	6.5	54	0.34 J	< 0.04 U	4600	18		7.5	64	23000
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated	11000	1.9	17	150	0.64	< 0.051 U	3800	16		9.8	53	23000
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated	8100	< 0.39 U	6.4	90	0.75	0.14 J	3900	11		8.7	41	23000
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated	6600	0.69 J	6.9	68	0.36 J	0.32 J	10000	18		6.6	41	20000
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated	8500	0.44 J	5.1	85	0.35 J	< 0.041 U	1500	13		5.9	20	18000
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated	5800	< 0.38 U	5.5	42	0.29 J	< 0.04 U	1200	8.5		5.8	19	15000
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated	6700	< 0.44 U	6.7	32	0.3 J	< 0.048 U	5500	9.4		7.6	21	17000
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated	7400	< 0.36 U	8.6	63	0.3 J	0.14 J	42000	12		6.6	29	19000
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated	5100	< 0.36 U	4.4	37	0.23 J	0.064 J	44000	8.4		4.8 J	19	14000
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated	5900	< 0.41 U	7.1	38	0.28 J	0.11 J	25000	9.7		6.2	20	17000
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated	12000	6	7	160	0.49 J	1.1	4700	14		9.6	45	34000
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated	8400	< 0.41 U	6.8	51	0.28 J	0.079 J	21000	19		5.3 J	270	28000
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated	6700	3.3	10	230	0.26 J	< 0.082 U	94000	37		8.3	260	88000
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated	7400	4.3	7.1	70	0.37 J	0.1 J	3700	15		6.7	120	20000
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated	8700	< 0.37 U	5.6	190	0.33 J	0.14 J	16000	13		7.4	24	21000
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated	4600	< 0.37 U	17	54	0.24 J	0.14 J	65000	8.5		5 J	31	12000
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated	5000	< 0.38 U	5.9	53	0.19 J	0.089 J	43000	7.9		4.3 J	31	12000
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated	8000	0.52 J	7.6	72	0.38 J	0.048 J	1100	9.4		5.8	22	18000
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated	8900	< 0.4 U	7.5	58	0.45 J	0.079 J	1500	11		9.5	22	20000
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated	7400	< 0.39 U	6.9	46	0.35 J	0.093 J	1500	10		6.9	22	18000
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated	9400	3.5	8.4	130	0.43 J	0.24 J	4800	42		9.7	170	34000
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated	10000	3.7	6.9	140	0.45 J	0.27 J	2000	15		7.7	240	27000
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated	5400	95 J	43 J	53	0.28 J	0.29 J	2300 J	45		31	9300 J	200000 J
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated	6600	49 J	16 J	73	0.34 J	0.3 J	4000 J	36		20	2600 J	95000 J
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated	9700	< 0.41 U	3.5	65	0.4 J	0.11 J	1400	13		6.9	24	18000
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated	7600	< 0.4 U	6.5	67	0.36 J	0.29 J	11000	20		7.4	150	27000
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	9600	0.40 J	5.1	74	0.40 J	0.082 J	1600	12		7.2	24	18000
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated	7400	< 0.38 U	5.8	120 J	0.3 J	0.14 J	1700 J	10		6.3	37 J	17000
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated	6300	< 0.41 UJ	5	38	0.28 J	0.12 J	6300 J	8.2		5.6 J	24 J-	15000
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated	10000	< 0.38 UJ	6.2	95	0.42 J	< 0.041 UJ	2400	17 J+		7.4	41	21000
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated	9900	0.46 J	8.7	70 J	0.41	0.2 J	3300 J+	14		6.5	28 J+	19000
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated	7000	< 0.33 U	6.2	76	0.34 J	0.093 J	5100	8.8		6.0	24	15000
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated	6900	< 0.21 U	5.9	77	0.30	0.11 J	8000	9.0		6.0	26	15000
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated	7900	< 0.24 U	11	170	0.34	0.19 J	14000	14		7.0	35	20000
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	9900	< 0.32 UT	11	360 T	0.45	0.41 J	2100 T	11 BT		7.5	43 T	23000
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	6600	< 0.21 U	4.4	59	0.28	0.091 J	900	7.7 B		6.0	15	17000
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated	7800	< 0.38 U	5.9	57	0.35 J	0.2 J	21000	15		7.1	48	19000
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated	8200	0.69 J	5.7	99	0.33 J	0.17 J	34000	15		6.9	44	20000
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated	6800	< 0.33 U	6.4	59	0.31 J	0.22 J	17000	22		5.5	40	43000
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated	7000	0.96 J	6.4	59	0.32 J	0.08 J	3900 J-	10		5.8	25	15000
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated	7000	< 0.31 U	5	82	0.29 J	0.052 J	3300	9.3		5.7	16	14000

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	130	2000	320	0.028 J	17	370	2.1	0.31 J	< 35 U		< 0.20 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	19	2200	340	0.045	15	510	0.35 J	< 0.078 U	< 38 U		< 0.21 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	17	4600	300	1.0	53	490	< 0.45 U	< 0.10 U	52 J		< 0.28 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	13	1900 T	590 T	0.021 J	140 T	640 T	< 0.50 U	< 0.11 UT	< 55 U		< 0.31 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	22	2500	230	< 0.019 U	200	710	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	22	2600	290	< 0.020 U	65	710	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	21	2300	330	< 0.018 U	30	660	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	64			0.21	11.9		1.4	< 1.19 U			
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated	89	3500	620	0.11	170		0.71 J	0.22 J	340 J		< 0.26 U
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated	13	2800	460	0.039	21		< 0.56 U	< 0.11 U	52 J		< 0.23 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated	26	13000	740	0.038	14		< 0.57 U	< 0.12 U	110 J		< 0.23 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated	480	2900	410	0.15	58		1.1 J	< 0.13 U	97 J		< 0.26 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated	260	2900	480	0.15	110		1.1	< 0.12 U	250 J		< 0.23 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated	62	3700	640	0.03 J	32		< 0.56 U	< 0.12 U	180 J		< 0.23 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated	12	2800	400	0.022 J	18		< 0.6 U	< 0.12 U	60 J		< 0.25 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated	11	2300	250	0.021 J	13	440 J	< 0.57 U	< 0.12 U	50 J		< 0.23 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated	1200	2300	390	0.11	17	670	< 0.64 U	< 0.13 U	66 J		< 0.26 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated	11	7100	500	0.081	15	620	< 0.56 U	< 0.11 U	78 J		< 0.23 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated	22	3000	780	< 0.008 U	20	940	< 0.57 U	< 0.12 U	44 J		< 0.23 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated	70	2600	280	0.049	450		< 0.65 U	< 0.13 U	78 J		< 0.26 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	14	2700	590	0.089	18	840	< 0.59 U	< 0.12 U	85 J		< 0.24 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated	20	2300	310	0.018 J	130		< 0.57 U	< 0.12 U	55 J		< 0.23 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated	120	1400	400	0.04	770		1.9	0.46 J	59 J		0.31 J
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	10	1800	410	0.043	13	750	< 0.61 U	< 0.12 U	54 J		< 0.25 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated	9.6	2000	820	0.021 J	17		< 0.57 U	< 0.12 U	44 J		< 0.23 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated	15	2900	440	0.05	20		< 0.58 U	< 0.12 U	50 J		< 0.24 U
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated	14	1900	490	0.045	13		< 0.63 U	< 0.13 U	44 J		< 0.25 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated	20	2100	660	0.019 J	16		< 0.57 U	< 0.12 U	50 J		< 0.23 U
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated	58	2100	370	0.021 J	31		< 0.61 U	< 0.12 U	68 J		< 0.25 U
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated	34	2700	400	0.019 J	37		< 0.62 U	< 0.13 U	63 J		< 0.25 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated	13	2600	410	< 0.0086 U	19		< 0.57 U	< 0.12 U	47 J		< 0.23 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated	27	3900	310	0.061	20	680	< 0.59 U	< 0.12 U	110 J		0.32 J
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated	47	1000	180	1.6	15	340 J	< 0.6 U	< 0.12 U	35 J		< 0.24 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated	44	2100	420	0.055	33	620	< 0.56 U	< 0.11 U	87 J		0.4 J
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated	150	2000	660	0.28	17	1000	1.3 J	< 0.15 U	140 J		0.75 J
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated	35	2000	510	0.094	23		< 0.6 U	< 0.12 U	75 J		< 0.24 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated	150	2700	460	0.033 J	170		< 0.63 U	< 0.13 U	87 J		< 0.26 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated	34	1700	770	0.084	13	610	< 0.58 U	< 0.12 U	42 J		0.37 J
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated	9.4	1700	350	0.0098 J	13		< 0.57 U	< 0.12 U	33 J		0.3 J
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated	9.7	2900	320	< 0.0097 U	17	910	< 0.67 U,^	< 0.14 U	50 J		0.4 J
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated	56	6900	460	0.016 J	19	720	< 0.54 U	< 0.11 U	71 J		< 0.22 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated	6.5	6700	340	< 0.0082 U	13	650	< 0.55 U	< 0.11 U	66 J		< 0.22 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated	8.5	6300	380	< 0.009 U	16	810	< 0.62 U	< 0.13 U	59 J		< 0.25 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated	370	2400	1400	0.047	18		< 0.72 U	< 0.15 U	100 J		< 0.29 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated	41	3000	270	0.032 J	200		< 0.62 U	< 0.13 U	150 J		< 0.25 U
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated	160	3100	700	0.034 J	21		0.94 J	0.21 J	1200		< 0.47 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated	67	2100	510	< 0.0091 U	110		< 0.59 U	< 0.12 U	56 J		< 0.24 U
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated	31	4400	920	0.038	20	820	0.65 J	< 0.12 U	98 J		< 0.35 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated	9.8	9600	380	< 0.016 U	18	560	1.2	< 0.12 U	99 J		< 0.35 U
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated	6.2	10000	390	< 0.011 U	11	540 J	< 0.57 U	< 0.12 U	77 J		< 0.36 U
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated	12	1900	360	< 0.011 U	16	720	< 0.6 U	< 0.12 U	33 J		< 0.37 U
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated	11	2500	610	< 0.014 U	19	840	< 0.61 U	< 0.12 U	67 J		< 0.38 U
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated	99	2400	510	< 0.014 U	19	660	< 0.6 U	< 0.12 U	42 J		< 0.37 U
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated	930	2200	470	0.062	45	700	< 0.65 U	< 0.13 U	87 J		< 0.4 U
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated	110	2300	560	0.17	130	700	< 0.64 U	< 0.13 U	100 J		< 0.4 U
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated	940 J	1200 J	1200	0.13 J	220	500 J	2.7 J	5.2 J	63 J		0.77 J
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated	330 J	2100 J	820	0.24 J	220	670	1.1 J	1.5 J	56 J		0.57 J
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated	47	2400	590	0.17	17	640	< 0.62 U	< 0.13 U	72 J		< 0.39 U
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated	110	2700	760	0.052	26	590	< 0.6 U	< 0.12 U	70 J		< 0.37 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	15	2400	400	0.043	18	560	< 0.58 U	< 0.12 U	62 J		< 0.36 U
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated	23 J	2300	460	< 0.014 U	19		< 0.58 U	< 0.12 U	54 J		< 0.36 U
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated	7.6	2700 J-	500	< 0.018 U	14	660 J	< 0.63 U	< 0.13 U	66 J		< 0.39 U
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated	42 J	2700	620 J	< 0.016 UJ	54 J	750	< 0.58 U	< 0.12 U	< 67 U		< 0.36 U
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated	20 J	2600 J-	350 J	0.028 J	29 J	820	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated	34	2700	360	0.047	16	590	< 0.50 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated	33	3400	390	0.036	19	630	0.42 J	< 0.064 U	110 J		< 0.19 U
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated	61	3300	460	0.033 J	23	610	0.43 J	< 0.074 U	110 J		< 0.23 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	51	2600	580 T	0.26	31 T	730	< 0.48 U	< 0.099 U	< 57 U		< 0.30 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	14	1900	380	0.031	18	410	< 0.32 U	< 0.066 U	< 38 U		< 0.20 U
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated	26	4200	410	0.037	23	940	< 0.57 U	< 0.12 U	85 J		< 0.36 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated	42	5300	450	0.062	24	810	0.71 J	< 0.096 U	150 J		< 0.29 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated	52	2200	420	1.1	49	740	0.76 J	3.5	110 J		< 0.31 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated	22	1900	470	0.023 J	16	670	< 0.59 U	< 0.12 U	530 J		< 0.37 U
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated	8.7	1900	340	0.032	15	700	< 0.48 U	< 0.097 U	< 56 U		< 0.3 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated		14	58
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated		13	41
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated		8.3	54
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated		11	62 T
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated		16	380
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated		17	85
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated		16	64
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	-	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated			62.1
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated		20	190
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated		10	67
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated		12	46
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated		17	330
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated		19	230
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated		11	100
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated		13	50
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated		10	45
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated		12	60
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated		11	51
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated		16	87
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated		15	1000
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated		12	60
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated		11	120
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated		19	220
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated		12	49
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated		11	51
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated		12	56
Football Field	SSHS-B2143	072618 08:50_PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated		9.1	48
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated		11	59
Football Field	SSHS-B2194	072618 08:50_PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated		11	87
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated		14	85
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated		15	66
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated		13	54
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated		8.9	57
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated		15	76
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated		21	120
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated		13	86
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated		11	170
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated		21	57
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated		11	44
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated		13	61
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated		13	75
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated		8.6	41
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated		13	50
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated		17	930
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated		14	90
Football Field	SSHS-B2190	072818 11:30_SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated		20	190
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated		13	110
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated		13	76
Football Field	SSHS-B2773	051519 08:45_SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated		8.7	110
Football Field	SSHS-B2774	051519 08:45_SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated		8.6	52
Football Field	SSHS-B2777	052119 08:40_SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated		13	53
Football Field	SSHS-B2778	052119 08:40_SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated		14	61
Football Field	SSHS-B2779	052119 08:40_SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated		12	60
Football Field	SSHS-B2786	052119 08:40_SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated		32	840
Football Field	SSHS-B2787	052119 08:40_SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated		18	1400
Football Field	SSHS-B2788	052119 08:40_PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated		72 J	660
Football Field	SSHS-B2788	052119 08:40_SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated		35 J	540
Football Field	SSHS-B2789	052219 08:40_SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated		13	53
Football Field	SSHS-B2790	052219 08:40_SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated		12	130
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated		14	61
Football Field	SSHS-IRM3-S097	080319 09:30_SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated		11 J	67
Football Field	SSHS-B3094	083119 10:15_SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated		11	56
Football Field	SSHS-B2942	110719 09:00_DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated		16	79
Football Field	SSHS-B2942	110719 09:00_SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated		15	57 J+
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated		11	55
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated		11	61
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated		12	87
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated		15 T	410
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated		10	69
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated		12	74
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated		15	84
Football Field	SSHS-B3464	072820 09:00_SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated		14	90
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated		12	71 J-
Football Field	SSHS-B3473	072820 09:00_SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated		11	45

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated	7900	0.32 J	5.8	99	0.33 J	0.14 J	11000	13		6.4	49	18000
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated	8300	< 0.22 UT	5.3	27 T	0.37	0.053 J	590	9.6		6.7	19 T	20000
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated	9700	0.43 J	5.7	59	0.39	0.12 J	5100	15		7.8	31	20000
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated	9600	< 0.27 U	6.8	60	0.38	0.087 J	2000	12		8.3	23	21000
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated	7900	0.51 J	6.1	150	0.36 J	0.15 J	13000	15		6.6	44	20000
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated	8000	0.33 J	5.9	94	0.33	0.14 J	13000	14		6.1	38	19000
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated	6500	< 0.41 U	7.6	37	0.33 J	0.11 BJ	1200	8.4		6.7	21	17000
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated	6900	< 0.37 UT	9.0	290 T	0.33 J	0.24 J	24000	47 T		6.5	62	24000 T
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated	7100	0.55 J	6.8	150	0.31 J	0.38 J	18000	14		7.0	94	22000
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated	7800	< 0.36 U	6.8	94	0.30 J	0.15 J	21000	14		7.3	46	20000
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated	6700	< 0.40 U	6.3	81	0.29 J	0.14 J	24000	9.9		5.9	50	19000
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated	6700	< 0.32 U	6.1	96	0.25 J	0.18 J	28000	15		6.1	56	17000
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated	6500	< 0.36 U	6.0	48	0.29 J	0.062 J	780	8.5		5.5	18	17000
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated	5400	6.5	6.2	67	0.28 J	0.10 J	5900	7.3		5.4	26	14000
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated	5600	< 0.31 U	5.6	51	0.26 J	0.082 J	2200	7.3		4.8	18	14000
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	7000	0.73 J	6.8	54	0.32 J	0.15 J	3400	9.1		5.9	31	16000
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated	7200	1.1	9.6 T	110	0.40 J	0.21 J	12000	11		6.5	130	19000
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated	9700	0.67 J	7.5 T	88	0.41	0.14 J	8500	20		8.1	87	24000
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated	7200	1.2	7.4 T	65	0.32 J	0.14 J	6400	9.3		6.6	44	18000
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated	10000	1.5	6.2 T	48	0.37 J	0.10 J	1200	20		7.4	34	20000
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated	8900	0.70 J	9.5 T	200	0.43	0.17 J	1300	10		6.7	28	19000
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated	7900	0.56 J	8.2 T	760	0.36 J	0.17 J	1600	10		6.7	35	18000
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated	11000	1.9	7.6 T	110	0.44	0.16 J	14000	12		7.8	23	22000
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated	7900	0.53 JT	6.5	58 T	0.32 J	1.2	4200 T	9.9		6.8	23 T	18000
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated	7900	0.43 J	7.3	93	0.37	0.21 J	6900	11		7.4	41	18000
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated	7100	< 0.32 U	7.5	66	0.33 J	0.12 J	14000	8.5		6.3	24	19000
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated	11000	0.49 J	9.8	99	0.43	0.22 J	7300	15		9.7	41	25000
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated	11000	3.0	8.5	170	0.49	0.12 J	2400	14		5.8 J	21	19000
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated	9600	0.83 JT	4.7	100 T	0.35 J	0.10 J	12000 T	10		5.1 J	63	18000
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated	10000	0.46 J	6.6	100	0.41 J	0.18 J	1200	11		6.7	16	19000
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated	12000	0.61 J	5.1	78	0.40	0.15 J	1200	12		7.4	20	20000
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated	4500	< 0.35 U	4.0	26	0.20 J	0.064 J	1200	5.7		3.6 J	11	11000
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated	4000	< 0.36 U	3.4	26	0.19 J	0.044 J	640	5.5		3.2 J	9.5	10000
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated	10000	1.3	12	340	0.50	0.82	23000	36		8.7	99	49000
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated	8300	34	12	100	0.48	0.39 J	4300	21		15	100	87000
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated	7500	< 0.43 U	12	110	0.51	0.16 J	16000	9.6		4.7 J	21	29000
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated	3500	6.2	5.9	280	0.12 J	0.43 J	190000	8.2		4.2 J	53	23000
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated	3100	4.2	4.2	310	0.086 J	0.43 J	230000	8.0		3.8 J	34	23000
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated	6400	< 0.33 U	7.2	210	0.36 J	0.12 J	2300	10		6.6	25	16000
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated	6100	0.94 J	6.0	91	0.31 J	0.25 J	8400	10		5.9	62	17000
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated	9000	0.68 J	8.5	85	0.38	0.19 J	6400	12		8.7	37	21000
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated	9500	0.77 J	8.5	66	0.39	0.16 J	5400	12		8.6	44	21000
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated	7800	1.6	6.7	120	0.34 J	0.19 J	14000	12		6.5	64	21000
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated	6700	1.2	5.7	79	0.29 J	0.23 J	110000	10		5.3	39	14000
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated	7400	3.6 J	20	110	0.41 J	6.2	53000	18		9.0	230	130000
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated	11000	0.60 J	4.7	60	0.40	0.081 J	1500	11		5.1	20	17000
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated	9600	0.53 J	8.5	77	0.51	0.15 J	2700	12		9.6	39	24000 B
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated	8500	0.33 J	9.9	150	0.43	0.39 J	22000	14		6.5	66	20000
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated	6600	< 0.28 U	5.7	50	0.29 J	0.18 J	27000	8.8		5.5	26	16000
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated	7700	< 0.29 U	7.9	110	0.36	0.28 J	14000	12		7.3	76	20000
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated	6500	< 0.31 U	6.4	35	0.31 J	0.12 J	1300	8.1		5.7	21	15000
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated	6000	0.46 J	5.2	66	0.29 J	0.20 J	12000	9.8		5.1	87	18000 B
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated	6600	1.0	8.9	260	0.35 J	0.92	47000	30		6.0	210	25000
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated	10000	< 0.27 U	4.6	140	0.40	0.096 J	1800	11		5.4	33	19000
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated	9900	< 0.24 U	11	71	0.46	0.057 J	3800	13		9.4	21	22000
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated	8000	< 0.30 U	2.7	64	0.26 J	0.060 J	830	9.0		4.7	8.1	12000
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated	6500	< 0.26 U	4.3	200	0.25 J	0.096 J	2200	32		4.8	37	14000
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated	9200	< 0.21 U	4.2	66	0.33	0.077 J	610	11		6.4	17	17000
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated	6000	0.31 J	7.4	58	0.26 J	0.13 J	4400	11		5.5	76	15000
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated	7600	0.68 JT	5.3	230 T	0.29 J	0.24 J	4100 T	13		5.1	73	21000
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated	1600	< 0.27 U	2.7	42	0.063 J	0.14 J	1900	5.6		1.2 J	39	17000
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated	7900	0.56 J	8.5	58	0.39 J	0.079 J	850	9.3		7.0	25	18000
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated	10000	0.71 J	3.7	99	0.33 J	0.052 J	1200	11		5.7	12	16000
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated	10000	0.46 J	2.9	130	0.31 J	0.043 J	1400	9.3		4.4 J	9.5	14000
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated	7600	0.58 J	5.9	40	0.31 J	0.082 J	1300	9.3		5.6	23	17000
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated	9500	0.66 J	3.9	150	0.37 J	0.094 J	2100	9.5		5.4	13	18000
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated	7700	< 1.5 UT	6.7	99 T	0.52 J	< 0.16 U	1100 J	10		6.6	33 T	21000 T
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated	5200	0.51 J	7.8	42	0.31 J	0.13 J	830	7.8		9.0	36	18000 B
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated	6900	0.38 J	7.0	400	0.34	0.063 J	5200	9.5		7.3	17	18000 B
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated	5900	< 0.22 U	4.5	38	0.24 J	0.071 J	770	7.7		5.5	21	14000
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated	5800	0.22 J	4.9	34	0.24 J	0.061 J	1500	7.0		5.4	23	14000
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated	7100	< 0.32 U	7.2	51	0.33 J	0.072 J	1100	8.9		6.5	23	17000 B
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated	7300	2.1	8.0	160	0.36	0.16 J	3600	28		6.5	52	25000 B
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated	6500	< 0.28 UT	5.8	330 T	0.27 J	0.13 J	1300 T	8.4		6.2	25	16000 B

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated	120	3800	350	0.035	50	610	< 0.44 U	< 0.090 U	70 J		< 0.27 U
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated	9.8	2300	310	0.034	16	600	< 0.34 U	< 0.069 U	61 J		< 0.21 U
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated	23	3800	400	< 0.017 U	28	820	< 0.39 U	< 0.079 U	51 J		< 0.24 U
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated	13	3000	550	0.031	23	630	< 0.41 U	< 0.084 U	< 48 U		< 0.26 U
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated	160	3600	460	0.033 J	59	720	< 0.51 U	< 0.10 U	70 J		< 0.31 U
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated	130	3900	390	0.025 J	61	710	0.47 J	< 0.087 U	68 J		< 0.26 U
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated	8.2	2100	490	< 0.022 U	19	780	< 0.53 U	< 0.092 U	< 71 U		2.5
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated	120 T	3500	370	0.052 J	40	610	< 0.48 U	< 0.083 U	160 J		2.1
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated	99	3600	860	0.040 J	64	620	0.58 J	0.083 J	110 J		< 0.41 U
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated	38	3000	450	0.12	28	570	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated	41	3400	450	0.084 J	30	560	< 0.52 U	< 0.090 U	140 J		< 0.44 U
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated	45	4600	440	0.073 J	36	590	< 0.42 U	< 0.072 U	110 J		< 0.36 U
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated	9.4	1900	350	< 0.021 U	14	600	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated	350	1700	320	< 0.023 U	15	600	< 0.53 U	< 0.11 U	86 J		< 0.33 U
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated	13	2000	390	< 0.024 U	13	550	< 0.47 U	< 0.096 U	< 55 U		< 0.29 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	22	3000	450	< 0.021 U	19	770	< 0.52 U	< 0.11 U	68 J		0.67 J
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated	110	3000	350	0.42 T	22	850	0.73 J	< 0.12 U	180 J		< 0.37 U
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated	47	3500	450	0.026 J	42	820	0.58 J	< 0.10 U	83 J		< 0.32 U
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated	64	2300	270	0.083	20	700	< 0.51 U	< 0.11 U	96 J		< 0.32 U
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated	24	2500	300	0.29	110	700	< 0.60 U	< 0.12 U	120 J		< 0.37 U
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated	29	2100	360	0.034	21	950	< 0.50 U	< 0.10 U	< 59 U		< 0.31 U
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated	75	2200	370	0.052	21	860	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated	750	2900	420	0.023 J	21	850	< 0.52 U	< 0.11 U	150 J		< 0.33 U
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated	24 T	2300	390	0.049	19 T	600	< 0.51 U	< 0.10 U	62 J		< 0.31 U
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated	66	2600	530	0.27	30	730	< 0.43 U	< 0.088 U	100 J		< 0.27 U
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated	17	4500	550	0.029 J	17	810	< 0.49 U	< 0.10 U	120 J		< 0.31 U
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated	130	3600	460	0.29	29	890	< 0.54 U	< 0.11 U	68 J		< 0.33 U
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated	24	2100	1100	0.034 J	13	770	0.78 J	< 0.12 U	190 J		< 0.38 U
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated	71 T	2300	420 T	< 0.022 U	17	860	< 0.57 U	< 0.12 U	230 J		< 0.36 U
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated	10	2300	610	< 0.023 U	35	660	< 0.57 U	< 0.12 U	84 J		< 0.35 U
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated	15	2800	730	0.022 J	20	640	< 0.51 U	< 0.10 U	88 J		< 0.32 U
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated	5.8	1300	180	< 0.020 U	9.5	520	< 0.53 U	< 0.11 U	< 63 U		< 0.33 U
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated	5.6	1000	270	0.025 J	8.2	450 J	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated	150	2700	510	0.12	100	1500	1.3	< 0.13 U	330 J		< 0.39 U
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated	170	1800	980	0.099	39	830	1.1	< 0.12 U	95 J		< 0.36 U
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated	39	9300	1100	< 0.023 U	20	1000	< 0.65 U	< 0.13 U	110 J		< 0.41 U
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated	81	1800	330	0.088	12	510 J	2.6	< 0.12 U	1900		< 0.36 U
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated	51	1800	310	0.051	10	490 J	2.8	< 0.13 U	2200		< 0.38 U
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated	37	1600	280	0.033 J	21	790	< 0.49 U	< 0.10 U	79 J		< 0.31 U
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated	54	2500	340	0.16	25	600	< 0.53 U	< 0.11 U	77 J		< 0.33 U
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated	36	3200	840	0.094	130	860	< 0.46 U	< 0.094 U	69 J		< 0.29 U
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated	38	3200	500	0.072	27	830	< 0.49 U	< 0.10 U	81 J		< 0.30 U
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated	91	3400	380	0.10	39	990	0.62 J	< 0.11 U	140 J		< 0.33 U
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated	60	4200	330	0.057	29	800	1.4	< 0.099 U	200 J		< 0.30 U
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated	870	3200	1200	0.50	50	720	1.7	0.19 J	240 J		< 0.34 U
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated	11	2300	200	< 0.023 U	17	560	< 0.44 U	< 0.090 U	140 J		< 0.28 U
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated	33	2000	530	0.077	20	1700	0.78 J	< 0.11 U	120 J		< 0.34 U
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated	130	4000	390	0.038	30	770	< 0.49 U	< 0.10 U	88 J		< 0.31 U
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated	21	3800	330	< 0.021 U	21	630	< 0.42 U	< 0.085 U	61 J		< 0.26 U
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated	63	3300	540	0.023 J	49	680	< 0.45 U	< 0.091 U	59 J		< 0.28 U
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated	15	2000	310	< 0.021 U	15	590	< 0.47 U	< 0.096 U	< 55 U		< 0.29 U
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated	63	2500	350	0.060	29	630	< 0.47 U	< 0.095 U	80 J		< 0.29 U
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated	340	3600	370	0.059	93	740	1.5	< 0.098 U	230 J		< 0.30 U
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated	35	2000	600	< 0.020 U	20	760	< 0.41 U	< 0.083 U	130 J		< 0.25 U
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated	32	3300	400	0.022 J	22	1200	< 0.37 U	< 0.075 U	55 J		< 0.23 U
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated	7.9	1700	790	< 0.021 U	12	540	< 0.45 U	< 0.092 U	58 J		< 0.28 U
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated	36	1900	280	0.027 J	32	590	< 0.40 U	< 0.081 U	87 J		< 0.25 U
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated	8.4	2500	380	< 0.022 U	17	580	< 0.32 U	< 0.066 U	53 J		< 0.20 U
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated	35	3000	290	< 0.019 U	25	750	< 0.44 U	< 0.090 U	66 J		< 0.27 U
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated	160 T	1600	450	0.044	62 T	660	< 0.50 U	< 0.10 U	110 J		< 0.31 U
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated	590	640	110	0.020 J	15	430	< 0.40 U	< 0.082 U	250 J		< 0.25 U
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated	10	1900	630	< 0.023 U	17	840	< 0.53 U	< 0.11 U	63 J		< 0.33 U
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated	10	2100	360	< 0.024 U	15	560	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated	8.1	1800	590	< 0.023 U	12	660	< 0.48 U	< 0.098 U	90 J		< 0.30 U
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated	12	2100	310	0.024 J	17	700	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated	13	1700	1200	< 0.024 U	12	440 J	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated	8.6	2200 T	1600 T	< 0.021 U	24	790 J	< 2.3 U	< 0.46 U	< 270 U		0.44 J
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated	13	1500	610	< 0.020 U	120	670	< 0.48 U	< 0.097 U	< 56 U		< 0.30 U
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated	210	2200	420	< 0.019 U	18	670	< 0.43 U	< 0.088 U	< 50 U		< 0.27 U
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated	6.6	1900	330	< 0.020 U	49	460	< 0.33 U	< 0.068 U	< 39 U		< 0.21 U
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated	8.1	1800	330	< 0.022 U	16	540	< 0.33 U	< 0.068 U	71 J		< 0.21 U
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated	8.4	2100	370	< 0.019 U	15	750	< 0.49 U	< 0.10 U	< 57 U		< 0.30 U
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated	81	2100	280	0.060	59	700	1.2	< 0.096 U	82 J		< 0.29 U
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated	13	2000 T	480 T	< 0.018 U	16	680	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated		13	73
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated		12	46 T
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated		14	72
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated		14	64
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated		13	80
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated		12	72
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated		11	56
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated		12	230
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated		12	230
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated		12	96
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated		11	77
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated		11	110
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated		11	45
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated		11	49
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated		12	60
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated		11	69
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated		14	120
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated		14	96
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated		12	70
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated		14	90
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated		16	79
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated		13	110
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated		16	110
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated		12	440 T
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated		13	100
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated		12	56
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated		15	140
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated		16	59
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated		13	57 T
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated		15	65
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated		16	90
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated		7.4	32
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated		8.1	26
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated		22	470
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated		21	130
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated		13	63
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated		11	100
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated		10	83
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated		17	65
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated		13	97
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated		15	110
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated		15	110
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated		13	110
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated		13	80
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated		24 J	3500
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated		16	55
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated		20	73
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated		16	470
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated		12	65
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated		14	110
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated		11	70
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated		9.8	110
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated		14	410
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated		15	83
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated		14	53
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated		11	38
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated		10	60
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated		13	51
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated		12	75
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated		12	120
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated		3.6 J	97
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated		13	74
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated		14	57
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated		13	59
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated		14	60
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated		14	250
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated		16 J	55 T
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated		13	180
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated		11	44
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated		9.6	150
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated		10	43
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated		13	56
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated		21	100
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated		12	63 T

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated	6900	0.34 J	6.8	110	0.32 J	0.083 J	3100	8.8		6.2	19	18000 B
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated	7900	0.52 J	6.1	97	0.33 J	0.15 J	8600	12		6.2	65	22000 B
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated	7400	0.27 J	26	77	0.33	0.060 J	6800	11		7.6	29	20000 B
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated	6200	0.33 J	5.5	46	0.29 J	0.070 J	1200	8.0		5.9	18	15000 B
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated	4300	< 0.27 U	5.6	36	0.20 J	0.25 J	56000	39		4.6	67	13000
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated	5400	< 0.33 U	3.5	32	0.23 J	0.075 J	800	6.6		4.5 J	16	13000
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated	5900	< 0.30 U	6.2	1600	0.23 J	0.15 J	900	8.5		6.8	36	16000
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated	6800	0.56 J	7.0	95	0.22 J	0.20 J	1100	10		4.7	27	19000
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated	6800	0.83	8.4	880	0.34	0.22 J	4100	9.9		5.7	60	17000
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1802200642	Not Excavated	9200	< 0.33 U	4.1	55	0.37 J	0.14 J	1600	11 B		6.7	35	16000
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1802200642	Not Excavated	8700	< 0.39 U	5.6	140	0.43 J	0.15 J	2000	10 B		7.9	22	16000
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1802200643	Not Excavated	4400	0.46 JT	4.0	22	0.20 J	0.24 J	530 J	5.7		3.9 J	15	11000
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1802200643	Not Excavated	5400	< 0.37 U	6.4	29	0.21 J	0.15 J	21000	7.6		5.7	22	14000
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1802200643	Not Excavated	7000	< 0.37 UT	6.4	26	0.35 J	0.080 J	660 T	9.0		6.4	24	15000
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1802201971	Not Excavated	9300	< 0.39 U	6.8	51	0.31 J	0.066 J	820	10		7.6	29	20000
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1802201971	Not Excavated	6500	< 0.39 U	5.0	41	0.24 J	0.061 J	1100	7.8		5.2	20	14000
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1802201971	Not Excavated	7500	< 0.33 U	4.9	59	0.31 J	0.12 J	1400	11		7.3	26	17000
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1802201971	Not Excavated	8000	< 0.36 U	5.6	47	0.32 J	0.11 J	1400	9.9		7.4	24	19000
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1802203601	Not Excavated	8700	< 0.46 U	10	150	0.48 J	0.35 J	11000	23 B		9.1	120 B	27000
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1802203601	Not Excavated	8800	0.62 J	7.2	120	0.38 J	0.29 J	11000	15 B		7.1	98 B	18000
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1802203601	Not Excavated	9500	< 0.43 U	7.1	120	0.43 J	0.16 J	6300	13 B		8.2	61 B	22000
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1802203601	Not Excavated	8900	< 0.39 U	6.9	110	0.37 J	0.18 J	8900	14 B		7.4	56 B	19000
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1802204573	Not Excavated	8600	< 0.40 U	6.5	160	0.29 J	0.20 J	40000	13		5.9	76	21000
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated	9600	0.73 J	9.8	180	0.58	0.73	1800	21		9.9	420	27000
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated	7600	0.47 J	8.7	170	0.41 J	0.50	5100	24		8.0	700	27000
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated	9500	< 0.36 U	4.1	70	0.35 J	0.068 J	750	11		5.4	20	16000
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated	6800	2.3	8.6	110	0.51 J	0.55	1900	19		6.7	410	23000
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated	2800	0.59 J	14	130	0.72	0.29 J	2800	14		4.9	360	21000
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated	3400 T	< 2.1 UT	110	340 T	0.48 J	0.50 J	3000 T	43 T		7.0	370 T	70000 T
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated	5900	< 0.28 U	5.0	50	0.27 J	0.056 J	920	7.6 B		6.1	17	14000 B
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated	6400	< 0.39 U	5.7	46	0.33 J	0.085 J	2100	8.6 B		5.7	19	15000 B
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated	8300	< 0.31 U	7.7	80	0.37 J	0.081 J	3600	11 B		8.6	29	18000 B
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated	6000	< 0.38 U	4.3	86	0.27 J	0.59	2000	8.3 B		4.9	42	16000 B
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated	8300	< 0.32 U	5.7	39	0.32 J	0.066 J	870	9.6 B		5.9	23	17000 B
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated	8300	< 0.34 U	4.5	93	0.28 J	0.11 J	2100	11 B		4.4	21	26000 B
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated	8300	0.39 J	5.7	67	0.33 J	0.17 J	1400	9.9 B		5.5	25	18000 B
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated	9200	< 0.41 U	7.4	270	0.39 J	0.15 J	20000	11		5.5	29	18000 B
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated	10000 B	< 0.34 U	5.0	140	0.36 J	0.057 J	1700	14		7.8	34	23000
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated	7000 B	< 0.44 U	7.0	53	0.31 J	0.16 J	14000	11		7.3	27	18000 B
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated	8800	28	10	120	0.42 J	0.27 J	2800	13		9.8	370	28000
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated	6500	< 0.40 U	6.9	41	0.29 J	0.16 J	8400	14		6.8	23	17000
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated	7400	36	13	100	0.49 J	0.29 J	3800	18		14	1100	65000
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated	8900	1.2 J	6.5	78	0.39 J	0.094 J	1500	11		7.5	170	20000
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated	6300	0.86 J	6.6	50	0.44 J	0.12 J	2200	9.2		8.1	4900	18000
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated	10000	< 0.40 U	4.3	100	0.34 J	0.072 J	1200	9.9		5.5	18	18000
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated	7400	< 0.35 U	6.3	38	0.35 J	0.070 J	620	11		6.9	30	16000
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated	6800 T	0.41 J	7.0	92	0.34 J	0.44 J	5700	23		6.8	74	20000
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated	8300 T	0.37 J	8.4	51	0.39 J	0.11 J	1400	13		7.8	27	21000
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated	10000 T	< 0.36 U	7.6	78	0.45 J	0.14 J	5300	17		9.6	48	22000
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated	7000	2.3	10	96	0.36 J	0.48	3300	34		11	190	46000
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated	6400 T	< 0.33 U	8.0	12 J	0.22 J	0.055 J	560	26		3.9	30	19000
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	8000	0.55 J	11	63	0.40	< 0.029 U	8600	11		8.1	30	20000
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated	7900	0.66 J	6.9	68	0.40	0.31 J	8400	10		7.9	120	21000
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	7200	1.3	11	100	0.41	0.13 J	7300	19		7.3	93	24000 B
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	5300	< 0.28 U	5.4	31	0.24 J	< 0.030 U	760	6.5		4.8	14	12000
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	5400	< 0.37 U	3.0	31	0.22 J	0.056 J	30000	6.6		4.5 J	19	11000
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	3900	< 0.32 U	2.2	22	0.16 J	0.039 J	33000	5.0		3.2 J	18	8100
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	7800	0.56 J	5.6	76	0.34 J	0.17 J	6200	11		6.2	95	18000
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	3500	< 0.35 U	2.8	23	0.14 J	0.039 J	31000	4.4		2.5 J	14	7000
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	5700	< 0.36 UT	3.6	37 T	0.24 J	0.061 J	16000 T	7.1		4.5 J	21 T	11000 T
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	8000	5.3	10	110	0.36 J	0.15 J	5800	12		7.1	94	21000
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	8800	< 0.38 U	8.2	49	0.39 J	0.060 J	990	12		6.8	37	20000
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated	5000	13	8.2	160	0.45	< 0.038 U	8300	12		7.1	130	31000
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated	13000	0.48 JT	3.9	110	0.47	< 0.038 U	1700	13		7.3	14	15000
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	4400	1.1 T	9.7	140	0.29 J	< 0.079 U	1300	50 T		4.3 J	200 T	24000 T
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	6900	5.5	19	250	0.46	< 0.18 U	12000	28		14	300	130000
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	5400	6.8	16	93	0.60	< 0.077 U	5700	25		11	240	51000
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated	7200	0.51	6.4	40	0.28	0.040 BJ	1000 B	11 B		5.9	190	17000 B
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	11000	0.49 J	3.7	89	0.36 J	< 0.043 U	8300	12		6.3	15	17000
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated	7100	0.73	6.9	140	0.38	0.8	17000	68 B		5.9 B	150	25000
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	9300	2.9	6.4	40	0.45	0.11	670	10 B		6.9 B	21	18000
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated	6700	0.46 J	5.9	44	0.27 J	0.053 J	18000	8.7		5.1	26	16000
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated	9800	0.72 J	10	81	0.41	0.066 J	5800	10		8.3	26	18000
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated	8500	< 0.35 U	6.5	75	0.37 J	0.094 J	4500	9.9		5.2	21	16000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated	150	2100	300	< 0.019 U	17	690	< 0.47 U	< 0.097 U	< 56 U		< 0.30 U
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated	61	3100	410	0.070	29	1100	< 0.46 U	< 0.095 U	62 J		< 0.29 U
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated	78	3500	370	0.039	20	690	< 0.40 U	< 0.083 U	67 J		< 0.25 U
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated	18	1800	360	0.030	17	610	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated	12	5300	350	< 0.023 U	52	600	0.90	< 0.083 U	67 J		< 0.25 U
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated	12	1700	300	< 0.021 U	12	590	< 0.49 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated	12	1800	330	< 0.020 U	17	640	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated	10	2300	130	< 0.023 U	19	870	< 0.49 U	< 0.099 U	< 57 U		< 0.30 U
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated	96	2300	300	0.050	30	720	0.43 J	< 0.085 U	51 J		< 0.26 U
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated	32 B	2300	240	0.059 J	19	480	< 0.43 U	< 0.074 U	< 58 U		< 0.37 U
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated	24 B	1900	300	0.21	15	330 J	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	5.4	1400	250	0.041	11	440 J	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	7.0	3500	310	< 0.023 U	15	590	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	7.0 T	2100	290 T	0.045 J	17	510 JT	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated	7.7	2800	440	< 0.017 U	21	750	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated	15	1900	290	0.020 J	17	470 J	< 0.51 U	< 0.087 U	< 68 U		< 0.43 U
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated	48	2200	390	0.040 J	30	550	< 0.43 U	< 0.074 U	58 J		< 0.36 U
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated	14	2600	370	0.027 J	22	510	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated	190	2600	530	0.095 J	42	660	< 0.59 U	< 0.10 U	140 J		< 0.51 U
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated	80	4000	540	0.034 J	53	750	< 0.55 U	< 0.094 U	110 J		< 0.46 U
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated	82	2800	510	0.12 J	31	820	< 0.56 U	< 0.097 U	95 J		< 0.48 U
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated	83	3200	420	0.092 J	61	800	< 0.51 U	< 0.089 U	82 J		< 0.44 U
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated	47	2000	680	0.056 J	19	890	< 0.53 U	0.11 J	440 J		0.47 J
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated	220	2200	800	0.20	150	890	< 0.49 U	0.13 J	96 J		0.44 J
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated	270	2200	530	0.062 J	140	580	< 0.47 U	0.10 J	250 J		< 0.40 U
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated	7.6	2300	350	0.037 J	19	790	< 0.47 U	0.082 J	< 63 U		< 0.40 U
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated	240	1400	530	0.097 J	120	770	< 0.49 U	< 0.084 U	95 J		< 0.42 U
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated	110	370 J	110	0.10 J	85	270 J	1.1 J	0.096 J	89 J		0.42 J
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated	350 T	850	320 T	0.23 T	230 T	530 J	6.4	0.53 J	300 J		< 2.3 U
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated	8.8	1800	420	0.023 J	15 B	480	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated	9.8	2200	410	0.030 J	15 B	600	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated	24	2500	490	0.040 J	22 B	670	< 0.40 U	0.069 J	< 54 U		< 0.34 U
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated	440	1500	450	0.046 J	40 B	430 J	< 0.50 U	0.11 J	< 67 U		< 0.43 U
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated	9.7	2200	280	0.022 J	17 B	620	< 0.42 U	< 0.072 U	64 J		< 0.36 U
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated	43	2000	160	0.028 J	50 B	860	< 0.45 U	0.091 J	480		0.43 J
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated	20	2400	550	0.037 J	18 B	770	< 0.48 U	0.11 J	79 J		< 0.41 U
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated	95	1800	910	0.042 J	15	930	< 0.53 U	0.11 J	310 J		0.45 J
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated	29	3000	270	0.067 J	38	660	0.95 J	< 0.076 U	67 J		< 0.37 U
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated	25	4000	390	< 0.021 U	23	690	< 0.57 U	< 0.099 U	< 77 U		< 0.49 U
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated	200	2000	640 B	0.11 J	110	680	0.84 BJ	0.12 J	< 73 U		< 0.47 U
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated	14	3200	350 B	< 0.021 U	20	660	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated	250	1500	780 B	0.25	24	730	1.4 BJ	0.46 J	96 J		< 2.2 U
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated	33	2000	580 B	0.15	52	650	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated	49	930	750 B	0.085 J	35	1000	0.64 BJ	< 0.076 U	93 J		< 0.38 U
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated	9.7	2200	580	0.030 J	16	630	< 0.52 U	< 0.090 U	< 70 U		< 0.45 U
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated	14	2200	380	0.035 J	22	640	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated	62	2300	380	0.031 J	74	670	< 0.50 U	0.20 J	66 J		< 0.42 U
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated	12	2500	480	< 0.024 U	26	790	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated	41	2800	490	0.049 J	99	770	< 0.47 U	< 0.081 U	66 J		< 0.40 U
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated	96	1700	650	0.12	140	510	0.60 J	< 0.078 U	< 61 U		0.55 J
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated	35	1700	270 B	< 0.023 U	22	640	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	80	2900	390	0.10	38	810	< 0.42 U	< 0.085 U	52 J		0.40 J
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated	21	2900	210	0.020 J	39	870	< 0.47 U	< 0.095 U	< 55 U		0.90 J
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	82	2500	650	0.090	60	690	< 0.45 U	< 0.093 U	60 J		0.28 J
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	5.7	1600	650	< 0.018 U	13	500	< 0.42 U	< 0.085 U	< 49 U		0.51 BJ
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	7.0	2400	360	< 0.019 U	12	480 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	4.1	2600	330	< 0.019 U	8.4	400 J	< 0.49 U	< 0.10 U	78 J		< 0.30 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	72	2200	520	0.18	21	600	< 0.51 U	< 0.10 U	< 60 U		0.37 J
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	3.8	2100	370	< 0.020 U	6.7	500 J	< 0.53 U	< 0.11 U	< 63 U		< 0.33 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	8.0	2900 T	400 T	< 0.022 U	12	530 T	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	110	2400	390	0.28	19	580	< 0.50 U	< 0.10 U	130 J		0.49 J
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	21	2100	360	0.026 J	25	730	< 0.57 U	< 0.12 U	< 67 U		0.43 J
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated	120	1300	410	0.29	39	740	< 0.54 U	< 0.11 U	170 J		< 0.33 U
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated	14	2200	380	0.036	17	990	0.60 J	< 0.11 U	81 J		< 0.34 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	56 T	920	260 T	0.058	51	620	< 0.56 UT	< 0.11 U	< 65 U		< 0.69 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	330	1800	650	0.11	150	750	< 0.51 U	< 0.11 U	150 J		< 1.6 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	190	1100	540	0.12	37	700	2.1	< 0.11 U	95 J		< 0.68 U
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated	46	2000	230	0.041	110	600	0.11 J	0.049 J	49		0.076 J
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	36	2000	750	0.040	14	570 J	< 0.61 U	< 0.12 U	97 J		< 0.38 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated	150	2700	390	0.30 T	19	790	0.72	0.79	270		0.17
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	9.0	2200	310	< 0.020 U	18	600	0.13 J	< 0.020 U	26 J		0.096
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated	13	6600	390	< 0.020 U	13	640	< 0.52 U	< 0.11 U	61 J		< 0.32 U
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated	38	2200	910	0.040	15	600	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated	37	1700	380	0.076 J	15	560	< 0.46 U	< 0.079 U	76 J		< 0.39 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated		11	50
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated		14	120
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated		13	57
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated		11	46
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated		11	170
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated		8.7	83
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated		12	140
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated		13	130
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated		12	220
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated		12	71
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated		13	59
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated		7.5	270
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated		8.8	55
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated		10 T	57
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated		14	94
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated		10	51
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated		12	64
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated		13	80
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated		17 B	160
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated		16 B	160
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated		17 B	100
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated		14 B	110
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated		15	120
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated		18	410
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated		15	280
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated		12	55
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated		14	400
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated		11	180
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated		23 J	290 T
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated		9.1	56
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated		10	57
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated		14	86
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated		9.0	400
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated		12	56
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated		12	55
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated		12	110
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated		14 B	91
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated		17	76
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated		11	70
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated		16	250
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated		10	64
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated		28	190
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated		15	110
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated		15	230
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated		13	67
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated		12	82
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated		11	120
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated		14	72
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated		16	120
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated		21	400
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated		12	65
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated		13	66
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated		13	86
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated		16	140
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated		8.7	36
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated		9.5	47
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated		6.8	36
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated		13	110
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated		7.0	29
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated		9.5	52 T
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated		16	110
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated		16	76
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated		18	120
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated		19	57
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated		19 T	220 T
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated		20	320
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated		26	170
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated		12	85
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated		17	56
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated		18	400
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated		16	93
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated		12	63
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated		17	67
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated		13	71

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	18012321 72	Not Excavated	7300	0.43 J	6.4	110	0.35 J	0.25 J	2200	57		7.2	140	18000
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	18012321 72	Not Excavated	8000	< 0.34 U	5.5	81	0.33 J	0.14 J	2000	25		6.9	63	17000
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	18012321 72	Not Excavated	12000	< 0.42 U	4.1	76	0.42 J	< 0.056 U	1100	13		8.0	10	17000
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	18012321 72	Not Excavated	8200	0.49 J	7.7	110	0.37 J	0.13 J	4600	17		8.1	47	21000
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	18012321 72	Not Excavated	8800	< 0.41 U	6.7	94	0.43 J	0.21 J	3800	39		7.3	53	18000
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	18012328 22	Not Excavated	4500	< 0.34 U	5.1	27	0.19 J	0.18 J	29000	6.4		5.1	29	10000
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	18012328 22	Not Excavated	5900	< 0.28 U	5.7	56	0.28 J	0.071 J	14000	7.8		5.9	22	16000
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	18012328 21	Not Excavated	5600	< 0.28 U	4.0	39	0.26 J	0.14 J	22000	7.6		6.0	27	13000
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	18012328 21	Not Excavated	6000	< 0.26 U	4.4	44	0.23 J	0.062 J	26000	7.4		5.7	19	14000
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	18012328 22	Not Excavated	5500	< 0.34 U	4.9	46	0.23 J	0.15 J	31000	7.5		5.3	21	14000
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	18012328 22	Not Excavated	7500	1.4 J	8.3	100	0.41	0.27 J	9100	15		7.3	90	20000
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	18012328 22	Not Excavated	6900	0.53 J	7.0	73	0.31 J	0.19 J	28000	12		6.6	55	18000
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	18012335 43	Not Excavated	5300	< 0.33 U	7.7	46	0.25 J	0.16 J	15000	7.8		5.4	30	17000
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	18012335 43	Not Excavated	5700	< 0.37 U	5.9	74	0.30 J	0.19 J	4400	11		5.2	42	18000
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	18012335 43	Not Excavated	6900	< 0.32 U	14	86	0.34 J	0.47	38000	11		7.3	110	17000
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	18012335 43	Not Excavated	5500	2.2	4.9	38	0.24 J	0.14 J	13000	7.7		5.1	51	11000
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	18012335 43	Not Excavated	5600	< 0.32 U	3.7	33	0.23 J	0.086 J	900	8.7		4.9	17	10000
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	18012343 91	Not Excavated	9700	0.68 J	8.7	120	0.43 J	0.10 J	15000	12		8.8	34	24000
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	18012343 91	Not Excavated	9700	0.68 J	8.7	120	0.43 J	0.10 J	15000	12		8.8	34	24000
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	18012377 32	Not Excavated	7000	0.69 J	9.1	45	0.36 J	0.051 J	5600	13		6.8	61	22000
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	18012377 31	Not Excavated	4800	< 0.34 U	5.9	18 J	0.15 J	< 0.036 U	32000	4.7		3.6 J	15	13000 B
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	18012377 32	Not Excavated	4700	0.38 J	4.5	30	0.19 J	0.034 J	13000	6.4		4.2	22	11000
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	18012377 32	Not Excavated	6200	0.73 J	8.5	72	0.30 J	0.16 J	19000	10		5.7	39	16000
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	18012377 32	Not Excavated	6100	0.84 J	14	60	0.34 J	0.55	22000	8.8		5.3	37	14000
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	18012377 32	Not Excavated	6700	0.67 J	9.0	58	0.36 J	0.19 J	12000	11		6.6	53	20000
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	18012377 32	Not Excavated	4900	0.33 J	6.5	41	0.22 J	0.089 J	32000	6.9		5.1	22	14000
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	18012471 61	Not Excavated	8800	< 0.34 U	4.5	57	0.33 J	< 0.036 U	1100	10		5.9	13	18000
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	18012471 61	Not Excavated	8600	< 0.25 U	5.7	42	0.35	< 0.026 U	860	11		7.1	26	17000
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	18012471 61	Not Excavated	5500	1.6	9.3	54	0.25 J	0.35 J	9400	27		7.1	180	47000
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	18012471 61	Not Excavated	6600	0.24 J	7.2	43	0.30	0.052 J	8500	8.7		6.6	35	16000
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	18012471 61	Not Excavated	5700	< 0.37 U	7.7	41	0.27 J	< 0.039 U	18000	8.6		6.1	31	19000
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	18012471 61	Not Excavated	6000	< 0.34 U	6.3	42	0.26 J	0.065 J	17000	9.1		6.2	27	15000
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	18012610 03	Not Excavated	5900	0.52 J	8.3	65	0.33 J	0.14 J	13000	11		6.0	49	19000
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	18012610 04	Not Excavated	7600	0.41 J	6.4	76	0.31 J	0.082 J	31000	9.0		6.0	26	16000
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	18012610 04	Not Excavated	14000	< 0.44 U	7.9	100	0.55	0.086 J	3000	17		12	18	24000
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	18012610 04	Not Excavated	7300	1.3	11	140	0.41 J	0.44 J	13000	18		7.1	110	25000
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	18012638 41	Not Excavated	7500	< 0.32 U	8.3	77	0.37 J	0.11 J	13000	10		6.5	36	17000
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	18012638 41	Not Excavated	7600	0.75 J	6.9	74	0.35	0.090 J	11000	11		6.2	48	19000
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	18012638 41	Not Excavated	7300	0.59 J	9.8	70	0.33 J	0.12 J	9800	17		7.4	55	34000
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	18012640 41	Not Excavated	7100	< 0.28 U	6.7	56	0.31 J	0.030 J	12000	9.8		6.5	31	25000
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	18012640 41	Not Excavated	6500	< 0.25 U	6.0	40	0.27 J	< 0.027 U	8900	9.8		6.6	21	20000
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	18012640 41	Not Excavated	7800	0.34 J	7.0	100	0.33	0.11 J	27000	21		6.9	63	23000
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	18012640 41	Not Excavated	6100	< 0.31 U	6.8	42	0.28 J	< 0.033 U	5500	8.7		5.8	19	19000
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	18012640 41	Not Excavated	6700	< 0.28 U	5.7	37	0.29 J	< 0.030 U	760	8.0		6.8	18	15000
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	18012640 41	Not Excavated	6600	< 0.23 U	6.8	55	0.29	0.051 J	11000	9.2		6.0	36	18000
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	18012719 82	Not Excavated	5300	21	7.1	72	0.25 J	0.39	26000	10		5.2	100	15000
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	12000	< 0.034 U	8.2	79	0.46 J	< 0.034 U	17000	21		8.6	30	24000
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	18012828 71	Not Excavated	5800	< 0.36 U	5.3	42	0.23 J	0.18 J	34000	7.8		3.8	21	13000
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	18012831 51	Not Excavated	3800	< 0.33 U	5.1	38	0.19 J	0.085 J	39000	6.2		3.9	19	10000
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	18012844 41	Not Excavated	4500	< 0.28 U	6.2 B	41	0.14 J	0.15 J	37000	6.5		3.9	22	12000
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	18012920 51	Not Excavated	6800	< 0.32 U	6.3	44	0.33 J	0.12 J	1800	8.6		6.6	22	24000
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	18013181 61	Not Excavated	9700	8.1	11	73	0.46	< 0.064 U	3200	12		9.5	29	23000 B
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	18013181 61	Not Excavated	8400	< 0.28 U	6.0	61	0.33 J	< 0.067 U	1200	9.3		4.8	19	17000 B
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	18013206 71	Not Excavated	8000	< 0.20 U	5.1	100	0.33	< 0.048 U	3900	8.7		4.9	18	15000
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	18013206 71	Not Excavated	6600	48	8.7	270	0.31	1.9	20000	10		6.1	40	23000
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	18013206 71	Not Excavated	7900	7.8	11	240	0.46	0.15 J	4100	15		7.1	88	27000
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	18013436 91	Not Excavated	7700	< 0.23 U	6.4	44	0.37	< 0.055 U	670	9.5		8.0	19	17000
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	18013436 92	Not Excavated	9300	< 0.28 U	7.9	39	0.41	< 0.067 U	890	11		9.0	19	19000
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	18013436 91	Not Excavated	9000	< 0.25 UT	6.9	40	0.45	< 0.061 U	510	11		7.9	18	19000
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	18013436 91	Not Excavated	8300	1.4	7.8	64	0.37	0.11 J	5000	15		7.2	83	19000
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	18013444 51	Not Excavated	7600	< 0.35 U	5.2	56	0.36 J	0.10 J	1000	9.4		6.6	18	15000
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	18013444 31	Not Excavated	6400	< 0.34 UT	5.8	38	0.46	0.11 J	1600	7.5		5.7	27	14000 T
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	18013444 31	Not Excavated	6600	< 0.26 U	7.1	62	0.31 J	0.069 J	810	8.6		6.0	23	14000
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	18013455 51	Not Excavated	7400	5.5	9.0	70	0.46	0.080 J	4500	9.6		5.7	210	17000 B
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	18013455 51	Not Excavated	7800	1.7 T	6.4	65 T	0.47 T	0.076 JT	3700 T	9.5 T		7.6	26	18000 BT
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	18013455 51	Not Excavated	7300	0.94	6.8	60	0.33	0.075 J	12000	8.4		5.3	29	15000 B
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	18013455 51	Not Excavated	7200	0.61 J	9.2	64	0.42	0.15 J	1800	11		5.8	170	21000 B
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	18013455 51	Not Excavated	6800	8.5	6.5	60	0.34 J	0.091 J	3100	9.4		5.1	45	19000 B
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	18013455 51	Not Excavated	8600	< 0.26 U	9.5	53	0.41	0.070 J	3200	9.7		7.4	24	19000 B
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	18013478 31	Not Excavated	6100	< 0.21 U	4.2	17	0.20 J	< 0.051 U	650	13		4.4	55	15000
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	18013484 11	Not Excavated	7800	0.27 J	8.8	76	0.36	< 0.056 U	7400	9.4		6.5	18	18000 B
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	18013484 11	Not Excavated	3300	< 0.21 U	2.0	21	0.11 J	< 0.051 U	340 J	3.8		2.1 J	5.8	5600 B
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	18013484 11	Not Excavated	9300	0.44 J	4.5	63	0.35 J	0.16 J	1600	10		6.2	22	16000 B
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	18013484 11	Not Excavated	6600	0.77 J	6.1	36	0.28 J	< 0.062 U	730	12		6.3	22	15000 B

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	18012321 72	Not Excavated	90	2000	470	0.083 J	97	600	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	18012321 72	Not Excavated	37	2200	460	0.037 J	38	650	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	18012321 72	Not Excavated	8.0	2300	650	0.040 J	15	700	< 0.54 U	< 0.094 U	< 73 U		< 0.46 U
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	18012321 72	Not Excavated	47	2900	450	0.11	49	590	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	18012321 72	Not Excavated	45	2500	430	0.027 J	91	730	< 0.53 U	< 0.092 U	< 71 U		< 0.45 U
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	18012328 22	Not Excavated	13	3800	430	< 0.019 U	230	400 J	< 0.45 U	< 0.078 U	67 J		< 0.38 U
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	18012328 22	Not Excavated	19	3200	310	< 0.017 U	19	480	< 0.37 U	< 0.064 U	100 J		< 0.31 U
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	18012328 21	Not Excavated	100	5100	280	< 0.018 U	17	650	< 0.36 U	< 0.063 U	52 J		< 0.31 U
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	18012328 21	Not Excavated	6.1	3100	380	< 0.016 U	15	440	< 0.33 U	< 0.058 U	< 45 U		< 0.28 U
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	18012328 22	Not Excavated	13	9600	340	< 0.020 U	16	500	< 0.44 U	< 0.076 U	100 J		< 0.38 U
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	18012328 22	Not Excavated	120	2900	380	0.18	100	630	< 0.38 U	< 0.065 U	78 J		< 0.32 U
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	18012328 22	Not Excavated	41	3900	400	0.17	56	620	< 0.38 U	< 0.066 U	65 J		< 0.33 U
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	18012335 43	Not Excavated	29	3000	320 B	0.023 J	17	500	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	18012335 43	Not Excavated	43	1700	450	0.15	42	410 J	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	18012335 43	Not Excavated	530	4500	600	0.090 J	27	500	< 0.42 U	< 0.072 U	71 J		0.60 J
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	18012335 43	Not Excavated	17	7600	430	0.020 J	14	440	< 0.41 U	< 0.070 U	< 55 U		< 0.35 U
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	18012335 43	Not Excavated	13	1400	420	0.021 J	14	440 J	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	18012343 91	Not Excavated	49	2500	710	0.061	20	820	< 0.57 U	< 0.12 U	100 J		< 0.36 U
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	18012343 91	Not Excavated	49	2500	710	0.061	20	820	< 0.57 U	< 0.12 U	100 J		< 0.36 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	18012377 32	Not Excavated	42	3800	460	0.10	50	590	< 0.47 U	< 0.097 U	< 55 U		< 0.29 U
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	18012377 31	Not Excavated	8.8	3400	190	< 0.019 U	8.9	540	< 0.51 U	< 0.10 U	49 J		< 0.32 U
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	18012377 32	Not Excavated	10	3800	310	0.061	13	420	< 0.39 U	< 0.080 U	< 46 U		< 0.25 U
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	18012377 32	Not Excavated	55	3500	320	0.040	23	700	0.57 J	< 0.094 U	< 54 U		< 0.29 U
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	18012377 32	Not Excavated	40	3400	350	0.080	19	560	0.66 J	< 0.099 U	< 57 U		< 0.30 U
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	18012377 32	Not Excavated	71	4200	440	0.054	35	690	< 0.51 U	< 0.11 U	< 60 U		< 0.32 U
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	18012377 32	Not Excavated	14	9100	460	< 0.019 U	14	460	0.67 J	< 0.080 U	46 J		< 0.25 U
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	18012471 61	Not Excavated	9.5	2200	420	0.046	13	460 J	< 0.51 U	< 0.10 U	< 60 U		< 0.32 U
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	18012471 61	Not Excavated	21	2200	380	0.032	21	510	< 0.37 U	< 0.076 U	< 44 U		< 0.23 U
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	18012471 61	Not Excavated	80	2400	570	0.18	71	430	0.63 J	< 0.076 U	47 J		< 0.23 U
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	18012471 61	Not Excavated	25	2800	320	0.021 J	17	530	0.33 J	< 0.068 U	< 39 U		< 0.21 U
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	18012471 61	Not Excavated	19	6900	540	0.048	23	520 J	< 0.55 U	< 0.11 U	< 65 U		< 0.35 U
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	18012471 61	Not Excavated	17	4300	390	< 0.023 U	38	560	< 0.51 U	< 0.10 U	< 60 U		< 0.32 U
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	18012610 03	Not Excavated	63	4100	420	0.037	44	550	< 0.51 U	< 0.10 U	< 60 U		< 0.32 U
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	18012610 04	Not Excavated	22	5500	370	0.033 J	17	590 J	< 0.62 U	< 0.13 U	73 J		< 0.38 U
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	18012610 04	Not Excavated	20	3600	630	< 0.021 U	25	1100	< 0.66 U	< 0.14 U	< 77 U		< 0.41 U
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	18012610 04	Not Excavated	140	3000	370	0.22	48	590 J	< 0.69 U	< 0.14 U	110 J		< 0.43 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	18012638 41	Not Excavated	46	4500	470	0.055	19	620	< 0.48 U	< 0.099 U	120 J		< 0.30 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	18012638 41	Not Excavated	49	3000	380	0.039	25	500	< 0.42 U	< 0.086 U	190 J		< 0.26 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	18012638 41	Not Excavated	93	3300	470	0.088	21	520	< 0.46 U	< 0.094 U	140 J		< 0.29 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	18012640 41	Not Excavated	28	2900	500	< 0.017 U	53	530	0.48 J	< 0.086 U	210 J		< 0.26 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	18012640 41	Not Excavated	11	2600	420	< 0.017 U	90	530	< 0.38 U	< 0.077 U	100 J		< 0.23 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	18012640 41	Not Excavated	84	5300	390	0.018 J	53	620	0.57 J	< 0.078 U	440		< 0.24 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	18012640 41	Not Excavated	10	2500	360	< 0.018 U	20	510	< 0.47 U	< 0.097 U	100 J		< 0.29 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	18012640 41	Not Excavated	9.0	2000	390	< 0.018 U	16	560	< 0.42 U	< 0.086 U	130 J		< 0.26 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	18012640 41	Not Excavated	39	2700	380	< 0.018 U	31	500	< 0.36 U	< 0.073 U	180 J		< 0.22 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	18012719 82	Not Excavated	90	4300	290	0.12	30	410	0.46 J	< 0.078 U	< 45 UT		< 0.24 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	44	4800	490	< 0.034 U	23	1000	< 0.034 U	< 0.034 U	93 J		< 0.034 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	18012828 71	Not Excavated	9.7	4000	340	< 0.021 U	26	490 J	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	18012831 51	Not Excavated	8.6	7700	310	< 0.018 U	10	430 J	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	18012844 41	Not Excavated	9.5	4800	290	< 0.022 U	22	450	< 0.37 U	< 0.064 U	51 J		< 0.31 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	18012920 51	Not Excavated	28	1900	320	0.038 JT	17	500	0.42 J	< 0.072 U	69 J		< 0.35 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	18013181 61	Not Excavated	61	3100	370	0.038	21	990	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	18013181 61	Not Excavated	17	1800	360	0.23	13	440 J	0.42 J	< 0.095 U	< 47 U		< 0.26 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	18013206 71	Not Excavated	14	2000	560	0.053	14	420	< 0.30 U	< 0.068 U	< 33 U		< 0.18 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	18013206 71	Not Excavated	820	3100	360	0.61	14	550	0.70	0.10 J	93 J		< 0.19 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	18013206 71	Not Excavated	280	1900	670	0.23	17	550	0.77	< 0.066 U	52 J		0.24 J
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	18013436 91	Not Excavated	9.8	2100	490	0.029 J	17	560	< 0.35 U	< 0.079 U	< 39 U		< 0.21 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	18013436 92	Not Excavated	11	2300	310	0.028 J	17	770	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	18013436 91	Not Excavated	10	2300	220	0.036	17	740 T	< 0.39 UT	< 0.087 U	< 43 U		< 0.24 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	18013436 91	Not Excavated	53	2400	380	0.11	170	720	0.42 J	< 0.084 U	73 J		< 0.23 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	18013444 31	Not Excavated	10	2000	500	< 0.021 U	18	690	< 0.53 UT	< 0.12 U	< 58 U		< 0.32 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	18013444 31	Not Excavated	14	940	410	< 0.019 UT	9.9	1100 T	0.85 JT	< 0.12 U	92 J		< 0.32 UT
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	18013444 31	Not Excavated	10	1600	500	< 0.019 U	13	640	0.58 JT	< 0.089 U	< 44 U		< 0.24 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	18013455 51	Not Excavated	45	1500	430	0.049	15	670	0.82	< 0.079 U	99 BJ		< 0.21 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	18013455 51	Not Excavated	27	1300 T	650	0.045	15	710	0.71 JT	< 0.075 UT	94 BJ		< 0.20 UT
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	18013455 51	Not Excavated	25	2100	350	0.061	14	500	< 0.38 U	< 0.085 U	76 BJ		< 0.23 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	18013455 51	Not Excavated	41	1300	490	0.072	13	660	0.59 J	< 0.080 U	97 BJ		0.22 J
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	18013455 51	Not Excavated	76	2200	390	0.057	14	530	< 0.43 U	< 0.096 U	90 BJ		< 0.26 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	18013455 51	Not Excavated	14	2300	540	0.027 J	17	580	0.41 J	< 0.090 U	70 BJ		< 0.24 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	18013478 31	Not Excavated	14	1800	150	< 0.017 U	68	420	0.39 J	< 0.073 U	40 J		< 0.20 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	18013484 11	Not Excavated	18	2300	480	0.053	15	700	0.38 J	< 0.079 U	< 39 U		< 0.22 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	18013484 11	Not Excavated	5.8	740	83	0.082	5.6	180 J	< 0.32 U	< 0.072 U	< 36 U		< 0.20 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	18013484 11	Not Excavated	21	2200	540	0.26	41	600	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	18013484 11	Not Excavated	8.8	2100	220	0.034	290	500	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated		12	140
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated		13	85
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated		17	55
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated		13	120
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated		14	130
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated		6.8	420
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated		9.4	64
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated		8.7	81
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated		8.7	60
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated		8.5	58
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated		12	190
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated		11	110
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated		9.1	130
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated		10	100
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated		13	600
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated		9.0	170
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated		9.1	54
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated		17	79
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated		17	79
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated		16	90
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated		7.4	33
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated		9.3	49
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated		12	120
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated		13	350
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated		14	190
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated		11	62
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated		13	35
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated		14	50
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated		15	170
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated		12	71
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated		10	74
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated		11	95
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated		12	100
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated		13	81
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated		18	68
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated		18	220
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated		13	67
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated		12	74
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated		14	87
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated		12	71
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated		10	49
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated		12	110
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated		10	49
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated		10	46
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated		10	67
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated		11	160
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated		21	110
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated		10	380
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated		7.1	47
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated		8.3	120
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated		13	100
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated		13	59
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated		14	54
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated		12	50
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated		18	850
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated		22	130
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated		13	51
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated		15	46
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated		15	45
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated		15	100
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated		12	50
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated		11	40
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated		11	51
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated		15	75
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated		16	51
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated		13	50
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated		17	100
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated		14	73
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated		23	63
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated		8.6	44
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated		12	52
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated		5.4	18
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated		13	65
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated		12	310

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	5400	< 0.20 UT	4.1	32	0.26	< 0.048 U	600	8.2		5.2	16	11000
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	5300	0.22 J	4.1	24	0.21 J	0.091 J	600	19		4.5	470	14000
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	5100	< 0.24 U	4.2	31	0.19 J	< 0.058 U	970	6.6		4.8	17	13000
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	4400	< 0.23 U	4.3	29	0.18 J	< 0.055 U	860	5.4		4.5	13	11000
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	6000	< 0.21 U	4.6	33	0.24 J	< 0.052 U	630	7.5		5.7	12	13000
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	6000	0.28 J	5.2	41	0.24 J	< 0.048 U	2700	7.4		6.4	110	14000
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	8600	< 0.31 U	4.6	120	0.38 J	< 0.075 U	3100	15		4.9 J	22	13000
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	9300	< 0.25 U	5.3	39	0.37	< 0.061 U	660	11		7.1	9.8	17000
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	9600	< 0.27 U	3.9	84	0.35	< 0.065 U	1100	9.7		5.3	9.6	14000
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	7000	< 0.31 U	6.3	65	0.34 J	< 0.075 U	10000	9.7		6.5	22	17000
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	7700	< 0.31 U	6.1	54	0.33 J	< 0.075 U	9000	9.7		6.7	17	17000
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated	7500	< 0.39 U	5.5	160	0.3 J	0.1 J	4200	13		5 J	58	18000
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated	9700	< 0.39 U	6.9	190	0.41 J	0.17 J	17000	14		6.5	24	19000
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated	6200	0.57 J	6.4	67	0.34 J	0.058 J	3300	7.6		4.2 J	16	12000
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated	7200	< 0.39 U	6.4	40	0.3 J	0.042 J	1400	8.6		6	17	15000
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated	11000	< 0.41 U	7.3	51	0.4 J	0.047 J	2900	15		8.2	18	22000
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated	6800	< 0.39 U	5.8	98	0.35 J	0.23 J	25000	11		4.8 J	41	15000
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated	5200	< 0.37 U	6.7	41	0.24 J	0.08 J	31000	8.4		5.8	35	16000
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	5600	< 0.38 U	6.4	37	0.23 J	0.085 J	39000	7.6		6.4	21	13000
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	6200	< 0.36 U	3.4	46	0.23 J	0.065 J	38000	10		5.3	25	14000
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	5500	< 0.37 U	4.1	50	0.21 J	0.084 J	46000	11		4.6 J	24	14000
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated	8200	0.76 J	7.5	80	0.49	0.31 J	20000	19		7.9	79	30000
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated	7700	< 0.39 U	5.7	130	0.33 J	0.22 J	58000	14		6.1	120	18000
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated	4500	< 0.37 U	3.7	42	0.2 J	0.081 J	9300	6.9		3.7 J	16	11000
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated	5400	< 0.39 U	6.1	42	0.29 J	0.1 J	360 J	5.6		9.5	16	13000
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated	7700	< 0.41 U	6	53	0.34 J	0.1 J	3100	11		6.6	30	19000
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated	5100	< 0.38 U	4	49	0.17 J	0.089 J	43000	20		4.4 J	28	12000
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated	4900	< 0.37 U	6.9	37	0.19 J	0.043 J	41000	8.1		4.6 J	16	12000
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated	4500	< 0.73 U	3.4	31	0.19 J	0.039 J	76000	6.3		4.5 J	15	11000
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated	8900	< 0.4 U	9.5	52	0.44 J	0.21 J	6600	30		6.8	280	21000
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	5500	< 0.37 U	4	36	0.22 J	0.058 J	4200	7		4.7 J	18	13000
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated	5400	1.9	4.5	43	0.25 J	0.12 J	1200	8.8		4.8 J	100	13000
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated	7100	1.1 J	12	71	0.36 J	0.28 J	1300	20		6.9	200	25000
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	6300	< 0.39 U	5.2	39	0.26 J	0.067 J	16000	8.9		5.9	15	15000
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated	6500	< 0.35 U	5.4	49	0.24 J	0.061 J	32000	8.9		6.7	18	15000
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated	7300	0.52 J	6.1	68	0.29 J	0.066 J	15000	9.9		6.4	120	18000
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	6000	< 0.39 U	5.2	36	0.25 J	0.066 J	4700	9.4		5.1 J	22	15000
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated	6000	< 0.38 U	5	31	0.26 J	0.092 J	17000	9.1		5.8	21	16000
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated	8600	< 0.37 U	5.4	73	0.37 J	0.091 J	4600	11		7.3	28	21000
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated	7700	< 0.39 U	5.9	58	0.29 J	< 0.041 U	23000	11		6.7	23	16000
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated	6800	< 0.38 U	4.6	65	0.29 J	0.12 J	3700	9.8		5.5	160	17000
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated	7300	< 0.38 U	5.5	42	0.31 J	0.11 J	1300	16		6.3	150	20000
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated	8400	0.79 J	9.7	66	0.38 J	< 0.044 U	2800	12		5.8 J	26	18000
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated	5800	< 0.37 U	7.1	49	0.31 J	0.11 J	2800	9.1		6.3	150	18000
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated	6100	< 0.38 U	6.9	46	0.29 J	< 0.041 U	5900	12		5.8	26	16000
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated	6400	< 0.39 U	5.9	36	0.31 J	0.15 J	3700	11		5.9	24	17000
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated	11000	< 0.39 U	4.6	120	0.43 J	< 0.042 U	1200	76		7.3	41	18000
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated	12000	< 0.41 U	7.8	44	0.49	< 0.043 U	1000	18		12	15	22000
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated	5400	< 0.39 U	6.9	46	0.3 J	< 0.042 U	1800	10		6.1	25	17000
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated	5100	< 0.37 U	4.6	23	0.22 J	< 0.04 U	19000	7.2		5 J	18	13000
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	8200	< 0.77 U	9.4	230	0.36 J	< 0.082 U	4500	340		9.6	53	69000
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated	7800	< 0.41 U	6.4	110	0.35 J	0.089 J	6700	13		6.3	29	18000
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated	6600	< 0.35 U	8.1	66	0.23 J	0.58	52000	11		5.5	21	14000
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated	6300	< 0.35 U	4.5	45	0.23 J	< 0.038 U	47000	12		5.5	18	15000
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated	5900	< 0.36 U	4.7	47	0.23 J	0.047 J	36000	12		5 J	17	15000
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated	6600	< 0.36 U	5.4	64	0.25 J	0.082 J	50000	10		5.6	21	16000
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated	13000	< 0.42 U	7.2	110	0.6	0.16 J	7500	22		11	24	25000
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated	11000	5.6	6.1	85	0.46 J	0.094 J	1800	16		7.1	25	20000
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated	6800	< 0.38 U	7.1	23	0.24 J	0.052 J	2300	20		3.8 J	120	19000
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated	8500	1.1	6.2	140	0.33 J	< 0.039 U	39000	27		7.7	110	38000
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated	6800	0.97 J	4.5	41	0.29 J	0.087 J	11000	11		6.4	84	16000
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated	8600	< 0.45 U	6.8	39	0.39 J	0.071 J	870	10		7.8	24	19000
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated	7500	< 0.38 U	5.8	68	0.32 J	0.094 J	5900	9.7		5.9	23	18000
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated	7800	< 0.39 U	5.7	100	0.3 J	0.11 J	11000	11		6.2	24	18000
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated	5400	< 0.37 U	12	56	0.27 J	0.12 J	40000	9.4		4.8 J	31	13000
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated	4200	< 0.36 U	21	46	0.17 J	0.066 J	32000	6.3		3.8 J	21	10000
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated	6800	< 0.39 U	4.9	92	0.24 J	0.056 J	1300	8.2		5.2 J	25	15000
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated	8500	0.47 J	5.1	74	0.31 J	0.1 J	2500	11		7	32	18000
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated	7600	0.53 J	4.8	89	0.28 J	0.066 J	3600	9.1		5.8	31	16000
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated	5900	< 0.35 U	5	49	0.22 J	0.19 J	42000	38		4.8 J	360	14000
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated	3000	0.81 J	3.8	120	0.15 J	1.9	27000	19		2.9 J	110	19000
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated	6300	< 0.33 U	6.1	44	0.27 J	0.091 J	17000	8		6	24	16000
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated	7600	< 0.35 U	8	1000	0.35 J	0.12 J	1600	11		6.8	24	18000
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated	8800	1.2	9.7	310	0.42 J	0.14 J	11000	13		7.5	56	27000

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	7.5	1500	440	< 0.022 U	21	350 T	< 0.30 UT	< 0.067 UT	< 33 U		< 0.18 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	39	1600	200	< 0.022 U	380	330	< 0.30 U	< 0.067 U	36 J		< 0.18 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	6.1	1700	290	< 0.020 U	15	380 J	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	5.1	1300	280	< 0.021 U	20	360 J	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	6.2	1700	260	< 0.020 U	12	390	< 0.32 U	< 0.073 U	< 36 U		< 0.20 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	12	2100	310	< 0.021 U	270	530	< 0.30 U	< 0.068 U	< 33 U		< 0.18 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	16	1600	600	0.53	15	510	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	7.9	2500	240	0.045	15	590	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	7.5	1800	300	0.057	13	500	< 0.41 U	< 0.092 U	< 45 U		< 0.25 UT
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	17	3600	370	0.23	31	550	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	14	3100	500	0.11	23	530	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated	290	2900	550	0.025 J	16	560 J	0.6 J	< 0.12 U	82 J		< 0.24 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated	100	2900	380	0.05	22	550 J	< 0.6 U	< 0.12 U	440 J		< 0.24 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated	39	1500	290	0.021 J	11	720	< 0.61 U	< 0.13 U	76 J		< 0.25 U
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated	11	1800	460	0.012 J	12	630	< 0.59 U	< 0.12 U	64 J		< 0.24 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated	14	3000	370	< 0.0085 U	18	770	< 0.62 U	< 0.13 U	70 J		< 0.25 U
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated	43	4100	340	0.071	49		< 0.59 U	< 0.12 U	170 J		< 0.24 U
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated	22	17000	670	0.012 J	19		< 0.56 U	< 0.12 U	74 J		< 0.23 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	13	17000	500	< 0.0079 U	13		0.68 J	< 0.12 U	190 J		< 0.24 U
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	17	6900	340	< 0.0076 U	16		< 0.55 U	< 0.11 U	100 J		< 0.22 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated	21	9000	360	0.028 J	15		< 0.56 U	< 0.11 U	140 J		< 0.23 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated	83	2900	600	0.098	67		0.61 J	< 0.12 U	180 J		< 0.23 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated	86	5100	460	0.025 J	40		0.8 J	< 0.12 U	210 J		< 0.24 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated	12	4400	450	0.012 J	11		< 0.56 U	< 0.11 U	88 J		< 0.23 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated	10	1400	820	0.013 J	19	400 J	< 0.59 U	< 0.12 U	35 J		< 0.24 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated	240	2700	610	0.0097 J	19	670	< 0.62 U	< 0.13 U	55 J		< 0.25 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated	10	12000	440	< 0.0076 U	24	610	< 0.57 U	< 0.12 U	89 J		< 0.23 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated	14	8400	320	0.0094 J	11	590	< 0.56 U	< 0.11 U	81 J		< 0.23 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated	6.3	9500	440	< 0.0082 U	11	570	< 0.55 U	< 0.11 U	88 J		< 0.23 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated	63	4100	280	0.027 J	380		< 0.6 U	< 0.12 U	72 J		< 0.25 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	12	2600	320	0.039	11	610	< 0.57 U	< 0.12 U	60 J		< 0.23 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated	38	1400	260	0.14	49		< 0.59 U	< 0.12 U	71 J		< 0.24 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated	64	2000	310	0.16	560		1 J	< 0.13 U	69 J		< 0.25 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	15	3300	430	0.01 J	13	670	< 0.59 U	< 0.12 U	64 J		< 0.24 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated	7.7	13000	610	0.01 J	15		< 0.54 U	< 0.11 U	87 J		< 0.22 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated	35	3200	370	< 0.0082 U	17		< 0.56 U	< 0.11 U	61 J		< 0.23 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated	7.5	3200	420	0.0094 J	13		< 0.59 U	< 0.12 U	52 J		< 0.24 U
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated	10	4800	400	0.0082 J	17		< 0.58 U	< 0.12 U	54 J		< 0.24 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated	10	3500	830	0.022 J	19		< 0.56 U	< 0.11 U	47 J		< 0.23 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated	16	3500	680	0.021 J	16	730	< 0.59 U	< 0.12 U	83 J		< 0.24 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated	29	2000	360	0.21	15	510 J	< 0.57 U	< 0.12 U	39 J		< 0.23 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated	25	2000	460	0.025 J	66	690	< 0.58 U	< 0.12 U	58 J		< 0.23 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated	55	2000	380	0.099	13	780	0.72 J	< 0.13 U	130 J		0.28 J
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated	14	2600	530	0.013 J	15		< 0.57 U	< 0.12 U	50 J		< 0.23 U
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated	63	2300	470	0.01 J	69		< 0.58 U	< 0.12 U	78 J		< 0.24 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated	61	2500	510	0.018 J	70		< 0.6 U	< 0.12 U	61 J		< 0.24 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated	11	2200	600	0.028 J	920	760	< 0.59 U	< 0.12 U	41 J		0.39 J
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated	12	2900	520	0.035 J	21		< 0.62 U	< 0.13 U	52 J		0.45 J
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated	8	1900	610	0.0089 J	12		< 0.6 U	< 0.12 U	42 J		0.4 J
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated	7.4	2700	290	< 0.0084 U	12	670	< 0.56 U,^	< 0.12 U	65 J		0.26 J
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	1100	2400	1200	0.022 J	57	850	< 0.58 U	0.19 J	93 J		< 0.47 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated	59	2500	410	0.024 J	28	700	< 0.63 U,^	< 0.13 U	240 J		0.29 J
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated	18	13000	470	0.015 J	15	660	< 0.53 U	< 0.11 U	75 J		< 0.22 U
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated	10	9000	340	< 0.0076 U	14	840	< 0.54 U	< 0.11 U	85 J		< 0.22 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated	8.6	7700	330	< 0.0076 U	14	690	< 0.54 U	< 0.11 U	74 J		< 0.22 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated	9.5	5600	390	< 0.0074 U	15	770	0.54 J	< 0.11 U	73 J		< 0.22 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated	16	6000	580	0.014 J	25		< 0.63 U	< 0.13 U	64 J		< 0.26 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated	150	2500	520	0.048	17		< 0.62 U	< 0.13 U	69 J		< 0.25 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated	24	1900	150	< 0.0084 U	110		< 0.58 U	< 0.12 U	60 J		< 0.23 U
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated	120	4600	560	0.031 J	28		0.69 J	0.18 J	150 J		< 0.22 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated	20	4200	420	< 0.0083 U	160		< 0.57 U	< 0.12 U	51 J		< 0.23 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated	11	2400	230	0.024 J	19	690	< 0.68 U	< 0.14 U	35 J		< 0.27 U
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated	17	3700	550	< 0.019 U	16	700	< 0.58 U	< 0.12 U	58 J		< 0.36 U
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated	21	4200	450	0.018 J	17	760	< 0.59 U	< 0.12 U	94 J		< 0.37 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated	9.7	11000	390	< 0.011 U	15	610	0.58 J	< 0.12 U	81 J		< 0.35 U
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated	5.2	6100	250	< 0.01 U	10	490 J	< 0.54 U	< 0.11 U	73 J		< 0.34 U
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated	17	1900	550	< 0.016 U	12		< 0.59 U	< 0.12 U	570 U		< 0.37 U
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated	28	2500	910	0.032 J	16	750	< 0.59 U	< 0.12 U	570 U		< 0.37 U
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated	20	2100	740	0.022 J	13	650	< 0.6 U	< 0.12 U	580 U		< 0.37 U
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated	18	14000	440	0.024 J	52	600	0.62 J	< 0.11 U	96 J		< 0.33 U
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated	240	1400	410	< 0.013 U	15		0.63 J	< 0.13 U	240 J		< 0.38 U
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated	8.5	5500	400	< 0.013 U	15		0.63 J	< 0.1 U	160 J		< 0.31 U
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated	11	2700	490	< 0.015 U	18		< 0.52 U	< 0.11 U	48 J		< 0.33 U
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated	120	2400	570	0.02 J	32		0.69 J	< 0.12 U	160 J		< 0.37 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated		7.2	61 T
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated		7.7	47
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated		7.5	45
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated		6.6	36
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated		9.9	32
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated		8.9	42
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated		13	47
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated		14	41
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated		13	45
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated		11	57
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated		11	53
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated		13	73
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated		16	88
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated		10	35
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated		12	38
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated		16	50
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated		13	240
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated		9.3	57
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated		14	39
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated		9.5	73
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated		8.8	59
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated		17	160
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated		11	160
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated		8.2	38
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated		7.8	40
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated		12	63
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated		7.9	110
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated		9.1	38
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated		6.4	36
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated		13	860
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated		8.1	51
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated		9	120
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated		15	220
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated		11	48
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated		10	55
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated		13	64
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated		11	49
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated		8.7	59
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated		13	75
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated		13	54
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated		9.9	81
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated		13	81
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated		15	70
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated		12	94
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated		11	85
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated		11	81
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated		18	1800
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated		19	52
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated		16	150
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated		9.8	44
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated		16	83
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated		14	210
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated		9.5	200
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated		12	47
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated		9.4	44
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated		10	56
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated		17	72
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated		17	76
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated		14	50
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated		18	160
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated		10	230
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated		13	57
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated		12	73
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated		14	69
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated		8.5	60
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated		6.5	49
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated		9.6	49
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated		12	73
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated		11	54
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated		9	220
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated		6	570
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated		12	59
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated		13	130
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated		17	79

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated		7600	< 0.37 U	6.3	63	0.33 J	0.1 J	25000	9.2		6.4	21	17000
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated		7000	< 0.46 U	7.2	42	0.33 J	0.11 J	3100	9.5		6.9	29	19000
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated		5700	< 0.37 U	4.8	27	0.26 J	0.095 J	2700	8.3		5.7	18	15000
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated		7200	0.8 J	17	120	0.32 J	0.17 J	38000	12		5.7	39	24000
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated		9400	0.43 J	7.1	78	0.4 J	0.2 J	760	12		7.3	26	21000
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated		8300	< 0.36 U	4.5	50	0.3 J	0.12 J	1200	10		4.8 J	41	15000
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated		11000	< 0.27 U	5.7	170	0.50	0.14 J	3200	12		6.8	24	16000
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated		7700	< 0.23 U	5.8	39	0.31	0.083 J	1100	9.5		6.5	20	17000
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated		5700	< 0.27 U	4.8	26	0.28 J	0.042 J	1100	7.7		5.3	14	14000
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated		8000	< 0.31 U	7.2	46	0.34 J	0.091 J	1400	10		6.8	21	19000
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated		8100	< 0.24 U	4.6	63	0.3	0.17 J	20000	15		7.2	34	18000
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated		5300	0.48 J	5.1	44	0.23 J	0.09 J	17000	8.8		5.1	18	13000
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated		7900	< 0.29 U	6.9	71	0.31 J	0.17 J	19000	20		6	45	17000
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated		4500	0.6 J	4.8	34	0.22 J	0.12 J	3600	6.7		4.7 J	16	11000
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated		14000	0.7 J	10	290	0.44	0.84	11000	33		7.8	450	24000
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated		8100	< 0.34 U	6.7	170	0.37 J	0.13 J	4200 B	9.9		8.4	21	18000
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated		7400	< 0.37 UT	7.0	75	0.38 J	0.11 J	4200 BT	10		6.4	66 T	22000
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated		8000	< 0.38 U	6.0	130	0.31 J	0.17 J	6400	10		6.5	32	25000
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated		7900	< 0.33 U	7.8	150	0.34 J	0.19 J	3800	11		7.1	34	19000
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated		9100	< 0.37 U	8.6	250	0.41 J	0.34 J	3800 B	12		6.6	65	20000
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated		7700	< 0.34 U	9.2	260	0.37 J	0.36 J	45000	12		6.2	51	25000
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated		9300	< 0.37 U	7.1	100	0.37 J	0.090 J	3500	11		6.7	27	19000
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated		8500	< 0.37 U	7.9	76	0.34 J	0.058 J	1300	11 B		7.3	20	19000
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated		8900	0.38 J	7.7	290	0.40 J	0.22 J	11000	12 B		6.6	51	20000
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated		9400	< 0.36 U	7.9	120	0.42	0.079 J	1400	11 B		7.1	28	21000
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated		7800	< 0.37 U	7.9	260	0.40 J	0.26 J	5500	10 B		6.7	44	19000
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated		6500	1.0 T	6.8	180 T	0.31 J	0.22 J	20000	12 T		5.9	40	31000
Football Field	IRM4-S135	081220 09:30 SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated		8700	0.72 J	9.4	290	0.39	0.19 J	4400	18		7.3	31	23000
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated		7200	< 0.28 U	5.0	41	0.30 J	0.042 J	820	8.9		6.0	20	15000
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated		5200	< 0.31 U	5.8	36	0.24 J	0.049 J	1400	6.6		5.0	18	13000
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated		5700	< 0.27 U	5.0	35	0.25 J	0.054 J	1800	7.0		5.6	18	14000
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated		5500	< 0.30 U	4.7	28	0.21 J	0.073 J	3900	7.1		5.8	18	15000
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated		8700	< 0.40 U	8.1	62	0.41 J	0.20 J	1700	10		7.8	34	20000
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated		6100	< 0.28 U	5.9	37	0.29 J	0.15 J	2000	7.6		5.8	18	15000
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated		7300	< 0.34 U	6.4	49	0.30 J	0.052 J	980	8.6		6.2	20	17000
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated		7700	< 0.38 U	6.9	49	0.34 J	0.13 J	5600	9.4		6.2	30	18000
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated		6400	< 0.36 UT	8.5	42 T	0.27 J	0.073 J	1600 T	8.4		5.7	18	15000
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated		7300	< 0.35 U	6.2	47	0.32 J	0.11 J	13000	9.0		5.9	21	16000
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated		7100	< 0.37 U	6.1	41	0.32 J	0.099 J	2000	9.4		6.1	20	16000
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated		6700	< 0.35 U	5.4	55	0.30 J	0.062 J	880	8.7		5.9	19	16000
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated		6500	0.71 J	7.1	160	0.45 J	0.17 J	6000	9.9		6.0	27	18000
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated		8800	< 0.36 U	7.3	98	0.39 J	0.20 J	8500	13		6.9	49	20000
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated		5000	2.1	8.0	140	0.28 J	0.72	5600	21		4.9 J	110	19000
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated		12000	0.46 J	12	85	0.53	0.070 J	5300	15		11	22	27000
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated		12000	0.41 J	9.2	54	0.48	0.12 J	1100	14		10	30	28000
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	846.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated		5700	0.94	4.2	170	0.25 J	0.29 J	5100	18		4.0	180	14000
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated		7700	0.43 J	6.4	54	0.31 J	0.10 J	980	9.4		6.5	18	17000
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated		6500	0.34 J	5.2	41	0.29 J	0.097 J	1400	7.5		5.5	19	16000
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated		9600	15	8.2	100	0.48	0.32 J	3100	17		10	880	25000
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated		9700	< 0.35 U	7.4	220	0.33 J	0.22 J	2500	14		7.1	42	24000 B
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated		5700	3.8	17	83	0.39	1.4	6200	13		6.1	170	32000
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated		7600	< 0.26 U	5.4	38	0.27 J	0.058 J	780	8.3		4.5	22	15000
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated		9100	< 0.28 U	6.9	39	0.35	0.071 J	890	10		6.8	22	18000
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated		9300	< 0.27 U	4.6	110	0.29 J	0.10 J	1400	15		6.8	22	20000
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated		8300	< 0.29 U	5.1	73	0.28 J	0.12 J	27000	9.4		4.9	28	21000
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated		12000	1.3	3.9	180	0.46	0.10 J	2700	12		6.8	39	18000
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated		3500	< 0.27 U	3.0	30	0.14 J	0.10 J	29000	4.7		3.2 J	20	8800 B
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated		7600	< 0.36 U	6.8	110	0.36 J	0.21 J	23000	12		5.7	60	21000 B
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated		8300	< 0.36 U	6.3	72	0.34 J	0.11 J	25000	11		6.5	33	17000
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated		7000	< 0.32 U	6.0	130	0.30 J	0.29 J	27000	27		5.8	130	15000
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated		5800	< 0.27 U	3.7	37	0.24 J	0.063 J	850	6.9		4.5	17	12000
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated		6600	< 0.35 U	5.4	43	0.31 J	0.092 J	4000	8.2		5.7	19	16000
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated		5600	< 0.28 U	6.3	36	0.27 J	0.11 J	710	6.9		5.5	15	14000
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated		5500	< 0.22 U	5.0	35	0.24 J	0.078 J	820	6.9		5.5	17	13000
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated		5000	< 0.34 U	4.8	84	0.22 J	0.20 J	26000	23		4.4 J	310	12000
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated		7800	0.46 JT	6.2	68 T	0.30 J	0.17 J	4900 T	12		5.0	46 T	17000
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated		8400	< 0.26 U	5.3	35	0.29 J	0.060 J	680	9.6		5.2	24	17000
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated		8600	< 0.34 U	6.2	65	0.30 J	0.13 J	1200	30		6.2	57	20000
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated		7300	0.37 J	4.6	180	0.29 J	0.11 J	2200	10		4.3 J	33	15000
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated		4400	< 0.38 U	4.1	39	0.19 J	0.16 J	38000	23		3.8 J	40	11000
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated		5500	< 0.25 U	4.5	23	0.23 J	0.081 J	2000	8.0		5.1	16	13000
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated		4900	< 0.33 U	4.5	52	0.23 J	0.20 J	16000	12		4.8 J	55	12000
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated		6400	0.36 J	5.3	57	0.30 J	0.088 J	2000	9.1		5.6	25	16000 B
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated		6900	< 0.30 U	5.5	71	0.30 J	0.14 J	1400	8.6		5.7	22	15000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-IRM3-S121	080619 09:00_SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated	7.9	3900	410	< 0.012 U	16		< 0.57 U	< 0.12 U	< 28 U		< 0.35 U
Football Field	SSHS-IRM3-S127	080619 09:00_SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated	9	3100	700	< 0.017 U	16	1100	< 0.69 U	< 0.14 U	55 J		< 0.43 U
Football Field	SSHS-IRM3-S127	080619 09:00_SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated	7.4	2800	350	< 0.015 U	13	720	< 0.56 U	< 0.11 U	51 J		< 0.35 U
Football Field	SSHS-IRM3-S129F	080919 09:00_SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated	73	5000	390	0.017 J	27	690	0.85 J	< 0.11 U	210 J		< 0.34 U
Football Field	SSHS-B2936	110719 09:00_SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated	11	2400	500	< 0.017 U	18	950	< 0.55 U	< 0.11 U	250 J		< 0.34 U
Football Field	SSHS-B2937	110719 09:00_SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated	8.9	2100	500	< 0.015 U	13	740	< 0.55 U	< 0.11 U	140 J		< 0.34 U
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated	72	2100	1100	0.083	17	620	0.76 J	< 0.085 U	300 J		< 0.26 U
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated	8.4	2400	360	< 0.020 U	18	590	< 0.34 U	< 0.070 U	< 40 U		< 0.21 U
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated	7.5	1700	190	< 0.023 U	13	540	< 0.41 U	< 0.085 U	< 49 U		< 0.26 U
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated	9.3	2600	440	< 0.021 U	18	660	< 0.46 U	< 0.095 U	< 54 U		< 0.29 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated	15	5100	420	0.025 J	22	770	0.45 J	< 0.073 U	95 J		< 0.22 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated	17	9600	360	0.022 J	15	660	< 0.43 U	< 0.087 U	85 J		< 0.27 U
Football Field	SSHS-B3464	072820 09:00_SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	35	2800	390	0.45	46	810	< 0.44 U	1.3	130 J		< 0.27 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated	9.5	2100	460	0.027 J	12	600	< 0.59 U	< 0.12 U	350 J		< 0.37 U
Football Field	SSHS-B3473	072820 09:00_SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	120	3000	540	0.15	84	730	0.73 J	0.16 J	90 J		< 0.27 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated	34	2600	580	0.052	20	550	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated	51	2100	320	0.045	26	630	< 0.56 U	< 0.12 U	100 J		< 0.35 U
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated	42	3000	470	0.092	20	510 J	< 0.57 U	< 0.12 U	73 J		< 0.36 U
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated	61	2700	440	0.030 J	29	570	< 0.51 U	< 0.10 U	< 59 U		< 0.32 U
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated	120	2800	380	0.054	24	700	< 0.56 U	< 0.11 U	74 J		< 0.35 U
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated	180	2400	560	0.063	45	760	1.3	< 0.11 U	420 J		< 0.33 U
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated	33	2500	410	0.028 J	21	640	< 0.56 U	< 0.11 U	69 J		< 0.35 U
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated	8.2	2400	440	< 0.022 U	18	700	< 0.56 U	< 0.12 U	< 66 U		< 0.35 U
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated	130	2800	450	0.040	22	640	< 0.56 U	< 0.11 U	85 J		< 0.35 U
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated	9.6	2600	420	< 0.021 U	20	740	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated	120	2500	540	0.045	23	550	< 0.56 U	< 0.12 U	77 J		< 0.35 U
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated	100 T	2400	620	0.073	55	580	0.74 J	< 0.089 U	140 J		< 0.27 U
Football Field	IRM4-S135	081220 09:30_SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated	220	2400	520	0.068	43	710	< 0.5 U	< 0.1 U	78 J		< 0.31 U
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated	8.2	2000	330	< 0.017 U	16	590	< 0.42 U	< 0.085 U	< 49 U		< 0.26 U
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated	18	1700	340	< 0.018 U	14	450	< 0.41 U	< 0.070 U	< 55 U		2.0
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated	13	1800	380	< 0.021 U	15	480	< 0.36 U	< 0.061 U	< 48 U		2.3
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated	6.5	3000	400	< 0.019 U	15	550	< 0.39 U	< 0.067 U	< 52 U		2.3
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated	16	2300	620	0.025 J	21	720	< 0.53 U	< 0.091 U	< 70 U		3.7
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated	8.1	2000	400	< 0.018 U	15	520	< 0.37 U	< 0.064 U	< 49 U		2.4
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated	8.2	2100	430	< 0.020 U	17	600	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated	21	4100	500	0.058	18	790	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated	79 T	1900	350	< 0.023 U	14	570	< 0.55 U	< 0.11 U	80 J		< 0.34 U
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated	16	6100	500	< 0.019 U	17	770	< 0.54 U	< 0.11 U	92 J		< 0.33 U
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated	27	2100	360	< 0.023 U	17	790	< 0.57 U	< 0.12 U	< 66 U		< 0.35 U
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated	11	2000	370	< 0.022 U	15	740	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated	190	2000	360	0.024 J	19	810	< 0.59 U	< 0.12 U	110 J		< 0.37 U
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated	97	3200	500	0.37	24	910	< 0.54 U	< 0.11 U	160 J		< 0.34 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	110	1800	390	0.090	61	570	0.57 J	< 0.11 U	72 J		0.61 J
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated	24	4000	440	< 0.022 U	28	1200	< 0.50 U	< 0.10 U	68 J		< 0.31 U
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated	24	3700	300	< 0.022 U	28	1200	< 0.62 U	< 0.13 U	< 72 U		< 0.38 U
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated	130	1600	290	0.073	73	470	< 0.40 U	0.11 J	76 J		< 0.25 U
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated	11	2100	430	< 0.021 U	16	710	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated	7.9	1900	360	< 0.022 U	16	590	< 0.46 U	< 0.094 U	57 J		< 0.29 U
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated	210	2800	600	0.15	270	760	< 0.44 U	0.14 J	75 J		< 0.27 U
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated	77	3000	290	< 0.023 U	550	930	< 0.53 U	< 0.11 U	150 J		< 0.33 U
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated	210	2200	370	0.21	34	580	1.1	< 0.084 U	70 J		< 0.25 U
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated	25	1900	180	< 0.019 U	14	770	< 0.39 U	< 0.080 U	180 J		< 0.24 U
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated	18	2500	250	< 0.018 U	18	700	< 0.42 U	< 0.085 U	81 J		< 0.26 U
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated	320	2800	180	< 0.023 U	21	780	< 0.42 U	< 0.085 U	63 J		< 0.26 U
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated	17	2100	290	< 0.022 U	15	1100	< 0.44 U	< 0.089 U	300 J		< 0.27 U
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated	29	2200	2100	0.045	21	1200	< 0.94 U	< 0.19 U	280 J		< 0.58 U
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated	6.2	2900	250	< 0.020 U	10	390 J	< 0.41 U	< 0.084 U	50 J		< 0.26 U
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated	46	3800	390	0.026 J	20	850	0.61 J	< 0.11 U	120 J		< 0.34 U
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated	41	4600	370	< 0.020 U	31	940	< 0.55 U	< 0.11 U	160 J		< 0.34 U
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated	150	4200	350	0.044	150	770	< 0.49 U	< 0.10 U	130 J		< 0.31 U
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated	7.5	1800	260	< 0.019 U	12	470	< 0.40 U	< 0.082 U	< 47 U		< 0.25 U
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated	55	2900	350	< 0.022 U	15	720	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated	9.9	1600	410	< 0.022 U	13	580	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated	8.2	1800	360	< 0.022 U	14	480	< 0.33 U	< 0.067 U	110 J		< 0.20 U
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated	38	3900	290	0.040	27	600	< 0.52 U	< 0.11 U	80 J		< 0.32 U
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated	53 T	2200	210	0.043	24	630	< 0.49 U	< 0.099 U	79 J		< 0.30 U
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated	6.7	2300	180	0.023 J	16	500	< 0.39 U	< 0.080 U	60 J		< 0.24 U
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated	37	2300	250	0.32	27	630	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated	40	1700	330	0.038	40	570	< 0.53 U	< 0.11 U	72 J		< 0.33 U
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated	31	14000	280	0.034 J	33	590	< 0.57 U	< 0.12 U	82 J		< 0.36 U
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated	23	2000	300	< 0.022 U	13	580	< 0.38 U	< 0.079 U	53 J		< 0.24 U
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated	46	4400	340	0.038	24	750	< 0.50 U	< 0.10 U	61 J		< 0.31 U
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated	54	2000	320	0.033	25	540	< 0.40 U	< 0.082 U	< 47 U		< 0.25 U
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated	17	2400	210	< 0.019 U	17	710	< 0.45 U	< 0.093 U	55 J		< 0.28 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated		12	65
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated		14	73
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated		11	55
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated		13	110
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated		15	65
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated		11	43
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated		15	66
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated		12	57
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated		11	42
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated		12	65
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated		11	71
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated		12	46
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated		13	100
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated		8.5	46
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated		16	250
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated		13	86
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated		13	65
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated		13	100
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated		12	100
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated		15	150
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated		14	160
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated		13	76
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated		13	56
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated		15	110
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated		15	72
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated		13	120
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated		18 T	110
Football Field	IRM4-S135	081220 09:30 SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated		13	82
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated		10	46
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated		9.4	56
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated		9.1	58 B
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated		10	65 B
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated		14 B	81
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated		10 B	62
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated		11	57
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated		13	66
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated		10	47 T
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated		12	60
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated		11	53
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated		11	47
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated		13	79
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated		17	99
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated		9.9	330
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated		17	61
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated		17	75
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated		10	140
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated		12	51
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated		11	52
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated		18	850
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated		20	110
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated		13	710
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated		11	43
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated		13	49
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated		15	85
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated		12	62
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated		18	68
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated		5.4	53
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated		13	120
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated		13	69
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated		11	170
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated		8.5	44
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated		11	58
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated		10	260
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated		8.3	49
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated		9.3	130
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated		12	91 T
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated		12	43
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated		13	87
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated		12	63
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated		11	68
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated		8.4	43
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated		10	100
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated		10	56
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated		11	97

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated	12000	< 0.35 U	7.1	62	0.48	0.14 J	920	13		8.5	33	21000
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated	5400	< 0.27 U	5.0	43	0.21 J	0.15 J	34000	12		5.6	45	14000
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated	4300	< 0.30 U	4.7	38	0.11 J	0.40 J	42000	52		4.3	460	13000
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated	3800	< 0.28 U	7.1	29	0.11 J	0.21 J	30000	32		4.5	580	11000
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated	4700	< 0.35 U	4.6	37	0.12 J	0.10 J	40000	19		4.6	83	12000
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated	4700	< 0.30 U	7.3	35	0.15 J	0.24 J	40000	9.9		4.9	22	13000
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated	4500	< 0.34 U	4.4	34	0.11 J	0.11 J	37000	5.8		4.4	23	12000
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated	4200	< 0.26 U	3.3	24	0.087 J	0.082 J	36000	5.5		4.3	17	10000
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated	11000	< 0.35 U	9.0	74	0.46 J	< 0.047 U	2700	13		12	18	25000
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated	10000	< 0.32 U	9.1	65	0.43 J	< 0.043 U	2900	12		11	17	24000
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated	7800	< 0.35 U	9.0	49	0.32 J	0.079 J	1300	8.6		6.6	22	17000
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated	6300	< 0.34 U	6.9	31	0.29 J	0.058 J	1800	7.6		6.1	20	16000
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated	8100	< 0.39 U	5.4	51	0.24 J	0.34 J	2600	12		8.1	24	18000
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated	8000	1.2 J	8.1	410	0.34 J	0.32 J	9300	14		8.8	42	30000
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated	7400	2.5	7.0	110	0.29 J	0.097 J	5400	11		7.1	30	18000
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated	5100	< 0.27 U	5.7	32	0.18 J	0.098 J	27000	7.0		5.4	17	13000
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated	9200	1.3 J	5.1	140	0.28 J	0.14 J	16000	12		5.0	110	16000
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated	9100	< 0.30 U	4.9	52	0.35 J	< 0.040 U	750	9.9		5.6	13	15000
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated	6900	21	18	120	0.61	0.40 J	4100	16		12	570	39000
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated	11000	< 0.31 U	6.3	51	0.48	0.064 J	870	12		7.5	27	23000
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated	9700	< 0.36 U	6.1	36	0.36 J	2.7	680	12		7.1	36	18000
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated	6200	0.42 J	5.4	190	0.46	0.13 J	1600	28		6.2	240	20000
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated	5800	< 0.39 U	5.6	190	0.28 J	0.068 J	3100	8.2 B		5.7	17	16000 B
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated	5700 T	< 0.38 UT	5.7	30	0.24 J	0.11 J	1100	7.8		6.3	19	14000 B
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated	6400 T	< 0.36 UT	5.5	60	0.25 J	0.074 J	610	7.9		5.6	19	14000
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated	9100	< 0.37 U	5.2	41	0.35 J	0.091 J	920	20		6.5	21	17000
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated	8100	< 0.36 U	8.3	55	0.41 J	0.096 J	1100	19		7.5	1000	18000
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated	8400	0.35 J	7.6	230	0.43	0.57	9400	63		8.1	260	26000
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated	7900 B	< 0.31 U	7.3	25	0.33 J	0.048 J	670	10		7.3	19	16000
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated	8000 B	< 0.32 U	4.9	110	0.36 J	0.15 J	5100	11		6.9	32	17000
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated	10000	11	12	130	0.55 J	0.13 J	1900	68		8.6	1300	26000
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated	6300	< 0.40 U	3.6	49	0.29 J	0.10 J	960	9.3		6.9	28	14000
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated	6400	< 0.37 U	3.9	37	0.25 J	0.059 J	760	8.0		5.8	24	14000
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated	8800	< 0.34 U	5.1	42	0.29 J	0.066 J	650	9.5		5.9	19	16000
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated	8200	< 0.39 U	6.6	51	0.38 J	0.079 J	1100	10		7.8	27	21000 B
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated	7300	< 0.34 U	7.7	49	0.34 J	0.10 J	1700	13		8.7	25	18000
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated	5200	< 0.33 U	4.8	54	0.18 J	0.073 J	48000	7.2		5.0	18	12000
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated	4300	< 0.35 U	4.5	47	0.15 J	0.089 J	32000	6.6		4.3	19	11000
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated	4400	< 0.40 U	3.6	14 J	0.20 J	0.14 J	24000	6.9		5.0	25	12000
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated	6700	< 0.39 U	6.3	44	0.32 J	0.091 J	1700	12		8.0	23	17000
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated	4400	< 0.39 U	5.3	20 J	0.19 J	0.13 J	18000	6.5		5.1	17	12000
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated	5200	< 0.34 U	5.3	26	0.20 J	0.16 J	33000	7.3		5.4	21	14000
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated	8700	< 0.39 U	6.7	45	0.37 J	0.10 J	750	11		7.2	24	18000
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated	11000	1.3 J	6.4	160	0.45 J	0.17 J	1700	14 B		9.3	620	20000
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated	7900 T	0.58 J	8.3	110	0.40 J	0.32 J	3400	87		7.8	77	22000
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated	8000 T	0.47 J	7.6	85	0.38 J	0.24 J	3100	36		8.4	69	21000
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	6300	< 0.35 U	7.1	33	0.26 J	< 0.038 U	1800	8.7		5.9	23	16000
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	7700	0.79 J	9.9	94	0.37 J	0.10 J	8200	24		7.8	95	29000 B
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	4700	< 0.20 U	5.0	25	0.22 J	< 0.022 U	930	6.5		4.9	16	12000
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	4900	< 0.31 U	7.4	43	0.24 J	0.048 J	1100	6.3		5.9	23	12000
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	5100	< 0.29 U	5.5	59	0.23 J	0.043 J	6200	6.4		5.0	19	12000
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	7900	0.76 J	8.8	75	0.46	< 0.034 U	4700	9.8		14	33	19000
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	8500	7.8	8.3	97	0.38	0.22 J	5200	11		7.9	2000	21000
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	9100	3.9	9.6	110	0.42	0.14 J	4600	16		8.1	210	23000
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	12000	0.61 J	11	73	0.56	< 0.049 U	1200	14		11	35	25000
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	18000	1.0 J	7.8	76	0.61	< 0.053 U	1400	20		9.9	28	28000
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	5400	1.5	10	74	0.60	< 0.038 U	6700	13		10	65	26000
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	6500	0.38 J	5.4	37	0.25 J	< 0.033 U	680	7.5		5.8	13	15000
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	7000	0.41 J	4.7	92	0.33	< 0.028 U	1100	12		4.8	110	15000
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	7300	0.11 J	4.4	38	0.35	0.041 BJ	660 B	8.5 B		5.5	270	15000 B
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	9700	6.7	9.6	120	0.43	0.22 B	2300 B	16 B		8.5	490	36000 B
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	11000	0.56	7.2	110	0.50	0.096 BJ	2300 B	17 B		8.5	180	21000 B
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	9400	0.19	6.7	77	0.39	0.042 BJ	1200 B	11 B		6.5	49	18000 B
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated	6600	1.9 T	8.5	40	0.31	0.18 B	980 B	99 BT		6.7	220	24000 BT
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated	6600	27	19	130	0.47	0.95 B	2700 B	27 B		12	680	62000 B
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	5200	1.5	5.5	190	0.26 J	0.15 J	110000	9.0		4.5 J	110	25000
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated	6300	1.2	6.5	52	0.27 J	0.048 J	15000	7.9		5.1	19	16000
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated	7900	0.59 J	8.7	53	0.34 J	< 0.038 U	1900	10		5.9	21	17000
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated	6500	< 0.30 U	5.1	44	0.26 J	0.062 J	700	7.6		5.8	21	14000
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated	8300	< 0.32 U	5.8	44	0.33 J	0.063 J	610	42		6.7	27	16000
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated	4400	< 0.30 UT	3.2	66	0.19 J	0.070 J	23000	6.4		4.4	17	9900
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated	5500	< 0.28 U	6.7	92	0.26 J	0.18 J	20000	8.7		6.0	71	14000
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated	5600	0.34 J	4.4	62	0.26 J	0.78	4100	8.4		4.9	39	11000
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated	8300	0.57 J	6.9	73	0.33 J	0.099 J	5400	10		6.3	40	18000

DRAFT

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated	21	2900	520	< 0.020 U	27	950	< 0.54 U	< 0.11 U	91 J		< 0.33 U
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated	24	4500	430	< 0.021 U	28	620	0.59 J	< 0.085 U	62 J		< 0.26 U
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated	17	4400	300	0.033 J	100	470	< 0.39 U	< 0.067 U	60 J		< 0.33 U
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated	5.9	3500	380	< 0.020 U	75	410	< 0.36 U	< 0.062 U	67 J		< 0.31 U
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated	5.8	8700	270	< 0.019 U	24	470 J	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated	13	4300	330	< 0.019 U	21	510	< 0.39 U	< 0.067 U	57 J		< 0.33 U
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated	11	4700	340	< 0.020 U	19	380 J	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated	4.1	3800	410	< 0.022 U	11	390	< 0.34 U	< 0.058 U	51 J		< 0.29 U
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated	13	3400	450	0.026 J	26	990	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated	13	3200	370	0.025 J	24	890	< 0.42 U	< 0.072 U	< 56 U		< 0.36 U
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated	15	2100	850	0.026 J	16	480 J	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated	10	1800	430	0.029 J	12	420 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated	15	2800	850	0.30	20	550	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated	3800	2600	620	0.028 J	200	610	< 0.43 U	0.23 J	160 J		< 0.37 U
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated	980	2500	690	0.028 J	24	510	< 0.40 U	0.089 J	< 53 U		< 0.34 U
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated	6.3	4100	280	< 0.023 U	14	570	< 0.36 U	< 0.062 U	51 J		< 0.30 U
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated	35	1800	550	0.058 J	15	610	< 0.50 U	< 0.087 U	160 J		< 0.43 U
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated	7.0	2100	260	0.042 J	14	520	< 0.40 U	< 0.068 U	< 53 U		< 0.34 U
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated	420	2200	690	0.31	250	830	2.5	0.30 J	94 J		0.88 J
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated	11	2700	470	0.050 J	21	480	< 0.41 U	0.10 J	< 54 U		< 0.35 U
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated	14	2400	330	0.055 J	28	680	< 0.47 U	0.13 J	< 63 U		< 0.40 U
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated	60	1400	310	0.051 J	110	540	< 0.43 U	0.12 J	< 57 U		< 0.37 U
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated	62	1800	320	0.026 J	15 B	620	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated	8.6	1900	340 BT	< 0.024 U	16	670	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated	7.8	1800	380 T	0.022 J	14	600	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated	9.7	3000	230	0.033 J	22	710	< 0.56 U	< 0.12 U	< 66 U		< 0.35 U
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated	16	2000	390	< 0.020 U	910	790	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated	310	2100	480	0.22	300	700	< 0.40 U	0.14 J	110 J		< 0.34 U
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated	7.9	2200	190	0.044 J	21	380 J	0.82 J	< 0.071 U	< 55 U		< 0.35 U
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated	36	2300	810	0.087 J	30	510	1.0 J	< 0.073 U	86 J		< 0.36 U
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated	92	1900	700 B	0.13	530	670	1.3 BJ	< 0.092 U	< 72 U		0.47 J
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated	23	1800	470	< 0.024 U	22	640	< 0.53 U	< 0.091 U	< 71 U		< 0.45 U
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated	9.6	2000	990	0.037 J	12	690	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated	6.5	2100	370	0.035 J	16	610	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated	22	2200	480	0.039 J	20	720	< 0.51 U	< 0.089 U	< 69 U		< 0.44 U
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated	9.4	2400	440	0.035 J	22	700	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated	6.9	7900	370	< 0.020 U	13	540	< 0.43 U	< 0.075 U	64 J		< 0.37 U
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated	8.3	4300	420	< 0.018 U	11	520	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated	9.8	5000	570	< 0.020 U	14	700	< 0.53 U	< 0.091 U	< 71 U		< 0.45 U
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated	8.7	2300	360	0.024 J	20	680	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated	6.8	5300	280	0.020 J	12	540	< 0.51 U	< 0.087 U	< 68 U		< 0.43 U
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated	6.7	3400	370	0.022 J	14	570	< 0.45 U	0.12 J	61 J		< 0.38 U
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated	9.3	2200	300	0.026 J	19	700	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated	50	2300	890	0.12 J	370	700	< 0.54 U	0.16 J	< 73 U		< 0.46 U
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated	460	2300	380	0.038 J	62	650	< 0.43 U	0.076 J	67 J		< 0.37 U
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated	220	2400	510	0.041 J	120	580	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	35	2600	370	< 0.021 U	16	580	< 0.54 U	< 0.11 U	< 63 U		0.52 BJ
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	190	2900	440	0.12	66	630	< 0.57 U	< 0.12 U	< 67 U		0.36 J
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	6.8	1500	330	< 0.018 U	13	360	< 0.31 U	< 0.063 U	< 36 U		< 0.19 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	11	1500	1100	0.036 J	13	490	< 0.46 U	< 0.095 U	< 54 U		0.68 BJ
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	11	3800	940	< 0.020 U	13	510	< 0.44 U	< 0.089 U	< 51 U		0.61 BJ
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	45	2200	450	0.13	29	660	< 0.49 U	< 0.099 U	57 J		0.42 BJ
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	340	2300	770	0.12	31	590	< 0.48 U	0.80	59 J		0.45 J
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	150	2800	420	0.12	130	900	< 0.53 U	< 0.11 U	< 62 U		0.33 J
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	17	2800	760	< 0.033 U	27	900	< 0.70 U	< 0.14 U	< 82 U		0.54 J
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	16	4000	750	< 0.031 U	27	890	< 0.75 U	< 0.15 U	< 88 U		0.67 J
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	73	1300	210	0.16	28	910	0.58 J	< 0.11 U	240 J		< 0.33 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	6.3	1900	310	< 0.021 U	14	350 J	< 0.46 U	< 0.094 U	< 54 U		< 0.29 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	22	1400	390	< 0.024 U	19	750	< 0.40 U	< 0.081 U	85 J		< 0.25 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	7.1	2100	180	0.021 J	140	450	< 0.099 U	< 0.022 U	43		0.059 J
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	140	2200	590	0.11	99	660	0.38 J	0.11	64		0.11
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	49	2600	490	0.047	130	830	0.24 J	0.053 J	59		0.12
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	11	2200	350	< 0.019 U	40	570	0.11 J	< 0.024 U	46		0.076 J
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated	150 T	1900	220	0.12	990	520	0.36 J	0.064 J	48		0.079 J
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated	1000	1700	670	0.27	150	810	1.5	0.23	88		0.29
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	29	1300	260	< 0.023 U	11	730	< 0.48 U	< 0.097 U	1100		< 0.30 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated	23	1700	400	0.034	11	590	< 0.49 U	< 0.10 U	75 J		< 0.31 U
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated	15	2100	380	0.023 J	15	830	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated	11	1700	370	0.030 J	14	440	< 0.40 U	< 0.069 U	< 53 U		< 0.34 U
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated	15	2200	360	0.057 J	30	620	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated	7.9	3400 T	290 T	< 0.017 U	14	490	< 0.39 U	< 0.068 U	64 J		< 0.34 U
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated	52	3600	380	0.026 J	150	450	< 0.37 U	< 0.064 U	77 J		< 0.31 U
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated	9.7	2800	650	0.020 J	15	530	< 0.46 U	0.31 J	< 54 U		< 0.29 U
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated	28	2100	490	0.050	17	540	< 0.52 U	< 0.11 U	64 J		< 0.32 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated		17	120
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated		11	75
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated		7.2	870
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated		5.7	460
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated		7.0	130
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated		9.1	320
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated		6.7	170
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated		6.0	50
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated		15	66
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated		14	65
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated		12	65
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated		11	51
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated		11	320
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated		14 B	150
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated		12 B	70
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated		9.4 B	49
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated		14 B	120
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP S6	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated		13	49
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated		21	360
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated		16	61
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated		14	110
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated		12	280
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated		10	56
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated		11	63 B
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated		10	130
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated		13	87
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated		13	320
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated		17	740
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated		12	52
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated		12	75
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated		17	510
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated		9.0	69
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated		11	52
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated		11	67
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated		13	63
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated		13	72
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated		7.7	54
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated		8.8	44
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated		10	58
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated		12	63
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated		8.6	48
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated		8.8	50
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated		14	63
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated		17	330
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated		14	180
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated		12	130
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated		10	66
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated		15	130
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated		9.2	36
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated		9.1	45
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated		8.5	49
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated		14	72
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated		16	180
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated		16	250
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated		21	76
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated		25	76
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated		18	92
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated		9.4	36
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated		12	46
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated		10	130
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated		19	290
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated		17	200
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated		13	69
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated		12	1400
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated		39	460
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated		14	66
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated		12	48
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated		15	66
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated		10	74
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated		12	75
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated		7.7	55
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated		9.9	130
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated		9.7	110
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated		13	110

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated	4300	0.35 J	5.5	33	0.20 J	0.10 J	37000	6.1		4.7 J	22	11000 B
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated	6400	0.43 J	7.7	49	0.30 J	0.087 J	15000	9.7		6.6	32	17000 B
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated	5100	< 0.27 U	4.9	29	0.18 J	0.033 J	32000	6.4		5.0	19	12000 B
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated	5900	< 0.28 U	6.3	43	0.25 J	0.050 J	9900	7.9		5.3	26	14000
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated	4500	< 0.27 U	5.6	42	0.19 J	< 0.029 U	23000	6.3		4.6	18	12000
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated	6200	< 0.34 U	7.3	63	0.29 J	0.13 J	25000	15		6.3	39	20000
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated	5100	< 0.32 U	4.0	36	0.20 J	0.087 J	36000	6.4		4.9	23	11000
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	7700	< 0.29 U	7.6	62	0.32 J	0.048 J	16000	11		7.0	33	19000
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	7400	0.43 J	7.6	84	0.32	0.058 J	19000	9.6		6.7	32	24000
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	6000	< 0.33 U	5.7	39	0.27 J	< 0.035 U	8100	7.5		5.7	20	17000
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	8100	< 0.34 UT	5.7	50	0.34 J	0.092 J	1100	9.8		6.7	47 T	16000
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	8200	< 0.36 U	5.6	62	0.32 J	0.094 J	32000	11		7.3	24	18000
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated	6100	< 0.35 U	5.3	34	0.22 J	0.065 J	27000	8.0		5.7	23	15000
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated	5400	< 0.35 U	6.0	36	0.22 J	0.17 J	30000	7.0		5.5	21	14000
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated	4600	< 0.31 U	5.7	43	0.19 J	0.17 J	63000	6.2		4.2 J	26	11000
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	7200	< 0.034 U	5.6	96	0.32 J	0.06 J	33000	9.3		6.1	19	15000
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	8300	< 0.034 U	6	71	0.31 J	0.094 J	30000	12		6.4	21	16000
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated	3700	< 0.27 U	4.1	34	0.15 J	0.084 J	38000	5.1		3.6	15	9200
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	8400	27	5.6	85	0.36	0.051 J	2200	9.8		6.3	34	16000
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	8700	0.27 J	4.1	170	0.36	< 0.063 U	2200	8.2		4.2 J	9.5	13000 B
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	8500	12	29	160	0.49	0.22 J	3300	15		7.3	180	30000
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	7600	94	9.0	110	0.35	0.75	9300	11		7.8	180	23000 B
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	10000	0.72 J	7.0	51	0.44	< 0.067 U	1600	11		7.7	16	18000 B
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	9700	< 0.22 U	8.6	75	0.41	0.10 J	4400	12		9.5	32	24000 B
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	5500	< 0.24 U	6.3	33	0.27 J	0.079 J	900	14		5.2	330	14000
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	5600	0.22 J	6.3	46	0.28	0.096 J	1400	7.1		5.0	21	16000
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	5900	< 0.23 U	4.1	35	0.25 J	< 0.056 U	1100	7.5		5.7	17	15000
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	7700	0.57 JT	2.6	130	0.34 J	< 0.072 U	1900 T	7.3		4.3 J	6.5	12000
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	7500	< 0.27 U	4.9	23	0.27 J	< 0.065 U	470	8.4		5.1	15	14000
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	5400	< 0.32 U	5.4	31	0.26 J	< 0.077 U	3400	6.7		4.9 J	17	13000
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	9000	0.83	5.1	33	0.37	< 0.058 U	780	9.5		6.1	19	18000
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	5600	< 0.29 U	4.7	23	0.23 J	< 0.070 U	690	7.0		4.8	19	13000
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	4900	< 0.25 U	4.6	26	0.23 J	0.063 J	3800	9.2		4.3	15	12000
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	9700	< 0.32 U	5.4	40	0.37 J	< 0.079 U	1100	11		6.4	11	17000
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	7400	< 0.4 U	5.9	78	0.32 J	0.11 J	31000	11		6.1	24	17000
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	4900	< 0.27 U	3.4	34	0.20 J	< 0.065 U	28000	5.8		3.5 J	14	9900
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	8200	< 0.28 U	6.4	56	0.38	0.74	15000	10		7.1	23	16000
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	5500	0.21	4.1	35	0.22	< 0.014	33000	7.1		4.7	20	13000
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated	12000	1.1 J	9.4	110	0.63	0.16 J	6600	17		9.8	41	25000
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	9000	0.83 J	9.7	110	0.47	0.58 J	4000	13		6.7	26	17000
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated		< 1.16	4.07	58.5	< 0.578	< 0.578		8.02		< 5.78	8.18	
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	7200	2.3	15	130	0.44 J	0.63	8500	16		7.4	55	20000
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	7300	0.69 J	5.4	80	0.20 J	0.24 J	44000	9.8		6.8	18	14000
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	6600	< 1.2 U	4.7	54	0.24 J	< 0.059 U	57000	8.9		5.2	21	18000
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	9400	< 0.37 U	5.3	120	0.34 J	0.054 J	1700	9.7		4.4	14	14000
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	8900	< 0.27 U	4.9	58	0.37	0.049 J	630	9.8		5.3	11	16000
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated	5600	< 0.37 U	4.7	51	0.22 J	1.1	5800	10		5.1 J	20	15000
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated	7000	< 0.36 U	5.3	51	0.27 J	0.068 J	22000	11		6	30	16000
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated	6900	0.72 J	6.3	71	0.3 J	0.23 J	19000 J	19		6.3	30	17000
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated	5600	< 0.34 U	4.6	39	0.21 J	0.089 J	43000	8.4		4.6 J	18	13000
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated	5000	< 0.38 U	4.5	50	0.21 J	0.098 J	11000	7.1		4.3 J	19	12000
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated	6200	< 0.38 U	5.4	55	0.25 J	0.16 J	9800	8.2		5.7	18	16000
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated	5600	< 0.37 U	5	27	0.23 J	0.082 J	17000	8.3		4.7 J	16	14000
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated	6200	< 0.34 U	4.6	71	0.24 J	0.12 J	42000	8.1		5.8	21	15000
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	6300	< 0.35 U	4.5	46	0.22 J	0.1 J	33000	11		5.1 J	21	14000
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated	5900	< 0.38 U	4.2	49	0.23 J	0.12 J	52000	8.5		5.3 J	28	14000
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated	5200	< 0.37 UJ	4.9	42	0.21 J	0.11 J	57000	7		5.4	29	12000
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated	4500	< 0.38 U	5.5	36	0.21 J	0.1 J	21000	6.8		4.4 J	18	13000
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated	6000	< 0.34 U	4.2	49	0.26 J	0.087 J	23000	8.1		5.5	17	14000
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated	4600	< 0.36 U	4.2	33	0.18 J	0.095 J	37000	10		4.4 J	17	12000
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated	6100	< 0.35 U	4.6	45	0.22 J	0.19 J	62000	9.5		5.4	21	14000
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated	7600	0.71 J	7.6	92	0.36 J	0.16 J	3700	17		6.4	42	20000
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated	7100	< 0.36 U	4.8	33	0.27 J	0.079 J	19000	11		6.4	19	15000
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated	5500	< 0.36 U	4.7	48	0.2 J	0.12 J	49000	11		5 J	17	13000
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated	6100	< 0.35 U	4.3	59	0.23 J	0.089 J	47000	9		6.6	20	15000
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated	5400	< 0.36 U	3.9	39	0.2 J	0.095 J	52000	7.9		5 J	15	13000
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated	7500	0.45 J	5.2	74	0.31 J	0.086 J	17000	11		5.9	16	15000
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated	8000	< 0.4 U	6.7	69	0.35 J	0.089 J	1500	11		6.5	21	17000
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated	6400	< 0.39 U	5.6	110	0.3 J	0.092 J	7300	9.3		5.6 J	23	14000
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated	5700	< 0.36 U	3	38	0.19 J	0.15 J	72000	7.4		5 J	16	13000
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated	6800	< 0.39 U	6.1	59	0.27 J	0.099 J	7500	11		5.9	20	15000
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated	5900	< 0.37 U	5.2	50	0.25 J	0.12 J	25000	8.5		5.8	21	14000
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	5600	< 0.39 U	5.3	30	0.2 J	0.11 J	63000	7.9		4.3 J	14	11000
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated	5700	< 0.34 UJ	4.5	42	0.21 J	0.12 J	40000	7.7		5.4	17	13000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated	16	4900	420	0.045	14	470 J	0.77 J	< 0.10 U	< 60 U		< 0.32 U
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated	22	5800	410	0.040	32	660	< 0.49 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated	9.3	3200	340	< 0.016 U	70	430	< 0.41 U	< 0.083 U	< 48 U		< 0.25 U
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated	16	3400	400	0.066	15	510	< 0.43 U	< 0.087 U	< 50 U		< 0.27 U
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated	10	3600	260	< 0.016 U	13	520	< 0.40 U	< 0.082 U	< 47 U		< 0.25 U
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated	110	5200	510	< 0.018 U	20	630	0.68 J	< 0.10 U	69 J		< 0.32 U
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated	12	4300	320	< 0.018 U	70	550	0.53 J	< 0.10 U	70 J		< 0.31 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	22	5800	450	< 0.023 U	23	610	< 0.44 U	< 0.091 U	250 J		< 0.28 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	40	3600	440	< 0.020 U	26	590	0.59 J	< 0.084 U	200 J		< 0.25 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	10	2300	380	< 0.016 U	39	490	< 0.49 U	< 0.10 U	110 J		< 0.31 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	15	2100	340 T	< 0.017 U	18	520	< 0.52 U	< 0.11 U	200 J		< 0.32 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	20	8200	420	0.018 J	21	680	< 0.55 U	< 0.11 U	71 J		< 0.34 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated	10	4200	400	< 0.021 U	19	400 J	< 0.52 U	< 0.11 U	< 61 UT		< 0.33 U
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated	14	5900	290	< 0.020 U	16	490 J	0.60 J	< 0.11 U	< 62 UT		< 0.33 U
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated	15	5400	310	< 0.021 U	13	480	0.77 J	< 0.095 U	< 54 UT		< 0.29 U
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	9.3	9400 J	710	< 0.034 U	16	850	< 0.034 U	< 0.034 U	86 J		< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	11	5300 J	440	< 0.034 U	18	850	< 0.034 U	< 0.034 U	100 J		< 0.034 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated	6.2	6000	260	< 0.022 U	9.7	440	< 0.36 U	< 0.062 U	< 48 U		< 0.30 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	90	1700	450	0.063	21	490	< 0.29 U	< 0.065 U	38 J		< 0.18 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	9.9	1400	950	0.029 J	9.6	540	0.46 J	< 0.090 U	82 BJ		< 0.24 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	120	1700	640	0.19	16	830	5.5	< 0.11 U	110 BJ		0.38 J
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	740	2100	460	0.053	17	810	0.39 J	< 0.083 U	130 BJ		< 0.23 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	16	2300	420	0.036	16	680	< 0.42 U	< 0.095 U	78 BJ		< 0.26 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	22	3300	420	0.061	24	790	0.38 J	< 0.075 U	37 J		< 0.20 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	6.4	1600	260	< 0.021 U	230	400	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	9.3	1500	520	< 0.020 U	35	460	0.33 J	< 0.069 U	< 34 U		< 0.19 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	6.2	2000	370	< 0.024 U	14	400	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	10 T	1400	590	0.055	8.5	470 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 UT
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	6.3	2000	210	0.034	14	480	0.41 J	< 0.092 U	< 45 U		< 0.25 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	9.7	2500	340	< 0.021 U	13	510 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	19	2100	290	0.032	15	470	0.41 J	< 0.082 U	< 40 U		< 0.22 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	6.2	1700	220	< 0.020 U	13	430 J	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Football Field	SSHS-ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	7.3	1600	300	0.14	49	450	< 0.38 U	< 0.086 U	< 42 U		< 0.24 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	7.9	2400	240	0.021 J	15	640	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	30	14000	360	0.68	17	670	< 0.6 U	0.42 J	91 J		< 0.24 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	7.8	3300	250	0.027	9.8	410 J	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	17	4200	380	0.028 J	19	570	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	6.7	3200	420	0.015	11	500	I	< 0.041	41		< 0.15
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated	37	3800	530	0.29	27	1100	< 0.62 U	< 0.13 U	72 J		< 0.38 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	130	2300	500	0.089	17	660	0.75 J	< 0.12 U	< 71 U		< 0.38 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	8.15			< 0.0578	12		< 0.578	< 1.16			< 1.16
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	220	2000	390	0.20	28	730	1.3 J	0.23 J	82 J		< 0.38 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	35	4100	400	0.062 J	17	720	< 0.37 U	< 0.064 U	75 J		< 0.31 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 25 U	9800	380	0.024 J	13	610	< 1.9 U	< 0.084 U	79 J		< 0.23 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	19	1600	540	0.061 J	11	400 J	0.66 J	< 0.083 U	170 J		< 0.41 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	9.9	1800	250	0.031 J	13	360 J	< 0.35 U	< 0.061 U	< 47 U		< 0.30 U
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated	12	1900	300	0.042	11	610	< 0.56 U	< 0.11 U	45 J		0.32 J
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated	9.4	8000	440	0.013 J	16	720	< 0.54 U	< 0.11 U	65 J		< 0.22 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated	32	3400	510	0.2	63	810	0.64 J	< 0.11 U	95 J		< 0.34 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30_SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated	7	8900	320	< 0.014 U	12		0.75 J	< 0.11 U	74 J		< 0.32 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated	6.7	6300	560	< 0.015 U	11	560	< 0.58 U	< 0.12 U	66 J		< 0.36 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated	7.8	3400	620	< 0.013 U	14	830	< 0.57 U	< 0.12 U	57 J		< 0.36 U
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated	6.2	5400	290	< 0.015 U	12	620	< 0.56 U	< 0.11 U	65 J		< 0.35 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated	11	7000	440	0.16	14	610	0.67 J	< 0.11 U	66 J		< 0.32 U
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	7.5	8700	570	< 0.014 U	13	810	< 0.54 U	< 0.11 U	89 J		< 0.33 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated	12	8800	480	0.026 J	14	630	0.73 J	< 0.12 U	83 J		< 0.35 U
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated	7	19000	500	0.018 J	13	650	0.95 J	< 0.11 U	110 J		< 0.35 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated	8.4	10000	520	0.027 J	11	630	< 0.58 U	< 0.12 U	61 J		< 0.36 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated	7.1	3200	340	< 0.013 U	13	650	< 0.52 U	< 0.11 U	67 J		< 0.32 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated	14	11000	380	< 0.014 U	11	580	0.55 J	< 0.11 U	79 J		< 0.34 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated	8.1	11000	420	0.047	14	750	0.9 J	< 0.11 U	92 J		< 0.33 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated	97	2200	510	0.26	17	600	0.68 J	< 0.11 U	97 J		< 0.33 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated	11 J	3000 J	460	< 0.014 UJ	15	700	< 0.55 U	< 0.11 U	61 J		< 0.34 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated	14	11000	380	< 0.015 U	13	710	0.85 J	< 0.11 U	< 28 U		< 0.34 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated	5.9	7400	460	< 0.014 U	15	690	0.58 J	< 0.11 U	28 J		< 0.33 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated	5.9	19000	400	< 0.014 U	12	690	0.61 J	< 0.11 U	40 J		< 0.34 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated	9.9	7000	540	< 0.016 U	13	770	< 0.58 U	< 0.12 U	66 J		< 0.36 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated	10	2300	530	0.033 J	16	800	< 0.61 U	< 0.12 U	< 30 U		< 0.38 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated	7.9	3000	520	< 0.017 U	14	680	< 0.58 U	< 0.12 U	78 J		< 0.36 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated	4.3	11000	390	< 0.015 U	13	580	0.84 J	< 0.11 U	110 J		< 0.34 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated	7.9	3100	470	0.015 J	15	830	< 0.59 U	< 0.12 U	59 J		< 0.37 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated	9.2	9500	510	< 0.013 U	14	740	< 0.56 U	< 0.11 U	78 J		< 0.35 U
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	19	13000	330	< 0.014 U	12	840	1 J	< 0.12 U	52 J		< 0.37 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated	6.4	8100 J-	410	< 0.014 U	13	580	< 0.51 U	< 0.1 U	110 J		< 0.32 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated		9.1	55
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated		13	140
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated		8.6	58
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated		10	64
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated		8.2	44
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated		12	86
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated		8.1	100
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated		11	62
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated		13	68
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated		9.1	48
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated		12	89 T
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated		12	71
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated		9.5	54
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated		10	65
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated		8.5	73
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated		14	52
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated		13	63
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated		5.8	42
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated		12	72
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated		12	48
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated		23	92
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated		17	700
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated		16	62
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated		14	120
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated		8.4	120
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated		8.9	46
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated		9.1	52
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated		11	44 T
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated		10	39
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated		8.8	44
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated		12	62
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated		8.4	37
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated		7.6	100
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated		14	41
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated		14	74
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated		7.8	35
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated		13	79
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated		9.5	47
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated		17	78
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated		17	110
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 57.8	14.2	39.4
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated		15	270
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated		12	160
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated		11	60
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated		15	200
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated		16	46
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated		11	67
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated		12	51
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated		15	70
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated		8.6	45
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated		8.3	55
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated		11	67
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated		10	43
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated		9	58
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated		10	50
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated		9.2	48
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated		8.3	49
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated		7.4	53
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated		8.7	55
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated		7.1	41
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated		9.4	54
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated		14	97
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated		11	63
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated		8.3	42
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated		9.1	45
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated		9.6	40
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated		12	53
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated		12	61
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated		10	57
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated		8.4	55
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated		10	57
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated		9.6	62
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated		10	41
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated		8.2	48

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	6600	< 0.37 U	6.8	61	0.32 J	0.12 J	3000	10		5.7	20	15000
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated	7200	< 0.37 U	5.7	88	0.32 J	0.13 J	40000	13		6.1	23	14000
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated	5500	< 0.38 U	6.1	36	0.24 J	0.12 J	35000	8.1		5.6	16	14000
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated	6600	0.39 J	6.4	42	0.3 J	0.12 J	1500	9.8		5.9	20	15000
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated	6800	< 0.4 U	6.4	42	0.32 J	0.097 J	13000	10		6.1	21	16000
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated	6200	< 0.34 U	5	51	0.23 J	0.1 J	53000	11		6.7	23	15000
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated	5700	< 0.37 U	5.2	53	0.19 J	0.12 J	62000	9		5.1 J	22	13000
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated	4600	< 0.39 U	12	46	0.2 J	0.14 J	30000	7.6		4.7 J	17	13000
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated	8100	< 0.37 U	5.7	69	0.32 J	0.1 J	24000	11		7.1	21	18000
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated	4800	< 0.33 U	3.8	38	0.2 J	0.057 J	20000	6.5		4.6 J	11	10000
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated	6200	< 0.38 U	5.5	37	0.29 J	0.05 J	2000	9		5.5 J	17	15000
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated	6600	< 0.39 U	5.5	45	0.25 J	0.12 J	21000	9.8		6.8	27	17000
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated	7900	< 0.4 U	4.2	47	0.26 J	0.097 J	17000	10		5.6 J	43	17000
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated	6100	< 0.35 U	4.4	75	0.23 J	0.086 J	53000	8.6		5.6	18	13000
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated	5100	< 0.37 U	5.6	39	0.29 J	0.061 J	14000	8.8		5 J	28	14000
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated	7800	0.49 J	8.5	72	0.31 J	0.21 J	1400	16		7.1	33	48000
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated	6100	< 0.4 UJ	9.2	55	0.28 J	0.11 J	700	9.3		4.7 J	16	15000
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated	7700	< 0.38 U	6.8	82	0.33 J	0.33 J	1200	9.5		6.1	21	16000
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated	5100	< 0.37 U	4.7	35	0.22 J	0.097 J	33000	6.9		5 J	16	12000
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	7300	< 0.36 U	4.7	65	0.27 J	0.22 J	25000	13		6	31	17000
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated	6900	< 0.35 U	4.5	430	0.27 J	0.079 J	49000	11		5.7	21	16000
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated	5900	< 0.36 U	4.1	57	0.23 J	0.087 J	59000	10		5.2 J	17	14000
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated	4600	< 0.36 U	7.5	36	0.22 J	0.056 J	40000	7.8		4.6 J	15	11000
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated	5800	< 0.38 U	4.1	98	0.25 J	0.051 J	53000	73		5.5	42	16000
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated	6100	< 0.36 U	4.6	96	0.25 J	0.074 J	56000	8.9		5.2 J	17	13000
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated	6400	< 0.35 U	5.6	55	0.23 J	0.1 J	38000	20		6.1	22	15000
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated	6200	< 0.36 U	5.1	48	0.24 J	0.083 J	34000	9		5.4	16	14000
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated	7400	< 0.39 U	8	66	0.36 J	0.13 J	35000	15		11	27	20000
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated	6300	< 0.37 U	5.4	40	0.26 J	0.11 J	10000	9.6		6	34	16000
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated	5700	< 0.38 U	5	37	0.24 J	0.18 J	24000	8.4		4.9 J	17	13000
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated	7400	< 0.34 U	5.4	60	0.27 J	0.097 J	12000	12		6.2	27	16000
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated	5300	< 0.35 U	4.8	54	0.22 J	0.085 J	43000	10		4.8 J	29	12000
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated	5300	< 0.37 U	4.2	39	0.21 J	0.1 J	63000	8		4.6 J	16	12000
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated	6600	< 0.37 U	4.9	46	0.26 J	0.084 J	31000	8.8		6.1	17	18000
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated	5600	< 0.36 U	6.2	38	0.23 J	0.13 J	38000	9.8		4.9 J	18	13000
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated	5900	1 J	7.9	56	0.39 J	0.42 J	26000	35 J		6.4	100 J	34000 J
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated	5400	< 0.38 U	5.3	36	0.21 J	0.081 J	29000	8.2		4.7 J	16	13000
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated	7500	0.47 J	6.9	58	0.32 J	0.1 J	13000	9.8		6.9	22	18000
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated	8100	0.61 J	7.7	54	0.37 J	0.082 J	1100	11		7.7	22	20000
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated	5700	< 0.36 U	6.3	25	0.29 J	0.11 J	6900	7.6		5.5	16	14000
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated	4100	< 0.4 U	3	31	0.14 J	0.065 J	31000	4.6		3.9 J	12	9200
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated	4400	< 0.4 U	6.7	30	0.22 J	0.068 J	870	6.4		4.7 J	12	12000
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated	5500	< 0.35 U	6.1	46	0.2 J	0.11 J	50000	9.6		4.9 J	16	13000
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated	6000	< 0.34 U	4.1	74	0.23 J	0.097 J	52000	8.4		5.8	20	14000
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated	4000	< 0.38 U	3.2	54	0.15 J	0.062 J	35000	6.3		3.6 J	13	10000
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated	6000	< 0.37 U	5.6	45	0.25 J	0.14 J	80000	9.8		5.6	22	14000
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	5900	0.95 J	8.1	79	0.29 J	0.55	22000	21		6.1	85	29000
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated	5700	< 0.36 U	5.2	36	0.23 J	0.1 J	29000	8.8		5.3	17	14000
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated	5600	< 0.36 U	5.8	59	0.2 J	0.11 J	37000	7.6		5.1 J	20	14000
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated	4000	< 0.37 U	4.7	26	0.17 J	0.072 J	37000	5.8		3.8 J	13	11000
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated	6600	< 0.36 U	4.2	48	0.23 J	0.065 J	35000	11		5.4	21	15000
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated	4600	< 0.37 U	6.2	27	0.19 J	0.085 J	47000	6.2		4.1 J	18	10000
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated	5100	< 0.35 U	4.2	54	0.19 J	0.075 J	34000	8.1		4.4 J	18	12000
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated	5000	< 0.38 U	6.2	45	0.28 J	0.14 J	14000	7.4		5.6	15	13000
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated	5100	< 0.35 U	5.5	41	0.19 J	0.064 J	13000	8		5 J	13	13000
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated	6300	< 0.39 U	6.2	36	0.29 J	0.13 J	22000	7.9		5.3 J	16	14000
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated	4700	< 0.42 U	4.6	53	0.21 J	0.11 J	35000	6.8		4.6 J	12	11000
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated	5300	< 0.36 U	4.5	43	0.21 J	0.12 J	39000	9.1		5 J	21	14000
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated	5800	< 0.36 U	5	43	0.21 J	0.061 J	35000	16		5.4	21	14000
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated	4900	< 0.35 U	3.7	45	0.19 J	0.075 J	38000	6.3		4.6 J	25	12000
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated	5300	< 0.39 U	6.7	37	0.21 J	0.14 J	64000	8.1		5.1 J	18	13000
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated	4600	< 0.34 U	3.2	39	0.16 J	0.098 J	40000	6.7		4.1 J	15	11000
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated	7200	< 0.37 U	5.2	40	0.29 J	0.096 J	8400	12		6.5	15	16000
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated	4400	< 0.38 U	3.7	56	0.17 J	0.14 J	88000	6.3		4.1 J	24	11000
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	6200	< 0.36 U	4.7	56	0.25 J	0.12 J	22000	8.1		5.3	21	14000
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated	5200	< 0.33 U	4.1	36	0.21 J	0.11 J	28000	8.7		4.7 J	18	13000
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated	5500	< 0.36 U	5.1	33	0.25 J	0.15 J	35000	7.6		5.5	20	14000
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated	4900	< 0.32 U	4	40	0.2 J	0.18 J	40000	8.5		4.5 J	15	11000
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated	6100	< 0.36 U	4.1	49	0.22 J	0.14 J	37000	11		5.1 J	19	14000
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated	4500	< 0.26 U	3.4	54	0.18 J	0.1 J	40000	7.9		6	17	13000
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated	4000	< 0.37 U	5.2	23	0.19 J	0.098 J	4600	6.7		3.4 J	24	11000
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated	4700	< 0.4 U	5	29	0.22 J	0.13 J	27000	6.2		4.7 J	15	12000
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated	4900	< 0.33 U	5.1	31	0.18 J	0.22 J	34000	7.4		4.1 J	19	13000
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated	4400	< 0.35 U	3.6	26	0.18 J	0.091 J	43000	6.2		4 J	14	11000

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	25	1900	700	< 0.015 U	15	790	< 0.57 U	< 0.12 U	57 J		< 0.35 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated	23	11000	500	0.15	17	820	0.78 J	< 0.12 U	130 J		< 0.35 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated	11	9400	550	< 0.014 U	13	650	< 0.58 U	< 0.12 U	67 J		< 0.36 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated	8.9	2100	500	0.02 J	15	790	< 0.52 U	< 0.11 U	51 J		< 0.32 U
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated	10	5100	430	0.019 J	15	850	< 0.61 U	< 0.12 U	< 31 U		< 0.38 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated	6.4	11000	550	< 0.014 U	15	710	0.75 J	< 0.11 U	83 J		< 0.32 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated	9.5	6900	430	< 0.013 U	13	720	1.1	< 0.11 U	81 J		< 0.35 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated	5.7	4500	340	< 0.016 U	13	620	< 0.59 U	< 0.12 U	56 J		< 0.37 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated	13	6500	750	0.02 J	17	760	< 0.56 U	< 0.11 U	82 J		< 0.35 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated	8.7	3200	390	< 0.014 U	9.7	590	< 0.5 U	< 0.1 U	77 J		< 0.31 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated	8.3	2200	400	< 0.016 U	14	770	< 0.58 U	< 0.12 U	59 J		< 0.36 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated	7.8	6100	510	< 0.015 U	14	840	< 0.59 U	< 0.12 U	74 J		< 0.37 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated	8.1	7400	510	< 0.016 U	14	660	< 0.61 U	< 0.12 U	54 J		< 0.38 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated	12	5600	550	< 0.014 U	13	710	0.83 J	< 0.11 U	74 J		< 0.33 U
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated	8.9	4000	430	< 0.015 U	14	610	< 0.56 U	< 0.11 U	91 J		< 0.35 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated	19	2300	1500	0.36	15	670	< 0.6 U	< 0.12 U	55 J		< 0.38 U
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated	9.6	1800	670	< 0.016 U	13	860	< 0.61 U	< 0.12 U	48 J		< 0.38 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated	22	1900	780	0.039	17	940	< 0.57 U	< 0.12 U	50 J		< 0.36 U
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated	9.7	9700	480	< 0.013 U	12	680	0.64 J	< 0.11 U	80 J		< 0.35 U
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	13	7200	480	0.28	19	760	0.57 J	< 0.11 U	100 J		< 0.34 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated	7.6	9500	390	< 0.013 U	15	770	< 0.53 U	< 0.11 U	89 J		< 0.33 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated	5.9	11000	440	< 0.014 U	13	780	0.85 J	< 0.11 U	100 J		< 0.34 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated	6	10000	380	< 0.014 U	11	590	< 0.55 U	< 0.11 U	84 J		< 0.34 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated	6.6	13000	400	< 0.013 U	17	720	0.81 J	< 0.12 U	99 J		< 0.36 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated	14	12000	420	< 0.014 U	14	810	0.88 J	< 0.11 U	110 J		< 0.34 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated	12	16000	480	< 0.015 U	15	640	< 0.54 U	< 0.11 U	72 J		< 0.33 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated	6.8	6200	540	< 0.017 U	13	720	0.76 J	< 0.11 U	78 J		< 0.34 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated	21	15000	550	< 0.016 U	24	1300	< 0.59 U	< 0.12 U	99 J		< 0.37 U
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated	10	4100	570	< 0.016 U	18	660	< 0.56 U	< 0.12 U	55 J		< 0.35 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated	7.7	3700	440	< 0.015 U	12	680	< 0.57 U	< 0.12 U	66 J		< 0.35 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated	8	6100	490	< 0.015 U	16	810	< 0.52 U	< 0.11 U	72 J		< 0.32 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated	5.9	8400	410	< 0.013 U	12	660	0.94 J	< 0.11 U	73 J		< 0.33 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated	7.3	20000	360	< 0.014 U	12	750	1.3	< 0.12 U	100 J		< 0.35 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated	6.2	11000	410	< 0.016 U	14	730	0.56 J	< 0.11 U	72 J		< 0.35 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated	7	14000	460	< 0.015 U	12	720	0.62 J	< 0.11 U	82 J		< 0.34 U
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated	38 J	7200 J	500	0.044	36	680	0.64 J	< 0.11 U	78 J		< 0.35 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated	6.5	3900	340	< 0.015 U	12	670	0.67 J	< 0.12 U	72 J		< 0.36 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated	9.2	6000	500	< 0.015 U	20	760	< 0.56 U	< 0.11 U	58 J		< 0.35 U
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated	13	2400	790	< 0.017 U	17	790	< 0.55 U	< 0.11 U	41 J		< 0.35 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated	7.5	2800	280	< 0.015 U	13	830	< 0.55 U	< 0.11 U	45 J		< 0.34 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated	15	9900	320	< 0.016 U	9.2	500 J	0.65 J	< 0.12 U	63 J		< 0.38 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated	8.7	1300	350	< 0.018 U	12	610	< 0.6 U	< 0.12 U	56 J		< 0.37 U
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated	8	12000	390	< 0.014 U	12	550	0.63 J	< 0.11 U	70 J		< 0.33 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated	9.6	13000	450	< 0.014 U	14	680	1.2	< 0.11 U	110 J		< 0.32 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated	4.4	5200	240	< 0.016 U	9	420 J	0.81 J	< 0.12 U	53 J		< 0.36 U
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated	7	8000	510	< 0.014 U	14	910	1.1	< 0.11 U	98 J		< 0.35 U
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	56	5700	390	0.12	30	660	0.65 J	< 0.11 U	92 J		< 0.33 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated	6	5000	350	< 0.014 U	13	700	< 0.55 U	< 0.11 U	68 J		< 0.34 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated	6	6900	720	< 0.015 U	12	650	< 0.54 U	< 0.11 U	73 J		< 0.34 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated	5.6	9700	300	< 0.014 U	9.5	550	< 0.55 U	< 0.11 U	67 J		< 0.34 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated	9.2	11000	320	0.015 J	15	750	0.55 J	< 0.11 U	77 J		< 0.34 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated	4.8	16000	290	< 0.014 U	10	710	0.96 J	< 0.11 U	84 J		< 0.35 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated	6.9	11000	360	< 0.016 U	11	660	0.72 J	< 0.11 U	34 J		< 0.33 U
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated	9.9	6600	690	< 0.015 U	13	650	< 0.58 U	< 0.12 U	62 J		< 0.36 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated	31	4600	350	< 0.014 U	11	730	< 0.53 U	< 0.11 U	47 J		< 0.33 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated	8.1	4200	340	< 0.016 U	14	810	0.62 J	< 0.12 U	< 30 U		< 0.37 U
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated	6.4	10000 J+	540	< 0.016 U	11	760	< 0.63 U	< 0.13 U	90 J		< 0.39 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated	10	9700	480	< 0.014 U	12	650	0.64 J	< 0.11 U	75 J		< 0.34 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated	5.1	9500	330	< 0.014 U	13	570	0.75 J	< 0.11 U	78 J		< 0.34 U
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated	3.5	6200	530	< 0.015 U	11	560	0.64 J	< 0.11 U	69 J		< 0.33 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated	6.4	10000	480	< 0.015 U	13	730	0.82 J	< 0.12 U	96 J		< 0.37 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated	5	12000	340	< 0.013 U	9.9	560	0.56 J	< 0.11 U	92 J		< 0.32 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated	18	3900	400	< 0.014 U	16	760	< 0.57 U	< 0.12 U	60 J		< 0.35 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated	5	6600	370	< 0.015 U	11	620	1.2	< 0.12 U	100 J		< 0.36 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	11	8300	500	< 0.023 U	13	570	< 0.54 U	< 0.11 U	66 J		< 0.34 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated	6.8	6500	380	< 0.023 U	12	490	0.71 J	< 0.1 U	60 J		< 0.31 U
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated	7.3	3900	420	< 0.024 U	14	650	< 0.55 U	< 0.11 U	73 J		< 0.34 U
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated	10	7700	310	< 0.023 U	12	640	0.49 J	< 0.098 U	68 J		< 0.3 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated	6.1	8500	450	< 0.021 U	14	770	< 0.54 U	< 0.11 U	82 J		< 0.34 U
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated	4.7	7000	380	< 0.021 U	12	650	0.61 J	< 0.081 U	59 J		< 0.25 U
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated	8.3	1800	290	< 0.025 U	9.2	470 J	< 0.57 U	< 0.12 U	< 66 U		< 0.35 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated	6.4	4800	240	< 0.026 U	11	660	< 0.6 U	< 0.12 U	< 71 U		< 0.38 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated	33	5300	290	< 0.023 U	11	560	< 0.5 U	< 0.1 U	61 J		< 0.31 U
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated	6.6	12000	360	< 0.023 U	10	530	< 0.53 U	< 0.11 U	73 J		< 0.33 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated		11	80
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated		11	73
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated		9.2	46
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated		12	69
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated		12	52
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated		12	65
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated		8.8	45
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated		8.6	47
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated		12	68
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated		7.7	38
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated		11	50
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated		15	67
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated		12	61
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated		9.7	51
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated		9.1	56
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated		26	85
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated		12	45
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated		12	74
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated		8.7	43
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated		11	140
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated		11	61
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated		9.1	48
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated		7.9	38
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated		15	40
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated		9.6	45
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated		9.5	49
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated		9.7	43
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated		20	63
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated		10	58
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated		9.6	68
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated		12	58
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated		8.7	42
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated		8.9	46
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated		12	75
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated		9.8	48
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated		11	130
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated		9.2	57
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated		12	59
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated		14	54
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated		10	46
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated		5.9	35
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated		7.4	33
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated		8.4	45
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated		8.8	49
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated		6.2	31
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated		10	49
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated		12	120
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated		9.4	47
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated		9.2	42
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated		7.8	35
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated		9.9	49
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated		7.1	45
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated		8.3	43
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated		9.1	62
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated		9.6	42
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated		11	47
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated		8	38
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated		9.2	55
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated		9.9	49
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated		7.5	45
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated		9.7	40
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated		7.4	40
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated		11	52
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated		6.6	36
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated		9.6	69
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated		8.5	49
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated		10	49
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated		7.6	50
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated		11	45
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated		8.5	42
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated		7.7	54
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated		8.7	41
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated		7.5	63
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated		7.7	34

														Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated	4500	< 0.3 U	4	31	0.18 J	0.097 J	28000	8.5		4 J	16	11000
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated	5800	< 0.31 U	6.2	37	0.23 J	0.12 J	28000	9.2		5.6	18	14000
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated	4400	< 0.34 U	3.5	36	0.15 J	0.1 J	46000	7.6		4.4 J	17	11000
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated	6900	< 0.37 U	5.4	67	0.29 J	0.12 J	25000	12		6.1	21	16000
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated	4800	< 0.36 U	4.4	34	0.21 J	0.11 J	28000	6.7		4.6 J	15	12000
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated	6000	< 0.36 U	4.4	41	0.21 J	0.13 J	34000	10		5.7	21	15000
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated	5500	< 0.34 U	5	42	0.2 J	0.17 J	39000	7.7		5.7	14	14000
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated	5400	< 0.3 U	4.9	30	0.22 J	0.13 J	32000	8.4		6	20	13000
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated	5500	< 0.34 U	5.7	42	0.21 J	0.13 J	35000	8		5.2	17	14000
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated	6700	< 0.34 U	4.7	47	0.23 J	0.099 J	41000	8.9		6	20	16000
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated	6500	< 0.34 U	5	45	0.24 J	0.2 J	52000	8.9		6.2	25	16000
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated	8200	< 0.35 U	7.5	79	0.29 J	0.14 J	47000	11		7.9	25	19000
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	5100	< 0.38 U	4.6	31	0.25 J	0.079 J	21000	7.9		4.7 J	15	12000
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	5200	0.43 JT	9.0	48	0.21 J	0.19 J	35000	8.5		5.1	16	13000
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	5900	< 0.30 U	5.0	34	0.24 J	0.14 J	6400	8.0		5.1	21	13000
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	6100	< 0.25 U	5	37	0.23 J	0.058 J	36000	8		5.1	17	13000
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	5000	< 0.33 U	4.7	35	0.22 J	0.12 J	53000	10		5	14	14000
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	6200	< 0.32 U	4.9	81	0.24 J	< 0.035 U	24000	9.1		5.5	22	14000
Northern Athletic Field	B555	110421 09:45 SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated	4400	< 0.34 U	3.7	39	0.15 J	0.076 J	47000	6.2		4.4	15	11000
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated	3600	< 0.32 U	4.3	26	0.13 J	0.098 J	81000	5.0		3.9	22	9200
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated	6300	< 0.36 U	5.0	54	0.26 J	0.094 J	30000	8.2		5.7	18	14000
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated	4800	< 0.36 U	4.4	35	0.20 J	0.099 J	36000	6.4		4.5	16	11000
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated	4400	< 0.34 U	3.7	39	0.15 J	0.076 J	47000	6.2		4.4	15	11000
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	7400	< 0.36 U	11	180	0.54	0.33 J	7300	11		7.8	47	16000
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	8300	0.46 J	6.1	76	0.43 J	0.12 J	2200	12		6.7	29	17000
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	6200	< 0.37 U	8.1	99	0.40 J	0.21 J	9100	10		5.6	39	14000
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	6900 T	0.50 JT	5.2	51	0.33 J	0.17 J	20000 T	11		6.6	61 T	17000 T
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	4400	< 0.19 U	4.7	30	0.19 J	0.048 J	21000	5.6		4.3	14	10000
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	5200	0.27 J	5.0	40	0.21 J	< 0.052 U	11000	6.1		4.8	18	12000
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	4100	< 0.23 U	3.9	26	0.15 J	< 0.056 U	20000	5.2		3.8	15	9800
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	3600	< 0.21 U	3.4	32	0.14 J	0.069 J	36000	4.7		4.1	13	9500
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	3900	< 0.23 U	3.6	26	0.15 J	< 0.055 U	25000	5.0		3.9	17	10000
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	7500	< 0.21 U	7.2	67	0.45	0.11 J	7000	9.9		6.2	43	15000
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	5500	< 0.22 U	4.9	35	0.21 J	0.060 J	11000	6.6		5.4	22	13000
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	6500	< 0.22 U	5.9	47	0.29	0.068 J	17000	7.9		6.1	16	14000
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	4900	< 0.20 U	3.8	40	0.20 J	0.074 J	34000	6.3		4.4	15	11000
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	5700	< 0.23 U	5.6	39	0.26 J	0.074 J	4600	7.5		5.1	18	13000
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	5500	< 0.20 U	3.7	43	0.21 J	0.064 J	32000	6.7		5.1	18	12000
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	5900	< 0.24 U	4.4	83	0.22 J	0.088 J	22000	6.7		5.9	20	15000
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	4200	< 0.23 U	5.5	29	0.22 J	0.064 J	2800	5.8		4.8	15	12000
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	4400	< 0.22 U	3.0	27	0.16 J	< 0.052 U	19000	5.9		4.1	21	11000
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	4200	< 0.22 UT	3.6	54 T	0.17 J	0.081 J	66000	5.5		4.3	14	10000 B
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	4400	< 0.21 U	2.8	32	0.16 J	0.067 J	4200	4.7		3.6	25	9900
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	4200	< 0.27 U	3.3	37	0.18 J	0.082 J	31000	5.2		3.9 J	12	9700
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	3800	< 0.25 U	2.3	27	0.15 J	0.097 J	56000	4.7		3.1 J	12	8300
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	4900	< 0.26 U	3.0	25	0.18 J	0.075 J	33000	5.9		4.6	17	11000
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	3600	< 0.23 U	2.6	30	0.14 J	0.11 J	53000	4.6		3.4 J	13	8100
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	3600	< 0.20 U	2.8	31	0.15 J	0.070 J	30000	4.5		3.8	14	8500
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	5000	< 0.22 U	4.4	36	0.18 J	0.075 J	25000	6.3		4.8	17	12000
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	4200	< 0.25 U	3.8	25	0.16 J	0.11 J	45000	5.2		4.1	13	10000
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	4400	< 0.27 U	3.3	30	0.17 J	0.085 J	59000	6.0		4.1 J	14	10000
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	6900	0.38 J	7.6	82	0.31 J	0.36 J	1900	12		5.9	41	17000
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	8900	0.56 J	8.2	81	0.42	0.25 J	1600	12		6.7	33	19000
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	4800	0.39 J	4.7	51	0.20 J	0.16 J	700	6.9		4.5	21	11000
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	4300	< 0.23 U	3.8	27	0.17 J	0.071 J	20000	5.0		3.9	14	9600
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	4300	< 0.37 U	3.5	30	0.17 J	< 0.090 U	20000	5.2		3.3 J	13	9200
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated												
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	5500	< 0.26 U	5.2	38	0.24 J	0.098 J	8000	6.7		4.9	17	12000
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	6700	< 0.30 U	6.0	53	0.28 J	0.086 J	3400	8.1		5.7	23	14000
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	6000	< 0.32 U	4.5	41	0.24 J	0.094 J	9300	7.2		4.7 J	18	13000
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	5800	< 0.28 U	5.3	43	0.26 J	0.098 J	14000	7.4		5.2	18	13000
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	5600	< 0.30 U	5.4	37	0.25 J	0.081 J	3200	7.1		5.0	18	14000
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	5800	< 0.33 U	6.4	33	0.26 J	0.085 J	1400	7.9		5.4	18	14000
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	8500	< 0.27 U	6	58	0.29 J	0.087 J	3800	14		6.1	18	16000
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	5100	< 0.3 U	5.4	41	0.2 J	0.09 J	25000	9.3		4.7 J	18	12000
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	4400	< 0.3 U	6.3	34	0.15 J	0.13 J	44000	8		4.2 J	15	12000
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	6700	< 0.33 U	7.5	63	0.32 J	0.11 J	8600	8.6		5.5	24	16000 B
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	5700	< 0.28 U	5.7 B	62	0.25 J	0.086 J	590	6.6		5.0	17	14000
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	6100	< 0.31 U	6.6	59	0.28 J	0.087 J	2600	7.5		5.5	19	14000 B
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	5300	< 0.28 UT	7.3 B	33	0.30 JT	0.098 JT	1600 T	7.0 T		4.5 J	16	11000
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	5800	< 0.31 U	8.1	47	0.26 J	0.098 J	1100	7.9		5.1	18	15000 B
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	4000	< 0.31 U	4.3 B	34	0.18 J	0.081 J	5500	5.0		4.2 J	11	12000
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	10000	< 0.32 U	5.8	39	0.41 J	< 0.078 U	980	11		6.7	14	17000 B
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	8800	< 0.33 U	6.9	69	0.36 J	0.094 J	2300	11		7.1	22	18000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated	7	5000	290	0.025 J	11	530	< 0.46 U	< 0.093 U	56 J		< 0.28 U
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated	9	4800	390	< 0.022 U	14	650	0.72 J	< 0.097 U	61 J		< 0.3 U
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated	6.5	6100	330	< 0.023 U	11	510	0.64 J	< 0.1 U	75 J		< 0.32 U
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated	16	5300	390	< 0.023 U	16	630	0.66 J	< 0.11 U	< 66 U		< 0.35 U
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated	5.7	3500	290	< 0.023 U	12	540	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated	9	7500	360	< 0.022 U	14	560	0.55 J	< 0.11 U	68 J		< 0.34 U
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated	10	7800	610	< 0.022 U	13	660	0.87 J	< 0.11 U	71 J		< 0.33 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated	7.8	5000	380	< 0.023 U	14	530	< 0.45 U	< 0.092 U	< 53 U		< 0.28 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated	8.4	6300	430	< 0.021 U	13	620	< 0.52 U	< 0.11 U	65 J		< 0.32 U
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated	15	10000	410	< 0.023 U	15	800	< 0.51 U	< 0.1 U	70 J		< 0.32 U
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated	6.2	17000	470	< 0.019 U	16	800	0.53 J	< 0.11 U	90 J		< 0.32 U
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated	9	14000	430	< 0.02 U	19	960	< 0.53 U	< 0.11 U	91 J		< 0.33 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	6.0	5500	270	< 0.021 U	12	690	< 0.58 U	< 0.12 U	< 67 U		< 0.36 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	15 T	13000 T	390	< 0.018 U	12	540	< 0.48 U	< 0.098 U	64 J		0.53 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	8.3	3000	250	< 0.021 U	13	550	< 0.45 U	< 0.092 U	< 53 U		0.66 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	8.4	12000	340	< 0.018 U	13	830	0.47 J	< 0.076 U	72 J		< 0.23 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	8.7	6400	340	< 0.017 U	12	640	1.1	< 0.1 U	69 J		< 0.31 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	17	6200	480	< 0.017 U	14	720	< 0.49 U	< 0.1 U	62 J		< 0.3 U
Northern Athletic Field	B555	110421 09:45 SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated	7.6	4100	320	< 0.019 U	11	450 J	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated	4.9	5100	280	0.048 J	9.6	500	< 0.42 U	< 0.073 U	66 J		< 0.36 U
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated	6.8	5600	360	< 0.019 U	14	920	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated	6.8	5200	310	< 0.020 U	11	640	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated	7.6	4100	320	< 0.019 U	11	450 J	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	76	1600	540	0.12	22	750	0.68 J	< 0.081 U	98 J		< 0.40 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	16	2500	430	0.030 J	21	730	0.52 J	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	48	1700	270	0.093 J	18	600	0.52 J	< 0.083 U	76 J		< 0.41 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	13	4200 T	420 T	0.025 J	25	730	< 0.45 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	5.2	3100	280	0.024 J	11	460	< 0.29 U	< 0.064 U	45 J		< 0.18 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	6.0	3000	320	0.019 J	12	450	0.41 J	< 0.074 U	49 J		< 0.20 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	10	2800	260	0.021 J	9.4	350 J	0.39 J	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	4.8	7000	260	0.019 J	9.7	290 J	0.60 J	< 0.071 U	50 J		< 0.19 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	5.3	3200	250	0.021 J	9.6	360 J	0.54 J	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	26	4100	340	0.051	20	780	0.47 J	< 0.070 U	45 J		< 0.19 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	6.9	4000	350	< 0.020 U	13	480	< 0.34 U	< 0.076 U	39 J		< 0.21 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	12	5900	300	< 0.017 U	14	710	< 0.34 U	< 0.076 U	52 J		< 0.21 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	5.9	4100	240	< 0.021 U	11	480	0.45 J	< 0.067 U	57 J		< 0.18 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	6.3	3200	390	< 0.025 U	13	570	< 0.35 U	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	4.8	3200	250	< 0.019 U	13	460	0.35 J	< 0.070 U	42 J		< 0.19 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	5.9	4100	680	< 0.023 U	13	490	0.37 J	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	32	1600	330	0.034	13	420	< 0.35 U	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	4.7	3100	240	< 0.018 U	10	360	< 0.33 U	< 0.074 U	40 J		< 0.20 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	5.4	10000 T	370	< 0.018 U	11	420	1.2	< 0.074 U	58 J		< 0.20 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	4.3	2600	360	< 0.020 U	9.4	440	< 0.32 U	< 0.072 U	< 36 U		< 0.20 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	4.0	2900	320	< 0.020 U	9.6	440	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	4.4	4400	200	< 0.017 U	8.3	430	0.70 J	< 0.085 U	49 J		< 0.23 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	5.3	4900	300	< 0.015 U	12	440	0.54 J	< 0.089 U	47 J		< 0.24 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	11	2600	250	0.019 J	9.2	360 J	0.98	< 0.079 U	65 J		< 0.21 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	4.4	2800	220	< 0.021 U	9.6	310 J	0.52 J	< 0.068 U	35 J		< 0.19 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	5.7	3600	310	< 0.018 U	13	380	0.61 J	< 0.074 U	40 J		< 0.20 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	5.4	3800	280	< 0.017 U	10	370 J	0.45 J	< 0.086 U	47 J		< 0.24 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	10	7500	290	0.023 J	10	460	0.74 J	< 0.094 U	81 J		< 0.26 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	70	2000	340	0.079	22	530	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	49	2200	380	0.041	21	650	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	33	1400	370	0.036	13	390 J	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	6.9	3400	290	< 0.019 U	11	460	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	17	2800	360	< 0.024 U	9.2	490 J	< 0.57 U	< 0.13 U	< 63 U		< 0.35 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated										740	
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	11	2900	380	< 0.021 U	12	610	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	12	2800	390	0.028 J	14	690	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	12	4800	330	< 0.020 U	12	630	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	8.6	5000	370	< 0.021 U	13	680	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	8.1	2200	340	< 0.021 U	13	590	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	11	1900	370	0.028 J	14	710	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	9.8	2700	570	0.046	14	670	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	14	8900	440	0.038	12	610	< 0.45 U	< 0.1 U	52 J		< 0.28 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	9.1	8500	580	0.031	10	530	< 0.46 U	< 0.1 U	56 J		< 0.28 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	15	4800	520 B	0.56	15	720	< 0.51 U	< 0.11 U	66 J		< 0.31 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	8.5	1500	420	0.021 J	11	560	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	10	2300	520 B	0.11	13	710	< 0.48 U	< 0.11 U	120 J		< 0.29 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	7.3	1800	410	0.032	15	780	< 0.43 UT	< 0.096 UT	< 47 UT		< 0.26 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	41	1600	630 B	0.025 J	12	610	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	14	1300	280	0.054	8.8	490 J	< 0.46 U	< 0.10 U	58 J		< 0.29 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	8.5	2300	210 B	0.031	26	680	0.61 J	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	14	2900	700	0.038	18	1100	0.53 J	< 0.11 U	72 J		< 0.31 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated		9.2	35
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated		9.8	45
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated		7.3	40
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated		11	52
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated		7.2	38
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated		10	60
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated		8.6	44
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated		9.2	47
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated		8.6	49
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated		12	47
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated		10	66
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated		16	70
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated		9.6	43
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated		9.3	45
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated		11	50
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated		12	43
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated		7.9	43
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated		10	53
Northern Athletic Field	B555	110421 09:45 SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated		7	38
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated		6.2	32
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated		9.7	53
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated		8.0	45
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated		7.0	38
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated		16	120
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated		14	62
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated		13	71
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated		10	90 T
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated		7.0	37
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated		7.4	44
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated		6.3	44
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated		5.9	47
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated		6.7	36
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated		12	74
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated		9.5	61
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated		10	68
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated		7.2	39
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated		9.4	44
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated		7.6	44
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated		9.0	49
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated		7.9	47
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated		7.0	37
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated		7.3	37 T
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated		6.3	34
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated		6.5	29
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated		5.6	28
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated		7.9	38
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated		5.3	34
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated		5.2	30
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated		7.2	62
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated		6.3	84
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated		7.1	35
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated		12	83
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated		14	77
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated		6.9	49
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated		7.0	38
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated		6.5	40
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated			
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated		9.2	55
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated		11	66
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated		9.7	59
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated		10	51
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated		9.5	48
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated		11	75
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated		12	49
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated		8	38
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated		6.3	39
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated		11	67
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated		9.5	46
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated		10	55
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated		10 T	38 T
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated		11	52
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated		7.0	31
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated		14	41
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated		14	55

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	3200	0.31 J	2.5	19	0.11 J	0.17 J	370 J	4.0		2.2 J	9.6	6700
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	5200	< 0.27 U	4.3	41	0.22 J	< 0.066 U	2500	6.7		3.7 J	14	13000
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	6300	< 0.30 U	5.8	77	0.32 J	0.15 J	15000	11		5.4	41	14000
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	8200	< 0.33 UT	6.1 T	54 T	0.33 JT	0.14 JT	9000 T	9.7 T		6.2 T	26 T	16000
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	6100	< 0.31 U	4.0	26	0.25 J	0.084 J	18000	7.3		4.7 J	16	13000
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	8800	< 0.32 U	7.9	53	0.39 J	0.13 J	2600	11		7.1	23	18000
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	6600	< 0.33 U	5.4	34	0.28 J	0.11 J	1500	9.7		5.8	22	14000
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	7200 B	< 0.30 U	6.7	35	0.30 J	0.091 J	580	7.8		5.1	17	16000
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	6700	< 0.29 U	11	55	0.35 J	0.15 J	820	7.8		6.8	31	17000
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	5700	< 0.26 U	4.5	38	0.24 J	0.26 J	590	6.9		4.6	20	13000
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	7500	< 0.30 U	5.1	37	0.29 J	0.093 J	800	8.3		5.1	18	15000
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	6000	< 0.31 U	5.6	31	0.24 J	0.080 J	500 J	7.8		4.7 J	18	14000
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	6700	< 0.26 U	5.8	31	0.29 J	0.12 J	640	7.9		5.4	23	14000
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	7000 B	< 0.30 U	5.6	35	0.38 J	0.17 J	610	8.3		5.4	24	16000
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	6900 B	< 0.28 U	5.9	29	0.30 J	0.076 J	630	7.5		5.2	19	14000
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	6900 B	< 0.30 U	7.7	52	0.34 J	0.12 J	770	8.5		6.0	20	16000
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	6600 B	< 0.29 U	5.0	41	0.28 J	0.12 J	900	7.4		5.4	20	15000
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	7200	< 0.32 U	7.0	35	0.32 J	< 0.077 U	570	8.7		5.9	17	15000
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	6400	0.35 J	5.9	43	0.30 J	< 0.078 U	630	7.9		5.0 J	19	14000
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	9800	< 0.46 U	8.1	60	0.49 J	0.11 J	790	11		8.1	25	21000
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	8400	0.35 J	9.4	64	0.44	0.13 J	890	11		6.7	30	19000
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	7600	< 0.31 U	3.5	37	0.30 J	< 0.076 U	500 J	8.7		5.1 J	19	12000
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	4500	< 0.29 U	4.8	33	0.21 J	0.12 J	24000	6.6		4.6 J	21	13000
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	4700	< 0.29 U	4.7	23	0.18 J	0.10 J	23000	5.9		4.6 J	17	12000 B
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	4500	< 0.30 U	3.0	32	0.17 J	0.11 J	30000	5.8		4.3 J	14	10000 B
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	4300	< 0.29 U	3.9	34	0.20 J	0.12 J	27000	6.0		4.0 J	15	11000 B
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	3900	< 0.30 U	3.6	54	0.16 J	0.12 J	45000	5.1		3.8 J	14	11000 B
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	4500	< 0.31 U	4.4	41	0.15 J	0.099 J	26000	5.4		4.1 J	16	10000 B
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	4800	< 0.27 U	4.7	47	0.20 J	0.14 J	57000	6.3		4.5	21	12000 B
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	4400	< 0.22 U	4.1	23	0.17 J	0.10 J	31000	5.9		4.5	17	11000
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	4500	< 0.21 U	3.6	30	0.16 J	0.088 J	29000	5.7		4.2	15	11000
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	4200	< 0.21 U	5.4	23	0.16 J	0.078 J	30000	5.8		4.1	15	11000
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	5000	< 0.29 U	5.1	47	0.24 J	0.078 J	20000	6.6		4.8 J	19	12000
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	5600	0.27 J	4.8	61	0.27 J	0.17 J	17000	7.8		6.3	24	13000
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	5700	< 0.31 U	5.4	33	0.25 J	0.16 J	1400	7.4		6.2	19	14000
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	4900	0.38 J	5.0	48	0.23 J	0.088 J	21000	6.3		4.7 J	20	12000
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	5300	< 0.27 U	5.2	32	0.20 J	0.066 J	600	6.5		4.2 J	15	12000
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	3600 T	< 0.31 UT	5.0	16 JT	0.14 J	0.15 J	24000	4.6 T		3.5 J	12 T	8200 T
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	5200	< 0.30 U	5.6	29	0.21 J	0.24 J	26000	8.3		4.8 J	33	12000
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	6000	< 0.31 U	4.8	36	0.28 J	0.12 J	14000	7.6		5.4	17	14000
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	5700	0.34 J	7.6	41	0.27 J	< 0.075 U	460 J	7.4		5.4	16	14000 B
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	7500	< 0.31 U	6.1	55	0.32 J	0.10 J	21000	9.9		7.5	17	17000 B
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	4700	< 0.31 U	4.7	40	0.23 J	< 0.075 U	3400	5.8		4.2 J	12	11000 B
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	3000	< 0.30 U	3.4	15 J	0.12 J	< 0.072 U	610	4.0		2.3 J	7.0	8800 B
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	3500	< 0.22 U	3.2	29	0.15 J	0.056 J	9400	4.9		3.1 J	11	8300 B
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	7000	< 0.30 U	5.7	52	0.33 J	0.33 J	1400	8.8		7.1	20	15000 B
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	5800	< 0.28 U	4.2	39	0.24 J	0.080 J	21000	6.8		5.2	20	14000 B
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	3800	< 0.29 U	3.2	28	0.15 J	< 0.071 U	20000	4.8		3.6 J	13	8700 B
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	6100	2.0 T	14 T	74 T	0.42 T	0.54 T	3700 T	62 T		7.4 T	120 T	23000 B
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	3400	0.25 J	3.0	24	0.14 J	0.11 J	22000	4.6		2.9 J	14	7900
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	5500	< 0.27 U	6.2	39	0.25 J	0.085 J	18000	7.2		5.1	17	13000
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	5700	< 0.30 U	6.5	39	0.25 J	< 0.072 U	12000	7.0		4.6 J	16	12000
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	4200	< 0.30 U	4.8	33	0.17 J	< 0.074 U	25000	5.7		4.6 J	16	11000
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	4400	< 0.31 U	4.4	24	0.19 J	< 0.076 U	20000	5.9		4.5 J	13	11000
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	3900	< 0.31 U	4.2	31	0.16 J	< 0.074 U	22000	5.0		4.5 J	13	11000
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	4300	< 0.27 U	5.0	21	0.19 J	0.065 J	27000	5.8		4.2 J	13	12000
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	8200	< 0.30 UT	7.0 T	57 T	0.37 JT	< 0.072 UT	11000	11 T		7.8	22 T	18000
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	3900	< 0.28 U	3.9	25	0.16 J	0.093 J	43000	5.3		4.0 J	14	9600
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	4900	< 0.30 U	4.2	28	0.18 J	< 0.072 U	27000	6.6		4.9	16	13000
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	4200	< 0.20 U	3.6	24	0.16 J	< 0.047 U	4000	5.7		3.7	13	9800
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	3200	< 0.28 U	3.5	19	0.14 J	< 0.067 U	6100	4.1		3.2 J	9.8	8000
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	3000	0.22 J	2.7	25	0.12 J	< 0.052 U	2700	5.9		2.5 J	14	7900
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	3700	< 0.26 U	4.3	21	0.16 J	< 0.062 U	6700	4.7		3.1 J	11	8700
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	3800	< 0.25 U	3.5	21	0.15 J	< 0.059 U	3100	5.4		3.0 J	11	8500
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	6100	< 0.30 U	4.5	30	0.24 J	< 0.073 U	490 J	6.9		4.4 J	14	13000
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	7400	< 0.30 U	5.7	37	0.28 J	< 0.073 U	530	8.8		5.5	17	16000
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	7800	< 0.29 U	7.3	40	0.31 J	< 0.071 U	630	9.0		6.8	19	16000
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	4500	< 0.26 U	4.3	28	0.20 J	< 0.064 U	25000	5.7		4.1 J	15	11000 B
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	6500 T	< 0.34 UT	6.5	49 T	0.28 JT	0.23 JT	9300 T	8.0 T		5.9	33 T	15000 BT
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	6700	< 0.28 U	5.8	42	0.31 J	< 0.068 U	4400	7.6		5.7	19	15000 B
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	6700	< 0.32 U	6.6	40	0.31 J	< 0.078 U	6700	8.9		6.2	22	16000 B
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	5700	< 0.31 U	6.4	35	0.27 J	< 0.074 U	2300	7.0		5.0 J	22	14000 B
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	5800	< 0.27 U	5.6	47	0.24 J	< 0.067 U	29000	6.3		5.0	17	13000 B
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	6400	< 0.29 U	5.7	46	0.28 J	0.10 J	18000	7.8		5.7	20	14000 B

DRAFT

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	4.8	870	270	0.033	5.5	400 J	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	13	1500	430	0.63	15	700	< 0.42 U	< 0.094 U	67 J		< 0.26 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	46	2500	290	0.64	17	800	< 0.46 U	< 0.10 U	88 J		< 0.28 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	17 T	2600 T	500	< 0.023 UT	16 T	1100 T	< 0.50 UT	< 0.11 UT	59 JT		< 0.31 UT
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	6.6	3200	390	< 0.016 U	12	770	0.54 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	12	2900	670	< 0.021 U	18	1200	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	8.2	2100	520	0.023 J	13	890	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	6.9	1900	310	0.030 J	13	420 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	10	1700	990 B	0.093	13	620	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	17	1500	410 B	0.14	14	480	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	6.2	1900	300 B	0.024	13	540	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	6.9	1700	350 B	< 0.022 U	12	510	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	12	1700	360 B	0.18	14	530	< 0.39 U	< 0.088 U	< 44 U		< 0.24 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	6.4	1900	300	0.029 J	14	550	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	7.6	1700	340	0.037	12	540	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	10	1600	580	0.033	15	660	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	8.3	1800	520	0.022 J	13	530	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	8.8	2000	340	0.018 J	14	500 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	15	1500	320	0.019 J	12	480 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	12	2400	540	< 0.031 U	20	730 J	< 0.71 U	< 0.16 U	< 78 U		< 0.44 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	14	2500	590	0.024 J	18	950	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	18	1800	140	0.19	21	540	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	7.6	3100	300	< 0.018 U	11	480	< 0.45 U	< 0.10 U	< 50 U		< 0.27 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	4.9	2900	290	< 0.020 U	11	560	0.67 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	4.5	3600	310	< 0.021 U	11	450 J	0.64 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	7.3	4900	300	0.071	10	610	0.49 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	5.5	3100	280	< 0.019 U	10	480 J	0.61 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	5.0	2800	340 T	< 0.018 U	10	410 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	13	11000	350 T	0.14	13	540	0.60 J	< 0.092 U	57 J		< 0.25 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	5.0	3400	270	< 0.021 U	11	430	0.60 J	< 0.075 U	47 J		< 0.21 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	5.0	3200	280	< 0.022 U	11	420	< 0.31 U	< 0.071 U	49 J		< 0.19 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	6.3	4000	230	< 0.021 U	10	440	0.51 J	< 0.073 U	50 J		< 0.20 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	7.7	4500	230	< 0.019 U	12	700	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	18	3000	1400	0.82	15	630	0.66 J	< 0.091 U	50 J		< 0.25 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	26	2100	450	< 0.020 U	13	680	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	8.7	5600	250	< 0.020 U	11	730	< 0.44 U	< 0.099 U	51 J		< 0.27 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	6.5	1400	250	0.036	10	430 J	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	72 T	1900 T	370	0.16 T	8.6	420 J	< 0.46 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	12	4100	330	0.022 J	15	660	0.91 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	8.4	3600	430	< 0.014 U	14	570	< 0.48 U	< 0.11 U	56 J		< 0.29 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	8.6	1500	310	0.023 J	13	560	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	8.5	7000	320	< 0.018 U	19	780	< 0.47 U	< 0.11 U	58 J		0.46 J
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	27	2100	540	0.16	10	460 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	3.8	870	110	0.12	5.9	200 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	5.9	2500	210	0.033	8.7	320 J	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	13	2100	850	0.15	27	680	< 0.45 U	< 0.10 U	< 50 U		0.47 J
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	5.7	7300	310	0.022 J	13	470	< 0.42 U	< 0.095 U	52 J		< 0.26 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	5.4	4100	330	0.048	10	370 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	66 T	2100	360	0.24 T	160 T	600 T	2.8 T	1.3 T	< 52 UT		0.45 JT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	6.8	2900	210	0.020 J	10	350 J	< 0.34 U	< 0.077 U	43 J		< 0.21 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	13	3400	340	0.020 J	12	600	< 0.41 U	< 0.094 U	55 J		< 0.26 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	13	4000	330	0.029 J	12	620	< 0.45 U	< 0.10 U	70 J		< 0.28 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	6.2	3500	400	< 0.014 U	12	530	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	7.0	4800	210	0.026 J	11	600	0.57 J	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	6.4	4000	440	< 0.017 U	10	480 J	< 0.46 U	< 0.10 U	< 52 U		0.33 J
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	6.5	3300	240	0.020 J	11	510	< 0.41 U	< 0.092 U	46 J		< 0.25 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	14 T	6600 T	470 T	0.060 T	19	1000 T	< 0.46 UT	< 0.10 UT	< 51 UT		< 0.28 UT
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	8.2	4400	310	0.077	9.5	510	0.99	< 0.096 U	69 J		< 0.26 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	7.7	3300	370	0.022 J	12	490	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	8.8	2700	290	0.057	10	490	< 0.30 U	< 0.067 U	< 33 U		< 0.18 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	5.8	4000	230	0.016 J	7.9	310 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	17	1500	170	0.040	10	290 J	< 0.33 U	< 0.073 U	62 J		0.21 J
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	11	2500	220	0.036	7.7	430	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	10	1800	250	0.068	8.1	500	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	5.6	1600	220	< 0.018 U	11	460 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	6.8	2000	310	< 0.019 U	13	550	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	8.8	1900	420	< 0.022 U	13	590	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	7.6	4400	270	< 0.017 U	10	530	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	13	4800 T	440	< 0.019 U	16	660 T	< 0.52 UT	< 0.12 UT	< 58 U		< 0.32 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	9.4	2600	410	< 0.019 U	18	620	< 0.43 U	< 0.096 U	< 47 U		0.28 J
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	9.1	3400	390	< 0.018 U	16	780	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	9.0	2200	450	< 0.021 U	13	680	< 0.47 U	< 0.11 U	< 52 U		0.32 J
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	7.7	4500	290	< 0.017 U	11	910	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	7.6	6900	340	< 0.021 U	15	810	< 0.45 U	< 0.10 U	< 50 U		< 0.27 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated		6.7	29
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated		11	41
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated		13	74
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated		13 T	58 T
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated		10	38
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated		14	64
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated		11	66
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated		11	46
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated		12	70
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated		10	57
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated		11	53
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated		9.5	56
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated		12	53
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated		12	70
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated		11	49
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated		11	55
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated		10	50
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated		11	40
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated		11	43
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated		16	58
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated		16	65
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated		12	40
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated		11	48
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated		7.3	37
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated		7.4	37
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated		8.3	37
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated		6.3	36
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated		6.7	39
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated		8.1	43
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated		8.7	39
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated		7.9	43
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated		8.8	34
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated		8.6	40
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated		9.4	56
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated		9.7	53
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated		8.7	39
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated		9.8	36
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated		6.3 T	33 T
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated		10	93
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated		9.8	50
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated		12	46
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated		11	45
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated		8.2	36
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated		5.5	20
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated		6.2	27
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated		11	200
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated		8.9	46
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated		6.3	36
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated		24 T	290 T
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated		6.4	49
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated		9.5	52
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated		10	47
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated		7.5	35
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated		8.0	36
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated		8.7	39
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated		7.8	36
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated		13 T	84
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated		7.4	39
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated		9.2	43
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated		8.3	35
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated		5.5	29
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated		7.0	28
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated		6.7	43
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated		7.2	31
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated		9.5	37
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated		12	49
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated		13	44
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated		8.6	41
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated		11 T	170
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated		11	58
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated		13	52
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated		10	45
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated		11	43
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated		10	74

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	5600	< 0.28 U	6.2	35	0.25 J	< 0.068 U	13000	7.1		5.0	18	14000 B
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	4300	< 0.25 U	4.2	31	0.17 J	0.080 J	26000	5.7		4.5	16	11000
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	9700	< 0.29 U	4.4	100	0.35 J	< 0.071 U	1300	9.7		5.5	10	14000
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	6900	< 0.28 U	7.0	61	0.34 J	0.12 J	2700	8.7		5.9	21	14000
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	4700	< 0.23 U	2.0	16	0.16 J	< 0.056 U	6300	5.3		3.3 J	8.8	9700
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	6000	< 0.27 U	3.6	21	0.22 J	< 0.065 U	380 J	6.8		3.4 J	9.4	11000
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	8700	< 0.30 UT	4.9	97 T	0.35 J	< 0.073 U	1800 T	9.3		4.6 J	14	13000
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	9300	< 0.29 U	8.7	79	0.43	< 0.069 U	7200	11		9.8	18	23000
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	5400	0.38 J	1.8	48	0.23 J	0.18 J	880	8.6		5.6	26	15000
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	5400	0.44 J	1.7	51	0.23 J	0.17 J	1100	8.0		5.9	23	15000
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	7100	0.54 J	4.0	74	0.33 J	0.15 J	3700	14		7.2	59	21000
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	5900	0.43 J	2.8	47	0.26 J	< 0.078 U	1200	10		5.6	24	17000
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	3300	< 0.30 U	3.5	18 J	0.14 J	< 0.072 U	35000	4.2		3.1 J	9.5	8100
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	4500	< 0.30 U	3.3	27	0.18 J	< 0.072 U	23000	5.5		3.7 J	13	9600
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	4200	< 0.30 U	4.6	27	0.17 J	< 0.072 U	31000	5.4		4.0 J	14	11000
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	2700	< 0.26 U	2.8	15 J	0.11 J	< 0.062 U	22000	3.6		2.5 J	9.4	7100
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	5400	< 0.27 U	5.6	40	0.24 J	< 0.066 U	6500	7.2		4.5	17	12000 B
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	5800	< 0.28 U	4.9	39	0.26 J	< 0.067 U	9000	7.4		4.4 J	17	12000 B
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	4100	< 0.31 U	4.3	25	0.18 J	< 0.075 U	17000	5.2		3.6 J	13	9600 B
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	3700	< 0.23 U	4.6	23	0.17 J	0.056 J	19000	5.2		3.5 J	13	9700
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	6700	< 0.32 U	5.8 J	78	0.43 J	0.14 J	1300	15		7.7	11	18000
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	6900	< 0.37 U	7.6	210	0.37 J	0.28 J	15000	10		6.4	27	16000 B
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	7500	< 0.38 U	7.0	52	0.39 J	0.066 J	3400	9.4		6.4	21	17000 B
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	8500	< 0.39 U	5.2	78	0.44 J	0.12 J	1500	12		8.4	21	19000
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	6100	< 0.37 U	5.1	54	0.26 J	< 0.049 U	14000	7.9		5.5	24	15000
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	5900	< 0.33 U	4.9	59	0.24 J	0.067 J	18000	7.5		5.7	18	14000
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	6200	< 0.33 U	5.0	40	0.25 J	0.076 J	11000	7.7		5.3	20	15000
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	7400	< 0.33 U	5.3	58	0.31 J	0.076 J	4300	9.4		6.4	19	16000
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	6200	< 0.29 U	7.7	48	0.22 J	0.16 J	19000	7.8		6.2	18	15000
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	6600	< 0.36 U	7.3	49	0.25 J	0.19 J	15000	8.6		6.3	20	15000
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	4400	< 0.31 U	3.5	37	< 0.046 U	0.15 J	43000	5.8		4.2	15	11000
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	4400	< 0.34 U	25	62	< 0.051 U	0.19 J	100000	6.4		8.5	21	18000
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	4600	< 0.35 U	2.2	41	< 0.052 U	0.14 J	56000	5.7		4.0	23	11000
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	4800	< 0.37 U	4.4	61	< 0.055 U	0.14 J	100000	6.5		5.8	25	13000
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	6400	< 0.31 U	4.2	41	< 0.046 U	0.14 J	58000	8.6		6.6	20	15000
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	4400	< 0.28 U	3.6	37	< 0.042 U	0.10 J	81000	5.8		4.4	17	11000
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	6700	< 0.29 U	5.0	54	0.18 J	0.27 J	28000	9.9		6.6	35	17000
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	4700	< 0.33 U	3.1	42	< 0.050 U	0.19 J	120000	6.6		4.6	13	11000
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	4400	< 0.28 U	3.9	28	0.048 J	0.11 J	28000	5.8		4.5	17	11000
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	6000	< 0.22 U	5.8	52	0.26 J	0.12 J	37000	8.2		6.2	27	15000
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	5000	< 0.17 U	4.1	28	0.18 J	0.37	38000	6.5		5.8	19	12000
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	7300	< 0.21 U	5.1	53	0.28	0.44	21000	8.6		7.2	17	17000 B
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	5600	< 0.23 U	4.3	56	0.22 J	0.41	64000	7.4		6.0	18	13000 B
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	5400	< 0.19 U	4.8	32	0.21 J	0.44	53000	6.8		6.1	20	13000
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	4900	< 0.21 UT	3.3	31	0.20 J	0.34	39000 T	6.5		4.9	17	12000
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	5800	0.58	3.0	41	0.19 J	< 0.042 U	54000	6.5		5.2	22	13000
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	5000	0.70 J	6.1	36	0.19 J	< 0.053 U	52000	5.9		4.8	16	14000
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	4300	0.69	< 3.9 U	31	0.16 J	< 0.046 U	81000	5.3		4.1	19	12000
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	4500	0.84	5.6	28	0.18 J	< 0.052 U	90000	5.7		4.7	16	15000
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	6600	0.85	9.0	53	0.26 J	< 0.056 U	43000	7.8		6.1	16	16000
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	4200	< 0.19	4.2	33	0.15	0.039	39000	7.1		3.9	21	11000
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	6000	0.28	5.7	47	0.23	< 0.014	33000	6.8		5.7	18	15000
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	4300	< 0.38	4.6	31	0.17	0.03	54000	5.8		4	13	11000
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	5300	< 0.38 U	5.1	29	0.21 J	0.64	3600	7.5		4.9 J	22	14000
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	4600	< 0.36 U	4	52	0.16 J	0.054 J	28000	6.1		4.9 J	17	12000
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	7300	2.3	7.3	75	0.34 J	0.27 J	7600	51		6.2	30	19000
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	5400	< 0.31 U	3.7	39	0.22 J	0.18 J	43000	10		5.8	17	13000
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	5800	< 0.39 U	4.4	45	0.24 J	0.092 J	9600	14		4.9 J	21	14000
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated	6600	< 0.38 U	4.9	45	0.26 J	0.11 J	14000	8.6		5.8	25	16000
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	6500	< 0.38 U	5	52	0.28 J	0.12 J	34000	9.8		5.8	21	15000
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated	6400	< 0.34 U	4.7	60	0.23 J	0.13 J	41000	9.9		6	22	16000
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated	4000	0.38 J	4.2	37	0.18 J	0.1 J	59000	13		3.8 J	19	11000
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated	5700	< 0.37 U	4.4	62	0.22 J	0.09 J	38000	8.4		5.3 J	21	13000
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	5800	< 0.37 U	3.9	45	0.21 J	0.099 J	43000	13		5.4	20	14000
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	5000	< 0.35 U	5.7	32	0.22 J	0.087 J	40000	8		5 J	17	13000
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	4800	< 0.37 U	4.1	44	0.21 J	0.082 J	41000	9.4		4.5 J	15	12000
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	5000	< 0.38 U	5.2	47	0.22 J	0.1 J	36000	9.7		4.9 J	17	13000
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	7100	< 0.35 U	5	43	0.28 J	0.11 J	35000	17		6.1	22	17000
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	6600	< 0.37 UJ	6.1	65	0.26 J	0.16 J	18000	20		5.8	31	17000
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	6400	< 0.37 U	5.1	37	0.25 J	0.092 J	17000	9		5.7	21	15000
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	6000	< 0.35 U	4.3	47	0.22 J	0.11 J	71000	11		5.5	21	14000
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	6200	< 0.37 U	4.8	46	0.2 J	0.094 J	40000	9.5		5.6	22	14000
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	5200	< 0.35 U	4.9	57	0.19 J	0.098 J	77000	9.7		4.8 J	17	12000
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	6000	< 0.39 U	4.9	570	0.25 J	0.1 J	76000	9.8		5.6 J	21	14000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	8.7	4500	380	< 0.019 U	12	600	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	6.2	5200	420	< 0.020 U	11	450	0.50 J	< 0.085 U	< 42 U		0.29 J
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	20	1700	380	0.031 J	12	490	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	230	1700	610	0.094	13	510	0.55 J	< 0.097 U	54 J		< 0.26 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	4.0	2200	190	< 0.019 U	8.9	360 J	< 0.35 U	< 0.079 U	72 J		0.26 J
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	5.1	1300	160	< 0.018 U	8.7	480	< 0.41 U	< 0.092 U	< 46 U		< 0.25 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	62 T	1500	460	0.13	11	510	0.73 J	< 0.10 U	57 J		< 0.28 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	11	3100	560	< 0.019 U	20	1000	0.47 J	< 0.098 U	< 48 U		0.33 J
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	54	1800	390	0.025	18	180 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	26	1700	480	0.051	17	190 J	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	60	2500	480	0.047	40	310 J	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	20	1700	380	0.043	20	240 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	4.1	3500	240	< 0.0079 U	7.2	520	0.45 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	4.6	4100	190	< 0.0079 U	9.0	650	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	5.6	5500	260	< 0.0078 U	9.7	530	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	3.5	2200	220	< 0.0079 U	6.0	340 J	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	8.0	1800	360	0.022	11	620	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	7.7	4600	340	0.020	12	810	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	5.8	6300	270	0.012 J	8.8	580	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	4.7	4100	190	0.011 J	9.0	560	< 0.35 U	< 0.078 U	43 J		< 0.21 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	3.8	2400	2600	< 0.022 U	24	630	< 2.1 U	< 0.073 U	< 56 U		6.3 J
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	66	4100	450	1.1	18	740	< 0.48 U	< 0.084 U	120 J		< 0.41 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	16	2300	380	0.085 J	17	760	< 0.50 U	< 0.086 U	66 J		< 0.42 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	6.8	2800	1000	< 0.018 U	23	860	< 0.51 U	< 0.089 U	< 69 U		2.9
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	6.4	3600	300	< 0.019 U	14	560	< 0.48 U	< 0.082 U	64 J		< 0.41 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	6.2	3100	350	< 0.022 U	15	530	< 0.43 U	< 0.075 U	68 J		< 0.37 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	6.1	3400	400	< 0.018 U	15	490	< 0.43 U	< 0.075 U	66 J		< 0.37 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	8.6	3200	560	0.019 J	16	760	< 0.43 U	< 0.074 U	59 J		< 0.37 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	16	4100	440	0.023 J	17	610	< 0.37 U	0.089 J	< 50 U		< 0.32 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	20	4000	490	0.024 J	18	690	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	6.1	3700	310	0.022 J	11	410 J	< 0.40 U	< 0.070 U	66 J		< 0.34 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	9.4	4200	340	< 0.018 U	19	310 J	< 0.44 U	< 0.077 U	71 J		< 0.38 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	3.9	5200	460	0.025 J	11	380 J	< 0.45 U	< 0.078 U	74 J		< 0.38 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	7.4	4300	540	0.029 J	15	380 J	< 0.48 U	< 0.083 U	98 J		< 0.41 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	7.3	4300	410	0.022 J	18	400 J	< 0.40 U	< 0.070 U	57 J		< 0.34 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	7.6	3300	250	0.048 J	12	370 J	< 0.37 U	< 0.063 U	60 J		< 0.31 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	15	4500	310	0.026 J	24	490	< 0.39 U	< 0.067 U	98 J		< 0.33 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	6.9	3600	520	< 0.022 U	13	420 J	< 0.43 U	< 0.075 U	120 J		< 0.37 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	6.8	2300	280	0.021 J	13	430	< 0.37 U	< 0.064 U	64 J		< 0.31 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	13	7400	500	< 0.017 U	17	460	< 0.34 U	< 0.076 U	54 J		0.56 J
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	7.4	3800	320	< 0.020 U	15	140 J	< 0.25 U	< 0.057 U	40 J		< 0.15 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	10	4300	330 B	< 0.023 U	17 B	410	< 0.32 U	< 0.072 U	37 J		< 0.20 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	8.5	7000	380 B	< 0.022 U	15 B	270 J	< 0.34 U	< 0.078 U	60 J		< 0.21 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	8.9	11000	470	< 0.021 U	15	230 J	< 0.29 U	< 0.064 U	58 J		< 0.18 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	6.6	8900	210 T	< 0.019 U	13	260 J	< 0.32 U	< 0.071 UT	47 J		< 0.19 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	8.9	6600	270	3.8	13	380	< 0.26 U	< 0.30 U	54 J		< 0.16 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	7.5	4800	310	0.061	11	360	< 0.34 U	< 0.076 U	52 J		< 0.21 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	8.6	4400	330	1.1	11	330	< 0.29 U	< 0.065 U	55 J		< 0.18 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	9.7	5600	350	0.58	12	360	< 0.32 U	< 0.073 U	79 J		0.28 J
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	9.6	5300	420	0.063	15	520	< 0.35 U	< 0.079 U	45 J		0.36 J
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	7	14000	300	< 0.011	9.4	510	< 0.25	< 0.038	65		< 0.14
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	6.4	8800	480	< 0.012	14	520	0.99	< 0.04	60		< 0.15
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	16	20000	330	< 0.011	9.7	510	< 0.26	< 0.039	64		< 0.14
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	12	3000	380	0.014 J	11	550 J	< 0.58 U	< 0.12 U	58 J		< 0.24 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	4.4	6600	670	< 0.008 U	11	480 J	< 0.54 U	< 0.11 U	54 J		< 0.22 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	49	3200	510	0.2	87	770	2.5	< 0.11 U	130 J		< 0.34 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	8.6	15000	360	< 0.020 U	14	530	< 0.48 U	< 0.097 U	75 J		0.44 J
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	7.5	4000	430	0.038	12	640	< 0.58 U	< 0.12 U	59 J		< 0.36 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated	6.7	7600	450	< 0.014 U	13	820	< 0.58 U	< 0.12 U	64 J		< 0.36 U
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	8.4	6600	820	< 0.014 U	15	760	< 0.57 U	< 0.12 U	89 J		< 0.36 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated	7.3	7700	380	0.041	15	680	0.76 J	< 0.11 U	95 J		< 0.33 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated	7.1	22000	370	< 0.015 U	11	500 J	1	< 0.11 U	89 J		< 0.34 U
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated	5.9	13000	330	0.019 J	13	690	< 0.56 U	< 0.11 U	82 J		< 0.35 U
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	6.9	13000	420	0.029 J	14	< 59 U	0.93 J	< 0.11 U	93 J		< 0.34 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	9.5	10000	360	0.027 J	15	630	< 0.53 U	< 0.11 U	74 J		< 0.33 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	7.9	12000	410	0.015 J	11	590	0.59 J	< 0.11 U	95 J		< 0.35 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	7.3	9000	400	< 0.014 U	12	590	< 0.57 U	< 0.12 U	97 J		< 0.36 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	12	6700	430	0.037	16	830	< 0.53 U	< 0.11 U	94 J		< 0.33 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	59 J+	2800	620	0.16	14	630	< 0.57 U	< 0.12 U	94 J		< 0.35 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	8.1	8800	420	< 0.017 U	14	700	< 0.56 U	< 0.11 U	68 J		< 0.35 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	11	13000	480	< 0.013 U	14	730	0.94 J	< 0.11 U	37 J		< 0.33 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	8	6500	400	< 0.014 U	14	630	0.98 J	< 0.11 U	28 J		< 0.35 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	5.5	9500	290	< 0.014 U	11	700	1.2	< 0.11 U	54 J		< 0.33 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	9.7	13000	550	0.017 J	15	800	0.71 J	< 0.12 U	110 J		< 0.36 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated		11	50
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated		7.9	180
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated		15	48
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated		13	82
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated		6.9	42
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated		12	30
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated		15	58
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated		13	47
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated		11	79
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated		11	65
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated		14	84
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated		11	54
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated		6.1	27
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated		7.3	40
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated		7.7	38
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated		5.0	24
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated		10	44
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated		11	59
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated		7.6	34
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated		8.8	33
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated		10	69
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated		13	170 B
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated		13	75 B
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated		13	69
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated		9.2	52
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated		8.9	58
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated		9.5	62
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated		12	70
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated		11	72
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated		12	74
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated		6.8	39
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated		7.0	67
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated		6.4	46
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated		7.4	48
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated		9.8	68
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated		6.8	43
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated		11	73
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated		10	50
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated		7.0	43
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated		9.4	52
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated		8.1	63
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated		11	47
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated		9.2	51
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated		8.9	56
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated		7.9	74
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated		9.1	57
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated		7.0	45
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated		6.2	61
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated		7.4	210
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated		8.9	58
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated		7.7	42
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated		9.8	73
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated		7.1	36
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated		9.7	63
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated		8	37
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated		25	86
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated		9.7	48
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated		9.1	54
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated		11	57
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated		10	59
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated		11	54
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated		7.9	39
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated		8.8	45
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated		12	49
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated		8.7	50
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated		7.7	45
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated		7.9	48
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated		12	66
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated		12	87
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated		11	64
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated		9	44
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated		8.8	50
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.68	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated		7.6	42
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated		10	47

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	8300	< 0.41 U	6.7	63	0.37 J	0.098 J	1800	12		8.1	24	18000
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	6300	< 0.36 U	6.6	58	0.24 J	0.086 J	25000	8.8		5.6	28	14000
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	5600	< 0.38 U	6.1	59	0.21 J	0.12 J	49000	8.6		4.9 J	19	14000
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	7500	< 0.34 U	4.8	62	0.27 J	0.1 J	45000	12		7	26	16000
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	6000	< 0.37 U	5.4	45	0.21 J	0.17 J	44000	9.9		5.6	16	13000
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	4900	< 0.37 U	4.4	41	0.21 J	0.12 J	51000	9.1		4.8 J	17	12000
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	6600	< 0.36 U	6.6	81	0.29 J	0.15 J	61000	12		5.9	25	13000
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	4600	< 0.36 U	4.4	36	0.19 J	0.085 J	31000	7		4.4 J	15	12000
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated	5900	< 0.38 U	7.9	48	0.24 J	0.12 J	15000	8.8		6.4	16	14000
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	5700	< 0.38 U	5.3	36	0.24 J	0.086 J	29000	9.8		5.3 J	19	14000
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	6700	< 0.41 U	4	70	0.23 J	0.17 J	59000	11		6.3	23	17000
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	5400	< 0.36 UJ	4.5	45	0.21 J	0.098 J	49000	8.9 J		5 J	18	12000
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	5800	< 0.36 U	4.5	59	0.27 J	0.14 J	20000	9		5.4	18	15000
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	6600	< 0.39 U	6.1	56	0.27 J	0.08 J	19000	11		5.1 J	18	14000
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	7100	< 0.38 U	3.2 J	45	0.24 J	< 0.041 UJ	24000	9		5.6	30	16000
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	6000	< 0.38 U	6.7	34	0.32 J	0.087 J	1900	8.4		5.6	16	15000
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	6900	< 0.43 U	8.6	56	0.29 J	0.13 J	29000	10		6.5	21	16000
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	5400	< 0.34 U	5.1	46	0.19 J	0.081 J	12000	6.7		4.4 J	17	12000
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated	6200	< 0.38 U	7	44	0.25 J	0.12 J	44000	10		5.7 J	17	14000
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	5900	0.61 J	18	51	0.24 J	0.077 J	25000	12		6.8	19	27000
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	7300	< 0.38 U	5.5	49	0.32 J	0.073 J	1700	9.2		6.7	18	16000
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	7400	< 0.37 U	6.4	120	0.34 J	0.09 J	1800	13		6.3	26	16000
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	6700	< 0.4 U	6.8	61	0.29 J	0.2 J	5300	9.1		5.9	24	16000
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	5800	< 0.39 U	5.4	39	0.23 J	0.065 J	18000	8.3		5.2 J	29	15000
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	7200	< 0.36 U	5.1	370	0.27 J	0.085 J	42000	12		5.7	19	16000
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	5600	< 0.37 U	4.4	52	0.2 J	0.11 J	33000	9.8		5.1 J	19	13000
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	5600	< 0.36 U	4.9	45	0.21 J	0.049 J	31000	13		5.3	20	14000
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	5800	< 0.35 U	4.3	54	0.21 J	0.13 J	31000	8.1		5.2	17	14000
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	5900	< 0.36 U	5	95	0.27 J	0.06 J	34000	11		5.2 J	21	14000
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	6300	< 0.35 U	5.5	47	0.23 J	0.063 J	24000	8.7		5.6	34	15000
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	6400	< 0.37 U	4.3	53	0.23 J	0.09 J	43000	10		5.7	18	15000
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	6400	< 0.36 U	13	46	0.25 J	0.073 J	33000	10		5.8	22	15000
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	6500	< 0.4 U	5.4	56	0.28 J	0.093 J	17000	8.4		5.1 J	22	14000
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	6100	< 0.36 UJ	5.6	43	0.25 J	0.11 J	27000	12		5.3	17	14000
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	7300	< 0.37 U	5.9	46	0.29 J	0.096 J	14000 J	12		6.1	20	16000
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	5500	< 0.34 U	5.2	48	0.21 J	0.07 J	36000	13		5.2	22	13000
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated	5000	< 0.36 U	3.9	45	0.2 J	0.05 J	46000	7.9		4.3 J	14	11000
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated	7000	< 0.37 U	4.9	50	0.28 J	0.088 J	58000	8.9		6	19	15000
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated	6600	< 0.37 U	5.2	51	0.24 J	0.11 J	41000	10		5.5	18	15000
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	6600	0.6 J	6.7	59	0.31 J	0.31 J	48000	20		6.8	83	27000
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	6400	0.52 J	6.7	48	0.29 J	0.11 J	5600	9.6		6.2	21	17000
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	6000	< 0.41 U	5.9	47	0.28 J	0.11 J	41000	8.7		5.4 J	24	14000
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated	7200	< 0.36 U	6.1	66	0.28 J	0.085 J	37000	9.8		6.6	21	16000
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	7800	0.52 J	6.8	59	0.36 J	0.1 J	4600	10		6.6	20	17000
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	4300	< 0.36 U	3.7	26	0.15 J	0.078 J	36000	7.6		5.2 J	13	10000
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated	4800	< 0.39 U	3.5	53	0.18 J	0.07 J	42000	7.5		3.9 J	20	11000
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated	7300	< 0.4 U	5.7	56	0.33 J	0.089 J	13000	9.6		6.6	19	17000
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	6400	< 0.37 U	4.9	56	0.23 J	0.092 J	31000	8.3		5.8	20	15000
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated	5800	< 0.36 U	5	51	0.2 J	0.11 J	54000	7.9		5.1 J	19	14000
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated	4500	< 0.38 U	4.5	43	0.22 J	0.11 J	43000	9.7		5.3 J	16	13000
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	5600	< 0.36 U	4.5	48	0.21 J	0.087 J	34000	12		4.8 J	22	13000
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	3900	< 0.38 U	2.7	24	0.16 J	0.074 J	27000	6.4		3.5 J	11	9900
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	6100	< 0.4 U	5.5	49	0.28 J	0.22 J	21000	9		5.6 J	20	14000
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	4900	< 0.37 U	5.1	42	0.21 J	0.095 J	44000	7		4.6 J	16	12000
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	6600	< 0.39 U	4.8	55	0.24 J	0.093 J	36000	9.4		5.7 J	22	15000
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	5400	< 0.36 U	4.4	40	0.2 J	0.069 J	42000	8.8		5 J	13	12000
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	5400	< 0.36 U	4.1	41	0.21 J	0.077 J	30000	9.1		4.7 J	16	12000
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	5500	0.43 J	7.1	57	0.27 J	0.089 J	14000	7.1		5.6 J	20	14000
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	4900	< 0.37 U	5.3	54	0.18 J	0.12 J	37000	7.2		4.8 J	19	11000
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated	6800	< 0.39 U	5.5	42	0.29 J	0.15 J	32000	8.9		5.8	20	15000
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	5700	< 0.35 U	5	61	0.22 J	0.086 J	38000	9.4		5.1 J	14	13000
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	7100	< 0.36 U	4.5	46	0.27 J	0.076 J	26000	13		6	23	17000
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated	6600	< 0.38 U	4.9	57	0.28 J	0.15 J	50000	10		5.9	22	16000
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	6500	< 0.35 U	5	110	0.23 J	0.12 J	60000	8		5.8	23	15000
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	4500	< 0.37 U	3.7	39	0.19 J	0.13 J	55000	9.3		4.2 J	17	11000
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated	5600	< 0.36 U	3.6	63	0.19 J	0.14 J	77000	7.9		5.4	21	13000
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated	6600	< 0.34 U	5.9	47	0.26 J	0.083 J	21000	8.7		5.7	19	15000
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated	5600	< 0.34 U	3.7	51	0.21 J	0.19 J	56000	7.6		5.3	20	13000
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	4700	< 0.34 U	3.8	31	0.18 J	0.14 J	58000	7.1		4 J	19	11000
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	6000	< 0.35 U	8.1	39	0.24 J	0.13 J	25000	11		5.4	16	15000
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	5900	< 0.33 U	4.6	45	0.24 J	0.12 J	22000	9.6		5.4	22	14000
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	5000	< 0.29 U	4.6	40	0.21 J	0.11 J	37000	14		4.7	17	12000
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	5400	< 0.31 U	3.4	41	0.22 J	0.11 J	29000	10		4.7	14	12000
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	5100	< 0.23 U	3.4	45	0.17 J	0.093 J	29000	8.4		4.9	14	12000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	13	2700	740	0.017 J	17	900	< 0.63 U	< 0.13 U	< 32 U		< 0.39 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	8.3	8400	580	< 0.013 U	14	690	< 0.55 U	< 0.11 U	74 J		< 0.34 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	6.9	11000	690	< 0.015 U	17	680	0.86 J	< 0.12 U	87 J		< 0.36 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	7.7	8100	480	< 0.015 U	19	860	0.75 J	< 0.11 U	91 J		< 0.32 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	13	9300	480	< 0.013 U	14	740	0.61 J	< 0.11 U	98 J		< 0.35 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	6.6	7800	390	< 0.014 U	12	600	0.68 J	< 0.12 U	81 J		< 0.35 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	37	14000	480	0.13	17	830	1.2	< 0.11 U	140 J		< 0.34 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	6.8	7800	350	< 0.014 U	11	580	< 0.55 U	< 0.11 U	67 J		< 0.34 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated	12	4200	530	< 0.015 U	14	700	< 0.58 U	< 0.12 U	59 J		< 0.36 U
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	7.7	10000	380	< 0.015 U	13	820	0.66 J	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	6.4	8200	770	< 0.016 U	16	710	< 0.62 U	< 0.13 U	88 J		< 0.38 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	17	8100 J-	620	< 0.014 U	12	630	< 0.55 U	< 0.11 U	91 J		< 0.34 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	6.9	5000	260	< 0.014 U	14	780	< 0.55 U	< 0.11 U	60 J		< 0.34 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	9.5	2600	380	< 0.016 U	13	900	< 0.59 U	< 0.12 U	110 J		< 0.37 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	10	5100 J	370	< 0.013 U	14	620	< 0.58 U	< 0.12 U	78 J		< 0.36 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	7.9	2200	320	< 0.016 U	14	860	< 0.57 U	< 0.12 U	55 J		< 0.35 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	9.3	10000	520	< 0.016 U	17	840	< 0.65 U	< 0.13 U	93 J		< 0.4 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	7.5	6100	490	< 0.014 U	11	530	< 0.52 U	< 0.11 U	46 J		< 0.32 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated	9.2	5100 J	350	< 0.017 U	14	770	0.6 J	< 0.12 U	74 J		< 0.36 U
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	8.9	8800	560	< 0.015 U	15	680	< 0.54 U	< 0.11 U	100 J		< 0.34 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	13	2400	420	0.1	14	700	< 0.58 U	< 0.12 U	43 J		< 0.36 U
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	14	2200	600	< 0.015 U	16	740	< 0.57 U	< 0.12 U	77 J		< 0.35 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	11	4400	1000	0.084	16	810	< 0.6 U	< 0.12 U	50 J		< 0.38 U
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	9	5100	360	< 0.016 U	12	710	< 0.6 U	< 0.12 U	72 J		< 0.37 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	12	14000	430	< 0.014 U	15	850	< 0.55 UJ	< 0.11 U	99 J		< 0.34 U
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	7	7600	600	< 0.015 U	13	630	< 0.56 U	< 0.12 U	77 J		< 0.35 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	6.2	7300	420	< 0.015 U	14	570	0.7 J	< 0.11 U	71 J		< 0.34 U
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	6.1	9700	560	< 0.015 U	13	550	< 0.53 U	< 0.11 U	69 J		< 0.33 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	8	9800	370	< 0.014 U	13	700	0.7 J	< 0.11 U	78 J		< 0.34 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	6.4	7600	420	< 0.014 U	13	640	0.63 J	< 0.11 U	79 J		< 0.33 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	12	14000	480	< 0.014 U	14	710	0.62 J	< 0.12 U	81 J		< 0.35 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	6.9	4600	460	< 0.014 U	15	660	0.66 J	< 0.11 U	74 J		< 0.34 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	6.8	7800	500	0.018 J	13	850	< 0.6 U	< 0.12 U	63 J		< 0.37 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	7.8	5300 J+	550	< 0.015 U	13	640	< 0.54 U	< 0.11 U	61 J		< 0.34 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	9.8	4100 J	480	< 0.015 U	15	760	< 0.56 UJ	< 0.11 U	71 J		< 0.35 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	6.3	12000	380	< 0.014 U	13	620	< 0.52 U	< 0.11 U	72 J		< 0.32 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated	5.4	9600	320	< 0.016 U	10	920	0.58 J	< 0.11 U	88 J		< 0.34 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated	15	11000	440	< 0.016 U	16	900	1.2	< 0.12 U	87 J		< 0.35 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated	7.3	8600	460	< 0.014 U	14	740	0.85 J	< 0.11 U	93 J		< 0.35 U
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	41	15000	500	0.035	29	750	0.91 J	< 0.12 U	96 J		< 0.36 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	9.2	2800	490	0.037	15	910	< 0.59 U	< 0.12 U	65 J		< 0.37 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	13	11000	420	< 0.017 U	13	840	< 0.62 U	< 0.13 U	83 J		< 0.39 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated	8	11000	500	< 0.015 U	17	790	0.77 J	< 0.11 U	70 J		< 0.34 U
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	9.6	4400	590	< 0.017 U	17	830	< 0.6 U	< 0.12 U	66 J		< 0.38 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	8.8	14000	300	< 0.015 U	10	520 J	0.66 J	< 0.11 U	76 J		< 0.34 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated	4.1	5900	450	< 0.017 U	10	590	0.83 J	< 0.12 U	81 J		< 0.37 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated	8.3	6000	460	< 0.017 U	16	920	< 0.6 U	< 0.12 U	60 J		< 0.37 U
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	10	9200	470	< 0.015 U	14	550	0.84 J	< 0.11 U	56 J		< 0.35 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated	5.1	16000	450	< 0.013 U	13	620	0.76 J	< 0.11 U	79 J		< 0.34 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated	5.4	7300	320	< 0.015 U	25	510 J	0.68 J	< 0.12 U	67 J		< 0.36 U
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	11	8200	410	< 0.013 U	12	840	< 0.55 U	< 0.11 U	84 J		< 0.34 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	3.5	3900	240	< 0.015 U	8.9	480 J	< 0.58 U	< 0.12 U	54 J		< 0.36 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	14	6200	1000	< 0.015 U	13	810	< 0.6 U	< 0.12 U	63 J		< 0.37 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	7.3	22000	330	< 0.013 U	11	680	0.65 J	< 0.12 U	83 J		< 0.35 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	8.8	9700	380	< 0.015 U	14	800	0.65 J	< 0.12 U	110 J		< 0.37 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	6.5	13000	390	< 0.015 U	12	760	< 0.55 U	< 0.11 U	81 J		< 0.34 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	6.7	7700	340	< 0.014 U	11	730	< 0.55 U	< 0.11 U	42 J		< 0.34 U
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	12	8500	770	< 0.016 U	13	640	< 0.6 U	< 0.12 U	< 30 U		< 0.38 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	11	16000	480	< 0.014 U	11	620	0.75 J	< 0.11 U	160 J		< 0.35 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated	9.9	5200	630	< 0.015 U	14	760	< 0.59 U	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	7.6	9500	450	< 0.015 U	12	760	0.6 J	< 0.11 U	110 J		< 0.33 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	7	6000	470	< 0.013 U	15	690	0.62 J	< 0.11 U	74 J		< 0.34 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated	6.5	14000	470	< 0.015 U	14	740	1.2	< 0.12 U	160 J		< 0.35 U
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	5.4	8000	370	< 0.014 U	14	670	0.92 J	< 0.11 U	86 J		< 0.33 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	5.6	13000	320	< 0.014 U	11	650	0.84 J	< 0.11 U	79 J		< 0.35 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated	5.3	11000	350	< 0.015 U	13	650	1.1	< 0.11 U	86 J		< 0.34 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated	7.3	5800	420	< 0.014 U	14	740	0.76 J	< 0.11 U	70 J		< 0.33 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated	5.8	7900	420	< 0.013 U	12	680	0.71 J	< 0.1 U	100 J		< 0.32 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	5.4	6600	410	< 0.026 U	12	530	1.1	< 0.11 U	75 J		< 0.32 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	6.9	5600	320	< 0.021 U	14	570	< 0.53 U	< 0.11 U	62 J		< 0.33 U
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	7.2	5700	370	< 0.023 U	15	640	< 0.49 U	< 0.1 U	60 J		< 0.31 U
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	8.6	12000	400	< 0.023 U	13	570	0.66 J	< 0.09 U	68 J		< 0.27 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	5.4	6100	350	< 0.024 U	13	590	< 0.47 U	< 0.096 U	68 J		< 0.29 U
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	6	9600	350	0.025 J	12	490	0.37 J	< 0.071 U	59 J		< 0.22 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated		14	74
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated		9	53
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated		9.8	50
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated		15	60
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated		10	57
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated		7.7	44
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated		10	79
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated		7.5	42
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated		9	71
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated		9.4	47
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated		11	61
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated		8.6	53
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated		10	55
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated		11	48
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated		10	60
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated		11	49
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated		12	62
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated		8.4	45
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated		10	59
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated		16	50
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated		11	49
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated		12	56
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated		12	70
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated		9.1	52
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated		11	60
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated		8.6	53
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated		8.7	48
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated		8.4	59
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated		9.6	51
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated		9.5	50
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated		11	55
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated		9.7	55
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated		11	47
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated		9.8	46
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated		12	55
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated		9.5	48
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated		8.7	34
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated		9.7	60
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated		11	49
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated		11	96
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated		13	62
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated		9.8	50
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated		12	67
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated		13	66
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated		7.1	32
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated		7.6	35
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated		12	61
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated		9	55
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated		9.4	67
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated		8.2	47
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated		10	49
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated		6.8	37
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated		10	45
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated		8	48
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated		11	56
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated		9	43
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated		9.1	42
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated		10	48
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated		8.6	63
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated		11	60
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated		8.3	42
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated		11	47
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated		11	92
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated		9.3	56
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated		7.7	38
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated		11	52
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated		10	53
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated		9.7	60
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated		7.6	66
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated		10	47
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated		11	51
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated		8.3	41
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated		8.9	43
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated		8.5	49

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	4300	< 0.29 U	4.1	26	0.19 J	0.11 J	17000	6.6		4 J	14	10000
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	5100	< 0.35 U	4.2	54	0.23 J	0.18 J	40000	8		5.3	22	13000
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	4500	< 0.35 U	3.7	30	0.18 J	0.12 J	29000	7.8		4 J	22	11000
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	5800	< 0.35 U	5.2	32	0.22 J	0.14 J	31000	9.1		5.6	18	14000
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	3000	< 0.29 U	2.7	21	0.11 J	0.059 J	29000	6.4		2.8 J	9.6	8000
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	5200	< 0.32 U	4.5	37	0.19 J	0.12 J	42000	10		4.7 J	19	13000
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	3900	< 0.34 U	3.1	41	0.15 J	0.13 J	48000	8.4		3.8 J	18	10000
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	3900	< 0.35 U	4	42	0.16 J	0.094 J	38000	5.9		4 J	13	10000
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	4800	< 0.36 U	3.8	34	0.2 J	0.13 J	43000	7.6		4.6 J	18	12000
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	4400	< 0.33 U	3.3	66	0.16 J	0.093 J	44000	7.4		4.4 J	15	12000
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	1900	< 0.32 U	2.1	25	0.071 J	0.13 J	84000	7.5		2 J	8.3	5700
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	5000	< 0.32 U	3.8	28	0.16 J	0.097 J	24000	7.7		4.5 J	42	13000
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	5300	< 0.34 U	6	33	0.25 J	0.12 J	24000	7.2		5.3	17	14000
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	5100	< 0.34 U	4.3	62	0.18 J	0.12 J	75000	7.8		4.8 J	16	12000
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated	6600	< 0.34 U	4.5	53	0.23 J	0.16 J	90000	8		5.9	18	14000
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	4000	0.36 J	3.2	25	0.16 J	0.059 J	17000	6.2		3.8 J	12	9400
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	7200	< 0.35 U	7.8	65	0.36 J	0.67	22000	11		6.3	28	17000
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	5100	0.49 J	4.9	45	0.20 J	0.18 J	45000	7.1		5.0	19	12000
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	5800	0.35 J	5.5	36	0.23 J	0.17 J	21000	9.3		5.2	21	13000
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	5400	< 0.28 U	4.6	61	0.17 J	0.049 J	47000	11		5.4	17	13000
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	5800	< 0.3 U	4.2	36	0.21 J	0.12 J	38000	9		5.3	17	14000
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	6600	< 0.33 U	4.3	42	0.24 J	0.058 J	39000	12		5.6	21	15000
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	2800	< 0.25 U	3.1	16	0.11 J	< 0.060 U	17000	3.7		2.6 J	10	7500
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	2600	< 0.21 U	2.5	16	0.095 J	< 0.051 U	34000	3.2		2.7 J	9.9	6800
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	4500	< 0.23 UT	4.8	39 T	0.19 JT	0.066 J	24000	6.0 T		4.7	15	11000
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	4000	< 0.27 U	3.2	32	0.17 J	0.071 J	50000	5.0		4.0 J	17	10000
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	5100	< 0.27 UT	3.8	30	0.20 J	< 0.065 U	28000 T	6.4		4.6	15	12000
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	4200	0.65 JT	13	62 T	0.71	0.15 J	6100 T	9.3		6.3	87	9800
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	5300	0.24 J	7.2	58	0.33	0.12 J	12000	9.2		4.8	72	14000
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	3300	< 0.19 U	4.5	26	0.15 J	0.089 J	27000	4.6		3.4	12	9300
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	5300	< 0.24 U	4.5	43	0.20 J	0.091 J	40000	6.6		5.3	19	13000
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	3800	< 0.22 U	2.8	28	0.14 J	0.060 J	25000	4.8		3.8	16	9300
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	5300	< 0.24 U	3.2	44	0.19 J	0.081 J	28000	6.2		4.6	18	11000
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	5600	< 0.23 UT	4.7	46 T	0.24 J	0.10 J	24000	6.9 T		5.1	18	13000
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	3500	< 0.24 U	5.4	32	0.15 J	0.089 J	44000	4.9		4.4	14	9700
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	5500	< 0.23 U	3.8	46	0.21 J	0.065 J	25000	12		5.3	16	12000
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	4900	< 0.18 U	3.9	37	0.20 J	0.083 J	28000	6.0		4.7	16	11000
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	3900	< 0.21 U	4.7	54	0.18 J	0.11 J	29000	4.9		3.7	15	9200
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	6000	< 0.27 U	5.0	47	0.25 J	0.094 J	27000	7.5		4.8	22	13000
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	5000	< 0.28 U	5.1	37	0.24 J	< 0.067 U	6400	6.4		5.0	21	13000
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	3900	< 0.23 U	4.7	26	0.17 J	0.068 J	26000	4.9		3.9	14	9600
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	4400	< 0.23 U	3.5	28	0.16 J	0.070 J	31000	5.1		4.1	13	11000
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	4700	< 0.24 U	3.5	38	0.19 J	< 0.059 U	2100	5.8		4.1	14	12000
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	4400	< 0.26 U	3.7	31	0.17 J	0.063 J	23000	5.6		4.0 J	14	10000
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	5000	< 0.28 U	3.5	31	0.19 J	0.083 J	36000	6.4		4.6 J	14	12000
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	4800	< 0.31 U	3.8	32	0.20 J	0.10 J	34000	6.0		4.6 J	16	12000
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	4100	< 0.26 UT	3.0	35	0.16 J	0.081 J	49000	5.0		3.6 J	13	9000
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	3400	< 0.26 U	2.5	25	0.16 J	< 0.064 U	20000	4.5		3.3 J	16	8100
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	3700	< 0.29 UT	3.7	23	0.14 J	0.078 J	32000 T	5.3		3.5 J	12	9700
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	4100	< 0.27 UT	3.7	27 T	0.18 JT	< 0.065 U	29000 T	5.3 T		3.9 J	17 T	10000
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	4000	< 0.30 U	3.1	23	0.15 J	< 0.072 U	34000	4.8		3.5 J	12	9000
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	4100	< 0.27 U	3.4	29	0.15 J	0.10 J	67000	4.8		3.6 J	12	9900
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	4100	< 0.24 U	4.6	31	0.18 J	0.060 J	32000	5.2		4.1	15	11000
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	4400	< 0.24 U	3.9	36	0.17 J	0.065 J	35000	5.7		4.3	15	11000
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	4900	< 0.25 U	3.3	34	0.21 J	0.070 J	31000	5.9		4.4	15	12000
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	4000	< 0.27 U	4.2	31	0.18 J	0.12 J	18000	4.9		4.0 J	20	10000
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	4300	< 0.22 UT	3.5	37 T	0.18 J	0.061 J	20000 T	5.0 T		3.9	14	9900
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	4500	< 0.28 U	3.7	38	0.19 J	< 0.067 U	28000	5.6		4.1 J	15	10000
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	3100	< 0.27 U	2.6	22	0.12 J	0.087 J	69000	3.7		3.0 J	11	8000
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	5300	0.60 JT	6.6 T	65 T	0.24 J	0.26 JT	1500 T	7.4 T		4.9 J	26 T	13000
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	5000	< 0.31 U	5.9	59	0.2 J	0.17 J	6500	8.1		5.6	17	13000
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	3800	< 0.29 U	6.5	38	0.13 J	0.13 J	32000	6.9		3.7 J	15	10000
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	4800	< 0.32 U	4.3	39	0.15 J	< 0.078 U	15000	9.2		4.8 J	17	12000
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	3200	< 0.27 U	3.0 B	30	0.11 J	0.090 J	45000	4.2		3.0 J	13	9200
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	3700	< 0.31 U	3.4	33	0.16 J	0.082 J	17000	4.6		3.5 J	16	9000 B
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	4400	< 0.29 U	3.9	28	0.18 J	0.077 J	14000	5.7		4.3 J	13	12000 B
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	5200	< 0.32 U	4.6	41	0.23 J	0.12 J	23000	6.8		4.7 J	16	12000
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	6700	< 0.31 U	7.1	52	0.33 J	0.080 J	1700	8.1		4.6 J	19	15000
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	4100	< 0.37 U	3.3	37	0.18 J	0.12 J	27000	5.2		3.6 J	15	11000
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	5400	0.39 J	5.7	42	0.23 J	< 0.078 U	23000	6.8		4.8 J	17	12000
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	5100	< 0.32 U	5.5	46	0.23 J	0.10 J	28000	6.3		4.4 J	19	13000
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	5700	< 0.33 U	5.4	41	0.26 J	0.10 J	12000	6.9		4.5 J	18	13000
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	6200	< 0.33 U	4.9	57	0.26 J	0.19 J	17000	7.8		5.3 J	18	13000
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	5600	< 0.33 U	5.1	33	0.24 J	0.094 J	27000	7.0		4.8 J	15	13000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	10	4200	310	0.028 J	10	470	< 0.44 U	< 0.089 U	< 51 U		< 0.27 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	8.3	7200	510	< 0.022 U	13	600	< 0.52 U	< 0.11 U	72 J		< 0.33 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	13	11000	340	< 0.024 U	10	570	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	9.6	9000	470	< 0.022 U	13	630	< 0.54 U	< 0.11 U	74 J		< 0.33 U
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	5.3	4300	270	< 0.022 U	7.4	340 J	< 0.44 U	< 0.09 U	< 52 U		< 0.27 U
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	8	12000	430	< 0.021 U	12	640	< 0.49 U	< 0.1 U	74 J		< 0.31 U
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	6.2	12000	390	< 0.022 U	9.3	510	0.68 J	< 0.1 U	78 J		< 0.32 U
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	6.5	5900	290	< 0.022 U	9.7	460 J	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	6.4	6600	360	< 0.023 U	11	600	< 0.54 U	< 0.11 U	70 J		< 0.34 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	5.5	4500	310	< 0.023 U	10	470 J	0.69 J	< 0.1 U	64 J		< 0.31 U
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	3.9	11000	210	< 0.024 U	5.9	350 J	1	< 0.098 U	67 J		< 0.3 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	5	6500	330	< 0.023 U	10	430 J	< 0.48 U	< 0.099 U	< 57 U		< 0.3 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	7.1	3900	230	< 0.021 U	14	670	< 0.51 U	< 0.11 U	< 60 U		< 0.32 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	5.1	10000	310	< 0.019 U	12	680	0.64 J	< 0.10 U	99 J		< 0.32 U
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated	5.8	8700	400	< 0.022 U	14	880	0.71 J	< 0.11 U	340 J		< 0.32 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	6.8	4000	310	< 0.021 U	9.2	490 J	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	28	5600	340	0.13	21	850	< 0.53 U	< 0.11 U	76 J		< 0.33 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	8.4	12000	410	< 0.022 U	12	610	< 0.47 U	< 0.097 U	81 J		0.45 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	7.2	6000	320	0.027 J	13	690	< 0.40 U	< 0.082 U	57 J		0.62 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	9.9	20000	520	< 0.02 U	13	780	0.74 J	< 0.087 U	95 J		< 0.26 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	6.5	8600	330	< 0.019 U	13	650	0.62 J	< 0.091 U	74 J		< 0.28 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	8	6700	510	< 0.016 U	14	770	0.7 J	< 0.1 U	90 J		< 0.31 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	4.4	1400	190	< 0.017 U	54	240 J	< 0.37 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	3.0	17000	180	0.017 J	12	230 J	0.49 J	< 0.073 U	52 J		< 0.20 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	12 T	4000 T	280	0.018 JT	12 T	450 T	< 0.35 U	< 0.079 U	40 J		< 0.22 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	4.5	3000	260	< 0.021 U	10	380 J	0.60 J	< 0.092 U	49 J		< 0.25 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	6.7	5600	350	< 0.017 U	11	530	1.0	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	46 T	1100	100 T	0.18	35 T	540	1.4 T	< 0.090 U	71 J		< 0.25 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	31	2600	280	0.071	22	500	0.55 J	< 0.079 U	59 J		< 0.22 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	4.4	3100	250	< 0.016 U	8.7	330	0.43 J	< 0.064 U	43 J		< 0.18 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	9.9	13000	480	< 0.016 U	13	500	0.53 J	< 0.083 U	64 J		< 0.23 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	4.2	5500	230	< 0.018 U	9.5	330 J	< 0.34 U	< 0.076 U	40 J		< 0.21 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	5.7	8300	350	< 0.019 U	12	520	< 0.37 U	< 0.083 U	46 J		< 0.23 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	8.0	7400 T	430	< 0.020 U	13	620 T	0.79	< 0.079 U	51 J		< 0.22 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	6.2	9300	300	< 0.023 U	12	470	0.73 J	< 0.082 U	54 J		< 0.22 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	4.7	4800	270	0.019 J	14	600	0.44 J	< 0.078 U	160 J		< 0.21 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	5.5	5700	340	< 0.015 U	11	490	0.65	< 0.063 U	46 J		< 0.17 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	5.1	3400	580	< 0.018 U	11	420	< 0.32 U	< 0.072 U	76 BJ		< 0.20 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	6.6	8500	340	< 0.019 U	13	630	0.47 J	< 0.092 U	95 BJ		< 0.25 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	11	4600	280	< 0.023 U	13	500	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	5.5	4100	200	< 0.019 U	9.2	440	0.36 J	< 0.081 U	40 J		< 0.22 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	4.4	2800	190	< 0.016 U	10	390	0.59 J	< 0.078 U	42 J		< 0.21 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	4.7	2100	250	< 0.018 U	11	330 J	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	6.9	5400	280	< 0.019 U	10	480	0.76 J	< 0.088 U	48 J		< 0.24 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	5.0	4400	340	< 0.017 U	12	500	0.71 J	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	6.6	6500	270	0.024	12	500 J	0.91 J	< 0.11 U	57 J		< 0.29 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	4.6	4800 T	310	< 0.017 U	9.8	450 T	0.91	< 0.090 U	50 J		< 0.25 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	4.7	3000	230	< 0.019 U	8.2	410 J	0.45 J	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	5.3	2800 T	270	< 0.014 U	9.5	310 J	0.50 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	4.9	3200 T	270	< 0.017 U	9.5	490 T	0.49 JT	< 0.092 UT	< 45 U		< 0.25 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	4.9	5500	190	< 0.017 U	9.1	440 J	0.83 J	< 0.10 U	57 J		< 0.28 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	5.5	5900	260	< 0.019 U	9.4	480	0.82 J	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	6.4	5200	220	< 0.017 U	9.6	450	0.62 J	< 0.082 U	42 J		< 0.22 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	7.0	7400	280	< 0.017 U	11	410	0.63 J	< 0.084 U	46 J		< 0.23 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	4.8	3400	240	< 0.016 U	11	470	0.67 J	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	5.7	1900	510	< 0.021 U	11	400 J	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	5.5	4300	210	< 0.018 U	9.9	420 T	< 0.34 U	< 0.077 U	38 J		< 0.21 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	5.1	4100	300	< 0.020 U	11	490	< 0.42 U	< 0.094 U	61 J		< 0.26 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	4.8	4400	220	< 0.020 U	8.0	340 J	0.45 J	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	34 T	1500	370	0.023 J	16	570 T	< 0.46 UT	< 0.10 UT	< 51 U		< 0.29 UT
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-12-14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	7.2	3400	760	0.087	14	560	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	7.4	9400	420	0.041	9.3	480	< 0.44 U	< 0.1 U	57 J		< 0.27 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-12-14	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	6.5	5200	370	0.025 J	12	500 J	< 0.49 U	< 0.11 U	< 54 U		< 0.3 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	5.2	19000	260	< 0.016 U	8.2	410 J	0.69 J	< 0.094 U	70 J		< 0.26 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	4.8	5200	260 B	< 0.019 U	8.3	510 J	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	4.7	4500	280 B	< 0.21 U	10	480 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	10	4700	310	0.53	11	830	< 0.49 U	< 0.11 U	69 J		< 0.30 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	16	1800	350	0.018 J	12	990	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	5.6	3600	710	< 0.022 U	9.0	790	< 0.57 U	< 0.13 U	< 63 U		< 0.35 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	9.1	5200	280	0.22	11	930	< 0.49 U	< 0.11 U	72 J		< 0.30 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	7.8	15000	590	0.077	11	820	< 0.48 U	< 0.11 U	92 J		< 0.30 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	12	5000	430	0.12	12	900	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	9.2	9600	880	0.053	14	830	< 0.50 U	< 0.11 U	76 J		< 0.30 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	12	6200	330	< 0.017 U	11	890	< 0.51 U	< 0.11 U	61 J		< 0.31 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated		8.1	43
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated		8.4	100
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated		7.5	41
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated		10	48
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated		6.6	25
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated		8.6	43
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated		7.2	44
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated		6.6	36
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated		8.3	46
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated		7.8	40
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated		3.6 J	17
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated		8	47
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated		8.8	43
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated		10	41
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated		9.8	45
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated		6.8	31
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated		13	60
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated		8.5	50
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated		11	47
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated		13	39
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated		9.4	90
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated		11	53
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated		4.0 J	26
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated		4.2	24
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated		7.2 T	48 T
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated		6.4	34
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated		8.1	45 T
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated		16 T	120
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated		9.7	73
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated		7.4	36
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated		9.9	45
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated		5.6	33
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated		7.2	48
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated		8.6 T	63 T
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated		4.8	32
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated		9.5	40
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated		7.1	44
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated		6.3	39
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated		11	47
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated		8.3	50
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated		6.4	43
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated		6.7	190
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated		7.0	58
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated		7.2	41
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated		8.4	47
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated		7.9	58
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated		6.4	33
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated		6.6	65
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated		6.3	37
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated		6.8 T	36 T
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated		7.4	39
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated		6.5	40
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated		8.1	36
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated		7.5	39
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated		7.4	40
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated		5.7	35
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated		5.9	39 T
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated		6.7	41
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated		4.5	28
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated		8.1 T	60 T
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated		8.4	51
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated		5.9	37
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated		6.6	56
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated		5.6	37
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated		6.1	31
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated		8.7	34
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated		9.7	60
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated		14	94
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated		7.4	32
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated		10	49
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated		9.9	39
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated		11	53
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated		11	61
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated		10	41

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	5500	< 0.31 U	4.9	29	0.23 J	0.098 J	26000	6.8		4.8 J	20	13000
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	6600	< 0.24 U	4.9	33	0.25 J	0.11 J	14000	7.5		5.4	19	15000
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	4200	< 0.29 U	3.9	28	0.17 J	0.096 J	44000	5.2		3.6 J	14	11000
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	4900	< 0.25 U	2.2	23	0.18 J	< 0.061 U	7400	5.9		4.4	12	13000
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	6300	< 0.27 U	7.1	48	0.28 J	0.11 J	23000	9.2		5.5	18	13000
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	7000	< 0.30 U	6.4	54	0.30 J	0.10 J	4200	7.8		4.7 J	18	14000
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	3600	< 0.30 U	3.9	35 T	0.13 J	0.11 J	64000	4.4		3.8 J	13	7900
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	9600	< 0.38 U	8.1	53	0.45 J	0.12 J	1900	12		7.6	24	22000
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	6100	< 0.31 U	5.5	35	0.30 J	0.11 J	18000	7.6		4.8 J	17	13000
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	6600	< 0.33 U	6.0	49	0.31 J	0.085 J	1900	7.7		4.3 J	19	14000
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	4200 B	< 0.31 U	5.3	46	0.21 J	0.095 J	820	6.3		3.1 J	18	10000
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	6600	< 0.33 U	4.9	53	0.29 J	0.16 J	740	7.5		5.4	26	14000
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	7800 B	< 0.31 UT	5.7	95 T	0.38 J	0.22 J	2100 T	9.0		5.6	25	14000 T
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	9500 B	0.51 J	11	110	0.52	0.11 J	1700	10		6.0	42	15000
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	6300 B	< 0.31 UT	5.3 T	55 T	0.31 JT	0.095 JT	790	7.8 T		4.7 JT	23 T	15000
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	8700 B	0.50 J	11	100	0.45	0.11 J	2000	9.6		4.7 J	23	14000
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	8700	< 0.30 U	7.8	67	0.41	0.099 J	1100	11		6.5	19	17000
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	4400	< 0.25 U	2.4	35	0.17 J	0.16 J	20000	6.3		3.9 J	20	9100
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	4500	< 0.28 U	2.9	18 J	0.81	0.11 J	31000	6.1		4.1 J	14	10000
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	4800	< 0.25 U	3.4	30	0.17 J	< 0.060 U	28000	6.0		4.6	12	12000
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	5600	< 0.30 U	5.4	33	0.27 J	< 0.073 U	730	7.4		4.9	16	13000
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	7200	< 0.27 U	6.0	41	0.30 J	< 0.065 U	760	9.0		6.2	20	17000
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	7200	< 0.30 U	8.7	86	0.37 J	< 0.073 U	2300	9.2		8.1	17	19000
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	4800	< 0.25 U	4.0	31	0.19 J	< 0.061 U	410 J	5.7		3.6 J	11	10000
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	6700	< 0.31 U	5.2	44	0.29 J	0.13 J	2300	9.1		4.8 J	18	13000
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	8800	< 0.31 U	6.3	77	0.34 J	0.091 J	2000	10		6.1	23	18000
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	3000	< 0.29 U	3.5	20	0.15 J	< 0.069 U	20000	4.2		2.9 J	11	7800
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	3800	< 0.28 U	4.0	23	0.17 J	< 0.069 U	23000	5.1		3.6 J	13	9700
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	4900	< 0.27 U	5.0	33	0.21 J	< 0.067 U	20000	6.3		4.2 J	14	11000
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	4900	< 0.31 U	4.5	32	0.20 J	0.076 J	33000	6.4		4.3 J	19	12000 B
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	4000	< 0.25 U	1.6	23	0.16 J	0.094 J	30000	5.4		3.2 J	13	8100 B
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	4100	< 0.28 U	3.1	31	0.16 J	< 0.068 U	22000	5.4		3.6 J	11	9200 B
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	3700	< 0.28 U	2.9	23	0.14 J	0.069 J	37000	5.0		3.3 J	10	9000 B
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	4500	< 0.31 U	3.9	39	0.16 J	< 0.074 U	24000	6.0		4.0 J	14	11000 B
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	4400	< 0.27 U	4.3	28	0.19 J	< 0.065 U	5800	5.7		4.0 J	17	11000 B
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	4300	< 0.29 U	3.5	23	0.14 J	< 0.069 U	21000	5.9		3.7 J	12	9700 B
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	3200	< 0.29 U	3.5	25	0.13 J	< 0.071 U	40000	4.4		3.1 J	12	8100
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	5300	< 0.30 U	6.4	36	0.21 J	< 0.074 U	21000	7.1		4.5 J	15	12000
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	5500	< 0.26 U	4.8	42	0.21 J	0.085 J	21000	6.6		5.7	18	14000
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	4700	< 0.23 U	11	47	0.21 J	0.076 J	21000	5.9		6.0	17	13000
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	5900	< 0.17 U	5.1	44	0.24	0.39	43000	7.6		6.5	16	13000 B
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	11000	< 0.27 U	10	85	0.45	0.64	6900	13		11	28	25000
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	6700	< 0.36 UJ	4.7	43	0.27 J	0.12 J	17000	9.9		6.1	22	16000
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	7900	< 0.37 U	4.5	56	0.28 J	0.11 J	25000	12		6.6	24	18000
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	6000	< 0.37 U	5.8	42	0.26 J	0.11 J	25000	16		5.6	20	14000
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	5700	< 0.36 U	5.3	51	0.22 J	0.08 J	38000	11		5 J	18	14000
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	6000	< 0.36 U	3.7	51	0.2 J	0.064 J	44000	7.9		5.4	14	14000
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	4600	< 0.38 U	4.6	47	0.18 J	0.084 J	89000	11		4.1 J	14	11000
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	6000	< 0.37 U	6	47	0.24 J	0.13 J	30000	9.4		5.4	23	14000
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	7000	0.43 J	5.5	60	0.28 J	0.063 J	25000	11		6.5	21	16000
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	5500	< 0.34 U	4.1	54	0.19 J	0.087 J	57000	8.2		5.2	22	13000
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated	5300	< 0.36 U	4.3	48	0.22 J	0.077 J	30000	7		4.5 J	15	12000
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated	4900	< 0.35 U	4.1	46	0.19 J	0.053 J	36000	6.6		4.6 J	13	11000
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated	4200	< 0.37 U	4.3	53	0.16 J	0.079 J	32000	5.5		4.2 J	15	10000
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	6200	< 0.36 U	5.5	46	0.26 J	0.062 J	15000	8.2		5.9	23	15000
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	6100	< 0.34 U	4.1	69	0.24 J	0.098 J	36000	9.8		5.3	21	15000
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	6300	< 0.36 U	4.1	57	0.24 J	0.12 J	49000	9.4		5.3	23	15000
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	7700	< 0.37 U	10	47	0.3 J	0.098 J	26000	14		7.2	32	17000
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	5000	< 0.37 U	5.2	50	0.2 J	0.14 J	44000	6.4		4.6 J	17	12000
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	5000	< 0.33 U	6.6	32	0.2 J	0.13 J	20000	8.4		5	18	13000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	4600	< 0.27 U	4.9	31	0.23 J	0.089 J	22000	6.1		4.6	13	12000
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	5000	< 0.35 U	3.4	42	0.18 J	0.095 J	41000	13		4.0 J	27	13000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	6400	< 0.41 U	5.1	47	0.25 J	0.081 J	15000	8.5		5.8 J	21	14000
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	6500	< 0.33 U	5.6	150	0.28 J	0.13 J	55000	10		6.7	24	17000
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	6400	< 0.33 U	4.3	36	0.21 J	0.09 J	44000	7.8		5.4	17	15000
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	4100	0.46 J	2.9	33	0.15 J	0.078 J	18000	6.5		3.9 J	16	10000
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	4500	< 0.38 U	3.3	41	0.17 J	0.082 J	32000	7.4		3.8 J	14	11000
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	5000	< 0.38 U	3.5	41	0.18 J	0.079 J	38000	7.0		4.1 J	14	12000
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	6300	< 0.37 U	4.1	40	0.23 J	0.091 J	13000	8.1		4.7 J	18	15000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	6100	< 0.38 UT	6.7	51	0.30 J	0.17 J	1700	9.5		5.8	23 T	15000
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	6200	< 0.30 U	3.9	48	0.21 J	0.16 J	43000	7.9		5.3	19	14000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	6900	0.63 J	4.6	47	0.23 J	0.26 J	71000	10		6.0	19	15000
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	5000	0.47 J	4.1	49	0.18 J	0.20 J	35000	7.9		4.7	15	12000
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	4700	0.24 JT	4.5	38 T	0.20 JT	0.14 JT	19000	6.7 T		4.3	14	11000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	9.1	4300	290	< 0.018 U	11	790	< 0.46 U	< 0.10 U	57 J		< 0.29 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	7.0	4500	400	< 0.015 U	14	910	< 0.37 U	< 0.083 U	46 J		< 0.23 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	5.3	14000	310	< 0.020 U	8.6	590	0.83 J	< 0.10 U	65 J		< 0.27 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	2.5	1900	150	< 0.015 U	9.9	430	< 0.38 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	13	15000	580	0.60	14	870	< 0.42 U	< 0.094 U	77 J		< 0.26 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	13	2900	520	0.023 J	13	910	< 0.45 U	< 0.10 U	65 J		< 0.28 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	5.5	4800 T	340	< 0.013 U	9.2	590	0.58 J	< 0.10 U	57 J		< 0.28 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	17	2800	590	< 0.025 U	20	1000	< 0.58 U	< 0.13 U	< 64 U		< 0.35 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	7.5	5400	450	< 0.017 U	11	1200	< 0.47 U	< 0.11 U	57 J		< 0.29 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	8.1	1800	400	0.027 J	12	900	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	14	1100	1100	0.10	8.9	490 J	< 0.46 U	< 0.10 U	< 52 U		0.33 J
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	12	1900	580 B	0.12	14	560	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	55 T	1900 T	440	0.25 T	13	550	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	67	1700	710	0.097	13	640	0.89 J	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	22 T	1700 T	360	0.061	15 T	590 T	< 0.47 UT	< 0.11 UT	< 52 U		< 0.29 UT
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	39	1500	380	0.097	12	570	0.65 J	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	11	2000	340	0.063	16	780	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	25	3100	190	0.14	10	460	0.40 J	< 0.087 U	43 J		< 0.24 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	5.5	4100	340	< 0.015 U	11	490	0.48 J	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	5.0	3400	280	< 0.021 U	11	390 J	0.45 J	< 0.084 U	46 J		< 0.23 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	6.8	1600	360	< 0.019 U	11	680	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	8.0	2000	390	< 0.020 U	15	600	< 0.41 U	< 0.092 U	< 46 U		< 0.25 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	19	2600	1200	0.038	19	770	< 0.46 U	< 0.10 U	< 51 U		0.65 J
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	5.2	1000	230	0.020	8.4	450	< 0.38 U	< 0.087 U	< 43 U		0.27 J
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	34	1900	320	0.12	12	490 J	< 0.47 U	< 0.11 U	54 J		< 0.29 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	110	1900	430	0.14	14	590	< 0.47 U	< 0.11 U	56 J		0.30 J
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	4.1	3300	180	< 0.0080 U	6.7	480	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	4.9	4100	220	< 0.0078 U	8.7	550	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	7.6	5100	290	0.016 J	11	660	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	9.2	4200	270	0.31	11	660	0.77 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	4.8	2700	190	0.067	9.3	480	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	4.9	4600	250	0.024	8.9	540	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	4.5	2700	190	0.015 J	8.6	500	< 0.43 U	< 0.097 U	50 J		< 0.26 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	8.7	5300	300	0.027	10	610	0.62 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	6.1	2600	490	0.010 J	10	540	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	3.8	2900	230	< 0.0083 U	9.2	530	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	3.9	3800	240	0.0082 J	7.8	450 J	1.0	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	7.7	5600	350	0.017 J	11	660	0.49 J	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	9.1	6700	360	< 0.020 U	13	380 J	< 0.40 U	< 0.090 U	47 J		0.61 J
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	7.8	4300	380	< 0.020 U	12	310 J	< 0.36 U	< 0.080 U	46 J		0.56 J
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	9.0	7800	330 B	< 0.021 U	16 B	410	< 0.27 U	< 0.060 U	51 J		0.20 J
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	15	4000	520	0.029 J	26	660	< 0.41 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	8.1	4600	440	< 0.015 U	15	920	< 0.55 U	< 0.11 U	59 J		< 0.34 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	8.3	7000	430	0.074	17	730	0.59 J	< 0.11 U	72 J		< 0.35 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	9	7600	420	< 0.014 U	14	800	< 0.56 U	< 0.12 U	85 J		< 0.35 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	14	7200	390	0.042	13	670	0.85 J	< 0.11 U	82 J		< 0.34 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	5.4	7500	290	< 0.012 U	12	660	0.94 J	< 0.11 U	85 J		< 0.34 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	5.6	9600	270	< 0.015 U	10	700	1.6	< 0.12 U	89 J		< 0.36 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	9.6	12000	510	< 0.014 U	13	710	< 0.56 U	< 0.11 U	83 J		< 0.35 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	13	9300	470	< 0.017 U	16	770	< 0.6 U	< 0.12 U	70 J		< 0.37 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	7.5	11000	450	< 0.015 U	13	600	1.1	< 0.11 U	100 J		< 0.32 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated	5.6	7000	340	< 0.016 U	11	610	< 0.55 U	< 0.11 U	69 J		< 0.34 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated	8.2	9100	440	< 0.015 U	12	590	< 0.53 U	< 0.11 U	86 J		< 0.33 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated	6	5700	310	< 0.015 U	11	420 J	< 0.57 U	< 0.12 U	54 J		< 0.35 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	6.6	4400	370	< 0.013 U	14	670	< 0.55 U	< 0.11 U	< 28 U		< 0.34 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	6.1	11000	380	< 0.014 U	13	620	0.8 J	< 0.11 U	110 J		< 0.32 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	6.2	12000	640	< 0.015 U	14	740	0.74 J	< 0.11 U	87 J		< 0.34 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	14	5900	630	< 0.015 U	16	970	0.64 J	< 0.11 U	84 J		< 0.35 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	6.6	6000	440	< 0.014 U	11	670	0.68 J	< 0.11 U	80 J		< 0.35 U
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	10	5600	430	< 0.023 U	13	500	< 0.51 U	< 0.1 U	< 59 U		< 0.31 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	6.3	4000	230	< 0.022 U	12	620	< 0.40 U	< 0.082 U	49 J		< 0.25 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	7.5	5300	320	0.025 J	15	490 J	< 0.53 U	< 0.11 U	81 J		< 0.33 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	11	3700	580	< 0.028 U	15	620	< 0.62 UT	< 0.13 U	< 73 U		< 0.39 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	16	7900	500	< 0.021 U	18	700	0.66 J	< 0.10 U	85 J		< 0.31 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	7	6600	290	0.028 J	15	520	< 0.49 U	< 0.1 U	70 J		< 0.31 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	4.6	3900	350	< 0.021 U	9.9	480 J	< 0.58 U	< 0.12 U	< 67 U		< 0.36 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	5.9	7000	240	< 0.024 U	10	590	< 0.58 U	< 0.12 U	77 J		< 0.36 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	5.3	5400	280	< 0.022 U	11	600	< 0.58 U	< 0.12 U	76 J		< 0.36 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	8.0	4900	190	< 0.023 U	13	640	< 0.55 U	< 0.11 U	< 65 U		< 0.35 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	8.8	2300	310	< 0.025 U	13	830	< 0.58 U	< 0.12 U	< 68 U		0.86 J
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	6.0	12000	330	< 0.019 U	14	590	< 0.46 U	< 0.094 U	68 J		< 0.29 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	7.8	18000	400	< 0.019 U	15	590	< 0.50 U	< 0.10 U	82 J		0.48 J
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	7.9	9300	480	< 0.020 U	11	570	< 0.47 U	< 0.096 U	61 J		0.46 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	6.5	7400	350 T	< 0.022 U	10	620 T	< 0.31 UT	< 0.063 U	60 J		0.38 J

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801430971	Not Excavated		11	44
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated		11	57
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated		8.6	31
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated		7.9	44
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated		12	48
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated		12	48
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated		6.2	30
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated		14	81
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated		12	68
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated		13	68
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated		7.2	38
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated		10	65
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated		12	120
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated		15	65
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated		10 T	65
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated		14	59
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated		14	52
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated		6.9	100
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated		7.6	210
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated		7.6	36
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated		11	40
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated		13	49
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated		14	49
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated		9.8	32
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated		11	65
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated		16	94
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated		6.4	27
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated		7.8	34
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated		8.8	40
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated		8.5	51
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated		6.5	34
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated		7.0	41
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated		6.7	28
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated		8.1	49
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated		8.2	41
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated		7.1	31
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated		6.0	30
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated		9.4	44
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated		8.6	58
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated		8.6	54
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated		9.4	41
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated		16	59
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated		11	60 J-
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated		12	67
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated		11	54
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated		9.3	46
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated		8.7	46
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated		8.8	46
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated		9.9	52
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated		11	58
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated		8.2	45
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated		7.9	41
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated		7.5	36
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated		6.4	42
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated		10	52
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated		8.8	59
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated		9.1	52
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated		12	58
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated		7.7	54
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated		8.9	49
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated		8.6	36
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated		8.2	47
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated		9.1	50
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated		10	68
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated		8.8	49
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated		6.9	37
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated		8.0	42
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated		7.9	47
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated		10	59
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated		12	54
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated		9.0	80
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated		11	97
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated		8.3	47
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated		9.1	37

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	2700	0.66 J	4.3	23	0.11 J	0.12 J	130000	4.5		3.2 J	9.8	7600
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	3900	5.2	3.7	27	0.15 J	0.11 J	45000	5.7		3.6 J	15	9500
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	5700	< 0.3 U	4.5	39	0.23 J	0.05 J	13000	8.4		4.5	15	13000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	5200	< 0.034 U	3.9	86 J	0.2 J	0.1 J	24000 J	10		4.5	16	12000
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	4000	< 0.27 U	4.5	39	0.19 J	0.21 J	69000	7.4		3.9 J	14	9700
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	6400	< 0.31 U	4.9	49	0.24 J	0.055 J	29000	15		5.7	21	15000
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	3500	< 0.20 U	3.1	27	0.14 J	0.072 J	22000	4.3		3.4	13	8300
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	5600	< 0.21 U	5.6	40	0.22 J	0.073 J	33000	7.2		5.6	18	13000
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	3500	< 0.18 U	4.2	20	0.16 J	0.068 J	28000	4.5		3.5	11	8700
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	3500	< 0.20 U	3.4	27	0.14 J	0.051 J	21000	4.4		3.7	12	8600
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	4100	< 0.23 U	5.0	29	0.21 J	0.099 J	23000	5.6		4.5	23	12000
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	3800	< 0.22 UT	4.6	29 T	0.18 J	0.055 J	31000	5.0		4.0	13	10000
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	3900	< 0.21 U	5.4	27	0.18 J	0.053 J	26000	4.9		3.9	12	9800
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	3600	< 0.21 U	3.2	28	0.14 J	0.075 J	39000	4.3		3.6	13	9100
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	5500	< 0.20 U	3.8	54	0.21 J	0.11 J	20000	7.0		5.0	20	14000
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	3500	< 0.30 U	4.5	25	0.19 J	0.090 J	28000	4.3		3.1 J	11	8600
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	3700	< 0.29 U	3.8	26	0.17 J	0.081 J	29000	4.8		3.3 J	12	9200
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	4500	< 0.24 U	5.5	32	0.20 J	0.12 J	34000	5.6		4.0	16	11000
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	3100	< 0.23 U	4.2	24	0.17 J	0.067 J	26000	4.2		3.1 J	10	7900
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	3500	< 0.22 U	3.4	27	0.13 J	< 0.053 U	8700	4.4		3.6	11	8900
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	4500	< 0.27 U	2.7	29	0.15 J	0.088 J	48000	5.1		3.9 J	16	10000
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	3500	< 0.33 U	2.9	29	0.15 J	< 0.081 U	22000	4.4		3.3 J	11	8800
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	4200	< 0.33 U	3.2	26	0.18 J	0.097 J	44000	5.5		3.7 J	15	8800
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	3400	< 0.24 U	5.1	29	0.15 J	0.084 J	28000	4.4		3.5 J	16	10000
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	5200	< 0.30 U	4.8	43	0.22 J	< 0.074 U	12000	6.2		4.7 J	27	12000
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	3600	< 0.25 U	2.2	20	0.14 J	0.085 J	25000	4.5		3.3 J	9.8	8500
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	3400	< 0.32 U	2.2	20 J	0.11 J	< 0.077 U	3300	4.0		4.6 J	13	8400
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	2900	< 0.30 U	3.5	21	0.13 J	< 0.073 U	17000	3.7		2.6 J	9.8	7900
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	3700	< 0.27 U	3.4	24	0.14 J	< 0.065 U	14000	5.0		3.3 J	18	9600
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	2900	< 0.23 U	2.3	15	0.11 J	< 0.055 U	28000	4.0		2.3 J	8.0	6900
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	4200	< 0.23 U	3.4	26	0.14 J	0.067 J	38000	5.0		3.7 J	12	9800
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	3600	< 0.24 U	4.1	25	0.13 J	< 0.058 U	20000	4.5		3.1 J	11	9200
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	3800	< 0.26 U	3.1	25	0.14 J	< 0.063 U	7700	4.8		3.3 J	14	9900
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	1600	< 0.30 U	1.9	9.9 J	< 0.11 U	< 0.072 U	26000	1.5		1.5 J	4.1	5300
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	4900	< 0.25 U	4.6	35	0.22 J	< 0.060 U	6700	6.4		4.5	19	12000
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	3000	< 0.28 U	3.2	30	0.12 J	0.10 J	64000	3.2		3.0 J	11	7100
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	3600	< 0.29 U	3.5	37	0.16 J	0.089 J	38000	4.3		3.6 J	15	9500
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	3200	< 0.19 UT	2.8 T	30 T	0.12 JT	0.072 JT	13000	3.9 T		3.4	12 T	8400 T
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	3900	< 0.27 U	4.1	29	0.16 J	0.070 J	4300	5.2		3.8 J	13	11000
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	2700	< 0.29 U	3.8	19	0.12 J	< 0.070 U	9900	3.6		2.5 J	9.5	7300
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	4300	< 0.25 U	4.0	36	0.17 J	0.079 J	15000	5.0		4.0 J	19	10000
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	5400	< 0.32 U	4.9	30	0.2 J	< 0.079 U	5500	10		4.6 J	13	14000
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	5200	0.31 J	4.9	51	0.2 J	0.089 J	1200	7.4	< 0.24 U	4.7 J	15	13000
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	5000	2	58	69	0.17 J	0.6	20000	470	< 0.22 U	11	170	63000
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	4800	< 0.25 U	8.3	49	0.19 J	0.12 J	18000	26	< 0.23 U	4.7	16	13000
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	4200	< 0.3 U	5.8	44	0.2 J	0.11 J	20000	11		5.7	33	16000
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	5600	< 0.3 U	6.8	54	0.22 J	0.17 J	26000	8.5	< 0.23 U	5	21	14000
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	5200	< 0.3 U	4.6	38	0.21 J	0.081 J	15000	9.1	< 0.22 U	5.6	16	13000
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	5000	< 0.21 U	4	36	0.19 J	0.081 J	22000	13	< 0.23 U	4.3	17	13000
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	3800	< 0.30 U	3.1	26	0.15 J	< 0.072 U	1000	5.0		3.5 J	10	9400
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	2700	< 0.29 U	2.9	16 J	0.12 J	< 0.070 U	16000	3.8		2.5 J	8.2	6900
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	4300	< 0.30 U	4.2	28	0.18 J	< 0.074 U	22000	5.4		3.7 J	15	10000
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	5100	< 0.28 U	4.6	40	0.20 J	< 0.068 U	23000	6.4		4.5 J	18	11000
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	5200	0.29 J	4.0	34	0.19 J	< 0.064 U	13000	6.4		5.0	16	12000
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	3900	< 0.26 UT	4.7 T	29 T	0.17 JT	< 0.062 UT	11000	5.2 T		3.9 JT	13 T	9700
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	5000	< 0.24 U	4.7	51	0.21 J	0.060 J	8500	6.1		5.2	16	12000
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	4200	< 0.25 U	5.4	45	0.20 J	0.075 J	31000	6.0		4.6	18	12000
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	9000	< 0.27 U	8.3	86	0.42	0.074 J	8700	11		9.0	23	23000
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	4300	< 0.22 U	3.7	45	0.18 J	0.054 J	17000	4.8		5.1	14	11000
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	5500	< 0.21 UT	4.8	54	0.24 J	0.12 J	25000	6.3		5.6	19	13000
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	5200	< 0.25 U	4.9	58	0.26 J	0.069 J	16000	7.5		5.1	19	15000
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	4800	< 0.20 U	3.0	32	0.20 J	0.30 J	47000	6.4		5.0	24	10000 B
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	4600	< 0.32 U	2.7	27	0.24 J	0.25 J	9300	6.1		5.7	21	9400 B
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	4800	< 0.28 U	4.2	36	0.19 J	0.33 J	27000	7.2		4.4 J	19	12000
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	5500	< 0.24 U	4.6	45	0.23 J	0.35 J	22000	7.1		6.0	17	13000
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	3900	< 0.26 U	2.2	24	0.17 J	0.25 J	25000	5.1		3.7 J	17	8600
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	4900	< 0.25 U	3.4	35	0.18 J	0.30 J	13000	6.3		4.8	16	12000
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	4500	< 0.20 U	2.7	28	0.17 J	0.26 J	24000	5.7		4.6	17	9500
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	7600	< 0.20 U	6.3	59	0.30	0.49	56000	9.3		8.8	21	17000
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	6800	< 0.17 U	6.9	49	0.29	0.43	26000	8.4		7.4	18	16000
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	3400	< 0.22 U	2.7	24	0.14 J	0.22 J	31000	4.6		3.4 J	13	7900
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	11000	< 0.29 U	8.5	92	0.47	0.69	5200	14		12	23	26000
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	6300	< 0.30 U	4.7	44	0.25 J	0.42 J	22000	8.0		6.6	24	15000
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	4300	< 0.28 U	3.5	26	0.17 J	0.29 J	44000	5.5		4.5 J	16	9300

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	9.0	3400	320	< 0.020 U	8.0	400	< 0.36 U	< 0.073 U	77 J		< 0.22 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	4.9	8000	250	< 0.020 U	8.8	360 J	< 0.47 U	< 0.096 U	72 J		0.55 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	9.8	2900	260	< 0.025 U	13	550	< 0.46 U	< 0.093 U	< 54 U		< 0.28 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	7	7800 J+	540	< 0.034 U	11	650	0.71 J	< 0.034 U	66 J		< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	7.5	9400	390	< 0.02 U	10	620	0.94	< 0.084 U	88 J		< 0.26 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	9.6	6400	420	< 0.021 U	15	750	< 0.48 U	< 0.097 U	67 J		< 0.3 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	4.3	2200	240	< 0.018 U	8.6	350	0.37 J	< 0.070 U	37 J		< 0.19 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	12	5000	360	< 0.016 U	14	460	0.54 J	< 0.073 U	52 J		< 0.20 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	4.4	2900	230	< 0.018 U	9.4	370	0.54 J	< 0.063 U	42 J		< 0.17 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	3.9	2400	250	< 0.022 U	9.1	340	0.46 J	< 0.067 U	41 J		< 0.18 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	8.6	4000	260	< 0.024 U	13	480	0.39 J	< 0.079 U	46 J		< 0.22 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	5.2	3200 T	260	< 0.019 U	10	390	0.52 J	< 0.074 U	51 J		< 0.20 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	5.5	2600	260	< 0.021 U	9.6	430	< 0.31 U	< 0.071 U	46 J		< 0.19 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	4.9	2600	300	< 0.017 U	8.6	350	0.66 J	< 0.072 U	44 J		< 0.20 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	7.6	3000	530	< 0.019 U	14	390	0.36 J	< 0.068 U	36 J		< 0.18 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	5.0	2700	250	< 0.019 U	8.6	440 J	< 0.46 U	< 0.10 U	92 BJ		< 0.28 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	5.0	2800	230	< 0.015 U	9.1	390 J	< 0.44 U	< 0.099 U	92 BJ		< 0.27 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	5.7	4000	220	< 0.020 U	11	430	< 0.36 U	< 0.082 U	78 BJ		< 0.22 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	5.0	2700	230	< 0.015 U	8.3	350 J	< 0.35 U	< 0.079 U	71 BJ		< 0.22 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	4.4	4500	320	< 0.015 U	8.9	300 J	< 0.33 U	< 0.075 U	40 J		< 0.20 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	3.9	3100	260	< 0.017 U	9.7	330 J	0.77 J	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	5.1	6000	290	< 0.018 U	7.8	430 J	< 0.51 U	< 0.11 U	57 J		< 0.31 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	5.5	21000	270	< 0.023 U	9.5	640	0.56 J	< 0.11 U	89 J		< 0.31 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	13	9500	340	< 0.020 U	9.7	320 J	0.56 J	< 0.084 U	41 J		< 0.23 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	7.4	3700	410	< 0.019 U	11	540	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	4.1	2200	330	< 0.021 U	8.4	280 J	0.44 J	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	7.2	2000	140	< 0.019 U	8.2	180 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	4.3	4900	230	0.018 J	6.6	340 J	0.47 J	< 0.10 U	51 J		< 0.28 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	4.7	2800	230	< 0.014 U	8.6	350 J	0.52 J	< 0.092 U	51 J		< 0.25 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	3.8	1600	92	< 0.016 U	6.5	280 J	0.54 J	< 0.077 U	58 J		< 0.21 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	6.1	6700	280	< 0.018 U	10	350 J	0.72 J	< 0.080 U	65 J		< 0.22 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	4.7	3700	190	< 0.020 U	8.0	350 J	0.46 J	< 0.083 U	46 J		< 0.23 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	4.9	2900	130	< 0.018 U	8.5	360 J	< 0.39 U	< 0.089 U	46 J		< 0.24 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	3.4	680	500	< 0.024 U	3.6 J	140 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	14	4100	320	0.018 J	12	480	0.46 J	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	5.9	16000	290	< 0.022 U	6.9	430 J	0.90 J	< 0.095 U	95 J		< 0.26 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	6.5	17000	570	< 0.021 U	8.9	420 J	0.66 J	< 0.098 U	60 J		< 0.27 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	4.4	3200 T	390 T	< 0.022 U	9.1 T	220 JT	0.51 JT	< 0.066 U	< 33 U		< 0.18 UT
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	5.4	2700	250	< 0.018 U	9.1	370 J	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	4.5	4200	170	< 0.020 U	6.2	310 J	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	7.0	5800	390	< 0.015 U	10	470	< 0.37 U	< 0.084 U	< 42 U		0.23 J
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	6.4	3500	270	0.022	12	500 J	0.51 J	< 0.11 U	< 55 U		< 0.3 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	5.4	1900	500	< 0.016 U	12	530	< 0.45 U	< 0.1 U	< 50 U		< 0.28 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	92	7300	960	0.95	100	510	4	0.2 J	71 J		0.56 J
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	7.6	8100	400	0.12	14	500	< 0.38 U	< 0.085 U	61 J		< 0.23 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	11	9400	500	0.059	15	500	< 0.45 U	< 0.1 U	59 J		< 0.28 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	6.1	5900	970	< 0.021 U	14	550	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	11	3100	440	0.058	13	630	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	7.8	4800	330	< 0.019 U	12	580	< 0.32 U	< 0.073 U	56 J		< 0.2 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	3.6	1500	210	< 0.0080 U	8.8	380 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	3.6	2700	150	< 0.0077 U	7.0	390 J	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	5.7	3200	330	0.0091 J	9.6	620	0.48 J	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	7.6	3900	310	0.019	11	690	< 0.43 U	< 0.097 U	48 J		< 0.26 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	6.3	3200	280	< 0.0080 U	11	510	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	7.1 T	5000 T	320	0.018	9.1	570 T	< 0.39 UT	< 0.088 UT	< 43 UT		< 0.24 UT
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	10	4200	240	< 0.019 U	13	270 J	< 0.37 U	< 0.083 U	54 J		0.48 J
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	11	19000	280	< 0.021 U	10	330 J	< 0.38 U	< 0.085 U	90 J		0.36 J
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	16	4100	540	< 0.018 U	19	790	< 0.41 U	< 0.093 U	< 46 U		0.82 J
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	7.0	5500	290	< 0.018 U	10	610	< 0.33 U	< 0.075 U	46 J		0.53 J
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	7.3	2400 T	340	< 0.019 U	13	340 J	< 0.33 U	< 0.074 U	73 J		0.52 J
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	9.4	5300	210	< 0.019 U	12	410 J	< 0.39 U	< 0.087 U	97 J		0.45 J
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	8.0	3200	230 B	< 0.022 U	13 B	260 J	< 0.30 U	< 0.069 U	60 J		< 0.19 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	12	3800	88 B	0.026 J	13 B	180 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	7.7	3500	240	< 0.020 U	13	290 J	< 0.42 U	< 0.095 U	49 J		< 0.26 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	8.2	3700	310	< 0.018 U	15	360 J	< 0.37 U	< 0.083 U	43 J		0.24 J
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	6.1	3400	140	< 0.020 U	9.6	220 J	< 0.39 U	< 0.088 U	60 J		< 0.24 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	7.0	5900	120	< 0.024 U	12	180 J	< 0.38 U	< 0.087 U	68 J		< 0.24 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	6.8	3900	140	< 0.023 U	12	250 J	< 0.30 U	< 0.069 U	65 J		< 0.19 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	14	4900	340	< 0.022 U	20	370	< 0.31 U	< 0.070 U	53 J		< 0.19 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	9.0	4900	280	0.032	18	450	< 0.26 U	< 0.058 U	49 J		< 0.16 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	7.0	6400	120	0.093	8.5	150 J	< 0.34 U	< 0.076 U	59 J		< 0.21 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	21	4100	550	0.023 J	26	710	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	11	7700	190	0.024 J	16	220 J	< 0.46 U	< 0.10 U	73 J		< 0.28 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	7.8	21000	160	0.025 J	11	190 J	< 0.42 U	< 0.095 U	110 J		< 0.26 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated		5.3	31
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated		7.0	38
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated		9.4	44
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated		9.5	40 J-
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated		7.7	35
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated		11	55
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated		5.1	33
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated		8.3	62
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated		5.5	26
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated		5.4	34
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated		7.5	41
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated		6.7	30 T
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated		6.2	36
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated		6.3	33
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated		8.1	51
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated		6.1	27
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated		6.1	26
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated		7.2	51
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated		5.4	23
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated		5.6	39
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated		5.9	44
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated		6.3	35
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated		7.1	42
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated		6.0	40
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated		8.3	60
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated		5.2	37
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated		4.1 J	30
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated		5.6	31
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated		6.9	36
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated		4.5	25
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated		6.3	40
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated		5.9	37
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated		6.5	40
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated		2.5 J	17
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated		8.5	51
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated		5.1	30
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated		7.1	36
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated		5.6 T	38 T
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated		6.5	42
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated		4.5 J	30
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated		5.9	46
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated		7.3	50
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated		7.7	49
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated		11	98
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated		7.8	42
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated		9.2	65
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated		7.8	61
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated		8.3	36
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated		7.4	36
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated		5.8	40
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated		5.5	25
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated		7.5	41
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated		9.1	49
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated		7.7	48
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated		7.2 T	39
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated		7.4	53
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated		8.2	52
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated		14	60
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated		8.6	45
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated		8.2	61 T
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated		9.4	69
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated		7.5	48
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated		8.0	61
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated		8.9	55
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated		8.9	48
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated		6.8	51
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated		7.9	53
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated		7.4	44
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated		12	53
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated		10	46
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated		5.5	36
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated		16	61
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated		11	68
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated		7.2	44

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	4000	< 0.29 U	4.3	23	0.18 J	0.31 J	25000	5.6		4.1 J	15	11000
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	5100	< 0.41 U	5.5	36	0.24 J	0.097 J	37000	7.5		4.9 J	17	13000
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated	5000	< 0.36 U	4.1	63	0.19 J	0.091 J	85000	6.1		4.5 J	15	12000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	5100	< 0.31 UT	4.3 T	33 T	0.24 JT	0.096 JT	15000	8.0 T		5.1	20 T	13000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	6000	0.37 J	5.4	50	0.28 J	0.17 J	1800	13		6.1	21	14000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	4800	0.68 J	7.1	40	0.22 J	0.17 J	21000	6.9		4.9 J	17	13000
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated	8100	< 0.36 U	87	72	0.37 J	0.27 J	31000	10		6.5	24	19000
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated	7400	1.8 J	8.8	75	0.38 J	0.27 J	29000	40		7	33	26000
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated	8400	0.59 J	6.4	130	0.42 J	0.18 J	28000	19		6.3	39	17000
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated	8900	< 0.36 U	6.1	59	0.4 J	0.16 J	30000	14		6.8	20	18000
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated	6700	< 0.36 U	6.2	35	0.32 J	0.12 J	7600 J	8.6		6.6	16	17000
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated	7600	3.7	13	110	0.45	0.22 J	4100	26		7.1	55	29000
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated	8500	< 0.39 U	5.5	30	0.34 J	0.043 J	780	11		6.3	19	16000
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated	10000	< 0.38 U	5.8	41	0.36 J	< 0.041 U	520 J	11		7.6	16	15000
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated	5400	< 0.39 UJ	4.2	33	0.23 J	0.069 J	5600 J	7.5		4.3 J	15	12000
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated	10000	< 0.4 U	5.5	130	0.43 J	0.07 J	1400	11		6	11	17000
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated	9900	< 0.38 U	6.7	60	0.42 J	< 0.041 U	3800	11		7.7	19	18000
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated	6100 J	0.45 J	8.3	92	0.49 J	0.14 J	2500	11		7.2	61	20000
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated	10000	< 0.39 U	7.5	79	0.4 J	0.093 J	810	13		7.1	27	19000
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated	8100	0.79 J	11	100	0.41 J	0.19 J	3200	14		6	67	22000
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated	7100	1 J	13	84	0.46	0.59	3700	19		8.1	140	27000
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated	7600	< 0.38 U	6.8	54	0.37 J	0.16 J	15000	11		7.3	23	18000
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated	11000	< 0.41 U	6.4	62	0.45 J	< 0.044 U	810	12		8.3	13	18000
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated	11000	< 0.42 U	6.9	71	0.42 J	0.07 J	1700	13		7.8	16	20000
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated	8800	0.53 J	7.2	75	0.45	0.086 J	1200	11		6	20	17000
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated	11000	< 0.44 U	7	110	0.45 J	< 0.047 U	4900	12		7.2	19	17000
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated	9800	< 0.39 U	4.9	53	0.36 J	< 0.042 U	1100	11		6	19	17000
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated	8800	0.64 J	6.3	54	0.36 J	0.078 J	1400	12		6.7	22	17000
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated	9200	0.4 J	7.5	73	0.43 J	0.12 J	1400	13		6.9	27	18000
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated	8300	0.55 J	7.2	69	0.37 J	0.075 J	760	10		5.7	21	16000
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated	7900	0.46 J	14	72	0.39 J	0.19 J	2300	9.9		8.6	19	18000
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated	4600	0.59 J	6.1	39	0.33 J	0.32 J	43000	20		5.2 J	79 J	22000
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated	11000	0.81 J	9.1	60	0.51	0.05 J	1200	14		7.5	40	23000
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated	10000	8.8	8.4	70	0.47 J	0.096 J	2200	13		8.5	20	20000
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated	9000	< 0.37 U	7.8	75	0.4 J	0.069 J	560 J	11		6.8	24	18000
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated	7900	0.42 J	4.9	46	0.31 J	0.093 J	980	9.3		5.8	26	16000
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated	8200	1.2	18	140	0.5	0.31 J	5600	16		5.5 J	34	34000
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated	11000	0.58 J	6.8	130	0.49 J	0.066 J	2200	13		7.7	17	18000
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated	6500	0.48 J	7	74	0.32 J	0.095 J	5200	9.5		5 J	21	15000
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated	8400	< 0.37 U	7.5	60	0.37 J	0.078 J	2100	10		7.6	24	19000
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated	9300	0.47 J	5.2	52	0.36 J	< 0.041 U	850	10		6	12	15000
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated	10000	0.49 J	6.1	77	0.36 J	0.063 J	340 J	10		7.2	10	15000
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated	10000	0.38 J	6.3	51	0.4 J	0.047 J	240 J	11		6.7	16	17000
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated	12000	0.42 J	7.1	56	0.48 J	0.049 J	470 J	13		7.5	16	20000
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated	10000	0.44 J	6	99	0.4 J	0.068 J	590 J	11		6.5 J	23	18000
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated	8300	< 0.37 U	5.3	51	0.33 J	0.075 J	1100	11		6.4	20	17000
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated	7000	< 0.39 U	4.4	46	0.28 J	0.045 J	1000	10		6	27	17000
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated	8300	0.52 J	7	60	0.38 J	0.13 J	630	11		6.7	23	19000
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated	9100	0.54 J	7.7	65	0.4 J	0.091 J	3500	11		6.7	24	19000
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated	8400	< 0.37 U	6.8	52	0.35 J	0.093 J	1000	10		6.8	24	18000
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated	8300	< 0.39 U	5.8	51	0.35 J	0.099 J	7700	10		6.8	18	17000
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated	7900	1 J	7.9	62	0.37 J	0.13 J	2100	9.4		6.5	22	17000
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated	8700	< 0.39 UJ	8.1	67	0.42 J	0.11 J	2900 J	10		6.8	26	18000
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated	5600	< 0.39 U	5.9	86	0.35 J	0.17 J	1700	8.2		4.7 J	22	14000
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated	9300	< 0.35 U	6.9	80	0.37 J	0.15 J	1100	10		5.4	17	14000
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated	11000	< 0.36 U	9.1	67	0.47	0.13 J	2500	14		9.5	26	24000
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated	9700	< 0.39 UJ	6.2	80	0.38 J	0.11 J	560 J	11		5.9	17	16000
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	8700	< 0.39 U	8.1	85	0.43 J	0.17 J	10000	12		6.7	23	16000
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated	7000	< 0.36 U	6.6	38	0.31 J	0.13 J	3000	11		6.4	18	17000
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	7400	< 0.33 UJ	6.2	43	0.29 J	0.076 J	480	8.3 J		5.4	15	14000
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	11000	1.1 J	9.5	110	0.54	0.13 J	3600	15		7.0	25	18000
Northern Athletic Field	SSHS-B3502A	012721 08:30_SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated	9600	1.2	7.1	86	0.39 J	0.18 J	4900	25	< 0.24 U	8.8	170	25000
Northern Athletic Field	SSHS-B3516	012721 08:30_SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated	5800	0.84 J	12	75	0.42	0.15 J	1400	11		5.6	55	17000
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	11000	1.1 J	12	140	0.62	0.16 J	5200	15		7.4	32	21000
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	9000	0.34 J	5.8	66	0.36 J	0.086 J	860	11		5.9	15	15000
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	7400	60	11	320	0.42 J	0.89	4500	13		5.3 J	34	17000
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	8600	0.55 J	6.1	50	0.33 J	0.11 J	1000	10		5.8	17	16000
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	9600	0.54 J	8	60	0.37 J	0.11 J	12000	11		6.8	30	18000
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	12000	0.48 J	6.1	110	0.45	0.11 J	1100	13		7.6	13	18000
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated	9800	< 0.33 U	5.9	96	0.38 J	0.060 J	2200	12		7.3	30	19000
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	9800	< 0.35 UJ	9.2	170	0.48	0.11 J	2400	15		7.2	31	18000
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	9800	0.44 J	6.5	120	0.42	0.12 J	2400	13		6.8	23	17000
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	9900	0.36 J	6.8	110	0.42	0.10 J	2000	12		6.8	22	17000
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	7500	< 0.35 U	5.5	56	0.33 J	0.11 J	51000	12		7.1	25	17000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	15	4900	210	0.021 J	10	< 82 U	< 0.44 U	< 0.10 U	69 J		< 0.27 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	6.7	6500	360	< 0.017 U	12	730	< 0.62 U	< 0.13 U	88 J		< 0.38 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated	4	12000	390	< 0.014 U	12	650	1.4	< 0.11 U	86 J		< 0.34 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	7.2 T	3000 T	450	0.026 J	13 T	620 T	< 0.46 UT	< 0.095 UT	< 54 U		< 0.29 UT
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	9.0	2300	550	< 0.019 U	14	730	< 0.51 U	< 0.10 U	73 J		0.78 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	7.0	3800	290	< 0.024 U	12	580	< 0.55 U	< 0.11 U	< 64 U		0.77 J
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated	25	4800	400	0.054	17	710	< 0.55 U	< 0.11 U	76 J		< 0.22 U
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated	69	13000	450	0.53	140	880	2.5	< 0.12 U	120 J		< 0.36 U
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated	48	3200	440	0.85	18	890	< 0.59 U	1.1	96 J		< 0.36 U
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated	14	5500	480	0.037	16	720	0.86 J	< 0.11 U	80 J		< 0.34 U
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated	11	4600	410	< 0.013 UJ	15	690	< 0.54 U	< 0.11 U	58 J		< 0.34 U
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated	370	1600	350	0.4	32	670	0.77 J	< 0.12 U	210 J		< 0.36 U
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated	8	2300	370	0.017 J	16	690	< 0.6 U	< 0.12 U	50 J		< 0.37 U
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated	8.7	2100	440	< 0.016 U	14	630	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated	8.8 J	2200 J-	300 J	0.33 J	10	540 J	< 0.59 U	< 0.12 U	53 J		< 0.37 U
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated	14	2000	420	0.038	13	550 J	< 0.61 U	< 0.12 U	46 J		< 0.38 U
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated	14	2300	600	0.048	15	750	< 0.58 U	< 0.12 U	61 J		< 0.36 U
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated	33	1600	210	0.067	18	580 J	0.76 J	< 0.12 U	65 J		< 0.35 U
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated	15	2300	690	0.03 J	17	910	< 0.59 U	< 0.12 U	42 J		< 0.37 U
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated	96	1800	480	0.17	24	620	0.66 J	< 0.12 U	77 J		< 0.37 U
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated	98	2200	410	0.25	31	820	1 J	< 0.12 U	70 J		< 0.37 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated	18	6000	590	0.02 J	19	950	< 0.57 U	< 0.12 U	64 J		< 0.36 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated	8.8	2300	280	0.031 J	14	610	< 0.62 U	< 0.13 U	62 J		< 0.39 U
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated	14	2400	480	0.032 J	17	650	< 0.63 U	< 0.13 U	41 J		< 0.39 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated	37 J-	2000	410	0.1	14	640	< 0.58 U	< 0.12 U	49 J		< 0.36 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated	18	2400	670	0.043	15	650	< 0.66 U	< 0.13 U	58 J		< 0.41 U
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated	9.1	2400	390	0.023 J	15	620	< 0.59 U	< 0.12 U	53 J		< 0.37 U
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated	17	2300	590	0.016 J	18	690	< 0.62 U	< 0.13 U	52 J		< 0.39 U
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated	19	2200	440	< 0.016 U	19	790	< 0.58 U	< 0.12 U	46 J		< 0.36 U
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated	19	1700	470	0.024 J	13	610	< 0.57 U	< 0.12 U	39 J		< 0.36 U
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated	17	1500	1400	0.031 J	14	610	< 0.59 U	< 0.12 U	89 J		< 0.37 U
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated	28	18000	430	0.042 J	27	740	0.67 J	< 0.11 U	73 J		< 0.35 U
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated	10	2600	620	0.016 J	20	1100	< 0.61 U	< 0.12 U	39 J		< 0.38 U
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated	47	2700	400	0.05	18	860	< 0.61 U	< 0.13 U	39 J		< 0.38 U
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated	11	2000	380	0.022 J	17	650	< 0.57 U	< 0.12 U	< 29 UJ		< 0.35 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated	11	2300	450	0.043	15	580	< 0.59 U	< 0.12 U	42 J		< 0.36 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated	51	1200	320	0.062	16	470 J	1.8	< 0.12 U	160 J		< 0.38 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated	20 J	2500	590	0.032 J	18	780	< 0.61 U	< 0.12 U	60 J		< 0.38 U
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated	28	1800	440	0.051	12	650	< 0.61 U	< 0.12 U	65 J		< 0.38 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated	8.5	3000	440	< 0.016 U	18	740	< 0.56 U	< 0.11 U	41 J		< 0.35 U
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated	28	1900	330	0.022 J	12	600	< 0.58 U	< 0.12 U	40 J		< 0.36 U
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated	12	1800	600	0.029 J	12	570 J	< 0.63 U	< 0.13 U	< 32 U		< 0.39 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated	9.1	2100	310	< 0.014 U	15	660	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated	12	2500	280	0.022 J	16	780	< 0.64 U	< 0.13 U	< 32 U		< 0.4 U
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated	20	2000	460	0.065	14	550 J	< 0.66 U	< 0.14 U	35 J		< 0.41 U
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated	7.2	2500	410	0.034	15	680	< 0.56 U	< 0.11 U	43 J		< 0.35 U
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated	6	2500	510	< 0.016 U	14	790	< 0.59 U	< 0.12 U	46 J		< 0.37 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated	11	2600	540	0.022 J	19	700	< 0.6 U	< 0.12 U	41 J		< 0.38 U
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated	11	3700	590	< 0.015 U	18	730	< 0.57 U	< 0.12 U	42 J		< 0.36 U
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated	11	2400	640	< 0.015 U	17	710	< 0.56 U	< 0.11 U	41 J		< 0.35 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated	10	2300	780	< 0.015 U	15	690	< 0.59 U	< 0.12 U	59 J		< 0.37 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated	38	2400	420	0.033 J	18	620	0.63 J	< 0.13 U	54 J		< 0.39 U
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated	20	2300	510	0.28 J	16	610	< 0.59 U	< 0.12 U	57 J		< 0.37 U
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated	28	1400	400	0.083	12	540 J	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated	17	1900	400	0.051	13	490 J	0.66 J	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated	26	3500	440	0.045	23	720	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated	11	2100	420	0.034 J	14	560 J	< 0.6 U	< 0.12 U	< 70 U		< 0.37 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	33	3000	420	0.073	22	740	0.9 J	< 0.12 U	71 J		< 0.37 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated	11	2500	610	< 0.024 U	15	660	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	11	1600	470 J	< 0.023 U	11	430 J	< 0.49 U	< 0.1 U	< 58 U		< 0.31 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	32	2300	430	0.073	18	780	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U
Northern Athletic Field	SSHS-B3502A	012721 08:30_SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated	52	3000	940	< 0.022 U	74	750	< 0.56 U	< 0.12 U	79 J		< 0.35 U
Northern Athletic Field	SSHS-B3516	012721 08:30_SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated	80	1300	300	0.11	29	470 J	0.51 J	< 0.1 U	< 60 U		< 0.32 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	46	2400	440	0.085	19	850	1.1 J	< 0.12 U	< 71 U		< 0.38 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	12	1900	390	< 0.023 U	14	610	< 0.49 U	< 0.099 U	< 57 U		< 0.30 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	710	1700	340	0.088	17	620 J	< 0.67 U	0.14 J	< 78 U		< 0.42 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	20	2200	370	< 0.021 U	15	460 J	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	17	5900	460	0.023 J	17	720	< 0.57 U	< 0.12 U	< 67 U		< 0.36 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	15	2300	520	0.026 J	17	660	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated	37	2100	410	0.060 J	16	610	< 0.43 U	< 0.074 U	65 J		< 0.36 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	130	1800	640	0.18	18	620	< 0.53 U	< 0.11 U	69 J		< 0.33 UJ
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	49	2100	560	0.13	20	670	0.61 J	< 0.10 U	< 59 U		< 0.32 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	56	2100	570	0.13	20	630	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	15	6700	640	0.025 J	19	820	0.95 J	< 0.11 U	93 J		< 0.33 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated		7.9	43
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated		10	43
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated		8.1	40
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated		8.8 T	43 T
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated		11	57
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated		9.4	47
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated		13	54
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated		25	110
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated		15	84
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated		13	58
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated		12	50
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated		18	89
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated		12	52
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated		15	42
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated		8.7	42 J+
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated		16	47
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated		16	51
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated		15	65
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated		18	67
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated		18	90
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated		17	290
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated		14	70
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated		17	45
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated		20	56
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated		14	60 J-
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated		16	55
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated		15	53
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated		13	54
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated		14	62
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated		14	48
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated		14	150
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated		8.1	98
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated		18	63
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated		17	58
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated		14	55
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated		11	64
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated		25	57
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated		16	59
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated		12	61
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated		12	69
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated		14	43
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated		15	49
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated		15	50 J
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated		18	51
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated		17	60
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated		13	54
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated		14	44
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated		13	70
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated		14	68
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated		13	58
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated		13	52
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated		12	51
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated		14	59
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated		11	51
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated		14	49
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated		15	87
Northern Athletic Field	SSHS-B3254	122119 10:30 SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated		13	59
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated		13	68
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated		11	53
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated		11	47 J+
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated		15	59
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated		15	110
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated		12	77
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated		17	70
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated		14	49
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated		17	140
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated		14	54
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated		15	57
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated		17	61
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated		16 B	64
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated		21	250
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated		17	100
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated		16	87
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated		13	65

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	7600	< 0.35 UJ	5.7	60	0.31 J	0.094 J	59000 J	10		5.9	21	15000
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated	7200	< 0.32 UT	6.5	59	0.30 J	0.069 J	580	8.6		7.0	19 B	15000
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated	7800	< 0.29 U	4.9	47	0.31 J	0.067 J	550	8.8		6.6	19 B	16000
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated	7600	< 0.40 U	14	140	0.53 J	0.33 J	5600	14		5.4	41 B	16000
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated	7800	< 0.36 U	46	130	0.49 J	0.33 J	7700	17		4.1	19 B	16000
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated	7800	< 0.35 U	11	93	0.38 J	0.25 J	4300	9.7		4.7	19 B	15000
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated	6600	< 0.30 U	6.9	99	0.30 J	0.22 J	22000	15		6.1	33	17000
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated	9000	< 0.32 U	9.1	77	0.39 J	0.14 J	16000	15		7.0	39	18000
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated	8100	< 0.33 U	9.9	85	0.36 J	0.12 J	19000	12		7.6	110	18000
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated	9400	< 0.30 U	7.2	84	0.44	0.11 J	2700	10		6.3	20	15000
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated	11000	< 0.35 U	6.0	45	0.39 J	< 0.046 U	820	11		6.7	17	18000
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated	7900	< 0.38 U	7.1	79	0.37 J	0.16 J	3900	11		6.0	18	16000
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated	7100	0.36 J	6.8	67	0.31 J	< 0.046 U	330 J	7.7		6.1	17	14000
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated	9000	< 0.35 U	3.7	93	0.28 J	< 0.046 U	200 J	8.2		4.1	8.8	13000
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated	10000	< 0.39 U	4.2	110	0.33 J	< 0.052 U	240 J	9.7		5.1	9.5	14000
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated	9300	< 0.30 U	5.6	61	0.34 J	0.047 J	510	9.8		5.4	15	15000
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated	10000	0.39 J	5.3	130	0.36 J	0.064 J	670	11		5.9	23	15000
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated	9400	< 0.34 U	7.9	130	0.45 J	0.13 J	1400	12		8.6	26	21000
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated	9900	< 0.33 U	7.9	95	0.44 J	0.058 J	4300	12		8.2	20	19000
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated	9400	< 0.35 U	7.2	89	0.43 J	0.088 J	1200	11		7.1	21	20000
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated	7400	< 0.38 UT	7.0 T	46	0.29 JT	< 0.051 U	760 T	9.1 T		7.4	19 T	15000
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated	7300	< 0.38 U	6.4	32	0.30 J	< 0.051 U	720	8.8		6.4	17	16000
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated	8000	< 0.38 U	5.3	42	0.29 J	< 0.051 U	540	8.9		5.8	19	16000
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated	7000	< 0.42 U	5.9	27	0.29 J	< 0.057 U	530 J	8.5		5.9	15	15000
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated	9000	< 0.41 U	8.6	57	0.36 J	< 0.054 U	790	9.7		7.3	29	18000
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated	5800	< 0.32 U	4.8	87	0.25 J	0.086 J	820	7.2		5.0	15	13000
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated	9400	< 0.41 U	6.9	100	0.46 J	0.11 J	1700	13		8.5	21	18000
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated	6800	< 0.33 U	6.2	43	0.27 J	0.054 J	540	8.0		5.6	18	14000
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated	8100	< 0.38 U	7.1	90	0.38 J	0.14 J	2000	12		7.2	26	17000
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated	7300	< 0.33 U	7.1	39	0.35 J	0.091 J	640	9.0		6.8	21	17000
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated	6800	< 0.37 U	9.1	52	0.40 J	0.18 J	980	10		8.0	31	19000
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated	6500	< 0.39 U	6.9	35	0.29 J	0.086 J	540	8.2		6.5	18	15000
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	9500	< 0.40 U	10	98	0.43 J	0.12 J	2400	12		5.8	16	17000
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated	7200	< 0.37 U	10	50	0.45 J	0.072 J	800	9.2		8.6	22	19000
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated	8500	0.42 J	7.5	16 J	0.37 J	0.068 J	730	10		6.7	24	18000
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated	8000	< 0.34 U	7.4	52	0.36 J	0.11 J	1100	9.3		8.2	22	17000
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated	7200	< 0.39 U	6.2	35	0.29 J	0.054 J	590	9.1		5.9	23	16000
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated	6800	< 0.33 U	6.0	50	0.31 J	0.066 J	670	8.5		6.1	22	15000
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated	5600	< 0.30 U	4.2	24	0.26 J	0.072 J	670	6.8		5.2	15	13000
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated	9800	0.36 J	7.2	73	0.41 J	0.073 J	3100	12		7.6	20	19000
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated	8700	< 0.34 U	6.4	63	0.35 J	0.14 J	8700	11		7.1	51	18000
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated	8100	< 0.37 U	6.5	95	0.36 J	0.096 J	1800	13		6.3	36	15000
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated	7400	< 0.35 U	7.3	81	0.37 J	0.21 J	8500	9.5		6.1	23	17000
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated	7800	< 0.34 U	5.9	46	0.32 J	0.080 J	480	9.4		7.7	21	15000
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	7200	0.40 J	7.4	53	0.33 J	0.12 J	840	9.7		8.0	22	18000
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated	7500	< 0.33 U	6.8	57	0.30 J	0.083 J	640	9.0		6.4	22	16000
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated	7800	< 0.33 U	6.5	57	0.32 J	0.096 J	820	9.4		6.3	19	16000
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	9900	0.55 J	9.8	120	0.43 J	0.57	3900	11		5.5	51	20000
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated	7100	< 0.34 U	5.4	38	0.29 J	0.063 J	410 J	8.3		6.7	15	14000
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated	7400	< 0.35 U	7.3	81	0.37 J	0.21 J	8500	9.5		6.1	23	17000
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	14000	0.46 J	33	200	0.78	0.18 J	13000	22		5.3	17	21000
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated	10000	< 0.35 U	7.3	43	0.40 J	0.058 J	460 J	11		8.7	20	18000
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated	9000	< 0.44 U	5.8	140	0.36 J	0.079 J	1900	9.4		4.9	10	13000
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated	9000	< 0.37 U	5.4	67	0.35 J	0.055 J	910	9.5		5.5	15	14000
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	9100	< 0.32 U	6.0	96	0.46	0.12 J	1600	13		7.2	38	18000
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	8600	< 0.33 U	6.1	74	0.43 J	0.12 J	2000	11		6.7	20	17000
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	5700	0.87 J	13	170	0.49 J	2.0	7100	15		5.8	63	16000
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated	7800	< 0.28 U	4.4	70	0.32 J	0.11 J	720	8.3		4.6	11	12000
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated	7300	< 0.22 UT	5.4 T	96 T	0.37 T	0.057 JT	1500 T	10 T		6.2	16	14000
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated	7600	< 0.32 U	6.5	91	0.36 J	0.078 J	1600	14		5.3	47	15000
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	8200	0.25 J	6.7	78	0.37	0.050 J	2900	9.2		5.0	21	13000
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated	9000	< 0.25 U	5.1	93	0.37	0.066 J	1100	9.5		5.4	17	14000
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated	7100	0.33 J	6.9	57	0.32 J	2.2	1400	11		5.8	26	25000
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	9500	< 0.45 UT	8.6 T	61 T	0.47 JT	0.067 JT	1100 T	11 T		6.1	34 T	19000
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	6600	< 0.28 U	7.1	69	0.35	0.12 J	1300	9.7		5.9	25	17000
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	7400	< 0.37 U	9.1	82	0.40 J	0.11 J	2800	11		5.4	23	16000
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated	8500	0.70 J	6.8	76	0.40	0.081 J	1700	10		6.5	37	17000
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	6900	0.48 J	9.0	85	0.43	0.040 J	1500	8.6		4.6	21	11000
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	10000	< 0.35 U	9.0	79	0.43	< 0.038 U	980	17		6.9	27	21000
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated	9000	< 0.35 U	6.3	100	0.43	0.11 J	1100	11		7.0	13	16000
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated	9100	< 0.33 U	7.9	77	0.40	0.11 J	1400	11		7.1	24	18000
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	6900	< 0.30 U	6.9	67	0.34 J	0.087 J	1100	9.4		5.7	29	15000
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated	8800	< 0.29 U	5.8	42	0.35	0.032 J	370 J	9.3		6.0	16	16000
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated	9300	< 0.28 U	5.4	65	0.34	< 0.030 U	720	10		5.5	16	16000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	15	8200 J	400	0.031 J	16	900	0.73 J	< 0.11 U	90 J		< 0.33 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated	7.9	2000	360	0.037 J	17	390 J	0.51 J	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated	7.0	2000	330	0.035 J	17	390 J	0.46 J	< 0.064 U	< 50 U		< 0.32 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated	69	1600	220	0.094 J	16	430 J	0.81 J	0.16 J	100 J		< 0.45 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated	17	830	90	0.33	14	370 J	1.3 J	< 0.082 U	290 J		0.78 J
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated	31	1100	210	0.12	13	410 J	0.83 J	< 0.080 U	160 J		< 0.39 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated	57	2800	310	0.075 J	33	570	< 0.39 U	< 0.068 U	100 J		< 0.33 U
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated	56	2700	390	0.057 J	38	700	< 0.42 U	< 0.073 U	60 J		< 0.36 U
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated	52	2800	580	0.053 J	35	660	< 0.42 U	< 0.073 U	63 J		0.38 J
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated	35	2100	410	0.087 J	16	640	< 0.40 U	< 0.069 U	< 53 U		0.35 J
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated	11	2300	200	< 0.023 U	17	550	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated	35	1900	340	0.068 J	16	580	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated	7.7	1600	370	0.027 J	15	540	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated	7.2	1400	580	0.043 J	10	400 J	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated	9.7	1600	480	0.032 J	11	380 J	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated	14	1900	280	0.055 J	14	460	0.45 J	< 0.068 U	< 52 U		< 0.33 U
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated	17	1800	630	0.063 J	16	510 J	< 0.49 U	< 0.084 U	< 65 U		0.50 J
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated	21	2700	990	0.044 J	24	630 B	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated	36	2600	520	0.080 J	20	710 B	0.47 J	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated	33	2100	590	0.078 J	16	410 BJ	0.50 J	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated	11 T	1900	500	0.027 J	15	530 BJ	< 0.50 UT	< 0.087 UT	< 67 UT		< 0.43 U
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated	8.6	2000	320	0.027 J	16	540 B	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated	7.7	2200	280	0.020 J	15	550 B	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated	7.5	1900	200	< 0.025 U	13	480 BJ	< 0.55 U	< 0.096 U	< 74 U		< 0.47 U
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated	13	1800	390	0.025 J	17	550 BJ	< 0.53 U	< 0.092 U	< 71 U		< 0.45 U
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated	8.6	1600	310	0.022 J	13	450	< 0.41 U	< 0.072 U	< 55 U		< 0.35 U
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated	19	2500	510	0.047 J	21	870 B	< 0.54 U	< 0.093 U	< 72 U		< 0.46 U
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated	9.1	1700	500	0.029 J	15	460 B	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated	30	2200	460	0.072 J	19	680 B	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated	8.6	2000	450	0.062 J	17	540	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated	18	1900	700	0.042 J	24	650	< 0.48 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated	7.2	1700	510	0.038 J	16	480 J	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	23	2000	220	0.080 J	15	560	< 0.53 U	< 0.091 U	< 71 U		< 0.45 U
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated	9.6	1500	1000	0.070 J	18	550	< 0.48 U	< 0.083 U	< 64 U		0.82 J
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated	8.5	2200	430	0.036 J	16	650	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated	8.2	2200	390	0.027 J	18	680	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated	7.2	2100	280	0.033 J	15	520 J	0.76 J	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated	8.3	1800	460	0.037 J	15	530	0.45 J	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated	5.6	1800	300	0.024 J	14	530	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated	16	3200	380	0.034 J	20	680	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated	49	2800	570	0.31	20	580	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated	27	1600	730	0.11	35	380 J	0.53 J	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated	15	5200	680	0.04 J	19	530	< 0.46 U	< 0.08 U	< 62 U		0.4 J
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated	9.2	2000	490	< 0.018 U	16	510	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	12	1800	450	< 0.022 U	15	510	0.64 J	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated	12	1900	440	< 0.021 U	17	470	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated	16	2000	360	< 0.019 U	16	460	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	55	1700	430	0.11 J	13	420 J	0.62 J	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated	9.3	1800	370	< 0.021 U	15	450 J	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated	15	5200	680	0.040 J	19	530	< 0.46 U	< 0.080 U	< 62 U		0.40 J
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	20	1600	180	0.059 J	15	490 J	< 0.52 U	< 0.090 U	350 J		< 0.45 U
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated	10	2200	350	< 0.018 U	17	550	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated	14	1500	780	0.030 J	11	380 J	< 0.58 U	< 0.10 U	< 78 U		< 0.49 U
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated	13	1700	350	< 0.018 U	13	400 J	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	16	2400	460	0.040 J	24	680	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	27	2500	490	0.055 J	18	800	< 0.43 U	< 0.074 U	< 58 U		< 0.37 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	280	1500	260	0.18	19	480 J	2.0 J	< 0.093 U	77 J		< 0.46 U
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated	8.5	1500	410	0.027 J	12	350 J	< 0.42 U	< 0.086 U	< 50 U		< 0.26 U
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated	25 T	1800 T	380	0.031 J	17	600 T	0.49 JT	< 0.070 UT	< 40 UT		< 0.21 UT
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated	24	1600	470	0.058	29	480	0.82 J	< 0.10 U	< 58 U		< 0.31 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	17	1500	230	0.036	12	450	0.61 J	< 0.075 U	94 J		< 0.23 U
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated	15	1800	520	0.057	14	400	0.59 J	< 0.078 U	< 45 U		< 0.24 U
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated	36	1700	520	0.27	15	510	0.76 J	< 0.086 U	< 49 U		< 0.26 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	12	1900 T	700 T	< 0.023 UT	17	530 JT	< 0.68 UT	< 0.14 UT	< 79 UT		< 0.21 UT
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	25	1700	500	0.028 J	16	550	< 0.43 U	< 0.088 U	< 51 U		< 0.27 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	25	1500	300	< 0.023 U	13	520 J	0.73 J	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated	97	2100	620	0.51	17	540	0.66 J	< 0.10 U	< 59 U		< 0.32 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	46	1500	290	0.099	10	390 J	2.0	< 0.092 U	< 53 U		< 0.28 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	38	2500	390	0.32	16	630	0.58 J	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated	23	2200	420	0.044	17	780	0.73 J	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated	25	2200	470	0.045	19	570	0.56 J	< 0.10 U	< 58 U		< 0.31 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	21	1700	400	0.044	16	450	< 0.46 U	< 0.093 U	< 53 U		< 0.28 U
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated	8.3	2000	290	0.028 J	14	410 J	< 0.44 U	< 0.090 U	< 51 U		< 0.27 U
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated	8.5	2200	280	0.027 J	15	420	< 0.42 U	< 0.086 U	< 49 U		< 0.26 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated		12	58
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated		11	58
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated		11	51
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated		15	68
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated		17	21
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated		14	38
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated		13	74
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated		15	88
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated		15	83
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated		16	62
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated		17	54
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated		13	51
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated		11	50
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated		14	40
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated		16	46
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated		15	48
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated		15	54
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated		16	78 B
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated		15	63 B
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated		15	110 B
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated		12	59 B
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated		12	50 B
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated		14	58 B
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated		12	39 B
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated		15	65 B
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated		9.6	48
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated		14	64 B
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated		11	49 B
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated		13	74 B
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated		12	64
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated		15	130
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated		11	59
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated		15	48
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated		13	120
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated		14	62
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated		14	80
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated		11	55
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated		11	58
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated		9.0	46
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated		14	59
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated		13	120
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated		13	55
Northern Athletic Field	B522	110621 09:30 SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated		13	87
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated		12	72
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated		12	54
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated		12	69
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated		12	62
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated		14	270
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated		11	61
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated		13	87
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated		29	20
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated		15	52
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated		14	44
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated		13	46
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated		14	67
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated		15	67
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated		17	240
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated		11	41
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated		10 T	45
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated		12	63
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated		12	45
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated		13	52
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated		12	860
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated		15 T	94
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated		12	54
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated		17	42
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated		14	64
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated		17	32
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated		30	66
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated		13	66
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated		15	66
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated		12	52
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated		13	44
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated		13	48

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	7800	0.45 J	9.5	120	0.44 J	0.082 J	2000	9.2		4.7 J	28	14000
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	5500	< 0.27 U	5.9	33	0.29 J	0.13 J	8100	7.8		5.5	21	14000
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	6500	0.37 J	6.4	56	0.33	0.15 J	11000	11		5.7	39	16000
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	7500	2.0	6.8	82	0.38	0.14 J	4100	36		6.7	44	17000
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	7100	< 0.27 U	6.6	63	0.33 J	0.15 J	2200	9.9		5.8	40	16000
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	3700	0.76 J	13	63	0.44	0.23 J	1200	9.5		4.8	34	19000
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	7500	0.60 J	8.2	95	0.41	0.65	2500	20		6.2	70	18000
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	23000	2.4 J	29	280	1.3	1.7	11000	63		21	390	72000
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	8000	4.2	8.5	72	0.36	0.093 J	4700	11		7.1	37	17000
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	6800	< 0.22 UT	6.4 T	55 T	0.30 T	0.084 JT	1600 T	8.5 T		6.0	21 T	14000
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	5200	2.9 J	13	66	0.55	2.8	22000	98		9.5	410	89000
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	7800	< 0.24 U	5.6	66	0.34	0.13 J	1300	11		6.5	23	15000
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	5900	0.20 J	6.2	42	0.29	0.17 J	6200	8.5		6.1	31	15000
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	6300	< 0.31 U	5.2	49	0.31 J	0.083 J	1200	8.8		5.4	22	15000
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	4900	< 0.25 U	4.9	34	0.26 J	0.066 J	1300	7.0		4.6	18	11000
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	5300	< 0.29 U	6.1	37	0.27 J	0.11 J	33000	7.0		5.4	19	13000
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	8100	< 0.26 U	6.5	31	0.37	< 0.064 U	450	9.6		7.0	18	16000
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	6800	< 0.20 U	6.8	59	0.36	0.15 J	1800	9.1		5.9	33	15000
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	7000	< 0.23 U	7.1	55	0.34	0.088 J	1100	8.9		6.6	23	16000
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	6300	< 1.2 U	19	48	0.29 J	< 0.059 U	1400	17		7.8	28	160000
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	7500	< 0.27 U	9.4	93	0.40	0.16 J	14000	10		6.6	24	16000
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	6800	< 0.28 U	7.1	59	0.30 J	0.086 J	37000	7.4		5.3	16	12000
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	5300	0.60 J	9.1	46	0.45	0.30 J	1200	7.4		6.6	32	15000 B
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	5200	< 0.23 U	4.7	47	0.23 J	0.058 J	20000	6.5		4.7	14	12000
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	7500	0.33 J	6.3	56	0.34	< 0.053 U	1200	9.6		7.1	21	17000
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	6900	0.42 J	9.2	88	0.38	0.41	3300	11		5.4	69	19000 B
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	6500	< 0.21 U	5.4	42	0.28	< 0.051 U	600	7.8		6.5	23	15000 B
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	7300	< 0.26 U	7.6	59	0.36	< 0.063 U	1600	10		6.8	33	16000 B
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	7500	0.29 J	6.0	51	0.35	< 0.056 U	1900	8.5		6.5	19	15000
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	3800	< 0.26 U	2.6	22	0.15 J	< 0.063 U	28000	4.7		3.3 J	13	8900
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	4000	< 0.23 U	3.4	28	0.18 J	0.087 J	51000	5.2		3.4 J	14	9200
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	2300	< 0.22 U	1.8	20	0.12 J	0.13 J	110000	3.1		2.5 J	12	5700
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	4500	< 0.18 U	4.1	39	0.21 J	0.11 J	39000	5.3		4.2	16	9400
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	5800	< 0.20 U	5.2	28	0.26 J	< 0.049 U	900	6.8		4.8	15	13000
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	7200	< 0.25 U	4.6	35	0.26 J	< 0.060 U	610	7.8		4.1	14	12000
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	7600	< 0.27 U	4.8	32	0.27 J	< 0.066 U	9100	8.0		4.5	19	13000
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	7900	< 0.29 U	7.3	44	0.35 J	< 0.069 U	970	9.2		6.3	21	16000
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	4100	0.56 J	13	74	0.38	0.41	12000	8.7		4.6	110	20000
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	5400	0.26 J	6.2	30	0.26 J	< 0.052 U	810	6.4		4.8	17	13000
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	5600	< 0.25 U	6.0	47	0.24 J	0.079 J	4400	8.3		5.9	24	17000
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	6100	< 0.29 U	4.9	43	0.25 J	0.075 J	27000	7.8		4.8	19	14000
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	5800	0.29 J	4.2	43	0.24 J	0.090 J	25000	7.6		5.0	18	13000
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	6100	< 0.27 U	5.7	43	0.29 J	0.066 J	4100	7.6		5.0	23	14000
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	6300	< 0.28 U	5.6	44	0.28 J	0.091 J	6700	7.9		5.3	20	15000
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	10000	< 0.27 U	6.7	65	0.41	< 0.066 U	2400	11		7.3	27	18000
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	11000	< 0.33 U	8.2	85	0.45	0.088 J	43000	12		8.3	24	21000
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	5600	< 0.24 UT	3.0	31	0.20 J	< 0.059 U	2300 T	6.1		3.1 J	11	9800
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	7400	0.33 J	6.2	72	0.31 J	0.098 J	28000	8.8		5.7	21	15000
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	7700	0.34 J	3.6	62	0.26 J	< 0.073 U	8700	8.1		4.4 J	11	13000
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	6300	< 0.29 U	6.2	70	0.27 J	0.10 J	46000	9.2		6.0	26	15000
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	6500	< 0.31 U	4.9	61	0.28 J	0.090 J	27000	8.5		5.6	22	14000
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	9200	< 0.31 U	6.1	98	0.47	0.21 J	2100	11		8.0	12	17000
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	5600	< 0.25 U	5.3	39	0.25 J	< 0.062 U	8700	7.2		5.2	19	14000
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	4300	< 0.28 U	4.6	36	0.18 J	0.099 J	34000	5.2		4.3 J	15	13000
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	4000	0.59 JT	6.9 T	56	0.28 JT	0.14 JT	2300 T	7.4 T		3.4 JT	60 T	11000 T
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	4300	< 0.27 UT	3.4	28 T	0.20 JT	0.068 J	27000 T	5.2 T		3.9 J	17 T	9900
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	6400	< 0.29 U	4.6	32	0.22 J	< 0.069 U	460 J	7.5		5.3	14	13000
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	9700	0.24 J	6.7	50	0.30	< 0.055 U	640	10		5.7	7.8	20000
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	6900	< 0.28 U	5.5	25	0.25 J	< 0.067 U	520	8.7		5.6	19	15000
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	8500	< 0.32 U	5.8	77	0.32 J	0.091 J	1400	11		6.0	15	16000
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	6400	0.34 J	5.3	82	0.30 J	0.090 J	15000	7.6		5.0	16	13000
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	6700	< 0.28 U	5.1	43	0.25 J	< 0.067 U	670	8.5		5.3	19	16000
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	4700	0.36 J	3.6	38	0.21 J	0.089 J	54000	5.2		5.2	17	12000
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	6100	0.69 J	6.0	55	0.36 J	0.34 J	3000	7.4		5.0	23	22000
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	7900	0.34 J	5.9	53	0.36 J	0.11 J	910	9.5		7.3	30	19000
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	6000	0.54 J	6.6	69	0.32 J	0.48	2000	7.6		5.4	31	15000
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	10000	0.38 J	5.1	47	0.38 J	< 0.078 U	690	11		6.6	11	17000
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	9300	< 0.35 U	4.8	100	0.38 J	0.097 J	1800	9.7		5.7 J	13	15000
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	7400	< 0.34 U	6.6	60	0.39 J	0.083 J	850	8.6		7.3	30	16000
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	9800	< 0.33 U	6.8	100	0.48	0.12 J	1900	11		8.8	12	18000
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	8300	0.51 J	3.8	120	0.31 J	< 0.090 U	1800	7.8		3.9 J	9.3	12000
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	8900	0.46 JT	6.8	52 T	0.43	< 0.076 UT	690	9.8 T		8.2	22 T	18000
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	7300	0.29 J	3.8	72	0.39	< 0.056 U	1000	7.3		7.3	16	12000
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	7500	0.86 J	5.6	78	0.41 J	0.17 J	27000	18		6.4	18	14000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	36	1400	400	0.16	12	460 J	1.0 J	< 0.12 U	< 71 U		< 0.38 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	15	2700	370	< 0.020 U	15	590	0.40 J	< 0.082 U	< 47 U		< 0.25 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	46	7100	310	1.7	17	660	0.43 J	< 0.086 U	< 49 U		< 0.26 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	92	2500	400	0.27	21	660	2.1	< 0.094 U	< 54 U		< 0.29 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	25	2000	330	0.053	31	540	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	36	710	230	0.41	15	350 J	3.3	< 0.080 U	< 39 U		0.27 J
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	43	1600	310	0.12	48	540	0.57 J	< 0.078 U	52 J		< 0.21 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	230	6000	1200	0.47	140	1600	2.5 J	< 0.33 U	< 160 U		< 0.90 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	62	2900	390	0.043	30	620	0.51 J	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	14 T	1800	350 T	0.039	19	600 T	< 0.33 UT	< 0.074 UT	< 37 UT		< 0.20 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	93	3500	620	0.24	160	440	1.8	0.21 J	60 J		0.61 J
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	18	2000	390	0.046	22	560	0.64 J	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	15	4100	390	0.041 B	20	500	0.41 J	< 0.070 U	35 J		< 0.19 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	15	1800	370	0.030 B	17	470 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	8.1	1600	390	0.025 BJ	15	450	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	10	1900	410	0.040 B	15	560	0.55 J	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	11	2100	340	0.033 B	16	500	0.56 J	< 0.090 U	540		< 0.25 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	22	1700	390	0.046 B	22	400	0.34 J	< 0.068 U	43 J		< 0.19 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	22	2000	560	0.029 J	16	510	< 0.35 U	< 0.079 U	< 39 U		0.69 J
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	15	1100	700	0.043	21	340 J	2.2	< 0.084 U	< 41 U		0.94 J
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	39	4100	340	0.70	19	650	0.63 J	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	16	4000	410	0.11	17	560	0.68 J	< 0.096 U	66 J		< 0.26 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	14	1400	280	0.11	21	390 J	0.89	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	6.6	5300	340	< 0.020 U	12	460	0.37 J	< 0.079 U	< 39 U		< 0.21 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	11	2300	350	0.031	19	560	0.36 J	< 0.075 U	< 37 U		< 0.21 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	48	1400	290	0.22	76	410	0.66	< 0.067 U	77 J		< 0.18 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	8.2	1900	410	0.031	14	420	0.50 J	< 0.073 U	< 36 U		< 0.20 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	24	1700	530	0.047	17	570	0.44 J	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	11	1900	490	0.031 J	15	540	0.42 J	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	4.4	4700	210	0.022 J	8.9	310 J	0.45 J	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	14	19000	280	0.096	10	310 J	0.65 J	< 0.079 U	61 J		< 0.22 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	4.1	3600	440	< 0.022 U	7.0	270 J	1.4	< 0.076 U	66 J		< 0.21 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	18	8500	300	0.34	11	330	0.60	< 0.061 U	47 J		< 0.17 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	8.1	1500	260	0.031 J	12	420	< 0.31 U	< 0.070 U	< 34 U		< 0.19 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	5.8	1700	170	0.027	11	380 J	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	5.6	2300	260	0.036	12	420 J	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	11	1900	280	0.030	16	630	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	200	1500	280	0.14	14	310 J	1.1	< 0.075 U	44 J		< 0.21 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	7.0	1500	270	0.026 J	12	480	< 0.33 U	< 0.074 U	< 36 U		< 0.20 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	18	2000	420	0.050	14	390 J	< 0.38 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	11	3900	280	0.023 J	13	500	0.67 J	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	12	4400	350	0.026 J	13	450 J	< 0.42 U	< 0.095 U	49 J		< 0.26 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	39	2300	350	0.061	13	570	< 0.41 U	< 0.092 U	< 45 U		< 0.25 UT
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	27	2800	350	0.052	13	590	0.64 J	< 0.097 U	< 48 U		< 0.26 UT
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	18	2400	560	0.032	17	570	0.49 J	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	22	5400	520	0.029 J	20	820	0.80 J	< 0.11 U	69 J		< 0.31 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	7.0	1400	150 T	0.040	8.3	320 J	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	28	4500	330	0.050	16	640	0.47 J	< 0.11 U	92 J		< 0.29 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	8.4	2800	260	0.043	11	410 J	< 0.46 U	< 0.10 U	55 J		< 0.28 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	15	5300	370	0.091	34	570	0.90 J	< 0.10 U	64 J		< 0.28 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	16	5400	360	0.18	22	540	< 0.47 U	< 0.11 U	56 J		< 0.29 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	15	2600	490	0.085	18	730	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	12	4300	400	0.022 J	13	460	0.47 J	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	4.9	4800	380	0.83	12	340 J	0.94	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	51 T	1100 T	140 T	0.42 T	10 T	300 JT	0.69 JT	< 0.11 UT	< 52 UT		0.30 JT
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	6.0	5000 T	250	0.037	10 T	380 JT	0.61 J	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	6.2	1700	340	0.045	12	410 J	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	6.5	1900	340	0.056	12	440	0.40 J	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	8.0	1800	320	0.045	13	440 J	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	15	2000	440	0.074	14	590	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	27	3400	490	0.082	12	620	< 0.46 U	< 0.10 U	230 J		< 0.28 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	6.2	2000	300	0.037	14	400 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	15	5900	340	0.047	20	390 J	0.81 J	< 0.10 U	57 J		< 0.28 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	38	1300	650	0.11	13	480 J	< 0.46 U	< 0.10 U	78 J		< 0.28 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	30	2000	400	0.039	15	580	0.62 J	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	52	1300	330	0.10	14	490	0.73 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	8.4	2200	230	< 0.024 U	14	560	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	20	1700	590	0.047	12	500 J	< 0.54 U	< 0.12 U	< 60 U		< 0.33 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	14	1700	540	0.047	13	520 J	< 0.52 U	< 0.12 U	< 58 U		0.33 J
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	12	2700	500	0.039	19	890	< 0.51 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	16	1300	690	0.046	8.8	350 J	< 0.57 U	< 0.13 U	< 63 U		0.57 J
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	9.6	2200 T	450 T	0.029 J	16 T	600 T	< 0.48 UT	< 0.11 UT	< 53 U		< 0.29 UT
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	7.5	1400	410	0.041	9.2	350 J	< 0.35 U	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	25	15000	380	0.40	28	730	0.58 J	0.31 J	< 55 U		< 0.30 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated		13	50
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated		10	75
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated		11	98
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated		12	96
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated		11	62
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated		14	92
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated		14	77
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated		45	440
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated		13	69
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated		11 T	48 T
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated		18	270
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated		12	54
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated		9.4	87
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated		11	50
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated		8.1	44
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated		9.0	42
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated		12	47
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated		11	53
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated		12	79
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated		21	55
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated		17	87
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated		9.9	37
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated		11	300
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated		8.1	36
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated		12	53
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated		12	90
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated		9.4	47
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated		12	56
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated		12	44
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated		6.1	34
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated		6.9	39
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated		4.1	24
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated		7.4	38
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated		9.1	38
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated		11	32
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated		9.9	39
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated		13	52
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated		11	140
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated		10	41
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated		9.5	56
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated		9.8	51
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated		9.2	53
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated		12	55
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated		11	68
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated		15	58
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated		16	75
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated		8.1	28 T
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated		12	60
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated		11	42
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated		9.9	57
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated		9.7	100
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated		11	74
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated		8.9	50
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated		7.8	51
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated		8.8 T	71 T
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated		7.1 T	41 T
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated		8.8	43
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated		14	36
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated		11	39
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated		13	45
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated		11	69
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated		9.4	55
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated		11	61
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated		13	100
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated		13	60
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated		12	140
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated		16	41
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated		14	45
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated		12	49
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated		13	49
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated		12	43
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated		14 T	53 T
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated		11	30
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated		12	64

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	7000	0.63 J	5.3	86	0.37 J	0.13 J	7200	10		5.7	21	17000
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	5300	1.1	7.4	140	0.36	0.10 J	4000	16		5.5	55	19000
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	6100	0.35 J	5.5	67	0.30 J	0.11 J	22000	18		5.2	26	13000
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	7000	0.40 J	7.4	60	0.33 J	0.098 J	24000	9.0		6.0	20	14000
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	7400	0.59 J	6.0	61	0.35 J	0.12 J	16000	9.4		5.9	23	14000
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	5400	< 0.31 U	4.9	48	0.25 J	0.11 J	9600	7.4		4.2 J	15	12000
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	7600	0.31 J	5.3	79	0.29 J	0.080 J	1500	8.2		4.6 J	16	13000
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	5800	0.55 J	6.0	79	0.29 J	0.11 J	2700	9.1		4.6 J	34	14000
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	6600	< 0.27 U	4.8	45	0.26 J	< 0.067 U	1100	7.9		4.5	16	13000
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	2700	1.4	7.9	130	0.29 J	0.13 J	3200	13		3.9 J	65	28000
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	6500	0.69 J	5.6	59	0.61	0.17 J	1600	11		8.0	54	15000
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	7000	0.53 J	7.2	76	0.31 J	0.18 J	2900	9.0		4.2 J	37	15000
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	5300	0.61 J	7.7	79	0.33 J	0.20 J	2700	8.6		5.0 J	35	14000
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	8100	0.43 J	5.9	84	0.30 J	0.076 J	1600	8.9		4.9	16	14000
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	5100	< 0.28 U	4.7	29	0.22 J	0.17 J	12000	6.2		5.0	19	12000
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	5500	< 0.26 U	5.1	51	0.25 J	0.13 J	39000	6.4		4.4	24	11000
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	6400	< 0.32 U	4.9	38	0.25 J	0.092 J	22000	7.5		5.6	18	14000
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	6100	< 0.34 U	5.5	34	0.30 J	< 0.083 U	2000	8.3		6.4	19	15000
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	1600	< 0.33 U	2.3	14 J	< 0.12 U	< 0.079 U	8300	2.4		1.8 J	6.4	4700
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	7800	< 0.30 U	7.3	47	0.36 J	0.075 J	1300	9.4		5.3	22	16000
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	6200	< 0.27 U	5.5	33	0.27 J	0.077 J	6200	7.7		4.6	18	13000
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	6500	< 0.26 UT	5.5	32	0.29 J	0.068 J	710	7.8		5.6	17	14000
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	5500	0.27 J	4.3	44	0.23 J	0.088 J	690	6.3		5.0	18	12000
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	6000	0.50 J	5.8	72	0.30 J	0.15 J	13000	8.6		5.0	26	13000 B
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	6400	9.8	5.2	77	0.31 J	0.16 J	11000	8.8		4.8 J	52	13000 B
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	6000	0.39 J	5.0	50	0.27 J	0.15 J	12000	7.9		5.4	19	13000 B
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	3600	0.64 J	2.9	43	0.15 J	< 0.084 U	760	4.6		2.5 J	7.8	6600 B
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	5200	0.74 J	7.5	61	0.37 J	< 0.079 U	1700	6.1		4.6 J	24	12000 B
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	8800	< 0.29 UT	4.3 T	94 T	0.35 JT	0.091 JT	1800 T	9.4 T		5.5	9.7 T	14000 B
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	6700	0.70 J	4.7	44	0.29 J	0.082 J	2400	8.4		4.8	22	13000 B
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	2600	0.60 J	2.2	20	< 0.11 U	< 0.074 U	2100	3.3		2.1 J	14	5800 B
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	4700	0.35 JT	4.6 T	30 T	0.19 JT	0.077 JT	1500 T	5.9 T		3.9 JT	13 T	10000 B
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	5500	0.44 J	5.7	42	0.26 J	0.098 J	910	7.2		5.1	18	13000 B
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	5800	0.46 J	6.5	38	0.30	0.12 J	3100	7.9		5.7	20	15000 B
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	6200	0.51 J	8.6	40	0.26 J	0.091 J	3300	8.7		6.0	20	16000 B
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	1700	0.40 J	1.6	10 J	< 0.10 U	< 0.067 U	920	2.3		1.3 J	4.4	4000 B
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	5500	< 0.28 UT	4.2 T	42	0.22 JT	0.095 JT	910 T	6.9 T		4.7	15	12000
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	6700	0.58 J	5.0	41	0.25 J	0.086 J	700	8.0		5.1	18	14000
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	8200	0.39 J	7.7	43	0.37	0.090 J	2800	10		6.7	22	17000
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	8300	0.76 J	7.9	64	0.43	0.094 J	2500	11		6.6	63	16000
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	8600	< 0.23 U	7.4	87	0.37	0.074 J	1500	9.4		5.8	14	14000
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	6500	< 0.28 U	4.9	62	0.30 J	0.12 J	10000	9.3		5.2	16	13000
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	7200	3.0	6.7	92	0.47	0.17 J	3500	10		6.3	50	20000
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	6000	< 0.26 U	6.3	44	0.27 J	0.13 J	25000	7.8		5.1	20	13000
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	8200	0.56 J	8.1	87	0.41	0.29 J	6500	13		6.6	32	18000
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	7100	0.52 J	7.9	57	0.35 J	0.17 J	27000	10		6.3	23	16000
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	9400	0.37 J	6.6	73	0.38	0.26 J	9900	11		6.3	22	17000
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	7500	< 0.27 U	8.8	76	0.40	0.15 J	8900	10		6.5	34	18000
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	8300	0.67 J	6.8	99	0.35 J	0.21 J	2400	10		5.7	36	14000
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	4600	0.93 J	4.9	45	0.25 J	0.074 J	1700	6.4		3.5 J	80	9800
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	9100	1.7	6.9	90	0.41 J	0.096 J	3300	12		7.1	29	19000
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	7800	0.35 J	5.1	41	0.30 J	0.11 J	12000	9.9		6.2	23	16000
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	6700	< 0.25 U	6.6	42	0.29 J	0.077 J	14000	8.3		5.6	17	13000
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	7000	< 0.32 U	5.3	39	0.29 J	0.083 J	17000	8.9		5.3	18	14000
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	7000	0.30 J	11	110	0.40	0.20 J	4100	11		5.9	73	17000
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	5300	0.59 J	40	150	0.64	0.096 J	3100	11		5.6	33	20000
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	5700	< 0.27 U	5.2	25	0.24 J	0.072 J	600	6.7		5.0	37	12000
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	7300	0.41 JT	6.8 T	230 T	0.44	0.15 JT	1600 T	9.4 T		5.4	26 T	16000
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	6700	0.40 J	4.3	62	0.25 J	0.076 J	790	6.8		3.9 J	13	11000
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	5600	< 0.28 U	5.1	40	0.23 J	< 0.067 U	540	6.8		4.1 J	16	12000
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	6300 T	0.46 JBT	4.9 T	35 T	0.26 JT	< 0.074 UT	1400 T	7.1 T		4.0 JT	14 T	11000 T
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	6700	1.9 BJ	7.1	50 J	< 0.50 U	< 0.33 U	800 J	8.4		4.6	25	14000
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	6900	0.39 BJ	5.5	43	0.27 J	< 0.077 U	1100	7.8		4.5 J	16	12000
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	7000	0.55 J	5.5	49	0.30 J	0.080 J	10000	7.6		5.1 J	20	14000
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	6800	< 0.31 U	5.5	52	0.28 J	0.084 J	900	8.5		5.6	30	14000
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	7400	< 0.32 U	8.7	82	0.35 J	0.23 J	35000	12		6.6	30	16000
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	7800	< 0.30 U	5.7	53	0.33 J	0.079 J	850	11		4.8 J	18	14000
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	7300	3.1	8.2	85	0.33 J	0.25 J	39000	13		6.5	36	17000
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	5600	< 0.27 U	4.5	39	0.25 J	0.093 J	18000	6.9		4.0 J	16	12000
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	5700	0.34 J	6.5	41	0.28 J	0.095 J	3500	7.4		4.7	18	14000
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	7200	< 0.25 U	7.4	39	0.34	0.10 J	930	8.9		6.9	22	16000
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	7900	< 0.27 U	9.7	74	0.44	0.13 J	2600	9.9		7.2	26	18000
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	5500	< 0.32 U	5.3	48	0.26 J	0.11 J	7200	6.8		4.1 J	16	12000
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	6200	< 0.30 U	5.5	25	0.30 J	0.073 J	660	7.5		5.0	16	14000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	40	2600	370	1.6	18	630	< 0.45 U	0.16 J	< 50 U		< 0.28 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	66	2100	210	0.17	21	480	0.65 J	< 0.089 U	97 J		< 0.24 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	32	7700	270	0.051	16	570	< 0.47 U	16	81 J		< 0.29 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	31	3200	330	0.21	16	640	< 0.48 U	< 0.11 U	59 J		< 0.30 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	32	4100	340	0.15	16	600	< 0.45 U	< 0.10 U	52 J		< 0.28 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	19	3100	310	0.31	15	440 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	39	1600	480	0.058	11	490 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	37	1500	270	0.074	14	470 J	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	13	1700	360	0.037	11	470	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.35	2 - 4 ft	2.13 ft	1801378342	Not Excavated	43	650	87	0.11	15	520	1.7	< 0.10 U	110 J		< 0.28 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	32	1600	380	0.078	26	400 J	0.51 J	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	47	3400	250	0.26	14	1900	< 0.41 U	< 0.094 U	1700		< 0.26 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	60	1400	240	0.13	14	780	0.51 J	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	28	1700	460	0.090	12	490	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	6.0	5100	260	< 0.019 U	12	470	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	8.2	23000	630	< 0.019 U	13	560	0.49 J	< 0.090 U	84 J		< 0.25 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	7.1	4200	310	< 0.021 U	14	530	< 0.48 U	< 0.11 U	54 J		< 0.30 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	7.4	2500	370	< 0.020 U	15	710	< 0.52 U	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	5.1	590	210	< 0.018 U	5.2	300 J	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	8.1	2200	260	0.022 J	16	770	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	8.8	4200	320	0.020 J	13	610	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	6.7	1900	350	0.023 J	14	460 T	< 0.39 UT	< 0.089 UT	< 44 U		< 0.24 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	9.2	1500	320	0.023 J	12	340	< 0.30 U	< 0.067 U	< 33 U		< 0.18 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	37	2100	310	1.4	50	570	< 0.46 U	< 0.10 U	54 J		< 0.28 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	78	2300	340	1.6	15	640	0.55 J	< 0.11 U	78 J		< 0.30 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	33	3100	400	0.069	13	600	< 0.39 U	< 0.088 U	43 J		< 0.24 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	370	690	190	0.13	5.2	270 J	< 0.53 U	< 0.12 U	< 59 U		< 0.32 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	45	1300	220	0.092	8.6	710	< 0.49 U	< 0.11 U	59 J		< 0.30 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	8.7 T	1800	560	0.037	12	500 T	0.57 JT	< 0.10 UT	< 50 UT		< 0.28 UT
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	25	1700	280	0.075	11	470 J	< 0.45 U	< 0.10 U	65 J		< 0.27 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	6.1	1200	110	0.11	4.9	240 J	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	8.9 T	1300 T	290	0.022 J	9.0 T	410 JT	< 0.44 UT	< 0.099 UT	< 49 UT		< 0.27 UT
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	8.8	1600	420	0.021 J	13	480	0.45 J	< 0.10 U	< 50 U		< 0.27 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	11	2700	400	0.020 J	15	530	< 0.35 U	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	9.7	2700	380	< 0.019 U	15	670	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	3.0	640	95	0.040	3.1 J	140 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	5.5 T	1800 T	250	< 0.021 U	12	550 T	< 0.43 UT	< 0.098 UT	< 48 UT		< 0.27 UT
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	9.1	1700	270	0.027 J	12	520	0.51 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	28	2000	430	0.16	15	720	0.45 J	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	85	1900	360	0.19	14	610	0.55 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	27	1700	690	0.071	12	550	< 0.35 U	< 0.079 U	46 J		< 0.22 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	13	3800	400	0.044	13	670	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	49	1400	580	0.11	21	700	0.87 J	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	12	6600	400	0.025 J	13	740	0.52 J	< 0.090 U	47 J		< 0.24 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	37	2600	530	0.13	18	730	0.66 J	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	17	4600	400	0.049	17	760	0.70 J	< 0.10 U	52 J		< 0.28 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	28	4200	410	0.12	16	770	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	37	2300	390	2.0	120	690	< 0.41 U	0.37 J	52 J		< 0.25 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	110	1500	480	0.26	12	610	0.90 J	< 0.11 U	75 J		< 0.29 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	90	980	370	0.52	9.1	480 J	0.66 J	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	32	2400	330	0.083	26	890	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	6.3	3600	330	< 0.020 U	16	1100	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	7.5	4900	310	< 0.022 U	15	930	< 0.38 U	< 0.086 U	46 J		< 0.23 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	6.0	4100	260	< 0.021 U	14	1100	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	76	1700	450	0.13	22	520	0.53 J	< 0.10 U	51 J		< 0.28 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	38	1300	150	0.11	17	390 J	1.5	< 0.095 U	< 47 U		0.42 J
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	9.1	1500	330	0.034	12	410 J	< 0.41 U	< 0.092 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	31 T	1500 T	440 T	0.18	21	460 JT	0.47 JT	< 0.10 UT	< 51 U		< 0.28 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	20	1300	390	0.040	13	350 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	7.7	1400	300	0.033	11	420 J	< 0.42 U	< 0.094 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	6.4 T	1600 T	160 T	0.025 J	10 T	470 JT	< 0.47 UT	< 0.10 UT	< 52 UT		< 0.29 UT
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	28	1500 J	420	0.18	12	560 J	< 2.1 U	< 0.47 U	< 230 U		< 0.26 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	9.0	1600	290	0.032	12	560	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	10	2900	370	0.030	13	570	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	9.5	1900	410	0.042	14	670	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	89	3900	280	0.19	17	560	0.67 J	< 0.11 U	62 J		< 0.30 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	31	1700	320	0.20	12	490	0.46 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	110	4500	300	0.28	17	540 J	0.73 J	< 0.11 U	61 J		< 0.31 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	53	5200	280	0.16	12	550	< 0.41 U	< 0.093 U	50 J		< 0.25 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	20	1800	300	0.11	14	490	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	11	1900	360	0.11	16	580	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	23	2000	710	0.034	17	570	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	16	2500	280	0.85	11	540	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	7.2	1700	250	< 0.020 U	13	620	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated		11	61
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated		16	57
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated		14	68
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated		12	63
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated		11	64
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated		11	48
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated		10	51
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated		10	52
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated		9.3	42
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated		14	51
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated		10	75
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated		13	64
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated		11	69
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated		13	50
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated		8.2	69
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated		8.9	51
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated		10	74
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated		13	41
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated		3.3 J	18
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated		12	52
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated		9.8	140
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated		9.3	45
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated		8.0	42
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated		11	63
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated		11	78
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated		9.7	210
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated		6.4	26
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated		7.9	27
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated		13 T	40
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated		11	46
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated		3.8 J	17
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated		8.0 T	33 T
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated		9.5	44
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated		10	55
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated		13	46
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated		3.1 J	14
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated		7.7 T	38 T
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated		10	42
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated		14	58
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated		14	59
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated		12	48
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated		11	51
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated		17	65
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated		11	48
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated		14	200
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated		12	65
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated		15	73
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated		14	71
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated		14	120
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated		9.0	51
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated		13	70
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated		13	44
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated		11	43
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated		13	38
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated		12	77
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated		15	58
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated		7.9	36
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated		13 T	70
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated		9.5	40
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated		8.3	55
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated		11 T	38 T
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated		12 J	48
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated		11	41
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated		11	43
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated		11	47
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated		13	160
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated		14	53
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated		11	130
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated		9.2	46
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated		9.3	57 B
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated		11	49
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated		14	54
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated		8.3	60
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated		10	53

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	5900	< 0.34 UT	7.5	59 T	0.41 JT	0.15 JT	8500 T	7.8 T		8.9	23 T	13000
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	6200	< 0.24 U	3.6	41	0.25 J	0.071 J	970	6.3		4.4	18	12000
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	6600	< 0.26 U	5.3	28	0.30 J	< 0.063 U	610	7.7		5.4	15	13000
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	8600	< 0.25 U	8.6	54	0.42	0.091 J	910	8.8		6.4	20	16000
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	5800	< 0.27 U	5.4	43	0.25 J	0.094 J	660	7.7		4.8	120	13000
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	6200	< 0.29 U	4.8	40	0.29 J	0.11 J	16000	7.8		5.2	17	14000
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	7300	< 0.27 U	5.7	53	0.30 J	0.14 J	26000	9.8		6.0	19	15000
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	7700	< 0.29 UT	5.8	61	0.33 JT	0.13 JT	25000	9.3 T		5.5	20	14000
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	9000	< 0.29 U	7.9	75	0.39	0.12 J	15000	9.7		6.8	16	17000
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	7500	< 0.31 U	7.9	84	0.35 J	0.22 J	1700	9.1		5.1	22	13000
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	6000	0.40 J	7.6	43	0.26 J	0.13 J	14000	8.0		6.7	20	16000
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	7200	< 0.31 U	7.2	66	0.33 J	0.14 J	5300	9.2		6.0	21	16000
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	6600	< 0.25 U	5.6	53	0.27 J	0.11 J	8300	8.3		4.9	18	13000
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	5500	0.74 J	34	110	0.45	0.55	3400	11		6.1	36	21000
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	7100	2.4	8.2	98	0.36 J	0.36 J	3300	10		5.6	32	15000
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	7900	0.36 J	7.4	97	0.38 J	0.24 J	2000	9.6		4.8 J	21	13000
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	7400	0.32 J	7.5	84	0.37 J	0.18 J	4500	11		6.3	31	16000
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	5400	0.39 J	10	210	0.39	0.12 J	5000	11		5.3	40	20000
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	8100	0.46 J	7.7	84	0.40 J	0.18 J	11000	12		6.4	32	20000
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	8400	< 0.29 U	6.0	32	0.35 J	0.088 J	810	9.5		6.5	16	17000
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	8400	< 0.31 U	4.6	45	0.30 J	< 0.075 U	2500	9.2		4.5 J	15	15000
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	7000	< 0.28 U	5.2	26	0.27 J	0.076 J	660	7.9		5.5	15	14000
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	6500	< 0.26 U	5.8	39	0.31 J	0.11 J	750	7.5		5.0	17	14000
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	6300	< 0.28 U	5.6	49	0.32 J	0.17 J	3500	7.5		5.4	19	21000
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	7900	< 0.32 U	4.5	36	0.33 J	0.090 J	1700	8.8		4.9 J	15	14000
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	7000	< 0.34 U	5.4	48	0.31 J	0.12 J	10000	8.2		5.2 J	24	15000
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	5400	< 0.31 U	4.9	31	0.22 J	0.12 J	6300	6.0		4.3 J	17	11000
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	7600	0.33 J	5.7	25	0.32 J	4.2	1100	9.3		5.3	20	16000
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	7100	< 0.28 U	4.8	40	0.30 J	0.12 J	18000	7.8		4.6	16	13000
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	6200	< 0.30 U	6.0	30	0.27 J	0.11 J	600	7.7		5.8	15	14000
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	7600	< 0.24 U	4.4	67	0.30 J	0.082 J	41000	11		6.0	24	14000
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	5800	< 0.24 U	3.7	60	0.19 J	0.091 J	68000	12		6.1	18	12000
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	3600	< 0.28 U	3.4	30	0.16 J	0.20 BJ	4900	6.5		3.4 J	16	11000
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	3500	< 0.23 U	3.0	21	0.14 J	< 0.055 U	15000	5.6		2.9 J	10	8900
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	4900	1.0 J	11	120	0.37 J	0.12 J	6400	8.2		5.5	73	18000
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	5600	< 0.31 U	5.6	55	0.27 J	0.18 J	1200	9.3		5.3	30	16000
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	7900	0.61 J	10	79	0.44	0.14 J	2200	11		7.3	37	19000
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	13000	1.1 J	9.1	130	0.64	0.19 J	20000	26		10	39	25000
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	7300	< 0.33 U	6.3	43	0.32 J	0.11 J	7100	11		7.1	28	17000
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	7100	< 0.34 U	6.5	41	0.30 J	0.10 J	12000	11		7.1	21	16000
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	7400	< 0.34 U	5.9	43	0.33 J	0.063 J	930	9.3		7.7	20	17000
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	9800	< 0.38 U	7.3	59	0.44 J	0.076 J	1900	13		8.1	26	20000
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	5400	< 0.28 U	4.5	28	0.26 J	0.085 J	1300	7.1		5.1	16	13000
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	7500	< 0.31 U	7.1	42	0.37 J	0.078 J	3900	10		7.6	23	19000
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	12000	< 0.38 U	5.9	53	0.47 J	< 0.051 U	740	12		6.6	17	19000
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	10000	< 0.42 U	6.9	75	0.49 J	0.12 J	1700	17		8.6	19	23000
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	7500	< 0.31 U	6.0	50	0.35 J	0.066 J	4200	12		6.8	19	17000
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	9100	< 0.30 U	8.1	58	0.41	0.045 J	2500	11		8.7	19	20000
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	5800	< 0.33 U	5.0	46	0.26 J	0.097 J	11000	7.5		5.4	23	13000
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	12000	< 0.42 U	7.6	96	0.54 J	0.16 J	2200	20		11	16	22000 B
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	7800	< 0.34 U	5.7	86	0.36 J	0.079 J	930	10		8.4	18	15000 B
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	11000	0.41 J	4.9	53	0.42 J	< 0.049 U	950	11		5.7	9.5	15000 B
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	9400	< 0.43 U	6.5	100	0.46 J	0.17 J	4500	22		8.2	34	18000 B
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	8400	< 0.31 U	6.4	54	0.37 J	0.085 J	1200	12		7.6	18	17000 B
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	7300	< 0.31 U	5.1	25	0.28 J	0.060 J	590	9.3		5.7	17	14000 B
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	7300	< 0.35 U	5.9	120	0.46 J	0.078 J	6600	9.1		6.0	20	16000 B
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	6900	< 0.34 U	5.4	28	0.27 J	< 0.045 U	1100	8.7		4.7	19	13000 B
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	5700	< 0.28 UT	4.2	39	0.27 JT	0.063 J	670	7.5		5.6	15	12000 B
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	10000	0.43 J	6.5	92	0.40 J	0.060 J	740	13		10	21	19000 B
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	12000	< 0.33 U	7.8	30	0.49	< 0.044 U	320 J	13		11	20	21000
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	8000	< 0.39 U	9.8	360	0.45 J	0.15 J	7800	15		9.1	57	19000
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	9300	< 0.36 U	6.1	110	0.39 J	0.20 J	6900	11		6.6	31	17000
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	3500	< 0.36 U	7.9	96	0.47 J	< 0.048 U	1700	9.0		3.7	46	32000
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	8600	< 0.39 U	6.3	86	0.44 J	0.26 J	1200	10		4.3	29	15000
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	9400	< 0.37 U	6.7	91	0.43 J	0.064 J	2100	13		8.1	46	18000
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	11000	0.44 J	4.6	110	0.42 J	< 0.051 U	1900	11		6.7	17	16000
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	12000	< 0.38 U	4.1	76	0.40 J	< 0.051 U	1200	13		6.0	11	16000
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	7500	< 0.28 U	6.0	28	0.30 J	0.038 J	490	9.1		6.6	20	16000
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	8400	< 0.35 UT	6.7	38	0.36 J	< 0.047 U	700	9.6		7.2	18	17000
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	6400	< 0.34 U	5.0	35	0.28 J	< 0.046 U	470 J	7.9		5.8	18	15000
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	11000	< 0.35 U	7.6	28	0.47 J	< 0.047 U	310 J	12		8.2	18	20000
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	7800	< 0.35 U	5.3	40	0.34 J	0.055 J	740	10		6.9	23	17000
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	7200	< 0.33 U	6.0	51	0.34 J	0.072 J	880	8.3		6.4	18	16000
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	7200	< 0.31 U	6.3	58	0.34 J	0.064 J	1000	8.7		6.6	18	16000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	95 T	1700 T	310	0.56 T	16	720 T	1.1 T	< 0.12 UT	< 57 U		< 0.32 UT
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	5.4	1800	290	< 0.022 U	11	360 J	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	6.5	1800	220	< 0.020 U	14	490	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	9.6	1800	300	< 0.021 U	17	750	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	15	1500	290	< 0.022 U	16	460	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	7.8	3600	340	< 0.019 U	14	640	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	15	4900	620	0.026 J	15	580	< 0.41 U	< 0.092 U	62 J		< 0.25 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	26 T	3600 T	320	0.072 T	14	600 T	< 0.43 UT	< 0.098 UT	60 J		< 0.27 UT
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	16	3000	420	< 0.023 U	16	670	< 0.44 U	< 0.10 U	78 J		< 0.27 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	58	1600	430	0.10	12	620	0.59 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	9.9	3600	400	< 0.018 U	16	590	< 0.42 U	< 0.096 U	56 J		< 0.26 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	11	3400	390	< 0.019 U	15	820	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	20	2600	370	< 0.021 U	13	680	< 0.38 U	< 0.085 U	100 J		< 0.23 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	79	1500	240	0.11	16	710	2.6	< 0.11 U	57 J		< 0.31 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	140	1900	400	0.15	17	800	< 0.47 U	< 0.10 U	54 J		< 0.29 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	69	1500	450	0.12	12	590	0.92 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	41	2300	340	0.074	17	720	0.57 J	< 0.10 U	52 J		< 0.28 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	43	1400	220	0.10	15	620	0.77 J	< 0.093 U	57 J		< 0.25 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	58	2900	290	0.056	17	720	< 0.47 U	< 0.11 U	53 J		< 0.29 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	9.3	2200	440	< 0.019 U	13	730	< 0.43 U	< 0.098 U	64 J		< 0.27 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	13	2400	200	< 0.019 U	13	420 J	< 0.47 U	< 0.11 U	72 J		< 0.29 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	11	1800	420	0.028 J	11	550	< 0.43 U	< 0.098 U	61 J		< 0.27 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	10	1800	360	< 0.020 U	12	530	< 0.40 U	< 0.090 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	12	2500	590	0.040	14	730	< 0.42 U	< 0.095 U	63 J		< 0.26 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	13	2100	210	0.11	13	570	< 0.48 U	< 0.11 U	72 J		< 0.30 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	18	3700	310	0.037	15	690	< 0.51 U	< 0.12 U	87 J		< 0.32 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	11	1900	320	0.16	10	560	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	36	2100	250	0.045	14	570	< 0.43 U	< 0.097 U	61 J		< 0.26 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	15	4700	290	0.056	12	540	< 0.42 U	< 0.095 U	72 J		< 0.26 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	7.3	1700	320	< 0.020 U	12	550	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	15	9900	490	0.021 J	16	730	0.60 J	< 0.082 U	81 J		< 0.22 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	9.0	14000	430	< 0.022 U	15	570	0.85	< 0.081 U	77 J		< 0.22 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	43	2900	190 B	0.38	8.4	320 J	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	11	5500	200 B	0.16	7.5	440	< 0.34 U	< 0.078 U	< 38 U		0.26 J
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	370	2700	260	0.091	30	510 J	0.83 J	< 0.11 U	82 J		0.43 J
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	34	1300	250	0.12	15	470 J	0.61 J	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	110	2100	360	0.14	19	690	0.78 J	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	53	10000	600	0.14	42	1800	< 0.68 U	< 0.15 U	89 BJ		< 0.42 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	13	3400	380	< 0.022 U	20	610	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	12	4900	370	< 0.017 U	19	610	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	7.6	2000	700	0.024 J	16	530	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	14	2700	590	0.034 J	20	610	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	6.1	1900	320	< 0.022 U	14	510	< 0.36 U	< 0.062 U	< 48 U		< 0.31 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	17	3000	490	< 0.019 U	19	710	< 0.41 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	8.3	2600	310	0.028 J	18	520 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	15	2800	580	0.029 J	21	780	< 0.54 U	< 0.094 U	< 73 U		< 0.46 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	9.5	2800	420	0.023 J	18	670	< 0.40 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	11	2800	400	< 0.021 U	21	820	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	46	3000	390	0.41	14	540	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	14	3000	600	0.054 J	23	900	< 0.55 U	< 0.095 U	< 73 U		< 0.47 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	9.8	2000	460	0.031 J	17	530	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	8.5	1800	140	0.046 J	13	610	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	70	2600	420	0.098 J	32	950	< 0.56 U	< 0.096 U	< 75 U		< 0.47 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	12	2100	510	0.041 J	17	490	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	6.9	2000	220	0.028 J	14	400 J	< 0.41 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	16	1500	320	0.053 J	16	440 J	0.54 J	< 0.080 U	70 J		< 0.39 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	6.1	1900	220	0.028 J	13	410 J	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	5.7 T	1600	320	0.022 J	14	410	< 0.37 U	< 0.064 U	< 49 UT		< 0.31 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	9.2	2800	520	0.033 J	22	560	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	12	2600	420	0.042 J	18	500	< 0.43 U	< 0.074 U	< 57 U		< 0.37 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	44	2500	480	0.12	25	600	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	59	2200	500	0.39	17	490 J	< 0.48 U	< 0.082 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	31	630	260	0.064 J	11	510	0.87 J	0.087 J	73 J		< 0.40 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	63	1600	130	0.17	14	530 J	0.75 J	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	20	2200	340	0.069 J	23	710	< 0.48 U	< 0.083 U	160 J		< 0.41 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	17	2200	760	0.051 J	15	590	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	9.1	2300	240	0.041 J	15	510 J	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	6.4	2100	260	0.029 J	18	430	< 0.37 U	< 0.064 U	< 50 U		< 0.32 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	7.4	2200	280 T	0.025 J	17	590	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	6.1	1900	300	0.025 J	14	460 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	9.6	2400	210	0.040 J	16	530	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	9.3	2200	550	0.033 J	16	590	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	8.3	1900	520	0.026 J	17	530	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	7.7	2100	370	0.022 J	18	460	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated		10 T	91 T
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated		8.4	33
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated		9.3	36
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated		12	69
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated		9.1	52
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated		8.9	54
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated		11	53
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated		11 T	52 T
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated		12	48
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated		13	120
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated		10	50
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated		13	61
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated		11	56
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated		14	210
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated		13	220
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated		13	130
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated		12	110
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated		14	46
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated		15	80
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated		12	51
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated		12	50
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated		10	60
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated		10	48
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated		11	69
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated		11	45
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated		11	51
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated		8.4	55
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated		11	710
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated		10	42
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated		11	41
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated		12	51
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated		8.8	53
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated		5.9	75
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated		7.1	31
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated		11	150
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated		11	84
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated		13	95
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated		22	110
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated		12	63
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated		11	55
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated		11	51
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated		15	63
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated		8.8	58
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated		13	62
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated		17	59
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated		16	79
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated		13	65
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated		15	64
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated		9.4	69
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated		15	66
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated		13	64
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated		16	38
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated		14	89
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated		12	55
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated		11	55
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated		13	41
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated		10	42
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated		8.9	53 T
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated		15	92
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated		17	63
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated		14	150
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated		14	96
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated		14	32
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated		14	82
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated		14	95
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated		16	59
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated		17	46
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated		11	55
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated		13	52
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated		9.7	50
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated		17	52
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated		13	75
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated		12	63
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated		12	70

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	7200	< 0.36 U	10	61	0.38 J	0.13 J	1100	8.7		7.5	22	19000
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	6500	< 0.38 U	6.1	50	0.31 J	< 0.051 U	780	7.9		6.3	17	15000
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	7500	< 0.37 U	5.8	46	0.33 J	< 0.049 U	670	8.5		6.1	18	15000
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	6900	< 0.36 U	4.0	43	0.28 J	< 0.049 U	560	8.0		5.5	17	15000
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	6000	< 0.30 U	8.5	39	0.28 J	0.056 J	540	7.2		6.5	18	14000
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	7700	< 0.28 U	5.6	57	0.34 J	0.083 J	1200	9.1		6.8	17	15000
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	9600	< 0.31 U	9.0	79	0.41 J	0.046 J	2700	11		8.9	19	22000
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	8500	0.36 J	9.8	48	0.31 J	0.052 J	3800	9.6		7.2	18	18000
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	8000	< 0.27 U	5.3	49	0.31 J	0.064 J	1200	8.5		5.4	16	14000
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	9900	< 0.35 U	9.0	75	0.44 J	0.063 J	3700	13		9.7	17	24000
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	10000	< 0.35 U	7.7	89	0.43 J	0.087 J	4600	12		9.2	20	22000
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	7500	< 0.37 U	6.4	41	0.30 J	0.060 J	1200	8.4		6.3	22	16000
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	7000	< 0.30 U	5.9	48	0.29 J	0.049 J	1200	8.7		6.5	19	16000
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	7000	< 0.32 U	4.8	42	0.29 J	0.059 J	690	8.2		6.5	18	15000
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	7800	< 0.34 U	5.9	35	0.31 J	< 0.046 U	840	8.9		6.3	16	15000
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	7000	< 0.37 U	4.7	52	0.28 J	0.051 J	930	8.6		6.3	62	16000
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	8300	< 0.39 U	7.1	53	0.37 J	< 0.052 U	860	9.6		7.5	20	18000
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	7600	0.44 J	5.7	56	0.30 J	0.056 J	1500	9.1		6.7	21	15000
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	6500	< 0.28 U	4.0	35	0.26 J	0.058 J	780	8.0		6.2	16	15000
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	7000	< 0.35 U	5.6	36	0.29 J	0.063 J	740	8.2		6.3	19	16000
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	6900	< 0.33 U	4.6	37	0.29 J	< 0.044 U	630	8.2		6.1	15	15000
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	9600	< 0.36 U	6.5	99	0.40 J	0.23 J	4100	11		7.0	26	17000
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	7000	< 0.28 U	7.0	130	0.38 J	0.92	2800	11		6.3	26	15000
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	7400	< 0.38 U	6.6	97	0.39 J	0.18 J	2700	9.6		6.3	21	16000
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	6000	< 0.37 U	7.6	83	0.34 J	0.17 J	4900	8.7		4.7	26	17000
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	8600	< 0.34 U	12	98	0.50	0.082 J	3300	12		5.9	21	18000
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	11000	< 0.33 U	6.3	120	0.47	0.051 J	14000	11		4.5	11	18000
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	6500	< 0.35 U	4.8	40	0.27 J	0.050 J	690	8.1		5.6	15	14000
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	7100	< 0.36 U	5.5	53	0.31 J	0.068 J	980	8.4		6.3	19	16000
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	8600	< 0.34 U	9.4	100	0.45 J	0.19 J	4800	11		6.6	23	17000
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	6000	7.4	25	87	0.32 J	0.22 J	3900	8.2		7.1	25	40000
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	6400	< 0.28 U	4.4	31	0.26 J	< 0.038 U	500	7.6		5.5	15	14000
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	7800	< 0.55 U	7.2	65	0.36 J	< 0.074 U	840	9.2		7.9	23	16000
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	8900	< 0.38 U	7.9	80	0.39 J	0.11 J	2000	11		6.4	22	15000
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	9200	< 0.33 U	8.5	63	0.47 J	0.16 J	850 J	11		8.7	26	20000
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	9500	< 0.36 U	17	59	0.46 J	0.075 J	990 J	10		8.2	27	22000
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	9100	< 0.30 U	7.6	55	0.43	0.17 J	1000	11		7.5	20	18000
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	6500	< 0.30 U	5.6	170	0.42	0.069 J	2100	9.5		5.1	22	14000
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	8300	< 0.31 U	10	78	0.35 J	< 0.042 U	4800	11		9.1	24	20000
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	8600	< 0.27 U	5.6	70	0.40 J	0.055 J	2300	9.8		7.4	18	18000
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	8200	< 0.35 U	7.3	62	0.36 J	< 0.046 U	1800	10		8.1	21	18000
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	8300	0.36 J	6.4	74	0.38 J	0.090 J	1200	10		7.1	19	16000
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	7800	< 0.29 U	5.2	64	0.35 J	0.072 J	910	9.5		7.4	16	15000
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	8400	< 0.34 U	7.6	80	0.42 J	0.12 J	1800	11		6.5	21	15000
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	7600	< 0.36 U	5.6	47	0.32 J	0.086 J	1400	9.4		6.3	22	17000
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	8700	< 0.35 U	10	120	0.58	0.62	6000	13		6.1	40	19000
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	6900	< 0.31 U	5.7	50	0.30 J	0.096 J	2400	8.4		6.6	17	15000
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	8000	< 0.36 U	6.4	66	0.37 J	0.11 J	2500	10		7.0	18	18000
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	8100	< 0.26 U	4.8	51	0.32 J	0.071 J	900	9.2		6.8	19	16000
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	7200	< 0.32 U	6.7	64	0.36 J	0.10 J	1200	8.9		6.2	21	16000
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	7700	0.37 J	6.1	57	0.35 J	0.098 J	1400	9.4		6.9	18	16000
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	5400	< 0.28 U	3.9	35	0.25 J	0.037 J	390	6.8		5.5	14	12000
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	7900	< 0.36 U	5.4	56	0.36 J	0.093 J	2300	9.6		6.4	16	15000
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	7300	< 0.38 U	4.9	31	0.31 J	< 0.050 U	480 J	8.6		5.4	16	14000
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	8200	< 0.31 U	5.9	48	0.33 J	< 0.042 U	430	8.7		6.0	17	14000
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	8500	< 0.35 U	4.5	120	0.37 J	0.047 J	650	8.6		3.6	12	10000
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	8700	< 0.32 U	5.9	72	0.38 J	0.096 J	1900	10		7.2	16	17000
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	8100	< 0.40 U	5.1	30	0.37 J	< 0.053 U	750	9.0		6.0	17	16000
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	7900	0.36 J	2.6	82	0.28 J	< 0.044 U	530	8.0		4.2	7.0	12000
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	6200	< 0.34 U	5.8	42	0.27 J	< 0.045 U	670	7.8		5.8	18	14000
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	7400	< 0.38 U	4.7	59	0.32 J	0.060 J	910	8.7		5.5	13	14000
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	7200	< 0.38 U	7.9	49	0.37 J	0.075 J	460 J	8.6		6.8	17	17000
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	4800	< 0.37 U	2.5	91	0.19 J	0.082 J	1800	4.7		3.0	7.2	7400
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	9400	< 0.34 U	5.7	65	0.35 J	0.050 J	1400	11		6.6	15	17000
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	8000	< 0.31 U	5.7	35	0.34 J	< 0.042 U	390 J	8.6		5.7	14	15000
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	8900	< 0.30 U	7.2	72	0.37 J	< 0.041 U	1400	10		7.1	14	17000
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	10000	0.37 J	7.6	58	0.41	< 0.038 U	2100	11		8.6	15	19000
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	9300	< 0.33 U	6.3	81	0.39 J	0.073 J	1400	10		5.3	16	16000
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	7700	< 0.38 U	6.3	69	0.34 J	0.10 J	1600	9.7		5.5	19	15000
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	9200	< 0.34 U	9.2	120	0.40 J	0.047 J	600	10		4.9	27	14000
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	8200	< 0.32 U	7.2	220	0.35 J	0.080 J	380 J	9.1		5.4	22	12000
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	7500	< 0.39 U	9.4	120	0.40 J	0.090 J	660	9.7		7.4	26	12000
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	7700	0.46 J	8.2	150	0.35 J	0.083 J	900	7.7		3.7	14	12000
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	7300	< 0.32 U	5.8	120	0.37 J	0.12 J	2100	8.9		5.7	19	13000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	17	1900	660	0.027 J	22	560	< 0.47 U	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	8.9	1800	420	0.026 J	15	500 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	7.5	1800	350	0.024 J	16	560	< 0.48 U	< 0.083 U	< 65 U		< 0.41 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	6.3	2000	250	< 0.018 U	15	450 J	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	9.1	1600	400	0.031 J	16	420	< 0.39 U	< 0.068 U	< 53 U		< 0.33 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	17	2100	410	0.037 J	16	560	< 0.36 U	< 0.063 U	< 48 U		< 0.31 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	15	2900	480	0.023 J	20	780	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	9.5	2400	340	0.031 J	16	570	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	13	2000	330	0.055 J	13	390	0.49 J	< 0.060 U	< 47 U		< 0.30 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	14	3300	470	0.018 J	22	910	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	17	3300	500	0.035 J	21	920	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	13	2000	370	0.038 J	15	440 J	< 0.48 U	< 0.083 U	< 65 U		< 0.41 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	10	2000	350	0.026 J	17	530	< 0.40 U	< 0.068 U	< 53 U		< 0.34 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	9.9	1900	420	0.028 J	16	430 J	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	10	2000	310	0.033 J	14	470 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	8.0	2100	380	0.023 J	14	470 J	< 0.48 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	10	2100	490	0.029 J	18	670	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	11	2000	430	0.040 J	16	520	0.52 J	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	6.6	2100	350	< 0.018 U	16	460	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	7.3	1900	430	0.022 J	16	490	< 0.46 U	< 0.079 U	< 62 U		< 0.39 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	9.4	1900	360	0.022 J	16	540	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	39	2100	400	0.089 J	37	620	< 0.47 U	< 0.081 U	98 J		< 0.40 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	110	1500	320	0.18	20	590	0.77 J	0.088 J	65 J		< 0.31 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	25	1800	340	0.13	49	570	0.50 J	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	21	1100	210	0.084 J	69	410 J	< 0.48 U	< 0.083 U	110 J		< 0.41 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	34	2000	200	0.16	51	620	0.74 J	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	6.6	1000	94	0.063 J	14	370 J	< 0.43 U	< 0.075 U	260 J		< 0.37 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	7.0	1800	290	0.037 J	14	480 J	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	7.0	1900	350	0.036 J	17	630	< 0.47 U	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	38	2100	380	0.080 J	21	570	0.44 J	< 0.076 U	63 J		< 0.37 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	89	820	260	0.092 J	23	240 J	0.90 J	< 0.077 U	94 J		< 0.38 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	6.5	1800	320	< 0.020 U	14	520	< 0.37 U	< 0.064 U	< 50 U		< 0.32 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	9.8	1700	680	0.027 J	18	630 J	< 0.72 U	< 0.13 U	< 97 U		< 0.31 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	43	1900	480	0.065 J	17	510 J	0.76 J	< 0.085 UT	< 66 U		< 0.42 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	40	2100	700	0.12	22	510 J	0.70 J	< 0.075 U	< 120 U		< 0.37 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	22	2300	560	0.059 J	21	650 J	0.61 J	< 0.081 U	< 130 U		< 0.40 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	28	2000	340	0.075 J	18	460	0.50 J	< 0.068 U	< 53 U		< 0.34 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	37	1300	500	0.050 J	13	470	0.78 J	0.072 JT	< 52 U		< 0.33 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	10	3700	400	< 0.022 U	22	810	< 0.41 U	< 0.070 UT	< 55 U		< 0.35 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	8.8	3000	400	0.024 J	19	640 J	0.42 J	< 0.061 UT	< 94 U		< 0.30 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	11	2300	390	< 0.018 U	21	680	< 0.45 U	< 0.078 UT	< 60 U		< 0.38 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	21	2000	450	0.049 J	18	580	< 0.41 U	< 0.071 UT	57 J		< 0.35 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	13	1900	420	0.027 J	16	480	< 0.38 U	< 0.066 UT	< 51 U		< 0.33 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	39	1900	450	0.067 J	19	550	0.74 J	< 0.077 UT	64 J		< 0.38 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	9.8	2500	350	0.034 J	18	540	0.51 J	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	130	2600	350	0.095 J	22	540	0.94 J	< 0.079 U	200 J		< 0.39 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	14	1800	460	0.052 J	16	590	0.55 J	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	19	2500	400	0.040 J	17	840	0.58 J	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	8.7	2100	320	0.030 J	17	420	0.58 J	< 0.059 U	< 46 U		< 0.29 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	8.6	1800	460	0.031 J	20	520	0.61 J	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	18	2200	380	0.051 J	17	650	0.68 J	< 0.066 U	< 51 U		< 0.33 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	6.6	1600	240	0.026 J	15	400	0.53 J	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	11	2200	370	0.033 J	16	570	0.71 J	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	6.4	1900	210	0.031 J	14	460 J	0.59 J	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	7.9	1900	390	0.038 J	15	360 J	< 0.41 U	< 0.070 U	< 54 U		< 0.35 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	17	1300	180	0.059 J	10	320 J	0.68 J	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	22	2400	460	0.056 J	17	480	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	8.3	2500	240	0.034 J	14	440 J	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	5.9	1400	260	0.035 J	10	270 J	< 0.43 U	< 0.074 U	85 J		< 0.37 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	7.9	1600	320	0.044 J	14	410 J	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	9.2	1800	410	0.038 J	13	460 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	12	1700	700	0.056 J	15	430 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	6.4	840	310	0.031 J	6.3	240 J	< 0.48 U	< 0.083 U	< 65 U		< 0.41 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	11	2500	370	0.049 J	17	510	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	18	1800	290	0.031 J	14	450	< 0.41 U	< 0.070 U	< 55 U		< 0.35 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	19	2200	400	0.044 J	16	590	< 0.40 U	< 0.069 U	< 53 U		< 0.34 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	11	2400	400	0.024 J	17	580	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	16	1800	440	0.060 J	14	430 J	0.50 J	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	21	1800	390	0.089 J	14	450 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	38	1500	460	0.097 J	11	400 J	1.4 J	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	28	1300	600	0.077 J	11	360 J	1.1 J	< 0.072 U	< 56 U		< 0.36 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	45	1300	410	0.13	10	400 J	2.2	< 0.087 U	90 J		< 0.43 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	26	1100	540	0.12 J	9.6	280 J	0.97 J	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	31	1500	950	0.079 J	13	410 J	1.1 J	0.14 J	< 56 U		< 0.36 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated		13	70
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated		11	50
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated		12	57
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated		10	49
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated		9.9	71
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated		12	68 T
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated		14	64
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated		11	54
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated		12	55
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated		14	68
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated		14	94
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated		11	65
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated		12	71
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated		11	64
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated		11	62
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated		11	52
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated		14	70
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated		11	60 T
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated		9.2	60 T
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated		11	59 T
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated		9.9	52
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated		12	80
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated		12	210
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated		12	56
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated		12	47
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated		15	55
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated		16	14
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated		11	51
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated		11	68
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated		14	65
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated		13	43
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated		9.3	53
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated		13	63
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated		15	71
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated		17	79
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated		16	72
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated		15	66
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated		13	46
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated		12	58
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated		13	64
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated		13	65
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated		13	66
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated		12	59
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated		14	73
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated		11	70
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated		18	250
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated		11	80
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated		12	85
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated		12	67
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated		12	81
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated		11	87
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated		8.1	47
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated		12	57
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated		11	49
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated		12	46
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated		13	49
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated		13	71
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated		14	52
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated		13	40
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated		10	51
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated		11	48
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated		13	50
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated		6.2	27
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated		13	55
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated		13	50
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated		13	55
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated		15	53
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated		15	61
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated		13	52
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated		16	51
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated		14	66
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated		15	45
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated		12	51
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated		12	59

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	9600	< 0.42 U	6.3	110	0.49 J	0.17 J	2500	20		9.1	16	19000
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	9100	< 0.40 UT	6.9	57	0.40 J	< 0.053 U	1700	11		7.6	15	20000
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	9700	< 0.42 U	6.3	110	0.49 J	0.14 J	2800	18		9.0	16	19000
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	10000	< 0.36 U	6.6	120	0.52	0.14 J	2000	14		10	14	19000
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	9600	< 0.47 U	8.0	110	0.41 J	0.22 J	14000	23		9.2	28	21000
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated								55	< 4.3 U			
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	9900	< 0.31 U	6.1	130	0.36 J	0.094 J	1800	12		6.6	22 B	18000
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	8800	< 0.39 UT	5.0	100	0.38 J	0.088 J	890	9.4		5.8	14 B	17000
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	9100	< 0.34 U	6.5	96	0.41 J	0.12 J	2300	10		6.7	17 B	16000
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	2500	0.61 J	11	110	0.34 J	0.080 J	1700	7.3		4.3	31 B	27000
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	8300	< 0.33 U	6.5	190	0.45 J	0.12 J	2500	12		7.6	19 B	17000
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	9500	< 0.30 U	5.6	140	0.36 J	0.099 J	8600	12		6.5	20 B	15000
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	8200	< 0.32 U	7.4	70	0.35 J	0.15 J	7600	9.1		7.3	20 B	17000
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	8500	0.29 J	7.9	24	0.48	0.071 J	170 J	9.7		7.5	21 B	20000
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	9700	< 0.41 U	13	96	0.56 J	0.24 J	1500	12		11	32	23000
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	8700	< 0.41 U	9.7	100	0.47 J	0.48 J	6700	16		7.5	77	24000
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	11000	< 0.32 U	6.8	41	0.44 J	0.060 J	1000	12		7.5	14	19000
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	9100	0.37 J	12	84	0.47 J	0.30 J	13000	14		7.5	34	19000
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	9900	0.43 J	7.8	72	0.45	0.16 J	6000	13		7.3	30	19000
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	10000	< 0.38 U	6.9	68	0.43 J	0.10 J	1600	11		5.9	18	17000
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	10000	0.54 J	6.6	39	0.43 J	0.049 J	1400	11		8.3	14	18000
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	9500	0.40 J	6.0	86	0.47 J	0.11 J	2600	12		8.6	24	18000
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	8400	< 0.33 U	8.8	95	0.44 J	0.18 J	2600	9.5		5.3	17	15000
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	9300	< 0.38 U	3.6	110	0.37 J	0.052 J	1500	8.9		5.6	8.3	12000
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	9400	0.35 J	3.8	110	0.34 J	< 0.046 U	1400	8.9		5.0	8.4	13000
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	7400	< 0.33 U	11	92	0.45 J	0.17 J	14000	11		8.3	22	17000
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	9900	< 0.37 U	9.9	100	0.46 J	0.15 J	3900	12		6.8	26	17000
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	10000	< 0.41 U	5.9	110	0.40 J	0.13 J	5200	11		6.4	14	15000
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	8300	< 0.36 U	6.4	40	0.37 J	0.11 J	380 J	9.7		6.5	17	17000
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	8600	< 0.35 UT	10	95	0.42 J	0.17 J	7800 T	11		7.5	24	20000
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	9000	< 0.36 U	7.7	71	0.40 J	0.23 J	6100	12		6.5	54	17000
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	9400	< 0.33 U	5.1	110	0.43 J	0.14 J	2200	10		6.1	14	16000
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	7900	< 0.33 U	6.7	48	0.40 J	0.070 J	1700	9.5		9.2	19	16000
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	9300	< 0.35 U	8.2	50	0.47 J	0.090 J	700	11		10	26	20000
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	8600	< 0.29 U	5.6	54	0.38 J	0.068 J	2100	10		6.7	15	17000
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	8200	< 0.29 U	4.8	99	0.36 J	0.043 J	1200	8.3		5.2	9.5	13000
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	11000	< 0.44 U	7.2	51	0.50 J	0.062 J	1400	12		8.5	20	20000
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	5400	< 0.24 U	4.7	29	0.21 J	0.071 J	410	6.5		5.1	14	11000
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	6700 B	< 0.19 U	6.1	54	0.29	0.11 J	1700	8.0		6.2	13	15000 B
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	4800 B	< 0.19 U	11	93	0.35	0.27 J	16000	6.9		3.5	34	11000 B
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	7400 B	< 0.17 U	3.3	59	0.26	0.053 J	390	7.4		3.3	8.1	11000 B
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	8000	< 0.30 UT	5.8 T	41 T	0.35 JT	< 0.074 UT	310 JT	8.4 T		6.0 T	13 T	15000
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	6600 B	< 0.16 U	4.3	73	0.35	0.12 J	1300	10		5.7	10	13000 B
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	6300	< 0.32 U	5.4	66	0.27 J	0.083 J	1100	7.4		5.2 J	10	14000
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	4500	< 0.22 U	3.4	24	0.16 J	< 0.054 U	310 J	5.2		3.4 J	9.4	8900
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	3900 B	< 0.17 U	3.6	21	0.16 J	0.063 J	380	4.7		3.4	11	9200 B
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	5200 B	< 0.20 U	4.0	34	0.23 J	0.075 J	410	5.7		4.1	11	12000 B
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	4800 B	< 0.18 U	3.6	22	0.20 J	0.067 J	380	5.4		4.0	13	11000 B
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	3100	< 0.20 U	2.8	47	0.18 J	0.079 J	3300	4.3		2.2 J	17	6100 B
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	5100	< 0.28 U	6.4	30	0.20 J	< 0.067 U	630	6.9		4.9	15	12000
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	3200	0.32 J	9.7	110	0.35 J	0.32 J	3000	8.8		4.1 J	57	15000 B
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	2600	< 0.32 U	8.0	84	0.34 J	< 0.077 U	1200	4.8		3.2 J	37	19000 B
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	7200	0.37 J	6.0	89	0.35	0.26 J	2400	11		5.3	29	16000 B
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	5800	< 0.16 U	8.3	81	0.37	0.11 J	1500	7.4		6.2	32	17000 B
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	5700	< 0.19 U	3.7	120	0.25	0.072 J	1800	6.5		4.4	19	12000 B
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	4800	3.1	14	220	0.38	0.69	5800	41		6.1	280	42000 B
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	5800	< 0.16 U	5.3	110	0.33	0.14 J	11000	7.2		4.8	29	14000 B
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	6400	< 0.37 U	10	89	0.53	0.23 J	10000	9.9		6.7	38	18000 B
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	7600	< 0.33 U	7.5	53	0.36 J	0.10 J	4700	9.1		5.8	28	17000 B
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	5000	0.17 J	4.0	31	0.21	0.044 J	810	5.8		5.1	12	11000 B
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	5900	< 0.28 U	5.9	39	0.29 J	0.078 J	2700	7.8		5.5	18	16000 B
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	5200	< 0.28 U	5.0	31	0.21 J	0.13 J	2600	6.5		4.9	20	12000 B
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	6800	< 0.32 U	4.2	82	0.32 J	0.081 J	1600	7.4		4.4 J	14	13000 B
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	5400	< 0.31 U	6.5	50	0.24 J	0.10 J	790	6.6		5.4	17	12000
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	6400	< 0.33 UT	4.8 T	52 T	0.28 JT	< 0.079 UT	1300 T	9.0 T		4.9 JT	13 T	13000
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	6300	< 0.23 U	6.2	31	0.28 J	0.092 J	590	8.5		5.7	20	15000
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	4600	< 0.27 U	3.8	33	0.22 J	0.080 J	740	5.9		3.9 J	15	11000
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	6000	< 0.25 U	5.1	54	0.29 J	0.12 J	840	7.5		5.4	13	12000 B
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	8500	< 0.35 U	6.6	65	0.39 J	0.11 J	1400	9.8		6.5	15	16000 B
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	7100	< 0.24 U	6.2	66	0.35	0.13 J	1200	9.2		6.2	12	14000 B
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	5900	< 0.43 U	5.2	45	0.26 J	< 0.10 U	830	7.7		5.1	21	15000 B
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	6900	< 0.29 U	9.5	26	0.25 J	0.23 J	530	7.8		5.3	19	15000 B
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	4600	< 0.26 U	4.0	36	0.23 J	0.097 J	510	6.0		4.3 J	13	11000 B
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	9800	< 2.7 U	20	140 J	< 0.97 U	< 0.65 U	1600 J	14		14	38	30000 B

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	28	2700	540	0.17	22	830	< 0.56 U	< 0.096 U	< 74 U		< 0.47 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	9.7	2400	330 T	0.030 J	18	600	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	21	2800	540	0.10 J	22	830	< 0.55 U	< 0.096 U	< 74 U		< 0.47 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	16	2700	600	0.22	24	700	< 0.47 U	< 0.081 U	99 J		< 0.40 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	42	3300	530	0.13	28	980	< 0.61 U	< 0.11 U	87 J		< 0.52 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated											
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	140	2000	380	0.051 J	22	470	0.44 J	< 0.069 U	100 J		< 0.34 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	30 T	1600	930	0.030 J	12	370 J	0.57 J	< 0.088 U	460 J		< 0.43 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	24	2200	530	0.059 J	17	560	0.58 J	< 0.077 U	260 J		< 0.38 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	36	390 J	71	0.13	13	440 J	1.7 J	< 0.086 U	290 J		< 0.42 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	22	1900	450	0.037 J	18	660	0.57 J	< 0.075 U	250 J		< 0.37 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	170	1800	380	0.039 J	19	460	< 0.39 U	< 0.068 U	96 J		< 0.33 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	19	2200	860	0.063 J	17	530	< 0.42 U	< 0.073 U	70 J		< 0.36 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	10	1900	370	0.023 J	16	520	< 0.38 U	< 0.066 U	55 J		< 0.33 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	19	2100	860	0.050 J	26	820	< 0.54 U	< 0.093 U	< 72 U		< 0.46 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	48	2200	470	0.14	42	700	< 0.53 U	< 0.092 U	190 J		< 0.45 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	13	2500	290	0.022 J	16	660	< 0.42 U	< 0.073 U	75 J		< 0.36 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	31	2500	470	0.14	25	810	< 0.48 U	< 0.084 U	150 J		< 0.41 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	35	2500	300	0.078 J	27	740	< 0.40 U	< 0.070 U	140 J		< 0.34 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	17	2000	260	0.031 J	15	530	0.50 J	< 0.086 U	91 J		< 0.43 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	9.2	2400	250	0.020 J	16	580	< 0.45 U	< 0.078 U	85 J		< 0.38 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	20	2500	450	0.059 J	25	740	< 0.47 U	< 0.081 U	140 J		< 0.40 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	26	1700	590	0.11 J	12	400 J	0.47 J	< 0.074 U	97 J		< 0.36 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	9.4	1500	790	0.033 J	11	430 J	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	8.0	1600	620	0.037 J	11	400 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	38	4700	350	0.078 J	21	690	0.54 J	< 0.074 U	110 J		< 0.36 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	45	2100	440	0.17 B	16	520	0.58 J	< 0.084 U	75 BJ		< 0.41 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	15	2300	740	0.052 J	14	430 J	< 0.54 U	< 0.093 U	< 72 U		< 0.46 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	7.6	1900	360	0.027 J	16	450 J	0.51 J	< 0.081 U	< 62 U		< 0.40 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	40	3600 T	350 T	0.065 J	21	570	0.59 J	< 0.079 U	110 J		< 0.39 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	28	2200	330	0.12	25	500	0.50 J	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	18	1800	790	0.095 J	15	420 J	< 0.44 U	< 0.075 U	59 J		< 0.37 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	14	2100	620	0.031 J	16	600	< 0.43 U	< 0.075 U	63 J		< 0.37 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	14	2300	580	0.033 J	21	730	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	12	2300	340	0.038 J	16	490	< 0.38 U	< 0.066 U	< 51 U		< 0.32 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	12	1500	630	0.039 J	11	370 J	0.62 J	0.083 J	< 50 U		< 0.32 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	13	2700	410	0.025 J	20	640	< 0.57 U	< 0.098 U	87 J		< 0.48 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	6.8	1400	250	< 0.020 U	11	230 J	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	9.3	1900	400	< 0.020 U	14	400	< 0.29 U	< 0.066 U	< 33 U		< 0.18 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	94	3500	370	0.093	10	370	1.5	< 0.065 U	58 J		0.24 J
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	5.8	1300	150	0.027 J	8.9	200 J	< 0.27 U	< 0.060 U	< 30 U		< 0.16 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	8.1 T	1800 T	310	< 0.020 U	12 T	310 JT	< 0.46 UT	< 0.10 UT	< 52 UT		< 0.29 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	23	1700	330	0.021 J	16	510	< 0.25 U	< 0.056 U	< 27 U		< 0.15 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	11	1600	470	< 0.021 U	11	330 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	4.5	1200	150	< 0.021 U	8.6	200 J	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	5.7	1100	210	< 0.023 U	7.7	200 J	< 0.26 U	< 0.058 U	< 28 U		< 0.16 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	5.8	1500	220	< 0.018 U	10	250 J	< 0.31 U	< 0.070 U	< 35 U		< 0.19 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	5.0	1300	230	< 0.019 U	10	270 J	< 0.28 U	< 0.062 U	< 31 U		< 0.17 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	28	910	140	0.11	7.7	240 J	0.33 J	< 0.069 U	< 34 U		< 0.19 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	8.0	1600	330	< 0.019 U	11	300 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	74	890	120	0.088	15	330 J	0.53 J	< 0.11 U	120 J		< 0.29 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	41	450 J	50	0.11	8.3	700	1.1	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	58	2000	420	0.28	14	410 J	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	110	1500	430	0.065	14	370	0.36 J	< 0.054 U	32 J		< 0.15 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	92	1600	250	0.063	12	250 J	< 0.29 U	< 0.065 U	< 32 U		< 0.18 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	270	1300	450	0.11	74	370	1.5	0.10 J	100 J		0.43 J
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	53	1500	270	0.089	13	400	0.69	< 0.055 U	57 J		< 0.15 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	73	1600	320	0.13	19	510 J	0.66 J	< 0.13 U	83 J		< 0.35 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	7.8	4200	350	0.021 J	17	660	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	11	1500	340	0.019 J	10	280	< 0.22 U	< 0.051 U	< 25 U		< 0.14 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	8.9	2400	520	< 0.018 U	14	370 J	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	9.4	1600	330	< 0.026 U	10	320 J	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	12	1300	280	0.035	9.6	340 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	8.7	1500	680	< 0.020 U	12	370 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	8.2 T	1800 T	390	0.025 JT	12 T	340 JT	< 0.50 UT	< 0.11 UT	< 55 UT		< 0.31 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	7.0	2000	270	0.018 J	15	440	0.35 J	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	9.6	1400	260	0.027 J	13	260 J	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	11	1500	440 B	0.027 J	12	290 J	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	12	2000	330 B	0.030 J	15	480 J	< 0.53 U	< 0.12 U	< 59 U		< 0.33 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	12	1800	340 B	0.026 J	14	410	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	9.9	1800	370 B	0.027 J	14	300 J	< 0.66 U	< 0.15 U	< 73 U		< 0.20 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	19	1900	270 B	0.019 J	12	300 J	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	35	1300	310 B	0.029 J	9.9	270 J	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	56	1600 J	1700 B	0.043	49	< 750 U	< 4.1 U	< 0.92 U	< 450 U		< 0.25 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated		13	72
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated		13	51
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated		13	71
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated		13	71
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated		14	110
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated			
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated		15	67
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated		15	53
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated		14	85
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated		13	21
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated		14	52
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated		15	66
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated		13	86
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated		17	65
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated		16	120
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated		17	110
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated		17	49
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated		15	85
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated		15	73
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated		17	65
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated		16	50
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated		13	70
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated		13	57
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		12	40
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		13	41
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated		16	77
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated		16	62
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated		15	55
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated		15	52
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated		15	77
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated		14	79
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated		14	55
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated		12	58
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated		15	75
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated		12	48
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated		11	39
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated		15	59
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated		7.9	55 B
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated		9.6	42
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated		15	48
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated		10	34
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated		11 T	42 BT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated		8.5	38
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated		9.2	40 B
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated		6.2	32 B
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated		6.0	26
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated		7.0	36
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated		5.9	35
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated		5.6	39
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated		9.0	46
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated		11	56
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated		10	28
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated		11	95
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated		11	59
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated		8.2	64
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated		13	220
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated		9.8	56
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated		14	79
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated		13	75
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated		7.2	35
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated		10	63
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated		8.1	68
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated		10	57
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated		8.6	56
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated		9.1 T	41 T
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated		11	46
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated		6.4	45
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated		8.9	44 B
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated		12	48 B
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated		9.6	42 B
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated		8.9	43 B
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated		9.5	180 B
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated		7.0	47 B
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated		16 J	65 B

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	5100	< 0.18 U	4.6	52	0.22 J	0.11 J	560	6.1		4.4	17	11000 B
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	5900 T	< 0.28 UT	5.6 T	47 T	0.27 JT	0.11 JT	710 T	7.2 T		5.5 T	17 T	14000 B
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	6300	< 0.24 U	6.6	52	0.31	0.16 J	970	7.6		5.9	17	13000
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	5800	< 0.20 U	13	43	0.29	0.13 J	610	6.1		11	13	13000
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	6200	< 0.25 U	6.1	48	0.28 J	< 0.061 U	990	7.5		4.8	14	13000
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	7200	< 0.29 UT	6.5 T	42 T	0.30 JT	< 0.071 UT	870 T	8.1 T		6.7 T	21 T	16000
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	5400	< 0.18 U	5.9	34	0.26	0.054 J	870	6.9		4.8	16	13000
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	5200	< 0.21 U	5.5	31	0.24 J	< 0.050 U	590	6.7		5.2	15	12000
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	6600	< 0.28 U	6.9	46	0.28 J	< 0.068 U	820	8.1		5.9	19	15000
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	5400	< 0.23 U	4.3	25	0.24 J	< 0.057 U	450	6.3		4.8	18	13000
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	4900	< 0.18 U	5.3	38	0.24	< 0.042 U	1200	6.4		5.0	11	11000
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	6700	< 0.30 U	6.3	27	0.32 J	0.084 J	650	8.4		5.9	21	17000
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	2500	< 0.19 U	2.4	15	0.12 J	< 0.047 U	910	3.0		2.6 J	7.5	5700
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	7400	< 0.27 U	6.4	58	0.33 J	< 0.066 U	1100	8.0		6.0	17	14000
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	6300	< 0.28 U	4.9	34	0.27 J	< 0.069 U	780	6.9		4.0 J	14	13000
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	8300	< 0.26 U	8.0	66	0.39	< 0.063 U	4400	10		8.5	16	20000
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	6600	< 0.18 U	4.2	55	0.28	0.049 J	1500	7.6		4.7	17	13000
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	9200	0.23 J	16	170	0.52	0.078 J	4600	13		5.6	38	17000
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	5600	< 0.29 U	4.8	32	0.23 J	< 0.070 U	530	7.1		5.3	19	13000
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	7400	< 0.16 U	9.0	66	0.33	< 0.038 U	5800	9.2		8.2	17	19000
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	8200	< 0.30 U	7.8	57	0.35 J	< 0.073 U	3200	10		7.4	21	18000
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	8700	< 0.19 U	8.2	73	0.35	< 0.046 U	4100	11		8.6	15	20000
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	7700	< 0.21 U	7.4	82	0.32	< 0.050 U	2200	9.6		16	15	19000
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	5600	< 0.19 U	4.8	50	0.26	0.048 J	1600	6.7		4.5	21	12000
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	5300	< 0.33 U	3.7	23	0.22 J	< 0.079 U	560	6.2		4.2 J	15	12000
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	5400	< 0.26 U	4.5	56	0.23 J	0.064 J	1100	7.8		5.3	18	13000
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	7000	< 0.16 U	7.7	50	0.34	< 0.039 U	3800	9.1		8.2	11	17000
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	6600	< 0.23 U	15	52	0.30	< 0.055 U	5100	8.9		8.6	14	17000
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	6700	< 0.27 UT	7.0 T	58 T	0.33 JT	< 0.064 UT	1600 T	8.5 T		7.5 T	19 T	15000 T
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	7600	< 0.26 U	4.9	54	0.31 J	< 0.062 U	1200	8.8		5.7	15	15000
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	8400	< 0.24 U	8.4	63	0.41	< 0.058 U	3100	11		9.3	16	21000
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	9600	< 0.25 U	7.5	44	0.41	< 0.060 U	830	10		7.1	20	20000
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	11000	< 0.27 U	7.5	120	0.45	< 0.066 U	4100	11		7.7	20	22000
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	10000	< 0.19 U	5.8	42	0.40	< 0.047 U	640	11		7.4	12	19000
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	14000	< 0.28 U	11	59	0.56	< 0.067 U	630	15		12	29	26000
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	10000	< 0.29 U	6.0	180	0.42	< 0.070 U	270 J	9.6		4.8	11	15000
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	9300	< 0.26 U	6.5	99	0.51	0.55	2200	12		7.3	44	19000
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	11000	< 0.31 UT	14	160	0.56	0.89	7300 T	11		5.4	26	17000
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	4600	0.26 J	10	62	0.33 J	0.36 J	3600	7.8		3.9 J	16	14000
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	8100	0.50 J	27	110	0.54	0.74	6000	13		6.0	23	22000
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	10000	< 0.28 U	17	150	0.58	0.80	6000	12		6.4	27	20000
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	8800	0.72 J	20	200	0.61	0.92	6800	16		6.0	40	20000
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	8800	0.28 J	14	120	0.55	0.53	4400	13		7.2	30	20000
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	9200	< 0.29 U	11	140	0.47	0.53	2900	10		5.9	21	16000
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	10000	< 0.28 U	7.7	120	0.47	0.56	1800	12		7.6	18	19000
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	9300	< 0.26 U	5.1	84	0.40	0.43	3200	11		6.2	17	16000
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	9500	< 0.26 U	6.9	96	0.47	0.60	2300	12		6.9	50	19000
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	8500	< 0.24 U	5.0	42	0.32	0.40	580	10		6.6	25	17000
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	8500	0.31 JT	6.2	47	0.34	< 0.060 U	1300 T	9.7		6.4	20	17000
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	11000	0.83 J	13	160	0.60	0.79	4100	15		7.4	52	24000
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	9000	< 0.28 U	6.6	66	0.41	< 0.068 U	910	11		8.5	25	19000
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	9400	< 0.33 U	13	140	0.57	< 0.079 U	2400	12		6.6	30	21000 B
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	8000	< 0.25 U	7.2	60	0.42	0.065 J	1600	9.9		7.7	22	18000 B
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	7600	< 0.26 U	6.3	53	0.35	< 0.064 U	860	9.3		6.8	20	17000 B
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	9900	< 0.25 UT	7.9	120	0.49	0.16 J	1700	12		7.0	26	18000
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	5300	< 0.23 U	7.5	33	0.36	1.0	1800	8.1		5.1	26	20000
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	9000	0.69 J	6.2	52	0.44	0.13 J	3500	12		9.7	28	21000
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	11000	0.65 J	14	70	0.46	0.17 J	11000	14		10	42	25000
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	5600	0.35 J	4.4	35	0.25 J	0.11 J	48000	7.5		5.7	14	13000
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	8900	< 0.29 U	7.5	56	0.39	0.85	4300	12		7.3	25	20000
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	9800	< 0.33 U	10	67	0.50	0.92	1200	12		8.6	29	21000
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	7200	< 0.23 UT	6.3	39	0.32	0.54	1000	10		6.5	20	16000
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	9200	< 0.28 U	7.9	79	0.43	0.51	2300	10		6.1	22	15000
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	5900	< 0.21 U	6.1	61	0.28	0.48	1200	8.5		5.8	19	14000
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	9200	< 0.26 U	8.0	130	0.42	0.42 J	650	9.8		4.4	23	12000
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	9800	< 0.19 U	6.9	50	0.47	0.64	4500	11		7.7	22	18000
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	11000	< 0.27 U	7.8	48	0.48	0.71	16000	13		9.6	26	21000
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	6100	0.45 J	14	170	0.47	1.3	12000	17		6.9	99	21000
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	9500	< 0.25 U	7.4	41	0.44	0.70	10000	12		9.2	22	20000
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	9400	< 0.24 UT	6.7	36	0.44	0.53	3100 T	11		7.2	18	17000
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	12000	< 0.23 U	8.0	37	0.50	0.67	850	14		9.1	19	20000
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	9200	0.50 JT	7.5	76	0.44	0.77	8300 T	13		6.9	44	20000
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	9500	0.33 J	7.6	95	0.44	0.75	5700	12		7.3	31	17000
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	4900	0.43 J	14	230	0.49	1.2	4000	22		5.4	210	23000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	6.7	1300	260 B	0.035	11	240 J	< 0.27 U	< 0.061 U	< 30 U		< 0.17 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	7.9 T	1600 T	370 B	0.028 J	12 T	300 JT	< 0.43 UT	< 0.097 UT	< 48 UT		< 0.27 UT
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	11	1600	420	0.021 J	14	340 J	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	17	1400	1500	0.029 J	13	210 J	< 0.61 U	< 0.14 U	< 34 U		< 0.38 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	16	1600	370	0.096	14	270 J	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	13 T	2100 T	470	0.029	14 T	450 JT	0.46 JT	< 0.10 UT	< 50 UT		< 0.28 UT
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	9.7	1400	340	< 0.023 U	12	330	< 0.28 U	< 0.062 U	< 31 U		< 0.17 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	7.9	1400	210	< 0.022 U	11	330 J	< 0.32 U	< 0.071 U	< 35 U		< 0.19 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	9.5	1800	420	0.034	13	330 J	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	7.3	1500	330	0.029 J	12	260 J	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	8.6	1500	290	0.027 J	11	320	< 0.27 U	< 0.060 U	< 30 U		< 0.16 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	9.0	1800	460	0.025 J	13	320 J	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	4.5	800	200	0.063	4.3	130 J	< 0.29 U	< 0.066 U	< 33 U		< 0.18 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	18	1600	530	0.057	12	300 J	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	15	1400	220	0.055	10	320 J	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	9.5	2800	290	< 0.018 U	19	670	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	30	1600	300	0.082	11	310	< 0.27 U	< 0.061 U	< 30 U		< 0.17 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	42	2100	360	0.15	15	480	1.2	< 0.075 U	60 J		0.35 J
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	7.3	1600	270	< 0.019 U	12	310 J	< 0.44 U	< 0.099 U	< 49 U		< 0.13 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	11	2400	400	< 0.020 U	18	490	< 0.24 U	< 0.054 U	46 J		< 0.15 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	14	2300	420	< 0.021 U	17	560	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	10	2700	390	< 0.022 U	19	710	< 0.29 U	< 0.066 U	36 J		< 0.18 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	12	2500	510	< 0.015 U	20	530	< 0.31 U	< 0.071 U	36 J		< 0.19 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	37	1500	300	0.077	11	300 J	< 0.28 U	< 0.064 U	< 31 U		< 0.17 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	7.0	1400	280	0.022 J	9.8	330 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	10	1600	530	< 0.020 U	14	350 J	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	9.8	2400	320	< 0.021 U	17	510	< 0.25 U	< 0.056 U	37 J		< 0.15 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	8.9	2300	420	< 0.021 U	16	550	< 0.34 U	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	8.4 T	1900 T	460 T	< 0.017 U	16 T	660 T	< 0.40 UT	< 0.091 UT	< 45 UT		< 0.25 UT
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	10	1800	330	< 0.022 U	14	410 J	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	12	2700	360	< 0.020 U	19	660	0.45 J	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	12	2400	360	0.039	17	370 J	< 0.38 U	< 0.085 U	< 42 U		0.41 J
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	18	2600	810	0.050	17	440 J	< 0.41 U	< 0.094 U	140 J		1.1 J
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	9.8	2100	220	0.024 J	14	330	< 0.29 U	< 0.066 U	470		0.32 J
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	17	3100	650	< 0.023 U	25	450 J	< 0.42 U	< 0.095 U	54 J		0.97 J
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	18	1500	680	0.056	11	220 J	0.73 J	< 0.099 U	< 49 U		1.1 J
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	38	2300	400	0.023 J	21	830 B	< 0.40 U	< 0.090 U	63 J		< 0.25 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	71 T	1100	380	0.071	17	620 B	0.76 J	< 0.10 U	250 J		0.49 J
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	5.0	420 J	42	0.30	11	330 BJ	< 0.40 U	< 0.090 U	150 J		0.27 J
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	25	980	160	0.15	17	620 B	0.68 J	< 0.12 U	200 J		0.60 J
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	47	1300	500	0.069	16	490 B	1.0	< 0.095 U	180 J		0.47 J
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	100	1300	280	0.084	19	650 B	1.6	< 0.11 U	130 J		0.43 J
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	47	2100	320	0.13	16	830 B	0.54 J	< 0.088 U	73 J		0.24 J
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	130	1400	690	0.058	13	560 B	0.85 J	< 0.099 U	78 J		< 0.27 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	30	2400	570	0.028 J	18	820 B	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	20	2100	400	< 0.023 U	15	700 B	< 0.40 U	< 0.090 U	< 45 U		< 0.25 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	37	2100	440	< 0.023 U	23	710 B	< 0.39 U	< 0.089 U	96 J		< 0.24 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	10	2500	390	< 0.022 U	16	560 B	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	11	2200	330	0.040 B	15	340 J	< 0.37 U	< 0.085 U	49 J		0.82 J
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	130	1700	430	0.17 B	26	480	1.5	< 0.091 U	130 J		1.3 J
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	11	2400	490	< 0.020 U	19	740	< 0.43 U	< 0.097 U	49 J		1.0 J
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	57	1800	420	0.095	16	350 J	0.80 J	< 0.11 U	82 J		1.2 J
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	17	2300	490	0.029 J	19	520	< 0.37 U	< 0.084 U	90 J		0.93 J
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	9.9	2200	470	0.021 J	17	470	< 0.40 U	< 0.091 U	< 45 U		0.78 J
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	54	2000	560	0.073	20	470	0.55 J	< 0.086 U	66 J		1.0 J
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	12	1800	450	< 0.021 U	16	310 J	< 0.36 U	< 0.080 U	< 39 U		0.64 J
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	9.6	3400	380	0.040 B	23	690	< 0.47 U	< 0.11 U	< 52 U		0.57 J
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	9.6	5800	420	0.034 BJ	25	960	< 0.47 U	< 0.11 U	< 52 U		0.61 J
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	4.9	6100	300	0.024 BJ	13	520	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	12	3100	350	0.026 J	21	720	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	22	2100	1200	0.042	20	910	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	8.9	2000 T	330	0.037	16	540	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	25	1700	400	0.071	14	500	0.95	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	15	1700	440	0.023 J	14	460	< 0.32 U	< 0.072 U	< 36 U		< 0.20 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	40	1400	330	0.066	12	450	1.4	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	15	2500	320	0.057	19	560	0.38 J	< 0.066 U	41 J		< 0.18 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	12	4500	450	0.031 J	20	630	< 0.40 U	< 0.091 U	48 J		< 0.25 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	180	2100	280	0.34	30	500	1.1	< 0.10 U	78 J		< 0.27 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	11	3400	480	< 0.021 U	21	610	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	8.7	2400	300	0.030 J	17	650	< 0.36 U	< 0.082 U	< 41 U		< 0.22 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	9.7	2800	240	< 0.022 U	18	640	0.38 J	< 0.080 U	< 40 U		< 0.22 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	36	3100	270 T	0.90 T	21	730	< 0.44 U	< 0.10 U	50 J		< 0.27 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	49	2200	540	0.061	19	600	< 0.44 U	< 0.099 U	54 J		< 0.27 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	150	1200	150	1.0	31	330 J	< 0.45 U	< 0.10 U	100 J		< 0.28 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated		7.3	37 B
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated		8.8 T	44 BT
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated		9.4	50
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated		9.4	35
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated		9.8	38
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated		11 T	52 T
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated		8.9	42
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated		8.4	39
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated		11	48
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated		7.8	40
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated		7.4	34
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated		12	150
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated		4.2	20
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated		12	46
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated		9.7	40
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated		11	57
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated		10	50
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated		16	56
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated		8.8	42
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated		10	40
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated		12	56
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated		12	47
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated		11	43
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated		9.4	44
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated		7.6	40
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated		7.9	43
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated		9.5	42
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated		9.3	36
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated		10 T	42 T
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated		11	47
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated		12	46
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated		17	61
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated		17	54
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated		18	43
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated		24	64
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated		14	49
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated		16	69 B
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated		18	72 BT
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated		14	11 B
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated		20	27 B
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated		18	67 B
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated		23	58 B
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated		16	47 B
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated		17	56 B
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated		16	82 B
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated		14	61 B
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated		15	80 B
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated		12	50 B
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated		12	47
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated		20	130
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated		13	58
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated		19	52
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated		13	59
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated		12	51
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated		15	81 T
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated		11	200
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated		17	61 B
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated		19	65 B
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated		9.0	43 B
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated		15	65
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated		20	160
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated		14	66 T
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated		16	48
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated		11	43
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated		16	62
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated		17	56
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated		18	64
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated		18	130
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated		18	59
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated		17	45 T
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated		20	55
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated		14	65
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated		15	80
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated		17	160

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	8400	< 0.24 U	6.8	53	0.38	0.74	7400	10		7.1	25	16000
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	4400	0.76 J	12	200	0.50	0.86	1800	44		7.0	150	25000
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	9900	< 0.27 U	6.1	74	0.39	0.56	1100	11		6.0	20	18000
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	12000	< 0.32 U	7.1	110	0.48	0.73	2300	13		8.1	19	21000
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	3900	0.82 J	12	200	0.56	1.3	6800	21		6.5	140	30000
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	8800	0.76 J	9.3	130	0.46	0.86	2200	10		5.8	35	24000
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	9700	< 0.25 UT	4.9	80 T	0.39	0.65	1700	11		6.9	33 T	19000 T
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	6600	1.3	15	62	0.41	1.7 J	2100	13		11	140	51000
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	12000	< 0.25 U	8.2	42	0.47	0.66	650	13		9.6	16	20000
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	10000	< 0.23 U	8.3	36	0.53	0.72	780	12		9.1	22	21000
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	11000	0.25 J	9.6	40	0.51	0.73	580	12		8.3	23	21000
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	10000	0.43 J	9.0	97	0.47	0.76	3600	11		9.2	37	18000
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	9600	0.61 J	8.7	120	0.39 J	0.99	43000	20		7.5	81	21000
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	9200	0.22 J	5.4	90	0.37	0.70	2700	13		6.1	23	16000
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	8100	< 0.28 U	5.6	92	0.35 J	0.63	4900	9.7		6.1	23	15000
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	8200	0.41 J	5.2	71	0.30	0.73	30000	10		6.8	27	16000
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	9200	0.42 J	6.3	89	0.40	0.66	2600	11		6.8	82	17000
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	6000	0.44 J	9.2	110	0.51	1.3	7600	12		6.0	67	21000
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	8500	< 0.29 U	5.7	100	0.39	0.87	1500	10		6.3	53	16000
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	8200	0.65 J	12	1100	0.40 J	2.3	2400	26		7.7	130	30000
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	11000	< 0.31 U	5.9	120	0.51	0.77	1700	15		9.4	17	18000
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	7600	1.9	19	98	0.43	1.4	5900	29		7.6	57	31000
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	9900	< 0.32 U	9.0	63	0.44	0.76	1900	12		7.2	26	19000
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	9400	< 0.30 U	8.7	50	0.41	0.72	910	12		8.0	27	18000
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	8400	< 0.29 U	7.0	54	0.36 J	0.72	2100	11		7.5	25	17000
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	8300	< 0.30 U	7.6	58	0.41	0.72	2400	11		8.0	23	17000
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	7200	< 0.21 U	6.8	32	0.32	0.61	640	9.5		7.0	22	15000
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	7600	< 0.28 U	7.2	33	0.32 J	0.70	1100	9.6		7.6	24	16000
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	7300	< 0.25 U	7.3	42	0.32 J	0.67	1400	9.7		6.9	22	16000
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	12000	0.31 J	7.7	52	0.49	0.83	2500	12		8.6	21	19000
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	8100	< 0.31 U	7.1	60	0.36 J	0.71	2000	11		9.2	24	17000
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	8800	< 0.33 UT	9.4	44	0.44	0.81	1400	12		8.2	28	20000
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	8200	< 0.32 U	8.2	1500	0.39 J	1.4	1900	20		7.2	86	17000
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	11000	0.31 J	6.4	59	0.43	0.81	22000	13		8.8	24	18000
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	7500	0.60 J	12	120	0.51	0.90	4900	12		7.4	67	22000
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	10000	< 0.28 U	9.5	31	0.47	0.65	920	11		8.1	22	22000
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	4500	0.30 J	9.8	100	0.38	0.69	2800	12		4.8	61	17000
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	13000	< 0.28 U	7.4	170	0.59	0.54	2300	12		6.0	12	18000
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	11000	0.33 J	5.5	130	0.46	0.38 J	3300	10		6.1	9.5	17000
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	6800	0.37 J	6.4	50	0.34 J	0.34 J	24000	9.3		6.4	34	19000
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	8700	0.49 J	12	120	0.56	0.71	33000	13		8.7	55	21000
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	6900	< 0.23 U	9.6	37	0.35	0.46	3900	9.3		7.3	28 B	17000
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	9500	< 0.33 U	11	88	0.51	0.55	2700	13		8.2	42	19000
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	10000	1.7 J	13	88 J	0.62 J	0.44 J	1100 J	12		8.1	29	27000
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	8000	< 0.35 U	25	180	0.63	6.0	3800	27		10	150	46000
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	7200	1.5	16	100	0.48	0.55 J	1900	24		7.6	130	53000
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	8100	< 0.28 U	9.6	70	0.54	0.46	1800	12		9.1	32	18000
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	8700	0.34 J	10	100	0.42	0.59	2600	17		7.6	76	18000
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	10000	0.32 JT	12	82	0.43	0.49 J	2300 T	14		9.0	57	20000
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	10000	0.35 J	10	79	0.43	0.56	8100	13		9.3	34	20000
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	7900	0.30 J	13	140	0.52	0.88	8700	20		8.0	100	19000
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	6700	0.59 J	20	130	0.55	1.3	5800	19		8.4	80	33000
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	7500	2.1	14	95	0.77	1.5	5100	12		8.0	74	28000
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	9400	0.55 J	12	97	0.50	1.1	6400	16		9.0	59	25000
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	9100	< 0.30 U	15	120	0.54	5.8	14000	17		9.6	360	26000
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	3900	0.88 J	19	87	0.88	0.54	2500	8.7		8.1	44	25000
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	8200	< 0.26 U	9.5	55	0.38	0.40 J	1000	12		9.4	27	18000
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	3100 T	0.48 JT	9.5	56	0.56	0.32 J	1700	7.0		6.0	24 T	16000 T
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	8600	< 0.99 U	14	96	0.52 J	0.44 J	1100 J	11		9.2	28	27000
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	6200	1.0	13	110	0.81	0.98	2400	12		12	73	20000
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	3900	0.76 J	7.1	67	0.38	0.46	3600	6.1		3.9 J	22	16000
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	7300	< 1.1 U	9.4	36	0.36	0.35 J	1100	10		8.6	25	16000
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	8100	< 0.31 U	9.9	68	0.40 J	1.1	5500	12		7.9	41	19000
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	8900	< 0.33 U	9.6	78	0.57	0.62	7800	12		8.7	38	19000
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	8100	< 0.28 U	9.1	62	0.40	0.50	2300	13		7.8	28	17000
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	6400	< 0.26 U	10	39	0.31 J	0.39 J	1300	9.3		7.3	25 B	17000
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	8400	< 0.24 U	8.1	73	0.38	0.53	8400	11		8.2	29 B	17000
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	10000	0.24 J	29	91	0.52	0.69	7800	14		12	39 B	23000
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	6400	< 0.26 U	8.5	32	0.29 J	0.42 J	1700	8.8		7.0	22 B	15000
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	7900	0.32 J	11	85	0.44	0.65	10000	14		7.5	38 B	19000
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	6600	0.25 JT	7.6	45	0.27 J	0.43	30000	9.8		6.9	27 B	15000
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	12000	< 0.26 U	9.2	120	0.58	0.75	21000	16		10	100	25000
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	11000	< 0.30 U	8.5	86	0.44	0.58	4900	16		8.2	48	23000
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	9900 B	< 0.20 U	8.1	89	0.42	0.40	12000	14		8.7	34	23000

DRAFT

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	11	3700	390	< 0.022 U	20	510	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	180	860	200	0.14	36	480	2.2	0.34 J	150 J		< 0.25 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	10	2200	380	< 0.023 U	16	410 J	< 0.41 U	< 0.092 U	< 45 U		0.27 J
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	21	2700	620	0.078	20	580	< 0.48 U	< 0.11 U	< 54 U		0.45 J
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	100	2700	150	0.070	30	470	1.6	0.20 J	170 J		< 0.26 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	120	1600	480	0.099	15	450 J	0.49 J	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	26	2300 T	480 T	0.032 J	18	550	< 0.37 U	< 0.084 U	86 J		< 0.23 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	180	1800	650	0.23	42	460	< 0.42 U	< 0.094 U	< 47 U		< 2.6 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	8.9	2600	280	< 0.024 U	19	740	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	10	2500	380	< 0.022 U	22	760	< 0.36 U	< 0.080 U	< 40 U		< 0.22 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	13	2600	360	< 0.021 U	22	710	< 0.33 U	< 0.076 U	< 37 U		0.23 J
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	63	2700	700	0.56 B	18	610	< 0.43 U	< 0.097 U	68 J		0.31 J
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	740	5600	440	0.18 B	48	660	< 0.49 U	< 0.11 U	100 J		< 0.30 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	66	2200	390	0.075 B	17	470	< 0.33 U	< 0.075 U	< 37 U		< 0.21 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	42	2200	470	0.065 B	16	620	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	20	8600	480	0.069 B	18	530	< 0.30 U	< 0.068 U	69 J		< 0.19 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	56	2100	510	0.085 B	17	650	< 0.42 U	< 0.095 U	< 47 U		0.38 J
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	74	2800	240	0.083	23	470 J	< 0.44 U	< 0.099 U	130 J		< 0.27 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	61	1900	490	0.20	48	480	< 0.43 U	< 0.098 U	< 48 U		0.39 J
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	160	2400	660	0.22 B	40	400 J	< 0.58 U	0.20 J	< 64 U		< 0.36 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	41	2600	520	0.097 B	23	860	< 0.46 U	< 0.10 U	54 J		< 0.29 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	140	2300	390	0.28 B	40	650	1.3	< 0.085 U	84 J		< 0.23 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	14	2400	390	0.046 B	18	560	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	12	2100	350	0.033 BJ	21	550	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	13	2700	480	0.031 BJ	20	590	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	13	2700	670	0.034 B	20	690	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	11	1900	270	0.028 BJ	17	450	< 0.32 U	< 0.073 U	41 J		< 0.20 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	8.1	2400	380	0.022 BJ	21	400 J	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	9.4	2200	320	0.021 BJ	19	520	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	13	2800	380	0.022 BJ	19	600	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	18	2500	580	0.032 B	20	580	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	11	2200	400	0.028 BJ	22	660	< 0.51 U	< 0.11 U	< 56 U		0.45 J
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	150	2200	510	0.23 B	34	510 J	< 0.49 U	0.11 J	< 54 U		< 0.30 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	11	5000	560	0.022 BJ	21	790	< 0.42 U	< 0.095 U	66 J		< 0.26 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	76	1700	330	0.072	23	510	0.42 J	< 0.083 U	160 J		< 0.23 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	8.4	2700	400	< 0.024 U	19	440 J	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	74	1100	210	0.10	18	310 J	0.47 J	< 0.073 U	93 J		< 0.20 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	19	2200	490	0.043	17	460	0.64 J	< 0.095 U	< 47 U		0.31 J
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	9.5	2500	570	< 0.024 U	13	450	0.72 J	< 0.083 U	43 J		0.66 J
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	7.3	5200	390	0.032 J	16	440 J	< 0.47 U	< 0.11 U	54 J		< 0.29 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	96	3100	530	0.17	26	560	0.59 J	< 0.10 U	75 J		< 0.28 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	20	2400	470 B	0.30	18	480	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	31	2400	510	< 0.023 U	22	670	< 0.50 U	< 0.11 U	69 J		< 0.31 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	11	2700	710	< 0.022 U	19	860 J	< 2.1 U	< 0.48 U	< 240 U		< 0.26 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	220	1500	620	0.33	49	650	3.9	< 0.12 U	77 J		< 0.33 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	160	1600	470	0.15	36	420	0.87	< 0.072 U	56 J		< 0.99 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	33	1800	390	0.036 J	20	560	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	46	2100	410	0.10	46	470	0.41 J	< 0.086 U	49 J		< 0.24 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	29	2600	470	0.033 J	30	610	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	21	4000	430	0.026 J	24	730	< 0.39 U	< 0.087 U	49 J		< 0.24 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	120	2100	420	0.18	28	800	0.90 J	0.29 J	88 J		< 0.27 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	100	1600	340	0.18	72	590	1.5	< 0.11 U	94 J		< 0.29 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	170	1700	530	0.10	39	630	0.75 J	< 0.11 U	120 J		< 0.30 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	78	3400	530	0.095	29	650	0.50 J	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	150	3400	550	< 0.021 U	39	820	0.46 J	< 0.10 U	150 J		< 0.28 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	42	600	160	0.16	21	260 J	0.66 J	< 0.099 U	59 J		< 0.27 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	15	2200	540	< 0.022 U	23	550	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	17	390 JT	110 T	0.28	11	300 J	1.1	< 0.10 U	< 51 U		< 0.28 UT
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	11	2300	1200	< 0.023 U	16	630 J	< 1.5 U	< 0.34 U	< 170 U		0.30 J
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	350	1000	270	0.27	25	550	0.79 J	< 0.10 U	59 J		< 0.28 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	20	470	80	3.5	8.8	230 J	0.57 J	< 0.091 U	47 J		< 0.25 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	9.7	2300	430	< 0.022 U	19	470	< 1.7 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	38	3100	460	< 0.022 U	22	570	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	65	2800	380	0.35	20	650	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	23	2300	480	< 0.022 U	18	640	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	10	2000	400 B	0.25	17	430	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	29	4200	820 B	0.10	19	480	< 0.36 U	< 0.082 U	40 J		< 0.22 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	42	4200	520 B	0.28	25	700	0.32 J	< 0.072 U	39 J		< 0.20 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	7.7	2200	390 B	0.19	16	460	< 0.40 U	< 0.091 U	< 45 U		0.40 BJ
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	48	3400	640 B	0.48	18	610	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	14 T	4100 T	500 B	0.041	16	510	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	70	9600	700	0.19	27	1000	0.57 J	< 0.090 U	90 J		< 0.25 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	57	3800	470	0.12	22	700	0.59 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	84	4100	520	0.061	26	760	< 0.30 U	< 0.067 U	100 J		< 0.18 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated		13	70
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated		23	100
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated		15	53
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated		18	67
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated		23	99
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated		13	98
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated		15	63 T
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated		13	130
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated		19	54
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated		20	60
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated		19	57
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated		17	71
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated		16	130
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated		15	90
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated		14	61
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated		13	64
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated		15	84
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated		16	140
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated		15	220
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated		34	590
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated		15	63
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated		23	100
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated		18	68
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated		17	59
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated		15	64
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated		15	66
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated		15	51
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated		12	60
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated		12	56
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated		20	57
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated		16	64
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated		18	69
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated		29	480
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated		17	69
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated		16	79
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated		18	58
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated		13	69
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated		17	60
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated		14	47
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated		11	56
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated		19	100
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated		13	110
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated		17	85
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		18 J	84
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated		23	2500
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated		17	200
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated		18	94
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated		16	98
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated		17	94 T
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated		17	79
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated		18	190
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated		23	370
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated		16	450
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated		20	340
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated		17	360
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		19	44
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		17	70
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		14	24 T
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		15 J	71
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		20	340
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		12	52
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated		13	79
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated		16	880
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated		15	180
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated		14	160
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated		15	68
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated		15	100
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated		17	180
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated		12	83
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated		16	200
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated		12	98
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated		19	210
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated		20	380
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated		16	73 B

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	9000	0.71 J	9.7	100	0.49	0.63	12000	15		6.9	56	20000
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	12000 B	< 0.33 U	13	150	0.71	0.91	6500	23		10	63	27000
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	11000 B	< 0.32 U	8.8	85	0.48	0.33 J	16000	13		9.8	23	26000
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	10000 B	< 0.21 U	8.4	72	0.44	0.38	21000	12		9.1	23	24000
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	9800 B	< 0.28 U	6.1	99	0.43	0.54	16000	13		7.3	31	19000
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	9000 B	< 0.22 U	5.5	87	0.34	0.67	33000	14		7.5	37	20000
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	10000	< 0.28 U	5.2	66	0.38	0.53	29000	12		8.6	31	22000
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	10000	< 0.30 U	10	97	0.49	0.79	11000	14		7.0	73	29000
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	12000	0.40 J	14	150	0.74	6.6	12000	30		8.8	130	26000
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	10000	< 0.28 U	6.6	71	0.42	0.54	82000	13		8.2	32	22000
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	9700	< 0.28 U	7.3	100	0.42	1.1	31000	13		7.3	47	21000
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	9700	< 0.23 U	6.4	79	0.40	0.54	41000	12		8.2	33	21000
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	9200	< 0.31 UT	10	84	0.42	0.26 J	2200 T	9.3		5.9	33	18000
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	10000	< 0.29 U	11	120	0.60	0.87	8200	14		13	72	23000
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	12000	< 0.21 U	5.9	98	0.44	0.43	7300	16		8.4	42	24000
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	7900	3.4 JT	23	170 J	< 1.2 U	3.3 J	4700 J	100		10 J	140	230000
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	9300	< 0.28 UT	7.1	57	0.39	0.34 J	4700	11		7.6	34	23000
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	9900	< 0.28 U	8.6	100	0.48	0.56	8400	15		7.9	39	22000
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	6300	< 0.21 U	6.9	61	0.27	0.28 J	21000	9.7		6.5	27	17000
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	9100	< 0.30 U	6.8	110	0.48	0.29 J	3000	14		8.1	16	18000
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	9000	< 0.32 U	6.9	100	0.44	0.33 J	32000	13		7.9	17	17000
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	7900	< 0.25 U	5.8	70	0.34	0.29 J	26000	12		6.5	21	17000
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	6400	0.30 J	7.0	83	0.33	0.35 J	46000	10		5.7	34	15000
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	7100	0.35 JT	6.2	400	0.31 J	0.32 J	30000 T	10		6.2	36	17000
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	7700	< 0.23 U	7.4	74	0.32	0.31 J	22000	11		7.7	37	19000
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	7300	< 0.30 U	6.3	66	0.27 J	0.23 J	26000	10		6.4	25	18000
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	4600	< 0.27 U	3.7	52	0.19 J	0.30 J	100000	6.6		3.9 J	24	11000
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	5400	< 0.18 U	4.8	83	0.20 J	0.25 J	21000	7.9		5.2	26	14000
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	6500	0.26 J	4.9	73	0.25	0.34	98000	9.1		5.7	21	15000
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	6200	0.25 J	6.9	53	0.25 J	0.30 J	47000	8.7		5.7	24	17000
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	9100	< 0.29 U	6.3	92	0.44	0.37 J	4900	18		7.8	19	18000
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	10000	< 0.28 U	10	92	0.44	< 0.067 U	2800	12		9.3	19	23000
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	7600	< 0.35 U	7.3	64	0.33 J	< 0.084 U	1200	9.9		6.2	23	17000
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	8300	< 0.27 U	5.7	160	0.32 J	< 0.065 U	1600	9.2		5.0	19	15000
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	7900	< 0.36 UT	13 T	120 T	0.36 J	0.76	1800 T	41 T		7.9	22	39000
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	10000	< 0.34 U	8.2	110	0.47	< 0.082 U	2800	11		8.8	20	22000
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	8700	< 0.33 U	5.2	44	0.31 J	< 0.080 U	490 J	9.5		6.4	16	16000
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	11000	< 0.28 U	6.3	99	0.42	< 0.067 U	1000	12		7.2	23	20000
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	9600	< 0.24 U	11	84	0.44	< 0.058 U	1200	9.5		7.3	25	24000
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	9500	< 0.35 U	5.0	65	0.32 J	< 0.084 U	790	9.9		5.6 J	14	17000
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	9600	< 0.31 U	6.9	59	0.36 J	< 0.075 U	1300	11		7.3	19	18000
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	9800	< 0.29 U	6.0	58	0.30 J	< 0.069 U	1000	10		6.0	12	18000
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	8600	< 0.37 U	5.5	150	0.56	< 0.091 U	1900	7.9		5.7 J	35	16000
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	11000	< 0.35 U	9.9	74	0.45 J	< 0.085 U	2400	13		9.2	21	25000
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	8300	< 0.25 U	6.4	63	0.31 J	< 0.059 U	1000	9.5		4.9	18	16000
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	7200	< 0.24 U	7.0	84	0.31	< 0.058 U	1600	10		5.2	41	15000
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	7500	< 0.32 U	7.7	91	0.41 J	< 0.078 U	1700	9.4		5.3	37	16000
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	6100	< 0.31 UT	8.7	77 T	0.25 J	< 0.076 U	54000	9.4		4.8 J	39	16000
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	8300	< 0.27 U	10	120	0.43	< 0.064 U	2300	11		5.9	38	17000
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	7500	< 0.31 U	7.0	120	0.30 J	0.16 J	2600	9.5		4.9 J	26	16000
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	7100	< 0.22 U	7.8	80	0.32	< 0.054 U	3300	9.7		6.4	37	18000
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	7800	< 0.34 U	6.7	94	0.32 J	< 0.082 U	2000	11		5.3 J	46	16000
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	6600	< 0.28 U	4.1	72	0.25 J	< 0.068 U	1100	6.8		4.2 J	13	13000
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	8400	< 0.26 U	6.4	76	0.32 J	0.11 J	1700	9.1		5.5	27	17000
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	6500	0.54 J	6.9	42	0.22 J	< 0.047 U	35000	8.1		5.8	17	16000
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	8300	0.38 JT	9.3	79	0.40	< 0.060 U	3800	11		6.1	24	17000
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	7300	0.43 J	7.2	69	0.29	< 0.051 U	18000	9.4		6.0	22	16000
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	8900	0.47 J	18	220	0.68	1.8	6000	25		7.1	54	14000
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	7000	0.41 J	7.3	44	0.28	< 0.051 U	32000	9.2		6.1	23	17000
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	8300	0.31 J	9.0	110	0.44	0.25 J	3300	10		6.0	27	16000
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	8500	< 0.26 U	4.6	88	0.28 J	< 0.063 U	400 J	7.8		4.8	23	14000
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	7300	< 0.25 U	6.1	78	0.28 J	0.47	1200	7.7		4.7	25	14000
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	7900	< 0.29 U	9.0	110	0.44	0.72	1900	9.2		6.7	31	17000
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	7400	< 0.25 U	6.5	82	0.27 J	0.76	1200	8.3		4.6	25	14000
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	7600	< 0.26 U	6.3	110	0.26 J	0.27 J	2900	8.3		4.3	24	14000
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	7300	< 0.23 U	5.6	77	0.33	0.097 J	4000	7.8		5.2	24	15000
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	8900	< 0.30 U	5.3	87	0.29 J	< 0.073 U	1400	8.5		5.1	24	15000
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	7900	< 0.25 UT	5.2	71 T	0.31 J	0.066 J	2200 T	8.7 T		5.9 T	32	16000
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	7500	0.23 J	6.9	93	0.27 J	0.26 J	610	8.7		5.4	36	13000
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	8600	< 0.27 U	8.6	72	0.36	0.59	1500	9.9		5.9	34	15000
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	9700	< 0.32 U	5.1	120	0.36	0.18 J	460	9.2		4.9	57	14000
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	9400	0.29 J	8.2	110	0.34 J	0.43 J	910	11		6.3	40	18000
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	6800	0.48 J	10	95	0.42	0.22 J	1800	9.0		6.8	40	12000
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	6400	8.9	38	120 J	0.30	1.4 J	3600	14		10	55	99000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	100	3200	540	0.13	21	830	0.64 J	< 0.085 U	55 J		< 0.23 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	150	4000	630	0.42	30	1100	1.3	< 0.11 U	66 J		< 0.31 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	18	5700	530	0.021 J	23	950	< 0.49 U	< 0.11 U	60 J		< 0.30 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	14	4800	430	< 0.021 U	21	780	< 0.32 U	< 0.073 U	52 J		< 0.20 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	30	5400	540	0.051	17	900	0.61 J	< 0.096 U	64 J		< 0.26 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	31	5100	500	0.090	22	590	0.38 J	< 0.074 U	68 J		< 0.20 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	23	7500	450	< 0.022 U	23	710	< 0.43 U	< 0.097 U	65 J		< 0.26 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	78	2600	580	0.11	17	1000	0.74 J	< 0.10 U	90 J		< 0.28 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	130	4700	540	0.22	26	1100	1.5	< 0.14 U	100 J		0.57 J
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	16	8300	720	< 0.021 U	23	770	< 0.43 U	< 0.096 U	95 J		< 0.26 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	62	5300	450	< 0.024 U	21	660	< 0.43 U	< 0.098 U	230 J		< 0.27 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	31	6800	730	0.077	23	720	< 0.35 U	< 0.080 U	84 J		< 0.22 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	27	2400	460	0.045	15	540	< 0.47 U	< 0.11 U	57 J		0.46 J
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	91	3900	1200	0.21	26	660	0.75 J	< 0.098 U	63 J		< 0.27 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	220	4500	430	0.33	30	790	< 0.32 U	< 0.073 U	62 J		< 0.20 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	800	890 J	860	0.92	28 J	< 960 U	< 5.2 U	< 1.2 U	< 580 U		3.3 J
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	22	4200	600	< 0.022 U	22	570	< 0.42 UT	< 0.096 U	48 J		< 0.26 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	60	4900	470	0.094	24	1000	0.60 JT	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	14	5400	420	0.046	50	520 B	< 0.31 U	< 0.071 U	57 J		< 0.19 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	25	2600	520	0.061	20	640 B	< 0.46 U	< 0.10 U	< 51 U		0.33 J
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	18	4800	530	0.14	19	690 B	< 0.49 U	< 0.11 U	58 J		< 0.30 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	19	6900	450	0.039	17	560 B	< 0.38 U	< 0.085 U	55 J		< 0.23 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	47	4100	360	0.074	21	570 B	< 0.38 U	< 0.086 U	100 J		< 0.23 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	59 T	4000 T	680	0.11	42	480 B	< 0.41 U	< 0.093 U	72 J		0.44 J
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	68	5300	630	0.024 J	45	620 B	< 0.35 U	< 0.080 U	64 J		< 0.22 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	11	4700	440	< 0.021 U	25	600 B	< 0.46 U	< 0.10 U	51 J		< 0.28 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	12	11000	300	0.022 J	22	440 B	< 0.40 U	< 0.091 U	84 J		< 0.25 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	14	3400	300	0.030 J	29	340 B	< 0.27 U	< 0.061 U	42 J		0.21 J
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	12	11000	450	0.061	15	400 B	< 0.29 U	< 0.064 U	79 J		< 0.18 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	9.2	9800	390	< 0.022 U	26	450 B	< 0.37 U	< 0.083 U	57 J		< 0.23 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	20	3000	450	0.16	20	660 B	< 0.44 U	< 0.10 U	< 49 U		0.29 J
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	23	3200	450	0.029 J	20	790	< 0.42 U	0.15 J	< 47 U		< 0.26 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	66	1800	430	0.040	13	390 J	< 0.53 U	< 0.12 U	< 59 U		< 0.33 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	41	1700	580	0.041	12	370 J	< 0.41 U	0.13 J	< 46 U		< 0.25 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	99 T	2800 T	440	0.061	16 T	430 J	< 0.55 U	0.30 JT	< 61 U		< 0.34 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	28	2600	690	< 0.023 U	18	630	< 0.51 U	0.17 J	< 57 U		< 0.32 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	9.8 J	2200	330	0.035	14	310 J	< 0.50 U	0.11 J	< 56 U		< 0.31 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	32	3000	460	0.064	19	360 J	< 0.42 U	0.18 J	58 J		< 0.26 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	22	1900	1400	0.050	14	610	< 0.37 U	0.20 J	< 41 U		< 0.23 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	12	2000	400	0.033	13	350 J	< 0.53 U	0.13 J	< 59 U		< 0.33 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	37	2300	290	0.031 J	15	440 J	< 0.47 U	0.14 J	< 52 U		< 0.29 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	13	2000	270	0.056	11	360 J	< 0.43 U	0.14 J	< 48 U		< 0.27 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	65	1400	770	0.039	11	350 J	< 0.57 U	0.16 J	< 63 U		< 0.35 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	25	3200	360	0.033 J	19	710	< 0.53 U	0.20 J	< 59 U		< 0.33 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	43	1700	270	0.043	12	330 J	< 0.37 U	0.14 J	< 41 U		< 0.23 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	71	1600	480	0.15	13	640	< 0.36 U	0.12 J	65 J		< 0.22 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	76	1600	440	0.11	14	610	< 0.49 U	0.15 J	57 J		< 0.30 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	61 T	2500 T	400 T	0.17	14	570	< 0.47 U	< 0.11 U	260 J		< 0.29 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	170	1700	640	0.26	15	590	< 0.40 U	0.14 J	79 J		< 0.25 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	81	1800	460	0.097	12	570	< 0.48 U	0.15 J	57 J		< 0.29 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	48	1900	360	0.061	85	490	< 0.34 U	0.12 J	41 J		< 0.21 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	78	1700	530	0.19	13	700	< 0.52 U	< 0.12 U	72 J		< 0.32 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	22	1400	520	0.054	9.1	290 J	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	77	1900	460	0.14	14	550	< 0.40 U	0.13 JT	47 J		< 0.24 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	13	8400	310	0.022 J	14	440	< 0.30 U	< 0.089 U	63 J		0.37 J
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	49	2100	460	0.15	20	540	< 0.38 U	< 0.44 U	66 J		0.74 J
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	25	2900	490	0.031 J	15	470	< 0.32 U	< 0.095 U	52 J		0.61 J
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	490	910	430	0.19	21	690	4.1	< 0.12 U	190 J		0.90 J
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	13	4100	340	0.021 J	15	500	< 0.32 U	< 0.38 U	53 J		0.50 J
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	80	2000	620	0.26	29	510	0.75	< 0.53 U	46 J		0.82 J
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	30	1500	500	0.071 B	9.2	510	< 0.40 U	0.094 J	< 44 U		< 0.25 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	64	1500	420	0.10 B	12	910	< 0.38 U	0.12 J	51 J		< 0.23 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	110	1700	680	0.13 B	18	930	< 0.44 U	0.15 J	56 J		< 0.27 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	80	1500	400	0.15 B	12	910	< 0.38 U	0.11 J	52 J		< 0.23 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	81	1500	510	0.12 B	11	580	< 0.40 U	0.13 J	53 J		< 0.25 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	48	2200	390	0.071 B	13	650	< 0.35 U	0.11 J	49 J		< 0.22 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	31	1800	480	0.070 B	10	530	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	48	2700	460	0.13 BT	14 T	590 T	< 0.37 UT	0.14 J	46 J		< 0.23 UT
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	34	1600	480	0.049	11	400 J	< 0.43 U	< 0.39 U	< 48 U		< 0.27 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	47	1800	350	0.19	16	590	< 0.37 U	< 0.46 U	44 J		< 0.23 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	12	1700	450	0.045	17	350 J	< 0.38 U	< 0.54 U	< 43 U		< 0.24 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	44	1600	360	0.065	14	410 J	< 0.45 U	< 0.43 U	< 50 U		< 0.28 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	290	1200	410	1.0	13	790	< 0.47 U	0.20 J	86 J		< 0.29 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	680	2200	640	14	28 J	< 610 U	< 3.3 U	0.82	40 J		< 0.20 U

DRAFT

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated		21	300
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated		20	380
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated		16	84
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated		15	74 B
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated		15	290 B
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated		24	310 B
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated		15	150
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated		19	210
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated		23	400
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated		15	140
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated		15	300
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated		15	200
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated		13	87 T
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated		18	400
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated		18	100
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated		38 J	380
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated		15	110
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated		14	190
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated		10	60
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated		13	59
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated		13	60
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated		11	76
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated		13	74
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated		13	130
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated		13	65
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated		11	62
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated		7.4	71
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated		8.4	62
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated		9.9	58
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated		10	56
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated		14	76
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated		15	73
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated		13	180
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated		12	140
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated		14 T	460
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated		15	66
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated		12	56
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated		15	89
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated		16	78
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated		14	48
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated		14	100
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated		18	63
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated		13	51
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated		16	82
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated		14	58
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		13	100
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		13	160
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		16 T	120 T
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		17	160
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		14	390
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated		12	82
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		14	120
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		11	43
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		14	340
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated		9.0	49
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated		15	64 T
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated		11	54
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated		27	800
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated		10	51
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated		13	370
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated		13	54
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated		12	200
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated		14	1500
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated		12	230
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated		13	400
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated		11	180
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated		16	63
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated		13 T	130
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated		14	70
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated		16	110
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated		14	70
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated		17	130
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		21	190
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		19 J	400

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	7100	< 0.26 U	5.6	35	0.24 J	< 0.063 U	1200	8.5		5.2	19	15000
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	11000	< 0.33 U	4.4	93	0.37 J	< 0.079 U	1400	10		6.5	12	16000
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	6400	1.1	7.7	71	0.33	0.53	20000	4.5		5.2	44	18000
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	7300	1.3	10	69	0.37 J	1.7	19000	9.8		5.5 J	50	18000
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	7600	1.7	14	100	0.47	1.1	12000	9.3		5.7	78	24000
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	8500	1.1	6.9	68	0.37	0.73	20000	5.1		6.1	33	19000
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	7300	1.6	12	170	0.47	1.3	2400	13		6.5	59	27000
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	7500	0.86 J	6.1	71	0.33 J	0.27 J	1300	9.7		6.2	27	27000
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	9100	0.61 J	5.3	40	0.36	< 0.062 U	590	9.4		6.3	27	18000
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	7800	0.29 J	4.3	52	0.28 J	< 0.056 U	150 J	9.7		5.8	20	14000
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	8700	0.35 J	3.1	57	0.30 J	< 0.070 U	280 J	9.3		4.6 J	16	13000
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	10000	0.53 JT	5.4	52	0.38	0.067 J	620	11		6.3	19	17000
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	7800	0.41 J	3.6	45	0.29 J	< 0.066 U	660	8.6		5.4	21	15000
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	7400	0.52 J	4.8	49	0.27 J	< 0.062 U	460	8.0		4.9	18	13000
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	8200	0.55 J	4.2	38	0.29	< 0.049 U	760	9.0		4.9	18	14000
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	6800	0.33 J	2.3	32	0.23 J	< 0.058 U	170 J	7.9		3.9 J	21	12000
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	8700	0.44 J	4.6	46	0.32 J	< 0.069 U	950	10		5.1	19	15000
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	8000	0.57 JT	5.0	67	0.35	< 0.056 U	1600	9.7		6.6	16	17000
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	8700	0.33 J	3.3	96	0.31	< 0.055 U	390	8.4		4.3	11	14000
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	9100	0.56 J	5.9	95	0.37	0.089 J	3200	11		5.3	19	17000
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	6800	0.46 J	3.7	41	0.26 J	< 0.052 U	750	7.4		4.0	14	12000
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	11000	0.74 J	5.2	140	0.41	< 0.072 U	2300	12		5.4	16	20000
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	8100	0.58 J	2.8	73	0.28 J	0.11 J	690	9.0		4.2	14	14000
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	10000	0.58 J	5.4	100	0.38 J	< 0.082 U	2100	11		4.9 J	18	18000
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	9900	0.48 JT	2.6	56 T	0.29 J	< 0.056 U	270 J	9.7		4.1	18 T	14000
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	8200	0.77 J	6.8	130	0.41	1.3	8100	12		6.0	27	17000
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	8600	0.90	4.0	77	0.31	< 0.053 U	1300	9.6		4.7	13	16000
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	11000	0.36 J	3.2	78	0.34	< 0.053 U	270 J	13		5.0	12	17000
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	8300	0.38 J	7.9	99	0.46	0.76	3100	14		7.6	41	23000
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	8400	0.61 J	7.4	650	0.44	0.69	2600	13		6.7	36	19000
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	8800	< 0.33 UT	5.9	110	0.43 J	0.78	2100 T	11		7.0	35	19000
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	8500	0.52 J	7.1	81	0.42	0.52	5800	13		8.5	38	22000
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	8500	< 0.22 U	2.8	140	0.38	0.31 J	2100	8.6		5.0	13	14000
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated	6600	< 0.26 U	5.2	32	0.24 J	< 0.064 U	270 J	7.3		4.3	14	13000
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated	8100	0.34 JT	7.0	65	0.29 J	< 0.078 U	2600 T	11		5.9	28	18000
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	8700	0.61 J	21	240	0.76	0.84	7000	19		5.2 J	57	22000
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	7700	< 0.35 U	18	150	0.63	0.84	7000	19		8.6	51	42000
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	6400	< 0.33 U	12	110	0.47	0.36 J	7000	9.5		4.1 J	61	16000
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	6900	1.1	7	53	0.32	0.53	4700	8.4		6.6	31	17000
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	8800	< 0.24	9.4	50	0.38	0.038	6500	9.7		7.9	23	20000
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	6300	< 0.21	6.7	33	0.32	< 0.015	1300	8.3		5.7	17	15000
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	5700	< 0.2	6.1	34	0.26	0.51	4000	8.3		5.5	17	15000
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	9100	< 0.21	11	55	0.4	0.034	2300	11		7.1	27	19000
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated		< 1.08	5.22	26.8	< 0.539	< 0.539		6.7		5.59	16.8	
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated	12000	< 0.4 U	7.6	58	0.53	0.059 J	4800	15		11	21	23000
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated	9100	1.6	10	95	0.49	0.19 J	15000	13		7.3	47	29000
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated	10000	< 0.39 U	8.3	46	0.5	0.044 J	970	11		8.4	19	20000
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated	12000	< 0.4 U	6.2	59	0.47	0.054 J	1000	12		6.4	15	20000
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated	10000	< 0.38 U	7.6	50	0.46	0.088 J	940	13		9.2	21	21000
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated	10000	0.57 J	5.9	800	0.41 J	0.074 J	7100	13		7	32	18000
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated	14000	0.44 J	6.5	65	0.52	0.064 J	1900	15		9.3	14	21000
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated	8800	< 0.4 U	7.4	67	0.44 J	0.082 J	8900	11		7.6	20	17000
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated	6900	< 0.37 U	6.5	55	0.34 J	0.12 J	14000	13		6.2	35	17000
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated	6400	0.53 J	4.5	43	0.24 J	0.11 J	37000	9.3		6	19	15000
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated	8700	0.84 J	8.4	130	0.39 J	0.22 J	3300	40		6.4	38	25000
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated	8900	0.39 J	6.7	53	0.36 J	0.065 J	920	12		7.9	22	20000
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated	6100	< 0.37 U	4.4	43	0.25 J	0.044 J	490 J	10		5.7	16	13000
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated	12000	0.58 J	6.6	61	0.49	0.063 J	4200	15		11	14	20000
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated	8300	< 0.39 U	5.3	36	0.39 J	0.059 J	410 J	10		7.4	18	18000
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated	9000	0.65 J	9	120	0.51	0.2 J	14000	12		8.2	39	23000
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated	12000	< 0.41 UJ	8.1	110	0.47 J	0.16 J	2600 J	12		6.8	16	16000
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated	12000	< 0.38 U	6.6	51	0.47	0.07 J	2100	14		7.7	15	19000
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated	11000	0.46 J	10	87	0.57	0.21 J	1900	14		9.3	29	22000
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated	8200	< 0.39 U	5.3	54	0.32 J	0.084 J	6300	11		6	23	17000
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated	7200	< 0.35 U	5.6	41	0.3 J	0.062 J	1000	9.4		6.2	19	16000
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated	8600	< 0.4 U	8.2	41	0.4 J	0.076 J	1500	11		6.6	23	18000
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated	13000	0.43 J	9.2	42	0.57	< 0.043 U	1100	14		10	23	24000
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated	13000	< 0.41 U	5.8	51	0.44 J	0.051 J	600	13		7.2	12	20000
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated	13000	< 0.39 U	6.9	60	0.5	< 0.042 U	1100	15		8.9	14	22000
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated	11000	0.58 J	7	91	0.44 J	0.064 J	1100	13		7.7	19	20000
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated	13000	1.5	7	71	0.47	0.066 J	1300	14		8	17	22000
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated	12000	0.43 J	5	89	0.44 J	< 0.045 U	1200	13		7.2	16	18000
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated	12000	0.42 J	4.9	95	0.44 J	0.067 J	1600	13		7.9	17	18000
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated	7100	< 0.35 U	5	45	0.25 J	0.18 J	28000	10		6.4	29	17000

DRAFT

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	15	2200	290	0.030 J	13	460	< 0.39 U	0.15 J	< 44 U		< 0.24 U
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	13	1900	390	0.031 J	11	510 J	< 0.50 U	0.17 J	57 J		< 0.31 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	52	2800 T	380	0.20	17	500	< 0.37 U	0.24 J	170 J		< 1.1 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	76	4800 T	410	11	22	790	< 0.54 U	0.26 J	61 J		< 1.7 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	82	2300 T	500	2.1	22	900	< 0.47 U	0.43 J	< 52 U		< 1.4 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	38	6100	380	0.19	22	810	< 1.9 U	0.27 J	55 J		< 0.46 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	300	1300	400	0.13	24	580	1.5	< 0.15 U	62 J		0.31 J
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	54	1800	450	0.041	17	530	< 0.42 U	< 0.19 U	< 47 U		< 0.26 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	15	2400	440	< 0.023 U	16	400 J	< 0.39 U	< 0.44 U	56 J		0.40 J
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	16	2000	340	< 0.023 U	14	320 J	< 0.35 U	< 0.40 U	50 J		0.43 J
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	20	1700	220	< 0.025 U	11	280 J	< 0.44 U	< 0.10 U	< 49 U		0.36 J
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	22 T	2400	260	0.024 J	17	420 T	< 0.34 U	< 0.077 U	79 J		0.42 J
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	15	2000	360	0.026 J	13	420 J	< 0.41 U	< 0.46 U	57 J		0.40 J
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	17	1700	340	< 0.023 U	12	280 J	< 0.39 U	< 0.44 U	< 43 U		0.52 J
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	23	2000	230	< 0.022 U	12	380	< 0.31 U	< 0.070 U	< 34 U		0.58 J
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	16	1700	130	< 0.022 U	11	270 J	< 0.36 U	< 0.082 U	< 40 U		0.47 J
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	41	2000	230	0.025 J	13	430 J	< 0.43 U	< 0.098 U	< 48 U		0.66 J
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	31 T	2300	360	< 0.023 U	15	510	< 0.35 U	< 0.080 U	42 J		0.61 J
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	25	1400	410	0.029 J	9.7	350 J	0.38 J	< 0.078 U	< 38 U		0.42 J
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	62	2300	380	0.067	14	780	0.67 J	< 0.081 U	< 40 U		0.49 J
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	21	1600	150	0.042	10	310 J	< 0.32 U	< 0.073 U	38 J		0.42 J
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	66	1900	680	0.052	14	530	0.73 J	< 0.10 U	54 J		0.71 J
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	36	1700	290	0.035	11	350 J	< 0.36 U	< 0.080 U	< 40 U		0.39 J
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	55	2100	360	0.058	13	660	< 0.51 U	< 0.12 U	< 57 U		0.46 J
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	11	1700	130 T	< 0.023 U	11	300 J	< 0.35 U	< 0.079 U	< 39 U		0.46 J
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	170	2300	490	0.14	14	650	0.63 J	< 0.098 U	63 J		0.50 J
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	38	1900	240	0.033 J	13	510	< 0.33 U	< 0.075 U	< 37 U		0.50 J
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	9.3	2000	160	< 0.025 U	14	390	< 0.34 U	< 0.076 U	< 37 U		0.59 J
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	180	2100	500	0.22	22	720	1.1	< 0.098 UT	< 48 U		< 0.27 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	130	2000	490	0.15	19	680	1.1	< 0.096 UT	< 47 U		< 0.26 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	81 T	2000	630 T	0.12	21	740	1.2	< 0.11 UT	< 56 U		< 0.31 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	60	2700	420	0.068	21	700	0.79 J	< 0.10 UT	< 51 U		< 0.28 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	20	1500	1100	0.059	11	420	0.92	< 0.077 UT	< 38 U		< 0.21 U
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated	9.3	1500	240	0.030 J	9.8	330 J	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated	21	2400 T	410 T	0.037	14 T	470 JT	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	270	1300	460	0.18	16	390 J	1.5	< 0.15 U	81 J		< 0.40 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	200	980	780	0.16	33	430 J	2.7	< 0.12 U	100 J		< 0.32 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	40	1000	120	0.13	24	460 J	1.0 J	< 0.11 U	140 J		< 0.31 U
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	45	1800	510	0.047	14	540	0.47	< 0.043	110		< 0.15
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	15	2500	610	0.031	17	620	< 0.32	< 0.048	40		< 0.17
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	7.4	1900	320	0.017	13	580	1	< 0.042	30		< 0.15
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	6.9	2700	450	< 0.012	13	550	1	< 0.041	33		< 0.15
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	16	2100	590	< 0.012	17	1000	0.49	< 0.042	43		< 0.15
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	6.15			< 0.0539	12.9		< 0.539	< 1.08			< 1.08
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated	16	3000	490	0.063	19	880	< 0.61 U	< 0.12 U	71 J		< 0.25 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated	76	2500	950	0.24	24	860	1.2	< 0.12 U	220 J		< 0.36 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated	15	2500	600	0.02 J	16	840	< 0.58 U	< 0.12 U	48 J		< 0.36 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated	12	2500	230	0.061	17	780	< 0.6 U	< 0.12 U	55 J		< 0.37 U
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated	13	2700	590	0.035 J	19	1100	< 0.58 U	< 0.12 U	54 J		< 0.36 U
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated	33	2900	370	0.3	17	700	0.62 J	< 0.12 U	57 J		< 0.36 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated	15	2900	810	0.038	18	960	< 0.63 U	< 0.13 U	54 J		< 0.39 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated	16	4100	490	0.05	15	710	< 0.61 U	< 0.13 U	63 J		< 0.38 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated	9.6	4900	550	0.023 J	17	660	< 0.55 U	< 0.11 U	72 J		< 0.35 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated	8.9	4900	400	0.018 J	15	630	< 0.52 U	< 0.11 U	73 J		< 0.33 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated	95	1700	800	0.12	16	540	0.6 J	< 0.11 U	100 J		< 0.34 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated	14	2800	420	< 0.016 U	20	740	< 0.57 U	< 0.12 U	49 J		< 0.35 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated	7.3	1700	470	< 0.014 U	12	570	< 0.55 U	< 0.11 U	< 28 U		< 0.34 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated	13	3800	460	0.024 J	18	860	< 0.61 U	< 0.12 U	72 J		< 0.38 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated	11	2200	760	0.014 J	14	670	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated	83	2500	460	0.27	23	830	1.2	< 0.12 U	58 J		< 0.37 U
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated	21	2200	590	0.077	15	700	0.81 J	< 0.13 U	68 J		< 0.39 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated	11	2300	310	< 0.015 U	16	780	< 0.57 U	< 0.12 U	43 J		< 0.35 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated	29	2700	1200	< 0.016 U	25	1300	< 0.62 U	< 0.13 U	46 J		< 0.39 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated	7.4	5200	350	0.025 J	16	850	< 0.59 U	< 0.12 U	52 J		< 0.37 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated	7.4	2100	350	0.015 J	16	710	< 0.53 U	< 0.11 U	41 J		< 0.33 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated	9.9	2100	520	< 0.013 U	15	960	< 0.6 U	< 0.12 U	47 J		< 0.38 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated	11	3000	500	0.032 J	21	1100	< 0.61 U	< 0.12 U	64 J		< 0.38 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated	10	2700	240	< 0.017 U	17	730	< 0.62 U	< 0.13 U	41 J		< 0.39 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated	10	2700	280	< 0.016 U	17	780	< 0.59 U	< 0.12 U	47 J		< 0.37 U
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated	19	2400	650	0.028 J	18	760	< 0.64 U	< 0.13 U	59 J		< 0.4 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated	20	2600	550	0.26	17	780	< 0.59 U	< 0.12 U	52 J		< 0.37 U
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated	18	2700	470	0.00044	17	740	< 0.63 U	< 0.13 U	68 J		< 0.4 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated	11	2300	440	0.026 J	15	720	< 0.64 U	< 0.13 U	45 J		< 0.4 U
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated	12	6100	420	0.36	17	750	0.73 J	< 0.11 U	74 J		< 0.33 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		11	62
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated		16	65
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		4.6	86
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		4.1 J	1600
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		6.1	320
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated		5.4	130
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated		16	660
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated		15	97
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated		15	80
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated		13	59
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated		14	51
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated		16	100
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated		12	79
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated		12	62
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		14	58
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		10	45
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		15	76
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated		12	71 T
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		13	66
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		14	160
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		9.9	55
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated		18	110
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		12	85
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		15	110
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		14	280
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated		14	550
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated		12	120
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated		15	85
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated		19	210
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated		17	180
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		16	760
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		16	140
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		13	49
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated		10	76
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated		14	83 T
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated		37	170
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated		19	160
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated		14	75
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated		11	63
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated		14	55
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated		11	46
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated		11	48
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated		17	55
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 53.9	11.6	98.8
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated		21	56
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated		21	110
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated		17	52
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated		17	60
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated		17	63
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated		15	75
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated		20	55
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated		12	60
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated		11	51
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated		9.9	80
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated		17	140
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated		15	62
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated		9.6	42
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated		16	54
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated		12	58
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated		18	91
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated		16	89
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated		18	59
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated		20	69
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated		13	52
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated		12	59
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated		15	51
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated		20	61
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated		19	54
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated		21	56
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated		17	58
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated		20	67
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated		16	66
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated		19	56
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated		11	100

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated	6300	< 0.37 U	5.2	42	0.27 J	0.12 J	49000	9.2		6.5	20	16000
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated	7800	0.35 J	5.9	68	0.33 J	0.046 J	1100	10		6.2	24	17000
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated	9200	< 0.37 U	6.3	50 J	0.37 J	0.072 J	2600	12		8.2	20	18000
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated	10000	0.78 J	7.4	68	0.45 J	0.062 J	1100	11		7.6	17	18000
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated	10000	0.5 J	6.2	79	0.44 J	0.048 J	1800	13		7.2	14	17000
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated	6900	< 0.38 U	5.9	41	0.31 J	0.096 J	2800	8.8		5.8	18	16000
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated	5600	< 0.35 U	5.5	34	0.25 J	0.1 J	24000	7.7		5.3	16	13000
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1[8]	Not Excavated	5100	< 0.42 U	4.1	56	0.24 J	0.066 J	560 J	6.5		4.2 J	11	12000
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated	7300	0.54 J	6.6	58	0.35 J	0.071 J	810	15		6.2	22	17000
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated	8300	< 0.37 U	8	60	0.41 J	0.1 J	1100	12		7.9	27	18000
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated	4900	< 0.36 U	3.2	41	0.21 J	0.11 J	43000	6.3		4.3 J	16	11000
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated	12000	0.68 J	9	76	0.62	0.069 J	1500	16		12	29	26000
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated	7700	< 0.39 U	6.1 J	64	0.32 J	0.1 J	23000	9.9		6.9 J	23	17000
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated	9100	< 0.39 U	8.6	83	0.42 J	0.063 J	1100	11		7.1	22	19000
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated	7800	0.45 J	7.3	50	0.35 J	0.079 J	1300	11		7	20	19000
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated	11000	0.55 J	9.1	110	0.56	0.12 J	6400	14		8.7	45	22000
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated	6500	0.69 J	6	43	0.29 J	0.068 J	1000	8.4		5.7	21	15000
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated	7600	0.51 J	7.1	48	0.37 J	0.13 J	790	10		7.2	21	19000
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated	5700	< 0.34 UJ	5.1	39	0.24 J	0.085 J	26000	10		5	25	13000
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated	6300	< 0.37 UJ	6.1	55	0.32 J	0.37 J	30000 J	13		5.9	43	18000
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated	5400	< 0.38 UJ	6.2	35	0.26 J	0.088 J	11000	7.8		5.2 J	19	14000
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated	4900	< 0.4 U	6	28	0.21 J	0.085 J	41000	6.8		4.8 J	36	12000
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated	6800	< 0.37 UJ	4.2	40	0.29 J	0.063 J	900	9.1		6	16	14000
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated	7800	< 0.37 U	5.5	56	0.33 J	0.13 J	1700	10		7	20	17000
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated	11000	0.41 J	6.2	53	0.42 J	0.044 J	260 J	11		7.7	11	18000
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated	9900	0.48 J	9.1	39	0.45 J	0.05 J	560 J	12		7.9	22	22000
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated	10000	0.44 J	7	55	0.43 J	0.059 J	370 J	12		7.3	19	21000
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated	9400	0.49 J	11	69	0.49	0.058 J	880	11		8.6	29	22000
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated	7900	< 0.37 U	6	60	0.32 J	0.12 J	5200	9.4		6.2	25	17000
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated	6000	< 0.37 U	4	58	0.22 J	0.14 J	44000	8.7		5.2 J	55	14000
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated	8	0.47 J	8	57	0.4 J	0.14 J	1300	9.3		5.9	27	19000
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated	5300	< 0.35 U	5.5	32	0.25 J	0.12 J	28000	7.1		5 J	17	13000
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated	4900	< 0.37 U	4.6	34	0.23 J	0.076 J	1500	7		4 J	14	11000
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated	5800	< 0.37 U	5.9	49	0.26 J	0.14 J	26000	7.2		5 J	17	13000
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated	6700	< 0.37 U	5.3	49	0.27 J	0.14 J	24000	12		5.8	25	16000
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated	7600	< 0.44 U	7.4	45	0.39 J	0.11 J	1200	10		6.5	26	19000
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	11000	< 0.39 U	7.9	46	0.5	0.1 J	980	16		8.7	49	23000
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated	9600	1.8	5.9	85	0.64	0.77	8800	11		7.6	440	17000
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated	6600	< 0.35 U	4.6	50	0.35 J	0.098 J	820	7.8		4.9 J	16	13000
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	11000	< 0.41 U	6.2	58	0.45 J	0.1 J	1000	13		6.9	26	18000
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated	10000	< 0.39 U	6.4	65	0.41 J	0.072 J	180 J	13		8.2	20	19000
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated	11000	< 0.37 U	7.8	91	0.45	0.095 J	1500	13		7.7	18	19000
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	9400 J	< 0.4 U	7.3	73	0.42 J	0.13 J	10000 J	12		7.1 J	21	17000
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated	5300	< 0.37 U	4	38	0.23 J	0.088 J	7900	11		4.7 J	16	13000
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated	5400	< 0.33 U	3.9	26	0.2 J	0.091 J	4100	7.9		4.2 J	16	13000
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated	6100	< 0.37 U	4.9	46	0.24 J	0.12 J	21000	9.2		5.2 J	130	14000
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated	8200	< 0.33 U	15	65	0.37 J	0.34 J	15000	11		6.7	33	22000
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated	4600	< 0.37 U	5.1	29	0.2 J	0.15 J	2000	7.2		4.1 J	17	12000
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated	5400	< 0.36 U	4.7	31	0.23 J	0.11 J	14000	7.9		4.7 J	20	14000
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated	5900	< 0.33 U	5.8	40	0.26 J	0.091 J	1500	8.1		5.2	19	14000
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated	6100	< 0.35 U	4.8	38	0.26 J	0.1 J	1000	8.1		5.5	24	15000
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated	7000	< 0.35 U	4.9	52	0.31 J	0.14 J	8400	9.4		6	19	17000
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated	10000	0.61 J	7.1	36	0.44	0.064 J	800	11		6.9	20	19000
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated	11000	0.7 J	7.6	70	0.43	0.11 J	1100	22	< 0.25 U	6.9	42	26000
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	9100	0.56 J	8.2	57	0.37 J	0.11 J	1000	13		7.1	28	20000
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	8500	0.74 J	9.6	45	0.33 J	0.11 J	8500	10		7.0	29	19000
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	5400	< 0.37 U	3.6	38	0.26 J	0.075 J	7700	7.8		6.1	17	12000
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	9000	< 0.69 U	7.6	61	0.42 J	0.38 J	1900	11		5.6	27	18000
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	8100	0.37 J	5.0	47	0.31 J	0.12 J	8900	9.8		4.8	15	13000
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	8400	0.34 J	6.7	48	0.35 J	< 0.033 U	370 J	9.4		6.1	20	16000
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4-6 ft	4-6 ft	180-127265-2	Not Excavated	5100	< 0.28 U	4.6	31	0.18 J	0.086 J	54000	7		4.7	14	13000
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	8700	0.32 J	5.4	49	0.32 J	0.046 J	40000 J	12		6.1	20	16000
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated	9000	< 0.34 U	7.6	47	0.35 J	0.053 J	260 J	9.8		6.8	18	17000
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated	9200	0.40 J	6.8	78	0.37 J	0.067 J	1800	9.9		5.1	29	30000
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated	9300	< 0.43 U	11	99	0.43 J	0.75	4100	13		6.8	500	23000
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated	6600	0.35 J	8.6	110	0.34 J	0.21 J	42000	15		6.2	36	16000
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated	8200	< 0.29 U	7.6	110	0.35 J	0.067 J	500	9.5		7.6	24	17000
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated	7900	0.37 JT	6.3	47	0.32 J	0.080 J	340 J	9.0		6.3	21	17000
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated	9600	< 0.35 U	8.8	55	0.45 J	0.089 J	170 J	9.5		9.1	22	20000
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated	8400	< 0.31 U	6.7	59	0.35 J	0.085 J	4300	9.4		5.9	19	15000
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated	9800	< 0.37 U	5.4	59	0.71	0.057 J	3600	9.3		5.3	15	14000
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated	5400	< 0.34 U	5.4	38	0.23 J	0.097 J	31000	7.3		4.9	17	13000
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated	5300	< 0.38 U	4.8	30	0.27 J	< 0.051 U	600	7.2		5.3	15	13000
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated	7500	< 0.38 U	7.0	61	0.34 J	0.11 J	1100	9.5		8.1	24	17000

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated	10	19000 J	390	0.013 J	16	730	1.3 J	< 0.12 U	94 J		< 0.35 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated	7	2300	490	< 0.017 U	16	710	< 0.53 U	< 0.11 U	48 J		< 0.33 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated	11	3600	510	0.016 J	19	910	< 0.57 U	< 0.12 U	40 J		< 0.35 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated	37	2200	450	0.027 J	16	810	< 0.63 U	< 0.13 U	57 J		< 0.39 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated	11	2300	600	0.023 J	15	840	< 0.6 U	< 0.12 U	44 J		< 0.38 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated	8.7	2800	440	< 0.016 U	15	780	< 0.58 U	< 0.12 U	43 J		< 0.36 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated	6.9	3700	400	< 0.013 U	13	690	< 0.53 U	< 0.11 U	63 J		< 0.33 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated	4.5	1300	200	< 0.016 U	9.5	520 J	< 0.63 U	< 0.13 U	34 J		< 0.39 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated	11	2000	520	0.012 J	16	730	< 0.57 U	< 0.12 U	58 J		< 0.36 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated	14	2100	760	0.022 J	15	730	< 0.56 U	< 0.12 U	49 J		< 0.35 U
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated	4.2	8500	340	< 0.014 U	11	680	0.68 J	< 0.11 U	76 J		< 0.34 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated	14	3800	690	0.029 J	33	1400	< 0.6 U	< 0.12 U	44 J		< 0.37 U
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated	9.3 J	12000	590	< 0.017 U	17	830	< 0.58 U	< 0.12 U	65 J		< 0.36 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated	10	2200	460	0.025 J	18	770	< 0.58 U	< 0.12 U	53 J		< 0.36 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated	9.3	2400	510	0.018 J	17	750	< 0.6 U	< 0.12 U	50 J		< 0.37 U
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated	13	4900	520	< 0.018 U	21	1300	< 0.62 U	< 0.13 U	59 J		< 0.39 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated	9.8	1800	460	< 0.015 U	14	710	< 0.57 U	< 0.12 U	44 J		< 0.36 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated	12	2100	810	0.026 J	16	670	< 0.57 U	< 0.12 U	42 J		< 0.36 U
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated	26	5000	430	0.015 J	12	740	< 0.52 U	< 0.11 U	67 J		< 0.32 U
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated	23	7300 J	400	0.027 J	50 J	810	0.97 J	< 0.11 U	74 J		< 0.35 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated	8.1	8000 J-	550	< 0.016 U	12	660	< 0.58 U	< 0.12 U	66 J		< 0.36 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated	8.8	22000	410	< 0.015 U	12	690	< 0.6 U	< 0.12 U	94 J		< 0.37 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated	12 J	2000	600	0.015 J	14	670	< 0.56 U	< 0.11 U	40 J		< 0.35 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated	9.5	2300	660	< 0.014 U	19	960	< 0.56 U	< 0.12 U	48 J		< 0.35 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated	8.7	2200	320	0.027 J	15	670	< 0.61 U	< 0.13 U	31 J		< 0.38 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated	11	2400	280	< 0.014 U	17	850	< 0.62 U	< 0.13 U	< 31 U		< 0.39 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated	10	2400	310	< 0.014 U	18	670	< 0.59 U	< 0.12 U	33 J		< 0.37 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated	17	2000	480	< 0.017 U	18	850	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated	12	3100	520	< 0.014 U	16	710	< 0.56 U	< 0.11 U	50 J		< 0.35 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated	4.2	4200	630	< 0.014 U	13	660	< 0.56 U	< 0.11 U	64 J		< 0.35 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated	9.8	2300	640	< 0.014 U	16	800	< 0.61 U	< 0.12 U	41 J		< 0.38 U
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated	6.3	9400 J-	380	< 0.014 U	13	690	< 0.54 U	< 0.11 U	68 J		< 0.33 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated	20	1500	650	< 0.014 U	9.9	630	< 0.56 U	< 0.11 U	39 J		< 0.35 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated	9.3	15000	600	< 0.014 U	12	650	< 0.56 U	< 0.11 U	87 J		< 0.35 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated	7.3	5500	570	< 0.015 U	14	820	< 0.56 U	< 0.11 U	75 J		< 0.35 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated	13	2100	560	< 0.016 U	17	820	< 0.66 U	< 0.14 U	49 J		< 0.41 U
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	15	2800	390	< 0.026 UJ	43	800	< 0.59 U	< 0.12 U	< 69 U		0.37 J
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated	81	1400	420	0.082	57	440 J	1 J	< 0.11 U	290 J		< 0.35 U
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated	11	1400	370	< 0.026 U	11	490 J	< 0.53 U	< 0.11 U	450 J		< 0.33 U
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	20	2300	320	0.029 J	17	680	< 0.62 U	< 0.13 U	< 73 U		< 0.39 U
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated	11	3000	280	< 0.025 U	19	770	< 0.59 U	< 0.12 U	< 69 U		< 0.37 U
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated	15	2600	440	0.029 J	18	930	< 0.56 U	< 0.11 U	< 66 U		0.35 J
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	23	2700 J	290	0.075	19	770 J	< 0.61 UJ	< 0.12 U	73 J		< 0.38 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated	7.6	2100	430	0.028 J	12	460 J	< 0.56 U	< 0.11 U	< 66 U		< 0.35 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated	6.4	2500	250	0.073	12	400 J	< 0.5 U	< 0.1 U	< 59 U		< 0.31 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated	17	6700	360	0.14	14	600	< 0.56 U	< 0.11 U	83 J		< 0.35 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated	440	3400	530	0.12	17	660	1	< 0.1 U	< 59 U		0.31 J
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated	7.9	1800	460	< 0.023 U	12	530 J	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated	7.2	4700	490	< 0.024 U	12	560	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated	11	1900	430	< 0.025 U	12	540	< 0.5 U	< 0.1 U	< 59 U		< 0.31 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated	8.8	1800	460	< 0.025 U	13	550	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated	8.9	4300	480	< 0.024 U	15	620	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated	9	2500	310	< 0.022 U	18	800	< 0.57 U	< 0.12 U	< 66 U		< 0.35 U
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated	33	2100	430	0.037	54	690	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	13	2500	520	< 0.022 U	20	840	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	9.4	3700	510	< 0.020 U	18	590	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	5.1	3500	280	< 0.020 U	11	640	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	15	1900	420	0.032 J	18	740 J	< 1.1 U	< 0.21 U	< 120 U		0.64 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	9.3	1800	240	0.027 J	17	490	< 0.45 U	< 0.092 U	64 J		0.75 J
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	9.3	1900	320	< 0.024 U	16	660	< 0.47 U	< 0.096 U	< 55 U		< 0.29 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4-6 ft	4-6 ft	180-127265-2	Not Excavated	7.9	17000	390	< 0.017 U	12	550	0.84	< 0.088 U	85 J		< 0.27 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	10	4300	390	< 0.019 U	16	760	0.56 J	< 0.094 U	71 J		< 0.29 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated	9.9	2000	450	0.11 J	16	610	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated	31	1900	410	0.062 J	13	440 J	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated	100	2200	440	0.10 J	17	640	0.81 J	< 0.097 U	< 75 U		< 0.48 U
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated	55	4700	410	0.053 J	51	660	< 0.46 U	< 0.080 U	83 J		< 0.39 U
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated	15	2200	700	0.028 J	18	630	< 0.39 U	< 0.066 U	< 52 U		0.65 J
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated	7.0	2300	380	0.029 J	19	460	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated	11	2000	1200	0.050 J	19	630	< 0.46 U	< 0.079 U	< 61 U		0.88 J
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated	19	2000	290	0.053 J	16	570	< 0.40 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated	15	2000	330	0.038 J	13	640	< 0.49 U	< 0.084 U	210 J		< 0.42 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated	7.3	7500	550	0.050 J	13	630	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated	6.0	1700	310	< 0.020 U	13	470 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated	11	2000	510	0.035 J	18	600	0.61 J	< 0.087 U	< 67 U		< 0.43 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated		11	57
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated		12	57
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated		14	65
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated		16	52
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated		17	52
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated		12	62
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated		9.6	57
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated		9.3	63
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated		13	50
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated		17	66
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated		7.8	42
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated		19	68
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated		13	63
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated		15	66
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated		14	58
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated		18	99
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated		11	51
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated		13	84
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated		9.9	49
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated		11	100 J
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated		9.6	49 J+
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated		8.3	42
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated		11	44
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated		13	61
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated		17	51
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated		18	55
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated		21	55
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated		18	71
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated		11	100
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated		9.5	43
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated		12	82
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated		8.7	41
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated		8	37
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated		9.6	62
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated		11	73
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated		13	62
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated		15	62
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated		10	200
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated		10	34
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated		16	56
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated		15	52
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated		17	52
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated		14	60
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated		9.5	42
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated		9.7	40
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated		9.6	49
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated		14	160
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated		7.9	49
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated		8.7	42
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated		9.6	51
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated		9.8	41
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated		11	57
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated		15	51 J-
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated		18	60
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated		14	60
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated		11	51
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated		8.9	34
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated		15	220
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated		13	54
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated		14	56
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated		8.6	44
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated		13	47
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated		15	56
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated		16	63
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated		15	130
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated		12	90
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated		13	66
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated		11	66
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated		15	60
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated		14	66
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated		14	48
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated		9.3	44
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated		8.8	40
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated		12	70

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated	7400	< 0.37 U	5.9	65	0.34 J	0.16 J	970	9.1		7.9	20	17000
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated	6200	< 0.33 U	4.7	33	0.28 J	0.054 J	1700	8.0		5.6	18	14000
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated	7100	< 0.35 U	16	48	0.34 J	0.10 J	3900	9.1		7.0	20	16000
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated	7200	< 0.36 U	7.0	40	0.31 J	0.088 J	9000	9.9		6.0	21	17000
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated	6800	< 0.28 U	5.5	45	0.30 J	0.074 J	690	8.4		5.4	19	15000
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated	6200	< 0.33 U	5.5	38	0.28 J	0.066 J	2400	8.1		5.8	17	15000
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated	6200	0.44 J	5.8	36	0.30 J	0.082 J	1800	8.1		5.9	23	15000
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated	7400	< 0.32 U	8.0	67	0.38 J	0.10 J	2200	9.2		4.6	21	16000
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated	6200	< 0.35 U	4.3	38	0.25 J	0.068 J	1400	8.2		6.0	19	15000
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated	6300	0.42 JT	5.4	37	0.31 J	0.10 J	11000 T	8.0		6.4	31	15000
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated	8100	< 0.43 U	9.3	130	0.43 J	0.086 J	2100	10		6.3	21	16000
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated	7500	0.47 J	7.7	85	0.40 J	0.13 J	5800	9.5		6.8	37	18000
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated	7500	1.5 J	68	110	0.56	0.30 J	20000	25		9.8	430	47000
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	9800	< 0.40 U	5.9	120	0.39 J	< 0.054 U	1600	11		6.0	15	16000
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated	11000	< 0.37 U	6.8	92	0.44 J	0.058 J	1900	13		6.5	18	17000
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated	6500	< 0.32 U	5.4	47	0.22 J	0.12 J	30000	8.6		5.6	26	15000
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated	5400	< 0.32 U	15	120	0.44	0.24 J	3100	10		5.0	49	21000
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated	9500	< 0.37 UJ	6.2	59	0.38 J	< 0.049 U	320 J	11		6.0	15	17000
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated	6800	0.56 J	10	83	0.45	0.15 J	1900	19		6.9	35	32000
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated	8600	< 0.34 U	7.4	76	0.39 J	0.11 J	5100	10		6.7	23	17000
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated	7000	0.35 J-	5.7	50	0.29 J	0.057 J	560	8.7		5.8	16	15000 T
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	8800	< 0.28 U	6.4	66	0.41	0.094 J	1500	10		7.1	18	17000
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	8900	0.45 J	7.2	79	0.42 J	0.42 J	1500	26		8.5	1300	23000
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated	10000	< 0.37 U	6.7	57	0.44 J	0.072 J	1300	11		7.5	21	19000
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	5600	< 0.33 U	11	90	0.49	0.046 J	2600	7.6		8.9	35	18000
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	7000	< 0.34 U	4.9	96	0.32 J	0.50	1400	8.8		4.8 J	20	12000
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	6700	< 0.37 U	30	57	0.36 J	< 0.040 U	2300	9.2		4.8 J	20	18000
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	8200	1.1	7.6	99	0.41	0.15 J	1800	13		6.2	78	17000
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	9100	< 0.36 U	7.3	140	0.47	0.59	1900	11		5.7	26	18000
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	5900	0.85 JT	5.9	68	0.28 J	0.35 J	2200 T	28 T		6.4	120 T	21000
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	8500	0.52 J	4.7	92	0.36	0.036 J	1900	9.7		4.5	27	13000
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	8400	< 0.26 U	4.5	120	0.36	< 0.027 U	2000	8.7		5.0	9.3	12000
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	8500	< 0.31 U	7.7	83	0.40	0.064 J	1900	9.3		5.0	43	14000
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	8700	< 0.21 U	6.9	48	0.40	< 0.052 U	1100	10		6.0	17	20000
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	9200	< 0.19 U	6.4	43	0.35	< 0.046 U	1000	10		5.6	14	17000
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	6000	0.51 J	18	46	0.33	0.21 J	1700	9.0		6.8	43	18000
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	6400	< 0.20 U	6.3	42	0.29	0.058 J	1400	8.2		6.3	24	15000
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	6200	< 0.20 U	6.2	48	0.30	0.10 J	970	8.6		6.4	29	16000
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	8900	< 0.21 U	5.1	53	0.29	< 0.050 U	3600	9.1		5.2	23	13000
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	7100	< 0.23 U	6.8	54	0.32	0.11 J	1900	10		6.8	39	17000
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	4200	< 0.20 U	3.6	26	0.15 J	0.070 J	28000	5.1		4.1	15	9800
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	6400	0.29 J	7.0	47	0.30	0.46	1300	11		6.7	34	19000
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	6300	< 0.23 U	5.2	40	0.24 J	0.059 J	1500	7.8		5.9	31	14000
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	5800	< 0.27 UT	4.4	34 T	0.22 JT	< 0.066 U	14000	7.0 T		5.1	21 T	14000
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	9000	4.3	6.1	55	0.83	0.42	8500	19		9.6	1400	14000
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	6300	< 0.21 U	6.5	46	0.28	0.17 J	1100	9.5		6.3	40	16000
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	5000	< 0.20 U	5.8	50	0.27	0.15 J	3400	6.6		5.4	23	12000
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	6000	< 0.19 U	7.1	38	0.29	0.058 J	1000	7.2		5.8	18	13000
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	6000	< 0.23 U	5.0	49	0.28 J	< 0.055 U	560	7.5		5.6	18	14000
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	7300	< 0.25 UT	6.4	54	0.34	0.11 J	1500 T	9.3		6.0	28	14000
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	3100	0.24 J	5.8	92	0.25 J	0.33 J	5700	7.8		2.8 J	36	11000
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	5900	0.22 J	5.5	42	0.25 J	0.082 J	13000	7.4		5.4	24	14000
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	6700	0.27 J	5.4	51	0.31 J	0.081 J	2200	8.3		4.7	21	12000
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	7200	0.36 J	5.9	66	0.33	0.11 J	10000	9.2		5.3	22	14000
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	7500	< 0.32 U	5.9	37	0.30 J	< 0.077 U	820	7.8		5.5	21	15000
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	7600	< 0.22 U	5.0	26	0.35	< 0.053 U	700	8.5		5.1	17	17000
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	7600	< 0.25 U	5.3	48	0.28 J	< 0.060 U	19000	9.3		5.6	20	14000
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	11000	< 0.23 U	6.5	32	0.43	< 0.057 U	1200	12		7.2	16	18000
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	6300	0.29 J	5.6	29	0.29 J	0.14 J	1500	9.1		6.3	23	16000
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	8100	< 0.22 U	5.6	51	0.33	< 0.054 U	12000	9.2		6.2	18	16000
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	9800	< 0.24 U	6.1	31	0.39	< 0.057 U	1400	10		7.9	14	16000
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	6300	< 0.27 U	5.3	34	0.28 J	< 0.067 U	1300	7.0		4.8	18	13000
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	5900	< 0.24 U	4.6	48	0.24 J	< 0.057 U	4200	6.8		4.8	19	12000
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	5800	< 0.21 U	5.0	65	0.24 J	0.078 J	15000	6.9		4.6	19	12000
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	5300	< 0.30 U	3.5	38	0.22 J	< 0.073 U	16000	6.5		4.1 J	15	11000
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	4400	< 0.23 U	3.6	27	0.18 J	0.059 J	16000	5.3		4.1	13	11000
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	4800	0.30 J	4.9	26	0.23 J	0.63	1100	6.1		4.4	16	13000
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	4700	< 0.29 UT	5.1	25	0.23 J	< 0.070 U	1000	6.1		4.4 J	14	12000
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	7300	< 0.33 U	6.8	43	0.33 J	< 0.080 U	1100	9.4		5.4 J	20	17000
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	7700	0.35 J	6.7	49	0.34 J	< 0.075 U	2800	9.1		6.3	22	18000
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	7500	< 0.26 U	4.1	40	0.26 J	< 0.062 U	7700	7.8		4.5	16	14000
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	5800	< 0.24 U	4.4	28	0.22 J	< 0.058 U	2700	6.4		4.3	15	12000
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	7100	< 0.22 U	4.8	41	0.27 J	< 0.053 U	4900	7.8		4.5	14	13000
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	4000	< 0.26 U	3.5	28	0.16 J	0.095 J	44000	5.2		3.9 J	15	9500

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated	8.3	2400	850	0.033 J	20	710	< 0.48 U	< 0.082 U	< 64 U		0.42 J
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated	6.4	2400	330	0.023 J	15	510	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated	40	2700	340	< 0.020 U	16	820	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated	9.1	6400	360	< 0.023 U	16	680	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated	6.3	1800	280	0.026 J	15	610	< 0.36 U	< 0.062 U	< 48 U		< 0.31 U
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated	6.2	2800	340	< 0.022 U	14	730	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated	8.6	2300	430	< 0.020 U	15	580	0.89 J	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated	11	2200	650	0.027 J	15	650	< 0.41 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated	5.7	2100	360	< 0.017 U	15	500	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated	11	5900 T	370	0.027 J	15	620	0.60 J	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated	25	2000	610	0.067 J	15	460 J	0.63 J	< 0.097 U	< 75 U		0.54 J
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated	58	2500	430	3.9	18	560	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated	130	2600	550	0.058 J	220	620	1.3 J	0.23 J	120 J		< 0.38 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	18	1700	650	0.039 J	15	450 J	< 0.52 U	< 0.091 U	< 70 U		< 0.45 U
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated	18	2100	470	0.041 J	18	600	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated	8.9	8600	340	< 0.018 U	16	480	< 0.42 U	< 0.072 U	< 56 U		0.37 J
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated	41	1100	250	0.10 J	17	530	0.83 J	< 0.071 U	79 J		< 0.35 U
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated	9.1	2100	210 J-	< 0.020 U	16	510	0.72 J	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated	28	1800	480	0.054 J	24	470	0.68 J	< 0.072 U	< 56 U		0.43 J
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated	25	3200	510	0.073 J	18	540	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated	8.3 J-	1600	490 T	0.027 J	14	380 J	< 0.42 UJ	< 0.072 UJ	< 56 U		0.40 J
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	12	2400	410	0.032 J	18	750	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	45	2300	480	0.047 J	88	610	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated	12	2400	490	0.031 J	18	710	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	49	1200	310	0.17	16	420 J	0.83 J	< 0.10 U	< 58 U		< 0.31 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	18	1200	500	0.12	41	370 J	< 0.52 U	< 0.11 U	< 61 U		0.38 J
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	11	2000	240	0.043	12	490 J	1.5	< 0.11 U	< 66 U		0.50 J
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	87	1700	520	0.24	51	550	0.57 J	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	26	1700	640	0.049	45	430 J	0.72 J	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	110 T	1500	410	0.066 T	85 T	390 J	0.92 J	< 0.10 U	< 58 U		0.36 J
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	20	1600	430	0.066	15	420	0.56 J	< 0.079 U	< 45 U		< 0.24 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	14	1500	700	0.036	9.9	390	0.63 J	< 0.079 U	< 45 U		< 0.24 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	27	1600	420	0.078	13	470	0.88 J	< 0.096 U	< 55 U		< 0.29 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	12	2000	260	0.062	15	530	0.37 J	< 0.074 U	< 36 U		< 0.20 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	9.7	2100	210	0.054	14	500	< 0.29 U	< 0.066 U	< 32 U		< 0.18 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	36	2000	340	0.034	20	510	< 0.34 U	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	12	1800	350	0.15	14	530	< 0.30 U	< 0.067 U	< 33 U		< 0.18 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	23	1800	400	0.24	16	470	0.32 J	< 0.068 U	< 34 U		< 0.19 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	14	1700	330	0.045	13	370	0.64 J	< 0.071 U	88 J		< 0.19 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	23	2100	330	0.064	18	600	0.71 J	< 0.080 U	< 40 U		< 0.22 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	5.1	3700	300	< 0.015 U	10	400	0.33 J	< 0.070 U	43 J		< 0.19 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	24	2000	460	0.050	27	560	0.47 J	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	8.5	2100	370	0.025 J	15	470	< 0.35 U	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	6.6	3900 T	310 T	< 0.026 U	14	460 T	< 0.41 UT	< 0.093 UT	< 46 U		< 0.26 UT
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	130	3700	280	0.042	34	990	0.62 J	0.081 J	100 J		< 0.22 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	16	1700	320	0.058	25	440	0.47 J	< 0.073 U	< 36 U		< 0.20 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	12	2500	600	0.025 BJ	18	450	< 0.30 U	< 0.069 U	36 J		< 0.19 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	7.2	1900	440	0.048	15	500	< 0.29 U	< 0.065 U	< 32 U		< 0.18 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	8.1	1700	440	0.043	13	390	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	21 T	1800 T	400	0.077	24	380 JT	0.47 J	< 0.084 U	< 42 U		< 0.23 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	59	1000	100	0.058	14	260 J	< 0.33 U	< 0.074 U	94 J		< 0.20 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	14	6200	360	0.10	15	520	0.40 J	< 0.074 U	47 J		< 0.20 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	41	1600	280	0.26	12	510	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	36	2300	360	0.15	15	490	0.52 J	< 0.074 U	< 36 U		< 0.20 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	7.5	1900	460	< 0.023 U	12	500 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	6.0	2000	270	0.024 J	14	410	< 0.33 U	< 0.075 U	< 37 U		< 0.21 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	12	4200	250	0.055	23	510	0.50 J	< 0.084 U	43 J		< 0.23 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	8.7	2400	180	0.025	16	580	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	9.0	2300	370	0.048	18	580	< 0.35 U	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	14	3700	330	0.046	19	500	< 0.34 U	< 0.077 U	39 J		< 0.21 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	8.8	2200	220	0.033	15	510	0.49 J	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	7.5	1600	310	0.036	12	470	0.44 J	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	12	2000	290	0.034	12	440	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	17	2200	300	0.026 J	12	520	< 0.33 U	< 0.073 U	54 J		< 0.20 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	6.3	3500	260	< 0.015 U	11	600	< 0.46 U	< 0.10 U	57 J		< 0.28 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	4.5	2400	270	< 0.020 U	11	420	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	5.8	1700	560	< 0.022 U	11	390	< 0.36 U	< 0.080 U	< 40 U		< 0.22 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	5.8	1700	280	0.023 J	12	560 T	< 0.44 U	< 0.099 U	< 49 U		< 0.27 UT
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	9.2	2000	470	< 0.024 U	14	690	< 0.50 U	< 0.11 U	< 56 U		0.31 J
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	15	2300	540	< 0.019 U	16	600	< 0.47 U	< 0.11 U	< 52 U		0.38 J
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	9.4	4300	240	0.042	12	420	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	6.4	1800	270	0.021 J	11	390	< 0.36 U	< 0.082 U	< 40 U		< 0.22 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	7.5	2400	210	0.024	12	420	0.52 J	< 0.076 U	< 37 U		< 0.21 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	5.9	4600	310	< 0.018 U	11	370 J	0.43 J	< 0.089 U	44 J		< 0.24 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated		12	63
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated		9.8	50
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated		11	69
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated		12	65
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated		11	71
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated		10	47
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated		11	63
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated		13	130
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated		11	50
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated		11	55
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated		15	54
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated		13	72
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated		19	280
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated		16	46
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated		17	54
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated		9.4	110
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated		16	58
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated		15	44
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated		20	68
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated		13	65
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated		11	55
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated		15	59
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated		14	270
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated		15	60
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated		11	35
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated		12	220
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated		13	36
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated		14	120
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated		16	200
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated		13	620 T
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated		14	45
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated		12	36
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated		14	49
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated		16	46
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated		16	41
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated		12	120
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated		11	55
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated		12	70
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated		12	43
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated		13	66
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated		6.9	37
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated		13	170
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated		10	54
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated		10 T	51
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated		13	83
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated		11	75
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated		9.3	57
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated		9.1	47
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated		9.1	49
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated		12	88
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated		9.4	50
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated		9.6	57
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated		11	59
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated		11	61
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated		12	43
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated		12	51
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated		12	46
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated		17	43
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated		12	91
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated		12	45
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated		14	38
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated		9.3	48
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated		9.1	52
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated		9.3	58
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated		7.4	40
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated		6.5	32
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated		8.0	230
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated		8.2 T	38
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated		13	47
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated		13	75
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated		12	40
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated		8.8	40
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated		11	41
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated		6.5	53

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	4400	< 0.21 U	3.9	30	0.17 J	0.11 J	30000	5.5		4.2	14	10000
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	6100	< 0.22 U	5.0	50	0.26 J	0.068 J	8700	7.8		5.6	21	13000
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	6600	< 0.32 U	6.2	43	0.28 J	< 0.079 U	710	8.3		5.6	16	15000
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	8800	< 0.28 U	6.6	34	0.45	< 0.068 U	690	9.4		8.5	15	17000
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	8500	< 0.29 UT	5.4 T	36	0.41	< 0.070 UT	750	10 T		7.5	17	17000
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	10000	< 0.31 U	5.7	39	0.46	< 0.075 U	560	11		10	13	20000
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	7800	< 0.29 U	7.1	31	0.38 J	< 0.071 U	610	8.2		7.5	11	15000
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	6400	0.62 J	4.8	150	0.26 J	0.21 J	54000	7.8		4.6 J	18	11000
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	7100	0.39 J	5.7	79	0.29 J	0.087 J	23000	8.8		5.7	19	14000
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	6200	< 0.31 U	5.8	150	0.29 J	< 0.075 U	12000	7.2		5.7	17	13000
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	7800	< 0.28 U	5.7	51	0.28 J	0.11 J	1700	9.4		6.4	18	14000
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	8800	< 0.30 U	6.2	57	0.38 J	0.079 J	1200	10		6.3	15	16000
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	10000	0.46 J	3.9	150	0.41 J	< 0.083 U	1400	10		6.2	9.5	16000
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	7000	0.57 J	5.9	50	0.32 J	0.11 J	1600	9.3		6.1	24	16000
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	9100	< 0.29 U	5.8	49	0.38	< 0.070 U	960	11		6.6	16	17000
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	11000	< 0.39 U	6.9	65	0.44 J	< 0.093 U	1000	12		8.0	15	20000
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	8400	< 0.33 U	5.9	56	0.37 J	0.086 J	1200	9.7		6.0	16	16000
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	7300	0.38 JT	5.5	30 T	0.34 J	0.082 JT	640	8.4		6.0	15 T	15000
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	8500	< 0.37 U	4.4	69	0.31 J	< 0.090 U	1100	9.1		5.0 J	17	14000
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	7100	< 0.34 U	5.1	63	0.28 J	0.11 J	1200	8.3		5.8	13	15000
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	9100	0.53 J	6.7	36	0.40 J	< 0.080 U	780	10		7.3	18	18000
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	11000	0.45 J	7.1	50	0.41	< 0.069 U	630	10		7.3	11	18000
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	11000	0.62 J	8.9	130	0.55	0.20 J	3400	15		9.6	26	21000
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	7800	0.60 J	7.0	90	0.34 J	< 0.091 U	1700	9.3		5.3 J	21	15000
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	9700	< 0.32 UT	4.0	94 T	0.32 J	< 0.077 U	950 T	9.4		4.7 J	6.8	13000
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	7400	0.56 J	7.2	30	0.33 J	< 0.082 U	630	8.8		6.8	19	16000
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	10000	0.43 J	6.0	65	0.41 J	< 0.076 U	670	11		7.7	13	17000
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	6500	0.50 J	6.7	50	0.29 J	0.099 J	1500	8.4		5.3	20	14000
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	8800	0.40 J	5.8	37	0.35 J	< 0.070 U	610	9.0		5.9	12	16000
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	9000	0.38 J	6.1	95	0.36 J	< 0.071 U	620	9.5		5.2	11	14000
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	3900	< 0.30 U	2.9	23	0.13 J	< 0.073 U	28000	5.2		3.6 J	12	10000
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	7900	< 0.33 U	4.0	38	0.32 J	< 0.081 U	600	8.5		5.5	11	14000
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	6000	0.34 J	5.0	65	0.29 J	0.12 J	2300	8.9		4.6 J	25	14000
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	12000	< 0.35 U	4.3	80	0.44 J	< 0.085 U	400 J	11		7.6	9.6	16000
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	7600	0.30 J	6.6	130	0.43	0.19 J	12000	12		5.5	34	16000
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	10000	< 0.33 U	5.9	53	0.36 J	< 0.080 U	670	11		5.8	11	16000
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	6500	< 0.33 U	6.6	69	0.33 J	0.11 J	1100	12		6.1	27	15000
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	6100	< 0.32 U	5.4	64	0.31 J	0.090 J	5500	7.4		5.5	21	13000
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	6600	0.31 J	5.7	73	0.29 J	0.13 J	4200	9.2		5.1 J	25	14000
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	9400	< 0.35 UT	5.6 T	93 T	0.37 JT	0.11 JT	1700 T	11 T		6.1 T	26 T	16000
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	7000	< 0.32 U	3.9	44	0.27 J	< 0.077 U	860	7.5		4.4 J	14	13000
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	7800	0.45 J	4.9	39	0.28 J	< 0.076 U	1100	8.9		5.5	10	13000
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	6100	0.89	7.5	75	0.33 J	0.095 J	2000	11		5.1	53	16000
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	7700	0.36 J	5.8	82	0.32 J	0.15 J	2000	7.9		4.5 J	38	12000
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	11000	0.40 J	5.7	79	0.39 J	0.098 J	1700	12		6.0	16	16000
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	9300	0.44 JT	5.2 T	100 T	0.30 J	< 0.063 UT	1400 T	9.1 T		4.5 T	9.2 T	12000 T
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	10000	0.26 J	4.8	54	0.36	< 0.054 U	800	10		5.6	9.3	15000
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	5400	0.93 J	7.9	130	0.37 J	0.13 J	7600	12		5.4	56	22000
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	13000	0.39 J	5.5	47	0.43	< 0.073 U	1000	14		8.1	13	20000
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	8900	0.66 J	6.7	65	0.41	0.073 J	2700	11		6.3	26	17000
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	12000	0.35 J	7.3	44	0.46	< 0.078 U	530	12		7.7	23	19000
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	7900	0.54 J	6.1	27	0.34 J	< 0.072 U	500	8.2		5.5	17	15000
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	8400	0.54 J	5.8	52	0.35 J	< 0.073 U	1200	9.2		5.6	20	15000
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	6400	< 0.26 UT	5.2 T	33 T	0.27 JT	< 0.063 UT	1100 T	7.8 T		5.9	19 T	15000
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	5800	< 0.29 U	5.5	39	0.25 J	0.13 J	25000	6.9		4.8 J	25	13000
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	5300	< 0.30 U	4.5	35	0.21 J	0.087 J	17000	6.2		4.7 J	17	12000
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	7300	< 0.32 U	6.2	57	0.32 J	0.12 J	4400	8.5		5.7	24	15000
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	6800	< 0.32 U	5.5	50	0.30 J	< 0.078 U	920	8.6		6.2	23	16000
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	7300	0.50 J	7.2	160	0.36 J	0.20 J	9800	10		5.6	32	17000
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	8100	0.41 J	6.9	92	0.35 J	0.27 J	2300	8.6		4.5 J	23	13000
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	11000	< 0.35 U	5.8	140	0.40 J	0.094 J	1800	11		6.3	15	14000
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	8400	< 0.27 U	6.5	58	0.36	0.067 J	5100	9.7		5.6	16	15000
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	8600	0.38 J	5.7	39	0.38 J	< 0.074 U	760	9.8		7.1	16	16000
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	6600	< 0.30 U	4.9	40	0.28 J	< 0.072 U	890	7.8		5.0	19	13000
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	4300	< 0.26 U	3.9	22	0.19 J	< 0.062 U	2100	5.5		3.4 J	17	9600
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	5500	< 0.26 U	4.6	36	0.24 J	< 0.062 U	530	6.8		5.1	16	12000
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	5600	< 0.28 U	4.8	55	0.2 J	0.11 J	24000	9.1		4.7	15	13000
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	7200	< 0.29 U	7.2	52	0.29 J	0.16 J	1300	9.0		6.0	22	16000
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	5400	< 0.28 U	5.5	59	0.23 J	0.21 J	1100	7.3		4.7	20	13000
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	3800	0.20 J	4.1	31	0.20 J	0.087 J	1900	4.8		3.7	12	9600
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	2600	< 0.27 UT	2.9	18	0.13 JT	< 0.064 UT	2500 T	3.5		2.2 J	8.0	6100
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	5600	< 0.29 U	4.3	40	0.22 J	0.090 J	16000	6.9		4.8	15	12000
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	6900	< 0.29 U	5.4	69	0.31 J	0.12 J	4300	9.6		5.9	18	15000 B
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	5900	1.3	4.9	38	0.25 J	0.087 J	6000	8.3		5.1	52	14000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	4.6	3800	270	< 0.014 U	11	400	0.42 J	< 0.071 U	39 J		< 0.19 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	11	3600	410	0.023 J	14	510	0.35 J	< 0.074 U	< 36 U		< 0.20 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	7.9	1900	270	0.030	14	600	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	8.7	2300	450	< 0.024 U	16	590	0.54 J	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	8.9	2500	250	0.030 J	17	640 T	< 0.44 UT	< 0.099 UT	< 49 U		< 0.27 UT
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	11	2700	230	0.033 J	18	700	0.49 J	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	6.8	2200	460	< 0.016 U	14	520	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	52	3900	350	0.053	12	590	1.0	< 0.10 U	210 J		< 0.28 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	27	5700	350	0.066	14	700	0.60 J	< 0.10 U	87 J		< 0.28 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	20	2300	420	0.054	12	590	0.76 J	< 0.11 U	86 J		< 0.29 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	12	2200	600	0.044	14	580	0.54 J	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	15	1900	390	< 0.023 U	13	520	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	12	1700	1000	< 0.026 U	12	580	< 0.52 U	< 0.12 U	< 58 U		0.42 J
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	22	1700	350	< 0.022 U	16	570	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	14	2100	240	< 0.025 U	15	570	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	17	2600	350	< 0.027 U	16	760	< 0.59 U	< 0.13 U	< 65 U		< 0.36 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	19	1900	370	< 0.023 U	13	540 J	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	7.8 T	1900 T	340	< 0.022 U	14	580 T	< 0.44 UT	< 0.098 UT	< 48 U		< 0.27 UT
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	14	1800	330	< 0.026 U	12	500 J	< 0.56 U	< 0.13 U	< 63 U		< 0.35 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	49	1800	430	0.14	12	430 J	< 0.52 U	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	12	2200	310	0.069	15	630	< 0.50 U	< 0.11 U	< 56 U		0.31 J
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	8.1	2000	400	0.027	14	520	< 0.43 U	< 0.097 U	< 48 U		0.34 J
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	38	3000	560	0.070	23	1300	0.69 J	< 0.12 U	73 J		< 0.34 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	99	1600	540	0.10	12	550 J	0.60 J	< 0.13 U	< 63 U		< 0.35 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	7.7 T	1600	390	0.044 T	10	760	< 0.48 UT	< 0.11 UT	< 54 U		< 0.30 UT
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	8.4	1900	330	0.029	14	580	< 0.52 U	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	9.0	2300	390	< 0.021 U	15	630	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	17	1900	370	0.11	13	580	< 0.49 U	< 0.11 U	< 54 U		0.32 J
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	7.9	2000	380	0.042	15	510	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	21	1600	420	0.062	11	460 J	0.81 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	5.2	3100	230	0.024	9.1	340 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	7.0	1800	270	0.039	13	520 J	< 0.51 U	< 0.11 U	< 57 U		< 0.31 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	25	1500	330	0.072	12	420 J	< 0.48 U	< 0.11 U	< 54 U		0.32 J
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	11	2100	650	0.026 J	14	560 J	< 0.53 U	< 0.12 U	< 59 U		0.46 J
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.90	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	100	2300	330	0.27	18	700	< 0.46 U	< 0.10 U	130 J		< 0.28 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	9.5	2000	320	0.044	12	510 J	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	50	1500	320	0.076	19	480 J	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	29	1500	460	0.081	12	430 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	35	1800	340	0.089	14	490 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	36 T	2000 T	440	0.072	16 T	570 JT	< 0.53 UT	< 0.12 UT	< 59 UT		< 0.33 UT
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	9.9	1600	270	0.038	11	380 J	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	7.7	1800	250	0.027 J	11	410 J	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	54	1400	250	0.070	15	480	< 0.40 U	< 0.091 U	45 J		0.32 J
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	18	1600	480	0.078	11	420 J	< 0.51 U	< 0.12 U	< 57 U		0.39 J
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	28	2300	410	0.080	14	640	< 0.53 U	< 0.12 U	< 59 U		< 0.33 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	11 T	1500 T	450 T	0.092 T	11 T	510	< 0.40 UT	< 0.090 U	45 J		< 0.24 UT
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	7.1	2100	220	< 0.024 U	13	540	< 0.34 U	< 0.077 U	47 J		< 0.21 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	41	2800	210	0.079	17	520	1.1	< 0.10 U	72 J		< 0.28 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	9.7	3100	220	0.033	17	950	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	30	2000	350	0.074	15	680	< 0.44 U	< 0.10 U	85 J		< 0.27 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	11	2500	470	0.021 J	17	800	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	8.6	2000	370	0.025 J	14	570	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	28	2000	340	0.049	15	570	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	7.4 T	2100 T	340	< 0.020 U	15	490 T	< 0.40 UT	< 0.089 UT	< 44 UT		< 0.24 UT
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	14	4700	300	< 0.021 U	13	540	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	7.0	7800	410	< 0.018 U	12	500	0.47 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	8.9	3500	410	0.10	15	740	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	7.9	2100	420	< 0.018 U	16	570	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	66	2500	320	0.44	20	690	0.49 J	< 0.11 U	200 J		< 0.30 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	31	1600	440	0.13	12	500 J	< 0.52 U	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	66	1900	640	0.59	14	670	< 0.53 U	< 0.12 U	< 59 U		< 0.33 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	13	3400	360	0.048	14	520	0.60 J	< 0.093 U	56 J		< 0.25 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	9.7	2000	400	0.036	14	570	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	8.8	1800	320	0.029	12	560	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	5.0	1600	230	0.024	8.5	430	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	14	1500	360	0.028 J	14	420 J	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	7	5900	420	0.025	12	610	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	7.3	2100	660	< 0.022 U	15	740	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	6.5	1500	1700	< 0.022 U	14	590	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	5.4	1100	440	< 0.022 U	9.5	420	< 0.25 U	< 0.057 U	< 28 U		< 0.16 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	3.8	1400 T	220 T	< 0.022 U	5.3	380 J	< 0.40 UT	< 0.091 UT	50 JT		< 0.25 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	8.4	3300	320	< 0.022 U	12	780	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	25	2400	290 B	0.51	15	560	< 0.44 U	< 0.098 U	54 J		< 0.27 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	24	2200	460	0.082	12	600	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated		6.9	51
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated		10	47
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated		10	45
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated		13	42
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated		12	44
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated		15	43
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated		11	36
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated		10	120
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated		12	70
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated		10	60
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated		12	47
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated		14	43
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated		15	46
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated		13	51
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated		15	41
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated		17	48
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated		14	49
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated		12	37 T
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated		13	41
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated		11	65
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated		15	45
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated		15	50
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated		14	82
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated		12	56
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated		14	42
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated		12	41
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated		14	49
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated		10	52
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated		13	48
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated		14	42
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated		5.3	31
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated		9.9	37
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated		10	50
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated		15	44
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated		14	98
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated		15	42
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated		12	50
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated		10	46
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated		12	56
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated		15 T	59 T
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated		11	39
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated		11	39
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated		11	59
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated		9.4	77
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated		14	80
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated		13 T	41 T
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated		14	45
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated		13	57
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated		16	52
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated		14	58
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated		16	68
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated		10	45
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated		12	49
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated		10 T	47 T
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated		9.5	61
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated		8.5	41
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated		12	83
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated		11	55
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated		14	110
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated		14	170
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated		15	97
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated		12	51
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated		14	41
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated		11	43
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated		7.3	32
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated		8.0	35
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated		8.5	43
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated		11	58
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated		9.2	39
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated		6.1	35
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated		4.5	26 T
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated		8.3	51
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated		11	68
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated		11	53

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	7900	0.52 JT	6.9 T	66 T	0.34 JT	0.14 JT	15000	9.6 T		5.9 T	36 T	16000 B
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	6200	0.85 J	7.7	82	0.33 J	0.41 J	19000	26		5.7	46	18000 B
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	8100	< 0.30 U	6.4	34	0.35 J	< 0.072 U	1400	8.9		6.7	17	16000
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	6700	0.68 J	5.6	53	0.32	0.094 J	2200	8.8		5.5	28	15000
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	7000	< 0.20 U	7.7	33	0.31	0.069 J	780	8.9		6.1	19	15000
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	6200	< 0.27 U	5.9	29	0.27 J	< 0.065 U	990	7.2		5.6	17	14000
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	5100	0.53 J	3.3	32	0.20 J	< 0.073 U	1100	5.6		3.3 J	7.2	8600
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	7300	0.46 J	6.5	70	0.30 J	0.16 J	12000	9.5		6.1	35	16000
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	6800	4.2	7.1	55	0.31 J	0.16 J	6800	9.3		5.5	57	16000
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	8600	0.40 J	6.1	35	0.36	0.073 J	2600	9.6		7.2	17	16000
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	8100	0.44 J	4.9	270	0.35 J	0.15 J	1800	9.4		4.5 J	16	16000
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	5300	4.3	23	110	0.57	0.44 J	7100	100		20	450	67000
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	5700	0.76 J	6.2	71	0.40	0.22 J	9600	8.3		6.0	30	21000
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	3200	0.33 J	2.9	27	0.24 J	< 0.065 U	1300	4.1		2.9 J	11	15000
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	4000	0.79 J	7.5	60	0.31 J	0.20 J	4400	10		5.3	31	15000
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	5500	1.8 T	14 T	92 T	0.57 T	0.37 JT	6800 T	39 T		7.1 T	51 T	37000 T
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	2700	0.94 J	2.0	9.6 J	< 0.11 U	< 0.073 U	210 J	3.2		2.1 J	7.1	5400 B
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	8800	< 0.33 U	5.3	21 J	0.34 J	< 0.079 U	590	9.6		6.8	9.7	15000 B
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	3000	< 0.33 U	2.2	11 J	< 0.12 U	< 0.080 U	210 J	3.8		2.3 J	5.4	6300 B
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	9800	< 0.34 U	6.3	34	0.41 J	< 0.081 U	730	11		7.0	11	16000 B
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	8000	0.45 J	6.5	62	0.35 J	0.097 J	2700	9.4		6.2	19	16000 B
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	7200	0.56 J	7.1	82	0.37 J	0.12 J	6200	10		5.7	31	15000 B
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	6400	< 0.64 U	13	190	0.28 J	0.50 J	14000	16		8.1	40	86000 B
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	7200	0.42 J	6.0	91	0.38 J	0.16 J	12000	12		5.7	40	15000 B
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	8300	0.92 J	6.7	86	0.37 J	0.16 J	9100	12		6.5	45	19000 B
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	9300	0.40 J	7.0	89	0.41 J	0.13 J	2700	11		7.5	17	17000
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	4400	< 0.27 U	4.0	36	0.17 J	0.088 J	27000	6.6		4.1 J	15	10000
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	4400	< 0.25 U	3.2	27	0.17 J	0.064 J	19000	5.3		3.8 J	9.7	10000
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	6900	< 0.55 U	6.3	55	0.35 J	< 0.13 U	1000	8.9		5.8	18	14000
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	5500	< 0.29 U	5.1	26	0.24 J	0.070 J	7600	7.1		4.8	15	13000
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	4200	< 0.28 U	3.7	26	0.18 J	0.084 J	41000	5.2		3.7 J	12	9700
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	4600	< 0.26 U	5.5	23	0.20 J	0.088 J	30000	7.0		4.3	14	12000
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	4700	0.31 J	3.9	28	0.18 J	0.070 J	24000	5.7		4.2	14	12000
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	6700	< 0.28 U	5.8	41	0.30 J	0.080 J	780	8.2		5.7	23	15000
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	5800	< 0.27 U	5.6	45	0.28 J	0.094 J	5500	7.2		4.7	18	14000
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	5800	0.36 BJ	5.1	43	0.24 J	0.063 J	2600	6.6		3.8 J	16	11000
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	7200	0.38 BJ	5.9	39	0.30 J	< 0.077 U	880	8.1		4.3 J	20	14000
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	6100	0.48 BJ	4.8	45	0.26 J	0.067 J	1500	7.6		5.1	16	12000
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	7200	0.45 BJ	4.8	36	0.29 J	< 0.076 U	540	8.2		5.7	24	14000
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	6400	0.40 BJ	5.4	42	0.26 J	0.088 J	610	7.1		4.5 J	14	12000
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	7200	< 0.28 U	4.4	24	0.27 J	< 0.068 U	520	7.9		4.4 J	15	13000
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	6100	0.42 BJ	6.0	36	0.23 J	< 0.069 U	470	6.8		4.1 J	12	11000
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	7000	0.28 BJ	5.2	42	0.29 J	0.066 J	630	8.0		5.1	24	13000
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	5900	0.32 BJ	6.8	36	0.25 J	0.072 J	960	6.9		4.5	15	12000
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	5900	0.44 J	7.0	45	0.26 J	< 0.073 U	1500	7.0		4.3 J	17	12000
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	5300	0.45 J	4.0	29	0.22 J	0.078 J	930	6.4		4.2	16	12000
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	4300	0.46 J	4.3	28	0.22 J	0.074 J	740	5.4		4.6 J	13	10000
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	4200	0.33 J	2.9	40	0.17 J	0.059 J	1500	4.7		4.5	9.1	9400
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	7100	0.56 J	5.1	180	0.28 J	< 0.077 U	780	8.2		4.8 J	17	13000
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	8900	1.4 J	8.5	62 J	< 0.48 U	< 0.32 U	1200 J	11		6.2	22	17000
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	7300	< 0.31 U	6.1	45	0.31 J	< 0.076 U	1100	9.5		5.7	20	15000
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	5700	0.32 J	4.3	42	0.24 J	0.076 J	3200	6.7		4.2 J	15	11000
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	5800	0.30 J	4.4	36	0.24 J	< 0.064 U	640	6.4		4.6	15	11000
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	6200	0.44 J	4.6	37	0.23 J	< 0.073 U	510	7.2		4.9 J	15	12000
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	6100	0.45 J	5.3	38	0.25 J	0.085 J	3100	7.0		4.3 J	18	12000
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	7000	2.7	8.1	91	0.32 J	0.34 J	7500	10 B		5.1	54	14000 B
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	5300	< 0.31 U	5.7	31	0.23 J	0.094 J	930	6.8		4.8 J	33	14000
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	5200	< 0.26 U	5.7	31	0.26 J	0.11 J	1100	6.9		5.3	16	13000
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	6000	< 0.30 U	6.2	32	0.27 J	0.091 J	990	7.9		5.5	20	15000
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	6400	< 0.27 U	5.9	42	0.27 J	0.068 J	720	7.6		5.3	18	14000
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	6100	< 0.29 U	5.4	49	0.27 J	0.12 J	1300	7.3 B		5.5	22	12000 B
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	8600	< 0.31 U	6.1	79	0.33 J	0.11 J	3500	9.8 B		4.7 J	23	14000 B
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	8300	0.38 J	11	50	0.38 J	0.13 J	700	9.0 B		5.8	28	18000 B
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	6700	1.6	8.2	110	0.30 J	0.28 J	13000	10 B		5.1	45	14000 B
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	7600	< 0.28 U	6.3	34	0.32 J	0.070 J	590	8.3 B		4.6 J	24	14000 B
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	6100	< 0.26 U	4.5	30	0.24 J	0.11 J	760	7.2 B		4.5	16	12000 B
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	6800	0.42 J	6.0	79	0.30 J	0.11 J	2800	8.1 B		4.7 J	21	12000 B
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	6800 T	0.36 JT	5.9	47 T	0.30 J	0.073 J	500	7.6 B		5.2	15	13000 B
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	6600	< 0.30 U	5.8	84	0.29 J	0.41 J	6500	8.8 B		4.5 J	22	13000 B
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	6500	< 0.28 U	14	250	0.36 J	0.42 J	5300	11 B		4.8	21	15000 B
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	5300	< 0.29 U	3.2	24	0.19 J	0.14 J	39000	5.8		4.6 J	16	12000
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	6900	< 0.28 U	7.4	69	0.33 J	< 0.069 U	870	8.3		5.4	30	16000
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	5600	< 0.29 U	4.4	49	0.25 J	< 0.070 U	660	6.9		4.7	16	14000
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	6100	< 0.33 U	5.2	49	0.26 J	0.082 J	730	7.8		5.1 J	20	15000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	36 T	3100 T	400 WARN	0.33 T	16 T	790 T	0.78 JT	< 0.11 UT	75 JT		< 0.29 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	150	3600	340 T	0.52	22	590	1.2	< 0.11 U	65 J		< 0.30 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	17	2100	320	0.054	15	520	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	55	1800	450	0.066	13	460	0.46 J	< 0.082 U	< 40 U		< 0.22 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	17	1700	450	0.045	15	580	< 0.30 U	< 0.069 U	< 34 U		< 0.19 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	9.9	1700	360	0.034 J	14	540	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	10	1200	190	0.079	7.4	360 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	56	2900	580	0.29	15	640	0.97	< 0.096 U	47 J		< 0.26 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	240	2200	410	0.13	13	610	< 0.45 U	< 0.10 U	53 J		< 0.28 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	22	2200	350	0.062	15	640	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	22	1400	710	0.10	10	490 J	0.55 J	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	130	2000	520	0.32	53	500 J	4.4	0.13 J	90 J		< 0.30 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	39	4000	300	0.092	20	480 J	0.96 J	< 0.10 U	64 J		< 0.28 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	10	870	81	0.25	150	280 J	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	31	2200	230	0.24	87	440 J	1.2	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	130 T	2100 T	290 T	0.25	20 T	640 T	3.0 T	< 0.10 UT	79 JT		< 0.28 UT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	7.3	630	130	0.030 J	4.3	170 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	6.6	2200	140	< 0.024 U	14	550	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	5.3	680	94	0.086	4.9	180 J	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	13	2200	230	0.044	15	680	< 0.51 U	< 0.12 U	< 57 U		< 0.31 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	94	2000	360	0.66	15	610	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	83	1800	390	4.4	22	590	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	83	2100	670	0.92	31	550	< 0.48 U	0.13 J	67 J		0.57 J
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	49	2300	340	1.2	52	600	< 0.52 U	1.5	63 J		< 0.32 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	42	2200	290	1.6	22	570	< 0.44 U	0.42 J	54 J		< 0.27 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	29	2400	400	0.21	17	860	< 0.51 U	< 0.12 U	< 57 U		< 0.31 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	3.8	3500	260	< 0.019 U	12	490	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	3.9	3400	170	< 0.020 U	9.7	390 J	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	9.3	1800	520	0.025	14	770 J	< 0.84 U	< 0.19 U	< 93 U		< 0.26 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	6.6	3500	360	0.024 J	13	540	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	5.0	8000	260	< 0.019 U	9.4	540	< 0.43 U	< 0.096 U	50 J		< 0.26 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	6.5	11000	340	< 0.016 U	10	640	0.62 J	< 0.089 U	58 J		< 0.24 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	5.7	3900	270	< 0.013 U	10	440	< 0.38 U	< 0.085 U	48 J		< 0.23 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	9.3	1800	420	0.028	16	520	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	7.5	4000	550	< 0.020 U	13	540	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	16	1800	320	0.074	10	500	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	8.4	1600	230	0.028	13	700	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	7.3	1800	320	0.027	13	610	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	7.4	1900	390	0.032	14	520	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	5.9	1500	350	0.027 J	12	600	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	5.7	1900	220	0.030	12	540	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	7.6	1500	240	0.038	11	470	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	8.2	1600	300	0.035	14	550	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	11	1600	330	0.032 J	12	520	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	16	1600	500	0.042	11	540	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	5.5	1600	290	0.019 J	11	440	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	5.9	1200	460	0.021 J	12	460 J	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	5.3	1400	340	0.035	8.8	410	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	13	1700	460	0.033 J	13	650	< 0.49 U	< 0.11 U	140 J		< 0.30 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	11	2100 J	490	0.042	14	830 J	< 2.0 U	< 0.45 U	< 220 U		< 0.25 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	8.0	2200	460	0.024 J	15	760	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	16	1900	460	0.034	10	500	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	6.7	1600	290	0.023 J	12	630	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	14	1700	390	0.038	12	520	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	20	2400	290	0.10	11	580	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	190	2000	440	0.12	14	590	< 0.38 U	< 0.086 U	49 J		< 0.24 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	7.0	1700	340	< 0.022 U	12	570	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	7.6	1700	610	< 0.022 U	13	710	< 0.40 U	< 0.089 U	48 J		< 0.24 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	7.5	1800	340	< 0.021 U	14	630	< 0.46 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	8.2	1900	310	0.064	13	530	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	35	1600	410	0.072	11	580	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	140	1800	220	0.17	14	570	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	18	1600	590	0.070	14	670	< 0.46 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	470	2000	330	0.18	13	590	< 0.44 U	< 0.10 U	54 J		< 0.27 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	6.9	1700	240	0.026	13	650	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	8.7	1500	280	0.045	10	530	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	30	2000	390	0.064	11	660	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	8.6	1700	410 T	0.025	13	710 T	< 0.42 U	< 0.094 U	47 J		< 0.26 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	66	1800	300	0.11	11	610	0.60 J	< 0.10 U	110 J		< 0.28 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	330	1400	270	0.075	12	720	0.56 J	< 0.096 U	160 J		< 0.26 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	7.1	2100	330	0.023 J	12	440 J	< 0.44 U	< 0.10 U	95 J		< 0.27 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	9.9	1700	430	0.040	15	600	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	8.7	1800	360	0.052	12	490	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	7.2	1700	400	0.28	12	510 J	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated		13 T	58 T
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated		17	250
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated		12	58
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated		13	60
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated		12	47
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated		9.4	52
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated		7.3	28
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated		12	70
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated		14	84
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated		13	61
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated		12	66
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated		42	93
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated		12	120
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated		6.8	21
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated		12	67
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated		25 T	140
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated		5.0	13
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated		12	36
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated		6.5	16
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated		14	66
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated		13	84
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated		13	100
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated		8.3 J	150
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated		13	110
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated		14	120
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated		13	64
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated		7.0	29
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated		6.0	38
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated		13	49
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated		9.7	58
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated		7.3	30
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated		11	33
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated		9.2	63
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated		11	47
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated		9.5	39
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated		9.2	49
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated		12	45
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated		10	44
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated		12	55
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated		10	39
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated		11	46
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated		9.9	34
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated		12	57
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated		9.4	43
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated		9.7	46
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated		8.6	50
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated		7.6	35
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated		6.4	28
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated		11	41
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated		15 J	55
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated		12	54
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated		8.9	41
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated		8.5	35
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated		9.5	43
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated		9.8	56
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated		10	140
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated		9.5	41
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated		8.5	43
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated		11	44
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated		10	44
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated		9.5	50
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated		14	69
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated		13	84
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated		10	130
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated		11	43
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated		9.4	38
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated		11	57
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated		10	39 T
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated		10	75
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated		15	140
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated		7.3	46
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated		11	43
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated		8.2	52
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated		9.9	44

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	6100	< 0.31 U	7.3	26	0.26 J	0.23 J	3400	7.8		6.2	17	16000
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	5600	< 0.28 U	4.9	27	0.25 J	0.13 J	2700	7.3		5.4	17	13000
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	6800	< 0.31 U	5.0	36	0.27 J	0.11 J	6700	8.3		5.4	21	15000
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	5200	< 0.27 U	4.9	36	0.28 J	0.19 J	4200	6.3		5.1	16	14000
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	6200	< 0.30 U	4.4	54	0.25 J	0.11 J	4200	7.1		5.5	19	14000
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	6100	0.35 J	6.3	52	0.26 J	0.22 J	11000	7.7		4.8	23	12000
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	7200	< 0.29 U	7.4	52	0.34 J	0.11 J	2300	8.3		4.9	21	16000
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	5300	< 0.30 UT	4.2	26	0.21 J	0.077 J	2000 T	6.3		4.5 J	16	12000
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	5300	< 0.29 U	5.7	32	0.25 J	0.088 J	1100	6.8		4.3 J	17	12000
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	5700	< 0.30 U	6.0	35	0.24 J	0.083 J	990	6.8		4.6 J	16	14000
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	7100	< 0.34 U	8.3	49	0.34 J	0.12 J	1300	11		7.1	23	18000
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	5700	0.36 J	9.2	37	0.28 J	0.15 J	2700	7.6		6.1	22	18000
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	6500	2.0	88	62	0.55	0.66	2500	46		11	170	28000
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	7300	< 0.29 U	7.3	59	0.34 J	0.14 J	1600	8.9		6.8	19	16000
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	7600	0.34 J	5.3	65	0.28 J	0.11 J	1600	10		6.4	24	17000
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	4600	< 0.22 U	10	34	0.19 J	0.12 J	29000	5.9		7.6	17	12000
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	5600	< 0.29 U	4.7	35	0.26 J	< 0.071 U	660	7.0		4.4 J	18	13000
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	7300	< 0.30 U	6.4	79	0.33 J	0.13 J	4300	8.8		5.9	21	16000
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	7400	< 0.25 U	5.7	37	0.33	0.084 J	610	8.1		5.8	20	16000
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	5800	< 0.27 U	5.4	50	0.27 J	0.17 J	4100	8.3		4.9	23	13000
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	5500	< 0.26 U	5.3	30	0.26 J	0.10 J	2600	7.5		5.5	15	13000
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	5900	< 0.27 U	7.4	47	0.32 J	0.14 J	12000	7.9		5.8	18	15000
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	6200	< 0.28 U	6.5	38	0.30 J	0.090 J	1100	7.0		4.5 J	16	13000
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	4200	< 0.26 U	3.7	24	0.17 J	0.14 J	46000	5.4		4.0 J	15	10000
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	4700	< 0.31 U	4.2	26	0.21 J	0.11 J	15000	5.9		4.5 J	18	11000
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	4500	< 0.29 U	5.4	21	0.21 J	0.14 J	34000	5.7		4.3 J	14	11000
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	4600	< 0.26 U	4.4	21	0.19 J	0.12 J	28000	5.8		4.2 J	14	11000
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	5500	< 0.33 U	4.8	30	0.23 J	0.13 J	39000	6.4		5.0 J	15	13000
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	6800	< 0.29 U	6.8	46	0.30 J	0.11 J	5600	8.4		5.7	18	15000
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	6300	0.36 J	7.8	43	0.29 J	0.12 J	1200	8.8		6.0	28	17000
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	5700	< 0.28 U	5.5	30	0.25 J	0.10 J	19000	6.9		5.2	16	13000
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	5600	< 0.28 U	5.9	35	0.27 J	0.14 J	4400	7.0		4.7	16	13000
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	4200	< 0.23 U	3.7	29	0.18 J	< 0.055 U	680	4.9		2.2 J	11	7500
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	7100	< 0.26 U	5.6	58	0.32 J	0.21 J	6900	11		6.1	20	15000
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	6500	< 0.28 U	17	61	0.30 J	0.26 J	4800	8.1		6.1	20	18000
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	7000	< 0.30 U	5.4	62	0.31 J	0.13 J	7200	8.4		5.6	23	16000
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	8300	< 0.29 U	7.3	160	0.39	0.19 J	3400	11		6.8	23	18000
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	5200	0.34 J	4.5	37	0.23 J	0.086 J	10000	7.0		3.6 J	28	10000
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	4200	0.31 J	4.0	13 J	0.19 J	< 0.054 U	340 J	4.8		2.8 J	9.6	8300
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	4900	< 0.28 U	3.6	33	0.21 J	0.11 J	14000	6.0		4.1 J	15	11000
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	6300	< 0.34 U	6.2	38	0.27 J	< 0.081 U	1000	7.8		5.0 J	18	14000
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	4500	< 0.21 U	4.5	25	0.20 J	0.082 J	920	5.7		4.0	13	10000
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	2900	< 0.25 U	2.3	26	0.12 J	0.080 J	17000	3.7		2.8 J	10	6700
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	3600	< 0.24 U	3.2	22	0.16 J	0.064 J	2900	4.2		2.9 J	10	8000
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	5700	< 0.27 U	4.7	43	0.23 J	0.093 J	8900	7.6		5.2	15	12000
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	5300	< 0.30 U	4.8	29	0.24 J	0.10 J	12000	6.3		4.5 J	17	13000
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	5200	0.33 J	5.7	36	0.26 J	0.12 J	3000	6.6		4.4 J	16	13000
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	4800	< 0.27 U	3.8	24	0.21 J	0.070 J	600	5.8		3.8 J	18	12000
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	4700	0.40 J	5.0	32	0.23 J	0.067 J	660	6.0		3.8 J	14	12000
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	7500	< 0.31 U	6.9	65	0.32 J	0.17 J	4000	9.4		5.8	20	16000
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	5800	< 0.30 U	5.2	26	0.23 J	0.11 J	1400	8.0		6.0	20	15000
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	5700	< 0.28 UT	5.7	32	0.26 J	0.13 J	4400 T	7.3		5.5	15	14000
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	7100	0.31 J	6.9	40	0.31 J	0.13 J	1500	8.9		6.4	19	16000
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	6900	< 0.29 U	5.9	43	0.29 J	0.15 J	3400	8.7		5.7	20	15000
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	6500	< 0.27 U	5.4	44	0.28 J	0.14 J	3700	8.2		5.1	20	15000
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	6800	< 0.28 U	5.4	45	0.28 J	0.17 J	17000	8.8		6.1	20	19000
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	5200	< 0.28 U	4.9	30	0.22 J	0.12 J	6200	6.8		4.8	15	12000
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	5800	< 0.28 U	4.3	35	0.23 J	0.14 J	17000	7.0		5.4	17	13000
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	10000	< 0.31 U	7.6	56	0.45	0.52	2200	14		10	23	22000
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	11000 B	0.34 J	6.2	44	0.41	0.11 J	870	12		6.9	14	18000
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	8700 B	< 0.30 U	5.8	35	0.33 J	0.11 J	1500	9.8		6.1	17	16000
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	6000	< 0.30 UT	5.9 T	39 T	0.24 JT	< 0.072 UT	12000 T	7.2 T		5.9	20 T	21000
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	6700	< 0.30 U	7.3	58	0.32 J	0.17 J	6700	9.2		5.8	30	25000
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	5300	< 0.31 U	5.2	26	0.22 J	< 0.076 U	11000	6.7		5.2	15	13000
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	7700	< 0.29 U	6.8	55	0.34 J	< 0.070 U	4900	9.2		6.0	23	16000
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	8300	< 0.32 U	6.5	55	0.32 J	< 0.078 U	1100	9.4		5.2 J	16	15000
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	7400	0.50 J	10	100	0.38 J	13	6200	55		6.9	63	18000
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	4300	< 0.28 U	5.4	22	0.18 J	< 0.067 U	640	6.2		2.8 J	13	10000
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	2300 T	< 0.17 UT	1.9 T	14 T	0.099 JT	< 0.042 UT	270 JT	3.0 T		1.7 JT	5.7 T	5100 T
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	5400	< 0.24 U	5.3	35	0.21 J	< 0.057 U	850	7.6		4.3	15	12000
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	5000	< 0.28 U	3.6	44	0.20 J	< 0.069 U	2700	7.5		3.6 J	17	11000
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	4900	< 0.25 U	4.9	25	0.22 J	< 0.060 U	1600	6.5		3.5 J	13	12000
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	6700	< 0.29 U	6.9	54	0.31 J	< 0.069 U	5600	8.3		5.9	20	16000
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	5500	< 0.28 U	4.2	31	0.20 J	0.071 J	19000	7.3		4.5 J	14	13000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	7.4	3400	390	0.026 J	15	630	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	6.6	2100	380	0.047	14	570	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	7.8	2700	290	0.031 J	13	630	< 0.47 U	< 0.11 U	67 J		< 0.29 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	6.2	3300	930	0.024 J	14	520	< 0.41 U	< 0.092 U	84 J		< 0.25 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	17	2400	270	0.055	14	550	< 0.45 U	< 0.10 U	50 J		< 0.28 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	32	2500	420	0.14	13	630	< 0.43 U	< 0.097 U	78 J		< 0.26 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	8.2	1900	750	0.036	14	680	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	6.7	2000	370 T	0.024 J	12	580 T	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	6.7	1600	410	0.034 J	11	510 B	< 0.44 U	< 0.10 U	110 BJ		< 0.27 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	6.2	1600	400	0.035	12	550 B	< 0.46 U	< 0.10 U	58 BJ		< 0.29 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	11	2300	490	0.045	16	1000 B	< 0.52 U	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	11	2500	460	0.039	17	590 B	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	290	1600	290	1.3	30	600	2.9	0.46 J	51 J		< 0.27 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	16	2000	550	0.046	14	590	< 0.44 U	< 0.098 U	53 J		< 0.27 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	9.5	2600	310	0.048	15	660	< 0.44 U	< 0.099 U	62 BJ		< 0.27 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	10	5100	290	< 0.021 U	14	450	< 0.34 U	< 0.076 U	72 J		< 0.21 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	7.7	1600	330	< 0.021 U	11	430 J	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	150	2400	380	0.15	16	580	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	12	2000	460	0.26	15	500	< 0.38 U	< 0.086 U	49 J		< 0.24 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	51	2200	340	0.17	13	440 J	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	7.8	2100	330	< 0.021 U	13	540	< 0.40 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	13	3300	600	0.029	15	690	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	6.6	1600	210	< 0.021 U	13	700	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	5.2	4300	240	< 0.011 U	10	450	< 0.39 U	< 0.088 U	62 J		< 0.24 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	5.5	4100	280	< 0.018 U	11	570	< 0.46 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	5.3	8700	300	< 0.015 U	11	580	< 0.44 U	< 0.099 U	73 J		< 0.27 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	5.2	7400	300	< 0.016 U	11	600	< 0.40 U	< 0.091 U	65 J		< 0.25 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	6.4	5500	310	< 0.023 U	13	630	< 0.50 U	< 0.11 U	64 J		< 0.31 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	11	3400	430	< 0.015 U	14	690	< 0.43 U	< 0.098 U	180 J		< 0.27 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	9.9	1800	330	< 0.020 U	15	730	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	6.5	7200	290	< 0.015 U	12	710	< 0.43 U	< 0.096 U	64 J		< 0.26 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	14	2600	320	0.032	12	690	< 0.43 U	< 0.097 U	71 J		< 0.27 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	4.0	1200	160	< 0.016 U	6.0	450	< 0.35 U	< 0.079 U	< 39 U		< 0.21 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	29	3200	370	0.038	15	740	< 0.40 U	< 0.089 U	72 J		< 0.24 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	23	2600	630	0.034	15	700	< 0.43 U	< 0.096 U	86 J		< 0.26 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	24	3200	410	0.045	14	850	< 0.46 U	< 0.10 U	120 J		< 0.28 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	37	2600	410	0.042	17	650	< 0.45 U	< 0.10 U	55 J		< 0.28 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	55	2800	220	0.12	13	500 J	< 0.50 U	< 0.11 U	64 J		< 0.31 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	4.4	960	110	< 0.023 U	7.1	400	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	5.7	3300	280	0.019 J	11	440 J	< 0.43 U	< 0.098 U	54 J		< 0.27 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	8.0	1700	320	0.027 J	13	540 J	< 0.51 U	< 0.12 U	< 57 U		< 0.31 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	5.4	1500	230	0.016 J	10	430	< 0.32 U	< 0.073 U	48 J		< 0.20 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	3.3	1900	190	< 0.012 U	7.0	380 J	< 0.38 U	< 0.086 U	48 J		< 0.23 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	6.9	2200	270	0.022	7.1	330 J	< 0.36 U	< 0.081 U	< 40 U		0.27 J
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	7.1	4000	300	0.045	13	580	< 0.41 U	< 0.092 U	48 J		< 0.25 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	9.0	5800	310	0.028	11	600	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	8.9	1800	380	< 0.019 U	11	570	< 0.48 U	< 0.11 U	58 J		< 0.29 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	7.4	1300	220	< 0.013 U	10	410 J	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	5.8	1200	270	0.031	9.9	450	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	19	2600	400	0.054	14	690	< 0.47 UT	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	6.9	2200	330	< 0.022 U	14	560	< 0.45 UT	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	7.5	3200 T	390	0.019 J	13	610	< 0.43 UT	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	10	2200	430	0.021 J	15	690	< 0.45 UT	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	18	2800	390	0.038	15	580	< 0.45 UT	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	140	2800	400	0.11	13	600	< 0.42 UT	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	13	4000	540	0.58	16	600	< 0.42 UT	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	12	3200	350	0.031	12	530	< 0.42 UT	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	6.7	3600	320	0.029 J	12	590	< 0.42 UT	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	12	4100	500	0.029 J	26	1300	< 0.48 U	< 0.11 U	67 J		< 0.29 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	9.4	2600	220	< 0.021 U	17	600	< 0.42 U	< 0.096 U	47 J		< 0.26 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	7.7	2400	240	< 0.017 U	15	640	0.46 J	< 0.10 U	64 J		< 0.28 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	9.7	4000	340	0.23 T	14	540	< 0.45 UT	< 0.10 UT	< 50 UT		< 0.28 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	66	2400	360	0.16	16	510	0.58 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	6.0	2500	330	< 0.020 U	13	650	0.59 J	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	16	2100	360	0.062	15	620	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	14	1800	410	0.044	13	580	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	170	2900	400	0.41	23	730	1.3	0.72	70 J		< 0.30 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	5.0	980	160	0.019 J	8.2	450 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	3.7 T	630 T	100 T	0.027 J	4.3 T	220 JT	< 0.27 UT	< 0.060 UT	< 30 UT		< 0.16 UT
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	6.8	1400	290	0.026	10	650	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	39	1600	200	0.11	12	400 J	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	5.6	1600	280	0.025 J	8.8	570	< 0.37 U	< 0.084 U	< 42 U		< 0.23 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	16	3000	600	0.047	14	670	< 0.43 U	< 0.098 U	< 48 U		0.27 J
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	11	3900	390	0.068	12	610	< 0.43 U	< 0.096 U	51 J		< 0.26 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated		11	140
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated		9.5	48
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated		10	45
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated		8.9	48
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated		11	54
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated		9.6	83
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated		12	59
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated		8.1	41
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated		9.9	40
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated		9.0	44
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated		18	52
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated		9.7	61
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated		47	370
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated		11	94
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated		15	68 B
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated		7.8	41
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated		8.6	90
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated		11	71
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated		10	47
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated		8.9	70
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated		8.7	47
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated		11	49
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated		10	45
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated		6.9	39
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated		7.8	41
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated		7.4	46
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated		8.0	42
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated		8.5	48
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated		12	57
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated		15	63
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated		9.8	48
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated		11	57
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated		6.9	32
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated		11	67
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated		12	85
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated		11	63
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated		14	100
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated		9.3	46
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated		7.6	22
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated		8.1	39
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated		11	42
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated		7.3	34
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated		4.8	26
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated		6.4	34
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated		8.8	38
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated		9.5	39
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated		9.5	47
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated		9.2	41
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated		10	35
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated		12	71
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated		9.7	47
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated		9.0	45
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated		11	57
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated		11	57
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated		10	60
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated		11	79
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated		8.0	49
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated		8.3	84
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated		16	170
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated		16	42
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated		13	44
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated		9.5 T	58 T
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated		13	92
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated		9.0	43
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated		13	50
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated		13	47
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated		15	340
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated		8.9	39
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated		4.2 T	17 T
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated		12	37
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated		8.4	39
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated		12	35
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated		11	61
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated		9.8	48

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	6500	< 0.29 U	9.2	47	0.28 J	< 0.071 U	8400	7.8		5.5	25	16000
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	6000	< 0.28 U	6.4	38	0.26 J	< 0.068 U	2500	11		5.8	16	15000
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	5100	< 0.29 U	4.5	43	0.21 J	< 0.071 U	12000	6.3		4.9	14	13000
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	4600	< 0.28 U	4.4	27	0.20 J	< 0.068 U	43000	5.9		4.3 J	16	11000
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	6800	< 0.27 U	4.4	41	0.25 J	< 0.066 U	6900	8.2		6.4	15	15000
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	7900	< 0.29 U	6.6	58	0.34 J	< 0.071 U	2700	9.6		5.8	20	16000
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	6500	< 0.28 U	6.3	56	0.29 J	< 0.067 U	5100	8.1		5.3	24	15000
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	8000	< 0.29 U	6.6	67	0.35 J	< 0.069 U	4800	10		7.4	22	18000
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	4300	< 0.28 U	3.3	39	0.19 J	0.10 J	20000	6.3		3.8 J	12	9000
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	7200	< 0.29 U	5.6	39	0.28 J	< 0.069 U	6200	8.6		7.0	32	17000
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	6300	< 0.28 U	5.4	31	0.27 J	< 0.067 U	4800	8.1		5.2	17	15000
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	5600	< 0.24 U	5.7	30	0.26 J	0.066 J	2000	7.5		5.3	18	15000
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	5800	< 0.29 U	6.0	28	0.26 J	< 0.070 U	2500	7.7		5.3	16	14000
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	6600	< 0.30 U	7.6	39	0.29 J	< 0.073 U	4300	8.3		5.9	18	16000
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	5600	< 0.28 U	5.4	42	0.25 J	0.070 J	12000	7.7		5.4	18	14000
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	5800	< 0.27 U	6.6	38	0.25 J	< 0.065 U	4600	7.5		5.9	16	14000
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	3100	< 0.29 U	3.3	20	0.13 J	< 0.070 U	35000	4.4		3.0 J	11	7800
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	5000	< 0.29 U	4.5	30	0.22 J	< 0.070 U	20000	6.4		4.6 J	17	12000
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	6900	< 0.24 U	5.7	41	0.31 J	0.097 J	3200	8.1		5.1	18	14000
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	8100	< 0.24 U	4.2	41	0.29 J	< 0.058 U	690	8.7		4.9	11	13000
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	4200	0.41 J	5.9	110	0.35 J	0.077 J	980	7.6		4.0 J	20	33000 B
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	6200	0.30 J	4.7	50	0.24 J	< 0.070 U	2400	7.9		4.3 J	14	12000 B
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	6400	0.54 J	6.7	69	0.28 J	< 0.070 U	1400	8.0		4.2 J	22	16000 B
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	4600	1.5	30	77	0.20 J	0.10 J	1300	13		4.1 J	380	30000 B
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	5500	< 0.30 U	6.7	65	0.26 J	< 0.072 U	2400	26		5.3	96	21000 B
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	4300	< 0.27 U	2.9	42	0.15 J	< 0.066 U	12000	4.8		2.6 J	9.0	7100
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	4700	< 0.27 U	3.4	31	0.20 J	< 0.065 U	1300	5.6		3.1 J	13	9100
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	7400	0.49 J	5.1	64	0.30 J	< 0.081 U	14000	8.2		4.1 J	15	11000
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	9700	0.59 J	7.2	78	0.41	< 0.067 U	2600	11		5.8	17	14000
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	11000	0.59 J	7.1	57	0.44	< 0.061 U	2100	12		8.8	23	19000
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	11000	0.32 J	8.0	51	0.44	< 0.071 U	7200	12		6.4	20	17000
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	5500	< 0.26 U	4.9	27	0.23 J	< 0.063 U	1200	7.7		4.7	14	13000
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	7800	0.29 J	8.2	53	0.33 J	< 0.070 U	2600	10		7.3	17	18000
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	4700	< 0.37 U	6.5 J	54	0.27 J	0.071 J	1700	6.8		6.6	15	15000
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	4300	< 0.33 U	9.5 J	140	0.33 J	0.31 J	2000	6.8		6.8	13	18000
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	6400	< 0.31 U	6.1	48	0.33 J	0.073 J	8000	8.4		6.2	22	16000
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	5900	< 0.37 U	6.8	37	0.25 J	0.17 J	35000	7.9		5.3	18	13000
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	7400	< 0.36 U	6.1	50	0.33 J	0.052 J	590	9.3		7.3	19	17000
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	11000	< 0.32 UT	6.7	45	0.47	< 0.042 U	550	11		9.2	21	20000
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	9700	< 0.44 U	6.5	70	0.47 J	< 0.059 U	2300	13		5.9	21	26000
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	6700	< 0.30 U	6.4	34	0.33 J	0.066 J	3000	8.7		6.0	20	16000
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	6600	< 0.33 U	5.7	35	0.27 J	0.072 J	24000	8.5		6.2	21	16000
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	8300	< 0.34 U	10	100	0.42 J	0.10 J	590	10		10	23	21000
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	7300	< 0.27 U	7.1	45	0.34 J	0.074 J	5600	9.4		6.8	21	17000
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	10000	< 0.34 U	6.3	51	0.44 J	< 0.045 U	1000	11		7.4	18	18000
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	8300	< 0.34 U	3.6	94	0.29 J	< 0.046 U	420 J	9.7		8.0	36	16000
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	8000	< 0.35 U	5.4	36	0.35 J	0.052 J	1500	10		6.2	19	16000
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	5100	< 0.34 U	5.5	29	0.25 J	0.074 J	6000	7.0		5.3	17	14000
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	6000	< 0.37 U	5.3	22	0.26 J	0.073 J	2700	7.6		5.9	20	16000
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	6700	< 0.32 U	6.4	34	0.28 J	0.088 J	19000	8.8		7.3	23	16000
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	6200	< 0.32 U	6.6	55	0.30 J	0.39 J	3000	8.8		7.5	24	16000
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	7100	< 0.35 U	5.6	44	0.32 J	0.069 J	1500	9.6		6.1	23	16000
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	6700	< 0.36 U	6.1	39	0.30 J	0.075 J	1100	8.9		6.0	22	16000
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	8000	< 0.37 U	5.3	92	0.38 J	< 0.049 U	350 J	9.4		7.9	23	15000
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	9800	< 0.38 U	7.4	29	0.49 J	< 0.051 U	780	12		11	17	18000
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	7700	< 0.33 UT	6.9	52	0.44 J	0.15 J	2300 T	10		7.8	24	17000
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	10000	< 0.44 U	7.2	31	0.52 J	< 0.058 U	660	11		8.6	16	20000
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	14000	< 0.39 U	6.1	50	0.59	< 0.052 U	800	14		10	11	21000
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	14000	< 0.42 U	7.4	41	0.59	< 0.057 U	650	16		11	17	23000
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	11000	< 0.38 U	5.7	61	0.44 J	< 0.051 U	760	12		6.5	8.5	17000
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	11000	< 0.41 U	7.4	60	0.50 J	< 0.054 U	4300	14		8.4	19	19000
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	12000	< 0.32 U	7.6	30	0.52	< 0.042 U	850	13		8.9	16	20000
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	8400	< 0.32 U	6.5	36	0.40 J	< 0.042 U	1100	10		7.1	18	17000
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	7900	< 0.37 U	8.2	170	0.43 J	0.21 J	9800	11		7.0	31	17000 B
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	11000	< 0.42 U	11	110	0.47 J	< 0.056 U	1900	11		6.7	14	17000 B
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	8700	< 0.42 U	8.3	110	0.49 J	0.14 J	6300	12		7.6	32	18000 B
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	7100	< 0.39 U	6.6	39	0.37 J	< 0.053 U	1800	9.7		6.3	19	16000 B
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	12000	< 0.37 U	7.8	47	0.54	< 0.049 U	1200	14		9.2	15	21000 B
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	8500	< 0.41 U	8.3	120	0.49 J	0.17 J	15000	15		7.2	43	19000 B
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	7800	< 0.28 U	6.1	71	0.33 J	0.10 J	1500	10		6.5	24	17000
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	11000	< 0.35 U	4.2	72	0.36 J	0.051 J	820	11		5.1	9.5	14000
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	8200	< 0.28 U	6.4	67	0.36 J	0.083 J	920	8.5		8.6	27	13000
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	7500	< 0.40 UT	8.1	91	0.41 J	0.18 J	2200	10		5.9	38	15000
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	8600	< 0.34 U	2.8	120	0.32 J	0.054 J	1300	8.7		4.0	7.5	12000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	12	4500	890	< 0.019 U	14	730	< 0.45 U	< 0.10 U	< 50 U		0.49 J
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	6.8	3200	300	< 0.015 U	15	660	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	5.9	7500	350	< 0.019 U	13	490	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	7.5	24000	340	0.075	11	600	< 0.43 U	< 0.096 U	92 J		< 0.26 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	6.1	3300	450	< 0.021 U	16	570	< 0.41 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	24	2400	450	0.064	15	840	< 0.45 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	19	2700	550	0.027	14	680	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	15	3300	610	0.021 J	18	770	< 0.43 U	< 0.098 U	< 48 U		0.32 J
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	7.8	3000	360	< 0.019 U	9.3	430 J	< 0.43 U	< 0.098 U	89 J		< 0.27 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	8.6	3300	490	< 0.010 U	17	780	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	7.9	2800	320	0.012 J	13	690	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	8.8	2000	490	0.017	13	680	< 0.36 U	< 0.082 U	< 41 U		< 0.22 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	7.8	2100	340	0.013 J	13	660	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	11	2600	440	0.032	14	650	0.58 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	15	4200	460	0.092	14	610	< 0.42 U	< 0.096 U	55 J		< 0.26 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	16	2400	440	0.017	14	610	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	7.8	8700	240	0.030	7.6	420 J	< 0.44 U	< 0.099 U	55 J		< 0.27 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	6.6	5900	320	< 0.0098 U	12	540	< 0.44 U	< 0.099 U	51 J		< 0.27 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	75	2000	270	0.16	13	510	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	7.1	1600	200	0.024 J	11	500	< 0.36 U	< 0.082 U	72 J		< 0.22 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	43	710	170	0.061	12	460	0.79 J	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	19	1600	290	0.35	17	530	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	36	1300	310	0.13	9.7	510	0.76 J	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	320	660	250	0.11	75	760	1.2	< 0.10 U	690		0.86 J
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	52	1300	400	0.041	90	490	0.45 J	< 0.10 U	99 J		< 0.28 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	13	1600	240	0.43	9.6	340 J	< 0.41 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	16	1100	250	1.3	7.7	390 J	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	31	2100	330	0.075	10	560	0.66 J	< 0.11 U	64 J		< 0.31 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	32	1800	360	0.028	13	660	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	18	2900	820	0.035	18	780	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	14	2700	410	0.051	18	1100	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	5.9	1800	240	0.012 J	12	600	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	7.9	2600	330	0.0092 J	17	960	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	45	1700	2700	< 0.020 U	15	590	< 2.4 U	< 0.084 U	< 65 U		< 2.1 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	320	1500	9800	< 0.021 U	16	450 J	< 8.7 U	< 0.075 U	< 58 U		< 7.4 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	6.0	2500	400	< 0.021 U	17	560	< 0.40 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	6.9	20000	940	< 0.017 U	15	820	< 0.49 U	< 0.084 U	83 J		< 0.42 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	7.6	2100	390	0.020 J	18	590	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	8.9	2500	460	0.021 J	19	620	< 0.42 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	17	2100	300	0.034 J	20	620	< 0.58 U	< 0.10 U	110 J		< 0.49 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	6.7	3000	380	< 0.023 U	17	610	< 0.40 U	< 0.069 U	< 53 U		< 0.34 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	6.6	8800	330	< 0.019 U	16	690	< 0.43 U	< 0.075 U	64 J		< 0.37 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	17	1900	2300	0.044 J	18	800	< 0.90 U	< 0.077 U	< 60 U		< 0.76 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	10	3300	540	0.030 J	18	630	< 0.35 U	< 0.061 U	52 J		< 0.30 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	9.1	2400	440	0.028 J	19	620	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	6.3	2200	360	< 0.021 U	18	390 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	11	2200	270	0.026 BJ	16	480 J	< 0.46 U	< 0.079 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	6.5	2200	420	< 0.018 U	14	530	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	6.1	2300	330	< 0.018 U	15	560	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	8.9	5000	390	< 0.021 U	18	740	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	10	2500	1700	0.026 BJ	20	560	< 0.84 U	< 0.072 U	< 56 U		< 0.71 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	7.4	2300	500	< 0.020 U	17	590	< 0.46 U	< 0.079 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	9.0	2100	450	0.023 BJ	16	600	< 0.47 U	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	7.6	1700	340	0.026 BJ	20	730	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	10	2400	310	0.041 J	28	580	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	12	2300	420	0.094 J	21	670	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	9.0	2400	420	0.029 J	17	580 J	< 0.57 U	< 0.099 U	< 76 U		< 0.49 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	10	2800	370	0.038 J	18	700	< 0.51 U	< 0.088 U	100 J		< 0.44 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	11	3500	300	0.029 J	30	870	< 0.55 U	< 0.096 U	77 J		< 0.47 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	7.8	2300	150	0.078 J	16	530	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	20	3000	380	0.068 J	44	700	< 0.53 U	< 0.091 U	71 J		< 0.45 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	9.1	2700	220	0.048 J	27	630	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	11	2200	300	0.038 J	27	510	< 0.41 U	< 0.072 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	100	3000	500	0.37	21	680	< 0.48 U	< 0.083 U	84 J		< 0.41 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	21	2100	650	0.026 J	14	560 J	< 0.55 U	< 0.095 U	< 74 U		< 0.47 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	76	2200	530	0.25	21	730	< 0.55 U	< 0.095 U	120 J		< 0.47 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	12	2000	360	0.020 J	16	580	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	9.9	2800	210	< 0.021 U	18	710	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	71	2600	460	0.48	22	750	< 0.54 U	< 0.093 U	97 J		< 0.46 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	30	2100	470	0.054 J	17	580	< 0.36 U	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	6.4	1800	180	< 0.024 U	12	470 J	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	19	1500	580	0.068 J	17	460	< 0.37 U	< 0.064 U	< 49 U		< 0.31 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	64 T	1600	390	0.13 J	17	640	0.61 J	< 0.090 U	83 J		< 0.44 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	7.1	1400	470	0.023 J	9.5	380 J	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated		11	64
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated		10	52
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated		8.1	40
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated		8.2	36
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated		9.2	53
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated		13	59
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated		11	61
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated		13	59
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated		7.3	59
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated		12	64
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated		11	46
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated		10	45
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated		11	48
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated		11	55
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated		10	59
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated		11	49
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated		6.0	29
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated		8.5	46
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated		11	68
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated		13	40
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated		12	75
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated		9.7	38
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated		12	42
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated		9.5	200
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated		9.9	87
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated		6.2	28
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated		7.7	34
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated		11	48
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated		15	60
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated		17	60
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated		17	47
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated		11	39
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated		12	45
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated		10	48
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated		9.1	48
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated		11	63
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated		11	82
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated		13	68
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated		15	59
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated		20	48
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated		12	94
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated		12	56
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated		15	110
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated		13	82
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated		16	52
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated		13	53
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated		12	52
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated		9.4	46
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated		11	73
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated		12	64
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated		13	130
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated		12	59
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated		12	57
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated		14	69
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated		15	51
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated		14	78
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated		15	50
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated		19	55
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated		19	60
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated		15	43
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated		16	61
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated		17	52
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated		14	58
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated		14	200 B
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated		16	49 B
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated		15	95 B
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated		13	55 B
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated		19	52 B
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated		16	100 B
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated		12	60
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated		15	45
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated		11	56
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated		13	69
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated		11	40

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	6900	0.51 J	6.5	88	0.37 J	0.28 J	1500	13		5.5	66	16000
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	6900	< 0.33 U	7.8	110	0.42 J	0.18 J	2800	31		6.5	200	19000
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	7000	< 0.40 U	4.9	69	0.30 J	0.087 J	1300	7.8		4.8	15	13000
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	6500	< 0.35 U	4.4	65	0.30 J	0.073 J	1100	7.9		5.2	28	13000
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	7400	0.35 J	8.6	120	0.37 J	0.20 J	2800	41		6.6	130	23000
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	7900	< 0.33 U	4.4	67	0.38 J	0.058 J	810	8.5		5.7	22	13000
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	9300	0.42 J	8.1	110	0.43 J	0.15 J	2300	20		7.7	74	20000
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	7600	< 0.33 U	10	76	0.34 J	0.14 J	1700	9.4		5.9	33	15000
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	8000	< 0.36 U	4.8	75	0.33 J	0.094 J	1500	9.7		4.9	27	14000
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	10000	< 0.32 U	3.3	120	0.36 J	0.052 J	1100	11		5.2	8.3	13000
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	8900	0.73 J	8.6	88	0.44 J	0.23 J	3600	60		9.9	740	28000
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	8400	11	9.1	110	0.36 J	0.17 J	1800	16		5.6	62	16000
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	7700	< 0.32 U	5.8	73	0.33 J	0.10 J	2400	11		6.3	36	16000
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	9200	< 0.35 U	6.1	49	0.43 J	< 0.047 U	2200	11		8.2	28	19000
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	10000	< 0.39 U	7.6	67	0.45 J	< 0.052 U	4300	11		7.3	18	18000
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	11000	< 0.32 U	7.1	35	0.48	< 0.043 U	880	12		8.6	17	20000
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	8500	< 0.39 U	8.0	48	0.39 J	< 0.052 U	930	9.9		7.9	20	19000
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	8500	< 0.35 UT	6.3 T	42 T	0.39 JT	< 0.046 UT	1600 T	9.8 T		7.1 T	20 T	17000
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	7100	< 0.33 U	4.5	61	0.28 J	0.17 J	23000	9.0		6.1	20	16000 B
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	7500	< 0.32 U	6.2	40	0.32 J	0.065 J	720	9.1		6.7	22	15000 B
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	6600	< 0.36 U	4.9	46	0.27 J	0.10 J	1100	8.4		5.6	18	14000 B
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	7000	< 0.32 U	6.4	55	0.31 J	0.16 J	1900	9.0		5.7	20	14000 B
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	5900	0.35 J	7.4	56	0.30 J	0.34 J	1800	9.3		5.1	140	11000 B
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	7300	< 0.33 U	4.4	47	0.25 J	0.11 J	34000	9.1		6.1	18	15000 B
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	10000	0.38 J	6.0	64	0.42 J	0.082 J	2300	11		7.6	16	18000
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	4400	0.38 J	4.2	27	0.30 JT	0.095 J	55000	5.8		4.4	16	11000
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	7100	< 0.27 U	5.1	40	0.29 J	0.11 J	4400	9.0		5.9	20	16000
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	6100	< 0.31 U	5.4	30	0.26 J	0.070 J	700	7.5		6.5	16	14000
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	7900	< 0.31 U	6.2	50	0.36 J	0.067 J	670	8.8		7.0	17	17000
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	10000	< 0.31 U	5.3	55	0.41 J	0.059 J	900	11		7.2	13	18000
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	8800	0.42 J	6.5	31	0.38 J	0.063 J	320 J	9.7		7.2	17	18000
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	7400	< 0.36 U	7.2	110	0.33 J	0.21 J	9300	11		6.4	32	16000
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	6700	< 0.34 U	4.9	55	0.28 J	0.13 J	940	8.1		6.1	21	15000
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	7800	0.42 J	11	91	0.38 J	0.30 J	7200	12		6.5	40	18000
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	7500	< 0.38 UT	6.1	52 T	0.35 J	0.087 J	960	8.9		6.4	18	16000
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	6700	< 0.37 U	5.1	39	0.28 J	0.18 J	11000	8.6		5.6	22	15000
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	10000	0.43 J	8.3	80	0.51	0.062 J	3400	13		9.8	32	23000
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	6300	< 0.37 U	5.9	58	0.32 J	0.071 J	950	7.7		5.8	18	15000
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	6900	< 0.30 U	5.4	39	0.32 J	0.049 J	810	8.1		6.5	18	14000
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	7600	0.57 J	5.0	44	0.36 JT	0.059 J	1100	9.0		6.8	20	16000
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	6200	0.33 J	5.9	38	0.33 JT	0.12 J	870	7.6		5.9	20	15000
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	8100	1.6 J	12	350	0.52	0.89	12000	38		10	290	33000
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	7700	< 0.38 U	6.0	53	0.37 JT	0.082 J	1200	9.3		7.3	19	16000
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	8300	0.43 J	8.5	64	0.41 JT	0.081 J	2700	15		7.5	36	17000
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	6000	< 0.37 UT	6.2	43 T	0.35 J	0.089 J	12000 T	7.5 T		5.0	17	14000
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	4400	< 0.32 U	4.0	22	0.12 J	0.070 J	45000	6.2		5.0	17	11000
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	8600	< 0.32 U	7.7	60	0.39 J	0.051 J	590	10		8.2	20	19000
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	7100	< 0.35 U	8.7	76	0.52	0.18 J	1500	9.9		5.8	26	15000
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	12000	< 0.39 U	5.8	44	0.44 J	< 0.052 U	540	12		7.4	14	18000
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	12000	< 0.36 U	5.9	47	0.43 J	< 0.049 U	800	13		7.0	14	19000
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	10000	0.45 J	5.0	58	0.39 J	0.058 J	1100	11		6.8	13	17000
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	8900	< 0.36 U	6.5	34	0.42 J	< 0.049 U	1000	10		7.1	19	18000
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	7200	< 0.35 U	5.6	34	0.35 J	< 0.046 U	650	7.9		5.7	14	15000
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	9800	< 0.32 U	4.2	51	0.41 J	< 0.043 U	580	10		7.1	13	15000
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	6400	< 0.37 U	5.7	43	0.31 J	0.050 J	1100	8.3		6.4	19	15000
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	8600	< 0.38 U	7.1	47	0.39 J	< 0.051 U	2300	10		8.2	21	19000
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	8800	< 0.33 U	7.2	40	0.40 J	< 0.044 U	940	11		7.6	20	19000
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	8300	< 0.36 U	6.3	59	0.35 J	< 0.048 U	490 J	9.4		6.9	21	18000
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	11000	< 0.40 UT	6.0	65	0.47 J	< 0.053 U	590	12		9.4	18	21000
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	8900	< 0.37 U	6.0	38	0.40 J	< 0.049 U	690	9.6		7.1	15	16000
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	5900	< 0.26 UT	5.8	34	0.28 J	0.052 J	680	7.4		5.9	17	14000
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	5600	< 0.36 U	6.3	39	0.27 J	0.075 J	1900	7.5		5.8	18	14000
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	8100	< 0.34 U	5.6	55	0.30 J	0.17 J	14000	14		6.0	24	25000
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	7900	< 0.37 U	6.3	77	0.35 J	0.49 J	1700	20		7.3	48	41000
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	7200	< 0.39 U	7.4	41	0.37 J	0.064 J	1400	9.2		6.5	20	18000
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	6300	< 0.31 U	5.0	32	0.27 J	0.055 J	6800	7.5		5.5	19	14000
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	6400	< 0.40 U	6.5	37	0.30 J	0.085 J	1100	8.3		6.3	19	16000
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	6700	< 0.26 U	6.4	44	0.32 J	0.056 J	980	8.1		6.0	20	15000
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	6400	< 0.33 U	8.7	45	0.35 J	0.17 J	1100	8.6		6.5	22	18000
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	4500	< 0.30 U	6.0	28	0.25 J	0.060 J	920	6.4		4.7	13	13000
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	9100	0.52 J	6.7	78	0.40 J	0.094 J	3300	12		8.3	27	20000
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	9200	< 0.36 U	9.7	75	0.45 J	0.18 J	8100	13		9.8	28	25000
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	9600	< 0.28 U	7.6	30	0.46	0.098 J	200 J	11		11	28	18000
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	11000	< 0.38 UT	7.2	29	0.46 J	< 0.051 U	250 J	11		10	15	20000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	63	1600	310	0.063 J	27	550	< 0.49 U	< 0.085 U	110 J		< 0.42 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	36	1600	430	0.12	49	560	0.43 J	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	21	1500	500	0.055 J	11	410 J	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	26	1500	470	0.082 J	14	460 J	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	140	1800	450	0.15	52	510	0.47 J	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	17	1500	360	0.040 J	13	420 J	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	96	1900	680	0.096 J	41	580	< 0.48 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	49	1800	460	0.096 J	15	570	< 0.43 U	< 0.074 U	63 J		< 0.36 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	26	1700	460	0.079 J	13	430 J	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	7.6	1700	530	< 0.021 U	11	410 J	< 0.42 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	65	2200	620	0.14	170	510	0.98 J	< 0.076 U	64 J		< 0.37 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	270	1800	490	0.13	34	550 J	< 0.54 U	< 0.093 U	< 72 U		< 0.46 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	33	2000	480	0.050 J	18	630	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	16	2800	510	0.045 J	19	650	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	15	2400	360	0.077 J	160	640	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	8.9	2600	280	< 0.020 U	18	720	< 0.42 U	< 0.072 U	< 56 U		< 0.36 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	8.5	2300	410	0.024 J	18	750	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	15 T	2200 T	430 T	0.043 J	17 T	680 T	< 0.45 UT	< 0.078 UT	< 61 UT		< 0.39 UT
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	6.5	3300	440	< 0.020 U	16	620	< 0.43 U	< 0.074 U	< 58 U		< 0.37 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	8.1	1900	390	0.029 J	16	470	< 0.42 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	7.1	1900	340	0.026 J	14	520	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	7.9	2100	2200	0.019 J	15	610	< 0.84 U	< 0.073 U	< 56 U		< 0.71 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	35	1500	320	0.047 J	17	400 J	0.40 J	< 0.069 U	66 J		< 0.34 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	5.4	3700	310	< 0.020 U	16	720	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	16	2500	280	0.034 J	16	680	< 0.46 U	< 0.079 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	5.9	12000	390	0.020 J	12	490	< 0.42 U	< 0.072 U	66 J		< 0.35 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	6.6	4000	330	0.022 J	17	510	< 0.36 U	< 0.062 U	55 J		< 0.30 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	6.8	1700	380	0.031 J	14	500	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	8.2	2100	390	0.025 J	16	530	< 0.41 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	8.3	2400	350	0.023 J	15	650	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	8.7	2400	320	< 0.020 U	17	650	< 0.45 U	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	140	2300	550	0.25	18	570	< 0.47 U	< 0.081 U	70 J		< 0.40 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	7.3	2200	700	< 0.021 U	16	600	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	300	2300	420	0.10	21	690	< 0.50 U	< 0.086 U	67 J		< 0.42 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	9.5	2000	430 T	0.022 J	15	510 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	8.1	8000	760	< 0.018 U	15	600	< 0.49 U	< 0.084 U	66 J		< 0.42 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	14	3100	470	0.077 J	22	840	< 0.39 U	< 0.068 U	< 52 U		0.38 J
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	13	1800	590	0.027 J	14	540	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	7.3	1700	360	0.033 J	14	610	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	10	2000	470	0.030 J	16	560	< 0.42 U	< 0.072 U	< 56 U		< 0.36 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	12	1700	700	0.028 J	14	570	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	410	2000	530	0.26	82	570	0.68 J	< 0.081 U	91 J		< 0.40 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	9.1	2100	530	0.025 J	17	700	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	37	2100	470	0.045 J	30	640	< 0.40 U	< 0.069 U	65 J		< 0.34 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	6.2 T	3400 T	300 T	0.024 J	14	620	< 0.49 U	< 0.084 U	< 65 U		< 0.42 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	6.3	3100	280	< 0.017 U	12	480	< 0.42 U	< 0.073 UT	< 56 U		< 0.36 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	9.0	1900	470	0.035 J	20	580	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	23	1600	580	0.19	14	480	0.82 J	< 0.078 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	12	2400	330	0.047 J	16	510 J	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	10	2500	260	0.036 J	16	630	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	11	2300	340	0.031 J	18	530	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	11	2200	360	0.038 J	17	510	< 0.48 U	< 0.082 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	7.1	1800	350	0.037 J	12	460 J	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	9.5	2000	340	0.048 J	15	470	< 0.42 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	9.6	2000	400	0.045 J	16	550	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	12	3000	590	0.035 J	19	570	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	11	2200	540	0.041 J	19	580	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	7.7	2100	360	0.029 J	19	570	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	11	2300	600	0.031 J	18	510 J	< 0.52 U	< 0.090 U	< 70 U		< 0.44 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	8.8	2000	280	0.030 J	16	570	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	6.3 T	1700	320 T	< 0.017 U	15	410	< 0.34 U	< 0.059 U	< 46 U		< 0.29 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	6.5	1900	440	0.020 J	15	490 J	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	30	2200	340	0.061 J	16	580	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	50	1900	400	0.10	25	620	< 0.48 U	< 0.083 U	< 65 U		< 0.41 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	8.6	2300	310	< 0.022 U	17	730	< 0.51 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	7.4	5100	360	0.030 J	14	570	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	10	2100	480	< 0.020 U	16	630	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	12	1900	330	0.026 J	17	550	< 0.35 U	< 0.060 U	< 46 U		< 0.29 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	26	1900	490	0.037 J	19	510	< 0.43 U	< 0.074 U	< 58 U		< 0.37 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	6.9	1600	290	< 0.021 U	13	440	< 0.40 U	< 0.068 U	< 53 U		< 0.34 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	33	2600	370	0.080 J	21	710	< 0.42 U	< 0.073 U	59 J		< 0.36 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	22	2900	510	0.072 J	24	940	< 0.47 U	< 0.082 U	73 J		< 0.40 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	24	2400	550	0.035 J	21	590	< 0.37 U	< 0.064 U	< 50 U		< 0.32 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	9.5	2600	390	0.026 J	18	540	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated		13	220
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated		13	86
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated		11	46
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated		10	47
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated		13	120
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated		11	48
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated		15	89
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated		13	67
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated		12	58
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated		14	47
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated		19	160
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated		13	93
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated		12	65
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated		14	61
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated		15	58
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated		18	55
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated		14	65
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated		13 T	56 T
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated		11	130
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated		12	55
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated		11	85
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated		11	56
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated		9.6	250
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated		11	92
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated		16	55
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated		7.4	46
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated		11	68
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated		9.8	52
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated		14	57
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated		16	47
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated		14	49
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated		13	100
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated		11	58
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated		14	98
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated		12	52
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated		11	60
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated		16	64
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated		10	61
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated		11	50
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated		12	59
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated		10	65
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated		20	400
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated		12	61
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated		13	73
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated		10	49
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated		7.0	44
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated		13	70
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated		12	72
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated		17	51
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated		18	50
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated		15	57
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated		14	57
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated		11	40
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated		14	44
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated		9.9	53
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated		13	76
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated		14	62
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated		12	60
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated		17	55
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated		13	49
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated		9.7	51
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated		9.5	63
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated		14	53
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated		13	70
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated		14	60
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated		9.4	55
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated		11	70
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated		12	68
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated		12	87
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated		9.2	44
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated		14	75
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated		13	72
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated		15	77
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated		15	53

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	11000	< 0.37 U	8.8	88	0.44 J	0.12 J	5600	14		11	26	27000
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	9500	1.3 J	9.4	88	0.50	0.27 J	3800	13		8.4	520	23000
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	9400	< 0.34 U	7.1	69	0.42 J	0.10 J	1800	11		8.3	19	19000
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	8900	< 0.30 U	7.7	37	0.38 J	0.10 J	860	11		6.5	20	18000
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	12000	< 0.35 U	6.8	110	0.44 J	0.082 J	800	12		6.1	14	17000
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	9600	< 0.36 U	6.6	56	0.40 J	0.086 J	1800	11		7.8	18	19000
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	11000	< 0.35 U	6.2	74	0.45 J	0.12 J	1600	12		7.7	19	18000
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	11000	< 0.31 U	7.7	47	0.48	0.12 J	1000	13		10	22	21000
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	9500	< 0.31 U	7.2	74	0.37 J	0.11 J	8200	15		8.1	22	20000
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	11000	< 0.46 U	9.3	140	0.47 J	0.18 J	2800	12		6.4	18	17000
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	9600	< 0.38 U	7.7	110	0.43 J	0.17 J	4700	12		7.8	38	19000
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	10000	< 0.27 U	9.2	93	0.43	0.097 J	4300	14		11	20	24000
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	7400	0.52 J	15	93	0.47 J	0.16 J	3200	16		8.4	94	37000
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	12000	2.8 J	27	200	0.66	0.92 J	13000	58		16	1900	110000
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	8900	< 0.30 U	4.2	82	0.35 J	0.079 J	1600	9.3		5.0	14	15000
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	6700	< 0.33 U	8.3	110	0.36 J	0.87	8200	12		5.1	43	16000
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	11000	< 0.32 U	5.4	120	0.43 J	0.12 J	1300	12		9.3	11	21000
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	8000	< 0.28 U	7.0	53	0.32 J	0.14 J	7600	10		7.4	22	17000
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	7000	< 0.37 U	4.8	60	0.25 J	0.14 J	13000	9.1		6.3	22	18000
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	10000	< 0.32 U	9.3	83	0.46	0.19 J	2800	13		9.6	30	23000
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	8700	0.31 J	8.0	90	0.40 J	0.40 J	4100	14		7.2	60	21000
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	9000	< 0.33 U	6.3	35	0.39 J	0.093 J	690	10		7.9	16	17000
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	9000	< 0.32 U	8.5	100	0.38 J	0.52	8600	16		7.4	57	22000
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	8400	< 0.31 U	6.6	57	0.36 J	0.13 J	1600	9.7		6.3	18	17000
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	7100	< 0.32 U	7.9	51	0.37 J	0.099 J	670	13		7.2	28	22000
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	9100	< 0.35 UT	9.0	88	0.45 J	0.16 J	3400	12		8.4	30	21000
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	9100	0.55 J	9.1	81	0.45 J	0.26 J	3600	16		9.2	43	32000
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	9800	< 0.34 U	10	75	0.48	0.055 J	4800	12		10	20	23000
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	7000	< 0.38 U	6.5	40	0.34 J	0.068 J	580	8.0		6.5	16	15000
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	7300	< 0.28 U	6.0	57	0.34 J	0.068 J	460	8.8		9.0	19	16000
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	4600	0.46 J	6.9	69	0.46	0.17 J	25000	16		4.9	37	16000
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	5500	0.94 J	8.1	54	0.27 J	0.30 J	3900	11		5.1 J	44	20000
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	3900	< 0.16 U	3.7	33	0.17 J	0.073 J	26000	5.5		4.1	16	9900
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	4500	< 0.28 U	5.4	43	0.21 J	0.15 J	110000	5.8		4.5 J	18	12000
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	5300	0.40 J	8.1	82	0.33	0.13 J	7100	9.8		5.7	32	17000
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	3400 T	0.28 JT	4.5 T	42 T	0.18 JT	0.11 JT	17000 T	14 T		3.1 JT	24 T	10000 T
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	7400	0.17 J	5.9	63	0.31	< 0.039 U	4800	9.2		6.6	15	16000
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	6900	< 0.16 U	4.0	44	0.29	0.053 J	1500	7.9		5.5	21	14000
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	5900	< 0.52 U	5.3	27	0.26 J	0.38 J	640	7.7		6.5	18	12000
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	8200	< 0.21 U	6.2	58	0.36	0.46	7900	10		7.5	23	16000
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	13000	< 1.4 U	11	100	0.56 J	0.65 J	2300	21		8.2	43	27000
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	6100	< 0.48 U	4.7	25	0.25 J	0.41 J	570	7.5		5.7	20	13000
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	11000	< 0.25 U	6.7	59	0.42	0.54	18000	13		8.0	29	19000
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	7700	< 0.24 U	5.3	45	0.30 J	0.47	27000	9.9		6.7	23	16000
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	5000	< 0.23 U	3.8	26	0.22 J	0.38	19000	6.4		4.9	16	12000
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	7100	< 0.25 U	6.4	40	0.32 J	0.53	7600	9.5		7.0	28	18000
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	6800	< 0.23 U	7.5	48	0.35	1.2	2100	9.5		7.1	23	18000
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	6200	< 0.19 UT	4.7	40	0.27	0.46	13000 T	8.7		6.2	23	15000
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	8500	< 0.26 U	5.8	59	0.35	0.55	28000	12		8.3	24	17000
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	5500	< 0.25 U	3.8	43	0.23 J	0.11 J	36000	6.7		5.8	22	14000
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	5000	< 0.23 U	4.7	33	0.23 J	0.085 J	36000	6.4		5.1	16	13000
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	8700	< 0.31 U	5.4	71	0.37 J	0.40 J	570	9.1		6.5	15	16000
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	8300	< 0.33 U	3.6	120	0.34 J	0.40 J	2900	8.9		5.7	12	15000
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	9200	< 0.30 U	3.9	56	0.34 J	0.40 J	700	9.5		5.5	18	16000
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	7000	< 0.31 U	5.5	71	0.33 J	0.51	16000	11		5.8	71	16000
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	9600	< 0.28 U	5.7	54	0.39	0.41 J	180 J	10		7.7	46	18000
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	9100	< 0.26 U	5.4	76	0.42	0.40 J	380 J	10		6.5	17	17000
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	9000	< 0.31 U	7.2	92	0.44	0.58	8300	11		7.6	44	18000
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	4500	2.3	19	110	0.50	0.54	4300	13		6.0	68	27000
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	7700	2.1	19	210	0.58	1.8 J	9900	18		8.8	64	45000
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	6200	0.94	11	95	0.49	0.43 J	4700	11		6.7	45	19000
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	5000	0.42 J	4.2	29	0.23 J	0.10 J	16000	6.6		5.1	17	12000
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	7600	< 0.28 U	6.5	61	0.35 J	0.62	2500	9.1		6.9	25	18000
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	9500	< 0.31 U	6.5	54	0.39 J	0.69	1700	11		7.5	33	18000
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	7300	< 0.26 U	9.9	110	0.41	0.88	13000	13		6.8	56	18000
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	9100	0.23 J	9.7	89	0.41	0.76	11000	11		10	26	21000
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	7900	< 0.22 U	7.9	51	0.36	0.61	18000	11		7.9	18	17000
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	7800	< 0.31 U	6.8	70	0.36 J	0.78	21000	9.8		11	26	18000
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	8000	< 0.29 U	6.6	100	0.37 J	0.61	5900	9.7		7.5	23	17000
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	5300	< 0.19 U	5.8	33	0.26	0.51	1100	6.9		5.6	17	13000
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	6600	< 0.23 U	5.8	46	0.33	0.55	3400	8.3		6.4	22	16000
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	8700	< 0.18 U	8.3	69	0.40	0.71	12000	11		9.2	26	18000
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	9300	< 0.23 U	6.6	60	0.37	0.70	23000	10		7.9	28	18000
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	6200	< 0.24 U	4.2	40	0.26 J	0.49	29000	7.7		5.2	22	13000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	16	3600	490	0.041 BJ	27	1100	< 0.48 U	< 0.083 U	68 BJ		< 0.41 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	57	2700	350	0.043 J	33	830	< 0.44 U	< 0.076 U	63 J		< 0.37 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	39	2500	510	0.031 J	18	680	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	13	1900	270	0.042 J	15	520	< 0.39 U	< 0.068 U	< 53 U		< 0.33 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	14	2200	440	0.15	15	550	0.63 J	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	11	2400	340	0.057 J	17	650	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	18	2600	390	0.061 BJ	18	550	0.53 J	< 0.079 U	61 BJ		< 0.39 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	10	2700	470	0.035 BJ	21	750	< 0.41 U	< 0.070 U	< 54 U		< 0.35 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	20	3100	480	0.091 BJ	21	880	< 0.41 U	< 0.071 U	74 BJ		< 0.35 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	27	2000	770	0.96 B	16	570 J	< 0.59 U	< 0.10 U	< 80 U		< 0.51 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	97	2600	610	0.12 B	19	740	0.70 J	< 0.085 U	110 BJ		< 0.42 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	16	3200	540	0.051 BJ	25	990	< 0.35 U	< 0.061 U	58 BJ		< 0.30 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	48	2000	320	< 0.022 U	38	880	0.99 J	< 0.080 U	96 BJ		< 0.39 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	960	2900	880	0.069 BJ	450	690	2.4	0.62 J	330 BJ		< 1.9 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	16	1800	320	0.085 BJ	13	430	< 0.39 U	< 0.068 U	< 53 U		< 0.33 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	130	1800	320	0.097 BJ	24	500	0.78 J	< 0.074 U	150 BJ		< 0.37 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	10	2100	420	0.043 BJ	17	500	0.47 J	< 0.072 U	99 BJ		< 0.35 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	20	4100	520	0.056 BJ	19	760	< 0.37 U	< 0.063 U	51 BJ		< 0.31 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	11	2200	750	0.024 J	17	700	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	25	2700	490	0.065 J	29	830	0.42 J	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	49	2100	370	0.084 J	33	480	0.51 J	< 0.069 U	56 J		< 0.34 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	11	2000	350	0.028 J	16	490	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	48	2500	440	0.10 J	39	480	0.49 J	< 0.073 U	71 J		< 0.36 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	16	2000	440	0.037 J	16	470	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	10	1900	390	0.023 J	24	590	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	24	2700	440	0.053 J	21	780	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	30	2600	570	0.070 J	30	640	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	14	3200	520	< 0.018 U	22	1100	< 0.44 U	< 0.076 U	< 59 U		< 0.38 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	8.2	1900	350	0.025 J	15	520 J	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	8.7	2000	470	0.024 J	17	650	< 0.36 U	< 0.062 U	< 48 U		< 0.31 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	55	6600	310	0.55	17	460 J	0.68 J	< 0.097 U	83 J		< 0.27 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	18	2500	650	0.029 J	19	390 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	9.8	4000	240	0.11	11	260	0.48 J	< 0.054 U	42 J		< 0.15 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	10	5700	350	< 0.020 U	12	340 J	0.54 J	< 0.095 U	76 J		< 0.26 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	43	2500	510	0.49	15	330 J	0.44 J	< 0.077 U	48 J		< 0.21 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	49 T	2100 T	220	0.43 T	12 T	400 JT	< 0.41 UT	< 0.092 UT	86 JT		< 0.25 UT
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	17	2100	400	0.026 J	15	500	0.40 J	< 0.055 U	38 J		< 0.15 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	19	1900	320	0.25	14	290	0.28 J	< 0.054 U	30 J		< 0.15 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	11	1500	420	0.042	14	300 J	< 0.79 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	20	3800	460	0.043	19	490	< 0.33 U	< 0.073 U	< 36 U		< 0.20 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	24	2800	1000	0.042	23	740 J	< 2.1 U	< 0.097 U	< 240 U		0.33 J
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	9.4	1600	310	0.023 J	14	260 J	< 0.73 U	< 0.082 U	< 41 U		< 0.23 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	13	5400	370	0.028 J	22	560	< 0.39 U	< 0.087 U	49 J		0.39 J
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	11	5700	340	0.030 J	19	440	< 0.37 U	< 0.083 U	54 J		< 0.23 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	8.2	2900	300	0.044	13	400	< 0.34 U	< 0.078 U	39 J		< 0.21 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	16	3500	410	0.030	18	470	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	18	2500	410	0.031 J	22	520	< 0.35 U	< 0.078 U	< 38 U		0.21 J
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	21 T	4400 T	360	0.029 J	17	410	< 0.28 U	< 0.064 U	34 J		< 0.18 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	14	5800	410	0.033 J	21	650	< 0.40 U	< 0.089 U	58 J		< 0.24 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	6.3	5800	430	< 0.018 U	14	310 J	< 0.38 U	< 0.085 U	50 J		0.55 J
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	8.0	3800	320	< 0.018 U	13	290 J	< 0.35 U	< 0.079 U	69 J		0.56 J
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	12	1800	480	0.025 J	14	220 J	< 0.47 U	< 0.11 U	< 52 U		0.42 J
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	12	1800	810	0.055	12	270 J	< 0.51 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	6.3	2100	280	0.033 J	15	200 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	29	2600	330	0.043	43	240 J	< 0.47 U	< 0.11 U	63 J		< 0.29 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	8.9	2400	370	0.030 J	17	270 J	< 0.43 U	< 0.096 U	< 47 U		0.39 J
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	8.6	2100	310	0.023 J	17	170 J	< 0.40 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	22	2500	420	0.038	27	390 J	0.52 J	< 0.11 U	83 J		< 0.29 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	100	850	190	0.53 B	15	320 J	2.2	< 0.11 U	59 J		0.76 J
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	210	2900	460	0.54 B	25	530	1.4	< 0.089 U	94 J		< 1.2 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	140	1700	310	0.20 B	16	500	0.69 J	< 0.097 U	67 J		0.65 J
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	6.7	7500	360	0.024 BJ	12	360	< 0.32 U	< 0.073 U	45 J		0.37 J
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	10	2500	780	0.025 J	19	540	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	11	2600	440	0.027 J	20	620	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	85	3100	330	0.20	25	510	0.60 J	< 0.088 U	65 J		< 0.24 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	13	3700	600	0.023 J	23	790	< 0.32 U	< 0.073 U	36 J		< 0.20 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	10	7600	360	0.023 J	18	910	< 0.33 U	< 0.074 U	48 J		< 0.20 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	11	6900	1700	0.026 J	25	730	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	9.4	3900	590	0.024 J	20	670	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	9.2	1500	570	0.046	15	410	< 0.29 U	< 0.066 U	< 32 U		< 0.18 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	6.9	2700	510	0.032 J	16	600	< 0.36 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	9.7	3300	370	< 0.020 U	20	800	0.30 J	< 0.062 U	34 J		< 0.17 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	12	7300	480	0.025 J	20	710	< 0.35 U	< 0.079 U	98 J		< 0.21 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	6.1	7600	390	< 0.022 U	14	560	< 0.37 U	< 0.083 U	48 J		< 0.23 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated		16	65
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated		15	130
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated		15	60
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated		16	53
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated		17	53
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated		15	54
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated		15	58
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated		17	85
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated		14	60
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated		16	58
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated		15	93
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated		15	63
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated		17	75
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated		23 J	970
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated		12	50
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated		14	210
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated		16	55
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated		13	73
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated		11	80
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated		16	78
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated		15	120
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated		15	52
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated		14	130
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated		14	59
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated		13	66
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated		14	86
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated		15	84
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated		14	64
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated		10	50
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated		14	60
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated		11	88
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated		11	79
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated		6.3	41
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated		6.7	51
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated		10	71
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated		8.0 T	66 T
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated		11	43
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated		9.9	55
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		11	55
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated		14	61
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		21 J	85
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		9.9	55
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		17	66
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		13	56
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated		8.8	170
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		14	71
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		15	280
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		12	56 T
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		14	68
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated		8.2	52
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated		7.8	40
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated		13	48
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated		14	43
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated		14	50
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated		12	76
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated		15	50
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated		13	55
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated		14	89
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated		17	100 B
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated		22	210 B
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated		16	120 B
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated		10	49 B
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated		13	60
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated		15	80
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated		15	95
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated		13	82
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated		13	53
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated		14	74
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated		12	63
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated		10	45
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated		12	43
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated		13	47
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated		13	73
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated		9.8	64

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	9700	< 0.29 U	7.7	52	0.40	0.68	970	11		7.2	38	19000
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	6100	< 0.28 U	6.4	34	0.29 J	0.46	830	8.3		5.7	19	14000
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	8200	< 0.26 U	7.8	39	0.42	0.56	950	10		6.9	23	18000
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	7900	< 1.4 U	11	160	0.55 J	0.98 J	5400	12		7.0	21	33000
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	6800	< 0.30 U	6.2	41	0.30 J	0.48 J	1400	9.5		6.3	22	16000
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	7200	< 0.22 U	9.0	48	0.32	0.56	1200	8.2		9.1	19	16000
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	8000	< 0.25 U	8.7	74	0.40	0.78	11000	12		7.7	39	18000
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	7300	< 0.19 U	6.2	63	0.37	0.61	980	9.3		8.5	22	16000
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	7400	< 0.55 U	11	87	0.43 J	0.59 J	1400	8.9		6.6	26	20000
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	7800	< 0.23 U	5.4	44	0.32	0.56	37000	9.9		6.8	18	14000
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	9200	< 0.26 U	6.7	60	0.42	0.52	1400	10		6.2	16	16000
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	13000	1.1	10	85	0.53	0.79	1900	14		9.5	20	23000
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	11000	< 0.33 U	7.3	160	0.51	0.49 J	680	12		5.7	15	16000
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	7600	< 0.19 U	6.8	47	0.35	0.55	940	9.1		6.5	19	15000
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	8400	< 0.33 U	6.8	100	0.41 J	0.48 J	2000	9.6		5.0 J	18	15000
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	11000	< 0.26 U	8.7	77	0.53	0.75	2500	12		8.4	27	23000
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	10000	< 0.25 U	6.5	150	0.46	0.57	2700	11		6.4	16	18000
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	12000	< 0.32 U	6.6	110	0.47	0.55	1100	12		6.5	19	18000
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	12000	< 0.26 U	6.5	74	0.53	0.63	1300	14		6.8	14	19000
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	12000	< 0.29 U	8.0	110	0.51	0.74	2300	13		8.3	17	21000
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	8600	< 0.24 U	4.8	92	0.37	0.47	1500	9.0		4.6	14	14000
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	15000	< 0.28 U	6.6	80	0.57	0.72	920	16		9.0	16	23000
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	12000	< 0.28 UT	14	100 T	0.55	0.97	6500 T	16		12	22	28000
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	13000	< 0.27 U	13	95	0.57	1.0	5700	17		13	32	30000
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	11000	< 0.24 U	6.8	56	0.47	0.65	1300	13		8.1	22	19000
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	13000	< 0.30 U	7.7	73	0.52	0.73	5000	14		9.5	20	22000
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	12000	< 0.20 U	11	74	0.46	0.78	4400	13		11	16	22000
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	12000	< 0.25 U	6.7	49	0.46	0.64	4200	13		8.0	14	20000
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	8500	0.41 J	4.8	85	0.36 J	0.58	12000	10		6.5	17	15000
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	14000	< 0.34 U	4.5	96	0.49	0.59	1200	14		7.7	13	18000
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	12000	< 0.22 U	4.3	78	0.44	0.60	600	12		6.5	13	16000
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	10000	0.39 J	7.2	120	0.50	0.88	7400	15		9.2	36	19000
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	11000	< 0.33 U	6.8	100	0.48	0.68	11000	12		6.8	20	18000
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	7000	0.56 J	5.5	55	0.28 J	0.63	57000	9.3		5.8	22	15000
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	11000	0.43 J	6.4	96	0.50	0.67	2600	12		7.4	25	18000
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	13000	< 0.28 UT	3.8	130 T	0.52	0.56	1200 T	12		7.9	10	15000
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	11000	< 0.29 U	3.8	160	0.46	0.49	2500	11		6.9	13	12000
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	12000	< 0.31 U	4.8	110	0.45	0.67	7100	12		7.2	15	17000
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	13000	0.31 J	8.1	59	0.52	0.72	1000	14		8.5	18	19000
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	12000	< 0.30 U	5.7	64	0.42	0.65	1000	13		6.9	13	17000
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	9300	0.28 J	4.1	70	0.32	0.62	61000	10		6.1	18	14000
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	9300	0.32 J	8.0	86	0.45	0.76	3300	11		7.2	34	19000
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	13000	< 0.31 U	4.5	120	0.45	0.57	1700	13		6.0	13	16000
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	13000	< 0.31 U	4.3	91	0.46	0.56	1000	13		7.4	11	17000
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	12000	0.60 J	7.7	120	0.50	0.68	4900	13		7.3	22	18000
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	14000	0.30 J	5.0	100	0.52	0.63	1400	14		8.0	13	19000
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	12000	0.37 J	7.3	83	0.46	0.81	27000	13		8.8	26	20000
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	9600	< 0.30 U	6.0	110	0.45	0.68	1800	11		7.6	38	18000
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	9700	0.54 J	9.6	120	0.53	1.3	11000	18		8.6	79	22000
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	12000	< 0.33 U	6.4	43	0.53	0.74	1100	14		10	15	20000
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	10000	0.27 J	5.8	120	0.44	0.77	3800	13		8.0	30	17000
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	9600	< 0.34 U	6.0	31	0.40 J	0.60	880	11		8.3	12	16000
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	9300	0.52 J	7.0	120	0.44	0.94	7700	14		7.7	62	17000
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	11000	0.20 J	9.5	39	0.43	0.67	870	13		8.4	18	21000
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	13000	0.18 JT	14	59 T	0.53	0.85	2200 T	14		11	21	24000 T
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	13000	< 0.26 U	9.2	59	0.51	0.70	3700	14		10	19	21000
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	13000	< 0.24 U	9.1	38	0.51	0.70	810	14		11	17	22000
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	12000	< 0.25 U	8.7	44	0.48	0.60	910	13		8.5	19	21000
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	7600	< 0.27 U	6.7	77	0.34 J	0.50	4600	8.9		5.8	27	16000
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	7000	1.3	6.8	72	0.39	0.49	6200	8.4		6.2	40	16000
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	13000	< 0.23 UT	8.7	49	0.53	0.58	1100	13		9.1	17	21000
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	10000	0.35 J	8.1	100	0.42	0.54	5200	11		6.5	21	18000
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	10000	< 0.31 U	5.7	91	0.45	< 0.074 U	1600	11		7.6	25	16000
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	9000	0.49 J	9.7	100	0.44	0.51 J	2800	9.5		11	58	20000
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	10000	0.55 J	6.7	75	0.39	0.47	1300	10		6.6	38	19000
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	7400	0.57 J	9.8	51	0.31	0.48	3200	8.8		6.3	26	18000
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	8700	< 0.32 U	9.8	74	0.43	0.37 J	3100	17		7.5	39	18000
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	10000 B	< 0.24 U	11	92	0.58	1.0	5100	15		8.0	50	24000
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	9700	< 0.32 U	6.4	79	0.44	0.33 J	7500	13		6.6	41	22000
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	9500	< 0.31 U	7.3	85	0.43	0.41 J	8500	14		6.6	39	20000
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	10000	0.37 J	9.7	100	0.55	0.82	9800	18		8.0	52	23000
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	9500	0.60 J	11	110	0.53	0.91	7700	24		8.0	60	23000
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	8800	0.56 J	8.6	100	0.45	0.74	16000	16		6.5	43	23000
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	5100	1.0 JT	36	99	0.65	1.3	20000	30		8.4	150 T	45000 T

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	11	2300	210	0.031 J	20	570	< 0.44 U	< 0.099 U	< 49 U		< 0.25 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	7.0	1800	310	0.023 J	14	600	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	10	2300	530	0.022 J	18	690	< 0.40 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	9.6	4600	3100	0.026 J	21	680 J	< 2.2 U	< 0.49 U	< 240 U		< 0.27 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	7.8	2200	360	< 0.022 U	14	730	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	14	2000	720	< 0.023 U	17	500	0.38 J	< 0.074 U	< 37 U		< 0.20 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	47	2800	390	0.12	23	570	< 0.39 U	< 0.087 U	45 J		< 0.24 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	14	2000	800	< 0.023 U	19	550	0.37 J	< 0.065 U	< 32 U		< 0.18 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	11	2000	600	< 0.023 U	18	660 J	< 0.83 U	< 0.19 U	< 92 U		< 0.26 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	9.5	3400	350	< 0.021 U	16	560	< 0.35 U	< 0.079 U	48 J		< 0.22 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	16	2000	340	0.024 J	16	450	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	18	2700	490	< 0.023 U	22	700	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	32	1900	510	0.47	13	440 J	1.0 J	< 0.11 U	< 56 U		0.49 J
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	11	1800	500	< 0.021 U	17	430	< 0.29 U	< 0.064 U	< 32 U		< 0.18 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	31	1600	470	0.061	12	440 J	< 0.50 U	< 0.11 U	< 56 U		0.39 J
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	27	2500	460	0.030 J	21	690	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	30	2200	610	0.045	15	470	< 0.39 U	< 0.087 U	< 43 U		0.38 J
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	22	2200	460	0.099	15	430 J	< 0.49 U	< 0.11 U	< 55 U		0.45 J
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	15	2300	470	0.026 J	16	550	< 0.40 U	< 0.089 U	< 44 U		0.30 J
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	29	2700	500	0.096	21	570	< 0.44 U	< 0.099 U	< 49 U		0.30 J
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	17	1600	410	0.027 J	12	410	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	10	3200	330	< 0.025 U	22	710	< 0.43 U	< 0.097 U	< 48 U		0.33 J
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	15	3900 T	490	< 0.020 U	29	1200 T	< 0.43 U	< 0.097 U	110 J		< 0.27 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	15	4100	490	< 0.021 U	31	960	< 0.40 U	< 0.091 U	45 J		< 0.25 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	11	2600	280	< 0.022 U	20	690	< 0.37 U	< 0.083 U	42 J		0.24 J
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	12	3000	380	< 0.022 U	22	920	< 0.45 U	< 0.10 U	< 50 U		0.35 J
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	12	3000	490	< 0.023 U	23	730	< 0.30 U	< 0.068 U	43 J		< 0.19 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	9.2	2700	250	< 0.024 U	19	840	< 0.38 U	< 0.086 U	46 J		< 0.23 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	8.4	3500	330	0.026 BJ	17	530	< 0.48 U	< 0.11 U	< 54 U		0.37 J
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	9.6	2600	350	0.025 J	20	620	< 0.52 U	< 0.12 U	< 57 U		0.67 J
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	7.8	2000	230	0.030 BJ	15	390	< 0.33 U	< 0.074 U	< 37 U		0.40 J
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	26	3500	430	0.061 B	28	870	< 0.50 U	< 0.11 U	57 J		< 0.31 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	13	2800	420	0.030 BJ	18	650	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	12	6300	370	< 0.031 U	17	490 J	< 0.52 U	< 0.12 U	92 J		< 0.32 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	15	2200	520	0.033 BJ	18	590	< 0.52 U	< 0.12 U	< 58 U		0.65 J
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	10	1800	650	0.031 BJ	16	390 J	< 0.43 U	< 0.098 U	89 J		0.53 J
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	20	1800	320	0.075 B	14	440 J	< 0.45 U	< 0.10 U	65 J		0.59 J
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	17	2600	730	0.049 B	17	590	< 0.48 U	< 0.11 U	57 J		0.38 J
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	10	2500	330	0.027 BJ	20	570	< 0.43 U	< 0.098 U	82 J		0.38 J
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	9.9	2400	180	< 0.024 U	17	420 J	< 0.46 U	< 0.10 U	< 51 U		0.45 J
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	8.3	6300	360	< 0.022 U	16	520	< 0.32 U	< 0.071 U	86 J		0.22 J
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	76	2200	540	0.090 B	19	670	< 0.48 U	< 0.11 U	< 54 U		0.40 J
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	13	2300	310	0.034 BJ	17	590	< 0.48 U	< 0.11 U	< 53 U		0.43 J
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	9.3	2600	300	< 0.026 U	18	550	< 0.48 U	< 0.11 U	< 53 U		0.52 J
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	36	2800	710	0.063	17	590	< 0.54 U	< 0.12 U	< 60 U		0.63 J
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	10	2700	380	< 0.025 U	20	580	< 0.44 U	< 0.098 U	< 48 U		0.61 J
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	31	6900	560	0.042	20	680	< 0.34 U	< 0.078 U	68 J		0.25 J
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	58	1800	1200	0.17	17	490 J	< 0.46 U	< 0.10 U	< 51 U		0.47 J
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	160	3600	560	0.56 B	33	770	0.47 J	< 0.10 U	86 J		< 0.28 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	10	2800	320	0.043 B	20	600	< 0.51 U	< 0.11 U	< 57 U		0.39 J
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	39	2000	620	0.064 B	22	620	< 0.37 U	< 0.084 U	43 J		< 0.23 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	8.4	2400	280	0.031 BJ	16	590	< 0.52 U	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	140	2700	400	0.33 B	28	660	< 0.37 U	< 0.084 U	80 J		< 0.23 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	9.3	3000	230	< 0.020 U	19	530	0.43 J	< 0.066 U	< 32 U		< 0.18 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	21 T	3400 T	320	< 0.021 U	24	650 T	0.53 J	< 0.063 U	37 J		< 0.17 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	13	3000	450	< 0.020 U	20	690	0.41 J	< 0.088 U	< 43 U		0.25 J
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	9.3	3000	280	< 0.024 U	20	550	< 0.36 U	< 0.082 U	< 40 U		< 0.22 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	8.9	2900	280	< 0.022 U	19	490	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	34	2500	440	0.053	14	340 J	< 0.42 U	< 0.094 U	46 J		< 0.26 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	47	2000	450	0.038	14	360 J	< 0.39 U	< 0.087 U	46 J		< 0.24 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	9.8	2800 T	340	< 0.024 U	18	510	< 0.35 U	< 0.079 U	< 39 U		< 0.21 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	20	3100	410	0.027 J	16	370 J	0.35 J	< 0.079 U	< 39 U		0.25 J
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	23	2200	390 B	< 0.024 U	15	500 J	< 0.47 U	< 0.11 U	< 52 U		0.73 J
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	79	1900	540	0.18	18	540 J	0.95 J	< 0.11 U	< 56 U		0.58 J
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	18	2400	570	< 0.022 U	22	460	< 0.41 U	< 0.092 U	< 45 U		0.64 J
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	28	2400	450	< 0.022 U	15	380	0.39 J	< 0.061 U	< 30 U		0.55 J
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	42	2200	440	0.044	17	550	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	100	3400	470	0.12	24	740	0.61 J	< 0.083 U	70 J		< 0.23 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	40	3900	450	0.034	17	690	< 0.49 U	< 0.11 U	57 J		< 0.30 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	73	2800	430	0.079	17	630	< 0.47 U	< 0.11 U	78 J		< 0.29 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	87	3900	590	0.22	23	880	0.87 J	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	82	3300	580	0.29	23	890	1.1 J	< 0.12 U	< 61 U		< 0.34 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	100	3800	530	0.20	19	810	0.88	< 0.090 U	77 J		< 0.25 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	60	2400 T	390 T	0.34 T	23	610 J	4.8	< 0.13 U	76 J		< 0.35 UT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated		16	87
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated		12	48
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated		14	53
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated		14 J	59
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated		13	51
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated		12	53
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated		16	76
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated		12	96
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated		13	88
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated		13	47
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated		13	58
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated		19	66
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated		17	56
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated		12	51
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated		15	48
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated		17	62
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated		16	56
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated		16	64
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated		20	55
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated		17	69
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated		13	45
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated		20	63
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated		18	68 T
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated		18	68
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated		17	57
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated		18	61
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated		17	55
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated		17	53
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated		14	54
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated		18	67
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated		18	50
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated		16	120
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated		17	65
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated		12	65
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated		17	63
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated		18	54 T
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated		15	57
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated		17	64
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated		20	58
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated		18	59
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated		14	59
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated		16	76
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated		16	62
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated		16	60
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated		19	75
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated		18	61
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated		17	67
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated		16	88
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated		21	140
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated		19	57
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated		18	78
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated		16	42
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated		17	120
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated		17	54
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated		19	62
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated		19	56
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated		18	59
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated		17	53
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated		13	55
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated		12	63
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated		17	58 T
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated		14	58
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated		15	57
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated		14	84
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated		15	82
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated		13	55
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated		16	68
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		18	360
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		17	110
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		18	270
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		22	510
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		25	380
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		19	390
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		21	780

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	8700 B	< 0.24 U	14	60	0.42	0.71	20000	16		8.2	77	28000
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	7400 B	< 0.25 U	8.0	70	0.41	0.35 J	18000	9.4		6.4	29	18000
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	9800 B	0.32 J	12	110	0.47	0.66	22000	16		9.3	54	25000
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	11000 B	< 0.32 U	13	100	0.67	1.2	5400	17		7.9	54	25000
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	7900	< 0.26 U	5.3	77	0.38	0.26 J	1900	8.8		4.9	25	13000
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	14000	< 1.8 U	7.0	120	0.50 J	< 0.11 U	2000	14		6.8	16	19000
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	14000	< 1.9 U	5.0	140	0.47 J	< 0.11 U	2100	14		6.7	19	18000
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	15000	< 1.9 U	9.6	140	0.58	< 0.11 U	980	15		7.6	15	21000
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	14000	< 1.9 U	8.2	60	0.53 J	< 0.11 U	1000	16		8.8	19	24000
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	13000	< 1.9 U	11	110	0.52 J	< 0.11 U	2200	14		7.0	19	19000
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	14000	< 1.8 U	8.7	100	0.54	< 0.10 U	3900	15		9.0	16	24000
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	16000	< 1.9 U	9.7	100	0.59	< 0.11 U	1900	17		9.4	28	25000
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	14000	< 2.0 U	4.1	180	0.44 J	< 0.12 U	2600	13		5.3	7.8	16000
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	15000	< 2.0 U	5.9	160	0.48 J	< 0.11 U	3300	15		4.9	11	17000
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	14000	< 1.9 U	8.5	150	0.46 J	< 0.11 U	3400	14		5.3	14	17000
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	16000	< 2.0 U	5.7	130	0.50 J	< 0.12 U	1500	15		7.7	45	22000
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	13000	< 1.9 U	6.3	130 T	0.47 J	< 0.11 U	3800	13		6.4	14	19000
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	9700	< 0.26 U	6.8	110	0.37	< 0.064 U	1300	9.8		6.6	16	17000
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	9900	< 0.29 U	5.9	150	0.44	0.31 J	1900	8.8		6.5	13	17000
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	8100	0.34 J	8.6	94	0.35	0.38 J	6800	9.9		6.4	38	20000
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	8800	< 0.27 U	7.9	52	0.38	0.28 J	1000	9.4		7.6	36	17000
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	8700	0.37 J	8.1 T	63 T	0.38 T	0.35 JT	18000 T	11 T		8.1 T	22	19000
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	7800	< 0.31 U	7.3	36	0.38	0.30 J	390 J	9.5		6.3	21	17000
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	6600	< 0.20 U	6.6	38	0.25 J	< 0.049 U	2000	8.1		5.3	23	16000
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	9500	0.45 J	4.9	210	0.41	< 0.061 U	1600	8.5		7.5	21	21000
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	11000	< 0.26 U	6.6	65	0.38	< 0.062 U	930	11		6.3	16	18000
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	6100	< 0.26 U	6.2	38	0.24 J	< 0.064 U	2000	7.7		5.1	23	16000
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	10000	0.59 JT	12 T	130	0.60	< 0.090 U	3300	13		8.0	83 T	20000
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	6700	< 0.27 U	7.5	44	0.33 J	< 0.066 U	5800	7.8		4.8	28	16000
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	6300	< 0.27 U	8.9	39	0.30 J	< 0.065 U	2600	8.2		5.7	21	18000
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	5800	< 0.28 U	4.9	46	0.22 J	< 0.068 U	25000	7.2		4.3 J	17	13000
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	8900	0.78 J	6.7	47	0.33	0.51	26000	6.0		7.1	26	19000
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	4800	0.78 J	6.8	25	0.20 J	0.42	30000	1.6		4.6	21	14000
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	5600	0.63 J	5.6	26	0.20 J	0.38 J	28000	11		5.3	21	14000
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	8600	0.92	6.3	48	0.30	0.49	16000	3.8		6.2	29	18000
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	6700	0.97	4.8	55	0.24 J	0.52	40000	0.88		4.8	25	16000
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	9400	1.1	6.4	67	0.38	0.66	53000	9.2		7.5	23	20000
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	7400	0.88	5.9	52	0.28 J	0.53	32000	2.8		6.3	23	17000
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	5300	0.70	5.2	68	0.20 J	0.47	120000	< 1.6 U		4.1	18	13000
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	11000	0.50 J	3.6	75	0.39	< 0.049 U	870	11		6.9	12	15000
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	9800	0.60 J	4.8	69	0.37 J	< 0.069 U	500	11		7.3	28	16000
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	8600	0.65 J	6.0	65	0.36 J	0.13 J	780	11		6.4	28	16000
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	8200	0.38 JT	3.5	51 T	0.29	< 0.051 UT	1300 T	8.8		4.8	14 T	13000
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated		< 1.13 U	6.46	65.9	< 0.566 U	< 0.566 U		9.17		6.48	24.5	
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	6300	< 0.23	6.8	42	0.27	0.08	6800	8		5.3	18	16000
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	4400	0.29	3.2	28	0.17	< 0.015	23000	5.5		4.1	16	11000
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	5400	< 0.21	5.2	33	0.22	0.53	30000	6.3		5.9	12	13000
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	4200	< 0.22	4.9	30	0.18	0.047	31000	5.7		4	14	11000
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated	6800	< 0.37 U	4.3	56	0.26 J	0.075 J	3700	9.3		5.4	16	16000
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated	12000	0.82 J	7.8	130	0.46	0.17 J	6400 J-	24		7.3	22	20000
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated	6700	< 0.38 U	5.6	40	0.31 J	0.088 J	1100	8.7		5.7	21	16000
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated	6900	0.55 J	6	50	0.31 J	0.069 J	1100	8.5		5.9 J	18	15000
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated	6800	< 0.36 U	5.6	41	0.31 J	0.098 J	11000	9.4		5.6	19	15000
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated	6400	0.47 J	6	41	0.36 J	0.074 J	810	9.1		5.5	18	17000
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated	7800	< 0.35 U	5.5	53	0.32 J	0.095 J	19000	14		6.2	20	16000
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated	8300	1.8	9.6	84	0.43 J	0.2 J	6700	16		7.7	85	22000
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated	6100	0.47 J	3.8	57	0.25 J	0.076 J	32000	9.2		5 J	22	12000
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated	9100	0.41 J	7.3	71	0.43 J	0.084 J	2400	12		8.6	20	20000
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated	7700	< 0.39 U	7.7	110	0.56	0.1 J	9800	13		8.7	15	15000
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated	5200	< 0.35 U	5	34	0.22 J	0.11 J	34000	8.2		5.1	19	14000
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated	6100	< 0.36 U	4.9	41	0.25 J	0.12 J	82000	10		5.4	19	14000
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated	8900	0.75 J	7.6	87	0.4 J	0.18 J	2700	15		6.5	42	22000
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated	8200	< 0.37 U	6.3	40	0.33 J	0.085 J	3600	11		7.4	23	17000
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated	6800	< 0.37 U	4.6	94	0.25 J	0.13 J	37000	10		5.7	23	17000
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated	5800	< 0.35 U	4.6	34	0.23 J	0.11 J	43000	7.8		5.4	17	13000
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated	6500	< 0.39 UJ	6.4	47	0.3 J	0.13 J	9800 J-	9.8		5.8	22	16000
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated	7300	0.46 J	6.2	48	0.37 J	0.089 J	5800	16		6.6	20	17000
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated	8800	< 0.41 U	8.8	49	0.39 J	0.075 J	910	11		8.1	25	20000
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated	8300	< 0.37 U	5.8	88	0.35 J	0.068 J	810	12		7.6	27	17000
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated	9800	< 0.72 U	11	120	0.6 J	0.27 J	2000	13		6.9	25	21000
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated	7400	< 0.37 U	6.5	65	0.3 J	0.064 J	840	11		7.1	20	16000
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated	6400	< 0.42 U	6.4	64	0.4 J	0.095 J	3600	11		7.5	16	17000
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated	7200	< 0.38 UJ	7.2	49 J	0.35 J	0.059 J	2600	9.7		7	20	17000
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated	8700	< 0.38 U	7.8	58	0.42 J	0.1 J	6900	11		7.1	27	17000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	28	6000	420	0.10	23	600	0.87	< 0.084 U	62 J		< 0.23 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	21	6200	370	0.032 J	17	530	< 0.38 U	< 0.085 U	48 J		0.25 J
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	100	6100	650	0.12	27	830	< 0.42 U	< 0.095 U	76 J		< 0.26 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	150	3100	430	0.20	27	840	0.77 J	< 0.11 U	85 J		< 0.30 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	100	1700	330	0.069	12	580	< 0.40 U	< 0.090 U	65 J		< 0.25 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	23	2500	590	0.061	16	1100	< 1.6 U	< 0.43 U	51 J		< 1.4 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	12	2500	790	0.032 J	18	1200	< 1.7 U	< 0.45 U	< 45 U		< 1.5 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	19	2500	770	0.068	16	1200	< 1.7 U	< 0.46 U	< 46 U		< 1.5 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	11	3200	400	0.027 J	19	1200	< 1.6 U	< 0.44 U	< 44 U		< 1.4 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	36	2500	570	0.049	16	1100	< 1.6 U	< 0.44 U	49 J		< 1.4 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	19	3300	620	0.039	20	1400	< 1.6 U	< 0.41 U	< 41 U		< 1.3 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	34	3200	570	0.060	20	1600	< 1.7 U	< 0.45 U	< 45 U		< 1.4 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	9.7	2000	860	0.027 J	12	840	< 1.8 U	< 0.47 U	< 47 U		< 1.5 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	16	2200	540	0.035 J	13	960	< 1.7 U	< 0.46 U	48 J		< 1.5 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	21	2400	600	0.056	13	1100	< 1.7 U	< 0.45 U	47 J		< 1.5 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	12	2900	500	0.028 J	21	960	< 1.8 U	< 0.47 U	< 47 U		< 1.5 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	14	2400 T	710	0.030 J	14	1100 T	< 1.7 U	< 0.45 U	53 J		< 1.5 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	28	1900	660	0.086	12	430 J	< 0.40 U	0.11 J	70 J		< 0.25 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	18	1600	1100	0.046	10	370 J	< 0.47 U	< 0.50 U	57 J		< 0.29 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	30	2000	560	0.032	16	380 J	< 0.39 U	< 0.42 U	52 J		< 0.24 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	15	2300	400	0.043	18	440 J	< 0.42 U	< 0.46 U	< 47 U		< 0.26 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	12 T	5400 T	400 T	0.040	17 T	590 T	< 0.42 UT	< 0.35 U	52 J		< 0.26 UT
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	23	2100	470	0.036	16	410	< 0.38 U	< 0.52 U	< 42 U		< 0.23 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	19	2300	360	0.059	12	470	< 0.31 U	0.18 J	< 34 U		< 0.19 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	150	1800	1500	0.092	11	420	< 0.38 U	0.29 J	< 43 U		< 0.24 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	13	2300	250	0.063	14	480	< 0.39 U	0.17 J	< 43 U		< 0.24 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	19	2200	370	0.054	12	460	< 0.40 U	0.17 J	< 44 U		< 0.25 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	820 T	2300 T	670 T	0.36 T	19	960 T	< 0.57 UT	0.33 J	100 J		< 0.35 UT
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	15	4200	610	< 0.021 U	13	770	< 0.41 U	0.16 J	50 J		< 0.25 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	23	1900	450	0.13	13	450	< 0.41 U	0.22 J	< 46 U		< 0.25 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	25	3100	360	0.057	9.7	470	< 0.42 U	0.14 J	53 J		< 0.26 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	14	7700	380	5.9	23	970	< 0.38 U	0.25 J	53 J		< 1.2 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	10	7100	310	< 0.026 U	15	470	< 0.38 U	0.16 J	49 J		< 1.2 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	13	4700	350	0.40	17	450	< 0.39 U	0.19 J	< 43 U		< 1.2 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	21	5700	410	7.1	20	660	< 0.35 U	0.21 J	44 J		< 1.1 U
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	9.6	4700	380	< 0.021 U	17	410 J	< 2.1 U	0.23 J	55 J		< 0.26 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	14	12000	480	< 0.022 U	25	870	< 2.2 U	0.26 J	95 J		< 0.27 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	12	6700	370	0.060	20	470	< 1.7 U	0.21 J	57 J		< 0.21 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	11	12000	450	0.21	14	390	< 1.6 U	0.16 J	94 J		< 0.20 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	14	1900	310	0.026 J	14	390	< 0.31 U	< 0.14 U	< 34 U		0.38 J
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	18	2000	330	0.030 J	16	450 J	< 0.44 U	< 0.20 U	< 48 U		0.45 J
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	87	2200	380	0.089	16	370 J	0.76 J	< 0.20 U	< 50 U		0.34 J
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	13	1800 T	210 T	0.025 J	13	410	< 0.32 U	< 0.073 UT	42 J		0.29 J
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	7.97			< 0.0566 U	15.4		0.68	< 1.13 U			< 1.13 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	6.2	2900	440	< 0.012	13	630	0.33	< 0.046	49		< 0.17
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	4.4	5800	350	< 0.011	9.3	530	1.1	< 0.043	42		< 0.16
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	5.1	4300	280	< 0.011	12	580	0.65	< 0.042	55		< 0.15
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	4.9	4700	300	< 0.011	9.8	540	< 0.29	< 0.044	48		< 0.16
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated	7.8	2400	450	0.02 J	13	680	< 0.56 U	< 0.11 U	41 J		< 0.23 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated	37 J	3000	620	0.31 J	63	820	0.92 J	< 0.12 U	110 J		< 0.36 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated	7.1	2100	400	< 0.014 U	14	580	< 0.58 U	< 0.12 U	41 J		< 0.36 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated	11	1900	640	0.017 J	13	750	< 0.61 U	< 0.13 U	43 J		< 0.38 U
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated	7.9	2500	400	< 0.016 U	14	810	< 0.54 U	< 0.11 U	82 J		< 0.34 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated	8.4	1900	410	0.049	14	590	< 0.54 U	< 0.11 U	38 J		< 0.34 U
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated	8.7	4200	430	0.053	16	970	< 0.53 U	< 0.11 U	72 J		< 0.33 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated	76	2600	640	0.14	23	770	< 0.57 U	< 0.12 U	71 J		< 0.35 U
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated	11	4200	330	0.12	12	780	< 0.56 U	< 0.11 U	79 J		< 0.35 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated	14	2400	630	0.031 J	19	840	< 0.58 U	< 0.12 U	43 J		< 0.36 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated	10	6300	560	0.036	20	1200	< 0.6 U	< 0.12 U	93 J		< 0.37 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated	9.6	12000	480	< 0.015 U	13	630	< 0.53 U	< 0.11 U	90 J		< 0.33 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated	8.8	20000	360	0.029 J	14	890	0.85 J	< 0.11 U	110 J		< 0.34 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated	92	2100	450	0.096	16	630	< 0.55 U	< 0.11 U	120 J		< 0.34 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated	8.5	3200	380	0.015 J	18	820	< 0.55 U	< 0.11 U	52 J		< 0.35 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated	7.5	7800	500	< 0.015 U	15	730	0.63 J	< 0.12 U	< 28 U		< 0.35 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated	5.1	4700	410	< 0.014 U	13	730	0.95 J	< 0.11 U	< 26 U		< 0.33 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated	11	6000 J-	660	0.019 J	15	790	< 0.58 UJ	< 0.12 UJ	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated	8.4	4800	510	< 0.016 U	15	680	< 0.59 U	< 0.12 U	54 J		< 0.37 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated	12	2300	400	< 0.017 U	19	910	< 0.62 U	< 0.13 U	< 31 U		< 0.39 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated	9.9	2300	760	0.019 J	17	780	< 0.56 U	< 0.11 U	51 J		< 0.35 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated	14	2900	1100	0.15	250	1200	< 1.1 U	< 0.22 U	56 J		< 0.34 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated	14	2100	750	< 0.015 U	16	730	< 0.56 U	< 0.11 U	56 J		< 0.35 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated	12	3500	600	0.014 J	17	790	< 0.63 U	< 0.13 U	66 J		< 0.4 U
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated	12	2100	550	0.097	15	800	< 0.58 U	< 0.12 U	< 29 UJ		< 0.36 U
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated	28	2300	440	0.061	24	870	< 0.58 U	< 0.12 U	63 J		< 0.36 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		15	260
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		13	110
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		16	220
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		19	400
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated		13	120
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated		22	62
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated		21	59
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated		24	62
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated		23	61
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated		21	69
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated		20	63
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated		25	78
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated		21	59
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated		23	61
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated		22	61
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated		23	63
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated		20	56
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated		15	71
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated		17	42
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated		19	95
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated		14	75
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated		13 T	66
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated		13	72
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		12	67
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		14	81
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		15	90
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		11	69
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated		26 T	190
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated		14	49
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated		12	47
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated		9.2	45
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		4.6	82
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		3.3 J	48
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		3.8 J	53
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		4.3	77
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated		1.9 J	58
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated		4.8	59
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated		2.3 J	61
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated		2.3 J	43
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated		17	60
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated		15	55
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated		15	100
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated		13	57
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 56.6 U	14.3	61.5
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated		11	54
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated		7.4	36
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated		8.9	44
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated		7.8	43
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated		11	48
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated		21	69 J+
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated		10	55
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated		11	57
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated		12	48
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated		10	47
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated		13	50
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated		15	96
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated		13	43
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated		16	54
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated		12	63
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated		8.6	44
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated		10	42
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated		16	100
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated		13	59
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated		10	79
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated		10	49
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated		12	53 J-
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated		16	49
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated		15	73
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated		13	54
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated		17	95
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated		11	60
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated		15	63
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated		13	49
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated		13	59

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated	7400	< 0.38 U	6.6	43	0.32 J	0.069 J	1200	10		6.5	20	16000
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated	8300	< 0.38 U	7	60	0.4 J	0.1 J	6500	11		7.7	22	18000
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated	4200	< 0.36 U	3	25	0.14 J	0.062 J	34000	6.1		3.8 J	18	10000
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated	6200	< 0.34 U	3.3	49	0.22 J	0.12 J	35000	8.4		5.4	13	14000
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated	5900	< 0.37 U	3.7	39	0.21 J	0.09 J	45000	8		4.9 J	21	14000
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated	6600	< 0.36 U	5.1	65	0.26 J	0.1 J	27000	9.2		6.1	20	17000
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated	5600	< 0.38 U	5.4	38	0.26 J	0.25 J	1300	7.4		4.6 J	14	12000
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated	8400	< 0.39 U	5.5	44	0.36 J	0.089 J	17000	9.3		5.6 J	22	16000
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated	12000	0.42 J	11	110 J-	0.55	0.1 J	12000	16 J-		10	33 J-	24000
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated	9300	< 0.39 U	5.6	55	0.35 J	0.073 J	590	12		9	21	19000
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated	8400	< 0.4 U	5.5	52	0.34 J	0.078 J	14000	10		5.7 J	30	15000
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated	10000	< 0.38 U	7	70	0.42 J	0.072 J	1400	14		7.6	22	20000
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated	9900	< 0.42 U	8.1	54	0.41 J	0.049 J	820	11		7.5	24	20000
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated	11000	< 0.39 UJ	6.7	49	0.46	0.078 J	1200	14		7.3	20	20000
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated	11000	< 0.4 U	6.3	48	0.45 J	< 0.043 U	710	13		7.1	20	19000
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated	11000	0.55 J	6	62	0.44 J	0.067 J	960	13		7.2	25	19000
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated	11000	0.46 J	6.8	42	0.44 J	0.05 J	640	13		8.2	33	19000
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated	6700	< 0.39 U	4.8	53	0.28 J	0.057 J	800	8.2		5.6 J	14	14000
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated	6600	< 0.37 UJ	5.6	45 J-	0.31 J	0.46 J	41000	11		6.6	40 J-	15000
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated	4800	< 0.36 U	4.3	62	0.21 J	0.14 J	41000	8.1		4.9 J	14	12000
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated	7000	< 0.38 U	5.6	73	0.29 J	0.13 J	27000	9.5		6.2	23	17000
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated	5700	< 0.4 U	4.3	54	0.25 J	0.054 J	5300	10		4.8 J	16	13000
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated	6500	< 0.38 U	3.4	62	0.24 J	0.083 J	34000	10		5.6	17	15000
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated	12000	0.39 J	9.4	91	0.56	0.089 J	1900	14		8.6	23	23000
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated	7600	0.41 J	6.5	72	0.33 J	0.12 J	9200	11		6.1	18	15000
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated	7100	< 0.38 U	6.3	54	0.28 J	0.076 J	4100	11		6	31 J	17000
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated	4900	< 0.35 U	5.5	24	0.23 J	0.064 J	17000	6.8		4.2 J	13	12000
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated	6100	< 0.38 U	6.3	36	0.28 J	0.09 J	950	8.7		5.1 J	17	14000
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated	5500	< 0.38 U	5.1	33	0.24 J	0.09 J	34000	7.2		5 J	17	13000
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated	6400	< 0.36 U	4.5	40	0.26 J	0.064 J	18000	9.4		6.5	18	15000
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated	6100	< 0.37 U	5.4	61	0.26 J	0.051 J	4100	7.7		5.2 J	14	15000
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated	6400	0.39 J	6.7	44	0.26 J	0.11 J	3300	9		5.5	16	16000
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated	5600	1.4	9.9	62	0.47	0.77	38000	39		7.7	250	53000
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated	6600	0.41 J	5.4	56	0.24 J	0.072 J	1300	8.1		5.6	19	17000
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated	5700	< 0.37 U	5.2	75	0.24 J	0.075 J	47000	9.1		4.9 J	18	14000
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated	4800	0.53 J	4.4	35	0.2 J	0.078 J	20000	6.4		4.4 J	15	12000
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated	4900	< 0.39 U	6.1	35	0.25 J	0.15 J	44000	7.1		5 J	16	13000
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated	5200	< 0.38 U	5.2	35	0.24 J	0.095 J	23000	16		4.7 J	15	14000
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated	6900	< 0.35 U	4.6	67	0.26 J	0.17 J	42000	10		6.4	20	15000
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated	5300	< 0.38 U	4.4	30	0.2 J	0.093 J	72000	7.3		4.8 J	20	13000
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated	5100	< 0.37 U	5.4	30	0.21 J	0.13 J	13000 J	7.4		5.5	16	14000
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated	6800	< 0.4 U	4.9	47	0.24 J	0.087 J	35000	10		5.6 J	23	16000
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated	5300	< 0.37 U	5.8	45	0.23 J	0.34 J	49000	11		5.2 J	41	17000
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated	5300	< 0.34 U	4.1	29	0.25 J	0.11 J	38000	7.5		5 J	15	12000
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated	4700	< 0.4 U	4.3	25	0.2 J	0.083 J	22000	7		4.3 J	16	12000
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated	5700	0.42 J	5.5	47	0.26 J	0.073 J	12000	7.6		5.2 J	17	14000
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated	5800	< 0.36 U	4.2	46	0.22 J	0.077 J	46000	9		4.7 J	23	14000
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated	7800	< 0.37 U	6.3	99	0.32 J	0.074 J	900	10		7	19	16000
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated	8600	< 0.4 UJ	7.7	63	0.38 J	0.072 J	3400 J	11		7.4	21	19000 J
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated	8200	< 0.39 U	6.7	97	0.35 J	0.091 J	770	11		6.8	24	18000
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated	10000	0.47 J	7	51	0.43 J	0.074 J	1000	12		6.7	20	19000
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated	5200	< 0.36 U	3.8	46	0.23 J	0.075 J	18000	15		4.3 J	15	13000
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated	6400	< 0.39 UJ	4.1	46	0.26 J	0.089 J	38000	10		5.7	25	15000
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated	5800	0.59 J	6.2	39	0.25 J	0.1 J	11000	9.4		5.4 J	17	15000
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	4500	< 0.35 U	7.3	33	0.33 J	0.1 J	25000	6.3		4.9 J	15	13000
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated	6600	< 0.37 U	5.2	51	0.26 J	0.11 J	42000	8.4		6	24	15000
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated	5700	< 0.35 U	4.5	39	0.22 J	0.095 J	45000	7		5.1 J	20	13000
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated	6100	< 0.37 U	5.7	46	0.28 J	0.095 J	27000	9.5		5.8	23	14000
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated	5600	< 0.38 U	5.7	41	0.24 J	0.13 J	32000	7.3		5.5 J	17	13000
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated	6100	< 0.36 UJ	5.8	37	0.27 J	0.23 J	6100	9.2		5.9	17	15000
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	8300	< 0.35 U	6.2	99	0.38 J	0.12 J	7400	9.6		6.3	21	16000
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated	4800	< 0.38 U	4.6	33	0.21 J	0.15 J	28000	7.4		4.7 J	17	12000
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated	4200	< 0.36 U	5.3	27	0.22 J	0.13 J	2600	6		4.5 J	15	12000
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated	4400	< 0.36 U	4.5	24	0.22 J	0.09 J	8800	6		4.5 J	15	12000
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated	3900	< 0.36 U	3.3	30	0.15 J	0.083 J	29000	6.5		3.3 J	13	9000
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated	4700	< 0.29 U	4.1	36	0.18 J	0.11 J	31000	7.4		4.3	14	11000
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated	4400	< 0.32 U	4.7	30	0.18 J	0.1 J	8000	7.8		3.7 J	17	11000
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated	4900	< 0.33 U	5	38	0.22 J	0.13 J	36000	6.9		4.6 J	22	12000
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated	5700	< 0.33 U	6.1	38	0.25 J	0.17 J	5700	8		4.5 J	19	13000
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated	5600	< 0.31 U	4.5	37	0.24 J	0.094 J	4700	9.9		4.9	17	14000
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated	5100	< 0.4 U	2.9	39	0.2 J	0.11 J	20000	6.7		4.8 J	14	13000
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated	6700	< 0.32 U	4.7	30	0.25 J	0.11 J	23000	8.8		5.7	39	16000
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated	5200	< 0.32 U	5.5	35	0.21 J	0.12 J	19000	12		5	16	13000
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated	7100	< 0.35 U	5.5	69	0.35 J	0.16 J	23000	12		6.2	27	15000

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated	10	2000	430	< 0.016 U	15	740	< 0.58 U	< 0.12 U	47 J		< 0.36 U
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated	12	2300	520	0.021 J	18	810	< 0.57 U	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated	3.4	5400	260	< 0.013 U	9	450 J	0.66 J	< 0.11 U	57 J		< 0.34 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated	7.9	7500	640	< 0.015 U	14	630	0.67 J	< 0.11 U	77 J		< 0.33 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated	26	11000	360	< 0.016 U	12	730	0.77 J	< 0.12 U	79 J		< 0.35 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated	9.5	9200	690	< 0.014 U	15	660	< 0.54 U	< 0.11 U	68 J		< 0.34 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated	5.9	1700	730	0.015 J	13	770	< 0.58 U	< 0.12 U	43 J		< 0.36 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated	9	2500	460	< 0.015 U	13	930	< 0.59 U	< 0.12 U	97 J		< 0.37 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated	16	2900 J-	760	< 0.015 U	24	1300 J-	< 0.58 U	< 0.12 U	75 J		< 0.36 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated	9.9	2700	550	< 0.014 U	19	720	< 0.59 U	< 0.12 U	42 J		< 0.37 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated	10	6800	480	< 0.016 U	14	780	< 0.6 U	< 0.12 U	67 J		< 0.38 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated	12	2700	440	0.051	21	850	< 0.57 U	< 0.12 U	57 J		< 0.36 U
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated	12	2300	440	0.033 J	18	930	< 0.63 U	< 0.13 U	58 J		< 0.39 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated	16	2600	340	0.17	17	830	< 0.59 U	< 0.12 U	47 J		< 0.37 U
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated	8.4	2700	400	0.023 J	17	830	< 0.6 U	< 0.12 U	61 J		< 0.37 U
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated	11	2600	520	0.069	17	830	< 0.61 U	< 0.12 U	76 J		< 0.38 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated	12	2700	360	0.073	17	810	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated	7.4	1700	540	0.019 J	12	490 J	< 0.6 U	< 0.12 U	64 J		< 0.37 U
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated	21 J-	11000 J	550	0.81	23	830	1.1	< 0.11 U	85 J		< 0.35 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated	8	8300	360	< 0.014 U	12	680	1	< 0.11 U	72 J		< 0.34 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated	6.8	11000	680	< 0.015 U	16	690	< 0.57 U	< 0.12 U	69 J		< 0.36 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated	6.5	2900	560	< 0.015 U	11	680	< 0.6 U	< 0.12 U	73 J		< 0.37 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated	6.2	7700	430	< 0.014 U	12	770	< 0.58 U	< 0.12 U	69 J		< 0.36 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated	13	3500	490	< 0.018 U	22	1300	< 0.59 U	< 0.12 U	53 J		< 0.37 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated	11	4300	670	0.024 J	16	940	< 0.6 U	< 0.12 U	57 J		< 0.37 U
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated	16	2300	500	< 0.013 U	18	690	< 0.58 U	< 0.12 U	45 J		< 0.36 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated	5.4	7400	320	< 0.012 U	11	580	< 0.52 U	< 0.11 U	49 J		< 0.33 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated	16	1900	410	0.018 J	13	690	< 0.57 U	< 0.12 U	44 J		< 0.36 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated	7.8	9100	330	< 0.017 U	12	680	0.59 J	< 0.12 U	72 J		< 0.36 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated	33	6300	510	< 0.015 U	14	670	< 0.54 U	< 0.11 U	81 J		< 0.34 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated	6.4	3000	390	< 0.015 U	12	730	< 0.57 U	< 0.12 U	52 J		< 0.35 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated	9.5	2300	580	< 0.018 U	13	640	< 0.55 U	< 0.11 U	40 J		< 0.34 U
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated	67	8100	760	0.12	85	620	0.89 J	< 0.12 U	95 J		< 0.37 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated	9	2100	590	0.024 J	14	690	< 0.56 U	< 0.11 U	41 J		< 0.35 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated	8	22000	600	< 0.015 U	13	700	1 J	< 0.12 U	91 J		< 0.35 U
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated	5.2	4300	310	< 0.014 U	11	510 J	< 0.54 U	< 0.11 U	63 J		< 0.34 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated	8.1	7600	460	< 0.014 U	13	680	0.6 J	< 0.12 U	68 J		< 0.37 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated	8	7000	400	< 0.017 U	12	610	< 0.57 U	< 0.12 U	60 J		< 0.36 U
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated	9	10000	720	< 0.015 U	15	690	< 0.53 U	< 0.11 U	67 J		< 0.33 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated	6.7	25000	500	< 0.015 U	12	690	0.95 J	< 0.12 U	110 J		< 0.35 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated	6.8	3300	520	< 0.016 U	13	510 J	< 0.56 U	< 0.11 U	79 J		< 0.35 U
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated	11	8800	540	< 0.014 U	14	760	< 0.6 U	< 0.12 U	81 J		< 0.37 U
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated	19	9100	490	0.059	28	620	0.71 J	< 0.11 U	99 J		< 0.35 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated	5.7	4600	350	< 0.015 U	13	550	0.6 J	< 0.11 U	71 J		< 0.32 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated	6.3	12000	390	< 0.016 U	11	630	< 0.61 U	< 0.12 U	64 J		< 0.38 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated	6.8	5600	400	0.016 J	12	860	< 0.56 U	< 0.11 U	55 J		< 0.35 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated	11	23000	330	0.02 J	12	830	0.75 J	< 0.11 U	88 J		< 0.34 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated	7.9	2300	440	0.019 J	17	860	< 0.55 U	< 0.11 U	40 J		< 0.35 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated	10	3500 J	520 J	< 0.016 U	18	970	< 0.6 U	< 0.12 U	< 30 U		< 0.37 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated	11	2400	530	< 0.015 U	16	940	< 0.59 U	< 0.12 U	42 J		< 0.37 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated	10	2500	430	< 0.014 U	16	740	< 0.59 U	< 0.12 U	< 30 U		< 0.37 U
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated	6.2	3800	340	< 0.013 U	11	660	< 0.55 U	< 0.11 U	62 J		< 0.34 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated	6.6	8500 J	460	< 0.015 U	13	660	< 0.59 U	< 0.12 U	66 J		< 0.36 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated	6.7	2700	510	< 0.015 U	13	660	< 0.63 U	< 0.13 U	47 J		< 0.39 U
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	7.2	9400	430	< 0.014 U	11	610	< 0.53 U	< 0.11 U	59 J		< 0.33 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated	7.5	12000	480	< 0.014 U	15	790	< 0.55 U	< 0.11 U	78 J		< 0.35 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated	13	11000	380	< 0.013 U	13	600	0.58 J	< 0.11 U	98 J		< 0.33 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated	7.1	8300	520	< 0.013 U	13	860	0.79 J	< 0.12 U	80 J		< 0.35 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated	7.6	4400	540	< 0.015 U	13	790	< 0.58 U	< 0.12 U	78 J		< 0.36 U
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated	13	3200	410	< 0.022 U	13	610	< 0.54 U	< 0.11 U	92 J		< 0.34 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	16	4200	590	0.037	14	700	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated	9.4	7600	630	0.06	12	520 J	< 0.58 U	< 0.12 U	< 68 U		< 0.36 U
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated	6.6	1800	320	< 0.025 U	11	520 J	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated	6.6	2300	350	< 0.024 U	11	610	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated	6.2	4800	230	0.036	8.7	430 J	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated	11	8800	390	0.043	11	500	< 0.44 U	< 0.09 U	63 J		< 0.28 U
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated	9.6	2300	340	0.072	10	430 J	< 0.48 U	< 0.098 U	< 56 U		< 0.3 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated	9.8	11000	340	< 0.024 U	11	740	< 0.5 U	< 0.1 U	88 J		< 0.31 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated	39	1900	340	0.028 J	12	560	< 0.51 U	< 0.1 U	< 59 U		< 0.32 U
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated	8.1	2100	560	0.082	11	530	< 0.47 U	< 0.096 U	< 55 U		0.29 J
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated	8	3600	540	< 0.025 U	12	450 J	< 0.6 U	< 0.12 U	< 71 U		< 0.37 U
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated	6.6	11000	390	< 0.021 U	15	640	< 0.49 U	< 0.1 U	63 J		< 0.31 U
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated	11	5500	430	< 0.022 U	13	550	< 0.48 U	< 0.099 U	< 57 U		< 0.3 U
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated	31	4000	470	0.065	18	620	0.59 J	< 0.11 U	< 62 U		< 0.33 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated		12	56
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated		13	59
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated		7.2	34
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated		8.8	53
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated		8.8	43
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated		10	49
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated		9.2	49
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated		15	55
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated		21 J-	110 J-
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated		15	67
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated		14	44
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-B3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated		15	59
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated		16	61
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated		17	62
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated		16	49
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated		16	55
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated		16	66
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated		10	46
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated		12	300
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated		8.8	86
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated		10	63
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated		9.4	46
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated		11	44
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated		19	88
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated		12	57
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated		11	59
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated		9.2	36
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated		11	44
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated		9.8	48
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated		13	50
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated		11	69
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated		10	50
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated		11	230
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated		10	60
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated		10	42
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated		8.3	43
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated		8.8	40
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated		12	41
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated		10	60
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated		9.1	41
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated		8.2	42
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated		10	58
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated		9.2	98
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated		8.8	45
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated		8.5	37
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated		10	56
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated		12	36
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated		13	55
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated		15	60
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated		14	75
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated		17	65
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated		9	45
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated		11	42 J-
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated		11	52
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated		9.8	39
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated		10	52
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated		8.2	44
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated		10	45
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated		10	51
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated		12	56
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated		13	75
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated		9.8	40
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated		8.4	41
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated		8.1	34
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated		7.2	31
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated		9.5	41
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated		10	49
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated		9	45
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated		8.8	62
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated		9.2	42
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated		10	43
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated		11	54
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated		8.9	48
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated		13	63

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated	5900	< 0.31 U	4.1	41	0.22 J	0.15 J	21000	8.9		5.4	23	14000
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated	6100	< 0.35 U	4.8	41	0.24 J	0.14 J	6100	8.5		5.4	16	14000
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated	6600	< 0.36 U	3.7	37	0.23 J	0.092 J	9100	10		5.2 J	18	15000
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated	5800	< 0.27 U	5.7	35	0.25 J	0.1 J	16000	8.4		5.4	31	14000
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated	3900	< 0.36 U	5.3	100	0.22 J	0.14 J	27000	6.5		4.1 J	26	10000
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated	5600	< 0.29 U	5.7	34	0.21 J	0.095 J	25000	9		5.4	19	14000
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated	6400	0.35 J	5.1	40	0.28 J	0.092 J	1300	8.7		5.6	19	14000
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	3800	< 0.31 U	3.5	29	0.19 J	0.072 J	17000	7.3		4.5	10	9500
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	6500	0.44 J	6.0	42	0.24 J	0.17 J	10000	10		5.4	20	14000
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	7000	0.36 J	7.3	36	0.28 J	0.12 J	9700	8.9		5.2	19	14000
Northern Athletic Field	SSHS-B3853	091721 09:30_SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated	4900	< 0.33 U	3.7	59 J	0.2 J	< 0.036 UJ	8300 J	9.5		3.6 J	14	10000
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	4700	< 0.35 U	5.5	29	0.18 J	0.081 J	60000	6.7		4.5 J	14	11000
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	7800	< 0.33 U	5.2	40	0.31 J	< 0.035 U	13000	14		5.7	20	15000
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated	8000	< 0.37 U	7.4	66	0.35 J	0.11 J	2500	9.2		6.1	18	15000
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated	7300	0.37 J	7.1	87	0.34 J	0.22 J	4700	10		5.0	45	16000
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated	12000	< 0.39 U	13	120	0.53 J	0.49 J	4000	14		8.5	24	19000
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated	8600	< 0.37 U	8.7	85	0.45 J	0.19 J	14000	9.6		7.2	33	17000
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated	5900	< 0.33 U	6.1	26	0.27 J	0.094 J	910	7.0		5.0	17	13000
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated	6500	< 0.29 U	5.8	31	0.29 J	0.064 J	520	7.7		5.8	16	14000
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated	7400	< 0.34 U	6.8	72	0.36 J	0.15 J	12000	9.0		5.9	23	17000
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated	5800	< 0.33 U	9.3	36	0.24 J	0.089 J	24000	7.8		5.9	24	14000
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated	5000	< 0.36 U	4.4	35	0.24 J	0.14 J	5100	6.6		5.5	15	12000
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated	4700	0.28 J	4.3	25	0.19 J	0.084 J	7400	6.1		4.9	15	12000
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated	6300	< 0.34 U	6.7	42	0.30 J	0.095 J	4200	8.5		6.0	20	16000
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated	5300	< 0.27 U	8.0	34	0.25 J	0.079 J	7400	6.9		5.5	28	14000
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated	4500	< 0.34 U	4.6	33	0.19 J	0.094 J	28000	5.8		4.7	17	12000
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated	5000	< 0.27 U	3.9	29	0.18 J	0.17 J	25000	6.8		5.1	18	13000
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated	4700	< 0.26 U	3.6	22	0.18 J	0.13 J	23000	5.9		4.6	14	12000
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated	5300	< 0.30 U	5.8	49	0.22 J	0.098 J	31000	6.7		4.9	17	13000
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated	4900	0.31 J	3.9	29	0.20 J	0.089 J	7400	6.9		5.1	20	13000
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated	5500	< 0.27 U	4.2	28	0.22 J	0.070 J	11000	7.3		5.4	19	14000
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated	4300	< 0.35 UT	3.6	21	0.18 J	0.078 J	18000 T	5.9		4.4	13	11000
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated	5800	< 0.33 UT	9.3	36	0.24 J	0.089 J	24000	7.8		5.9	24	14000
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated	4800	< 0.36 U	6.6	31	0.23 J	0.11 J	19000	6.4		4.9	20	13000
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated	9000	< 0.36 U	6.1	100	0.37 J	< 0.048 U	1500	9.9		5.7	16	15000
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated	10000	< 0.37 U	7.1	87	0.41 J	0.078 J	1500	12		6.4	31	18000
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	8400	< 0.38 U	7.1	72	0.44 J	0.12 J	2400	11		6.6	22	18000
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	9200	< 0.32 U	6.2	86	0.47	0.10 J	1600	12		7.1	35	19000
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	7600	< 0.40 U	6.7	68	0.37 J	0.15 J	2000	27		6.9	230	22000
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated	5400	< 0.33 U	3.8	45	0.24 J	0.048 J	730	6.1		4.9	20	12000
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated	11000	< 0.32 U	9.0	58	0.49	0.080 J	1200	12		8.5	23	20000
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated	8500	< 0.34 U	6.2	29	0.35 J	0.048 J	530	9.6		6.1	18	16000
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated	11000	< 0.36 U	7.7	65	0.49 J	0.056 J	850	12		9.1	19	19000
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	4200	< 0.25 U	3.9	27	0.17 J	0.081 J	25000	5.5		4.4	21	10000
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	7600	< 0.20 UT	7.3 T	41 T	0.36 T	< 0.047 UT	370 T	8.8 T		6.4	18	16000
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	7000	< 0.23 U	6.2	42	0.33	0.067 J	1100	8.1		6.8	21	15000
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	8200	< 0.18 U	6.0	52	0.37	< 0.043 U	1000	9.3		6.1	17	15000
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	6600	< 0.22 U	6.9	58	0.34	0.098 J	860	8.6		5.5	17	15000
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	8700	< 0.26 U	9.0	47	0.46	< 0.064 U	1100	12		7.2	23	20000
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	5300	0.27 J	6.2	56	0.25 J	0.76	3500	9.7		5.3	43	14000
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	5600	< 0.23 U	6.0	45	0.24 J	0.089 J	4800	7.4		5.6	19	14000
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	4100	< 0.18 U	4.0	27	0.16 J	0.072 J	28000	4.7		3.6	15	8700
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	5300	< 0.19 U	5.8	40	0.23 J	0.22 J	12000	8.6		5.4	44	16000
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	3300	< 0.17 U	2.9	17	0.12 J	0.053 J	19000	4.2		3.1	11	8000
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	5900	0.37 J	7.7	60	0.29	3.0	5700	9.4		6.3	67	17000
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	7700	0.24 J	6.7	58	0.33	0.34	2300	9.6		6.6	31	17000
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	6400	< 0.22 U	7.8	56	0.28 J	0.19 J	1300	8.6		5.5	29	15000
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	3900	< 0.21 U	4.2	44	0.15 J	0.091 J	22000	6.3		4.1	24	9500
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	5500	0.22 J	7.3	47	0.29	0.14 J	14000	6.6		5.8	23	15000
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	5600	< 0.32 U	5.4	35	0.27 J	0.10 J	750	7.2		5.3	16	14000
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	6600	< 0.42 U	11	120	0.54 J	0.18 J	900	8.0		6.8	27	22000
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	4800	< 0.25 U	4.7	27	0.21 J	< 0.060 U	950	5.8		4.5	16	12000
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	6200	< 0.28 U	8.5	40	0.29 J	0.086 J	50000	7.4		6.8	19	14000
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	7800	< 0.26 U	7.2	42	0.37	0.074 J	2300	9.3		6.9	25	18000
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	7100	< 0.29 U	6.7	50	0.34 J	< 0.070 U	6200	8.8		7.0	21	16000
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	6300	0.29 J	6.2	60	0.39	0.085 J	2200	9.1		5.1	37	15000
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	4300	< 0.28 U	3.3	24	0.18 J	< 0.067 U	21000	5.3		4.0 J	17	11000
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	6200	< 0.20 U	7.3	74	0.34	0.088 J	4100	7.7		6.1	25	15000
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	6100	< 0.21 U	8.4	43	0.30	0.069 J	780	7.7		6.8	17	14000
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	5600	< 0.22 U	4.4	37	0.27 J	0.080 J	970	7.1		5.4	16	12000
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	4500 T	0.33 JT	9.1	85 T	0.32	0.17 J	3700	9.1		4.6	45	15000 T
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	4900	< 0.22 U	3.6	29	0.23 J	0.057 J	2200	5.9		4.5	20	11000
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	6200	< 0.22 U	4.8	32	0.25 J	< 0.053 U	540	7.1		5.6	18	13000
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	7500	< 0.22 U	6.2	58	0.39	0.088 J	1200	9.3		6.8	19	15000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated	6.4	3900	440	< 0.023 U	13	550	0.66 J	< 0.094 U	< 54 U		< 0.29 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated	8.1	3100	550	< 0.022 U	13	590	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated	9.1	3200	340	< 0.023 U	14	540	< 0.54 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated	12	8900	430	< 0.022 U	14	520	< 0.41 U	< 0.083 U	53 J		< 0.25 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated	7.5	14000	2000	< 0.022 U	9.9	640	< 1.1 U	< 0.22 U	87 J		< 0.68 U
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated	6.8	6600	490	< 0.021 U	13	610	< 0.44 U	< 0.089 U	79 J		< 0.27 U
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated	8.3	2000	540	< 0.022 U	15	910	< 0.53 U	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	4.1	4200	300	< 0.023 U	8.7	570	< 0.47 U	< 0.095 U	< 55 U		< 0.29 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	15	4800	400	0.020 J	14	610	< 0.48 U	< 0.098 U	< 56 U		0.59 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	9.3	1900	270	0.028 J	16	500	< 0.42 U	< 0.086 U	< 49 U		0.74 J
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated	7	3300 J	320	< 0.019 U	9.2	740	< 0.5 U	< 0.1 U	65 J		< 0.31 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	6.2	14000	350	< 0.019 U	12	570	0.98 J	< 0.11 U	74 J		< 0.33 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	8.4	4000	440	< 0.016 U	15	780	< 0.5 U	< 0.1 U	< 58 U		< 0.31 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated	19	2200	350	0.24	15	660	< 0.49 U	< 0.085 U	< 65 U		< 0.42 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated	45	1600	290	0.10	18	450	< 0.41 U	< 0.070 U	69 J		< 0.34 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated	140	2600	490	0.37	19	910	< 0.51 U	< 0.088 U	< 68 U		< 0.44 U
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated	45	2700	490	0.15	18	720	0.56 J	< 0.084 U	67 J		< 0.42 U
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated	6.3	1800	310	< 0.021 U	14	560	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated	6.5	2000	330	< 0.020 U	15	570	< 0.38 U	< 0.066 U	< 51 U		< 0.32 U
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated	19	3100	380	0.13	16	630	< 0.44 U	< 0.076 U	69 J		< 0.37 U
Northern Athletic Field	B201	110421 09:45 SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated	6.8	4300	310	0.066 J	14	910	0.44 J	< 0.075 U	58 J		< 0.37 U
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated	6.2	2700	680	0.059 J	13	480 J	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated	5.0	3300	360	< 0.018 U	12	380	< 0.34 U	< 0.058 U	< 45 U		< 0.29 U
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated	8.8	3300	610	< 0.021 U	16	620	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated	5.8	3500	370	< 0.018 U	13	400	< 0.35 U	< 0.060 U	< 47 U		< 0.30 U
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated	6.2	4500	300	< 0.019 U	11	530	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated	5.1	2700	500	< 0.016 U	13	470	< 0.35 U	< 0.060 U	< 47 U		< 0.30 U
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated	4.4	2100	290	< 0.017 U	12	420	< 0.34 U	< 0.059 U	< 46 U		< 0.29 U
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated	5.9	6000	340	< 0.018 U	12	540	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated	6.1	2400	330	< 0.019 U	13	340 J	< 0.37 U	< 0.064 U	< 50 U		< 0.32 U
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated	7.2	6100	400	< 0.016 U	14	470	< 0.35 U	< 0.060 U	< 47 U		< 0.30 U
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated	6.0	3400 T	310 T	< 0.019 U	10	410 J	0.56 J	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated	6.8	4300	310 T	0.066 J	14	910	0.44 J	< 0.075 U	58 J		< 0.37 U
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated	6.1	5600	650	< 0.022 U	12	560	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated	17	1600	510	0.084 J	13	480 J	0.56 J	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated	77	2100	370	0.049 J	21	560	< 0.48 U	< 0.083 U	< 65 U		< 0.41 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	11	2300	470	0.024 J	17	870	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	15	2400	480	0.034 J	25	710	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	71	2100	400	0.062 J	110	590	< 0.52 U	< 0.090 U	< 70 U		< 0.44 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated	7.7	1500	470	0.022 J	12	430 J	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated	12	2400	520	0.030 J	20	830	< 0.42 U	< 0.072 U	< 56 U		< 0.36 U
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated	7.2	2200	270	< 0.020 U	15	610	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated	14	2300	780	0.024 J	18	710	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	7.2	9500	290	< 0.017 U	11	460	0.45 J	< 0.077 U	46 J		< 0.23 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	8.3	1800	260	0.042	15	400 T	< 0.30 UT	< 0.067 UT	< 33 UT		< 0.18 UT
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	10	1800	780	0.033	15	540	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	13	1900	400	0.14	15	370	0.31 J	< 0.061 U	< 30 U		< 0.17 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	9.8	2700	470	0.027 J	17	810	< 0.34 U	< 0.076 U	< 38 U		< 0.21 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	14	2600	570	0.024 J	17	790	0.42 J	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	27	2300	420	0.043	34	390	0.55 J	< 0.074 U	< 37 U		< 0.20 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	10	2900	500	0.069	15	490	< 0.35 U	< 0.080 U	< 39 U		0.26 J
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	5.9	8200	350	< 0.020 U	9.1	370	0.67	< 0.063 U	55 J		< 0.17 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	21	3000	340	0.069	22	430	0.47 J	< 0.065 U	< 32 U		< 0.18 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	3.7	1700	220	< 0.017 U	8.0	280 J	0.50 J	< 0.060 U	< 29 U		< 0.16 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	23	3100	400	0.059	43	470	0.92	< 0.071 U	59 J		< 0.19 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	21	2600	400	0.040	22	480	0.52 J	< 0.070 U	< 34 U		< 0.19 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	21	1900	420	0.067	16	470	0.56 J	< 0.075 U	< 37 U		< 0.21 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	7.1	3200	380	< 0.018 U	11	390	0.48 J	< 0.073 U	< 36 U		< 0.20 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	46	9500	670	0.030	15	540	0.45 J	< 0.076 U	< 37 U		< 0.21 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	6.5	1900	330	< 0.021 U	15	530	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	12	1800	2000	0.041 B	18	670 J	< 0.64 U	< 0.14 U	< 71 U		0.22 J
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	5.8	1600	300	< 0.018 U	12	390 J	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	12	10000	400	0.039	16	790	0.66 J	< 0.098 U	63 J		< 0.27 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	11	3200	380	0.043	19	640	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	15	4600	460	0.043	17	690	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	15	1500	350	0.27	16	380 J	0.58 J	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	4.6	2400	290	0.028 J	10	350 J	0.67 J	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	16	2000	480	0.090	16	410	0.31 J	< 0.069 U	< 34 U		< 0.19 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	7.4	1900	410	< 0.022 U	18	580	< 0.32 U	< 0.072 U	120 J		< 0.20 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	7.3	1600	410	< 0.021 U	13	510	< 0.34 U	< 0.076 U	47 J		< 0.21 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	37 T	1100	150 T	0.055	23 T	370 JT	0.70 JT	< 0.084 U	110 J		< 0.23 UT
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	4.7	2100	340	< 0.016 U	13	500	< 0.33 U	< 0.075 U	92 J		< 0.21 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	5.8	1800	350	< 0.024 U	15	520	< 0.33 U	< 0.075 U	90 J		< 0.21 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	8.8	2100	520	0.047	17	680	< 0.33 U	< 0.074 U	58 J		< 0.20 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated		9.2	74
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated		10	61
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated		11	45
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated		9.7	48
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated		7.3	36
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated		10	45
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated		10	53
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated		7.2	28
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated		11	47
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated		12	46
Northern Athletic Field	SSHS-B3853	091721 09:30_SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated		9.3	34
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated		7.9	35
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated		12	50
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated		14	53
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated		13	73
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated		19	120
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated		15	78
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated		10	45
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated		11	43
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated		13	62
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated		9.6	47
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated		7.9	63
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated		7.2	48
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated		11	73
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated		8.5	64
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated		7.9	40
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated		8.1	60
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated		7.0	90
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated		8.3	56
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated		7.6	46
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated		8.7	50
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated		6.7	50
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated		9.6	47
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated		8.2	56
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated		14	170
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated		16	63
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated		15	59
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated		15	63
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated		12	100
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated		7.6	39
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated		17	66
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated		12	46
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated		16	64
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated		7.5	37
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated		14 T	44 T
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated		12	56
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated		13	43
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated		11	52
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated		17	71
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated		10	130
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated		9.7	53
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated		6.9	32
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated		9.9	140
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated		5.1	24
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated		11	130
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated		13	81
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated		11	110
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated		7.1	34
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated		9.5	100
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated		8.9	54
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated		20	64
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated		7.2	39
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated		9.6	47
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated		12	100
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated		11	59
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated		10	46
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated		6.5	36
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated		11	60
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated		11	45
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated		8.9	57
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated		11 T	78 T
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated		7.6	38
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated		9.3	41
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated		12	56

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	5600	< 0.29 UT	4.6	37	0.27 J	0.12 J	14000	7.1		4.7	18	15000
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	6500	< 0.32 UT	6.8	40	0.30 J	< 0.078 U	1300	8.4		4.9 J	19	15000
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	4000	< 0.24 U	3.6	17	0.15 J	0.062 J	44000	4.7		3.7 J	12	9800
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	3900	0.30 J	4.0	23	0.15 J	0.065 J	34000	5.1		4.1	15	10000
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	6300	< 0.28 UT	6.0 T	42 T	0.29 JT	0.072 JT	3700 T	7.5 T		5.5	21 T	14000
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	4900	0.30 J	5.6	56	0.21 J	0.11 J	40000	5.9		5.3	17	13000 B
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	3600	0.33 J	3.9	22	0.19 J	< 0.075 U	1100	4.6		2.7 J	13	8200
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	4400	0.31 J	4.0	47	0.19 J	0.11 J	25000	5.9		3.9 J	20	11000
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	4700	< 0.30 U	3.6	31	0.20 J	0.13 J	38000	6.2		4.5 J	17	12000
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	5100	0.44 J	3.8	40	0.22 J	0.13 J	6000	6.6		4.9	29	14000
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	4100	< 0.20 U	3.9	34	0.17 J	0.093 J	27000	5.1		4.1	12	9900
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	3500	< 0.23 U	2.5	17	0.14 J	0.068 J	17000	4.4		3.4 J	16	8600
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	4400	< 0.29 U	3.9	33	0.19 J	0.12 J	36000	5.6		4.1 J	15	11000
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	5200	< 0.27 U	4.6	27	0.22 J	< 0.066 U	11000	6.4		4.5	16	13000
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	5500	< 0.29 U	5.3	36	0.26 J	< 0.070 U	980	7.1		4.8	15	14000
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	5100	< 0.26 U	4.5	27	0.22 J	< 0.062 U	3200	6.2		5.2	14	12000
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	5200	< 0.24 U	5.3	27	0.22 J	< 0.059 U	14000	6.5		5.0	15	13000
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	6100	0.77 J	6.1	36	0.26 J	< 0.074 U	4900	7.4		5.0 J	170	14000
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	6800	< 0.30 U	5.8	46	0.28 J	< 0.072 U	1500	8.0		5.2	19	14000
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	4600	< 0.23 U	3.2	36	0.19 J	0.076 J	23000	6.0		4.3	13	9900
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	5000	< 0.21 U	4.0	35	0.20 J	0.062 J	19000	6.3		4.7	17	12000
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	4000	< 0.20 UT	2.9 T	33 T	0.16 JT	0.14 J	65000 T	5.1 T		4.2	16 T	9200
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	3800	< 0.21 U	3.4	26	0.16 J	0.075 J	45000	4.9		3.7	12	8800
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	4100	< 0.23 U	3.1	32	0.16 J	0.076 J	26000	5.0		4.0	13	9400
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	3600	< 0.21 U	2.6	23	0.14 J	0.085 J	45000	5.5		3.7	14	8600
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	6900	< 0.24 U	6.1	49	0.32	0.12 J	8600	8.8		7.1	23	15000
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	5500	< 0.20 U	4.0	37	0.22 J	0.088 J	19000	7.1		4.9	16	12000
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	5200	< 0.25 U	3.8	32	0.22 J	0.087 J	34000	6.4		4.4	16	11000
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	6200	< 0.20 U	4.4	38	0.24 J	0.080 J	24000	7.7		5.6	17	13000
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	7400	0.33 J	7.1	68	0.34 J	0.16 J	14000	12		6.6	31	16000
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	5400	< 0.33 U	7.5	71	0.34 J	0.11 J	3200	8.9		4.3 J	31	16000
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	4200	1.9	7.7	87	0.33 J	0.22 J	5300	72		4.2 J	50	17000
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	5400	< 0.23 U	4.7	25	0.20 J	< 0.056 U	850	6.4		3.8	12	11000
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	6400	0.31 J	12	33	0.30 J	< 0.074 U	3800	8.0		6.0	17	15000
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	6700	< 0.26 U	7.9	47	0.33 J	< 0.064 U	1300	8.8		5.6	18	17000
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	6100	< 0.32 U	5.1	31	0.26 J	< 0.078 U	550	7.1		4.6 J	15	13000
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	5400	< 0.28 U	5.3	47	0.24 J	< 0.069 U	410 J	6.7		4.7	15	13000
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	5900	< 0.29 U	5.8	31	0.28 J	< 0.071 U	550	6.8		5.5	14	14000
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	5800	< 0.29 U	6.4	46	0.28 J	< 0.069 U	5100	7.1		5.1	18	13000
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	5900 T	< 0.25 UT	4.9	31 T	0.24 J	0.15 J	26000	7.4 T		6.1	20 T	14000 BT
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	7700	0.38 J	5.0	56	0.32 J	0.66	1900	10		6.6	31	16000
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	10000	0.41 J	6.8	70	0.44 J	0.12 J	800	11		7.0	19	18000
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	11000	0.35 J	6.4	34	0.42	< 0.077 U	230 J	11		6.8	17	19000
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	9900	0.71 J	6.6	39	0.39 J	< 0.075 U	650	11		7.4	13	18000
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	8600	0.44 J	5.2	73	0.40 J	< 0.075 U	1100	9.2		5.6	14	13000
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	9200	0.37 J	5.9	84	0.37 J	1.0	18000	10		6.3	33	17000
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	8100	0.45 J	8.2	41	0.36 J	0.13 J	990	9.2		6.7	20	17000
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	8100	0.54 J	6.1	57	0.35 J	0.44 J	1500	10		6.9	33	19000
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	8300	0.36 J	9.7	29	0.32 J	< 0.073 U	630	9.3		5.5	20	16000
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	4900	0.39 J	3.8	33	0.17 J	< 0.070 U	520	5.8		4.5 J	15	11000
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	6000	< 0.54 UT	6.1	57	0.29 JT	< 0.13 UT	670 JT	6.8		5.6	16	15000
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	5200	0.44 J	4.3	44	0.20 J	0.13 J	7600	7.5		4.2 J	17	11000
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	7800	< 0.28 UT	6.4	31 T	0.38	< 0.068 U	1600 T	9.4 T		6.9	17 T	17000
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	10000	< 0.29 U	9.7	52	0.49	< 0.071 U	390 J	12		9.5	22	22000
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	8400	< 0.60 U	10	120	0.41 J	< 0.15 U	630 J	10		8.2	30	23000
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	7900	< 0.28 U	7.0	53	0.36 J	0.095 J	1500	9.7		6.5	27	17000
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	6700	< 0.27 U	6.8	47	0.32 J	< 0.065 U	750	8.5		6.8	19	15000
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	9500	< 0.30 U	6.1	42	0.39	< 0.072 U	690	10		7.4	20	18000
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	7900	< 0.29 U	5.4	54	0.31 J	< 0.070 U	690	8.9		7.3	17	16000
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	13000	0.38 J	7.9	45	0.45	< 0.079 U	1100	13		8.9	19	21000
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	12000	< 0.28 U	8.2	38	0.45	< 0.068 U	940	12		9.3	18	20000
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	8400	< 0.25 U	7.5	36	0.41	< 0.060 U	650	10		7.4	19	19000
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	10000	< 0.30 U	6.2	35	0.44	< 0.073 U	830	10		6.4	13	16000
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	6000	0.37 J	4.3	55	0.28 J	< 0.069 U	630	6.9		5.3	18	13000
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	6500	< 0.27 U	6.2	59	0.31 J	< 0.066 U	940	7.4		6.2	17	15000
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	7600 B	< 0.29 UT	6.2	42 T	0.35 J	< 0.070 U	730 T	8.1		6.4	16 T	15000
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	11000	< 0.31 U	7	51	0.42	< 0.075 U	610	13		7.2	15	19000
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	6600	0.34 J	8.8	49	0.33 J	0.12 J	8800	10		7.3	19	15000
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	4400	< 0.31 U	4.1	25	0.15 J	0.13 J	56000	7.3		4.3 J	19	11000
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	2700	< 0.29 U	1.7	16 J	0.10 J	< 0.071 U	170 J	3.3		2.3 J	6.0	5400
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	2200	0.99 J	2.4	20 J	< 0.12 U	< 0.077 U	3600	3.9		1.9 J	31	10000
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	6000	< 0.26 U	4.8	34	0.23 J	0.092 J	3100	8.1		5.3	16	14000
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	8900	< 0.31 U	8.4	60	0.36 J	0.13 J	1100	11		12	25	20000
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	7000	< 0.29 U	5.2	52	0.26 J	0.12 J	11000	9.0		5.8	23	15000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	5.7	2600	500	< 0.020 U	13	550	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	10	2000	370	< 0.022 U	15	630	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	4.6	4500	210	< 0.021 U	9.4	360 J	< 0.37 U	< 0.083 U	60 J		< 0.23 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	5.9	3300	510	< 0.016 U	9.7	380 J	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	11	3200 T	310	0.043 T	14 T	490 T	< 0.43 UT	< 0.097 UT	54 JT		< 0.27 UT
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	6.1	4700	610	< 0.022 U	13	530	0.61 J	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	4.5	870	220	0.029	6.4	430 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	9.3	3200	420	< 0.021 U	12	420 J	0.51 J	< 0.092 U	47 J		< 0.25 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	5.8	2900	330	< 0.019 U	12	440 J	0.71 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	13	2500	390	0.030	15	440 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	4.6	3200	250	< 0.018 U	10	370	0.50 J	< 0.069 U	41 J		< 0.19 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	3.7	2200	240	< 0.020 U	8.3	280 J	0.40 J	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	6.4	3100	450	0.022 J	11	460 J	0.74 J	< 0.10 U	< 50 U		< 0.28 UT
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	8.0	3900	330	< 0.021 U	12	500	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	10	1800	530	< 0.020 U	13	590	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	9.4	2200	300	< 0.022 U	12	490	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	6.5	8300	400	< 0.019 U	13	540	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	16	3500	360	< 0.019 U	13	520	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	10	1900	460	< 0.023 U	13	540	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	5.0	3300	280	< 0.014 U	11	500	0.42 J	< 0.079 U	42 J		< 0.22 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	6.6	4500	290	< 0.015 U	13	410	0.47 J	< 0.073 U	< 36 U		< 0.20 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	4.9	4200 T	350 T	< 0.019 U	11	330 T	1.1 T	< 0.068 U	55 JT		< 0.19 UT
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	4.5	17000	280	< 0.020 U	9.6	390	0.32 J	< 0.071 U	61 J		< 0.19 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	4.5	3000	260	< 0.014 U	9.6	430	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	5.9	4400	270	< 0.018 U	9.1	320 J	< 0.31 U	< 0.070 U	48 J		< 0.19 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	14	2900	470	< 0.023 U	19	630	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	14	4300	320	0.11	14	470	0.50 J	< 0.069 U	53 J		< 0.19 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	5.8	9400	260	< 0.020 U	12	560	0.44 J	< 0.088 U	50 J		< 0.24 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	6.0	4400	390	< 0.021 U	15	600	0.46 J	< 0.069 U	40 J		< 0.19 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	36	3900	360	0.068	20	630	0.45 J	< 0.091 U	46 J		< 0.25 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	33	1400	230	0.11	15	410 J	< 0.50 U	< 0.11 U	120 J		< 0.31 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	51	1200	160	0.054	15	290 J	2.3	< 0.11 U	180 J		< 0.30 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	5.5	1500	190	0.037	9.3	360 J	0.36 J	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	12	2100	340	0.017 J	14	680	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	12	1800	490	0.027 J	15	710	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	6.9	1500	310	0.024 J	11	550	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	8.4	1500	310	0.022 J	11	490	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	8.3	1400	340	0.027 J	11	500	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	10	2900	330	0.029 J	13	460 J	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	8.6	3100 T	360	0.11	16	470 T	0.40 J	< 0.086 U	45 J		< 0.23 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	49	2200	250	0.22	18	700	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	21	2300	520	0.27	17	780	< 0.52 U	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	7.9	2400	270	0.025 J	16	600	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	8.9	2400	290	0.026 J	15	730	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	14	1800	360	0.044	12	530	0.87 J	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	46	3700	600	0.10	17	660	< 0.47 U	< 0.11 U	53 J		< 0.29 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	13	2000	590	0.024 J	15	700	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	24	2400	370	0.14	19	740	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	8.0	1900	200	< 0.023 U	14	590	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	5.8	1400	380	< 0.016 U	10	400 J	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	7.5	1800	750 T	< 0.022 U	13	650 J	< 0.83 UT	< 0.19 UT	< 92 UT		< 0.26 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	11	2200	260	0.034 J	12	520	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	12 T	2000 T	290	0.029 JT	15	670 T	0.54 J	< 0.096 UT	< 47 U		< 0.26 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	11	2300	430	0.047	71	860	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	13	1900	1100	0.027 J	260	790 J	< 0.92 U	< 0.21 U	< 100 U		< 0.28 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	47	1900	380	0.12	47	640	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	8.5	1700	320	0.031	140	700	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	8.9	2200	380	0.017 J	18	710	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	12	2100	480	< 0.019 U	16	630	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	15	2900	280	0.042	19	950	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	12	2700	240	0.044	19	810	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	11	2000	390	0.028	18	580	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	8.3	2100	270	0.029	14	550	0.91 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	6.8	1700	420	0.022 J	14	380 J	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	9.2	1800	530	< 0.022 U	15	510	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	11 T	1900	590 T	< 0.015 U	14	610	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	9.3	2600	250	0.04	17	770	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	16	1900	590	0.052	14	770	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	6.5	26000	350	0.027 J	10	510 J	< 0.48 U	< 0.11 U	100 J		< 0.3 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	3.0	770	130	0.072	6.1	260 J	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	24	760	350	0.21	15	210 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	6.1	2400	400	< 0.022 U	15	460	< 0.39 U	< 0.089 U	< 44 U		< 0.24 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	11	2400	660	< 0.021 U	21	860	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	14	3800	520	0.048	16	770	< 0.44 U	< 0.10 U	79 J		< 0.27 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated		10	52
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated		12	58
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated		6.5	31
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated		6.5	32
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated		12 T	64 T
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated		8.3	49
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated		6.7	29
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated		6.3	40
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated		8.2	77
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated		7.4	57
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated		6.2	30
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated		5.0	42
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated		7.2	35
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated		9.1	48
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated		9.6	38
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated		8.3	54
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated		8.0	41
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated		11	55
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated		11	50
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated		7.0	43
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated		7.8	47
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated		5.6 T	43 T
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated		5.9	27
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated		6.2	37
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated		6.4	36
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated		11	74
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated		8.0	45
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated		7.5	42
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated		9.0	40
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated		11	79
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated		11	49
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated		32	59
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated		8.7	32
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated		11	47
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated		14	49
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated		9.6	37
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated		8.8	38
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated		10	42
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated		9.9	44
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated		8.2	110 T
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated		12	400
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated		14	68
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated		15	45
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated		14	42
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated		12	44
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated		11	480
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated		12	89
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated		13	190
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated		12	45
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated		6.3	41
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated		8.6 J	63 T
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated		10	41
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated		15 T	48 T
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated		20	59
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated		16	79
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated		13	60
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated		11	45
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated		14	52
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated		11	48
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated		18	53
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated		17	50
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated		15	50
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated		13	43
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated		7.3	48
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated		9.3	50
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated		11	43
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated		14	53
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated		10	52
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated		6.7	100
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated		3.9 J	17
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated		4.9 J	38
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated		8.6	46
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated		14	53
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated		11	54

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	6700	< 0.30 U	6.3	45	0.29 J	0.097 J	2900	8.5		5.9	21	16000
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	5400	< 0.28 U	3.7	43	0.20 J	0.13 J	33000	6.8		4.6	20	12000
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	7300	0.35 J	5.9	98	0.37 J	0.20 J	20000	9.5		5.1 J	38	14000
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	8600	0.38 J	12	84	0.39 J	0.22 J	4600	13		6.4	63	17000
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	8100	< 0.27 U	6.5	64	0.35 J	0.25 J	19000	23		6.8	26	16000
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	7900	< 0.30 U	6.4 B	110	0.35 J	0.17 J	7200	11		7.0	29	13000
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	8500	< 0.28 U	5.8 B	35	0.39	0.074 J	660	9.1		6.6	16	13000
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	7000	< 0.32 U	6.1	46	0.31 J	0.096 J	1000	8.8		6.5	22	17000 B
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	6900	0.42 J	7.4	120	0.35 J	0.16 J	11000	10		5.7	30	17000 B
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	5500	0.88 J	5.1	42	0.30 J	< 0.078 U	7200	8.5		4.6 J	37	15000
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	2900	0.49 J	1.8	16 J	0.20 J	< 0.076 U	780	9.1		4.1 J	31	14000
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	5900	0.48 J	3.8	29	0.31 J	< 0.079 U	3800	9.9		5.3 J	18	16000
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	12000	0.43 J	8.3	77	0.47	2.2	2200	15		7.2	35	22000
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	7000	0.39 JT	6.0	74 T	0.32 J	0.14 J	11000 T	8.4		5.9	21	16000
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	7100	0.77 J	9.1	76	0.40 J	0.16 J	13000	10		5.8	33	19000
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	6700 B	< 0.29 U	7.1	75	0.37 J	0.12 J	24000	8.9		5.2	22	15000
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	7300	0.51 J	7.2	66	0.38	0.11 J	11000	8.7		5.2	22	16000
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	6200	7.5	6.6	57	0.36 J	0.16 J	6100	9.7		5.5	90	14000 B
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	6500	0.44 J	7.3	63	0.34 J	0.14 J	8700	34		5.2 J	31	16000 B
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	6700	0.36 J	6.0	60	0.34 J	0.16 J	5800	9.7		5.5	39	15000 B
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	5800	0.69 J	11	57	0.43	0.27 J	9100	16		7.1	33	16000 B
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	9100	1.2	8.7	72	0.39	0.076 J	4300	12		8.5	23	21000
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	10000	0.47 J	13	170	0.51	0.095 J	2300	12		6.2	28	16000
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	5400	< 0.25 U	4.9	45	0.24 J	0.094 J	720	6.9		4.7	16	13000
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	8100	0.28 JT	8.7 T	32	0.38 T	< 0.063 UT	3200 T	9.4 T		7.1 T	15	18000
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	8200	< 0.23 U	6.2	37	0.37	0.063 J	750	9.5		6.7	17	16000
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	4000	< 0.24 U	4.2	18	0.18 J	< 0.058 U	1100	5.3		3.4 J	9.9	9500
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	6100	< 0.30 UT	6.1	37	0.27 JT	0.074 J	7100 T	8.0		5.6	19	14000
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	5300	< 0.28 U	4.6	24	0.23 J	0.085 J	660	6.4		4.5 J	15	12000
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	7200	< 0.25 U	6.4	69	0.33	< 0.060 U	380 J	8.7		6.7	18	15000
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	6300	< 0.31 U	6.7	34	0.28 J	0.12 J	1500	8.4		5.7	19	15000
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	4300	0.39 J	3.9	26	0.17 J	0.14 J	66000	5.6		4.7	13	11000
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	5500	< 0.26 U	5.3	66	0.22 J	0.35 J	690	6.5		4.5	21	11000
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	8800	< 0.27 U	4.2	51	0.31 J	< 0.066 U	660	9.5		6.3	7.5	14000
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	6600	< 0.32 UT	6.0 T	48 T	0.30 JT	0.11 JT	3600 T	8.2 T		6.1	23 T	15000
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	3900	0.38 J	4.3	24	0.20 J	< 0.074 U	1700	5.8		4.3 J	12	10000
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	7200	0.35 J	6.5	32	0.35	0.060 J	1600	9.0		5.9	22	18000 B
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	5800	0.23 J	5.5	26	0.30	< 0.051 U	620	7.2		5.8	13	14000 B
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	7200	0.36 J	6.5	69	0.34 J	0.082 J	790	8.5		6.3	22	14000
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	7300	< 0.29 U	6.7	63	0.32 J	< 0.069 U	660	8.8		6.3	17	15000 B
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	5500	0.46 J	5.5	28	0.27 J	< 0.084 U	670	7.4		6.1	13	13000 B
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	6500	< 0.31 U	5.5	35	0.29 J	< 0.076 U	630	7.9		5.8	18	14000 B
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	8600	< 0.32 U	8.0	36	0.39 J	< 0.077 U	1200	10		7.1	18	18000 B
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	7300	1.4	5.4	63	0.31 J	0.10 J	18000	9.8		5.3 J	25	13000 B
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	7200	0.31 J	6.6	41	0.38 J	< 0.075 U	800	9.5		6.4	16	17000 B
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	6400	0.67 J	9.3	110	0.37 J	17	4100	53		5.6	77	15000
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	3400	< 0.36 U	3.0	19 J	0.14 J	< 0.088 U	1100	4.1		2.4 J	7.9	6700
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	5900	0.41 J	5.1	43	0.29 J	< 0.059 U	560	6.9		5.0	13	12000
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	2900	0.40 J	2.1	20 J	0.12 J	< 0.075 U	1600	3.7		2.4 J	6.0	5800
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	6300	< 0.27 U	4.9	24	0.28 J	< 0.065 U	290 J	7.6		5.3	12	13000
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	4700	0.36 J	3.7	26	0.21 J	< 0.067 U	470	5.6		4.0 J	11	10000
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	7000	0.43 J	5.5	50	0.30 J	< 0.081 U	710	8.6		6.2	18	15000
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	6300	< 0.25 U	5.5	46	0.27 J	< 0.061 U	940	7.4		5.9	14	14000
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	6700	0.45 J	6.5	93	0.32 J	0.17 J	14000	10		5.3	45	16000
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	6500	0.42 J	5.6	48	0.30 J	0.12 J	3300	8.7		5.3	36	15000
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	5800	0.24 J	5.7	31	0.29 J	< 0.057 U	520	7.1		5.8	14	13000
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	6700	< 0.31 U	7.0	39	0.33 J	< 0.075 U	840	8.2		6.2	18	14000
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	6700	0.36 J	5.3	48	0.28 J	0.069 J	3000	8.4		5.3	17	13000
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	5400	0.36 J	5.8	45	0.28 J	< 0.069 U	660	6.8		5.6	15	13000
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	5800	< 0.31 U	6.0	41	0.30 J	< 0.074 U	1100	7.2		5.2	16	14000 B
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	7900	0.39 JT	6.0 T	43	0.37 J	0.082 JT	780 T	9.6 T		6.8	16 T	17000
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	7700	< 0.27 U	5.8	58	0.35	0.097 J	1500	9.8		5.7	20	15000
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	10000	< 0.30 U	5.5	64	0.38 J	0.078 J	910	11		6.4	12	15000
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	8300	0.51 J	7.5	79	0.42	0.12 J	2700	11		6.6	39	18000
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	9400	< 0.34 U	7.5	40	0.47	< 0.081 U	940	11		8.9	18	20000
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	9000	0.26 J	7.4	43	0.45	0.073 J	900	10		8.1	19	19000
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	7000	0.29 J	5.5	57	0.39	0.095 J	910	9.1		6.4	17	17000
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	9000	0.38 J	6.9	73	0.41	0.12 J	3400	13		7.2	22	17000
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	6600	0.31 J	5.3	42	0.30	0.073 J	730	7.7		5.5	18	13000
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	7200	0.32 J	6.8	57	0.35	0.10 J	1700	8.9		6.0	20	16000
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	9700	0.45 J	8.8	57	0.47	0.081 J	2000	11		8.3	17	18000
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	7100	< 0.28 U	5.7	31	0.33 J	0.076 J	630	7.9		5.2	12	14000
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	7300	0.33 J	6.9	79	0.34 J	0.085 J	640	8.8		6.4	16	15000
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	8700	< 0.30 U	7.2	58	0.42	0.088 J	1300	9.9		6.5	17	16000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	10	2600	470	< 0.021 U	14	650	< 0.45 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	5.6	8700	470	< 0.021 U	11	670	< 0.42 U	< 0.096 U	54 J		< 0.26 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	66	1900	360	0.14	15	630	0.86 J	< 0.12 U	66 J		< 0.33 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	43	2400	370 T	0.15	18	690	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	37	4300	470 T	0.062	16	640	0.82 J	< 0.094 U	50 J		< 0.26 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	41	2800	370	0.68	18	780	< 0.45 U	< 0.10 U	65 J		< 0.28 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	18	2100	440	< 0.022 U	15	600	< 0.43 U	< 0.096 U	48 J		< 0.26 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	7.9	2000	680 B	< 0.020 U	16	620	0.51 J	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	41	2400	320 B	0.93	43	800	0.64 J	< 0.097 U	86 J		< 0.26 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	35	1800	410	0.080	10	650	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	11	350 J	580	0.29	7.1	400 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	11	1600	400	9.4	12	1000	< 0.49 U	< 0.11 U	64 J		< 0.30 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	31	2500	390	0.14	18	980	< 0.51 U	< 0.11 U	60 J		< 0.31 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	32	3200	460 B	1.1	16	680 T	< 0.47 U	< 0.11 U	60 J		< 0.29 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	190	1800	410 B	0.91	15	740	0.71 J	< 0.11 U	140 J		< 0.30 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	53	3900	330	0.16	13	850	0.47 J	< 0.098 U	110 J		< 0.27 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	56	2700	390	0.087	13	500	< 0.43 U	< 0.097 U	110 J		< 0.27 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	72	2200	330 T	0.29	150	510	0.63 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	45	3000	330 T	0.44	15	520 J	1.1	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	51	2300	270 T	0.47	160	530	0.42 J	< 0.091 U	46 J		< 0.25 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	32	3300	300 T	0.13	170	550	0.58 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	18	2900	450	0.073	19	970	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	52	1600	1000	0.13	12	640	0.72 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	6.0	1600	450	0.031 J	12	470	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	12	2100 T	410	0.17 T	16 T	550	< 0.40 UT	< 0.090 UT	< 44 UT		< 0.25 UT
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	8.1	2100	350	0.028 J	16	630	0.36 J	< 0.079 U	< 39 U		< 0.22 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	5.1	1100	180	0.073	7.4	350 J	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	11	2900	390	0.042	14	730	< 0.46 U	< 0.10 UT	< 51 U		< 0.28 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	5.1	1600	320	0.023 J	12	480	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	8.4	1800	470	0.37	14	630	< 0.37 U	< 0.084 U	< 42 U		< 0.23 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	7.8	2000	390	0.043	14	760	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	4.1	2700	350	< 0.017 U	12	480	0.86 J	< 0.090 U	51 J		< 0.25 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	220	1500	260	1.2	11	540	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	6.7	2000	300	0.059	12	560	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	36 T	2900 T	670 T	0.25 T	15	640 T	< 0.49 UT	< 0.11 UT	< 54 UT		< 0.30 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	6.4	1400	280	0.074	9.7	620	< 0.46 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	12	2100	360	0.038	17	500	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	7.4	1600	300	< 0.020 U	14	400	< 0.32 U	< 0.073 U	< 36 U		< 0.20 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	28	1700	690	0.12	41	680	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	7.4	1900	530	< 0.019 U	15	620	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	6.5	1500	290	< 0.024 U	12	570	< 0.53 U	< 0.12 U	< 59 U		< 0.32 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	6.2	1800	300	0.025 J	13	520	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	10	2100	290	0.037	17	680	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	78	3400	290	1.7	18	630	< 0.51 U	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	7.8	1900	320	0.022 J	16	660	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	210	2600	280	1.1	23	610	0.68 J	1.3	55 J		< 0.27 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	7.6	880	120	0.40	63	260 J	< 0.55 U	< 0.12 U	< 61 U		< 0.34 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	8.7	1400	300	0.080	14	460	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	11	680	100	0.36	11	230 J	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	9.7	1700	280	0.018 J	13	470	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	5.0	1300	230	< 0.017 U	10	410 J	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	8.3	2000	380	0.019 J	15	540 J	< 0.51 U	< 0.11 U	< 57 U		< 0.31 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	8.1	1900	360	0.045	26	430	< 0.38 U	< 0.086 U	< 43 U		< 0.24 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	64	2300	270	1.4	19	560	< 0.44 U	< 0.10 U	68 J		< 0.27 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	41	1900	330	0.35	16	460	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	9.5	1500	460	0.027 J	13	430	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	12	1700	410	0.035	26	540	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	20	1900	360	0.14	20	450	< 0.37 U	< 0.083 U	41 J		< 0.23 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	9.3	1500	470	0.025 J	13	500	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	11	1500	530	0.75	34	570	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	9.3	2100 T	600	0.023 J	16	590 T	< 0.46 UT	< 0.10 UT	56 JT		< 0.28 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	19	2000	390	0.12	30	740	< 0.41 U	< 0.092 U	49 J		< 0.25 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	11	2100	310	0.034	16	800	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	61	2000	390	0.21	47	780	< 0.40 U	< 0.090 U	57 J		< 0.24 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	9.7	2400	340	0.021 J	17	890	< 0.51 U	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	9.3	2200	300	0.030	16	820	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	7.5	1900	530	0.025 J	17	830	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	37	2300	460	0.30	21	720	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	13	1700	320	0.063	17	680	< 0.35 U	< 0.079 U	< 39 U		< 0.21 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	20	2000	470	0.076	32	770	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	20	2500	520	0.042	20	860	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	7.9	1800	340	0.019 J	14	630	0.43 J	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	12	1900	420	0.025 J	16	710	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	26	2000	430	0.059	15	760	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated		11	53
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated		8.3	40
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated		13	75
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated		14	88
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated		16	90
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated		13	86
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated		12	50
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated		11	52
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated		14	77
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated		14	49
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated		16	15
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated		14	32
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated		19	82
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated		12	96 T
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated		15	73
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated		12	57
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated		14	61
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated		12	69
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated		14	73
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated		11	75
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated		13	69
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated		14	52
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated		17	65
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated		8.6	45
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated		13 T	52 T
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated		11	42
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated		8.0	27
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated		11	50 T
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated		8.5	39
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated		12	55
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated		12	55
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated		7.7	33
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated		9.1	41
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated		13	37
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated		11 T	50 T
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated		12	31
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated		14	43
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated		11	36
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated		12	48
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated		11	49
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated		11	37
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated		10	42
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated		14	47
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated		12	62
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated		15	45
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated		14	370
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated		5.7 J	21
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated		8.9	32
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated		5.6	17
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated		10	34
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated		8.4	29
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated		11	45
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated		11	37
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated		12	85
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated		12	56
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated		11	37
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated		12	42
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated		11	42
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated		9.7	47
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated		9.9	42
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated		13 T	40 T
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated		13	53
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated		15	42
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated		15	73
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated		16	46
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated		16	50
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated		11	41
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated		15	79
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated		10	57
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated		13	53
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated		16	47
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated		12	40
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated		11	48
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated		14	52

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	7300	0.33 J	7.3	86	0.40	0.089 J	1200	9.2		6.4	22	17000
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	6800	< 0.28 U	7.9	51	0.33 J	< 0.067 U	900	8.4		5.9	21	16000
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	7100	1.1	5.2	58	0.29 J	0.092 J	1800	8.2		4.4 J	16	12000
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	9100	< 0.31 U	8.9	74	0.44	< 0.075 U	3000	11		8.8	16	22000
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	10000	< 0.31 U	6.6	37	0.41	< 0.074 U	1100	11		7.3	17	17000
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	8700	< 0.32 U	6.1	73	0.35 J	0.12 J	3000	13		6.1	33	16000
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	8700	< 0.30 U	8.6	70	0.38 J	< 0.072 U	4200	11		8.5	16	20000
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	5200	< 0.19 U	3.9	36	0.19 J	0.10 J	42000	6.1		4.5	17	11000
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	5800	< 0.31 U	4.5	46	0.22 J	0.093 J	31000	7.2		5.1	21	13000
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	4800	< 0.30 U	4.1	27	0.18 J	0.086 J	48000	6.7		4.5 J	17	11000
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	4200	< 0.20 U	3.9	39	0.16 J	0.079 J	30000	5.4		4.1	12	9800
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	3700	< 0.25 U	2.5	19	0.14 J	0.091 J	35000	4.5		3.4 J	11	8800
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	4300	< 0.28 U	3.8	29	0.15 J	0.091 J	35000	5.2		3.7 J	11	10000
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	3400	< 0.25 U	3.6	17	0.12 J	< 0.062 U	19000	4.1		2.9 J	9.2	8200
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	4700	< 0.23 U	3.3	23	0.20 J	0.12 J	22000	5.9		4.0	12	10000
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	3800	< 0.29 U	2.9	21	0.19 J	0.077 J	23000	4.6		3.3 J	16	9400
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	3900	< 0.26 U	4.0	26	0.17 J	0.086 J	17000	4.9		4.0 J	13	10000
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	6500	0.29 J	5.7	50	0.27 J	0.095 J	1500	7.9		5.2	29	14000
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	6900	0.56 J	5.9	48	0.29 J	0.10 J	3100	8.3		5.8	18	14000
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	5700	< 0.25 U	4.6	41	0.26 J	0.074 J	1200	7.1		4.1	26	12000
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	7100	< 0.27 U	6.2	53	0.37	0.10 J	2600	9.4		5.7	24	16000
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	5000	< 0.24 U	3.8	35	0.21 J	0.074 J	780	6.2		4.5	16	12000
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	6600	0.34 J	5.5	45	0.27 J	0.082 J	1400	7.3		4.5	15	12000
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	5900	< 0.33 UT	6.0	45 T	0.25 J	0.11 J	5800 T	7.9		5.9	18	14000 T
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	4900	< 0.25 U	4.0	28	0.21 J	0.098 J	25000	5.8		4.2	13	11000
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	5000	0.31 J	4.4	26	0.22 J	0.11 J	18000	6.6		4.8	18	12000
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	5100	< 0.29 U	5.6	33	0.22 J	0.11 J	21000	6.8		4.4 J	18	13000
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	4000	< 0.26 U	5.5	25	0.18 J	0.13 J	28000	5.7		4.1 J	13	11000
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	4300	< 0.27 U	5.5	33	0.18 J	0.15 J	26000	5.8		4.1 J	22	11000
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	5200	0.30 J	4.4	42	0.23 J	0.26 J	26000	7.2		4.9	24	12000
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	5400	< 0.23 U	5.3	41	0.24 J	0.14 J	21000	7.4		4.5	26	12000
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	4600	< 0.27 U	3.9	27	0.18 J	0.10 J	26000	5.7		4.1 J	18	11000
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	4500	< 0.28 U	5.5	27	0.18 J	0.11 J	48000	5.7		4.5 J	16	11000
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	4300	< 0.26 U	3.7	24	0.16 J	0.098 J	16000	5.6		4.0 J	16	11000
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	5000	< 0.31 U	10	39	0.21 J	0.12 J	25000	6.2		6.3	22	14000
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	6400	0.79 J	6.1	72	0.28 J	0.096 J	2000	7.4		4.6 J	18	14000
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	7100	0.58 J	7.9	110	0.32 J	0.17 J	7300	9.6		7.0	29	24000
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	6500	< 0.31 U	5.8	48	0.30 J	0.10 J	970	8.2		6.4	20	15000
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	6600	0.29 JT	7.8 T	58 T	0.28 JT	0.16 JT	2300 T	10 T		6.4	22 T	22000
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	4500	< 0.30 U	3.8	39	0.20 J	0.11 J	22000	5.7		3.7 J	12	10000
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	7400	0.30 J	6.0	46	0.31 J	0.15 J	15000	9.0		6.0	20	16000
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	5900	< 0.28 U	5.9	46	0.26 J	0.14 J	19000	7.2		4.8	21	13000
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	5600	< 0.27 U	4.9	35	0.26 J	0.10 J	27000	7.3		5.0	16	13000
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	4700	0.43 JT	3.9 T	80 T	0.23 JT	0.72 T	1300 T	8.6 T		3.0 JT	68 T	8000
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	6900	0.44 J	7.9	64	0.30 J	0.46 J	920	12		5.5	60	15000
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	4400	< 0.25 U	4.0	24	0.19 J	0.11 J	8500	5.6		4.2	15	11000
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	6100	0.34 JT	4.7 T	43 T	0.33 JT	0.11 JT	3100 T	6.5 T		5.1 T	18 T	14000
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	4600	< 0.31 U	4.1	36	0.22 J	0.083 J	5500	5.9		3.6 J	13	11000
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	4200	< 0.30 U	4.4	34	0.20 J	0.10 J	14000	5.6		4.0 J	14	11000
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	5600	< 0.29 U	4.7	25	0.26 J	< 0.069 U	1100	6.5		4.3 J	14	12000
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	5000	0.31 J	3.9	24	0.23 J	0.067 J	3400	6.3		3.7 J	13	11000
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	4300	< 0.26 U	3.8	24	0.19 J	0.12 J	8400	5.6		4.3	17	11000
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	4400	< 0.28 U	4.8	29	0.20 J	0.084 J	7300	5.7		3.9 J	14	11000
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	2300	< 0.34 U	4.8	12 J	0.13 J	0.13 J	63000	3.2		2.2 J	9.6	7100
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	5400	< 0.30 U	5.2	29	0.25 J	0.077 J	1900	7.1		4.8 J	18	12000
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	3500	< 0.19 U	2.8	15	0.13 J	0.081 J	18000	4.4		3.1	10	7800
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	4100	0.25 J	5.1	24	0.18 J	0.096 J	5800	5.8		3.8 J	13	11000
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	4700	0.37 J	4.3	33	0.23 J	0.079 J	1900	5.9		3.6 J	14	11000
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	4400	0.50 J	5.3	38	0.22 J	0.11 J	1000	6.4		3.5 J	17	11000
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	4100	0.39 J	3.2	25	0.16 J	< 0.059 U	780	5.2		2.7 J	9.7	7900
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	5100	0.40 J	4.2	40	0.24 J	0.15 J	1100	6.1		3.8 J	15	12000
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	5700	0.41 J	6.0	34	0.24 J	< 0.078 U	660	7.1		4.8 J	17	13000
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	6300	< 0.33 UT	4.6 T	44 T	0.26 JT	0.080 JT	970 T	7.4 T		4.4 JT	13 T	11000
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	4600	0.39 J	4.3	29	0.21 J	0.077 J	4100	5.5		3.5 J	11	9500
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	4400	< 0.26 U	3.9	24	0.20 J	0.080 J	1100	5.7		3.9 J	14	10000
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	6500	< 0.30 U	5.0	46	0.30 J	0.13 J	7000	8.4		5.6	15	14000
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	6300	< 0.27 U	5.4	50	0.27 J	0.13 J	2100	8.9		5.2	18	14000
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	6000	< 0.30 U	6.1	38	0.26 J	0.15 J	14000	7.5		7.1	18	16000
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	7900	< 0.30 U	6.1	63	0.37 J	0.12 J	7800	10		7.3	18	17000
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	4600	< 0.29 U	4.0	26	0.19 J	0.13 J	21000	6.6		4.4 J	13	12000
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	5800	< 0.31 U	5.7	45	0.27 J	0.19 J	24000	6.9		4.7 J	20	14000
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	4400	< 0.27 U	4.8	32	0.19 J	0.15 J	2800	5.4		3.9 J	14	11000
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	6800	< 0.30 U	6.6	60	0.33 J	0.85	2400	9.0		6.9	120	16000
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	5200	0.31 J	5.2	33	0.25 J	0.13 J	1600	6.9		4.9 J	14	13000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	8.6	2000	660	0.028 J	18	890	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	31	1800	380	< 0.019 U	16	810	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	120	1400	370	0.091	11	510	0.70 J	< 0.099 U	49 J		< 0.27 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	11	2800	470	0.027 J	20	950	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	9.5	2300	260	0.031 J	16	850	< 0.47 U	< 0.10 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	63	1800	440	0.20	20	680	0.60 J	< 0.11 U	53 J		< 0.30 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	12	2700	420	< 0.020 U	19	1000	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	5.9	3800	230	0.13	12	480	0.34 J	< 0.066 U	43 J		< 0.18 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	6.2	3900	290	< 0.016 U	13	550	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	4.8	4300	240	< 0.019 U	12	560	< 0.45 U	< 0.10 U	53 J		< 0.28 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	4.5	5700	270	< 0.018 U	9.7	410	< 0.31 U	< 0.070 U	38 J		< 0.19 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	3.3	2700	240	< 0.021 U	8.7	340 J	< 0.38 U	< 0.086 U	< 42 U		< 0.23 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	4.5	3200	290	< 0.013 U	10	460	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	4.4	2200	180	< 0.019 U	7.2	300 J	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	4.4	3800	490	< 0.018 U	10	500	< 0.35 U	< 0.080 U	42 J		< 0.22 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	7.5	2700	200	0.51	8.7	320 J	< 0.45 U	< 0.10 U	52 J		< 0.28 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	5.7	2800	320	< 0.023 U	9.5	420 J	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	8.6	2100	350	0.080	13	610	< 0.43 U	< 0.098 U	49 J		< 0.27 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	13	2700	440	0.038	13	580	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	14	1400	280	0.071	12	490	< 0.38 U	< 0.085 U	75 J		< 0.23 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	27	2300	370	0.10	17	580	< 0.41 U	< 0.093 U	110 J		< 0.25 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	5.5	1600	350	0.028 J	12	450	< 0.37 U	< 0.083 U	53 J		< 0.23 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	12	1800	360	0.053	11	470	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	7.6	4600 T	350	0.037	14	610	< 0.50 UT	< 0.11 U	58 J		< 0.31 U
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	5.2	2800	270	0.024 J	11	560	< 0.38 U	< 0.085 U	48 J		< 0.23 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	4.8	8400	460	0.030 J	12	550	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	11	2700	260	0.041	12	530	< 0.44 U	< 0.099 U	76 J		< 0.27 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	7.2	3000	260	0.036	9.8	490	0.42 J	< 0.089 U	74 J		< 0.24 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	15	5200	320	0.042	11	450	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	26	3200	430	0.099	14	620	0.45 J	< 0.093 U	60 J		< 0.25 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	25	2900	330	0.17	13	520	< 0.35 U	< 0.078 U	41 J		< 0.21 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	8.5	5100	280	0.029 J	11	540 B	0.63 BJ	< 0.093 U	58 BJ		< 0.25 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	5.5	4200	370	0.023 J	11	420 BJ	0.71 BJ	< 0.097 U	75 BJ		< 0.26 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	8.9	3800	310	< 0.022 U	10	390 BJ	< 0.39 U	< 0.088 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	7.0	5100	610	0.025 J	13	540 B	< 0.47 U	< 0.11 U	180 BJ		< 0.29 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	20	2100	450	0.065	11	610 B	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	37	2700	410	0.095	17	600 B	< 0.43 U	< 0.098 U	60 BJ		< 0.27 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	12	1800	580	0.057	18	750 B	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	30	1900	430 T	0.10	14	600 BT	< 0.43 UT	< 0.098 UT	< 48 U		< 0.27 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	7.6	4900	320	0.029 J	9.8	480 J	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	26	3100	380	0.057	15	640	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	22	4000	360	0.047	13	570	< 0.43 U	< 0.096 U	69 J		< 0.26 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	7.3	4500	270	< 0.020 U	13	1300	< 0.42 U	< 0.094 U	130 J		< 0.26 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	150 T	970 T	130 T	1.2	10 T	370 JT	< 0.51 UT	0.25 JT	< 56 UT		< 0.31 UT
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	58	1500	280	0.52	17	480	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	6.0	3300	260	< 0.017 U	10	450	< 0.37 U	< 0.084 U	45 J		< 0.23 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	8.9 T	2400 T	330	0.047	11 T	600 T	< 0.44 UT	< 0.10 UT	< 49 UT		< 0.27 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	8.8	2700	320	0.026 J	9.7	500 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	6.8	4300	360	< 0.021 U	9.9	440 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	8.5	1500	220	0.034	10	540	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	6.3	2100	200	0.021 J	9.6	500	< 0.37 U	< 0.084 U	< 42 U		< 0.23 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	5.7	3900	260	0.014 J	10	450	< 0.39 U	< 0.088 U	< 44 U		< 0.24 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	6.7	2500	290	0.045	9.7	440 J	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	10	39000	450	< 0.019 U	5.7	390 J	< 0.52 U	< 0.12 U	100 J		< 0.32 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	7.2	1900	320	0.018 J	12	540	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	3.8	1900	230	< 0.013 U	8.0	310	0.30 J	< 0.064 U	32 J		< 0.17 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	6.3	2800	240	0.022 J	9.3	420	< 0.36 U	< 0.082 U	< 40 U		< 0.22 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	11	1700	240	0.041	9.9	350 J	< 0.34 U	< 0.077 U	< 38 U		< 0.21 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	20	1000	270	0.069	10	370 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	7.5	1000	170	0.080	7.1	320 J	< 0.37 U	< 0.084 U	< 41 U		< 0.23 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	13	1300	300	0.056	10	440 J	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	6.0	1700	280	0.027 J	12	520 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	10 T	1600 T	360	0.091 T	11 T	450 JT	< 0.50 UT	< 0.11 UT	< 56 UT		< 0.31 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	9.0	1800	260	0.057	8.6	390 J	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	5.3	1500	250	< 0.014 U	9.9	400 J	< 0.40 U	< 0.091 U	45 J		< 0.25 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	6.4	2600	340	< 0.016 U	14	810	< 0.45 UT	< 0.10 U	79 J		< 0.28 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	18	1900	380	0.058	13	660	< 0.41 UT	< 0.093 U	61 J		< 0.25 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	11	6300	490	0.025 J	13	560	< 0.45 UT	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	7.9	3100	420	< 0.019 U	17	980	< 0.45 UT	< 0.10 U	95 J		< 0.28 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	6.0	5000	350	< 0.022 U	11	520	< 0.44 U	< 0.099 U	61 J		< 0.27 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	18	2200	380	0.058	12	560	0.71 BJ	< 0.10 U	68 J		< 0.29 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	6.6	2000	310	< 0.022 U	10	480	0.46 BJ	< 0.091 U	45 J		< 0.25 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	12	2600	440	0.059	18	640	< 0.46 U	< 0.10 U	< 51 U		0.30 J
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	6.2	1900	300	< 0.022 U	12	640	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated		16	47
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated		12	46
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated		11	55
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated		13	50
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated		14	44
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated		15	74
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated		12	44
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated		7.2	52
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated		9.2	52
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated		8.2	34
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated		6.5	35
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated		5.9	29
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated		5.8	33
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated		5.5	27
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated		7.1	38
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated		5.3	41
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated		6.0	38
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated		10	50
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated		11	53
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated		9.3	41
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated		13	56
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated		7.6	37
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated		10	45
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated		9.9	47 T
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated		7.5	35
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated		10	41
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated		9.9	41
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated		9.1	33
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated		6.8	46
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated		8.4	74
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated		9.0	62
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated		6.6	37
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated		7.3	46
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated		6.2	35
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated		7.8	56
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated		10	44
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated		13	72
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated		11	54
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated		16 T	55
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated		7.5	36
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated		11	68
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated		9.5	56
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated		8.1	42
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated		8.5 T	150
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated		12	110
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated		7.6	48
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated		16 T	45 T
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated		8.4	34
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated		7.5	49
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated		8.9	34
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated		8.5	34
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated		8.0	45
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated		8.6	34
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated		4.7 J	19
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated		8.7	50
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated		5.3	28
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated		8.3	39
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated		8.0	32
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated		9.2	58
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated		7.2	29
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated		9.0	79
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated		9.4	42
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated		12 T	36 T
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated		8.1	33
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated		7.3	38
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated		9.5	54
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated		11	48
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated		11	63
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated		12	65
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated		8.2	44
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated		9.4	61
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated		6.7	68
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated		11	390
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated		8.4	51

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	4400	< 0.28 U	4.5	32	0.16 J	0.12 J	28000	5.6		4.2 J	13	11000
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	5500	< 0.29 U	4.2	30	0.22 J	0.13 J	27000	6.8		5.0	15	12000
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	5400	< 0.31 U	4.2	30	0.20 J	0.14 J	16000	6.8		4.8 J	15	13000
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	4700	< 0.27 U	4.1	26	0.17 J	0.12 J	9200	5.3		4.6	11	11000
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	6800	< 0.29 U	4.3	65	0.27 J	0.13 J	29000	8.3		6.1	21	15000
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	5200	< 0.28 U	4.1	39	0.21 J	0.13 J	32000	6.9		4.8	16	13000
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	5500	< 0.27 U	5.3	45	0.26 J	0.15 J	13000	7.2		5.4	17	13000
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	4300	< 0.27 UT	4.0	26 T	0.18 J	0.11 J	6600 T	5.4		4.2 J	14 T	11000
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	4400	< 0.27 U	4.6	21	0.20 J	< 0.066 U	4700	6.0		4.5	14	12000
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	5900	< 0.28 U	5.8	35	0.26 J	< 0.067 U	3200	7.5		5.7	19	14000
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	5700	< 0.29 U	5.8	37	0.25 J	< 0.070 U	11000	7.5		5.5	20	14000
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	5600	< 0.29 U	5.9	39	0.24 J	< 0.070 U	3000	7.3		5.3	17	14000
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	5600	< 0.29 U	4.6	27	0.22 J	< 0.070 U	1600	7.1		5.6	16	13000
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	5700	< 0.28 U	5.1	31	0.23 J	< 0.068 U	22000	7.1		5.3	17	14000
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	4300	< 0.29 U	3.8	28	0.18 J	< 0.071 U	21000	5.6		4.0 J	13	11000
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	5400	< 0.28 U	6.0	36	0.24 J	0.11 J	4200	7.1		5.0	18	13000
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	4700	< 0.29 U	5.3	30	0.19 J	< 0.071 U	25000	6.2		4.6 J	16	12000
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	4400	< 0.29 U	3.3	34	0.16 J	0.073 J	26000	5.5		4.3 J	11	9800
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	5300	< 0.28 U	4.0	34	0.20 J	< 0.067 U	19000	6.8		4.8	20	12000
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	3700	< 0.30 U	3.5	31	0.17 J	0.14 J	42000	4.6		3.6 J	11	9800
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	6200	< 0.26 U	5.0	44	0.26 J	< 0.062 U	16000	8.0		5.9	18	14000
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	4300	< 0.26 U	3.9	28	0.17 J	< 0.064 U	27000	5.6		4.3	14	11000
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	4100	< 0.27 U	4.1	21	0.20 J	< 0.064 U	1200	5.6		4.5	14	11000
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	4000	< 0.27 UT	3.5	23 T	0.19 J	0.11 J	24000 T	5.2		3.8 J	14	9200
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	6300	< 0.31 U	5.8	42	0.29 J	< 0.075 U	2000	8.2		5.3	18	16000
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	4900	< 0.29 U	3.5	25	0.19 J	< 0.070 U	21000	5.9		4.3 J	16	12000
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	4600	< 0.25 UT	4.0	30 T	0.19 J	< 0.061 U	21000	5.6		4.2	21 T	11000
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	5800	< 0.32 UT	5.9 T	29 T	0.26 JT	< 0.079 UT	3700	7.4 T		5.4	17 T	14000
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	4600	< 0.25 U	3.7	25	0.17 J	< 0.060 U	16000	5.8		4.5	14	11000
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	6200	< 0.31 U	5.1	50	0.25 J	< 0.076 U	2400	7.3		4.9 J	15	13000
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	4800	< 0.29 U	4.4	28	0.18 J	0.076 J	27000	6.4		4.8	19	11000
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	4200	< 0.30 U	4.4	35	0.19 J	< 0.074 U	1200	5.4		3.7 J	12	9800
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	4000	< 0.27 U	4.0	22	0.15 J	< 0.065 U	610	4.9		2.6 J	11	8300
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	4100	< 0.25 U	4.8	23	0.19 J	< 0.062 U	1000	5.6		4.3	12	11000
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	3100	< 0.21 U	2.8	22	0.12 J	< 0.050 U	2500	4.0		2.0 J	7.6	9200
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	3900	< 0.30 U	3.3	26	0.16 J	< 0.072 U	4400	5.4		2.7 J	13	8600
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	4900	< 0.26 U	4.5	530	0.19 J	0.17 J	13000	11		3.8 J	65	11000
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	6000	< 0.25 U	3.7	39	0.24 J	< 0.061 U	18000	7.4		5.1	16	13000
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	6400	0.30 JT	6.1	40 T	0.28 J	< 0.068 U	1400	8.6		6.2	19	17000
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	5500	< 0.28 U	4.9	35	0.25 J	< 0.067 U	6500	7.4		5.0	21	14000
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	6600	< 0.30 U	6.3	49	0.30 J	< 0.072 U	18000	8.3		5.6	20	16000
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	5800	< 0.27 U	5.1	40	0.26 J	< 0.067 U	12000	7.0		4.4 J	17	13000
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	6900	< 0.31 U	6.5	39	0.31 J	0.083 J	2200	8.8		6.6	19	16000
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	6000	< 0.26 U	5.5	40	0.26 J	< 0.063 U	15000	7.6		5.2	16	13000
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	4600	< 0.27 U	4.4	26	0.19 J	< 0.064 U	23000	5.8		4.5	13	11000
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	5000	< 0.26 U	4.2	31	0.20 J	< 0.063 U	24000	6.5		4.9	14	12000
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	5500	< 0.27 U	3.9	38	0.23 J	< 0.065 U	38000	6.7		5.1	16	12000
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	6300	< 0.26 U	6.2	72	0.27 J	< 0.064 U	5900	7.9		5.2	19	14000
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	4800	< 0.28 U	5.7	32	0.20 J	0.095 J	28000	6.3		4.9	16	13000
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	5900	< 0.29 UT	6.2	33 T	0.26 J	< 0.069 U	5200	8.0		5.4	17	15000
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	5700	< 0.24 U	5.4	35	0.25 J	< 0.058 U	8700	7.2		5.5	15	13000
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	5100	< 0.27 UT	4.2	31 T	0.20 J	< 0.066 U	11000 T	6.5		4.7	16 T	12000
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	6400	< 0.29 U	4.6	40	0.24 J	< 0.069 U	15000	8.2		5.4	18	14000
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	5100	< 0.25 U	4.8	37	0.23 J	< 0.061 U	20000	6.5		4.8	14	12000
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	9600	< 0.27 U	4.6	68	0.33 J	< 0.066 U	1900	10		4.8	11	15000
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	6000	< 0.28 UT	5.8 T	39 T	0.24 JT	0.081 JT	950	8.2 T		6.4	20 T	16000
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	8100	< 0.32 U	7.3	64	0.31 J	0.11 J	51000	9.9		5.2	21	15000
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	6100	< 0.28 U	5.6	34	0.27 J	< 0.068 U	610	7.5		5.4	15	14000
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	5000	< 0.27 U	4.8	27	0.23 J	< 0.065 U	600	6.2		4.5	13	12000
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	6100	< 0.59 U	11	41	0.33 J	0.17 J	8300	9.3		8.2	23	17000
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	6000	< 0.28 U	6.7	36	0.29 J	< 0.067 U	640	7.6		4.8	17	15000
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	7600	< 0.28 U	6.2	47	0.34 J	< 0.068 U	2000	8.7		5.4	18	15000 B
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	7400	< 0.29 U	6.6	61	0.38 J	< 0.071 U	2300	8.8		5.0	24	14000 B
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	7300	< 0.24 U	5.5	45	0.28 J	< 0.058 U	7600	8.3		5.2	19	14000
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	7400	< 0.23 U	6.8	44	0.31	< 0.057 U	7300	8.6		5.8	19	14000
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	8500	< 0.25 U	7.3	72	0.39	0.066 J	8000	15		6.8	20	16000
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	7000	< 0.26 U	6.7	36	0.29 J	< 0.064 U	1100	8.8		5.7	19	15000
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	7400	< 0.26 U	5.3	38	0.30 J	< 0.062 U	340 J	8.2		5.4	14	14000
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	7500	< 0.27 UT	6.0 T	54 T	0.34 JT	< 0.065 UT	5100 T	9.3 T		5.7	20 T	14000
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	4000	< 0.27 U	3.7	21	0.18 J	< 0.067 U	710	5.2		2.8 J	11	9400
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	4300 T	< 0.21 UT	1.7 T	22 T	0.13 JT	< 0.051 UT	470 T	4.5 T		2.1 JT	5.9 T	6100 T
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	5100	0.61 J	6.8	58	0.34 J	0.11 J	3400	25		4.0 J	82	13000
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	9700	0.35 J	1.4	67	0.37 J	< 0.076 U	960	11		5.7	9.0	16000
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	10000	0.48 JT	1.5	54	0.39 J	< 0.074 U	840	11		6.8	9.9	17000 T

DRAFT

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	7.2	4100	270	< 0.022 U	10	490	0.76 BJ	< 0.097 U	53 J		< 0.26 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	6.3	5400	340	< 0.020 U	12	540	0.49 BJ	< 0.099 U	53 J		< 0.27 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	6.8	4000	290	< 0.022 U	12	630	< 0.47 U	< 0.11 U	63 J		< 0.29 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	12	2500	450	< 0.019 U	11	440	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	5.9	3600	440	< 0.019 U	15	840	0.48 BJ	< 0.099 U	53 J		< 0.27 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	6.2	4500	360	< 0.019 U	12	550	0.54 BJ	< 0.096 U	55 J		< 0.26 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	15	3700	650	0.078	14	610	0.46 BJ	< 0.094 U	46 J		< 0.26 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	5.2	2500 T	290	< 0.021 U	10	440 T	< 0.41 UT	< 0.092 UT	< 45 U		< 0.25 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	5.4	1700	280	< 0.019 U	11	460	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	9.9	2700	370	0.21	14	550	< 0.42 U	< 0.094 U	< 47 U		< 0.26 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	15	6300	460	0.030	13	570	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	7.3	2900	400	0.022 J	13	640	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	8.6	2000	270	0.029	12	540	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	7.1	4500	340	0.029 J	13	560	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	5.9	4000	260	< 0.014 U	10	520	< 0.44 U	< 0.10 U	71 J		< 0.27 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	8.5	3300	490	0.073	13	600	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	7.1	4000	300	0.026 J	12	590	0.45 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	5.7	2700	290	0.028	11	540	0.53 J	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	8.0	6100	300	0.066	12	550	< 0.42 U	< 0.095 U	50 J		< 0.26 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	7.3	3300	360	< 0.017 U	8.6	460 J	< 0.45 U	< 0.10 U	52 J		< 0.28 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	11	3900	330	0.077	15	700	< 0.39 U	< 0.088 U	53 J		< 0.24 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	5.8	3300	280	< 0.017 U	10	550	< 0.40 U	< 0.090 U	46 J		< 0.25 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	5.5	1600	270	< 0.015 U	10	450	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	7.4	5100 T	340 T	0.032 T	9.6	570 T	0.41 J	< 0.092 U	59 J		< 0.25 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	9.1	2100	510	< 0.015 U	14	660	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	4.4	4100	260	< 0.017 U	12	420 J	0.46 J	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	5.1	2800 T	260	< 0.016 U	10	490	0.43 J	< 0.086 U	42 J		< 0.24 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	8.2	2500	270	0.020 J	13	760 T	< 0.49 UT	< 0.11 U	< 55 U		< 0.30 UT
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	6.0	2500	310	< 0.020 U	11	440	0.38 J	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	10	1800	400	0.030	13	560	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	11	4800	340	0.060	12	520	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	5.6	1500	200	0.024 J	9.6	550	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	5.4	950	180	0.030	7.4	460	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	15	1400	260	0.031	11	440	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	9.9	1000	140	0.045	5.1	310 J	< 0.31 U	< 0.071 U	< 35 U		< 0.19 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	8.9	3000	240	0.028	7.1	510	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	190	3200	320	0.49	10	480	< 0.40 U	< 0.089 U	63 J		< 0.24 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	6.1	4100	290	< 0.020 U	13	740	< 0.38 U	< 0.086 U	45 J		< 0.24 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	8.6	2000 T	430	< 0.020 UT	15	710 T	< 0.43 UT	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	11	3700	500	0.023 J	13	530	< 0.42 U	< 0.095 U	< 47 U		0.27 J
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	13	8100	440	< 0.014 U	14	750	< 0.46 U	< 0.10 U	53 J		< 0.28 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	10	4100	410	0.022 J	12	590	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	8.1	2200	590	< 0.017 U	17	780	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	9.6	3400	330	0.028	13	610	< 0.39 U	< 0.089 U	48 J		< 0.24 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	5.7	2800	320	< 0.015 U	11	530	< 0.40 U	< 0.091 U	48 J		< 0.25 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	5.7	3200	290	< 0.019 U	12	580	0.50 J	< 0.090 U	< 44 U		< 0.24 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	7.0	5000	380	< 0.013 U	13	610	0.55 J	< 0.093 U	54 J		< 0.25 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	14	3200	480	0.28	13	690	< 0.40 U	< 0.091 U	46 J		< 0.25 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	8.0	11000	500	< 0.010 U	12	620	0.65 J	< 0.094 U	64 J		< 0.26 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	7.8	2800	330	0.012 J	13	680 T	< 0.44 UT	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	8.3	2400	280	< 0.0099 U	14	590	< 0.36 U	< 0.082 U	53 J		< 0.22 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	5.9	6700 T	320	< 0.0093 U	12	590	< 0.41 U	< 0.093 U	53 J		< 0.25 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	19	5500	370	0.28	14	640	< 0.44 U	< 0.098 U	65 J		< 0.27 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	12	2700	290	< 0.010 U	12	510	< 0.39 U	< 0.087 U	45 J		< 0.24 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	14	1900	250	0.029 J	12	510	< 0.42 U	< 0.094 U	49 J		< 0.26 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	8.4	1900 T	460	< 0.020 U	17	530 T	0.51 JT	< 0.098 UT	< 48 UT		< 0.27 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	100	6800	470	0.051	14	690	1.0	< 0.11 U	200 J		< 0.30 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	7.9	1700	230	< 0.018 U	13	560	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	5.8	1500	260	< 0.016 U	11	480	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	15	1700	650	< 0.018 U	16	680 J	< 0.90 U	< 0.20 U	< 100 U		< 0.28 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	8.6	1600	300	< 0.018 U	12	570	0.53 J	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	19	2000	390	0.039	15	560	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	56	1700	340	0.13	12	550	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	14	2700	310	0.044	13	550	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	14	2300	350	0.022 J	14	660	< 0.36 U	< 0.081 U	< 40 U		< 0.22 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	26	3600	410	0.14	18	910	< 0.38 U	0.27 J	< 43 U		< 0.24 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	9.4	1800	300	< 0.019 U	13	680	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	9.1	1700	230	< 0.021 U	13	540	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	26	2200 T	330	0.13	16	610 T	< 0.41 UT	< 0.092 UT	< 45 UT		< 0.25 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	4.8	1100	240	< 0.018 U	7.8	510	< 0.42 U	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	8.2 T	800 T	89 T	0.25	5.1 T	230 JT	< 0.32 UT	< 0.072 UT	< 35 UT		0.28 JT
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	290	1300	190	0.49	9.2	510	0.93 J	< 0.10 U	64 J		0.28 J
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	7.4	1900	230	< 0.018 U	13	400 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	7.4	2200	200	< 0.021 UT	15	380 J	< 0.46 U	< 0.10 UT	< 51 U		< 0.29 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated		7.6	39
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated		8.4	49
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated		8.9	56
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated		6.9	38
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated		9.5	48
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated		7.5	42
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated		7.9	48
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated		6.1	36
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated		7.8	40
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated		11	52
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated		10	49
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated		10	43
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated		9.0	54
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated		9.1	47
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated		7.8	37
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated		9.5	58
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated		8.4	37
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated		6.5	34
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated		8.4	43
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated		6.3	54
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated		10	61
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated		7.4	44
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated		7.9	38
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated		7.3	37
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated		12	52
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated		7.7	41
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated		7.4	38
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated		10 T	51
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated		7.9	40
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated		10	45
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated		8.6	50
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated		7.1	31
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated		7.1	38
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated		6.5	34
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated		5.8	31
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated		7.8	35
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated		8.9	230
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated		8.6	46
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated		13 T	52 T
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated		9.5	52
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated		11	59
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated		9.3	47
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated		11	53
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated		9.7	43
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated		7.2	33
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated		7.9	36
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated		7.9	43
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated		11	56
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated		9.2	43
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated		11	56 T
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated		9.5	41
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated		8.6	45 T
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated		10	56
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated		8.3	43
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated		15	56
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated		11	50
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated		14	56
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated		11	41
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated		8.3	33
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated		19	140
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated		13	40
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated		13	51
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated		13	56
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated		12	44
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated		12	49
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated		15	61
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated		14	49
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated		12	44
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated		12 T	62 T
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated		7.6	36
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated		7.1 T	26 T
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated		12	120
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated		15	40
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated		15	46 T

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	8200	0.81 J	1.0	100	0.46	0.19 J	6200	42		8.8	310	32000
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	11000	0.39 J	1.3	39	0.47	< 0.085 U	880	14		11	41	25000
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	10000	0.62 J	1.9	74	0.46	< 0.082 U	1400	12		7.1	15	21000
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	9500	0.39 J	1.2	50	0.39 J	< 0.073 U	7700	12		8.0	19	21000
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	5300	< 0.29 U	4.2	32	0.20 J	< 0.069 U	930	6.4		4.1 J	14	11000
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	3800	< 0.32 U	3.4	18 J	0.16 J	< 0.079 U	620	4.8		3.4 J	8.3	8700
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	2400	< 0.28 U	3.0	20	0.14 J	< 0.067 U	330 J	2.7		1.4 J	6.4	5700
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	4100	0.29 J	3.1	24	0.16 J	< 0.070 U	4700	4.8		2.7 J	9.4	8100
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	5200	< 0.31 U	4.0	33	0.21 J	< 0.075 U	2800	6.3		3.9 J	15	11000
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	2300 T	0.52 JT	3.0 T	42 T	< 0.15 UT	5.4 T	1400 T	50 T		1.8 JT	37 T	5400
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	8100	0.41 J	6.9	44	0.35 J	< 0.072 U	680	9.1		5.8	16	15000
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	10000	0.38 J	6.9	58	0.42	< 0.068 U	2200	12		6.7	22	17000
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	8300	< 0.31 U	1.1	47	0.36 J	< 0.074 U	9300	10		7.2	18	18000
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	4500	< 0.26 U	4.5	30	0.19 J	0.072 J	21000	5.8		4.4	15	11000
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	6200	< 0.30 U	5.3	44	0.26 J	< 0.072 U	8000	7.6		5.8	16	13000 B
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	6400	< 0.28 U	5.4	40	0.26 J	< 0.069 U	9700	8.0		4.8	17	13000 B
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	4400	< 0.28 U	3.4	30	0.18 J	< 0.067 U	25000	5.4		3.8 J	13	9300 B
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	8400	< 0.30 U	7.6	70	0.35 J	< 0.072 U	1200	10		7.1	27	17000
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	6600	< 0.30 U	5.0	35	0.23 J	< 0.074 U	930	8.0		4.8 J	18	14000
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	7700	< 0.30 U	5.4	52	0.29 J	< 0.074 U	5800	8.8		4.8 J	15	13000
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	5000	< 0.28 U	4.0	33	0.19 J	< 0.068 U	28000	6.2		4.4 J	14	11000
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	5900	< 0.33 U	4.2	35	0.25 J	0.073 J	18000	7.5		5.9	24	13000
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	5100	< 0.34 U	5.5	27	0.21 J	0.10 J	31000	7.0		5.4	16	14000
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	5800	< 0.33 U	3.8	41	0.20 J	0.072 J	31000	7.3		5.3	17	13000
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	5900	< 0.31 U	7.2	38	1.1	0.062 J	17000	7.4		6.6	27	28000
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	8200	< 0.32 U	5.4	47	0.42 J	< 0.043 U	2300	9.6		7.0	19	16000
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	7300	< 0.33 U	5.0	44	0.34 J	< 0.044 U	640	9.3		6.3	18	16000
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	4500	< 0.31 UT	4.1	27	0.15 J	0.094 JT	54000	6.3		4.7	16	11000
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	6000	< 0.31 U	4.2	36	0.22 J	0.068 J	30000	7.8		5.5	18	14000
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	6500	< 0.27 U	3.5	29	0.24 J	0.088 J	12000	8.1		6.2	33	15000
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	8400	< 0.43 U	7.0	44	0.39 J	< 0.057 U	1000	11		8.0	24	19000
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	8100	< 0.35 U	5.7	69	0.33 J	0.052 J	750	12		8.5	24	18000
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	8800	< 0.30 U	6.7	66	0.41	0.073 J	1300	11		8.8	22	19000
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	5200	< 0.32 UT	5.2	25	0.22 J	0.073 J	21000	7.8		5.4	18	14000
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	5400	< 0.34 U	4.3	29	0.20 J	0.086 J	28000	6.9		5.3	18	14000
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	5500	< 0.37 U	4.9	24	0.22 J	0.064 J	28000	7.3		5.3	16	14000
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	7000	< 0.34 U	6.2	87	0.33 J	< 0.046 U	880	8.8		7.4	20	17000
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	7600	< 0.35 U	6.1	43	0.35 J	0.056 J	890	9.4		8.1	18	17000
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	7900	< 0.36 U	7.0	43	0.39 J	0.057 J	950	9.5		7.5	22	17000
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	5300	< 0.35 U	5.1	31	0.24 J	0.086 J	15000	7.5		5.8	20	13000
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	4600	< 0.31 U	2.8	24	0.16 J	0.099 J	42000	6.0		4.4	17	9700
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	6900	< 0.31 U	5.8	50	0.32 J	0.062 J	3500	9.0		6.2	22	16000
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	10000	< 0.38 UT	8.1	50	0.49 J	< 0.050 U	790	11		8.5	22	20000
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	8400	< 0.32 U	6.6	86	0.38 J	0.16 J	2000	10		5.4	22	15000
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	7800	< 0.36 U	6.8	45	0.39 J	0.052 J	3100	11		7.7	23	17000
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	6600	< 0.36 U	5.2	43	0.30 J	< 0.048 U	760	8.7		5.9	17	15000
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	6900	< 0.35 U	6.9	41	0.37 J	< 0.047 U	2200	8.5		7.0	19	16000 B
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	6700	< 0.38 U	7.9	69	0.37 J	< 0.051 U	880	8.9		7.0	22	16000 B
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	6800	< 0.37 U	7.6	67	0.39 J	0.081 J	23000	8.5		5.7	23	15000 B
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	5700	< 0.37 U	5.4	29	0.29 J	< 0.049 U	730	7.3		5.5	19	13000 B
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	6300	< 0.36 U	5.7	41	0.31 J	< 0.048 U	1000	8.3		6.2	19	15000 B
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	7200	< 0.30 U	6.2	62	0.36 J	0.12 J	4200	12		6.7	76	15000
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	10000	< 0.35 U	3.9	130	0.38 J	0.063 J	1700	11		5.3	10	13000
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	9500	0.35 J	7.2	75	0.43 J	0.13 J	5800	13		8.4	32	21000
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	7800	< 0.34 U	5.5	44	0.36 J	0.055 J	870	9.3		7.7	20	17000
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	6900	< 0.31 U	5.5	43	0.34 J	0.068 J	1900	8.1		6.3	27	16000
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	7700	0.38 J	6.4	77	0.35 J	0.067 J	1000	9.5		8.2	23	18000
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	8700	< 0.39 U	8.6	55	0.45 J	< 0.052 U	750	9.9		8.2	22	21000
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	8800	< 0.31 U	6.4	64	0.41 J	0.092 J	6600	11		7.6	30	18000
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	7700	< 0.34 U	6.2	88	0.42 J	0.13 J	26000	9.9		6.6	28	15000
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	11000	< 0.44 U	7.0	110	0.58 J	0.19 J	6600	25		8.7	24	21000
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	11000	< 0.32 U	10	88	0.48	< 0.042 U	5300	13		11	22	26000
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	9800	< 0.37 U	9.9	51	0.54	< 0.050 U	850	12		11	26	23000
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	7200	< 0.27 U	6.3	34	0.34 J	< 0.037 U	340 J	8.2		7.0	20	17000
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	10000	< 0.37 U	6.4	46	0.43 J	< 0.049 U	910	11		7.9	15	19000
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	8900	< 0.37 U	6.4	48	0.39 J	< 0.049 U	870	11		7.2	21	19000
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	7700	< 0.34 U	7.6	52	0.40 J	0.048 J	1100	8.7		8.6	23	18000
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	7700	< 0.39 U	6.4	79	0.39 J	0.14 J	64000	9.5		5.6	29	13000
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	8200	< 0.34 UT	6.6	71 T	0.43 J	0.060 J	1500	9.4		8.0	20	19000
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	9100	< 0.34 U	5.4	73	0.37 J	< 0.046 U	3500	9.7		6.2	19	16000
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	12000	< 0.45 U	4.1	160	0.57 J	0.13 J	5600	11		5.7	11	15000
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	7200	< 0.39 U	6.9	54	0.37 J	0.060 J	2400	9.0		6.4	21	18000
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	7600	< 0.39 U	6.4	50	0.36 J	0.12 J	7200	9.3		6.4	21	17000
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	6200	< 0.28 U	4.2	24	0.26 J	< 0.037 U	570	7.2		5.2	14	13000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	93	2500	430	0.074	120	390 J	< 0.47 U	< 0.11 U	100 J		0.43 J
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	10	3000	350	< 0.022 U	29	410 J	< 0.54 U	< 0.12 U	< 59 U		< 0.33 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	13	2300	380	0.29	16	360 J	< 0.51 U	< 0.12 U	< 57 U		< 0.32 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	15	3000	360	0.12	18	360 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	5.8	1400	280	0.021	11	500	< 0.43 U	< 0.098 U	57 J		< 0.27 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	4.2	1200	150	< 0.0093 U	7.7	390 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	3.2	490	390	0.024	4.3	230 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	6.3	1400	180	0.036	7.0	370 J	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	10	1600	320	< 0.0088 U	9.8	550	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	100 T	910 T	68 T	1.2	6.5 T	260 JT	< 0.64 UT	0.72 T	< 71 UT		< 0.39 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	7.7	1900	350	0.0090 J	14	730	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	22	2300	310	0.092	16	760	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	15	2700	380	0.11	15	320 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	4.9	3500	240	< 0.0077 U	11	590	< 0.40 U	< 0.091 U	46 J		< 0.25 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	9.1	2800	560	0.090	12	740	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	13	3100	330	0.096	13	780	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	4.4	5000	260	0.0087 J	9.7	610	0.57 J	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	10	2000	550	0.028	16	1000	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	6.3	1700	260	0.024	13	640	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	13	2100	310	0.051	12	620	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	6.7	9000	390	0.015 J	10	660	0.47 J	< 0.096 U	66 BJ		< 0.26 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	8.5	4000	550	< 0.020 U	17	630	< 0.44 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84[1]	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	7.6	3800	310	0.066 J	14	560	< 0.44 U	< 0.076 U	66 J		< 0.37 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	5.5	3700	320	< 0.022 U	14	560	< 0.44 U	< 0.075 U	60 J		< 0.37 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	8.3	5000	600	< 0.021 U	18	590	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	7.3	2100	400	0.025 J	18	610	< 0.42 U	< 0.072 U	< 56 U		< 0.36 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	7.4	1900	200	0.021 J	16	560	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	7.1 T	6400 T	290 T	< 0.018 U	12	480	< 0.41 UT	< 0.070 U	59 J		< 0.35 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	5.9	4400	320	< 0.018 U	15	600	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	5.9	5600	510	< 0.022 U	16	570	< 0.35 U	< 0.061 U	< 47 U		< 0.30 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	8.8	2400	370	0.028 BJ	20	700	< 0.56 U	< 0.097 U	< 75 U		< 0.48 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	8.3	2500	600	< 0.019 U	20	640	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	12	2400	640	0.020 J	27	620	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	6.7	7200 T	430	< 0.020 U	14	520	< 0.41 U	< 0.071 U	66 J		< 0.35 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	5.7	4800	310	< 0.020 U	14	520	< 0.44 U	< 0.076 U	68 J		< 0.37 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	7.1	12000	410	< 0.018 U	14	530	< 0.48 U	< 0.083 U	73 J		< 0.41 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	7.4	2000	440	< 0.024 U	18	620	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	8.4	2300	500	< 0.017 U	18	640	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	8.0	1900	390	0.023 BJ	17	670	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	8.3	3900	670	0.13 B	14	520	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	8.9	2800	270	0.065 BJ	11	470	< 0.40 U	< 0.069 U	66 J		< 0.34 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	7.1	3400	410	< 0.023 U	16	610	< 0.41 U	< 0.070 U	< 54 U		< 0.35 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	12	2400	490	< 0.020 U	18	770	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	59	1800	560	0.13 B	13	460	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	10	2500	460	0.12	120	590	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	6.1	2000	340	0.031 J	15	440 J	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	9.3	1800	460	< 0.020 U	15	660	< 0.45 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	10	1800	540	0.022 J	15	720	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	21	13000	510	0.023 J	20	900	< 0.48 U	< 0.083 U	70 J		< 0.41 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	7.0	1600	440	< 0.019 U	12	560	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	7.0	1900	370	< 0.018 U	14	590	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	29	2900	400	0.062 J	28	470	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	11	1800	630	0.045 J	14	510	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	34	2900	470	0.080 J	23	740	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	7.1	2300	470	0.026 J	25	530	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	18	1900	440	< 0.025 U	17	560	< 0.40 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	7.5	2100	540	< 0.022 U	26	650	< 0.46 U	< 0.080 U	< 62 U		< 0.39 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	8.7	2200	760	0.020 J	19	620	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	34	2800	460	0.52	28	570	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	46	3300	420	0.43	75	680	< 0.45 U	< 0.078 U	87 J		< 0.38 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	32	3100	500	0.63	23	930	< 0.58 U	< 0.099 U	94 J		< 0.49 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	13	4300	540	< 0.019 U	26	1100	< 0.41 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	11	2500	430	0.021 J	37	760	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	7.8	1900	520	0.017 J	15	480	< 0.36 U	< 0.062 U	< 48 U		< 0.31 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	8.0	2500	330	0.037 J	17	630	< 0.48 U	< 0.083 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	8.5	2300	330	0.028 J	41	730	< 0.48 U	< 0.082 U	< 64 U		< 0.41 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	11	1900	690	0.048 J	21	770	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	73	34000	470	1.3	260	610	< 0.51 U	< 0.087 U	150 J		< 0.43 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	11 T	2200	810	0.068 J	23	600	< 0.45 UT	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	11	2100	630	0.044 J	120	540	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	7.6	1700	880	0.030 J	13	690	< 0.59 U	< 0.10 U	< 79 U		< 0.51 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	10	2800	520	< 0.019 U	17	750	< 0.51 U	< 0.089 U	93 J		< 0.44 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	8.8	5500	1000	0.019 J	18	770	< 0.51 U	< 0.088 U	< 68 U		< 0.44 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	6.4	1800	280	< 0.017 U	12	460	< 0.37 U	< 0.063 U	< 49 U		< 0.31 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated		17	130
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated		23	81
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated		19	51
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated		17	59
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated		8.3	35
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated		6.3	24
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated		4.6	16
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated		6.5	27
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated		8.2	39
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated		5.2 JT	210
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated		13	40
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated		17	63
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated		16	52
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated		7.9	37
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated		11	44
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated		11	48
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated		7.3	40
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated		16	55
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated		11	53
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated		13	46
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated		8.6	47
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated		11	51
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated		11	53
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated		9.3	51
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated		12	87
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated		12	62
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated		13	49
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated		8.4	44
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated		9.6	62
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated		11	56
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated		14	64
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated		14	68
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated		15	83
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated		11	54
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated		9.2	87
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated		9.5	48
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated		12	100
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated		12	64
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated		13	57
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated		11	62
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated		7.9	42
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated		12	82
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated		15	55
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated		13	97
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated		13	71
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated		10	85
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated		13	52 B
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated		12	51 B
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated		12	97 B
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated		9.8	42 B
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated		11	48 B
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated		11	83
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated		13	48
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated		15	77
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated		11	58
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated		11	61
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated		12	69
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated		13	73
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated		13	73
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated		13	80
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated		16	94
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated		15	67
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated		16	71
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated		11	56
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated		14	51
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated		13	62
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated		13	65
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated		13	66
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated		12	66
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated		13	47
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated		14	44
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated		13	69
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated		13	63
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated		9.3	60

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	7300	< 0.32 U	6.1	50	0.35 J	0.069 J	2500	11		6.4	20	17000
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	8300	< 0.39 U	5.9	35	0.38 J	< 0.052 U	690	9.2		6.4	18	18000
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	8400	< 0.34 U	5.8	60	0.39 J	0.094 J	1600	10		7.3	23	18000
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	7100	< 0.34 U	8.6	58	0.35 J	0.062 J	990	8.2		8.0	21	17000
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	7500	0.88 J	10	110	0.48 J	0.25 J	2500	11		6.8	43	18000
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	8000	0.81 J	19	98	0.39 J	0.42 J	5000	12		6.3	46	23000
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	7000	0.81 J	8.7	130	0.45 J	0.26 J	2700	11		6.7	39	16000
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	8100	< 0.38 U	8.8	120	0.44 J	0.32 J	4000	12		7.1	57	21000
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	7600	< 0.38 U	9.7	90	0.41 J	0.36 J	37000	11		7.5	37	16000
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	7500	0.41 J	11	90	0.39 J	0.62	2700	10		6.6	41	21000
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	6000	0.96 JT	8.0	140 T	0.48 J	0.21 J	6700 T	7.9		5.6	38	8900
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	6400	< 0.35 U	20	75	0.49	1.1	3300	8.5		9.3	27	13000
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	7800	< 0.33 U	6.8	41	0.36 J	0.078 J	860	8.9		6.4	20	16000 B
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	7600	< 0.37 U	7.3	59	0.35 J	0.15 J	4900	11		6.8	34	18000
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	8000	< 0.38 U	6.8	70	0.42 J	0.15 J	3500	9.9		6.8	22	20000
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	6500	< 0.29 U	6.4	58	0.30 J	0.14 J	1900	8.3		5.8	21	15000
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	7500	0.37 J	5.8	61	0.40 J	0.12 J	1700	9.1		8.8	22	17000
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	8300	0.42 J	7.0	61	0.38 J	0.11 J	2700	9.7		7.1	20	18000
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	6600	0.42 J	5.6	48	0.28 J	0.13 J	1400	8.0		6.1	24	15000
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	8100	< 0.38 U	6.7	86	0.36 J	0.11 J	1000	9.7		6.9	22	17000
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	7600	< 0.39 U	6.8	73	0.34 J	0.11 J	2200	10		6.6	23	18000
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	12000	< 0.34 U	5.2	55	0.43 J	< 0.046 U	680	12		6.7	13	19000
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	6900	< 0.38 U	7.5	86	0.34 J	0.063 J	740	8.5		7.5	22	17000
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	8500	< 0.36 U	8.9	67	0.39 J	0.062 J	1200	11		7.1	29	19000
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	7700	< 0.41 U	5.9	38	0.35 J	< 0.054 U	380 J	8.6		7.8	18	16000
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	9200	< 0.37 U	5.8	59	0.38 J	0.051 J	980	10		6.9	23	16000
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	7700	< 0.32 U	6.1	53	0.34 J	< 0.042 U	430 J	8.7		7.3	19	16000
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	7300	100	7.7	76	0.36 J	0.35 J	2200	11		7.4	120	17000
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	6600	< 0.30 U	4.9	48	0.29 J	0.044 J	660	8.1		7.1	18	14000
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	8200	< 0.37 U	5.4	59	0.35 J	< 0.050 U	840	9.5		6.5	18	17000
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	5300	< 0.35 U	4.6	29	0.20 J	0.092 J	11000	6.5		5.2	15	14000
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	5400	< 0.33 U	4.0	27	0.18 J	0.068 J	11000	6.3		5.0	17	13000
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	5000	< 0.30 U	4.4	31	0.12 J	0.056 J	22000	6.4		5.2	16	12000
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	6100	< 0.30 U	7.0	41	0.21 J	0.16 J	15000	7.7		6.1	21	15000
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	6600	< 0.37 U	5.8	31	0.31 J	0.053 J	2900	8.2		6.5	20	15000
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	4600	< 0.32 U	4.4	26	0.11 J	0.063 J	21000	6.2		4.6	13	12000
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	6300	< 0.41 U	8.6	82	0.42 J	0.40 J	7100	10		5.6	30	15000
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	10000	< 0.28 U	10	79	0.48	0.10 J	3600	13		12	17	25000
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	6300	< 0.34 U	7.8	68	0.34 J	0.28 J	8500	9.0		5.7	26	16000
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	7800	< 0.34 U	7.0	55	0.37 J	0.10 J	870	9.4		7.6	21	17000
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	12000	< 0.31 U	5.4	77	0.45	0.071 J	440	13		11	12	19000
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	11000	< 0.29 U	6.2	53	0.43	0.086 J	1400	13		7.5	15	19000
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	9700	< 0.34 U	7.2	50	0.44 J	0.10 J	900	11		7.6	19	20000
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	6400	< 0.37 U	5.1	38	0.26 J	0.10 J	920	7.7		5.2	14	14000
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	7400	< 0.34 U	6.5	42	0.33 J	0.085 J	460 J	8.5		6.5	18	16000
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	8700	< 0.29 U	7.8	49	0.40	0.10 J	1900	11		8.1	18	19000
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	11000	< 0.37 U	6.4	96	0.44 J	0.12 J	1500	12		6.8	19	18000
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	11000	< 0.35 U	6.5	60	0.44 J	0.13 J	1400	13		7.8	22	19000
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	11000	< 0.43 U	4.6	140	0.47 J	0.090 J	1900	11		7.0	14	17000
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	9600	< 0.43 UT	12	130 T	0.48 J	0.095 J	2800	10		8.1	18	15000
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	9700	< 0.35 U	12	440	0.49	0.13 J	4700	17		9.8	1000	25000
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	13000	< 0.38 U	6.8	58	0.52 J	0.092 J	350 J	13		9.2	15	21000
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	6800	< 0.36 U	8.7	46	0.30 J	0.21 J	4400	8.6		6.0	21	16000
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	9800	< 0.36 U	8.8	99	0.42 J	0.30 J	6300	20		8.0	52	20000
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	6000	< 0.34 U	9.2	99	0.37 J	0.27 J	23000	13		4.8	69	18000
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	8800	< 0.30 U	8.4	75	0.41 J	0.11 J	5000	12		10	36	25000
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	7900	< 0.34 U	6.8	55	0.40 J	0.098 J	4500	9.4		6.5	21	17000
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	7600	< 0.36 U	6.3	76	0.43 J	0.26 J	1400	9.2		7.4	19	17000
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	7400	< 0.38 U	6.9	51	0.39 J	0.082 J	1100	9.3		5.9	18	17000
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	4800	< 0.31 U	3.5	39	0.17 J	0.057 J	26000	6.1		5.0	16	12000
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	8400	0.24 J	5.6	78	0.35	0.45	50000	9.8		6.4	63	15000
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	6700	< 0.21 U	10	72	0.44	0.56	16000	12		8.0	44	15000
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	7700	< 0.24 U	7.0	60	0.35	0.52	23000	10		9.5	22	18000
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	5900	6.2	36	180	0.42 J	8.0	6600	52		45 J	1100	280000
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	7500	< 0.29 U	4.4	51	0.31 J	0.43 J	550	8.1		6.8	24	15000
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	9900	< 0.31 UT	7.7 T	94 T	0.43 T	0.57	3500 T	14 T		8.6	29	23000
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	5400	0.50 J	3.9	41	0.24 J	0.15 J	110000	7.0		5.7	20	13000
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	7100	0.86 JT	4.2 T	49 T	0.29 JT	0.14 JT	58000 T	8.8 T		6.4 T	22 T	16000
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	6500	0.59 J	3.9	46	0.26 J	0.11 J	36000	8.0		6.3	20	15000
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	7000	0.62 J	6.0	52	0.34 J	0.16 J	44000	9.4		7.0	20	17000
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	14000	0.58 J	8.9	43	0.54	0.49	1100	13		8.3	17	24000
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	11000	< 1.0 U	8.1	74	0.51 J	0.43	870	12		8.1	26	18000
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	12000	0.72	10	29	0.51	0.52	850	13		8.7	20	23000
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	12000	0.81 J	13	44	0.58	0.57	1100	13		9.6	19	27000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	9.4	2900	420	< 0.018 U	17	730	< 0.42 U	< 0.072 U	< 56 U		< 0.35 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	8.7	2200	420	< 0.018 U	16	660	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	13	2400	720	0.031 J	130	670	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	240	1600	1200	0.020 J	17	520	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	280	1400	470	0.17	18	450 J	< 0.50 U	< 0.087 U	78 J		< 0.43 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	170	2300	460	0.43	15	510	< 0.44 U	< 0.076 U	69 J		< 0.38 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	390	1300	390	0.23	17	480	0.48 J	< 0.078 U	92 J		< 0.38 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	110	1600	530	0.52	17	430 J	< 0.49 U	< 0.085 U	94 J		< 0.42 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	140	3300	380	0.36	19	540	0.90 J	< 0.086 U	110 J		< 0.42 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	110	1600	490	0.28	16	460	3.8	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	220 T	990	300 T	0.24 T	12	450 J	0.74 J	< 0.093 U	160 J		< 0.46 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	280	710	300	0.74	20	390 J	7.0	0.081 J	130 J		< 0.39 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	6.9	1900	340	0.022 J	19	590	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	21	2100	450	0.051 J	25	600	< 0.48 U	< 0.082 U	< 64 U		< 0.41 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	20	2800	440	0.048 J	16	520 J	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	21	1800	480	0.039 J	18	470	< 0.38 U	< 0.066 U	< 51 U		< 0.32 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	18	2100	660	0.058 J	17	570	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	13	2500	480	0.050 J	17	670	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	10	1800	570	0.059 J	16	530	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	8.9	2000	590	0.030 J	17	710	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	8.7	2900	440	0.025 J	18	610	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	8.3	2400	230	0.035 J	16	550	< 0.45 U	< 0.078 U	72 J		< 0.38 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	11	1800	590	0.030 J	18	630	< 0.49 U	< 0.085 U	87 J		< 0.42 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	8.7	2500	490	0.026 J	18	650	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	11	1900	580	0.030 J	15	490 J	< 0.53 U	< 0.091 U	78 J		< 0.45 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	18	2100	400	0.050 J	17	520	< 0.48 U	< 0.083 U	< 65 U		< 0.41 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	9.6	1900	550	0.022 J	16	600	< 0.42 U	< 0.072 U	75 J		< 0.35 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	270	2200	660	0.052 J	22	590	< 0.42 U	0.098 J	81 J		< 0.36 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	8.6	1800	810	0.047 J	15	470	< 0.39 U	0.075 J	< 52 U		< 0.33 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	10	2000	450	0.041 J	15	500 J	< 0.49 U	< 0.084 U	< 65 U		< 0.42 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	6.8	3700	340	< 0.018 U	13	510	< 0.45 U	< 0.078 U	< 60 U		< 0.38 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	5.9	5200	320	< 0.019 U	13	500	< 0.43 U	< 0.074 U	64 J		< 0.37 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	8.2	4700	310	< 0.020 U	13	460	< 0.39 U	< 0.067 U	< 52 U		< 0.33 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	20	3800	430	0.028 J	17	530	< 0.40 U	< 0.068 U	< 53 U		< 0.34 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	8.9	3000	300	0.018 J	16	710	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	6.2	2600	290	< 0.022 U	12	450	< 0.42 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	64	2500	410	0.081 J	18	440 J	< 0.54 U	< 0.093 U	110 J		< 0.46 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	13	3400	430	0.019 J	26	980	< 0.37 U	< 0.064 U	57 J		< 0.31 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	37	3000	400	0.062 J	16	400 J	< 0.45 U	< 0.077 U	81 J		< 0.38 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	10	2100	400	0.035 J	19	590	< 0.45 U	< 0.078 U	62 J		< 0.38 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	7.9	2500	350	0.035 J	17	540	< 0.40 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	9.8	2500	310	0.034 J	18	600	0.38 J	< 0.065 U	< 51 U		< 0.32 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	9.1	2200	400	0.038 J	17	510	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	6.3	1700	290	0.057 J	13	740	< 0.49 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	8.7	1800	380	0.024 J	15	520	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	9.0	2200	380	0.037 BJ	19	660	< 0.38 U	< 0.065 U	60 BJ		< 0.32 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	22	2200	570	0.084 BJ	16	530	< 0.48 U	< 0.083 U	68 BJ		< 0.41 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	13	2500	340	0.052 BJ	19	610	< 0.45 U	< 0.078 U	65 BJ		< 0.38 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	17	2100	800	0.066 BJ	15	440 J	0.64 J	< 0.098 U	< 76 U		< 0.48 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	34 T	1700	940	0.13 B	13	520 J	1.4 J	< 0.096 U	110 BJ		< 0.47 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	46	2500	510	0.083 BJ	40	910	0.48 J	< 0.078 U	66 BJ		< 0.38 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	9.1	2800	310	< 0.023 U	19	620	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	8.8	3400	450	0.035 J	16	640	< 0.48 U	< 0.082 U	< 64 U		< 0.40 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	40	3400	570	0.096 J	56	650	< 0.47 U	< 0.081 U	170 J		< 0.40 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	69	7800	220	0.15	22	410 J	< 0.45 U	0.13 J	99 J		< 0.38 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	18	2700	410	0.039 J	25	760	0.43 J	< 0.068 U	54 J		< 0.33 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	9.3	3300	530	0.022 J	17	800	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	9.5	2600	660	0.024 J	31	790	< 0.47 U	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	7.7	2200	360	< 0.024 U	16	710	< 0.50 U	< 0.086 U	< 67 U		< 0.43 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	4.7	4000	330	< 0.017 U	12	340 J	< 0.41 U	< 0.070 U	< 54 U		< 0.34 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	32	5100	410	0.064	18	300 J	< 0.33 U	< 0.074 U	60 J		0.22 J
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	61	4400	350	0.16	23	290 J	0.43 J	< 0.073 U	58 J		0.24 J
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	14	5400	420	0.029 J	20	410	< 0.36 U	< 0.082 U	54 J		< 0.22 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	380	1300	1300	0.052	7300	200 J	2.3	0.45 J	160 J		< 8.1 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	10	2200	590	0.030 J	17	260 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	14	3600 T	450 T	0.019 JT	28	490 J	< 0.48 UT	< 0.11 UT	63 JT		< 0.29 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	7.0	4100	610	0.022 BJ	15	540	< 0.45 U	< 0.10 U	84 J		0.37 J
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	6.4 T	6400 T	330	0.034 B	16 T	630 T	< 0.46 UT	< 0.10 UT	71 JT		0.41 JT
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	6.1	4200	290	0.026 BJ	15	600	< 0.43 U	< 0.097 U	< 48 U		0.31 J
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	9.5	4200	410	0.021 BJ	17	660	< 0.42 U	< 0.096 U	48 J		0.38 J
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	11	3200	240	< 0.024 U	19	620	< 0.31 U	< 0.070 U	< 34 U		0.47 J
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	12	2200	360	< 0.022 U	21	1100 J	< 0.31 U	< 0.35 U	< 170 U		0.42 J
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	10	3200	280	< 0.024 U	19	580	0.42 J	< 0.070 U	< 34 U		0.47 J
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	11	2900	390	< 0.023 U	19	650	< 0.42 U	< 0.096 U	< 47 U		0.60 J

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated		14	69
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated		13	55
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated		12	110
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated		11	71
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated		18	140
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated		16	160
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated		16	160
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated		15	200
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated		18	150
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated		20	180
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated		18	91 T
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated		29	390
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated		12	68
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated		13	70
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated		14	60
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated		12	59
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated		12	67
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated		13	66
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated		11	57
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated		13	61
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated		13	67
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated		17	51
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated		12	64
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated		14	82
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated		11	52
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated		14	57
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated		12	51
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated		12	120
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated		10	54
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated		13	52
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated		9.2	57
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated		9.6	50
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated		8.2	55
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated		11	66
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated		11	53
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated		8.2	59
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated		13	66
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated		13	70
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated		12	70
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated		11	71
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated		17	51
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated		16	53
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated		16	54
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated		10	63
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated		12	47
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated		15	63
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated		16	61
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated		17	67
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated		16	49
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated		16	43
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated		16	90
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated		19	56
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated		10	100
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated		15	100
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated		13	110
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated		13	68
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated		12	68
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated		11	120
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated		11	58
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated		6.7	50
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated		13	61
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated		14	96
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated		14	53
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated		24	480
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated		12	69
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated		14	68 T
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated		9.6	44 B
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated		12 T	57 BT
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated		11	57 B
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated		12	60 B
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated		19	57
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated		16 J	48
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated		19	54
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated		20	65

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	14000	< 1.0 UT	15	84	0.67 J	< 0.25 U	1000	16		9.9	35	22000
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	6200 T	0.49 J	5.1	47	0.23 J	0.42 J	35000	3.9		5.1	22	16000
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	843.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	4800	0.66 J	4.0	42	0.18 J	0.32 J	57000	< 2.2 U		4.0 J	16	13000
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	5100	0.61 J	3.3	24	0.16 J	0.33 J	40000	4.5		4.0 J	16	12000
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	5900	0.55 J	4.6	31	0.22 J	0.35 J	49000	2.4		4.8	18	14000
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	4900	0.76	3.8	42	0.18 J	0.41	31000	< 0.60 U		3.9	17	13000
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	8200	0.99	5.4	55	0.26 J	0.57	32000	2.9		6.1	28	18000
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	6700	0.87	6.1	41	0.23 J	0.47	32000	2.1		5.0	26	16000
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	6600	0.95	6.1	55	0.24 J	0.51	41000	0.72		5.8	22	16000
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	5800	1.0	4.3	35	0.20 J	0.45	110000	< 2.8 U		4.1	18	14000
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	5400	< 0.2	5.2	49	0.21	0.058	34000	8.6		4.7	17	13000
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	5300	< 0.2	12	42	0.21	0.015	36000	8		4.5	16	13000
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated		< 1.06 U	3.55	42.2	< 0.532 U	< 0.532 U		7.49		5.87	15.9	
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated		< 1.04	4.51	34.1	< 0.518	< 0.518		6.26		5.78	16.5	
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated	5100	< 0.36 U	4.5	40	0.2 J	0.056 J	62000	7.1		4.1 J	14	11000
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated	9000	0.88 J	5.3	67	0.36 J	0.16 J	4400	21		5.8	20	18000
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated	4900	< 0.35 U	3.5	39	0.2 J	0.075 J	31000	7.5		4.1 J	14	12000
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated	7000	0.61 J	6.6	48	0.29 J	0.09 J	2600	11		5.8	20	17000
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated	7300	< 0.39 U	6.2	46	0.33 J	0.1 J	2200	10		6.6	19	17000
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated	6900	< 0.35 U	4.5	41	0.26 J	0.13 J	46000	9.8		5.5	21	14000
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated	6000	< 0.36 U	3.8	37	0.25 J	0.24 J	16000	7.8		5 J	16	14000
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated	7600	< 0.38 U	5.1	55	0.35 J	0.13 J	44000	16		6.3	40	17000
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated	6300	< 0.37 U	4.5	48	0.28 J	0.12 J	35000	9.1		6.2	25	15000
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated	6500	0.45 J	5.6	42	0.27 J	0.11 J	39000	9.2		5.5	21	16000
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated	5300	< 0.4 U	6.3	49	0.3 J	0.095 J	3100	7.4		5.9	20	14000
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated	8300	< 0.37 U	6.5	57	0.37 J	0.076 J	10000	11		7.5	17	17000
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated	5500	< 0.36 U	5.8	45	0.22 J	0.12 J	42000	12		5.1 J	21	14000
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated	7300	< 0.35 U	4.7	46	0.29 J	0.1 J	38000	12		6.4	23	17000
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated	7300	0.69 J	7.2	74	0.33 J	0.13 J	2000	16		6.8	32	20000
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated	5700	< 0.4 U	4.6	36	0.22 J	0.21 J	29000	7.6		5 J	16	13000
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated	6800	< 0.35 U	3.9	84	0.22 J	0.098 J	50000	8.7		5.5	23	15000
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated	5800	< 0.37 U	4.1	52	0.21 J	0.1 J	53000	7.5		5.3 J	20	14000
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated	6000	< 0.35 U	4.3	44	0.24 J	0.11 J	23000	11		5.4	17	14000
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated	9100	< 0.41 U	5.5	86	0.36 J	0.096 J	15000	13		7.4	19	17000
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated	10000	< 0.45 U	6.2	97	0.43 J	0.076 J	1900	14		7.5	19	19000
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated	8600	< 0.4 U	7.2	56	0.41 J	0.076 J	2000	10		6.6	21	17000
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated	6700	< 0.37 U	6.8	43	0.28 J	0.1 J	84000	9.2		6	18	15000
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated	6600	< 0.38 U	5.2	47	0.25 J	0.11 J	63000	9.6		6.1	22	14000
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated	7000	< 0.37 U	6.4	61	0.3 J	0.083 J	5400	9.3		6.3	18	16000
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated	5500	< 0.37 U	4.5	33	0.22 J	0.1 J	31000	7.9		4.7 J	19	13000
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated	8600	< 0.36 U	6	72	0.33 J	0.088 J	6300	11		7	25	19000
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated	9400	< 0.43 U	12	89	0.47 J	0.13 J	2400	11		8.5	27	20000
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated	9100	0.52 J	11	98	0.47 J	0.13 J	5000	12		7.4	32	22000
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated	9800	< 0.41 UJ	8.9	86	0.46 J	0.11 J	1700	14		7.9	29	20000
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated	5700	< 0.41 U	6.9	35	0.26 J	0.11 J	50000	7.6		5.3 J	18	13000
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated	7000	< 0.37 U	5.5	46	0.27 J	0.088 J	37000	10		6.5	20	15000
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated	5600	< 0.35 U	4.1	55	0.21 J	0.12 J	57000	11		5.1	18	12000
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated	7400	< 0.35 U	5.2	51	0.27 J	0.093 J	42000	10		6	22	16000
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated	5900	< 0.36 U	4.8	44	0.23 J	0.085 J	14000	11		5.5	23	14000
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated	6400	< 0.36 U	5.4	90	0.23 J	0.12 J	23000	9.1		6	21	16000
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated	6900	< 0.41 U	5.7	50	0.3 J	0.12 J	3600	10		6	24	17000
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated	5900	< 0.37 U	4.1	36	0.23 J	0.13 J	42000	8.1		5.1 J	16	13000
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated	11000	0.51 J	8.1	42	0.5	< 0.044 U	1200	12		9.3	19	20000
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated	12000	< 0.42 U	13	88	0.62	0.08 J	1300	15		8.6	35	26000
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated	7000	< 0.36 U	5.5	49	0.28 J	0.11 J	11000	8.8		5.1 J	15	14000
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated	7600	< 0.4 U	7.2	70	0.33 J	0.095 J	17000	9.2		5.9	22	16000
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated	6400	< 0.41 U	7	36	0.33 J	0.056 J	1100	8.6		6.5	17	16000
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated	6400	< 0.39 UJ	6.5 J	50 J-	0.27 J	0.093 J	2900 J	9.8 J-		5.6 J	19 J-	16000
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated	9100	< 0.37 U	6.6	81	0.38 J	0.045 J	980	11		7	31	18000
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated	6500	0.46 J	10	93	0.44 J	0.34 J	810	9.8		6.6	39	18000
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated	6900	< 0.36 U	6.7	61	0.3 J	0.083 J	2000	13		5.9	22	15000
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated	5900	< 0.36 U	4.3	45	0.23 J	0.2 J	50000	11		5.3 J	27	13000
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated	5700	< 0.36 U	5	1200	0.2 J	0.096 J	49000	8		4.8 J	18	13000
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated	6500	< 0.35 U	4.8	67	0.27 J	0.089 J	40000	9.4		6.4	17	15000
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated	5700	< 0.38 U	4.5	180	0.23 J	0.063 J	63000	9.6		4.8 J	17	13000
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated	7700	< 0.36 U	5.3	57	0.34 J	0.11 J	4400	12		6.6	22	17000
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated	6200	< 0.37 U	4.5	49	0.24 J	0.084 J	25000	9.2		5.6	19	14000
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated	7800	< 0.38 U	5.5	62	0.34 J	0.086 J	8000 J	10		6.4	19	16000
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated	7200	0.42 J	5.8	61	0.3 J	0.11 J	22000	17		6.4	21	16000
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated	5800	< 0.42 U	6.8	33	0.29 J	0.077 J	1800	8.4		5.5 J	19	15000
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated	6300	< 0.36 U	5.6	36	0.28 J	0.11 J	14000	9.1		5.8	17	16000
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated	5800	< 0.35 U	5.3	39	0.23 J	0.078 J	27000	11		5.2	16	13000
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated	5600	< 0.38 U	5.2	62	0.19 J	0.11 J	50000	8.9		6.4	18	13000
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated	3700	< 0.36 UJ	4.5	26	0.18 J	0.091 J	18000	6.7		3.6 J	12	10000

												Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	14	2100	300	< 0.023 U	24	930 J	< 1.6 U	< 0.36 U	< 180 U		< 0.98 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	9.5 J	5300	270	< 0.022 U	17	480 J	< 0.47 U	0.20 J	52 J		< 1.4 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	9.2 J	17000	430	< 0.019 U	13	370 J	< 0.45 U	0.14 J	65 J		< 1.4 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	6.7 J	3000 T	340	0.11	14	310 J	< 0.38 U	0.13 J	< 42 U		< 1.2 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	8.8	5200	300	0.039	16	360 J	< 0.35 U	0.16 J	46 J		< 1.1 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	8.1	3400	320	0.50	13	290 J	< 1.5 U	0.17 J	40 J		< 0.19 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	10	4900	360	< 0.021 U	20	410 J	< 1.9 U	0.24 J	52 J		< 0.24 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	9.8	8400	320	< 0.021 U	18	360	< 1.6 U	0.21 J	73 J		< 0.38 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	11	5100	390	0.23	18	420	< 1.5 U	0.21 J	51 J		< 0.19 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	9.2	5300	490	< 0.020 U	15	340	< 2.8 U	0.17 J	63 J		< 0.18 U
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	7.6	9900	380	< 0.011	11	760	< 0.26	< 0.04	78		< 0.14
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	7.2	11000	420	< 0.011	11	780	0.64	< 0.041	89		< 0.15
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	6.02			< 0.053 U	13.9		1.32	< 1.06 U			< 1.06 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	9.84			< 0.0518	12		0.518	< 1.04			< 1.04
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated	6.2	32000	470	0.0089 J	11	600	< 0.54 U	< 0.11 U	94 J		< 0.22 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated	24	2900	460	0.27	44	720	0.64 J	< 0.12 U	120 J		< 0.35 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated	5.4	5000	310	0.014 J	10		< 0.54 U	< 0.11 U	67 J		< 0.33 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated	6.7	3100	410	< 0.015 U	15	610	< 0.54 U	< 0.11 U	49 J		< 0.33 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated	14	2100	620	0.042	15	760	< 0.6 U	< 0.12 U	45 J		< 0.37 U
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated	7.6	5300	410	0.019 J	14	810	0.63 J	< 0.11 U	100 J		< 0.33 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated	6.5	4800	460	0.023 J	13	520	< 0.54 U	< 0.11 U	49 J		< 0.34 U
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated	9.3	6000	540	0.039	16	< 62 U	0.81 J	< 0.12 U	93 J		< 0.36 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated	10	5000	650	0.054	16	690	0.7 J	< 0.12 U	75 J		< 0.35 U
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated	8.7	13000	440	0.03 J	14	810	0.62 J	< 0.11 U	83 J		< 0.34 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated	10	2200	650	< 0.016 U	13	800	< 0.6 U	< 0.12 U	44 J		< 0.38 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated	9.7	6500	410	0.023 J	18	860	< 0.56 U	< 0.11 U	61 J		< 0.35 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated	10	11000	430	< 0.013 U	13	680	0.88 J	< 0.11 U	110 J		< 0.34 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated	12	8900	380	0.046	17	820	0.76 J	< 0.11 U	87 J		< 0.33 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated	69	2100	480	0.11	17	600	< 0.53 U	< 0.11 U	79 J		< 0.33 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated	5.8	11000	450	< 0.016 U	12	770	< 0.6 U	< 0.12 U	91 J		< 0.37 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated	5.8	10000	370	< 0.015 U	14	690	0.66 J	< 0.11 U	40 J		< 0.33 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated	5.8	9000	370	< 0.014 U	13	660	0.97 J	< 0.11 U	29 J		< 0.35 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated	7.7	5300	390	< 0.015 U	13	730	0.54 J	< 0.11 U	< 27 U		< 0.33 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated	10	5600	770	< 0.015 U	16	780	< 0.62 U	< 0.13 U	67 J		< 0.39 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated	17	2600	540	< 0.018 U	16	880	< 0.67 U	< 0.14 U	< 34 U		< 0.42 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated	9.7	2700	390	< 0.016 U	17	1100	< 0.61 U	< 0.12 U	65 J		< 0.38 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated	8.7	9200	410	0.033 J	29	700	1.3	< 0.12 U	100 J		< 0.35 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated	9.4	17000	550	< 0.015 U	15	750	1.1	< 0.12 U	110 J		< 0.36 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated	9.2	3100	430	< 0.015 U	15	690	< 0.57 U	< 0.12 U	63 J		< 0.35 U
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated	8.3	17000	410	0.16	12	640	0.6 J	< 0.11 U	29 J		< 0.35 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated	10	5000	720	0.029 J	18	750	< 0.54 U	< 0.11 U	56 J		< 0.34 U
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated	25	1900	1300	0.037 J	19	1000	< 0.65 U	< 0.13 U	62 J		< 0.4 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated	18	4000	460	0.027 J	22	890	< 0.62 U	< 0.13 U	59 J		< 0.38 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated	10	2700	570	< 0.015 U	21	1000	< 0.62 U	< 0.13 U	50 J		< 0.39 U
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated	11	29000	400	< 0.015 U	13	850	0.76 J	< 0.13 U	56 J		< 0.38 U
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated	12	7300	500	< 0.014 U	15	730	0.66 J	< 0.11 U	80 J		< 0.35 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated	6.3	10000	420	< 0.015 U	13	690	0.82 J	< 0.11 U	96 J		< 0.33 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated	11	11000	440	< 0.016 U	15	890	0.7 J	< 0.11 U	80 J		< 0.33 U
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated	8.2	3700	380	< 0.015 U	13	570	< 0.54 U	< 0.11 U	66 J		< 0.34 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated	6.5	5500	620	< 0.014 U	15	710	< 0.54 U	< 0.11 U	59 J		< 0.34 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated	8.9	3000	660	0.016 J	15	790	< 0.62 U	< 0.13 U	50 J		< 0.38 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated	6.5	6800	500	< 0.014 U	13	620	0.63 J	< 0.11 U	77 J		< 0.34 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated	10	2400	410	< 0.015 U	17	920	< 0.62 U	< 0.13 U	69 J		< 0.39 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated	22	2500	640	< 0.015 U	28	1100	< 0.64 U	< 0.13 U	47 J		< 0.4 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated	8.7	5300	780	0.017 J	13	760	< 0.55 U	< 0.11 U	54 J		< 0.34 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated	8.5	9400	400	< 0.016 U	14	860	< 0.61 U	< 0.12 U	72 J		< 0.38 U
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated	8.7	1900	320	0.016 J	15	790	< 0.62 U	< 0.13 U	50 J		< 0.38 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated	44 J-	2200 J	540	0.053	13 J	640	< 0.6 UJ	< 0.12 UJ	49 J		< 0.37 U
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated	11	2200	590	< 0.015 U	16	860	< 0.56 U	< 0.11 U	53 J		< 0.35 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated	25	1400	980	0.095	19	1100	< 0.62 U	< 0.13 U	43 J		< 0.39 U
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated	14	2300	420	0.022 J	15	730	< 0.55 U	< 0.11 U	63 J		< 0.34 U
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated	12	12000	410	0.16	15	730	0.9 J	< 0.11 U	160 J		< 0.34 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated	8	12000	330	< 0.014 U	12	650	1.1	< 0.11 U	83 J		< 0.34 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated	6.8	9000	450	< 0.014 U	15	690	0.61 J	< 0.11 U	98 J		< 0.33 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated	4.9	17000	420	< 0.016 U	12	780	0.89 J	< 0.12 U	100 J		< 0.35 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated	9.7	3200	610	< 0.014 U	16	750	< 0.54 U	< 0.11 U	67 J		< 0.34 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated	6.6	7100	430	< 0.014 U	13	730	< 0.57 U	< 0.12 U	64 J		< 0.35 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated	10 J	4800	560	0.026 J	16	740	< 0.58 U	< 0.12 U	56 J		< 0.36 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated	9.3	7900	710	0.051	15	810	< 0.59 U	< 0.12 U	60 J		< 0.37 U
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated	7.9	2100	300	< 0.017 U	15	750	< 0.63 U	< 0.13 U	43 J		< 0.39 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated	13	2400	490	< 0.016 U	14	700	< 0.54 U	< 0.11 U	59 J		< 0.34 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated	7.1	8600	440	< 0.015 U	13	710	0.61 J	< 0.11 U	71 J		< 0.33 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated	5.2	10000	480	< 0.013 U	15	570	1 J	< 0.12 U	74 J		< 0.36 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated	5.4	3900 J	230	< 0.014 U	8.7	570	< 0.55 U	< 0.11 U	64 J		< 0.34 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated		24	80
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated		2.6 J	53
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		2.3 J	38
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		5.9	55
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		2.1 J	46
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated		1.4 J	41
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated		3.0 J	69
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated		2.1 J	50
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated		2.8 J	54
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated		2.1 J	43
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated		10	44
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated		9.6	43
Northern Athletic Field	SSHS-B37	12 SEP 00B37_8-10	12 Sep 00B37_8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 53 U	113	44.8
Northern Athletic Field	SSHS-B46	13 SEP 00B46_8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 51.8	11.1	41.5
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated		9.7	30
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated		17	60
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30_SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated		8.9	39
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated		10	49
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated		13	57
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated		11	47
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated		8.3	110
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated		12	60
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated		9.9	53
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated		12	57
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated		9.9	50
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated		14	51
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated		8	49
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated		12	58
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated		13	82
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated		9.1	120
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated		9.6	59
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated		9	46
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated		11	51
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated		13	63
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated		15	65
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated		15	73
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated		11	46
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated		11	49
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated		11	56
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated		9.1	47
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated		14	59
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated		17	120
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated		17	68
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated		16	90
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated		10	48
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated		11	51
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated		8.5	43
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated		11	57
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated		9.4	44
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated		11	60
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated		12	66
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated		8.9	87
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated		17	49
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated		20	120
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated		11	46
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated		12	77
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated		12	49
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated		11 J-	58 J
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated		14	53
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated		12	75
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated		11	58
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated		9	100
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated		9	52
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated		10	52
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated		8.9	38
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated		12	65
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated		10	44
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated		12	55
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated		12	63
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated		11	48
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated		11	54
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated		10	41
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated		9.5	50
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated		8.3	35

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated	4400	< 0.38 U	3.8	40	0.19 J	0.11 J	65000	6		4.5 J	14	11000
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated	5000	< 0.37 U	5.8	29	0.22 J	0.13 J	31000	6.8		4.7 J	16	13000
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated	6100	1.6	16	90	0.4 J	0.78	43000	49		8.4	210	55000
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated	6500	0.45 J	6	57	0.28 J	0.1 J	23000	11		6.1	24	16000
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated	5900	0.41 J	5.3	56	0.25 J	0.072 J	17000	10		5.5 J	18	14000
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated	8700	0.61 J	7.2	39 J	0.39 J	0.054 J	1300	12		6.7	19	18000
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated	5200	< 0.38 U	6.4	26	0.27 J	0.11 J	1700	6.9		5.1 J	14	14000
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated	5600	< 0.38 U	4.3	33	0.22 J	0.095 J	48000	8.3		5 J	21	13000
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated	11000	< 0.4 U	6	77	0.45 J	0.068 J	1300	14		6.7	26	18000
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated	6500	< 0.35 U	5.2	62	0.24 J	0.15 J	41000	11		6.2	33	19000
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated	6000	< 0.34 U	3.6	83	0.18 J	0.071 J	37000	15		4.7 J	21	15000
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated	4200	< 0.37 U	5.1	29	0.2 J	0.094 J	18000	5.5		5.1 J	15	11000
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated	5100	< 0.35 U	4.2	42	0.19 J	0.11 J	46000	8.8		4.4 J	18	11000
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated	4800	< 0.37 U	5.2	39	0.19 J	0.18 J	47000	7.7		4.7 J	29	14000
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated	4300	< 0.35 U	3.3	30	0.18 J	0.075 J	31000	5.9		4.1 J	13	10000
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated	5500	< 0.37 UJ	3.5	32 J	0.22 J	0.17 J	85000	7.3		4.8 J	19	12000
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated	5000	< 0.39 U	5	41	0.2 J	0.13 J	32000	6.8		4.8 J	13	12000
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated	7000	< 0.35 U	5.3	60	0.3 J	0.11 J	35000	9.7		6.2	26	16000
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated	8600	0.38 J	7.6	71	0.4 J	0.07 J	4600	12		7	18	18000
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated	7700	< 0.35 UJ	4.7	52	0.29 J	0.079 J	28000	10		6.4	28	17000
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated	7600	< 0.38 U	9.1	51	0.35 J	0.064 J	1200	9.6		6.1	20	17000
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated	7100	< 0.38 U	6.7	74	0.32 J	0.1 J	1500	10		6.4	23	17000
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated	5800	< 0.38 U	6.4	33	0.29 J	0.12 J	8300	7.7		5.6	18	15000
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated	4900	< 0.36 U	3.2	49	0.19 J	0.078 J	40000	6.6		4.2 J	14	11000
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated	5600	< 0.35 U	5.3	39	0.23 J	0.22 J	24000	8.3		5.3	16	14000
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated	4300	< 0.39 U	3	30	0.16 J	0.053 J	35000	5.4		3.8 J	13	10000
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated	3900	< 0.36 U	4.1	26	0.16 J	0.12 J	52000	5.2		4 J	16	9700
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated	4900	< 0.37 U	3.9	35	0.22 J	0.12 J	39000	10		4.5 J	15	11000
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated	5100	< 0.36 U	3.9	42	0.22 J	0.1 J	42000	7.8		5 J	16	12000
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated	6000	< 0.36 U	4.9	38	0.25 J	0.078 J	22000	8.7		5.3	16	13000
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated	5000	< 0.39 U	3.7	37	0.19 J	0.094 J	51000	6.5		4.2 J	17	12000
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated	4800	< 0.31 U	4.1	30	0.19 J	0.11 J	29000	6.4		4.3 J	13	11000
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated	5000	< 0.32 U	5.2	33	0.24 J	0.13 J	18000	9.2		5	16	12000
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated	4000	< 0.35 U	3.7	35	0.16 J	0.13 J	60000	5.4		3.8 J	11	9700
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	7500	< 0.36 U	6.5	79	0.33 J	0.13 J	3600	11		6.2	23	16000
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated	4900	< 0.35 U	3.9	36	0.18 J	0.22 J	31000	6.7		4.6 J	15	13000
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated	5100	< 0.36 U	4.5	37	0.25 J	0.11 J	7500	8.1		5 J	17	14000
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated	5300	< 0.34 U	4	57	0.22 J	0.13 J	42000	9.6		4.8 J	16	12000
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated	5700	< 0.35 U	4.7	43	0.23 J	0.13 J	38000	11		4.8 J	16	13000
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated	4600	< 0.34 U	4.2	37	0.19 J	0.1 J	29000	8.6		4.2 J	16	13000
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated	5500	< 0.28 U	5.5	26	0.25 J	0.11 J	8500	8		5.2	19	13000
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated	5200	< 0.3 U	4	47	0.19 J	0.098 J	36000	7.7		4.9	18	12000
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated	5100	< 0.34 U	5.5	37	0.21 J	0.11 J	12000	7.8		4.5 J	23	12000
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated	6300	< 0.38 U	6.8	40	0.28 J	0.18 J	38000	12		6.5	21	17000
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated	4900	< 0.29 U	4.7	32	0.21 J	0.12 J	29000	6.7		5	16	12000
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated	4100	< 0.35 U	4.2	42	0.15 J	0.11 J	58000	5.6		4 J	14	11000
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated	5000	< 0.32 U	4.9	56	0.2 J	0.12 J	46000	7.7		4.9	18	12000
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated	4800	< 0.33 UJ	4.6	37	0.19 J	0.15 J	39000 J	7		5.1	13	13000 J
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated	3600	< 0.35 UJ	3.3	22	0.12 J	0.11 J	45000	5.4		3.3 J	11	8900
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated	5200	< 0.35 U	4.9	33	0.19 J	0.12 J	53000	7.5		4.8 J	16	13000
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated	5800	< 0.36 U	4.8	34	0.26 J	0.31 J	24000 J	9		5.2 J	19	14000
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated	5400	< 0.37 U	4.3	45	0.2 J	0.13 J	58000	7.7		5.3 J	13	13000
Northern Athletic Field	SSHS-B3522A	011521 08:45_SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated	4700	< 0.28 U	4.2	40	0.18 J	0.12 J	46000	7.2		4.4	17	11000
Northern Athletic Field	SSHS-B3523A	011521 08:45_SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated	4700	< 0.33 U	4.3	26	0.19 J	0.12 J	24000	7.1		4.7 J	18	12000
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated	4200	< 0.34 U	4.3	31	0.15 J	0.15 J	51000	5.9		3.9 J	18	11000
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated	5600	< 0.35 U	4.4	34	0.21 J	0.11 J	12000	7.4		5.5	17	14000
Northern Athletic Field	SSHS-B3636	012721 08:30_SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated	5200	< 0.33 U	5	36	0.19 J	0.14 J	40000	6.9		4.7 J	23	13000
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated	6300	< 0.24 U	4.2	38	0.23 J	0.085 J	14000	9.1		5.3	21	15000
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated	4600	< 0.33 U	3.9	32	0.16 J	0.16 J	39000	6.3		4.6 J	15	11000
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	3800	< 0.37 U	2.5	32	0.18 J	0.039 J	13000	5.5		4.3 J	8.9	8700
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	3100	< 0.37 U	2.6	27	0.18 J	0.051 J	13000	5.6		3.7 J	7.6	7600
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	5500	0.66 J	6.9	41	0.22 J	0.20 J	48000	7.6		4.9	19	13000
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	6200	0.43 J	5.4	43	0.24 J	0.16 J	18000	9.2		5.4	23	14000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	6000	< 0.37 U	6.8	33 J	0.27 J	0.069 J	20000	8		5 J	17	14000
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	5400	< 0.35 UJ	6.4	36	0.22 J	0.17 J	38000	10		5.2	17	13000 J
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	7800	< 0.31 U	5.8	63	0.32 J	< 0.033 U	5100	10		5.9	23	17000
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated	5300	< 0.33 U	5.2	25	0.24 J	0.078 J	18000	6.5		4.9	15	12000
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated	4800	< 0.34 U	6.7	26	0.26 J	0.12 J	30000	6.2		4.5	15	12000
Northern Athletic Field	B202	110421 09:45_SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated	4700	< 0.28 U	4	31	0.17 J	0.11 J	37000	6.4		4.8	17	11000
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated	4400	< 0.31 U	4.2	28	0.18 J	0.11 J	21000	5.9		4.6	16	12000
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated	5400	< 0.37 U	4.8	37	0.22 J	0.099 J	31000	6.6		5.5	18	13000
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated	4000	< 0.31 U	3.7	26	0.15 J	0.092 J	42000	5.3		4.1	15	9800
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated	4600	0.45 J	4.7	61	0.20 J	0.084 J	37000	6.2		4.6	16	11000
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated	5200	< 0.39 U	5.9	29	0.21 J	0.11 J	47000	8.1		5.7	23	14000

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated	9.3	4400	650	< 0.016 U	10	710	0.8 J	< 0.12 U	80 J		< 0.36 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated	6.4	5800 J	380	< 0.016 U	12	570	< 0.57 UJ	< 0.12 U	58 J		< 0.35 U
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated	79	4100	660	0.098	53	680	1.5	< 0.12 U	94 J		< 0.37 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated	8.7	6000	520	0.023 J	16	870	0.63 J	< 0.11 U	74 J		< 0.35 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated	7.9	6000	500	< 0.015 U	15	720	< 0.58 U	< 0.12 U	74 J		< 0.36 U
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated	14	2300	360	< 0.016 U	16	640	< 0.6 U	< 0.12 U	44 J		< 0.37 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated	7.2	2100	260	< 0.016 U	13	790	< 0.58 U	< 0.12 U	39 J		< 0.36 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated	5.6	9600	450	0.016 J	13	680	0.94 J	< 0.12 U	78 J		< 0.36 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated	33	2500	400	< 0.016 U	15	770	< 0.61 U	< 0.13 U	52 J		< 0.38 U
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated	11	15000	740	< 0.014 U	19	590	0.69 J	< 0.11 U	72 J		< 0.33 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated	5.5	10000	620	< 0.016 U	13	710	0.62 J	< 0.11 U	100 J		< 0.32 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated	6.1	3100	260	< 0.017 U	11	460 J	< 0.56 U	< 0.11 U	41 J		< 0.35 U
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated	11	15000	470	< 0.015 U	12	670	< 0.54 U	< 0.11 U	94 J		< 0.33 U
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated	15	7200	390	0.037	20	580	0.88 J	< 0.11 U	68 J		< 0.35 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated	4.2	2600	310	< 0.015 U	10	550	< 0.53 U	< 0.11 U	70 J		< 0.33 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated	5	4900	370	< 0.016 U	13	670	1.4	< 0.12 U	88 J		< 0.35 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated	5.8	5100	420	< 0.015 U	11	600	< 0.6 U	< 0.12 U	66 J		< 0.37 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated	12	7300	560	< 0.015 U	15	790	0.67 J	< 0.11 U	82 J		< 0.33 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated	11	3000	620	< 0.015 U	17	1000	< 0.56 U	< 0.11 U	50 J		< 0.35 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated	7.5	7300	540	< 0.015 U	17	820	< 0.53 UJ	< 0.11 U	27 J		< 0.33 U
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated	15	2000	350	< 0.015 U	15	620	< 0.57 U	< 0.12 U	40 J		< 0.36 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated	23	2500	590	< 0.015 U	15	740	< 0.58 U	< 0.12 U	46 J		< 0.36 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated	34	3000	390	< 0.013 U	14	770	< 0.58 U	< 0.12 U	< 29 U		< 0.36 U
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated	7.7	17000	350	< 0.015 U	9.7	540	< 0.55 U	< 0.11 U	98 J		< 0.34 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated	6.8	4800	350	< 0.015 U	12	680	0.68 J	< 0.11 U	68 J		< 0.33 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated	4.1	6200	290	< 0.017 U	9.4	500 J	0.79 J	< 0.12 U	62 J		< 0.37 U
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated	4.3	10000	330	< 0.014 U	9.3	510 J	0.8 J	< 0.11 U	76 J		< 0.34 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated	6.7	5800	460	< 0.014 U	11	780	< 0.56 U	< 0.11 U	79 J		< 0.35 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated	7.4	13000	430	< 0.014 U	12	640	0.67 J	< 0.11 U	93 J		< 0.34 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated	8.2	4900	390	0.05	13	890	0.73 J	< 0.11 U	79 J		< 0.34 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated	5.1	13000	470	< 0.016 U	11	670	0.78 J	< 0.12 U	82 J		< 0.37 U
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated	5.6	5700	330	< 0.023 U	11	580	< 0.47 U	< 0.097 U	70 J		< 0.3 U
Northern Athletic Field	SSHS-B3245	122119 10:30 SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated	7.1	5800	370	< 0.022 U	12	660	< 0.48 U	< 0.098 U	95 J		< 0.3 U
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated	6.1	22000	390	< 0.023 U	8.9	650	1.1	< 0.11 U	92 J		< 0.33 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	11	2800	570	0.032 J	15	720	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated	9.3	6400	420	< 0.024 U	12	480 J	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated	6.7	2800	340	< 0.023 U	12	620	< 0.55 U	< 0.11 U	< 64 U		< 0.34 U
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated	6.2	4600	350	0.031 J	13	630	< 0.51 U	< 0.1 U	75 J		< 0.32 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated	6.5	4800	410	< 0.021 U	13	680	0.87 J	< 0.11 U	73 J		< 0.33 U
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated	8.6	6400	480	0.029 J	11	560	< 0.51 U	< 0.11 U	62 J		< 0.32 U
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated	8.8	3000	350	0.026 J	14	530	< 0.43 U	< 0.088 U	< 51 U		< 0.27 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated	7.1	13000	310	< 0.021 U	12	580	< 0.46 U	< 0.094 U	89 J		< 0.29 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated	26	2500	390	< 0.025 U	11	620	< 0.51 U	< 0.1 U	< 60 U		< 0.32 U
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated	20	8800	440	< 0.023 U	16	750	0.57 J	< 0.12 U	94 J		< 0.36 U
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated	6.8	4500	320	< 0.024 U	13	600	0.6 J	< 0.09 U	55 J		< 0.27 U
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated	12	19000	340	< 0.021 U	9.9	500 J	0.83 J	< 0.11 U	80 J		< 0.33 U
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated	16	9800	480	< 0.022 U	12	520	0.99	< 0.099 U	60 J		< 0.3 U
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated	6.9	5500	500 J	< 0.022 U	12	580	0.68 J	< 0.1 U	< 59 U		< 0.32 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated	5.3	5300 J	290	< 0.023 U	7.8	370 J	0.61 J	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated	8.8	18000	370	< 0.022 U	12	610	0.9 J	< 0.11 U	83 J		< 0.33 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated	8	5100	380	< 0.023 U	13	630	< 0.55 UJ	< 0.11 U	< 64 UJ		< 0.34 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated	6.7	9300	410	< 0.024 U	13	580	0.93 J	< 0.11 U	69 J		< 0.35 U
Northern Athletic Field	SSHS-B3522A	011521 08:45 SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated	5.2	8300	390	< 0.021 U	11	610	0.56 J	< 0.087 U	68 J		< 0.26 U
Northern Athletic Field	SSHS-B3523A	011521 08:45 SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated	5.6	4900	380	< 0.021 U	12	610	< 0.51 U	< 0.1 U	< 59 U		< 0.32 U
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated	5.1	9700	430	< 0.018 U	10	600	< 0.52 U	< 0.11 U	72 J		< 0.32 U
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated	14	5600	560	< 0.019 U	13	800	< 0.52 U	< 0.11 U	< 61 U		< 0.33 U
Northern Athletic Field	SSHS-B3636	012721 08:30 SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated	4.5	8200	460	< 0.019 U	12	760	< 0.5 U	< 0.1 U	63 J		< 0.31 U
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated	6	4100	400	< 0.022 U	13	580	< 0.36 U	< 0.074 U	100 J		< 0.23 U
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated	4.6	8400	350	< 0.021 U	11	590	0.67 J	< 0.1 U	66 J		< 0.31 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	6.7	4300	230	< 0.021 U	9.0	400 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	4.1	4700	170	< 0.024 U	6.1	360 J	< 0.56 U	< 0.11 U	< 65 U		< 0.35 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	12	22000	420	< 0.020 U	12	670	< 0.50 U	< 0.10 U	95 J		0.50 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	7.0	6900	520	< 0.021 U	15	570	< 0.54 U	< 0.11 U	< 63 U		0.66 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	7.7 J	3000	280 J	< 0.015 UJ	13	840	< 0.56 UJ	< 0.12 U	< 66 UJ		< 0.35 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	9.2	6900 J-	340 J	< 0.018 U	13	730	0.88 J	< 0.11 U	77 J		< 0.33 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	9.4	3000	420	< 0.022 U	16	790	0.65 J	< 0.095 U	< 54 U		< 0.29 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated	8.3	2800	300	< 0.018 U	13	590	< 0.43 U	< 0.073 U	< 57 U		< 0.36 U
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated	6.0	13000	350	< 0.019 U	12	550	< 0.44 U	< 0.076 U	76 J		< 0.38 U
Northern Athletic Field	B202	110421 09:45 SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated	5.5	6700	300	< 0.02 U	11	580	< 0.36 U	< 0.063 U	55 J		< 0.31 U
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated	5.7	2700	330	< 0.018 U	11	470	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated	6.3	7200	370	< 0.018 U	12	570	< 0.48 U	< 0.084 U	< 65 U		< 0.41 U
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated	7.9	3800	280	0.057 J	10	430	0.45 J	< 0.070 U	59 J		0.35 J
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated	6.1	6100	310	0.063 J	11	610	< 0.44 U	< 0.076 U	61 J		< 0.37 U
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated	6.9	5900	360	0.055 J	14	730	< 0.51 U	< 0.089 U	< 69 U		< 0.44 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated		7.8	40
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated		9	46
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated		12	170
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated		12	55
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated		9.5	52
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated		16	51
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated		9.8	47
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated		9.2	45
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated		17	53
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated		11	62
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated		10	43
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated		7.3	39
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated		8.2	42
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated		7.8	83
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated		6.8	33
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated		8.9	39
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated		7.8	42
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated		11	51
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated		14	60
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated		12	52
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated		13	56
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated		11	64
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated		10	48
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated		6.8	50
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated		8.3	89
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated		5.6 J	80
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated		6.7	38
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated		8	46
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated		9.3	44
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated		8.9	44
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated		8.8	33
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated		7.7	35
Northern Athletic Field	SSHS-B3245	122119 10:30 SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated		8.4	45
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated		6.4	33
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated		12	86
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated		7.8	57
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated		11	41
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated		9	54
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated		9.7	47
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated		8.9	35
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated		10	46
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated		9	43
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated		9.2	48
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated		13	55
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated		8.2	41
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated		7.3	43
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated		7.8	43
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated		7.7	45
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated		6.1	30 J+
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated		8.6	46
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated		8.8	66
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated		8.4	40
Northern Athletic Field	SSHS-B3522A	011521 08:45 SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated		8.1	51
Northern Athletic Field	SSHS-B3523A	011521 08:45 SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated		9	41
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated		6.9	40
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated		9.6	54
Northern Athletic Field	SSHS-B3636	012721 08:30 SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated		9.2	50
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated		11	46
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated		7.7	87
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated		6.0	33
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated		5.3 J	20
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated		9.7	64
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated		10	47
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated		11 J	41
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated		9.3	43 J-
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated		12	59
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated		9.0	44
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated		8.7	41
Northern Athletic Field	B202	110421 09:45 SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated		8.2	51
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated		8.1	58
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated		11	50
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated		6.7	35
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated		7.4	38
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated		9.3	49

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated	4600	< 0.31 U	5.0	25	0.20 J	0.11 J	31000	6.2		4.9	18	11000
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated	4400	< 0.38 U	6.3	29	0.20 J	0.13 J	27000	6.7		5.2	17	14000
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated	4700	< 0.28 U	4.0	31	0.17 J	0.11 J	37000	6.4		4.8	17	11000
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	16000	< 0.46 UT	9.1	150	0.88	0.33 J	3600	21		14	31	30000
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	5400	< 0.42 U	12	110	0.34 J	0.41 J	6200	9.2		6.9	33	17000
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	8800	< 0.38 U	9.6	100	0.56	0.18 J	11000	12		9.6	48	24000
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated	5700	< 0.36 U	7.3	34	0.29 J	0.092 J	2300	8.2		6.3	18	15000
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated	5300	< 0.31 U	7.6	39	0.25 J	0.14 J	25000	7.6		5.9	18	14000
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	8800	< 0.36 U	5.8	73	0.43 J	0.13 J	1400	11		7.2	17	18000
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	7900	< 0.29 U	5.9	63	0.37 J	0.14 J	3000	9.6		6.3	19	16000
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	9000	0.40 J	6.2	63	0.40 J	0.12 J	1200	21		7.4	99	21000
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	9600	0.61 J	8.2	89	0.47 J	0.24 J	2300	50		10	500	33000
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	7300	< 0.42 U	7.0	88	0.37 J	0.25 J	4800	9.4		4.8	41	15000
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	5700	< 0.32 U	6.2	110	0.33 J	0.36 J	3700	9.0		3.9	37	13000
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated	7600	0.48 J	6.7	86	0.35 J	0.15 J	14000	13		5.9	47	17000
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated	7000	0.50 JT	6.3	33	0.30 J	0.090 J	840	8.3		5.6	18	15000
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated	7600	< 0.28 U	6.3	32	0.33 J	0.069 J	1300	8.1		5.4	17	14000
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	7000	< 0.21 U	6.7	33	0.29	0.065 J	750	9.7		5.5	33	16000
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	6800	< 0.24 U	9.6	48	0.35	0.13 J	9800	8.8		5.3	20	16000
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	7500	< 0.22 U	6.6	44	0.34	0.079 J	1400	9.9		6.4	26	16000
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	5000	< 0.18 U	4.3	35	0.22 J	0.078 J	27000	6.4		4.9	15	11000
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	5600	< 0.21 UT	5.6 T	45	0.26 JT	0.13 JT	930 T	7.8		5.2	17	14000
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	7600	< 0.20 U	11	40	0.42	0.14 J	1700	10		7.4	22	20000
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	1600	< 0.24 U	1.6	9.6 J	< 0.086 U	< 0.058 U	16000	2.4		1.5 J	7.1	4300
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	3800	< 0.17 U	3.7	27	0.16 J	0.076 J	26000	5.4		3.9	12	10000
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	3500	< 0.17 UT	3.5	17	0.15 J	0.076 J	23000 T	4.7		3.3	11	8900
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	6300	< 0.18 U	5.2	52	0.27	0.074 J	3700	8.6		5.6	18	14000
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	4600	< 0.23 U	4.5	34	0.24 J	< 0.056 U	2600	6.0		4.6	15	12000
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	6100	< 0.21 U	5.4	40	0.29	< 0.050 U	2100	7.5		5.8	17	14000
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	7400	0.30 J	5.2	59	0.34 J	< 0.065 U	1500	9.0		5.8	25	15000
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	3700	< 0.27 UT	3.4	30	0.15 J	0.087 J	33000 T	4.4		3.6 J	14	8900
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	4700	< 0.25 U	5.6	28	0.22 J	0.069 J	2300	6.2		5.0	15	13000
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	4800	< 0.21 U	4.0	34	0.20 J	0.094 J	29000	6.2		4.5	15	11000
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	5300	< 0.22 U	6.1	42	0.29	0.072 J	8500	6.9		4.8	15	13000
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	3800	< 0.22 U	3.6	32	0.17 J	< 0.053 U	9500	4.8		3.8	15	9100
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	5000	< 0.23 U	4.3	31	0.22 J	0.059 J	1600	6.6		4.2	16	12000
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	7800	< 0.23 U	6.4	98	0.38	0.11 J	2000	11		5.9	20	15000
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	5400	< 0.27 U	5.6	52	0.27 J	0.10 J	21000	7.2		5.0	26	14000
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	5400	< 0.27 U	4.3	42	0.25 J	0.16 J	30000	7.0		4.7	18	12000
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	4400	< 0.28 U	2.7	29	0.18 J	0.078 J	12000	5.5		3.6 J	16	10000
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	4700	< 0.25 U	3.3	51	0.20 J	0.065 J	18000	17		5.3	15	11000
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	4100	< 0.29 U	3.8	28	0.17 J	0.097 J	26000	5.9		4.0 J	15	10000
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	4400	< 0.26 U	3.9	34	0.17 J	< 0.064 U	18000	5.5		4.2 J	14	11000
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	3900	< 0.30 U	3.1	30	0.16 J	0.11 J	37000	4.9		3.5 J	18	8900
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	4800	< 0.27 U	4.3	33	0.21 J	0.081 J	37000	5.9		4.7	16	11000
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	3900	< 0.26 U	3.1	32	0.16 J	< 0.063 U	27000	5.0		3.7 J	12	9000
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	4300	< 0.25 U	3.2	25	0.17 J	0.082 J	27000	5.5		4.2	13	10000
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	4700	< 0.23 U	4.9	31	0.18 J	0.056 J	20000	5.8		4.5	15	11000
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	4200	< 0.22 U	2.9	36	0.16 J	0.069 J	35000	5.3		3.9	15	10000
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	5000	< 0.23 U	5.9	43	0.25 J	0.080 J	16000	7.2		4.9	21	12000
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	5400	< 0.25 U	6.0	43	0.27 J	0.074 J	7400	7.8		5.2	23	13000
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	10000	< 0.27 U	4.9	83	0.39	< 0.065 U	1500	10		6.9	9.5	15000
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	7000	0.33 J	7.3	60	0.31 J	0.090 J	7000	11		5.8	41	16000
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	8100	0.41 J	8.6	70	0.37 J	0.073 J	2100	11		6.9	31	19000
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	6700	< 0.25 U	6.1	65	0.31 J	0.065 J	4800	8.0		5.9	25	14000
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	5700	< 0.29 U	5.3	60	0.27 J	0.10 J	4700	7.3		4.8	61	13000
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	7600	< 0.30 U	2.3	98	0.33 J	< 0.074 U	950	7.4		4.4 J	8.6	9000
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	7400	0.44 J	8.1	73	0.34 J	0.25 J	1100	11		6.7	29	17000
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	7200	0.63 J	7.3	81	0.32 J	0.26 J	1100	11		6.0	31	16000
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	11000	0.64 J	7.5	77	0.44	0.15 J	3500	14		7.5	29	19000
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	6400	0.55 J	8.3	88	0.32 J	0.50	1200	13		5.8	45	17000
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	6500	0.34 J	6.5	29	0.27 J	< 0.077 U	650	7.4		5.6	16	13000
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	6700	0.43 J	6.2	36	0.28 J	< 0.065 U	750	7.3		5.5	18	14000
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	6600	0.33 J	5.5	49	0.26 J	0.074 J	1200	7.8		5.4	18	13000
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	5900	0.36 J	4.6	44	0.23 J	0.085 J	1400	6.8		6.6	13	13000
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	11000	< 0.32 U	5.5	53	0.38 J	< 0.077 U	750	11		7.7	12	16000
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	12000	< 0.33 U	5.6	53	0.39 J	< 0.080 U	740	12		7.4	15	17000
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	2400	2.0	17	44	< 0.17 U	0.11 J	820	29		2.6 J	220	45000
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	6900 B	< 0.29 U	7.3	59	0.29 J	0.078 J	4700	7.9		4.8	18	15000
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	7000	< 0.29 U	6.0	49	0.29 J	0.072 J	1200	7.8		6.1	16	15000
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	8700	< 0.30 U	5.7	41	0.33 J	< 0.072 U	590	9.1		6.4	13	16000
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	5400	< 0.26 U	6.3	45	0.22 J	< 0.063 U	840	5.3		4.0 J	13	13000
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	11000	< 0.27 U	6.5	37	0.42	< 0.066 U	770	12		7.7	15	19000
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	6900	< 0.33 U	6.6	53	0.25 J	< 0.080 U	980	8.9		5.7	21	31000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated	5.8	5400	290	< 0.021 U	12	730	< 0.41 U	< 0.070 U	< 54 U		< 0.35 U
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated	6.8	5600	330	< 0.019 U	13	610	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated	5.5	6700	300	< 0.020 U	11	580	< 0.36 U	< 0.063 U	55 J		< 0.31 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	25	4600	590	0.055 J	38	1800	< 0.61 U	< 0.10 U	< 81 U		< 0.52 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	65	1100	210	0.056 J	21	530 J	0.75 J	< 0.095 U	120 J		< 0.47 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	53	2500	390	0.16	27	680	< 0.49 U	< 0.085 U	82 J		< 0.42 U
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated	10	1800	330	< 0.021 U	16	610	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated	7.8	4400	350	< 0.019 U	16	620	< 0.41 U	< 0.071 U	56 J		0.35 J
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	13	2600	400	0.036 J	19	800	< 0.47 U	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	9.9	3200	440	0.024 J	17	700	< 0.38 U	< 0.065 U	< 51 U		< 0.32 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	33	2200	380	0.039 J	44	620	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	83	2400	490	0.051 J	270	830	< 0.49 U	< 0.084 U	230 J		< 0.41 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	47	1500	240	0.077 J	17	520 J	0.81 J	< 0.094 U	120 J		< 0.47 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	77	900	160	0.081 J	15	420 J	< 0.42 U	< 0.072 U	120 J		< 0.35 U
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated	55	3000	340	0.056 J	49	690	< 0.42 U	< 0.072 U	74 J		< 0.35 U
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated	7.2	2000	320 T	< 0.018 U	15	590	0.50 J	< 0.080 U	< 62 U		< 0.40 U
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated	9.7	2000	300	0.023 J	15	610	< 0.37 U	< 0.063 U	77 J		< 0.31 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	8.3	2100	240	< 0.022 U	14	650	0.36 J	< 0.071 U	77 J		< 0.19 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	12	6100	530	0.021 J	12	790	< 0.37 U	< 0.084 U	45 J		< 0.23 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	8.4	2300	360	< 0.024 U	15	610	< 0.34 U	< 0.076 U	100 J		< 0.21 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	6.7	18000	370	< 0.023 U	11	640	0.36 J	< 0.061 U	110 J		< 0.17 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	7.6	1800	390 T	0.023 J	12	490	< 0.31 UT	< 0.070 UT	< 35 UT		< 0.19 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	13	2000	430	< 0.023 U	20	1100	0.45 J	< 0.069 U	57 J		< 0.19 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	2.3	1300	120	< 0.020 U	3.6	210 J	0.42 J	< 0.082 U	< 40 U		< 0.22 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	4.5	3200	230	< 0.020 U	9.9	380	0.38 J	< 0.058 U	44 J		< 0.16 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	3.8	1800	210 T	< 0.020 U	8.0	340	< 0.26 U	< 0.058 U	56 J		< 0.16 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	8.2	2900	380	< 0.021 U	14	510	< 0.28 U	< 0.063 U	41 J		< 0.17 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	5.7	2200	390	0.020 J	12	450	< 0.35 U	< 0.079 U	< 39 U		< 0.21 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	7.2	2200	380	0.027 J	14	580	< 0.31 U	< 0.070 U	< 35 U		< 0.19 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	7.2	2500	280	0.018 J	14	830	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	4.2	3500 T	250 T	< 0.017 U	8.9	310 J	0.48 J	< 0.094 U	57 J		< 0.26 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	6.2	2200	320	< 0.023 U	12	400 J	< 0.38 U	< 0.085 U	< 42 U		< 0.23 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	5.0	3100	270	< 0.018 U	12	480	0.56 J	< 0.074 U	47 J		< 0.20 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	18	2300	490	< 0.025 U	13	490	0.44 J	< 0.076 U	52 J		< 0.21 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	5.7	4400	400	< 0.017 U	9.6	400	< 0.33 U	< 0.075 U	< 37 U		< 0.20 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	6.0	1900	330	0.036	11	440	< 0.34 U	< 0.077 U	43 J		< 0.21 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	25	2000	340	0.097	17	670	< 0.35 U	< 0.079 U	66 BJ		< 0.22 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	19	12000	490	0.055	15	470	< 0.41 U	< 0.093 U	55 J		< 0.25 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	9.6	4400	500	0.021 J	13	610	0.48 J	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	6.0	3000	280	< 0.020 U	9.7	410 J	0.49 J	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	6.9	4400	240	< 0.018 U	22	440	0.45 J	< 0.085 U	47 J		< 0.23 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	7.6	3500	300	0.015 J	10	450 J	0.65 J	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	5.3	3300	220	< 0.017 U	11	400 J	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	5.4	3600	440	< 0.019 U	8.9	490 J	0.70 J	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	6.6	13000	410	< 0.018 U	11	590	0.61 J	< 0.093 U	55 J		< 0.25 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	5.2	4000	260	< 0.020 U	9.2	460	0.47 J	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	4.7	4100	230	< 0.016 U	10	470	0.43 J	< 0.084 U	41 J		< 0.23 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	5.0	3700	260	< 0.017 U	11	430	< 0.35 U	< 0.078 U	39 J		< 0.21 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	6.3	3200	310	< 0.017 U	10	400	0.61 J	< 0.075 U	43 J		< 0.21 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	19	4800	310	0.033	13	470	0.35 J	< 0.079 U	39 J		< 0.22 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	15	2500	280	0.055	14	430	< 0.38 U	< 0.086 U	< 43 U		< 0.24 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	14	1500	840	0.27	13	550	0.44 J	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	25	2200	360	0.13	19	520	0.85 J	< 0.095 U	80 J		< 0.26 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	18	2400	430	< 0.026 U	22	680	< 0.45 U	< 0.10 U	67 J		< 0.28 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	14	3100	490	0.032 J	16	550	< 0.39 U	< 0.087 U	< 43 U		< 0.24 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	26	1800	370	0.036	21	420 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	10	1300	120	0.046	9.6	350 J	0.56 J	< 0.10 U	72 J		< 0.28 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	52	1900	470	0.032	20	620	0.52 J	< 0.12 U	< 58 U		< 0.32 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	56	1900	380	0.089	20	540	< 0.41 U	< 0.093 U	< 46 U		< 0.25 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	45	3400	320	0.031 J	19	710	0.54 J	< 0.11 U	73 J		< 0.30 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	99	1800	500	0.11	25	500	< 0.38 U	< 0.086 U	71 J		< 0.24 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	7.5	1800	290	0.028	13	580	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	9.6	1800	350	0.024 J	14	560	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	8.0	1900	440	0.029	14	550	< 0.40 U	< 0.090 U	< 45 U		< 0.25 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	6.7	2100	780	0.026 J	15	450 J	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	7.8	2400	330	< 0.022 U	15	720	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	10	2600	300	0.028 J	16	670	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	200	560 J	130	0.079	7.7	270 J	2.1	0.16 J	96 J		0.50 J
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	9.7	3800	470	0.021 J	13	670	0.60 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	9.2	2000	460	0.020 J	14	540	0.54 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	8.3	2100	290	0.024 J	13	550	0.74 J	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	7.8	1700	450	0.023 J	10	410 J	< 0.39 U	< 0.089 U	< 44 U		0.30 J
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	8.9	2700	230	0.026 J	17	550	1.0	< 0.094 U	< 46 U		< 0.26 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	11	1900	560	0.036 J	13	530 J	0.85 J	< 0.11 U	< 56 U		< 0.31 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated		8.2	40
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated		12	50
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated		8.2	51
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated		24	120
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated		13	59
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated		16	88
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated		11	57
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated		9.1	52
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated		14	64
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated		14	72
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated		14	82
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated		16	180
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated		11	64
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated		11	61
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated		11	93
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated		11	50
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated		11	46
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated		12	46
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated		13	48
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated		13	49
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated		8.5	35
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated		10	83
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated		14	60
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated		2.9 J	24
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated		7.0	30
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated		5.6	27
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated		11	51
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated		7.8	40
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated		9.6	53
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated		11	50
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated		5.4	32 T
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated		8.1	47
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated		7.0	34
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated		9.4	39
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated		6.0	40
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated		8.6	47
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated		12	56
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated		9.2	52
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated		8.4	47
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated		6.3	44
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated		6.6	39
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated		6.9	35
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated		6.7	37
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated		6.2	45
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated		8.0	47
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated		6.4	35
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated		6.8	77
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated		7.2	37
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated		6.4	33
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated		9.4	49
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated		9.1	49
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated		15	41
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated		12	60
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated		14	65
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated		11	49
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated		8.9	54
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated		9.8	31
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated		11	72
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated		11	74
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated		16	68
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated		12	87
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated		8.8	41
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated		9.0	44
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated		8.7	46
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated		7.6	39
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated		13	43
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated		14	47
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated		8.4	62
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated		11	57
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated		10	48
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated		12	41
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated		8.1	49
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated		14	48
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated		10	47

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	9400	1.0 JT	11	840	0.52 J	2.4	12000 T	26		9.6	96	22000
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	3400	< 0.28 U	4.2	33	0.17 J	< 0.068 U	640	6		2.6 J	11	7900
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	4300	0.29 J	5.4	38	0.17 J	0.099 J	21000	16		3.8 J	14	10000
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	5100	< 0.3 U	4.5	48	0.18 J	0.11 J	30000	7.4		4.7 J	22	7900
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	7600	< 0.35 U	8.4	59	0.35 J	0.10 J	1000	8.7		6.6	31	12000
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	6700	0.34 J	8.1	130	0.33 J	0.12 J	2100	9.0		4.8 J	22	14000
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	6900	0.97	8.7	120	0.36 J	0.28 J	15000	13		5.7	62	11000
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	7500	0.78 J	6.9	120	0.36 J	0.31 J	7500	15		6.7	85	13000
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	4800	< 0.30 U	3.7	30	0.19 J	< 0.072 U	1000	6.3		4.4 J	15	15000
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	5400	< 0.25 U	5.0	45	0.24 J	0.076 J	2300	6.9		4.9	19	13000
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	6300	< 0.26 U	4.9	30	0.27 J	0.062 J	530	7.2		5.0	15	13000
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	7000	< 0.32 U	4.8	34	0.30 J	0.10 J	600	7.6		5.0 J	15	15000
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	6000	< 0.32 UT	6.6 T	48 T	0.31 JT	0.13 JT	1100 T	7.6 T		5.2 T	18 T	15000
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	2600	< 0.31 U	3.0	17 J	0.17 J	0.16 J	88000	4.1		2.1 J	8.3	7100
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	7600	< 0.28 U	6.5	48	0.32 J	0.082 J	880	9.1		6.0	22	12000
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	8000	< 0.30 U	6.6 B	49	0.34 J	0.084 J	1000	9.1		6.1	21	15000
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	7000	< 0.28 U	6.4 B	54	0.30 J	0.091 J	900	8.1		6.5	22	16000
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	6300	< 0.30 U	6.1	49	0.29 J	0.075 J	1600	10		5.3	19	14000
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	6700	< 0.30 U	7.5	52	0.31 J	0.092 J	1200	32		5.6	20	11000
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	9000	< 0.32 U	6.8	59	0.39 J	< 0.079 U	800	10		7.0	21	14000
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	6800	< 0.31 U	6.1 B	37	0.28 J	< 0.074 U	670	7.5		5.8	20	14000
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	7800	< 0.32 U	6.1 B	51	0.38 J	0.10 J	2400	8.6		5.9	25	12000
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	8200	< 0.29 U	6.9	61	0.37 J	< 0.071 U	2700	10		7.6	18	19000 B
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	6900	< 0.27 U	12	56	0.46	0.16 J	1400	9.3		7.0	20	19000 B
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	7400	< 0.32 U	6.8	59	0.32 J	0.095 J	770	10		6.6	24	17000 B
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	7000	< 0.30 U	7.1 B	54	0.32 J	0.085 J	580	8.6		6.2	19	14000
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	9200	< 0.32 U	13 B	95	0.46	0.077 J	890	10		8.9	25	9300
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	8500	< 0.31 UT	7.9	70 T	0.39 J	0.099 J	1100 T	11 T		7.9	23 T	18000 B
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	7600	< 0.31 U	7.2 B	64	0.35 J	0.11 J	3200	13		7.0	23	14000
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	7400	< 0.31 U	6.7 B	57	0.34 J	0.11 J	1300	29		5.9	20	12000
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	5900	< 0.31 U	5.3 B	47	0.30 J	0.095 J	3400	7.7		5.3	22	11000
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	7100	< 0.26 U	5.9	55	0.31 J	0.095 J	1100	8.5		5.6	29	14000
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	4300	< 0.29 U	6.3	37	0.26 J	< 0.070 U	1200	5.3		3.9 J	17	11000 B
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	7000	< 0.31 U	5.7	53	0.25 J	< 0.075 U	590	8.8		5.6	16	16000
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	8600	< 0.31 U	6.3	71	0.37 J	0.12 J	2800	24		5.8	19	12000
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	6900	< 0.30 U	6.0	46	0.30 J	0.094 J	990	8.9		5.7	22	16000 B
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	7300	< 0.32 U	9.6	64	0.36 J	0.12 J	1100	8.9		6.0	21	17000 B
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	5900	< 0.31 U	4.3	29	0.22 J	0.11 J	77000	6.6		3.9 J	17	11000
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	7200	< 0.30 U	5.3	42	0.29 J	0.17 J	1600	8.7		5.7	28	15000
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	7400	< 0.35 U	7.3	91	0.31 J	5.9	1400	45		5.5 J	85	17000
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	6300	< 0.30 U	5.4	43	0.26 J	0.073 J	890	8.9		4.8 J	18	13000
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	5200	< 0.31 U	10	58	0.40	0.21 J	1200	7.8		6.8	19	18000
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	7000	< 0.33 U	6.0	68	0.30 J	< 0.080 U	610	8.5		6.2	16	14000
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	6800	< 0.32 U	3.7	36	0.27 J	0.097 J	660	7.6		4.4 J	19	12000
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	11000	< 0.29 U	6.8	69	0.57	0.17 J	910	11		5.9	23	39000
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	3300	< 0.46 U	3.7	650	< 0.16 U	0.32 J	210000	4.6		2.2 J	15	5100
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	8800	< 0.31 U	6.8	36	0.37 J	0.080 J	770	9.8		5.7	17	16000
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	7900	0.35 J	6.7	71	0.38	0.15 J	5600	10		5.3	21	16000
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	9400	< 0.29 U	6.1	52	0.37 J	0.079 J	640	10		6.1	19	17000
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	7600 B	< 0.33 U	5.3	37	0.34 J	0.086 J	740	8.1		5.0 J	13	14000
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	4900	< 0.27 U	4.7	30	0.23 J	0.10 J	29000	6.5		5.0	16	12000
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	8000	< 0.31 UT	6.2 T	47 T	0.36 JT	< 0.074 UT	990	9.2 T		6.3	14	16000
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	7400	0.37 J	5.4	35	0.32 J	0.071 J	580	8.5		5.8	15	15000
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	7700	0.58 J	5.5	82	0.36 J	< 0.081 U	1000	8.1		6.0	21	13000
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	8200	< 0.30 U	4.8	73	0.33 J	0.093 J	520	8.9		5.5	21	12000
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	6600	< 0.28 U	4.7	30	0.30 J	< 0.068 U	550	7.6		4.4 J	16	13000
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	6800	< 0.28 U	6.4	26	0.29 J	< 0.068 U	540	8.3		5.5	18	15000
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	4600	< 0.30 U	4.6	30	0.21 J	0.12 J	34000	6.2		4.7 J	24	12000
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	4300	< 0.27 UT	4.4	25 T	0.19 J	0.092 JT	34000	5.6 T		4.3 J	15	11000
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	5700	< 0.32 U	5.3	36	0.29 J	0.081 J	5500	7.3		5.1 J	18	14000
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	3800	< 0.31 U	3.5	30	0.17 J	0.099 J	25000	5.2		3.8 J	15	9700
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	7900	0.38 J	6.4	49	0.37 J	0.078 J	1100	9.8		7.0	18	17000
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	6900	0.42 J	6.5	46	0.34 J	0.079 J	2100	8.4		6.4	18	15000
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	6500	< 0.33 U	6.4	34	0.29 J	0.10 J	730	8.9		5.5	21	16000
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	4700 T	0.37 JT	5.3 T	33 T	0.23 JT	0.11 JT	16000	7.4 T		4.4 JT	18 T	11000 T
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	9500	< 0.32 U	8.3	35	0.44	< 0.077 U	2000	11		7.8	16	19000
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	5100	< 0.31 U	6.0	26	0.26 J	< 0.075 U	1200	6.6		4.4 J	15	12000 B
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	3900	< 0.33 U	4.0	31	0.17 J	< 0.080 U	690	5.7		4.1 J	12	10000 B
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	5300	< 0.30 U	4.9	45	0.24 J	0.082 J	800	6.7		4.3 J	16	13000 B
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	4000	< 0.28 U	3.9	34	0.16 J	0.087 J	29000	5.4		4.5 J	13	10000 B
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	4700	< 0.32 U	4.8	25	0.21 J	0.11 J	2100	6.4		4.6 J	14	13000 B
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	2900	0.27 J	2.7	32	0.13 J	< 0.062 U	800	3.7		1.8 J	10	5200
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	6500	< 0.26 U	7.1	47	0.33 J	< 0.064 U	1100	8.6		5.1	21	13000
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	7700	< 0.23 U	5.0	130	0.33	0.086 J	1200	8.9		4.5	13	11000

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	470	5300	430	3.8	56	990 T	1.2 JT	0.60 J	210 BJ		< 0.39 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	5.4	830	260	0.026 J	7.3	500	< 0.43 U	< 0.097 U	65 J		< 0.26 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	9.5	5600	320	0.051	12	570	< 0.39 U	< 0.089 U	51 J		< 0.24 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	5.5	6600	350	0.023 J	12	560	< 0.45 U	< 0.1 U	55 J		< 0.28 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	16	1800	570	< 0.020 U	17	840	< 0.53 U	< 0.12 U	< 59 U		< 0.32 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	9.6	1300	370 T	0.24	49	670	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	68	2400	390	3.2	18	700	0.66 J	< 0.098 U	93 J		< 0.27 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	160	2800	480	0.24	38	690	0.58 J	< 0.10 U	64 J		< 0.27 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	5.2	1700	360	< 0.017 U	11	460 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	10	2300	440	< 0.023 U	12	540	< 0.38 U	< 0.086 U	< 42 U		< 0.24 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	11	1600	340 T	< 0.016 U	11	600	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	6.5	1800	330	< 0.022 U	13	610	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	7.8 T	2000 T	880 WARN	< 0.020 UT	14	650 T	< 0.48 UT	< 0.11 UT	< 54 UT		< 0.30 UT
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	4.2	50000	490	< 0.023 U	5.8	390 J	1.1	< 0.11 U	120 J		< 0.29 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	8.3	1800	410	< 0.020 U	14	670	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	11	1800	360	0.030	14	720	< 0.46 U	< 0.10 U	56 J		< 0.28 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	9.0	1800	460	0.029	16	570	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	7.7	1900	450	< 0.014 U	13	650	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	17	1800	450	0.024 J	14	620	< 0.45 U	4.2	< 50 U		< 0.28 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	18	2000	580	< 0.020 U	15	780	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	7.0	1800	380	< 0.021 U	14	570	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	11	1700	410	< 0.018 U	13	600	< 0.48 U	< 0.11 U	75 J		< 0.30 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	14	2500	460 B	0.032	17	760	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	21	1700	1200 B	0.035	20	680	< 0.41 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	10	2000	500 B	0.029 J	18	750	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	10	1700	520	0.026 J	14	690	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	15	1900	730	0.032 J	19	930	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	12	2300 T	690 B	0.040 T	19	950 T	< 0.47 UT	< 0.11 UT	< 53 U		< 0.29 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	18	2700	540	0.079	17	770	< 0.48 U	0.75	< 53 U		< 0.29 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	19	1900	410	0.085	14	700	< 0.47 U	3.7	< 52 U		< 0.29 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	7.4	2300	390	< 0.024 U	13	730	< 0.48 U	< 0.11 U	88 J		< 0.29 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	6.4	2000	430	< 0.019 U	15	600	< 0.39 U	< 0.088 U	< 44 U		< 0.24 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	6.6	1200	360 B	0.019 J	10	610	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	6.1	2400	380	< 0.018 U	13	810	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	55	2000	450	0.075	14	640	< 0.48 U	1.3	< 53 U		< 0.29 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	7.2	2100	430 B	< 0.022 U	15	660	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	12	1800	530 B	0.025 J	15	700	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	13	44000	420	< 0.018 U	11	740	0.66 J	< 0.11 U	170 J		< 0.29 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	5.6	2200	800	< 0.022 U	14	840	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	52	1800	410	0.77	24	720	< 0.54 U	28	62 J		< 0.33 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	7.2	1800	350	< 0.021 U	13	770	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	19	1600	1400	< 0.017 U	22	1200	< 0.47 U	< 0.10 U	< 52 U		0.42 J
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	29	1700	720	0.015 J	12	910	< 0.51 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	24	1700	110 B	0.21	13	460 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	6.9	2400	740 B	< 0.024 U	17	450 J	0.60 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	150	5400	160 B	< 0.024 U	6.4	400 J	1.9	< 0.16 U	120 J		< 0.43 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	15	2200	280 B	0.021 J	15	720	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	31	2400	360 B	0.15	15	590	< 0.40 U	0.23 J	71 J		< 0.25 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	7.5	2100	410 B	0.030 J	15	640	< 0.45 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	8.2	1700	310	0.066	12	470 J	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	6.0	3300	270	< 0.019 U	13	570	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	9.6	2100 T	270	0.032	14	650 T	< 0.47 UT	< 0.11 UT	< 52 UT		< 0.29 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	7.3	1900	290	0.023 J	13	510	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	23	1600	290	0.059	45	390 J	0.68 J	< 0.12 U	< 57 U		< 0.31 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	11	1600	510	0.052	13	500	< 0.46 U	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	6.6	1700	200	0.024	12	430 J	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	7.4	1900	310	0.023 J	14	510	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	5.8	4700	370	< 0.021 U	12	490 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	6.0	6000 T	340	0.028	11	470 T	0.54 JT	< 0.093 UT	49 J		< 0.26 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	8.0	2300	390	< 0.023 U	13	580	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	5.2	2400	460	0.041	9.8	460 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	9.7	2200	370	< 0.020 U	16	720	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	10	2400	410	0.032 J	14	690	0.52 J	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	11	1700	410	0.028 J	13	590	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	12 T	2400 T	340 T	0.032	12 T	530 JT	< 0.51 UT	0.57 T	< 56 UT		< 0.31 UT
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	11	2600	410	0.034	17	850	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	6.5	1600	230 T	< 0.017 U	11	780	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	5.3	1100	250	< 0.021 U	8.1	520 J	0.50 J	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	5.6	1600	520	0.023 J	11	620	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	8.1	6600	270	0.054	10	480	0.45 J	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	7.1	1600	290	0.042	12	620	< 0.48 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	19	510	170	0.16	4.2	180 J	< 0.39 U	< 0.088 U	< 43 U		< 0.24 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	130	1500	330	0.12	12	490	< 0.40 U	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	160	1200	820	0.19	9.7	460	0.84	< 0.079 U	< 39 U		< 0.22 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated		24 T	870
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated		5.1	52
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated		7.2	35
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated		7.8	46
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated		13	70
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated		11	69
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated		14	110
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated		13	130
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated		7.1	38
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated		9.3	46
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated		10	40
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated		11	42
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated		11 T	46
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated		8.4	25
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated		13	47
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated		14	55
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated		10	55
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated		11	50
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated		11	58
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated		15	55
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated		10	49
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated		13	51
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated		12	49
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated		14	61
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated		12	65
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated		13	65
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated		15	65
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated		14 T	60 T
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated		13	62
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated		12	60
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated		11	61
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated		11	59
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated		8.2	36
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated		13	58
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated		14	75
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated		11	63
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated		13	62
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated		10	34
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated		15	75
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated		14	240
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated		9.9	51
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated		12	48
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated		12	44
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated		11	41
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated		15	49
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated		4.4 J	1600
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated		13	53
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated		13	61
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated		13	59
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated		11	39
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated		8.6	41
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated		12 T	44 T
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated		11	41
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated		11	42
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated		11	41
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated		11	39
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated		11	39
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated		8.5	41
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated		7.3 T	34
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated		9.4	49
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated		6.6	32
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated		13	48
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated		12	44
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated		13	45
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated		8.2 T	50 T
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated		15	44
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated		9.9	42
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated		9.2	30
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated		9.5	39
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated		7.1	35
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated		10	39
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated		5.8	22
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated		12	56
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated		12	51

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	3200	< 0.23 U	2.6	22	0.13 J	< 0.055 U	3500	4.5		2.6 J	8.3	7700
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	10000	0.59 J	11	160	0.47	< 0.068 U	2000	13		5.2	29	15000
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	3400	< 0.33 U	2.2	43	0.15 J	< 0.080 U	530 J	3.7		2.0 J	7.2	5400
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	4900	< 0.29 U	4.4	23	0.23 J	0.094 J	1800	6.3		4.5 J	15	12000
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	3800	< 0.23 U	3.8	21	0.17 J	0.076 J	19000	5.1		3.9	11	9600
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	3600	0.46 J	5.4	38	0.18 J	0.33 J	28000	12		3.9 J	44	9900
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	7200	< 0.26 U	4.4	31	0.31 J	0.092 J	630	6.9		5.6	17	15000
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	6500	< 0.32 U	4.6	40	0.26 J	0.11 J	8600	8.0		5.2	18	14000
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	6500	< 0.29 U	6.1	52	0.29 J	< 0.071 U	660	8.2		5.8	22	16000
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	7100	< 0.29 U	4.8	30	0.29 J	< 0.070 U	440 J	7.7		4.7 J	13	13000
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	6300	< 0.28 U	5.1	24	0.26 J	< 0.069 U	470	6.9		4.5 J	16	13000
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	4400	0.40 J	4.6	26	0.17 J	0.15 J	24000	5.4		4.4	19	9300
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	4600	< 0.27 U	4.0	26	0.27 J	0.098 J	22000	5.5		4.3 J	14	10000
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	4300	< 0.31 U	4.4	24	0.17 J	0.090 J	10000	5.5		3.7 J	13	9700
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	4800	0.30 J	4.6	30	0.17 J	0.092 J	28000	6.1		4.5	15	11000
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	5900	< 0.30 U	6.3	42	0.27 J	0.11 J	7800	8.2		5.1	20	13000
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	3300	0.31 J	4.0	30	0.13 J	0.19 J	14000	8.9		3.3 J	27	8200
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	9800	0.60 J	7.7	91	0.53	0.18 J	2700	15		8.4	21	20000
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	6000	< 0.29 U	5.3	49	0.28 J	< 0.070 U	1400	7.0		5.2	15	13000
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	4000	< 0.29 U	3.2	24	0.18 J	0.14 J	15000	5.0		3.7 J	12	10000
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	5400	< 0.31 U	4.9	49	0.26 J	< 0.076 U	920	6.5		4.7 J	20	13000
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	4800	< 0.28 U	4.5	33	0.22 J	< 0.067 U	740	5.8		4.4 J	14	11000
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	5500	< 0.31 U	6.5	32	0.29 J	0.078 J	1100	7.4		5.1 J	15	14000
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	4500	< 0.31 U	4.5	33	0.21 J	< 0.074 U	540	5.8		4.0 J	13	10000
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	6400	< 0.32 U	6.7	33	0.31 J	< 0.079 U	770	7.8		5.0 J	18	14000
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	5900	< 0.28 U	6.4	52	0.30 J	< 0.068 U	440 J	7.6		6.8	15	13000
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	1400	< 0.32 U	1.7	8.2 J	< 0.12 U	< 0.078 U	1200	1.9		1.1 J	3.9	3400
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	6900	0.69 J	5.8	46	0.31 J	< 0.075 U	4300	7.9		5.4	15	13000
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	5900	0.38 J	7.0	32	0.28 J	0.086 J	980	8.3		6.0	16	16000
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	6000	< 0.30 UT	5.7 T	60 T	0.29 JT	0.10 JT	1100 T	8.3 T		5.9 T	18 T	15000
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	1900	0.45 J	1.9	13 J	< 0.13 U	< 0.087 U	290 J	2.6		1.4 J	5.7	4400
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	4300	0.36 J	4.9	19 J	0.23 J	< 0.073 U	1000	6.0		4.1 J	12	12000
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	6900	0.49 J	6.6	63	0.33 J	0.31 J	4800	9.0		5.5	23	15000
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	6300	0.43 J	16	48	0.30 J	< 0.075 U	2000	9.1		6.6	27	16000
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	3600	< 0.33 U	2.3	15 J	0.16 J	< 0.080 U	660	5.0		3.4 J	9.7	7500
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	6900	0.50 J	5.8	60	0.31 J	0.12 J	3500	8.8		5.4	21	14000
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	2100	< 0.27 UT	1.5 T	9.7 JT	< 0.096 UT	< 0.065 UT	350 JT	3.0 T		1.8 JT	6.0 T	4100 B
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	4400	0.38 J	2.7	27	0.18 J	< 0.079 U	820	5.9		3.9 J	13	9000 B
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	5800	0.39 J	4.6	43	0.26 J	< 0.059 U	1800	7.0		4.4	15	12000 B
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	7600	0.46 J	5.5	54	0.32 J	< 0.075 U	4200	8.7		5.9	18	14000 B
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	5600	0.31 J	5.3	50	0.26 J	0.069 J	1400	7.2		5.4	19	13000 B
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	6500	0.44 J	5.9	44	0.28 J	< 0.068 U	2500	7.6		5.9	16	14000 B
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	2200	< 0.27 U	2.8	10 J	< 0.096 U	< 0.065 U	320 J	3.2		1.7 J	5.6	5800 B
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	3200	0.96 J	3.2	21	0.13 J	< 0.075 U	1100	4.1		2.5 J	10	8000 B
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	1700	< 0.30 U	2.5	17 J	< 0.11 U	< 0.072 U	340 J	2.6		1.9 J	6.1	5600 B
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	4800	0.28 J	6.6	62	0.25 J	0.12 J	710	6.2		6.3	16	17000 B
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	6200	< 0.30 U	5.9	39	0.28 J	0.10 J	6100	7.5		5.8	20	14000 B
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	5100	< 0.28 U	5.4	50	0.23 J	< 0.068 U	600	6.9		5.3	15	13000 B
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	5900	< 0.29 U	6.7	45	0.29 J	0.088 J	6500	7.6		5.3	19	16000 B
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	4400	< 0.27 U	5.4	39	0.19 J	0.074 J	7100	5.8		4.0 J	13	11000 B
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	5700	< 0.28 U	5.4	40	0.25 J	0.097 J	15000	7.3		4.8	18	13000 B
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	4700	0.30 J	4.8	27	0.20 J	0.12 J	26000	6.1		4.5 J	15	12000
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	5100	0.29 J	5.2	35	0.24 J	0.12 J	23000	7.0		4.9	20	13000
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	4800	< 0.21 U	4.8	35	0.23 J	0.085 J	15000	6.1		4.3	15	11000
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	6200	0.27 JT	5.5 T	39 T	0.29 JT	0.10 JT	3200 T	7.9 T		5.3 T	20 T	15000 B
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	7000	< 0.30 U	4.9	34	0.30 J	< 0.073 U	920	7.4		6.1	15	13000 B
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	6400	0.58 J	6.8	63	0.31 J	0.13 J	26000	8.7		5.5	29	18000 B
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	6000	< 0.29 U	5.5	38	0.28 J	0.073 J	890	7.6		5.7	17	14000 B
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	6200	< 0.30 U	7.3	87	0.31 J	0.23 J	52000	8.2		5.2	27	15000 B
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	5500	< 0.29 U	5.3	22	0.27 J	0.10 J	1200	7.6		4.5 J	19	14000
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	5800	< 0.30 U	4.9	38	0.27 J	< 0.073 U	640	6.9		4.7 J	16	12000
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	5300	< 0.31 U	4.7	58	0.21 J	0.24 J	23000	6.4		5.4	23	13000
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	7000	< 0.29 U	6.9	57	0.32 J	0.20 J	15000	9.1		6.6	48	15000
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	5100	< 0.24 U	8.6	67	0.27 J	0.42	24000	7.5		5.5	75	15000
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	4600	< 0.29 U	4.2	42	0.20 J	0.18 J	19000	6.2		4.1 J	23	10000
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	4700	< 0.26 U	3.4	32	0.18 J	0.11 J	58000	5.6		4.0 J	16	11000
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	4200	< 0.25 UT	3.3 T	26 T	0.17 JT	0.12 JT	34000 T	5.9 T		3.9 J	16 T	9800
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	4600	< 0.20 U	3.4	28	0.18 J	0.075 J	26000	5.6		4.2	14	11000
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	4900	< 0.24 U	3.5	23	0.18 J	0.086 J	34000	5.6		4.1	15	11000
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	4800	< 0.27 U	3.7	41	0.19 J	0.50	9800	6.9		4.2 J	27	12000
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	3400	< 0.24 U	3.1	27	0.14 J	0.13 J	13000	4.5		3.3 J	16	8400
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	7000	0.35 J	7.2	49	0.33 J	0.17 J	9000	9.4 B		5.7	21	16000 B
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	5600	0.37 JT	5.9	36	0.27 J	0.18 J	5700 T	7.2 B		5.4	20	14000 B
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	6200	< 0.28 U	6.1	46	0.29 J	0.093 J	2100	7.8		5.3	19	14000

DRAFT

													Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	4.1	1400	220	0.042	7.1	360 J	< 0.35 U	< 0.078 U	< 39 U		< 0.21 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	46	1600	920	0.11	11	590	0.75 J	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	12	550	160	0.13	4.0 J	200 J	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	5.3	1700	320	< 0.020 U	12	550	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	4.0	1800	260	< 0.020 U	9.4	400	< 0.35 U	< 0.079 U	45 J		< 0.21 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	150	3000	340	2.4	13	460 J	1.0	2.2	< 49 U		< 0.27 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	6.4	2500	260	0.018 J	14	520	0.42 J	< 0.090 U	46 J		< 0.25 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	18	3000	320	0.25	14	600	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	7.9	1800	290	0.018 J	14	640	< 0.44 U	< 0.10 U	98 J		< 0.27 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	6.2	1600	240	0.030	11	520	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	6.0	1500	250	0.023 J	11	490	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	29	6300	380	0.34	11	510	< 0.40 U	< 0.091 U	46 J		< 0.25 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	7.4	2700	350	0.089	11	480	0.47 J	< 0.093 U	< 46 U		< 0.26 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	5.0	1800	350	< 0.021 U	9.7	530	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	4.9	2700	260	< 0.020 U	11	530	0.47 J	< 0.093 U	50 J		< 0.25 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	15	2400	370	0.30	14	730	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	85	2800	270	1.9	9.2	380 J	< 0.41 U	2.0	< 45 U		0.32 J
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	33	2600	480	0.13	21	1200	< 0.53 U	< 0.12 U	< 59 U		< 0.33 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	10	1600	420	0.048	13	520	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	4.6	2000	250	0.023 J	9.2	390 J	< 0.43 U	< 0.098 U	53 J		0.73 J
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	5.3	1600	300	< 0.014 U	12	500 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	11	1300	310	0.033	12	430 J	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	7.0	1800	210	< 0.016 U	14	640	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	6.7	1300	410	< 0.024 U	11	470 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	7.6	1600	230	< 0.022 U	13	590	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	14	1400	460	0.025 J	14	620	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	2.4	640	72	0.065	3.0 J	140 J	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	14	2300	380	0.059	14	550	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	7.6	1700	320	< 0.021 U	15	680	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	19 T	2000 T	410	< 0.016 U	15 T	660 T	< 0.46 UT	< 0.10 UT	< 51 UT		< 0.28 UT
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	3.4	480 J	100	0.15	3.3 J	200 J	< 0.54 U	< 0.12 U	< 60 U		0.87 J
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	5.8	1600	240	< 0.015 U	11	550	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	33	2000	320	0.80	17	560	< 0.43 U	< 0.098 U	50 J		< 0.27 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	17	1900	380	0.42	18	520	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	4.8	1200	61	0.060	8.9	390 J	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	38	2300	330	0.47	15	540	0.49 J	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	2.5 T	570 T	28 T	0.042	4.0 T	220 JT	< 0.41 UT	< 0.092 UT	< 45 UT		0.38 JT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	9.9	1200	210	0.33	18	460 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	13	1600	270	0.13	13	390 J	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	15	2000	400	0.11	15	540	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	12	1800	410	0.047	14	450	< 0.37 U	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	15	2400	400	0.072	17	500	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	2.8	700	110	0.051	4.3	170 J	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	4.2	1200	180	0.057	6.9	290 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	2.9	450 J	220	0.035	3.7 J	230 J	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	8.6	1400	850	0.029 J	140	460	< 0.39 U	< 0.089 U	< 44 U		0.39 J
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	8.9	3000	510	< 0.021 U	270	550	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	7.1	1500	420	< 0.017 U	45	470	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	8.9	4200	420	< 0.024 U	38	540	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	6.4	4800	510	0.040	11	420 J	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	11	3500	340	0.096	12	660	< 0.43 U	< 0.098 U	57 J		< 0.27 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	6.0	3300	480	< 0.019 U	12	500	< 0.42 U	< 0.096 U	49 J		< 0.26 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	11	5700	320	0.13	12	660	< 0.35 U	< 0.079 U	58 J		< 0.22 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	14	3200	320	0.093	11	530	< 0.32 U	< 0.073 U	46 J		< 0.20 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	8.5	2300 T	380	0.069	14 T	590 T	< 0.40 UT	< 0.091 UT	< 45 UT		< 0.25 UT
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	8.6	1700	380	0.029 J	11	570	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	29	7900	380	0.061	14	650	< 0.44 U	< 0.10 U	67 J		< 0.27 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	11	1700	320	0.026	13	530	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	150	6200	460	0.24	19	650	0.73 J	< 0.10 U	72 J		< 0.29 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	15	1900	160	0.80	12	760	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	6.3	1600	320	< 0.021 U	12	540	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	6.8	3500	370	< 0.020 U	13	510 J	< 0.48 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	15	4200	340	0.080	15	1000	< 0.45 U	< 0.10 U	< 50 U		< 0.27 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	38	3200	510	0.026 J	21	480	0.42 J	< 0.082 U	41 J		< 0.22 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	8.4	3000	260	0.016 J	11	620	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	7.4	3300	260	0.017 J	10	530	0.57 J	< 0.090 U	53 J		< 0.25 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	4.8	3000	300 T	0.024 J	9.8	520 T	< 0.38 UT	< 0.087 UT	49 JT		< 0.24 UT
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	4.6	3600	240	0.030	10	480	< 0.31 U	< 0.070 U	38 J		< 0.19 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	4.6	4100	240	0.024 J	10	600	< 0.36 U	< 0.082 U	52 J		< 0.22 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	50	2900	200	3.7	11	490	< 0.41 U	0.88	160 J		< 0.25 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	18	3400	210	1.8	8.3	340 J	< 0.37 U	0.40	< 41 U		< 0.23 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	12	4800	430	0.26	15	950	< 0.46 U	< 0.10 U	85 J		< 0.28 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	16	3200	490	0.54 T	13	730	< 0.43 U	< 0.097 U	54 J		< 0.27 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	17	2000	310	0.059	14	670	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated		5.9	29
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated		15	58
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated		6.2	20
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated		8.1	41
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated		6.7	30
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated		8.2	140
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated		16	45
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated		11	50
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated		11	52
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated		11	36
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated		9.8	36
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated		8.2	38
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated		7.9	34
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated		8.3	35
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated		8.3	36
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated		10	50
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated		6.6	62
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated		15	81
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated		9.5	40
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated		6.6	93
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated		8.8	55
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated		7.9	38
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated		8.9	39
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated		7.9	33
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated		11	41
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated		12	46
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated		3.4 J	11
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated		11	42
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated		13	44
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated		12 T	55 T
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated		4.4 J	14
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated		8.6	32
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated		12	170
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated		11	53
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated		6.5	26
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated		12	88
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated		4.9 T	15 T
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated		8.4	43
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated		9.1	40
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated		11	44
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated		9.0	41
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated		11	41
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated		4.8	14
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated		5.8	26
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated		4.9	26
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated		9.0	47
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated		11	61
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated		9.4	40
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated		9.7	52
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated		7.7	37
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated		10	42
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated		7.6	44
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated		10	60
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated		8.8	37
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated		11 T	46 T
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated		11	37
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated		12	55
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated		11	41
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated		11	78
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated		11	55
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated		9.0	36
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated		7.8	110
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated		12	98
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated		9.0	150
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated		7.6	73
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated		7.3	34
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated		7.1 T	38
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated		7.4	39
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated		8.0	33
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated		6.2	210
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated		5.2	54
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated		13	63
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated		9.6	69 T
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated		10	50

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	5500	< 0.29 U	5.2	35	0.21 J	0.14 J	27000	6.8		4.9	23	13000
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	7000	0.52 J	6.3	73	0.31 J	0.19 J	1200	8.5		5.1	26	15000
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	5900	< 0.27 U	4.6	39	0.24 J	0.091 J	7200	7.5		5.4	15	13000
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	3600	< 0.29 U	3.8	22	0.16 J	0.10 J	37000	4.8		3.7 J	13	9300
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	3400	< 0.27 U	3.0	21	0.14 J	0.16 J	89000	4.3		3.2 J	13	8400
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	4200	< 0.25 U	4.8	24	0.19 J	0.089 J	28000	5.4		3.8 J	14	11000
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	4300 T	< 0.27 UT	4.0	38 T	0.17 J	0.11 J	32000 T	5.3 T		4.0 J	16 T	11000
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	6700	< 0.28 U	6.3	46	0.32 J	0.11 J	1700	8.4		5.7	22	15000
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	4100	0.31 J	4.8	32	0.18 J	0.11 J	750	5.6		4.1	12	10000
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	3900	0.30 J	4.5	36	0.21 J	0.14 J	1800	6.0		3.9 J	17	12000
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	4600	< 0.31 U	4.1	36	0.22 J	0.10 J	800	6.0		4.2 J	13	11000
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	5700	< 0.27 U	6.0	38	0.25 J	0.17 J	8900	7.3		5.4	17	14000
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	5600	< 0.27 U	5.0	37	0.23 J	0.12 J	26000	7.1		5.4	13	13000
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	3800	< 0.27 U	3.4	23	0.17 J	0.14 J	31000	4.7		3.9 J	13	9200
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	5000	< 0.28 U	4.5	28	0.20 J	< 0.069 U	25000	6.2		4.5 J	16	12000
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	4000	< 0.27 U	4.2	36	0.17 J	0.099 J	59000	5.5		4.2 J	16	9900
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	4300	< 0.26 U	4.8	23	0.18 J	< 0.064 U	21000	5.5		4.2 J	15	11000
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	6700	< 0.30 U	9.4	98	0.37 J	0.18 J	13000	9.2		6.7	23	15000
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	5800	< 0.30 U	8.0	41	0.25 J	< 0.073 U	8900	7.7		5.2	18	14000
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	4100	< 0.27 U	4.3	25	0.17 J	< 0.065 U	21000	5.2		4.1 J	13	10000
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	6400	< 0.31 U	6.2	54	0.27 J	< 0.075 U	8100	8.5		5.4	24	15000
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	6900	< 0.29 UT	7.3 T	54 T	0.31 JT	< 0.071 UT	8800 T	9.4 T		6.7 T	24 T	16000
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	3900	< 0.27 U	3.2	26	0.15 J	< 0.066 U	28000	5.1		3.6 J	15	9400
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	5200	< 0.30 U	4.5	45	0.21 J	0.098 J	28000	7.4		4.8 J	23	12000
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	6800	< 0.29 U	5.5	43	0.29 J	< 0.070 U	4600	8.6		6.3	19	15000
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	5200	< 0.29 U	4.6	41	0.21 J	0.075 J	38000	6.9		4.9	19	12000
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	3900	< 0.28 U	5.2	30	0.17 J	< 0.068 U	38000	5.3		3.8 J	12	9800
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	5300	< 0.28 U	4.9	31	0.21 J	< 0.068 U	22000	6.8		4.5 J	19	13000
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	4700	< 0.26 U	3.8	28	0.16 J	0.066 J	31000	6.5		4.7	13	11000
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	4700	< 0.28 U	5.3	26	0.21 J	< 0.067 U	3800	5.9		4.2 J	15	12000
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	6000	< 0.31 U	5.4	45	0.26 J	< 0.074 U	1300	7.6		5.2	18	14000
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	4800	< 0.30 U	5.6	28	0.19 J	< 0.072 U	27000	6.1		4.5 J	16	12000
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	5200	< 0.29 U	6.4	26	0.23 J	< 0.069 U	13000	6.8		5.1	17	13000
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	5600	< 0.29 U	5.5	34	0.26 J	< 0.070 U	16000	9.3		4.7 J	18	13000
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	4900	< 0.33 U	5.6	25	0.23 J	< 0.081 U	1200	6.6		4.7 J	14	13000
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	5400	< 0.26 U	7.0	31	0.25 J	0.43	1100	11		4.8	35	13000
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	3100	< 0.31 U	3.3	26	0.13 J	< 0.075 U	1000	4.6		2.4 J	12	7400
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	3400	< 0.27 U	2.4	37	0.098 J	< 0.065 U	2100	6.6		2.7 J	11	9100
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	3200	< 0.26 U	3.0	25	0.13 J	< 0.063 U	3200	4.2		2.3 J	14	7200
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	7600	< 0.35 U	10	180	0.46	< 0.085 U	3700	12		6.1	43	15000
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	4900	< 0.29 U	4.6	27	0.25 J	< 0.071 U	1200	6.3		4.6 J	16	12000
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	5200	< 0.26 U	5.3	26	0.24 J	< 0.062 U	920	6.6		4.6	15	13000
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	5400	< 0.28 U	5.4	58	0.25 J	< 0.069 U	860	7.2		5.2	19	14000
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	4900	< 0.29 U	5.1	34	0.25 J	< 0.069 U	1500	6.7		4.8	17	13000
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	4600	< 0.28 U	5.9	38	0.22 J	0.59	2400	5.9		4.4 J	45	13000
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	6400	< 0.30 U	6.0	47	0.30 J	< 0.074 U	1100	7.8		6.0	20	15000
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	5900	< 0.31 U	6.3	40	0.30 J	< 0.075 U	3300	7.9		5.4	21	15000
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	7300	< 0.28 U	7.5	82	0.36 J	< 0.069 U	1300	9.1		7.8	18	17000
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	5400	< 0.25 U	4.8	34	0.24 J	< 0.061 U	2300	7.2		4.6	16	13000
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	8200	< 0.27 U	7.0	55	0.34 J	< 0.065 U	1300	9.4		6.2	17	17000
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	5900	< 0.28 U	4.9	34	0.26 J	< 0.068 U	860	7.5		5.0	20	14000
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	7400 T	< 0.30 UT	6.7	46 T	0.35 J	< 0.073 U	1900 T	9.0 T		6.8	18 T	16000 T
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	6500	< 0.30 U	5.7	46	0.30 J	< 0.072 U	1100	9.8		6.3	16	15000
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	8400	< 0.29 U	7.4	65	0.41	< 0.071 U	3400	11		6.6	34	18000
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	5400	< 0.30 U	5.4	26	0.25 J	< 0.072 U	750	6.8		5.1	15	13000
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	7100	< 0.29 U	7.4	54	0.34 J	< 0.069 U	1300	8.5		6.7	20	16000
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	9600	< 0.28 U	9.6	65	0.44	< 0.068 U	2100	11		9.4	20	23000
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	6400	< 0.29 U	5.2	35	0.29 J	< 0.071 U	690	7.8		5.6	18	15000 B
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	6600	< 0.33 U	7.1	44	0.31 J	< 0.079 U	9700	7.5		4.9 J	21	15000 B
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	5900	< 0.32 U	5.2	30	0.26 J	< 0.077 U	1900	7.2		4.7 J	16	13000 B
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	6000	< 0.33 U	6.0	28	0.28 J	< 0.080 U	3600	7.7		5.5	21	14000 B
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	8100	< 0.31 U	6.3	36	0.32 J	< 0.076 U	810	9.1		6.3	19	17000 B
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	7600	< 0.29 U	6.3	47	0.34 J	< 0.069 U	6600	8.7		6.8	19	15000 B
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	7400	< 0.28 U	6.1	40	0.31 J	< 0.068 U	5800	8.8		5.6	20	15000 B
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	6300	< 0.28 U	6.3	42	0.28 J	< 0.068 U	3500	7.5		5.1	17	14000 B
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	5300	< 0.27 U	5.4	33	0.25 J	< 0.064 U	27000	6.5		4.8	16	12000
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	7000	< 0.29 UT	6.5 T	44 T	0.31 JT	< 0.070 UT	8600 T	8.2 T		5.7	19 T	15000
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	3800	< 0.22 U	2.9	19	0.15 J	< 0.054 U	480	4.6		2.9 J	8.3	8000
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	7200	< 0.26 U	6.2	63	0.33 J	0.075 J	5300	9.5		6.0	27	15000
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	3600	< 0.23 U	3.0	16	0.14 J	< 0.055 U	310 J	4.0		2.9 J	6.6	7600
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	2100	< 0.18 U	2.2	11 J	0.091 J	< 0.043 U	380	2.7		1.6 J	5.4	5300
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	6000	< 0.28 U	6.6	42	0.29 J	0.094 J	2900	8.1		4.5 J	21	14000
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	9200	0.44 J	2.8	84	0.45	< 0.079 U	1000	11		10	23	24000
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	8300	0.49 J	1.2	74	0.38 J	< 0.081 U	1300	15		7.3	51	27000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	10	5100	410	0.024 J	12	550	< 0.43 U	< 0.098 U	100 J		< 0.28 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	21	1700	370	0.44	18	510 B	< 0.47 U	< 0.11 U	65 BJ		< 0.29 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	7.7	3900	300	0.028 J	13	720	< 0.41 U	< 0.091 U	51 J		< 0.25 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	5.6	3300	240	0.025 J	9.0	430 J	0.58 J	< 0.098 U	59 J		< 0.27 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	6.4	5600	360	0.027 J	8.3	470	0.78 J	< 0.093 U	87 J		< 0.25 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	19	2900	290	0.021 J	9.7	410 J	< 0.39 U	< 0.087 U	49 J		< 0.24 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	8.4	3200 T	300 T	0.025 J	9.9	470	< 0.41 U	< 0.094 U	50 J		< 0.26 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411037	Not Excavated	14	2100	390	0.053	15	740	< 0.43 U	< 0.097 U	< 48 U		< 0.27 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	5.2	1300	330	< 0.012 U	11	400	< 0.35 U	< 0.080 U	< 39 U		< 0.22 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	18	1300	250	0.063	12	350 J	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	5.7	1500	280	< 0.017 U	11	500 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	10	3900	570	0.030 J	13	630	0.45 BJ	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	5.7	3300	320	< 0.021 U	13	650	0.40 BJ	< 0.091 U	56 J		< 0.25 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	5.3	3500	300	< 0.019 U	9.5	410 J	0.70 BJ	< 0.091 U	55 J		< 0.25 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	6.9	4400	310	< 0.020 U	11	530	< 0.43 U	< 0.097 U	51 J		< 0.27 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	13	14000	300	0.17	9.7	590	0.91	< 0.094 U	67 J		< 0.26 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	6.6	2500	250	< 0.022 U	11	470	< 0.40 U	< 0.090 U	46 J		< 0.25 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	38	3600	410	0.069	17	620	0.65 J	< 0.10 U	80 J		< 0.28 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	33	2700	330	0.028 J	14	600	< 0.46 U	< 0.10 U	56 J		< 0.28 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	5.4	2900	270	0.023 J	10	520	0.58 J	< 0.092 U	51 J		< 0.25 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	29	2800	340	0.29	17	650	< 0.47 U	< 0.11 U	< 53 U		< 0.29 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	14 T	3400 T	370 T	0.72	17 T	790 T	< 0.45 UT	< 0.10 U	50 J		< 0.28 UT
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	5.6	3800	320	0.029	9.7	430 J	0.46 J	< 0.094 U	46 J		< 0.26 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	24	10000	370	0.61	12	630	0.58 J	0.21 J	59 J		< 0.28 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	12	3300	440	0.029	15	750	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	17	12000	290	0.12	12	720	0.59 J	< 0.099 U	72 J		< 0.27 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	6.0	4200	280	< 0.020 U	9.7	510	0.64 J	< 0.096 U	51 J		< 0.26 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	6.8	3500	370	< 0.017 U	12	520	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	4.8	3100	330	< 0.020 U	11	410 J	0.59 J	< 0.091 U	47 J		< 0.25 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	7.2	2900	340	< 0.016 U	11	550	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	8.3	1900	370	0.025 J	12	660	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	6.9	3200	290	0.017 J	11	500	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	7.6	3600	320	< 0.015 U	13	670	< 0.44 U	< 0.098 U	54 J		< 0.27 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	7.3	2600	400	< 0.020 U	12	620	< 0.44 U	< 0.099 U	< 49 U		< 0.27 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	6.5	1500	300	< 0.024 U	11	650	< 0.51 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	15	1700	250	0.071	13	520	0.51 J	< 0.090 U	< 44 U		< 0.25 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	13	1100	160	0.034	8.3	360 J	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	9.2	2100	130	0.029 J	9.0	680	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	14	1600	180	0.072	7.0	340 J	0.40 J	< 0.090 U	< 44 U		< 0.24 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	470	1200	490	1.5	13	530 J	1.0 J	< 0.12 U	90 J		< 0.33 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	6.6	1700	440	< 0.017 U	12	510	< 0.45 U	< 0.10 U	< 50 U		< 0.27 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	7.3	1600	270	< 0.018 U	11	540	< 0.39 U	< 0.088 U	< 44 U		< 0.24 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	8.5	1500	410	< 0.019 U	12	580	< 0.43 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	8.1	1900	490	< 0.020 U	11	580	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	9.4	2100	460	0.061	12	460	< 0.42 U	< 0.094 U	< 46 U		0.27 J
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	8.2	1800	560	< 0.019 U	14	670	0.48 J	< 0.10 U	< 51 U		< 0.29 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	12	2400	470	< 0.019 U	13	590	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	22	1900	510	< 0.020 U	17	760	< 0.43 U	< 0.098 U	< 48 U		0.31 J
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	6.8	2400	330	< 0.021 U	12	500	< 0.38 U	< 0.086 U	43 J		< 0.24 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	11	2200	410	0.024 J	16	650	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	5.7	1900	320	< 0.019 U	13	530	< 0.43 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	13	2200	470 T	< 0.021 UT	15	640 T	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	28	2000	570	< 0.019 U	12	580	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	35	2500	380	0.14	18	710	< 0.44 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	7.3	1600	270	< 0.019 U	12	600	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	10	1800	500	< 0.019 U	14	730	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	14	3000	570	< 0.018 U	20	980	< 0.43 U	< 0.097 U	< 48 U		0.27 J
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	8.1	1800	380	< 0.020 U	14	580	< 0.45 U	< 0.10 U	< 49 U		< 0.27 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	7.8	2700	280	< 0.020 U	14	750	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	8.1	1700	320	< 0.020 U	11	650	< 0.49 U	< 0.11 U	< 54 U		< 0.30 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	7.7	2900	410	< 0.019 U	14	600	< 0.50 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	8.3	2000	480	< 0.020 U	14	740	< 0.48 U	< 0.11 U	< 53 U		< 0.30 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	20	4800	430	0.10	14	730	< 0.44 U	< 0.098 U	< 48 U		< 0.27 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	15	2300	330	0.025 J	15	720	< 0.43 U	< 0.097 U	< 48 U		< 0.26 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	12	2400	420	< 0.019 U	13	640	< 0.42 U	< 0.096 U	< 47 U		0.26 J
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	8.0	15000	350	< 0.015 U	12	650	< 0.40 U	< 0.091 U	49 J		< 0.25 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	30	2800 T	340	0.065	14	560 T	0.49 JT	< 0.099 UT	< 49 UT		< 0.27 UT
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	4.9	910	220	0.012 J	6.5	330 J	< 0.34 U	< 0.077 U	< 38 U		0.24 J
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	86	2500	380	0.28	17	580	< 0.39 U	< 0.088 U	48 J		< 0.24 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	5.5	800	250	0.020 J	5.5	250 J	< 0.35 U	< 0.078 U	< 38 U		< 0.21 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	2.4	600	120	< 0.019 U	3.9	190 J	< 0.27 U	< 0.062 U	< 30 U		< 0.17 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	110	1900	330	0.12	13	490	< 0.42 U	< 0.096 U	< 47 U		0.29 J
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	16	2500	780	0.036 J	21	460 J	< 0.50 U	< 0.11 U	< 55 U		< 0.31 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	32	2100	520	0.029 J	30	330 J	< 0.51 U	< 0.12 U	< 57 U		< 0.31 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated		8.5	45
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated		11	80
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated		10	50
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated		6.6	33
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated		6.3	28
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated		7.0	32
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated		6.7	40 T
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated		11	53
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated		6.4	40
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated		9.3	56
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated		7.7	56
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated		9.6	52
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated		8.6	39
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated		4.7	40
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated		8.3	38
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated		7.3	45
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated		6.8	34
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated		14	76
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated		11	48
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated		7.1	33
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated		11	57
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated		12 T	52 T
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated		6.1	34
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated		8.5	66
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated		12	54
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated		9.1	57
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated		6.7	33
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated		10	52
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated		7.8	37
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated		8.9	39
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated		10	46
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated		7.9	38
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated		9.8	47
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated		9.7	43
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated		9.6	47
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated		11	200
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated		5.9	25
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated		11	26
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated		5.9	28
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated		24	74
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated		7.8	47
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated		8.9	54
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated		11	41
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated		8.4	41
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated		9.3	370
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated		11	46
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated		11	52
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated		12	62
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated		9.4	50
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated		13	52
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated		9.5	49
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated		13 T	69 T
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated		11	44
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated		14	69
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated		9.5	41
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated		12	66
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated		19	58
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated		11	47
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated		12	64
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated		10	39
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated		11	63
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated		13	46
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated		14	55
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated		13	61
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated		11	52
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated		9.8	40
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated		12 T	54 T
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated		6.9	25
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated		13	80
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated		6.8	21
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated		4.2	17
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated		11	75
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated		16	64
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated		18	71

DRAFT

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	10000	< 0.33 U	2.3	40	0.42 J	< 0.081 U	750	15		9.1	20	21000
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	8300	0.49 J	2.5	33	0.41	< 0.068 U	750	11		10	21	22000
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	4300	< 0.30 U	3.7	28	0.17 J	< 0.072 U	9500	5.8		3.3 J	15	9700
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	5600	< 0.31 U	5.3	43	0.24 J	< 0.075 U	1000	7.1		4.6 J	16	13000
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	3800	< 0.30 U	4.6	18 J	0.15 J	< 0.073 U	24000	5.0		3.6 J	13	9300
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	6600	< 0.28 U	5.8	49	0.29 J	< 0.067 U	6200	8.5		5.1	16	14000 B
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	6200	< 0.27 U	5.4	39	0.25 J	< 0.064 U	3400	7.9		4.8	17	14000 B
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	6800	< 0.27 UT	6.5 T	38 T	0.29 JT	< 0.065 UT	4700 T	8.4 T		5.6 T	17 T	14000 B
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	6300	< 0.31 U	5.7	38	0.26 J	< 0.075 U	2800	8.5		4.9 J	19	13000 B
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	6500	< 0.33 U	6.3	46	0.30 J	0.093 J	3600	8.4		5.3 J	16	14000 B
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	5900	< 0.30 U	4.9	36	0.24 J	< 0.073 U	12000	7.2		4.8 J	17	13000 B
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	4500	< 0.28 U	3.5	26	0.16 J	< 0.067 U	20000	5.7		4.1 J	14	10000 B
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	7100	0.32 J	5.8	46	0.28 J	< 0.071 U	9300	8.7		5.8	18	15000
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	4400	0.31 J	4.2	31	0.18 J	0.059 J	35000	5.5		4.1	16	10000
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	6800	< 0.29 U	11	59	0.33 J	0.080 J	1300	8.7		6.8	21	17000
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	4400	< 0.28 U	4.3	26	0.15 J	0.075 J	35000	6.1		4.6	16	12000
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	5500	< 0.26 U	4.5	43	0.21 J	0.12 J	29000	7.4		5.5	21	14000
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	5800	< 0.32 U	5.9	42	0.28 J	0.070 J	8700	7.9		6.1	24	15000
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	4900	< 0.30 U	4.1	32	0.12 J	0.047 J	48000	6.2		4.7	16	12000
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	5100	< 0.30 U	4.5	34	0.18 J	0.073 J	31000	6.8		5.3	15	13000
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	7100	< 0.30 U	6.9	48	0.24 J	0.080 J	35000	9.9		7.1	27	17000
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	6500	< 0.28 U	4.5	27	0.23 J	0.073 J	19000	8.5		5.9	19	16000
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	7800	< 0.33 U	6.9	93	0.36 J	0.054 J	1300	10		8.0	24	19000
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	6000	< 0.31 U	6.1	71	0.32 J	0.084 J	1100	7.9		7.8	20	15000
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	8900	< 0.38 U	8.4	95	0.44 J	< 0.050 U	8000	11		8.2	26	20000
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	7300	< 0.37 U	7.0	54	0.36 J	0.054 J	1600	9.3		7.4	20	17000
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	7700	< 0.29 U	6.9	64	0.43	0.20 J	3500	10		7.0	200	17000
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	5400	< 0.29 U	4.2	35	0.18 J	0.10 J	35000	7.2		5.4	17	13000
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	5400	< 0.25 U	3.9	36	0.15 J	0.073 J	50000	6.8		5.4	15	13000
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	6000	< 0.29 U	5.4	57	0.28 J	0.068 J	1700	7.3		6.1	18	15000
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	7600	< 0.35 U	6.8	62	0.36 J	0.074 J	850	9.4		7.6	21	19000
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	7500	< 0.30 U	5.0	50	0.35 J	0.050 J	3000	9.5		6.2	18	13000
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	7600	< 0.34 U	8.4	56	0.40 J	0.26 J	1200	9.6		8.1	30	17000
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	5100	< 0.38 U	4.8	42	0.23 J	0.059 J	23000	6.7		4.8	17	11000
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	5100	< 0.41 U	5.6	71	0.26 J	< 0.055 U	880	7.0		4.1	16	13000 B
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	5900	< 0.39 U	5.3	57	0.29 J	0.069 J	1300	7.9		5.9	18	14000 B
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	6600	< 0.40 U	8.0	62	0.38 J	0.057 J	1300	8.2		5.9	21	16000 B
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	5400	< 0.36 U	4.0	34	0.25 J	< 0.048 U	5100	6.9		4.2	16	11000 B
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	4100	0.28 J	4.2	27	0.21 J	0.086 J	20000	5.5		4.6	13	10000
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	4600	< 0.29 UT	3.6	24	0.18 J	0.070 J	13000 T	6.1		4.6	17	11000
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	4600	< 0.29 UT	3.6	24	0.18 J	0.070 J	13000 T	6.1		4.6	17	11000
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	8000	< 0.39 U	5.7	63	0.35 J	0.071 J	1700	9.5		6.4	28	18000
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	8400	< 0.38 U	6.3	60	0.39 J	0.092 J	2400	10		7.4	27	18000
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	9200	< 0.39 U	7.4	73	0.44 J	0.11 J	5100	11		7.4	29	20000
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	8200	< 0.40 U	6.4	89	0.37 J	0.10 J	2600	10		7.2	31	19000
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	6700	< 0.34 U	5.7	54	0.28 J	0.18 J	5300	8.5		5.6	26	15000
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	6400	< 0.38 U	5.8	49	0.31 J	0.13 J	4900	8.2		7.8	18	15000
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	5500	< 0.34 U	4.2	38	0.20 J	0.077 J	16000	7.0		5.5	19	13000
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	6900	< 0.34 U	6.5	56	0.31 J	0.065 J	4400	8.7		6.7	23	17000
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	6500	< 0.38 U	5.4	43	0.28 J	0.055 J	1800	8.4		6.1	21	15000
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	6000	< 0.30 U	4.5	46	0.22 J	0.079 J	11000	9.1		5.8	16	14000
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	8800	0.40 J	5.5	100	0.42 J	0.072 J	3900	11		8.3	15	18000
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	6600	< 0.40 U	6.9	42	0.16 J	0.13 J	26000	8.1		6.2	17	16000
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	6800	< 0.35 UT	7.6	58	0.32 J	0.13 J	3500 T	8.6		6.5	20	17000
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	4800	< 0.25 U	3.8	31	< 0.038 U	0.072 J	43000	6.1		5.0	13	11000
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	5500	< 0.33 U	5.3	40	0.10 J	0.12 J	32000	7.0		5.6	15	13000
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	5100	< 0.35 U	4.9	36	0.12 J	0.14 J	28000	6.6		5.0	16	13000
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	9000	< 0.40 U	10	110	0.54 J	0.30 J	4200	20		7.6	36	20000
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	5200	< 0.31 U	5.3	39	0.23 J	0.091 J	19000	7.1		5.7	19	14000
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	5200	0.92 J	10	100	0.49 J	1.7	7800	19		6.1	140	28000
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	10000	< 0.39 U	7.4	49	0.44 J	0.11 J	1000	12		7.7	19	20000
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	7500	< 0.32 U	5.5	46	0.31 J	0.090 J	700	9.4		6.3	18	16000
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	10000	0.66 JT	8.7	79	0.45 J	0.18 J	14000 T	16		8.6	34	22000
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	6100	< 0.39 U	3.4	41	< 0.059 U	0.18 J	51000	7.4		5.3	16	15000
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	9200	< 0.37 U	10	92	0.46 J	0.41 J	6900	14		8.8	50	25000
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	7600	8.0	12	97	0.47 J	0.59	6200	13		7.3	1000	20000
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	6700	< 0.28 U	6.6	35	0.33 J	0.11 J	1200	8.8		6.7	18	16000
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	4000	< 0.31 U	4.0	51	0.13 J	0.056 J	53000	5.1		4.2	12	10000
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	6800	< 0.33 U	7.4	60	0.30 J	0.12 J	21000	9.8		6.1	31	18000
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	5900	< 0.34 U	4.8	41	0.26 J	0.090 J	16000	7.2		5.9	16	14000
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	6000	< 0.33 U	5.7	43	0.25 J	0.080 J	9800	7.7		5.9	31	15000
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	6600	< 0.38 U	6.7	36	0.32 J	0.12 J	1200	8.8		6.5	17	16000
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	5800	< 0.37 U	6.1	33	0.28 J	0.11 J	15000	7.8		5.9	15	15000
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	5500	< 0.31 UT	4.6	63	0.24 J	0.13 J	26000 T	7.8		6.4	22	14000

DRAFT

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	11	2900	420	0.025 J	20	980	< 0.51 U	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	13	2300	560	0.025 J	16	270 J	< 0.42 U	< 0.096 U	< 47 U		< 0.26 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	4.5	1900	230	< 0.0081 U	8.6	530	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	6.2	1500	260	0.014 J	11	670	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	5.4	3000	270	< 0.0087 U	8.4	560	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	7.8	4800	460	0.014 J	13	1000	0.42 J	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	7.4	2900	350	0.025	13	620	< 0.40 U	< 0.091 U	< 45 U		< 0.25 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	7.6 T	2700	320	0.023	14 T	920	< 0.41 UT	< 0.093 UT	63 JT		< 0.25 UT
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	9.8	2100	360	0.025	13	760	< 0.47 U	< 0.11 U	< 52 U		< 0.29 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	7.5	3000	390	0.014 J	13	900	0.54 J	< 0.11 U	< 56 U		< 0.31 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	8.5	3500	350	0.028	12	680	< 0.46 U	< 0.10 U	< 51 U		< 0.28 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	4.6	3200	270	< 0.0078 U	10	490	< 0.42 U	< 0.095 U	< 47 U		< 0.26 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	13	3600	380	0.11	14	710	< 0.45 U	< 0.10 U	< 50 U		< 0.28 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	6.4	11000	310	0.015 J	9.7	600	0.45 J	< 0.084 U	65 BJ		< 0.23 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	8.6	2200	470	< 0.020 U	18	630	< 0.38 U	< 0.065 U	< 50 U		< 0.32 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	4.9	3500	310	< 0.016 U	12	420	< 0.36 U	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	23	4500	350	0.12	14	450	< 0.34 U	< 0.059 U	53 J		< 0.29 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	45	3300	420	0.021 J	15	510	< 0.41 U	< 0.071 U	< 55 U		< 0.35 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	5.5	8800	250	< 0.016 U	12	500	< 0.40 U	< 0.069 U	65 J		< 0.34 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	5.4	3600	310	< 0.016 U	14	460	< 0.39 U	< 0.067 U	53 J		< 0.33 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	6.1	4500	390	< 0.019 U	19	540	< 0.39 U	< 0.067 U	53 J		< 0.33 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	6.6	3200	350	< 0.017 U	16	460	< 0.36 U	< 0.063 U	< 49 U		< 0.31 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	9.5	2500	490	< 0.017 U	20	650	< 0.43 U	< 0.074 U	< 57 U		< 0.37 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	8.1	1900	670	< 0.022 U	17	560	< 0.40 U	< 0.069 U	< 54 U		< 0.34 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	10	6000	580	0.027 J	22	820	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	8.1	2400	800	< 0.019 U	18	690	< 0.49 U	< 0.084 U	< 65 U		< 0.42 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	61	2600	560	0.14	21	530	< 0.38 U	< 0.066 U	54 J		< 0.33 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	7.4	3800	390	< 0.021 U	15	490	< 0.38 U	< 0.065 U	58 J		< 0.32 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	5.7	3800	280	< 0.017 U	14	450	< 0.32 U	< 0.055 U	59 J		< 0.27 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	6.8	2000	400	< 0.017 U	15	550	< 0.38 U	< 0.065 U	< 51 U		< 0.32 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	11	2200	680	< 0.021 U	19	740	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	9.3	2500	380	0.042 J	17	490	< 0.40 U	< 0.069 U	< 53 U		< 0.34 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	12	1900	440	0.038 J	19	610	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	8.6	7600	410	0.026 J	12	500 J	< 0.50 U	< 0.086 U	< 67 U		< 0.42 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	10	1500	290	< 0.020 U	11	600	< 0.54 U	< 0.093 U	79 J		< 0.46 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	7.0	2100	560	< 0.021 U	15	580	< 0.51 U	< 0.088 U	< 68 U		< 0.44 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	11	1700	600	< 0.019 U	16	760	< 0.53 U	< 0.091 U	< 70 U		< 0.45 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	8.7	3700	280	< 0.020 U	11	670	< 0.47 U	< 0.081 U	< 63 U		< 0.40 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	4.5	2600	270	< 0.018 U	11	430	< 0.34 U	< 0.058 U	< 45 U		0.91 J
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	3.7	2600	260 T	< 0.017 U	12	380 J	< 0.38 U	< 0.066 U	< 51 U		0.75 J
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	3.7	2600	260 T	< 0.017 U	12	380 J	< 0.38 U	< 0.066 U	< 51 U		0.75 J
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	8.3	2400	430	0.026 J	18	720	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	15	2700	590	0.060 J	20	660	< 0.49 U	< 0.085 U	< 66 U		< 0.42 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	14	3600	660	0.027 J	24	790	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	16	2700	470	0.16	19	720	< 0.53 U	< 0.091 U	< 70 U		< 0.45 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	56	2300	410	0.11	14	410 J	< 0.44 U	1.1	< 59 U		< 0.38 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	8.8	3600	760	0.040 J	20	560	< 0.50 U	< 0.086 U	71 J		< 0.42 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	6.6	3500	650	< 0.018 U	14	420 J	< 0.44 U	0.092 J	< 59 U		< 0.38 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	9.7	2800	470	0.024 J	17	630	< 0.44 U	< 0.076 U	< 59 U		< 0.37 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	6.6	2200	340	0.018 J	15	530 J	< 0.50 U	< 0.087 U	< 67 U		< 0.43 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	7.3	6900	410	< 0.018 U	14	620	< 0.40 U	< 0.069 U	73 J		< 0.34 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	9.9	3600	550	0.031 J	18	750	< 0.48 U	< 0.082 U	74 J		< 0.40 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	14	5800	390	< 0.023 U	17	730	< 0.52 U	< 0.089 U	69 BJ		< 0.44 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	21 T	3300 T	470 T	0.038 J	18	580	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	5.4	3400	290	< 0.018 U	13	510	< 0.33 U	< 0.057 U	60 BJ		< 0.28 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	13	8000	380	< 0.020 U	14	620	< 0.43 U	< 0.075 U	77 BJ		< 0.37 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	7.4	4300	380	< 0.021 U	13	670	< 0.46 U	< 0.079 U	< 61 U		< 0.39 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	38	2000	350	0.16	160	590	< 0.53 U	< 0.091 U	170 J		< 0.45 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	7.5	5200	350	< 0.019 U	13	520	< 0.41 U	< 0.071 U	75 J		< 0.35 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	87	1100	270	0.11	69	440 J	0.96 J	< 0.087 U	170 J		< 0.43 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	10	2400	340	0.031 J	18	780	< 0.52 U	< 0.089 U	< 69 U		< 0.44 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	7.1	2000	350	0.028 J	15	580	< 0.42 U	< 0.073 U	< 56 U		< 0.36 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	32 T	3900	430 T	0.086 J	29	980	< 0.47 U	< 0.082 U	120 J		< 0.40 U
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	5.2	3200	360	< 0.023 U	15	480 J	< 0.51 U	< 0.088 U	< 68 U		< 0.43 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	37	2500	460	0.13	33	750	< 0.48 U	< 0.083 U	90 J		< 0.41 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	190	1700	580	0.16	34	630	0.68 J	0.38 J	110 J		< 0.45 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	7.3	2400	310	< 0.018 U	18	750	< 0.36 U	< 0.062 U	56 J		< 0.31 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	5.4	3000	300	< 0.019 U	10	390 J	< 0.41 U	< 0.070 U	< 54 U		< 0.35 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	15	2600	420	0.041 J	18	610	< 0.43 U	< 0.075 U	< 58 U		< 0.37 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	6.7	5600	410	< 0.020 U	14	520	< 0.45 U	< 0.077 U	< 60 U		< 0.38 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	5.8	6100	470	< 0.021 U	14	550	< 0.43 U	< 0.074 U	< 57 U		< 0.36 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	7.8	2300	310	< 0.020 U	17	750	< 0.50 U	< 0.086 U	< 66 U		< 0.42 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	7.5	3000	250	< 0.018 U	15	710	< 0.48 U	< 0.083 U	85 J		< 0.41 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	12	4600	370 T	0.024 J	16	410 J	< 0.40 U	< 0.069 U	80 J		< 0.34 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated		18	57
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated		22	50
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated		7.5	29
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated		11	43
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated		7.2	30
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated		12	48
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated		11	47
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated		12 T	52 T
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated		11	45
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated		12	94
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated		10	46
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated		7.4	36
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated		12	54
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated		7.6	48
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated		12	72
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated		8.0	48
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated		8.9	70
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated		11	69
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated		8.1	57
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated		8.2	55
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated		12	77
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated		9.4	79
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated		13	75
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated		10	100
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated		15	81
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated		12	71
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated		14	120
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated		8.9	59
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated		7.8	52
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated		11	61
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated		14	74
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated		11	52
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated		14	130
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated		9.0	56
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated		8.7	45 B
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated		10	60 B
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated		12	58 B
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated		8.6	39 B
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated		7.1	39
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated		7.1	44
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated		7.1	44
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated		12	81
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated		13	83
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated		15	92
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated		13	100
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated		11	100
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated		10	93
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated		8.5	53
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated		11	71
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated		12	60
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated		11	67
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated		15	66
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated		12	82
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated		12	67
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated		8.1	46
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated		11	63
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated		11	87
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated		15	74
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated		9.9	64
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated		15	190
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated		17	57
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated		13	54
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated		16	84
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated		8.0	61
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated		15	120
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated		14	120
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		10	55
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated		6.3	37
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated		10	56
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated		8.9	67
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated		8.9	54
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		9.7	52
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated		9.1	47
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated		8.6	57

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	7300	< 0.34 U	6.9	78	0.36 J	0.12 J	5000	11		6.4	24	16000
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	4100	0.29 J	3.9	37	0.18 J	0.091 J	71000	5.4		4.2	13	11000
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	5000	< 0.24 U	5.1	36	0.22 J	0.084 J	28000	6.7		4.9	17	13000
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	6800	< 0.20 U	7.6	67	0.28	0.080 J	18000	7.9		6.8	17	18000
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	7100	0.36 J	21	60	0.48	2.4	13000	14		9.2	240	60000 B
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	9800 T	< 0.17 UT	15	81 T	0.50	0.69 J	9400	12 T		12	20	29000 B
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	6800	0.56 J	14	57	0.54	1.9 J	31000	16		6.2	260	47000 B
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	4200	< 0.17 U	3.7	33	0.18 J	0.35	87000	5.5		4.9	18	10000 B
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	6200	0.22 J	4.5	48	0.26 J	0.42	21000	10		6.5	27	14000
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	6000	< 0.25 U	8.3	60	0.34	0.88	25000	8.9		8.5	33	28000
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	5800	< 0.21 UT	5.1	53 T	0.25 J	0.40	24000	7.4		6.6	21	14000
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	4600	0.73 J	4.8	37	0.19 J	0.37 J	37000	2.9		4.0 J	21	13000
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	5900	0.53 J	4.9	35	0.23 J	0.34	57000	2.1		4.5	19	14000
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	5200	0.52 J	5.2	31	0.21 J	0.35 J	40000	2.1		4.4	18	13000
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	9700 T	1.1	11	77	0.43	0.53	10000	4.0		10	22	29000
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	5600	0.57 J	3.5	42	0.21 J	< 0.064 U	61000	7.4		5.0	22	14000
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	6400	0.49 J	4.2	44	0.27	< 0.048 U	7900	7.8		5.8	15	15000
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	5200	0.55 J	3.5	44	0.19 J	< 0.048 U	37000	6.4		5.0	19	12000
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	4300	0.53 JT	5.1	30	0.17 J	< 0.074 U	29000	5.1		4.0 J	17	11000
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	5200	0.71	8.3	42	0.24 J	< 0.052 U	59000	6.3		5.0	20	18000
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	12000	< 0.24 U	9	72	0.55	0.062 J	5200	14		9.8	15	23000
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	6000	< 0.22 U	51	93	0.15 J	< 0.015 U	< 1.6 U	11		3.5 J	22	44000
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	6400	< 0.21 U	49	82	0.22 J	< 0.015 U	990	11		3.3 J	41	51000
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated	4700	0.56 J	53	71	0.15 J	< 0.12 U	340 J	9.2		2.4 J	25	41000
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated	3500	1.1	61	76	0.13 J	< 0.12 U	1100	13		2.4 J	95	51000
Rear Parking Lot	SSHS-B1251	070318 09:15 SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated	6900	< 0.43 U	30	110	0.22 J	0.23 J	960	18		3.3 J	68	51000
Rear Parking Lot	SSHS-B1252	070318 09:15 SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated	8200	< 0.39 U	17	98	0.29 J	0.15 J	950	16		5.1 J	36	36000
Rear Parking Lot	SSHS-B1254	070318 09:15 SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated	6500	< 0.42 U	16	59	0.23 J	0.27 J	14000	16		3.9 J	80	32000
Rear Parking Lot	SSHS-BSW-001	071318 09:15 EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	8900	4.4	28	580	0.32 J	1.8	42000	170		14	330	45000
Rear Parking Lot	SSHS-B1299	080718 09:00 SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated	7000	< 0.74 U	21	180	0.41 J	0.69	21000	100		20	180	81000
Rear Parking Lot	SSHS-B3840	072421 09:00 SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated	7100	0.3 J	10	58	0.17 J	< 0.026 U	1100	12		5	25	25000
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	6900	< 0.28 U	52	96	0.23 J	< 0.068 U	2500	9.7		3.4 J	18	29000
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated	3100	< 0.39 UT	53 T	81 T	0.11 JT	0.049 JT	560 T	8.2 T		2.1 JT	29 T	49000 T
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	3900	< 0.24 U	2.7	73	0.15 J	0.076 J	20000	5.6		3.7 J	15	9800
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	5100	< 0.36 U	6.9	49	0.30 J	0.15 J	1400	11		6.3	70	12000
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated	5900	< 0.4 U	38	80	0.2 J	< 0.13 U	4700	15		3.5 J	30	34000
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated	5500	0.62 J	57	110	0.25 J	< 0.13 U	9000	17		4.4 J	79	47000
Rear Parking Lot	SSHS-B1254	070318 09:15 SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated	6600	< 0.42 U	28	100	0.3 J	0.28 J	23000 J	24		4.5 J	120 J-	39000 J
Rear Parking Lot	SSHS-B1303	080718 09:00 SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated	6100	< 0.41 U	9.1	73	0.32 J	0.25 J	33000	10		6.4	79	22000
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	5200	< 0.31 U	22	58	0.16 J	< 0.076 U	1100	8.1		3.2 J	32	20000
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated	3500	< 0.44 U	30	130	0.16 J	< 0.053 U	2700	12		2.9 J	43	47000
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	4800	< 0.20 U	4.2	56	0.21 J	0.11 J	12000	7.2		4.9	18	12000
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	6800	< 0.2 U	5.6	62	0.35 J	0.11 J	22000	10		6.6	29	14000
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated			39									
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated	7400	< 0.38 U	7.7	73	0.40 J	0.41 J	15000	19		8.8	150	21000
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated	6400	0.70 J	6.8	58	0.29 J	0.17 J	6100	26		7.5	31	16000
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated	3900	< 0.36 U	31	73	0.19 J	< 0.044 U	4900	13		3.3	34	41000
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	1500	< 0.16 U	2.2	9.1 J	0.059 J	< 0.038 U	320	2.7		1.5 J	16	4100
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	5100	< 0.29 U	2.9	23	0.14 J	< 0.071 U	1800	15		3.7 J	17	15000
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated	8700	< 0.39 U	5.5	85	0.36 J	0.16 J	4900	33		7.8	31	20000
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated			15									
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated			9.2									
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated	6000	< 0.27 U	3.7	41	0.26 J	0.12 J	120000	7.8		6	17	13000
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	3300		4.8 J	660 J	0.29 J	0.075 J	17000 J	6.7 J		4.8 J	23 J	12000
Rear Parking Lot	SSHS-W3-1	080118 09:00 W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated	6500 =	< 0.39 U	5	58	0.26 J	< 0.042 U	8900	7.7		6	23	16000 =
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated	5800	0.62 J	46	88	0.24 J	0.30 J	14000	19		5.0	55	45000
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	3100	4.6	20	110	0.81	< 0.016 U	2300	9.3		11	74	32000
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	3500	2.7	17	140	0.92	0.069 J	2000	9.3		7.2	70	29000
Rear Parking Lot	SSHS-W10-1	080118 09:00 W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated	6300 =	0.5 J	6.9	71	0.28 J	< 0.042 U	26000	23		5.9	74	19000 =
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated												
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated	8000	< 0.39 U	8.1	150	0.4 J	0.11 J	16000	15		6.8	57	19000
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated	10000	0.3 J	15	140	0.46 J	0.035 J	4400 J	13		8.8	36	24000
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	3300	< 0.22 U	3.6	210	0.15 J	< 0.053 U	14000	6.4		3.4 J	21	10000
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated	5500 =	< 0.42 U	5	56	0.27 J	< 0.045 U	12000	9.3		5 J	39	13000 =
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated	6400	0.83 J	20	59	0.35 J	0.41 J	24000	14		10	49	37000
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated	8600	0.49 J	14	64	0.38 J	0.52	18000	29		7.6	130	31000
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated	9100	1.5	6.9	780	0.4 J	< 0.042 U	18000	22		8.8	340	38000
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated	8800	< 0.41 U	8.0	91	0.39 J	0.18 J	25000	15		7.2	35	19000
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated	8200 =	< 0.41 U	9.8	120	0.42 J	< 0.044 U	4100	15		7.1	60	19000 =
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	1809185 71	Not Excavated	7600	0.42 J	6.3	52	0.32 J	< 0.040 U	30000	11		6.8	24	18000
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	1809185 71	Not Excavated	7500	0.43 J	5.2	60	0.26 J	< 0.041 U	68000	15		6.7	34	18000
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	1809185 71	Not Excavated	8500	0.64 J	7.3	83	0.39 J	< 0.042 U	14000	12		7.1	30	18000
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	1809185 71	Not Excavated	8600	0.70 J	11	81	0.38 J	< 0.041 U	40000	14		6.8	48	17000
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	1809185 71	Not Excavated	10000	0.58 J	17	120	0.45 J	< 0.044 U	16000	17		7.6	76	20000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	15	2700	500	0.059 J	17	580	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	6.8	3800	360	< 0.019 U	11	280 J	< 0.34 U	< 0.077 U	55 J		0.44 J
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	8.0	3500	300	< 0.019 U	13	370 J	< 0.36 U	< 0.081 U	49 J		0.51 J
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	7.0	4700	650	< 0.020 U	15	440	< 0.30 U	< 0.067 U	< 33 U		0.74 J
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	42	3600	370 B	0.38	26 B	370	1.0	< 0.070 U	91 J		< 0.95 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	20 T	3800 T	500 B	< 0.021 U	26 B	660 T	< 0.27 U	< 0.060 U	34 J		< 0.82 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	50	3600	350 B	0.14	19 B	290 J	1.4	0.17 J	120 J		< 1.1 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	7.1	4400	440 B	< 0.021 U	12 B	190 J	< 0.26 U	< 0.059 U	61 J		0.23 J
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	11	4400	380	< 0.023 U	15	430	< 0.33 U	< 0.075 U	39 J		0.22 J
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	32	6700	370	0.10	23	300 J	0.86	0.091 J	60 J		< 0.23 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	16	3600	310 T	0.033	16 T	270 J	< 0.32 U	< 0.072 U	36 J		< 0.20 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	17	3700 T	270	0.10	14	410	< 0.38 U	0.17 J	56 J		< 1.2 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	8.7	14000	300	0.17	16	310 J	< 0.32 U	0.14 J	43 J		< 0.98 U
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	9.6	4200	290	3.6	14	420	< 0.36 U	0.16 J	45 J		< 1.1 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	17	3700 T	550	0.32	26	750	< 0.39 U	0.33 J	< 43 U		< 2.4 U
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	15	11000	350	0.71	13	440	< 0.40 U	< 0.091 U	71 J		< 0.25 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	10	3600	240	0.12	13	580	< 0.30 U	< 0.13 U	35 J		< 0.18 U
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	8.8	3700	360	0.23	13	340	< 0.30 U	< 0.14 U	49 J		< 0.19 U
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	7.8 J	5000 T	270	< 0.021 U	9.3	410 J	< 0.46 U	< 0.10 U	52 J		< 0.29 U
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	15	25000	520	0.23	12	620	< 0.33 U	< 0.074 U	79 J		0.48 J
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	12	4000	440	0.017 J	19	1700	0.56 J	< 0.049 U	88 J		< 0.18 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	15	1700	130	0.026 J	8.8	1400	2.7	< 0.044 U	580		< 0.16 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	7.2	1600	110	< 0.012 U	8.7	810	1 J	< 0.043 U	550		0.24 J
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated	7.7	1300	67	< 0.008 U	10	1000	1.3	< 0.18 U	510 J		< 0.54 U
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated	2100	880	83	0.046	24	890	2.6	< 0.18 U	850		< 0.53 U
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated	15	1700	120	< 0.0085 U	12	1800	1.3	< 0.13 U	1100		< 0.26 U
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated	11	2100	150	< 0.0089 U	15		0.87 J	< 0.12 U	460 J		< 0.24 U
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated	23	2600	150	0.094 =	23		1.1 J	< 0.13 U	420 J		< 0.26 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	650	5200	720	1.4	2000	930	1.3	< 0.13 U	500 J		< 0.26 U
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated	290	4400	830	0.069	2000	650	1.4	< 0.11 U	290 J		< 0.23 U
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated	7	2100	180	< 0.02 U	13	710	0.39 J	< 0.076 U	170 J		< 0.23 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	11	1700	230	< 0.021 U	11	690	3.2	< 0.096 U	180 J		0.59 J
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated	20 T	860 T	160 T	0.24 T	6.7 T	1400 T	1.5 T	< 0.067 UT	360 T		0.31 JT
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	9.3	6800	280	< 0.021 U	9.8	320 J	< 0.37 U	< 0.084 U	120 J		< 0.23 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	12	1200	690	< 0.025 U	27	680	< 0.47 U	0.19 BJ	< 140 U		< 0.40 U
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated	22	2300	130	0.69	15	960	1.2	< 0.19 U	410 J		< 0.56 U
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated	130	5400	170	0.043	20	1200	1.7	< 0.19 U	880		< 0.56 U
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated	34	2600	180	0.069 =	32		2.3	< 0.13 U	540 J		< 0.26 U
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated	55	6600	450	0.019 J	26	720	< 0.62 U	< 0.13 U	160 J		< 0.25 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	9.6	1700	110	< 0.023 U	11	660	0.98 J	< 0.11 U	100 J		< 0.29 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated	14	1200	110	0.16	9.8	630	2.2	< 0.075 U	230 J		0.50 J
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	10	4200	520	< 0.017 U	24	520	< 0.31 U	< 0.070 U	140 J		< 0.19 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	9	5900	420	0.013 J	17	690	0.44 J	< 0.04 U	71 J		< 0.14 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated											
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated	31	5000	2000	< 0.023 U	76	800	< 0.99 U	0.17 BJ	190 J		0.95 J
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated	14	2600	660	< 0.019 U	22	880	< 0.56 U	0.16 BJ	< 170 U		< 0.48 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated	11	1200	130	0.066	9.9	710	1.6	< 0.062 U	240 J		0.42 J
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	2.1	670	71	< 0.020 U	3.5	150 J	< 0.24 U	< 0.054 U	< 27 U		< 0.15 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	4.1	2000	180	< 0.019 U	11	300 J	< 0.45 U	< 0.10 U	< 49 U		< 0.27 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated	11	2700	480	< 0.022 U	22	980	0.76 J	0.12 BJ	< 160 U		< 0.44 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated											
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated											
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated	8.6	6400	500	0.025 J	16	650	1.2	< 0.083 U	130 J		< 0.25 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	19 J	4200 J	310	< 0.016 UT	14 J	360 J	< 0.37 UJ	< 0.084 UJ	650 J		< 0.23 UJ
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated	8.6	3200	690 =	0.024 J	14	490 J	< 0.59 U	< 0.12 U	170 J		0.35 J
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated	170	3000	180	0.041 J	67	680	2.7	< 0.080 U	290 J		< 0.40 U
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	120	390 J	200	0.065	20	< 7 U	1.9	< 0.044 U	220 J		< 0.16 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	120	850	180	0.13	16	< 8.2 U	1.8	< 0.052 U	180 J		< 0.19 U
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated	90	3000	370 =	0.08	86	670	< 0.6 U	< 0.12 U	150 J		< 0.24 U
Rear Parking Lot	SSHS-B955	030118 10:00_SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated										< 11 U	
Rear Parking Lot	SSHS-B1346	080418 11:30_SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated	40	3500	510	0.036 J	41	850	< 0.6 U	< 0.12 U	430 J		0.33 J
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated	27	2700	370	0.043	43	620	0.63 J	< 0.086 U	150 J		< 0.26 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	18	2900	210	< 0.015 U	10	250 J	< 0.33 U	< 0.075 U	310 J		< 0.20 U
Rear Parking Lot	SSHS-W3-2	080118 09:00_W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated	44	4000	380 =	0.026 J	25	660	< 0.63 U	< 0.13 U	180 J		< 0.26 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated	110	4600	460	0.022 J	71	560	1.3 J	< 0.082 U	190 J		< 0.40 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated	130	3500	240	< 0.022 U	96	580	1.2 J	< 0.078 U	220 J		< 0.39 U
Rear Parking Lot	SSHS-N-E-0	080718 09:00_N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated	290	2000	540	0.038 J	160	800	0.65 J	< 0.12 U	520 J		< 0.24 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated	33	4500	430	0.18	26	800	0.73 J	< 0.093 U	< 160 U		0.48 J
Rear Parking Lot	SSHS-W1-2	080118 09:00_W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated	72	2600	330 =	0.055	43	620	0.86 J	< 0.13 U	350 J		0.37 J
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated	22	14000	360	0.031 J	21	590	< 0.56 U	< 0.12 U	170 J		0.51 J
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated	11	16000	530	0.016 J	16	700	< 0.58 U	< 0.12 U	120 J		0.62 J
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated	49	4300	390	0.14	20	750	< 0.59 U	< 0.12 U	87 J		0.68 J
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated	31	4400	450	0.19	79	800	< 0.58 U	< 0.12 U	170 J		0.66 J
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated	62	4500	520	0.11	160	930	< 0.63 U	< 0.13 U	230 J		0.81 J

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated		11	67
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated		6.7	35
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated		8.3	51
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated		11	47
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated		17	310
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated		15	56
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated		19	190
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated		8.3	41
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated		12	65
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated		13	140
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated		8.9	44 T
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		2.0 J	52
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		1.6 J	55
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		2.2 J	46
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated		1.9 J	56
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated		9.8	91
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated		9.1	35
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated		9.3	45
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated		6.5	40 T
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated		8.8	61
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated		18	56
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated		15	45
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated		13	37
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated		14	31
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated		13	55
Rear Parking Lot	SSHS-B1251	070318 09:15 SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated		16	51
Rear Parking Lot	SSHS-B1252	070318 09:15 SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated		15	51
Rear Parking Lot	SSHS-B1254	070318 09:15 SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated		13	70
Rear Parking Lot	SSHS-BSW-001	071318 09:15 EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated		18	840
Rear Parking Lot	SSHS-B1299	080718 09:00 SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated		15	220
Rear Parking Lot	SSHS-B3840	072421 09:00 SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated		13	46
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated		12	45
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated		8.2 T	26 T
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated		6.0	39
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated		9.3	96
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated		15	53
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated		15	54
Rear Parking Lot	SSHS-B1254	070318 09:15 SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated		15	83
Rear Parking Lot	SSHS-B1303	080718 09:00 SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated		10	94
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated		9.4	45
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated		15	30
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated		8.1	63
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated		10	76
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated			
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated		14	170
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated		12	82
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated		12	35
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated		2.5 J	16
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated		7.9	64
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated		14	79
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated			
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated			
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated		9	47
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated		9.8 J	41
Rear Parking Lot	SSHS-W3-1	080118 09:00 W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated		11	55
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated		15	77
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated		20	69
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated		18	68
Rear Parking Lot	SSHS-W10-1	080118 09:00 W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated		12	70
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated			
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated		16	140
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated		15	81
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated		6.6	35
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated		9.9	55
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated		11	360
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated		13	150
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated		21	140
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated		15	110
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated		16	100
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated		12	64
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated		12	58
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated		14	90
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated		15	70
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated		16	170

DRAFT

														Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated													
Rear Parking Lot	SSHS-SS-05 8 20	082218 09:15 SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated	3800	< 0.4 U	79	82	0.13 J	0.23 J	520 J	12		1.9 J	69	35000
Rear Parking Lot	SSHS-B1500	082218 09:15 SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated	4900	< 0.39 U	33	79	0.15 J	0.17 J	140 J	8		1.9 J	20	39000
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated	9200	0.39 J	18	95	0.32 J	< 0.041 U	3300 J	15		7.7	38 J	34000
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	6300	< 0.26 U	5.1	170	0.26 J	< 0.064 U	7000	9.2		5.2	19	14000
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	4800	< 0.23 U	8.7	63	0.54	0.059 J	17000	9.1		5.5 J	36	21000
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated	8000	0.47 J	7.2	75	0.37 J	< 0.044 U	31000	12		6.9	30	18000
Rear Parking Lot	SSHS-W6-3	080118 09:00 W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated	10000 =	< 0.4 U	7.5	100	0.43 J	< 0.043 U	4900	15		8.3	85	23000 =
Rear Parking Lot	SSHS-GS3-4	073118 08:50 G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated	13000	< 0.41 U	9.2	80	0.59	0.061 J	24000	15		9.6	38	23000
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	10000	0.40 J	7.7	83	0.49 J	0.21 J	8100	16		8.9	150	25000
Rear Parking Lot	SSHS-N-E-1	080718 09:00 N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated	9800	2.2	6.9	290	0.41 J	< 0.041 U	2400	23		8	280	24000
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	8000	< 0.31 U	6.6	88	0.32 J	0.15 J	17000	21		6.9	48	18000
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	11000	< 0.31 U	13	190	0.49	0.14 J	7200	19		8.6	49	21000
Rear Parking Lot	SSHS-EN3-4	073118 08:50 E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated	13000	< 0.42 U	9.8	66	0.59	0.05 J	1300	16		10	37	23000
Rear Parking Lot	SSHS-SS-02 8 20	SSHS-SS-02 8 20	SSHS-SS-02 8 20	8/20/2018	-	848.51	-	842.58	6-8 ft	5.93 ft	-	Not Excavated	4400	<0.4U	120	65	0.21J	0.36J	2200	9.2		2.7J	44	51000
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated	7300	< 0.39 U	16	92	0.45 J	0.22 J	34000	20		5.9	44	22000
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	6200	0.37 J	5.9	74	0.28 J	0.23 J	53000	10		4.6 J	42	13000
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	2800	0.36 J	26	210	0.61	< 0.017 U	11000	11		6.5	47	26000
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	6400	< 0.26 U	63	140	0.22 J	< 0.018 U	6000	14		4 J	33	42000
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated												
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated	8600	< 0.36 U	10	79	0.25 J	< 0.039 U	1300	14		6.6	20	32000
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated	3400	< 0.20 U	20	210	0.15 J	< 0.049 U	1500	9.0		2.6 J	23	28000
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	3300	< 0.19 U	2.6	67	0.14 J	0.060 J	31000	4.8		3.7	11	8200
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated	8700	0.69 J	16	84	0.38 J	< 0.042 U	14000	18		6.6	98	17000
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated	7400	< 0.27 U	9.7	67	0.19 J	0.16 J	47000	16		6.0	27	18000
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	5100	0.51 J	14	130	0.55	0.41 J	20000	13		9	53	20000
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	6600	< 0.38 U	6	150	0.32 J	0.16 J	14000	9.1		6.4	24	15000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45 SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated	6400	< 0.35 U	7.3	36	0.29 J	0.084 J	1000	8.3		6.4	20	16000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00 SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated	6500	0.46 J	6.3	44	0.28 J	0.12 J	2400	8.3		6	22	17000
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00 SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated	6400	< 0.36 U	6	49	0.28 J	0.1 J	13000	8.6		5.7	22	16000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00 SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated	6400	0.48 J	7.9	40	0.29 J	0.069 J	1000	8.5		6.1	19	16000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00 SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated	5600	< 0.34 U	5.6 J	48	0.24 J	0.088 J	32000	6.9		5 J	16	15000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00 SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated	7700	0.69 J	8.8	130	0.67	0.15 J	38000	11		6.3	32	20000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00 SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated	7000	0.37 J	6.4	100	0.3 J	0.12 J	11000	9.1		6.6	24	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00 SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated	6700	0.48 J	9.3	64	0.31 J	0.081 J	3400	9		6.3	20	17000
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	7300	0.36 J	5.9	86	0.3 J	0.11 J	85000	13		5.9	31	15000
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	5800	< 0.034 U	5	63	0.22 J	0.079 J	69000 J	10		5.2 J	27	13000
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	5700	< 0.034 U	7.2	33	0.26 J	0.084 J	16000	7.4		5.9	16	14000
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	5700	< 0.22 U	5.8	37	0.28 J	< 0.016 U	1200	8.1		6.7	19	15000
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	4900	0.32 J	4.9	35	0.23 J	< 0.014 U	37000	6.4		4.9	15	12000
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	4800	< 0.22 U	6.4	47	0.23 J	0.068 J	2700	7.4		4.9 J	15	14000
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	4800	< 0.21 U	4.8	42	0.2 J	0.06 J	85000	5.9		4.6 J	17	12000
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	6800	< 0.21 U	7.9	72	0.3 J	0.11 J	1200	8.9		6.6	22	17000
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	6800	< 0.22 U	6.9	96	0.3 J	0.1 J	1500	9.2		7.1	18	17000
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	6100	< 0.22 U	6.5	59	0.27 J	1.2	2400	7.8		5.8	18	16000
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	7900	< 0.23 U	9.8	87	0.37 J	0.065 J	1300	11		6.6	24	20000
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	4400	< 0.2 U	4.9	35	0.21 J	0.058 J	1700	5.6		4.2 J	20	12000
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	4900	0.39 J	4.7	36	0.24 J	< 0.013 U	71000	5.5		3.8 J	16	9700
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	5100	0.27 J	6	41	0.23 J	< 0.015 U	19000	6.7		5 J	17	14000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00 SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated	7100	< 0.37 U	5.9	68	0.36 J	0.11 J	8800	9.5		5.9	62	19000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00 SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated	6900	0.41 J	6.8	43	0.31 J	0.091 J	21000	9		7.4	22	17000
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00 SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	5800	0.76 J	6.5	110	0.43 J	0.14 J	37000	8.8		5.5	29	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00 SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated	5700	19	6.6	86	0.28 J	0.18 J	92000	8.8		5.6	80	14000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00 SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated	4400	< 0.34 U	4.4	36	0.19 J	0.094 J	34000 J	6.1		4.2 J	16	11000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00 SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated	5000	0.34 J	5.6	39	0.23 J	0.12 J	37000	6.8		5	23	14000
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30 SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	13000	19	130	740	2.3	5.1	7100	180		23	2600	190000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30 SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated	6400	< 0.76 U	6.6	62	0.37 J	0.11 J	27000	8.7		6	23	20000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00 SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated	7600	0.59 J	7.3	100	0.53	0.11 J	29000	10		6.7	31	22000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00 SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated	9400	0.63 J	8.9	100	0.63	0.12 J	31000	11		7.5	30	23000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00 SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated	6600	0.34 J	5.6	66	0.3 J	0.14 J	14000	8.8		6.6	23	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00 SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated	6700	0.51 J	7.1	58	0.32 J	0.11 J	7800	9		6.7	24	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated	6100	0.43 J	6.4	46	0.29 J	0.093 J	4700	8		5.8	21	15000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated	6500	< 0.38 U	5.9	45	0.29 J	0.085 J	2700	9.1		5.6	21	16000
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	7500	< 0.034 U	5.8	71	0.64	0.039 J	49000	8.3		7.3	26	22000
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	6100	< 0.034 U	9.3 J	43	0.22 J	0.054 J	37000	13		5.6	26	15000
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	5400	< 0.034 U	4.5	48	0.18 J	0.075 J	52000	11		4.6	16	13000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00 SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated	7800	0.43 J	13	290	0.56	0.25 J	44000	13		7.5	78	23000
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00 SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated	5900	< 0.43 U	5.7	73	0.28 J	0.12 J	34000	7.9		5.6 J	29	15000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00 SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated	5700	< 0.38 U	3.9	40	0.22 J	0.084 J	22000	7.2		4.8 J	23	13000
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	7500	< 0.034 U	6.3	67	0.33 J	0.081 J	38000	14		6	30	16000
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	7500	< 0.034 U	5.6	59	0.26 J	0.071 J	32000	16		6	50	17000
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	5000	< 0.034 U	5.6	46	0.2 J	0.059 J	33000	9.9		5.7	18	13000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated	6900	0.5 J	5.1	56	0.3 J	0.13 J	35000	9.2		5.6	32	15000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated	6300	0.53 J	5.5	73 J-	0.33 J	0.17 J	45000	8.6		5.8	38 J-	17000

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated									< 11 U	
Rear Parking Lot	SSHS-SS-05 8 20	082218 09:15 SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated	24	810	90	0.04	15	520 J	3	< 0.12 U	240 J		< 0.38 U
Rear Parking Lot	SSHS-B1500	082218 09:15 SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated	7.9	1100	73	0.021 J	5.8	760	0.92 J	< 0.12 U	150 J		< 0.37 U
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated	22	2900	540 J	0.034 J	23	780	0.76 J	< 0.12 U	110 J		< 0.36 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	28	2900	260	< 0.015 U	15	540	< 0.40 U	< 0.090 U	310 J		< 0.25 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	28	2400	130	0.027 J	17	790	1.2	< 0.046 U	200 J		< 0.17 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated	33	8900	390	0.14	24	860	< 0.63 U	< 0.13 U	200 J		0.50 J
Rear Parking Lot	SSHS-W6-3	080118 09:00 W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated	110	3000	500 =	0.041 J	59	840	< 0.61 U	< 0.12 U	140 J		0.3 J
Rear Parking Lot	SSHS-GS3-4	073118 08:50 G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated	14	3600	650	0.038	41	1000	< 0.62 U	< 0.13 U	500 J		< 0.25 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	44	2900	170	< 0.021 U	68	960	0.62 J	< 0.088 U	220 J		< 0.43 U
Rear Parking Lot	SSHS-N-E-1	080718 09:00 N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated	270	2300	520	0.059	150	850	< 0.58 U	< 0.12 U	480 J		0.26 J
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	26	4500	460	0.036	28	750	0.46 J	< 0.069 U	< 120 U		< 0.34 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	14	3000	2900	0.11	35	950	< 2.0 U	0.36 BJ	240 J		< 1.7 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50 E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated	15	3200	480	0.02 J+	270	1100	< 0.64 U	< 0.13 U	420 J		< 0.26 U
Rear Parking Lot	SSHS-SS-02 8 20	SSHS-SS-02 8 20	SSHS-SS-02 8 20	8/20/2018	-	848.51	-	842.58	6-8 ft	5.93 ft	-	Not Excavated	29	1400	140	0.028J	13	680	2.5	<0.12U			<0.37U
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated	64	3100	360	0.23	43	610	1.7 J	< 0.087 U	270 J		< 0.43 U
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	230	6500	320	0.2	25	670	0.86 J	< 0.12 U	170 J		< 0.23 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	26	2300	87	0.1	16	< 7.7 U	2.6	< 0.049 U	180 J		< 0.18 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	28	2500	200	0.032 J	35	1200	4	< 0.052 U	670		< 0.19 U
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated									< 11 U	
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated	12	2400	330	< 0.019 U	16	850	< 0.55 U	< 0.11 U	100 J		< 0.34 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated	8.2	940	87	0.079	8.3	620	1.4	< 0.069 U	200 J		0.42 J
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	7.4	4400	170	< 0.022 U	9.2	250 J	0.34 J	< 0.064 U	180 J		< 0.18 U
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated	46	3400	430	6.6	250	770	< 0.59 U	< 0.12 U	200 J		0.62 J
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated	15	4700	300	0.27	21	810	0.66 J	< 0.060 U	240 J		0.38 J
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	61	2700	270	0.59	31	820	2.3	< 0.12 U	400 J		< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	27	2400	690	0.095	17	530	< 0.42 U	< 0.18 U	< 150 U		< 0.53 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45 SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated	7.8	2100	350	< 0.014 U	16		< 0.53 U	< 0.11 U	200 J		< 0.33 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00 SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated	7.9	2700	570	< 0.015 U	16		< 0.57 U	< 0.12 U	150 J		< 0.36 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00 SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated	25	5300	410	< 0.014 U	15		< 0.55 U	< 0.11 U	< 28 U		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00 SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated	8	2200	440	< 0.013 U	15		< 0.54 U	< 0.11 U	200 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00 SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated	7.1	14000 J	470	< 0.012 U	12		< 0.52 U	< 0.11 U	200 J		< 0.32 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00 SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated	50	2700	250	< 0.017 U	19		1.8	< 0.12 U	600		< 0.37 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00 SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated	21	7500	640	< 0.014 U	16		< 0.55 U	< 0.11 U	240 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00 SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated	10	2200	450	< 0.014 U	15	800	< 0.56 U	< 0.11 U	260 J		< 0.35 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	28	23000	520 J	0.043 J-	18	890	1.5	< 0.034 U	290 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	12	13000	420	< 0.034 U	17	730	0.88 J	< 0.034 U	140 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	7.4	6100	270	< 0.034 U	14	830	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	8.7	1900	710	< 0.012 U	14	< 6.9 U	< 0.29 U	< 0.044 U	90 J		< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	6	11000	370	< 0.012 U	12	560	< 0.26 U	< 0.04 U	130 J		< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	6.7	1900	490	< 0.012 U	12	490 J	0.5 J	< 0.044 U	76 J		< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	5.6	8300	420	< 0.011 U	12	500 J	0.5 J	< 0.042 U	110 J		< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	14	2300	420	0.017 J	15	790	< 0.28 U	< 0.042 U	< 1.1 U		< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	9.3	2300	410	0.015 J	16	720	0.48 J	< 0.045 U	110 J		< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	7.8	2800	830	< 0.012 U	16	510 J	0.52 J	< 0.044 U	110 J		0.23 J
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	13	2300	550	0.013 J	18	670	0.3 J	< 0.046 U	350 J		0.24 J
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	5.4	1700	380	< 0.012 U	11	440 J	< 0.27 U	< 0.04 U	84 J		< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	4.2	8500	360	< 0.011 U	9.3	520	0.48 J	< 0.038 U	180 J		< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	5.9	8500	360	< 0.012 U	12	550	< 0.28 U	< 0.042 U	94 J		< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00 SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated	22	2900	310	< 0.016 U	15		0.8 J	< 0.12 U	230 J		< 0.35 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00 SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated	21	6000	370	< 0.015 U	18		< 0.52 U	< 0.11 U	260 J		< 0.33 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00 SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	42	8300	280	< 0.016 U	16		1 J	< 0.12 U	500 J		< 0.35 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00 SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated	860	20000	440	0.016 J	16		1.5	< 0.1 U	310 J		< 0.32 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00 SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated	8	5500 J	240	< 0.013 U	11		0.8 J	< 0.11 U	120 J		< 0.32 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00 SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated	14	9600	310	< 0.013 U	13		1.1	< 0.11 U	160 J		< 0.32 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30 SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	4600	990	560	0.44	1400	570 J	5.5	0.51 J	860		1.8 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30 SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated	430	6200 J-	310	< 0.016 U	16		0.78 J	< 0.12 U	420 J		< 0.36 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00 SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated	38	3500	270	< 0.017 U	18		0.66 J	< 0.11 U	500 J		< 0.35 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00 SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated	26	2500	300	< 0.017 U	18		1.3	< 0.11 U	360 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00 SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated	10	5100	360	< 0.014 U	17		< 0.5 U	< 0.1 U	< 25 U		< 0.31 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00 SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated	16	3600	490	< 0.014 U	15		< 0.56 U	< 0.11 U	250 J		< 0.35 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated	11	3400	420	< 0.014 U	14	680	< 0.55 U	< 0.11 U	280 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated	11	2600	420	< 0.015 U	14	670	< 0.58 U	< 0.12 U	240 J		< 0.36 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	12	7300	170	0.028 J	20	820	1.6	< 0.034 U	300 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	11	7700	700 J	< 0.034 U	17	670	0.95 J	< 0.034 U	120 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	8.8	9600	510	< 0.034 U	12	610	0.61 J	< 0.034 U	140 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00 SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated	87	4200	330	0.037	24		1.3	< 0.13 U	750		< 0.38 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00 SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated	22	6500 J+	370	< 0.015 UJ	16		< 0.65 U	< 0.13 U	240 J		< 0.4 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00 SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated	5.1	5000	220	< 0.015 U	13		< 0.57 U	< 0.12 U	140 J		< 0.36 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	25	5300	310	0.024 J	19	870	1.1	< 0.034 U	270 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	17	8400	420	< 0.034 U	23	830	0.56 J	< 0.034 U	150 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	9.5	5800	420	< 0.034 U	13	650	< 0.034 U	< 0.034 U	74 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated	21	6200	370	0.02 J	17		0.61 J	< 0.11 U	200 J		< 0.33 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated	20	6500 J-	410	< 0.015 U	18		0.66 J	< 0.11 U	210 J		< 0.34 U

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated			
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15 SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated		13	36
Rear Parking Lot	SSHS-B1500	082218 09:15 SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated		15	31
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated		16	74
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated		10	48
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated		16	30
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated		13	73
Rear Parking Lot	SSHS-W6-3	080118 09:00 W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated		17	100
Rear Parking Lot	SSHS-GS3-4	073118 08:50 G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated		18	56
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated		15	120
Rear Parking Lot	SSHS-N-E-1	080718 09:00 N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated		16	130
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		14	82
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		16	66
Rear Parking Lot	SSHS-EN3-4	073118 08:50 E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated		18	59
Rear Parking Lot	SSHS-SS-02_8_20	SSHS-SS-02_8_20	SSHS-SS-02_8_20	8/20/2018	-	848.51	-	842.58	6-8 ft	5.93 ft	-	Not Excavated		16	45
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated		16	73
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated		9.8	93
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated		17	35
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated		20	39
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated			
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated		14	65
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated		9.9	32
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated		5.7	26
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated		14	87
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated		14	65
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated		18	130
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated		9.9	68
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45 SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated		10	53
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00 SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated		12	54
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00 SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated		11	58
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00 SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated		11	53
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00 SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated		9.3	52
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00 SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated		14	66
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00 SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated		14	64
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00 SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated		12	59
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated		12	57 J+
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated		11	41
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated		10	44
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated		10	77
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated		8.6	42
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated		7.8	53
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated		8.2	49
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated		13	56
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated		12	55
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated		9.9	350
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated		13	59
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated		7.3	46
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated		7.5	36
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated		9.7	120
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00 SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated		14	56
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00 SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated		11	57
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00 SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated		12	59 J+
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00 SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated		11	94
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00 SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated		7.3	48
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00 SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated		8.9	54
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30 SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated		61	1200
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30 SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated		13	50
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00 SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated		14	58
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00 SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated		17	52
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00 SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated		12	88
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00 SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated		13	61
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated		11	53
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated		11	54
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated		13	29
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated		11	47
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated		8.7	40
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00 SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated		16	130
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00 SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated		10	69 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00 SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated		9.4	52
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated		13	60
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated		14	66
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated		8.4	45
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated		11	61
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated		12	72 J-

														Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																13	350	7.2	2.5		30	1		50	
Restricted - Residential																16	400	72	4.3		110	110		270	
Protection of Groundwater																16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity																100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]													
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated	7700	2.5	13	73	0.46	0.23 J	10000	15		7.6	130	26000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated	4800	1.1 J	8.5	66	0.54	0.058 J	2100	7.9		5.1 J	36	17000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated	7900	0.55 J	6.7	62	0.38 J	0.13 J	10000	10		7	32	17000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated	8800	< 0.35 U	6.3	55	0.37 J	0.075 J	20000	11		7.1	20	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated	7000	< 0.35 U	5	62	0.31 J	0.13 J	29000	9.2		5.5	21	14000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated	7800	< 0.36 U	6.3	88	0.38 J	0.2 J	36000	11		6.6	23	15000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated	8200	1.4	9.8	170	0.42	0.17 J	8100 J	24 J		8.3	99	25000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated	7100	0.66 J	7.4	160	0.35 J	0.16 J	37000 J	14 J		6	81	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated	5600	0.43 J	4.5	30	0.25 J	0.059 J	1200	6.6		4.6 J	17	13000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated	5700	0.5 J	8.8	82	0.33 J	0.17 J	750	7.4		5.3	24	18000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated	5800	0.82 J	9.8	130	0.35 J	0.1 J	8700	11		6.9	45	35000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated	6300	< 0.41 U	5.9	38	0.29 J	0.069 J	1800	7.9		5.8 J	19	16000
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated	7400	0.45 J	6.1	39	0.34 J	0.092 J	4700	9.2		5.9	27	18000
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	8800	< 0.034 U	5.7	77	0.36	0.097 J	33000	12		7.1	23	18000
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	8200	< 0.034 U	6.8	72	0.35 J	0.15 J	31000	12		5.9	71	23000
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	8000	0.39 J	6.8	70	0.34 J	0.066 J	21000	11		6.1	23	16000
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	4200	0.43 J	3.2	35	0.14 J	0.079 J	50000	6.4		3.6	18	10000

DRAFT

												Lead	**Magnesium**	**Manganese**	**Mercury**	**Nickel**	**Potassium**	**Selenium**	**Silver**	**Sodium**	**Sulfide**	**Thallium**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												63		1600	0.18	30		3.9	2			
Restricted - Residential												400		2000	0.81	310		180	180			
Protection of Groundwater												450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity												1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated	100	3800	420	0.06	69		1 J	< 0.12 U	360 J		< 0.37 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated	35	970	170	0.02 J	12		1.1 J	< 0.13 U	410 J		< 0.39 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated	25	3000	410	< 0.014 U	18		< 0.58 U	< 0.12 U	260 J		< 0.36 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated	12	5300	430	< 0.015 U	17		0.59 J	< 0.11 U	170 J		< 0.33 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated	21	6400	360	0.062	15		0.64 J	< 0.11 U	160 J		< 0.33 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated	32	5800	420	0.23	18		0.89 J	< 0.11 U	95 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated	130	2500	480	0.061	180 J		0.77 J	< 0.11 U	290 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated	110	2600	350	0.056	46 J		0.97 J	< 0.11 U	300 J		< 0.33 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated	11	1600	270	0.021	13		< 0.5 U	< 0.1 U	65 J		< 0.31 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated	9.5	1400	360	0.012 J	13		< 0.55 U	< 0.11 U	150 J		< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated	350	1900	460	< 0.016 U	55		1.4	< 0.13 U	190 J		< 0.4 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated	9	2100	350	< 0.015 U	14		0.75 J	< 0.13 U	170 J		< 0.38 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated	34	2100	300	0.017 J	26		< 0.56 U	< 0.12 U	110 J		< 0.35 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	20	9500	400	0.071	20	890	0.54 J	< 0.034 U	120 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	42	4300	400	0.027 J	38	770	0.74 J	< 0.034 U	240 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	49	5600	350	0.039	17	890	0.81 J	< 0.034 U	96 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	25	3100	230	0.088	11	400	0.58 J	< 0.069 U	48 J		< 0.19 U

DRAFT

TABLE 6-3B
Subsurface Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated		16	120
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated		14	28
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated		12	64
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated		13	50
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated		12	59
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated		13	71
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated		16	110
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated		12	84
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated		8.9	37
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated		10	78
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated		13	62
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated		10	50
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated		12	50
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated		15	68
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated		16	80
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated		16	80
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated		7.0	42

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAHS**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated			ND		< U		< U				< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated			2.28		< U		0.1 J				0.25 J
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated			2.69		0.092 J		0.11 J				0.21 J
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated			5.36		< U		0.12 J				0.46
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			5.37		< U		0.12 J				0.46
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated			1.0195	< 0.00093 U	0.055	< 0.013 U	0.024	< 0.044 U	< 0.021 U	< 0.028 U	0.062
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated			5.96	< 0.021 U	0.15	< 0.02 U	0.18	< 0.16 U	0.026 J	< 0.045 U	0.52
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated			2.459	< 0.042 U	0.084 J	< 0.039 U	0.055 J	< 0.32 U	< 0.03 U	< 0.09 U	0.23
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated			0.0735	< 0.018 U	< 0.018 U	< 0.053 U	< 0.018 U	< 0.18 U	< 0.039 U	< 0.18 U	0.0059 J
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated			0.115	< 0.018 U	< 0.018 U	< 0.053 U	0.0042 J	< 0.18 U	< 0.039 U	< 0.18 U	0.01 J
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	1.678 - 2.028 f	1.678 - 2.028 ft	1802045421	Not Excavated			0.0037	< 0.018 U	< 0.018 U	< 0.055 U	< 0.018 U	< 0.18 U	< 0.041 U	< 0.18 U	< 0.018 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated			ND	< 0.019 U	< 0.019 U	< 0.056 U	< 0.019 U	< 0.19 U	< 0.041 U	< 0.19 U	< 0.019 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	1.879 - 2.486 f	1.879 - 2.486 ft	1802045921	Not Excavated			0.0268	< 0.018 U	< 0.018 U	< 0.053 U	< 0.018 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.018 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated			0.89	< 0.018 U	< 0.0081 U	< 0.25 U	< 0.018 U	< 0.83 U	< 0.39 U	< 0.53 U	< 0.015 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated			0.0175	< 0.0008 U	< 0.00037 U	< 0.012 U	< 0.00082 U	< 0.038 U	< 0.018 U	< 0.024 U	< 0.00066 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated			2.278	< 0.0035 U	0.042	< 0.05 U	< 0.0035 U	< 0.16 U	< 0.077 U	< 0.1 U	0.17
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 R	< 0.013 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.013 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.013 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated			0.057	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	0.016 J
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated			2.005	< 0.022 U	0.041 J	< 0.021 U	0.063 J	< 0.17 U	< 0.016 U	< 0.047 U	0.2
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated			0.751	< 0.02 U	0.025 J	< 0.019 U	0.019 J	< 0.15 U	< 0.015 U	< 0.044 U	0.076
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated		< 39 U									
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated		< 39 U	ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated		< 39 U	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated		1100	6.224	< 0.022 U	0.27	< 0.02 U	0.2	< 0.16 U	< 0.016 U	< 0.047 U	0.61
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated		550	0.471	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.048 J
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated		13000	2.196	< 0.021 U	0.12	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.16
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated		90	1.453	< 0.024 U	0.035 J	< 0.022 U	0.03 J	< 0.18 U	< 0.017 U	< 0.051 U	0.12
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated		160	2.095	< 0.022 U	0.026 J	< 0.021 U	0.055 J	< 0.17 U	< 0.016 U	< 0.048 U	0.17
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated		450	0.639	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	0.064 J
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated		< 8.3 U	ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated		< 9.2 U	ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.037 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated		67	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated		180	0.099	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated		3100	0.96	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated			10.964	< 0.021 U	0.12	< 0.02 U	0.13	< 0.16 U	< 0.016 U	< 0.046 U	1
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated			2.71	< 0.062 U	< 0.047 U	< 0.059 U	< 0.056 U	< 0.47 U	< 0.045 U	< 0.13 U	0.51
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated			4.4	< 0.019 U	< 0.015 U	< 0.018 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.042 U	1.1
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated			3.31	< 0.06 U	< 0.046 U	< 0.057 U	< 0.054 U	< 0.46 U	< 0.044 U	< 0.13 U	0.71
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated			5.182	< 0.021 U	0.041 J	< 0.02 U	0.061 J	< 0.16 U	< 0.015 U	< 0.045 UT	0.49
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated			1.216	< 0.022 U	0.017 J	< 0.02 U	0.023 J	< 0.16 U	< 0.016 U	< 0.047 U	0.1
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated			0.609	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.064 J
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated			ND	< 0.028 U	< 0.022 U	< 0.18 U	< 0.025 U	< 0.22 U	< 0.18 U	< 0.061 U	< 0.044 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated			11.195	0.26	0.019 J	< 0.034 U	0.5	< 0.16 U	< 0.034 U	< 0.046 U	0.88
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.024 U	< 0.2 U	< 0.034 U	< 0.057 U	< 0.034 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated			0.037	< 0.00084 U	< 0.00039 U	< 0.012 U	< 0.00086 U	< 0.04 U	< 0.019 U	< 0.026 U	< 0.0007 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated			0.6381	< 0.00087 U	< 0.0004 U	< 0.013 U	< 0.00089 U	< 0.041 U	< 0.019 U	< 0.026 U	0.15
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated			ND	< 0.0018 U	< 0.00082 U	< 0.026 U	< 0.0018 U	< 0.084 U	< 0.04 U	< 0.054 U	< 0.0015 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated			1.5	< 0.041 U	< 0.019 U	< 0.6 U	< 0.042 U	< 2 U	< 0.92 U	< 1.2 U	< 0.034 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated			6.33	< 0.042 U	0.22	< 0.039 U	0.19	< 0.32 U	< 0.03 U	< 0.09 U	0.59
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated			ND	< 0.07 U	< 0.07 U	< 0.7 U	< 0.07 U	< 0.7 U	< 0.34 U	< 0.7 U	< 0.07 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated			0.489	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	0.046 J
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated		57									
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated		72									
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated		46 J	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated		1200	ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated		970	4.145	0.028 J	0.079	< 0.019 U	0.13	< 0.15 U	< 0.015 U	< 0.043 U	0.37
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated		1000	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated		1100	2.071	< 0.021 U	0.062 J	< 0.019 U	0.058 J	< 0.16 U	< 0.015 U	< 0.044 U	0.2
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated		1200	3.812	< 0.021 U	0.026 J	< 0.02 U	0.085	< 0.16 U	< 0.015 U	< 0.045 U	0.33
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated		11000	1.076	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.12
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated		12000	2.09	< 0.022 U	< 0.017 U	< 0.02 U	0.31	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated		550	0.081	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated		360	0.959	< 0.033 U	< 0.025 U	< 0.031 U	< 0.03 U	< 0.25 U	< 0.024 U	< 0.071 U	0.095 J
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated		1400	ND	< 0.031 U	< 0.024 U	< 0.03 U	< 0.028 U	< 0.24 U	< 0.023 U	< 0.068 U	< 0.049 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated		800 T	1.118	< 0.021 U	< 0.016 U	< 0.019 U	0.032 J	< 0.16 U	< 0.015 U	< 0.044 U	0.091
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated		12 J	ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated		340	1.013	< 0.021 U	< 0.016 U	< 0.02 U	0.026 J	< 0.16 U	< 0.016 U	< 0.046 U	0.09
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated		28000	5.05	< 0.092 U	< 0.07 U	< 0.087 U	0.53	< 0.7 U	< 0.067 U	< 0.2 U	0.22 J
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated			3	< 0.069 U	< 0.053 U	< 0.065 U	< 0.062 U	< 0.53 U	< 0.05 U	< 0.15 U	0.58
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated			0.88	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.22
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated			2.839	< 0.021 U	0.064 J	< 0.02 U	0.065 J	< 0.16 U	< 0.016 U	< 0.046 U	0.24

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U	< U	< U	< U				1.1		
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U	< U	< U	< U				1.1		
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.22 J	0.31 J	0.12 J	0.15 J				0.57		
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.29 J	0.47	0.18 J	0.23 J				0.53		
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.47	0.63	0.26 J	0.36				0.68		
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	0.47	0.63	0.26 J	0.36				0.68		
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	0.07	0.11	0.053	0.12	< 0.015 U	< 0.015 U	< 0.012 U	< 0.062 U	< 0.017 U	< 0.027 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	0.53	0.6	0.24	0.56	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	0.26	0.32	0.11 J	0.23	< 0.034 U	< 0.026 U	< 0.053 U	< 0.77 U	< 0.05 U	< 0.5 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0091 J	0.01 J	0.0036 J	0.0088 J	< 0.039 U	< 0.039 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0097 J	0.013 J	0.0048 J	0.0077 J	< 0.039 U	< 0.039 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.018 U	0.0037 J	< 0.018 U	< 0.018 U	< 0.041 U	< 0.041 U	< 0.048 U	< 0.18 U	< 0.041 U	< 0.18 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.192 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.019 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.041 U	< 0.041 U	< 0.049 U	< 0.19 U	< 0.041 U	< 0.19 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	0.0051 J	0.0056 J	< 0.018 U	0.0054 J	< 0.039 U	< 0.039 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.015 U	< 0.014 U	< 0.016 U	< 0.0081 U	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.32 U	< 0.51 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.00067 U	< 0.00062 U	< 0.00072 U	< 0.00037 U	< 0.013 U	< 0.013 U	< 0.011 U	< 0.054 U	< 0.015 U	< 0.023 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	0.23	0.27	0.12	0.15	< 0.055 U	< 0.055 U	< 0.045 U	< 0.23 U	< 0.064 U	< 0.1 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	0.18	0.22	0.07 J	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	0.066 J	0.073	0.032 J	0.054 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated										
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	0.6	0.71	0.21	0.42	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 UT
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	0.049 J	0.06 J	< 0.021 U	0.04 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 UT
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	0.14	0.17	0.053 J	0.15	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	0.15	0.17	0.089	0.19	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	0.045 J	0.052 J	0.039 J	0.072 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	1.2	1.3	0.37	0.98	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.094 U	< 0.053 U	< 0.065 U	< 0.047 U	< 0.051 U	< 0.039 U	< 0.08 U	< 1.1 U	< 0.075 U	< 0.74 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.091 U	< 0.052 U	< 0.063 U	< 0.045 U	< 0.05 U	< 0.038 U	< 0.078 U	< 1.1 U	< 0.073 U	< 0.72 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	0.59	0.57	0.24	0.4	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	0.12	0.14	0.06 J	0.087	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	0.082	0.068 J	0.046 J	0.075	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.043 U	< 0.024 U	< 0.029 U	< 0.021 U	< 0.18 U	< 0.018 U	< 0.036 U	< 0.52 U	< 0.21 U	< 0.34 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	0.55	0.71	0.27	0.42	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.19 U	< 0.034 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.00071 U	< 0.00065 U	< 0.00075 U	< 0.00039 U	< 0.013 U	< 0.013 U	< 0.011 U	0.064 J	< 0.016 U	< 0.024 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	0.021	0.02	< 0.00078 U	0.0091	< 0.014 U	< 0.014 U	< 0.011 U	0.077 J	< 0.016 U	< 0.025 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0015 U	< 0.0014 U	< 0.0016 U	< 0.00082 U	< 0.028 U	< 0.028 U	< 0.023 U	< 0.12 U	< 0.033 U	< 0.051 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.035 U	< 0.032 U	< 0.037 U	< 0.019 U	< 0.65 U	< 0.65 U	< 0.54 U	< 2.8 U	< 0.76 U	< 1.2 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	0.53	0.71	0.24	0.51	< 0.035 U	< 0.026 U	< 0.054 U	< 0.77 U	< 0.051 U	< 0.5 U
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.07 U	< 0.07 U	< 3.4 U	< 0.34 U	< 0.34 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	0.044 J	0.051 J	< 0.023 U	0.041 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated										
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated										
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	0.32	0.39	0.13	0.3	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 UT
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	0.2	0.2	0.086	0.16	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 UT
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	0.37	0.35	0.21	0.3	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	0.065 J	0.094 J	0.036 J	0.11	< 0.027 U	< 0.021 U	< 0.042 U	< 0.61 U	< 0.04 U	< 0.39 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.047 U	< 0.027 U	< 0.033 U	< 0.024 U	< 0.026 U	< 0.02 U	< 0.04 U	< 0.58 U	< 0.038 U	< 0.37 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	0.096	0.093	0.047 J	0.092	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	0.091	0.087	0.052 J	0.084	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 0.14 U	< 0.079 U	< 0.096 U	< 0.069 U	< 0.076 U	< 0.058 U	< 0.12 U	< 1.7 U	< 0.11 U	< 1.1 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.1 U	< 0.059 U	< 0.072 U	< 0.052 U	< 0.057 U	< 0.044 U	< 0.089 U	< 1.3 U	< 0.084 U	< 0.83 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	0.24	0.35	0.088	0.24	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							< U		
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							< U		
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							0.22 J		
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							0.25 J		
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							0.44		
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							0.44		
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.092 U	< 0.023 U	< 0.037 U	< 0.055 U	< 0.017 U	< 0.012 U	< 0.017 U	0.083	< 0.00081 U	0.032 J
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.24 U	0.046 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.5	0.13	0.059 J
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.47 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.044 U	0.26	< 0.092 U	< 0.032 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U	< 0.039 U	< 0.18 U	< 0.053 U	< 0.036 U	< 0.039 U	< 0.039 U	0.0073 J	< 0.018 U	< 0.039 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U	< 0.039 U	< 0.18 U	< 0.053 U	< 0.036 U	< 0.039 U	< 0.039 U	0.0090 J	< 0.018 U	< 0.039 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.18 U	< 0.041 U	< 0.18 U	< 0.055 U	< 0.037 U	< 0.041 U	< 0.041 U	< 0.018 U	< 0.018 U	< 0.041 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.19 U	< 0.041 U	< 0.19 U	< 0.056 U	< 0.037 U	< 0.041 U	< 0.041 U	< 0.019 U	< 0.019 U	< 0.041 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.18 U	< 0.039 U	< 0.18 U	< 0.053 U	< 0.035 U	< 0.039 U	< 0.039 U	< 0.018 U	< 0.018 U	< 0.039 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 1.7 U	< 0.44 U	< 0.69 U	< 1 U	< 0.32 U	< 0.23 U	< 0.32 U	< 0.025 U	< 0.015 U	< 0.3 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.079 U	< 0.02 U	< 0.032 U	< 0.047 U	< 0.015 U	< 0.011 U	< 0.015 U	< 0.0012 U	< 0.0007 U	< 0.014 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.34 U	< 0.086 U	< 0.14 U	< 0.2 U	< 0.064 U	< 0.045 U	< 0.064 U	0.22	< 0.003 U	< 0.059 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.015 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.015 U	< 0.015 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.015 U	< 0.015 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	< 0.25 U	0.019 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.22	0.034 J	< 0.017 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.081	< 0.045 U	< 0.015 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated										
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.048 U	< 0.016 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	< 0.25 U	0.056 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.62	0.12	0.018 J
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.062 J	< 0.045 U	< 0.015 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.56	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.13	< 0.052 U	< 0.018 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.25 U	0.026 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.16	< 0.05 U	< 0.017 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.068 J	< 0.055 U	< 0.019 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 0.26 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.018 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.24 U	0.04 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.93	0.21	< 0.016 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.7 U	< 0.051 U	< 0.073 U	< 0.051 U	< 0.05 U	< 0.05 U	< 0.065 U	1.2	< 0.14 U	< 0.047 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	2.1	< 0.043 U	< 0.015 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.68 U	< 0.049 U	< 0.071 U	< 0.049 U	< 0.048 U	< 0.049 U	< 0.064 U	1.5	< 0.13 U	< 0.046 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.46	0.085	< 0.016 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.068 J	< 0.047 U	< 0.016 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.32 U	< 0.023 U	< 0.13 U	< 0.17 U	< 0.023 U	< 0.18 U	< 0.16 U	< 0.055 U	< 0.063 U	< 0.18 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.24 U	0.15	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.85	0.12	< 0.14 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.3 U	< 0.034 U	< 0.12 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.051 U	< 0.034 U	< 0.17 U	
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.0012 U	< 0.00073 U	< 0.014 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.086 U	< 0.022 U	< 0.034 U	< 0.052 U	< 0.016 U	< 0.011 U	< 0.016 U	0.26	< 0.00076 U	< 0.015 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.18 U	< 0.044 U	< 0.07 U	< 0.11 U	< 0.033 U	< 0.023 U	< 0.033 U	< 0.0026 U	< 0.0015 U	< 0.03 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 4.1 U	< 1 U	< 1.6 U	< 2.4 U	< 0.76 U	< 0.54 U	< 0.76 U	< 0.06 U	< 0.036 U	< 0.71 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.47 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.044 U	0.68	< 0.032 U	0.057 J
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	< 1.8 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.07 U	< 0.07 U	< 0.34 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	< 0.24 U	< 0.018 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.086	< 0.017 U	< 0.016 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated										
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated										
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.048 U	< 0.016 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U	< 0.018 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.23 U	0.033 J	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.42	0.075	0.032 J
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.23	< 0.046 U	< 0.016 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	< 0.24 U	0.033 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.33	0.055 J	< 0.016 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.51	< 0.049 U	< 0.017 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.37 U	< 0.027 U	< 0.039 U	< 0.027 U	< 0.026 U	< 0.027 U	< 0.035 U	0.084 J	< 0.073 U	< 0.025 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.35 U	< 0.026 U	< 0.037 U	< 0.026 U	< 0.025 U	< 0.025 U	< 0.033 U	< 0.061 U	< 0.07 U	< 0.024 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.12	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	< 0.24 U	0.023 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.1	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 1 U	< 0.075 U	< 0.11 U	< 0.075 U	< 0.073 U	< 0.074 U	< 0.097 U	2	< 0.2 U	< 0.07 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.78 U	< 0.056 U	< 0.082 U	< 0.057 U	< 0.055 U	< 0.056 U	< 0.073 U	1.3	< 0.15 U	< 0.053 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.44	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.24 U	0.032 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.27	< 0.048 U	0.02 J

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					
Restricted - Residential																					
Protection of Groundwater																					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated										
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated										
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated										
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated										
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated										
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated										
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.053 U	< 0.054 U	< 0.038 U	< 0.049 U	< 0.017 U	< 0.027 U	< 0.034 U	< 0.098 U	< 0.068 U	< 0.17 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.67 U	< 0.056 U	< 0.25 U	< 0.045 U	< 0.053 U	< 0.32 U	< 0.42 U	< 1.2 U	< 0.045 U	< 4 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.36 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.53 U	< 0.039 U	< 1.1 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.36 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.53 U	< 0.039 U	< 1.1 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.37 U	< 0.048 U	< 0.18 U	< 0.041 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.55 U	< 0.041 U	< 1.1 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.37 U	< 0.049 U	< 0.19 U	< 0.041 U	< 0.19 U	< 0.19 U	< 0.19 U	< 0.56 U	< 0.041 U	< 1.1 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.35 U	< 0.046 U	< 0.18 U	< 0.039 U	< 0.18 U	< 0.18 U	< 0.18 U	< 0.53 UT	< 0.039 U	< 1.1 UT
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.32 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.045 U	< 0.046 U	< 0.033 U	< 0.042 U	< 0.015 U	< 0.023 U	< 0.03 U	< 0.084 U	< 0.059 U	< 0.15 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.2 U	< 0.2 U	< 0.14 U	< 0.18 U	< 0.064 U	< 0.1 U	< 0.13 U	< 0.36 U	< 0.25 U	< 0.64 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 0.95 UJ
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.96 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 0.93 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 0.93 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated										
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.33 U	< 0.027 U	0.12 J	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 2.3 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U	< 2.4 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 2.2 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.2 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 1 U	< 0.083 U	< 0.38 U	< 0.067 U	< 0.08 U	< 0.47 U	< 0.63 U	< 1.9 U	< 0.067 U	< 6 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U	< 1.9 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.98 U	< 0.081 U	< 0.37 U	< 0.065 U	< 0.078 U	< 0.46 U	< 0.61 U	< 1.8 U	< 0.065 U	< 5.8 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 UT
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.46 U	< 0.038 U	< 0.17 U	< 0.17 U	< 0.19 U	< 0.22 U	< 0.29 U	< 0.85 U	< 0.19 U	< 3.1 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.15 U	< 0.18 U	< 0.034 U	< 0.27 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.048 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.016 U	< 0.024 U	< 0.031 U	< 0.089 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.049 U	< 0.05 U	< 0.035 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.064 U	< 0.16 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.1 U	< 0.1 U	< 0.072 U	< 0.093 U	< 0.033 U	< 0.051 U	< 0.065 U	< 0.19 U	< 0.13 U	< 0.33 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 2.3 U	< 2.4 U	< 1.7 U	< 2.2 U	< 0.76 U	< 1.2 U	< 1.5 U	< 4.3 U	< 3 U	< 7.7 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.68 U	< 0.056 U	< 0.25 U	< 0.045 U	< 0.026 U	< 0.32 U	< 0.42 U	< 1.3 U	< 0.045 U	< 2 U
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	< 0.34 U	< 0.07 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U	< 1.8 U	< 0.34 U	< 3.4 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated										
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated										
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.53 U	< 0.044 U	< 0.2 U	< 0.036 U	< 0.042 U	< 0.25 U	< 0.33 U	< 0.99 U	< 0.035 U	< 3.2 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.51 U	< 0.042 U	< 0.19 U	< 0.034 U	< 0.04 U	< 0.24 U	< 0.32 U	< 0.94 U	< 0.034 U	< 3 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 1.5 U	< 0.12 U	< 0.56 U	< 0.099 U	< 0.12 U	< 0.7 U	< 0.93 U	< 2.8 U	< 0.099 U	< 8.9 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 1.1 U	< 0.093 U	< 0.42 U	< 0.075 U	< 0.089 U	< 0.53 U	< 0.7 U	< 2.1 U	< 0.074 U	< 6.7 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					< U					
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					< U					
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					0.46					
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					0.31 J					
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					I					
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated					I					
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.076 U			< 0.018 U	0.11	0.0045 J	< 0.0026 U	< 0.015 U	< 0.076 U	< 0.011 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.055 U			< 0.11 U	0.85	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.11 U			< 0.22 U	0.33	< 0.028 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U		< 0.18 U		0.0091 J	< 0.018 U	< 0.036 U	< 0.053 U	< 0.53 U	< 0.18 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.18 U		< 0.18 U		0.019	< 0.018 U	< 0.036 U	< 0.053 U	< 0.53 U	< 0.18 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.18 U		< 0.18 U		< 0.018 U	< 0.018 U	< 0.037 U	< 0.055 U	< 0.55 UT	< 0.18 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.19 U		< 0.19 U		< 0.019 U	< 0.019 U	< 0.037 U	< 0.056 U	< 0.56 UT	< 0.19 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.18 U		< 0.18 U		0.0046 J	< 0.018 U	< 0.035 U	< 0.053 U	< 0.53 UT	< 0.18 UT
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 1.4 U			< 0.35 U	< 0.013 U	< 0.012 U	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.065 U			< 0.016 U	< 0.00058 U	< 0.00056 U	< 0.0022 U	< 0.013 U	< 0.065 U	< 0.0095 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.28 U			< 0.068 U	0.27	< 0.0024 U	< 0.0095 U	< 0.055 U	< 0.28 U	< 0.041 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.017 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.017 U			< 0.11 U	0.019 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	< 0.019 U			< 0.12 U	0.27	0.016 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.053 U			< 0.11 U	0.096	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated										
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	< 0.057 U	< 0.12 U			0.95	0.036 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.053 U	< 0.11 U			0.068 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	0.14	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.062 U	< 0.13 U			0.22	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.058 U	< 0.12 U			0.26	0.016 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.065 U	< 0.13 U			0.061 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 0.058 U	< 0.12 U			0.035 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.056 U	< 0.12 U			1.9	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.16 U	< 0.34 U			< 0.057 U	< 0.042 U	< 0.077 U	< 0.063 U	< 0.11 U	< 0.056 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.051 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.16 U	< 0.33 U			< 0.055 U	< 0.041 U	< 0.075 U	< 0.061 U	< 0.11 U	< 0.054 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.055 U	< 0.11 UT			0.87	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.057 U	< 0.12 U			0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.056 U	< 0.12 U			0.076	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.29 U	< 0.15 U			< 0.026 U	< 0.019 U	< 0.035 U	< 0.029 U	< 0.05 U	< 0.17 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.11 U	1.9	0.22	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.27 U			< 0.14 U	< 0.024 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.069 U			< 0.017 U	< 0.00061 U	< 0.00059 U	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.071 U			< 0.017 U	< 0.00063 U	< 0.00061 U	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.14 U			< 0.035 U	< 0.0013 U	< 0.0012 U	< 0.0049 U	< 0.028 U	< 0.14 U	< 0.021 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 3.4 U			< 0.81 U	< 0.03 U	< 0.029 U	< 0.11 U	< 0.65 U	< 3.4 U	< 0.49 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.036 U			< 0.23 U	0.99	< 0.029 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	< 0.34 U	< 0.7 U			< 0.07 U	< 0.07 U	< 0.07 U	< 0.07 U	< 0.34 U	< 0.34 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	< 0.019 U			< 0.12 U	0.06 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated										
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated										
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.021 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.053 U	< 0.11 U			0.54	0.035 J	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	< 0.054 U	< 0.11 U			0.24	0.017 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	< 0.055 U	< 0.11 U			0.63	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.057 U	< 0.12 U			0.28	0.14	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.056 U	< 0.12 U			0.034 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.086 U	< 0.18 U			0.094 J	< 0.022 U	< 0.041 U	< 0.033 U	< 0.058 U	< 0.029 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.082 U	< 0.17 U			< 0.029 U	< 0.021 U	< 0.039 U	< 0.032 U	< 0.056 U	< 0.028 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.054 U	< 0.11 U			0.12	0.019 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	< 0.056 U	< 0.12 U			0.16	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 0.24 U	< 0.5 U			< 0.084 U	< 0.063 U	< 0.11 U	< 0.093 U	< 0.16 U	< 0.082 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.18 U	< 0.37 U			0.35	< 0.047 U	< 0.086 U	< 0.07 U	< 0.12 U	< 0.062 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.056 U	< 0.12 U			< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.056 U	< 0.12 U			0.44	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U

DRAFT

												Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.5	0.33				0.33	12			
Restricted - Residential												0.5	100				100	100			
Protection of Groundwater												8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U									
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated	< U									
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.14 J									
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.2 J									
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated	0.31 J									
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated	0.31 J									
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	0.076	< 0.038 U	< 0.035 U	< 0.015 U	0.037		0.14	< 0.049 U	< 0.06 U	< 0.073 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	0.44	< 0.1 U	< 0.11 U	< 0.019 U	0.068 J		0.15	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	0.18	< 0.21 U	< 0.21 U	< 0.037 U	< 0.035 U		0.034 J	< 0.33 U	< 0.18 U	< 0.035 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0059 J	< 0.053 U		< 0.071 U	0.0060 J		0.0095 J	< 0.053 U	< 0.18 U	< 0.18 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0086 J	< 0.053 U		< 0.071 U	< 0.018 U		< 0.018 U	< 0.053 U	< 0.18 U	< 0.18 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.018 U	< 0.055 U		< 0.074 U	< 0.018 U		< 0.018 U	< 0.055 U	< 0.18 U	< 0.18 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.019 U	< 0.056 U		< 0.075 U	< 0.019 U		< 0.019 U	< 0.056 U	< 0.19 U	< 0.19 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.018 U	< 0.053 U		< 0.071 U	< 0.018 U		< 0.018 U	< 0.053 U	< 0.18 U	< 0.18 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0081 U	< 0.72 U	< 0.67 U	< 0.28 U	1.5		< 0.019 U	< 0.93 U	< 1.1 U	< 1.4 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.00037 U	< 0.033 U	< 0.031 U	< 0.013 U	< 0.00053 U		< 0.00086 U	< 0.042 U	< 0.052 U	< 0.063 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	0.13	< 0.14 U	< 0.13 U	< 0.055 U	0.076		0.098	< 0.18 U	< 0.22 U	< 0.27 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U	< 0.017 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.014 U	< 0.099 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.017 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	0.11	< 0.11 U	< 0.11 U	< 0.019 U	0.027 J		0.032 J	< 0.17 U	< 0.097 U	< 0.019 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	0.047 J	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated										
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 UT	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	0.34	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.028 J	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	0.081	< 0.11 U	0.086	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	0.12	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	0.053 J	< 0.19 U	< 0.1 U	< 0.02 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	0.12	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	0.035 J	< 0.18 U	< 0.098 U	< 0.019 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	0.05 J	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	0.017 J	< 0.2 U	< 0.11 U	< 0.021 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 UT	< 0.1 U	< 0.02 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 UT	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 0.04 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 UT	< 0.1 U	< 0.019 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	0.72	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.044 J	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.11 U	< 0.31 U		< 0.055 U	< 0.052 U	< 0.32 U	< 0.042 U	< 0.49 U	< 0.27 U	< 0.052 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.034 U	< 0.097 U		< 0.017 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.016 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.1 U	< 0.3 U		< 0.054 U	< 0.05 U	< 0.31 U	< 0.041 U	< 0.48 U	< 0.27 U	< 0.051 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	0.31	< 0.1 U		< 0.018 U	0.018 J	< 0.11 U	0.026 J	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	0.066 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.049 U	< 0.14 U		< 0.18 U	< 0.024 U	< 0.14 U	< 0.019 U	< 0.22 U	< 0.12 U	< 0.18 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	0.36	< 0.034 U	< 0.034 U	< 0.034 U	0.048 J		0.055 J	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.17 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.00039 U	< 0.034 U	< 0.032 U	< 0.013 U	< 0.00055 U		< 0.00091 U	< 0.044 U	< 0.054 U	< 0.067 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0004 U	< 0.035 U	< 0.033 U	< 0.014 U	< 0.00057 U		< 0.00094 U	< 0.046 U	< 0.056 U	< 0.069 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.00082 U	< 0.072 U	< 0.068 U	< 0.028 U	< 0.0012 U		< 0.0019 U	< 0.093 U	< 0.11 U	< 0.14 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.019 U	< 1.7 U	< 1.6 U	< 0.65 U	1.6		< 0.044 U	< 2.2 U	< 2.7 U	< 3.3 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	0.39	< 0.21 U	< 0.21 U	< 0.037 U	0.054 J		0.11 J	< 0.33 U	< 0.18 U	< 0.035 U
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	< 0.07 U	< 0.34 U		< 0.34 U	< 0.07 U	< 0.34 U	< 0.07 U	< 1.8 U	< 1.8 U	< 1.8 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	0.037 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated										
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated										
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 UT	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	0.21	< 0.1 U		< 0.018 U	0.058 J	< 0.1 U	0.087	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	0.12	< 0.1 U		< 0.018 U	0.031 J	< 0.11 U	0.04 J	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	0.22	< 0.1 U		< 0.019 U	0.022 J	< 0.11 U	0.022 J	< 0.17 U	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	0.03 J	< 0.11 U	0.036 J	< 0.17 U	< 0.097 U	< 0.018 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	0.064 J	< 0.11 U	0.07 J	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.015 J	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	0.084 J	< 0.16 U		< 0.029 U	0.034 J	< 0.17 U	0.045 J	< 0.26 U	< 0.15 U	< 0.028 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.054 U	< 0.16 U		< 0.028 U	< 0.026 U	< 0.16 U	< 0.021 U	< 0.25 U	< 0.14 U	< 0.026 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	0.076	< 0.1 U		< 0.018 U	0.019 J	< 0.11 U	0.022 J	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	0.056 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.017 J	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 0.16 U	< 0.46 U		< 0.081 U	< 0.077 U	< 0.47 U	< 0.062 U	< 0.73 UT	< 0.41 U	< 0.078 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.12 U	< 0.34 U		< 0.061 U	< 0.058 U	< 0.35 U	< 0.047 U	< 0.55 U	< 0.31 U	< 0.058 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	0.18	< 0.11 U		< 0.019 U	0.029 J	< 0.11 U	0.056 J	< 0.17 U	< 0.095 U	< 0.018 U

DRAFT

													Nitrobenzene	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								< U		< U
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								< U		< U
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.31 J		
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.1 J		0.34 J
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								0.47		0.84
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								0.47		0.84
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.016 U	< 0.016 U	< 0.11 U		< 0.013 U	< 0.015 U	< 0.071 U	0.079	0.015 J	0.088
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.42	< 0.11 U	0.84
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.26 U	< 0.11 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.11 J	< 0.22 U	0.34
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.039 U	< 0.053 U	< 0.53 U		< 0.071 U	< 0.039 U	< 0.18 U	0.0051 J	< 0.039 U	0.0087 J
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.039 U	< 0.053 U	< 0.53 U		< 0.071 U	< 0.039 U	< 0.18 U	0.012 J	< 0.039 U	0.017 J
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.041 U	< 0.055 U	< 0.55 U		< 0.074 U	< 0.041 U	< 0.18 U	< 0.018 U	< 0.041 U	< 0.018 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.041 U	< 0.056 U	< 0.56 U		< 0.075 U	< 0.041 U	< 0.19 U	< 0.019 U	< 0.041 U	< 0.019 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.039 U	< 0.053 U	< 0.53 U		< 0.071 U	< 0.039 U	< 0.18 U	< 0.018 U	< 0.039 U	0.0061 J
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.3 U	< 0.3 U	< 2.2 U		< 0.25 U	< 0.28 U	< 1.3 U	0.58	< 0.19 U	0.31
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.014 U	< 0.014 U	< 0.099 U		< 0.012 U	< 0.013 U	< 0.061 U	0.0055 J	< 0.0084 U	0.012
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.059 U	< 0.059 U	< 0.43 U		< 0.05 U	< 0.055 U	< 0.26 U	0.27	< 0.036 U	0.35
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U	0.022 J
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 UJ		< 0.026 U	< 0.13 U	< 0.61 U	0.15	< 0.12 U	0.31
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.077	< 0.11 U	0.13
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated										
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.51	< 0.11 U	0.87
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.061 J	< 0.11 U	0.083
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.8	< 0.11 U	0.45
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.087	< 0.12 U	0.18
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.24	< 0.12 U	0.44
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.061 J	< 0.13 U	0.11
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 0.15 U	< 0.065 U	< 0.28 UT		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 UT		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.028 J	< 0.12 U	0.036 J
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 UT		< 0.027 U	< 0.13 U	< 0.64 U	0.96	< 0.12 U	< 0.019 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.28	< 0.11 U	1.9
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.39 U	< 0.17 U	< 0.76 U		< 0.073 U	< 0.36 U	< 1.7 U	< 0.058 U	< 0.33 U	1
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	1.2
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.38 U	< 0.17 U	< 0.74 U		< 0.071 U	< 0.35 U	< 1.7 U	< 0.056 U	< 0.32 U	1.1
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.18	< 0.11 U	0.9
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.11	< 0.11 U	0.19
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.049 J	< 0.11 U	0.081 B
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.18 U	< 0.18 U	< 0.34 U		< 0.033 U	< 0.16 U	< 0.79 U	< 0.026 U	< 0.15 U	< 0.023 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	2.3	< 0.11 U	1.8
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.32 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.022 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.064 U	< 0.00081 U	< 0.0089 U	0.037
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.018	< 0.0092 U	0.16
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.03 U	< 0.03 U	< 0.22 U		< 0.026 U	< 0.028 U	< 0.14 U	< 0.0017 U	< 0.019 U	< 0.001 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.71 U	< 0.71 U	< 5.1 U		< 0.6 U	< 0.65 U	< 3.1 U	1.5	< 0.43 U	< 0.024 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.27 U	< 0.12 U	< 0.51 U		< 0.049 U	< 0.24 U	< 1.2 U	0.49	< 0.22 U	0.9
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated	< 0.7 U	< 0.34 U	< 1.8 UJ		< 0.07 U	< 0.34 U	< 1.8 U	< 0.07 U	< 0.34 U	< 0.07 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 UJ		< 0.025 U	< 0.12 U	< 0.6 U	0.048 J	< 0.11 U	0.076
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated										
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated										
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.43	< 0.11 U	0.68
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.21	< 0.11 U	0.31
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.32	< 0.11 U	0.59
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.41	< 0.12 U	< 0.018 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.79	< 0.11 U	0.5
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.032 J
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.21 U	< 0.091 U	< 0.4 U		< 0.039 U	< 0.19 U	< 0.92 U	0.082 J	< 0.17 U	0.17
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.2 U	< 0.087 U	< 0.38 U		< 0.037 U	< 0.18 U	< 0.88 U	< 0.029 U	< 0.17 U	< 0.026 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.13	< 0.11 U	0.18
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.1	< 0.11 U	0.15
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 0.58 U	< 0.25 U	< 1.1 UT		< 0.11 U	< 0.53 U	< 2.6 U	2.3	< 0.48 U	< 0.076 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.44 U	< 0.19 U	< 0.84 U		< 0.081 U	< 0.4 U	< 1.9 U	< 0.065 U	< 0.36 U	0.77
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.22
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.24	< 0.11 U	0.43

DRAFT

												Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																
Restricted - Residential																
Protection of Groundwater																
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated					
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated					
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated					
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated		< 0.017 U	< 0.36 U	< 0.084 U	< 0.078 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated		< 0.031 U	< 0.3 U	< 0.051 U	< 0.04 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1-20260424	SSHS-IRM5-SND-DUP1	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		< 0.039 U	< 0.18 U	< 0.039 U	< 0.039 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3-20260424	SSHS-IRM5-SND-SCV3	4/24/2026	855.602	855.602	0.00	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated		< 0.039 U	< 0.18 U	< 0.039 U	< 0.039 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4-20260423	SSHS-IRM5-SND-SCV4	4/23/2026	855.378	855.378	0.00	-	.678 - 2.028 f	1.678 - 2.028 ft	1802045421	Not Excavated		< 0.041 U	< 0.18 U	< 0.041 U	< 0.041 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5-20260423	SSHS-IRM5-SND-SCV5	4/23/2026	854.796	854.796	0.00	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated		< 0.041 U	< 0.19 U	< 0.041 U	< 0.041 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6-20260424	SSHS-IRM5-SND-SCV6	4/24/2026	855.395	855.395	0.00	-	.879 - 2.486 f	1.879 - 2.486 ft	1802045921	Not Excavated		< 0.039 U	< 0.18 U	< 0.039 U	< 0.039 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated		< 0.32 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated		< 0.015 U	< 0.31 U	< 0.073 U	< 0.067 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated		< 0.064 U	< 1.3 U	< 0.31 U	< 0.29 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated					
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated		< 0.047 U	< 0.45 U	< 0.077 U	< 0.059 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated		< 0.045 U	< 0.44 U	< 0.075 U	< 0.058 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated		< 0.19 U	< 0.2 U	< 0.17 U	< 0.16 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated		< 0.016 U	< 0.32 U	< 0.077 U	< 0.071 U
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated		< 0.016 U	< 0.34 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated		< 0.033 U	< 0.68 U	< 0.16 U	< 0.15 U
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated		< 0.76 U	< 16 U	< 3.7 U	< 3.5 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated		< 0.031 U	< 0.3 U	< 0.052 U	< 0.04 U
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated		< 0.34 U	< 0.34 U	< 0.34 U	< 0.34 U
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated					
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated					
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated		< 0.025 U	< 0.24 U	< 0.041 U	< 0.031 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated		< 0.024 U	< 0.23 U	< 0.039 U	< 0.03 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated		< 0.069 U	< 0.67 U	< 0.11 U	< 0.088 U
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated		< 0.052 U	< 0.5 U	< 0.086 U	< 0.066 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated			11.809	0.26	0.028 J	< 0.034 U	0.51	< 0.16 U	< 0.034 U	< 0.045 U	0.96
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.042 U	< 0.034 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 R	< 0.014 U
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated			0.714	0.041 J	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 R	0.13
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated			2078.3	12	32	< 0.81 U	110	< 6.5 U	2.4 J	< 1.8 U	170
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated			0.088	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated			1.451	< 0.022 U	< 0.017 U	< 0.021 U	0.027 J	< 0.17 U	< 0.016 U	< 0.047 U	0.11
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated			0.717	< 0.022 U	0.024 J	< 0.021 U	0.022 J	< 0.17 U	< 0.016 U	< 0.048 U	0.042 J
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated		840	0.886	< 0.021 U	0.018 J	< 0.02 U	0.022 J	< 0.16 U	< 0.016 U	< 0.046 U	0.086
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated		< 39 U	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated		890 T	ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated		570	1.771	< 0.02 U	0.044 J	< 0.019 U	0.055 J	< 0.15 U	< 0.015 U	< 0.044 U	0.17
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated		520	0.538	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.052 J
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated		15000	2.668	< 0.021 U	0.11	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.09
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated		10000	2.762	< 0.021 U	< 0.016 U	< 0.02 U	0.14	< 0.16 U	< 0.015 U	< 0.045 U	0.15
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated		660	2.341	< 0.021 U	0.052 J	< 0.02 U	0.058 J	< 0.16 U	< 0.015 U	< 0.045 U	0.19
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated		700	1.692	< 0.021 U	0.033 J	< 0.02 U	0.034 J	< 0.16 U	< 0.015 U	< 0.045 U	0.15
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated		12000	6.1	< 0.084 U	< 0.064 U	< 0.079 U	0.47	< 0.64 U	< 0.061 U	< 0.18 U	0.32
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated		12000	5.2	< 0.082 U	< 0.063 U	< 0.078 U	0.41	< 0.63 U	< 0.06 U	< 0.18 U	0.29
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated			0.056	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated			20.06	0.45	0.056 J	< 0.034 U	0.89	< 0.16 U	< 0.034 U	< 0.046 U	1.6
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated			0.29	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.033 J
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			ND	< 0.41 U	< 0.41 U		< 0.41 U				< 0.41 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			0.745	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.18 J
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			0.328	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.072 J
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated			0.5	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.11
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated			2.69	< 0.0021 U	0.063	< 0.031 U	0.049	< 0.1 U	< 0.048 U	< 0.065 U	0.24
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated			0.6236	0.0041 J	0.014	< 0.013 U	0.015	< 0.041 U	< 0.019 U	< 0.026 U	0.051
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated			0.367	< 0.00085 U	0.012	< 0.012 U	0.01	< 0.04 U	< 0.019 U	< 0.026 U	0.032
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated			0.168	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.05 U	0.018 J
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated			0.157	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated			19.314	0.039 J	0.036 J	< 0.019 U	0.29	< 0.16 U	< 0.015 U	< 0.044 U	2.3
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated			6.281	< 0.021 U	0.052 J	< 0.02 U	0.1	< 0.16 U	< 0.015 U	< 0.045 U	0.62
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated			0.262	< 0.022 U	< 0.017 U	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated			0.621	< 0.021 U	0.021 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.06 J
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated		530	4.026	< 0.021 U	0.1	< 0.02 U	0.096	< 0.16 U	< 0.015 U	< 0.046 U	0.31
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated			5.175	< 0.022 U	0.047 J	< 0.021 U	0.055 J	< 0.17 U	< 0.016 U	< 0.047 U	0.52
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated		12 J									
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.031 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated			0.881	< 0.02 U	0.029 J	< 0.019 U	0.018 J	< 0.15 U	< 0.014 U	< 0.043 U	0.076
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated			2.217	< 0.02 U	0.073	< 0.019 U	0.07 J	< 0.15 U	0.016 J	< 0.044 U	0.17
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated			6.481	< 0.021 U	0.17	< 0.13 U	0.15	< 0.16 U	< 0.14 U	< 0.046 U	0.62
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated			1.237	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.12
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated			1614.2	39	< 0.84 U	< 0.034 U	76	< 8.4 U	< 0.034 U	< 2.4 U	140
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated			2.369	< 0.023 U	0.033 J	< 0.14 U	0.049 J	< 0.18 U	< 0.15 U	< 0.05 U	0.22
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated			3.675	< 0.023 U	0.054 J	< 0.14 U	0.065 J	< 0.17 U	< 0.14 U	< 0.049 U	0.35
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated			5.611	< 0.021 U	0.079	< 0.13 U	0.075	< 0.16 U	< 0.13 U	< 0.046 U	0.53
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated			0.966	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	0.078 J
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated			0.552	< 0.021 U	0.019 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.057 J
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated			51.71	0.12	0.87	< 0.14 U	0.86	< 0.17 U	< 0.14 U	< 0.048 U	4.6
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated			5.902	< 0.021 U	0.071 J	< 0.13 U	0.096	< 0.16 U	< 0.13 U	< 0.045 U	0.55
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated			7.943	< 0.022 U	0.17	< 0.14 U	0.18	< 0.17 U	< 0.14 U	< 0.048 U	0.74
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated			0.134	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated			3.1633	0.0033 J	0.046	< 0.014 U	0.068	< 0.017 U	< 0.014 U	< 0.0048 U	0.35
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated			0.389	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	0.042 J
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated			0.22	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.039 J
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated			4.739	< 0.022 U	0.078	< 0.14 U	0.078	< 0.17 U	< 0.14 U	< 0.048 U	0.44
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated			10.559	< 0.022 U	0.16	< 0.13 U	0.22	< 0.16 U	< 0.14 U	< 0.047 U	1.1
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated			17.53	0.34	0.12	< 0.13 U	0.75	< 0.17 U	< 0.14 U	< 0.047 U	1.5
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated			0.527	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.061 J
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated			0.16	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated			4.613	< 0.021 U	0.12	< 0.13 U	0.1	< 0.16 U	< 0.14 U	< 0.046 U	0.41
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated			0.578	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.075 J
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated			0.198	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated			0.291	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.041 J
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated			6.238	0.023 J	0.064 J	< 0.13 U	0.14	< 0.16 U	< 0.14 U	< 0.047 U	0.59

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	0.61	0.78	0.27	0.48	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.034 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	0.017 J	0.02 J	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	120	110	47	66	< 0.71 U	< 0.54 U	< 1.1 U	< 16 U	< 1 U	< 10 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	0.13	0.18	0.07 J	0.11	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	0.048 J	0.061 J	0.027 J	0.042 J	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	0.076	0.1	0.041 J	0.067 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 UT
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	0.14	0.17	0.053 J	0.14	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 UT
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	0.064 J	0.056 J	0.036 J	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.032 U	0.16	0.045 J	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	0.14	0.14	0.047 J	0.11	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	0.21	0.26	0.084	0.2	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	0.15	0.15	0.098	0.15	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.13 U	< 0.072 U	< 0.088 U	< 0.063 U	< 0.07 U	< 0.053 U	< 0.11 U	< 1.6 U	< 0.1 U	< 1 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.12 U	< 0.07 U	< 0.086 U	< 0.062 U	< 0.068 U	< 0.052 U	< 0.11 U	< 1.5 U	< 0.1 U	< 0.98 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	1.1	1.3	0.55	0.79	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	0.03 J	< 0.022 U	0.031 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.034 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U						
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.034 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	0.23	0.35	0.1	0.13	< 0.034 U	< 0.034 U	< 0.028 U	< 0.14 U	< 0.04 U	< 0.062 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	0.056	0.083	0.032	0.028	< 0.014 U	< 0.014 U	< 0.011 U	0.062 J	< 0.016 U	< 0.025 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	0.035	0.048	0.022	< 0.00039 U	< 0.013 U	< 0.013 U	< 0.011 U	0.07 J	< 0.016 U	< 0.024 U
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	0.023 J	0.02 J	< 0.024 U	0.021 J	< 0.019 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.27 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	< 0.034 U	0.032 J	< 0.023 U	0.025 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	1.2	1.4	0.44	1	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	0.61	0.63	0.26	0.52	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	0.034 J	0.036 J	< 0.023 U	0.029 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	0.059 J	0.07 J	0.029 J	0.056 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	0.33	0.43	0.18	0.47	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	0.59	0.56	0.25	0.47	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	0.084	0.11	0.036 J	0.13	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	0.19	0.26	0.068 J	0.23	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	0.52	0.75	0.26	0.5	< 0.14 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.16 U	< 0.25 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	0.12	0.14	0.067 J	0.1	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	76	100	33	47	< 7.1 U	< 0.7 U	< 1.4 U	< 21 U	< 8.2 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	0.21	0.27	0.1	0.18	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	0.31	0.43	0.13	0.31	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	0.52	0.62	0.25	0.46	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	0.084	0.12	0.039 J	0.076 J	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	0.05 J	0.067 J	0.026 J	0.049 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	4.3	5.7	2	3.7	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	0.46	0.64	0.23	0.4	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	0.62	0.89	0.26	0.51	< 0.14 U	< 0.014 U	< 0.029 U	0.65 J	< 0.16 U	< 0.27 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.032 U	0.029 J	< 0.022 U	0.019 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	0.28	0.34	0.11	0.19	< 0.014 U	< 0.0014 U	< 0.0029 U	< 0.041 U	< 0.016 U	< 0.026 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	0.043 J	0.054 J	< 0.024 U	0.031 J	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	853.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.033 U	0.04 J	< 0.023 U	0.032 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	0.47	0.54	0.21	0.36	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	0.96	1.2	0.48	0.69	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	1.1	1.3	0.55	0.69	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	0.056 J	0.08	< 0.023 U	0.041 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.032 U	0.031 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	0.38	0.4	0.24	0.41	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	0.059 J	0.062 J	0.028 J	0.046 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.032 U	0.036 J	< 0.022 U	0.03 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.035 U	0.034 J	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	0.57	0.57	0.22	0.44	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.24 U	0.15	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.91	0.12	0.15 J
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.22 U	< 0.034 U	< 0.09 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.21	< 0.016 U	< 0.016 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 9.7 U	19	< 0.49 U	< 0.7 U	< 0.68 U	< 0.69 U	< 0.9 U	140	21	22
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.048 J	< 0.048 U	< 0.016 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.25 U	0.023 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.14	< 0.049 U	< 0.017 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.1	< 0.049 U	< 0.017 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.11	< 0.048 U	< 0.016 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.21	< 0.045 U	0.019 J
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.081	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.49	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.48	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.22	< 0.046 U	0.028 J
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.23 U	0.021 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.16	< 0.046 U	0.016 J
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.95 U	< 0.068 U	< 0.099 U	< 0.069 U	< 0.067 U	< 0.068 U	< 0.088 U	1.6	< 0.19 U	< 0.064 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.93 U	< 0.067 U	< 0.098 U	< 0.067 U	< 0.066 U	< 0.067 U	< 0.087 U	1.2	< 0.18 U	< 0.063 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U	< 0.017 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.24 U	0.26	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.5	0.21	0.26 J
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated								< 0.41 U	< 0.41 U	< 0.41 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.29 J	< 0.048 U	< 0.016 U
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.17 J	< 0.047 U	< 0.016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.016 U
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	< 0.21 U	< 0.054 U	< 0.085 U	< 0.13 U	< 0.04 U	< 0.028 U	< 0.04 U	0.33	0.046	< 0.037 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	< 0.086 U	< 0.022 U	< 0.034 U	< 0.052 U	< 0.016 U	< 0.011 U	< 0.016 U	0.063	< 0.00076 U	< 0.015 U
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	< 0.083 U	< 0.021 U	< 0.033 U	< 0.05 U	< 0.016 U	< 0.011 U	< 0.016 U	0.037	< 0.00073 U	< 0.014 U
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.021 J	< 0.018 U	< 0.017 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.23 U	0.042 J	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	2.4	0.31	< 0.016 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.59	0.13	< 0.016 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.043 J	< 0.048 U	< 0.017 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.064 J	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.34	0.1	0.032 J
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.25 U	0.06 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.48	0.09	< 0.017 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.084	< 0.044 U	< 0.015 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.23 U	0.02 J	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.2	0.055 J	0.024 J
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	< 0.24 U	0.045 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.65	0.12	< 0.14 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.13	< 0.046 U	< 0.13 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 13 U	23	< 5.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	120	16	21
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.24	0.055 J	< 0.15 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.25 U	0.033 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.39	0.066 J	< 0.14 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.24 U	0.037 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.53	0.11	< 0.14 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.15	< 0.051 U	< 0.15 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.057 J	< 0.047 U	< 0.14 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.25 U	0.59	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	4.9	0.9	< 0.14 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.23 U	0.074	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.59	0.086	< 0.13 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.25 U	0.056 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.66	0.13	< 0.14 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.025 U	0.018	< 0.01 U	< 0.014 U	< 0.0018 U	< 0.014 U	< 0.013 U	0.26	0.052	< 0.014 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.078 J	< 0.051 U	< 0.15 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.25 U	0.049 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.44	0.081	< 0.14 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.25 U	0.085	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.98	0.18	< 0.14 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.25 U	0.34	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.4	0.21	0.31 J
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.058 J	< 0.05 U	< 0.14 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.075	< 0.048 U	< 0.14 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.24 U	0.046 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.43	0.093	< 0.14 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.079	< 0.049 U	< 0.14 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.048 J	< 0.048 U	< 0.14 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.052 J	< 0.051 U	< 0.15 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.051 U	< 0.15 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.24 U	0.023 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.58	0.076	< 0.14 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.026 U	< 0.034 U	< 0.11 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.96 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 14 U	< 1.1 U	< 5.2 U	< 0.92 U	< 0.54 U	< 6.5 U	< 8.6 U	< 26 U	< 0.92 U	< 40 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.35 UT	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 UT	< 0.023 U	< 2.1 UT
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 1.4 U	< 0.11 U	< 0.51 U	< 0.091 U	< 0.11 U	< 0.64 U	< 0.85 U	< 2.5 U	< 0.09 U	< 8.1 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 1.3 U	< 0.11 U	< 0.5 U	< 0.089 U	< 0.11 U	< 0.63 U	< 0.83 U	< 2.5 U	< 0.088 U	< 7.9 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	0.18 J	< 0.23 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated										
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 2 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.3 J	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	< 0.12 U	< 0.12 U	< 0.088 U	< 0.11 U	< 0.04 U	< 0.062 U	< 0.079 U	< 0.23 U	< 0.16 U	< 0.4 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	< 0.049 U	< 0.05 U	< 0.035 U	< 0.046 U	< 0.016 U	< 0.025 U	< 0.032 U	< 0.092 U	< 0.064 U	< 0.16 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	< 0.048 U	< 0.049 U	< 0.034 U	< 0.044 U	< 0.016 U	< 0.024 U	< 0.031 U	< 0.089 U	< 0.062 U	< 0.16 U
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	0.18 J	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	0.22 J	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 1.5 U	< 0.034 U	< 6.5 U	< 7.6 U	< 0.034 U	< 11 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.036 U	< 0.0030 U	< 0.014 U	< 0.013 U	< 0.015 U	< 0.017 U	< 0.022 U	< 0.066 U	< 0.015 U	< 0.24 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.11 U	2	0.23	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.018 U			< 0.11 U	0.066 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.74 U			< 4.6 U	380	43	< 1.1 U	< 0.87 U	< 1.5 U	< 0.77 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.057 U	< 0.12 U			0.24	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.058 U	< 0.12 U			0.086	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	< 0.053 U	< 0.11 U			0.22	0.021 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			0.093	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.056 U	< 0.12 U			0.45	0.11	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.055 U	< 0.11 U			0.31	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.054 U	< 0.11 U			0.33	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.054 U	< 0.11 U			0.26	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.22 U	< 0.46 U			0.61	0.2 J	< 0.1 U	< 0.085 U	< 0.15 U	< 0.075 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.22 U	< 0.45 U			0.45	0.12 J	< 0.1 U	< 0.084 U	< 0.15 U	< 0.074 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.06 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.11 U	3.3	0.42	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.11 U	0.068 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated					< 0.41 U	< 0.41 U	< 0.41 U			
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.056 U			< 0.12 U	0.065 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.055 U			< 0.11 U	< 0.019 UJ	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	< 0.18 U			< 0.042 U	0.43	0.013 J	< 0.0059 U	< 0.034 U	< 0.18 U	< 0.025 U
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	< 0.071 U			< 0.017 U	0.097	0.0085	< 0.0024 U	< 0.014 U	< 0.071 U	< 0.01 U
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	< 0.069 U			< 0.017 U	0.064	< 0.00059 U	< 0.0023 U	< 0.013 U	< 0.069 U	< 0.01 U
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.02 U			< 0.12 U	0.021 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	< 0.059 U			< 0.12 U	0.034 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.054 U			< 0.11 U	2.6	0.025 J	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.055 U			< 0.11 U	1	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.057 U			< 0.12 U	0.044 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.056 U			< 0.12 U	0.081	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	< 0.056 U	< 0.11 U			0.48	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.057 U	< 0.12 U			0.81	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 0.052 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.052 U	< 0.11 U			0.083	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.053 U	< 0.11 U			0.29	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	< 0.22 U	< 0.12 U			0.9	0.031 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	< 0.22 U	< 0.11 U			0.23	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 12 U			< 6 U	260	34	< 1.4 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.24 U	< 0.13 UT			0.31	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.23 U	< 0.12 UT			0.47	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.22 U	< 0.11 UT			0.8	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.24 U	< 0.12 U			0.098	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.22 U	< 0.12 U			0.077	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.23 U	< 0.12 U			8.1	0.18	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.22 U	< 0.11 U			0.96	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.23 U	< 0.12 U			1.4	0.023 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.22 U	< 0.11 U			0.042 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.023 U	< 0.012 U			0.59	0.014	< 0.0028 U	< 0.0023 U	< 0.0039 U	< 0.014 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.24 U	< 0.12 U			0.07 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.23 U	< 0.12 U			0.059 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			0.75	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.22 U	< 0.12 U			1.7	0.019 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.22 U	< 0.12 U			2.8	0.44	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.23 U	< 0.12 U			0.099	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.22 U	< 0.12 U			0.026 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.22 U	< 0.12 U			0.65	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.23 U	< 0.12 U			0.09	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.22 U	< 0.12 U			0.033 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.24 U	< 0.13 U			0.065 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.22 U	< 0.12 U			0.94	0.033 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	0.41	< 0.034 U	< 0.034 U	< 0.034 U	0.057 J		0.069 J	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	64	< 4.3 U		< 0.76 U	4.2	< 4.4 U	5.3	< 6.8 U	< 3.8 U	< 0.72 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	0.084	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.038 U	< 0.11 U		< 0.02 U	0.055 J	< 0.11 U	0.079	< 0.18 U	< 0.098 U	< 0.019 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	0.051 J	< 0.11 U		< 0.019 U	0.025 J	< 0.11 U	0.021 J	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	0.1	< 0.1 U		< 0.018 U	0.032 J	< 0.1 U	0.042 J	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	0.11	< 0.11 U		< 0.019 U	0.049 J	< 0.11 U	0.063 J	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	0.1	< 0.11 U		< 0.019 U	0.042 J	< 0.11 U	0.035 J	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	0.19	< 0.1 U		< 0.018 U	0.038 J	< 0.11 U	0.099	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	0.13	< 0.1 U		< 0.018 U	0.02 J	< 0.11 U	0.05 J	< 0.16 U	< 0.092 U	< 0.017 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.15 U	< 0.42 U		< 0.074 U	< 0.07 U	< 0.43 U	< 0.057 U	< 0.67 U	< 0.37 U	< 0.071 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.14 U	< 0.41 U		< 0.073 U	< 0.069 U	< 0.42 U	< 0.056 U	< 0.65 U	< 0.36 U	< 0.07 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.019 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	0.7	< 0.034 U	< 0.034 U	< 0.034 U	0.11		0.15	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U			
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U	< 0.018 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.018 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	0.12	< 0.088 U	< 0.082 U	< 0.034 U	0.062		0.072	< 0.11 U	< 0.14 U	< 0.17 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	0.026	< 0.035 U	< 0.033 U	< 0.014 U	0.018		0.013	< 0.046 U	< 0.056 U	< 0.069 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	0.015	< 0.034 U	< 0.032 U	< 0.013 U	0.023		0.026	< 0.044 U	< 0.055 U	< 0.067 U
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.016 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	0.71	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	0.4	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		0.031 J	< 0.17 U	< 0.092 U	< 0.018 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	0.049 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.018 J	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	0.38	< 0.11 U		< 0.019 U	0.044 J	< 0.11 U	0.1	< 0.17 UT	< 0.094 U	< 0.018 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	0.35	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.03 J	< 0.17 U	< 0.097 U	< 0.018 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 0.034 U	< 0.099 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.017 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	0.086	< 0.098 U		< 0.017 U	0.025 J	< 0.1 U	0.026 J	< 0.16 U	< 0.087 U	< 0.017 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	0.18	< 0.1 U		< 0.018 U	0.049 J	< 0.1 U	0.084	< 0.16 U	< 0.09 U	< 0.017 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	0.42	< 0.11 U		< 0.14 U	0.038 J	< 0.11 U	0.11	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	0.088	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	46	< 0.034 U	< 0.034 U	< 0.034 U	8.3		7.2	< 0.034 U	< 0.034 U	< 7.2 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	0.17	< 0.12 U		< 0.15 U	0.024 J	< 0.12 U	0.035 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	0.26	< 0.11 U		< 0.15 U	0.024 J	< 0.11 U	0.084	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	0.41	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.036 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	0.073 J	< 0.11 U		< 0.15 U	0.023 J	< 0.12 U	0.018 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	0.042 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.024 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	3.2	< 0.11 U		< 0.15 U	0.051 J	< 0.11 U	0.15	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	0.33	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	0.49	< 0.11 U		< 0.14 U	0.068 J	< 0.11 U	0.17	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	0.18	< 0.011 U		< 0.014 U	0.0076 J	< 0.011 U	0.026	< 0.018 U	< 0.0098 U	< 0.014 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	0.31	< 0.11 U		< 0.15 U	0.03 J	< 0.11 U	0.11	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	0.61	< 0.11 U		< 0.14 U	0.031 J	< 0.11 U	0.12	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	0.66	< 0.11 U		< 0.14 U	0.1	< 0.11 U	0.29	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	0.3	< 0.11 U		< 0.14 U	0.052 J	< 0.11 U	0.16	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.038 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.015 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	0.33	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.016 J	< 0.17 U	< 0.095 U	< 0.14 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	2.3	< 0.11 U	1.9
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	< 0.016 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.23
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 5.4 U	< 2.4 U	< 10 U		< 1 U	< 4.9 U	< 24 U	430	< 4.5 U	360
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.04 J
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.12	< 0.11 U	0.24
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.1
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.062 J	< 0.11 U	0.14
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.17	< 0.11 U	0.28
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.077	< 0.11 U	0.079
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.61	< 0.11 U	0.54
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.64	< 0.11 U	0.47
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.2	< 0.11 U	0.3
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.13	< 0.11 U	0.23
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.53 U	< 0.23 U	< 1 U		< 0.099 U	< 0.49 U	< 2.3 U	1.8	< 0.44 U	1.1
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.52 U	< 0.23 U	< 1 U		< 0.097 U	< 0.48 U	< 2.3 U	1.8	< 0.43 U	0.93
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	0.056 J
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	4	< 0.11 U	3.1
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.069 J	< 0.11 U	0.059 J
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated							< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.21 J
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.086 J
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.21
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated	< 0.037 U	< 0.037 U	< 0.27 U		< 0.031 U	< 0.034 U	< 0.16 U	0.21	< 0.023 U	0.37
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated	< 0.015 U	< 0.015 U	< 0.11 U		< 0.013 U	< 0.014 U	< 0.066 U	0.063	< 0.0092 U	0.084
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated	< 0.014 U	< 0.014 U	< 0.1 U		< 0.012 U	< 0.013 U	< 0.065 U	0.036	< 0.0089 U	0.042
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.024 J	< 0.12 U	0.02 J
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.026 J	< 0.12 U	0.04 J
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	2	< 0.11 U	4.7
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.29	< 0.11 U	1.1
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.029 J	< 0.11 U	0.047 J
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.04 J	< 0.11 U	0.095
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 UT		< 0.025 U	< 0.12 U	< 0.59 U	0.33	< 0.11 U	0.48
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.15	< 0.12 U	0.82
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.064 J	< 0.1 U	0.084
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.14	< 0.11 U	0.28
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.35	< 0.11 U	1.1
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.052 J	< 0.11 U	0.19
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 14 U		< 0.034 U	< 0.034 U	< 0.034 U	350	< 5.8 U	270
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.19	< 0.12 U	0.34
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.25	< 0.12 U	0.56
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.27	< 0.11 U	1
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.12	< 0.12 U	0.11
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.028 J	< 0.11 U	0.075
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	3.1	< 0.12 U	9.9
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.36	< 0.11 U	1.2
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.57	< 0.12 U	1.3
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.044 J
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.014 U	< 0.014 U	< 0.027 U		< 0.0026 U	< 0.013 U	< 0.062 U	0.17	< 0.012 U	0.53
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.071 J
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.05 J
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.26	< 0.12 U	0.69
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.6	< 0.11 U	1.7
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	2.9	< 0.11 U	2.6
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.032 J	< 0.12 U	0.1
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.028 J
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.32	< 0.11 U	0.72
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.06 J	< 0.12 U	0.079
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.036 J
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.042 J	< 0.12 U	0.057 J
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.51	< 0.11 U	1.2

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated		< 0.64 U	< 6.2 U	< 1.1 U	< 0.81 U
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated		< 0.063 U	< 0.61 U	< 0.1 U	< 0.08 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated		< 0.062 U	< 0.6 U	< 0.1 U	< 0.079 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated					
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated		< 0.04 U	< 0.83 U	< 0.19 U	< 0.18 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated		< 0.016 U	< 0.34 U	< 0.079 U	< 0.073 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated		< 0.016 U	< 0.33 U	< 0.077 U	< 0.071 U
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated					
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUP1-20211230	SSHS-ISMP-DUP1	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated		< 0.015 U	< 0.016 U	< 0.013 U	< 0.013 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U

														Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated			12.274	0.032 J	0.21	< 0.14 U	0.46	< 0.17 U	< 0.14 U	< 0.048 U	0.95
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated			0.054	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated			0.757	< 0.021 U	0.031 J	< 0.13 U	0.02 J	< 0.16 U	< 0.13 U	< 0.045 U	0.08
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated			0.748	< 0.02 U	0.019 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.059 J
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated			25.275	0.045 J	0.39 T	< 0.13 U	0.71 T	< 0.16 U	< 0.13 U	< 0.046 U	2.1 T
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated			9.17	0.15 J	0.16 J	< 0.51 U	0.46	< 0.62 U	< 0.52 U	< 0.18 U	0.79
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated			0.333	< 0.021 U	0.026 J	< 0.13 U	0.026 J	< 0.16 U	< 0.14 U	< 0.046 U	0.039 J
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated			1.553	< 0.021 U	0.059 J	< 0.13 U	0.052 J	< 0.16 U	< 0.13 U	< 0.045 U	0.17
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated			4.79	< 0.01 U	0.11 J	< 0.018 U	0.081 J	< 0.021 U	0.018 J	< 0.06 U	0.41
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated			25.464	0.057 J	0.46	< 0.019 U	0.56	< 0.023 U	0.051 J	< 0.063 U	2
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated			2.661	0.024 J	0.058 J	< 0.13 U	0.091	< 0.16 U	< 0.13 U	< 0.045 U	0.24
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated			0.088	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated			15.557	< 0.022 U	0.46	< 0.13 U	0.53	< 0.16 U	< 0.14 U	< 0.047 U	1.3
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated			0.2887	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.023 J
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated			0.742	< 0.01 U	0.024 J	< 0.017 U	0.014 J	< 0.021 U	< 0.012 U	< 0.059 U	0.056
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated			0.668	< 0.0099 U	< 0.0099 U	< 0.017 U	0.012 J	< 0.02 U	< 0.012 U	< 0.057 U	0.06
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated			0.879	< 0.051 U	< 0.051 U	< 0.087 U	< 0.054 U	< 0.1 U	< 0.062 U	< 0.29 U	0.089 J
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated			0.255	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.025 J
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated			0.253	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.027 J
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated			0.5184	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.051
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated			3.275	0.023 J	< 0.017 U	< 0.14 U	0.11	< 0.17 U	< 0.14 U	< 0.049 U	0.32
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated			ND	< 0.047 U	< 0.036 U	< 0.29 U	< 0.043 U	< 0.36 U	< 0.3 U	< 0.1 U	< 0.074 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated			0.621	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.072 J
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated			35.663	0.033 J	0.65	< 0.13 U	0.8	< 0.16 U	< 0.13 U	< 0.044 U	3.4
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated			2.765	< 0.02 U	0.07 J	< 0.13 U	0.059 J	< 0.15 U	< 0.13 U	< 0.044 U	0.23
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated			0.677	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.066 J
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated			2.282	< 0.02 U	0.045 J	< 0.12 U	0.032 J	< 0.15 U	< 0.13 U	< 0.043 U	0.24
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated			2.603	< 0.02 U	0.091	< 0.12 U	0.066 J	< 0.15 U	< 0.13 U	< 0.043 U	0.24
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated			0.243	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated			4.475	0.053 J	0.062 J	< 0.021 U	0.053 J	< 0.17 U	0.018 J	< 0.048 UT	0.45
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated			1.159	< 0.022 U	0.021 J	0.028 J	0.02 J	< 0.16 U	0.029 J	< 0.046 U	0.075
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated			1.503	< 0.023 U	< 0.017 U	< 0.021 U	0.046 J	< 0.17 U	< 0.017 U	< 0.049 U	0.11
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated			86.17	2.2	0.15	< 0.021 U	5.5	< 0.17 U	0.25 J	< 0.047 U	6.2
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated			3.468	0.024 J	0.046 J	< 0.02 U	0.093	< 0.16 U	< 0.16 U	< 0.046 U	0.29
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated		920	0.655	< 0.021 U	0.016 J	< 0.02 U	0.02 J	< 0.16 U	< 0.015 U	< 0.046 U	0.061 J
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated		1400	13.013	0.05 J	0.15	< 0.02 U	0.27	< 0.16 U	0.029 J	< 0.046 U	1.2
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated		70	ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated		13000 T	0.463	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.05 J
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated		7700	2.06	< 0.022 U	0.057 J	< 0.021 U	0.065 J	< 0.17 U	< 0.016 U	< 0.047 U	0.23
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated		7700	1.984	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.31
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated		9700	0.95	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.11
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated		650 T	0.425	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	0.043 J
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated		630	2.94	< 0.037 UT	0.072 J	< 0.035 U	0.065 JT	< 0.28 U	< 0.027 UT	< 0.08 U	0.27
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated			1.325	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.15
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated		14 J	ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated		240									
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated		820									
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated			2.584	< 0.023 U	0.029 J	0.023 J	0.047 J	< 0.17 U	< 0.017 U	0.051 J	0.15
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated			0.066	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated			0.603	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	0.052 J
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated			4.8	< 0.1 U	< 0.078 U	< 0.096 U	< 0.092 U	< 0.78 U	< 0.074 U	< 0.22 U	1.3
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated			0.397	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated			0.227	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated			0.418	< 0.02 U	0.024 J	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated			2.485	< 0.021 U	0.069 J	< 0.019 U	0.066 J	< 0.16 U	0.023 J	< 0.044 U	0.21
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated			4.495	0.042 J	0.053 J	< 0.13 U	0.15	< 0.16 U	< 0.14 U	< 0.046 U	0.4
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated			1.839	< 0.024 U	0.033 J	< 0.15 U	0.046 J	< 0.18 U	< 0.15 U	< 0.052 U	0.16
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated			4.735	< 0.021 U	0.099	< 0.13 U	0.11	< 0.16 U	< 0.13 U	< 0.046 U	0.46
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated			8.839	0.2	0.018 J	< 0.034 U	0.41 J	< 0.16 U	< 0.034 U	< 0.046 U	0.7
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated			14.404	0.25	0.075 J	< 0.034 U	0.74 J	< 0.17 U	< 0.034 U	< 0.048 U	1.1 J
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated			2.435	< 0.034 U	0.048 J	< 0.034 U	0.068 J	< 0.16 U	< 0.034 U	< 0.046 U	0.2
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated			0.702	< 0.021 U	< 0.016 U	< 0.13 U	0.018 J	< 0.16 U	< 0.13 U	< 0.044 U	0.074
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated			1.608	< 0.022 U	0.037 J	< 0.14 U	0.033 J	< 0.17 U	< 0.14 U	< 0.047 U	0.16
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated			1.166	< 0.021 U	< 0.016 U	< 0.13 U	0.021 J	< 0.16 U	< 0.13 U	< 0.045 U	0.11
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated			3.608	< 0.022 U	0.11	< 0.13 U	0.11	< 0.17 U	< 0.14 U	< 0.047 U	0.39
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated			0.73	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.091
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated			0.12	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated			4.126	< 0.021 U	0.061 J	< 0.13 U	0.082	< 0.16 U	< 0.13 U	< 0.045 U	0.39

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	1	1.2	0.45	0.75	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	0.073	0.09	0.026 J	0.065 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	0.071	0.072	0.033 J	0.083	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	1.8 T	2.4 T	1	1.6 T	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	0.47	0.58	< 0.086 U	0.2 J	< 0.52 U	< 0.052 U	< 0.11 U	< 1.5 U	< 0.61 U	< 0.98 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.032 U	0.055 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	0.11	0.18	0.06 J	0.17	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	0.41	0.61	0.22	0.28 J	< 0.028 U	< 0.013 U	< 0.0065 U	0.024 J	< 0.014 U	< 0.017 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	2	3	0.9	1.3	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	0.18	0.26	0.083	0.21	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	1.2	1.6	0.56	1.4	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	0.013 J	0.022 J	0.0077 J	0.02 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	0.048	0.081	0.026 J	0.069 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	0.045	0.07	0.024 J	0.034 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	0.053 J	0.11 J	< 0.035 U	0.15 J	< 0.14 U	< 0.062 U	< 0.032 U	< 0.094 U	< 0.071 U	< 0.083 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	0.022 J	0.029 J	0.013 J	0.016 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	0.025 J	0.034 J	0.012 J	0.019 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	0.048	0.071	0.024 J	0.038 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	0.22	0.25	0.1	0.11	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.071 U	< 0.04 U	< 0.049 U	< 0.035 U	< 0.3 U	< 0.03 U	< 0.061 U	< 0.87 U	< 0.35 U	< 0.56 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	0.061 J	0.066 J	0.03 J	0.044 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	3.4	3.9	1.4	2.6	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	0.29	0.3	0.14	0.29	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	0.074	0.071 J	0.034 J	0.06 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	0.22	0.26	0.095	0.17	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	0.23	0.31	0.11	0.22	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	0.034 J	0.049 J	< 0.02 U	0.041 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.017 U	0.34	< 0.023 U	0.11	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	0.056 J	0.082	0.044 J	0.07 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	0.13	0.14	0.067 J	0.12	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	5	5.8	1.6	2.9	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	0.3	0.36	0.12	0.26	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	0.046 J	0.084	0.023 J	0.065 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 UT
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	0.91	1.1	0.37	0.89	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.032 U	0.066 J	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	0.13	0.14	0.071 J	0.19	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	0.046 J	0.064 J	< 0.022 U	0.053 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	0.27	0.35 T	0.13	0.25	< 0.031 U	< 0.024 UT	< 0.048 U	< 0.69 U	< 0.045 U	< 0.45 U
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	0.15	0.17	0.081	0.12	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	0.18	0.33	0.085	0.28	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	0.064 J	0.071 J	0.024 J	0.051 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.15 U	< 0.087 U	< 0.11 U	< 0.077 U	< 0.085 U	< 0.064 U	< 0.13 U	< 1.9 U	< 0.12 U	< 1.2 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	0.06 J	0.064 J	0.038 J	0.11	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.03 U	0.033 J	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	0.045 J	0.054 J	< 0.021 U	0.069 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	0.19	0.3	0.071 J	0.22	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	0.31	0.37	0.19	0.25	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	0.15	0.18	0.083	0.14	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	0.37	0.51	0.18	0.4	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.44	0.55	0.21 J	0.34	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.72	0.82	0.42 J	0.46	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.16	0.22	0.076	0.17	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	0.068 J	0.084	0.037 J	0.073	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	0.12	0.17	0.067 J	0.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	0.085	0.11	0.063 J	0.071 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	0.28	0.39	0.14	0.28	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	0.056 J	0.077	0.031 J	0.06 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.031 U	0.026 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	0.34	0.44	0.17	0.36	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.25 U	0.16	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.87	0.17	< 0.14 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.076	< 0.047 U	< 0.13 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.073	< 0.045 U	< 0.13 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.24 U	0.37 T	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	1.9 T	0.36 T	0.14 J
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.93 U	< 0.067 U	< 0.37 U	< 0.5 U	< 0.065 U	< 0.53 U	< 0.47 U	1.3	< 0.18 U	< 0.53 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.072 J	< 0.047 U	< 0.14 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.18	< 0.047 U	< 0.13 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.056 U	0.058 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.4	0.073	0.045 J
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.06 U	0.21 J	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	2	0.35	0.16 J
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.24 U	0.039 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.24	0.048 J	< 0.14 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.24 U	0.17	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	1.3	0.28	0.14 J
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.022 J	< 0.016 U	0.016 J
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.054 J	< 0.015 U	0.024 J
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.08 J	< 0.015 U	0.013 J
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.28 U	< 0.068 U	< 0.32 U	< 0.1 U	< 0.082 U	< 0.063 U	< 0.063 U	0.12 J	< 0.077 U	< 0.059 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.025 J	< 0.015 U	< 0.012 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.029 J	< 0.015 U	< 0.012 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.055 J	< 0.015 U	< 0.012 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.26 U	0.035 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.31	< 0.051 U	< 0.15 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.53 U	< 0.038 U	< 0.22 U	< 0.29 U	< 0.038 U	< 0.3 U	< 0.27 U	< 0.091 U	< 0.11 U	< 0.3 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.064 J	< 0.048 U	< 0.14 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.23 U	0.048 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	3.1	0.62	< 0.13 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.26	0.066 J	< 0.13 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.071 J	< 0.046 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.25	0.046 J	< 0.13 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.23 U	0.018 J	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.22	0.049 J	< 0.13 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.6	< 0.017 U	< 0.017 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.24 U	0.026 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.11	< 0.048 U	0.043 J
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	< 0.26 U	0.028 J	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.15	< 0.05 U	0.021 J
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	< 0.25 U	1.8	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	4.7	0.87	1.6
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	< 0.24 U	0.049 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.28	0.063 J	0.018 J
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.082	< 0.047 U	< 0.016 U
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.24 U	0.086	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	1.4	0.22	0.071 J
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.15	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.43	< 0.049 U	< 0.017 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.62	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.38	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.048 J	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.42 UT	< 0.03 UT	< 0.044 UT	< 0.031 U	< 0.03 UT	< 0.03 UT	< 0.039 UT	0.29 T	< 0.083 U	< 0.028 UT
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	< 0.26 U	0.035 J	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.3	0.071 J	0.036 J
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.016 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.085	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 1.2 U	< 0.083 U	< 0.12 U	< 0.083 U	< 0.081 U	< 0.082 U	< 0.11 U	2.3	< 0.23 U	< 0.078 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U	< 0.018 U	
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.048 J	< 0.045 U	0.02 J
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.058 J	< 0.045 U	0.015 J
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.37	< 0.046 U	0.035 J
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	< 0.24 U	0.042 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.39	0.069 J	< 0.14 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.16	< 0.053 U	< 0.15 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	< 0.24 U	0.029 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.43	0.097	< 0.14 U
Football Field	SSHS-B4164	092421 10:00_DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.24 U	0.12	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.66	0.09	< 0.14 UJ
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.25 U	0.2	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.1 J	0.13	0.16 J
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.24 U	0.029 J	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.2	< 0.034 U	< 0.14 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.07 J	< 0.046 U	< 0.13 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.16	< 0.049 U	< 0.14 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.12	< 0.046 U	< 0.13 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.25 U	0.033 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.39	0.088	< 0.14 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.078	< 0.048 U	< 0.14 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.23 U	0.037 J	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.39	0.072	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.34 UT	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 UT	< 0.14 U	< 2.3 UT
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 1.3 U	< 0.11 U	< 0.5 U	< 0.48 U	< 0.56 U	< 0.62 U	< 0.83 U	< 2.5 U	< 0.56 U	< 8.9 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.27 U	< 0.11 U	< 0.057 U	< 0.21 U	< 0.4 U	< 0.067 U	< 0.094 U	< 0.73 U	< 0.13 U	< 0.87 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.76 U	< 0.063 U	< 0.29 U	< 0.28 U	< 0.32 U	< 0.36 U	< 0.48 U	< 1.4 U	< 0.32 U	< 5.1 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.23 J	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.17 J	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	0.18 J	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.21 J	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	0.076 J	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.6 U	< 0.05 U	< 0.23 UT	< 0.04 U	< 0.048 UT	< 0.28 UT	< 0.38 U	< 1.1 UT	< 0.04 U	< 3.6 UT
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 1.7 U	< 0.14 U	< 0.62 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U	< 0.11 U	< 9.8 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U	< 2.2 U
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	0.41	< 0.2 U	< 0.61 U	< 0.022 U	< 1.9 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.022 U	< 0.026 U	0.36	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 UT
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.23 U	< 0.12 U			2.1	0.082	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.24 U	< 0.12 U			0.024 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.22 U	< 0.11 U			0.12	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.21 U	< 0.11 U			0.085	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.22 U	< 0.11 U			4.5 T	0.18 T	< 0.026 UT	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.85 U	< 0.44 U			1.3	0.45	< 0.1 U	< 0.083 U	< 0.15 U	< 0.5 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.22 U	< 0.12 U			0.057 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.22 U	< 0.11 U			0.21	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.039 U		< 0.032 U		0.72	0.016 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.041 U		< 0.034 U		4.6	0.077 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.22 U	< 0.11 U			0.32	0.026 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.22 U	< 0.12 U			2	0.067 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.04 U		< 0.033 U		0.028 J	0.012 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.038 U		< 0.031 U		0.084 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.037 U		< 0.03 U		0.097 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.19 U		< 0.16 U		0.074 J	< 0.052 U	< 0.085 U	< 0.038 U	< 0.16 U	< 0.061 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.038 U		< 0.031 U		0.041 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.038 U		< 0.031 U		0.034 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.038 U		< 0.031 U		0.075 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.24 U	< 0.12 U			0.69	0.032 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.49 U	< 0.26 U			< 0.043 U	< 0.032 U	< 0.059 U	< 0.048 U	< 0.084 U	< 0.29 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.22 U	< 0.12 U			0.089	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.21 U	< 0.11 U			6	0.14	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.21 U	< 0.11 U			0.35	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.22 U	< 0.11 U			0.084	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.21 U	< 0.11 U			0.33	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.21 U	< 0.11 U			0.4	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.2 U	< 0.11 U			0.044 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.019 U	< 0.12 U			0.29	0.071 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.056 U			< 0.12 U	0.11	0.044 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	< 0.059 U	< 0.12 U			0.21	0.016 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	< 0.058 U	< 0.12 U			15	2.7	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	< 0.056 U	< 0.12 U			0.55	0.018 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.056 U	< 0.11 U			0.07 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.056 U	< 0.11 U			1.9	0.063 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.056 U	< 0.12 U			0.077	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.057 U	< 0.12 U			0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	0.084	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.057 U	< 0.12 U			0.061 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.098 UT	< 0.2 U			0.37 T	< 0.025 UT	< 0.046 U	< 0.038 U	< 0.066 U	< 0.033 UT
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.056 U	< 0.12 U			0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	< 0.06 U	< 0.12 U			0.31	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 0.053 U	< 0.11 U			0.03 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.054 U	< 0.11 U			0.054 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.27 U	< 0.55 U			< 0.094 U	< 0.07 U	< 0.13 U	< 0.1 U	< 0.18 U	< 0.091 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.061 U	< 0.13 U			0.021 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.021 U
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.053 U	< 0.11 U			0.021 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.053 U	< 0.11 U			0.036 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.054 U	< 0.11 U			0.31	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	< 0.22 U	< 0.12 U			0.76	0.039 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	< 0.25 U	< 0.13 U			0.33	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	< 0.22 U	< 0.11 U			0.74	0.017 J	< 0.026 U	< 0.022 U	< 0.038 UT	< 0.13 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.12 U	1.5 J	0.19	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.23 U			< 0.12 U	2.6 J	0.26	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.12 U	0.43	0.029 J	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.21 U	< 0.11 UT			0.086	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.23 U	< 0.12 UT			0.24	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.22 U	< 0.11 UT			0.2	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.22 U	< 0.11 UT			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.23 U	< 0.12 UT			0.44	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.22 U	< 0.12 UT			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.21 U	< 0.11 UT			0.048 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.21 U	< 0.11 UT			0.57	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.5	0.33				0.33	12			
Restricted - Residential												0.5	100				100	100			
Protection of Groundwater												8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	0.69	< 0.11 U		< 0.15 U	0.042 J	< 0.11 U	0.12	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	0.054 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.023 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	0.073	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.042 J	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	1.3 T	< 0.11 U		< 0.14 U	0.08	< 0.11 U	0.28	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	0.19 J	< 0.41 U		< 0.53 U	0.13 J	< 0.42 U	0.18 J	< 0.65 U	< 0.36 U	< 0.53 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.024 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	0.13	< 0.1 U		< 0.14 U	0.023 J	< 0.11 U	0.051 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	0.33	< 0.014 U		< 0.1 U	0.053 J	< 0.023 U	0.22 J	< 0.028 U	< 0.086 U	< 0.042 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	1.5	< 0.014 U		< 0.11 U	0.13 J	< 0.024 U	0.52	< 0.029 U	< 0.091 U	< 0.044 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	0.16	< 0.1 U		< 0.14 U	0.041 J	< 0.11 U	0.079	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.088	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	1.2	< 0.11 U		< 0.14 U	0.11	< 0.11 U	0.52	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	0.016 J	< 0.014 U		< 0.11 U	0.024 J	< 0.023 U	0.036 J	< 0.028 U	< 0.089 U	< 0.043 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	0.064	< 0.013 U		< 0.1 U	0.065 J	< 0.022 U	0.1 J	< 0.027 U	< 0.085 U	< 0.041 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	0.037	< 0.013 U		< 0.1 U	0.038 J	< 0.022 U	0.024 J	< 0.027 U	< 0.083 U	< 0.04 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	0.1 J	< 0.066 U		< 0.51 U	< 0.05 U	< 0.11 U	< 0.031 U	< 0.14 U	< 0.42 U	< 0.2 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	0.015 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	0.023 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	0.041	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0084 J	< 0.027 U	< 0.084 U	< 0.04 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	0.1	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.082 U	< 0.24 U		< 0.31 U	< 0.039 U	< 0.24 U	< 0.032 U	< 0.37 U	< 0.21 U	< 0.3 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	0.04 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	2.3	< 0.1 U		< 0.13 U	0.064 J	< 0.11 U	0.27	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	0.22	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.04 J	< 0.16 U	< 0.089 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	0.055 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	0.14	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	0.18	< 0.1 U		< 0.13 U	0.02 J	< 0.1 U	0.058 J	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	0.031 J	< 0.15 U	< 0.086 U	< 0.13 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	0.12	< 0.11 U		< 0.02 U	0.063 J	< 0.11 U	0.068 J	< 0.18 U	< 0.098 U	< 0.019 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	0.058 J	< 0.11 U	< 0.11 U	< 0.019 U	0.081		0.21	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	0.086	< 0.11 U		< 0.02 U	0.024 J	< 0.12 U	0.028 J	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	2.6	< 0.11 U		< 0.019 U	0.92	< 0.11 U	1.3	< 0.17 U	< 0.097 U	< 0.019 U
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	0.21	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.02 J	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	0.045 J	< 0.11 U		< 0.019 U	0.025 J	< 0.11 U	0.016 J	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	0.58	< 0.11 U		< 0.019 U	0.14	< 0.11 UT	0.16	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 UT	< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	0.11	< 0.11 U		< 0.019 U	0.035 J	< 0.11 U	0.044 J	< 0.17 U	< 0.097 U	< 0.018 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.016 J	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	0.22	< 0.19 UT		< 0.033 U	0.039 JT	< 0.19 U	0.085 JT	< 0.3 U	< 0.16 UT	< 0.031 UT
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	0.095	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	0.21	< 0.11 U		< 0.02 U	0.054 J	< 0.12 U	0.071 J	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	0.039 J	< 0.1 U		< 0.018 U	0.03 J	< 0.1 U	0.029 J	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.18 U	< 0.51 U		< 0.09 U	< 0.085 U	< 0.52 U	< 0.069 U	< 0.81 U	< 0.45 U	< 0.086 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	0.077 J	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.02 U
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	0.041 J	< 0.1 U	0.03 J	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	0.044 J	< 0.1 U		< 0.018 U	0.037 J	< 0.1 U	0.024 J	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	0.17	< 0.1 U		< 0.018 U	0.079	< 0.1 U	0.078	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	0.22	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.025 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	0.11	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	0.34	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.041 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.3	< 0.034 U	< 0.034 U	< 0.034 U	0.049 J		0.049 J	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.43	< 0.034 U	< 0.034 U	< 0.034 U	0.048 J		0.074 J	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	0.14	< 0.034 U	< 0.034 U	< 0.034 U	0.032 J		0.092	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	0.046 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	0.11	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.038 J	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	0.046 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	0.21	< 0.11 U		< 0.14 U	0.041 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	0.33	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	0.042 J	< 0.16 U	< 0.091 U	< 0.13 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.4	< 0.12 U	2
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.03 J
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.13
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.057 J	< 0.11 U	0.1
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	3 T	< 0.11 U	4.1 T
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.52 U	< 0.53 U	< 1 U		< 0.097 U	< 0.47 U	< 2.3 U	1.7	< 0.43 U	1.4
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.06 J
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.24
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.32 J	< 0.013 U	0.7
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	2.4	< 0.014 U	4.2
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.32	< 0.11 U	0.38
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	1.4	< 0.11 U	2.2
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.069 J	< 0.014 U	0.02 J
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.069 J	< 0.013 U	0.077 J
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.093 J	< 0.013 U	0.092 J
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.099 U	< 0.18 U	< 0.29 U		< 0.13 U	< 0.15 U	< 0.36 U	0.084 J	< 0.065 U	0.099 J
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.033 J	< 0.013 U	0.036 J
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.016 J	< 0.013 U	0.034 J
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.036 J	< 0.013 U	0.071 J
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.4	< 0.12 U	0.61
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.3 U	< 0.3 U	< 0.58 U		< 0.056 U	< 0.27 U	< 1.3 U	< 0.044 U	< 0.25 U	< 0.039 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.035 J	< 0.11 U	0.12
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	2.3	< 0.11 U	5.4
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.11	< 0.11 U	0.41
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.032 J	< 0.11 U	0.13
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.089	< 0.1 U	0.41
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.15	< 0.11 U	0.37
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.044 J
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.39	< 0.12 U	0.93
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.16	< 0.11 U	0.12
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.19	< 0.12 U	0.21
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	17	< 0.12 U	12
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.3	< 0.11 U	0.58
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.064 J	< 0.11 U	0.079
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	1.5	< 0.11 U	2.4
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.12
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.15	< 0.12 U	0.3
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.54	< 0.11 U	0.43
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.11	< 0.11 U	0.35
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.034 J	< 0.11 U	0.06 J
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.24 U	< 0.1 U	< 0.45 U		< 0.044 U	< 0.22 U	< 1 U	0.21	< 0.2 U	0.43
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.039 J	< 0.11 U	0.19
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated										
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.29	< 0.12 U	0.26
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.036 J
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.057 J	< 0.11 U	0.077
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.65 U	< 0.28 U	< 1.2 U		< 0.12 U	< 0.59 U	< 2.8 U	< 0.095 U	< 0.54 U	1.2
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.027 J
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.07 J	< 0.11 U	0.025 J
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.052 J	< 0.11 U	0.036 J
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.16	< 0.11 U	0.34
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.51	< 0.11 U	0.77
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.17	< 0.13 U	0.31
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.31	< 0.11 U	0.73
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.026 U		< 0.034 U	< 0.034 U	< 0.034 U	1.8	< 0.11 U	1.4
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.027 U		< 0.034 U	< 0.034 U	< 0.034 U	3 J	< 0.12 U	2.3 J
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.026 U		< 0.034 U	< 0.034 U	< 0.034 U	0.27	< 0.11 U	0.38
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.036 J	< 0.11 U	0.11
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.12	< 0.12 U	0.29
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.1	< 0.11 U	0.24
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.29	< 0.11 U	0.6
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.077	< 0.11 U	0.13
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.046 J
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.26	< 0.11 U	0.68

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated		< 0.56 U	< 0.59 U	< 0.5 U	< 0.47 U
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		< 0.055 U	< 0.12 U	< 0.18 U	< 0.23 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated		< 0.32 U	< 0.34 U	< 0.29 U	< 0.27 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated		< 0.028 U	< 0.27 U	< 0.046 U	< 0.036 U
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated					
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated					
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated		< 0.077 U	< 0.74 U	< 0.13 U	< 0.097 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated			0.185	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.035 J
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated			1.925	< 0.021 U	0.02 J	< 0.13 U	0.044 J	< 0.16 U	< 0.14 U	< 0.046 U	0.19
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated			0.046	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated			4.163	< 0.023 U	0.047 J	< 0.15 U	0.047 J	< 0.18 U	< 0.15 U	< 0.051 U	0.18
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated			9.396	< 0.023 U	0.13	< 0.14 U	0.15	< 0.18 U	< 0.15 U	< 0.05 U	0.9
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated			4.015	< 0.023 U	0.077 J	< 0.14 U	0.074 J	< 0.18 U	< 0.15 U	< 0.05 U	0.39
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated			6.67	< 0.023 U	0.094	< 0.14 U	0.11	< 0.18 U	< 0.15 U	< 0.05 UT	0.51
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated			0.137	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated			0.058	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated			0.323	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.042 J
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated			0.051	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated			5.587	< 0.021 U	0.049 J	< 0.13 U	0.11	< 0.16 U	< 0.13 U	< 0.046 U	0.62
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated			0.039	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated			1.041	< 0.021 U	0.029 J	< 0.13 U	0.027 J	< 0.16 U	< 0.14 U	< 0.046 U	0.092
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated			2.272	< 0.022 U	0.041 J	< 0.13 U	0.061 J	< 0.16 U	< 0.14 U	< 0.047 U	0.23
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated			0.502	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.043 J
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated			1.571	< 0.021 U	0.047 J	< 0.13 U	0.045 J	< 0.16 U	< 0.14 U	< 0.046 U	0.14
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated			0.906	< 0.022 U	0.03 J	< 0.14 U	0.044 J	< 0.17 U	< 0.14 U	< 0.048 U	0.088
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated			1.536	< 0.042 U	< 0.032 U	< 0.26 U	0.13 J	< 0.32 U	< 0.27 U	< 0.092 U	0.16
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated			0.326	< 0.021 U	< 0.016 U	< 0.13 U	0.049 J	< 0.16 U	< 0.13 U	< 0.046 U	0.092
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated			0.11	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated			4.15	< 0.022 U	0.12	< 0.13 U	0.11	< 0.16 U	< 0.14 U	< 0.047 U	0.33
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated			0.115	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.037 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated			0.338	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.044 J
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated			0.974	< 0.02 U	0.015 J	< 0.13 U	0.018 J	< 0.15 U	< 0.13 U	< 0.044 U	0.11
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated			0.271	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.037 J
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated			9.851	< 0.021 U	0.29	< 0.13 U	0.3	< 0.16 U	< 0.13 U	< 0.046 U	0.86
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated			22.867	< 0.041 U	0.44	< 0.25 U	0.59	< 0.31 U	< 0.26 U	< 0.088 U	2.4
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated			4.46	< 0.021 U	0.15	< 0.13 U	0.12	< 0.16 U	< 0.13 U	< 0.044 U	0.38
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated			7.62	< 0.022 U	0.14	< 0.14 U	0.19	< 0.17 U	< 0.14 U	< 0.048 U	0.71
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated			7.34	< 0.021 U	0.14	< 0.13 U	0.12	< 0.16 U	< 0.14 U	< 0.046 U	0.62
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated			0.654	< 0.02 U	0.015 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.067 J
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated			0.316	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.039 J
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated			0.914	< 0.021 U	0.018 J	< 0.13 U	0.019 J	< 0.16 U	< 0.14 U	< 0.046 U	0.078
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated			6.18	< 0.022 U	0.14	< 0.13 U	0.24	< 0.16 U	< 0.14 U	< 0.046 U	0.51
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated			0.438	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.045 J
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated			4.827	< 0.022 U	0.057 J	< 0.14 U	0.11	< 0.17 U	< 0.14 U	< 0.048 U	0.46
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated			5.434	< 0.022 U	0.12	< 0.14 U	0.14	< 0.17 U	< 0.14 U	< 0.048 U	0.47
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated			0.021	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated			0.039	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated			6.04	< 0.1 U	< 0.079 U	< 0.64 U	0.14 J	< 0.79 U	< 0.66 U	< 0.22 U	0.47
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated			3.388	< 0.042 U	0.084 J	< 0.26 U	0.088 J	< 0.32 U	< 0.27 U	< 0.091 U	0.26
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated			9.751	0.33	< 0.03 U	< 0.25 U	< 0.036 U	< 0.3 U	< 0.25 U	< 0.086 U	0.54
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated			2.57	< 0.043 U	< 0.033 U	< 0.27 U	< 0.039 U	< 0.33 U	< 0.27 U	< 0.093 U	0.31
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated			3.23	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	0.24 J	0.096
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated			2.673	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.17
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated			14.458	< 0.023 U	0.15	< 0.14 U	0.31	< 0.18 U	< 0.15 U	< 0.05 U	1.6
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated			1.189	< 0.023 U	< 0.017 U	< 0.14 U	0.043 J	< 0.17 U	< 0.14 U	< 0.049 U	0.1
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated			0.076	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 UT	< 0.034 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated			1.108	< 0.022 U	0.019 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.13
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated			0.927	< 0.021 U	< 0.016 U	< 0.13 U	0.02 J	< 0.16 U	< 0.14 U	< 0.046 U	0.083
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated			0.262	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated			11.91	0.033 J	0.23	< 0.14 U	0.26	< 0.17 U	< 0.14 U	< 0.049 U	1
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated			4.422	< 0.021 U	0.087	< 0.13 U	0.076	< 0.16 U	< 0.14 U	< 0.046 U	0.4
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated			0.241	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.034 J
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated			0.257	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	0.039 J
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated			0.128	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated			8.118	< 0.023 U	0.13	< 0.14 U	0.19	< 0.17 U	< 0.14 U	< 0.049 U	0.71
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated			5.86	< 0.022 U	0.11	< 0.14 U	0.11	< 0.17 U	< 0.14 U	< 0.048 U	0.51

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.031 U	0.036 J	0.021 J	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	0.15	0.21	0.077	0.13	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	0.3	0.39	0.12	1.2	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	0.8	0.97	0.35	0.65	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	0.33	0.39	0.2	0.3	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	0.52	0.67	0.3	0.75	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.035 U	0.027 J	< 0.025 U	0.022 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.034 U	0.02 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	0.033 J	0.042 J	< 0.022 U	0.025 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	0.44	0.52	0.23	0.25	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	0.081	0.11	0.041 J	0.11	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.25 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	0.18	0.22	0.088	0.17	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	0.041 J	0.056 J	< 0.023 U	0.066 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	0.14	0.19	0.075	0.13	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.033 U	0.074 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.064 U	0.21	0.066 J	< 0.032 U	< 0.27 U	< 0.027 U	< 0.055 U	< 0.79 U	< 0.31 U	< 0.51 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.033 U	0.027 J	< 0.023 U	0.016 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	0.31	0.42	0.16	0.68	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.033 U	0.022 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.031 U	0.045 J	< 0.021 U	0.036 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	0.088	0.13	0.028 J	0.065 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.032 U	0.038 J	< 0.022 U	0.027 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.79	1	0.43	0.78	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	1.7	2.2	0.93	1.2	< 0.26 U	< 0.026 U	< 0.053 U	< 0.76 U	< 0.3 U	< 0.49 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.36	0.49	0.2	0.39	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	0.6	0.82	0.29	0.56	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	0.62	0.89	0.3	0.6	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	0.6 J	< 0.16 U	< 0.26 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	0.051 J	0.084	0.029 J	0.052 J	< 0.13 U	< 0.013 U	< 0.026 U	0.63 J	< 0.15 U	< 0.24 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	0.035 J	0.051 J	< 0.023 U	0.036 J	< 0.14 U	< 0.014 U	< 0.028 U	0.67 J	< 0.16 U	< 0.26 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	0.067 J	0.11	0.036 J	0.066 J	< 0.14 U	< 0.014 U	< 0.028 U	0.64 J	< 0.16 U	< 0.26 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	0.41	0.6	0.21	0.33	< 0.14 U	< 0.014 U	< 0.028 U	0.74 J	< 0.16 U	< 0.26 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	0.036 J	0.058 J	< 0.023 U	0.031 J	< 0.14 U	< 0.014 U	< 0.028 U	0.65 J	< 0.16 U	< 0.26 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	0.36	0.49	0.19	0.27	< 0.14 U	< 0.014 U	< 0.029 U	0.68 J	< 0.17 U	< 0.27 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	0.39	0.66	0.14	0.42	< 0.14 U	< 0.014 U	< 0.028 U	1.2 J	< 0.16 U	< 0.26 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	0.58	0.66	0.15 J	0.42	< 0.66 U	< 0.066 U	< 0.13 U	< 1.9 U	< 0.77 U	< 1.2 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	0.31	0.43	0.13 J	0.39	< 0.27 U	< 0.027 U	< 0.054 U	< 0.78 U	< 0.31 U	< 0.5 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.06 U	0.31	0.19	< 0.03 U	< 0.25 U	< 0.025 U	< 0.051 U	< 0.74 U	< 0.29 U	< 0.48 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.065 U	< 0.037 U	< 0.045 U	< 0.032 U	< 0.27 U	< 0.027 U	< 0.055 U	< 0.8 U	< 0.32 U	< 0.51 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.035 U	0.14	0.05 J	0.12	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	0.069 J	0.11	0.046 J	0.05 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	1.2	1.4	0.49	0.7	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	0.079	0.1	0.04 J	0.071 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	0.099	0.13	0.082	0.078	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	0.068 J	0.1	0.041 J	0.071 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.036 U	0.027 J	< 0.025 U	0.022 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	0.98	1.2	0.53	0.76	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	0.42	0.54	0.21	0.38	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	0.035 J	0.038 J	< 0.022 U	0.021 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	0.036 J	0.046 J	< 0.022 U	0.035 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.034 U	0.026 J	< 0.023 U	0.019 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	0.69	0.81	0.31	0.52	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	0.52	0.69	0.23	0.46	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.23 UT	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.19	< 0.047 U	< 0.14 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.22	0.14	< 0.15 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.26 U	0.047 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.88	0.14	< 0.15 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.26 U	0.041 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.39	0.073 J	< 0.15 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.26 U	0.054 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.48	0.13	< 0.15 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.47	0.065 J	< 0.14 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.084	< 0.048 U	< 0.14 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.24 U	0.023 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.19	0.051 J	< 0.14 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.054 J	< 0.049 U	< 0.14 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.15	< 0.048 U	< 0.14 U
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.16	< 0.049 U	< 0.14 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.48 U	< 0.035 U	< 0.19 U	< 0.26 U	< 0.034 U	< 0.27 U	< 0.25 U	0.25	< 0.094 U	< 0.27 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.1	< 0.047 U	< 0.14 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.34	0.07 J	< 0.14 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.048 U	< 0.055 U	< 0.16 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.042 J	< 0.046 U	< 0.13 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.098	< 0.045 U	< 0.13 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.24 U	0.063 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.82	0.14	< 0.14 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.46 U	0.17	< 0.19 U	< 0.25 U	< 0.033 U	< 0.26 U	< 0.24 U	1.9	0.31	< 0.26 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.23 U	0.039 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.39	0.11	< 0.13 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.25 U	0.1	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.7	0.14	< 0.14 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.24 U	0.12	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.75	0.14	< 0.14 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.069 J	< 0.045 U	< 0.13 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.091	< 0.048 U	< 0.14 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.24 U	0.082	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.55	0.081	< 0.14 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.044 J	< 0.048 U	< 0.14 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.25 U	0.056 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.41	0.071 J	< 0.14 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.25 U	0.058 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.43	0.096	< 0.14 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 1.2 U	< 0.085 U	< 0.47 U	< 0.63 U	< 0.083 U	< 0.67 U	< 0.6 U	1.1	< 0.23 U	< 0.67 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.48 U	0.043 J	< 0.19 U	< 0.26 U	< 0.034 U	< 0.27 U	< 0.24 U	0.3	< 0.094 U	< 0.27 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.45 U	< 0.032 U	< 0.18 U	< 0.24 U	< 0.032 U	< 0.26 U	< 0.23 U	3.5	< 0.089 U	< 0.26 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.49 U	< 0.035 U	< 0.2 U	< 0.26 U	< 0.034 U	< 0.28 U	< 0.25 U	1.1	< 0.096 U	< 0.28 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.8	< 0.052 U	< 0.15 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.6	< 0.049 U	< 0.14 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.26 U	0.15	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	1.2	0.19	< 0.15 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.13	< 0.05 U	< 0.14 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.14	< 0.048 U	< 0.14 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.11	< 0.048 U	< 0.14 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.25 U	0.14	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.93	0.16	< 0.14 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.24 U	0.057 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.39	0.086	< 0.14 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.25 U	0.11	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.69	0.13	< 0.14 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.25 U	0.071 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.51	0.1	< 0.14 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	0.53	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 UT
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.35 UT	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 UT	< 0.14 U	< 2.3 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.69 U	< 0.057 U	< 0.26 U	< 0.25 U	< 0.29 U	< 0.32 U	< 0.43 U	< 1.3 U	< 0.29 U	< 4.6 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 0.36 U	< 0.03 U	0.16 J	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.66 U	< 0.055 U	< 0.25 U	< 0.24 U	< 0.28 U	< 0.31 U	< 0.41 U	< 1.2 U	< 0.28 U	< 4.4 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 1.7 U	< 0.14 U	< 0.63 U	< 0.61 U	< 0.72 U	< 0.79 U	< 1.1 U	< 3.1 U	< 0.7 U	< 11 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.68 U	< 0.057 U	< 0.26 U	< 0.25 U	< 0.29 U	< 0.32 U	< 0.43 U	< 1.3 U	< 0.29 U	< 4.6 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.65 U	< 0.053 U	< 0.24 U	< 0.23 U	< 0.27 U	< 0.3 U	< 0.4 U	< 1.2 U	< 0.27 U	< 4.3 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.7 U	< 0.058 U	< 0.26 U	< 0.25 U	< 0.3 U	< 0.33 U	< 0.43 U	< 1.3 U	< 0.29 U	< 4.6 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	0.22 J	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 UT	< 0.15 U	< 2.4 UT
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.21 U	< 0.11 UT			0.045 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.22 U	< 0.12 U			0.3	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.23 U	< 0.12 U			0.024 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.24 U	< 0.13 U			0.28	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.24 U	< 0.13 U			1.7	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.24 U	< 0.13 U			0.69	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.24 U	< 0.13 U			0.91	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.24 U	< 0.13 U			0.041 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.24 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.23 U	< 0.12 U			0.02 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.21 U	< 0.11 U			0.07 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.21 U	< 0.11 U			0.028 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.22 U	< 0.11 U			1.2	0.019 J	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.21 U	< 0.11 U			0.019 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.22 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.22 U	< 0.12 U			0.37	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.23 U	< 0.12 U			0.074 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.22 U	< 0.12 U			0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.23 U	< 0.12 U			0.09	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.44 U	< 0.23 U			0.19	< 0.029 U	< 0.053 U	< 0.043 U	< 0.075 U	< 0.26 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.23 U	< 0.12 U			0.037 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.22 U	< 0.12 U			0.48	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.23 U	< 0.12 U			0.035 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.26 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.21 U	< 0.11 U			0.06 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.21 U	< 0.11 U			0.15	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.22 U	< 0.12 U			0.049 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.22 U	< 0.11 U			1.4	0.041 J	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.42 U	< 0.22 U			4.3	0.067 J	< 0.051 U	< 0.042 U	< 0.073 U	< 0.25 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.21 U	< 0.11 U			0.54	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.23 U	< 0.12 U			1.1	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.22 U	< 0.12 U			1	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.21 U	< 0.11 U			0.099	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.23 U	< 0.12 U			0.06 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.22 U	< 0.12 U			0.14	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.22 U	< 0.12 U			1.1	0.029 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.23 U	< 0.12 U			0.075 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.23 U	< 0.12 U			0.88	0.022 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.23 U	< 0.12 U			0.82	0.018 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.22 U	< 0.12 U			0.02 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 1.1 U	< 0.56 U			0.58	< 0.071 U	< 0.13 U	< 0.11 U	< 0.18 U	< 0.64 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.44 U	< 0.23 U			0.37	< 0.029 U	< 0.053 U	< 0.043 U	< 0.075 U	< 0.26 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.41 U	< 0.22 U			1	< 0.027 U	< 0.05 U	< 0.04 U	< 0.071 U	< 0.25 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.45 U	< 0.23 U			0.31	< 0.029 U	< 0.054 U	< 0.044 U	< 0.076 U	< 0.26 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.24 U	< 0.13 U			0.4	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.23 U	< 0.12 U			0.27	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.24 U	< 0.12 U			2.9	0.048 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.23 U	< 0.12 U			0.2	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.23 U	< 0.12 U			0.024 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.22 U	< 0.12 U			0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.22 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.24 U	< 0.13 U			0.046 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			2.1	0.057 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.22 U	< 0.12 U			0.65	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.22 U	< 0.12 U			0.05 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.22 U	< 0.11 U			0.053 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			0.043 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			1.4	0.018 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			0.9	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	0.12	< 0.11 U		< 0.14 U	0.018 J	< 0.11 U	0.034 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	0.76	< 0.12 U		< 0.15 U	0.041 J	< 0.12 U	0.086	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	0.56	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	0.036 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	0.26	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	0.028 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	0.64	< 0.12 U		< 0.15 U	0.1	< 0.12 U	0.29	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	0.018 J	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	0.26	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.033 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	0.096	< 0.11 U		< 0.14 U	0.02 J	< 0.11 U	0.054 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	0.16	< 0.11 U		< 0.14 U	0.019 J	< 0.11 U	0.042 J	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	0.047 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.018 J	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	0.1	< 0.11 U		< 0.14 U	0.04 J	< 0.11 U	0.081	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.16	< 0.11 U	0.08	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.073 U	< 0.21 U		< 0.28 U	0.14 J	< 0.22 U	0.12 J	< 0.34 U	< 0.19 U	< 0.27 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	0.03 J	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	0.26	< 0.11 U		< 0.14 U	0.049 J	< 0.11 U	0.16	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.043 U	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	0.017 J	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	0.058 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.026 J	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.034 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.62	< 0.11 U		< 0.14 U	0.066 J	< 0.11 U	0.18	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	1.2	< 0.2 U		< 0.27 U	0.085 J	< 0.21 U	0.27	< 0.32 U	< 0.18 U	< 0.26 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.33	< 0.1 U		< 0.13 U	0.075	< 0.1 U	0.2	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	0.45	< 0.11 U		< 0.14 U	0.065 J	< 0.11 U	0.18	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	0.54	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	0.045 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.021 J	< 0.16 U	< 0.09 U	< 0.13 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	0.06 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.03 J	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	0.3	< 0.11 U		< 0.14 U	0.045 J	< 0.11 U	0.11	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.035 J	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	0.27	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	0.044 J	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	0.38	< 0.11 U		< 0.14 U	0.067 J	< 0.11 U	0.19	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	0.32 J	< 0.52 U		< 0.68 U	0.12 J	< 0.53 U	< 0.07 U	< 0.82 U	< 0.46 U	< 0.67 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	0.33	< 0.21 U		< 0.28 U	0.049 J	< 0.22 U	0.12 J	< 0.33 U	< 0.19 U	< 0.27 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.069 U	< 0.2 U		< 0.26 U	0.15	< 0.2 U	0.081 J	< 0.32 U	< 0.18 U	< 0.26 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.074 U	< 0.21 U		< 0.28 U	0.039 J	< 0.22 U	< 0.029 U	< 0.34 U	< 0.19 U	< 0.28 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	0.093	< 0.12 U		< 0.15 U	0.039 J	< 0.12 U	0.041 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	0.059 J	< 0.11 U		< 0.14 U	0.04 J	< 0.11 U	0.039 J	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	0.72	< 0.11 U		< 0.15 U	0.024 J	< 0.12 U	0.12	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	0.066 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	0.074 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	0.052 J	< 0.11 U		< 0.14 U	0.028 J	< 0.11 U	0.037 J	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	0.023 J	< 0.12 U	0.078 J	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	0.71	< 0.11 U		< 0.15 U	0.065 J	< 0.11 U	0.19	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	0.32	< 0.11 U		< 0.14 U	0.041 J	< 0.11 U	0.12	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	0.49	< 0.11 U		< 0.15 U	0.037 J	< 0.11 U	0.14	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	0.42	< 0.11 U		< 0.15 U	0.056 J	< 0.11 U	0.2	< 0.18 U	< 0.099 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.048 J
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.18	< 0.11 U	0.3
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	0.022 J
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.65 U	0.16	0.16 J	0.28
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.46	< 0.12 U	1.8
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.2	< 0.12 U	0.69
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.46	< 0.12 U	0.9
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	0.047 J
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.018 J
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.03 J	< 0.11 U	0.063 J
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.023 J
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.27	< 0.11 U	1.1
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.02 J
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.066 J	< 0.11 U	0.16
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.17	< 0.11 U	0.34
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.029 J	< 0.12 U	0.074 J
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.11	< 0.11 U	0.22
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.27	< 0.12 U	0.1
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.27 U	< 0.27 U	< 0.52 U		< 0.05 U	< 0.25 U	< 1.2 U	0.21	< 0.22 U	0.2
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.085	< 0.11 U	< 0.017 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	0.03 J
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.25	< 0.11 U	0.58
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.12 U	0.031 J
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.033 J	< 0.11 U	0.061 J
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.053 J	< 0.11 U	0.15
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.035 J	< 0.11 U	0.051 J
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.89	< 0.11 U	1.6
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.26 U	< 0.26 U	< 0.5 U		< 0.048 U	< 0.24 U	< 1.1 U	2.2	< 0.22 U	3.6
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.29	< 0.11 U	0.66
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.58	< 0.12 U	1.3
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.46	< 0.11 U	1.3
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.037 J	< 0.11 U	0.1
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.032 J	< 0.12 U	0.063 J
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.077	< 0.11 U	0.14
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.77	< 0.11 U	0.94
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.042 J	< 0.11 U	0.072 J
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.46	< 0.12 U	0.79
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.48	< 0.12 U	0.8
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.021 J
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.019 J
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.66 U	< 0.67 U	< 1.3 U		< 0.12 U	< 0.6 U	< 2.9 U	0.62	< 0.55 U	1
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.27 U	< 0.27 U	< 0.51 U		< 0.05 U	< 0.24 U	< 1.2 U	0.23	< 0.22 U	0.43
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.25 U	< 0.26 U	< 0.49 U		< 0.047 U	< 0.23 U	< 1.1 U	2	< 0.21 U	1.8
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.27 U	< 0.28 U	< 0.52 U		< 0.051 U	< 0.25 U	< 1.2 U	0.44	< 0.23 U	0.41
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	1	< 0.12 U	0.49
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.93	< 0.11 U	0.33
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.98	< 0.12 U	2.6
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.18	< 0.12 U	0.18
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.12 U	0.025 J
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.055 J	< 0.11 U	0.17
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.095	< 0.11 U	0.13
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.042 J	< 0.12 U	0.047 J
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	1.3	< 0.12 U	1.7
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.23	< 0.11 U	0.6
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.022 J	< 0.11 U	0.041 J
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.048 J
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.04 J
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.82	< 0.12 U	1.2
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.41	< 0.12 U	0.8

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated		< 0.29 U	< 0.31 U	< 0.26 U	< 0.25 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated		< 0.28 U	< 0.3 U	< 0.25 U	< 0.24 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated		< 0.72 U	< 0.75 U	< 0.63 U	< 0.6 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated		< 0.29 U	< 0.31 U	< 0.26 U	< 0.24 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated		< 0.27 U	< 0.29 U	< 0.24 U	< 0.23 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated		< 0.3 U	< 0.31 U	< 0.26 U	< 0.25 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated			0.175	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated			2.773	< 0.022 U	0.062 J	< 0.13 U	0.053 J	< 0.16 U	< 0.14 U	< 0.047 U	0.25
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated			1.635	< 0.021 U	0.023 J	< 0.13 U	0.022 J	< 0.16 U	< 0.13 U	< 0.046 U	0.17
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated			0.043	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated			1.435	< 0.021 U	0.023 J	< 0.13 U	0.033 J	< 0.16 U	< 0.14 U	< 0.046 U	0.14
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated			21.12	< 0.15 U	0.63	< 0.93 U	0.34 J	< 1.1 U	< 0.95 U	< 0.32 U	1.5
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated			0.519	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.043 J
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated			2.814	< 0.023 U	0.08 J	< 0.14 U	0.054 J	< 0.18 U	< 0.15 U	< 0.05 U	0.25
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated			2.162	< 0.021 U	0.046 J	< 0.13 U	0.047 J	< 0.16 U	< 0.13 U	< 0.045 U	0.24
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated			2.612	< 0.022 U	0.045 J	< 0.14 U	0.091	< 0.17 U	< 0.14 U	< 0.047 U	0.24
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated			0.144	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated			0.297	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.036 J
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated			1.775	< 0.023 U	0.025 J	< 0.14 U	0.038 J	< 0.17 U	< 0.14 U	< 0.049 U	0.17
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated			0.05	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated			0.104	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated			1.057	< 0.022 U	< 0.016 U	< 0.13 U	0.027 J	< 0.16 U	< 0.14 U	< 0.047 U	0.092
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated			0.04	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated			0.568	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.065 J
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated			1.105	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	0.1
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated			0.949	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.09
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated			0.764	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.066 J
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.035 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated			0.081	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated			0.314	< 0.021 U	0.016 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.043 J
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated			0.335	< 0.4 U	< 0.4 U		< 0.4 U				0.041 J
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.015 U
Football Field	SSHS-B2686	052219 08:40_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U		< 0.014 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated			4.732	0.04 J	0.045 J	< 0.021 U	0.047 J	< 0.17 U	0.016 J	< 0.047 UT	0.69
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated			0.756	< 0.022 U	0.09	< 0.021 U	0.077	< 0.17 U	< 0.016 U	< 0.047 U	0.046 J
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated			0.045	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	800	7.164	< 0.021 U	0.14	< 0.02 U	0.14	< 0.16 U	0.031 J	< 0.045 U	0.68
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	880	4.04	< 0.02 U	0.06 J	< 0.019 U	0.1	< 0.16 U	< 0.015 U	< 0.044 U	0.36
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 36 U	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	9100	1.54	< 0.021 U	< 0.016 U	< 0.02 U	0.17	< 0.16 U	< 0.015 U	< 0.045 U	0.18
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	5300	1.46	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	0.24
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	8200	0.41	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	8100	1.37	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	0.23
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	7700	2.657	< 0.021 U	< 0.016 U	< 0.02 U	0.21	< 0.16 U	< 0.015 U	< 0.045 UT	0.4
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	2200	0.787	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.055 J
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	1400	2.613	0.023 J	< 0.017 U	< 0.021 U	0.047 J	< 0.17 U	< 0.016 U	< 0.048 U	0.27
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	290	0.403	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	1800	1.544	< 0.021 U	0.03 J	< 0.02 U	0.037 J	< 0.16 U	< 0.015 U	< 0.045 U	0.12
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	1400	0.491	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	0.044 J
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated		0.479	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	0.039 J
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	160	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated		1.82	< 0.041 U	< 0.032 U	< 0.039 U	< 0.037 U	< 0.32 U	< 0.03 U	< 0.089 U	0.33
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated		0.342	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated		ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated		7.615	0.028 J	0.33	< 0.14 U	0.22	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 UT	

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.034 U	0.037 J	< 0.023 U	0.023 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	0.24	0.3	0.13	0.2	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	0.16	0.2	0.082	0.13	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.034 U	0.024 J	< 0.024 U	0.019 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	0.12	0.16	0.05 J	0.11	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	2.5	3.6	1.1	3.2	< 0.95 U	< 0.094 U	< 0.19 U	< 2.8 U	< 1.1 U	< 1.8 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.034 U	0.11	0.031 J	0.039 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	0.24	0.32	0.11	0.28	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	0.18	0.27	0.092	0.16	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	0.21	0.23	0.091	0.14	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.033 U	0.02 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	0.035 J	0.039 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	0.14	0.17	0.068 J	0.11	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.032 U	0.025 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	0.086	0.097	0.045 J	0.063 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	0.058 J	0.066 J	0.025 J	0.047 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	0.082	0.13	0.042 J	0.084	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	0.1	0.074 J	0.07 J	0.087	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	0.069 J	0.093	0.029 J	0.056 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.031 U	0.02 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	0.035 J	0.042 J	< 0.022 U	0.043 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	0.042 J	0.044 J	0.043 J	< 0.4 U						
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.017 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U	< 0.27 U
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	0.21	0.17	0.24	0.16	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	0.053 J	0.06 J	< 0.023 U	0.16	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	0.73	0.87	0.25	0.53	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 UT
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	0.27	0.32	0.15	0.28	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	0.074	0.096	0.026 J	0.092	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	0.19	0.27	0.068 J	0.18	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	0.086	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	0.14	0.16	0.045 J	0.14	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	0.061 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.062 U	< 0.035 U	< 0.043 U	< 0.031 U	< 0.034 U	< 0.026 U	< 0.053 U	< 0.77 U	< 0.05 U	< 0.49 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	0.036 J	0.055 J	0.027 J	0.04 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	0.78	1	0.23	0.64	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.25 U	0.023 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.24	0.048 J	< 0.14 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.18	< 0.047 U	< 0.14 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.16	< 0.048 U	< 0.14 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 1.7 U	0.28 J	< 0.68 U	< 0.91 U	< 0.12 U	< 0.96 U	< 0.86 U	1.9	0.63	< 0.96 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.097	< 0.05 U	< 0.14 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.26 U	0.027 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.22	< 0.052 U	< 0.15 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.24	< 0.046 U	< 0.13 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.23	< 0.049 U	< 0.14 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.046 J	< 0.05 U	< 0.14 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.16	< 0.05 U	< 0.15 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.099	< 0.048 U	< 0.14 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.077 J	< 0.05 U	< 0.14 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.2	< 0.051 U	< 0.15 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.1	< 0.048 U	< 0.14 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.075	< 0.047 U	< 0.14 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated								0.052 J	< 0.4 U	< 0.4 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.016 U	< 0.018 U	< 0.017 U
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.1	0.058 J	< 0.017 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.063 J	< 0.049 U	< 0.017 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.24 U	0.12	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.68	0.13	0.032 J
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.42	0.08	0.025 J
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.55	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.62	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.52	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.9	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.087	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.25 U	0.053 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.24	< 0.049 U	< 0.017 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.072 J	< 0.053 U	< 0.018 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.21	< 0.046 U	0.018 J
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.13	< 0.05 U	< 0.017 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.15	< 0.05 U	< 0.017 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.47 U	< 0.034 U	< 0.049 U	< 0.034 U	< 0.033 U	< 0.033 U	< 0.044 U	0.7	< 0.092 U	< 0.032 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.047 J	< 0.047 U	< 0.016 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	< 0.26 U	0.044 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.88	0.16	< 0.15 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 2.4 U	< 0.2 U	< 0.91 U	< 0.87 U	< 1 U	< 1.1 U	< 1.5 U	< 4.5 U	< 1 U	< 16 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated										
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	0.028 J	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 UT
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 UT	< 0.024 U	< 2.2 UT
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.67 U	< 0.055 U	< 0.25 U	< 0.045 U	< 0.053 U	< 0.32 U	< 0.42 U	< 1.2 U	< 0.044 U	< 4 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.23 U	< 0.12 U			0.048 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.22 U	< 0.12 U			0.43	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.22 U	< 0.11 U			0.26	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.22 U	< 0.12 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.22 U	< 0.12 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.22 U	< 0.12 U			0.23	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 1.5 U	< 0.81 U			1.6	< 0.1 U	< 0.19 U	< 0.15 U	< 0.27 U	< 0.92 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.23 U	< 0.12 U			0.072 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.24 U	< 0.13 U			0.39	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.22 U	< 0.11 U			0.34	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			0.52	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			0.051 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			0.057 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.24 U	< 0.12 U			0.34	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.22 U	< 0.11 U			0.025 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.22 U	< 0.12 U			0.029 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.22 U	< 0.12 U			0.18	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.23 U	< 0.12 U			0.02 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.23 U	< 0.12 U			0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.24 U	< 0.12 U			0.15	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.22 U	< 0.12 U			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.22 U	< 0.12 U			0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.22 U	< 0.11 U			0.029 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.21 U	< 0.11 U			0.055 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated					0.053 J	< 0.4 U	< 0.4 U			
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.02 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U
Football Field	SSHS-B2686	052219 08:40_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.019 U	< 0.12 U			0.43	0.088	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	< 0.057 U	< 0.12 U			0.06 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 0.055 U	< 0.11 U			0.024 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.055 U	< 0.11 U			1.1	0.024 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.054 U	< 0.11 U			0.54	0.028 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.056 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.055 U	< 0.11 UT			0.24	0.047 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.055 U	< 0.11 U			0.088	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.058 U	< 0.12 U			0.34	0.025 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	< 0.063 U	< 0.13 U			0.05 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	< 0.054 U	< 0.11 U			0.19	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 0.059 U	< 0.12 U			0.056 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.11 U	< 0.22 U			< 0.038 U	< 0.028 U	< 0.052 U	< 0.042 U	< 0.074 U	< 0.037 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.055 U	< 0.11 U			0.054 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	< 0.24 U	< 0.13 U			1.2	0.045 J	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	0.18	< 0.11 U		< 0.14 U	0.02 J	< 0.11 U	0.082	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	0.11	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.026 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	0.082	< 0.11 U		< 0.14 U	0.028 J	< 0.11 U	0.042 J	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	2.5	< 0.74 U		< 0.97 U	0.17 J	< 0.76 U	0.45 J	< 1.2 U	< 0.66 U	< 0.97 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	0.042 J	< 0.11 U		< 0.15 U	0.059 J	< 0.11 U	0.036 J	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	0.23	< 0.12 U		< 0.15 U	0.058 J	< 0.12 U	0.16	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	0.13	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	0.13	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	0.099	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	0.054 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.034 J	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	0.058 J	< 0.11 U		< 0.15 U	0.022 J	< 0.12 U	0.019 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	0.077	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	0.052 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.021 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	0.035 J	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	< 0.4 U	< 0.4 U				< 0.4 U	< 0.4 U			
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.016 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	0.14	< 0.11 U		< 0.019 U	0.064 J	< 0.11 U	0.049 J	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	0.097	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	0.016 J	< 0.17 U	< 0.097 U	< 0.018 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	0.43	< 0.1 U		< 0.018 U	0.068 J	< 0.11 U	0.07 J	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	0.24	< 0.1 U		< 0.018 U	0.059 J	< 0.1 UT	0.072	< 0.16 U	< 0.09 U	< 0.017 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 UT	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	0.03 J	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.036 U	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	0.068 J	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	0.027 J	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	0.13	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	0.06 J	< 0.12 U		< 0.021 U	0.02 J	< 0.12 U	0.029 J	< 0.19 UT	< 0.11 U	< 0.02 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	0.098	< 0.1 U		< 0.018 U	0.059 J	< 0.11 U	0.064 J	< 0.16 UT	< 0.092 U	< 0.018 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	0.033 J	< 0.12 U	0.025 J	< 0.18 UT	< 0.1 U	< 0.019 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.072 U	< 0.21 U		< 0.037 U	< 0.035 U	< 0.21 U	< 0.028 U	< 0.33 U	< 0.18 U	< 0.035 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	0.54	< 0.12 U		< 0.15 U	0.058 J	< 0.12 U	0.092	< 0.18 U	< 0.1 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.022 J	< 0.12 U	0.045 J
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.17	< 0.11 U	0.45
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.055 J	< 0.11 U	0.24
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.078	< 0.11 U	0.23
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.95 U	< 0.96 U	< 1.8 U		< 0.18 U	< 0.86 U	< 4.2 U	< 0.14 U	< 0.79 U	1.8
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.049 J
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.14	< 0.12 U	0.42
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.093	< 0.11 U	0.37
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.02 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.28	< 0.11 U	0.45
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.032 J	< 0.12 U	0.041 J
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.029 J	< 0.12 U	0.055 J
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.18	< 0.12 U	0.3
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.025 J
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.022 J	< 0.11 U	0.028 J
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.11	< 0.11 U	0.17
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.02 J
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.12
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.08	< 0.12 U	0.16
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.061 J	< 0.11 U	0.16
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.083	< 0.11 U	0.11
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.032 J
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.061 J
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated							< 2 U	< 0.4 U	< 0.4 U	0.06 J
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	SSHS-B2686	052219 08:40_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.52	< 0.11 U	0.79
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.056 J	< 0.12 U	0.068 J
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.021 J
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.43	< 0.11 U	1.1
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.5	< 0.11 U	0.68
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.23	< 0.11 U	0.41
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.23	< 0.11 U	0.37
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.21	< 0.11 U	0.2
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.16	< 0.11 U	0.46
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.27	< 0.11 U	0.59
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.064 J	< 0.11 U	0.11
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.35	< 0.12 U	0.48
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	< 0.15 U	< 0.066 U	< 0.29 UT		< 0.028 U	< 0.14 U	< 0.67 U	0.052 J	< 0.13 U	0.054 J
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 UT		< 0.024 U	< 0.12 U	< 0.58 U	0.15	< 0.11 U	0.19
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 0.14 U	< 0.062 U	< 0.28 UT		< 0.027 U	< 0.13 U	< 0.63 U	0.11	< 0.12 U	0.065 J
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.16	< 0.12 U	0.13
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.26 U	< 0.11 U	< 0.5 U		< 0.049 U	< 0.24 U	< 1.2 U	< 0.039 U	< 0.22 U	0.79
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.034 J	< 0.11 U	0.049 J
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.4	< 0.12 U	1.4 T

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	18013211411	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated		< 1 U	< 1.1 U	< 0.9 U	< 0.86 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated					
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B2686	052219 08:40_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated		< 0.031 U	< 0.3 U	< 0.051 U	< 0.039 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated			3.471	< 0.021 U	0.12	< 0.13 U	0.089	< 0.16 U	< 0.13 U	< 0.046 U	0.32
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated			9.232	0.03 J	0.31	< 0.14 U	0.25	< 0.17 U	< 0.14 U	< 0.049 U	0.79
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated			1.468	< 0.021 U	< 0.016 U	< 0.13 U	0.027 J	< 0.16 U	< 0.13 U	< 0.045 U	0.16
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated			27.349	< 0.021 U	0.65	< 0.13 U	0.55	< 0.16 U	< 0.13 U	< 0.044 U	7.9
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated			7.843	< 0.02 U	0.11	< 0.13 U	0.18	< 0.16 U	< 0.13 U	< 0.044 U	0.82
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated			18.79	0.39	0.07 J	< 0.034 U	0.78	< 0.25 U	< 0.034 U	< 0.071 U	1.6
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated			0.914	< 0.034 U	0.017 J	< 0.034 U	0.026 J	< 0.16 U	< 0.034 U	< 0.046 U	0.076
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated			1.843	< 0.021 U	0.043 J	< 0.13 U	0.042 J	< 0.16 U	< 0.13 U	< 0.045 U	0.16
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated			0.168	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.033 J
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated			0.745	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.078
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated			1.024	< 0.022 U	< 0.016 U	< 0.13 U	0.031 J	< 0.16 U	< 0.14 U	< 0.047 U	0.1
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated			5.904	< 0.023 U	0.1	< 0.14 U	0.095	< 0.18 U	< 0.15 U	< 0.05 U	0.49
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated			5.608	< 0.02 U	0.1	< 0.12 U	0.13	< 0.15 U	< 0.13 U	< 0.043 U	0.48
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated			0.025	< 0.023 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 UT	< 0.037 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated			0.137	< 0.023 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated			5.462	< 0.023 U	0.05 J	< 0.14 U	0.07 J	< 0.17 U	< 0.14 U	< 0.049 U	0.59
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated			0.457	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.054 J
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated			3.727	< 0.023 U	0.048 J	< 0.14 U	0.043 J	< 0.17 U	< 0.14 U	< 0.049 U	0.38
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated			0.646	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.069 J
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated			0.224	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated			1.091	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.14
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated			0.044	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated			0.521	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.062 J
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.05 U	< 0.036 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated			2.379	< 0.022 U	0.056 J	< 0.13 U	0.031 J	< 0.16 U	< 0.14 U	< 0.047 U	0.27
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated			0.968	< 0.021 U	0.026 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.093
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated			26.55	< 0.018 U	0.55	< 0.26 U	1.2	< 0.84 U	< 0.4 U	< 0.54 U	2
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated			0.543	< 0.02 U	< 0.015 U	< 0.019 U	0.032 J	< 0.15 U	< 0.015 U	< 0.043 U	0.047 J
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.014 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated		70									
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	70										
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated			15.681	< 0.025 U	0.041 J	< 0.023 U	0.23	< 0.19 U	< 0.018 U	< 0.053 U	2
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated		220	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated		690	2.872	< 0.023 U	0.055 J	< 0.022 U	0.083	< 0.17 U	< 0.017 U	< 0.049 U	0.25
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated		100	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated		1300	ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated		3200	ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated		650	1.022	< 0.022 U	0.026 J	< 0.021 U	0.028 J	< 0.17 U	< 0.016 U	< 0.047 U	0.085
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated		660	0.316	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	0.039 J
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated		930	2.012	< 0.022 U	0.036 J	< 0.02 U	0.05 J	< 0.16 U	< 0.016 U	< 0.047 U	0.18
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated		870	ND	< 0.029 U	< 0.022 U	< 0.027 U	< 0.026 U	< 0.22 U	< 0.021 U	< 0.062 U	< 0.045 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated		1400	0.221	< 0.033 U	< 0.025 U	< 0.031 U	< 0.029 U	< 0.25 U	< 0.024 U	< 0.07 U	< 0.051 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated		< 8.3 U	ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated		210	0.019	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated		< 8.1 U	ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated		920	0.431	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	0.069 J
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated		1400	0.346	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.042 J
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated		140	ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.032 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated			0.028	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated			4.1	< 0.065 U	< 0.049 U	< 0.061 U	< 0.059 U	< 0.49 U	< 0.047 U	< 0.14 U	0.4
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated			3.6	< 0.063 U	< 0.048 U	< 0.06 U	< 0.057 U	< 0.48 U	< 0.046 U	< 0.14 U	0.7
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated			10.253	< 0.022 U	0.22	< 0.13 U	0.28	< 0.16 U	< 0.14 U	< 0.046 U	1
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated			1.341	< 0.021 U	0.04 J	< 0.13 U	0.032 J	< 0.16 U	< 0.13 U	< 0.045 U	0.13
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated			1.707	< 0.021 U	0.042 J	< 0.13 U	0.058 J	< 0.16 U	< 0.13 U	< 0.046 U	0.17
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.017 UJ	< 0.034 U	< 0.02 UJ	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	0.29	0.43	0.15	0.25	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	0.74	1.2	0.48	0.76	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	0.1	0.16	0.062 J	0.11	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	2.3	3	1.3	1.9	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	0.52	0.73	0.19	0.47	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	1.1	1.3	0.48	0.82	< 0.21 U	< 0.021 U	< 0.042 U	< 0.61 U	< 0.24 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	0.041 J	0.074	0.023 J	0.053 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	0.14	0.2	0.072 J	0.17	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.031 U	0.033 J	< 0.022 U	0.021 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	0.066 J	0.084	0.048 J	0.054 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	0.075	0.12	0.028 J	0.081	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	0.45	0.64	0.25	0.41	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	0.45	0.49	0.2	0.41	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.035 U	0.031 J	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	0.53	0.59	0.22	0.38	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	0.048 J	0.058 J	0.024 J	0.031 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	0.35	0.45	0.21	0.3	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	0.064 J	0.078 J	0.044 J	0.057 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	0.12	0.15	0.046 J	0.065 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	0.053 J	0.066 J	0.025 J	0.051 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	0.27	0.28	0.13	0.18	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	0.12	0.15	0.05 J	0.072 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	2.1	2.5	0.91	0.91	< 0.28 U	< 0.28 U	< 0.23 U	< 1.2 U	< 0.33 U	< 0.51 U
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated										
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated										
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	1.6	1.3	0.44	0.98	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U	< 0.29 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 UT
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	0.22	0.27	0.086	0.24	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	0.076	0.12	0.073 J	0.084	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 UT
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	0.039 J	0.048 J	0.025 J	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	0.18	0.23	0.058 J	0.18	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.043 U	< 0.025 U	< 0.03 U	< 0.022 U	< 0.024 U	< 0.018 U	< 0.037 U	< 0.53 U	< 0.035 U	< 0.34 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.049 U	< 0.028 U	< 0.034 U	0.075 J	< 0.027 U	< 0.021 U	< 0.042 U	< 0.6 U	< 0.04 U	< 0.39 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.25 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	0.037 J	< 0.018 U	< 0.022 U	0.051 J	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.098 U	< 0.055 U	< 0.068 U	< 0.049 U	< 0.054 U	< 0.041 U	< 0.084 U	< 1.2 U	< 0.079 U	< 0.77 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.095 U	< 0.054 U	< 0.066 U	< 0.047 U	< 0.052 U	< 0.04 U	< 0.081 U	< 1.2 U	< 0.077 U	< 0.76 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	0.83	1.2	0.36	0.71	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	0.11	0.19	< 0.022 U	0.11	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	0.15	0.16	0.089	0.12	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.019 UJ	< 0.023 UJ	< 0.017 UJ	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.034 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	< 0.24 U	0.026 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.36	0.071 J	< 0.14 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	< 0.26 U	0.056 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	1	0.18	< 0.14 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.15	< 0.047 U	< 0.13 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	< 0.23 U	0.15	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	2.8	0.42	< 0.13 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.23 U	0.045 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.8	0.12	< 0.13 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.37 U	0.23	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.4	0.21	0.23 J
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.24 U	< 0.034 U	< 0.097 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.065 J	< 0.034 U	< 0.14 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.24 U	0.026 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.18	< 0.047 U	< 0.13 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.081	< 0.049 U	< 0.14 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.089	< 0.048 U	< 0.14 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.26 U	0.078 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.62	0.08 J	< 0.15 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.22 U	0.049 J	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.52	0.078	< 0.13 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.053 J	< 0.052 U	< 0.15 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.26 U	0.071 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.55	0.098	< 0.15 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.07 J	< 0.048 U	< 0.14 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.25 U	0.018 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.38	0.073 J	< 0.14 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.076 J	< 0.051 U	< 0.15 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.12	< 0.05 U	< 0.14 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.066 J	< 0.053 U	< 0.15 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.23	< 0.048 U	< 0.14 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.094	< 0.047 U	< 0.14 U
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 1.7 U	0.45 J	< 0.7 U	< 1 U	< 0.33 U	< 0.23 U	< 0.33 U	2.1	< 0.015 U	< 0.3 U
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.073	< 0.015 U	< 0.015 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U
Football Field	SSHS-B3464	072820 09:00_SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated										
Football Field	SSHS-B3473	072820 09:00_SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated										
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	2.1	0.32	< 0.019 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.31	< 0.051 U	0.021 J
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.12	< 0.048 U	< 0.017 U
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.19	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.33 U	< 0.023 U	< 0.034 U	< 0.024 U	< 0.023 U	< 0.023 U	< 0.03 U	< 0.056 U	< 0.064 U	< 0.022 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.37 U	< 0.026 U	< 0.039 U	< 0.027 U	< 0.026 U	< 0.026 U	< 0.034 U	< 0.063 U	< 0.072 U	< 0.025 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.097	< 0.046 U	< 0.016 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.059 J	< 0.048 U	< 0.016 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.054 U	< 0.018 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.73 U	< 0.053 U	< 0.077 U	< 0.053 U	< 0.052 U	< 0.052 U	< 0.068 U	2	< 0.14 U	< 0.049 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.72 U	< 0.051 U	< 0.075 U	< 0.052 U	< 0.05 U	< 0.051 U	< 0.067 U	1.6	< 0.14 U	< 0.048 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	< 0.24 U	0.064 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.93	0.19	< 0.14 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.14	< 0.046 U	< 0.13 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	< 0.24 U	0.018 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.19	< 0.047 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00_DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 UJ	< 0.034 U	< 0.14 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.044 U	< 0.034 U	< 0.19 U	< 0.23 U	< 0.034 U	< 0.33 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 UT
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 1 U	< 1 U	< 0.72 U	< 0.93 U	< 0.33 U	< 0.51 U	< 0.65 U	< 1.9 U	< 1.3 U	< 3.3 U
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 0.93 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated										
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated										
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.026 U	< 2.4 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.025 U	< 2.2 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.47 U	< 0.039 U	< 0.18 U	< 0.031 U	< 0.037 U	< 0.22 U	< 0.29 U	< 0.86 U	< 0.031 U	< 2.8 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.53 U	< 0.044 U	< 0.2 U	< 0.035 U	< 0.042 U	< 0.25 U	< 0.33 U	< 0.98 U	< 0.035 U	< 3.1 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 1.1 U	< 0.087 U	< 0.4 U	< 0.07 U	< 0.084 U	< 0.49 U	< 0.66 U	< 1.9 U	< 0.07 U	< 6.3 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 1 U	< 0.085 U	< 0.39 U	< 0.068 U	< 0.081 U	< 0.48 U	< 0.64 U	< 1.9 U	< 0.068 U	< 6.1 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	< 0.22 U	< 0.12 U			0.51	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	< 0.23 U	< 0.12 U			1.3	0.049 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.22 U	< 0.11 U			0.22	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	< 0.21 U	< 0.11 U			4.2	0.049 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.21 U	< 0.11 U			1.2	0.031 J	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.34 U			< 0.18 U	3.1	0.35	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.11 U	0.18	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.22 U	< 0.11 U			0.28	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.22 U	< 0.11 U			0.038 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.23 U	< 0.12 U			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.22 U	< 0.12 U			0.17	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.24 U	< 0.13 U			1	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.21 U	< 0.11 U			0.9	0.022 J	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.24 U	< 0.13 UT			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 UT
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.24 U	< 0.13 U			0.026 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.24 U	< 0.12 U			0.97	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.22 U	< 0.12 U			0.086	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.23 U	< 0.12 U			0.5	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.24 U	< 0.12 U			0.097	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.23 U	< 0.12 U			0.034 J	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.23 U	< 0.12 U			0.18	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.22 U	< 0.11 U			0.021 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.21 U	< 0.11 UT			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.25 U	< 0.13 U			0.098	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.22 U	< 0.12 U			0.35	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.22 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 1.4 U			< 0.35 U	4.7	0.54	< 0.049 U	< 0.28 U	< 1.4 U	< 0.21 U
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.017 U			< 0.11 U	0.15	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated										
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated										
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	< 0.064 U	< 0.13 U			1.6	0.021 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.06 U	< 0.12 U			0.4	0.029 J	< 0.028 U	< 0.023 U	< 0.041 U	< 0.02 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	< 0.057 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.054 U	< 0.11 U			0.05 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.057 U	< 0.12 U			0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.075 U	< 0.16 U			< 0.026 U	< 0.02 U	< 0.036 U	< 0.029 U	< 0.051 U	< 0.026 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.085 U	< 0.18 U			0.037 J	< 0.022 U	< 0.041 U	< 0.033 U	< 0.058 U	< 0.029 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 0.054 U	< 0.11 U			0.086	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	< 0.056 U	< 0.12 U			0.055 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 0.053 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.063 U	< 0.13 U			0.028 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.17 U	< 0.35 U			< 0.06 U	< 0.044 U	< 0.081 U	< 0.066 U	< 0.12 U	< 0.058 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.17 U	< 0.34 U			< 0.058 U	< 0.043 U	< 0.079 U	< 0.064 U	< 0.11 U	< 0.057 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	< 0.22 U	< 0.12 U			1.6	0.028 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	< 0.22 U	< 0.11 U			0.2	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 0.22 U	< 0.12 U			< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	< 0.22 U	< 0.11 U			0.24	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.23 U			< 0.12 U	< 0.021 UJ	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

												Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.5	0.33				0.33	12			
Restricted - Residential												0.5	100				100	100			
Protection of Groundwater												8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	0.22	< 0.11 U		< 0.14 U	0.026 J	< 0.11 U	0.041 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	0.67	< 0.11 U		< 0.15 U	0.04 J	< 0.12 U	0.073 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	0.11	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.035 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	1.9	< 0.1 U		< 0.13 U	0.072	< 0.1 U	0.33	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	0.4	< 0.1 U		< 0.13 U	0.023 J	< 0.1 U	0.062 J	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	0.72	< 0.034 U	< 0.034 U	< 0.034 U	0.1 J		0.14	< 0.034 U	< 0.034 U	< 0.21 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	0.043 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.023 J	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	0.15	< 0.1 U		< 0.14 U	0.028 J	< 0.11 U	0.059 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	0.043 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	0.06 J	< 0.11 U		< 0.14 U	0.018 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	0.33	< 0.12 U		< 0.15 U	0.027 J	< 0.12 U	0.039 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	0.33	< 0.099 U		< 0.13 U	0.033 J	< 0.1 U	0.088	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	0.33	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.039 J	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	0.018 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	0.26	< 0.11 U		< 0.15 U	0.032 J	< 0.11 U	0.071 J	< 0.18 U	< 0.099 U	< 0.15 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	0.051 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	0.064 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	0.16	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.041 J	< 0.17 U	< 0.096 U	< 0.14 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	0.064 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.025 J	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	0.87	< 0.72 U	< 0.67 U	< 0.28 U	0.38		0.52	< 0.93 U	< 1.1 U	< 1.4 U
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	0.023 J		0.041 J	< 0.16 U	< 0.088 U	< 0.017 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated										
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated										
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	0.7	< 0.12 U		< 0.022 U	0.11	< 0.13 U	0.11	< 0.19 U	< 0.11 U	< 0.021 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	0.14	< 0.11 U		< 0.02 U	0.039 J	< 0.12 UT	0.064 J	< 0.18 U	< 0.1 U	< 0.019 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 UT	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	0.067 J	< 0.11 U		< 0.019 U	0.023 J	< 0.11 U	0.028 J	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	0.025 J	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	0.15	< 0.11 U		< 0.019 U	0.028 J	< 0.11 U	0.054 J	< 0.17 U	< 0.096 U	< 0.018 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.05 U	< 0.14 U		< 0.026 U	< 0.024 U	< 0.15 U	< 0.02 U	< 0.23 U	< 0.13 U	< 0.024 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	0.056 J	< 0.16 U		< 0.029 U	< 0.027 U	< 0.17 U	< 0.022 U	< 0.26 U	< 0.14 U	< 0.027 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 UT	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 UT	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.11 U	< 0.32 U		< 0.057 U	< 0.054 U	< 0.33 U	< 0.044 U	< 0.51 U	< 0.29 U	< 0.055 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.11 U	< 0.32 U		< 0.056 U	< 0.053 U	< 0.32 U	< 0.043 U	< 0.5 U	< 0.28 U	< 0.053 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	0.68	< 0.11 U		< 0.14 U	0.02 J	< 0.11 U	0.085	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	0.1	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.016 J	< 0.17 U	< 0.092 U	< 0.13 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	0.11	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.02 J	< 0.17 U	< 0.093 U	< 0.14 U
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.039 UJ	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.15 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.19	< 0.11 U	0.55
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.41	< 0.12 U	1.3
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.084	< 0.11 U	0.25
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	1.4	< 0.11 U	4.3
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.72	< 0.11 U	1.6
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.4 U		< 0.034 U	< 0.034 U	< 0.034 U	3.5	< 0.17 U	2.9
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.17	< 0.11 U	0.14
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.12	< 0.11 U	0.27
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.043 J
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.041 J	< 0.12 U	0.12
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.13	< 0.11 U	0.14
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.5	< 0.12 U	1
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.51	< 0.1 U	1
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.025 J	< 0.12 U	< 0.019 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	0.027 J
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.095	< 0.12 U	1
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.086
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.11	< 0.12 U	0.6
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.11
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.19	< 0.12 U	< 0.018 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.026 J	< 0.12 U	0.18
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.023 J
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	0.1
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.11 U	0.41
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.04 J	< 0.11 U	0.14
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.3 U	< 0.3 U	< 2.2 U		< 0.26 U	< 0.28 U	< 1.3 U	4	< 0.19 U	4.2
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.11	< 0.1 U	0.09
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated									
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated									
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.38	< 0.13 U	3.9
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.34	< 0.12 U	0.44
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.091	< 0.11 U	0.13
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.034 J	< 0.11 U	0.056 J
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.16	< 0.11 U	0.38
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.18 U	< 0.08 U	< 0.35 U		< 0.034 U	< 0.17 U	< 0.8 U	< 0.027 U	< 0.15 U	< 0.024 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.21 U	< 0.09 U	< 0.4 U		< 0.038 U	< 0.19 U	< 0.91 U	< 0.03 U	< 0.17 U	0.053 J
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 UT		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 UT		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.019 J
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.092	< 0.11 U	0.087
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.044 J	< 0.11 U	0.058 J
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.41 U	< 0.18 U	< 0.79 U		< 0.076 U	< 0.38 U	< 1.8 U	< 0.061 U	< 0.34 U	1.7 B
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.4 U	< 0.18 U	< 0.77 U		< 0.075 U	< 0.37 U	< 1.8 U	< 0.059 U	< 0.33 U	1.3
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.66	< 0.11 U	1.7
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.083	< 0.11 U	0.23
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.13	< 0.11 U	0.27
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U	< 0.018 UJ

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated		< 0.33 U	< 6.8 U	< 1.6 U	< 1.5 U
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated					
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated					
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated		< 0.022 U	< 0.21 U	< 0.036 U	< 0.027 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated		< 0.024 U	< 0.24 U	< 0.04 U	< 0.031 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated		< 0.049 U	< 0.47 U	< 0.08 U	< 0.062 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated		< 0.047 U	< 0.46 U	< 0.078 U	< 0.06 U
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated			7.325	0.16 J	0.021 J	< 0.034 U	0.31 J	< 0.16 U	< 0.034 U	< 0.046 U	0.6 J
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated			0.184	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.044 U	< 0.034 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated			0.588	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.067 J
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated			0.021	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.053 U	< 0.039 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated			0.727	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.081
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated			0.066	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated			0.411	< 0.0071	0.039	< 0.03	0.02	< 0.036	< 0.033	< 0.055	0.058
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated			3.782	< 0.0022 U	0.13	< 0.032 U	0.062	< 0.11 U	< 0.05 U	< 0.067 U	0.32
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated			0.111	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.008	< 0.029	< 0.0069	< 0.034	< 0.031	< 0.053	< 0.0088
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated	680										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated		1000	186.99	0.47	7.8	< 0.11 U	4.9	< 0.88 U	< 0.084 U	< 0.25 U	17
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated			ND	< 0.38	< 0.38		< 0.38				< 0.38
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated			0.6059	< 0.0099 U	0.02 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.054
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated			0.185	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.022 J
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated			0.673	< 0.019 U	< 0.015 U	< 0.12 U	0.026 J	< 0.15 U	< 0.12 U	< 0.042 U	0.056 J
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated			0.414	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.071 U	0.039 J
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated			0.686	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	0.068
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	390										
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	120										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.013 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated			0.018	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated			0.046	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated			14.71	< 0.068 U	1	< 0.42 U	0.62	< 0.52 U	< 0.43 U	< 0.15 U	1.2
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated			0.165	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated			35.31	0.2 J	1.5	< 0.41 U	1.2	< 0.5 U	< 0.42 U	< 0.14 U	3.2
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated			0.252	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.036 J
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated			50.26	1.1	0.12	< 0.14 U	2.5	< 0.17 U	< 0.14 U	< 0.049 U	4.6
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated			0.296	< 0.02 U	0.046 J	< 0.13 U	0.022 J	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated			25.475	0.055 J	1.5	< 0.13 U	1	< 0.16 U	< 0.14 U	< 0.046 U	2.4
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated			10.835	0.035 J	0.9	< 0.14 U	0.53	< 0.17 U	< 0.15 U	< 0.049 U	0.85

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	0.37 J	0.46 J	0.22 J	0.3 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	0.021 J	< 0.021 U	0.023 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.034 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	0.056 J	0.069 J	0.027 J	0.041 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.037 U	0.021 J	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	0.07 J	0.053 J	0.052 J	0.059 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.16 U	< 0.25 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.031 U	0.018 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	0.07	< 0.012	< 0.015	< 0.0073	< 0.024	< 0.0099	< 0.0079	< 0.059	< 0.032	< 0.05
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.36	0.57	0.19	0.15	< 0.035 U	< 0.035 U	< 0.029 U	< 0.15 U	< 0.041 U	< 0.065 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.031 U	0.028 J	< 0.021 U	0.022 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0076	< 0.057	< 0.031	< 0.048
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	16	21	6.9	15	< 0.096 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	0.057 T	0.095	0.033 J	0.032 J	< 0.027 U	< 0.012 U	< 0.0063 U	0.019 J	< 0.014 UT	< 0.016 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	0.018 JT	0.026 J	0.0086 J	0.016 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	0.062 J	0.056 J	0.032 J	0.049 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	0.036 J	0.053	0.024 J	0.03 J	< 0.034 U	< 0.015 U	< 0.0078 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	0.055	0.068	0.037	0.061	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	0.018 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	1.2	1.8	0.61	1.5	< 0.43 U	< 0.043 U	< 0.087 U	< 1.3 U	< 0.5 U	< 0.81 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.036 U	0.03 J	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	2.8	4.4	1.4	2.8	< 0.42 U	< 0.042 U	< 0.085 U	< 1.2 U	< 0.49 U	< 0.79 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.035 U	0.036 J	< 0.024 U	0.02 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	3.3	4	1.4	1.7	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	0.036 J	0.056 J	0.023 J	0.049 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	1.9	2.7	0.9	2.1	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	0.85	1.3	0.45	1.1	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.24 U	0.1 J	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.57 J	0.074 J	< 0.14 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.065 J	< 0.05 U	< 0.14 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.048 U	< 0.055 U	< 0.16 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.087	< 0.052 U	< 0.15 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.048 U	< 0.055 U	< 0.16 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.28	< 0.0068	< 0.029	< 0.034	< 0.0077	< 0.03	< 0.041	0.06	< 0.0082	< 0.036
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.22 U	< 0.056 U	< 0.088 U	< 0.13 U	< 0.041 U	< 0.029 U	< 0.041 U	0.44	< 0.0019 U	< 0.038 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0084	< 0.0078	< 0.035
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 1.3 U	1	< 0.14 U	< 0.095 U	< 0.092 U	< 0.093 U	< 0.12 U	17	3.8	0.41 J
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated		< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.071 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.021 J	< 0.015 U	< 0.012 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.059 J	< 0.043 U	< 0.12 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.067 U	< 0.016 U	< 0.077 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	0.044 J	< 0.019 U	< 0.014 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0074	< 0.029	< 0.04	0.093	0.011	< 0.035
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.013 U	< 0.015 U	< 0.015 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 0.77 U	0.1 J	< 0.31 U	< 0.41 U	< 0.054 U	< 0.44 U	< 0.39 U	1.4	0.35	< 0.44 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 0.75 U	0.42	< 0.3 U	< 0.4 U	< 0.053 U	< 0.42 U	< 0.38 U	3.3	0.78	< 0.42 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.051 U	< 0.15 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.26 U	0.9	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	3.7	0.63	0.67
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.24 U	0.13	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	2.6	0.52	< 0.14 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.26 U	0.08	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	1.1	0.27	< 0.15 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.029 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.38 U	< 0.031 U	0.14 J	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 UT	< 0.16 U	< 2.6 UT
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.19 J	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.21 J	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	0.2 J	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	0.32 J	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.039	< 0.0074	0.041	< 0.057	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.091 U	< 0.12 U	< 0.041 U	< 0.065 U	< 0.082 U	< 0.23 U	< 0.16 U	< 0.42 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.037	< 0.0071	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 1.9 U	< 0.16 U	< 0.71 U	< 0.12 U	< 0.15 U	< 0.88 U	< 1.2 U	< 3.5 U	< 0.12 U	< 11 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 2	< 0.38	< 2
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	0.015 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.017 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 UT	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.065 U	< 0.028 U	< 0.014 U	< 0.052 U	< 0.098 U	< 0.016 U	< 0.023 U	< 0.18 U	< 0.031 U	< 0.21 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.038	< 0.0071	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.012 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 0.92 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 UT
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 1.1 U	< 0.091 U	< 0.41 U	< 0.4 U	< 0.47 U	< 0.52 U	< 0.69 U	< 2 U	< 0.46 U	< 7.3 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 1.1 U	< 0.088 U	< 0.4 U	< 0.38 U	< 0.45 U	< 0.5 U	< 0.67 U	< 2 U	< 0.45 U	< 7.1 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.1 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.32 U	< 0.027 U	0.12 J	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 UT	< 0.14 U	< 2.2 UT
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 0.33 U	< 0.027 U	0.13 J	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.22 U			< 0.12 U	1.2 J	0.15 J	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.21 U			< 0.11 U	0.05 J	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.23 U	< 0.12 U			0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.26 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.24 U	< 0.13 U			0.13	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.26 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.22 U	< 0.12 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.22 U	< 0.11 U			0.022 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.03			< 0.042	0.073	< 0.0097	< 0.0078	< 0.0082	< 0.04	< 0.026
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.18 U			< 0.044 U	0.5	0.03	< 0.0062 U	< 0.035 U	< 0.18 U	< 0.026 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.21 U	< 0.11 U			0.029 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.3 U	< 0.63 U			28	1	< 0.14 U	< 0.12 U	< 0.21 U	< 0.1 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38				< 0.38	< 0.38	< 0.38	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.038 U		< 0.03 U		0.096 J	< 0.01 U	< 0.017 UT	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.037 U		< 0.03 U		0.02 J	< 0.01 U	< 0.016 UT	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.2 U		< 0.1 U		0.12	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.046 U		< 0.038 U		0.073 J	< 0.013 U	< 0.021 U	< 0.0092 U	< 0.038 U	< 0.015 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.029			< 0.041	0.11	< 0.0094	< 0.0076	< 0.008	< 0.038	< 0.026
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	< 0.017 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.2 U			< 0.11 U	0.024 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 0.7 U	< 0.37 U			1.6	0.11 J	< 0.085 U	< 0.069 U	< 0.12 U	< 0.42 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.25 U	< 0.13 U			0.052 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 0.68 U	< 0.36 U			4.8	0.27	< 0.082 U	< 0.067 U	< 0.12 U	< 0.41 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.24 U	< 0.13 U			0.065 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.23 U	< 0.12 U			8.9	1	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.21 U	< 0.11 U			0.031 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.22 U	< 0.12 U			3.7	0.18	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.24 U	< 0.12 U			1.2	0.09	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	0.26 J	< 0.034 U	< 0.034 U	< 0.034 U	0.038 J		0.051 J	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.043 U	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	0.042 J	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.043 U	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	180134841[1]	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.0076	< 0.026		< 0.028	0.028	< 0.036	0.034	< 0.16	< 0.15	< 0.15
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.11	< 0.091 U	< 0.085 U	< 0.035 U	0.15		0.25	< 0.12 U	< 0.14 U	< 0.18 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.0072	< 0.025		< 0.026	< 0.0063	< 0.034	< 0.0061	< 0.16	< 0.14	< 0.14
Northern Athletic Field	SSHS-B3273	122119 10:30_SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	12	< 0.58 U		< 0.1 U	0.6	< 0.59 U	0.92	< 0.92 U	< 0.51 U	< 0.098 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38		< 0.38	< 0.38	< 0.38	< 0.38	< 2	< 2	< 2
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	0.038	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0079 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	0.021 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	0.042 J	< 0.096 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	0.035 J	< 0.016 U		< 0.12 U	< 0.012 U	< 0.027 U	< 0.0075 U	< 0.033 U	< 0.1 U	< 0.05 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	0.043	< 0.025		< 0.027	0.0077	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	< 0.014 U	< 0.098 U	< 0.1 U	< 0.017 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	1.3	< 0.34 U		< 0.44 U	0.22 J	< 0.35 U	0.49	< 0.54 U	< 0.3 U	< 0.44 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	2.5	< 0.33 U		< 0.43 U	0.26	< 0.34 U	0.56	< 0.52 U	< 0.29 U	< 0.43 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	1.8	< 0.11 U		< 0.15 U	0.37	< 0.12 U	0.63	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	0.037 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	1.7	< 0.11 U		< 0.14 U	0.23	< 0.11 U	0.32	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	0.87	< 0.11 U		< 0.15 U	0.15	< 0.12 U	0.2	< 0.18 U	< 0.1 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	1.4 J	< 0.11 U	1.2 J
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.049 J	< 0.11 U	0.041 J
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.053 J	< 0.12 U	0.1
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.023 J	< 0.12 U	0.13
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.026 J
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated	< 0.031	< 0.04	< 0.13		< 0.0086	< 0.034	< 0.033	0.035	< 0.0087	0.061
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.038 U	< 0.038 U	< 0.28 U		< 0.032 U	< 0.035 U	< 0.17 U	0.29	< 0.023 U	0.51
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.032 J
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.033	< 0.031	< 0.011	< 0.0083	< 0.0071
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated										
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	14	< 0.61 U	29
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.38	< 0.38	< 2	< 0.38	< 0.38	< 0.38	< 2	< 0.38	< 0.38	< 0.38
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.041 J	< 0.013 U	0.081 J
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.0094 J	< 0.013 U	0.023 J
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.074	< 0.1 U	0.097
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.036 U	< 0.089 U	0.024 J	< 0.016 U	0.056 J
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084	0.14
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.022 J
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 0.43 U	< 0.44 U	< 0.83 U		< 0.08 U	< 0.39 U	< 1.9 U	0.63	< 0.36 U	1.9
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.029 J	< 0.12 U	0.054 J
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 0.42 U	< 0.42 U	< 0.8 U		< 0.078 U	< 0.38 U	< 1.8 U	2.3	< 0.35 U	4.8
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.037 J	< 0.12 U	0.058 J
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	7.9	< 0.12 U	7.1
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.042 J
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	1.2	< 0.11 U	4.2
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.39	< 0.12 U	1.6

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated		< 0.028	< 0.024	< 0.039	< 0.055
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated		< 0.041 U	< 0.86 U	< 0.2 U	< 0.19 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated					
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated		< 0.087 U	< 0.84 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated				< 0.38	< 0.38
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated		< 0.013 U	< 0.029 U	< 0.044 U	< 0.055 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated					
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated					
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated					
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated					
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated					
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated		< 0.47 U	< 0.49 U	< 0.41 U	< 0.39 U
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated		< 0.45 U	< 0.48 U	< 0.4 U	< 0.38 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated			2.321	< 0.02 U	0.27	< 0.13 U	0.16	< 0.15 U	< 0.13 U	< 0.044 U	0.16
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated			0.297	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 UT	0.034
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated			5.29	0.12 J	0.2 J	< 0.21 U	< 0.13 U	< 0.26 U	< 0.15 U	< 0.72 UT	< 0.15 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated			0.0584	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 UT	0.012 J
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated			0.157	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 UT	0.016 J
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated			0.577	< 0.01 U	0.016 J	< 0.017 U	0.011 J	< 0.021 U	< 0.012 U	< 0.058 UT	0.057
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated			0.071	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 UT	0.014 J
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 UT	< 0.014 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated			0.142	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated			0.2494	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.029 J
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated			1.412	0.014 J	0.015 J	< 0.018 U	0.038 J	< 0.022 U	< 0.013 U	< 0.061 U	0.13
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated			0.849	0.01 J	0.019 J	< 0.017 U	0.023 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.066
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated			0.107	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated			0.043	< 0.022 U	0.026 J	< 0.14 U	0.02 J	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated			3.038	< 0.021 U	0.069 J	< 0.13 U	0.088	< 0.16 U	< 0.13 U	< 0.046 U	0.28
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated			0.404	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 UT	0.035 J
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated			0.0083	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 UT	< 0.013 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated			6.85	< 0.11 U	0.13 J	< 0.18 U	0.17 J	< 0.22 U	< 0.13 U	< 0.61 U	0.38
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated			0.414	< 0.01 U	0.015 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.031 J
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated			0.0413	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.013 J
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated			0.759	< 0.01 U	0.03 J	< 0.018 U	0.013 J	< 0.021 U	< 0.013 U	< 0.06 U	0.061
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated			0.0357	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 UT	< 0.013 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated			ND	< 0.016 U	< 0.016 U	< 0.027 U	< 0.017 U	< 0.032 U	< 0.019 U	< 0.091 U	< 0.019 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated			2.484	0.047 J	0.091 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated			0.33	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated			0.337	< 0.0099 U	0.011 J	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.058 U	0.021 J
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated			0.0459	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated			0.13	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated			1.521	< 0.01 U	0.042 J	< 0.017 U	0.027 J	< 0.021 UT	0.012 J	< 0.058 U	0.077
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated			1.672	< 0.01 U	0.063 J	< 0.017 U	0.039 J	< 0.021 UT	0.018 J	< 0.058 U	0.096
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated			6.603	0.063 J	0.14 JT	< 0.018 UT	0.14 JT	< 0.021 UT	0.067 JT	< 0.06 UT	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated			0.0096	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated			0.0062	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated			0.705	< 0.02 U	< 0.015 U	< 0.12 U	0.023 J	< 0.15 U	< 0.13 U	< 0.043 U	0.053 J
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated			0.556	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	0.059 J
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated			0.0587	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated			0.207	< 0.011 U	0.017 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.019 J
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated			0.511	< 0.01 U	0.055 J	< 0.018 U	0.011 J	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated			0.344	< 0.0099 U	0.012 J	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.039
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated			0.451	< 0.011 U	0.022 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated			0.276	< 0.0099 U	0.055 J	< 0.017 U	0.042 J	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated			0.738	< 0.011 U	0.017 JT	< 0.018 UT	< 0.011 UT	< 0.022 U	< 0.013 UT	< 0.061 U	0.048 T
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	0.19	0.29	0.09	0.28	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	0.023 JT	0.031 J	0.014 J	0.015 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	0.59 T	0.99	< 0.086 U	0.46 J	< 0.34 U	< 0.15 U	< 0.079 U	< 0.23 U	< 0.17 U	< 0.21 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0092 UT	0.0095 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	0.015 JT	0.015 J	0.011 J	0.023 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	0.053 T	0.071	0.029 J	0.044 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0091 UT	0.01 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0093 UT	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.01 UT	< 0.01 U	< 0.0076 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.032 U	0.028 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	0.017 J	0.028 J	0.0083 J	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	0.11	0.14	0.063	0.053 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.0098 U	< 0.0096 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	0.06	0.082	0.038	0.051 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 0.031 U	0.024 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	0.23	0.25	0.13	0.19	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	0.032 J	0.033 J	0.024 J	0.026 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 UT	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	0.23 J	0.31 J	0.13 J	0.24 J	< 0.29 U	< 0.13 U	< 0.067 U	< 0.2 U	< 0.15 U	< 0.17 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	0.027 J	0.05	0.02 J	0.035 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0095 U	< 0.0093 U	0.0089 J	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	0.057	0.11	0.044	0.032 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 UT	< 0.02 U	< 0.015 U	0.018 J
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 UT	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0096 U	0.0096 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 UT	0.031 J	< 0.014 U	0.054 J
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 UT	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.015 U	< 0.014 U	< 0.011 U	< 0.016 U	< 0.043 U	< 0.019 U	< 0.0099 U	< 0.029 U	< 0.022 U	< 0.026 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	0.096	0.13	< 0.0072 U	0.11 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	0.17 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	0.017 J	0.038	0.016 J	0.039 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0067 U	0.13 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	0.099	0.2	0.059	0.13 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	0.11	0.21	0.057	0.15 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	0.25 T	< 0.0094 UT	< 0.0071 UT	0.16 JT	< 0.028 UT	< 0.013 UT	< 0.0066 U	< 0.019 UT	< 0.014 UT	< 0.017 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	0.051 J	0.064 J	0.028 J	0.05 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	0.04 J	0.056 J	0.02 J	0.048 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.0099 U	0.014 J	< 0.0073 U	0.015 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	0.012 J	0.017 J	< 0.0072 U	0.03 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	0.093 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	0.015 J	0.043	< 0.0068 U	0.029 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	0.033 J	< 0.01 U	< 0.0076 U	0.086 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	0.12 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	0.045 T	0.1 T	0.034 JT	0.047 JT	< 0.029 UT	< 0.013 UT	< 0.0067 UT	< 0.02 UT	< 0.015 UT	< 0.017 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.23 U	0.023 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.21	0.066 J	< 0.13 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.03 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.68 U	< 0.17 U	< 0.78 U	< 0.25 U	< 0.2 U	< 0.16 U	< 0.15 U	< 0.074 U	< 0.19 U	< 0.15 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0089 J	< 0.015 U	< 0.011 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.013 J	< 0.016 U	< 0.012 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.05 J	< 0.015 U	< 0.012 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.011 J	< 0.015 U	< 0.011 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.016 U	< 0.012 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.058 U	0.018 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.13 J	0.016 J	0.013 J
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.063 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.58 U	< 0.14 U	< 0.66 U	< 0.21 U	< 0.17 U	< 0.13 U	< 0.13 U	1.2 J	< 0.16 U	< 0.12 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	0.024 J	< 0.012 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0096 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.069 J	0.02 J	< 0.012 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0064 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.086 U	< 0.021 U	< 0.098 U	< 0.031 U	< 0.025 U	< 0.02 U	< 0.019 U	< 0.0093 U	< 0.024 U	< 0.018 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.55	< 0.016 U	0.05 J
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.032 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.054 U	0.015 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.13 J	< 0.015 U	0.031 J
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.055 U	0.017 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.13 J	< 0.015 U	0.046 J
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.057 UT	< 0.014 UT	< 0.064 UT	< 0.02 UT	< 0.017 UT	< 0.013 UT	< 0.013 UT	1.7 T	< 0.016 UT	0.12 JT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.056 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.052 J	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.059 J	< 0.043 U	< 0.12 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.012 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.22 J	0.016 J	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.027 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	0.031 J
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.058 U	< 0.014 UT	< 0.066 U	< 0.021 UT	< 0.017 UT	< 0.013 UT	< 0.013 UT	0.077 JT	0.028 JT	< 0.012 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.66 U	< 0.28 U	< 0.14 U	< 0.52 U	< 0.99 U	< 0.16 U	< 0.23 U	< 1.8 U	< 0.32 U	< 2.2 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 UT	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 UT	< 0.14 U	< 2.3 UT
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.56 U	< 0.24 U	< 0.12 U	< 0.44 U	< 0.84 U	< 0.14 U	< 0.2 U	< 1.5 U	< 0.27 U	< 1.8 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.083 U	< 0.035 U	< 0.018 U	< 0.066 U	< 0.12 U	< 0.021 U	< 0.029 U	< 0.22 U	< 0.04 U	< 0.27 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	0.26 J	< 0.028 U	0.69
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.055 UT	< 0.023 UT	< 0.012 UT	< 0.043 UT	< 0.083 UT	< 0.014 UT	< 0.019 UT	< 0.15 UT	< 0.026 UT	< 0.18 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.056 UT	< 0.024 UT	< 0.012 UT	< 0.044 UT	< 0.084 UT	< 0.014 UT	< 0.02 UT	< 0.15 UT	< 0.027 UT	< 0.18 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.21 U	< 0.11 U			0.22	0.027 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.037 U		< 0.03 U		0.055 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.47 U		< 0.38 U		0.58 J	< 0.13 U	< 0.21 U	< 0.093 U	< 0.38 U	< 0.15 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.037 U		< 0.03 U		0.015 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.039 U		< 0.032 U		0.016 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.038 U		< 0.031 U		0.1 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.037 U		< 0.03 U		0.018 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.22 U	< 0.12 U			0.034 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.039 U		< 0.031 U		0.04 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.04 U		< 0.032 U		0.22 J	0.016 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.038 U		< 0.031 U		0.1 J	0.014 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 0.21 U	< 0.11 U			0.03 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	< 0.23 U	< 0.12 U			0.023 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	< 0.22 U	< 0.11 U			0.49	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	< 0.22 U	< 0.11 U			0.085	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.4 U		< 0.32 U		0.7 J	0.33 J	< 0.18 U	< 0.079 U	< 0.33 U	< 0.13 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.039 U		< 0.032 U		0.047 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.039 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.039 U		< 0.032 U		0.1 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.059 U		< 0.048 U		< 0.019 U	< 0.016 U	< 0.026 U	< 0.012 U	< 0.048 U	< 0.019 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.04 U		< 0.032 U		0.16 J	0.18 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		0.033 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.038 U		< 0.031 U		0.18 J	0.019 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.038 U		< 0.031 U		0.17 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.039 UT		< 0.032 UT		0.37 T	0.34 JT	< 0.017 UT	< 0.0077 UT	< 0.032 UT	< 0.012 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.12	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	0.081	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.04 U		< 0.032 U		0.018 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.037 U		< 0.03 U		0.034 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.042 U		< 0.034 U		0.059 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.038 U		< 0.03 U		0.018 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.04 UT		< 0.032 U		0.097 JT	< 0.011 UT	< 0.018 UT	< 0.0079 UT	< 0.033 UT	< 0.013 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	0.22	< 0.1 U		< 0.13 U	0.04 J	< 0.1 U	0.048 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	0.5	< 0.16 U		< 1.3 U	< 0.12 U	< 0.27 U	0.11 J	< 0.33 U	< 1 U	< 0.5 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	0.022 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	0.046	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.025 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	0.04	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.0091 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	0.06	< 0.014 U		< 0.11 U	0.016 J	< 0.023 U	0.022 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	0.086	< 0.013 U		< 0.1 U	0.083 J	< 0.022 U	0.094 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	0.16	< 0.11 U		< 0.14 U	0.053 J	< 0.11 U	0.15	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	0.46	< 0.14 U		< 1.1 U	< 0.1 U	< 0.23 U	< 0.064 U	< 0.28 U	< 0.88 U	< 0.43 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	0.063	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.024 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	0.079	< 0.014 U		< 0.1 U	0.015 J	< 0.023 U	0.037 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.021 U	< 0.021 U		< 0.16 U	< 0.015 U	< 0.034 U	< 0.0095 U	< 0.042 U	< 0.13 U	< 0.063 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	0.19	< 0.014 U		< 0.11 U	0.015 J	< 0.023 U	0.011 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	0.16	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	0.05	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.033 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	0.027 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.012 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	0.18	< 0.013 U		< 0.1 U	0.028 J	< 0.022 U	0.13 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	0.18	< 0.013 U		< 0.1 U	0.063 J	0.028 J	0.27 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	0.12 T	< 0.014 UT		< 0.1 UT	0.14 JT	< 0.023 UT	0.16 JT	< 0.028 UT	< 0.086 UT	< 0.042 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	0.0062 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	0.047 J	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		0.021 J	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	0.035 J	< 0.097 U	< 0.099 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	0.021 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.024 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	0.094	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	0.017 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	0.049	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.027 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	0.096	< 0.015 U		< 0.11 U	0.019 J	< 0.024 U	0.059 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	0.079	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	0.077 T	< 0.014 UT		< 0.11 UT	0.02 JT	< 0.023 UT	0.034 JT	< 0.028 U	< 0.088 U	< 0.043 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.08	< 0.11 U	0.28
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.029 J	< 0.013 U	0.049 J
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.24 U	< 0.44 U	< 0.71 U		< 0.32 U	< 0.36 U	< 0.9 U	0.44 J	< 0.16 U	1.5 J
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0060 U	< 0.013 U	0.013 J
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.01 J	< 0.013 U	0.016 J
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.024 J	< 0.013 U	0.092 J
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.018 J
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		0.029 J	< 0.12 U	< 0.6 U	0.022 J	< 0.11 U	0.033 J
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.022 J	< 0.013 U	0.033 J
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.17 J	< 0.014 U	0.23 J
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.069 J	< 0.013 U	0.093 J
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.02 J	< 0.11 U	0.033 J
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.45
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.051 J	< 0.11 U	0.075
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.0083 J	< 0.014 U	< 0.0091 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.21 U	< 0.37 U	< 0.6 U		< 0.27 U	< 0.31 U	< 0.76 U	1.7 J	< 0.14 U	1 J
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.021 J	< 0.013 U	0.042 J
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0098 J	< 0.013 U	< 0.0089 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.041 J	< 0.013 U	0.096 J
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.01 J	< 0.013 U	0.0097 J
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.03 U	< 0.055 U	< 0.09 U		< 0.04 U	< 0.045 U	< 0.11 U	< 0.0097 U	< 0.02 U	< 0.014 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.71	< 0.014 U	0.3 J
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.02 J	< 0.013 U	0.038 J
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.0069 J	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.11 J	< 0.013 U	0.18 J
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.11 J	< 0.013 U	0.15 J
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.02 UT	< 0.036 UT	< 0.059 UT		< 0.026 UT	< 0.03 U	< 0.074 UT	2.2 T	< 0.013 UT	1.1 T
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0096 J	< 0.013 U	< 0.0089 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.099	< 0.1 U	0.097
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.069	< 0.1 U	0.089
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	0.0077 J	< 0.014 U	0.01 J
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.023 J	< 0.014 U	0.019 J
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.027 J	< 0.013 U	0.033 J
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.032 J	< 0.013 U	0.049 J
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.063 J	< 0.014 U	0.055 J
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.017 J
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.021 UT	< 0.037 UT	< 0.06 UT		< 0.027 UT	< 0.03 UT	< 0.076 U	0.069 JT	< 0.014 UT	0.082 JT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	18013712 72	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated		< 0.14 U	< 0.3 U	< 0.45 U	< 0.56 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated		< 0.12 U	< 0.25 U	< 0.38 U	< 0.48 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated		< 0.017 U	< 0.037 U	< 0.056 U	< 0.071 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated		< 0.011 UT	< 0.025 UT	< 0.037 UT	< 0.047 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 UT	< 0.048 U
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated			0.2115	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.023 J
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated			0.278	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.031 J
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated			0.117	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated			0.2256	< 0.01 U	< 0.01 U	< 0.018 U	0.012 J	< 0.021 U	< 0.013 U	< 0.06 U	0.023 J
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated			0.441	< 0.01 U	< 0.01 U	< 0.018 U	0.014 J	< 0.021 U	< 0.012 U	< 0.059 U	0.041
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated			0.353	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.036
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated			0.0078	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated			0.017	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated			0.37	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.041
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated			0.014	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.014 J
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated			0.176	< 0.0098 U	0.011 J	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated			2.515	< 0.011 U	0.012 J	< 0.018 U	0.043 J	< 0.022 U	< 0.013 U	< 0.061 U	0.19
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated			0.219	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.018 J
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated			0.109	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	0.016 J
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated			0.2335	< 0.01 U	0.033 J	< 0.018 U	0.018 J	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated			2.482	< 0.01 U	0.18 J	< 0.017 U	0.05 J	< 0.021 U	< 0.012 U	< 0.059 U	0.16
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated			0.928	< 0.011 U	0.043 J	< 0.018 U	0.028 J	< 0.022 U	< 0.013 U	< 0.062 U	0.077
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated			1.613	< 0.01 U	0.059 J	< 0.018 U	0.025 J	< 0.022 U	< 0.013 U	< 0.06 U	0.14
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.064 UT	< 0.014 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated			3.067	0.015 J	0.038 J	< 0.018 U	0.063 J	< 0.022 UT	< 0.013 U	< 0.061 U	0.28
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated			2.065	< 0.01 U	0.077 J	< 0.018 U	0.048 J	< 0.021 UT	0.025 J	< 0.06 U	0.14
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.065 UT	< 0.014 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated			0.0088	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated			0.01	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated			5.653	< 0.01 U	0.21 J	< 0.017 U	0.066 J	< 0.021 U	0.016 J	< 0.058 U	0.37
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated			3.022	< 0.01 U	0.11 J	< 0.018 U	0.037 J	< 0.021 U	< 0.013 U	< 0.06 U	0.19
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated			0.402	< 0.01 U	0.013 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.046
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated			0.0846	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.016 J
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated			0.343	< 0.0098 U	< 0.0098 U	< 0.017 U	0.014 J	< 0.02 U	< 0.012 U	< 0.057 U	0.036
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated			0.699	0.024 J	< 0.012 U	< 0.02 U	0.055 J	< 0.024 U	< 0.014 U	< 0.067 U	0.041
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated			0.514	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.058
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated			3.436	0.034 J	0.044 J	< 0.017 U	0.09 J	< 0.021 U	< 0.012 U	< 0.058 U	0.31
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated			3.405	0.037 J	0.049 J	< 0.017 U	0.1 J	< 0.02 U	< 0.012 U	< 0.057 U	0.29
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated			0.367	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.041
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated			0.3286	< 0.01 U	0.01 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.035
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0087

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	0.016 J	0.022 J	0.0085 J	0.011 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.0099 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	0.019 J	0.021 J	0.014 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	0.011 J	0.014 J	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	0.014 J	0.018 J	0.0076 J	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	0.033 J	0.043	0.015 J	0.019 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	0.029 J	0.038	0.015 J	0.018 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	0.031 J	0.036	0.012 J	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 UT	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	0.19	0.27	0.094	0.12 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	0.016 J	0.023 J	0.01 J	0.012 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.0099 U	0.02 J	< 0.0073 U	< 0.011 UT	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	0.012 J	0.034 J	0.0096 J	0.026 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	0.24	0.4	0.13	0.24 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	0.083	0.12	0.045	0.06 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	0.16	0.22	0.08	0.11 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	0.26	0.37	0.14	0.15 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	0.16	0.24	0.089	0.16 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	0.51	0.81	0.29	0.47	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	0.27	0.44	0.17	0.27 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	0.043	0.056	0.019 J	0.032 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.0094 U	0.012 J	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	0.024 J	0.035	0.014 J	0.014 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	0.025 J	0.035 J	0.014 J	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	0.053	0.071	0.029 J	0.034 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	0.29	0.41	0.17	0.18 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	0.27	0.38	0.15	0.17 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	0.036	0.05	0.02 J	0.021 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	0.027 J	0.045	0.015 J	0.026 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.007	< 0.011	< 0.014	< 0.0069	< 0.023	< 0.0093	< 0.0075	< 0.056	< 0.03	< 0.048

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.017 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	< 0.016 UT	< 0.012 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.013 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.018 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.038 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.032 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 UT	< 0.013 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.057 U	0.029 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.25 J	0.036 J	< 0.012 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.024 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.019 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.014 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.055 U	0.016 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.22 J	0.062	0.012 J
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.087 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.17 J	0.031 J	< 0.012 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.061 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.058 UT	0.024 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.29 J	0.054	0.02 J
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.057 UT	0.023 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.14 J	0.035 J	0.049 J
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.061 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.055 U	0.032 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.58	0.14	0.037 J
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.056 U	0.016 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.3 J	0.077	0.018 J
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.044 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.0086 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.029 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.064 U	< 0.016 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	0.034 J	< 0.018 U	0.029 J
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.058 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.055 U	0.033 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.3 J	0.063	0.024 J
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.054 U	0.036 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.3 J	0.058	0.026 J
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.036 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.036 J	< 0.015 U	< 0.012 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.028	< 0.039	< 0.0083	< 0.0077	< 0.034

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 UT	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 UT	< 0.027 U	< 0.18 UT
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	0.048 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	0.052 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	0.048 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	0.041 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	0.033 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.021 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	0.017 J	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	0.018 J	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	0.026 J	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.037	< 0.007	< 0.038	< 0.054	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.41

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.04 U		< 0.032 U		0.028 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 UT	< 0.013 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 UT	< 0.012 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.04 U		< 0.032 U		0.046 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.039 U		< 0.032 U		0.022 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.039 U		< 0.031 U		0.042 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		0.074 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		0.059 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	< 0.042 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.039 U		< 0.032 U		0.076 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		0.012 J	0.011 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.04 U		< 0.032 U		0.41	0.011 J	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.038 U		< 0.03 U		0.032 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.04 U		< 0.033 U		0.017 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 UT	< 0.013 UT
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.039 U		< 0.032 U		0.014 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.038 U		< 0.031 U		0.21 J	0.011 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.04 U		< 0.033 U		0.11 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.039 U		< 0.032 U		0.19 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.04 U		< 0.032 U		0.48	0.019 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.039 U		< 0.032 U		0.23 J	0.013 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.038 U		< 0.031 U		0.68	0.027 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.039 U		< 0.032 U		0.37	0.014 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.038 U		< 0.031 U		0.042 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.038 U		< 0.031 U		0.016 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.037 U		< 0.03 U		0.054 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.044 U		< 0.036 U		0.11 J	0.037 J	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.039 U		< 0.031 U		0.063 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.038 U		< 0.031 U		0.47	0.034 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.037 U		< 0.03 U		0.49	0.045 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.039 U		< 0.031 U		0.05 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.038 U		< 0.031 U		0.039 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 UT	< 0.12 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	< 0.2 U		< 0.11 U		< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.028			< 0.04	< 0.0074	< 0.0092	< 0.0074	< 0.0078	< 0.038	< 0.025

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	0.014 J	< 0.014 U		< 0.11 U	0.02 J	< 0.023 U	0.023 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	0.053	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	0.022 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	0.02 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0078 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	< 0.015 UT	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 UT	0.065 J	< 0.022 U	0.1 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	0.13	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.011 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.014 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.015 UT	< 0.014 U		< 0.11 U	< 0.01 UT	< 0.023 UT	0.011 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	0.068	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.014 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	0.34	< 0.013 U		< 0.1 U	0.046 J	< 0.022 U	0.073 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	0.11	< 0.014 U		< 0.11 U	0.021 J	< 0.023 U	0.042 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	0.18	< 0.014 U		< 0.11 U	0.024 J	< 0.023 U	0.042 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	0.18	< 0.014 U		< 0.11 U	0.028 J	< 0.023 U	0.056 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	0.18	< 0.014 U		< 0.11 U	0.084 J	< 0.023 U	0.23 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	0.56	< 0.013 U		< 0.1 U	0.11 J	< 0.022 U	0.13 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	0.31	< 0.014 U		< 0.1 U	0.047 J	< 0.023 U	0.054 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	0.031 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.012 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	0.016 J	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	0.016 J	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	0.024 J	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	0.039	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	0.23	< 0.013 U		< 0.1 U	0.026 J	< 0.022 U	0.035 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	0.23	< 0.013 U		< 0.1 U	0.023 J	< 0.022 U	0.035 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	0.024 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	0.027 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0096 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.0072	< 0.024		< 0.026	< 0.0063	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.023 J	< 0.014 U	0.026 J
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.023 J	< 0.014 U	0.041 J
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.013 J	< 0.013 U	0.026 J
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.047 J	< 0.013 U	0.044 J
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.06 J	< 0.013 U	0.082 J
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.039 J	< 0.013 U	0.067 J
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.017 J	< 0.014 U	< 0.0096 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.082 J	< 0.013 U	0.062 J
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 UT	< 0.028 U	< 0.071 U	0.035 J	< 0.013 U	0.018 J
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.28 J	< 0.014 U	0.48
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.03 J	< 0.013 U	0.04 J
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.013 J	< 0.014 U	0.013 J
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.0079 J	< 0.013 U	0.016 J
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.066 J	< 0.013 U	0.28 J
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.046 J	< 0.014 U	0.12 J
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.055 J	< 0.013 U	0.21 J
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.29 J	< 0.014 U	0.42
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.19 J	< 0.013 U	0.21 J
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.0088 J
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	0.01 J
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.22 J	< 0.013 U	0.8
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.11 J	< 0.013 U	0.41
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.023 J	< 0.013 U	0.054 J
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.015 J	< 0.013 U	0.017 J
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.047 J	< 0.013 U	0.06 J
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 U	0.19 J	< 0.015 U	0.094 J
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.033 J	< 0.013 U	0.076 J
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.29 J	< 0.013 U	0.53
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.34	< 0.013 U	0.51
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.028 J	< 0.013 U	0.061 J
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.023 J	< 0.013 U	0.046 J
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.029	< 0.038	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0082	< 0.007

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.052 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated		< 0.026	< 0.022	< 0.037	< 0.052

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAHS**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	< 0.0089
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0088
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated			1.583	< 0.007	< 0.0083	< 0.03	< 0.0071	< 0.035	< 0.032	< 0.054	0.18
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	120										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.032 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated	40 J										
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	40 J										
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	41 J										
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	92										
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	150										
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	960										
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	140										
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	87										
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	540										
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	350										
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	1100										
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 41 U										
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	76										
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	550										
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	94										
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	120 J										
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 40 U										
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	52 J										
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	6900 J+										
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 40 U										
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 37 UJ										
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	790										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 39 U										
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	42 J										
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 39 U										
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 34 U										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	6200 J+		1.123	0.036 J	< 0.016 U	< 0.02 U	0.023 J	< 0.16 U	< 0.015 U	< 0.045 U	0.061 J
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 36 U										

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.0071	< 0.011	< 0.014	< 0.0071	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0075	< 0.056	< 0.03	< 0.048
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	0.059	0.11	0.037	0.047	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated										
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated										
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated										
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	0.04 J	0.059 J	< 0.022 U	0.075	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.27	< 0.0066	< 0.028	< 0.033	< 0.0074	< 0.029	< 0.04	< 0.0085	< 0.0079	< 0.035
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0083	< 0.0078	< 0.034
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.27	< 0.0067	< 0.029	< 0.033	< 0.0076	< 0.03	< 0.04	0.46	< 0.0081	< 0.036
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated										
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3077	082719 09:30_SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3075	082819 09:00_SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated										
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated										
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.23 UJ	< 0.017 U	< 0.012 UJ	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.21	< 0.016 U	< 0.016 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.038	< 0.0071	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.037	< 0.007	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.038	< 0.0073	< 0.04	< 0.057	< 0.039	< 0.045	< 0.038	< 0.15	< 0.037	< 0.43
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated										
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated										
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated										
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 UJ
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.029			< 0.041	< 0.0076	< 0.0094	< 0.0076	< 0.008	< 0.038	< 0.026
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0092	< 0.0074	< 0.0078	< 0.038	< 0.025
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.029			< 0.042	< 0.0077	0.16	< 0.0077	< 0.0081	< 0.039	< 0.026
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180l217472	Not Excavated	< 0.053 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated										
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated										
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated										
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.018 U			< 0.11 U	0.19	0.12	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.0073	< 0.025		< 0.027	< 0.0064	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0072	< 0.024		< 0.026	< 0.0063	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	0.05	< 0.025		< 0.027	< 0.0065	< 0.035	< 0.0062	< 0.16	< 0.15	< 0.15
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated										
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated										
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated										
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	0.049 J	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 UJ	< 0.017 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084	< 0.0072
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0083	< 0.0071
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.03	< 0.04	< 0.13		< 0.0085	< 0.034	< 0.032	0.48	< 0.0086	< 0.0073
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180I217472	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated										
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated										
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated										
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated										
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated										
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated										
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated										
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated										
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated										
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated										
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated										
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated										
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated										
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated										
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated										
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated										
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated										
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.26 J
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated		< 0.027	< 0.023	< 0.039	< 0.054
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated					
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated					
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated					
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated					
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated					
Northern Athletic Field	SSHS-B3077	082719 09:30_SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated					
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated					
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated					
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated					
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated					
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated					
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated					
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated					
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated					
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated					
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated					
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated					
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated					
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated					
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated					
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated					
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated					
Northern Athletic Field	SSHS-B3075	082819 09:00_SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated					
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated					
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated					
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated					
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated					
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated					
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated					
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated					
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated					
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated					
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated					
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated					
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated					
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated					
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated					
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated					
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated					
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated					
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated					
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated					
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated					
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated					
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated					
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated					
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated					
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated					
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated					
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated					
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated					
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated					
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated					
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated					
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated					
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated					
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated					
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated					
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated					
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated					
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated					
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated					
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated					
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated					
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated					
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated					
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated					
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated					
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated					
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated					

DRAFT

													Diesel Range Organics	**Diesel Fuel**	**Total PAHS**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	65										
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	110										
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	53										
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	83										
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	210										
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	53										
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 38 U										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated			0.083	< 0.019 U	< 0.015 U	< 0.018 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.041 U	< 0.03 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated			3.76	< 0.022 U	0.11	< 0.02 U	0.1	< 0.16 U	< 0.016 U	< 0.046 U	0.27
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated			0.16	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated			0.018	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated			0.055	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated			9.39	0.15	0.1	< 0.16 U	0.37	< 0.19 U	< 0.16 U	< 0.054 U	0.9
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated			4.807	0.051 J	0.13	< 0.14 U	0.18	< 0.17 U	< 0.14 U	< 0.048 U	0.45
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.053 U	< 0.038 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated			3.702	< 0.021 U	0.39	< 0.13 U	0.21	< 0.16 U	< 0.13 U	< 0.045 U	0.24
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated			ND	< 0.02 U	0.019 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated			0.025	< 0.019 U	0.016 J	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated			ND	< 0.021 UT	< 0.016 U	< 0.13 U	< 0.019 UT	< 0.16 UT	< 0.13 U	< 0.044 U	< 0.032 UT
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated			ND	< 0.021 U	0.016 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated			ND	< 0.021 U	0.019 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated			5.795	< 0.021 U	0.56	< 0.13 U	0.31	< 0.16 U	< 0.14 U	< 0.046 U	0.44
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated			0.055	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated			0.0082	< 0.0095 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated			3.797	< 0.021 U	0.063 J	< 0.13 U	0.1	< 0.16 U	< 0.13 U	< 0.045 U	0.34
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated			0.119	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.029 U	0.023 J	< 0.02 U	0.019 J	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U	< 0.23 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	0.27	0.39	0.1	0.31	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.034 U	0.017 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	0.74	0.8	0.34	0.47	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.19 U	< 0.3 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	0.4	0.52	0.16	0.3	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	0.34	0.56	0.17	0.46	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 UT
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.031 UT	< 0.018 UT	< 0.021 U	< 0.015 UT	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 UT	< 0.15 UT	< 0.25 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	0.46	0.79	0.22	0.61	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	0.28	0.38	0.16	0.19	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	0.016 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	< 0.037 U	< 0.043 U	< 0.015 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.24 U	0.04 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.27	0.073 J	0.05 J
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.28 U	0.13	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	0.79	0.13	< 0.16 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.25 U	0.055 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.42	0.07 J	< 0.14 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.12 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.23 U	0.027 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.31	0.11	< 0.13 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.23 U	< 0.017 UT	< 0.094 UT	< 0.13 U	< 0.016 UT	< 0.13 U	< 0.12 UT	< 0.04 UT	< 0.046 UT	< 0.13 UT
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.24 U	0.067 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.54	0.12	< 0.14 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.23 U	0.031 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.31	0.051 J	< 0.13 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.33 UT	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 UT	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.33 UT	< 0.028 U	< 0.13 UT	< 0.12 U	< 0.14 UT	< 0.16 UT	< 0.21 U	< 0.62 UT	< 0.14 U	< 2.2 UT
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.34 U	< 0.028 U	0.14 J	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.05 U	< 0.1 U			0.019 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.056 U	< 0.12 U			0.61	0.037 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.052 U			< 0.11 U	0.043 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	0.019 J	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.26 U	< 0.14 U			1.5	0.15	< 0.031 U	< 0.026 U	< 0.045 U	< 0.15 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.23 U	< 0.12 U			0.72	0.054 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.22 U	< 0.11 U			0.3	0.031 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 UT	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.21 UT	< 0.11 U			< 0.019 UT	< 0.014 UT	< 0.026 UT	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.22 U	< 0.12 U			0.61	0.045 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.11 U	0.028 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.1 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.21 U	< 0.11 U			0.62	0.016 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.23 U	< 0.12 U			0.035 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.033 U	< 0.096 U		< 0.017 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.016 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	0.22	< 0.11 U		< 0.019 U	0.099	< 0.11 U	0.19	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		0.036 J	< 0.16 U	< 0.088 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.036 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	0.4	< 0.13 U		< 0.16 U	0.078 J	< 0.13 U	0.15	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	0.28	< 0.11 U		< 0.14 U	0.033 J	< 0.11 U	0.052 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.017 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	0.4	< 0.1 U		< 0.14 U	0.042 J	< 0.11 U	0.053 J	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.033 U	< 0.095 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.036 UT	< 0.1 U		< 0.13 U	< 0.017 UT	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 UT	< 0.13 UT
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	0.49	< 0.11 U		< 0.14 U	0.087	< 0.11 U	0.13	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-12-14	SSHS-DW-10 11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-12-14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.033 U	< 0.096 U	< 0.098 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-12-14	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.038 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	0.19	< 0.1 U		< 0.13 U	0.047 J	< 0.11 U	0.14	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated										
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated										
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated										
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated										
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated										
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated										
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.12 U	< 0.053 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.022 J
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.43	< 0.11 U	0.49
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	0.029 J	< 0.1 U	0.052 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.018 J
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U	0.019 J
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 UJ
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	1.1	< 0.13 U	1.4
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.44	< 0.12 U	0.71
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.088	< 0.11 U	0.43
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.025 J
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 UT
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 UT	< 0.58 UT	< 0.019 UT	< 0.11 U	< 0.017 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.19	< 0.11 U	0.84
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.027 J
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	0.0082 J	< 0.012 U	< 0.0083 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.43	< 0.11 U	0.59
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.032 J	< 0.11 U	0.036 J

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated					
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated					
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated					
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated					
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated					
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated					
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated					
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated					
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated					
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated					
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated					
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated					
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated					
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated					
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated					
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated					
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated					
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated		< 0.014 U	< 0.14 U	< 0.024 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 UT	< 0.12 U	< 0.12 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated			3.724	< 0.021 U	0.055 J	< 0.13 U	0.1	< 0.16 U	< 0.13 U	< 0.044 U	0.32
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated			0.145	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated			0.39	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.045 J
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated			1.304	< 0.021 U	0.025 J	< 0.13 U	0.031 J	< 0.16 U	< 0.13 U	< 0.045 U	0.11
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.16 U	< 0.023 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated			6.571	0.096 J	0.13 J	< 0.019 U	0.16 J	< 0.022 U	< 0.013 U	< 0.063 UT	0.54
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated			2.076	< 0.011 U	0.065 J	< 0.02 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated			4.951	0.035 J	0.094 JT	< 0.019 UT	0.15 JT	< 0.023 UT	0.035 J	< 0.064 UT	0.3
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated			0.689	< 0.011 U	0.02 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 UT	< 0.014 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated			0.178	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 UT	0.019 J
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated			0.1905	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 UT	0.016 J
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated			4.48	0.056 J	0.054 J	< 0.13 U	0.16	< 0.16 U	< 0.14 U	< 0.046 U	0.37
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated			0.008	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated			0.255	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.024 J
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated			0.59	< 0.0099 U	0.013 J	< 0.017 U	0.011 J	< 0.021 UT	< 0.012 U	< 0.058 UT	0.048
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated			0.1773	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 UT	0.024 J
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated			0.214	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.024 J
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated			0.127	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.019 J
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated			ND	< 0.02 U	0.023 J	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated			0.018	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	50 J										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	52 J										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 39 U										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated			1.345	< 0.022 U	< 0.017 U	< 0.021 U	0.027 J	< 0.17 U	< 0.016 U	< 0.047 U	0.097
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated			0.037	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated			0.026	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated			12.79	0.12	0.096	< 0.022 U	0.21	< 0.18 U	0.055 J	< 0.05 U	0.84

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	0.28	0.35	0.15	0.21	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 0.032 U	0.028 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	0.038 J	0.053 J	< 0.022 U	0.027 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	0.093	0.13	0.05 J	0.075	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 UT	< 0.15 U	< 0.24 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 0.038 U	< 0.022 U	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.19 U	< 0.3 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	0.36	0.5	0.3	0.15 J	< 0.03 U	< 0.013 U	< 0.0069 UT	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	0.08	0.17	< 0.0078 U	0.047 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	0.17 T	0.46	< 0.0075 U	0.13 JT	< 0.03 UT	< 0.013 UT	< 0.0070 UT	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	0.06	0.11	< 0.0078 U	0.046 J	< 0.031 U	< 0.014 U	< 0.0072 UT	< 0.021 U	< 0.016 U	0.093 J
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	0.012 JT	0.027 J	0.01 J	0.017 J	< 0.031 U	< 0.014 U	< 0.0072 UT	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	0.011 J	0.029 J	0.0097 J	0.012 J	< 0.029 U	< 0.013 U	< 0.0067 UT	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.0099 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated	0.33	0.4	0.15	0.29	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	0.021 J	0.032 J	0.014 J	0.021 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	0.041	0.072	0.033 J	0.042 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	0.019 J	0.03 J	0.0083 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	0.018 J	0.02 J	0.02 J	0.023 J	< 0.027 U	< 0.012 U	< 0.0062 U	0.02 J	< 0.014 U	0.02 J
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	0.015 J	0.015 J	0.0070 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	0.1	0.14	0.047 J	0.093	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.038 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	0.4	0.79	0.36	0.34	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.23 U	0.04 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.31	0.056 J	< 0.13 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.11	< 0.046 U	< 0.13 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	< 0.049 U	< 0.056 U	< 0.16 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.15 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	1.2	0.045	0.08 J
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.71	< 0.017 U	< 0.013 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.06 UT	< 0.015 UT	< 0.068 UT	< 0.022 UT	< 0.018 U	< 0.014 UT	< 0.014 U	0.92 T	0.036 JT	0.11 J
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.062 UT	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	0.032 J	0.15 J	0.018 J	0.023 J
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.062 UT	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.017 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.032 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated	< 0.24 U	0.052 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.38	0.051 J	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0080 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.024 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.052 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.056 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.021 J	0.021 J	< 0.011 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.012 J	< 0.015 U	< 0.011 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.25 U	0.025 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.12	< 0.048 U	< 0.017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.28 U	< 0.02 U	< 0.03 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.056 U	< 0.019 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U	< 0.018 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	< 0.047 U	< 0.054 U	< 0.018 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.89	0.13	0.3 J

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.058 U	< 0.025 UT	< 0.012 UT	< 0.046 UT	< 0.087 UT	< 0.014 UT	< 0.02 U	< 0.16 UT	< 0.028 UT	< 0.19 UT
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 UT	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated	< 0.34 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.02 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.017 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.046 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	0.048 J	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	0.04 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.034 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.053 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.018 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.027 U	< 2.4 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U	< 2.3 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.2 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.24 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.21 U	< 0.11 U			0.61	0.018 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 0.22 U	< 0.12 U			0.045 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	< 0.22 U	< 0.12 U			0.082	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	< 0.22 U	< 0.11 U			0.23	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 0.26 U	< 0.14 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.15 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.041 U		< 0.033 U		0.72	0.3 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.043 U		< 0.035 U		0.22 J	0.089 J	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.041 UT		< 0.034 UT		0.55 T	0.19 J	< 0.018 UT	< 0.0082 UT	< 0.034 UT	< 0.013 UT
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.043 U		< 0.035 U		0.02 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.04 U		< 0.032 U		0.019 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	0.72	0.053 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0072 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.038 U		< 0.031 U		0.029 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.038 U		< 0.03 U		0.073 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.04 U		< 0.032 U		0.029 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.037 U		< 0.03 U		0.014 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.037 U		< 0.03 U		0.022 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.057 U	< 0.12 U			0.27	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.066 U	< 0.14 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.12 U			< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.062 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.06 U	< 0.12 U			3	0.17	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	0.17	< 0.1 U		< 0.13 U	0.044 J	< 0.1 U	0.14	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.024 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	0.067 J	< 0.1 U		< 0.14 U	0.018 J	< 0.11 U	0.058 J	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 0.044 U	< 0.13 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	0.15	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	0.1	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.095 U	< 0.046 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	0.11 T	0.017 JT		< 0.11 UT	0.089 JT	0.34 JT	0.14 J	< 0.029 UT	< 0.091 UT	< 0.044 UT
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	0.048	< 0.015 U		< 0.11 U	0.044 J	0.04 J	0.027 J	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	0.019 J	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	0.014 J	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	0.014 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0078 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated	0.24	< 0.11 U	< 0.11 U	< 0.14 U	0.042 J		0.05 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	0.02 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.013 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	0.086	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.023 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	0.027 J	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	0.071 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	0.037 J	< 0.2 U	< 0.11 U	< 0.021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	0.33	< 0.11 U		< 0.02 U	0.27	< 0.12 U	0.21	< 0.18 U	< 0.1 U	< 0.019 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.44	< 0.11 U	0.57
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.03 J	< 0.11 U	0.042 J
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.051 J	< 0.11 U	0.07 J
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.14	< 0.11 U	0.21
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	< 0.023 U	< 0.13 U	< 0.021 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	1.1	< 0.014 U	0.95
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.26 J	< 0.015 U	0.4
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.021 UT	< 0.038 UT	< 0.063 UT		< 0.028 UT	< 0.032 U	< 0.079 U	1.1 T	< 0.014 UT	0.66 T
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	0.13 J	< 0.015 U	0.1 J
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	0.023 J
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	0.023 J	< 0.014 U	0.017 J
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.56	< 0.11 U	0.67
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.018 J	< 0.013 U	0.039 J
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.037 J	< 0.013 U	0.072 J
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.018 J	< 0.014 U	0.025 J
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.011 J	< 0.013 U	0.015 J
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.018 J	< 0.013 U	0.019 J
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.018 J
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.16	< 0.11 U	0.22
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.16 U	< 0.069 U	< 0.31 U		< 0.029 U	< 0.14 U	< 0.7 U	< 0.023 U	< 0.13 U	< 0.021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.026 J
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	2.8	< 0.12 U	2.2

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated		< 0.012 UT	< 0.026 UT	< 0.039 UT	< 0.049 UT
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated					
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated					
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated					
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated					
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated					
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated					
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated					
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated					
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated					
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated					
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated					
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated					
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated					
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated					
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated					
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated			0.049	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated			0.388	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.05 J
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated			4.905	< 0.022 U	0.67	< 0.14 U	0.36	< 0.17 U	< 0.14 U	< 0.048 U	0.28
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated			ND	< 0.022 U	0.016 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated			1.167	< 0.021 U	0.15	< 0.13 U	0.064 J	< 0.16 U	< 0.13 U	< 0.045 U	0.088
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated			0.177	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.031 J
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated			0.176	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated			1.139	< 0.02 U	< 0.015 U	< 0.12 U	0.03 J	< 0.15 U	< 0.12 U	< 0.042 U	0.12
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated			0.029	< 0.021 U	< 0.016 U	< 0.13 U	0.029 J	< 0.16 UT	< 0.13 U	< 0.045 UT	< 0.033 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated			0.144	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 UT	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U	< 0.23 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	0.048 J	0.054 J	< 0.024 U	0.036 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	0.43	0.6	0.24	0.76	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	0.12	0.16	0.069 J	0.16	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.03 U	0.025 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	0.38 J	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.031 U	0.029 J	< 0.021 U	0.019 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	0.083	0.12	0.042 J	0.068	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	0.084	< 0.15 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U	< 0.015 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.051 J	< 0.05 U	< 0.15 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.25 U	0.045 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.37	0.13	< 0.14 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.11	< 0.046 U	< 0.13 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 UT	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-14-16	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-14-16	SSHS-DW-13 14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-14-16	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.11	< 0.043 U	< 0.13 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	0.34	< 0.2 U	< 0.59 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 UT	< 0.023 U	< 2.1 UT
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.1 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 UT
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.32 U	< 0.026 U	0.16 J	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	0.02 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	0.021 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801727471	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801727471	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801727471	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801727471	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801727471	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 UT	< 0.14 U	< 2.3 UT
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801727471	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.052 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.018 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.052 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.24 U			< 0.13 U	0.026 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.23 U	< 0.12 U			0.073 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.23 U	< 0.12 U			0.42	0.043 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.22 U	< 0.11 U			0.1	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 UT	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	0.048 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.046 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	0.18	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 UT	< 0.13 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.034 U	< 0.098 U		< 0.017 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.034 U	< 0.098 U		< 0.017 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.04 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	0.52	< 0.11 U		< 0.14 U	0.058 J	< 0.11 U	0.072 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	0.11	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.016 J	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.035 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	0.066 J	< 0.097 U	< 0.1 U	< 0.13 U	0.018 J		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	0.06 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.13 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.023 J
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.076 J
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.57
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.17
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-14-16	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-14-16	SSHS-DW-13 14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.03 J	< 0.1 U	0.043 J
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-14-16	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.037 J	< 0.11 U	0.045 J
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.14	< 0.1 U	0.18
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-14-16	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-14-16	SSHS-DW-13 14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-14-16	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U

														Diesel Range Organics	**Diesel Fuel**	**Total PAH's**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated			ND	< 0.022 U	0.017 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 8.3 U										
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 42 U										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated			0.523	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.044 J
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated			1.123	< 0.022 U	0.029 J	< 0.021 U	0.028 J	< 0.17 U	< 0.016 U	< 0.048 U	0.08
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated			19.255	< 0.12 U	0.74	< 0.11 U	0.59	< 0.89 U	< 0.085 U	< 0.25 U	2
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated			0.568	< 0.021 U	0.065 J	< 0.02 U	0.022 J	< 0.16 U	< 0.016 U		< 0.014 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated			0.669	< 0.022 U	0.021 J	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	0.068 J
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated			0.322	< 0.043 U	0.049 J	< 0.041 U	< 0.039 U	< 0.33 U	< 0.031 U		< 0.028 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated			7.137	0.022 J	0.31	< 0.021 U	0.14	< 0.17 U	0.022 J	< 0.048 U	0.59
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated			0.366	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	0.054 J
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated			0.085	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	0.015 J
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated			2.793	< 0.022 U	0.12	< 0.021 U	0.068 J	< 0.17 U	< 0.016 U	< 0.047 U	0.26
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated			1.76	< 0.022 U	0.044 J	< 0.02 U	0.076	< 0.16 U	< 0.016 U	< 0.047 U	0.16
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated			1.387	< 0.022 U	0.099	< 0.021 U	0.045 J	< 0.17 U	< 0.016 U	< 0.048 U	0.12
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated			8.576	0.027 J	0.46 J	< 0.021 UJ	0.24 J	< 0.17 U	< 0.016 UJ	< 0.047 U	0.72 J
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated			4.107	< 0.022 U	0.18	< 0.021 U	0.094	< 0.17 U	< 0.016 U	< 0.048 U	0.36
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.014 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated			12.513	0.037 J	0.62	< 0.022 U	0.32	< 0.18 U	0.017 J	< 0.05 U	1.1
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated			0.316	< 0.022 U	0.043 J	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.031 J
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated			98.42	0.2 J	4.6	< 0.063 U	2.6	< 0.51 U	< 0.049 U	< 0.14 U	8.8
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated			0.969	< 0.022 U	0.11	< 0.02 U	0.051 J	< 0.16 U	< 0.016 U	< 0.047 U	0.065 J
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated			6.565	0.026 J	0.38	< 0.022 U	0.21	< 0.17 U	0.017 J	< 0.049 U	0.53
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.014 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated			5.374	< 0.022 UJ	0.25	< 0.021 U	0.15	< 0.17 U	< 0.016 U	< 0.047 U	0.57
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated			0.282	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	0.032 J
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated			0.721	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.067 J
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated			12.789	< 0.022 U	0.61	< 0.021 U	0.41	< 0.17 U	0.038 J	< 0.048 U	1.2
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated			2.926	< 0.022 U	0.049 J	< 0.021 U	0.066 J	< 0.17 U	< 0.016 U	< 0.047 U	0.3
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated			1.541	< 0.019 U	0.068	< 0.018 U	0.038 J	< 0.15 U	0.02 J	< 0.042 U	0.11
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated			1.065	< 0.024 U	0.037 J	< 0.023 U	0.022 J	< 0.18 U	< 0.018 U	< 0.052 U	0.12
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated			7.546	< 0.023 U	0.3	< 0.021 U	0.14	< 0.17 U	< 0.017 U	< 0.049 U	0.74
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated			0.095	< 0.021 U	0.017 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated			2.766	< 0.022 U	0.12	< 0.021 U	0.06 J	< 0.17 U	< 0.016 U	< 0.047 U	0.26
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated			2.577	< 0.022 U	0.085	< 0.021 U	0.041 J	< 0.17 U	< 0.016 U	< 0.048 U	0.24
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated			0.43	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	0.04 J
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated			8.437	< 0.022 U	0.46	< 0.021 U	0.28	< 0.17 U	< 0.016 U	< 0.048 U	0.79
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated			8.437	< 0.022 U	0.46	< 0.021 U	0.28	< 0.17 U	< 0.016 U	< 0.048 U	0.79
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	440	440 J	64.15	< 0.087 UJ	2.6 J	< 0.082 U	1.4	< 0.66 U	< 0.064 UJ	< 0.19 U	5.9 J
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated			0.425	< 0.023 U	0.025 J	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	0.047 J
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated			0.643	< 0.021 U	0.046 J	< 0.02 U	0.022 J	< 0.16 U	< 0.015 U	< 0.045 U	0.059 J
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated			16.408	< 0.022 U	0.58	< 0.021 U	0.36	< 0.17 U	< 0.016 U	< 0.048 U	1.5
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated			150.45	< 0.12 U	6	< 0.11 U	3.5	< 0.88 U	< 0.084 U	< 0.25 U	14
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated			3.401	< 0.022 U	0.17	< 0.021 U	0.088	< 0.17 U	< 0.016 U	< 0.048 U	0.33
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated			9.228	< 0.024 U	0.29	< 0.023 U	0.23	< 0.19 U	0.023 J	< 0.053 U	0.82
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated			24.923	0.053 J	1.1	< 0.02 U	0.65	< 0.16 U	< 0.015 U	< 0.046 U	2.2
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	53 J	53 J	5.084	0.025 J	0.28	< 0.021 U	0.14	< 0.17 U	< 0.016 U	< 0.048 U	0.45
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	40 J	40 J	1.71	< 0.022 U	0.037 J	< 0.021 U	0.031 J	< 0.17 U	< 0.016 U	< 0.047 U	0.17
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated			1.667	< 0.022 U	0.1	< 0.021 U	0.051 J	< 0.17 U	< 0.016 U	< 0.048 U	0.15
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated			10.92	< 0.022 U	0.67	< 0.021 U	0.28	< 0.17 U	< 0.016 U	< 0.048 U	0.93
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated			10.222	< 0.022 U	0.41	< 0.02 U	0.29	< 0.16 U	< 0.016 U	< 0.047 U	0.88
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated			1.219	< 0.022 U	0.06 J	< 0.021 U	0.026 J	< 0.17 U	< 0.016 U	< 0.047 U	0.13
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated			4.99	< 0.022 U	0.31	< 0.02 U	0.16	< 0.16 U	< 0.016 U	< 0.046 U	0.4
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated			1.594	< 0.021 U	0.033 J	< 0.13 U	0.031 J	< 0.16 U	< 0.13 U	< 0.045 U	0.14
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated			4.16	< 0.021 U	0.076 J	< 0.13 U	0.15	< 0.16 U	< 0.13 U	< 0.045 U	0.36 J
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated			1.755	< 0.025 U	0.049 J	< 0.16 U	0.036 J	< 0.19 U	< 0.16 U	< 0.054 U	0.14
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated			1.721	< 0.023 U	0.066 J	< 0.14 U	0.042 J	< 0.17 U	< 0.14 U	< 0.049 U	0.13
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated			9.279	< 0.023 U	0.28	< 0.14 U	0.2	< 0.17 U	< 0.15 U	< 0.05 U	0.9
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated			5.29	< 0.021 U	0.18	< 0.13 U	0.29	< 0.16 U	< 0.14 U	< 0.046 U	0.5
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated			0.807	< 0.022 U	0.06 J	< 0.14 U	0.05 J	< 0.17 U	< 0.14 U	< 0.047 U	0.064 J
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated			0.804	< 0.024 U	0.021 J	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.08 J
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated			4.642	0.039 J	0.33	< 0.13 U	0.15	< 0.16 U	< 0.13 U	< 0.045 U	0.42
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated			1.239	< 0.023 U	0.037 J	< 0.14 U	0.028 J	< 0.17 U	< 0.14 U	< 0.049 U	0.11
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated			1.475	< 0.024 U	0.023 J	< 0.15 U	0.023 J	< 0.18 U	< 0.15 U	< 0.052 U	0.13
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated			0.307	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.044 J
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated			0.143	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	0.042 J	0.06 J	< 0.022 U	0.04 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated	0.077	0.12	0.048 J	0.075 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated	1.7	2.5	0.86	1.3	< 0.097 U	< 0.074 U	< 0.15 U	< 2.2 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	0.44	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	0.062 J	0.076	0.028 J	0.044 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated	< 0.033 U	< 0.037 U	< 0.045 U	0.1 J	< 0.036 U	< 0.027 U	< 0.056 U	< 0.8 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated	0.63	0.76	0.3	0.7	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	< 0.018 U	0.054 J	0.026 J	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated	< 0.017 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	0.25	0.37	0.12	0.23	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated	0.14	0.17	0.058 J	0.094	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	0.13	0.19	0.048 J	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	0.8 J	0.99 J	0.42 J	0.69 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	0.4	0.58	0.16	0.35	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.06	0.00	-	2 - 4 ft	2.06-4.06 ft	180-100363-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated	1.2	1.6	0.64	1.1	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U	< 0.28 U
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	0.047 J	0.047 J	0.024 J	0.034 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	6.9	11	3.1	6.6	< 0.055 U	< 0.042 U	< 0.086 U	< 1.2 U	< 0.081 U	< 0.79 U
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated	0.096	0.16	0.036 J	0.11	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated	0.58	0.7	0.25	0.7	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	0.47	0.57	0.21	0.42	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated	0.03 J	0.03 J	< 0.026 U	0.042 J	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U	< 0.3 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	0.072 J	0.099	0.032 J	0.056 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated	1.2	1.5	0.6	1.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated	0.32	0.37	0.11	0.24	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	0.13	0.19	0.059 J	0.16	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U	< 0.23 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	0.1	0.12	0.06 J	0.081 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated	0.83	1.1	0.27	0.63	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.032 U	0.038 J	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	0.27	0.41	0.11	0.22	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	0.23	0.33	0.1	0.19	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	0.042 J	0.06 J	< 0.025 U	0.034 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U	< 0.29 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	0.77	0.99	0.37	0.66	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	0.77	0.99	0.37	0.66	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	5.5 J	7.3 J	2.7 J	4.7 J	< 0.072 U	< 0.055 U	< 0.11 U	< 1.6 U	< 0.11 U	< 1 U
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	0.045 J	0.053 J	0.024 J	0.032 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	0.062 J	0.08	0.028 J	0.052 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated	1.4	2.1	0.55	1.2	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated	13	17	6	12	< 0.096 U	< 0.073 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	0.34	0.43	0.18	0.27	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	0.81	1.1	0.39	0.8	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U	< 0.29 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	2.3	3.1	0.88	2.2	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	0.46	0.61	0.17	0.35	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	0.14	0.19	0.061 J	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	0.16	0.22	0.07 J	0.13	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	1	1.4	0.66	1.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.99	1.1	0.59	0.74	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.12	0.17	0.06 J	0.1	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	0.51	0.66	0.22	0.49	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	0.14	0.18	0.065 J	0.14	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	0.29 J	0.38 J	0.15 J	0.21	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	0.12	0.22	0.058 J	0.089	< 0.16 U	< 0.016 U	< 0.032 U	< 0.47 U	< 0.19 U	< 0.3 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	0.12	0.23	0.056 J	0.097	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	0.61	1.2	0.4	0.57	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	858.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	0.35	0.54	0.17	0.32	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	0.069 J	0.12	0.033 J	0.093	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	0.062 J	0.1	0.039 J	0.05 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	0.3	0.5	0.16	0.32	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	0.1	0.16	0.052 J	0.081	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	0.098	0.19	0.037 J	0.084 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.034 U	0.046 J	< 0.023 U	0.019 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.033 U	0.038 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.041 J	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U	< 0.018 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated	< 0.25 U	0.02 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.11	0.027 J	0.017 J
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated	< 1.3 U	0.27 J	< 0.068 U	< 0.096 U	< 0.093 U	< 0.094 U	< 0.12 U	1.9	0.51	0.14 J
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.015 U	< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.068 J	< 0.017 U	< 0.016 U
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated	< 0.49 U	< 0.035 U	< 0.025 UJ	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	0.11 J	< 0.033 U	< 0.033 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated	< 0.25 U	0.054 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.6	0.2	0.053 J
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	0.04 J	< 0.018 U	< 0.018 U
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.024 J	< 0.018 U	< 0.017 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.3	0.06 J	< 0.017 U
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated	< 0.25 U	0.018 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.14	0.031 J	0.029 J
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.15	< 0.017 U	0.019 J
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	< 0.25 U	0.05 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.86 J	0.21 J	0.026 J
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.25 U	0.027 J	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.43	0.095	0.022 J
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated	< 0.23 UJ	< 0.017 U	< 0.012 UJ	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated	< 0.26 U	0.086	< 0.013 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	1.3	0.29	0.042 J
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.032 J	< 0.017 U	< 0.017 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 0.75 U	0.74	< 0.039 U	< 0.054 U	< 0.053 U	< 0.054 U	< 0.07 U	10	1.7	0.46 J
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.086	0.03 J	< 0.016 U
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated	< 0.26 U	0.054 J	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.55	0.21	0.05 J
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U	< 0.016 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.25 U	0.038 J	< 0.013 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.57	0.17	0.019 J
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated	< 0.28 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.034 J	< 0.019 U	< 0.019 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.083	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated	< 0.25 U	0.086	< 0.027 U	< 0.018 U	< 0.018 U	< 0.024 U	1.2	0.28	0.065 J
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated	< 0.25 U	0.022 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.27	< 0.049 U	0.018 J
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	0.15	0.044 J	0.04 J
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	0.11	< 0.054 U	< 0.018 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.74	0.19	< 0.017 U
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.28	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.27	0.051 J	< 0.017 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	0.058 J	< 0.054 U	< 0.018 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.25 U	0.035 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.9	0.17	0.019 J
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.25 U	0.035 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.9	0.17	0.019 J
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	< 0.99 U	0.3 J	< 0.1 U	< 0.071 U	< 0.07 U	< 0.071 U	< 0.092 U	6.5 J	1.3 J	0.19 J
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.056 J	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.069 J	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated	< 0.25 U	0.091	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	1.6	0.29	0.046 J
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated	< 1.3 U	0.72	< 0.14 U	< 0.095 U	< 0.092 U	< 0.093 U	< 0.12 U	15	3	0.23 J
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.25 U	0.02 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.34	0.1	< 0.017 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.28 U	0.082 J	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	0.87	0.25	0.058 J
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.24 U	0.14	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	2.5	0.59	0.034 J
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.25 U	0.034 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.53	0.096	< 0.017 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.16	< 0.048 U	< 0.017 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.18	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	< 0.25 U	0.057 J	< 0.026 U	< 0.018 UJ	< 0.018 U	< 0.018 U	< 0.024 U	1	0.26	0.038 J
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.24 U	0.068 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.87	0.17	0.056 J
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.13	< 0.048 U	< 0.017 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.24 U	0.046 J	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.46	0.12	0.033 J
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.15	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.24 U	0.044 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.33 J	0.051 J	< 0.13 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	0.19	< 0.056 U	< 0.16 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.18	< 0.051 U	< 0.15 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	< 0.26 U	0.038 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	1	0.17	< 0.15 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	< 0.24 U	0.029 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.52	0.09	< 0.14 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.081	< 0.049 U	< 0.14 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.09	< 0.052 U	< 0.15 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	< 0.24 U	0.055 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.5	0.09	< 0.13 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.13	< 0.05 U	< 0.14 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	0.16	< 0.054 U	< 0.16 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.047 J	< 0.05 U	< 0.14 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.24 J	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	0.28 J	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2.2 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 2.5 U
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated	< 1.9 U	< 0.16 U	< 0.71 U	< 0.13 U	< 0.074 U	< 0.89 U	< 1.2 U	< 3.5 U	< 0.13 U	< 5.5 U
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated	< 0.7 U	< 0.058 U	< 0.26 U	< 0.047 U	< 0.027 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.046 U	< 2 U
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated	< 0.36 U	< 0.03 U	0.19 J	0.041 J	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U	< 1.1 U
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 1 U
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 0.97 U
Northern Athletic Field	SSHS-B3257	122119 10:30_SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3259	122119 10:30_SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 1.1 U	< 0.089 U	< 0.41 U	< 0.072 U	< 0.042 U	< 0.51 U	< 0.67 U	< 2 U	< 0.071 U	< 3.1 U
Northern Athletic Field	SSHS-B3225	122119 10:30_SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3226	122119 10:30_SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3228	122119 10:30_SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 0.99 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Northern Athletic Field	SSHS-B3227	012520 10:00_SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.016 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U	< 1.2 U
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U	< 1.9 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3613	012721 08:30_SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3615	012721 08:30_SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3616	012721 08:30_SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3620	012721 08:30_SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	< 1.4 U	< 0.12 U	< 0.53 U	< 0.094 U	< 0.11 U	< 0.66 U	< 0.88 U	< 2.6 U	< 0.094 U	< 8.4 U
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated	< 0.36 U	< 0.03 U	0.14 J	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated	< 1.9 U	< 0.15 U	< 0.71 U	< 0.12 U	< 0.15 U	< 0.88 U	< 1.2 U	< 3.5 U	< 0.12 U	< 11 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.39 U	< 0.033 U	0.18 J	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U	< 2.3 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.054 U	< 0.11 U			0.12	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.06 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated	< 0.019 U			< 0.12 U	0.19	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated	< 0.1 U			< 0.63 U	2.9	0.095 J	< 0.15 U	< 0.12 U	< 0.21 U	< 0.1 U
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.019 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.019 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated	< 0.037 U			< 0.23 U	< 0.04 U	< 0.029 U	< 0.054 U	< 0.044 U	< 0.077 U	< 0.039 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated	< 0.019 U			< 0.12 U	0.93	0.045 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	< 0.021 U			< 0.13 U	0.056 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.021 U
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated	< 0.02 U			< 0.12 U	0.026 J	< 0.016 U	< 0.028 UJ	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.019 U			< 0.12 U	0.36	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated	< 0.019 U			< 0.12 U	0.28	0.034 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	< 0.019 U			< 0.12 U	0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	< 0.019 U			< 0.12 U	1.1 J	0.067 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.019 U			< 0.12 U	0.52	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated	< 0.02 U			< 0.12 U	1.5	0.066 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	< 0.019 U			< 0.12 U	0.035 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 0.058 U			< 0.36 U	15	0.5	< 0.083 U	< 0.068 U	< 0.12 U	< 0.06 U
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated	< 0.019 U			< 0.12 U	0.093	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated	< 0.02 U			< 0.12 U	0.8	0.049 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.021 U
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.019 U			< 0.12 U	0.74	0.032 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated	< 0.022 U			< 0.13 U	0.045 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.022 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.056 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated	< 0.059 U			< 0.12 U	1.6	0.059 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated	< 0.057 U			< 0.12 U	0.44	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.051 U			< 0.1 U	0.13	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.017 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.063 U	< 0.13 U			0.15	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.022 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated	< 0.06 U			< 0.12 U	0.85	0.029 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.055 U			< 0.11 U	0.028 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.37	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	< 0.059 U			< 0.12 U	0.36	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.063 U	< 0.13 U			0.073 J	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	1.2	0.041 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	1.2	0.041 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	< 0.23 U			< 0.47 U	9 J	0.36 J	< 0.11 U	< 0.089 U	< 0.16 U	< 0.078 U
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	< 0.059 U	< 0.12 U			0.066 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.055 U	< 0.11 U			0.089	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	2.3	0.078	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated	< 0.3 U			< 0.63 U	22	0.7	< 0.14 U	< 0.12 U	< 0.21 U	< 0.1 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.058 U			< 0.12 U	0.41	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.064 U			< 0.13 U	1.2	0.048 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.022 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.055 U	< 0.11 U			3.2	0.11	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.058 U			< 0.12 U	0.78	0.033 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	< 0.057 U			< 0.12 U	0.32	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.058 U	< 0.12 U			0.24	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	< 0.059 U			< 0.12 U	1.3	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U			1.5	0.052 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U			0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.056 U			< 0.12 U	0.57	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.21 U			< 0.11 U	0.24	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.22 U			< 0.11 U	0.77 J	0.03 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	< 0.26 U	< 0.14 U			0.21	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.15 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	< 0.24 U	< 0.12 U			0.16	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	< 0.24 U	< 0.12 U			1.2	0.029 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	< 0.22 U	< 0.12 U			0.92	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	< 0.23 U	< 0.12 U			0.069 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	< 0.24 U	< 0.13 U			0.12	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	< 0.22 U	< 0.11 U			0.66	0.043 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	< 0.23 U	< 0.12 U			0.18	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	< 0.25 U	< 0.13 U			0.24	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.23 U	< 0.12 U			0.061 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.23 U	< 0.12 U			0.04 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.017 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated	0.069 J	< 0.11 U	< 0.11 U	< 0.02 U	0.061 J		0.059 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated	1.1	< 0.58 U	< 0.6 U	< 0.1 U	0.33 J		0.3 J	< 0.93 U	< 0.52 U	< 0.099 U
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	0.085	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.021 J	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	0.049 J	< 0.11 U	< 0.11 U	< 0.019 U	0.024 J		0.017 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated	0.08 J	< 0.21 U	< 0.22 U	< 0.038 U	< 0.036 U		0.032 J	< 0.34 U	< 0.19 UJ	< 0.036 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated	0.59	< 0.11 U	< 0.11 U	< 0.02 U	0.11		0.27	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	0.039 J	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated	< 0.016 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	0.2	< 0.11 U	< 0.11 U	< 0.019 U	0.032 J		0.035 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated	0.081	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.026 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	0.095	< 0.11 U	< 0.11 U	< 0.02 U	0.074 J		0.052 J	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	0.63 J	< 0.11 U	< 0.11 U	< 0.019 U	0.045 J		0.062 J	< 0.17 U	< 0.097 U	< 0.018 U
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	0.29	< 0.11 U	< 0.11 U	< 0.02 U	0.086		0.078	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated	< 0.015 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U	< 0.017 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated	0.88	< 0.11 U	< 0.12 U	< 0.02 U	0.12		0.14	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	0.028 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	5.6	< 0.33 U	< 0.34 U	< 0.059 U	0.35		0.42	< 0.53 U	< 0.29 U	< 0.056 U
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated	0.088	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.017 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated	0.58	< 0.11 U	< 0.12 U	< 0.02 U	0.12		0.19	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated	< 0.015 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	0.38	< 0.11 U	< 0.11 U	< 0.019 U	0.066 J		0.062 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated	0.032 J	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U	< 0.021 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	0.047 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated	0.94	< 0.11 U	< 0.11 U	< 0.02 U	0.14		0.32	< 0.18 U	< 0.099 U	< 0.019 U
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated	0.22	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.04 J	< 0.17 U	< 0.097 U	< 0.018 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	0.1	< 0.096 U	< 0.099 U	< 0.017 U	0.18		0.13	< 0.15 U	< 0.086 U	< 0.016 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	0.073 J	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated	0.57	< 0.11 U	< 0.12 U	< 0.02 U	0.049 J		0.067 J	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	0.2	< 0.11 U	< 0.11 U	< 0.019 U	0.035 J		0.026 J	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	0.15	< 0.11 U	< 0.11 U	< 0.02 U	0.03 J		0.025 J	< 0.18 U	< 0.099 U	< 0.019 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.02 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	0.54	< 0.11 U	< 0.11 U	< 0.02 U	0.045 J		0.056 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	0.54	< 0.11 U		< 0.02 U	0.045 J	< 0.11 U	0.056 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	4.1 J	< 0.44 U	< 0.45 U	< 0.077 U	0.37 J		0.59 J	< 0.69 U	< 0.39 U	< 0.074 U
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	0.044 J	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated	1	< 0.11 U	< 0.11 U	< 0.02 U	0.1		0.13	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated	9.7	< 0.58 U	< 0.59 U	< 0.1 U	0.52		0.75	< 0.92 U	< 0.51 U	< 0.098 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	0.25	< 0.11 U		< 0.02 U	0.063 J	< 0.11 U	0.053 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	0.64	< 0.12 U		< 0.022 U	0.17	< 0.12 U	0.16	< 0.19 U	< 0.11 U	< 0.021 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	1.8	< 0.11 U		< 0.019 U	0.082	< 0.11 U	0.14	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	0.3	< 0.11 U	< 0.11 U	< 0.02 U	0.021 J		0.03 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	0.094	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	0.11	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	0.83	< 0.11 U	< 0.11 U	< 0.02 U	0.11		0.2	< 0.18 U	< 0.099 U	< 0.019 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.58	< 0.11 U		< 0.019 U	0.086	< 0.11 U	0.14	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	0.085	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	0.39	< 0.11 U	< 0.11 U	< 0.019 U	0.11		0.11	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	0.11	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		0.038 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	0.21	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		0.059 J	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	0.082 J	< 0.13 U		< 0.16 U	0.24	< 0.13 U	0.18	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	0.086	< 0.11 U		< 0.15 U	0.29	< 0.12 U	0.2	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	0.53	< 0.11 U		< 0.15 U	0.3	< 0.12 U	0.3	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	0.31	< 0.11 U		< 0.14 U	0.14	< 0.11 U	0.11	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	0.089	< 0.11 U		< 0.14 U	0.018 J	< 0.11 U	0.016 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	0.041 J	< 0.12 U		< 0.15 U	0.044 J	< 0.12 U	0.035 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	0.28	< 0.1 U		< 0.14 U	0.16	< 0.11 U	0.13	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	0.076 J	< 0.11 U		< 0.15 U	0.042 J	< 0.12 U	0.032 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	0.074 J	< 0.12 U		< 0.16 U	0.092	< 0.12 U	0.059 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.076	< 0.11 U	0.1
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.1	< 0.12 U	0.14
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.68 U	< 3.3 U	1.2	< 0.62 U	2.3
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.047 J	< 0.11 U	0.1
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated	< 0.27 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	< 0.04 U	< 0.23 U	< 0.036 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.43	< 0.12 U	0.93
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.033 J	< 0.13 U	0.064 J
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.02 J
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.13	< 0.11 U	0.41
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.24	< 0.11 U	0.23
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.077	< 0.12 U	0.2
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.17	< 0.12 U	0.58
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.17	< 0.12 U	0.58
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.54	< 0.12 U	1.8
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.038 J
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated	< 0.42 U	< 0.18 U	< 0.81 U		< 0.078 U	< 0.39 U	< 1.9 U	11	< 0.35 U	15
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.11 U	0.11
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.36	< 0.12 U	0.83
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.21	< 0.11 U	0.82
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	0.037 J
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.035 J	< 0.11 U	0.12
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.58	< 0.12 U	1.8
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.18	< 0.12 U	0.37
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.14	< 0.1 U	0.16
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.049 J	< 0.13 U	0.18
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.29	< 0.12 U	1.1
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	0.029 J
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.11	< 0.12 U	0.45
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.14	< 0.12 U	0.45
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.05 J	< 0.13 U	0.073 J
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.37	< 0.12 U	1.3
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.37	< 0.12 U	1.3
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated	< 0.56 U	< 0.24 U	< 1.1 U		< 0.1 U	< 0.51 U	< 2.4 U	4.8 J	< 0.46 U	10 J
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.026 J	< 0.12 U	0.076 J
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.028 J	< 0.11 U	0.11
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.2	< 0.12 U	2.7
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated	< 0.74 U	< 0.32 U	< 1.4 U		< 0.14 U	< 0.67 U	< 3.2 U	9.8	< 0.61 U	24
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.14	< 0.12 U	0.47
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.61	< 0.13 U	1.3
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	1.3	< 0.11 U	3.9
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.24	< 0.12 U	0.87
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.094	< 0.11 U	0.32
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.076 J	< 0.12 U	0.28
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.36	< 0.12 U	1.6
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.82	< 0.11 U	1.5
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.058 J	< 0.11 U	0.19
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.27	< 0.11 U	0.63
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.12	< 0.11 U	0.24
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.48 J	< 0.11 U	0.69 J
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.18	< 0.13 U	0.25
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.19	< 0.12 U	0.23
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.57	< 0.12 U	1.6
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.4	< 0.11 U	0.77
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.026 J	< 0.12 U	0.097
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.077 J	< 0.12 U	0.11
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.32	< 0.11 U	0.73
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.1	< 0.12 U	0.19
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.15	< 0.13 U	0.23
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.026 J	< 0.12 U	0.064 J
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.02 J	< 0.11 U	0.045 J

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated					
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated					
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated		< 0.088 U	< 0.85 U	< 0.15 U	< 0.11 U
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated		< 0.032 U	< 0.31 U	< 0.054 U	< 0.041 U
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated		< 0.05 U	< 0.48 U	< 0.083 U	< 0.064 U
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated		< 0.015 U	< 0.14 U	< 0.024 U	< 0.018 U
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated		< 0.066 U	< 0.63 U	< 0.11 U	< 0.083 U
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated		< 0.087 U	< 0.84 U	< 0.14 U	< 0.11 U
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated			20.743	0.22 J	0.32	< 0.44 U	0.65	< 0.54 U	< 0.45 U	< 0.15 U	2
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated			3.064	< 0.023 U	0.097	< 0.14 U	0.06 J	< 0.18 U	< 0.15 U	< 0.05 U	0.32
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated			35.858	0.068 J	0.64	< 0.14 U	1.2	< 0.17 U	< 0.14 U	< 0.047 UT	3.3
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated			7.512	< 0.023 U	0.27	< 0.14 U	0.17	< 0.17 U	< 0.15 U	< 0.05 U	0.78
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated			1.527	< 0.023 U	0.049 J	< 0.14 U	0.028 J	< 0.18 U	< 0.15 U	< 0.05 U	0.15
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated			39.96	0.29	0.44	< 0.15 U	2.3	< 0.19 U	< 0.16 U	< 0.053 U	3.4
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated			ND	< 0.022 U	0.022 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated			13.458	0.031 J	0.55	< 0.14 U	0.43	< 0.17 U	< 0.14 U	< 0.048 U	1.3
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated			5.832	< 0.023 U	0.19	< 0.14 U	0.16	< 0.17 U	< 0.15 U	< 0.049 U	0.61
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated			1.003	< 0.022 U	0.07 J	< 0.13 U	0.044 J	< 0.16 U	< 0.14 U	< 0.047 U	0.11
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated			3.639	< 0.022 U	0.19	< 0.14 U	0.18	< 0.17 U	< 0.14 U	< 0.048 U	0.33
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated			1.456	< 0.023 U	0.065 J	< 0.14 U	0.1	< 0.17 U	< 0.15 U	< 0.049 U	0.13
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated			0.916	< 0.022 U	0.063 J	< 0.14 U	0.036 J	< 0.17 U	< 0.14 U	< 0.047 U	0.078
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated			2.375	< 0.022 U	0.14	< 0.14 U	0.087	< 0.17 U	< 0.14 U	< 0.047 U	0.3
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated			0.821	< 0.022 U	0.046 J	< 0.14 U	0.027 J	< 0.17 U	< 0.14 U	< 0.048 U	0.087
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated			14.6	< 0.075 U	0.68	< 0.47 U	0.46	< 0.57 U	< 0.48 U	< 0.16 U	1.4
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated			0.908	< 0.023 U	0.032 J	< 0.14 U	0.027 J	< 0.17 U	< 0.14 U	< 0.049 U	0.087
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated			0.201	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.034 J
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated			0.695	< 0.022 U	0.049 J	< 0.14 U	0.041 J	< 0.17 U	< 0.14 U	< 0.047 U	0.063 J
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated			0.132	< 0.022 U	0.018 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated			0.024	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated			0.051	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated			0.101	< 0.024 U	< 0.018 U	< 0.15 U	0.022 J	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated			1.185	< 0.022 U	0.067 J	< 0.14 U	0.029 J	< 0.17 U	< 0.14 U	< 0.048 U	0.11
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated			1.615	< 0.022 U	0.052 J	< 0.14 U	0.054 J	< 0.17 U	< 0.14 U	< 0.048 U	0.12
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated			3.562	< 0.086 U	0.16 J	< 0.53 U	0.092 J	< 0.65 U	< 0.54 U	< 0.18 U	0.32
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated			1.354	< 0.021 U	0.035 J	< 0.13 U	0.026 J	< 0.16 U	< 0.14 U	< 0.046 U	0.13
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated			0.446	< 0.021 U	0.032 J	< 0.13 U	0.021 J	< 0.16 U	< 0.14 U	< 0.046 U	0.043 J
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated			31.678	0.057 J	0.97	< 0.13 U	1	< 0.16 U	< 0.14 U	< 0.047 U	0.9
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated			0.669	< 0.021 U	0.044 J	< 0.13 U	0.031 J	< 0.16 U	< 0.13 U	< 0.045 U	0.063 J
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated			0.121	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 UT	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated			1.422	< 0.022 U	< 0.017 U	< 0.14 U	0.036 J	< 0.17 U	< 0.14 U	< 0.048 U	0.14
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated			0.226	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.033 J
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated			0.756	< 0.021 U	0.016 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	0.076
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated			0.286	< 0.022 U	0.02 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.038 J
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated			16.738	< 0.021 U	0.25	< 0.13 U	0.5	< 0.16 U	< 0.14 U	< 0.046 U	1.6
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated			13.034	< 0.021 U	0.21	< 0.13 U	0.37	< 0.16 U	< 0.13 U	< 0.045 U	1.2
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated			1.688	< 0.021 U	0.035 J	< 0.13 U	0.032 J	< 0.16 U	< 0.13 U	< 0.044 U	0.19
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated			0.076	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated			1.464	< 0.02 U	0.026 J	< 0.13 U	0.029 J	< 0.15 U	< 0.13 U	< 0.044 U	0.12
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated			1.405	< 0.025 U	0.029 J	< 0.15 U	0.034 J	< 0.19 U	< 0.16 U	< 0.053 U	0.12
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated			0.037	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 UT	< 0.033 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated			2.647	< 0.021 U	0.1	< 0.13 U	0.083	< 0.16 U	< 0.13 U	< 0.045 U	0.25
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated			0.43	< 0.02 U	0.02 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.045 J
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated			3.396	0.05 J	0.056 J	< 0.13 U	0.11	< 0.16 U	< 0.14 U	< 0.047 U	0.28
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated			0.871	< 0.024 U	0.051 J	< 0.15 U	0.035 J	< 0.18 U	< 0.15 U	< 0.052 U	0.064 J
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated			1.527	< 0.02 U	0.018 J	< 0.13 U	0.042 J	< 0.15 U	< 0.13 U	< 0.044 U	0.17
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated			3.485	< 0.025 U	0.069 J	< 0.15 U	0.087	< 0.19 U	< 0.16 U	< 0.053 UT	0.29
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated			0.103	< 0.023 U	0.093	< 0.14 U	0.026 J	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated			0.602	< 0.022 U	0.032 J	< 0.13 U	0.022 J	< 0.16 U	< 0.14 U	< 0.046 U	0.049 J
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated			1.935	< 0.06 U	< 0.046 U	< 0.37 U	< 0.054 U	< 0.46 U	< 0.38 U	< 0.13 U	0.2 J
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated			0.319	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.043 J
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated			0.364	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.049 J
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100						
Restricted - Residential												1	1	3.9	100						
Protection of Groundwater												22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	1.5	2.1	0.73	1.2	< 0.45 U	< 0.045 U	< 0.092 U	< 1.3 U	< 0.53 U	< 0.85 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	0.24	0.36	0.12	0.19	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	2	2.7	1.1	1.3	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	0.6	0.84	0.39	0.47	< 0.15 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	0.12	0.19	0.058 J	0.093	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	1.8	2.2	0.88	0.95	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	1.1	1.6	0.62	1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	0.49	0.73	0.21	0.4	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	0.1	0.16	0.056 J	0.079	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	0.3	0.52	0.14	0.26	< 0.14 U	< 0.014 U	< 0.028 U	0.75 J	< 0.16 U	< 0.26 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	0.12	0.19	0.061 J	0.1	< 0.15 U	< 0.014 U	< 0.029 U	0.83 J	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	0.094	0.12	0.044 J	0.084	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	0.23	0.31	0.11	0.16	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	0.084	0.11	0.038 J	0.077 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	1.3	1.9	0.6	0.96	< 0.48 U	< 0.047 U	< 0.097 U	< 1.4 U	< 0.56 U	< 0.9 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	0.078 J	0.11	0.029 J	0.062 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.032 U	0.038 J	< 0.022 U	0.024 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	0.051 J	0.074 J	0.026 J	0.056 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.032 U	0.035 J	< 0.022 U	0.022 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	0.12	0.16	0.062 J	0.1	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	0.12	0.19	0.054 J	0.17	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	0.31	0.45	0.14 J	0.33	< 0.54 U	< 0.054 U	< 0.11 U	< 1.6 U	< 0.63 U	< 1 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	0.13	0.18	0.054 J	0.12	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	0.056 J	0.075	< 0.022 U	0.033 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	4.1	5.3	2.1	1.7	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	0.059 J	0.11	0.025 J	0.062 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.031 U	0.028 J	< 0.022 U	0.022 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.03 U	< 0.017 UT	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	0.11	0.13	0.059 J	0.053 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.031 U	0.035 J	< 0.022 U	0.019 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	0.068 J	0.078	0.041 J	0.067 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.032 U	0.044 J	< 0.022 U	0.047 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	1.3	1.4	0.62	0.87	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	1.1	1.3	0.39	0.68	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	0.16	0.23	0.071 J	0.14	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.031 U	0.026 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	0.12	0.17	0.094	0.083	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	0.11	0.15	0.052 J	0.13	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.29 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	0.21	0.28	0.093	0.19	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	0.042 J	0.047 J	0.027 J	0.048 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	0.24	0.26	0.12	0.22	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	0.063 J	0.067 J	< 0.025 U	0.11	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	0.092	0.11	0.045 J	0.079	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	0.27	0.41	< 0.026 U	0.36	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.29 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	0.055 J	0.059 J	0.034 J	0.087	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	0.23	0.29	0.12 J	0.19 J	< 0.38 U	< 0.038 U	< 0.077 U	< 1.1 U	< 0.44 U	< 0.71 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	0.039 J	0.061 J	< 0.023 U	0.027 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	0.04 J	0.041 J	< 0.023 U	0.025 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	< 0.81 U	0.28	< 0.33 U	< 0.44 U	< 0.057 U	< 0.46 U	< 0.41 U	1.9	0.37	< 0.46 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.38	0.052 J	< 0.15 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	< 0.25 U	0.28	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	3.3	0.32	0.21 J
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	< 0.26 U	0.027 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.95	0.13	< 0.15 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.2	< 0.052 U	< 0.15 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	< 0.28 U	0.22	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	3	0.26	0.26 J
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	< 0.25 U	0.058 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	1.4	0.29	< 0.14 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	< 0.26 U	0.021 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.58	0.11	< 0.15 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.12	< 0.048 U	< 0.14 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	< 0.25 U	0.035 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.41	0.085	< 0.14 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.16	< 0.051 U	< 0.15 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.091	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.32	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.096	< 0.05 U	< 0.14 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.85 U	0.099 J	< 0.34 U	< 0.46 U	< 0.06 U	< 0.48 U	< 0.44 U	1.5	0.27	< 0.48 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.081	< 0.051 U	< 0.15 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.095	< 0.048 U	< 0.14 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.054 U	< 0.15 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.15	< 0.05 U	< 0.14 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.25 U	0.02 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.14	0.058 J	< 0.14 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.97 U	< 0.069 U	< 0.39 U	< 0.52 U	< 0.068 U	< 0.55 U	< 0.49 U	0.32	< 0.19 U	< 0.55 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.13	< 0.048 U	< 0.14 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.058 J	< 0.047 U	< 0.14 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.24 U	0.16	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	3.6	0.65	< 0.14 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.063 J	< 0.046 U	< 0.13 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.16	< 0.049 U	< 0.14 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.08	< 0.047 U	< 0.14 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.12 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.042 J	< 0.048 U	< 0.14 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.24 U	0.25	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	1.1	0.23	< 0.14 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.23 U	0.16	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.98	0.17	< 0.13 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.16	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.14	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.12	< 0.055 U	< 0.16 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.24 U	0.023 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.24	0.053 J	< 0.13 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.04 J	< 0.045 U	< 0.13 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.24 U	0.048 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.26	0.049 J	< 0.14 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.074 J	< 0.053 U	< 0.15 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.17	< 0.045 U	< 0.13 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.28 U	0.035 J	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.38	< 0.055 U	< 0.16 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.051 J	< 0.048 U	< 0.14 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.68 U	< 0.049 U	< 0.27 U	< 0.36 U	< 0.048 U	< 0.38 U	< 0.35 U	0.17 J	< 0.13 U	< 0.38 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.049 J	< 0.05 U	< 0.14 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.057 J	< 0.05 U	< 0.14 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	< 1.2 U	< 0.096 U	< 0.44 U	< 0.42 U	< 0.49 U	< 0.54 U	< 0.72 U	< 2.1 U	< 0.48 U	< 7.7 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 1.2 U	< 0.1 U	< 0.46 U	< 0.44 U	< 0.52 U	< 0.57 U	< 0.76 U	< 2.3 U	< 0.51 U	< 8.1 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 1.4 U	< 0.11 U	< 0.52 U	< 0.5 U	< 0.59 U	< 0.65 U	< 0.86 U	< 2.6 U	< 0.58 U	< 9.2 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 UT	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	0.18 J	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.2 J	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.2 J	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 UT
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.4 UT	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 UT	< 0.17 U	< 2.7 UT
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.97 U	< 0.08 U	< 0.36 U	< 0.35 U	< 0.41 U	< 0.46 U	< 0.6 U	< 1.8 U	< 0.41 U	< 6.5 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.18 J	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	< 0.74 U	< 0.39 U			3.5	0.2 J	< 0.089 U	< 0.073 U	< 0.13 U	< 0.44 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.24 U	< 0.13 U			0.45	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	< 0.23 U	< 0.12 U			7.1 T	0.28	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	< 0.24 U	< 0.12 U			1.1	0.025 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.24 U	< 0.13 U			0.2	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	< 0.26 U	< 0.13 U			8.8	0.74	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	< 0.23 U	< 0.12 U			1.8	0.053 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	< 0.24 U	< 0.12 U			0.82	0.035 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.22 U	< 0.12 U			0.097	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	< 0.23 U	< 0.12 U			0.39	0.024 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	< 0.24 U	< 0.12 U			0.17	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.23 U	< 0.12 U			0.1	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.23 U	< 0.12 U			0.26	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.23 U	< 0.12 U			0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.78 U	< 0.41 U			2.1	0.1 J	< 0.094 U	< 0.076 U	< 0.13 U	< 0.46 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.24 U	< 0.12 U			0.14	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.22 U	< 0.11 U			0.04 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.23 U	< 0.12 U			0.08	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.22 U	< 0.12 U			0.036 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.23 U	< 0.12 U			0.021 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.25 U	< 0.13 U			0.043 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.23 U	< 0.12 U			0.17	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.23 U	< 0.12 U			0.22	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.89 U	< 0.46 U			0.44	< 0.058 U	< 0.11 U	< 0.087 U	< 0.15 U	< 0.53 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.22 U	< 0.12 U			0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.22 U	< 0.12 U			0.02 J	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.22 U	< 0.12 U			2.3	0.086	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.21 U	< 0.11 U			0.072	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.22 U	< 0.11 U			0.038 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 UT
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.23 U	< 0.12 U			0.26	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.21 U	< 0.11 U			0.056 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.22 U	< 0.11 U			0.12	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.22 U	< 0.12 U			0.045 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.22 U	< 0.12 U			3.1	0.088	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.22 U	< 0.11 U			2.3	0.064 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.21 U	< 0.11 U			0.26	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.22 U	< 0.11 U			0.024 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.21 U	< 0.11 U			0.27	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.26 U	< 0.13 U			0.23	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.22 U	< 0.11 U			0.02 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.22 U	< 0.11 U			0.44	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.21 U	< 0.11 U			0.053 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.22 U	< 0.12 U			0.51	0.04 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.25 U	< 0.13 U			0.085	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.21 U	< 0.11 U			0.26	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.26 U	< 0.13 U			0.59	0.026 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.22 U	< 0.12 U			0.044 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.62 U	< 0.32 U			0.25	< 0.041 U	< 0.074 U	< 0.061 U	< 0.11 U	< 0.37 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.23 U	< 0.12 U			0.053 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.23 U	< 0.12 U			0.08	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	1.1	< 0.36 U		< 0.46 U	0.081 J	< 0.36 U	0.073 J	< 0.57 U	< 0.32 U	< 0.46 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	0.17	< 0.12 U		< 0.15 U	0.053 J	< 0.12 U	0.042 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	1.2	< 0.11 U		< 0.14 U	0.15	< 0.11 U	0.29	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	0.43	< 0.11 U		< 0.15 U	0.044 J	< 0.12 U	0.057 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	0.076 J	< 0.12 U		< 0.15 U	0.075 J	< 0.12 U	0.056 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	0.95	< 0.12 U		< 0.16 U	0.061 J	< 0.13 U	0.19	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	0.92	< 0.11 U		< 0.14 U	0.055 J	< 0.11 U	0.084	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	0.39	< 0.11 U		< 0.15 U	0.029 J	< 0.12 U	0.047 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	0.066 J	< 0.11 U		< 0.14 U	0.019 J	< 0.11 U	0.024 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	0.24	< 0.11 U		< 0.14 U	0.075 J	< 0.11 U	0.15	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	0.1	< 0.11 U		< 0.15 U	0.03 J	< 0.12 U	0.048 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	0.068 J	< 0.11 U		< 0.14 U	0.026 J	< 0.11 U	0.03 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	0.14	< 0.11 U		< 0.14 U	0.07 J	< 0.11 U	0.087	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	0.062 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	0.87	< 0.37 U		< 0.49 U	0.17 J	< 0.38 U	0.21 J	< 0.6 U	< 0.33 U	< 0.49 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	0.06 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.024 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	0.038 J	< 0.11 U		< 0.14 U	0.06 J	< 0.11 U	0.049 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	0.21 J	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	0.084	< 0.11 U		< 0.15 U	0.019 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	0.14	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	0.018 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	0.32	< 0.43 U		< 0.56 U	0.098 J	< 0.44 U	0.16 J	< 0.68 U	< 0.38 U	< 0.55 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	0.1	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.034 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	0.03 J	< 0.11 U	0.084	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	1.8	< 0.11 U		< 0.14 U	0.089	< 0.11 U	0.095	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	0.053 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	0.014 J	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 UT	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	0.044 J	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	0.042 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.02 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.017 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	0.82	< 0.11 U		< 0.14 U	0.025 J	< 0.11 U	0.11	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	0.67	< 0.1 U		< 0.14 U	0.021 J	< 0.11 U	0.11	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	0.13	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	0.02 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	0.068 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	0.098	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	0.021 J	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	0.16	< 0.1 U		< 0.14 U	0.035 J	< 0.11 U	0.048 J	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	0.04 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.023 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	0.17	< 0.11 U		< 0.14 U	0.027 J	< 0.11 U	0.087	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	0.043 J	< 0.12 U		< 0.16 U	0.067 J	< 0.12 U	0.12	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	0.059 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	0.25	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	0.022 J	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	0.035 J	< 0.12 U	0.077 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	0.061 J	< 0.11 U		< 0.14 U	0.025 J	< 0.11 U	0.05 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	0.15 J	< 0.3 U		< 0.39 U	< 0.05 U	< 0.31 U	< 0.041 U	< 0.47 U	< 0.26 U	< 0.39 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U

DRAFT

												Nitrobenzene	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	< 0.45 U	< 0.46 U	< 0.87 U		< 0.084 U	< 0.41 U	< 2 U	2.2	< 0.38 U	3
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.15	< 0.12 U	0.53
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	4.8	< 0.12 U	6.9
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.27	< 0.12 U	1.3
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.086	< 0.12 U	0.27
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	6.5	< 0.13 U	7.7
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.53	< 0.12 U	2.3
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.25	< 0.12 U	1
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.027 J	< 0.11 U	0.12
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.14	< 0.12 U	0.47
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.067 J	< 0.12 U	0.21
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.051 J	< 0.12 U	0.12
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.041 J	< 0.12 U	0.33
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.13
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.48 U	< 0.48 U	< 0.92 U		< 0.089 U	< 0.44 U	< 2.1 U	0.73	< 0.4 U	2.2
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.07 J	< 0.12 U	0.14
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.021 J	< 0.11 U	0.044 J
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.031 J	< 0.11 U	0.091
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.039 J
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.024 J
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.03 J
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	0.036 J
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.2
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.091	< 0.12 U	0.24
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.54 U	< 0.55 U	< 1 U		< 0.1 U	< 0.49 U	< 2.4 U	0.26 J	< 0.45 U	0.42
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.07 J	< 0.11 U	0.19
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.024 J	< 0.11 U	0.032 J
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.29	< 0.11 U	4.7
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.034 J	< 0.11 U	0.083
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.033 J
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 UT		< 0.024 UT	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 UT	< 0.017 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.19	< 0.12 U	0.24
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.03 J	< 0.11 U	0.053 J
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.054 J	< 0.11 U	0.11
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.053 J
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	2.1	< 0.11 U	2.9
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	1.4	< 0.11 U	2.3
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.025 J	< 0.11 U	0.27
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.026 J
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.15	< 0.11 U	0.22
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.13	< 0.13 U	0.21
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.017 J
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.21	< 0.11 U	0.39
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.065 J
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.42	< 0.11 U	0.58
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.11	< 0.13 U	0.1
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.13	< 0.11 U	0.37
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	0.33	< 0.13 U	0.47
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.037 J	< 0.11 U	0.053 J
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.38 U	< 0.38 U	< 0.73 U		< 0.07 U	< 0.35 U	< 1.7 U	0.075 J	< 0.31 U	0.26
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.047 J
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.072 J
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated		< 0.49 U	< 0.52 U	< 0.43 U	< 0.41 U
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated		< 0.52 U	< 0.54 U	< 0.45 U	< 0.44 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated		< 0.59 U	< 0.62 U	< 0.52 U	< 0.49 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated		< 0.41 U	< 0.43 U	< 0.36 U	< 0.35 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH's**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated			0.142	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated			0.377	< 0.024 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.053 U	< 0.038 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated			0.464	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated			5.035	< 0.023 U	0.17	< 0.14 U	0.16	< 0.17 U	< 0.15 U	< 0.05 U	0.54
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated			13.29	0.028 J	0.66	< 0.14 U	0.49	< 0.17 U	< 0.14 U	< 0.048 U	1.2
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated			1.763	< 0.022 U	0.042 J	< 0.14 U	0.032 J	< 0.17 U	< 0.14 U	< 0.048 U	0.1
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated			5.363	< 0.0099 U	0.1 J	< 0.017 U	0.097 J	< 0.02 U	0.012 J	< 0.057 U	0.43
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated			7.65	< 0.053 U	0.2 J	< 0.091 U	0.3 J	< 0.11 U	< 0.064 U	< 0.31 U	0.31
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated			1.235	< 0.0097 U	0.028 J	< 0.017 U	0.02 J	< 0.02 U	< 0.012 U	< 0.056 U	0.1
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated			17.08	< 0.049 U	0.27 J	< 0.085 U	0.4 J	< 0.1 U	< 0.06 U	< 0.29 U	0.26
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated			1.324	< 0.011 U	0.035 J	< 0.019 U	0.03 J	< 0.023 UT	< 0.013 U	< 0.063 U	0.12
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated			2.183	< 0.011 U	0.051 J	< 0.018 U	0.031 J	< 0.022 U	< 0.013 U	< 0.061 U	0.2
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated			0.1039	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.017 J
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated			1.848	< 0.01 U	0.059 J	< 0.018 U	0.021 J	< 0.021 U	0.02 J	< 0.06 U	0.14
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated			0.903	< 0.011 U	0.028 J	< 0.018 U	0.013 J	< 0.022 U	< 0.013 U	< 0.062 U	0.075
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated			4.969	< 0.01 U	0.15 J	< 0.018 U	0.045 J	< 0.021 UT	< 0.013 U	< 0.06 U	0.43
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated			9.081	0.017 J	0.34 J	< 0.019 U	0.18 J	< 0.023 UT	0.026 J	< 0.064 U	0.79
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated			2.331	< 0.011 U	0.055 J	< 0.019 U	0.045 J	< 0.023 UT	< 0.013 U	< 0.064 U	0.2
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated			0.0565	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.014 J
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated			0.0871	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.017 J
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated			0.0783	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated			11.002	0.012 J	0.27 J	< 0.018 U	0.21 J	< 0.022 U	0.046 J	< 0.06 U	0.83
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated			6.818	0.017 J	0.22 J	< 0.018 U	0.17 J	< 0.021 U	0.044 J	< 0.06 U	0.41
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated			0.318	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.023 J
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated			1.74	0.03 J	0.019 J	< 0.019 U	0.052 J	< 0.022 U	0.021 J	< 0.063 U	0.14
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated			2.402	0.045 J	0.043 J	< 0.018 U	0.13 J	< 0.022 U	0.061 J	< 0.061 U	0.12
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated			0.295	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.033 J
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated			2.56	< 0.05 U	< 0.05 U	< 0.085 U	< 0.053 U	< 0.1 U	< 0.061 U	< 0.29 U	< 0.061 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated			0.2046	< 0.0097 U	0.012 J	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.022 J
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated			0.267	< 0.0094 U	< 0.0094 U	< 0.016 U	< 0.01 U	< 0.019 U	< 0.011 U	< 0.055 U	0.025 J
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated			0.546	< 0.0097 U	0.031 J	< 0.017 U	0.023 J	< 0.02 U	< 0.012 U	< 0.056 U	0.052
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated			0.0998	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.018 J
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated			0.123	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.037 J
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated			0.399	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.042 J
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated			0.133	< 0.022 U	0.033 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated			0.1005	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.016 J
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated			3.702	< 0.01 U	0.17 J	< 0.018 U	0.074 J	< 0.021 UT	0.022 J	< 0.06 U	0.37
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated			0.109	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.015 J
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated			0.992	< 0.01 U	0.016 J	< 0.018 U	0.016 J	< 0.021 UT	< 0.012 U	< 0.059 U	0.085
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated			0.2523	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	0.024 J
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated			0.276	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.027 J
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated			14.269	0.021 J	0.29	< 0.13 U	0.33	< 0.16 U	< 0.13 U	< 0.045 U	1.2
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated			1.458	< 0.021 U	< 0.016 U	< 0.13 U	0.023 J	< 0.16 U	< 0.14 U	< 0.046 U	0.14
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated			7.67	0.12	0.078	< 0.14 U	0.14	< 0.17 U	0.3 J	< 0.047 U	0.71
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated			0.757	< 0.02 U	< 0.015 U	< 0.13 U	0.019 J	< 0.15 U	< 0.13 U	< 0.044 U	0.069 J
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated			1.546	< 0.01 U	0.067 J	< 0.017 U	0.017 J	< 0.021 UT	< 0.012 U	< 0.058 UT	0.14
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated			3.256	< 0.0098 U	0.24 J	0.027 J	0.048 J	< 0.02 UT	0.024 J	< 0.057 UT	0.23
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated			1.7754	< 0.0097 U	0.06 J	< 0.017 U	0.02 J	< 0.02 UT	< 0.012 U	< 0.056 UT	0.16
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated			0.513	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 UT	0.049
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 UT	< 0.012 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated			0.013	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.013 J
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated			0.1658	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.02 J
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated			0.0062	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated			0.359	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.035 J
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated			0.198	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.026 J
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated			0.93	< 0.011 U	0.011 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.091

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	18013704 31	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	18013709 81	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	18013709 81	Not Excavated	< 0.034 U	0.024 J	< 0.024 U	0.056 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	18013709 81	Not Excavated	< 0.037 U	0.041 J	< 0.025 U	0.24	< 0.16 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	18013709 81	Not Excavated	< 0.034 UT	0.036 J	< 0.023 U	0.26	< 0.14 U	< 0.014 U	< 0.029 U	0.43 J	< 0.17 U	< 0.27 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	18013709 81	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	18013748 61	Not Excavated	0.32	0.63	0.11	0.43	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	18013748 61	Not Excavated	1.2	1.4	0.46	1.3	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	18013769 31	Not Excavated	0.15	0.18	0.081	0.26	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	18013779 81	Not Excavated	0.45	0.62	0.23	0.48	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	18013779 81	Not Excavated	0.23	0.48	0.18	2	< 0.14 U	< 0.065 U	< 0.034 U	< 0.098 U	< 0.073 U	< 0.087 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	18013779 81	Not Excavated	0.11	0.14	0.055	0.087 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	18013779 81	Not Excavated	1.5	1	0.37	5.2	< 0.13 U	< 0.06 U	< 0.031 U	< 0.091 U	< 0.069 U	< 0.081 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	18013783 43	Not Excavated	0.1	0.16	0.068	0.1 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	18013783 42	Not Excavated	0.21 T	0.31	0.12	0.14 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	18013783 41	Not Excavated	0.0095 J	0.015 J	0.0074 J	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	18013783 42	Not Excavated	0.15 T	0.23	0.086	0.12 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	18013783 42	Not Excavated	0.063 T	0.1	0.039	0.055 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	18013783 43	Not Excavated	0.29	0.68	0.25	0.17 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	18013783 43	Not Excavated	0.78	1.1	0.39	0.64	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	18013783 43	Not Excavated	0.2	0.28	0.11	0.15 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	18013798 61	Not Excavated	< 0.0094 U	0.014 J	< 0.0070 U	0.012 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	18013798 61	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	18013798 61	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	18013798 61	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	18013798 61	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	18013831 71	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	18013831 71	Not Excavated	< 0.0090 U	0.0099 J	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	18013831 71	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	18013918 81	Not Excavated	< 0.0090 U	0.01 J	< 0.0066 U	0.017 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	18013918 81	Not Excavated	0.89	1.3	0.52	0.76	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	18013918 81	Not Excavated	0.44	0.7	0.25	0.41	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	18013918 81	Not Excavated	0.015 J	0.026 J	< 0.0068 U	0.023 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	18013918 81	Not Excavated	0.076	0.13	0.052	0.046 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	18013918 81	Not Excavated	0.084	0.14	0.041	0.082 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	18013918 81	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	18013918 81	Not Excavated	0.025 J	0.035 J	0.014 J	0.019 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	18013918 81	Not Excavated	< 0.046 U	< 0.045 U	< 0.034 U	0.34 J	< 0.14 U	< 0.061 U	< 0.032 U	< 0.092 U	< 0.069 U	< 0.082 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	18013918 81	Not Excavated	0.013 J	0.018 J	0.0077 J	0.038 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	18013918 81	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	18013918 81	Not Excavated	0.023 J	0.033	0.012 J	0.022 J	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.017 U	< 0.013 U	< 0.015 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	18013918 81	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	18013918 81	Not Excavated	0.05	0.068	0.027 J	0.076 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	18013918 81	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	18013918 81	Not Excavated	< 0.0090 U	0.014 J	< 0.0067 U	0.012 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	18013982 72	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	18013982 72	Not Excavated	0.036 J	0.05 J	< 0.022 U	0.028 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	18013982 72	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	18013994 72	Not Excavated	0.0095 J	0.015 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	18013994 72	Not Excavated	0.29	0.53	0.2	0.18 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	18013994 72	Not Excavated	< 0.0094 U	0.014 J	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	18013994 72	Not Excavated	0.067	0.14	0.051	0.054 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	18013994 72	Not Excavated	0.014 J	0.029 J	0.0093 J	0.013 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	18013994 72	Not Excavated	0.019 J	0.032 J	0.016 J	0.016 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	18014018 21	Not Excavated	1.2	1.4	0.57	1.4	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	18014018 21	Not Excavated	0.12	0.16	0.057 J	0.11	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	18014018 21	Not Excavated	0.36	0.75	< 0.023 U	0.33	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	18014018 21	Not Excavated	0.05 J	0.083	0.035 J	0.069 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	18014067 72	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	0.39 J	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	18014067 71	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	18014067 72	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	18014076 31	Not Excavated	0.15	0.25	0.094	0.11 J	< 0.027 U	< 0.012 U	< 0.0064 U	0.023 J	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	18014076 31	Not Excavated	0.25	0.51	0.18	0.17 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	18014076 31	Not Excavated	0.15	0.25	0.089	0.13 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	18014076 31	Not Excavated	0.041 T	0.07	0.025 J	0.037 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	18014076 31	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	18014076 31	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	18014079 91	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	18014079 91	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	18014079 91	Not Excavated	0.017 J	0.026 J	0.0081 J	0.015 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	18014079 91	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	18014079 92	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	18014105 71	Not Excavated	0.022 J	0.044	0.024 J	0.016 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	18014105 71	Not Excavated	0.016 J	0.027 J	0.013 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	18014105 71	Not Excavated	0.077	0.11	0.05	0.05 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	0.058 J	< 0.14 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.051 U	< 0.15 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.26 U	0.055 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.089	< 0.15 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.25 U	0.067 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	1	0.3	< 0.14 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.18	0.097	< 0.14 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.054 U	0.03 J	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.41	0.14	0.028 J
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.29 U	0.073 J	< 0.33 U	< 0.1 U	< 0.086 U	< 0.066 U	< 0.065 U	0.32 J	0.31	< 0.062 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.094 J	0.033 J	0.012 J
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.27 U	0.074 J	< 0.31 U	< 0.097 U	< 0.08 U	< 0.062 U	< 0.061 U	0.2 J	1	< 0.058 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.11 J	0.035 J	< 0.013 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.22 J	0.042	0.015 J
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.012 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	0.032 J	< 0.013 U	< 0.013 U	0.23 J	0.043	0.032 J
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	0.07 J	< 0.013 U	< 0.013 U	0.096 J	0.019 J	0.013 J
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.057 U	0.027 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.55	0.067	0.029 J
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.06 UT	0.06 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.91	0.18	0.049 J
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.21 J	0.046	< 0.013 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0095 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0092 J	< 0.015 U	< 0.011 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0072 J	< 0.015 U	< 0.011 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.057 U	0.087 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.82	0.13	0.12 J
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.057 U	0.11 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.46	0.067	0.14 J
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.019 J	< 0.015 U	0.013 J
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.21 J	< 0.016 U	0.031 J
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.21 J	< 0.016 U	0.18 J
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.027 J	< 0.016 U	< 0.012 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.27 U	< 0.066 U	< 0.31 U	< 0.098 U	< 0.081 U	< 0.062 U	< 0.061 U	1 J	< 0.075 U	< 0.058 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.017 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.051 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	0.019 J	< 0.014 U	< 0.011 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.039 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0091 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.041 J	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.068 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.014 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.056 U	0.027 J	< 0.064 U	< 0.02 U	0.03 J	< 0.013 U	< 0.013 U	0.37	0.076	0.034 J
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.013 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.12 J	0.03 J	< 0.012 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.025 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.031 J	< 0.016 U	< 0.012 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.23 U	0.11	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	1.1	0.32	0.13 J
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.16	< 0.047 U	< 0.14 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.4	0.07 J	0.26 J
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.08	< 0.045 U	< 0.13 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.16 J	0.04	< 0.012 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.054 U	0.015 J	< 0.061 UT	< 0.019 U	0.031 J	< 0.012 U	< 0.012 U	0.36	0.057	0.035 J
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.17 J	0.042	< 0.011 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 UT	< 0.021 U	< 0.017 U	< 0.013 UT	< 0.013 U	0.073 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.017 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0062 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.038 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.029 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.093 J	0.032 J	< 0.013 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					
Restricted - Residential																					
Protection of Groundwater																					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.36 U	< 0.03 U	0.24 BJ	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.37 U	< 0.031 U	0.14 BJ	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.28 U	< 0.12 U	< 0.06 U	< 0.22 U	< 0.42 U	< 0.07 U	< 0.098 U	< 0.76 U	< 0.13 U	< 0.91 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.26 U	< 0.11 U	< 0.056 U	< 0.21 U	< 0.39 U	< 0.065 U	< 0.092 U	< 0.71 U	< 0.13 U	< 0.85 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.075 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.069 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	0.04 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.03 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 UT	< 0.028 U	< 0.19 UT
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.26 U	< 0.11 U	< 0.056 U	< 0.21 U	< 0.4 U	< 0.066 U	< 0.092 U	< 0.71 U	< 0.13 U	< 0.86 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.039 U	< 0.075 U	< 0.012 U	< 0.017 U	< 0.13 U	< 0.024 U	< 0.16 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	0.2 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.34 U	< 0.028 U	0.36	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.056 U	< 0.024 UT	< 0.012 U	< 0.044 UT	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg			mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.24 U	< 0.12 U			0.033 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.24 U	< 0.12 U			0.94	0.036 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.23 U	< 0.12 U			1.9	0.062 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.23 U	< 0.12 U			0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.037 U		< 0.03 U		0.79	0.016 J	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.2 U		< 0.16 U		0.53 J	< 0.054 U	< 0.088 U	< 0.039 U	< 0.16 U	< 0.064 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.037 U		< 0.03 U		0.17 J	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.19 U		< 0.15 U		0.34 J	< 0.051 U	< 0.082 U	< 0.037 U	< 0.15 U	< 0.059 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.041 U		< 0.033 U		0.18 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.04 U		< 0.032 U		0.29 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.038 U		< 0.031 U		0.016 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.039 U		< 0.032 U		0.21 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.04 U		< 0.033 U		0.12 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.039 U		< 0.032 U		0.83	0.014 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.042 U		< 0.034 U		1.2	0.044 J	< 0.018 UT	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.041 U		< 0.034 U		0.34 J	< 0.011 U	< 0.018 UT	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.042 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.037 U		< 0.03 U		0.02 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.039 U		< 0.032 U		1.7	0.04 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.039 U		< 0.032 U		1.1	0.044 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.037 U		< 0.03 U		0.024 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.041 U		< 0.033 U		0.25 J	0.062 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.04 U		< 0.032 U		0.29 J	0.19 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.039 U		< 0.032 U		0.037 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.19 U		< 0.15 U		0.14 J	< 0.051 U	< 0.083 U	< 0.037 U	< 0.15 U	< 0.06 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.037 U		< 0.03 U		0.021 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.036 U		< 0.029 U		0.033 J	< 0.0097 U	< 0.016 U	< 0.0070 U	< 0.029 U	< 0.011 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.037 U		< 0.03 U		0.078 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.037 U		< 0.03 U		0.017 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.21 U	< 0.11 U			0.045 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.22 U	< 0.12 U			0.062 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.23 U	< 0.12 U			0.037 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.037 U		< 0.03 U		0.015 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.039 U		< 0.032 U		0.45	0.022 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.038 U		< 0.031 U		0.014 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.039 U		< 0.031 U		0.14 J	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.037 U		< 0.03 U		0.028 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.039 U		< 0.031 U		0.039 J	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.22 U	< 0.11 U			1.8	0.058 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.22 U	< 0.12 U			0.21	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.23 U	< 0.12 U			0.65	0.26	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.21 U	< 0.11 U			0.11	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.038 U		< 0.031 UT		0.15 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 UT
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.037 U		< 0.03 UT		0.34	0.021 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 UT
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.037 U		< 0.03 UT		0.22 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 UT
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.04 U		< 0.032 UT		0.04 J	< 0.011 U	< 0.018 U	< 0.0079 UT	< 0.032 U	< 0.013 WARN
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.038 U		< 0.031 UT		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 UT
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.037 U		< 0.03 UT		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 UT
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		0.017 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.042 U		< 0.034 U		0.053 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.038 U		< 0.031 U		0.033 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.041 U		< 0.034 U		0.13 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	0.096	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.017 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	0.11	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	0.37	< 0.11 U		< 0.15 U	0.048 J	< 0.12 U	0.14	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	1.1	< 0.11 U		< 0.14 U	0.078	< 0.11 U	0.25	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	0.2	< 0.11 U		< 0.15 U	0.083	< 0.11 U	0.063 J	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	0.56	< 0.013 U		< 0.1 U	0.051 J	< 0.022 U	0.14 J	< 0.026 U	< 0.083 U	< 0.04 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	2.1	< 0.069 U		< 0.54 U	0.19 J	< 0.12 U	0.19 J	< 0.14 U	< 0.44 U	< 0.21 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	0.13	< 0.013 U		< 0.098 U	0.026 J	< 0.021 U	0.066 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	6.2	< 0.065 U		< 0.5 U	0.11 J	< 0.11 U	0.13 J	< 0.13 U	< 0.41 U	< 0.2 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	0.14	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.019 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	0.17	< 0.014 U		< 0.11 U	0.034 J	< 0.023 U	0.05 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	0.13	< 0.014 U		< 0.11 U	0.11 J	< 0.023 U	0.078 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	0.055	< 0.014 U		< 0.11 U	0.044 J	< 0.023 U	0.048 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	0.32	< 0.014 U		< 0.1 U	0.069 J	< 0.023 U	0.093 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	0.72	< 0.014 U		< 0.11 U	0.12 J	< 0.024 U	0.22 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	0.17	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.02 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0070 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0057 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	0.014 J	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	0.011 J	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	1	< 0.014 U		< 0.11 U	0.15 J	< 0.023 U	0.6	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	0.53	< 0.014 U		< 0.11 U	0.12 J	0.025 J	0.51	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	0.039	< 0.013 U		< 0.1 U	0.019 J	< 0.022 U	0.092 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	0.097	< 0.014 U		< 0.11 U	0.086 J	< 0.024 U	0.065 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	0.13	< 0.014 U		< 0.11 U	0.12 J	< 0.023 U	0.16 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	0.046	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	0.43	< 0.065 U		< 0.5 U	< 0.049 U	0.77 J	< 0.03 U	< 0.13 U	< 0.41 U	< 0.2 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	0.028 J	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	0.0099 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	0.046	< 0.012 U		< 0.095 U	< 0.0092 U	< 0.021 U	0.0080 J	< 0.025 U	< 0.078 U	< 0.038 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	0.065	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	0.0082 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.028 J	< 0.11 U	0.056 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	0.24	< 0.014 U		< 0.1 U	0.078 J	< 0.023 U	0.21 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	0.027 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	0.091	< 0.013 U		< 0.1 U	0.014 J	< 0.022 U	0.017 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	0.033 J	< 0.013 U		< 0.098 U	0.027 J	< 0.021 U	0.018 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	0.037	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	1.2	< 0.1 U		< 0.14 U	0.17	< 0.11 U	0.58	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	0.088	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	0.34	< 0.11 U		< 0.14 U	0.57	< 0.11 U	0.34	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	0.052 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	0.17	< 0.013 U		< 0.1 U	0.023 J	< 0.022 U	0.033 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	0.25	< 0.013 U		< 0.1 U	0.082 J	< 0.022 U	0.19 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	0.19	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	0.0084 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	0.065	< 0.014 U		< 0.11 UT	0.018 JT	< 0.023 U	0.012 JT	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	0.018 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	0.053	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	0.093	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.011 J	< 0.029 U	< 0.091 U	< 0.044 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.029 J
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.4	< 0.12 U	0.87
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.8	< 0.12 U	1.8
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.15	< 0.12 U	0.16
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.32 J	< 0.013 U	0.68
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.1 U	< 0.19 U	< 0.3 U		< 0.13 U	< 0.15 U	< 0.38 U	0.29 J	< 0.068 U	0.41 J
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.08 J	< 0.013 U	0.15 J
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.096 U	< 0.17 U	< 0.28 U		< 0.13 U	< 0.14 U	< 0.35 U	0.2 J	< 0.064 U	0.28 J
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.092 J	< 0.014 U	0.17 J
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.11 J	< 0.014 U	0.29 J
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.011 J	< 0.013 U	0.016 J
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.18 J	< 0.013 U	0.23 J
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.11 J	< 0.014 U	0.11 J
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.53	< 0.013 U	0.7
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.51	< 0.014 U	1.4
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.21 J	< 0.014 U	0.35 J
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0058 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.014 J	< 0.012 U	0.017 J
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	0.0081 J	< 0.012 U	0.011 J
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.79	< 0.013 U	1.4
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.88	< 0.013 U	0.83
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.034 J	< 0.013 U	0.023 J
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.21 J	< 0.014 U	0.32 J
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.47	< 0.014 U	0.31 J
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.023 J	< 0.013 U	0.036 J
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.097 U	< 0.17 U	< 0.28 U		< 0.13 U	< 0.14 U	< 0.36 U	< 0.031 U	< 0.064 U	0.65 J
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.011 J	< 0.013 U	0.019 J
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	0.018 J	< 0.012 U	0.028 J
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	0.068 J
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0065 J	< 0.012 U	0.015 J
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.05 J	< 0.11 U	0.063 J
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.04 J	< 0.12 U	< 0.018 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.016 J	< 0.013 U	0.015 J
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.19 J	< 0.013 U	0.5
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.014 J	< 0.013 U	0.012 J
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.061 J	< 0.013 U	0.12 J
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.033 J	< 0.013 U	0.026 J
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.026 J	< 0.013 U	0.033 J
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.99	< 0.11 U	2.1
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.12	< 0.11 U	0.27
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.1	< 0.12 U	1.1
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.08	< 0.11 U	0.11
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.052 J	< 0.013 U	0.18 J
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.22 J	< 0.013 U	0.43
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.096 J	< 0.013 U	0.25 J
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.02 U	< 0.037 UT	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.055 J	< 0.014 U	0.046 J
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.0077 J	< 0.013 U	0.02 J
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.028 J	< 0.014 U	0.046 J
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.02 J	< 0.013 U	0.034 J
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.043 J	< 0.014 U	0.15 J

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated		< 0.058 U	< 0.13 U	< 0.19 U	< 0.24 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated		< 0.054 U	< 0.12 U	< 0.18 U	< 0.22 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated		0.041 J	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated		< 0.012 UT	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated		< 0.012 UT	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated		< 0.054 U	< 0.12 U	< 0.18 U	< 0.22 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated		< 0.01 U	< 0.022 U	< 0.034 U	< 0.042 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	853.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated			1.763	< 0.01 U	0.032 J	< 0.017 U	0.05 J	< 0.021 U	< 0.012 U	< 0.058 U	0.15
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated			2.15	< 0.019 U	0.056 J	< 0.12 U	0.057 J	< 0.15 U	< 0.12 U	< 0.042 U	0.17
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated			0.0587	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated			0.1831	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.024 J
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated			0.025	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	0.014 J
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated			0.0265	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.013 J
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated			0.0507	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.016 J
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated			3.746	0.013 J	0.071 J	< 0.018 U	0.19 J	< 0.022 U	< 0.013 U	< 0.062 U	0.3
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated			0.813	< 0.011 U	0.018 J	< 0.018 U	0.021 J	< 0.022 U	< 0.013 U	< 0.062 U	0.079
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated			5.236	< 0.021 U	0.2	< 0.13 U	0.16	< 0.16 U	< 0.13 U	< 0.045 U	0.46
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated			0.041	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated			6.813	0.027 J	0.33	< 0.14 U	0.25	< 0.17 U	< 0.14 U	< 0.049 U	0.53
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated			1.718	< 0.02 U	0.063 J	< 0.12 U	0.05 J	< 0.15 U	< 0.13 U	< 0.043 U	0.16
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated			2.803	< 0.021 U	0.15	< 0.13 U	0.085	< 0.16 U	< 0.13 U	< 0.045 U	0.24
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated			7.772	0.02 J	0.37	< 0.13 U	0.27	< 0.15 U	< 0.13 U	< 0.044 U	0.7
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated			5.25	< 0.02 U	0.12	< 0.12 U	0.11	< 0.15 U	< 0.13 U	< 0.043 U	0.47
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated			0.615	< 0.02 U	0.016 J	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.048 J
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated			0.047	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.013 J
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated			0.453	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.051
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated			75.8	1.7	0.05 J	< 0.019 U	3.3	< 0.022 UT	0.088 J	< 0.063 U	0.63
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated			1.232	< 0.011 U	0.015 J	< 0.019 U	0.019 J	< 0.023 UT	< 0.013 U	< 0.064 U	0.11
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated			0.1521	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated			0.31	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.03 J
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	3.11 ft	1801418911	Not Excavated			0.0815	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.012 J
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated			0.1251	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.014 J
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated			0.7651	< 0.01 U	0.017 J	< 0.017 U	0.016 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.071
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated			0.983	0.015 J	0.048 J	< 0.017 U	0.033 J	< 0.021 UT	0.016 J	< 0.058 U	0.075
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated			0.421	< 0.0095 U	< 0.0095 U	< 0.016 U	0.012 J	< 0.02 U	< 0.012 U	< 0.055 U	0.031 J
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated			0.1695	< 0.0096 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	0.017 J
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated			1.377	< 0.011 U	< 0.011 U	< 0.019 U	0.029 J	< 0.023 U	< 0.014 U	< 0.065 U	0.12
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated			2.079	0.04 J	0.038 J	0.019 J	0.1 J	< 0.021 U	0.015 J	< 0.06 U	0.16
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated			29.538	0.048 J	0.59	< 0.017 U	1	< 0.021 U	0.053 J	< 0.059 U	2.8
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated			0.832	< 0.016 U	< 0.016 U	< 0.028 U	< 0.017 U	< 0.033 UT	< 0.02 U	< 0.093 U	0.071
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated			0.3142	< 0.01 U	< 0.01 U	< 0.017 UT	< 0.011 UT	< 0.021 U	< 0.012 U	< 0.058 U	0.033 J
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated			0.2179	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.025 J
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated			0.041	< 0.01 U	0.02 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated			0.633	< 0.011 U	0.032 J	< 0.019 U	0.015 J	< 0.023 U	< 0.013 U	< 0.064 U	0.049
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated			0.0094	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated			0.12	< 0.01 U	0.041 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated			0.552	< 0.011 U	0.021 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.043
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated			0.0581	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated			0.1153	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.02 J
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated			0.237	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.026 J
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated			1.451	< 0.013 U	0.041 J	< 0.022 U	0.076 J	< 0.026 U	< 0.015 U	< 0.073 U	0.13
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated			0.015	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated			0.14	< 0.011 U	0.049 J	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated			0.678	< 0.011 U	0.036 J	< 0.02 U	0.018 J	< 0.024 U	< 0.014 U	< 0.066 U	0.049
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated			0.313	< 0.011 U	0.015 J	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.031 J
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated			2.414	< 0.01 U	0.39	< 0.018 U	0.053 J	< 0.021 U	0.072 J	< 0.06 U	0.07
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated			0.203	< 0.01 U	0.029 J	< 0.017 U	0.012 J	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated			0.015	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated			5.757	0.015 J	0.15 J	< 0.018 U	0.13 J	< 0.021 U	0.051 J	< 0.06 U	0.45
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated			5.081	< 0.011 U	0.17 J	< 0.018 U	0.08 J	< 0.022 U	0.024 J	< 0.061 U	0.38
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated			1.127	< 0.01 U	0.16 J	< 0.018 U	0.015 J	< 0.021 U	0.042 J	< 0.059 U	0.032 J
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated			0.619	< 0.01 U	0.018 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated			0.467	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.042
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated			10.517	0.077 J	0.44	< 0.018 U	0.23 J	< 0.022 U	0.06 J	< 0.062 U	0.77
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated			0.377	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.033 J
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated			0.0363	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated			ND	< 0.01 U	< 0.01 UT	< 0.017 U	< 0.011 UT	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	0.13	0.17	0.082	0.12 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	0.17	0.24	0.061 J	0.18	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	0.015 J	0.024 J	0.0091 J	0.011 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.0094 U	< 0.0092 U	0.0070 J	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.0096 U	0.012 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	0.25	0.33	0.12	0.18 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	0.065	0.087	0.038	0.054 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	0.48	0.56	0.18	0.52	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	0.56	0.72	0.25	0.71	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	0.14	0.19	0.06 J	0.18	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	0.26	0.31	0.13	0.27	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	0.75	0.81	0.36	0.91	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	0.48	0.6	0.19	0.57	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	0.049 J	0.078	0.025 J	0.045 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	0.043	0.061	0.02 J	0.024 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	4.3	5.4	2.2	2.1	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	0.1	0.16	0.052	0.07 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	0.015 J	0.021 J	0.0081 J	0.011 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	0.021 J	0.035 J	0.013 J	0.02 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	–	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.0092 U	0.014 J	0.0074 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	0.01 J	0.017 J	0.0071 J	0.011 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	0.069	0.11	0.043	0.046 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	0.061	0.08	0.033 J	0.044 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	0.034	0.063	0.021 J	0.025 J	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	0.014 J	0.028 J	0.013 J	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	0.099	0.14	0.056	0.065 J	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	0.12	0.16	0.07	0.068 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	2.3	3	1.1	1.1	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	0.062	0.088	0.033 J	0.05 J	< 0.044 U	< 0.02 U	< 0.01 U	< 0.03 U	< 0.022 U	< 0.026 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.019 JT	0.032 J	0.012 J	0.018 JT	< 0.028 UT	< 0.012 UT	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.015 J	0.022 J	0.0079 J	0.011 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	0.041 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	0.037 J	0.058	0.031 J	0.092 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.0092 U	0.0094 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	0.12 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	0.031 J	0.068	0.017 J	0.066 J	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.0092 U	0.02 J	< 0.0068 U	0.018 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	0.021 J	0.032 J	0.012 J	0.02 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.16	0.2	0.074	0.11 J	< 0.035 U	< 0.015 U	< 0.0080 U	< 0.023 U	< 0.018 U	< 0.021 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0099 U	< 0.0097 U	< 0.0073 U	0.015 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	0.14 J	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.053	0.078	0.027 J	0.062 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	0.026 J	0.037 J	0.013 J	0.038 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	0.074	0.12	0.031 J	0.077 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0094 U	0.012 J	< 0.0069 U	0.11 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	0.097 J
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	0.015 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	0.46	0.67	0.25	0.35 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	0.5	0.71	0.24	0.46	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	0.026 J	0.059	0.015 J	0.015 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	0.12	0.23	0.058	0.06 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	0.049	0.058	0.024 J	0.034 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	0.89	1.3	0.44	0.88	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	0.025 J	0.035 J	0.013 J	0.04 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.0094 UT	< 0.0091 UT	< 0.0069 UT	< 0.01 UT	< 0.027 UT	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.016 UT

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.15 J	0.029 J	< 0.012 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.22 U	0.019 J	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.21	0.052 J	< 0.12 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0097 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.016 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.0065 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0097 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.058 U	0.028 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.27 J	0.044	0.028 J
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.064 J	< 0.016 U	< 0.012 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.24 U	0.035 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.52	0.13	< 0.13 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.26 U	0.065 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.66	0.19	< 0.14 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.18	0.05 J	< 0.13 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.24 U	0.02 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.28	0.067 J	< 0.13 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.23 U	0.055 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.74	0.22	< 0.13 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.23 U	0.045 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.58	0.15	< 0.13 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.1	< 0.045 U	< 0.13 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.01 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.045 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.059 U	1.2	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	4.3	0.67	0.85
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.13 J	0.021 J	< 0.013 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.028 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.012 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.016 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.071 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.07 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	0.049 J	< 0.014 U	< 0.011 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.024 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.13 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.056 U	0.033 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.15 J	0.016 J	0.058 J
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.055 U	0.25 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	2.4	0.36	0.34 J
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.087 U	< 0.021 U	< 0.1 U	< 0.032 U	< 0.026 U	< 0.02 U	< 0.02 U	0.074 J	< 0.024 U	< 0.019 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 UT	< 0.012 U	0.029 J	< 0.015 UT	< 0.012 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.018 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 UT	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.049 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 UT	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.061 UT	< 0.015 U	< 0.07 UT	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.052 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 UT	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0091 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.023 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.069 U	0.027 J	< 0.079 U	< 0.025 U	< 0.021 U	< 0.016 U	< 0.016 U	0.15 J	0.026 J	< 0.015 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.019 U	< 0.014 U	< 0.014 U	0.06 J	< 0.017 U	0.023 J
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.021 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	0.98	< 0.013 U	< 0.013 U	0.1 J	0.016 J	0.041 J
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.057 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.057 U	0.042 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.44	0.093	0.11 J
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	< 0.057 U	0.029 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.43	0.11	0.048 J
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	0.083 J	< 0.013 U	< 0.013 U	0.11 J	< 0.015 U	0.036 J
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	0.038	0.02 J
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.054 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	1.2	0.2	0.16 J
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.037 J	< 0.017 U	0.013 J
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0093 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 UT	< 0.015 U	< 0.012 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	1	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	0.051 J	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.079 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	0.067 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	0.068 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.085 U	< 0.036 U	< 0.018 U	< 0.067 U	< 0.13 U	< 0.021 U	< 0.03 U	< 0.23 U	< 0.041 U	< 0.28 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.053 UT	< 0.023 UT	< 0.011 U	< 0.042 UT	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 UT	< 0.026 U	< 0.17 UT
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.059 UT	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.052 UT	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.054 UT	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.054 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.055 UT	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.052 UT	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.067 U	< 0.028 U	< 0.014 U	< 0.053 U	< 0.1 U	< 0.017 U	< 0.024 U	< 0.18 U	< 0.032 U	< 0.22 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 UT	< 0.08 U	< 0.013 UT	< 0.019 UT	< 0.14 U	< 0.025 UT	< 0.17 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.038 U		< 0.031 U		0.28 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.2 U	< 0.1 U			0.26	0.027 J	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.038 U		< 0.031 U		0.014 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.039 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.039 U		< 0.032 U		0.029 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.04 U		< 0.033 U		0.65	0.052 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.04 U		< 0.033 U		0.13 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.22 U	< 0.11 U			0.63	0.026 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.22 U	< 0.11 U			0.021 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.23 U	< 0.12 U			0.79	0.034 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.21 U	< 0.11 U			0.2	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.22 U	< 0.11 U			0.37	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.21 U	< 0.11 U			0.8	0.032 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.21 U	< 0.11 U			0.56	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.21 U	< 0.11 U			0.071	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		0.071 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.041 U		< 0.033 U		13	1.5	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.042 U		< 0.034 U		0.17 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.039 U		< 0.032 U		0.023 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		0.052 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.037 U		< 0.03 U		0.014 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		0.016 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.038 U		< 0.031 U		0.11 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.038 U		< 0.031 U		0.11 J	0.048 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.036 U		< 0.029 U		0.053 J	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.036 U		< 0.029 U		0.023 J	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.042 U		< 0.034 U		0.23 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.039 U		< 0.032 U		0.29 J	0.075 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.038 U		< 0.031 U		5.2	0.14 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.06 U		< 0.049 U		0.11 J	< 0.016 U	< 0.027 U	< 0.012 U	< 0.049 U	< 0.019 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.038 U		< 0.031 U		0.043 J	< 0.01 U	< 0.017 UT	< 0.0075 UT	< 0.031 UT	< 0.012 UT
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.038 U		< 0.031 U		0.024 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.042 U		< 0.034 U		0.069 J	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.042 U		< 0.034 U		0.067 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.039 U		< 0.032 U		0.018 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.037 U		< 0.03 U		0.018 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.042 U		< 0.034 U		0.029 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.048 U		< 0.039 U		0.16 J	< 0.013 U	< 0.021 U	< 0.0094 U	< 0.039 U	< 0.015 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.043 U		< 0.035 U		0.067 J	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.041 U		< 0.033 U		0.039 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.039 U		< 0.032 U		0.23 J	0.014 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.038 U		< 0.031 U		0.013 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	B-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.039 U		< 0.032 U		0.82	0.039 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	< 0.04 U		< 0.032 U		0.59	0.021 J	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	< 0.038 U		< 0.031 U		0.1 J	0.025 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	< 0.038 U		< 0.031 U		0.056 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	< 0.04 U		< 0.033 U		0.94	0.17 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	< 0.041 U		< 0.034 U		0.04 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 UT	< 0.031 U	< 0.012 UT

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	0.12	< 0.013 U		< 0.1 U	0.014 J	< 0.022 U	0.072 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	0.16	< 0.096 U		< 0.13 U	0.038 J	< 0.098 U	0.093	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.0090 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	0.014 J	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	0.2	< 0.014 U		< 0.11 U	0.016 J	< 0.023 U	0.067 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	0.058	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.035 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	0.42	< 0.1 U		< 0.14 U	0.034 J	< 0.11 U	0.05 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.033 U	< 0.096 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	0.59	< 0.11 U		< 0.15 U	0.11	< 0.12 U	0.092	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	0.14	< 0.099 U		< 0.13 U	0.018 J	< 0.1 U	0.019 J	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	0.22	< 0.1 U		< 0.14 U	0.022 J	< 0.11 U	0.031 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	0.73	< 0.1 U		< 0.13 U	0.11	< 0.1 U	0.17	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	0.47	< 0.1 U		< 0.13 U	0.15	< 0.1 U	0.12	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	0.035 J	< 0.1 U		< 0.13 U	0.046 J	< 0.1 U	0.03 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	0.031 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	2.9	< 0.014 U		< 0.11 U	0.24 J	< 0.024 U	0.23 J	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	0.092	< 0.014 U		< 0.11 U	0.011 J	< 0.024 U	0.018 J	< 0.03 U	< 0.092 U	< 0.044 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	0.023 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.018 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0061 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	0.098	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0091 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	0.049	< 0.013 U		< 0.1 U	0.12 J	< 0.022 U	0.095 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	0.027 J	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	0.011 J	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	0.013 J	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	0.12	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	0.0080 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	0.12	< 0.014 U		< 0.1 U	0.091 J	< 0.023 U	0.11 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	1.6	0.018 J		< 0.1 U	0.15 J	0.056 J	0.29 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	0.052 J	< 0.021 U		< 0.16 U	< 0.016 U	< 0.035 U	0.063 J	< 0.043 U	< 0.13 U	< 0.065 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.054 T	< 0.013 UT		< 0.1 UT	< 0.0099 UT	< 0.022 U	0.0062 JT	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.053	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	0.1	< 0.014 U		< 0.11 U	0.011 J	< 0.024 U	0.023 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	0.095	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	0.032 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0093 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	0.02 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.011 J	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.12	< 0.017 U		< 0.13 U	0.016 J	< 0.028 U	0.046 J	< 0.034 U	< 0.11 U	< 0.051 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.059	< 0.015 U		< 0.12 U	0.034 J	< 0.025 U	0.091 J	< 0.03 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	0.027 J	< 0.014 U		< 0.11 U	0.011 J	< 0.024 U	0.028 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	0.069	< 0.014 U		< 0.1 U	0.11 J	< 0.023 U	1	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	0.032 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.011 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.015 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	0.38	< 0.014 U		< 0.11 U	0.15 J	< 0.023 U	0.45	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	0.47	< 0.014 U		< 0.11 U	0.089 J	< 0.023 U	0.31 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	0.014 J	< 0.013 U		< 0.1 U	0.13 J	< 0.022 U	0.4	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	0.086	< 0.013 U		< 0.1 U	0.022 J	< 0.022 U	0.027 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	0.038	< 0.013 U		< 0.1 U	0.012 J	< 0.022 U	0.017 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	0.94	< 0.014 U		< 0.11 U	0.22 J	0.058 J	0.48	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	0.033 J	< 0.014 U		< 0.11 U	0.014 J	< 0.024 U	0.038 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 UT	< 0.0098 UT	< 0.022 U	< 0.0061 UT	< 0.027 U	< 0.083 U	< 0.04 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Nitrobenzene	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.15 J	< 0.013 U	0.26 J
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.17	< 0.1 U	0.3
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.011 J	< 0.013 U	0.015 J
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.015 J	< 0.013 U	0.026 J
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	0.011 J
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	0.013 J
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.49	< 0.014 U	0.59
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.062 J	< 0.014 U	0.12 J
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.27	< 0.11 U	0.83
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.02 J
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.44	< 0.12 U	0.97
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.089	< 0.1 U	0.26
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.14	< 0.11 U	0.4
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.26	< 0.11 U	1
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.35	< 0.11 U	0.6
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.059 J	< 0.11 U	0.075
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 UT		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 UT		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.012 J	< 0.013 U	0.012 J
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.032 J	< 0.013 U	0.075 J
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	14	< 0.014 U	13
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.12 J	< 0.014 U	0.17 J
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.014 J	< 0.013 U	0.022 J
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.027 J	< 0.013 U	0.043 J
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.016 J
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.017 J	< 0.013 U	0.017 J
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.026 J	< 0.013 U	0.096 J
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.14 J	< 0.013 U	0.13 J
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	0.032 J	< 0.012 U	0.063 J
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	0.0085 J	< 0.012 U	0.029 J
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.16 J	< 0.014 U	0.22 J
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.36	< 0.013 U	0.24 J
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	4	< 0.013 U	4.2
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.031 U	< 0.056 U	< 0.092 U		< 0.041 U	< 0.046 U	< 0.12 U	0.069 J	< 0.021 U	0.16 J
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.02 UT	< 0.035 UT	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.023 JT	< 0.013 U	0.045 J
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.015 J	< 0.013 U	0.027 J
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.036 J	< 0.014 U	0.074 J
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	0.019 J	< 0.014 U	0.062 J
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	0.013 J
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.019 J
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.014 J	< 0.014 U	0.029 J
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.025 U	< 0.044 U	< 0.072 U		< 0.032 U	< 0.036 U	< 0.091 U	0.069 J	< 0.016 U	0.13 J
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.05 J	< 0.015 U	0.064 J
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.02 J	< 0.014 U	0.033 J
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.36	< 0.013 U	0.2 J
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.013 J	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	< 0.0099 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.49	< 0.013 U	0.72
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.24 J	< 0.014 U	0.54
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.22 J	< 0.013 U	0.096 J
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.032 J	< 0.013 U	0.063 J
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.7	< 0.014 U	1.3
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.036 J	< 0.014 U	0.047 J
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.016 J	< 0.013 U	0.011 J
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated	< 0.019 U	< 0.035 UT	< 0.057 U		< 0.026 U	< 0.029 UT	< 0.072 U	< 0.0062 UT	< 0.013 U	< 0.0087 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated		< 0.018 U	< 0.038 U	< 0.057 U	< 0.072 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated		< 0.014 U	< 0.03 U	< 0.045 U	< 0.057 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated		0.22 J	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated			0.391	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.047
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated			0.214	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.013 J
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated			0.038	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated			0.047	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated			3.637	0.017 J	0.019 J	< 0.017 U	0.044 J	< 0.021 U	0.027 J	< 0.058 U	0.051
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated			0.293	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.034 J
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated			0.41	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.04
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated			0.0419	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.015 J
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated			0.253	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.031 J
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated			0.1092	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.018 J
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated			0.157	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.025 J
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated			12.149	< 0.01 U	0.33 J	< 0.017 U	0.14 J	< 0.021 U	< 0.012 U	< 0.059 U	1.1
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated			55.589	0.039 J	1.3	< 0.018 U	0.7	< 0.021 U	0.018 J	< 0.059 U	5.1
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated			7.308	< 0.01 U	0.2 J	< 0.017 U	0.094 J	< 0.021 U	0.012 J	< 0.058 U	0.63
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated			4.034	< 0.0097 U	0.11 J	< 0.017 U	0.05 J	< 0.02 U	< 0.012 U	< 0.057 U	0.37
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated			0.172	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.02 J
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated			0.1098	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.012 J
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated			1.407	< 0.0099 U	0.037 J	< 0.017 U	0.012 J	< 0.02 U	< 0.012 U	< 0.058 U	0.12
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated			0.779	< 0.011 U	0.03 JT	< 0.02 U	< 0.012 UT	< 0.023 U	< 0.014 UT	< 0.066 U	0.07 T
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated			0.5879	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	0.06
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated			0.938	< 0.01 U	0.027 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.074
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated			0.988	< 0.011 U	0.024 J	< 0.019 U	0.021 J	< 0.023 U	< 0.013 U	< 0.064 U	0.076
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated			0.699	< 0.01 U	0.015 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.064
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated			0.399	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.036 J
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated			0.498	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.054
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated			0.3146	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.03 J
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated			5.666	0.031 J	< 0.012 U	< 0.02 U	0.11 J	< 0.024 U	< 0.014 U	< 0.067 U	0.47
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated			10.267	0.082 J	0.24 J	< 0.019 U	0.21 J	< 0.023 U	0.016 J	< 0.064 U	0.89
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated			0.025	< 0.01 U	< 0.01 U	< 0.017 U	0.012 J	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated			0.025	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated			0.32	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	0.031 J
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated			0.0939	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.018 J
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated			ND	< 0.021 U	< 0.021 U	0.42 J	< 0.023 U	< 0.044 U	< 0.026 U	2.1	< 0.026 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated			0.0746	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.016 J
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated			0.0626	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.014 J
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated			0.132	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.022 J
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated			0.0069	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**	**Butylbenzyl phthalate**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	0.025 J	0.028 J	0.011 J	0.026 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	0.011 J	0.019 J	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.0095 U	0.01 J	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	0.034 J	0.041	0.02 J	0.017 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	0.023 J	0.029 J	0.02 J	0.012 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	0.026 J	0.047	0.017 J	0.021 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.0096 U	0.01 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	0.014 J	0.025 J	0.011 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	0.013 J	0.017 J	0.0069 J	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	0.014 J	0.035 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.0093 U	< 0.0090 UT	< 0.0068 U	< 0.01 UT	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 UT	< 0.014 U	< 0.016 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	1.1	1.6	0.55 T	0.83	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 UT
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	4.9	7	2.4 T	3.8	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 UT
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	0.66	0.91	0.3 T	0.53	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	0.38	0.57	0.19 T	0.26 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	0.012 J	0.017 J	0.01 JT	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.0093 U	0.0096 J	0.0072 JT	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 UT	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 UT	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 UT
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	0.13	0.2	0.072 T	0.099 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	0.078 T	0.11 T	0.046 T	0.053 JT	< 0.031 UT	< 0.014 U	< 0.0072 U	< 0.021 UT	< 0.016 UT	< 0.019 UT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.0093 U	< 0.0090 UT	< 0.0069 U	< 0.01 UT	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 UT	< 0.014 U	< 0.016 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.0097 U	< 0.0094 UT	< 0.0072 U	< 0.011 UT	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 UT	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	0.054	0.08	0.026 J	0.041 J	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	0.088	0.14	0.051	0.073 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	0.088	0.14	0.07	0.083 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	0.063	0.099	0.032 J	0.05 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	0.034 J	0.052	0.017 J	0.025 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	0.052	0.069	0.033 J	0.033 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	0.028 J	0.044	0.015 J	0.023 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	0.4	0.52	0.22	0.23 J	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	0.93	1.5	0.57	0.58	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.0097 U	0.015 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	0.023 J	0.036 J	0.014 J	0.017 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 UT	< 0.017 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.0093 U	0.012 J	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.02 U	< 0.019 U	< 0.015 U	< 0.022 U	< 0.058 U	< 0.026 U	< 0.014 U	< 0.04 U	< 0.03 UT	< 0.035 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.0098 U	0.012 J	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 UT	< 0.017 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.0094 U	0.01 J	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	0.012 J	0.016 J	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 UT	< 0.019 U

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.072 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.015 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.055 U	0.029 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.037 J	< 0.015 U	0.076 J
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.036 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0069 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.014 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.019 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.055 U	0.051 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 UT	1.3	0.26	0.025 J
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.056 U	0.19 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 UT	5.6	1.2	0.067 J
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.055 U	0.028 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 UT	0.7	0.16	0.021 J
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 UT	0.4	0.075	0.012 J
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 UT	0.023 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 UT	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 UT	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 UT	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 UT	0.16 J	0.028 J	< 0.012 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.062 U	< 0.015 UT	< 0.071 U	< 0.022 UT	< 0.018 UT	< 0.014 UT	< 0.014 UT	0.092 JT	< 0.017 UT	< 0.013 UT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.063 U	< 0.016 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.059 J	< 0.018 U	< 0.014 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.098 J	0.023 J	< 0.012 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.095 J	0.033 J	< 0.013 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.076 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.044 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.05 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.032 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.063 U	0.079 J	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.48	0.064	0.022 J
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.06 U	0.088 J	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.85	0.12	0.056 J
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	0.032 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.061 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0099 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.12 UT	< 0.028 U	< 0.13 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.026 U	< 0.013 U	< 0.032 U	< 0.025 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.01 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.0086 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.056 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.012 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.064 UT	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	0.0069 J	< 0.018 U	< 0.014 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 UT	< 0.042 U	< 0.079 U	< 0.013 UT	< 0.018 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 UT	< 0.17 UT
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 UT	< 0.18 UT
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 UT	< 0.17 UT
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.06 U	< 0.025 UT	< 0.013 UT	< 0.047 U	< 0.09 UT	< 0.015 UT	< 0.021 UT	< 0.16 UT	< 0.029 UT	< 0.2 UT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 UT	< 0.042 U	< 0.079 U	< 0.013 UT	< 0.019 U	< 0.14 U	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 UT	< 0.044 U	< 0.083 U	< 0.014 UT	< 0.019 U	< 0.15 U	< 0.026 UT	< 0.18 UT
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.11 U	< 0.048 U	< 0.024 U	< 0.089 U	< 0.17 U	< 0.028 U	< 0.04 U	< 0.3 U	< 0.054 U	< 0.37 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1			100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		0.042 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		0.019 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		0.14 J	0.077 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		0.04 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.039 U		< 0.032 U		0.067 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.04 U		< 0.032 U		0.04 J	0.013 J	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		0.017 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.039 U		< 0.032 U		0.026 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.037 UT		< 0.03 U		< 0.012 UT	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.038 UT		< 0.031 U		1.7	0.029 J	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.039 UT		< 0.031 U		7.9	0.2 J	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.038 UT		< 0.031 U		1	0.034 J	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.037 UT		< 0.03 U		0.57	0.014 J	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.037 UT		< 0.03 U		0.028 J	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.038 UT		< 0.031 U		0.012 J	< 0.01 U	< 0.017 UT	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.038 UT		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.038 UT		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.037 UT		< 0.03 U		0.19 J	< 0.01 U	< 0.017 UT	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.043 UT		< 0.035 U		0.096 JT	< 0.012 UT	< 0.019 UT	< 0.0085 UT	< 0.035 UT	< 0.014 UT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.038 UT		< 0.031 U		< 0.012 UT	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.039 UT		< 0.032 U		< 0.013 UT	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.044 U		< 0.036 U		0.088 J	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.039 U		< 0.032 U		0.11 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.042 U		< 0.034 U		0.1 J	0.013 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.039 U		< 0.032 U		0.089 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.041 U		< 0.034 U		0.054 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.038 U		< 0.031 U		0.072 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.039 U		< 0.032 U		0.042 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.044 U		< 0.035 U		1.2	0.036 J	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.041 U		< 0.034 U		1.4	0.075 J	< 0.018 UT	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.041 U		< 0.033 U		0.059 J	< 0.011 U	< 0.018 UT	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 UT	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 UT	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.038 U		< 0.031 U		0.024 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.08 U		< 0.065 U		< 0.026 U	< 0.022 U	< 0.035 UT	< 0.016 U	< 0.066 U	< 0.026 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.04 U		< 0.032 U		0.015 J	< 0.011 U	< 0.018 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.038 U		< 0.031 U		0.017 J	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 UT	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.041 U		< 0.033 U		0.029 J	< 0.011 U	< 0.018 UT	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 UT	< 0.0087 U	< 0.036 U	< 0.014 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	< 0.013 UT	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	0.028 JT	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.023 J	< 0.022 U	0.12 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.038 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.037 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	0.022 J	0.056 J		< 0.1 U	0.2 J	0.12 J	2.8	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	0.054	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	0.061	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	0.014 J	< 0.023 U	0.023 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	1 T	< 0.013 U		< 0.1 U	0.084 J	< 0.022 U	0.12 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	4.5 T	< 0.013 U		< 0.1 U	0.097 J	< 0.022 U	0.15 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	0.6 T	< 0.013 U		< 0.1 U	0.065 J	< 0.022 U	0.12 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.099 U	0.051 J		< 0.099 U	0.051 J	< 0.021 U	0.085 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.013 UT	< 0.013 U		< 0.099 U	0.02 J	< 0.021 U	0.011 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	0.026 J	< 0.022 U	0.021 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	0.12 T	< 0.013 U		< 0.1 U	0.01 J	< 0.022 U	0.013 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	0.07 T	< 0.015 UT		< 0.11 UT	0.035 J	< 0.025 U	< 0.0069 UT	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.014 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	0.047	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.0099 J	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	0.084	< 0.014 U		< 0.1 U	0.032 J	< 0.023 U	0.031 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	0.092	< 0.014 U		< 0.11 U	0.023 J	< 0.024 U	0.021 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	0.059	< 0.014 U		< 0.1 U	0.029 J	< 0.023 U	0.026 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	0.029 J	< 0.014 U		< 0.11 U	0.013 J	< 0.024 U	0.012 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	0.041	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0086 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	0.29	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.015 J	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	0.75	< 0.014 U		< 0.11 U	0.1 J	< 0.024 U	0.11 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	0.021 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.017 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.029 U	< 0.028 U		< 0.22 U	< 0.021 U	< 0.047 U	< 0.013 U	< 0.057 U	< 0.18 U	< 0.086 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	< 0.0071 U	< 0.031 U	< 0.097 U	< 0.047 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.043 J	< 0.013 U	0.069 J
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.017 J
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.24 J	0.2 J	0.097 J
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.016 J	< 0.013 U	0.041 J
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.036 J	< 0.013 U	0.059 J
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	0.01 J
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.04 J	< 0.014 U	0.036 J
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0083 J	< 0.013 U	0.015 J
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.011 J	< 0.013 U	0.027 J
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.019 U	< 0.035 UT	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.52	< 0.013 U	1.9
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	3	< 0.013 U	9.1
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.47	< 0.013 U	1.1
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.18 J	< 0.013 U	0.59
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.025 J	< 0.013 U	0.026 J
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.025 J	< 0.013 U	0.012 J
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.063 J	< 0.013 U	0.2 J
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.022 U	< 0.04 UT	< 0.065 UT		< 0.029 UT	< 0.033 UT	< 0.081 U	0.044 JT	< 0.015 UT	0.12 JT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.019 U	< 0.035 UT	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.02 U	< 0.037 UT	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.033 U	< 0.083 U	0.036 J	< 0.015 U	0.087 J
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.046 J	< 0.013 U	0.12 J
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.046 J	< 0.014 U	0.11 J
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.043 J	< 0.013 U	0.098 J
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.044 J	< 0.014 U	0.052 J
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.026 J	< 0.013 U	0.068 J
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.023 J	< 0.013 U	0.044 J
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.61	< 0.015 U	0.99
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.7	< 0.014 U	1.5
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.013 J
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	0.01 J
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.034 J	< 0.014 U	0.036 J
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.014 J	< 0.013 U	0.016 J
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.041 U	< 0.075 U	< 0.12 U		< 0.054 U	< 0.061 U	< 0.15 U	< 0.013 U	< 0.027 U	< 0.019 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.0096 J	< 0.014 U	0.012 J
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.013 J
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.02 J	< 0.014 U	0.021 J
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 U	< 0.0072 U	< 0.015 U	< 0.01 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated		< 0.011 U	< 0.024 UT	< 0.035 U	< 0.045 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 U	< 0.046 UT
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.037 U	< 0.046 UT
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 U	< 0.045 UT
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated		< 0.011 UT	< 0.023 UT	< 0.035 U	< 0.044 UT
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated		< 0.011 UT	< 0.023 UT	< 0.035 U	< 0.044 UT
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 U	< 0.045 UT
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 U	< 0.045 UT
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 U	< 0.045 UT
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.035 U	< 0.045 UT
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated		< 0.012 UT	< 0.027 UT	< 0.04 UT	< 0.051 UT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated		< 0.011 U	< 0.024 UT	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated		< 0.011 U	< 0.025 UT	< 0.037 U	< 0.047 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated		< 0.013 U	< 0.028 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated		< 0.023 U	< 0.051 U	< 0.076 U	< 0.096 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated			0.221	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.023 J
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated			0.0313	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated			16.783	0.019 J	0.22 J	< 0.019 U	0.37 J	< 0.023 U	0.027 J	< 0.065 U	1.8
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated			0.1589	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.021 J
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated			0.504	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	0.049
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated			0.641	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	0.065
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated			0.665	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.071 U	0.061
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated			0.2	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.033 J
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated			0.0797	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.018 J
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated			1.041	< 0.011 U	0.044 J	< 0.018 U	0.015 J	< 0.022 U	0.037 J	< 0.062 U	0.034 J
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated			2.729	< 0.011 U	0.053 J	< 0.019 U	0.025 J	< 0.023 U	< 0.014 U	< 0.065 U	0.25
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated			25.153	0.019 J	0.3 J	< 0.019 U	0.54	< 0.023 U	0.025 J	< 0.065 U	2.6
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated			0.963	0.014 J	0.019 J	< 0.019 U	0.032 J	< 0.023 U	< 0.013 U	< 0.064 U	0.09
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated			16.193	0.083 J	0.5	< 0.019 U	0.39	< 0.023 U	0.027 J	< 0.064 U	1.6
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated			57.62	1.4	0.22 J	< 0.018 U	3.3	< 0.022 U	0.18 J	< 0.062 U	4.7
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated			4.015	0.017 J	0.15 J	< 0.018 U	0.087 J	< 0.022 U	< 0.013 U	< 0.061 U	0.38
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated			6.681	0.12 J	0.088 J	< 0.019 U	0.28 J	< 0.023 U	0.018 J	< 0.064 U	0.59
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated			0.2242	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.031 J
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated			0.1188	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.02 J
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated			2.345	< 0.011 U	0.035 J	< 0.019 U	0.026 J	< 0.023 U	0.045 J	< 0.064 U	0.19
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated			0.379	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.026 U	< 0.015 U	< 0.072 U	0.036 J
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated			7.425	< 0.011 U	0.11 J	< 0.019 U	0.12 J	< 0.023 U	< 0.014 U	< 0.065 U	0.72
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated			0.332	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.039
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated			0.784	< 0.011 U	0.035 J	< 0.019 U	0.016 J	< 0.022 U	< 0.013 U	< 0.063 U	0.077
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated			0.364	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.044
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated			2.683	0.047 J	0.015 J	< 0.017 U	0.11 J	< 0.021 U	< 0.012 U	< 0.059 U	0.24
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated			0.499	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.051
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated			1.615	0.011 J	0.023 J	< 0.019 U	0.04 J	< 0.022 U	< 0.013 U	< 0.062 U	0.15
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated			1.231	< 0.0097 U	0.022 J	< 0.017 U	0.02 J	< 0.02 U	< 0.012 U	< 0.056 U	0.1
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated			1.139	< 0.011 U	0.018 J	< 0.02 U	0.023 J	< 0.024 U	< 0.014 U	< 0.066 U	0.12
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated			0.017	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated			0.187	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated			0.372	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.04 J
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated			0.065	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated			23.425	0.065 J	1	< 0.28 U	0.77	< 0.35 U	< 0.29 U	< 0.098 U	1.8
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated			0.245	< 0.022 U	0.09	< 0.13 U	0.043 J	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated			70.14	0.2 J	4	< 0.4 U	2.3	< 0.49 U	< 0.41 U	< 0.14 U	6.7
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated			6.976	< 0.022 U	0.15	< 0.14 U	0.23	< 0.17 U	< 0.14 U	< 0.048 U	0.74
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated			2.703	< 0.023 U	0.13	< 0.14 U	0.076 J	< 0.17 U	< 0.15 U	< 0.049 U	0.23
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated			1.774	< 0.021 U	0.058 J	< 0.13 U	0.031 J	< 0.16 U	< 0.14 U	< 0.046 U	0.18
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated			22.673	0.043 J	0.54	< 0.13 U	0.85	< 0.17 U	< 0.14 U	< 0.047 U	2.1
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated			2.498	< 0.023 U	0.2	< 0.14 U	0.11	< 0.18 U	< 0.15 U	< 0.05 U	0.22
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated			36.112	0.092	1.5	< 0.13 U	1.1	< 0.16 U	< 0.13 U	< 0.045 U	3.7
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated			81.01	0.31	2.8	< 0.29 U	4.1	< 0.36 U	< 0.3 U	< 0.1 U	6.4
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated			2.263	< 0.022 U	0.084	< 0.13 U	0.069 J	< 0.16 U	< 0.14 U	< 0.047 U	0.22
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated			ND	< 0.021 U	0.019 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated			ND	< 0.021 U	0.017 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated			0.146	< 0.021 U	0.044 J	< 0.13 U	0.027 J	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated			0.045	< 0.024 U	0.063 J	< 0.15 U	0.028 J	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated			0.094	< 0.021 U	0.042 J	< 0.13 U	0.021 J	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated			0.822	< 0.021 U	0.081	< 0.13 U	0.04 J	< 0.16 U	< 0.14 U	< 0.046 UT	0.05 J
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated			0.714	< 0.021 U	0.048 J	< 0.13 U	0.035 J	< 0.16 U	< 0.13 U	< 0.046 U	0.064 J
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated			0.069	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated			0.119	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U

												Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100						
Restricted - Residential												1	1	3.9	100						
Protection of Groundwater												22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	0.018 J	0.029 J	0.01 J	0.012 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.011 U	0.011 J	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	1.5	1.9	0.69	0.76	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 UT	< 0.018 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	0.015 J	0.029 J	0.0089 J	0.013 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	0.042	0.07	0.023 J	0.029 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	0.062	0.11	0.031 J	0.039 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	0.059	0.083	0.031 J	0.039 J	< 0.033 U	< 0.015 U	< 0.0078 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	0.018 J	0.02 J	0.011 J	0.011 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.01 U	0.012 J	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	0.014 J	0.042	0.012 J	0.019 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	0.16	0.27	0.12	0.13 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	2.4	2.9	1.4	1.5	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	0.068	0.11	0.051	0.035 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	1.4	2.1	0.73	0.98	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	3.7	4.7	2	1.8	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	0.36	0.54	0.18	0.28 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	0.49	0.64	0.27	0.28 J	< 0.03 U	< 0.014 U	< 0.0070 U	0.025 J	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	0.02 J	0.033 J	0.011 J	0.013 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	0.011 J	0.016 J	0.0078 J	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	0.17	0.26	0.095	0.089 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	0.026 J	0.049	0.019 J	0.027 J	< 0.034 U	< 0.015 U	< 0.0079 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	0.72	0.87	0.36	0.46	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	0.031 J	0.041	0.015 J	0.022 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	0.073	0.11	0.048	0.056 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	0.036 J	0.046	0.017 J	0.023 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.2	0.25	0.1	0.11 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	0.045	0.068	0.025 J	0.031 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	0.14	0.18	0.091	0.086 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	0.11	0.16	0.056	0.09 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.1	0.14	0.056	0.063 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	0.05 J	0.063 J	0.024 J	0.038 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.033 U	0.022 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	2.2	2.6	0.73	2.8	< 0.29 U	< 0.029 U	< 0.059 U	< 0.84 U	< 0.34 U	< 0.54 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	0.16	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	7.5	10	3.4	5.7	< 0.41 U	< 0.041 U	< 0.084 U	< 1.2 U	< 0.48 U	< 0.78 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	0.64	0.74	0.31	0.34	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	0.27	0.3	0.13	0.28	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	0.17	0.22	0.078	0.11	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	1.9	2.1	0.87	1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	0.22	0.37	0.099	0.23	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	3.1	3.5	1.3	1.9	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	6.9	7	2.8	5.4	< 0.3 U	< 0.03 U	< 0.061 U	< 0.87 U	< 0.35 U	< 0.56 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	0.23	0.32	0.092	0.23	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	0.073	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	0.038 J	0.067 J	< 0.022 U	0.13	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	0.066 J	0.1	0.033 J	0.053 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.033 U	0.019 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.031 U	0.031 J	< 0.022 U	0.023 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.026 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.0083 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.018 U	< 0.013 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.061 UT	0.07 J	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	1.4	0.22	0.086 J
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.016 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.045 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.06 J	0.03 J	< 0.013 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.067 U	< 0.016 U	< 0.076 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	0.068 J	0.032 J	< 0.014 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.021 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.011 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	0.6	< 0.013 U	< 0.013 U	0.11 J	< 0.016 U	0.036 J
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.24 J	0.034 J	< 0.013 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.061 U	0.053 J	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	2.1	0.41	0.056 J
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.088 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.061 U	0.12 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	1.5	0.32	0.092 J
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.058 U	1.4	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	3.9	0.62	1.3
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.057 U	0.025 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.38	0.09	0.021 J
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.06 U	0.1 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.52	0.081	0.11 J
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.024 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.059 U	< 0.014 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.013 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	0.067 J	0.029 J	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.23 J	0.033 J	0.055 J
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.068 UT	< 0.017 U	< 0.077 U	< 0.024 U	< 0.02 U	< 0.016 U	< 0.015 U	0.05 J	< 0.019 U	< 0.015 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.061 UT	0.017 J	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.58	0.11	< 0.013 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	3.89 ft		1801492041	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.08 J	0.017 J	< 0.013 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.034 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.055 U	0.047 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.21 J	0.041	0.037 J
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.047 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.059 U	0.015 J	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.14 J	0.028 J	0.013 J
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.12 J	0.025 J	< 0.011 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.019 U	< 0.014 U	< 0.014 U	0.11 J	0.022 J	< 0.013 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.046 J	< 0.05 U	< 0.14 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.042 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.52 U	0.17	< 0.21 U	< 0.28 U	< 0.036 U	< 0.29 U	< 0.26 U	1.8	0.52	< 0.29 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.74 U	0.37	< 0.3 U	< 0.4 U	< 0.052 U	< 0.42 U	< 0.38 U	7.1	1.4	< 0.42 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.25 U	0.078	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.65	0.11	< 0.14 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.26 U	0.031 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.25	0.095	< 0.15 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.21	< 0.048 U	< 0.14 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.25 U	0.24	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.8	0.3	0.21 J
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.26 U	0.019 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.24	0.055 J	< 0.15 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.24 U	0.082	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	3.4	0.54	< 0.13 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.53 U	0.72	< 0.22 U	< 0.29 U	< 0.038 U	< 0.3 U	< 0.27 U	9.6	1.2	0.91
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.23	< 0.048 U	< 0.14 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.24 U	0.017 J	< 0.097 UT	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.091	< 0.047 U	< 0.14 U
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	RS-B0T47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.081	< 0.047 U	< 0.14 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 UT	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.065 U	< 0.028 U	< 0.014 U	< 0.051 U	< 0.098 U	< 0.016 U	< 0.023 U	< 0.18 U	< 0.031 U	< 0.21 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.021 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	0.018 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 UT
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.74 U	< 0.061 U	< 0.28 U	< 0.27 U	< 0.31 U	< 0.35 U	< 0.46 U	< 1.4 U	< 0.31 U	< 4.9 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 1.1 U	< 0.087 U	< 0.4 U	< 0.38 U	< 0.45 U	< 0.49 U	< 0.66 U	< 1.9 U	< 0.44 U	< 7 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.77 U	< 0.063 U	< 0.29 U	< 0.28 U	< 0.32 U	< 0.36 U	< 0.48 U	< 1.4 U	< 0.32 U	< 5.1 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.35 UT	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	RS-B0T47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.039 U		< 0.032 U		0.038 J	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.044 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.042 U		< 0.034 U		3.3	0.094 J	< 0.019 UT	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.043 U		< 0.035 U		0.018 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.042 U		< 0.034 U		0.082 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.042 U		< 0.034 U		0.081 J	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.046 U		< 0.038 U		0.098 J	< 0.013 U	< 0.02 U	< 0.0091 U	< 0.038 U	< 0.015 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.04 U		< 0.032 U		0.035 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.041 U		< 0.033 U		0.015 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.04 U		< 0.033 U		0.08 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.043 U		< 0.035 U		0.5	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.042 U		< 0.034 U		4.1	0.054 J	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.041 U		< 0.034 U		0.15 J	0.015 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.042 U		< 0.034 U		2.1	0.13 J	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.04 U		< 0.033 U		8.4	1.7	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.04 U		< 0.032 U		0.48	0.027 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.042 U		< 0.034 U		0.94	0.14 J	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.042 U		< 0.034 U		0.033 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.041 U		< 0.033 U		0.021 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.041 U		< 0.034 U		0.31 J	0.032 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.047 U		< 0.038 U		0.044 J	< 0.013 U	< 0.021 U	< 0.0093 U	< 0.038 U	< 0.015 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.042 U		< 0.034 U		1.2	0.028 J	< 0.019 U	< 0.0084 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	< 0.04 U		< 0.033 U		0.05 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	< 0.041 U		< 0.033 U		0.092 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	< 0.041 U		< 0.033 U		0.055 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.038 U		< 0.031 U		0.39	0.052 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.038 U		< 0.031 U		0.061 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.041 U		< 0.033 U		0.22 J	0.016 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.037 U		< 0.03 U		0.16 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.043 U		< 0.035 U		0.15 J	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.23 U	< 0.12 U			0.044 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.22 U	< 0.11 U			0.047 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.23 U	< 0.12 U			0.022 J	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.47 U	< 0.25 U			2.2	0.14 J	< 0.057 U	< 0.046 U	< 0.081 U	< 0.28 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.67 U	< 0.35 U			7.4	0.34	< 0.081 U	< 0.066 U	< 0.12 U	< 0.4 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.23 U	< 0.12 U			1.1	0.038 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.24 U	< 0.12 U			0.33	0.022 J	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.22 U	< 0.12 U			0.22	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.23 U	< 0.12 U			3.8	0.15	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.24 U	< 0.12 U			0.25	0.018 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.22 U	< 0.11 U			5.5	0.25	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.49 U	< 0.26 U			12	1.1	< 0.059 U	< 0.048 U	< 0.084 U	< 0.29 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.22 U	< 0.12 U			0.22	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.21 U	< 0.11 U			0.036 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.22 U	< 0.12 U			0.063 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.22 U	< 0.12 U			0.098	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.22 U	< 0.12 U			0.027 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.22 U	< 0.11 U			0.031 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	0.016 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	1	< 0.015 U		< 0.11 U	0.074 J	< 0.025 U	0.23 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	0.017 JT	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.014 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	0.039 T	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	0.051 T	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	0.05 T	< 0.016 U		< 0.12 U	< 0.012 U	< 0.027 U	< 0.0074 U	< 0.033 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	0.015 J	< 0.014 U		< 0.11 U	0.11 J	< 0.023 U	0.41	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	0.16	< 0.015 U		< 0.11 U	< 0.011 U	0.03 J	< 0.0068 U	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	1.8	< 0.015 U		< 0.11 U	0.085 J	< 0.025 U	0.43	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	0.051	< 0.014 U		< 0.11 U	0.012 J	< 0.024 U	0.021 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	1.2	< 0.015 U		< 0.11 U	0.17 J	< 0.024 U	0.21 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	0.045 J	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	2.5	0.025 J		< 0.11 U	0.72	0.078 J	1.5	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	0.33	< 0.014 U		< 0.11 U	0.049 J	< 0.023 U	0.054 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	0.37	< 0.014 U		< 0.11 U	0.086 J	0.13 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	0.046 J	0.0072 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	0.11	< 0.014 U		< 0.11 U	0.31 J	< 0.024 U	0.21 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	0.055	< 0.016 U		< 0.13 U	< 0.012 U	< 0.027 U	< 0.0075 U	< 0.033 U	< 0.1 U	< 0.05 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	0.58	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	0.067 J	< 0.03 U	< 0.093 U	< 0.045 UT
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 UT
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	0.071	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 UT
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	0.029 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 UT
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.14	< 0.013 U		< 0.1 U	0.028 J	< 0.022 U	0.043 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	0.036	< 0.013 U		< 0.1 U	0.01 J	< 0.022 U	0.014 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	0.1	< 0.014 U		< 0.11 U	0.024 J	< 0.024 U	0.043 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	0.097	< 0.013 U		< 0.099 U	0.018 J	0.032 J	0.033 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.08	< 0.015 U		< 0.12 U	0.013 J	< 0.025 U	0.014 J	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	0.024 J	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	0.29 J	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	2	< 0.23 U		< 0.3 U	0.4	< 0.23 U	1.5	< 0.36 U	< 0.2 U	< 0.29 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	0.042 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	4.8	< 0.32 U		< 0.42 U	0.7	< 0.33 U	1	< 0.52 U	< 0.29 U	< 0.42 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	0.31	< 0.11 U		< 0.15 U	0.13	< 0.11 U	0.068 J	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	0.18	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	0.091	< 0.11 U		< 0.14 U	0.12	< 0.11 U	0.064 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	1	< 0.11 U		< 0.14 U	0.074 J	< 0.11 U	0.16	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	0.2	< 0.11 U		< 0.15 U	0.034 J	< 0.12 U	0.052 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	1.7	< 0.1 U		< 0.14 U	0.2	< 0.11 U	0.43	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	4.6	< 0.24 U		< 0.31 U	0.7	< 0.24 U	2.1	< 0.37 U	< 0.21 U	< 0.31 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	0.18	< 0.11 U		< 0.14 U	0.029 J	< 0.11 U	0.042 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	0.017 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	0.039 J	< 0.11 U		< 0.14 U	0.089	< 0.11 U	0.15	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	0.045 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	0.11 J	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.023 J	< 0.013 U	0.026 J
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	0.012 J
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.022 U	< 0.041 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	1.4	0.015 J	2.3
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.022 U	< 0.04 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	< 0.0069 U	< 0.015 U	0.021 J
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.045 J	< 0.014 U	0.08 J
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.022 J	< 0.014 U	0.09 J
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.035 U	< 0.088 U	0.046 J	< 0.016 U	0.098 J
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.019 J	< 0.014 U	0.032 J
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.0097 J	< 0.014 U	0.014 J
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.21 J	< 0.014 U	0.08 J
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.022 U	< 0.04 U	< 0.064 U		< 0.029 U	< 0.033 U	< 0.081 U	0.35 J	< 0.015 U	0.49
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	1	< 0.014 U	3.9
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.098 J	< 0.014 U	0.14 J
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.95	< 0.014 U	2.5
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	< 0.0069 U	< 0.014 U	< 0.0098 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	10	0.036 J	7.4
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.23 J	< 0.014 U	0.58
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.87	< 0.014 U	0.96
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.019 J	< 0.014 U	0.033 J
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.012 J	< 0.014 U	0.018 J
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0091 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.35 J	< 0.014 U	0.24 J
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.024 U	< 0.044 U	< 0.071 U		< 0.032 U	< 0.036 U	< 0.089 U	0.03 J	< 0.016 U	0.043 J
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.41	< 0.014 U	1.2
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.029 J	< 0.014 U	0.05 J
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.034 J	< 0.014 U	0.11 J
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.025 J	< 0.014 U	0.055 J
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.36	< 0.013 U	0.39
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.04 J	< 0.013 U	0.081 J
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.13 J	< 0.014 U	0.24 J
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.08 J	< 0.013 U	0.18 J
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.091 J	< 0.015 U	0.17 J
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.017 J
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.061 J	< 0.12 U	0.036 J
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.022 J	< 0.11 U	0.046 J
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.021 J
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.29 U	< 0.29 U	< 0.56 U		< 0.054 U	< 0.26 U	< 1.3 U	1.3	< 0.24 U	3
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.41 U	< 0.42 U	< 0.79 U		< 0.077 U	< 0.38 U	< 1.8 U	2.3	< 0.34 U	10
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.7	< 0.12 U	1
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.18	< 0.12 U	0.36
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.16	< 0.11 U	0.24
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	3	< 0.11 U	3.6
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.094	< 0.12 U	0.34
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	2.4	< 0.11 U	7.2
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.3 U	< 0.3 U	< 0.58 U		< 0.056 U	< 0.27 U	< 1.3 U	9.5	< 0.25 U	12
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.11	< 0.11 U	0.32
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.02 J	< 0.11 U	0.063 J
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.065 J	< 0.11 U	0.089
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.029 J	< 0.11 U	0.11
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.023 J
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.034 J
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated		< 0.013 U	< 0.029 U	< 0.044 U	< 0.055 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated		0.92	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated		< 0.014 U	< 0.03 U	< 0.044 U	< 0.056 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated		< 0.31 U	< 0.33 U	< 0.28 U	< 0.26 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated		< 0.45 U	< 0.47 U	< 0.39 U	< 0.38 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated		< 0.32 U	< 0.34 U	< 0.29 U	< 0.27 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-B0T47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.053 U	< 0.038 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated			0.725	< 0.022 U	0.028 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.08
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated			0.025	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated			0.138	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated			0.101	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated			0.202	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.04 J
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated			1.247	< 0.021 U	0.016 J	< 0.13 U	0.024 J	< 0.16 U	< 0.14 U	< 0.046 U	0.12
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated			1.186	< 0.025 U	< 0.019 U	< 0.16 U	< 0.023 U	< 0.19 U	< 0.16 U	< 0.055 U	0.1
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated			0.017	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated			4.654	0.043 J	0.092	< 0.13 U	0.16	< 0.16 U	< 0.13 U	< 0.046 U	0.37
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated			ND	< 0.02 U	0.028 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 UT	< 0.033 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated			0.082	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated			1.154	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.077
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated			14.091	0.028 J	0.57	< 0.13 U	0.35	< 0.16 U	< 0.14 U	< 0.046 U	1.2
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated			6.099	< 0.022 U	0.15	< 0.14 U	0.15	< 0.17 U	< 0.14 U	< 0.048 U	0.43
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated			0.971	< 0.021 U	0.026 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.055 J
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated			10.911	< 0.026 U	0.47	< 0.16 U	0.27	< 0.2 U	< 0.17 U	< 0.057 U	0.77
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated			2.502	< 0.023 U	0.065 J	< 0.14 U	0.042 J	< 0.17 U	< 0.15 U	< 0.049 U	0.2
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated			6.103	0.024 J	0.14	< 0.15 U	0.086	< 0.19 U	< 0.16 U	< 0.053 U	0.46
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated			1.268	< 0.021 U	0.034 J	< 0.13 U	0.025 J	< 0.16 U	< 0.13 U	< 0.045 U	0.099
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated			2.964	< 0.023 U	0.088	< 0.14 U	0.047 J	< 0.17 U	< 0.14 U	< 0.049 U	0.26
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated			2.785	< 0.022 U	0.079	< 0.14 U	0.05 J	< 0.17 U	< 0.14 U	< 0.047 U	0.25
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated			3.611	< 0.021 U	0.11	< 0.13 U	0.064 J	< 0.16 U	< 0.13 U	< 0.045 U	0.33
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated			9.448	< 0.02 U	0.38	< 0.13 U	0.25	< 0.16 U	< 0.13 U	< 0.044 U	0.83
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated			0.132	< 0.021 U	0.016 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated			0.488	< 0.02 U	0.017 J	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	0.05 J
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated			42.432	0.082 J	1.7	< 0.26 U	1.1	< 0.32 U	< 0.27 U	< 0.092 UT	4
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated			0.924	< 0.021 U	0.02 J	< 0.13 U	0.023 J	< 0.16 U	< 0.13 U	< 0.045 U	0.068 J
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated			0.101	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated			1.179	< 0.02 U	0.071	< 0.13 U	0.028 J	< 0.15 U	< 0.13 U	< 0.044 UT	0.091
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.14 U	< 0.046 UT	< 0.034 UT
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated			0.184	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated			0.738	< 0.023 U	0.051 J	< 0.14 U	0.027 J	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated			2.291	< 0.021 U	0.11	< 0.13 U	0.059 J	< 0.16 U	< 0.13 U	< 0.045 U	0.14
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated			0.02	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated			13.542	< 0.024 U	0.74	< 0.15 U	0.36	< 0.18 U	< 0.15 U	< 0.052 U	1.2
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated			5.633	< 0.021 U	0.083	< 0.13 U	0.096	< 0.16 UT	< 0.13 U	< 0.045 UT	0.58
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated			4.519	< 0.021 U	0.36	< 0.13 U	0.15	< 0.16 U	< 0.13 U	< 0.045 U	0.3

												Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**	**Butylbenzyl phthalate**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100						
Restricted - Residential												1	1	3.9	100						
Protection of Groundwater												22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	0.074 J	0.093	0.057 J	0.052 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.032 U	0.03 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.033 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.033 U	0.03 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.03 U	0.027 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	0.12	0.17	0.051 J	0.068 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	0.096	0.13	0.057 J	0.071 J	< 0.16 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.19 U	< 0.3 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	0.46	0.49	0.12	0.44	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 UT	< 0.15 U	< 0.25 UT
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	< 0.031 U	0.019 J	< 0.021 U	0.022 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	0.1	0.13	0.063 J	0.088	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	1.4	2	0.53	1.4	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	0.47	0.67	0.24	0.38	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	0.05 J	0.082	< 0.022 U	0.045 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	1.2	1.5	0.62	1.2	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.19 U	< 0.31 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	0.2	0.31	0.1	0.18	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	0.53	0.7	0.25	0.4	< 0.16 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	0.11	0.16	0.052 J	0.097	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	0.27	0.39	0.14	0.24	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	0.26	0.34	0.13	0.24	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	0.35	0.46	0.18	0.32	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	0.97	1.2	0.47	0.97	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.031 U	0.04 J	< 0.022 U	0.029 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	0.058 J	0.058 J	0.037 J	0.061 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	4.1	4.8	1.5	4	< 0.27 U	< 0.027 U	< 0.055 U	< 0.79 U	< 0.32 U	< 0.51 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	0.058 J	0.065 J	0.031 J	0.052 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.03 U	0.027 J	< 0.021 U	0.022 J	< 0.13 U	< 0.012 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	0.13	0.18	0.059 J	0.12	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	0.2	0.22	0.092	0.38	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	1.1	1.3	0.63	1	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	0.63	0.68	0.34	0.42	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 UT	< 0.15 U	< 0.25 UT
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	0.43	0.43	0.16	0.71	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.055 U	< 0.16 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.089	< 0.049 U	< 0.14 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.041 J	< 0.044 U	< 0.13 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.15	< 0.047 U	< 0.14 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.29 U	< 0.021 U	< 0.12 U	< 0.16 U	< 0.02 U	< 0.16 U	< 0.15 U	0.13	< 0.057 U	< 0.16 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 0.24 U	0.052 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.4	0.15	< 0.14 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.13	< 0.047 U	< 0.13 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.15 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.24 U	0.061 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	1.4	0.35	< 0.14 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.25 U	0.08	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.59	0.098	< 0.14 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.097	< 0.046 U	< 0.13 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.3 U	0.053 J	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	1	0.3	< 0.17 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.26 U	0.019 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.25	< 0.051 U	< 0.15 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.28 U	0.036 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	0.62	0.12	< 0.16 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.14	< 0.047 U	< 0.13 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.32	0.065 J	< 0.15 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.29	0.06 J	< 0.14 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.4	0.078	< 0.13 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.23 U	0.04 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.93	0.24	< 0.13 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.051 J	< 0.044 U	< 0.13 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.48 U	0.18	< 0.19 U	< 0.26 U	< 0.034 U	< 0.27 U	< 0.25 U	4.4	1.1	< 0.27 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.17	< 0.047 U	< 0.13 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.23 UT	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.14	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 UT	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.044 J	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.24 U	0.036 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.16	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.27 U	0.072 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	1.5	0.28	< 0.16 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.57	0.1	< 0.13 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.24 U	0.043 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.34	0.097	< 0.13 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.34 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 UT
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.41 U	< 0.034 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.19 U	< 0.26 U	< 0.76 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 UT	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.39 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 UT
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 UT
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 UT
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.43 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.79 U	< 0.18 U	< 2.8 UT
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 UT
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 UT
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 UT
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 UT
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 UT
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 UT
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 UT
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 UT
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.69 U	< 0.057 U	< 0.26 U	< 0.25 U	< 0.29 U	< 0.32 U	< 0.43 U	< 1.3 U	< 0.29 U	< 4.6 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.33 UT	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 UT
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 UT	< 0.21 UT	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.22 U	< 0.12 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.23 U	< 0.12 U			0.096	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.22 U	< 0.11 U			0.039 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.23 U	< 0.12 U			0.03 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			0.043 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 0.22 U	< 0.12 U			0.19	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.26 U	< 0.14 U			0.19	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.16 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 0.22 U	< 0.11 U			0.59	0.052 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.22 U	< 0.11 U			0.21	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.22 U	< 0.12 U			1.4	0.053 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.23 U	< 0.12 U			0.83	0.041 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.22 U	< 0.11 U			0.058 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.27 U	< 0.14 U			0.74	0.041 J	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.24 U	< 0.12 U			0.26	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.25 U	< 0.13 U			0.71	0.033 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.22 U	< 0.11 U			0.14	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.23 U	< 0.12 U			0.34	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.23 U	< 0.12 U			0.34	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.22 U	< 0.11 U			0.37	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.21 U	< 0.11 U			0.92	0.038 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.22 U	< 0.11 U			0.024 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.21 U	< 0.11 U			0.046 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.44 U	< 0.23 U			4.7	0.19	< 0.053 U	< 0.043 U	< 0.076 U	< 0.26 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.22 U	< 0.11 U			0.079	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.21 U	< 0.11 U			0.027 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.21 U	< 0.11 U			0.13	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.22 UT	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 UT	< 0.038 UT	< 0.13 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.24 U	< 0.12 U			0.055 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.23 U	< 0.12 U			0.064 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.22 U	< 0.11 U			0.21	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.25 U	< 0.13 U			1.9	0.072 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 UT	< 0.13 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.21 U	< 0.11 U			0.76	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 UT	< 0.13 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.22 U	< 0.11 U			0.36	0.042 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.13 U	< 0.017 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	0.074	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	0.053 J	< 0.13 U		< 0.17 U	0.023 J	< 0.13 U	0.019 J	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	0.35	< 0.11 U		< 0.14 U	0.027 J	< 0.11 U	0.049 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.024 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	0.062 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	1.1	< 0.11 U		< 0.14 U	0.12	< 0.11 U	0.17	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	0.33	< 0.11 U		< 0.15 U	0.31	< 0.11 U	0.22	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	0.43	< 0.11 U	0.22	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	0.92	< 0.13 U		< 0.17 U	0.52	< 0.13 U	0.62	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	0.15	< 0.11 U		< 0.15 U	0.35	< 0.12 U	0.22	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	0.36	< 0.12 U		< 0.16 U	0.56	< 0.12 U	0.34	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	0.077	< 0.1 U		< 0.14 U	0.11	< 0.11 U	0.068 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	0.21	< 0.11 U		< 0.15 U	0.074 J	< 0.12 U	0.062 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	0.2	< 0.11 U		< 0.14 U	< 0.018 U	0.64	0.015 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	0.26	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.019 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	0.77	< 0.1 U		< 0.13 U	0.1	< 0.1 U	0.16	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	0.055 J	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	3.3	< 0.21 U		< 0.28 U	0.33	< 0.22 U	0.36	< 0.34 U	< 0.19 U	< 0.28 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	0.056 J	< 0.1 U		< 0.14 U	0.09	< 0.11 U	0.062 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	0.092	< 0.1 U		< 0.13 U	0.02 J	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.037 UT	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	0.27	< 0.12 U	0.49	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	0.21	< 0.11 U		< 0.14 U	0.063 J	< 0.11 U	0.26	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	0.83	< 0.12 U		< 0.16 U	0.31	< 0.12 U	0.27	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	0.36	< 0.1 U		< 0.13 U	0.046 J	< 0.11 U	0.097	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	0.42	< 0.1 U		< 0.14 U	0.13	< 0.11 U	0.41	< 0.17 U	< 0.093 U	< 0.14 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.054 J	< 0.11 U	0.13
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.025 J
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.02 J	< 0.11 U	0.049 J
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.041 J
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	0.051 J
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1802526801	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.1	< 0.11 U	0.18
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1802526801	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.13	< 0.13 U	0.21
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1802526801	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.017 J
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1802526801	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1802526801	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.41	< 0.11 U	0.57
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.017 J
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1802526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.074	< 0.11 U	0.22
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.51	< 0.11 U	2.2
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.55	< 0.12 U	1.1
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.27	< 0.11 U	0.094
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.33	< 0.14 U	1.4
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.24	< 0.12 U	0.35
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.56	< 0.13 U	0.91
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.11	< 0.11 U	0.19
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.15	< 0.12 U	0.47
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.12	< 0.12 U	0.49
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.12	< 0.11 U	0.66
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.3	< 0.11 U	1.4
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.039 J
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.072
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.27 U	< 0.27 U	< 0.52 U		< 0.05 U	< 0.25 U	< 1.2 U	2.1	< 0.22 U	6.7
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.17	< 0.11 U	0.09
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.025 J
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.049 J	< 0.11 U	0.16
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.14 UT	< 0.14 U	< 0.26 U		< 0.025 UT	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.035 J	< 0.12 U	0.05 J
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.088	< 0.12 U	0.069 J
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.1	< 0.11 U	0.26
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.02 J
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.15 U	< 0.16 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.68 U	1.1	< 0.13 U	2
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 UT	< 0.58 U	0.27	< 0.11 U	0.73
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.22	< 0.11 U	0.45

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated		< 0.18 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated		< 0.29 U	< 0.31 U	< 0.26 U	< 0.25 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U

														Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated				8.163	< 0.022 U	0.4	< 0.13 U	0.25	< 0.17 U	< 0.14 U	< 0.047 U	0.65
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated				0.431	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.032 J
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated				ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated				0.675	< 0.026 U	< 0.019 U	< 0.16 U	0.04 J	< 0.19 U	< 0.16 U	< 0.055 U	0.062 J
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated				7.947	0.024 J	0.61	< 0.14 U	0.32	< 0.17 U	< 0.14 U	< 0.047 U	0.65
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated				1.259	< 0.024 U	0.025 J	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.053 U	0.095
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated				0.33	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 UT	< 0.14 U	< 0.047 UT	0.043 J
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated				2.425	< 0.022 U	0.027 J	< 0.14 U	0.034 J	< 0.17 U	< 0.14 U	< 0.047 U	0.25
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated				ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 UT	< 0.035 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 UT	< 0.033 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated				ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated				1.505	< 0.021 U	0.026 J	< 0.13 U	0.027 J	< 0.16 U	< 0.14 U	< 0.046 U	0.15
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated				133.3	2.9	0.19	< 0.14 U	5.4	< 0.17 U	0.19 J	< 0.05 U	10
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated				1.626	< 0.021 U	0.024 J	< 0.13 U	0.025 J	< 0.16 U	< 0.14 U	< 0.046 U	0.18
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated				4.315	< 0.021 U	0.057 J	< 0.13 U	0.12	< 0.16 U	< 0.13 U	< 0.045 U	0.4
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated				2.044	< 0.02 U	0.033 J	< 0.13 U	0.045 J	< 0.15 U	< 0.13 U	< 0.044 U	0.21
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated				0.571	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.064 J
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated				29.513	0.043 J	1.2	< 0.13 U	0.84	< 0.16 U	< 0.13 U	< 0.045 U	2.8
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated				4.587	< 0.022 U	0.075 J	< 0.14 U	0.1	< 0.17 U	< 0.14 U	< 0.048 U	0.51
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated				9.3	< 0.6 U	0.65 J	< 3.7 U	< 0.54 U	< 4.6 U	< 3.8 U	< 1.3 U	1 J
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated				0.085	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated				17.132	0.025 J	0.36	< 0.13 U	0.41	< 0.16 U	< 0.13 U	< 0.045 U	1.9
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated				1.139	< 0.021 U	0.072 J	< 0.13 U	0.039 J	< 0.16 U	< 0.14 U	< 0.046 U	0.083
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated				0.971	< 0.021 U	0.046 J	< 0.13 U	0.039 J	< 0.16 U	< 0.13 U	< 0.046 U	0.082
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated				0.176	< 0.021 U	0.017 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated				ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated				ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated				ND	< 0.02 U	0.016 J	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated				0.91	< 0.02 U	0.054 J	< 0.12 U	0.04 J	< 0.15 U	< 0.13 U	< 0.043 U	0.076
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.14 U	< 0.046 UT	< 0.033 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated				3.4	< 0.55 U	0.43 J	< 3.4 U	< 0.5 U	< 4.2 U	< 3.5 U	< 1.2 U	< 0.86 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated				ND	< 0.02 U	0.05 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated				36.688	0.068 J	1.8	< 0.14 U	0.98	< 0.17 U	< 0.15 U	< 0.049 U	3.9
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated				47.527	0.047 J	1.7	< 0.13 U	1.2	< 0.16 U	< 0.14 U	< 0.047 U	5.1
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated				0.105	< 0.025 U	< 0.019 U	< 0.16 U	< 0.023 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated				ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated				0.031	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated				12.362	0.038 J	0.42	< 0.14 U	0.43	< 0.17 U	< 0.14 U	< 0.049 U	1
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated				3.216	< 0.021 U	0.21	< 0.13 U	0.13	< 0.16 U	< 0.14 U	< 0.046 U	0.26
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	--	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	--	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated				5.48	0.028 J	0.4	< 0.15 U	0.23	< 0.19 U	< 0.16 U	< 0.054 U	0.36
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated				4.57	< 0.02 U	0.26	< 0.12 U	0.17	< 0.15 U	< 0.13 U	< 0.043 U	0.31
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	--	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated				0.381	< 0.022 U	0.019 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated				1.275	< 0.022 U	0.085	< 0.14 U	0.048 J	< 0.17 U	< 0.14 U	< 0.047 U	0.1
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated				0.348	< 0.021 U	0.021 J	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.14 U	< 0.046 UT	0.034 J
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated				6.512	< 0.021 U	0.32	< 0.13 U	0.17	< 0.16 U	< 0.13 U	< 0.045 U	0.5
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated				27.673	0.063 J	1.8	< 0.13 U	1.1	< 0.16 U	< 0.13 U	< 0.045 U	2.3
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated				4.653	0.023 J	0.32	< 0.13 U	0.2	< 0.16 U	< 0.14 U	< 0.046 U	0.34
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated				1.047	< 0.022 U	0.031 J	< 0.14 U	0.024 J	< 0.17 U	< 0.14 U	< 0.047 U	0.068 J
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated				5.272	0.04 J	0.22	< 0.14 U	0.23	< 0.17 U	< 0.14 U	< 0.049 U	0.46
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated				1.276	< 0.021 U	0.073 J	< 0.13 U	0.038 J	< 0.16 U	< 0.14 U	< 0.046 U	0.11
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	--	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				0.326	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	--	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	--	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				0.298	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 UT	< 0.036 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	--	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				0.037	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	--	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				0.622	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.051 J
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	--	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated				3.056	0.049 J	0.025 J	< 0.13 U	0.25	< 0.17 U	< 0.14 U	< 0.047 U	0.043 J
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated				0.02	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated				0.073	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated				0.616	< 0.022 U	< 0.017 U	< 0.13 U	0.028 J	< 0.17 U	< 0.14 U	< 0.047 U	0.042 J
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated				0.069	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	--	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated				ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	--	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated				0.321	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.032 J
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated				0.544	< 0.022 U	< 0.016 U	< 0.13 U	0.062 J	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated				ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated				0.622	< 0.021 U	0.016 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.06 J
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated				0.042	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.14 U	< 0.046 UT	< 0.034 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated				ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	--	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated				0.627	< 0.023 U	0.017 J	< 0.14 U	0.022 J	< 0.17 U	< 0.14 U	< 0.049 U	0.052 J
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated				0.86	< 0.021 U	0.018 J	< 0.13 U	0.11	< 0.16 U	< 0.13 U	< 0.045 U	0.07 J

												Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100						
Restricted - Residential												1	1	3.9	100						
Protection of Groundwater												22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	0.58	0.74	0.34	0.66	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.031 U	0.047 J	< 0.021 U	0.031 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	0.058 J	0.055 J	0.049 J	0.052 J	< 0.16 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.19 U	< 0.3 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	0.69	0.82	0.38	0.76	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	0.097	0.2	0.066 J	0.13	< 0.16 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	0.036 J	0.035 J	0.023 J	0.021 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	0.23	0.25	0.092	0.16	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.033 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	0.15	0.13	0.11	0.11	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	8	8.8	3.4	6.1	< 0.15 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	0.18	0.17	0.08	0.12	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	0.41	0.42	0.18	0.24	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	0.22	0.23	0.099	0.14	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	0.073 J	0.066 J	0.035 J	0.035 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	2.7	3.4	1.3	2.9	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	0.41	0.42	0.22	0.26	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	1.3 J	1.3 J	< 0.63 U	1.4 J	< 3.8 U	< 0.38 U	< 0.77 U	< 11 U	< 4.4 U	< 7.2 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.033 U	0.032 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	1.5	2.4	1.1	0.86	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	0.084	0.088	0.046 J	0.29	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	0.07 J	0.083	0.03 J	0.12	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.031 U	0.025 J	< 0.022 U	0.047 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	0.071	0.082	0.027 J	0.12	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.83 U	0.66 J	< 0.57 U	1.3 J	< 3.5 U	< 0.35 U	< 0.71 U	< 10 U	< 4.1 U	< 6.6 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	3.9	4.7	1.6	3	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	4.9	5.7	2.2	3.3	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.038 U	0.024 J	< 0.026 U	0.022 J	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.19 U	< 0.3 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	1.1	1.1	0.45	1.2	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.31	0.39	0.12	0.33	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	0.44	0.62	0.24	0.57	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	0.36	0.5	0.17	0.4	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.034 U	0.038 J	< 0.023 U	0.046 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	0.13	0.16	0.062 J	0.15	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	0.041 J	0.049 J	0.026 J	0.041 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.61	0.8	0.3	0.58	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	2.7	3	1.1	2.8	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	0.38	0.53	0.14	0.43	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	0.095	0.11	0.042 J	0.13	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	0.44	0.54	0.19	0.38	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	0.12	0.16	0.062 J	0.1	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.035 U	0.038 J	< 0.024 U	0.035 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.034 U	0.022 J	< 0.024 U	< 0.017 UT	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	0.058 J	0.055 J	0.037 J	0.035 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.033 U	0.058 J	0.028 J	0.024 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.034 U	0.022 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	0.05 J	0.05 J	0.03 J	0.037 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.031 U	0.02 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	0.032 J	0.037 J	0.029 J	0.02 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	0.039 J	0.045 J	0.022 J	0.041 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	0.058 J	0.076	0.043 J	0.045 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.032 U	0.023 J	< 0.022 U	< 0.016 UT	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.05 J	0.086	0.041 J	0.054 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	0.064 J	0.07 J	0.048 J	0.047 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.25 U	0.071 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.91	0.15	< 0.14 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.084	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.29 U	0.037 J	< 0.12 U	< 0.16 U	< 0.02 U	< 0.16 U	< 0.15 U	0.079 J	< 0.057 U	< 0.16 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.25 U	0.048 J	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.81	0.18	< 0.14 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	0.16	< 0.054 U	< 0.16 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 UT	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.042 J	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.25 U	0.021 J	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.27	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.13	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.26 U	2.4	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	8.6	2.5	1.6
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.17	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.24 U	0.027 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.38	0.051 J	< 0.14 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.2	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.062 J	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.24 U	0.17	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	3.3	0.73	< 0.13 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.25 U	0.027 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.51	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 6.8 U	< 0.49 U	< 2.7 U	< 3.7 U	< 0.48 U	< 3.8 U	< 3.5 U	< 1.2 U	< 1.3 U	< 3.8 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.24 U	0.16	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	2.1	0.28	< 0.13 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.08	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.24 U	0.017 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.072 J	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.068 J	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 6.2 U	< 0.45 U	< 2.5 U	< 3.4 U	< 0.44 U	< 3.5 U	< 3.2 U	< 1.1 U	< 1.2 U	< 3.5 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.26 U	0.18	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	3.8	0.78	< 0.15 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.25 U	0.22	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	4.8	0.83	< 0.14 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	< 0.048 U	< 0.056 U	< 0.16 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.26 U	0.09	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.96	0.22	< 0.14 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.24 U	0.025 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.34	0.071 J	< 0.14 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.28 U	0.063 J	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.58	0.13	< 0.16 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.22 U	0.044 J	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.55	0.11	< 0.13 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.062 J	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.14	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.042 J	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.23 U	0.04 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.64	0.15	< 0.13 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.23 U	0.15	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	3	0.72	0.17 J
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.24 U	0.046 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.56	0.1	< 0.14 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.12	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.26 U	0.059 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.54	0.11	< 0.14 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.14	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.063 J	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.046 J	< 0.051 UT	< 0.15 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.062 J	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.085	< 0.048 U	0.19 J
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.056 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.04 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.047 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.075	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 UT	< 0.14 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.082	< 0.05 U	< 0.15 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.17	< 0.047 U	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 UT	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 UT	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.41 U	< 0.034 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.19 U	< 0.26 UT	< 0.76 U	< 0.17 U	< 2.8 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 UT	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 UT	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 UT	< 0.65 UT	< 0.15 U	< 2.4 UT
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 UT	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 UT	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 UT	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 UT	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 9.7 U	< 0.8 U	< 3.7 U	< 3.5 U	< 4.1 U	< 4.6 U	< 6.1 U	< 18 U	< 4.1 U	< 65 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 8.9 U	< 0.74 U	< 3.4 U	< 3.2 U	< 3.8 U	< 4.2 U	< 5.6 U	< 17 U	< 3.7 U	< 59 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.41 U	< 0.033 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.34 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 UT	< 0.15 U	< 2.5 UT
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.23 U	< 0.12 U			1	0.063 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.21 U	< 0.11 U			0.042 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.26 U	< 0.14 U			0.07 J	0.027 J	< 0.032 U	< 0.026 U	< 0.045 U	< 0.16 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.23 U	< 0.12 U			0.75	0.043 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.25 U	< 0.13 U			0.18	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.23 U	< 0.12 U			0.053 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 UT	< 0.13 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.23 U	< 0.12 U			0.43	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.22 U	< 0.12 U			0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.24 U	< 0.12 U			24	2.5	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.22 U	< 0.12 U			0.27	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.22 U	< 0.11 U			0.73	0.02 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.21 U	< 0.11 U			0.31	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.23 U	< 0.12 U			0.096	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.22 U	< 0.11 U			3.3	0.11	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.23 U	< 0.12 U			0.81	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 6.2 U	< 3.3 U			1.7 J	< 0.41 U	< 0.75 U	< 0.61 U	< 1.1 U	< 3.7 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.23 U	< 0.12 U			0.025 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.22 U	< 0.11 U			2.5	0.037 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			0.094	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.22 U	< 0.11 U			0.15	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.22 U	< 0.11 U			0.036 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.21 U	< 0.11 U			0.12	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 UT	< 0.13 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 5.7 U	< 3 U			0.71 J	< 0.38 U	< 0.69 U	< 0.56 U	< 0.98 U	< 3.4 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.24 U	< 0.12 U			4.5	0.14	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.22 U	< 0.12 U			6.9	0.17	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.26 U	< 0.14 U			0.029 J	< 0.017 U	< 0.031 U	< 0.026 U	< 0.045 U	< 0.15 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.23 U	< 0.12 U			1.4	0.084	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.22 U	< 0.12 U			0.34	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.26 U	< 0.14 U			0.57	0.052 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.21 U	< 0.11 U			0.51	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.23 U	< 0.12 U			0.041 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.23 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.22 U	< 0.12 U			0.04 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 UT	< 0.13 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.22 U	< 0.11 U			0.72	0.038 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.22 U	< 0.11 U			2.9	0.18	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.22 U	< 0.12 U			0.49	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.72	0.059 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.22 U	< 0.12 U			0.16	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.24 U	< 0.13 U			0.03 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.24 U	< 0.12 U			0.021 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.07 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.12	0.029 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.022 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.23 U	< 0.12 U			0.061 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.21 U	< 0.11 U			0.023 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.21 U	< 0.11 U			0.043 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.22 U	< 0.12 U			0.045 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.22 U	< 0.12 U			0.069 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 UT	< 0.13 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.23 U	< 0.12 U			0.081	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.22 U	< 0.11 U			0.089	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	0.47	< 0.11 U		< 0.14 U	0.35	< 0.11 U	0.36	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	0.044 J	< 0.11 U	0.022 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	0.046 J	< 0.13 U		< 0.17 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	0.58	< 0.11 U		< 0.14 U	0.38	< 0.11 U	0.62	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	0.1	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.017 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	0.12	< 0.11 U		< 0.14 U	0.037 J	< 0.11 U	0.019 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	0.084	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.015 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	5.2	< 0.11 U		< 0.15 U	0.61	< 0.12 U	0.9	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	0.081	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	0.2	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	0.024 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	0.13	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	2.1	< 0.1 U		< 0.14 U	0.26	< 0.11 U	0.39	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	0.27	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	0.037 J	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 1 U	< 3 U		< 3.9 U	< 0.5 U	< 3.1 U	< 0.41 U	< 4.8 U	< 2.7 U	< 3.9 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	0.77	< 0.1 U		< 0.14 U	0.091	< 0.11 U	0.12	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	0.12	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.036 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	0.075	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	0.069 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.02 J	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.95 U	< 2.7 U		< 3.6 U	< 0.46 U	< 2.8 U	< 0.37 U	< 4.4 U	< 2.4 U	< 3.6 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	2.5	< 0.11 U		< 0.15 U	0.2	< 0.12 U	0.32	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	2.8	< 0.11 U		< 0.14 U	0.2	< 0.11 U	0.38	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.043 U	< 0.13 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	0.91	< 0.11 U		< 0.15 U	0.11	< 0.12 U	0.3	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.25	< 0.11 U		< 0.14 U	0.06 J	< 0.11 U	0.055 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	0.43	< 0.12 U		< 0.16 U	0.15	< 0.13 U	0.14	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	0.3	< 0.099 U		< 0.13 U	0.24	< 0.1 U	0.16	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	0.11	< 0.11 U	0.052 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	0.11	< 0.11 U		< 0.14 U	0.035 J	< 0.11 U	0.026 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 UT	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.43	< 0.1 U		< 0.14 U	0.093	< 0.11 U	0.094	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	2.2	< 0.1 U		< 0.14 U	0.47	< 0.11 U	0.51	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	0.34	< 0.11 U		< 0.14 U	0.25	< 0.11 U	0.16	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	0.058 J	< 0.11 U		< 0.14 U	0.042 J	< 0.11 U	0.03 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	0.3	< 0.11 U		< 0.15 U	0.076 J	< 0.12 U	0.073 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	0.087	< 0.11 U		< 0.14 U	0.024 J	< 0.11 U	0.023 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	0.05 J	< 0.12 U	0.034 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.039 UT	< 0.11 U		< 0.15 U	0.14	< 0.12 U	0.1	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	0.021 J	< 0.11 U	0.037 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.11	< 0.11 U	0.12	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	2	< 0.11 U	1.8	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.021 J	< 0.11 U	0.02 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.15	< 0.11 U	0.13	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	0.1	< 0.11 U	0.11	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	0.042 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.037 UT	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.046 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	0.043 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.032 J	< 0.17 U	< 0.093 U	< 0.14 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.89	< 0.11 U	1.1
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.12	< 0.11 U	0.053 J
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.061 J	< 0.13 U	0.076 J
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.43	< 0.12 U	0.89
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.041 J	< 0.13 U	0.19
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.021 J	< 0.11 U	0.056 J
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.16	< 0.11 U	0.41
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.089	< 0.11 U	0.31
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	25	< 0.12 U	20
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.1	< 0.11 U	0.25
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.46	< 0.11 U	0.68
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.15	< 0.11 U	0.31
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.044 J	< 0.12 U	0.096
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	1.3	< 0.11 U	4.3
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.33	< 0.12 U	0.71
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 3.8 U	< 3.8 U	< 7.3 U		< 0.71 U	< 3.5 U	< 17 U	1 J	< 3.2 U	1.6 J
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.028 J
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.43	< 0.11 U	2.7
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.049 J	< 0.11 U	0.13
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.11	< 0.11 U	0.14
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.024 J	< 0.11 U	0.044 J
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.087	< 0.11 U	0.13
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 3.5 U	< 3.5 U	< 6.7 U		< 0.65 U	< 3.2 U	< 15 U	< 0.51 U	< 2.9 U	0.73 J
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	1.4	< 0.12 U	5.3
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	2.3	< 0.11 U	6.9
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	< 0.023 U	< 0.13 U	0.03 J
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.031 J
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.87	< 0.12 U	2.3
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.17	< 0.11 U	0.45
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	0.31	< 0.13 U	0.78
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.35	< 0.1 U	0.68
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.09	< 0.12 U	0.052 J
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.059 J	< 0.11 U	0.17
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.029 J	< 0.11 UT	0.046 J
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.38	< 0.11 U	1.1
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	1.2	< 0.11 U	3.9
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.34	< 0.11 U	0.62
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.11	< 0.12 U	0.14
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.42	< 0.12 U	0.77
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.056 J	< 0.11 U	0.22
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.085	< 0.12 U	0.041 J
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.079 J	< 0.12 U	0.03 J
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.052 J	< 0.12 U	0.082
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.41	< 0.11 U	0.16
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.029 J
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.055 J	< 0.11 U	0.077
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.026 J
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.026 J	< 0.11 U	0.062 J
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.059 J	< 0.11 U	0.074 J
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.024 J	< 0.11 U	0.13
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.019 J
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.039 J	< 0.12 U	0.074 J
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.035 J	< 0.11 U	0.082

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated		< 0.18 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated		< 4.1 U	< 4.3 U	< 3.6 U	< 3.5 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated		< 3.8 U	< 4 U	< 3.3 U	< 3.2 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated			3.413	< 0.022 U	0.063 J	< 0.14 U	0.055 J	< 0.17 U	< 0.14 U	< 0.048 U	0.37
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated			14.654	0.026 J	0.47	< 0.16 U	0.43	< 0.2 U	< 0.17 U	< 0.056 U	2.4
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated			0.179	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	0.033 J
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated			1.613	< 0.021 U	0.089	< 0.13 U	0.051 J	< 0.16 U	< 0.13 U	< 0.045 U	0.14
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated			0.312	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.037 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated			0.875	< 0.021 U	< 0.016 U	< 0.13 U	0.022 J	< 0.16 U	< 0.14 U	< 0.046 U	0.077
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated			0.11	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated			0.584	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.051 J
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated			44.35	0.59	0.57	< 0.17 U	0.84	< 0.2 U	< 0.17 U	< 0.058 U	2.4
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated			0.089	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated			0.127	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated			0.97	< 0.022 U	< 0.017 U	< 0.14 U	0.023 J	< 0.17 U	< 0.14 U	< 0.048 U	0.092
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated			0.186	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 UT	< 0.035 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated			0.407	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	0.046 J
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated			3.05	< 0.022 U	0.093	< 0.14 U	0.095	< 0.17 U	< 0.14 U	< 0.047 U	0.27
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated			7.524	< 0.022 U	0.11	< 0.13 U	0.12	< 0.16 U	< 0.14 U	0.068 J	0.87
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated			0.017	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated			0.289	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated			1.705	< 0.02 U	0.055 J	< 0.13 U	0.042 J	< 0.15 U	< 0.13 U	< 0.044 U	0.15
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated			0.155	< 0.023 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated			1.164	< 0.024 U	0.023 J	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.11
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated			0.302	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.041 J
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated			2.771	< 0.02 U	0.1	< 0.12 U	0.055 J	< 0.15 U	< 0.13 U	< 0.043 U	0.26
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated			9.886	< 0.021 U	0.4	< 0.13 U	0.2	< 0.16 UT	< 0.13 U	< 0.046 UT	0.66
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated			0.816	< 0.02 U	0.045 J	< 0.13 U	0.02 J	< 0.15 U	< 0.13 U	< 0.044 U	0.063 J
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated			0.454	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.052 J
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated			0.686	< 0.02 U	0.025 J	< 0.12 U	0.018 J	< 0.15 U	< 0.12 U	< 0.042 U	0.057 J
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated			1.28	< 0.021 U	0.052 J	< 0.13 U	0.028 J	< 0.16 U	< 0.13 U	< 0.045 U	0.1
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated			1.62	< 0.022 U	0.061 J	< 0.14 U	0.059 J	< 0.17 U	< 0.14 U	< 0.048 U	0.14
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated			0.98	< 0.024 U	0.054 J	< 0.15 U	0.022 J	< 0.18 U	< 0.15 U	< 0.051 U	0.083
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated			0.33	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.038 J
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated			0.27	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated			0.105	< 0.023 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated			0.812	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 UT	< 0.15 U	< 0.05 UT	0.067 J
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated			0.733	< 0.022 U	0.041 J	< 0.13 U	0.025 J	< 0.17 U	< 0.14 U	< 0.047 U	0.058 J
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated			0.451	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.053 J
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated			1.995	< 0.02 U	0.051 J	< 0.13 U	0.031 J	< 0.15 U	< 0.13 U	< 0.044 U	0.18
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated			0.388	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.043 J
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated			0.973	< 0.022 U	0.065 J	< 0.13 U	0.03 J	< 0.16 U	< 0.14 U	< 0.047 U	0.082
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated			3.172	< 0.022 U	0.044 J	< 0.14 U	0.053 J	< 0.17 U	< 0.14 U	< 0.047 U	0.34
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated			0.019	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated			0.579	< 0.023 U	0.022 J	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.055 J
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated			0.067	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated			0.574	< 0.022 U	0.042 J	< 0.13 U	0.022 J	< 0.16 U	< 0.14 U	< 0.046 U	0.051 J
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			1.883	< 0.022 U	0.045 J	< 0.13 U	0.043 J	< 0.16 U	< 0.14 U	< 0.046 U	0.18
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			1.753	< 0.022 U	0.037 J	< 0.13 U	0.066 J	< 0.16 U	< 0.14 U	< 0.047 U	0.16
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			1.148	< 0.021 U	0.055 J	< 0.13 U	0.033 J	< 0.16 UT	< 0.13 U	< 0.046 UT	0.1
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			2.172	< 0.023 U	0.079 J	< 0.14 U	0.059 J	< 0.17 U	< 0.15 U	< 0.049 U	0.21
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			2.682	< 0.022 U	0.13	< 0.13 U	0.069 J	< 0.16 U	< 0.14 U	< 0.047 U	0.23
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated			0.55	< 0.021 U	0.043 J	< 0.13 U	0.023 J	< 0.16 U	< 0.13 U	< 0.044 U	0.048 J
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			2.058	< 0.022 U	0.056 J	< 0.14 U	0.048 J	< 0.17 U	< 0.14 U	< 0.047 U	0.19
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			1.019	< 0.021 U	0.018 J	< 0.13 U	0.038 J	< 0.16 U	< 0.13 U	< 0.046 U	0.095
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated			4.273	< 0.022 U	0.14	< 0.13 U	0.11	< 0.17 U	< 0.14 U	< 0.047 U	0.39
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated			1.302	< 0.022 U	0.053 J	< 0.14 U	0.028 J	< 0.17 U	< 0.14 U	< 0.048 U	0.11
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated			0.331	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	0.048 J
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated			1.29	< 0.026 U	0.044 J	< 0.16 U	0.037 J	< 0.19 U	< 0.16 U	< 0.055 U	0.1
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated			1.304	< 0.021 U	0.049 J	< 0.13 U	0.03 J	< 0.16 U	< 0.14 U	< 0.046 U	0.11
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated			0.621	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.058 J
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated			1.492	< 0.021 U	0.042 J	< 0.13 U	0.037 J	< 0.16 U	< 0.13 U	< 0.045 U	0.14
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated			3.697	< 0.02 U	0.16	< 0.13 U	0.094	< 0.16 U	< 0.13 U	< 0.044 U	0.29
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated			2.939	< 0.021 U	< 0.016 U	< 0.13 U	0.067 J	< 0.16 U	< 0.13 U	< 0.045 U	0.25
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated			1.746	< 0.021 U	0.088	< 0.13 U	0.048 J	< 0.16 U	< 0.13 U	< 0.044 U	0.15
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated			1.048	< 0.02 U	0.048 J	< 0.13 U	0.029 J	< 0.15 U	< 0.13 U	< 0.044 U	0.09
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated			0.403	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.044 J
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated			2.179	< 0.021 U	0.039 J	< 0.13 U	0.034 J	< 0.16 UT	< 0.13 U	< 0.045 UT	0.22
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated			2.903	< 0.022 U	0.24	< 0.14 U	0.12	< 0.17 U	< 0.14 U	< 0.048 U	0.22
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated			11.105	0.039 J	0.52	< 0.12 U	0.28	< 0.15 U	< 0.13 U	< 0.043 U	0.77
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated			25.947	0.086	0.6	< 0.14 U	0.68	< 0.17 U	< 0.14 U	< 0.048 U	2.4
Northern Athletic Field	A8P3H3A1-S1	SSHS-IRM5A2-A8P3H3A1-S1-20231116	SSHS-IRM5A2-A8P3H3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated			0.854	< 0.022 U	< 0.017 U	< 0.14 U	0.021 J	< 0.17 U	< 0.14 U	< 0.048 U	0.081
Northern Athletic Field	A8P3H3A1-S3	SSHS-IRM5A2-A8P3H3A1-S3-20231116	SSHS-IRM5A2-A8P3H3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated			1.497	< 0.021 U	< 0.016 U	< 0.13 U	0.039 J	< 0.16 U	< 0.13 U	< 0.045 U	0.13
Northern Athletic Field	A8P3H3A1-S5	SSHS-IRM5A2-A8P3H3A1-S5-20231116	SSHS-IRM5A2-A8P3H3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U

												Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100						
Restricted - Residential												1	1	3.9	100						
Protection of Groundwater												22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.34	0.35	0.18	0.22	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	1.1	1.7	0.68	0.86	< 0.17 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.032 U	0.039 J	< 0.022 U	0.026 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	0.18	0.27	0.1	0.16	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	0.041 J	0.07 J	< 0.025 U	0.039 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	0.077	0.096	0.038 J	0.067 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.031 U	0.032 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	0.06 J	0.073 J	0.027 J	0.055 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	1.9	3	1.3	1.5	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.032 U	0.022 J	< 0.022 U	0.018 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.032 U	0.027 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	0.09	0.098	0.047 J	0.062 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.034 U	0.032 J	< 0.023 U	0.022 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	0.047 J	0.051 J	0.025 J	0.031 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	0.27	0.31	0.13	0.19	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	0.89	0.97	0.42	0.63	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.03 U	0.017 J	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	0.036 J	0.049 J	0.026 J	0.033 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	0.15	0.18	0.057 J	0.15	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.035 U	0.038 J	< 0.024 U	0.027 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	0.15	0.18	0.06 J	0.13	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	0.043 J	0.057 J	0.022 J	0.034 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	0.28	0.28	0.13	0.26	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	0.87	1	0.49	1.2 T	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 UT	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	0.082	0.092	0.04 J	0.1	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	0.045 J	0.049 J	0.022 J	0.041 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	0.059 J	0.071	0.026 J	0.077	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	0.11	0.14	0.058 J	0.14	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	0.14	0.15	0.062 J	0.13	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	0.1	0.11	0.057 J	0.1	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	0.041 J	0.056 J	< 0.022 U	0.031 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	0.035 J	0.044 J	0.025 J	0.026 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.035 U	0.037 J	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	0.07 J	0.095	0.047 J	0.055 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	0.074 J	0.1	0.046 J	0.061 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	0.058 J	0.07 J	0.024 J	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	0.22	0.25	0.11	0.13	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	0.044 J	0.056 J	< 0.023 U	0.029 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	0.098	0.14	0.062 J	0.086	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	0.31	0.36	0.22	0.21	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	0.058 J	0.066 J	0.039 J	0.047 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.034 U	0.021 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	0.064 J	0.081	0.036 J	0.054 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.19	0.22	0.1	0.12	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.13	0.16	0.063 J	0.075	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.11	0.16	0.038 J	0.091	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.2	0.27	0.097	0.15	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.25	0.3	0.13	0.18	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	0.057 J	0.07 J	0.032 J	0.051 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.21	0.25	0.1	0.14	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.077	0.08	0.037 J	0.046 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.43	0.52	0.2	0.28	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	0.13	0.16	0.07 J	0.1	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	0.045 J	0.043 J	0.023 J	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	0.14	0.17	0.063 J	< 0.019 U	< 0.16 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	0.13	0.15	0.089	0.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	0.066 J	0.076	0.033 J	0.054 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	0.15	0.18	0.076	0.11	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	0.36	0.49	0.17	0.29	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	0.28	0.37	0.15	0.22	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	0.18	0.23	0.07 J	0.19	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.11	0.15	0.053 J	0.093	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	0.048 J	0.062 J	0.025 J	0.033 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.23 T	0.24	0.14	0.14	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	0.27	0.34	0.13	0.25	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	0.93	1.4	0.45	1	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	1.8	2.2	0.95	1.4	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	0.085	0.097	0.05 J	0.046 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	0.15	0.22	0.065 J	0.14	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.25 U	0.021 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.49	0.088	< 0.14 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.29 U	0.12	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	1.5	0.21	< 0.17 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.17	< 0.047 U	< 0.13 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.053 J	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.1	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.063 J	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.3 U	1.1	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	3.7	0.42	0.47
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.1	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	0.047 J	< 0.054 U	< 0.16 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.25 U	0.039 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.29	0.055 J	< 0.14 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.24 U	0.019 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.93	0.14	< 0.14 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.042 J	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.15	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.12	< 0.052 U	< 0.15 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.24	0.058 J	< 0.13 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.24 UT	0.12	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.71	0.19 T	< 0.14 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.069 J	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.045 J	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.056 J	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.099	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.14	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.1	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.051 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.043 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 UT	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.092	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.081	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.05 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.21	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.051 J	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.1	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.34	0.053 J	< 0.14 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.071 J	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.059 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.19	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.24 U	0.024 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.16	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.13	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.22	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.24 U	0.019 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.28	0.053 J	< 0.14 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.058 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.21	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.084	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.25 U	0.024 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.43	0.078	< 0.14 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.15	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.046 J	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.29 U	< 0.021 U	< 0.12 U	< 0.16 U	< 0.02 U	< 0.16 U	< 0.15 U	0.14	< 0.057 U	< 0.16 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.14	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.073 J	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.17	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.23 U	0.029 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.39	0.073	< 0.13 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.33	0.055 J	< 0.13 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.19	0.047 J	< 0.13 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.11	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.052 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 UT	0.23 T	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.25 U	0.034 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.3	0.083	< 0.14 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.22 U	0.085	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	1.1	0.21	< 0.13 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.25 U	0.3	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	2.3	0.37	< 0.14 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.09	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.2	0.054 J	< 0.14 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.42 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.26 U	< 0.78 U	< 0.18 U	< 2.8 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	0.39	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.43 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.8 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.39 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 UT	< 0.16 U	< 0.18 UT	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.41 U	< 0.034 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.19 U	< 0.26 U	< 0.77 U	< 0.17 U	< 2.8 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 UT	< 0.14 UT	< 2.2 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.23 U	< 0.12 U			0.46	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.27 U	< 0.14 U			3.1	0.039 J	< 0.032 U	< 0.026 U	< 0.046 U	< 0.16 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.22 U	< 0.11 U			0.041 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.22 U	< 0.11 U			0.15	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.25 U	< 0.13 U			0.057 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.22 U	< 0.12 U			0.14	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.21 U	< 0.11 U			0.033 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.23 U	< 0.12 U			0.077	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.28 U	< 0.14 U			9.4	1	< 0.033 U	< 0.027 U	< 0.048 U	< 0.16 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.22 U	< 0.12 U			0.023 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.22 U	< 0.12 U			0.035 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.23 U	< 0.12 U			0.18	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.23 U	< 0.12 U			0.034 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.25 U	< 0.13 U			0.069 J	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.23 U	< 0.12 U			0.5	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.22 U	< 0.12 U			0.94	0.015 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.21 U	< 0.11 U			0.052 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.27	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.24 U	< 0.13 U			0.047 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.24 U	< 0.13 U			0.14	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.053 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.42	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.22 U	< 0.11 U			1.2	0.026 J	< 0.026 U	< 0.022 U	< 0.038 UT	< 0.13 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.21 U	< 0.11 U			0.096	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.22 U	< 0.11 U			0.098	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.2 U	< 0.11 U			0.097	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.21 U	< 0.11 U			0.17	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.23 U	< 0.12 U			0.29	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.25 U	< 0.13 U			0.13	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.22 U		< 0.12 U		0.058 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.23 U		< 0.12 U		0.049 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.24 U		< 0.13 U		0.036 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.24 U		< 0.13 U		0.14	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 UT	< 0.14 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.23 U		< 0.12 U		0.099	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.23 U		< 0.12 U		0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.21 U		< 0.11 U		0.37	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.23 U		< 0.12 U		0.069 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.22 U		< 0.12 U		0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.23 U		< 0.12 U		0.55	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.23 U		< 0.12 U		< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.24 U		< 0.13 U		0.095	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.23 U		< 0.12 U		0.024 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.22 U		< 0.12 U		0.066 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.22 U		< 0.12 U		0.31	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.22 U		< 0.12 U		0.31	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.22 U		< 0.11 U		0.16	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 UT	< 0.13 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.24 U		< 0.12 U		0.34	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.22 U		< 0.12 U		0.41	0.019 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.21 U		< 0.11 U		0.062 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.23 U		< 0.12 U		0.34	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.22 U		< 0.11 U		0.19	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.23 U		< 0.12 U		0.66	0.02 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.23 U		< 0.12 U		0.15	0.039 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.2 U		< 0.11 U		0.063 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.27 U		< 0.14 U		0.22	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.16 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.2 U		< 0.11 U		< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.22 U		< 0.12 U		0.17	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.22 U		< 0.12 U		0.093	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.22 U		< 0.11 U		0.22	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.21 U		< 0.11 U		0.52	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.22 U		< 0.11 U		0.41	0.017 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.21 U		< 0.11 U		0.2	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.21 U		< 0.11 U		0.14	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.22 U		< 0.12 U		0.062 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.21 UT		< 0.11 U		0.37	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 UT	< 0.13 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.23 U		< 0.12 U		0.4	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.21 U		< 0.11 U		1.5	0.066 J	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.24 U		< 0.13 U		< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.23 U		< 0.12 U		4.8	0.28	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.23 U		< 0.12 U		0.13	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.22 U		< 0.11 U		0.11	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.19	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.77	< 0.13 U		< 0.17 U	0.037 J	< 0.13 U	0.039 J	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	0.16	< 0.1 U		< 0.14 U	0.017 J	< 0.11 U	0.023 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	0.049 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	0.038 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	1.3	< 0.13 U		< 0.17 U	0.27	< 0.14 U	0.4	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	0.052 J	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	0.02 J	< 0.11 U	0.02 J	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	0.15	< 0.11 U		< 0.14 U	0.044 J	< 0.11 U	0.1	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	0.54	< 0.11 U		< 0.14 U	0.037 J	< 0.11 U	0.079	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	0.11	< 0.1 U		< 0.13 U	0.027 J	< 0.1 U	0.056 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	0.11	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	0.21	< 0.1 U		< 0.13 U	0.031 J	< 0.1 U	0.048 J	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	0.85 T	< 0.11 U		< 0.14 U	0.21	< 0.11 U	0.84	< 0.17 U	< 0.094 U	< 0.14 UT
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	0.076	< 0.1 U		< 0.13 U	0.023 J	< 0.1 U	0.04 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	0.052 J	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	0.04 J	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	0.12	< 0.1 U		< 0.13 U	0.022 J	< 0.11 U	0.089	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	0.1	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	0.029 J	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	0.079 J	< 0.12 U		< 0.15 U	0.024 J	< 0.12 U	0.034 J	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	0.04 J	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 UT	< 0.15 UT
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	0.051 J	< 0.11 U		< 0.14 U	0.02 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	0.11	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	0.071 J	< 0.11 U		< 0.14 U	0.018 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	0.18	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	0.041 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.11	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.02 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.067 J	< 0.11 U		< 0.14 U	0.05 J	< 0.11 U	0.032 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.073 J	< 0.11 U		< 0.14 U	0.031 J	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.12	< 0.11 U		< 0.15 U	0.025 J	< 0.12 U	0.026 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.14	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.021 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	0.042 J	< 0.1 U		< 0.13 U	0.018 J	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.12	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.042 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	0.24	< 0.11 U		< 0.14 U	0.019 J	< 0.11 U	0.035 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.035 U	< 0.1 UT		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	0.07 J	< 0.11 UT		< 0.14 U	0.022 J	< 0.11 U	0.02 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.034 U	< 0.098 UT		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	0.085 J	< 0.13 UT		< 0.17 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.17 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.034 U	< 0.098 UT		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	0.087	< 0.11 UT		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	0.043 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	0.083	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	0.016 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	0.22	< 0.1 U		< 0.13 U	0.037 J	< 0.1 U	0.04 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	0.18	< 0.1 U		< 0.14 U	0.038 J	< 0.11 U	0.04 J	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	0.12	< 0.1 U		< 0.13 U	0.027 J	< 0.1 U	0.025 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.074	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.12	< 0.1 U		< 0.14 U	< 0.017 UT	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	0.21	< 0.11 U		< 0.15 U	0.04 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	0.8	< 0.099 U		< 0.13 U	0.12	< 0.1 U	0.14	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	1.2	< 0.11 U		< 0.14 U	0.072 J	< 0.11 U	0.081	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	0.039 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	0.1	< 0.11 U		< 0.14 U	0.061 J	< 0.11 U	0.066 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.11	< 0.12 U	0.56
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	0.4	< 0.14 U	2.4
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.04 J
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.039 J	< 0.11 U	0.17
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	0.052 J
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.069 J	< 0.11 U	0.14
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.045 J
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.05 J	< 0.12 U	0.09
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.17 U	< 0.17 U	< 0.33 U		< 0.032 U	< 0.15 U	< 0.75 U	8.3	< 0.14 U	8.3
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.026 J
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.025 J	< 0.11 U	0.04 J
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.076 J	< 0.12 U	0.15
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.031 J	< 0.12 U	0.047 J
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.027 J	< 0.13 U	0.064 J
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.25	< 0.11 U	0.44
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.15	< 0.11 U	0.83
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.051 J
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.16	< 0.11 U	0.23
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	0.043 J
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.034 J	< 0.12 U	0.13
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	0.052 J
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.15	< 0.11 U	0.38
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.55	< 0.11 U	1.1
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.047 J	< 0.11 U	0.091
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.026 J	< 0.11 U	0.076
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.05 J	< 0.1 U	0.083
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.076	< 0.11 U	0.15
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.14	< 0.12 U	0.24
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.045 J	< 0.13 U	0.12
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.055 J
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.048 J
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U	0.032 J
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 UT	< 0.65 U	0.086 T	< 0.12 U	0.12
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.038 J	< 0.11 U	0.1
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.086
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.074	< 0.11 U	0.31
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.026 J	< 0.12 U	0.07 J
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.044 J	< 0.11 U	0.13
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.096	< 0.11 U	0.46
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.019 J
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.055 J	< 0.12 U	0.093
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.022 J
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.025 J	< 0.11 U	0.075
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.14	< 0.11 U	0.26
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.26	< 0.11 U	0.27
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.093	< 0.11 U	0.16
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.17	< 0.12 U	0.31
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.6 U	0.19	< 0.11 U	0.41
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.038 J	< 0.11 U	0.069 J
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.15	< 0.11 U	0.3
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.17	< 0.11 U	0.16
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.27	< 0.11 U	0.61
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.075 J	< 0.12 U	0.2
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.063 J
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	0.095	< 0.13 U	0.24
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.078	< 0.11 U	0.22
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.042 J	< 0.11 U	0.083
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.1	< 0.11 U	0.21
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.24	< 0.11 U	0.52
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.17	< 0.11 U	0.4
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.086	< 0.11 U	0.21
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.059 J	< 0.11 U	0.14
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.026 J	< 0.11 U	0.051 J
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.095	< 0.11 U	0.36
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.17	< 0.12 U	0.41
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.42	< 0.1 U	2
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	3.2	< 0.12 U	4.4
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.085	< 0.12 U	0.13
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.073 J	< 0.11 U	0.15
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated		< 0.18 U	< 0.19 U	< 0.15 U	< 0.15 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated			1.798	< 0.021 U	< 0.016 U	< 0.13 U	0.053 J	< 0.16 U	< 0.13 U	< 0.046 U	0.15
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated			3.201	< 0.023 U	0.12	< 0.14 U	0.093	< 0.18 U	< 0.15 U	< 0.05 U	0.24
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated			3.104	< 0.024 U	0.079 J	< 0.15 U	0.059 J	< 0.18 U	< 0.15 U	< 0.051 U	0.23
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated			0.465	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.043 J
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated			5.354	< 0.024 U	0.27	< 0.15 U	0.13	< 0.18 U	< 0.15 U	< 0.052 U	0.41
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated			3.636	< 0.02 U	0.23	< 0.13 U	0.11	< 0.15 U	< 0.13 U	< 0.044 U	0.25
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated			0.05	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated			0.259	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	0.045 J
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated			0.193	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated			2.862	< 0.023 U	0.096	< 0.14 U	0.052 J	< 0.17 U	< 0.14 U	< 0.049 U	0.23
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated			1.287	< 0.021 U	0.032 J	< 0.13 U	0.019 J	< 0.16 U	< 0.14 U	< 0.046 U	0.12
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated			0.472	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.053 J
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated			0.396	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.039 J
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated			0.923	< 0.02 U	0.024 J	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.094
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated			0.345	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.047 J
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated			0.821	< 0.022 U	0.044 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.069 J
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated			20.709	0.099	0.85	< 0.15 U	0.5	< 0.19 U	< 0.16 U	< 0.054 U	1.7
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated			0.516	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	0.052 J
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated			0.432	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.045 J
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated			2.928	0.029 J	0.083	< 0.14 U	0.062 J	< 0.17 U	< 0.14 U	< 0.047 U	0.23
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated			29.297	0.067 J	1.1	< 0.15 U	0.68	< 0.18 U	< 0.15 U	< 0.052 U	2.7
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated			0.043	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 UT	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated			3.024	< 0.023 U	0.059 J	< 0.14 U	0.04 J	< 0.17 U	< 0.14 U	< 0.049 U	0.25
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated			0.047	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated			5.826	< 0.023 U	0.23	< 0.14 U	0.089	< 0.17 U	< 0.15 U	< 0.049 U	0.6
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated			0.295	< 0.022 U	0.019 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.037 J
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated			1.581	< 0.023 U	0.043 J	< 0.15 U	0.049 J	< 0.18 U	< 0.15 U	< 0.051 U	0.17
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated			2.286	< 0.024 U	0.14	< 0.15 U	0.077 J	< 0.18 U	< 0.15 U	< 0.051 U	0.19
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated			0.985	< 0.022 U	0.032 J	< 0.14 U	0.024 J	< 0.17 U	< 0.14 U	< 0.047 U	0.094
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated			11.857	0.045 J	0.26	< 0.17 U	0.27	< 0.21 U	< 0.18 U	< 0.06 U	1
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated			195.46	0.34	6.6	< 0.16 U	5.5	< 0.2 U	< 0.17 U	< 0.057 U	18
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated			5.015	< 0.023 U	0.17	< 0.14 U	0.1	< 0.17 U	< 0.15 U	< 0.049 U	0.46
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated			8.768	0.06 J	< 0.019 U	< 0.15 U	0.24	< 0.19 U	< 0.16 U	< 0.053 U	0.63
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated			3.657	< 0.045 U	< 0.034 U	< 0.28 U	0.047 J	< 0.34 U	< 0.29 U	< 0.097 UT	0.3
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated			2.722	0.029 J	0.032 J	< 0.14 U	0.081	< 0.17 U	< 0.14 U	< 0.048 U	0.25
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated			6.0561	0.0091	0.14	< 0.03	0.15	< 0.036	< 0.033	< 0.055	0.52
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated			0.333	< 0.0073	0.02	< 0.031	0.012	< 0.037	< 0.034	< 0.057	0.036
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated			ND	< 0.0072	< 0.0086	< 0.031	< 0.0074	< 0.037	< 0.034	< 0.057	< 0.0095
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated			ND	< 0.0069	< 0.0083	< 0.03	< 0.0071	< 0.035	< 0.032	< 0.054	< 0.009
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated			0.041	< 0.0069	< 0.0082	< 0.03	< 0.007	< 0.035	< 0.032	< 0.054	< 0.009
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated			ND	< 0.36	< 0.36		< 0.36				< 0.36
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated			0.033	< 0.043 U	< 0.033 U	< 0.041 U	< 0.039 U	< 0.33 U	< 0.031 U	< 0.093 U	< 0.028 U
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated			1.726	< 0.045 U	< 0.034 U	< 0.042 U	< 0.04 U	< 0.34 U	< 0.033 U	< 0.096 U	0.17
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.015 U
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated			1.759	< 0.023 U	0.1	< 0.021 U	0.05 J	< 0.17 U	< 0.017 U	< 0.049 U	0.14
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated			5.812	< 0.091 U	0.29 J	< 0.085 U	0.16 J	< 0.69 U	< 0.066 U	< 0.2 U	0.54
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated			1.044	0.022	0.017	0.021	0.02	0.17	0.016	0.048	0.096
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated			3.872	0.027 J	0.12	< 0.021 U	0.13	< 0.17 U	0.017 J	< 0.047 U	0.32
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated			1.775	< 0.021 U	0.035 J	< 0.02 U	0.038 J	< 0.16 U	< 0.016 U	< 0.046 U	0.17
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated			3.719	< 0.022 U	0.088	< 0.021 U	0.074 J	< 0.17 U	< 0.016 U	< 0.047 U	0.34
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated			2.576	< 0.021 U	0.11	< 0.019 U	0.053 J	< 0.16 U	< 0.015 U	< 0.044 U	0.25
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated			0.741	< 0.022 U	0.052 J	< 0.02 U	0.028 J	< 0.16 U	< 0.016 U	< 0.046 U	0.07 J
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated			0.741	< 0.022 U	0.052 J	< 0.02 U	0.028 J	< 0.16 U	< 0.016 U	< 0.046 U	0.07 J
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	< 38 U	< 38 U	1.787	< 0.022 U	0.1	< 0.021 U	0.042 J	< 0.17 U	< 0.016 U	< 0.047 U	0.15
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated			4.457	< 0.022 U	0.2	< 0.021 U	0.094	< 0.17 U	< 0.016 U	< 0.048 U	0.41
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated			17.857	< 0.022 U	0.71	< 0.02 U	0.46	< 0.16 U	< 0.016 U	< 0.047 U	1.7
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated			1.237	< 0.021 U	0.081	< 0.02 U	0.036 J	< 0.16 U	< 0.016 U	< 0.046 U	0.11
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	< 39 U	< 39 U	0.731	< 0.022 U	0.055 J	< 0.021 U	0.025 J	< 0.17 U	< 0.016 U	< 0.047 U	0.067 J
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	< 41 U	< 41 U	0.887	< 0.022 U	0.043 J	< 0.021 U	0.024 J	< 0.17 U	< 0.016 U	< 0.048 U	0.082
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated			0.805	< 0.023 U	< 0.017 U	< 0.021 U	0.02 J	< 0.17 U	< 0.017 U	< 0.049 U	0.081
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated			0.155	< 0.021 U	0.02 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated			0.643	< 0.023 U	0.062 J	< 0.021 U	0.028 J	< 0.17 U	< 0.017 U	< 0.049 U	0.05 J
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated			0.335	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.037 J
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		< 0.034 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated			0.078	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated			0.369	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.043 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated			0.125	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated			1.27	< 0.021 U	0.085	< 0.02 U	0.037 J	< 0.16 U	< 0.015 U	< 0.045 U	0.1

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.15	0.25	0.089	0.098	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.3	0.49	0.18	0.27	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.27	0.45	0.15	0.19	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	0.051 J	0.065 J	0.042 J	0.037 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	0.5	0.62	0.24	0.4	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	0.34	0.37	0.22	0.28	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.032 U	0.05 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.034 U	0.046 J	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	0.26	0.34	0.16	0.2	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	0.11	0.14	0.069 J	0.075	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	0.046 J	0.071 J	0.027 J	0.034 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	0.042 J	0.064 J	0.023 J	0.026 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	0.089	0.11	0.049 J	0.063 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	0.033 J	0.068 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.074 J	0.096	0.036 J	0.076 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	1.9	2.1	1	1.7	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.047 J	0.056 J	0.021 J	0.029 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	0.043 J	0.051 J	0.026 J	0.025 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.23	0.32	0.1	0.21	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	2.4	2.9	1.3	2.3	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 UT	< 0.17 U	< 0.27 UT
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	0.26	0.39	0.16	0.19	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	0.73	0.94	0.3	0.48	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.034 U	0.041 J	< 0.023 U	0.042 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	0.16	0.15	0.067 J	0.11	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	0.19	0.25	0.11	0.21	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	0.09	0.11	0.047 J	0.088	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	1	1.4	0.53	0.95	< 0.18 U	< 0.017 U	< 0.036 U	< 0.51 U	< 0.2 U	< 0.33 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	16	21	7.3	16	< 0.17 U	< 0.017 U	< 0.034 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	0.37	0.5	0.19	0.27	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated	0.68	0.98	0.35	0.5	< 0.16 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated	0.35	0.47	0.17	0.3	< 0.29 U	< 0.048 U	< 0.058 U	< 0.83 UT	< 0.33 U	< 0.54 UT
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated	0.25	0.27	0.1	0.19	< 0.14 U	< 0.024 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	0.56	0.6	0.3	0.62	< 0.024	< 0.0098	< 0.0079	< 0.059	< 0.032	< 0.05
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	0.034	0.043	0.016	< 0.0075	< 0.025	< 0.01	< 0.0081	< 0.061	< 0.033	< 0.052
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.0076	< 0.012	< 0.015	< 0.0075	< 0.025	< 0.01	< 0.0081	< 0.061	< 0.033	< 0.052
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.0072	< 0.011	< 0.015	< 0.0072	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.0072	< 0.011	< 0.015	< 0.0071	< 0.024	< 0.0096	< 0.0078	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B47	_13 SEP 00B47_3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated	< 0.033 U	< 0.037 U	< 0.045 U	< 0.032 U	< 0.036 U	< 0.027 U	< 0.055 U	< 0.8 U	< 0.052 U	< 0.51 U
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated	0.19	0.21	0.076 J	0.18	< 0.037 U	< 0.028 U	< 0.057 U	< 0.83 U	< 0.054 U	< 0.53 U
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	< 0.018 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U	< 0.28 U
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	0.17	0.24	0.097	0.15	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	0.44 J	0.61 J	0.24 J	0.44 J	< 0.075 U	< 0.057 U	< 0.12 U	< 1.7 U	< 0.11 U	< 1.1 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.11	0.12	0.053	0.017	0.018	0.014	0.028	0.41	0.027	0.26
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated	0.33	0.41	0.17	0.28	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated	0.18	0.2	0.085	0.13	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated	0.42	0.44	0.19	0.31	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated	0.28	0.35	0.14	0.23	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	0.076	0.1	0.033 J	0.067 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	0.076	0.1	0.033 J	0.067 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	0.18	0.21	0.12	0.16	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated	0.47	0.59	0.19	0.37	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated	1.6	2.2	0.58	1.5	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	0.12	0.18	0.032 J	0.12	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	0.07 J	0.088	0.034 J	0.053 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	0.087	0.11	0.038 J	0.081	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated	0.07 J	0.082	0.033 J	0.052 J	< 0.019 U	< 0.014 U	< 0.029 U	0.46 J	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated	< 0.032 U	0.031 J	< 0.022 U	0.036 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated	0.059 J	0.078 J	0.025 J	0.078 J	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated	0.039 J	0.045 J	< 0.023 U	0.036 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3629	020421 09:30_SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.033 U	0.039 J	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated	0.11	0.17	0.089	0.14	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7									
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.2	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.26 U	0.035 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.34	0.072 J	< 0.15 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.27 U	0.05 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.36	0.06 J	< 0.15 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.056 J	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.27 U	0.033 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.55	0.081 J	< 0.15 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.23 U	0.029 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.38	0.062 J	< 0.13 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.05 J	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.32	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.15	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.059 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.049 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.11	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.046 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.097	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.28 U	0.11	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	2.2	0.4	< 0.16 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.061 J	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.05 J	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.25 U	0.024 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.28	0.066 J	< 0.14 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.27 U	0.16	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	2.9	0.56	< 0.15 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.26 U	0.023 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.36	0.064 J	< 0.15 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.74	0.15	< 0.15 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.046 J	< 0.05 U	< 0.14 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.18	< 0.052 U	< 0.15 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.27 U	0.022 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.24	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.1	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	< 0.31 U	0.07 J	< 0.13 U	< 0.17 U	< 0.022 U	< 0.18 U	< 0.16 U	1.3	0.23	< 0.18 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	< 0.3 U	0.96	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	20	4.6	0.33 J
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	< 0.26 U	0.038 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.56	0.095	< 0.15 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated	< 0.28 U	0.16	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.76	0.13	< 0.16 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated	< 0.51 U	< 0.037 U	< 0.21 U	< 0.27 U	< 0.036 U	< 0.29 U	< 0.26 U	0.34	< 0.1 U	< 0.29 U
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated	< 0.25 U	0.028 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.26	0.057 J	< 0.14 U
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.28	0.032	< 0.029	< 0.034	< 0.0077	< 0.03	< 0.041	0.51	0.14	0.045
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.28	< 0.007	< 0.03	< 0.035	< 0.0079	< 0.031	< 0.042	0.036	< 0.0084	< 0.037
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.28	< 0.007	< 0.03	< 0.035	< 0.0079	< 0.031	< 0.042	< 0.009	< 0.0084	< 0.037
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	< 0.0086	< 0.008	< 0.035
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0075	< 0.029	< 0.04	< 0.0086	< 0.008	< 0.035
Northern Athletic Field	SSHS-B47	_13 SEP 00B47_3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated		< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated	< 0.49 U	< 0.035 U	< 0.025 U	< 0.035 U	< 0.034 U	< 0.035 U	< 0.045 U	< 0.029 U	< 0.033 U	< 0.033 U
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated	< 0.51 U	< 0.036 U	< 0.026 U	< 0.037 U	< 0.036 U	< 0.036 U	< 0.047 U	0.17	0.071 J	< 0.034 U
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	< 0.27 U	< 0.019 U	< 0.014 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.016 U	< 0.018 U	< 0.018 U
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	< 0.26 U	< 0.018 U	< 0.013 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.19	0.048 J	< 0.017 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	< 1 U	< 0.074 UJ	< 0.052 U	< 0.074 U	< 0.072 U	< 0.073 U	< 0.095 U	0.55 J	0.37	< 0.069 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.25	0.018	0.026	0.018	0.018	0.018	0.023	0.12	0.049	0.017
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated	< 0.25 U	0.033 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.33	0.065 J	0.03 J
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.16	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated	< 0.25 U	0.019 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.34	0.078	0.023 J
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.28	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.081	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.081	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.19	0.061 J	< 0.017 U
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated	< 0.25 U	0.027 J	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.44	0.12	< 0.017 U
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated	< 0.25 U	0.068 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	1.8	0.4	< 0.016 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.08	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.095	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.074 J	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.062 J	< 0.051 U	< 0.017 U
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.049 J	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3629	020421 09:30_SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.047 J	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U	< 0.017 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 UJ	< 0.017 U	< 0.017 U	< 0.022 U	0.12	< 0.046 U	< 0.016 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 UT	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 UT	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 UT	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 UT	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	< 0.45 U	< 0.037 U	< 0.17 U	< 0.16 U	< 0.19 U	< 0.21 UT	< 0.28 U	< 0.83 U	< 0.19 U	< 3 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	< 0.42 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 UT	< 0.26 U	< 0.79 U	< 0.18 U	< 2.8 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 UT	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated	< 0.73 U	< 0.06 U	< 0.27 U	< 0.26 U	< 0.87 U	< 1.6 U	< 0.45 U	< 1.3 U	< 0.3 U	< 4.9 U
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.43 U	< 0.81 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.039	< 0.0074	< 0.04	< 0.057	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.04	< 0.0076	< 0.041	< 0.059	< 0.041	< 0.047	< 0.04	< 0.15	< 0.039	< 0.45
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.04	< 0.0076	< 0.041	< 0.059	< 0.041	< 0.047	< 0.04	< 0.15	< 0.039	< 0.45
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.43
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.43
Northern Athletic Field	SSHS-B47	13 SEP 00B47_3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 1.8	< 0.36	< 1.8
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated	< 0.7 U	< 0.058 U	< 0.26 U	< 0.046 U	< 0.027 U	< 0.33 U	< 0.44 U	< 1.3 U	< 0.046 U	< 2 U
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated	< 0.72 U	< 0.06 U	< 0.27 U	< 0.048 U	< 0.028 U	< 0.34 U	< 0.45 U	< 1.3 U	< 0.048 U	< 2.1 U
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.015 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U	< 1.1 U
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	< 1.5 U	< 0.12 U	< 0.55 U	< 0.098 U	< 0.057 U	< 0.69 U	< 0.91 U	< 2.7 U	< 0.097 U	< 4.2 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.36	0.03	0.13	0.024	0.028	0.17	0.22	0.66	0.024	2.1
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated	< 0.35 U	< 0.029 U	0.16 J	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated	< 0.37 U	< 0.03 U	0.14 J	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3629	020421 09:30_SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	< 0.24 U		< 0.13 U		< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.22 U		< 0.11 U		0.26	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.24 U		< 0.13 U		0.39	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.25 U		< 0.13 U		0.48	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	< 0.22 U		< 0.12 U		0.071 J	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.25 U		< 0.13 U		0.85	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.21 U		< 0.11 U		0.55	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.21 U		< 0.11 U		0.025 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.22 U		< 0.11 U		0.055 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.24 U		< 0.12 U		0.06 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.24 U		< 0.12 U		0.48	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.22 U		< 0.12 U		0.23	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.23 U		< 0.12 U		< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.21 U		< 0.11 U		0.091	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.22 U		< 0.12 U		0.077	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.21 U		< 0.11 U		0.16	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.21 U		< 0.11 U		0.064 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.23 U		< 0.12 U		0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.26 U		< 0.14 U		2.7	0.11	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.2 U		< 0.11 U		0.084	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.25 U		< 0.13 U		0.083	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.23 U		< 0.12 U		0.39	0.018 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.25 U		< 0.13 U		4.1	0.12	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.24 U		< 0.12 U		0.021 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 UT	< 0.14 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.23 U		< 0.12 U		0.47	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.22 U		< 0.11 U		0.024 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.24 U		< 0.12 U		0.56	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.23 U		< 0.12 U		0.055 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.24 U		< 0.13 U		0.23	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.25 U		< 0.13 U		0.34	0.018 J	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.23 U		< 0.12 U		0.15	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.25 U		< 0.13 U		< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	< 0.29 U		< 0.15 U		1.3	0.057 J	< 0.034 U	< 0.028 U	< 0.049 U	< 0.17 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	< 0.27 U		< 0.14 U		27	0.87	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	< 0.24 U		< 0.12 U		0.77	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated	< 0.25 U		< 0.13 U		1.5	0.078 J	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated	< 0.47 U		< 0.49 U		0.68 T	< 0.031 U	< 0.056 U	< 0.046 U	< 0.21 UT	< 0.28 U
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated	< 0.23 U		< 0.24 U		0.41	0.025 J	< 0.028 U	< 0.023 U	< 0.11 U	< 0.14 U
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.03			< 0.042	0.83	0.027	< 0.0078	< 0.0082	< 0.04	< 0.026
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.03			< 0.043	0.051	< 0.0099	< 0.008	< 0.0084	< 0.041	< 0.027
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.03			< 0.043	< 0.0081	< 0.0099	< 0.008	< 0.0084	< 0.041	< 0.027
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.029			< 0.041	< 0.0077	< 0.0095	< 0.0077	< 0.0081	< 0.039	< 0.026
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.029			< 0.041	0.015	< 0.0095	< 0.0077	< 0.008	< 0.039	< 0.026
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.36				< 0.36	< 0.36	< 0.36	< 0.36	< 0.36	< 0.36
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated	< 0.037 U			< 0.23 U	< 0.04 U	< 0.029 U	< 0.054 U	< 0.044 U	< 0.077 U	< 0.039 U
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated	< 0.039 U			< 0.24 U	0.23	< 0.03 U	< 0.056 U	< 0.045 U	< 0.079 U	< 0.04 U
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	< 0.02 U			< 0.13 U	< 0.022 UJ	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.021 U
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	< 0.02 U			< 0.12 U	0.2	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	< 0.078 U			< 0.49 U	0.8 J	< 0.062 UJ	< 0.11 U	< 0.092 U	< 0.16 U	< 0.081 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.058			0.12	0.15	0.015	0.028	0.022	0.039	0.02
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.56	0.033 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated	< 0.056 U			< 0.12 U	0.28	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated	< 0.057 U			< 0.12 U	0.47	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated	< 0.054 U			< 0.11 U	0.3	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.018 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.056 U			< 0.12 U	0.094	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.056 U			< 0.12 U	0.094	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	< 0.057 U			< 0.12 U	0.2	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated	< 0.058 U			< 0.12 U	0.53	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated	< 0.057 U			< 0.12 U	2.5	0.076	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.056 U	< 0.12 U			0.16	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	< 0.057 U			< 0.12 U	0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	< 0.058 U			< 0.12 U	0.12	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated	< 0.059 U			< 0.12 U	0.13	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated	< 0.056 U			< 0.12 U	0.03 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated	< 0.06 U			< 0.12 U	0.068 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated	< 0.058 U			< 0.12 U	0.054 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3629	020421 09:30_SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.055 U	< 0.11 U			0.032 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.057 U	< 0.12 U			0.088	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.059 U	< 0.12 U			0.042 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated	< 0.054 U			< 0.11 U	0.14	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.091	< 0.11 U		< 0.14 U	0.069 J	< 0.11 U	0.077	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.2	< 0.12 U		< 0.15 U	0.039 J	< 0.12 U	0.066 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	0.17	< 0.12 U		< 0.15 U	0.034 J	< 0.12 U	0.045 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	0.3	< 0.12 U		< 0.16 U	0.065 J	< 0.12 U	0.063 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	0.22	< 0.1 U		< 0.13 U	0.064 J	< 0.1 U	0.054 J	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	0.16	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	0.058 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	0.051 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.065 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	1.3	< 0.12 U		< 0.16 U	0.11	< 0.13 U	0.3	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.057 J	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.17	< 0.11 U		< 0.14 U	0.02 J	< 0.11 U	0.093	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	1.8	< 0.12 U		< 0.16 U	0.1	< 0.12 U	0.17	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	0.17	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	0.37	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	0.086	< 0.12 U		< 0.15 U	0.028 J	< 0.12 U	0.039 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	0.15	< 0.12 U		< 0.15 U	0.05 J	< 0.12 U	0.071 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	0.075 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.018 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	0.76	< 0.14 U		< 0.18 U	0.056 J	< 0.14 U	0.065 J	< 0.22 U	< 0.12 U	< 0.18 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	13	< 0.13 U		< 0.17 U	0.57	< 0.13 U	0.85	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	0.25	< 0.11 U		< 0.15 U	0.26	< 0.12 U	0.19	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated	0.44	< 0.12 U		< 0.16 U	0.078 J	< 0.12 U	0.14	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated	0.25 T	< 0.22 U		< 0.29 U	< 0.038 U	< 0.23 U	< 0.03 U	< 0.36 U	< 0.2 U	< 0.29 U
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated	0.14	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	0.49	< 0.026		< 0.028	0.051	< 0.036	0.18	< 0.16	< 0.15	< 0.15
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	0.026	< 0.026		< 0.028	0.013	< 0.037	< 0.0065	< 0.17	< 0.16	< 0.15
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.0078	< 0.026		< 0.028	< 0.0068	< 0.037	< 0.0065	< 0.17	< 0.16	< 0.15
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.0074	< 0.025		< 0.027	< 0.0065	< 0.035	< 0.0062	< 0.16	< 0.15	< 0.15
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.0074	< 0.025		< 0.027	0.0096	< 0.035	< 0.0062	< 0.16	< 0.15	< 0.15
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.36	< 0.36		< 0.36	< 0.36	< 0.36	< 0.36	< 1.8	< 1.8	< 1.8
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated	< 0.03 U	< 0.21 U	< 0.22 U	< 0.038 U	< 0.036 U		0.033 J	< 0.34 U	< 0.19 U	< 0.036 U
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated	0.14 J	< 0.22 U	< 0.23 U	< 0.04 U	< 0.037 U		< 0.03 U	< 0.35 U	< 0.2 U	< 0.038 U
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	< 0.017 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U	< 0.02 U
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	0.13	< 0.11 U	< 0.12 U	< 0.02 U	0.028 J		0.036 J	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	0.39 J	< 0.45 U	< 0.46 U	< 0.08 U	< 0.075 UJ		0.072 J	< 0.72 U	< 0.4 U	< 0.076 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.061	0.11		0.02	0.018	0.11	0.015	0.17	0.098	0.019
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated	0.23	< 0.11 U	< 0.11 U	< 0.019 U	0.05 J		0.097	< 0.17 U	< 0.097 U	< 0.018 U
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated	0.11	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.059 J	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated	0.26	< 0.11 U	< 0.11 U	< 0.019 U	0.07 J		0.077	< 0.17 U	< 0.097 U	< 0.018 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated	0.18	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		0.021 J	< 0.16 U	< 0.091 U	< 0.017 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	0.055 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	0.055 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	0.14	< 0.11 U	< 0.11 U	< 0.019 U	0.026 J		0.033 J	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated	0.32	< 0.11 U	< 0.11 U	< 0.02 U	0.038 J		0.053 J	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated	1.2	< 0.11 U	< 0.11 U	< 0.019 U	0.06 J		0.091	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	0.11	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	0.047 J	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U	< 0.018 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	0.068 J	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.098 U	< 0.019 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated	0.042 J	< 0.11 U	< 0.12 U	< 0.02 U	0.034 J		0.041 J	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		0.028 J	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated	0.065 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		0.026 J	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated	0.11	< 0.1 U	< 0.11 U	< 0.018 U	0.018 J		0.049 J	< 0.16 U	< 0.092 U	< 0.018 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Nitrobenzene	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.14	< 0.11 U	0.24
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.15	< 0.12 U	0.41
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.2	< 0.12 U	0.44
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.029 J	< 0.11 U	0.071 J
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.29	< 0.13 U	0.92
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.16	< 0.11 U	0.64
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.025 J
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.059 J
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.022 J	< 0.12 U	0.065 J
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.16	< 0.12 U	0.5
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.076	< 0.11 U	0.24
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.091
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.076
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.047 J	< 0.11 U	0.15
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.023 J	< 0.11 U	0.064 J
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.048 J	< 0.12 U	0.14
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	1	< 0.13 U	3.7
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.029 J	< 0.1 U	0.08
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.042 J	< 0.13 U	0.067 J
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.19	< 0.12 U	0.54
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	2	< 0.13 U	5.3
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.022 J
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.18	< 0.12 U	0.49
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.023 J
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.097	< 0.12 U	0.77
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.024 J	< 0.12 U	0.05 J
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.1	< 0.12 U	0.24
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.14	< 0.12 U	0.3
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.069 J	< 0.12 U	0.12
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated	< 0.18 U	< 0.18 U	< 0.34 U		< 0.033 U	< 0.16 U	< 0.77 U	0.75	< 0.15 U	2.2
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	13	< 0.14 U	32
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.47	< 0.12 U	0.79
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	0.98	< 0.13 U	1.3
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated	< 0.29 U	< 0.29 U	< 0.55 U		< 0.053 U	< 0.26 U	< 1.3 UT	0.19	< 0.24 U	0.56 T
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.26	< 0.12 U	0.4
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.031	< 0.04	< 0.13		< 0.0086	< 0.034	< 0.033	0.37	< 0.0087	0.75
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.031	< 0.042	< 0.14		< 0.0089	< 0.035	< 0.034	0.034	< 0.0089	0.045
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.031	< 0.042	< 0.14		< 0.0089	< 0.035	< 0.034	< 0.012	< 0.0089	< 0.0076
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.03	< 0.04	< 0.13		< 0.0085	< 0.033	< 0.032	< 0.011	< 0.0085	< 0.0073
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.03	< 0.04	< 0.13		< 0.0084	< 0.033	< 0.032	0.013	< 0.0085	0.013
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.36	< 0.36	< 1.8	< 0.36	< 0.36	< 0.36	< 1.8	< 0.36	< 0.36	< 0.36
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated	< 0.27 U	< 0.12 U	< 0.53 U		< 0.051 U	< 0.25 U	< 1.2 U	< 0.04 U	< 0.23 U	< 0.035 U
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated	< 0.28 U	< 0.12 U	< 0.54 U		< 0.053 U	< 0.26 U	< 1.2 U	0.069 J	< 0.24 U	0.22
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 UJ	< 0.12 U	< 0.019 UJ
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.068 J	< 0.12 U	0.24
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated	< 0.58 U	< 0.25 U	< 1.1 U		< 0.11 U	< 0.52 U	< 2.5 U	0.35 J	< 0.48 U	0.85 J
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated	0.14	0.061	0.27		0.026	0.13	0.62	0.046	0.12	0.15
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.34	< 0.12 U	0.55
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.093	< 0.11 U	0.27
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.18	< 0.12 U	0.54
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.092	< 0.11 U	0.4
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.027 J	< 0.11 U	0.11
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.027 J	< 0.11 U	0.11
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.061 J	< 0.11 U	0.24
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.2	< 0.12 U	0.67
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.95	< 0.11 U	2.8
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.049 J	< 0.11 U	0.19
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.037 J	< 0.12 U	0.12
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.042 J	< 0.12 U	0.14
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.07 J	< 0.12 U	0.11
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.03 J
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.029 J	< 0.12 U	0.075 J
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.12 U	0.048 J
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.022 J	< 0.11 U	0.024 J
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.072 J	< 0.11 U	0.08
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.028 J	< 0.12 U	0.055 J
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.035 J	< 0.11 U	0.17

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated		< 0.19 U	< 0.2 U	< 0.17 U	< 0.16 U
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated		< 0.31 U	< 0.33 U	< 0.27 U	< 0.26 U
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated		< 0.028	< 0.024	< 0.039	< 0.055
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated		< 0.029	< 0.024	< 0.04	< 0.057
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated		< 0.029	< 0.024	< 0.04	< 0.056
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated		< 0.027	< 0.023	< 0.039	< 0.054
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.054
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated				< 0.36	< 0.36
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated		< 0.032 U	< 0.31 U	< 0.053 U	< 0.041 U
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated		< 0.034 U	< 0.32 U	< 0.055 U	< 0.043 U
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated		< 0.068 U	< 0.66 U	< 0.11 U	< 0.086 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated		0.017	0.16	0.027	0.021
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.16 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated			1.171	< 0.023 U	0.06 J	< 0.021 U	0.031 J	< 0.17 U	< 0.017 U	< 0.049 U	0.088 J
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U		< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated			0.098	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated			22.033	0.073 J	0.9	< 0.15 U	0.86	< 0.18 U	< 0.15 U	< 0.051 U	7.3
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated			2.63	< 0.022 U	0.095	< 0.14 U	0.078	< 0.17 U	< 0.14 U	< 0.048 U	0.23
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated			0.262	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.04 J
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated			1.467	< 0.022 U	< 0.017 U	< 0.14 U	0.025 J	< 0.17 U	< 0.14 U	< 0.048 U	0.16
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated			0.843	< 0.023 U	< 0.017 U	< 0.14 U	0.02 J	< 0.17 U	< 0.14 U	< 0.049 U	0.076 J
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated			0.117	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated			0.301	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated			0.405	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.045 J
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated			0.795	< 0.023 U	< 0.017 U	< 0.14 U	0.021 J	< 0.17 U	< 0.14 U	< 0.049 U	0.069 J
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated			18.288	0.098	0.16	< 0.14 U	0.53	< 0.17 U	< 0.14 U	< 0.048 U	1.8
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated			0.073	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated			0.081	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated			0.48	< 0.025 U	< 0.019 U	< 0.16 U	< 0.023 U	< 0.19 U	< 0.16 U	< 0.054 U	0.057 J
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated			4.26	< 0.022 U	0.21	< 0.14 U	0.12	< 0.17 U	< 0.14 U	< 0.048 U	0.45
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.035 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated			5.165	0.089	0.035 J	< 0.14 U	0.21	< 0.17 U	< 0.14 U	< 0.048 U	0.47
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated			0.565	< 0.022 U	0.018 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	0.064 J
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated			0.746	< 0.022 U	0.024 J	< 0.14 U	0.021 J	< 0.17 U	< 0.14 U	< 0.048 U	0.071 J
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated			0.582	< 0.022 U	0.025 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.066 J
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated			0.069	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated			0.674	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.082
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated			0.912	< 0.021 U	0.037 J	< 0.13 U	0.028 J	< 0.16 U	< 0.13 U	< 0.045 U	0.12
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated			1.819	< 0.022 U	0.12	< 0.14 U	0.063 J	< 0.17 U	< 0.14 U	< 0.048 U	0.16
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated			29	0.2	1.7	< 0.13 U	1.1	< 0.16 U	< 0.14 U	< 0.046 U	7.7
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated			0.399	< 0.021 U	0.018 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.051 J
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated			0.059	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated			0.861	< 0.022 U	0.035 J	< 0.14 U	0.021 J	< 0.17 U	< 0.14 U	< 0.047 U	0.071 J
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated			0.289	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.037 J
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated			1.549	< 0.022 U	0.033 J	< 0.14 U	0.039 J	< 0.17 U	< 0.14 U	< 0.047 U	0.15
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated			0.402	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.038 J
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated			0.085	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated			0.083	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated			0.016	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated			0.103	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated			0.158	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated			0.147	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated			0.421	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.052 J
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated			3.311	0.03 J	0.039 J	< 0.14 U	0.061 J	< 0.17 U	< 0.14 U	< 0.048 U	0.23
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated			0.054	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated			1.013	< 0.022 U	0.039 J	< 0.14 U	0.028 J	< 0.17 U	< 0.14 U	< 0.047 U	0.091
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated			1.276	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.1
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated			0.184	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated			0.027	< 0.021 U	0.031 J	< 0.13 U	0.027 J	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated			0.091	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated			0.696	< 0.023 U	0.024 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.062 J
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated			1.044	< 0.023 U	< 0.017 U	< 0.14 U	0.028 J	< 0.17 U	< 0.14 U	< 0.049 U	0.12

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated	0.13 J	0.13 J	0.078 J	0.12	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U	< 0.27 U
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.03 U	0.025 J	< 0.021 U	0.015 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	1.6	2.7	0.79	1.6	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	0.18	0.3	0.079	0.17	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.034 U	0.045 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	0.12	0.15	0.076 J	0.068 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	0.048 J	0.073 J	< 0.024 U	0.029 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	0.04 J	0.05 J	0.03 J	0.031 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	0.057 J	0.085	0.042 J	0.06 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	1.3	1.8	0.69	0.86	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 0.035 U	0.025 J	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 0.035 U	0.025 J	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	0.043 J	0.078 J	< 0.026 U	0.044 J	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.19 U	< 0.3 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	0.39	0.55	0.21	0.28	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	0.26	0.28	0.16	0.11	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	0.066 J	0.068 J	0.026 J	0.048 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	0.085	0.084	0.048 J	0.06 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	0.059 J	0.077	0.036 J	0.05 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.033 U	0.021 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	0.062 J	0.089	0.032 J	0.042 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	0.081	0.13	0.026 J	0.066 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	0.17	0.25	0.074 J	0.15	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	2.7	3.6	1.1	3	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	0.036 J	0.057 J	< 0.022 U	0.026 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.032 U	0.022 J	< 0.022 U	0.017 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	0.069 J	0.1	< 0.023 U	0.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	0.039 J	0.051 J	< 0.023 U	0.037 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	0.13	0.16	0.052 J	0.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	0.041 J	0.047 J	0.024 J	0.047 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.031 U	0.021 J	< 0.021 U	0.015 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.032 U	0.024 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 UT	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.03 U	0.024 J	< 0.021 U	0.02 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.031 U	0.028 J	< 0.021 U	0.017 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	0.045 J	0.056 J	< 0.022 U	0.049 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	0.16	0.18	0.089	0.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	0.12	0.18	< 0.023 U	0.09	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	0.14	0.16	0.066 J	0.11	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	0.032 J	0.054 J	< 0.022 U	0.028 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.034 U	0.019 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	0.06 J	0.08	0.035 J	0.07 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	0.1	0.1	0.05 J	0.067 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.11 J	< 0.051 U	< 0.017 U
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U	< 0.017 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	< 0.27 U	0.16	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	2.4	0.45	< 0.15 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.27	0.052 J	< 0.14 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.046 J	< 0.05 U	< 0.14 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.15	< 0.049 U	< 0.14 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.15	< 0.05 U	< 0.14 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.048 J	< 0.048 U	< 0.14 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.049 J	< 0.05 U	< 0.14 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.12	< 0.05 U	< 0.15 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	< 0.25 U	0.21	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	1.7	0.22	< 0.14 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.051 U	< 0.15 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.15 U	0.066 J	< 0.056 U	< 0.16 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.25 U	0.021 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.55	0.069 J	< 0.14 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.25 U	0.13	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.45	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.06 J	< 0.048 U	< 0.14 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.08	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.048 U	< 0.055 U	< 0.16 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.094	< 0.052 U	< 0.15 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.12	< 0.046 U	< 0.13 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.19	< 0.049 U	< 0.14 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.24 U	0.23	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	2.6	0.74	0.14 J
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.073	< 0.046 U	< 0.13 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.1	< 0.049 U	< 0.14 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.14	< 0.049 U	< 0.14 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.12 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.047 J	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.5	< 0.049 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.1	< 0.049 U	< 0.14 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.13	< 0.05 U	< 0.14 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.088	< 0.05 U	< 0.14 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.11	< 0.051 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					
Restricted - Residential																					
Protection of Groundwater																					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 2.2 U
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 UJ
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 0.39 U	< 0.032 U	0.15 J	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	< 0.36 UT	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	< 0.41 U	< 0.034 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.15 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U	< 2.7 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 UT
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 UT
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.39 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.16 U	< 2.6 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.019 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated	< 0.06 U			< 0.12 U	0.16 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.02 U
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated	< 0.057 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.21 U			< 0.11 U	0.03 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	< 0.24 U	< 0.13 U			2.9	0.13	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	< 0.23 U	< 0.12 U			0.35	0.018 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.23 U	< 0.12 U			0.066 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.23 U	< 0.12 U			0.29	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	< 0.23 U	< 0.12 U			0.088	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.24 U	< 0.13 U			0.03 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 0.23 U	< 0.12 U			0.037 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	< 0.23 U	< 0.12 U			0.063 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.24 U	< 0.12 U			0.098	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	< 0.23 U	< 0.12 U			3.2	0.17	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 0.24 U	< 0.13 U			0.023 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 0.24 U	< 0.13 U			0.028 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	< 0.26 U	< 0.14 U			0.083 J	< 0.017 U	< 0.031 U	< 0.025 U	< 0.045 U	< 0.15 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.23 U	< 0.12 U			0.5	0.018 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.23 U	< 0.12 U			1.3	0.036 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.22 U	< 0.12 U			0.093	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.23 U	< 0.12 U			0.099	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.23 U	< 0.12 U			0.076	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.22 U	< 0.12 U			0.02 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.26 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.24 U	< 0.13 U			0.11	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.22 U	< 0.11 U			0.13	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 UT			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 U			0.24	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.22 U	< 0.12 U			3.2	0.25	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	< 0.22 U	< 0.11 U			0.069 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.23 U	< 0.12 U			0.097	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.23 U	< 0.12 U			0.052 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.23 U	< 0.12 U			0.28	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.22 U	< 0.11 U			0.056 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.21 U	< 0.11 U			0.023 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.22 U	< 0.12 U			0.029 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.21 U	< 0.11 UT			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.21 U	< 0.11 U			0.025 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.21 U	< 0.11 U			0.053 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			0.044 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.22 U	< 0.11 U			0.044 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.23 U	< 0.12 U			0.45	0.13	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.22 U	< 0.11 U			0.02 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.23 U	< 0.12 U			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.23 U	< 0.12 U			0.19	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.22 U	< 0.11 U			0.037 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.23 U	< 0.12 U			0.033 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.23 U	< 0.12 U			0.097	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.24 U	< 0.12 U			0.2	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U

DRAFT

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated	0.1 J	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U	< 0.019 U
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	1.5	< 0.12 U		< 0.15 U	0.2	< 0.12 U	0.23	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	0.17	< 0.11 U		< 0.15 U	0.035 J	< 0.11 U	0.043 J	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	0.069 J	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	0.078 J	< 0.12 U	0.037 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.13	< 0.11 U	0.096	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	0.043 J	< 0.11 U		< 0.15 U	0.033 J	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	0.82	< 0.11 U		< 0.14 U	0.021 J	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	< 0.043 U	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	0.21	< 0.11 U		< 0.14 U	0.11	< 0.11 U	0.12	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	0.089	< 0.11 U		< 0.14 U	0.085	< 0.11 U	0.071 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	0.041 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	0.049 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	0.038 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.043 U	< 0.12 U		< 0.16 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	0.02 J	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	0.061 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801322631	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801322621	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801322621	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801322621	Not Excavated	0.13	< 0.11 U		< 0.14 U	0.044 J	< 0.11 U	0.042 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	2.4	< 0.11 U		< 0.14 U	0.15	< 0.11 U	0.21	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	0.071 J	< 0.11 U		< 0.14 U	0.038 J	< 0.11 U	0.047 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	0.088	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	0.037 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.026 J	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	0.038 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	0.091	< 0.11 U		< 0.14 U	0.07 J	< 0.11 U	0.04 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	0.082	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	0.11	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	0.062 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.022 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	0.059 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.02 J	< 0.18 U	< 0.1 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.074 J	< 0.12 U	0.15 J
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 UJ	< 0.11 U	0.028 J
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	1.1	< 0.12 U	3.4
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.23	< 0.12 U	0.46
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.065 J
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.099	< 0.12 U	0.26
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.23	< 0.12 U	0.092
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.052 J	< 0.12 U	0.035 J
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.082	< 0.11 U	0.038 J
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.03 J	< 0.12 U	0.067 J
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.1	< 0.12 U	0.1
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	2.1	< 0.12 U	3
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.025 J
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	0.028 J
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.7 U	0.038 J	< 0.13 U	0.071 J
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.043 J	< 0.12 U	0.75
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.54	< 0.12 U	1.1
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.099
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.046 J	< 0.12 U	0.11
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	0.1
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.028 J
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.043 J	< 0.12 U	0.12
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.15
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.24
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	1.4	< 0.11 U	3.6
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.087
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.02 J
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.065 J	< 0.12 U	0.12
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.023 J	< 0.12 U	0.05 J
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.12	< 0.12 U	0.29
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.025 J	< 0.11 U	0.061 J
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.026 J
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.03 J
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.016 J
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.034 J
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.06 J
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.054 J	< 0.11 U	0.049 J
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.023 J	< 0.11 U	0.067 J
Northern Athletic Field	MS-SLT-S62	SSHS-IRM5A2-SLT-S62-20220321	SSHS-IRM5A2-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.72	< 0.12 U	0.53
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.034 J
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.062 J	< 0.12 U	0.13
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.08	< 0.12 U	0.19
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.033 J
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.039 J
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.12
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.19

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.15 U
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.16 U	< 0.024 U	< 0.2 U	< 0.17 U	< 0.057 U	< 0.041 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated			0.127	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated			17.379	0.089	0.13	< 0.14 U	0.48	< 0.17 U	< 0.14 U	< 0.048 U	1.7
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated			0.178	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated			0.354	< 0.022 U	0.019 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	0.052 J
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated			4.558	< 0.026 U	0.2	< 0.16 U	0.14	< 0.2 U	< 0.16 U	< 0.055 U	0.43
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated			0.423	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	0.049 J
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated			0.12	< 0.022 U	0.017 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated			3.718	< 0.021 U	0.14	< 0.13 U	0.13	< 0.16 U	< 0.13 U	< 0.045 U	0.32
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated			0.732	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.072 J
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated			0.098	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated			13.972	0.033 J	0.16	< 0.13 U	0.49	< 0.16 U	< 0.14 U	< 0.047 U	1.3
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated			6.551	< 0.021 U	0.28	< 0.13 U	0.14	< 0.16 U	< 0.13 U	< 0.045 U	0.59
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated			76.652	0.092 J	2.6	< 0.25 U	2	< 0.31 U	< 0.26 U	< 0.088 U	6.8
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated			3.027	< 0.021 U	0.16	< 0.13 U	0.066 J	< 0.16 U	< 0.14 U	< 0.046 U	0.24
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated			6.777	< 0.021 U	0.14	< 0.13 U	0.17	< 0.16 U	< 0.13 U	< 0.045 U	0.63
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated			8.395	0.023 J	0.48	< 0.13 U	0.27	< 0.16 U	< 0.13 U	0.064 J	0.79
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated			8.532	0.025 J	0.27	< 0.14 U	0.31	< 0.17 U	< 0.14 U	< 0.049 U	0.81
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated			0.714	< 0.023 U	0.021 J	< 0.14 U	0.022 J	< 0.17 U	< 0.15 U	< 0.049 U	0.066 J
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated			1.787	< 0.01 U	0.032 J	< 0.017 U	0.024 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.17
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated			0.119	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.071 U	0.019 J
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated			0.1137	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	0.018 J
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated			1.642	< 0.01 U	0.014 J	< 0.017 U	0.057 J	< 0.021 U	< 0.012 U	< 0.059 U	0.15
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated			1.416	< 0.01 U	0.042 J	< 0.018 U	0.029 J	< 0.021 U	< 0.013 U	< 0.06 U	0.12
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated			0.0923	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated			0.0275	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated			0.055	< 0.01 U	0.021 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated			0.0663	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.016 J
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated			15.73	0.1 J	0.33 J	< 0.018 U	0.41	< 0.021 U	0.03 J	< 0.059 UT	1.4
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated			0.688	< 0.012 U	< 0.012 U	< 0.02 U	0.019 J	< 0.024 U	< 0.014 U	< 0.067 U	0.065
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated			0.3632	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.04
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated			0.0331	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated			1.126	< 0.02 U	0.066 J	< 0.13 U	0.024 J	< 0.15 U	< 0.13 U	< 0.044 U	0.095
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated			0.159	< 0.01 U	0.015 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated			0.172	< 0.011 U	0.026 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated			6.449	0.057 J	0.069 J	< 0.019 U	0.17 J	< 0.022 U	0.017 J	< 0.063 U	0.57
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated			0.524	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.051 J
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated			1.508	< 0.0099 U	0.022 JT	< 0.017 UT	0.021 JT	< 0.02 UT	< 0.012 U	< 0.057 U	0.13
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated			2.172	< 0.011 U	0.041 J	0.027 J	0.055 J	< 0.022 UT	0.047 J	< 0.061 U	0.11
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated			0.663	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.065 J
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated			0.22	< 0.023 U	0.06 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated			0.48	< 0.061 U	< 0.047 U	< 0.38 U	< 0.055 U	< 0.47 U	< 0.39 U	< 0.13 U	< 0.096 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated			0.686	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.058 J
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated			0.179	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated			0.123	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	0.018 J
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated			1.633	< 0.01 U	0.083 J	< 0.018 U	0.029 J	< 0.021 UT	0.068 J	< 0.059 U	0.06
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated			4.037	0.039 J	0.066 J	< 0.017 U	0.073 J	< 0.021 UT	0.29 J	< 0.058 U	0.12
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated			0.691	< 0.0098 U	0.09 J	< 0.017 U	0.013 J	< 0.02 UT	0.023 J	< 0.057 U	0.024 J
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated			3.543	< 0.0098 U	0.052 J	< 0.017 U	0.042 J	< 0.02 UT	< 0.012 U	< 0.057 U	0.23

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.04 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.032 U	0.027 J	< 0.022 U	0.025 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	0.41	2.4	1.4	1.1	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.033 U	0.036 J	< 0.023 U	0.032 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	0.044 J	0.055 J	< 0.022 U	0.042 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	0.37	0.52	0.17	0.37	< 0.16 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	0.041 J	0.068 J	< 0.025 U	0.033 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.033 U	0.036 J	< 0.023 U	0.02 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	0.35	0.43	0.16	0.26	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	0.074 J	0.096	0.029 J	0.042 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.03 U	0.025 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	1.1	1.2	0.47	0.65	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	0.66	0.88	0.32	0.53	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	6.8	8.2	2.8	8.1	< 0.26 U	< 0.026 U	< 0.052 U	< 0.75 U	< 0.3 U	< 0.49 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	0.29	0.42	0.18	0.27	< 0.14 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.16 U	< 0.25 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	0.61	0.79	0.34	0.43	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	0.81	0.98	0.35	0.84	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	0.72	0.78	0.27	0.66	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	0.073 J	0.092	0.025 J	0.079 J	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	0.17	0.26	0.094	0.099 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.01 UT	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.011 U	0.016 J	< 0.0084 U	< 0.013 U	< 0.034 U	< 0.015 U	< 0.0078 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	0.01 J	0.019 J	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	0.13 T	0.17	0.075	0.087 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.01 U	< 0.01 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	0.12	0.18	0.076	0.091 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	0.0097 J	0.016 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0089 U	0.0087 J	< 0.0065 U	0.012 J	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	0.045 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	0.021 J	< 0.014 U	< 0.017 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	1.3 T	1.8	0.72	0.84	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	0.048	0.078	0.029 J	0.033 J	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.0098 U	< 0.0096 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	0.017 J	0.02 J	0.0092 J	0.012 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	0.11	0.17	0.061 J	0.092	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	0.073 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.0098 U	< 0.0096 U	< 0.0072 U	0.095 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	0.48	0.66	0.29	0.25 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	0.042 J	0.059 J	< 0.023 U	0.037 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	0.11 T	0.19 T	0.066 T	0.087 JT	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	0.14	0.2	0.076	0.4	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	0.067 J	0.081	0.03 J	0.064 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	0.16	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.092 U	< 0.052 U	< 0.064 U	< 0.046 U	< 0.39 U	< 0.039 U	< 0.079 U	< 1.1 U	< 0.45 U	< 0.73 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	0.062 J	0.085	0.032 J	0.055 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	0.035 J	0.036 J	< 0.021 U	0.049 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	0.012 J	0.016 J	< 0.0074 U	0.013 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	0.041	0.11	0.032 J	0.034 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	0.063	0.11	0.028 J	0.035 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	0.012 J	0.027 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	0.27	0.73	0.24	0.19 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.3 U	< 0.021 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.051 U	< 0.059 U	< 0.17 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.25 U	0.26	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	1.6	0.13	< 0.14 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.045 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.29 U	0.031 J	< 0.12 U	< 0.16 U	< 0.02 U	< 0.16 U	< 0.15 U	0.46	0.088 J	< 0.16 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.055 J	< 0.053 U	< 0.15 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.24 U	0.025 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.35	0.072 J	< 0.13 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.078 J	< 0.052 U	< 0.15 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.24 U	0.036 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.1	0.15	< 0.14 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.24 U	0.038 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.67	0.16	< 0.13 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.46 U	0.59	< 0.19 U	< 0.25 U	< 0.033 U	< 0.26 U	< 0.24 U	6.3	1.7	0.41 J
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.3	0.077	< 0.14 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.24 U	0.023 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.6	0.097	< 0.13 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.24 U	0.045 J	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.82	0.21	< 0.13 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.25 U	0.048 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.68	0.14	< 0.14 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.06 J	< 0.051 U	< 0.15 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.17 J	0.039	0.016 J
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.067 U	< 0.016 U	< 0.076 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	0.014 J	< 0.019 U	< 0.014 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.014 J	< 0.017 U	< 0.013 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.13 J	0.021 J	< 0.012 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.14 J	0.036	< 0.012 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.012 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0073 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.056 U	0.13 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	1.4	0.26	0.1 J
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.064 U	< 0.016 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	0.061 J	< 0.018 U	< 0.014 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0070 U	< 0.018 U	< 0.014 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.055 J	< 0.015 U	< 0.012 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.0061 J	< 0.015 U	< 0.012 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.13	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.059 U	0.07 J	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.58	0.081	0.053 J
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.095	< 0.049 U	< 0.14 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.054 U	< 0.013 UT	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 UT	< 0.012 U	0.16 JT	0.032 JT	0.014 J
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.058 U	0.021 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.15 J	0.082	0.036 J
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.08	< 0.046 U	< 0.13 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.69 U	< 0.05 U	< 0.28 U	< 0.37 U	< 0.049 U	< 0.39 U	< 0.35 U	0.48	< 0.14 U	< 0.39 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.096	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.012 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.056 U	0.014 J	< 0.063 U	< 0.02 U	0.054 J	< 0.013 U	< 0.013 U	0.12 J	0.03 J	0.1 J
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.054 U	0.058 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.22 J	0.029 J	0.71
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	0.042 J	< 0.012 U	< 0.012 U	0.057 J	< 0.015 U	0.032 J
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.053 U	0.037 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.46	0.057	0.016 J

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.43 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.79 U	< 0.18 U	< 2.9 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.36 U	< 0.029 U	0.27 BJ	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.42 U	< 0.034 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.26 U	< 0.77 U	< 0.17 U	< 2.8 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.36 U	< 0.03 U	0.22 J	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.35 U	< 0.029 U	0.15 J	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.66 U	< 0.055 U	< 0.25 U	< 0.24 U	< 0.28 U	< 0.31 U	< 0.41 U	< 1.2 U	< 0.28 U	< 4.4 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.33 U	< 0.028 U	0.13 J	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.065 U	< 0.028 U	< 0.014 U	< 0.051 U	< 0.098 U	< 0.016 U	< 0.023 U	< 0.18 U	< 0.031 U	< 0.21 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	0.14 J	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	0.033 J	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	0.037 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	0.046 J	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.03 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	0.044 J	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.052 U	< 0.022 UT	< 0.011 U	< 0.041 UT	< 0.079 U	< 0.013 UT	< 0.018 UT	< 0.14 UT	< 0.025 U	< 0.17 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.99 U	< 0.082 U	< 0.37 U	< 0.36 U	< 0.42 U	< 0.47 U	< 0.62 U	< 1.8 U	< 0.41 U	< 6.6 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.27 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U	< 0.16 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.22 U	< 0.12 U			0.036 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.23 U	< 0.12 U			2.5	0.15	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.23 U	< 0.12 U			0.06 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.22 U	< 0.12 UT			0.054 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.27 U	< 0.14 U			0.63	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.16 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.25 U	< 0.13 UT			0.06 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.23 U	< 0.12 UT			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.23 U	< 0.12 UT			0.035 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.22 U	< 0.11 UT			0.49	0.026 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.22 U	< 0.12 UT			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.24 U	< 0.13 UT			0.13	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.21 U	< 0.11 UT			0.037 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.22 U	< 0.12 U			3.4	0.089	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.22 U	< 0.11 U			0.76	0.031 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.42 U	< 0.22 U			11	0.26	< 0.051 U	< 0.041 U	< 0.072 U	< 0.25 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.22 U	< 0.12 U			0.32	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.22 U	< 0.11 U			1.1	0.041 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.22 U	< 0.11 U			0.98	0.042 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.23 U	< 0.12 U			1.6	0.047 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.24 U	< 0.12 U			0.087	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.038 U		< 0.031 U		0.24 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.046 U		< 0.038 U		0.024 J	< 0.013 U	< 0.02 U	< 0.0092 U	< 0.038 U	< 0.015 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.038 U		< 0.031 U		0.28 J	0.015 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.039 U		< 0.032 U		0.18 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.039 U		< 0.032 U		0.013 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.038 U		< 0.031 U		0.016 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.039 U		< 0.031 U		2.4	0.13 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.044 U		< 0.036 U		0.12 J	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.02 U	< 0.0088 U	< 0.036 U	< 0.014 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.038 U		< 0.03 U		0.058 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.038 U		< 0.031 U		0.014 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	0.13	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.039 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.041 U		< 0.033 U		1	0.066 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	< 0.23 U	< 0.12 U			0.074 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		0.22 J	< 0.01 U	< 0.016 U	< 0.0074 UT	< 0.03 U	< 0.012 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.04 U		< 0.032 U		0.16 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			0.09	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.63 U	< 0.33 U			< 0.056 U	< 0.042 U	< 0.076 U	< 0.062 U	< 0.11 U	< 0.38 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.21 U	< 0.11 U			0.095	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.21 U	< 0.11 U			0.03 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.041 U		< 0.033 U		0.019 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.038 U		< 0.031 U		0.15 J	0.03 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.038 U		< 0.03 U		0.16 J	0.093 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.037 U		< 0.03 U		0.051 J	0.017 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.037 U		< 0.03 U		0.41	0.011 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.046 U	< 0.13 U		< 0.17 U	< 0.022 U	< 0.13 U	< 0.018 U	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	1	< 0.11 U		< 0.15 U	0.063 J	< 0.11 U	0.12	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	0.3	< 0.13 U		< 0.17 U	0.081 J	< 0.13 U	0.15	< 0.2 U	< 0.11 U	< 0.17 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	0.018 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	0.24	< 0.1 U		< 0.14 U	0.036 J	< 0.11 U	0.11	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	0.041 J	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	0.59	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.05 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	0.47	< 0.1 U		< 0.14 U	0.065 J	< 0.11 U	0.13	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	6.8	< 0.2 U		< 0.27 U	0.47	< 0.21 U	1.7	< 0.32 U	< 0.18 U	< 0.26 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	0.25	< 0.11 U		< 0.14 U	0.057 J	< 0.11 U	0.094	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	0.42	< 0.1 U		< 0.14 U	0.031 J	< 0.11 U	0.059 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	0.68	< 0.1 U		< 0.14 U	0.089	< 0.11 U	0.16	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	0.62	< 0.11 U		< 0.15 U	0.048 J	< 0.11 U	0.14	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	0.072 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	0.16	< 0.013 U		< 0.1 U	0.044 J	< 0.022 U	0.051 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.017 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.027 U	< 0.0074 U	< 0.033 U	< 0.1 U	< 0.049 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	0.031 J	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	0.1	< 0.013 U		< 0.1 U	0.012 J	< 0.022 U	0.017 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	0.14	< 0.013 U		< 0.1 U	0.02 J	< 0.023 U	0.035 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	1	< 0.013 U		< 0.1 U	0.11 J	< 0.022 U	0.17 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	0.04 J	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.013 J	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0071 U	< 0.031 U	< 0.098 U	< 0.047 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	0.076	< 0.1 U	< 0.1 U	< 0.13 U	0.02 J		0.028 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	0.086	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	0.077	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	0.29	< 0.014 U		< 0.11 U	0.058 J	< 0.024 U	0.085 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.021 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	0.14	< 0.013 UT		< 0.1 UT	0.018 JT	< 0.022 U	0.042 JT	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	0.42	< 0.014 U		< 0.11 U	0.14 J	< 0.023 U	0.099 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	0.051 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	0.06 J	< 0.11 U		< 0.15 U	0.025 J	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.11 U	< 0.3 U		< 0.4 U	< 0.051 U	< 0.31 U	< 0.041 U	< 0.48 U	< 0.27 U	< 0.4 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	0.045 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	0.067	< 0.013 U		< 0.1 U	0.4	0.23 J	0.47	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	0.057	< 0.013 U		< 0.1 U	1.8	0.036 J	1.1	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	0.027 J	< 0.013 U		< 0.1 U	0.12 J	< 0.022 U	0.24 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	0.31	< 0.013 U		< 0.099 U	0.035 J	< 0.021 U	0.063 J	< 0.026 U	< 0.081 U	< 0.039 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.17 U	< 0.17 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	< 0.025 U	< 0.14 U	< 0.022 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.039 J
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	< 0.02 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	1.9	< 0.12 U	2.4
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	0.05 J
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.062 J
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	0.22	< 0.14 U	0.71
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.042 J	< 0.13 U	0.057 J
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.029 J
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.26	< 0.11 U	0.52
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.05 J	< 0.12 U	0.12
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.036 J
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.85	< 0.11 U	2.5
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.28	< 0.11 U	0.93
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.26 U	< 0.26 U	< 0.5 U		< 0.048 U	< 0.24 U	< 1.1 U	4.3	< 0.21 U	9.8
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.13	< 0.11 U	0.39
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.39	< 0.11 U	1.1
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.34	< 0.11 U	1.1
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.43	< 0.12 U	1.3
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.047 J	< 0.12 U	0.091
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.11 J	< 0.013 U	0.2 J
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.035 U	< 0.088 U	0.021 J	< 0.016 U	0.025 J
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.0077 J	< 0.014 U	0.014 J
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.17 J	< 0.013 U	0.24 J
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.079 J	< 0.013 U	0.19 J
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.0096 J	< 0.013 U	0.014 J
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.019 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	0.0068 J	< 0.012 U	< 0.0083 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.01 J	< 0.013 U	< 0.0087 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.012 J	< 0.013 U	0.015 J
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	1.6	< 0.013 U	2.2
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.034 U	< 0.084 U	0.082 J	< 0.015 U	0.1 J
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 U	< 0.0072 U	< 0.015 U	< 0.01 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.078 J	< 0.013 U	0.074 J
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.013 J
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.04 J	< 0.11 U	0.17
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.77	< 0.014 U	1.1
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.094	< 0.11 U	0.072 J
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.019 UT	< 0.035 UT	< 0.057 U		< 0.025 U	< 0.029 UT	< 0.071 U	0.12 JT	< 0.013 UT	0.19 J
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	0.15 J	< 0.014 U	0.13 J
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.054 J	< 0.11 U	0.081
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.39 U	< 0.39 U	< 0.75 U		< 0.072 U	< 0.35 U	< 1.7 U	< 0.057 U	< 0.32 U	< 0.05 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.064 J	< 0.11 U	0.094
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.029 J
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.012 J	< 0.014 U	0.021 J
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.35 J	< 0.013 U	0.11 J
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	1.7	< 0.013 U	0.21 J
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.17 J	< 0.013 U	0.053 J
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.14 J	< 0.013 U	0.39

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated		< 0.28 U	< 0.3 U	< 0.25 U	< 0.24 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated		< 0.013 U	< 0.029 U	< 0.044 U	< 0.055 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.052 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-4-6	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated		< 0.42 U	< 0.44 U	< 0.37 U	< 0.35 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated			1.372	< 0.01 UT	0.094 JT	< 0.017 UT	0.026 JT	< 0.021 UT	0.027 JT	< 0.058 U	0.076 T
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated			1.311	< 0.01 U	0.035 J	< 0.018 U	< 0.011 U	< 0.021 U	0.025 J	< 0.06 U	< 0.013 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated			4.803	0.077	0.031 J	< 0.13 U	0.19	< 0.16 U	< 0.14 U	< 0.047 U	0.38
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated			0.585	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.057 J
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated			0.402	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.045 J
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated			0.0359	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.016 J
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated			2.06	< 0.1 U	0.13 J	< 0.18 U	< 0.11 U	< 0.21 U	< 0.12 U	< 0.59 U	< 0.13 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated			0.368	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.027 J
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated			9.979	0.011 J	0.12 J	< 0.018 U	0.23 J	< 0.022 U	0.019 J	< 0.061 U	0.91
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated			20.99	< 0.011 U	0.43	< 0.019 U	0.56	< 0.023 U	0.057 J	< 0.063 U	1.6
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated			11.172	0.015 J	0.28 J	< 0.018 U	0.22 J	< 0.021 U	0.052 J	< 0.06 U	0.86
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated			22.005	0.025 J	0.55	< 0.019 U	0.44	< 0.022 U	0.093 J	< 0.063 U	1.8
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated			86.05	0.34 J	1.7	< 0.018 U	3.5	< 0.022 U	0.26 J	< 0.061 U	7.4
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated			1.883	< 0.022 U	< 0.016 U	< 0.13 U	0.026 J	< 0.16 U	< 0.14 U	< 0.046 U	0.12
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.059 UT	< 0.013 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated			0.0224	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.013 J
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated			0.1279	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.015 J
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated			0.0692	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.015 J
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated			0.0526	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.016 J
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated			0.1375	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.021 J
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated			0.0194	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.013 J
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated			0.01	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated			0.361	0.011 J	0.011 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.033 J
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated			0.0395	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.014 J
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated			1.5022	< 0.0098 U	< 0.0098 U	< 0.017 U	0.057 J	< 0.02 U	< 0.012 U	< 0.057 U	0.13
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated			0.0083	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated			0.145	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.019 J
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated			0.355	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.034 J
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated			0.243	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.027 J
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated			0.248	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.025 J
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated			1.363	< 0.01 U	0.019 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.083
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated			2.287	0.013 J	0.09 J	< 0.018 U	0.042 J	< 0.021 U	< 0.013 U	< 0.06 U	0.17
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated			0.228	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.029 J
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.069 U	< 0.015 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated			0.0084	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated			3.819	< 0.023 U	0.2	< 0.14 U	0.11	< 0.17 U	< 0.15 U	< 0.05 U	0.28

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	0.046 T	0.14 T	0.036 T	0.044 JT	< 0.027 UT	< 0.012 UT	< 0.0063 UT	< 0.018 UT	< 0.014 UT	< 0.016 UT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	0.097 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	0.34	0.39	0.14	0.28	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	0.049 J	0.097	< 0.021 U	0.038 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	0.038 J	0.036 J	0.026 J	0.038 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.096 U	< 0.093 U	< 0.07 U	0.25 J	< 0.28 U	< 0.12 U	< 0.065 U	< 0.19 U	< 0.14 U	< 0.17 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	0.019 J	0.04	0.015 J	0.027 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	0.84	1.2	0.45	0.59	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	1.5	2.3	0.83	1.2	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	0.92	1.4	0.54	0.76	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	1.8	2.9	1.1	1.4	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	6.8	8	3.2	2.4	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	0.13	0.19	0.074 J	0.18	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.0092 U	0.011 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.0090 U	0.012 J	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.01 U	0.016 J	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	0.012 J	0.025 J	0.011 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	0.022 J	0.043	0.019 J	0.017 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	0.088	0.13	0.049	0.064 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	0.015 J	0.017 J	< 0.0068 U	0.03 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	0.031 J	0.047	0.016 J	0.037 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	0.022 J	0.029 J	0.011 J	0.019 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 UT	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	0.022 J	0.032 J	0.014 J	0.017 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	0.096	0.21	0.082	0.07 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.0098 UT	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.0096 UT	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.0094 UT	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.0097 UT	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.0091 UT	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.0095 UT	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	0.19 T	0.32	0.13	0.18 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	0.018 J	0.027 J	0.011 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.011 U	< 0.011 U	< 0.0082 U	< 0.012 U	< 0.033 U	< 0.015 U	< 0.0076 U	< 0.022 U	< 0.017 U	< 0.02 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	0.34	0.38	0.21	0.35	< 0.15 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.054 U	< 0.013 UT	0.071 JT	< 0.02 UT	0.059 JT	< 0.012 UT	< 0.012 UT	0.17 JT	0.033 JT	0.026 JT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	0.024 J
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.24 U	0.063 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.37	0.065 J	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.066 J	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.048 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.059 U	< 0.014 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.0099 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.56 U	< 0.14 U	< 0.64 U	< 0.2 U	< 0.17 U	< 0.13 U	< 0.13 U	< 0.061 U	< 0.16 U	< 0.12 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.032 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.058 U	0.053 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.86	0.12	0.072 J
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.06 U	0.25 J	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	1.5	0.22	0.24 J
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.057 U	0.094 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.83	0.14	0.15 J
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.059 U	0.18 J	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	1.7	0.27	0.26 J
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.057 U	1.2	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	6.6	0.63	1.3
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.32	< 0.048 U	< 0.14 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 UT	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0069 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0092 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.0096 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.02 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0064 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.038 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0082 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.053 U	0.041 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.13 J	0.022 J	0.015 J
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.015 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.038 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.025 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.054 U	0.026 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.17 J	0.027 J	0.012 J
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.057 U	0.015 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.2 J	0.046	0.013 J
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.026 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.065 U	< 0.016 U	< 0.074 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0071 U	< 0.018 U	< 0.014 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.26 U	0.045 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.33	0.076 J	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.053 UT	< 0.022 UT	< 0.011 UT	< 0.042 UT	< 0.079 UT	< 0.013 UT	< 0.019 UT	< 0.14 UT	< 0.025 UT	< 0.17 UT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.54 U	< 0.23 U	< 0.12 U	< 0.43 U	< 0.81 U	< 0.14 U	< 0.19 U	< 1.5 U	< 0.26 U	< 1.8 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 UT	< 0.13 U	< 2.1 UT
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	0.1 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.063 U	< 0.027 U	< 0.013 U	< 0.05 U	< 0.095 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.21 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.038 UT		< 0.031 UT		0.14 JT	< 0.01 UT	< 0.017 UT	< 0.0074 UT	< 0.031 UT	< 0.012 UT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.039 U		< 0.032 U		0.18 J	0.067 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	0.73	0.067 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.092	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	0.06 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.39 U		< 0.31 U		0.3 J	< 0.1 U	< 0.17 U	< 0.076 U	< 0.31 U	< 0.12 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.041 U		< 0.034 U		0.04 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.04 U		< 0.032 U		1.7	0.038 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.041 U		< 0.033 U		3.7	0.11 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.039 U		< 0.032 U		1.6	0.047 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.041 U		< 0.033 U		3.3	0.07 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.039 U		< 0.032 U		16	0.88	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.22 U	< 0.12 U			0.18	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.039 U		< 0.031 UT		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 UT
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.037 U		< 0.03 UT		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 UT
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.038 U		< 0.031 U		0.019 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.038 U		< 0.031 U		0.039 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.037 U		< 0.03 U		0.26 J	0.025 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.037 U		< 0.03 U		0.017 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.037 U		< 0.03 U		0.048 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0072 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.038 U		< 0.031 U		0.038 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.037 UT		< 0.03 U		< 0.012 U	< 0.01 UT	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.04 U		< 0.033 U		0.034 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.038 U		< 0.031 U		0.2 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.039 U		< 0.032 U		0.25 J	0.015 J	< 0.017 UT	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		0.039 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.045 U		< 0.037 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0089 U	< 0.037 U	< 0.014 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.24 U	< 0.12 U			0.55	0.024 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U

DRAFT

												Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.5	0.33				0.33	12			
Restricted - Residential												0.5	100				100	100			
Protection of Groundwater												8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	0.071 T	< 0.013 UT		< 0.1 UT	0.099 JT	0.025 JT	0.29 JT	< 0.027 UT	< 0.083 UT	< 0.04 UT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	0.16	< 0.013 U		< 0.1 U	0.052 J	< 0.023 U	0.027 J	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	0.23	< 0.11 U	< 0.11 U	< 0.14 U	0.036 J		0.044 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.1 U	< 0.13 U	0.034 J		0.037 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	0.43	< 0.13 U		< 1 U	< 0.1 U	< 0.22 U	< 0.062 U	< 0.27 U	< 0.85 U	< 0.41 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	0.054	< 0.014 U		< 0.11 U	0.013 J	< 0.024 U	0.042 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	0.82	< 0.014 U		< 0.11 U	0.054 J	< 0.023 U	0.25 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	1.6	< 0.014 U		< 0.11 U	0.17 J	0.047 J	0.67	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	1	< 0.014 U		< 0.11 U	0.19 J	0.049 J	0.68	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	2	0.014 J		< 0.11 U	0.32 J	0.046 J	1	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	3.5	0.038 J		< 0.11 U	0.77	0.12 J	1.8	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	0.16	< 0.11 U		< 0.14 U	0.056 J	< 0.11 U	0.063 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.033 U	< 0.095 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.013 J	< 0.022 U	0.044 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	0.048	< 0.013 U		< 0.1 U	0.023 J	< 0.022 U	0.022 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	0.06	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	0.0072 J	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0083 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	0.014 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	0.029 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	0.016 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	0.022 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	0.091	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.014 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 UT	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 UT	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 UT	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 UT	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 UT	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	0.24	< 0.014 U		< 0.11 U	0.022 JT	< 0.023 U	0.031 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.016 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U	< 0.032 U	< 0.099 U	< 0.048 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.0084 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	0.28	< 0.11 U		< 0.15 U	0.081	< 0.12 U	0.099	< 0.18 U	< 0.1 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.019 UT	< 0.035 UT	< 0.057 UT		< 0.025 UT	< 0.029 UT	< 0.072 UT	0.16 JT	< 0.013 UT	0.14 JT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.33 J	< 0.013 U	0.45
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.71	< 0.11 U	0.79
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.058 J	< 0.11 U	0.091
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.048 J	< 0.11 U	0.063 J
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	0.01 J
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.2 U	< 0.36 U	< 0.58 U		< 0.26 U	< 0.29 U	< 0.74 U	0.4 J	< 0.13 U	0.68 J
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.034 J	< 0.014 U	0.038 J
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	0.56	< 0.014 U	1.4
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.032 U	< 0.079 U	2.4	< 0.014 U	2.8
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.76	< 0.013 U	1.4
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	1.5	< 0.014 U	2.7
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	13	0.14 J	12
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.1	< 0.11 U	0.34
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.0094 J
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.029 U	< 0.071 U	0.024 J	< 0.013 U	0.012 J
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0060 U	< 0.012 U	0.015 J
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	0.011 J
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.0095 J	< 0.013 U	0.02 J
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	0.01 J	< 0.014 U	< 0.0094 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.026 J	< 0.013 U	0.043 J
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.0075 J	< 0.013 U	0.0098 J
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.28 J	< 0.013 U	0.2 J
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.018 J
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.029 J	< 0.013 U	0.046 J
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.021 J	< 0.013 U	0.037 J
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.023 J	< 0.014 U	0.034 J
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.15 J	< 0.013 U	0.17 J
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.15 J	< 0.013 U	0.31 J
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.071 U	0.039 J	< 0.013 U	0.039 J
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.086 U	< 0.0073 U	< 0.015 U	< 0.01 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.27	< 0.12 U	0.52

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 UT	< 0.045 UT
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated		< 0.11 U	< 0.24 U	< 0.37 U	< 0.46 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated		< 0.013 U	< 0.028 U	< 0.043 U	< 0.054 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated			0.191	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.031 J
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated			0.058	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated			0.1424	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.019 J
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated			2.403	0.016 J	0.013 J	< 0.017 U	0.05 J	< 0.02 U	< 0.012 U	< 0.057 U	0.23
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated			0.473	< 0.0099 U	0.015 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.047
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated			0.1737	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.023 J
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated			0.067	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated			0.109	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.019 J
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated			0.745	< 0.011 U	< 0.011 U	< 0.019 U	0.018 J	< 0.023 UT	< 0.013 U	< 0.064 U	0.077
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated			0.3184	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.032 J
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated			0.761	< 0.011 U	< 0.011 U	< 0.018 U	0.014 J	< 0.022 U	< 0.013 U	< 0.061 U	0.081
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated			7.484	0.13 J	< 0.011 U	< 0.019 U	0.28 J	< 0.022 U	0.017 J	< 0.062 U	0.7
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated			0.456	< 0.011 U	0.014 J	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.046
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated			0.745	< 0.011 U	0.014 J	< 0.018 U	0.012 J	< 0.022 UT	< 0.013 U	< 0.062 U	0.071
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated			0.0564	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.014 J
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated			0.021	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated			0.2175	< 0.0095 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.055 U	0.025 J
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated			0.118	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	0.02 J
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated			0.433	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.049
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated			0.1462	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	0.018 J
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated			0.572	< 0.01 U	< 0.01 U	< 0.018 U	0.012 J	< 0.021 UT	< 0.013 U	< 0.06 U	0.062
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated			0.138	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.02 J
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated			0.2905	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.031 J
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated			0.0436	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.015 J
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated			0.1503	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.058 U	0.02 J
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated			0.645	< 0.01 U	< 0.01 U	< 0.017 U	0.014 J	< 0.021 U	< 0.012 U	< 0.059 U	0.067
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated			53.87	0.37 J	1.1	< 0.019 U	2.9	< 0.022 U	0.21 J	< 0.063 U	3.9
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated			0.0289	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.013 J
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated			0.081	< 0.0096 U	< 0.0097 UT	< 0.017 UT	< 0.01 UT	< 0.02 UT	< 0.012 U	< 0.056 U	0.018 J
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated			0.262	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.037
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated			0.668	< 0.01 U	0.032 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.065
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated			4.954	0.011 J	0.17 J	< 0.019 U	0.092 J	< 0.023 U	0.033 J	< 0.064 U	0.38
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated			0.0065	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated			1.583	0.02 J	0.011 J	< 0.018 U	0.043 J	< 0.021 U	< 0.013 U	< 0.06 U	0.13
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated			0.163	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.024 J
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated			0.0996	< 0.0095 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.055 U	0.016 J
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated			0.556	< 0.01 U	< 0.01 U	< 0.017 U	0.014 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.048
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated			0.133	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	0.024 J
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated			0.1081	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.021 J
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated			0.0097	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated			0.0188	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated			0.0392	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	0.012 J
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated			0.14	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	0.018 J

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.03 U	0.036 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.029 U	0.02 J	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	0.013 J	0.018 J	0.0070 J	0.011 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	0.17	0.26	0.092	0.11 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	0.045	0.059	0.032 J	0.03 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	0.016 J	0.024 J	0.0093 J	0.015 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.029 U	0.018 J	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	0.012 J	0.016 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	0.058	0.082	0.029 J	0.034 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	0.025 J	0.043	0.016 J	0.02 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	0.065	0.079	0.035 J	0.033 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	0.49	0.66	0.28	0.22 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	0.037 J	0.059	0.024 J	0.031 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	0.068	0.097	0.035 J	0.049 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.0093 U	0.011 J	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.01 U	0.011 J	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	0.019 J	0.027 J	0.02 J	0.018 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	0.014 J	0.022 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	0.035 J	0.053	0.018 J	0.019 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	0.011 J	0.016 J	0.0072 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	0.052	0.07	0.026 J	0.029 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	0.025 J	0.032 J	0.014 J	0.019 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.0095 U	0.01 J	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	0.014 J	0.018 J	0.01 J	0.01 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	0.05	0.072	0.026 J	0.035 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	3.2	3.7	1.8	1.6	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 UT	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.0090 UT	< 0.0087 U	< 0.0066 UT	< 0.01 UT	< 0.026 UT	< 0.012 UT	< 0.0061 U	< 0.018 U	< 0.013 UT	< 0.016 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	0.02 J	0.032 J	0.02 J	0.016 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	0.078	0.11	0.036 J	0.054 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	0.4	0.65	0.23	0.21 J	< 0.03 U	< 0.014 U	< 0.0071 U	0.26 J	< 0.015 U	0.072 J
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	0.12	0.16	0.053	0.081 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	0.017 J	0.025 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	0.034 J	0.051	0.021 J	0.026 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	0.015 J	0.022 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	0.012 J	0.019 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	0.013 J	0.021 J	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.018 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.054 U	0.026 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.24 J	0.043	0.014 J
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.05 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.019 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.018 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.063 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.039 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.1 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.059 U	0.097 J	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.66	0.077	0.053 J
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.044 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.082 J	< 0.016 U	< 0.013 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0084 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.01 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	0.024 J	< 0.014 U	< 0.011 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.014 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.046 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.015 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.052 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.011 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.026 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0076 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.016 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.065 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.059 U	0.55	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	3.3	0.39	1.5
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0067 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.053 UT	< 0.013 UT	< 0.06 U	< 0.019 UT	< 0.016 U	< 0.012 UT	< 0.012 U	0.012 JT	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.026 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.07 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.061 U	0.049 J	0.16 J	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.5	0.063	0.072 J
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0065 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.13 J	0.024 J	0.012 J
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.018 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.052 UT	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	0.0089 J	< 0.014 U	< 0.011 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.044 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.013 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.011 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0068 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0078 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.016 J	< 0.015 U	< 0.012 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.051 U	< 0.022 UT	< 0.011 U	< 0.04 UT	< 0.077 UT	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.21 U	< 0.11 U			0.05 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.2 U	< 0.11 U			0.02 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.038 U		< 0.031 U		0.017 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.037 U		< 0.03 U		0.36	0.013 J	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.038 U		< 0.031 U		0.059 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.038 U		< 0.031 U		0.023 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.2 U	< 0.1 U			0.026 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.039 U		< 0.032 U		0.024 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.041 U		< 0.034 U		0.13 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.038 U		< 0.031 U		0.049 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.04 U		< 0.032 U		0.13 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.041 U		< 0.033 U		1.2	0.1 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.041 U		< 0.033 U		0.061 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.04 U		< 0.033 U		0.11 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.038 U		< 0.031 U		0.013 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.036 U		< 0.029 U		0.019 J	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.037 U		< 0.03 U		0.018 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.039 U		< 0.032 U		0.077 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.039 U		< 0.032 U		0.02 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.039 U		< 0.032 U		0.085 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.039 U		< 0.032 U		0.032 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.038 U		< 0.031 U		0.046 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.037 U		< 0.03 U		0.02 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.038 U		< 0.031 U		0.1 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.041 U		< 0.033 U		9.3	2.2	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.036 U		< 0.03 U		0.021 J	< 0.0099 U	< 0.016 UT	< 0.0072 UT	< 0.03 U	< 0.012 UT
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.039 U		< 0.031 U		0.042 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.039 U		< 0.032 U		0.088 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.042 U		< 0.034 U		0.79	0.038 J	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.039 U		< 0.032 U		0.24 J	0.017 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.037 U		< 0.03 U		0.029 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.036 U		< 0.029 U		0.013 J	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.038 U		< 0.031 U		0.095 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		0.024 J	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.039 U		< 0.032 U		0.021 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.038 U		< 0.031 U		0.024 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0074 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	0.17	< 0.013 U		< 0.1 U	0.011 J	< 0.022 U	0.029 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	0.058	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	0.015 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0064 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	0.04	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.01 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	0.024 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0064 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	0.036 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	0.26	< 0.014 U		< 0.11 U	0.057 J	< 0.024 U	0.027 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	0.036 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.022 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	0.057	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	0.017 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	0.022 J	< 0.012 U		< 0.097 U	< 0.0094 U	< 0.021 U	0.0065 J	< 0.026 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	0.024 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.015 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	0.036	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	0.024 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0095 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	0.014 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0083 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	0.038	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.017 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	2.1	< 0.014 U		< 0.11 U	0.44	0.039 J	0.51	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.013 U	< 0.013 UT		< 0.098 UT	< 0.0095 UT	< 0.021 UT	< 0.0058 UT	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	0.063	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	0.29	< 0.015 U		< 0.11 U	0.21 J	< 0.024 U	0.16 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	0.087	< 0.014 U		< 0.11 U	0.013 J	< 0.023 U	0.028 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	0.042	< 0.012 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	0.071	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.026 J	< 0.1 U	0.048 J
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.018 J
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.013 J	< 0.013 U	0.019 J
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.24 J	< 0.013 U	0.38
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.022 J	< 0.013 U	0.071 J
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.023 J
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.023 J
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	0.02 J
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.064 J	< 0.014 U	0.14 J
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 UT		< 0.025 U	< 0.029 U	< 0.072 U	0.018 J	< 0.013 U	0.046 J
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.076 U	0.068 J	< 0.014 U	0.12 J
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 UT		< 0.027 U	< 0.031 U	< 0.077 U	1.2	< 0.014 U	1.2
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 UT		< 0.028 U	< 0.031 U	< 0.078 U	0.033 J	< 0.014 U	0.063 J
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.047 J	< 0.014 U	0.1 J
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.01 J
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	0.014 J	< 0.012 U	0.023 J
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0080 J	< 0.013 U	0.022 J
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.032 J	< 0.013 U	0.08 J
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.021 J	< 0.013 U	0.023 J
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.059 J	< 0.013 U	0.089 J
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.042 J	< 0.013 U	0.033 J
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.025 J	< 0.013 U	0.039 J
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	0.011 J
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.02 J
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.069 J	< 0.013 U	0.092 J
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	11	< 0.014 U	7.6
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	0.0092 J
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.019 UT	< 0.034 UT	< 0.055 U		< 0.025 UT	< 0.028 UT	< 0.069 U	0.011 JT	< 0.012 UT	0.019 J
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.025 J	< 0.013 U	0.044 J
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.025 J	< 0.013 U	0.079 J
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0091 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.47	< 0.014 U	0.67
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.18 J	< 0.013 U	0.27 J
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.021 J	< 0.013 U	0.029 J
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.019 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.069 U	0.0067 J	< 0.012 U	0.013 J
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.061 J	< 0.013 U	0.091 J
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.013 J	< 0.013 U	0.022 J
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.0071 J	< 0.013 U	0.017 J
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 UT
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	0.0097 JT
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.012 JT
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.0074 J	< 0.013 U	0.012 JT
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.019 J	< 0.013 U	0.029 JT

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.049 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated		< 0.011 UT	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated			0.525	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 UT	0.058
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated			1.572	< 0.0097 U	0.019 J	< 0.017 U	0.028 J	< 0.02 U	< 0.012 U	< 0.056 U	0.14
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated			10.349	0.025 J	0.43	< 0.019 U	0.19 J	< 0.022 U	0.048 J	< 0.063 U	0.98
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated			51.885	0.025 J	0.42	< 0.019 U	1.3	< 0.022 U	0.032 J	< 0.063 U	5.3
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated			0.3329	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.032 J
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated			1.206	< 0.011 U	0.038 J	< 0.019 U	0.018 J	< 0.022 U	< 0.013 U	< 0.063 U	0.098
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated			0.491	< 0.011 U	0.012 J	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	0.045
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated			1.234	< 0.01 U	0.03 J	< 0.017 U	0.025 J	< 0.021 U	< 0.012 U	< 0.058 U	0.11
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated			0.793	< 0.011 U	0.011 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.08
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated			0.191	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.028 J
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated			2.475	< 0.01 U	0.032 J	< 0.018 U	0.052 J	< 0.021 U	< 0.013 U	< 0.06 U	0.23
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated			5.24	< 0.05 U	0.14 J	< 0.085 U	< 0.053 U	< 0.1 UT	< 0.061 U	< 0.29 U	0.28
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated			0.308	< 0.01 U	< 0.01 U	< 0.018 UT	< 0.011 UT	< 0.021 UT	< 0.013 U	< 0.06 U	0.022 J
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated			2.676	0.018 J	0.14 J	< 0.021 U	0.081 J	< 0.025 UT	0.092 J	< 0.071 U	0.11
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated			0.62	< 0.055 U	0.061 J	< 0.095 U	< 0.059 U	< 0.11 UT	< 0.067 U	< 0.32 U	< 0.067 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated			0.101	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.019 J
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated			1.52	< 0.11 U	0.15 J	< 0.19 U	< 0.12 U	< 0.22 UT	< 0.13 U	< 0.63 U	< 0.13 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated			0.0205	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated			0.053	< 0.0099 U	0.012 J	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated			1.81	< 0.11 U	0.21 J	< 0.18 U	< 0.11 U	< 0.22 UT	< 0.13 U	< 0.62 U	< 0.13 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated			0.0613	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.017 J
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated			0.1	< 0.011 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	0.021 J
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated			0.1843	< 0.011 U	0.025 J	< 0.02 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated			0.0366	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 U	< 0.014 U	< 0.068 U	0.021 J
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated			25.22	0.28 J	0.094 J	< 0.018 U	0.71	< 0.021 UT	0.056 J	< 0.06 U	2.4
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated			0.2107	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 UT	< 0.014 U	< 0.067 U	0.021 J
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated			21.187	0.087 J	0.48	< 0.02 U	0.41	< 0.024 UT	0.12 J	< 0.067 U	1.7
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated			4.005	< 0.01 U	0.089 J	< 0.018 U	0.03 J	< 0.021 UT	< 0.013 U	< 0.06 U	0.25
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated			0.0095	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated			20.67	0.08 J	0.6	0.022 J	0.41	< 0.023 UT	0.12 J	< 0.064 U	1.5
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated			0.484	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.051 J
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated			0.668	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.071 J
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated			15.684	< 0.023 U	0.73	< 0.14 U	0.31	< 0.17 U	< 0.14 U	< 0.049 UT	1.4
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated			0.044	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated			29.147	0.057 J	1.7	< 0.14 U	0.82	< 0.17 U	< 0.14 U	< 0.049 U	2.6
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated			2.06	< 0.022 U	0.084	< 0.14 U	0.056 J	< 0.17 U	< 0.14 U	< 0.048 U	0.18
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated			0.265	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.034 J
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated			5.464	< 0.021 U	0.19	< 0.13 U	0.075	< 0.16 U	< 0.13 U	< 0.044 U	0.61
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated			10.603	< 0.021 U	0.45	< 0.13 U	0.17	< 0.16 U	< 0.13 U	< 0.044 U	1
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated			1.46	< 0.02 U	0.024 J	< 0.13 U	0.032 J	< 0.15 U	< 0.13 U	< 0.044 U	0.15
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated			0.941	< 0.022 U	0.04 J	< 0.14 U	0.024 J	< 0.17 U	< 0.14 U	< 0.047 U	0.081
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated			4.161	< 0.021 U	0.12	< 0.13 U	0.099	< 0.16 U	< 0.13 U	< 0.045 U	0.36
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated			1.357	< 0.021 U	0.02 J	< 0.13 U	0.025 J	< 0.16 U	< 0.13 U	< 0.046 U	0.16
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated			1.385	< 0.023 U	0.057 J	< 0.14 U	0.034 J	< 0.17 U	< 0.15 U	< 0.05 U	0.13
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated			0.699	< 0.022 U	0.032 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.066 J
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated			2.557	< 0.021 U	0.044 J	< 0.13 U	0.067 J	< 0.16 U	< 0.13 U	< 0.045 U	0.25
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated			0.651	< 0.01 U	0.019 J	< 0.018 U	0.011 J	< 0.021 UT	< 0.013 U	< 0.06 UT	0.053
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated			0.0802	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	0.051	0.069	0.033 J	0.031 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	0.12	0.19	0.054	0.1 J	< 0.027 U	< 0.012 UT	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 UT	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	0.92	1.4	0.59	0.44	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	4.6	5.9	2.3	2.5	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	0.021 J	0.036	0.018 J	0.014 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	0.098	0.15	0.075	0.082 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	0.034 J	0.058	0.02 J	0.032 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	0.095	0.14	0.05	0.092 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	0.093	0.12	0.053	0.068 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	0.02 J	0.02 J	0.014 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	0.21	0.29	0.12	0.14 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	0.18	0.62	0.18	0.25 J	< 0.14 U	< 0.061 U	< 0.032 U	< 0.092 U	< 0.069 U	< 0.082 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	0.018 JT	0.03 JT	0.011 J	0.037 JT	< 0.028 UT	< 0.013 UT	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	0.084	0.19	0.045	0.17 J	< 0.034 U	< 0.015 U	< 0.0078 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.051 U	< 0.05 U	< 0.038 U	0.25 J	< 0.15 U	< 0.067 U	< 0.035 U	< 0.1 U	< 0.076 U	< 0.09 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	0.04 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	0.3 J	< 0.099 U	< 0.075 U	0.37 J	< 0.3 U	< 0.13 U	< 0.069 U	< 0.2 U	< 0.15 U	< 0.18 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0093 U	0.0095 J	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	0.039 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	0.34 J	< 0.097 U	< 0.073 U	0.46 J	< 0.29 U	< 0.13 U	< 0.068 U	< 0.2 U	< 0.15 U	< 0.17 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	0.015 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	< 0.011 U	0.011 J	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	0.1 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0075 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	2	2.7	1.1	0.99	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	0.016 J	0.03 J	0.0090 J	0.014 J	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	1.9	2.8	0.87	1.3	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	0.49	0.68	0.23	0.41	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	1.9	2.7	0.96	1.5	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	0.059 J	0.07 J	0.025 J	0.047 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	0.072 J	0.085	0.037 J	0.053 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	1.5	2.2	0.8	1.2	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.035 U	0.023 J	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	2.7	4	1.2	2.5	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	0.17	0.26	0.07 J	0.15	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	0.036 J	0.042 J	< 0.023 U	0.029 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	0.66	0.79	0.23	0.45	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	1.4	1.6	0.45	0.99	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	0.14	0.18	0.049 J	0.093	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	0.1	0.12	0.041 J	0.092	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	0.34	0.44	0.15	0.29	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	0.14	0.16	0.075	0.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	0.12	0.18	0.063 J	0.11	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	0.066 J	0.091	0.038 J	0.084	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	0.23	0.26	0.13	0.18	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	0.055	0.085	0.028 J	0.051 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	0.013 J	0.022 J	0.0092 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.054 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	< 0.053 U	0.013 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.13 J	0.028 J	0.013 J
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.059 U	0.057 J	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	1.1	0.16	0.088 J
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.059 U	0.18 J	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	4.3	0.69	0.12 J
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.038 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.059 U	< 0.014 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.12 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.055 J	< 0.017 U	< 0.013 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.091 J	0.02 J	0.012 J
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.07 J	< 0.016 U	< 0.013 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.021 J	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.21 J	0.024 J	< 0.012 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.27 U	< 0.066 U	< 0.31 U	< 0.098 U	< 0.081 U	< 0.062 U	< 0.061 U	1.4 J	< 0.075 U	< 0.058 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.056 U	< 0.014 UT	< 0.064 U	< 0.02 UT	< 0.017 U	< 0.013 UT	< 0.013 U	0.024 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.067 U	< 0.016 U	< 0.076 U	< 0.024 U	0.036 J	< 0.015 U	< 0.015 U	0.52	0.04 J	0.16 J
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.3 U	< 0.073 U	< 0.34 U	< 0.11 U	< 0.089 U	< 0.069 U	< 0.068 U	0.18 J	< 0.083 U	< 0.064 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.59 U	< 0.15 U	< 0.68 U	< 0.21 U	< 0.18 U	< 0.14 U	< 0.13 U	< 0.064 U	< 0.17 U	< 0.13 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.58 U	< 0.14 U	< 0.66 U	< 0.21 U	< 0.17 U	< 0.13 U	< 0.13 U	< 0.063 U	< 0.16 U	< 0.12 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	< 0.0069 U	< 0.018 U	< 0.014 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0072 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	< 0.063 U	< 0.015 U	< 0.071 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.015 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0069 U	< 0.018 U	< 0.014 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	0.0082 J	< 0.018 U	< 0.014 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.056 UT	0.27 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	2.4	0.35	0.18 J
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.063 UT	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.029 J	< 0.018 U	< 0.014 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.063 UT	0.16 J	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	2	0.38	0.24 J
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.057 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.31 J	0.1	0.027 J
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.06 UT	0.18 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	1.7	0.38	0.27 J
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.051 J	< 0.047 U	< 0.13 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.064 J	< 0.049 U	< 0.14 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.25 U	0.066 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	1.7	0.34	< 0.14 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.26 U	0.17	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	2.9	0.69	< 0.14 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.21	< 0.05 U	< 0.14 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.57	0.12	< 0.13 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.23 U	0.037 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	1	0.25	< 0.13 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.13	< 0.045 U	< 0.13 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.099	< 0.049 U	< 0.14 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.23 U	0.038 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.36	0.071 J	< 0.13 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.14	< 0.048 U	< 0.14 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.15	< 0.051 U	< 0.15 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.08	< 0.049 U	< 0.14 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.23	< 0.047 U	< 0.14 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.056 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.015 J	< 0.016 U	< 0.013 U

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	0.078 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	0.061 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	0.067 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	0.065 J	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.073 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	0.02 J	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	0.035 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	0.019 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	0.019 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	0.018 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.053 UT	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.26 U	< 0.11 U	< 0.056 U	< 0.21 U	< 0.4 U	< 0.066 U	< 0.092 U	< 0.71 U	< 0.13 U	< 0.86 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.054 UT	< 0.023 U	< 0.012 U	< 0.043 UT	< 0.082 U	< 0.014 UT	< 0.019 UT	< 0.15 UT	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.065 U	< 0.028 U	< 0.014 U	< 0.051 U	< 0.098 U	< 0.016 U	< 0.023 U	< 0.18 U	< 0.031 U	< 0.21 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.29 U	< 0.12 U	< 0.062 U	< 0.23 U	< 0.44 U	< 0.073 U	< 0.1 U	< 0.79 U	< 0.14 U	< 0.95 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.58 U	< 0.24 U	< 0.12 U	< 0.46 U	< 0.87 U	< 0.14 U	< 0.2 U	< 1.6 U	< 0.28 U	< 1.9 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.56 U	< 0.24 U	< 0.12 U	< 0.45 U	< 0.85 U	< 0.14 U	< 0.2 U	< 1.5 U	< 0.27 U	< 1.8 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.094 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.092 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.055 UT	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.037 U		< 0.03 U		0.071 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0072 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		0.24 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.041 U		< 0.033 U		1.3	0.074 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.041 U		< 0.033 U		8.8	0.17 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.039 U		< 0.032 U		0.038 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.041 U		< 0.033 U		0.16 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.042 U		< 0.034 U		0.059 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.038 U		< 0.031 U		0.19 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.04 U		< 0.033 U		0.067 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.04 U		< 0.033 U		0.036 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.039 U		< 0.032 U		0.41	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.19 U		< 0.15 U		0.49 J	< 0.051 U	< 0.083 U	< 0.037 U	< 0.15 U	< 0.06 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.039 U		< 0.031 U		0.024 J	< 0.011 U	< 0.017 UT	< 0.0077 UT	< 0.032 U	< 0.012 UT
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.046 U		< 0.038 U		0.11 J	0.048 J	< 0.02 U	< 0.0092 U	< 0.038 U	< 0.015 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.21 U		< 0.17 U		< 0.067 U	< 0.056 U	< 0.091 U	< 0.041 U	< 0.17 U	< 0.066 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.41 U		< 0.33 U		< 0.13 U	< 0.11 U	< 0.18 U	< 0.081 U	< 0.33 U	< 0.13 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.4 U		< 0.33 U		< 0.13 U	< 0.11 U	< 0.18 U	< 0.079 U	< 0.33 U	< 0.13 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		0.021 J	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	< 0.044 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.02 U	< 0.0088 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.039 U		< 0.032 U		3.7	0.26 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.044 U		< 0.036 U		0.031 J	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.043 U		< 0.035 U		2.6	0.14 J	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.039 U		< 0.032 U		0.3 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.042 U		< 0.034 U		2.6	0.14 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.22 U	< 0.11 U			0.063 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			2	0.054 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			3.6	0.15	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			0.31	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			0.053 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.21 U	< 0.11 U			0.65	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.21 U	< 0.11 U			1.1	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.21 U	< 0.11 U			0.26	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			0.12	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.21 U	< 0.11 U			0.71	0.022 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.22 U	< 0.12 U			0.21	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.24 U	< 0.12 U			0.21	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			0.091	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.22 U	< 0.11 U			0.46	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.039 U		< 0.032 U		0.073 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	0.036	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	0.12	< 0.013 U		< 0.099 UT	0.017 J	< 0.021 U	0.042 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 UT	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	0.57	< 0.014 U		< 0.11 U	0.25 J	< 0.024 U	0.32 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	3.3	< 0.014 U		< 0.11 U	0.094 J	0.053 J	0.6	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	0.059	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0099 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	0.14	< 0.014 U		< 0.11 U	0.014 J	< 0.024 U	0.026 J	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	0.075	< 0.015 U		< 0.11 U	0.014 J	< 0.024 U	0.017 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	0.1	< 0.013 U		< 0.1 U	0.02 J	< 0.022 U	0.071 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	0.13	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	0.018 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	0.25	< 0.014 U		< 0.1 U	0.014 J	< 0.023 U	0.029 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	0.29	< 0.065 U		< 0.5 U	< 0.049 U	< 0.11 U	< 0.03 U	< 0.13 U	< 0.41 U	< 0.2 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	0.033 J	< 0.013 UT		< 0.1 UT	0.025 JT	< 0.022 UT	0.059 JT	< 0.027 U	< 0.085 U	< 0.041 UT
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	0.19	< 0.016 U		< 0.12 U	0.31 J	< 0.027 U	0.58	< 0.033 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	0.19	< 0.072 U		< 0.56 U	< 0.054 U	< 0.12 U	< 0.033 U	< 0.15 U	< 0.46 U	< 0.22 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	0.015 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	0.43	< 0.14 U		< 1.1 U	< 0.11 U	< 0.24 U	< 0.066 U	< 0.29 U	< 0.91 U	< 0.44 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	0.014 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	0.57	< 0.14 U		< 1.1 U	< 0.1 U	< 0.23 U	< 0.065 U	< 0.28 U	< 0.89 U	< 0.43 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	< 0.0071 U	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.047 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	0.077	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0071 U	< 0.031 U	< 0.098 U	< 0.047 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	1.3	< 0.013 U		< 0.1 U	0.16 J	< 0.023 U	0.23 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.0077 J	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	1.6	0.029 J		< 0.12 U	0.48	0.09 J	1.2	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	0.48	< 0.014 U		< 0.1 U	0.044 J	< 0.023 U	0.16 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	1.7	0.029 J		< 0.11 U	0.42	0.089 J	1.4	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	0.041 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	0.047 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	1.1	< 0.11 U		< 0.15 U	0.099	< 0.11 U	0.18	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	2.1	< 0.11 U		< 0.15 U	0.27	< 0.12 U	0.33	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	0.12	< 0.11 U		< 0.15 U	0.051 J	< 0.11 U	0.044 J	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	0.39	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	0.88	< 0.1 U		< 0.13 U	0.021 J	< 0.1 U	0.043 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	0.086	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	0.075 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	0.25	< 0.1 U		< 0.13 U	0.023 J	< 0.11 U	0.039 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	0.088	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	0.091	< 0.11 U		< 0.15 U	0.028 J	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	0.056 J	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	0.15	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	0.058	< 0.013 U		< 0.1 U	0.018 J	< 0.023 U	0.061 J	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.024 J	< 0.013 U	0.098 JT
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 UT	< 0.028 U	< 0.07 U	0.13 J	< 0.013 U	0.25 J
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 UT	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	0.78	< 0.014 U	1.5
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	3.6	< 0.014 U	8.5
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.031 J	< 0.013 U	0.036 J
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.069 J	< 0.014 U	0.17 J
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.039 J	< 0.014 U	0.057 J
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.09 J	< 0.013 U	0.16 J
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.027 J	< 0.014 U	0.067 J
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.022 J	< 0.014 U	0.03 J
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.11 J	< 0.013 U	0.4
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.097 U	< 0.17 U	< 0.28 U		< 0.13 U	< 0.14 U	< 0.36 U	0.25 J	< 0.064 U	1.3 J
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.02 UT	< 0.036 U	< 0.059 U		< 0.026 UT	< 0.03 U	< 0.074 U	0.024 JT	< 0.013 U	0.026 J
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.035 U	< 0.088 U	0.31 J	< 0.016 U	0.18 J
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.11 U	< 0.19 U	< 0.31 U		< 0.14 U	< 0.16 U	< 0.39 U	< 0.034 U	< 0.071 U	< 0.048 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.027 J	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.21 U	< 0.38 U	< 0.62 U		< 0.28 U	< 0.31 U	< 0.78 U	< 0.067 U	< 0.14 U	0.42 J
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.011 J
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.21 U	< 0.37 U	< 0.61 U		< 0.27 U	< 0.31 U	< 0.76 U	< 0.066 U	< 0.14 U	0.44 J
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 U	< 0.0072 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.0091 J	< 0.014 U	0.013 J
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.082 U	0.013 J	< 0.015 U	0.019 J
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.0073 J	< 0.015 U	< 0.0099 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 U	0.0074 J	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	< 0.0070 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	< 0.0099 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.02 U	< 0.036 U	0.062 J		< 0.026 U	< 0.03 U	< 0.074 U	3.3	< 0.013 U	3.5
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.033 U	< 0.083 U	0.023 J	< 0.015 U	0.03 J
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	1.6	0.074 J	2.6
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.085 J	< 0.013 U	0.48
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	0.0095 J
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	1.4	0.064 J	2.3
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.022 J	< 0.11 U	0.055 J
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.036 J	< 0.11 U	0.093
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.6	< 0.12 U	2.3
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.021 J
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	1.3	< 0.12 U	4.2
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.19	< 0.12 U	0.3
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.12 U	0.044 J
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.059 J	< 0.11 U	0.86
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.12	< 0.11 U	1.6
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.11	< 0.11 U	0.23
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.049 J	< 0.12 U	0.14
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.4	< 0.11 U	0.63
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.069 J	< 0.11 U	0.19
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.097	< 0.12 U	0.2
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.038 J	< 0.12 U	0.089
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.21	< 0.11 U	0.39
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.041 J	< 0.013 U	0.079 J
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.021 J	< 0.014 U	< 0.0094 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.043 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated		< 0.054 U	< 0.12 U	< 0.18 U	< 0.22 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated		< 0.013 U	< 0.029 U	< 0.044 U	< 0.055 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated		< 0.06 U	< 0.13 U	< 0.2 U	< 0.25 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated		< 0.12 U	< 0.26 U	< 0.39 U	< 0.49 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated		< 0.12 U	< 0.25 U	< 0.38 U	< 0.48 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated		< 0.013 U	< 0.028 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated			1.712	< 0.01 U	0.05 J	< 0.017 U	0.028 J	< 0.021 UT	< 0.012 U	< 0.058 UT	0.13
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated			0.0594	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated			0.1359	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.022 J
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated			0.222	< 0.011 U	0.075 J	< 0.019 U	0.013 J	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated			1.683	0.015 J	0.032 J	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated			0.335	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.034 J
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated			0.027	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated			0.234	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	0.024 J
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated			1.012	< 0.011 U	0.05 J	< 0.018 U	0.029 J	< 0.022 U	< 0.013 U	< 0.062 U	0.094
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated			0.121	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated			1.985	< 0.01 U	0.035 J	< 0.018 U	0.03 J	< 0.022 U	0.02 J	< 0.061 U	0.18
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated			0.913	0.019 JT	0.025 JT	< 0.018 UT	< 0.011 UT	< 0.022 U	< 0.013 UT	< 0.061 U	0.098 T
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated			0.115	< 0.01 U	0.031 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated			0.379	< 0.01 U	0.011 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.041
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated			0.471	< 0.011 U	0.013 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.04
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated			0.029	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated			0.472	< 0.01 U	0.014 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.038
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.014 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated			6.412	< 0.011 U	0.27 J	< 0.018 U	0.11 J	< 0.022 U	0.049 J	< 0.061 U	0.46
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated			0.1739	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.021 J
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated			2.28	< 0.01 U	0.026 J	< 0.018 U	0.02 J	< 0.021 U	< 0.012 U	< 0.059 U	0.22
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated			2.828	0.072 J	0.091 J	< 0.019 U	0.081 J	< 0.023 U	0.037 J	< 0.063 U	0.24
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated			0.547	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.072
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated			0.036	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.012 J
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated			1.445	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.24
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated			0.0671	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.013 J
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated			0.0503	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.014 J
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated			0.297	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.027 J
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated			0.033	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.014 J
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated			0.6998	< 0.0098 U	< 0.0099 U	< 0.017 U	0.014 J	< 0.02 UT	< 0.012 U	< 0.057 U	0.065
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated			2.509	< 0.011 U	0.055 J	< 0.018 U	0.051 J	< 0.022 UT	< 0.013 U	< 0.061 U	0.24
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated			6.33	0.16 J	0.18 J	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	0.48
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated			1.5	0.018 J	< 0.011 U	< 0.018 U	0.025 J	< 0.022 U	0.015 J	< 0.061 U	0.028 J
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated			0.32	< 0.011 U	0.012 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.018 J
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated			0.238	< 0.01 U	0.013 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated			7.125	< 0.0099 U	0.36	< 0.017 U	0.13 J	< 0.02 U	< 0.012 U	< 0.057 U	0.45
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated			6.64	< 0.01 U	0.29 J	< 0.017 U	0.12 J	< 0.021 U	0.013 J	< 0.059 U	0.43
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated			2.437	< 0.01 U	0.078 J	< 0.018 U	0.048 J	< 0.021 U	< 0.013 U	< 0.06 U	0.18
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated			1.389	< 0.01 U	0.042 J	< 0.017 U	0.036 J	< 0.021 U	< 0.012 U	< 0.058 U	0.13
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated			0.1529	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.024 J
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated			0.186	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.025 J
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated			3.885	< 0.011 U	0.15 J	< 0.018 U	0.063 J	< 0.022 U	< 0.013 U	< 0.061 U	0.33
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated			0.421	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.07 U	0.037 J
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated			0.664	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	0.065
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated			0.191	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	0.024 J
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated			0.159	< 0.013 U	< 0.013 U	< 0.022 U	< 0.013 U	< 0.026 U	< 0.015 U	< 0.073 U	0.027 J
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated			29.15	< 0.011 U	0.56	< 0.018 U	1.1	< 0.022 U	0.022 J	< 0.062 U	2.4
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated			0.3875	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.042
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated			2.771	< 0.01 U	0.22 J	< 0.018 U	0.066 J	< 0.021 U	0.093 J	0.1 J	0.13
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated			0.685	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	0.019 J	< 0.062 U	< 0.013 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated			1.248	< 0.011 U	0.014 J	< 0.019 U	0.017 J	< 0.023 U	< 0.013 U	< 0.064 U	0.14
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated			7.688	0.032 J	0.19 J	< 0.02 U	0.14 J	< 0.023 U	< 0.014 U	< 0.066 U	0.7

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.0099 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	0.16	0.23	0.085	0.13 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	0.025 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	0.018 J	0.02 J	0.0089 J	0.021 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	0.17 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	0.075 J	< 0.027 U	< 0.012 U	< 0.0062 U	0.3 J	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	0.029 J	0.041	0.015 J	0.031 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	0.015 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	0.018 J	0.024 J	< 0.0071 U	0.04 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0098 U	< 0.0096 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	0.084	0.14	0.046	0.091 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	0.061 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	0.18	0.24	0.09	0.11 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0098 UT	0.053 T	< 0.0072 UT	0.053 JT	< 0.029 UT	< 0.013 UT	< 0.0067 U	< 0.02 UT	< 0.015 UT	< 0.017 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	0.094 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	0.032 J	0.047	< 0.0072 U	0.035 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	0.032 J	0.06	0.015 J	0.046 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	0.029 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	0.041	0.064	< 0.0071 U	0.053 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	0.58	0.92	0.27	0.52	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	0.014 J	0.021 J	0.0079 J	0.018 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	0.23	0.32	0.1	0.13 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	0.3	0.12	0.034 J	0.19 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	0.021 J	0.04	0.012 J	0.015 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	0.046	0.11	< 0.0070 U	0.022 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	< 0.0095 U	0.0093 J	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	0.013 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	0.021 J
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	0.026 J	0.035 J	0.017 J	0.036 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	0.059	0.071	0.027 J	0.043 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	0.21	0.33	0.098	0.18 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	0.35	0.73	0.26	0.39	< 0.03 U	< 0.014 U	< 0.0070 U	0.04 J	< 0.015 U	< 0.018 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	0.018 J	0.023 J	0.012 J	0.012 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	0.021 J	0.033 J	0.013 J	0.021 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	0.022 J	0.036	0.011 J	0.021 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	0.66	1.2	0.34	0.67	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	0.6	1.1	0.37	0.58	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	0.21	0.32	0.099	0.29 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	0.11	0.19	0.077	0.083 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	0.015 J	0.022 J	0.014 J	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	0.015 J	0.02 J	0.011 J	0.012 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	0.34	0.53	0.2	0.27 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	0.033 J	0.05	0.02 J	0.028 J	< 0.033 U	< 0.015 U	< 0.0076 U	< 0.022 U	< 0.017 U	< 0.02 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	0.056	0.074	0.03 J	0.038 J	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	0.018 J	0.022 J	0.012 J	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	0.02 J	0.028 J	0.01 J	< 0.013 U	< 0.034 U	< 0.015 U	< 0.0080 U	< 0.023 U	< 0.017 U	< 0.021 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	2	2.1	0.94	1.1	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	0.03 J	0.044	0.02 J	0.024 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	0.095	0.17	0.041	0.08 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	0.015 J	0.042	< 0.0073 U	0.022 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	0.13	0.15	0.069	0.07 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	0.66	0.99	0.36	0.47	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.14 J	0.029 J	0.024 J
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.66	0.027 J	0.015 J
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.022 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.093 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.057 U	0.018 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.22 J	0.039	0.017 J
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.058 UT	< 0.014 UT	< 0.066 U	< 0.021 UT	< 0.017 UT	< 0.013 UT	< 0.013 UT	0.12 JT	0.028 JT	0.027 JT
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.031 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.049 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.047 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.057 U	0.052 J	< 0.065 U	< 0.021 U	0.033 J	< 0.013 U	< 0.013 U	0.54	0.16	0.093 J
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.016 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.29 J	0.044	0.015 J
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	0.37 J	0.046	0.074 J
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.15 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.012 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.43	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0091 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.014 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.033 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0070 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.058 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.27 J	0.05	< 0.012 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.06 U	0.045 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.55	0.11	0.12 J
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.017 J	< 0.016 U	0.039 J
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.019 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.054 U	0.044 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.68	0.17	0.024 J
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.055 U	0.035 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.64	0.16	0.033 J
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.18 J	0.065	0.025 J
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.15 J	0.018 J	< 0.012 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.057 U	0.022 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.39	0.079	0.025 J
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.017 U	< 0.013 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.066 U	< 0.016 U	< 0.075 U	< 0.024 U	< 0.019 U	< 0.015 U	< 0.015 U	0.039 J	0.028 J	< 0.014 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.063 UT	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.072 J	0.029 J	< 0.013 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.062 UT	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.068 UT	< 0.017 U	< 0.078 U	< 0.025 U	< 0.02 U	< 0.016 U	< 0.016 U	< 0.0074 U	< 0.019 U	< 0.015 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.059 UT	0.52	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	1.9	0.36	0.44
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.033 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.057 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.26 J	0.042	0.07 J
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.12 J	0.029 J	0.041 J
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.11 J	0.035 J	< 0.013 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.062 UT	0.046 J	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.67	0.13	0.029 J

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.055 UT	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 UT	< 0.084 U	< 0.014 UT	< 0.02 UT	< 0.15 U	< 0.027 U	< 0.18 UT
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 UT
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.077 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 UT
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 UT
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.064 U	< 0.027 U	< 0.014 U	< 0.05 U	< 0.096 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.21 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.066 U	< 0.028 U	< 0.014 U	< 0.052 U	< 0.1 U	< 0.017 U	< 0.023 U	< 0.18 U	< 0.032 U	< 0.22 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.038 U		< 0.031 U		0.21 J	0.01 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.037 U		< 0.03 U		0.15 J	0.057 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		0.035 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.039 U		< 0.031 U		0.033 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.041 U		< 0.033 U		0.12 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.042 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		0.28 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 UT		0.11 JT	0.039 JT	< 0.018 UT	< 0.0079 UT	< 0.032 UT	< 0.013 UT
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.04 U		< 0.032 U		0.054 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.04 U		< 0.032 U		0.049 J	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.039 U		< 0.032 U		0.055 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.04 U		< 0.032 U		0.6	0.042 J	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.04 U		< 0.033 U		0.021 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	< 0.039 U		< 0.031 U		0.27 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	< 0.041 U		< 0.033 U		0.29 J	0.099 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	< 0.04 U		< 0.032 U		0.062 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		0.12 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		0.013 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	< 0.039 U		< 0.032 U		0.029 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	< 0.037 U		< 0.03 U		0.12 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.04 U		< 0.032 U		0.33 J	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.042 U		< 0.034 U		0.72	0.28 J	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.04 U		< 0.032 U		0.06 J	0.033 J	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.04 U		< 0.032 U		0.025 J	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.039 U		< 0.032 U		0.024 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.037 U		< 0.03 U		0.8	0.033 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		0.72	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.039 U		< 0.032 U		0.23 J	0.016 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.038 U		< 0.031 U		0.2 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.039 U		< 0.032 U		0.022 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 UT	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.039 U		< 0.031 U		0.028 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.04 U		< 0.032 U		0.47	0.019 J	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.045 U		< 0.037 U		0.043 J	< 0.012 U	< 0.02 U	< 0.0090 U	< 0.037 U	< 0.014 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.042 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.044 U		< 0.035 U		0.093 J	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.042 U		< 0.034 U		0.027 J	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.047 U		< 0.038 U		0.028 J	< 0.013 U	< 0.021 U	< 0.0094 U	< 0.039 U	< 0.015 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.041 U		< 0.033 U		5.2	0.21 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.039 U		< 0.031 U		0.057 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.039 U		< 0.032 U		0.2 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.04 U		< 0.033 U		0.04 J	0.019 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.042 U		< 0.034 U		0.19 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.043 U		< 0.035 U		1.1	0.046 J	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	0.14	< 0.013 U		< 0.1 U	0.037 J	< 0.022 U	0.12 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0094 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	0.016 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	0.039	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	0.1	< 0.013 U		< 0.1 U	0.01 J	< 0.022 U	0.069 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	0.031 J	< 0.014 U		< 0.11 U	0.012 J	< 0.023 U	0.037 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	0.038	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	0.095	< 0.014 U		< 0.11 U	0.026 J	< 0.024 U	0.047 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	0.06	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	0.14	< 0.014 U		< 0.11 U	0.051 J	< 0.023 U	0.056 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	0.06 T	< 0.014 UT		< 0.11 UT	0.019 JT	< 0.023 UT	0.023 JT	< 0.028 U	< 0.088 U	< 0.042 UT
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	0.021 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	0.04	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.01 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	0.048	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.021 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	0.057	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.018 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	0.59	0.02 J		< 0.11 U	0.17 J	0.063 J	0.45	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	0.017 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	0.17	< 0.013 U		< 0.1 U	0.029 J	< 0.022 U	0.046 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	0.22	< 0.014 U		< 0.11 U	0.079 J	0.041 J	0.096 J	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	0.018 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	< 0.014 UT	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	0.027 JT	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	0.031 JT	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	0.01 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.014 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	< 0.014 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	0.049	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	0.0078 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	0.21	< 0.014 U		< 0.11 U	0.024 J	< 0.023 U	0.04 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	0.45	< 0.014 U		< 0.11 U	0.29 J	< 0.024 U	0.35 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	0.014 J	< 0.014 U		< 0.11 U	0.12 J	< 0.023 U	1.1	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	0.013 J	< 0.023 U	0.11 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.023 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	0.73	< 0.013 U		< 0.1 U	0.053 J	< 0.022 U	0.082 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	0.67	< 0.013 U		< 0.1 U	0.076 J	< 0.022 U	0.11 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	0.29 T	< 0.014 U		< 0.11 U	0.027 J	< 0.023 U	0.079 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	0.097	< 0.013 U		< 0.1 U	0.018 J	< 0.022 U	0.025 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	0.031 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	0.33	< 0.014 U		< 0.11 U	0.079 J	< 0.023 U	0.074 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	0.057	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	0.013 J	< 0.032 U	< 0.1 U	< 0.048 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	0.071	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.0070 J	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	0.033 J	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	0.013 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.017 U	< 0.016 U		< 0.13 U	< 0.012 U	< 0.027 U	< 0.0076 U	< 0.034 U	< 0.1 U	< 0.05 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	1.4	< 0.014 U		< 0.11 U	0.046 J	0.055 J	0.14 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	0.05	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.0095 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	0.097	0.024 J		< 0.1 U	0.24 J	0.051 J	0.82	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	0.041	< 0.014 U		< 0.11 U	0.068 J	< 0.023 U	0.026 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	0.11	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	0.61	< 0.015 U		< 0.12 U	0.046 J	< 0.025 U	0.07 J	< 0.03 U	< 0.095 U	< 0.046 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.1 J	< 0.013 U	0.2 J
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	0.01 J
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.022 U	< 0.04 U	< 0.064 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	< 0.0098 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.32 J	< 0.013 U	0.21 J
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.023 J	< 0.014 U	0.037 J
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	0.012 J
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.023 J	< 0.013 U	0.034 J
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.063 J	< 0.014 U	0.11 J
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.14 J	< 0.014 U	0.28 J
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.021 UT	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 UT	< 0.076 U	0.14 JT	< 0.014 UT	0.17 JT
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.02 U	< 0.037 U	0.36 J		< 0.027 U	< 0.03 U	< 0.075 U	0.039 J	< 0.014 U	0.05 J
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.021 U	< 0.037 U	0.42 J		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.032 J	< 0.014 U	0.079 J
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.032 J	< 0.013 U	0.067 J
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.39	< 0.014 U	0.78
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.015 J	< 0.014 U	0.023 J
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.02 U	< 0.036 U	0.22 J		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.14 J	< 0.013 U	0.3 J
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.032 U	< 0.079 U	0.35 J	< 0.014 U	0.32 J
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.071 J	< 0.014 U	0.086 J
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	0.012 J
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.21 J	< 0.013 U	0.24 J
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0087 J	< 0.013 U	0.014 J
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	0.0093 J
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.016 J	< 0.013 U	0.037 J
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	0.012 J
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.076 J	< 0.013 U	0.11 J
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.11 J	< 0.014 U	0.39
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.72	< 0.014 U	0.78
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.095 J	< 0.014 U	0.045 J
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	0.031 J
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.013 J	< 0.013 U	0.026 J
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.18 J	< 0.013 U	1
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.18 J	< 0.013 U	0.96
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.12 J	< 0.013 U	0.31 J
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.073 J	< 0.013 U	0.2 J
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.0099 J	< 0.013 U	0.023 J
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.016 J	< 0.013 U	0.028 J
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.17 J	< 0.014 U	0.62
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft		1801491411	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.023 U	< 0.042 U	< 0.069 U		< 0.031 U	< 0.035 U	< 0.086 U	0.033 J	< 0.015 U	0.04 J
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.044 J	< 0.015 U	0.085 J
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	< 0.0098 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.015 J	< 0.014 U	0.027 J
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.024 U	< 0.044 U	< 0.072 U		< 0.032 U	< 0.036 U	< 0.09 U	0.02 J	< 0.016 U	0.026 J
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	5.5	< 0.014 U	4.3
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.024 J	< 0.013 U	0.054 J
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.53	0.094 J	0.24 J
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	0.2 J	0.27 J	< 0.014 U	0.061 J
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.057 J	< 0.014 U	0.17 J
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.51	< 0.015 U	1.2

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated		< 0.012 UT	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated		< 0.013 U	< 0.029 U	< 0.043 U	< 0.054 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated		< 0.014 U	< 0.03 U	< 0.045 U	< 0.056 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.07 U	< 0.015 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated			0.242	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.062 U	0.027 J
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated			0.252	< 0.01 U	< 0.01 U	< 0.018 U	0.012 J	< 0.021 U	< 0.012 U	< 0.059 U	0.028 J
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated			3.599	< 0.011 U	0.15 J	< 0.018 U	0.069 J	< 0.022 U	0.041 J	< 0.061 U	0.26
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated			1.879	< 0.011 U	0.044 J	< 0.019 U	0.045 J	< 0.023 U	< 0.014 U	< 0.064 U	0.17
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated			1.499	< 0.011 U	0.05 J	< 0.019 U	0.03 J	< 0.022 U	< 0.013 U	< 0.063 U	0.14
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated			3.323	0.016 J	0.077 J	< 0.018 U	0.076 J	< 0.022 U	< 0.013 U	< 0.062 U	0.31
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated			0.0304	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.012 J
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated			2.522	< 0.0099 U	0.049 J	< 0.017 U	0.034 J	< 0.021 U	< 0.012 U	< 0.058 U	0.22
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated			2.215	< 0.01 U	0.044 J	< 0.018 U	0.022 J	< 0.021 U	< 0.012 U	< 0.059 U	0.19
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated			0.096	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.017 J
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated			0.22	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.027 J
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated			8.97	< 0.02 U	0.27	< 0.13 U	0.27	< 0.16 U	< 0.13 U	< 0.044 U	1.1
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated			0.212	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated			0.038	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated			6.323	< 0.021 U	0.22	< 0.13 U	0.16	< 0.16 U	< 0.13 U	< 0.045 U	0.74
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated			39.182	0.028 J	0.64	< 0.13 U	0.77	< 0.16 U	< 0.13 U	< 0.044 UT	5.4 T
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated			0.142	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated			4.74	0.044 J	0.084	< 0.14 U	0.14	< 0.17 U	< 0.14 U	< 0.048 U	0.4
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated			0.018	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.044 UT	< 0.032 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated			0.167	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	0.033 J
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated			4.198	< 0.021 U	0.19	< 0.13 U	0.084	< 0.16 U	< 0.13 U	< 0.045 U	0.39
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated			24.6	< 0.11 U	0.61	< 0.68 U	0.59	< 0.84 U	< 0.7 U	< 0.24 U	2.2
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated			15.06	0.12	0.43	< 0.13 U	0.32	< 0.16 U	< 0.14 U	< 0.047 U	0.95
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated			5.302	0.026 J	0.16	< 0.14 U	0.14	< 0.17 U	< 0.14 U	< 0.047 U	0.35
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated			0.019	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated			9.036	< 0.021 U	0.61	< 0.13 U	0.27	< 0.16 U	< 0.13 U	< 0.046 U	0.79
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated			5.961	< 0.021 U	0.33	< 0.13 U	0.15	< 0.16 U	< 0.13 U	< 0.045 U	0.56
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 UT	< 0.033 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated			ND	< 0.026 U	< 0.019 U	< 0.16 U	< 0.023 U	< 0.19 U	< 0.16 U	< 0.055 U	< 0.04 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated			0.132	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.011 U	< 0.011 U	< 0.0083 U	< 0.012 U	< 0.033 U	< 0.015 U	< 0.0077 U	< 0.022 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	0.02 J	0.026 J	0.012 J	0.014 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	0.016 J	0.025 J	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	0.33	0.51	0.19	0.29 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	0.15	0.21	0.08	0.091 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	0.14	0.2	0.074	0.11 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	0.29	0.4	0.14	0.19 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	0.22	0.35	0.15	0.15 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	0.18	0.32	0.12	0.13 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	0.01 J	0.014 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.0097 U	0.031 J	0.014 J	0.017 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	0.72	1.1	0.41	0.54	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.031 U	0.051 J	0.026 J	0.053 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	0.56	0.8	0.3	0.34	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	3.4 T	4.5 T	1.6	2	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 0.031 U	0.033 J	< 0.021 U	0.019 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	0.44	0.51	0.18	0.39	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.031 U	0.038 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	0.4	0.56	0.2	0.27	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	1.6	3.8	1.1	1.8	< 0.7 U	< 0.069 U	< 0.14 U	< 2 U	< 0.81 U	< 1.3 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	0.79	1.4	0.58	0.58	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	0.33	0.56	0.24	0.29	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	0.82	0.94	0.39	0.81	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	0.57	0.66	0.26	0.57	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.19 U	< 0.31 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.036 U	0.034 J	< 0.025 U	0.021 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.066 UT	< 0.016 U	< 0.075 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	< 0.0072 U	< 0.018 U	< 0.014 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.021 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.021 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.058 U	0.029 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.33 J	0.078	0.03 J
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.061 UT	0.016 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.18 J	0.033 J	< 0.013 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	< 0.059 UT	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.059 UT	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.15 J	0.034 J	< 0.013 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	< 0.058 UT	0.024 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.33 J	0.056	< 0.013 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0064 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.054 U	0.013 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.25 J	0.049	0.014 J
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.21 J	0.042	0.02 J
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.011 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.025 J	< 0.016 U	< 0.012 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.23 U	0.045 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.97	0.19	< 0.13 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.24 U	0.031 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.66	0.13	< 0.13 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.23 U	0.11	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	4.1 T	0.75	< 0.13 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	< 0.25 U	0.049 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.4	0.13	< 0.14 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 UT	< 0.016 U	< 0.092 UT	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.46	0.084	< 0.13 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 1.2 U	0.38	< 0.5 U	< 0.67 U	< 0.088 U	< 0.71 U	< 0.64 U	3	0.52	< 0.71 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.25 U	0.35	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.6	0.17	< 0.14 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.25 U	0.13	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.63	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.24 U	0.046 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	1.1	0.21	< 0.14 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.24 U	0.024 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.67	0.13	< 0.13 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.29 U	< 0.021 U	< 0.12 U	< 0.16 U	< 0.02 U	< 0.16 U	< 0.15 U	< 0.049 U	< 0.057 U	< 0.16 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.064 U	< 0.027 U	< 0.014 U	< 0.051 U	< 0.096 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.031 U	< 0.21 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 UT	< 0.14 U	< 2.2 UT
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 UT	< 0.2 U	< 0.61 UT	< 0.14 U	< 2.2 UT
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 1.8 U	< 0.15 U	< 0.67 U	< 0.64 U	< 0.76 U	< 0.84 U	< 1.1 U	< 3.3 U	< 0.75 U	< 12 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 UT	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 UT	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.41 U	< 0.034 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.19 U	< 0.26 UT	< 0.77 U	< 0.17 U	< 2.8 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 UT	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 UT	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 UT	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 UT	< 0.71 U	< 0.16 U	< 2.6 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.046 U		< 0.037 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0090 U	< 0.037 U	< 0.015 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.041 U		< 0.033 U		0.03 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.039 U		< 0.031 U		0.052 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.04 U		< 0.032 U		0.36 J	0.022 J	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.042 U		< 0.034 U		0.32 J	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.041 U		< 0.033 U		0.18 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	< 0.04 U		< 0.033 U		0.48	0.025 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.038 U		< 0.03 U		0.31 J	0.013 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.039 U		< 0.031 U		0.26 J	0.011 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.039 U		< 0.032 U		0.015 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.039 U		< 0.032 U		0.028 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.21 U	< 0.11 U			1.5	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.21 U	< 0.11 U			0.025 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.21 U	< 0.11 U			0.021 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.22 U	< 0.11 U			1.2	0.018 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.21 U	< 0.11 U			6.6 T	0.084	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 0.21 U	< 0.11 U			0.035 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	< 0.23 U	< 0.12 U			0.64	0.04 J	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 UT	< 0.12 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			0.04 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			0.59	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 1.1 U	< 0.6 U			3.7	< 0.075 U	< 0.14 U	< 0.11 U	< 0.2 U	< 0.68 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.22 U	< 0.12 U			3.2	0.15	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.23 U	< 0.12 U			0.99	0.036 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.22 U	< 0.11 U			1.1	0.046 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.22 U	< 0.11 U			0.74	0.03 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.27 U	< 0.14 U			< 0.023 U	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U	< 0.16 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.25 U	< 0.13 U			0.039 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U

DRAFT

												Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.5	0.33				0.33	12			
Restricted - Residential												0.5	100				100	100			
Protection of Groundwater												8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.017 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0073 U	< 0.032 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	0.037 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	0.33	< 0.014 U		< 0.11 U	0.11 J	< 0.023 U	0.11 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	0.12	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 UT
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 UT
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	0.13	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 UT
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	0.23	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 UT
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	0.18	< 0.013 U		< 0.1 U	0.032 J	< 0.022 U	0.036 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	0.16	< 0.013 U		< 0.1 U	0.059 J	< 0.022 U	0.06 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	0.021 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	0.54	< 0.1 U		< 0.13 U	0.11	< 0.1 U	0.11	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	0.036 J	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	0.34	< 0.1 U		< 0.14 U	0.05 J	< 0.11 U	0.045 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	2.1	< 0.1 U		< 0.13 U	0.14	< 0.1 U	0.2	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	0.31	< 0.11 U		< 0.14 U	0.031 J	< 0.11 U	0.046 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 UT
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	0.21	< 0.1 U		< 0.13 U	0.024 J	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	1.4	< 0.55 U		< 0.72 U	0.14 J	< 0.56 U	0.22 J	< 0.87 U	< 0.49 U	< 0.71 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	0.48	< 0.11 U		< 0.14 U	0.15	< 0.11 U	0.12	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	0.23	< 0.11 U		< 0.14 U	0.094	< 0.11 U	0.11	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	0.63	< 0.11 U		< 0.14 U	0.2	< 0.11 U	0.22	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	0.43	< 0.1 U		< 0.14 U	0.061 J	< 0.11 U	0.091	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.044 U	< 0.13 U		< 0.17 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.17 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.024 U	< 0.042 U	< 0.069 U		< 0.031 U	< 0.035 U	< 0.087 U	< 0.0074 U	< 0.016 U	< 0.011 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	0.025 J	< 0.014 U	0.03 J
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.047 J	< 0.013 U	0.051 J
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.22 J	< 0.014 U	0.5
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.18 J	< 0.014 U	0.3 J
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.081 J	< 0.014 U	0.23 J
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.23 J	< 0.014 U	0.55
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.012 J
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.15 J	< 0.013 U	0.41
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.03 U	< 0.074 U	0.15 J	< 0.013 U	0.36
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.012 J	< 0.013 U	0.017 J
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	0.017 J	< 0.013 U	0.04 J
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.22	< 0.11 U	1.3
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.021 J
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.017 J
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.15	< 0.11 U	0.88
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.13 U	< 0.13 UT	< 0.25 UT		< 0.024 U	< 0.12 U	< 0.57 UT	0.65	< 0.11 U	7 T
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.022 J	< 0.11 U	0.033 J
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.43	< 0.12 U	0.64
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.018 J
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 UT	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.056 J
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.19	< 0.11 U	0.76
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.7 U	< 0.71 U	< 1.3 U		< 0.13 U	< 0.64 U	< 3.1 U	0.97	< 0.58 U	3.7
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	1.9	< 0.11 U	2.7
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.53	< 0.11 U	0.84
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.019 J	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.41	< 0.11 U	1.3
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.26	< 0.11 U	0.84
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.16 U	< 0.16 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.13 U	< 0.021 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U	0.038 J
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated		< 0.013 U	< 0.029 U	< 0.043 U	< 0.054 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated		< 0.14 U	< 0.15 UT	< 0.12 UT	< 0.12 UT
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated		< 0.76 U	< 0.8 U	< 0.67 U	< 0.64 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated		< 0.18 U	< 0.19 U	< 0.15 U	< 0.15 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated			0.612	< 0.023 U	0.024 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.077 J
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated			0.591	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	0.066 J
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated			0.048	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated			0.05	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 UT	< 0.033 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 UT	< 0.034 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated			0.076	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated			0.108	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated			17.436	< 0.024 U	0.35	< 0.15 U	0.21	< 0.18 U	< 0.15 U	< 0.051 U	1.8
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated			2.997	< 0.027 U	0.12	< 0.17 U	0.056 J	< 0.2 U	< 0.17 U	< 0.058 U	0.27
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated			0.895	< 0.022 U	0.039 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.09
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 UT	< 0.15 U	< 0.05 UT	< 0.036 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated			0.216	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.047 J
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated			0.078	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated			3.73	0.048 J	0.033 J	< 0.13 U	0.11	< 0.16 U	< 0.14 U	< 0.046 U	0.3
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated			0.353	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.051 U	0.051 J
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated			0.28	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	0.051 J
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated			1.749	< 0.022 U	0.028 J	< 0.14 U	0.045 J	< 0.17 U	< 0.14 U	< 0.047 U	0.2
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated			14.103	0.025 J	0.39	< 0.14 U	0.4	< 0.17 U	< 0.14 U	< 0.047 U	1.1
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated			4.919	< 0.021 U	0.14	< 0.13 U	0.12	< 0.16 U	< 0.14 U	< 0.046 U	0.38
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated			8.806	0.021 J	0.3	< 0.13 U	0.29	< 0.16 U	< 0.14 U	< 0.046 U	0.79
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.035 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated			0.163	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated			0.172	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 UT	< 0.14 U	< 0.048 UT	< 0.035 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated			0.021	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated			3.061	0.04 J	0.046 JT	< 0.14 U	0.088	< 0.17 UT	< 0.14 U	< 0.048 U	0.33 T
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated			41.444	0.034 J	0.34	< 0.14 U	0.72	< 0.17 U	< 0.14 U	< 0.049 U	3.8
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated			1.297	< 0.022 U	< 0.017 U	< 0.13 U	0.035 J	< 0.17 U	< 0.14 U	< 0.047 U	0.14
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated			2.19	< 0.022 U	0.022 J	< 0.13 U	0.043 J	< 0.16 U	< 0.14 U	< 0.046 U	0.2
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated			0.018	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			0.819	< 0.027 U	0.023 J	< 0.17 U	< 0.024 U	< 0.2 U	< 0.17 U	< 0.058 U	0.073 J
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			0.268	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.037 J
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			0.425	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	0.039 J
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			1.412	< 0.024 U	0.045 J	< 0.15 U	0.039 J	< 0.18 U	< 0.15 U	< 0.052 U	0.15
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			4.839	0.049 J	0.084	< 0.15 U	0.18	< 0.18 U	< 0.15 U	< 0.052 U	0.42
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			6.09	0.027 J	0.044 J	< 0.15 U	0.16	< 0.18 U	< 0.15 U	< 0.051 U	0.56
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			3.137	< 0.025 U	0.1	< 0.15 U	0.098	< 0.19 U	< 0.16 U	< 0.054 UT	0.26
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			0.241	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			0.402	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	0.039 J
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			4.737	< 0.023 U	0.15	< 0.14 U	0.13	< 0.18 U	< 0.15 U	< 0.05 U	0.45
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated			0.624	< 0.023 U	0.019 J	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	0.056 J
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated			0.551	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated			0.065	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated			0.524	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.048 J
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated			0.584	< 0.023 U	< 0.017 U	< 0.14 U	0.02 J	< 0.17 U	< 0.14 U	< 0.049 U	0.059 J
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated			9.541	< 0.021 U	0.16	< 0.13 U	0.25	< 0.16 U	< 0.13 U	< 0.045 U	1
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated			0.48	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.051 J
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated			0.275	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 UT	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated			0.179	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	0.063 J	0.071 J	0.033 J	0.049 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	0.077 J	0.074 J	0.034 J	0.053 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.032 U	0.02 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.033 U	0.029 J	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	1.1	2	0.68	1.2	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	0.31	0.36	0.16	0.3	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	0.097	0.13	0.046 J	0.085	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.034 U	0.031 J	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.032 U	0.018 J	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	0.3	0.33	0.14	0.22	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	0.044 J	0.042 J	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.035 U	0.044 J	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	0.14	0.17	0.074 J	0.13	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	1.4	1.5	0.65	1.5	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	0.51	0.59	0.2	0.57	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	0.85	1	0.32	0.96	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.034 U	0.034 J	< 0.023 U	0.018 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	0.034 J	0.032 J	< 0.023 U	0.02 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	0.19 T	0.24 T	0.089 T	0.14 T	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 UT	< 0.16 UT	< 0.26 UT
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	3.9	4.3	1.7	2.9	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	0.12	0.15	0.052 J	0.055 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	0.2	0.2	0.11	0.12	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.093	0.11	0.045 J	0.079 J	< 0.17 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.2 U	< 0.32 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.032 U	0.044 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.054 J	0.071 J	0.027 J	0.044 J	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.13	0.2	0.076 J	0.085	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.39	0.53	0.24	0.3	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.43	0.59	0.25	0.31	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.25	0.4	0.15	0.19	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U	< 0.3 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.035 U	0.043 J	< 0.024 U	0.029 J	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.041 J	0.056 J	< 0.022 U	0.044 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.37	0.52	0.25	0.27	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.06 J	0.069 J	0.038 J	0.054 J	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.033 U	0.022 J	< 0.023 U	0.41	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.033 U	0.021 J	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	0.057 J	0.066 J	0.028 J	0.041 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	0.058 J	0.058 J	0.031 J	0.033 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	0.99	1.1	0.45	0.57	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	0.051 J	0.055 J	0.029 J	0.038 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	0.037 J	0.047 J	< 0.023 U	0.027 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.035 U	0.037 J	< 0.024 U	0.025 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.054 U	< 0.16 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.069 J	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.068 J	< 0.054 U	< 0.15 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.27 U	0.038 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	2.2	0.32	< 0.15 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.3 U	< 0.022 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.37	< 0.06 U	< 0.17 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.1	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.24 U	0.051 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.29	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.048 J	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.18	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.25 U	0.051 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.2	0.33	< 0.14 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.24 U	0.021 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.43	0.12	< 0.14 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.24 U	0.047 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.8	0.21	< 0.14 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 UT	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 UT	< 0.13 U	0.41 T	< 0.049 UT	< 0.14 U
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.26 U	0.19	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	3.4	0.63	< 0.15 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.12	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.2	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.3 U	< 0.022 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.15 U	0.087 J	< 0.059 U	< 0.17 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.065 J	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.062 J	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.21	< 0.054 U	< 0.15 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.27 U	0.084	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.49	0.089	< 0.15 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.27 U	0.065 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.64	0.07 J	< 0.15 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.28 U	0.054 J	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	0.41	0.063 J	< 0.16 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.046 J	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.062 J	< 0.047 U	< 0.14 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.26 U	0.019 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.45	0.077 J	< 0.15 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.072 J	< 0.051 U	< 0.15 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.065 J	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.056 J	< 0.05 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.24 U	0.017 J	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.94	0.14	< 0.14 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.05 J	< 0.048 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.045 J	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U	< 0.15 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 UT	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 UT	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 UT	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 UT	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 UT	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 UT	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 UT	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 UT	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 UT	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 UT	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 UT	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.43 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.8 U	< 0.18 U	< 2.9 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 UT	< 0.16 U	< 2.5 UT
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 UT	< 0.15 U	< 2.4 UT
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.15 U	< 2.5 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	< 0.36 UT	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 UT	< 0.17 UT	< 0.22 UT	< 0.66 UT	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.43 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.18 U	< 0.2 U	< 0.27 U	< 0.8 U	< 0.18 U	< 2.9 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.15 UT	< 0.17 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.17 U	< 2.7 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.23 U	< 0.12 U			0.094	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.25 U	< 0.13 U			0.096	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.22 U	< 0.11 U			0.025 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.24 U	< 0.12 U			0.026 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.22 U	< 0.12 U			0.03 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.23 U	< 0.12 U			0.031 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.24 U	< 0.13 U			2.4	0.026 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.14 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.28 U	< 0.14 U			0.28	< 0.018 U	< 0.033 U	< 0.027 U	< 0.048 U	< 0.16 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.23 U	< 0.12 U			0.097	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 UT	< 0.14 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.24 U	< 0.12 U			0.062 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.22 U	< 0.12 U			0.028 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.22 U	< 0.12 U			0.49	0.045 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.25 U	< 0.13 U			0.062 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.24 U	< 0.12 U			0.073 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.23 U	< 0.12 U			0.28	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.23 U	< 0.12 U			1.6	0.058 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			0.43	0.029 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.22 U	< 0.12 U			0.97	0.045 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.23 U	< 0.12 U			0.047 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.23 U	< 0.12 U			0.046 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 UT	< 0.14 UT
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	< 0.23 U	< 0.12 U			0.43 T	0.052 J	< 0.028 UT	< 0.022 U	< 0.039 UT	< 0.14 U
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.24 U	< 0.12 U			6.1	0.13	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.23 U	< 0.12 U			0.21	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.22 U	< 0.12 U			0.33	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.28 U	< 0.14 U			0.11	< 0.018 U	< 0.033 U	< 0.027 U	< 0.048 U	< 0.16 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.22 U	< 0.11 U			0.047 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.24 U	< 0.12 U			0.052 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.25 U	< 0.13 U			0.19	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.25 U	< 0.13 U			0.72	0.044 J	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.25 U	< 0.13 U			1.3	0.038 J	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.26 U	< 0.13 U			0.48	0.019 J	< 0.031 U	< 0.025 U	< 0.044 U	< 0.15 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.24 U	< 0.12 U			0.052 J	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.22 U	< 0.11 U			0.06 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.24 U	< 0.13 U			1	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.24 U	< 0.12 U			0.1	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.23 U	< 0.12 U			0.034 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.22 U	< 0.12 U			0.023 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.23 U	< 0.12 U			0.068 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.23 U	< 0.12 U			0.11	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.22 U	< 0.11 U			1.7	0.023 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.23 U	< 0.12 U			0.081	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.23 U	< 0.12 U			0.044 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.24 U		< 0.13 U		0.049 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	0.98	< 0.12 U		< 0.15 U	0.081 J	< 0.12 U	0.11	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	0.23	< 0.13 U		< 0.17 U	0.038 J	< 0.14 U	0.061 J	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	0.082	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	0.2	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.027 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	0.12	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	1.2	< 0.11 U		< 0.14 U	0.085	< 0.11 U	0.25	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	0.4	< 0.11 U		< 0.14 U	0.045 J	< 0.11 U	0.12	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	0.71	< 0.11 U		< 0.14 U	0.071 J	< 0.11 U	0.16	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	0.1 T	< 0.11 U		< 0.14 U	0.034 J	< 0.11 U	0.062 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	2.4	< 0.11 U		< 0.15 U	0.04 J	< 0.12 U	0.13	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	0.055 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	0.097	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.061 J	< 0.13 U		< 0.17 U	< 0.022 U	< 0.14 U	< 0.018 U	< 0.21 U	< 0.12 U	< 0.17 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.076 J	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.26	< 0.12 U		< 0.16 U	0.03 J	< 0.12 U	0.067 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.25	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	0.045 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.15	< 0.12 U		< 0.16 U	0.052 J	< 0.13 U	0.067 J	< 0.2 U	< 0.11 U	< 0.16 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.24	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	0.044 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	0.045 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	0.043 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	0.52	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	0.048 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.15 U	< 0.16 U	< 0.3 U		< 0.028 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.036 J	< 0.12 U	0.12
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.025 J	< 0.13 U	0.098
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.023 J
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.024 J
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.026 J
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.048 J
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.71	< 0.12 U	3.7
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.17 U	< 0.17 U	< 0.33 U		< 0.031 U	< 0.15 U	< 0.75 U	0.09 J	< 0.14 U	0.51
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.028 J	< 0.11 U	0.14
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.02 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.076 J
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.032 J
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.44	< 0.11 U	0.79
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.033 J	< 0.13 U	0.073 J
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.04 J	< 0.12 U	0.072 J
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.13	< 0.12 U	0.28
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.69	< 0.11 U	.2
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.27	< 0.11 U	0.75
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.38	< 0.11 U	1.3
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.024 J	< 0.12 U	0.04 J
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	0.04 J
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 UT	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.021 J
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	< 0.14 U	< 0.14 UT	< 0.27 U		< 0.026 U	< 0.13 UT	< 0.62 UT	0.29	< 0.12 U	0.6 T
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	3.4	< 0.12 U	7.9
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.12	< 0.11 U	0.24
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.23	< 0.11 U	0.46
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.018 J
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.17 U	< 0.17 U	< 0.33 U		< 0.031 U	< 0.15 U	< 0.75 U	0.051 J	< 0.14 U	0.11
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.034 J	< 0.11 U	0.041 J
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.025 J	< 0.12 U	0.051 J
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.066 J	< 0.13 U	0.19
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.42	< 0.13 U	0.64
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.42	< 0.12 U	1
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.7 U	0.19	< 0.13 U	0.41
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.023 J	< 0.12 U	0.048 J
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.043 J	< 0.11 U	0.057 J
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.12	< 0.12 U	0.86
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.041 J	< 0.12 U	0.09
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.04 J
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.021 J
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.032 J	< 0.12 U	0.076 J
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.061 J	< 0.12 U	0.098
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.31	< 0.11 U	1.5
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.046 J	< 0.11 U	0.079
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.02 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.026 J	< 0.12 U	0.049 J
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.025 J	< 0.12 U	0.043 J

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated		< 0.15 U	< 0.16 UT	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 UT
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated			0.138	< 0.024 U	0.02 J	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated			0.575	< 0.022 U	0.024 J	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.051 J
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated			0.371	< 0.021 U	0.02 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.033 J
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated			1.225	< 0.021 U	0.06 J	< 0.13 U	0.035 J	< 0.16 U	< 0.13 U	< 0.045 U	0.11
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated			0.263	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.037 J
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.049 U	< 0.036 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated			0.169	< 0.026 U	< 0.02 U	< 0.16 U	< 0.023 U	< 0.2 U	< 0.16 U	< 0.056 U	< 0.04 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated			1.06	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.17
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated			2.201	< 0.021 U	< 0.016 U	< 0.13 U	0.048 J	< 0.16 U	< 0.13 U	< 0.045 U	0.29
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated			0.473	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.076
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated			1.09	< 0.023 U	0.082	< 0.14 U	0.029 J	< 0.18 U	< 0.15 U	< 0.05 U	0.08 J
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated			0.785	< 0.022 U	< 0.017 U	< 0.14 U	0.032 J	< 0.17 U	< 0.14 U	< 0.048 U	0.071 J
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated			1.217	< 0.022 U	0.068 J	< 0.14 U	0.029 J	< 0.17 U	< 0.14 U	< 0.048 U	0.11
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated			0.544	< 0.022 U	0.032 J	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.043 J
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated			ND	< 0.37 U	< 0.37 U		< 0.37 U				< 0.37 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated			ND	< 0.0071	< 0.0085	< 0.03	< 0.0072	< 0.036	< 0.033	< 0.055	< 0.0093
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0088
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated			ND	< 0.0068	< 0.0081	< 0.029	< 0.0069	< 0.034	< 0.032	< 0.053	< 0.0089
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	< 0.0089
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.013 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated			0.016	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	0.016 J
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated			0.247	< 0.021 U	0.024 J	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated			0.014	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated			1.773	< 0.022 U	0.12	< 0.02 U	0.069 J	< 0.16 U	< 0.016 U	< 0.047 U	0.16
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated			0.046	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated			0.235	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	0.035 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated			0.097	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated			0.068	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated			10.177	0.033 J	0.48	< 0.13 U	0.39	< 0.16 U	< 0.14 U	< 0.047 U	0.96
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated			2.091	0.023 J	0.081	< 0.14 U	0.078	< 0.17 U	< 0.14 U	< 0.047 U	0.19
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated			1.796	< 0.024 U	0.1	< 0.15 U	0.067 J	< 0.18 U	< 0.15 U	< 0.052 U	0.16
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated			0.02	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated			0.099	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated			0.439	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 UT	0.049 J
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated			0.048	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 UT	< 0.033 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated			10.347	< 0.02 U	0.18	< 0.13 U	0.22	< 0.15 U	< 0.13 U	< 0.043 U	1.1
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated			7.169	< 0.023 U	0.31	< 0.14 U	0.26	< 0.17 U	< 0.15 U	< 0.05 U	0.83
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated			0.441	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.049 J
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated			0.522	< 0.021 U	0.018 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.045 J
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated			7.049	< 0.022 U	0.33	< 0.14 U	0.25	< 0.17 U	< 0.14 U	< 0.048 U	0.85
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated			0.896	< 0.022 U	0.051 J	< 0.14 U	0.035 J	< 0.17 U	< 0.14 U	< 0.047 U	0.11
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated			0.424	< 0.021 U	0.026 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.042 J
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated			2.115	< 0.022 U	0.11	< 0.13 U	0.059 J	< 0.17 U	< 0.14 U	< 0.047 U	0.21
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated			3.69	0.04 J	0.14	< 0.14 U	0.15	< 0.17 U	< 0.14 U	< 0.048 U	0.33
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated			44.96	0.62	0.36	< 0.14 U	1.8	< 0.18 U	< 0.15 U	< 0.05 U	4.4

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.036 U	0.034 J	< 0.025 U	0.022 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	0.057 J	0.067 J	0.029 J	0.08	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	0.04 J	0.063 J	< 0.022 U	0.048 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	0.12	0.15	0.04 J	0.094	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	0.042 J	0.052 J	0.028 J	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.19 U	< 0.31 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.1	0.16	0.053 J	0.038 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.28 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.16	0.089	0.086	0.055 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.05 J	0.067 J	0.028 J	0.022 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	0.086	0.13	0.068 J	0.093	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	0.067 J	0.061 J	0.035 J	0.036 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	0.13	0.2	< 0.023 U	0.082	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	0.054 J	0.073 J	0.031 J	0.046 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50_4-7	13 Sep 00B50_4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.0074	< 0.012	< 0.015	< 0.0074	< 0.024	< 0.0099	< 0.008	< 0.06	< 0.032	< 0.05
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0075	< 0.056	< 0.03	< 0.048
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.0071	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0095	< 0.0076	< 0.057	< 0.031	< 0.048
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.0071	< 0.011	< 0.014	< 0.0071	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031	< 0.049
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated	0.037 J	0.05 J	0.022 J	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated	0.18	0.19	0.089	0.17	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.03 U	0.027 J	0.024 J	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U	< 0.24 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U	< 0.25 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	0.02 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	0.79	1.3	0.37	0.83	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	0.16	0.27	0.065 J	0.16	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	0.14	0.22	0.063 J	0.13	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.034 U	0.03 J	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	0.042 J	0.064 J	< 0.024 U	0.041 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	0.91	1.2	0.4	0.69	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	0.68	0.93	0.28	0.36	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	0.042 J	0.045 J	0.027 J	0.025 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	0.053 J	0.064 J	0.036 J	0.044 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	0.67	0.9	0.28	0.37	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	0.085	0.1	0.039 J	0.074 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	0.036 J	0.062 J	0.029 J	0.032 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	0.2	0.27	0.099	0.15	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	0.33	0.43	0.16	0.23	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	3.7	4.2	1.5	2.2	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.07 J	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.28	< 0.0068	< 0.03	< 0.034	< 0.0077	< 0.03	< 0.041	< 0.0088	< 0.0082	< 0.036
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0083	< 0.0078	< 0.034
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.033	< 0.0074	< 0.029	< 0.039	< 0.0084	< 0.0079	< 0.035
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.27	< 0.0066	< 0.029	< 0.033	< 0.0074	< 0.029	< 0.04	< 0.0085	< 0.0079	< 0.035
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.011 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.015 U	< 0.015 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.016 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.041 J	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.17	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U	< 0.015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6-8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.013 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.013 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	< 0.24 U	0.052 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1	0.23	< 0.14 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	< 0.25 U	0.02 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.2	< 0.049 U	< 0.14 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	< 0.27 U	0.023 J	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.17	< 0.054 U	< 0.15 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.06 J	< 0.05 U	< 0.14 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.23 U	0.081	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	1	0.18	< 0.13 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.26 U	0.024 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.83	0.13	< 0.15 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.047 J	< 0.05 U	< 0.14 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.061 J	< 0.046 U	< 0.13 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.25 U	0.029 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.82	0.13	< 0.14 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.1	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.066 J	< 0.047 U	< 0.14 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.22	< 0.048 U	< 0.14 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.25 U	0.044 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.34	0.062 J	< 0.14 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.26 U	0.55	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	3.6	0.7	0.35 J

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.39 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.15 U	< 2.5 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	< 0.42 U	< 0.035 U	< 0.16 U	< 0.15 U	< 0.18 U	< 0.2 U	< 0.26 U	< 0.77 U	< 0.17 U	< 2.8 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 UT	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 UT	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 UT	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 UT	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 1.9 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.039	< 0.0074	< 0.04	< 0.058	< 0.04	< 0.046	< 0.039	< 0.15	< 0.038	< 0.44
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.037	< 0.007	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.037	< 0.0071	< 0.039	< 0.055	< 0.039	< 0.044	< 0.037	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037	< 0.42
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.012 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U	< 0.92 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 0.95 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U	< 1.9 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 0.34 U	< 0.028 U	0.13 J	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.32 UT	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U	< 2.5 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.25 U		< 0.13 U		0.037 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.23 U		< 0.12 U		0.072 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.21 U		< 0.11 U		0.055 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.21 U		< 0.11 U		0.18	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.22 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.25 U		< 0.13 U		0.054 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.24 U		< 0.12 U		< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.22 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	< 0.27 U		< 0.14 U		0.062 J	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U	< 0.16 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.23 U		< 0.12 U		0.17	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.25 U		< 0.13 U		< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.22 U		< 0.11 U		0.54	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.22 U		< 0.11 U		0.078	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	< 0.22 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.24 U		< 0.13 U		0.17	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.23 U		< 0.12 U		0.17	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.23 U		< 0.12 U		0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.23 U		< 0.12 U		0.09	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.37 U				< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.03			< 0.042	< 0.0079	< 0.0097	< 0.0079	< 0.0083	< 0.04	< 0.027
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0092	< 0.0074	< 0.0078	< 0.038	< 0.025
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.029			< 0.041	< 0.0076	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.029			< 0.041	< 0.0076	< 0.0094	< 0.0076	< 0.008	< 0.038	< 0.026
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.017 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.018 U
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated	< 0.056 U			< 0.12 U	0.041 J	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated	< 0.057 U			< 0.12 U	0.23	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.11 U			0.026 J	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.053 U	< 0.11 U			0.068 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.055 U	< 0.11 U			0.029 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	0.023 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	< 0.22 U	< 0.12 U			1.2	0.054 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	< 0.23 U	< 0.12 U			0.25	0.019 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	< 0.25 U	< 0.13 U			0.29	0.023 J	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.24 U	< 0.12 U			0.031 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.23 U	< 0.12 U			0.073 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 0.22 U	< 0.11 U			0.023 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.21 U	< 0.11 U			1.7	0.017 J	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.24 U	< 0.12 U			1	0.027 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.23 U	< 0.12 U			0.084	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.22 U	< 0.11 U			0.069 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.23 U	< 0.12 U			0.94	0.032 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.23 U	< 0.12 U			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.22 U	< 0.12 U			0.054 J	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.24 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 U			0.29	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.23 U	< 0.12 U			0.47	0.051 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.23 U	< 0.12 UT			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.24 U	< 0.13 U			7.6	0.61	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	0.041 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	0.078	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	< 0.045 U	< 0.13 U		< 0.17 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U	< 0.17 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.039 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	0.063 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	0.079 J	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	0.074 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.37 U	< 0.37 U		< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 1.9 U	< 1.9 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.0076	< 0.026		< 0.028	< 0.0066	< 0.036	< 0.0064	< 0.17	< 0.15	< 0.15
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.0072	< 0.024		< 0.026	< 0.0063	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.0073	< 0.025		< 0.027	< 0.0064	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.0073	< 0.025		< 0.027	< 0.0064	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.014 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.017 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.018 U		0.014 J	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated	0.13	< 0.11 U	< 0.11 U	< 0.019 U	0.037 J		0.045 J	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.018 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.097 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	0.74	< 0.11 U		< 0.14 U	0.1	< 0.11 U	0.13	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	0.15	< 0.11 U		< 0.14 U	0.057 J	< 0.11 U	0.056 J	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	0.12	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	0.023 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	0.63	< 0.1 U		< 0.13 U	0.032 J	< 0.1 U	0.11	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	0.34	< 0.11 U		< 0.15 U	0.037 J	< 0.12 U	0.038 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	0.04 J	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	0.33	< 0.11 U		< 0.14 U	0.041 J	< 0.11 U	0.031 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	0.063 J	< 0.11 U		< 0.14 U	0.019 J	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	0.063 J	< 0.11 U	0.039 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 UT	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	0.14	< 0.11 U		< 0.14 U	0.023 J	< 0.11 U	0.027 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	0.21	< 0.11 U		< 0.14 U	0.054 J	< 0.11 U	0.067 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.04 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	2.2	< 0.12 U		< 0.15 U	0.19	< 0.12 U	0.23	< 0.18 U	< 0.1 U	< 0.15 U

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	0.045 J
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.028 J	< 0.11 U	0.084
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.02 J	< 0.11 U	0.07 J
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.068 J	< 0.11 U	0.2
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	--	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	0.05 J
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated	< 0.16 U	< 0.17 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	0.04 J	< 0.14 U	0.067 J
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	0.15
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U	< 0.02 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.12	< 0.11 U	0.47
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.074
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.035 J	< 0.12 U	0.2
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U	0.13
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.052 J	< 0.12 U	0.21
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.027 J	< 0.11 U	0.11
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U	< 1.9 U	< 0.37 U	< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.031	< 0.041	< 0.13		< 0.0087	< 0.034	< 0.033	< 0.012	< 0.0087	< 0.0075
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0083	< 0.0071
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.029	< 0.039	< 0.13		< 0.0083	< 0.033	< 0.032	< 0.011	< 0.0084	< 0.0072
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084	< 0.0072
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.056 J
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.1	< 0.11 U	0.24
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.02 J
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.13 U	< 0.056 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.03 J	< 0.11 U	0.051 J
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.028 J	< 0.11 U	0.04 J
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U	0.025 J
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	0.45	< 0.11 U	1.7
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.16	< 0.12 U	0.31
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.14	< 0.13 U	0.25
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.02 J
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	0.038 J
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.032 J	< 0.12 U	0.078 J
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.025 J
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.59	< 0.11 U	1.6
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.064 J	< 0.12 U	1.4
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.039 J	< 0.12 U	0.083
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.036 J	< 0.11 U	0.074
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.046 J	< 0.12 U	1.4
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	0.16
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.064 J
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.14	< 0.11 U	0.31
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.34	< 0.12 U	0.48
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U	< 0.019 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	5.2	< 0.12 U	6.4

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated		< 0.18 U	< 0.19 U	< 0.16 U	< 0.15 U
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated				< 0.37 U	< 0.37 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated		< 0.028	< 0.024	< 0.039	< 0.055
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated			0.106	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated			1.175	< 0.022 U	0.034 J	< 0.13 U	0.027 J	< 0.17 U	< 0.14 U	< 0.047 U	0.1
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated			0.094	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated			0.061	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated			4.292	< 0.022 U	0.085	< 0.14 U	0.15	< 0.17 U	< 0.14 U	< 0.048 U	0.38
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated			0.035	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated			ND	< 0.019 U	< 0.014 U	< 0.12 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated			0.27	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.041 J
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated			2.966	< 0.02 U	0.041 J	< 0.12 U	0.066 J	< 0.15 U	< 0.13 U	< 0.043 U	0.31
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated			0.906	< 0.021 U	0.017 J	< 0.13 U	0.036 J	< 0.16 U	< 0.13 U	< 0.046 U	0.088
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated			12.58	< 0.022 U	0.26	< 0.13 U	0.22	< 0.17 U	< 0.14 U	< 0.047 U	0.4
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated			5.377	< 0.023 U	0.32	< 0.14 U	0.18	< 0.18 U	< 0.15 U	< 0.05 U	0.49
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated			26.09	0.34	0.33	< 0.14 U	0.99	< 0.17 U	< 0.14 U	< 0.048 U	0.74
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated			0.33	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.046 J
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated			0.383	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	0.043 J
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated			0.639	< 0.023 U	0.02 J	< 0.14 U	< 0.021 U	< 0.17 U	< 0.14 U	< 0.049 U	0.067 J
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated			0.948	< 0.024 U	0.029 J	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	0.085
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated			0.067	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated			1.013	< 0.024 U	0.046 J	< 0.15 U	0.033 J	< 0.18 U	< 0.15 U	< 0.052 U	0.086
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated			0.15	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated			0.1133	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.019 J
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated			1.069	0.0044 J	0.031	< 0.013 U	0.026	< 0.017 U	< 0.014 U	< 0.0047 U	0.086
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated			0.271	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.035 J
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated			0.014	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated			0.486	< 0.011 U	< 0.011 U	< 0.018 U	0.011 J	< 0.022 U	< 0.013 U	< 0.061 U	0.045
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated			0.0339	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated			0.174	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	0.023 J
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated			2.123	< 0.011 U	0.024 J	< 0.019 U	0.037 J	< 0.023 UT	< 0.013 U	< 0.064 U	0.21
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated			ND	< 0.01 UT	< 0.01 UT	< 0.017 UT	< 0.011 UT	< 0.021 UT	< 0.012 UT	< 0.058 UT	< 0.012 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated			9.324	0.026 J	0.2	< 0.14 U	0.26	< 0.17 U	< 0.14 U	< 0.048 U	0.74
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated			6.396	0.08 J	0.071 J	< 0.018 U	0.2 J	< 0.021 U	0.03 J	< 0.059 U	0.56

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.03 U	0.029 J	< 0.021 U	0.021 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	0.13	0.16	0.068 J	0.12	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.031 U	0.023 J	< 0.022 U	0.021 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	0.27	0.29	0.18	0.15	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.024 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	0.035 J	0.036 J	0.026 J	0.027 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	0.25	0.25	0.16	0.14	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	0.078	0.093	0.024 J	0.049 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	1.2	1.5	0.5	0.84	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	0.48	0.68	0.3	0.42	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	2.3	2.8	1.1	1.3	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	0.042 J	0.053 J	< 0.021 U	0.031 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	0.041 J	0.038 J	0.045 J	0.031 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	0.054 J	0.063 J	0.032 J	0.041 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	0.085	0.12	0.038 J	0.076 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	0.08 J	0.1	0.041 J	0.061 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.034 U	0.027 J	< 0.023 U	0.018 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.011 UT	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	0.01 J	0.018 J	0.0072 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.0095 UT	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 UT	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	0.097	0.11	0.041	0.086	< 0.014 U	< 0.0014 U	< 0.0028 U	< 0.04 U	< 0.016 U	< 0.026 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	0.022 J	0.03 J	0.015 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	0.035 J	0.06	0.016 J	0.031 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.01 U	0.012 J	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	0.012 J	0.014 J	< 0.0079 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	0.21	0.25	0.11	0.13 J	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.0093 UT	< 0.0091 UT	< 0.0069 UT	< 0.01 UT	< 0.027 UT	< 0.012 UT	< 0.0063 UT	< 0.019 UT	< 0.014 UT	< 0.016 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	0.7	0.92	0.38	0.57	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	0.24	< 0.0093 U	< 0.0070 U	0.1 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.1	< 0.048 U	< 0.14 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.25 U	0.093	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.37	< 0.049 U	< 0.14 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 0.23 UT	< 0.016 UT	< 0.092 UT	< 0.12 UT	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 0.21 U	< 0.015 U	< 0.086 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.042 U	< 0.12 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.26	< 0.045 U	< 0.13 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.084	< 0.047 U	< 0.14 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	< 0.25 U	0.02 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.1	0.25	< 0.14 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	< 0.26 U	0.031 J	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.55	0.099	< 0.15 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	< 0.25 U	0.29	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	2.2	0.39	0.17 J
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.046 U	< 0.13 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 UT	< 0.016 U	< 0.13 U	< 0.12 U	0.044 J	< 0.045 U	< 0.13 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.068 J	< 0.051 U	< 0.15 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.12	< 0.053 U	< 0.15 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.1	< 0.053 U	< 0.15 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0098 J	< 0.015 U	< 0.011 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.025 U	0.0083	< 0.01 U	< 0.013 U	< 0.0017 U	< 0.014 U	< 0.013 U	0.1	0.018	< 0.014 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.016 U	< 0.012 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.05 J	< 0.016 U	< 0.012 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.011 J	< 0.018 U	< 0.013 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.19 J	0.042	< 0.013 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.055 U	< 0.013 UT	< 0.062 UT	< 0.02 UT	< 0.016 UT	< 0.012 UT	< 0.012 UT	< 0.0059 UT	< 0.015 UT	< 0.012 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.25 U	0.044 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.75	0.14	< 0.14 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	1.8	< 0.016 U	0.12 J

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.16 J	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	0.22 J	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	0.25 J	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	0.13 J	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 0.33 UT	< 0.027 U	0.13 J	< 0.12 UT	< 0.14 U	< 0.15 UT	< 0.2 U	< 0.6 UT	< 0.14 U	< 2.2 UT
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 0.31 U	< 0.025 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.14 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.35 U	< 0.029 U	0.17 J	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.33 U	< 0.027 UT	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.35 U	< 0.029 U	0.13 J	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.035 U	< 0.0029 U	< 0.013 U	< 0.013 U	< 0.015 U	0.06	< 0.022 U	< 0.065 U	< 0.015 U	< 0.24 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 UT	< 0.027 U	< 0.18 UT
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.042 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	0.041 J	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	0.058 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	0.058 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.055 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.038 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	0.031 J	< 0.021 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.053 UT	< 0.023 UT	< 0.011 UT	< 0.042 UT	< 0.08 UT	< 0.013 UT	< 0.019 UT	< 0.14 UT	< 0.025 UT	< 0.17 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1			100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.21 U	< 0.11 U			0.029 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.23 U	< 0.12 U			0.13	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.22 U	< 0.11 U			0.021 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.21 U	< 0.11 U			0.029 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.23 U	< 0.12 U			0.86	0.032 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 0.21 UT	< 0.11 U			< 0.018 UT	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 UT	< 0.12 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 0.2 U	< 0.1 U			< 0.017 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	< 0.22 U	< 0.12 U			0.044 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			0.58	0.02 J	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	< 0.22 U	< 0.11 U			0.17	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	< 0.22 U	< 0.12 U			2.1	0.021 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	< 0.24 U	< 0.13 U			0.67	0.032 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	< 0.23 U	< 0.12 U			4	0.3	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.21 U	< 0.11 U			0.053 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.21 U	< 0.11 U			0.062 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.24 U	< 0.12 U			0.11	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.25 U	< 0.13 U			0.18	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.21 U	< 0.11 U			0.036 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.25 U	< 0.13 U			0.18	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.23 U	< 0.12 U			0.052 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.037 U		< 0.03 U		0.022 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.023 U	< 0.012 U			0.18	0.0056 J	< 0.0027 U	< 0.0022 U	< 0.0039 U	< 0.013 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.04 U		< 0.033 U		0.046 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.04 U		< 0.032 U		0.057 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.044 U		< 0.035 U		0.024 J	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.042 U		< 0.034 U		0.34 J	< 0.011 U	< 0.018 UT	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 UT	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.038 UT		< 0.031 U		< 0.012 UT	< 0.01 UT	< 0.017 UT	< 0.0075 UT	< 0.031 UT	< 0.012 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.23 U			< 0.12 U	1.5	0.058 J	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.039 U		< 0.031 U		0.59	0.21 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U

DRAFT

												Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.5	0.33				0.33	12			
Restricted - Residential												0.5	100				100	100			
Protection of Groundwater												8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	0.11	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.029 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	0.12	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	0.02 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 UT	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 UT	< 0.13 UT
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 0.033 U	< 0.094 U		< 0.12 U	< 0.016 U	< 0.097 U	< 0.013 U	< 0.15 U	< 0.084 U	< 0.12 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	0.12	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	0.043 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.027 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	0.79	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	0.039 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	0.32	< 0.12 U		< 0.15 U	0.052 J	< 0.12 U	0.066 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	1.3	< 0.11 U		< 0.15 U	0.12	< 0.11 U	0.17	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.022 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	0.045 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	0.061 J	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	0.062 J	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	0.023 J	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.095 U	< 0.046 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	0.073	< 0.011 U		< 0.014 U	0.011	< 0.011 U	0.015	< 0.017 U	< 0.0096 U	< 0.014 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.016 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.014 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	0.057	< 0.014 U		< 0.11 U	0.013 J	< 0.023 U	0.024 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	0.032 J	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.019 J	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	0.16	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	0.036 J	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.014 UT	< 0.013 UT		< 0.1 UT	< 0.0098 UT	< 0.022 UT	< 0.0061 UT	< 0.027 UT	< 0.083 UT	< 0.04 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	0.54	< 0.11 U	< 0.11 U	< 0.15 U	0.53		0.39	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	0.14	< 0.013 U		< 0.1 U	0.084 J	< 0.022 U	0.076 J	< 0.027 U	< 0.085 U	< 0.041 U

DRAFT

												Nitrobenzene	**2-Nitrophenol**	**4-Nitrophenol**	**N-Nitrosodimethylamine**	**N-Nitrosodi-n-propylamine**	**N-Nitrosodiphenylamine**	**Pentachlorophenol**	**Phenanthrene**	**Phenol**	**Pyrene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.027 J
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.051 J	< 0.11 U	0.15
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	0.029 J
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	0.032 J
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.77	< 0.12 U	0.7
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.035 J
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 UT	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.022 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.061 J
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.22	< 0.11 U	0.59
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.034 J	< 0.11 U	0.18
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.22	< 0.11 U	2.4
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.3	< 0.12 U	0.79
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	2.8	< 0.12 U	3.6
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.029 J	< 0.11 U	0.054 J
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.022 J	< 0.11 U	0.057 J
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.06 J	< 0.12 U	0.099
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.023 J	< 0.13 U	0.16
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.031 J
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.077 J	< 0.13 U	0.17
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.053 J
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	< 0.0070 U	< 0.015 U	< 0.0099 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0083 J	< 0.013 U	0.019 J
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.014 U	< 0.014 U	< 0.027 U		< 0.0026 U	< 0.013 U	< 0.061 U	0.077	< 0.011 U	0.15
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.036 J	< 0.014 U	0.047 J
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.041 J	< 0.014 U	0.059 J
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.0099 J	< 0.014 U	0.012 J
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.022 U	< 0.041 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.015 J	< 0.015 U	0.024 J
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.078 J	< 0.014 U	0.33 J
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.019 UT	< 0.035 UT	< 0.057 UT		< 0.025 UT	< 0.029 UT	< 0.072 UT	< 0.0062 UT	< 0.013 UT	< 0.0087 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.95	< 0.12 U	1.4
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.8	< 0.013 U	1.6

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated		< 0.13 U	< 0.14 U	< 0.11 U	< 0.11 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated		< 0.015 U	< 0.016 U	< 0.013 U	< 0.013 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 UT	< 0.045 UT
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-6-8	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-6-8	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-6-8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U

DRAFT

														Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated			0.527	< 0.011 U	0.017 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.033 J
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated			0.987	< 0.01 U	0.026 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated			0.7953	< 0.011 U	0.026 J	< 0.018 U	0.014 J	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated			0.29	< 0.01 U	0.034 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated			0.09	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated			11.56	0.04 J	0.59	< 0.019 U	0.33 J	< 0.023 UT	0.13 J	< 0.063 U	0.71
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated			26.862	0.082 J	0.52	< 0.018 U	0.78	< 0.021 UT	0.052 J	< 0.06 U	2.1
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated			2.017	< 0.011 U	0.061 J	< 0.018 U	0.05 J	< 0.022 UT	0.018 J	< 0.061 U	0.13
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated			8.525	0.051 J	0.13 J	< 0.018 U	0.22 J	< 0.021 UT	0.025 J	< 0.06 U	0.71
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated			0.011	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated			0.0078	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated			10.093	0.073 J	0.13 J	< 0.017 U	0.4	< 0.02 U	0.034 J	< 0.058 U	0.81
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated			0.511	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.053 J
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated			1.245	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	0.068 J	0.052 J
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated			0.021	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated			0.414	< 0.024 U	0.019 J	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	0.043 J
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated			0.1488	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.021 J
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated			4.504	0.027 J	0.038 J	< 0.018 U	0.088 J	< 0.022 U	< 0.013 U	< 0.061 U	0.39
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated			0.246	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 UT	0.029 J
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated			0.602	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.049
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated			1.628	< 0.01 U	0.014 J	< 0.017 U	0.03 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.14
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated			2.684	< 0.01 U	0.048 J	< 0.017 U	0.037 J	< 0.021 UT	< 0.012 U	< 0.059 U	0.21
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated			1.288	< 0.01 U	0.014 J	< 0.017 U	0.02 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.097
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated			4.198	< 0.0099 U	0.13 J	0.036 J	0.064 J	< 0.021 UT	0.03 J	< 0.058 U	0.32
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated			0.161	< 0.021 U	0.027 J	< 0.13 U	0.021 J	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated			0.161	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 UT	< 0.034 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 UT	< 0.032 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 UT	< 0.014 U	< 0.069 UT	< 0.014 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated			4.974	0.054 J	0.096 J	< 0.017 U	0.17 J	< 0.02 UT	0.072 J	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated			0.593	< 0.011 U	0.022 J	< 0.018 U	0.017 J	< 0.022 UT	< 0.013 U	< 0.061 U	0.032 J
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated			0.162	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 UT	< 0.013 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated			10.18	< 0.1 U	0.15 J	< 0.18 U	< 0.11 U	< 0.21 UT	< 0.13 U	< 0.6 U	< 0.13 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated			6.752	0.043 J	0.088 J	< 0.017 U	0.16 J	< 0.02 U	0.019 J	< 0.057 U	0.54
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated			6.366	0.11	0.051 J	< 0.13 U	0.25	< 0.16 U	< 0.14 U	< 0.046 U	0.52
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated			9.95	0.022 J	0.17	< 0.14 U	0.39	< 0.17 U	< 0.14 U	< 0.047 U	0.91
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated			0.036	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated			0.102	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated			0.1398	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.023 J
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated			0.2176	< 0.01 U	0.014 J	< 0.018 U	0.016 J	< 0.022 U	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated			10.601	0.012 J	0.28 J	< 0.018 U	0.18 J	< 0.022 U	0.032 J	< 0.062 U	0.83
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated			9.701	0.036 J	0.047 J	0.022 J	0.13 J	< 0.024 U	< 0.014 U	< 0.068 U	0.74
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated			1.621	< 0.011 U	0.1 J	< 0.019 U	0.093 J	< 0.023 UT	< 0.014 U	< 0.065 UT	0.14
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated			0.895	< 0.01 U	0.017 J	< 0.017 U	0.024 J	< 0.021 UT	< 0.012 U	< 0.058 UT	0.079
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated			39.49	0.44 J	0.56 J	< 0.18 U	1.5 J	< 0.22 UT	0.45 J	< 0.62 UT	4
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated			0.175	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	0.025 J
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated			0.2228	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated			4.121	< 0.01 U	0.091 J	< 0.018 U	0.083 J	< 0.021 UT	0.035 J	< 0.059 UT	0.29
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated			0.877	< 0.0098 U	0.016 J	< 0.017 U	0.02 J	< 0.02 UT	< 0.012 U	< 0.057 UT	0.077
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 UT	< 0.012 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated			0.173	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	0.017 J
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated			3.485	0.02 J	0.15 J	< 0.018 U	0.083 J	< 0.022 UT	0.018 J	< 0.06 UT	0.24
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated			0.0666	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	0.014 J
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated			0.115	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 UT	< 0.031 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated			4.216	0.063 J	0.08	< 0.13 U	0.13	< 0.15 U	< 0.13 U	< 0.044 U	0.38
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated			2.549	< 0.02 U	0.04 J	< 0.12 U	0.035 J	< 0.15 U	< 0.13 U	< 0.043 U	0.21
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated			7.949	< 0.022 U	0.13	< 0.14 U	0.31	< 0.17 U	< 0.14 U	< 0.047 U	0.62

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	0.041	0.064	0.019 J	0.068 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.0094 U	0.28	< 0.0069 U	0.12 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.01 U	0.16	< 0.0073 U	0.08 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	0.13 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	0.042 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	0.95	1.3	0.56	0.93	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	1.8	2.5	1.1	1.1	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	0.15	0.24	0.087	0.14 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	0.67	0.93	0.32	0.47	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	0.68	0.95	0.37	0.34 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	0.04 J	0.05 J	< 0.023 U	0.037 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U	< 0.27 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	0.046 J	0.12	< 0.022 U	0.073	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	0.045 J	0.064 J	< 0.025 U	0.054 J	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	0.013 J	0.018 J	0.0088 J	< 0.011 UT	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	0.4	0.48	0.22	0.25 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	0.024 J	0.035 J	0.012 J	0.017 J	< 0.028 U	< 0.013 U	< 0.0066 UT	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	0.028 J	0.059	0.024 J	0.028 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	0.13	0.19	0.072	0.12 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	0.17	0.28	0.097	0.11 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	0.096	0.15	0.053	0.078 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	0.27	0.67	0.22	0.19 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.032 UT	< 0.018 UT	< 0.022 UT	< 0.016 UT	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.036 U	0.033 J	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U	< 0.29 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0075 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	0.033 J	0.051	0.018 J	0.049 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	0.01 JT	0.015 J	< 0.0072 U	0.018 JT	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.097 U	0.58	< 0.071 U	1.7 J	< 0.28 U	< 0.13 U	< 0.066 U	< 0.19 U	< 0.14 U	< 0.17 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	0.51	0.79	0.29	0.36	< 0.027 U	< 0.012 U	< 0.0063 U	0.026 J	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	0.45	0.56	0.18	0.36	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	0.73	0.87	0.32	0.51	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.0098 U	0.012 J	0.0088 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	0.011 J	0.017 J	0.0078 J	0.036 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	0.97	1.4	0.52	0.7	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	0.88	1.3	0.43	0.53	< 0.032 U	< 0.014 U	< 0.0074 U	0.15 J	< 0.016 U	0.069 J
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	0.09	0.15	0.048	0.24 J	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	0.075	0.094	0.044	0.063 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	1.2	1.9	0.61	0.59 J	< 0.29 U	< 0.13 U	< 0.068 U	< 0.2 U	< 0.15 U	< 0.17 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	0.016 J	0.023 J	0.012 J	0.019 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	0.064 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	0.29	0.4	0.15	0.24 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	0.068	0.1	0.045	0.064 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	0.012 J	0.017 J	< 0.0069 U	0.026 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	0.24	0.42	0.13	0.31 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.0094 U	0.0096 J	< 0.0069 U	0.018 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	0.23	0.24	0.073	0.3	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	0.24	0.3	0.14	0.27	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	0.56	0.65	0.26	0.56	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.078 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.32 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.23 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.06 UT	0.13 J	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	0.79	0.17	0.28 J
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.057 UT	0.33 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	2.1	0.3	0.31 J
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.058 UT	0.025 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.15 J	0.027 J	0.05 J
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.057 U	0.074 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.72	0.12	0.071 J
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	0.012 J
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.054 U	0.14 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.78	0.11	0.13 J
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.084	< 0.05 U	< 0.14 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.43	< 0.047 U	< 0.13 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.054 J	< 0.054 U	< 0.15 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.013 J	< 0.016 UT	< 0.012 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.058 U	0.048 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.36 J	0.053	0.021 J
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.031 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.062 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.16 J	0.047	< 0.012 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.055 U	0.029 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.25 J	0.04	0.023 J
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.13 J	0.036	0.02 J
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.054 U	0.042 J	< 0.062 U	< 0.02 U	0.031 J	< 0.012 U	< 0.012 U	0.46	0.074	0.065 J
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 UT	< 0.14 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	0.047 J	< 0.053 U	< 0.15 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.065 UT	< 0.016 U	< 0.074 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0070 U	< 0.018 U	< 0.014 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	1.2	< 0.015 U	0.09 J
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.078 J	0.026 J	0.012 J
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.057 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.038 J	< 0.016 UT	< 0.012 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.57 U	< 0.14 U	< 0.65 U	< 0.2 U	< 0.17 U	< 0.13 U	< 0.13 U	1.8 J	< 0.16 U	0.12 J
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.054 U	0.062 J	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.55	0.073	0.057 J
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.24 U	0.093	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.47	0.084	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.25 U	0.037 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.74	0.15	< 0.14 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.012 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.015 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.013 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.059 U	0.08 J	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.85	0.14	0.11 J
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.064 U	0.044 J	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	0.8	0.11	0.029 J
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.061 UT	0.02 J	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.21 J	0.02 J	0.019 J
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.069 J	0.015 J	< 0.012 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.58 UT	< 0.14 U	< 0.66 U	< 0.21 U	< 0.17 U	< 0.13 U	< 0.13 U	5.3	0.19 J	1.6 J
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.03 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.078 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.056 UT	0.028 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.31 J	0.057	0.073 J
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.076 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.052 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.025 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.057 UT	0.029 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.34 J	0.056	0.068 J
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.042 J	< 0.043 U	< 0.12 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 UT	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.57	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.23 U	0.016 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.26	0.048 J	< 0.13 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.25 U	0.12	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.59	0.15	< 0.14 U

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.053 U	< 0.022 U	0.028 J	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 UT	< 0.026 U	< 0.18 UT
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 UT	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U	< 2.6 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.35 UT	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 UT	< 0.15 U	< 2.3 UT
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.33 UT	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 UT	< 0.14 U	< 2.2 UT
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.063 U	< 0.027 U	< 0.013 U	< 0.049 U	< 0.094 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 UT	< 0.027 UT	< 0.18 UT
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.55 U	< 0.23 U	< 0.12 U	< 0.43 U	< 0.83 U	< 0.14 U	< 0.19 U	< 1.5 U	< 0.26 U	< 1.8 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.03 U	< 0.2 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.56 U	< 0.24 U	< 0.12 U	< 0.45 U	< 0.85 U	< 0.14 U	< 0.2 U	< 1.5 U	< 0.27 U	< 1.8 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	0.017 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.32 UT	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.04 U		< 0.033 U		0.042 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.038 U		< 0.031 U		0.017 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.04 U		< 0.033 U		0.028 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.041 U		< 0.033 U		1.1	0.11 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.039 U		< 0.032 U		4.5	0.25 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.04 U		< 0.032 U		0.24 J	0.033 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.039 U		< 0.032 U		1.3	0.054 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.037 U		< 0.03 U		1.7	0.14 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	< 0.23 U	< 0.12 U			0.078	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	< 0.22 U	< 0.11 U			0.081	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	< 0.25 U	< 0.13 U			0.053 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.039 U		< 0.032 U		0.03 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 UT	< 0.013 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.04 U		< 0.032 U		0.76	0.026 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.039 U		< 0.032 U		0.027 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.039 U		< 0.031 U		0.11 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.038 U		< 0.031 U		0.23 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.038 U		< 0.031 U		0.5	0.024 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.038 U		< 0.031 U		0.18 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.038 U		< 0.03 U		0.55	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.22 U	< 0.12 U			0.028 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.25 U	< 0.13 U			0.027 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U	< 0.15 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 UT			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 UT
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.045 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.02 U	< 0.0088 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		0.31 J	0.34	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.04 U		< 0.032 U		0.056 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.04 UT		< 0.032 U		0.016 J	< 0.011 U	< 0.018 U	< 0.0079 UT	< 0.032 UT	< 0.013 UT
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.39 U		< 0.32 U		0.45 J	0.35 J	< 0.17 U	< 0.077 U	< 0.32 U	< 0.12 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.037 U		< 0.03 U		1.1	0.046 J	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	1	0.091	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.23 U			< 0.12 U	1.9	0.091	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.043 U		< 0.035 U		0.03 J	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.04 U		< 0.032 U		0.034 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.039 U		< 0.032 U		0.019 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.04 U		< 0.033 U		1.6	0.039 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.044 U		< 0.036 U		1.9	0.038 J	< 0.02 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.043 U		< 0.035 U		0.19 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.038 U		< 0.031 U		0.13 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.4 U		< 0.33 U		5.6	1.9 J	< 0.18 U	< 0.079 U	< 0.33 U	< 0.13 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.039 U		< 0.031 U		0.54	0.021 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.037 U		< 0.03 U		0.13 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.038 U		< 0.031 U		0.02 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.039 U		< 0.032 U		0.41	0.056 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.2 U	< 0.11 U			0.03 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 UT			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 UT
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			0.5	0.13	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			0.27	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.23 U	< 0.12 U			1.2	0.059 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	0.063	< 0.014 U		< 0.11 U	0.011 J	< 0.023 U	0.036 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	0.14	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	0.13	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0083 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	0.16	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	0.048	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	0.9	0.026 J		< 0.11 U	0.53	0.084 J	1.6	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	1.3	< 0.014 U		< 0.11 U	0.18 J	< 0.023 U	0.35 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	0.15	< 0.014 U		< 0.11 U	0.055 J	< 0.023 U	0.17 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	0.56	< 0.014 U		< 0.11 U	0.092 J	< 0.023 U	0.21 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	0.4	< 0.013 U		< 0.1 U	0.1 J	< 0.022 U	0.24 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.14 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	0.031 J	< 0.11 U	0.019 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	0.017 J	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.014 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	0.38	< 0.014 U		< 0.11 U	0.012 J	< 0.023 U	0.02 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	0.018 J	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	0.049	< 0.013 U		< 0.1 U	0.012 J	< 0.022 U	0.019 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	0.15	< 0.013 U		< 0.1 U	0.021 J	< 0.022 U	0.019 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	0.18	< 0.013 U		< 0.1 U	0.032 J	< 0.022 U	0.036 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	0.11	< 0.013 U		< 0.1 U	0.044 J	< 0.022 U	0.038 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	0.3	< 0.013 U		< 0.1 U	0.21 J	< 0.022 U	0.33 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.037 UT	< 0.11 U		< 0.14 U	0.035 J	< 0.11 U	0.048 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U	< 0.15 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U	< 0.032 U	< 0.098 U	< 0.048 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	0.4	< 0.021 U	0.2 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	0.078	< 0.014 U		< 0.11 U	0.021 J	< 0.023 U	0.067 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	0.014 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.011 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	2.1	< 0.14 U		< 1.1 U	0.69 J	0.56 J	0.32 J	< 0.28 U	< 0.86 U	< 0.42 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	0.5	< 0.013 U		< 0.1 U	0.059 J	< 0.022 U	0.16 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	0.3	< 0.11 U	< 0.11 U	< 0.14 U	0.048 J		0.061 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	0.45	< 0.11 U	< 0.11 U	< 0.14 U	0.032 J		0.067 J	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	0.048	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0077 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	0.98	< 0.014 U		< 0.11 U	0.11 J	0.039 J	0.46	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	0.79	< 0.015 U		< 0.12 U	0.064 J	< 0.026 U	0.067 J	< 0.031 U	< 0.098 U	< 0.047 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	0.12	< 0.015 U		< 0.11 U	0.026 J	0.033 J	0.093 J	< 0.03 UT	< 0.094 U	< 0.045 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	0.067	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.038 J	< 0.027 UT	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	0.76	< 0.14 U		< 1.1 U	0.4 J	< 0.23 U	1.3 J	< 0.28 UT	< 0.89 U	< 0.43 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	0.018 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 UT	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 UT	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 UT	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	0.058	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 UT	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	0.25	< 0.013 U		< 0.1 U	0.13 J	< 0.022 U	0.68	< 0.027 UT	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	0.069	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	0.024 J	< 0.026 UT	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 UT	< 0.08 U	< 0.039 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 UT	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	0.29	< 0.014 U		< 0.11 U	0.053 J	< 0.023 U	0.2 J	< 0.028 UT	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 UT	< 0.084 U	< 0.04 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	0.19	< 0.1 U		< 0.13 U	0.057 J	< 0.1 U	0.12	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	0.21	< 0.1 U		< 0.13 U	0.03 J	< 0.1 U	0.066 J	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	0.45	< 0.11 U		< 0.14 U	0.042 J	< 0.11 U	0.14	< 0.17 U	< 0.096 U	< 0.14 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.038 J	< 0.014 U	0.045 J
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.11 J
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.015 J	< 0.014 U	0.13 J
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 UT		< 0.028 U	< 0.032 U	< 0.079 U	0.87	0.05 J	1.2
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.075 U	4	< 0.013 U	4.6
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.076 U	0.18 J	< 0.014 U	0.27 J
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.89	< 0.013 U	1.3
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.011 J	< 0.013 U	< 0.0089 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.0078 J	< 0.013 U	< 0.0091 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	1.4	< 0.013 U	1.7
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.092	< 0.12 U	0.077 J
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.33	< 0.11 U	0.094
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.021 J	< 0.12 U	< 0.018 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.028 J	< 0.13 U	0.056 J
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.02 U	< 0.037 UT	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.02 J	< 0.013 U	0.025 J
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.38	< 0.014 U	0.67
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.019 J	< 0.013 U	0.034 J
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.089 J	< 0.013 U	0.085 J
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.12 J	< 0.013 U	0.22 J
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.38	< 0.013 U	0.37
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.14 J	< 0.013 U	0.16 J
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.22 J	< 0.013 U	0.53
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.064 J	< 0.11 U	< 0.018 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.03 J	< 0.13 U	0.024 J
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.14 U	< 0.14 UT	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 UT	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.085 U	< 0.0073 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	2.1	< 0.013 U	0.6
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.038 J	< 0.014 U	0.05 J
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.02 U	< 0.037 UT	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 UT	0.019 J	< 0.014 U	0.021 J
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.2 U	< 0.36 U	< 0.59 U		< 0.26 U	< 0.3 U	< 0.75 U	2.1 J	< 0.13 U	0.78 J
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.65	< 0.013 U	0.98
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.93	< 0.11 U	1
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.1	< 0.11 U	1.7
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	0.024 J	< 0.014 U	< 0.0094 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.033 J	< 0.015 U	0.039 J
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.023 J	< 0.014 U	0.024 J
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.0091 J	< 0.013 U	0.015 J
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.62	< 0.014 U	1.3
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 U	0.65	< 0.015 U	1.3
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.022 U	< 0.04 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	0.067 J	< 0.015 U	0.16 J
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.067 J	< 0.013 U	0.13 J
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.21 U	< 0.37 U	< 0.61 U		< 0.27 U	< 0.31 U	< 0.76 U	8.7	< 0.14 U	5.5
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.032 J
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.013 J	< 0.013 U	0.0098 J
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.31 J	< 0.013 U	0.5
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.074 J	< 0.013 U	0.13 J
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.018 J	< 0.013 U	0.021 J
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.28 J	< 0.013 U	0.41
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.014 J
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.019 J	< 0.1 U	0.024 J
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.69	< 0.11 U	0.6
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.16	< 0.11 U	0.34
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	1.2	< 0.11 U	1.2

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated		< 0.11 U	< 0.25 U	< 0.37 U	< 0.47 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated		< 0.12 U	< 0.25 U	< 0.38 U	< 0.48 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated			0.072	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated			0.517	< 0.02 U	< 0.015 U	< 0.12 U	0.021 J	< 0.15 U	< 0.12 U	< 0.042 U	0.037 J
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated			0.243	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.035 J
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated			0.239	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.035 J
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated			ND	< 0.02 U	0.022 J	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated			0.425	< 0.019 U	< 0.015 U	< 0.12 U	0.018 J	< 0.15 U	< 0.12 U	< 0.042 U	0.053 J
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated			0.018	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated			4.234	< 0.021 U	0.063 J	< 0.13 U	0.086	< 0.16 U	< 0.13 U	< 0.045 U	0.36
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated			0.491	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.049 J
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated			0.026	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated			0.062	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated			0.092	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated			ND	< 0.019 U	< 0.014 U	< 0.12 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated			0.223	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated			ND	< 0.011 U	< 0.011 UT	< 0.019 UT	< 0.012 UT	< 0.023 U	< 0.014 UT	< 0.065 U	< 0.014 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated			0.0552	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.014 J
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated			1.334	< 0.0097 U	0.099 J	< 0.017 U	0.028 J	< 0.02 U	< 0.012 U	< 0.057 U	0.088
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated			0.181	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.026 J
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated			3.694	0.039 J	< 0.01 U	< 0.018 U	0.079 J	< 0.021 U	< 0.013 U	< 0.06 U	0.35
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated			2.608	0.065 J	< 0.01 U	< 0.018 U	0.099 J	< 0.021 U	< 0.012 U	< 0.059 U	0.2
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated			1.474	< 0.0099 U	0.012 J	< 0.017 U	0.033 J	< 0.02 U	< 0.012 U	< 0.057 U	0.17
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated			1.382	0.026 J	< 0.0099 U	< 0.017 U	0.043 J	< 0.02 U	< 0.012 U	< 0.057 U	0.13
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated			1.857	0.042 J	< 0.0097 U	< 0.017 U	0.063 J	< 0.02 U	< 0.012 U	< 0.056 U	0.18
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated			8.772	< 0.09 U	0.4	< 0.56 U	0.27 J	< 0.68 U	< 0.57 U	< 0.19 U	0.65
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated			3.4	< 0.021 U	0.16	< 0.13 U	0.12	< 0.16 U	< 0.13 U	< 0.046 U	0.25
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated			0.0742	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	0.013 J
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated			0.292	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	0.027 J
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated			1.485	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.12
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated			0.036	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.013 J
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated			3.046	< 0.01 U	0.031 J	< 0.018 U	0.069 J	< 0.021 UT	< 0.012 U	< 0.059 U	0.3
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated			0.04	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated			0.0603	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.012 J
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated			0.1926	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.018 J
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated			0.184	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	0.022 J
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated			0.041	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.014 J
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated			0.0754	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.016 J
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated			1.416	< 0.01 U	0.027 J	< 0.017 U	0.013 J	< 0.021 UT	< 0.012 U	< 0.059 U	0.12
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated			1.099	< 0.01 U	0.025 J	< 0.018 U	0.018 J	< 0.021 UT	0.014 J	< 0.059 U	0.077
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated			0.1809	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.059 U	0.019 J
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated			2.778	0.014 J	0.09 J	< 0.018 U	0.11 J	< 0.021 UT	0.015 J	< 0.059 U	0.19
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated			0.295	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 U	0.015 J
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated			0.1654	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.021 J
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated			0.036	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated			0.0427	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.015 J
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**	**Butylbenzyl phthalate**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	0.04 J	0.041 J	< 0.02 U	0.054 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.032 U	0.026 J	< 0.022 U	0.033 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.4 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.03 U	0.029 J	< 0.021 U	0.022 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.029 U	0.035 J	< 0.02 U	0.083	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	0.36	0.38	0.21	0.33	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	0.043 J	0.047 J	0.023 J	0.036 J	< 0.13 U	< 0.012 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.03 U	0.018 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.031 U	0.024 J	< 0.022 U	0.019 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.028 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.024 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.0094 U	0.029 J	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.0098 UT	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.011 UT	< 0.01 UT	< 0.0077 UT	< 0.012 UT	< 0.031 UT	< 0.014 UT	< 0.0071 U	< 0.021 U	< 0.016 UT	< 0.018 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.0091 UT	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.0094 UT	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.0091 UT	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.0092 UT	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.0091 UT	0.011 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	0.15	0.21	0.08	0.14 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.0092 U	0.02 J	0.011 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	0.26	0.39	0.14	0.15 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	0.14	0.2	0.087	0.085 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	0.13	0.16	0.068	0.053 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	0.094	0.13	0.041	0.049 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	0.12	0.17	0.052	0.059 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	0.75	1.2	0.35	0.73	< 0.57 U	< 0.057 U	< 0.12 U	< 1.7 U	< 0.67 U	< 1.1 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	0.29	0.4	0.16	0.33	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0099 U	0.012 J	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	0.024 J	0.034 J	0.013 J	0.019 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	0.11	0.2	0.089	0.085 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.0093 U	0.012 J	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	0.22	0.32	0.14	0.13 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	0.012 J	0.023 J	0.0078 J	0.014 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	0.011 J	0.017 J	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.0092 U	0.01 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	0.16	0.2	0.077	0.095 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	0.077	0.15	0.044	0.071 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	0.039 J
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	0.017 J	0.026 J	0.0089 J	0.015 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	0.18	0.23	0.092	0.11 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	0.021 J	0.028 J	< 0.0075 U	0.096 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	0.013 J	0.022 J	0.0094 J	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.0095 U	0.0099 J	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.059 J	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.061 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.063 J	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.07	< 0.043 U	< 0.12 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.23 U	0.023 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.33	0.088	< 0.13 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.047 J	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.21 U	< 0.015 U	< 0.086 U	< 0.11 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.036 U	< 0.042 U	< 0.12 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	0.28 J	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	0.013 J
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.061 U	< 0.015 UT	< 0.07 U	< 0.022 UT	< 0.018 UT	< 0.014 UT	< 0.014 UT	< 0.0067 UT	< 0.017 UT	< 0.013 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.011 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.13 J	0.032 J	< 0.011 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.027 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.056 U	0.028 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.33 J	< 0.016 U	0.018 J
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.056 U	0.043 J	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.2 J	0.033 J	0.036 J
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.054 U	0.026 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.15 J	0.022 J	< 0.012 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.054 U	0.017 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.13 J	0.015 J	0.014 J
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.053 U	0.021 J	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.16 J	0.024 J	0.023 J
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 1 U	0.1 J	2.4	< 0.55 U	< 0.072 U	< 0.58 U	< 0.52 U	0.8	< 0.2 U	< 0.58 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.24 U	0.036 J	0.44	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.31	0.086	< 0.14 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0072 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.027 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.17 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.24 J	0.024 J	< 0.012 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0083 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.012 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.015 J	< 0.016 U	< 0.013 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0072 J	< 0.015 U	< 0.011 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0080 J	< 0.015 U	< 0.011 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.15 J	0.027 J	< 0.012 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.12 J	0.018 J	0.021 J
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.056 U	0.041 J	< 0.063 U	< 0.02 U	0.032 J	< 0.013 U	< 0.013 U	0.2 J	0.038	0.037 J
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.019 J	0.041	< 0.013 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0068 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.31 U	< 0.025 U	< 0.11 U	< 0.11 U	< 0.13 U	< 0.14 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.06 U	< 0.025 UT	< 0.013 UT	< 0.047 UT	< 0.09 UT	< 0.015 UT	< 0.021 UT	< 0.16 UT	< 0.029 UT	< 0.19 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.075 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 1.5 UT	< 0.12 U	< 0.55 U	< 0.53 U	< 0.62 U	< 0.68 U	< 0.91 U	< 2.7 UT	< 0.61 U	< 9.7 UT
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 UT	< 0.027 U	< 0.18 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			0.023 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.2 U	< 0.11 U			0.059 J	0.013 J	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.22 U	< 0.12 U			0.033 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			0.033 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.2 U	< 0.11 U			0.037 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.21 U	< 0.11 U			0.57	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.21 U	< 0.11 U			0.08	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.21 U	< 0.11 U			0.022 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.21 U	< 0.11 U			0.022 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.2 U	< 0.1 U			< 0.017 U	< 0.013 U	< 0.023 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.038 U		< 0.031 U		0.035 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.042 UT		< 0.034 U		< 0.014 UT	< 0.012 UT	< 0.019 UT	< 0.0084 UT	< 0.035 UT	< 0.014 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.037 U		< 0.03 U		0.13 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.037 U		< 0.03 U		0.033 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.039 U		< 0.032 U		0.61	0.033 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.038 U		< 0.031 U		0.43	0.038 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.037 U		< 0.03 U		0.27 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.037 U		< 0.03 U		0.21 J	0.019 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.037 U		< 0.03 U		0.29 J	0.034 J	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.93 U	< 0.49 U			1.3	0.072 J	< 0.11 U	< 0.091 U	< 0.16 U	< 0.55 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.22 U	< 0.11 U			0.43	0.025 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.04 U		< 0.032 U		0.04 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.038 U		< 0.031 U		0.27 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.039 U		< 0.031 U		0.6	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.037 U		< 0.03 U		0.018 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.04 U		< 0.033 U		0.028 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.037 U		< 0.03 U		0.013 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		0.17 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.039 U		< 0.031 U		0.12 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.039 U		< 0.031 U		0.02 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		0.4	0.064 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.041 U		< 0.033 U		0.015 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.039 U		< 0.031 U		0.029 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U

DRAFT

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	0.037 J	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	0.02 J	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	0.019 J	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	0.33	< 0.1 U		< 0.13 U	0.16	< 0.11 U	0.27	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	0.039 J	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.033 U	< 0.095 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.033 U	< 0.095 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.033 U	< 0.094 U		< 0.12 U	< 0.016 U	< 0.096 U	< 0.013 U	< 0.15 U	< 0.083 U	< 0.12 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.045 J	< 0.022 U	0.062 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 UT	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.015 UT	< 0.015 UT		< 0.11 UT	< 0.011 UT	< 0.025 UT	< 0.0068 UT	< 0.03 U	< 0.094 U	< 0.045 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 UT	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 UT	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	0.14	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0057 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	0.26	< 0.014 U		< 0.1 U	0.019 J	< 0.023 U	0.033 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	0.14	< 0.013 U		< 0.1 U	0.018 J	< 0.022 U	0.011 J	< 0.027 UT	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	0.078	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	0.061	< 0.013 U		< 0.1 U	0.02 J	< 0.022 U	0.014 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	0.078	< 0.013 U		< 0.098 U	0.027 J	< 0.021 U	0.015 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	0.62	< 0.45 U		< 0.59 U	0.24 J	< 0.46 U	0.18 J	< 0.71 U	< 0.4 U	< 0.58 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	0.29	< 0.11 U		< 0.14 U	0.07 J	< 0.11 U	0.059 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	0.042	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	0.023 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.027 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	0.14	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0090 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	0.22	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.023 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	0.04	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	0.04	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	0.052	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0078 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	0.047	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	0.0063 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	0.11	< 0.013 U		< 0.1 U	0.024 J	< 0.022 U	0.019 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	0.081	< 0.013 U		< 0.1 U	0.075 J	< 0.022 U	0.063 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	0.016 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	0.13	< 0.013 U		< 0.1 U	0.064 J	< 0.022 U	0.17 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	0.032 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.019 J	< 0.022 U	0.027 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.019 J	< 0.11 U	0.03 J
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.071	< 0.1 U	0.065 J
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.055 J
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	0.057 J
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.041 J	< 0.1 U	0.069
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.018 J	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.29	< 0.11 U	0.63
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.043 J	< 0.1 U	0.084
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.026 J
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	0.022 J
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.027 J
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.022 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.099 U	< 0.016 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 UT		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.097 J	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.022 UT	< 0.04 UT	< 0.064 U		< 0.029 U	< 0.032 UT	< 0.081 U	< 0.0069 UT	< 0.015 UT	< 0.0098 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0092 J	< 0.013 U	0.01 J
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.07 U	0.036 J	< 0.013 U	0.17 J
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 UT		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.028 J	< 0.013 U	0.036 J
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0058 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.4	< 0.013 U	0.62
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.47	< 0.013 U	0.41
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.071 U	0.12 J	< 0.013 U	0.22 J
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.071 U	0.21 J	< 0.013 U	0.21 J
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 UT		< 0.025 U	< 0.028 U	< 0.07 U	0.3 J	< 0.012 U	0.27 J
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.57 U	< 0.58 U	< 1.1 U		< 0.11 U	< 0.52 U	< 2.5 U	0.65	< 0.47 U	1.2
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.21	< 0.11 U	0.44
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.025 J	< 0.014 U	0.033 J
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.052 J	< 0.013 U	0.24 J
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.22 J	< 0.013 U	0.54
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.029 U	< 0.071 U	0.011 J	< 0.013 U	0.017 J
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.022 J	< 0.014 U	0.022 J
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0088 J	< 0.013 U	0.011 J
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.0081 J	< 0.013 U	0.014 J
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.055 J	< 0.013 U	0.22 J
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.13 J	< 0.013 U	0.13 J
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.019 J	< 0.013 U	0.02 J
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.47	< 0.013 U	0.38
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.015 J	< 0.014 U	0.013 J
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.021 J	< 0.013 U	0.03 J
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.0090 J	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	0.011 J
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.11 U	< 0.11 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated		0.39	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated		< 0.012 UT	< 0.027 UT	< 0.04 UT	< 0.051 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated		< 0.62 U	< 0.65 U	< 0.54 U	< 0.52 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.045 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated			1.467	< 0.01 U	0.014 J	< 0.017 U	0.065 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.14
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated			0.1419	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.064 U	0.017 J
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated			0.6883	< 0.0098 U	< 0.0098 U	< 0.017 U	0.024 J	< 0.02 UT	< 0.012 U	< 0.057 U	0.065
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated			ND	< 0.0099 U	< 0.0099 UT	< 0.017 UT	< 0.011 UT	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated			0.04	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated			0.125	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.017 J
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated			0.24	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	0.026 J
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated			0.0574	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.013 J
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated			0.216	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.028 J
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated			1.152	< 0.01 U	0.01 J	< 0.017 U	0.023 J	< 0.021 U	< 0.012 U	< 0.059 U	0.12
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated			0.024	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 UT	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated			0.071	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.015 J
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.024 UT	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated			0.038	< 0.0096 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated			0.212	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 UT	0.023 J
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated			0.286	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.03 J
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated			0.353	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.046
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated			ND	< 0.0094 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.019 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated			3.784	0.092 J	0.036 J	< 0.018 U	0.16 J	< 0.021 U	< 0.013 U	< 0.06 U	0.19
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated			0.275	< 0.01 U	0.016 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	0.026 J
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated			0.355	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.032 J
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated			0.386	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.035
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated			2.292	< 0.0097 U	0.063 J	< 0.017 U	0.046 J	< 0.02 U	0.016 J	< 0.056 U	0.18
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated			0.01	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated			0.0083	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated			0.766	< 0.01 U	0.014 JT	< 0.018 UT	0.013 JT	< 0.021 UT	< 0.012 U	< 0.059 U	0.068
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated			0.011	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.0090 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	0.098	0.14	0.058	0.054 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	0.01 J	0.015 J	< 0.0076 U	0.012 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	0.045	0.06	0.024 J	0.026 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.0092 UT	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 UT	< 0.012 UT	< 0.0063 U	< 0.018 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	0.011 J	0.014 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	0.02 J	0.023 J	0.011 J	0.012 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	0.019 J	0.026 J	0.012 J	0.011 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	0.11	0.14	0.052	0.069 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.0093 UT	< 0.0090 U	< 0.0068 U	< 0.01 UT	< 0.027 UT	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.0093 U	0.012 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.0089 U	0.011 J	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	0.018 J	0.024 J	0.012 J	0.012 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 UT	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	0.021 J	0.031 J	0.017 J	0.014 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.0088 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	0.032 J	0.057	0.031 J	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.0088 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	0.29	0.18	0.048	0.5	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	0.02 J	0.022 J	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	0.026 J	0.054	0.021 J	0.022 J	< 0.027 U	< 0.012 UT	< 0.0062 U	0.024 J	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	0.028 J	0.036	0.019 J	0.024 J	< 0.027 U	< 0.012 UT	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	0.17	0.25	0.092	0.12 J	< 0.027 U	< 0.012 UT	< 0.0062 U	0.027 J	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 UT	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 UT	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	0.051 T	0.083	0.033 J	0.039 JT	< 0.028 UT	< 0.012 UT	< 0.0065 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.11 J	0.016 J	< 0.012 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 UT	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.01 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 UT	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.052 UT	< 0.013 U	< 0.06 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.053 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.054 UT	< 0.013 UT	< 0.061 UT	< 0.019 UT	< 0.016 U	< 0.012 UT	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.012 J	< 0.015 U	< 0.011 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.022 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0080 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.023 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.11 J	0.024 J	< 0.012 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 UT	< 0.016 U	< 0.012 UT	< 0.012 U	< 0.0059 U	< 0.015 UT	< 0.012 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0070 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.062 UT	< 0.015 U	< 0.071 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.052 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.02 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 UT	< 0.012 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.023 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.05 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.2 J	0.063	< 0.012 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.021 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.042 J	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.034 J	< 0.015 U	0.013 J
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.18 J	0.03 J	0.027 J
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 UT	< 0.013 U	0.079 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.053 UT	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.051 UT	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.055 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.053 UT	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.052 UT	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.051 UT	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.051 UT	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	0.033 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.052 UT	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.052 UT	< 0.022 UT	< 0.011 U	< 0.041 UT	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 UT	< 0.025 U	< 0.17 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.053 U	< 0.022 UT	< 0.011 U	< 0.042 UT	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 UT	< 0.025 U	< 0.17 UT
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	0.016 J	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 UT	< 0.025 U	< 0.17 UT
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.075 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.039 U	< 0.075 U	< 0.012 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	< 0.054 U	< 0.023 UT	< 0.012 U	< 0.043 UT	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW827	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.038 U		< 0.031 U		0.28 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0072 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		0.11 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 UT	< 0.0074 UT	< 0.03 U	< 0.012 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 UT	< 0.012 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		0.027 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 UT	< 0.012 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.039 U		< 0.031 U		0.043 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.039 U		< 0.031 U		0.013 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.037 U		< 0.03 U		0.033 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		0.16 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 UT	< 0.031 UT	< 0.012 UT
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.038 U		< 0.03 U		0.014 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.036 U		< 0.029 U		0.014 J	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.037 U		< 0.03 U		0.03 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.037 U		< 0.03 U		0.043 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		0.052 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0070 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0072 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.039 U		< 0.032 U		0.28 J	0.091 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.039 U		< 0.032 U		0.033 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		0.046 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		0.047 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		0.31 J	0.024 J	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	< 0.039 U		< 0.031 U		0.11 J	< 0.01 U	< 0.017 UT	< 0.0076 UT	< 0.031 U	< 0.012 UT
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U

DRAFT

													Indeno (1,2,3-cd)pyrene	**2-Methylphenol**	**3/4-Methylphenol**	**Isophorone**	**2-Methylnaphthalene**	**4-methylphenol**	**Naphthalene**	**2-Nitroaniline**	**3-Nitroaniline**	**4-Nitroaniline**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 UT	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 UT	< 0.04 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	0.076	< 0.013 U		< 0.1 U	< 0.0099 UT	< 0.022 U	0.02 J	< 0.027 U	< 0.084 UT	< 0.041 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 UT	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 UT	< 0.04 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	0.055	< 0.015 U		< 0.11 U	< 0.011 UT	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 UT	< 0.045 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 UT	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 UT	< 0.04 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 UT	< 0.039 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 UT	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 UT	< 0.042 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 UT	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 UT	< 0.04 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 UT	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 UT	< 0.04 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 UT	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 UT	< 0.039 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 UT	< 0.039 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	0.072	< 0.013 U		< 0.1 U	< 0.0096 UT	< 0.022 U	0.0073 J	< 0.026 U	< 0.082 UT	< 0.04 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 UT		< 0.1 UT	< 0.0097 UT	< 0.022 UT	< 0.0060 UT	< 0.026 U	< 0.082 UT	< 0.04 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.017 J	< 0.022 U	0.027 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	0.075	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.014 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	0.013 J	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.014 UT	< 0.013 UT		< 0.1 UT	< 0.0098 UT	< 0.022 UT	< 0.0060 UT	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	0.014 J	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	0.053	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0057 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.01 J	< 0.022 U	0.011 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0057 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	0.22	< 0.014 U		< 0.1 U	0.18 J	< 0.023 U	0.18 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	0.015 J	< 0.014 U		< 0.11 U	0.039 J	< 0.023 U	0.074 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	0.024 J	< 0.013 U		< 0.099 UT	< 0.0095 U	< 0.021 U	0.016 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	0.029 J	< 0.013 U		< 0.1 UT	0.043 J	< 0.022 U	0.038 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	0.15	< 0.013 U		< 0.098 UT	0.14 J	< 0.021 U	0.24 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 UT	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 UT	< 0.0098 U	< 0.022 U	0.0083 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	0.086	< 0.013 UT		< 0.1 UT	0.014 JT	< 0.022 UT	0.04 JT	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.02 U	< 0.035 U	0.066 J		< 0.026 U	< 0.029 U	< 0.072 U	0.17 J	< 0.013 U	0.24 J
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.0079 J	< 0.014 U	0.015 J
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.092 J	< 0.013 U	0.11 J
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.019 UT	< 0.035 UT	< 0.056 U		< 0.025 U	< 0.028 UT	< 0.071 U	< 0.0061 UT	< 0.013 UT	< 0.0086 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.013 J	< 0.013 U	< 0.0089 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.023 J	< 0.013 U	0.021 J
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.019 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 UT
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.034 J	< 0.013 U	0.049 J
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0094 J	< 0.013 U	0.014 J
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.022 J	< 0.013 U	0.042 J
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.075 J	< 0.013 U	0.18 J
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.011 J	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.019 UT	< 0.035 UT	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 UT	< 0.0087 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.01 J	< 0.013 U	0.013 J
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	0.013 J
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.018 J	< 0.012 U	0.041 JT
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 UT
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 UT
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.018 J	< 0.012 U	0.036 J
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0058 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.018 J	< 0.013 U	0.056 J
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0058 U	< 0.012 U	< 0.0082 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 UT
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.56	< 0.013 U	0.73
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.032 J	< 0.013 U	0.032 J
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 UT	< 0.028 U	< 0.07 U	0.027 J	< 0.013 U	0.045 J
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated	< 0.019 U	0.044 J	< 0.056 U		< 0.025 UT	< 0.028 U	0.13 J	0.044 J	< 0.013 U	0.052 J
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 UT	< 0.028 U	< 0.07 U	0.2 J	< 0.013 U	0.3 J
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 UT	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.01 J
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 UT	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated	< 0.02 UT	< 0.036 UT	< 0.058 U		< 0.026 UT	< 0.029 U	< 0.073 U	0.064 JT	< 0.013 UT	0.1 J
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.011 J	< 0.013 U	< 0.0090 U

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated		< 0.01 U	< 0.022 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated		< 0.01 U	< 0.022 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated		< 0.011 U	0.1 J	< 0.035 U	0.052 J
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated			0.63	< 0.011 U	0.016 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.048
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated			0.73	< 0.011 U	0.028 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.053
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated			2.948	< 0.011 U	0.1 J	< 0.019 U	0.044 J	< 0.023 U	< 0.014 U	< 0.064 U	0.25
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated			1.042	< 0.01 U	0.018 J	< 0.018 U	0.02 J	< 0.022 U	< 0.013 U	< 0.061 U	0.097
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated			3.784	< 0.015 U	0.036 J	0.047 J	0.036 J	< 0.032 U	0.024 J	< 0.089 U	0.27
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated			1.622	< 0.011 U	0.027 J	< 0.018 U	0.033 J	< 0.022 U	< 0.013 U	< 0.061 U	0.15
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated			0.575	< 0.01 U	0.012 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.049
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated			0.1768	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.026 J
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated			0.1307	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.02 J
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated			0.054	< 0.01 U	0.016 J	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated			0.041	< 0.01 U	0.019 J	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated			0.02	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated			0.162	< 0.011 U	0.054 J	< 0.019 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	0.024 J
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated			0.096	< 0.01 U	0.042 J	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated			0.107	< 0.01 U	0.015 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated			ND	< 0.011 U	0.099 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated			0.228	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.024 J
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated			0.241	< 0.01 U	0.042 J	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated			0.34	< 0.099 U	< 0.099 U	< 0.17 U	< 0.11 U	< 0.2 UT	< 0.12 U	< 0.57 U	< 0.12 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated			ND	< 0.011 U	< 0.011 UT	< 0.019 UT	< 0.012 UT	< 0.022 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated			0.89	< 0.01 U	0.014 J	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.094
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated			0.1587	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.019 J
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated			0.783	< 0.01 U	< 0.01 U	< 0.018 U	0.02 J	< 0.022 UT	< 0.013 U	< 0.06 U	0.076
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated			0.0074	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	< 0.014 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated			0.1409	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.017 J
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated			0.1239	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	0.017 J	< 0.057 U	0.013 J
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated			0.696	< 0.021 U	0.022 J	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.052 J
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated			2.239	< 0.01 U	0.053 J	< 0.018 U	0.046 J	< 0.022 U	0.013 J	< 0.06 U	0.17
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 UT	< 0.012 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 UT	< 0.013 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated			0.615	< 0.011 U	0.032 J	< 0.018 U	0.017 J	< 0.022 UT	< 0.013 U	< 0.062 UT	0.036 J
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated			16.682	0.03 J	0.54	< 0.019 U	0.3 J	< 0.023 UT	0.1 J	< 0.064 UT	1.2
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated			3.371	0.015 J	0.051 J	< 0.02 U	0.077 J	< 0.024 UT	< 0.014 U	< 0.067 UT	0.29
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 UT	< 0.012 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.065 UT	< 0.014 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 UT	< 0.013 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated			0.231	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	0.024 J
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated			5.076	< 0.012 U	0.18 J	< 0.02 U	0.11 J	< 0.024 UT	0.027 J	< 0.067 UT	0.41
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 UT	< 0.012 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated			0.602	< 0.011 U	0.013 J	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.065 UT	0.056
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated			ND	< 0.013 U	< 0.013 U	< 0.023 UT	< 0.014 U	< 0.027 UT	< 0.016 U	< 0.076 UT	< 0.016 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	0.055	0.087	0.029 J	0.061 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	0.043	0.074	0.028 J	0.036 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	0.25	0.41	0.13	0.2 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	0.081	0.12	0.051	0.052 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	0.28	0.51	0.17	0.24 J	< 0.042 U	< 0.019 U	< 0.0098 U	0.29 J	< 0.021 U	0.11 J
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	0.13	0.19	0.062	0.09 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	0.05	0.066	0.031 J	0.041 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	0.014 J	0.024 J	< 0.0070 U	0.013 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	0.0097 J	0.014 J	0.0090 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	0.68	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	0.054 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	0.041 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	0.02 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	0.099 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	0.096 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	0.051 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	0.019 J	0.026 J	0.011 J	0.016 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	0.19 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.092 U	< 0.09 U	< 0.068 U	0.19 J	< 0.27 U	< 0.12 U	< 0.063 U	< 0.18 U	< 0.14 U	< 0.16 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.01 UT	< 0.0098 UT	< 0.0074 U	< 0.011 UT	< 0.03 U	< 0.013 UT	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	0.095	0.14	0.046	0.075 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	0.014 J	0.017 J	0.0088 J	0.014 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	0.064	0.08	0.03 J	0.042 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	0.013 J	0.018 J	< 0.0071 U	0.014 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.0092 U	0.012 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	0.057 J	0.075	0.023 J	0.049 J	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	0.17	0.28	0.099	0.16 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	0.044	0.064	0.019 J	0.1 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	1.6	2.2	0.62	1.7	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	0.28	0.37	0.13	0.2 J	< 0.032 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	0.019 J	0.026 J	0.013 J	0.014 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	0.44	0.65	0.24	0.4 J	< 0.032 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.0095 UT	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	0.027 J	0.047	0.014 J	0.044 J	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.012 UT	< 0.012 U	< 0.0090 U	< 0.014 UT	< 0.036 UT	< 0.016 UT	< 0.0083 UT	< 0.024 U	< 0.018 U	< 0.022 U

DRAFT

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.065 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.084 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.3 J	0.043	0.013 J
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.098 J	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.084 U	0.037 J	0.2 J	< 0.03 U	< 0.025 U	< 0.019 U	< 0.019 U	0.35 J	0.048 J	0.047 J
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.14 J	< 0.016 U	0.019 J
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.048 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.023 J	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.016 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.062 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.54 U	< 0.13 U	< 0.61 U	< 0.19 U	< 0.16 U	< 0.12 U	< 0.12 U	< 0.059 U	< 0.15 U	< 0.12 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 UT	< 0.018 U	< 0.013 UT	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.096 J	0.02 J	< 0.012 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.012 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.076 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.011 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0080 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.082	< 0.047 U	< 0.14 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.057 U	0.02 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	0.041	0.035 J
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.058 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.043 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.061 UT	0.13 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	1.2	0.37	0.21 J
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.063 UT	0.029 J	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	0.3 J	0.059	0.032 J
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.061 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.063 UT	0.036 J	< 0.072 U	< 0.023 U	0.028 J	< 0.014 U	< 0.014 U	0.42	0.079	0.073 J
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.061 UT	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.091 J	< 0.017 U	0.013 J
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.072 UT	< 0.018 U	< 0.082 U	< 0.026 U	< 0.021 U	< 0.016 UT	< 0.016 U	< 0.0078 U	< 0.02 U	< 0.015 U

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.04 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	0.05 J	< 0.019 U	< 0.15 UT	< 0.026 U	< 0.18 UT
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	0.068 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.064 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.054 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.024 J	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.02 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.026 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	0.014 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	0.024 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	0.034 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.082 U	< 0.035 U	< 0.017 U	< 0.064 U	< 0.12 U	0.055 J	< 0.029 U	< 0.22 U	< 0.039 U	< 0.27 U
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	0.02 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	0.022 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 UT	< 0.025 U	< 0.17 UT
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.52 U	< 0.22 U	< 0.11 U	< 0.41 U	< 0.79 U	< 0.13 U	< 0.18 U	< 1.4 U	< 0.25 U	< 1.7 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.057 U	< 0.024 UT	< 0.012 U	< 0.045 UT	< 0.086 U	< 0.014 UT	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 UT	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.07 UT	< 0.03 U	< 0.015 U	< 0.055 UT	< 0.1 U	< 0.017 U	< 0.024 U	< 0.19 U	< 0.033 U	< 0.23 U

													2,4-Dinitrotoluene	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**	**Hexachloroethane**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.04 U		< 0.033 U		0.067 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.04 U		< 0.033 U		0.1 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.042 U		< 0.034 U		0.39	0.012 J	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.04 U		< 0.032 U		0.17 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.058 U		< 0.047 U		0.57	< 0.016 U	< 0.026 U	< 0.011 U	< 0.047 U	< 0.019 U
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.04 U		< 0.032 U		0.25 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.039 U		< 0.032 U		0.075 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.038 U		< 0.031 U		0.025 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.037 U		< 0.03 U		0.023 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.038 U		< 0.031 U		0.035 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.37 U		< 0.3 U		< 0.12 U	< 0.1 U	< 0.16 U	< 0.074 U	< 0.3 U	< 0.12 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 UT	< 0.033 U	< 0.013 UT
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.038 U		< 0.031 U		0.088 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.038 U		< 0.031 U		0.018 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.039 U		< 0.032 U		0.11 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.039 U		< 0.032 U		0.016 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.22 U	< 0.11 U			0.084	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.039 U		< 0.032 U		0.32 J	0.02 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.04 U		< 0.033 U		0.058 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.042 U		< 0.034 U		1.6	0.082 J	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.044 U		< 0.035 U		0.5	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.039 U		< 0.032 U		0.034 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.044 U		< 0.035 U		0.6	0.027 J	< 0.019 U	< 0.0086 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 UT
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.042 U		< 0.034 U		0.069 J	0.015 J	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.05 U		< 0.04 U		< 0.016 U	< 0.013 U	< 0.022 U	< 0.0098 UT	< 0.04 U	< 0.016 UT

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	0.057	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.032 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	0.037	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.055 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	0.28	< 0.015 U		< 0.11 U	0.044 J	< 0.024 U	0.069 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	0.12	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.023 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	0.37	< 0.02 U		< 0.16 U	0.15 J	< 0.034 U	0.15 J	< 0.041 U	< 0.13 U	< 0.062 U
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	0.18	< 0.014 U		< 0.11 U	0.038 J	< 0.023 U	0.057 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	0.086	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.023 J	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.0088 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	0.039	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	0.056	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	0.051	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.14 U	< 0.13 U		< 1 U	< 0.097 U	< 0.22 U	< 0.06 U	< 0.26 U	< 0.82 U	< 0.4 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.015 U	< 0.014 UT		< 0.11 UT	< 0.011 UT	< 0.024 U	< 0.0066 UT	< 0.029 U	< 0.09 U	< 0.044 UT
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	0.087	< 0.013 U		< 0.1 U	0.01 J	< 0.022 U	0.024 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	0.016 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0079 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	0.052	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.013 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	0.014 J	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	0.01 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.062 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	0.036 J	< 0.1 U		< 0.14 U	0.092	< 0.11 U	0.027 J	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	0.22	< 0.014 U		< 0.11 U	0.047 J	< 0.023 U	0.13 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	0.057	< 0.014 U		< 0.11 U	0.012 J	< 0.023 U	0.074 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	1.8	< 0.015 U		< 0.11 U	0.37 J	< 0.024 U	1.2	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	0.24	< 0.015 U		< 0.12 U	0.044 J	< 0.025 U	0.14 J	< 0.031 U	< 0.096 U	< 0.047 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	0.41	< 0.015 U		< 0.12 U	0.079 J	< 0.025 U	0.37 J	< 0.031 U	< 0.096 U	< 0.047 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 UT	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	0.043	< 0.015 U		< 0.11 U	0.012 J	< 0.024 U	0.027 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.018 U	< 0.017 U		< 0.13 UT	< 0.013 UT	< 0.029 U	< 0.0080 UT	< 0.035 U	< 0.11 U	< 0.053 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.038 J	< 0.014 U	0.091 J
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.1 J	< 0.014 U	0.12 J
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.15 J	< 0.014 U	0.42
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.06 J	< 0.014 U	0.15 J
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.03 U	< 0.054 U	< 0.088 U		< 0.039 U	< 0.044 U	< 0.11 U	0.3 J	< 0.02 U	0.49 J
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.12 J	< 0.014 U	0.22 J
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.037 J	< 0.013 U	0.069 J
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.014 J	< 0.013 U	0.029 J
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.016 J	< 0.013 U	0.023 J
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.022 U	< 0.04 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	< 0.0069 U	< 0.015 U	< 0.0098 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.018 J	< 0.013 U	0.038 J
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.19 U	< 0.35 U	< 0.56 U		< 0.25 U	< 0.28 U	< 0.71 U	< 0.061 U	< 0.13 U	0.15 J
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.021 UT	< 0.038 UT	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 UT	< 0.014 U	< 0.0094 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.029 J	< 0.013 U	0.096 J
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	< 0.0069 U	< 0.014 U	< 0.0098 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	0.01 J	< 0.013 U	0.022 J
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.09 J	< 0.013 U	0.13 J
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.0074 J	< 0.014 U	< 0.0096 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.0079 J	< 0.013 U	0.02 J
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.019 J	< 0.013 U	0.0099 J
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.13	< 0.11 U	0.081
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.24 J	< 0.013 U	0.32 J
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.043 J	< 0.014 U	0.06 J
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.88	< 0.014 U	1.9
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.29 J	< 0.015 U	0.48
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.02 J	< 0.013 U	0.041 J
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	0.29 J	< 0.015 U	0.63
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.073 J	< 0.014 U	0.096 J
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.026 UT	< 0.046 UT	< 0.075 U		< 0.033 UT	< 0.038 U	< 0.094 U	< 0.0081 U	< 0.017 UT	< 0.011 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated		< 0.017 U	< 0.037 U	< 0.055 U	< 0.069 U
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated		< 0.11 U	< 0.23 U	< 0.35 U	< 0.44 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated		< 0.013 U	< 0.028 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated		< 0.014 U	< 0.031 U	< 0.047 U	< 0.059 U

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated			2.87	< 0.01 U	0.05 J	< 0.017 U	0.056 J	< 0.021 UT	< 0.012 U	< 0.058 UT	0.24
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 UT	< 0.012 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated			1.437	< 0.011 U	0.07 J	< 0.018 U	0.034 J	< 0.022 UT	< 0.013 U	< 0.062 UT	0.11
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated			0.011	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.06 UT	< 0.013 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated			1.767	0.023 J	< 0.011 U	< 0.018 U	0.047 J	< 0.022 U	< 0.013 U	< 0.062 U	0.15
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated			0.315	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.031 J
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated			2.2626	< 0.01 U	0.013 J	< 0.017 U	0.027 J	< 0.021 U	< 0.012 U	< 0.059 U	0.28
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated			1.116	< 0.011 U	0.014 J	< 0.019 U	0.029 J	< 0.023 U	< 0.014 U	< 0.065 U	0.094
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated			3.479	< 0.011 U	0.1 J	< 0.02 U	0.049 J	< 0.023 U	< 0.014 U	< 0.066 U	0.3
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated			2.002	0.012 J	0.028 J	< 0.019 U	0.044 J	< 0.022 U	< 0.013 U	< 0.063 U	0.16
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated			0.0978	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.066 U	0.019 J
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated			0.108	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.017 J
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated			0.477	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.047
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated			0.289	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.029 J
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated			0.014	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.014 J
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated			0.015	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated			0.438	< 0.011 U	0.019 J	< 0.019 U	0.012 J	< 0.022 U	< 0.013 U	< 0.063 U	0.037 J
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated			0.077	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated			0.0074	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated			0.081	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.018 J
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated			0.641	0.012 J	0.017 J	< 0.018 U	0.016 J	< 0.022 U	< 0.013 U	0.074 J	0.068
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated			1.595	0.017 J	0.023 J	< 0.018 U	< 0.011 U	< 0.022 U	0.013 J	< 0.062 U	0.14
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated			0.2965	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.038
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated			0.2943	< 0.01 U	< 0.01 U	< 0.017 U	0.016 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.042
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated			0.1868	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.039
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated			0.3037	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.06 U	0.042
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated			0.153	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.018 J
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated			0.1089	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.016 J
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated			0.4356	< 0.0098 U	0.028 J	< 0.017 U	0.012 J	< 0.02 U	< 0.012 U	< 0.057 U	0.033 J
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated			0.3787	< 0.01 U	0.023 J	< 0.017 U	0.012 J	< 0.021 U	< 0.012 U	< 0.059 U	0.031 J
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated			5.777	< 0.0098 U	0.25 J	< 0.017 U	0.098 J	< 0.02 U	< 0.012 U	< 0.057 U	0.38
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated			0.087	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.015 J
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated			16.41	0.33 J	0.16 J	< 0.021 U	0.7	< 0.025 U	0.028 J	< 0.071 U	1.4
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated			0.0697	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.016 J
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated			14.03	0.25 J	0.15 J	< 0.019 U	0.58	< 0.022 U	0.03 J	< 0.063 U	1.2
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated			0.38	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	0.041
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated			0.106	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	0.019 J
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated			0.714	< 0.012 U	< 0.012 U	< 0.021 U	0.032 J	< 0.025 U	< 0.015 U	< 0.071 U	0.074
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated			0.131	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.07 U	0.023 J
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated			0.1094	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated			0.121	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated			ND	< 0.012 U	< 0.012 UT	< 0.021 UT	< 0.013 UT	< 0.025 U	< 0.015 U	< 0.07 U	< 0.015 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated			0.314	< 0.01 U	< 0.01 U	< 0.018 U	0.015 J	< 0.021 U	< 0.013 U	< 0.06 U	0.03 J
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated			6.037	0.024 J	0.19 J	< 0.019 U	0.11 J	< 0.023 U	< 0.013 U	< 0.064 U	0.52
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated			7.447	< 0.011 U	0.31 J	0.033 J	0.15 J	< 0.022 U	0.053 J	< 0.061 U	0.61
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated			2.66	0.026 J	0.03 J	< 0.018 U	0.062 J	< 0.021 U	< 0.013 U	< 0.06 U	0.24
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated			0.321	< 0.01 U	< 0.01 U	< 0.018 U	0.012 J	< 0.021 U	< 0.013 U	< 0.06 U	0.034 J
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated			0.0087	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated			3.36	< 0.022 U	0.095	< 0.13 U	0.086	< 0.16 U	< 0.14 U	< 0.047 U	0.3
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated			2.179	< 0.02 U	0.054 J	< 0.13 U	0.047 J	< 0.16 U	< 0.13 U	< 0.044 U	0.19
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated			13.228	< 0.022 U	0.62	< 0.13 U	0.32	< 0.17 U	< 0.14 U	< 0.047 U	1.5
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated			0.136	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.044 UT	< 0.032 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	0.24	0.33	0.11	0.19 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	0.11	0.15	0.056	0.2 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	0.097	0.14	0.051	0.057 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	0.025 J	0.034 J	0.015 J	0.02 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	0.18	0.48	0.16	0.13 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	0.087	0.11	0.043	0.065 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	0.28	0.35	0.13	0.22 J	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	0.14	0.21	0.078	0.12 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	0.012 J	0.013 J	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	0.011 J	0.016 J	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	0.046	0.061	0.025 J	0.036 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	0.023 J	0.037	0.012 J	0.03 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	0.038	0.057	< 0.0075 U	0.052 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0099 U	< 0.0097 U	< 0.0073 U	0.039 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	< 0.0097 U	0.01 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	0.031 J	< 0.0096 U	< 0.0073 U	0.05 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	0.2	0.19	0.08	0.13 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	0.011 J	0.015 J	0.0075 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	0.013 J	0.028 J	0.011 J	0.018 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	0.025 J	0.034 J	0.011 J	0.025 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	0.015 J	0.023 J	0.01 J	0.015 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	0.013 J	0.019 J	0.0089 J	0.011 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	0.042	0.072	0.025 J	0.049 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	0.04	0.064	0.022 J	0.04 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	0.52	0.89	0.28	0.49	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	0.012 J	0.019 J	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	1.2	1.5	0.69	0.71	< 0.033 U	< 0.015 U	< 0.0077 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.0093 U	0.014 J	0.0087 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	1	1.4	0.61	0.63	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	0.037 J	0.057	0.02 J	0.025 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.01 U	0.015 J	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	0.055	0.075	0.033 J	0.03 J	< 0.034 U	< 0.015 U	< 0.0078 U	< 0.023 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	0.012 J	0.019 J	< 0.0083 U	< 0.012 U	< 0.033 U	< 0.015 U	< 0.0077 U	< 0.022 U	< 0.017 U	< 0.02 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	0.012 J	0.016 J	0.0084 J	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	0.01 J	0.018 J	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.011 UT	< 0.011 UT	< 0.0083 U	< 0.012 UT	< 0.033 UT	< 0.015 UT	< 0.0076 U	< 0.022 U	< 0.017 UT	< 0.02 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	0.016 J	0.034 J	< 0.0071 U	0.015 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	0.53	0.77	0.3	0.39	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	0.58	1	0.31	0.36 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	0.23	0.32	0.12	0.13 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	0.023 J	0.03 J	0.014 J	0.014 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	0.32	0.36	0.11	0.33	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	0.22	0.22	0.13	0.14	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	1.2	1.6	0.66	0.85	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.03 U	0.031 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.055 UT	0.019 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.24 J	0.051	0.024 J
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.11 J	0.031 J	0.03 J
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.058 U	0.037 J	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.14 J	0.018 J	< 0.012 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.035 J	< 0.016 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.36	0.05	< 0.012 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.092 J	0.018 J	< 0.013 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.062 U	0.022 J	< 0.071 U	< 0.022 U	0.12 J	< 0.014 U	< 0.014 U	0.34 J	0.067	< 0.013 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.059 U	0.02 J	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.17 J	0.033 J	0.014 J
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.019 U	< 0.014 U	< 0.014 U	0.011 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.014 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.045 J	< 0.016 U	< 0.012 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.02 J	< 0.016 U	< 0.012 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	0.026 J	< 0.013 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.019 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.11 J	0.017 J	0.013 J
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.2 J	0.046	0.016 J
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.051 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.052 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.076 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.015 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.04 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.035 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.054 U	0.038 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.56	0.13	0.021 J
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.011 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.066 U	0.25 J	< 0.076 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	1.3	0.23	0.19 J
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.059 U	0.22 J	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	1.2	0.16	0.19 J
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	0.04 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.012 J	< 0.017 U	< 0.013 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.067 UT	< 0.016 U	< 0.076 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	0.056 J	< 0.019 U	< 0.014 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.061 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.066 UT	< 0.016 U	< 0.075 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	0.013 J	< 0.018 U	< 0.014 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.062 UT	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.022 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.066 U	< 0.016 UT	< 0.075 U	< 0.024 UT	< 0.02 U	< 0.015 UT	< 0.015 U	< 0.0071 UT	< 0.018 UT	< 0.014 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.06 U	0.039 J	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.6	0.11	0.034 J
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.057 U	0.04 J	< 0.066 U	< 0.021 U	0.077 J	< 0.013 U	< 0.013 U	0.78	0.12	0.062 J
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.056 U	0.027 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.24 J	0.04	0.024 J
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.028 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.059 U	< 0.014 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.33	0.06 J	< 0.14 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.19	0.045 J	< 0.13 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.25 U	0.046 J	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	1.4	0.24	< 0.14 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.055 UT	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.053 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.054 UT	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.055 UT	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.064 U	< 0.027 U	< 0.014 U	< 0.051 U	< 0.097 U	< 0.016 U	< 0.023 U	< 0.17 U	< 0.031 U	< 0.21 UT
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 UT
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 UT
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.065 U	< 0.028 U	< 0.014 U	< 0.051 U	< 0.098 U	< 0.016 U	< 0.023 U	< 0.18 U	< 0.031 U	< 0.21 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.064 U	< 0.027 U	< 0.014 U	< 0.051 U	< 0.096 U	< 0.016 U	< 0.022 U	< 0.17 U	< 0.031 U	< 0.21 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.064 U	< 0.027 UT	< 0.014 U	< 0.05 UT	< 0.096 UT	< 0.016 UT	< 0.022 U	< 0.17 U	< 0.031 UT	< 0.21 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	0.31 J	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.038 U		< 0.031 U		0.43	0.013 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.04 U		< 0.033 U		0.11 J	0.014 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.04 U		< 0.033 U		0.43	0.012 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.04 U		< 0.033 U		0.055 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.038 U		< 0.031 U		0.11 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.042 U		< 0.034 U		0.2 J	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.043 U		< 0.035 U		0.57	0.013 J	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.041 U		< 0.033 U		0.36 J	0.018 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.043 U		< 0.035 U		0.017 J	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.041 U		< 0.034 U		0.021 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		0.06 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		0.028 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.041 U		< 0.033 U		0.041 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	< 0.04 U		< 0.033 U		0.059 J	0.02 J	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	< 0.041 U		< 0.033 U		0.1 J	0.023 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	< 0.038 U		< 0.031 U		0.034 J	0.012 J	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	< 0.038 U		< 0.031 U		0.037 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	< 0.039 U		< 0.032 U		0.021 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	< 0.039 U		< 0.032 U		0.034 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		0.016 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.037 U		< 0.03 U		0.043 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.038 U		< 0.031 U		0.035 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.037 U		< 0.03 U		0.72	0.029 J	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.037 U		< 0.03 U		0.014 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.046 U		< 0.037 U		2.6	0.29 J	< 0.02 U	< 0.0091 U	< 0.037 U	< 0.015 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.037 U		< 0.03 U		0.015 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.041 U		< 0.033 U		2.2	0.24 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.041 U		< 0.033 U		0.049 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.041 U		< 0.034 U		0.019 J	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.046 U		< 0.038 U		0.11 J	< 0.013 U	< 0.02 U	< 0.0092 U	< 0.038 U	< 0.015 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.046 U		< 0.037 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0090 U	< 0.037 U	< 0.015 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.043 U		< 0.035 U		0.016 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.045 U		< 0.037 U		< 0.015 UT	< 0.012 U	< 0.02 UT	< 0.0090 UT	< 0.037 U	< 0.014 UT
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.039 U		< 0.032 U		0.053 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.042 U		< 0.034 U		0.75	0.041 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.04 U		< 0.032 U		0.92	0.047 J	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.039 U		< 0.032 U		0.35 J	0.028 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.039 U		< 0.032 U		0.043 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.22 U	< 0.12 U			0.4	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.21 U	< 0.11 U			0.33	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.23 U	< 0.12 U			1.7	0.058 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.21 U	< 0.11 U			0.035 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 UT	< 0.12 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	0.22	< 0.013 U		< 0.1 U	0.036 J	< 0.022 U	0.12 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	0.16	< 0.014 U		< 0.11 U	0.043 J	< 0.023 U	0.12 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	0.07	< 0.014 U		< 0.11 U	0.013 J	< 0.023 U	0.012 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	0.022 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	0.18	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0076 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	0.075	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	0.013 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	0.24	< 0.015 U		< 0.12 U	0.013 J	< 0.025 U	0.13 J	< 0.03 U	< 0.095 U	< 0.046 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	0.14	< 0.014 U		< 0.11 U	0.016 J	< 0.024 U	0.037 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	0.042	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.019 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	0.027 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.031 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	0.053	< 0.014 U		< 0.11 U	0.013 J	< 0.024 U	0.038 J	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	0.038	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	< 0.015 UT	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	< 0.014 UT	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	0.067 T	< 0.014 U		< 0.11 U	0.021 J	< 0.023 U	0.022 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	0.14 T	< 0.014 U		< 0.11 U	0.031 J	< 0.024 U	0.039 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 U	0.011 J	< 0.022 U	0.019 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	0.015 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.0093 J	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.0098 J	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	0.026 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0067 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	0.018 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	0.014 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	0.055	< 0.013 U		< 0.1 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	0.047	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	7.8 ft	7.8 ft	1801469411	Not Excavated	0.55	< 0.013 U		< 0.1 U	0.058 J	< 0.022 U	0.07 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	0.86	< 0.016 U		< 0.12 U	0.14 J	< 0.027 U	0.2 J	< 0.033 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	0.77	< 0.014 U		< 0.11 U	0.18 J	< 0.024 U	0.29 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	0.029 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	0.063	< 0.016 U		< 0.12 U	< 0.012 U	< 0.027 U	< 0.0074 U	< 0.033 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	0.033 J	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0073 U	< 0.032 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	0.03 J	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	0.031 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.016 U	< 0.016 UT		< 0.12 UT	< 0.012 UT	< 0.026 UT	< 0.0073 UT	< 0.032 U	< 0.1 U	< 0.049 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	0.48	< 0.014 U		< 0.11 U	0.078 J	< 0.024 U	0.092 J	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	0.44	< 0.014 U		< 0.11 U	0.2 J	0.027 J	0.39	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	0.16	< 0.013 U		< 0.1 U	0.036 J	< 0.023 U	0.044 J	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	0.018 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.011 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	0.0087 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	0.28	< 0.11 U		< 0.14 U	0.022 J	< 0.11 U	0.064 J	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	0.13	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.047 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	0.69	< 0.11 U		< 0.14 U	0.11	< 0.11 U	0.21	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.2 J	< 0.013 U	0.43
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.092 J	< 0.014 U	0.14 J
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	0.011 J
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.19 J	< 0.014 U	0.33 J
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.032 J	< 0.014 U	0.046 J
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.018 J	< 0.013 U	0.28 J
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.12 J	< 0.014 U	0.17 J
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.21 J	< 0.015 U	0.58
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.18 J	< 0.014 U	0.3 J
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.0098 J	< 0.015 U	0.016 J
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.013 J	< 0.014 U	0.016 J
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.031 J	< 0.014 U	0.065 J
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.021 J	< 0.014 U	0.031 J
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	0.015 J
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.032 J	< 0.014 U	0.052 J
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0074 J	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.014 J	< 0.013 U	0.02 J
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.096 J	< 0.014 U	0.073 J
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.12 J	< 0.014 U	0.17 J
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.058 J	< 0.013 U	0.051 J
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.014 J	< 0.013 U	0.039 J
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	0.041 J
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.049 J	< 0.013 U	0.051 J
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.023 J
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	0.016 J
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.0096 J	< 0.013 U	0.055 J
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0087 J	< 0.013 U	0.044 J
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.18 J	< 0.013 U	0.88
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.016 J
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.035 U	< 0.087 U	2.1	< 0.016 U	2.3
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.016 J
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	1.7	< 0.014 U	1.8
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.032 U	< 0.079 U	0.025 J	< 0.014 U	0.057 J
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.018 J	< 0.014 U	0.023 J
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.035 U	< 0.088 U	0.089 J	< 0.016 U	0.097 J
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.024 U	< 0.042 U	< 0.069 U		< 0.031 U	< 0.035 U	< 0.087 U	0.012 J	< 0.016 U	0.019 J
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.081 U	0.01 J	< 0.015 U	0.017 J
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.02 J	< 0.014 U	0.02 J
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.023 U	< 0.042 UT	< 0.069 U		< 0.031 U	< 0.035 UT	< 0.087 U	< 0.0074 UT	< 0.016 UT	< 0.011 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.057 J	< 0.013 U	0.053 J
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	0.38	< 0.014 U	0.94
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.54	0.031 J	1.2
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.26 J	< 0.013 U	0.41
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.042 J	< 0.013 U	0.052 J
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	0.1 J		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.17	< 0.11 U	0.55
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.12	< 0.11 U	0.37
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.7	< 0.11 U	2.3
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.026 J	< 0.11 U	0.044 J
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated		0.046 J	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.049 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated		< 0.013 U	< 0.029 U	< 0.043 U	< 0.055 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated		< 0.013 U	< 0.029 U	< 0.044 U	< 0.055 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated		< 0.013 U	< 0.029 U	< 0.043 U	< 0.054 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated		< 0.013 U	< 0.029 U	< 0.043 U	< 0.054 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U

DRAFT

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]	Diesel Range Organics mg/kg	Diesel Fuel mg/kg	Total PAHS mg/kg	Acenaphthene mg/kg	Acenaphthylene mg/kg	Acetophenone mg/kg	Anthracene mg/kg	Atrazine mg/kg	1,1-Biphenyl mg/kg	Benzaldehyde mg/kg	Benz(a)anthracene mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated			ND	< 0.022 UT	< 0.017 UT	< 0.14 U	< 0.02 UT	< 0.17 UT	< 0.14 UT	< 0.048 UT	< 0.035 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated			1.963	< 0.02 U	< 0.015 U	< 0.12 U	0.036 J	< 0.15 U	< 0.13 U	< 0.043 U	0.23
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated			ND	< 0.0068	< 0.0081	< 0.029	< 0.0069	< 0.034	< 0.031	< 0.053	< 0.0088
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated			ND	< 0.0067	< 0.0079	< 0.028	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0087
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated			0.37	< 0.35 U	< 0.35 U		< 0.35 U				< 0.35 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated			ND	< 0.34	< 0.34		< 0.34				< 0.34
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.013 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated			0.049	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated			0.27	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.044 U	0.045 J
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U		< 0.031 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated			0.051	< 0.028 U	< 0.021 U	< 0.17 U	< 0.025 U	< 0.21 U	< 0.18 U	< 0.059 UT	< 0.043 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated			64.69	0.37	3.2	< 0.56 U	2.6	< 0.69 U	< 0.58 U	< 0.2 U	5.9
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated			37.3	0.11 J	1.6	< 0.57 U	1.3	< 0.7 U	< 0.58 U	< 0.2 U	3
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated			0.239	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.038 J
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated			0.08	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.036 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated			0.299	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.039 J
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated			1.798	< 0.023 U	0.02 J	< 0.14 U	0.025 J	< 0.17 U	< 0.14 U	< 0.049 U	0.19
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated			20.757	0.057 J	1.1	< 0.14 U	0.74	< 0.17 U	< 0.15 U	< 0.049 U	1.9
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated			43.62	0.16	2	< 0.15 U	1.5	< 0.19 U	< 0.16 U	< 0.053 UT	4.1
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated			ND	< 0.019 U	< 0.014 U	< 0.12 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated			0.79	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	0.062 J
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated			6.573	< 0.022 U	0.25	< 0.14 U	0.16	< 0.17 U	< 0.14 U	< 0.048 U	0.67
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated			7.683	< 0.021 U	0.24	< 0.13 U	0.24	< 0.16 U	< 0.14 U	< 0.046 U	0.73
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated			0.04	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated			ND	< 0.02 U	0.021 J	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated			ND	< 0.02 U	0.022 J	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated			7.491	0.023 J	0.18	< 0.13 U	0.23	< 0.15 U	< 0.13 U	< 0.044 U	0.66
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated			5.987	0.072	0.059 J	< 0.12 U	0.19	< 0.15 U	< 0.12 U	< 0.041 U	0.51
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated			4.673	< 0.023 U	0.3	< 0.14 U	0.14	< 0.17 U	< 0.15 U	< 0.05 U	0.37
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated			9.177	0.041 J	0.71	< 0.14 U	0.48	< 0.17 U	< 0.14 U	< 0.048 U	0.63
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated			1.448	0.045 J	< 0.018 U	< 0.15 U	0.074 J	< 0.18 U	< 0.15 U	< 0.051 U	0.13
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated			0.267	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	0.052 J
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated			0.621	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.09
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated			0.23	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.037 J
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated			10.363	0.033 J	0.97	< 0.14 U	0.56	< 0.17 U	< 0.14 U	< 0.047 U	0.79

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.034 UT	< 0.019 UT	< 0.023 UT	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 UT	< 0.41 UT	< 0.16 UT	< 0.27 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	0.14	0.17	0.086	0.043 J	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.0071	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0095	< 0.0076	< 0.057	< 0.031	< 0.048
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.0069	< 0.011	< 0.014	< 0.0069	< 0.023	< 0.0093	< 0.0075	< 0.056	< 0.03	< 0.047
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	< 0.015 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U	< 0.24 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U	< 0.26 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	0.031 J	0.05 J	< 0.021 U	0.023 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.041 U	< 0.024 U	< 0.029 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.035 U	< 0.51 U	< 0.2 U	< 0.33 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	4.8	7.6	2.3	4.5	< 0.58 U	< 0.057 U	< 0.12 U	< 1.7 U	< 0.67 U	< 1.1 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	3.2	4.1	1.5	3.5	< 0.58 U	< 0.058 U	< 0.12 U	< 1.7 U	< 0.68 U	< 1.1 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.034 U	0.036 J	< 0.023 U	0.02 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.034 U	0.025 J	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.034 U	0.05 J	< 0.023 U	0.022 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	0.13	0.19	0.074 J	0.082	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	1.7	2.9	0.66	1.6	< 0.15 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	3.4	5.5	1.9	3.1	< 0.16 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U	< 0.29 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.028 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.024 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	0.11	0.13	0.053 J	0.086	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	0.47	0.76	0.28	0.49	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	0.79	0.98	0.35	0.62	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 UT	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	0.58	0.72	0.28	0.54	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	0.43	0.55	0.21	0.34	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	0.62	0.76	0.26	0.47	< 0.15 U	< 0.014 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.27 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	0.99	1.5	0.6	1.1	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	0.1	0.11	0.067 J	0.055 J	< 0.15 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.032 U	0.021 J	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	0.04 J	0.041 J	0.025 J	0.054 J	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.032 U	0.029 J	< 0.022 U	0.025 J	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	0.82	1.2	0.41	1.1	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.05 U	< 0.15 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.25 UT	< 0.018 UT	< 0.1 U	< 0.14 UT	< 0.018 UT	< 0.14 UT	< 0.13 UT	< 0.043 UT	< 0.05 U	< 0.14 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.22 U	0.076	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	0.23	< 0.044 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	< 0.23 U	< 0.016 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.27	< 0.0065	< 0.028	< 0.032	< 0.0074	< 0.029	< 0.039	< 0.0084	< 0.0078	< 0.035
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0072	< 0.028	< 0.039	< 0.0083	< 0.0077	< 0.034
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated		< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	< 0.23 U	< 0.016 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.014 U	< 0.016 U	< 0.015 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U	< 0.016 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U	< 0.016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.046 U	< 0.016 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U	< 0.017 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.31 U	< 0.022 U	< 0.13 U	< 0.17 U	< 0.022 U	< 0.18 U	< 0.16 U	< 0.053 U	< 0.061 U	< 0.18 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	< 1 U	0.51	< 0.41 U	< 0.55 U	< 0.072 U	< 0.58 U	< 0.53 U	6.7	1.3	< 0.58 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	< 1 U	0.38	< 0.42 U	< 0.56 U	< 0.073 U	< 0.59 U	< 0.53 U	2.7	0.81	< 0.59 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U	< 0.15 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.045 J	< 0.05 U	< 0.14 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.21	< 0.05 U	< 0.15 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	< 0.26 U	0.12	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	2.1	0.46	< 0.15 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	< 0.28 U	0.29	< 0.11 U	< 0.15 U	< 0.019 U	< 0.16 U	< 0.14 U	4.6	0.89	0.16 J
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.21 U	< 0.015 U	< 0.086 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.036 U	< 0.042 U	< 0.12 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.048 U	< 0.14 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.08	< 0.05 U	< 0.14 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.25 U	0.036 J	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.82	0.14	< 0.14 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.24 U	0.038 J	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.65	0.16	< 0.14 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 UT	< 0.14 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	< 0.23 U	0.058 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.59	0.14	< 0.13 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	< 0.22 U	0.076	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.51	0.097	< 0.12 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	< 0.26 U	0.019 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.45	0.13	< 0.15 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	< 0.25 U	0.075 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.74	0.25	< 0.14 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	< 0.27 U	0.028 J	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.11	< 0.053 U	< 0.15 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.1	< 0.047 U	< 0.14 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.14	< 0.049 U	< 0.14 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.05 J	< 0.048 U	< 0.14 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.25 U	0.082	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	0.97	0.26	< 0.14 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					
Restricted - Residential																					
Protection of Groundwater																					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	0.19 J	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.36 UT	< 0.03 UT	< 0.14 UT	< 0.13 U	< 0.15 UT	0.2 JT	< 0.23 UT	< 0.67 UT	< 0.15 UT	< 2.4 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 UT	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.037	< 0.0071	< 0.039	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036	< 0.42
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.037	< 0.007	< 0.038	< 0.054	< 0.038	< 0.043	< 0.037	< 0.14	< 0.036	< 0.41
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	-	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 1.8 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 1.8	< 0.34	< 1.8
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.013 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U	< 0.95 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 2.1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U	< 2 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U	< 2 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U	< 2.1 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 UJ
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.45 U	< 0.037 U	< 0.17 U	< 0.16 U	< 0.19 U	< 0.21 U	< 0.28 U	< 0.83 U	< 0.19 U	< 3 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	< 1.5 U	< 0.12 U	< 0.55 U	< 0.53 U	< 0.62 U	< 0.69 U	< 0.92 U	< 2.7 U	< 0.62 U	< 9.8 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	< 1.5 U	< 0.12 U	< 0.56 U	< 0.53 U	< 0.63 U	< 0.7 U	< 0.92 U	< 2.7 U	< 0.62 U	< 9.9 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.5 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.17 U	< 2.6 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.31 U	< 0.025 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.14 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.36 UT	< 0.03 U	< 0.13 U	< 0.13 UT	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 UT	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 UT	< 0.13 U	< 2.1 UT
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	< 0.33 U	< 0.027 U	0.12 J	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U

DRAFT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.23 UT	< 0.12 U			< 0.02 UT	< 0.015 UT	< 0.028 UT	< 0.023 U	< 0.04 UT	< 0.14 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.21 U		< 0.11 U		0.48	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.028			< 0.04	< 0.0075	< 0.0093	< 0.0075	< 0.0079	< 0.038	< 0.025
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.028			< 0.04	< 0.0074	< 0.0091	< 0.0074	< 0.0078	< 0.037	< 0.025
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.35 U				< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.34				< 0.34	< 0.34	< 0.34	< 0.34	< 0.34	< 0.34
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	< 0.017 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.12 U			0.027 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.02 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.23 U			< 0.12 U	< 0.02 UJ	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.21 U			< 0.11 U	0.05 J	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.29 U	< 0.15 U			0.027 J	< 0.019 U	< 0.034 U	< 0.028 U	< 0.049 U	< 0.17 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	< 0.94 U	< 0.49 U			9.5	0.61	< 0.11 U	< 0.092 U	< 0.16 U	< 0.56 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	< 0.95 U	< 0.5 U			5	0.28 J	< 0.11 U	< 0.093 U	< 0.16 U	< 0.56 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.23 U	< 0.12 U			0.054 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.24 U	< 0.12 U			0.025 J	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.23 U	< 0.12 U			0.056 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.24 U	< 0.12 U			0.33	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	< 0.24 U	< 0.12 U			2.8	0.1	< 0.028 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	< 0.25 U	< 0.13 U			6.1	0.26	< 0.03 U	< 0.025 U	< 0.043 U	< 0.15 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.2 U	< 0.1 U			< 0.017 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.23 U	< 0.12 U			0.078 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.23 U	< 0.12 U			0.85	0.028 J	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.22 U	< 0.12 U			1	0.053 J	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.21 U	< 0.11 U			0.02 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.22 U	< 0.12 U			< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	< 0.21 U	< 0.11 U			1	0.058 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	< 0.2 U	< 0.1 U			0.79	0.08	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	< 0.24 U	< 0.12 U			0.34	0.021 J	< 0.029 U	< 0.023 U	< 0.041 U	< 0.14 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	< 0.23 U	< 0.12 U			0.56	0.066 J	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	< 0.25 U	< 0.13 U			0.24	0.032 J	< 0.029 U	< 0.024 U	< 0.042 U	< 0.15 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.22 U	< 0.11 U			0.022 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U	< 0.13 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.23 U	< 0.12 U			0.07 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U	< 0.14 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.22 U	< 0.12 U			0.041 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.23 U	< 0.12 U			1.2	0.09	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.039 UT	< 0.11 UT		< 0.15 U	< 0.019 UT	< 0.11 UT	< 0.015 UT	< 0.18 UT	< 0.098 UT	< 0.14 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	0.046 J	< 0.099 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.0073	< 0.025		< 0.027	< 0.0063	< 0.035	< 0.0061	< 0.16	< 0.15	< 0.14
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.0071	< 0.024		< 0.026	< 0.0062	< 0.034	< 0.006	< 0.16	< 0.14	< 0.14
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.35 U	< 0.35 U		< 0.35 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 1.8 U	< 1.8 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.34	< 0.34		< 0.34	< 0.34	< 0.34	< 0.34	< 1.8	< 1.8	< 1.8
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	< 0.014 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U	< 0.018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.048 U	< 0.14 U		< 0.18 U	< 0.023 U	< 0.14 U	< 0.019 U	< 0.22 U	< 0.12 U	< 0.18 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	4.1	< 0.45 U		< 0.59 U	0.51	< 0.46 U	0.61	< 0.72 U	< 0.4 U	< 0.59 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	3.1	< 0.46 U		< 0.6 U	0.43	< 0.47 U	1.6	< 0.72 U	< 0.4 U	< 0.59 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	0.08	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.017 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	1.5	< 0.11 U		< 0.15 U	0.17	< 0.12 U	0.26	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	3	< 0.12 U		< 0.16 U	0.34	< 0.12 U	0.41	< 0.19 U	< 0.11 U	< 0.16 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.033 U	< 0.094 U		< 0.12 U	< 0.016 U	< 0.097 U	< 0.013 U	< 0.15 U	< 0.084 U	< 0.12 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.033 U	< 0.095 U		< 0.12 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.084 U	< 0.12 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.034 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	0.08	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	0.37	< 0.11 U		< 0.14 U	0.038 J	< 0.11 U	0.045 J	< 0.17 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	0.59	< 0.11 U		< 0.14 U	0.052 J	< 0.11 U	0.11	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.036 UT	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U	< 0.14 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	0.54	< 0.1 U		< 0.13 U	0.04 J	< 0.1 U	0.13	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	0.33	< 0.096 U		< 0.13 U	0.027 J	< 0.098 U	0.068	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	0.41	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.029 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	0.91	< 0.11 U		< 0.14 U	0.092	< 0.11 U	0.15	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	0.049 J	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	0.016 J	< 0.19 U	< 0.1 U	< 0.15 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	0.031 J	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	0.91	< 0.11 U		< 0.14 U	0.18	< 0.11 U	0.25	< 0.17 U	< 0.097 U	< 0.14 U

DRAFT

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.14 UT	< 0.14 UT	< 0.27 U		< 0.026 UT	< 0.13 UT	< 0.62 U	< 0.021 UT	< 0.12 U	< 0.018 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.092	< 0.1 U	0.41
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.029	< 0.039	< 0.13		< 0.0083	< 0.033	< 0.032	< 0.011	< 0.0083	< 0.0071
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.029	< 0.038	< 0.13		< 0.0081	< 0.032	< 0.031	< 0.011	< 0.0082	< 0.007
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 0.35 U	< 0.35 U	< 1.8 U	< 0.35 U	< 0.35 U	0.37
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.34	< 0.34	< 1.8	< 0.34	< 0.34	< 0.34	< 1.8	< 0.34	< 0.34	< 0.34
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.022 J
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.021 J	< 0.11 U	0.05 J
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.14	< 0.12 U	0.33
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	< 0.58 U	< 0.58 U	< 1.1 U		< 0.11 U	< 0.53 U	< 2.5 U	4.7	< 0.48 U	9.6
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	< 0.58 U	< 0.59 U	< 1.1 U		< 0.11 U	< 0.53 U	< 2.6 U	2.5	< 0.48 U	4.6
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	0.029 J	< 0.12 U	0.062 J
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.03 J
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	0.029 J	< 0.12 U	0.058 J
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.14 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.14	< 0.12 U	0.33
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.88	< 0.12 U	3.1
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	2.3	< 0.13 U	6.4
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.022 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.026 J	< 0.12 U	0.085
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.29	< 0.12 U	1.2
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.44	< 0.11 U	0.97
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 UT		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.02 J
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.8	< 0.11 U	1.2
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	0.87	< 0.1 U	0.94
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.093	< 0.12 U	0.58
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.32	< 0.12 U	0.84
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	0.22	< 0.12 U	0.2
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	0.072 J
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	0.13
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.048 J
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.37	< 0.11 U	1.4

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated		< 0.15 U	< 0.16 UT	< 0.13 UT	< 0.13 UT
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated				< 0.35 U	< 0.35 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated				< 0.34	< 0.34
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated		< 0.19 U	< 0.2 U	< 0.17 U	< 0.16 U
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated		< 0.62 U	< 0.66 U	< 0.55 U	< 0.53 U
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated		< 0.63 U	< 0.66 U	< 0.55 U	< 0.53 U
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated		< 0.13 U	< 0.14 U	< 0.11 U	< 0.11 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAHS**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated			7.396	0.026 J	0.67	< 0.13 U	0.39	< 0.16 U	< 0.13 U	< 0.046 U	0.56
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated			16.773	0.043 J	1.2	< 0.14 U	0.67	< 0.17 U	< 0.14 U	< 0.048 U	1.4
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated			9.738	0.051 J	1	< 0.13 U	0.59	< 0.16 U	< 0.13 U	< 0.045 U	0.69
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated			0.14	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.014 J
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated			0.1036	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	0.022 J
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated			0.1045	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 U	0.02 J
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated			0.365	< 0.011 U	< 0.011 U	< 0.018 U	0.014 J	< 0.022 UT	< 0.013 U	< 0.062 U	0.041
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated			8.112	0.018 J	0.073 J	< 0.019 U	0.25 J	< 0.023 UT	< 0.014 U	< 0.064 U	0.76
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated			0.774	< 0.015 U	0.017 J	< 0.026 U	< 0.016 U	< 0.031 U	< 0.019 U	< 0.088 U	0.051 J
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated			0.671	< 0.011 U	< 0.011 U	< 0.019 U	0.023 J	< 0.022 UT	< 0.013 U	< 0.063 U	0.065
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated			2.577	< 0.01 U	0.021 J	< 0.017 U	0.041 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.27
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated			0.394	< 0.01 U	< 0.01 U	< 0.018 U	0.016 J	< 0.021 UT	< 0.013 U	< 0.06 U	0.04
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated			0.705	< 0.01 U	< 0.01 U	< 0.017 U	0.032 J	< 0.021 UT	< 0.012 U	< 0.058 U	0.064
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated			0.06	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 U	0.02 J
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated			61.63	0.19 J	0.88	< 0.019 U	3.2	< 0.023 UT	0.075 J	< 0.064 U	4.8
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated			35.94	< 0.14 U	0.99	< 0.85 U	0.83	< 1 U	< 0.88 U	< 0.3 U	3
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated			0.038	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated			4.666	< 0.01 U	0.084 J	< 0.018 U	0.1 J	< 0.021 UT	0.021 J	< 0.06 U	0.34
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated			28.84	0.22 J	0.36 J	< 0.019 U	0.95	< 0.023 UT	0.098 J	< 0.064 U	2.4
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated			8.434	0.16 J	0.081 J	< 0.019 U	0.33 J	< 0.023 UT	0.033 J	< 0.064 U	0.59
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated			0.052	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated			0.27	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	0.024 J
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated			0.106	0.011 J	< 0.011 U	< 0.018 U	0.017 J	< 0.022 UT	0.017 J	< 0.061 U	0.016 J
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated			0.134	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.018 J
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated			0.0076	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated			0.535	< 0.011 U	0.012 J	< 0.018 U	0.017 J	< 0.022 UT	< 0.013 U	< 0.061 U	0.053
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated			0.0175	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 UT	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated			11.75	< 0.08 U	0.32	< 0.5 U	0.38	< 0.61 U	< 0.51 U	< 0.17 U	1.1
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated			0.952	< 0.011 U	0.012 J	< 0.018 U	0.021 J	< 0.022 U	< 0.013 U	< 0.062 U	0.082
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated			1.339	< 0.01 U	0.019 J	< 0.018 U	0.03 J	< 0.021 U	< 0.012 U	< 0.059 U	0.12
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 UT	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated			0.088	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.017 J
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated			0.739	< 0.01 U	0.012 J	< 0.018 U	0.02 J	< 0.021 UT	< 0.012 U	< 0.059 U	0.067
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated			0.388	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.04
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated			0.012	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated			0.0085	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated			3.034	< 0.011 U	0.063 J	< 0.018 U	0.043 J	< 0.022 UT	< 0.013 U	< 0.062 U	0.23
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated			0.156	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	0.023 J
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated			1.02	< 0.023 U	0.059 J	< 0.14 U	0.039 J	< 0.18 U	< 0.15 U	< 0.05 U	0.087
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated			1.966	0.039 J	0.062 J	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated			0.319	< 0.015 U	< 0.015 U	< 0.026 U	0.019 J	< 0.031 U	< 0.018 U	< 0.087 U	0.029 J
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated			0.555	< 0.01 U	0.011 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.038
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated			1.629	< 0.011 U	0.073 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated			4.633	< 0.011 U	0.08 J	< 0.019 U	< 0.012 U	< 0.023 U	0.016 J	< 0.065 U	< 0.014 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U

												Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100						
Restricted - Residential												1	1	3.9	100						
Protection of Groundwater												22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	0.62	0.91	0.29	0.81	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	1.3	1.9	0.72	1.5	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	0.74	1.2	0.38	1.1	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.01 UT	< 0.01 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	0.015 JT	0.023 J	0.0090 J	0.017 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	0.012 J	0.018 J	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.01 U	0.016 J	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	0.03 J	0.04	0.015 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	0.62	0.76	0.32	0.29 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	0.042 J	0.083	0.03 J	0.049 J	< 0.041 U	< 0.019 U	< 0.0096 U	< 0.028 U	< 0.021 U	< 0.025 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	0.057	0.068 T	0.03 J	0.034 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	0.26	0.3	0.13	0.15 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 UT	< 0.016 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	0.033 J	0.037	0.015 J	0.02 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	0.049	0.06	0.024 J	0.031 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	3.7	4.5	1.7	2.3	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 UT	< 0.018 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	2.9	3.7	1.8	2.8	< 0.88 U	< 0.087 U	< 0.18 U	< 2.5 U	< 1 U	< 1.6 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.031 U	0.021 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	0.37	0.49	0.2	0.32 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	2	2.7	1.2	1.3	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	0.53	0.75	0.23	0.41	< 0.03 U	< 0.013 U	< 0.0070 U	0.034 J	< 0.015 U	< 0.018 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.01 U	0.01 J	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	0.018 JT	0.033 J	0.012 J	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.0098 U	< 0.0096 U	0.0078 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	0.011 J	0.016 J	0.0080 J	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	0.04	0.052	0.028 J	0.028 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	0.037 J	< 0.016 U	< 0.019 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	0.76	0.84	0.46	0.61	< 0.51 U	< 0.05 U	< 0.1 U	< 1.5 U	< 0.59 U	< 0.95 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	0.075	0.1	0.031 J	0.056 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	0.11	0.15	0.059	0.055 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.0097 U	0.012 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	0.052	0.076	0.025 J	0.039 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	0.029 J	0.044	0.019 J	0.026 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	0.25	0.39	0.15	0.25 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	0.012 J	0.016 J	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	0.085	0.1	0.042 J	0.13	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.28 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	0.1	0.21	< 0.0074 U	0.051 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	0.021 J	0.025 J	0.022 J	0.025 J	< 0.041 U	< 0.018 U	< 0.0096 U	< 0.028 U	< 0.021 U	< 0.025 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	0.045	0.066	0.031 J	0.039 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 UT	0.023 J	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.0098 U	< 0.0096 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	0.11	0.11	0.044	0.054 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	0.36	0.44	< 0.0077 U	0.13 J	< 0.03 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.24 U	0.06 J	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.7	0.18	< 0.14 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.25 U	0.1	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	1.7	0.35	< 0.14 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.24 U	0.099	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.92	0.22	< 0.13 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.013 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0096 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.012 J	< 0.017 U	< 0.013 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.03 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.061 U	0.016 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.55	0.064	0.02 J
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.083 U	< 0.02 U	< 0.094 U	< 0.03 U	< 0.025 U	< 0.019 U	< 0.019 U	0.069 J	< 0.023 U	< 0.018 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 UT	0.056 J	< 0.016 U	< 0.013 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.22 J	0.038	< 0.012 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.032 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.054 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.059 UT	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.013 J	< 0.017 U	< 0.013 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.06 UT	1.9	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	4.2	0.62	1
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 1.6 U	0.29 J	< 0.63 U	< 0.84 U	< 0.11 U	< 0.88 U	< 0.8 U	3.2	0.62	< 0.88 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.062 UT	< 0.015 U	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.056 UT	0.05 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.37	0.055	0.057 J
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.06 UT	0.28 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	2.2	0.36	0.35 J
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.06 UT	0.13 J	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.6	0.084	0.14 J
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.061 UT	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0067 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.052 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.057 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.06 UT	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.03 J	< 0.017 U	< 0.013 U
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0082 J	< 0.016 U	0.019 J
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.011 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.05 J	< 0.016 U	0.015 J
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.063 U	< 0.016 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	0.0075 J	< 0.018 U	< 0.014 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.9 U	0.15 J	< 0.36 U	< 0.49 U	< 0.064 U	< 0.51 U	< 0.46 U	0.94	< 0.18 U	< 0.51 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.078 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.056 U	0.014 J	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.11 J	0.019 J	0.013 J
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.064 U	< 0.016 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	< 0.0069 U	< 0.018 U	< 0.014 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.011 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.062 J	< 0.016 U	< 0.012 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.034 J	< 0.016 U	< 0.012 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.059 U	0.016 J	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.24 J	0.051	0.028 J
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.015 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.14 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	0.1	< 0.052 U	< 0.15 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.55	< 0.016 U	< 0.013 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.082 U	< 0.02 U	< 0.094 U	< 0.03 U	< 0.024 U	< 0.019 U	< 0.019 U	0.023 J	< 0.023 U	< 0.018 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.065 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	0.042 J
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.061 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	1.7	< 0.017 U	0.047 J
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.34 U	< 0.028 U	0.18 J	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	0.19 J	< 0.028 U	< 0.19 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.08 U	< 0.034 U	< 0.017 U	< 0.064 U	< 0.12 U	< 0.02 U	< 0.028 U	< 0.22 U	< 0.038 U	< 0.26 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 UT	< 0.19 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 2.2 U	< 0.18 U	< 0.84 U	< 0.8 U	< 0.95 U	< 1 U	< 1.4 U	< 4.1 U	< 0.93 U	< 15 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.4 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 UT	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	0.31
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	0.039 J	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 1.3 U	< 0.11 U	< 0.49 U	< 0.47 U	< 0.55 U	< 0.61 U	< 0.81 U	< 2.4 U	< 0.54 U	< 8.6 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	0.19 J	< 0.027 U	0.34
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.16 U	< 2.5 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.08 U	< 0.034 U	< 0.017 U	< 0.063 U	< 0.12 U	< 0.02 U	< 0.028 U	< 0.22 U	< 0.038 U	< 0.26 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.22 U	< 0.12 U			0.79	0.06 J	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.23 U	< 0.12 U			2.3	0.12	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.22 U	< 0.11 U			0.99	0.087	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.038 U		< 0.03 U		0.013 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.04 U		< 0.033 U		0.023 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.041 U		< 0.033 U		0.025 J	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.04 U		< 0.033 U		0.095 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.042 U		< 0.034 U		1.9	0.058 J	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.057 U		< 0.047 U		0.14 J	< 0.016 U	< 0.025 U	< 0.011 U	< 0.047 U	< 0.018 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.041 UT		< 0.033 U		0.14 J	< 0.011 U	< 0.018 UT	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.038 U		< 0.031 U		0.47	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.039 U		< 0.032 U		0.079 J	< 0.011 U	< 0.017 UT	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.038 U		< 0.031 U		0.14 J	< 0.01 U	< 0.017 UT	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 UT	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.042 U		< 0.034 U		11	1.6	< 0.018 UT	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 1.4 U	< 0.75 U			6.2	< 0.094 U	< 0.17 U	< 0.14 U	< 0.24 U	< 0.85 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.23 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.039 U		< 0.032 U		0.7	0.021 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.042 U		< 0.034 U		4.7	0.31 J	< 0.018 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.042 U		< 0.034 U		1.2	0.15 J	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.042 U		< 0.034 U		0.014 J	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.042 U		< 0.034 U		0.064 J	< 0.011 U	< 0.018 U	< 0.0083 UT	< 0.034 U	< 0.013 UT
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	0.016 J	0.018 J	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.038 U		< 0.031 U		0.022 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.04 U		< 0.032 U		0.078 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.83 U	< 0.43 U			2.1	< 0.055 U	< 0.099 U	< 0.081 U	< 0.14 U	< 0.49 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.04 U		< 0.032 U		0.15 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.038 U		< 0.031 U		0.22 J	0.011 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.039 U		< 0.032 U		0.018 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.039 U		< 0.031 U		0.12 J	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.039 U		< 0.031 U		0.051 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.041 U		< 0.033 U		0.42	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.04 U		< 0.033 U		0.03 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	--	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	< 0.24 U	< 0.13 U			0.099	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U	< 0.14 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.041 U		< 0.033 U		0.14 J	0.076 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.057 U		< 0.046 U		0.02 J	0.015 J	< 0.025 U	< 0.011 U	< 0.046 U	< 0.018 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.039 U		< 0.032 U		0.063 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	9 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.04 U		< 0.033 U		0.15 J	0.14 J	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.042 U		< 0.034 U		0.41	0.16 J	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	0.64	< 0.11 U		< 0.14 U	0.13	< 0.11 U	0.17	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	1.2	< 0.11 U		< 0.14 U	0.13	< 0.11 U	0.19	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	0.9	< 0.1 U		< 0.14 U	0.19	< 0.11 U	0.24	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	0.44	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	0.052 J	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	0.05 J	0.039 J		< 0.15 U	< 0.015 U	< 0.033 U	< 0.0092 U	< 0.041 U	< 0.13 U	< 0.061 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	0.035 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	0.19	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	0.037	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	2.8	< 0.014 U		< 0.11 U	0.2 J	< 0.024 U	0.52	< 0.029 U	< 0.092 U	< 0.044 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	2.3	< 0.69 U		< 0.9 U	0.17 J	< 0.7 U	0.49	< 1.1 U	< 0.61 U	< 0.89 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U	< 0.13 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.016 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.094 U	< 0.046 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	0.32	< 0.014 U		< 0.1 U	0.067 J	< 0.023 U	0.28 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	1.6	< 0.014 U		< 0.11 U	0.35 J	0.046 J	1	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	0.43	< 0.014 U		< 0.11 U	0.11 J	< 0.024 U	0.27 J	< 0.03 U	< 0.092 U	< 0.044 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 UT	< 0.024 U	< 0.0067 UT	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	0.029 J	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	0.064	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.017 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0071 U	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	0.51	< 0.4 U		< 0.52 U	0.15 J	< 0.41 U	0.25 J	< 0.63 U	< 0.35 U	< 0.52 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	0.067	< 0.014 U		< 0.11 U	0.013 J	< 0.023 U	0.042 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	0.069	< 0.013 U		< 0.1 U	0.016 J	< 0.022 U	0.036 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0071 U	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	0.065	< 0.013 U		< 0.1 U	0.013 J	< 0.022 U	0.036 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	0.03 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	0.032 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	0.37	< 0.014 U		< 0.11 U	0.039 J	< 0.024 U	0.13 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 0.036 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U	< 0.14 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	0.081	< 0.12 U		< 0.15 U	0.042 J	< 0.12 U	0.072 J	< 0.18 U	< 0.1 U	< 0.15 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	0.12	< 0.014 U		< 0.11 U	0.016 J	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	0.064	< 0.02 U		< 0.15 U	< 0.015 U	< 0.033 U	0.012 J	< 0.04 U	< 0.13 U	< 0.061 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	0.07	< 0.014 U		< 0.1 U	0.012 J	< 0.023 U	0.016 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	0.13	< 0.014 U		< 0.11 U	0.062 J	< 0.023 U	0.041 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	0.25	< 0.015 U		< 0.11 U	0.047 J	< 0.024 U	0.033 J	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.25	< 0.11 U	1
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.68	< 0.12 U	2.7
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.33	< 0.11 U	1.3
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.019 J
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	0.019 J
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.0085 J	< 0.014 U	0.023 J
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.029 J	< 0.014 U	0.071 J
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	0.63	< 0.014 U	1.4
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.03 U	< 0.053 U	< 0.087 U		< 0.039 U	< 0.044 U	< 0.11 U	0.12 J	< 0.02 U	0.14 J
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.043 J	< 0.014 U	0.12 JT
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.068 J	< 0.013 U	0.44
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	0.019 J	< 0.013 U	0.078 J
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.084 J	< 0.013 U	0.13 J
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	0.027 J
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	12	< 0.014 U	8.5
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.88 U	< 0.88 U	< 1.7 U		< 0.16 U	< 0.8 U	< 3.8 U	2.7	< 0.72 U	5.4
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	0.017 J
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U	< 0.018 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 UT		< 0.029 U	< 0.033 U	< 0.081 U	< 0.0070 U	< 0.015 U	< 0.0099 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	0.43	0.017 J	0.67
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.022 U	< 0.039 U	< 0.063 UT		< 0.028 U	< 0.032 U	< 0.08 U	3.6	0.046 J	4.3
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 UT		< 0.028 U	< 0.032 U	< 0.079 U	1.4	< 0.014 U	1.3
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 UT		< 0.029 U	< 0.032 U	< 0.081 U	0.014 J	< 0.014 U	0.014 J
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.019 U	< 0.034 U	0.062 JT		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.022 U	< 0.039 UT	< 0.063 UT		< 0.028 U	< 0.032 U	< 0.08 U	0.043 J	< 0.014 U	0.046 J
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.076 U	0.019 J	< 0.014 U	0.011 J
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 UT		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.019 J
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0076 J	< 0.013 U	< 0.0089 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.037 J	< 0.014 U	0.071 J
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.034 U	< 0.084 U	0.01 J	< 0.015 U	< 0.01 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.51 U	< 0.51 U	< 0.97 U		< 0.094 U	< 0.46 U	< 2.2 U	2	< 0.42 U	1.8
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.11 J	< 0.014 U	0.14 J
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.13 J	< 0.013 U	0.22 J
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.034 U	< 0.084 U	< 0.0072 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U	< 0.0091 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.015 J	< 0.013 U	0.015 J
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.077 J	< 0.013 U	0.1 J
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.029 J	< 0.013 U	0.054 J
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.012 J	< 0.014 U	< 0.0095 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	0.0085 J
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.16 J	< 0.014 U	0.35 J
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.021 U	< 0.037 U	0.11 J		< 0.027 U	< 0.031 U	< 0.076 U	0.037 J	< 0.014 U	0.023 J
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U	< 0.018 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.075 J	< 0.12 U	0.11
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.34 J	< 0.014 U	0.34 J
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.029 U	< 0.053 U	< 0.086 U		< 0.038 U	< 0.043 U	< 0.11 U	0.024 J	< 0.019 U	0.02 J
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.064 J	< 0.013 U	0.058 J
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	0.021 J	< 0.0093 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.52	< 0.014 U	0.33 J
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	0.6	< 0.014 U	0.55
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U

DRAFT

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	18013712272	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated		< 0.017 U	< 0.036 U	< 0.054 U	< 0.068 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated		< 0.012 UT	< 0.026 UT	< 0.039 U	< 0.049 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated		< 0.95 U	< 1 U	< 0.83 U	< 0.8 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.052 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated		< 0.55 U	< 0.58 U	< 0.48 U	< 0.46 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.052 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated		< 0.016 U	< 0.036 U	< 0.054 U	< 0.068 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated			0.015	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated			0.071	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.024 J
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated			0.1045	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated			0.077	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated			0.0432	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.013 J
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated			0.32	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 U	0.019 J
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated			0.145	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated			8.64	0.12	0.16	< 0.13 U	0.24	< 0.16 U	< 0.14 U	< 0.046 U	0.61 T
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated			0.022	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated			ND	< 0.068 U	< 0.052 U	< 0.42 U	< 0.061 U	< 0.52 U	< 0.43 U	< 0.15 U	< 0.11 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated			0.611	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	0.077
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated			ND	< 0.066 U	0.23	< 0.41 U	< 0.059 U	< 0.5 U	< 0.42 U	< 0.14 U	< 0.1 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated			4.901	< 0.051 U	0.12 J	< 0.088 U	< 0.055 U	< 0.11 U	0.077 J	< 0.3 U	< 0.063 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated			0.384	< 0.01 U	0.023 J	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.023 J
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated			5.698	0.16 J	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	0.063 J	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated			1.359	0.018 J	0.078 J	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated			1.2065	< 0.0098 U	0.028 J	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.057 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated			1.387	< 0.01 U	0.04 J	< 0.018 U	0.025 J	< 0.021 UT	0.013 J	< 0.06 UT	0.088
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated			3.483	< 0.011 U	0.071 J	< 0.019 U	0.057 J	< 0.022 UT	0.024 J	< 0.063 UT	0.19
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated			4.43	< 0.012 U	0.12 J	< 0.02 U	0.061 J	< 0.024 UT	< 0.014 U	< 0.067 U	0.47
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated			3.429	0.033 J	0.043 J	< 0.018 U	0.11 J	< 0.021 UT	0.037 J	< 0.06 UT	0.33
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated			6.274	0.11	0.037 J	< 0.13 U	0.3	< 0.16 U	< 0.13 U	< 0.044 U	0.47
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated			0.466	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	0.042 J
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated			0.283	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	0.037 J
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated			0.1916	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	0.023 J
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated			0.583	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.057
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated			0.292	< 0.01 U	0.016 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated			0.054	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated			0.218	< 0.011 U	0.025 J	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated			2.8	< 0.01 U	0.097 J	< 0.018 U	0.053 J	< 0.022 U	< 0.013 U	< 0.061 U	0.2
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated			0.914	< 0.01 U	0.021 J	< 0.017 U	0.021 J	< 0.021 U	< 0.012 U	< 0.059 U	0.068
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated			3	< 0.11 U	0.12 J	< 0.18 U	0.14 J	< 0.22 U	< 0.13 U	< 0.62 U	< 0.13 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated			0.631	< 0.01 U	0.019 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	0.048
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated			0.096	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.014 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated			0.105	< 0.011 U	0.031 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	0.077 J	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated			2.678	< 0.01 U	0.13 J	< 0.018 U	0.092 J	< 0.021 U	< 0.013 U	< 0.06 U	0.2
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated			0.353	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.038
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated			0.095	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	0.023 J
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated			0.301	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.029 J
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated			0.399	< 0.0099 U	0.036 J	< 0.017 U	0.028 J	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated			0.14	< 0.01 U	0.052 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated			0.183	< 0.01 U	0.03 J	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated			0.673	< 0.01 U	0.043 J	< 0.018 U	0.043 J	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated			3.22	< 0.079 U	0.11 J	< 0.49 U	< 0.071 U	< 0.6 U	< 0.5 U	< 0.17 U	0.14 J
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated			1.044	< 0.019 U	0.034 J	< 0.12 U	0.031 J	< 0.15 U	< 0.12 U	< 0.041 U	0.078
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated			2.54	< 0.04 U	0.11 J	< 0.25 U	0.065 J	< 0.3 U	< 0.25 U	< 0.085 U	0.13 J
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated			ND	< 0.02 U	0.043 J	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.042 U	< 0.031 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	0.015 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	0.044 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.0097 U	0.023 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	0.02 J	0.037	0.015 J	0.041 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.0096 U	0.014 J	< 0.0070 U	0.015 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.032 UT	< 0.018 UT	< 0.022 UT	< 0.016 UT	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 UT	< 0.16 U	< 0.26 UT
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.1 U	< 0.058 U	< 0.071 U	< 0.051 U	< 0.43 U	< 0.043 U	< 0.088 U	< 1.3 U	< 0.5 U	< 0.81 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	0.059 J	0.068 J	0.024 J	0.058 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.099 U	< 0.056 U	< 0.069 U	< 0.049 U	< 0.42 U	< 0.042 U	< 0.085 U	< 1.2 U	< 0.49 U	< 0.79 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	0.087 J	0.21	0.068 J	0.087 J	< 0.14 U	< 0.063 U	< 0.033 U	< 0.095 U	< 0.071 U	< 0.084 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	0.02 J	0.039	0.015 J	0.065 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	0.23	< 0.0089 U	< 0.0068 U	0.091 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	0.085 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	0.11	0.16	0.057	0.12 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	0.19	0.29	< 0.0074 U	0.14 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	0.4	0.72	0.25	0.23 J	< 0.032 U	< 0.014 U	< 0.0074 U	0.037 J	< 0.016 U	< 0.019 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	0.11	0.16	0.067	0.096 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	0.4	0.48	0.16	0.32	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	0.041 J	0.047 J	< 0.022 U	0.032 J	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	0.031 J	0.041 J	< 0.021 U	0.026 J	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	0.012 J	0.021 J	0.0096 J	0.011 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	0.046	0.06	0.028 J	0.031 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	0.07 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	0.13 J	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	0.21	0.32	0.12	0.2 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	0.041	0.089	0.037	0.059 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	0.21 J	< 0.097 U	< 0.074 U	0.65 J	< 0.29 U	< 0.13 U	< 0.068 U	< 0.2 U	< 0.15 U	< 0.18 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	0.052	0.073	0.028 J	0.053 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	0.048 J	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	0.077 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	0.21	0.28	0.12	0.23 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	0.016 J	0.029 J	0.011 J	0.03 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	0.015 J	0.025 J	< 0.0071 U	0.025 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	0.13	< 0.0090 U	< 0.0068 U	0.08 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	0.14 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	0.13 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.0096 U	< 0.0094 U	< 0.0071 U	0.32 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.12 U	0.38	< 0.083 U	0.72	< 0.5 U	< 0.05 U	< 0.1 U	< 1.5 U	< 0.59 U	< 0.95 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	0.082	0.075	0.069	0.12	< 0.12 U	< 0.012 U	< 0.025 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	0.12 J	0.24	< 0.041 U	0.46	< 0.25 U	< 0.025 U	< 0.051 U	< 0.73 U	< 0.29 U	< 0.47 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.018 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0065 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.057 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.028 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0069 U	< 0.018 U	< 0.014 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0062 J	0.024 J	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.025 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.24 U	< 0.017 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	1.8 T	< 0.048 UT	0.25 J
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U	< 0.14 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.77 U	< 0.055 U	< 0.31 U	< 0.42 U	< 0.054 U	< 0.44 U	< 0.39 U	< 0.13 U	< 0.15 U	< 0.44 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	0.079	< 0.049 U	< 0.14 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.74 U	< 0.054 U	< 0.3 U	< 0.4 U	< 0.052 U	< 0.42 U	< 0.38 U	< 0.13 U	< 0.15 U	< 0.42 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	0.38 J	< 0.069 U	< 0.32 U	< 0.1 U	< 0.083 U	< 0.064 U	< 0.064 U	0.93 J	< 0.078 U	0.12 J
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.029 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.055 UT	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	1.4	< 0.015 U	0.15 J
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.054 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.59	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.63	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.053 UT	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.12 J	0.026 J	0.034 J
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.059 UT	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.7	0.035 J	0.049 J
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.064 U	0.026 J	< 0.072 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	0.52	0.079	0.024 J
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.056 UT	0.02 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.47	0.023 J	0.13 J
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.23 U	0.11	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.45	0.08	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	0.05 J	< 0.048 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.022 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.047 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.085 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.057 U	0.027 J	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.22 J	0.043	0.047 J
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.064 J	0.023 J	0.016 J
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.59 U	< 0.14 U	< 0.67 U	< 0.21 U	< 0.17 U	< 0.13 U	< 0.13 U	< 0.064 U	< 0.16 U	< 0.13 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.052 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.056 U	0.041 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.25 J	0.038	0.031 J
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.052 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.016 J	< 0.016 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.035 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.071 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.9 U	< 0.064 U	< 0.36 U	< 0.48 U	< 0.063 U	< 0.51 U	< 0.46 U	0.46	< 0.18 U	< 0.51 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.087 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.077	< 0.043 U	< 0.12 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.45 U	< 0.032 U	< 0.18 U	< 0.24 U	< 0.032 U	< 0.25 U	< 0.23 U	0.35	< 0.088 U	< 0.25 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

												3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					
Restricted - Residential																					
Protection of Groundwater																					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.055 UT	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 UT	< 0.026 U	< 0.18 UT
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.092 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.35 UT	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 UT	< 0.64 U	< 0.15 U	< 2.3 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 1.1 U	< 0.091 U	< 0.42 U	< 0.4 U	< 0.47 U	< 0.52 U	< 0.69 U	< 2 U	< 0.46 U	< 7.3 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 1.1 U	< 0.088 U	< 0.4 U	< 0.38 U	< 0.45 U	< 0.5 U	< 0.67 U	< 2 U	< 0.45 U	< 7.1 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.27 U	< 0.12 U	< 0.058 U	< 0.21 U	< 0.41 U	< 0.068 U	< 0.095 U	< 0.74 U	< 0.13 U	< 0.88 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	0.18 J	< 0.027 U	0.41
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.062 U	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.14 U	< 2.3 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 UT	< 0.026 U	< 0.17 UT
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.57 U	< 0.24 U	< 0.12 U	< 0.45 U	< 0.86 U	< 0.14 U	< 0.2 U	< 1.5 U	< 0.27 U	< 1.8 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 UT	< 0.028 U	< 0.19 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 1.3 U	< 0.11 U	< 0.48 U	< 0.46 U	< 0.54 U	< 0.6 U	< 0.8 U	< 2.4 U	< 0.54 U	< 8.5 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.64 U	< 0.053 U	< 0.24 U	< 0.23 U	< 0.27 U	< 0.3 U	< 0.4 U	< 1.2 U	< 0.27 U	< 4.3 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.32 UT	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 UT	< 0.13 U	< 2.1 UT

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.04 U		< 0.033 U		0.013 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.037 U		< 0.03 U		0.028 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.039 U		< 0.031 U		0.014 J	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.22 U	< 0.12 U			2.2	0.43	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.71 U	< 0.37 U			< 0.062 U	< 0.047 U	< 0.085 U	< 0.069 U	< 0.12 U	< 0.42 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.23 U	< 0.12 U			0.092	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.68 U	< 0.36 U			< 0.06 U	< 0.045 U	< 0.082 U	< 0.067 U	< 0.12 U	< 0.4 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.19 U		< 0.16 U		0.41 J	0.36 J	< 0.086 U	< 0.038 U	< 0.16 U	< 0.062 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.039 U		< 0.032 U		0.028 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	0.69	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	0.026 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		0.039 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.039 U		< 0.032 U		0.13 J	0.011 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.041 U		< 0.033 U		0.29 J	0.11 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.044 U		< 0.036 U		0.58	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U	< 0.014 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.039 U		< 0.032 U		0.43	0.14 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.21 U			< 0.11 U	1	0.1	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.22 U			< 0.12 U	0.086	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.2 U			< 0.11 U	0.049 J	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.037 U		< 0.03 U		0.024 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.04 U		< 0.033 U		0.1 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.038 U		< 0.031 U		0.015 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.039 U		< 0.032 U		0.014 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.039 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 UT	< 0.012 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.039 U		< 0.032 U		0.35 J	0.014 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.038 U		< 0.031 U		0.14 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.41 U		< 0.33 U		0.26 J	< 0.11 U	< 0.18 U	< 0.08 U	< 0.33 U	< 0.13 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.039 U		< 0.032 U		0.087 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 UT	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.039 U		< 0.032 U		0.38	0.028 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.04 U		< 0.032 U		0.047 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.041 U		< 0.033 U		0.021 J	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.039 U		< 0.032 U		0.043 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.82 U	< 0.43 U			0.26 J	< 0.054 U	< 0.099 U	< 0.08 U	< 0.14 U	< 0.49 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.2 U	< 0.1 U			0.12	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.41 U	< 0.21 U			0.23	< 0.027 U	< 0.049 U	< 0.04 U	< 0.07 U	< 0.24 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.2 UT	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	0.054	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	0.056	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	0.027 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.018 J	< 0.022 U	0.069 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.037 UT	< 0.11 U		< 0.14 U	0.23	0.27 J	0.27	< 0.17 U	< 0.095 U	< 0.14 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.12 U	< 0.34 U		< 0.44 U	< 0.057 U	< 0.35 U	< 0.046 U	< 0.54 U	< 0.3 U	< 0.44 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	0.043 J	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.11 U	< 0.33 U		< 0.43 U	< 0.055 U	< 0.34 U	< 0.045 U	< 0.52 U	< 0.29 U	< 0.43 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.034 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	0.079 J	< 0.067 U		< 0.52 U	0.33 J	0.29 J	0.2 J	< 0.14 U	< 0.43 U	< 0.21 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	0.057	< 0.014 U		< 0.11 U	0.012 J	< 0.023 U	0.058 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	0.096	< 0.013 U		< 0.1 U	0.039 J	< 0.022 U	0.031 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	0.057	< 0.013 U		< 0.1 U	0.011 J	< 0.022 U	0.0080 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	0.082	< 0.013 U		< 0.099 U	0.015 J	< 0.021 U	0.0085 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	0.11	< 0.014 U		< 0.1 U	0.046 J	< 0.023 U	0.16 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	0.14	< 0.014 U		< 0.11 U	0.071 J	0.15 J	0.081 J	< 0.029 U	< 0.09 U	< 0.043 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	0.35	< 0.015 U		< 0.12 U	0.061 J	< 0.025 U	0.07 J	< 0.031 U	< 0.097 U	< 0.047 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	0.095	< 0.014 U		< 0.1 U	0.031 J	< 0.023 U	0.095 J	< 0.028 UT	< 0.086 U	< 0.042 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	0.28	< 0.1 U	< 0.1 U	< 0.13 U	0.048 J		0.064 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	0.027 J		0.03 J	< 0.17 U	< 0.094 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	0.036	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	0.064	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.015 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	0.084	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	0.024 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	0.088	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	0.28	< 0.014 U		< 0.11 U	0.043 J	< 0.023 U	0.21 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	0.096	< 0.013 U		< 0.1 U	0.021 J	< 0.022 U	0.077 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	0.85	< 0.14 U		< 1.1 U	< 0.11 U	< 0.24 U	< 0.065 U	< 0.29 U	< 0.89 U	< 0.43 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	0.077	< 0.014 U		< 0.11 U	0.011 J	< 0.023 U	0.04 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	0.048	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	0.028 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	0.2	< 0.014 U		< 0.1 U	0.023 J	< 0.023 U	0.12 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	0.019 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.022 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	0.042	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.018 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	0.09	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	0.053	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	0.31	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	0.38	< 0.39 U		< 0.52 U	0.085 J	< 0.4 U	< 0.054 U	< 0.63 U	< 0.35 U	< 0.51 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	0.098	< 0.095 U		< 0.12 U	0.017 J	< 0.098 U	0.054 J	< 0.15 U	< 0.084 U	< 0.12 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	0.24	< 0.2 U		< 0.26 U	0.048 J	< 0.2 U	0.035 J	< 0.31 U	< 0.17 U	< 0.26 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	0.016 J
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	0.012 J	< 0.013 U	0.014 J
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.021 J	< 0.013 U	0.031 J
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.02 J	< 0.013 U	0.013 J
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	2	< 0.11 U	0.97 T
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.022 J	< 0.12 U	< 0.018 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.43 U	< 0.44 U	< 0.83 U		< 0.08 U	< 0.39 U	< 1.9 U	< 0.064 U	< 0.36 U	< 0.056 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.035 J	< 0.12 U	0.076 J
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.42 U	< 0.42 U	< 0.8 U		< 0.078 U	< 0.38 U	< 1.8 U	< 0.061 U	< 0.35 U	< 0.054 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.1 U	< 0.18 U	< 0.29 U		< 0.13 U	< 0.15 U	< 0.37 U	1.9	< 0.066 U	0.57 J
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.023 J	< 0.013 U	0.027 J
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	3	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.21 J	< 0.013 U	0.45
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.082 J	< 0.013 U	0.28 J
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.11 J	< 0.013 U	0.16 J
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.027 U	< 0.031 U	< 0.078 U	0.6	< 0.014 U	0.66
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.023 U	< 0.041 U	< 0.066 U		< 0.03 U	< 0.034 U	< 0.084 U	0.14 J	< 0.015 U	0.56
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.71	< 0.013 U	0.56
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	1.1	< 0.11 U	0.96
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.062 J	< 0.11 U	0.076
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.044 J	< 0.1 U	0.055 J
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	0.033 J
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	0.049 J	< 0.014 U	0.086 J
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0067 U	< 0.014 U	< 0.0095 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	0.038 J
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	0.016 J
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 UT	< 0.058 UT		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.25 J	< 0.013 U	0.33 J
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.079 J	< 0.013 U	0.12 J
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.21 U	< 0.38 U	< 0.61 U		< 0.27 U	< 0.31 U	< 0.77 U	< 0.066 U	< 0.14 U	0.89 J
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.046 J	< 0.013 U	0.075 J
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.022 U	< 0.039 UT	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.22 J	< 0.013 U	0.31 J
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.037 J	< 0.014 U	0.052 J
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.016 J	< 0.014 U	0.019 J
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.03 J	< 0.013 U	0.039 J
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.5 U	< 0.51 U	< 0.97 U		< 0.093 U	< 0.46 U	< 2.2 U	0.41	< 0.42 U	0.47
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.53 U	0.1	< 0.1 U	0.14
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.25 U	< 0.25 U	< 0.48 U		< 0.047 U	< 0.23 U	< 1.1 U	0.32	< 0.21 U	0.35
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 UT	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated		< 0.013 U	< 0.028 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated		< 0.47 U	< 0.49 U	< 0.41 U	< 0.39 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated		< 0.45 U	< 0.48 U	< 0.4 U	< 0.38 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated		< 0.056 U	< 0.12 U	< 0.18 U	< 0.23 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated		< 0.013 U	< 0.028 U	< 0.042 U	< 0.052 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated		< 0.12 U	< 0.26 U	< 0.38 U	< 0.48 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated		< 0.54 U	< 0.57 U	< 0.48 U	< 0.46 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated		< 0.27 U	< 0.29 U	< 0.24 U	< 0.23 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated			0.57	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	0.052 J
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated			ND	< 0.019 U	< 0.014 U	< 0.12 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated			0.47	< 0.062 U	< 0.047 U	< 0.39 U	< 0.056 U	< 0.47 U	< 0.4 U	< 0.13 U	< 0.098 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated			3.17	< 0.059 U	< 0.045 U	< 0.36 U	< 0.053 U	< 0.45 U	< 0.37 U	< 0.13 U	< 0.092 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated			0.359	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	0.04 J
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated			0.018	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated			0.034	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated			0.071	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.041 U	< 0.03 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated			0.231	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.026 J
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated			0.7323	< 0.01 U	< 0.01 U	< 0.018 U	0.016 J	< 0.021 U	< 0.013 U	< 0.059 U	0.078
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated			1.7429	< 0.0095 U	0.014 J	< 0.016 U	0.057 J	< 0.02 U	< 0.012 U	< 0.055 U	0.17
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated			0.287	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.029 J
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated			0.0469	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated			6.007	< 0.0096 U	0.05 J	< 0.016 U	0.22 J	< 0.02 U	< 0.012 U	< 0.056 U	0.61
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated			1.608	< 0.0097 U	0.013 J	< 0.017 U	0.054 J	< 0.02 U	< 0.012 U	< 0.056 U	0.16
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated			0.1903	< 0.01 UT	< 0.01 U	< 0.017 U	< 0.011 UT	< 0.021 U	< 0.012 U	< 0.058 U	0.026 JT
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated			0.941	< 0.01 U	< 0.01 U	< 0.018 U	0.019 J	< 0.022 U	< 0.013 U	< 0.06 U	0.1
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated			0.738	< 0.011 U	0.025 J	< 0.018 U	0.017 J	< 0.022 UT	< 0.013 U	< 0.061 U	0.059
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated			0.0282	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	0.013 J
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated			0.322	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.032 J
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated			2.069	0.017 J	0.02 J	< 0.018 U	0.062 J	< 0.021 U	< 0.013 U	< 0.06 U	0.17
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated			1.815	0.02 J	0.021 J	< 0.017 U	0.062 J	< 0.021 U	< 0.012 U	< 0.058 U	0.14
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated			0.1539	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	0.019 J
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated			0.0074	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated			ND	< 0.0096 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated			1.493	0.022 J	< 0.01 U	< 0.018 U	0.049 J	< 0.021 U	< 0.012 U	< 0.059 U	0.13
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated			0.478	< 0.01 U	< 0.01 U	< 0.017 U	0.017 J	< 0.021 U	< 0.012 U	< 0.058 U	0.044
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated			1.663	0.037 J	< 0.01 U	< 0.017 U	0.068 J	< 0.021 U	< 0.012 U	< 0.059 U	0.13
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated			0.775	< 0.011 U	0.021 J	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.066 U	0.065
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated			0.06	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated			0.0358	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.013 J
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated			0.018	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated			0.0299	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated			0.386	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.034 J
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated			0.0149	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated			34.174	0.044 J	0.34 J	< 0.018 U	1.3	< 0.021 UT	0.013 J	< 0.06 U	1
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated			0.227	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated			8.852	0.041 J	0.13 J	< 0.017 U	0.38	< 0.021 UT	0.015 J	< 0.058 U	0.65
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated			1.329	< 0.011 U	0.037 J	< 0.018 U	0.024 J	< 0.022 UT	< 0.013 U	< 0.061 U	0.096
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated			0.0473	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated			ND	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 U	< 0.012 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**	**Butylbenzyl phthalate**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	0.047 J	0.071 J	0.024 J	0.078	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.024 U	< 0.35 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.094 U	< 0.053 U	< 0.065 U	< 0.047 U	< 0.4 U	< 0.039 U	< 0.08 U	< 1.2 U	< 0.46 U	< 0.74 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.088 U	< 0.05 U	< 0.061 U	< 0.044 U	< 0.37 U	< 0.037 U	< 0.075 U	< 1.1 U	< 0.43 U	< 0.7 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	0.032 J	0.035 J	0.023 J	0.022 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.03 U	0.017 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.03 U	0.025 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	0.014 J	0.027 J	0.017 J	0.015 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	0.062	0.081	0.029 J	0.034 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	0.12	0.15	0.055	0.051 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	0.022 J	0.039	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	0.45	0.57	0.19	0.19 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	0.11	0.14	0.064	0.052 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	0.015 J	0.021 JT	0.0073 JT	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 UT	< 0.014 U	< 0.017 UT
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	0.072	0.1	0.036	0.046 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	0.06	0.1	0.031 J	0.06 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	0.028 J	0.036 J	0.011 J	0.025 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	0.16	0.21	0.069	0.1 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	0.12	0.15	0.076	0.088 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	0.015 J	0.015 J	0.018 J	0.015 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.0090 U	< 0.0088 U	< 0.0066 U	< 0.01 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	0.11	0.14	0.039	0.062 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	0.034 J	0.049	0.019 J	0.024 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	0.11	0.13	0.051	0.062 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	0.053	0.11	0.038 J	0.048 J	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.0092 U	0.012 J	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.0098 U	0.01 J	0.0079 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	0.028 J	0.041	0.018 J	0.022 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.0093 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	2.5	3	1.1	1.2	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	0.022 J	0.033 J	0.017 J	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	0.55	0.67	0.24	0.28 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	0.11	0.16	0.054	0.11 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.0092 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U

												Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.068 J	< 0.046 U	< 0.13 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.21 U	< 0.015 U	< 0.086 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.042 U	< 0.12 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.7 U	< 0.051 U	< 0.28 U	< 0.38 U	< 0.05 U	< 0.4 U	< 0.36 U	< 0.12 U	< 0.14 U	< 0.4 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.66 U	< 0.048 U	< 0.27 U	< 0.36 U	< 0.047 U	< 0.38 U	< 0.34 U	1.8	< 0.13 U	< 0.38 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.038 J	< 0.043 U	< 0.12 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.024 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.071 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	0.14 J	0.02 J	0.011 J
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.04 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0069 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.052 U	0.11 J	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.48	0.063	0.026 J
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.12 J	0.018 J	< 0.011 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.055 U	< 0.013 UT	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 UT	0.021 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.075 J	0.02 J	0.012 J
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 UT	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 UT	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 UT	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.032 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.056 U	0.02 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.16 J	0.026 J	0.014 J
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.054 U	0.02 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.13 J	0.018 J	0.021 J
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.017 J	0.015 J	< 0.011 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.0074 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.056 U	0.014 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.11 J	0.018 J	< 0.012 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.041 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.055 U	0.023 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.11 J	0.017 J	0.019 J
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.023 U	0.021 J	< 0.014 U	< 0.014 U	0.1 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0090 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0068 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.058 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.013 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.012 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.04 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.0076 J	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.056 U	0.82	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	2.6	0.39	0.16 J
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.032 J	< 0.016 U	< 0.012 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.054 U	0.16 J	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.62	0.086	0.18 J
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.12 J	0.029 J	0.024 J
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0063 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.31 U	< 0.025 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.14 U	< 0.19 U	< 0.57 U	< 0.13 U	< 2 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 1 U	< 0.083 U	< 0.38 U	< 0.36 U	< 0.43 U	< 0.47 U	< 0.63 U	< 1.9 U	< 0.42 U	< 6.7 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.95 U	< 0.079 U	< 0.36 U	< 0.34 U	< 0.4 U	< 0.45 U	< 0.59 U	< 1.8 U	< 0.4 U	< 6.3 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 UT	< 0.042 U	< 0.08 UT	< 0.013 UT	< 0.019 UT	< 0.14 U	< 0.025 UT	< 0.17 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.053 UT	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.054 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.051 UT	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg			mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.22 U	< 0.11 U			0.068 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.2 U	< 0.1 U			< 0.017 U	< 0.013 U	< 0.024 U	< 0.019 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.65 U	< 0.34 U			0.11 J	< 0.043 U	< 0.078 U	< 0.063 U	< 0.11 U	< 0.38 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.61 U	< 0.32 U			0.48	< 0.04 U	< 0.073 U	< 0.06 U	< 0.1 U	< 0.36 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.2 U	< 0.1 U			0.069	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.21 U	< 0.11 U			0.024 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.039 U		< 0.032 U		0.023 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.039 U		< 0.031 U		0.12 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.036 U		< 0.029 U		0.33	0.018 J	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.038 U		< 0.031 U		0.04 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.038 U		< 0.031 U		0.014 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.036 U		< 0.029 U		1.1	0.054 J	< 0.016 U	< 0.0072 U	< 0.029 U	< 0.012 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.037 U		< 0.03 U		0.3 J	0.016 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.038 UT		< 0.031 U		0.038 JT	< 0.01 UT	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.039 U		< 0.032 U		0.15 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.04 U		< 0.032 U		0.069 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.04 U		< 0.032 U		0.041 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.039 U		< 0.032 U		0.37	0.02 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.037 U		< 0.03 U		0.32 J	0.024 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 UT	< 0.012 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 UT	< 0.012 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 UT	< 0.012 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.036 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0084 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.039 U		< 0.031 U		0.24 J	0.016 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		0.079 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.038 U		< 0.031 U		0.28 J	0.03 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	< 0.043 U		< 0.035 U		0.08 J	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.037 U		< 0.03 U		0.012 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.039 U		< 0.032 U		0.06 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.039 U		< 0.032 U		5.5	0.32 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.039 U		< 0.032 U		0.037 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.038 U		< 0.031 U		1.5	0.26 J	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.04 U		< 0.032 U		0.14 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.039 U		< 0.032 U		0.013 J	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	0.057 J	< 0.1 U		< 0.14 U	0.02 J	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.033 U	< 0.094 U		< 0.12 U	< 0.016 U	< 0.097 U	< 0.013 U	< 0.15 U	< 0.084 U	< 0.12 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.11 U	< 0.31 U		< 0.41 U	< 0.052 U	< 0.32 U	< 0.042 U	< 0.49 U	< 0.28 U	< 0.4 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.1 U	< 0.29 U		< 0.38 U	< 0.049 U	< 0.3 U	< 0.04 U	< 0.46 U	< 0.26 U	< 0.38 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	0.048	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.028 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	0.041	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.0083 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	0.075	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	0.0069 J	< 0.026 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	0.015 J	< 0.022 U	0.026 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	0.26	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	0.02 J	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	0.066	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	0.0080 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 UT	< 0.084 UT	< 0.04 UT
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	0.055	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.013 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	0.066	< 0.014 U		< 0.11 U	0.035 J	< 0.023 U	0.031 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 UT	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 UT	< 0.04 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 UT	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 UT	< 0.041 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 UT	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 UT	< 0.039 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	0.027 J	< 0.014 U		< 0.11 U	0.033 J	< 0.023 U	0.025 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	0.12	< 0.014 U		< 0.1 U	0.018 J	< 0.023 U	0.025 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	0.1	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.017 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	0.017 J	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	0.064	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	0.013 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	0.024 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	0.066	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.012 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	0.09	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	0.04 J	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	0.018 J	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.01 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	1.5	< 0.013 U		< 0.1 U	0.032 J	< 0.023 U	0.12 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	0.02 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	0.32	< 0.013 U		< 0.1 U	0.03 J	< 0.022 U	0.055 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	0.11	< 0.014 U		< 0.11 U	0.036 J	< 0.023 U	0.11 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.014 U	< 0.014 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.042 J	< 0.11 U	0.063 J
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.022 U	< 0.11 U	< 0.53 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.4 U	< 0.4 U	< 0.76 U		< 0.073 U	< 0.36 U	< 1.7 U	0.19 J	< 0.33 U	0.17 J
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.37 U	< 0.38 U	< 0.71 U		< 0.069 U	< 0.34 U	< 1.6 U	0.89	< 0.31 U	< 0.048 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	0.035 J	< 0.1 U	0.065 J
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.018 J
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	0.017 J
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.022 J
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.011 J	< 0.013 U	0.026 J
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 UT		< 0.026 U	< 0.03 U	< 0.074 U	0.082 J	< 0.013 U	0.11 J
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 UT		< 0.024 U	< 0.028 U	< 0.069 U	0.27 J	< 0.012 U	0.28 J
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.046 J	< 0.013 U	0.045 J
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 UT		< 0.025 U	< 0.029 U	< 0.072 U	0.014 J	< 0.013 U	0.012 J
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 UT		< 0.024 U	< 0.028 U	< 0.069 U	0.84	< 0.012 U	0.96
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 UT		< 0.025 U	< 0.028 U	< 0.07 U	0.25 J	< 0.013 U	0.25 J
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 UT		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 UT		< 0.026 UT	< 0.029 U	< 0.072 U	0.026 J	< 0.013 U	0.036 JT
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 UT		< 0.027 U	< 0.03 U	< 0.075 U	0.097 J	< 0.013 U	0.15 J
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.067 J	< 0.014 U	0.083 J
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.0064 J	< 0.013 U	0.0088 J
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.03 J	< 0.014 U	0.035 J
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.25 J	< 0.013 U	0.31 J
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.28 J	< 0.013 U	0.27 J
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0060 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0089 J	< 0.013 U	0.014 J
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.019 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0098 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.2 J	< 0.013 U	0.28 J
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.062 J	< 0.013 U	0.085 J
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.27 J	< 0.013 U	0.29 J
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	0.075 J	< 0.015 U	0.076 J
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 UT
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.013 J	< 0.013 U	0.014 JT
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	0.016 J
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 UT
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 UT
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 UT
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.043 J	< 0.013 U	0.065 JT
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	0.0073 J	< 0.013 U	< 0.0087 UT
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0087 UT
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	5.2	< 0.013 U	6.4 T
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 UT
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.021 J	< 0.013 U	0.045 JT
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	1.8	< 0.013 U	1.4 T
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.096 J	< 0.014 U	0.17 JT
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.014 J	< 0.013 U	0.014 JT
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 UT

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated		< 0.13 U	< 0.14 U	< 0.11 U	< 0.11 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated		< 0.43 U	< 0.45 U	< 0.38 U	< 0.36 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated		< 0.4 U	< 0.42 U	< 0.35 U	< 0.34 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.043 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAHS	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated			0.0065	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated			3.292	< 0.011 U	0.052 J	< 0.019 U	0.12 J	< 0.022 U	< 0.013 U	< 0.063 U	0.28
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated			0.137	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.06 U	0.021 J
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated			0.187	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.024 J
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated			0.1808	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.022 J
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated			0.081	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 UT	< 0.021 U	< 0.012 UT	< 0.059 U	0.017 JT
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated			0.379	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.03 J
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated			1.595	< 0.01 U	0.038 J	< 0.018 U	0.031 J	< 0.021 U	< 0.013 U	< 0.06 U	0.12
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated			0.17	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.015 J
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated			0.0312	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated			5.184	< 0.01 U	0.087 J	< 0.017 U	0.059 J	< 0.021 UT	< 0.012 U	< 0.059 UT	0.42
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.27	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated			2.394	0.033 J	0.034 J	< 0.019 U	0.085 J	< 0.022 U	< 0.013 U	< 0.063 U	0.2
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated			3.651	< 0.01 U	0.039 J	< 0.018 UT	0.1 J	< 0.021 UT	< 0.013 U	< 0.06 U	0.35
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated			0.028	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated			0.411	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	0.047
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated			ND	< 0.0095 U	< 0.0095 U	< 0.016 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated			0.0307	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	0.013 J
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated			ND	< 0.0096 U	< 0.0096 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated			0.117	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated			0.012	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated			0.508	< 0.0097 U	0.017 J	< 0.017 U	0.011 J	< 0.02 U	< 0.012 U	< 0.056 U	0.041
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated			0.248	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	0.025 J
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated			ND	< 0.0097 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated			ND	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated			ND	< 0.0098 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.06 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated			1.959	< 0.0098 U	0.065 J	< 0.017 U	0.044 J	< 0.02 U	< 0.012 U	< 0.057 U	0.15
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated			ND	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated			ND	< 0.0095 U	< 0.0096 U	< 0.016 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.055 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated			0.021	< 0.0098 U	< 0.0098 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.057 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated			0.059	< 0.01 U	0.018 J	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated			0.0661	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.06 U	0.014 J
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated			0.255	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	0.024 J
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated			0.1679	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 UT	< 0.012 U	< 0.056 UT	0.017 J
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated			0.13	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	0.018 J
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated			0.13	< 0.0099 U	< 0.0099 U	< 0.017 U	< 0.011 U	< 0.02 UT	< 0.012 U	< 0.057 UT	0.018 J
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated			0.134	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 UT	< 0.013 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated			0.522	< 0.011 U	0.011 J	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 UT	0.037
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated			0.3496	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 UT	< 0.013 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated			1.179	< 0.011 U	0.023 J	< 0.018 U	0.024 J	< 0.022 UT	< 0.013 U	< 0.061 UT	0.089
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated			0.495	< 0.01 U	< 0.01 U	< 0.018 U	0.011 J	< 0.021 U	< 0.012 U	< 0.059 U	0.052
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated			0.0097	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.013 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated			0.2578	< 0.0098 U	< 0.0099 U	< 0.017 U	0.031 J	< 0.02 UT	< 0.012 U	< 0.057 U	0.026 J
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated			0.056	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated			0.0253	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated			0.012	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated			0.335	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	0.03 J
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated			2.029	< 0.01 U	0.077 J	< 0.018 U	0.025 J	< 0.022 U	< 0.013 U	< 0.061 U	0.12
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated			4.554	0.013 J	0.22 JT	< 0.018 UT	0.1 JT	< 0.021 UT	0.016 J	< 0.06 U	0.27
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated			0.9209	< 0.0099 U	0.041 J	< 0.017 U	0.014 J	< 0.02 U	< 0.012 U	< 0.057 U	0.055
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated			2.467	< 0.01 U	0.08 J	< 0.018 U	0.025 J	< 0.021 U	< 0.012 U	< 0.059 U	0.16
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated			0.3592	< 0.0099 U	0.016 J	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	0.024 J

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]	Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	0.25	0.27	0.13	0.13 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.0097 U	0.015 J	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	0.016 J	0.017 J	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	0.014 J	0.015 J	0.0088 J	< 0.01 U	< 0.028 U	< 0.012 UT	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.0095 U	< 0.0092 UT	< 0.0070 UT	< 0.011 UT	< 0.028 U	< 0.012 UT	< 0.0064 U	< 0.019 U	< 0.014 UT	< 0.017 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	0.022 J	0.033 J	0.013 J	0.018 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	0.14	0.2	0.091	0.12 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	0.016 J	0.024 J	0.014 J	0.015 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	0.56	0.75	0.24	0.45	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U	< 0.018 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	0.18	0.26	0.11	0.11 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	0.28 T	0.36 T	0.14	0.18 J	< 0.028 UT	< 0.013 UT	< 0.0066 UT	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.0097 U	< 0.0094 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	0.033 J	0.043	0.02 J	0.024 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.0089 U	< 0.0086 U	< 0.0065 U	< 0.0098 U	< 0.026 U	< 0.012 U	< 0.0060 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0090 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	0.019 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	0.012 J	< 0.026 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	0.036	0.062	0.033 J	0.042 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	0.015 J	0.025 J	0.011 J	0.011 J	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0091 U	< 0.0088 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	0.17	0.23	0.11	0.19 J	< 0.027 U	< 0.012 U	< 0.0062 U	0.021 J	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0091 U	< 0.0089 U	< 0.0067 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0089 U	< 0.0087 U	< 0.0066 U	< 0.0099 U	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0092 U	< 0.0089 U	< 0.0067 U	0.021 J	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	0.034 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.0097 U	0.014 J	< 0.0072 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.0099 U	< 0.0096 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	0.024 J	0.036 J	0.013 J	0.034 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	0.017 J	0.022 J	0.0099 J	0.02 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	0.012 J	0.014 J	0.015 J	0.013 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	0.012 J	0.014 J	0.015 J	0.013 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	0.011 J	0.015 J	< 0.0072 U	0.013 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	0.041	0.051	0.017 J	0.041 J	< 0.029 U	< 0.013 U	< 0.0067 U	0.028 J	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	0.014 J	0.026 J	0.0076 J	0.026 J	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	0.089	0.14	0.049	0.1 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	0.035 J	0.046	0.019 J	0.023 J	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.011 U	< 0.028 U	< 0.013 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	0.016 J	0.024 J	0.0098 J	0.014 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	< 0.0099 U	0.014 J	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	0.065 J	< 0.015 U	< 0.017 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	< 0.0095 U	0.0093 J	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.0095 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	0.027 J	0.035 J	0.012 J	0.021 J	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	0.16	0.25	0.11	0.18 J	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	0.38 T	0.61 T	0.24	0.38 T	< 0.028 UT	< 0.013 UT	< 0.0066 UT	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	0.085	0.13	0.049	0.11 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	0.2	0.33	0.11	0.24 J	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	0.033 J	0.053	0.02 J	0.034 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

												Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			1	0.33	7
Restricted - Residential																			3.9	0.33	59
Protection of Groundwater																			1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	< 0.059 U	0.081 J	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.26 J	0.042	0.016 J
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.015 J	< 0.016 U	< 0.012 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.017 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.018 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 UT	< 0.013 U	< 0.013 UT	0.011 JT	< 0.015 UT	< 0.012 UT
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.036 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.056 U	0.017 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.14 J	0.039	0.021 J
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.021 J	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.055 UT	0.02 J	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.39	0.066	0.016 J
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.059 U	0.03 J	< 0.067 U	< 0.021 U	< 0.018 U	< 0.013 U	< 0.013 U	0.2 J	< 0.016 U	0.023 J
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.055 UT	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.056 UT	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 UT	< 0.013 U	0.33 J	0.045	< 0.012 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.013 J	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.055 UT	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.04 J	< 0.015 U	< 0.012 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.052 UT	< 0.013 U	< 0.059 U	< 0.019 U	< 0.015 U	< 0.012 U	< 0.012 U	< 0.0056 U	< 0.014 U	< 0.011 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.0077 J	< 0.017 U	< 0.013 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.046 J	0.018 J	< 0.011 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	0.02 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.054 U	0.02 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.17 J	0.043	0.026 J
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.052 U	< 0.013 U	< 0.059 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0057 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.053 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0058 U	< 0.015 U	< 0.011 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.063 U	< 0.015 U	< 0.071 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.06 UT	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U	< 0.013 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.057 UT	< 0.014 U	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.0087 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.023 J	< 0.016 U	< 0.012 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.053 UT	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.014 J	< 0.015 U	< 0.011 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.017 J	< 0.015 U	< 0.012 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.054 UT	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.017 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.019 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.069 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	0.017 J
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.058 UT	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.091 J	0.021 J	0.014 J
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.047 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	< 0.054 U	< 0.013 U	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.024 J	< 0.015 U	< 0.012 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.035 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.18 J	0.052	0.013 J
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.057 U	0.029 JT	< 0.065 U	< 0.02 UT	< 0.017 U	< 0.013 UT	< 0.013 U	0.38 T	0.11	0.038 J
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.088 J	0.03 J	< 0.012 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.056 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.23 J	0.068	0.013 J
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	0.037 J	< 0.015 U	< 0.012 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																						
Restricted - Residential																						
Protection of Groundwater																						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.027 U	< 0.19 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.054 U	< 0.023 UT	< 0.011 UT	< 0.043 U	< 0.081 UT	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 UT	< 0.18 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	0.056 J	< 0.021 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	0.062 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	0.063 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	0.05 J	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	0.022 J	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	0.033 J	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 UT	< 0.082 U	0.044 J	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 UT
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.05 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.051 U	< 0.021 U	< 0.011 U	< 0.04 U	< 0.076 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.16 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.078 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.06 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.055 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 UT	< 0.083 U	< 0.014 UT	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U

													2,4-Dinitrotoluene	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**	**Hexachloroethane**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	< 0.041 U		< 0.033 U		0.62	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.039 U		< 0.032 U		0.031 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.038 U		< 0.031 U		0.038 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.038 U		< 0.031 U		0.034 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.038 U		< 0.031 U		0.02 J	< 0.01 UT	< 0.017 UT	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.038 U		< 0.031 U		0.055 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.039 U		< 0.032 U		0.18 J	0.014 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.038 U		< 0.031 U		0.023 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.038 U		< 0.031 U		0.68	0.012 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0083 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.27	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.041 U		< 0.033 U		0.35 J	0.035 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.039 U		< 0.032 U		0.71 T	0.011 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 UT
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.038 U		< 0.031 U		0.078 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0097 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.011 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U	< 0.013 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		0.015 J	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		0.062 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.038 U		< 0.031 U		0.037 J	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		0.24 J	0.013 J	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.036 U		< 0.029 U		< 0.012 U	< 0.0098 U	< 0.016 U	< 0.0071 U	< 0.029 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U	< 0.013 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.04 U		< 0.032 U		0.025 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.037 U		< 0.03 U		0.015 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.04 U		< 0.032 U		0.014 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.04 U		< 0.032 U		0.058 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.04 U		< 0.033 U		0.023 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.04 U		< 0.032 U		0.17 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U	< 0.013 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.039 U		< 0.031 U		0.11 J	< 0.011 U	< 0.017 U	< 0.0076 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	< 0.037 U		< 0.03 U		0.03 J	< 0.01 U	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	< 0.04 U		< 0.033 U		0.017 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.04 U		< 0.032 U		0.041 J	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.04 U		< 0.032 U		0.22 J	0.015 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.039 U		< 0.032 U		0.45	0.041 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.037 U		< 0.03 U		0.088 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.038 U		< 0.031 U		0.3 J	0.016 J	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.038 U		< 0.03 U		0.042 J	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0065 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.023 U	< 0.0062 U	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	0.18	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 UT	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.014 UT	< 0.013 U		< 0.1 UT	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	0.016 J	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.011 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	0.12	< 0.013 U		< 0.1 U	0.021 J	< 0.023 U	0.079 J	< 0.027 U	< 0.086 U	< 0.041 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	0.023 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	0.63	< 0.013 U		< 0.1 U	0.01 J	< 0.022 U	0.037 J	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0068 U	< 0.03 U	< 0.093 U	< 0.045 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	0.2	< 0.014 U		< 0.11 U	0.022 J	< 0.024 U	0.051 J	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.023 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.04 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U	< 0.043 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	0.23	< 0.014 UT		< 0.1 UT	< 0.01 UT	< 0.023 UT	0.025 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	0.029 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.013 U	< 0.012 U		< 0.096 U	< 0.0093 U	< 0.021 U	< 0.0058 U	< 0.025 U	< 0.079 U	< 0.038 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	0.053	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	0.052	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	0.023 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	0.052	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	0.2	< 0.013 U		< 0.1 U	0.02 J	< 0.022 U	0.085 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	< 0.0058 U	< 0.026 U	< 0.08 U	< 0.038 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.013 U	< 0.013 U		< 0.099 U	< 0.0096 U	< 0.021 U	< 0.0059 U	< 0.026 U	< 0.082 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.095 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U	< 0.044 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.0074 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	0.034 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	0.019 J	< 0.013 U		< 0.098 U	< 0.0095 U	< 0.021 U	0.016 J	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	0.017 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	0.014 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.014 J	< 0.028 U	< 0.088 U	< 0.042 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	0.043	< 0.014 U		< 0.11 U	0.011 J	< 0.023 U	0.036 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	0.034 J	< 0.014 U		< 0.11 U	0.015 J	< 0.023 U	0.16 J	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	0.11	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.036 J	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	0.028 J	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	0.015 J	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.012 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	0.017 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	0.21	< 0.014 U		< 0.11 U	0.045 J	< 0.023 U	0.17 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	0.43	< 0.014 UT		< 0.11 UT	0.087 JT	< 0.023 UT	0.45 T	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	0.12	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	0.0069 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	0.27	< 0.013 U		< 0.1 U	0.027 J	< 0.022 U	0.057 J	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	0.04	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.0082 J	< 0.027 U	< 0.083 U	< 0.04 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.8	100	0.33	100
Restricted - Residential																		6.7	100	100	100
Protection of Groundwater																		0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 UT
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.49	< 0.014 U	0.52
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.029 J	< 0.013 U	0.026 J
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.039 J	< 0.013 U	0.036 J
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 UT	< 0.029 U	< 0.073 U	0.034 J	< 0.013 U	0.035 J
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.02 U	< 0.036 U	0.069 J		< 0.026 UT	< 0.029 UT	< 0.073 U	0.016 JT	< 0.013 U	0.017 JT
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.057 J	< 0.013 U	0.088 J
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.091 J	< 0.013 U	0.23 J
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.014 J	< 0.013 U	0.028 J
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.0082 J	< 0.013 U	< 0.0088 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.22 J	< 0.013 U	0.67
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.022 U	< 0.039 U	< 0.064 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0069 U	< 0.014 U	< 0.0097 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.26 J	< 0.014 U	0.32 J
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0094 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0090 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.02 UT	< 0.036 U	< 0.059 UT		< 0.026 UT	< 0.03 U	< 0.074 U	0.21 J	< 0.013 UT	0.68
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	0.015 J
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.024 J	< 0.013 U	0.073 J
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.018 U	< 0.033 U	< 0.054 U		< 0.024 U	< 0.027 U	< 0.068 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U	0.01 J
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0084 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	0.0080 J	< 0.013 U	0.022 J
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	0.026 J	< 0.012 U	0.056 J
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.021 J	< 0.013 U	0.031 J
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0060 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	< 0.0061 U	< 0.013 U	< 0.0086 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.094 J	< 0.013 U	0.22 J
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	< 0.0059 U	< 0.012 U	< 0.0083 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.013 U	< 0.0085 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U	< 0.0091 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.082 U	< 0.0071 U	< 0.015 U	< 0.01 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 U	< 0.0070 U	< 0.015 U	< 0.0099 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.021 U	< 0.038 U	0.096 J		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U	< 0.0096 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.075 U	0.0080 J	< 0.013 U	0.014 J
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	< 0.0092 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.015 J	< 0.014 U	0.027 J
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.07 U	< 0.0060 U	< 0.012 U	0.018 J
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.011 J	< 0.013 U	0.013 J
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.011 J	< 0.013 U	0.013 J
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.015 J	< 0.014 U	0.019 J
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	0.067 J	< 0.014 U	0.062 J
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	0.03 J	< 0.014 U	0.029 J
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	0.11 J	< 0.014 U	0.15 J
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	0.036 J	< 0.013 U	0.088 J
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated	< 0.02 U	< 0.036 U	< 0.059 U		< 0.026 U	< 0.03 U	< 0.074 U	< 0.0063 U	< 0.013 U	0.0097 J
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.032 J	< 0.013 U	0.024 J
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.076 U	< 0.0065 U	< 0.014 U	0.025 J
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	0.016 J
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0063 U	< 0.013 U	0.012 J
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.041 J	< 0.014 U	0.051 J
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	0.067 J	< 0.014 U	0.27 J
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.02 UT	< 0.037 U	< 0.059 U		< 0.026 UT	< 0.03 U	< 0.075 U	0.14 JT	< 0.013 UT	0.56
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.025 J	< 0.013 U	0.12 J
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	0.091 J	< 0.013 U	0.37
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	0.013 J	< 0.013 U	0.055 J

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated		< 0.011 UT	< 0.024 UT	< 0.036 UT	< 0.046 UT
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.046 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated		< 0.01 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469431	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAHS**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated			9.656	0.023 J	0.53	< 0.019 U	0.21 J	< 0.023 U	0.035 J	< 0.065 U	0.86
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated			0.935	< 0.01 U	0.018 J	< 0.017 U	0.021 J	< 0.021 U	< 0.012 U	< 0.058 U	0.091
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated			46.62	0.59	0.75	0.038 J	1.7	< 0.024 U	0.089 J	< 0.067 U	4.2
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated			0.0425	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated			1.847	< 0.011 U	< 0.012 UT	< 0.02 UT	0.03 JT	< 0.024 U	< 0.014 UT	< 0.067 U	0.14 T
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated			0.237	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	0.035 J
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated			11.07	0.064 J	0.31 J	< 0.018 U	0.28 J	< 0.021 U	0.022 J	< 0.06 U	1.1
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated			4.89	0.013 J	0.16 J	< 0.019 U	0.089 J	< 0.022 U	< 0.013 U	< 0.063 U	0.41
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated			0.5099	< 0.0096 U	< 0.0096 U	< 0.017 U	0.02 J	< 0.02 U	< 0.012 U	< 0.056 U	0.052
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated			3.379	0.017 J	0.042 J	< 0.017 U	0.05 J	< 0.02 U	< 0.012 U	< 0.057 U	0.33
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.013 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated			0.343	< 0.0097 U	< 0.0097 U	< 0.017 U	< 0.01 U	< 0.02 U	< 0.012 U	< 0.056 U	0.035
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated			79.39	1.6	0.17 J	< 0.017 U	4 T	< 0.02 U	0.18 J	< 0.056 U	7.2 T
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated			3.288	0.025 J	0.047 J	< 0.018 U	0.075 J	< 0.021 U	< 0.013 U	< 0.06 U	0.33
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 UT	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 UT	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated			4.287	< 0.02 U	0.094	< 0.13 U	0.12	< 0.15 U	< 0.13 U	< 0.044 U	0.4
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated			2.816	< 0.021 U	0.06 J	< 0.13 U	0.076	< 0.16 U	< 0.13 U	< 0.044 U	0.26
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated			3.146	< 0.021 U	0.086	< 0.13 U	0.095	< 0.16 U	< 0.13 U	< 0.045 U	0.26
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated			0.26	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 UT	< 0.12 U	< 0.042 U	0.032 J
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated			5.343	0.03 J	0.03 J	< 0.13 U	0.16	< 0.15 U	< 0.13 U	< 0.044 U	0.45
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated			5.648	< 0.019 U	< 0.015 U	< 0.12 U	0.25	< 0.15 U	< 0.12 U	< 0.042 U	0.59
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated			0.285	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	0.041 J
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated			0.017	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated			7.143	0.11	< 0.015 U	< 0.13 U	0.26	< 0.15 U	< 0.13 U	< 0.044 U	0.58
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated			0.018	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated			ND	< 0.0074 U	< 0.0089 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.035 U	< 0.058 U	< 0.0097 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated			ND	< 0.0071 U	< 0.0085 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0093 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated			ND	< 0.0069 U	< 0.0082 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.009 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15 EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated			4.16	< 0.11 U	< 0.087 U	< 0.11 U	0.14 J	< 0.87 U	< 0.084 U	< 0.25 U	0.24 J
Rear Parking Lot	SSHS-SS-12 8 20	082218 09:15 SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated			0.1	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	0.02 J
Rear Parking Lot	SSHS-SS-14 8 20	082218 09:15 SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.015 U
Rear Parking Lot	SSHS-SS-16 8 20	082218 09:15 SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated			0.017	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.052 U	< 0.016 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated			0.9	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	0.23
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated			ND	< 0.0073 U	< 0.0088 U	< 0.031 U	< 0.0075 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0096 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated			0.02	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated			0.036	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U		< 0.035 U
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated			1.476	< 0.0075 U	< 0.0089 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.035 U	0.1 J	0.087
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated			2.18	< 0.0078 U	< 0.0093 U	0.094 J	0.033 J	< 0.04 U	0.045 J	0.14 J	0.11
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated			0.029	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated			0.019	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated			0.636	< 0.0074 U	< 0.0089 U	< 0.032 U	0.013 J	< 0.038 U	< 0.035 U	< 0.058 U	0.042 J
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated			0.311	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	0.035 J
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated			2.13	< 0.021 U	0.044 J	< 0.13 U	0.07 J	< 0.16 U	< 0.13 U	< 0.045 U	0.18
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated			0.922	< 0.023 U	< 0.017 U	< 0.14 U	0.03 J	< 0.17 U	< 0.15 U	< 0.049 U	0.079 J
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated			3.399	< 0.061 U	0.051 J	< 0.057 U	0.058 J	< 0.46 U	< 0.044 U	< 0.13 U	0.42
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated			1.228	< 0.0079 U	< 0.0094 U	0.057 J	0.014 J	< 0.04 U	< 0.037 U	0.1 J	0.055 J
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated			0.835	< 0.0081 U	0.025 J	< 0.035 U	0.022 J	< 0.041 U	< 0.038 U	< 0.063 U	0.081 J
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated			19.45	0.18 J	0.2 J	< 0.096 U	0.32 J	< 0.77 U	< 0.074 U	< 0.22 U	1.6
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated			6.951	< 0.034 U	0.11 J	< 0.034 U	0.19 J	< 0.039 U	< 0.034 U	< 0.034 U	0.64 J
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated			60.581	0.061 J	1.1	< 0.025 U	2	< 0.051 U	0.043 J	< 0.024 U	5.5
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated			100.877	0.087 J	1.6	< 0.034 U	3.1	< 0.071 U	< 0.034 U	< 0.11 U	9.3
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated			7.668	< 0.034 U	0.11	< 0.034 U	0.24	< 0.034 U	< 0.034 U	< 0.052 U	0.66
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated			3.154	0.029 J	0.065 J	< 0.034 U	0.1	< 0.036 U	< 0.034 U	< 0.055 U	0.26
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.024 U	< 0.026 U	< 0.049 U	< 0.028 U	< 0.023 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated			8.578	0.027 J	0.12	< 0.034 U	0.3	< 0.17 U	< 0.034 U	< 0.034 U	0.66
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated			1.821	< 0.034 U	< 0.061 UJ	< 0.034 U	< 0.072 UJ	< 0.61 U	< 0.034 U	< 0.17 U	0.15 J
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 UJ	< 0.0094 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^{1} (ft amsl)	Final grade elevation^{2} (ft amsl)	Change in surface elevation^{3} (ft)	Grab sample elevation^{4} (ft amsl)	Sample depth at time of sampling^{5} (bgs)	Sample depth from final grade^{6} (bfg)	Lab Report	Excavation Status^{7}										
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	0.88	1.3	0.5	0.74	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	0.084	0.12	0.047	0.056 J	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	3.7	5	2.1	2	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U	< 0.019 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.01 U	0.01 J	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0073 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	0.14 T	0.22 T	0.072 T	0.1 JT	< 0.031 UT	< 0.014 UT	< 0.0073 U	< 0.021 U	< 0.016 UT	< 0.019 U
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	0.021 J	0.03 J	0.012 J	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U	< 0.017 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	0.97	1.4	0.52	0.64	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	0.4	0.61	0.24	0.32 J	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U	< 0.018 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	0.042	0.052	0.023 J	0.025 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	0.3	0.45	0.19	0.18 J	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.0096 U	< 0.0093 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0065 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	0.028 J	0.041	0.017 J	0.019 J	< 0.026 U	< 0.012 U	< 0.0061 U	< 0.018 U	< 0.013 U	< 0.016 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	6 T	7.3 T	3.1 T	3 T	< 0.027 U	< 0.012 U	< 0.0062 U	< 0.018 U	< 0.014 U	< 0.016 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	0.3	0.36	0.21	0.17 J	< 0.028 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.014 U	< 0.017 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	0.36	0.42	0.17	0.29	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	0.24	0.25	0.13	0.19	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	0.28	0.38	0.12	0.2	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	0.038 J	0.039 J	0.022 J	0.026 J	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.43	0.61	0.24	0.25	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.33	0.39	0.2	0.095	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U	< 0.23 U
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	0.034 J	0.047 J	< 0.021 U	0.018 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	0.26	0.36	0.13	0.11	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U	< 0.25 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.0078 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.0072 U	< 0.011 U	< 0.015 U	< 0.0071 U	< 0.024 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U	< 0.049 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	0.31 J	0.4	0.2 J	0.49	< 0.095 U	< 0.072 U	< 0.15 U	< 2.1 U	< 0.14 U	< 1.4 U
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated	< 0.017 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated	< 0.017 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U	< 0.27 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated	< 0.018 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U	< 0.29 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.025 U	< 0.03 U	< 0.44 U	< 0.17 U	< 0.28 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.0077 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.033 U	< 0.052 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.26 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.26 U
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	0.048 J	0.14	0.035 J	0.14	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	0.084	0.15	0.037 J	0.14	< 0.027 U	< 0.011 U	< 0.0088 U	< 0.066 U	< 0.035 U	< 0.056 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.25 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U	< 0.27 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	0.029 J	0.062 J	< 0.016 U	< 0.0077 U	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.033 U	0.033 J	< 0.023 U	0.066 J	< 0.14 U	< 0.024 U	< 0.029 U	< 0.41 U	< 0.16 U	< 0.27 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	0.15	0.19	0.069 J	0.17	< 0.13 U	< 0.022 U	< 0.027 U	0.66 J	< 0.15 U	< 0.25 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	0.074 J	0.082	0.044 J	0.083	< 0.15 U	< 0.025 U	< 0.03 U	< 0.42 U	< 0.17 U	< 0.27 U
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	0.24	0.33	< 0.064 U	0.21	< 0.05 U	< 0.038 U	< 0.078 U	< 1.1 U	< 0.074 U	< 0.73 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	0.052 J	0.089	< 0.017 U	0.087	< 0.027 U	< 0.011 U	< 0.0089 U	< 0.067 U	< 0.036 U	< 0.056 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	0.056 J	0.077 J	0.029 J	0.068 J	< 0.028 U	< 0.011 U	< 0.0091 U	< 0.068 U	< 0.037 U	< 0.058 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.24 U
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	1.1	1.9	0.59	1.4	< 0.084 U	< 0.064 U	< 0.13 U	< 1.9 U	< 0.12 U	< 1.2 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated	0.61 J	0.72 J	0.32	0.5	< 0.026 U	< 0.011 U	< 0.0087 U	< 0.065 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	4.7	5.7	2.2	3.5	< 0.021 U	< 0.022 U	< 0.024 U	< 0.25 U	< 0.035 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated	8.1	9.9	3.5	6.1	< 0.048 U	< 0.02 U	< 0.016 U	< 0.12 U	< 0.064 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated	0.61	0.77	0.21	0.47	< 0.023 U	< 0.0093 U	< 0.0075 U	< 0.056 U	< 0.03 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	0.25	0.3	0.13	0.23	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated	< 0.029 U	< 0.031 U	< 0.024 U	< 0.031 U	< 0.02 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	0.45	0.62	0.25	0.34	< 0.034 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	0.14 J	0.23 J	< 0.084 UJ	0.21 J	< 0.51 U	< 0.051 U	< 0.1 U	< 1.5 U	< 0.59 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.032 U	< 0.051 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Caprolactam	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**	**Dibenzofuran**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.062 U	0.071 J	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	0.95	0.19	0.087 J
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	0.088 J	0.017 J	< 0.012 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.063 U	0.59	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	4.1	0.66	0.47
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.059 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U	< 0.013 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0063 U	< 0.016 U	< 0.012 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.063 U	0.02 JT	< 0.072 U	< 0.023 UT	< 0.019 UT	< 0.014 UT	< 0.014 UT	0.15 JT	0.041 T	< 0.013 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.058 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	0.029 J	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.057 U	0.092 J	< 0.065 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	1	0.19	0.075 J
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.059 U	0.029 J	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	0.47	0.082	0.027 J
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.052 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.042 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.054 U	0.018 J	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.34 J	0.06	0.017 J
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U	< 0.012 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.056 U	< 0.014 U	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0061 U	< 0.016 U	< 0.012 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.053 U	< 0.013 U	< 0.06 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	0.031 J	< 0.015 U	< 0.011 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.053 U	1.5	< 0.061 U	< 0.019 U	< 0.016 U	< 0.012 U	< 0.012 U	5.7 T	0.99	1.3
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.056 U	0.025 J	< 0.064 U	< 0.02 U	< 0.017 U	< 0.013 U	< 0.013 U	0.29 J	0.06	0.018 J
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.12 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.12 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.23 U	0.023 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.39	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.043 U	< 0.13 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.23 U	0.02 J	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.26	0.047 J	< 0.13 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.27	0.058 J	< 0.13 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.23 U	0.043 J	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.53	0.069 J	< 0.13 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.22 U	0.19	< 0.089 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	0.6	0.043 J	< 0.12 U
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	< 0.23 U	0.19	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.58	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U	< 0.13 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	< 0.038 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0066 U	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	< 0.0085 U	< 0.008 U	< 0.035 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	< 1.3 U	< 0.093 U	< 0.066 U	< 0.094 U	< 0.091 U	< 0.093 U	< 0.12 U	0.31 J	< 0.089 U	< 0.087 U
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	0.052 J	< 0.018 U	< 0.017 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated	< 0.25 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.015 U	< 0.017 U	< 0.017 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated	< 0.27 U	< 0.02 U	< 0.014 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.017 U	< 0.019 U	< 0.019 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.22 U	< 0.016 U	< 0.089 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	0.41	< 0.052 U	< 0.15 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.038 U	< 0.044 U	< 0.13 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.007 U	< 0.031 U	< 0.035 U	< 0.008 U	< 0.031 U	< 0.042 U	< 0.0091 U	< 0.0085 U	< 0.038 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U	< 0.13 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U	< 0.14 U
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.0072 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	0.23	< 0.0087 U	0.072 J
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.31 U	< 0.0075 U	< 0.033 U	< 0.037 U	< 0.0085 U	< 0.033 U	< 0.045 U	0.31	0.041 J	0.13 J
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U	< 0.14 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	0.13	< 0.0086 U	< 0.038 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.048 J	< 0.049 U	< 0.14 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.23 U	0.024 JT	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	0.19	< 0.046 U	< 0.13 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.26 U	< 0.019 UT	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	0.084	< 0.051 U	< 0.15 U
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	< 0.69 UJ	< 0.05 U	< 0.035 UJ	< 0.05 U	< 0.049 U	< 0.049 U	< 0.064 U	0.8	< 0.047 U	< 0.046 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.31 U	< 0.0076 U	< 0.033 U	< 0.038 U	< 0.0086 U	< 0.034 U	< 0.046 U	0.19	< 0.0092 U	0.079 J
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.32 U	< 0.0078 U	< 0.034 U	< 0.039 U	< 0.0088 U	< 0.035 U	< 0.047 U	0.11	< 0.0094 U	< 0.042 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.044 U	< 0.13 U
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	< 1.1 U	0.19 J	< 0.059 U	< 0.083 U	< 0.081 U	< 0.082 U	< 0.11 U	1.7	0.31 J	0.28 J
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated	< 0.3 U	0.095	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.55 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	< 0.17 U	0.95	< 0.021 U	< 0.039 U	< 0.024 U	< 0.026 U	< 0.026 U	4.3	0.93	0.3 J
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated	< 0.55 U	1.7	< 0.059 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	7.3	1.4	0.39 J
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated	< 0.26 U	0.12	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.55	0.12	0.034 J
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.28 U	0.042 J	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24	< 0.034 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	< 0.028 U	< 0.029 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.25 U	0.062 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.68	0.091	0.2 J
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.91 U	< 0.034 U	< 0.37 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.15 J	< 0.034 U	< 0.51 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.041 U	< 0.0089 U	< 0.0083 U	< 0.037 U

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

														3,3-Dichlorobenzidine	**2,4-Dichlorophenol**	**Diethylphthalate**	**2,4-Dimethylphenol**	**Dimethylphthalate**	**Di-n-butyl phthalate**	**Di-n-octyl phthalate**	**4,6-Dinitro-2-methylphenol**	**2,6-Dinitrotoluene**	**2,4-Dinitrophenol**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																							
Restricted - Residential																							
Protection of Groundwater																							
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated		< 0.06 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.09 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.19 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated		< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated		< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U	< 0.2 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated		< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U	< 0.19 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated		< 0.056 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated		< 0.061 U	< 0.026 UT	< 0.013 UT	< 0.048 UT	< 0.092 UT	< 0.015 UT	< 0.021 U	< 0.16 UT	< 0.029 UT	< 0.2 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated		< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.18 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated		< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated		< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U	< 0.19 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated		< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated		< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated		< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U	< 0.17 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated		< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		< 0.054 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated		< 0.051 U	< 0.022 U	< 0.011 U	< 0.04 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.024 U	< 0.17 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated		< 0.052 U	< 0.022 U	< 0.011 U	< 0.041 U	< 0.077 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U	< 0.17 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated		< 0.055 U	< 0.023 U	< 0.012 U	< 0.043 U	< 0.082 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U	< 0.18 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated		< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated		< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated		< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 UT	< 0.13 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.13 U	< 2.1 U
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated		< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 UT	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated		< 0.041 U	< 0.0078 U	< 0.042 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated		< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated		< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated		< 1.9 U	< 0.15 U	< 0.48 U	< 0.12 U	< 0.072 U	< 0.87 U	< 1.2 U	< 3.4 U	< 0.12 U	< 5.4 U
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated		< 0.37 U	< 0.03 U	< 0.095 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U	< 1.1 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated		< 0.36 U	< 0.03 U	< 0.094 U	< 0.024 U	< 0.014 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U	< 1.1 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated		< 0.39 U	< 0.033 U	< 0.1 U	< 0.026 U	< 0.015 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U	< 1.1 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated		< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated		< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated		< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.45 U	< 0.85 U	< 0.24 U	< 0.71 U	< 0.16 U	< 2.5 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated		< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U	< 2.1 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated		< 0.04 U	< 0.0077 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.46 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.3 J	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated		< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	0.28 J	< 0.22 U	< 0.65 U	< 0.15 U	< 2.3 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated		< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U	< 2.4 U
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated		< 0.041 U	< 0.0078 U	< 0.043 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated		< 0.043 U	< 0.0082 U	< 0.044 U	< 0.064 U	< 0.044 U	< 0.051 U	< 0.043 U	< 0.16 U	< 0.042 U	< 0.48 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated		< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated		< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U	< 2.4 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated		< 0.041 U	< 0.0078 U	< 0.042 U	< 0.061 U	< 0.042 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated		< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.43 U	< 0.8 U	< 0.22 U	< 0.67 U	< 0.15 U	< 2.4 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.4 U	< 0.75 U	< 0.21 U	< 0.62 U	< 0.14 U	< 2.2 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.44 U	< 0.83 U	< 0.23 U	< 0.69 U	< 0.16 U	< 2.5 U
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated		< 0.99 U	< 0.082 U	< 0.26 U	< 0.066 U	< 0.038 U	< 0.46 U	< 0.62 U	< 1.8 U	< 0.065 U	< 2.8 R
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated		< 0.044 U	< 0.0083 U	0.077 J	< 0.064 U	< 0.045 U	< 0.052 U	< 0.043 U	< 0.17 U	< 0.042 U	< 0.49 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated		< 0.045 U	< 0.0085 U	< 0.046 U	< 0.066 U	< 0.046 U	< 0.053 U	< 0.045 U	< 0.17 U	< 0.044 U	< 0.5 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated		< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U	< 2.2 U
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated		< 1.6 U	< 0.14 U	< 0.43 U	< 0.11 U	< 0.064 U	< 0.77 U	< 1 U	< 3 U	< 0.11 U	< 4.8 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.0081 U	< 0.034 U	< 0.063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated		< 0.15 U	< 0.03 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.043 U	< 0.68 U	< 0.025 U	< 0.74 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.015 U	< 0.034 U	< 0.11 U	< 0.08 U	< 0.034 U	< 0.077 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.007 U	< 0.034 U	< 0.054 U	< 0.038 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.0074 U	< 0.034 U	< 0.058 U	< 0.04 U	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated		< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.025 U	< 0.028 U	< 0.042 U	< 0.65 U	< 0.024 U	< 0.71 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.11 U	< 0.034 U	< 0.47 U	< 0.55 U	< 0.034 U	< 0.81 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated		< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.44 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.043 U		< 0.035 U		1	0.063 J	< 0.019 U	< 0.0084 U	< 0.035 U	< 0.014 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.038 U		< 0.031 U		0.12 J	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.043 U		< 0.035 U		6.6	0.73	< 0.019 U	< 0.0086 U	< 0.035 U	< 0.014 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.04 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U	< 0.013 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.043 UT		< 0.035 U		0.32 JT	< 0.012 UT	< 0.019 UT	< 0.0086 UT	< 0.035 UT	< 0.014 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.04 U		< 0.032 U		0.038 J	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.039 U		< 0.032 U		1.4	0.096 J	< 0.017 U	< 0.0078 U	< 0.032 U	< 0.013 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.041 U		< 0.033 U		0.61	0.033 J	< 0.018 U	< 0.0081 U	< 0.033 U	< 0.013 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.038 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.036 U		< 0.029 U		0.073 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.037 U		< 0.03 U		0.42	0.019 J	< 0.016 U	< 0.0074 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.039 U		< 0.031 U		< 0.013 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U	< 0.012 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.036 U		< 0.03 U		0.043 J	< 0.0099 U	< 0.016 U	< 0.0072 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.037 U		< 0.03 U		11	1.9	< 0.016 U	< 0.0073 U	< 0.03 U	< 0.012 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.039 U		< 0.032 U		0.45	0.025 J	< 0.017 U	< 0.0077 U	< 0.032 U	< 0.012 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			0.63	0.029 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			0.38	0.021 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.22 U	< 0.11 U			0.47	0.014 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.2 U	< 0.1 U			0.046 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 UT	< 0.12 U
Northern Athletic Field	A8P3A1-S13	SSHS-IRM5A2-A8P3A1-S13-20231130	SSHS-IRM5A2-A8P3A1-S13	11/30/2023	--	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.21 U		< 0.11 U		0.9	0.034 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8P3A1-S17	SSHS-IRM5A2-A8P3A1-S17-20231130	SSHS-IRM5A2-A8P3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.2 U		< 0.11 U		1.3	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U	< 0.12 U
Northern Athletic Field	A8P3A1-S21	SSHS-IRM5A2-A8P3A1-S21-20231130	SSHS-IRM5A2-A8P3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.21 U		< 0.11 U		< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8P3A1-S22	SSHS-IRM5A2-A8P3A1-S22-20231130	SSHS-IRM5A2-A8P3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	< 0.21 U		< 0.11 U		0.055 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8P3A1-S29	SSHS-IRM5A2-A8P3A1-S29-20231208	SSHS-IRM5A2-A8P3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8P3A1-S31	SSHS-IRM5A2-A8P3A1-S31-20231208	SSHS-IRM5A2-A8P3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	< 0.21 U		< 0.11 U		2.1	0.042 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8P3A1-S32	SSHS-IRM5A2-A8P3A1-S32-20231208	SSHS-IRM5A2-A8P3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	< 0.21 U		< 0.11 U		0.018 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Northern Athletic Field	A8P3A1-S34	SSHS-IRM5A2-A8P3A1-S34-20231214	SSHS-IRM5A2-A8P3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Northern Athletic Field	A8P3A1-S35	SSHS-IRM5A2-A8P3A1-S35-20231214	SSHS-IRM5A2-A8P3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	< 0.21 U		< 0.11 U		< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.044 U	< 0.0083 U	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0097 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0077 U	< 0.0095 U	< 0.0076 U	< 0.008 U	< 0.039 U	< 0.026 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15 EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	< 0.099 U			< 0.62 U	0.71	< 0.078 U	< 0.14 U	< 0.12 U	< 0.1 U	< 0.1 U
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15 SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated	< 0.019 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.02 U	< 0.02 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15 SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated	< 0.019 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.02 U	< 0.02 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15 SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated	< 0.021 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.022 U	< 0.022 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.24 U		< 0.26 U		< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.11 U	< 0.14 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.044 U	< 0.0082 U	< 0.01 U	< 0.0081 U	< 0.0086 U	< 0.041 U	< 0.027 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.23 U	< 0.12 UT			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U	< 0.14 U
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.045 U	0.14	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.033 U			< 0.047 U	0.16	< 0.011 U	< 0.0087 U	< 0.0091 U	< 0.044 U	< 0.029 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U	< 0.14 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.031 U			< 0.044 U	0.065 J	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.23 U		< 0.24 U		0.024 J	< 0.015 U	< 0.028 U	< 0.023 U	< 0.1 U	< 0.14 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.21 U		< 0.23 U		0.38	0.029 J	< 0.026 U	< 0.021 U	< 0.097 U	< 0.13 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.24 U		< 0.25 U		0.15	< 0.016 U	< 0.029 U	< 0.023 U	< 0.11 U	< 0.14 U
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	< 0.053 U			< 0.33 U	0.37	< 0.042 U	< 0.076 U	< 0.062 U	< 0.054 U	< 0.055 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.033 U			< 0.047 U	0.077 J	< 0.011 U	< 0.0088 U	< 0.0092 U	< 0.044 U	< 0.03 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.034 U			< 0.048 U	0.11	< 0.011 U	< 0.009 U	< 0.0095 U	< 0.046 U	< 0.03 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U	< 0.12 U
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	< 0.088 U			< 0.55 U	4.3	0.24 J	< 0.13 U	< 0.1 U	< 0.09 U	< 0.091 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated	< 0.032 U			< 0.046 U	1.3	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	< 0.049 U			< 0.055 U	8.7	0.3	< 0.03 U	< 0.023 U	< 0.031 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated	< 0.059 U			< 0.084 U	20	0.45	< 0.016 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated	< 0.028 U			< 0.04 U	1.6	0.036 J	< 0.0074 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.03 U			< 0.042 U	0.57	0.027 J	< 0.0079 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.053 U	< 0.028 U	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.034 U	2.3	0.08	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.83 U			< 0.43 U	0.26 J	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0098 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U

DRAFT

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	0.84	< 0.015 U		< 0.11 U	0.26 J	< 0.025 U	0.29 J	< 0.03 U	< 0.094 U	< 0.045 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	0.067	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	0.012 J	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	2.8	< 0.015 U		< 0.12 U	0.46	0.029 J	0.74	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	0.025 J	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.015 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0065 U	< 0.028 U	< 0.089 U	< 0.043 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	0.15 T	< 0.015 UT		< 0.12 UT	0.014 JT	< 0.025 UT	0.034 JT	< 0.031 U	< 0.096 U	< 0.046 U
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U	< 0.043 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	0.8	< 0.014 U		< 0.11 U	0.13 J	< 0.023 U	0.15 J	< 0.028 U	< 0.087 U	< 0.042 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	0.38	< 0.014 U		< 0.11 U	0.071 J	< 0.024 U	0.073 J	< 0.029 U	< 0.09 U	< 0.044 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	0.03 J	< 0.013 U		< 0.097 U	< 0.0094 U	< 0.021 U	0.0079 J	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	0.22	< 0.013 U		< 0.1 U	0.034 J	< 0.022 U	0.043 J	< 0.026 U	< 0.082 U	< 0.04 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U	< 0.041 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U	< 0.04 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U	< 0.041 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	0.024 J	< 0.013 U		< 0.098 U	0.0096 J	< 0.021 U	0.022 J	< 0.026 U	< 0.08 U	< 0.039 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	4.1 T	0.016 J		< 0.099 U	0.7	0.039 J	1.5	< 0.026 U	< 0.081 U	< 0.039 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	0.21	< 0.014 U		< 0.1 U	0.025 J	< 0.023 U	0.033 J	< 0.028 U	< 0.086 U	< 0.042 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	0.24	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.028 J	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.034 U	< 0.097 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	0.16	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	0.022 J	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	0.18	< 0.1 U		< 0.14 U	0.022 J	< 0.11 U	0.069 J	< 0.16 U	< 0.092 U	< 0.13 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U	< 0.12 U
Northern Athletic Field	A8PH3AI-S13	SSHS-IRM5A2-A8PH3AI-S13-20231130	SSHS-IRM5A2-A8PH3AI-S13	11/30/2023	--	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.21	< 0.1 U		< 0.13 U	0.13	< 0.1 U	0.15	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S17	SSHS-IRM5A2-A8PH3AI-S17-20231130	SSHS-IRM5A2-A8PH3AI-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	0.1	< 0.097 U		< 0.13 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S21	SSHS-IRM5A2-A8PH3AI-S21-20231130	SSHS-IRM5A2-A8PH3AI-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S22	SSHS-IRM5A2-A8PH3AI-S22-20231130	SSHS-IRM5A2-A8PH3AI-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S29	SSHS-IRM5A2-A8PH3AI-S29-20231208	SSHS-IRM5A2-A8PH3AI-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S31	SSHS-IRM5A2-A8PH3AI-S31-20231208	SSHS-IRM5A2-A8PH3AI-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	0.091	< 0.1 U		< 0.13 U	0.017 J	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S32	SSHS-IRM5A2-A8PH3AI-S32-20231208	SSHS-IRM5A2-A8PH3AI-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S34	SSHS-IRM5A2-A8PH3AI-S34-20231214	SSHS-IRM5A2-A8PH3AI-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Northern Athletic Field	A8PH3AI-S35	SSHS-IRM5A2-A8PH3AI-S35-20231214	SSHS-IRM5A2-A8PH3AI-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U	< 0.13 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.008 U	< 0.027 U		< 0.029 U	< 0.007 U	< 0.038 U	< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.0076 U	< 0.026 U		< 0.028 U	< 0.0067 U	< 0.036 U	< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.0074 U	< 0.025 U		< 0.027 U	< 0.0065 U	< 0.035 U	< 0.0062 U	< 0.16 U	< 0.15 U	< 0.15 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15 EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	0.45	< 0.57 U		< 0.1 U	< 0.096 U	< 0.59 U	< 0.078 U	< 0.91 U	< 0.51 U	< 0.097 U
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15 SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated	< 0.016 U	< 0.11 U		< 0.02 U	0.019 J	< 0.11 U	0.028 J	< 0.18 U	< 0.1 U	< 0.019 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15 SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated	< 0.016 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.019 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15 SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated	< 0.017 U	< 0.12 U		< 0.022 U	< 0.02 U	< 0.12 U	0.017 J	< 0.19 U	< 0.11 U	< 0.021 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.041 U	< 0.12 U		< 0.15 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U	< 0.15 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U	< 0.13 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.0079 U	< 0.027 U		< 0.029 U	< 0.0069 U	< 0.037 U	< 0.0066 U	< 0.17 U	< 0.16 U	< 0.15 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U	< 0.14 U
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	0.046 J	< 0.027 U		< 0.029 U	0.2	< 0.038 U	0.1	< 0.17 U	< 0.16 U	< 0.16 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	0.065 J	< 0.028 U		< 0.031 U	0.37	< 0.04 U	0.14	< 0.18 U	< 0.17 U	< 0.16 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U	< 0.15 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	0.025 J	< 0.027 U		< 0.029 U	0.078	< 0.038 U	0.044 J	< 0.17 U	< 0.16 U	< 0.16 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.038 U	< 0.11 U		< 0.14 U	0.045 J	< 0.11 U	0.03 J	< 0.18 U	< 0.098 U	< 0.14 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	0.13	< 0.1 U		< 0.13 U	0.025 J	< 0.11 U	0.072	< 0.16 U	< 0.091 U	< 0.13 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	0.059 J	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	0.032 J	< 0.18 U	< 0.1 U	< 0.15 U
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	0.16 J	< 0.3 U		< 0.054 U	< 0.051 U	< 0.31 U	0.071 J	< 0.48 U	< 0.27 U	< 0.051 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	0.025 J	< 0.029 U		< 0.031 U	0.25	< 0.04 U	0.11	< 0.18 U	< 0.17 U	< 0.17 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	0.04 J	< 0.03 U		< 0.032 U	0.056 J	< 0.041 U	0.045 J	< 0.19 U	< 0.17 U	< 0.17 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.035 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U	< 0.13 U
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	1.2	< 0.51 U		< 0.09 U	0.2 J	< 0.52 U	0.21 J	< 0.81 U	< 0.45 U	< 0.086 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated	0.46	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.061 J	< 0.034 U	< 0.034 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	3.2	< 0.032 U	0.11 J	< 0.02 U	0.13		0.59	< 0.13 U	< 0.11 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated	5.8	< 0.034 U	0.13 J	< 0.034 U	0.18		0.84	< 0.034 U	< 0.034 U	< 0.3 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated	0.41	< 0.034 U	< 0.034 U	< 0.034 U	0.014 J		0.072	< 0.034 U	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	0.19	< 0.034 U	< 0.034 U	< 0.034 U	0.037 J		0.078	< 0.034 U	< 0.034 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated	< 0.027 U	< 0.031 U	< 0.031 U	< 0.031 U	< 0.02 U	< 0.027 U	< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	0.36	< 0.034 U	< 0.034 U	< 0.034 U	0.082		0.24	< 0.034 U	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	0.17 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.071 J	< 0.034 U	< 0.034 U	< 0.52 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.022 U	< 0.04 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	0.51	< 0.015 U	1.3
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	0.062 J	< 0.013 U	0.15 J
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	5	0.023 J	6.7
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.0075 J	< 0.014 U	< 0.0095 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.021 U	< 0.037 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U	< 0.0093 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.022 UT	< 0.04 UT	< 0.066 U		< 0.029 UT	< 0.033 UT	< 0.083 U	0.17 JT	< 0.015 UT	0.28 JT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.021 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.031 U	< 0.076 U	0.014 J	< 0.014 U	0.058 J
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.02 U	< 0.037 U	< 0.059 U		< 0.027 U	< 0.03 U	< 0.075 U	0.66	< 0.013 U	1.8
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	0.36 J	< 0.014 U	0.8
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.024 U	< 0.028 U	< 0.069 U	0.064 J	< 0.012 U	0.079 J
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.019 U	< 0.035 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.071 U	0.2 J	< 0.013 U	0.56
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U	< 0.0088 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U	< 0.0087 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.074 U	< 0.0063 U	< 0.013 U	< 0.0089 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.019 U	< 0.034 U	< 0.055 U		< 0.025 U	< 0.028 U	< 0.069 U	0.026 J	< 0.012 U	0.057 J
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.019 U	< 0.034 U	< 0.056 U		< 0.025 U	< 0.028 U	< 0.07 U	11	< 0.013 U	11
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.02 U	< 0.036 U	0.064 J		< 0.026 U	< 0.03 U	< 0.074 U	0.24 J	< 0.013 U	0.51
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.42	< 0.11 U	0.79
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.29	< 0.11 U	0.49
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.2	< 0.11 U	0.55
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U	0.057 J
Northern Athletic Field	A8P13A1-S13	SSHS-IRM5A2-A8P13A1-S13-20231130	SSHS-IRM5A2-A8P13A1-S13	11/30/2023	--	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	0.49	< 0.11 U	0.79
Northern Athletic Field	A8P13A1-S17	SSHS-IRM5A2-A8P13A1-S17-20231130	SSHS-IRM5A2-A8P13A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.12 U	< 0.12 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.65	< 0.1 U	1.1
Northern Athletic Field	A8P13A1-S21	SSHS-IRM5A2-A8P13A1-S21-20231130	SSHS-IRM5A2-A8P13A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Northern Athletic Field	A8P13A1-S22	SSHS-IRM5A2-A8P13A1-S22-20231130	SSHS-IRM5A2-A8P13A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.033 J	< 0.11 U	0.057 J
Northern Athletic Field	A8P13A1-S29	SSHS-IRM5A2-A8P13A1-S29-20231208	SSHS-IRM5A2-A8P13A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	0.017 J
Northern Athletic Field	A8P13A1-S31	SSHS-IRM5A2-A8P13A1-S31-20231208	SSHS-IRM5A2-A8P13A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.92	< 0.11 U	1.6
Northern Athletic Field	A8P13A1-S32	SSHS-IRM5A2-A8P13A1-S32-20231208	SSHS-IRM5A2-A8P13A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8P13A1-S34	SSHS-IRM5A2-A8P13A1-S34-20231214	SSHS-IRM5A2-A8P13A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Northern Athletic Field	A8P13A1-S35	SSHS-IRM5A2-A8P13A1-S35-20231214	SSHS-IRM5A2-A8P13A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U	< 0.017 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0092 U	< 0.0078 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0075 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0085 U	< 0.0073 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15 EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated	< 0.73 U	< 0.11 U	< 1.4 U		< 0.14 U	< 0.66 U	< 3.2 U	0.29 J	< 0.6 U	0.62
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated	< 0.14 U	< 0.022 U	< 0.27 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated	< 0.14 U	< 0.022 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	< 0.019 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated	< 0.15 U	< 0.024 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U	< 0.02 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U	< 0.017 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U	0.26
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U	< 0.018 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U	< 0.016 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.032 U	< 0.042 U	< 0.14 U		< 0.009 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U	< 0.017 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	0.02 J	< 0.11 U	< 0.018 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.036 J	< 0.12 U	< 0.018 U
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	0.4 J	< 0.0092 U	0.11
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0095 U	< 0.038 U	< 0.036 U	0.77 J	< 0.0096 U	0.14
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.029 J	< 0.11 U	< 0.017 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U	0.019 J
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	0.17	< 0.0092 U	0.056 J
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.034 J	< 0.12 U	0.041 J
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.13	< 0.11 U	0.37
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.065 J	< 0.12 U	0.14
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated	< 0.39 U	< 0.061 U	< 0.74 U		< 0.072 U	< 0.35 U	< 1.7 UJ	0.28	< 0.32 U	0.46
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0097 U	< 0.038 U	< 0.037 U	0.44	< 0.0097 U	0.089
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.035 U	< 0.047 U	< 0.15 U		< 0.0099 U	< 0.039 U	< 0.038 U	0.1	< 0.01 U	0.097
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U	< 0.016 U
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated	< 0.65 U	< 0.1 U	< 1.2 U		< 0.12 U	< 0.59 U	< 2.8 U	1	< 0.54 U	3.4
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.15 U		< 0.034 U	< 0.034 U	< 0.034 U	0.65	< 0.0095 U	0.95 J
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated	< 0.028 U	< 0.027 U	< 0.38 U		< 0.025 U	< 0.058 U	< 0.69 U	7.9	< 0.05 U	11
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	11	< 0.017 U	14
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.13 U		< 0.034 U	< 0.034 U	< 0.034 U	0.82	< 0.0082 U	1.1
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.14 U		< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.0087 U	0.4
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.67 U	< 0.03 U	< 0.048 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.38	< 0.12 U	1.8
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.098 U		< 0.034 U	< 0.034 U	< 0.034 U	0.13 J	< 0.42 U	0.31 J
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0075 U

DRAFT

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated		< 0.012 U	< 0.027 U	< 0.04 U	< 0.051 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated		< 0.013 UT	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated		< 0.011 U	< 0.023 U	< 0.034 U	< 0.043 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		< 0.011 U	< 0.024 U	< 0.037 U	< 0.046 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated		< 0.011 U	< 0.023 U	< 0.035 U	< 0.044 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated		< 0.086 U	< 0.83 U	< 0.14 U	< 0.11 U
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated		< 0.029 U	< 0.025 U	< 0.041 U	< 0.057 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated		< 0.03 U	< 0.025 U	< 0.042 U	< 0.058 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated		< 0.031 U	< 0.026 U	< 0.043 U	< 0.061 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated		< 0.046 U	< 0.44 UJ	< 0.076 U	< 0.058 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated		< 0.031 U	< 0.026 U	< 0.044 U	< 0.062 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated		< 0.032 U	< 0.027 U	< 0.045 U	< 0.063 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated		< 0.076 U	< 0.74 U	< 0.13 U	< 0.097 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.029 U	< 0.035 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.028 U	< 0.034 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAHS**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.035 U	< 0.032 U	< 0.053 UJ	< 0.0089 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated			ND	< 0.0071 U	< 0.0084 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0092 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	< 0.0089 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.037 U	< 0.033 U	< 0.056 U	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated			ND	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0095 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated			ND	< 0.0071 U	< 0.0085 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0093 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated			ND	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0075 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0096 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated			ND	< 0.0067 U	< 0.008 U	< 0.029 U	< 0.0068 U	< 0.034 U	< 0.031 U	< 0.052 U	< 0.0088 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated			ND	< 0.007 U	< 0.0084 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 UJ	< 0.0092 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated			1.415	< 0.024 U	< 0.024 U	< 0.024 U	0.04 J	< 0.048 U	< 0.028 U	< 0.023 U	0.13
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated			78.65	0.74 J	1.6 J	< 0.083 U	2.9 J	< 0.67 U	0.84 J	< 0.19 U	5.7 J
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated			7.28	0.038 J	0.13 J	< 0.02 U	0.29 J	< 0.16 U	0.052 J	< 0.045 U	0.48 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	940 J		129.91	0.71	2.3	< 0.083 U	4.3	< 0.67 U	0.39 J	< 0.19 UJ	12
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated			27.7	0.43	0.22	< 0.027 U	0.85	< 0.22 U	0.09 J	< 0.062 U	3.3
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated			7.534	0.033 J	0.12	< 0.034 U	0.27	< 0.18 U	< 0.034 U	< 0.05 U	0.61
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated			3.06	< 0.034 U	0.094 J	< 0.034 U	< 0.091 UJ	< 0.77 U	< 0.034 U	< 0.22 U	0.24 J
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated			3.303	< 0.034 U	0.062 J	< 0.034 U	0.12	< 0.17 U	< 0.034 U	< 0.048 U	0.28
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated			3.656	< 0.034 U	0.11 J	< 0.034 U	0.096 J	< 0.78 U	< 0.034 U	< 0.22 U	0.3 J
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.025 U	< 0.025 U	< 0.027 U	< 0.05 U	< 0.029 U	< 0.024 U	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated			1.946	< 0.034 U	0.063 J	< 0.034 U	0.055 J	< 0.15 U	< 0.034 U	< 0.044 U	0.16
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated			19.65	< 0.034 U	0.5 J	< 0.034 U	0.64	< 1.3 U	< 0.034 U	< 0.36 U	1.7
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated			2.217	< 0.021 U	0.036 J	< 0.13 U	0.032 J	< 0.16 U	< 0.13 U	< 0.045 U	0.21
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated			5.564	0.027 J	0.11	< 0.13 U	0.13	< 0.16 U	< 0.13 U	< 0.044 U	0.48
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated			0.041	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0084 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0092 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated			ND	< 0.0075 U	< 0.0089 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.035 U	< 0.058 U	< 0.0098 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated			0.051	< 0.0076 U	< 0.009 U	< 0.032 U	< 0.0077 U	< 0.038 U	< 0.035 U	< 0.059 U	< 0.0099 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated			ND	< 0.0079 U	< 0.0094 U	< 0.034 U	< 0.008 U	< 0.04 U	< 0.037 U	< 0.062 U	< 0.01 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated			ND	< 0.0077 U	< 0.0092 U	< 0.033 U	< 0.0078 U	< 0.039 U	< 0.036 U	< 0.06 U	< 0.01 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated			ND	< 0.0074 U	< 0.0088 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.034 U	< 0.058 U	< 0.0097 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated			ND	< 0.0076 U	< 0.009 U	< 0.032 U	< 0.0077 U	< 0.038 U	< 0.035 U	< 0.059 U	< 0.0099 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated			ND	< 0.0074 U	< 0.0088 U	< 0.032 U	< 0.0076 U	< 0.038 U	< 0.034 U	< 0.058 U	< 0.0097 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated			8.138	0.013 J	0.17	< 0.03 U	0.26	< 0.036 U	< 0.033 U	< 0.055 U	0.7
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.0091 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated			ND	< 0.0071 U	< 0.0085 U	< 0.03 U	< 0.0072 U	< 0.036 U	< 0.033 U	< 0.055 UJ	< 0.0093 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated			0.045	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 U	< 0.0095 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated			0.126	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 UJ	< 0.0095 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated			0.995	< 0.025 U	< 0.025 U	< 0.025 U	0.033 J	< 0.051 U	< 0.029 U	< 0.024 U	0.09
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated			0.257	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	0.05 J	0.043 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated			0.214	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	0.032 J
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated			1.122	< 0.034 U	0.021 J	< 0.034 U	0.04 J	< 0.17 U	< 0.034 U	< 0.047 U	0.1
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated			1.556	< 0.034 U	0.055 J	< 0.034 U	0.052 J	< 0.31 U	< 0.034 U	< 0.088 U	0.13 J
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.0069 U	< 0.034 U	< 0.032 U	< 0.053 U	< 0.0089 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.0091 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated			ND	< 0.0072 U	< 0.0085 U	< 0.031 U	< 0.0073 U	< 0.036 U	< 0.033 U	< 0.056 U	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.033 U	< 0.055 U	< 0.0091 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated			ND	< 0.007 U	< 0.0083 U	< 0.03 U	< 0.0071 U	< 0.035 U	< 0.032 U	< 0.054 U	< 0.0091 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated			ND	< 0.007 U	< 0.0084 U	< 0.03 U	< 0.0071 U	< 0.036 U	< 0.033 U	< 0.055 U	< 0.0091 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated			ND	< 0.0073 U	< 0.0087 U	< 0.031 U	< 0.0074 U	< 0.037 U	< 0.034 U	< 0.057 UJ	< 0.0095 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated			ND	< 0.0068 U	< 0.0081 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.053 U	< 0.0089 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated			ND	< 0.0069 U	< 0.0082 U	< 0.029 U	< 0.007 U	< 0.035 U	< 0.032 U	< 0.054 UJ	< 0.009 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated			ND	< 0.0072 U	< 0.0086 U	< 0.031 U	< 0.0073 U	< 0.037 U	< 0.033 U	< 0.056 UJ	< 0.0094 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.024 U	< 0.026 U	< 0.049 U	< 0.028 U	< 0.023 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated			1.247	< 0.034 U	0.021 J	< 0.034 U	0.038 J	< 0.16 U	< 0.034 U	< 0.045 U	0.098
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated			0.58	< 0.034 U	< 0.065 U	< 0.034 U	< 0.077 U	< 0.65 U	< 0.034 U	< 0.18 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated			2.011	< 0.024 U	0.032 J	< 0.024 U	0.076	< 0.049 U	< 0.028 U	< 0.023 U	0.18

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether	Butylbenzyl phthalate
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100						
Restricted - Residential													1	1	3.9	100						
Protection of Groundwater													22	1.7	1.7	1000						
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.023 U	< 0.0095 U	< 0.0077 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0099 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.062 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.007 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0094 U	< 0.0075 U	< 0.056 U	< 0.03 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.0073 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	0.11	0.13	0.07	0.063 J	< 0.02 U	< 0.021 U	< 0.023 U	< 0.23 U	< 0.033 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	4.8 J	5.4 J	1.4 J	2.8 J	< 0.073 U	< 0.055 U	< 0.11 U	< 1.6 U	< 0.11 U	< 1 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	0.42 J	0.52 J	0.2 J	0.38 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U	< 0.25 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	8.6	11	4.1	6.5	< 0.073 U	< 0.055 U	< 0.11 U	< 1.6 U	< 0.11 U	< 1 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	1.1	1.2	0.97	1	< 0.024 U	< 0.018 U	< 0.037 U	< 0.53 U	< 0.035 U	< 0.34 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	0.44	0.61	0.23	0.38	< 0.034 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	0.27 J	0.35	0.11 J	0.34 J	< 0.64 U	< 0.064 U	< 0.13 U	< 1.9 U	< 0.75 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	0.21	0.3	0.099	0.17	< 0.034 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	0.3 J	0.42	0.13 J	0.38	< 0.65 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.76 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	< 0.03 U	< 0.031 U	< 0.025 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.024 U	< 0.24 U	< 0.034 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	0.16	0.2	0.092	0.16	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	1.5	2	0.69	1.6	< 1.1 U	< 0.11 U	< 0.21 U	< 3.1 U	< 1.2 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	0.21	0.22	0.11	0.17	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U	< 0.25 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	0.47	0.64	0.19	0.48	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U	< 0.24 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U	< 0.23 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 UT	< 0.15 U	< 0.24 UT
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0073 U	< 0.012 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0078 U	< 0.012 U	< 0.016 U	< 0.0078 U	< 0.026 U	< 0.01 U	< 0.0084 U	< 0.063 U	< 0.034 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0079 U	< 0.012 U	< 0.016 U	< 0.0078 U	< 0.026 U	< 0.011 U	< 0.0085 U	< 0.064 U	< 0.034 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0082 U	< 0.013 U	< 0.017 U	< 0.0082 U	< 0.027 U	< 0.011 U	< 0.0089 U	< 0.066 U	< 0.036 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.008 U	< 0.013 U	< 0.016 U	< 0.008 U	< 0.026 U	< 0.011 U	< 0.0087 U	< 0.065 U	< 0.035 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0077 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.034 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0079 U	< 0.012 U	< 0.016 U	< 0.0078 U	< 0.026 U	< 0.011 U	< 0.0085 U	< 0.064 U	< 0.034 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0077 U	< 0.012 U	< 0.016 U	< 0.0077 U	< 0.025 U	< 0.01 U	< 0.0083 U	< 0.062 U	< 0.034 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	0.75	0.82	0.34	0.79	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0074 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.024 U	< 0.0099 U	< 0.008 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	0.079	0.099	0.036 J	0.059 J	< 0.021 U	< 0.022 U	< 0.024 U	< 0.25 U	< 0.035 U	< 0.27 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	0.025 J	0.029 J	< 0.022 U	0.021 J	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U	< 0.25 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	0.02 J	0.03 J	< 0.023 U	0.023 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	0.094	0.1	0.053 J	0.068 J	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	0.11 J	0.17	0.052 J	0.18	< 0.26 U	< 0.026 U	< 0.052 U	< 0.75 U	< 0.3 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.007 U	< 0.023 U	< 0.0095 U	< 0.0076 U	< 0.057 U	< 0.031 U	< 0.048 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0097 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0074 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.06 U	< 0.032 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0072 U	< 0.024 U	< 0.0098 U	< 0.0078 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.0073 U	< 0.011 U	< 0.015 U	< 0.0073 U	< 0.024 U	< 0.0098 U	< 0.0079 U	< 0.059 U	< 0.032 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0076 U	< 0.012 U	< 0.015 U	< 0.0076 U	< 0.025 U	< 0.01 U	< 0.0082 U	< 0.061 U	< 0.033 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.0071 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.023 U	< 0.0095 U	< 0.0077 U	< 0.057 U	< 0.031 U	< 0.049 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0072 U	< 0.011 U	< 0.014 U	< 0.0071 U	< 0.024 U	< 0.0096 U	< 0.0077 U	< 0.058 U	< 0.031 U	< 0.049 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0075 U	< 0.012 U	< 0.015 U	< 0.0075 U	< 0.025 U	< 0.01 U	< 0.0081 U	< 0.061 U	< 0.033 U	< 0.051 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	< 0.029 U	< 0.031 U	< 0.025 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	0.076	0.11	0.043 J	0.062 J	< 0.034 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	0.13 J	< 0.089 U	0.13 J	< 0.54 U	< 0.054 U	< 0.11 U	< 1.6 U	< 0.63 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	0.15	0.18	0.079	0.093	< 0.02 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U	< 0.26 U

DRAFT

													Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene	Dibenzofuran
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33	7
Restricted - Residential																				3.9	0.33	59
Protection of Groundwater																				1	1000	210
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0083 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	< 0.0091 U	< 0.0085 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.031 U	< 0.035 U	< 0.008 U	< 0.031 U	< 0.042 U	< 0.0091 U	< 0.0085 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0083 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.26 U	< 0.0064 U	< 0.028 U	< 0.032 U	< 0.0073 U	< 0.029 U	< 0.039 U	< 0.0083 U	< 0.0078 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	0.1	< 0.029 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.99 U	0.8 J	< 0.051 U	< 0.072 U	< 0.07 U	< 0.071 U	< 0.092 U	5.6 J	0.71 J	3.2 J
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.24 U	0.086 J	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.55 J	0.092 J	0.15 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	< 0.99 U	1.2	< 0.051 U	< 0.072 U	< 0.07 U	< 0.071 U	< 0.092 U	11	1.3	2.6
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.33 U	< 0.023 U	< 0.017 U	< 0.024 U	< 0.023 U	< 0.023 U	< 0.03 U	5.3	0.25	0.58
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.26 U	0.087	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.54	0.091	0.15 J
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 1.1 U	< 0.034 U	< 0.46 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24 J	< 0.034 U	< 0.65 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.25 U	0.031 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 1.2 U	< 0.034 U	< 0.47 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.28 J	< 0.034 U	< 0.66 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.031 U	< 0.02 U	< 0.038 U	< 0.024 U	< 0.026 U	< 0.026 U	< 0.028 U	< 0.03 U	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.23 U	0.018 J	< 0.092 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 1.9 U	0.14 J	< 0.76 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	1.5	0.43 J	< 1.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	0.23	0.048 J	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.23 U	0.042 J	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.46	0.1	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.23 U	< 0.016 UT	< 0.092 U	< 0.12 UT	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0082 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.29 U	< 0.0072 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0093 U	< 0.0087 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.3 U	< 0.0073 U	< 0.032 U	< 0.036 U	< 0.0082 U	< 0.032 U	< 0.044 U	< 0.0094 U	< 0.0088 U	< 0.039 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.31 U	< 0.0076 U	< 0.033 U	< 0.038 U	< 0.0086 U	< 0.034 U	< 0.046 U	< 0.0098 U	< 0.0091 U	< 0.04 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.3 U	< 0.0074 U	< 0.032 U	< 0.037 U	< 0.0084 U	< 0.033 U	< 0.045 U	< 0.0095 U	< 0.0089 U	< 0.039 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.3 U	< 0.0072 U	< 0.031 U	< 0.036 U	< 0.0082 U	< 0.032 U	< 0.044 U	< 0.0094 U	< 0.0087 U	< 0.039 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.29 U	< 0.0071 U	< 0.031 U	< 0.036 U	< 0.0081 U	< 0.032 U	< 0.043 U	< 0.0092 U	< 0.0086 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.28 U	0.061 J	< 0.029 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	0.68	0.17	0.057 J
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0086 U	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0068 U	< 0.03 U	< 0.034 U	< 0.0077 U	< 0.03 U	< 0.041 U	< 0.0088 U	< 0.0082 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	< 0.009 U	< 0.0084 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	0.065 J	< 0.0084 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.031 U	< 0.021 U	< 0.039 U	< 0.024 U	< 0.026 U	< 0.026 U	0.069 J	< 0.03 U	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.04 J	< 0.017 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.24 U	< 0.018 U	< 0.013 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.032 J	< 0.017 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.25 U	< 0.034 U	< 0.099 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.098	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.46 U	< 0.034 U	< 0.19 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.12 J	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0084 U	< 0.0079 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0086 U	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0083 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.034 U	< 0.0078 U	< 0.031 U	< 0.041 U	< 0.0089 U	< 0.0083 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0087 U	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.27 U	< 0.0067 U	< 0.029 U	< 0.033 U	< 0.0076 U	< 0.03 U	< 0.04 U	< 0.0087 U	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.28 U	< 0.0067 U	< 0.029 U	< 0.034 U	< 0.0076 U	< 0.03 U	< 0.041 U	< 0.0087 U	< 0.0081 U	< 0.036 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.29 U	< 0.007 U	< 0.03 U	< 0.035 U	< 0.0079 U	< 0.031 U	< 0.042 U	< 0.009 U	< 0.0084 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.27 U	< 0.0065 U	< 0.028 U	< 0.033 U	< 0.0074 U	< 0.029 U	< 0.039 U	< 0.0085 U	< 0.0079 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.27 U	< 0.0066 U	< 0.029 U	< 0.033 U	< 0.0075 U	< 0.029 U	< 0.04 U	< 0.0085 U	< 0.008 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.28 U	< 0.0069 U	< 0.03 U	< 0.035 U	< 0.0078 U	< 0.031 U	< 0.042 U	< 0.0089 U	< 0.0084 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.026 U	< 0.025 U	< 0.028 U	< 0.029 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.24 U	0.017 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.1	< 0.034 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.97 U	< 0.034 U	< 0.39 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.16 U	< 0.034 U	< 0.55 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	< 0.17 U	0.042 J	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	0.14	< 0.029 U	< 0.028 U

												3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene	2,4-Dinitrophenol
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					
Restricted - Residential																					
Protection of Groundwater																					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.038 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.04 U	< 0.0076 U	< 0.042 U	< 0.059 U	< 0.041 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.04 U	< 0.0077 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.037 U	< 0.007 U	< 0.038 U	< 0.055 U	< 0.038 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.036 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.15 U	< 0.028 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.041 U	< 0.65 U	< 0.024 U	< 0.71 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 1.4 U	< 0.12 U	< 0.53 U	< 0.094 U	< 0.055 U	< 0.67 U	< 0.88 U	< 2.6 U	< 0.094 U	< 4.1 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U	< 0.98 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	< 1.4 U	< 0.12 U	< 0.53 U	< 0.095 U	< 0.055 U	< 0.67 U	< 0.89 U	< 2.6 UJ	< 0.094 U	< 4.1 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.47 U	< 0.039 U	< 0.18 U	< 0.031 U	< 0.018 U	< 0.22 U	< 0.29 U,*	< 0.86 U	< 0.031 U	< 1.3 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.031 U	< 0.034 U	< 0.14 U	< 0.16 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.14 U	< 0.034 U	< 0.59 U	< 0.69 U	< 0.034 U	< 1 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.14 U	< 0.034 U	< 0.6 U	< 0.7 U	< 0.034 U	< 1 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	< 0.15 U	< 0.029 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.043 U	< 0.67 U	< 0.025 U	< 0.73 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.97 U	< 1.1 U	< 0.034 U	< 1.7 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	0.19 J	< 0.21 U	< 0.63 U	< 0.14 U	< 2.3 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U	< 2.2 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.32 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.14 U	0.19 J	< 0.2 U	< 0.59 U	< 0.13 U	< 2.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 UT	< 0.14 U	0.17 JT	< 0.2 UT	< 0.6 UT	< 0.14 U	< 2.2 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.041 U	< 0.0078 U	< 0.043 U	< 0.061 U	< 0.043 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.042 U	< 0.0079 U	< 0.043 U	< 0.062 U	< 0.043 U	< 0.049 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.043 U	< 0.0082 U	< 0.045 U	< 0.064 U	< 0.045 U	< 0.051 U	< 0.043 U	< 0.17 U	< 0.042 U	< 0.49 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.042 U	< 0.008 U	< 0.044 U	< 0.063 U	< 0.044 U	< 0.05 U	< 0.042 U	< 0.16 U	< 0.041 U	< 0.48 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.041 U	< 0.0078 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.042 U	< 0.0079 U	< 0.043 U	< 0.061 U	< 0.043 U	< 0.049 U	< 0.041 U	< 0.16 U	< 0.041 U	< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.041 U	< 0.0077 U	< 0.042 U	< 0.06 U	< 0.042 U	< 0.048 U	< 0.041 U	< 0.16 U	< 0.04 U	< 0.46 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.039 U	< 0.0074 U	< 0.04 U	< 0.058 U	< 0.04 U	< 0.046 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	< 0.15 U	< 0.03 U	< 0.033 U	< 0.028 U	< 0.026 U	< 0.029 U	< 0.044 U	< 0.68 U	< 0.025 U	< 0.74 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.013 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U	< 1 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.014 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U	< 1 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.055 U	< 0.034 U	< 0.24 U	< 0.28 U	< 0.034 U	< 0.41 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.037 U	< 0.0071 U	< 0.039 U	< 0.055 U	< 0.039 U	< 0.044 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.045 U	< 0.038 U	< 0.15 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.039 U	< 0.0075 U	< 0.041 U	< 0.058 U	< 0.041 U	< 0.047 U	< 0.039 U	< 0.15 U	< 0.038 U	< 0.44 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.038 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.039 U	< 0.0073 U	< 0.04 U	< 0.057 U	< 0.04 U	< 0.046 U	< 0.038 U	< 0.15 U	< 0.038 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.04 U	< 0.0076 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.048 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.038 U	< 0.0071 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.037 U	< 0.14 U	< 0.037 U	< 0.42 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.038 U	< 0.0072 U	< 0.039 U	< 0.056 U	< 0.039 U	< 0.045 U	< 0.038 U	< 0.14 U	< 0.037 U	< 0.43 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.04 U	< 0.0075 U	< 0.041 U	< 0.059 U	< 0.041 U	< 0.047 U	< 0.04 U	< 0.15 U	< 0.039 U	< 0.45 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.025 U	< 0.028 U	< 0.042 U	< 0.66 U	< 0.025 U	< 0.72 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.11 U	< 0.034 U	< 0.5 U	< 0.59 U	< 0.034 U	< 0.86 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.042 U	< 0.65 U	< 0.024 U	< 0.71 U

													2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene	Hexachloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33			
Restricted - Residential														13	13	13	100	100	1.2			
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0094 U	< 0.0076 U	< 0.0079 U	< 0.038 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0097 U	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0081 U	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0097 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0082 U	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.028 U			< 0.04 U	< 0.0075 U	< 0.0092 U	< 0.0074 U	< 0.0078 U	< 0.038 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0078 U	< 0.0097 U	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.046 U			< 0.053 U	0.3	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.076 U			< 0.47 U	19 J	2.5 J	< 0.11 U	< 0.089 U	< 0.16 U	< 0.078 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.018 U			< 0.11 U	1.4 J	0.15 J	< 0.026 U	< 0.021 U	< 0.037 U	< 0.019 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	< 0.076 U			< 0.47 U	26	1.2	< 0.11 U	< 0.089 U	< 0.16 U	< 0.079 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.025 U			< 0.16 U	4.2	0.99	< 0.036 U	< 0.029 U	< 0.051 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.24 U			< 0.13 U	1.6	0.1	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 1 U			< 0.55 U	0.47	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.12 U	0.66	0.034 J	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 1.1 U			< 0.55 U	0.53	< 0.034 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	< 0.048 U			< 0.055 U	< 0.029 U	< 0.026 U	< 0.029 U	< 0.023 U	< 0.031 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.21 U			< 0.11 U	0.31	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 1.7 U			< 0.9 U	3.1	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.22 U	< 0.11 U			0.31	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.21 U	< 0.11 U			0.82	0.027 J	< 0.025 U	< 0.021 U	< 0.036 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.2 U	< 0.11 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.21 U	< 0.11 U			0.019 J	< 0.014 UT	< 0.025 U	< 0.02 U	< 0.036 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0078 U	< 0.0097 U	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.031 U			< 0.045 U	< 0.0083 U	< 0.01 U	< 0.0083 U	< 0.0087 U	< 0.042 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.032 U			< 0.045 U	0.02 J	< 0.01 U	< 0.0084 U	< 0.0088 U	< 0.043 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.033 U			< 0.047 U	< 0.0088 U	< 0.011 U	< 0.0087 U	< 0.0092 U	< 0.044 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.032 U			< 0.046 U	< 0.0086 U	< 0.011 U	< 0.0085 U	< 0.009 U	< 0.043 U	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0083 U	< 0.01 U	< 0.0082 U	< 0.0086 U	< 0.042 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.032 U			< 0.045 U	< 0.0084 U	< 0.01 U	< 0.0084 U	< 0.0088 U	< 0.042 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0083 U	< 0.01 U	< 0.0082 U	< 0.0086 U	< 0.042 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.03 U			< 0.042 U	1.2	0.035 J	< 0.0078 U	< 0.0082 U	< 0.04 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.042 U	< 0.0079 U	< 0.0098 U	< 0.0079 U	< 0.0083 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.031 U			< 0.044 U	0.017 J	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.043 U	0.015 J	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.041 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	< 0.049 U			< 0.055 U	0.15	< 0.026 U	< 0.03 U	< 0.023 U	< 0.031 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.018 U			< 0.12 U	0.031 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.019 U			< 0.12 U	0.028 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U	< 0.019 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.23 U			< 0.12 U	0.18	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.42 U			< 0.22 U	0.23	< 0.034 U	< 0.051 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0093 U	< 0.0075 U	< 0.0079 U	< 0.038 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0098 U	< 0.0079 U	< 0.0084 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0077 U	< 0.0081 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.029 U			< 0.042 U	< 0.0078 U	< 0.0096 U	< 0.0078 U	< 0.0082 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.031 U			< 0.044 U	< 0.0081 U	< 0.01 U	< 0.0081 U	< 0.0085 U	< 0.041 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.029 U			< 0.041 U	< 0.0076 U	< 0.0094 U	< 0.0076 U	< 0.008 U	< 0.038 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.029 U			< 0.041 U	< 0.0077 U	< 0.0095 U	< 0.0076 U	< 0.008 U	< 0.039 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.03 U			< 0.043 U	< 0.008 U	< 0.0099 U	< 0.008 U	< 0.0084 U	< 0.04 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.054 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.022 U	< 0.03 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.22 U			< 0.11 U	0.23	0.023 J	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.89 U			< 0.46 U	0.14 J	< 0.034 U	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	< 0.047 U			< 0.053 U	0.34	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U	< 0.025 U

													Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline	4-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12			
Restricted - Residential													0.5	100				100	100			
Protection of Groundwater													8.2	0.33				0.33	12			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.0076 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U		< 0.0065 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0078 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0068 U		< 0.0066 U	< 0.17 U	< 0.16 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0076 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0079 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0069 U		< 0.0066 U	< 0.17 U	< 0.16 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.0072 U	< 0.024 U	< 0.034 U	< 0.026 U	< 0.0063 U		< 0.006 U	< 0.16 U	< 0.14 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.0075 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	0.062 J	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U		< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	2.3 J	< 0.44 U	< 0.45 U	< 0.078 U	1.6 J		4.4 J	< 0.69 U	< 0.39 U	< 0.074 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	0.3 J	< 0.1 U	< 0.11 U	< 0.019 U	0.26 J		0.38 J	< 0.17 U	< 0.092 U	< 0.018 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	5.8	< 0.44 U		< 0.078 U	1	< 0.45 U	3.4	< 0.69 U	< 0.39 U	< 0.074 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	0.9	< 0.14 U		< 0.026 U	0.12	< 0.15 U	0.21	< 0.23 U	< 0.13 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	0.36	< 0.034 U	< 0.034 U	< 0.034 U	0.1		0.24	< 0.034 U	< 0.034 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	0.29 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.09 J	< 0.034 U	< 0.034 U	< 0.65 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	0.16	< 0.034 U	< 0.034 U	< 0.034 U	0.027 J		0.08	< 0.034 U	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	0.32 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.12 J	< 0.034 U	< 0.034 U	< 0.66 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	< 0.028 U	< 0.032 U	< 0.032 U	< 0.02 U	< 0.028 U		< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	0.12	< 0.034 U	< 0.034 U	< 0.034 U	0.028 J		0.049 J	< 0.034 U	< 0.034 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	1.4	< 0.034 U	< 0.034 U	< 0.034 U	0.19 J		0.69	< 0.034 U	< 0.034 U	< 1.1 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	0.15	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	0.024 J	< 0.17 U	< 0.092 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	0.39	< 0.1 U		< 0.13 U	0.11	< 0.1 U	0.15	< 0.16 U	< 0.09 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.034 U	< 0.098 U		< 0.13 U	< 0.016 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.087 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.035 U	< 0.1 U		< 0.13 UT	< 0.017 UT	< 0.1 U	< 0.014 U	< 0.16 UT	< 0.089 U	< 0.13 UT
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B84	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.008 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.007 U		< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0081 U	< 0.028 U	< 0.039 U	< 0.03 U	< 0.0071 U		< 0.0068 U	< 0.18 U	< 0.16 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0085 U	< 0.029 U	< 0.04 U	< 0.031 U	< 0.0074 U		< 0.0071 U	< 0.18 U	< 0.17 U	< 0.17 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0083 U	< 0.028 U	< 0.039 U	< 0.03 U	< 0.0072 U		< 0.0069 U	< 0.18 U	< 0.17 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.008 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.0069 U		< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0081 U	< 0.027 U	< 0.038 U	< 0.03 U	< 0.0071 U		< 0.0068 U	< 0.18 U	< 0.16 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.008 U	< 0.027 U	< 0.038 U	< 0.029 U	< 0.0069 U		< 0.0067 U	< 0.17 U	< 0.16 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	0.63	< 0.026 U	< 0.036 U	< 0.028 U	0.058 J		0.23	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.0075 U	< 0.025 U	< 0.036 U	< 0.027 U	< 0.0065 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0076 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0067 U		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0078 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0068 U		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0078 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0068 U		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	0.05 J	< 0.032 U	< 0.033 U	< 0.02 U	< 0.028 U		< 0.026 U	< 0.13 U	< 0.11 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	0.026 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U	< 0.018 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	0.016 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U	< 0.018 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	0.057 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.022 J	< 0.034 U	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	0.13 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.052 J	< 0.034 U	< 0.034 U	< 0.26 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0065 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U		< 0.0065 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0067 U		< 0.0064 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.025 U	< 0.036 U	< 0.027 U	< 0.0066 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0075 U	< 0.025 U	< 0.036 U	< 0.027 U	< 0.0065 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.0075 U	< 0.026 U	< 0.036 U	< 0.028 U	< 0.0066 U		< 0.0063 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0078 U	< 0.027 U	< 0.037 U	< 0.029 U	< 0.0068 U		< 0.0065 U	< 0.17 U	< 0.16 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.0073 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U		< 0.0061 U	< 0.16 U	< 0.15 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0074 U	< 0.025 U	< 0.035 U	< 0.027 U	< 0.0064 U		< 0.0062 U	< 0.16 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0077 U	< 0.026 U	< 0.037 U	< 0.028 U	< 0.0068 U		< 0.0065 U	< 0.17 U	< 0.15 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	< 0.027 U	< 0.031 U	< 0.031 U	< 0.02 U	< 0.027 U		< 0.026 U	< 0.12 U	< 0.1 U	< 0.13 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	0.057 J	< 0.034 U	< 0.034 U	< 0.034 U	0.018 J		0.04 J	< 0.034 U	< 0.034 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.55 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	0.083	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U		< 0.025 U	< 0.12 U	< 0.1 U	< 0.13 U

DRAFT

													Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol	Pyrene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																			0.8	100	0.33	100
Restricted - Residential																			6.7	100	100	100
Protection of Groundwater																			0.8	1000	0.33	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.0089 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.032 U	< 0.042 U	< 0.14 U		< 0.009 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0082 U	< 0.032 U	< 0.031 U	< 0.011 U	< 0.0083 U	< 0.0071 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.66 U	0.19	< 0.047 U	0.22
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.56 U	< 0.24 U	< 1.1 U		< 0.1 U	< 0.51 U	< 2.4 U	8.4 J	< 0.46 U	12 J
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.88 J	< 0.11 U	1.2 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated	< 0.56 U	< 0.24 U	< 1.1 U		< 0.1 U	< 0.51 U	< 2.4 U	10	< 0.46 U	24
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.18 U	< 0.08 U	< 0.35 U		< 0.034 U	< 0.17 U	< 0.8 U	1	< 0.15 U	6
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	0.73	< 0.12 U	1.3
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 1.2 U		< 0.034 U	< 0.034 U	< 0.034 U	0.23 J	< 0.53 U	0.43
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.4	< 0.12 U	0.54
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 1.2 U		< 0.034 U	< 0.034 U	< 0.034 U	0.25 J	< 0.54 U	0.53
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated	< 0.028 U	< 0.026 U	< 0.38 U		< 0.025 U	< 0.057 U	< 0.68 U	< 0.03 U	< 0.049 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	0.17	< 0.11 U	0.29
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 2 U		< 0.034 U	< 0.034 U	< 0.034 U	1.5	< 0.88 U	2.9
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	0.093	< 0.11 U	0.41
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.42	< 0.11 U	0.78
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.12 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U	< 0.016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 UT	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 UT	0.022 J
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0092 U	< 0.0079 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.033 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	0.015 J	< 0.0093 U	0.016 J
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.034 U	< 0.045 U	< 0.15 U		< 0.0096 U	< 0.038 U	< 0.037 U	< 0.013 U	< 0.0097 U	< 0.0083 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.033 U	< 0.044 U	< 0.15 U		< 0.0094 U	< 0.037 U	< 0.036 U	< 0.013 U	< 0.0095 U	< 0.0081 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0091 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.033 U	< 0.043 U	< 0.14 U		< 0.0092 U	< 0.036 U	< 0.035 U	< 0.013 U	< 0.0093 U	< 0.008 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.032 U	< 0.043 U	< 0.14 U		< 0.0091 U	< 0.036 U	< 0.035 U	< 0.012 U	< 0.0091 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.031 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	0.52	< 0.0087 U	1
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	< 0.012 U	< 0.0086 U	< 0.0073 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.13 U		< 0.0087 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0087 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	0.012 J	< 0.009 U	0.016 J
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.042 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	0.035 J	< 0.0089 U	0.011 J
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated	< 0.028 U	< 0.027 U	< 0.39 U		< 0.025 U	< 0.058 U	< 0.7 U	0.13	< 0.05 U	0.2
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U	0.042 J
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U	0.033 J
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.13	< 0.11 U	0.18
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.5 U		< 0.034 U	< 0.034 U	< 0.034 U	0.12 J	< 0.21 U	0.21
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.029 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.032 U	< 0.012 U	< 0.0086 U	< 0.0073 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.033 U	< 0.012 U	< 0.0088 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0086 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0085 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0086 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0086 U	< 0.034 U	< 0.033 U	< 0.012 U	< 0.0086 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.032 U	< 0.042 U	< 0.14 U		< 0.0089 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.009 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.03 U	< 0.039 U	< 0.13 U		< 0.0083 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0084 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.03 U	< 0.04 U	< 0.13 U		< 0.0084 U	< 0.033 U	< 0.032 U	< 0.011 U	< 0.0085 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.031 U	< 0.041 U	< 0.14 U		< 0.0088 U	< 0.035 U	< 0.034 U	< 0.012 U	< 0.0089 U	< 0.0076 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.056 U	< 0.67 U	< 0.03 U	< 0.048 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.11 U	0.21
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 1 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.45 U	0.18 J
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.67 U	0.31	< 0.048 U	0.38

TABLE 6-3C
Subsurface Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated		< 0.029 U	< 0.024 U	< 0.041 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated		< 0.029 U	< 0.025 U	< 0.041 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated		< 0.026 U	< 0.022 U	< 0.037 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.028 U	< 0.033 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated		< 0.066 U	< 0.63 U	< 0.11 U	< 0.083 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00 SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated		< 0.066 U	< 0.63 U	< 0.11 U	< 0.084 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30 SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated		< 0.022 U	< 0.21 U	< 0.036 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.029 U	< 0.034 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated		< 0.03 U	< 0.025 U	< 0.042 U	< 0.058 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated		< 0.03 U	< 0.025 U	< 0.042 U	< 0.059 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated		< 0.031 U	< 0.026 U	< 0.044 U	< 0.061 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated		< 0.03 U	< 0.026 U	< 0.043 U	< 0.06 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated		< 0.03 U	< 0.025 U	< 0.042 U	< 0.059 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated		< 0.029 U	< 0.025 U	< 0.041 U	< 0.058 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated		< 0.029 U	< 0.024 U	< 0.04 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated		< 0.029 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated		< 0.026 U	< 0.029 U	< 0.035 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30 SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30 SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.039 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.023 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated		< 0.028 U	< 0.023 U	< 0.039 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated		< 0.028 U	< 0.023 U	< 0.039 U	< 0.055 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated		< 0.029 U	< 0.024 U	< 0.041 U	< 0.057 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.053 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated		< 0.027 U	< 0.023 U	< 0.038 U	< 0.054 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated		< 0.028 U	< 0.024 U	< 0.04 U	< 0.056 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.028 U	< 0.034 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated		< 0.025 U	< 0.028 U	< 0.034 U	< 0.031 U

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated							
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated								
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated								
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated								
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.021 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.025 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.023 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	0.0067 J	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.026 UT	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated								
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated								
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	0.015 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	0.044	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated						
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated						
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated						
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated						
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated						
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated						
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated						
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated						
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated						
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated						
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0038 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated							
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 UT
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated							
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U,*
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated							
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0029 U	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.002 U	< 0.0012 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated							
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0026 J	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	0.0022 J	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	0.0025 J	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	0.0027 J	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	0.0042 J	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated							
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0028 U	< 0.0033 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.0022 U	< 0.0025 U	< 0.0027 U	< 0.0037 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated							
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated							
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated							
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U	< 0.0026 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated								
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated								
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated								
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.01 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated								
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated								
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.0021 U	< 0.0026 U
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U	< 0.002 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated								
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated								
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated								
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated								
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated								
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated								
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated								
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated								
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0083 U	< 0.0083 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U	< 0.0083 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0099 U	< 0.0099 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0099 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0093 U	< 0.0093 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0093 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0094 U	< 0.0094 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U	< 0.0094 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.01 U	< 0.01 UT	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 UT	< 0.01 U	< 0.0052 U
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated								
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated								
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.007 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0027 U	< 0.0017 U	< 0.0034 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated						
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated						
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated						
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated						
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated						
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated						
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated						
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated						
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated						
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated						
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0025 U	< 0.002 U	< 0.0031 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0029 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated							
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U	< 0.0083 U	< 0.0041 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U	< 0.0099 U	< 0.0050 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U	< 0.0093 U	< 0.0047 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U	< 0.0094 U	< 0.0047 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.0052 UT	< 0.0052 U	< 0.0052 U	< 0.01 U	< 0.01 U	< 0.0052 U
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/25/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated							
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U	< 0.003 U
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0019 U	< 0.0015 U	< 0.0023 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
EHS Building	SSHS-B8SS	B-4-8-9-COMP_SSHS-B8SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	856.03	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated		< U					
EHS Building	SSHS-B9SS	B-4-8-9-COMP_SSHS-B9SS_10 JUN 08	B-4-8-9-Comp	6/10/2008	855.45	-	-	-	0 - 2.2 ft	0 - 2.2 ft	NA	Not Excavated		< U					
EHS Building	SSHS-B10SS	B-10-11-COMP_SSHS-B10SS_10 JUN 08	B-10-11-Comp	6/10/2008	855.75	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		0.0023 J					
EHS Building	SSHS-B5SS	B-2-3-5-COMP_SSHS-B5SS_10 JUN 08	B-2-3-5-Comp	6/10/2008	855.52	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		0.0051 J					
EHS Building	SSHS-B6SS	B-1-6-7-COMP_SSHS-B6SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	855.59	-	-	-	0 - 2.5 ft	0 - 2.5 ft	NA	Not Excavated		0.0051 J					
EHS Building	SSHS-B1SS	B-1-6-7-COMP_SSHS-B1SS_10 JUN 08	B-1-6-7-Comp	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated			0.0051 J				
EHS Building	SSHS-B1SS	B1-B11-COMP.1_SSHS-B1SS_10 JUN 08	B1-B11-Comp.1	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B1SS	B1-B11-COMP.2_SSHS-B1SS_10 JUN 08	B1-B11-Comp.2	6/10/2008	-	-	-	-	0 - 2.6 ft	0 - 2.6 ft	-	Not Excavated							
EHS Building	SSHS-B4S	B4-C2-COMPOSITE_SSHS-B4S_25 JUL 07	B4-C2-Composite	7/25/2007	-	-	-	-	2 - 2.9 ft	2 - 2.9 ft	-	Not Excavated							
EHS Building	SSHS-B3S	B3-C2-COMPOSITE_SSHS-B3S_25 JUL 07	B3-C2-Composite	7/25/2007	855.70	-	-	-	2 - 2.9 ft	2 - 2.9 ft	NA	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-0.17-2	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-0.17-2	SSHS-B2385-SUB-0.17-2	8/30/2018	855.00	855.38	0.38	-	0.17 - 2 ft	0.55-2.38 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-0.17-2	SSHS-B2386-SUB-0.17-2	8/30/2018	855.18	855.37	0.19	-	0.17 - 2 ft	0.36-2.19 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-0.17-2	SSHS-B3474-SUB-0.17-2	7/27/2020	855.64	855.65	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-0.17-2	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-0.17-2	SSHS-B3476-SUB-0.17-2	7/27/2020	855.25	855.45	0.20	-	0.17 - 2 ft	0.37-2.2 ft	180-108826-1	Not Excavated							
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-0.17-2	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3501	090120 10:30_SSHS-B3501-SUB-0.17-2	SSHS-B3501-SUB-0.17-2	8/31/2020	855.88	855.90	0.02	-	0.17 - 2 ft	0.19-2.02 ft	180-110264-1	Not Excavated							
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-DUP1	SSHS-IRM5-SND-DUP1	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0041 U	< 0.0083 U
Football Field	IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	SSHS-IRM5-SND-SCV3	4/24/2026	-	855.602	-	-	1.58 - 2.026 ft	1.58 - 2.026 ft	1802045921	Not Excavated	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0050 U	< 0.0099 U
Football Field	IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	SSHS-IRM5-SND-SCV4	4/23/2026	-	855.378	-	-	1.678 - 2.028 ft	1.678 - 2.028 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0093 U
Football Field	IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	SSHS-IRM5-SND-SCV5	4/23/2026	-	854.796	-	-	1.8 - 2.197 ft	1.8 - 2.197 ft	1802045421	Not Excavated	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0047 U	< 0.0094 U
Football Field	IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	SSHS-IRM5-SND-SCV6	4/24/2026	-	855.395	-	-	1.879 - 2.486 ft	1.879 - 2.486 ft	1802045921	Not Excavated	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.0052 U	< 0.01 U
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-10-12	SSHS-B451-SUB-10-12	9/27/2016	854.61	855.67	1.06	-	10 - 12 ft	11.06-13.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20_SSHS-B625-SUB-10-12	SSHS-B625-SUB-10-12	2/8/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35_SSHS-B621-SUB-10-12	SSHS-B621-SUB-10-12	2/13/2017	854.74	855.25	0.51	-	10 - 12 ft	10.51-12.51 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50_SSHS-B622-SUB-10-12	SSHS-B622-SUB-10-12	2/16/2017	856.13	856.14	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B654	021817 08:50_SSHS-B654-SUB-10-12	SSHS-B654-SUB-10-12	2/16/2017	855.76	855.77	0.01	-	10 - 12 ft	10.01-12.01 ft	180-63593-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00_SSHS-B683-SUB-10-12	032317 09:00_SSHS-B683-SUB-10-12	3/22/2017	855.02	855.65	0.63	-	10 - 12 ft	10.63-12.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B625A	071217 08:20_SSHS-B625A-SUB-10-12	SSHS-B625A-SUB-10-12	7/11/2017	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-68095-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50_SSHS-B2230-SUB-10-12	SSHS-B2230-SUB-10-12	7/23/2018	856.03	856.03	0.00	-	10 - 12 ft	10-12 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50_SSHS-B2231-SUB-10-12	SSHS-B2231-SUB-10-12	7/23/2018	856.14	856.13	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50_SSHS-B2234-SUB-10-12	SSHS-B2234-SUB-10-12	7/23/2018	855.41	855.54	0.13	-	10 - 12 ft	10.13-12.13 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2235	072418 08:50_SSHS-B2235-SUB-10-12	SSHS-B2235-SUB-10-12	7/23/2018	855.30	855.51	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2240	072418 08:50_SSHS-B2240-SUB-10-12	SSHS-B2240-SUB-10-12	7/23/2018	855.85	855.85	0.00	-	10 - 12 ft	10-12 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2244	072418 08:50_SSHS-B2244-SUB-10-12	SSHS-B2244-SUB-10-12	7/23/2018	856.09	856.15	0.06	-	10 - 12 ft	10.06-12.06 ft	180-80091-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-10-12	SSHS-B2185-SUB-10-12	7/24/2018	855.07	855.49	0.42	-	10 - 12 ft	10.42-12.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-10-12	SSHS-B2186-SUB-10-12	7/24/2018	854.94	855.41	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-10-12	SSHS-B2187-SUB-10-12	7/24/2018	856.10	856.10	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-10-12	SSHS-B2188-SUB-10-12	7/24/2018	855.99	855.99	0.00	-	10 - 12 ft	10-12 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_PS-FD-12	PS-FD-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-10-12	SSHS-B2189-SUB-10-12	7/24/2018	855.74	855.90	0.16	-	10 - 12 ft	10.16-12.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-10-12	SSHS-B2191-SUB-10-12	7/24/2018	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-10-12	SSHS-B2197-SUB-10-12	7/24/2018	854.99	855.43	0.44	-	10 - 12 ft	10.44-12.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_PS-FD-9	PS-FD-9	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-2	Not Excavated							
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-10-12	SSHS-B2232-SUB-10-12	7/24/2018	856.82	856.82	0.00	-	10 - 12 ft	10-12 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-10-12	SSHS-B2233-SUB-10-12	7/24/2018	854.83	855.35	0.52	-	10 - 12 ft	10.52-12.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00_SSHS-B2245-SUB-10-12	SSHS-B2245-SUB-10-12	7/24/2018	855.25	855.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-10-12	SSHS-B2070-SUB-10-12	7/25/2018	854.72	855.22	0.50	-	10 - 12 ft	10.5-12.5 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2073	072618 08:50_SSHS-B2073-SUB-10-12	SSHS-B2073-SUB-10-12	7/25/2018	856.99	856.99	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-10-12	SSHS-B2089-SUB-10-12	7/25/2018	855.40	855.39	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-10-12	SSHS-B2091-SUB-10-12	7/25/2018	856.61	856.61	0.00	-	10 - 12 ft	10-12 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-10-12	SSHS-B2108-SUB-10-12	7/25/2018	855.64	855.64	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-10-12	SSHS-B2109-SUB-10-12	7/25/2018	855.25	855.48	0.23	-	10 - 12 ft	10.23-12.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-10-12	SSHS-B2110-SUB-10-12	7/25/2018	854.78	855.36	0.58	-	10 - 12 ft	10.58-12.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-10-12	SSHS-B2127-SUB-10-12	7/25/2018	855.91	855.91	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-10-12	SSHS-B2128-SUB-10-12	7/25/2018	856.01	856.01	0.00	-	10 - 12 ft	10-12 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-10-12	SSHS-B2129-SUB-10-12	7/25/2018	855.33	855.52	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-10-12	SSHS-B2143-SUB-10-12	7/25/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-10-12	SSHS-B2194-SUB-10-12	7/25/2018	856.19	856.19	0.00	-	10 - 12 ft	10-12 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-10-12	SSHS-B2216-SUB-10-12	7/25/2018	855.16	855.46	0.30	-	10 - 12 ft	10.3-12.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-10-12	SSHS-B2025-SUB-10-12	7/26/2018	854.55	854.52	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-10-12	SSHS-B2026-SUB-10-12	7/26/2018	855.26	855.47	0.21	-	10 - 12 ft	10.21-12.21 ft	180-80227-1	Not Excavated							
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-10-12	SSHS-B2028-SUB-10-12	7/26/2018	855.23	855.54	0.31	-	10 - 12 ft	10.31-12.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-10-12	SSHS-B2050-SUB-10-12	7/26/2018	855.45	855.45	0.00	-	10 - 12 ft	10-12 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-10-12	SSHS-B2192-SUB-10-12	7/26/2018	855.49	855.50	0.01	-	10 - 12 ft	10.01-12.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-10-12	SSHS-B2195-SUB-10-12	7/26/2018	855.94	855.94	0.00	-	10 - 12 ft	10-12 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_PS-FD-35	PS-FD-35	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-10-12	SSHS-B2213-SUB-10-12	7/26/2018	855.06	855.53	0.47	-	10 - 12 ft	10.47-12.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-10-12	SSHS-B2214-SUB-10-12	7/26/2018	855.14	855.34	0.20	-	10 - 12 ft	10.2-12.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-10-12	SSHS-B2215-SUB-10-12	7/26/2018	855.11	855.30	0.19	-	10 - 12 ft	10.19-12.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2223	072718 09:00_SSHS-B2223-SUB-10-12	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0044 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-B2224	072718 09:00_PS-FD-44	PS-FD-44	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-10-12	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0035 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2618	051819 10:00_PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00_SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U
Football Field	SSHS-IRM3-S130	080319 09:30_SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S152	080319 09:30_SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B2961	110719 09:00_SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated								
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated								
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated								
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated								
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated								
Football Field	IRM4-S169	080120 09:45_SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated								
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated								
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated								
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated								
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated								
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3573	020421 09:30_DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00_DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	0.021 J	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.21 U	< 0.077 U	< 0.16 U	< 0.13 U	< 0.14 U	< 0.12 U	< 0.22 U	< 0.11 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated								
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated								
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated								
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated								
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated								
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated								
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated								
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated								

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U,*
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2618	051819 10:00_PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2618	051819 10:00_SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-IRM3-S130	080319 09:30_SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S152	080319 09:30_SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B2961	110719 09:00_SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated							
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated							
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated							
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated							
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated							
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated							
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated							
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated							
Football Field	IRM4-S169	080120 09:45_SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated							
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated							
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated							
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated							
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated							
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated							
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated							
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated							
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated							
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated							
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated							
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated							
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated							
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3573	020421 09:30_DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 UJ	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 UJ
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UJ	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	020621 10:00_DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.071 U	< 0.13 U	< 0.16 U	< 0.087 U	< 0.11 U	< 0.13 U	< 0.18 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated							
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated							
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated							
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated							
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated							
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated							
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated							
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated							
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated							
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2618	051819 10:00_PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00_SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-IRM3-S130	080319 09:30_SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S152	080319 09:30_SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B2961	110719 09:00_SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated								
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated								
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated								
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated								
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	0.008	< 0.0029 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	0.0099	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated								
Football Field	IRM4-S169	080120 09:45_SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated								
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated								
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated								
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated								
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated								
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3573	020421 09:30_DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UJ	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3580	020621 10:00_DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.25 U	< 0.074 U	< 0.14 U	< 0.091 U	< 0.17 U	< 0.081 U	< 0.087 U	< 0.078 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 UJ	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated								
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated								
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated								
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated								
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated								
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated								
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated								
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2618	051819 10:00_PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00_SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-IRM3-S130	080319 09:30_SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S152	080319 09:30_SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B2961	110719 09:00_SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated								
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated								
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated								
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated								
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated								
Football Field	IRM4-S169	080120 09:45_SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated								
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated								
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated								
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated								
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated								
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3573	020421 09:30_DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3580	020621 10:00_DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.12 UJ	< 0.22 U	< 0.082 U	< 0.095 U	< 0.072 U	< 0.12 U	< 0.12 U	< 0.1 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated								
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated								
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated								
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated								
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated								
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated								
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated								
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Football Field	SSHS-B2618	051819 10:00_PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00_SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-IRM3-S130	080319 09:30_SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S152	080319 09:30_SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B2961	110719 09:00_SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated								
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated								
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated								
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated								
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated								
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated								
Football Field	IRM4-S169	080120 09:45_SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated								
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated								
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated								
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated								
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated								
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated								
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3573	020421 09:30_DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00_DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.11 U	< 0.085 U	< 0.14 U	< 0.4 U	< 0.13 U	< 0.14 U	< 0.099 U	< 0.08 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated								
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated								
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated								
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated								
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated								
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated								
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated								
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated								
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2071	072818 11:30 PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Football Field	SSHS-B2763	042819 10:00 PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U	< 0.0027 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Football Field	SSHS-B2618	051819 10:00 PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B108	080319 09:30 SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-PIPE11	080319 09:30 SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Football Field	SSHS-IRM3-S130	080319 09:30 SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S152	080319 09:30 SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B2961	110719 09:00 SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated							
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated							
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated							
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated							
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated							
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated							
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated							
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated							
Football Field	IRM4-S169	080120 09:45 SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated							
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated							
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated							
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated							
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated							
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated							
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated							
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated							
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated							
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated							
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated							
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated							
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3573	020421 09:30 DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UJ	< 0.0026 UJ	< 0.0017 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ	< 0.0017 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3580	020621 10:00 DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.081 U	< 0.083 U	< 0.11 U	< 0.078 U	< 0.15 U	< 0.14 U	< 0.091 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated							
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated							
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated							
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated							
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated							
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated							
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated							
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated							
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated							
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2226	072718 09:00_SSHS-B2226-SUB-10-12	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2227	072718 09:00_SSHS-B2227-SUB-10-12	SSHS-B2227-SUB-10-12	7/26/2018	856.55	856.55	0.00	-	10 - 12 ft	10-12 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30_PS-FD-48	PS-FD-48	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-10-12	SSHS-B2031-SUB-10-12	7/27/2018	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-10-12	SSHS-B2032-SUB-10-12	7/27/2018	854.88	855.51	0.63	-	10 - 12 ft	10.63-12.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-10-12	SSHS-B2033-SUB-10-12	7/27/2018	854.70	855.74	1.04	-	10 - 12 ft	11.04-13.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-10-12	SSHS-B2051-SUB-10-12	7/27/2018	855.08	855.37	0.29	-	10 - 12 ft	10.29-12.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2071	072818 11:30_PS-FD-47	PS-FD-47	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2071	072818 11:30_SSHS-B2071-SUB-10-12	SSHS-B2071-SUB-10-12	7/27/2018	856.16	856.16	0.00	-	10 - 12 ft	10-12 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-10-12	SSHS-B2090-SUB-10-12	7/27/2018	855.97	855.96	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-10-12	SSHS-B2217-SUB-10-12	7/27/2018	855.08	855.32	0.24	-	10 - 12 ft	10.24-12.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2228	072818 11:30_SSHS-B2228-SUB-10-12	SSHS-B2228-SUB-10-12	7/27/2018	855.33	855.33	0.00	-	10 - 12 ft	10-12 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00_SSHS-B2747-SUB-10-12	SSHS-B2747-SUB-10-12	4/23/2019	856.08	856.07	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-10-12	SSHS-B2753-SUB-10-12	4/23/2019	856.56	856.57	0.01	-	10 - 12 ft	10.01-12.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-10-12	SSHS-B2767-SUB-10-12	4/23/2019	856.06	856.06	0.00	-	10 - 12 ft	10-12 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-10-12	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2763	042819 10:00_PS-FD-17	PS-FD-17	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-10-12	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2618	051819 10:00_PS-FD-19	PS-FD-19	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2618	051819 10:00_SSHS-B2618-SUB-10-12	SSHS-B2618-SUB-10-12	5/17/2019	855.12	855.29	0.17	-	10 - 12 ft	10.17-12.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-B108-C	SSHS-IRM3-B108-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B108	080319 09:30_SSHS-IRM3-DUP3-C	SSHS-IRM3-DUP3-C	8/2/2019	-	855.78	-	843.81	10 - 12 ft	11.97 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-PIPE11	080319 09:30_SSHS-IRM3-PIPE11-C	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U		< 0.0025 U	< 0.0045 U
Football Field	SSHS-IRM3-S130	080319 09:30_SSHS-IRM3-S130-C	SSHS-IRM3-S130-C	8/2/2019	-	856.03	-	845.82	10 - 12 ft	10.21 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S152	080319 09:30_SSHS-IRM3-S152-C	SSHS-IRM3-S152-C	8/2/2019	-	856.02	-	845.02	10 - 12 ft	11 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B2961	110719 09:00_SSHS-B2961-SUB-10-12	SSHS-B2961-SUB-10-12	11/5/2019	855.28	855.38	0.10	-	10 - 12 ft	10.1-12.1 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-10-12	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S150	SSHS-IRM4-S150-10-12-20200723	SSHS-IRM4-S150-10-12	7/23/2020	-	855.65	-	843.78	10 - 12 ft	11.87	1801086951	Not Excavated							
Football Field	IRM4-S124	SSHS-IRM4-S124-8-10-20200723	SSHS-IRM4-S124-8-10	7/23/2020	-	855.33	-	845.22	10 - 12 ft	10.11 ft	1801086851	Not Excavated							
Football Field	IRM4-S144	SSHS-IRM4-S144-10-12-20200725	SSHS-IRM4-S144-10-12	7/25/2020	-	855.73	-	844.33	10 - 12 ft	11.4 ft	1801088021	Not Excavated							
Football Field	IRM4-B007	SSHS-IRM4-B007-20200725	SSHS-IRM4-B007	7/25/2020	-	855.59	-	844.09	10 - 12 ft	11.5 ft	1801088021	Not Excavated							
Football Field	IRM4-S145	SSHS-IRM4-S145-10-12-20200725	SSHS-IRM4-S145-10-12	7/25/2020	-	855.36	-	844.29	10 - 12 ft	11.07 ft	1801088021	Not Excavated							
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-10-12	SSHS-B3459-SUB-10-12	7/27/2020	856.30	856.31	0.01	-	10 - 12 ft	10.01-12.01 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-10-12	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-10-12	SSHS-B3472-SUB-10-12	7/27/2020	855.50	855.50	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	IRM4-S158	SSHS-IRM4-DUP9-20200728	SSHS-IRM4-DUP9	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated							
Football Field	IRM4-S158	SSHS-IRM4-S158-12-14-20200728	SSHS-IRM4-S158-12-14	7/28/2020	-	855.26	-	843.64	10 - 12 ft	11.62 ft	1801088511	Not Excavated							
Football Field	IRM4-S157	SSHS-IRM4-S157-12-14-20200728	SSHS-IRM4-S157-12-14	7/28/2020	-	855.59	-	843.75	10 - 12 ft	11.84 ft	1801088411	Not Excavated							
Football Field	IRM4-S169	080120 09:45_SSHS-IRM4-S169-12-14	SSHS-IRM4-S169	7/31/2020	-	855.50	-	844.59	10 - 12 ft	10.91 ft	180-109051-1	Not Excavated							
Football Field	IRM4-S143B	SSHS-IRM4-S143B-10-12-20200803	SSHS-IRM4-S143B-10-12	8/3/2020	-	855.68	-	844.90	10 - 12 ft	10.78 ft	1801090931	Not Excavated							
Football Field	IRM4-S143C	SSHS-IRM4-S143C-10-12-20200803	SSHS-IRM4-S143C-10-12	8/3/2020	-	855.85	-	845.77	10 - 12 ft	10.08 ft	1801090931	Not Excavated							
Football Field	IRM4-S143F	SSHS-IRM4-S143F-12-14-20200803	SSHS-IRM4-S143F-12-14	8/3/2020	-	855.85	-	844.03	10 - 12 ft	11.82 ft	1801090931	Not Excavated							
Football Field	IRM4-S123BOT2	SSHS-IRM4-DUP17-20200806	SSHS-IRM4-DUP17	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated							
Football Field	IRM4-S123BOT2	SSHS-IRM4-S123BOT2-20200806	SSHS-IRM4-S123BOT2	8/6/2020	-	855.37	-	844.88	10 - 12 ft	10.49 ft	1801092831	Not Excavated							
Football Field	IRM4A-B008	SSHS-IRM4A-B008-20201012	SSHS-IRM4A-B008	10/12/2020	-	855.76	-	845.53	10 - 12 ft	10.24 ft	1801121721	Not Excavated							
Football Field	IRM4A-B009	SSHS-IRM4A-B009-20201012	SSHS-IRM4A-B009	10/12/2020	-	856.18	-	846.04	10 - 12 ft	10.14 ft	1801121721	Not Excavated							
Football Field	IRM4A-S143	SSHS-IRM4A-S143-20201012	SSHS-IRM4A-S143	10/12/2020	-	856.22	-	844.73	10 - 12 ft	11.49 ft	1801121721	Not Excavated							
Football Field	IRM4A-S144	SSHS-IRM4A-S144-20201012	SSHS-IRM4A-S144	10/12/2020	-	856.47	-	845.06	10 - 12 ft	11.41 ft	1801121721	Not Excavated							
Football Field	IRM4A-S146	SSHS-IRM4A-DUP9-20201019	SSHS-IRM4A-DUP9	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated							
Football Field	IRM4A-S146	SSHS-IRM4A-S146-20201019	SSHS-IRM4A-S146	10/19/2020	-	855.62	-	844.02	10 - 12 ft	11.6 ft	1801124481	Not Excavated							
Football Field	IRM4A-S125 BOT	SSHS-IRM4A-S125 BOT-20201119	SSHS-IRM4A-S125 BOT	11/19/2020	-	855.40	-	844.81	10 - 12 ft	10.59 ft	1801138861	Not Excavated							
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-10-12	SSHS-B3575-SUB-10-12	2/2/2021	854.85	855.40	0.55	-	10 - 12 ft	10.55-12.55 ft	180-116724-1	Not Excavated	< 0.0011 U	0.0021 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3573	020421 09:30_DUP-28	DUP-28	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.001 U	0.065	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-10-12	SSHS-B3573-SUB-10-12	2/3/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.001 U	0.0074	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-10-12	SSHS-B3574-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.0011 U	0.036	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-10-12	SSHS-B3576-SUB-10-12	2/3/2021	855.76	855.76	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-10-12	SSHS-B3578-SUB-10-12	2/3/2021	855.72	855.72	0.00	-	10 - 12 ft	10-12 ft	180-116773-1	Not Excavated	< 0.001 U	0.0084	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-10-12	SSHS-B3572-SUB-10-12	2/4/2021	855.42	855.51	0.09	-	10 - 12 ft	10.09-12.09 ft	180-116864-1	Not Excavated	< 0.0011 U	0.0034 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3580	020621 10:00_DUP-32	DUP-32	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0011 U	0.0089 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-10-12	SSHS-B3580-SUB-10-12	2/5/2021	856.23	856.24	0.01	-	10 - 12 ft	10.01-12.01 ft	180-116914-1	Not Excavated	< 0.0011 U	0.023 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-10-12	SSHS-B3581-SUB-10-12	2/5/2021	856.18	856.18	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-10-12	SSHS-B3582-SUB-10-12	2/5/2021	855.93	855.93	0.00	-	10 - 12 ft	10-12 ft	180-116914-1	Not Excavated	< 0.054 U	< 0.085 U	< 0.23 U	< 0.2 U	< 0.097 U	< 0.11 U	< 0.39 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-10-12	SSHS-B3583-SUB-10-12	2/5/2021	855.33	855.44	0.11	-	10 - 12 ft	10.11-12.11 ft	180-116914-1	Not Excavated	< 0.001 U	0.011	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	IRM4A-S132	SSHS-IRM4A-DUP104-20210208	SSHS-IRM4A-DUP104	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169472	Not Excavated							
Football Field	IRM4A-S161	SSHS-IRM4A-S161-10-12-20210208	SSHS-IRM4A-S161-10-12	2/8/2021	-	855.36	-	844.68	10 - 12 ft	10.68 ft	1801169471	Not Excavated							
Football Field	IRM4A-S132	SSHS-IRM4A-S132-8-10-20210208	SSHS-IRM4A-S132-8-10	2/8/2021	-	855.39	-	844.55	10 - 12 ft	10.84 ft	1801169471	Not Excavated							
Football Field	IRM4A-S157A	SSHS-IRM4A-DUP18-20210302	SSHS-IRM4A-DUP18	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177751	Not Excavated							
Football Field	IRM4A-S157A	SSHS-IRM4A-S157A-20210302	SSHS-IRM4A-S157A	3/2/2021	-	855.50	-	843.62	10 - 12 ft	11.88 ft	1801177752	Not Excavated							
Football Field	IRM4A-S157B	SSHS-IRM4A-S157B-20210302	SSHS-IRM4A-S157B	3/2/2021	-	855.46	-	843.79	10 - 12 ft	11.67 ft	1801177752	Not Excavated							
Football Field	IRM5-MH-X	SSHS-IRM5-MH-X-20210308	SSHS-IRM5-MH-X	3/8/2021	-	855.32	-	844.80	10 - 12 ft	10.53 ft	1801180551	Not Excavated							
Football Field	IRM5-S269	SSHS-IRM5-S269-20210317	SSHS-IRM5-S269	3/17/2021	-	855.30	-	843.65	10 - 12 ft	11.64 ft	1801185741	Not Excavated							
Football Field	IRM5-S268	SSHS-IRM5-S268-20210317	SSHS-IRM5-S268	3/17/2021	-	855.25	-	843.99	10 - 12 ft	11.26 ft	1801185741	Not Excavated							
Football Field	IRM5-S270	SSHS-IRM5-S270-20210317	SSHS-IRM5-S270	3/17/2021	-	855.26	-	843.57	10 - 12 ft	11.69 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131DBOT2	SSHS-IRM4A-S131DBOT2-20210319	SSHS-IRM4A-S131DBOT2	3/19/2021	-	855.43	-	845.18	10 - 12 ft	10.25 ft	1801187461	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated							
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated							
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated							
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated							
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated							
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated							
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated							
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated							
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated							
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated							
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated							
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated							
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated							
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated							
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated							
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated							
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated							
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated							
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated							
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated							
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated							
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated							
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated							
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated							
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated							
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	0.0069 J	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	0.0060 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 UT	< 0.0020 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 UT	< 0.0022 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0047 UT	< 0.0017 UT	< 0.0036 UT	< 0.0028 UT	< 0.0031 UT	< 0.0028 UT	< 0.0048 UT	< 0.0025 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0034 U	< 0.0036 U	< 0.0033 U	< 0.0058 U	< 0.0029 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated								
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated								
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0034 U	< 0.0036 U	< 0.0033 U	< 0.0058 U	< 0.0029 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated								

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated						
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated						
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated						
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated						
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated						
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated						
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated						
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated						
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated						
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated						
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated						
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated						
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated						
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated						
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated						
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated						
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated						
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated						
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated						
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated						
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated						
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated						
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated						
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated						
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated						
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated						
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated						
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated						
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated						
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated						
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 UT
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0016 UT	< 0.0030 UT	< 0.0035 UT	< 0.0019 UT	< 0.0024 UT	< 0.0029 UT	< 0.0039 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0019 U	< 0.0036 U	< 0.0042 U	< 0.0023 U	< 0.0029 U	< 0.0035 U	< 0.0047 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 UT
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated							
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated							
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0019 U	< 0.0036 U	< 0.0042 U	< 0.0023 U	< 0.0029 U	< 0.0035 U	< 0.0047 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated							
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated							
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated							
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated							
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated							
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated							
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated							
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated							
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated							
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated							
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated							
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated							
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated							
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated							
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated							
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated							
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated							
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated							
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated							
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated							
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated							
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated							
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated							
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated							
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated							
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 UT	< 0.0034 UT	< 0.0016 UT	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0055 UT	< 0.0017 UT	< 0.0030 UT	< 0.0020 UT	< 0.0037 UT	< 0.0018 UT	< 0.0019 UT	< 0.0017 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0065 U	< 0.0020 U	< 0.0036 U	< 0.0024 U	< 0.0045 U	< 0.0022 U	< 0.0023 U	< 0.0021 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 UT	< 0.0030 UT	< 0.0015 UT	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated							
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated							
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0065 U	< 0.0020 U	< 0.0036 U	< 0.0024 U	< 0.0044 U	< 0.0022 U	< 0.0023 U	< 0.0021 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated								
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated								
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated								
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated								
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated								
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated								
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated								
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated								
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated								
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated								
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated								
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated								
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated								
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated								
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated								
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated								
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated								
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated								
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated								
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated								
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated								
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated								
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated								
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated								
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated								
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated								
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated								
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated								
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0029 U	< 0.0052 U	0.0049 J	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0027 UT	< 0.0049 UT	< 0.0018 UT	< 0.0021 UT	< 0.0016 UT	< 0.0027 UT	< 0.0027 UT	< 0.0022 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0033 U	0.037	0.036	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0033 U	< 0.0027 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated								
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated								
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0033 U	< 0.0059 U	< 0.0022 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0032 U	< 0.0027 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated								
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated								
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated								
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated								
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated								
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated								
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated								
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated								
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated								
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated								
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated								
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated								
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated								
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated								
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated								
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated								
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated								
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated								
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated								
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated								
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated								
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated								
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated								
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated								
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated								
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated								
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated								
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated								
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0024 UT	< 0.0019 UT	0.0055 JT	< 0.0089 UT	0.0041 JT	< 0.0031 UT	< 0.0022 UT	< 0.0018 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0029 U	< 0.0023 U	< 0.0038 U	< 0.011 U	< 0.0035 U	< 0.0037 U	< 0.0027 U	< 0.0021 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated								
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated								
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0029 U	< 0.0023 U	< 0.0038 U	< 0.011 U	< 0.0035 U	< 0.0037 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated						
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated						
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated						
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated						
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated						
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated						
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated						
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated						
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated						
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated						
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated						
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated						
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated						
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated						
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated						
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated						
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated						
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated						
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated						
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated						
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated						
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated						
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated						
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated						
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated						
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated						
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated						
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated						
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated						
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated						
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 UT	< 0.0028 UT	< 0.0018 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.63	-	845.80	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0018 UT	< 0.0018 UT	< 0.0024 UT	< 0.0017 UT	< 0.0033 UT	< 0.0031 UT	< 0.0020 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0040 U	< 0.0037 U	< 0.0024 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 UT	< 0.0025 UT	< 0.0016 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated							
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated							
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0022 U	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0040 U	< 0.0037 U	< 0.0024 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4A-S131DBOT1	SSHS-IRM4A-S131DBOT1-20210319	SSHS-IRM4A-S131DBOT1	3/19/2021	-	855.36	-	844.70	10 - 12 ft	10.66 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131D5	SSHS-IRM4A-S131D5-20210319	SSHS-IRM4A-S131D5	3/19/2021	-	855.63	-	845.59	10 - 12 ft	10.04 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131BOT1B	SSHS-IRM4A-S131DBOT1B-20210319	SSHS-IRM4A-S131DBOT1B	3/19/2021	-	855.51	-	843.58	10 - 12 ft	11.93 ft	1801187461	Not Excavated							
Football Field	IRM5-PIPE 18-SDBOT1	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1-2021040	SSHS-IRM5-PIPE 18-STEPDOWN-BOT-1	4/1/2021	-	855.51	-	845.48	10 - 12 ft	10.02 ft	1801194581	Not Excavated							
Football Field	ISMP-PIPE1EAST	SSHS-ISMP-PIPE1EAST-20210405	SSHS-ISMP-PIPE1EAST	4/5/2021	-	855.84	-	845.57	10 - 12 ft	10.28	1801195091	Not Excavated							
Football Field	ISMP-PIPE1BOT	SSHS-ISMP-PIPE1BOT-20210405	SSHS-ISMP-PIPE1BOT	4/5/2021	-	855.84	-	844.98	10 - 12 ft	10.86	1801195091	Not Excavated							
Football Field	IRM5-WELL 2 NORTH	SSHS-IRM5-WELL 2 NORTH-20210409	SSHS-IRM5-WELL 2 NORTH	4/9/2021	-	855.61	-	845.21	10 - 12 ft	10.4 ft	1801197961	Not Excavated							
Football Field	IRM5-WELL 2 SOUTH	SSHS-IRM5-WELL 2 SOUTH-20210409	SSHS-IRM5-WELL 2 SOUTH	4/9/2021	-	855.51	-	845.30	10 - 12 ft	10.21 ft	1801197961	Not Excavated							
Football Field	IRM5-B605	SSHS-IRM5-B605-20210412	SSHS-IRM5-B605	4/12/2021	-	855.60	-	844.53	10 - 12 ft	11.07 ft	1801198482	Not Excavated							
Football Field	IRM5-B700D	SSHS-IRM5-DUP 48-20210413	SSHS-IRM5-DUP 48	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated							
Football Field	IRM5-B700D	SSHS-IRM5-B700D-20210413	SSHS-IRM5-B700D	4/13/2021	-	855.35	-	843.89	10 - 12 ft	11.46 ft	1801199181	Not Excavated							
Football Field	IRM5-B808 BOT 2	SSHS-IRM5-B808 BOT 2-20210416	SSHS-IRM5-B808 BOT 2	4/16/2021	-	855.56	-	844.66	10 - 12 ft	10.9 ft	1801201431	Not Excavated							
Football Field	IRM5-B700B2	SSHS-IRM5-B700 B2-20210418	SSHS-IRM5-B700 B2	4/18/2021	-	855.57	-	844.21	10 - 12 ft	11.36 ft	1801201971	Not Excavated							
Football Field	IRM5-B700B3	SSHS-IRM5-B700 B3-20210418	SSHS-IRM5-B700 B3	4/18/2021	-	855.54	-	844.01	10 - 12 ft	11.53 ft	1801201971	Not Excavated							
Football Field	IRM5-B700B4	SSHS-IRM5-B700 B4-20210418	SSHS-IRM5-B700 B4	4/18/2021	-	855.49	-	844.49	10 - 12 ft	11 ft	1801201971	Not Excavated							
Football Field	IRM5-SEGMENT 7 BOT	SSHS-IRM5-SEG 7 S BOT-20210421	SSHS-IRM5-SEG 7 S BOT	4/21/2021	-	853.51	-	842.06	10 - 12 ft	11.45 ft	1801203601	Not Excavated							
Football Field	IRM5-DW3BOT	SSHS-IRM5-DW3 BOT-20210423	SSHS-IRM5-DW3 BOT	4/23/2021	-	855.60	-	844.96	10 - 12 ft	10.65 ft	1801205491	Not Excavated							
Football Field	IRM5-DW4WEST	SSHS-IRM5-DW4 W-20210423	SSHS-IRM5-DW4 W	4/23/2021	-	855.61	-	845.36	10 - 12 ft	10.25 ft	1801205491	Not Excavated							
Football Field	IRM5-ALPHA BOT 8	SSHS-IRM5-ALPHA BOT 8-20210430	SSHS-IRM5-ALPHA BOT 8	4/30/2021	-	855.67	-	844.21	10 - 12 ft	11.46 ft	1801209531	Not Excavated							
Football Field	IRM5-ALPHA BOT 7	SSHS-IRM5-ALPHA BOT 7-20210430	SSHS-IRM5-ALPHA BOT 7	4/30/2021	-	855.80	-	844.69	10 - 12 ft	11.11 ft	1801209531	Not Excavated							
Football Field	IRM5-P18 7 S3A	SSHS-IRM5-P187 S3A-20210508	SSHS-IRM5-P187 S3A	5/8/2021	-	855.77	-	845.00	10 - 12 ft	10.77 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 7 S4B	SSHS-IRM5-P187 S4B-20210508	SSHS-IRM5-P187 S4B	5/8/2021	-	855.79	-	845.43	10 - 12 ft	10.36 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 7 BOT 6	SSHS-IRM5-P187 BOT 6-20210508	SSHS-IRM5-P187 BOT 6	5/8/2021	-	855.81	-	844.11	10 - 12 ft	11.7 ft	1801213861	Not Excavated							
Football Field	IRM5-P18 VAULT BOT 2	SSHS-IRM5-P18 VAULT BOT 2-20210510	SSHS-IRM5-P18 VAULT BOT 2	5/10/2021	-	855.83	-	845.24	10 - 12 ft	10.59 ft	1801213911	Not Excavated							
Football Field	IRM5-B227 BOT 3	SSHS-IRM5-B227 BOT 3-20210512	SSHS-IRM5-B227 BOT 3	5/12/2021	-	855.36	-	844.56	10 - 12 ft	10.8 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 BOT 4	SSHS-IRM5-B227 BOT 4-20210512	SSHS-IRM5-B227 BOT 4	5/12/2021	-	855.49	-	844.81	10 - 12 ft	10.68 ft	1801215152	Not Excavated							
Football Field	IRM5-S234 BOT D	SSHS-IRM5-S234 BOT D-20210513	SSHS-IRM5-S234 BOT D	5/13/2021	-	855.70	-	844.20	10 - 12 ft	11.51 ft	1801215901	Not Excavated							
Football Field	IRM5-S234 S13	SSHS-IRM5-S234 S13-20210513	SSHS-IRM5-S234 S13	5/13/2021	-	855.78	-	845.67	10 - 12 ft	10.11 ft	1801215901	Not Excavated							
Football Field	IRM5-PIPE 51 S10	SSHS-IRM5-PIPE 51 S10-20210519	SSHS-IRM5-PIPE 51 S10	5/19/2021	-	855.63	-	845.00	10 - 12 ft	10.63 ft	1801218701	Not Excavated							
Football Field	IRM5-BRAVO S13	SSHS-IRM5-BRAVO S13-20210526	SSHS-IRM5-BRAVO S13	5/26/2021	-	855.39	-	843.97	10 - 12 ft	11.42 ft	1801222611	Not Excavated							
Football Field	IRM5-BRAVO S14	SSHS-IRM5-BRAVO S14-20210526	SSHS-IRM5-BRAVO S14	5/26/2021	-	855.49	-	843.77	10 - 12 ft	11.73 ft	1801222611	Not Excavated							
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4-20210527	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5-20210527	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5-20210527	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4-20210527	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10-20210602	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18-20210602	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 0.0012 U	0.0023 J	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25-20210603	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 0.0012 U	0.032	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37-20210603	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 0.0013 U	0.018	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Football Field	ISMP-B538	SSHS-ISMP-B538-20210604	SSHS-ISMP-B538	6/4/2021	-	855.75	-	845.73	10 - 12 ft	10.02 ft	1801227322	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-B540	SSHS-ISMP-B540-20210604	SSHS-ISMP-B540	6/4/2021	-	855.64	-	843.81	10 - 12 ft	11.83 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210605	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210605	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210605	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210605	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210605	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9-20210607	SSHS-ISMP-DUP 9	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48-20210607	SSHS-ISMP-B527 S48	6/7/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49-20210607	SSHS-ISMP-B527 S49	6/7/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228231	Not Excavated	< 0.0012 UT	< 0.0019 UT	< 0.0050 UT	< 0.0044 UT	< 0.0022 UT	< 0.0024 UT	< 0.0087 UT
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65-20210607	SSHS-ISMP-B527 S65	6/7/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68-20210607	SSHS-ISMP-B527 S68	6/7/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228231	Not Excavated	< 0.0014 U	0.22	< 0.0060 U	< 0.0052 U	< 0.0026 U	< 0.0029 U	< 0.01 U
Football Field	IRM5-FIS BOT 7	SSHS-IRM5-FIS BOT 7-20210613	SSHS-IRM5-FIS BOT 7	6/13/2021	-	--	-	840.19	10 - 12 ft	10 - 12 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S5	SSHS-IRM5-FIS S5-20210614	SSHS-IRM5-FIS S5	6/14/2021	-	854.28	-	844.04	10 - 12 ft	10.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S11	SSHS-IRM5-FIS S11-20210614	SSHS-IRM5-FIS S11	6/14/2021	-	854.55	-	844.14	10 - 12 ft	10.42 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S17	SSHS-IRM5-FIS S17-20210614	SSHS-IRM5-FIS S17	6/14/2021	-	855.24	-	844.51	10 - 12 ft	10.74 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S24	SSHS-IRM5-FIS S24-20210614	SSHS-IRM5-FIS S24	6/14/2021	-	854.65	-	842.68	10 - 12 ft	11.97 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-DUP 133-20210618	SSHS-IRM5-DUP 133	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S218	SSHS-IRM5-FIS S218-20210618	SSHS-IRM5-FIS S218	6/18/2021	-	853.31	-	843.15	10 - 12 ft	10.16 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS BOT 24	SSHS-IRM5-FIS BOT 24-20210618	SSHS-IRM5-FIS BOT 24	6/18/2021	-	853.22	-	842.39	10 - 12 ft	10.83 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S206	SSHS-IRM5-FIS S206-20210618	SSHS-IRM5-FIS S206	6/18/2021	-	853.15	-	842.98	10 - 12 ft	10.17 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S209	SSHS-IRM5-FIS S209-20210618	SSHS-IRM5-FIS S209	6/18/2021	-	853.40	-	843.26	10 - 12 ft	10.15 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86-20210623	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 0.0011 U	0.02	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87-20210623	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88-20210623	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90-20210624	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94-20210624	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 0.0011 U	0.0078 T	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92-20210624	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 0.0011 U	0.012	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93-20210624	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 0.0011 U	0.0074	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	IRM5-FIS-S298	SSHS-IRM5-FIS S298-20210821	SSHS-IRM5-FIS S298	8/21/2021	-	854.05	-	843.89	10 - 12 ft	10.17	1801261003	Not Excavated							
Football Field	IRM5-FIS-S299	SSHS-IRM5-FIS S299-20210821	SSHS-IRM5-FIS S299	8/21/2021	-	855.03	-	843.86	10 - 12 ft	11.17 ft	1801261003	Not Excavated							
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1-20210827	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 0.0014 U	< 0.0023 U	< 0.0060 U	< 0.0052 U	< 0.0026 U	< 0.0029 U	< 0.01 U
Football Field	IRM5-FIS BOT 54	SSHS-IRM5-FIS BOT54-20210916	SSHS-IRM5-FIS BOT54	9/16/2021	-	854.97	-	844.07	10 - 12 ft	10.89 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S322A	SSHS-IRM5-FIS S322A-20210916	SSHS-IRM5-FIS S322A	9/16/2021	-	854.95	-	844.56	10 - 12 ft	10.4 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S323A	SSHS-IRM5-FIS S323A-20210916	SSHS-IRM5-FIS S323A	9/16/2021	-	854.94	-	844.73	10 - 12 ft	10.21 ft	1801271981	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	0.057	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	0.026	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	0.043	< 0.00045 U	< 0.00041 U	< 0.00052 U	< 0.00028 U	< 0.0012 U	0.0026 J	< 0.00058 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	0.0099 J	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	0.082	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	0.011 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	0.09	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	0.089	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	0.016 J	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	0.028	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	0.11	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	0.011 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	0.025	0.0021 J	< 0.00041 U	< 0.00053 U	< 0.00028 U	< 0.0012 U	0.0013 J	< 0.00059 U
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	0.021	0.0036 J	< 0.00051 U	< 0.00066 U	< 0.00035 U	< 0.0015 U	0.0066	< 0.00073 U
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	0.0051 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	0.014 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	0.0055 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	0.015 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	0.0056 J	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	0.018 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	0.0064 J	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	0.012 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	0.016 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	0.007 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	0.0055 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	0.0091 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	0.0084 J	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	0.011 J	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	0.005 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.004 U	< 0.0025 U	< 0.0024 U	< 0.003 U	< 0.0033 U	< 0.0057 U	< 0.0038 U	< 0.0042 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	0.014 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	0.01 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	0.02	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	0.055	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.004 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0021 U	< 0.0023 U	< 0.004 U	< 0.0027 U	< 0.0029 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	0.0069 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	0.0055 J	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated								

DRAFT

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated						
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated						
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated						
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.002 U	< 0.0037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0036 U	< 0.034 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated							
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	< 0.00035 U	< 0.00033 U	< 0.00078 U	0.00097 J	< 0.00039 U	< 0.00052 U	< 0.00053 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.00036 U	< 0.00033 U	< 0.00078 U	< 0.00051 U	< 0.00039 U	0.0042 J	< 0.00053 U
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	< 0.00045 U	< 0.00041 U	< 0.00098 U	< 0.00064 U	< 0.00049 U	0.016	< 0.00067 U
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.002 U	< 0.003 U	< 0.0033 U	< 0.0027 U	< 0.0049 U	< 0.0015 U	< 0.0039 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0032 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U,*
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0014 U	< 0.0021 U	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0022 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	< 0.0019 U	< 0.00035 U	< 0.00035 U	< 0.00039 U	< 0.00063 U	< 0.00041 U	< 0.00057 U	< 0.00034 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	< 0.0025 U	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	0.0025 J	< 0.0029 U	< 0.0031 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	0.0037 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	0.0026 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	0.0012 J	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	< 0.0028 U	< 0.0032 U	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.0019 U	< 0.00035 U	< 0.00036 U	< 0.00039 U	< 0.00064 U	< 0.00041 U	< 0.00057 U	< 0.00034 U
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	< 0.0024 U	< 0.00043 U	< 0.00045 U	< 0.00049 U	< 0.0008 U	< 0.00051 U	< 0.00071 U	< 0.00042 U
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0042 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	0.0028 J	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.0025 U	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0034 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	0.0024 J	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	0.0024 J	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	0.0025 J	< 0.0029 U	< 0.0032 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	< 0.0026 U	< 0.0031 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	0.0027 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	< 0.0028 U	< 0.0033 U	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0023 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.003 U	< 0.0034 U	< 0.0037 U	< 0.0051 U	< 0.002 U	< 0.0013 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	< 0.0029 U	< 0.0033 U	< 0.0036 U	< 0.0049 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0023 U	< 0.0026 U	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0021 U	< 0.0024 U	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0009 U	< 0.0016 U	< 0.0013 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	0.0026 J	< 0.0029 U	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0024 U	< 0.0028 U	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	0.0026 J	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.0026 U	< 0.034 U	< 0.0033 U	< 0.0034 U	< 0.0028 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	< 0.0007 U	< 0.00085 U	< 0.00044 U	< 0.00053 U	< 0.00042 U	< 0.00025 U	< 0.0003 U	< 0.00048 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U	< 0.0025 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.0007 U	< 0.00086 U	< 0.00044 U	< 0.00053 U	< 0.00042 U	< 0.00025 U	< 0.00031 U	0.00066 J
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	< 0.00088 U	< 0.0011 U	< 0.00055 U	< 0.00067 U	< 0.00053 U	< 0.00032 U	< 0.00038 U	0.00077 J
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0025 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U	< 0.0026 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	< 0.0033 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0025 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.0036 U	< 0.005 U	< 0.002 U	< 0.0032 U	< 0.0031 U	< 0.002 U	< 0.0022 U	< 0.0027 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	< 0.0028 U	< 0.0038 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0015 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U	< 0.0026 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0022 U	< 0.0022 U	< 0.0014 U	< 0.0015 U	< 0.0019 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0036 U	< 0.034 U	< 0.0028 U	< 0.0022 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated								
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated								
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	< 0.00068 U	< 0.00072 U	< 0.00056 U	< 0.0032 U,*	0.00069 J	0.0057 J	< 0.00091 U	< 0.00038 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.0041 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.00068 U	< 0.00072 U	< 0.00056 U	< 0.0033 U	0.0064 J	0.0033 J	< 0.00092 U	< 0.00038 U
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	< 0.00085 U	< 0.0009 U	< 0.0007 U	< 0.0041 U	0.026	< 0.00084 U	< 0.0011 U	< 0.00048 U
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.0024 U	< 0.0053 U	< 0.0029 U	< 0.0074 U	< 0.0026 U	< 0.0037 U	< 0.0023 U	< 0.0046 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	< 0.0018 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0017 U	< 0.0037 U	< 0.002 U	< 0.0052 U	< 0.0019 U	< 0.0026 U	< 0.0016 U	< 0.0033 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated						
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated						
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated						
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.0023 U	< 0.034 U	< 0.003 U	< 0.0022 U	< 0.034 U	< 0.0038 U	< 0.034 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated							
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U	< 0.0027 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	< 0.00049 U	< 0.00037 U	< 0.00038 U	< 0.00048 U	< 0.00039 U	< 0.00052 U	< 0.00035 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0018 U	< 0.0027 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0024 U	< 0.0019 U	< 0.0029 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.00049 U	< 0.00037 U	< 0.00038 U	0.0071	< 0.00039 U	< 0.00052 U	< 0.00035 U
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	< 0.00061 U	< 0.00047 U	< 0.00048 U	0.007	< 0.00049 U	< 0.00065 U	< 0.00043 U
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.002 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0021 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0019 U	< 0.0029 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.002 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.002 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.002 U	< 0.0016 U	< 0.0024 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0025 U	< 0.0019 U	< 0.003 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0025 U	< 0.0021 U	< 0.0026 U	< 0.002 U	< 0.0032 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U	< 0.0024 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U	< 0.0024 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.0021 U	< 0.0025 U	< 0.002 U	< 0.0031 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.002 U	< 0.0016 U	< 0.0024 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0012 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0022 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0021 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0023 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-FIS-S325A	SSHS-IRM5-FIS S325A-20210916	SSHS-IRM5-FIS S325A	9/16/2021	-	854.98	-	844.32	10 - 12 ft	10.67 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S332	SSHS-IRM5-FIS S332-20210916	SSHS-IRM5-FIS S332	9/16/2021	-	855.08	-	843.94	10 - 12 ft	11.14 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S335	SSHS-IRM5-FIS S335-20210916	SSHS-IRM5-FIS S335	9/16/2021	-	855.08	-	843.62	10 - 12 ft	11.47 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-10-12	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-10-12	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.011 U
Football Field	IRM5-FIS-S355	SSHS-IRM5-FIS-S355-20211008	SSHS-IRM5-FIS-S355	10/8/2021	-	855.40	-	843.88	10 - 12 ft	11.52 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S363	SSHS-IRM5-FIS-S363-20211009	SSHS-IRM5-FIS-S363	10/9/2021	-	855.21	-	843.96	10 - 12 ft	11.26 ft	1801283151	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-12-14	SSHS-B451-SUB-12-14	9/27/2016	854.61	855.67	1.06	-	12 - 14 ft	13.06-15.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B625	021017 09:20 SSHS-B625-SUB-12-14	SSHS-B625-SUB-12-14	2/8/2017	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B627	021017 09:20 SSHS-B627-SUB-12-14	SSHS-B627-SUB-12-14	2/8/2017	856.12	856.36	0.24	-	12 - 14 ft	12.24-14.24 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-12-14	SSHS-B624-SUB-12-14	2/9/2017	855.38	855.50	0.12	-	12 - 14 ft	12.12-14.12 ft	180-63367-2	Not Excavated							
Football Field	SSHS-B628	021017 09:20 SSHS-B628-SUB-12-14	SSHS-B628-SUB-12-14	2/9/2017	855.84	855.84	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-12-14	SSHS-B629-SUB-12-14	2/9/2017	855.95	855.95	0.00	-	12 - 14 ft	12-14 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-12-14	SSHS-B621-SUB-12-14	2/13/2017	854.74	855.25	0.51	-	12 - 14 ft	12.51-14.51 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-12-14	SSHS-B651-SUB-12-14	2/14/2017	855.56	855.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-12-14	SSHS-B652-SUB-12-14	2/14/2017	855.55	855.58	0.03	-	12 - 14 ft	12.03-14.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-12-14	SSHS-B653-SUB-12-14	2/14/2017	855.63	855.62	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B656	021617 08:35 SSHS-B656-SUB-12-14	SSHS-B656-SUB-12-14	2/14/2017	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-63507-1	Not Excavated							
Football Field	SSHS-B683	032317 09:00 SSHS-B683-SUB-12-14	032317 09:00 SSHS-B683-SUB-12-14	3/22/2017	855.02	855.65	0.63	-	12 - 14 ft	12.63-14.63 ft	180-64526-1	Not Excavated							
Football Field	SSHS-B724	041317 08:55 SSHS-B724-SUB-12-14	SSHS-B724-SUB-12-14	4/12/2017	855.97	856.12	0.15	-	12 - 14 ft	12.15-14.15 ft	180-65174-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-12-14	SSHS-B2230-SUB-12-14	7/23/2018	856.03	856.03	0.00	-	12 - 14 ft	12-14 ft	180-80091-4	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-12-14	SSHS-B2231-SUB-12-14	7/23/2018	856.14	856.13	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80091-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-12-14	SSHS-B2234-SUB-12-14	7/23/2018	855.41	855.54	0.13	-	12 - 14 ft	12.13-14.13 ft	180-80091-2	Not Excavated	< 0.00057 U	< 0.0004 U	< 0.00086 U	< 0.00075 U	< 0.00051 U	< 0.00044 U	< 0.00084 U
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-12-14	SSHS-B2235-SUB-12-14	7/23/2018	855.30	855.51	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80091-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0025 U	< 0.0045 U
Football Field	SSHS-B2240	072418 08:50 SSHS-B2240-SUB-12-14	SSHS-B2240-SUB-12-14	7/23/2018	855.85	855.85	0.00	-	12 - 14 ft	12-14 ft	180-80091-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B2241	072418 08:50 SSHS-B2241-SUB-12-14	SSHS-B2241-SUB-12-14	7/23/2018	855.46	855.52	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2244	072418 08:50 SSHS-B2244-SUB-12-14	SSHS-B2244-SUB-12-14	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-3	Not Excavated	< 0.0026 U	< 0.0017 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2244	072418 08:50 PS-FD-1	PS-FD-1	7/23/2018	856.09	856.15	0.06	-	12 - 14 ft	12.06-14.06 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-12-14	SSHS-B2185-SUB-12-14	7/24/2018	855.07	855.49	0.42	-	12 - 14 ft	12.42-14.42 ft	180-80106-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-12-14	SSHS-B2187-SUB-12-14	7/24/2018	856.10	856.10	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-12-14	SSHS-B2188-SUB-12-14	7/24/2018	855.99	855.99	0.00	-	12 - 14 ft	12-14 ft	180-80106-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-12-14	SSHS-B2189-SUB-12-14	7/24/2018	855.74	855.90	0.16	-	12 - 14 ft	12.16-14.16 ft	180-80105-3	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-12-14	SSHS-B2191-SUB-12-14	7/24/2018	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-80105-3	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-12-14	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated	< 0.00057 U	< 0.0004 U	< 0.00087 U	< 0.00076 U	0.0066 J	0.0017 J	0.0083 J
Football Field	SSHS-B2198	072518 09:00 SSHS-B2198-SUB-12-14	SSHS-B2198-SUB-12-14	7/24/2018	855.05	855.51	0.46	-	12 - 14 ft	12.46-14.46 ft	180-80105-2	Not Excavated	< 0.00071 U	< 0.0005 U	< 0.0011 U	< 0.00094 U	0.0063 J	0.0024 J	0.0087 J
Football Field	SSHS-B2221	072518 09:00 SSHS-B2221-SUB-12-14	SSHS-B2221-SUB-12-14	7/24/2018	855.38	855.38	0.00	-	12 - 14 ft	12-14 ft	180-80106-1	Not Excavated	< 0.0025 U	0.0024 J	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-12-14	SSHS-B2232-SUB-12-14	7/24/2018	856.82	856.82	0.00	-	12 - 14 ft	12-14 ft	180-80105-2	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-12-14	SSHS-B2233-SUB-12-14	7/24/2018	854.83	855.35	0.52	-	12 - 14 ft	12.52-14.52 ft	180-80105-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Football Field	SSHS-B2245	072518 09:00 PS-FD-13	PS-FD-13	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0024 U	0.0042 J	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-12-14	SSHS-B2245-SUB-12-14	7/24/2018	855.25	855.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-80106-1	Not Excavated	< 0.0025 U	0.01	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-12-14	SSHS-B2070-SUB-12-14	7/25/2018	854.72	855.22	0.50	-	12 - 14 ft	12.5-14.5 ft	180-80157-3	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B2072	072618 08:50 SSHS-B2072-SUB-12-14	SSHS-B2072-SUB-12-14	7/25/2018	856.82	856.83	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80154-2	Not Excavated	< 0.0025 U	0.0047 J	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2073	072618 08:50 SSHS-B2073-SUB-12-14	SSHS-B2073-SUB-12-14	7/25/2018	856.99	856.99	0.00	-	12 - 14 ft	12-14 ft	180-80157-3	Not Excavated	< 0.0027 U	0.0045 J	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-12-14	SSHS-B2089-SUB-12-14	7/25/2018	855.40	855.39	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80157-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-12-14	SSHS-B2091-SUB-12-14	7/25/2018	856.61	856.61	0.00	-	12 - 14 ft	12-14 ft	180-80154-1	Not Excavated	< 0.0028 U	0.011	< 0.0017 U	< 0.0042 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-12-14	SSHS-B2108-SUB-12-14	7/25/2018	855.64	855.64	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-12-14	SSHS-B2109-SUB-12-14	7/25/2018	855.25	855.48	0.23	-	12 - 14 ft	12.23-14.23 ft	180-80154-1	Not Excavated	< 0.0024 U	0.0042 J	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-12-14	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0048 U
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-12-14	SSHS-B2127-SUB-12-14	7/25/2018	855.91	855.91	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-12-14	SSHS-B2128-SUB-12-14	7/25/2018	856.01	856.01	0.00	-	12 - 14 ft	12-14 ft	180-80157-1	Not Excavated	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-12-14	SSHS-B2129-SUB-12-14	7/25/2018	855.33	855.52	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80157-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-12-14	SSHS-B2143-SUB-12-14	7/25/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80154-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-12-14	SSHS-B2216-SUB-12-14	7/25/2018	855.16	855.46	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80154-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-12-14	SSHS-B2025-SUB-12-14	7/26/2018	854.55	854.52	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-80225-3	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-12-14	SSHS-B2026-SUB-12-14	7/26/2018	855.26	855.47	0.21	-	12 - 14 ft	12.21-14.21 ft	180-80227-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2027	072718 09:00 SSHS-B2027-SUB-12-14	SSHS-B2027-SUB-12-14	7/26/2018	855.22	855.52	0.30	-	12 - 14 ft	12.3-14.3 ft	180-80227-1	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-12-14	SSHS-B2028-SUB-12-14	7/26/2018	855.23	855.54	0.31	-	12 - 14 ft	12.31-14.31 ft	180-80227-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-12-14	SSHS-B2050-SUB-12-14	7/26/2018	855.45	855.45	0.00	-	12 - 14 ft	12-14 ft	180-80225-2	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-12-14	SSHS-B2192-SUB-12-14	7/26/2018	855.49	855.50	0.01	-	12 - 14 ft	12.01-14.01 ft	180-80225-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-12-14	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-12-14	SSHS-B2213-SUB-12-14	7/26/2018	855.06	855.53	0.47	-	12 - 14 ft	12.47-14.47 ft	180-80225-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0046 U	< 0.0024 U	< 0.0031 U	< 0.0054 U
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-12-14	SSHS-B2214-SUB-12-14	7/26/2018	855.14	855.34	0.20	-	12 - 14 ft	12.2-14.2 ft	180-80227-3	Not Excavated	< 0.0023 U	0.0043 J	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-12-14	SSHS-B2215-SUB-12-14	7/26/2018	855.11	855.30	0.19	-	12 - 14 ft	12.19-14.19 ft	180-80227-2	Not Excavated	< 0.0023 U	0.002 J	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2223	072718 09:00 SSHS-B2223-SUB-12-14	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-12-14	SSHS-B2226-SUB-12-14	7/26/2018	856.56	856.56	0.00	-	12 - 14 ft	12-14 ft	180-80227-1	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0052 U
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-12-14	SSHS-B2032-SUB-12-14	7/27/2018	854.88	855.51	0.63	-	12 - 14 ft	12.63-14.63 ft	180-80251-2	Not Excavated	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-12-14	SSHS-B2033-SUB-12-14	7/27/2018	854.70	855.74	1.04	-	12 - 14 ft	13.04-15.04 ft	180-80251-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0038 U
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-12-14	SSHS-B2051-SUB-12-14	7/27/2018	855.08	855.37	0.29	-	12 - 14 ft	12.29-14.29 ft	180-80251-1	Not Excavated	< 0.0026 U	0.0043 J	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-12-14	SSHS-B2071-SUB-12-14	7/27/2018	856.16	856.16	0.00	-	12 - 14 ft	12-14 ft	180-80251-2	Not Excavated	< 0.0025 U	0.024	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-12-14	SSHS-B2090-SUB-12-14	7/27/2018	855.97	855.96	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80251-3	Not Excavated	< 0.0025 U	0.0059	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-12-14	SSHS-B2217-SUB-12-14	7/27/2018	855.08	855.32	0.24	-	12 - 14 ft	12.24-14.24 ft	180-80251-3	Not Excavated	< 0.0027 U	0.0019 J	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-12-14	SSHS-B2228-SUB-12-14	7/27/2018	855.33	855.33	0.00	-	12 - 14 ft	12-14 ft	180-80252-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-12-14	SSHS-B2534-SUB-12-14	10/30/2018	855.61	855.76	0.15	-	12 - 14 ft	12.15-14.15 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-12-14	SSHS-B2747-SUB-12-14	4/23/2019	856.08	856.07	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-89344-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2724	042519 08:35_SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated							
Football Field	SSHS-B2756	042819 10:00_PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2756	042819 10:00_SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2759	042819 10:00_SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-IRM3-B012	072019 09:15_SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B009	080319 09:30_SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S158	080319 09:30_SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B014	080619 09:00_SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B021	080619 09:00_SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S141	080619 09:00_SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S142	080619 09:00_SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S144	080619 09:00_SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S146	080619 09:00_SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S148	080619 09:00_SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S149	080619 09:00_SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S155	080619 09:00_SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S159	080619 09:00_SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S160	080619 09:00_SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S161	080619 09:00_SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S162	080619 09:00_SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated							
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated							
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated							
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated							
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated							
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated							
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated							
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated							
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated							
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated							
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated							
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated							
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated							
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated							
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated							
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated							
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated							
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated							
Football Field	SSHS-B3459	090120 10:30_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated							
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated							
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated							
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated							
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated							
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated							
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/3/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated							
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated							
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated							
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated							
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2724	042519 08:35_SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated						
Football Field	SSHS-B2756	042819 10:00_PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2756	042819 10:00_SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2759	042819 10:00_SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-IRM3-B012	072019 09:15_SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B009	080319 09:30_SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S158	080319 09:30_SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B014	080619 09:00_SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B021	080619 09:00_SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S141	080619 09:00_SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S142	080619 09:00_SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S144	080619 09:00_SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S146	080619 09:00_SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S148	080619 09:00_SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S149	080619 09:00_SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S155	080619 09:00_SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S159	080619 09:00_SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S160	080619 09:00_SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S161	080619 09:00_SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S162	080619 09:00_SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated							
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated							
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated							
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated							
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated							
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated							
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated							
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated							
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated							
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated							
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated							
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated							
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated							
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated							
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated							
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated							
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated							
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated							
Football Field	SSHS-B3459	090120 10:30_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated							
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated							
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated							
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated							
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated							
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated							
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/2/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UJ	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UJ	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UJ	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated							
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated							
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated							
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated							
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2724	042519 08:35 SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated							
Football Field	SSHS-B2756	042819 10:00 PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2756	042819 10:00 SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2759	042819 10:00 SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-IRM3-B012	072019 09:15 SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B009	080319 09:30 SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S158	080319 09:30 SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B014	080619 09:00 SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B021	080619 09:00 SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S141	080619 09:00 SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S142	080619 09:00 SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S144	080619 09:00 SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S146	080619 09:00 SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S148	080619 09:00 SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S149	080619 09:00 SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S155	080619 09:00 SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S159	080619 09:00 SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S160	080619 09:00 SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S161	080619 09:00 SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S162	080619 09:00 SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated							
Football Field	SSHS-B2976	110919 09:30 SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated							
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated							
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated							
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated							
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated							
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	0.008	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated							
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated							
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated							
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated							
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated							
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated							
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated							
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated							
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated							
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated							
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated							
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated							
Football Field	SSHS-B3459	090120 10:30 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated							
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated							
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated							
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated							
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated							
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated							
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/2/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 UJ	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 UJ	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.0047 U	< 0.0014 UJ	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated							
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated							
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated							
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated							
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2724	042519 08:35 SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated							
Football Field	SSHS-B2756	042819 10:00 PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2756	042819 10:00 SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2759	042819 10:00 SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-IRM3-B012	072019 09:15 SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B009	080319 09:30 SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S158	080319 09:30 SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B014	080619 09:00 SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-B021	080619 09:00 SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S141	080619 09:00 SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S142	080619 09:00 SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S144	080619 09:00 SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S146	080619 09:00 SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S148	080619 09:00 SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S149	080619 09:00 SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S155	080619 09:00 SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S159	080619 09:00 SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S160	080619 09:00 SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S161	080619 09:00 SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S162	080619 09:00 SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated								
Football Field	SSHS-B2976	110919 09:30 SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated								
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated								
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated								
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated								
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated								
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated								
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated								
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated								
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated								
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated								
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated								
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated								
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated								
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated								
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated								
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated								
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated								
Football Field	SSHS-B3459	090120 10:30 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated								
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated								
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated								
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated								
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated								
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated								
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated								
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated								
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated								
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/2/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated								
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated								
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated								
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated								
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated								

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2724	042519 08:35 SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated								
Football Field	SSHS-B2756	042819 10:00 PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated								
Football Field	SSHS-B2756	042819 10:00 SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated								
Football Field	SSHS-B2759	042819 10:00 SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-IRM3-B012	072019 09:15 SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B009	080319 09:30 SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S158	080319 09:30 SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B014	080619 09:00 SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-B021	080619 09:00 SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S141	080619 09:00 SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S142	080619 09:00 SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S144	080619 09:00 SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S146	080619 09:00 SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S148	080619 09:00 SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S149	080619 09:00 SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S155	080619 09:00 SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S159	080619 09:00 SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S160	080619 09:00 SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S161	080619 09:00 SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S162	080619 09:00 SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated								
Football Field	SSHS-B2976	110919 09:30 SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated								
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated								
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated								
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated								
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated								
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated								
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated								
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated								
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated								
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated								
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated								
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated								
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated								
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated								
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated								
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated								
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated								
Football Field	SSHS-B3459	090120 10:30 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated								
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated								
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated								
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated								
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated								
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated								
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated								
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated								
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated								
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/2/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated								
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated								
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated								
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated								
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2753	042419 09:00 SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2724	042519 08:35 SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated						
Football Field	SSHS-B2756	042819 10:00 PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2756	042819 10:00 SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2759	042819 10:00 SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Football Field	SSHS-IRM3-B012	072019 09:15 SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated						
Football Field	SSHS-IRM3-B009	080319 09:30 SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-S158	080319 09:30 SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-B014	080619 09:00 SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-B020	080619 09:00 SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-B021	080619 09:00 SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated						
Football Field	SSHS-IRM3-S141	080619 09:00 SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated						
Football Field	SSHS-IRM3-S142	080619 09:00 SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated						
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S143	080619 09:00 SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S144	080619 09:00 SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S146	080619 09:00 SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated						
Football Field	SSHS-IRM3-S148	080619 09:00 SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S149	080619 09:00 SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S155	080619 09:00 SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S159	080619 09:00 SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated						
Football Field	SSHS-IRM3-S160	080619 09:00 SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S161	080619 09:00 SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S162	080619 09:00 SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated						
Football Field	SSHS-B2976	110919 09:30 SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated						
Football Field	SSHS-B2977	110919 09:30 SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated						
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated						
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated						
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated						
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated						
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated						
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated						
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated						
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated						
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated						
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated						
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated						
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated						
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated						
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated						
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated						
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated						
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated						
Football Field	SSHS-B3459	090120 10:30 SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated						
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated						
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated						
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated						
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated						
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated						
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated						
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated						
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated						
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated						
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated						
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/2/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ	< 0.0018 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated						
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated						
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated						
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated						
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2753	042419 09:00_SSHS-B2753-SUB-12-14	SSHS-B2753-SUB-12-14	4/23/2019	856.56	856.57	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-12-14	SSHS-B2767-SUB-12-14	4/23/2019	856.06	856.06	0.00	-	12 - 14 ft	12-14 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2724	042519 08:35_SSHS-B2724-SUB-12-14	SSHS-B2724-SUB-12-14	4/24/2019	855.34	855.35	0.01	-	12 - 14 ft	12.01-14.01 ft	180-89408-2	Not Excavated							
Football Field	SSHS-B2756	042819 10:00_PS-FD-14	PS-FD-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2756	042819 10:00_SSHS-B2756-SUB-12-14	SSHS-B2756-SUB-12-14	4/26/2019	856.39	856.41	0.02	-	12 - 14 ft	12.02-14.02 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2759	042819 10:00_SSHS-B2759-SUB-12-14	SSHS-B2759-SUB-12-14	4/26/2019	856.32	856.44	0.12	-	12 - 14 ft	12.12-14.12 ft	180-89521-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00_SSHS-B2762-SUB-12-14	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated	< 0.0027 U	0.0024 J	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0048 U
Football Field	SSHS-IRM3-B012	072019 09:15_SSHS-IRM3-B012	SSHS-IRM3-B012	7/19/2019	-	856.09	-	842.85	12 - 14 ft	13.24 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B009	080319 09:30_SSHS-IRM3-B009-C	SSHS-IRM3-B009-C	8/2/2019	-	856.15	-	842.56	12 - 14 ft	13.59 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S158	080319 09:30_SSHS-IRM3-S158-C	SSHS-IRM3-S158-C	8/2/2019	-	855.76	-	842.46	12 - 14 ft	13.3 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B014	080619 09:00_SSHS-IRM3-B014-C	SSHS-IRM3-B014-C	8/5/2019	-	856.04	-	842.31	12 - 14 ft	13.73 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-B020-C	SSHS-IRM3-B020-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B020	080619 09:00_SSHS-IRM3-DUP2-C	SSHS-IRM3-DUP2-C	8/5/2019	-	856.04	-	843.18	12 - 14 ft	12.86 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-B021	080619 09:00_SSHS-IRM3-B021-C	SSHS-IRM3-B021-C	8/5/2019	-	855.76	-	842.45	12 - 14 ft	13.31 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S141	080619 09:00_SSHS-IRM3-S141-C	SSHS-IRM3-S141-C	8/5/2019	-	855.70	-	842.27	12 - 14 ft	13.43 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S142	080619 09:00_SSHS-IRM3-S142-C	SSHS-IRM3-S142-C	8/5/2019	-	855.66	-	843.00	12 - 14 ft	12.66 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-DUP12-C	SSHS-IRM3-DUP12-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S143	080619 09:00_SSHS-IRM3-S143-C	SSHS-IRM3-S143-C	8/5/2019	-	855.71	-	843.17	12 - 14 ft	12.54 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S144	080619 09:00_SSHS-IRM3-S144-C	SSHS-IRM3-S144-C	8/5/2019	-	855.89	-	843.26	12 - 14 ft	12.63 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S146	080619 09:00_SSHS-IRM3-S146-D	SSHS-IRM3-S146-D	8/5/2019	-	855.97	-	842.38	12 - 14 ft	13.59 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S148	080619 09:00_SSHS-IRM3-S148-D	SSHS-IRM3-S148-D	8/5/2019	-	856.35	-	844.13	12 - 14 ft	12.22 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S149	080619 09:00_SSHS-IRM3-S149-D	SSHS-IRM3-S149-D	8/5/2019	-	856.40	-	842.34	12 - 14 ft	14.06 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S155	080619 09:00_SSHS-IRM3-S155-C	SSHS-IRM3-S155-C	8/5/2019	-	856.22	-	843.53	12 - 14 ft	12.69 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S159	080619 09:00_SSHS-IRM3-S159-C	SSHS-IRM3-S159-C	8/5/2019	-	855.72	-	841.84	12 - 14 ft	13.88 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S160	080619 09:00_SSHS-IRM3-S160-C	SSHS-IRM3-S160-C	8/5/2019	-	855.68	-	841.66	12 - 14 ft	14.02 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S161	080619 09:00_SSHS-IRM3-S161-C	SSHS-IRM3-S161-C	8/5/2019	-	855.74	-	842.52	12 - 14 ft	13.22 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S162	080619 09:00_SSHS-IRM3-S162-C	SSHS-IRM3-S162-C	8/5/2019	-	855.88	-	843.11	12 - 14 ft	12.77 ft	180-93683-2	Not Excavated							
Football Field	SSHS-B2976	110919 09:30_SSHS-B2976-SUB-12-14	SSHS-B2976-SUB-12-14	11/7/2019	854.56	854.87	0.31	-	12 - 14 ft	12 - 14 ft	180-98520-1	Not Excavated							
Football Field	SSHS-B2977	110919 09:30_SSHS-B2977-SUB-12-14	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S148	SSHS-IRM4-S148-10-12-20200723	SSHS-IRM4-S148-10-12	7/23/2020	-	855.64	-	842.70	12 - 14 ft	12.95 ft	1801086951	Not Excavated							
Football Field	IRM4-S147	SSHS-IRM4-S147-10-12-20200723	SSHS-IRM4-S147-10-12	7/23/2020	-	855.64	-	843.38	12 - 14 ft	12.27 ft	1801086951	Not Excavated							
Football Field	IRM4-B008	SSHS-IRM4-B008-20200724	SSHS-IRM4-B008	7/24/2020	-	855.66	-	842.18	12 - 14 ft	13.48 ft	1801087891	Not Excavated							
Football Field	IRM4-S171	SSHS-IRM4-S171-12-14-20200724	SSHS-IRM4-S171-12-14	7/24/2020	-	855.64	-	841.69	12 - 14 ft	13.95 ft	1801087881	Not Excavated							
Football Field	IRM4-S172	SSHS-IRM4-S172-12-14-20200724	SSHS-IRM4-S172-12-14	7/24/2020	-	855.64	-	841.85	12 - 14 ft	13.79 ft	1801087881	Not Excavated							
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	7/27/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-108826-3	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-12-14	SSHS-B3461-SUB-12-14	7/27/2020	856.51	856.51	0.00	-	12 - 14 ft	12-14 ft	180-108826-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	IRM4-S160	SSHS-IRM4-S160-12-14-20200727	SSHS-IRM4-S160-12-14	7/27/2020	-	855.53	-	843.33	12 - 14 ft	12.2 ft	1801088061	Not Excavated							
Football Field	IRM4-S179	SSHS-IRM4-S179-14-16-20200728	SSHS-IRM4-S179-14-16	7/28/2020	-	855.30	-	841.41	12 - 14 ft	13.89 ft	1801088411	Not Excavated							
Football Field	IRM4-S159	SSHS-IRM4-S159-12-14-20200728	SSHS-IRM4-S159-12-14	7/28/2020	-	855.38	-	843.19	12 - 14 ft	12.19 ft	1801088411	Not Excavated							
Football Field	IRM4-S143BOT	SSHS-IRM4-S143-BOT-12-14-20200803	SSHS-IRM4-S143-BOT-12-14	8/3/2020	-	855.81	-	842.33	12 - 14 ft	13.48 ft	1801090931	Not Excavated							
Football Field	IRM4-S143D	SSHS-IRM4-S143D-12-14-20200803	SSHS-IRM4-S143D-12-14	8/3/2020	-	855.93	-	843.38	12 - 14 ft	12.55 ft	1801090931	Not Excavated							
Football Field	IRM4-S143E	SSHS-IRM4-S143E-12-14-20200803	SSHS-IRM4-S143E-12-14	8/3/2020	-	855.76	-	843.06	12 - 14 ft	12.7 ft	1801090931	Not Excavated							
Football Field	IRM4-B007BOT	SSHS-IRM4-B007-BOT-10-12-20200803	SSHS-IRM4-B007-BOT-10-12	8/3/2020	-	855.51	-	841.76	12 - 14 ft	13.75 ft	1801090932	Not Excavated							
Football Field	IRM4-B007A	SSHS-IRM4-B007A-10-12-20200803	SSHS-IRM4-B007A-10-12	8/3/2020	-	855.62	-	843.22	12 - 14 ft	12.4 ft	1801090932	Not Excavated							
Football Field	IRM4-B007B	SSHS-IRM4-B007B-10-12-20200803	SSHS-IRM4-B007B-10-12	8/3/2020	-	855.43	-	843.00	12 - 14 ft	12.43 ft	1801090932	Not Excavated							
Football Field	IRM4-S174BOT	SSHS-IRM4-S174-BOT-12-14-20200805	SSHS-IRM4-S174-BOT-12-14	8/5/2020	-	855.61	-	841.90	12 - 14 ft	13.71 ft	1801092181	Not Excavated							
Football Field	IRM4-S174A	SSHS-IRM4-S174A-12-14-20200805	SSHS-IRM4-S174A-12-14	8/5/2020	-	855.65	-	843.09	12 - 14 ft	12.56 ft	1801092181	Not Excavated							
Football Field	IRM4-S174B	SSHS-IRM4-S174B-12-14-20200805	SSHS-IRM4-S174B-12-14	8/5/2020	-	855.56	-	842.38	12 - 14 ft	13.18 ft	1801092181	Not Excavated							
Football Field	SSHS-B3459	090120 10:30_SSHS-B3459-SUB-12-14	SSHS-B3459-SUB-12-14	8/31/2020	856.30	856.31	0.01	-	12 - 14 ft	12.01-14.01 ft	180-110264-1	Not Excavated							
Football Field	IRM4A-S165	SSHS-IRM4A-S165-20201012	SSHS-IRM4A-S165	10/12/2020	-	855.88	-	843.04	12 - 14 ft	12.84 ft	1801121381	Not Excavated							
Football Field	IRM4A-S166	SSHS-IRM4A-S166-20201012	SSHS-IRM4A-S166	10/12/2020	-	856.18	-	842.53	12 - 14 ft	13.65 ft	1801121381	Not Excavated							
Football Field	IRM4A-S167	SSHS-IRM4A-S167-20201012	SSHS-IRM4A-S167	10/12/2020	-	855.82	-	842.26	12 - 14 ft	13.57 ft	1801121381	Not Excavated							
Football Field	IRM4A-SSUMP	SSHS-IRM4A-SSUMP-20201012	SSHS-IRM4A-SSUMP	10/12/2020	-	856.00	-	843.93	12 - 14 ft	12.07 ft	1801121381	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-DUP8-20201019	SSHS-IRM4A-DUP8	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S147	SSHS-IRM4A-S147-20201019	SSHS-IRM4A-S147	10/19/2020	-	855.55	-	843.52	12 - 14 ft	12.04 ft	1801124481	Not Excavated							
Football Field	IRM4A-S168	SSHS-IRM4A-S168-20201019	SSHS-IRM4A-S168	10/19/2020	-	855.59	-	842.26	12 - 14 ft	13.34 ft	1801124481	Not Excavated							
Football Field	IRM4A-S169	SSHS-IRM4A-S169-20201019	SSHS-IRM4A-S169	10/19/2020	-	855.59	-	841.94	12 - 14 ft	13.65 ft	1801124481	Not Excavated							
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-12-14	SSHS-B3566-SUB-12-14	1/12/2021	855.28	855.43	0.15	-	12 - 14 ft	12.15-14.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-12-14	SSHS-B3567-SUB-12-14	1/12/2021	855.39	855.47	0.08	-	12 - 14 ft	12.08-14.08 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-12-14	SSHS-B3575-SUB-12-14	2/2/2021	854.85	855.40	0.55	-	12 - 14 ft	12.55-14.55 ft	180-116724-1	Not Excavated	< 0.0011 U	0.0037 J	< 0.0046 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-12-14	SSHS-B3573-SUB-12-14	2/3/2021	855.66	855.66	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-12-14	SSHS-B3574-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0022 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-12-14	SSHS-B3576-SUB-12-14	2/3/2021	855.76	855.76	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-12-14	SSHS-B3578-SUB-12-14	2/3/2021	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0021 J	< 0.0048 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-12-14	SSHS-B3572-SUB-12-14	2/4/2021	855.42	855.51	0.09	-	12 - 14 ft	12.09-14.09 ft	180-116864-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-12-14	SSHS-B3580-SUB-12-14	2/5/2021	856.23	856.24	0.01	-	12 - 14 ft	12.01-14.01 ft	180-116914-1	Not Excavated	< 0.0011 U	0.017 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-12-14	SSHS-B3581-SUB-12-14	2/5/2021	856.18	856.18	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.001 U	0.017	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-12-14	SSHS-B3582-SUB-12-14	2/5/2021	855.93	855.93	0.00	-	12 - 14 ft	12-14 ft	180-116914-1	Not Excavated	< 0.0011 U	0.025	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-12-14	SSHS-B3583-SUB-12-14	2/5/2021	855.33	855.44	0.11	-	12 - 14 ft	12.11-14.11 ft	180-116914-1	Not Excavated	< 0.001 U	0.0065	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	IRM4A-S150	SSHS-IRM4A-S150-10-12-20210208	SSHS-IRM4A-S150-10-12	2/8/2021	-	855.37	-	843.18	12 - 14 ft	12.19 ft	1801169471	Not Excavated							
Football Field	IRM4A-S177	SSHS-IRM4A-S177-12-14-20210208	SSHS-IRM4A-S177-12-14	2/8/2021	-	855.38	-	843.31	12 - 14 ft	12.07 ft	1801169472	Not Excavated							
Football Field	IRM4A-S157BOT	SSHS-IRM4A-S157 BOT-20210302	SSHS-IRM4A-S157 BOT	3/2/2021	-	855.47	-	842.79	12 - 14 ft	12.69 ft	1801177752	Not Excavated							
Football Field	IRM4A-S149A	SSHS-IRM4A-S149A-20210303	SSHS-IRM4A-S149A	3/3/2021	-	855.37	-	841.88	12 - 14 ft	13.49 ft	1801178551	Not Excavated							
Football Field	IRM5-B254	SSHS-IRM5-DUP20-20210317	SSHS-IRM5-DUP20	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated							
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0042 U	< 0.0021 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated								
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated								
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated								
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated								
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated								
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated								
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated								
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated								
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated								
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	0.0055 J	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	0.0072 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0064 U	< 0.0023 U	< 0.0049 U	< 0.0038 U	< 0.0041 U	< 0.0037 U	< 0.0065 U	< 0.0033 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0064 U	< 0.0023 U	< 0.0049 U	< 0.0038 U	< 0.0041 U	< 0.0037 U	< 0.0065 U	< 0.0033 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated								
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	0.023 J	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated								
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated								
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated						
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated						
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 UT	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated							
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated							
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated							
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated							
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated							
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated							
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated							
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated							
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated							
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated							
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated							
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated							
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated							
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 UT
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 UT
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0021 U	< 0.0040 U	< 0.0048 U	< 0.0026 U	< 0.0032 U	< 0.0039 U	< 0.0053 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0021 U	< 0.0040 U	< 0.0048 U	< 0.0026 U	< 0.0032 U	< 0.0039 U	< 0.0053 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 UT
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated							
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated							
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated							
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated							
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated							
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated							
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated							
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated							
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated								
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated								
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated								
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated								
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated								
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated								
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated								
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated								
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated								
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 UT	< 0.0036 UT	< 0.0017 UT	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 UT	< 0.0034 UT	< 0.0017 UT	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0074 U	< 0.0022 U	< 0.0041 U	< 0.0027 U	< 0.0050 U	< 0.0024 U	< 0.0026 U	< 0.0024 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0074 U	< 0.0022 U	< 0.0041 U	< 0.0027 U	< 0.0050 U	< 0.0024 U	< 0.0026 U	< 0.0023 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 UT	< 0.0036 UT	< 0.0018 UT	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated								
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	0.0063	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	0.0058	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated								
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated								
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated							
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated								
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated								
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated								
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated								
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated								
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated								
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated								
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated								
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated								
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0037 U	< 0.0067 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0036 U	< 0.0037 U	< 0.0030 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0037 U	< 0.0067 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0036 U	< 0.0037 U	< 0.0030 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0025 U	0.0054 J	0.0054	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated								
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated								
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated								
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated								
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated								
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated								
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated								
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated								
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated								
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated								
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated								
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated								
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated								
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated								
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated								
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0033 U	< 0.0026 U	< 0.0042 U	< 0.012 U	< 0.0039 U	< 0.0041 U	< 0.0030 U	< 0.0024 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0033 U	< 0.0026 U	< 0.0042 U	< 0.012 U	< 0.0039 U	< 0.0041 U	< 0.0030 U	< 0.0024 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated								
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0023 U	< 0.0018 U	0.0074	< 0.0086 U	0.0048 J	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated								
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated								
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated								
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated								
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated								
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated								
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated								
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated								
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated								
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated						
Football Field	IRM4A-S131B0T1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated						
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated							
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.58	12 - 14 ft	12.35 ft	1801199181	Not Excavated							
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated							
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated							
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated							
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated							
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated							
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated							
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated							
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated							
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated							
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated							
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated							
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 UT	< 0.0029 UT	< 0.0019 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 UT	< 0.0028 UT	< 0.0018 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0024 U	< 0.0025 U	< 0.0033 U	< 0.0024 U	< 0.0045 U	< 0.0041 U	< 0.0027 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0024 U	< 0.0025 U	< 0.0033 U	< 0.0023 U	< 0.0045 U	< 0.0041 U	< 0.0027 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 UT	< 0.0030 UT	< 0.0020 U
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated							
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated							
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated							
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated							
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated							
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated							
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated							
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B254	SSHS-IRM5-B254-20210317	SSHS-IRM5-B254	3/17/2021	-	855.25	-	843.17	12 - 14 ft	12.08 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131BOT1C	SSHS-IRM4A-S131DBOT1C-20210319	SSHS-IRM4A-S131DBOT1C	3/19/2021	-	855.67	-	843.65	12 - 14 ft	12.01 ft	1801187461	Not Excavated							
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2-20210330	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	IRM5-B700C	SSHS-IRM5-B700C-20210413	SSHS-IRM5-B700C	4/13/2021	-	855.40	-	843.27	12 - 14 ft	12.13 ft	1801199181	Not Excavated							
Football Field	IRM5-B700 BOT1	SSHS-IRM5-B700 BOT 1-20210413	SSHS-IRM5-B700 BOT 1	4/13/2021	-	855.33	-	842.38	12 - 14 ft	12.35 ft	1801199181	Not Excavated							
Football Field	IRM5-B700B BOT 1	SSHS-IRM5-B700 BOT 1-20210418	SSHS-IRM5-B700 BOT 1	4/18/2021	-	855.33	-	842.98	12 - 14 ft	12.35 ft	1801201972	Not Excavated							
Football Field	IRM5-B700B BOT2	SSHS-IRM5-B700 BOT 2-20210418	SSHS-IRM5-B700 BOT 2	4/18/2021	-	855.36	-	843.29	12 - 14 ft	12.07 ft	1801201972	Not Excavated							
Football Field	IRM5-B254A	SSHS-IRM5-B254A-20210422	SSHS-IRM5-B254A	4/22/2021	-	855.24	-	842.70	12 - 14 ft	12.54 ft	1801204573	Not Excavated							
Football Field	IRM5-DW4BOT	SSHS-IRM5-DW4 BOT-20210423	SSHS-IRM5-DW4 BOT	4/23/2021	-	855.61	-	843.20	12 - 14 ft	12.41 ft	1801205491	Not Excavated							
Football Field	IRM5-A4V E	SSHS-IRM5-A4V E-20210423	SSHS-IRM5-A4V E	4/23/2021	-	855.48	-	842.56	12 - 14 ft	12.92 ft	1801205491	Not Excavated							
Football Field	IRM5-P18 7 BOT 7	SSHS-IRM5-P187 BOT 7-20210508	SSHS-IRM5-P187 BOT 7	5/8/2021	-	855.78	-	843.77	12 - 14 ft	12.01 ft	1801213861	Not Excavated							
Football Field	IRM5-PIPE 51 BOT 3	SSHS-IRM5-PIPE 51 BOT 3-20210519	SSHS-IRM5-PIPE 51 BOT 3	5/19/2021	-	855.67	-	842.86	12 - 14 ft	12.81 ft	1801218701	Not Excavated							
Football Field	IRM5-P18 7 S13	SSHS-IRM5-P187 S13-20210520	SSHS-IRM5-P187 S13	5/20/2021	-	855.73	-	843.51	12 - 14 ft	12.22 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S14	SSHS-IRM5-P187 S14-20210520	SSHS-IRM5-P187 S14	5/20/2021	-	855.73	-	842.02	12 - 14 ft	13.71 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S16	SSHS-IRM5-P187 S16-20210520	SSHS-IRM5-P187 S16	5/20/2021	-	855.85	-	843.60	12 - 14 ft	12.26 ft	1801219611	Not Excavated							
Football Field	IRM5-P18 7 S17	SSHS-IRM5-P187 S17-20210520	SSHS-IRM5-P187 S17	5/20/2021	-	855.86	-	842.26	12 - 14 ft	13.6 ft	1801219611	Not Excavated							
Football Field	IRM5-S234A S14	SSHS-IRM5-S234A S14-20210521	SSHS-IRM5-S234A S14	5/21/2021	-	855.62	-	843.25	12 - 14 ft	12.37 ft	1801220741	Not Excavated							
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-DUP 114-20210526	SSHS-IRM5-DUP 114	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated							
Football Field	IRM5-BRAVO BOT 7	SSHS-IRM5-BRAVO BOT 7-20210526	SSHS-IRM5-BRAVO BOT 7	5/26/2021	-	855.36	-	842.48	12 - 14 ft	12.88 ft	1801222611	Not Excavated							
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6-20210527	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5-20210527	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5-20210527	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6-20210527	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6-20210527	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6-20210527	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11-20210602	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12-20210602	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19-20210602	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 0.0011 U	0.0020 J	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26-20210603	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 0.0016 U	0.051	< 0.0068 U	< 0.0059 U	< 0.0029 U	< 0.0033 U	< 0.012 U
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33-20210603	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 0.0016 U	0.0026 J	< 0.0068 U	< 0.0059 U	< 0.0029 U	< 0.0033 U	< 0.012 U
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38-20210603	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 0.0011 U	0.019	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B539	SSHS-ISMP-B539-20210604	SSHS-ISMP-B539	6/4/2021	-	855.58	-	843.07	12 - 14 ft	12.51 ft	1801227322	Not Excavated							
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210605	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210605	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210605	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50-20210607	SSHS-ISMP-B527 S50	6/7/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228231	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	0.0036 J	0.014	0.018
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66-20210607	SSHS-ISMP-B527 S66	6/7/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69-20210607	SSHS-ISMP-B527 S69	6/7/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228231	Not Excavated	< 0.0010 U	0.0088	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	IRM5-FIS BOT 2	SSHS-IRM5-FIS BOT 2-20210612	SSHS-IRM5-FIS BOT 2	6/12/2021	-	854.24	-	840.68	12 - 14 ft	13.57 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS-S6	SSHS-IRM5-FIS S6-20210614	SSHS-IRM5-FIS S6	6/14/2021	-	854.28	-	842.04	12 - 14 ft	12.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S12	SSHS-IRM5-FIS S12-20210614	SSHS-IRM5-FIS S12	6/14/2021	-	854.57	-	842.14	12 - 14 ft	12.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S18	SSHS-IRM5-FIS S18-20210614	SSHS-IRM5-FIS S18	6/14/2021	-	855.24	-	842.51	12 - 14 ft	12.74 ft	1801231602	Not Excavated							
Football Field	IRM5-FIS-S36	SSHS-IRM5-FIS S36-20210614	SSHS-IRM5-FIS S36	6/14/2021	-	854.33	-	842.28	12 - 14 ft	12.05 ft	1801231602	Not Excavated							
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27-20210623	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28-20210623	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91-20210624	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 0.0011 U	0.015	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	IRM5-FIS-S327	SSHS-IRM5-FIS S327-20210916	SSHS-IRM5-FIS S327	9/16/2021	-	854.08	-	841.89	12 - 14 ft	12.20	1801271981	Not Excavated							
Football Field	IRM5-FIS-S328	SSHS-IRM5-FIS S328-20210916	SSHS-IRM5-FIS S328	9/16/2021	-	855.03	-	841.86	12 - 14 ft	13.17 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S336	SSHS-IRM5-FIS S336-20210916	SSHS-IRM5-FIS S336	9/16/2021	-	855.08	-	841.62	12 - 14 ft	13.47 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS- BOT 58	SSHS-IRM5-FIS BOT58-20210916	SSHS-IRM5-FIS BOT58	9/16/2021	-	855.08	-	841.14	12 - 14 ft	13.95 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS-S333	SSHS-IRM5-FIS S333-20210916	SSHS-IRM5-FIS S333	9/16/2021	-	855.08	-	841.94	12 - 14 ft	13.14 ft	1801271982	Not Excavated							
Football Field	IRM5-FIS-S350	SSHS-IRM5-FIS S350-20210916	SSHS-IRM5-FIS S350	9/16/2021	-	854.79	-	841.81	12 - 14 ft	12.98 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-12-14	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-12-14	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated							
Football Field	IRM5-FIS-S352	SSHS-IRM5-FIS-S352-20211008	SSHS-IRM5-FIS-S352	10/8/2021	-	855.62	-	843.57	12 - 14 ft	12.05 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S359	SSHS-IRM5-FIS-S359-20211008	SSHS-IRM5-FIS-S359	10/8/2021	-	855.40	-	841.57	12 - 14 ft	13.84 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S356	SSHS-IRM5-FIS-S356-20211008	SSHS-IRM5-FIS-S356	10/8/2021	-	855.62	-	841.66	12 - 14 ft	13.96 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S353	SSHS-IRM5-FIS-S353-20211008	SSHS-IRM5-FIS-S353	10/8/2021	-	855.23	-	841.96	12 - 14 ft	13.27 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS BOT 67	SSHS-IRM5-FIS-BOT67-20211009	SSHS-IRM5-FIS-BOT67	10/9/2021	-	855.23	-	843.11	12 - 14 ft	12.12 ft	1801283151	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-14-16	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B624	021017 09:20 SSHS-B624-SUB-14-16	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated							
Football Field	SSHS-B657	021117 09:30 SSHS-B657-SUB-14-16	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated							
Football Field	SSHS-B621	021617 08:35 SSHS-B621-SUB-14-16	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B645	021617 08:35 SSHS-B645-SUB-14-16	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B646	021617 08:35 SSHS-B646-SUB-14-16	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B630	021617 08:35 SSHS-B630-SUB-14-16	SSHS-B630-SUB-14-16	2/14/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B650	021617 08:35 SSHS-B650-SUB-14-16	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B651	021617 08:35 SSHS-B651-SUB-14-16	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B652	021617 08:35 SSHS-B652-SUB-14-16	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B653	021617 08:35 SSHS-B653-SUB-14-16	SSHS-B653-SUB-14-16	2/14/2017	855.63	855.62	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-63507-2	Not Excavated							
Football Field	SSHS-B659	021817 08:50 SSHS-B659-SUB-14-16	SSHS-B659-SUB-14-16	2/16/2017	856.83	856.83	0.00	-	14 - 16 ft	14-16 ft	180-63593-2	Not Excavated							
Football Field	SSHS-B792	051717 09:05 SSHS-B792-SUB-14-16	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated							
Football Field	SSHS-B803	051717 09:05 SSHS-B803-SUB-14-16	SSHS-B803-SUB-14-16	5/16/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-66369-2	Not Excavated							
Football Field	SSHS-B804	051717 09:05 SSHS-B804-SUB-14-16	SSHS-B804-SUB-14-16	5/16/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-66369-2	Not Excavated							

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B800	051817 08:45_SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated							
Football Field	SSHS-B630A	071317 07:30_SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B657A	071317 07:30_SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B803A	071317 07:30_SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B804A	071317 07:30_SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B2532	103118 09:00_SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated							
Football Field	SSHS-B2534	103118 09:00_SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2535	103118 09:00_SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated							
Football Field	SSHS-B2629	042819 10:00_SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated							
Football Field	SSHS-B2761	042819 10:00_SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated							
Football Field	SSHS-B2720	051619 09:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 UJ	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2811	052119 08:40_SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2812	052119 08:40_SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2813	052119 08:40_SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2814	052119 08:40_SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2815	052119 08:40_SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2816	052119 08:40_SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2817	052119 08:40_SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2818	052119 08:40_SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	0.017 U	< 0.0017 U	< 0.0016 U	< 0.002 U	< 0.0022 U	< 0.0038 UJ	< 0.0025 U	< 0.0028 U
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B016	072719 09:00_SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-B026	072719 09:00_SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-B027	072719 09:00_SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-S156C	072719 09:00_SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-S188	072719 09:00_SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-B022	073019 09:00_SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-B023	073019 09:00_SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S175	073019 09:00_SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S176	073019 09:00_SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S177	073019 09:00_SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S179	073019 09:00_SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated							
Football Field	SSHS-IRM3-S180	073019 09:00_SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated							
Football Field	SSHS-IRM3-S181	073019 09:00_SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated							
Football Field	SSHS-IRM3-S182	073019 09:00_SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S183	073019 09:00_SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-B024	073119 09:00_SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated							
Football Field	SSHS-IRM3-S201	080219 09:00_SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated							
Football Field	SSHS-IRM3-MH1DA	080319 09:30_SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated							
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	0.014 J,*	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	0.0053	< 0.0035 U
Football Field	SSHS-IRM3-S150	080619 09:00_SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S156A	080619 09:00_SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S156B	080619 09:00_SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S166	080619 09:00_SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S167	080619 09:00_SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S169	080619 09:00_SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S170	080619 09:00_SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S172	080619 09:00_SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S174	080619 09:00_SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated							
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated							
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated							
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated							
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated							
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated							
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated							
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated							
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated							
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated							
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated							
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated							
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated							
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated							
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated							
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated							
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated							
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated							
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated							
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated							
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated							
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated							
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated							

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B800	051817 08:45_SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated						
Football Field	SSHS-B630A	071317 07:30_SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B657A	071317 07:30_SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B803A	071317 07:30_SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B804A	071317 07:30_SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B2532	103118 09:00_SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated						
Football Field	SSHS-B2534	103118 09:00_SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated						
Football Field	SSHS-B2535	103118 09:00_SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated						
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated						
Football Field	SSHS-B2629	042819 10:00_SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated						
Football Field	SSHS-B2761	042819 10:00_SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated						
Football Field	SSHS-B2720	051619 09:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2811	052119 08:40_SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2812	052119 08:40_SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2813	052119 08:40_SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2814	052119 08:40_SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2815	052119 08:40_SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2816	052119 08:40_SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2817	052119 08:40_SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2818	052119 08:40_SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0013 U	< 0.002 U	< 0.0022 U	< 0.0018 U	< 0.0033 UJ	< 0.001 U	< 0.0026 U
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated						
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated						
Football Field	SSHS-IRM3-B016	072719 09:00_SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-B026	072719 09:00_SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-B027	072719 09:00_SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-S156C	072719 09:00_SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-S188	072719 09:00_SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-B022	073019 09:00_SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-B023	073019 09:00_SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S175	073019 09:00_SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S176	073019 09:00_SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S177	073019 09:00_SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S179	073019 09:00_SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated						
Football Field	SSHS-IRM3-S180	073019 09:00_SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated						
Football Field	SSHS-IRM3-S181	073019 09:00_SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated						
Football Field	SSHS-IRM3-S182	073019 09:00_SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S183	073019 09:00_SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-B024	073119 09:00_SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated						
Football Field	SSHS-IRM3-S201	080219 09:00_SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated						
Football Field	SSHS-IRM3-MH1DA	080319 09:30_SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated						
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-IRM3-S150	080619 09:00_SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S156A	080619 09:00_SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated						
Football Field	SSHS-IRM3-S156B	080619 09:00_SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S166	080619 09:00_SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S167	080619 09:00_SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S169	080619 09:00_SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S170	080619 09:00_SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S172	080619 09:00_SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S174	080619 09:00_SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated						
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated						
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated						
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated						
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated						
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated						
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated						
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated						
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated						
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated						
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated						
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated						
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated						
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated						
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated						
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated						
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated						
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated						
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated						
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated						
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated						
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated						
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated						

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B800	051817 08:45 SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated								
Football Field	SSHS-B630A	071317 07:30 SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B657A	071317 07:30 SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B803A	071317 07:30 SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B804A	071317 07:30 SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B2532	103118 09:00 SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated								
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2535	103118 09:00 SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2679	042519 08:35 SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated								
Football Field	SSHS-B2629	042819 10:00 SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated								
Football Field	SSHS-B2761	042819 10:00 SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated								
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2811	052119 08:40 SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2812	052119 08:40 SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2813	052119 08:40 SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2814	052119 08:40 SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2815	052119 08:40 SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2816	052119 08:40 SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2817	052119 08:40 SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2818	052119 08:40 SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0032 U	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0013 U	< 0.00086 U	< 0.0015 UJ	< 0.0012 U
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B016	072719 09:00 SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B026	072719 09:00 SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B027	072719 09:00 SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-S156C	072719 09:00 SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-S188	072719 09:00 SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B022	073019 09:00 SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-B023	073019 09:00 SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S175	073019 09:00 SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S176	073019 09:00 SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S177	073019 09:00 SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S179	073019 09:00 SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S180	073019 09:00 SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S181	073019 09:00 SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S182	073019 09:00 SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S183	073019 09:00 SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-B024	073119 09:00 SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated								
Football Field	SSHS-IRM3-S201	080219 09:00 SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated								
Football Field	SSHS-IRM3-MH1DA	080319 09:30 SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated								
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.004 U	< 0.0029 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-IRM3-S150	080619 09:00 SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S156A	080619 09:00 SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S156B	080619 09:00 SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S166	080619 09:00 SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S167	080619 09:00 SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S169	080619 09:00 SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S170	080619 09:00 SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S172	080619 09:00 SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S174	080619 09:00 SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated								
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated								
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated								
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated								
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated								
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated								
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated								
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated								
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated								
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated								
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated								
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated								
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated								
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated								
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated								
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated								
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated								
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated								
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B800	051817 08:45 SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated								
Football Field	SSHS-B630A	071317 07:30 SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B657A	071317 07:30 SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B803A	071317 07:30 SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B804A	071317 07:30 SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B2532	103118 09:00 SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated								
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2535	103118 09:00 SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2679	042519 08:35 SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated								
Football Field	SSHS-B2629	042819 10:00 SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated								
Football Field	SSHS-B2761	042819 10:00 SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated								
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2811	052119 08:40 SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2812	052119 08:40 SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2813	052119 08:40 SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2814	052119 08:40 SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2815	052119 08:40 SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2816	052119 08:40 SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2817	052119 08:40 SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2818	052119 08:40 SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0024 U	< 0.0034 U	< 0.0013 U	< 0.0021 UJ	< 0.0021 U	< 0.0013 U	< 0.0015 UJ	< 0.0018 U
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B016	072719 09:00 SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B026	072719 09:00 SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B027	072719 09:00 SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-S156C	072719 09:00 SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-S188	072719 09:00 SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B022	073019 09:00 SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-B023	073019 09:00 SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S175	073019 09:00 SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S176	073019 09:00 SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S177	073019 09:00 SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S179	073019 09:00 SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S180	073019 09:00 SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S181	073019 09:00 SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S182	073019 09:00 SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S183	073019 09:00 SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-B024	073119 09:00 SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated								
Football Field	SSHS-IRM3-S201	080219 09:00 SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated								
Football Field	SSHS-IRM3-MH1DA	080319 09:30 SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated								
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-IRM3-S150	080619 09:00 SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S156A	080619 09:00 SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S156B	080619 09:00 SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S166	080619 09:00 SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S167	080619 09:00 SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S169	080619 09:00 SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S170	080619 09:00 SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S172	080619 09:00 SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S174	080619 09:00 SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated								
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated								
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated								
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated								
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated								
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated								
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated								
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated								
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated								
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated								
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated								
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated								
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated								
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated								
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated								
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated								
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated								
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated								
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated								

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B800	051817 08:45_SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated								
Football Field	SSHS-B630A	071317 07:30_SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B657A	071317 07:30_SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B803A	071317 07:30_SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B804A	071317 07:30_SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated								
Football Field	SSHS-B2532	103118 09:00_SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated								
Football Field	SSHS-B2534	103118 09:00_SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2535	103118 09:00_SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated								
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated								
Football Field	SSHS-B2629	042819 10:00_SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated								
Football Field	SSHS-B2761	042819 10:00_SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated								
Football Field	SSHS-B2720	051619 09:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2811	052119 08:40_SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2812	052119 08:40_SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2813	052119 08:40_SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2814	052119 08:40_SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2815	052119 08:40_SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2816	052119 08:40_SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2817	052119 08:40_SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2818	052119 08:40_SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated								
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.002 U	< 0.005 U	< 0.0018 U	< 0.0024 U	< 0.0016 UJ	< 0.0031 U
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated								
Football Field	SSHS-IRM3-B016	072719 09:00_SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B026	072719 09:00_SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B027	072719 09:00_SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-S156C	072719 09:00_SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-S188	072719 09:00_SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated								
Football Field	SSHS-IRM3-B022	073019 09:00_SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-B023	073019 09:00_SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S175	073019 09:00_SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S176	073019 09:00_SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S177	073019 09:00_SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S179	073019 09:00_SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S180	073019 09:00_SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S181	073019 09:00_SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated								
Football Field	SSHS-IRM3-S182	073019 09:00_SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-S183	073019 09:00_SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated								
Football Field	SSHS-IRM3-B024	073119 09:00_SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated								
Football Field	SSHS-IRM3-S201	080219 09:00_SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated								
Football Field	SSHS-IRM3-MH1DA	080319 09:30_SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated								
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U,*	< 0.0019 U	< 0.0038 U
Football Field	SSHS-IRM3-S150	080619 09:00_SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S156A	080619 09:00_SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated								
Football Field	SSHS-IRM3-S156B	080619 09:00_SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S166	080619 09:00_SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S167	080619 09:00_SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S169	080619 09:00_SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S170	080619 09:00_SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S172	080619 09:00_SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated								
Football Field	SSHS-IRM3-S174	080619 09:00_SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated								
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated								
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated								
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated								
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated								
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated								
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated								
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated								
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated								
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated								
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated								
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated								
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated								
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated								
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated								
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated								
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated								
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated								
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated								
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B800	051817 08:45 SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated						
Football Field	SSHS-B630A	071317 07:30 SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B657A	071317 07:30 SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B803A	071317 07:30 SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B804A	071317 07:30 SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated						
Football Field	SSHS-B2532	103118 09:00 SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated						
Football Field	SSHS-B2534	103118 09:00 SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated						
Football Field	SSHS-B2535	103118 09:00 SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated						
Football Field	SSHS-B2679	042519 08:35 SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated						
Football Field	SSHS-B2629	042819 10:00 SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated						
Football Field	SSHS-B2761	042819 10:00 SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated						
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2811	052119 08:40 SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2812	052119 08:40 SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2813	052119 08:40 SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2814	052119 08:40 SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2815	052119 08:40 SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2816	052119 08:40 SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2817	052119 08:40 SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2818	052119 08:40 SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated						
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0011 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0031 U	< 0.0021 U
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated						
Football Field	SSHS-IRM3-B010	072019 09:15 SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated						
Football Field	SSHS-IRM3-B016	072719 09:00 SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-B026	072719 09:00 SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-B027	072719 09:00 SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-S156C	072719 09:00 SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-S188	072719 09:00 SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated						
Football Field	SSHS-IRM3-B022	073019 09:00 SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-B023	073019 09:00 SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S175	073019 09:00 SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S176	073019 09:00 SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S177	073019 09:00 SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S179	073019 09:00 SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated						
Football Field	SSHS-IRM3-S180	073019 09:00 SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated						
Football Field	SSHS-IRM3-S181	073019 09:00 SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated						
Football Field	SSHS-IRM3-S182	073019 09:00 SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-S183	073019 09:00 SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated						
Football Field	SSHS-IRM3-B024	073119 09:00 SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated						
Football Field	SSHS-IRM3-S201	080219 09:00 SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated						
Football Field	SSHS-IRM3-MH1DA	080319 09:30 SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated						
Football Field	SSHS-IRM3-PIPE10	080319 09:30 SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Football Field	SSHS-IRM3-S150	080619 09:00 SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S156A	080619 09:00 SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated						
Football Field	SSHS-IRM3-S156B	080619 09:00 SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S166	080619 09:00 SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S167	080619 09:00 SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S169	080619 09:00 SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S170	080619 09:00 SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S172	080619 09:00 SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated						
Football Field	SSHS-IRM3-S174	080619 09:00 SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated						
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated						
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated						
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated						
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated						
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated						
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated						
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated						
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated						
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated						
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated						
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated						
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated						
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated						
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated						
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated						
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated						
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated						
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated						
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated						
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated						
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated						
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B800	051817 08:45_SSHS-B800-SUB-14-16	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated							
Football Field	SSHS-B630A	071317 07:30_SSHS-B630A-SUB-14-16	SSHS-B630A-SUB-14-16	7/12/2017	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B657A	071317 07:30_SSHS-B657A-SUB-14-16	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B803A	071317 07:30_SSHS-B803A-SUB-14-16	SSHS-B803A-SUB-14-16	7/12/2017	855.86	855.86	0.00	-	14 - 16 ft	14-16 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B804A	071317 07:30_SSHS-B804A-SUB-14-16	SSHS-B804A-SUB-14-16	7/12/2017	855.75	855.74	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-68139-1	Not Excavated							
Football Field	SSHS-B2532	103118 09:00_SSHS-B2532-SUB-14-16	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated							
Football Field	SSHS-B2534	103118 09:00_SSHS-B2534-SUB-14-16	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2535	103118 09:00_SSHS-B2535-SUB-14-16	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated							
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated							
Football Field	SSHS-B2629	042819 10:00_SSHS-B2629-SUB-14-16	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated							
Football Field	SSHS-B2761	042819 10:00_SSHS-B2761-SUB-14-16	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated							
Football Field	SSHS-B2720	051619 09:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2811	052119 08:40_SSHS-B2811-SUB-14-16	SSHS-B2811-SUB-14-16	5/18/2019	856.01	856.01	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2812	052119 08:40_SSHS-B2812-SUB-14-16	SSHS-B2812-SUB-14-16	5/18/2019	856.10	856.10	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2813	052119 08:40_SSHS-B2813-SUB-14-16	SSHS-B2813-SUB-14-16	5/18/2019	856.22	856.21	-0.01	-	14 - 16 ft	13.99-15.99 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2814	052119 08:40_SSHS-B2814-SUB-14-16	SSHS-B2814-SUB-14-16	5/18/2019	856.31	856.31	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2815	052119 08:40_SSHS-B2815-SUB-14-16	SSHS-B2815-SUB-14-16	5/18/2019	856.40	856.40	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2816	052119 08:40_SSHS-B2816-SUB-14-16	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2817	052119 08:40_SSHS-B2817-SUB-14-16	SSHS-B2817-SUB-14-16	5/18/2019	856.07	856.07	0.00	-	14 - 16 ft	14-16 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2818	052119 08:40_SSHS-B2818-SUB-14-16	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated							
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.002 U	< 0.0013 U	< 0.0012 U	< 0.0031 UJ	< 0.0016 U	< 0.0021 U	< 0.0036 U
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B010	072019 09:15_SSHS-IRM3-B010	SSHS-IRM3-B010	7/19/2019	-	856.35	-	842.34	14 - 16 ft	14.01 ft	180-92988-1	Not Excavated							
Football Field	SSHS-IRM3-B016	072719 09:00_SSHS-IRM3-B016-C	SSHS-IRM3-B016-C	7/26/2019	-	856.08	-	840.96	14 - 16 ft	15.12 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-B026	072719 09:00_SSHS-IRM3-B026-C	SSHS-IRM3-B026-C	7/26/2019	-	856.00	-	840.33	14 - 16 ft	15.67 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-B027	072719 09:00_SSHS-IRM3-B027-C	SSHS-IRM3-B027-C	7/26/2019	-	855.79	-	840.00	14 - 16 ft	15.79 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-S156C	072719 09:00_SSHS-IRM3-S156C-C	SSHS-IRM3-S156C-C	7/26/2019	-	855.52	-	839.78	14 - 16 ft	15.74 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-S188	072719 09:00_SSHS-IRM3-S188-C	SSHS-IRM3-S188-C	7/26/2019	-	855.90	-	841.25	14 - 16 ft	14.65 ft	180-93321-1	Not Excavated							
Football Field	SSHS-IRM3-B022	073019 09:00_SSHS-IRM3-B022-C	SSHS-IRM3-B022-C	7/29/2019	-	856.35	-	840.35	14 - 16 ft	16.00	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-B023	073019 09:00_SSHS-IRM3-B023-C	SSHS-IRM3-B023-C	7/29/2019	-	856.36	-	840.37	14 - 16 ft	15.99 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S175	073019 09:00_SSHS-IRM3-S175-C	SSHS-IRM3-S175-C	7/29/2019	-	856.09	-	841.75	14 - 16 ft	14.34 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S176	073019 09:00_SSHS-IRM3-S176-C	SSHS-IRM3-S176-C	7/29/2019	-	856.14	-	840.90	14 - 16 ft	15.24 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S177	073019 09:00_SSHS-IRM3-S177-C	SSHS-IRM3-S177-C	7/29/2019	-	856.14	-	841.29	14 - 16 ft	14.85 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S179	073019 09:00_SSHS-IRM3-S179-D	SSHS-IRM3-S179-D	7/29/2019	-	856.39	-	841.78	14 - 16 ft	14.61 ft	180-93353-1	Not Excavated							
Football Field	SSHS-IRM3-S180	073019 09:00_SSHS-IRM3-S180-D	SSHS-IRM3-S180-D	7/29/2019	-	856.29	-	841.02	14 - 16 ft	15.27 ft	180-93353-1	Not Excavated							
Football Field	SSHS-IRM3-S181	073019 09:00_SSHS-IRM3-S181-D	SSHS-IRM3-S181-D	7/29/2019	-	856.09	-	840.92	14 - 16 ft	15.17 ft	180-93353-1	Not Excavated							
Football Field	SSHS-IRM3-S182	073019 09:00_SSHS-IRM3-S182-C	SSHS-IRM3-S182-C	7/29/2019	-	856.28	-	841.99	14 - 16 ft	14.29	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-S183	073019 09:00_SSHS-IRM3-S183-C	SSHS-IRM3-S183-C	7/29/2019	-	856.42	-	841.32	14 - 16 ft	15.1 ft	180-93352-1	Not Excavated							
Football Field	SSHS-IRM3-B024	073119 09:00_SSHS-IRM3-B024-C	SSHS-IRM3-B024-C	7/30/2019	-	856.33	-	840.36	14 - 16 ft	15.97 ft	180-93419-1	Not Excavated							
Football Field	SSHS-IRM3-S201	080219 09:00_SSHS-IRM3-S201-C	SSHS-IRM3-S201-C	8/1/2019	-	856.09	-	841.85	14 - 16 ft	14.24 ft	180-93547-1	Not Excavated							
Football Field	SSHS-IRM3-MH1DA	080319 09:30_SSHS-IRM3-MH1DA-C	SSHS-IRM3-MH1DA-C	8/2/2019	-	855.87	-	840.06	14 - 16 ft	15.81 ft	180-93640-2	Not Excavated							
Football Field	SSHS-IRM3-PIPE10	080319 09:30_SSHS-IRM3-PIPE10-C	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U		< 0.0025 U	< 0.0045 U
Football Field	SSHS-IRM3-S150	080619 09:00_SSHS-IRM3-S150-D	SSHS-IRM3-S150-D	8/5/2019	-	856.28	-	840.80	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S156A	080619 09:00_SSHS-IRM3-S156A-C	SSHS-IRM3-S156A-C	8/5/2019	-	856.16	-	841.26	14 - 16 ft	14.9 ft	180-93683-1	Not Excavated							
Football Field	SSHS-IRM3-S156B	080619 09:00_SSHS-IRM3-S156B-C	SSHS-IRM3-S156B-C	8/5/2019	-	856.15	-	840.86	14 - 16 ft	15.29 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S166	080619 09:00_SSHS-IRM3-S166-D	SSHS-IRM3-S166-D	8/5/2019	-	856.37	-	840.97	14 - 16 ft	15.4 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S167	080619 09:00_SSHS-IRM3-S167-D	SSHS-IRM3-S167-D	8/5/2019	-	856.38	-	840.91	14 - 16 ft	15.47 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S169	080619 09:00_SSHS-IRM3-S169-D	SSHS-IRM3-S169-D	8/5/2019	-	856.26	-	841.07	14 - 16 ft	15.19 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S170	080619 09:00_SSHS-IRM3-S170-D	SSHS-IRM3-S170-D	8/5/2019	-	856.10	-	840.82	14 - 16 ft	15.28	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S172	080619 09:00_SSHS-IRM3-S172-D	SSHS-IRM3-S172-D	8/5/2019	-	856.31	-	840.97	14 - 16 ft	15.34 ft	180-93684-1	Not Excavated							
Football Field	SSHS-IRM3-S174	080619 09:00_SSHS-IRM3-S174-C	SSHS-IRM3-S174-C	8/5/2019	-	856.34	-	841.70	14 - 16 ft	14.64	180-93683-1	Not Excavated							
Football Field	IRM4-B014	SSHS-IRM4-B014-20200724	SSHS-IRM4-B014	7/24/2020	-	855.62	-	841.17	14 - 16 ft	14.45 ft	1801087891	Not Excavated							
Football Field	IRM4-B013	SSHS-IRM4-B013-20200724	SSHS-IRM4-B013	7/24/2020	-	855.68	-	841.08	14 - 16 ft	14.60	1801087891	Not Excavated							
Football Field	IRM4-B016	SSHS-IRM4-B016-20200724	SSHS-IRM4-B016	7/24/2020	-	855.62	-	840.98	14 - 16 ft	14.65 ft	1801087891	Not Excavated							
Football Field	IRM4-S180	SSHS-IRM4-S180-14-16-20200727	SSHS-IRM4-S180-14-16	7/27/2020	-	855.35	-	841.03	14 - 16 ft	14.32 ft	1801088021	Not Excavated							
Football Field	IRM4-B009	SSHS-IRM4-B009-20200727	SSHS-IRM4-B009	7/27/2020	-	855.35	-	840.43	14 - 16 ft	14.93 ft	1801088021	Not Excavated							
Football Field	IRM4-S178A	SSHS-IRM4-DUP-21-20200807	SSHS-IRM4-DUP-21	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated							
Football Field	IRM4-S163BOT2	SSHS-IRM4-S163BOT2-20200807	SSHS-IRM4-S163BOT2	8/7/2020	-	855.99	-	840.16	14 - 16 ft	15.83 ft	1801093661	Not Excavated							
Football Field	IRM4-S178B	SSHS-IRM4-S178B-20200807	SSHS-IRM4-S178B	8/7/2020	-	855.60	-	840.85	14 - 16 ft	14.75 ft	1801093661	Not Excavated							
Football Field	IRM4-S178A	SSHS-IRM4-S178A-20200807	SSHS-IRM4-S178A	8/7/2020	-	855.48	-	840.90	14 - 16 ft	14.58 ft	1801093661	Not Excavated							
Football Field	IRM4-S178BOT	SSHS-IRM4-S178BOT-20200807	SSHS-IRM4-S178BOT	8/7/2020	-	855.46	-	840.01	14 - 16 ft	15.45 ft	1801093661	Not Excavated							
Football Field	IRM4A-B016	SSHS-IRM4A-B016-20201012	SSHS-IRM4A-B016	10/12/2020	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801121371	Not Excavated							
Football Field	IRM4A-B017	SSHS-IRM4A-B017-20201012	SSHS-IRM4A-B017	10/12/2020	-	856.31	-	841.90	14 - 16 ft	14.42 ft	1801121371	Not Excavated							
Football Field	IRM4A-B018	SSHS-IRM4A-B018-20201012	SSHS-IRM4A-B018	10/12/2020	-	855.86	-	841.71	14 - 16 ft	14.15 ft	1801121371	Not Excavated							
Football Field	IRM4A-S190	SSHS-IRM4A-S190-20201012	SSHS-IRM4A-S190	10/12/2020	-	855.72	-	839.90	14 - 16 ft	15.82 ft	1801121381	Not Excavated							
Football Field	IRM4A-S189	SSHS-IRM4A-S189-20201012	SSHS-IRM4A-S189	10/12/2020	-	856.15	-	840.30	14 - 16 ft	15.85 ft	1801121381	Not Excavated							
Football Field	IRM4A-S188	SSHS-IRM4A-S188-20201012	SSHS-IRM4A-S188	10/12/2020	-	855.97	-	840.31	14 - 16 ft	15.66 ft	1801121381	Not Excavated							
Football Field	IRM4A-S187	SSHS-IRM4A-S187-20201019	SSHS-IRM4A-S187	10/19/2020	-	855.76	-	840.09	14 - 16 ft	15.68 ft	1801124481	Not Excavated							
Football Field	IRM4A-B42 BOT	SSHS-IRM4A-B42-BOTT-20201114	SSHS-IRM4A-B42-BOTT	11/14/2020	-	855.46	-	841.15	14 - 16 ft	14.31 ft	1801137151	Not Excavated							
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-DUP13-20201120	SSHS-IRM4A-DUP13	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated							
Football Field	IRM4A-B044-WEST	SSHS-IRM4A-B044-WEST-20201120	SSHS-IRM4A-B044-WEST	11/20/2020	-	855.36	-	839.61	14 - 16 ft	15.75 ft	1801139241	Not Excavated							
Football Field	IRM4A-B044-BOT-BOT	SSHS-IRM4A-B044-BOT-BOT-20201120	SSHS-IRM4A-B044-BOT-BOT	11/20/2020	-	855.50	-	839.51	14 - 16 ft	15.99 ft	1801139241	Not Excavated							
Football Field	IRM4A-B044-EAST	SSHS-IRM4A-B044-EAST-20201120	SSHS-IRM4A-B044-EAST	11/20/2020	-	855.45	-	839.61	14 - 16 ft	15.84 ft	1801139241	Not Excavated							

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated							
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated							
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated							
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated							
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated							
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.19 U	< 0.07 U	< 0.15 U	< 0.12 U	< 0.12 U	< 0.11 U	< 0.2 U	< 0.1 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3577	020621 10:00_SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3579	020621 10:00_SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00_DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3583	020621 10:00_DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated								
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated								
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated								
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated								
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated								
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated								
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated								
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated								
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated								
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated								
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.025 U	< 0.0062 U						< 0.0062 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B410	082616 09:00_SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated								

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated						
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated						
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated						
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated						
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated						
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.064 U	< 0.12 U	< 0.14 U	< 0.08 U	< 0.098 U	< 0.12 U	< 0.16 U
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UJ	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 UJ
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SSHS-B3582	020621 10:00 DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated							
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated							
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated							
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated							
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated							
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated							
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated							
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated							
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated							
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated							
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated							
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UT
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 UT
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated							
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated							
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated							
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated							
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.0062 U			< 0.0062 U			
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated								
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated								
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	0.33	< 0.068 U	< 0.12 U	< 0.083 U	< 0.15 U	< 0.074 U	< 0.079 U	< 0.071 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3577	020621 10:00_SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	SSHS-B3579	020621 10:00_SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3582	020621 10:00_DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3583	020621 10:00_DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0048 U	< 0.0015 UJ	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated								
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated								
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated								
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated								
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated								
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated								
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 UT	< 0.0033 UT	< 0.0016 UT	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 UT	< 0.0032 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated								
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated								
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated								
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated								
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.0062 U			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0062 U	< 0.0062 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U
Football Field	SSHS-B410	082616 09:00_SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated								
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated								
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.11 U	< 0.2 U	< 0.075 U	< 0.087 U	< 0.066 U	< 0.11 U	< 0.11 U	< 0.092 U
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00 DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated								
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated								
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated								
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated								
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated								
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated								
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated								
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated								
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated								
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated								
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.0062 U		< 0.0062 U	< 0.0062 U				< 0.0062 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated								
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated								
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated								
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated								
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.099 U	< 0.078 U	< 0.13 U	< 0.36 U	< 0.12 U	< 0.13 U	< 0.091 U	< 0.073 U
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00 DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	180169472	Not Excavated								
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	180169472	Not Excavated								
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	180169472	Not Excavated								
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	180169472	Not Excavated								
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated								
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated								
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated								
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated								
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated								
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated								
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated								
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated								
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated								
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated								
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.018 J	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated								
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated						< 0.012 U		
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated						
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated						
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated						
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated						
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated						
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.074 U	< 0.075 U	< 0.1 U	< 0.071 U	< 0.14 UJ	< 0.13 U	< 0.083 U
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UJ	< 0.0029 UJ	< 0.0019 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3582	020621 10:00 DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ	< 0.0018 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated							
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated							
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated							
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated							
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated							
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated							
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated							
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated							
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated							
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated							
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated							
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 UT	< 0.0027 UT	< 0.0018 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0026 UT	< 0.0017 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated							
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated							
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated							
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated							
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			0.0052 J	< 0.0062 U			< 0.0062 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated							

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4A-B044-SOUTH	SSHS-IRM4A-B044-SOUTH-20201120	SSHS-IRM4A-B044-SOUTH	11/20/2020	-	855.44	-	839.56	14 - 16 ft	15.88 ft	1801139241	Not Excavated							
Football Field	IRM4A-B039-BOT-BOT	SSHS-IRM4A-B039-BOT-BOT-20201120	SSHS-IRM4A-B039-BOT-BOT	11/20/2020	-	855.42	-	839.48	14 - 16 ft	15.94 ft	1801139241	Not Excavated							
Football Field	IRM4A-B039-EAST	SSHS-IRM4A-B039-EAST-20201120	SSHS-IRM4A-B039-EAST	11/20/2020	-	855.44	-	839.61	14 - 16 ft	15.83 ft	1801139241	Not Excavated							
Football Field	IRM4A-B039-SOUTH	SSHS-IRM4A-B039-SOUTH-20201120	SSHS-IRM4A-B039-SOUTH	11/20/2020	-	855.43	-	839.49	14 - 16 ft	15.94 ft	1801139241	Not Excavated							
Football Field	IRM4A-B040-SOUTH	SSHS-IRM4A-B040-SOUTH-20201120	SSHS-IRM4A-B040-SOUTH	11/20/2020	-	855.47	-	839.72	14 - 16 ft	15.75 ft	1801139241	Not Excavated							
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT-20201120	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated							
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.049 U	< 0.078 U	< 0.21 U	< 0.18 U	< 0.088 U	< 0.1 U	< 0.36 U
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-14-16	SSHS-B3577-SUB-14-16	2/5/2021	856.15	856.15	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0011 U	0.0061	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-14-16	SSHS-B3581-SUB-14-16	2/5/2021	856.18	856.18	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0011 U	0.003 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3582	020621 10:00 DUP-35	DUP-35	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0011 U	0.026	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-14-16	SSHS-B3582-SUB-14-16	2/5/2021	855.93	855.93	0.00	-	14 - 16 ft	14-16 ft	180-116914-1	Not Excavated	< 0.0011 U	0.017	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0011 U	0.0055 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0011 U	0.0049 J	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	IRM4A-S197	SSHS-IRM4A-DUP106-20210208	SSHS-IRM4A-DUP106	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated							
Football Field	IRM4A-S196	SSHS-IRM4A-S196-14-16-20210208	SSHS-IRM4A-S196-14-16	2/8/2021	-	855.60	-	840.60	14 - 16 ft	15.01 ft	1801169472	Not Excavated							
Football Field	IRM4A-S197	SSHS-IRM4A-S197-14-16-20210208	SSHS-IRM4A-S197-14-16	2/8/2021	-	855.41	-	840.73	14 - 16 ft	14.67 ft	1801169472	Not Excavated							
Football Field	IRM4A-B016	SSHS-IRM4A-B016-12-14-20210208	SSHS-IRM4A-B016-12-14	2/8/2021	-	855.82	-	841.08	14 - 16 ft	14.74 ft	1801169472	Not Excavated							
Football Field	IRM4A-MOAB2	SSHS-IRM4A-MOAB2-20210302	SSHS-IRM4A-MOAB2	3/2/2021	-	855.45	-	840.41	14 - 16 ft	15.04 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB3	SSHS-IRM4A-MOAB3-20210302	SSHS-IRM4A-MOAB3	3/2/2021	-	855.46	-	840.30	14 - 16 ft	15.16 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB4	SSHS-IRM4A-MOAB4-20210302	SSHS-IRM4A-MOAB4	3/2/2021	-	855.41	-	840.05	14 - 16 ft	15.36 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB6	SSHS-IRM4A-MOAB6-20210302	SSHS-IRM4A-MOAB6	3/2/2021	-	855.33	-	840.08	14 - 16 ft	15.25 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB7	SSHS-IRM4A-MOAB7-20210302	SSHS-IRM4A-MOAB7	3/2/2021	-	855.38	-	839.74	14 - 16 ft	15.65 ft	1801177752	Not Excavated							
Football Field	IRM4A-MOAB8	SSHS-IRM4A-MOAB8-20210303	SSHS-IRM4A-MOAB8	3/3/2021	-	855.30	-	840.12	14 - 16 ft	15.18 ft	1801178551	Not Excavated							
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1-20210330	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT-20210330	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	IRM5-A4V NORTH A	SSHS-IRM5-A4V NORTH A-20210502	SSHS-IRM5-A4V NORTH A	5/2/2021	-	855.42	-	840.84	14 - 16 ft	14.58 ft	1801210181	Not Excavated							
Football Field	IRM5-A4V WEST A	SSHS-IRM5-A4V WEST A-20210502	SSHS-IRM5-A4V WEST A	5/2/2021	-	855.40	-	840.70	14 - 16 ft	14.7 ft	1801210181	Not Excavated							
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217211	Not Excavated							
Football Field	IRM5-P18 7 BOT 8	SSHS-IRM5-P187 BOT 8-20210515	SSHS-IRM5-P187 BOT 8	5/15/2021	-	855.88	-	840.35	14 - 16 ft	15.53 ft	1801217212	Not Excavated							
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217211	Not Excavated							
Football Field	IRM5-P18 7 BOT 9	SSHS-IRM5-P187 BOT 9-20210515	SSHS-IRM5-P187 BOT 9	5/15/2021	-	855.85	-	840.73	14 - 16 ft	15.12 ft	1801217212	Not Excavated							
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT-20210527	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7-20210527	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7-20210527	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7-20210527	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated							
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7-20210527	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13-20210602	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14-20210602	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20-20210602	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 0.0011 U	0.0022 J	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21-20210602	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 0.0011 U	0.0058	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21-20210607	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22-20210607	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-FIS BOT 1	SSHS-IRM5-FIS BOT 1-20210612	SSHS-IRM5-FIS BOT 1	6/12/2021	-	854.33	-	839.97	14 - 16 ft	14.36 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 3	SSHS-IRM5-FIS BOT 3-20210612	SSHS-IRM5-FIS BOT 3	6/12/2021	-	854.67	-	840.60	14 - 16 ft	14.08 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 4	SSHS-IRM5-FIS BOT 4-20210612	SSHS-IRM5-FIS BOT 4	6/12/2021	-	855.31	-	840.51	14 - 16 ft	14.8 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 5	SSHS-IRM5-FIS BOT 5-20210612	SSHS-IRM5-FIS BOT 5	6/12/2021	-	854.57	-	840.13	14 - 16 ft	14.44 ft	1801231431	Not Excavated							
Football Field	IRM5-FIS BOT 6	SSHS-IRM5-FIS BOT 6-20210613	SSHS-IRM5-FIS BOT 6	6/13/2021	-	854.28	-	839.84	14 - 16 ft	14.44 ft	1801231601	Not Excavated							
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-14-16	SSHS-B4015-SUB-14-16	6/30/2021	855.88	855.88	0.00	-	14 - 16 ft	14-16 ft	180-123901-2	Not Excavated							
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-14-16	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	IRM5-FIS-S341	SSHS-IRM5-FIS S341-20210916	SSHS-IRM5-FIS S341	9/16/2021	-	854.05	-	839.89	14 - 16 ft	14.16	1801271981	Not Excavated							
Football Field	IRM5-FIS-S342	SSHS-IRM5-FIS S342-20210916	SSHS-IRM5-FIS S342	9/16/2021	-	855.03	-	839.86	14 - 16 ft	15.17 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S344	SSHS-IRM5-FIS S344-20210916	SSHS-IRM5-FIS S344	9/16/2021	-	855.04	-	840.56	14 - 16 ft	14.48 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S351	SSHS-IRM5-FIS S351-20210916	SSHS-IRM5-FIS S351	9/16/2021	-	854.79	-	839.65	14 - 16 ft	15.15 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-14-16	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-14-16	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-DUP144-20211008	SSHS-IRM5-FIS-DUP144	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S354	SSHS-IRM5-FIS-S354-20211008	SSHS-IRM5-FIS-S354	10/8/2021	-	855.62	-	839.99	14 - 16 ft	15.63 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S360	SSHS-IRM5-FIS-S360-20211008	SSHS-IRM5-FIS-S360	10/8/2021	-	855.40	-	840.02	14 - 16 ft	15.38 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S357	SSHS-IRM5-FIS-S357-20211008	SSHS-IRM5-FIS-S357	10/8/2021	-	855.23	-	839.54	14 - 16 ft	15.69 ft	1801282871	Not Excavated							
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	-	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated		< 0.0062 U		< 0.0062 U	< 0.0062 U	< 0.0062 U	
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B410	082616 09:00 SSHS-B410-SUB-2-4	SSHS-B410-SUB-2-4	8/25/2016	856.77	856.76	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-2-4	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-2-4	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-2-4	SSHS-B2089-SUB-2-4	7/25/2018	855.40	855.39	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-2-4	SSHS-B2108-SUB-2-4	7/25/2018	855.64	855.64	0.00	-	2 - 4 ft	2-4 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-2-4	SSHS-B2109-SUB-2-4	7/25/2018	855.25	855.48	0.23	-	2 - 4 ft	2.23-4.23 ft	180-80154-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2385	090118 10:00 SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2386	090118 10:00 SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2639	052119 08:40 SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2642	052119 08:40 SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2643	052119 08:40 SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	0.024 J,B	< 0.0024 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0054 U	< 0.0036 U	< 0.004 U
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated							
Football Field	SSHS-B2916	110919 09:30 SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated							
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated								
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	< 0.27 U	< 0.097 U	< 0.21 U	< 0.16 U	< 0.17 U	< 0.16 U	< 0.27 U	< 0.14 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated								
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated								
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3593	020521 09:00 SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00 DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.24 U	< 0.087 U	< 0.18 U	< 0.14 U	< 0.16 U	< 0.14 U	< 0.25 U	< 0.13 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated								
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated								
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated								
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated								
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated								
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated								
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated								
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated								
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated								
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated								
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated								
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated								
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated								
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated								
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated								
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated								
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated								
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated								
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated								
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated								
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2385	090118 10:00 SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated						
Football Field	SSHS-B2386	090118 10:00 SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated						
Football Field	SSHS-B2639	052119 08:40 SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2642	052119 08:40 SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2643	052119 08:40 SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0015 U	< 0.0037 U
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated						
Football Field	SSHS-B2916	110919 09:30 SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated						
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated						
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated						
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated						
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated						
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	< 0.089 U	< 0.17 U	< 0.2 U	< 0.11 U	< 0.14 U	< 0.16 U	< 0.22 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated						
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated						
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3593	020521 09:00 SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3582	020621 10:00 DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.08 U	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated						
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated						
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated						
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated						
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated						
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated						
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated						
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated						
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated						
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated						
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated						
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated						
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated						
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated						
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated						
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated						
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated						
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated						
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated						
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated						
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated						
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated						
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated						
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated						
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated						
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated						
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated						
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated						
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated						
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated						
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated						
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated						
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated						

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2385	090118 10:00 SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2386	090118 10:00 SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2639	052119 08:40 SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2642	052119 08:40 SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2643	052119 08:40 SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.0046 U	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated								
Football Field	SSHS-B2916	110919 09:30 SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated								
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated								
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	0.54	< 0.094 U	< 0.17 U	< 0.12 U	< 0.21 U	< 0.1 U	< 0.11 U	< 0.099 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated								
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated								
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SSHS-B3593	020521 09:00 SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00 DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0052 U	< 0.0016 UJ	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.28 U	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.099 U	< 0.089 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated								
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated								
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated								
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated								
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated								
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated								
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated								
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated								
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated								
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated								
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated								
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated								
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated								
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated								
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated								
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated								
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated								
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated								
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated								
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated								
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2639	052119 08:40_SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2642	052119 08:40_SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2643	052119 08:40_SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.0034 U	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U	< 0.0026 U
Football Field	SSHS-IRM3-S058D	080919 09:00_SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated								
Football Field	SSHS-B2916	110919 09:30_SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated								
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated								
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	< 0.16 U	< 0.28 U	< 0.1 U	< 0.12 U	< 0.091 U	< 0.15 U	< 0.16 U	< 0.13 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated								
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated								
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	SSHS-B3593	020521 09:00_SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00_DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.14 UJ	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 U	< 0.11 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated								
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated								
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated								
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated								
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated								
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated								
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated								
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated								
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated								
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated								
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated								
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated								
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated								
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated								
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated								
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated								
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated								
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated								
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated								
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated								
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2385	090118 10:00_SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2386	090118 10:00_SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated								
Football Field	SSHS-B2639	052119 08:40_SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2642	052119 08:40_SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2643	052119 08:40_SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2215A	052219 08:40_SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.0023 U	< 0.005 U	< 0.0028 U	< 0.0071 U	< 0.0025 U	< 0.0035 U	< 0.0022 U	< 0.0044 U
Football Field	SSHS-IRM3-S058D	080919 09:00_SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated								
Football Field	SSHS-B2916	110919 09:30_SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated								
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated								
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3474	072820 09:00_SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B3475	072820 09:00_SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	SSHS-B3476	072820 09:00_SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B3477	072820 09:00_SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated								
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated								
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	< 0.14 U	< 0.11 U	< 0.18 U	< 0.5 U	< 0.17 U	< 0.17 U	< 0.13 U	< 0.1 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated								
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated								
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B3593	020521 09:00_SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00_DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.12 U	< 0.097 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.091 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated								
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated								
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated								
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated								
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated								
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated								
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated								
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated								
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated								
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated								
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated								
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated								
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated								
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated								
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated								
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated								
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated								
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated								
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated								
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated								
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated								
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated								
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated								
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated								
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated								
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated								
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated								

DRAFT

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2385	090118 10:00 SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated						
Football Field	SSHS-B2386	090118 10:00 SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated						
Football Field	SSHS-B2639	052119 08:40 SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2642	052119 08:40 SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2643	052119 08:40 SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U	< 0.003 U
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated						
Football Field	SSHS-B2916	110919 09:30 SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated						
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated						
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U	< 0.0027 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U	< 0.0027 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated						
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated						
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated						
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	< 0.1 U	< 0.1 U	< 0.14 U	< 0.099 U	< 0.19 U	< 0.17 U	< 0.11 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated						
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated						
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0017 U	< 0.0017 UT	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U
Football Field	SSHS-B3593	020521 09:00 SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3582	020621 10:00 DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 UJ	< 0.003 UJ	< 0.002 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.092 U	< 0.094 U	< 0.12 U	< 0.089 U	< 0.17 U	< 0.16 U	< 0.1 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated						
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated						
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated						
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated						
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated						
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated						
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated						
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated						
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated						
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated						
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated						
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated						
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated						
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated						
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated						
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated						
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated						
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated						
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated						
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated						
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated						
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated						
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated						
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated						
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated						
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated						
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated						
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated						
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated						
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated						
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated						
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated						
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-2-4	SSHS-B2127-SUB-2-4	7/25/2018	855.91	855.91	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 PS-FD-19	PS-FD-19	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-2-4	SSHS-B2128-SUB-2-4	7/25/2018	856.01	856.01	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-2-4	SSHS-B2129-SUB-2-4	7/25/2018	855.33	855.52	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-2-4	SSHS-B2143-SUB-2-4	7/25/2018	856.56	856.56	0.00	-	2 - 4 ft	2-4 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 PS-FD-25	PS-FD-25	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-2-4	SSHS-B2216-SUB-2-4	7/25/2018	855.16	855.46	0.30	-	2 - 4 ft	2.3-4.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 PS-FD-37	PS-FD-37	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-2-4	SSHS-B2025-SUB-2-4	7/26/2018	854.55	854.52	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-2-4	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-2-4	SSHS-B2050-SUB-2-4	7/26/2018	855.45	855.45	0.00	-	2 - 4 ft	2-4 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-2-4	SSHS-B2213-SUB-2-4	7/26/2018	855.06	855.53	0.47	-	2 - 4 ft	2.47-4.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-2-4	SSHS-B2215-SUB-2-4	7/26/2018	855.11	855.30	0.19	-	2 - 4 ft	2.19-4.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-2-4	SSHS-B2031-SUB-2-4	7/27/2018	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2385	090118 10:00 SSHS-B2385-SUB-2-4	SSHS-B2385-SUB-2-4	8/30/2018	855.00	855.38	0.38	-	2 - 4 ft	2.38-4.38 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2386	090118 10:00 SSHS-B2386-SUB-2-4	SSHS-B2386-SUB-2-4	8/30/2018	855.18	855.37	0.19	-	2 - 4 ft	2.19-4.19 ft	180-81525-1	Not Excavated							
Football Field	SSHS-B2639	052119 08:40 SSHS-B2639-SUB-2-4	SSHS-B2639-SUB-2-4	5/19/2019	855.11	855.38	0.27	-	2 - 4 ft	2.27-4.27 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2642	052119 08:40 SSHS-B2642-SUB-2-4	SSHS-B2642-SUB-2-4	5/19/2019	855.14	855.38	0.24	-	2 - 4 ft	2.24-4.24 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2643	052119 08:40 SSHS-B2643-SUB-2-4	SSHS-B2643-SUB-2-4	5/19/2019	854.91	855.38	0.47	-	2 - 4 ft	2.47-4.47 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2215A	052219 08:40 SSHS-B2215A-SUB-2-4	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated	< 0.0029 U	0.0051 J	< 0.0018 U	< 0.0044 U	< 0.0023 U	< 0.0029 U	< 0.0052 U
Football Field	SSHS-IRM3-S058D	080919 09:00 SSHS-IRM3-S058-D	SSHS-IRM3-S058-D	8/8/2019	-	856.42	-	853.72	2 - 4 ft	2.7 ft	180-93896-2	Not Excavated							
Football Field	SSHS-B2916	110919 09:30 SSHS-B2916-SUB-2-4	SSHS-B2916-SUB-2-4	11/7/2019	856.41	856.40	-0.01	-	2 - 4 ft	1.99-3.99 ft	180-98520-1	Not Excavated							
Football Field	IRM4-S041	SSHS-IRM4-S041-2-4-20200716	SSHS-IRM4-S041-2-4	7/16/2020	-	855.66	-	852.13	2 - 4 ft	3.53 ft	1801083941	Not Excavated							
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-2-4	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3474	072820 09:00 SSHS-B3474-SUB-2-4	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3475	072820 09:00 SSHS-B3475-SUB-2-4	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	SSHS-B3476	072820 09:00 SSHS-B3476-SUB-2-4	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B3477	072820 09:00 SSHS-B3477-SUB-2-4	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated	< 0.0025 U	0.0018 J	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Football Field	IRM4-S182S	SSHS-IRM4-S182S-20200813	SSHS-IRM4-S182S	8/13/2020	-	855.58	-	852.81	2 - 4 ft	2.78 ft	1801095841	Not Excavated							
Football Field	IRM4-S194N	SSHS-IRM4-S194N-20200813	SSHS-IRM4-S194N	8/13/2020	-	855.37	-	851.69	2 - 4 ft	3.68 ft	1801095841	Not Excavated							
Football Field	IRM5-B034	SSHS-IRM5-B034-20201216	SSHS-IRM5-B034	12/16/2020	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801150641	Not Excavated							
Football Field	IRM5-B034	SSHS-IRM5-B034-20210108	SSHS-IRM5-B034	1/8/2021	-	855.66	-	853.37	2 - 4 ft	2.29 ft	1801157731	Not Excavated	< 0.068 U	1	< 0.29 U	< 0.25 U	< 0.12 U	< 0.14 U	< 0.5 U
Football Field	IRM5-B066	SSHS-IRM5-B066-20210115	SSHS-IRM5-B066	1/15/2021	-	855.92	-	851.93	2 - 4 ft	3.99 ft	1801160721	Not Excavated							
Football Field	IRM5-B079	SSHS-IRM5-B079-20210115	SSHS-IRM5-B079	1/15/2021	-	856.12	-	852.93	2 - 4 ft	3.19 ft	1801160721	Not Excavated							
Football Field	IRM5-B013	SSHS-IRM5-B013-20210120	SSHS-IRM5-B013	1/20/2021	-	855.53	-	853.51	2 - 4 ft	2.02 ft	1801162461	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-2-4	SSHS-B3572-SUB-2-4	2/4/2021	855.42	855.51	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116864-1	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3593	020521 09:00 SSHS-B3593-SUB-2-4	SSHS-B3593-SUB-2-4	2/4/2021	854.95	855.33	0.38	-	2 - 4 ft	2.38-4.38 ft	180-116864-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3582	020621 10:00 DUP-34	DUP-34	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-2-4	SSHS-B3582-SUB-2-4	2/5/2021	855.93	855.93	0.00	-	2 - 4 ft	2-4 ft	180-116914-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-2-4	SSHS-B3583-SUB-2-4	2/5/2021	855.33	855.44	0.11	-	2 - 4 ft	2.11-4.11 ft	180-116914-1	Not Excavated	< 0.061 U	< 0.097 U	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	IRM5-S094	SSHS-IRM5-S094-2-4-20210215	SSHS-IRM5-S094-2-4	2/15/2021	-	855.51	-	852.03	2 - 4 ft	3.47 ft	1801173961	Not Excavated							
Football Field	IRM5-S019BOT	SSHS-IRM5-S019BOT-20210225	SSHS-IRM5-S019BOT	2/25/2021	-	856.43	-	854.39	2 - 4 ft	2.04 ft	1801176021	Not Excavated							
Football Field	IRM4A-PIPE1 BOT	SSHS-IRM4A-PIPE1 BOT-20210301	SSHS-IRM4A-PIPE1 BOT	3/1/2021	-	855.57	-	851.84	2 - 4 ft	3.73 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1S1	SSHS-IRM4A-PIPE1S1-20210301	SSHS-IRM4A-PIPE1S1	3/1/2021	-	855.57	-	852.28	2 - 4 ft	3.29 ft	1801177071	Not Excavated							
Football Field	IRM5-S300 BOT 1	SSHS-IRM5-S300 BOT1-20210304	SSHS-IRM5-S300 BOT1	3/4/2021	-	855.59	-	851.69	2 - 4 ft	3.91 ft	1801179111	Not Excavated							
Football Field	IRM5-PIPE 22	SSHS-IRM5-PIPE 22-20210316	SSHS-IRM5-PIPE 22	3/16/2021	-	855.37	-	852.51	2 - 4 ft	2.86 ft	1801185091	Not Excavated							
Football Field	IRM5-B006	SSHS-IRM5-DUP 24-20210326	SSHS-IRM5-DUP 24	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated							
Football Field	IRM5-B010	SSHS-IRM5-B010-20210326	SSHS-IRM5-B010	3/26/2021	-	855.48	-	852.75	2 - 4 ft	2.73 ft	1801191091	Not Excavated							
Football Field	IRM5-B006	SSHS-IRM5-B006-20210326	SSHS-IRM5-B006	3/26/2021	-	855.48	-	852.97	2 - 4 ft	2.51 ft	1801191091	Not Excavated							
Football Field	IRM5-B009	SSHS-IRM5-B009-20210326	SSHS-IRM5-B009	3/26/2021	-	855.47	-	852.68	2 - 4 ft	2.8 ft	1801191091	Not Excavated							
Football Field	IRM5-B007	SSHS-IRM5-B007-20210326	SSHS-IRM5-B007	3/26/2021	-	855.39	-	852.70	2 - 4 ft	2.69 ft	1801191091	Not Excavated							
Football Field	IRM5-B061	SSHS-IRM5-DUP 37-20210402	SSHS-IRM5-DUP 37	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated							
Football Field	IRM5-B098	SSHS-IRM5-B098-20210402	SSHS-IRM5-B098	4/2/2021	-	855.49	-	852.62	2 - 4 ft	2.87 ft	1801194611	Not Excavated							
Football Field	IRM5-B085	SSHS-IRM5-B085-20210402	SSHS-IRM5-B085	4/2/2021	-	855.55	-	852.72	2 - 4 ft	2.83 ft	1801194611	Not Excavated							
Football Field	IRM5-B061	SSHS-IRM5-B061-20210402	SSHS-IRM5-B061	4/2/2021	-	855.94	-	853.78	2 - 4 ft	2.16 ft	1801194611	Not Excavated							
Football Field	ISMP-S104	SSHS-ISMP-S104-20210408	SSHS-ISMP-S104	4/8/2021	-	855.33	-	851.48	2 - 4 ft	3.85 ft	1801197252	Not Excavated							
Football Field	ISMP-S109	SSHS-ISMP-S109-20210408	SSHS-ISMP-S109	4/8/2021	-	855.36	-	852.06	2 - 4 ft	3.3 ft	1801197252	Not Excavated							
Football Field	ISMP-S124	SSHS-ISMP-S124-20210408	SSHS-ISMP-S124	4/8/2021	-	855.38	-	852.31	2 - 4 ft	3.06 ft	1801197253	Not Excavated							
Football Field	ISMP-S142	SSHS-ISMP-S142-20210409	SSHS-ISMP-S142	4/9/2021	-	855.49	-	851.85	2 - 4 ft	3.65 ft	1801197961	Not Excavated							
Football Field	ISMP-S141	SSHS-ISMP-S141-20210409	SSHS-ISMP-S141	4/9/2021	-	855.49	-	852.23	2 - 4 ft	3.26 ft	1801197961	Not Excavated							
Football Field	IRM5-PIPE 39 S1A	SSHS-IRM5-PIPE 39 S1A-20210411	SSHS-IRM5-PIPE 39 S1A	4/11/2021	-	855.35	-	851.57	2 - 4 ft	3.78 ft	1801198481	Not Excavated							
Football Field	IRM5-B071	SSHS-IRM5-DUP 53-20210414	SSHS-IRM5-DUP 53	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated							
Football Field	IRM5-B172	SSHS-IRM5-B172-20210414	SSHS-IRM5-B172	4/14/2021	-	854.54	-	850.80	2 - 4 ft	3.74 ft	1801199782	Not Excavated							
Football Field	IRM5-B173	SSHS-IRM5-B173-20210414	SSHS-IRM5-B173	4/14/2021	-	854.85	-	851.84	2 - 4 ft	3 ft	1801199782	Not Excavated							
Football Field	IRM5-B109	SSHS-IRM5-B109-20210414	SSHS-IRM5-B109	4/14/2021	-	855.18	-	852.11	2 - 4 ft	3.07 ft	1801199782	Not Excavated							
Football Field	IRM5-B171	SSHS-IRM5-B171-20210414	SSHS-IRM5-B171	4/14/2021	-	854.95	-	851.76	2 - 4 ft	3.19 ft	1801199782	Not Excavated							
Football Field	IRM5-B095	SSHS-IRM5-B095-20210414	SSHS-IRM5-B095	4/14/2021	-	855.45	-	852.53	2 - 4 ft	2.92 ft	1801199781	Not Excavated							
Football Field	IRM5-B097	SSHS-IRM5-B097-20210414	SSHS-IRM5-B097	4/14/2021	-	855.48	-	852.80	2 - 4 ft	2.68 ft	1801199782	Not Excavated							
Football Field	IRM5-B125	SSHS-IRM5-B125-20210414	SSHS-IRM5-B125	4/14/2021	-	855.45	-	852.50	2 - 4 ft	2.95 ft	1801199782	Not Excavated							
Football Field	IRM5-B002A	SSHS-IRM5-B002A-20210414	SSHS-IRM5-B002A	4/14/2021	-	856.02	-	853.46	2 - 4 ft	2.56 ft	1801199783	Not Excavated							
Football Field	IRM5-B071	SSHS-IRM5-B071-20210414	SSHS-IRM5-B071	4/14/2021	-	855.49	-	852.64	2 - 4 ft	2.86 ft	1801199783	Not Excavated							
Football Field	IRM5-B005	SSHS-IRM5-B005-20210414	SSHS-IRM5-B005	4/14/2021	-	855.43	-	853.29	2 - 4 ft	2.14 ft	1801199782	Not Excavated							
Football Field	IRM5-B004	SSHS-IRM5-B004-20210414	SSHS-IRM5-B004	4/14/2021	-	855.70	-	853.27	2 - 4 ft	2.43 ft	1801199783	Not Excavated							
Football Field	IRM5-B016	SSHS-IRM5-B016-20210414	SSHS-IRM5-B016	4/14/2021	-	855.46	-	852.61	2 - 4 ft	2.85 ft	1801199783	Not Excavated							

DRAFT

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated							
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated							
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated							
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated							
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated							
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated							
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated							
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated							
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated							
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated							
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated							
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated							
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated							
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated							
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated							
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated							
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated							
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated							
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated							
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated							
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated							
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated							
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated							
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated							
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated							
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated							
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated							
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated							
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated							
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated							
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated							
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated							
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated							
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated							
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated								
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated								
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.011 U	< 0.00038 U	< 0.00067 U	< 0.00081 U	< 0.0013 U	< 0.0022 U	< 0.00062 U	< 0.0017 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0054 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0035 U	< 0.0032 U	< 0.0055 U	< 0.0028 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0069 U	< 0.0025 U	< 0.0053 U	< 0.0041 U	< 0.0044 U	< 0.0040 U	< 0.0070 U	< 0.0036 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0066 U	< 0.0024 U	< 0.0051 U	< 0.0039 U	< 0.0043 U	< 0.0039 U	< 0.0068 U	< 0.0034 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0033 U	< 0.0036 U	< 0.0033 U	< 0.0057 U	< 0.0029 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.0032 U	< 0.0012 U	< 0.0025 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0033 U	< 0.0017 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U

DRAFT

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated						
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated						
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated						
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated						
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated						
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated						
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated						
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated						
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated						
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated						
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated						
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated						
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated						
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated						
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated						
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated						
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated						
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated						
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated						
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated						
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated						
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated						
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated						
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated						
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated						
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated						
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated						
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated						
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated						
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated						
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated						
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated						
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated						
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated						
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated						
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated						
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated						
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated						
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated						
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated						
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated						
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated						
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated						
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated						
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated						
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated						
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.00049 U	< 0.0015 U	< 0.0015 U	< 0.00042 U	< 0.0012 U	< 0.00074 U	< 0.0019 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated						
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated						
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated						
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated						
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated						
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated						
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated						
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.0040 U	< 0.0022 U	< 0.0027 U	< 0.0033 U	< 0.0045 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0044 U	< 0.0051 U	< 0.0028 U	< 0.0035 U	< 0.0042 U	< 0.0057 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0042 U	< 0.0049 U	< 0.0027 U	< 0.0034 U	< 0.0040 U	< 0.0055 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.0042 U	< 0.0023 U	< 0.0028 U	< 0.0034 U	< 0.0046 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0028 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0021 U	< 0.0024 U	< 0.0013 U	< 0.0016 U	< 0.0020 U	< 0.0027 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated							
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated							
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated							
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated							
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated							
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated							
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated							
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated							
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated							
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated							
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated							
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated							
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated							
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated							
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated							
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated							
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated							
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated							
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated							
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated							
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated							
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated							
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated							
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated							
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated							
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated							
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated							
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated							
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated							
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated							
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated							
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated							
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated							
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated							
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated							
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated							
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated							
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated							
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.0064 U	< 0.00041 U	< 0.00051 U	< 0.00060 U	< 0.00044 U	< 0.00047 U	< 0.00037 U	< 0.00041 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0062 U	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.0020 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0079 U	< 0.0024 U	< 0.0044 U	< 0.0030 U	< 0.0054 U	< 0.0026 U	< 0.0028 U	< 0.0025 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0076 U	< 0.0023 U	< 0.0042 U	< 0.0028 U	< 0.0052 U	< 0.0025 U	< 0.0027 U	< 0.0024 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0064 U	< 0.0020 U	< 0.0036 U	< 0.0024 U	< 0.0044 U	< 0.0021 U	< 0.0023 U	< 0.0021 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.0037 U	< 0.0011 U	< 0.0021 U	< 0.0014 U	< 0.0025 U	< 0.0012 U	< 0.0013 U	< 0.0012 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated								
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated								
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated								
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated								
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated								
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated								
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated								
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated								
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated								
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated								
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated								
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated								
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated								
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated								
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated								
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated								
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated								
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated								
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated								
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated								
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated								
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated								
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated								
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated								
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated								
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated								
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated								
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated								
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated								
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated								
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated								
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated								
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated								
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated								
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated								
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated								
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated								
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated								
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated								
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated								
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated								
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated								
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated								
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated								
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.00098 U	< 0.00060 U	< 0.00080 U	< 0.00076 U	< 0.00046 U	< 0.0015 U	< 0.0020 U	< 0.00056 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0031 U	< 0.0056 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0031 U	< 0.0026 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0040 U	< 0.0072 U	< 0.0027 U	< 0.0031 U	< 0.0023 U	< 0.0039 U	< 0.0040 U	< 0.0033 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0038 U	< 0.0069 U	< 0.0026 U	< 0.0030 U	< 0.0023 U	< 0.0037 U	< 0.0038 U	< 0.0031 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0032 U	< 0.0058 U	< 0.0022 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0032 U	< 0.0026 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0022 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.0019 U	< 0.0034 U	< 0.0013 U	< 0.0014 U	< 0.0011 U	< 0.0018 U	< 0.0019 U	< 0.0015 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U

												Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.12		0.93
Restricted - Residential																	100		100
Protection of Groundwater																	0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated								
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated								
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated								
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated								
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated								
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated								
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated								
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated								
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated								
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated								
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated								
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated								
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated								
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated								
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated								
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated								
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated								
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated								
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated								
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated								
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated								
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated								
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated								
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated								
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated								
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated								
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated								
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated								
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated								
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated								
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated								
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated								
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated								
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated								
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated								
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated								
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated								
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated								
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated								
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated								
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated								
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated								
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated								
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated								
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.00069 U	< 0.0022 U	< 0.0010 U	< 0.0018 U	< 0.00066 U	< 0.0019 U	< 0.0020 U	< 0.0011 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0028 U	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0033 U	< 0.0035 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0035 U	< 0.0028 U	< 0.0046 U	< 0.013 U	< 0.0042 U	< 0.0045 U	< 0.0032 U	< 0.0026 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0027 U	< 0.0044 U	< 0.012 U	< 0.0041 U	< 0.0043 U	< 0.0031 U	< 0.0025 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0029 U	< 0.0022 U	< 0.0037 U	< 0.011 U	< 0.0034 U	< 0.0036 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0064 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0061 U	< 0.0020 U	< 0.0021 U	< 0.0015 U	< 0.0012 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated						
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated						
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated						
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated						
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated						
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated						
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated						
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated						
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated						
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated						
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated						
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated						
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated						
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated						
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated						
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated						
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated						
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated						
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated						
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated						
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated						
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated						
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated						
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated						
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated						
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated						
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated						
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated						
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated						
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated						
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated						
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated						
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated						
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated						
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated						
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated						
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated						
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated						
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated						
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated						
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated						
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated						
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated						
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated						
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated						
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated						
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.00062 U	< 0.00077 U	< 0.00039 U	< 0.00042 U	< 0.0016 U	< 0.0013 U	< 0.00095 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated						
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated						
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated						
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated						
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated						
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated						
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated						
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0038 U	< 0.0035 U	< 0.0023 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0026 U	< 0.0027 U	< 0.0035 U	< 0.0025 U	< 0.0048 U	< 0.0045 U	< 0.0029 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0026 U	< 0.0034 U	< 0.0024 U	< 0.0047 U	< 0.0043 U	< 0.0028 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0039 U	< 0.0036 U	< 0.0024 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.0018 U	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.0012 U	< 0.0013 U	< 0.0017 U	< 0.0012 U	< 0.0023 U	< 0.0021 U	< 0.0014 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-B030	SSHS-IRM5-B030-20210414	SSHS-IRM5-B030	4/14/2021	-	855.54	-	853.16	2 - 4 ft	2.38 ft	1801199783	Not Excavated							
Football Field	IRM5-B044	SSHS-IRM5-B044-20210414	SSHS-IRM5-B044	4/14/2021	-	855.59	-	853.22	2 - 4 ft	2.38 ft	1801199783	Not Excavated							
Football Field	IRM5-B032	SSHS-IRM5-B032-20210414	SSHS-IRM5-B032	4/14/2021	-	855.54	-	852.78	2 - 4 ft	2.76 ft	1801199782	Not Excavated							
Football Field	IRM5-B113	SSHS-IRM5-B113-20210414	SSHS-IRM5-B113	4/14/2021	-	855.45	-	853.27	2 - 4 ft	2.18 ft	1801199782	Not Excavated							
Football Field	IRM5-B126	SSHS-IRM5-B126-20210414	SSHS-IRM5-B126	4/14/2021	-	855.75	-	852.70	2 - 4 ft	3.05 ft	1801199783	Not Excavated							
Football Field	IRM5-B031	SSHS-IRM5-B031-20210414	SSHS-IRM5-B031	4/14/2021	-	855.63	-	852.95	2 - 4 ft	2.68 ft	1801199783	Not Excavated							
Football Field	IRM5-S169	SSHS-IRM5-S169-20210415	SSHS-IRM5-S169	4/15/2021	-	854.93	-	851.90	2 - 4 ft	3.03 ft	1801200642	Not Excavated							
Football Field	IRM5-S068	SSHS-IRM5-S068-20210415	SSHS-IRM5-S068	4/15/2021	-	855.65	-	851.84	2 - 4 ft	3.81 ft	1801200641	Not Excavated							
Football Field	IRM5-B142	SSHS-IRM5-B142-20210415	SSHS-IRM5-B142	4/15/2021	-	855.48	-	852.82	2 - 4 ft	2.66 ft	1801200642	Not Excavated							
Football Field	IRM5-B168	SSHS-IRM5-B168-20210415	SSHS-IRM5-B168	4/15/2021	-	852.72	-	849.34	2 - 4 ft	3.38 ft	1801200643	Not Excavated							
Football Field	IRM5-B160	SSHS-IRM5-B160-20210416	SSHS-IRM5-B160	4/16/2021	-	854.99	-	851.39	2 - 4 ft	3.6 ft	1801201431	Not Excavated							
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT 3-20210416	SSHS-IRM5-B118 BOT 3	4/16/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801201431	Not Excavated							
Football Field	IRM5-B118A	SSHS-IRM5-B118A-20210416	SSHS-IRM5-B118A	4/16/2021	-	855.56	-	852.40	2 - 4 ft	3.16 ft	1801201431	Not Excavated							
Football Field	IRM5-S025A	SSHS-IRM5-DUP 76-20210422	SSHS-IRM5-DUP 76	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204571	Not Excavated							
Football Field	IRM5-S025A	SSHS-IRM5-S025A-20210422	SSHS-IRM5-S025A	4/22/2021	-	855.38	-	851.86	2 - 4 ft	3.52 ft	1801204562	Not Excavated							
Football Field	IRM5-S057A	SSHS-IRM5-S057A-20210423	SSHS-IRM5-S057A	4/23/2021	-	855.29	-	852.36	2 - 4 ft	2.93 ft	1801205492	Not Excavated							
Football Field	IRM5-S057C	SSHS-IRM5-S057C-20210423	SSHS-IRM5-S057C	4/23/2021	-	854.91	-	852.73	2 - 4 ft	2.18 ft	1801205492	Not Excavated							
Football Field	IRM5-S057ABOT	SSHS-IRM5-S057A BOT-20210423	SSHS-IRM5-S057A BOT	4/23/2021	-	855.06	-	851.62	2 - 4 ft	3.44 ft	1801205491	Not Excavated							
Football Field	IRM5-B118 BOT3	SSHS-IRM5-B118 BOT3-20210423	SSHS-IRM5-B118 BOT3	4/23/2021	-	855.54	-	851.98	2 - 4 ft	3.56 ft	1801205492	Not Excavated							
Football Field	ISMP-B200	SSHS-ISMP-B200-20210426	SSHS-ISMP-B200	4/26/2021	-	855.31	-	852.76	2 - 4 ft	2.55 ft	1801206042	Not Excavated							
Football Field	ISMP-B201	SSHS-ISMP-B201-20210426	SSHS-ISMP-B201	4/26/2021	-	855.49	-	853.07	2 - 4 ft	2.42 ft	1801206042	Not Excavated							
Football Field	IRM5-S234A1	SSHS-IRM5-S234A1-20210430	SSHS-IRM5-S234A1	4/30/2021	-	855.82	-	852.48	2 - 4 ft	3.34 ft	1801209532	Not Excavated							
Football Field	IRM5-B078A2 S3	SSHS-IRM5-B078A2 S3-20210501	SSHS-IRM5-B078A2 S3	5/1/2021	-	856.13	-	852.59	2 - 4 ft	3.54 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 S1	SSHS-IRM5-B106 S1-20210501	SSHS-IRM5-B106 S1	5/1/2021	-	855.66	-	853.63	2 - 4 ft	2.03 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 S2	SSHS-IRM5-B106 S2-20210501	SSHS-IRM5-B106 S2	5/1/2021	-	855.60	-	853.39	2 - 4 ft	2.21 ft	1801210061	Not Excavated							
Football Field	IRM5-B106 BOT 1	SSHS-IRM5-B106 BOT 1-20210501	SSHS-IRM5-B106 BOT 1	5/1/2021	-	855.54	-	851.96	2 - 4 ft	3.58 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 S1	SSHS-IRM5-PIPE 47 S1-20210504	SSHS-IRM5-PIPE 47 S1	5/4/2021	-	855.03	-	851.92	2 - 4 ft	3.11 ft	1801211061	Not Excavated							
Football Field	IRM5-PIPE 47 BOT 2	SSHS-IRM5-PIPE 47 BOT 2-20210504	SSHS-IRM5-PIPE 47 BOT 2	5/4/2021	-	855.45	-	851.46	2 - 4 ft	3.99 ft	1801211061	Not Excavated							
Football Field	IRM5-PIPE 47 S2	SSHS-IRM5-PIPE 47 S2-20210504	SSHS-IRM5-PIPE 47 S2	5/4/2021	-	855.16	-	851.96	2 - 4 ft	3.2 ft	1801211061	Not Excavated							
Football Field	IRM5-B078A2S6 BOT 3	SSHS-IRM5-B078A2S6 BOT 3-20210507	SSHS-IRM5-B078A2S6 BOT 3	5/7/2021	-	855.80	-	852.85	2 - 4 ft	2.95 ft	1801213531	Not Excavated							
Football Field	IRM5-B078A2S6 BOT 1	SSHS-IRM5-B078A2S6 BOT 1-20210507	SSHS-IRM5-B078A2S6 BOT 1	5/7/2021	-	855.84	-	852.59	2 - 4 ft	3.25 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S13	SSHS-IRM5-S643 S13-20210509	SSHS-IRM5-S643 S13	5/9/2021	-	855.69	-	852.45	2 - 4 ft	3.24 ft	1801213911	Not Excavated							
Football Field	ISMP-B500	SSHS-ISMP-B500-20210514	SSHS-ISMP-B500	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated							
Football Field	ISMP-B500	SSHS-ISMP-DUP 3-20210514	SSHS-ISMP-DUP 3	5/14/2021	-	855.64	-	852.48	2 - 4 ft	3.16 ft	1801216751	Not Excavated							
Football Field	ISMP-B507	SSHS-ISMP-DUP 2-20210514	SSHS-ISMP-DUP 2	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B502	SSHS-ISMP-B502-20210514	SSHS-ISMP-B502	5/14/2021	-	856.01	-	852.98	2 - 4 ft	3.03 ft	1801216751	Not Excavated							
Football Field	ISMP-B507	SSHS-ISMP-B507-20210514	SSHS-ISMP-B507	5/14/2021	-	856.11	-	853.37	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B512	SSHS-ISMP-B512-20210514	SSHS-ISMP-B512	5/14/2021	-	855.64	-	852.97	2 - 4 ft	2.67 ft	1801216751	Not Excavated							
Football Field	ISMP-B518	SSHS-ISMP-B518-20210514	SSHS-ISMP-B518	5/14/2021	-	855.59	-	852.85	2 - 4 ft	2.74 ft	1801216751	Not Excavated							
Football Field	ISMP-B524	SSHS-ISMP-B524-20210514	SSHS-ISMP-B524	5/14/2021	-	855.63	-	851.88	2 - 4 ft	3.75 ft	1801216751	Not Excavated							
Football Field	IRM5-B118Y	SSHS-IRM5-B118Y-20210524	SSHS-IRM5-B118Y	5/24/2021	-	855.39	-	851.87	2 - 4 ft	3.52 ft	1801221151	Not Excavated							
Football Field	ISMP-S510	SSHS-ISMP-S510-20210527	SSHS-ISMP-S510	5/27/2021	-	855.72	-	851.77	2 - 4 ft	3.95 ft	1801223381	Not Excavated							
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210605	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61-20210607	SSHS-ISMP-B527 S61	6/7/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228231	Not Excavated	< 0.0010 U	0.032	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-S522	SSHS-ISMP-S522-20210609	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 0.0011 U	0.049	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-S523	SSHS-ISMP-S523-20210609	SSHS-ISMP-S523	6/9/2021	-	855.54	-	851.70	2 - 4 ft	3.83 ft	1801229791	Not Excavated							
Football Field	ISMP-S526	SSHS-ISMP-S526-20210610	SSHS-ISMP-S526	6/10/2021	-	855.63	-	851.62	2 - 4 ft	4.01 ft	1801230401	Not Excavated							
Football Field	IRM5-P18 S5A S18	SSHS-IRM5-P18 S5A S18-20210615	SSHS-IRM5-P18 S5A S18	6/15/2021	-	855.89	-	852.29	2 - 4 ft	3.6 ft	1801232172	Not Excavated							
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210617	SSHS-ISMP-B527 S78	6/17/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801233581	Not Excavated							
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210618	SSHS-ISMP-B527 S78	6/18/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801234402	Not Excavated	< 0.00061 U	< 0.00034 U	< 0.0014 U	< 0.00095 U	< 0.00042 U	< 0.00046 U	< 0.00085 U
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78-20210623	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106-20210628	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 0.00099 U	0.013	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110-20210628	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	IRM5-FIS BOT 33	SSHS-IRM5-FIS BOT 33-20210628	SSHS-IRM5-FIS BOT 33	6/28/2021	-	853.46	-	850.34	2 - 4 ft	3.13 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S219	SSHS-IRM5-FIS S219-20210628	SSHS-IRM5-FIS S219	6/28/2021	-	853.49	-	851.01	2 - 4 ft	2.49 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 39	SSHS-IRM5-FIS BOT 39-20210628	SSHS-IRM5-FIS BOT 39	6/28/2021	-	854.47	-	851.23	2 - 4 ft	3.24	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 42	SSHS-IRM5-FIS BOT 42-20210628	SSHS-IRM5-FIS BOT 42	6/28/2021	-	855.14	-	851.46	2 - 4 ft	3.67 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS BOT 43	SSHS-IRM5-FIS BOT 43-20210628	SSHS-IRM5-FIS BOT 43	6/28/2021	-	855.11	-	851.97	2 - 4 ft	3.14 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S254	SSHS-IRM5-FIS S254-20210720	SSHS-IRM5-FIS S254	7/20/2021	-	854.99	-	851.23	2 - 4 ft	3.75 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S301	SSHS-IRM5-FIS S301-20210821	SSHS-IRM5-FIS S301	8/21/2021	-	855.12	-	851.39	2 - 4 ft	3.73 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3-20210828	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8-20210828	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11-20210828	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15-20210829	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15V-20210830	SSHS-ISMP-CB-7 S15V	8/30/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264191	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0057 U	< 0.0050 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11V-20210830	SSHS-ISMP-CB-7 S11V	8/30/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0073 U	< 0.0063 U	< 0.0031 U	< 0.0035 U	< 0.013 U
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3V-20210830	SSHS-ISMP-CB-7 S3V	8/30/2021	-	855.92	-	852.55	2 - 4 ft	3.37 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0070 U	< 0.0061 U	< 0.0030 U	< 0.0034 U	< 0.012 U
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8V-20210830	SSHS-ISMP-CB-7 S8V	8/30/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801264191	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0059 U	< 0.0051 U	< 0.0025 U	< 0.0029 U	< 0.01 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-2-4	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-2-4	SSHS-B4165-SUB-2-4	9/23/2021	856.00	856.00	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0083 U
Football Field	ISMP-S601	SSHS-ISMP-S601-20211007	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 0.00087 U	< 0.0014 U	< 0.0036 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0063 U
Football Field	ISMP-S604	SSHS-ISMP-S604-20211007	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	ISMP-S608	SSHS-ISMP-S608-20211007	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 0.00082 U	< 0.0013 U	< 0.0034 U	< 0.0030 U	< 0.0015 U	< 0.0017 U	< 0.0060 U
Football Field	SLT-S11	SSHS-ISMP-SLT-S11-20211014	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 0.0012 U	0.0051 J	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0055 U	< 0.0020 U	< 0.0042 U	< 0.0033 U	< 0.0035 U	< 0.0032 U	< 0.0056 U	< 0.0029 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	0.0077	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	0.012	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.2 U	< 0.071 U	< 0.15 U	< 0.12 U	< 0.13 U	< 0.11 U	< 0.2 U	< 0.1 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.24 U	< 0.085 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0041 U	< 0.0021 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 UT	< 0.0043 UT	< 0.0022 UT
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 UT	< 0.0048 U	< 0.0025 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 UT	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated								
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	0.0062 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 UT	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.0077 U	< 0.00035 U	< 0.00038 UT	< 0.00035 U	< 0.00057 U	< 0.0013 U	< 0.00036 U	< 0.00052 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 UT	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 UT	< 0.00034 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 UT	< 0.00042 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 UT	< 0.00042 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 UT	< 0.00041 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 UT	< 0.00035 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.0089 U	< 0.00040 U	< 0.00044 U	< 0.00040 U	< 0.00066 U	< 0.0016 U	< 0.00042 UT	< 0.00060 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0058 U	< 0.0021 U	< 0.0045 U	< 0.0035 U	< 0.0037 U	< 0.0034 U	< 0.0059 U	< 0.0030 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0042 UHT	< 0.0015 UHT	< 0.0032 UHT	< 0.0025 UHT	< 0.0027 UHT	< 0.0024 UHT	< 0.0043 UHT	< 0.0022 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0041 UHT	< 0.0015 UHT	< 0.0032 UHT	< 0.0025 UHT	< 0.0027 UHT	< 0.0024 UHT	< 0.0042 UHT	< 0.0021 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0043 UHT	< 0.0016 UHT	< 0.0033 UHT	< 0.0026 UHT	< 0.0028 UHT	< 0.0025 UHT	< 0.0044 UHT	< 0.0022 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0041 UHT	< 0.0015 UHT	< 0.0031 UHT	< 0.0024 UHT	< 0.0026 UHT	< 0.0024 UHT	< 0.0042 UHT	< 0.0021 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Football Field	SSHS-B432	PS-FD-1	082316 09:15 PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B432	SSHS-B432-SUB-4-6	082316 09:15 SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B421	SSHS-B421-SUB-4-6	082416 08:45 SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B422	SSHS-B422-SUB-4-6	082416 08:45 SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B433	SSHS-B433-SUB-4-6	082416 08:45 SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B456	SSHS-B456-SUB-4-6	090616 09:00 SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated								
Football Field	SSHS-B451	SSHS-B451-SUB-4-6	092916 09:00 SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	SSHS-B452-SUB-4-6	092916 09:00 SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B2185	PS-FD-16	072518 09:00 PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2185	SSHS-B2185-SUB-4-6	072518 09:00 SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	SSHS-B2186-SUB-4-6	072518 09:00 SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	SSHS-B2187-SUB-4-6	072518 09:00 SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	SSHS-B2197-SUB-4-6	072518 09:00 SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	SSHS-B2070-SUB-4-6	072618 08:50 SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0018 U	< 0.0035 U	< 0.0041 U	< 0.0023 U	< 0.0028 UT	< 0.0034 U	< 0.0045 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.066 U	< 0.13 U	< 0.15 U	< 0.081 U	< 0.1 U	< 0.12 U	< 0.16 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.079 U	< 0.15 U	< 0.18 U	< 0.097 U	< 0.12 U	< 0.14 U	< 0.2 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UT	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0017 U	< 0.0021 UT	< 0.0026 UT	< 0.0035 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0015 U	< 0.0028 UT	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 UT
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated							
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0018 J	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0019 J	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 UT	< 0.00048 U	< 0.00025 U	< 0.00051 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00070 U	< 0.0013 UT	< 0.00059 U	< 0.00030 U	< 0.00062 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 UT	< 0.00046 U	< 0.00024 U	< 0.00049 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00019 U	< 0.00020 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00028 U	< 0.00030 UT	< 0.00082 U	< 0.0015 U	< 0.00068 U	< 0.00035 U	< 0.00072 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0019 U	< 0.0037 U	< 0.0043 UT	< 0.0024 U	< 0.0029 U	< 0.0035 U	< 0.0048 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 UT	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0042 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0014 UHT	< 0.0027 UHT	< 0.0031 UHT	< 0.0017 UHT	< 0.0021 UHT	< 0.0026 UHT	< 0.0035 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0014 UHT	< 0.0026 UHT	< 0.0031 UHT	< 0.0017 UHT	< 0.0021 UHT	< 0.0025 UHT	< 0.0034 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0014 UHT	< 0.0027 UHT	< 0.0032 UHT	< 0.0018 UHT	< 0.0022 UHT	< 0.0026 UHT	< 0.0036 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0014 UHT	< 0.0026 UHT	< 0.0031 UHT	< 0.0017 UHT	< 0.0021 UHT	< 0.0025 UHT	< 0.0034 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Football Field	SSHS-B432	082316 09:15_PS-FD-1	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated							
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-4-6	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated							
Football Field	SSHS-B421	082416 08:45_SSHS-B421-SUB-4-6	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B422	082416 08:45_SSHS-B422-SUB-4-6	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B433	082416 08:45_SSHS-B433-SUB-4-6	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B456	090616 09:00_SSHS-B456-SUB-4-6	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-4-6	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-4-6	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0063 U	< 0.0019 U	< 0.0035 UT	< 0.0024 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.0020 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 UT	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00037 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.23 U	< 0.069 U	< 0.13 U	< 0.085 U	< 0.16 U	< 0.076 U	< 0.081 U	< 0.073 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.27 U	< 0.083 U	< 0.15 UT	< 0.1 U	< 0.19 U	< 0.091 U	< 0.097 U	< 0.087 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 UT	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 UT
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 UT	< 0.0016 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated								
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00046 U	< 0.00049 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00022 U	< 0.00032 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.0018 U	< 0.00028 U	< 0.00053 U	< 0.00056 U	< 0.00057 U	< 0.00035 U	< 0.00032 U	< 0.00046 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0067 U	< 0.0020 U	< 0.0037 U	< 0.0025 U	< 0.0046 U	< 0.0022 U	< 0.0024 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0048 UHT	< 0.0015 UHT	< 0.0027 UHT	< 0.0018 UHT	< 0.0033 UHT	< 0.0016 UHT	< 0.0017 UHT	< 0.0015 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0048 UHT	< 0.0014 UHT	< 0.0026 UHT	< 0.0018 UHT	< 0.0033 UHT	< 0.0016 UHT	< 0.0017 UHT	< 0.0015 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0050 UHT	< 0.0015 UHT	< 0.0028 UHT	< 0.0019 UHT	< 0.0034 UHT	< 0.0017 UHT	< 0.0018 UHT	< 0.0016 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0047 UHT	< 0.0014 UHT	< 0.0026 UHT	< 0.0018 UHT	< 0.0032 UHT	< 0.0016 UHT	< 0.0017 UHT	< 0.0015 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Football Field	SSHS-B432	082316 09:15 PS-FD-1	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B432	082316 09:15 SSHS-B432-SUB-4-6	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B421	082416 08:45 SSHS-B421-SUB-4-6	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B422	082416 08:45 SSHS-B422-SUB-4-6	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B433	082416 08:45 SSHS-B433-SUB-4-6	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B456	090616 09:00 SSHS-B456-SUB-4-6	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-4-6	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-4-6	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0032 U	< 0.0057 U	< 0.0021 U	< 0.0025 U	< 0.0019 U	< 0.0031 U	< 0.0032 U	< 0.0026 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00031 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.11 U	< 0.21 U	< 0.076 U	< 0.088 U	< 0.067 U	< 0.11 U	< 0.11 U	< 0.093 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.14 U	< 0.25 U	< 0.091 U	< 0.11 U	< 0.08 U	< 0.13 U	< 0.14 U	< 0.11 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0024 UT	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 UT	< 0.0025 UT	< 0.0025 UT	< 0.0021 U
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 UT	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated								
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 UT	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00048 UT	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 UT	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 UT	< 0.00017 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 UT	< 0.00022 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 UT	< 0.00022 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 UT	< 0.00021 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 UT	< 0.00018 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00035 U	< 0.00060 U	< 0.00056 U	< 0.00038 U	< 0.00066 U	< 0.00043 U	< 0.00042 UT	< 0.00031 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0034 U	< 0.0061 U	< 0.0022 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0033 U	< 0.0027 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0029 U	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0024 UHT	< 0.0044 UHT	< 0.0016 UHT	< 0.0019 UHT	< 0.0014 UHT	< 0.0024 UHT	< 0.0024 UHT	< 0.0020 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0024 UHT	< 0.0043 UHT	< 0.0016 UHT	< 0.0018 UHT	< 0.0014 UHT	< 0.0023 UHT	< 0.0024 UHT	< 0.0020 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0025 UHT	< 0.0045 UHT	< 0.0017 UHT	< 0.0019 UHT	< 0.0015 UHT	< 0.0024 UHT	< 0.0025 UHT	< 0.0020 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0024 UHT	< 0.0043 UHT	< 0.0016 UHT	< 0.0018 UHT	< 0.0014 UHT	< 0.0023 UHT	< 0.0024 UHT	< 0.0019 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B432	082316 09:15 PS-FD-1	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B432	082316 09:15 SSHS-B432-SUB-4-6	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B421	082416 08:45 SSHS-B421-SUB-4-6	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B422	082416 08:45 SSHS-B422-SUB-4-6	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B433	082416 08:45 SSHS-B433-SUB-4-6	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B456	090616 09:00 SSHS-B456-SUB-4-6	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-4-6	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-4-6	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated								

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0028 U	< 0.0022 U	< 0.0037 U	< 0.01 U	< 0.0034 U	< 0.0036 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.00037 U	< 0.0021 UT	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.1 U	< 0.079 U	< 0.13 U	< 0.37 U	< 0.12 U	< 0.13 U	< 0.092 U	< 0.074 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.12 U	< 0.095 U	< 0.16 U	< 0.44 U	< 0.15 U	< 0.15 U	< 0.11 U	< 0.089 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 UT	< 0.0027 UT	< 0.0020 UT	< 0.0016 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 UT	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0028 UT	< 0.0021 UT	< 0.0016 UT
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated								
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 UT
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00038 U	< 0.0058 U	< 0.00067 U	< 0.00050 U	< 0.0021 U	< 0.00069 UT
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 UT
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00047 U	< 0.0027 U	< 0.00045 U	< 0.0067 U	< 0.00078 U	< 0.00057 U	< 0.0024 U	< 0.00080 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0030 U	< 0.0023 U	< 0.0039 U	< 0.011 U	< 0.0036 U	< 0.0038 U	< 0.0027 U	< 0.0022 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0021 UHT	< 0.0017 UHT	< 0.0028 UHT	< 0.0079 UHT	< 0.0026 UHT	< 0.0027 UHT	< 0.0020 UHT	< 0.0016 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0021 UHT	< 0.0017 UHT	< 0.0027 UHT	< 0.0078 UHT	< 0.0025 UHT	< 0.0027 UHT	< 0.0019 UHT	< 0.0016 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0022 UHT	< 0.0017 UHT	< 0.0029 UHT	< 0.0081 UHT	< 0.0027 UHT	< 0.0028 UHT	< 0.0020 UHT	< 0.0016 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0021 UHT	< 0.0016 UHT	< 0.0027 UHT	< 0.0077 UHT	< 0.0025 UHT	< 0.0027 UHT	< 0.0019 UHT	< 0.0015 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Football Field	SSHS-B432	082316 09:15_PS-FD-1	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-4-6	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated								
Football Field	SSHS-B421	082416 08:45_SSHS-B421-SUB-4-6	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B422	082416 08:45_SSHS-B422-SUB-4-6	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B433	082416 08:45_SSHS-B433-SUB-4-6	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated								
Football Field	SSHS-B456	090616 09:00_SSHS-B456-SUB-4-6	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-4-6	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-4-6	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0039 U	< 0.0036 U	< 0.0023 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.00034 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.00034 UT	< 0.00026 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.076 U	< 0.077 U	< 0.1 U	< 0.073 U	< 0.14 U	< 0.13 U	< 0.084 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.091 U	< 0.092 U	< 0.12 U	< 0.087 U	< 0.17 UT	< 0.15 UT	< 0.1 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0016 U	< 0.0016 UT	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 UT
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 UT	< 0.0016 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated							
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.00037 U	< 0.00029 U	< 0.00041 U	< 0.00032 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	0.00023 J	< 0.00016 U	< 0.00031 U	< 0.00020 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.00033 J	< 0.00020 U	< 0.00039 U	< 0.00025 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00043 U	< 0.00033 U	< 0.00048 U	< 0.00037 U	< 0.00028 U	< 0.00056 U	< 0.00036 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0030 U	< 0.0021 U	< 0.0041 U	< 0.0038 U	< 0.0025 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U	< 0.0021 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0016 UHT	< 0.0016 UHT	< 0.0022 UHT	< 0.0015 UHT	< 0.0029 UHT	< 0.0027 UHT	< 0.0018 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0016 UHT	< 0.0016 UHT	< 0.0021 UHT	< 0.0015 UHT	< 0.0029 UHT	< 0.0027 UHT	< 0.0018 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0017 UHT	< 0.0017 UHT	< 0.0022 UHT	< 0.0016 UHT	< 0.0030 UHT	< 0.0028 UHT	< 0.0018 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0016 UHT	< 0.0016 UHT	< 0.0021 UHT	< 0.0015 UHT	< 0.0029 UHT	< 0.0027 UHT	< 0.0017 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0015 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Football Field	SSHS-B432	082316 09:15_PS-FD-1	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated							
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-4-6	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated							
Football Field	SSHS-B421	082416 08:45_SSHS-B421-SUB-4-6	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B422	082416 08:45_SSHS-B422-SUB-4-6	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B433	082416 08:45_SSHS-B433-SUB-4-6	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B456	090616 09:00_SSHS-B456-SUB-4-6	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-4-6	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-4-6	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001-20211027	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0058 U	< 0.0051 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002-20211027	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 0.0012 U	0.0019 J	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	ISMP-S621	SSHS-ISMP-S621-20211202	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 0.00015 U	0.00064 J	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Football Field	SLT-S42	SSHS-ISMP-SLT-S42-20211207	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 0.00022 U	0.00069 J	< 0.00050 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00080 U
Football Field	SLT-S43	SSHS-ISMP-SLT-S43-20211207	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 0.00016 U	0.0043	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00056 U
Football Field	ISMP-S662	SSHS-ISMP-S662-20211216	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 0.00022 U	0.00075 J	< 0.00050 U	< 0.00067 U	< 0.00021 UT	< 0.00024 UT	< 0.00079 UT
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI-20211230	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.05 U	0.34	< 0.21 U	< 0.18 U	< 0.09 U	< 0.1 U	< 0.36 U
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3-20211230	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 0.0011 U	0.015	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3-20220103	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1-20220103	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 0.06 U	1.2	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14-20220107	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 0.0010 U	0.11	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	SLT-S50	SSHS-ISMP-SLT-S50-20220110	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9-20220112	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	SLT-S52	SSHS-ISMP-SLT-S52-20220112	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SLT-S54	SSHS-ISMP-SLT-S54-20220112	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	ISMP-S670	SSHS-ISMP-S670-20220228	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 0.0010 U	0.031 T	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-S679	SSHS-ISMP-S679-20220228	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 0.0011 U	0.018	< 0.0044 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	ISMP-S689	SSHS-ISMP-S689-20220228	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 0.0012 U	< 0.0019 UT	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4-20220228	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 0.0011 U	0.03	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10-20220301	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	ISMP-S703	SSHS-ISMP-S703-20220301	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 0.0011 U	0.0075	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B-20220301	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SLT-S67	SSHS-ISMP-SLT-S67-20220301	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SLT-S61	SSHS-ISMP-SLT-S61-20220301	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220305	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3-20220307	SSHS-ISMP-PIPE3-S3	3/7/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 0.0011 U	0.0084	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	ISMP-S2003	SSHS-ISMP-S2003-20220308	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 0.0011 U	0.0080	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-S2013	SSHS-ISMP-S2013-20220309	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 0.0012 U	0.05	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79-20220322	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29-20220324	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Football Field	SLT-S97	SSHS-ISMP-SLT-S97-20220324	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3-20220324	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Football Field	IRM5-FP-S7S	SSHS-IRM5-FP-S7S-20220328	SSHS-IRM5-FP-S7S	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated							
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7-20220328	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1-20220330	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5-20220330	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1-20220519	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2-20220519	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1-20220527	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 0.0011 U	0.021	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2-20220527	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3-20220527	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5-20220620	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated	< 0.00020 U	0.0029	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3-20220620	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00055 U	< 0.00074 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT-20220620	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1-20220801	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2-20220801	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4-20220801	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1-20220801	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2-20220801	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.93	1801422541	Not Excavated	< 0.00016 U	0.00044 J	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3-20220801	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated	0.0020	0.0020	< 0.00063 U	< 0.00085 U	< 0.00027 U	< 0.00030 U	< 0.00027 U
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6-20220822	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0062 U	< 0.0053 U	< 0.0026 U	< 0.0030 U	< 0.011 U
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7-20220822	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4-20220822	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5-20220825	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 0.0011 UHT	< 0.0017 UHT	< 0.0044 UHT	< 0.0039 UHT	< 0.0019 UHT	< 0.0022 UHT	< 0.0077 UHT
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9-20220825	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 0.0010 UHT	< 0.0017 UHT	< 0.0044 UHT	< 0.0038 UHT	< 0.0019 UHT	< 0.0021 UHT	< 0.0076 UHT
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10-20220825	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 0.0011 UHT	< 0.0017 UHT	< 0.0046 UHT	< 0.0040 UHT	< 0.0020 UHT	< 0.0022 UHT	< 0.0080 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6-20220825	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 0.0010 UHT	< 0.0016 UHT	< 0.0043 UHT	< 0.0038 UHT	< 0.0019 UHT	< 0.0021 UHT	< 0.0075 UHT
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14-20220825	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18-20220829	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0038 U	< 0.0033 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16-20220829	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Football Field	SSHS-B432	082316 09:15_PS-FD-1	PS-FD-1	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated							
Football Field	SSHS-B432	082316 09:15_SSHS-B432-SUB-4-6	SSHS-B432-SUB-4-6	8/22/2016	855.16	855.27	0.11	-	4 - 6 ft	4.11-6.11 ft	180-57858-1	Not Excavated							
Football Field	SSHS-B421	082416 08:45_SSHS-B421-SUB-4-6	SSHS-B421-SUB-4-6	8/23/2016	854.90	855.42	0.52	-	4 - 6 ft	4.52-6.52 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B422	082416 08:45_SSHS-B422-SUB-4-6	SSHS-B422-SUB-4-6	8/23/2016	855.04	855.52	0.48	-	4 - 6 ft	4.48-6.48 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B433	082416 08:45_SSHS-B433-SUB-4-6	SSHS-B433-SUB-4-6	8/23/2016	855.58	855.58	0.00	-	4 - 6 ft	4-6 ft	180-57888-1	Not Excavated							
Football Field	SSHS-B456	090616 09:00_SSHS-B456-SUB-4-6	SSHS-B456-SUB-4-6	8/30/2016	855.99	855.99	0.00	-	4 - 6 ft	4-6 ft	180-58129-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-4-6	SSHS-B451-SUB-4-6	9/27/2016	854.61	855.67	1.06	-	4 - 6 ft	5.06-7.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-4-6	SSHS-B452-SUB-4-6	9/27/2016	854.99	855.46	0.47	-	4 - 6 ft	4.47-6.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_PS-FD-16	PS-FD-16	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-4-6	SSHS-B2185-SUB-4-6	7/24/2018	855.07	855.49	0.42	-	4 - 6 ft	4.42-6.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-4-6	SSHS-B2186-SUB-4-6	7/24/2018	854.94	855.41	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-4-6	SSHS-B2187-SUB-4-6	7/24/2018	856.10	856.10	0.00	-	4 - 6 ft	4-6 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-4-6	SSHS-B2197-SUB-4-6	7/24/2018	854.99	855.43	0.44	-	4 - 6 ft	4.44-6.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-4-6	SSHS-B2070-SUB-4-6	7/25/2018	854.72	855.22	0.50	-	4 - 6 ft	4.5-6.5 ft	180-80157-3	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2362	082918 09:00 SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated							
Football Field	SSHS-B2523	103118 09:00 SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated							
Football Field	SSHS-B2685	051819 10:00 SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	0.034 BJ	< 0.0026 U	< 0.0025 U	< 0.0031 U	< 0.0034 U	< 0.0059 U	< 0.0039 U	< 0.0043 U
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B2943	110719 09:00 SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2925	110719 09:00 SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated							
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated							
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated							
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated							
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated							
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated							
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated							
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated							
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated							
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated							
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated							
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated							
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated							
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3576	020421 09:30 DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.28 U	< 0.1 U	< 0.22 U	< 0.17 U	< 0.18 U	< 0.16 U	< 0.29 U	< 0.15 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.2 U	< 0.073 U	< 0.16 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.21 U	< 0.11 U
Football Field	SSHS-B3581	020621 10:00 DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.23 U	< 0.085 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated								
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated								
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated								
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated								
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated								
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated								
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated								
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated								

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated						
Football Field	SSHS-B2362	082918 09:00 SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated						
Football Field	SSHS-B2523	103118 09:00 SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated						
Football Field	SSHS-B2685	051819 10:00 SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.0021 U	< 0.0031 U	< 0.0034 U	< 0.0028 U	< 0.0050 U	< 0.0016 U	< 0.0040 UT
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated						
Football Field	SSHS-B2943	110719 09:00 SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated						
Football Field	SSHS-B2925	110719 09:00 SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated						
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated						
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated						
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated						
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated						
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated						
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated						
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated						
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated						
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated						
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated						
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated						
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated						
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated						
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated						
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated						
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 UJ	< 0.003 U	< 0.004 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3576	020421 09:30 DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.094 U	< 0.18 U	< 0.21 U	< 0.12 U	< 0.14 U	< 0.17 U	< 0.23 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.067 U	< 0.13 U	< 0.15 U	< 0.083 U	< 0.1 U	< 0.12 U	< 0.17 U
Football Field	SSHS-B3581	020621 10:00 DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.078 U	< 0.15 U	< 0.18 U	< 0.097 U	< 0.12 U	< 0.14 U	< 0.2 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated						
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated						
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated						
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated						
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated						
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated						
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated						
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated						
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated						

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2362	082918 09:00 SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated							
Football Field	SSHS-B2523	103118 09:00 SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated							
Football Field	SSHS-B2685	051819 10:00 SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.0050 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0021 U	< 0.0013 U	< 0.0024 U	< 0.0019 U
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B2943	110719 09:00 SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2925	110719 09:00 SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated							
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	0.0058	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated							
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated							
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated							
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated							
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated							
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated							
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated							
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated							
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated							
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated							
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated							
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated							
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30 DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.33 U	< 0.099 U	< 0.18 U	< 0.12 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.1 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.23 U	< 0.071 U	< 0.13 U	< 0.087 U	< 0.16 U	< 0.078 U	< 0.083 U	< 0.075 U
Football Field	SSHS-B3581	020621 10:00 DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.27 U	< 0.083 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.09 U	< 0.096 U	< 0.087 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 UJ	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated							
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated							
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated							
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated							
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated							
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated							
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated							
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated							

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2192	072718 09:00_PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00_SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2362	082918 09:00_SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated								
Football Field	SSHS-B2523	103118 09:00_SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated								
Football Field	SSHS-B2685	051819 10:00_SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2709	052119 08:40_SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.0037 U	< 0.0052 U	< 0.0021 U	< 0.0033 U	< 0.0032 U	< 0.0021 U	< 0.0023 U	< 0.0028 U
Football Field	SSHS-IRM3-S058	080319 09:30_SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S084	080319 09:30_SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B2943	110719 09:00_SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2925	110719 09:00_SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated								
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated								
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated								
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated								
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated								
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated								
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated								
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated								
Football Field	SSHS-B3503	090120 10:30_SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated								
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated								
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated								
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated								
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated								
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated								
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated								
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0028 U	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3576	020421 09:30_DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.16 U	< 0.29 U	< 0.11 U	< 0.13 U	< 0.096 U	< 0.16 U	< 0.16 U	< 0.13 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.12 UJ	< 0.21 U	< 0.078 U	< 0.091 U	< 0.069 U	< 0.11 U	< 0.12 U	< 0.096 U
Football Field	SSHS-B3581	020621 10:00_DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.14 UJ	< 0.25 U	< 0.091 U	< 0.11 U	< 0.08 U	< 0.13 U	< 0.14 U	< 0.11 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated								
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated								
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated								
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated								
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated								
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated								
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated								
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2362	082918 09:00 SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated								
Football Field	SSHS-B2523	103118 09:00 SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated								
Football Field	SSHS-B2685	051819 10:00 SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.0025 U	< 0.0055 U	< 0.0030 U	< 0.0077 U	< 0.0027 U	0.0089	< 0.0024 U	< 0.0048 U
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B2943	110719 09:00 SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2925	110719 09:00 SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated								
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated								
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated								
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated								
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated								
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated								
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated								
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated								
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated								
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated								
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated								
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated								
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated								
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated								
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated								
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30 DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.14 U	< 0.11 U	< 0.19 U	< 0.53 U	< 0.17 U	< 0.18 U	< 0.13 U	< 0.11 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.1 U	< 0.081 U	< 0.13 U	< 0.38 U	< 0.13 U	< 0.13 U	< 0.095 U	< 0.076 U
Football Field	SSHS-B3581	020621 10:00 DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.12 U	< 0.095 U	< 0.16 U	< 0.44 U	< 0.15 U	< 0.15 U	< 0.11 U	< 0.089 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated								
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated								
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated								
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated								
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated								
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated								
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated								
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated								
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated						
Football Field	SSHS-B2362	082918 09:00 SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated						
Football Field	SSHS-B2523	103118 09:00 SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated						
Football Field	SSHS-B2685	051819 10:00 SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.0017 U	< 0.0039 U	< 0.0026 U	< 0.0022 U	< 0.0046 UT	< 0.0049 UT	< 0.0033 U
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated						
Football Field	SSHS-B2943	110719 09:00 SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated						
Football Field	SSHS-B2925	110719 09:00 SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated						
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated						
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated						
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated						
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated						
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated						
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated						
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated						
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated						
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated						
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated						
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated						
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated						
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated						
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated						
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated						
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3576	020421 09:30 DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.11 U	< 0.11 U	< 0.15 U	< 0.1 U	< 0.2 UJ	< 0.18 U	< 0.12 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.078 U	< 0.079 U	< 0.1 U	< 0.075 U	< 0.14 U	< 0.13 U	< 0.086 U
Football Field	SSHS-B3581	020621 10:00 DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.09 U	< 0.092 U	< 0.12 U	< 0.087 U	< 0.17 U	< 0.15 U	< 0.1 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated						
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated						
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated						
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated						
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated						
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated						
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated						
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated						
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated						
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated						

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-4-6	SSHS-B2089-SUB-4-6	7/25/2018	855.40	855.39	-0.01	-	4 - 6 ft	3.99-5.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-4-6	SSHS-B2091-SUB-4-6	7/25/2018	856.61	856.61	0.00	-	4 - 6 ft	4-6 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-4-6	SSHS-B2108-SUB-4-6	7/25/2018	855.64	855.64	0.00	-	4 - 6 ft	4-6 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-4-6	SSHS-B2109-SUB-4-6	7/25/2018	855.25	855.48	0.23	-	4 - 6 ft	4.23-6.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-4-6	SSHS-B2127-SUB-4-6	7/25/2018	855.91	855.91	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-4-6	SSHS-B2128-SUB-4-6	7/25/2018	856.01	856.01	0.00	-	4 - 6 ft	4-6 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-4-6	SSHS-B2129-SUB-4-6	7/25/2018	855.33	855.52	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-4-6	SSHS-B2143-SUB-4-6	7/25/2018	856.56	856.56	0.00	-	4 - 6 ft	4-6 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-4-6	SSHS-B2194-SUB-4-6	7/25/2018	856.19	856.19	0.00	-	4 - 6 ft	4-6 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-4-6	SSHS-B2216-SUB-4-6	7/25/2018	855.16	855.46	0.30	-	4 - 6 ft	4.3-6.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-4-6	SSHS-B2025-SUB-4-6	7/26/2018	854.55	854.52	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 PS-FD-38	PS-FD-38	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-4-6	SSHS-B2026-SUB-4-6	7/26/2018	855.26	855.47	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-4-6	SSHS-B2050-SUB-4-6	7/26/2018	855.45	855.45	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 PS-FD-34	PS-FD-34	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-4-6	SSHS-B2192-SUB-4-6	7/26/2018	855.49	855.50	0.01	-	4 - 6 ft	4.01-6.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-4-6	SSHS-B2195-SUB-4-6	7/26/2018	855.94	855.94	0.00	-	4 - 6 ft	4-6 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-4-6	SSHS-B2213-SUB-4-6	7/26/2018	855.06	855.53	0.47	-	4 - 6 ft	4.47-6.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-4-6	SSHS-B2214-SUB-4-6	7/26/2018	855.14	855.34	0.20	-	4 - 6 ft	4.2-6.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-4-6	SSHS-B2215-SUB-4-6	7/26/2018	855.11	855.30	0.19	-	4 - 6 ft	4.19-6.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-4-6	SSHS-B2224-SUB-4-6	7/26/2018	854.93	855.29	0.36	-	4 - 6 ft	4.36-6.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-4-6	SSHS-B2031-SUB-4-6	7/27/2018	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-4-6	SSHS-B2032-SUB-4-6	7/27/2018	854.88	855.51	0.63	-	4 - 6 ft	4.63-6.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-4-6	SSHS-B2033-SUB-4-6	7/27/2018	854.70	855.74	1.04	-	4 - 6 ft	5.04-7.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 PS-FD-51	PS-FD-51	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-4-6	SSHS-B2217-SUB-4-6	7/27/2018	855.08	855.32	0.24	-	4 - 6 ft	4.24-6.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2362	082918 09:00 SSHS-B2362-SUB-4-6	SSHS-B2362-SUB-4-6	8/28/2018	855.13	855.25	0.12	-	4 - 6 ft	4.12-6.12 ft	180-81347-1	Not Excavated							
Football Field	SSHS-B2523	103118 09:00 SSHS-B2523-SUB-4-6	SSHS-B2523-SUB-4-6	10/29/2018	855.03	855.47	0.44	-	4 - 6 ft	4.44-6.44 ft	180-83541-1	Not Excavated							
Football Field	SSHS-B2685	051819 10:00 SSHS-B2685-SUB-4-6	SSHS-B2685-SUB-4-6	5/17/2019	855.39	855.54	0.15	-	4 - 6 ft	4.15-6.15 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2709	052119 08:40 SSHS-B2709-SUB-4-6	SSHS-B2709-SUB-4-6	5/20/2019	855.26	855.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6-20190521	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 0.0031 U	< 0.0020 U	< 0.0019 U	< 0.0048 U	< 0.0024 U	< 0.0032 U	< 0.0056 U
Football Field	SSHS-IRM3-S058	080319 09:30 SSHS-IRM3-S058-C	SSHS-IRM3-S058-C	8/2/2019	-	856.18	-	851.27	4 - 6 ft	4.91 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S084	080319 09:30 SSHS-IRM3-S084-C	SSHS-IRM3-S084-C	8/2/2019	-	856.10	-	851.08	4 - 6 ft	5.02 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B2943	110719 09:00 SSHS-B2943-SUB-4-6	SSHS-B2943-SUB-4-6	11/4/2019	854.94	855.38	0.44	-	4 - 6 ft	4.44-6.44 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2925	110719 09:00 SSHS-B2925-SUB-4-6	SSHS-B2925-SUB-4-6	11/5/2019	855.34	855.52	0.18	-	4 - 6 ft	4.18-6.18 ft	180-98355-1	Not Excavated							
Football Field	IRM4-S037	SSHS-IRM4-S037-2-4-20200716	SSHS-IRM4-S037-2-4	7/16/2020	-	855.65	-	850.92	4 - 6 ft	4.73 ft	1801083941	Not Excavated							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-4-6	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated	< 0.0026 U	0.003 J	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-4-6	SSHS-B3472-SUB-4-6	7/27/2020	855.50	855.50	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S197N	SSHS-IRM4-DUP27-20200813	SSHS-IRM4-DUP27	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated							
Football Field	IRM4-S181S	SSHS-IRM4-S181S-20200813	SSHS-IRM4-S181S	8/13/2020	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801095841	Not Excavated							
Football Field	IRM4-S193N	SSHS-IRM4-S193N-20200813	SSHS-IRM4-S193N	8/13/2020	-	855.38	-	850.10	4 - 6 ft	5.28 ft	1801095841	Not Excavated							
Football Field	IRM4-S197N	SSHS-IRM4-S197N-20200813	SSHS-IRM4-S197N	8/13/2020	-	855.45	-	850.33	4 - 6 ft	5.12 ft	1801095841	Not Excavated							
Football Field	IRM4-S63-BOT	SSHS-IRM4-S63-BOT-20200820	SSHS-IRM4-S63-BOT	8/20/2020	-	855.45	-	850.76	4 - 6 ft	4.69 ft	1801099081	Not Excavated							
Football Field	SSHS-B3503	090120 10:30 SSHS-B3503-SUB-4-6	SSHS-B3503-SUB-4-6	8/31/2020	856.71	856.71	0.00	-	4 - 6 ft	4-6 ft	180-110264-1	Not Excavated							
Football Field	IRM5-B255A	SSHS-IRM5-B255A-20201214	SSHS-IRM5-B255a	12/14/2020	-	855.68	-	851.59	4 - 6 ft	4.09 ft	1801148711	Not Excavated							
Football Field	IRM5-S291	SSHS-IRM5-S291-20210112	SSHS-IRM5-S291	1/12/2021	-	855.60	-	849.70	4 - 6 ft	5.9 ft	1801158641	Not Excavated							
Football Field	IRM5-S287	SSHS-IRM5-S287-20210112	SSHS-IRM5-S287	1/12/2021	-	855.61	-	849.91	4 - 6 ft	5.7 ft	1801158641	Not Excavated							
Football Field	IRM5-RED 2	SSHS-IRM5-RED 2-20210112	SSHS-IRM5-RED 2	1/12/2021	-	855.72	-	850.42	4 - 6 ft	5.3 ft	1801158641	Not Excavated							
Football Field	IRM5-PR SOIL 1	SSHS-IRM5-PURPLE SOIL 1-20210112	SSHS-IRM5-PURPLE SOIL 1	1/12/2021	-	855.67	-	850.05	4 - 6 ft	5.62 ft	1801158641	Not Excavated							
Football Field	IRM5-B040	SSHS-IRM5-B040-20210115	SSHS-IRM5-B040	1/15/2021	-	855.74	-	851.72	4 - 6 ft	4.02 ft	1801160721	Not Excavated							
Football Field	IRM5-B053	SSHS-IRM5-B053-20210115	SSHS-IRM5-B053	1/15/2021	-	855.75	-	851.52	4 - 6 ft	4.23 ft	1801160721	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-4-6	SSHS-B3575-SUB-4-6	2/2/2021	854.85	855.40	0.55	-	4 - 6 ft	4.55-6.55 ft	180-116724-1	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-4-6	SSHS-B3573-SUB-4-6	2/3/2021	855.66	855.66	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0042 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3576	020421 09:30 DUP-27	DUP-27	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-4-6	SSHS-B3576-SUB-4-6	2/3/2021	855.76	855.76	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.071 U	< 0.11 U	< 0.3 U	< 0.26 U	< 0.13 U	< 0.15 U	< 0.52 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-4-6	SSHS-B3578-SUB-4-6	2/3/2021	855.72	855.72	0.00	-	4 - 6 ft	4-6 ft	180-116773-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-4-6	SSHS-B3572-SUB-4-6	2/4/2021	855.42	855.51	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116864-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-4-6	SSHS-B3580-SUB-4-6	2/5/2021	856.23	856.24	0.01	-	4 - 6 ft	4.01-6.01 ft	180-116914-1	Not Excavated	< 0.051 U	< 0.081 U	< 0.22 U	< 0.19 U	< 0.092 U	< 0.1 U	< 0.37 U
Football Field	SSHS-B3581	020621 10:00 DUP-33	DUP-33	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0011 U	0.0083 J	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-4-6	SSHS-B3581-SUB-4-6	2/5/2021	856.18	856.18	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.0012 U	0.022 J	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-4-6	SSHS-B3582-SUB-4-6	2/5/2021	855.93	855.93	0.00	-	4 - 6 ft	4-6 ft	180-116914-1	Not Excavated	< 0.06 U	< 0.095 U	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-4-6	SSHS-B3583-SUB-4-6	2/5/2021	855.33	855.44	0.11	-	4 - 6 ft	4.11-6.11 ft	180-116914-1	Not Excavated	< 0.0011 U	0.005 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	IRM5-S187	SSHS-IRM5-S187-4-6-20210211	SSHS-IRM5-S187-4-6	2/11/2021	-	855.48	-	850.11	4 - 6 ft	5.37 ft	1801171241	Not Excavated							
Football Field	IRM5-S290G	SSHS-IRM5-DUP-13-20210218	SSHS-IRM5-DUP-13	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated							
Football Field	IRM5-S290G	SSHS-IRM5-S290G-4-6-20210218	SSHS-IRM5-S290G-4-6	2/18/2021	-	855.56	-	849.96	4 - 6 ft	5.6 ft	1801173861	Not Excavated							
Football Field	IRM5-S290A2	SSHS-IRM5-S290A2-20210227	SSHS-IRM5-S290A2	2/27/2021	-	855.75	-	849.99	4 - 6 ft	5.76 ft	1801177071	Not Excavated							
Football Field	IRM5-S290A3	SSHS-IRM5-S290A3-20210227	SSHS-IRM5-S290A3	2/27/2021	-	855.83	-	850.09	4 - 6 ft	5.74 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1S3	SSHS-IRM4A-PIPE1S3-20210301	SSHS-IRM4A-PIPE1S3	3/1/2021	-	855.57	-	851.11	4 - 6 ft	4.46 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1 BOT2	SSHS-IRM4A-PIPE1 BOT2-20210301	SSHS-IRM4A-PIPE1 BOT2	3/1/2021	-	855.57	-	850.88	4 - 6 ft	4.69 ft	1801177071	Not Excavated							
Football Field	IRM4A-PIPE1S4	SSHS-IRM4A-PIPE1S4-20210301	SSHS-IRM4A-PIPE1S4	3/1/2021	-	855.57	-	851.35	4 - 6 ft	4.23 ft	1801177071	Not Excavated							
Football Field	IRM5-PIPE 5 BOT D	SSHS-IRM5-PIPE 5 BOT D-20210311	SSHS-IRM5-PIPE 5 BOT D	3/11/2021	-	855.80	-	849.86	4 - 6 ft	5.94 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 14	SSHS-IRM5-PIPE 14-20210316	SSHS-IRM5-PIPE 14	3/16/2021	-	855.79	-	850.14	4 - 6 ft	5.66 ft	1801185091	Not Excavated							
Football Field	IRM5-PIPE 17	SSHS-IRM5-PIPE 17-20210316	SSHS-IRM5-PIPE 17	3/16/2021	-	855.64	-	850.57	4 - 6 ft	5.07 ft	1801185091	Not Excavated							
Football Field	IRM5-PIPE 26	SSHS-IRM5-PIPE26-20210321	SSHS-IRM5-PIPE26	3/21/2021	-	856.00	-	850.99	4 - 6 ft	5.01 ft	1801188031	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated							
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated							
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated							
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated							
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated							
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated							
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated							
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated							
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated							
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated							
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated							
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated							
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated							
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated							
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated							
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated							
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated							
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated							
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated							
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated							
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated							
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated							
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated							
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated							
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated							
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated							
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated							
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated							
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated							
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated							
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated							
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated							
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated							
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated							
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated							
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated							
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated							
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated							
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated							
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated							
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated							
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated							
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	0.015 J	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated								
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated								
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated								
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	0.01 J	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated						
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated						
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated						
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated						
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated						
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated						
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated						
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated						
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated						
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated						
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated						
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated						
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated						
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated						
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated						
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated						
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated						
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated						
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated						
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated						
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated						
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated						
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated						
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated						
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated						
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated						
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated						
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated						
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated						
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated						
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated						
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated						
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated						
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated						
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated						
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated						
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated						
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated						
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated						
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated						
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated						
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated						
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated						
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated						
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated						
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated						
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated						
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated						
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated						
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated						
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated						
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated						
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 UT
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated							
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated							
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated							
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated							
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated							
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated							
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated							
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated							
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated							
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated							
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated							
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated							
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated							
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated							
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated							
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated							
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated							
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated							
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated							
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated							
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated							
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated							
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated							
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated							
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated							
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated							
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated							
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated							
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated							
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated							
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated							
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated							
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated							
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated							
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated							
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated							
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated							
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated							
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated							
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated							
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated							
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated							
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated							
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated							
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated							
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 UT	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 UT	< 0.0032 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated								
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated								
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated								
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated								
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated								
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated								
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated								
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated								
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated								
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated								
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated								
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated								
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated								
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated								
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated								
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated								
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated								
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated								
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated								
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated								
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated								
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated								
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated								
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated								
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated								
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated								
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated								
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated								
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated								
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated								
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated								
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated								
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated								
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated								
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated								
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated								
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated								
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated								
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated								
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated								
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated								
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated								
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated								
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated								
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated								
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated								
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated								
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated								
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated								
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated								
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated								
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated								
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated								
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated								
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated								
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated								
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated								
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated								
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated								
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated								
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated								
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated								
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated								
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated								
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated								
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated								
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated								
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated								
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated								
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated								
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated								
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated								
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated								
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated								
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated								
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated								
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated								
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated								
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated								
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated								
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated								
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated								
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated								
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated								
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated								
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated								
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated								
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated								
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated								
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated								
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated								
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated								
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated								
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated								
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated								
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated								
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.0020 U	< 0.0016 U	0.0029 J	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated						
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated						
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated						
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated						
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated						
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated						
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated						
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated						
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated						
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated						
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated						
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated						
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated						
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated						
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated						
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated						
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated						
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated						
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated						
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated						
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated						
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated						
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated						
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated						
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated						
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated						
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated						
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated						
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated						
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated						
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated						
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated						
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated						
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated						
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated						
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated						
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated						
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated						
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated						
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated						
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated						
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated						
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated						
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated						
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated						
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated						
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated						
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated						
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated						
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated						
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated						
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated						
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated						
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 UT	< 0.0026 UT	< 0.0017 U
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT	< 0.0018 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-S235	SSHS-IRM5-S235-20210322	SSHS-IRM5-S235	3/22/2021	-	855.94	-	850.02	4 - 6 ft	5.92 ft	1801188032	Not Excavated							
Football Field	IRM5-MT 1 BOT	SSHS-IRM5-MT 1 BOT-20210323	SSHS-IRM5-MT 1 BOT	3/23/2021	-	855.34	-	851.03	4 - 6 ft	4.32 ft	1801188701	Not Excavated							
Football Field	IRM5-B080A-1	SSHS-IRM5-B080A-1-20210325	SSHS-IRM5-B080A-1	3/25/2021	-	855.88	-	850.04	4 - 6 ft	5.84 ft	1801190471	Not Excavated							
Football Field	IRM5-B080A-2	SSHS-IRM5-B080A-2-20210325	SSHS-IRM5-B080A-2	3/25/2021	-	856.01	-	850.91	4 - 6 ft	5.1 ft	1801190471	Not Excavated							
Football Field	IRM5-PIPE 20-B	SSHS-IRM5-PIPE 20 B-20210329	SSHS-IRM5-PIPE 20 B	3/29/2021	-	855.33	-	849.43	4 - 6 ft	5.9 ft	1801191613	Not Excavated							
Football Field	IRM5-B807	SSHS-IRM5-B807-20210408	SSHS-IRM5-B807	4/8/2021	-	855.18	-	850.92	4 - 6 ft	4.26 ft	1801197251	Not Excavated							
Football Field	IRM5-B806	SSHS-IRM5-B806-20210408	SSHS-IRM5-B806	4/8/2021	-	855.33	-	850.58	4 - 6 ft	4.75 ft	1801197251	Not Excavated							
Football Field	IRM5-S813	SSHS-IRM5-S813-20210408	SSHS-IRM5-S813	4/8/2021	-	855.61	-	849.82	4 - 6 ft	5.79 ft	1801197251	Not Excavated							
Football Field	ISMP-S105	SSHS-ISMP-S105-20210408	SSHS-ISMP-S105	4/8/2021	-	855.33	-	850.10	4 - 6 ft	5.23 ft	1801197252	Not Excavated							
Football Field	ISMP-S110	SSHS-ISMP-S110-20210408	SSHS-ISMP-S110	4/8/2021	-	855.36	-	850.23	4 - 6 ft	5.13 ft	1801197252	Not Excavated							
Football Field	ISMP-S130	SSHS-ISMP-S130-20210408	SSHS-ISMP-S130	4/8/2021	-	855.37	-	850.42	4 - 6 ft	4.96 ft	1801197253	Not Excavated							
Football Field	ISMP-B107	SSHS-ISMP-B107-20210409	SSHS-ISMP-B107	4/9/2021	-	855.47	-	850.80	4 - 6 ft	4.67 ft	1801197961	Not Excavated							
Football Field	IRM5-S605	SSHS-IRM5-S605-20210410	SSHS-IRM5-S605	4/10/2021	-	855.38	-	850.14	4 - 6 ft	5.24 ft	1801198461	Not Excavated							
Football Field	IRM5-B604	SSHS-IRM5-B604-20210411	SSHS-IRM5-B604	4/11/2021	-	855.53	-	850.52	4 - 6 ft	5.01 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE40 BOT1	SSHS-IRM5-PIPE 40 BOT 1-20210411	SSHS-IRM5-PIPE 40 BOT 1	4/11/2021	-	855.33	-	850.12	4 - 6 ft	5.2 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S1A	SSHS-IRM5-PIPE 40 S1A-20210411	SSHS-IRM5-PIPE 40 S1A	4/11/2021	-	855.33	-	850.90	4 - 6 ft	4.43 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S1B	SSHS-IRM5-PIPE 40 S1B-20210411	SSHS-IRM5-PIPE 40 S1B	4/11/2021	-	855.32	-	850.92	4 - 6 ft	4.41 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 BOT2	SSHS-IRM5-PIPE 40 BOT 2-20210411	SSHS-IRM5-PIPE 40 BOT 2	4/11/2021	-	855.47	-	850.08	4 - 6 ft	5.39 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S2A	SSHS-IRM5-PIPE 40 S2A-20210411	SSHS-IRM5-PIPE 40 S2A	4/11/2021	-	855.44	-	851.24	4 - 6 ft	4.21 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE40 S2B	SSHS-IRM5-PIPE 40 S2B-20210411	SSHS-IRM5-PIPE 40 S2B	4/11/2021	-	855.49	-	850.50	4 - 6 ft	4.99 ft	1801198482	Not Excavated							
Football Field	IRM5-PIPE39 BOT1	SSHS-IRM5-PIPE 39 BOT 1-20210411	SSHS-IRM5-PIPE 39 BOT 1	4/11/2021	-	855.34	-	850.10	4 - 6 ft	5.24 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE39 S2A	SSHS-IRM5-PIPE 39 S2A-20210411	SSHS-IRM5-PIPE 39 S2A	4/11/2021	-	855.41	-	849.44	4 - 6 ft	5.98 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE39 S2B	SSHS-IRM5-PIPE 39 S2B-20210411	SSHS-IRM5-PIPE 39 S2B	4/11/2021	-	855.47	-	849.91	4 - 6 ft	5.56 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S1A	SSHS-IRM5-PIPE 38 S1A-20210411	SSHS-IRM5-PIPE 38 S1A	4/11/2021	-	855.31	-	850.09	4 - 6 ft	5.22 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S1B	SSHS-IRM5-PIPE 38 S1B-20210411	SSHS-IRM5-PIPE 38 S1B	4/11/2021	-	855.32	-	849.84	4 - 6 ft	5.49 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S2A	SSHS-IRM5-PIPE 38 S2A-20210411	SSHS-IRM5-PIPE 38 S2A	4/11/2021	-	855.52	-	850.07	4 - 6 ft	5.45 ft	1801198481	Not Excavated							
Football Field	IRM5-S163	SSHS-IRM5-DUP 57-20210415	SSHS-IRM5-DUP 57	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200642	Not Excavated							
Football Field	IRM5-S163	SSHS-IRM5-S163-20210415	SSHS-IRM5-S163	4/15/2021	-	854.91	-	850.50	4 - 6 ft	4.41 ft	1801200641	Not Excavated							
Football Field	IRM5-S161	SSHS-IRM5-S161-20210415	SSHS-IRM5-S161	4/15/2021	-	855.64	-	849.89	4 - 6 ft	5.75 ft	1801200641	Not Excavated							
Football Field	IRM5-B609	SSHS-IRM5-B609-20210415	SSHS-IRM5-B609	4/15/2021	-	855.71	-	851.02	4 - 6 ft	4.69 ft	1801200642	Not Excavated							
Football Field	IRM5-S072	SSHS-IRM5-S072-20210415	SSHS-IRM5-S072	4/15/2021	-	855.71	-	851.50	4 - 6 ft	4.2 ft	1801200641	Not Excavated							
Football Field	IRM5-S085	SSHS-IRM5-S085-20210415	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated							
Football Field	IRM5-S090	SSHS-IRM5-S090-20210415	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated							
Football Field	IRM5-S089	SSHS-IRM5-S089-20210415	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated							
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-DUP 69-20210421	SSHS-IRM5-DUP 69	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated							
Football Field	IRM5-SEGMENT 7 S1	SSHS-IRM5-SEG 7 S1-20210421	SSHS-IRM5-SEG 7 S1	4/21/2021	-	853.47	-	849.05	4 - 6 ft	4.43 ft	1801203601	Not Excavated							
Football Field	IRM5-B157	SSHS-IRM5-B157-20210422	SSHS-IRM5-B157	4/22/2021	-	855.09	-	850.01	4 - 6 ft	5.08 ft	1801204561	Not Excavated							
Football Field	IRM5-B158	SSHS-IRM5-B158-20210422	SSHS-IRM5-B158	4/22/2021	-	855.11	-	850.34	4 - 6 ft	4.77 ft	1801204561	Not Excavated							
Football Field	IRM5-B159	SSHS-IRM5-B159-20210422	SSHS-IRM5-B159	4/22/2021	-	855.13	-	850.53	4 - 6 ft	4.6 ft	1801204561	Not Excavated							
Football Field	IRM5-S201	SSHS-IRM5-S201-20210422	SSHS-IRM5-S201	4/22/2021	-	855.44	-	849.45	4 - 6 ft	5.99 ft	1801204562	Not Excavated							
Football Field	IRM5-B148 BOT	SSHS-IRM5-B148 BOT-20210423	SSHS-IRM5-B148 BOT	4/23/2021	-	855.11	-	850.95	4 - 6 ft	4.16 ft	1801205492	Not Excavated							
Football Field	IRM5-P18 4S	SSHS-IRM5-P18-4S-20210426	SSHS-IRM5-P18-4S	4/26/2021	-	855.97	-	850.21	4 - 6 ft	5.76 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 11N	SSHS-IRM5-CB28 11N-20210426	SSHS-IRM5-CB28 11N	4/26/2021	-	855.89	-	850.05	4 - 6 ft	5.85 ft	1801206041	Not Excavated							
Football Field	IRM5-P18-3E	SSHS-IRM5-P18-3E-20210426	SSHS-IRM5-P18-3E	4/26/2021	-	855.75	-	850.42	4 - 6 ft	5.33 ft	1801206041	Not Excavated							
Football Field	IRM5-S234A2	SSHS-IRM5-S234A2-20210430	SSHS-IRM5-S234A2	4/30/2021	-	855.82	-	850.72	4 - 6 ft	5.1 ft	1801209532	Not Excavated							
Football Field	IRM5-B106 BOT 2	SSHS-IRM5-B106 BOT 2-20210501	SSHS-IRM5-B106 BOT 2	5/1/2021	-	855.45	-	851.38	4 - 6 ft	4.07 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 S3	SSHS-IRM5-PIPE 47 S3-20210504	SSHS-IRM5-PIPE 47 S3	5/4/2021	-	855.47	-	851.35	4 - 6 ft	4.12 ft	1801211061	Not Excavated							
Football Field	IRM5-S234A S7	SSHS-IRM5-S234A S7-20210507	SSHS-IRM5-S234A S7	5/7/2021	-	855.68	-	850.80	4 - 6 ft	4.88 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S4	SSHS-IRM5-S234A S4-20210507	SSHS-IRM5-S234A S4	5/7/2021	-	855.81	-	851.27	4 - 6 ft	4.54 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S8	SSHS-IRM5-S643 S8-20210509	SSHS-IRM5-S643 S8	5/9/2021	-	855.64	-	849.98	4 - 6 ft	5.66 ft	1801213911	Not Excavated							
Football Field	IRM5-S643 S14	SSHS-IRM5-S643 S14-20210509	SSHS-IRM5-S643 S14	5/9/2021	-	855.69	-	850.44	4 - 6 ft	5.25 ft	1801213911	Not Excavated							
Football Field	IRM5-P50 S1	SSHS-IRM5-P50 S1-20210509	SSHS-IRM5-P50 S1	5/9/2021	-	855.77	-	850.09	4 - 6 ft	5.68 ft	1801213911	Not Excavated							
Football Field	IRM5-PIPE 51 S13	SSHS-IRM5-PIPE 51 S13-20210519	SSHS-IRM5-PIPE 51 S13	5/19/2021	-	855.14	-	849.94	4 - 6 ft	5.2 ft	1801218701	Not Excavated							
Football Field	ISMP-S500	SSHS-ISMP-DUP 4-20210521	SSHS-ISMP-DUP 4	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated							
Football Field	ISMP-B526	SSHS-ISMP-B526-20210521	SSHS-ISMP-B526	5/21/2021	-	855.86	-	850.38	4 - 6 ft	5.48 ft	1801220721	Not Excavated							
Football Field	ISMP-S500	SSHS-ISMP-S500-20210521	SSHS-ISMP-S500	5/21/2021	-	855.72	-	850.94	4 - 6 ft	4.78 ft	1801220721	Not Excavated							
Football Field	ISMP-B525	SSHS-ISMP-B525-20210521	SSHS-ISMP-B525	5/21/2021	-	856.02	-	850.69	4 - 6 ft	5.33 ft	1801220721	Not Excavated							
Football Field	ISMP-S503	SSHS-ISMP-S503-20210522	SSHS-ISMP-S503	5/22/2021	-	855.79	-	851.49	4 - 6 ft	4.3 ft	1801221081	Not Excavated							
Football Field	ISMP-B536	SSHS-ISMP-DUP 8-20210527	SSHS-ISMP-DUP 8	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1-20210527	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-S507	SSHS-ISMP-S507-20210527	SSHS-ISMP-S507	5/27/2021	-	855.44	-	850.52	4 - 6 ft	4.92 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1-20210527	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B533	SSHS-ISMP-B533-20210527	SSHS-ISMP-B533	5/27/2021	-	855.57	-	850.23	4 - 6 ft	5.34 ft	1801223381	Not Excavated							
Football Field	ISMP-B532	SSHS-ISMP-B532-20210527	SSHS-ISMP-B532	5/27/2021	-	855.63	-	850.36	4 - 6 ft	5.27 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1-20210527	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-B535	SSHS-ISMP-B535-20210527	SSHS-ISMP-B535	5/27/2021	-	855.74	-	851.15	4 - 6 ft	4.6 ft	1801223381	Not Excavated							
Football Field	ISMP-S515	SSHS-ISMP-S515-20210527	SSHS-ISMP-S515	5/27/2021	-	855.64	-	851.22	4 - 6 ft	4.42 ft	1801223381	Not Excavated							
Football Field	ISMP-B536	SSHS-ISMP-B536-20210527	SSHS-ISMP-B536	5/27/2021	-	855.74	-	851.06	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	ISMP-B537	SSHS-ISMP-B537-20210527	SSHS-ISMP-B537	5/27/2021	-	855.98	-	851.30	4 - 6 ft	4.68 ft	1801223381	Not Excavated							
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8-20210602	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1-20210602	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2-20210602	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	0.0041 J	0.0051	0.0092 J
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3-20210602	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15-20210602	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 0.0011 U	0.0027 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0075 U	< 0.0027 U	< 0.0057 U	< 0.0045 U	< 0.0048 U	< 0.0044 U	< 0.0077 U	< 0.0039 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated								
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated								
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated								
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated								
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated								
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated								
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated								
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated								
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated								
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated								
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.0086 U	< 0.00029 U	< 0.00051 U	< 0.00061 U	< 0.00098 U	< 0.0017 U	< 0.00048 U	< 0.0013 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.01 U	< 0.00034 U	< 0.00061 U	< 0.00073 U	< 0.0012 U	< 0.0020 U	< 0.00057 U	< 0.0016 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 UT	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 UT	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 UT	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0067 U	< 0.0024 U	< 0.0051 U	< 0.0040 U	< 0.0043 U	< 0.0039 U	< 0.0068 U	< 0.0035 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.03 U	< 0.011 U	< 0.023 U	< 0.018 U	< 0.02 U	< 0.018 U	< 0.031 U	< 0.016 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0075 U	< 0.0027 U	< 0.0057 U	< 0.0045 U	< 0.0048 U	< 0.0044 U	< 0.0076 U	< 0.0039 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0076 U	< 0.0028 U	< 0.0059 U	< 0.0046 U	< 0.0049 U	< 0.0045 U	< 0.0078 U	< 0.0040 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0060 U	< 0.0022 U	< 0.0046 U	< 0.0036 U	< 0.0039 U	< 0.0035 U	< 0.0062 U	< 0.0031 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated								
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0025 U	< 0.0048 U	< 0.0056 U	< 0.0031 U	< 0.0038 U	< 0.0046 U	< 0.0062 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated							
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated							
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated							
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated							
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated							
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated							
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated							
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated							
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated							
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated							
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated							
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.00038 U	< 0.0011 U	< 0.0011 U	< 0.00032 U	< 0.00093 U	< 0.00056 U	< 0.0015 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.00045 U	< 0.0014 U	< 0.0013 U	< 0.00039 U	< 0.0011 U	< 0.00067 U	< 0.0018 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated							
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0042 U	< 0.0050 U	< 0.0027 U	< 0.0034 U	< 0.0041 U	< 0.0055 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.01 U	< 0.019 U	< 0.023 U	< 0.013 U	< 0.015 U	< 0.019 U	< 0.025 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0047 U	< 0.0056 U	< 0.0031 U	< 0.0038 U	< 0.0046 U	< 0.0062 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0049 U	< 0.0057 U	< 0.0032 U	< 0.0039 U	< 0.0047 U	< 0.0063 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0020 U	< 0.0038 U	< 0.0045 U	< 0.0025 U	< 0.0031 U	< 0.0037 U	< 0.0050 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0025 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0028 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0028 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0028 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0025 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0028 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated							
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated							
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0086 U	< 0.0026 U	< 0.0048 U	< 0.0032 U	< 0.0059 U	< 0.0029 U	< 0.0031 U	< 0.0028 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated								
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated								
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated								
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated								
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated								
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated								
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated								
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated								
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated								
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated								
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.0049 U	< 0.00032 U	< 0.00039 U	< 0.00046 U	< 0.00033 U	< 0.00036 U	< 0.00028 U	< 0.00032 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.0059 U	< 0.00038 U	< 0.00046 U	< 0.00054 U	< 0.00040 U	< 0.00043 U	< 0.00034 U	< 0.00038 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0077 U	< 0.0023 U	< 0.0042 U	< 0.0029 U	< 0.0053 U	< 0.0026 U	< 0.0027 U	< 0.0025 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.035 U	< 0.011 U	< 0.019 U	< 0.013 U	< 0.024 U	< 0.012 U	< 0.012 U	< 0.011 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0086 U	< 0.0026 U	< 0.0048 U	< 0.0032 U	< 0.0059 U	< 0.0029 U	< 0.0031 U	< 0.0028 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0088 U	< 0.0027 U	< 0.0049 U	< 0.0033 U	< 0.0060 U	< 0.0029 U	< 0.0031 U	< 0.0028 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0070 U	< 0.0021 U	< 0.0039 U	< 0.0026 U	< 0.0048 U	< 0.0023 U	< 0.0025 U	< 0.0022 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.0039 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0039 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated								
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0043 U	< 0.0078 U	< 0.0029 U	< 0.0034 U	< 0.0025 U	< 0.0042 U	< 0.0043 U	< 0.0035 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated								
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated								
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated								
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated								
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated								
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated								
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated								
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated								
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated								
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated								
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.00075 U	< 0.00046 U	< 0.00061 U	< 0.00058 U	< 0.00035 U	< 0.0012 U	< 0.0015 U	< 0.00043 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.00089 U	< 0.00055 U	< 0.00072 U	< 0.00069 U	< 0.00042 U	< 0.0014 U	< 0.0018 U	< 0.00051 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0039 U	< 0.0070 U	< 0.0026 U	< 0.0030 U	< 0.0023 U	< 0.0038 U	< 0.0038 U	< 0.0032 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.018 U	< 0.032 U	< 0.012 U	< 0.014 U	< 0.01 U	< 0.017 U	< 0.018 U	< 0.014 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0043 U	< 0.0078 U	< 0.0029 U	< 0.0033 U	< 0.0025 U	< 0.0042 U	< 0.0043 U	< 0.0035 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0044 U	< 0.0080 U	< 0.0030 U	< 0.0034 U	< 0.0026 U	< 0.0043 U	< 0.0044 U	< 0.0036 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0035 U	< 0.0063 U	< 0.0023 U	< 0.0027 U	< 0.0021 U	< 0.0034 U	< 0.0035 U	< 0.0029 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0035 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0035 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated								
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0038 U	< 0.0030 U	< 0.0050 U	< 0.014 U	< 0.0046 U	< 0.0049 U	< 0.0035 U	< 0.0028 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated								
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated								
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated								
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated								
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated								
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated								
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated								
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated								
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated								
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated								
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated								
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated								
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.00053 U	< 0.0017 U	< 0.00079 U	< 0.0014 U	< 0.00050 U	< 0.0015 U	< 0.0015 U	< 0.00081 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.00063 U	< 0.0020 U	< 0.00094 U	< 0.0017 U	< 0.00060 U	< 0.0017 U	< 0.0018 U	< 0.00097 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated								
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0027 U	< 0.0044 U	< 0.013 U	< 0.0041 U	< 0.0043 U	< 0.0031 U	< 0.0025 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.016 U	< 0.012 U	< 0.02 U	< 0.057 U	< 0.019 U	< 0.02 U	< 0.014 U	< 0.011 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0038 U	< 0.0030 U	< 0.0050 U	< 0.014 U	< 0.0046 U	< 0.0049 U	< 0.0035 U	< 0.0028 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0039 U	< 0.0031 U	< 0.0051 U	< 0.014 U	< 0.0047 U	< 0.0050 U	< 0.0036 U	< 0.0029 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0031 U	< 0.0024 U	< 0.0040 U	< 0.011 U	< 0.0037 U	< 0.0039 U	< 0.0028 U	< 0.0023 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.0017 U	< 0.0014 U	< 0.0023 U	< 0.0064 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0017 U	< 0.0014 U	< 0.0023 U	< 0.0064 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated								
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0029 U	< 0.0029 U	< 0.0039 U	< 0.0028 U	< 0.0053 U	< 0.0049 U	< 0.0032 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated							
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated							
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated							
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated							
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated							
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated							
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated							
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated							
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated							
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated							
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated							
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.00047 U	< 0.00059 U	< 0.00030 U	< 0.00032 U	< 0.0012 U	< 0.0010 U	< 0.00073 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.00057 U	< 0.00070 U	< 0.00036 U	< 0.00038 U	< 0.0014 U	< 0.0012 U	< 0.00087 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated							
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0026 U	< 0.0026 U	< 0.0034 U	< 0.0025 U	< 0.0047 U	< 0.0043 U	< 0.0028 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.012 U	< 0.012 U	< 0.016 U	< 0.011 U	< 0.021 U	< 0.02 U	< 0.013 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0029 U	< 0.0029 U	< 0.0038 U	< 0.0028 U	< 0.0053 U	< 0.0049 U	< 0.0032 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0029 U	< 0.0030 U	< 0.0039 U	< 0.0028 U	< 0.0054 U	< 0.0050 U	< 0.0033 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0024 U	< 0.0031 U	< 0.0022 U	< 0.0043 U	< 0.0039 U	< 0.0026 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 UT	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0017 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 UT	< 0.0022 U	< 0.0015 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0017 U	< 0.0013 U	< 0.0024 UT	< 0.0022 UT	< 0.0015 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated							
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated							
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated							

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23-20210603	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 0.0019 U	0.055	< 0.0080 U	< 0.0069 U	< 0.0034 U	< 0.0039 U	< 0.014 U
Football Field	IRM5-PIPE 52 S1	SSHS-IRM5-PIPE 52 S1-20210605	SSHS-IRM5-PIPE 52 S1	6/5/2021	-	856.15	-	851.18	4 - 6 ft	4.97 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 S2	SSHS-IRM5-PIPE 52 S2-20210605	SSHS-IRM5-PIPE 52 S2	6/5/2021	-	856.13	-	850.50	4 - 6 ft	5.63 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 S4	SSHS-IRM5-PIPE 52 S4-20210605	SSHS-IRM5-PIPE 52 S4	6/5/2021	-	856.06	-	850.48	4 - 6 ft	5.58 ft	1801228131	Not Excavated							
Football Field	ISMP-B541	SSHS-ISMP-B541-20210609	SSHS-ISMP-B541	6/9/2021	-	855.63	-	850.25	4 - 6 ft	5.38 ft	1801229771	Not Excavated							
Football Field	ISMP-B542	SSHS-ISMP-B542-20210609	SSHS-ISMP-B542	6/9/2021	-	855.83	-	851.08	4 - 6 ft	4.75 ft	1801229771	Not Excavated							
Football Field	ISMP-B543	SSHS-ISMP-B543-20210609	SSHS-ISMP-B543	6/9/2021	-	855.89	-	850.44	4 - 6 ft	5.46 ft	1801229771	Not Excavated							
Football Field	ISMP-B544	SSHS-ISMP-B544-20210609	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 0.0011 U	0.017	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-S524	SSHS-ISMP-S524-20210609	SSHS-ISMP-S524	6/9/2021	-	855.52	-	850.04	4 - 6 ft	5.49 ft	1801229791	Not Excavated							
Football Field	ISMP-B546	SSHS-ISMP-B546-20210610	SSHS-ISMP-B546	6/10/2021	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801230401	Not Excavated							
Football Field	ISMP-S527	SSHS-ISMP-S527-20210610	SSHS-ISMP-S527	6/10/2021	-	855.61	-	851.47	4 - 6 ft	4.14 ft	1801230401	Not Excavated							
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76-20210611	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-FIS-S2	SSHS-IRM5-FIS S2-20210614	SSHS-IRM5-FIS S2	6/14/2021	-	854.28	-	850.04	4 - 6 ft	4.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S8	SSHS-IRM5-FIS S8-20210614	SSHS-IRM5-FIS S8	6/14/2021	-	854.57	-	850.14	4 - 6 ft	4.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S14	SSHS-IRM5-FIS S14-20210614	SSHS-IRM5-FIS S14	6/14/2021	-	855.24	-	850.51	4 - 6 ft	4.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A S17	SSHS-IRM5-P18 S5A S17-20210615	SSHS-IRM5-P18 S5A S17	6/15/2021	-	855.92	-	851.65	4 - 6 ft	4.27 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S19	SSHS-IRM5-P18 S5A S19-20210615	SSHS-IRM5-P18 S5A S19	6/15/2021	-	855.92	-	850.40	4 - 6 ft	5.53 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S20	SSHS-IRM5-P18 S5A S20-20210615	SSHS-IRM5-P18 S5A S20	6/15/2021	-	855.89	-	850.54	4 - 6 ft	5.35 ft	1801232172	Not Excavated							
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210617	SSHS-ISMP-B527 BOT 25	6/17/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801233581	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210617	SSHS-ISMP-B527 S77	6/17/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801233581	Not Excavated							
Football Field	IRM5-FIS-S191	SSHS-IRM5-FIS S191-20210617	SSHS-IRM5-FIS S191	6/17/2021	-	854.50	-	850.03	4 - 6 ft	4.47	1801233543	Not Excavated							
Football Field	IRM5-FIS-S194	SSHS-IRM5-FIS S194-20210617	SSHS-IRM5-FIS S194	6/17/2021	-	854.47	-	849.36	4 - 6 ft	5.1 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S196	SSHS-IRM5-FIS S196-20210617	SSHS-IRM5-FIS S196	6/17/2021	-	854.52	-	849.94	4 - 6 ft	4.58 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S120	SSHS-IRM5-FIS S120-20210617	SSHS-IRM5-FIS S120	6/17/2021	-	854.70	-	850.67	4 - 6 ft	4.04 ft	1801233543	Not Excavated							
Football Field	IRM5-PIPE 53 S1	SSHS-ISMP-PIPE 53 S1-20210618	SSHS-ISMP-PIPE 53 S1	6/18/2021	-	855.63	-	851.24	4 - 6 ft	4.4 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 BOT 1	SSHS-ISMP-PIPE 53 BOT 1-20210618	SSHS-ISMP-PIPE 53 BOT 1	6/18/2021	-	855.59	-	849.75	4 - 6 ft	5.84 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S2	SSHS-ISMP-PIPE 53 S2-20210618	SSHS-ISMP-PIPE 53 S2	6/18/2021	-	855.58	-	851.19	4 - 6 ft	4.39 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S4	SSHS-ISMP-PIPE 53 S4-20210618	SSHS-ISMP-PIPE 53 S4	6/18/2021	-	855.55	-	850.69	4 - 6 ft	4.86 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 S3	SSHS-ISMP-PIPE 53 S3-20210618	SSHS-ISMP-PIPE 53 S3	6/18/2021	-	855.52	-	850.79	4 - 6 ft	4.73 ft	1801234401	Not Excavated							
Football Field	IRM5-PIPE 53 BOT 2	SSHS-ISMP-PIPE 53 BOT 2-20210618	SSHS-ISMP-PIPE 53 BOT 2	6/18/2021	-	855.55	-	849.84	4 - 6 ft	5.72 ft	1801234401	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210618	SSHS-ISMP-B527 S77	6/18/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801234402	Not Excavated	< 0.00046 U	< 0.00026 U	< 0.0011 U	< 0.00073 U	< 0.00032 U	< 0.00035 U	< 0.00065 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210618	SSHS-ISMP-B527 BOT 25	6/18/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801234402	Not Excavated	< 0.00055 U	< 0.00031 U	< 0.0013 U	< 0.00087 U	< 0.00038 U	< 0.00042 U	< 0.00078 U
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25-20210623	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77-20210623	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated							
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101-20210625	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 0.0010 U	0.023	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99-20210625	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102-20210625	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Football Field	IRM5-FIS-S221	SSHS-IRM5-DUP 135-20210628	SSHS-IRM5-DUP 135	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated							
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103-20210628	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 0.0010 U	0.019	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105-20210628	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 0.0010 U	0.018	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109-20210628	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	IRM5-FIS BOT 34	SSHS-IRM5-FIS BOT 34-20210628	SSHS-IRM5-FIS BOT 34	6/28/2021	-	854.49	-	850.39	4 - 6 ft	4.1 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S220	SSHS-IRM5-FIS S220-20210628	SSHS-IRM5-FIS S220	6/28/2021	-	854.66	-	850.58	4 - 6 ft	4.08 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 35	SSHS-IRM5-FIS BOT 35-20210628	SSHS-IRM5-FIS BOT 35	6/28/2021	-	854.98	-	850.28	4 - 6 ft	4.71 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S221	SSHS-IRM5-FIS S221-20210628	SSHS-IRM5-FIS S221	6/28/2021	-	855.12	-	850.81	4 - 6 ft	4.32 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 36	SSHS-IRM5-FIS BOT 36-20210628	SSHS-IRM5-FIS BOT 36	6/28/2021	-	855.28	-	850.54	4 - 6 ft	4.74 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS BOT 38	SSHS-IRM5-FIS BOT 38-20210628	SSHS-IRM5-FIS BOT 38	6/28/2021	-	855.17	-	851.00	4 - 6 ft	4.17 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S302	SSHS-IRM5-FIS S302-20210821	SSHS-IRM5-FIS S302	8/21/2021	-	855.12	-	849.46	4 - 6 ft	5.66 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S311	SSHS-IRM5-FIS S311-20210821	SSHS-IRM5-FIS S311	8/21/2021	-	855.10	-	849.16	4 - 6 ft	5.94 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2-20210828	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7-20210828	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16-20210829	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28-20210829	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12-20210829	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12V-20210830	SSHS-ISMP-CB-7 S12V	8/30/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0071 U	< 0.0061 U	< 0.0030 U	< 0.0034 U	< 0.012 U
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16V-20210830	SSHS-ISMP-CB-7 S16V	8/30/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264191	Not Excavated	< 0.0077 U	< 0.012 U	< 0.032 U	< 0.028 U	< 0.014 U	< 0.016 U	< 0.056 U
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7V-20210830	SSHS-ISMP-CB-7 S7V	8/30/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801264191	Not Excavated	< 0.0019 U	< 0.0030 U	< 0.0079 U	< 0.0069 U	< 0.0034 U	< 0.0038 U	< 0.014 U
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28V-20210830	SSHS-ISMP-CB-7 S28V	8/30/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264191	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0081 U	< 0.0071 U	< 0.0035 U	< 0.0039 U	< 0.014 U
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2V-20210830	SSHS-ISMP-CB-7 S2V	8/30/2021	-	855.92	-	850.55	4 - 6 ft	5.37 ft	1801264191	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0064 U	< 0.0056 U	< 0.0028 U	< 0.0031 U	< 0.011 U
Football Field	SSHS-B4164	092421 10:00 DUP-20	DUP-20	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-4-6	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-4-6	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	ISMP-S605	SSHS-ISMP-DUPA-20211007	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-B606	SSHS-ISMP-B606-20211007	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Football Field	ISMP-B607	SSHS-ISMP-B607-20211007	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	ISMP-B608	SSHS-ISMP-B608-20211007	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 0.00086 U	< 0.0014 U	< 0.0036 U	< 0.0031 U	< 0.0015 U	< 0.0017 U	< 0.0063 U
Football Field	ISMP-S602	SSHS-ISMP-S602-20211007	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Football Field	ISMP-S605	SSHS-ISMP-S605-20211007	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Football Field	ISMP-S606	SSHS-ISMP-S606-20211007	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 0.00087 U	< 0.0014 U	< 0.0036 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0063 U
Football Field	ISMP-S609	SSHS-ISMP-S609-20211007	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 0.00087 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Football Field	ISMP-S611	SSHS-ISMP-S611-20211007	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 0.00086 U	< 0.0014 U	< 0.0036 U	< 0.0031 U	< 0.0015 U	< 0.0017 U	< 0.0063 U
Football Field	IRM5-FIS-S358	SSHS-IRM5-FIS-S358-20211009	SSHS-IRM5-FIS-S358	10/9/2021	-	855.21	-	850.19	4 - 6 ft	5.03 ft	1801283151	Not Excavated							
Football Field	IRM5-FIS-S367	SSHS-IRM5-FIS-S367-20211013	SSHS-IRM5-FIS-S367	10/13/2021	-	855.40	-	849.96	4 - 6 ft	5.44 ft	1801284441	Not Excavated							
Football Field	IRM5-FIS-S368	SSHS-IRM5-FIS-S368-20211013	SSHS-IRM5-FIS-S368	10/13/2021	-	855.43	-	851.09	4 - 6 ft	4.34 ft	1801284441	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	0.0062 J	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	0.015 J	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	0.013 J	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	0.0086 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.0032 U	< 0.0012 U	< 0.0025 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0033 U	< 0.0017 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 UT	< 0.00033 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.0099 U	< 0.00045 U	< 0.00049 U	< 0.00044 U	< 0.00073 U	< 0.0017 U	< 0.00046 UT	< 0.00067 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 UT	< 0.00034 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.0065 UT	< 0.00029 UT	< 0.00032 UT	< 0.00029 UT	< 0.00049 UT	< 0.0011 UT	< 0.00030 UT	< 0.00044 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.0092 U	< 0.00041 U	< 0.00045 U	< 0.00041 U	< 0.00068 U	< 0.0016 U	< 0.00043 UT	< 0.00062 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0013 U	< 0.00033 UT	< 0.00048 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.0081 U	< 0.00036 U	< 0.00040 U	< 0.00036 U	< 0.00060 U	< 0.0014 U	< 0.00038 UT	< 0.00055 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	0.00038 J	< 0.00046 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated								
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated								
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.0093 U	< 0.00042 U	< 0.00046 U	< 0.00042 U	< 0.00069 U	< 0.0016 U	< 0.00043 U	< 0.00063 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated								
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated								
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated								
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	0.0087	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	0.0090	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	< 0.00021 U	< 0.00031 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.0067 UT	< 0.00030 UT	< 0.00033 UT	< 0.00030 UT	< 0.00050 UT	< 0.0012 UT	< 0.00031 UT	< 0.00045 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.0084 U	< 0.00038 U	< 0.00041 U	< 0.00038 U	< 0.00063 U	< 0.0015 U	< 0.00039 UT	< 0.00057 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	0.048	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	0.0081	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	0.0099	< 0.00042 U	< 0.00046 U	< 0.00042 U	< 0.00070 U	< 0.0016 U	< 0.00044 UT	< 0.00064 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00033 UT	< 0.00047 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	0.00026 J	< 0.00031 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 UT	< 0.00023 U	< 0.00033 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	0.0064	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 UT	< 0.00025 U	< 0.00036 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	< 0.00021 U	< 0.00031 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0045 U	< 0.0023 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 UT	< 0.0042 U	< 0.0022 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 UT	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	0.014 J	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 UT	< 0.0040 U	< 0.0020 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	0.019 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 UT	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	0.024	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 UT	< 0.0047 U	< 0.0024 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	0.025	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.0037 UT	< 0.0014 UT	< 0.0029 UT	< 0.0022 UT	< 0.0024 U	< 0.0022 UT	< 0.0038 UT	< 0.0020 UT
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U

DRAFT

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0029 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.0011 U	< 0.0020 U	< 0.0024 U	< 0.0013 U	< 0.0016 U	< 0.0020 U	< 0.0026 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00031 U	< 0.00034 U	< 0.00090 U	< 0.0017 U	< 0.00075 U	< 0.00038 U	< 0.00080 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.00020 UT	< 0.00022 UT	< 0.00060 UT	< 0.0011 UT	< 0.00050 UT	< 0.00025 UT	< 0.00053 U
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.00028 U	< 0.00031 U	< 0.00084 U	< 0.0016 U	< 0.00070 U	< 0.00035 U	< 0.00074 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00058 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00074 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00065 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 UT
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated							
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated							
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.00029 U	< 0.00031 U	< 0.00085 U	< 0.0016 U	< 0.00071 U	< 0.00036 U	< 0.00075 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated							
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated							
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated							
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00035 U	< 0.00018 U	< 0.00036 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.00021 UT	< 0.00023 UT	< 0.00061 UT	< 0.0011 UT	< 0.00051 UT	< 0.00026 UT	< 0.00054 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00077 U	< 0.0014 U	< 0.00064 U	< 0.00033 U	< 0.00068 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.00029 U	< 0.00032 U	< 0.00086 U	< 0.0016 U	< 0.00072 U	< 0.00036 U	< 0.00076 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00034 U	< 0.00018 U	< 0.00036 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0037 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0016 U	< 0.0020 UT	< 0.0024 U	< 0.0033 UT
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0017 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 UT	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0023 UT	< 0.0027 U	< 0.0037 UT
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 UT	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 UT	< 0.0015 UT	< 0.0019 UT	< 0.0023 UT	< 0.0031 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 UT	< 0.0016 U	< 0.0019 U	< 0.0024 U	< 0.0032 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0038 U	< 0.0018 U	< 0.0019 U	< 0.0018 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0028 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.0037 U	< 0.0011 U	< 0.0020 U	< 0.0014 U	< 0.0025 U	< 0.0012 U	< 0.0013 U	< 0.0012 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.0020 U	< 0.00031 U	< 0.00058 U	< 0.00062 U	< 0.00063 U	< 0.00039 U	< 0.00036 U	< 0.00051 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.0013 UT	< 0.00021 UT	< 0.00039 UT	< 0.00041 UT	< 0.00042 UT	< 0.00026 UT	< 0.00024 UT	< 0.00034 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.0018 U	< 0.00029 U	< 0.00054 U	< 0.00058 U	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00047 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00048 U	< 0.00051 U	< 0.00051 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.0017 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 UT	< 0.00043 UT	< 0.00027 UT	< 0.00024 U	< 0.00035 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated								
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated								
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.0019 U	< 0.00029 U	< 0.00055 U	< 0.00059 U	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00048 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated								
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated								
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated								
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.0013 UT	< 0.00021 UT	< 0.00039 UT	< 0.00042 UT	< 0.00043 UT	< 0.00026 UT	< 0.00024 UT	< 0.00034 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.0017 U	< 0.00027 U	< 0.00050 U	< 0.00053 U	< 0.00054 U	< 0.00033 U	< 0.00030 U	< 0.00044 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.0019 U	< 0.00030 U	< 0.00056 U	< 0.00059 U	< 0.00060 U	< 0.00037 U	< 0.00034 U	< 0.00049 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00037 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 UT	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 UT	< 0.0035 UT	< 0.0017 UT	< 0.0018 U	< 0.0016 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.0043 UT	< 0.0013 U	< 0.0024 UT	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 UT	< 0.0014 UT
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.0020 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.0019 U	< 0.0033 U	< 0.0012 U	< 0.0014 U	< 0.0011 U	< 0.0018 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 UT	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00039 U	< 0.00066 U	< 0.00062 U	< 0.00043 UT	< 0.00073 U	< 0.00047 U	< 0.00046 U	< 0.00034 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 UT	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.00026 UT	< 0.00044 UT	< 0.00041 UT	< 0.00028 UT	< 0.00048 UT	< 0.00031 UT	< 0.00030 UT	< 0.00023 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.00036 U	< 0.00061 U	< 0.00057 U	< 0.00039 U	< 0.00068 U	< 0.00044 U	< 0.00043 U	< 0.00032 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00051 U	< 0.00035 UT	< 0.00060 U	< 0.00039 U	< 0.00038 U	< 0.00028 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated								
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated								
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.00036 U	< 0.00062 U	< 0.00058 U	< 0.00040 U	< 0.00069 U	< 0.00044 U	< 0.00043 U	< 0.00032 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated								
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated								
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated								
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.00026 UT	< 0.00044 UT	< 0.00042 UT	< 0.00029 UT	< 0.00049 UT	< 0.00032 UT	< 0.00031 UT	< 0.00023 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00053 U	< 0.00036 U	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.00040 U	< 0.00070 U	< 0.00045 U	< 0.00044 U	< 0.00033 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00033 U	< 0.00024 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	< 0.00019 U	0.00038 J	0.00038 J	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.0022 UT	< 0.0039 UT	< 0.0015 UT	< 0.0017 UT	< 0.0013 UT	< 0.0021 UT	< 0.0022 U	< 0.0018 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	0.028	< 0.0019 U	< 0.0015 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	0.028	< 0.0021 U	< 0.0017 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	0.013	< 0.0019 U	< 0.0015 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0066 U	< 0.0022 U	< 0.0023 U	< 0.0016 U	< 0.0013 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0060 U	< 0.0020 U	< 0.0021 U	< 0.0015 U	< 0.0012 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00052 U	< 0.0030 U	< 0.00049 U	< 0.0074 U	< 0.00086 U	< 0.00064 U	< 0.0027 U	< 0.00088 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.00034 UT	< 0.0020 UT	< 0.00033 UT	< 0.0049 UT	< 0.00057 UT	< 0.00042 UT	< 0.0018 UT	< 0.00058 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.00048 U	< 0.0027 U	< 0.00046 U	< 0.0069 U	< 0.00080 U	< 0.00059 U	< 0.0025 U	< 0.00082 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.00038 U	< 0.0021 U	< 0.00036 U	0.024	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0061 U	< 0.00070 U	< 0.00052 U	< 0.0022 U	< 0.00072 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated								
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated								
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.00049 U	< 0.0028 U	< 0.00046 U	< 0.0070 U	< 0.00081 U	< 0.00060 U	< 0.0025 U	< 0.00083 UT
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated								
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated								
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated								
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 UT	< 0.00047 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.00024 U	< 0.0014 UT	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 UT	< 0.00041 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.00035 UT	< 0.0020 UT	< 0.00033 UT	0.0081 T	< 0.00058 UT	< 0.00043 UT	< 0.0018 UT	< 0.00060 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00044 U	< 0.0025 UT	< 0.00042 U	0.45	< 0.00074 U	< 0.00054 U	< 0.0023 UT	< 0.00076 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.00034 U	< 0.0020 UT	< 0.00033 U	< 0.0049 U	< 0.00057 U	0.0068	< 0.0018 UT	< 0.00059 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 UT
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.00050 U	< 0.0028 UT	< 0.00047 U	< 0.0071 U	< 0.00082 U	< 0.00061 U	< 0.0026 UT	< 0.00084 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.00037 U	< 0.0021 UT	< 0.00035 U	0.0059 J	< 0.00061 U	< 0.00045 U	< 0.0019 UT	< 0.00063 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.00027 U	< 0.0015 UT	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.00034 U	< 0.0019 UT	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.00037 U	< 0.0021 UT	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.00031 U	< 0.0018 UT	< 0.00029 U	< 0.0044 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.00024 U	< 0.0014 UT	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0012 U	< 0.00041 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	0.0062	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.0019 UT	< 0.0015 U	< 0.0025 U	< 0.0071 UT	< 0.0023 UT	< 0.0024 UT	< 0.0018 U	< 0.0014 UT
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0024 U	< 0.0018 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.0013 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.0012 U	< 0.0012 U	< 0.0016 U	< 0.0012 U	< 0.0023 U	< 0.0021 U	< 0.0014 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0024 U	< 0.0015 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00048 U	< 0.00037 U	< 0.00053 U	< 0.00040 U	< 0.00031 U	< 0.00062 U	< 0.00040 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.00032 UT	< 0.00024 UT	< 0.00035 UT	< 0.00027 UT	< 0.00021 UT	< 0.00041 UT	< 0.00027 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.00045 U	< 0.00034 U	< 0.00049 U	< 0.00038 U	< 0.00029 U	< 0.00057 U	< 0.00037 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00026 U	< 0.00051 U	< 0.00033 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	0.00036 J	< 0.00018 U	< 0.00036 U	< 0.00023 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.00033 U	< 0.00025 UT	< 0.00036 U	< 0.00028 U	< 0.00021 UT	< 0.00042 UT	< 0.00028 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated							
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated							
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.00045 U	< 0.00035 U	< 0.00049 U	< 0.00038 U	< 0.00029 U	< 0.00058 U	< 0.00038 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated							
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated							
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated							
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.00032 UT	< 0.00025 UT	< 0.00036 UT	< 0.00027 UT	< 0.00021 UT	< 0.00042 UT	< 0.00027 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00041 U	< 0.00032 U	0.00064 J	< 0.00035 U	< 0.00027 U	< 0.00053 U	< 0.00034 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.00046 U	< 0.00035 U	< 0.00050 U	< 0.00039 U	< 0.00030 U	< 0.00059 U	< 0.00038 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	0.00024 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00029 UT	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.00025 UT	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.00031 UT	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.00034 UT	< 0.00026 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00030 UT	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.00029 UT	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.00022 UT	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 UT	< 0.0026 UT	< 0.0017 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UT	< 0.0029 UT	< 0.0019 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 UT
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	852.38	-	847.58	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4-20211014	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.00087 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1-20211014	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SLT-S9	SSHS-ISMP-SLT-S9-20211014	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2-20211014	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	SLT-S4	SSHS-ISMP-SLT-S4-20211014	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3-20211014	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 0.0012 U	0.0032 J	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SLT-S6	SSHS-ISMP-SLT-S6-20211014	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Football Field	SLT-S12	SSHS-ISMP-SLT-S12-20211014	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 0.0012 U	0.0031 J	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4-20211014	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Football Field	SLT-S15	SSHS-ISMP-SLT-S15-20211014	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6-20211014	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SLT-S19	SSHS-ISMP-SLT-S19-20211014	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5-20211014	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	SLT-S18	SSHS-ISMP-SLT-S18-20211014	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7-20211014	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 0.00089 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0065 U
Football Field	SLT-S31	SSHS-ISMP-SLT-S31-20211014	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005-20211028	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 0.00081 U	< 0.0013 U	< 0.0034 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0059 U
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006-20211028	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 0.00092 U	0.0033 J	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0019 U	< 0.0067 U
Football Field	ISMP-S612	SSHS-ISMP-DUPB-20211201	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Football Field	ISMP-S612	SSHS-ISMP-S612-20211201	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 0.00031 U	< 0.00055 U	< 0.00070 U	< 0.00094 U	< 0.00030 U	< 0.00034 U	< 0.0011 U
Football Field	ISMP-B609	SSHS-ISMP-B609-20211201	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00056 U
Football Field	ISMP-S614	SSHS-ISMP-S614-20211201	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 0.00020 UT	< 0.00037 UT	< 0.00046 UT	< 0.00062 UT	< 0.00020 UT	< 0.00022 UT	< 0.00073 UT
Football Field	ISMP-S615	SSHS-ISMP-S615-20211201	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 0.00029 U	< 0.00052 U	< 0.00065 U	< 0.00088 U	< 0.00028 U	< 0.00031 U	< 0.0010 U
Football Field	ISMP-S617	SSHS-ISMP-S617-20211201	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 0.00022 U	0.00051 J	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00080 U
Football Field	ISMP-B610	SSHS-ISMP-B610-20211201	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 0.00025 U	< 0.00045 U	< 0.00057 U	< 0.00077 U	< 0.00025 U	< 0.00027 U	< 0.00091 U
Football Field	ISMP-S625	SSHS-ISMP-S625-20211202	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 0.00018 U	0.064	< 0.00041 U	< 0.00055 U	0.00024 J	< 0.00019 U	< 0.00064 U
Football Field	ISMP-S629	SSHS-ISMP-S629-20211202	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 0.00021 U	0.13	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00076 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211203	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated							
Football Field	ISMP-S639	SSHS-ISMP-S639-20211203	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated							
Football Field	ISMP-B617	SSHS-ISMP-B617-20211203	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 0.00029 U	0.012	< 0.00066 U	< 0.00089 U	< 0.00028 U	< 0.00031 U	< 0.0010 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211203	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated							
Football Field	ISMP-S641	SSHS-ISMP-S641-20211203	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated							
Football Field	ISMP-S643	SSHS-ISMP-S643-20211203	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated							
Football Field	ISMP-S645	SSHS-ISMP-S645-20211203	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 0.00016 U	0.036	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Football Field	ISMP-B618	SSHS-ISMP-B618-20211203	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 0.00014 U	0.028	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00051 U
Football Field	ISMP-S647	SSHS-ISMP-S647-20211203	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 0.00021 UT	0.055 T	< 0.00047 UT	< 0.00064 UT	< 0.00020 UT	< 0.00023 UT	< 0.00075 UT
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6-20211207	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00026 U	0.0096	< 0.00060 U	< 0.00081 U	< 0.00026 U	< 0.00029 U	< 0.00095 U
Football Field	SLT-S37	SSHS-ISMP-SLT-S37-20211207	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 0.00020 U	0.0025	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00073 U
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11-20211207	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 0.00019 U	0.0014	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00068 U
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12-20211207	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 0.00029 U	0.0023	< 0.00067 U	< 0.00090 U	< 0.00029 U	< 0.00032 U	< 0.0011 U
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13-20211207	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 0.00022 U	0.0015	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00079 U
Football Field	ISMP-S640	SSHS-ISMP-S640-20211208	SSHS-ISMP-S640	12/8/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801309511	Not Excavated	< 0.00018 U	0.016	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00066 U
Football Field	ISMP-S639	SSHS-ISMP-S639-20211208	SSHS-ISMP-S639	12/8/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801309511	Not Excavated	< 0.00016 U	0.033	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00058 U
Football Field	ISMP-S643	SSHS-ISMP-S643-20211208	SSHS-ISMP-S643	12/8/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801309511	Not Excavated	< 0.00014 U	0.024	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00051 U
Football Field	ISMP-B618	SSHS-ISMP-DUPF-20211210	SSHS-ISMP-DUPF	12/10/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801311092	Not Excavated	< 0.00015 U	0.053	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Football Field	ISMP-S641	SSHS-ISMP-S641-20211210	SSHS-ISMP-S641	12/10/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801311092	Not Excavated	< 0.00017 U	0.031	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Football Field	ISMP-S659	SSHS-ISMP-S659-20211214	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 0.00014 U	0.00052 J	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00051 U
Football Field	ISMP-B623	SSHS-ISMP-DUPH-20211216	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00019 U	0.00087 J	< 0.00043 U	< 0.00058 U	< 0.00018 UT	< 0.00021 UT	< 0.00068 UT
Football Field	ISMP-S667	SSHS-ISMP-S667-20211216	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 UT	< 0.00018 UT	< 0.00058 UT
Football Field	ISMP-S663	SSHS-ISMP-S663-20211216	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 0.00020 U	0.00071 J	< 0.00045 U	< 0.00061 U	< 0.00019 UT	< 0.00022 UT	< 0.00072 UT
Football Field	ISMP-S664	SSHS-ISMP-S664-20211216	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 0.00022 U	0.00082 J	< 0.00050 U	< 0.00067 U	< 0.00021 UT	< 0.00024 UT	< 0.00079 UT
Football Field	ISMP-B623	SSHS-ISMP-B623-20211216	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 UT	< 0.00021 UT	< 0.00069 UT
Football Field	ISMP-S665	SSHS-ISMP-S665-20211216	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 0.00018 U	0.00085 J	< 0.00042 U	< 0.00056 U	< 0.00018 UT	< 0.00020 UT	< 0.00066 UT
Football Field	ISMP-S666	SSHS-ISMP-S666-20211216	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 0.00014 U	0.00091	< 0.00033 U	< 0.00044 U	< 0.00014 UT	< 0.00016 UT	< 0.00052 UT
Football Field	IRM5-S401	SSHS-IRM5-S401-20211229	SSHS-IRM5-S401	12/29/2021	-	855.41	-	849.80	4 - 6 ft	5.61 ft	1801318161	Not Excavated	< 0.0011 U	0.0020 J	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ-20211230	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4-20211230	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 0.0011 U	0.0059	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1-20211230	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3-20211230	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1-20211230	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2-20211230	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1-20211230	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3-20211230	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4-20211230	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2-20211230	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	0.0036 J	0.0031 J	< 0.0082 U
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1-20220103	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2-20220103	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13-20220107	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 0.0011 U	0.047	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11-20220107	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 0.0011 U	0.026	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16-20220107	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 0.00096 U	0.14	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15-20220107	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 0.00095 U	0.11 T	< 0.0040 UT	< 0.0035 UT	< 0.0017 U	< 0.0019 U	< 0.0069 U
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17-20220107	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 0.0012 U	0.2	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8-20220110	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SLT-S44	SSHS-ISMP-SLT-S44-20220110	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 0.00097 U	0.0023 J	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	0.0067 J	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 UT	< 0.0048 U	< 0.0024 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0043 UT	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 UT	< 0.0022 UT
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0061 U	< 0.0022 U	< 0.0047 U	< 0.0036 U	< 0.0039 U	< 0.0036 U	< 0.0062 U	< 0.0032 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0047 UT	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 UT	< 0.0048 UT	< 0.0024 UT
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0044 UT	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 UT	< 0.0023 UT
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 UT	< 0.0043 UT	< 0.0022 UT
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0052 UT	< 0.0019 UT	< 0.0040 UT	< 0.0031 UT	< 0.0033 U	< 0.0030 UT	< 0.0053 UT	< 0.0027 UT
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 UT	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 UT	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 UT	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 UT	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	0.0088 J	< 0.006 U						< 0.006 U
Football Field	SSHS-B221	071615 09:30 SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated								
Football Field	SSHS-B216	071715 08:50 SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated								
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B212	072915 09:15 SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B220	072915 09:15 SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B234A	072915 09:15 SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B312	030316 09:45 SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B314	030316 09:45 SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B407	082616 09:00 SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B412	082616 09:00 SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B743	041417 09:10 SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated								
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated								

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UT	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 UT	< 0.0026 UT	< 0.0035 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0020 U	< 0.0039 U	< 0.0046 U	< 0.0025 U	< 0.0031 U	< 0.0037 U	< 0.0050 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 UT	< 0.0019 U	< 0.0024 UT	< 0.0029 UT	< 0.0039 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0023 UT	< 0.0027 UT	< 0.0037 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0017 U	< 0.0021 UT	< 0.0026 UT	< 0.0035 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0039 UT	< 0.0021 UT	< 0.0026 UT	< 0.0032 UT	< 0.0043 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0015 U	< 0.0028 UT	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 UT
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0015 U	< 0.0029 UT	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 UT
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0014 U	< 0.0026 UT	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0014 U	< 0.0026 UT	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	< 0.006 U			< 0.006 U			
Football Field	SSHS-B221	071615 09:30 SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated							
Football Field	SSHS-B216	071715 08:50 SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated							
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated							
Football Field	SSHS-B212	072915 09:15 SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B220	072915 09:15 SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B234A	072915 09:15 SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B312	030316 09:45 SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B314	030316 09:45 SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B407	082616 09:00 SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B412	082616 09:00 SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B743	041417 09:10 SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated							
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0070 U	< 0.0021 U	< 0.0039 UT	< 0.0026 U	< 0.0048 U	< 0.0023 U	< 0.0025 U	< 0.0022 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0060 UT	< 0.0018 U	< 0.0033 UT	< 0.0022 U	< 0.0041 U	< 0.0020 U	< 0.0021 UT	< 0.0019 UT
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 UT	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 UT
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 UT	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 UT
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0051 UT	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 UT
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 UT
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 UT	< 0.0015 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	< 0.006 U			< 0.4 U	< 0.4 U	< 0.4 U	< 0.006 U	< 0.006 U
Football Field	SSHS-B221	071615 09:30_SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated								
Football Field	SSHS-B216	071715 08:50_SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated								
Football Field	SSHS-B232	072815 05:00_SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B212	072915 09:15_SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B220	072915 09:15_SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B234A	072915 09:15_SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B312	030316 09:45_SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B314	030316 09:45_SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B407	082616 09:00_SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B412	082616 09:00_SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20_SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B743	041417 09:10_SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated								
Football Field	SSHS-B629A	071117 08:30_SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0025 UT	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0035 U	< 0.0064 U	< 0.0024 U	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.0035 U	< 0.0029 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0027 UT	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0026 UT	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0025 UT	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0030 UT	< 0.0054 UT	< 0.0020 UT	< 0.0023 UT	< 0.0018 UT	< 0.0029 UT	< 0.0030 U	< 0.0025 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 UT	< 0.0025 UT	< 0.0026 UT	< 0.0021 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 UT	< 0.0026 UT	< 0.0027 UT	< 0.0022 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 UT	< 0.0023 UT	< 0.0024 UT	< 0.0020 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 UT	< 0.0023 UT	< 0.0024 UT	< 0.0020 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated	< 0.006 U		< 0.006 U	< 0.006 U				< 0.006 U
Football Field	SSHS-B221	071615 09:30 SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated								
Football Field	SSHS-B216	071715 08:50 SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated								
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B212	072915 09:15 SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B220	072915 09:15 SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B234A	072915 09:15 SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B312	030316 09:45 SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B314	030316 09:45 SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B407	082616 09:00 SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B412	082616 09:00 SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B743	041417 09:10 SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated								
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 UT	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 UT	< 0.0028 UT	< 0.0020 UT	< 0.0016 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0031 U	< 0.0025 U	< 0.0041 U	< 0.011 U	< 0.0038 U	< 0.0040 U	< 0.0029 U	< 0.0023 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 UT	< 0.0031 UT	< 0.0022 UT	< 0.0018 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 UT	< 0.0029 UT	< 0.0021 UT	< 0.0017 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 UT	< 0.0028 UT	< 0.0020 UT	< 0.0016 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0027 UT	< 0.0021 U	< 0.0035 U	< 0.0098 UT	< 0.0032 UT	< 0.0034 UT	< 0.0024 U	< 0.0020 UT
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 UT	< 0.0021 UT	< 0.0017 UT
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 UT	< 0.0022 UT	< 0.0017 UT
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 UT	< 0.0019 UT	< 0.0016 UT
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 UT	< 0.0019 UT	< 0.0016 UT
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated						0.0018 J		
Football Field	SSHS-B221	071615 09:30_SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated								
Football Field	SSHS-B216	071715 08:50_SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated								
Football Field	SSHS-B232	072815 05:00_SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B212	072915 09:15_SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B220	072915 09:15_SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B234A	072915 09:15_SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B312	030316 09:45_SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B314	030316 09:45_SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B407	082616 09:00_SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B412	082616 09:00_SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20_SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B743	041417 09:10_SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated								
Football Field	SSHS-B629A	071117 08:30_SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0033 U	< 0.0021 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0016 U	< 0.0017 UT	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 UT
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0023 U	< 0.0024 U	< 0.0031 U	< 0.0022 U	< 0.0043 U	< 0.0040 U	< 0.0026 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0018 U	< 0.0018 UT	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 UT
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0017 U	< 0.0017 UT	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 UT
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0016 U	< 0.0016 UT	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 UT
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0022 UT
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-FB1	FB1_29 JUN 00_6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated			0.0035 J	< 0.006 U			< 0.006 U
Football Field	SSHS-B221	071615 09:30_SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated							
Football Field	SSHS-B216	071715 08:50_SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated							
Football Field	SSHS-B232	072815 05:00_SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated							
Football Field	SSHS-B212	072915 09:15_SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B220	072915 09:15_SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B234A	072915 09:15_SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B312	030316 09:45_SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B314	030316 09:45_SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B407	082616 09:00_SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B412	082616 09:00_SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00_SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00_SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20_SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B743	041417 09:10_SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated							
Football Field	SSHS-B629A	071117 08:30_SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00_SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SLT-S45	SSHS-ISMP-SLT-S45-20220110	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14-20220110	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Football Field	SLT-S46	SSHS-ISMP-SLT-S46-20220110	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	SLT-S47	SSHS-ISMP-SLT-S47-20220110	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SLT-S51	SSHS-ISMP-SLT-S51-20220110	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15-20220110	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SLT-S49	SSHS-ISMP-SLT-S49-20220110	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	SLT-S53	SSHS-ISMP-SLT-S53-20220112	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16-20220112	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SLT-S55	SSHS-ISMP-SLT-S55-20220112	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17-20220112	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-S671	SSHS-ISMP-S671-20220228	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 0.00091 U	0.0055	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0019 U	< 0.0066 U
Football Field	ISMP-S674	SSHS-ISMP-S674-20220228	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 0.0013 U	0.0036 J	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Football Field	ISMP-S668	SSHS-ISMP-S668-20220228	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 0.0012 U	0.0083 T	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	ISMP-S680	SSHS-ISMP-S680-20220228	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 UT	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-S701	SSHS-ISMP-DUPN-20220301	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0015 U	0.06	< 0.0065 U	< 0.0056 U	< 0.0028 U	< 0.0031 U	< 0.011 U
Football Field	ISMP-S695	SSHS-ISMP-S695-20220301	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 UT	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-S701	SSHS-ISMP-S701-20220301	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 0.0011 U	0.078	< 0.0047 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-S704	SSHS-ISMP-S704-20220301	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 0.0012 U	0.0078	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-S702	SSHS-ISMP-S702-20220301	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SLT-S57	SSHS-ISMP-SLT-S57-20220301	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 0.0013 U	< 0.0021 UT	< 0.0055 UT	< 0.0048 UT	< 0.0024 U	< 0.0027 U	< 0.0096 U
Football Field	SLT-S58	SSHS-ISMP-SLT-S58-20220301	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19-20220301	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	SLT-S59	SSHS-ISMP-SLT-S59-20220301	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SLT-S65	SSHS-ISMP-SLT-S65-20220301	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21-20220301	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SLT-S66	SSHS-ISMP-SLT-S66-20220301	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22-20220301	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A-20220301	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20-20220301	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	SLT-S62	SSHS-ISMP-SLT-S62-20220301	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SLT-S69	SSHS-ISMP-SLT-S69-20220301	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SLT-S70	SSHS-ISMP-SLT-S70-20220301	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	ISMP-B631A	SSHS-ISMP-B631A-20220302	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	IRM5-S432	SSHS-IRM5-S432-20220302	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	SLT-S73	SSHS-ISMP-SLT-S73-20220302	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23-20220302	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	SLT-S74	SSHS-ISMP-SLT-S74-20220302	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220305	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220305	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220305	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220305	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220305	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2-20220307	SSHS-ISMP-PIPE3-S2	3/7/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 0.0011 UT	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4-20220307	SSHS-ISMP-PIPE3-S4	3/7/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 0.0012 UT	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8-20220307	SSHS-ISMP-PIPE3-S8	3/7/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2-20220307	SSHS-ISMP-PIPE3-BOT2	3/7/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 0.0011 UT	0.0073	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6-20220307	SSHS-ISMP-PIPE3-S6	3/7/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 0.0011 UT	0.0027 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2-20220308	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1-20220308	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	ISMP-S2006	SSHS-ISMP-S2006-20220308	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 0.0010 U	0.0019 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-S2014	SSHS-ISMP-S2014-20220309	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 0.0011 U	0.012	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80-20220322	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT-20220322	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1-20220322	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2-20220322	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3-20220322	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	SSHS-FB1	FB1 29 JUN 00 6-8	B23494	6/29/2000	857.00	855.82	-1.18	--	6 - 8 ft	4.82-6.82 ft	NA	Not Excavated		< 0.006 U		< 0.006 U	< 0.006 U	< 0.006 U	
Football Field	SSHS-B221	071615 09:30 SSHS-B221-SUB-6-8	SSHS-B221-SUB-6-8	7/15/2015	855.95	855.96	0.01	-	6 - 8 ft	6.01-8.01 ft	180-45961-1	Not Excavated							
Football Field	SSHS-B216	071715 08:50 SSHS-B216-SUB-6-8	SSHS-B216-SUB-6-8	7/16/2015	855.82	855.81	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46033-1	Not Excavated							
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-6-8	SSHS-B232-SUB-6-8	7/27/2015	856.44	856.44	0.00	-	6 - 8 ft	6-8 ft	180-46300-1	Not Excavated							
Football Field	SSHS-B212	072915 09:15 SSHS-B212-SUB-6-8	SSHS-B212-SUB-6-8	7/28/2015	855.42	855.41	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B220	072915 09:15 SSHS-B220-SUB-6-8	SSHS-B220-SUB-6-8	7/28/2015	855.52	855.52	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B234A	072915 09:15 SSHS-B234A-SUB-6-8	SSHS-B234A-SUB-6-8	7/28/2015	857.08	857.08	0.00	-	6 - 8 ft	6-8 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B312	030316 09:45 SSHS-B312-SUB-6-8	SSHS-B312-SUB-6-8	3/2/2016	857.49	857.49	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B314	030316 09:45 SSHS-B314-SUB-6-8	SSHS-B314-SUB-6-8	3/2/2016	856.85	856.85	0.00	-	6 - 8 ft	6-8 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B407	082616 09:00 SSHS-B407-SUB-6-8	SSHS-B407-SUB-6-8	8/25/2016	857.28	857.28	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B412	082616 09:00 SSHS-B412-SUB-6-8	SSHS-B412-SUB-6-8	8/25/2016	856.86	856.86	0.00	-	6 - 8 ft	6-8 ft	180-57995-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-6-8	SSHS-B451-SUB-6-8	9/27/2016	854.61	855.67	1.06	-	6 - 8 ft	7.06-9.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-6-8	SSHS-B452-SUB-6-8	9/27/2016	854.99	855.46	0.47	-	6 - 8 ft	6.47-8.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-6-8	SSHS-B629-SUB-6-8	2/9/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B743	041417 09:10 SSHS-B743-SUB-6-8	SSHS-B743-SUB-6-8	4/13/2017	855.75	855.75	0.00	-	6 - 8 ft	6-8 ft	180-65226-1	Not Excavated							
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-6-8	SSHS-B629A-SUB-6-8	7/10/2017	855.95	855.95	0.00	-	6 - 8 ft	6-8 ft	180-68038-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-6-8	SSHS-B2185-SUB-6-8	7/24/2018	855.07	855.49	0.42	-	6 - 8 ft	6.42-8.42 ft	180-80106-3	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2329	082918 09:00 SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated							
Football Field	SSHS-B2368	083018 09:15 SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated							
Football Field	SSHS-B2369	083018 09:15 SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2686	051619 09:00 PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0029 UJ	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0042 UJ	< 0.0028 U	< 0.0031 U
Football Field	SSHS-B2686	051619 09:00 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	0.031 J	< 0.0017 U	< 0.0017 U	< 0.0021 U	< 0.0023 U	< 0.004 UJ	< 0.0027 U	< 0.003 U
Football Field	SSHS-B2619	051719 09:00 SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2620	051719 09:00 PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2620	051719 09:00 SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2648	051719 09:00 SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2649	051819 10:00 SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2671	052119 08:40 SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated							
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated							
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated							
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated							
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	0.045 B	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated							
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated							
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated							
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated							
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated							
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated							
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated							
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated							
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated							

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated						
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated						
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated						
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated						
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated						
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated						
Football Field	SSHS-B2329	082918 09:00 SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated						
Football Field	SSHS-B2368	083018 09:15 SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated						
Football Field	SSHS-B2369	083018 09:15 SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated						
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2686	051619 09:00 PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0015 U	< 0.0022 U	< 0.0024 U	< 0.002 U	< 0.0036 UJ	< 0.0011 U	< 0.0029 U
Football Field	SSHS-B2686	051619 09:00 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0014 U	< 0.0021 U	< 0.0023 U	< 0.0019 U	< 0.0034 UJ	< 0.0011 U	< 0.0027 U
Football Field	SSHS-B2619	051719 09:00 SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2620	051719 09:00 PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2620	051719 09:00 SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2648	051719 09:00 SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2649	051819 10:00 SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2671	052119 08:40 SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated						
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 UT
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated						
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated						
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated						
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated						
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated						
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated						
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated						
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated						
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated						
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated						

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2329	082918 09:00 SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated								
Football Field	SSHS-B2368	083018 09:15 SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated								
Football Field	SSHS-B2369	083018 09:15 SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2686	051619 09:00 PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	0.0059 J	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.00095 U	< 0.0017 U	< 0.0013 U
Football Field	SSHS-B2686	051619 09:00 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0034 UJ	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00091 U	< 0.0016 U	< 0.0013 U
Football Field	SSHS-B2619	051719 09:00 SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2620	051719 09:00 PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2620	051719 09:00 SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2648	051719 09:00 SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2649	051819 10:00 SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2671	052119 08:40 SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated								
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.0046 U	< 0.0032 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated								
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated								
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated								
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated								
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated								
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated								
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated								
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2186	072518 09:00_SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00_SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00_SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00_SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00_SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00_SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00_SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00_SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50_SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2089	072618 08:50_SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50_SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50_SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50_SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50_SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50_SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50_SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50_SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2143	072618 08:50_SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50_PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2194	072618 08:50_SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50_SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00_SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00_SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2028	072718 09:00_SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00_SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2192	072718 09:00_SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00_SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00_SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2215	072718 09:00_SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00_SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30_SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30_SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30_SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30_SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2090	072818 11:30_SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2190	072818 11:30_SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2217	072818 11:30_SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2329	082918 09:00_SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated								
Football Field	SSHS-B2368	083018 09:15_SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated								
Football Field	SSHS-B2369	083018 09:15_SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00_SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2763	042819 10:00_SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Football Field	SSHS-B2773	051519 08:45_SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2774	051519 08:45_SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2686	051619 09:00_PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0026 U	< 0.0037 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0016 U	< 0.002 U
Football Field	SSHS-B2686	051619 09:00_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0015 U	< 0.0019 U
Football Field	SSHS-B2619	051719 09:00_SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2620	051719 09:00_PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2620	051719 09:00_SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2648	051719 09:00_SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2649	051819 10:00_SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2671	052119 08:40_SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated								
Football Field	SSHS-B2777	052119 08:40_SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2778	052119 08:40_SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2779	052119 08:40_SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2786	052119 08:40_SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2787	052119 08:40_SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2788	052119 08:40_PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2788	052119 08:40_SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2686	052219 08:40_SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2789	052219 08:40_SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2790	052219 08:40_SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.0030 U	< 0.0029 U	< 0.0019 U	< 0.0020 U	< 0.0025 U
Football Field	SSHS-IRM3-S097	080319 09:30_SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B3094	083119 10:15_SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated								
Football Field	SSHS-B2942	110719 09:00_DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated								
Football Field	SSHS-B2942	110719 09:00_SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated								
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated								
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated								
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated								
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated								
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated								
Football Field	SSHS-B3459	072820 09:00_SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2329	082918 09:00 SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated								
Football Field	SSHS-B2368	083018 09:15 SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated								
Football Field	SSHS-B2369	083018 09:15 SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2686	051619 09:00 PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0018 U	< 0.0039 U	< 0.0021 U	< 0.0055 U	< 0.002 U	< 0.0027 U	< 0.0017 UJ	< 0.0034 U
Football Field	SSHS-B2686	051619 09:00 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0017 U	< 0.0037 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 UJ	< 0.0033 U
Football Field	SSHS-B2619	051719 09:00 SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2620	051719 09:00 PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2620	051719 09:00 SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2648	051719 09:00 SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2649	051819 10:00 SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2671	052119 08:40 SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated								
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated								
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated								
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated								
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.0023 U	< 0.0050 U	< 0.0027 U	< 0.0070 U	< 0.0025 U	0.011	< 0.0022 U	< 0.0044 U
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated								
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated								
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated								
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated								
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated								
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated								
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated								
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated								
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated						
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated						
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated						
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated						
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated						
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated						
Football Field	SSHS-B2329	082918 09:00 SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated						
Football Field	SSHS-B2368	083018 09:15 SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated						
Football Field	SSHS-B2369	083018 09:15 SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated						
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2686	051619 09:00 PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0012 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U	< 0.0023 U
Football Field	SSHS-B2686	051619 09:00 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0033 U	< 0.0022 U
Football Field	SSHS-B2619	051719 09:00 SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2620	051719 09:00 PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2620	051719 09:00 SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2648	051719 09:00 SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2649	051819 10:00 SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2671	052119 08:40 SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated						
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated						
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated						
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.0020 U	< 0.0042 UT	< 0.0044 UT	< 0.0030 U
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated						
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated						
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated						
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated						
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated						
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated						
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated						
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated						
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated						
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-6-8	SSHS-B2186-SUB-6-8	7/24/2018	854.94	855.41	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-6-8	SSHS-B2187-SUB-6-8	7/24/2018	856.10	856.10	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-6-8	SSHS-B2188-SUB-6-8	7/24/2018	855.99	855.99	0.00	-	6 - 8 ft	6-8 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-6-8	SSHS-B2189-SUB-6-8	7/24/2018	855.74	855.90	0.16	-	6 - 8 ft	6.16-8.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-6-8	SSHS-B2191-SUB-6-8	7/24/2018	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-6-8	SSHS-B2197-SUB-6-8	7/24/2018	854.99	855.43	0.44	-	6 - 8 ft	6.44-8.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-6-8	SSHS-B2232-SUB-6-8	7/24/2018	856.82	856.82	0.00	-	6 - 8 ft	6-8 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-6-8	SSHS-B2233-SUB-6-8	7/24/2018	854.83	855.35	0.52	-	6 - 8 ft	6.52-8.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-6-8	SSHS-B2070-SUB-6-8	7/25/2018	854.72	855.22	0.50	-	6 - 8 ft	6.5-8.5 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-6-8	SSHS-B2089-SUB-6-8	7/25/2018	855.40	855.39	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-6-8	SSHS-B2091-SUB-6-8	7/25/2018	856.61	856.61	0.00	-	6 - 8 ft	6-8 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-6-8	SSHS-B2108-SUB-6-8	7/25/2018	855.64	855.64	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-6-8	SSHS-B2109-SUB-6-8	7/25/2018	855.25	855.48	0.23	-	6 - 8 ft	6.23-8.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-6-8	SSHS-B2110-SUB-6-8	7/25/2018	854.78	855.36	0.58	-	6 - 8 ft	6.58-8.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-6-8	SSHS-B2127-SUB-6-8	7/25/2018	855.91	855.91	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-6-8	SSHS-B2128-SUB-6-8	7/25/2018	856.01	856.01	0.00	-	6 - 8 ft	6-8 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-6-8	SSHS-B2129-SUB-6-8	7/25/2018	855.33	855.52	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 PS-FD-21	PS-FD-21	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-6-8	SSHS-B2143-SUB-6-8	7/25/2018	856.56	856.56	0.00	-	6 - 8 ft	6-8 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 PS-FD-30	PS-FD-30	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-2	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-6-8	SSHS-B2194-SUB-6-8	7/25/2018	856.19	856.19	0.00	-	6 - 8 ft	6-8 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-6-8	SSHS-B2216-SUB-6-8	7/25/2018	855.16	855.46	0.30	-	6 - 8 ft	6.3-8.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-6-8	SSHS-B2025-SUB-6-8	7/26/2018	854.55	854.52	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-6-8	SSHS-B2026-SUB-6-8	7/26/2018	855.26	855.47	0.21	-	6 - 8 ft	6.21-8.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-6-8	SSHS-B2028-SUB-6-8	7/26/2018	855.23	855.54	0.31	-	6 - 8 ft	6.31-8.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-6-8	SSHS-B2050-SUB-6-8	7/26/2018	855.45	855.45	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-6-8	SSHS-B2192-SUB-6-8	7/26/2018	855.49	855.50	0.01	-	6 - 8 ft	6.01-8.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-6-8	SSHS-B2195-SUB-6-8	7/26/2018	855.94	855.94	0.00	-	6 - 8 ft	6-8 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-6-8	SSHS-B2213-SUB-6-8	7/26/2018	855.06	855.53	0.47	-	6 - 8 ft	6.47-8.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-6-8	SSHS-B2215-SUB-6-8	7/26/2018	855.11	855.30	0.19	-	6 - 8 ft	6.19-8.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-6-8	SSHS-B2224-SUB-6-8	7/26/2018	854.93	855.29	0.36	-	6 - 8 ft	6.36-8.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-6-8	SSHS-B2031-SUB-6-8	7/27/2018	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-6-8	SSHS-B2032-SUB-6-8	7/27/2018	854.88	855.51	0.63	-	6 - 8 ft	6.63-8.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-6-8	SSHS-B2033-SUB-6-8	7/27/2018	854.70	855.74	1.04	-	6 - 8 ft	7.04-9.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-6-8	SSHS-B2051-SUB-6-8	7/27/2018	855.08	855.37	0.29	-	6 - 8 ft	6.29-8.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-6-8	SSHS-B2090-SUB-6-8	7/27/2018	855.97	855.96	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-6-8	SSHS-B2190-SUB-6-8	7/27/2018	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-6-8	SSHS-B2217-SUB-6-8	7/27/2018	855.08	855.32	0.24	-	6 - 8 ft	6.24-8.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2329	082918 09:00 SSHS-B2329-SUB-6-8	SSHS-B2329-SUB-6-8	8/28/2018	856.92	856.92	0.00	-	6 - 8 ft	6-8 ft	180-81347-1	Not Excavated							
Football Field	SSHS-B2368	083018 09:15 SSHS-B2368-SUB-6-8	SSHS-B2368-SUB-6-8	8/29/2018	856.48	856.48	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated							
Football Field	SSHS-B2369	083018 09:15 SSHS-B2369-SUB-6-8	SSHS-B2369-SUB-6-8	8/29/2018	856.80	856.80	0.00	-	6 - 8 ft	6-8 ft	180-81403-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-6-8	SSHS-B2767-SUB-6-8	4/23/2019	856.06	856.06	0.00	-	6 - 8 ft	6-8 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-6-8	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-6-8	SSHS-B2773-SUB-6-8	5/13/2019	854.27	854.35	0.08	-	6 - 8 ft	6.08-8.08 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-6-8	SSHS-B2774-SUB-6-8	5/13/2019	854.02	854.07	0.05	-	6 - 8 ft	6.05-8.05 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2686	051619 09:00 PS-FD-9	PS-FD-9	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0014 UJ	< 0.0034 UJ	< 0.0017 U	< 0.0023 U	< 0.004 U
Football Field	SSHS-B2686	051619 09:00 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/15/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90165-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0013 UJ	< 0.0033 UJ	< 0.0017 U	< 0.0022 U	< 0.0038 U
Football Field	SSHS-B2619	051719 09:00 SSHS-B2619-SUB-6-8	SSHS-B2619-SUB-6-8	5/16/2019	855.10	855.30	0.20	-	6 - 8 ft	6.2-8.2 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2620	051719 09:00 PS-FD-17	PS-FD-17	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2620	051719 09:00 SSHS-B2620-SUB-6-8	SSHS-B2620-SUB-6-8	5/16/2019	855.02	855.27	0.25	-	6 - 8 ft	6.25-8.25 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2648	051719 09:00 SSHS-B2648-SUB-6-8	SSHS-B2648-SUB-6-8	5/16/2019	855.86	855.86	0.00	-	6 - 8 ft	6-8 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2649	051819 10:00 SSHS-B2649-SUB-6-8	SSHS-B2649-SUB-6-8	5/17/2019	856.28	856.28	0.00	-	6 - 8 ft	6-8 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2671	052119 08:40 SSHS-B2671-SUB-6-8	SSHS-B2671-SUB-6-8	5/18/2019	855.78	855.78	0.00	-	6 - 8 ft	6-8 ft	180-90319-1	Not Excavated							
Football Field	SSHS-B2777	052119 08:40 SSHS-B2777-SUB-6-8	SSHS-B2777-SUB-6-8	5/19/2019	854.82	855.37	0.55	-	6 - 8 ft	6.55-8.55 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2778	052119 08:40 SSHS-B2778-SUB-6-8	SSHS-B2778-SUB-6-8	5/19/2019	855.64	855.65	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2779	052119 08:40 SSHS-B2779-SUB-6-8	SSHS-B2779-SUB-6-8	5/19/2019	855.06	855.39	0.33	-	6 - 8 ft	6.33-8.33 ft	180-90323-1	Not Excavated							
Football Field	SSHS-B2786	052119 08:40 SSHS-B2786-SUB-6-8	SSHS-B2786-SUB-6-8	5/20/2019	856.97	856.98	0.01	-	6 - 8 ft	6.01-8.01 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2787	052119 08:40 SSHS-B2787-SUB-6-8	SSHS-B2787-SUB-6-8	5/20/2019	857.02	857.01	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2788	052119 08:40 PS-FD-26	PS-FD-26	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2788	052119 08:40 SSHS-B2788-SUB-6-8	SSHS-B2788-SUB-6-8	5/20/2019	856.74	856.74	0.00	-	6 - 8 ft	6-8 ft	180-90324-1	Not Excavated							
Football Field	SSHS-B2686	052219 08:40 SSHS-B2686-SUB-6-8	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated							
Football Field	SSHS-B2789	052219 08:40 SSHS-B2789-SUB-6-8	SSHS-B2789-SUB-6-8	5/21/2019	855.23	855.57	0.34	-	6 - 8 ft	6.34-8.34 ft	180-90380-1	Not Excavated							
Football Field	SSHS-B2790	052219 08:40 SSHS-B2790-SUB-6-8	SSHS-B2790-SUB-6-8	5/21/2019	855.30	855.52	0.22	-	6 - 8 ft	6.22-8.22 ft	180-90380-1	Not Excavated							
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8-20190521	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Football Field	SSHS-IRM3-S097	080319 09:30 SSHS-IRM3-S097-C	SSHS-IRM3-S097-C	8/2/2019	-	855.71	-	848.45	6 - 8 ft	7.26 ft	180-93640-1	Not Excavated							
Football Field	SSHS-B3094	083119 10:15 SSHS-DUP-56	SSHS-DUP-56	8/30/2019	857.26	857.26	0.00	-	6 - 8 ft	6-8 ft	180-95050-2	Not Excavated							
Football Field	SSHS-B2942	110719 09:00 DUP-11	DUP-11	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-3	Not Excavated							
Football Field	SSHS-B2942	110719 09:00 SSHS-B2942-SUB-6-8	SSHS-B2942-SUB-6-8	11/5/2019	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-98355-2	Not Excavated							
Football Field	IRM4-B05	SSHS-IRM4-B05-20200723	SSHS-IRM4-B05	7/23/2020	-	855.52	-	847.91	6 - 8 ft	7.61 ft	1801086851	Not Excavated							
Football Field	IRM4-S099	SSHS-IRM4-S099-6-8-20200723	SSHS-IRM4-S099-6-8	7/23/2020	-	855.59	-	848.25	6 - 8 ft	7.34 ft	1801086851	Not Excavated							
Football Field	IRM4-S101	SSHS-IRM4-S101-6-8-20200723	SSHS-IRM4-S101-6-8	7/23/2020	-	855.44	-	848.08	6 - 8 ft	7.36 ft	1801086851	Not Excavated							
Football Field	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O-20200723	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated							
Football Field	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O-20200723	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated							
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-6-8	SSHS-B3459-SUB-6-8	7/27/2020	856.30	856.31	0.01	-	6 - 8 ft	6.01-8.01 ft	180-108826-2	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated							
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated							
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated							
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated							
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated							
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated							
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated							
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated							
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated							
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SSHS-B3572	020521 09:00 DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.23 U	< 0.083 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.13 U	< 0.24 U	< 0.12 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.25 U	< 0.092 U	< 0.2 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.26 U	< 0.13 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated								
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated								
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated								
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated								
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated								
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated								
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated								
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated								
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated								
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated								
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated								
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated								
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated								
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated								
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated								
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated								
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated								
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated								
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated								
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated								
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated								
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated								
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated								
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated								
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated								
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated								
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated								
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated								

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00		6 - 8 ft	6-8 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated						
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated						
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated						
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated						
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated						
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated						
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated						
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated						
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated						
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated						
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated						
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated						
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated						
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated						
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 UJ	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UJ	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UJ
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3572	020521 09:00 DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.077 U	< 0.15 U	< 0.17 U	< 0.095 U	< 0.12 U	< 0.14 U	< 0.19 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.085 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.16 U	< 0.21 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 UJ
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated						
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated						
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated						
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated						
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated						
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated						
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated						
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated						
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated						
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated						
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated						
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated						
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated						
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated						
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated						
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated						
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated						
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated						
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated						
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated						
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated						
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated						
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated						
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated						
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated						
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated						
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated						
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated						
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated						
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated						
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated						
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated						
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated						
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated						
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated						
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated						
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated						
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated						
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated						
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated						
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated						
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated						
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated						
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated						
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated						
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated						

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3461	072820 09:00_SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3464	072820 09:00_SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3472	072820 09:00_SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3473	072820 09:00_SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated							
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated							
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated							
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated							
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated							
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated							
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated							
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated							
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated							
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated							
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 UJ	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3572	020521 09:00_DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.27 U	< 0.081 U	< 0.15 U	< 0.099 U	< 0.18 U	< 0.089 U	< 0.094 U	< 0.085 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.29 U	< 0.089 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.098 U	< 0.1 U	< 0.094 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 UJ	< 0.0034 UJ	< 0.0017 UJ	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated							
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated							
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated							
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated							
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated							
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated							
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated							
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated							
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated							
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated							
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated							
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated							
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated							
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated							
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated							
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated							
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated							
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated							
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated							
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated							
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated							
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated							
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated							
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated							
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated							
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated							
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated							
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated							
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated							

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated								
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated								
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated								
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated								
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated								
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated								
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated								
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated								
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated								
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated								
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated								
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated								
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated								
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B3572	020521 09:00 DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.13 UJ	< 0.24 U	< 0.089 U	< 0.1 U	< 0.079 U	< 0.13 U	< 0.13 U	< 0.11 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.15 UJ	< 0.27 U	< 0.098 U	< 0.11 U	< 0.087 U	< 0.14 U	< 0.15 U	< 0.12 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated								
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated								
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated								
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated								
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated								
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated								
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated								
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated								
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated								
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated								
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated								
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated								
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated								
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated								
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated								
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated								
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated								
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated								
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated								
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated								
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated								
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated								
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated								
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated								
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated								
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated								
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated								
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated								
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated								
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated								
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated								
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated								
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated								
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated								
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated								
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated								
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated								
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated								
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated								
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated								
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00 DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.12 U	< 0.093 U	< 0.15 U	< 0.43 U	< 0.14 U	< 0.15 U	< 0.11 U	< 0.087 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.13 U	< 0.1 U	< 0.17 U	< 0.48 U	< 0.16 U	< 0.17 U	< 0.12 U	< 0.096 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated								
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated								
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated								
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated								
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated								
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated								
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated								
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated								
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated								
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated								
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated								
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated								
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated								
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated								
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated								
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated								
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated								
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated								
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated								
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated								
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated								
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated								
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated								
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated								
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated								
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated								
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated								
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated								
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated								
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated								
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated								
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated								
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated							
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated							
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated							
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated							
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated							
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated							
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated							
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated							
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated							
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ	< 0.0018 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3572	020521 09:00 DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.089 U	< 0.09 U	< 0.12 U	< 0.085 U	< 0.16 U	< 0.15 U	< 0.099 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0019 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.098 U	< 0.099 U	< 0.13 U	< 0.094 U	< 0.18 U	< 0.17 U	< 0.11 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 UJ	< 0.0028 UJ	< 0.0019 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated							
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated							
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated							
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated							
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated							
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated							
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated							
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated							
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated							
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated							
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated							
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated							
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated							
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated							
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated							
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated							
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated							
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated							
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated							
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated							
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated							
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated							
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated							
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated							
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated							
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated							
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated							
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated							
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated							

DRAFT

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-6-8	SSHS-B3461-SUB-6-8	7/27/2020	856.51	856.51	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-6-8	SSHS-B3464-SUB-6-8	7/27/2020	856.28	856.27	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-6-8	SSHS-B3472-SUB-6-8	7/27/2020	855.50	855.50	0.00	-	6 - 8 ft	6-8 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-6-8	SSHS-B3473-SUB-6-8	7/27/2020	855.34	855.50	0.16	-	6 - 8 ft	6.16-8.16 ft	180-108826-2	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-DUP26-20200813	SSHS-IRM4-DUP26	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S180S	SSHS-IRM4-S180S-20200813	SSHS-IRM4-S180S	8/13/2020	-	855.54	-	848.48	6 - 8 ft	7.06 ft	1801095841	Not Excavated							
Football Field	IRM4-S184S	SSHS-IRM4-S184S-20200813	SSHS-IRM4-S184S	8/13/2020	-	855.46	-	847.46	6 - 8 ft	8 ft	1801095841	Not Excavated							
Football Field	IRM4-S185S	SSHS-IRM4-S185S-20200813	SSHS-IRM4-S185S	8/13/2020	-	855.48	-	849.45	6 - 8 ft	6.03 ft	1801095841	Not Excavated							
Football Field	IRM4-S192N	SSHS-IRM4-S192N-20200813	SSHS-IRM4-S192N	8/13/2020	-	855.41	-	848.08	6 - 8 ft	7.33 ft	1801095841	Not Excavated							
Football Field	IRM4-S196N	SSHS-IRM4-S196N-20200813	SSHS-IRM4-S196N	8/13/2020	-	855.46	-	848.10	6 - 8 ft	7.36 ft	1801095841	Not Excavated							
Football Field	IRM4A-S099	SSHS-IRM4A-S099-20201007	SSHS-IRM4A-S099	10/7/2020	-	855.57	-	848.63	6 - 8 ft	6.94 ft	1801119521	Not Excavated							
Football Field	IRM4A-S096	SSHS-IRM4A-S096-20201008	SSHS-IRM4A-S096	10/8/2020	-	856.38	-	848.64	6 - 8 ft	7.74 ft	1801120561	Not Excavated							
Football Field	IRM4A-S084	SSHS-IRM4A-S084-4-6-20201118	SSHS-IRM4A-S084-4-6	11/18/2020	-	856.33	-	849.70	6 - 8 ft	6.63 ft	1801138131	Not Excavated							
Football Field	IRM4A-S039	SSHS-IRM4A-S039-2-4-20201118	SSHS-IRM4A-S039-2-4	11/18/2020	-	856.05	-	849.02	6 - 8 ft	7.03 ft	1801138131	Not Excavated							
Football Field	IRM4A-S035	SSHS-IRM4A-S035-4-6-20201118	SSHS-IRM4A-S035-4-6	11/18/2020	-	855.96	-	849.24	6 - 8 ft	6.72 ft	1801138131	Not Excavated							
Football Field	IRM4A-S087	SSHS-IRM4A-S087-4-6-20201118	SSHS-IRM4A-S087-4-6	11/18/2020	-	856.05	-	848.81	6 - 8 ft	7.24 ft	1801138131	Not Excavated							
Football Field	IRM5-S244	SSHS-IRM5-S244-20210108	SSHS-IRM5-S244	1/8/2021	-	855.44	-	847.69	6 - 8 ft	7.75 ft	1801157731	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-6-8	SSHS-B3575-SUB-6-8	2/2/2021	854.85	855.40	0.55	-	6 - 8 ft	6.55-8.55 ft	180-116724-1	Not Excavated	< 0.0011 U	0.0034 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-6-8	SSHS-B3573-SUB-6-8	2/3/2021	855.66	855.66	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0044 J	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-6-8	SSHS-B3574-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0011 U	0.031	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-6-8	SSHS-B3576-SUB-6-8	2/3/2021	855.76	855.76	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-6-8	SSHS-B3578-SUB-6-8	2/3/2021	855.72	855.72	0.00	-	6 - 8 ft	6-8 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0036 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3572	020521 09:00 DUP-30	DUP-30	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0011 U	0.012 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-6-8	SSHS-B3572-SUB-6-8	2/4/2021	855.42	855.51	0.09	-	6 - 8 ft	6.09-8.09 ft	180-116864-1	Not Excavated	< 0.0011 U	< 0.0017 UJ	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-6-8	SSHS-B3580-SUB-6-8	2/5/2021	856.23	856.24	0.01	-	6 - 8 ft	6.01-8.01 ft	180-116914-1	Not Excavated	< 0.058 U	< 0.093 U	< 0.25 U	< 0.21 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-6-8	SSHS-B3581-SUB-6-8	2/5/2021	856.18	856.18	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.0011 U	0.018	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-6-8	SSHS-B3582-SUB-6-8	2/5/2021	855.93	855.93	0.00	-	6 - 8 ft	6-8 ft	180-116914-1	Not Excavated	< 0.064 U	< 0.1 U	< 0.27 U	< 0.23 U	< 0.12 U	< 0.13 U	< 0.47 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-6-8	SSHS-B3583-SUB-6-8	2/5/2021	855.33	855.44	0.11	-	6 - 8 ft	6.11-8.11 ft	180-116914-1	Not Excavated	< 0.0011 U	0.05	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	IRM5-S248	SSHS-IRM5-S248-6-8-20210211	SSHS-IRM5-S248-6-8	2/11/2021	-	855.42	-	847.69	6 - 8 ft	7.73 ft	1801171241	Not Excavated							
Football Field	IRM5-S290-BOT2	SSHS-IRM5-S290-BOT2-4-6-20210212	SSHS-IRM5-S290-BOT2-4-6	2/12/2021	-	855.87	-	849.52	6 - 8 ft	6.36 ft	1801171731	Not Excavated							
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)-20210224	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated							
Football Field	IRM5-S290A4	SSHS-IRM5-S290A4-20210227	SSHS-IRM5-S290A4	2/27/2021	-	855.91	-	849.23	6 - 8 ft	6.68 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT	SSHS-IRM5-S290A BOT-20210227	SSHS-IRM5-S290A BOT	2/27/2021	-	855.57	-	849.08	6 - 8 ft	6.49 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT1	SSHS-IRM5-S290A BOT1-20210227	SSHS-IRM5-S290A BOT1	2/27/2021	-	855.81	-	848.09	6 - 8 ft	7.72 ft	1801177071	Not Excavated							
Football Field	IRM5-S290ABOT2	SSHS-IRM5-S290A BOT2-20210227	SSHS-IRM5-S290A BOT2	2/27/2021	-	855.73	-	849.45	6 - 8 ft	6.28 ft	1801177071	Not Excavated							
Football Field	IRM5-S188 BOT	SSHS-IRM5-DUP15-20210301	SSHS-IRM5-DUP15	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated							
Football Field	IRM5-S188 BOT	SSHS-IRM5-S188 BOT-20210301	SSHS-IRM5-S188 BOT	3/1/2021	-	855.49	-	848.92	6 - 8 ft	6.58 ft	1801177071	Not Excavated							
Football Field	IRM4A-S075 BOT	SSHS-IRM4A-S75 BOT-20210301	SSHS-IRM4A-S75 BOT	3/1/2021	-	855.54	-	849.05	6 - 8 ft	6.49 ft	1801177071	Not Excavated							
Football Field	IRM5-PIPE 4 BOT 1	SSHS-IRM5-PIPE4 BOT1-20210302	SSHS-IRM5-PIPE4 BOT1	3/2/2021	-	855.83	-	848.38	6 - 8 ft	7.45 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 4 BOT 2	SSHS-IRM5-PIPE4 BOT2-20210302	SSHS-IRM5-PIPE4 BOT2	3/2/2021	-	855.82	-	848.84	6 - 8 ft	6.98 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 4S1	SSHS-IRM5-PIPE4S1-20210302	SSHS-IRM5-PIPE4S1	3/2/2021	-	855.82	-	848.97	6 - 8 ft	6.85 ft	1801177752	Not Excavated							
Football Field	IRM5-PIPE 4S2	SSHS-IRM5-PIPE4S2-20210302	SSHS-IRM5-PIPE4S2	3/2/2021	-	855.83	-	849.16	6 - 8 ft	6.67 ft	1801177752	Not Excavated							
Football Field	IRM5-PIPE 7 BOT O	SSHS-IRM5-PIPE 7 BOT O-20210309	SSHS-IRM5-PIPE 7 BOT O	3/9/2021	-	855.94	-	848.97	6 - 8 ft	6.98 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT M	SSHS-IRM5-PIPE 7 BOT M-20210309	SSHS-IRM5-PIPE 7 BOT M	3/9/2021	-	855.97	-	848.91	6 - 8 ft	7.06 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT N	SSHS-IRM5-PIPE 7 BOT N-20210309	SSHS-IRM5-PIPE 7 BOT N	3/9/2021	-	855.76	-	848.23	6 - 8 ft	7.53 ft	1801181261	Not Excavated							
Football Field	IRM5-PIPE 7 BOT I	SSHS-IRM5-PIPE 7 BOT I-20210309	SSHS-IRM5-PIPE 7 BOT I	3/9/2021	-	855.74	-	848.27	6 - 8 ft	7.47 ft	1801181261	Not Excavated							
Football Field	IRM5-GS VAULT A BOT	SSHS-IRM5-GS VAULT A BOT-20210310	SSHS-IRM5-GS VAULT A BOT	3/10/2021	-	855.58	-	848.18	6 - 8 ft	7.4 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - N	SSHS-IRM5-PIPE 7- GS VAULT A-N-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-N	3/10/2021	-	855.57	-	849.26	6 - 8 ft	6.31 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - E	SSHS-IRM5-PIPE 7- GS VAULT A-E-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-E	3/10/2021	-	855.59	-	849.21	6 - 8 ft	6.38 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - S	SSHS-IRM5-PIPE 7- GS VAULT A-S-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-S	3/10/2021	-	855.56	-	848.57	6 - 8 ft	6.99 ft	1801181881	Not Excavated							
Football Field	IRM5-GS VAULT A - W	SSHS-IRM5-PIPE 7- GS VAULT A-W-20210310	SSHS-IRM5-PIPE 7- GS VAULT A-W	3/10/2021	-	855.60	-	848.45	6 - 8 ft	7.15 ft	1801181881	Not Excavated							
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-DUP 20-20210311	SSHS-IRM5-DUP 20	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 5 BOT C	SSHS-IRM5-PIPE 5 BOT C-20210311	SSHS-IRM5-PIPE 5 BOT C	3/11/2021	-	855.79	-	849.75	6 - 8 ft	6.04 ft	1801183131	Not Excavated							
Football Field	IRM5-PIPE 5 BOT G	SSHS-IRM5-PIPE 5 BOT G-20210311	SSHS-IRM5-PIPE 5 BOT G	3/11/2021	-	855.54	-	848.91	6 - 8 ft	6.63 ft	1801183131	Not Excavated							
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-DUP3-20210315	SSHS-IRM5A-DUP3	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-DUP5-20210315	SSHS-IRM5A-DUP5	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP H BOT	SSHS-IRM5A-GSP H BOT-20210315	SSHS-IRM5A-GSP H BOT	3/15/2021	-	855.91	-	849.45	6 - 8 ft	6.46 ft	1801184352	Not Excavated							
Football Field	IRM5A-GSP A BOT	SSHS-IRM5A-GSP A BOT-20210315	SSHS-IRM5A-GSP A BOT	3/15/2021	-	856.07	-	849.21	6 - 8 ft	6.86 ft	1801184351	Not Excavated							
Football Field	IRM5A-S275 BOT	SSHS-IRM5A-S275 BOT-20210315	SSHS-IRM5A-S275 BOT	3/15/2021	-	855.84	-	848.81	6 - 8 ft	7.03	1801184352	Not Excavated							
Football Field	IRM5-PIPE 16	SSHS-IRM5-PIPE 16-20210316	SSHS-IRM5-PIPE 16	3/16/2021	-	855.83	-	848.58	6 - 8 ft	7.24	1801185091	Not Excavated							
Football Field	IRM5-S217	SSHS-IRM5-S217-20210317	SSHS-IRM5-S217	3/17/2021	-	855.38	-	849.01	6 - 8 ft	6.37 ft	1801185741	Not Excavated							
Football Field	IRM5-B080A BOT	SSHS-IRM5-B080A BOT-20210325	SSHS-IRM5-B080A BOT	3/25/2021	-	855.89	-	849.81	6 - 8 ft	6.08 ft	1801190471	Not Excavated							
Football Field	IRM5-S196	SSHS-IRM5-S196-20210326	SSHS-IRM5-S196	3/26/2021	-	855.60	-	848.90	6 - 8 ft	6.7 ft	1801191091	Not Excavated							
Football Field	IRM5-S197	SSHS-IRM5-S197-20210326	SSHS-IRM5-S197	3/26/2021	-	855.62	-	849.22	6 - 8 ft	6.4 ft	1801191091	Not Excavated							
Football Field	IRM5-B226	SSHS-IRM5-B226-20210326	SSHS-IRM5-B226	3/26/2021	-	855.35	-	848.49	6 - 8 ft	6.87 ft	1801191091	Not Excavated							
Football Field	IRM5-PIPE15 BTC	SSHS-IRM5-PIPE 15 BOT C-20210327	SSHS-IRM5-PIPE 15 BOT C	3/27/2021	-	855.84	-	848.67	6 - 8 ft	7.18 ft	1801191611	Not Excavated							
Football Field	ISMP-B002	SSHS-ISMP-B002-20210401	SSHS-ISMP-B002	4/1/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801194581	Not Excavated							
Football Field	IRM5-PIPE 32 S1A	SSHS-IRM5-PIPE 32 S1A-20210406	SSHS-IRM5-PIPE 32 S1A	4/6/2021	-	856.06	-	849.55	6 - 8 ft	6.51 ft	1801195651	Not Excavated							
Football Field	IRM5-PIPE 32 S2A	SSHS-IRM5-PIPE 32 S2A-20210406	SSHS-IRM5-PIPE 32 S2A	4/6/2021	-	855.85	-	849.40	6 - 8 ft	6.45 ft	1801195651	Not Excavated							
Football Field	IRM5-S706	SSHS-IRM5-S706-20210407	SSHS-IRM5-S706	4/7/2021	-	855.30	-	847.42	6 - 8 ft	7.88 ft	1801196311	Not Excavated							
Football Field	IRM5-B800	SSHS-IRM5-B800-20210407	SSHS-IRM5-B800	4/7/2021	-	855.64	-	848.10	6 - 8 ft	7.53 ft	1801196311	Not Excavated							
Football Field	IRM5-S803	SSHS-IRM5-S803-20210407	SSHS-IRM5-S803	4/7/2021	-	855.34	-	847.73	6 - 8 ft	7.61 ft	1801196311	Not Excavated							
Football Field	IRM5-B805	SSHS-IRM5-B805-20210407	SSHS-IRM5-B805	4/7/2021	-	855.62	-	847.86	6 - 8 ft	7.77 ft	1801196312	Not Excavated							
Football Field	IRM5-S802	SSHS-IRM5-S802-20210407	SSHS-IRM5-S802	4/7/2021	-	855.41	-	847.97	6 - 8 ft	7.44 ft	1801196311	Not Excavated							

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated							
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated							
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated							
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated							
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated							
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated							
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated							
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated							
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated							
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated							
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated							
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated							
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated							
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated							
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated							
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated							
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated							
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated							
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated							
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated							
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated							
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated							
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated							
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated							
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated							
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated							
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated							
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated							
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated							
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated							
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated							
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated							
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated							
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated							
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated							
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated							
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated							
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated							
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated							
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated							
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated							
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated							
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated							
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated							
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated							
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated							
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated						
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated						
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated						
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated						
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated						
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated						
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated						
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated						
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated						
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated						
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated						
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated						
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated						
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated						
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated						
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated						
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated						
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated						
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated						
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated						
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated						
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated						
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated						
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated						
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated						
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated						
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated						
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated						
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated						
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated						
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated						
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated						
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated						
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated						
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated						
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated						
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated						
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated						
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated						
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated						
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated						
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated						
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated						
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated						
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated						
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated						
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 UT
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 UT
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated								
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated								
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated								
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated								
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated								
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated								
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated								
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated								
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated								
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated								
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated								
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated								
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated								
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated								
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated								
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated								
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated								
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated								
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated								
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated								
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated								
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated								
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated								
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated								
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated								
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated								
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated								
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated								
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated								
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated								
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated								
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated								
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated								
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated								
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated								
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated								
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated								
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated								
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated								
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated								
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated								
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated								
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated								
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated								
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated								
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated								
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 UT	< 0.0032 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 UT	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 UT	< 0.0032 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated							
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated							
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated							
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated							
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated							
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated							
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated							
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated							
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated							
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated							
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated							
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated							
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated							
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated							
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated							
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated							
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated							
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated							
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated							
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated							
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated							
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated							
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated							
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated							
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated							
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated							
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated							
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated							
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated							
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated							
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated							
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated							
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated							
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated							
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated							
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated							
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated							
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated							
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated							
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated							
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated							
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated							
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated							
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated							
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated							
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated							
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated								
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated								
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated								
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated								
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated								
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated								
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated								
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated								
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated								
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated								
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated								
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated								
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated								
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated								
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated								
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated								
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated								
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated								
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated								
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated								
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated								
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated								
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated								
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated								
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated								
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated								
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated								
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated								
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated								
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated								
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated								
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated								
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated								
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated								
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated								
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated								
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated								
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated								
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated								
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated								
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated								
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated								
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated								
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated								
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated								
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated								
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated								
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated								
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated								
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated								
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	7.99 ft	7.99 ft	1801223391	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated						
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated						
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated						
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated						
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated						
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated						
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated						
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated						
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated						
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated						
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated						
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated						
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated						
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated						
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated						
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated						
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated						
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated						
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated						
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated						
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated						
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated						
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated						
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated						
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated						
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated						
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated						
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated						
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated						
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated						
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated						
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated						
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated						
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated						
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated						
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated						
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated						
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated						
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated						
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated						
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated						
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated						
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated						
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated						
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated						
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated						
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated						
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated						
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated						
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UT	< 0.0026 UT	< 0.0017 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UT	< 0.0026 UT	< 0.0017 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT	< 0.0018 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-S804	SSHS-IRM5-S804-20210407	SSHS-IRM5-S804	4/7/2021	-	855.51	-	848.72	6 - 8 ft	6.79 ft	1801196312	Not Excavated							
Football Field	IRM5-S807	SSHS-IRM5-S807-20210407	SSHS-IRM5-S807	4/7/2021	-	855.68	-	849.16	6 - 8 ft	6.52 ft	1801196312	Not Excavated							
Football Field	IRM5-S900	SSHS-IRM5-DUP 44-20210408	SSHS-IRM5-DUP 44	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated							
Football Field	IRM5-B900	SSHS-IRM5-B900-20210408	SSHS-IRM5-B900	4/8/2021	-	855.51	-	847.70	6 - 8 ft	7.81 ft	1801197251	Not Excavated							
Football Field	IRM5-S901	SSHS-IRM5-S901-20210408	SSHS-IRM5-S901	4/8/2021	-	855.69	-	848.88	6 - 8 ft	6.81 ft	1801197251	Not Excavated							
Football Field	IRM5-S900	SSHS-IRM5-S900-20210408	SSHS-IRM5-S900	4/8/2021	-	855.83	-	849.68	6 - 8 ft	6.15 ft	1801197251	Not Excavated							
Football Field	IRM5-S907	SSHS-IRM5-S907-20210408	SSHS-IRM5-S907	4/8/2021	-	855.43	-	849.19	6 - 8 ft	6.24 ft	1801197251	Not Excavated							
Football Field	ISMP-S103	SSHS-ISMP-S103-20210408	SSHS-ISMP-S103	4/8/2021	-	855.36	-	848.96	6 - 8 ft	6.4 ft	1801197252	Not Excavated							
Football Field	ISMP-B100	SSHS-ISMP-B100-20210408	SSHS-ISMP-B100	4/8/2021	-	855.40	-	847.95	6 - 8 ft	7.45 ft	1801197253	Not Excavated							
Football Field	ISMP-S138	SSHS-ISMP-S138-20210408	SSHS-ISMP-S138	4/8/2021	-	855.30	-	848.03	6 - 8 ft	7.27 ft	1801197253	Not Excavated							
Football Field	ISMP-S106	SSHS-ISMP-S106-20210408	SSHS-ISMP-S106	4/8/2021	-	855.33	-	848.43	6 - 8 ft	6.9 ft	1801197252	Not Excavated							
Football Field	ISMP-S111	SSHS-ISMP-S111-20210408	SSHS-ISMP-S111	4/8/2021	-	855.37	-	848.52	6 - 8 ft	6.84 ft	1801197252	Not Excavated							
Football Field	ISMP-B102	SSHS-ISMP-B102-20210408	SSHS-ISMP-B102	4/8/2021	-	855.53	-	848.23	6 - 8 ft	7.3 ft	1801197253	Not Excavated							
Football Field	ISMP-S126	SSHS-ISMP-S126-20210408	SSHS-ISMP-S126	4/8/2021	-	855.39	-	848.66	6 - 8 ft	6.73 ft	1801197253	Not Excavated							
Football Field	ISMP-S132	SSHS-ISMP-S132-20210408	SSHS-ISMP-S132	4/8/2021	-	855.51	-	848.77	6 - 8 ft	6.75 ft	1801197253	Not Excavated							
Football Field	ISMP-S136	SSHS-ISMP-S136-20210408	SSHS-ISMP-S136	4/8/2021	-	855.43	-	848.76	6 - 8 ft	6.67 ft	1801197253	Not Excavated							
Football Field	ISMP-S131	SSHS-ISMP-S131-20210408	SSHS-ISMP-S131	4/8/2021	-	855.38	-	848.62	6 - 8 ft	6.76 ft	1801197253	Not Excavated							
Football Field	ISMP-B105	SSHS-ISMP-B105-20210408	SSHS-ISMP-B105	4/8/2021	-	855.35	-	848.44	6 - 8 ft	6.91 ft	1801197253	Not Excavated							
Football Field	ISMP-S140	SSHS-ISMP-S140-20210408	SSHS-ISMP-S140	4/8/2021	-	855.52	-	848.12	6 - 8 ft	7.4 ft	1801197253	Not Excavated							
Football Field	IRM5-S610	SSHS-IRM5-S610-20210411	SSHS-IRM5-S610	4/11/2021	-	855.60	-	847.95	6 - 8 ft	7.65 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE 39 BOT 2	SSHS-IRM5-PIPE 39 BOT 2-20210411	SSHS-IRM5-PIPE 39 BOT 2	4/11/2021	-	855.43	-	848.86	6 - 8 ft	6.57 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 BOT1	SSHS-IRM5-PIPE 38 BOT 1-20210411	SSHS-IRM5-PIPE 38 BOT 1	4/11/2021	-	855.31	-	849.08	6 - 8 ft	6.23 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 BOT2	SSHS-IRM5-PIPE 38 BOT 2-20210411	SSHS-IRM5-PIPE 38 BOT 2	4/11/2021	-	855.54	-	848.68	6 - 8 ft	6.86 ft	1801198481	Not Excavated							
Football Field	IRM5-PIPE38 S2B	SSHS-IRM5-PIPE 38 S2B-20210411	SSHS-IRM5-PIPE 38 S2B	4/11/2021	-	855.54	-	849.41	6 - 8 ft	6.13 ft	1801198481	Not Excavated							
Football Field	IRM5-B231	SSHS-IRM5-B231-20210415	SSHS-IRM5-B231	4/15/2021	-	855.69	-	849.23	6 - 8 ft	6.46 ft	1801200642	Not Excavated							
Football Field	IRM5-B231A	SSHS-IRM5-B231A-20210415	SSHS-IRM5-B231A	4/15/2021	-	855.68	-	848.69	6 - 8 ft	6.98 ft	1801200642	Not Excavated							
Football Field	IRM5-B195	SSHS-IRM5-B195-20210415	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated							
Football Field	IRM5-B196	SSHS-IRM5-B196-20210415	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated							
Football Field	IRM5-B195A	SSHS-IRM5-B195A-20210415	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated							
Football Field	IRM5-B801 BOT	SSHS-IRM5-B801 BOT-20210417	SSHS-IRM5-B801 BOT	4/17/2021	-	855.45	-	847.82	6 - 8 ft	7.63 ft	1801201971	Not Excavated							
Football Field	IRM5-B801B	SSHS-IRM5-B801B-20210417	SSHS-IRM5-B801B	4/17/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated							
Football Field	IRM5-B801C	SSHS-IRM5-B801C-20210417	SSHS-IRM5-B801C	4/17/2021	-	855.47	-	848.53	6 - 8 ft	6.94 ft	1801201971	Not Excavated							
Football Field	IRM5-B801B	SSHS-IRM5-DUP 66-20210418	SSHS-IRM5-DUP 66	4/18/2021	-	855.39	-	848.28	6 - 8 ft	7.11 ft	1801201971	Not Excavated							
Football Field	IRM5-B078A5	SSHS-IRM5-B078 A5-20210421	SSHS-IRM5-B078 A5	4/21/2021	-	856.00	-	849.38	6 - 8 ft	6.62 ft	1801203601	Not Excavated							
Football Field	IRM5-B028	SSHS-IRM5-B028-20210421	SSHS-IRM5-B028	4/21/2021	-	855.98	-	848.93	6 - 8 ft	7.05 ft	1801203601	Not Excavated							
Football Field	IRM5-B027 A3	SSHS-IRM5-B027 A3-20210421	SSHS-IRM5-B027 A3	4/21/2021	-	855.96	-	848.92	6 - 8 ft	7.04 ft	1801203601	Not Excavated							
Football Field	IRM5-B028 A1	SSHS-IRM5-B028 A1-20210421	SSHS-IRM5-B028 A1	4/21/2021	-	855.79	-	848.24	6 - 8 ft	7.55 ft	1801203601	Not Excavated							
Football Field	IRM5-S272A2	SSHS-IRM5-S272A2-20210422	SSHS-IRM5-S272A2	4/22/2021	-	855.92	-	848.17	6 - 8 ft	7.75 ft	1801204573	Not Excavated							
Football Field	IRM5-P18 5N	SSHS-IRM5-DUP 87-20210426	SSHS-IRM5-DUP 87	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 5N	SSHS-IRM5-P18-5N-20210426	SSHS-IRM5-P18-5N	4/26/2021	-	856.15	-	848.86	6 - 8 ft	7.29 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 10S	SSHS-IRM5-CB28 10S-20210426	SSHS-IRM5-CB28 10S	4/26/2021	-	855.68	-	848.63	6 - 8 ft	7.05 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 3	SSHS-IRM5-P18 BOT 3-20210426	SSHS-IRM5-P18 BOT 3	4/26/2021	-	855.79	-	847.93	6 - 8 ft	7.86 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 11S	SSHS-IRM5-CB28 11S-20210426	SSHS-IRM5-CB28 11S	4/26/2021	-	855.82	-	849.49	6 - 8 ft	6.33 ft	1801206041	Not Excavated							
Football Field	IRM5-P18-3W	SSHS-IRM5-P18-3W-20210426	SSHS-IRM5-P18-3W	4/26/2021	-	855.79	-	849.62	6 - 8 ft	6.17 ft	1801206041	Not Excavated							
Football Field	IRM5-S655	SSHS-IRM5-S655-20210426	SSHS-IRM5-S655	4/26/2021	-	855.43	-	847.98	6 - 8 ft	7.45 ft	1801206042	Not Excavated							
Football Field	IRM5-B619	SSHS-IRM5-B619-20210426	SSHS-IRM5-B619	4/26/2021	-	855.58	-	847.66	6 - 8 ft	7.92 ft	1801206042	Not Excavated							
Football Field	IRM5-S652	SSHS-IRM5-S652-20210426	SSHS-IRM5-S652	4/26/2021	-	855.65	-	848.89	6 - 8 ft	6.75 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S1A	SSHS-IRM5-PIPE 34 S1A-20210426	SSHS-IRM5-PIPE 34 S1A	4/26/2021	-	855.71	-	849.53	6 - 8 ft	6.18 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 BOT 1	SSHS-IRM5-PIPE 34 BOT 1-20210426	SSHS-IRM5-PIPE 34 BOT 1	4/26/2021	-	855.72	-	847.89	6 - 8 ft	7.83 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S1B	SSHS-IRM5-PIPE 34 S1B-20210426	SSHS-IRM5-PIPE 34 S1B	4/26/2021	-	855.69	-	848.71	6 - 8 ft	6.98 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S2A	SSHS-IRM5-PIPE 34 S2A-20210426	SSHS-IRM5-PIPE 34 S2A	4/26/2021	-	855.77	-	849.32	6 - 8 ft	6.45 ft	1801206042	Not Excavated							
Football Field	IRM5-PIPE 34 S2B	SSHS-IRM5-PIPE 34 S2B-20210426	SSHS-IRM5-PIPE 34 S2B	4/26/2021	-	855.75	-	849.61	6 - 8 ft	6.14 ft	1801206042	Not Excavated							
Football Field	IRM5-ALPHA BOT 11	SSHS-IRM5-ALPHA BOT 11-20210506	SSHS-IRM5-ALPHA BOT 11	5/6/2021	-	855.50	-	847.79	6 - 8 ft	7.7 ft	1801212761	Not Excavated							
Football Field	IRM5-ALPHA S33	SSHS-IRM5-DUP 99-20210507	SSHS-IRM5-DUP 99	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S9	SSHS-IRM5-DUP 98-20210507	SSHS-IRM5-DUP 98	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated							
Football Field	IRM5-ALPHA S33	SSHS-IRM5-ALPHA S33-20210507	SSHS-IRM5-ALPHA S33	5/7/2021	-	855.46	-	847.64	6 - 8 ft	7.82 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S8	SSHS-IRM5-S234A S8-20210507	SSHS-IRM5-S234A S8	5/7/2021	-	855.69	-	849.27	6 - 8 ft	6.42 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S9	SSHS-IRM5-S234A S9-20210507	SSHS-IRM5-S234A S9	5/7/2021	-	855.69	-	847.78	6 - 8 ft	7.91 ft	1801213531	Not Excavated							
Football Field	IRM5-S234A S6	SSHS-IRM5-S234A S6-20210507	SSHS-IRM5-S234A S6	5/7/2021	-	855.81	-	848.08	6 - 8 ft	7.73 ft	1801213531	Not Excavated							
Football Field	IRM5-P18 VAULT S4	SSHS-IRM5-P18 VAULT S4-20210510	SSHS-IRM5-P18 VAULT S4	5/10/2021	-	855.83	-	848.08	6 - 8 ft	7.75 ft	1801213911	Not Excavated							
Football Field	IRM5-PIPE 51 S4	SSHS-IRM5-PIPE 51 S4-20210512	SSHS-IRM5-PIPE 51 S4	5/12/2021	-	855.21	-	848.55	6 - 8 ft	6.65 ft	1801215151	Not Excavated							
Football Field	IRM5-PIPE 50 S5	SSHS-IRM5-PIPE 50 S5-20210515	SSHS-IRM5-PIPE 50 S5	5/15/2021	-	855.87	-	848.85	6 - 8 ft	7.02 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 S7	SSHS-IRM5-PIPE 50 S7-20210515	SSHS-IRM5-PIPE 50 S7	5/15/2021	-	855.78	-	848.04	6 - 8 ft	7.74 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 S6	SSHS-IRM5-PIPE 50 S6-20210515	SSHS-IRM5-PIPE 50 S6	5/15/2021	-	855.79	-	849.42	6 - 8 ft	6.37 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 51 S14	SSHS-IRM5-PIPE 51 S14-20210519	SSHS-IRM5-PIPE 51 S14	5/19/2021	-	855.12	-	847.83	6 - 8 ft	7.29 ft	1801218701	Not Excavated							
Football Field	IRM5-TANK C BOT	SSHS-ISMP-TANK C BOT-20210524	SSHS-ISMP-TANK C BOT	5/24/2021	-	855.70	-	848.40	6 - 8 ft	7.3 ft	1801221161	Not Excavated							
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2-20210527	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-S509	SSHS-ISMP-S509-20210527	SSHS-ISMP-S509	5/27/2021	-	855.63	-	848.99	6 - 8 ft	6.64 ft	1801223381	Not Excavated							
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2-20210527	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2-20210527	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4-20210602	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5-20210602	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9-20210602	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6-20210602	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated								
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated								
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated								
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 UT	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 UT	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 UT	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated								
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated								
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated								
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0066 U	< 0.0024 U	< 0.0050 U	< 0.0039 U	< 0.0042 U	< 0.0038 U	< 0.0067 U	< 0.0034 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0060 U	< 0.0022 U	< 0.0046 U	< 0.0036 U	< 0.0039 U	< 0.0035 U	< 0.0061 U	< 0.0031 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0071 U	< 0.0026 U	< 0.0055 U	< 0.0042 U	< 0.0046 U	< 0.0041 U	< 0.0073 U	< 0.0037 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0060 U	< 0.0022 U	< 0.0047 U	< 0.0036 U	< 0.0039 U	< 0.0035 U	< 0.0062 U	< 0.0031 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0064 U	< 0.0023 U	< 0.0049 U	< 0.0038 U	< 0.0042 U	< 0.0038 U	< 0.0066 U	< 0.0033 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0066 U	< 0.0024 U	< 0.0051 U	< 0.0039 U	< 0.0042 U	< 0.0038 U	< 0.0067 U	< 0.0034 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0062 U	< 0.0022 U	< 0.0048 U	< 0.0037 U	< 0.0040 U	< 0.0036 U	< 0.0064 U	< 0.0032 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0064 U	< 0.0023 U	< 0.0049 U	< 0.0038 U	< 0.0041 U	< 0.0037 U	< 0.0065 U	< 0.0033 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated							
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated							
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated							
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated							
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated							
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated							
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated							
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated							
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated							
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated							
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0042 U	< 0.0049 U	< 0.0027 U	< 0.0033 U	< 0.0040 U	< 0.0054 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0020 U	< 0.0038 U	< 0.0045 U	< 0.0025 U	< 0.0030 U	< 0.0037 U	< 0.0050 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0024 U	< 0.0045 U	< 0.0053 U	< 0.0029 U	< 0.0036 U	< 0.0043 U	< 0.0059 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0020 U	< 0.0038 U	< 0.0045 U	< 0.0025 U	< 0.0031 U	< 0.0037 U	< 0.0050 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0021 U	< 0.0041 U	< 0.0048 U	< 0.0027 U	< 0.0033 U	< 0.0039 U	< 0.0053 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0042 U	< 0.0049 U	< 0.0027 U	< 0.0033 U	< 0.0040 U	< 0.0054 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0047 U	< 0.0026 U	< 0.0032 U	< 0.0038 U	< 0.0051 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0021 U	< 0.0041 U	< 0.0048 U	< 0.0026 U	< 0.0032 U	< 0.0039 U	< 0.0053 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 UT	< 0.0032 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated								
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated								
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated								
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated								
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated								
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated								
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0076 U	< 0.0023 U	< 0.0042 U	< 0.0028 U	< 0.0052 U	< 0.0025 U	< 0.0027 U	< 0.0024 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0069 U	< 0.0021 U	< 0.0038 U	< 0.0026 U	< 0.0047 U	< 0.0023 U	< 0.0025 U	< 0.0022 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0082 U	< 0.0025 U	< 0.0045 U	< 0.0031 U	< 0.0056 U	< 0.0027 U	< 0.0029 U	< 0.0026 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0070 U	< 0.0021 U	< 0.0039 U	< 0.0026 U	< 0.0048 U	< 0.0023 U	< 0.0025 U	< 0.0022 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0074 U	< 0.0023 U	< 0.0041 U	< 0.0028 U	< 0.0051 U	< 0.0025 U	< 0.0026 U	< 0.0024 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0076 U	< 0.0023 U	< 0.0042 U	< 0.0028 U	< 0.0052 U	< 0.0025 U	< 0.0027 U	< 0.0024 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0072 U	< 0.0022 U	< 0.0040 U	< 0.0027 U	< 0.0049 U	< 0.0024 U	< 0.0025 U	< 0.0023 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0074 U	< 0.0022 U	< 0.0041 U	< 0.0027 U	< 0.0050 U	< 0.0025 U	< 0.0026 U	< 0.0024 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated								
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated								
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated								
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated								
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated								
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated								
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0038 U	< 0.0069 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0037 U	< 0.0038 U	< 0.0031 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0035 U	< 0.0063 U	< 0.0023 U	< 0.0027 U	< 0.0020 U	< 0.0034 U	< 0.0035 U	< 0.0028 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0041 U	< 0.0074 U	< 0.0027 U	< 0.0032 U	< 0.0024 U	< 0.0040 U	< 0.0041 U	< 0.0034 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0035 U	< 0.0063 U	< 0.0023 U	< 0.0027 U	< 0.0021 U	< 0.0034 U	< 0.0035 U	< 0.0029 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0037 U	< 0.0067 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0036 U	< 0.0037 U	< 0.0030 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0038 U	< 0.0069 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0037 U	< 0.0038 U	< 0.0031 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0036 U	< 0.0065 U	< 0.0024 U	< 0.0028 U	< 0.0021 U	< 0.0035 U	< 0.0036 U	< 0.0029 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0037 U	< 0.0067 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0036 U	< 0.0037 U	< 0.0030 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated								
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated								
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated								
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated								
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated								
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated								
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated								
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated								
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated								
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated								
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated								
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0026 U	< 0.0044 U	< 0.012 U	< 0.0041 U	< 0.0043 U	< 0.0031 U	< 0.0025 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0031 U	< 0.0024 U	< 0.0040 U	< 0.011 U	< 0.0037 U	< 0.0039 U	< 0.0028 U	< 0.0023 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0036 U	< 0.0029 U	< 0.0047 U	< 0.013 U	< 0.0044 U	< 0.0046 U	< 0.0033 U	< 0.0027 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0031 U	< 0.0024 U	< 0.0040 U	< 0.011 U	< 0.0037 U	< 0.0039 U	< 0.0028 U	< 0.0023 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0033 U	< 0.0026 U	< 0.0043 U	< 0.012 U	< 0.0040 U	< 0.0042 U	< 0.0030 U	< 0.0024 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0026 U	< 0.0044 U	< 0.012 U	< 0.0041 U	< 0.0043 U	< 0.0031 U	< 0.0025 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0032 U	< 0.0025 U	< 0.0041 U	< 0.012 U	< 0.0038 U	< 0.0040 U	< 0.0029 U	< 0.0023 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0033 U	< 0.0026 U	< 0.0042 U	< 0.012 U	< 0.0039 U	< 0.0041 U	< 0.0030 U	< 0.0024 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0026 UT	< 0.0017 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated							
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated							
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated							
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated							
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated							
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated							
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated							
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated							
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated							
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated							
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0026 U	< 0.0034 U	< 0.0024 U	< 0.0046 U	< 0.0043 U	< 0.0028 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0023 U	< 0.0031 U	< 0.0022 U	< 0.0042 U	< 0.0039 U	< 0.0026 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0027 U	< 0.0028 U	< 0.0037 U	< 0.0026 U	< 0.0050 U	< 0.0046 U	< 0.0030 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0024 U	< 0.0031 U	< 0.0022 U	< 0.0043 U	< 0.0039 U	< 0.0026 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0025 U	< 0.0033 U	< 0.0024 U	< 0.0045 U	< 0.0042 U	< 0.0028 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0026 U	< 0.0034 U	< 0.0024 U	< 0.0046 U	< 0.0043 U	< 0.0028 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0024 U	< 0.0024 U	< 0.0032 U	< 0.0023 U	< 0.0044 U	< 0.0040 U	< 0.0027 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0025 U	< 0.0025 U	< 0.0033 U	< 0.0024 U	< 0.0045 U	< 0.0041 U	< 0.0027 U

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7-20210602	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16-20210602	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31-20210603	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-S520	SSHS-ISMP-S520-20210604	SSHS-ISMP-S520	6/4/2021	-	855.56	-	847.91	6 - 8 ft	7.65 ft	1801227322	Not Excavated							
Football Field	IRM5-P18 5SA BOT 2	SSHS-IRM5-P18 5SA BOT 2-20210604	SSHS-IRM5-P18 5SA BOT 2	6/4/2021	-	856.05	-	849.85	6 - 8 ft	6.19 ft	1801227321	Not Excavated							
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210605	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210605	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210605	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 S3	SSHS-IRM5-PIPE 52 S3-20210605	SSHS-IRM5-PIPE 52 S3	6/5/2021	-	856.04	-	849.94	6 - 8 ft	6.1 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46-20210607	SSHS-ISMP-B527 S46	6/7/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228231	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53-20210607	SSHS-ISMP-B527 S53	6/7/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228231	Not Excavated	< 0.0011 U	0.0046 J	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54-20210607	SSHS-ISMP-B527 S54	6/7/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228231	Not Excavated	< 0.0011 U	0.0041 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-S525	SSHS-ISMP-S525-20210609	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	IRM5-PIPE 54	SSHS-IRM5-PIPE 54-20210610	SSHS-IRM5-PIPE 54	6/10/2021	-	855.58	-	849.33	6 - 8 ft	6.25 ft	1801230391	Not Excavated							
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75-20210611	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	IRM5-FIS-S3	SSHS-IRM5-FIS S3-20210614	SSHS-IRM5-FIS S3	6/14/2021	-	854.28	-	848.04	6 - 8 ft	6.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S9	SSHS-IRM5-FIS S9-20210614	SSHS-IRM5-FIS S9	6/14/2021	-	854.57	-	848.14	6 - 8 ft	6.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S15	SSHS-IRM5-FIS S15-20210614	SSHS-IRM5-FIS S15	6/14/2021	-	855.24	-	848.51	6 - 8 ft	6.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-DUP 124-20210615	SSHS-IRM5-DUP 124	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A BOT 4	SSHS-IRM5-P18 S5A BOT 4-20210615	SSHS-IRM5-P18 S5A BOT 4	6/15/2021	-	855.98	-	849.35	6 - 8 ft	6.64 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S21	SSHS-IRM5-P18 S5A S21-20210615	SSHS-IRM5-P18 S5A S21	6/15/2021	-	856.08	-	848.75	6 - 8 ft	7.33 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S22	SSHS-IRM5-P18 S5A S22-20210615	SSHS-IRM5-P18 S5A S22	6/15/2021	-	856.17	-	849.75	6 - 8 ft	6.42 ft	1801232172	Not Excavated							
Football Field	IRM5-P18 S5A S23	SSHS-IRM5-P18 S5A S23-20210615	SSHS-IRM5-P18 S5A S23	6/15/2021	-	856.01	-	849.08	6 - 8 ft	6.93 ft	1801232172	Not Excavated							
Football Field	IRM5-FIS BOT 16	SSHS-IRM5-FIS BOT 16-20210616	SSHS-IRM5-FIS BOT 16	6/16/2021	-	854.66	-	846.79	6 - 8 ft	7.87 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS-DUP 127-20210616	SSHS-IRM5-FIS-DUP 127	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S139	SSHS-IRM5-FIS 139-20210616	SSHS-IRM5-FIS 139	6/16/2021	-	854.84	-	847.77	6 - 8 ft	7.07 ft	1801232821	Not Excavated							
Football Field	IRM5-FIS-S141	SSHS-IRM5-FIS 141-20210616	SSHS-IRM5-FIS 141	6/16/2021	-	854.86	-	848.76	6 - 8 ft	6.09 ft	1801232821	Not Excavated							
Football Field	IRM5-FIS-S145	SSHS-IRM5-FIS 145-20210616	SSHS-IRM5-FIS 145	6/16/2021	-	854.90	-	847.13	6 - 8 ft	7.77 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S149	SSHS-IRM5-FIS 149-20210616	SSHS-IRM5-FIS 149	6/16/2021	-	854.91	-	847.05	6 - 8 ft	7.87 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 10	SSHS-IRM5-FIS BOT 10-20210616	SSHS-IRM5-FIS BOT 10	6/16/2021	-	--	-	846.74	6 - 8 ft	6 - 8 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS-S192	SSHS-IRM5-FIS S192-20210617	SSHS-IRM5-FIS S192	6/17/2021	-	854.51	-	848.18	6 - 8 ft	6.33	1801233543	Not Excavated							
Football Field	IRM5-FIS-S200	SSHS-IRM5-FIS S200-20210617	SSHS-IRM5-FIS S200	6/17/2021	-	855.53	-	848.67	6 - 8 ft	6.86 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 20	SSHS-IRM5-FIS BOT 20-20210617	SSHS-IRM5-FIS BOT 20	6/17/2021	-	854.60	-	847.17	6 - 8 ft	7.44 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 21	SSHS-IRM5-FIS BOT 21-20210617	SSHS-IRM5-FIS BOT 21	6/17/2021	-	854.63	-	848.01	6 - 8 ft	6.61 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS BOT 22	SSHS-IRM5-FIS BOT 22-20210617	SSHS-IRM5-FIS BOT 22	6/17/2021	-	855.54	-	847.77	6 - 8 ft	7.76 ft	1801233543	Not Excavated							
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS S214-20210618	SSHS-IRM5-FIS S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S214	SSHS-IRM5-FIS-S214-20210618	SSHS-IRM5-FIS-S214	6/18/2021	-	853.49	-	846.51	6 - 8 ft	6.99 ft	1801234391	Not Excavated							
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95-20210625	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97-20210625	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 0.0010 U	0.0051 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98-20210625	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-FIS-S227A	SSHS-IRM5-FIS S227A-20210628	SSHS-IRM5-FIS S227A	6/28/2021	-	854.74	-	847.57	6 - 8 ft	7.17 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S228	SSHS-IRM5-FIS S228-20210628	SSHS-IRM5-FIS S228	6/28/2021	-	854.80	-	848.04	6 - 8 ft	6.76 ft	1801237731	Not Excavated							
Football Field	IRM5-FIS-S229	SSHS-IRM5-FIS S229-20210628	SSHS-IRM5-FIS S229	6/28/2021	-	854.81	-	847.76	6 - 8 ft	7.04 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S233	SSHS-IRM5-FIS S233-20210628	SSHS-IRM5-FIS S233	6/28/2021	-	854.20	-	846.91	6 - 8 ft	7.29	1801237732	Not Excavated							
Football Field	IRM5-FIS-S237	SSHS-IRM5-FIS S237-20210628	SSHS-IRM5-FIS S237	6/28/2021	-	--	-	846.97	6 - 8 ft	6 - 8 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S238	SSHS-IRM5-FIS S238-20210628	SSHS-IRM5-FIS S238	6/28/2021	-	854.60	-	846.82	6 - 8 ft	7.78	1801237732	Not Excavated							
Football Field	IRM5-FIS-S239	SSHS-IRM5-FIS S239-20210628	SSHS-IRM5-FIS S239	6/28/2021	-	854.58	-	846.67	6 - 8 ft	7.91 ft	1801237732	Not Excavated							
Football Field	IRM5-FIS-S241	SSHS-IRM5-FIS S241-20210720	SSHS-IRM5-FIS S241	7/20/2021	-	855.58	-	848.67	6 - 8 ft	6.91 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S242	SSHS-IRM5-FIS S242-20210720	SSHS-IRM5-FIS S242	7/20/2021	-	855.55	-	848.33	6 - 8 ft	7.22 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S243	SSHS-IRM5-FIS S243-20210720	SSHS-IRM5-FIS S243	7/20/2021	-	854.70	-	848.22	6 - 8 ft	6.48 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S244	SSHS-IRM5-FIS S244-20210720	SSHS-IRM5-FIS S244	7/20/2021	-	854.54	-	847.95	6 - 8 ft	6.59 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S246	SSHS-IRM5-FIS S246-20210720	SSHS-IRM5-FIS S246	7/20/2021	-	854.73	-	847.05	6 - 8 ft	7.68 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S260	SSHS-IRM5-FIS S260-20210720	SSHS-IRM5-FIS S260	7/20/2021	-	854.77	-	847.28	6 - 8 ft	7.49 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S326	SSHS-IRM5-FIS S326-20210821	SSHS-IRM5-FIS S326	8/21/2021	-	854.60	-	847.33	6 - 8 ft	7.26	1801261003	Not Excavated							
Football Field	IRM5-FIS-S303	SSHS-IRM5-FIS S303-20210821	SSHS-IRM5-FIS S303	8/21/2021	-	855.08	-	847.94	6 - 8 ft	7.14 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S312	SSHS-IRM5-FIS S312-20210821	SSHS-IRM5-FIS S312	8/21/2021	-	855.05	-	847.66	6 - 8 ft	7.4 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S306	SSHS-IRM5-FIS S306-20210821	SSHS-IRM5-FIS S306	8/21/2021	-	855.14	-	847.62	6 - 8 ft	7.52 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1-20210828	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1-20210828	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5-20210828	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13-20210829	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14-20210829	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17-20210829	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22-20210829	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27-20210829	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13-20210829	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13V-20210830	SSHS-ISMP-DUP 13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0070 U	< 0.0061 U	< 0.0030 U	< 0.0034 U	< 0.012 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14V-20210830	SSHS-ISMP-DUP 14V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0064 U	< 0.0055 U	< 0.0027 U	< 0.0031 U	< 0.011 U
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1V-20210830	SSHS-ISMP-CB-7 S1V	8/30/2021	-	855.92	-	848.55	6 - 8 ft	7.37 ft	1801264191	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0075 U	< 0.0065 U	< 0.0032 U	< 0.0037 U	< 0.013 U
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22V-20210830	SSHS-ISMP-CB-7 S22V	8/30/2021	-	856.17	-	848.77	6 - 8 ft	7.4 ft	1801264191	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0064 U	< 0.0056 U	< 0.0028 U	< 0.0031 U	< 0.011 U
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13V-20210830	SSHS-ISMP-CB-7 S13V	8/30/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264191	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0068 U	< 0.0059 U	< 0.0029 U	< 0.0033 U	< 0.012 U
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27V-20210830	SSHS-ISMP-CB-7 S27V	8/30/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0070 U	< 0.0061 U	< 0.0030 U	< 0.0034 U	< 0.012 U
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1V-20210830	SSHS-ISMP-CB-7 BOT 1V	8/30/2021	-	855.92	-	848.24	6 - 8 ft	7.68 ft	1801264191	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0066 U	< 0.0057 U	< 0.0028 U	< 0.0032 U	< 0.011 U
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5V-20210830	SSHS-ISMP-CB-7 S5V	8/30/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801264191	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0068 U	< 0.0059 U	< 0.0029 U	< 0.0033 U	< 0.012 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0059 U	< 0.0021 U	< 0.0045 U	< 0.0035 U	< 0.0038 U	< 0.0034 U	< 0.0060 U	< 0.0031 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	0.052	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0080 U	< 0.0029 U	< 0.0062 U	< 0.0048 U	< 0.0052 U	< 0.0047 U	< 0.0082 U	< 0.0042 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.17 U	< 0.063 U	< 0.13 U	< 0.1 U	< 0.11 U	< 0.1 U	< 0.18 U	< 0.091 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0040 UT	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0043 UT	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.0032 U	< 0.0012 U	< 0.0025 U	< 0.0019 U	< 0.0021 U	< 0.0019 UT	< 0.0033 U	< 0.0017 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0045 UT	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 UT	< 0.0023 UT
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0026 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 UT	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0020 U	< 0.0037 U	< 0.0044 U	< 0.0024 U	< 0.0030 U	< 0.0036 U	< 0.0049 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00		6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.0021 U	< 0.004 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0039 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated							
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated							
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0027 U	< 0.0051 U	< 0.0060 U	< 0.0033 U	< 0.0041 U	< 0.0049 U	< 0.0066 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.058 U	< 0.11 U	< 0.13 U	< 0.072 U	< 0.089 U	< 0.11 U	< 0.15 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.0011 U	< 0.0020 U	< 0.0024 UT	< 0.0013 U	< 0.0016 U	< 0.0020 U	< 0.0026 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0019 U	< 0.0023 UT	< 0.0027 UT	< 0.0037 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0014 U	< 0.0027 UT	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UT
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0030 U	< 0.0040 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0024 U	< 0.0032 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated							
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated							
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated							
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated							
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0068 U	< 0.0021 U	< 0.0038 U	< 0.0025 U	< 0.0046 U	< 0.0023 U	< 0.0024 U	< 0.0022 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.0023 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0093 U	< 0.0028 U	< 0.0051 U	< 0.0034 U	< 0.0063 U	< 0.0031 U	< 0.0033 U	< 0.0030 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.2 U	< 0.061 U	< 0.11 U	< 0.075 U	< 0.14 U	< 0.067 U	< 0.072 U	< 0.065 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.0037 U	< 0.0011 U	< 0.0020 U	< 0.0014 U	< 0.0025 U	< 0.0012 U	< 0.0013 U	< 0.0012 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 UT
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.00099 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 UT	< 0.0016 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0062 U	< 0.0023 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0034 U	< 0.0028 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.0029 U	< 0.034 U	< 0.0036 U	< 0.0037 U	< 0.003 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0046 U	< 0.0084 U	< 0.0031 U	< 0.0036 U	< 0.0027 U	< 0.0045 U	< 0.0046 U	< 0.0038 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.1 U	< 0.18 U	< 0.068 U	< 0.078 U	< 0.06 U	< 0.1 U	< 0.1 U	< 0.083 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.0019 U	< 0.0033 U	< 0.0012 U	< 0.0014 U	< 0.0011 U	< 0.0018 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0026 UT	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0029 U	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 UT	< 0.0024 UT	< 0.0025 UT	< 0.0020 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 UT	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated								

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0030 U	< 0.0024 U	< 0.0039 U	< 0.011 U	< 0.0036 U	< 0.0038 U	< 0.0028 U	< 0.0022 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0039 U	< 0.034 U	< 0.003 U	< 0.0024 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated								
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated								
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated								
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0041 U	< 0.0032 U	< 0.0053 U	< 0.015 U	< 0.0049 U	< 0.0052 U	< 0.0038 U	< 0.0030 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.09 U	< 0.07 U	< 0.12 U	< 0.33 U	< 0.11 U	< 0.11 U	< 0.082 U	< 0.066 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0020 U	< 0.0016 UT	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 UT	< 0.0019 UT	< 0.0015 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0022 U	< 0.0017 UT	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 UT	< 0.0020 UT	< 0.0016 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0024 U	< 0.0019 UT	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 UT	< 0.0022 UT	< 0.0018 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0060 U	< 0.0020 UT	< 0.0021 U	< 0.0015 U	< 0.0012 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 UT	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 UT	< 0.0029 UT	< 0.0021 UT	< 0.0017 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0096 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated								
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 UT	< 0.0020 UT	< 0.0016 UT
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated								
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated								
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated								
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated								
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated								
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated								
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated								
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated								
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated								
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated								
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated								
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated								
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated								
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated								
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated								
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated								
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated								
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0023 U	< 0.0030 U	< 0.0022 U	< 0.0041 U	< 0.0038 U	< 0.0025 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.0024 U	< 0.034 U	< 0.0033 U	< 0.0023 U	< 0.034 U	< 0.0041 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated							
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated							
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0031 U	< 0.0031 U	< 0.0041 U	< 0.0030 U	< 0.0056 U	< 0.0052 U	< 0.0034 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.067 U	< 0.068 U	< 0.091 U	< 0.065 U	< 0.12 U	< 0.11 U	< 0.075 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.0012 U	< 0.0012 U	< 0.0016 U	< 0.0012 U	< 0.0023 U	< 0.0021 U	< 0.0014 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0017 U	< 0.0017 UT	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 UT
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated							
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.94	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated							
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated							
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated							
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17V-20210830	SSHS-ISMP-CB-7 S17V	8/30/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264191	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0063 U	< 0.0054 U	< 0.0027 U	< 0.0030 U	< 0.011 U
Football Field	IRM5-FIS-S337	SSHS-IRM5-FIS S337-20210916	SSHS-IRM5-FIS S337	9/16/2021	-	855.17	-	847.99	6 - 8 ft	7.18 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-6-8	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.012 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-6-8	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	IRM5-FIS-S365	SSHS-IRM5-FIS-S365-20211008	SSHS-IRM5-FIS-S365	10/8/2021	-	855.40	-	848.12	6 - 8 ft	7.28 ft	1801282871	Not Excavated							
Football Field	IRM5-FIS-S361	SSHS-IRM5-FIS-S361-20211009	SSHS-IRM5-FIS-S361	10/9/2021	-	855.21	-	847.99	6 - 8 ft	7.23 ft	1801283151	Not Excavated							
Football Field	IRM5-FIS BOT 68	SSHS-IRM5-FIS-BOT68-20211013	SSHS-IRM5-FIS-BOT68	10/13/2021	-	855.43	-	849.12	6 - 8 ft	6.31 ft	1801284441	Not Excavated							
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002-20211028	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 0.0020 U	< 0.0032 U	< 0.0085 U	< 0.0074 U	< 0.0037 U	< 0.0041 U	< 0.015 U
Football Field	IRM5-B400	SSHS-IRM5-B400-20211229	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 0.044 U	0.23	< 0.19 U	< 0.16 U	< 0.08 U	< 0.091 U	< 0.32 U
Football Field	IRM5-S405	SSHS-IRM5-S405-20211229	SSHS-IRM5-S405	12/29/2021	-	855.45	-	849.35	6 - 8 ft	6.1 ft	1801318161	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	IRM5-S417	SSHS-IRM5-S417-20220106	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 0.0010 U	0.0078	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	IRM5-S418	SSHS-IRM5-S418-20220106	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 0.0011 U	0.043	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	IRM5-S423	SSHS-IRM5-S423-20220106	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 0.0012 U	0.085	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-S673	SSHS-ISMP-S673-20220228	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 0.00098 U	0.027	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-B675	SSHS-ISMP-BOT675-20220228	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 0.0011 U	0.0074	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	ISMP-S669	SSHS-ISMP-S669-20220228	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 0.00081 U	0.015 T	< 0.0034 U	< 0.0029 U	< 0.0015 U	< 0.0016 U	< 0.0059 U
Football Field	ISMP-S690	SSHS-ISMP-S690-20220228	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 0.0011 U	0.0066 T	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	ISMP-S697	SSHS-ISMP-S697-20220301	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 0.0011 U	0.039	< 0.0048 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0083 U
Football Field	IRM5-S424	SSHS-IRM5-S424-20220301	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	IRM5-B411	SSHS-IRM5-B411-20220301	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	IRM5-S425	SSHS-IRM5-S425-20220302	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 0.0012 U	0.015	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	IRM5-S426	SSHS-IRM5-S426-20220302	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 0.0012 U	0.075	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Football Field	IRM5-S435	SSHS-IRM5-S435-20220302	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	IRM5-S429	SSHS-IRM5-S429-20220302	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 0.0011 U	0.0021 J	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	IRM5-S431	SSHS-IRM5-S431-20220302	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 0.0012 U	0.0032 J	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	IRM5-S433	SSHS-IRM5-S433-20220302	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 0.0013 U	0.0023 J	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220305	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated							
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1-20220307	SSHS-ISMP-PIPE3-BOT1	3/7/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 0.0011 UT	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-S2000	SSHS-ISMP-S2000-20220308	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 0.0011 U	0.0057	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-S2001	SSHS-ISMP-S2001-20220308	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-S2002	SSHS-ISMP-S2002-20220308	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-S2004	SSHS-ISMP-S2004-20220308	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	ISMP-S2007	SSHS-ISMP-S2007-20220309	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-S2008	SSHS-ISMP-S2008-20220309	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 0.00099 U	0.0020 J	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-S2009	SSHS-ISMP-S2009-20220309	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-S2010	SSHS-ISMP-S2010-20220309	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-S2012	SSHS-ISMP-S2012-20220309	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-B1008	SSHS-ISMP-B1008-20220309	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 0.0010 U	0.034	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3-20220311	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 0.0012 U	0.0023 J	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	ISMP-S2016	SSHS-ISMP-S2016-20220314	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1-20220316	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 0.00015 U	0.0017	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00055 U
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81-20220322	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15-20220322	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Football Field	SSHS-B232	072815 05:00 SSHS-B232-SUB-8-10	SSHS-B232-SUB-8-10	7/27/2015	856.44	856.44	0.00	-	8 - 10 ft	8-10 ft	180-46300-1	Not Excavated							
Football Field	SSHS-B227A	072915 09:15 SSHS-B227A-SUB-8-10	SSHS-B227A-SUB-8-10	7/28/2015	856.71	856.71	0.00	-	8 - 10 ft	8-10 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B233	072915 09:15 SSHS-B233-SUB-8-10	SSHS-B233-SUB-8-10	7/28/2015	856.93	856.94	0.01	-	8 - 10 ft	8.01-10.01 ft	180-46310-1	Not Excavated							
Football Field	SSHS-B319	030316 09:45 SSHS-B319-SUB-8-10	SSHS-B319-SUB-8-10	3/2/2016	857.02	857.02	0.00	-	8 - 10 ft	8-10 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B322	030316 09:45 SSHS-B322-SUB-8-10	SSHS-B322-SUB-8-10	3/2/2016	857.31	857.32	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52664-1	Not Excavated							
Football Field	SSHS-B335	030416 08:45 SSHS-B335-SUB-8-10	SSHS-B335-SUB-8-10	3/3/2016	856.16	856.49	0.33	-	8 - 10 ft	8.33-10.33 ft	180-52706-1	Not Excavated							
Football Field	SSHS-B336	030416 08:45 SSHS-B336-SUB-8-10	SSHS-B336-SUB-8-10	3/3/2016	856.00	856.01	0.01	-	8 - 10 ft	8.01-10.01 ft	180-52706-1	Not Excavated							
Football Field	SSHS-B337	031016 09:45 SSHS-B337-SUB-8-10	SSHS-B337-SUB-8-10	3/9/2016	856.65	856.65	0.00	-	8 - 10 ft	8-10 ft	180-52876-1	Not Excavated							
Football Field	SSHS-B451	092916 09:00 SSHS-B451-SUB-8-10	SSHS-B451-SUB-8-10	9/27/2016	854.61	855.67	1.06	-	8 - 10 ft	9.06-11.06 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 DUP2103	DUP2103	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B452	092916 09:00 SSHS-B452-SUB-8-10	SSHS-B452-SUB-8-10	9/27/2016	854.99	855.46	0.47	-	8 - 10 ft	8.47-10.47 ft	180-59163-1	Not Excavated							
Football Field	SSHS-B629	021017 09:20 SSHS-B629-SUB-8-10	SSHS-B629-SUB-8-10	2/9/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-63367-1	Not Excavated							
Football Field	SSHS-B622	021817 08:50 SSHS-B622-SUB-8-10	SSHS-B622-SUB-8-10	2/16/2017	856.13	856.14	0.01	-	8 - 10 ft	8.01-10.01 ft	180-63593-2	Not Excavated							
Football Field	SSHS-B629A	071117 08:30 SSHS-B629A-SUB-8-10	SSHS-B629A-SUB-8-10	7/10/2017	855.95	855.95	0.00	-	8 - 10 ft	8-10 ft	180-68038-1	Not Excavated							
Football Field	SSHS-B2230	072418 08:50 SSHS-B2230-SUB-8-10	SSHS-B2230-SUB-8-10	7/23/2018	856.03	856.03	0.00	-	8 - 10 ft	8-10 ft	180-80091-4	Not Excavated							
Football Field	SSHS-B2231	072418 08:50 SSHS-B2231-SUB-8-10	SSHS-B2231-SUB-8-10	7/23/2018	856.14	856.13	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80091-2	Not Excavated							
Football Field	SSHS-B2234	072418 08:50 SSHS-B2234-SUB-8-10	SSHS-B2234-SUB-8-10	7/23/2018	855.41	855.54	0.13	-	8 - 10 ft	8.13-10.13 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2235	072418 08:50 PS-FD-3	PS-FD-3	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2235	072418 08:50 SSHS-B2235-SUB-8-10	SSHS-B2235-SUB-8-10	7/23/2018	855.30	855.51	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80091-1	Not Excavated							
Football Field	SSHS-B2185	072518 09:00 SSHS-B2185-SUB-8-10	SSHS-B2185-SUB-8-10	7/24/2018	855.07	855.49	0.42	-	8 - 10 ft	8.42-10.42 ft	180-80106-3	Not Excavated							
Football Field	SSHS-B2186	072518 09:00 SSHS-B2186-SUB-8-10	SSHS-B2186-SUB-8-10	7/24/2018	854.94	855.41	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2187	072518 09:00 SSHS-B2187-SUB-8-10	SSHS-B2187-SUB-8-10	7/24/2018	856.10	856.10	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 PS-FD-14	PS-FD-14	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2188	072518 09:00 SSHS-B2188-SUB-8-10	SSHS-B2188-SUB-8-10	7/24/2018	855.99	855.99	0.00	-	8 - 10 ft	8-10 ft	180-80106-2	Not Excavated							
Football Field	SSHS-B2189	072518 09:00 SSHS-B2189-SUB-8-10	SSHS-B2189-SUB-8-10	7/24/2018	855.74	855.90	0.16	-	8 - 10 ft	8.16-10.16 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2191	072518 09:00 SSHS-B2191-SUB-8-10	SSHS-B2191-SUB-8-10	7/24/2018	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-80105-3	Not Excavated							
Football Field	SSHS-B2197	072518 09:00 SSHS-B2197-SUB-8-10	SSHS-B2197-SUB-8-10	7/24/2018	854.99	855.43	0.44	-	8 - 10 ft	8.44-10.44 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2232	072518 09:00 SSHS-B2232-SUB-8-10	SSHS-B2232-SUB-8-10	7/24/2018	856.82	856.82	0.00	-	8 - 10 ft	8-10 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2233	072518 09:00 SSHS-B2233-SUB-8-10	SSHS-B2233-SUB-8-10	7/24/2018	854.83	855.35	0.52	-	8 - 10 ft	8.52-10.52 ft	180-80105-1	Not Excavated							
Football Field	SSHS-B2245	072518 09:00 SSHS-B2245-SUB-8-10	SSHS-B2245-SUB-8-10	7/24/2018	855.25	855.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-80106-1	Not Excavated							
Football Field	SSHS-B2070	072618 08:50 SSHS-B2070-SUB-8-10	SSHS-B2070-SUB-8-10	7/25/2018	854.72	855.22	0.50	-	8 - 10 ft	8.5-10.5 ft	180-80157-3	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated							
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated							
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated							
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated							
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated							
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated							
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated							
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated							
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated							
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated							
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated							
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated							
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated							
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated							
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated							
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated							
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated							
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated							
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U,*
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated						
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated						
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated						
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated						
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated						
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated						
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated						
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated						
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated						
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated						
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated						
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated						
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated						
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated						
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated						
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated						
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated						
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated						
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated						
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated						
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated						
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated						
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated						
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated						

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0027 U	< 0.0031 U	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated								
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated								
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated								
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated								
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated								
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated								
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	0.0099	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated								
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated								
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated								
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated								
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated								
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated								
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0025 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated								
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated								
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated								
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated								
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated								
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated								
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U	< 0.0025 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated								
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated								
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated								
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated								
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated								
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated								
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated								
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated								
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated								
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated								
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated								
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated								
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated								
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated								
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated								
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated								
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated								
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated								
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated								
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated								
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated								
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated								
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated								
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated								
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated								
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated								
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated								
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated								
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated								
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated								
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated								
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated								
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated								
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated								
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated								
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated								
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated								
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated								
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated								
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated								
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated								
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated								
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated								
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated								
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated								
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated								
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated						
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated						
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated						
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated						
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0024 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated						
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated						
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated						
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated						
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated						
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated						
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated						
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated						
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated						
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated						
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated						
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated						
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated						
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated						
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated						
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated						
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated						
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated						
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated						
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated						
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated						
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated						
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated						
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U	< 0.0029 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated						
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated						
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated						
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated						
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated						
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated						
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated						
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated						
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated						
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated						
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2089	072618 08:50 SSHS-B2089-SUB-8-10	SSHS-B2089-SUB-8-10	7/25/2018	855.40	855.39	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2091	072618 08:50 SSHS-B2091-SUB-8-10	SSHS-B2091-SUB-8-10	7/25/2018	856.61	856.61	0.00	-	8 - 10 ft	8-10 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2108	072618 08:50 SSHS-B2108-SUB-8-10	SSHS-B2108-SUB-8-10	7/25/2018	855.64	855.64	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2109	072618 08:50 SSHS-B2109-SUB-8-10	SSHS-B2109-SUB-8-10	7/25/2018	855.25	855.48	0.23	-	8 - 10 ft	8.23-10.23 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2110	072618 08:50 SSHS-B2110-SUB-8-10	SSHS-B2110-SUB-8-10	7/25/2018	854.78	855.36	0.58	-	8 - 10 ft	8.58-10.58 ft	180-80154-1	Not Excavated							
Football Field	SSHS-B2127	072618 08:50 SSHS-B2127-SUB-8-10	SSHS-B2127-SUB-8-10	7/25/2018	855.91	855.91	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2128	072618 08:50 SSHS-B2128-SUB-8-10	SSHS-B2128-SUB-8-10	7/25/2018	856.01	856.01	0.00	-	8 - 10 ft	8-10 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2129	072618 08:50 SSHS-B2129-SUB-8-10	SSHS-B2129-SUB-8-10	7/25/2018	855.33	855.52	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80157-1	Not Excavated							
Football Field	SSHS-B2143	072618 08:50 SSHS-B2143-SUB-8-10	SSHS-B2143-SUB-8-10	7/25/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80154-3	Not Excavated							
Football Field	SSHS-B2194	072618 08:50 SSHS-B2194-SUB-8-10	SSHS-B2194-SUB-8-10	7/25/2018	856.19	856.19	0.00	-	8 - 10 ft	8-10 ft	180-80157-3	Not Excavated							
Football Field	SSHS-B2216	072618 08:50 SSHS-B2216-SUB-8-10	SSHS-B2216-SUB-8-10	7/25/2018	855.16	855.46	0.30	-	8 - 10 ft	8.3-10.3 ft	180-80154-2	Not Excavated							
Football Field	SSHS-B2025	072718 09:00 SSHS-B2025-SUB-8-10	SSHS-B2025-SUB-8-10	7/26/2018	854.55	854.52	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2026	072718 09:00 SSHS-B2026-SUB-8-10	SSHS-B2026-SUB-8-10	7/26/2018	855.26	855.47	0.21	-	8 - 10 ft	8.21-10.21 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2028	072718 09:00 SSHS-B2028-SUB-8-10	SSHS-B2028-SUB-8-10	7/26/2018	855.23	855.54	0.31	-	8 - 10 ft	8.31-10.31 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2050	072718 09:00 SSHS-B2050-SUB-8-10	SSHS-B2050-SUB-8-10	7/26/2018	855.45	855.45	0.00	-	8 - 10 ft	8-10 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2192	072718 09:00 SSHS-B2192-SUB-8-10	SSHS-B2192-SUB-8-10	7/26/2018	855.49	855.50	0.01	-	8 - 10 ft	8.01-10.01 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 PS-FD-31	PS-FD-31	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-3	Not Excavated							
Football Field	SSHS-B2195	072718 09:00 SSHS-B2195-SUB-8-10	SSHS-B2195-SUB-8-10	7/26/2018	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-80225-1	Not Excavated							
Football Field	SSHS-B2213	072718 09:00 SSHS-B2213-SUB-8-10	SSHS-B2213-SUB-8-10	7/26/2018	855.06	855.53	0.47	-	8 - 10 ft	8.47-10.47 ft	180-80225-2	Not Excavated							
Football Field	SSHS-B2214	072718 09:00 SSHS-B2214-SUB-8-10	SSHS-B2214-SUB-8-10	7/26/2018	855.14	855.34	0.20	-	8 - 10 ft	8.2-10.2 ft	180-80227-3	Not Excavated							
Football Field	SSHS-B2215	072718 09:00 SSHS-B2215-SUB-8-10	SSHS-B2215-SUB-8-10	7/26/2018	855.11	855.30	0.19	-	8 - 10 ft	8.19-10.19 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2224	072718 09:00 SSHS-B2224-SUB-8-10	SSHS-B2224-SUB-8-10	7/26/2018	854.93	855.29	0.36	-	8 - 10 ft	8.36-10.36 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2226	072718 09:00 SSHS-B2226-SUB-8-10	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B2227	072718 09:00 SSHS-B2227-SUB-8-10	SSHS-B2227-SUB-8-10	7/26/2018	856.55	856.55	0.00	-	8 - 10 ft	8-10 ft	180-80227-2	Not Excavated							
Football Field	SSHS-B2031	072818 11:30 SSHS-B2031-SUB-8-10	SSHS-B2031-SUB-8-10	7/27/2018	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 PS-FD-46	PS-FD-46	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2032	072818 11:30 SSHS-B2032-SUB-8-10	SSHS-B2032-SUB-8-10	7/27/2018	854.88	855.51	0.63	-	8 - 10 ft	8.63-10.63 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2033	072818 11:30 SSHS-B2033-SUB-8-10	SSHS-B2033-SUB-8-10	7/27/2018	854.70	855.74	1.04	-	8 - 10 ft	9.04-11.04 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2051	072818 11:30 SSHS-B2051-SUB-8-10	SSHS-B2051-SUB-8-10	7/27/2018	855.08	855.37	0.29	-	8 - 10 ft	8.29-10.29 ft	180-80251-1	Not Excavated							
Football Field	SSHS-B2071	072818 11:30 SSHS-B2071-SUB-8-10	SSHS-B2071-SUB-8-10	7/27/2018	856.16	856.16	0.00	-	8 - 10 ft	8-10 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2090	072818 11:30 SSHS-B2090-SUB-8-10	SSHS-B2090-SUB-8-10	7/27/2018	855.97	855.96	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-80251-2	Not Excavated							
Football Field	SSHS-B2190	072818 11:30 SSHS-B2190-SUB-8-10	SSHS-B2190-SUB-8-10	7/27/2018	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-80252-2	Not Excavated							
Football Field	SSHS-B2217	072818 11:30 SSHS-B2217-SUB-8-10	SSHS-B2217-SUB-8-10	7/27/2018	855.08	855.32	0.24	-	8 - 10 ft	8.24-10.24 ft	180-80251-3	Not Excavated							
Football Field	SSHS-B2228	072818 11:30 SSHS-B2228-SUB-8-10	SSHS-B2228-SUB-8-10	7/27/2018	855.33	855.33	0.00	-	8 - 10 ft	8-10 ft	180-80252-1	Not Excavated							
Football Field	SSHS-B2747	042419 09:00 SSHS-B2747-SUB-8-10	SSHS-B2747-SUB-8-10	4/23/2019	856.08	856.07	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2767	042419 09:00 SSHS-B2767-SUB-8-10	SSHS-B2767-SUB-8-10	4/23/2019	856.06	856.06	0.00	-	8 - 10 ft	8-10 ft	180-89344-1	Not Excavated							
Football Field	SSHS-B2762	042819 10:00 SSHS-B2762-SUB-8-10	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Football Field	SSHS-B2763	042819 10:00 SSHS-B2763-SUB-8-10	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Football Field	SSHS-B2773	051519 08:45 SSHS-B2773-SUB-8-10	SSHS-B2773-SUB-8-10	5/13/2019	854.27	854.35	0.08	-	8 - 10 ft	8.08-10.08 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2774	051519 08:45 SSHS-B2774-SUB-8-10	SSHS-B2774-SUB-8-10	5/13/2019	854.02	854.07	0.05	-	8 - 10 ft	8.05-10.05 ft	180-90048-2	Not Excavated							
Football Field	SSHS-B2676	051719 09:00 SSHS-B2676-SUB-8-10	SSHS-B2676-SUB-8-10	5/16/2019	856.26	856.26	0.00	-	8 - 10 ft	8-10 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2805	051719 09:00 PS-FD-11	PS-FD-11	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2805	051719 09:00 SSHS-B2805-SUB-8-10	SSHS-B2805-SUB-8-10	5/16/2019	856.47	856.46	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-90231-1	Not Excavated							
Football Field	SSHS-B2618	051819 10:00 SSHS-B2618-SUB-8-10	SSHS-B2618-SUB-8-10	5/17/2019	855.12	855.29	0.17	-	8 - 10 ft	8.17-10.17 ft	180-90275-1	Not Excavated							
Football Field	SSHS-B2700	051819 10:00 SSHS-B2700-SUB-8-10	SSHS-B2700-SUB-8-10	5/17/2019	856.68	856.69	0.01	-	8 - 10 ft	8.01-10.01 ft	180-90275-1	Not Excavated							
Football Field	SSHS-IRM3-B107	080319 09:30 SSHS-IRM3-B107-C	SSHS-IRM3-B107-C	8/2/2019	-	855.97	-	847.23	8 - 10 ft	8.74 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-B110	080319 09:30 SSHS-IRM3-B110-C	SSHS-IRM3-B110-C	8/2/2019	-	855.89	-	845.89	8 - 10 ft	10 ft	180-93640-1	Not Excavated							
Football Field	SSHS-IRM3-S098	080319 09:30 SSHS-IRM3-S098-C	SSHS-IRM3-S098-C	8/2/2019	-	855.88	-	846.78	8 - 10 ft	9.1 ft	180-93640-2	Not Excavated							
Football Field	SSHS-IRM3-S121	080619 09:00 SSHS-IRM3-S121-C	SSHS-IRM3-S121-C	8/5/2019	-	855.75	-	846.14	8 - 10 ft	9.61 ft	180-93683-2	Not Excavated							
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-DUP6-D	SSHS-IRM3-DUP6-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S127	080619 09:00 SSHS-IRM3-S127-D	SSHS-IRM3-S127-D	8/5/2019	-	856.35	-	847.83	8 - 10 ft	8.52 ft	180-93684-2	Not Excavated							
Football Field	SSHS-IRM3-S129F	080919 09:00 SSHS-IRM3-S129F-D	SSHS-IRM3-S129F-D	8/8/2019	-	856.47	-	847.26	8 - 10 ft	9.21 ft	180-93896-2	Not Excavated							
Football Field	SSHS-B2936	110719 09:00 SSHS-B2936-SUB-8-10	SSHS-B2936-SUB-8-10	11/5/2019	856.94	856.92	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-98355-1	Not Excavated							
Football Field	SSHS-B2937	110719 09:00 SSHS-B2937-SUB-8-10	SSHS-B2937-SUB-8-10	11/5/2019	856.90	856.90	0.00	-	8 - 10 ft	8-10 ft	180-98355-1	Not Excavated							
Football Field	IRM4-S068	SSHS-IRM4-S068-4-6-20200719	SSHS-IRM4-S068-4-6	7/19/2020	-	855.60	-	846.15	8 - 10 ft	9.45 ft	1801085011	Not Excavated							
Football Field	IRM4-B04	SSHS-IRM4-B04-20200723	SSHS-IRM4-B04	7/23/2020	-	855.34	-	847.29	8 - 10 ft	8.05 ft	1801086851	Not Excavated							
Football Field	IRM4-S116	SSHS-IRM4-S116-8-10-20200723	SSHS-IRM4-S116-8-10	7/23/2020	-	856.06	-	846.78	8 - 10 ft	9.28 ft	1801086851	Not Excavated							
Football Field	IRM4-S122	SSHS-IRM4-S122-8-10-20200725	SSHS-IRM4-S122-8-10	7/25/2020	-	855.48	-	846.82	8 - 10 ft	8.66 ft	1801088021	Not Excavated							
Football Field	SSHS-B3459	072820 09:00 SSHS-B3459-SUB-8-10	SSHS-B3459-SUB-8-10	7/27/2020	856.30	856.31	0.01	-	8 - 10 ft	8.01-10.01 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3461	072820 09:00 SSHS-B3461-SUB-8-10	SSHS-B3461-SUB-8-10	7/27/2020	856.51	856.51	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3464	072820 09:00 SSHS-B3464-SUB-8-10	SSHS-B3464-SUB-8-10	7/27/2020	856.28	856.27	-0.01	-	8 - 10 ft	7.99-9.99 ft	180-108826-2	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 UJ	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Football Field	SSHS-B3472	072820 09:00 SSHS-B3472-SUB-8-10	SSHS-B3472-SUB-8-10	7/27/2020	855.50	855.50	0.00	-	8 - 10 ft	8-10 ft	180-108826-2	Not Excavated							
Football Field	SSHS-B3473	072820 09:00 SSHS-B3473-SUB-8-10	SSHS-B3473-SUB-8-10	7/27/2020	855.34	855.50	0.16	-	8 - 10 ft	8.16-10.16 ft	180-108826-2	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Football Field	IRM4-S123A	SSHS-IRM4-FD10-20200803	SSHS-IRM4-FD10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090931	Not Excavated							
Football Field	IRM4-S143A	SSHS-IRM4-S143A-10-12-20200803	SSHS-IRM4-S143A-10-12	8/3/2020	-	855.93	-	845.98	8 - 10 ft	9.95 ft	1801090931	Not Excavated							
Football Field	IRM4-S123A	SSHS-IRM4-S123A-8-10-20200803	SSHS-IRM4-S123A-8-10	8/3/2020	-	855.36	-	846.80	8 - 10 ft	8.56 ft	1801090932	Not Excavated							
Football Field	IRM4-S123C	SSHS-IRM4-S123C-8-10-20200803	SSHS-IRM4-S123C-8-10	8/3/2020	-	855.38	-	845.75	8 - 10 ft	9.63 ft	1801090932	Not Excavated							
Football Field	IRM4-S123B	SSHS-IRM4-S123B-20200803	SSHS-IRM4-S123B	8/3/2020	-	855.37	-	846.29	8 - 10 ft	9.08 ft	1801090931	Not Excavated							
Football Field	IRM4-S124N	SSHS-IRM4-S124N-8-10-20200805	SSHS-IRM4-S124N-8-10	8/5/2020	-	855.43	-	846.29	8 - 10 ft	9.14 ft	1801092181	Not Excavated							
Football Field	IRM4-S124S	SSHS-IRM4-S124S-8-10-20200805	SSHS-IRM4-S124S-8-10	8/5/2020	-	855.30	-	846.87	8 - 10 ft	8.43 ft	1801092181	Not Excavated							
Football Field	IRM4-S123A1	SSHS-IRM4-DUP15-20200806	SSHS-IRM4-DUP15	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated							
Football Field	IRM4-S123A2	SSHS-IRM4-DUP16-20200806	SSHS-IRM4-DUP16	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated							
Football Field	IRM4-S123A1	SSHS-IRM4-S123A1-20200806	SSHS-IRM4-S123A1	8/6/2020	-	855.36	-	846.69	8 - 10 ft	8.67 ft	1801092831	Not Excavated							
Football Field	IRM4-S123A2	SSHS-IRM4-S123A2-20200806	SSHS-IRM4-S123A2	8/6/2020	-	855.39	-	846.52	8 - 10 ft	8.87 ft	1801092831	Not Excavated							

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated							
Football Field	IRM4-S135	081220 09:30 SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated							
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated							
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated							
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated							
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated							
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated							
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated							
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated							
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated							
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated							
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated							
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated							
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated							
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated							
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.23 U	< 0.083 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.13 U	< 0.24 U	< 0.12 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3578	020421 09:30_DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated								
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated								
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated								
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated								
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated								
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated								
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated								
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated								
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated								
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated								
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated								
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated								
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated								
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated								
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated								
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated								
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated								
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated								
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated								
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated								
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated								
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated								
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated								
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated								
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated								
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated								
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated								
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated								
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated								
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated						
Football Field	IRM4-S135	081220 09:30 SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated						
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated						
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated						
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated						
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated						
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated						
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated						
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated						
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated						
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated						
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated						
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated						
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated						
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated						
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated						
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.077 U	< 0.15 U	< 0.17 U	< 0.095 U	< 0.12 U	< 0.14 U	< 0.19 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3578	020421 09:30 DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UJ	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UJ	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0033 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated							
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated							
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated							
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated							
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated							
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated							
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated							
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated							
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated							
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated							
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated							
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated							
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated							
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated							
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated							
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated							
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated							
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated							
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated							
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated							
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated							
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated							
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated							
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated							
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated							
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated							
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated							
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated							
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated							
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated							
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated							
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated							
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated							
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated							
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated							
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated							
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated							
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated							
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated							

DRAFT

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated								
Football Field	IRM4-S135	081220 09:30_SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated								
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated								
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated								
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated								
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated								
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated								
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated								
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated								
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated								
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated								
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated								
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated								
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated								
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.27 U	< 0.081 U	< 0.15 U	< 0.099 U	< 0.18 U	< 0.089 U	< 0.095 U	< 0.085 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3578	020421 09:30_DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 UJ	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0014 UJ	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0014 UJ	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated								
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated								
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated								
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated								
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated								
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated								
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated								
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated								
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated								
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated								
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated								
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated								
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated								
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated								
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated								
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated								
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated								
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated								
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated								
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated								
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated								
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated								
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated								
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated								
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated								
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated								
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated								
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated								
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated								
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated								
Football Field	IRM4-S135	081220 09:30_SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated								
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated								
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated								
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated								
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated								
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated								
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated								
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated								
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated								
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated								
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated								
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated								
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated								
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated								
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.13 U	< 0.24 U	< 0.089 U	< 0.1 U	< 0.079 U	< 0.13 U	< 0.13 U	< 0.11 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3578	020421 09:30_DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated								
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated								
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated								
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated								
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated								
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated								
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated								
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated								
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated								
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated								
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated								
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated								
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated								
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated								
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated								
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated								
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated								
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated								
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated								
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated								
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated								
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated								
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated								
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated								
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated								
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated								
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated								
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated								
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated								
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated								
Football Field	IRM4-S135	081220 09:30 SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated								
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated								
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated								
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated								
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated								
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated								
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated								
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated								
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated								
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated								
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated								
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated								
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated								
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated								
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated								
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.12 U	< 0.093 U	< 0.15 U	< 0.44 U	< 0.14 U	< 0.15 U	< 0.11 U	< 0.087 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	SSHS-B3578	020421 09:30 DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated								
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated								
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated								
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated								
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated								
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated								
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated								
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated								
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated								
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated								
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated								
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated								
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated								
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated								
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated								
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated								
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated								
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated								
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated								
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated								
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated								
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated								
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated								
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated								
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated								
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated								
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated								
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated								
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated								
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated								
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated								
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated								
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated								
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated								
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated								
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated						
Football Field	IRM4-S135	081220 09:30_SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated						
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated						
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated						
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated						
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated						
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated						
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated						
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated						
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated						
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated						
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated						
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated						
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated						
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated						
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated						
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.089 U	< 0.09 U	< 0.12 U	< 0.085 U	< 0.16 UJ	< 0.15 U	< 0.099 U
Football Field	SSHS-B3573	020421 09:30_SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3574	020421 09:30_SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	SSHS-B3576	020421 09:30_SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ	< 0.0018 U
Football Field	SSHS-B3578	020421 09:30_DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ	< 0.0018 U
Football Field	SSHS-B3578	020421 09:30_SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3572	020521 09:00_SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U
Football Field	SSHS-B3581	020621 10:00_SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Football Field	SSHS-B3582	020621 10:00_SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated						
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated						
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated						
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated						
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated						
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated						
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated						
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated						
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated						
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated						
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated						
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated						
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated						
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated						
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated						
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated						
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated						
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated						
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated						
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated						
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated						
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated						
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated						
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated						
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated						
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated						
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated						
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated						
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated						
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated						
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated						
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated						
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated						
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated						
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated						
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated						
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated						
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated						
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated						
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated						
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated						
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated						
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated						
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated						
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated						
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated						
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated						

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM4-S124N2	SSHS-IRM4-S124N2-20200807	SSHS-IRM4-S124N2	8/7/2020	-	855.58	-	846.23	8 - 10 ft	9.35 ft	1801093751	Not Excavated							
Football Field	IRM4-S135	081220 09:30 SSHS-IRM4-S135	SSHS-IRM4-S135	8/8/2020	-	855.65	-	845.94	8 - 10 ft	9.71 ft	180-109428-1	Not Excavated							
Football Field	IRM4-B200	SSHS-IRM4-B200-20200813	SSHS-IRM4-B200	8/13/2020	-	855.49	-	847.46	8 - 10 ft	8.03 ft	1801095841	Not Excavated							
Football Field	IRM4A-S092	SSHS-IRM4A-S092-20201012	SSHS-IRM4A-S092	10/12/2020	-	855.62	-	847.54	8 - 10 ft	8.08 ft	1801121381	Not Excavated							
Football Field	IRM4A-S118	SSHS-IRM4A-S118-20201012	SSHS-IRM4A-S118	10/12/2020	-	855.73	-	845.77	8 - 10 ft	9.97 ft	1801121721	Not Excavated							
Football Field	IRM4A-S119	SSHS-IRM4A-S119-20201012	SSHS-IRM4A-S119	10/12/2020	-	855.68	-	846.71	8 - 10 ft	8.97 ft	1801121721	Not Excavated							
Football Field	IRM4A-S107	SSHS-IRM4A-S107-20201019	SSHS-IRM4A-S107	10/19/2020	-	855.54	-	845.93	8 - 10 ft	9.62 ft	1801124481	Not Excavated							
Football Field	IRM4A-B036	SSHS-IRM4A-B036-20201019	SSHS-IRM4A-B036	10/19/2020	-	855.59	-	845.90	8 - 10 ft	9.69 ft	1801124481	Not Excavated							
Football Field	IRM4A-S125A	SSHS-IRM4A-S125A-8-10-20201118	SSHS-IRM4A-S125A-8-10	11/18/2020	-	855.41	-	845.51	8 - 10 ft	9.9 ft	1801138121	Not Excavated							
Football Field	IRM5-B233	SSHS-IRM5-DUP6-20210108	SSHS-IRM5-DUP6	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated							
Football Field	IRM5-S247	SSHS-IRM5-S247-20210108	SSHS-IRM5-S247	1/8/2021	-	855.34	-	847.13	8 - 10 ft	8.21 ft	1801157731	Not Excavated							
Football Field	IRM5-B233	SSHS-IRM5-B233-20210108	SSHS-IRM5-B233	1/8/2021	-	855.45	-	846.78	8 - 10 ft	8.67 ft	1801157731	Not Excavated							
Football Field	IRM5-S246	SSHS-IRM5-S246-20210108	SSHS-IRM5-S246	1/8/2021	-	855.49	-	847.18	8 - 10 ft	8.31 ft	1801157731	Not Excavated							
Football Field	IRM5-S245	SSHS-IRM5-S245-20210108	SSHS-IRM5-S245	1/8/2021	-	855.36	-	846.87	8 - 10 ft	8.5 ft	1801157731	Not Excavated							
Football Field	IRM5-B236	SSHS-IRM5-B236-20210108	SSHS-IRM5-B236	1/8/2021	-	855.39	-	846.58	8 - 10 ft	8.81 ft	1801157731	Not Excavated							
Football Field	IRM5-S243	SSHS-IRM5-S243-20210108	SSHS-IRM5-S243	1/8/2021	-	855.36	-	846.95	8 - 10 ft	8.41 ft	1801157731	Not Excavated							
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-8-10	SSHS-B3575-SUB-8-10	2/2/2021	854.85	855.40	0.55	-	8 - 10 ft	8.55-10.55 ft	180-116724-1	Not Excavated	< 0.059 U	< 0.093 U	< 0.25 U	< 0.21 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3573	020421 09:30 SSHS-B3573-SUB-8-10	SSHS-B3573-SUB-8-10	2/3/2021	855.66	855.66	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0041 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3574	020421 09:30 SSHS-B3574-SUB-8-10	SSHS-B3574-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0023 J	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3576	020421 09:30 SSHS-B3576-SUB-8-10	SSHS-B3576-SUB-8-10	2/3/2021	855.76	855.76	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3578	020421 09:30 DUP-29	DUP-29	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.001 U	0.0031 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3578	020421 09:30 SSHS-B3578-SUB-8-10	SSHS-B3578-SUB-8-10	2/3/2021	855.72	855.72	0.00	-	8 - 10 ft	8-10 ft	180-116773-1	Not Excavated	< 0.0011 U	0.0046 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-B3572	020521 09:00 SSHS-B3572-SUB-8-10	SSHS-B3572-SUB-8-10	2/4/2021	855.42	855.51	0.09	-	8 - 10 ft	8.09-10.09 ft	180-116864-1	Not Excavated	< 0.0011 U	0.0036 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-8-10	SSHS-B3580-SUB-8-10	2/5/2021	856.23	856.24	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116914-1	Not Excavated	< 0.0012 U	0.0052 J	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SSHS-B3581	020621 10:00 SSHS-B3581-SUB-8-10	SSHS-B3581-SUB-8-10	2/5/2021	856.18	856.18	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.0011 U	0.0055	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3582	020621 10:00 SSHS-B3582-SUB-8-10	SSHS-B3582-SUB-8-10	2/5/2021	855.93	855.93	0.00	-	8 - 10 ft	8-10 ft	180-116914-1	Not Excavated	< 0.001 U	0.0032 J	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-8-10	SSHS-B3583-SUB-8-10	2/5/2021	855.33	855.44	0.11	-	8 - 10 ft	8.11-10.11 ft	180-116914-1	Not Excavated	< 0.001 U	0.0051	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT-20210224	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated							
Football Field	IRM4A-S131A	SSHS-IRM4A-S131A-20210302	SSHS-IRM4A-S131A	3/2/2021	-	855.40	-	845.75	8 - 10 ft	9.65 ft	1801177751	Not Excavated							
Football Field	IRM5-PIPE 7-E	SSHS-IRM5-PIPE 7-E-20210308	SSHS-IRM5-PIPE 7-E	3/8/2021	-	855.50	-	846.27	8 - 10 ft	9.23 ft	1801180551	Not Excavated							
Football Field	IRM5-S266	SSHS-IRM5-S266-20210317	SSHS-IRM5-S266	3/17/2021	-	855.38	-	845.59	8 - 10 ft	9.79 ft	1801185741	Not Excavated							
Football Field	IRM4A-S131D1	SSHS-IRM4A-S131D1-20210319	SSHS-IRM4A-S131D1	3/19/2021	-	855.46	-	845.85	8 - 10 ft	9.61 ft	1801187461	Not Excavated							
Football Field	IRM4A-S131D4	SSHS-IRM4A-S131D4-20210319	SSHS-IRM4A-S131D4	3/19/2021	-	855.43	-	845.75	8 - 10 ft	9.68 ft	1801187461	Not Excavated							
Football Field	IRM5-PIPE 29	SSHS-IRM5-PIPE29-20210321	SSHS-IRM5-PIPE29	3/21/2021	-	855.89	-	846.80	8 - 10 ft	9.09 ft	1801188031	Not Excavated							
Football Field	IRM5-PIPE 7 SD-2-A	SSHS-IRM5-PIPE 7 STEPDOWN 2A-20210325	SSHS-IRM5-PIPE 7 STEPDOWN 2A	3/25/2021	-	855.42	-	845.73	8 - 10 ft	9.69 ft	1801190471	Not Excavated							
Football Field	IRM5-PIPE15 BTA	SSHS-IRM5-PIPE 15 BOT A-20210327	SSHS-IRM5-PIPE 15 BOT A	3/27/2021	-	855.84	-	846.56	8 - 10 ft	9.28	1801191611	Not Excavated							
Football Field	IRM5-S270A	SSHS-IRM5-S270A-20210327	SSHS-IRM5-S270A	3/27/2021	-	856.12	-	847.80	8 - 10 ft	8.32 ft	1801191612	Not Excavated							
Football Field	IRM5-S271A	SSHS-IRM5-S271A-20210327	SSHS-IRM5-S271A	3/27/2021	-	856.05	-	847.88	8 - 10 ft	8.17 ft	1801191613	Not Excavated							
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210327	SSHS-IRM5-S269A	3/27/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801191612	Not Excavated							
Football Field	IRM5-S272A	SSHS-IRM5-S272A-20210327	SSHS-IRM5-S272A	3/27/2021	-	855.83	-	847.67	8 - 10 ft	8.16 ft	1801191613	Not Excavated							
Football Field	IRM5-UBO-1 BOT	SSHS-IRM5-UBO-1 BOT-20210329	SSHS-IRM5-UBO-1 BOT	3/29/2021	-	855.73	-	847.16	8 - 10 ft	8.57 ft	1801191613	Not Excavated							
Football Field	IRM5-PIPE 18-SD-C	SSHS-IRM5-PIPE 18-STEPDOWN-C-20210401	SSHS-IRM5-PIPE 18-STEPDOWN-C	4/1/2021	-	855.51	-	846.35	8 - 10 ft	9.15 ft	1801194581	Not Excavated							
Football Field	ISMP-B001	SSHS-ISMP-B001-20210401	SSHS-ISMP-B001	4/1/2021	-	855.84	-	846.09	8 - 10 ft	9.75	1801194581	Not Excavated							
Football Field	ISMP-PIPE1WEST	SSHS-ISMP-PIPE1WEST-20210405	SSHS-ISMP-PIPE1WEST	4/5/2021	-	855.67	-	845.78	8 - 10 ft	9.89	1801195091	Not Excavated							
Football Field	IRM5-PIPE 33 S1B	SSHS-IRM5-PIPE 33 S1B-20210406	SSHS-IRM5-PIPE 33 S1B	4/6/2021	-	855.55	-	846.96	8 - 10 ft	8.59 ft	1801195651	Not Excavated							
Football Field	IRM5-S700	SSHS-IRM5-S700-20210406	SSHS-IRM5-S700	4/6/2021	-	855.48	-	846.16	8 - 10 ft	9.32 ft	1801195651	Not Excavated							
Football Field	IRM5-B703	SSHS-IRM5-B703-20210406	SSHS-IRM5-B703	4/6/2021	-	855.31	-	846.46	8 - 10 ft	8.85 ft	1801195652	Not Excavated							
Football Field	IRM5-S702	SSHS-IRM5-S702-20210406	SSHS-IRM5-S702	4/6/2021	-	855.45	-	846.15	8 - 10 ft	9.3 ft	1801195651	Not Excavated							
Football Field	IRM5-S705	SSHS-IRM5-S705-20210406	SSHS-IRM5-S705	4/6/2021	-	855.28	-	846.08	8 - 10 ft	9.2 ft	1801195651	Not Excavated							
Football Field	IRM5-B704	SSHS-IRM5-B704-20210406	SSHS-IRM5-B704	4/6/2021	-	855.40	-	846.50	8 - 10 ft	8.9 ft	1801195652	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 1	SSHS-IRM5-PIPE 32 BOT 1-20210407	SSHS-IRM5-PIPE 32 BOT 1	4/7/2021	-	856.06	-	847.80	8 - 10 ft	8.26 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 2	SSHS-IRM5-PIPE 32 BOT 2-20210407	SSHS-IRM5-PIPE 32 BOT 2	4/7/2021	-	855.85	-	847.53	8 - 10 ft	8.32 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 3	SSHS-IRM5-PIPE 32 BOT 3-20210407	SSHS-IRM5-PIPE 32 BOT 3	4/7/2021	-	855.70	-	847.44	8 - 10 ft	8.26 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 32 BOT 4	SSHS-IRM5-PIPE 32 BOT 4-20210407	SSHS-IRM5-PIPE 32 BOT 4	4/7/2021	-	855.41	-	846.39	8 - 10 ft	9.02 ft	1801196311	Not Excavated							
Football Field	IRM5-PIPE 33 BOT 1	SSHS-IRM5-PIPE 33 BOT 1-20210407	SSHS-IRM5-PIPE 33 BOT 1	4/7/2021	-	855.56	-	845.66	8 - 10 ft	9.9 ft	1801196311	Not Excavated							
Football Field	IRM5-S704	SSHS-IRM5-S704-20210407	SSHS-IRM5-S704	4/7/2021	-	855.45	-	846.19	8 - 10 ft	9.27 ft	1801196311	Not Excavated							
Football Field	IRM5-B802	SSHS-IRM5-B802-20210407	SSHS-IRM5-B802	4/7/2021	-	855.58	-	847.06	8 - 10 ft	8.53 ft	1801196312	Not Excavated							
Football Field	ISMP-B106	SSHS-ISMP-B106-20210408	SSHS-ISMP-B106	4/8/2021	-	855.38	-	846.83	8 - 10 ft	8.55 ft	1801197253	Not Excavated							
Football Field	IRM5-WELL 1 NORTH	SSHS-IRM5-WELL 1 NORTH-20210409	SSHS-IRM5-WELL 1 NORTH	4/9/2021	-	855.58	-	845.78	8 - 10 ft	9.8 ft	1801197961	Not Excavated							
Football Field	IRM5-WELL 1 SOUTH	SSHS-IRM5-WELL 1 SOUTH-20210409	SSHS-IRM5-WELL 1 SOUTH	4/9/2021	-	855.61	-	846.56	8 - 10 ft	9.05 ft	1801197961	Not Excavated							
Football Field	IRM5-S614	SSHS-IRM5-S614-20210412	SSHS-IRM5-S614	4/12/2021	-	855.65	-	846.07	8 - 10 ft	9.58 ft	1801198482	Not Excavated							
Football Field	IRM5-B808C	SSHS-IRM5-DUP 63-20210416	SSHS-IRM5-DUP 63	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated							
Football Field	IRM5-B808D	SSHS-IRM5-B808D-20210416	SSHS-IRM5-B808D	4/16/2021	-	855.46	-	846.48	8 - 10 ft	8.98 ft	1801201431	Not Excavated							
Football Field	IRM5-B808 BOT 1	SSHS-IRM5-B808 BOT 1-20210416	SSHS-IRM5-B808 BOT 1	4/16/2021	-	855.56	-	845.69	8 - 10 ft	9.87 ft	1801201431	Not Excavated							
Football Field	IRM5-B808A	SSHS-IRM5-B808A-20210416	SSHS-IRM5-B808A	4/16/2021	-	855.63	-	847.51	8 - 10 ft	8.12 ft	1801201431	Not Excavated							
Football Field	IRM5-B808B	SSHS-IRM5-B808B-20210416	SSHS-IRM5-B808B	4/16/2021	-	855.64	-	846.93	8 - 10 ft	8.71 ft	1801201431	Not Excavated							
Football Field	IRM5-B808C	SSHS-IRM5-B808C-20210416	SSHS-IRM5-B808C	4/16/2021	-	855.52	-	846.41	8 - 10 ft	9.11 ft	1801201431	Not Excavated							
Football Field	IRM5-B700B6	SSHS-IRM5-DUP 67-20210418	SSHS-IRM5-DUP 67	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated							
Football Field	IRM5-B700B6	SSHS-IRM5-B700 B6-20210418	SSHS-IRM5-B700 B6	4/18/2021	-	855.53	-	846.61	8 - 10 ft	8.92 ft	1801201972	Not Excavated							
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-DUP 70-20210421	SSHS-IRM5-DUP 70	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated							
Football Field	IRM5-SEGMENT 7 S5	SSHS-IRM5-SEG 7 S5-20210421	SSHS-IRM5-SEG 7 S5	4/21/2021	-	853.91	-	844.44	8 - 10 ft	9.47 ft	1801203601	Not Excavated							
Football Field	IRM5-S269A	SSHS-IRM5-S269A-20210422	SSHS-IRM5-S269A	4/22/2021	-	855.97	-	847.51	8 - 10 ft	8.46 ft	1801204573	Not Excavated							
Football Field	IRM5-DW3WEST	SSHS-IRM5-DW3 W-20210423	SSHS-IRM5-DW3 W	4/23/2021	-	855.61	-	846.86	8 - 10 ft	8.75 ft	1801205491	Not Excavated							
Football Field	IRM5-DW3EAST	SSHS-IRM5-DW3 E-20210423	SSHS-IRM5-DW3 E	4/23/2021	-	855.62	-	846.39	8 - 10 ft	9.24 ft	1801205491	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated							
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated							
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated							
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated							
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated							
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated							
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated							
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated							
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated							
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated							
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated							
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated							
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated							
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated							
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated							
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated							
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated							
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated							
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated							
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated							
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.02 U	< 0.00066 U	< 0.00056 U	< 0.00064 UT	< 0.0023 U	< 0.00093 U	< 0.0011 U	< 0.0031 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0061 U	< 0.0022 U	< 0.0047 U	< 0.0036 U	< 0.0039 U	< 0.0036 U	< 0.0062 U	< 0.0032 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 UT	< 0.0022 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 UT	< 0.0023 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated								
Football Field	SSHS-B3526	062321 09:30 DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3526	062321 09:30 SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30 DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30 SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	0.014 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated								

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated						
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated						
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated						
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated						
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated						
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated						
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated						
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated						
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated						
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated						
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated						
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated						
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated						
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated						
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated						
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated						
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated						
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated						
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated						
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated						
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated						
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated						
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.00086 U	< 0.0026 U	< 0.0011 U	< 0.00074 U	< 0.00098 U	< 0.0013 U	< 0.0034 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0020 U	< 0.0039 U	< 0.0046 U	< 0.0025 U	< 0.0031 U	< 0.0037 U	< 0.0050 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated							
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated							
Football Field	SSHS-B3526	062321 09:30 DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3526	062321 09:30 SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3527	062321 09:30 DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3527	062321 09:30 SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated							
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UT
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated							
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated							
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated							
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated							
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated							
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated							
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated							
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated							
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated							
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated							
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated							
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated							
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated							
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated							
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated							
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated							
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated							
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated							
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.63	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated							
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated							
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated							
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated							
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.011 U	< 0.00073 U	< 0.00089 U	< 0.0010 U	< 0.00077 U	< 0.00083 U	< 0.00065 U	< 0.00073 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0070 U	< 0.0021 U	< 0.0039 U	< 0.0026 U	< 0.0048 U	< 0.0023 U	< 0.0025 U	< 0.0022 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated								
Football Field	SSHS-B3526	062321 09:30 DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3526	062321 09:30 SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30 DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30 SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 UT	< 0.0033 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated								
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated								
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated								
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated								
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated								
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated								
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated								
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated								
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated								
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated								
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated								
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated								
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated								
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated								
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated								
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated								
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated								
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated								
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated								
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated								
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated								
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated								
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.00085 U	0.0026 J	0.0026 J	< 0.00044 U	< 0.00080 U	< 0.0014 U	< 0.00097 U	< 0.00099 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0035 U	0.0069 J	0.0069 J	< 0.0027 U	< 0.0021 U	< 0.0034 U	< 0.0035 U	< 0.0029 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated								
Football Field	SSHS-B3526	062321 09:30_DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3526	062321 09:30_SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30_DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30_SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated								

												Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	0.12		0.93
Restricted - Residential																	100		100
Protection of Groundwater																	0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated								
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated								
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated								
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated								
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated								
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated								
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated								
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated								
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated								
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated								
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated								
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated								
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated								
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated								
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated								
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated								
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated								
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated								
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated								
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated								
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated								
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated								
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated								
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated								
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated								
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated								
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated								
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.0012 U	< 0.0038 U	< 0.00078 U	< 0.0032 U	< 0.0012 U	< 0.0033 U	< 0.0035 U	< 0.00077 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0031 U	< 0.0024 U	< 0.0041 U	< 0.011 U	< 0.0038 U	< 0.0040 U	< 0.0029 U	< 0.0023 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated								
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated								
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated								
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated								
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated								
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated								
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated								
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated								
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated								
Football Field	SSHS-B3526	062321 09:30_DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3526	062321 09:30_SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30_DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	SSHS-B3527	062321 09:30_SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated								
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated								
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated						
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated						
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated						
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated						
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated						
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated						
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated						
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated						
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated						
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated						
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated						
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated						
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated						
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated						
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated						
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated						
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated						
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated						
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated						
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated						
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated						
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated						
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated						
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated						
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated						
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated						
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.0011 UT	< 0.0013 U	< 0.00069 U	< 0.00073 U	< 0.00054 U	< 0.00054 U	< 0.00077 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0023 U	< 0.0024 U	< 0.0031 U	< 0.0022 U	< 0.0043 U	< 0.0040 U	< 0.0026 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated							
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated							
Football Field	SSHS-B3526	062321 09:30 DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3526	062321 09:30 SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3527	062321 09:30 DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3527	062321 09:30 SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated							
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT	< 0.0018 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated							
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated							
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated							

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-DW4EAST	SSHS-IRM5-DW4 E-20210423	SSHS-IRM5-DW4 E	4/23/2021	-	855.50	-	845.69	8 - 10 ft	9.81 ft	1801205491	Not Excavated							
Football Field	IRM5-P18-BOT	SSHS-IRM5-P18-BOT1-20210423	SSHS-IRM5-P18-BOT1	4/23/2021	-	855.41	-	846.88	8 - 10 ft	8.53 ft	1801205492	Not Excavated							
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-DUP 86-20210426	SSHS-IRM5-DUP 86	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 5	SSHS-IRM5-P18 BOT 5-20210426	SSHS-IRM5-P18 BOT 5	4/26/2021	-	856.15	-	847.27	8 - 10 ft	8.88 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 4	SSHS-IRM5-P18 BOT 4-20210426	SSHS-IRM5-P18 BOT 4	4/26/2021	-	855.97	-	847.81	8 - 10 ft	8.16 ft	1801206041	Not Excavated							
Football Field	IRM5-CB28 BOT 4	SSHS-IRM5-CB28 BOT4-20210426	SSHS-IRM5-CB28 BOT4	4/26/2021	-	855.67	-	847.36	8 - 10 ft	8.31 ft	1801206041	Not Excavated							
Football Field	IRM5-P18 BOT 2A	SSHS-IRM5-P18 BOT 2A-20210426	SSHS-IRM5-P18 BOT 2A	4/26/2021	-	855.77	-	847.32	8 - 10 ft	8.45 ft	1801206041	Not Excavated							
Football Field	IRM5-B618	SSHS-IRM5-B618-20210426	SSHS-IRM5-B618	4/26/2021	-	855.46	-	847.43	8 - 10 ft	8.03 ft	1801206042	Not Excavated							
Football Field	IRM5-ALPHA BOT 1	SSHS-IRM5-ALPHA BOT 1-20210430	SSHS-IRM5-ALPHA BOT 1	4/30/2021	-	855.51	-	846.76	8 - 10 ft	8.76 ft	1801209531	Not Excavated							
Football Field	IRM5-P18F BOT 1	SSHS-IRM5-P18F BOT 1-20210501	SSHS-IRM5-P18F BOT 1	5/1/2021	-	855.31	-	847.25	8 - 10 ft	8.06 ft	1801210061	Not Excavated							
Football Field	IRM5-PIPE 47 BOT 1	SSHS-IRM5-PIPE 47 BOT 1-20210504	SSHS-IRM5-PIPE 47 BOT 1	5/4/2021	-	855.05	-	845.87	8 - 10 ft	9.18 ft	1801211061	Not Excavated							
Football Field	IRM5-P18-5S-BOT A	SSHS-IRM5-P18-5S-BOT A-20210505	SSHS-IRM5-P18-5S-BOT A	5/5/2021	-	856.07	-	846.08	8 - 10 ft	9.99 ft	1801211941	Not Excavated							
Football Field	IRM5-P18-5S-BOT B	SSHS-IRM5-P18-5S-BOT B-20210505	SSHS-IRM5-P18-5S-BOT B	5/5/2021	-	856.18	-	846.44	8 - 10 ft	9.74 ft	1801211941	Not Excavated							
Football Field	IRM5-ALPHA BOT 12	SSHS-IRM5-ALPHA BOT 12-20210506	SSHS-IRM5-ALPHA BOT 12	5/6/2021	-	855.56	-	846.90	8 - 10 ft	8.66 ft	1801212761	Not Excavated							
Football Field	IRM5-ALPHA BOT 10	SSHS-IRM5-ALPHA BOT 10-20210506	SSHS-IRM5-ALPHA BOT 10	5/6/2021	-	855.78	-	847.68	8 - 10 ft	8.09 ft	1801212761	Not Excavated							
Football Field	IRM5-S234A BOT A	SSHS-IRM5-S234A BOT A-20210507	SSHS-IRM5-S234A BOT A	5/7/2021	-	855.74	-	846.70	8 - 10 ft	9.04 ft	1801213531	Not Excavated							
Football Field	IRM5-S643 S16	SSHS-IRM5-S643 S16-20210509	SSHS-IRM5-S643 S16	5/9/2021	-	855.70	-	845.86	8 - 10 ft	9.84 ft	1801213911	Not Excavated							
Football Field	IRM5-S643 S12	SSHS-IRM5-S643 S12-20210509	SSHS-IRM5-S643 S12	5/9/2021	-	855.66	-	845.85	8 - 10 ft	9.81 ft	1801213911	Not Excavated							
Football Field	IRM5-P18 VAULT S5	SSHS-IRM5-P18 VAULT S5-20210510	SSHS-IRM5-P18 VAULT S5	5/10/2021	-	855.84	-	847.14	8 - 10 ft	8.71 ft	1801213911	Not Excavated							
Football Field	IRM5-P18 VAULT S6	SSHS-IRM5-P18 VAULT S6-20210510	SSHS-IRM5-P18 VAULT S6	5/10/2021	-	855.81	-	847.51	8 - 10 ft	8.3 ft	1801213911	Not Excavated							
Football Field	IRM5-B227 S8	SSHS-IRM5-DUP 104-20210512	SSHS-IRM5-DUP 104	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S5	SSHS-IRM5-B227 S5-20210512	SSHS-IRM5-B227 S5	5/12/2021	-	855.56	-	846.94	8 - 10 ft	8.62 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S6	SSHS-IRM5-B227 S6-20210512	SSHS-IRM5-B227 S6	5/12/2021	-	855.49	-	846.38	8 - 10 ft	9.1 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S7	SSHS-IRM5-B227 S7-20210512	SSHS-IRM5-B227 S7	5/12/2021	-	855.28	-	846.90	8 - 10 ft	8.38 ft	1801215152	Not Excavated							
Football Field	IRM5-B227 S8	SSHS-IRM5-B227 S8-20210512	SSHS-IRM5-B227 S8	5/12/2021	-	855.35	-	845.99	8 - 10 ft	9.36 ft	1801215152	Not Excavated							
Football Field	IRM5-BRAVO S7	SSHS-IRM5-BRAVO S7-20210513	SSHS-IRM5-BRAVO S7	5/13/2021	-	855.44	-	846.31	8 - 10 ft	9.13 ft	1801215901	Not Excavated							
Football Field	IRM5-BRAVO S9	SSHS-IRM5-BRAVO S9-20210513	SSHS-IRM5-BRAVO S9	5/13/2021	-	855.65	-	846.67	8 - 10 ft	8.98 ft	1801215901	Not Excavated							
Football Field	IRM5-ALPHA BOT 14	SSHS-IRM5-ALPHA BOT 14-20210513	SSHS-IRM5-ALPHA BOT 14	5/13/2021	-	855.50	-	847.12	8 - 10 ft	8.39 ft	1801215901	Not Excavated							
Football Field	IRM5-S234 S10	SSHS-IRM5-S234 S10-20210513	SSHS-IRM5-S234 S10	5/13/2021	-	855.69	-	846.47	8 - 10 ft	9.23 ft	1801215901	Not Excavated							
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-DUP 106-20210515	SSHS-IRM5-DUP 106	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated							
Football Field	IRM5-PIPE 50 BOT 2	SSHS-IRM5-PIPE 50 BOT 2-20210515	SSHS-IRM5-PIPE 50 BOT 2	5/15/2021	-	855.83	-	846.95	8 - 10 ft	8.88 ft	1801217211	Not Excavated							
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3-20210527	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3-20210527	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3-20210527	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3-20210527	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4-20210527	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4-20210527	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated							
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17-20210602	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24-20210603	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 0.0011 U	0.041	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32-20210603	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 0.0011 U	0.0064	< 0.0010 U	0.0016 J	< 0.00074 U	< 0.00081 U	< 0.0015 U
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36-20210603	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 0.0015 U	0.014	< 0.0065 U	< 0.0056 U	< 0.0028 U	< 0.0031 U	< 0.011 U
Football Field	ISMP-S519	SSHS-ISMP-S519-20210604	SSHS-ISMP-S519	6/4/2021	-	855.75	-	847.69	8 - 10 ft	8.06 ft	1801227322	Not Excavated	< 0.0011 U	0.0053 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210605	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210605	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210605	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210605	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210605	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated							
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210605	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 1	SSHS-IRM5-PIPE 52 BOT 1-20210605	SSHS-IRM5-PIPE 52 BOT 1	6/5/2021	-	856.15	-	847.45	8 - 10 ft	8.7 ft	1801228131	Not Excavated							
Football Field	IRM5-PIPE 52 BOT 2	SSHS-IRM5-PIPE 52 BOT 2-20210605	SSHS-IRM5-PIPE 52 BOT 2	6/5/2021	-	856.04	-	848.00	8 - 10 ft	8.04 ft	1801228131	Not Excavated							
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47-20210607	SSHS-ISMP-B527 S47	6/7/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20-20210607	SSHS-ISMP-B527 BOT 20	6/7/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228231	Not Excavated	< 0.0010 U	0.0050 J	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64-20210607	SSHS-ISMP-B527 S64	6/7/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19-20210607	SSHS-ISMP-B527 BOT 19	6/7/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228231	Not Excavated	< 0.0010 U	0.0018 J	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67-20210607	SSHS-ISMP-B527 S67	6/7/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228231	Not Excavated	< 0.0011 U	0.0090	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18-20210607	SSHS-ISMP-B527 BOT 18	6/7/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228231	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	ISMP-B545	SSHS-ISMP-B545-20210609	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	IRM5-FIS-S4	SSHS-IRM5-FIS S4-20210614	SSHS-IRM5-FIS S4	6/14/2021	-	854.28	-	846.04	8 - 10 ft	8.24 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S10	SSHS-IRM5-FIS S10-20210614	SSHS-IRM5-FIS S10	6/14/2021	-	854.57	-	846.14	8 - 10 ft	8.43 ft	1801231601	Not Excavated							
Football Field	IRM5-FIS-S16	SSHS-IRM5-FIS S16-20210614	SSHS-IRM5-FIS S16	6/14/2021	-	855.24	-	846.51	8 - 10 ft	8.74 ft	1801231601	Not Excavated							
Football Field	IRM5-P18 S5A BOT 5	SSHS-IRM5-P18 S5A BOT 5-20210615	SSHS-IRM5-P18 S5A BOT 5	6/15/2021	-	856.07	-	847.59	8 - 10 ft	8.48 ft	1801232172	Not Excavated							
Football Field	IRM5-FIS BOT 11	SSHS-IRM5-FIS BOT 11-20210616	SSHS-IRM5-FIS BOT 11	6/16/2021	-	854.88	-	845.91	8 - 10 ft	8.97 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 12	SSHS-IRM5-FIS BOT 12-20210616	SSHS-IRM5-FIS BOT 12	6/16/2021	-	854.77	-	846.53	8 - 10 ft	8.24 ft	1801232822	Not Excavated							
Football Field	IRM5-FIS BOT 23	SSHS-IRM5-FIS BOT 23-20210618	SSHS-IRM5-FIS BOT 23	6/18/2021	-	853.46	-	843.57	8 - 10 ft	9.89 ft	1801234391	Not Excavated							
Football Field	IRM5-FIS-S215	SSHS-IRM5-FIS S215-20210618	SSHS-IRM5-FIS S215	6/18/2021	-	853.49	-	844.44	8 - 10 ft	9.05 ft	1801234391	Not Excavated							
Football Field	SSHS-B3526	062321 09:30 DUP-7	DUP-7	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3526	062321 09:30 SSHS-B3526-SUB-8-10	SSHS-B3526-SUB-8-10	6/22/2021	855.55	855.94	0.39	-	8 - 10 ft	8.39-10.39 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3527	062321 09:30 DUP-8	DUP-8	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated							
Football Field	SSHS-B3527	062321 09:30 SSHS-B3527-SUB-8-10	SSHS-B3527-SUB-8-10	6/22/2021	855.96	856.08	0.12	-	8 - 10 ft	8.12-10.12 ft	180-123547-1	Not Excavated							
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10-20210624	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89-20210624	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	IRM5-FIS BOT 30	SSHS-IRM5-FIS BOT 30-20210626	SSHS-IRM5-FIS BOT 30	6/26/2021	-	854.72	-	846.31	8 - 10 ft	8.41 ft	1801237631	Not Excavated							
Football Field	IRM5-FIS BOT 31	SSHS-IRM5-FIS BOT 31-20210626	SSHS-IRM5-FIS BOT 31	6/26/2021	-	854.66	-	846.62	8 - 10 ft	8.04 ft	1801237631	Not Excavated							
Football Field	IRM5-FIS BOT 32	SSHS-IRM5-FIS BOT 32-20210626	SSHS-IRM5-FIS BOT 32	6/26/2021	-	854.67	-	846.14	8 - 10 ft	8.53 ft	1801237631	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0068 U	< 0.0025 U	< 0.0052 U	< 0.0041 U	< 0.0044 U	< 0.0040 U	< 0.0070 U	< 0.0035 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0058 U	< 0.0021 U	< 0.0045 U	< 0.0035 U	< 0.0037 U	< 0.0034 U	< 0.0059 U	< 0.0030 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0066 U	< 0.0024 U	< 0.0051 U	< 0.0040 U	< 0.0043 U	< 0.0039 U	< 0.0068 U	< 0.0035 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0060 U	< 0.0022 U	< 0.0046 U	< 0.0036 U	< 0.0039 U	< 0.0035 U	< 0.0062 U	< 0.0031 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0034 U	< 0.0036 U	< 0.0033 U	< 0.0058 U	< 0.0029 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated								
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0027 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0025 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated								
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated								
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	0.008 J	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0036 U	< 0.0039 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0041 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.0049	< 0.00066	< 0.00067	< 0.00055	< 0.00043	< 0.00072	< 0.0005	< 0.00044
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.023	< 0.0058		< 0.0058	< 0.0058	< 0.0058	< 0.012	< 0.0058
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.0094 U	< 0.00042 U	< 0.00046 U	< 0.00042 U	< 0.00070 U	< 0.0016 UT	< 0.00044 U	< 0.00064 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 UT	< 0.00034 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.01	< 0.003	< 0.0014	< 0.002	< 0.0045	< 0.0017	< 0.0021	< 0.0013
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated						
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated						
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated						
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated						
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0043 U	< 0.0051 U	< 0.0028 U	< 0.0034 U	< 0.0042 U	< 0.0056 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0019 U	< 0.0037 U	< 0.0043 U	< 0.0024 U	< 0.0029 U	< 0.0035 U	< 0.0048 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0042 U	< 0.0050 U	< 0.0027 U	< 0.0034 U	< 0.0041 U	< 0.0055 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0020 U	< 0.0038 U	< 0.0045 U	< 0.0025 U	< 0.0031 U	< 0.0037 U	< 0.0050 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0019 U	< 0.0036 U	< 0.0042 U	< 0.0023 U	< 0.0029 U	< 0.0035 U	< 0.0047 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated							
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	0.0021 J	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated							
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated							
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0019 U	< 0.0028 U	< 0.0031 U	< 0.0025 U	< 0.0046 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.00074	< 0.00069	< 0.0015	< 0.00057	< 0.00083	< 0.00036	< 0.00073
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated							
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058		
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.00029 U	< 0.00032 U	< 0.00086 U	< 0.0016 U	< 0.00071 U	< 0.00036 U	< 0.00076 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 UT	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 UT	< 0.00020 U	< 0.00041 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.0022	< 0.0024	< 0.0021	< 0.0012	< 0.0026	< 0.0015	< 0.0045
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0079 U	< 0.0024 U	< 0.0043 U	< 0.0029 U	< 0.0054 U	< 0.0026 U	< 0.0028 U	< 0.0025 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0067 U	< 0.0020 U	< 0.0037 U	< 0.0025 U	< 0.0046 U	< 0.0022 U	< 0.0024 U	< 0.0021 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0077 U	< 0.0023 U	< 0.0042 U	< 0.0029 U	< 0.0052 U	< 0.0026 U	< 0.0027 U	< 0.0025 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0070 U	< 0.0021 U	< 0.0038 U	< 0.0026 U	< 0.0048 U	< 0.0023 U	< 0.0025 U	< 0.0022 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0065 U	< 0.0020 U	< 0.0036 U	< 0.0024 U	< 0.0045 U	< 0.0022 U	< 0.0023 U	< 0.0021 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated								
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0038 U	< 0.0018 U	< 0.0019 U	< 0.0018 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated								
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated								
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0028 U	< 0.0032 U	< 0.0035 U	< 0.0048 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.00066	< 0.00084	< 0.00065	< 0.00078	< 0.00064	< 0.00062	< 0.00056	< 0.0006
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058			< 0.38	< 0.38	< 0.38	< 0.0058	< 0.0058
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.0019 U	< 0.00030 U	< 0.00056 U	< 0.00059 U	< 0.00060 U	< 0.00037 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.0012 UT	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	0.0049	< 0.0021	< 0.0029	< 0.0032	< 0.0029	< 0.0029	< 0.0011	< 0.0011
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0039 U	< 0.0071 U	< 0.0026 U	< 0.0030 U	< 0.0023 U	< 0.0038 U	< 0.0039 U	< 0.0032 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0061 U	< 0.0022 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0033 U	< 0.0027 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0038 U	< 0.0069 U	< 0.0026 U	< 0.0030 U	< 0.0023 U	< 0.0038 U	< 0.0038 U	< 0.0031 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0035 U	< 0.0063 U	< 0.0023 U	< 0.0027 U	< 0.0021 U	< 0.0034 U	< 0.0035 U	< 0.0029 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0033 U	< 0.0059 U	< 0.0022 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0033 U	< 0.0027 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated								
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0030 U	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated								
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated								
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U	< 0.0025 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.00083		< 0.00069	< 0.00058	< 0.00053	< 0.00066	< 0.00058	< 0.00063
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058		< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058	< 0.0058
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.00040 U	< 0.00069 U	< 0.00045 U	< 0.00044 U	< 0.00033 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.0014	< 0.0023	< 0.0013	< 0.001	< 0.0018	< 0.0022	< 0.0024	< 0.002
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 UJ	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated								
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated								
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0035 U	< 0.0027 U	< 0.0045 U	< 0.013 U	< 0.0042 U	< 0.0044 U	< 0.0032 U	< 0.0026 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0030 U	< 0.0023 U	< 0.0039 U	< 0.011 U	< 0.0036 U	< 0.0038 U	< 0.0027 U	< 0.0022 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0034 U	< 0.0027 U	< 0.0044 U	< 0.013 U	< 0.0041 U	< 0.0043 U	< 0.0031 U	< 0.0025 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0031 U	< 0.0024 U	< 0.0040 U	< 0.011 U	< 0.0037 U	< 0.0039 U	< 0.0028 U	< 0.0023 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0029 U	< 0.0023 U	< 0.0038 U	< 0.011 U	< 0.0035 U	< 0.0037 U	< 0.0026 U	< 0.0021 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated								
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated								
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated								
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0024 U	< 0.0019 UT	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 UT	< 0.0022 UT	< 0.0018 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0096 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0028 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated								
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated								
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0023 U	< 0.005 U	< 0.0027 U	< 0.007 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0044 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.001	< 0.00067	< 0.00066	< 0.00088	< 0.00071	< 0.00086	< 0.00064	< 0.00073
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.012				< 0.012	< 0.012	
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.00049 U	< 0.0028 U	< 0.00047 U	< 0.0071 U	< 0.00082 U	< 0.00060 U	< 0.0026 UT	< 0.00084 UT
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.0014	< 0.004	< 0.0034	< 0.013	< 0.0018	< 0.0029	< 0.0035	< 0.0025
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated						
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated						
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated						
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated						
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0026 U	< 0.0026 U	< 0.0035 U	< 0.0025 U	< 0.0048 U	< 0.0044 U	< 0.0029 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0030 U	< 0.0021 U	< 0.0041 U	< 0.0038 U	< 0.0025 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0026 U	< 0.0026 U	< 0.0034 U	< 0.0025 U	< 0.0047 U	< 0.0043 U	< 0.0028 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0023 U	< 0.0023 U	< 0.0031 U	< 0.0022 U	< 0.0042 U	< 0.0039 U	< 0.0026 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0022 U	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0040 U	< 0.0037 U	< 0.0024 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated							
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0024 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated							
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated							
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0024 U	< 0.0019 U	< 0.003 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.00069	< 0.0007	< 0.00066	< 0.00071	< 0.00083	< 0.00086	< 0.00048
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated							
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.0058	< 0.0058		< 0.38	< 0.0058
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.00046 U	< 0.00035 U	< 0.00050 U	< 0.00038 U	< 0.00030 U	< 0.00059 U	< 0.00038 U
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00028 J	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.00025 U	< 0.00019 UT	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.0023	< 0.0039	< 0.0012	< 0.0036	< 0.004	< 0.004	< 0.0011
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	IRM5-FIS-S248	SSHS-IRM5-FIS S248-20210720	SSHS-IRM5-FIS S248	7/20/2021	-	854.75	-	846.48	8 - 10 ft	8.27 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S258	SSHS-IRM5-FIS S258-20210720	SSHS-IRM5-FIS S258	7/20/2021	-	854.93	-	846.68	8 - 10 ft	8.25 ft	1801247161	Not Excavated							
Football Field	IRM5-FIS-S322	SSHS-IRM5-FIS S322-20210821	SSHS-IRM5-FIS S322	8/21/2021	-	--	-	846.27	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated							
Football Field	IRM5-FIS-S323	SSHS-IRM5-FIS S323-20210821	SSHS-IRM5-FIS S323	8/21/2021	-	--	-	844.28	8 - 10 ft	8 - 10 ft	1801261004	Not Excavated							
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2-20210829	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3-20210829	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21-20210829	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26-20210829	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30-20210829	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated							
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2V-20210830	SSHS-ISMP-CB-7 BOT 2V	8/30/2021	-	855.69	-	847.83	8 - 10 ft	7.86 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0072 U	< 0.0063 U	< 0.0031 U	< 0.0035 U	< 0.013 U
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26V-20210830	SSHS-ISMP-CB-7 S26V	8/30/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264191	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0062 U	< 0.0053 U	< 0.0026 U	< 0.0030 U	< 0.011 U
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21V-20210830	SSHS-ISMP-CB-7 S21V	8/30/2021	-	856.17	-	846.77	8 - 10 ft	9.4 ft	1801264191	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0071 U	< 0.0061 U	< 0.0030 U	< 0.0034 U	< 0.012 U
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3V-20210830	SSHS-ISMP-CB-7 BOT 3V	8/30/2021	-	856.29	-	847.50	8 - 10 ft	8.79 ft	1801264191	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0064 U	< 0.0056 U	< 0.0027 U	< 0.0031 U	< 0.011 U
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30V-20210830	SSHS-ISMP-CB-7 S30V	8/30/2021	-	856.30	-	847.19	8 - 10 ft	9.11 ft	1801264191	Not Excavated	< 0.0014 U	< 0.0023 U	< 0.0060 U	< 0.0052 U	< 0.0026 U	< 0.0029 U	< 0.01 U
Football Field	IRM5-FIS-324A	SSHS-IRM5-FIS S324A-20210916	SSHS-IRM5-FIS S324A	9/16/2021	-	854.98	-	846.22	8 - 10 ft	8.77 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S331	SSHS-IRM5-FIS S331-20210916	SSHS-IRM5-FIS S331	9/16/2021	-	855.08	-	845.94	8 - 10 ft	9.14 ft	1801271981	Not Excavated							
Football Field	IRM5-FIS-S334	SSHS-IRM5-FIS S334-20210916	SSHS-IRM5-FIS S334	9/16/2021	-	855.14	-	845.62	8 - 10 ft	9.52 ft	1801271982	Not Excavated							
Football Field	SSHS-B4164	092421 10:00 DUP-21	DUP-21	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-8-10	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-8-10	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	IRM5-FIS-S362	SSHS-IRM5-FIS-S362-20211009	SSHS-IRM5-FIS-S362	10/9/2021	-	855.21	-	846.14	8 - 10 ft	9.07 ft	1801283151	Not Excavated							
Football Field	IRM5-B410	SSHS-IRM5-B410-20220106	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 0.0012 U	0.12	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	IRM5-B412	SSHS-IRM5-B412-20220302	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 0.0012 U	0.16	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	ISMP-S706	SSHS-ISMP-S706-20220302	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 0.0012 U	0.0096	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Football Field	IRM5-B404A	SSHS-IRM5-B404A-20220302	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 0.0012 U	0.14	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Football Field	IRM5-B403A	SSHS-IRM5-B403A-20220302	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 0.0013 U	0.01	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Football Field	ISMP-B1000	SSHS-ISMP-B1000-20220308	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B1005	SSHS-ISMP-B1005-20220309	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0011 U	0.0037 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B1006	SSHS-ISMP-B1006-20220309	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-B1007	SSHS-ISMP-B1007-20220309	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1-20220311	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 0.0012 U	0.014	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Football Field	ISMP-B1009	SSHS-ISMP-B1009-20220314	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 0.00091 U	0.022	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Football Field	ISMP-B1010	SSHS-ISMP-B1010-20220314	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 0.00098 U	0.015	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Football Field	ISMP-S2020	SSHS-ISMP-S2020-20220314	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 0.0010 U	0.045	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Football Field	ISMP-S2019	SSHS-ISMP-S2019-20220314	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 0.0011 U	0.0023 J	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Football Field	ISMP-S2018	SSHS-ISMP-S2018-20220314	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 0.00093 U	0.011	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Football Field	ISMP-S2017	SSHS-ISMP-S2017-20220314	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 0.00094 U	0.0048	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	SSHS-B285	SSHS-B285-SUB-0-2	SSHS-B285-SUB-0-2	7/14/2015	856.00	856.42	0.42	-	0 - 2 ft	0.42 - 2.42 ft	180-45961-1	Not Excavated							
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated							
Northern Athletic Field	SSHS-B678	SSHS-B678-SUB-0-2	SSHS-B678-SUB-0-2	3/21/2017	856.07	857.58	1.51	-	0 - 2 ft	1.51-3.51 ft	180-64494-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-0-2	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7-20220311	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305-20230714	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated	< 0.00081	< 0.00064	< 0.0009	< 0.00046		< 0.00076	
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-0.17-2	SSHS-B3273-SUB-0.17-2	12/18/2019	856.15	858.40	2.25	-	0.17 - 2 ft	2.42-4.25 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3512A	011421 08:45 SSHS-B3512-SUB-0.17-2	SSHS-B3512-SUB-0.17-2	1/13/2021	856.63	857.09	0.46	-	0.17 - 2 ft	0.63-2.46 ft	180-115927-1	Not Excavated							
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-0.17-2	SSHS-B3607-SUB-0.17-2	1/25/2021	855.19	857.92	2.73	-	0.17 - 2 ft	2.9-4.73 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-0.17-2	SSHS-B3611-SUB-0.17-2	1/25/2021	856.16	858.07	1.91	-	0.17 - 2 ft	2.08-3.91 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2-20210126	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B48	13 SEP 00B48 0.5-2.5	B48-0.5-2.5	9/13/2000	855.11	855.12	0.01	-	0.5 - 2.5 ft	0.51-2.51 ft	NA	Not Excavated	< 0.0058	< 0.0058	< 0.0058	< 0.0058		< 0.0058	
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2-20221110	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated	< 0.00029 U	< 0.00053 U	< 0.00067 UT	< 0.00090 U	0.00042 J	< 0.00032 U	0.00042 J
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2-20221110	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2-20231120	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217-20221114	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A-20221115	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 UT	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated	< 0.0028	< 0.0011	< 0.0029	< 0.0025		< 0.0029	< 0.0045
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-10-12	SSHS-B2024-SUB-10-12	7/26/2018	852.76	854.11	1.35	-	10 - 12 ft	11.35-13.35 ft	180-80225-2	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-10-12	SSHS-B2030-SUB-10-12	7/27/2018	856.20	856.42	0.22	-	10 - 12 ft	10.22-12.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-10-12	SSHS-B3008-SUB-10-12	8/26/2019	852.37	854.67	2.30	-	10 - 12 ft	12.3-14.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-10-12	082719 09:30 SSHS-B3021-SUB-10-12	8/26/2019	853.71	855.73	2.02	-	10 - 12 ft	12.02-14.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-10-12	SSHS-B3022-SUB-10-12	8/26/2019	853.76	855.66	1.90	-	10 - 12 ft	11.9-13.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-10-12	SSHS-B3034-SUB-10-12	8/26/2019	855.10	856.53	1.43	-	10 - 12 ft	11.43-13.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-10-12	SSHS-B3035-SUB-10-12	8/26/2019	854.81	856.27	1.46	-	10 - 12 ft	11.46-13.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-10-12	SSHS-B3049-SUB-10-12	8/26/2019	856.17	857.50	1.33	-	10 - 12 ft	11.33-13.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-10-12	SSHS-B3050-SUB-10-12	8/26/2019	855.60	856.84	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94752-1	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-10-12	SSHS-B3064-SUB-10-12	8/26/2019	856.77	857.84	1.07	-	10 - 12 ft	11.07-13.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-10-12	SSHS-B3065-SUB-10-12	8/26/2019	856.77	857.30	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-10-12	SSHS-B3078-SUB-10-12	8/26/2019	856.70	857.12	0.42	-	10 - 12 ft	10.42-12.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-10-12	SSHS-B3098-SUB-10-12	8/26/2019	855.97	857.05	1.08	-	10 - 12 ft	11.08-13.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-10-12	SSHS-B3099-SUB-10-12	8/26/2019	856.40	856.53	0.13	-	10 - 12 ft	10.13-12.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-10-12	SSHS-B3006-SUB-10-12	8/27/2019	852.36	852.39	0.03	-	10 - 12 ft	10.03-12.03 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-10-12	SSHS-B3007-SUB-10-12	8/27/2019	852.58	854.74	2.16	-	10 - 12 ft	12.16-14.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-10-12	SSHS-B3018-SUB-10-12	8/27/2019	853.82	854.59	0.77	-	10 - 12 ft	10.77-12.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-10-12	SSHS-B3019-SUB-10-12	8/27/2019	854.09	855.31	1.22	-	10 - 12 ft	11.22-13.22 ft	180-94824-3	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	0.004 J	< 0.0018 U	< 0.0017 U	< 0.0021 U	< 0.0024 U	< 0.0041 U	< 0.0027 U	< 0.003 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 UJ	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated						

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00093 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	SSHS-B3075	082819 09:00_SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00_SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U	< 0.002 U
Northern Athletic Field	SSHS-B3075	082819 09:00_SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00_SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated								

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-B3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U	< 0.0023 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated						

WORK

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-10-12	SSHS-B3020-SUB-10-12	8/27/2019	853.86	855.74	1.88	-	10 - 12 ft	11.88-13.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-10-12	SSHS-B3031-SUB-10-12	8/27/2019	855.08	855.61	0.53	-	10 - 12 ft	10.53-12.53 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-10-12	SSHS-B3032-SUB-10-12	8/27/2019	855.25	856.15	0.90	-	10 - 12 ft	10.9-12.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-10-12	SSHS-B3033-SUB-10-12	8/27/2019	855.17	856.58	1.41	-	10 - 12 ft	11.41-13.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-10-12	SSHS-B3046-SUB-10-12	8/27/2019	856.22	856.03	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-10-12	SSHS-B3047-SUB-10-12	8/27/2019	856.24	856.75	0.51	-	10 - 12 ft	10.51-12.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-10-12	SSHS-B3048-SUB-10-12	8/27/2019	856.08	857.32	1.24	-	10 - 12 ft	11.24-13.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-10-12	SSHS-B3061-SUB-10-12	8/27/2019	857.02	856.09	-0.93	-	10 - 12 ft	9.07-11.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-10-12	SSHS-B3062-SUB-10-12	8/27/2019	856.91	856.86	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-94819-3	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-10-12	SSHS-B3063-SUB-10-12	8/27/2019	856.95	857.80	0.85	-	10 - 12 ft	10.85-12.85 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-10-12	SSHS-B3074-SUB-10-12	8/27/2019	857.18	856.02	-1.16	-	10 - 12 ft	8.84-10.84 ft	180-94824-2	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-10-12	SSHS-B3075-SUB-10-12	8/27/2019	856.99	856.91	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-10-12	SSHS-B3076-SUB-10-12	8/27/2019	856.92	857.74	0.82	-	10 - 12 ft	10.82-12.82 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-10-12	SSHS-B3096-SUB-10-12	8/27/2019	855.86	856.29	0.43	-	10 - 12 ft	10.43-12.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-10-12	SSHS-B3097-SUB-10-12	8/27/2019	856.19	856.93	0.74	-	10 - 12 ft	10.74-12.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-10-12	SSHS-B3029-SUB-10-12	8/28/2019	854.97	853.59	-1.38	-	10 - 12 ft	8.62-10.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-10-12	SSHS-B3030-SUB-10-12	8/28/2019	855.22	855.02	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-10-12	SSHS-B3043-SUB-10-12	8/28/2019	855.78	856.62	0.84	-	10 - 12 ft	10.84-12.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-10-12	SSHS-B3044-SUB-10-12	8/28/2019	856.00	854.20	-1.80	-	10 - 12 ft	8.2-10.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-10-12	SSHS-B3045-SUB-10-12	8/28/2019	856.03	855.07	-0.96	-	10 - 12 ft	9.04-11.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-10-12	SSHS-B3057-SUB-10-12	8/28/2019	856.09	857.58	1.49	-	10 - 12 ft	11.49-13.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-10-12	SSHS-B3058-SUB-10-12	8/28/2019	856.47	856.55	0.08	-	10 - 12 ft	10.08-12.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-10-12	SSHS-B3059-SUB-10-12	8/28/2019	856.71	854.42	-2.29	-	10 - 12 ft	7.71-9.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-10-12	SSHS-S3060-SUB-10-12	8/28/2019	856.96	855.38	-1.58	-	10 - 12 ft	8.42-10.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-10-12	SSHS-B3070-SUB-10-12	8/28/2019	856.51	857.05	0.54	-	10 - 12 ft	10.54-12.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-10-12	SSHS-B3071-SUB-10-12	8/28/2019	856.76	856.63	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-10-12	SSHS-B3072-SUB-10-12	8/28/2019	856.89	856.00	-0.89	-	10 - 12 ft	9.11-11.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-10-12	SSHS-B3073-SUB-10-12	8/28/2019	857.14	855.25	-1.89	-	10 - 12 ft	8.11-10.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-10-12	SSHS-B3095-SUB-10-12	8/28/2019	857.12	856.70	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-10-12	SSHS-B3004-SUB-10-12	8/29/2019	852.25	853.25	1.00	-	10 - 12 ft	11-13 ft	180-94981-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-10-12	SSHS-B3005-SUB-10-12	8/29/2019	852.31	852.62	0.31	-	10 - 12 ft	10.31-12.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-10-12	SSHS-B3026-SUB-10-12	8/29/2019	854.13	857.81	3.68	-	10 - 12 ft	13.68-15.68 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-10-12	SSHS-B3040-SUB-10-12	8/29/2019	855.10	858.65	3.55	-	10 - 12 ft	13.55-15.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-10-12	SSHS-B3041-SUB-10-12	8/29/2019	855.17	858.67	3.50	-	10 - 12 ft	13.5-15.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-10-12	SSHS-B3054-SUB-10-12	8/29/2019	856.01	856.77	0.76	-	10 - 12 ft	10.76-12.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-10-12	SSHS-B3055-SUB-10-12	8/29/2019	856.20	858.70	2.50	-	10 - 12 ft	12.5-14.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-10-12	SSHS-B3056-SUB-10-12	8/29/2019	855.88	858.82	2.94	-	10 - 12 ft	12.94-14.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-10-12	SSHS-B3069-SUB-10-12	8/29/2019	855.92	856.73	0.81	-	10 - 12 ft	10.81-12.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-10-12	SSHS-B3079-SUB-10-12	8/29/2019	856.36	857.37	1.01	-	10 - 12 ft	11.01-13.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-10-12	SSHS-B3083-SUB-10-12	8/29/2019	857.13	857.39	0.26	-	10 - 12 ft	10.26-12.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-10-12	SSHS-B3084-SUB-10-12	8/29/2019	856.55	857.05	0.50	-	10 - 12 ft	10.5-12.5 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-10-12	SSHS-B3181-SUB-10-12	8/29/2019	857.57	857.81	0.24	-	10 - 12 ft	10.24-12.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-10-12	SSHS-B3182-SUB-10-12	8/29/2019	857.45	857.88	0.43	-	10 - 12 ft	10.43-12.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-10-12	SSHS-B3223-SUB-10-12	8/29/2019	858.27	858.28	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-10-12	SSHS-B3003-SUB-10-12	8/30/2019	851.95	852.83	0.88	-	10 - 12 ft	10.88-12.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-10-12	SSHS-B3011-SUB-10-12	8/30/2019	853.85	854.62	0.77	-	10 - 12 ft	10.77-12.77 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-10-12	SSHS-B3025-SUB-10-12	8/30/2019	854.59	855.82	1.23	-	10 - 12 ft	11.23-13.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-10-12	SSHS-B3039-SUB-10-12	8/30/2019	855.85	856.37	0.52	-	10 - 12 ft	10.52-12.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-10-12	SSHS-B3068-SUB-10-12	8/30/2019	856.38	856.82	0.44	-	10 - 12 ft	10.44-12.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-10-12	SSHS-B3082-SUB-10-12	8/30/2019	856.73	857.22	0.49	-	10 - 12 ft	10.49-12.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-10-12	SSHS-B3087-SUB-10-12	8/30/2019	857.68	857.65	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-10-12	SSHS-B3214-SUB-10-12	8/30/2019	855.06	855.25	0.19	-	10 - 12 ft	10.19-12.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-10-12	SSHS-B3222-SUB-10-12	8/30/2019	858.28	858.08	-0.20	-	10 - 12 ft	9.8-11.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-10-12	SSHS-B3224-SUB-10-12	8/30/2019	858.38	858.48	0.10	-	10 - 12 ft	10.1-12.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-10-12	SSHS-B3001-SUB-10-12	9/3/2019	855.74	853.44	-2.30	-	10 - 12 ft	10.09-12.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-10-12	SSHS-B3002-SUB-10-12	9/3/2019	853.09	853.12	0.03	-	10 - 12 ft	10.03-12.03 ft	180-95155-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-10-12	SSHS-B3009-SUB-10-12	9/3/2019	853.88	854.29	0.41	-	10 - 12 ft	10.41-12.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-10-12	SSHS-B3010-SUB-10-12	9/3/2019	854.13	854.48	0.35	-	10 - 12 ft	10.35-12.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-10-12	SSHS-B3023-SUB-10-12	9/3/2019	854.48	854.90	0.42	-	10 - 12 ft	10.42-12.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-10-12	SSHS-B3024-SUB-10-12	9/3/2019	855.00	855.16	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-10-12	SSHS-B3036-SUB-10-12	9/3/2019	855.09	855.21	0.12	-	10 - 12 ft	10.12-12.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-10-12	SSHS-B3038-SUB-10-12	9/3/2019	855.76	855.72	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-10-12	SSHS-B3052-SUB-10-12	9/3/2019	855.98	855.94	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-10-12	SSHS-B3053-SUB-10-12	9/3/2019	856.41	856.22	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-10-12	SSHS-B3067-SUB-10-12	9/3/2019	856.40	856.48	0.08	-	10 - 12 ft	10.08-12.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-10-12	SSHS-B3051-SUB-10-12	9/4/2019	855.15	855.32	0.17	-	10 - 12 ft	10.17-12.17 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-10-12	SSHS-B3066-SUB-10-12	9/4/2019	855.86	856.02	0.16	-	10 - 12 ft	10.16-12.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-10-12	SSHS-B3080-SUB-10-12	9/4/2019	856.58	856.76	0.18	-	10 - 12 ft	10.18-12.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-10-12	SSHS-B3081-SUB-10-12	9/4/2019	856.96	857.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-10-12	SSHS-B3085-SUB-10-12	9/4/2019	857.12	857.26	0.14	-	10 - 12 ft	10.14-12.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-10-12	SSHS-B3086-SUB-10-12	9/4/2019	857.77	857.49	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-10-12	SSHS-B3220-SUB-10-12	9/4/2019	857.44	857.92	0.48	-	10 - 12 ft	10.48-12.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-10-12	SSHS-B3221-SUB-10-12	9/4/2019	857.92	857.93	0.01	-	10 - 12 ft	10.01-12.01 ft	180-95165-3	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.26 U	< 0.095 U	< 0.2 U	< 0.16 U	< 0.17 U	< 0.15 U	< 0.27 U	< 0.14 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	0.015 J	< 0.00049 U	< 0.00059 U	< 0.0004 U	< 0.0049 U	< 0.00069 U	< 0.00059 U	< 0.00049 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.0062 U	< 0.00052 U	< 0.00062 U	< 0.00041 U	< 0.0052 U	< 0.00073 U	< 0.00062 U	< 0.00052 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	0.13	< 0.00064 U	< 0.00077 U	< 0.00051 U	< 0.0064 U	< 0.0009 U	< 0.00077 U	< 0.00064 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.0063 U	< 0.00052 U	< 0.00063 U	< 0.00042 U	< 0.0052 U	< 0.00073 U	< 0.00063 U	< 0.00052 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.0036 U	< 0.00021 U	< 0.00031 U	< 0.00057 U	< 0.0021 U	< 0.00038 U	< 0.0021 U	< 0.00041 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	0.012 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	0.018 J	0.00039 J	< 0.0003 U	< 0.00055 U	< 0.0021 U	< 0.00037 U	< 0.0021 U	< 0.0004 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.018 U	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.001 U	< 0.0029 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.017 U	< 0.00056 U	< 0.001 U	< 0.0012 U	< 0.0019 U	< 0.0033 U	< 0.00094 U	< 0.0026 U
Northern Athletic Field	B555	110421 09:45_SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated								
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated								
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.02 UT	< 0.00065 U	< 0.0012 U	< 0.0014 U	< 0.0022 U	< 0.0039 U	< 0.0011 U	< 0.0030 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.021 UT	< 0.00069 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0041 U	< 0.0011 U	< 0.0032 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0036 UT	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0040 UT	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0039 UT	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.0039 UT	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated								
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 UT	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00056 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated								
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated								
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	0.015	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.088 U	< 0.17 U	< 0.2 U	< 0.11 U	< 0.13 U	< 0.16 U	< 0.22 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated						
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	< 0.00049 U	< 0.00049 U	< 0.00099 U	< 0.00059 U	< 0.00059 U	< 0.00049 U	< 0.00049 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00062 U	< 0.00062 U	< 0.00052 U	< 0.00052 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	< 0.00064 U	< 0.00064 U	< 0.0013 U	< 0.00077 U	< 0.00077 U	< 0.00064 U	< 0.00064 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00063 U	< 0.00063 U	< 0.00052 U	< 0.00052 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.00056 U	< 0.00054 U	< 0.00096 U	< 0.00026 U	< 0.00026 U	< 0.00059 U	< 0.0021 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.00064 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.00054 U	< 0.00053 U	< 0.00093 U	< 0.00025 U	< 0.00025 U	0.00063 J	< 0.0021 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.0008 U	< 0.0024 U	< 0.0024 U	< 0.00069 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.00074 U	< 0.0022 U	< 0.0022 U	< 0.00063 U	< 0.0018 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	B555	110421 09:45_SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated						
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated						
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated						
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated						
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.00085 U	< 0.0026 U	< 0.0025 U	< 0.00073 U	< 0.0021 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.00090 U	< 0.0027 U	< 0.0027 U	< 0.00078 U	< 0.0022 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0037 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated						
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	0.0017 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 UT	0.0017 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.000098 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated							
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated							
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated							
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated							
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.3 U	< 0.092 U	< 0.17 U	< 0.11 U	< 0.21 U	< 0.1 U	< 0.11 U	< 0.097 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	< 0.002 U	< 0.0004 U	< 0.00059 U	< 0.00049 U	< 0.00049 U	< 0.0004 U	< 0.00049 U	< 0.00059 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00041 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00062 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	< 0.0026 U	< 0.00051 U	< 0.00077 U	< 0.00064 U	< 0.00064 U	< 0.00051 U	< 0.00064 U	< 0.00077 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00042 U	< 0.00063 U	< 0.00052 U	< 0.00052 U	< 0.00042 U	< 0.00052 U	< 0.00063 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.00055 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00059 U	< 0.00052 U	< 0.00021 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.00024 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.0019 U	< 0.00053 U	< 0.00034 U	< 0.00032 U	< 0.00021 U	< 0.00058 U	< 0.0005 U	< 0.00021 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00067 U	< 0.00083 U	< 0.00097 U	< 0.00072 U	< 0.00077 U	< 0.00061 U	< 0.00068 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.0096 U	< 0.00062 U	< 0.00076 U	< 0.00089 U	< 0.00066 U	< 0.00071 U	< 0.00056 U	< 0.00062 U
Northern Athletic Field	B555	110421 09:45_SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated								
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated								
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.011 UT	< 0.00072 U	< 0.00088 U	< 0.0010 U	< 0.00076 U	< 0.00082 U	< 0.00064 U	< 0.00072 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.012 UT	< 0.00076 U	< 0.00093 U	< 0.0011 U	< 0.00080 U	< 0.00087 U	< 0.00068 U	< 0.00076 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated								
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0049 UT	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.00064 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00013 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated								
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated								
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.00071 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.15 U	< 0.27 U	< 0.1 U	< 0.12 U	< 0.09 U	< 0.15 U	< 0.15 U	< 0.12 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	< 0.00049 U	< 0.00099 U	< 0.00049 U	< 0.00049 U	< 0.00049 U	< 0.0004 U	< 0.00049 U	< 0.0004 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00041 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	< 0.00064 U	< 0.0013 U	< 0.00064 U	< 0.00064 U	< 0.00064 U	< 0.00051 U	< 0.00064 U	< 0.00051 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00042 U	< 0.00052 U	< 0.00042 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.00052 U	< 0.0022 U	< 0.00054 U	< 0.00044 U	< 0.0021 U	< 0.00061 U	< 0.0019 U	< 0.00029 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.0005 U	< 0.034 U	< 0.0007 U	< 0.0021 U	< 0.00034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.0005 U	< 0.0022 U	< 0.00053 U	< 0.00043 U	< 0.0021 U	< 0.00059 U	< 0.0018 U	< 0.00028 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0012 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00092 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.0015 U	< 0.0009 U	< 0.0012 U	< 0.0011 U	< 0.00068 U	< 0.0023 U	< 0.003 U	< 0.00084 U
Northern Athletic Field	B555	110421 09:45_SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated								
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated								
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0014 U	< 0.0013 U	< 0.00079 U	< 0.0027 U	< 0.0034 U	< 0.00097 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00084 U	< 0.0028 U	< 0.0037 U	< 0.0010 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated								
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 UT	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 UT	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated								
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated								
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.13 U	< 0.11 U	< 0.18 U	< 0.5 U	< 0.16 U	< 0.17 U	< 0.12 U	< 0.099 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	< 0.00059 U	< 0.00099 U	< 0.0004 U	< 0.00099 U	< 0.00059 U	< 0.002 U	< 0.00099 U	< 0.00049 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.001 U	< 0.00062 U	< 0.0021 U	< 0.001 U	< 0.00052 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	< 0.00077 U	< 0.0013 U	< 0.00051 U	0.042	< 0.00077 U	0.0056 J	< 0.0013 U	< 0.00064 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.00063 U	< 0.001 U	< 0.00042 U	< 0.001 U	< 0.00063 U	< 0.0021 U	< 0.001 U	< 0.00052 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.00097 U	< 0.0021 U	< 0.00064 U	< 0.0026 U	< 0.00065 U	< 0.0016 U	< 0.0014 U	< 0.00042 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00088 J	< 0.034 U	< 0.0016 U	< 0.00048 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.00094 U	< 0.0021 U	< 0.00062 U	< 0.0025 U	0.0013 J	< 0.0015 U	< 0.0014 U	< 0.0004 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.003 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0017 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0033 U	< 0.0015 U	< 0.0027 U	< 0.00099 U	< 0.0029 U	< 0.003 U	< 0.0016 U
Northern Athletic Field	B555	110421 09:45_SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated								
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated								
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated								
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.0012 U	< 0.0038 U	< 0.0018 U	< 0.0032 U	< 0.0011 U	< 0.0033 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.0013 U	< 0.0040 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0035 U	< 0.0037 U	< 0.0020 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 UT
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 UT
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 UT
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 UT
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated								
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.00017 U	< 0.00095 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00020 U	< 0.00086 U	< 0.00028 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated								
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated								
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0026 U	< 0.00031 U	< 0.00023 U	< 0.00096 U	< 0.00032 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3455	012721 08:30 SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.1 U	< 0.1 U	< 0.14 U	< 0.097 U	< 0.19 U	< 0.17 U	< 0.11 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated						
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	< 0.0004 U	< 0.0004 U	< 0.00049 U	< 0.00059 U	< 0.0049 U	< 0.0049 U	< 0.00059 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.00041 U	< 0.00041 U	0.00066 J	< 0.00062 U	< 0.0052 U	< 0.0052 U	< 0.00062 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	< 0.00051 U	< 0.00051 U	< 0.00064 U	< 0.00077 U	< 0.0064 U	< 0.0064 U	< 0.00077 U
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.00042 U	< 0.00042 U	0.00074 J	< 0.00063 U	< 0.0052 U	< 0.0052 U	< 0.00063 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.00021 U	< 0.00069 U	< 0.00057 U	< 0.00032 U	< 0.00045 U	< 0.00026 U	< 0.00031 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.00024 U	< 0.034 U	< 0.00065 U	0.0009 J	< 0.034 U	< 0.0003 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.00021 U	< 0.00067 U	< 0.00055 U	0.00079 J	< 0.00044 U	< 0.00025 U	< 0.0003 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.00093 U	< 0.0012 U	0.00068 J	< 0.00062 U	< 0.0024 U	< 0.002 U	< 0.0014 U
Northern Athletic Field	B555	110421 09:45 SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated						
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated						
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated						
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated						
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0013 U	< 0.00068 U	< 0.00072 U	< 0.0027 U	< 0.0023 U	< 0.0016 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.00072 U	< 0.00076 U	< 0.0029 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated						
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	0.00019 J	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated						
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated						
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated						
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated						
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated						
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U

DRAFT

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-10-12	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-10-12	SSHS-B3100-SUB-10-12	1/13/2020	856.74	856.68	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-10-12	SSHS-B3101-SUB-10-12	1/13/2020	856.75	856.69	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-10-12	SSHS-B3102-SUB-10-12	1/13/2020	856.74	856.23	-0.51	-	10 - 12 ft	9.49-11.49 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-10-12	SSHS-B3104-SUB-10-12	1/13/2020	856.82	856.64	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-10-12	SSHS-B3105-SUB-10-12	1/14/2020	856.73	856.62	-0.11	-	10 - 12 ft	9.89-11.89 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-10-12	SSHS-B3106-SUB-10-12	1/14/2020	856.72	856.30	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-10-12	SSHS-B3108-SUB-10-12	1/14/2020	857.55	856.76	-0.79	-	10 - 12 ft	9.21-11.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-10-12	SSHS-B3113-SUB-10-12	1/14/2020	856.36	856.08	-0.28	-	10 - 12 ft	9.72-11.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-10-12	SSHS-B3117-SUB-10-12	1/14/2020	856.54	856.53	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-10-12	SSHS-B3183-SUB-10-12	1/14/2020	856.70	855.84	-0.86	-	10 - 12 ft	9.14-11.14 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-10-12	SSHS-B3184-SUB-10-12	1/14/2020	856.85	855.95	-0.90	-	10 - 12 ft	9.1-11.1 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-10-12	SSHS-B3107-SUB-10-12	1/15/2020	857.05	857.26	0.21	-	10 - 12 ft	10.21-12.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-10-12	SSHS-B3109-SUB-10-12	1/15/2020	857.26	856.77	-0.49	-	10 - 12 ft	9.51-11.51 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-10-12	SSHS-B3110-SUB-10-12	1/15/2020	856.32	856.06	-0.26	-	10 - 12 ft	9.74-11.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-10-12	SSHS-B3111-SUB-10-12	1/15/2020	857.08	857.00	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-10-12	SSHS-B3112-SUB-10-12	1/15/2020	856.71	856.67	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-10-12	SSHS-B3116-SUB-10-12	1/15/2020	856.51	856.63	0.12	-	10 - 12 ft	10.12-12.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-10-12	SSHS-B3118-SUB-10-12	1/15/2020	856.74	856.72	-0.02	-	10 - 12 ft	9.98-11.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-10-12	SSHS-B3455-SUB-10-12	1/23/2021	853.86	856.33	2.47	-	10 - 12 ft	12.47-14.47 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-10-12	SSHS-B3247A-SUB-10-12	1/26/2021	857.58	857.70	0.12	-	10 - 12 ft	10.12-12.12 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-10-12	SSHS-B3637-SUB-10-12	1/26/2021	857.63	857.60	-0.03	-	10 - 12 ft	9.97-11.97 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-10-12	SSHS-B3638-SUB-10-12	1/26/2021	857.95	857.95	0.00	-	10 - 12 ft	10-12 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12-20210511	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	0.0038 J	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-10-12	SSHS-B3918-SUB-10-12	5/12/2021	854.82	854.84	0.02	-	10 - 12 ft	10.02-12.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12-20210517	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12-20210518	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.067 U	< 0.11 U	< 0.28 U	< 0.24 U	< 0.12 U	< 0.14 U	< 0.49 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-10-12	SSHS-B3017A-SUB-10-12	6/17/2021	853.79	853.15	-0.64	-	10 - 12 ft	9.36-11.36 ft	180-123398-1	Not Excavated							
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-10-12	SSHS-B3931-SUB-10-12	6/17/2021	856.63	855.62	-1.01	-	10 - 12 ft	8.99-10.99 ft	180-123399-1	Not Excavated	< 0.00049 U	< 0.00049 U	< 0.00069 U	< 0.00059 U	< 0.00099 U	< 0.0004 U	< 0.0014 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-10-12	SSHS-B3932-SUB-10-12	6/17/2021	857.09	855.85	-1.24	-	10 - 12 ft	8.76-10.76 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.00073 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.0015 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-10-12	SSHS-B3933-SUB-10-12	6/17/2021	856.55	855.68	-0.87	-	10 - 12 ft	9.13-11.13 ft	180-123399-1	Not Excavated	< 0.00064 U	< 0.00064 U	< 0.0009 U	< 0.00077 U	< 0.0013 U	< 0.00051 U	< 0.0018 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-10-12	SSHS-B3934-SUB-10-12	6/17/2021	856.72	855.95	-0.77	-	10 - 12 ft	9.23-11.23 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.00073 U	< 0.00063 U	< 0.001 U	< 0.00042 U	< 0.0015 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-10-12	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated	< 0.00055 U	< 0.00093 U	< 0.0004 U	< 0.00052 U	< 0.00071 U	< 0.00055 U	< 0.00071 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-10-12	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0011 J	< 0.034 U	0.0011 J
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-10-12	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.00054 U	0.0012 J	< 0.00039 U	< 0.0005 U	< 0.00069 U	< 0.00054 U	< 0.00069 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-10-12	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated	< 0.00099 U	< 0.00055 U	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00075 U	< 0.0014 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-10-12	SSHS-B4264-SUB-10-12	11/1/2021	852.29	853.31	1.02	-	10 - 12 ft	11.02-13.02 ft	180-129325-1	Not Excavated	< 0.00091 U	0.0019 J	< 0.0022 U	< 0.0014 U	< 0.00063 U	< 0.00069 U	< 0.0013 U
Northern Athletic Field	B555	110421 09:45_SSHS-IRM5A2-B555	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	180-129463-2	Not Excavated							
Northern Athletic Field	B555	SSHS-IRM5A2-DUP10-20211103	SSHS-IRM5A2-DUP10	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294633	Not Excavated							
Northern Athletic Field	B561	SSHS-IRM5A2-B561-20211103	SSHS-IRM5A2-B561	11/3/2021	-	857.59	-	847.21	10 - 12 ft	10.38 ft	1801294632	Not Excavated							
Northern Athletic Field	B556	SSHS-IRM5A2-B556-20211103	SSHS-IRM5A2-B556	11/3/2021	-	857.76	-	847.22	10 - 12 ft	10.54 ft	1801294632	Not Excavated							
Northern Athletic Field	B555	SSHS-IRM5A2-B555-20211103	SSHS-IRM5A2-B555	11/3/2021	-	857.89	-	847.57	10 - 12 ft	10.32 ft	1801294632	Not Excavated							
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14-20211106	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated							
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A-20211106	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated							
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT-20211106	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated							
Northern Athletic Field	DW2-BOT1B	SSHS-IRM5A2-DW2-BOT1B-20211108	SSHS-IRM5A2-DW2-BOT1B	11/8/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 0.0011 U	< 0.00059 U	< 0.0025 U	< 0.0016 U	< 0.00073 U	< 0.00080 U	< 0.0015 U
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1-20211110	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 0.0011 U	< 0.00062 U	< 0.0027 U	< 0.0017 U	< 0.00077 U	< 0.00085 U	< 0.0016 U
Northern Athletic Field	S598	SSHS-IRM5A2-S598-20220119	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S597	SSHS-IRM5A2-S597-20220119	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S249	SSHS-IRM5A2-S249-20220119	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	S250	SSHS-IRM5A2-S250-20220119	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S251	SSHS-IRM5A2-S251-20220119	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S245	SSHS-IRM5A2-S245-20220208	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 UT	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	S234	SSHS-IRM5A2-S234-20220209	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	S233	SSHS-IRM5A2-S233-20220209	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44-20220210	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	S230	SSHS-IRM5A2-S230-20220210	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	S232	SSHS-IRM5A2-S232-20220210	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	S231	SSHS-IRM5A2-S231-20220210	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585-20220221	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S571	SSHS-IRM5A2-S571-20220303	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220305	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated							
Northern Athletic Field	S573	SSHS-IRM5A2-S573-20220307	SSHS-IRM5A2-S573	3/7/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S584	SSHS-IRM5A2-S584-20220314	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583-20220314	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S582	SSHS-IRM5A2-S582-20220314	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S287	SSHS-IRM5A2-S287-20220318	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 0.000099 U	< 0.00018 U	< 0.00023 U	< 0.00030 U	< 0.000097 U	< 0.00011 U	< 0.00036 U
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220319	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated							
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220319	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated							
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220319	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated							
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220319	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220320	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated							
Northern Athletic Field	S290	SSHS-IRM5A2-S290-20220321	SSHS-IRM5A2-S290	3/21/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354851	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00040 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574-20220321	SSHS-IRM5A2-S574	3/21/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354851	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00075 U

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	0.013	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	0.0071	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.02 U	< 0.00066 U	< 0.0012 U	< 0.0014 U	< 0.0023 U	< 0.0039 U	< 0.0011 U	< 0.0031 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.033 U	< 0.0011 U	< 0.0019 U	< 0.0023 U	< 0.0038 U	< 0.0065 U	< 0.0018 U	< 0.0051 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.0010 U	< 0.0029 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated								
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 UT	< 0.0038 U	< 0.0019 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 UT	< 0.0037 U	< 0.0019 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00046 U	< 0.00012 UT	< 0.00018 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 UT	< 0.00026 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.01 U	< 0.00047 U	< 0.00051 U	< 0.00047 U	< 0.00077 U	< 0.0018 U	< 0.00048 UT	< 0.00070 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.0053 U	< 0.00024 UT	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00047 U	< 0.00013 UT	< 0.00018 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	0.0095	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	0.0078	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	0.064	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 UT	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00031 U	< 0.00074 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.0039 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00069 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00070 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	0.099	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	0.0016	< 0.00032 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	0.011	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.0078 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00058 U	< 0.0014 U	< 0.00036 U	< 0.00053 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	0.018	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	0.0052	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00027 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	0.018	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00068 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	0.0026 J	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	0.00018 J	< 0.00026 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	0.0084	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00086 U	< 0.00023 U	< 0.00033 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.00087 U	< 0.0026 U	< 0.0026 U	< 0.00075 U	< 0.0022 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.0014 U	< 0.0044 U	< 0.0043 U	< 0.0012 U	< 0.0036 U	< 0.0022 U	< 0.0056 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.00070 U	< 0.0020 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	0.0023 J	< 0.0025 U	< 0.0030 U	< 0.0041 UT
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated							
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 UT	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 UT	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0017 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	0.0036 J,B	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.000082 U	< 0.000090 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.00032 U	< 0.00035 U	< 0.00095 U	< 0.0018 U	< 0.00079 U	< 0.00040 U	< 0.00084 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.00016 UT	< 0.00018 UT	< 0.00049 UT	< 0.00090 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.000089 U	< 0.000098 U	< 0.00026 UT	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 UT	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.000084 U	< 0.000092 U	< 0.00025 U	< 0.00046 U	< 0.00021 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 UT	< 0.00090 U	< 0.00040 UT	< 0.00020 U	< 0.00043 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0020 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 UT	< 0.00099 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 UT	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 UT	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00055 UT	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 UT	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 UT	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 UT	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.0015 UT	< 0.0028 UT	< 0.0033 U	0.0039 J	< 0.0022 U	< 0.0027 U	< 0.0037 UT
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0042 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 UT	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0039 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0035 J	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0021 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0020 J	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0019 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0022 J	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00039 U	< 0.00072 U	< 0.00032 U	< 0.00016 U	< 0.00034 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 UT	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 UT	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00012 U	< 0.00014 U	< 0.00037 UT	< 0.00068 U	< 0.00031 U	< 0.00016 U	< 0.00032 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 UT	< 0.00081 U	< 0.00036 U	< 0.00019 U	< 0.00039 UT
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.00024 U	< 0.00027 U	< 0.00071 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00063 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.000097 U	< 0.00011 U	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.00011 U	< 0.00013 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00066 U	< 0.00030 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.000082 U	< 0.000089 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0040 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0031 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0040 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00044 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00030 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.00071 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.011 U	< 0.00073 U	< 0.00090 U	< 0.0011 U	< 0.00078 U	< 0.00084 U	< 0.00066 U	< 0.00073 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.019 U	< 0.0012 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0014 U	< 0.0011 U	< 0.0012 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 U	< 0.00098 U	< 0.00072 U	< 0.00078 U	< 0.00061 U	< 0.00068 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 UT	< 0.0039 UT	< 0.0019 UT	< 0.0020 U	< 0.0018 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated								
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-10-12	SSHS-DW-10 11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-10-12	SSHS-DW-13 14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-10-12	SSHS-DW-7 8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.00053 U	< 0.000083 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000095 U	< 0.00014 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.0021 U	< 0.00033 U	< 0.00062 U	< 0.00066 U	< 0.00066 U	< 0.00041 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.0011 U	< 0.00017 UT	< 0.00031 U	< 0.00034 UT	< 0.00034 UT	< 0.00021 UT	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.00058 U	< 0.000090 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.00054 U	< 0.000085 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000097 U	< 0.00014 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.00083 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.0012 U	< 0.00019 UT	< 0.00036 U	< 0.00038 UT	< 0.00039 UT	< 0.00024 UT	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.0051 U	< 0.0016 UT	< 0.0028 U	< 0.0019 UT	< 0.0035 UT	< 0.0017 UT	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00085 U	< 0.00013 U	< 0.00025 U	< 0.00027 U	< 0.00027 U	< 0.00017 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.00079 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00081 U	< 0.00013 U	< 0.00024 U	< 0.00025 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 UT	< 0.00031 UT	< 0.00019 UT	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.0022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00046 U	< 0.00049 U	< 0.00050 U	< 0.00031 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.00063 U	< 0.000099 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.00074 U	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.00078 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.00053 U	< 0.000083 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000095 U	< 0.00014 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.0017 U	< 0.0011 U	< 0.0014 U	< 0.0014 U	< 0.00081 U	< 0.0027 U	< 0.0035 U	< 0.0010 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0023 U	< 0.0022 U	< 0.0013 U	< 0.0045 U	< 0.0058 U	< 0.0016 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00092 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated								
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 002 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.00041 U	< 0.00070 U	< 0.00065 U	< 0.00045 U	< 0.00077 U	< 0.00050 U	< 0.00048 U	< 0.00036 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 UT	< 0.00025 UT	< 0.00019 UT
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.00010 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000094 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 UT	< 0.00028 UT	< 0.00021 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 UT	< 0.0021 UT
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	0.00024 J
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.00031 U	< 0.00052 U	< 0.00049 U	< 0.00034 UT	< 0.00058 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00014 UT	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 UT	< 0.00027 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 UT	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00016 U	< 0.00011 UT	< 0.00019 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00096 U	< 0.00032 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.0012 U	< 0.0039 U	< 0.0018 U	< 0.0032 U	< 0.0012 U	< 0.0034 U	< 0.0035 U	< 0.0019 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.0020 U	< 0.0064 U	< 0.0030 U	< 0.0053 U	< 0.0019 U	< 0.0056 U	< 0.0058 U	< 0.0031 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0017 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated								
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00079 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0029 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.00055 U	< 0.0031 U	< 0.00052 U	< 0.0078 U	< 0.00091 U	< 0.00067 U	< 0.0028 U	< 0.00093 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 UT	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.00015 U	< 0.00086 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00018 U	< 0.00078 U	< 0.00026 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00081 U	< 0.00013 U	< 0.0020 U	< 0.00024 U	< 0.00017 U	< 0.00073 U	< 0.00024 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 UT	< 0.00054 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.0023 U	< 0.0018 UT	< 0.0029 UT	< 0.0083 U	< 0.0027 U	0.017	< 0.0021 UT	< 0.0017 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00022 U	< 0.0013 U	< 0.00021 U	< 0.0032 U	< 0.00037 U	< 0.00027 U	< 0.0011 U	< 0.00038 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	0.00050 J	0.0025 J	0.00063 J	< 0.0036 U	< 0.00042 U	0.024	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00039 U	< 0.0059 U	< 0.00068 U	< 0.00050 U	< 0.0021 U	< 0.00070 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	0.0048	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.00017 U	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	0.0052	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.00014 U	< 0.00079 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.00069 U	< 0.00073 U	< 0.0028 U	< 0.0024 U	< 0.0017 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.0018 U	< 0.0022 U	< 0.0011 U	< 0.0012 U	< 0.0046 U	< 0.0039 U	< 0.0028 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.0010 U	< 0.0013 U	0.0010 J	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 UT	< 0.0032 UT	< 0.0021 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated							
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-10-12	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-10-12	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-10-12	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	0.00038 J	< 0.000099 U	< 0.00014 U	< 0.00011 U	< 0.000084 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.00051 U	< 0.00039 U	< 0.00056 U	< 0.00043 U	< 0.00033 U	< 0.00065 U	< 0.00042 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.00026 UT	< 0.00020 U	< 0.00028 UT	< 0.00022 UT	< 0.00017 U	< 0.00033 UT	< 0.00022 U
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000091 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00014 U	< 0.00011 U	< 0.000085 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.00030 UT	< 0.00023 U	< 0.00032 UT	< 0.00025 U	< 0.00019 U	< 0.00038 UT	< 0.00025 U
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.0017 UT	< 0.0017 UT	< 0.0023 UT	< 0.0016 UT	< 0.0031 UT	< 0.0029 UT	< 0.0019 U
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00021 U	< 0.00016 U	< 0.00023 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00020 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.00023 U	< 0.00018 UT	< 0.00026 U	0.00038 J	< 0.00015 UT	< 0.00030 UT	< 0.00020 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00042 U	< 0.00032 U	< 0.00025 U	< 0.00049 U	< 0.00032 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.00013 U	< 0.000099 U	< 0.00014 U	< 0.00011 U	< 0.000083 U	< 0.00016 U	< 0.00011 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	0.0011	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S575	SSHS-IRM5A2-S575-20220321	SSHS-IRM5A2-S575	3/21/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354851	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00040 U
Northern Athletic Field	S576	SSHS-IRM5A2-S576-20220321	SSHS-IRM5A2-S576	3/21/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00066 U
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6-20220321	SSHS-IRM5A2-S174-BOT6	3/21/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354861	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00056 U
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9-20220425	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 0.0011 U	< 0.00060 U	< 0.0026 U	< 0.0017 U	< 0.00074 U	< 0.00082 U	< 0.0015 U
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7-20220425	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 0.0018 U	< 0.00099 U	< 0.0042 U	< 0.0028 U	< 0.0012 U	< 0.0013 U	< 0.0025 U
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11-20220425	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 0.0010 U	0.0015 J	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00076 U	< 0.0014 U
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87-20220512	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	0.0030 J	< 0.0092 U
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA-20220512	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380712	Not Excavated							
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-B1-20220512	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11-20220512	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12-20220512	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-B2-20220512	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13-20220512	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14-20220512	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-10-12	SSHS-DW-10 11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-10-12	SSHS-DW-13 14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-10-12	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-10-12	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-10-12	SSHS-DW-7 8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3-20220610	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000081 U	< 0.000090 U	< 0.000081 U
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4-20220610	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3-20220610	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated	< 0.00032 U	< 0.00058 U	< 0.00074 U	< 0.00099 U	< 0.00032 U	< 0.00035 U	< 0.00032 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22-20220610	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 UT	< 0.00018 UT	< 0.00016 UT
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4-20220610	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated	< 0.000089 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000087 U	< 0.000098 U	< 0.000087 U
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23-20220610	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5-20220610	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated	< 0.000084 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000082 U	< 0.000092 U	< 0.000082 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220611	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220611	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220611	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220611	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220611	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220611	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220611	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220611	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111-20220613	SSHS-IRM5A2-DUP111	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117-20220613	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8-20220613	SSHS-IRM5A2-FISR-S8	6/13/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395961	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100-20220613	SSHS-IRM5A2-A4-S100	6/13/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395961	Not Excavated	< 0.00013 U	0.0012	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101-20220613	SSHS-IRM5A2-A4-S101	6/13/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102-20220613	SSHS-IRM5A2-A4-S102	6/13/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395961	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 UT	< 0.00021 UT	< 0.00018 UT
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103-20220613	SSHS-IRM5A2-A4-S103	6/13/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395961	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104-20220613	SSHS-IRM5A2-A4-S104	6/13/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395961	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105-20220613	SSHS-IRM5A2-A4-S105	6/13/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16-20220613	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated	< 0.0011 UT	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 UT	< 0.0023 UT	< 0.0082 UT
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20-20220613	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT-20220613	SSHS-IRM5A2-S506-BOT	6/13/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395961	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23-20220613	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24-20220613	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28-20220613	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32-20220613	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35-20220613	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36-20220613	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated	< 0.0010 U	0.0023 J	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40-20220613	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120-20220614	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44-20220614	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated	< 0.00012 U	0.0034	< 0.00028 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45-20220614	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46-20220614	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00038 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1-20220614	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated	< 0.00015 U	0.00045 J	< 0.00034 U	< 0.00046 U	0.00070 J	0.00081 J	0.0015 J
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3-20220614	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2-20220615	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated	< 0.00024 U	< 0.00044 U	< 0.00055 U	< 0.00075 U	< 0.00024 U	< 0.00027 U	< 0.00024 U
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4-20220615	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6-20220615	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated	< 0.000098 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000096 U	< 0.00011 U	< 0.000096 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8-20220615	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated	< 0.00011 U	< 0.00021 U	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1-20220615	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2-20220615	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000080 U	< 0.000089 U	< 0.000080 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1-20220616	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1-20220616	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2-20220616	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128-20220617	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10-20220617	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated	< 0.00012 U	0.00033 J	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12-20220617	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3-20220617	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1-20220617	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	0.02	< 0.00023 UT	< 0.00025 UT	< 0.00023 UT	< 0.00037 UT	< 0.00088 U	0.00096 T	< 0.00034 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.0044 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00077 U	< 0.00020 U	< 0.00030 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 UT	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	0.021	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 UT	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 UT	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 UT	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.0025 UT	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	0.0095 J	< 0.00042 U	< 0.00045 UT	< 0.00042 U	< 0.00069 U	< 0.0016 U	< 0.00043 U	< 0.00063 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	0.0051	< 0.00020 U	< 0.00022 UT	< 0.00020 U	< 0.00033 U	< 0.00078 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00025 UT	< 0.00022 UT	< 0.00037 UT	< 0.00087 U	< 0.00023 UT	< 0.00034 U
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 U	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	0.015	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 U	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	0.0048	< 0.00016 U	< 0.00018 U	< 0.00016 U	< 0.00027 U	< 0.00063 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.0032 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 UT
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00032 U	< 0.00047 UT
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 UT
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 UT
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.0084 U	< 0.00038 U	< 0.00041 U	< 0.00038 U	< 0.00063 U	< 0.0015 U	< 0.00039 U	< 0.00057 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated								
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.0090 U	< 0.00041 U	< 0.00044 U	< 0.00041 U	< 0.00067 U	< 0.0016 U	< 0.00042 U	< 0.00061 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.0028 U	< 0.00012 U	< 0.00014 U	< 0.00012 U	< 0.00021 U	< 0.00048 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	0.075	< 0.00040 U	< 0.00044 U	< 0.00040 U	< 0.00067 U	< 0.0016 U	< 0.00042 U	< 0.00061 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00081 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 UT	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 UT	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.00016 UT	< 0.00017 UT	< 0.00046 U	< 0.00085 UT	< 0.00038 UT	< 0.00019 UT	< 0.00040 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00033 U	< 0.00017 U	< 0.00035 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0032 J	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0027 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	0.0029 J,B	< 0.002 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.00029 U	< 0.00031 U	< 0.00084 U	< 0.0016 U	< 0.00070 U	< 0.00036 U	< 0.00074 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.00015 UT	< 0.00017 UT	< 0.00046 U	< 0.00085 UT	< 0.00038 U	< 0.00019 U	< 0.00040 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0041 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.00016 UT	< 0.00017 UT	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.000093 U	< 0.00010 U	< 0.00027 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00033 U	< 0.00061 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00052 U	< 0.00027 U	< 0.00055 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.00021 U	< 0.00024 U	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00077 U	< 0.0014 U	< 0.00064 U	< 0.00033 U	< 0.00068 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated							
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00028 U	< 0.00031 U	< 0.00082 U	< 0.0015 U	< 0.00069 U	< 0.00035 U	< 0.00073 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.000086 U	< 0.000094 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.00028 U	< 0.00030 U	< 0.00082 U	< 0.0015 U	< 0.00068 U	< 0.00035 U	< 0.00072 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00019 U	< 0.00041 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.0010 U	< 0.00016 UT	< 0.00030 U	< 0.00032 UT	< 0.00032 UT	< 0.00020 UT	< 0.00018 UT	< 0.00026 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.00088 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.0019 U	< 0.00029 U	< 0.00055 U	< 0.00058 U	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.00089 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.0010 UT	< 0.00016 UT	< 0.00029 U	< 0.00031 UT	< 0.00032 UT	< 0.00020 UT	< 0.00018 UT	< 0.00026 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.0010 U	< 0.00016 UT	< 0.00030 U	< 0.00032 UT	< 0.00032 UT	< 0.00020 UT	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00060 U	< 0.000094 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	< 0.00072 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 UT	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 UT	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 UT	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00050 UT	< 0.00053 U	< 0.00054 U	< 0.00033 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated								
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.0018 U	< 0.00028 U	< 0.00053 U	< 0.00057 U	< 0.00058 U	< 0.00035 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 UT	< 0.00048 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 UT	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.0055 U	< 0.000087 U	< 0.00016 U	< 0.00017 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.0018 U	< 0.00028 U	< 0.00053 U	< 0.00057 U	< 0.00057 U	< 0.00035 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00028 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.00020 UT	< 0.00033 UT	< 0.00031 UT	< 0.00022 UT	< 0.00037 UT	< 0.00024 UT	< 0.00023 UT	0.00071 JT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 UT	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 UT	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 UT	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 UT	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 UT	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.00036 U	< 0.00062 U	< 0.00058 U	< 0.00040 U	< 0.00068 U	< 0.00044 U	< 0.00043 U	< 0.00032 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.00020 UT	< 0.00033 UT	< 0.00031 UT	< 0.00021 UT	< 0.00037 UT	< 0.00024 UT	< 0.00023 UT	< 0.00017 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 UT	< 0.00024 UT	< 0.00018 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00027 U	< 0.00017 U	< 0.00017 U	< 0.00012 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00031 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00053 U	< 0.00036 U	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated								
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00035 U	< 0.00060 U	< 0.00056 U	< 0.00039 U	< 0.00067 U	< 0.00043 U	< 0.00042 U	< 0.00031 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.00030 U	< 0.00050 U	< 0.00047 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000096 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.00035 U	< 0.00060 U	< 0.00056 U	< 0.00039 U	< 0.00066 U	< 0.00043 U	< 0.00042 U	< 0.00031 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.00026 UT	< 0.0015 UT	0.00081 JT	< 0.0038 U	< 0.00044 UT	0.0045	< 0.0014 UT	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0033 U	< 0.00038 U	< 0.00028 U	< 0.0012 U	< 0.00039 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	0.024	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.00049 U	< 0.0028 U	< 0.00046 U	< 0.0070 U	< 0.00081 U	< 0.00059 U	< 0.0025 U	< 0.00083 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0033 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.00026 U	< 0.0015 UT	< 0.00025 UT	< 0.0037 UT	< 0.00044 U	< 0.00032 UT	< 0.0014 UT	< 0.00045 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	0.00064 J	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	0.00061 J	< 0.00038 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 UT
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.00031 U	< 0.0018 UT	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00016 U	< 0.00090 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00098 U	< 0.00032 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00017 U	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00042 U	< 0.0063 U	< 0.00073 U	< 0.00054 U	< 0.0023 U	< 0.00075 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated								
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00047 U	< 0.0027 U	< 0.00045 U	< 0.0068 U	< 0.00079 U	< 0.00058 U	< 0.0025 U	< 0.00081 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.00015 U	< 0.00083 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00075 U	< 0.00025 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.00047 U	< 0.0027 U	< 0.00045 U	0.01	< 0.00078 U	0.013	< 0.0024 U	< 0.00080 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 UT	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated								

													Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1.3	0.7			0.68
Restricted - Residential															19	100			100
Protection of Groundwater															1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.00024 UT	< 0.00019 UT	< 0.00027 UT	0.00049 JT	< 0.00016 UT	< 0.00031 UT	< 0.00020 UT
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00016 U	< 0.00023 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	0.00043 J	< 0.00019 U	0.00046 J	0.00021 J	< 0.00016 UT	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	0.00026 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.00045 U	< 0.00035 U	< 0.00049 U	< 0.00038 U	< 0.00029 U	< 0.00058 U	< 0.00038 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	0.00043 J	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.00024 UT	< 0.00019 U	< 0.00027 UT	< 0.00020 UT	< 0.00016 UT	< 0.00031 UT	< 0.00020 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	0.00052 J	< 0.00019 U	< 0.00027 U	0.00055 J	< 0.00016 U	< 0.00032 U	< 0.00021 UT
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	0.00043 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 UT
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00034 U	< 0.00022 UT
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.0029 U	< 0.0022 U	< 0.0032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.00025 UT	< 0.00019 UT	< 0.00027 U	0.00028 JT	< 0.00016 U	< 0.00032 UT	< 0.00021 U
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.0029 U	< 0.0022 U	< 0.0032 U	0.00036 J	< 0.00019 U	< 0.00038 U	< 0.00024 UT
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 UT
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00023 J	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00032 U	0.00096 J	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00035 J	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	0.00041 J	< 0.000095 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	0.00019 J	< 0.00011 U	< 0.00022 U	< 0.00015 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	0.00013 J	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.00034 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	0.00098 J	< 0.00031 U	< 0.00045 U	0.00046 J	< 0.00027 U	< 0.00053 U	< 0.00034 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated							
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.00036 J	< 0.00020 UT	< 0.00040 UT	< 0.00026 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00044 U	< 0.00034 U	< 0.00048 U	0.00073 J	< 0.00029 U	< 0.00056 U	< 0.00037 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	0.00023 J	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000088 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00034 U	< 0.00026 U	0.00041 J	0.00048 J	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	0.00037 J
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.00044 U	< 0.00034 U	0.0013 J	0.00044 J	< 0.00028 U	< 0.00056 U	0.0018
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	0.00032 J	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	0.00078 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	0.00021 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	847.07	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated							

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2-20220617	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated	< 0.00016 UT	0.00051 JT	< 0.00036 UT	< 0.00048 U	0.0012 T	0.0012 T	0.0024 T
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3-20220617	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00031 U	< 0.00042 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136-20220620	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 UT	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132-20220620	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00017 U	0.0017	< 0.00039 UT	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-10-12	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-10-12	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-10-12	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9-20220620	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 UT	< 0.00058 UT	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11-20220620	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 UT	< 0.00063 UT	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17-20220620	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated	< 0.00017 U	0.0028	< 0.00038 UT	< 0.00051 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19-20220620	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated	< 0.00017 U	0.00039 J	< 0.00039 UT	< 0.00053 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5-20220620	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 UT	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6-20220620	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated	< 0.00029 U	< 0.00052 U	< 0.00066 UT	< 0.00088 U	< 0.00028 U	< 0.00031 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7-20220620	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00031 UT	< 0.00042 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9-20220620	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated	< 0.00016 UT	0.00046 JT	< 0.00035 U	< 0.00048 UT	< 0.00015 UT	< 0.00017 UT	< 0.00015 UT
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15-20220630	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A-20220808	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1-20220808	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000-20220808	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	0.00021 J	< 0.00017 U	0.00021 J
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001-20220808	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006-20220808	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202-20220808	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203-20220808	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated	< 0.00016 UT	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 UT	< 0.00017 UT	< 0.00015 UT
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204-20220808	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205-20220808	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188-20220810	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00016 U	0.00043 J	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6-20220810	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8-20220810	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated	< 0.00018 U	0.0012	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9-20220810	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT-20220810	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220813	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220813	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220813	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196-20220815	SSHS-IRM5A2-FISR-DUP196	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.000093 U	< 0.00017 U	< 0.00021 U	< 0.00029 U	0.00014 J	< 0.00010 U	0.00014 J
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94-20220815	SSHS-IRM5A2-FISR-S94	8/15/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429581	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98-20220815	SSHS-IRM5A2-FISR-S98	8/15/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429581	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000099 U	< 0.00011 U	< 0.000099 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200-20220817	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00049 U	< 0.00066 UT	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1-20220817	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430861	Not Excavated	< 0.00018 U	0.00073 J	< 0.00041 U	< 0.00055 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3-20220817	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated	< 0.00019 U	0.00081 J	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6-20220817	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7-20220817	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8-20220817	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1-20220817	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430861	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00050 U	< 0.00068 UT	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2-20220817	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430861	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00060 U	< 0.00080 UT	< 0.00026 U	< 0.00029 U	< 0.00026 U
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated							
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3-20220817	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430811	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195-20220818	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00028 U	< 0.00051 U	< 0.00064 U	< 0.00086 U	< 0.00027 U	< 0.00031 U	< 0.00027 U
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73-20220818	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00054 U	< 0.00072 UT	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82-20220818	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85-20220818	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89-20220818	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17-20220818	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated	< 0.000086 U	< 0.00016 U	< 0.00020 U	< 0.00026 U	< 0.000084 U	< 0.000094 U	< 0.000084 U
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000-20220823	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00022 U	0.0027	< 0.00049 U	< 0.00066 U	0.00024 J	< 0.00024 U	0.00024 J
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001-20220823	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated	< 0.00020 U	0.00099 J	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002-20220823	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated	< 0.00028 U	0.0061	< 0.00064 U	< 0.00086 U	< 0.00027 U	< 0.00030 U	< 0.00027 U
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000-20220823	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated	< 0.00014 U	0.00037 J	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000-20220824	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001-20220824	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200-20220824	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202-20220824	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	0.00022 J	< 0.00016 U	0.00022 J
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003-20220825	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004-20220825	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205-20220825	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206-20220825	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221-20220908	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A6-S1003	SSHS-IRM5A2-A6-S1003-20220908	SSHS-IRM5A2-A6-S1003	9/8/2022	-	857.56	-	846.24	10 - 12 ft	11.33 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001-20220908	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002-20220908	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221020	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221020	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]	Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.05	0.06						0.76
Restricted - Residential													100	4.8						2.4
Protection of Groundwater													0.05	0.06						0.76
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	0.011	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 UT	< 0.00027 UT	< 0.00063 U	< 0.00017 U	< 0.00024 UT
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 UT	< 0.00017 UT	< 0.00040 U	< 0.00011 UT	< 0.00015 UT
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 UT	< 0.00021 UT	< 0.00049 U	< 0.00013 UT	< 0.00019 UT
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00051 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	0.011	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated								
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.0049	< 0.00067	< 0.00068	< 0.00055	< 0.00044	< 0.00073	< 0.0005	< 0.00044
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.005	< 0.00067	< 0.00068	< 0.00056	< 0.00044	< 0.00074	< 0.00051	< 0.00044
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0046	< 0.00063	< 0.00064	< 0.00052	< 0.00041	< 0.00068	< 0.00047	< 0.00041
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0099	< 0.0029	< 0.0014	< 0.0019	< 0.0044	< 0.0017	< 0.002	< 0.0013
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	0.018 J	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	0.008 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	0.0081 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	0.0041 J	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.0029 U	< 0.0051 U	< 0.0034 U	< 0.0037 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	0.0053 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	0.0046 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0021 U	< 0.0023 U	< 0.004 U	< 0.0027 U	< 0.003 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0021 UJ	< 0.0023 UJ	< 0.004 U	< 0.0027 U	< 0.003 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	0.0075 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.0039 U	< 0.0024 U	< 0.0024 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.0041 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	0.0035 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	0.0069 J	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.002 U	< 0.0022 U	< 0.0039 U	< 0.0026 U	< 0.0029 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	0.017 J	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0017 U	< 0.0021 U	< 0.0024 U	< 0.0041 U	< 0.0027 U	< 0.003 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 UJ	< 0.0024 UJ	< 0.0041 U	< 0.0027 U	< 0.003 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.002 U	< 0.0013 U	< 0.0012 U	< 0.0015 UJ	< 0.0017 UJ	< 0.0029 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 UJ	< 0.0025 UJ	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0019 UJ	< 0.0021 UJ	< 0.0037 U	< 0.0025 U	< 0.0027 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0018 UJ	< 0.002 UJ	< 0.0034 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-B3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00033 U	< 0.00061 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.000070 U	< 0.000077 UT	< 0.00021 U	< 0.00038 U	< 0.00017 U	< 0.000087 U	< 0.00018 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.000087 U	< 0.000095 UT	< 0.00026 U	< 0.00048 U	< 0.00021 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.000090 U	< 0.000099 UT	< 0.00027 U	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00014 U	< 0.00016 UT	< 0.00042 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.000082 U	< 0.000090 UT	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00099 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00019 UT	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.00022 U	< 0.00024 UT	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.00015 U	< 0.00017 UT	< 0.00045 U	< 0.00084 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.000089 U	< 0.000098 UT	< 0.00026 U	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UT	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0030 U	< 0.0018 U	< 0.0022 U	< 0.0029 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0031 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated							
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated							
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated							
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.00075	< 0.0007	< 0.0015	< 0.00058	< 0.00084	< 0.00037	< 0.00074
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00075	< 0.00071	< 0.0015	< 0.00058	< 0.00085	< 0.00037	< 0.00074
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0007	< 0.00066	< 0.0014	< 0.00054	< 0.00079	< 0.00034	< 0.00069
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0021	< 0.0024	< 0.0021	< 0.0012	< 0.0025	< 0.0014	< 0.0044
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0014 U	< 0.0021 U	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0014 U	< 0.0021 UJ	< 0.0023 U	< 0.0019 U	< 0.0034 U	< 0.0011 U	< 0.0027 UJ
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.0019 U	< 0.003 U	< 0.0032 U	< 0.0026 U	< 0.0047 UJ	< 0.0015 U	< 0.0038 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0014 U	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.0011 U	< 0.0026 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0014 U	< 0.0022 UJ	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.001 U	< 0.0016 UJ	< 0.0017 U	< 0.0014 U	< 0.0025 U	< 0.00079 U	< 0.002 UJ
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.0015 U	< 0.0023 UJ	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 UJ	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.0013 U	< 0.002 UJ	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.001 U	< 0.0025 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.0012 U	< 0.0018 UJ	< 0.002 U	< 0.0016 U	< 0.0029 U	< 0.00093 U	< 0.0023 UJ
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 UJ	< 0.0013 U	< 0.0033 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.00072 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00045 U	< 0.000071 U	< 0.00013 U	< 0.00014 U	< 0.00014 U	< 0.000089 U	< 0.000081 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00056 U	< 0.000088 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	0.00073 J	< 0.000091 U	< 0.00017 U	< 0.00018 U	< 0.00019 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	0.0012 J	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.00053 U	< 0.000083 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000095 U	< 0.00014 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	0.0019 J	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.00099 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00058 U	< 0.000091 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.0041 U	< 0.0012 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated								
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.00066	< 0.00085	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.0006
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00067	< 0.00086	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.00061
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00062	< 0.0008	< 0.00062	< 0.00074	< 0.00061	< 0.00059	< 0.00053	< 0.00057
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	0.0074	< 0.0021	< 0.0028	< 0.0031	< 0.0029	< 0.0029	< 0.0011	< 0.0011
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	< 0.0026 U	< 0.003 U	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	< 0.0024 U	< 0.0027 U	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 004 U	< 0.0029 U	< 003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0034 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00091 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0034 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00091 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 003 U	< 002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 003 U	< 002 U	< 0.0016 U	< 001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.0047 U	< 0.0034 U	< 0.0036 U	< 0.0025 U	< 002 U	< 0.0013 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 002 U	< 0.0016 U	< 001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0033 U	< 0.0024 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00088 U	< 0.0016 U	< 0.0012 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	< 0.004 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0026 U	< 0.0018 U	< 0.0014 U	< 0.00093 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.0025 U	< 0.0018 U	< 0.0019 U	< 0.0013 U	< 0.001 U	< 0.00066 U	< 0.0012 U	< 0.00094 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0042 U	< 003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 003 U	< 002 U	< 0.0016 U	< 001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 004 U	< 0.0028 U	< 003 U	< 0.0021 U	< 0.0016 U	< 001 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.0032 U	< 0.0022 U	< 0.0024 U	< 0.0016 U	< 0.0013 U	< 0.00084 U	< 0.0015 U	< 0.0012 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.0029 U	< 0.0021 U	< 0.0022 U	< 0.0015 U	< 0.0012 U	< 0.00078 U	< 0.0014 U	< 0.0011 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0042 U	< 003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0042 U	< 003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 002 U	< 0.0016 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 UT	< 0.00027 UT	< 0.00020 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 UT	< 0.00028 UT	< 0.00021 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00017 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.000089 U	< 0.00015 U	< 0.00014 U	< 0.000097 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000079 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000097 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 UT	< 0.00010 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.00027 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 UT	< 0.00010 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated								
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.00084		< 0.00069	< 0.00059	< 0.00054	< 0.00067	< 0.00059	< 0.00063
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00084		< 0.0007	< 0.00059	< 0.00054	< 0.00067	< 0.00059	< 0.00064
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00079		< 0.00065	< 0.00055	< 0.0005	< 0.00063	< 0.00055	< 0.0006
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0014	< 0.0023	< 0.0013	< 0.00099	< 0.0018	< 0.0021	< 0.0023	< 0.0019
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0025 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0015 U	< 0.0019 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0025 U	< 0.0035 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 UJ	< 0.0015 UJ	< 0.0019 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.0035 U	< 0.0049 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.002 U	< 0.0021 U	< 0.0026 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0025 U	< 0.0034 U	< 0.0014 U	< 0.0022 U	< 0.0021 U	< 0.0014 U	< 0.0015 U	< 0.0019 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0014 U	< 0.0016 U	< 0.002 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 UJ	< 0.0016 UJ	< 0.002 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.0018 U	< 0.0026 U	< 0.001 U	< 0.0016 U	< 0.0016 U	< 0.001 UJ	< 0.0011 UJ	< 0.0014 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.0028 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 UJ	< 0.0017 UJ	< 0.0021 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.0023 U	< 0.0033 U	< 0.0013 U	< 0.0021 U	< 0.002 U	< 0.0013 UJ	< 0.0014 UJ	< 0.0018 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.0022 U	< 0.003 U	< 0.0012 U	< 0.0019 U	< 0.0019 U	< 0.0012 UJ	< 0.0013 UJ	< 0.0016 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 UT	< 0.00052 UT
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 UT	< 0.00055 UT
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.00019 U	< 0.0011 UT	< 0.00018 U	< 0.0027 U	< 0.00032 U	< 0.00023 U	< 0.00098 U	< 0.00032 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00012 U	< 0.00068 UT	< 0.00011 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00061 U	< 0.00020 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00015 U	< 0.00084 UT	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00015 U	< 0.00087 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00019 U	< 0.00079 U	< 0.00026 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.00014 U	< 0.00079 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	0.0040 J	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00015 U	< 0.00086 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00019 U	< 0.00078 U	< 0.00026 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 UT	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 UT	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 UT	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 UT	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	-	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	-	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated								
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated								
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.0011	< 0.00068	< 0.00067	< 0.00089	< 0.00071	< 0.00087	< 0.00064	< 0.00074
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.0011	< 0.00069	< 0.00068	< 0.0009	< 0.00072	< 0.00088	< 0.00065	< 0.00074
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00099	< 0.00064	< 0.00063	< 0.00084	< 0.00067	< 0.00082	< 0.0006	< 0.00069
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0013	< 0.0039	< 0.0033	< 0.013	< 0.0017	< 0.0029	< 0.0034	< 0.0024
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 0.0022 U	< 0.0047 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0017 U	< 0.0037 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0017 U	< 0.0037 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.0023 U	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0036 U	< 0.0023 U	< 0.0045 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.0051 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0032 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0053 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0033 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0034 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0015 U	< 0.0038 U	< 0.0014 U	< 0.0019 U	< 0.0012 U	< 0.0024 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.0016 U	< 0.0034 U	< 0.0019 U	< 0.0049 U	< 0.0017 U	< 0.0024 U	< 0.0015 U	< 0.003 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.0015 U	< 0.0032 U	< 0.0018 U	< 0.0045 U	< 0.0016 U	< 0.0022 U	< 0.0014 U	< 0.0028 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-B3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U	< 0.002 U	< 0.004 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.00018 U	< 0.00014 U	0.00019 J	< 0.00015 U	< 0.00011 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00011 U	< 0.000085 U	< 0.00012 U	< 0.000092 U	< 0.000072 U	< 0.00014 U	< 0.000092 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.00014 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000089 U	< 0.00018 U	< 0.00011 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000092 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.00013 U	< 0.000099 U	< 0.00014 U	< 0.00011 U	< 0.000084 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00028 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000091 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated							
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated							
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated							
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.00069	< 0.00071	< 0.00067	< 0.00072	< 0.00083	< 0.00087	< 0.00048
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.0007	< 0.00071	< 0.00068	< 0.00073	< 0.00084	< 0.00088	< 0.00048
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00065	< 0.00067	< 0.00063	< 0.00068	< 0.00078	< 0.00082	< 0.00045
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0023	< 0.0038	< 0.0012	< 0.0035	< 0.0039	< 0.0039	< 0.001
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80255-2	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0023 U	< 0.0018 U	< 0.0027 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0021 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.0035 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U	< 0.0027 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.0016 U	< 0.0037 U	< 0.0025 U	< 0.0021 U	< 0.0043 U	< 0.0046 U	< 0.0031 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0027 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0011 U	< 0.0026 U	< 0.0017 U	< 0.0015 U	< 0.003 U	< 0.0032 U	< 0.0022 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U	< 0.0023 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U	< 0.0023 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.00086 U	< 0.0019 U	< 0.0013 U	< 0.0011 U	< 0.0023 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.0041 U	< 0.0027 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.0011 U	< 0.0025 U	< 0.0016 U	< 0.0014 U	< 0.0029 U	< 0.0031 U	< 0.0021 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.001 U	< 0.0023 U	< 0.0015 U	< 0.0013 U	< 0.0027 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221020	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243-20221024	SSHS-IRM5A2-DUP243	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A-20221024	SSHS-IRM5A2-A6-S806A	10/24/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801468451	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800-20221024	SSHS-IRM5A2-A6-B800	10/24/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801468451	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT-20221025	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated	< 0.00011 U	0.00025 J	< 0.00026 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248-20221026	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.000070 U	< 0.00013 U	< 0.00016 U	< 0.00022 U	< 0.000069 U	< 0.000077 U	< 0.000069 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT-20221026	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated	< 0.000087 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000085 U	< 0.000095 U	< 0.000085 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270-20221209	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.000090 U	0.00019 J	< 0.00021 U	< 0.00028 U	< 0.000088 U	< 0.000099 U	< 0.000088 U
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1-20221209	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2-20221209	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000080 U	< 0.000090 U	< 0.000080 U
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3-20221209	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1-20221209	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3-20221209	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4-20221209	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT-20221209	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5-20221209	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated	< 0.000090 U	0.00020 J	< 0.00020 U	< 0.00027 U	< 0.000088 U	< 0.000098 U	< 0.000088 U
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5-20230530	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A-20230601	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15-20230601	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21-20230601	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 0.00090 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0065 U
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27-20230601	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28-20230601	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT-20231208	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338-20231214	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33-20231214	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated							
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT-20231214	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated							
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10-20231214	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated							
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated	< 0.00082	< 0.00065	< 0.00091	< 0.00046		< 0.00077	
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00083	< 0.00065	< 0.00091	< 0.00047		< 0.00078	
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00077	< 0.00061	< 0.00085	< 0.00043		< 0.00072	
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0027	< 0.0011	< 0.0028	< 0.0025		< 0.0028	< 0.0044
Northern Athletic Field	SSHS-B2024	072718 09:00 SSHS-B2024-SUB-12-14	SSHS-B2024-SUB-12-14	7/26/2018	852.76	854.11	1.35	-	12 - 14 ft	13.35-15.35 ft	180-80225-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-12-14	SSHS-B2030-SUB-12-14	7/27/2018	856.20	856.42	0.22	-	12 - 14 ft	12.22-14.22 ft	180-80252-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-12-14	SSHS-B3022-SUB-12-14	8/26/2019	853.76	855.66	1.90	-	12 - 14 ft	13.9-15.9 ft	180-94754-3	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-12-14	SSHS-B3034-SUB-12-14	8/26/2019	855.10	856.53	1.43	-	12 - 14 ft	13.43-15.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-12-14	SSHS-B3035-SUB-12-14	8/26/2019	854.81	856.27	1.46	-	12 - 14 ft	13.46-15.46 ft	180-94752-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-12-14	SSHS-B3049-SUB-12-14	8/26/2019	856.17	857.50	1.33	-	12 - 14 ft	13.33-15.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-12-14	SSHS-B3064-SUB-12-14	8/26/2019	856.77	857.84	1.07	-	12 - 14 ft	13.07-15.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-12-14	SSHS-B3065-SUB-12-14	8/26/2019	856.77	857.30	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3077	082719 09:30 SSHS-B3077-SUB-12-14	SSHS-B3077-SUB-12-14	8/26/2019	856.86	857.85	0.99	-	12 - 14 ft	12.99-14.99 ft	180-94752-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-12-14	SSHS-B3078-SUB-12-14	8/26/2019	856.70	857.12	0.42	-	12 - 14 ft	12.42-14.42 ft	180-94752-3	Not Excavated	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-12-14	SSHS-B3098-SUB-12-14	8/26/2019	855.97	857.05	1.08	-	12 - 14 ft	13.08-15.08 ft	180-94754-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-12-14	SSHS-B3099-SUB-12-14	8/26/2019	856.40	856.53	0.13	-	12 - 14 ft	12.13-14.13 ft	180-94754-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-12-14	SSHS-B3006-SUB-12-14	8/27/2019	852.36	852.39	0.03	-	12 - 14 ft	12.03-14.03 ft	180-94829-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0038 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-12-14	SSHS-B3018-SUB-12-14	8/27/2019	853.82	854.59	0.77	-	12 - 14 ft	12.77-14.77 ft	180-94829-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0038 U
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-12-14	SSHS-B3019-SUB-12-14	8/27/2019	854.09	855.31	1.22	-	12 - 14 ft	13.22-15.22 ft	180-94824-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-12-14	SSHS-B3020-SUB-12-14	8/27/2019	853.86	855.74	1.88	-	12 - 14 ft	13.88-15.88 ft	180-94824-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-12-14	SSHS-B3031-SUB-12-14	8/27/2019	855.08	855.61	0.53	-	12 - 14 ft	12.53-14.53 ft	180-94824-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-12-14	SSHS-B3032-SUB-12-14	8/27/2019	855.25	856.15	0.90	-	12 - 14 ft	12.9-14.9 ft	180-94819-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-12-14	SSHS-B3033-SUB-12-14	8/27/2019	855.17	856.58	1.41	-	12 - 14 ft	13.41-15.41 ft	180-94824-1	Not Excavated	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0053 U
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-12-14	SSHS-B3046-SUB-12-14	8/27/2019	856.22	856.03	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-94824-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-12-14	SSHS-B3047-SUB-12-14	8/27/2019	856.24	856.75	0.51	-	12 - 14 ft	12.51-14.51 ft	180-94819-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-12-14	SSHS-B3048-SUB-12-14	8/27/2019	856.08	857.32	1.24	-	12 - 14 ft	13.24-15.24 ft	180-94819-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-12-14	SSHS-B3061-SUB-12-14	8/27/2019	857.02	856.09	-0.93	-	12 - 14 ft	11.07-13.07 ft	180-94824-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-12-14	SSHS-B3063-SUB-12-14	8/27/2019	856.95	857.80	0.85	-	12 - 14 ft	12.85-14.85 ft	180-94819-1	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3075	082819 09:00 SSHS-B3075-SUB-12-14	SSHS-B3075-SUB-12-14	8/27/2019	856.99	856.91	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-94819-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-12-14	SSHS-B3076-SUB-12-14	8/27/2019	856.92	857.74	0.82	-	12 - 14 ft	12.82-14.82 ft	180-94819-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-12-14	SSHS-B3096-SUB-12-14	8/27/2019	855.86	856.29	0.43	-	12 - 14 ft	12.43-14.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-12-14	SSHS-B3097-SUB-12-14	8/27/2019	856.19	856.93	0.74	-	12 - 14 ft	12.74-14.74 ft	180-94824-1	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-12-14	SSHS-B3029-SUB-12-14	8/28/2019	854.97	853.59	-1.38	-	12 - 14 ft	10.62-12.62 ft	180-94902-3	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0033 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-12-14	SSHS-B3030-SUB-12-14	8/28/2019	855.22	855.02	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-94902-1	Not Excavated	< 0.0015 U	< 0.00097 U	< 0.00094 U	< 0.0024 U	< 0.0012 U	< 0.0016 U	< 0.0028 U
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-12-14	SSHS-B3043-SUB-12-14	8/28/2019	855.78	856.62	0.84	-	12 - 14 ft	12.84-14.84 ft	180-94902-2	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-12-14	SSHS-B3044-SUB-12-14	8/28/2019	856.00	854.20	-1.80	-	12 - 14 ft	10.2-12.2 ft	180-94900-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-12-14	SSHS-B3045-SUB-12-14	8/28/2019	856.03	855.07	-0.96	-	12 - 14 ft	11.04-13.04 ft	180-94900-3	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-12-14	SSHS-B3057-SUB-12-14	8/28/2019	856.09	857.58	1.49	-	12 - 14 ft	13.49-15.49 ft	180-94900-3	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-12-14	SSHS-B3058-SUB-12-14	8/28/2019	856.47	856.55	0.08	-	12 - 14 ft	12.08-14.08 ft	180-94902-2	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0012 U	< 0.003 U	< 0.0015 U	< 0.002 U	< 0.0035 U
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-12-14	SSHS-B3059-SUB-12-14	8/28/2019	856.71	854.42	-2.29	-	12 - 14 ft	9.71-11.71 ft	180-94902-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0011 U	< 0.0028 U	< 0.0014 U	< 0.0019 U	< 0.0033 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-12-14	SSHS-S3060-SUB-12-14	8/28/2019	856.96	855.38	-1.58	-	12 - 14 ft	10.42-12.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-12-14	SSHS-B3070-SUB-12-14	8/28/2019	856.51	857.05	0.54	-	12 - 14 ft	12.54-14.54 ft	180-94900-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.0021 U	< 0.0027 U	< 0.0047 U
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-12-14	SSHS-B3071-SUB-12-14	8/28/2019	856.76	856.63	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-94900-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0027 U	< 0.0047 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 UJ	< 0.0027 UJ	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.002 UJ	< 0.0022 U	< 0.0039 U	< 0.0026 U	< 0.0028 UJ
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0034 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 UJ	< 0.0036 U
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0019 UJ	< 0.0021 U	< 0.0037 U	< 0.0025 U	< 0.0027 U
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0023 U	< 0.0028 U	< 0.0031 U	< 0.0053 U	< 0.0035 U	< 0.0039 U
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0034 U
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0022 U	< 0.0025 U	< 0.0042 U	< 0.0028 U	< 0.0031 U
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0035 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3266	122119 10:30_SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3267	122119 10:30_SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	0.0049 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0027 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	SSHS-B3493	012221 08:30_SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 UJ	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 UJ	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0016 U	< 0.0024 UJ	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0014 U	< 0.0021 UJ	< 0.0022 U	< 0.0018 U	< 0.0033 U	< 0.001 U	< 0.0026 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.0013 U	< 0.002 UJ	< 0.0021 U	< 0.0017 U	< 0.0032 U	< 0.001 U	< 0.0025 U
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0019 U	< 0.0028 UJ	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0036 U	< 0.0012 U	< 0.0029 U
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3266	122119 10:30_SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3267	122119 10:30_SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3493	012221 08:30_SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated							
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00097 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 UJ	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0033 U	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.00088 U	< 0.0016 U	< 0.0012 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 UJ	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.0032 U	< 0.0022 U	< 0.0024 U	< 0.0016 U	< 0.0013 U	< 0.00084 U	< 0.0015 U	< 0.0012 U
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0044 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0036 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00096 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3266	122119 10:30_SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3267	122119 10:30_SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	0.0044 J	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	0.0042 J	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	0.0041 J	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0039 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.0037 U	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00098 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	0.0039 J	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	0.0042 J	< 0.0027 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	0.005	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3493	012221 08:30_SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0028 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 UJ	< 0.0018 UJ	< 0.0022 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.003 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0029 UJ	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0024 U	< 0.0034 U	< 0.0014 U	< 0.0022 U	< 0.0021 U	< 0.0014 UJ	< 0.0015 UJ	< 0.0018 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0031 UJ	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.0023 U	< 0.0033 U	< 0.0013 U	< 0.0021 U	< 0.002 U	< 0.0013 UJ	< 0.0014 UJ	< 0.0018 U
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0034 U	< 0.0047 U	< 0.0019 U	< 0.003 U	< 0.0029 U	< 0.0019 UJ	< 0.002 UJ	< 0.0025 U
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U	< 0.0025 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0032 U	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U	< 0.002 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.003 U	< 0.0029 U	< 0.0019 U	< 0.002 U	< 0.0025 U
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0016 U	< 0.002 U
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3266	122119 10:30_SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3267	122119 10:30_SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0016 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.0027 U	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0024 U	< 0.0015 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0029 U	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3493	012221 08:30_SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.002 U	< 0.0051 U	< 0.0018 U	< 0.0025 U	< 0.0016 U	< 0.0032 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0019 U	< 0.0049 U	< 0.0017 U	< 0.0024 U	< 0.0015 U	< 0.003 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0025 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0022 U	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0027 U	< 0.0017 U	< 0.0034 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0027 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0019 U	< 0.0043 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3266	122119 10:30 SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3267	122119 10:30 SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0039 U
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.0018 U	< 0.004 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-B3493	012221 08:30 SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated								
Northern Athletic Field	SSHS-B3455	012721 08:30 SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated								

DRAFT

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3016	083019 09:00 SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U	< 0.0027 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3028	083019 09:00 SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0011 U	< 0.0026 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0032 U	< 0.0022 UJ
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.0011 U	< 0.0025 U	< 0.0016 U	< 0.0014 U	< 0.0029 U	< 0.0031 U	< 0.0021 U
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0024 U	< 0.002 U	< 0.0042 U	< 0.0044 U	< 0.003 U
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U	< 0.0029 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0015 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0027 U
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U	< 0.0023 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0016 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U	< 0.0029 U
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U	< 0.0027 U
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0013 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U	< 0.0024 U
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0014 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3266	122119 10:30 SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3267	122119 10:30 SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.0035 U	< 0.0036 U	< 0.0025 U
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0027 U
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0015 U	< 0.0015 UT	0.0042 J	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3493	012221 08:30 SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated							
Northern Athletic Field	SSHS-B3455	012721 08:30 SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3247A	012721 08:30 SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-12-14	SSHS-B3072-SUB-12-14	8/28/2019	856.89	856.00	-0.89	-	12 - 14 ft	11.11-13.11 ft	180-94900-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-12-14	SSHS-B3073-SUB-12-14	8/28/2019	857.14	855.25	-1.89	-	12 - 14 ft	10.11-12.11 ft	180-94900-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U		< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-12-14	SSHS-B3095-SUB-12-14	8/28/2019	857.12	856.70	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-94902-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-12-14	SSHS-B3005-SUB-12-14	8/29/2019	852.31	852.62	0.31	-	12 - 14 ft	12.31-14.31 ft	180-94981-3	Not Excavated	< 0.0025 U	0.0016 J	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3016	083019 09:00_SSHS-B3016-SUB-12-14	SSHS-B3016-SUB-12-14	8/29/2019	853.54	855.13	1.59	-	12 - 14 ft	13.59-15.59 ft	180-94981-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3028	083019 09:00_SSHS-B3028-SUB-12-14	SSHS-B3028-SUB-12-14	8/29/2019	854.60	856.02	1.42	-	12 - 14 ft	13.42-15.42 ft	180-94981-3	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-12-14	SSHS-B3054-SUB-12-14	8/29/2019	856.01	856.77	0.76	-	12 - 14 ft	12.76-14.76 ft	180-95024-2	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0013 U	< 0.0032 U	< 0.0016 U	< 0.0021 U	< 0.0037 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-12-14	SSHS-B3079-SUB-12-14	8/29/2019	856.36	857.37	1.01	-	12 - 14 ft	13.01-15.01 ft	180-95024-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0012 U	< 0.003 U	< 0.0015 U	< 0.002 U	< 0.0035 U
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-12-14	SSHS-B3083-SUB-12-14	8/29/2019	857.13	857.39	0.26	-	12 - 14 ft	12.26-14.26 ft	180-95024-2	Not Excavated	< 0.0028 U	< 0.0018 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0029 U	< 0.0051 U
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-12-14	SSHS-B3084-SUB-12-14	8/29/2019	856.55	857.05	0.50	-	12 - 14 ft	12.5-14.5 ft	180-95006-2	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-12-14	SSHS-B3181-SUB-12-14	8/29/2019	857.57	857.81	0.24	-	12 - 14 ft	12.24-14.24 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-12-14	SSHS-B3182-SUB-12-14	8/29/2019	857.45	857.88	0.43	-	12 - 14 ft	12.43-14.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-12-14	SSHS-B3223-SUB-12-14	8/29/2019	858.27	858.28	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-12-14	SSHS-B3003-SUB-12-14	8/30/2019	851.95	852.83	0.88	-	12 - 14 ft	12.88-14.88 ft	180-95047-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-12-14	SSHS-B3011-SUB-12-14	8/30/2019	853.85	854.62	0.77	-	12 - 14 ft	12.77-14.77 ft	180-95050-1	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-12-14	SSHS-B3025-SUB-12-14	8/30/2019	854.59	855.82	1.23	-	12 - 14 ft	13.23-15.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-12-14	SSHS-B3039-SUB-12-14	8/30/2019	855.85	856.37	0.52	-	12 - 14 ft	12.52-14.52 ft	180-95047-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-12-14	SSHS-B3068-SUB-12-14	8/30/2019	856.38	856.82	0.44	-	12 - 14 ft	12.44-14.44 ft	180-95050-1	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-12-14	SSHS-B3082-SUB-12-14	8/30/2019	856.73	857.22	0.49	-	12 - 14 ft	12.49-14.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-12-14	SSHS-B3087-SUB-12-14	8/30/2019	857.68	857.65	-0.03	-	12 - 14 ft	11.97-13.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-12-14	SSHS-B3214-SUB-12-14	8/30/2019	855.06	855.25	0.19	-	12 - 14 ft	12.19-14.19 ft	180-95050-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-12-14	SSHS-B3222-SUB-12-14	8/30/2019	858.28	858.08	-0.20	-	12 - 14 ft	11.8-13.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-12-14	SSHS-B3224-SUB-12-14	8/30/2019	858.38	858.48	0.10	-	12 - 14 ft	12.1-14.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-12-14	SSHS-B3001-SUB-12-14	9/3/2019	853.35	853.44	0.09	-	12 - 14 ft	12.09-14.09 ft	180-95155-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-12-14	SSHS-B3009-SUB-12-14	9/3/2019	853.88	854.29	0.41	-	12 - 14 ft	12.41-14.41 ft	180-95155-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-12-14	SSHS-B3010-SUB-12-14	9/3/2019	854.13	854.48	0.35	-	12 - 14 ft	12.35-14.35 ft	180-95155-2	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-12-14	SSHS-B3023-SUB-12-14	9/3/2019	854.48	854.90	0.42	-	12 - 14 ft	12.42-14.42 ft	180-95155-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-12-14	SSHS-B3024-SUB-12-14	9/3/2019	855.00	855.16	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95155-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-12-14	SSHS-B3036-SUB-12-14	9/3/2019	855.09	855.21	0.12	-	12 - 14 ft	12.12-14.12 ft	180-95155-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-12-14	SSHS-B3038-SUB-12-14	9/3/2019	855.76	855.72	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-12-14	SSHS-B3052-SUB-12-14	9/3/2019	855.98	855.94	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-95162-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-12-14	SSHS-B3053-SUB-12-14	9/3/2019	856.41	856.22	-0.19	-	12 - 14 ft	11.81-13.81 ft	180-95155-3	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-12-14	SSHS-B3067-SUB-12-14	9/3/2019	856.40	856.48	0.08	-	12 - 14 ft	12.08-14.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-12-14	SSHS-B3051-SUB-12-14	9/4/2019	855.15	855.32	0.17	-	12 - 14 ft	12.17-14.17 ft	180-95165-2	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-12-14	SSHS-B3066-SUB-12-14	9/4/2019	855.86	856.02	0.16	-	12 - 14 ft	12.16-14.16 ft	180-95165-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	< 0.002 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-12-14	SSHS-B3080-SUB-12-14	9/4/2019	856.58	856.76	0.18	-	12 - 14 ft	12.18-14.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-12-14	SSHS-B3081-SUB-12-14	9/4/2019	856.96	857.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-95165-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-12-14	SSHS-B3085-SUB-12-14	9/4/2019	857.12	857.26	0.14	-	12 - 14 ft	12.14-14.14 ft	180-95165-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-12-14	SSHS-B3086-SUB-12-14	9/4/2019	857.77	857.49	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-12-14	SSHS-B3220-SUB-12-14	9/4/2019	857.44	857.92	0.48	-	12 - 14 ft	12.48-14.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-12-14	SSHS-B3221-SUB-12-14	9/4/2019	857.92	857.93	0.01	-	12 - 14 ft	12.01-14.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3266	122119 10:30_SSHS-B3266-SUB-12-14	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3267	122119 10:30_SSHS-B3267-SUB-12-14	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-12-14	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-12-14	SSHS-B3100-SUB-12-14	1/13/2020	856.74	856.68	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-12-14	SSHS-B3101-SUB-12-14	1/13/2020	856.75	856.69	-0.06	-	12 - 14 ft	11.94-13.94 ft	180-100985-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0038 U	0.0022 J	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-12-14	SSHS-B3102-SUB-12-14	1/13/2020	856.74	856.23	-0.51	-	12 - 14 ft	11.49-13.49 ft	180-100985-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-12-14	SSHS-B3104-SUB-12-14	1/13/2020	856.82	856.64	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-100985-2	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-12-14	SSHS-B3105-SUB-12-14	1/14/2020	856.73	856.62	-0.11	-	12 - 14 ft	11.89-13.89 ft	180-101038-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-12-14	SSHS-B3106-SUB-12-14	1/14/2020	856.72	856.30	-0.42	-	12 - 14 ft	11.58-13.58 ft	180-101038-1	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0024 U	< 0.0041 U
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-12-14	SSHS-B3108-SUB-12-14	1/14/2020	857.55	856.76	-0.79	-	12 - 14 ft	11.21-13.21 ft	180-101038-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-12-14	SSHS-B3113-SUB-12-14	1/14/2020	856.36	856.08	-0.28	-	12 - 14 ft	11.72-13.72 ft	180-101038-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3117	011520 09:00_SSHS-B3117-SUB-12-14	SSHS-B3117-SUB-12-14	1/14/2020	856.54	856.53	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-101038-3	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-12-14	SSHS-B3183-SUB-12-14	1/14/2020	856.70	855.84	-0.86	-	12 - 14 ft	11.14-13.14 ft	180-101038-2	Not Excavated	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-12-14	SSHS-B3184-SUB-12-14	1/14/2020	856.85	855.95	-0.90	-	12 - 14 ft	11.1-13.1 ft	180-101038-2	Not Excavated	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-12-14	SSHS-B3107-SUB-12-14	1/15/2020	857.05	857.26	0.21	-	12 - 14 ft	12.21-14.21 ft	180-101084-2	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-12-14	SSHS-B3109-SUB-12-14	1/15/2020	857.26	856.77	-0.49	-	12 - 14 ft	11.51-13.51 ft	180-101084-2	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-12-14	SSHS-B3110-SUB-12-14	1/15/2020	856.32	856.06	-0.26	-	12 - 14 ft	11.74-13.74 ft	180-101084-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-12-14	SSHS-B3111-SUB-12-14	1/15/2020	857.08	857.00	-0.08	-	12 - 14 ft	11.92-13.92 ft	180-101084-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-12-14	SSHS-B3112-SUB-12-14	1/15/2020	856.71	856.67	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-101084-3	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-12-14	SSHS-B3116-SUB-12-14	1/15/2020	856.51	856.63	0.12	-	12 - 14 ft	12.12-14.12 ft	180-101084-1	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-12-14	SSHS-B3118-SUB-12-14	1/15/2020	856.74	856.72	-0.02	-	12 - 14 ft	11.98-13.98 ft	180-101084-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0010 U	0.0096	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	SSHS-B3493	012221 08:30_SSHS-B3493-SUB-12-14	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated							
Northern Athletic Field	SSHS-B3455	012721 08:30_SSHS-B3455-SUB-12-14	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3247A	012721 08:30_SSHS-B3247A-SUB-12-14	SSHS-B3247A-SUB-12-14	1/26/2021	857.58	857.70	0.12	-	12 - 14 ft	12.12-14.12 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14-20210511	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	0.0019 J	0.0041 J	< 0.0075 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-12-14	SSHS-B3918-SUB-12-14	5/12/2021	854.82	854.84	0.02	-	12 - 14 ft	12.02-14.02 ft	180-121548-2	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.28 U	< 0.024 U	< 0.028 U	< 0.019 U	< 0.24 U	< 0.033 U	< 0.028 U	< 0.094 U
Northern Athletic Field	SSHS-B3923	061921 10:00 SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3926	061921 10:00 SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B4034	072721 09:30 SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.006 U	< 0.00035 U	< 0.00052 U	< 0.00096 U	< 0.0036 U	< 0.00064 U	< 0.0036 U	< 0.00069 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated								
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.0028 U	< 0.00017 U	< 0.00024 U	< 0.00045 U	< 0.0017 U	< 0.0003 U	< 0.0017 U	< 0.00033 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.018 U	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.001 U	< 0.0029 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	0.022 J-	< 0.0005 UJ	< 0.00088 UJ	< 0.0011 UJ	< 0.0017 UJ	< 0.003 UJ	< 0.00083 UJ	< 0.0023 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0039 U	< 0.0031 U	< 0.0033 U	< 0.0030 U	< 0.0053 UT	< 0.0027 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0042 UT	< 0.0015 UT	< 0.0032 UT	< 0.0025 UT	< 0.0027 UT	< 0.0025 UT	< 0.0043 UT	< 0.0022 UT
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00056 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 U	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	0.0040	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00014 U	< 0.00012 U	< 0.00020 U	< 0.00048 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	0.0036	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 U	< 0.00043 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00051 U	< 0.00013 U	< 0.00020 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.0027 U	< 0.00012 UT	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00047 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.0025 U	< 0.00011 UT	< 0.00012 U	< 0.00011 U	< 0.00019 U	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00047 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.0024 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 U	< 0.00042 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 U	< 0.00017 U	< 0.00039 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 UT	< 0.0022 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.02 U	< 0.00068 U	< 0.0012 U	< 0.0015 U	< 0.0023 U	< 0.0041 U	< 0.0011 U	< 0.0032 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00033 UT	< 0.00047 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 UT	< 0.00042 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.0054 U	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated								

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.024 U	< 0.094 U	< 0.047 U	< 0.028 U	< 0.028 U	< 0.024 U	< 0.047 U
Northern Athletic Field	SSHS-B3923	061921 10:00 SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3926	061921 10:00 SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B4034	072721 09:30 SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated							
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.00094 U	< 0.00091 U	< 0.0016 U	< 0.00044 U	< 0.00043 U	< 0.001 U	< 0.0036 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated							
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00044 U	< 0.00043 U	< 0.00076 U	< 0.00021 U	< 0.0002 U	< 0.00047 U	< 0.0017 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.0008 U	< 0.0024 U	< 0.0024 U	< 0.00069 U	< 0.002 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	< 0.00065 UJ	< 0.002 UJ	< 0.002 UJ	< 0.00056 UJ	< 0.0016 UJ	< 0.00098 UJ	< 0.0026 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 UT
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0030 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0014 UT	< 0.0027 UT	< 0.0032 UT	< 0.0017 UT	< 0.0021 UT	< 0.0026 UT	< 0.0035 U
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0018 J	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	0.0018 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.000099 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.000089 U	< 0.000098 U	< 0.00026 U	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.000078 U	< 0.000085 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000097 U	< 0.00020 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00064 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.000085 U	< 0.000093 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.000075 U	< 0.000083 U	< 0.00022 U	< 0.00041 U	< 0.00019 U	< 0.000094 U	< 0.00020 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.000090 U	< 0.000098 U	< 0.00026 U	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.000083 UT	< 0.000091 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 UT	< 0.00021 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.000079 UT	< 0.000086 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000098 UT	< 0.00020 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.000083 U	< 0.000091 U	< 0.00025 U	< 0.00046 U	< 0.00020 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.000074 U	< 0.000082 U	< 0.00022 U	< 0.00041 U	< 0.00018 U	< 0.000093 U	< 0.00019 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.000070 U	< 0.000076 U	< 0.00021 U	< 0.00038 U	< 0.00017 U	< 0.000087 U	< 0.00018 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.00089 U	< 0.0027 U	< 0.0027 U	< 0.00077 U	< 0.0022 U	< 0.0013 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-12-14	SSHS-DW-10 11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated							
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-12-14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated							
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-12-14	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 UT	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.094 U	< 0.019 U	< 0.028 U	< 0.024 U	< 0.024 U	< 0.019 U	< 0.024 U	< 0.028 U
Northern Athletic Field	SSHS-B3923	061921 10:00 SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3926	061921 10:00 SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B4034	072721 09:30 SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.0033 U	< 0.00092 U	< 0.00059 U	< 0.00056 U	< 0.00037 U	< 0.001 U	< 0.00087 U	< 0.00036 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated								
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.0015 U	< 0.00043 U	< 0.00028 U	< 0.00026 U	< 0.00017 U	< 0.00047 U	< 0.00041 U	< 0.00017 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 UJ	< 0.00098 U	< 0.00072 U	< 0.00077 UJ	< 0.00061 U	< 0.00068 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	< 0.0086 UJ	< 0.00055 UJ	< 0.00067 UJ	< 0.00079 UJ	< 0.00058 UJ	< 0.00063 UJ	< 0.00049 UJ	< 0.00055 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0041 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	0.0051 J	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0049 UT	< 0.0015 UT	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 UT	< 0.0016 UT
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.00064 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.00058 U	< 0.000091 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.00050 U	< 0.000079 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.000099 U	< 0.000091 U	< 0.00013 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.00055 U	< 0.000086 U	< 0.00016 U	< 0.00017 U	< 0.00018 U	< 0.00011 U	< 0.000099 U	< 0.00014 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.00049 U	< 0.000077 U	< 0.00014 U	< 0.00015 U	< 0.00016 U	< 0.000096 U	< 0.000088 U	< 0.00013 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.00058 U	< 0.000091 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.00053 U	< 0.000084 U	< 0.00016 U	< 0.00017 UT	< 0.00017 UT	< 0.00011 UT	< 0.000096 U	< 0.00014 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.00051 U	< 0.000080 UT	< 0.00015 U	< 0.00016 UT	< 0.00016 UT	< 0.00010 UT	< 0.000092 UT	< 0.00013 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.00054 U	< 0.000085 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000097 U	< 0.00014 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.00048 U	< 0.000076 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000095 U	< 0.000087 U	< 0.00012 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	0.00065 J	< 0.000071 U	< 0.00013 U	< 0.00014 U	< 0.00014 U	< 0.000089 U	< 0.000081 U	< 0.00012 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.012 U	< 0.00075 U	< 0.00092 U	< 0.0011 U	< 0.00080 U	< 0.00086 U	< 0.00068 U	< 0.00075 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.24 U	< 0.047 U	< 0.24 U	< 0.24 U	< 0.24 U	< 0.019 U	< 0.24 U	< 0.019 U
Northern Athletic Field	SSHS-B3923	061921 10:00 SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3926	061921 10:00 SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B4034	072721 09:30 SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.00087 U	< 0.0037 U	< 0.00091 U	< 0.00074 U	< 0.0036 U	< 0.001 U	< 0.0031 U	< 0.00049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated								
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00041 U	< 0.0018 U	< 0.00043 U	< 0.00035 U	< 0.0017 U	< 0.00049 U	< 0.0015 U	< 0.00023 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0012 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00092 UJ
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	< 0.0013 UJ	< 0.0008 UJ	< 0.0011 UJ	< 0.001 UJ	< 0.00061 UJ	< 0.0021 UJ	< 0.0026 UJ	< 0.00075 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0025 UT	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0030 UT	< 0.0054 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0030 U	< 0.0024 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0024 UT	< 0.0044 UT	< 0.0016 UT	< 0.0019 UT	< 0.0014 UT	< 0.0024 UT	< 0.0024 UT	< 0.0020 UT
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 UT	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.00010 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.000099 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000088 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000096 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.000096 U	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00018 U	< 0.00012 U	< 0.00011 U	< 0.000085 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.00010 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000093 UT
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 UT	< 0.00012 UT	< 0.00012 UT	< 0.000088 UT
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000093 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.000095 U	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00018 U	< 0.00011 U	< 0.00011 U	< 0.000084 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.000089 U	< 0.00015 U	< 0.00014 U	< 0.000097 U	< 0.00017 U	< 0.00011 U	< 0.00010 U	< 0.000078 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0014 U	< 0.0014 U	< 0.00083 U	< 0.0028 U	< 0.0036 U	< 0.0010 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-13_14	060622 10:25 SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00033 U	< 0.00024 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.028 U	< 0.047 U	< 0.019 U	< 0.047 U	< 0.028 U	< 0.094 U	< 0.047 U	< 0.024 U
Northern Athletic Field	SSHS-B3923	061921 10:00_SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3926	061921 10:00_SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B4034	072721 09:30_SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0036 U	< 0.0011 U	< 0.0043 U	< 0.0011 U	< 0.0026 U	< 0.0023 U	< 0.0007 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated								
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00077 U	< 0.0017 U	< 0.00051 U	< 0.002 U	< 0.00051 U	< 0.0012 U	< 0.0011 U	< 0.00033 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 UJ	< 0.003 U	0.0015 J	< 0.0031 U	< 0.0033 U	< 0.0017 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	< 0.00091 UJ	< 0.0029 UJ	< 0.0014 UJ	0.0028 J	< 0.00088 UJ	< 0.0025 UJ	< 0.0026 UJ	< 0.0014 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0021 U	< 0.0034 U	< 0.0097 UT	< 0.0032 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0024 U	< 0.0019 UT	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0022 UT	< 0.0017 UT	< 0.0028 UT	< 0.0080 UT	< 0.0026 UT	< 0.0028 UT	< 0.0020 UT	< 0.0016 UT
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.00017 U	< 0.00096 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00087 U	< 0.00029 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.00015 U	< 0.00086 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00019 U	< 0.00078 U	< 0.00026 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00075 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00069 U	< 0.00023 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00082 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00075 U	< 0.00025 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00073 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00016 U	< 0.00066 U	< 0.00022 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.00015 U	< 0.00087 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00019 U	< 0.00079 U	< 0.00026 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.00014 U	< 0.00080 UT	< 0.00013 UT	< 0.0020 U	< 0.00023 UT	< 0.00017 U	< 0.00073 UT	< 0.00024 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.00013 U	< 0.00076 UT	< 0.00013 UT	< 0.0019 U	< 0.00022 UT	< 0.00016 U	< 0.00069 UT	< 0.00023 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00080 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00073 U	< 0.00024 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00072 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00015 U	< 0.00065 U	< 0.00022 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.00012 U	< 0.00067 U	< 0.00011 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00061 U	< 0.00020 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0021 UT	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.0013 U	< 0.0040 U	< 0.0019 U	< 0.0033 U	< 0.0012 U	< 0.0035 U	< 0.0036 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-12-14	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-12-14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated								
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-12-14	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated								

DRAFT

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.019 U	< 0.019 U	< 0.024 U	< 0.028 U	< 0.24 U	< 0.24 U	< 0.028 U
Northern Athletic Field	SSHS-B3923	061921 10:00 SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3926	061921 10:00 SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B4034	072721 09:30 SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated							
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.00036 U	< 0.0012 U	< 0.00096 U	< 0.00054 U	< 0.00076 U	< 0.00043 U	< 0.00052 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated							
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00017 U	< 0.00055 U	< 0.00045 U	0.00029 J	< 0.00036 U	< 0.0002 U	< 0.00024 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	< 0.00083 UJ	< 0.001 UJ	< 0.00052 UJ	< 0.00055 UJ	< 0.0021 UJ	< 0.0018 UJ	< 0.0013 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 UT	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0016 UT	< 0.0016 UT	< 0.0022 UT	< 0.0016 UT	< 0.0030 U	< 0.0028 U	< 0.0018 UT
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00011 U	0.00035 J	< 0.00012 U	< 0.000091 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.00012 U	< 0.000094 U	0.00032 J	< 0.00010 U	< 0.000080 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000087 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.00012 U	< 0.000091 U	< 0.00013 U	< 0.00010 U	< 0.000077 U	< 0.00015 U	< 0.000099 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.0000092 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.00013 UT	< 0.00010 U	< 0.00014 U	< 0.00011 UT	< 0.000085 UT	< 0.00017 UT	< 0.00011 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.00012 UT	< 0.000095 UT	0.00025 J	< 0.00010 UT	< 0.000080 UT	< 0.00016 UT	< 0.00010 U
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00014 U	< 0.00011 U	< 0.000085 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.00012 U	< 0.000090 U	< 0.00013 U	< 0.000098 U	< 0.000076 U	< 0.00015 U	< 0.000098 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.00011 U	< 0.000084 U	< 0.00012 U	< 0.000092 U	< 0.000071 U	< 0.00014 U	< 0.000092 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.00071 U	< 0.00075 U	< 0.0029 U	< 0.0024 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-12-14	SSHS-DW-10 11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated							
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-12-14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated							
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-12-14	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	0.00071 J	< 0.00026 U	< 0.00037 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14-20210512	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14-20210517	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14-20210518	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-12-14	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated	< 0.024 U	< 0.024 U	< 0.033 U	< 0.028 U	0.069 J	0.023 J	0.092 J
Northern Athletic Field	SSHS-B3923	061921 10:00 SSHS-B3923-SUB-12-14	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3926	061921 10:00 SSHS-B3926-SUB-12-14	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-12-14	SSHS-B3928-SUB-12-14	6/18/2021	853.07	854.10	1.03	-	12 - 14 ft	13.03-15.03 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-12-14	SSHS-B3929-SUB-12-14	6/18/2021	854.16	854.85	0.69	-	12 - 14 ft	12.69-14.69 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B4034	072721 09:30 SSHS-B4034-SUB-12-14	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated							
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-12-14	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated	< 0.00093 U	< 0.0016 U	< 0.00068 U	< 0.00087 U	< 0.0012 U	< 0.00093 U	< 0.0012 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-12-14	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated							
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-12-14	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00044 U	< 0.00074 U	< 0.00032 U	< 0.00041 U	< 0.00057 U	< 0.00044 U	< 0.00057 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-12-14	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated	< 0.00099 U	< 0.00056 U	< 0.0024 U	< 0.0016 U	< 0.00069 UJ	< 0.00076 U	< 0.0014 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-12-14	SSHS-B4264-SUB-12-14	11/1/2021	852.29	853.31	1.02	-	12 - 14 ft	13.02-15.02 ft	180-129325-1	Not Excavated	< 0.00081 UJ	0.0019 J	< 0.0019 UJ	< 0.0013 UJ	< 0.00056 UJ	< 0.00061 UJ	< 0.0011 UJ
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27-20220119	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	S599	SSHS-IRM5A2-S599-20220119	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S600	SSHS-IRM5A2-S600-20220119	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 0.0011 U	< 0.0018 UT	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	S601	SSHS-IRM5A2-S601-20220119	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	S602	SSHS-IRM5A2-S602-20220120	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	S592	SSHS-IRM5A2-S592-20220208	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 0.0013 U	< 0.0021 U	< 0.0055 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0095 U
Northern Athletic Field	S596	SSHS-IRM5A2-S596-20220208	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 0.0011 U	0.0027 J	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S277	SSHS-IRM5A2-S277-20220208	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S591	SSHS-IRM5A2-S591-20220209	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 UT	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	S590	SSHS-IRM5A2-S590-20220209	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45-20220221	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	S588	SSHS-IRM5A2-S588-20220221	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S586	SSHS-IRM5A2-S586-20220221	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S587	SSHS-IRM5A2-S587-20220221	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589-20220221	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	B595	SSHS-IRM5A2-B595-20220302	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 UT	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	B596	SSHS-IRM5A2-B596-20220302	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 0.0011 UT	< 0.0017 UT	< 0.0045 UT	< 0.0039 UT	< 0.0019 UT	< 0.0022 UT	< 0.0078 UT
Northern Athletic Field	S282	SSHS-IRM5A2-S282-20220303	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 0.0011 U	0.0027 J	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S283	SSHS-IRM5A2-S283-20220314	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53-20220318	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000097 U	< 0.00011 U	< 0.00036 U
Northern Athletic Field	S319	SSHS-IRM5A2-S319-20220318	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 0.000090 U	0.00018 J	< 0.00020 U	< 0.00027 U	< 0.000088 U	< 0.000098 U	< 0.00032 U
Northern Athletic Field	S318	SSHS-IRM5A2-S318-20220318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 0.000078 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000077 U	< 0.000085 U	< 0.00028 U
Northern Athletic Field	S317	SSHS-IRM5A2-S317-20220318	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00042 U
Northern Athletic Field	S316	SSHS-IRM5A2-S316-20220318	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 0.000086 U	< 0.00015 U	< 0.00020 U	< 0.00026 U	< 0.000084 U	< 0.000093 U	< 0.00031 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315-20220318	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 0.000076 U	< 0.00014 U	< 0.00017 U	< 0.00023 U	< 0.000074 U	< 0.000083 U	< 0.00027 U
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A-20220318	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 0.000090 U	< 0.00016 U	< 0.00021 U	< 0.00028 U	< 0.000088 U	< 0.000098 U	< 0.00033 U
Northern Athletic Field	S314	SSHS-IRM5A2-S314-20220318	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 0.000083 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000081 UT	< 0.000091 UT	< 0.00030 UT
Northern Athletic Field	S313	SSHS-IRM5A2-S313-20220318	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 0.000079 UT	< 0.00014 UT	< 0.00018 U	< 0.00024 U	< 0.000077 UT	< 0.000086 UT	< 0.00029 UT
Northern Athletic Field	B697	SSHS-IRM5A2-B697-20220318	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	S284	SSHS-IRM5A2-S284-20220318	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00037 U
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A-20220318	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 0.000084 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000082 U	< 0.000091 U	< 0.00030 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285-20220318	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 0.000075 U	< 0.00014 U	< 0.00017 U	< 0.00023 U	< 0.000073 U	< 0.000082 U	< 0.00027 U
Northern Athletic Field	S286	SSHS-IRM5A2-S286-20220318	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 0.000070 U	< 0.00013 U	< 0.00016 U	< 0.00022 U	< 0.000069 U	< 0.000076 U	< 0.00025 U
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1-20220330	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2-20220330	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3-20220330	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	S730	SSHS-IRM5A2-S730-20220418	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1-20220425	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 0.0011 U	< 0.00062 U	< 0.0026 U	< 0.0017 U	< 0.00076 U	< 0.00084 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-12-14	SSHS-DW-10 11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated							
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-12-14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-12-14	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated							
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-12-14	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-12-14	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT-20220610	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2-20220610	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2-20220610	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220611	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220611	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220611	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220611	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220611	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220611	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220611	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220611	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220611	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220611	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220611	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220611	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220611	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220611	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	0.032	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	0.0091	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.0048 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	0.0064	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	0.0076	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	0.0083	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	0.0071	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	0.061	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	0.0051 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	0.0057	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	0.0061	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	0.0067 T	< 0.00026 UT	< 0.00028 UT	< 0.00026 UT	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	0.0091	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	0.0028	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00047 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated								
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.0030 U	< 0.00013 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	0.0080	0.00016 J	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00056 U	0.00040 J	< 0.00022 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.0017 U	< 0.000076 U	< 0.000082 U	< 0.000075 U	< 0.00012 U	< 0.00029 U	< 0.000078 U	< 0.00011 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	0.00090 J	< 0.00047 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.0055 U	0.0025 J	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.0055 U	0.00034 J	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00046 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	0.0092 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 UJ	< 0.0033 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 UJ	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 UJ	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 UT	< 0.00099 U	< 0.00044 UT	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 UT	< 0.0011 U	< 0.00051 UT	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 UT	< 0.00085 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0023 J	< 0.0022 U	< 0.0027 U	< 0.0036 UT
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 UT	< 0.00080 U	< 0.00036 UT	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 UT	< 0.00081 U	< 0.00036 UT	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 UT	< 0.00095 U	< 0.00043 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 UT	< 0.00091 U	< 0.00041 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 UT	< 0.00093 U	< 0.00042 UT	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 UT	< 0.00083 U	< 0.00037 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	0.0035 J	< 0.0024 U	< 0.0029 U	< 0.0039 UT
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 UT	< 0.00099 U	< 0.00044 UT	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 UT	< 0.00085 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0027 J	< 0.0022 U	< 0.0026 U	< 0.0036 UT
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 UT	< 0.00088 U	< 0.00039 UT	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 UT	< 0.00091 U	< 0.00041 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	< 0.00018 UT	< 0.00020 UT	< 0.00053 UT	< 0.00098 UT	< 0.00044 UT	< 0.00022 U	< 0.00046 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 UT	< 0.00085 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 UT	< 0.00082 U	< 0.00037 UT	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 UT	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 UT	< 0.00095 U	< 0.00043 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	0.0021 J	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0027 J	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0021 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.000084 U	< 0.000092 U	< 0.00025 UT	< 0.00046 U	< 0.00021 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated							
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated							
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated							
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.000092 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00023 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00029 U	< 0.00055 U	< 0.00025 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.000052 U	< 0.000057 U	< 0.00015 U	< 0.00028 U	< 0.00013 U	< 0.000065 U	< 0.00013 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.00021 U	< 0.00024 U	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00044 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00044 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 UT	< 0.0035 UT	< 0.0017 UT	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 UT	< 0.0037 UT	< 0.0018 UT	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 UT	< 0.0034 UT	< 0.0017 UT	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	< 0.0012 U	< 0.00018 UT	< 0.00034 U	< 0.00036 UT	< 0.00037 UT	< 0.00023 UT	< 0.00021 UT	< 0.00030 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.00054 U	< 0.000085 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000097 U	< 0.00014 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated								
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.00034 U	< 0.000053 U	< 0.000099 U	< 0.00011 U	< 0.00011 U	< 0.000066 U	< 0.000060 U	< 0.000087 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 UT	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0037 U	< 0.0027 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0039 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0035 U	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00039 UT	< 0.00036 UT	< 0.00025 UT	< 0.00043 UT	< 0.00028 UT	< 0.00027 UT	< 0.00020 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000094 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated								
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.000066 U	< 0.00011 U	< 0.00010 U	< 0.000072 U	< 0.00012 U	< 0.000080 U	< 0.000078 U	< 0.000058 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.003 U	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 UJ	< 0.0017 UJ	< 0.0021 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 UJ	< 0.0018 UJ	< 0.0022 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0031 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0026 U	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U	< 0.002 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.003 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	0.0089	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	0.015	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 UT	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	< 0.00030 U	< 0.0017 UT	< 0.00029 UT	< 0.0043 U	< 0.00050 UT	< 0.00037 UT	< 0.0016 UT	< 0.00052 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.00014 U	< 0.00081 U	< 0.00013 U	< 0.0020 U	< 0.00024 U	< 0.00017 U	< 0.00073 U	< 0.00024 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated								
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated								
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	0.00068 J	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	0.00073 J	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.00016 U	< 0.00089 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	< 0.00017 U	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.000088 U	< 0.00050 U	< 0.000084 U	< 0.0013 U	< 0.00015 U	< 0.00011 U	< 0.00046 U	< 0.00015 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.002 U	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0017 U	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0034 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.002 U	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UT	< 0.0029 UT	< 0.0019 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 UT	< 0.0030 UT	< 0.0020 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 UT	< 0.0030 UT	< 0.0028 UT	< 0.0018 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	< 0.00028 UT	< 0.00022 UT	< 0.00031 UT	< 0.00024 UT	< 0.00018 UT	< 0.00036 UT	< 0.00024 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00014 U	< 0.00011 U	< 0.000085 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated							
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated							
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated							
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 UT
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	0.00028 J	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00032 J	< 0.00019 U	< 0.00037 U	< 0.00024 UT
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	0.00014 J	< 0.000094 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	0.00047 J	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.000081 U	< 0.000063 U	< 0.000089 U	< 0.000069 U	< 0.000053 U	< 0.00010 U	< 0.000068 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	0.00036 J	< 0.00021 U	< 0.00030 U	0.00035 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00044 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00052 J	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	0.00038 J	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	0.00087 J	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U	< 0.0023 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U	< 0.0026 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220611	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220611	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220611	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220611	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated							
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114-20220613	SSHS-IRM5A2-DUP114	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115-20220613	SSHS-IRM5A2-DUP115	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 UT	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113-20220613	SSHS-IRM5A2-DUP113	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00035 U	< 0.00048 UT	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116-20220613	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200-20220613	SSHS-IRM5A2-A4-S1200	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 UT	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202-20220613	SSHS-IRM5A2-A4-S1202	6/13/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 UT	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201-20220613	SSHS-IRM5A2-A4-S1201	6/13/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203-20220613	SSHS-IRM5A2-A4-S1203	6/13/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204-20220613	SSHS-IRM5A2-A4-S1204	6/13/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205-20220613	SSHS-IRM5A2-A4-S1205	6/13/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 UT	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12-20220613	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206-20220613	SSHS-IRM5A2-A4-S1206	6/13/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395962	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207-20220613	SSHS-IRM5A2-A4-S1207	6/13/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 UT	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6-20220613	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	0.0024 J	0.0026 J	< 0.0080 U
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208-20220613	SSHS-IRM5A2-A4-S1208	6/13/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209-20220613	SSHS-IRM5A2-A4-S1209	6/13/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250-20220613	SSHS-IRM5A2-A4-B1250	6/13/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395962	Not Excavated	< 0.00018 UT	< 0.00032 UT	< 0.00041 U	< 0.00055 UT	< 0.00018 UT	< 0.00020 UT	< 0.00018 UT
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251-20220613	SSHS-IRM5A2-A4-B1251	6/13/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395962	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 UT	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252-20220613	SSHS-IRM5A2-A4-B1252	6/13/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395962	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 UT	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253-20220613	SSHS-IRM5A2-A4-B1253	6/13/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395962	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254-20220613	SSHS-IRM5A2-A4-B1254	6/13/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395962	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7-20220613	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8-20220613	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9-20220613	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10-20220614	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated	< 0.000084 U	0.00037 J	< 0.00019 U	< 0.00026 U	< 0.000082 U	< 0.000092 U	< 0.000082 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-12-14	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated							
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-12-14	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated							
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-12-14	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated							
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200-20220808	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201-20220808	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206-20220808	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220813	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220813	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220813	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95-20220815	SSHS-IRM5A2-FISR-S95	8/15/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429581	Not Excavated	< 0.000092 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99-20220815	SSHS-IRM5A2-FISR-S99	8/15/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429581	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	0.00019 J	< 0.00011 U	0.00019 J
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19-20220815	SSHS-IRM5A2-FISR-BOT19	8/15/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429581	Not Excavated	< 0.000052 U	< 0.000094 U	< 0.00012 U	< 0.00016 U	< 0.000051 U	< 0.000057 U	< 0.000051 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86-20220818	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90-20220818	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18-20220818	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206-20220824	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201-20220824	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	0.00029 J	< 0.00019 U	0.00029 J
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210-20220825	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	0.00019 J	< 0.00016 U	0.00019 J
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400-20220825	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401-20220825	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402-20220825	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	0.00030 J	< 0.00019 U	0.00030 J
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403-20220825	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400-20220825	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	0.00047 J	< 0.00019 U	0.00047 J
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203-20220825	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204-20220825	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402-20220825	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405-20220825	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8-20230530	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9-20230530	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16-20230601	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34-20230602	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-14-16	SSHS-S3060-SUB-14-16	8/28/2019	856.96	855.38	-1.58	-	14 - 16 ft	12.42-14.42 ft	180-94900-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0023 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-14-16	SSHS-B3087-SUB-14-16	8/30/2019	857.68	857.65	-0.03	-	14 - 16 ft	13.97-15.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-14-16	SSHS-B3222-SUB-14-16	8/30/2019	858.28	858.08	-0.20	-	14 - 16 ft	13.8-15.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0032 U	< 002 U	< 002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Northern Athletic Field	SSHS-B3103	011420 09:00_SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.003 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0025 U	< 0.0042 U	< 0.0028 U	< 0.0031 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3904	050821 10:00_SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3906	051121 10:30_SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0029 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3894	051221 10:30_SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	0.022	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3902	051321 10:15_SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3893	051521 09:00_SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3901	051521 09:00_SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3888	051521 09:00_SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3892	051521 09:00_SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3900	051521 09:00_SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3896	051821 09:00_SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3912	051821 09:00_SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3897	051821 09:00_SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3886	051921 10:30_SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3910	061121 09:00_SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated								
Northern Athletic Field	SSHS-B3911	061221 09:00_SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3913	061221 09:00_SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.00024 U	< 0.00035 U	< 0.00064 U	< 0.0024 U	< 0.00043 U	< 0.0024 U	< 0.00047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	0.0068 J	0.00037 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	0.018 J	< 0.00032 U	< 0.00047 U	< 0.00086 U	< 0.0032 U	< 0.00058 U	< 0.0032 U	< 0.00062 U
Northern Athletic Field	SSHS-B3885	092321 09:30_SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated								
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.02 U	< 0.00065 U	< 0.0012 U	< 0.0014 U	< 0.0022 U	< 0.0039 U	< 0.0011 U	< 0.003 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.016 U	< 0.00052 U	< 0.00092 U	< 0.0011 U	< 0.0018 U	< 0.0031 U	< 0.00086 U	< 0.0024 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 UT	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0039 UT	< 0.0014 UT	< 0.0030 UT	< 0.0023 UT	< 0.0025 UT	< 0.0023 UT	< 0.0040 UT	< 0.0020 UT
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	0.0050 J	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Northern Athletic Field	SSHS-B3103	011420 09:00_SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0036 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3904	050821 10:00_SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3906	051121 10:30_SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated							
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated							
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3894	051221 10:30_SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated							
Northern Athletic Field	SSHS-B3902	051321 10:15_SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3893	051521 09:00_SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated							
Northern Athletic Field	SSHS-B3901	051521 09:00_SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated							
Northern Athletic Field	SSHS-B3888	051521 09:00_SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3892	051521 09:00_SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3900	051521 09:00_SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3896	051821 09:00_SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3912	051821 09:00_SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3897	051821 09:00_SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SSHS-B3886	051921 10:30_SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated							
Northern Athletic Field	SSHS-B3910	061121 09:00_SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated							
Northern Athletic Field	SSHS-B3911	061221 09:00_SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated							
Northern Athletic Field	SSHS-B3913	061221 09:00_SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated							
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated							
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00063 U	< 0.00062 U	< 0.0011 U	< 0.0003 U	< 0.00029 U	< 0.00067 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.00088 U	< 0.00085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.00085 U	< 0.00082 U	< 0.0015 U	< 0.0004 U	< 0.00039 U	< 0.0009 U	< 0.0032 U
Northern Athletic Field	SSHS-B3885	092321 09:30_SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated							
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.00086 U	< 0.0026 U	< 0.0026 U	< 0.00074 U	< 0.0021 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00068 U	< 0.0021 U	< 0.002 U	< 0.00058 U	< 0.0017 U	0.0013 J	< 0.0027 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 UT	< 0.0021 U	< 0.0029 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 UT	< 0.0021 U	< 0.0028 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0037 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 UT	< 0.0023 U	< 0.0031 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 UT	< 0.0023 U	< 0.0032 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0013 UT	< 0.0025 UT	< 0.0029 UT	< 0.0016 UT	< 0.0020 UT	< 0.0024 UT	< 0.0032 U
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0043 U	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.004 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	0.011	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3103	011420 09:00_SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.0036 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.00096 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3904	050821 10:00_SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3906	051121 10:30_SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3894	051221 10:30_SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3902	051321 10:15_SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B3893	051521 09:00_SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3901	051521 09:00_SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3888	051521 09:00_SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3892	051521 09:00_SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3900	051521 09:00_SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3896	051821 09:00_SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3912	051821 09:00_SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3897	051821 09:00_SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3886	051921 10:30_SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3910	061121 09:00_SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated								
Northern Athletic Field	SSHS-B3911	061221 09:00_SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3913	061221 09:00_SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.0022 U	< 0.00062 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00067 U	< 0.00059 U	< 0.00024 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00033 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.003 U	< 0.00083 U	< 0.00053 U	< 0.0005 U	< 0.00033 U	< 0.0009 U	< 0.00079 U	< 0.00032 U
Northern Athletic Field	SSHS-B3885	092321 09:30_SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated								
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.00072 U	< 0.00088 U	< 0.001 U	< 0.00076 U	< 0.00082 U	< 0.00065 U	< 0.00072 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.0089 U	< 0.00057 U	< 0.0007 U	< 0.00082 U	< 0.0006 U	< 0.00065 U	< 0.00051 U	< 0.00057 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 UT	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UT	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UT	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0045 UT	< 0.0014 UT	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 UT	< 0.0014 UT
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0028 U	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Northern Athletic Field	SSHS-B3103	011420 09:00_SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.0027 U	< 0.0037 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0016 U	< 0.002 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3904	050821 10:00_SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3906	051121 10:30_SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0029 U	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3894	051221 10:30_SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3902	051321 10:15_SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0023 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B3893	051521 09:00_SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3901	051521 09:00_SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3888	051521 09:00_SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3892	051521 09:00_SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	SSHS-B3900	051521 09:00_SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3896	051821 09:00_SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3912	051821 09:00_SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3897	051821 09:00_SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3886	051921 10:30_SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3910	061121 09:00_SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated								
Northern Athletic Field	SSHS-B3911	061221 09:00_SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3913	061221 09:00_SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00059 U	< 0.0025 U	< 0.00062 U	< 0.0005 U	< 0.0024 U	< 0.00069 U	< 0.0021 U	< 0.00033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00085 U	< 0.00069 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.00046 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.00079 U	< 0.0034 U	< 0.00082 U	< 0.00066 U	< 0.0032 U	< 0.00093 U	< 0.0028 U	< 0.00044 U
Northern Athletic Field	SSHS-B3885	092321 09:30_SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated								
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.0017 U	< 0.0011 U	< 0.0014 U	< 0.0013 U	< 0.00079 U	< 0.0027 U	< 0.0035 U	< 0.00098 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.00083 U	< 0.0011 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0027 U	< 0.00078 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0023 UT	< 0.0041 UT	< 0.0015 UT	< 0.0018 UT	< 0.0013 UT	< 0.0022 UT	< 0.0023 UT	< 0.0019 UT
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0019 U	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0028 U	< 0.0018 U	< 0.0036 U
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U
Northern Athletic Field	SSHS-B3103	011420 09:00 SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.0018 U	< 0.0039 U	< 0.0022 U	< 0.0055 U	< 0.002 U	< 0.0027 U	< 0.0017 U	< 0.0035 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3904	050821 10:00 SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3909	050821 10:00 SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30 SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3906	051121 10:30 SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated								
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3894	051221 10:30 SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30 SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3890	051321 10:15 SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3902	051321 10:15 SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3893	051521 09:00 SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3901	051521 09:00 SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated								
Northern Athletic Field	SSHS-B3888	051521 09:00 SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3892	051521 09:00 SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3900	051521 09:00 SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated								
Northern Athletic Field	SSHS-B3887	051821 09:00 SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3896	051821 09:00 SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3912	051821 09:00 SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3897	051821 09:00 SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3886	051921 10:30 SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30 DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30 SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3910	061121 09:00 SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated								
Northern Athletic Field	SSHS-B3911	061221 09:00 SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3913	061221 09:00 SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated								
Northern Athletic Field	SSHS-B3017A	061821 09:00 SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated								
Northern Athletic Field	SSHS-B3928	061921 10:00 SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3929	061921 10:00 SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated								
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.0011 U	< 0.0024 U	< 0.00072 U	< 0.0029 U	< 0.00073 U	< 0.0018 U	< 0.0016 U	< 0.00047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 UJ	< 0.034 U	< 0.034 U	< 0.00065 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.0015 U	< 0.0032 U	< 0.00097 U	< 0.0039 U	< 0.00098 U	< 0.0024 U	< 0.0021 U	< 0.00063 U
Northern Athletic Field	SSHS-B3885	092321 09:30 SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated								
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.0012 U	< 0.0038 U	< 0.0018 U	< 0.0032 U	< 0.0011 U	< 0.0033 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00095 U	< 0.003 U	< 0.0014 U	< 0.0025 U	0.0021 J	< 0.0026 U	< 0.0028 U	< 0.0015 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0066 U	< 0.0021 U	< 0.0023 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.0019 U	< 0.0015 UT	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.0020 U	< 0.0015 UT	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0020 UT	< 0.0016 UT	< 0.0026 UT	< 0.0074 UT	< 0.0024 UT	< 0.0025 UT	< 0.0018 UT	< 0.0015 UT
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0013 U	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0042 U	< 0.0028 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U
Northern Athletic Field	SSHS-B3103	011420 09:00_SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.0013 U	< 0.0028 U	< 0.0019 U	< 0.0016 U	< 0.0033 U	< 0.0035 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3904	050821 10:00_SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3906	051121 10:30_SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated							
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated							
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3894	051221 10:30_SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated							
Northern Athletic Field	SSHS-B3902	051321 10:15_SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SSHS-B3893	051521 09:00_SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated							
Northern Athletic Field	SSHS-B3901	051521 09:00_SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated							
Northern Athletic Field	SSHS-B3888	051521 09:00_SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3892	051521 09:00_SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3900	051521 09:00_SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3896	051821 09:00_SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3912	051821 09:00_SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3897	051821 09:00_SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3886	051921 10:30_SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated							
Northern Athletic Field	SSHS-B3910	061121 09:00_SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated							
Northern Athletic Field	SSHS-B3911	061221 09:00_SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated							
Northern Athletic Field	SSHS-B3913	061221 09:00_SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated							
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated							
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00024 U	< 0.00078 U	< 0.00064 U	0.00037 J	< 0.00051 U	< 0.00029 U	< 0.00035 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0009 U	0.0014 J	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.00032 U	< 0.001 U	< 0.00086 U	< 0.00049 U	< 0.00068 U	< 0.00039 U	< 0.00047 U
Northern Athletic Field	SSHS-B3885	092321 09:30_SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated							
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.0011 U	< 0.0013 U	< 0.00068 U	0.00079 J	< 0.0028 U	< 0.0023 U	< 0.0017 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00086 U	< 0.0011 U	0.0035 J	0.0014 J	< 0.0022 U	< 0.0019 U	< 0.0013 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.0013 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0015 UT	< 0.0015 UT	< 0.0020 UT	< 0.0014 UT	< 0.0028 U	< 0.0025 U	< 0.0017 UT
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.00026 U	< 0.00020 U	0.00093 J	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.00023 U	< 0.00018 U	0.0012	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-14-16	SSHS-B3086-SUB-14-16	9/4/2019	857.77	857.49	-0.28	-	14 - 16 ft	13.72-15.72 ft	180-95165-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0025 U	< 0.0015 U	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-14-16	SSHS-B3246-SUB-14-16	12/20/2019	858.13	857.94	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-100361-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3103	011420 09:00_SSHS-B3103-SUB-14-16	SSHS-B3103-SUB-14-16	1/13/2020	856.47	856.36	-0.11	-	14 - 16 ft	13.89-15.89 ft	180-100985-2	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0014 U	< 0.0034 U	< 0.0018 U	< 0.0023 U	< 0.004 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16-20210506	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3904	050821 10:00_SSHS-B3904-SUB-14-16	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-14-16	SSHS-B3909-SUB-14-16	5/7/2021	857.06	856.73	-0.33	-	14 - 16 ft	13.67-15.67 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-14-16	SSHS-B3905-SUB-14-16	5/10/2021	856.83	856.65	-0.18	-	14 - 16 ft	13.82-15.82 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3906	051121 10:30_SSHS-B3906-SUB-14-16	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3882	DUP-1-20210510	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated							
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0054 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated							
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3894	051221 10:30_SSHS-B3894-SUB-14-16	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-14-16	SSHS-B3908-SUB-14-16	5/11/2021	856.72	856.50	-0.22	-	14 - 16 ft	13.78-15.78 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16-20210511	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	0.0053	0.0021 J	< 0.0076 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-14-16	SSHS-B3890-SUB-14-16	5/12/2021	856.79	856.60	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121548-1	Not Excavated							
Northern Athletic Field	SSHS-B3902	051321 10:15_SSHS-B3902-SUB-14-16	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-14-16	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16-20210513	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	SSHS-B3893	051521 09:00_SSHS-B3893-SUB-14-16	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated							
Northern Athletic Field	SSHS-B3901	051521 09:00_SSHS-B3901-SUB-14-16	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated							
Northern Athletic Field	SSHS-B3888	051521 09:00_SSHS-B3888-SUB-14-16	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3892	051521 09:00_SSHS-B3892-SUB-14-16	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3899	DUP-21-20210514	DUP-21	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16-20210514	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3900	051521 09:00_SSHS-B3900-SUB-14-16	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated							
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-14-16	SSHS-B3887-SUB-14-16	5/15/2021	855.62	854.16	-1.46	-	14 - 16 ft	12.54-14.54 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3896	051821 09:00_SSHS-B3896-SUB-14-16	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3912	051821 09:00_SSHS-B3912-SUB-14-16	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3897	051821 09:00_SSHS-B3897-SUB-14-16	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3886	051921 10:30_SSHS-B3886-SUB-14-16	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_DUP-20	DUP-20	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-14-16	SSHS-B3898-SUB-14-16	5/18/2021	856.45	856.26	-0.19	-	14 - 16 ft	13.81-15.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16-20210518	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-14-16-20210519	SSHS-B3903-SUB-14-16	5/19/2021	856.98	855.02	-1.96	-	14 - 16 ft	12.04-14.04 ft	1801219031	Not Excavated							
Northern Athletic Field	SSHS-B3910	061121 09:00_SSHS-B3910-SUB-14-16	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated							
Northern Athletic Field	SSHS-B3911	061221 09:00_SSHS-B3911-SUB-14-16	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated							
Northern Athletic Field	SSHS-B3913	061221 09:00_SSHS-B3913-SUB-14-16	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated							
Northern Athletic Field	SSHS-B3017A	061821 09:00_SSHS-B3017A-SUB-14-16	SSHS-B3017A-SUB-14-16	6/17/2021	853.79	853.15	-0.64	-	14 - 16 ft	13.36-15.36 ft	180-123398-1	Not Excavated							
Northern Athletic Field	SSHS-B3928	061921 10:00_SSHS-B3928-SUB-14-16	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3929	061921 10:00_SSHS-B3929-SUB-14-16	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated							
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-14-16	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00062 U	< 0.0011 U	< 0.00045 U	< 0.00059 U	< 0.00081 U	< 0.00063 U	< 0.00081 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-14-16	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.00084 U	< 0.0014 U	< 0.00061 U	< 0.00079 U	< 0.0011 U	< 0.00084 U	< 0.0011 U
Northern Athletic Field	SSHS-B3885	092321 09:30_SSHS-B3885-SUB-14-16	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated							
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-14-16	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated	< 0.0011 U	< 0.00059 U	< 0.0025 U	< 0.0017 U	0.00086 J	< 0.0008 U	< 0.0015 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00084 U	0.0063	< 0.002 U	< 0.0013 U	0.0009 J	< 0.00064 U	< 0.0012 U
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38-20220208	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S279	SSHS-IRM5A2-S279-20220208	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 UT	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	S276	SSHS-IRM5A2-S276-20220208	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 0.00087 U	< 0.0014 U	< 0.0036 U	< 0.0032 UT	< 0.0016 U	< 0.0018 U	< 0.0063 U
Northern Athletic Field	S278	SSHS-IRM5A2-S278-20220208	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S275	SSHS-IRM5A2-S275-20220208	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S273	SSHS-IRM5A2-S273-20220209	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274-20220209	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	S281	SSHS-IRM5A2-S281-20220209	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0034 UT	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	S280	SSHS-IRM5A2-S280-20220209	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 UT	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47-20220302	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.0010 U	0.0017 J	< 0.0043 U	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	S296	SSHS-IRM5A2-S296-20220302	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S295	SSHS-IRM5A2-S295-20220302	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294-20220302	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 0.00099 UT	< 0.0016 UT	< 0.0042 UT	< 0.0036 UT	< 0.0018 UT	< 0.0020 UT	< 0.0072 UT
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52-20220318	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 0.00015 U	0.00042 J	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00055 U
Northern Athletic Field	B711	SSHS-IRM5A2-B711-20220318	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 0.00017 U	0.0017	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00061 U
Northern Athletic Field	B712	SSHS-IRM5A2-B712-20220318	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 0.00015 U	0.0015	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 U	< 0.00027 U	< 0.00063 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.0043 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00032 U	< 0.00075 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	0.0077	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 UT	< 0.0021 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 UT	< 0.0023 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 UT	< 0.0021 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.0054 U	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	0.0076 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	0.0094 J	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.000086 U	< 0.000095 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00033 U	< 0.00061 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.00013 U	< 0.00015 U	< 0.00039 U	< 0.00073 U	< 0.00033 U	< 0.00017 U	< 0.00035 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00057 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UT	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	0.0027 J	< 0.0025 U	< 0.0029 U	0.0016 J	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0039 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0028 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0027 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0028 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 UT	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0031 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0031 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0016 U	< 0.0025 UJ	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated							
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated							
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated							
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated							

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.00056 U	< 0.000088 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.00072 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.00086 U	< 0.00014 U	< 0.00025 U	< 0.00027 U	< 0.00027 U	< 0.00017 U	< 0.00016 U	< 0.00022 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 UT	< 0.00033 UT	< 0.00020 UT	< 0.00019 U	< 0.00027 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	0.0041 J	< 0.0028 U	< 0.003 UJ	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00017 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000097 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00023 U	< 0.00015 U	< 0.00027 U	< 0.00017 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00027 U	< 0.00019 U	< 0.00032 U	< 0.00021 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.00019 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0029 U	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U	< 0.0022 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 002 U	< 0.0025 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00031 U	< 0.00023 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.00015 U	< 0.00084 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00098 U	< 0.00032 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00021 U	< 0.0032 U	< 0.00038 U	< 0.00028 U	< 0.0012 U	< 0.00039 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 UT
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 003 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 UT	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 UT	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 UT	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 UT	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 UT	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 UT	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0068 UT	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 UT	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.002 U	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated								
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated								
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated								
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated								
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated								
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated								
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00013 U	0.00051 J	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.00017 U	< 0.00013 U	0.0075	< 0.00014 U	< 0.00011 U	< 0.00022 U	0.00048 J
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00010 U	0.00034 J	< 0.00011 U	< 0.000088 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.00030 U	< 0.00023 U	0.00066 J	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.00018 U	< 0.00013 U	0.0011	< 0.00015 U	< 0.00011 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.00021 U	< 0.00016 U	0.00063 J	< 0.00018 U	< 0.00014 U	< 0.00027 U	< 0.00018 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.00029 U	< 0.00022 U	0.00091 J	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.00023 U	< 0.00018 U	0.00050 J	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00035 U	< 0.00027 U	0.00051 J	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.00026 U	< 0.00020 U	0.0013	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.00026 U	< 0.00020 U	0.0015	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00029 U	< 0.00022 U	0.00071 J	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.00017 U	< 0.00013 U	0.0026	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.00028 U	< 0.00021 U	0.00034 J	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.00025 UT	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 UT	< 0.00021 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0026 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U	< 0.0029 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated							
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated							
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated							
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B707	SSHS-IRM5A2-B707-20220318	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00039 U
Northern Athletic Field	S321	SSHS-IRM5A2-S321-20220318	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 0.00011 U	0.016	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00039 U
Northern Athletic Field	S320	SSHS-IRM5A2-S320-20220318	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 0.000087 U	0.00043 J	< 0.00020 U	< 0.00027 U	< 0.000085 U	< 0.000095 U	< 0.00031 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706-20220318	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 0.00019 U	0.00084 J	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00068 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705-20220318	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 0.00011 U	0.0027	< 0.00026 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00040 U
Northern Athletic Field	B704	SSHS-IRM5A2-B704-20220318	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 0.00013 U	0.0011	< 0.00031 U	< 0.00041 U	< 0.00013 U	< 0.00015 U	< 0.00048 U
Northern Athletic Field	B703	SSHS-IRM5A2-B703-20220318	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 0.00018 U	0.0011	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00066 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702-20220318	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 0.00015 U	0.00033 J	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00053 U
Northern Athletic Field	B700	SSHS-IRM5A2-B700-20220318	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00080 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699-20220318	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 0.00017 U	0.00091 J	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	B698	SSHS-IRM5A2-B698-20220318	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 0.00016 U	0.00094	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	B701	SSHS-IRM5A2-B701-20220318	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 0.00018 U	0.00076 J	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00066 U
Northern Athletic Field	S312	SSHS-IRM5A2-S312-20220318	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 0.00011 U	0.0023	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00039 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59-20220330	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1-20220330	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A-20220405	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0039 U	< 0.0033 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61-20220418	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731-20220418	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732-20220418	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-14-16	SSHS-DW-13_14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-14-16	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400-20220824	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401-20220824	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403-20220825	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404-20220825	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601-20220825	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604-20220825	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A-20230530	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 UT	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10-20230530	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 UT	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11-20230530	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12-20230530	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13-20230530	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1-20230530	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 UT	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17-20230601	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18-20230601	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22-20230601	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23-20230601	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2-20230601	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3-20230601	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25-20230601	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29-20230601	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0038 U	< 0.0033 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30-20230601	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A-20230602	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35-20230602	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36-20230602	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37-20230602	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4-20230602	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.0015 UJ	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3909	050821 10:00_SSHS-B3909-SUB-16-18	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated							
Northern Athletic Field	SSHS-B3905	051121 10:30_SSHS-B3905-SUB-16-18	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated							
Northern Athletic Field	SSHS-B3908	051221 10:30_SSHS-B3908-SUB-16-18	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	0.0032 J	0.0030 J	< 0.0080 U
Northern Athletic Field	SSHS-B3890	051321 10:15_SSHS-B3890-SUB-16-18	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated							
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3887	051821 09:00_SSHS-B3887-SUB-16-18	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated							
Northern Athletic Field	SSHS-B3898	051921 10:30_SSHS-B3898-SUB-16-18	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated							
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18-20210519	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated							
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B580	SSHS-B580-SUB-2-4	SSHS-B580-SUB-2-4	2/10/2017	856.11	856.72	0.61	-	2 - 4 ft	2.61-4.61 ft	180-63389-1	Not Excavated							
Northern Athletic Field	SSHS-B585	SSHS-B585-SUB-2-4	SSHS-B585-SUB-2-4	2/10/2017	856.14	856.15	0.01	-	2 - 4 ft	2.01-4.01 ft	180-63389-1	Not Excavated							
Northern Athletic Field	SSHS-B754	052417 09:15_SSHS-B754-SUB-2-4	SSHS-B754-SUB-2-4	5/23/2017	856.12	856.86	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B755	052417 09:15_SSHS-B755-SUB-2-4	SSHS-B755-SUB-2-4	5/23/2017	856.01	856.68	0.67	-	2 - 4 ft	2.67-4.67 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B763	052417 09:15_SSHS-B763-SUB-2-4	SSHS-B763-SUB-2-4	5/23/2017	856.04	856.62	0.58	-	2 - 4 ft	2.58-4.58 ft	180-66622-1	Not Excavated							

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B781	052417 09:15_SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated							
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3289	121819 10:30_SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3290	121819 10:30_SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated							
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3258	122119 10:30_SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3270	122119 10:30_SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3271	122119 10:30_SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3273	122119 10:30_SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3241	122119 10:30_SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3251	122119 10:30_SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B781	052417 09:15 SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated						
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated						
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated						
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated						
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated						
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated						
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated						
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated						
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3289	121819 10:30 SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3290	121819 10:30 SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated						
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3258	122119 10:30 SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3270	122119 10:30 SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3271	122119 10:30 SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3241	122119 10:30 SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3251	122119 10:30 SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3254	122119 10:30 SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated						

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B781	052417 09:15_SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated							
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3289	121819 10:30_SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3290	121819 10:30_SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated							
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3258	122119 10:30_SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3270	122119 10:30_SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3271	122119 10:30_SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3273	122119 10:30_SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3241	122119 10:30_SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3251	122119 10:30_SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B781	052417 09:15_SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated								
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3289	121819 10:30_SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3290	121819 10:30_SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated								
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3258	122119 10:30_SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3270	122119 10:30_SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3271	122119 10:30_SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3273	122119 10:30_SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3241	122119 10:30_SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3251	122119 10:30_SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B781	052417 09:15_SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated								
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3289	121819 10:30_SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3290	121819 10:30_SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated								
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated								
Northern Athletic Field	SSHS-B3258	122119 10:30_SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3270	122119 10:30_SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3271	122119 10:30_SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3273	122119 10:30_SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3241	122119 10:30_SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3251	122119 10:30_SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B781	052417 09:15 SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated						
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated						
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated						
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated						
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated						
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated						
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated						
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3330	121819 10:30 SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3331	121819 10:30 SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3284	121819 10:30 SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated						
Northern Athletic Field	SSHS-B3288	121819 10:30 SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3289	121819 10:30 SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3290	121819 10:30 SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3308	121819 10:30 SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated						
Northern Athletic Field	SSHS-B3315	121819 10:30 SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3258	122119 10:30 SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3270	122119 10:30 SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3271	122119 10:30 SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3272	122119 10:30 SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3273	122119 10:30 SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3275	122119 10:30 SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3281	122119 10:30 SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3283	122119 10:30 SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3241	122119 10:30 SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3250	122119 10:30 SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3251	122119 10:30 SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3252	122119 10:30 SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3253	122119 10:30 SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3254	122119 10:30 SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3255	122119 10:30 SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B781	052417 09:15_SSHS-B781-SUB-2-4	SSHS-B781-SUB-2-4	5/23/2017	856.09	857.50	1.41	-	2 - 4 ft	3.41 - 5.41 ft	180-66622-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-2-4	SSHS-B2030-SUB-2-4	7/27/2018	856.20	856.42	0.22	-	2 - 4 ft	2.22-4.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-2-4	SSHS-B3008-SUB-2-4	8/26/2019	852.37	854.67	2.30	-	2 - 4 ft	4.3-6.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-2-4	SSHS-B3078-SUB-2-4	8/26/2019	856.70	857.12	0.42	-	2 - 4 ft	2.42-4.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-2-4	SSHS-B3099-SUB-2-4	8/26/2019	856.40	856.53	0.13	-	2 - 4 ft	2.13-4.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-2-4	SSHS-B3006-SUB-2-4	8/27/2019	852.36	852.39	0.03	-	2 - 4 ft	2.03-4.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-2-4	SSHS-B3007-SUB-2-4	8/27/2019	852.58	854.74	2.16	-	2 - 4 ft	4.16-6.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-2-4	SSHS-B3018-SUB-2-4	8/27/2019	853.82	854.59	0.77	-	2 - 4 ft	2.77-4.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-2-4	SSHS-B3031-SUB-2-4	8/27/2019	855.08	855.61	0.53	-	2 - 4 ft	2.53-4.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-2-4	SSHS-B3032-SUB-2-4	8/27/2019	855.25	856.15	0.90	-	2 - 4 ft	2.9-4.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-2-4	SSHS-B3030-SUB-2-4	8/28/2019	855.22	855.02	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-2-4	SSHS-B3043-SUB-2-4	8/28/2019	855.78	856.62	0.84	-	2 - 4 ft	2.84-4.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-2-4	SSHS-B3057-SUB-2-4	8/28/2019	856.09	857.58	1.49	-	2 - 4 ft	3.49-5.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-2-4	SSHS-B3058-SUB-2-4	8/28/2019	856.47	856.55	0.08	-	2 - 4 ft	2.08-4.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-2-4	SSHS-B3071-SUB-2-4	8/28/2019	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-2-4	SSHS-B3004-SUB-2-4	8/29/2019	852.25	853.25	1.00	-	2 - 4 ft	3-5 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-2-4	SSHS-B3005-SUB-2-4	8/29/2019	852.31	852.62	0.31	-	2 - 4 ft	2.31-4.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-2-4	SSHS-B3040-SUB-2-4	8/29/2019	855.10	858.65	3.55	-	2 - 4 ft	5.55-7.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-2-4	SSHS-B3054-SUB-2-4	8/29/2019	856.01	856.77	0.76	-	2 - 4 ft	2.76-4.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-2-4	SSHS-B3055-SUB-2-4	8/29/2019	856.20	858.70	2.50	-	2 - 4 ft	4.5-6.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-2-4	SSHS-B3056-SUB-2-4	8/29/2019	855.88	858.82	2.94	-	2 - 4 ft	4.94-6.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-2-4	SSHS-B3079-SUB-2-4	8/29/2019	856.36	857.37	1.01	-	2 - 4 ft	3.01-5.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-2-4	SSHS-B3083-SUB-2-4	8/29/2019	857.13	857.39	0.26	-	2 - 4 ft	2.26-4.26 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-2-4	SSHS-B3084-SUB-2-4	8/29/2019	856.55	857.05	0.50	-	2 - 4 ft	2.5-4.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-2-4	SSHS-B3182-SUB-2-4	8/29/2019	857.45	857.88	0.43	-	2 - 4 ft	2.43-4.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-2-4	SSHS-B3223-SUB-2-4	8/29/2019	858.27	858.28	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-2-4	SSHS-B3003-SUB-2-4	8/30/2019	851.95	852.83	0.88	-	2 - 4 ft	2.88-4.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-2-4	SSHS-B3011-SUB-2-4	8/30/2019	853.85	854.62	0.77	-	2 - 4 ft	2.77-4.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-2-4	SSHS-B3039-SUB-2-4	8/30/2019	855.85	856.37	0.52	-	2 - 4 ft	2.52-4.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-2-4	SSHS-B3068-SUB-2-4	8/30/2019	856.38	856.82	0.44	-	2 - 4 ft	2.44-4.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-2-4	SSHS-B3082-SUB-2-4	8/30/2019	856.73	857.22	0.49	-	2 - 4 ft	2.49-4.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-2-4	SSHS-B3222-SUB-2-4	8/30/2019	858.28	858.08	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-2-4	SSHS-B3224-SUB-2-4	8/30/2019	858.38	858.48	0.10	-	2 - 4 ft	2.1-4.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-2-4	SSHS-B3001-SUB-2-4	9/3/2019	853.35	853.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-2-4	SSHS-B3009-SUB-2-4	9/3/2019	853.88	854.29	0.41	-	2 - 4 ft	2.41-4.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-2-4	SSHS-B3023-SUB-2-4	9/3/2019	854.48	854.90	0.42	-	2 - 4 ft	2.42-4.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-2-4	SSHS-B3036-SUB-2-4	9/3/2019	855.09	855.21	0.12	-	2 - 4 ft	2.12-4.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-2-4	SSHS-B3038-SUB-2-4	9/3/2019	855.76	855.72	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-2-4	SSHS-B3053-SUB-2-4	9/3/2019	856.41	856.22	-0.19	-	2 - 4 ft	1.81-3.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-2-4	SSHS-B3067-SUB-2-4	9/3/2019	856.40	856.48	0.08	-	2 - 4 ft	2.08-4.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-2-4	SSHS-B3051-SUB-2-4	9/4/2019	855.15	855.32	0.17	-	2 - 4 ft	2.17-4.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-2-4	SSHS-B3066-SUB-2-4	9/4/2019	855.86	856.02	0.16	-	2 - 4 ft	2.16-4.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-2-4	SSHS-B3080-SUB-2-4	9/4/2019	856.58	856.76	0.18	-	2 - 4 ft	2.18-4.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-2-4	SSHS-B3081-SUB-2-4	9/4/2019	856.96	857.03	0.07	-	2 - 4 ft	2.07-4.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-2-4	SSHS-B3085-SUB-2-4	9/4/2019	857.12	857.26	0.14	-	2 - 4 ft	2.14-4.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-2-4	SSHS-B3086-SUB-2-4	9/4/2019	857.77	857.49	-0.28	-	2 - 4 ft	1.72-3.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-2-4	SSHS-B3220-SUB-2-4	9/4/2019	857.44	857.92	0.48	-	2 - 4 ft	2.48-4.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-2-4	SSHS-B3221-SUB-2-4	9/4/2019	857.92	857.93	0.01	-	2 - 4 ft	2.01-4.01 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3330	121819 10:30_SSHS-B3330-SUB-2-4	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3331	121819 10:30_SSHS-B3331-SUB-2-4	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3284	121819 10:30_SSHS-B3284-SUB-2-4	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated							
Northern Athletic Field	SSHS-B3288	121819 10:30_SSHS-B3288-SUB-2-4	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3289	121819 10:30_SSHS-B3289-SUB-2-4	SSHS-B3289-SUB-2-4	12/17/2019	857.03	856.77	-0.26	-	2 - 4 ft	1.74-3.74 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3290	121819 10:30_SSHS-B3290-SUB-2-4	SSHS-B3290-SUB-2-4	12/17/2019	857.23	856.80	-0.43	-	2 - 4 ft	1.57-3.57 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3308	121819 10:30_SSHS-B3308-SUB-2-4	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated							
Northern Athletic Field	SSHS-B3315	121819 10:30_SSHS-B3315-SUB-2-4	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated							
Northern Athletic Field	SSHS-B3258	122119 10:30_SSHS-B3258-SUB-2-4	SSHS-B3258-SUB-2-4	12/18/2019	856.41	856.86	0.45	-	2 - 4 ft	2.45-4.45 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3270	122119 10:30_SSHS-B3270-SUB-2-4	SSHS-B3270-SUB-2-4	12/18/2019	855.88	858.85	2.97	-	2 - 4 ft	4.97-6.97 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3271	122119 10:30_SSHS-B3271-SUB-2-4	SSHS-B3271-SUB-2-4	12/18/2019	855.39	858.94	3.55	-	2 - 4 ft	5.55-7.55 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3272	122119 10:30_SSHS-B3272-SUB-2-4	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3273	122119 10:30_SSHS-B3273-SUB-2-4	SSHS-B3273-SUB-2-4	12/18/2019	856.15	858.40	2.25	-	2 - 4 ft	4.25-6.25 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3275	122119 10:30_SSHS-B3275-SUB-2-4	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-2-4	SSHS-B3279-SUB-2-4	12/18/2019	856.57	856.71	0.14	-	2 - 4 ft	2.14-4.14 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3281	122119 10:30_SSHS-B3281-SUB-2-4	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3283	122119 10:30_SSHS-B3283-SUB-2-4	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3241	122119 10:30_SSHS-B3241-SUB-2-4	SSHS-B3241-SUB-2-4	12/19/2019	856.35	857.24	0.89	-	2 - 4 ft	2.89-4.89 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-2-4	SSHS-B3242-SUB-2-4	12/19/2019	856.23	857.22	0.99	-	2 - 4 ft	2.99-4.99 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-2-4	SSHS-B3243-SUB-2-4	12/19/2019	856.13	857.96	1.83	-	2 - 4 ft	3.83-5.83 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3250	122119 10:30_SSHS-B3250-SUB-2-4	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3251	122119 10:30_SSHS-B3251-SUB-2-4	SSHS-B3251-SUB-2-4	12/19/2019	858.34	858.34	0.00	-	2 - 4 ft	2-4 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3252	122119 10:30_SSHS-B3252-SUB-2-4	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3253	122119 10:30_SSHS-B3253-SUB-2-4	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3254	122119 10:30_SSHS-B3254-SUB-2-4	SSHS-B3254-SUB-2-4	12/19/2019	856.34	856.66	0.32	-	2 - 4 ft	2.32-4.32 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3255	122119 10:30_SSHS-B3255-SUB-2-4	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated							

DRAFT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3229	122119 10:30 SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3230	122119 10:30 SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3231	122119 10:30 SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3237	122119 10:30 SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3238	122119 10:30 SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3240	122119 10:30 SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated							
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated							
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3623	012721 08:30 SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3624	012721 08:30 SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3500A	012721 08:30 SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3501A	012721 08:30 SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3603	012721 08:30 SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3604	012721 08:30 SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3605	012721 08:30 SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3606	012721 08:30 SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3608	012721 08:30 SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3609	012721 08:30 SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3610	012721 08:30 SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3612	012721 08:30 SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3617	012721 08:30 SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3618	012721 08:30 SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3621	012721 08:30 SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3622	012721 08:30 SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated							
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated							
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	1801239851	Not Excavated	< 0.0043 UJ	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.004 U	< 0.00023 U	< 0.00034 U	< 0.00064 U	< 0.0024 U	< 0.00043 U	< 0.0024 U	< 0.00046 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.023 U	< 0.00076 U	< 0.0014 U	< 0.0016 U	< 0.0026 U	< 0.0045 U	< 0.0013 U	< 0.0035 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated							
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated							
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated							
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated							
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3229	122119 10:30 SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3230	122119 10:30 SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3231	122119 10:30 SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3237	122119 10:30 SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3238	122119 10:30 SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3240	122119 10:30 SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated						
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3623	012721 08:30 SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3624	012721 08:30 SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3500A	012721 08:30 SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3501A	012721 08:30 SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3603	012721 08:30 SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3604	012721 08:30 SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3605	012721 08:30 SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3606	012721 08:30 SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3608	012721 08:30 SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3609	012721 08:30 SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3610	012721 08:30 SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3612	012721 08:30 SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3617	012721 08:30 SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3618	012721 08:30 SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3621	012721 08:30 SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3622	012721 08:30 SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated						
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.00063 U	< 0.00061 U	< 0.0011 U	< 0.00029 U	< 0.00029 U	< 0.00066 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.003 U	< 0.003 U	< 0.00086 U	< 0.0025 U	< 0.0015 U	< 0.0039 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated						
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated						
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated						
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated						
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated						

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3229	122119 10:30 SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3230	122119 10:30 SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3231	122119 10:30 SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3237	122119 10:30 SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3238	122119 10:30 SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3240	122119 10:30 SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated								
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3623	012721 08:30 SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3624	012721 08:30 SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3500A	012721 08:30 SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3501A	012721 08:30 SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3603	012721 08:30 SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3604	012721 08:30 SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3605	012721 08:30 SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3606	012721 08:30 SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3608	012721 08:30 SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3609	012721 08:30 SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3610	012721 08:30 SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3612	012721 08:30 SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3617	012721 08:30 SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3618	012721 08:30 SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3621	012721 08:30 SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3622	012721 08:30 SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated								
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	0.013	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	0.0081	< 0.0016 U	< 0.0028 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	0.0086	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	0.0069	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	0.011	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.0022 U	< 0.00061 U	< 0.00039 U	< 0.00037 U	< 0.00024 U	< 0.00066 U	< 0.00058 U	< 0.00024 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.013 U	< 0.00084 U	< 0.001 UJ	< 0.0012 U	< 0.00089 U	< 0.00096 UJ	< 0.00076 U	< 0.00084 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated								
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated								
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated								
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated								
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3257	122119 10:30_SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3259	122119 10:30_SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3260	122119 10:30_SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3225	122119 10:30_SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3226	122119 10:30_SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3228	122119 10:30_SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3229	122119 10:30_SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3230	122119 10:30_SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3231	122119 10:30_SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3237	122119 10:30_SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3238	122119 10:30_SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3240	122119 10:30_SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3227	012520 10:00_SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated								
Northern Athletic Field	SSHS-B3517	011521 08:45_SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3623	012721 08:30_SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3624	012721 08:30_SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SSHS-B3037A	012721 08:30_SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3500A	012721 08:30_SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3501A	012721 08:30_SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3502A	012721 08:30_SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3516	012721 08:30_SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3603	012721 08:30_SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3604	012721 08:30_SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3605	012721 08:30_SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3606	012721 08:30_SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30_SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3608	012721 08:30_SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3609	012721 08:30_SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3610	012721 08:30_SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30_SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3612	012721 08:30_SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3613	012721 08:30_SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3615	012721 08:30_SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3616	012721 08:30_SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3617	012721 08:30_SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3618	012721 08:30_SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3620	012721 08:30_SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3621	012721 08:30_SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3622	012721 08:30_SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated								
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3491A	012721 08:30_SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B4019	070221 09:00_SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.00058 U	< 0.0025 U	< 0.00061 U	< 0.00049 U	< 0.0024 U	< 0.00068 U	< 0.0021 U	< 0.00033 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.002 U	< 0.0012 U	< 0.0016 U	< 0.0015 U	< 0.00093 U	< 0.0031 U	< 0.004 U	< 0.0011 UJ
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated								
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated								
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated								
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated								
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated								
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3229	122119 10:30 SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3230	122119 10:30 SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3231	122119 10:30 SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3237	122119 10:30 SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3238	122119 10:30 SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3240	122119 10:30 SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated								
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3623	012721 08:30 SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3624	012721 08:30 SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3500A	012721 08:30 SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3501A	012721 08:30 SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3603	012721 08:30 SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3604	012721 08:30 SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3605	012721 08:30 SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3606	012721 08:30 SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3608	012721 08:30 SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3609	012721 08:30 SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3610	012721 08:30 SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3612	012721 08:30 SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3617	012721 08:30 SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3618	012721 08:30 SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3621	012721 08:30 SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3622	012721 08:30 SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated								
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.0025 U	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated								
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0022 U	< 0.0017 UJ	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.0011 U	< 0.0024 U	< 0.00072 U	< 0.0029 U	< 0.00072 U	< 0.0017 U	< 0.0016 U	< 0.00047 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.0014 U	< 0.0045 U	< 0.0021 UJ	< 0.0037 U	< 0.0013 U	< 0.0039 U	< 0.004 U	< 0.0022 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated								
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated								
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated								
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated								
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3229	122119 10:30 SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3230	122119 10:30 SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3231	122119 10:30 SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3237	122119 10:30 SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3238	122119 10:30 SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3240	122119 10:30 SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated						
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3623	012721 08:30 SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3624	012721 08:30 SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3500A	012721 08:30 SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3501A	012721 08:30 SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3603	012721 08:30 SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3604	012721 08:30 SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3605	012721 08:30 SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3606	012721 08:30 SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3608	012721 08:30 SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3609	012721 08:30 SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3610	012721 08:30 SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3612	012721 08:30 SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3617	012721 08:30 SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3618	012721 08:30 SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3621	012721 08:30 SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3622	012721 08:30 SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated						
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.00024 U	< 0.00077 U	< 0.00064 U	< 0.00036 U	< 0.0005 U	< 0.00029 U	< 0.00034 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.0013 U	< 0.0016 U	< 0.0008 U	< 0.00084 U	< 0.0032 U	< 0.0027 U	< 0.0019 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated						
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated						
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated						
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated						
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3257	122119 10:30 SSHS-B3257-SUB-2-4	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3259	122119 10:30 SSHS-B3259-SUB-2-4	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3260	122119 10:30 SSHS-B3260-SUB-2-4	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated							
Northern Athletic Field	SSHS-B3225	122119 10:30 SSHS-B3225-SUB-2-4	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3226	122119 10:30 SSHS-B3226-SUB-2-4	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3228	122119 10:30 SSHS-B3228-SUB-2-4	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3229	122119 10:30 SSHS-B3229-SUB-2-4	SSHS-B3229-SUB-2-4	12/20/2019	855.55	855.45	-0.10	-	2 - 4 ft	1.9-3.9 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3230	122119 10:30 SSHS-B3230-SUB-2-4	SSHS-B3230-SUB-2-4	12/20/2019	855.45	855.49	0.04	-	2 - 4 ft	2.04-4.04 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3231	122119 10:30 SSHS-B3231-SUB-2-4	SSHS-B3231-SUB-2-4	12/20/2019	855.72	855.63	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-2-4	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3237	122119 10:30 SSHS-B3237-SUB-2-4	SSHS-B3237-SUB-2-4	12/20/2019	856.01	856.02	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3238	122119 10:30 SSHS-B3238-SUB-2-4	SSHS-B3238-SUB-2-4	12/20/2019	855.23	855.98	0.75	-	2 - 4 ft	2.75-4.75 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3240	122119 10:30 SSHS-B3240-SUB-2-4	SSHS-B3240-SUB-2-4	12/20/2019	856.04	856.82	0.78	-	2 - 4 ft	2.78-4.78 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-2-4	SSHS-B3118-SUB-2-4	1/15/2020	856.74	856.72	-0.02	-	2 - 4 ft	1.98-3.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3227	012520 10:00 SSHS-B3227-SUB-2-4	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated							
Northern Athletic Field	SSHS-B3517	011521 08:45 SSHS-B3517-SUB-2-4	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated							
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-2-4	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-2-4	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-2-4	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3623	012721 08:30 SSHS-B3623-SUB-2-4	SSHS-B3623-SUB-2-4	1/23/2021	855.47	858.93	3.46	-	2 - 4 ft	5.46-7.46 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3624	012721 08:30 SSHS-B3624-SUB-2-4	SSHS-B3624-SUB-2-4	1/23/2021	855.26	858.01	2.75	-	2 - 4 ft	4.75-6.75 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	DUP-2-20210125	DUP-2	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-2-4	SSHS-B3037A-SUB-2-4	1/25/2021	855.59	855.55	-0.04	-	2 - 4 ft	1.96-3.96 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-2-4	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3500A	012721 08:30 SSHS-B3500-SUB-2-4	SSHS-B3500-SUB-2-4	1/25/2021	855.38	855.47	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3501A	012721 08:30 SSHS-B3501-SUB-2-4	SSHS-B3501-SUB-2-4	1/25/2021	855.77	855.89	0.12	-	2 - 4 ft	2.12-4.12 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3502A	012721 08:30 SSHS-B3502-SUB-2-4	SSHS-B3502-SUB-2-4	1/25/2021	855.86	857.66	1.80	-	2 - 4 ft	3.8-5.8 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-2-4	SSHS-B3516-SUB-2-4	1/25/2021	856.33	856.96	0.63	-	2 - 4 ft	2.63-4.63 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3603	012721 08:30 SSHS-B3603-SUB-2-4	SSHS-B3603-SUB-2-4	1/25/2021	855.89	855.73	-0.16	-	2 - 4 ft	1.84-3.84 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3604	012721 08:30 SSHS-B3604-SUB-2-4	SSHS-B3604-SUB-2-4	1/25/2021	855.40	855.57	0.17	-	2 - 4 ft	2.17-4.17 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3605	012721 08:30 SSHS-B3605-SUB-2-4	SSHS-B3605-SUB-2-4	1/25/2021	855.99	856.05	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3606	012721 08:30 SSHS-B3606-SUB-2-4	SSHS-B3606-SUB-2-4	1/25/2021	855.37	855.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3607	012721 08:30 SSHS-B3607-SUB-2-4	SSHS-B3607-SUB-2-4	1/25/2021	855.19	857.92	2.73	-	2 - 4 ft	4.73-6.73 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3608	012721 08:30 SSHS-B3608-SUB-2-4	SSHS-B3608-SUB-2-4	1/25/2021	856.10	855.95	-0.15	-	2 - 4 ft	1.85-3.85 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3609	012721 08:30 SSHS-B3609-SUB-2-4	SSHS-B3609-SUB-2-4	1/25/2021	855.67	858.61	2.94	-	2 - 4 ft	4.94-6.94 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3610	012721 08:30 SSHS-B3610-SUB-2-4	SSHS-B3610-SUB-2-4	1/25/2021	856.08	856.39	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3611	012721 08:30 SSHS-B3611-SUB-2-4	SSHS-B3611-SUB-2-4	1/25/2021	856.16	858.07	1.91	-	2 - 4 ft	3.91-5.91 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3612	012721 08:30 SSHS-B3612-SUB-2-4	SSHS-B3612-SUB-2-4	1/25/2021	856.56	857.03	0.47	-	2 - 4 ft	2.47-4.47 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3613	012721 08:30 SSHS-B3613-SUB-2-4	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3615	012721 08:30 SSHS-B3615-SUB-2-4	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3616	012721 08:30 SSHS-B3616-SUB-2-4	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3617	012721 08:30 SSHS-B3617-SUB-2-4	SSHS-B3617-SUB-2-4	1/25/2021	856.07	856.84	0.77	-	2 - 4 ft	2.77-4.77 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3618	012721 08:30 SSHS-B3618-SUB-2-4	SSHS-B3618-SUB-2-4	1/25/2021	856.15	857.13	0.98	-	2 - 4 ft	2.98-4.98 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3620	012721 08:30 SSHS-B3620-SUB-2-4	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3621	012721 08:30 SSHS-B3621-SUB-2-4	SSHS-B3621-SUB-2-4	1/25/2021	856.33	856.42	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3622	012721 08:30 SSHS-B3622-SUB-2-4	SSHS-B3622-SUB-2-4	1/25/2021	856.17	858.35	2.18	-	2 - 4 ft	4.18-6.18 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4-20210125	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-2-4	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3481A	DUP-9-20210126	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated							
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4-20210126	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-2-4	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-2-4	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-2-4	SSHS-B3491A-SUB-2-4	1/26/2021	858.35	858.44	0.09	-	2 - 4 ft	2.09-4.09 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U		< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.0012 U	< 0.002 U	< 0.0052 U	< 0.0045 U		< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4-20210126	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-2-4	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-2-4	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4-20210126	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	IRM5-S057B	SSHS-IRM5-S057B-20210423	SSHS-IRM5-S057B	4/23/2021	-	855.92	-	852.60	2 - 4 ft	3.31 ft	1801205492	Not Excavated							
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-2-4	SSHS-B3918-SUB-2-4	5/12/2021	854.82	854.84	0.02	-	2 - 4 ft	2.02-4.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-2-4	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4018	DUP-1-20210701	DUP-1	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4-20210701	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B4019	070221 09:00 SSHS-B4019-SUB-2-4	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-2-4	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.00062 U	< 0.001 U	< 0.00045 U	< 0.00058 U	< 0.0008 U	< 0.00062 U	< 0.0008 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-2-4	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated	< 0.0012 U	< 0.00069 U	< 0.0029 U	< 0.0019 U	< 0.00085 UJ	< 0.00094 U	< 0.0017 U
Northern Athletic Field	B773	SSHS-IRM5A2-B773-20211024	SSHS-IRM5A2-B773	10/24/2021	-	857.05	-	853.70	2 - 4 ft	3.35 ft	1801289731	Not Excavated							
Northern Athletic Field	B780	SSHS-IRM5A2-B780-20211024	SSHS-IRM5A2-B780	10/24/2021	-	857.11	-	853.90	2 - 4 ft	3.21 ft	1801289731	Not Excavated							
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289731	Not Excavated							
Northern Athletic Field	B757	SSHS-IRM5A2-B757-20211024	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated							
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289731	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated							
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated							
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated							
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated							
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated							
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated							
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated							
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated							
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated							
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated							
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated							
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated							
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated							
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated							
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated							
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated							
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated							
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated							
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated							
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated							
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated							
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated							
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated							
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated							
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated							
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated							
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated							
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated							
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated							
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.018 UT	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.0010 U	< 0.0029 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.019 UT	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.0010 U	< 0.0029 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated							
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated							
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated							
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated							
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated							
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated							
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated							
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated							
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated							
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated							
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated							
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated							
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated							
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated							
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated							

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated						
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated						
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated						
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated						
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated						
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated						
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated						
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated						
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated						
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated						
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated						
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated						
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated						
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated						
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated						
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated						
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated						
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated						
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated						
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated						
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated						
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated						
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated						
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated						
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated						
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated						
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated						
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated						
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated						
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated						
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated						
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated						
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated						
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated						
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated						
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated						
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated						
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated						
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated						
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated						
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated						
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated						
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated						
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated						
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated						
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated						
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated						
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated						
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated						
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated						
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated						
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated						
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated						
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.00069 U	< 0.0020 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.00070 U	< 0.0020 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated						
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated						
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated						
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated						
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated						
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated						
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated						
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated						
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated						
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated						
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated						
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated						
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated						
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated						
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated						
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated						
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated						
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated						
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated						

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated							
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated							
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated							
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated							
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated							
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated							
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated							
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated							
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated							
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated							
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated							
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated							
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated							
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated							
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated							
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated							
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated							
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated							
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated							
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated							
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated							
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated							
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	110621 09:30 SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated							
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated							
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated							
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated							
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated							
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated							
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated							
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.011 UT	< 0.00068 U	< 0.00083 U	< 0.00098 U	< 0.00072 U	< 0.00078 U	< 0.00061 U	< 0.00068 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.011 UT	< 0.00068 U	< 0.00084 U	< 0.00099 U	< 0.00072 U	< 0.00078 U	< 0.00061 U	< 0.00068 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated							
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated							
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated							
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated							
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated							
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated							
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated							
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated							
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated							
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated							
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated							
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated							
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated							
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated							
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated								
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated								
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated								
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated								
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated								
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated								
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated								
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated								
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated								
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated								
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated								
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated								
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated								
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated								
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated								
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated								
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated								
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated								
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated								
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated								
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated								
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated								
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated								
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated								
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated								
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated								
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated								
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated								
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated								
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated								
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated								
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated								
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated								
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated								
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated								
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated								
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated								
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated								
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated								
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated								
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated								
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated								
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated								
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated								
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated								
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated								
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated								
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated								
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated								
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated								
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated								
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00092 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.0016 U	< 0.0010 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0026 U	< 0.0033 U	< 0.00093 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated								
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated								
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated								
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated								
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated								
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated								
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated								
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated								
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated								
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated								
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated								
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated								
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated								
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated								
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated								
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated								
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated								
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated								
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated								
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated								
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated								
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated								
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated								
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated								
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated								
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated								
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated								
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated								
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated								
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated								
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated								
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated								
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated								
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated								
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated								
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated								
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated								
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated								
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated								
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated								
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated								
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated								
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated								
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated								
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated								
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated								
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated								
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated								
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated								
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated								
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated								
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated								
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated								
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated								
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated								
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated								
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated								
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated								
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated								
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated								
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated								
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated								
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated								
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated								
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated								
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated								
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated								
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated								
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated								
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0017 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0032 U	< 0.0033 U	< 0.0018 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated								
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated								
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated								
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated								
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated								
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated								
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated								
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated								
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated								
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated								
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated								
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated								
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated								
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated								
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated								
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated								
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated								
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated								
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated							
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated							
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated							
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated							
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated							
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated							
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	856.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated							
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated							
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated							
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated							
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated							
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated							
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated							
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated							
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated							
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated							
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated							
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated							
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated							
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated							
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated							
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated							
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	110621 09:30 SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated							
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated							
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated							
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated							
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated							
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated							
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated							
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.0010 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.0010 U	< 0.0013 U	< 0.00065 U	< 0.00069 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated							
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated							
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated							
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated							
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated							
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated							
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated							
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated							
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated							
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated							
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated							
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated							
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated							
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated							
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated							

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B747	SSHS-IRM5A2-B747-20211024	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289731	Not Excavated							
Northern Athletic Field	B758	SSHS-IRM5A2-B758-20211024	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291081	Not Excavated							
Northern Athletic Field	B797	SSHS-IRM5A2-B797-20211027	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-DUP1-20211028	SSHS-IRM5A2-DUP1	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292042	Not Excavated							
Northern Athletic Field	S437	SSHS-IRM5A2-S437-20211028	SSHS-IRM5A2-S437	10/28/2021	-	855.65	-	852.58	2 - 4 ft	3.07 ft	1801292041	Not Excavated							
Northern Athletic Field	S436	SSHS-IRM5A2-S436-20211028	SSHS-IRM5A2-S436	10/28/2021	-	855.68	-	852.60	2 - 4 ft	3.08 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S435	SSHS-IRM5A2-S435-20211028	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S434	SSHS-IRM5A2-S434-20211028	SSHS-IRM5A2-S434	10/28/2021	-	855.89	-	852.22	2 - 4 ft	3.67 ft	1801292041	Not Excavated							
Northern Athletic Field	S433	SSHS-IRM5A2-S433-20211028	SSHS-IRM5A2-S433	10/28/2021	-	856.26	-	853.00	2 - 4 ft	3.26 ft	1801292041	Not Excavated							
Northern Athletic Field	S441	SSHS-IRM5A2-S441-20211028	SSHS-IRM5A2-S441	10/28/2021	-	856.40	-	852.97	2 - 4 ft	3.43 ft	1801292041	Not Excavated							
Northern Athletic Field	S440	SSHS-IRM5A2-S440-20211028	SSHS-IRM5A2-S440	10/28/2021	-	856.34	-	853.18	2 - 4 ft	3.16 ft	1801292041	Not Excavated							
Northern Athletic Field	S439	SSHS-IRM5A2-S439-20211028	SSHS-IRM5A2-S439	10/28/2021	-	856.10	-	852.89	2 - 4 ft	3.21 ft	1801292041	Not Excavated							
Northern Athletic Field	S438	SSHS-IRM5A2-S438-20211028	SSHS-IRM5A2-S438	10/28/2021	-	855.79	-	852.49	2 - 4 ft	3.3 ft	1801292041	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-DUP5-20211029	SSHS-IRM5A2-A1-DUP5	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B796	SSHS-IRM5A2-A1-B796-20211029	SSHS-IRM5A2-A1-B796	10/29/2021	-	855.74	-	853.26	2 - 4 ft	2.48 ft	1801292771	Not Excavated							
Northern Athletic Field	B793	SSHS-IRM5A2-A1-B793-20211029	SSHS-IRM5A2-A1-B793	10/29/2021	-	856.14	-	853.76	2 - 4 ft	2.37 ft	1801292771	Not Excavated							
Northern Athletic Field	B771	SSHS-IRM5A2-A1-B771-20211029	SSHS-IRM5A2-A1-B771	10/29/2021	-	857.37	-	854.33	2 - 4 ft	3.04 ft	1801292771	Not Excavated							
Northern Athletic Field	B772	SSHS-IRM5A2-A1-B772-20211029	SSHS-IRM5A2-A1-B772	10/29/2021	-	857.26	-	853.94	2 - 4 ft	3.32 ft	1801292771	Not Excavated							
Northern Athletic Field	B767	SSHS-IRM5A2-A1-B767-20211029	SSHS-IRM5A2-A1-B767	10/29/2021	-	857.34	-	853.97	2 - 4 ft	3.38 ft	1801292771	Not Excavated							
Northern Athletic Field	B759	SSHS-IRM5A2-A1-B759-20211029	SSHS-IRM5A2-A1-B759	10/29/2021	-	857.51	-	854.97	2 - 4 ft	2.53 ft	1801292771	Not Excavated							
Northern Athletic Field	B748	SSHS-IRM5A2-A1-B748-20211029	SSHS-IRM5A2-A1-B748	10/29/2021	-	857.77	-	854.81	2 - 4 ft	2.96 ft	1801292771	Not Excavated							
Northern Athletic Field	B749	SSHS-IRM5A2-A1-B749-20211029	SSHS-IRM5A2-A1-B749	10/29/2021	-	857.52	-	854.38	2 - 4 ft	3.15 ft	1801292771	Not Excavated							
Northern Athletic Field	B760	SSHS-IRM5A2-A1-B760-20211029	SSHS-IRM5A2-A1-B760	10/29/2021	-	857.23	-	853.89	2 - 4 ft	3.34 ft	1801292771	Not Excavated							
Northern Athletic Field	B761	SSHS-IRM5A2-A1-B761-20211029	SSHS-IRM5A2-A1-B761	10/29/2021	-	856.96	-	853.88	2 - 4 ft	3.09 ft	1801292771	Not Excavated							
Northern Athletic Field	B750	SSHS-IRM5A2-A1-B750-20211029	SSHS-IRM5A2-A1-B750	10/29/2021	-	857.39	-	854.56	2 - 4 ft	2.83 ft	1801292771	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-DUP7-20211103	SSHS-IRM5A2-DUP7	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294633	Not Excavated							
Northern Athletic Field	S425	SSHS-IRM5A2-S425-20211103	SSHS-IRM5A2-S425	11/3/2021	-	857.48	-	853.46	2 - 4 ft	4.02 ft	1801294631	Not Excavated							
Northern Athletic Field	S428	SSHS-IRM5A2-S428-20211103	SSHS-IRM5A2-S428	11/3/2021	-	857.89	-	853.88	2 - 4 ft	4 ft	1801294631	Not Excavated							
Northern Athletic Field	S429	SSHS-IRM5A2-S429-20211103	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated							
Northern Athletic Field	S430	SSHS-IRM5A2-S430-20211103	SSHS-IRM5A2-S430	11/3/2021	-	857.97	-	854.59	2 - 4 ft	3.38 ft	1801294631	Not Excavated							
Northern Athletic Field	S431	SSHS-IRM5A2-S431-20211103	SSHS-IRM5A2-S431	11/3/2021	-	857.94	-	854.37	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S432	SSHS-IRM5A2-S432-20211103	SSHS-IRM5A2-S432	11/3/2021	-	857.72	-	854.39	2 - 4 ft	3.33 ft	1801294631	Not Excavated							
Northern Athletic Field	S422	SSHS-IRM5A2-S422-20211103	SSHS-IRM5A2-S422	11/3/2021	-	857.49	-	853.93	2 - 4 ft	3.57 ft	1801294631	Not Excavated							
Northern Athletic Field	S423	SSHS-IRM5A2-S423-20211103	SSHS-IRM5A2-S423	11/3/2021	-	857.43	-	853.81	2 - 4 ft	3.62 ft	1801294631	Not Excavated							
Northern Athletic Field	S424	SSHS-IRM5A2-S424-20211103	SSHS-IRM5A2-S424	11/3/2021	-	857.39	-	853.51	2 - 4 ft	3.88 ft	1801294631	Not Excavated							
Northern Athletic Field	S444	SSHS-IRM5A2-S444-20211104	SSHS-IRM5A2-S444	11/4/2021	-	856.90	-	853.09	2 - 4 ft	3.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S445	SSHS-IRM5A2-S445-20211104	SSHS-IRM5A2-S445	11/4/2021	-	856.79	-	853.04	2 - 4 ft	3.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S449	SSHS-IRM5A2-S449-20211104	SSHS-IRM5A2-S449	11/4/2021	-	856.77	-	853.12	2 - 4 ft	3.65 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	110621 09:30_SSHS-IRM5A2-B522	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	180-129637-1	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-DUP12-20211105	SSHS-IRM5A2-DUP12	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S516	SSHS-IRM5A2-S516-20211105	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated							
Northern Athletic Field	S519	SSHS-IRM5A2-S519-20211105	SSHS-IRM5A2-S519	11/5/2021	-	858.37	-	855.15	2 - 4 ft	3.22 ft	1801296371	Not Excavated							
Northern Athletic Field	S517	SSHS-IRM5A2-S517-20211105	SSHS-IRM5A2-S517	11/5/2021	-	858.23	-	854.67	2 - 4 ft	3.57 ft	1801296371	Not Excavated							
Northern Athletic Field	S520	SSHS-IRM5A2-S520-20211105	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated							
Northern Athletic Field	S518	SSHS-IRM5A2-S518-20211105	SSHS-IRM5A2-S518	11/5/2021	-	858.23	-	855.49	2 - 4 ft	2.74 ft	1801296371	Not Excavated							
Northern Athletic Field	B522	SSHS-IRM5A2-B522-20211105	SSHS-IRM5A2-B522	11/5/2021	-	858.29	-	854.39	2 - 4 ft	3.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S521	SSHS-IRM5A2-S521-20211105	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated							
Northern Athletic Field	B729A	SSHS-IRM5A2-B729A-20211105	SSHS-IRM5A2-B729A	11/5/2021	-	858.31	-	856.18	2 - 4 ft	2.13 ft	1801296371	Not Excavated							
Northern Athletic Field	B782	SSHS-IRM5A2-B782-20211106	SSHS-IRM5A2-B782	11/6/2021	-	856.76	-	853.41	2 - 4 ft	3.35 ft	1801296741	Not Excavated							
Northern Athletic Field	B744	SSHS-IRM5A2-B744-20211106	SSHS-IRM5A2-B744	11/6/2021	-	856.96	-	853.74	2 - 4 ft	3.22 ft	1801296741	Not Excavated							
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1-20211108	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 0.0010 U	< 0.00056 U	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00076 U	< 0.0014 U
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1-20211108	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 0.0010 U	< 0.00056 U	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00076 U	< 0.0014 U
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B-20211109	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated							
Northern Athletic Field	B781	SSHS-IRM5A2-B781-20211123	SSHS-IRM5A2-B781	11/23/2021	-	856.85	-	853.62	2 - 4 ft	3.24 ft	1801303991	Not Excavated							
Northern Athletic Field	B760A	SSHS-IRM5A2-B760A-20211123	SSHS-IRM5A2-B760A	11/23/2021	-	857.39	-	853.94	2 - 4 ft	3.45 ft	1801303991	Not Excavated							
Northern Athletic Field	B762	SSHS-IRM5A2-B762-20211123	SSHS-IRM5A2-B762	11/23/2021	-	856.93	-	853.37	2 - 4 ft	3.55 ft	1801303991	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18-20211201	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B794	SSHS-IRM5A2-B794-20211201	SSHS-IRM5A2-B794	12/1/2021	-	855.99	-	853.55	2 - 4 ft	2.44 ft	1801305751	Not Excavated							
Northern Athletic Field	B791	SSHS-IRM5A2-B791-20211201	SSHS-IRM5A2-B791	12/1/2021	-	856.40	-	853.54	2 - 4 ft	2.86 ft	1801305751	Not Excavated							
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A-20211201	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated							
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A-20211201	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated							
Northern Athletic Field	B737	SSHS-IRM5A2-B737-20211201	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated							
Northern Athletic Field	B784	SSHS-IRM5A2-B784-20211201	SSHS-IRM5A2-B784	12/1/2021	-	856.68	-	853.43	2 - 4 ft	3.25 ft	1801305751	Not Excavated							
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1-20211201	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated							
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1-20211204	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated							
Northern Athletic Field	B729	SSHS-IRM5A2-B729-20211204	SSHS-IRM5A2-B729	12/4/2021	-	858.20	-	855.25	2 - 4 ft	2.95 ft	1801307631	Not Excavated							
Northern Athletic Field	B738	SSHS-IRM5A2-B738-20211204	SSHS-IRM5A2-B738	12/4/2021	-	857.76	-	854.38	2 - 4 ft	3.38 ft	1801307631	Not Excavated							
Northern Athletic Field	B739	SSHS-IRM5A2-B739-20211204	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated							
Northern Athletic Field	B740	SSHS-IRM5A2-B740-20211204	SSHS-IRM5A2-B740	12/4/2021	-	856.84	-	853.93	2 - 4 ft	2.91 ft	1801307631	Not Excavated							
Northern Athletic Field	B751	SSHS-IRM5A2-B751-20211204	SSHS-IRM5A2-B751	12/4/2021	-	856.85	-	854.09	2 - 4 ft	2.76 ft	1801307631	Not Excavated							
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752-20211204	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated								
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated								
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	0.00025 J	< 0.00036 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	0.00060 J	< 0.00039 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated								
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.015 U	< 0.0055 U	< 0.012 U	< 0.0091 U	< 0.0098 U	< 0.0089 U	< 0.016 U	< 0.0079 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 UT	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	0.01 J	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 U	< 0.00027 U	< 0.00063 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00059 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	0.0044 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated								
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated							
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated							
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 UT	< 0.00020 U	< 0.00043 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 UT	< 0.00022 U	< 0.00047 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated							
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.0051 U	< 0.0097 U	< 0.011 U	< 0.0063 U	< 0.0077 U	< 0.0093 U	< 0.013 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated							
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated							
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 UT	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 UT
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00033 U	< 0.00062 U	< 0.00028 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00031 U	< 0.00058 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated							
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated								
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated								
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated								
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.018 U	< 0.0053 U	< 0.0097 U	< 0.0065 U	< 0.012 U	< 0.0058 U	< 0.0062 U	< 0.0056 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0058 UT	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0050 UT	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0050 UT	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0053 UT	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0047 UT	< 0.0014 U	< 0.0026 UT	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00073 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 UT	< 0.0015 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 UT	< 0.0014 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated								
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated								
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated								
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated								
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.0088 U	< 0.016 U	< 0.0059 U	< 0.0068 U	< 0.0052 U	< 0.0086 U	< 0.0088 U	< 0.0072 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 UT	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00017 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 UT	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated								
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0029 U	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated								
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated								
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 UT	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.00031 U	< 0.0017 UT	< 0.00029 U	< 0.0044 UT	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated								
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.0078 U	< 0.0061 U	< 0.01 U	< 0.029 U	< 0.0094 U	< 0.0099 U	< 0.0071 U	< 0.0057 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	0.0047 J	< 0.0019 U	< 0.0015 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated								
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00032 U	< 0.00023 U	< 0.00099 U	< 0.00032 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00092 U	< 0.00030 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated								
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U

DRAFT

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated							
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated							
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated							
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 UT	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 UT	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 UT	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.0058 U	< 0.0059 U	< 0.0078 U	< 0.0056 U	< 0.011 U	< 0.0099 U	< 0.0065 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 UT	< 0.0017 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	0.0025 J	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated							
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated							
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0033 U	< 0.0021 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT	< 0.0017 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00019 U	< 0.00015 U	< 0.00011 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00028 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated							
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT-20211210	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 0.00015 U	0.0016	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT-20211217	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated							
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT-20211217	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated							
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928BOT-20211220	SSHS-IRM5A2-S928BOT	12/20/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315621	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00050 UT	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927BOT-20211220	SSHS-IRM5A2-S927BOT	12/20/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315621	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 UT	< 0.00018 U	< 0.00020 U	< 0.00065 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-S-20220130	SSHS-IRM5A2-RS-BOT18-S	1/30/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated							
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30-20220131	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18-20220131	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43-20220131	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25-20220131	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 0.0039 U	< 0.0061 U	< 0.016 U	< 0.014 U	< 0.0069 U	< 0.0078 U	< 0.028 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26-20220131	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27-20220131	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54-20220202	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39-20220202	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37-20220207	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41-20220207	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42-20220207	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A-20220207	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61-20220207	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64-20220207	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43-20220211	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44-20220211	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77-20220303	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85-20220303	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220305	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220305	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220305	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220305	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220305	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated							
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220305	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated							
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220306	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated							
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7-20220307	SSHS-IRM5A2-NE-MSA-BOT7	3/7/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6-20220307	SSHS-IRM5A2-NE-MSA-BOT6	3/7/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9-20220307	SSHS-IRM5A2-NE-MSA-BOT9	3/7/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1-20220307	SSHS-IRM5A2-NE-MSA-BOT1	3/7/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2-20220307	SSHS-IRM5A2-NE-MSA-BOT2	3/7/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91-20220307	SSHS-ISMP-SLT-S91	3/7/2022	-	857.12	-	853.81	2 - 4 ft	3.31	1801347841	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S460	SSHS-IRM5A2-S460-20220307	SSHS-IRM5A2-S460	3/7/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1-20220310	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2-20220310	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3-20220310	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4-20220310	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1-20220310	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6-20220311	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8-20220311	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10-20220311	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.56	1801350892	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3-20220311	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13-20220311	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1-20220314	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15-20220314	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.82	1801351292	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18-20220314	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3-20220316	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00011 U	0.00040 J	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00012 U	< 0.00041 U
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33-20220316	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.51	1801352871	Not Excavated	< 0.00011 U	0.00024 J	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00012 U	< 0.00038 U
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45-20220317	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00051 U
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48-20220317	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00057 U
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51-20220318	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.13	1801354291	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55-20220318	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61-20220321	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1-20220322	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2-20220322	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1-20220324	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C-20220328	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A-20220328	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1S-20220329	SSHS-IRM5A2-PIPE1S	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated							
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1-20220329	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9-20220408	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166-20220408	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174-20220408	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167-20220408	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175-20220408	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88-20220408	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154-20220408	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83-20220408	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63-20220421	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00078 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.0075 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00023 U	< 0.00021 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.015 U	< 0.00066 U	< 0.00072 U	< 0.00066 U	< 0.0011 U	< 0.0026 U	< 0.00068 U	< 0.00099 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.0080 U	< 0.00036 U	< 0.00039 U	< 0.00036 U	< 0.00060 U	< 0.0014 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.0095 U	< 0.00043 U	< 0.00047 U	< 0.00043 U	< 0.00070 U	< 0.0017 U	< 0.00044 U	< 0.00064 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.014 U	< 0.00061 U	< 0.00066 U	< 0.00061 U	< 0.0010 U	< 0.0024 U	< 0.00063 U	< 0.00091 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.0080 U	< 0.00036 U	< 0.00039 U	< 0.00036 U	< 0.00060 U	< 0.0014 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	FLS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.012 U	< 0.00052 U	< 0.00057 U	< 0.00052 U	< 0.00086 U	< 0.0020 U	0.0021	< 0.00078 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	0.0068	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.0072 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0013 U	< 0.00033 U	< 0.00049 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	0.051	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	0.00026 J	< 0.00036 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	0.0090	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.0063 UT	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 UT	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	0.091	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	0.0016	< 0.00035 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.0054 UT	< 0.00024 UT	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00094 U	< 0.00025 UT	< 0.00036 UT
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.0075 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00055 U	< 0.0013 U	< 0.00035 U	< 0.00050 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.0074 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	0.021	< 0.00050 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00023 U	< 0.00021 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00060 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 U	< 0.00027 U	< 0.00063 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	0.0069	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.00023 U	< 0.00025 UT	< 0.00068 U	< 0.0013 U	< 0.00057 UT	< 0.00029 U	< 0.00060 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00051 U	< 0.00094 U	< 0.00042 UT	< 0.00021 U	< 0.00045 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.00014 U	< 0.00015 UT	< 0.00041 U	< 0.00077 U	< 0.00034 UT	< 0.00017 U	< 0.00036 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00044 U	< 0.00081 U	< 0.00036 UT	< 0.00018 U	< 0.00038 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00045 U	< 0.00050 U	< 0.0013 U	< 0.0025 U	< 0.0011 U	< 0.00056 U	< 0.0012 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00052 UT	< 0.00027 U	< 0.00055 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	< 0.00028 U	< 0.00058 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00073 U	< 0.0014 U	< 0.00061 UT	< 0.00031 U	< 0.00065 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.00029 U	< 0.00032 U	< 0.00086 U	< 0.0016 U	< 0.00072 U	< 0.00037 U	< 0.00076 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.00042 U	< 0.00046 U	< 0.0012 U	< 0.0023 U	< 0.0010 U	< 0.00052 U	< 0.0011 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00073 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00065 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0023 J	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0026 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0019 J	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00036 U	< 0.00039 U	< 0.0011 U	< 0.0020 U	< 0.00088 U	< 0.00045 U	< 0.00093 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	< 0.00028 U	< 0.00058 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00019 UT	< 0.00021 UT	< 0.00057 UT	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 UT
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00017 UT	< 0.00018 UT	< 0.00049 U	< 0.00091 UT	< 0.00041 U	< 0.00021 UT	< 0.00043 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00042 U	< 0.00077 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00068 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0013 U	< 0.00056 U	< 0.00029 U	< 0.00059 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0035 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0038 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0036 BJ	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00039 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0027 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0022 J	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0022 J	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0023 J	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0037 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	0.0042 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0036 BJ	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00030 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00031 U	< 0.00058 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00033 U	< 0.00061 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.000098 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0018 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00029 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.0029 U	< 0.00046 U	< 0.00086 U	< 0.00092 U	< 0.00093 U	< 0.00057 U	< 0.00053 U	< 0.00076 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 UT	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00046 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00049 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00048 UT	< 0.00051 U	< 0.00051 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.0019 U	< 0.00030 U	< 0.00056 U	< 0.00060 U	< 0.00060 U	< 0.00037 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.0027 U	< 0.00042 U	< 0.00080 U	< 0.00085 U	< 0.00086 U	< 0.00053 U	< 0.00049 U	< 0.00070 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00048 U	< 0.00051 U	< 0.00051 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	0.0069	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.0023 U	< 0.00036 U	< 0.00068 U	< 0.00073 U	< 0.00074 U	< 0.00045 U	< 0.00042 U	< 0.00060 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.0013 U	< 0.00020 UT	< 0.00037 U	< 0.00040 UT	< 0.00040 UT	< 0.00025 UT	< 0.00023 U	< 0.00033 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.0011 U	< 0.00017 UT	< 0.00032 UT	< 0.00034 UT	< 0.00034 UT	< 0.00021 UT	< 0.00019 UT	< 0.00028 U
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00029 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00047 U	< 0.00029 U	< 0.00027 U	< 0.00038 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00019 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.00069 U	< 0.00011 U	< 0.00020 U	< 0.00022 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.00072 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.00063 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0027 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.00029 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00055 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00057 U	< 0.00098 U	< 0.00091 U	< 0.00063 U	< 0.0011 U	< 0.00070 U	< 0.00068 U	< 0.00051 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00048 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00050 U	< 0.00035 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.00037 U	< 0.00063 U	< 0.00059 U	< 0.00041 U	< 0.00070 U	< 0.00045 U	< 0.00044 U	< 0.00033 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.00053 U	< 0.00090 U	< 0.00085 U	< 0.00058 U	< 0.0010 U	< 0.00064 U	< 0.00063 U	< 0.00047 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00050 U	< 0.00035 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00045 U	< 0.00077 U	< 0.00072 U	< 0.00050 U	< 0.00085 U	< 0.00055 U	< 0.00054 U	< 0.00040 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 UT	< 0.00029 UT	< 0.00022 UT
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00021 UT	< 0.00036 UT	< 0.00034 UT	< 0.00023 UT	< 0.00040 UT	< 0.00026 UT	< 0.00025 UT	< 0.00019 UT
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.00029 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00055 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00032 U	< 0.00055 U	< 0.00035 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00017 U	< 0.00012 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0030 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00067 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00077 U	< 0.0044 U	< 0.00073 U	< 0.011 UT	< 0.0013 U	< 0.00094 U	< 0.0040 U	< 0.0013 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00063 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 UT	< 0.00068 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0060 U	< 0.00070 U	< 0.00052 U	< 0.0022 U	< 0.00072 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.00050 U	< 0.0028 U	< 0.00047 U	< 0.0071 UT	< 0.00083 U	< 0.00061 U	< 0.0026 U	< 0.00085 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.00071 U	< 0.0040 U	< 0.00067 U	< 0.01 UT	< 0.0012 U	< 0.00087 U	< 0.0037 U	< 0.0012 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0060 UT	< 0.00070 U	< 0.00052 U	< 0.0022 U	< 0.00072 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 UT	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0030 UT	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00061 U	< 0.0035 U	< 0.00057 U	< 0.0087 U	< 0.0010 U	< 0.00074 U	< 0.0031 U	< 0.0010 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0054 U	< 0.00063 U	< 0.00046 U	< 0.0020 U	< 0.00064 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.00028 U	< 0.0016 U	0.00036 J	< 0.0040 U	< 0.00047 U	0.015	< 0.0015 U	< 0.00048 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	0.00064 J	< 0.0016 U	< 0.00052 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 UT	< 0.0047 UT	< 0.00055 U	< 0.00040 U	< 0.0017 UT	< 0.00056 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.00027 U	0.0024 J	< 0.00026 U	< 0.0039 U	< 0.00045 U	0.031	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00028 UT	< 0.0016 UT	< 0.00027 UT	< 0.0040 UT	< 0.00047 UT	< 0.00035 UT	< 0.0015 UT	< 0.00048 UT
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00067 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00056 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.00034 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00093 U	< 0.00031 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00097 U	< 0.00032 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00095 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00020 U	< 0.00086 U	< 0.00028 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0018 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0033 U	< 0.0021 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00040 UT	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00030 UT
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 UT	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 UT
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 UT	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 UT
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 UT	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 UT
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00071 U	< 0.00055 U	< 0.00078 U	< 0.00060 U	< 0.00046 U	< 0.00091 U	< 0.00060 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00025 U	< 0.00050 U	< 0.00033 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.00046 U	< 0.00035 U	< 0.00050 U	< 0.00039 U	< 0.00030 U	< 0.00059 U	< 0.00039 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.00066 U	< 0.00051 U	< 0.00072 U	< 0.00055 U	< 0.00043 U	< 0.00085 U	< 0.00055 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00025 U	< 0.00050 U	< 0.00033 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 UT	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00056 U	< 0.00043 U	< 0.00062 U	< 0.00047 U	< 0.00037 U	< 0.00072 U	< 0.00047 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	0.00030 J	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00031 UT	< 0.00024 UT	< 0.00033 U	< 0.00026 UT	< 0.00020 U	< 0.00039 UT	< 0.00026 U
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00026 UT	< 0.00020 U	< 0.00029 UT	< 0.00022 UT	< 0.00017 UT	< 0.00034 UT	< 0.00022 UT
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	0.00052 J	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00028 U	< 0.00019 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	0.00090 J	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00030 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00015 U	< 0.00011 U	< 0.00022 U	< 0.00015 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S481	SSHS-IRM5A2-S481-20220421	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528-20220421	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	S145	SSHS-IRM5A2-S145-20220421	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	S146	SSHS-IRM5A2-S146-20220421	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65-20220422	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	S525	SSHS-IRM5A2-S525-20220422	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524-20220422	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	S523	SSHS-IRM5A2-S523-20220422	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504-20220422	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001-20220502	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00070 U
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002-20220502	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00050 U
Northern Athletic Field	S861	SSHS-IRM5A2-S861-20220505	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00079 U
Northern Athletic Field	S956	SSHS-IRM5A2-S956-20220506	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00071 UT	< 0.00023 U	< 0.00025 U	< 0.00084 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A-20220506	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 UT	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	S957	SSHS-IRM5A2-S957-20220506	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 UT	< 0.00014 U	< 0.00015 U	< 0.00051 U
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021-20220506	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 UT	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85-20220509	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00045 U	< 0.00082 U	< 0.0010 U	< 0.0014 U	< 0.00044 U	< 0.00050 U	< 0.0016 U
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13-20220509	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00049 U	< 0.00066 UT	< 0.00021 U	< 0.00023 U	< 0.00077 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531-20220509	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00069 UT	< 0.00022 U	< 0.00025 U	< 0.00082 U
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2-20220509	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00054 U	< 0.00073 U	< 0.00023 U	< 0.00026 U	< 0.00085 U
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15-20220509	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated	< 0.00025 U	< 0.00045 U	< 0.00057 U	< 0.00077 UT	< 0.00024 U	< 0.00027 U	< 0.00090 U
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1-20220509	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated	< 0.00029 U	< 0.00053 U	< 0.00067 U	< 0.00090 U	< 0.00029 U	< 0.00032 U	< 0.0011 U
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2-20220509	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated	< 0.00042 U	< 0.00076 U	< 0.00096 U	< 0.0013 U	< 0.00041 U	< 0.00046 U	< 0.0015 U
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3-20220509	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated	< 0.00025 U	< 0.00045 U	< 0.00057 U	< 0.00077 U	< 0.00024 U	< 0.00027 U	< 0.00090 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86-20220511	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1-20220511	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2-20220511	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3-20220511	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4-20220511	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005-20220518	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006-20220518	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007-20220518	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102-20220606	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00036 U	< 0.00065 U	< 0.00082 U	< 0.0011 U	< 0.00035 U	< 0.00039 U	< 0.00035 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1-20220606	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated	< 0.00017 U	0.00060 J	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2-20220606	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00069 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	S951	SSHS-IRM5A2-S951-20220606	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950-20220606	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	0.00064 J	0.00060 J	0.0012 J
Northern Athletic Field	S949	SSHS-IRM5A2-S949-20220606	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	S948	SSHS-IRM5A2-S948-20220606	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00020 UT	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 UT	< 0.00021 UT	< 0.00019 UT
Northern Athletic Field	S947	SSHS-IRM5A2-S947-20220606	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	S946	SSHS-IRM5A2-S946-20220606	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400-20220606	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated	< 0.00017 UT	< 0.00030 UT	< 0.00038 UT	< 0.00051 U	< 0.00016 UT	< 0.00018 UT	< 0.00016 UT
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401-20220606	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402-20220606	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402-20220606	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00071 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403-20220606	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404-20220606	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405-20220606	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00052 U	< 0.00071 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202-20220616	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204-20220616	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205-20220616	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131-20220617	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00015 U	0.00044 J	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A-20220617	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A-20220617	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A-20220617	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A-20220617	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated	< 0.00015 U	0.00032 J	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207-20220617	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated	< 0.00015 U	0.00055 J	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT-20220622	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211-20220622	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212-20220622	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213-20220622	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 0.0011 U	0.0038 J	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143-20220630	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48-20220630	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168-20220630	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200-20220701	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201-20220701	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203-20220701	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00033 U	< 0.00010 U	< 0.00012 U	< 0.00010 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400-20220701	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401-20220701	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402-20220701	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204-20220705	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408-20220705	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated	< 0.000099 U	< 0.00018 U	< 0.00023 U	< 0.00030 U	< 0.00096 U	< 0.00011 U	< 0.000096 U
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403-20220705	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407-20220705	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00046 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 UT	< 0.0038 U	< 0.0019 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 U	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	0.063	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	0.01	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.0075 U	< 0.00034 UT	< 0.00037 UT	< 0.00034 UT	< 0.00056 UT	< 0.0013 U	< 0.00035 UT	< 0.00051 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0037 UT	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 UT	< 0.0038 U	< 0.0019 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	0.0050 J	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	0.0066 BJ	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.0033 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0034 U	< 0.0017 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	0.016 BJ	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.0036 UT	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 UT	< 0.0037 U	< 0.0019 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0038 UT	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 UT	< 0.0039 U	< 0.0020 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0040 UT	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 UT	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	0.0076 BJ	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	0.0095 BJ	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	0.0091	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	0.014	< 0.00036 U	< 0.00039 U	< 0.00036 U	< 0.00059 U	< 0.0014 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.0070 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	0.0072	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0011 U	< 0.00031 U	< 0.00044 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	0.016	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00078 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00069 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 U	< 0.00017 U	< 0.00041 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	0.0065 BJ	< 0.0021 U	< 0.0045 U	< 0.0035 U	< 0.0038 U	< 0.0034 U	< 0.0060 U	< 0.0030 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	0.022	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.0048 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 UT	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0040 U	< 0.0031 U	< 0.0034 U	< 0.0030 U	< 0.0053 U	< 0.0027 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	0.0053 J	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00052 U	< 0.00027 U	< 0.00055 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 UT	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.00023 UT	< 0.00026 UT	< 0.00069 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00061 UT
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 UT	< 0.0015 UT	< 0.0019 U	< 0.0023 U	< 0.0031 UT
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.0011 U	< 0.0021 U	< 0.0025 U	< 0.0014 U	< 0.0017 U	< 0.0020 U	< 0.0028 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 UT	< 0.0015 UT	< 0.0018 U	< 0.0022 U	< 0.0030 UT
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 UT	< 0.0016 UT	< 0.0019 U	< 0.0023 U	< 0.0031 UT
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0016 UT	< 0.0020 U	< 0.0024 U	< 0.0033 UT
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 UT
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 UT
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00073 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00064 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.000087 U	< 0.000095 U	< 0.00026 U	< 0.00048 U	< 0.00021 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.000072 U	< 0.000079 U	< 0.00021 U	< 0.00039 U	< 0.00018 U	< 0.000090 U	< 0.00019 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.0019 U	< 0.0037 U	< 0.0044 U	< 0.0024 U	< 0.0030 U	< 0.0036 U	< 0.0048 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.000088 U	< 0.000096 UT	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0039 U	< 0.0021 U	< 0.0026 U	< 0.0032 U	< 0.0043 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00099 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.0015 U	< 0.00024 UT	< 0.00045 U	< 0.00048 UT	< 0.00048 UT	< 0.00030 UT	< 0.00027 UT	< 0.00039 UT
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0043 UT	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.0042 UT	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.0039 UT	< 0.0012 U	< 0.0021 U	< 0.0014 U	< 0.0026 U	< 0.0013 U	< 0.0014 U	< 0.0012 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.0042 UT	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0044 UT	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0046 UT	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.0041 U	< 0.0012 U	< 0.0022 U	< 0.0015 UT	< 0.0028 UT	< 0.0013 UT	< 0.0014 U	< 0.0013 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 UT	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	0.0015 J	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00047 U	< 0.00050 U	< 0.00051 U	< 0.00031 U	< 0.00029 U	< 0.00041 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.00079 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.00056 U	< 0.000088 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.00047 U	< 0.000073 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000091 U	< 0.000084 U	< 0.00012 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.0067 U	< 0.0020 U	< 0.0037 U	< 0.0025 U	< 0.0046 U	< 0.0022 U	< 0.0024 U	< 0.0021 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.00057 U	< 0.000089 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0060 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0041 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.00030 U	< 0.00050 UT	< 0.00047 UT	< 0.00032 UT	< 0.00056 U	< 0.00036 UT	< 0.00035 UT	< 0.00026 UT
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.0013 U	< 0.0015 U	< 0.0011 U	< 0.0019 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.0020 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.00031 U	< 0.00053 U	< 0.00050 U	< 0.00034 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00027 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000098 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.000091 U	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000081 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.0034 U	< 0.0061 U	< 0.0023 U	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0034 U	< 0.0028 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000098 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0030 U	< 0.0054 U	< 0.0020 U	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0030 U	< 0.0025 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.00027 U	< 0.0015 UT	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.00027 U	< 0.0016 UT	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.00030 U	< 0.0017 UT	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.00040 U	< 0.0023 UT	< 0.00038 UT	< 0.0057 U	< 0.00066 UT	< 0.00049 U	< 0.0021 UT	< 0.00068 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.0018 U	< 0.0015 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.0019 U	< 0.0015 UT	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0024 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0063 U	< 0.0021 U	< 0.0022 UT	< 0.0016 U	< 0.0013 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 UT	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0024 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 UT	< 0.0018 U	< 0.0014 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 UT	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0066 U	< 0.0022 U	< 0.0023 UT	< 0.0016 U	< 0.0013 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.0020 U	< 0.0016 UT	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 UT	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0060 U	< 0.00070 U	< 0.00051 U	< 0.0022 U	< 0.00071 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.00015 U	< 0.00084 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.00012 U	< 0.00070 U	< 0.00012 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00063 U	< 0.00021 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.0030 U	< 0.0023 U	< 0.0039 U	< 0.011 U	< 0.0036 U	< 0.0038 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	0.019	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	0.0041 J	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.0098 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0030 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated								

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	0.0012	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	0.00042 J	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	0.00065 J	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.00037 UT	< 0.00028 UT	< 0.00040 UT	< 0.00031 UT	< 0.00024 UT	< 0.00047 UT	< 0.00031 U
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0014 UT	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 UT	< 0.0024 UT	< 0.0016 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0024 U	< 0.0015 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0017 U	< 0.0012 U	< 0.0024 U	< 0.0022 U	< 0.0014 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.0014 UT	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0027 UT	< 0.0025 UT	< 0.0016 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.0015 UT	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 UT	< 0.0025 UT	< 0.0016 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0015 UT	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UT	< 0.0026 UT	< 0.0017 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.0013 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 UT	< 0.0023 UT	< 0.0015 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 UT	< 0.0026 UT	< 0.0017 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00042 U	< 0.00033 U	< 0.00025 U	< 0.00050 U	< 0.00032 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00044 U	< 0.00028 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 UT	< 0.00043 UT	< 0.00028 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 UT	< 0.00041 UT	< 0.00027 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	0.00038 J	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.00014 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000089 U	< 0.00018 U	< 0.00011 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.00011 U	< 0.000087 U	< 0.00012 U	< 0.000095 U	< 0.000074 U	< 0.00015 U	< 0.000095 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.0022 U	< 0.0023 U	< 0.0030 U	< 0.0021 U	< 0.0041 U	< 0.0038 U	< 0.0025 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	0.00033 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	0.00020 J	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	0.00062	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0022 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	0.0039 J	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412-20220705	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 UT	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149-20220708	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409-20220708	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410-20220708	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420-20220711	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446-20220713	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164-20220714	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453-20220714	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456-20220714	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461-20220714	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A-20220714	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 UT	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463-20220714	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464-20220714	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468-20220714	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421-20220714	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425-20220714	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429-20220714	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated	< 0.00019 UT	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430-20220714	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated	< 0.00023 UT	< 0.00042 UT	< 0.00054 U	< 0.00072 U	< 0.00023 UT	< 0.00026 UT	< 0.00023 UT
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431-20220714	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated	< 0.00016 UT	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169-20220722	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424-20220722	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 0.00091 U	< 0.0015 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423-20220722	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0038 U	< 0.0033 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422-20220722	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 0.00085 U	< 0.0013 U	< 0.0036 U	< 0.0031 U	< 0.0015 U	< 0.0017 U	< 0.0062 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406-20220722	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT-20220722	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0039 U	< 0.0033 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT-20220722	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT-20220722	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201-20220722	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 0.00089 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0065 U
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202-20220722	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171-20220725	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432-20220725	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated	< 0.00025 U	< 0.00045 U	< 0.00057 U	< 0.00076 U	< 0.00024 U	< 0.00027 U	< 0.00024 U
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434-20220725	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435-20220725	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436-20220725	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437-20220725	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438-20220725	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439-20220725	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440-20220725	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441-20220725	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442-20220725	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2-20220817	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3-20220817	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206-20220819	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207-20220819	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216-20220822	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217-20220822	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated	< 0.000087 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000085 U	< 0.000095 U	< 0.000085 U
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219-20220822	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated	< 0.000072 U	< 0.00013 U	< 0.00016 U	< 0.00022 U	< 0.000071 U	< 0.000079 U	< 0.000071 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-20220826	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0062 U	< 0.0054 U	< 0.0027 U	< 0.0030 U	< 0.011 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225-20220901	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229-20220901	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230-20220901	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231-20220901	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232-20220901	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233-20220901	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234-20220901	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235-20220901	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236-20220901	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237-20220901	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239-20220919	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000086 U	< 0.000096 U	< 0.000086 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235-20220927	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0013 U	< 0.0021 U	< 0.0055 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0096 U
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240-20220927	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241-20220927	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242-20220927	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243-20220927	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244-20220927	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245-20220927	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246-20220927	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431-20220927	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432-20220927	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221020	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221020	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221020	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221020	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221020	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	0.036	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 UT	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	0.016	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 UT	< 0.00032 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	< 0.00034 UT	< 0.00050 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	0.021	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00051 U	0.00050 JT	< 0.00020 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 UT	< 0.00034 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	0.032	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	0.00036 J	< 0.00039 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00019 U	< 0.00045 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.0039 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00029 UT	< 0.00068 UT	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 UT	< 0.00051 U	< 0.00014 U	< 0.00020 UT
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.0031 U	0.00014 J	< 0.00015 U	< 0.00014 U	< 0.00023 UT	< 0.00053 U	< 0.00014 U	< 0.00021 UT
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 UT	< 0.00053 U	< 0.00014 U	< 0.00021 UT
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.0033 U	0.00039 J	< 0.00016 U	< 0.00015 U	< 0.00024 UT	< 0.00057 U	< 0.00015 U	< 0.00022 UT
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.0025 U	0.00018 J	< 0.00012 U	< 0.00011 U	< 0.00019 UT	< 0.00044 U	< 0.00012 U	< 0.00017 UT
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 UT	< 0.00057 U	< 0.00015 U	< 0.00022 UT
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.0034 U	0.00088	< 0.00017 U	< 0.00015 U	< 0.00025 UT	< 0.00059 U	< 0.00016 U	< 0.00023 UT
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.0030 U	< 0.00013 U	< 0.00015 U	< 0.00013 U	< 0.00022 UT	< 0.00052 U	< 0.00014 UT	< 0.00020 UT
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 UT	< 0.00053 U	< 0.00014 U	< 0.00021 UT
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00031 U	< 0.00051 UT	< 0.0012 U	< 0.00032 U	< 0.00046 UT
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 UT	< 0.0011 U	< 0.00029 U	< 0.00042 UT
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 UT	< 0.00054 U	< 0.00014 U	< 0.00021 UT
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 UT	< 0.00059 U	< 0.00016 U	< 0.00023 UT
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.0041 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 UT	< 0.00072 U	< 0.00019 U	< 0.00028 UT
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 UT	< 0.00041 UT
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 UT	< 0.0011 U	< 0.00029 UT	< 0.00042 UT
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 UT	< 0.00059 U	< 0.00016 UT	< 0.00023 UT
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 UT	< 0.00057 U	< 0.00015 UT	< 0.00022 UT
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 UT	< 0.00091 U	< 0.00024 UT	< 0.00035 UT
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	0.01 T	< 0.00041 UT
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.0032 U	< 0.00015 U	< 0.00016 U	< 0.00014 U	< 0.00024 UT	< 0.00056 U	< 0.00015 UT	< 0.00022 UT
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00093 U	< 0.00025 UT	< 0.00036 UT
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00070 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00016 U	< 0.00027 U	< 0.00064 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.0043 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00032 U	< 0.00076 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00079 U	0.00027 J	< 0.00030 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 U	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00057 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.0074 U	< 0.00034 U	< 0.00037 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	< 0.00035 U	< 0.00050 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00067 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.0043 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00032 U	< 0.00075 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 UT	< 0.0011 U	< 0.00030 UT	< 0.00043 UT
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 UT	< 0.00025 UT	< 0.00058 U	< 0.00015 UT	< 0.00022 UT
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 UT	< 0.00045 UT	< 0.0010 U	< 0.00028 UT	< 0.00041 UT
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	0.052	0.0016	< 0.00034 U	< 0.00031 UT	< 0.00052 UT	< 0.0012 U	< 0.00032 UT	< 0.00047 UT
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00029 UT	< 0.00049 UT	< 0.0011 U	< 0.00030 UT	< 0.00044 UT
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 UT	< 0.00049 UT	< 0.0011 U	< 0.00031 UT	< 0.00044 UT
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 UT	< 0.00048 UT	< 0.0011 U	< 0.00030 UT	< 0.00044 UT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	< 0.000090 U	< 0.000099 U	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.000079 U	< 0.000087 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000099 U	< 0.00021 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00066 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.000090 U	< 0.000099 UT	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.000095 U	< 0.00010 UT	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.000095 U	< 0.00010 UT	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.000078 U	< 0.000085 UT	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000097 U	< 0.00020 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.000092 U	< 0.00010 UT	< 0.00027 U	< 0.00050 U	< 0.00023 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.000094 U	< 0.00010 UT	< 0.00028 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.000095 U	< 0.00010 UT	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.00013 U	< 0.00014 UT	< 0.00038 U	< 0.00070 U	< 0.00032 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00020 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00029 U	< 0.00055 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00068 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00033 U	< 0.00062 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 U	< 0.00079 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.00013 U	< 0.00015 U	< 0.00039 U	< 0.00073 U	< 0.00033 U	< 0.00017 U	< 0.00035 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00068 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00065 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00039 U	< 0.00072 U	< 0.00032 U	< 0.00016 U	< 0.00034 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.00019 U	< 0.00020 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.00022 U	< 0.00024 UT	< 0.00064 U	< 0.0012 U	< 0.00053 U	0.00086 J	< 0.00056 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	< 0.00059 U	< 0.000092 U	< 0.00017 U	< 0.00018 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	0.0017 J	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.00051 U	< 0.000081 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000092 U	< 0.00013 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00077 U	< 0.00012 U	< 0.00023 U	< 0.00024 UT	< 0.00025 UT	< 0.00015 UT	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00058 U	< 0.000092 U	< 0.00017 U	< 0.00018 U	< 0.00019 U	< 0.00011 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.00061 U	< 0.000096 U	< 0.00018 U	< 0.00019 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00061 U	< 0.000096 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.00050 U	< 0.000079 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.000099 U	< 0.000090 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00061 U	< 0.000095 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00062 U	< 0.000097 U	< 0.00018 U	< 0.00019 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.00083 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.00067 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00064 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00071 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.00080 U	< 0.00013 U	< 0.00024 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00073 U	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.00083 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.00086 U	< 0.00014 U	< 0.00026 U	< 0.00027 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00022 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00049 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00029 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.00085 U	< 0.00013 U	< 0.00025 U	< 0.00027 U	< 0.00027 U	< 0.00017 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	0.0012 J	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	0.0064	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	0.0016 J	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00032 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000089 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.000099 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000087 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00013 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 UT	< 0.00012 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 UT	< 0.00016 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 UT	< 0.00014 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00027 U	< 0.00019 U	< 0.00032 U	< 0.00021 U	< 0.00020 UT	< 0.00015 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 UT	< 0.00023 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 UT	< 0.00020 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00048 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.00029 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00055 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.00017 U	< 0.00028 U	< 0.00027 U	< 0.00018 U	< 0.00032 U	< 0.00020 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00024 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.00027 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00032 U	0.00053 J
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	< 0.00015 U	< 0.00087 U	< 0.00015 U	0.0081	< 0.00026 U	0.0061	< 0.00079 U	< 0.00026 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	0.0029 J	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.00013 U	< 0.00077 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00070 U	< 0.00023 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00020 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00056 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00015 U	< 0.00087 U	< 0.00015 U	< 0.0022 U	< 0.00025 U	< 0.00019 U	< 0.00079 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00091 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00083 U	< 0.00027 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00091 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00083 U	< 0.00027 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.00013 U	< 0.00075 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00068 U	< 0.00022 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00030 U	< 0.00022 U	< 0.00092 U	< 0.00030 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00089 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00091 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00020 U	< 0.00082 U	< 0.00027 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00092 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00084 U	< 0.00028 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00092 U	< 0.00030 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00091 U	< 0.00030 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00017 U	< 0.00096 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00087 U	< 0.00029 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00096 U	< 0.00032 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 UT	< 0.0011 U	< 0.00036 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0028 U	< 0.00032 U	< 0.00024 UT	< 0.0010 U	< 0.00033 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0032 U	< 0.00038 U	< 0.00028 U	< 0.0012 U	< 0.00039 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 UT	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 UT	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 UT	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 UT	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00067 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0029 U	< 0.00033 U	< 0.00025 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.00022 U	< 0.0013 U	< 0.00021 U	< 0.0032 U	< 0.00037 U	< 0.00027 U	< 0.0012 U	< 0.00038 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00061 U	< 0.00045 UT	< 0.0019 U	< 0.00063 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 UT	< 0.00058 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.00017 U	< 0.00099 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	0.00094 J	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.0035	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000093 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.00012 U	< 0.000096 U	< 0.00014 U	0.00080	< 0.000081 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00019 UT	< 0.00014 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00024 UT	< 0.00016 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00035 U	0.0010 J	< 0.00020 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	0.00013 J	< 0.000092 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	0.00013 J	< 0.000097 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	0.00031 J	< 0.000097 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	0.00027 J	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.00012 U	< 0.000094 U	< 0.00013 U	0.00013 J	< 0.000080 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00018 U	< 0.00013 U	< 0.00010 U	< 0.00021 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	0.00037 J	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000094 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000096 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	0.00041 J	< 0.00025 U	< 0.00036 U	0.00080 J	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	854.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.00031 U	< 0.00023 U	< 0.00033 U	0.00040 J	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00016 U	< 0.00013 U	< 0.000097 U	< 0.00019 U	< 0.00013 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.00020 U	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00032 U	0.00026 J	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	0.00016 J	< 0.00010 U	< 0.00021 U	< 0.00013 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	0.00076 J	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	0.00018 J	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00040 J	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00026 J	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.00020 U	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.00021 U	< 0.00016 U	< 0.00023 U	< 0.00018 U	< 0.00014 U	< 0.00027 U	< 0.00018 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00086 J	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00075 J	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00060 J	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	0.00058 J	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.00051 J	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00040 U	0.00073 J	< 0.00024 U	< 0.00047 U	< 0.00030 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.00019 U	< 0.00014 U	< 0.00020 U	0.00056 J	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.00021 U	< 0.00016 U	< 0.00023 U	< 0.00017 U	< 0.00013 U	< 0.00027 U	< 0.00017 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00038 U	0.0019	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00018 U	< 0.00013 U	< 0.00010 U	< 0.00021 U	< 0.00013 UT
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 UT
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	0.0058	< 0.00022 U	< 0.00044 U	< 0.00028 UT
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 UT
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 UT
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00026 UT

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221020	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221020	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221020	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221020	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221020	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221020	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221020	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221020	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241-20221024	SSHS-IRM5A2-DUP241	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	0.00021 J	0.00021 J
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249-20221024	SSHS-IRM5A2-A6-B249	10/24/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00016 U	0.00089	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251-20221024	SSHS-IRM5A2-A6-B251	10/24/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801468431	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252-20221024	SSHS-IRM5A2-A6-B252	10/24/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801468431	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253-20221024	SSHS-IRM5A2-A6-B253	10/24/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801468431	Not Excavated	< 0.000091 U	< 0.00016 U	< 0.00021 U	< 0.00028 U	< 0.000089 U	< 0.000099 U	< 0.000089 U
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254-20221024	SSHS-IRM5A2-A6-B254	10/24/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801468431	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434-20221024	SSHS-IRM5A2-A6-S434	10/24/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801468431	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435-20221024	SSHS-IRM5A2-A6-S435	10/24/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801468431	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439-20221024	SSHS-IRM5A2-A6-B439	10/24/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801468431	Not Excavated	< 0.000080 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000078 U	< 0.000087 U	< 0.000078 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440-20221024	SSHS-IRM5A2-A6-B440	10/24/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801468431	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00027 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442-20221024	SSHS-IRM5A2-A6-B442	10/24/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801468441	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648-20221024	SSHS-IRM5A2-A6-B648	10/24/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801468441	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245-20221026	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.000091 U	< 0.00016 U	< 0.00021 U	< 0.00028 U	< 0.000089 U	< 0.000099 U	< 0.000089 U
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1-20221026	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated	< 0.000095 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000093 U	< 0.00010 U	< 0.000093 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2-20221026	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated	< 0.000095 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000093 U	< 0.00010 U	< 0.000093 U
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3-20221026	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000099 U	< 0.00011 U	< 0.000099 U
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4-20221026	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated	< 0.000078 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000076 U	< 0.000085 U	< 0.000076 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5-20221026	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6-20221026	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250-20221027	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.000092 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249-20221027	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.000094 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000092 U	< 0.00010 U	< 0.000092 U
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204-20221027	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205-20221027	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206-20221027	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated	< 0.000096 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000094 U	< 0.00010 U	< 0.000094 U
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207-20221027	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208-20221027	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209-20221027	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210-20221027	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200-20221027	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	0.00012 J	< 0.00011 U	0.00012 J
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201-20221027	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202-20221027	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203-20221027	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204-20221027	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000098 U	< 0.00011 U	< 0.000098 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205-20221027	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253-20221028	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251-20221028	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A-20221028	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200-20221028	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated	< 0.00011 U	< 0.00021 U	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201-20221028	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202-20221028	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203-20221028	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00031 U	< 0.00041 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209-20221028	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210-20221028	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216-20221028	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220-20221028	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221-20221028	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224-20221028	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441-20221101	SSHS-IRM5A2-A6-B441	11/1/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801472371	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255-20221102	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201-20221102	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202-20221102	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203-20221102	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204-20221102	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00054 U	< 0.00073 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201-20221102	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00071 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202-20221102	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205-20221102	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206-20221102	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00030 U	< 0.00041 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207-20221102	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211-20221102	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256-20221103	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213-20221103	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211-20221103	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212-20221103	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	0.0018	0.00057 J	0.0024
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213-20221103	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226-20221103	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227-20221103	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 UT	< 0.00043 UT	< 0.0010 U	< 0.00027 UT	< 0.00039 UT
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 UT	< 0.00047 UT	< 0.0011 U	< 0.00030 UT	< 0.00043 UT
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 UT	< 0.00023 UT	< 0.00054 U	< 0.00014 UT	< 0.00021 UT
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	0.0033	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 UT	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00060 UT	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 UT	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00059 UT	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 UT	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00059 UT	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00053 UT	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00052 UT	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.0024 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 U	< 0.00043 UT	< 0.00011 U	< 0.00017 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.0028 U	< 0.00012 U	< 0.00014 U	< 0.00012 U	< 0.00020 U	< 0.00048 UT	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00013 U	< 0.00011 U	< 0.00019 U	< 0.00045 UT	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.0034 U	< 0.00016 U	< 0.00017 U	< 0.00015 U	< 0.00026 U	< 0.00060 UT	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 UT	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 UT	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00022 U	< 0.00053 UT	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00027 U	< 0.00064 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	0.0065	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00019 U	< 0.00045 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.0059 U	< 0.00027 UT	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.0041 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00071 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00031 U	< 0.00050 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated								
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00034 U	< 0.00032 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 UT	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 UT	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	0.0068	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 UT	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	0.02	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 UT	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 UT	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.0044 U	< 0.00020 U	< 0.00022 UT	< 0.00020 UT	< 0.00033 UT	< 0.00077 U	< 0.00021 UT	< 0.00030 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 UT	< 0.00078 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 UT	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.0081 U	< 0.00036 U	< 0.00040 U	< 0.00036 U	< 0.00060 U	< 0.0014 UT	< 0.00038 U	< 0.00055 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	0.0085	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 UT	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00052 UT	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.0074 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 UT	< 0.00034 U	< 0.00050 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00059 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.0039 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00068 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.0032 U	< 0.00014 UT	< 0.00016 U	< 0.00014 U	< 0.00023 UT	< 0.00055 U	< 0.00015 UT	< 0.00021 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00019 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00070 U	< 0.00019 U	< 0.00027 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.000095 U	< 0.00010 UT	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.000089 U	< 0.000098 U	< 0.00026 U	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.000088 U	< 0.000097 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00031 U	< 0.00057 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.000088 U	< 0.000096 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00031 U	< 0.00057 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.000094 U	< 0.00010 U	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.000091 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.000075 U	< 0.000083 U	< 0.00022 U	< 0.00041 U	< 0.00019 U	< 0.000094 U	< 0.00020 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.000085 U	< 0.000094 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.000079 U	< 0.000086 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000098 U	< 0.00020 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00031 U	< 0.00058 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.000093 U	< 0.00010 U	< 0.00027 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.000093 U	< 0.00010 U	< 0.00028 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00034 U	< 0.00062 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.000080 U	< 0.000088 U	< 0.00024 U	< 0.00044 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.00018 UT	< 0.00020 UT	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00037 U	< 0.00069 U	< 0.00031 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00070 U	< 0.00032 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated							
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00012 U	< 0.00013 UT	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00030 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00027 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00022 U	< 0.00024 UT	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.00014 UT	< 0.00015 UT	< 0.00040 U	< 0.00075 UT	< 0.00034 U	< 0.00017 U	< 0.00036 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.00014 U	< 0.00015 UT	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00074 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00065 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00042 U	< 0.00077 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.000091 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00068 U	< 0.0013 U	< 0.00056 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00031 U	< 0.00058 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00064 U	< 0.00030 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.000098 UT	< 0.00011 UT	< 0.00029 U	< 0.00054 UT	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00030 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.000081 U	< 0.000089 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00014 U	< 0.00037 U	< 0.00068 U	< 0.00030 U	< 0.00015 U	< 0.00032 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	0.0017 J	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.00061 U	< 0.000096 U	< 0.00018 U	< 0.00019 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00058 U	< 0.000090 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.00069 U	< 0.00011 U	< 0.00020 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.00057 U	< 0.000090 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00067 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00057 U	< 0.000089 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00067 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.00061 U	< 0.000096 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00017 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00049 U	< 0.000077 U	< 0.00014 U	< 0.00015 U	< 0.00016 U	< 0.000096 U	< 0.000088 U	< 0.00013 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.00055 U	< 0.000087 U	< 0.00016 U	< 0.00017 U	< 0.00018 U	< 0.00011 U	< 0.000099 U	< 0.00014 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.00051 U	< 0.000080 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000092 U	< 0.00013 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00069 U	< 0.00011 U	< 0.00020 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00060 U	< 0.000094 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.00069 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.00060 U	< 0.000095 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.00074 U	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.00052 U	< 0.000082 U	< 0.00015 U	< 0.00016 U	< 0.00017 U	< 0.00010 U	< 0.000093 U	< 0.00013 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.0012 UT	< 0.00019 UT	< 0.00035 U	< 0.00037 UT	< 0.00038 UT	< 0.00023 UT	< 0.00021 UT	< 0.00031 UT
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00082 U	< 0.00013 U	< 0.00024 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.00083 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated								
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00019 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.00089 U	< 0.00014 UT	< 0.00026 U	< 0.00028 UT	< 0.00028 UT	< 0.00017 UT	< 0.00016 U	< 0.00023 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00048 U	< 0.00051 U	< 0.00052 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00017 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	0.0015 J	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00047 U	< 0.00029 U	< 0.00027 U	< 0.00038 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.00078 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00063 UT	< 0.000099 UT	< 0.00019 U	< 0.00020 UT	< 0.00020 UT	< 0.00012 UT	< 0.00011 UT	< 0.00016 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00052 U	< 0.000083 U	< 0.00015 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000094 U	< 0.00014 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00080 U	< 0.00013 U	< 0.00024 U	< 0.00025 U	< 0.00026 U	< 0.00016 U	< 0.00014 U	< 0.00021 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.00010 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000099 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000099 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.000096 U	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00018 U	< 0.00012 U	< 0.00011 U	< 0.000085 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000096 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000089 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000090 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00025 U	< 0.00044 UT	< 0.00028 UT	< 0.00028 UT	< 0.00021 UT
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00026 U	< 0.00018 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated								
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00024 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 UT	< 0.00023 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 UT	< 0.00013 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00028 UT	< 0.00021 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 UT	< 0.00019 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 UT	< 0.00019 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.00023 U	0.0012 J	0.0012	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 UT	< 0.00017 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	0.00051 J
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.00017 U	< 0.00030 UT	< 0.00028 UT	< 0.00019 UT	< 0.00033 U	< 0.00021 UT	< 0.00021 UT	< 0.00015 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00051 U	< 0.00035 U	< 0.00060 U	< 0.00039 U	< 0.00038 U	< 0.00028 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00044 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00029 U	< 0.00050 U	< 0.00046 U	< 0.00032 U	< 0.00055 U	< 0.00035 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00021 UT	< 0.00020 UT	< 0.00014 UT	< 0.00023 UT	< 0.00015 UT	< 0.00015 UT	< 0.00011 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00013 U	< 0.00012 U	< 0.000091 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.00016 U	< 0.00092 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00083 U	< 0.00027 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00086 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00018 U	< 0.00078 U	< 0.00026 UT
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00094 U	< 0.00031 UT
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00078 U	< 0.00026 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00091 U	< 0.00030 UT
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 UT
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00091 U	< 0.00030 UT
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00091 U	< 0.00015 U	0.0035	< 0.00026 U	< 0.00020 U	< 0.00083 U	< 0.00027 UT
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 UT
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00088 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00080 U	< 0.00026 UT
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00013 U	< 0.00073 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00016 U	< 0.00066 U	< 0.00022 UT
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00083 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00075 U	< 0.00025 UT
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.00013 U	< 0.00076 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00069 U	< 0.00023 UT
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00094 U	< 0.00031 UT
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00090 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 UT
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00094 U	< 0.00031 UT
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00090 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00019 U	< 0.00082 U	< 0.00027 UT
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.00014 U	< 0.00078 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00071 U	< 0.00023 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00044 UT
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.00031 U	< 0.0018 UT	< 0.00030 UT	< 0.0045 UT	< 0.00052 U	< 0.00038 U	< 0.0016 UT	< 0.00053 UT
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0031 U	< 0.00036 U	< 0.00026 U	< 0.0011 U	< 0.00036 UT
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 UT
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 UT
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated								
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00028 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.00023 U	< 0.0013 UT	< 0.00022 UT	< 0.0033 UT	< 0.00039 U	< 0.00028 U	< 0.0012 UT	< 0.00040 U
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0061 U	< 0.00070 U	< 0.00052 U	< 0.0022 U	< 0.00072 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.00016 U	< 0.00088 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00080 U	< 0.00026 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00017 U	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00092 U	< 0.00030 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00017 U	< 0.00094 U	< 0.00016 UT	< 0.0024 U	< 0.00028 UT	< 0.00020 U	< 0.00086 UT	< 0.00028 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00014 U	< 0.00078 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00071 U	< 0.00023 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 UT
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 UT
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	< 0.00013 U	< 0.000097 U	< 0.00019 U	< 0.00012 UT
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000091 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	0.00014 J	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	0.00012 J	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	0.00015 J	< 0.000096 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000093 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00012 U	< 0.000091 U	< 0.00013 U	< 0.00010 U	< 0.000077 U	< 0.00015 U	< 0.000099 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000087 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.00012 U	< 0.000095 U	< 0.00014 U	< 0.00010 U	< 0.000081 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000095 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000096 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.00013 U	< 0.000097 U	< 0.00014 U	< 0.00011 U	< 0.000082 U	< 0.00016 U	< 0.00011 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.00029 UT	< 0.00022 UT	< 0.00032 U	< 0.00024 UT	< 0.00019 U	< 0.00037 UT	< 0.00024 U
Northern Athletic Field	A1N-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00020 U	< 0.00015 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	0.00041 J	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated							
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.74	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	0.00050 J	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	0.00016 J	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00033 J	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00036 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.00022 UT	< 0.00017 U	< 0.00024 UT	< 0.00018 UT	< 0.00014 UT	< 0.00028 UT	< 0.00018 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00025 J	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00026 U	< 0.00051 U	< 0.00033 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 UT	< 0.00019 U	< 0.00014 UT	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	0.00041 J	< 0.00022 U	< 0.00044 U	< 0.00028 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	0.00013 J	< 0.000093 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00040 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230215	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00015 UT	< 0.00012 U	< 0.00017 UT	< 0.00013 UT	< 0.00010 U	< 0.00020 UT	< 0.00013 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	0.00022 J	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00013 U	< 0.000098 U	< 0.00014 U	< 0.00011 U	< 0.000083 U	< 0.00016 U	< 0.00011 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228-20221103	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230-20221103	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231-20221103	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated	< 0.000095 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000093 U	< 0.00010 U	< 0.000093 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258-20221107	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.000089 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000087 U	< 0.000098 U	< 0.000087 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259-20221107	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214-20221107	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215-20221107	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated	< 0.000089 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000087 U	< 0.000097 U	< 0.000087 U
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216-20221107	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235-20221107	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000086 U	< 0.000096 U	< 0.000086 U
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236-20221107	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237-20221107	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated	< 0.000094 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000092 U	< 0.00010 U	< 0.000092 U
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238-20221107	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239-20221107	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated	< 0.000092 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241-20221107	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated	< 0.000076 U	< 0.00014 U	< 0.00017 U	< 0.00023 U	< 0.000074 U	< 0.000083 U	< 0.000074 U
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242-20221107	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated	< 0.000086 U	< 0.00015 U	< 0.00020 U	< 0.00026 U	< 0.000084 U	< 0.000094 U	< 0.000084 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243-20221107	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated	< 0.000079 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000077 U	< 0.000086 U	< 0.000077 U
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244-20221107	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00033 U	< 0.00010 U	< 0.00012 U	< 0.00010 U
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245-20221107	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated	< 0.000093 U	< 0.00017 U	< 0.00021 U	< 0.00029 U	< 0.000091 U	< 0.00010 U	< 0.000091 U
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247-20221107	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248-20221107	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated	< 0.000094 U	< 0.00017 U	< 0.00021 U	< 0.00029 U	< 0.000092 U	< 0.00010 U	< 0.000092 U
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249-20221107	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated	< 0.00011 U	< 0.00021 U	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250-20221107	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251-20221107	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated	< 0.000081 U	< 0.00015 U	< 0.00018 U	< 0.00025 U	< 0.000079 U	< 0.000088 U	< 0.000079 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260-20221108	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1-20221108	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated	< 0.00018 UT	< 0.00033 U	< 0.00042 U	< 0.00057 UT	< 0.00018 UT	< 0.00020 UT	< 0.00018 UT
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3-20221108	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00039 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1-20221108	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2-20221108	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10-M-20221117	SSHS-IRM5A2-DW10-M	11/17/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801481251	Not Excavated							
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261-20221129	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200-20221129	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201-20221129	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204-20221129	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205-20221129	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207-20221129	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208-20221129	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210-20221129	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403-20221201	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211-20221202	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212-20221202	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00026 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214-20221202	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215-20221202	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216-20221202	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated	< 0.00017 U	0.00033 J	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218-20221205	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224-20221205	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated	< 0.00018 U	0.00083 J	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225-20221205	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000099 U	< 0.00011 U	< 0.000099 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226-20221205	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265-20221205	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1-20221208	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated	< 0.00015 U	0.00031 J	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228-20221209	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221210	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221210	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221210	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221210	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221210	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1-20221212	SSHS-IRM5A2-A6N-B213-S1	12/12/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00050 U	< 0.00068 U	0.0018	0.00068 J	0.0025
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2-20221212	SSHS-IRM5A2-A6N-B213-S2	12/12/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492231	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245-20221212	SSHS-IRM5A2-A6N-B245	12/12/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492231	Not Excavated	< 0.00014 UT	< 0.00025 UT	< 0.00031 U	< 0.00042 U	< 0.00013 UT	< 0.00015 UT	< 0.00013 UT
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246-20221212	SSHS-IRM5A2-A6N-B246	12/12/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492231	Not Excavated	< 0.00014 U	0.00040 J	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247-20221212	SSHS-IRM5A2-A6N-B247	12/12/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492231	Not Excavated	< 0.00016 U	0.00031 J	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274-20221214	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00025 U	0.00051 J	< 0.00057 U	< 0.00077 U	< 0.00025 U	< 0.00027 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27-20221214	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	0.00028 J	< 0.00015 U	0.00028 J
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A-20221214	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated	< 0.00022 U	0.00069 J	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A-20221214	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated	< 0.000092 U	0.00025 J	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A-20221214	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated	< 0.00023 U	0.00054 J	< 0.00053 U	< 0.00071 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276-20230213	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000099 U	< 0.00011 U	< 0.000099 U
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252-20230215	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00012 U	< 0.00010 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253-20230215	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254-20230215	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255-20230215	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.000098 UT	< 0.00018 UT	< 0.00022 UT	< 0.00030 UT	< 0.000096 UT	< 0.00011 UT	< 0.000096 UT
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256-20230215	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257-20230215	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258-20230215	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000080 U	< 0.000089 U	< 0.000080 U
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259-20230215	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00014 U	< 0.00012 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00058 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.0039 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00069 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.0079 U	< 0.00036 U	< 0.00039 U	< 0.00035 U	< 0.00059 U	< 0.0014 U	< 0.00037 U	< 0.00053 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.0030 U	< 0.00013 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00059 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00047 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00058 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.0083 U	< 0.00038 UT	< 0.00041 UT	< 0.00037 UT	< 0.00062 UT	< 0.0015 UT	< 0.00039 UT	< 0.00056 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 UT	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 UT	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.0024 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 UT	< 0.00043 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 UT	< 0.00056 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 UT	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 UT	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 UT	< 0.0012 U	< 0.00031 U	< 0.00046 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	0.028	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 UT	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00031 U	< 0.00057 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.00024 U	< 0.00027 U	< 0.00072 U	< 0.0013 U	< 0.00060 U	< 0.00030 U	< 0.00063 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.000092 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00023 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00030 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00026 UT	< 0.00028 UT	< 0.00076 UT	< 0.0014 UT	< 0.00063 U	< 0.00032 UT	< 0.00067 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.000082 U	< 0.000090 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.000078 U	< 0.000085 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000097 U	< 0.00020 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.000078 U	< 0.000086 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000098 U	< 0.00020 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.000076 U	< 0.000083 U	< 0.00022 U	< 0.00041 U	< 0.00019 U	< 0.000094 U	< 0.00020 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.000099 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.00067 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.00079 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00047 U	< 0.00050 U	< 0.00050 U	< 0.00031 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.00060 U	< 0.000094 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.00067 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.0017 UT	< 0.00026 UT	< 0.00049 U	< 0.00053 UT	< 0.00053 UT	< 0.00033 UT	< 0.00030 UT	< 0.00043 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00053 U	< 0.000083 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000095 U	< 0.00014 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.00074 U	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.00050 U	< 0.000079 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.000099 U	< 0.000090 U	< 0.00013 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.00051 U	< 0.000080 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000091 U	< 0.00013 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.00049 U	< 0.000077 U	< 0.00014 U	< 0.00015 U	< 0.00016 U	< 0.000096 U	< 0.000088 U	< 0.00013 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.00064 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.00031 U	< 0.00053 U	< 0.00049 U	< 0.00034 U	< 0.00058 U	< 0.00038 U	< 0.00037 U	< 0.00027 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00033 U	< 0.00024 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00012 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00033 UT	< 0.00056 UT	< 0.00052 UT	< 0.00036 UT	< 0.00062 UT	< 0.00040 UT	< 0.00039 UT	< 0.00029 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.000099 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000087 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000088 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.000096 U	< 0.00016 U	< 0.00015 U	< 0.00011 U	< 0.00018 U	< 0.00012 U	< 0.00011 U	< 0.000085 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.00013 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 UT	< 0.0019 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00091 U	< 0.00030 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0029 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.00041 U	< 0.0024 U	< 0.00039 U	< 0.0059 U	< 0.00069 U	< 0.00051 U	< 0.0021 U	< 0.00071 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.00016 U	< 0.00089 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00091 U	< 0.00030 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00099 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00044 UT	< 0.0025 UT	< 0.00042 UT	< 0.0063 U	< 0.00073 UT	< 0.00054 UT	< 0.0023 UT	< 0.00075 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00014 U	< 0.00079 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.00013 U	< 0.00075 U	< 0.00012 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00068 U	< 0.00022 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.00013 U	< 0.00076 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00069 U	< 0.00023 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.00013 U	< 0.00073 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00016 U	< 0.00066 U	< 0.00022 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.00017 U	< 0.00096 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00087 U	< 0.00029 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	0.00043 J	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00042 U	< 0.00032 U	< 0.00025 U	< 0.00049 U	< 0.00032 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000094 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00018 U	< 0.00014 U	< 0.00010 U	< 0.00021 U	< 0.00013 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00036 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00041 UT	< 0.00031 UT	< 0.00044 UT	< 0.00034 UT	< 0.00026 UT	< 0.00052 UT	< 0.00034 UT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00013 U	< 0.000099 U	< 0.00014 U	< 0.00011 U	< 0.000084 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.00012 U	< 0.000094 U	< 0.00013 U	< 0.00010 U	< 0.000079 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.00012 U	< 0.000095 U	< 0.00014 U	< 0.00010 U	< 0.000080 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.00012 U	< 0.000091 U	< 0.00013 U	< 0.00010 U	< 0.000077 U	< 0.00015 U	< 0.00010 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0016 UT	< 0.0016 UT	< 0.0021 UT	< 0.0015 UT	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260-20230215	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261-20230215	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277-20230221	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278-20230221	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	0.00045 J	0.00023 J	0.00068 J
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256-20230221	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 0.00025 U	< 0.00044 U	< 0.00056 U	< 0.00075 U	< 0.00024 U	< 0.00027 U	< 0.00024 U
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257-20230221	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258-20230221	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259-20230221	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 0.000093 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260-20230221	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261-20230221	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262-20230221	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263-20230221	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267-20230221	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268-20230221	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269-20230221	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270-20230221	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271-20230221	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272-20230221	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	0.00043 J	0.00018 J	0.00062 J
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273-20230221	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.00026 UT	< 0.00047 UT	< 0.00059 UT	< 0.00080 U	0.00071 JT	< 0.00028 UT	0.00087 JT
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274-20230221	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	0.00021 J	< 0.000090 U	0.00026 J
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47-20230221	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00026 U	< 0.00035 U	0.00040 J	< 0.00013 U	0.00051 J
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279-20230223	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.000078 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	0.000076 J	< 0.000085 U	0.000076 J
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262-20230223	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 0.000079 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000077 U	< 0.000086 U	< 0.000077 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263-20230223	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 0.000076 U	< 0.00014 U	< 0.00017 U	< 0.00023 U	< 0.000074 U	< 0.000083 U	< 0.000074 U
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264-20230223	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 0.000099 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	0.00031 J	< 0.00011 U	0.00031 J
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265-20230223	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	0.00015 J	< 0.00016 U	0.00015 J
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266-20230223	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	0.00020 J	< 0.00020 U	0.00020 J
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267-20230223	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268-20230223	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269-20230223	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	0.00023 J	< 0.00023 U	0.00023 J
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270-20230223	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	0.00019 J	< 0.00017 U	0.00019 J
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280-20230224	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281-20230224	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271-20230224	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272-20230224	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273-20230224	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274-20230224	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275-20230224	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276-20230224	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277-20230224	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278-20230224	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279-20230224	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280-20230224	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230227	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230227	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230227	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230227	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230227	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230227	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230227	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230227	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230227	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230227	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230227	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230227	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230227	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230227	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230227	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230227	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated							
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282-20230228	SSHS-IRM5A2-DUP282	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283-20230228	SSHS-IRM5A2-DUP283	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281-20230228	SSHS-IRM5A2-A1N-B281	2/28/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282-20230228	SSHS-IRM5A2-A1N-B282	2/28/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284-20230228	SSHS-IRM5A2-A1N-B284	2/28/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286-20230228	SSHS-IRM5A2-A1N-B286	2/28/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801527601	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287-20230228	SSHS-IRM5A2-A1N-B287	2/28/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801527601	Not Excavated	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288-20230228	SSHS-IRM5A2-A1N-B288	2/28/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801527601	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A-20230228	SSHS-IRM5A2-A6-B269A	2/28/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801527601	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A-20230228	SSHS-IRM5A2-A6-B270A	2/28/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A-20230228	SSHS-IRM5A2-A6-B271A	2/28/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801527601	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A-20230228	SSHS-IRM5A2-A6-B272A	2/28/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A-20230228	SSHS-IRM5A2-A6-B273A	2/28/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A-20230228	SSHS-IRM5A2-A6-B274A	2/28/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801527601	Not Excavated	< 0.0010 UT	< 0.0016 U	< 0.0043 U	< 0.0037 UT	< 0.0018 U	< 0.0021 UT	< 0.0075 UT
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275-20230228	SSHS-IRM5A2-A6-B275	2/28/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801527601	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0026 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 UT	< 0.0049 U	< 0.0025 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0045 U	< 0.0023 UT
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 UT
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UT	< 0.0040 U	< 0.0020 UT
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0039 U	< 0.0031 U	< 0.0033 U	< 0.0030 UT	< 0.0053 U	< 0.0027 UT
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 UT	< 0.0048 U	< 0.0025 UT
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 UT	< 0.0049 U	< 0.0025 UT
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0042 U	< 0.0021 UT
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 UT	< 0.0048 U	< 0.0024 UT
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 UT	< 0.0046 U	< 0.0023 UT
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 UT	< 0.0045 U	< 0.0023 UT
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 UT	< 0.0043 U	< 0.0022 UT
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0043 UT	< 0.0016 UT	< 0.0033 UT	< 0.0026 UT	< 0.0028 UT	< 0.0025 UT	< 0.0044 UT	< 0.0022 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 UT	< 0.0022 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 UT	< 0.0021 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 UT	< 0.0021 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0032 U	< 0.0025 UT	< 0.0027 U	< 0.0025 U	< 0.0043 UT	< 0.0022 UT
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 UT	< 0.0043 UT	< 0.0022 UT
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	0.0059	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	0.0055	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	0.0047 J	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0039 UT	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0039 UT	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0040 UT	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.0038 UT	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0040 UT	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	0.15	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0037 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 UT	< 0.0028 U	< 0.0037 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 UT	< 0.0024 U	< 0.0032 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0038 U	< 0.0044 U	< 0.0026 UT	< 0.0031 U	< 0.0043 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 UT	< 0.0029 U	< 0.0039 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0041 U	< 0.0024 UT	< 0.0029 U	< 0.0040 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 UT	< 0.0028 U	< 0.0038 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 UT	< 0.0028 U	< 0.0037 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 UT	< 0.0027 U	< 0.0037 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0014 UT	< 0.0027 UT	< 0.0032 UT	< 0.0037 UT	< 0.0022 UT	< 0.0026 UT	< 0.0036 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UT	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0036 U	< 0.0021 UT	< 0.0026 UT	< 0.0035 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.0014 U	0.0053	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.0014 U	0.0051 J	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.0016 U	0.0052 J	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0031 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 UT	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UT	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0018 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 UT
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 UT
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 UT
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0033 UT	< 0.0022 U	< 0.0041 U	< 0.0020 U	< 0.0021 U	< 0.0019 UT
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 UT
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0031 UT	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 UT
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 UT
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 UT	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 UT
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 UT
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 UT
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 UT
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0050 UT	< 0.0015 UT	< 0.0027 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 UT	< 0.0016 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0048 UT	< 0.0015 U	< 0.0026 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 UT	< 0.0015 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0047 UT	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 UT	< 0.0015 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0046 UT	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 UT	< 0.0015 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0049 UT	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 UT	< 0.0016 UT
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0049 UT	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0057 UT	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.0055 UT	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0052 UT	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0030 U	< 0.0054 U	< 0.0020 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0030 U	< 0.0024 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0025 UT	< 0.0045 UT	< 0.0017 UT	< 0.0019 UT	< 0.0015 UT	< 0.0024 UT	< 0.0025 UT	< 0.0020 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0024 U	< 0.0043 UT	< 0.0016 U	< 0.0019 UT	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0023 U	< 0.0042 UT	< 0.0016 U	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0023 U	< 0.0042 UT	< 0.0016 U	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0024 U	< 0.0044 UT	< 0.0016 U	< 0.0019 UT	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.0024 UT	< 0.0044 UT	< 0.0016 U	< 0.0019 UT	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.0027 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 UT	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 UT	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 UT	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 UT	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 UT	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0026 U	< 0.0021 U	< 0.0034 U	< 0.0097 UT	< 0.0032 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 UT	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0090 UT	< 0.0030 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 UT	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 UT	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 UT	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 UT	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 UT	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0022 UT	< 0.0017 UT	< 0.0029 UT	< 0.0081 UT	< 0.0027 UT	< 0.0028 UT	< 0.0020 UT	< 0.0016 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0021 UT	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 UT
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 UT
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0022 UT	< 0.0017 UT	< 0.0028 U	< 0.0079 UT	< 0.0026 U	< 0.0027 UT	< 0.0020 U	< 0.0016 UT
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.0021 UT	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 UT	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															1.3	0.7			0.68
Restricted - Residential															19	100			100
Protection of Groundwater															1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0018 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0017 UT	< 0.0017 UT	< 0.0022 UT	< 0.0016 UT	< 0.0030 U	< 0.0028 U	< 0.0018 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 UT
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801596051	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801596051	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801596051	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801596051	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801596051	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801596051	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801596051	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801596061	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801596061	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801596061	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801596061	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801596061	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276-20230228	SSHS-IRM5A2-A6-B276	2/28/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801527601	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248-20230425	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249-20230425	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250-20230425	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251-20230425	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252-20230425	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 UT	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299-20230505	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 UT	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1-20230505	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 UT	< 0.0042 UT	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2-20230505	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 UT	< 0.0036 UT	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3-20230505	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 0.0013 U	< 0.0021 U	< 0.0055 UT	< 0.0047 UT	< 0.0023 U	< 0.0026 U	< 0.0095 U
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4-20230505	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 UT	< 0.0044 UT	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5-20230505	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 UT	< 0.0044 UT	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1-20230505	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2-20230505	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 UT	< 0.0043 UT	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1-20230505	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 UT	< 0.0042 UT	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2-20230505	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 UT	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3-20230505	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4-20230505	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1-20230509	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 UT	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1-20230509	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 0.0011 UT	< 0.0017 UT	< 0.0046 UT	< 0.0040 UT	< 0.0020 UT	< 0.0022 UT	< 0.0079 UT
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302-20230510	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1-20230510	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2-20230510	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3-20230510	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4-20230510	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1-20230530	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3-20230710	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4-20230710	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2-20230710	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10-20230711	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13-20230711	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15-20230711	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17-20230711	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19-20230711	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21-20230711	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22-20230711	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24-20230711	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26-20230711	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28-20230711	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29-20230711	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31-20230711	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1-20230714	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3-20230714	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5-20230714	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3-20230714	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35-20230717	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36-20230717	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38-20230717	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40-20230717	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41-20230717	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44-20230717	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46-20230717	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53-20230717	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54-20230717	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16-20230717	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64-20230718	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65-20230718	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66-20230718	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67-20230718	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20-20230718	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68-20230718	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73-20230718	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74-20230718	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A-20230720	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77-20230720	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24-20230720	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80-20230720	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81-20230720	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82-20230720	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83-20230720	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27-20230720	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84-20230720	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85-20230720	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86-20230720	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	0.033	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	0.0064 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	0.011 J	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.0039 J	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	0.0052 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	0.0064 J	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615841	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.0047 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.0053 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	0.0056 J	< 0.0020 U	< 0.0042 U	< 0.0032 U	< 0.0035 U	< 0.0032 U	< 0.0056 U	< 0.0028 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	0.063	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 UT	< 0.0021 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	0.014 J	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0044 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0037 U	< 0.0043 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 UT
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0037 U	< 0.0022 UT	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 UT	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 UT	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 UT	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0018 U	< 0.0035 U	< 0.0041 U	< 0.0047 U	< 0.0028 U	< 0.0033 U	< 0.0045 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0019 U	0.0036 J	< 0.0032 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0019 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	0.0073	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	0.0060	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 UT	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	0.011	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 UT	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0063 U	< 0.0019 U	< 0.0035 U	< 0.0023 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.0020 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0029 U	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0023 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0026 U	< 0.0046 UT	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.0022 U	< 0.0040 UT	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0025 U	< 0.0046 UT	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0031 U	< 0.0057 UT	< 0.0021 U	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0031 U	< 0.0026 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0023 U	< 0.0041 UT	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0023 U	< 0.0042 UT	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0026 U	< 0.0046 UT	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0024 U	< 0.0044 UT	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0023 UT	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0096 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.0022 U	< 0.0018 UT	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 UT	< 0.0016 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0024 U	< 0.0018 UT	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 UT	< 0.0017 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0028 UT	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0034 U	< 0.0035 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0021 UT	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	0.014 J	0.0050	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0024 UT	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0022 UT	< 0.0017 UT	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0020 UT	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 UT	< 0.0025 UT	< 0.0017 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0038 U	< 0.0035 U	< 0.0023 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28-20230720	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29-20230720	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30-20230720	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31-20230720	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A-20230725	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90-20230725	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93-20230725	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94-20230725	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1-20230814	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95-20230818	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96-20230818	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 0.0012 U	0.0019 J	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313-20230824	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310-20230824	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311-20230824	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12-20230824	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11-20230824	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15-20230824	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2-20230824	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3-20230824	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4-20230824	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5-20230824	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6-20230824	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7-20230824	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8-20230824	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9-20230824	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16-20230824	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17-20230824	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18-20230824	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19-20230824	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20-20230824	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21-20230824	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10-20230824	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11-20230824	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12-20230824	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 UT	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13-20230824	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 UT	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26-20230824	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28-20230824	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14-20230824	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15-20230824	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16-20230824	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17-20230824	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315-20230829	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A-20230829	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31-20230829	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34-20230829	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42-20230829	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0058 U	< 0.0050 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18-20230829	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19-20230829	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20-20230829	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21-20230829	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22-20230829	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 UT	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46-20230829	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47-20230829	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 UT	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23-20230829	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24-20230829	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 UT	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25-20230829	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0040 U	< 0.0035 UT	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26-20230829	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27-20230829	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 UT	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50-20230829	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51-20230906	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66-20230906	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36-20230906	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A-20230922	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1-20230922	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2-20230922	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1-20230922	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4-20230922	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1-20230922	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2-20230922	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A-20230925	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5-20230925	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6-20230925	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8-20230925	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3-20230925	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 UT	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 UT	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	0.0049 J	0.0029 J	< 0.0026 UT	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UT	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 UT	< 0.0051 U	< 0.0026 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 UT	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	0.012 J	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0029 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0015 U	0.0063	< 0.0034 UT	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 UT	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 UT	< 0.0043 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0014 U	0.0026 J	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 UT	< 0.0041 U	< 0.0024 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0043 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 UT	< 0.0040 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated							
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	0.0048 J	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0058 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 UT	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 UT	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0024 UT	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 UT	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 UT	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 UT	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 UT	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 UT	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 UT	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 UT	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0029 U	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0027 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0027 UT	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 UT	< 0.0016 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 UT	< 0.0016 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 UT	< 0.0015 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 UT	< 0.0015 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0019 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated							
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4-20230925	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321-20231025	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2-20231025	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4-20231025	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1-20231025	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2-20231025	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322-20231026	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6-20231026	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3-20231026	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323-20231027	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8-20231027	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10-20231027	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11-20231027	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4-20231027	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5-20231027	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324-20231101	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14-20231101	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16-20231101	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17-20231101	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18-20231101	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6-20231101	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7-20231101	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 UT	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9-20231101	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 UT	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10-20231101	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325-20231102	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20-20231102	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 UT	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21-20231102	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated	< 0.00098 U	< 0.0015 U	< 0.0041 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22-20231102	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 UT	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11-20231102	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12-20231102	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 UT	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327-20231106	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326-20231106	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25-20231106	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26-20231106	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28-20231106	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 UT	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13-20231106	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14-20231106	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15-20231106	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 UT	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0074 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328-20231107	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31-20231107	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34-20231107	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 UT	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16-20231107	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1-20231116	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3-20231116	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5-20231116	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2-20231116	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10-20231130	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14-20231130	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18-20231130	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23-20231201	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1-20231208	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 UT	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5-20231208	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334-20231211	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10-20231211	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12-20231211	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2-20231211	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3-20231211	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4-20231211	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335-20231212	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14-20231212	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16-20231212	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5-20231212	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336-20231213	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337-20231213	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18-20231213	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20-20231213	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22-20231213	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24-20231213	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25-20231213	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6-20231213	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7-20231213	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8-20231213	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339-20240112	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated							
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2-20240112	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated							
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated							
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated							
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated							
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0065	< 0.00087	< 0.00089	< 0.00073	< 0.00057	< 0.00096	< 0.00066	< 0.00058
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0052	< 0.0007	< 0.00071	< 0.00058	< 0.00046	< 0.00076	< 0.00053	< 0.00046
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.005	< 0.00068	< 0.00069	< 0.00056	< 0.00044	< 0.00074	< 0.00051	< 0.00045
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.0047	< 0.00064	< 0.00065	< 0.00053	< 0.00042	< 0.0007	< 0.00049	< 0.00042
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.0052	< 0.00071	< 0.00072	< 0.00059	< 0.00046	< 0.00078	< 0.00054	< 0.00047
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.022	< 0.0054		< 0.0054	< 0.0054	< 0.0054	< 0.011	< 0.0054
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-B3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated						
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated						
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated						
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00098	< 0.00092	< 0.002	< 0.00076	< 0.0011	< 0.00048	< 0.00097
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00078	< 0.00073	< 0.0016	< 0.00061	< 0.00088	< 0.00038	< 0.00077
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.00076	< 0.00071	< 0.0016	< 0.00059	< 0.00086	< 0.00037	< 0.00075
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.00072	< 0.00067	< 0.0015	< 0.00055	< 0.00081	< 0.00035	< 0.00071
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.0008	< 0.00074	< 0.0016	< 0.00061	< 0.00089	< 0.00039	< 0.00079
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054		
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated						
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated						
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated						
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated						
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated						
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated						
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated						
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated						
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated						
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated						
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated						
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated						
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated						

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated							
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated							
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated							
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated							
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00087	< 0.0011	< 0.00086	< 0.001	< 0.00085	< 0.00083	< 0.00075	< 0.00079
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0007	< 0.00089	< 0.00069	< 0.00083	< 0.00068	< 0.00066	< 0.0006	< 0.00063
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.00068	< 0.00087	< 0.00067	< 0.0008	< 0.00066	< 0.00064	< 0.00058	< 0.00062
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.00064	< 0.00082	< 0.00063	< 0.00076	< 0.00062	< 0.0006	< 0.00055	< 0.00058
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.00071	< 0.00091	< 0.0007	< 0.00084	< 0.00069	< 0.00067	< 0.0006	< 0.00064
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.0054			< 0.36	< 0.36	< 0.36	< 0.0054	< 0.0054
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated								
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated								
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated								
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated								
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated								
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated								
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated								
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0011		< 0.00091	< 0.00077	< 0.0007	< 0.00088	< 0.00077	< 0.00083
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00088		< 0.00073	< 0.00062	< 0.00056	< 0.0007	< 0.00062	< 0.00066
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.00085		< 0.00071	< 0.0006	< 0.00055	< 0.00068	< 0.0006	< 0.00065
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.0008		< 0.00067	< 0.00057	< 0.00052	< 0.00064	< 0.00057	< 0.00061
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.00089		< 0.00074	< 0.00063	< 0.00057	< 0.00071	< 0.00063	< 0.00067
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.0054		< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054	< 0.0054
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-B3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated								

DRAFT

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated								
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated								
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated								
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated								
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated								
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated								
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated								
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated								
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0014	< 0.00089	< 0.00088	< 0.0012	< 0.00094	< 0.0011	< 0.00085	< 0.00097
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0011	< 0.00071	< 0.0007	< 0.00093	< 0.00075	< 0.00091	< 0.00068	< 0.00077
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.0011	< 0.00069	< 0.00068	< 0.00091	< 0.00073	< 0.00089	< 0.00066	< 0.00075
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.001	< 0.00065	< 0.00064	< 0.00085	< 0.00069	< 0.00084	< 0.00062	< 0.00071
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.0011	< 0.00072	< 0.00071	< 0.00095	< 0.00076	< 0.00093	< 0.00068	< 0.00078
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.0054	< 0.011				< 0.011	< 0.011	
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated						
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated						
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated						
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00091	< 0.00093	< 0.00088	< 0.00095	< 0.0011	< 0.0011	< 0.00063
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00073	< 0.00074	< 0.0007	< 0.00075	< 0.00087	< 0.00091	< 0.0005
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.00071	< 0.00072	< 0.00068	< 0.00073	< 0.00085	< 0.00089	< 0.00049
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.00067	< 0.00068	< 0.00065	< 0.00069	< 0.0008	< 0.00084	< 0.00046
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.00074	< 0.00075	< 0.00071	< 0.00077	< 0.00089	< 0.00093	< 0.00051
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.0054	< 0.0054	< 0.0054	< 0.0054		< 0.36	< 0.0054
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-B3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1-20240112	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2-20240112	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3-20240112	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated							
Northern Athletic Field	A8PH7-SCV15B	SSHS-IRM5A2-A8PH7-SCV15B-20240401	SSHS-IRM5A2-A8PH7-SCV15B	4/1/2024	-	857.94	-	855.57	2 - 4 ft	2.37 ft	1801716851	Not Excavated							
Northern Athletic Field	A8PH7-SCV15-BOT	SSHS-IRM5A2-A8PH7-SCV15-BOT-20240401	SSHS-IRM5A2-A8PH7-SCV15-BOT	4/1/2024	-	857.46	-	854.79	2 - 4 ft	2.67 ft	1801716851	Not Excavated							
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1-20240410	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2-20240410	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT-20240410	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated							
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E-20240418	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated							
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2-20240418	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated							
Northern Athletic Field	SSHS-B75	081514 01:15 DUP-14	081514 01:15 DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.0011	< 0.00085	< 0.0012	< 0.00061		< 0.001	
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated	< 0.00086	< 0.00068	< 0.00095	< 0.00049		< 0.00081	
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated	< 0.00084	< 0.00066	< 0.00092	< 0.00047		< 0.00078	
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated	< 0.00079	< 0.00062	< 0.00087	< 0.00045		< 0.00074	
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated	< 0.00087	< 0.00069	< 0.00096	< 0.00049		< 0.00082	
Northern Athletic Field	SSHS-B47	13 SEP 00B47 3-5	B47-3-5	9/13/2000	856.71	856.92	0.21	-	3 - 5 ft	3.21-5.21 ft	NA	Not Excavated	< 0.0054	< 0.0054	< 0.0054	< 0.0054		< 0.0054	
Northern Athletic Field	SSHS-B586	SSHS-B586-SUB-4-6	SSHS-B586-SUB-4-6	2/10/2017	855.97	856.56	0.59	-	4 - 6 ft	4.59-6.59 ft	180-63389-2	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-4-6	SSHS-B2030-SUB-4-6	7/27/2018	856.20	856.42	0.22	-	4 - 6 ft	4.22-6.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-4-6	SSHS-B3008-SUB-4-6	8/26/2019	852.37	854.67	2.30	-	4 - 6 ft	6.3-8.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-4-6	SSHS-B3034-SUB-4-6	8/26/2019	855.10	856.53	1.43	-	4 - 6 ft	5.43-7.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-4-6	SSHS-B3049-SUB-4-6	8/26/2019	856.17	857.50	1.33	-	4 - 6 ft	5.33-7.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-4-6	SSHS-B3050-SUB-4-6	8/26/2019	855.60	856.84	1.24	-	4 - 6 ft	5.24-7.24 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-4-6	SSHS-B3065-SUB-4-6	8/26/2019	856.77	857.30	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-4-6	SSHS-B3078-SUB-4-6	8/26/2019	856.70	857.12	0.42	-	4 - 6 ft	4.42-6.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-4-6	SSHS-B3098-SUB-4-6	8/26/2019	855.97	857.05	1.08	-	4 - 6 ft	5.08-7.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-4-6	SSHS-B3099-SUB-4-6	8/26/2019	856.40	856.53	0.13	-	4 - 6 ft	4.13-6.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-4-6	SSHS-B3006-SUB-4-6	8/27/2019	852.36	852.39	0.03	-	4 - 6 ft	4.03-6.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-4-6	SSHS-B3007-SUB-4-6	8/27/2019	852.58	854.74	2.16	-	4 - 6 ft	6.16-8.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-4-6	SSHS-B3018-SUB-4-6	8/27/2019	853.82	854.59	0.77	-	4 - 6 ft	4.77-6.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-4-6	SSHS-B3031-SUB-4-6	8/27/2019	855.08	855.61	0.53	-	4 - 6 ft	4.53-6.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-4-6	SSHS-B3032-SUB-4-6	8/27/2019	855.25	856.15	0.90	-	4 - 6 ft	4.9-6.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-4-6	SSHS-B3033-SUB-4-6	8/27/2019	855.17	856.58	1.41	-	4 - 6 ft	5.41-7.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-4-6	SSHS-B3062-SUB-4-6	8/27/2019	856.91	856.86	-0.05	-	4 - 6 ft	3.95-5.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-4-6	SSHS-B3074-SUB-4-6	8/27/2019	857.18	856.02	-1.16	-	4 - 6 ft	2.84-4.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-4-6	SSHS-B3096-SUB-4-6	8/27/2019	855.86	856.29	0.43	-	4 - 6 ft	4.43-6.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-4-6	SSHS-B3030-SUB-4-6	8/28/2019	855.22	855.02	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-4-6	SSHS-B3043-SUB-4-6	8/28/2019	855.78	856.62	0.84	-	4 - 6 ft	4.84-6.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-4-6	SSHS-B3044-SUB-4-6	8/28/2019	856.00	854.20	-1.80	-	4 - 6 ft	2.2-4.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-4-6	SSHS-B3045-SUB-4-6	8/28/2019	856.03	855.07	-0.96	-	4 - 6 ft	3.04-5.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-4-6	SSHS-B3057-SUB-4-6	8/28/2019	856.09	857.58	1.49	-	4 - 6 ft	5.49-7.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-4-6	SSHS-B3058-SUB-4-6	8/28/2019	856.47	856.55	0.08	-	4 - 6 ft	4.08-6.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-4-6	SSHS-B3059-SUB-4-6	8/28/2019	856.71	854.42	-2.29	-	4 - 6 ft	1.71-3.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-4-6	SSHS-S3060-SUB-4-6	8/28/2019	856.96	855.38	-1.58	-	4 - 6 ft	2.42-4.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-4-6	SSHS-B3070-SUB-4-6	8/28/2019	856.51	857.05	0.54	-	4 - 6 ft	4.54-6.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-4-6	SSHS-B3071-SUB-4-6	8/28/2019	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-4-6	SSHS-B3072-SUB-4-6	8/28/2019	856.89	856.00	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-4-6	SSHS-B3004-SUB-4-6	8/29/2019	852.25	853.25	1.00	-	4 - 6 ft	5-7 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-4-6	SSHS-B3005-SUB-4-6	8/29/2019	852.31	852.62	0.31	-	4 - 6 ft	4.31-6.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-4-6	SSHS-B3040-SUB-4-6	8/29/2019	855.10	858.65	3.55	-	4 - 6 ft	7.55-9.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-4-6	SSHS-B3054-SUB-4-6	8/29/2019	856.01	856.77	0.76	-	4 - 6 ft	4.76-6.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-4-6	SSHS-B3055-SUB-4-6	8/29/2019	856.20	858.70	2.50	-	4 - 6 ft	6.5-8.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-4-6	SSHS-B3056-SUB-4-6	8/29/2019	855.88	858.82	2.94	-	4 - 6 ft	6.94-8.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-4-6	SSHS-B3079-SUB-4-6	8/29/2019	856.36	857.37	1.01	-	4 - 6 ft	5.01-7.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-4-6	SSHS-B3083-SUB-4-6	8/29/2019	857.13	857.39	0.26	-	4 - 6 ft	4.26-6.26 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-4-6	SSHS-B3084-SUB-4-6	8/29/2019	856.55	857.05	0.50	-	4 - 6 ft	4.5-6.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-4-6	SSHS-B3182-SUB-4-6	8/29/2019	857.45	857.88	0.43	-	4 - 6 ft	4.43-6.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-4-6	SSHS-B3223-SUB-4-6	8/29/2019	858.27	858.28	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-4-6	SSHS-B3003-SUB-4-6	8/30/2019	851.95	852.83	0.88	-	4 - 6 ft	4.88-6.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-4-6	SSHS-B3011-SUB-4-6	8/30/2019	853.85	854.62	0.77	-	4 - 6 ft	4.77-6.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-4-6	SSHS-B3039-SUB-4-6	8/30/2019	855.85	856.37	0.52	-	4 - 6 ft	4.52-6.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-4-6	SSHS-B3068-SUB-4-6	8/30/2019	856.38	856.82	0.44	-	4 - 6 ft	4.44-6.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-4-6	SSHS-B3082-SUB-4-6	8/30/2019	856.73	857.22	0.49	-	4 - 6 ft	4.49-6.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-4-6	SSHS-B3214-SUB-4-6	8/30/2019	855.06	855.25	0.19	-	4 - 6 ft	4.19-6.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-4-6	SSHS-B3222-SUB-4-6	8/30/2019	858.28	858.08	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-4-6	SSHS-B3224-SUB-4-6	8/30/2019	858.38	858.48	0.10	-	4 - 6 ft	4.1-6.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-4-6	SSHS-B3001-SUB-4-6	9/3/2019	853.35	853.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-4-6	SSHS-B3002-SUB-4-6	9/3/2019	853.09	853.12	0.03	-	4 - 6 ft	4.03-6.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-4-6	SSHS-B3009-SUB-4-6	9/3/2019	853.88	854.29	0.41	-	4 - 6 ft	4.41-6.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-4-6	SSHS-B3010-SUB-4-6	9/3/2019	854.13	854.48	0.35	-	4 - 6 ft	4.35-6.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-4-6	SSHS-B3023-SUB-4-6	9/3/2019	854.48	854.90	0.42	-	4 - 6 ft	4.42-6.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-4-6	SSHS-B3024-SUB-4-6	9/3/2019	855.00	855.16	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-4-6	SSHS-B3036-SUB-4-6	9/3/2019	855.09	855.21	0.12	-	4 - 6 ft	4.12-6.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-4-6	SSHS-B3038-SUB-4-6	9/3/2019	855.76	855.72	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-95162-1	Not Excavated							

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated							
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated							
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated							
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated							
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated							
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated							
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.55 U	< 0.046 U	< 0.055 U	< 0.037 U	< 0.46 U	< 0.064 U,*+	< 0.055 U	< 0.18 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated							
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.0046 U	< 0.00027 U	< 0.00039 U	< 0.00073 U	< 0.0027 U	< 0.00049 U	< 0.0027 U	< 0.00053 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	0.084 J	< 0.00067 U	< 0.0012 U	< 0.0015 U	< 0.0023 U	< 0.004 U	< 0.0011 U	< 0.0031 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated							
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated							
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated							
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated							
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated							
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated							
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated							
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated						
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated						
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated						
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated						
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated						
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated						
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.046 U	< 0.18 U	< 0.092 U	< 0.055 U	< 0.055 U	< 0.046 U	< 0.092 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated						
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.00072 U	< 0.0007 U	< 0.0012 U	< 0.00034 U	< 0.00033 U	< 0.00076 U	< 0.0027 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.00089 U	< 0.0027 U	< 0.0026 U	< 0.00076 U	< 0.0022 U	< 0.0013 U	< 0.0035 UJ
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated						
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated						
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated						
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated						
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated						
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated						
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated						
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated						

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated							
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated							
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated							
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated							
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	0.012	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated							
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated							
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.18 U	< 0.037 U	< 0.055 U	< 0.046 U	< 0.046 U	< 0.037 U	< 0.046 U	< 0.055 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated							
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.0025 U	< 0.0007 U	< 0.00045 U	< 0.00043 U	< 0.00028 U	< 0.00076 U	< 0.00067 U	< 0.00027 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.012 U	< 0.00074 U	< 0.00091 U	< 0.0011 UJ	< 0.00079 UJ	< 0.00085 UJ	< 0.00067 U	< 0.00075 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated							
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated							
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated							
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated							
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated							
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated							
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated							
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated							

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3327	121819 10:30_SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3329	121819 10:30_SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3276	122119 10:30_SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3277	122119 10:30_SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3279	122119 10:30_SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3280	122119 10:30_SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3242	122119 10:30_SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3243	122119 10:30_SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3232	122119 10:30_SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated								
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated								
Northern Athletic Field	SSHS-B13A	012721 08:30_SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3057A	012721 08:30_SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3071A	012721 08:30_SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3037A	012721 08:30_SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3261A	012721 08:30_SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3516	012721 08:30_SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3631	012721 08:30_SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated								
Northern Athletic Field	SSHS-B3182A	012721 08:30_SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3224A	012721 08:30_SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3260A	012721 08:30_SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated								
Northern Athletic Field	SSHS-B3484A	012721 08:30_SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3490A	012721 08:30_SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3491A	012721 08:30_SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	SSHS-B3498	012721 08:30_SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3499	012721 08:30_SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3098A	012821 08:30_SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated								
Northern Athletic Field	SSHS-B3286A	012821 08:30_SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated								
Northern Athletic Field	SSHS-B3519	012821 08:30_SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated								
Northern Athletic Field	SSHS-B3282A	013021 10:00_SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated								
Northern Athletic Field	SSHS-B3629	020421 09:30_SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.046 U	< 0.092 U	< 0.046 U	< 0.046 U	< 0.046 U	< 0.037 U	< 0.046 U	< 0.037 U
Northern Athletic Field	SSHS-B4017	070221 09:00_SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated								
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-B4025	070221 09:00_SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4026	070221 09:00_SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.00067 U	< 0.0029 U	< 0.0007 U	< 0.00056 U	< 0.0027 U	< 0.00079 U	< 0.0024 U	< 0.00038 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0014 U	< 0.0014 U	< 0.00082 U	< 0.0028 U	< 0.0036 U	< 0.001 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated								
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated								
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated								
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated								
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated								
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated								
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated								
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated								
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated								
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated								
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated								
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated								
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated								
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated								
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated								
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated								
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated								
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated								
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated								
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.055 U	< 0.092 U	< 0.037 U	< 0.092 U	< 0.055 U	< 0.18 U	< 0.092 U	< 0.046 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated								
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated								
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.0012 U	< 0.0027 U	< 0.00082 U	< 0.0033 U	< 0.00083 U	< 0.002 U	< 0.0018 U	< 0.00054 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.0012 U	< 0.0039 U	< 0.0019 U	< 0.0033 U	< 0.0012 U	< 0.0034 U	< 0.0036 U	< 0.0019 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated								
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated								
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated								
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated								
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated								
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated								
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated								
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated						
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated						
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated						
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated						
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated						
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated						
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.037 U	< 0.037 U	< 0.046 U	< 0.055 U	< 0.46 U	< 0.46 U	< 0.055 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated						
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.00027 U	< 0.00088 U	< 0.00073 U	< 0.00041 U	< 0.00058 U	< 0.00033 U	< 0.0004 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.0011 U	< 0.0014 UJ	< 0.00071 U	0.0016 J	< 0.0029 UJ	< 0.0024 UJ	< 0.0017 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated						
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated						
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated						
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated						
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated						
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated						
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated						
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-4-6	SSHS-B3053-SUB-4-6	9/3/2019	856.41	856.22	-0.19	-	4 - 6 ft	3.81-5.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-4-6	SSHS-B3067-SUB-4-6	9/3/2019	856.40	856.48	0.08	-	4 - 6 ft	4.08-6.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-4-6	SSHS-B3051-SUB-4-6	9/4/2019	855.15	855.32	0.17	-	4 - 6 ft	4.17-6.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-4-6	SSHS-B3066-SUB-4-6	9/4/2019	855.86	856.02	0.16	-	4 - 6 ft	4.16-6.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-4-6	SSHS-B3080-SUB-4-6	9/4/2019	856.58	856.76	0.18	-	4 - 6 ft	4.18-6.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-4-6	SSHS-B3081-SUB-4-6	9/4/2019	856.96	857.03	0.07	-	4 - 6 ft	4.07-6.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-4-6	SSHS-B3085-SUB-4-6	9/4/2019	857.12	857.26	0.14	-	4 - 6 ft	4.14-6.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-4-6	SSHS-B3086-SUB-4-6	9/4/2019	857.77	857.49	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-4-6	SSHS-B3220-SUB-4-6	9/4/2019	857.44	857.92	0.48	-	4 - 6 ft	4.48-6.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-4-6	SSHS-B3221-SUB-4-6	9/4/2019	857.92	857.93	0.01	-	4 - 6 ft	4.01-6.01 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3327	121819 10:30 SSHS-B3327-SUB-4-6	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3329	121819 10:30 SSHS-B3329-SUB-4-6	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated							
Northern Athletic Field	SSHS-B3276	122119 10:30 SSHS-B3276-SUB-4-6	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3277	122119 10:30 SSHS-B3277-SUB-4-6	SSHS-B3277-SUB-4-6	12/18/2019	856.31	857.29	0.98	-	4 - 6 ft	4.98-6.98 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3279	122119 10:30 SSHS-B3279-SUB-4-6	SSHS-B3279-SUB-4-6	12/18/2019	856.57	856.71	0.14	-	4 - 6 ft	4.14-6.14 ft	180-100380-1	Not Excavated							
Northern Athletic Field	SSHS-B3280	122119 10:30 SSHS-B3280-SUB-4-6	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated							
Northern Athletic Field	SSHS-B3242	122119 10:30 SSHS-B3242-SUB-4-6	SSHS-B3242-SUB-4-6	12/19/2019	856.23	857.22	0.99	-	4 - 6 ft	4.99-6.99 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3243	122119 10:30 SSHS-B3243-SUB-4-6	SSHS-B3243-SUB-4-6	12/19/2019	856.13	857.96	1.83	-	4 - 6 ft	5.83-7.83 ft	180-100363-2	Not Excavated							
Northern Athletic Field	SSHS-B3232	122119 10:30 SSHS-B3232-SUB-4-6	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-4-6	SSHS-B3100-SUB-4-6	1/13/2020	856.74	856.68	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-4-6	SSHS-B3104-SUB-4-6	1/13/2020	856.82	856.64	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-4-6	SSHS-B3108-SUB-4-6	1/14/2020	857.55	856.76	-0.79	-	4 - 6 ft	3.21-5.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-4-6	SSHS-B3113-SUB-4-6	1/14/2020	856.36	856.08	-0.28	-	4 - 6 ft	3.72-5.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-4-6	SSHS-B3107-SUB-4-6	1/15/2020	857.05	857.26	0.21	-	4 - 6 ft	4.21-6.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-4-6	SSHS-B3110-SUB-4-6	1/15/2020	856.32	856.06	-0.26	-	4 - 6 ft	3.74-5.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-4-6	SSHS-B3111-SUB-4-6	1/15/2020	857.08	857.00	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-4-6	SSHS-B3116-SUB-4-6	1/15/2020	856.51	856.63	0.12	-	4 - 6 ft	4.12-6.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-4-6	SSHS-B3118-SUB-4-6	1/15/2020	856.74	856.72	-0.02	-	4 - 6 ft	3.98-5.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-4-6	SSHS-B3494-SUB-4-6	1/14/2021	858.31	858.13	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116002-2	Not Excavated							
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated							
Northern Athletic Field	SSHS-B13A	012721 08:30 SSHS-B13A-SUB-4-6	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3057A	012721 08:30 SSHS-B3057A-SUB-4-6	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3071A	012721 08:30 SSHS-B3071A-SUB-4-6	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3037A	012721 08:30 SSHS-B3037A-SUB-4-6	SSHS-B3037A-SUB-4-6	1/25/2021	855.59	855.55	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3261A	012721 08:30 SSHS-B3261A-SUB-4-6	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3516	012721 08:30 SSHS-B3516-SUB-4-6	SSHS-B3516-SUB-4-6	1/25/2021	856.33	856.96	0.63	-	4 - 6 ft	4.63-6.63 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3631	012721 08:30 SSHS-B3631-SUB-4-6	SSHS-B3631-SUB-4-6	1/25/2021	856.31	857.24	0.93	-	4 - 6 ft	4.93-6.93 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6-20210125	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated							
Northern Athletic Field	SSHS-B3182A	012721 08:30 SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3224A	012721 08:30 SSHS-B3224A-SUB-4-6	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-4-6	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6-20210126	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated							
Northern Athletic Field	SSHS-B3484A	012721 08:30 SSHS-B3484A-SUB-4-6	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3490A	012721 08:30 SSHS-B3490A-SUB-4-6	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3491A	012721 08:30 SSHS-B3491A-SUB-4-6	SSHS-B3491A-SUB-4-6	1/26/2021	858.35	858.44	0.09	-	4 - 6 ft	4.09-6.09 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6-20210126	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3498	012721 08:30 SSHS-B3498-SUB-4-6	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3499	012721 08:30 SSHS-B3499-SUB-4-6	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6-20210126	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3098A	012821 08:30 SSHS-B3098A-SUB-4-6	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-4-6	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated							
Northern Athletic Field	SSHS-B3519	012821 08:30 SSHS-B3519-SUB-4-6	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-4-6	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated							
Northern Athletic Field	SSHS-B3629	020421 09:30 SSHS-B3629-SUB-4-6	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6-20210511	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	0.0090	0.0033 J	0.012
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-4-6	SSHS-B3918-SUB-4-6	5/12/2021	854.82	854.84	0.02	-	4 - 6 ft	4.02-6.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6-20210517	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6-20210518	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-4-6	SSHS-B3933-SUB-4-6	6/17/2021	856.55	855.68	-0.87	-	4 - 6 ft	3.13-5.13 ft	180-123399-1	Not Excavated	< 0.046 U	< 0.046 U	< 0.064 U	< 0.055 U	< 0.092 U	< 0.037 U	< 0.13 U
Northern Athletic Field	SSHS-B4017	070221 09:00 SSHS-B4017-SUB-4-6	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated							
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6-20210701	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B4025	070221 09:00 SSHS-B4025-SUB-4-6	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4026	070221 09:00 SSHS-B4026-SUB-4-6	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated							
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-4-6	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.00071 U	< 0.0012 U	< 0.00052 U	< 0.00067 U	< 0.00092 U	< 0.00071 U	< 0.00092 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-4-6	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated	< 0.0011 U	0.002 J	< 0.0026 U	< 0.0017 U	< 0.00076 U	< 0.00083 U	< 0.0015 U
Northern Athletic Field	S169	SSHS-IRM5A2-DUP2-20211028	SSHS-IRM5A2-DUP2	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292042	Not Excavated							
Northern Athletic Field	S166	SSHS-IRM5A2-S166-20211028	SSHS-IRM5A2-S166	10/28/2021	-	855.73	-	850.85	4 - 6 ft	4.87 ft	1801292041	Not Excavated							
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292041	Not Excavated							
Northern Athletic Field	S165	SSHS-IRM5A2-S165-20211028	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated							
Northern Athletic Field	S164	SSHS-IRM5A2-S164-20211028	SSHS-IRM5A2-S164	10/28/2021	-	855.88	-	850.28	4 - 6 ft	5.6 ft	1801292041	Not Excavated							
Northern Athletic Field	S163	SSHS-IRM5A2-S163-20211028	SSHS-IRM5A2-S163	10/28/2021	-	856.26	-	851.08	4 - 6 ft	5.18 ft	1801292041	Not Excavated							
Northern Athletic Field	S162	SSHS-IRM5A2-S162-20211028	SSHS-IRM5A2-S162	10/28/2021	-	856.35	-	851.11	4 - 6 ft	5.24 ft	1801292041	Not Excavated							
Northern Athletic Field	S169	SSHS-IRM5A2-S169-20211028	SSHS-IRM5A2-S169	10/28/2021	-	856.21	-	851.33	4 - 6 ft	4.88 ft	1801292041	Not Excavated							

DRAFT

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.018 U	0.0025 J	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.001 U	< 0.0028 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated								
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated								
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated								
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated								
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated								
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated								
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated								
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated								
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated								
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated								
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated								
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated								
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated								
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated								
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated								
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated								
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated								
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	0.02 JT	< 0.00060 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.0010 U	< 0.0028 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.02 UT	< 0.00065 U	< 0.0012 U	< 0.0014 U	< 0.0022 U	< 0.0039 U	< 0.0011 U	< 0.0030 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated								
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated								
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated								
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated								
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0045 UT	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0047 UT	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801330901	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated								
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.00079 U	< 0.0024 U	< 0.0024 U	< 0.00068 U	< 0.002 U	0.0034 J	< 0.0031 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated							
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated							
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated							
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated							
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated							
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated							
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated							
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated							
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated							
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated							
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated							
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated							
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated							
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated							
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated							
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated							
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated							
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated							
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated							
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated							
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated							
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.00079 U	< 0.0024 U	< 0.0024 U	< 0.00068 U	< 0.0020 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.00085 U	< 0.0026 U	< 0.0026 U	< 0.00073 U	< 0.0021 U	< 0.0013 U	< 0.0034 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated							
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated							
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated							
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated							
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated							
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated							
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated							
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated							
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated							
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated							
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated							
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated							
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated							
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated								
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated								
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.01 U	< 0.00067 U	< 0.00081 U	< 0.00096 U	< 0.0007 U	< 0.00076 U	< 0.0006 U	< 0.00067 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated								
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated								
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated								
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated								
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated								
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated								
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated								
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated								
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated								
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated								
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated								
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated								
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated								
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated								
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated								
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated								
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated								
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.01 UT	< 0.00066 U	< 0.00081 U	< 0.00096 U	< 0.00070 U	< 0.00076 U	< 0.00060 U	< 0.00066 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.011 UT	< 0.00072 U	< 0.00088 U	< 0.0010 U	< 0.00076 U	< 0.00082 U	< 0.00065 U	< 0.00072 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated								
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated								
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated								
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated								
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801330901	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated								
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated								
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated								
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.00097 U	< 0.0013 U	< 0.0012 U	< 0.00074 U	< 0.0025 U	< 0.0032 U	0.00095 J
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated								
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated								
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated								
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated								
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated								
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated								
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated								
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated								
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated								
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated								
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated								
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated								
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated								
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated								
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated								
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated								
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated								
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.0016 U	< 0.00097 U	< 0.0013 U	< 0.0012 U	< 0.00073 U	< 0.0025 U	< 0.0032 U	< 0.00090 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0014 U	< 0.0013 U	< 0.00079 U	< 0.0027 U	< 0.0035 U	< 0.00098 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated								
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated								
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated								
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated								
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801330901	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated								
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated								
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated								
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0035 U	< 0.0017 U	< 0.0029 U	0.0065 J	< 0.0031 U	< 0.0032 U	< 0.0017 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated								
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated								
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated								
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated								
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated								
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated								
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated								
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated								
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated								
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated								
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated								
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated								
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated								
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated								
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated								
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated								
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated								
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated								
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated								
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated								
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0035 U	< 0.0017 U	0.042	< 0.0011 U	0.0046 J	< 0.0032 U	< 0.0017 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.0012 U	< 0.0038 U	< 0.0018 U	< 0.0032 U	< 0.0011 U	< 0.0033 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated								
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated								
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated								
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated								
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated								
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated								
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated								
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0023 U	< 0.0018 UT	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 UT	< 0.0021 UT	< 0.0017 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0024 U	< 0.0019 UT	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 UT	< 0.0022 UT	< 0.0018 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 UT	< 0.0017 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	5.21 ft	5.21 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	5.29 ft	5.29 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated								
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0012 U	< 0.00063 U	0.0073	< 0.0025 U	< 0.0022 U	< 0.0015 U
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated							
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated							
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated							
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated							
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated							
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated							
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated							
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated							
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated							
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated							
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated							
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated							
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated							
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated							
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated							
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated							
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated							
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated							
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated							
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated							
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated							
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.0010 U	< 0.0012 U	< 0.00063 U	< 0.00066 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.0011 U	< 0.0013 U	< 0.00068 U	< 0.00072 U	< 0.0028 U	< 0.0023 U	< 0.0017 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated							
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated							
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated							
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated							
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated							
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated							
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated							
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated							
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated							
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated							
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated							
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated							
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated							
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S168	SSHS-IRM5A2-S168-20211028	SSHS-IRM5A2-S168	10/28/2021	-	855.93	-	851.03	4 - 6 ft	4.9 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292041	Not Excavated							
Northern Athletic Field	S167	SSHS-IRM5A2-S167-20211028	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-4-6	SSHS-B4264-SUB-4-6	11/1/2021	852.29	853.31	1.02	-	4 - 6 ft	5.02-7.02 ft	180-129325-1	Not Excavated	< 0.00098 U	< 0.00055 U	< 0.0023 U	< 0.0015 U	0.0056 J	0.0019 J	0.0075 J
Northern Athletic Field	S161	SSHS-IRM5A2-DUP8-20211103	SSHS-IRM5A2-DUP8	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294633	Not Excavated							
Northern Athletic Field	S426	SSHS-IRM5A2-S426-20211103	SSHS-IRM5A2-S426	11/3/2021	-	857.62	-	853.31	4 - 6 ft	4.31 ft	1801294631	Not Excavated							
Northern Athletic Field	S427	SSHS-IRM5A2-S427-20211103	SSHS-IRM5A2-S427	11/3/2021	-	857.71	-	853.44	4 - 6 ft	4.27 ft	1801294631	Not Excavated							
Northern Athletic Field	S155	SSHS-IRM5A2-S155-20211103	SSHS-IRM5A2-S155	11/3/2021	-	857.55	-	851.99	4 - 6 ft	5.56 ft	1801294631	Not Excavated							
Northern Athletic Field	S156	SSHS-IRM5A2-S156-20211103	SSHS-IRM5A2-S156	11/3/2021	-	857.69	-	851.99	4 - 6 ft	5.7 ft	1801294631	Not Excavated							
Northern Athletic Field	S157	SSHS-IRM5A2-S157-20211103	SSHS-IRM5A2-S157	11/3/2021	-	857.82	-	851.98	4 - 6 ft	5.84 ft	1801294631	Not Excavated							
Northern Athletic Field	S158	SSHS-IRM5A2-S158-20211103	SSHS-IRM5A2-S158	11/3/2021	-	858.02	-	852.34	4 - 6 ft	5.68 ft	1801294631	Not Excavated							
Northern Athletic Field	S159	SSHS-IRM5A2-S159-20211103	SSHS-IRM5A2-S159	11/3/2021	-	858.00	-	852.58	4 - 6 ft	5.42 ft	1801294631	Not Excavated							
Northern Athletic Field	S160	SSHS-IRM5A2-S160-20211103	SSHS-IRM5A2-S160	11/3/2021	-	857.99	-	852.77	4 - 6 ft	5.22 ft	1801294631	Not Excavated							
Northern Athletic Field	S161	SSHS-IRM5A2-S161-20211103	SSHS-IRM5A2-S161	11/3/2021	-	857.75	-	852.47	4 - 6 ft	5.28 ft	1801294632	Not Excavated							
Northern Athletic Field	S152	SSHS-IRM5A2-S152-20211103	SSHS-IRM5A2-S152	11/3/2021	-	857.49	-	852.11	4 - 6 ft	5.39 ft	1801294631	Not Excavated							
Northern Athletic Field	S153	SSHS-IRM5A2-S153-20211103	SSHS-IRM5A2-S153	11/3/2021	-	857.47	-	852.18	4 - 6 ft	5.29 ft	1801294631	Not Excavated							
Northern Athletic Field	S154	SSHS-IRM5A2-S154-20211103	SSHS-IRM5A2-S154	11/3/2021	-	857.46	-	851.82	4 - 6 ft	5.64 ft	1801294631	Not Excavated							
Northern Athletic Field	S442	SSHS-IRM5A2-DUP11-20211104	SSHS-IRM5A2-DUP11	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated							
Northern Athletic Field	S446	SSHS-IRM5A2-S446-20211104	SSHS-IRM5A2-S446	11/4/2021	-	858.35	-	853.45	4 - 6 ft	4.9 ft	1801296371	Not Excavated							
Northern Athletic Field	S447	SSHS-IRM5A2-S447-20211104	SSHS-IRM5A2-S447	11/4/2021	-	858.81	-	853.29	4 - 6 ft	5.51 ft	1801296371	Not Excavated							
Northern Athletic Field	S448	SSHS-IRM5A2-S448-20211104	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated							
Northern Athletic Field	B421	SSHS-IRM5A2-B421-20211104	SSHS-IRM5A2-B421	11/4/2021	-	857.23	-	852.01	4 - 6 ft	5.22 ft	1801296371	Not Excavated							
Northern Athletic Field	B416	SSHS-IRM5A2-B416-20211104	SSHS-IRM5A2-B416	11/4/2021	-	857.74	-	851.92	4 - 6 ft	5.82 ft	1801296371	Not Excavated							
Northern Athletic Field	S450	SSHS-IRM5A2-S450-20211104	SSHS-IRM5A2-S450	11/4/2021	-	857.14	-	852.92	4 - 6 ft	4.22 ft	1801296371	Not Excavated							
Northern Athletic Field	B418A	SSHS-IRM5A2-B418A-20211104	SSHS-IRM5A2-B418A	11/4/2021	-	857.01	-	852.28	4 - 6 ft	4.74 ft	1801296371	Not Excavated							
Northern Athletic Field	S442	SSHS-IRM5A2-S442-20211104	SSHS-IRM5A2-S442	11/4/2021	-	857.32	-	853.14	4 - 6 ft	4.18 ft	1801296371	Not Excavated							
Northern Athletic Field	S443	SSHS-IRM5A2-S443-20211104	SSHS-IRM5A2-S443	11/4/2021	-	857.13	-	852.77	4 - 6 ft	4.36 ft	1801296371	Not Excavated							
Northern Athletic Field	B417	SSHS-IRM5A2-B417-20211104	SSHS-IRM5A2-B417	11/4/2021	-	857.29	-	852.27	4 - 6 ft	5.02 ft	1801296371	Not Excavated							
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2-20211108	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 0.00097 U	< 0.00054 U	< 0.0023 U	< 0.0015 U	< 0.00067 U	< 0.00074 U	< 0.0014 U
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1-20211110	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 0.0011 U	< 0.00059 U	< 0.0025 U	< 0.0017 U	< 0.00073 U	< 0.00080 U	< 0.0015 U
Northern Athletic Field	B418-S2	SSHS-IRM5A2-B418-S2-20211113	SSHS-IRM5A2-B418-S2	11/13/2021	-	856.86	-	851.13	4 - 6 ft	5.73 ft	1801299881	Not Excavated							
Northern Athletic Field	B775	SSHS-IRM5A2-B775-20211201	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated							
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20-20211205	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated							
Northern Athletic Field	B768	SSHS-IRM5A2-B768-20211205	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated							
Northern Athletic Field	B763	SSHS-IRM5A2-B763-20211205	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated							
Northern Athletic Field	B764	SSHS-IRM5A2-B764-20211205	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated							
Northern Athletic Field	B754	SSHS-IRM5A2-B754-20211205	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated							
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2-20211210	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated							
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3-20211210	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated							
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1-20211210	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated							
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24-20220106	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0011 U	0.0040 J	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S471	SSHS-IRM5A2-S471-20220106	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15-20220201	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16-20220201	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17-20220201	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28-20220202	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29-20220202	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 0.00099 U	0.0063	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34-20220202	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52-20220202	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53-20220202	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36-20220202	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37-20220202	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55-20220202	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220202	SSHS-IRM5A2-RS-S56	2/2/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801330901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35-20220207	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1-20220207	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3-20220207	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5-20220207	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1-20220208	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56-20220208	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated							
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78-20220303	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24-20220303	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25-20220303	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82-20220303	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86-20220303	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26-20220303	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S181	SSHS-IRM5A2-S181-20220303	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220306	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated							
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220306	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated							
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92-20220307	SSHS-ISMP-SLT-S92	3/7/2022	-	857.12	-	851.78	4 - 6 ft	5.34	1801347841	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27-20220307	SSHS-ISMP-SLT-BOT27	3/7/2022	-	856.46	-	850.59	4 - 6 ft	5.87	1801347841	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2-20220311	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3-20220311	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14-20220311	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.0027 UT	< 0.00012 UT	< 0.00013 UT	< 0.00012 UT	< 0.00020 U	< 0.00048 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated								
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	0.02	< 0.00038 U	< 0.00041 U	< 0.00037 U	< 0.00062 U	< 0.0015 U	< 0.00039 U	< 0.00056 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	0.0070	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	0.012	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	0.01	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	0.0074 J	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	0.0046 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0026 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0054 U	< 0.0020 U	< 0.0042 U	< 0.0032 U	< 0.0035 U	< 0.0032 U	< 0.0056 U	< 0.0028 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.018 U	< 0.00059 U	< 0.0011 U	< 0.0013 U	< 0.0020 U	< 0.0035 U	< 0.00098 U	< 0.0028 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.015 U	< 0.00048 U	< 0.00086 U	< 0.0010 U	< 0.0017 U	< 0.0029 U	< 0.00081 U	< 0.0023 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.024 U	< 0.00080 U	< 0.0014 U	< 0.0017 U	< 0.0027 U	< 0.0048 U	< 0.0013 U	< 0.0037 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.019 U	< 0.00064 U	< 0.0011 U	< 0.0014 U	< 0.0022 U	< 0.0038 U	< 0.0011 U	< 0.0030 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.018 U	< 0.00059 U	< 0.0010 U	< 0.0013 U	< 0.0020 U	< 0.0035 U	< 0.00098 U	< 0.0028 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.013 U	< 0.00042 U	< 0.00075 U	< 0.00091 U	< 0.0015 U	< 0.0025 U	< 0.00070 U	< 0.0020 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.018 U	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.0010 U	< 0.0028 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.022 U	< 0.00073 U	< 0.0013 U	< 0.0016 U	< 0.0025 U	< 0.0043 U	< 0.0012 U	< 0.0034 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.021 U	< 0.00069 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0041 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.021 U	< 0.00069 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0041 U	< 0.0011 U	< 0.0032 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.0010 U	< 0.0029 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.0057 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	0.011	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	0.036	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	0.00041 J	< 0.00038 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.000091 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.000084 UT	< 0.000092 U	< 0.00025 U	< 0.00046 UT	< 0.00021 U	< 0.00010 U	< 0.00022 UT
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated							
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated							
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated							
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.00026 U	< 0.00028 U	< 0.00076 U	< 0.0014 U	< 0.00063 U	< 0.00032 U	< 0.00067 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.0041 U	< 0.0022 U	< 0.0027 U	< 0.0033 U	< 0.0045 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.00078 U	< 0.0024 U	< 0.0023 U	< 0.00067 U	< 0.0019 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.00064 U	< 0.0019 U	< 0.00055 U	< 0.0016 U	< 0.00095 U	< 0.0025 U	
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.0010 U	< 0.0032 U	< 0.0031 U	< 0.00090 U	< 0.0026 U	< 0.0016 U	< 0.0041 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.00084 U	< 0.0026 U	< 0.0025 U	< 0.00073 U	< 0.0021 U	< 0.0013 U	< 0.0033 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.00078 U	< 0.0024 U	< 0.0023 U	< 0.00067 U	< 0.0019 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.00056 U	< 0.0017 U	< 0.00048 U	< 0.0014 U	< 0.00083 U	< 0.0022 U	
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.00080 U	< 0.0024 U	< 0.0024 U	< 0.00069 U	< 0.0020 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.00095 U	< 0.0029 U	< 0.0028 U	< 0.00082 U	< 0.0024 U	< 0.0014 U	< 0.0037 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.00091 U	< 0.0028 U	< 0.0027 U	< 0.00078 U	< 0.0023 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.00090 U	< 0.0027 U	< 0.0027 U	< 0.00078 U	< 0.0022 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.00069 U	< 0.0020 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.00021 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 UT	< 0.00027 U	< 0.00057 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0017 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00017 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.00071 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.00054 UT	< 0.000086 UT	< 0.00016 U	< 0.00017 UT	< 0.00017 UT	< 0.00011 UT	< 0.000098 U	< 0.00014 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated								
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00049 U	< 0.00052 U	< 0.00053 U	< 0.00033 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0029 U	< 0.0019 U	< 0.0033 U	< 0.0017 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0054 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0063 U	< 0.0019 U	< 0.0035 U	< 0.0023 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.0020 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.01 U	< 0.00065 U	< 0.00080 U	< 0.00094 U	< 0.00069 U	< 0.00075 U	< 0.00059 U	< 0.00065 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.0083 U	< 0.00053 U	< 0.00065 U	< 0.00077 U	< 0.00057 U	< 0.00061 U	< 0.00048 U	< 0.00054 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.014 U	< 0.00088 U	< 0.0011 U	< 0.0013 U	< 0.00093 U	< 0.0010 U	< 0.00079 U	< 0.00088 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.011 U	< 0.00071 U	< 0.00087 U	< 0.0010 U	< 0.00075 U	< 0.00081 U	< 0.00064 U	< 0.00071 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.01 U	< 0.00065 U	< 0.00080 U	< 0.00094 U	< 0.00069 U	< 0.00075 U	< 0.00059 U	< 0.00065 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.0073 U	< 0.00047 U	< 0.00057 U	< 0.00067 U	< 0.00049 U	< 0.00053 U	< 0.00042 U	< 0.00047 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.01 U	< 0.00067 U	< 0.00082 U	< 0.00097 U	< 0.00071 U	< 0.00077 U	< 0.00060 U	< 0.00067 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.012 U	< 0.00080 U	< 0.00098 U	< 0.0012 U	< 0.00085 U	< 0.00092 U	< 0.00072 U	< 0.00080 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.012 U	< 0.00076 U	< 0.00093 U	< 0.0011 U	< 0.00081 U	< 0.00087 U	< 0.00069 U	< 0.00076 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.012 U	< 0.00076 U	< 0.00093 U	< 0.0011 U	< 0.00080 U	< 0.00087 U	< 0.00068 U	< 0.00076 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 U	< 0.00098 U	< 0.00072 U	< 0.00078 U	< 0.00061 U	< 0.00068 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 UT	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 UT	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 UT	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.00011 U	< 0.00018 UT	< 0.00017 UT	< 0.00012 UT	< 0.00020 U	< 0.00013 UT	< 0.00013 U	< 0.000095 UT
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated								
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00052 U	< 0.00036 U	< 0.00061 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0031 U	< 0.0057 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0031 U	< 0.0026 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.0015 U	< 0.00095 U	< 0.0013 U	< 0.0012 U	< 0.00072 U	< 0.0024 U	< 0.0031 U	< 0.00089 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.0013 U	< 0.00078 U	< 0.0010 U	< 0.00099 U	< 0.00059 U	< 0.0020 U	< 0.0026 U	< 0.00073 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.0021 U	< 0.0013 U	< 0.0017 U	< 0.0016 U	< 0.00097 U	< 0.0033 U	< 0.0042 U	< 0.0012 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.0017 U	< 0.0010 U	< 0.0014 U	< 0.0013 U	< 0.00078 U	< 0.0027 U	< 0.0034 U	< 0.00097 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.0015 U	< 0.00095 U	< 0.0013 U	< 0.0012 U	< 0.00072 U	< 0.0024 U	< 0.0031 U	< 0.00089 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.0011 U	< 0.00068 U	< 0.00090 U	< 0.00086 U	< 0.00052 U	< 0.0017 U	< 0.0022 U	< 0.00063 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.0016 U	< 0.00098 U	< 0.0013 U	< 0.0012 U	< 0.00074 U	< 0.0025 U	< 0.0032 U	< 0.00091 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0015 U	< 0.0015 U	< 0.00088 U	< 0.0030 U	< 0.0039 U	< 0.0011 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00084 U	< 0.0028 U	< 0.0037 U	< 0.0010 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00084 U	< 0.0028 U	< 0.0037 U	< 0.0010 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.0016 U	< 0.00099 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00092 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.00016 U	< 0.00088 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00080 U	< 0.00026 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00096 U	< 0.00032 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.00014 U	< 0.00081 UT	< 0.00014 UT	< 0.0020 UT	< 0.00024 UT	< 0.00017 UT	< 0.00074 UT	< 0.00024 UT
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated								
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated								
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00041 U	< 0.0063 U	< 0.00073 U	< 0.00053 U	< 0.0023 U	< 0.00074 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated								
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0024 UT	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0028 U	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0033 U	< 0.0035 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.0011 U	< 0.0035 U	< 0.0016 U	< 0.0029 U	< 0.0010 U	< 0.0030 U	< 0.0031 U	< 0.0017 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.00089 U	< 0.0028 U	< 0.0013 U	< 0.0024 U	< 0.00085 U	< 0.0025 U	< 0.0026 U	< 0.0014 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.0015 U	< 0.0047 U	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0041 U	< 0.0043 U	< 0.0023 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.0012 U	< 0.0038 U	< 0.0018 U	< 0.0031 U	< 0.0011 U	< 0.0033 U	< 0.0034 U	< 0.0018 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.0011 U	< 0.0035 U	< 0.0016 U	< 0.0029 U	< 0.0010 U	< 0.0030 U	< 0.0031 U	< 0.0017 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.00078 U	< 0.0025 U	< 0.0012 U	< 0.0021 U	< 0.00074 U	< 0.0022 U	< 0.0023 U	< 0.0012 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0031 U	< 0.0032 U	< 0.0017 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.0013 U	< 0.0042 U	< 0.0020 U	< 0.0035 U	< 0.0013 U	< 0.0037 U	< 0.0039 U	< 0.0021 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.0013 U	< 0.0040 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0035 U	< 0.0037 U	< 0.0020 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.0013 U	< 0.0040 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0035 U	< 0.0037 U	< 0.0020 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0017 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 UT	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0014 U	< 0.00044 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 UT	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 UT	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 UT	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 UT	< 0.0028 U	< 0.0020 U	< 0.0016 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000093 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.00013 UT	< 0.00010 UT	< 0.00014 UT	< 0.00011 UT	< 0.000086 UT	< 0.00017 UT	< 0.00011 U
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated							
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated							
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated							
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.00040 U	< 0.00031 U	< 0.00044 U	< 0.00034 U	< 0.00026 U	< 0.00052 U	< 0.00034 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0038 U	< 0.0035 U	< 0.0023 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.00098 U	< 0.0012 U	< 0.00062 U	< 0.00065 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.00080 U	< 0.00099 U	< 0.00051 U	< 0.00054 U	< 0.0020 U	< 0.0017 U	< 0.0012 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.0013 U	< 0.0016 U	0.0014 J	< 0.00089 U	< 0.0034 U	< 0.0029 U	< 0.0020 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.0011 U	< 0.0013 U	0.00068 J	< 0.00071 U	< 0.0027 U	< 0.0023 U	< 0.0016 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.00098 U	< 0.0012 U	< 0.00062 U	< 0.00065 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.00070 U	< 0.00087 U	< 0.00044 U	< 0.00047 U	< 0.0018 U	< 0.0015 U	< 0.0011 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.0010 U	< 0.0012 U	< 0.00064 U	< 0.00067 U	< 0.0026 U	< 0.0022 U	< 0.0015 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.0012 U	< 0.0015 U	< 0.00076 U	< 0.00080 U	< 0.0031 U	< 0.0026 U	< 0.0018 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.0011 U	< 0.0014 U	0.0012 J	< 0.00076 U	< 0.0029 U	< 0.0025 U	< 0.0018 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.00072 U	< 0.00076 U	< 0.0029 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.0010 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.00032 U	< 0.00025 U	0.00037 J	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00025 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S124	SSHS-IRM5A2-S124-20220314	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22-20220315	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 0.000092 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.00033 U
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28-20220315	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.03	1801352021	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00040 U
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34-20220316	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.36	1801352871	Not Excavated	< 0.000085 U	< 0.00015 UT	< 0.00019 U	< 0.00026 U	< 0.000083 UT	< 0.000092 UT	< 0.00030 UT
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40-20220317	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46-20220317	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00026 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00042 U
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52-20220318	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10-20220318	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54-20220318	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.88	1801354291	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220319	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated							
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220319	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated							
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220319	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated							
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62-20220321	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00059 U	< 0.00079 U	< 0.00025 U	< 0.00028 U	< 0.00093 U
Northern Athletic Field	S221	SSHS-IRM5A2-S221-20220321	SSHS-IRM5A2-S221	3/21/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354851	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A-20220321	SSHS-IRM5A2-S123A	3/21/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00056 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122-20220321	SSHS-IRM5A2-S122	3/21/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00071 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA-20220328	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	IRM5-FP-BOT6S	SSHS-IRM5-FP-BOT6S-20220328	SSHS-IRM5-FP-BOT6S	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-S6S	SSHS-IRM5-FP-S6S-20220328	SSHS-IRM5-FP-S6S	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-S5S	SSHS-IRM5-FP-S5S-20220328	SSHS-IRM5-FP-S5S	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated							
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6-20220328	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5-20220328	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6-20220328	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87-20220408	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16-20220408	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89-20220408	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182-20220408	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64-20220421	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S147	SSHS-IRM5A2-S147-20220421	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0020 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	B116	SSHS-IRM5A2-B116-20220421	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111-20220421	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	B117	SSHS-IRM5A2-B117-20220421	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0058 U	< 0.0050 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Northern Athletic Field	B110	SSHS-IRM5A2-B110-20220421	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	B115	SSHS-IRM5A2-B115-20220421	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	B114	SSHS-IRM5A2-B114-20220421	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	B113	SSHS-IRM5A2-B113-20220422	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	B105	SSHS-IRM5A2-B105-20220422	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67-20220425	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.00096 U	< 0.00054 U	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00073 U	< 0.0013 U
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1-20220425	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 0.00079 U	< 0.00044 U	< 0.0019 U	< 0.0012 U	< 0.00054 U	< 0.00060 U	< 0.0011 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148-20220425	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 0.0013 U	0.0032 J	< 0.0031 U	< 0.0020 U	< 0.00090 U	< 0.00099 U	< 0.0018 U
Northern Athletic Field	S149	SSHS-IRM5A2-S149-20220425	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 0.0010 U	< 0.00058 U	< 0.0025 U	< 0.0016 U	< 0.00072 U	< 0.00079 U	< 0.0015 U
Northern Athletic Field	S151	SSHS-IRM5A2-S151-20220425	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 0.00096 U	< 0.00054 U	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00073 U	< 0.0013 U
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4-20220425	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 0.00069 U	< 0.00038 U	< 0.0016 U	< 0.0011 U	< 0.00047 U	< 0.00052 U	< 0.00096 U
Northern Athletic Field	S150	SSHS-IRM5A2-S150-20220425	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 0.00099 U	< 0.00055 U	< 0.0023 U	< 0.0015 U	< 0.00068 U	< 0.00075 U	< 0.0014 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133-20220425	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 0.0012 U	< 0.00066 U	< 0.0028 U	< 0.0018 U	< 0.00081 U	< 0.00089 U	< 0.0016 U
Northern Athletic Field	S134	SSHS-IRM5A2-S134-20220425	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 0.0011 U	< 0.00063 U	< 0.0027 U	< 0.0018 U	< 0.00077 U	< 0.00085 U	< 0.0016 U
Northern Athletic Field	S135	SSHS-IRM5A2-S135-20220425	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 0.0011 U	< 0.00062 U	< 0.0027 U	< 0.0017 U	< 0.00077 U	< 0.00085 U	< 0.0016 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6-20220425	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 0.0010 U	< 0.00056 U	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00076 U	< 0.0014 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73-20220426	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	B103	SSHS-IRM5A2-B103-20220426	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	B102	SSHS-IRM5A2-B102-20220426	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00070 U
Northern Athletic Field	B108	SSHS-IRM5A2-B108-20220426	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00058 U
Northern Athletic Field	B112	SSHS-IRM5A2-B112-20220426	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 0.00021 U	0.00038 J	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00074 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119-20220426	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 0.00016 U	0.00033 J	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00058 U
Northern Athletic Field	B106	SSHS-IRM5A2-B106-20220426	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	B100	SSHS-IRM5A2-B100-20220426	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 0.00018 U	0.00084 J	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00065 U
Northern Athletic Field	B107	SSHS-IRM5A2-B107-20220426	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00057 U
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7-20220505	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81-20220509	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00075 U
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7-20220509	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 UT	< 0.00015 U	< 0.00017 U	< 0.00056 U
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000-20220509	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 UT	< 0.00020 U	< 0.00022 U	< 0.00072 U
Northern Athletic Field	S532	SSHS-IRM5A2-S532-20220509	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 UT	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001-20220509	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 UT	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16-20220509	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 UT	< 0.00022 U	< 0.00024 U	< 0.00080 U
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603-20220509	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 UT	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220509	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 UT	< 0.00015 U	< 0.00017 U	< 0.00056 U
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605-20220509	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 UT	< 0.00016 U	< 0.00017 U	< 0.00058 U
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602-20220509	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604-20220509	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 UT	< 0.00014 U	< 0.00016 U	< 0.00051 U
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5-20220511	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1-20220511	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3-20220511	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2-20220511	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6-20220511	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	0.012	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 UT
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 UT	< 0.00040 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.0078 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00058 U	< 0.0014 U	0.00037 J	< 0.00053 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.0065 U	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.01 U	< 0.00045 U	< 0.00049 U	< 0.00045 U	< 0.00074 U	< 0.0018 U	< 0.00047 U	< 0.00068 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 UT	< 0.00034 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.0056 UT	< 0.00025 UT	< 0.00028 UT	< 0.00025 UT	< 0.00042 UT	< 0.00098 U	< 0.00026 UT	< 0.00038 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.0084 U	< 0.00038 U	< 0.00041 U	< 0.00038 U	< 0.00062 U	< 0.0015 U	< 0.00039 U	< 0.00057 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.0083 U	< 0.00037 U	< 0.00041 U	< 0.00037 U	< 0.00062 U	< 0.0015 U	< 0.00039 U	< 0.00056 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.0087 U	< 0.00039 U	< 0.00043 U	< 0.00039 U	< 0.00065 U	< 0.0015 U	< 0.00041 U	< 0.00059 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.0094 U	< 0.00042 U	< 0.00046 U	< 0.00042 U	< 0.00069 U	< 0.0016 U	< 0.00043 U	< 0.00063 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	0.062	< 0.00023 U	< 0.00025 UT	< 0.00023 U	< 0.00038 U	< 0.00090 U	0.00094	< 0.00035 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 UT	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	0.077	< 0.00025 U	< 0.00027 UT	< 0.00024 U	< 0.00040 U	< 0.00095 U	0.00096	< 0.00037 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 UT	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 UT	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 UT	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	0.012	< 0.00025 U	< 0.00027 UT	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 UT	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	0.0074	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.0034 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00060 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	0.0076	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00059 U	< 0.00016 U	< 0.00023 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0017 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00034 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00071 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00063 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0024 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0021 J	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0024 J	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0025 J	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25_SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0039 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.00031 U	< 0.00034 U	< 0.00091 U	< 0.0017 U	< 0.00076 U	< 0.00039 U	< 0.00081 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.00017 UT	< 0.00019 UT	< 0.00051 U	< 0.00095 UT	< 0.00043 U	< 0.00022 U	< 0.00045 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00077 U	< 0.0014 U	< 0.00064 U	< 0.00032 U	< 0.00068 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	0.0029 BJ	< 0.0017 U	< 0.0021 U	< 0.0028 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	0.0044 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0039 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0040 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0046 BJ	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0036 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0045 BJ	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0040 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00057 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.00026 U	< 0.00028 U	< 0.00076 U	< 0.0014 U	< 0.00063 U	< 0.00032 U	< 0.00067 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.00027 U	< 0.00030 U	< 0.00080 U	< 0.0015 U	< 0.00066 U	< 0.00034 U	< 0.00070 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.00029 U	< 0.00032 U	< 0.00085 U	< 0.0016 U	< 0.00071 U	< 0.00036 U	< 0.00075 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0026 J,B	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0025 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0025 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0025 J	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0032 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	0.0039 BJ	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0035 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0043 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0042 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0034 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0036 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.000096 U	< 0.00011 U	< 0.00028 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.00011 U	< 0.00013 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00031 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00057 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.00084 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 UT
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00046 U	< 0.00049 U	< 0.00050 U	< 0.00031 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.0020 U	< 0.00032 U	< 0.00059 U	< 0.00063 U	< 0.00064 U	< 0.00039 U	< 0.00036 U	< 0.00052 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.0011 UT	< 0.00018 UT	< 0.00033 U	< 0.00035 UT	< 0.00036 UT	< 0.00022 UT	< 0.00020 UT	< 0.00029 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00050 U	< 0.00053 U	< 0.00054 U	< 0.00033 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00049 U	< 0.00052 U	< 0.00053 U	< 0.00033 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.0017 U	< 0.00027 U	< 0.00052 U	< 0.00055 U	< 0.00056 U	< 0.00034 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.0019 U	< 0.00029 U	< 0.00055 U	< 0.00059 U	< 0.00060 U	< 0.00037 U	< 0.00034 U	< 0.00048 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.00062 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.00074 U	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.00069 U	< 0.00011 U	< 0.00020 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00015 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.00031 U	< 0.00052 U	< 0.00049 U	< 0.00034 U	< 0.00058 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.00039 U	< 0.00067 U	< 0.00063 U	< 0.00043 U	< 0.00074 U	< 0.00048 U	< 0.00047 U	< 0.00035 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.00022 UT	< 0.00037 UT	< 0.00035 UT	< 0.00024 UT	< 0.00041 UT	< 0.00027 UT	< 0.00026 UT	< 0.00019 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00053 U	< 0.00036 UT	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.00033 U	< 0.00055 U	< 0.00052 U	< 0.00036 U	< 0.00061 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.00034 U	< 0.00058 U	< 0.00055 U	< 0.00038 U	< 0.00064 U	< 0.00042 U	< 0.00041 U	< 0.00030 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.00037 U	< 0.00062 U	< 0.00059 U	< 0.00040 U	< 0.00069 U	< 0.00045 U	< 0.00043 U	< 0.00033 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	0.00019 J
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 UT	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00047 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.00022 U	< 0.0013 U	< 0.00021 U	< 0.0031 U	< 0.00037 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00039 U	< 0.0059 U	< 0.00068 U	< 0.00050 U	< 0.0021 U	< 0.00070 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.00034 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.00053 U	< 0.0030 U	< 0.00050 U	< 0.0075 U	< 0.00087 U	< 0.00065 U	< 0.0027 U	< 0.00090 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.00029 UT	< 0.0017 UT	< 0.00028 UT	< 0.0042 U	< 0.00049 UT	< 0.00036 UT	< 0.0015 UT	< 0.00050 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00042 U	< 0.0063 U	< 0.00073 U	< 0.00054 U	< 0.0023 U	< 0.00075 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.00038 U	< 0.0021 U	< 0.00036 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00041 U	< 0.0062 U	< 0.00072 U	< 0.00053 U	< 0.0023 U	< 0.00074 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.00046 U	< 0.0026 U	< 0.00043 U	< 0.0066 U	< 0.00076 U	< 0.00056 U	< 0.0024 U	< 0.00078 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.00049 U	< 0.0028 U	< 0.00047 U	< 0.0070 U	< 0.00082 U	< 0.00060 U	< 0.0025 U	< 0.00084 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	0.012	< 0.0014 U	< 0.00046 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	0.017	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.00016 U	< 0.00093 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00094 U	< 0.00031 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.00038 U	< 0.0021 U	< 0.00036 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00030 U	< 0.00022 U	< 0.00092 U	< 0.00030 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.00020 U	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00042 U	< 0.00032 U	< 0.00025 U	< 0.00049 U	< 0.00032 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-4-6	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	0.00053 J	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.00049 U	< 0.00038 U	< 0.00053 U	< 0.00041 U	< 0.00032 U	< 0.00063 U	< 0.00041 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.00027 UT	< 0.00021 UT	< 0.00030 UT	< 0.00023 UT	< 0.00018 UT	< 0.00035 UT	< 0.00023 U
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.00041 U	< 0.00031 U	< 0.00045 U	< 0.00034 U	< 0.00027 U	< 0.00053 U	< 0.00034 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.00040 U	< 0.00031 U	< 0.00044 U	< 0.00034 U	< 0.00026 U	< 0.00052 U	< 0.00034 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.00042 U	< 0.00033 U	< 0.00046 U	< 0.00036 U	< 0.00028 U	< 0.00055 U	< 0.00036 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00033 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.00045 U	< 0.00035 U	< 0.00050 U	< 0.00038 U	< 0.00030 U	< 0.00059 U	< 0.00038 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000098 U	< 0.00019 U	< 0.00013 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	0.00037 J	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606-20220512	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8-20220517	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00047 U
Northern Athletic Field	S544	SSHS-IRM5A2-S544-20220517	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00067 U
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628-20220517	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated	< 0.00024 U	< 0.00044 U	< 0.00055 U	< 0.00075 U	< 0.00024 U	< 0.00026 U	< 0.00088 U
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001-20220518	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002-20220518	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003-20220518	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004-20220518	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-4-6	SSHS-DW-15-SUB-4-6	6/4/2022	856.60	856.86	0.26	-	4 - 6 ft	4.26-6.26 ft	180-139185-1	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-4-6	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25_SSHS-DW-7 8-SUB-4-6	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103-20220607	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601-20220607	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600-20220607	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603-20220607	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602-20220607	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated	< 0.00031 U	< 0.00056 U	< 0.00071 U	< 0.00096 U	< 0.00030 U	< 0.00034 U	< 0.00030 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27-20220610	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated	< 0.00016 U	0.00037 J	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220611	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1-20220613	SSHS-IRM5A2-FISR-S1	6/13/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395961	Not Excavated	< 0.00019 U	0.0011	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9-20220615	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated	< 0.00017 UT	< 0.00031 UT	< 0.00040 U	< 0.00053 UT	< 0.00017 UT	< 0.00019 UT	< 0.00017 UT
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25-20220615	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00060 U	< 0.00080 U	< 0.00026 U	< 0.00029 U	< 0.00026 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127-20220616	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.00087 U	< 0.0014 U	< 0.0036 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0063 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401-20220616	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402-20220616	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403-20220616	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404-20220616	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200-20220616	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201-20220616	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203-20220616	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405-20220617	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated	< 0.00016 U	0.00050 J	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A-20220617	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A-20220617	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated	< 0.00026 U	0.0057	< 0.00059 U	< 0.00079 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206-20220617	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated	< 0.00027 U	0.013	< 0.00062 U	< 0.00083 U	< 0.00027 U	< 0.00030 U	< 0.00027 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208-20220617	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated	< 0.00018 U	0.0033	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A-20220617	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated	< 0.00029 U	0.00052 J	< 0.00066 U	< 0.00089 U	< 0.00028 U	< 0.00032 U	< 0.00028 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133-20220620	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 UT	< 0.00049 U	< 0.00016 U	0.00024 J	0.00024 J
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-4-6	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-4-6	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-4-6	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409-20220620	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 UT	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410-20220620	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 UT	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A-20220620	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 UT	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411-20220620	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated	< 0.00020 U	0.00042 J	< 0.00045 UT	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412-20220620	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 UT	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413-20220620	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 UT	< 0.00053 U	0.00064 J	0.00030 J	0.00094 J
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414-20220620	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 UT	< 0.00060 U	0.00030 J	< 0.00021 U	0.00030 J
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415-20220620	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214-20220622	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144-20220630	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50-20220630	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65-20220630	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59-20220630	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60-20220630	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66-20220630	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55-20220630	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403-20220701	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404-20220701	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148-20220705	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405-20220705	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated	< 0.000097 U	< 0.00017 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406-20220705	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407-20220705	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00033 U	< 0.00010 U	< 0.00012 U	< 0.00010 U
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400-20220705	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401-20220705	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402-20220705	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404-20220705	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405-20220705	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406-20220705	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408-20220705	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00054 UT	< 0.00072 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410-20220705	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 UT	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411-20220705	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 UT	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413-20220705	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 UT	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414-20220705	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 UT	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415-20220705	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416-20220705	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	0.0065	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	0.0076	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 UT	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 UT	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 UT	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 UT	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.0062 U	< 0.00028 UT	< 0.00031 UT	< 0.00028 U	< 0.00046 UT	< 0.0011 UT	< 0.00029 UT	< 0.00042 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 UT	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.011 U	< 0.00050 U	< 0.00055 U	< 0.00050 U	< 0.00083 U	< 0.0019 UT	< 0.00052 U	< 0.00075 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 UT	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.0044 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00077 UT	< 0.00020 U	< 0.00030 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 UT	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 UT	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00095 UT	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00057 U	< 0.0013 UT	< 0.00035 U	< 0.00052 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.0085 UT	< 0.00038 UT	< 0.00042 UT	< 0.00038 UT	< 0.00063 UT	< 0.0015 UT	< 0.00040 UT	< 0.00058 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	0.35	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.0084 U	< 0.00038 U	< 0.00041 U	< 0.00038 U	< 0.00063 U	< 0.0015 UT	< 0.00039 UT	< 0.00057 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 UT	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UT	< 0.0040 U	< 0.0020 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	0.015	0.00031 J	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	0.01	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	0.0064	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	0.0094 J	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	0.013 BJ	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	0.0070 BJ	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	0.01 J	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	0.0086 J	< 0.0012 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	0.0077 J	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	0.0066 J	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.0048 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	0.0072	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.0092 U	< 0.00042 U	< 0.00045 U	< 0.00042 U	< 0.00069 U	< 0.0016 U	< 0.00043 U	< 0.00063 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418891	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	0.011	< 0.00035 U	< 0.00039 U	< 0.00035 U	< 0.00058 U	< 0.0014 U	< 0.00036 U	< 0.00053 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	0.0062	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00041 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	0.0081	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 UT	< 0.00046 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 UT	< 0.00041 UT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 UT	< 0.0011 U	< 0.00047 UT	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 UT	< 0.00096 U	< 0.00043 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 UT	< 0.0011 U	< 0.00049 UT	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 UT	< 0.00094 U	< 0.00042 UT	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 UT	< 0.0011 U	< 0.00049 UT	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 UT	< 0.0011 U	< 0.00048 UT	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 UT	< 0.00094 U	< 0.00042 UT	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 UT	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.00019 UT	< 0.00021 UT	< 0.00057 UT	< 0.0011 UT	< 0.00048 UT	< 0.00024 UT	< 0.00050 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 UT	< 0.0011 U	< 0.00048 UT	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.00035 U	< 0.00038 U	< 0.0010 UT	< 0.0019 U	< 0.00085 UT	< 0.00043 U	< 0.00090 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 UT	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 UT	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00034 UT	< 0.00017 U	< 0.00035 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 UT	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 UT	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00041 UT	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00070 U	< 0.0013 U	< 0.00058 UT	< 0.00029 U	< 0.00061 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 UT	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 UT	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.00026 UT	< 0.00029 UT	< 0.00078 UT	< 0.0014 UT	< 0.00065 UT	< 0.00033 UT	< 0.00068 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.00022 U	< 0.00025 U	< 0.00066 U	< 0.0012 U	< 0.00055 UT	< 0.00028 U	< 0.00058 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 UT	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00077 U	< 0.0014 U	< 0.00064 UT	< 0.00033 U	< 0.00068 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UT
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00052 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0030 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.00029 U	< 0.00031 U	< 0.00084 U	< 0.0016 U	< 0.00070 U	< 0.00036 U	< 0.00074 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00024 U	< 0.00027 U	< 0.00072 U	< 0.0013 U	< 0.00060 U	< 0.00030 U	< 0.00063 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00057 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.00019 UT	< 0.00021 UT	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 UT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.0013 U	< 0.00020 UT	< 0.00037 UT	< 0.00039 UT	< 0.00040 UT	< 0.00025 UT	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.0022 U	< 0.00035 U	< 0.00066 U	< 0.00070 U	< 0.00071 U	< 0.00044 U	< 0.00040 U	< 0.00058 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.00088 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00049 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00037 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.0017 UT	< 0.00027 UT	< 0.00050 UT	< 0.00054 UT	< 0.00054 UT	< 0.00033 UT	< 0.00031 UT	< 0.00044 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00046 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	0.0018 J	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.0017 U	< 0.00027 U	< 0.00050 U	< 0.00053 U	< 0.00054 U	< 0.00033 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 UT	< 0.0034 UT	< 0.0016 UT	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0041 UT	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.0042 UT	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.0044 UT	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.0040 UT	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.0043 UT	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0044 UT	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.0010 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.0019 U	< 0.00029 U	< 0.00055 U	< 0.00058 U	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00046 U	< 0.00049 U	< 0.00050 U	< 0.00031 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.0012 U	< 0.00019 UT	< 0.00036 U	< 0.00039 UT	< 0.00039 UT	< 0.00024 UT	< 0.00022 U	< 0.00032 UT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.00025 UT	< 0.00042 UT	< 0.00039 UT	< 0.00027 UT	< 0.00046 U	< 0.00030 UT	< 0.00029 UT	< 0.00022 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.00044 U	< 0.00074 U	< 0.00070 U	< 0.00048 U	< 0.00082 U	< 0.00053 U	< 0.00052 U	< 0.00039 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00048 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00027 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.00033 UT	< 0.00057 UT	< 0.00053 UT	< 0.00037 UT	< 0.00063 UT	< 0.00041 UT	< 0.00040 UT	< 0.00030 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00045 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00053 U	< 0.00036 U	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.00036 U	< 0.00062 U	< 0.00058 U	< 0.00040 U	< 0.00068 U	< 0.00044 U	< 0.00043 U	< 0.00032 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00031 U	< 0.00052 U	< 0.00049 U	< 0.00034 U	< 0.00058 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00047 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 UT	< 0.00028 UT	< 0.00021 UT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.00033 UT	< 0.0019 U	< 0.00031 UT	< 0.0047 U	< 0.00054 UT	< 0.00040 UT	< 0.0017 UT	< 0.00056 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.00059 U	< 0.0033 U	< 0.00056 U	< 0.0084 U	< 0.00097 U	< 0.00072 U	< 0.0030 U	< 0.0010 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0033 U	< 0.00038 U	< 0.00028 U	< 0.0012 U	< 0.00039 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00067 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.00033 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.00045 UT	< 0.0025 UT	< 0.00042 UT	< 0.0064 U	< 0.00074 UT	< 0.00055 UT	< 0.0023 UT	< 0.00076 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00063 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	0.035	< 0.00058 U	0.016	< 0.0018 U	< 0.00060 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00042 U	< 0.0063 U	< 0.00073 U	< 0.00054 U	< 0.0023 U	< 0.00075 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.00024 U	< 0.0014 UT	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00027 U	< 0.0015 UT	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 U	< 0.0022 U	< 0.0023 UT	< 0.0017 U	< 0.0013 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0020 U	< 0.0016 UT	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 UT	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0019 U	< 0.0015 UT	< 0.0025 U	< 0.0069 U	< 0.0023 U	< 0.0024 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 UT	< 0.0018 U	< 0.0014 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 UT	< 0.0016 U	< 0.0013 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 UT	< 0.0017 U	< 0.0014 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 UT	< 0.0018 U	< 0.0014 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	0.0073	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.00049 U	< 0.0028 U	< 0.00046 U	< 0.0069 U	< 0.00081 U	< 0.00059 U	< 0.0025 U	< 0.00083 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00039 U	< 0.0059 U	< 0.00068 U	< 0.00050 U	< 0.0021 U	< 0.00070 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.00038 U	< 0.0021 U	< 0.00036 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 UT	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	0.00043 J	< 0.00020 U	< 0.00028 U	0.00034 J	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	0.00032 J	< 0.00019 U	< 0.00027 U	0.00026 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	0.00045 J	< 0.00019 U	< 0.00027 U	0.00032 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.00033 J	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	0.00029 J	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00024 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.00030 UT	< 0.00023 U	< 0.00033 UT	< 0.00026 UT	< 0.00020 UT	< 0.00039 UT	< 0.00025 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.00054 U	< 0.00042 U	< 0.00059 U	< 0.00046 U	< 0.00035 U	< 0.00070 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	0.00045 J	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	0.00026 J	< 0.00016 U	< 0.00023 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.00037 U	< 0.00029 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	0.00071 J	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.00041 UT	< 0.00032 UT	< 0.00045 UT	< 0.00035 UT	< 0.00027 UT	< 0.00053 UT	< 0.00035 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00045 U	< 0.00030 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	0.0013	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.00041 U	< 0.00032 U	< 0.00045 U	< 0.00034 U	< 0.00027 U	< 0.00053 U	< 0.00034 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	0.0027 J	< 0.0030 UT	< 0.0028 UT	< 0.0018 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	0.0011	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	0.00033 J	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00024 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.00045 U	< 0.00035 U	< 0.00049 U	< 0.00038 U	< 0.00029 U	< 0.00058 U	< 0.00038 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	0.00024 J	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00042 U	0.00045 J	< 0.00025 U	< 0.00049 U	< 0.00032 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	0.00025 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00033 U	0.00033 J	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.00030 UT	< 0.00023 UT	< 0.00033 UT	< 0.00025 UT	< 0.00019 U	< 0.00038 UT	< 0.00025 UT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417-20220705	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated	< 0.00016 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419-20220705	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420-20220705	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151-20220708	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150-20220708	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1-20220708	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4-20220708	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7-20220708	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421-20220708	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422-20220708	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 UT	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423-20220708	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424-20220708	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 UT	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425-20220708	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426-20220708	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427-20220708	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428-20220708	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated	< 0.00019 UT	< 0.00035 UT	< 0.00044 UT	< 0.00060 UT	< 0.00019 UT	< 0.00021 UT	< 0.00019 UT
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429-20220708	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 UT	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A-20220708	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated	< 0.00035 U	< 0.00063 U	< 0.00079 U	< 0.0011 UT	< 0.00034 U	< 0.00038 U	< 0.00034 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155-20220711	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3-20220711	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5-20220711	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7-20220711	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9-20220711	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00031 U	< 0.00042 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11-20220711	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13-20220711	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15-20220711	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17-20220711	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00054 U	< 0.00073 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19-20220711	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21-20220711	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23-20220711	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated	< 0.00026 UT	< 0.00048 UT	< 0.00060 UT	< 0.00081 UT	< 0.00026 UT	< 0.00029 UT	< 0.00026 UT
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27-20220711	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00069 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29-20220711	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	0.00052 J	< 0.00023 U	0.00052 J
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33-20220711	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00060 U	< 0.00080 U	< 0.00026 U	< 0.00029 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37-20220711	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22-20220712	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 0.0011 U	0.0017 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161-20220713	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445-20220713	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166-20220714	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00018 UT	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454-20220714	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455-20220714	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00020 U	< 0.00017 U
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462-20220714	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465-20220714	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426-20220714	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427-20220714	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428-20220714	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated	< 0.00017 UT	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168-20220722	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167-20220722	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602-20220722	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603-20220722	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605-20220722	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 0.00098 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606-20220722	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607-20220722	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608-20220722	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172-20220725	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174-20220725	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609-20220725	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610-20220725	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611-20220725	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612-20220725	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613-20220725	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614-20220725	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615-20220725	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	0.00015 J	< 0.00017 U	0.00015 J
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-FL-PIPE24-S8-20220725	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated	< 0.00029 U	< 0.00052 U	< 0.00066 U	< 0.00088 U	< 0.00028 U	< 0.00031 U	< 0.00028 U
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616-20220725	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617-20220725	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00035 U	< 0.00048 U	0.00017 J	< 0.00017 U	0.00017 J
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618-20220725	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated	< 0.00024 U	< 0.00044 U	< 0.00056 U	< 0.00075 U	0.00027 J	< 0.00027 U	0.00027 J
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT-20220725	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT-20220725	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT-20220725	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00054 U	< 0.00072 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5-20220725	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9-20220725	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607-20220726	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00049 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608-20220726	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609-20220726	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated	< 0.00019 UT	< 0.00034 U	< 0.00043 UT	< 0.00058 U	< 0.00019 UT	< 0.00021 UT	< 0.00019 UT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 UT	< 0.00040 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	0.032	0.0012 J	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	0.0077	< 0.00051 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	0.0084	< 0.00021 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	0.0096	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	0.0027	< 0.00033 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00078 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 U	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 UT	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.0072 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.0093 U	< 0.00042 U	< 0.00046 U	< 0.00042 U	< 0.00069 U	< 0.0016 U	< 0.00043 U	< 0.00063 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0041 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00071 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0011 U	< 0.00031 U	< 0.00044 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.0070 U	< 0.00032 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00033 U	< 0.00047 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	0.0081	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	0.0060	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	0.0064	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 UT
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 UT
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00069 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.0022 U	< 0.000099 U	< 0.00011 U	< 0.000098 U	< 0.00016 U	< 0.00038 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.0054 U	0.00026 J	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.0078 U	0.00065 J	< 0.00038 U	< 0.00035 U	< 0.00058 U	< 0.0014 U	< 0.00036 U	< 0.00053 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.0054 U	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00019 U	< 0.00018 U	< 0.00029 U	< 0.00069 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	0.0055	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00029 U	< 0.00068 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	0.11	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	0.00023 J	< 0.00033 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	0.12	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	0.00099 J	< 0.00040 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	0.0082	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00081 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	0.025	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	0.09	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	0.032	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00042 U	< 0.00077 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00044 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.00021 UT	< 0.00024 UT	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.00022 U	< 0.00025 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	< 0.00028 U	< 0.00058 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.00029 U	< 0.00031 U	< 0.00085 U	< 0.0016 U	< 0.00071 U	< 0.00036 U	< 0.00075 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00037 U	< 0.00069 U	< 0.00031 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.000096 U	< 0.00011 U	< 0.00028 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.000068 U	< 0.000074 U	< 0.00020 U	< 0.00037 U	< 0.00017 U	< 0.000085 U	< 0.00018 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	0.00030 J	< 0.00043 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.000096 U	< 0.00010 U	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00071 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00062 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00036 U	< 0.00067 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.000097 U	< 0.00011 U	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00066 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	0.00036 J	< 0.00039 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	0.0014 J	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	0.0011 J	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.0014 U	< 0.00022 UT	< 0.00041 U	< 0.00044 UT	< 0.00044 UT	< 0.00027 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.0019 U	< 0.00029 U	< 0.00055 U	< 0.00059 U	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00082 U	< 0.00013 U	< 0.00024 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00062 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 UT	< 0.00021 UT	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 UT	< 0.00020 UT	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 UT	< 0.00021 UT	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 UT	< 0.00021 UT	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 UT	< 0.00024 UT	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 UT	< 0.00022 UT	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 UT	< 0.00023 UT	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.00079 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.00044 U	< 0.000069 U	< 0.00013 U	< 0.00014 U	< 0.00014 U	< 0.000086 U	< 0.000079 U	< 0.00011 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.00062 U	< 0.000097 U	< 0.00018 U	< 0.00019 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.0016 U	< 0.00024 U	< 0.00046 U	< 0.00049 U	< 0.00050 U	< 0.00031 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00079 U	< 0.00012 U	< 0.00023 U	< 0.00025 U	< 0.00025 U	< 0.00016 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00063 U	< 0.000099 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.00078 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.0012 U	< 0.00018 UT	< 0.00034 U	< 0.00036 UT	< 0.00037 UT	< 0.00023 UT	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	0.0010 J	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0044 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.00030 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 UT	< 0.00021 UT	< 0.00016 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 UT	< 0.00028 UT	< 0.00021 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 UT	< 0.00032 UT	< 0.00024 UT
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.00036 U	< 0.00062 U	< 0.00058 U	< 0.00040 U	< 0.00069 U	< 0.00044 U	< 0.00043 U	< 0.00032 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00026 U	< 0.00018 U	< 0.00030 U	< 0.00020 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00033 U	< 0.00033 U	< 0.00024 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.00016 U	< 0.00026 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.000086 U	< 0.00015 U	< 0.00014 U	< 0.000094 U	< 0.00016 U	< 0.00010 U	< 0.00010 U	< 0.000076 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.00031 U	< 0.00052 U	< 0.00049 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00016 U	< 0.00026 U	< 0.00025 U	< 0.00017 U	< 0.00029 U	< 0.00019 U	< 0.00018 U	< 0.00014 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	0.00022 J
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.00030 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.00040 U	< 0.0022 U	< 0.00037 U	< 0.0057 U	< 0.00066 U	0.0040 J	< 0.0020 U	< 0.00067 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0014 U	< 0.00044 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 UT	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 UT	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 UT	< 0.0052 UT	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 UT
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0054 U	< 0.00063 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.00049 U	< 0.0028 U	< 0.00046 U	< 0.0070 U	0.0011 J	< 0.00060 U	< 0.0025 U	< 0.00083 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00022 U	< 0.0012 UT	< 0.00020 U	< 0.0031 U	< 0.00036 U	< 0.00026 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00029 U	< 0.0016 UT	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.00030 U	< 0.0017 UT	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00016 U	< 0.00093 UT	< 0.00016 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00035 U	< 0.0020 UT	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.00026 U	< 0.0015 UT	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.00027 U	< 0.0016 UT	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.00031 U	< 0.0018 UT	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.00033 U	< 0.0019 UT	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.00037 U	< 0.0021 UT	< 0.00035 U	< 0.0053 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00035 U	< 0.0020 UT	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.00012 U	< 0.00066 U	< 0.00011 U	< 0.0016 U	< 0.00019 U	< 0.00014 U	< 0.00060 U	< 0.00020 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.00016 U	< 0.00092 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00084 U	< 0.00028 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00039 U	< 0.0058 U	< 0.00068 U	< 0.00050 U	< 0.0021 U	< 0.00070 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00086 U	< 0.00028 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.00020 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.00025 U	0.0038 J	< 0.00024 U	< 0.0036 U	< 0.00042 U	0.028	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.00031 U	0.0024 J	< 0.00029 U	< 0.0044 U	< 0.00051 U	0.028	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	0.0077	< 0.0021 U	< 0.00068 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	0.0099	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	0.0011 J	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	0.00022 J	< 0.00014 U	< 0.00028 U	< 0.00019 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00036 J	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	0.00043 J	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.00034 UT	< 0.00026 UT	< 0.00037 UT	< 0.00028 UT	< 0.00022 U	< 0.00043 UT	< 0.00028 U
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.84	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00039 U	0.00038 J	< 0.00023 U	< 0.00045 U	< 0.00030 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.00045 U	< 0.00035 U	< 0.00049 U	< 0.00038 U	< 0.00029 U	< 0.00058 U	< 0.00038 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00020 U	< 0.00015 U	< 0.00022 U	0.00027 J	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00033 J	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	0.00049 J	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	0.00061	< 0.00012 U	< 0.00017 U	0.00013 J	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 UT	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	0.00055 J	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 UT	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	0.00051 J	< 0.00020 U	< 0.00028 U	0.00043 J	< 0.00016 UT	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	0.00050 J	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00038 J	< 0.00019 UT	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 UT	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	0.00075 J	< 0.00026 U	< 0.00037 U	0.00041 J	< 0.00022 UT	< 0.00044 U	< 0.00029 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	0.00039 J	< 0.00021 UT	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	0.00069 J	< 0.00019 U	< 0.00028 U	0.00025 J	< 0.00016 UT	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00023 J	< 0.00017 UT	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 UT	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 UT	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 UT	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00053 J	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.00032 J	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 UT
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 UT
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.00011 U	< 0.000082 U	< 0.00012 U	< 0.000090 U	< 0.000069 U	< 0.00014 U	< 0.000089 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	0.00054 J	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00016 U	< 0.00013 U	< 0.000098 U	< 0.00019 U	< 0.00013 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.00040 J	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00041 U	0.0014	< 0.00025 U	< 0.00049 U	< 0.00032 U
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00019 U	< 0.00015 U	< 0.00021 U	< 0.00016 U	< 0.00013 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	0.00020 J	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.00019 U	< 0.00014 U	< 0.00021 U	0.00033 J	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	0.00030 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00031 J	< 0.00018 U	< 0.00036 UT	< 0.00023 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U

DRAFT

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610-20220726	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611-20220726	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613-20220726	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614-20220726	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00072 U	0.00045 J	< 0.00026 U	0.00045 J
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615-20220726	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616-20220726	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00046 U	0.00015 J	< 0.00017 U	0.00015 J
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619-20220726	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A-20220729	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A-20220729	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619-20220808	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated	< 0.00022 UT	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 UT	< 0.00024 UT	< 0.00021 UT
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620-20220808	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT-20220809	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621-20220809	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00051 U	< 0.00069 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622-20220809	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25-20220809	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated	< 0.00029 U	< 0.00052 U	< 0.00066 U	< 0.00089 U	< 0.00028 U	< 0.00031 U	< 0.00028 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189-20220810	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00039 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1-20220810	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A-20220810	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT-20220810	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated	< 0.00018 U	0.00088 J	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651-20220810	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated	< 0.000097 U	< 0.00017 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190-20220811	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192-20220811	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655-20220811	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656-20220811	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657-20220811	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658-20220811	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659-20220811	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660-20220811	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661-20220811	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666-20220811	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00050 U	< 0.00067 U	< 0.00021 U	< 0.00024 U	< 0.00021 U
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667-20220811	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A-20220811	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670-20220811	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671-20220811	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	0.00020 J	< 0.00018 U	0.00020 J
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674-20220811	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675-20220811	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676-20220811	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681-20220812	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682-20220812	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	0.00025 J	< 0.00020 U	0.00025 J
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683-20220812	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1-20220817	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430811	Not Excavated	< 0.00019 U	0.0012	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2-20220817	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430811	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404-20220822	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409-20220823	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated	< 0.000068 U	< 0.00012 U	< 0.00016 U	< 0.00021 U	< 0.000067 U	< 0.000074 U	< 0.000067 U
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402-20220823	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403-20220823	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	0.00025 J	< 0.00018 U	0.00025 J
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404-20220823	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400-20220824	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated	< 0.000096 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000094 U	< 0.00010 U	< 0.000094 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603-20220824	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401-20220824	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402-20220824	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated	< 0.00020 U	0.00040 J	< 0.00045 U	< 0.00061 U	0.00020 J	< 0.00022 U	0.00020 J
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403-20220824	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated	< 0.00024 U	< 0.00044 U	< 0.00055 U	< 0.00074 U	0.00068 J	< 0.00026 U	0.00068 J
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604-20220824	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705-20220825	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706-20220825	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212-20220901	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412-20220901	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated	< 0.000098 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000096 U	< 0.00011 U	< 0.000096 U
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413-20220901	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00027 U	< 0.00037 U	0.00015 J	< 0.00013 U	0.00015 J
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414-20220901	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415-20220901	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	0.00019 J	< 0.00017 U	0.00019 J
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416-20220901	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	0.00020 J	< 0.00020 U	0.00020 J
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417-20220901	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407-20220901	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408-20220901	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409-20220901	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00054 U	< 0.00072 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410-20220901	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411-20220901	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	0.00017 J	< 0.00018 U	0.00017 J
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217-20220902	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413-20220902	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated	< 0.00098 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414-20220902	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415-20220902	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416-20220902	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0020 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.0035 U	< 0.0012 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.0037 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	0.026	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	0.0050	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 UT	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 UT	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 UT	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00023 U	< 0.00021 U	< 0.00035 UT	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220908	SSHS-IRM5A2-A6-B422	9/8/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801442121	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220908	SSHS-IRM5A2-A6-B423	9/8/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801442121	Not Excavated	< 0.0054 U	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 UT	< 0.00070 U	< 0.00019 UT	< 0.00027 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.0044 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00077 U	< 0.00020 U	< 0.00030 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.0074 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	< 0.00035 U	< 0.00050 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	0.00035 J	< 0.00042 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.0072 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.0083 U	< 0.00037 U	< 0.00041 U	< 0.00037 U	< 0.00062 U	< 0.0015 U	< 0.00039 U	< 0.00056 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 UT	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.0041 U	< 0.00018 U	< 0.00020 U	< 0.00018 U	< 0.00030 U	< 0.00071 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	0.0044	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00047 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	0.0056 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	0.019 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	0.053 B	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated							
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated							
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00050 U	< 0.00093 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220908	SSHS-IRM5A2-A6-B422	9/8/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801442121	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220908	SSHS-IRM5A2-A6-B423	9/8/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801442121	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.00012 U	< 0.00014 UT	< 0.00037 U	< 0.00068 U	< 0.00030 U	< 0.00015 U	< 0.00032 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00033 U	< 0.00017 U	< 0.00035 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00068 U	< 0.0013 U	< 0.00056 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	< 0.00028 U	< 0.00058 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.00026 U	< 0.00028 U	< 0.00076 U	< 0.0014 U	< 0.00063 U	< 0.00032 U	< 0.00067 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00052 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00064 U	< 0.00029 U	< 0.00015 U	< 0.00030 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.00018 U	< 0.00019 UT	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00037 U	< 0.00069 U	< 0.00031 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.000088 U	< 0.000097 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.000083 U	< 0.000091 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0034 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	0.0016 J	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220908	SSHS-IRM5A2-A6-B422	9/8/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801442121	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220908	SSHS-IRM5A2-A6-B423	9/8/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801442121	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.00080 U	< 0.00013 U	< 0.00024 UT	< 0.00025 U	< 0.00026 U	< 0.00016 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00088 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00047 U	< 0.00029 U	< 0.00027 U	< 0.00038 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.00043 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00092 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00049 U	< 0.00052 U	< 0.00053 U	< 0.00033 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.00081 U	< 0.00013 U	< 0.00024 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.00057 U	< 0.000090 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00054 U	< 0.000084 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000097 U	< 0.00014 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 UT	< 0.0033 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220908	SSHS-IRM5A2-A6-B422	9/8/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801442121	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220908	SSHS-IRM5A2-A6-B423	9/8/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801442121	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00019 U	< 0.00031 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.00029 U	< 0.00050 U	< 0.00046 U	< 0.00032 U	< 0.00055 U	< 0.00035 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.00033 U	< 0.00055 U	< 0.00052 U	< 0.00036 U	< 0.00061 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000099 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000093 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated								
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220908	SSHS-IRM5A2-A6-B422	9/8/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801442121	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220908	SSHS-IRM5A2-A6-B423	9/8/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801442121	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0033 U	< 0.00038 U	< 0.00028 U	< 0.0012 U	< 0.00039 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0054 U	< 0.00063 U	< 0.00046 U	< 0.0020 U	< 0.00064 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00041 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00060 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00041 U	< 0.0062 U	< 0.00072 U	< 0.00053 U	< 0.0023 U	< 0.00074 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.00021 U	< 0.0012 U	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.00015 U	< 0.00085 U	0.00015 J	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00026 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00014 U	< 0.00080 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00073 U	< 0.00024 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 UT	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 UT	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 UT	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 UT	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0066 U	< 0.0021 UT	< 0.0023 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 UT	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 UT	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 UT	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 UT	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00040 U	0.0031	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00025 U	< 0.00019 U	0.00030 J	0.0049	< 0.00016 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.0035	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.00035 U	< 0.00027 U	0.00075 J	0.0039	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.00031 U	< 0.00024 U	0.0013	0.0081	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.0045	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.0014	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00025 U	0.0028	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.0014	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.0031	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	0.0038	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.00029 U	< 0.00022 U	0.00045 J	0.00085 J	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.00034 U	< 0.00026 U	0.0010 J	0.0099	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.00040 U	< 0.00031 U	< 0.00044 U	0.0042	< 0.00026 U	< 0.00052 U	< 0.00034 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00028 U	< 0.00022 U	0.00069 J	0.0016	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	0.00035 J	< 0.00012 U	< 0.00024 U	< 0.00015 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.0019	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	0.00051 J	< 0.00015 U	< 0.00022 U	0.0021	< 0.00013 U	< 0.00025 U	< 0.00017 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	0.0047	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00014 U	0.00028 J	< 0.000085 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT	< 0.0018 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 UT	< 0.0016 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 UT	< 0.0017 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 UT	< 0.0018 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 UT	< 0.0016 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 UT	< 0.0017 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 UT	< 0.0017 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.0013 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 UT	< 0.0015 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 UT	< 0.0017 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 UT	< 0.0016 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 UT	< 0.0016 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417-20220902	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418-20220902	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419-20220902	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420-20220902	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218-20220906	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421-20220906	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220906	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated							
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220906	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated							
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424-20220906	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425-20220906	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426-20220906	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427-20220906	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428-20220906	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429-20220908	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT-20220908	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616-20220908	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618-20220908	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619-20220908	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422-20220908	SSHS-IRM5A2-A6-B422	9/8/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801442121	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423-20220908	SSHS-IRM5A2-A6-B423	9/8/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801442121	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430-20220909	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00028 U	< 0.00038 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224-20220913	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222-20220913	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223-20220913	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00031 U	< 0.00042 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418-20220913	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00071 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419-20220913	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420-20220913	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421-20220913	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 0.00022 U	0.0029	< 0.00051 U	< 0.00069 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423-20220913	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 0.00020 U	0.00075 J	< 0.00046 U	< 0.00061 U	< 0.00020 U	0.00022 J	0.00022 J
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424-20220913	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425-20220913	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426-20220913	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432-20220913	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433-20220913	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434-20220913	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435-20220913	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436-20220913	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 0.00022 U	0.0027	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT-20220913	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00059 U	< 0.00079 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT-20220913	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 0.00018 U	0.00087 J	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00020 U	< 0.00017 U
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232-20220916	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.00012 U	0.00022 J	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438-20220916	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623-20220916	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00039 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623-20220916	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated	< 0.000089 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000087 U	0.00021 J	0.00021 J
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624-20220916	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated	< 0.000083 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000082 U	< 0.000091 U	< 0.000082 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236-20220927	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430-20220927	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625-20220927	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626-20220927	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625-20220927	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627-20220927	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238-20220929	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239-20220929	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628-20220929	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626-20220929	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627-20220929	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630-20220929	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631-20220929	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632-20220929	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633-20220929	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634-20220929	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635-20220929	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636-20220929	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637-20220929	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638-20220929	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639-20220929	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640-20220929	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641-20220929	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642-20220929	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643-20220929	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644-20220929	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645-20220929	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2-20221011	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221020	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221020	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 UT	< 0.00039 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	0.017	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	0.01	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	0.00027 J	< 0.00037 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 UT	0.00019 J	< 0.00021 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 UT	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 UT	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00058 UT	< 0.00015 U	< 0.00023 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	0.016	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 UT	< 0.0011 UT	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00012 U	< 0.00021 U	< 0.00049 UT	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00047 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0011 U	< 0.00031 U	< 0.00044 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 UT	< 0.00020 UT	< 0.00047 U	< 0.00012 U	< 0.00018 UT
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 UT	< 0.00020 UT	< 0.00047 U	< 0.00013 U	< 0.00018 UT
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.0033 U	0.00042 J	< 0.00016 U	< 0.00015 U	< 0.00025 UT	< 0.00058 U	< 0.00015 U	< 0.00022 UT
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.0030 U	0.00018 J	< 0.00015 U	< 0.00013 U	< 0.00022 UT	< 0.00052 U	< 0.00014 U	< 0.00020 UT
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.0031 U	0.00018 J	< 0.00015 U	< 0.00014 U	< 0.00023 UT	< 0.00053 U	< 0.00014 U	< 0.00021 UT
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 UT	< 0.00061 U	< 0.00016 U	< 0.00024 UT
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00097 U	< 0.00026 U	< 0.00038 UT
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 UT	< 0.0011 U	< 0.00029 U	< 0.00042 UT
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.0058 U	< 0.00026 UT	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.0092 U	< 0.00041 U	< 0.00045 U	< 0.00041 U	< 0.00068 U	< 0.0016 U	< 0.00043 U	< 0.00062 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00079 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00025 U	< 0.00058 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 UT	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 UT	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 UT	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 UT	< 0.00079 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.0048 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.000097 U	< 0.00011 U	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	< 0.00020 UT	< 0.00021 UT	< 0.00058 UT	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.000086 U	< 0.000094 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.000083 U	< 0.000091 U	< 0.00024 U	< 0.00046 U	< 0.00020 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.000083 U	< 0.000091 UT	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.000084 U	< 0.000092 UT	< 0.00025 U	< 0.00046 U	< 0.00021 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.000092 U	< 0.00010 UT	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.000095 U	< 0.00010 UT	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.00018 UT	< 0.00020 UT	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.000097 U	< 0.00011 U	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.000091 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.00021 U	< 0.00022 U	< 0.00061 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.00028 U	< 0.00031 U	< 0.00084 U	< 0.0016 U	< 0.00070 U	< 0.00036 U	< 0.00074 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.00014 U	< 0.00015 UT	< 0.00041 U	< 0.00077 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	0.0019	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.00063 U	< 0.000099 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.00092 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.00067 U	< 0.00010 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 UT	< 0.00040 UT	< 0.00025 UT	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.00056 U	< 0.000088 U	< 0.00016 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.00054 U	< 0.000084 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000097 U	< 0.00014 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00053 U	< 0.000084 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000096 U	< 0.00014 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00054 U	< 0.000085 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000098 U	< 0.00014 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00017 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.00061 U	< 0.000096 U	< 0.00018 U	< 0.00019 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.0012 U	< 0.00018 UT	< 0.00034 U	< 0.00037 UT	< 0.00037 UT	< 0.00023 UT	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00063 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.00074 U	< 0.00012 U	< 0.00022 U	< 0.00023 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.00071 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00017 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.0018 U	< 0.00029 U	< 0.00054 U	< 0.00058 U	< 0.00059 U	< 0.00036 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	0.0017 J	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00020 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00015 U	< 0.00012 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00026 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 UT	< 0.00022 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00017 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000097 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 UT	< 0.00012 UT	< 0.000093 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 UT	< 0.00031 UT	< 0.00023 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000093 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000094 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00025 U	< 0.00016 U	< 0.00015 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 UT	< 0.00043 U	< 0.00028 UT	< 0.00027 UT	< 0.00020 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00017 U	< 0.00012 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00047 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.00036 U	< 0.00061 U	< 0.00058 U	< 0.00040 U	< 0.00068 U	< 0.00044 U	< 0.00043 U	< 0.00032 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00012 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated								
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	0.0032 J	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.00017 U	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00041 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 UT	< 0.0047 UT	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.00015 U	< 0.00083 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.00014 U	< 0.00080 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00073 UT	< 0.00024 UT
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 UT	< 0.00059 UT
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00014 U	< 0.00080 UT	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00073 U	< 0.00024 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00014 U	< 0.00081 UT	< 0.00014 U	< 0.0020 U	< 0.00024 U	< 0.00017 U	< 0.00074 U	< 0.00024 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00099 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00088 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00080 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00092 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00083 U	< 0.00027 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00031 U	< 0.00023 U	< 0.00095 U	< 0.00031 UT
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 UT	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 UT	< 0.00052 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00032 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00097 U	< 0.00032 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00088 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00080 U	< 0.00026 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.00048 U	< 0.0027 U	< 0.00046 U	< 0.0069 U	< 0.00080 U	< 0.00059 U	< 0.0025 U	< 0.00082 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00099 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00090 U	< 0.00030 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated								
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.00028 U	< 0.00022 U	0.00070 J	< 0.00024 U	< 0.00018 U	< 0.00036 U	0.00041 J
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	< 0.00026 U	< 0.00020 U	0.0015	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.00025 U	< 0.00019 U	0.00057 J	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.00016 U	< 0.00012 U	0.00032 J	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.00028 U	< 0.00022 U	0.00043 J	0.0016	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	< 0.00031 UT	< 0.00024 U	0.00036 JT	< 0.00026 U	< 0.00020 U	< 0.00040 UT	< 0.00026 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.00014 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000088 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00014 U	< 0.00011 U	< 0.000085 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00013 U	< 0.00010 U	0.00085	< 0.00011 U	< 0.000084 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.00013 U	< 0.00010 U	0.00020 J	< 0.00011 U	< 0.000086 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00018 U	0.00020 J	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000094 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	< 0.00013 U	< 0.000097 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	0.00016 J	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.00026 J	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	0.00050 J	< 0.00021 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00021 U	< 0.00013 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	0.00045 JT	< 0.00022 U	< 0.00031 U	< 0.00024 UT	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00015 UT	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.00018 UT	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.00017 UT	< 0.00013 U	< 0.00019 U	< 0.00015 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.00014 UT	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000093 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	0.00032 J	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.00037 U	< 0.00028 U	0.00064 J	< 0.00031 U	< 0.00024 U	< 0.00047 U	0.00040 J
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.00045 U	< 0.00034 U	< 0.00049 U	< 0.00038 U	< 0.00029 U	< 0.00058 U	0.00056 J
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.00031 U	< 0.00024 U	0.00041 J	< 0.00026 U	< 0.00020 U	< 0.00040 U	0.00092 J
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.00022 U	< 0.00017 U	0.00071 J	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.00027 U	< 0.00021 U	0.0028	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.00032 U	< 0.00024 U	0.0012	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	0.00030 J	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00018 U	< 0.00014 U	< 0.00010 U	< 0.00021 U	< 0.00013 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 UT	< 0.00019 U	< 0.00015 UT	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 UT	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 UT	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00022 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221020	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221020	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S437-S	SSHS-IRM5A2-A6-S437-S-20221020	SSHS-IRM5A2-A6-S437-S	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221020	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated							
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221020	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221020	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221020	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221020	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221020	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221020	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221020	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221020	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221020	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221020	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221020	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242-20221024	SSHS-IRM5A2-DUP242	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255-20221024	SSHS-IRM5A2-A6-B255	10/24/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801468431	Not Excavated	< 0.00018 U	0.0046	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436-20221024	SSHS-IRM5A2-A6-S436	10/24/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801468431	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437-20221024	SSHS-IRM5A2-A6-S437	10/24/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801468431	Not Excavated	< 0.00017 U	0.00033 J	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438-20221024	SSHS-IRM5A2-A6-S438	10/24/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801468431	Not Excavated	< 0.00016 U	0.00089	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443-20221024	SSHS-IRM5A2-A6-B443	10/24/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801468441	Not Excavated	< 0.000098 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444-20221024	SSHS-IRM5A2-A6-B444	10/24/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801468441	Not Excavated	< 0.00014 U	0.00031 J	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445-20221024	SSHS-IRM5A2-A6-B445	10/24/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801468441	Not Excavated	< 0.00016 U	0.00047 J	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646-20221024	SSHS-IRM5A2-A6-B646	10/24/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801468441	Not Excavated	< 0.00010 U	0.00065	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647-20221024	SSHS-IRM5A2-A6-B647	10/24/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801468441	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631-20221024	SSHS-IRM5A2-A6-S631	10/24/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630-20221024	SSHS-IRM5A2-A6-S630	10/24/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635-20221024	SSHS-IRM5A2-A6-S635	10/24/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801468441	Not Excavated	< 0.00020 U	0.00039 J	< 0.00045 U	< 0.00060 UT	< 0.00019 U	< 0.00021 UT	< 0.00019 U
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636-20221024	SSHS-IRM5A2-A6-S636	10/24/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801468441	Not Excavated	< 0.000087 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000085 U	< 0.000094 U	< 0.000085 U
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637-20221024	SSHS-IRM5A2-A6-S637	10/24/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801468451	Not Excavated	< 0.000083 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000082 U	< 0.000091 U	< 0.000082 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638-20221024	SSHS-IRM5A2-A6-S638	10/24/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801468451	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244-20221025	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.000083 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000081 U	< 0.000091 U	< 0.000081 U
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1-20221025	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated	< 0.000085 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000083 U	< 0.000092 U	< 0.000083 U
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7-20221026	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8-20221026	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated	< 0.000092 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9-20221026	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated	< 0.000095 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000093 U	< 0.00010 U	< 0.000093 U
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10-20221026	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11-20221026	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12-20221026	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT-20221108	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402-20221201	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404-20221201	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227-20221205	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated	< 0.00018 UT	< 0.00032 UT	< 0.00041 U	< 0.00055 U	< 0.00018 UT	< 0.00020 UT	< 0.00018 UT
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267-20221209	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00016 U	0.00039 J	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269-20221209	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00017 U	0.0021	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3-20221209	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.000097 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3-20221209	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00026 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4-20221209	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2-20221209	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated	< 0.000092 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229-20221209	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230-20221209	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231-20221209	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated	< 0.00019 U	0.00040 J	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232-20221209	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated	< 0.00024 U	0.00076 J	< 0.00054 U	< 0.00072 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234-20221209	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237-20221209	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated	< 0.00015 U	0.00059 J	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239-20221209	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated	< 0.00029 U	0.0019	< 0.00065 U	< 0.00088 U	< 0.00028 U	< 0.00031 U	< 0.00028 U
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240-20221209	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated	< 0.00020 U	0.0016	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241-20221209	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated	< 0.00014 U	0.00062 J	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242-20221209	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated	< 0.00017 U	0.0093	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243-20221209	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated	< 0.00020 U	0.0020	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244-20221209	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1-20221209	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4-20221209	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated	< 0.00010 U	0.0016	< 0.00023 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221210	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221210	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221210	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221210	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271-20221212	SSHS-IRM5A2-DUP271	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	0.00064 J	0.00022 J	0.00086 J
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3-20221212	SSHS-IRM5A2-A6N-B213-S3	12/12/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492231	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	0.00018 J	< 0.00018 U	0.00018 J
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4-20221212	SSHS-IRM5A2-A6N-B213-S4	12/12/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492231	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	0.0010 J	0.00045 J	0.0014 J
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT-20221212	SSHS-IRM5A2-A6N-B213-BOT	12/12/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492231	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272-20221214	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12-20221214	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15-20221214	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0040 UT	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0041 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0042 UT	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	0.0044 J	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	0.0063	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	0.0054	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	0.0036 J	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	0.0038 J	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	0.0040 J	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	0.01 J	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0047 UT	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0044 UT	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0045 UT	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0040 UT	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0044 UT	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.0038 UT	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.0039 UT	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 UT	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 UT	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 UT	< 0.0030 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 UT	< 0.0032 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 UT	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 UT	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 UT	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 UT	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 UT	< 0.0031 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 UT
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0014 U	0.0049 J	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0034 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.0013 U	0.0058	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0013 U	0.0051	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0014 U	0.0034 J	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0013 U	0.0041 J	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0015 U	0.0040 J	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0043 U	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0034 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 UT	< 0.0033 UT	< 0.0016 UT	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0049 UT	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.0058 UT	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.0044 UT	< 0.0013 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0054 UT	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0048 UT	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0054 UT	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.0022 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0022 U	< 0.0017 UT	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 UT	< 0.0020 U	< 0.0016 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0022 U	< 0.0017 UT	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 UT	< 0.0020 U	< 0.0016 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0020 U	< 0.0016 UT	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 UT	< 0.0019 U	< 0.0015 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0021 U	< 0.0017 UT	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 UT	< 0.0019 U	< 0.0016 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0022 U	< 0.0017 UT	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 UT	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated								
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0066 U	< 0.0021 U	< 0.0023 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0020 U	< 0.0016 UT	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 UT	< 0.0018 UT	< 0.0015 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0024 U	< 0.0019 UT	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 UT	< 0.0022 UT	< 0.0017 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0021 U	< 0.0017 UT	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 UT	< 0.0019 UT	< 0.0016 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0022 U	< 0.0017 UT	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 UT	< 0.0020 UT	< 0.0016 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0020 U	< 0.0016 UT	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 UT	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0018 U	< 0.0015 UT	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 UT	< 0.0017 UT	< 0.0014 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0021 U	< 0.0016 UT	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 UT	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.0026 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0016 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 UT	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 UT	< 0.00024 U	< 0.00018 UT	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 UT	< 0.00020 U	< 0.00016 UT	< 0.00031 U	< 0.00020 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 UT	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 UT	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 UT	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 UT	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0013 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 UT	< 0.0027 UT	< 0.0018 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	0.0021 J	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18-20221214	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21-20221214	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24-20221214	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1-20230208	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0011 U	< 0.0017 UT	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1-20230208	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated	< 0.0011 U	< 0.0017 UT	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2-20230208	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 0.0010 U	< 0.0016 UT	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3-20230208	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 UT	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4-20230208	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 0.0010 U	< 0.0017 UT	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1-20230208	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 0.0011 U	< 0.0017 UT	< 0.0045 U	< 0.0039 UT	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230227	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230227	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated							
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A-20230228	SSHS-IRM5A2-A6-B267A	2/28/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801527601	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A-20230228	SSHS-IRM5A2-A6-B268A	2/28/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801527601	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0040 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP-20230523	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	LP2-1	ISMP-LP2-1-20230523	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	LP2-2	ISMP-LP2-2-20230523	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	LP2-3	ISMP-LP2-3-20230523	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	LP2-4	ISMP-LP2-4-20230523	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	LP2-5	ISMP-LP2-5-20230523	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	LP1-1	ISMP-LP1-1-20230523	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	LP1-2	ISMP-LP1-2-20230523	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	LP1-3	ISMP-LP1-3-20230523	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	LP1-4	ISMP-LP1-4-20230523	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	LP1-5	ISMP-LP1-5-20230523	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2-20230530	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 UT	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3-20230530	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 UT	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303-20230606	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1-20230606	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4-20230606	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5-20230606	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1-20230606	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2-20230606	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 0.00091 U	< 0.0015 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT-20230606	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3-20230710	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5-20230710	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6-20230710	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7-20230710	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	853.81	-	848.14	4 - 6 ft	5.67 ft	1801589971	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A-20230711	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A-20230711	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A-20230711	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8-20230711	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9-20230711	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11-20230711	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12-20230711	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14-20230711	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16-20230711	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4-20230711	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5-20230711	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6-20230711	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18-20230711	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20-20230711	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23-20230711	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25-20230711	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7-20230711	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8-20230711	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27-20230711	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32-20230711	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34-20230711	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9-20230711	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A-20230717	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A-20230717	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37-20230717	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39-20230717	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 0.00098 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42-20230717	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43-20230717	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45-20230717	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11-20230717	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12-20230717	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13-20230717	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47-20230717	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48-20230717	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49-20230717	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50-20230717	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51-20230717	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0054 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0035 U	< 0.0031 U	< 0.0055 U	< 0.0028 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated								
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0031 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0027 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	0.0057 J	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.0040 U	< 0.0046 U	< 0.0027 U	< 0.0033 U	< 0.0044 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0042 U	< 0.0025 U	< 0.0030 U	< 0.0040 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated							
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0044 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0040 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0044 U	< 0.0026 U	< 0.0031 U	< 0.0042 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0038 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0041 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0040 U	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0062 U	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.0021 U	< 0.0022 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0056 U	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated								
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0059 U	< 0.0018 U	< 0.0033 UT	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0031 U	< 0.0056 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.0030 U	< 0.0031 U	< 0.0025 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0028 U	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated								
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0029 U	< 0.0053 UT	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0022 U	< 0.0040 UT	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0025 U	< 0.0044 UT	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0026 U	< 0.0048 UT	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0027 U	< 0.0049 UT	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0027 U	< 0.0048 UT	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0030 U	< 0.0053 UT	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0024 U	< 0.0044 UT	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0024 U	< 0.0043 UT	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0027 U	< 0.0049 UT	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0026 U	< 0.0048 UT	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0028 U	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0033 U	< 0.0035 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated								
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 UT	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 UT	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 UT	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 UT	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0023 U	< 0.0018 UT	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 UT	< 0.0017 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0026 UT	< 0.0020 U	< 0.0034 U	< 0.0096 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0020 UT	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0022 UT	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0024 UT	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0024 UT	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0026 UT	< 0.0021 U	< 0.0034 U	< 0.0096 U	< 0.0032 U	< 0.0033 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0021 UT	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0021 UT	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0024 UT	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0023 UT	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0021 U	< 0.0021 U	< 0.0028 U	< 0.0020 U	< 0.0038 U	< 0.0035 U	< 0.0023 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.18	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated							
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52-20230717	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0074 U
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14-20230717	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15-20230717	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A-20230718	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A-20230718	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55-20230718	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56-20230718	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57-20230718	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58-20230718	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0057 U	< 0.0050 U	< 0.0024 U	< 0.0028 U	< 0.0099 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17-20230718	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61-20230718	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62-20230718	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63-20230718	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59-20230718	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60-20230718	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18-20230718	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19-20230718	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69-20230718	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70-20230718	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71-20230718	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72-20230718	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21-20230718	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22-20230718	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A-20230720	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78-20230720	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79-20230720	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25-20230720	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26-20230720	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A-20230721	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87-20230721	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88-20230721	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32-20230721	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89-20230725	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91-20230725	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92-20230725	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33-20230725	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34-20230725	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230814	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated							
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2-20230814	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3-20230814	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2-20230814	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B-20230815	SSHS-IRM5A2-AREAF-S1B	8/15/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801608961	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7-20230818	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314-20230829	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32-20230829	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33-20230829	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35-20230829	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36-20230829	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37-20230829	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38-20230829	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0013 U	< 0.0021 U	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39-20230829	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41-20230829	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43-20230829	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44-20230829	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45-20230829	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 UT	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A-20231009	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A-20231009	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1-20231009	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2-20231009	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3-20231009	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4-20231009	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1-20231009	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1-20231009	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2-20231009	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3-20231009	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4-20231009	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1-20231009	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8-20231101	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 UT	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32-20231107	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 UT	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33-20231107	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35-20231107	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17-20231107	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18-20231107	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 UT	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329-20231116	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.023 U	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.011 U	< 0.0057 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.0054	< 0.00073	< 0.00074	< 0.00061	< 0.00048	< 0.0008	< 0.00055	< 0.00048
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.0051	< 0.00069	< 0.00071	< 0.00058	< 0.00045	< 0.00076	< 0.00053	< 0.00046
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.0056	< 0.00076	< 0.00077	< 0.00063	< 0.0005	< 0.00083	< 0.00058	< 0.0005
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.005	< 0.00067	< 0.00068	< 0.00056	< 0.00044	< 0.00073	< 0.00051	< 0.00044
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated						
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.00082	< 0.00077	< 0.0017	< 0.00063	< 0.00092	< 0.0004	< 0.00081
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.00078	< 0.00073	< 0.0016	< 0.0006	< 0.00088	< 0.00038	< 0.00077
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.00085	< 0.0008	< 0.0017	< 0.00066	< 0.00096	< 0.00042	< 0.00084
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.00075	< 0.00071	< 0.0015	< 0.00058	< 0.00085	< 0.00037	< 0.00074
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.0057 U			< 0.37 U	< 0.37 U	< 0.37 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.00073	< 0.00093	< 0.00072	< 0.00086	< 0.00071	< 0.00069	< 0.00062	< 0.00066
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.00069	< 0.00089	< 0.00068	< 0.00082	< 0.00067	< 0.00065	< 0.00059	< 0.00063
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.00076	< 0.00097	< 0.00075	< 0.0009	< 0.00074	< 0.00072	< 0.00065	< 0.00069
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.00067	< 0.00086	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.00061
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-28	082919 09:10_SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50_4-7	13 Sep 00B50_4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.0057 U		< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.00092		< 0.00076	< 0.00064	< 0.00059	< 0.00073	< 0.00065	< 0.0007
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.00087		< 0.00072	< 0.00061	< 0.00056	< 0.0007	< 0.00061	< 0.00066
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.00095		< 0.00079	< 0.00067	< 0.00061	< 0.00076	< 0.00067	< 0.00072
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.00084		< 0.0007	< 0.00059	< 0.00054	< 0.00067	< 0.00059	< 0.00064
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	082919 09:10_SSHS-DUP-28	082919 09:10_SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated								
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated								
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.0057 U	< 0.011 U				< 0.011 U	< 0.011 U	
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.0012	< 0.00075	< 0.00073	< 0.00098	< 0.00078	< 0.00095	< 0.00071	< 0.00081
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.0011	< 0.00071	< 0.0007	< 0.00093	< 0.00075	< 0.00091	< 0.00067	< 0.00077
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.0012	< 0.00078	< 0.00076	< 0.001	< 0.00082	< 0.00099	< 0.00073	< 0.00084
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.0011	< 0.00069	< 0.00068	< 0.0009	< 0.00072	< 0.00088	< 0.00065	< 0.00074
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated						
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U		< 0.37 U	< 0.0057 U
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.00076	< 0.00078	< 0.00074	< 0.00079	< 0.00091	< 0.00095	< 0.00053
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.00073	< 0.00074	< 0.0007	< 0.00075	< 0.00087	< 0.00091	< 0.0005
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.00079	< 0.00081	< 0.00077	< 0.00082	< 0.00095	< 0.00099	< 0.00055
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.0007	< 0.00071	< 0.00068	< 0.00073	< 0.00084	< 0.00088	< 0.00048
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-S3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2-20231116	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4-20231116	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6-20231116	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated							
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1-20231116	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3-20231116	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7-20231116	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8-20231116	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331-20231130	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11-20231130	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15-20231130	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19-20231130	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24-20231201	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25-20231201	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7-20231201	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8-20231201	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2-20231208	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 UT	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3-20231208	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8-20231208	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 UT	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1-20231208	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 UT	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B50	13 SEP 00B50 4-7	13 Sep 00B50 4-7	9/13/2000	854.58	857.45	2.87	--	4 - 7 ft	6.87-9.87 ft	NA	Not Excavated	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	< 0.0057 U	
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated	< 0.0009	< 0.00071	< 0.00099	< 0.00051		< 0.00084	
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated	< 0.00085	< 0.00068	< 0.00094	< 0.00048		< 0.0008	
Northern Athletic Field	SSHS-B77	081514 01:15 DUP-19	081514 01:15 DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated	< 0.00094	< 0.00074	< 0.001	< 0.00053		< 0.00088	
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated	< 0.00083	< 0.00065	< 0.00091	< 0.00047		< 0.00078	
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-6-8	SSHS-B572-SUB-6-8	8/30/2016	852.49	854.82	2.33	-	6 - 8 ft	8.33-10.33 ft	180-58129-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-6-8	SSHS-B2030-SUB-6-8	7/27/2018	856.20	856.42	0.22	-	6 - 8 ft	6.22-8.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-6-8	SSHS-B3008-SUB-6-8	8/26/2019	852.37	854.67	2.30	-	6 - 8 ft	8.3-10.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-6-8	SSHS-B3022-SUB-6-8	8/26/2019	853.76	855.66	1.90	-	6 - 8 ft	7.9-9.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-6-8	SSHS-B3034-SUB-6-8	8/26/2019	855.10	856.53	1.43	-	6 - 8 ft	7.43-9.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-6-8	SSHS-B3035-SUB-6-8	8/26/2019	854.81	856.27	1.46	-	6 - 8 ft	7.46-9.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-6-8	SSHS-B3049-SUB-6-8	8/26/2019	856.17	857.50	1.33	-	6 - 8 ft	7.33-9.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-6-8	SSHS-B3050-SUB-6-8	8/26/2019	855.60	856.84	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-6-8	SSHS-B3064-SUB-6-8	8/26/2019	856.77	857.84	1.07	-	6 - 8 ft	7.07-9.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-6-8	SSHS-B3065-SUB-6-8	8/26/2019	856.77	857.30	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-6-8	SSHS-B3078-SUB-6-8	8/26/2019	856.70	857.12	0.42	-	6 - 8 ft	6.42-8.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-6-8	SSHS-B3098-SUB-6-8	8/26/2019	855.97	857.05	1.08	-	6 - 8 ft	7.08-9.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-6-8	SSHS-B3099-SUB-6-8	8/26/2019	856.40	856.53	0.13	-	6 - 8 ft	6.13-8.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-6-8	SSHS-B3006-SUB-6-8	8/27/2019	852.36	852.39	0.03	-	6 - 8 ft	6.03-8.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-6-8	SSHS-B3007-SUB-6-8	8/27/2019	852.58	854.74	2.16	-	6 - 8 ft	8.16-10.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-6-8	SSHS-B3018-SUB-6-8	8/27/2019	853.82	854.59	0.77	-	6 - 8 ft	6.77-8.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-6-8	SSHS-B3019-SUB-6-8	8/27/2019	854.09	855.31	1.22	-	6 - 8 ft	7.22-9.22 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-6-8	SSHS-B3020-SUB-6-8	8/27/2019	853.86	855.74	1.88	-	6 - 8 ft	7.88-9.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-6-8	SSHS-B3031-SUB-6-8	8/27/2019	855.08	855.61	0.53	-	6 - 8 ft	6.53-8.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-6-8	SSHS-B3032-SUB-6-8	8/27/2019	855.25	856.15	0.90	-	6 - 8 ft	6.9-8.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-6-8	SSHS-B3033-SUB-6-8	8/27/2019	855.17	856.58	1.41	-	6 - 8 ft	7.41-9.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-6-8	SSHS-B3046-SUB-6-8	8/27/2019	856.22	856.03	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-6-8	SSHS-B3047-SUB-6-8	8/27/2019	856.24	856.75	0.51	-	6 - 8 ft	6.51-8.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-6-8	SSHS-B3048-SUB-6-8	8/27/2019	856.08	857.32	1.24	-	6 - 8 ft	7.24-9.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-6-8	SSHS-B3061-SUB-6-8	8/27/2019	857.02	856.09	-0.93	-	6 - 8 ft	5.07-7.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-6-8	SSHS-B3062-SUB-6-8	8/27/2019	856.91	856.86	-0.05	-	6 - 8 ft	5.95-7.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-6-8	SSHS-B3074-SUB-6-8	8/27/2019	857.18	856.02	-1.16	-	6 - 8 ft	4.84-6.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-6-8	SSHS-B3096-SUB-6-8	8/27/2019	855.86	856.29	0.43	-	6 - 8 ft	6.43-8.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-6-8	SSHS-B3097-SUB-6-8	8/27/2019	856.19	856.93	0.74	-	6 - 8 ft	6.74-8.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-6-8	SSHS-B3017-SUB-6-8	8/28/2019	853.78	853.15	-0.63	-	6 - 8 ft	5.37-7.37 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-6-8	SSHS-B3029-SUB-6-8	8/28/2019	854.97	853.59	-1.38	-	6 - 8 ft	4.62-6.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-6-8	SSHS-B3030-SUB-6-8	8/28/2019	855.22	855.02	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-6-8	SSHS-B3043-SUB-6-8	8/28/2019	855.78	856.62	0.84	-	6 - 8 ft	6.84-8.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-6-8	SSHS-B3044-SUB-6-8	8/28/2019	856.00	854.20	-1.80	-	6 - 8 ft	4.2-6.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-6-8	SSHS-B3045-SUB-6-8	8/28/2019	856.03	855.07	-0.96	-	6 - 8 ft	5.04-7.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-6-8	SSHS-B3057-SUB-6-8	8/28/2019	856.09	857.58	1.49	-	6 - 8 ft	7.49-9.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-6-8	SSHS-B3058-SUB-6-8	8/28/2019	856.47	856.55	0.08	-	6 - 8 ft	6.08-8.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-6-8	SSHS-B3059-SUB-6-8	8/28/2019	856.71	854.42	-2.29	-	6 - 8 ft	3.71-5.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-6-8	SSHS-B3060-SUB-6-8	8/28/2019	856.96	855.38	-1.58	-	6 - 8 ft	4.42-6.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-6-8	SSHS-B3070-SUB-6-8	8/28/2019	856.51	857.05	0.54	-	6 - 8 ft	6.54-8.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-6-8	SSHS-B3071-SUB-6-8	8/28/2019	856.76	856.63	-0.13	-	6 - 8 ft	5.87-7.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-6-8	SSHS-B3072-SUB-6-8	8/28/2019	856.89	856.00	-0.89	-	6 - 8 ft	5.11-7.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	082919 09:10 SSHS-DUP-28	082919 09:10 SSHS-DUP-28	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94903-1	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-6-8	SSHS-B3073-SUB-6-8	8/28/2019	857.14	855.25	-1.89	-	6 - 8 ft	4.11-6.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-6-8	SSHS-B3095-SUB-6-8	8/28/2019	857.12	856.70	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-6-8	SSHS-B3004-SUB-6-8	8/29/2019	852.25	853.25	1.00	-	6 - 8 ft	7-9 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-6-8	SSHS-B3005-SUB-6-8	8/29/2019	852.31	852.62	0.31	-	6 - 8 ft	6.31-8.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-6-8	SSHS-B3040-SUB-6-8	8/29/2019	855.10	858.65	3.55	-	6 - 8 ft	9.55-11.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-6-8	SSHS-B3041-SUB-6-8	8/29/2019	855.17	858.67	3.50	-	6 - 8 ft	9.5-11.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-6-8	SSHS-B3054-SUB-6-8	8/29/2019	856.01	856.77	0.76	-	6 - 8 ft	6.76-8.76 ft	180-95024-2	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.0057 U	< 0.00047 U	< 0.00057 U	< 0.00038 U	< 0.0047 U	< 0.00066 U	< 0.00057 U	< 0.00047 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.032 U	< 0.021 U	< 0.27 U	< 0.038 U,*+	< 0.032 U	< 0.11 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	0.031 H	< 0.00049 U,H	< 0.00059 U,H	< 0.00039 U,H	< 0.0049 U,H	< 0.00069 U,H	< 0.00059 U,H	< 0.00049 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.32 U	< 0.027 U	< 0.032 U	< 0.021 U	< 0.27 U	< 0.037 U,*+	< 0.032 U	< 0.11 U
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.0077 U	< 0.00065 U	< 0.00077 U	< 0.00052 U	< 0.0065 U	< 0.0009 U	< 0.00077 U	< 0.00065 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.00047 U	< 0.00047 U	< 0.00095 U	< 0.00057 U	< 0.00057 U	< 0.00047 U	< 0.00047 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.027 U	< 0.11 U	< 0.054 U	< 0.032 U	< 0.032 U	< 0.027 U	< 0.054 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	< 0.00049 U,H	< 0.00049 U,H	< 0.00098 U,H	< 0.00059 U,H	< 0.00059 U,H	< 0.00049 U,H	< 0.00049 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.027 U	< 0.11 U	< 0.053 U	< 0.032 U	< 0.032 U	< 0.027 U	< 0.053 U
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.00065 U	< 0.00065 U	< 0.0013 U	< 0.00077 U	< 0.00077 U	< 0.00065 U	< 0.00065 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated						

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0038 U	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.0019 U	< 0.00038 U	< 0.00057 U	< 0.00047 U	< 0.00047 U	< 0.00038 U	< 0.00047 U	< 0.00057 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.11 U	< 0.021 U	< 0.032 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U	< 0.032 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	< 0.002 U,H	< 0.00039 U,H	< 0.00059 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00039 U,H	< 0.00049 U,H	< 0.00059 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.11 U	< 0.021 U	< 0.032 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U	< 0.032 U
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.0026 U	< 0.00052 U	< 0.00077 U	< 0.00065 U	< 0.00065 U	< 0.00052 U	< 0.00065 U	< 0.00077 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated							

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0028 U	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated								
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	0.015
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.00047 U	< 0.00095 U	< 0.00047 U	< 0.00047 U	< 0.00047 U	< 0.00038 U	< 0.00047 U	< 0.00038 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.027 U	< 0.054 U	< 0.027 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	< 0.00049 U,H	< 0.00098 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00049 U,H	< 0.00039 U,H	< 0.00049 U,H	< 0.00039 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.027 U	< 0.053 U	< 0.027 U	< 0.027 U	< 0.027 U	< 0.021 U	< 0.027 U	0.11 J
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.00065 U	< 0.0013 U	< 0.00065 U	< 0.00065 U	< 0.00065 U	< 0.00052 U	< 0.00065 U	< 0.00052 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated								
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated								
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated								
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	0.018 J	0.0058	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.00057 U	< 0.00095 U	< 0.00038 U	< 0.00095 U	< 0.00057 U	< 0.0019 U	< 0.00095 U	< 0.00047 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.032 U	< 0.054 U	< 0.021 U	< 0.054 U	< 0.032 U	< 0.11 U	< 0.054 U	< 0.027 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	< 0.00059 U,H	< 0.00098 U,H	< 0.00039 U,H	< 0.00098 U,H	< 0.00059 U,H	0.0027 J	< 0.00098 U,H	< 0.00049 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.032 U	< 0.053 U	< 0.021 U	< 0.053 U	< 0.032 U	< 0.11 U	< 0.053 U	< 0.027 U
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.00077 U	< 0.0013 U	< 0.00052 U	< 0.0013 U	0.00087 J	< 0.0026 U	< 0.0013 U	< 0.00065 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0013 U	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.00038 U	< 0.00038 U	< 0.00047 U	< 0.00057 U	< 0.0047 U	< 0.0047 U	< 0.00057 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.021 U	< 0.021 U	< 0.027 U	< 0.032 U	< 0.27 U	< 0.27 U	< 0.032 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	< 0.00039 U,H	< 0.00039 U,H	< 0.00049 U,H	< 0.00059 U,H	< 0.0049 U,H	< 0.0049 U,H	< 0.00059 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.021 U	< 0.021 U	< 0.027 U	< 0.032 U	< 0.27 U	< 0.27 U	< 0.032 U
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.00065 U	0.00093 J	< 0.0065 U	< 0.0065 U	< 0.00077 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-6-8	SSHS-B3055-SUB-6-8	8/29/2019	856.20	858.70	2.50	-	6 - 8 ft	8.5-10.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-6-8	SSHS-B3056-SUB-6-8	8/29/2019	855.88	858.82	2.94	-	6 - 8 ft	8.94-10.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-6-8	SSHS-B3069-SUB-6-8	8/29/2019	855.92	856.73	0.81	-	6 - 8 ft	6.81-8.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-6-8	SSHS-B3079-SUB-6-8	8/29/2019	856.36	857.37	1.01	-	6 - 8 ft	7.01-9.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-6-8	SSHS-B3083-SUB-6-8	8/29/2019	857.13	857.39	0.26	-	6 - 8 ft	6.26-8.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-6-8	SSHS-B3084-SUB-6-8	8/29/2019	856.55	857.05	0.50	-	6 - 8 ft	6.5-8.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-6-8	SSHS-B3181-SUB-6-8	8/29/2019	857.57	857.81	0.24	-	6 - 8 ft	6.24-8.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-6-8	SSHS-B3182-SUB-6-8	8/29/2019	857.45	857.88	0.43	-	6 - 8 ft	6.43-8.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-6-8	SSHS-B3223-SUB-6-8	8/29/2019	858.27	858.28	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-6-8	SSHS-B3003-SUB-6-8	8/30/2019	851.95	852.83	0.88	-	6 - 8 ft	6.88-8.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-6-8	SSHS-B3011-SUB-6-8	8/30/2019	853.85	854.62	0.77	-	6 - 8 ft	6.77-8.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-6-8	SSHS-B3025-SUB-6-8	8/30/2019	854.59	855.82	1.23	-	6 - 8 ft	7.23-9.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-6-8	SSHS-B3039-SUB-6-8	8/30/2019	855.85	856.37	0.52	-	6 - 8 ft	6.52-8.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-6-8	SSHS-B3068-SUB-6-8	8/30/2019	856.38	856.82	0.44	-	6 - 8 ft	6.44-8.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-6-8	SSHS-B3082-SUB-6-8	8/30/2019	856.73	857.22	0.49	-	6 - 8 ft	6.49-8.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-6-8	SSHS-B3214-SUB-6-8	8/30/2019	855.06	855.25	0.19	-	6 - 8 ft	6.19-8.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-6-8	SSHS-B3222-SUB-6-8	8/30/2019	858.28	858.08	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-6-8	SSHS-B3224-SUB-6-8	8/30/2019	858.38	858.48	0.10	-	6 - 8 ft	6.1-8.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-6-8	SSHS-B3001-SUB-6-8	9/3/2019	853.35	853.44	0.09	-	6 - 8 ft	6.09-8.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-6-8	SSHS-B3002-SUB-6-8	9/3/2019	853.09	853.12	0.03	-	6 - 8 ft	6.03-8.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-6-8	SSHS-B3009-SUB-6-8	9/3/2019	853.88	854.29	0.41	-	6 - 8 ft	6.41-8.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-6-8	SSHS-B3010-SUB-6-8	9/3/2019	854.13	854.48	0.35	-	6 - 8 ft	6.35-8.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-6-8	SSHS-B3023-SUB-6-8	9/3/2019	854.48	854.90	0.42	-	6 - 8 ft	6.42-8.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-6-8	SSHS-B3024-SUB-6-8	9/3/2019	855.00	855.16	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-6-8	SSHS-B3036-SUB-6-8	9/3/2019	855.09	855.21	0.12	-	6 - 8 ft	6.12-8.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-6-8	SSHS-B3038-SUB-6-8	9/3/2019	855.76	855.72	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-6-8	SSHS-B3053-SUB-6-8	9/3/2019	856.41	856.22	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-6-8	SSHS-B3067-SUB-6-8	9/3/2019	856.40	856.48	0.08	-	6 - 8 ft	6.08-8.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-6-8	SSHS-B3051-SUB-6-8	9/4/2019	855.15	855.32	0.17	-	6 - 8 ft	6.17-8.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-6-8	SSHS-B3066-SUB-6-8	9/4/2019	855.86	856.02	0.16	-	6 - 8 ft	6.16-8.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-6-8	SSHS-B3080-SUB-6-8	9/4/2019	856.58	856.76	0.18	-	6 - 8 ft	6.18-8.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-6-8	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated	< 0.0024 U	< 0.0015 U	< 0.0014 U	< 0.0037 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-6-8	SSHS-B3085-SUB-6-8	9/4/2019	857.12	857.26	0.14	-	6 - 8 ft	6.14-8.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-6-8	SSHS-B3086-SUB-6-8	9/4/2019	857.77	857.49	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-6-8	SSHS-B3220-SUB-6-8	9/4/2019	857.44	857.92	0.48	-	6 - 8 ft	6.48-8.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-6-8	SSHS-B3221-SUB-6-8	9/4/2019	857.92	857.93	0.01	-	6 - 8 ft	6.01-8.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-6-8	SSHS-B3244-SUB-6-8	12/19/2019	857.74	857.53	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-6-8	SSHS-B3233-SUB-6-8	12/20/2019	855.71	855.74	0.03	-	6 - 8 ft	6.03-8.03 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-6-8	SSHS-B3235-SUB-6-8	12/20/2019	856.44	856.25	-0.19	-	6 - 8 ft	5.81-7.81 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-6-8	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-6-8	SSHS-B3100-SUB-6-8	1/13/2020	856.74	856.68	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-6-8	SSHS-B3101-SUB-6-8	1/13/2020	856.75	856.69	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-6-8	SSHS-B3102-SUB-6-8	1/13/2020	856.74	856.23	-0.51	-	6 - 8 ft	5.49-7.49 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-6-8	SSHS-B3104-SUB-6-8	1/13/2020	856.82	856.64	-0.18	-	6 - 8 ft	5.82-7.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-6-8	SSHS-B3105-SUB-6-8	1/14/2020	856.73	856.62	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-6-8	SSHS-B3106-SUB-6-8	1/14/2020	856.72	856.30	-0.42	-	6 - 8 ft	5.58-7.58 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-6-8	SSHS-B3108-SUB-6-8	1/14/2020	857.55	856.76	-0.79	-	6 - 8 ft	5.21-7.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-6-8	SSHS-B3113-SUB-6-8	1/14/2020	856.36	856.08	-0.28	-	6 - 8 ft	5.72-7.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3117	011520 09:00 SSHS-B3117-SUB-6-8	SSHS-B3117-SUB-6-8	1/14/2020	856.54	856.53	-0.01	-	6 - 8 ft	5.99-7.99 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-6-8	SSHS-B3183-SUB-6-8	1/14/2020	856.70	855.84	-0.86	-	6 - 8 ft	5.14-7.14 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-6-8	SSHS-B3184-SUB-6-8	1/14/2020	856.85	855.95	-0.90	-	6 - 8 ft	5.1-7.1 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-6-8	SSHS-B3107-SUB-6-8	1/15/2020	857.05	857.26	0.21	-	6 - 8 ft	6.21-8.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-6-8	SSHS-B3109-SUB-6-8	1/15/2020	857.26	856.77	-0.49	-	6 - 8 ft	5.51-7.51 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-6-8	SSHS-B3110-SUB-6-8	1/15/2020	856.32	856.06	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-6-8	SSHS-B3111-SUB-6-8	1/15/2020	857.08	857.00	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-6-8	SSHS-B3112-SUB-6-8	1/15/2020	856.71	856.67	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-6-8	SSHS-B3116-SUB-6-8	1/15/2020	856.51	856.63	0.12	-	6 - 8 ft	6.12-8.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-6-8	SSHS-B3118-SUB-6-8	1/15/2020	856.74	856.72	-0.02	-	6 - 8 ft	5.98-7.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-6-8	SSHS-B3521-SUB-6-8	1/25/2021	855.79	855.68	-0.11	-	6 - 8 ft	5.89-7.89 ft	180-116404-1	Not Excavated							
Northern Athletic Field	SSHS-B3260A	012721 08:30 SSHS-B3260A-SUB-6-8	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-6-8	SSHS-B3634-SUB-6-8	1/26/2021	857.44	857.49	0.05	-	6 - 8 ft	6.05-8.05 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-6-8	SSHS-B3635-SUB-6-8	1/26/2021	857.87	857.72	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3286A	012821 08:30 SSHS-B3286A-SUB-6-8	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated							
Northern Athletic Field	SSHS-B3282A	013021 10:00 SSHS-B3282A-SUB-6-8	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated							
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8-20210511	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	0.081	0.033	0.11
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-6-8	SSHS-B3918-SUB-6-8	5/12/2021	854.82	854.84	0.02	-	6 - 8 ft	6.02-8.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8-20210517	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8-20210518	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-6-8	SSHS-B3931-SUB-6-8	6/17/2021	856.63	855.62	-1.01	-	6 - 8 ft	4.99-6.99 ft	180-123399-1	Not Excavated	< 0.00047 U	< 0.00047 U	< 0.00066 U	< 0.00057 U	< 0.00095 U	< 0.00038 U	< 0.0013 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-6-8	SSHS-B3932-SUB-6-8	6/17/2021	857.09	855.85	-1.24	-	6 - 8 ft	4.76-6.76 ft	180-123399-1	Not Excavated	< 0.027 U	< 0.027 U	< 0.038 U	< 0.032 U	< 0.054 U	< 0.021 U	< 0.075 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-6-8	SSHS-B3933-SUB-6-8	6/17/2021	856.55	855.68	-0.87	-	6 - 8 ft	5.13-7.13 ft	180-123399-1	Not Excavated	< 0.00049 U,H	0.00089 J	< 0.00069 U,H	< 0.00059 U,*+,H	< 0.00098 U,H	< 0.00039 U,H	< 0.0014 U,H
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-6-8	SSHS-B3934-SUB-6-8	6/17/2021	856.72	855.95	-0.77	-	6 - 8 ft	5.23-7.23 ft	180-123399-1	Not Excavated	< 0.027 U	< 0.027 U	< 0.037 U	< 0.032 U	0.51	0.14 J	0.65
Northern Athletic Field	SSHS-B3935	061821 09:00 SSHS-B3935-SUB-6-8	SSHS-B3935-SUB-6-8	6/17/2021	856.53	856.13	-0.40	-	6 - 8 ft	5.6-7.6 ft	180-123399-1	Not Excavated	< 0.00065 U	< 0.00065 U	< 0.0009 U	< 0.00077 U	< 0.0013 U	< 0.00052 U	< 0.0018 U
Northern Athletic Field	SSHS-B3853	091721 09:30 SSHS-B3853-SUB-6-8	SSHS-B3853-SUB-6-8	9/16/2021	856.30	856.51	0.21	-	6 - 8 ft	6.21-8.21 ft	180-127205-2	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.0041 U	< 0.00024 U	< 0.00035 U	< 0.00065 U	< 0.0024 U	< 0.00044 U	< 0.0024 U	< 0.00047 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.24 U	< 0.041 U	< 0.051 U	< 0.06 U	< 0.23 U	< 0.16 U	< 0.11 U	< 0.1 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated								
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated								
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated								
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated								
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated								
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated								
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated								
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated								
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated								
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated								
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated								
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated								
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated								
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated								
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated								
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated								
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated								
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.018 UT	< 0.00059 U	< 0.0011 U	< 0.0013 U	< 0.0020 U	< 0.0035 U	< 0.00099 U	< 0.0028 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.018 UT	< 0.00059 U	< 0.0010 U	< 0.0013 U	< 0.0020 U	< 0.0035 U	< 0.00098 U	< 0.0027 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.019 UT	< 0.00063 U	< 0.0011 U	< 0.0014 U	< 0.0022 U	< 0.0038 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated								
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated								
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.0037 UT	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 UT	< 0.0038 U	< 0.0019 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated								
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.0035 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0022 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.00094 U	< 0.00091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.00064 U	< 0.00062 U	< 0.0011 U	< 0.0003 U	< 0.00029 U	< 0.00068 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00		6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.035 U	< 0.12 U	< 0.15 U	< 0.053 U	< 0.065 U	< 0.16 U	< 0.22 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated							
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated							
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated							
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated							
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated							
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated							
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated							
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.0007 U	< 0.002 U	< 0.0012 U	< 0.0032 UJ
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated							
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated							
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated							
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated							
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated							
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated							
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated							
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated							
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated							
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated							
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated							
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated							
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated							
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated							
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated							
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated							
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.00078 U	< 0.0024 U	< 0.0023 U	< 0.00067 U	< 0.0019 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.00077 U	< 0.0023 U	< 0.0023 U	< 0.00067 U	< 0.0019 U	< 0.0012 U	< 0.0030 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.00083 U	< 0.0025 U	< 0.0025 U	< 0.00071 U	< 0.0021 U	< 0.0012 U	< 0.0033 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated							
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated							
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 UT	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0018 J	< 0.0023 UT	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated							
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0018 J	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0017 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00092 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U	< 0.00036 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.0022 U	< 0.00062 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00068 U	< 0.00059 U	< 0.00024 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.38 U	< 0.078 U	< 0.052 U	< 0.12 U	< 0.045 U	< 0.054 U	< 0.047 U	< 0.046 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated								
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated								
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated								
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated								
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated								
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.011 U	< 0.00068 U	< 0.00083 U	< 0.00098 UJ	< 0.00072 UJ	< 0.00078 UJ	< 0.00061 U	< 0.00068 U
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated								
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated								
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated								
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated								
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated								
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated								
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated								
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated								
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated								
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated								
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated								
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated								
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.01 UT	< 0.00065 U	< 0.00080 U	< 0.00094 U	< 0.00069 U	< 0.00075 U	< 0.00059 U	< 0.00066 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.01 UT	< 0.00065 U	< 0.00080 U	< 0.00094 U	< 0.00069 U	< 0.00074 U	< 0.00059 U	< 0.00065 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.011 UT	< 0.00070 U	< 0.00085 U	< 0.0010 U	< 0.00074 U	< 0.00080 U	< 0.00063 U	< 0.00070 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated								
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated								
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.0043 UT	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated								
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.0040 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	0.011	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	0.0062	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00091 U	< 0.00074 U	< 0.034 U	< 0.001 U	< 0.0031 U	< 0.00049 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.00059 U	< 0.0025 U	< 0.00062 U	< 0.0005 U	< 0.0024 U	< 0.0007 U	< 0.0021 U	< 0.00033 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.081 U	< 0.061 U	< 0.039 U	< 0.061 U	< 0.037 U	< 0.12 U	< 0.1 U	< 0.046 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated								
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated								
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated								
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated								
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated								
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00093 U
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated								
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated								
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated								
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated								
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated								
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated								
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated								
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated								
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated								
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated								
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated								
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated								
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.0015 U	< 0.00096 U	< 0.0013 U	< 0.0012 U	< 0.00072 U	< 0.0024 U	< 0.0031 U	< 0.00089 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.0015 U	< 0.00095 U	< 0.0012 U	< 0.0012 U	< 0.00072 U	< 0.0024 U	< 0.0031 U	< 0.00088 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.0016 U	< 0.0010 U	< 0.0013 U	< 0.0013 U	< 0.00077 U	< 0.0026 U	< 0.0034 U	< 0.00095 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated								
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated								
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.0022 U	< 0.0039 UT	< 0.0014 UT	< 0.0017 UT	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated								
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.0020 U	< 0.0036 U	< 0.0013 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0028 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.0007 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.0011 U	< 0.0024 U	< 0.00073 UJ	< 0.0029 U	< 0.00074 U	< 0.0018 U	< 0.0016 U	< 0.00048 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.066 U	< 0.26 U	< 0.038 U	< 0.17 U	< 0.065 U	0.2 J	< 0.23 U	< 0.037 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated								
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated								
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated								
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated								
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated								
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated								
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated								
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.003 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0018 U
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated								
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated								
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated								
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated								
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated								
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated								
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated								
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated								
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated								
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated								
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated								
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated								
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated								
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated								
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0035 U	< 0.0016 U	< 0.0029 U	< 0.0010 U	< 0.0030 U	< 0.0032 U	< 0.0017 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0034 U	< 0.0016 U	< 0.0029 U	< 0.0010 U	< 0.0030 U	< 0.0031 U	< 0.0017 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.0012 U	< 0.0037 U	< 0.0017 U	< 0.0031 U	< 0.0011 U	< 0.0032 U	< 0.0034 U	< 0.0018 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated								
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated								
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated								
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.0019 U	< 0.0015 UT	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 UT	< 0.0017 UT	< 0.0014 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0023 U	< 0.0018 UT	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 UT	< 0.0021 UT	< 0.0017 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0021 U	< 0.0016 UT	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 UT	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated								
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0022 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0023 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0030 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated								

DRAFT

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.00036 U	< 0.034 U	< 0.00096 U	< 0.00054 U	< 0.034 U	< 0.00043 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.00024 U	< 0.00079 U	< 0.00065 U	< 0.00037 U	< 0.00052 U	< 0.00029 U	< 0.00035 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.051 U	< 0.15 U	< 0.096 U	< 0.24 U	< 0.17 U	< 0.13 U	< 0.077 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated							
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated							
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated							
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated							
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated							
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated							
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated							
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0013 UJ	< 0.00065 U	< 0.00068 U	< 0.0026 UJ	< 0.0022 UJ	< 0.0016 U
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated							
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated							
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated							
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated							
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated							
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated							
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated							
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated							
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated							
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated							
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated							
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated							
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated							
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated							
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated							
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated							
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.00098 U	< 0.0012 U	< 0.00062 U	< 0.00066 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.00098 U	< 0.0012 U	< 0.00062 U	< 0.00065 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.0010 U	< 0.0013 U	< 0.00066 U	< 0.00070 U	< 0.0027 U	< 0.0023 U	< 0.0016 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated							
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated							
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated							
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0018 U	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-6-8	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0012 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-6-8	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.00063 U	< 0.0011 U	< 0.00046 U	< 0.00059 U	< 0.00081 U	< 0.00063 U	< 0.00081 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-6-8	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated	< 0.056 U	< 0.14 U	< 0.14 U	< 0.12 U	< 0.052 U	< 0.042 U	< 0.09 U
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292041	Not Excavated							
Northern Athletic Field	S241	SSHS-IRM5A2-S241-20211028	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated							
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292041	Not Excavated							
Northern Athletic Field	S240	SSHS-IRM5A2-S240-20211028	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated							
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292041	Not Excavated							
Northern Athletic Field	S239	SSHS-IRM5A2-S239-20211028	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated							
Northern Athletic Field	S238	SSHS-IRM5A2-S238-20211028	SSHS-IRM5A2-S238	10/28/2021	-	856.14	-	849.18	6 - 8 ft	6.96 ft	1801292042	Not Excavated							
Northern Athletic Field	S244	SSHS-IRM5A2-S244-20211028	SSHS-IRM5A2-S244	10/28/2021	-	856.32	-	849.09	6 - 8 ft	7.22 ft	1801292042	Not Excavated							
Northern Athletic Field	S243	SSHS-IRM5A2-S243-20211028	SSHS-IRM5A2-S243	10/28/2021	-	856.19	-	849.06	6 - 8 ft	7.13 ft	1801292042	Not Excavated							
Northern Athletic Field	S242	SSHS-IRM5A2-S242-20211028	SSHS-IRM5A2-S242	10/28/2021	-	855.96	-	848.93	6 - 8 ft	7.03 ft	1801292042	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-6-8	SSHS-B4264-SUB-6-8	11/1/2021	852.29	853.31	1.02	-	6 - 8 ft	7.02-9.02 ft	180-129325-1	Not Excavated	< 0.001 U	0.0023 J	< 0.0024 U	< 0.0016 U	< 0.00069 U	< 0.00076 U	< 0.0014 U
Northern Athletic Field	B201	110421 09:45_SSHS-IRM5A2-B201	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	180-129463-2	Not Excavated							
Northern Athletic Field	S203	SSHS-IRM5A2-DUP9-20211103	SSHS-IRM5A2-DUP9	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294633	Not Excavated							
Northern Athletic Field	S206	SSHS-IRM5A2-S206-20211103	SSHS-IRM5A2-S206	11/3/2021	-	857.59	-	850.17	6 - 8 ft	7.41 ft	1801294632	Not Excavated							
Northern Athletic Field	S207	SSHS-IRM5A2-S207-20211103	SSHS-IRM5A2-S207	11/3/2021	-	857.69	-	850.13	6 - 8 ft	7.56 ft	1801294632	Not Excavated							
Northern Athletic Field	S208	SSHS-IRM5A2-S208-20211103	SSHS-IRM5A2-S208	11/3/2021	-	857.87	-	850.31	6 - 8 ft	7.56 ft	1801294632	Not Excavated							
Northern Athletic Field	S209	SSHS-IRM5A2-S209-20211103	SSHS-IRM5A2-S209	11/3/2021	-	857.98	-	850.57	6 - 8 ft	7.4 ft	1801294632	Not Excavated							
Northern Athletic Field	S210	SSHS-IRM5A2-S210-20211103	SSHS-IRM5A2-S210	11/3/2021	-	857.90	-	850.74	6 - 8 ft	7.17 ft	1801294632	Not Excavated							
Northern Athletic Field	S211	SSHS-IRM5A2-S211-20211103	SSHS-IRM5A2-S211	11/3/2021	-	857.95	-	850.58	6 - 8 ft	7.37 ft	1801294632	Not Excavated							
Northern Athletic Field	S212	SSHS-IRM5A2-S212-20211103	SSHS-IRM5A2-S212	11/3/2021	-	857.73	-	850.60	6 - 8 ft	7.14 ft	1801294632	Not Excavated							
Northern Athletic Field	S203	SSHS-IRM5A2-S203-20211103	SSHS-IRM5A2-S203	11/3/2021	-	857.52	-	850.53	6 - 8 ft	6.99 ft	1801294632	Not Excavated							
Northern Athletic Field	S204	SSHS-IRM5A2-S204-20211103	SSHS-IRM5A2-S204	11/3/2021	-	857.50	-	850.18	6 - 8 ft	7.32 ft	1801294632	Not Excavated							
Northern Athletic Field	S205	SSHS-IRM5A2-S205-20211103	SSHS-IRM5A2-S205	11/3/2021	-	857.48	-	850.04	6 - 8 ft	7.43 ft	1801294632	Not Excavated							
Northern Athletic Field	B201	SSHS-IRM5A2-B201-20211103	SSHS-IRM5A2-B201	11/3/2021	-	857.74	-	849.75	6 - 8 ft	7.99 ft	1801294632	Not Excavated							
Northern Athletic Field	B200	SSHS-IRM5A2-B200-20211103	SSHS-IRM5A2-B200	11/3/2021	-	857.91	-	849.96	6 - 8 ft	7.95 ft	1801294632	Not Excavated							
Northern Athletic Field	B420	SSHS-IRM5A2-B420-20211104	SSHS-IRM5A2-B420	11/4/2021	-	858.76	-	852.31	6 - 8 ft	6.45 ft	1801296371	Not Excavated							
Northern Athletic Field	B419	SSHS-IRM5A2-B419-20211104	SSHS-IRM5A2-B419	11/4/2021	-	858.29	-	852.12	6 - 8 ft	6.17 ft	1801296371	Not Excavated							
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3-20211108	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 0.00096 U	< 0.00054 U	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00073 U	< 0.0013 U
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2-20211108	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 0.00096 U	< 0.00053 U	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00073 U	< 0.0013 U
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2-20211110	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 0.0010 U	< 0.00057 U	< 0.0024 U	< 0.0016 U	< 0.00071 U	< 0.00078 U	< 0.0014 U
Northern Athletic Field	B418-S4	SSHS-IRM5A2-B418-S4-20211113	SSHS-IRM5A2-B418-S4	11/13/2021	-	858.28	-	851.23	6 - 8 ft	7.05 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-S1	SSHS-IRM5A2-B418-S1-20211113	SSHS-IRM5A2-B418-S1	11/13/2021	-	858.07	-	851.14	6 - 8 ft	6.93 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-S3	SSHS-IRM5A2-B418-S3-20211113	SSHS-IRM5A2-B418-S3	11/13/2021	-	857.63	-	851.27	6 - 8 ft	6.37 ft	1801299881	Not Excavated							
Northern Athletic Field	B418-BOT1	SSHS-IRM5A2-B418-BOT1-20211113	SSHS-IRM5A2-B418-BOT1	11/13/2021	-	858.08	-	850.30	6 - 8 ft	7.78 ft	1801299881	Not Excavated							
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1-20211214	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated							
Northern Athletic Field	S473	SSHS-IRM5A2-S473-20220106	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0040 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	S474	SSHS-IRM5A2-S474-20220106	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S472	SSHS-IRM5A2-S472-20220106	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S529	SSHS-IRM5A2-S529-20220112	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220120	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated							
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34-20220202	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30-20220202	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31-20220202	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 0.00092 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32-20220202	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33-20220202	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58-20220202	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59-20220202	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57-20220202	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38-20220202	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 0.00088 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36-20220207	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62-20220207	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65-20220207	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63-20220207	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1-20220207	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2-20220207	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4-20220207	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6-20220207	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2-20220207	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3-20220207	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39-20220208	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40-20220208	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2-20220208	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5-20220208	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4-20220208	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7-20220208	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S125	SSHS-IRM5A2-S125-20220228	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	S126	SSHS-IRM5A2-S126-20220228	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48-20220303	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S254	SSHS-IRM5A2-S254-20220303	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S180	SSHS-IRM5A2-S180-20220303	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220305	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 U	< 0.00017 U	< 0.00040 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 U	< 0.00017 U	< 0.00040 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.0085 U	< 0.00038 U	< 0.00042 U	< 0.00038 U	< 0.00063 U	< 0.0015 U	< 0.00040 U	< 0.00058 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.0028 U	< 0.00012 U	< 0.00014 U	< 0.00012 U	< 0.00021 U	< 0.00048 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated								
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated								
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated								
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	0.013	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	0.0074	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	0.00053 J	< 0.00041 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	0.014	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	0.011	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	0.0091	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354851	Not Excavated	0.0075	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	0.011	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	0.015	< 0.00022 UT	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	0.0097	< 0.00038 U	< 0.00041 U	< 0.00038 U	< 0.00063 U	< 0.0015 U	< 0.00039 U	< 0.00057 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	0.011	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	0.0095	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00050 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0040 U	< 0.0031 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0027 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.021 U	< 0.00069 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0041 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.013 U	< 0.00045 U	< 0.00079 U	< 0.00096 U	< 0.0015 U	< 0.0026 U	< 0.00074 U	< 0.0021 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.019 U	< 0.00063 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.0010 U	< 0.0029 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.011 U	< 0.00035 U	< 0.00062 U	< 0.00075 U	< 0.0012 U	< 0.0021 U	< 0.00058 U	< 0.0016 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.14 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.094 U	< 0.061 U	< 0.058 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.022 U	< 0.00072 U	< 0.0013 U	< 0.0016 U	< 0.0025 U	< 0.0043 U	< 0.0012 U	< 0.0034 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.037 U	< 0.0012 U	< 0.0022 U	< 0.0027 U	< 0.0043 U	< 0.0074 U	< 0.0021 U	< 0.0058 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.018 U	< 0.00061 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.0010 U	< 0.0028 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.0043 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00032 U	< 0.00075 U	< 0.00020 U	< 0.00029 UT
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.0074 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	< 0.00035 U	< 0.00050 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 UT	< 0.00041 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 UT	< 0.00039 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0034 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0029 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.000071 U	< 0.000078 U	< 0.00021 U	< 0.00039 U	< 0.00018 U	< 0.000089 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.000088 U	< 0.000096 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.000071 U	< 0.000078 U	< 0.00021 U	< 0.00039 U	< 0.00017 U	< 0.000089 U	< 0.00018 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00078 U	< 0.0014 U	< 0.00065 U	< 0.00033 U	< 0.00069 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.000086 U	< 0.000094 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UT	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated							
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated							
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated							
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated							
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated							
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated							
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated							
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	< 0.00015 UT	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 UT	< 0.00039 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00077 U	< 0.0014 U	< 0.00064 U	< 0.00033 U	< 0.00068 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00028 U	< 0.00057 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00069 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0018 U	< 0.0033 U	< 0.0039 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0044 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated							
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.00091 U	< 0.0028 U	< 0.0027 U	< 0.00078 U	< 0.0023 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.00058 U	< 0.0018 U	< 0.0017 U	< 0.00050 U	< 0.0015 U	< 0.00088 U	< 0.0023 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.00082 U	< 0.0025 U	< 0.0025 U	< 0.00071 U	< 0.0020 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.00046 U	< 0.0014 U	< 0.0014 U	< 0.00040 U	< 0.0011 U	< 0.00069 U	< 0.0018 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.02 U	< 0.066 U	< 0.085 U	< 0.031 U	< 0.037 U	< 0.092 U	< 0.12 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.00095 U	< 0.0029 U	< 0.0028 U	< 0.00081 U	< 0.0024 U	< 0.0014 U	< 0.0037 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.0016 U	< 0.0049 U	< 0.0049 U	< 0.0014 U	< 0.0040 U	< 0.0024 U	< 0.0064 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.00080 U	< 0.0024 U	< 0.0024 U	< 0.00069 U	< 0.0020 U	< 0.0012 U	< 0.0032 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 UT	< 0.00022 U	< 0.00046 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.00013 U	< 0.00015 U	< 0.00039 U	< 0.00073 U	< 0.00033 U	< 0.00017 U	< 0.00035 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00068 U	< 0.0013 U	< 0.00056 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.0041 U	< 0.0012 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.00046 U	< 0.000073 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000091 U	< 0.000083 U	< 0.00012 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.00057 U	< 0.000090 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.00046 U	< 0.000072 U	< 0.00014 U	< 0.00014 U	< 0.00015 U	< 0.000090 U	< 0.000083 U	< 0.00012 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.0017 U	< 0.00027 U	< 0.00050 U	< 0.00054 U	< 0.00054 U	< 0.00034 U	< 0.00031 U	< 0.00044 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.00055 U	< 0.000087 U	< 0.00016 U	< 0.00017 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated								
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated								
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated								
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 UT	< 0.00031 UT	< 0.00019 UT	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00050 U	< 0.00053 U	< 0.00054 U	< 0.00033 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 UT	< 0.0014 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0061 U	< 0.0018 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.0020 U	< 0.0022 U	< 0.0019 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.012 U	< 0.00076 U	< 0.00094 U	< 0.0011 U	< 0.00081 U	< 0.00088 U	< 0.00069 U	< 0.00077 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.0077 U	< 0.00049 U	< 0.00060 U	< 0.00071 U	< 0.00052 U	< 0.00056 UT	< 0.00044 U	< 0.00049 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.011 U	< 0.00069 U	< 0.00084 U	< 0.0010 U	< 0.00073 U	< 0.00079 U	< 0.00062 U	< 0.00069 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.0060 U	< 0.00039 U	< 0.00047 U	< 0.00056 U	< 0.00041 U	< 0.00044 U	< 0.00035 U	< 0.00039 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.22 U	< 0.045 U	< 0.03 U	< 0.068 U	< 0.026 U	< 0.031 U	< 0.027 U	< 0.027 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.012 U	< 0.00080 U	< 0.00097 U	< 0.0011 U	< 0.00084 U	< 0.00091 U	< 0.00072 U	< 0.00080 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.021 U	< 0.0014 U	< 0.0017 U	< 0.0020 U	< 0.0014 U	< 0.0016 UT	< 0.0012 U	< 0.0014 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.01 U	< 0.00067 U	< 0.00082 U	< 0.00097 U	< 0.00071 U	< 0.00077 U	< 0.00061 U	< 0.00068 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 UT	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00040 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.00086 U	< 0.00014 U	< 0.00025 U	< 0.00027 U	< 0.00027 U	< 0.00017 U	< 0.00015 U	< 0.00022 UT
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00047 U	< 0.00029 U	< 0.00027 U	< 0.00038 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 UT
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.000091 U	< 0.00015 U	< 0.00014 U	< 0.000099 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000080 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000099 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.000090 U	< 0.00015 U	< 0.00014 U	< 0.000099 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000080 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.00034 U	< 0.00057 U	< 0.00053 U	< 0.00037 U	< 0.00063 U	< 0.00041 U	< 0.00040 U	< 0.00030 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000096 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated								
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated								
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated								
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 UT
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00053 U	< 0.00036 U	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	< 0.00030 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00032 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 UT	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0030 U	< 0.0055 U	< 0.0020 U	< 0.0024 U	< 0.0018 U	< 0.0030 U	< 0.0030 U	< 0.0025 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00084 U	< 0.0029 U	< 0.0037 U	< 0.0010 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.0012 U	< 0.00072 U	< 0.00094 U	< 0.00091 U	< 0.00054 U	< 0.0018 U	< 0.0024 U	< 0.00067 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.0016 U	< 0.0010 U	< 0.0013 U	< 0.0013 U	< 0.00076 U	< 0.0026 U	< 0.0033 U	< 0.00094 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.00091 U	< 0.00056 U	< 0.00074 U	< 0.00071 U	< 0.00043 U	< 0.0014 U	< 0.0019 U	< 0.00053 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.046 U	< 0.035 U	< 0.023 U	< 0.035 U	< 0.021 U	< 0.07 U	< 0.059 U	< 0.027 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.0019 U	< 0.0012 U	< 0.0015 U	< 0.0015 U	< 0.00088 U	< 0.0030 U	< 0.0038 U	< 0.0011 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.0032 U	< 0.0020 U	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.0051 U	< 0.0066 U	< 0.0019 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.0016 U	< 0.00098 U	< 0.0013 U	< 0.0012 U	< 0.00074 U	< 0.0025 U	< 0.0032 U	< 0.00092 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00027 U	< 0.00018 U	< 0.00032 U	< 0.00021 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.00029 U	< 0.00050 U	< 0.00046 U	< 0.00032 U	< 0.00055 U	< 0.00035 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 UT	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 UT	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.00012 U	< 0.00069 U	< 0.00011 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00063 U	< 0.00021 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.00012 U	< 0.00069 U	< 0.00011 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00062 U	< 0.00021 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.00045 U	< 0.0025 U	< 0.00042 U	< 0.0064 U	< 0.00074 U	< 0.00055 U	< 0.0023 U	< 0.00076 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.00015 U	< 0.00083 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00075 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated								
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated								
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated								
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated								
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated								
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated								
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	< 0.00025 U	< 0.0014 UT	< 0.00024 UT	< 0.0036 UT	< 0.00042 UT	< 0.00031 U	< 0.0013 UT	< 0.00043 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00042 U	< 0.0063 U	< 0.00073 U	< 0.00054 U	< 0.0023 U	< 0.00075 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.00038 U	< 0.0021 U	< 0.00036 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	< 0.00040 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00066 U	< 0.00048 U	< 0.0020 U	< 0.00067 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0072 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0027 UT	< 0.0021 U	< 0.0035 U	< 0.0099 U	< 0.0032 U	< 0.0034 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0021 UT	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.0013 U	< 0.0041 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0035 U	< 0.0037 U	< 0.0020 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.00082 U	< 0.0026 U	< 0.0012 U	< 0.0022 U	< 0.00078 U	< 0.0023 U	< 0.0024 U	< 0.0013 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.0011 U	< 0.0037 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0032 U	< 0.0033 U	< 0.0018 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.00064 U	< 0.0020 U	< 0.00096 U	< 0.0017 U	< 0.00062 U	< 0.0018 U	< 0.0019 U	< 0.00099 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.038 U	< 0.15 U	< 0.021 U	< 0.095 U	< 0.037 U	< 0.089 U	< 0.13 U	< 0.021 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.0013 U	< 0.0042 U	< 0.0020 U	< 0.0035 U	< 0.0013 U	< 0.0037 U	< 0.0038 U	< 0.0020 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.0023 U	< 0.0072 U	< 0.0034 U	< 0.0060 U	< 0.0022 U	< 0.0063 U	< 0.0066 U	< 0.0035 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.0011 U	< 0.0036 U	< 0.0017 U	< 0.0030 U	< 0.0011 U	< 0.0031 U	< 0.0032 U	< 0.0017 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 UT	< 0.00047 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 UT	< 0.00052 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 UT	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00021 U	< 0.0032 U	< 0.00037 U	< 0.00028 U	< 0.0012 U	< 0.00038 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00041 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.00011 U	< 0.000086 U	0.00015 J	< 0.000094 U	< 0.000073 U	< 0.00014 U	< 0.000094 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.00011 U	< 0.000086 U	< 0.00012 U	< 0.000094 U	< 0.000073 U	< 0.00014 U	< 0.000094 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00031 U	< 0.00024 U	0.00067 J	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.00041 U	< 0.00032 U	< 0.00045 U	< 0.00035 U	< 0.00027 U	< 0.00053 U	< 0.00035 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000088 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated							
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated							
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated							
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated							
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated							
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated							
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated							
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	< 0.00023 UT	< 0.00018 UT	< 0.00026 UT	< 0.00020 UT	< 0.00015 UT	< 0.00030 UT	< 0.00020 U
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	< 0.00041 U	< 0.00031 U	< 0.00045 U	< 0.00034 U	< 0.00027 U	< 0.00053 U	< 0.00034 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0023 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated							
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.00072 U	< 0.00077 U	< 0.0029 U	< 0.0025 U	< 0.0018 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.00074 U	< 0.00091 U	0.0018 J	< 0.00049 U	< 0.0019 U	< 0.0016 U	< 0.0011 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.0010 U	< 0.0013 U	< 0.00065 U	< 0.00069 U	< 0.0026 U	< 0.0022 U	< 0.0016 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.00058 U	< 0.00072 U	< 0.00037 U	< 0.00039 U	< 0.0015 U	< 0.0013 U	< 0.00089 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.029 U	< 0.085 U	0.056 J	< 0.14 U	< 0.095 U	< 0.075 U	< 0.044 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.0012 U	< 0.0015 U	< 0.00075 U	< 0.00080 U	< 0.0030 U	< 0.0026 U	< 0.0018 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.0021 U	< 0.0025 U	< 0.0013 U	< 0.0014 U	< 0.0052 U	< 0.0044 U	< 0.0031 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.0010 U	< 0.0013 U	< 0.00064 U	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0015 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00036 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	0.00057 J	< 0.00016 U	< 0.00023 U	< 0.00018 U	< 0.00014 U	< 0.00027 U	< 0.00017 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00040 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S255	SSHS-IRM5A2-S255-20220307	SSHS-IRM5A2-S255	3/7/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11-20220311	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.18	1801350892	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S223	SSHS-IRM5A2-S223-20220314	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17-20220314	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 0.00090 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20-20220314	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23-20220315	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 0.000072 U	< 0.00013 U	< 0.00016 U	< 0.00022 U	< 0.000070 U	< 0.000078 U	< 0.00026 U
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29-20220315	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 0.000089 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000087 U	< 0.000096 U	< 0.00032 U
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35-20220316	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.70	1801352871	Not Excavated	< 0.000071 U	< 0.00013 U	< 0.00016 U	< 0.00022 U	< 0.000070 U	< 0.000078 U	< 0.00026 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4-20220317	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00071 U
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41-20220317	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 0.00027 U	< 0.00048 U	< 0.00060 U	< 0.00081 U	< 0.00026 U	< 0.00029 U	< 0.00096 U
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8-20220317	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00065 U
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44-20220317	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 0.000086 U	< 0.00016 U	< 0.00020 U	< 0.00026 U	< 0.000084 U	< 0.000094 U	< 0.00031 U
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47-20220317	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60-20220318	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220319	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated							
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220319	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated							
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220319	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated							
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220319	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated							
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220319	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated							
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220319	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220319	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220319	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220319	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated							
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220319	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated							
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220319	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220320	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220320	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated							
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56-20220321	SSHS-IRM5A2-DUP56	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63-20220321	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12-20220321	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00068 U
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66-20220321	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00068 U
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69-20220321	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00064 U
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13-20220321	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00064 U
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72-20220321	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	S579	SSHS-IRM5A2-S579-20220321	SSHS-IRM5A2-S579	3/21/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354851	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00067 U
Northern Athletic Field	S219	SSHS-IRM5A2-S219-20220321	SSHS-IRM5A2-S219	3/21/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354851	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00070 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220-20220321	SSHS-IRM5A2-S220	3/21/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	S222	SSHS-IRM5A2-S222-20220321	SSHS-IRM5A2-S222	3/21/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354851	Not Excavated	< 0.00015 U	< 0.00027 UT	< 0.00034 U	< 0.00046 U	< 0.00015 UT	< 0.00016 UT	< 0.00054 UT
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A-20220321	SSHS-IRM5A2-S183A	3/21/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3-20220321	SSHS-IRM5A2-FISR-BOT3	3/21/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00071 U
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1-20220321	SSHS-IRM5A2-FISR-BOT1	3/21/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354851	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00073 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2-20220321	SSHS-IRM5A2-FISR-BOT2	3/21/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354851	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00060 U	< 0.00080 U	< 0.00026 U	< 0.00029 U	< 0.00094 U
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4-20220321	SSHS-IRM5A2-FISR-BOT4	3/21/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354851	Not Excavated	< 0.00022 U	0.00041 J	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00080 U
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7-20220321	SSHS-IRM5A2-S174-S7	3/21/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354861	Not Excavated	< 0.00023 U	0.00050 J	< 0.00053 U	< 0.00072 U	< 0.00023 U	< 0.00025 U	< 0.00084 U
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8-20220321	SSHS-IRM5A2-S174-S8	3/21/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354861	Not Excavated	< 0.00023 U	0.0018	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00082 U
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1-20220322	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.08	1801355361	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0070 U
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A-20220322	SSHS-IRM5A2-S255A	3/22/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801355351	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S179	SSHS-IRM5A2-S179-20220413	SSHS-IRM5A2-S179	4/13/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801366611	Not Excavated	< 0.0013 U	< 0.0021 U	< 0.0056 U	< 0.0049 U	< 0.0024 U	< 0.0027 U	< 0.0097 U
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A-20220413	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	PIPE4S	SSHS-IRM5A2-PIPE4S-20220422	SSHS-IRM5A2-PIPE4S	4/22/2022	-	856.39	-	849.93	6 - 8 ft	6.46 ft	1801370981	Not Excavated							
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72-20220425	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 0.0011 U	< 0.00063 U	< 0.0027 U	< 0.0018 U	< 0.00078 U	< 0.00085 U	< 0.0016 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1-20220425	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 0.00072 U	0.0012 J	< 0.0017 U	< 0.0011 U	< 0.00050 U	< 0.00055 U	< 0.0010 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1-20220425	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 0.0010 U	< 0.00057 U	< 0.0024 U	< 0.0016 U	< 0.00070 U	< 0.00077 U	< 0.0014 U
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2-20220425	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 0.00057 U	< 0.00032 U	< 0.0013 U	< 0.00089 U	< 0.00039 U	< 0.00043 U	< 0.00080 U
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3-20220425	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 0.032 U	2.2	< 0.077 UT	< 0.069 U	< 0.03 U	< 0.024 U	< 0.051 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5-20220425	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 0.0012 U	< 0.00065 U	< 0.0028 U	< 0.0018 U	< 0.00081 U	< 0.00089 U	< 0.0016 U
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9-20220425	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 0.0020 U	< 0.0011 U	< 0.0048 U	< 0.0031 U	< 0.0014 U	< 0.0015 U	< 0.0028 U
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10-20220425	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 0.00099 U	< 0.00055 U	< 0.0024 U	< 0.0015 U	< 0.00068 U	< 0.00075 U	< 0.0014 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17-20220509	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 UT	< 0.00018 U	< 0.00020 U	< 0.00065 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14-20220509	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12-20220509	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 UT	< 0.00018 U	< 0.00020 U	< 0.00065 U
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5-20220509	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00049 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00077 U
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008-20220516	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00030 UT	< 0.00041 U	< 0.00013 U	< 0.00015 U	< 0.00048 U
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014-20220517	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	S256	SSHS-IRM5A2-S256-20220517	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00071 U	< 0.00023 U	< 0.00025 U	< 0.00083 U
Northern Athletic Field	S257	SSHS-IRM5A2-S257-20220517	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated	< 0.00023 U	0.0052	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00082 U
Northern Athletic Field	B238	SSHS-IRM5A2-B238-20220517	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated	< 0.00014 U	0.00037 J	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00052 U
Northern Athletic Field	S258	SSHS-IRM5A2-S258-20220517	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	S259	SSHS-IRM5A2-S259-20220517	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00054 U
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016-20220517	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017-20220517	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00058 U
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11-20220517	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00058 U
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19-20220520	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00069 U
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18-20220520	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00064 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00027 UT	< 0.00040 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	0.097	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	0.00044 J	< 0.00036 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	0.0088	< 0.00036 U	< 0.00039 U	< 0.00036 U	< 0.00060 U	< 0.0014 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	0.011	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	0.0063	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	0.00091 J	< 0.00037 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 UT	< 0.00042 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 UT	< 0.00040 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.0065 U	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 U	< 0.00017 U	< 0.00040 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.0082 U	< 0.00037 U	< 0.00040 U	< 0.00037 U	< 0.00061 U	< 0.0014 U	< 0.00038 U	< 0.00055 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.0097 U	< 0.00044 U	< 0.00048 U	< 0.00044 U	< 0.00072 U	< 0.0017 U	0.0053	< 0.00066 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0040 U	< 0.0031 U	< 0.0033 U	< 0.0030 U	< 0.0053 U	< 0.0027 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	0.057	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	0.0026	< 0.00045 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 UT	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 UT	< 0.00021 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	0.17	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 UT	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 UT	< 0.00034 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	0.049	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.0081 U	< 0.00037 U	< 0.00040 U	< 0.00037 U	< 0.00060 U	< 0.0014 U	< 0.00038 U	< 0.00055 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	0.0099	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	0.14	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	0.0027	< 0.00040 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	0.0066	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00086 U	< 0.00023 U	< 0.00033 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0021 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0018 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00073 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00064 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	-	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 UT	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 UT	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 UT	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	-	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0040 J	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0040 J	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0019 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.000071 U	< 0.000078 U	< 0.00021 UT	< 0.00039 U	< 0.00018 U	< 0.000089 U	< 0.00019 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.00025 U	< 0.00028 U	< 0.00074 U	< 0.0014 U	< 0.00062 U	< 0.00032 U	< 0.00066 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.00030 U	< 0.00033 U	< 0.00088 U	< 0.0016 U	< 0.00074 U	< 0.00037 U	< 0.00078 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	0.0046 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0039 U	0.0050 BJ	< 0.0026 U	< 0.0032 U	< 0.0043 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0041 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	0.0049 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	0.0038 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0043 BJ	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0042 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0045 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0044 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.000095 UT	< 0.00010 UT	< 0.00028 U	< 0.00052 UT	< 0.00023 U	< 0.00012 UT	< 0.00025 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0026 J,B	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0028 J,B	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	0.0022 J,B	< 0.002 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00049 U	< 0.00090 U	< 0.00040 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00052 UT	< 0.00027 U	< 0.00055 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 UT	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 UT	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 U	< 0.00079 U	< 0.00035 UT	< 0.00018 U	< 0.00038 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.00025 U	< 0.00028 U	< 0.00074 U	< 0.0014 U	< 0.00062 UT	< 0.00031 U	< 0.00065 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 UT	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 UT	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 UT	< 0.00023 U	< 0.00048 UT
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 UT	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 UT	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 UT	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 UT	< 0.00019 U	< 0.00039 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00047 U	< 0.00051 U	< 0.00051 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.00046 U	< 0.000073 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000091 U	< 0.000083 U	< 0.00012 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.00048 U	< 0.00051 U	< 0.00052 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.0019 U	< 0.00030 U	< 0.00057 U	< 0.00061 U	< 0.00062 U	< 0.00038 U	< 0.00035 U	< 0.00050 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0060 U	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0041 U	< 0.0020 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.00062 UT	< 0.000097 U	< 0.00018 U	< 0.00019 UT	< 0.00020 UT	< 0.00012 UT	< 0.00011 UT	< 0.00016 UT
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00028 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.00048 U	< 0.00051 U	< 0.00052 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 UT	< 0.00038 UT	< 0.00023 UT	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 UT	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.00021 U	< 0.00035 U	0.00040 J	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00050 U	< 0.00034 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.000091 U	< 0.00015 U	< 0.00014 U	< 0.000099 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000080 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 UT	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00051 U	< 0.00035 UT	< 0.00060 U	< 0.00039 U	< 0.00038 U	< 0.00028 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 UT	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.00038 U	< 0.00065 U	< 0.00061 U	< 0.00042 U	< 0.00072 U	< 0.00046 U	< 0.00045 U	< 0.00034 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0030 U	< 0.0054 U	< 0.0020 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0030 U	< 0.0024 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	0.00037 J
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.00012 UT	< 0.00021 UT	< 0.00019 UT	< 0.00013 UT	< 0.00023 UT	< 0.00015 U	< 0.00014 UT	< 0.00011 UT
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	0.00057 J
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 UT	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 UT	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 UT	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 UT	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 UT	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 UT	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 UT	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00051 U	< 0.00035 UT	< 0.00060 U	< 0.00039 U	< 0.00038 U	< 0.00028 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 UT	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 UT	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 UT	< 0.00044 U	< 0.00028 U	< 0.00028 U	0.00038 J
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 UT	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 UT	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 UT	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 UT	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 UT	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 UT	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	0.018	< 0.0014 U	< 0.00048 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0060 U	< 0.00070 U	< 0.00052 U	< 0.0022 U	< 0.00072 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.00034 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.00012 U	< 0.00069 U	< 0.00011 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00063 U	< 0.00021 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.00043 U	< 0.0024 U	< 0.00041 U	< 0.0061 U	< 0.00071 U	< 0.00052 U	< 0.0022 U	< 0.00073 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.00051 U	< 0.0029 U	< 0.00048 U	< 0.0073 U	< 0.00085 U	< 0.00062 U	< 0.0026 U	< 0.00087 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0026 U	< 0.0021 U	< 0.0034 U	< 0.0097 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00035 U	< 0.0020 U	0.00085 J	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.00016 UT	< 0.00092 U	< 0.00015 UT	< 0.0023 U	< 0.00027 UT	< 0.00020 U	< 0.00084 UT	< 0.00028 UT
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.00031 U	0.0055	0.0011	< 0.0044 U	< 0.00051 U	0.053	0.0020 J	< 0.00052 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	0.017	< 0.00060 U	0.0033 J	< 0.0019 U	< 0.00061 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.00043 U	< 0.0024 U	< 0.00040 U	< 0.0061 U	< 0.00071 U	< 0.00052 U	< 0.0022 U	< 0.00073 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00031 U	0.0034 J	0.00054 J	< 0.0045 U	0.00081 J	0.027	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.00029 U	< 0.00022 U	0.00042 J	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.00026 U	< 0.00020 U	0.00066 J	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00025 U	< 0.00050 U	< 0.00033 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.00011 U	< 0.000086 U	< 0.00012 U	< 0.000094 U	< 0.000073 U	< 0.00014 U	< 0.000094 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.00040 U	< 0.00031 U	< 0.00043 U	< 0.00033 U	< 0.00026 U	< 0.00051 U	< 0.00033 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.00047 U	< 0.00036 U	< 0.00052 U	< 0.00040 U	< 0.00031 U	< 0.00061 U	< 0.00039 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0020 U	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0036 U	< 0.0034 U	< 0.0022 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	0.00029 J	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.00015 UT	< 0.00012 U	< 0.00016 UT	< 0.00013 UT	< 0.000098 UT	< 0.00019 UT	< 0.00013 U
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00080 J	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 UT	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 UT	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 UT	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	0.00034 J	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 UT	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 UT	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 UT	< 0.00029 U	< 0.00019 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.00039 U	< 0.00030 U	0.00083 J	< 0.00033 U	< 0.00026 UT	< 0.00051 U	< 0.00033 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 UT	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 UT	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00029 U	< 0.00022 UT	< 0.00032 U	0.00030 J	< 0.00019 UT	< 0.00037 UT	< 0.00024 U
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	0.00026 J	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	0.00027 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21-20220520	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00066 U
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17-20220520	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	SSHS-DW-10 11	060622 10:25 SSHS-DW-10 11-SUB-6-8	SSHS-DW-10 11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-DW-13 14	060622 10:25 SSHS-DW-13 14-SUB-6-8	SSHS-DW-13 14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-6-8	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-6-8	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-7 8	060622 10:25 SSHS-DW-7 8-SUB-6-8	SSHS-DW-7 8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated	< 0.001 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2-20220606	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated	< 0.00017 U	0.0011	< 0.00038 U	< 0.00051 U	< 0.00016 U	0.00035 J	0.00035 J
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1-20220606	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated	< 0.00025 U	0.00048 J	< 0.00057 U	< 0.00077 U	< 0.00024 U	< 0.00027 U	< 0.00024 U
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801-20220607	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800-20220607	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800-20220607	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00035 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803-20220607	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802-20220607	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106-20220609	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	0.00046 J	< 0.00019 U	0.00046 J
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16-20220609	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	0.00043 J	< 0.00020 U	0.00043 J
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT-20220609	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated	< 0.00017 U	0.00086 J	< 0.00038 U	< 0.00052 U	0.00053 J	< 0.00018 U	0.00053 J
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110-20220610	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20-20220610	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812-20220610	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26-20220610	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220611	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220611	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220611	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220611	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2-20220613	SSHS-IRM5A2-FISR-S2	6/13/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395961	Not Excavated	< 0.00020 U	0.00086 J	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3-20220613	SSHS-IRM5A2-FISR-S3	6/13/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395961	Not Excavated	< 0.00020 U	0.0016	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4-20220613	SSHS-IRM5A2-FISR-S4	6/13/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395961	Not Excavated	< 0.00020 U	0.0012	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6-20220613	SSHS-IRM5A2-FISR-S6	6/13/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395961	Not Excavated	< 0.00018 U	0.00080 J	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10-20220613	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26-20220613	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated	< 0.0011 U	0.0029 J	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34-20220613	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated	< 0.0010 U	0.0048 J	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42-20220614	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated	< 0.000072 U	0.0025	< 0.00016 U	< 0.00022 U	< 0.000070 U	< 0.000078 U	< 0.000070 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124-20220615	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00015 U	0.023	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17-20220615	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated	< 0.00025 U	< 0.00046 U	< 0.00058 U	< 0.00078 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33-20220615	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated	< 0.00018 U	0.014	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41-20220615	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated	< 0.00030 U	0.0022	< 0.00069 U	< 0.00092 U	< 0.00029 U	< 0.00033 U	< 0.00029 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400-20220616	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600-20220616	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 0.0013 U	< 0.0021 U	< 0.0055 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0095 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602-20220616	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603-20220616	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604-20220616	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600-20220616	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602-20220616	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603-20220616	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608-20220616	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606-20220617	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607-20220617	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608-20220617	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	0.0011 J	0.0013	0.0023
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609-20220617	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609-20220617	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated	< 0.000096 UT	< 0.00017 UT	< 0.00022 U	< 0.00029 U	< 0.000094 UT	< 0.00010 UT	< 0.000094 UT
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610-20220617	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	0.0021	0.0019	0.0040
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137-20220620	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134-20220620	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 UT	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-6-8	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-6-8	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-6-8	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18-20220620	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated	< 0.00016 U	0.0021	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610-20220620	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611-20220620	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00049 U	< 0.00066 UT	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612-20220620	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613-20220620	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614-20220620	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00047 U	< 0.00064 UT	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615-20220620	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 UT	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16-20220620	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated	< 0.00025 U	0.0025	< 0.00058 U	< 0.00078 UT	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618-20220620	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated	< 0.00018 U	0.00079 J	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619-20220620	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1-20220620	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	0.0022	0.0026	0.0049
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611-20220620	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612-20220620	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613-20220620	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614-20220620	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615-20220620	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated	< 0.00020 U	0.00046 J	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616-20220620	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00057 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	0.012	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.0082 U	< 0.00037 U	< 0.00040 U	< 0.00037 U	< 0.00061 U	< 0.0014 U	< 0.00038 U	< 0.00055 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.0072 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0013 UT	< 0.00033 U	< 0.00049 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 U	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	0.0078	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	0.0071	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.0064 U	< 0.00029 UT	< 0.00032 UT	< 0.00029 UT	< 0.00048 UT	< 0.0011 UT	< 0.00030 U	< 0.00043 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 UT	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 UT	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 UT	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 UT	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	0.0063	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.0049 UT	< 0.00022 UT	< 0.00024 UT	< 0.00022 UT	< 0.00037 UT	< 0.00086 UT	< 0.00023 UT	< 0.00033 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	0.0094	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.0064 UT	< 0.00029 UT	< 0.00031 U	< 0.00029 UT	< 0.00047 UT	< 0.0011 U	< 0.00030 UT	< 0.00043 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	0.0074	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00050 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801401241	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 UT	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801401241	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 UT	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801401241	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 UT	< 0.00029 U	< 0.00061 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801401241	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00042 U	< 0.00078 U	< 0.00035 UT	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0021 BJ	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0026 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0023 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0021 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0028 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0028 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0028 BJ	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0027 BJ	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0030 BJ	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0027 BJ	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0027 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0027 BJ	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0024 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0026 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0025 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0026 BJ	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0022 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0028 BJ	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0025 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0019 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0023 J	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0028 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0037 BJ	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0039 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0041 BJ	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0040 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0042 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	0.0031 BJ	< 0.0025 U	< 0.0030 U	< 0.0041 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0043 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0035 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.00025 U	< 0.00028 U	< 0.00075 U	< 0.0014 U	< 0.00062 U	< 0.00032 U	< 0.00066 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00055 UT	< 0.00028 U	< 0.00058 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 UT	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.00020 UT	< 0.00022 UT	< 0.00059 U	< 0.0011 UT	< 0.00049 UT	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 UT	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 UT	< 0.00019 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 UT	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 UT	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 UT	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 UT	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 UT	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 UT	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 UT	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 UT	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 UT	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00042 U	< 0.00077 U	< 0.00035 UT	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.00015 UT	< 0.00017 UT	< 0.00045 UT	< 0.00083 UT	< 0.00037 UT	< 0.00019 UT	< 0.00040 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	0.0037 BJ	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0036 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.00020 UT	< 0.00022 UT	< 0.00058 U	< 0.0011 UT	< 0.00049 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00019 U	< 0.00041 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00049 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	851.31	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0057 U	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.00048 U	< 0.00052 U	< 0.00052 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.00042 U	< 0.00045 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.0013 UT	< 0.00020 UT	< 0.00038 U	< 0.00040 UT	< 0.00041 UT	< 0.00025 UT	< 0.00023 U	< 0.00033 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.00092 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.00098 UT	< 0.00015 UT	< 0.00029 UT	< 0.00031 UT	< 0.00031 UT	< 0.00019 UT	< 0.00018 UT	< 0.00025 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.0013 UT	< 0.00020 UT	< 0.00038 U	< 0.00040 UT	< 0.00041 UT	< 0.00025 UT	< 0.00023 U	< 0.00033 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 UT	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 UT	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.00030 U	0.00065 J	0.00065 J	< 0.00033 UT	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 UT	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0029 U	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00031 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.00032 U	< 0.00055 U	< 0.00051 U	< 0.00035 U	< 0.00061 U	< 0.00039 U	< 0.00038 U	< 0.00028 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00028 U	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.00025 U	< 0.00043 UT	< 0.00040 UT	< 0.00028 UT	< 0.00047 U	< 0.00031 UT	< 0.00030 UT	< 0.00022 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.0023 U	< 0.0040 U	< 0.0037 U	< 0.0026 U	< 0.0044 U	< 0.0028 U	< 0.0028 U	< 0.0021 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.00019 UT	< 0.00033 UT	< 0.00031 UT	< 0.00021 UT	< 0.00036 UT	< 0.00023 UT	< 0.00023 UT	< 0.00017 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.00025 U	< 0.00043 UT	< 0.00040 UT	< 0.00027 UT	< 0.00047 U	< 0.00030 UT	< 0.00030 UT	< 0.00022 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0025 U	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.00043 U	< 0.0024 U	< 0.00041 U	< 0.0062 U	< 0.00071 U	< 0.00053 U	< 0.0022 U	< 0.00073 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00038 U	< 0.0021 U	< 0.00036 U	< 0.0054 U	< 0.00063 U	< 0.00046 U	< 0.0019 U	< 0.00064 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 UT	< 0.0048 U	< 0.00056 UT	< 0.00041 UT	< 0.0017 UT	< 0.00057 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.00026 UT	< 0.0015 UT	< 0.00025 UT	< 0.0037 UT	< 0.00043 UT	< 0.00032 UT	< 0.0013 UT	< 0.00044 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-FL-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.00034 U	< 0.0019 UT	< 0.00032 UT	< 0.0048 U	< 0.00056 U	< 0.00041 UT	< 0.0017 UT	< 0.00057 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-FL-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-FL-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-FL-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-FL-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-FL-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-FL-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0019 U	< 0.0019 U	< 0.0026 U	0.0024 J	< 0.0035 U	< 0.0032 U	< 0.0021 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.00037 J	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	0.00053 J	< 0.00031 U	< 0.00044 U	0.00035 J	< 0.00026 U	< 0.00051 U	< 0.00033 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00023 U	< 0.00045 U	< 0.00029 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	0.00035 JT	< 0.00024 U	< 0.00034 UT	< 0.00026 UT	< 0.00020 U	< 0.00040 UT	< 0.00026 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	0.00093	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	0.00030 J	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.00024 UT	< 0.00018 UT	< 0.00026 UT	< 0.00020 UT	< 0.00016 UT	< 0.00031 UT	< 0.00020 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	0.00046 J	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.00031 UT	< 0.00024 U	< 0.00034 UT	< 0.00026 UT	< 0.00020 UT	< 0.00040 UT	< 0.00026 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00025 J	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00024 J	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617-20220620	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618-20220620	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619-20220620	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated	< 0.00024 U	0.0088	< 0.00054 U	< 0.00073 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620-20220620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138-20220621	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621-20220621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622-20220621	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623-20220621	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624-20220621	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625-20220621	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626-20220621	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627-20220621	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628-20220621	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629-20220621	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630-20220621	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631-20220621	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 0.0011 U	0.0025 J	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632-20220621	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636-20220621	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637-20220621	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638-20220621	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639-20220621	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140-20220622	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141-20220622	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616-20220622	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617-20220622	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814-20220622	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51-20220630	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52-20220630	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58-20220630	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56-20220630	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62-20220630	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68-20220630	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 0.0013 U	< 0.0020 U	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61-20220630	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67-20220630	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2-20220708	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5-20220708	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8-20220708	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated	< 0.00025 U	< 0.00046 U	< 0.00058 U	< 0.00078 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154-20220711	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00051 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1-20220711	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2-20220711	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4-20220711	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6-20220711	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8-20220711	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated	< 0.00020 UT	< 0.00036 UT	< 0.00046 U	< 0.00061 U	< 0.00020 UT	< 0.00022 UT	< 0.00020 UT
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10-20220711	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12-20220711	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14-20220711	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16-20220711	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18-20220711	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20-20220711	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22-20220711	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24-20220711	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26-20220711	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30-20220711	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32-20220711	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34-20220711	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36-20220711	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38-20220711	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40-20220711	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated	< 0.00015 UT	< 0.00028 UT	< 0.00035 UT	< 0.00047 UT	< 0.00015 UT	< 0.00017 UT	< 0.00015 UT
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3-20220711	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6-20220711	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7-20220711	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1-20220714	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated	< 0.00017 UT	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE-5A-20220720	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE-5B-20220720	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173-20220725	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-FL-PIPE24-S1-20220725	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated	< 0.00020 UT	< 0.00036 UT	< 0.00045 U	< 0.00061 U	< 0.00019 UT	< 0.00022 UT	< 0.00019 UT
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-FL-PIPE24-S2-20220725	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-FL-PIPE24-S3-20220725	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-FL-PIPE24-S4-20220725	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00042 U	< 0.00057 U	0.00019 J	< 0.00020 U	0.00019 J
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-FL-PIPE24-S5-20220725	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-FL-PIPE24-S6-20220725	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-FL-PIPE24-S7-20220725	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-FL-PIPE24-S9-20220725	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-FL-PIPE24-B1-20220725	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	0.0059	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	0.018	< 0.00036 U	< 0.00039 U	< 0.00036 U	< 0.00059 U	< 0.0014 U	0.0033	< 0.00054 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.0081 U	< 0.00036 U	< 0.00040 U	< 0.00036 U	< 0.00060 U	< 0.0014 U	< 0.00038 U	< 0.00055 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.0068 U	< 0.00031 UT	< 0.00033 UT	< 0.00031 UT	< 0.00051 UT	< 0.0012 U	< 0.00032 UT	< 0.00046 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.026 U	< 0.0012 U	< 0.0013 U	< 0.0011 U	< 0.0019 U	< 0.0045 U	< 0.0012 U	< 0.0017 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	0.0012	< 0.00038 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.0075 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 UT	< 0.00051 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	0.0063 J	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	0.00057 J	< 0.00041 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.0065 U	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.0079 U	< 0.00036 U	< 0.00039 U	< 0.00035 U	< 0.00059 U	< 0.0014 U	< 0.00037 U	< 0.00053 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.0089 U	< 0.00040 U	< 0.00044 U	< 0.00040 U	< 0.00066 U	< 0.0016 U	< 0.00041 U	< 0.00060 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.0085 U	< 0.00038 U	< 0.00042 U	< 0.00038 U	< 0.00063 U	< 0.0015 U	< 0.00040 U	< 0.00058 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.0076 UT	< 0.00034 UT	< 0.00037 UT	< 0.00034 UT	< 0.00057 UT	< 0.0013 UT	< 0.00035 UT	< 0.00052 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	0.0071	< 0.00021 UT	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.0053 U	< 0.00024 UT	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.0060 U	< 0.00027 UT	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	0.0063	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	< 0.00034 U	< 0.00050 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	0.0080	< 0.00025 UT	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.0088 U	< 0.00039 U	< 0.00043 U	< 0.00039 U	< 0.00065 U	< 0.0015 U	< 0.00041 U	< 0.00059 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00065 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	0.013	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.0059 U	< 0.00026 UT	< 0.00029 U	< 0.00026 UT	< 0.00044 U	< 0.0010 U	< 0.00027 UT	< 0.00040 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.0055 U	0.00029 J	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	0.00034 J	< 0.00038 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.0029 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00051 U	< 0.00013 U	< 0.00020 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.0023 U	< 0.00010 U	< 0.00011 U	< 0.00010 U	< 0.00017 U	< 0.00040 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated								

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00073 U	< 0.0014 U	< 0.00061 U	< 0.00031 U	< 0.00064 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00019 U	< 0.00041 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00074 U	< 0.0014 U	< 0.00062 U	< 0.00031 U	< 0.00065 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.00021 UT	< 0.00023 UT	< 0.00062 U	< 0.0012 UT	< 0.00052 U	< 0.00026 U	< 0.00055 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.00079 U	< 0.00087 U	< 0.0023 U	< 0.0043 U	< 0.0019 U	< 0.00099 U	< 0.0021 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00069 U	< 0.0013 U	< 0.00057 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.00024 U	< 0.00027 U	< 0.00072 U	< 0.0013 U	< 0.00060 U	< 0.00030 U	< 0.00063 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	0.00034 J	< 0.00045 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.00027 U	< 0.00030 U	< 0.00081 U	< 0.0015 U	< 0.00067 U	< 0.00034 U	< 0.00071 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.00026 U	< 0.00029 U	< 0.00078 U	< 0.0014 U	< 0.00065 U	< 0.00033 U	< 0.00068 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.00024 UT	< 0.00026 UT	< 0.00070 UT	< 0.0013 UT	< 0.00058 UT	< 0.00029 UT	< 0.00061 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.00015 UT	< 0.00016 UT	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.00016 UT	< 0.00018 UT	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.00019 UT	< 0.00020 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 UT
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.00017 UT	< 0.00019 UT	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.00027 U	< 0.00030 U	< 0.00080 U	< 0.0015 U	< 0.00067 U	< 0.00034 U	< 0.00070 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00063 U	< 0.00028 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.000082 U	< 0.000090 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00054 U	< 0.0010 UT	< 0.00045 UT	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.000090 U	< 0.000098 U	< 0.00026 U	< 0.00049 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.000071 U	< 0.000078 U	< 0.00021 U	< 0.00039 U	< 0.00018 U	< 0.000089 U	< 0.00019 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00047 U	< 0.00050 U	< 0.00051 U	< 0.00031 U	< 0.00029 U	< 0.00041 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00048 U	< 0.00051 U	< 0.00052 U	< 0.00032 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.0014 UT	< 0.00021 UT	< 0.00040 U	< 0.00043 UT	< 0.00043 UT	< 0.00027 UT	< 0.00025 UT	< 0.00035 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.0051 U	< 0.00080 U	< 0.0015 U	< 0.0016 U	< 0.0016 U	< 0.0010 U	< 0.00092 U	< 0.0013 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00044 U	< 0.00047 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00047 U	< 0.00050 U	< 0.00050 U	< 0.00031 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.0018 U	< 0.00028 U	< 0.00052 U	< 0.00056 U	< 0.00057 U	< 0.00035 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.0017 U	< 0.00027 U	< 0.00050 U	< 0.00054 U	< 0.00054 U	< 0.00033 U	< 0.00031 U	< 0.00044 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.0015 UT	< 0.00024 UT	< 0.00045 UT	< 0.00048 UT	< 0.00049 UT	< 0.00030 UT	< 0.00027 UT	< 0.00039 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.00094 U	< 0.00015 UT	< 0.00028 U	< 0.00030 UT	< 0.00030 UT	< 0.00019 UT	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.0011 U	< 0.00017 UT	< 0.00031 U	< 0.00034 UT	< 0.00034 UT	< 0.00021 UT	< 0.00019 U	< 0.00028 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.0012 U	< 0.00019 UT	< 0.00036 U	< 0.00038 UT	< 0.00039 UT	< 0.00024 UT	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00026 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00096 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00017 UT	< 0.00033 U	< 0.00035 UT	< 0.00035 UT	< 0.00022 UT	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.0018 U	< 0.00028 U	< 0.00052 U	< 0.00055 U	< 0.00056 U	< 0.00034 U	< 0.00032 U	< 0.00045 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.00053 U	< 0.000084 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000096 U	< 0.00014 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 UT	< 0.00025 UT	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 UT	< 0.00022 UT	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.0012 UT	< 0.00018 UT	< 0.00035 U	< 0.00037 U	< 0.00037 UT	< 0.00023 UT	< 0.00021 UT	< 0.00030 UT
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.00058 U	< 0.000091 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.00046 U	< 0.000073 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000091 U	< 0.000083 U	< 0.00012 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00040 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.00031 U	< 0.00053 U	< 0.00050 U	< 0.00034 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.00032 U	< 0.00054 U	< 0.00051 U	< 0.00035 U	< 0.00060 U	< 0.00039 U	< 0.00038 U	< 0.00028 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.00027 U	< 0.00046 UT	< 0.00043 UT	< 0.00029 UT	< 0.00050 UT	< 0.00033 UT	< 0.00032 UT	< 0.00024 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0012 U	< 0.0012 U	< 0.00089 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.00030 U	< 0.00050 U	< 0.00047 U	< 0.00032 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.00031 U	< 0.00053 U	< 0.00049 U	< 0.00034 U	< 0.00058 U	< 0.00038 U	< 0.00037 U	< 0.00027 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 UT	< 0.00026 UT	< 0.00019 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.00035 U	< 0.00059 U	< 0.00056 U	< 0.00038 U	< 0.00066 U	< 0.00042 U	< 0.00041 U	< 0.00031 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.00033 U	< 0.00057 U	< 0.00053 U	< 0.00037 U	< 0.00063 U	< 0.00041 U	< 0.00040 U	< 0.00030 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.00030 UT	< 0.00051 UT	< 0.00048 UT	< 0.00033 UT	< 0.00056 UT	< 0.00036 UT	< 0.00035 UT	< 0.00027 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 UT	< 0.00022 UT	< 0.00016 UT
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 UT	< 0.00025 UT	< 0.00019 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 UT	< 0.00028 UT	< 0.00021 UT
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.00026 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00032 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 UT	< 0.00026 UT	< 0.00019 UT
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.00034 U	< 0.00058 U	< 0.00055 U	< 0.00038 U	< 0.00065 U	< 0.00042 U	< 0.00041 U	< 0.00030 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.00024 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.00023 U	< 0.00039 UT	< 0.00037 UT	< 0.00025 UT	< 0.00043 UT	< 0.00028 UT	< 0.00027 UT	< 0.00020 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.00010 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.000091 U	< 0.00015 U	< 0.00014 U	< 0.000099 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000080 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00058 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00040 U	< 0.0060 U	< 0.00070 U	0.0046 J	< 0.0022 U	< 0.00071 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.00043 U	< 0.0024 U	< 0.00040 U	< 0.0061 U	< 0.00071 U	< 0.00052 U	< 0.0022 U	< 0.00072 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 UT	< 0.0051 U	< 0.00059 U	< 0.00044 UT	< 0.0019 UT	< 0.00061 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.0013 U	< 0.0076 U	< 0.0013 U	< 0.019 U	< 0.0022 U	< 0.0016 U	< 0.0069 U	< 0.0023 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.00040 U	< 0.0022 U	< 0.00037 U	< 0.0057 U	< 0.00066 U	< 0.00048 U	< 0.0020 U	< 0.00067 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00034 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.00041 U	< 0.0024 U	< 0.00039 U	< 0.0059 U	< 0.00069 U	< 0.00051 U	< 0.0021 U	< 0.00070 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 UT	< 0.0042 U	0.00054 J	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.00047 U	< 0.0027 U	< 0.00044 U	< 0.0067 U	< 0.00077 U	< 0.00057 U	< 0.0024 U	< 0.00079 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.00045 U	< 0.0025 U	< 0.00042 U	< 0.0064 U	< 0.00074 U	< 0.00055 U	< 0.0023 U	< 0.00076 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.00040 UT	< 0.0023 UT	< 0.00038 UT	< 0.0057 UT	< 0.00067 UT	< 0.00049 UT	< 0.0021 UT	< 0.00068 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 UT	< 0.0035 U	< 0.00041 U	< 0.00032 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	0.00071 J	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	0.00060 J	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 UT	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 UT	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 UT	< 0.00054 UT
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	0.00059 J	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.00034 U	< 0.0019 UT	< 0.00032 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.00030 U	< 0.0017 UT	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.00030 U	< 0.0017 UT	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.00030 U	< 0.0017 UT	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.00039 U	< 0.0022 UT	< 0.00037 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00025 U	< 0.0014 UT	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.00029 U	< 0.0017 UT	< 0.00028 UT	< 0.0042 UT	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.00029 U	< 0.0017 UT	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.00031 U	< 0.0017 UT	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.00046 U	< 0.0026 UT	< 0.00044 U	< 0.0064 U	< 0.00076 U	< 0.00056 U	< 0.0024 U	< 0.00078 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.00033 U	< 0.0019 UT	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.00020 U	< 0.0011 UT	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00033 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.00014 U	< 0.00079 UT	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.00029 U	< 0.0016 UT	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00029 U	< 0.0016 UT	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 UT	< 0.00053 UT
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.00015 U	< 0.00087 U	< 0.00014 U	< 0.0022 U	< 0.00025 U	< 0.00019 U	< 0.00079 U	< 0.00026 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.00012 U	< 0.00069 U	< 0.00012 U	< 0.0017 U	< 0.00020 U	< 0.00015 U	< 0.00063 U	< 0.00021 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00025 U	< 0.00050 U	< 0.00033 U
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00043 U	< 0.00033 U	< 0.00026 U	< 0.00051 U	< 0.00033 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.00033 UT	< 0.00025 U	< 0.00036 UT	< 0.00028 UT	< 0.00022 UT	< 0.00043 UT	< 0.00028 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00096 U	< 0.0014 U	< 0.0010 U	< 0.00081 U	< 0.0016 U	< 0.0010 U
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00042 U	< 0.00032 U	< 0.00025 U	< 0.00049 U	< 0.00032 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.00043 U	< 0.00033 U	< 0.00047 U	< 0.00036 U	< 0.00028 U	< 0.00056 U	< 0.00036 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.00041 U	< 0.00032 U	< 0.00045 U	< 0.00035 U	< 0.00027 U	< 0.00053 U	< 0.00035 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.00037 UT	< 0.00029 UT	< 0.00041 UT	< 0.00031 UT	< 0.00024 UT	< 0.00048 UT	< 0.00031 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.00023 UT	< 0.00018 U	< 0.00025 UT	0.00040 JT	< 0.00015 U	< 0.00029 UT	< 0.00019 UT
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 UT
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	0.00045 J	< 0.00016 U	< 0.00031 U	< 0.00020 UT
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.00026 UT	< 0.00020 UT	< 0.00028 U	< 0.00022 UT	< 0.00017 U	< 0.00033 UT	< 0.00022 UT
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.00029 UT	< 0.00023 UT	< 0.00032 UT	< 0.00025 UT	< 0.00019 U	< 0.00038 UT	< 0.00025 U
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	0.00058 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	0.00045 J	< 0.00021 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	0.00060 J	< 0.00023 U	< 0.00032 U	0.00068 J	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00076 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00051 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00054 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	0.00040 J	< 0.00015 UT	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.00027 UT	< 0.00021 U	< 0.00030 UT	0.00099 T	< 0.00018 UT	< 0.00035 UT	< 0.00023 U
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	0.00047 J	< 0.00021 U	< 0.00030 U	0.00061 J	< 0.00018 UT	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	0.00062 J	< 0.00022 U	< 0.00031 U	0.00044 J	< 0.00018 UT	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.00043 U	< 0.00033 U	< 0.00047 U	0.00088 J	< 0.00028 UT	< 0.00055 U	< 0.00036 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.00030 J	< 0.00020 UT	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 U	< 0.00015 U	< 0.00012 UT	< 0.00023 U	< 0.00015 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.00013 U	< 0.000099 U	< 0.00014 U	< 0.00011 U	< 0.000084 UT	< 0.00017 U	< 0.00011 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	0.00097	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	0.00026 J	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 UT	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 UT	< 0.00037 U	< 0.00024 UT
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00087 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	0.00033 J	< 0.00011 U	< 0.00015 U	0.00016 J	< 0.00092 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.00011 U	< 0.000086 U	< 0.00012 U	< 0.000094 U	< 0.000073 U	< 0.00014 U	< 0.000094 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	0.00036 J	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-FL-PIPE24-B2-20220725	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-FL-PIPE24-B3-20220725	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1-20220725	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00049 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2-20220725	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3-20220725	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated	< 0.00025 U	< 0.00045 U	< 0.00057 U	< 0.00076 U	0.00031 J	< 0.00027 U	0.00031 J
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4-20220725	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	0.00020 J	< 0.00017 U	0.00020 J
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6-20220725	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated	< 0.00025 U	< 0.00045 U	< 0.00057 U	< 0.00077 U	< 0.00025 U	< 0.00027 U	< 0.00025 U
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7-20220725	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated	< 0.00021 UT	< 0.00038 UT	< 0.00048 U	< 0.00065 UT	< 0.00021 UT	< 0.00023 UT	< 0.00021 UT
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8-20220725	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated	< 0.00079 U	< 0.0014 U	< 0.0018 U	< 0.0024 U	0.0011 J	< 0.00087 U	0.0011 J
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10-20220725	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177-20220726	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601-20220726	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated	< 0.00023 U	< 0.00042 U	< 0.00053 U	< 0.00072 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604-20220726	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612-20220726	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182-20220728	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1-20220728	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2-20220728	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1-20220728	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated	< 0.00025 U	< 0.00044 U	< 0.00056 U	< 0.00075 U	< 0.00024 U	< 0.00027 U	< 0.00024 U
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3-20220728	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4-20220728	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5-20220728	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6-20220728	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7-20220728	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated	< 0.00028 U	< 0.00050 U	< 0.00063 U	< 0.00085 U	< 0.00027 U	< 0.00030 U	< 0.00027 U
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8-20220728	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated	< 0.00026 U	< 0.00048 U	< 0.00060 U	< 0.00081 U	< 0.00026 U	< 0.00029 U	< 0.00026 U
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4-20220728	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9-20220728	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated	< 0.00017 U	0.00098	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10-20220728	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated	< 0.00024 UT	< 0.00043 UT	< 0.00054 UT	< 0.00073 UT	< 0.00023 UT	< 0.00026 UT	< 0.00023 UT
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A-20220808	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A-20220808	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1-20220808	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1-20220808	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2-20220808	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3-20220808	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4-20220808	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5-20220808	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6-20220808	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7-20220808	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8-20220808	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1-20220808	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2-20220808	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3-20220808	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4-20220808	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801-20220808	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated	< 0.00015 UT	< 0.00026 UT	< 0.00033 U	< 0.00045 U	< 0.00014 UT	< 0.00016 UT	< 0.00014 UT
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802-20220808	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803-20220808	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	0.00018 J	< 0.00017 U	0.00018 J
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804-20220808	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated	< 0.00017 UT	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 UT	< 0.00018 UT	< 0.00016 UT
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15-20220808	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated	< 0.00019 UT	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 UT	< 0.00020 UT	< 0.00018 UT
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17-20220808	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19-20220808	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT-20220809	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	0.00027 J	< 0.00018 U	0.00027 J
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2-20220810	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4-20220810	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A-20220810	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A-20220810	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A-20220810	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A-20220810	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191-20220811	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652-20220811	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated	< 0.00017 UT	< 0.00031 UT	< 0.00039 U	< 0.00053 U	< 0.00017 UT	< 0.00019 UT	< 0.00017 UT
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653-20220811	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654-20220811	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662-20220811	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated	< 0.00027 U	< 0.00049 U	< 0.00062 U	< 0.00084 U	< 0.00027 U	< 0.00030 U	< 0.00027 U
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A-20220811	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663-20220811	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664-20220811	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated	< 0.000083 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000081 U	< 0.000090 U	< 0.000081 U
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665-20220811	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668-20220811	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669-20220811	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00061 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672-20220811	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673-20220811	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated	< 0.00018 UT	< 0.00033 UT	< 0.00042 U	< 0.00056 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193-20220812	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	0.00036 J	0.00020 J	0.00056 J
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677-20220812	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated	< 0.000090 U	< 0.00016 U	< 0.00021 U	< 0.00028 U	0.000097 J	< 0.000098 U	0.000097 J
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A-20220812	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated	< 0.000072 U	< 0.00013 U	< 0.00016 U	< 0.00022 U	< 0.000070 U	< 0.000078 U	< 0.000070 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684-20220812	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00049 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220813	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.0034 U	< 0.00015 UT	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00059 U	< 0.00016 UT	< 0.00023 UT
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.0039 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00029 U	< 0.00068 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 U	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00060 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 U	< 0.00067 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	0.0038	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00022 U	< 0.00051 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 UT
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 UT
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00050 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00046 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.0089 U	< 0.00040 UT	< 0.00044 U	< 0.00040 U	< 0.00066 U	< 0.0016 U	< 0.00042 U	< 0.00060 UT
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.0071 U	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 UT
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.0077 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00057 U	< 0.0013 U	< 0.00036 U	< 0.00052 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 UT	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.016 U	< 0.00072 U	< 0.00078 U	< 0.00072 U	< 0.0012 U	< 0.0028 U	< 0.00074 U	< 0.0011 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.0054 U	0.00060 J	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.01 U	< 0.00045 UT	< 0.00049 UT	< 0.00045 UT	< 0.00075 UT	< 0.0018 U	< 0.00047 UT	< 0.00068 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.0079 U	0.00051 J	< 0.00039 U	< 0.00036 U	< 0.00059 U	< 0.0014 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	0.0057	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	0.0057	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated								
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	0.016	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	0.013	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.0076 U	< 0.00034 U	< 0.00037 U	< 0.00034 U	< 0.00056 U	< 0.0013 U	< 0.00035 U	< 0.00051 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.0083 U	< 0.00038 U	< 0.00041 U	< 0.00037 U	< 0.00062 U	< 0.0015 U	< 0.00039 U	< 0.00056 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	0.088	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 U	< 0.00048 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	0.054	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0041 UT	< 0.0015 UT	< 0.0032 UT	< 0.0024 UT	< 0.0026 UT	< 0.0024 UT	< 0.0042 UT	< 0.0021 UT
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	0.029	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0020 U	< 0.0036 U	< 0.0018 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00089 U	< 0.00024 U	< 0.00035 U

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.000096 U	< 0.00011 U	< 0.00028 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.00010 UT	< 0.00011 UT	< 0.00031 U	< 0.00057 UT	< 0.00026 U	< 0.00013 UT	< 0.00027 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00066 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.000079 U	< 0.000086 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000098 U	< 0.00020 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00065 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.000090 U	< 0.000099 U	< 0.00027 U	< 0.00050 U	< 0.00022 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.00028 UT	< 0.00030 U	< 0.00082 U	< 0.0015 U	< 0.00068 U	< 0.00035 U	< 0.00072 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00070 U	< 0.0013 U	< 0.00058 U	< 0.00030 U	< 0.00062 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.00015 U	< 0.00017 UT	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.00049 U	< 0.00054 U	< 0.0015 U	< 0.0027 U	< 0.0012 U	< 0.00062 U	< 0.0013 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.00031 UT	< 0.00034 UT	< 0.00092 U	< 0.0017 UT	< 0.00076 U	< 0.00039 UT	< 0.00081 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00072 U	< 0.0013 U	< 0.00060 U	< 0.00031 U	< 0.00064 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated							
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00026 U	< 0.00069 U	< 0.0013 U	< 0.00058 U	< 0.00029 U	< 0.00061 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.00026 UT	< 0.00028 UT	< 0.00076 U	< 0.0014 U	< 0.00063 U	< 0.00032 U	< 0.00067 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	< 0.00027 U	< 0.00057 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.00022 U	< 0.00025 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	< 0.00028 U	< 0.00058 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0014 UT	< 0.0026 UT	< 0.0031 UT	< 0.0017 UT	< 0.0021 UT	< 0.0025 UT	< 0.0034 U
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0018 U	< 0.0021 U	< 0.0029 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.00062 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.00067 UT	< 0.00011 UT	< 0.00020 U	< 0.00021 UT	< 0.00021 UT	< 0.00013 UT	< 0.00012 UT	< 0.00017 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.00078 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.00051 U	< 0.000080 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000091 U	< 0.00013 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.00069 U	< 0.00011 U	< 0.00020 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.00059 U	< 0.000092 U	< 0.00017 U	< 0.00018 U	< 0.00019 U	< 0.00011 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.0018 U	< 0.00028 UT	< 0.00053 U	< 0.00056 UT	< 0.00057 UT	< 0.00035 UT	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	0.00098 J	< 0.00015 U	< 0.00028 UT	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 UT	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 UT	< 0.00048 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.00099 U	< 0.00016 UT	< 0.00029 UT	< 0.00031 UT	< 0.00032 U	< 0.00019 UT	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.0032 U	< 0.00050 U	< 0.00094 U	< 0.0010 U	< 0.0010 U	< 0.00063 U	< 0.00057 U	< 0.00083 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.0020 UT	< 0.00032 UT	< 0.00059 U	< 0.00063 UT	< 0.00064 UT	< 0.00040 UT	< 0.00036 UT	< 0.00052 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.0016 U	< 0.00025 U	< 0.00047 U	< 0.00050 U	< 0.00051 U	< 0.00031 U	< 0.00029 U	< 0.00041 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	0.0016 J	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated								
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00048 U	< 0.00048 U	< 0.00030 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00049 U	< 0.00053 UT	< 0.00053 UT	< 0.00033 UT	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00046 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 UT	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0047 UT	< 0.0014 UT	< 0.0026 UT	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 UT	< 0.0015 UT
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.0041 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0028 U	< 0.0013 U	< 0.0014 U	< 0.0013 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.00013 UT	< 0.00022 UT	< 0.00021 UT	< 0.00014 UT	< 0.00025 UT	< 0.00016 UT	< 0.00016 UT	< 0.00012 UT
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000088 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00018 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00032 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00024 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.00035 U	< 0.00060 U	< 0.00056 U	< 0.00038 U	< 0.00066 U	< 0.00043 UT	< 0.00042 UT	< 0.00031 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00048 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 UT	< 0.00023 UT	< 0.00017 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.00063 U	< 0.0011 U	< 0.0010 U	< 0.00069 U	< 0.0012 U	< 0.00076 U	< 0.00074 U	< 0.00055 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.00040 UT	< 0.00067 UT	< 0.00063 UT	< 0.0043 UT	< 0.00074 UT	< 0.00048 UT	< 0.00047 UT	< 0.00035 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.00031 U	< 0.00053 U	< 0.00050 U	< 0.00034 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated								
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00047 U	< 0.00033 U	< 0.00056 U	< 0.00036 U	< 0.00035 U	< 0.00026 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.00019 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00052 U	< 0.00036 U	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.00028 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00052 U	< 0.00034 U	< 0.00033 U	< 0.00025 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00045 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0024 UT	< 0.0043 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 UT	< 0.0023 UT	< 0.0024 UT	< 0.0019 UT
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0020 U	< 0.0017 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated								
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.00016 U	< 0.00093 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00084 U	< 0.00028 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.00018 UT	< 0.0010 UT	< 0.00017 UT	< 0.0025 U	< 0.00029 UT	< 0.00022 UT	< 0.00092 UT	< 0.00030 UT
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.00020 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.00013 U	< 0.00076 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00069 U	< 0.00023 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00094 U	< 0.00031 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0029 U	< 0.00033 U	< 0.00025 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00087 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00079 U	< 0.00026 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.00047 U	< 0.0027 U	< 0.00045 U	< 0.0067 UT	< 0.00078 U	< 0.00057 U	< 0.0024 U	< 0.00080 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated								
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0053 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00063 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00031 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0058 U	< 0.00067 U	< 0.00049 U	< 0.0021 U	< 0.00069 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 UT
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.00084 U	< 0.0048 U	< 0.00079 U	< 0.012 U	< 0.0014 U	< 0.0010 U	< 0.0043 U	< 0.0014 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	0.00083 J	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00054 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.00053 U	< 0.0030 UT	< 0.00050 UT	< 0.0076 U	< 0.00088 UT	< 0.00065 UT	< 0.0027 UT	< 0.00090 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00039 U	< 0.0060 U	0.00095 J	< 0.00051 U	< 0.0022 U	< 0.00071 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated								
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0057 U	< 0.00066 U	< 0.00049 U	< 0.0021 U	< 0.00068 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	0.0075	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00042 U	< 0.0063 UT	< 0.00073 U	< 0.00054 U	< 0.0023 U	< 0.00075 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	0.02	< 0.00062 U	0.014	< 0.0019 U	< 0.00063 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00063 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0013 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0021 UT	< 0.0017 UT	< 0.0027 UT	< 0.0077 UT	< 0.0025 UT	< 0.0027 UT	< 0.0019 UT	< 0.0015 UT
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0066 U	< 0.0022 U	< 0.0023 U	< 0.0016 U	< 0.0013 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	0.00019 J	< 0.000098 U	< 0.00019 U	< 0.00013 U
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.00016 UT	< 0.00013 UT	< 0.00018 UT	0.00017 JT	< 0.00011 U	< 0.00021 UT	< 0.00014 UT
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.00019 U	< 0.00014 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.00012 U	< 0.000095 U	< 0.00014 U	< 0.00010 U	< 0.000080 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	0.00031 J	< 0.00014 U	< 0.00020 U	0.00018 J	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	0.00017 J	< 0.000093 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.00034 J	< 0.00019 UT	< 0.00037 UT	< 0.00024 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 UT	< 0.00037 UT	< 0.00024 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 UT	< 0.00046 UT	< 0.00030 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 UT	< 0.00042 UT	< 0.00028 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.00043 UT	< 0.00033 UT	< 0.00048 U	< 0.00037 UT	< 0.00028 U	< 0.00056 UT	< 0.00036 UT
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.00034 U	< 0.00027 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 UT
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	0.00023 J	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	0.00046 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.00037 U	< 0.00029 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00040 J	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	0.00024 J
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00042 J	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.00078 U	< 0.00060 U	< 0.00085 U	< 0.00065 U	< 0.00050 U	< 0.0010 U	< 0.00065 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	0.00098	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00028 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	0.00041 J	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	0.0012	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.00049 UT	< 0.00038 UT	< 0.00054 UT	< 0.00041 UT	< 0.00032 UT	< 0.00063 UT	< 0.00041 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.00039 U	< 0.00030 U	< 0.00042 U	0.00080 J	< 0.00025 U	< 0.00050 U	< 0.00032 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	0.00063 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	0.00063 J	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated							
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00037 U	< 0.00028 U	< 0.00040 U	< 0.00031 U	< 0.00024 U	< 0.00047 U	< 0.00031 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	0.00023 J	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.00041 UT	< 0.00031 U	< 0.00044 UT	< 0.00034 U	< 0.00026 U	< 0.00052 UT	< 0.00034 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00038 U	< 0.00029 U	< 0.00022 U	< 0.00044 U	< 0.00029 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.00035 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00045 U	< 0.00030 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0016 UT	< 0.0016 UT	< 0.0021 UT	< 0.0015 UT	< 0.0029 U	< 0.0027 U	< 0.0018 UT
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.0013 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220813	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801430891	Not Excavated							
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220813	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated							
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92-20220815	SSHS-IRM5A2-FISR-S92	8/15/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429581	Not Excavated	< 0.000096 U	< 0.00017 U	< 0.00022 U	< 0.00030 U	0.000095 J	< 0.00011 U	0.000095 J
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93-20220815	SSHS-IRM5A2-FISR-S93	8/15/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429581	Not Excavated	< 0.00010 UT	< 0.00019 UT	< 0.00024 U	< 0.00032 U	0.00010 JT	< 0.00011 UT	0.00010 JT
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96-20220815	SSHS-IRM5A2-FISR-S96	8/15/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00027 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690-20220815	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated	< 0.000079 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000077 U	< 0.000086 U	< 0.000077 U
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691-20220815	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21-20220815	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11-20220815	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated	< 0.000091 U	< 0.00016 U	< 0.00021 U	< 0.00028 U	< 0.000089 U	< 0.000099 U	< 0.000089 U
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10-20220817	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11-20220817	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696-20220817	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430811	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700-20220817	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430811	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701-20220817	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00070 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702-20220817	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430811	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1-20220817	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430811	Not Excavated	< 0.00028 UT	< 0.00050 U	< 0.00063 U	< 0.00085 U	< 0.00027 UT	< 0.00030 U	< 0.00027 U
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated							
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2-20220817	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430811	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00050 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81-20220818	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 UT	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84-20220818	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88-20220818	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated	< 0.00024 U	0.00071 J	< 0.00055 U	< 0.00073 UT	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604-20220823	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600-20220823	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated	< 0.00015 UT	< 0.00028 U	< 0.00035 U	< 0.00047 UT	0.00017 J	< 0.00017 U	0.00017 J
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601-20220823	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602-20220823	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated	< 0.00015 U	0.00030 J	< 0.00035 U	< 0.00047 U	0.00019 J	< 0.00017 U	0.00019 J
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603-20220823	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated	< 0.00050 U	< 0.00089 U	< 0.0011 U	< 0.0015 U	< 0.00049 U	< 0.00054 U	< 0.00049 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207-20220824	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	0.00049 J	0.00022 J	0.00071 J
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205-20220824	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600-20220824	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601-20220824	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602-20220824	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802-20220824	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26-20220824	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated	< 0.00031 UT	< 0.00056 UT	< 0.00071 U	< 0.00096 U	< 0.00031 UT	< 0.00034 UT	< 0.00031 UT
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605-20220824	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606-20220824	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated	< 0.00025 U	< 0.00044 U	< 0.00056 U	< 0.00076 U	0.00035 J	< 0.00027 U	0.00035 J
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600-20220824	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	0.00019 J	< 0.00020 U	0.00019 J
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211-20220825	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806-20220825	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807-20220825	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808-20220825	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2-20220825	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704-20220825	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707-20220825	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20-20220826	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated							
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213-20220901	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	0.00018 J	< 0.00019 U	0.00018 J
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605-20220901	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606-20220901	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607-20220901	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00054 U	< 0.00072 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608-20220901	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609-20220901	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600-20220901	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00059 U	< 0.00080 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601-20220901	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated	< 0.00022 U	< 0.00040 U	< 0.00050 U	< 0.00068 U	< 0.00022 U	< 0.00024 U	< 0.00022 U
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602-20220901	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00069 U	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216-20220902	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603-20220902	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604-20220902	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605-20220902	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606-20220902	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607-20220902	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated	< 0.00091 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608-20220902	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated	< 0.0010 UT	< 0.0017 UT	< 0.0044 UT	< 0.0038 UT	< 0.0019 UT	< 0.0021 UT	< 0.0076 UT
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609-20220902	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610-20220902	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611-20220902	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated	< 0.00093 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612-20220902	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated	< 0.00089 U	< 0.0014 U	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0065 U
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613-20220902	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614-20220902	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412-20220902	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615-20220906	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610-20220906	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00045 UT	< 0.0010 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.0065 U	< 0.00030 U	< 0.00032 U	< 0.00029 U	< 0.00049 UT	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 UT	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 UT	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00026 U	< 0.00039 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	0.0073	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 UT	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	0.0072	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 UT	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 UT	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.0084 U	< 0.00038 U	< 0.00041 U	< 0.00038 U	< 0.00062 UT	< 0.0015 U	< 0.00039 U	< 0.00057 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.0069 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 UT	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 UT	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446691	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.0077 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00057 UT	< 0.0014 U	< 0.00036 U	< 0.00052 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 UT	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	0.012	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 UT	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00031 U	< 0.00051 UT	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 UT	< 0.0011 U	< 0.00028 U	< 0.00041 UT
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.0074 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00055 U	< 0.0013 U	< 0.00034 U	< 0.00050 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	0.02	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.0032 U	< 0.00015 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00056 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 UT	< 0.00059 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	0.074	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 UT	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 U	< 0.00027 UT	< 0.00063 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.0032 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 UT	< 0.00057 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 UT	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	0.031	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 UT	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.0041 U	< 0.00018 U	< 0.00020 UT	< 0.00018 UT	< 0.00030 UT	< 0.00071 U	< 0.00019 UT	< 0.00028 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 UT	< 0.00085 U	< 0.00023 U	< 0.00033 UT
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	0.02	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 UT	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	0.036	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 UT	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 UT	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	0.017	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 UT	< 0.0011 U	< 0.00029 U	< 0.00042 UT
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	0.02	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	0.011	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 UT	< 0.00049 U	< 0.00013 U	< 0.00019 UT
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 UT	< 0.00044 U	< 0.00012 U	< 0.00017 UT
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 UT	< 0.00088 U	< 0.00023 U	< 0.00034 UT
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.0026 U	0.00013 J	< 0.00013 U	< 0.00012 U	< 0.00020 UT	< 0.00046 U	< 0.00012 U	< 0.00018 UT
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 UT	< 0.00088 U	< 0.00023 U	< 0.00034 UT
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.0054 U	0.00026 J	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00094 U	< 0.00025 U	< 0.00036 UT
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.0077 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00057 U	< 0.0014 U	< 0.00036 U	< 0.00052 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00020 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00025 U	< 0.00053 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00043 U	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00015 U	< 0.00017 UT	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.00020 U	< 0.00022 UT	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00063 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00028 UT	< 0.00076 U	< 0.0014 U	< 0.00064 U	< 0.00032 U	< 0.00067 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00063 U	< 0.0012 U	< 0.00052 U	< 0.00027 U	< 0.00055 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00024 U	< 0.00026 UT	< 0.00071 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00062 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00023 UT	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00068 U	< 0.0013 U	< 0.00056 U	< 0.00029 U	< 0.00060 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00029 U	< 0.00055 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.000082 U	< 0.000090 U	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00032 U	< 0.00059 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00033 U	< 0.00061 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00055 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.00015 U	< 0.00016 UT	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.00014 U	< 0.00016 UT	< 0.00043 U	< 0.00079 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.00013 UT	< 0.00014 UT	< 0.00037 U	< 0.00069 UT	< 0.00031 U	< 0.00016 UT	< 0.00033 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	0.0035 J	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0034 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.00015 U	< 0.00017 UT	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	< 0.00019 U	< 0.00021 UT	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.000087 U	< 0.000096 UT	< 0.00026 U	< 0.00048 U	< 0.00021 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.000078 U	< 0.000085 UT	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000097 U	< 0.00020 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.000082 U	< 0.000090 UT	< 0.00024 U	< 0.00045 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00070 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00062 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00041 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00029 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00049 U	< 0.00053 U	< 0.00053 U	< 0.00033 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00046 U	< 0.00049 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 UT	< 0.00039 UT	< 0.00024 UT	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00044 U	< 0.00047 U	< 0.00047 U	< 0.00029 U	< 0.00027 U	< 0.00038 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.00064 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.00053 U	< 0.000083 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000095 U	< 0.00014 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00072 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.00065 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.00082 U	< 0.00013 UT	< 0.00024 UT	< 0.00026 UT	< 0.00026 UT	< 0.00016 UT	< 0.00015 U	< 0.00021 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	0.0014 J	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.00057 U	< 0.000089 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.00050 U	< 0.000079 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.000099 U	< 0.00010 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.00053 U	< 0.000083 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000095 U	< 0.00014 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00046 U	< 0.00049 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.00033 U	< 0.00056 U	< 0.00052 U	< 0.00036 U	< 0.00062 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00030 U	< 0.00052 U	< 0.00048 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 UT	< 0.00021 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00032 U	< 0.00055 U	< 0.00035 U	< 0.00034 U	< 0.00026 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.00013 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00017 U	< 0.00012 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.00016 UT	< 0.00027 UT	< 0.00026 UT	< 0.00018 UT	< 0.00030 U	< 0.00019 UT	< 0.00019 UT	< 0.00014 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 UT	< 0.00024 UT	< 0.00018 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 UT	< 0.00025 UT	< 0.00018 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000098 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.000099 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000087 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00017 U	< 0.00011 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.000092 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00030 U	< 0.00052 U	< 0.00048 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.00034 U	< 0.0020 U	< 0.00033 U	< 0.0049 U	< 0.00057 U	< 0.00042 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00041 U	< 0.00031 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00056 U	< 0.00042 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00042 U	< 0.0063 U	< 0.00073 U	< 0.00054 U	< 0.0023 U	< 0.00075 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00039 U	< 0.0058 U	< 0.00068 U	< 0.00050 U	< 0.0021 U	< 0.00069 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 UT	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.00039 U	< 0.0022 U	< 0.00037 U	< 0.0056 U	< 0.00065 U	< 0.00048 U	< 0.0020 U	< 0.00066 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00096 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00087 U	< 0.00029 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.00014 U	< 0.00079 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00029 U	< 0.00022 U	< 0.00092 U	< 0.00030 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00031 U	0.0031	< 0.00095 U	< 0.00031 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00033 U	< 0.00023 U	< 0.00097 U	< 0.00032 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.00017 U	< 0.00097 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00088 U	< 0.00029 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	0.058	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.00021 UT	< 0.0012 UT	< 0.00020 UT	< 0.0031 U	< 0.00036 UT	< 0.00026 UT	< 0.0011 UT	< 0.00036 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated								
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	0.0035 J	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0045 U	< 0.00052 U	0.0052	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 UT	< 0.00046 UT
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 UT	< 0.00047 UT
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.00013 U	< 0.00075 U	< 0.00012 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00068 U	< 0.00022 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.00014 U	< 0.00079 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00072 U	< 0.00024 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00038 U	< 0.0058 U	< 0.00067 U	< 0.00050 U	< 0.0021 U	< 0.00069 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.00032 U	< 0.00024 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.00028 U	< 0.00021 U	0.00068 J	0.0017	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.00030 U	< 0.00023 U	0.0036	0.0073	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	0.00062 J	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.0014	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.0058	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.0011	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	0.013	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	0.0019	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	0.0010 J	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.00041 U	< 0.00031 U	< 0.00045 U	< 0.00034 U	< 0.00026 U	< 0.00052 U	< 0.00034 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00037 U	0.0052	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	0.0052	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	0.0056	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00041 U	0.0025	< 0.00024 U	< 0.00048 U	< 0.00032 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	0.0095	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	0.0016	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.00030 UT	< 0.00023 U	< 0.00033 UT	0.0012	< 0.00019 U	< 0.00038 UT	< 0.00025 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	0.0011	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.00036 U	< 0.00028 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	0.013	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.0022	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	0.0028	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	0.00034 J	< 0.00020 U	< 0.00029 U	0.0096	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.012	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.00013 U	< 0.000099 U	< 0.00014 U	0.0013	< 0.000084 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	0.00091	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	0.00093	< 0.00011 U	< 0.00022 U	< 0.00015 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00066 J	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	0.0036	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.00020 UT	< 0.00015 U	< 0.00022 UT	0.00081 T	< 0.00013 UT	< 0.00026 UT	< 0.00017 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	0.00062 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.00024 U	< 0.00018 U	0.00070 J	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00025 J	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	0.0015	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	< 0.00024 U	< 0.00019 U	0.0041	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000089 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	0.00016 J	< 0.000094 U	< 0.00013 U	0.00010 J	< 0.000079 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	0.00025 J	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.00013 U	< 0.000099 U	< 0.00014 U	0.00020 J	< 0.000084 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	0.00075 J	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00041 U	< 0.00032 U	< 0.00024 U	< 0.00048 U	< 0.00031 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220-20220908	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804-20220908	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated	< 0.00020 U	< 0.00037 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805-20220908	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806-20220908	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807-20220908	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422-20220913	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 0.00018 U	0.0016	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437-20220913	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 0.00019 U	0.0056	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11-20220914	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230-20220916	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231-20220916	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A-20220916	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A-20220916	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A-20220916	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A-20220916	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A-20220916	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00059 U	< 0.00080 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B-20220916	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611-20220916	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612-20220916	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613-20220916	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00055 U	< 0.00074 U	< 0.00024 U	< 0.00026 U	< 0.00024 U
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614-20220916	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615-20220916	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616-20220916	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617-20220916	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 UT	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618-20220916	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619-20220916	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated	< 0.00023 U	0.00043 J	< 0.00053 U	< 0.00071 U	< 0.00023 U	< 0.00025 U	< 0.00023 U
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15-20220916	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16-20220916	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17-20220916	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18-20220916	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	0.00031 J	0.00031 J
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8-20220916	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	0.00027 J	0.00027 J
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621-20220916	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000098 U	< 0.00011 U	< 0.000098 U
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622-20220916	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000081 U	< 0.000090 U	< 0.000081 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233-20220919	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00010 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA-20220919	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB-20220919	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC-20220919	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000099 U	< 0.00011 U	< 0.000099 U
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1-20220919	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2-20220919	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3-20220919	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated	< 0.00013 U	< 0.00023 UT	< 0.00029 UT	< 0.00039 UT	< 0.00012 UT	< 0.00014 UT	< 0.00012 UT
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427-20220919	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624-20220927	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237-20220929	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A-20220929	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A-20220929	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A-20220929	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A-20220929	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A-20220929	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628-20220929	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629-20220929	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221020	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221020	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221020	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221020	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221020	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221020	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated							
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221020	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221020	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221020	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446-20221024	SSHS-IRM5A2-A6-B446	10/24/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801468441	Not Excavated	< 0.00015 U	0.00079 J	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649-20221024	SSHS-IRM5A2-A6-B649	10/24/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650-20221024	SSHS-IRM5A2-A6-B650	10/24/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632-20221024	SSHS-IRM5A2-A6-S632	10/24/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801468441	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633-20221024	SSHS-IRM5A2-A6-S633	10/24/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801468441	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634-20221024	SSHS-IRM5A2-A6-S634	10/24/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801468441	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639-20221024	SSHS-IRM5A2-A6-S639	10/24/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640-20221024	SSHS-IRM5A2-A6-S640	10/24/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00035 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641-20221024	SSHS-IRM5A2-A6-S641	10/24/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801468451	Not Excavated	< 0.00016 U	0.0012	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246-20221026	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000086 U	< 0.000096 U	< 0.000086 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13-20221026	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated	< 0.000078 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000076 U	< 0.000085 U	< 0.000076 U
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14-20221026	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15-20221026	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated	< 0.000082 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000081 U	< 0.000090 U	< 0.000081 U
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16-20221026	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17-20221026	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262-20221201	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00055 U	< 0.00074 U	< 0.00023 U	< 0.00026 U	< 0.00023 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	0.0062	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.0041 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00053 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00026 U	< 0.00039 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.0057 U	< 0.00026 UT	< 0.00028 UT	< 0.00026 UT	< 0.00042 UT	< 0.0010 U	< 0.00027 UT	< 0.00039 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00060 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.0037 U	< 0.00017 U	< 0.00018 U	< 0.00017 U	< 0.00028 U	< 0.00066 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated								
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated								
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.0046	< 0.00061	< 0.00063	< 0.00051	< 0.0004	< 0.00067	< 0.00047	< 0.00041
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.0047	< 0.00063	< 0.00064	< 0.00052	< 0.00041	< 0.00069	< 0.00048	< 0.00042
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.021 U	< 0.0053 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.011 U	< 0.0053 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.021	< 0.0052		< 0.0052	< 0.0052	< 0.0052	< 0.01	< 0.0052
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00019 U	< 0.00041 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00070 U	< 0.00032 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.000094 U	< 0.00010 U	< 0.00028 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.00018 UT	< 0.00019 UT	< 0.00052 UT	< 0.00097 UT	< 0.00043 UT	< 0.00022 UT	< 0.00046 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00019 UT	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.000097 U	< 0.00011 UT	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00031 U	< 0.00058 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00034 U	< 0.00064 U	< 0.00029 U	< 0.00014 U	< 0.00030 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0036 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UT	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 UT	< 0.0033 U	< 0.0019 U	< 0.0023 U	< 0.0032 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 UT	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0039 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated							
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated							
Northern Athletic Field	SSHS-B71	081614 09:00_DUP-20	081614 09:00_DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00069	< 0.00065	< 0.0014	< 0.00053	< 0.00078	< 0.00034	< 0.00068
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00071	< 0.00066	< 0.0014	< 0.00055	< 0.00079	< 0.00035	< 0.0007
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052		
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30_SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-8-10	082719 09:30_SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30_SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30_SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30_SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30_SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30_SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30_SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30_SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30_SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00_SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00_SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00_SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3020	082819 09:00_SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00_SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00_SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00_SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00_SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	0.0013 J	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.00083 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.00061 U	< 0.000095 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	0.0014 J	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	0.0033	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00029 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.0011 UT	< 0.00018 UT	< 0.00034 UT	< 0.00036 UT	< 0.00036 UT	< 0.00022 UT	< 0.00021 UT	< 0.00030 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	0.0031	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.00063 U	< 0.000099 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00022 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00075 U	< 0.00012 U	< 0.00022 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.0044 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0030 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 UT	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated								
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated								
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00061	< 0.00079	< 0.00061	< 0.00073	< 0.0006	< 0.00058	< 0.00052	< 0.00056
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00063	< 0.0008	< 0.00062	< 0.00074	< 0.00061	< 0.00059	< 0.00054	< 0.00057
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.0053 U			< 0.35 U	< 0.35 U	< 0.35 U	< 0.0053 U	< 0.0053 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.0052			< 0.34	< 0.34	< 0.34	< 0.0052	< 0.0052
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 UT	< 0.00019 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	0.00074 J
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.00022 UT	< 0.00038 UT	< 0.00036 UT	< 0.00025 UT	< 0.00042 UT	< 0.00027 UT	< 0.00027 UT	< 0.00020 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 UT	< 0.00012 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00023 U	< 0.00016 U	< 0.00028 U	< 0.00018 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated								
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated								
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00077		< 0.00064	< 0.00054	< 0.00049	< 0.00062	< 0.00054	< 0.00058
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00079		< 0.00066	< 0.00056	< 0.00051	< 0.00063	< 0.00056	< 0.0006
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.0053 U		< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.0052		< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052	< 0.0052
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00091 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00019 U	< 0.00082 U	< 0.00027 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.00030 UT	< 0.0017 UT	< 0.00028 UT	< 0.0043 U	< 0.00050 UT	< 0.00037 UT	< 0.0016 UT	< 0.00051 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00093 U	< 0.00031 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0028 U	< 0.00033 U	< 0.00024 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 UT	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0021 U	< 0.0016 UT	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 UT	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.0020 U	< 0.0015 UT	< 0.0025 U	< 0.0072 U	< 0.0024 U	< 0.0025 UT	< 0.0018 UT	< 0.0014 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.0020 U	< 0.0015 UT	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 UT	< 0.0018 UT	< 0.0015 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 UT	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 UT	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 UT	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 UT	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0023 U	< 0.0018 UT	< 0.0030 U	< 0.0085 UT	< 0.0028 U	< 0.0029 UT	< 0.0021 UT	< 0.0017 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated								
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated								
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated								
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated								
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00097	< 0.00063	< 0.00062	< 0.00082	< 0.00066	< 0.0008	< 0.00059	< 0.00068
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00099	< 0.00064	< 0.00063	< 0.00084	< 0.00068	< 0.00082	< 0.00061	< 0.0007
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.0053 U	< 0.011 U				< 0.011 U	< 0.011 U	
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.0052	< 0.01				< 0.01	< 0.01	
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated								
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated								
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated								
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated								
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated								
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated								
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated								
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated								
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated								
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated								
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00043 J	< 0.00018 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	0.00042 J	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.00025 UT	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.00020 UT	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.00024 UT	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.00015 UT	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000096 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00025 U	< 0.00019 U	0.00028 J	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.00028 U	< 0.00021 U	0.0032	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.00028 UT	< 0.00021 UT	0.0020 T	< 0.00023 UT	< 0.00018 UT	< 0.00036 UT	< 0.00023 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00023 U	< 0.00018 U	0.00035 J	< 0.00020 U	< 0.00015 U	< 0.00030 U	0.00022 J
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00018 U	< 0.00014 U	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 UT	< 0.00024 U	< 0.00019 UT	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 UT	< 0.00021 U	< 0.00016 UT	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 UT	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 UT	< 0.00025 U	< 0.00019 UT	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00020 UT	< 0.00015 U	< 0.00012 UT	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 UT	< 0.00022 U	< 0.00017 UT	< 0.00033 U	< 0.00022 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated							
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated							
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00064	< 0.00065	< 0.00062	< 0.00066	< 0.00077	< 0.0008	< 0.00044
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00066	< 0.00067	< 0.00063	< 0.00068	< 0.00079	< 0.00082	< 0.00045
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U		< 0.35 U	< 0.0053 U
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.0052	< 0.0052	< 0.0052	< 0.0052		< 0.34	< 0.0052
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602-20221201	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603-20221201	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604-20221202	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	0.00024 J	< 0.00019 U	0.00024 J
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268-20221209	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1-20221209	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	0.0038	0.0014	0.0052
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2-20221209	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7-20221209	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8-20221209	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated	< 0.000094 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000092 U	< 0.00010 U	< 0.000092 U
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233-20221209	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235-20221209	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236-20221209	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00016 U	0.0011	< 0.00036 U	< 0.00049 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238-20221209	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated	< 0.00018 U	0.0059	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A-20221209	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated	< 0.00018 UT	0.0053 T	< 0.00041 UT	< 0.00055 UT	< 0.00017 UT	< 0.00019 UT	< 0.00017 UT
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A-20221209	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated	< 0.00015 U	0.0011	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439-20221209	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2-20221209	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated	< 0.000098 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5-20221209	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00033 U	< 0.00010 U	< 0.00012 U	< 0.00010 U
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13-20221214	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16-20221214	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated	< 0.00016 U	0.0010	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19-20221214	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22-20221214	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25-20221214	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00027 U	< 0.00036 U	< 0.00011 U	< 0.00013 U	< 0.00011 U
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26-20221214	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26-20230601	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31-20230602	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38-20230602	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6-20230606	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7-20230606	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 0.00097 U	< 0.0015 U	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3-20230606	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 0.00098 U	< 0.0015 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A-20230710	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1-20230710	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2-20230710	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1-20230710	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A-20230814	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4-20230814	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5-20230814	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6-20230814	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1-20230814	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9-20231129	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated							
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12-20231130	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16-20231130	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20-20231130	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332-20231201	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26-20231201	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated							
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27-20231201	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28-20231201	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated							
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9-20231201	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated							
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00076	< 0.0006	< 0.00084	< 0.00043		< 0.00071	
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated	< 0.00077	< 0.00061	< 0.00086	< 0.00044		< 0.00073	
Northern Athletic Field	SSHS-B37	12 SEP 00B37 8-10	12 Sep 00B37 8-10	9/12/2000	856.46	855.88	-0.57	--	8 - 10 ft	7.42-9.43 ft	NA	Not Excavated	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	< 0.0053 U	
Northern Athletic Field	SSHS-B46	13 SEP 00B46 8-10	B46-8-10	9/13/2000	858.24	858.17	-0.07	-	8 - 10 ft	7.93-9.93 ft	NA	Not Excavated	< 0.0052	< 0.0052	< 0.0052	< 0.0052		< 0.0052	
Northern Athletic Field	SSHS-B572	SSHS-B572-SUB-8-10	SSHS-B572-SUB-8-10	8/30/2016	852.49	854.82	2.33	-	8 - 10 ft	10.33-12.33 ft	180-58129-1	Not Excavated							
Northern Athletic Field	SSHS-B2030	072818 11:30 SSHS-B2030-SUB-8-10	SSHS-B2030-SUB-8-10	7/27/2018	856.20	856.42	0.22	-	8 - 10 ft	8.22-10.22 ft	180-80252-1	Not Excavated							
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-8-10	SSHS-B3008-SUB-8-10	8/26/2019	852.37	854.67	2.30	-	8 - 10 ft	10.3-12.3 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-8-10	082719 09:30 SSHS-B3021-SUB-8-10	8/26/2019	853.71	855.73	2.02	-	8 - 10 ft	10.02-12.02 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3022	082719 09:30 SSHS-B3022-SUB-8-10	SSHS-B3022-SUB-8-10	8/26/2019	853.76	855.66	1.90	-	8 - 10 ft	9.9-11.9 ft	180-94754-3	Not Excavated							
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-8-10	SSHS-B3034-SUB-8-10	8/26/2019	855.10	856.53	1.43	-	8 - 10 ft	9.43-11.43 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3035	082719 09:30 SSHS-B3035-SUB-8-10	SSHS-B3035-SUB-8-10	8/26/2019	854.81	856.27	1.46	-	8 - 10 ft	9.46-11.46 ft	180-94752-1	Not Excavated							
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-8-10	SSHS-B3049-SUB-8-10	8/26/2019	856.17	857.50	1.33	-	8 - 10 ft	9.33-11.33 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3050	082719 09:30 SSHS-B3050-SUB-8-10	SSHS-B3050-SUB-8-10	8/26/2019	855.60	856.84	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94752-2	Not Excavated							
Northern Athletic Field	SSHS-B3064	082719 09:30 SSHS-B3064-SUB-8-10	SSHS-B3064-SUB-8-10	8/26/2019	856.77	857.84	1.07	-	8 - 10 ft	9.07-11.07 ft	180-94754-2	Not Excavated							
Northern Athletic Field	SSHS-B3065	082719 09:30 SSHS-B3065-SUB-8-10	SSHS-B3065-SUB-8-10	8/26/2019	856.77	857.30	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3078	082719 09:30 SSHS-B3078-SUB-8-10	SSHS-B3078-SUB-8-10	8/26/2019	856.70	857.12	0.42	-	8 - 10 ft	8.42-10.42 ft	180-94752-3	Not Excavated							
Northern Athletic Field	SSHS-B3098	082719 09:30 SSHS-B3098-SUB-8-10	SSHS-B3098-SUB-8-10	8/26/2019	855.97	857.05	1.08	-	8 - 10 ft	9.08-11.08 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3099	082719 09:30 SSHS-B3099-SUB-8-10	SSHS-B3099-SUB-8-10	8/26/2019	856.40	856.53	0.13	-	8 - 10 ft	8.13-10.13 ft	180-94754-1	Not Excavated							
Northern Athletic Field	SSHS-B3006	082819 09:00 SSHS-B3006-SUB-8-10	SSHS-B3006-SUB-8-10	8/27/2019	852.36	852.39	0.03	-	8 - 10 ft	8.03-10.03 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-8-10	SSHS-B3007-SUB-8-10	8/27/2019	852.58	854.74	2.16	-	8 - 10 ft	10.16-12.16 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3018	082819 09:00 SSHS-B3018-SUB-8-10	SSHS-B3018-SUB-8-10	8/27/2019	853.82	854.59	0.77	-	8 - 10 ft	8.77-10.77 ft	180-94829-1	Not Excavated							
Northern Athletic Field	SSHS-B3019	082819 09:00 SSHS-B3019-SUB-8-10	SSHS-B3019-SUB-8-10	8/27/2019	854.09	855.31	1.22	-	8 - 10 ft	9.22-11.22 ft	180-94824-3	Not Excavated							
Northern Athletic Field	SSHS-B3020	082819 09:00 SSHS-B3020-SUB-8-10	SSHS-B3020-SUB-8-10	8/27/2019	853.86	855.74	1.88	-	8 - 10 ft	9.88-11.88 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3031	082819 09:00 SSHS-B3031-SUB-8-10	SSHS-B3031-SUB-8-10	8/27/2019	855.08	855.61	0.53	-	8 - 10 ft	8.53-10.53 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3032	082819 09:00 SSHS-B3032-SUB-8-10	SSHS-B3032-SUB-8-10	8/27/2019	855.25	856.15	0.90	-	8 - 10 ft	8.9-10.9 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3033	082819 09:00 SSHS-B3033-SUB-8-10	SSHS-B3033-SUB-8-10	8/27/2019	855.17	856.58	1.41	-	8 - 10 ft	9.41-11.41 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3046	082819 09:00 SSHS-B3046-SUB-8-10	SSHS-B3046-SUB-8-10	8/27/2019	856.22	856.03	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-94824-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3245	122119 10:30 SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3042	082919 09:10_SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated						
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3069	083019 09:00_SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3233	122119 10:30_SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3235	122119 10:30_SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-B3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3245	122119 10:30 SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3042	082919 09:10_SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00_SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3233	122119 10:30_SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3235	122119 10:30_SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3047	082819 09:00 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated								
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated								
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated								
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated								
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated								
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated								
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated								
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated								
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated								
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated								
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated								
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated								
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated								
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated								
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated								
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated								
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated								
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated								
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated								
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated								
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated								
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated								
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated								
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated								
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated								
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated								
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated								
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated								
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated								
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated								
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3245	122119 10:30 SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated								
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3047	082819 09:10 SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3048	082819 09:00 SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3061	082819 09:00 SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated						
Northern Athletic Field	SSHS-B3062	082819 09:00 SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3063	082819 09:00 SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated						
Northern Athletic Field	SSHS-B3074	082819 09:00 SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated						
Northern Athletic Field	SSHS-B3076	082819 09:00 SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated						
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3097	082819 09:00 SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3017	082919 09:10 SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3029	082919 09:10 SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated						
Northern Athletic Field	SSHS-B3030	082919 09:10 SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3042	082919 09:10 SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3043	082919 09:10 SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3044	082919 09:10 SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3045	082919 09:10 SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3057	082919 09:10 SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3058	082919 09:10 SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3059	082919 09:10 SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated						
Northern Athletic Field	SSHS-B3060	082919 09:10 SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3070	082919 09:10 SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3071	082919 09:10 SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated						
Northern Athletic Field	SSHS-B3072	082919 09:10 SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated						
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated						
Northern Athletic Field	SSHS-B3095	082919 09:10 SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated						
Northern Athletic Field	SSHS-B3004	083019 09:00 SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated						
Northern Athletic Field	SSHS-B3005	083019 09:00 SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3054	083019 09:00 SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3069	083019 09:00 SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3079	083019 09:00 SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3083	083019 09:00 SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated						
Northern Athletic Field	SSHS-B3084	083019 09:00 SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3003	083119 10:15 SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3011	083119 10:15 SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3039	083119 10:15 SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3068	083119 10:15 SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3214	083119 10:15 SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated						
Northern Athletic Field	SSHS-B3222	083119 10:15 SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3001	090419 03:44 SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3002	090419 03:44 SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3009	090419 03:44 SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3010	090419 03:44 SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3023	090419 03:44 SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3024	090419 03:44 SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated						
Northern Athletic Field	SSHS-B3036	090419 03:44 SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated						
Northern Athletic Field	SSHS-B3038	090419 03:44 SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3052	090419 03:44 SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3053	090419 03:44 SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3051	090519 09:00 SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3066	090519 09:00 SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	090519 09:00 SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3085	090519 09:00 SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3086	090519 09:00 SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3244	122119 10:30 SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3245	122119 10:30 SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3246	122119 10:30 SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated						
Northern Athletic Field	SSHS-B3233	122119 10:30 SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3235	122119 10:30 SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated						

WORK

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3047	082819 09:00_SSHS-B3047-SUB-8-10	SSHS-B3047-SUB-8-10	8/27/2019	856.24	856.75	0.51	-	8 - 10 ft	8.51-10.51 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3048	082819 09:00_SSHS-B3048-SUB-8-10	SSHS-B3048-SUB-8-10	8/27/2019	856.08	857.32	1.24	-	8 - 10 ft	9.24-11.24 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3061	082819 09:00_SSHS-B3061-SUB-8-10	SSHS-B3061-SUB-8-10	8/27/2019	857.02	856.09	-0.93	-	8 - 10 ft	7.07-9.07 ft	180-94824-1	Not Excavated							
Northern Athletic Field	SSHS-B3062	082819 09:00_SSHS-B3062-SUB-8-10	SSHS-B3062-SUB-8-10	8/27/2019	856.91	856.86	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3063	082819 09:00_SSHS-B3063-SUB-8-10	SSHS-B3063-SUB-8-10	8/27/2019	856.95	857.80	0.85	-	8 - 10 ft	8.85-10.85 ft	180-94819-1	Not Excavated							
Northern Athletic Field	SSHS-B3074	082819 09:00_SSHS-B3074-SUB-8-10	SSHS-B3074-SUB-8-10	8/27/2019	857.18	856.02	-1.16	-	8 - 10 ft	6.84-8.84 ft	180-94824-2	Not Excavated							
Northern Athletic Field	SSHS-B3076	082819 09:00_SSHS-B3076-SUB-8-10	SSHS-B3076-SUB-8-10	8/27/2019	856.92	857.74	0.82	-	8 - 10 ft	8.82-10.82 ft	180-94819-2	Not Excavated							
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-8-10	SSHS-B3096-SUB-8-10	8/27/2019	855.86	856.29	0.43	-	8 - 10 ft	8.43-10.43 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3097	082819 09:00_SSHS-B3097-SUB-8-10	SSHS-B3097-SUB-8-10	8/27/2019	856.19	856.93	0.74	-	8 - 10 ft	8.74-10.74 ft	180-94819-3	Not Excavated							
Northern Athletic Field	SSHS-B3017	082919 09:10_SSHS-B3017-SUB-8-10	SSHS-B3017-SUB-8-10	8/28/2019	853.78	853.15	-0.63	-	8 - 10 ft	7.37-9.37 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3029	082919 09:10_SSHS-B3029-SUB-8-10	SSHS-B3029-SUB-8-10	8/28/2019	854.97	853.59	-1.38	-	8 - 10 ft	6.62-8.62 ft	180-94902-3	Not Excavated							
Northern Athletic Field	SSHS-B3030	082919 09:10_SSHS-B3030-SUB-8-10	SSHS-B3030-SUB-8-10	8/28/2019	855.22	855.02	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3042	082919 09:10_SSHS-B3042-SUB-8-10	SSHS-B3042-SUB-8-10	8/28/2019	855.23	857.40	2.17	-	8 - 10 ft	10.17-12.17 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3043	082919 09:10_SSHS-B3043-SUB-8-10	SSHS-B3043-SUB-8-10	8/28/2019	855.78	856.62	0.84	-	8 - 10 ft	8.84-10.84 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3044	082919 09:10_SSHS-B3044-SUB-8-10	SSHS-B3044-SUB-8-10	8/28/2019	856.00	854.20	-1.80	-	8 - 10 ft	6.2-8.2 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3045	082919 09:10_SSHS-B3045-SUB-8-10	SSHS-B3045-SUB-8-10	8/28/2019	856.03	855.07	-0.96	-	8 - 10 ft	7.04-9.04 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3057	082919 09:10_SSHS-B3057-SUB-8-10	SSHS-B3057-SUB-8-10	8/28/2019	856.09	857.58	1.49	-	8 - 10 ft	9.49-11.49 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3058	082919 09:10_SSHS-B3058-SUB-8-10	SSHS-B3058-SUB-8-10	8/28/2019	856.47	856.55	0.08	-	8 - 10 ft	8.08-10.08 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3059	082919 09:10_SSHS-B3059-SUB-8-10	SSHS-B3059-SUB-8-10	8/28/2019	856.71	854.42	-2.29	-	8 - 10 ft	5.71-7.71 ft	180-94902-1	Not Excavated							
Northern Athletic Field	SSHS-B3060	082919 09:10_SSHS-S3060-SUB-8-10	SSHS-S3060-SUB-8-10	8/28/2019	856.96	855.38	-1.58	-	8 - 10 ft	6.42-8.42 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3070	082919 09:10_SSHS-B3070-SUB-8-10	SSHS-B3070-SUB-8-10	8/28/2019	856.51	857.05	0.54	-	8 - 10 ft	8.54-10.54 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3071	082919 09:10_SSHS-B3071-SUB-8-10	SSHS-B3071-SUB-8-10	8/28/2019	856.76	856.63	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-94900-2	Not Excavated							
Northern Athletic Field	SSHS-B3072	082919 09:10_SSHS-B3072-SUB-8-10	SSHS-B3072-SUB-8-10	8/28/2019	856.89	856.00	-0.89	-	8 - 10 ft	7.11-9.11 ft	180-94900-3	Not Excavated							
Northern Athletic Field	SSHS-B3073	SSHS-B3073-SUB-8-10	SSHS-B3073-SUB-8-10	8/28/2019	857.14	855.25	-1.89	-	8 - 10 ft	6.11-8.11 ft	180-94900-1	Not Excavated							
Northern Athletic Field	SSHS-B3095	082919 09:10_SSHS-B3095-SUB-8-10	SSHS-B3095-SUB-8-10	8/28/2019	857.12	856.70	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-94902-2	Not Excavated							
Northern Athletic Field	SSHS-B3004	083019 09:00_SSHS-B3004-SUB-8-10	SSHS-B3004-SUB-8-10	8/29/2019	852.25	853.25	1.00	-	8 - 10 ft	9-11 ft	180-94981-2	Not Excavated							
Northern Athletic Field	SSHS-B3005	083019 09:00_SSHS-B3005-SUB-8-10	SSHS-B3005-SUB-8-10	8/29/2019	852.31	852.62	0.31	-	8 - 10 ft	8.31-10.31 ft	180-94981-3	Not Excavated							
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-8-10	SSHS-B3013-SUB-8-10	8/29/2019	852.90	857.00	4.10	-	8 - 10 ft	12.1-14.1 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-8-10	SSHS-B3040-SUB-8-10	8/29/2019	855.10	858.65	3.55	-	8 - 10 ft	11.55-13.55 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-8-10	SSHS-B3041-SUB-8-10	8/29/2019	855.17	858.67	3.50	-	8 - 10 ft	11.5-13.5 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3054	083019 09:00_SSHS-B3054-SUB-8-10	SSHS-B3054-SUB-8-10	8/29/2019	856.01	856.77	0.76	-	8 - 10 ft	8.76-10.76 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-8-10	SSHS-B3055-SUB-8-10	8/29/2019	856.20	858.70	2.50	-	8 - 10 ft	10.5-12.5 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-8-10	SSHS-B3056-SUB-8-10	8/29/2019	855.88	858.82	2.94	-	8 - 10 ft	10.94-12.94 ft	180-94981-1	Not Excavated							
Northern Athletic Field	SSHS-B3069	083019 09:00_SSHS-B3069-SUB-8-10	SSHS-B3069-SUB-8-10	8/29/2019	855.92	856.73	0.81	-	8 - 10 ft	8.81-10.81 ft	180-95006-1	Not Excavated							
Northern Athletic Field	SSHS-B3079	083019 09:00_SSHS-B3079-SUB-8-10	SSHS-B3079-SUB-8-10	8/29/2019	856.36	857.37	1.01	-	8 - 10 ft	9.01-11.01 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3083	083019 09:00_SSHS-B3083-SUB-8-10	SSHS-B3083-SUB-8-10	8/29/2019	857.13	857.39	0.26	-	8 - 10 ft	8.26-10.26 ft	180-95024-2	Not Excavated							
Northern Athletic Field	SSHS-B3084	083019 09:00_SSHS-B3084-SUB-8-10	SSHS-B3084-SUB-8-10	8/29/2019	856.55	857.05	0.50	-	8 - 10 ft	8.5-10.5 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-8-10	SSHS-B3181-SUB-8-10	8/29/2019	857.57	857.81	0.24	-	8 - 10 ft	8.24-10.24 ft	180-95006-3	Not Excavated							
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-8-10	SSHS-B3182-SUB-8-10	8/29/2019	857.45	857.88	0.43	-	8 - 10 ft	8.43-10.43 ft	180-95024-1	Not Excavated							
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-8-10	SSHS-B3223-SUB-8-10	8/29/2019	858.27	858.28	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95006-2	Not Excavated							
Northern Athletic Field	SSHS-B3003	083119 10:15_SSHS-B3003-SUB-8-10	SSHS-B3003-SUB-8-10	8/30/2019	851.95	852.83	0.88	-	8 - 10 ft	8.88-10.88 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3011	083119 10:15_SSHS-B3011-SUB-8-10	SSHS-B3011-SUB-8-10	8/30/2019	853.85	854.62	0.77	-	8 - 10 ft	8.77-10.77 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-8-10	SSHS-B3025-SUB-8-10	8/30/2019	854.59	855.82	1.23	-	8 - 10 ft	9.23-11.23 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3039	083119 10:15_SSHS-B3039-SUB-8-10	SSHS-B3039-SUB-8-10	8/30/2019	855.85	856.37	0.52	-	8 - 10 ft	8.52-10.52 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3068	083119 10:15_SSHS-B3068-SUB-8-10	SSHS-B3068-SUB-8-10	8/30/2019	856.38	856.82	0.44	-	8 - 10 ft	8.44-10.44 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-8-10	SSHS-B3082-SUB-8-10	8/30/2019	856.73	857.22	0.49	-	8 - 10 ft	8.49-10.49 ft	180-95047-3	Not Excavated							
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-8-10	SSHS-B3087-SUB-8-10	8/30/2019	857.68	857.65	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-95047-2	Not Excavated							
Northern Athletic Field	SSHS-B3214	083119 10:15_SSHS-B3214-SUB-8-10	SSHS-B3214-SUB-8-10	8/30/2019	855.06	855.25	0.19	-	8 - 10 ft	8.19-10.19 ft	180-95050-2	Not Excavated							
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-8-10	SSHS-B3222-SUB-8-10	8/30/2019	858.28	858.08	-0.20	-	8 - 10 ft	7.8-9.8 ft	180-95047-1	Not Excavated							
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-8-10	SSHS-B3224-SUB-8-10	8/30/2019	858.38	858.48	0.10	-	8 - 10 ft	8.1-10.1 ft	180-95050-1	Not Excavated							
Northern Athletic Field	SSHS-B3001	090419 03:44_SSHS-B3001-SUB-8-10	SSHS-B3001-SUB-8-10	9/3/2019	853.35	853.44	0.09	-	8 - 10 ft	8.09-10.09 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3002	090419 03:44_SSHS-B3002-SUB-8-10	SSHS-B3002-SUB-8-10	9/3/2019	853.09	853.12	0.03	-	8 - 10 ft	8.03-10.03 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3009	090419 03:44_SSHS-B3009-SUB-8-10	SSHS-B3009-SUB-8-10	9/3/2019	853.88	854.29	0.41	-	8 - 10 ft	8.41-10.41 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3010	090419 03:44_SSHS-B3010-SUB-8-10	SSHS-B3010-SUB-8-10	9/3/2019	854.13	854.48	0.35	-	8 - 10 ft	8.35-10.35 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3023	090419 03:44_SSHS-B3023-SUB-8-10	SSHS-B3023-SUB-8-10	9/3/2019	854.48	854.90	0.42	-	8 - 10 ft	8.42-10.42 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3024	090419 03:44_SSHS-B3024-SUB-8-10	SSHS-B3024-SUB-8-10	9/3/2019	855.00	855.16	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95155-1	Not Excavated							
Northern Athletic Field	SSHS-B3036	090419 03:44_SSHS-B3036-SUB-8-10	SSHS-B3036-SUB-8-10	9/3/2019	855.09	855.21	0.12	-	8 - 10 ft	8.12-10.12 ft	180-95155-2	Not Excavated							
Northern Athletic Field	SSHS-B3038	090419 03:44_SSHS-B3038-SUB-8-10	SSHS-B3038-SUB-8-10	9/3/2019	855.76	855.72	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3052	090419 03:44_SSHS-B3052-SUB-8-10	SSHS-B3052-SUB-8-10	9/3/2019	855.98	855.94	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3053	090419 03:44_SSHS-B3053-SUB-8-10	SSHS-B3053-SUB-8-10	9/3/2019	856.41	856.22	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-95155-3	Not Excavated							
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-8-10	SSHS-B3067-SUB-8-10	9/3/2019	856.40	856.48	0.08	-	8 - 10 ft	8.08-10.08 ft	180-95162-1	Not Excavated							
Northern Athletic Field	SSHS-B3051	090519 09:00_SSHS-B3051-SUB-8-10	SSHS-B3051-SUB-8-10	9/4/2019	855.15	855.32	0.17	-	8 - 10 ft	8.17-10.17 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3066	090519 09:00_SSHS-B3066-SUB-8-10	SSHS-B3066-SUB-8-10	9/4/2019	855.86	856.02	0.16	-	8 - 10 ft	8.16-10.16 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-8-10	SSHS-B3080-SUB-8-10	9/4/2019	856.58	856.76	0.18	-	8 - 10 ft	8.18-10.18 ft	180-95165-1	Not Excavated							
Northern Athletic Field	SSHS-B3081	090519 09:00_SSHS-B3081-SUB-8-10	SSHS-B3081-SUB-8-10	9/4/2019	856.96	857.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3085	090519 09:00_SSHS-B3085-SUB-8-10	SSHS-B3085-SUB-8-10	9/4/2019	857.12	857.26	0.14	-	8 - 10 ft	8.14-10.14 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3086	090519 09:00_SSHS-B3086-SUB-8-10	SSHS-B3086-SUB-8-10	9/4/2019	857.77	857.49	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-95165-2	Not Excavated							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-8-10	SSHS-B3220-SUB-8-10	9/4/2019	857.44	857.92	0.48	-	8 - 10 ft	8.48-10.48 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-8-10	SSHS-B3221-SUB-8-10	9/4/2019	857.92	857.93	0.01	-	8 - 10 ft	8.01-10.01 ft	180-95165-3	Not Excavated							
Northern Athletic Field	SSHS-B3244	122119 10:30_SSHS-B3244-SUB-8-10	SSHS-B3244-SUB-8-10	12/19/2019	857.74	857.53	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3245	122119 10:30_SSHS-B3245-SUB-8-10	SSHS-B3245-SUB-8-10	12/19/2019	857.37	857.51	0.14	-	8 - 10 ft	8.14-10.14 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3246	122119 10:30_SSHS-B3246-SUB-8-10	SSHS-B3246-SUB-8-10	12/19/2019	858.13	857.94	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100363-3	Not Excavated							
Northern Athletic Field	SSHS-B3233	122119 10:30_SSHS-B3233-SUB-8-10	SSHS-B3233-SUB-8-10	12/20/2019	855.71	855.74	0.03	-	8 - 10 ft	8.03-10.03 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3235	122119 10:30_SSHS-B3235-SUB-8-10	SSHS-B3235-SUB-8-10	12/20/2019	856.44	856.25	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-100362-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3236	122119 10:30_SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3522A	011521 08:45_SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated							
Northern Athletic Field	SSHS-B3523A	011521 08:45_SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated							
Northern Athletic Field	SSHS-B3521	012721 08:30_SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3636	012721 08:30_SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 1.9 U	< 0.7 U	< 1.5 U	< 1.2 U	< 1.3 U	< 1.1 U	< 2 U	< 1 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 1.9 U	< 0.7 U	< 1.5 U	< 1.2 U	< 1.3 U	< 1.1 U	< 2 U	< 1 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3930A	061821 09:00_SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.0065 U	< 0.00054 U	< 0.00065 U	< 0.00043 U	< 0.0054 U	< 0.00075 U	< 0.00065 U	< 0.00054 U
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	0.028	< 0.00052 U	< 0.00062 U	< 0.00041 U	< 0.0052 U	< 0.00072 U	< 0.00062 U	< 0.00052 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.0063 U	< 0.00053 U	< 0.00063 U	< 0.00042 U	< 0.0053 U	< 0.00074 U	< 0.00063 U	< 0.00053 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.0062 U	< 0.00052 U	< 0.00062 U	< 0.00041 U	< 0.0052 U	< 0.00072 U	< 0.00062 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.0058 U	< 0.00048 U	< 0.00058 U	< 0.00039 U	< 0.0048 U	< 0.00068 U	< 0.00058 U	< 0.00048 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.00025 U	< 0.00036 U	< 0.00067 U	< 0.0025 U	< 0.00045 U	< 0.0025 U	< 0.00049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	0.0058 J	< 0.00024 U	< 0.00035 U	< 0.00065 U	< 0.0024 U	< 0.00044 U	< 0.0024 U	< 0.00047 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.019 U	< 0.00063 U	< 0.0011 U	< 0.0014 U	< 0.0022 U	< 0.0038 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.018 U	< 0.00058 U	< 0.001 U	< 0.0013 U	< 0.002 U	< 0.0035 U	< 0.00097 U	< 0.0027 U
Northern Athletic Field	B202	110421 09:45_SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated								
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated								
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated								
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated								
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated								
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.021 UT	< 0.00069 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0041 U	< 0.0011 U	< 0.0032 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.023 UT	< 0.00077 U	< 0.0014 U	< 0.0017 U	< 0.0027 U	< 0.0046 U	< 0.0013 U	< 0.0036 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.026 UT	< 0.00086 U	< 0.0015 U	< 0.0019 U	< 0.0030 U	< 0.0051 U	< 0.0014 U	< 0.0040 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.018 UT	< 0.00059 U	< 0.0010 U	< 0.0013 U	< 0.0020 U	< 0.0035 U	< 0.00098 U	< 0.0027 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.017 U	< 0.00057 U	< 0.0010 U	< 0.0012 U	< 0.0020 U	< 0.0034 U	< 0.00095 U	< 0.0026 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated								
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 UT	< 0.0024 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3236	122119 10:30 SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3522A	011521 08:45 SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B3523A	011521 08:45 SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3636	012721 08:30 SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.65 U	< 1.2 U	< 1.5 U	< 0.8 U	< 0.99 U	< 1.2 U	< 1.6 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.65 U	< 1.2 U	< 1.5 U	< 0.8 U	< 0.99 U	< 1.2 U	< 1.6 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	SSHS-B3930A	061821 09:00 SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.00054 U	< 0.00054 U	< 0.0011 U	< 0.00065 U	< 0.00065 U	< 0.00054 U	< 0.00054 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00062 U	< 0.00062 U	0.0008 J	< 0.00052 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.00053 U	< 0.00053 U	< 0.0011 U	< 0.00063 U	< 0.00063 U	< 0.00053 U	< 0.00053 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.001 U	< 0.00062 U	< 0.00062 U	< 0.00052 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.00048 U	< 0.00048 U	< 0.00097 U	< 0.00058 U	< 0.00058 U	< 0.00048 U	< 0.00048 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.00066 U	< 0.00064 U	< 0.0011 U	< 0.00031 U	< 0.0003 U	< 0.0007 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.00093 U	< 0.00091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00099 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.00065 U	< 0.00063 U	< 0.0011 U	< 0.0003 U	< 0.0003 U	< 0.00068 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.00083 U	< 0.0025 U	< 0.0025 U	< 0.00071 U	< 0.0021 U	< 0.0012 U	< 0.0033 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated							
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.00077 U	< 0.0023 U	< 0.0023 U	< 0.00066 U	< 0.0019 U	< 0.0012 U	< 0.003 U
Northern Athletic Field	B202	110421 09:45 SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated							
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated							
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated							
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated							
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated							
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated							
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated							
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated							
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated							
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated							
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated							
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated							
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated							
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated							
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.00090 U	< 0.0027 U	< 0.0027 U	< 0.00078 U	< 0.0023 U	< 0.0014 U	< 0.0036 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.0010 U	< 0.0031 U	< 0.0030 U	< 0.00087 U	< 0.0025 U	< 0.0015 U	< 0.0040 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0034 U	< 0.0034 U	< 0.00097 U	< 0.0028 U	< 0.0017 U	< 0.0045 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.00077 U	< 0.0023 U	< 0.0023 U	< 0.00066 U	< 0.0019 U	< 0.0012 U	< 0.0030 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.00074 U	< 0.0023 U	< 0.0022 U	< 0.00064 U	< 0.0019 U	< 0.0011 U	< 0.0029 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated							
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	0.0020 J	< 0.0024 U	< 0.0028 U	< 0.0038 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0039 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U

DRAFT

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3236	122119 10:30 SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3522A	011521 08:45 SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B3523A	011521 08:45 SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3636	012721 08:30 SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 2.3 U	< 0.68 U	< 1.2 U	< 0.84 U	< 1.5 U	< 0.75 U	< 0.8 U	< 0.72 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 2.3 U	< 0.68 U	< 1.2 U	< 0.84 U	< 1.5 U	< 0.75 U	< 0.8 U	< 0.72 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	0.0058	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	SSHS-B3930A	061821 09:00 SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.0022 U	< 0.00043 U	< 0.00065 U	< 0.00054 U	< 0.00054 U	< 0.00043 U	< 0.00054 U	< 0.00065 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00041 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00062 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00042 U	< 0.00063 U	< 0.00053 U	< 0.00053 U	< 0.00042 U	< 0.00053 U	< 0.00063 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.0021 U	< 0.00041 U	< 0.00062 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00062 U
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.0019 U	< 0.00039 U	< 0.00058 U	< 0.00048 U	< 0.00048 U	< 0.00039 U	< 0.00048 U	< 0.00058 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.0023 U	< 0.00065 U	< 0.00042 U	< 0.00039 U	< 0.00026 U	< 0.0007 U	< 0.00061 U	< 0.00025 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00091 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00099 U	< 0.034 U	< 0.00035 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.0022 U	< 0.00063 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00068 U	< 0.0006 U	< 0.00025 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.011 U	< 0.0007 U	< 0.00085 UJ	< 0.001 U	< 0.00074 U	< 0.0008 UJ	< 0.00063 U	< 0.0007 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.01 U	< 0.00064 U	< 0.00079 U	< 0.00093 U	< 0.00068 U	< 0.00074 U	< 0.00058 U	< 0.00065 U
Northern Athletic Field	B202	110421 09:45 SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated								
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated								
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated								
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated								
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated								
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.012 UT	< 0.00076 U	< 0.00093 U	< 0.0011 U	< 0.00081 U	< 0.00087 U	< 0.00068 U	< 0.00076 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.013 UT	< 0.00085 U	< 0.0010 U	< 0.0012 U	< 0.00090 U	< 0.00098 U	< 0.00077 U	< 0.00086 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.015 UT	< 0.00095 U	< 0.0012 U	< 0.0014 U	< 0.0010 U	< 0.0011 U	< 0.00086 U	< 0.00095 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.01 UT	< 0.00065 U	< 0.00079 U	< 0.00093 U	< 0.00069 U	< 0.00074 U	< 0.00058 U	< 0.00065 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.0098 U	< 0.00063 U	< 0.00077 U	< 0.00090 U	< 0.00066 U	< 0.00072 U	< 0.00056 U	< 0.00063 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated								
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0018 U	< 0.0017 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0053 U	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3236	122119 10:30_SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3522A	011521 08:45_SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B3523A	011521 08:45_SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B3521	012721 08:30_SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3636	012721 08:30_SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 1.1 U	< 2 U	< 0.75 U	< 0.87 U	< 0.66 U	< 1.1 U	< 1.1 U	1.8 J
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 1.1 U	< 2 U	< 0.75 U	< 0.87 U	< 0.66 U	< 1.1 U	< 1.1 U	1.9 J
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SSHS-B3930A	061821 09:00_SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.00054 U	< 0.0011 U	< 0.00054 U	< 0.00054 U	< 0.00054 U	< 0.00043 U	< 0.00054 U	< 0.00043 U
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00041 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.00053 U	< 0.0011 U	< 0.00053 U	< 0.00053 U	< 0.00053 U	< 0.00042 U	< 0.00053 U	< 0.00042 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.001 U	< 0.00052 U	< 0.00052 U	< 0.00052 U	< 0.00041 U	< 0.00052 U	< 0.00041 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.00048 U	< 0.00097 U	< 0.00048 U	< 0.00048 U	< 0.00048 U	< 0.00039 U	< 0.00048 U	< 0.00039 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.00062 U	< 0.0026 U	< 0.00064 U	< 0.00052 U	< 0.0025 U	< 0.00072 U	< 0.0022 U	< 0.00035 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00091 U	< 0.00073 U	< 0.034 U	< 0.001 U	< 0.0031 U	< 0.00049 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.0006 U	< 0.0026 U	< 0.00063 U	< 0.0005 U	< 0.0024 U	< 0.0007 U	< 0.0022 U	< 0.00034 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00077 U	< 0.0026 U	< 0.0034 U	< 0.00095 UJ
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.0015 U	< 0.00094 U	< 0.0012 U	< 0.0012 U	< 0.00071 U	< 0.0024 U	< 0.0031 U	< 0.00088 U
Northern Athletic Field	B202	110421 09:45_SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated								
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated								
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated								
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated								
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated								
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00084 U	< 0.0028 U	< 0.0037 U	< 0.0010 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0016 U	< 0.0016 U	< 0.00094 U	< 0.0032 U	< 0.0041 U	< 0.0012 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.0023 U	< 0.0014 U	< 0.0018 U	< 0.0018 U	< 0.0011 U	< 0.0036 U	< 0.0046 U	< 0.0013 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.0015 U	< 0.00095 U	< 0.0012 U	< 0.0012 U	< 0.00072 U	< 0.0024 U	< 0.0031 U	< 0.00088 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.0015 U	< 0.00091 U	< 0.0012 U	< 0.0012 U	< 0.00069 U	< 0.0023 U	< 0.0030 U	< 0.00085 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated								
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0024 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0027 U	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0026 U	< 0.0048 U	< 0.0018 U	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3236	122119 10:30_SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated								
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated								
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated								
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated								
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated								
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated								
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated								
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated								
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated								
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated								
Northern Athletic Field	SSHS-B3522A	011521 08:45_SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B3523A	011521 08:45_SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated								
Northern Athletic Field	SSHS-B3521	012721 08:30_SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated								
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3636	012721 08:30_SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated								
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated								
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 1 U	< 0.78 U	< 1.3 UT	< 3.7 U	< 1.2 U	< 1.3 U	< 0.91 U	< 0.73 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 1 U	< 0.78 U	< 1.3 UT	< 3.7 U	< 1.2 U	< 1.3 U	< 0.91 U	< 0.73 U
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated								
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-B3930A	061821 09:00_SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.00065 U	< 0.0011 U	< 0.00043 U	< 0.0011 U,*+	< 0.00065 U	< 0.0022 U	< 0.0011 U	< 0.00054 U
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.001 U	0.0012 J	< 0.0021 U	< 0.001 U	< 0.00052 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.00063 U	< 0.0011 U	< 0.00042 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0011 U	< 0.00053 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.001 U	< 0.00062 U	< 0.0021 U	< 0.001 U	< 0.00052 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.00058 U	< 0.00097 U	< 0.00039 U	< 0.00097 U	0.00066 J	< 0.0019 U	< 0.00097 U	< 0.00048 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.0011 U	< 0.0025 U	< 0.00076 U	< 0.003 U	< 0.00076 U	< 0.0018 U	< 0.0016 U	< 0.00049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.00069 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.0011 U	< 0.0024 U	< 0.00074 U	< 0.003 U	0.00086 J	< 0.0018 U	< 0.0016 U	< 0.00048 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.0012 U	< 0.0037 U	< 0.0017 UJ	< 0.0031 U	< 0.0011 U	< 0.0032 U	< 0.0034 U	< 0.0018 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated								
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0034 U	< 0.0016 U	< 0.0028 U	0.0011 J	< 0.003 U	< 0.0031 U	< 0.0017 U
Northern Athletic Field	B202	110421 09:45_SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated								
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated								
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated								
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated								
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated								
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated								
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated								
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated								
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated								
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated								
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated								
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.0013 U	< 0.0040 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0035 U	< 0.0037 U	< 0.0020 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.0014 U	< 0.0045 U	< 0.0021 U	0.0078 J	< 0.0014 U	< 0.0039 U	< 0.0041 U	< 0.0022 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.0016 U	< 0.0051 U	< 0.0024 U	< 0.0042 U	< 0.0015 U	< 0.0044 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.0011 U	< 0.0034 U	< 0.0016 U	< 0.0029 U	< 0.0010 U	< 0.0030 U	< 0.0031 U	< 0.0017 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.0010 U	< 0.0033 U	< 0.0016 U	< 0.0028 U	< 0.0010 U	< 0.0029 U	< 0.0030 U	< 0.0016 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated								
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated								
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0031 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3236	122119 10:30 SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3343	122119 10:30 SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3100	011420 09:00 SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3101	011420 09:00 SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3102	011420 09:00 SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated						
Northern Athletic Field	SSHS-B3104	011420 09:00 SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated						
Northern Athletic Field	SSHS-B3105	011520 09:00 SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3106	011520 09:00 SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3108	011520 09:00 SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated						
Northern Athletic Field	SSHS-B3113	011520 09:00 SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3183	011520 09:00 SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated						
Northern Athletic Field	SSHS-B3184	011520 09:00 SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated						
Northern Athletic Field	SSHS-B3107	011620 08:30 SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3109	011620 08:30 SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3110	011620 08:30 SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3111	011620 08:30 SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3112	011620 08:30 SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated						
Northern Athletic Field	SSHS-B3116	011620 08:30 SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated						
Northern Athletic Field	SSHS-B3118	011620 08:30 SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated						
Northern Athletic Field	SSHS-B3522A	011521 08:45 SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B3523A	011521 08:45 SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B3521	012721 08:30 SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3634	012721 08:30 SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3635	012721 08:30 SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3636	012721 08:30 SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3637	012721 08:30 SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3638	012721 08:30 SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.75 U	< 0.76 U	< 1 U	< 0.72 UT	< 1.4 U	< 1.3 UT	< 0.83 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.75 U	< 0.76 U	< 1 U	< 0.72 UT	< 1.4 U	< 1.3 UT	< 0.83 U
Northern Athletic Field	SSHS-B3918	051321 10:15 SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated						
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-B3930A	061821 09:00 SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.00043 U	< 0.00043 U	< 0.00054 U	< 0.00065 U	< 0.0054 U	< 0.0054 U	< 0.00065 U
Northern Athletic Field	SSHS-B3931	061821 09:00 SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	< 0.00041 U	< 0.00041 U	0.00082 J	0.00084 J	< 0.0052 U	< 0.0052 U	< 0.00062 U
Northern Athletic Field	SSHS-B3932	061821 09:00 SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.00042 U	< 0.00042 U	< 0.00053 U	< 0.00063 U	< 0.0053 U	< 0.0053 U	< 0.00063 U
Northern Athletic Field	SSHS-B3933	061821 09:00 SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.00041 U	< 0.00041 U	< 0.00052 U	< 0.00062 U	< 0.0052 U	< 0.0052 U	< 0.00062 U
Northern Athletic Field	SSHS-B3934	061821 09:00 SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.00039 U	< 0.00039 U	< 0.00048 U	< 0.00058 U	< 0.0048 U	< 0.0048 U	< 0.00058 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.00025 U	< 0.00082 U	< 0.00067 U	< 0.00038 U	< 0.00053 U	< 0.00031 U	< 0.00036 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.00035 U	< 0.034 U	< 0.00095 U	< 0.00053 U	< 0.034 U	< 0.00043 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.00024 U	< 0.00079 U	< 0.00066 U	0.00095 J	< 0.00052 U	< 0.0003 U	< 0.00035 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.0013 U	< 0.00066 U	< 0.0007 U	< 0.0027 U	< 0.0023 U	< 0.0016 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated						
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated						
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.00097 U	< 0.0012 U	< 0.00061 U	0.00075 J	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	B202	110421 09:45 SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated						
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated						
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated						
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated						
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated						
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated						
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated						
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated						
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated						
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated						
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated						
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated						
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated						
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.00072 U	< 0.00076 U	< 0.0029 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.0013 U	< 0.0016 U	< 0.00081 U	< 0.00086 U	< 0.0033 U	< 0.0028 U	< 0.0020 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.00090 U	< 0.00096 U	< 0.0036 U	< 0.0031 U	< 0.0022 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.00097 U	< 0.0012 U	< 0.00061 U	< 0.00065 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.00094 U	< 0.0012 U	< 0.00059 U	< 0.00063 U	< 0.0024 U	< 0.0020 U	< 0.0014 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated						
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated						
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated						
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated						
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated						
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 UT	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 UT	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 UT	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 UT	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 UT	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 UT	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3236	122119 10:30_SSHS-B3236-SUB-8-10	SSHS-B3236-SUB-8-10	12/20/2019	856.32	856.30	-0.02	-	8 - 10 ft	8.98-9.98 ft	180-100362-1	Not Excavated							
Northern Athletic Field	SSHS-B3343	122119 10:30_SSHS-B3343-SUB-8-10	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated							
Northern Athletic Field	SSHS-B3100	011420 09:00_SSHS-B3100-SUB-8-10	SSHS-B3100-SUB-8-10	1/13/2020	856.74	856.68	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3101	011420 09:00_SSHS-B3101-SUB-8-10	SSHS-B3101-SUB-8-10	1/13/2020	856.75	856.69	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3102	011420 09:00_SSHS-B3102-SUB-8-10	SSHS-B3102-SUB-8-10	1/13/2020	856.74	856.23	-0.51	-	8 - 10 ft	7.49-9.49 ft	180-100985-1	Not Excavated							
Northern Athletic Field	SSHS-B3104	011420 09:00_SSHS-B3104-SUB-8-10	SSHS-B3104-SUB-8-10	1/13/2020	856.82	856.64	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-100985-2	Not Excavated							
Northern Athletic Field	SSHS-B3105	011520 09:00_SSHS-B3105-SUB-8-10	SSHS-B3105-SUB-8-10	1/14/2020	856.73	856.62	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3106	011520 09:00_SSHS-B3106-SUB-8-10	SSHS-B3106-SUB-8-10	1/14/2020	856.72	856.30	-0.42	-	8 - 10 ft	7.58-9.58 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3108	011520 09:00_SSHS-B3108-SUB-8-10	SSHS-B3108-SUB-8-10	1/14/2020	857.55	856.76	-0.79	-	8 - 10 ft	7.21-9.21 ft	180-101038-3	Not Excavated							
Northern Athletic Field	SSHS-B3113	011520 09:00_SSHS-B3113-SUB-8-10	SSHS-B3113-SUB-8-10	1/14/2020	856.36	856.08	-0.28	-	8 - 10 ft	7.72-9.72 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3183	011520 09:00_SSHS-B3183-SUB-8-10	SSHS-B3183-SUB-8-10	1/14/2020	856.70	855.84	-0.86	-	8 - 10 ft	7.14-9.14 ft	180-101038-1	Not Excavated							
Northern Athletic Field	SSHS-B3184	011520 09:00_SSHS-B3184-SUB-8-10	SSHS-B3184-SUB-8-10	1/14/2020	856.85	855.95	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-101038-2	Not Excavated							
Northern Athletic Field	SSHS-B3107	011620 08:30_SSHS-B3107-SUB-8-10	SSHS-B3107-SUB-8-10	1/15/2020	857.05	857.26	0.21	-	8 - 10 ft	8.21-10.21 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3109	011620 08:30_SSHS-B3109-SUB-8-10	SSHS-B3109-SUB-8-10	1/15/2020	857.26	856.77	-0.49	-	8 - 10 ft	7.51-9.51 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3110	011620 08:30_SSHS-B3110-SUB-8-10	SSHS-B3110-SUB-8-10	1/15/2020	856.32	856.06	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3111	011620 08:30_SSHS-B3111-SUB-8-10	SSHS-B3111-SUB-8-10	1/15/2020	857.08	857.00	-0.08	-	8 - 10 ft	7.92-9.92 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3112	011620 08:30_SSHS-B3112-SUB-8-10	SSHS-B3112-SUB-8-10	1/15/2020	856.71	856.67	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-101084-2	Not Excavated							
Northern Athletic Field	SSHS-B3116	011620 08:30_SSHS-B3116-SUB-8-10	SSHS-B3116-SUB-8-10	1/15/2020	856.51	856.63	0.12	-	8 - 10 ft	8.12-10.12 ft	180-101084-1	Not Excavated							
Northern Athletic Field	SSHS-B3118	011620 08:30_SSHS-B3118-SUB-8-10	SSHS-B3118-SUB-8-10	1/15/2020	856.74	856.72	-0.02	-	8 - 10 ft	7.98-9.98 ft	180-101084-3	Not Excavated							
Northern Athletic Field	SSHS-B3522A	011521 08:45_SSHS-B3522-SUB-8-10	SSHS-B3522-SUB-8-10	1/14/2021	857.57	857.69	0.12	-	8 - 10 ft	8.12-10.12 ft	180-116002-1	Not Excavated							
Northern Athletic Field	SSHS-B3523A	011521 08:45_SSHS-B3523-SUB-8-10	SSHS-B3523-SUB-8-10	1/14/2021	858.01	858.02	0.01	-	8 - 10 ft	8.01-10.01 ft	180-116002-1	Not Excavated							
Northern Athletic Field	SSHS-B3521	012721 08:30_SSHS-B3521-SUB-8-10	SSHS-B3521-SUB-8-10	1/25/2021	855.79	855.68	-0.11	-	8 - 10 ft	7.89-9.89 ft	180-116404-3	Not Excavated							
Northern Athletic Field	SSHS-B3634	012721 08:30_SSHS-B3634-SUB-8-10	SSHS-B3634-SUB-8-10	1/26/2021	857.44	857.49	0.05	-	8 - 10 ft	8.05-10.05 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3635	012721 08:30_SSHS-B3635-SUB-8-10	SSHS-B3635-SUB-8-10	1/26/2021	857.87	857.72	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3636	012721 08:30_SSHS-B3636-SUB-8-10	SSHS-B3636-SUB-8-10	1/26/2021	857.79	857.79	0.00	-	8 - 10 ft	8-10 ft	180-116462-3	Not Excavated							
Northern Athletic Field	SSHS-B3637	012721 08:30_SSHS-B3637-SUB-8-10	SSHS-B3637-SUB-8-10	1/26/2021	857.63	857.60	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3638	012721 08:30_SSHS-B3638-SUB-8-10	SSHS-B3638-SUB-8-10	1/26/2021	857.95	857.95	0.00	-	8 - 10 ft	8-10 ft	180-116462-1	Not Excavated							
Northern Athletic Field	SSHS-B3930	DUP-41-20210511	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.49 U	< 0.78 U	< 2.1 U	< 1.8 U	10	4	14
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10-20210511	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.49 U	< 0.78 U	< 2.1 U	< 1.8 U	11	4.1	15
Northern Athletic Field	SSHS-B3918	051321 10:15_SSHS-B3918-SUB-8-10	SSHS-B3918-SUB-8-10	5/12/2021	854.82	854.84	0.02	-	8 - 10 ft	8.02-10.02 ft	180-121548-2	Not Excavated							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10-20210517	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10-20210518	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3930A	061821 09:00_SSHS-B3930A-SUB-8-10	SSHS-B3930A-SUB-8-10	6/17/2021	856.76	855.86	-0.90	-	8 - 10 ft	7.1-9.1 ft	180-123399-1	Not Excavated	< 0.00054 U	< 0.00054 U	< 0.00075 U	< 0.00065 U	0.0014 J	0.00056 J	0.002 J
Northern Athletic Field	SSHS-B3931	061821 09:00_SSHS-B3931-SUB-8-10	SSHS-B3931-SUB-8-10	6/17/2021	856.63	855.62	-1.01	-	8 - 10 ft	6.99-8.99 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.00072 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.0014 U
Northern Athletic Field	SSHS-B3932	061821 09:00_SSHS-B3932-SUB-8-10	SSHS-B3932-SUB-8-10	6/17/2021	857.09	855.85	-1.24	-	8 - 10 ft	6.76-8.76 ft	180-123399-1	Not Excavated	< 0.00053 U	< 0.00053 U	< 0.00074 U	< 0.00063 U	< 0.0011 U	< 0.00042 U	< 0.0015 U
Northern Athletic Field	SSHS-B3933	061821 09:00_SSHS-B3933-SUB-8-10	SSHS-B3933-SUB-8-10	6/17/2021	856.55	855.68	-0.87	-	8 - 10 ft	7.13-9.13 ft	180-123399-1	Not Excavated	< 0.00052 U	< 0.00052 U	< 0.00072 U	< 0.00062 U	< 0.001 U	< 0.00041 U	< 0.0014 U
Northern Athletic Field	SSHS-B3934	061821 09:00_SSHS-B3934-SUB-8-10	SSHS-B3934-SUB-8-10	6/17/2021	856.72	855.95	-0.77	-	8 - 10 ft	7.23-9.23 ft	180-123399-1	Not Excavated	< 0.00048 U	< 0.00048 U	< 0.00068 U	< 0.00058 U	< 0.00097 U	< 0.00039 U	< 0.0014 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-8-10	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated	< 0.00065 U	< 0.0011 U	< 0.00048 U	< 0.00061 U	< 0.00084 U	< 0.00066 U	< 0.00084 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-8-10	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0012 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-8-10	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated	< 0.00064 U	< 0.0011 U	< 0.00046 U	< 0.0006 U	0.00097 J	< 0.00064 U	0.00097 J
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-8-10	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.00057 U	< 0.0024 U	< 0.0016 U	< 0.00071 UJ	< 0.00078 U	< 0.0014 U
Northern Athletic Field	B235	SSHS-IRM5A2-DUP3-20211028	SSHS-IRM5A2-DUP3	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated							
Northern Athletic Field	B235	SSHS-IRM5A2-B235-20211028	SSHS-IRM5A2-B235	10/28/2021	-	856.26	-	848.05	8 - 10 ft	8.21 ft	1801292042	Not Excavated							
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-8-10	SSHS-B4264-SUB-8-10	11/1/2021	852.29	853.31	1.02	-	8 - 10 ft	9.02-11.02 ft	180-129325-1	Not Excavated	< 0.00095 U	0.00091 J	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00072 U	< 0.0013 U
Northern Athletic Field	B202	110421 09:45_SSHS-IRM5A2-B202	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	180-129463-2	Not Excavated							
Northern Athletic Field	S568	SSHS-IRM5A2-S568-20211103	SSHS-IRM5A2-S568	11/3/2021	-	857.63	-	847.93	8 - 10 ft	9.7 ft	1801294632	Not Excavated							
Northern Athletic Field	S569	SSHS-IRM5A2-S569-20211103	SSHS-IRM5A2-S569	11/3/2021	-	857.72	-	848.19	8 - 10 ft	9.54 ft	1801294633	Not Excavated							
Northern Athletic Field	S570	SSHS-IRM5A2-S570-20211103	SSHS-IRM5A2-S570	11/3/2021	-	857.91	-	848.46	8 - 10 ft	9.44 ft	1801294633	Not Excavated							
Northern Athletic Field	S593	SSHS-IRM5A2-S593-20211103	SSHS-IRM5A2-S593	11/3/2021	-	857.88	-	848.61	8 - 10 ft	9.28 ft	1801294633	Not Excavated							
Northern Athletic Field	S593A	SSHS-IRM5A2-S593A-20211103	SSHS-IRM5A2-S593A	11/3/2021	-	857.77	-	848.32	8 - 10 ft	9.44 ft	1801294633	Not Excavated							
Northern Athletic Field	S566	SSHS-IRM5A2-S566-20211103	SSHS-IRM5A2-S566	11/3/2021	-	857.66	-	848.35	8 - 10 ft	9.31 ft	1801294632	Not Excavated							
Northern Athletic Field	S567	SSHS-IRM5A2-S567-20211103	SSHS-IRM5A2-S567	11/3/2021	-	857.54	-	847.97	8 - 10 ft	9.57 ft	1801294632	Not Excavated							
Northern Athletic Field	B202	SSHS-IRM5A2-B202-20211103	SSHS-IRM5A2-B202	11/3/2021	-	857.54	-	849.34	8 - 10 ft	8.2 ft	1801294632	Not Excavated							
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A-20211106	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated							
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5-20211106	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated							
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3-20211106	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated							
Northern Athletic Field	B236-S4	SSHS-IRM5A2-B236-S4-20211106	SSHS-IRM5A2-B236-S4	11/6/2021	-	855.81	-	846.64	8 - 10 ft	9.17 ft	1801296741	Not Excavated							
Northern Athletic Field	B236-S2	SSHS-IRM5A2-B236-S2-20211106	SSHS-IRM5A2-B236-S2	11/6/2021	-	856.26	-	847.18	8 - 10 ft	9.07 ft	1801296741	Not Excavated							
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4-20211108	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 0.0011 U	< 0.00063 U	< 0.0027 U	< 0.0017 U	< 0.00077 U	< 0.00085 U	< 0.0016 U
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3-20211108	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 0.0013 U	< 0.00070 U	< 0.0030 U	< 0.0020 U	< 0.00087 U	< 0.00095 U	< 0.0018 U
Northern Athletic Field	DW1-BOT1B	SSHS-IRM5A2-DW1-BOT1B-20211108	SSHS-IRM5A2-DW1-BOT1B	11/8/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 0.0014 U	< 0.00078 U	< 0.0033 U	< 0.0022 U	< 0.00097 U	< 0.0011 U	< 0.0020 U
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3-20211110	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 0.00095 U	< 0.00053 U	< 0.0023 U	< 0.0015 U	< 0.00066 U	< 0.00072 U	< 0.0013 U
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4-20211110	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 0.00092 U	< 0.00051 U	< 0.0022 U	< 0.0014 U	< 0.00064 U	< 0.00070 U	< 0.0013 U
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1-20211113	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A-20211113	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1B	SSHS-IRM5A2-B236-S1B-20211113	SSHS-IRM5A2-B236-S1B	11/13/2021	-	855.93	-	847.31	8 - 10 ft	8.62 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1C	SSHS-IRM5A2-B236-S1C-20211113	SSHS-IRM5A2-B236-S1C	11/13/2021	-	856.09	-	847.13	8 - 10 ft	8.96 ft	1801299881	Not Excavated							
Northern Athletic Field	B236-S1-BOT2	SSHS-IRM5A2-B236-S1-BOT2-20211113	SSHS-IRM5A2-B236-S1-BOT2	11/13/2021	-	855.93	-	845.84	8 - 10 ft	10.09 ft	1801299881	Not Excavated							
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25-20220113	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	S131	SSHS-IRM5A2-S131-20220113	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	S132	SSHS-IRM5A2-S132-20220113	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-A2-B118	SSHS-IRM5A2-B118-20220113	SSHS-IRM5A2-B118	1/13/2022	-	858.66	-	848.88	8 - 10 ft	9.78 ft	1801323151	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	S170	SSHS-IRM5A2-S170-20220113	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	S171	SSHS-IRM5A2-S171-20220113	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 0.0012 U	< 0.0018 U	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	0.0041 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 UT	< 0.0044 U	< 0.0022 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UT	< 0.0042 U	< 0.0021 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00079 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 U	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated								
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated								
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated								
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated								
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	0.0074	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	0.0095	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.0055 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	0.011	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.0070 U	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00052 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	0.0064	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	0.00029 J	< 0.00039 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.02 U	< 0.00068 U	< 0.0012 U	< 0.0015 U	< 0.0023 U	< 0.0040 U	< 0.0011 U	< 0.0032 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.018 U	< 0.00060 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0036 U	< 0.0010 U	< 0.0028 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.023 U	< 0.00076 U	< 0.0013 U	< 0.0016 U	< 0.0026 U	< 0.0045 U	< 0.0013 U	< 0.0035 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.023 U	< 0.00075 U	< 0.0013 U	< 0.0016 U	< 0.0026 U	< 0.0045 U	< 0.0013 U	< 0.0035 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.0065 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0065 U	< 0.0024 U	< 0.0050 U	< 0.0039 U	< 0.0042 U	< 0.0038 U	< 0.0067 U	< 0.0034 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 UT	< 0.00034 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00088 U	< 0.00024 UT	< 0.00034 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 UT	< 0.00041 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 UT	< 0.00038 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0034 U	< 0.0036 U	< 0.0033 U	< 0.0058 U	< 0.0029 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.0021 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00078 U	0.00028 J	< 0.00030 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 UT	< 0.00091 U	< 0.00024 U	< 0.00035 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 UT	< 0.0025 U	< 0.0033 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0018 J	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 UT	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 UT	0.0017 J	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00059 U	< 0.00026 U	< 0.00013 U	< 0.00028 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.000077 U	< 0.000085 U	< 0.00023 U	< 0.00042 U	< 0.00019 U	< 0.000097 U	< 0.00020 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated							
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated							
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated							
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated							
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated							
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00064 U	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.00089 U	< 0.0027 U	< 0.0027 U	< 0.00076 U	< 0.0022 U	< 0.0013 U	< 0.0035 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.00079 U	< 0.0024 U	< 0.0024 U	< 0.00068 U	< 0.0020 U	< 0.0012 U	< 0.0031 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.00099 U	< 0.0030 U	< 0.0030 U	< 0.00085 U	< 0.0025 U	< 0.0015 U	< 0.0039 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.00099 U	< 0.0030 U	< 0.0030 U	< 0.00085 U	< 0.0025 U	< 0.0015 U	< 0.0039 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 UT	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 UT	< 0.00021 U	< 0.00044 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0022 U	< 0.0042 U	< 0.0049 U	0.0031 J	< 0.0033 U	< 0.0040 U	< 0.0054 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0019 U	< 0.0036 U	< 0.0042 U	< 0.0023 U	< 0.0029 U	< 0.0035 U	< 0.0047 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	0.0032 J,B	< 0.002 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00038 U	< 0.00019 U	< 0.00041 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00076 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00046 UT	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.00016 UT	< 0.00018 UT	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0028 UT	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.00090 U	< 0.00014 U	< 0.00027 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00050 U	< 0.000079 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.000098 U	< 0.000090 U	< 0.00013 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated								
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated								
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated								
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated								
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.0014 U	< 0.00022 U	< 0.00041 U	< 0.00044 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.012 U	< 0.00075 U	< 0.00091 U	< 0.0011 U	< 0.00079 U	< 0.00086 U	< 0.00067 U	< 0.00075 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.01 U	< 0.00066 U	< 0.00081 U	< 0.00096 U	< 0.00070 U	< 0.00076 U	< 0.00060 U	< 0.00066 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.013 U	< 0.00083 U	< 0.0010 U	< 0.0012 U	< 0.00088 U	< 0.00096 U	< 0.00075 U	< 0.00084 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.013 U	< 0.00083 U	< 0.0010 U	< 0.0012 U	< 0.00088 U	< 0.00095 U	< 0.00075 U	< 0.00083 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 UT	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	0.0012 J	< 0.00017 U	< 0.00032 UT	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0076 U	< 0.0023 U	< 0.0042 U	< 0.0028 U	< 0.0052 U	< 0.0025 U	< 0.0027 U	< 0.0024 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0035 U	< 0.0037 U	< 0.0038 U	< 0.0023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0036 U	< 0.0038 U	< 0.0039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0065 U	< 0.0020 U	< 0.0036 U	< 0.0024 U	< 0.0044 U	< 0.0022 U	< 0.0023 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0051 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.00089 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.0010 U	< 0.00016 UT	< 0.00031 U	< 0.00033 UT	< 0.00033 UT	< 0.00020 UT	< 0.00019 U	< 0.00027 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0023 UT	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 UT	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 UT
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 UT	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.000098 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00018 U	< 0.00012 U	< 0.00012 U	< 0.000087 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated								
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated								
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated								
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated								
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.00027 U	< 0.00047 U	< 0.00044 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0018 U	< 0.0011 U	< 0.0014 U	< 0.0014 U	< 0.00083 U	< 0.0028 U	< 0.0036 U	< 0.0010 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.0016 U	< 0.00097 U	< 0.0013 U	< 0.0012 U	< 0.00073 U	< 0.0025 U	< 0.0032 U	< 0.00090 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0016 U	< 0.0015 U	< 0.00092 U	< 0.0031 U	< 0.0040 U	< 0.0011 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.0020 U	< 0.0012 U	< 0.0016 U	< 0.0015 U	< 0.00092 U	< 0.0031 U	< 0.0040 U	< 0.0011 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00041 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00023 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0038 U	< 0.0068 U	< 0.0025 U	< 0.0029 U	< 0.0022 U	< 0.0037 U	< 0.0038 U	< 0.0031 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 UT	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 UT	< 0.00037 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 UT	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE5-BOT9-20220520	SSHS-IRM5A2-PIPE5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 UT	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 UT	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0033 U	< 0.0059 U	< 0.0022 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0032 U	< 0.0027 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	0.00029 J
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	0.00030 J
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.00020 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 UT	< 0.00024 UT	< 0.00018 UT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0024 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0026 U	< 0.00031 U	< 0.00023 U	< 0.00096 U	< 0.00032 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0026 U	< 0.00030 U	< 0.00022 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00013 U	< 0.00075 U	< 0.00012 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00068 U	< 0.00022 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated								
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated								
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated								
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated								
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated								
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated								
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated								
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.00037 U	< 0.0021 U	< 0.00035 U	< 0.0052 U	< 0.00061 U	< 0.00045 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0012 U	< 0.0040 U	< 0.0019 U	< 0.0033 U	< 0.0012 U	< 0.0034 U	< 0.0036 U	< 0.0019 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.0011 U	< 0.0035 U	< 0.0016 U	< 0.0029 U	< 0.0011 U	< 0.0031 U	< 0.0032 U	< 0.0017 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0014 U	< 0.0044 U	< 0.0021 U	< 0.0037 U	< 0.0013 U	< 0.0039 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.0014 U	< 0.0044 U	< 0.0021 U	< 0.0037 U	< 0.0013 U	< 0.0038 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 UT	< 0.00059 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0049 U	< 0.00056 U	< 0.00042 U	< 0.0018 UT	< 0.00058 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00049 U	< 0.00036 U	< 0.0015 UT	< 0.00051 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0034 U	< 0.0026 U	< 0.0044 U	< 0.012 U	< 0.0040 U	< 0.0043 U	< 0.0031 U	< 0.0025 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0029 U	< 0.0023 U	< 0.0038 U	< 0.011 U	< 0.0035 U	< 0.0037 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 002 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.00024 U	< 0.0013 U	< 0.00022 U	< 0.0034 U	< 0.00039 U	< 0.00029 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 UT	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 UT	< 0.00047 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 UT	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 UT	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.0014 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00017 U	< 0.00013 U	0.00054 J	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00012 U	< 0.000094 U	0.00039 J	< 0.00010 U	< 0.000079 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated							
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated							
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated							
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated							
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated							
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.00034 U	< 0.00026 U	0.00045 J	< 0.00028 U	< 0.00022 U	< 0.00044 U	< 0.00028 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.0007 U	< 0.00075 U	< 0.0029 U	< 0.0024 U	< 0.0017 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.0010 U	< 0.0012 U	< 0.00063 U	< 0.00066 U	< 0.0025 U	< 0.0021 U	< 0.0015 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0013 U	< 0.0016 U	< 0.00079 U	< 0.00084 U	< 0.0032 U	< 0.0027 U	< 0.0019 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.0013 U	< 0.0015 U	0.0047 J	< 0.00084 U	< 0.0032 U	< 0.0027 U	< 0.0019 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00035 U	< 0.00026 U	< 0.00020 U	< 0.00041 U	< 0.00026 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0025 U	< 0.0025 U	< 0.0034 U	< 0.0024 U	< 0.0046 U	< 0.0043 U	< 0.0028 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	0.00064 J	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.00027 U	< 0.00021 U	0.00030 J	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0022 U	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0040 U	< 0.0037 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.002 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	0.00054 J	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	0.00029 J	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.00025 UT	< 0.00019 U	< 0.00028 UT	< 0.00021 UT	< 0.00016 U	< 0.00033 UT	< 0.00021 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	S178	SSHS-IRM5A2-S178-20220113	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S177	SSHS-IRM5A2-S177-20220113	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S176	SSHS-IRM5A2-S176-20220113	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	S130	SSHS-IRM5A2-S130-20220113	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28-20220119	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S248	SSHS-IRM5A2-S248-20220119	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	S252	SSHS-IRM5A2-S252-20220120	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40-20220207	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66-20220207	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2-20220208	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8-20220208	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3-20220208	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	S229	SSHS-IRM5A2-S229-20220221	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	B594	SSHS-IRM5A2-B594-20220302	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 UT	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	S253	SSHS-IRM5A2-S253-20220303	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	S225	SSHS-IRM5A2-S225-20220314	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	S224	SSHS-IRM5A2-S224-20220314	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	S581	SSHS-IRM5A2-S581-20220314	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4-20220314	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 0.00095 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5-20220315	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00040 U
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54-20220318	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.00011 U	0.00030 J	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00039 U
Northern Athletic Field	S288	SSHS-IRM5A2-S288-20220318	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00051 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289-20220318	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 0.000078 U	0.00021 J	< 0.00018 U	< 0.00024 U	< 0.000076 U	< 0.000085 U	< 0.00028 U
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220319	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated							
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220319	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated							
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220319	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated							
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220319	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated							
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220319	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated							
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220320	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220320	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated							
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220320	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated							
Northern Athletic Field	S577	SSHS-IRM5A2-S577-20220321	SSHS-IRM5A2-S577	3/21/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578-20220321	SSHS-IRM5A2-S578	3/21/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00064 U
Northern Athletic Field	S580	SSHS-IRM5A2-S580-20220321	SSHS-IRM5A2-S580	3/21/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354851	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217-20220321	SSHS-IRM5A2-S217	3/21/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354851	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00059 U
Northern Athletic Field	S218	SSHS-IRM5A2-S218-20220321	SSHS-IRM5A2-S218	3/21/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354851	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00064 U
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4-20220321	SSHS-IRM5A2-S174-BOT4	3/21/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354861	Not Excavated	< 0.00022 U	0.00073 J	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00024 U	< 0.00078 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5-20220321	SSHS-IRM5A2-S174-BOT5	3/21/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354861	Not Excavated	< 0.00018 U	0.0027	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00064 U
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9-20220321	SSHS-IRM5A2-S174-S9	3/21/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354861	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00068 U
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1-20220330	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2-20220330	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1-20220330	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66-20220425	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0011 U	0.0019 J	< 0.0026 U	< 0.0017 U	< 0.00076 U	< 0.00083 U	< 0.0015 U
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8-20220425	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 0.00097 U	0.0013 J	< 0.0023 U	< 0.0015 U	< 0.00067 U	< 0.00074 U	< 0.0014 U
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6-20220425	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 0.0012 U	< 0.00069 U	< 0.0029 U	< 0.0019 U	< 0.00085 U	< 0.00093 U	< 0.0017 U
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10-20220425	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 0.0012 U	0.0049 J	< 0.0029 U	< 0.0019 U	< 0.00085 U	< 0.00093 U	< 0.0017 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18-20220509	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00063 U
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3-20220509	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 UT	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8-20220509	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00076 U
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16-20220509	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 U	< 0.00020 U	< 0.00022 U	< 0.00073 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7-20220509	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6-20220509	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated	< 0.00018 U	0.00034 J	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00064 U
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1-20220510	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0070 U	< 0.0060 U	< 0.0030 U	< 0.0034 U	< 0.012 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99-20220520	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00066 U
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11-20220520	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00057 U
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22-20220520	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00057 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10-20220520	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00060 U
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9-20220520	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated	< 0.00019 U	0.00062 J	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00068 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20-20220520	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated	< 0.00017 U	0.0030	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00062 U
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW-20220601	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 0.0014 U	< 0.0023 U	< 0.0060 U	< 0.0052 U	< 0.0026 U	< 0.0029 U	< 0.01 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-8-10	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-13_14	060622 10:25_SSHS-DW-13_14-SUB-8-10	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-8-10	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-8-10	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-8-10	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105-20220609	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	0.00033 J	< 0.00020 U	0.00033 J
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800-20220609	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated	< 0.00016 U	0.0063	< 0.00037 U	< 0.00049 U	0.0010	0.00029 J	0.0013 J
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801-20220609	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	0.00046 J	< 0.00017 U	0.00046 J
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802-20220609	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated	< 0.00014 U	0.00032 J	< 0.00032 U	< 0.00043 U	0.00038 J	< 0.00015 U	0.00038 J
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803-20220609	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	0.00053 J	< 0.00020 U	0.00053 J
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804-20220609	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	0.0010	0.00026 J	0.0013 J
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805-20220609	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	0.00043 J	< 0.00016 U	0.00043 J
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806-20220609	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00035 U	< 0.00048 U	0.00046 J	< 0.00017 U	0.00046 J
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807-20220609	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated	< 0.00016 UT	< 0.00029 U	< 0.00037 U	< 0.00050 U	0.00050 JT	< 0.00018 UT	0.00050 JT

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	0.0013	< 0.00035 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	0.0093	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	0.00095 J	< 0.00042 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.0054 U	< 0.00025 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 U	< 0.00027 U	< 0.00063 U	< 0.00017 UT	< 0.00025 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 UT	< 0.00031 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 UT	< 0.00021 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.0044 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00077 U	< 0.00021 UT	< 0.00030 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 UT	< 0.00044 U	< 0.00012 UT	< 0.00017 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.0030 U	< 0.00013 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 UT	< 0.00020 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00032 UT	< 0.00046 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.0062 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 U	< 0.00048 U	< 0.00013 UT	< 0.00018 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-DUP112-20220613	SSHS-IRM5A2-DUP112	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395962	Not Excavated	0.0070	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220613	SSHS-IRM5A2-FISR-S5	6/13/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395961	Not Excavated	< 0.0079 U	< 0.00036 U	< 0.00039 U	< 0.00036 U	< 0.00059 U	< 0.0014 U	< 0.00037 U	< 0.00054 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220613	SSHS-IRM5A2-FISR-S7	6/13/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395961	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220613	SSHS-IRM5A2-FISR-BOT5	6/13/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395961	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220613	SSHS-IRM5A2-A4-S107	6/13/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395961	Not Excavated	< 0.0097 U	< 0.00044 U	< 0.00048 U	< 0.00044 U	< 0.00072 U	< 0.0017 U	< 0.00045 U	< 0.00066 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220613	SSHS-IRM5A2-A4-S108	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395961	Not Excavated	0.0082	< 0.00031 U	< 0.00034 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00047 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220613	SSHS-IRM5A2-A4-S109	6/13/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395961	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.0061 U	< 0.0022 U	< 0.0047 U	< 0.0037 U	< 0.0040 U	< 0.0036 U	< 0.0063 U	< 0.0032 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	0.0097	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.0089 U	< 0.00040 U	< 0.00044 U	< 0.00040 U	< 0.00066 U	< 0.0016 U	< 0.00042 U	< 0.00060 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.0039 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00029 U	< 0.00067 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	0.16	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	0.0017	< 0.00037 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	0.12	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	0.00042 J	< 0.00041 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00022 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.0048 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00083 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	0.01	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.0063 U	< 0.00029 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	0.0064	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	0.0079	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	0.02	< 0.00037 U	< 0.00041 U	< 0.00037 U	< 0.00062 U	< 0.0015 U	< 0.00039 U	< 0.00056 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	0.011	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00019 U	< 0.00046 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	0.0072	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	0.0069 J	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0056 U	< 0.0020 U	< 0.0043 U	< 0.0033 U	< 0.0036 U	< 0.0032 U	< 0.0057 U	< 0.0029 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	0.012 J	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 UT	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00033 U	< 0.00062 U	< 0.00028 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 UT	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 UT	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 UT	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 UT	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 UT	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 UT	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.000097 U	< 0.00011 U	< 0.00028 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.000078 UT	< 0.000085 UT	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000097 U	< 0.00020 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.000092 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00023 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 UT	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 UT	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 UT	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 UT	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 UT	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.000084 U	< 0.000092 U	< 0.00025 U	< 0.00046 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.000096 U	< 0.00010 U	< 0.00028 UT	< 0.00053 U	< 0.00024 U	0.00013 J	< 0.00025 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S108	SSHS-IRM5A2-DUP112-20220613	SSHS-IRM5A2-DUP112	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395962	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 UT	< 0.00098 U	< 0.00044 UT	< 0.00022 U	< 0.00047 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220613	SSHS-IRM5A2-FISR-S5	6/13/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00027 U	< 0.00072 UT	< 0.0013 U	< 0.00060 U	< 0.00031 U	< 0.00064 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220613	SSHS-IRM5A2-FISR-S7	6/13/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395961	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 UT	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220613	SSHS-IRM5A2-FISR-BOT5	6/13/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395961	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 UT	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0034 J	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220613	SSHS-IRM5A2-A4-S107	6/13/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395961	Not Excavated	< 0.00030 U	< 0.00033 U	< 0.00089 UT	< 0.0016 U	< 0.00074 U	< 0.00037 U	< 0.00078 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0036 J	< 0.0022 U	< 0.0027 U	< 0.0036 UT
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220613	SSHS-IRM5A2-A4-S108	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395961	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00063 UT	< 0.0012 U	< 0.00053 U	< 0.00027 U	< 0.00056 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220613	SSHS-IRM5A2-A4-S109	6/13/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395961	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 UT	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.0020 U	< 0.0039 U	< 0.0046 U	0.0053 J	< 0.0031 U	< 0.0038 U	< 0.0051 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0039 J	< 0.0023 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0037 J	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0023 J	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0023 J	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00028 U	< 0.00030 U	< 0.00081 U	< 0.0015 U	< 0.00068 U	< 0.00034 U	< 0.00072 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 UT	< 0.00065 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 UT	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00043 UT
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 UT	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 UT	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 UT	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 UT	< 0.00081 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00049 UT	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 UT	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 UT	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 UT	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 UT	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 UT	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.00026 U	< 0.00028 U	< 0.00076 U	< 0.0014 U	< 0.00063 U	< 0.00032 U	< 0.00067 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.000081 U	< 0.000089 U	< 0.00024 U	< 0.00044 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	0.0043 BJ	< 0.0023 U	< 0.0027 U	< 0.0037 UT
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	0.0042 BJ	< 0.0023 U	< 0.0028 U	< 0.0037 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0036 U	0.0051 BJ	< 0.0024 U	< 0.0029 U	< 0.0039 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0036 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.0042 U	0.0060 BJ	< 0.0028 U	< 0.0034 U	< 0.0046 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	0.0053 BJ	< 0.0024 U	< 0.0028 U	< 0.0038 UT
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0043 BJ	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0046 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00048 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00032 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00073 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.00063 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.00088 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.00050 U	< 0.000079 UT	< 0.00015 U	< 0.00016 UT	< 0.00016 UT	< 0.000099 UT	< 0.000090 U	< 0.00013 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.00059 U	< 0.000093 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00055 U	< 0.000086 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000098 U	< 0.00014 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.00062 U	< 0.000097 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated								
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.0018 U	< 0.00028 U	< 0.00053 U	< 0.00056 U	< 0.00057 U	< 0.00035 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.00077 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 UT	< 0.00034 UT	< 0.00021 UT	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00095 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00017 UT	< 0.00032 U	< 0.00034 UT	< 0.00034 UT	< 0.00021 UT	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00028 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.0017 U	< 0.00026 U	< 0.00049 U	< 0.00052 U	< 0.00053 U	< 0.00033 U	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.00052 U	< 0.000082 U	< 0.00015 U	< 0.00017 U	< 0.00017 U	< 0.00010 U	< 0.000094 U	< 0.00014 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.00092 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 UT	< 0.0035 UT	< 0.0017 UT	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0052 U	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0055 U	< 0.0017 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0018 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0064 U	< 0.0020 U	< 0.0035 U	< 0.0024 U	< 0.0044 U	< 0.0021 U	< 0.0023 U	< 0.0021 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.0054 U	< 0.0016 U	< 0.0030 U	< 0.0020 UT	< 0.0037 UT	< 0.0018 UT	< 0.0019 U	< 0.0017 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	0.00037 J
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	0.00031 J
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00023 U	< 0.00016 U	< 0.00027 U	< 0.00017 U	< 0.00017 U	< 0.00013 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00015 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.000099 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 UT	< 0.00012 UT	< 0.000087 UT
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000095 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-DUP112-20220613	SSHS-IRM5A2-DUP112	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395962	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220613	SSHS-IRM5A2-FISR-S5	6/13/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395961	Not Excavated	< 0.00031 U	< 0.00053 U	< 0.00050 U	< 0.00034 U	< 0.00059 U	< 0.00038 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220613	SSHS-IRM5A2-FISR-S7	6/13/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395961	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220613	SSHS-IRM5A2-FISR-BOT5	6/13/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395961	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220613	SSHS-IRM5A2-A4-S107	6/13/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395961	Not Excavated	< 0.00038 U	< 0.00065 U	< 0.00061 U	< 0.00042 U	< 0.00072 U	< 0.00046 U	< 0.00045 U	< 0.00034 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220613	SSHS-IRM5A2-A4-S108	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395961	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00030 U	< 0.00051 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220613	SSHS-IRM5A2-A4-S109	6/13/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395961	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.0035 U	< 0.0064 U	< 0.0024 U	< 0.0027 U	< 0.0021 U	< 0.0035 U	< 0.0035 U	< 0.0029 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0025 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00035 U	< 0.00060 U	< 0.00056 U	< 0.00038 U	< 0.00066 U	< 0.00043 U	< 0.00042 U	< 0.00031 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00028 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	0.00026 J
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 UT	< 0.00025 UT	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.00033 U	< 0.00055 U	< 0.00052 U	< 0.00036 U	< 0.00061 U	< 0.00040 U	< 0.00039 U	< 0.00029 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 UT	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 UT	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000091 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 UT	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 UT	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 UT	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0026 U	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0027 U	< 0.0050 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0032 U	< 0.0058 U	< 0.0022 U	< 0.0025 U	< 0.0019 U	< 0.0032 U	< 0.0032 U	< 0.0026 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.0027 U	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00032 U	< 0.00023 U	< 0.00099 U	< 0.00032 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.00016 U	< 0.00093 U	< 0.00016 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0033 U	< 0.00039 U	< 0.00028 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.00013 U	< 0.00075 UT	< 0.00013 UT	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00068 UT	< 0.00022 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.00016 U	< 0.00089 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00081 U	< 0.00014 U	< 0.0020 U	< 0.00024 U	< 0.00018 U	< 0.00074 U	< 0.00024 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.00016 U	< 0.00093 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00084 U	< 0.00028 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated								
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-DUP112-20220613	SSHS-IRM5A2-DUP112	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395962	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220613	SSHS-IRM5A2-FISR-S5	6/13/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395961	Not Excavated	< 0.00042 U	< 0.0024 U	< 0.00039 U	< 0.0060 U	< 0.00069 U	< 0.00051 U	< 0.0022 U	< 0.00071 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220613	SSHS-IRM5A2-FISR-S7	6/13/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395961	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220613	SSHS-IRM5A2-FISR-BOT5	6/13/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395961	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220613	SSHS-IRM5A2-A4-S107	6/13/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395961	Not Excavated	< 0.00051 U	< 0.0029 U	< 0.00048 U	< 0.0073 U	< 0.00085 U	< 0.00062 U	< 0.0026 U	< 0.00087 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220613	SSHS-IRM5A2-A4-S108	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395961	Not Excavated	< 0.00036 U	< 0.0021 U	< 0.00034 U	< 0.0052 U	< 0.00060 U	< 0.00044 U	< 0.0019 U	< 0.00062 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220613	SSHS-IRM5A2-A4-S109	6/13/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395961	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.0031 U	< 0.0025 U	< 0.0041 U	< 0.012 U	< 0.0038 U	< 0.0040 U	< 0.0029 U	< 0.0023 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0022 U	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00047 U	< 0.0027 U	< 0.00044 U	< 0.0067 U	< 0.00078 U	< 0.00057 U	< 0.0024 U	< 0.00080 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.00020 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	0.00070 J	0.0032 J	0.00041 J	< 0.0041 U	< 0.00047 U	0.047	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	0.00046 J	0.0026 J	< 0.00030 U	< 0.0045 U	< 0.00053 U	0.03	< 0.0016 U	< 0.00054 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	0.0025 J	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.00044 U	< 0.0025 U	< 0.00041 U	< 0.0062 U	< 0.00072 U	0.0051 J	< 0.0023 U	< 0.00074 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.00014 U	< 0.00078 U	< 0.00013 U	< 0.0020 U	< 0.00023 U	< 0.00017 U	< 0.00071 U	< 0.00023 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00041 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0032 U	< 0.0090 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0029 U	< 0.0022 U	< 0.0037 U	< 0.01 U	< 0.0034 U	< 0.0036 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.0024 U	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	0.0051 J	< 0.0022 U	< 0.0017 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	0.00030 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00018 U	< 0.00014 U	< 0.00019 U	< 0.00015 U	< 0.00011 U	< 0.00023 U	< 0.00015 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	0.00027 J	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	0.00024 J	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	0.00026 J	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.00021 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.00012 UT	< 0.000094 U	< 0.00013 UT	< 0.00010 UT	< 0.000079 U	< 0.00016 UT	< 0.00010 U
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	< 0.00012 U	< 0.000094 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00028 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	0.00034 J	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000086 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000098 U	< 0.00019 U	< 0.00013 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S108	SSHS-IRM5A2-DUP112-20220613	SSHS-IRM5A2-DUP112	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395962	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220613	SSHS-IRM5A2-FISR-S5	6/13/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395961	Not Excavated	< 0.00038 U	< 0.00030 U	< 0.00042 U	< 0.00032 U	< 0.00025 U	< 0.00050 U	< 0.00032 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220613	SSHS-IRM5A2-FISR-S7	6/13/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395961	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220613	SSHS-IRM5A2-FISR-BOT5	6/13/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395961	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220613	SSHS-IRM5A2-A4-S107	6/13/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395961	Not Excavated	< 0.00047 U	< 0.00036 U	< 0.00052 U	< 0.00040 U	< 0.00031 U	< 0.00061 U	< 0.00040 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UT	< 0.0029 UT	< 0.0019 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220613	SSHS-IRM5A2-A4-S108	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395961	Not Excavated	< 0.00034 U	< 0.00026 U	< 0.00037 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220613	SSHS-IRM5A2-A4-S109	6/13/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.0024 U	< 0.0024 U	< 0.0032 U	< 0.0023 U	< 0.0043 U	< 0.0040 U	< 0.0026 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00043 U	< 0.00033 U	< 0.00048 U	< 0.00037 U	< 0.00028 U	< 0.00056 U	< 0.00036 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00014 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.00026 U	< 0.00020 UT	< 0.00029 U	0.00026 J	< 0.00017 UT	< 0.00034 UT	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.00026 UT	< 0.00020 U	< 0.00029 UT	< 0.00022 U	< 0.00017 U	< 0.00034 UT	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	0.00069 J	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	0.00058 J	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00035 U	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.00040 U	< 0.00031 U	< 0.00044 U	< 0.00034 U	< 0.00026 U	< 0.00052 U	< 0.00034 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.00013 U	< 0.000098 U	< 0.00014 U	< 0.00011 U	< 0.000083 U	< 0.00016 U	< 0.00011 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UT	< 0.0029 UT	< 0.0019 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0018 U	< 0.0033 U	< 0.0031 U	< 0.0020 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0021 U	< 0.0022 U	< 0.0029 U	< 0.0021 U	< 0.0039 U	< 0.0036 U	< 0.0024 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.0018 U	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 UT	< 0.0030 UT	< 0.0020 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808-20220609	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	0.0010	0.00028 J	0.0013 J
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809-20220609	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	0.0010 J	0.00027 J	0.0013 J
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108-20220610	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109-20220610	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00026 U	< 0.00035 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802-20220610	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803-20220610	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813-20220610	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807-20220610	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808-20220610	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810-20220610	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811-20220610	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1-20220610	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1-20220610	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated	< 0.000097 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2-20220610	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00031 U	< 0.00042 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2-20220610	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated	< 0.000078 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000076 UT	< 0.000085 UT	< 0.000076 UT
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3-20220610	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated	< 0.000092 U	0.00018 J	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT-20220610	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21-20220610	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800-20220610	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT-20220610	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801-20220610	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804-20220610	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated	< 0.00019 U	0.00072 J	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5-20220610	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated	< 0.000085 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000083 U	< 0.000092 U	< 0.000083 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6-20220610	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated	< 0.000096 U	< 0.00017 U	< 0.00022 U	< 0.00030 U	< 0.000094 U	< 0.00010 U	< 0.000094 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220611	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220611	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated							
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220611	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220611	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220611	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220611	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated							
Northern Athletic Field	A4-S108	SSHS-IRM5A2-DUP112-20220613	SSHS-IRM5A2-DUP112	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395962	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00055 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5-20220613	SSHS-IRM5A2-FISR-S5	6/13/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395961	Not Excavated	< 0.00025 U	< 0.00044 U	< 0.00056 U	< 0.00076 U	< 0.00024 U	< 0.00027 U	< 0.00024 U
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7-20220613	SSHS-IRM5A2-FISR-S7	6/13/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395961	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5-20220613	SSHS-IRM5A2-FISR-BOT5	6/13/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395961	Not Excavated	< 0.00019 U	0.00075 J	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11-20220613	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107-20220613	SSHS-IRM5A2-A4-S107	6/13/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395961	Not Excavated	< 0.00030 U	< 0.00054 U	< 0.00069 U	< 0.00093 U	< 0.00030 U	< 0.00033 U	< 0.00030 U
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15-20220613	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108-20220613	SSHS-IRM5A2-A4-S108	6/13/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395961	Not Excavated	< 0.00022 U	< 0.00039 U	< 0.00049 U	< 0.00066 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109-20220613	SSHS-IRM5A2-A4-S109	6/13/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395961	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18-20220613	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0065 U	< 0.0057 U	< 0.0028 U	< 0.0032 U	< 0.011 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19-20220613	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27-20220613	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated	< 0.0011 U	0.0026 J	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31-20220613	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39-20220613	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121-20220614	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122-20220614	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00028 U	< 0.00050 U	< 0.00063 U	< 0.00085 U	< 0.00027 U	< 0.00030 U	< 0.00027 U
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43-20220614	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated	< 0.00012 U	0.0035	< 0.00027 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1-20220614	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	0.00051 J	0.00057 J	0.0011 J
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2-20220614	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3-20220614	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4-20220614	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00032 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5-20220614	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6-20220614	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 UT	< 0.00018 UT	< 0.00016 UT
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7-20220614	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8-20220614	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9-20220614	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10-20220614	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2-20220614	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4-20220614	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5-20220614	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated	< 0.00026 U	< 0.00047 U	< 0.00059 U	< 0.00079 U	< 0.00025 U	< 0.00028 U	< 0.00025 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123-20220615	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1-20220615	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated	< 0.000081 U	< 0.00015 U	< 0.00019 U	< 0.00025 U	< 0.000080 U	< 0.000089 U	< 0.000080 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3-20220615	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5-20220615	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7-20220615	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126-20220616	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125-20220616	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601-20220616	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0050 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601-20220616	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604-20220616	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0059 U	< 0.0051 U	< 0.0025 U	< 0.0029 U	< 0.01 U
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605-20220616	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 0.0012 U	< 0.0019 U	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606-20220616	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607-20220616	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130-20220617	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated	< 0.00019 U	0.00045 J	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	0.0058	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.0042 U	< 0.00019 U	< 0.00020 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	0.097	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	0.0031	< 0.00037 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	0.098	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00081 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	0.066	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	0.0065	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	0.0092	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	0.033	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00077 U	0.00025 J	< 0.00030 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.0077 U	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00057 U	< 0.0014 U	< 0.00036 U	< 0.00052 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	0.0054 J	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00_SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 UT	< 0.00037 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	0.0063	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 UT	< 0.00039 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00042 U	< 0.0010 U	< 0.00027 UT	< 0.00039 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 UT	< 0.00043 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	0.0070	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 UT	< 0.00037 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	0.03	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 UT	< 0.00037 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 UT	< 0.00037 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	0.0070	< 0.00023 UT	< 0.00025 U	< 0.00023 U	< 0.00037 UT	< 0.00088 U	< 0.00023 UT	< 0.00034 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 UT	< 0.00038 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	0.18	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	0.0011	< 0.00037 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00084 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	0.012 T	< 0.00031 U	< 0.00034 UT	< 0.00031 UT	< 0.00051 UT	< 0.0012 UT	< 0.00032 UT	< 0.00047 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	0.012	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	0.013	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 UT	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 UT	< 0.00030 U	< 0.00043 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 UT	< 0.00028 U	< 0.00041 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00098 UT	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	0.04	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 UT	< 0.00029 U	< 0.00042 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 UT	< 0.00024 U	< 0.00036 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	0.0062	< 0.00024 U	< 0.00026 UT	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 UT	< 0.00024 U	< 0.00039 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 UT	< 0.00025 U	< 0.00041 U	< 0.00098 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 UT	< 0.00023 U	< 0.00038 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 UT	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	0.017	< 0.00022 U	< 0.00024 UT	< 0.00022 U	< 0.00036 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	0.0041 J	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	0.02 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 UT	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 UT	< 0.00025 U	< 0.00042 U	< 0.00099 UT	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	0.016	< 0.00035 U	< 0.00038 U	< 0.00035 U	< 0.00057 U	< 0.0013 U	< 0.00036 U	< 0.00052 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00033 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 UT
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00033 U	< 0.00017 U	< 0.00035 UT
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00071 U	< 0.0013 U	< 0.00059 U	< 0.00030 U	< 0.00062 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 UT	< 0.00020 U	< 0.00043 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0022 J	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0029 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	0.0019 J	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00016 UT	< 0.00017 UT	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 UT	< 0.00022 U	< 0.00047 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 UT	< 0.00026 U	< 0.00055 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 UT	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 UT	< 0.00021 U	< 0.00044 UT
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 UT	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.00021 UT	< 0.00023 UT	< 0.00063 UT	< 0.0012 UT	< 0.00052 UT	< 0.00027 UT	< 0.00055 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	0.0022 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0025 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	0.0026 BJ	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0020 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0021 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0022 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	0.0020 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0022 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0022 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0025 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 UT
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0024 BJ	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0036 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0033 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	0.0033 BJ	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	0.0037 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	0.0037 BJ	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	0.0029 BJ	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0030 BJ	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	0.0032 BJ	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00043 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.00019 U	< 0.00020 U	< 0.00055 UT	< 0.0010 U	< 0.00046 UT	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.00018 UT	< 0.00019 UT	< 0.00052 UT	< 0.00096 U	< 0.00043 UT	< 0.00022 U	< 0.00046 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.00024 U	< 0.00026 U	< 0.00070 U	< 0.0013 U	< 0.00058 UT	< 0.00030 U	< 0.00062 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.00083 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.00092 U	< 0.00015 U	< 0.00027 U	< 0.00029 UT	< 0.00029 UT	< 0.00018 UT	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.00088 U	< 0.00014 U	< 0.00026 U	< 0.00028 UT	< 0.00028 UT	< 0.00017 UT	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00046 U	< 0.00049 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.005 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00021 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	0.0014 J	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.0010 U	< 0.00016 UT	< 0.00030 U	< 0.00032 UT	< 0.00032 UT	< 0.00020 UT	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 UT	< 0.00035 UT	< 0.00022 UT	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00030 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.0014 UT	< 0.00022 UT	< 0.00041 UT	< 0.00044 UT	< 0.00044 UT	< 0.00027 UT	< 0.00025 UT	< 0.00036 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0026 U	< 0.0018 UT	< 0.0033 UT	< 0.0016 UT	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00038 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.0011 U	< 0.00018 UT	< 0.00034 U	< 0.00036 UT	< 0.00036 UT	< 0.00022 UT	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.0015 U	< 0.00024 U	< 0.00045 U	< 0.00049 U	< 0.00049 U	< 0.00030 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00020 U	0.00020 J
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.00030 U	< 0.00052 U	< 0.00048 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 UT	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 UT	< 0.00023 UT	< 0.00018 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 UT	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 UT	< 0.00050 U	< 0.00032 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 UT	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 UT	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 UT	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.00027 UT	< 0.00046 UT	< 0.00043 UT	< 0.00030 UT	< 0.00051 UT	< 0.00033 UT	< 0.00032 UT	< 0.00024 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 UT	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 UT	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.00025 U	0.00054 J	0.00054 J	< 0.00028 UT	< 0.00047 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 UT	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 UT	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 UT	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 UT	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 UT
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00044 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00036 U	< 0.00024 U	< 0.00042 U	< 0.00027 UT	< 0.00026 UT	< 0.00020 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.00030 U	< 0.00051 U	< 0.00048 U	< 0.00033 U	< 0.00057 U	< 0.00037 U	< 0.00036 U	< 0.00027 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.00029 U	0.0031 J	< 0.00027 U	< 0.0041 U	< 0.00048 U	0.026	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	0.033	< 0.0013 U	< 0.00041 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	0.019	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.00023 U	< 0.0013 U	0.00025 J	< 0.0033 U	< 0.00038 U	0.0029 J	< 0.0012 U	< 0.00039 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.00041 U	< 0.0023 U	< 0.00039 U	< 0.0058 U	< 0.00067 U	< 0.00050 U	< 0.0021 U	< 0.00069 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	0.014	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	0.012	< 0.00045 U	0.0066	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 UT	< 0.0038 U	< 0.00044 U	< 0.00032 UT	< 0.0014 UT	< 0.00045 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	0.0045 J	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0018 U	< 0.00061 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.00029 U	0.0057	< 0.00027 U	< 0.0041 U	< 0.00048 U	0.045	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.00036 UT	< 0.0021 UT	< 0.00034 UT	< 0.0052 UT	< 0.00060 UT	< 0.00044 UT	< 0.0019 UT	< 0.00062 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	0.0053 J	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.00033 U	0.0019 J	< 0.00031 U	< 0.0047 U	< 0.00054 U	0.012	< 0.0017 U	< 0.00056 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	0.0031 J	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	0.0064	< 0.0019 U	< 0.0016 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0075 U	< 0.0024 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0043 UT	< 0.00050 U	< 0.00037 UT	< 0.0015 U	< 0.00051 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.00040 U	< 0.0023 U	< 0.00038 U	< 0.0058 U	< 0.00067 U	< 0.00049 U	< 0.0021 U	< 0.00069 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.00020 U	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.00022 U	< 0.00017 UT	< 0.00025 U	0.00023 J	< 0.00015 UT	< 0.00029 UT	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00016 UT	< 0.00023 U	< 0.00018 U	< 0.00014 UT	< 0.00028 UT	< 0.00018 U
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.00038 U	< 0.00029 U	< 0.00041 U	< 0.00032 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	0.00033 J	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	0.00027 J	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	0.00080 J	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 UT	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 UT	< 0.00036 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 UT	< 0.00039 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	0.00027 J	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 UT	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 UT	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 UT	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 UT	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00024 UT	< 0.00019 U	< 0.00027 UT	< 0.00021 U	< 0.00016 UT	< 0.00032 UT	< 0.00021 U
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 UT	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 UT	< 0.00042 U	< 0.00028 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 UT	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.00027 U	< 0.00020 UT	< 0.00029 U	< 0.00022 U	< 0.00017 UT	< 0.00034 UT	< 0.00022 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 UT	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.00034 UT	< 0.00026 UT	0.00050 JT	< 0.00028 UT	< 0.00022 UT	< 0.00043 UT	< 0.00028 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	0.00044 J	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	0.00029 J	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 UT	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UT	< 0.0027 UT	< 0.0018 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	0.0020	< 0.00022 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00024 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00030 UT	0.00025 J	< 0.00018 U	< 0.00036 UT	< 0.00023 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.00037 U	< 0.00029 U	< 0.00041 U	< 0.00031 U	< 0.00024 U	< 0.00048 U	< 0.00031 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129-20220617	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9-20220617	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11-20220617	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00030 U	< 0.00040 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1-20220617	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2-20220617	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3-20220617	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	0.00030 J	0.00034 J	0.00064 J
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4-20220617	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	0.00028 J	0.00019 J	0.00047 J
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5-20220617	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated	< 0.00017 U	0.00033 J	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6-20220617	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7-20220617	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4-20220617	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated	< 0.00014 U	0.00071 J	< 0.00031 U	< 0.00042 U	0.00022 J	0.00027 J	0.00050 J
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT-20220617	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00055 U	< 0.00074 U	< 0.00024 U	< 0.00026 U	< 0.00024 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135-20220620	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-8-10	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 004 U	< 002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-8-10	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-3B	062122 07:00 SSHS-DW-3B-SUB-8-10	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated	< 0.001 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11-20220620	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12-20220620	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13-20220620	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00018 U	0.00093 J	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14-20220620	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15-20220620	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16-20220620	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17-20220620	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated	< 0.00016 U	0.0015	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6-20220620	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7-20220620	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated	0.00029 J	0.032	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8-20220620	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00017 U	0.00031 J	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9-20220620	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated	< 0.00016 UT	< 0.00028 UT	< 0.00036 U	< 0.00048 U	< 0.00015 UT	< 0.00017 UT	< 0.00015 UT
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1-20220620	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2-20220620	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3-20220620	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 UT	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4-20220620	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1-20220620	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2-20220620	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 UT	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8-20220620	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated	< 0.00021 UT	< 0.00039 UT	< 0.00049 UT	< 0.00066 UT	< 0.00021 UT	< 0.00023 UT	< 0.00021 UT
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10-20220620	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 UT	< 0.00059 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12-20220620	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated	< 0.00016 U	0.0016	< 0.00036 UT	< 0.00049 UT	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13-20220620	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated	< 0.00020 U	0.0011	< 0.00046 UT	< 0.00061 UT	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14-20220620	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 UT	< 0.00058 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15-20220620	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated	< 0.00018 U	0.00040 J	< 0.00040 UT	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16-20220620	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 UT	< 0.00059 UT	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18-20220620	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 UT	< 0.00050 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20-20220620	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 UT	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21-20220620	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 UT	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22-20220620	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 UT	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23-20220620	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 UT	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24-20220620	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 UT	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8-20220620	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 UT	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139-20220621	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634-20220621	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635-20220621	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640-20220621	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641-20220621	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642-20220621	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643-20220621	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644-20220621	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645-20220621	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633-20220621	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815-20220622	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145-20220630	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12-20220630	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13-20220630	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70-20220630	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69-20220630	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64-20220630	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14-20220630	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63-20220630	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3-20220708	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6-20220708	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00038 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9-20220708	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00057 UT	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1-20220708	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 UT	< 0.00054 UT	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159-20220711	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158-20220711	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1-20220711	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated	< 0.00024 U	< 0.00043 U	< 0.00055 U	< 0.00073 U	< 0.00023 U	< 0.00026 U	< 0.00023 U
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2-20220711	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.0020 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0057 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	0.011	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00081 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	0.021	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	0.035	0.00038 J	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.0068 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00046 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00086 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	0.0063	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00062 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.0060 U	< 0.00027 U	< 0.00029 U	< 0.00027 U	< 0.00044 U	< 0.0010 U	< 0.00028 U	< 0.00040 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	0.0065	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	0.0052	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	0.0066	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	0.32	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 U	< 0.00099 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	0.013	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.0059 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00028 U	< 0.00046 U	< 0.0011 U	< 0.00029 U	< 0.00042 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated								
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.0034 U	< 0.00015 U	< 0.00017 U	< 0.00015 U	< 0.00025 U	< 0.00059 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.0039 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00029 U	< 0.00068 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 U	< 0.00043 U	< 0.00011 U	< 0.00017 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.0025 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00019 U	< 0.00044 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	0.0031	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00019 U	< 0.00045 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.0030 U	< 0.00013 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.0045 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00034 U	< 0.00079 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.0024 U	< 0.00011 U	< 0.00012 U	< 0.00011 U	< 0.00018 U	< 0.00042 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.0032 U	< 0.00014 U	< 0.00016 U	< 0.00014 U	< 0.00024 U	< 0.00056 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00054 U	< 0.00014 U	< 0.00021 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00023 U	< 0.00055 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.0059 U	< 0.00027 U	< 0.00029 U	< 0.00026 U	< 0.00044 U	< 0.0010 U	< 0.00027 U	< 0.00040 UT
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00025 U	< 0.00036 UT
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00036 UT
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 UT
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.0091 U	< 0.00041 U	< 0.00045 U	< 0.00041 U	< 0.00068 U	< 0.0016 U	< 0.00042 U	< 0.00062 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 UT
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.0050 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00037 U	< 0.00087 U	< 0.00023 U	< 0.00034 UT
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00031 U	< 0.00029 U	< 0.00047 U	< 0.0011 U	< 0.00030 U	< 0.00043 UT
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00092 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.0068 U	< 0.00031 U	< 0.00033 U	< 0.00031 U	< 0.00051 U	< 0.0012 U	< 0.00032 U	< 0.00046 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.0073 U	< 0.00033 U	< 0.00036 U	< 0.00033 U	< 0.00054 U	< 0.0013 U	< 0.00034 U	< 0.00049 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.0064 U	< 0.00029 U	< 0.00032 U	< 0.00029 U	< 0.00048 U	< 0.0011 U	< 0.00030 U	< 0.00044 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.0043 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00032 U	< 0.00075 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.0044 U	< 0.00020 U	< 0.00022 U	< 0.00020 U	< 0.00033 U	< 0.00077 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.0066 U	< 0.00030 U	< 0.00032 U	< 0.00030 U	< 0.00049 U	< 0.0012 U	< 0.00031 U	< 0.00045 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00019 U	< 0.00052 U	< 0.00097 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	0.00046 J	< 0.00041 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00057 U	< 0.0011 U	< 0.00047 U	< 0.00024 U	< 0.00050 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00037 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.00011 U	< 0.00012 U	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00048 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00047 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.000096 U	< 0.00011 U	< 0.00028 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00010 U	< 0.00011 U	< 0.00031 U	< 0.00057 U	< 0.00026 U	< 0.00013 U	< 0.00027 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00013 U	< 0.00035 U	< 0.00066 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.000076 U	< 0.000083 U	< 0.00022 U	< 0.00042 U	< 0.00019 U	< 0.000095 U	< 0.00020 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.000079 U	< 0.000086 U	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000098 U	< 0.00020 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.000088 U	< 0.000097 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.000087 U	< 0.000096 U	< 0.00026 U	< 0.00048 U	< 0.00021 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.000080 U	< 0.000088 U	< 0.00024 U	< 0.00044 U	< 0.00020 U	< 0.00010 U	< 0.00021 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.000092 U	< 0.00010 U	< 0.00027 U	< 0.00050 U	< 0.00023 U	< 0.00011 U	< 0.00024 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.000098 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	0.00042 J	< 0.00025 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00041 U	< 0.00077 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.000086 U	< 0.000095 U	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.000088 U	< 0.000096 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.000075 U	< 0.000082 U	< 0.00022 U	< 0.00041 U	< 0.00018 U	< 0.000093 U	< 0.00019 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.000099 U	< 0.00011 U	< 0.00029 U	< 0.00054 U	< 0.00024 U	< 0.00012 U	< 0.00026 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.000095 U	< 0.00010 U	< 0.00028 U	< 0.00052 U	< 0.00023 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.000097 U	< 0.00011 U	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00054 U	< 0.0010 U	< 0.00045 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00090 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.00028 U	< 0.00031 U	< 0.00083 U	< 0.0015 U	< 0.00069 U	< 0.00035 U	< 0.00073 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.00015 U	< 0.00017 U	< 0.00045 U	< 0.00084 U	< 0.00038 U	< 0.00019 U	< 0.00040 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00025 U	< 0.00051 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00062 U	< 0.0012 U	< 0.00052 U	< 0.00026 U	< 0.00055 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.00023 U	< 0.00025 U	< 0.00067 U	< 0.0012 U	< 0.00056 U	< 0.00028 U	< 0.00059 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00059 U	< 0.0011 U	< 0.00049 U	< 0.00025 U	< 0.00052 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.00021 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.00013 U	< 0.00015 U	< 0.00039 U	< 0.00073 U	< 0.00033 U	< 0.00017 U	< 0.00035 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.00014 U	< 0.00015 U	< 0.00040 U	< 0.00075 U	< 0.00034 U	< 0.00017 U	< 0.00036 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.00020 U	< 0.00022 U	< 0.00060 U	< 0.0011 U	< 0.00050 U	< 0.00026 U	< 0.00053 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.0044 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0030 U	< 0.0015 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00025 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00027 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.0010 U	< 0.00016 U	0.00049 J	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0048 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0048 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.0012 U	< 0.00020 U	< 0.00037 U	< 0.00039 U	< 0.00040 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 U	< 0.00043 U	< 0.00043 U	< 0.00027 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00099 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.00071 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00038 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00094 U	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00019 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	0.0059	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00035 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated								
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00062 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00068 U	< 0.00011 U	< 0.00020 U	< 0.00021 U	< 0.00022 U	< 0.00013 U	< 0.00012 U	< 0.00018 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.00077 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00025 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.00049 U	< 0.000077 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.000097 U	< 0.000088 U	< 0.00013 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00051 U	< 0.000080 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000092 U	< 0.00013 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.00057 U	< 0.000090 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.00057 U	< 0.000089 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.00052 U	< 0.000081 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000093 U	< 0.00013 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.00060 U	< 0.000094 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.00063 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.00091 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.00056 U	< 0.000088 U	< 0.00017 U	< 0.00018 UT	< 0.00018 UT	< 0.00011 UT	< 0.00010 U	< 0.00014 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00057 U	< 0.000089 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.00048 U	< 0.000076 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000095 U	< 0.000087 U	< 0.00012 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00064 U	< 0.00010 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.00062 U	< 0.000097 U	< 0.00018 U	< 0.00019 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00063 U	< 0.000098 U	< 0.00018 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00035 U	< 0.00037 U	< 0.00038 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00033 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.0018 U	< 0.00029 U	< 0.00054 UT	< 0.00057 U	< 0.00058 U	< 0.00036 U	< 0.00033 U	< 0.00047 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.00099 U	< 0.00016 U	< 0.00029 U	< 0.00031 U	< 0.00032 U	< 0.00019 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	0.0013 J	< 0.00020 U	< 0.00038 U	< 0.00040 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 UT	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.0014 U	< 0.00021 U	< 0.00040 UT	< 0.00043 U	< 0.00044 U	< 0.00027 U	< 0.00025 U	< 0.00035 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.0015 U	< 0.00023 U	< 0.00043 UT	< 0.00046 U	< 0.00047 U	< 0.00029 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00038 UT	< 0.00041 U	< 0.00041 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.00086 U	< 0.00014 U	< 0.00025 U	< 0.00027 U	< 0.00027 U	< 0.00017 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.00089 U	< 0.00014 U	< 0.00026 U	< 0.00028 U	< 0.00028 U	< 0.00017 U	< 0.00016 U	< 0.00023 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00039 U	< 0.00042 U	< 0.00042 U	< 0.00026 U	< 0.00024 U	< 0.00034 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00038 U	< 0.00036 U	< 0.00025 U	< 0.00042 U	< 0.00027 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0025 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00026 U	< 0.00046 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00039 U	< 0.00027 U	< 0.00046 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.00027 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00024 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.00023 U	< 0.00040 U	< 0.00037 U	< 0.00026 U	< 0.00044 U	< 0.00028 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00019 U	< 0.00031 U	< 0.00030 U	< 0.00020 U	< 0.00035 U	< 0.00023 U	< 0.00022 U	< 0.00016 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	0.00054 J
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00029 U	< 0.00021 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated								
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00021 U	< 0.00015 U	< 0.00025 U	< 0.00016 U	< 0.00016 U	< 0.00012 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00024 U	< 0.00017 U	< 0.00029 U	< 0.00018 U	< 0.00018 U	< 0.00013 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.000097 U	< 0.00016 U	< 0.00015 U	< 0.00011 U	< 0.00018 U	< 0.00012 U	< 0.00011 U	< 0.000085 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000088 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000099 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000098 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000090 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.00018 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00017 U	< 0.00012 U	< 0.00021 U	< 0.00013 UT	< 0.00013 UT	< 0.000097 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000098 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.000095 U	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00018 U	< 0.00011 U	< 0.00011 U	< 0.000084 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00013 U	< 0.00021 U	< 0.00020 U	< 0.00014 U	< 0.00024 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00019 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00014 U	< 0.00011 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00037 U	< 0.00025 U	< 0.00044 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00018 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.00036 U	< 0.00061 U	< 0.00057 U	< 0.00039 U	< 0.00067 U	< 0.00043 U	< 0.00042 U	< 0.00032 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.00027 U	< 0.00046 U	< 0.00043 U	< 0.00029 U	< 0.00050 U	< 0.00033 U	< 0.00032 U	< 0.00024 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.00029 U	< 0.00049 U	< 0.00046 U	< 0.00031 U	< 0.00054 U	< 0.00035 U	< 0.00034 U	< 0.00025 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00025 U	< 0.00043 U	< 0.00040 U	< 0.00028 U	< 0.00048 U	< 0.00031 U	< 0.00030 U	< 0.00022 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00029 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00027 U	< 0.00018 U	< 0.00032 U	< 0.00021 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00028 U	< 0.00019 U	< 0.00033 U	< 0.00021 U	< 0.00021 U	< 0.00015 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.00026 U	< 0.00044 U	< 0.00041 U	< 0.00028 U	< 0.00049 U	< 0.00032 U	< 0.00031 U	< 0.00023 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00051 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	0.00058 J	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00031 U	< 0.0046 U	< 0.00054 U	0.0038 J	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	0.00086 J	0.0035 J	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	0.00056 J	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.00019 U	< 0.0011 U	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00096 U	< 0.00032 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00030 U	< 0.0045 U	< 0.00052 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 U	< 0.00042 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	0.044	< 0.00049 U	0.037	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.00031 U	< 0.0018 UT	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.00032 U	< 0.0018 UT	< 0.00031 U	< 0.0046 U	< 0.00054 U	< 0.00040 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.00028 U	< 0.0016 UT	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated								
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00016 U	< 0.00093 U	< 0.00016 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	< 0.0025 U	< 0.00030 U	< 0.00022 U	< 0.00092 U	< 0.00030 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.00020 U	< 0.0012 U	< 0.00019 U	< 0.0029 U	< 0.00034 U	< 0.00025 U	< 0.0011 U	< 0.00035 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.00013 U	< 0.00073 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00016 U	< 0.00067 U	< 0.00022 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00013 U	< 0.00076 U	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00069 U	< 0.00023 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00078 U	< 0.00026 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00084 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00077 U	< 0.00013 U	< 0.0019 U	< 0.00023 U	< 0.00017 U	< 0.00070 U	< 0.00023 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.00016 U	< 0.00089 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00081 U	< 0.00027 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.00017 U	< 0.00095 U	< 0.00016 U	< 0.0024 U	0.00059	< 0.00020 U	< 0.00086 U	< 0.00028 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0034 U	< 0.00040 U	< 0.00029 U	< 0.0012 U	< 0.00041 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00084 U	< 0.00014 U	< 0.0021 UT	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.00013 U	< 0.00072 U	< 0.00012 U	< 0.0018 U	< 0.00021 U	< 0.00016 U	< 0.00066 U	< 0.00022 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00017 U	< 0.00096 U	< 0.00016 U	< 0.0024 U	< 0.00028 U	< 0.00021 U	< 0.00087 U	< 0.00029 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.00016 U	< 0.00092 U	< 0.00015 U	< 0.0023 U	< 0.00027 U	< 0.00020 U	< 0.00084 U	< 0.00028 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00016 U	< 0.00094 U	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00031 U	< 0.0018 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00038 U	< 0.0016 U	< 0.00053 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated								
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.00048 U	< 0.0027 U	< 0.00045 U	< 0.0068 U	< 0.00079 U	< 0.0025 U	< 0.00082 U	
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	0.00070 J	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00025 U	< 0.0037 U	< 0.00043 U	< 0.00032 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0017 U	< 0.00057 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.00036 U	< 0.0020 U	< 0.00034 U	< 0.0051 U	< 0.00059 U	< 0.00044 U	< 0.0019 U	< 0.00061 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.00038 U	< 0.0022 U	< 0.00036 U	< 0.0055 U	< 0.00064 U	< 0.00047 U	< 0.0020 U	< 0.00065 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00034 U	< 0.0019 U	< 0.00032 U	< 0.0048 U	< 0.00056 U	< 0.00041 U	< 0.0018 U	< 0.00058 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00043 U	< 0.0018 U	< 0.00059 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00021 U	< 0.0032 U	< 0.00038 U	< 0.00028 U	< 0.0012 U	< 0.00038 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.00023 U	< 0.0013 U	< 0.00022 U	< 0.0033 U	< 0.00039 U	< 0.00028 U	< 0.0012 U	< 0.00040 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0050 U	< 0.00058 U	< 0.00042 U	< 0.0018 U	< 0.00059 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00021 U	< 0.00031 U	< 0.00023 U	< 0.00018 U	< 0.00036 U	< 0.00023 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.00032 J	< 0.00020 U	< 0.00039 U	< 0.00025 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	0.00033 J	< 0.00021 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00023 U	< 0.00017 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	0.00035 J	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.00069 J	< 0.00019 U	< 0.00039 U	< 0.00025 UT
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.0010 J	< 0.00020 U	< 0.00039 U	< 0.00025 UT
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00028 U	< 0.00021 U	< 0.00042 U	< 0.00028 UT
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 UT
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 UT
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	0.00018 J	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00032 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00025 U	< 0.00019 U	< 0.00015 U	< 0.00030 U	< 0.00019 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	< 0.00027 U	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	0.00037 J	< 0.00021 U	< 0.00030 U	0.00086 J	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	0.00064 J	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00045 J	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00016 U	< 0.00013 U	< 0.00018 U	0.00016 J	< 0.00011 U	< 0.00021 U	< 0.00014 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.00019 U	< 0.00014 U	< 0.00021 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.00012 U	< 0.000092 U	< 0.00013 U	< 0.00010 U	< 0.000078 U	< 0.00015 U	< 0.00010 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00012 U	< 0.000095 U	< 0.00014 U	< 0.00010 U	< 0.000080 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	0.00014 J	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000089 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.00013 U	< 0.000097 U	< 0.00014 U	< 0.00011 U	< 0.000082 U	< 0.00016 U	< 0.00011 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00016 U	0.00016 J	< 0.000094 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00019 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	0.00024 J	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.00014 UT	< 0.00010 U	< 0.00015 U	< 0.00011 U	< 0.000088 U	< 0.00017 UT	< 0.00011 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 U	< 0.00012 U	< 0.000090 U	< 0.00018 U	< 0.00012 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.00012 U	< 0.000090 U	< 0.00013 U	< 0.000099 U	< 0.000076 U	< 0.00015 U	< 0.000098 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00017 U	0.00013 J	< 0.00010 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	0.00020 J	< 0.00012 U	< 0.00016 U	< 0.00013 U	< 0.000098 U	< 0.00019 U	< 0.00013 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00029 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00019 U	< 0.00037 U	< 0.00024 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00035 U	< 0.00022 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.00044 U	< 0.00034 U	< 0.00049 U	0.00078 J	< 0.00029 U	< 0.00057 U	< 0.00037 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00026 U	< 0.00020 U	< 0.00016 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 UT	< 0.00038 UT	< 0.00025 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 UT	< 0.00033 UT	< 0.00021 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.00033 U	< 0.00026 U	< 0.00036 U	< 0.00028 U	< 0.00022 U	< 0.00043 U	< 0.00028 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.00036 U	< 0.00027 U	< 0.00039 U	< 0.00030 U	< 0.00023 U	< 0.00046 U	< 0.00030 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00040 U	< 0.00026 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.00032 U	< 0.00025 U	< 0.00035 U	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.00021 U	< 0.00016 U	< 0.00023 U	< 0.00018 U	< 0.00014 U	< 0.00027 U	< 0.00018 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.00022 U	< 0.00017 U	< 0.00024 U	< 0.00018 U	< 0.00014 U	< 0.00028 U	< 0.00018 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.00032 U	< 0.00025 U	0.00043 J	< 0.00027 U	< 0.00021 U	< 0.00041 U	< 0.00027 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4-20220711	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated	< 0.00096 U	< 0.0015 U	< 0.0040 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.0070 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5-20220711	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8-20220711	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9-20220711	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10-20220711	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175-20220725	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1-20220725	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2-20220725	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2-20220728	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3-20220728	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5-20220728	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187-20220808	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185-20220808	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2-20220808	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3-20220808	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4-20220808	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1-20220808	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2-20220808	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1-20220808	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800-20220808	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	0.00034 J	< 0.00021 U	0.00034 J
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002-20220808	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated	< 0.00019 U	< 0.00035 U	< 0.00044 U	< 0.00059 U	0.00051 J	0.00022 J	0.00073 J
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003-20220808	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004-20220808	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005-20220808	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13-20220808	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14-20220808	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16-20220808	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00042 U	< 0.00057 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18-20220808	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7-20220808	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8-20220808	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9-20220808	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00047 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10-20220808	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	0.0017	0.00084 J	0.0025
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT-20220808	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3-20220810	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5-20220810	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated	< 0.00019 U	0.00051 J	< 0.00044 U	< 0.00059 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7-20220810	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated	< 0.00016 U	0.00033 J	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220813	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197-20220815	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.000097 U	< 0.00017 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198-20220815	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00024 U	< 0.00032 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97-20220815	SSHS-IRM5A2-FISR-S97	8/15/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429581	Not Excavated	< 0.00012 U	< 0.00022 U	< 0.00027 U	< 0.00037 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22-20220815	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated	< 0.000076 U	< 0.00014 U	< 0.00017 U	< 0.00023 U	< 0.000075 U	< 0.000083 U	< 0.000075 U
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23-20220815	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.000079 U	< 0.00014 U	< 0.00018 U	< 0.00024 U	< 0.000077 U	< 0.000086 U	< 0.000077 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12-20220815	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated	< 0.000089 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000087 U	< 0.000097 U	< 0.000087 U
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13-20220815	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000086 U	< 0.000096 U	< 0.000086 U
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14-20220815	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated	< 0.000080 U	< 0.00014 U	< 0.00018 U	< 0.00025 U	< 0.000079 U	< 0.000088 U	< 0.000079 U
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15-20220815	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated	< 0.000093 U	< 0.00017 U	< 0.00021 U	< 0.00028 U	< 0.000090 U	< 0.00010 U	< 0.000090 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12-20220815	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated	< 0.000098 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000096 U	< 0.00011 U	< 0.000096 U
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13-20220815	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated	< 0.00014 U	< 0.00025 U	< 0.00032 U	< 0.00043 U	< 0.00014 U	< 0.00015 U	< 0.00014 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14-20220815	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15-20220815	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated	< 0.000087 UT	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000085 U	< 0.000095 U	< 0.000085 U
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3-20220815	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000086 U	< 0.000096 U	< 0.000086 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25-20220815	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated	< 0.000075 U	0.00031 J	< 0.00017 U	< 0.00023 U	< 0.000073 U	< 0.000082 U	< 0.000073 U
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26-20220815	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated	< 0.000099 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.000097 U	< 0.00011 U	< 0.000097 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27-20220815	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated	< 0.000096 U	< 0.00017 U	< 0.00022 U	< 0.00029 U	< 0.000094 U	< 0.00010 U	< 0.000094 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28-20220815	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated	< 0.000097 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199-20220817	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00042 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2-20220817	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated	< 0.00016 U	0.0019	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4-20220817	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5-20220817	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated							
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9-20220817	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430861	Not Excavated	< 0.00028 U	< 0.00051 U	< 0.00065 U	< 0.00087 UT	0.00035 J	< 0.00031 U	0.00035 J
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12-20220817	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13-20220817	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14-20220817	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00045 U	< 0.00061 U	< 0.00019 U	< 0.00022 U	< 0.00019 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4-20220817	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5-20220817	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194-20220818	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 UT	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76-20220818	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00065 UT	< 0.00021 U	< 0.00023 U	< 0.00021 U
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78-20220818	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated	< 0.00023 U	< 0.00041 U	< 0.00052 U	< 0.00070 UT	< 0.00022 U	< 0.00025 U	< 0.00022 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79-20220818	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated	< 0.00020 U	< 0.00036 U	< 0.00046 U	< 0.00062 UT	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16-20220818	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated	< 0.00021 U	< 0.00037 U	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800-20220823	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00031 U	< 0.00041 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801-20220823	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated	< 0.00014 U	0.00036 J	< 0.00031 U	< 0.00042 U	< 0.00013 U	< 0.00015 U	< 0.00013 U
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802-20220823	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated	< 0.00021 U	0.0011 J	< 0.00047 U	< 0.00063 U	< 0.00020 U	< 0.00022 U	< 0.00020 U

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.0043 U	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00032 U	< 0.00075 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.0048 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00022 U	< 0.00033 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.0083 UT	< 0.00037 UT	< 0.00041 UT	< 0.00037 UT	< 0.00062 UT	< 0.0014 UT	< 0.00039 UT	< 0.00056 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.0063 U	< 0.00028 U	< 0.00031 U	< 0.00028 U	< 0.00047 U	< 0.0011 U	< 0.00029 U	< 0.00043 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	0.032 T	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00028 U	< 0.00026 U	< 0.00043 U	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 U	< 0.00037 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.0061 U	< 0.00028 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 U	< 0.00036 U	< 0.00085 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	0.015	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 UT	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 UT	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.0053 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 UT	< 0.00093 U	< 0.00025 U	< 0.00036 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00028 U	< 0.00025 U	< 0.00042 UT	< 0.00099 U	< 0.00026 UT	< 0.00038 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.0061 U	< 0.00027 U	< 0.00030 U	< 0.00027 U	< 0.00045 U	< 0.0011 U	< 0.00028 U	< 0.00041 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.0067 U	< 0.00030 U	< 0.00033 U	< 0.00030 U	< 0.00050 U	< 0.0012 U	< 0.00031 U	< 0.00045 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.0046 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	< 0.00021 U	< 0.00031 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00027 U	< 0.00024 U	< 0.00040 U	< 0.00095 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 U	< 0.00034 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.0027 U	< 0.00012 U	< 0.00013 U	< 0.00012 U	< 0.00020 UT	< 0.00047 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.0047 U	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.0030 U	< 0.00013 U	< 0.00015 U	< 0.00013 U	< 0.00022 U	< 0.00052 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.0049 U	< 0.00022 U	< 0.00024 U	< 0.00022 UT	< 0.00036 UT	< 0.00085 U	< 0.00023 U	< 0.00033 UT
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.0026 U	< 0.00012 U	< 0.00013 U	< 0.00011 UT	< 0.00019 UT	< 0.00045 U	< 0.00012 U	< 0.00017 UT
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.0036 U	< 0.00016 U	< 0.00018 U	< 0.00016 UT	< 0.00027 UT	< 0.00063 U	< 0.00017 UT	< 0.00024 UT
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.0028 UT	< 0.00012 UT	< 0.00014 UT	< 0.00012 UT	< 0.00021 UT	< 0.00048 UT	< 0.00013 UT	< 0.00019 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.0031 U	< 0.00014 U	< 0.00015 U	< 0.00014 UT	< 0.00023 UT	< 0.00055 U	< 0.00015 UT	< 0.00021 UT
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.0040 U	< 0.00018 U	< 0.00020 U	< 0.00018 UT	< 0.00030 UT	< 0.00071 U	< 0.00019 UT	< 0.00027 UT
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.0028 U	0.00013 J	< 0.00014 U	< 0.00012 UT	< 0.00021 UT	< 0.00048 U	< 0.00013 UT	< 0.00019 UT
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 UT	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.0058 U	< 0.00026 U	< 0.00029 U	< 0.00026 U	< 0.00043 UT	< 0.0010 U	< 0.00027 U	< 0.00039 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.0038 U	< 0.00017 U	< 0.00019 U	< 0.00017 U	< 0.00028 UT	< 0.00067 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	0.0044	< 0.00019 U	< 0.00021 U	< 0.00019 U	< 0.00031 U	< 0.00073 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00034 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.0047 UT	< 0.00021 UT	< 0.00023 UT	< 0.00021 UT	< 0.00035 UT	< 0.00082 UT	< 0.00022 UT	< 0.00032 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.0056 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00097 U	< 0.00026 U	< 0.00038 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.0033 U	< 0.00015 U	< 0.00016 U	< 0.00015 U	< 0.00024 U	< 0.00058 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.0035 U	< 0.00016 U	< 0.00017 U	< 0.00016 U	< 0.00026 U	< 0.00061 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.0028 U	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00050 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00091 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.0023 U	< 0.00011 U	< 0.00011 U	< 0.00011 U	< 0.00017 U	< 0.00041 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00026 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 U	< 0.00035 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	**Chlorodibromomethane**	**Chloroethane**	**Chloroform**	**Chloromethane**	**Cyclohexane**	**1,2-Dibromo-3-Chloropropane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00039 U	< 0.00072 U	< 0.00032 U	< 0.00016 U	< 0.00034 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.00026 UT	< 0.00028 UT	< 0.00076 UT	< 0.0014 UT	< 0.00063 UT	< 0.00032 UT	< 0.00067 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00021 U	< 0.00058 U	< 0.0011 U	< 0.00048 U	< 0.00024 U	< 0.00051 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00045 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00018 U	< 0.00020 U	< 0.00053 U	< 0.00098 U	< 0.00044 U	< 0.00022 U	< 0.00046 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00094 U	< 0.00042 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00056 U	< 0.0010 U	< 0.00046 U	< 0.00024 U	< 0.00049 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00044 U	< 0.00082 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.00016 U	< 0.00017 UT	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00018 UT	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.00016 U	< 0.00018 UT	< 0.00049 U	< 0.00090 U	< 0.00040 U	< 0.00021 U	< 0.00043 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00052 U	< 0.00096 U	< 0.00043 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00021 U	< 0.00055 U	< 0.0010 U	< 0.00046 U	< 0.00023 U	< 0.00049 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00017 UT	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00017 UT	< 0.00018 U	< 0.00050 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.00021 U	< 0.00023 U	< 0.00061 U	< 0.0011 U	< 0.00051 U	< 0.00026 U	< 0.00054 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	< 0.00018 U	< 0.00037 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	< 0.00021 U	< 0.00044 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	< 0.00019 U	< 0.00041 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.000084 U	< 0.000092 UT	< 0.00025 U	< 0.00046 U	< 0.00021 U	< 0.00010 U	< 0.00022 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00043 U	< 0.00079 U	< 0.00035 U	< 0.00018 U	< 0.00038 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00086 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.000092 U	< 0.00010 U	< 0.00027 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.00015 U	< 0.00017 UT	< 0.00045 U	< 0.00083 U	< 0.00037 U	< 0.00019 U	< 0.00039 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.000079 U	< 0.000087 UT	< 0.00023 U	< 0.00043 U	< 0.00019 U	< 0.000099 U	< 0.00021 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00033 U	< 0.00061 U	< 0.00027 U	< 0.00014 U	< 0.00029 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.000086 UT	< 0.000094 UT	< 0.00025 UT	< 0.00047 UT	< 0.00021 UT	< 0.00011 UT	< 0.00022 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.000097 U	< 0.00011 UT	< 0.00029 U	< 0.00053 U	< 0.00024 U	< 0.00012 U	< 0.00025 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00012 U	< 0.00014 UT	< 0.00037 U	< 0.00069 U	< 0.00031 U	< 0.00016 U	< 0.00032 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.000086 U	< 0.000094 UT	< 0.00025 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00051 U	< 0.00094 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.00018 U	< 0.00020 UT	< 0.00053 U	< 0.00099 U	< 0.00044 U	< 0.00023 U	< 0.00047 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.00012 U	< 0.00013 UT	< 0.00035 U	< 0.00065 U	< 0.00029 U	< 0.00015 U	< 0.00031 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.00013 U	< 0.00014 U	< 0.00038 U	< 0.00071 U	< 0.00032 U	< 0.00016 U	< 0.00034 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.00014 UT	< 0.00016 UT	< 0.00043 UT	< 0.00079 UT	< 0.00036 UT	< 0.00018 UT	< 0.00038 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00019 UT	< 0.00051 U	< 0.00095 U	< 0.00042 U	< 0.00022 U	< 0.00045 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.00010 U	< 0.00011 UT	< 0.00030 U	< 0.00056 U	< 0.00025 U	< 0.00013 U	< 0.00026 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.00011 U	< 0.00012 UT	< 0.00032 U	< 0.00060 U	< 0.00027 U	< 0.00014 U	< 0.00028 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.000088 U	< 0.000096 U	< 0.00026 U	< 0.00048 U	< 0.00022 U	< 0.00011 U	< 0.00023 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	< 0.00020 U	< 0.00042 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.000072 U	< 0.000079 U	< 0.00021 U	< 0.00040 U	< 0.00018 U	< 0.000090 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00040 U	< 0.00020 U	< 0.00042 U

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	0.00089 J	< 0.00013 U	< 0.00025 U	< 0.00027 U	< 0.00027 U	< 0.00017 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.0017 UT	< 0.00026 UT	< 0.00049 UT	< 0.00052 UT	< 0.00053 UT	< 0.00033 UT	< 0.00030 UT	< 0.00043 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.0013 U	< 0.00020 U	< 0.00037 U	< 0.00040 U	< 0.00040 U	< 0.00025 U	< 0.00023 U	< 0.00033 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	0.0011 J	< 0.00016 U	< 0.00031 U	< 0.00033 UT	< 0.00033 UT	< 0.00020 UT	< 0.00019 U	< 0.00027 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00036 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00033 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00039 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00032 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0051 U	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0049 U	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.00097 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00017 U	< 0.00025 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00031 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00036 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.0012 U	< 0.00019 U	< 0.00036 U	< 0.00038 U	< 0.00039 U	< 0.00024 U	< 0.00022 U	< 0.00031 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 UT	< 0.00035 UT	< 0.00021 UT	< 0.00020 U	< 0.00028 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 UT	< 0.00035 UT	< 0.00021 UT	< 0.00020 U	< 0.00028 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.0013 U	< 0.00021 U	< 0.00040 U	< 0.00042 U	< 0.00043 U	< 0.00026 U	< 0.00024 U	< 0.00035 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.00092 U	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.0011 U	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00021 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.00054 U	< 0.000085 U	< 0.00016 U	< 0.00017 U	< 0.00017 U	< 0.00011 U	< 0.000097 U	< 0.00014 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.00093 U	< 0.00015 U	< 0.00028 U	< 0.00029 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.00060 U	< 0.000094 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00015 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.00098 U	< 0.00015 U	< 0.00029 U	< 0.00031 U	< 0.00031 U	< 0.00019 U	< 0.00018 U	< 0.00025 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.00051 U	< 0.000080 U	< 0.00015 U	< 0.00016 U	< 0.00016 U	< 0.00010 U	< 0.000092 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00072 U	< 0.00011 U	< 0.00021 U	< 0.00023 U	< 0.00023 U	< 0.00014 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.00055 UT	< 0.000087 UT	< 0.00016 UT	< 0.00017 UT	< 0.00018 UT	< 0.00011 UT	< 0.00010 UT	< 0.00014 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.00063 U	< 0.000099 U	< 0.00019 U	< 0.00020 U	< 0.00020 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00081 U	< 0.00013 U	< 0.00024 U	< 0.00025 U	< 0.00026 U	< 0.00016 U	< 0.00015 U	< 0.00021 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.00055 U	< 0.000087 U	< 0.00016 U	< 0.00017 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.0011 U	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.0012 U	< 0.00018 U	< 0.00034 U	< 0.00037 U	< 0.00037 U	< 0.00023 U	< 0.00021 U	< 0.00030 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.00076 U	< 0.00012 U	< 0.00023 U	< 0.00024 U	< 0.00024 U	< 0.00015 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.00084 U	< 0.00013 U	< 0.00025 U	< 0.00026 U	< 0.00027 U	< 0.00016 U	< 0.00015 U	< 0.00022 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.00094 UT	< 0.00015 UT	< 0.00028 UT	< 0.00030 UT	< 0.00030 UT	< 0.00018 UT	< 0.00017 UT	< 0.00024 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	0.0011 J	< 0.00018 U	< 0.00033 U	< 0.00035 U	< 0.00036 U	< 0.00022 U	< 0.00020 U	< 0.00029 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.00066 U	< 0.00010 U	< 0.00019 U	< 0.00021 U	< 0.00021 U	< 0.00013 U	< 0.00012 U	< 0.00017 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.00070 U	< 0.00011 U	< 0.00021 U	< 0.00022 U	< 0.00022 U	< 0.00014 U	< 0.00013 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00057 U	< 0.000089 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00015 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.00047 U	< 0.000074 U	< 0.00014 U	< 0.00015 U	< 0.00015 U	< 0.000092 U	< 0.000084 U	< 0.00012 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.00017 U	< 0.00029 U	< 0.00027 U	< 0.00018 U	< 0.00032 U	< 0.00020 U	< 0.00020 U	< 0.00015 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00022 U	< 0.00017 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.00033 UT	< 0.00055 UT	< 0.00052 UT	< 0.00036 UT	< 0.00061 UT	< 0.00040 UT	< 0.00039 UT	< 0.00029 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00025 U	< 0.00042 U	< 0.00039 U	< 0.00027 U	< 0.00047 U	< 0.00030 U	< 0.00029 U	< 0.00022 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 UT	< 0.00024 UT	< 0.00018 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.00024 U	< 0.00041 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0021 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0026 U	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0024 U	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.00019 U	< 0.00032 U	< 0.00030 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00033 U	< 0.00023 U	< 0.00039 U	< 0.00025 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.00022 U	< 0.00038 U	< 0.00035 U	< 0.00024 U	< 0.00042 U	< 0.00027 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.00024 U	< 0.00040 U	< 0.00038 U	< 0.00026 U	< 0.00045 U	< 0.00029 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.00026 U	< 0.00045 U	< 0.00042 U	< 0.00029 U	< 0.00050 U	< 0.00032 U	< 0.00031 U	< 0.00023 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.00021 U	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00018 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000094 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.00021 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 UT	< 0.00024 UT	< 0.00018 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.00018 U	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 UT	< 0.00022 UT	< 0.00016 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 UT	< 0.00024 UT	< 0.00018 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 UT	< 0.00014 UT	< 0.00010 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.00019 U	< 0.00033 U	< 0.00031 U	< 0.00021 U	< 0.00036 U	< 0.00023 U	< 0.00023 U	< 0.00017 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.00010 U	< 0.00017 U	< 0.00016 U	< 0.00011 U	< 0.00019 U	< 0.00012 U	< 0.00012 U	< 0.000089 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00014 U	< 0.00024 U	< 0.00022 U	< 0.00015 U	< 0.00027 U	< 0.00017 U	< 0.00017 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.00011 UT	< 0.00018 UT	< 0.00017 UT	< 0.00012 UT	< 0.00020 UT	< 0.00013 UT	< 0.00013 UT	< 0.000096 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.00012 U	< 0.00021 U	< 0.00020 U	< 0.00013 U	< 0.00023 U	< 0.00015 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00016 U	< 0.00027 U	< 0.00025 U	< 0.00017 U	< 0.00030 U	< 0.00019 U	< 0.00019 U	< 0.00014 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.00011 U	< 0.00018 U	< 0.00017 U	< 0.00012 U	< 0.00020 U	< 0.00013 U	< 0.00013 U	< 0.000096 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 UT	< 0.00026 UT	< 0.00019 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.00023 U	< 0.00039 U	< 0.00036 U	< 0.00025 U	< 0.00043 U	< 0.00028 UT	< 0.00027 UT	< 0.00020 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.00015 U	< 0.00025 U	< 0.00024 U	< 0.00016 U	< 0.00028 U	< 0.00018 UT	< 0.00018 UT	< 0.00013 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00026 U	< 0.00018 U	< 0.00031 U	< 0.00020 U	< 0.00019 U	< 0.00015 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.00018 UT	< 0.00031 UT	< 0.00029 UT	< 0.00020 UT	< 0.00035 UT	< 0.00022 UT	< 0.00022 UT	< 0.00016 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.00022 U	< 0.00037 U	< 0.00035 U	< 0.00024 U	< 0.00041 U	< 0.00027 U	< 0.00026 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.00013 U	< 0.00022 U	< 0.00021 U	< 0.00014 U	< 0.00024 U	< 0.00016 U	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.00014 U	< 0.00023 U	< 0.00022 U	< 0.00015 U	< 0.00026 U	< 0.00017 U	< 0.00016 UT	< 0.00012 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00018 U	< 0.00012 U	< 0.00021 U	< 0.00014 U	< 0.00013 U	< 0.000099 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.000092 U	< 0.00016 U	< 0.00015 U	< 0.00010 U	< 0.00017 U	< 0.00011 U	< 0.00011 U	< 0.000081 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.00022 U	< 0.0013 U	< 0.00021 U	< 0.0032 U	< 0.00037 U	< 0.00027 U	< 0.0012 U	< 0.00038 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00024 U	< 0.0036 U	0.00054 J	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.00044 UT	< 0.0025 UT	< 0.00041 UT	< 0.0062 U	< 0.00072 UT	< 0.00053 UT	< 0.0023 UT	< 0.00074 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00033 U	< 0.0019 U	< 0.00031 U	< 0.0047 U	< 0.00055 U	< 0.00041 U	< 0.0017 U	< 0.00056 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00048 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.00027 U	< 0.0016 UT	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 UT	< 0.00047 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00029 U	< 0.0043 U	< 0.00050 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0017 U	< 0.00055 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 UT	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 UT	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 UT	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0023 U	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0028 UT	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00047 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.00026 U	< 0.0015 U	< 0.00024 U	< 0.0037 U	< 0.00042 U	< 0.00031 U	< 0.0013 U	< 0.00043 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00048 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.00030 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00051 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.00032 U	< 0.0018 U	< 0.00030 U	< 0.0046 U	< 0.00053 U	< 0.00039 U	< 0.0016 U	< 0.00054 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 UT	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00029 U	< 0.0016 U	< 0.00027 UT	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00049 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.00035 U	< 0.0020 U	< 0.00033 U	< 0.0051 U	< 0.00059 U	< 0.00043 U	< 0.0018 U	< 0.00060 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.00024 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00040 U	< 0.00030 U	< 0.0013 U	< 0.00041 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.00028 U	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00032 U	< 0.0014 U	< 0.00045 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.00014 U	< 0.00081 U	< 0.00013 U	< 0.0020 U	< 0.00024 U	< 0.00017 U	< 0.00073 U	< 0.00024 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated								
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 UT	< 0.00047 UT
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.00025 U	< 0.0014 U	< 0.00023 U	< 0.0035 U	< 0.00041 U	< 0.00030 U	< 0.0013 UT	< 0.00042 UT
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 UT	< 0.00046 UT
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00089 U	< 0.00015 U	< 0.0022 U	< 0.00026 U	< 0.00019 U	< 0.00081 UT	< 0.00027 UT
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.00026 U	< 0.0015 UT	< 0.00024 U	< 0.0037 U	< 0.00043 U	< 0.00031 U	< 0.0013 U	< 0.00044 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.00013 U	< 0.00076 UT	< 0.00013 U	< 0.0019 U	< 0.00022 U	< 0.00016 U	< 0.00069 U	< 0.00023 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00019 U	< 0.0011 UT	< 0.00018 U	< 0.0027 U	< 0.00031 U	< 0.00023 U	< 0.00098 U	< 0.00032 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.00015 UT	< 0.00083 U	< 0.00014 UT	< 0.0021 UT	< 0.00024 UT	< 0.00018 UT	< 0.00075 UT	< 0.00025 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.00017 U	< 0.00094 UT	< 0.00016 U	< 0.0024 U	< 0.00027 U	< 0.00020 U	< 0.00085 U	< 0.00028 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00021 U	< 0.0012 UT	< 0.00020 U	< 0.0030 U	< 0.00035 U	< 0.00026 U	< 0.0011 U	< 0.00036 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.00015 U	< 0.00083 UT	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00075 U	< 0.00025 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.00031 U	< 0.0017 U	< 0.00029 U	< 0.0044 U	< 0.00051 U	< 0.00037 U	< 0.0016 U	< 0.00052 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.00020 U	< 0.0011 U	< 0.00019 U	< 0.0029 U	< 0.00033 U	< 0.00025 U	< 0.0010 U	< 0.00034 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.00022 U	< 0.0012 U	< 0.00021 U	< 0.0031 U	< 0.00036 U	< 0.00027 U	< 0.0011 U	< 0.00037 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00044 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.00025 UT	< 0.0014 UT	< 0.00023 UT	< 0.0035 UT	< 0.00041 UT	< 0.00030 UT	< 0.0013 UT	< 0.00042 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.00029 U	< 0.0017 U	< 0.00028 U	< 0.0042 U	< 0.00049 U	< 0.00036 U	< 0.0015 U	< 0.00050 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00098 U	< 0.00016 U	< 0.0025 U	< 0.00029 U	< 0.00021 U	< 0.00089 U	< 0.00029 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.00018 U	< 0.0010 U	< 0.00017 U	0.0046	< 0.00031 U	< 0.00023 U	< 0.00095 U	< 0.00031 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00085 U	< 0.00014 U	< 0.0021 U	< 0.00025 U	< 0.00018 U	< 0.00077 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.00012 U	< 0.00070 U	< 0.00012 U	< 0.0018 U	< 0.00020 U	< 0.00015 U	< 0.00064 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.00027 U	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00047 U

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.00021 U	< 0.00016 U	< 0.00023 U	0.00019 J	< 0.00014 U	< 0.00027 U	< 0.00017 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.00023 U	< 0.00018 U	< 0.00026 U	< 0.00020 U	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.00040 UT	< 0.00031 UT	< 0.00044 UT	< 0.00034 UT	< 0.00026 UT	< 0.00052 UT	< 0.00034 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00031 U	< 0.00024 U	< 0.00034 U	< 0.00026 U	< 0.00020 U	< 0.00039 U	< 0.00026 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	0.00036 JT	< 0.00019 U	< 0.00028 U	0.00055 J	< 0.00016 U	< 0.00033 UT	< 0.00021 U
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.00027 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	0.00056 J	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00029 U	< 0.00023 U	< 0.00017 U	< 0.00035 U	< 0.00022 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.00030 U	< 0.00023 U	< 0.00033 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 U	< 0.00021 U	< 0.00016 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00028 J	< 0.00015 U	< 0.00030 U	< 0.00020 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	< 0.00022 U	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	0.00061 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00028 U	0.00041 J	< 0.00017 U	< 0.00033 U	< 0.00022 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.00029 U	< 0.00023 U	< 0.00032 U	< 0.00025 U	< 0.00019 U	< 0.00038 U	< 0.00025 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00026 UT	< 0.00020 U	< 0.00029 UT	0.00023 J	< 0.00017 U	< 0.00034 UT	< 0.00022 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00026 UT	< 0.00020 U	< 0.00029 UT	0.00023 J	< 0.00017 U	< 0.00034 UT	< 0.00022 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.00033 U	< 0.00025 U	< 0.00036 U	0.0017	< 0.00021 U	< 0.00042 U	< 0.00027 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	0.00035 J	< 0.00017 U	< 0.00025 U	0.0066	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.00026 U	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.00024 U	< 0.00019 U	< 0.00027 U	0.0069	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00014 U	0.00057	< 0.000085 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.00025 U	< 0.00020 U	< 0.00028 U	0.0014	< 0.00017 U	< 0.00033 U	< 0.00021 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.00023 U	< 0.00017 U	0.0015	0.00033 J	< 0.00015 U	< 0.00029 U	< 0.00019 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	0.00067 J	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 U	0.0010	< 0.000095 U	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.00024 U	< 0.00018 U	< 0.00026 U	0.00044 J	< 0.00015 U	< 0.00031 U	< 0.00020 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.00012 U	< 0.000096 U	0.00018 J	< 0.00010 U	< 0.000081 U	< 0.00016 U	< 0.00010 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00015 U	< 0.00011 U	< 0.00022 U	< 0.00015 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.00013 UT	< 0.00010 UT	< 0.00015 UT	< 0.00011 UT	< 0.000087 UT	< 0.00017 UT	< 0.00011 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.00015 U	< 0.00012 U	< 0.00017 U	< 0.00013 U	< 0.000099 U	< 0.00020 U	< 0.00013 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00020 U	< 0.00015 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00025 U	< 0.00016 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.00013 U	< 0.00010 U	< 0.00015 U	0.00019 J	< 0.000088 U	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.00028 U	< 0.00022 U	< 0.00031 U	< 0.00024 U	< 0.00018 U	< 0.00036 U	< 0.00024 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.00019 U	< 0.00014 U	< 0.00020 U	< 0.00016 U	< 0.00012 U	< 0.00024 U	< 0.00016 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.00020 UT	< 0.00016 U	< 0.00022 U	< 0.00017 U	< 0.00013 U	< 0.00026 U	< 0.00017 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.00025 UT	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.00023 UT	< 0.00017 UT	< 0.00025 UT	< 0.00019 UT	< 0.00015 UT	< 0.00029 UT	< 0.00019 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.00027 U	< 0.00021 U	< 0.00030 U	< 0.00023 U	< 0.00018 U	< 0.00035 U	< 0.00023 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.00016 U	< 0.00012 U	< 0.00018 U	< 0.00013 U	< 0.00010 U	< 0.00021 U	< 0.00013 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00013 U	< 0.00019 U	< 0.00014 U	< 0.00011 U	< 0.00022 U	< 0.00014 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00014 U	< 0.00011 U	< 0.00015 UT	< 0.00012 U	< 0.000090 UT	< 0.00018 U	< 0.00012 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 UT	< 0.00021 U	< 0.00016 UT	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 UT	< 0.00021 U	< 0.00016 UT	< 0.00032 U	< 0.00021 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.00011 U	< 0.000088 U	< 0.00012 UT	< 0.000096 U	< 0.000074 UT	< 0.00015 U	< 0.00011 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00028 UT	< 0.00021 U	< 0.00016 UT	< 0.00033 U	< 0.00021 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803-20220823	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated	< 0.00013 U	< 0.00024 U	< 0.00030 U	< 0.00041 U	< 0.00013 U	< 0.00014 U	< 0.00013 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800-20220824	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801-20220824	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated	< 0.00026 UT	< 0.00046 UT	< 0.00059 UT	< 0.00079 UT	< 0.00025 UT	< 0.00028 UT	< 0.00025 UT
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002-20220824	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	0.00018 J	< 0.00018 U	0.00018 J
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209-20220825	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00020 U	< 0.00035 U	< 0.00045 U	< 0.00060 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803-20220825	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804-20220825	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated	< 0.00016 UT	< 0.00029 U	< 0.00037 U	< 0.00050 U	0.00033 J	< 0.00018 U	0.00033 J
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805-20220825	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005-20220825	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00041 U	< 0.00055 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006-20220825	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00039 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007-20220825	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00019 U	< 0.00021 U	< 0.00019 U
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A-20220825	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11-20220826	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215-20220902	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0017 U	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214-20220902	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1-20220902	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2-20220902	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3-20220902	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4-20220902	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5-20220902	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6-20220902	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7-20220902	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8-20220902	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9-20220902	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10-20220902	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0018 U	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1-20220902	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2-20220902	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3-20220902	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4-20220902	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5-20220902	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11-20220906	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12-20220906	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00034 U	< 0.00046 U	< 0.00015 U	< 0.00016 U	< 0.00015 U
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6-20220906	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00018 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004-20220908	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005-20220908	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00018 U	< 0.00017 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006-20220908	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007-20220908	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated	< 0.00018 U	< 0.00032 U	< 0.00040 U	< 0.00054 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT-20220908	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated	< 0.00019 U	< 0.00034 U	< 0.00043 U	< 0.00058 U	< 0.00018 U	< 0.00021 U	< 0.00018 U
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT-20220908	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 UT	< 0.00018 UT	< 0.00017 UT
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT-20220908	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00039 U	< 0.00052 U	< 0.00017 UT	< 0.00018 UT	< 0.00017 UT
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13-20220916	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated	< 0.00021 U	< 0.00038 U	< 0.00048 U	< 0.00064 U	< 0.00020 U	< 0.00023 U	< 0.00020 U
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14-20220916	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated	< 0.00014 U	< 0.00026 U	< 0.00033 U	< 0.00044 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A-20220916	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated	< 0.00017 U	< 0.00030 U	< 0.00038 U	< 0.00052 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7-20220916	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated	< 0.00016 U	< 0.00028 U	< 0.00036 U	< 0.00048 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4-20220919	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated	< 0.000084 U	< 0.00015 U	< 0.00019 U	< 0.00026 U	< 0.000082 U	< 0.000092 U	< 0.000082 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221020	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221020	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221020	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221020	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated							
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642-20221024	SSHS-IRM5A2-A6-S642	10/24/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A-20221024	SSHS-IRM5A2-A6-S804A	10/24/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801468451	Not Excavated	< 0.00015 U	< 0.00026 U	< 0.00033 U	< 0.00045 U	< 0.00014 U	< 0.00016 U	< 0.00014 U
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A-20221024	SSHS-IRM5A2-A6-S805A	10/24/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801468451	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801-20221024	SSHS-IRM5A2-A6-B801	10/24/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801468451	Not Excavated	< 0.000093 U	< 0.00017 U	< 0.00021 U	< 0.00029 U	< 0.000091 U	< 0.00010 U	< 0.000091 U
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT-20221025	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated	< 0.00015 U	< 0.00027 U	< 0.00035 U	< 0.00047 U	< 0.00015 U	< 0.00017 U	< 0.00015 U
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT-20221025	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated	< 0.000080 U	0.00019 J	< 0.00018 U	< 0.00024 U	< 0.00078 U	< 0.000087 U	< 0.000078 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247-20221026	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00026 U	< 0.00034 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18-20221026	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated	< 0.000086 UT	< 0.00016 UT	< 0.00020 UT	< 0.00026 UT	< 0.000084 UT	< 0.000094 UT	< 0.000084 UT
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19-20221026	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated	< 0.000098 U	< 0.00018 U	< 0.00022 U	< 0.00030 U	< 0.000095 U	< 0.00011 U	< 0.000095 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20-20221026	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00029 U	< 0.00039 U	< 0.00012 U	< 0.00014 U	< 0.00012 U
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21-20221026	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated	< 0.000086 U	< 0.00016 U	< 0.00020 U	< 0.00026 U	< 0.000084 U	< 0.000094 U	< 0.000084 U
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802-20221202	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803-20221202	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated	< 0.00018 U	< 0.00033 U	< 0.00041 U	< 0.00056 U	< 0.00018 U	< 0.00020 U	< 0.00018 U
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804-20221202	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated	< 0.00012 U	0.00039 J	< 0.00027 U	< 0.00036 U	< 0.00012 U	< 0.00013 U	< 0.00012 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5-20221209	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated	< 0.00013 U	< 0.00023 U	< 0.00030 U	< 0.00040 U	0.00026 J	< 0.00014 U	0.00026 J
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6-20221209	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	0.00043 J	< 0.00017 U	0.00043 J
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1-20221209	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated	< 0.00015 UT	0.0012 T	< 0.00033 UT	< 0.00045 UT	< 0.00014 UT	< 0.00016 UT	< 0.00014 UT
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2-20221209	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated	< 0.00017 U	< 0.00031 U	< 0.00040 U	< 0.00053 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3-20221209	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated	< 0.00010 U	< 0.00018 U	< 0.00023 U	< 0.00031 U	< 0.00010 U	< 0.00011 U	< 0.00010 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6-20221209	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated	< 0.00011 U	< 0.00020 U	< 0.00025 U	< 0.00033 U	< 0.00011 U	< 0.00012 U	< 0.00011 U
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273-20221214	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.000088 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000086 U	< 0.000096 U	< 0.000086 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14-20221214	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17-20221214	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20-20221214	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated	< 0.000073 U	< 0.00013 U	< 0.00017 U	< 0.00022 U	< 0.000071 U	< 0.000079 U	< 0.000071 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23-20221214	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00029 U	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	0.0038	< 0.00013 U	< 0.00014 U	< 0.00013 U	< 0.00021 U	< 0.00049 U	< 0.00013 U	< 0.00019 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.0030 U	< 0.00014 U	< 0.00015 U	< 0.00014 U	< 0.00022 U	< 0.00053 U	< 0.00014 U	< 0.00020 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.0024 U	< 0.00011 UT	< 0.00012 U	< 0.00011 UT	< 0.00017 UT	< 0.00041 UT	< 0.00011 UT	< 0.00016 UT
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.0052 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00090 UT	< 0.00024 U	< 0.00035 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	0.0084 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	0.0040 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated								
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated								
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45 PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45 SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45 SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10 PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10 SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B1063	062018 10:30 SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated								
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.004 U	< 0.00054 U	< 0.00055 U	< 0.00045 U	< 0.00036 U	< 0.00059 U	< 0.00041 U	< 0.00036 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	0.0053 J	< 0.00065 U	< 0.00066 U	< 0.00054 U	< 0.00043 U	< 0.00071 U	< 0.00049 U	< 0.00043 U
Rear Parking Lot	SSHS-B389	031116 09:30 SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated								
Rear Parking Lot	SSHS-MW-46	090216 08:45 SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B538	092316 08:45 SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B543	092316 08:45 SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B545	092316 08:40 SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B838	011018 09:40 SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B855	011218 12:30 SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B919	011718 12:00 SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B920	011718 12:00 SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated								
Rear Parking Lot	SSHS-B856	011818 12:20 SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B885	011818 12:20 SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B845	011918 10:00 SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B851	011918 10:00 SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B877	011918 10:00 SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B852	012018 09:00 SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B879	012018 09:00 SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B886	012018 09:00 SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B891	012018 09:00 SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B893	012018 09:00 SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B841	012418 09:30 SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B883	012418 09:30 SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B888	012418 09:30 SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30 PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30 SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B887	012518 09:00 SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10 PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10 SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1006	030518 07:30 SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B958	030618 09:15 PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated								

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.000086 U	< 0.000095 U	< 0.00026 U	< 0.00047 U	< 0.00021 U	< 0.00011 U	< 0.00022 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.000093 U	< 0.00010 U	< 0.00028 U	< 0.00051 U	< 0.00023 U	< 0.00012 U	< 0.00024 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.000073 UT	< 0.000080 UT	< 0.00021 U	< 0.00040 UT	< 0.00018 U	< 0.000091 UT	< 0.00019 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	< 0.00020 U	< 0.00041 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UT	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UT	< 0.0035 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0032 U	< 0.0019 U	< 0.0023 U	< 0.0031 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0033 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0034 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0035 U	< 0.0021 U	< 0.0025 U	< 0.0034 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated							
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated							
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated							
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated							
Rear Parking Lot	SSHS-B381	031016 09:45_PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B381	031016 09:45_SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B531	091716 09:10_PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B531	091716 09:10_SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B1063	062018 10:30_SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated							
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.00061 U	< 0.00057 U	< 0.0012 U	< 0.00047 U	< 0.00069 U	< 0.0003 U	< 0.0006 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.00073 U	< 0.00068 U	< 0.0015 U	< 0.00056 U	< 0.00082 U	< 0.00036 U	< 0.00072 U
Rear Parking Lot	SSHS-B389	031116 09:30_SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B538	092316 08:45_SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B919	011718 12:00_SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B920	011718 12:00_SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated							
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B885	011818 12:20_SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B845	011918 10:00_SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B851	011918 10:00_SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B877	011918 10:00_SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B852	012018 09:00_SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B891	012018 09:00_SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B883	012418 09:30_SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B948	012418 09:30_PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B948	012418 09:30_SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B887	012518 09:00_SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1006	030518 07:30_SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B958	030618 09:15_PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated							

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00056 U	< 0.000088 U	< 0.00017 U	< 0.00018 U	< 0.00018 U	< 0.00011 U	< 0.00010 U	< 0.00014 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.00060 U	< 0.000095 U	< 0.00018 U	< 0.00019 U	< 0.00019 U	< 0.00012 U	< 0.00011 U	< 0.00016 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.00047 U	< 0.000074 UT	< 0.00014 U	< 0.00015 UT	< 0.00015 UT	< 0.000093 UT	< 0.000085 U	< 0.00012 UT
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.0010 U	< 0.00016 U	< 0.00030 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0043 U	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0047 U	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated								
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated								
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45_PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45_SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10_PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10_SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B829	0112218 12:30_SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B1063	062018 10:30_SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated								
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00048 U	< 0.00052 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.00054 U	< 0.00069 U	< 0.00054 U	< 0.00064 U	< 0.00053 U	< 0.00051 U	< 0.00046 U	< 0.00049 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.00065 U	< 0.00083 U	< 0.00064 U	< 0.00077 U	< 0.00063 U	< 0.00061 U	< 0.00055 U	< 0.00059 U
Rear Parking Lot	SSHS-B389	031116 09:30_SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated								
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B538	092316 08:45_SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B919	011718 12:00_SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B920	011718 12:00_SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated								
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B885	011818 12:20_SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B845	011918 10:00_SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B851	011918 10:00_SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B877	011918 10:00_SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B852	012018 09:00_SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B891	012018 09:00_SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B883	012418 09:30_SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30_PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30_SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B887	012518 09:00_SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10_PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1006	030518 07:30_SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B958	030618 09:15_PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00011 U	< 0.00019 U	< 0.00017 U	< 0.00012 U	< 0.00021 U	< 0.00013 U	< 0.00013 U	< 0.000097 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.00012 U	< 0.00020 U	< 0.00019 U	< 0.00013 U	< 0.00022 U	< 0.00014 U	< 0.00014 U	< 0.00010 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.000093 U	< 0.00016 UT	< 0.00015 UT	< 0.00010 UT	< 0.00017 UT	< 0.00011 UT	< 0.00011 UT	< 0.000082 UT
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.00020 U	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.0022 U	< 0.0040 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.0023 U	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated								
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated								
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45 PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45 SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45 SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10 PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10 SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B1063	062018 10:30 SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated								
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.00072 U		< 0.00059 U	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.0005 U	< 0.00054 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.00068 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00048 U	< 0.00052 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.00082 U		< 0.00068 U	< 0.00057 U	< 0.00052 U	< 0.00065 U	< 0.00058 U	< 0.00062 U
Rear Parking Lot	SSHS-B389	031116 09:30 SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated								
Rear Parking Lot	SSHS-MW-46	090216 08:45 SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B538	092316 08:45 SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B543	092316 08:45 SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B545	092316 08:40 SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B838	011018 09:40 SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B855	011218 12:30 SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B919	011718 12:00 SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B920	011718 12:00 SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated								
Rear Parking Lot	SSHS-B856	011818 12:20 SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B885	011818 12:20 SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B845	011918 10:00 SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B851	011918 10:00 SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B877	011918 10:00 SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B852	012018 09:00 SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B879	012018 09:00 SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B886	012018 09:00 SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B891	012018 09:00 SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B893	012018 09:00 SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B841	012418 09:30 SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B883	012418 09:30 SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B888	012418 09:30 SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30 PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30 SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B887	012518 09:00 SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10 PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10 SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1006	030518 07:30 SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B958	030618 09:15 PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00084 U	< 0.00014 U	< 0.0021 U	< 0.00024 U	< 0.00018 U	< 0.00076 U	< 0.00025 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.00016 U	< 0.00090 U	< 0.00015 U	< 0.0023 U	< 0.00026 U	< 0.00019 U	< 0.00082 U	< 0.00027 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.00012 U	< 0.00070 UT	< 0.00012 UT	< 0.0018 U	< 0.00021 UT	< 0.00015 U	< 0.00064 UT	< 0.00021 U
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.00027 U	< 0.0015 U	< 0.00026 U	< 0.0039 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0070 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0075 UT	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.0020 U	< 0.0016 U	< 0.0026 U	< 0.0074 UT	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 UT	< 0.0025 U	< 0.0026 U	< 0.0019 UT	< 0.0015 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated								
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated								
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated								
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated								
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated								
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45_PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B381	031016 09:45_SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10_PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B531	091716 09:10_SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B1063	062018 10:30_SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated								
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00074 U	< 0.00055 U	< 0.00063 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.00086 U	< 0.00056 U	< 0.00055 U	< 0.00073 U	< 0.00058 U	< 0.00071 U	< 0.00052 U	< 0.0006 U
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.001 U	< 0.00067 U	< 0.00065 U	< 0.00087 U	< 0.0007 U	< 0.00085 U	< 0.00063 U	< 0.00072 U
Rear Parking Lot	SSHS-B389	0311116 09:30_SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated								
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B538	092316 08:45_SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B919	011718 12:00_SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B920	011718 12:00_SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated								
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B885	011818 12:20_SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B845	011918 10:00_SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B851	011918 10:00_SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B877	011918 10:00_SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B852	012018 09:00_SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B891	012018 09:00_SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B883	012418 09:30_SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30_PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B948	012418 09:30_SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B887	012518 09:00_SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10_PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1006	030518 07:30_SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B958	030618 09:15_PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.00014 U	< 0.00010 U	< 0.00015 UT	< 0.00011 U	< 0.000088 UT	< 0.00017 U	< 0.00011 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.00015 U	< 0.00011 U	< 0.00016 UT	< 0.00012 U	< 0.000095 UT	< 0.00019 U	< 0.00012 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.00011 UT	< 0.000088 U	< 0.00013 UT	< 0.000096 UT	< 0.000074 UT	< 0.00015 UT	< 0.000096 UT
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.00025 U	< 0.00019 U	< 0.00027 U	< 0.00021 U	< 0.00016 U	< 0.00032 U	< 0.00021 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0017 U	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0016 U	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated							
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated							
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated							
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated							
Rear Parking Lot	SSHS-B381	031016 09:45 PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B381	031016 09:45 SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B382	031016 09:45 SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B531	091716 09:10 PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B531	091716 09:10 SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B1063	062018 10:30 SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated							
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.00059 U	< 0.00061 U	< 0.00057 U	< 0.00061 U	< 0.00071 U	< 0.00074 U	< 0.00041 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00068 U	< 0.00071 U	< 0.00039 U
Rear Parking Lot	SSHS-B67	081514 01:15 SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.00068 U	< 0.00069 U	< 0.00066 U	< 0.0007 U	< 0.00081 U	< 0.00085 U	< 0.00047 U
Rear Parking Lot	SSHS-B389	031116 09:30 SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45 SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B538	092316 08:45 SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45 SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B537	092316 08:40 SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B542	092316 08:40 SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40 SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B838	011018 09:40 SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B855	011218 12:30 SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B919	011718 12:00 SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B920	011718 12:00 SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated							
Rear Parking Lot	SSHS-B856	011818 12:20 SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B885	011818 12:20 SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B845	011918 10:00 SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B851	011918 10:00 SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B877	011918 10:00 SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B852	012018 09:00 SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B879	012018 09:00 SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B886	012018 09:00 SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B891	012018 09:00 SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B893	012018 09:00 SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B841	012418 09:30 SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B883	012418 09:30 SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B888	012418 09:30 SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B948	012418 09:30 PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B948	012418 09:30 SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B887	012518 09:00 SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10 PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10 SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1006	030518 07:30 SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B958	030618 09:15 PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT-20221214	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated	< 0.000087 U	< 0.00016 U	< 0.00020 U	< 0.00027 U	< 0.000085 U	< 0.000095 U	< 0.000085 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT-20221214	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated	< 0.000094 U	< 0.00017 U	< 0.00021 U	< 0.00029 U	< 0.000092 U	< 0.00010 U	< 0.000092 U
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2-20221214	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated	< 0.000073 UT	< 0.00013 UT	< 0.00017 U	< 0.00022 U	< 0.000072 UT	< 0.000080 UT	< 0.000072 UT
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3-20221214	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated	< 0.00016 U	0.00033 J	< 0.00037 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4-20230530	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6-20230530	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0042 UT	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7-20230530	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 UT	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A-20230601	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.00094 U	< 0.0015 U	< 0.0040 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14-20230601	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0071 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19-20230601	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20-20230601	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24-20230601	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 0.00099 U	< 0.0016 U	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32-20230602	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 0.0011 U	< 0.0017 U	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33-20230602	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 0.0010 U	< 0.0016 U	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13-20231130	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17-20231130	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21-20231130	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated							
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22-20231130	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated							
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29-20231208	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated							
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31-20231208	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32-20231208	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated							
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34-20231214	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated							
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35-20231214	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated							
Rear Parking Lot	SSHS-B381	031016 09:45_PS-FD-22	PS-FD-22	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B381	031016 09:45_SSHS-B381-SUB-0-2	SSHS-B381-SUB-0-2	3/9/2016	852.40	852.92	0.52	-	0 - 2 ft	0.52-2.52 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-0-2	SSHS-B382-SUB-0-2	3/9/2016	850.28	850.38	0.10	-	0 - 2 ft	0.1-2.1 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B531	091716 09:10_PS-FD-28	PS-FD-28	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B531	091716 09:10_SSHS-B531-SUB-0-2	SSHS-B531-SUB-0-2	9/16/2016	852.31	852.87	0.57	-	0 - 2 ft	0.57-2.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-0-2	SSHS-B829-SUB-0-2	1/10/2018	852.37	852.65	0.28	-	0 - 2 ft	0.28-2.28 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B1063	062018 10:30_SSHS-B1063-SUB-0-2	SSHS-B1063-SUB-0-2	6/19/2018	852.50	852.65	0.15	-	0 - 2 ft	0.15-2.15 ft	200-43950-2	Not Excavated							
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-10-12 (11)	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated	< 0.0007 U	< 0.00055 U	< 0.00077 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-10-12 (11)	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated	< 0.00067 U	< 0.00053 U	< 0.00074 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
Rear Parking Lot	SSHS-B67	081514 01:15_SSHS-B67-10-12 (11)	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated	< 0.0008 U	< 0.00063 U	< 0.00089 U	< 0.00045 U	< 0.0014 U	< 0.00075 U	
Rear Parking Lot	SSHS-B389	031116 09:30_SSHS-B389-SUB-10-12	SSHS-B389-SUB-10-12	3/10/2016	851.50	851.68	0.18	-	10 - 12 ft	10.18-12.18 ft	180-52921-2	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-10-12	SSHS-MW46-SUB-10-12	8/30/2016	850.92	850.97	0.05	-	10 - 12 ft	10.05-12.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B538	092316 08:45_SSHS-B538-SUB-10-12	SSHS-B538-SUB-10-12	9/21/2016	851.14	851.09	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-10-12	SSHS-B543-SUB-10-12	9/21/2016	851.17	851.32	0.15	-	10 - 12 ft	10.15-12.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-10-12	SSHS-B537-SUB-10-12	9/22/2016	850.44	850.26	-0.18	-	10 - 12 ft	9.82-11.82 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-10-12	SSHS-B542-SUB-10-12	9/22/2016	850.47	850.35	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-10-12	SSHS-B545-SUB-10-12	9/22/2016	850.94	850.75	-0.19	-	10 - 12 ft	9.81-11.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-10-12	SSHS-B838-SUB-10-12	1/9/2018	852.00	852.24	0.24	-	10 - 12 ft	10.24-12.24 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-10-12	SSHS-B855-SUB-10-12	1/10/2018	851.40	851.77	0.37	-	10 - 12 ft	10.37-12.37 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-10-12	SSHS-B889-SUB-10-12	1/12/2018	851.80	852.52	0.72	-	10 - 12 ft	10.72-12.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B919	011718 12:00_SSHS-B919-SUB-10-12	SSHS-B919-SUB-10-12	1/12/2018	851.30	851.09	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B920	011718 12:00_SSHS-B920-SUB-10-12	SSHS-B920-SUB-10-12	1/16/2018	850.90	850.66	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-74203-1	Not Excavated							
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-10-12	SSHS-B856-SUB-10-12	1/17/2018	850.56	850.62	0.06	-	10 - 12 ft	10.06-12.06 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B885	011818 12:20_SSHS-B885-SUB-10-12	SSHS-B885-SUB-10-12	1/17/2018	850.40	850.24	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-10-12	SSHS-B839-SUB-10-12	1/18/2018	850.25	850.52	0.27	-	10 - 12 ft	10.27-12.27 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B845	011918 10:00_SSHS-B845-SUB-10-12	SSHS-B845-SUB-10-12	1/18/2018	851.50	851.17	-0.33	-	10 - 12 ft	9.67-11.67 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B851	011918 10:00_SSHS-B851-SUB-10-12	SSHS-B851-SUB-10-12	1/18/2018	851.29	851.55	0.26	-	10 - 12 ft	10.26-12.26 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B877	011918 10:00_SSHS-B877-SUB-10-12	SSHS-B877-SUB-10-12	1/18/2018	851.10	851.42	0.32	-	10 - 12 ft	10.32-12.32 ft	180-74307-3	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-10-12	SSHS-B843-SUB-10-12	1/19/2018	851.40	851.34	-0.06	-	10 - 12 ft	9.94-11.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B852	012018 09:00_SSHS-B852-SUB-10-12	SSHS-B852-SUB-10-12	1/19/2018	851.20	851.36	0.16	-	10 - 12 ft	10.16-12.16 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-10-12	SSHS-B879-SUB-10-12	1/19/2018	851.30	851.82	0.52	-	10 - 12 ft	10.52-12.52 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-10-12	SSHS-B886-SUB-10-12	1/19/2018	850.37	850.66	0.29	-	10 - 12 ft	10.29-12.29 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B891	012018 09:00_SSHS-B891-SUB-10-12	SSHS-B891-SUB-10-12	1/19/2018	851.10	851.65	0.55	-	10 - 12 ft	10.55-12.55 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-10-12	SSHS-B893-SUB-10-12	1/19/2018	850.90	851.38	0.48	-	10 - 12 ft	10.48-12.48 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-10-12	SSHS-B841-SUB-10-12	1/20/2018	850.05	849.85	-0.20	-	10 - 12 ft	9.80-11.80 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-10-12	SSHS-B878-SUB-10-12	1/20/2018	851.47	851.87	0.40	-	10 - 12 ft	10.40-12.40 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B883	012418 09:30_SSHS-B883-SUB-10-12	SSHS-B883-SUB-10-12	1/20/2018	851.96	852.10	0.14	-	10 - 12 ft	10.14-12.14 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-10-12	SSHS-B842-SUB-10-12	1/22/2018	851.80	851.59	-0.21	-	10 - 12 ft	9.79-11.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-10-12	SSHS-B888-SUB-10-12	1/22/2018	849.80	849.67	-0.13	-	10 - 12 ft	9.87-11.87 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-10-12	SSHS-B850-SUB-10-12	1/23/2018	850.33	850.69	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-10-12	SSHS-B890-SUB-10-12	1/23/2018	851.90	852.26	0.36	-	10 - 12 ft	10.36-12.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B948	012418 09:30_PS-FD-39	PS-FD-39	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B948	012418 09:30_SSHS-B948-SUB-10-12	SSHS-B948-SUB-10-12	1/23/2018	851.70	851.83	0.13	-	10 - 12 ft	10.13-12.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B887	012518 09:00_SSHS-B887-SUB-10-12	SSHS-B887-SUB-10-12	1/24/2018	850.60	850.52	-0.08	-	10 - 12 ft	9.92-11.92 ft	180-74436-1	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-10-12	SSHS-B981-SUB-10-12	2/28/2018	851.85	852.05	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-10-12	SSHS-B973-SUB-10-12	3/1/2018	852.19	852.39	0.20	-	10 - 12 ft	10.20-12.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-10-12	SSHS-B977-SUB-10-12	3/1/2018	851.96	852.03	0.07	-	10 - 12 ft	10.07-12.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_PS-FD-4	PS-FD-4	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-10-12	SSHS-B993-SUB-10-12	3/1/2018	851.75	851.76	0.01	-	10 - 12 ft	10.01-12.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1006	030518 07:30_SSHS-B1006-SUB-10-12	SSHS-B1006-SUB-10-12	3/3/2018	851.67	851.88	0.21	-	10 - 12 ft	10.21-12.21 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B958	030618 09:15_PS-FD-13	PS-FD-13	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	0.0060 J	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.0036 UJ	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 UJ	< 0.0037 U	< 0.0019 UT
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	0.03	< 0.0034 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 UT	< 0.0047 U	< 0.0024 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated							
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated							
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated							
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023B-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated						
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 UT	< 0.0025 U	< 0.0033 UJ
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 UJ	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.0034 U	< 0.0029 U	< 0.0034 UT	< 0.0039 U	< 0.0046 U	< 0.0039 U	< 0.0038 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated						
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated						
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated						
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated						
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated						
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated						
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated						
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated						
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated						
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated						
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated						
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated						
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated						
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated						
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated						
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023B-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated						
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated						

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated								
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.0046 U	< 0.0014 UJ	< 0.0026 UT	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 UT	< 0.0016 U	< 0.0029 UT	< 0.0014 UT	< 0.0015 U	< 0.0013 U
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.0053 U	< 0.0030 U	< 0.0047 U	< 0.0033 U	< 0.0036 U	< 0.0032 U	< 0.0030 U	< 0.0035 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated								
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated								
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated								
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023B-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated								
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.0023 U	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.0021 UT	< 0.0038 UT	< 0.0014 UT	< 0.0016 UT	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 UT
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.0045 U	< 0.0048 U	< 0.0029 U	< 0.0036 U	< 0.0028 U	< 0.0026 U	< 0.0026 U	< 0.0044 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated							
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated							
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated							
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023B-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated							

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated								
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 UJ	< 0.0015 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.0019 U	< 0.0015 UJ	< 0.0024 UT	< 0.0069 U	< 0.0023 UT	< 0.0024 UJ	< 0.0017 UJ	< 0.0014 U
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.0054 U	< 0.0049 U	< 0.0044 U	< 0.0086 U	< 0.0041 U	< 0.011 U	< 0.0034 U	< 0.0034 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated								
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated								
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated								
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated								
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated								
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated								
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023B-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated								
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated								
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated						
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.0014 U	< 0.0014 UJ	< 0.0019 UT	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 UT
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.0039 U	< 0.0044 U	< 0.0044 U	< 0.0044 U	< 0.0032 U	< 0.0030 U	< 0.0020 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated						
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated						
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated						
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated						
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated						
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated						
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated						
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated						
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated						
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated						
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated						
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated						
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated						
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated						
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated						
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023B-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated						
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated						
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated						

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B958	030618 09:15_SSHS-B958-SUB-10-12	SSHS-B958-SUB-10-12	3/4/2018	851.26	851.68	0.42	-	10 - 12 ft	10.42-12.42 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B979	030618 09:15_PS-FD-12	PS-FD-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B979	030618 09:15_SSHS-B979-SUB-10-12	SSHS-B979-SUB-10-12	3/4/2018	849.85	850.02	0.17	-	10 - 12 ft	10.17-12.17 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-10-12	SSHS-B992-SUB-10-12	3/4/2018	852.95	853.53	0.58	-	10 - 12 ft	10.58-12.58 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_PS-FD-17	PS-FD-17	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-10-12	SSHS-B978-SUB-10-12	3/5/2018	852.09	852.56	0.47	-	10 - 12 ft	10.47-12.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-10-12	SSHS-B989-SUB-10-12	3/5/2018	853.10	853.59	0.49	-	10 - 12 ft	10.49-12.49 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-10-12	SSHS-B1010-SUB-10-12	4/24/2018	851.50	852.08	0.58	-	10 - 12 ft	10.58-12.58 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1016	042518 09:00_SSHS-B1016-SUB-10-12	SSHS-B1016-SUB-10-12	4/24/2018	849.90	849.78	-0.12	-	10 - 12 ft	9.88-11.88 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-10-12	SSHS-B1017-SUB-10-12	4/24/2018	853.03	853.47	0.44	-	10 - 12 ft	10.44-12.44 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-10-12	SSHS-B1018-SUB-10-12	4/24/2018	852.50	852.75	0.25	-	10 - 12 ft	10.25-12.25 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1160	070318 09:15_SSHS-B1160-SUB-10-12	SSHS-B1160-SUB-10-12	6/30/2018	851.49	851.07	-0.42	-	10 - 12 ft	9.58-11.58 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1068	070318 09:15_SSHS-B1068-SUB-10-12	SSHS-B1068-SUB-10-12	7/1/2018	850.17	850.19	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1219	070318 09:15_SSHS-B1219-SUB-10-12	SSHS-B1219-SUB-10-12	7/1/2018	850.00	849.86	-0.14	-	10 - 12 ft	9.86-11.86 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1251	070318 09:15_SSHS-B1251-SUB-10-12	SSHS-B1251-SUB-10-12	7/1/2018	849.70	849.77	0.07	-	10 - 12 ft	10.07-12.07 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1252	070318 09:15_SSHS-B1252-SUB-10-12	SSHS-B1252-SUB-10-12	7/1/2018	849.20	848.96	-0.24	-	10 - 12 ft	9.76-11.76 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-10-12	SSHS-B1254-SUB-10-12	7/1/2018	849.77	849.85	0.08	-	10 - 12 ft	10.08-12.08 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1086	070718 09:30_SSHS-B1086-SUB-10-12	SSHS-B1086-SUB-10-12	7/6/2018	850.69	851.13	0.44	-	10 - 12 ft	10.44-12.44 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1122	070718 09:30_SSHS-B1122-SUB-10-12	SSHS-B1122-SUB-10-12	7/6/2018	851.50	851.52	0.02	-	10 - 12 ft	10.02-12.02 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-10-12	SSHS-B1198-SUB-10-12	7/6/2018	851.80	852.61	0.81	-	10 - 12 ft	10.81-12.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1247	070718 09:30_SSHS-B1247-SUB-10-12	SSHS-B1247-SUB-10-12	7/6/2018	851.72	852.30	0.58	-	10 - 12 ft	10.58-12.58 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12	SSHS-B1249-SUB-10-12	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1249	070718 09:30_SSHS-B1249-SUB-10-12-DUP	SSHS-B1249-SUB-10-12-DUP	7/6/2018	851.72	852.01	0.29	-	10 - 12 ft	10.29-12.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-SW-011	071218 09:15_SW-011-10-12	SW-011-10-12	7/11/2018	-	853.72	-	843.30	10 - 12 ft	10.42 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-BSW-001	071318 09:15_EBSW-10-12	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1204	073118 08:50_SSHS-B1204-SUB-10-12	SSHS-B1204-SUB-10-12	7/28/2018	850.73	850.43	-0.30	-	10 - 12 ft	9.70-11.70 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1299	080718 09:00_SSHS-B1299-SUB-10-12	SSHS-B1299-SUB-10-12	8/4/2018	-	851.91	-	841.70	10 - 12 ft	10.21 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-SS-07_8_20	082218 09:15_SS-07 (10-12) 20180820	SS-07 (10-12) 20180820	8/20/2018	-	849.48	-	838.50	10 - 12 ft	10.98 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-12_8_20	082218 09:15_SS-12 (10-12) 20180820	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-14_8_20	082218 09:15_SS-14 (10-12) 20180820	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-16_8_20	082218 09:15_SS-16 (10-12) 20180820	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1502	082218 09:15_SSHS-B1502 (10-12) 20180821	SSHS-B1502 (10-12) 20180821	8/21/2018	-	850.00	-	-	10 - 12 ft	9.71-11.71 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3840	072421 09:00_SSHS-B3840-SUB-10-12	SSHS-B3840	7/23/2021	847.79	847.79	0.00	-	10 - 12 ft	10 - 12 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12-20230118	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 0.0010 UJ	0.0020 J	< 0.0043 UT	< 0.0037 UT	< 0.0018 U	< 0.0021 U	< 0.0074 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-10-12-20230130	STI-OS-SB-4A-SUB-10-12	1/30/2023	848.46	848.46	0.00	-	10 - 12 ft	10-12 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12-20230209	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 0.00093 U	< 0.0015 UT	< 0.0039 U	< 0.0034 U	< 0.0017 UT	< 0.0019 UT	< 0.0067 UT
Rear Parking Lot	SSHS-C-E-P-1	080718 09:00_CEP-1	CEP-1	8/4/2018	-	851.89	-	841.10	10.1 - 10.1 ft	10.79 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838-20240812	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated	< 0.0031 U	< 0.0032 U	< 0.0048 U	< 0.0042 U	< 0.0046 U	< 0.0040 U	< 0.0084 U
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-12-14	SSHS-MW46-SUB-12-14	8/30/2016	850.92	850.97	0.05	-	12 - 14 ft	12.05-14.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B537	092316 08:40_SSHS-B537-SUB-12-14	SSHS-B537-SUB-12-14	9/22/2016	850.44	850.26	-0.18	-	12 - 14 ft	11.82-13.82 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B542	092316 08:40_SSHS-B542-SUB-12-14	SSHS-B542-SUB-12-14	9/22/2016	850.47	850.35	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B838	011018 09:40_SSHS-B838-SUB-12-14	SSHS-B838-SUB-12-14	1/9/2018	852.00	852.24	0.24	-	12 - 14 ft	12.24-14.24 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B855	011218 12:30_SSHS-B855-SUB-12-14	SSHS-B855-SUB-12-14	1/10/2018	851.40	851.77	0.37	-	12 - 14 ft	12.37-14.37 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-12-14	SSHS-B889-SUB-12-14	1/12/2018	851.80	852.52	0.72	-	12 - 14 ft	12.72-14.72 ft	180-74207-2	Not Excavated							
Rear Parking Lot	SSHS-B856	011818 12:20_SSHS-B856-SUB-12-14	SSHS-B856-SUB-12-14	1/17/2018	850.56	850.62	0.06	-	12 - 14 ft	12.06-14.06 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B892	011818 12:20_SSHS-B892-SUB-12-14	SSHS-B892-SUB-12-14	1/17/2018	850.89	851.05	0.16	-	12 - 14 ft	12.16-14.16 ft	180-74241-1	Not Excavated							
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-12-14	SSHS-B839-SUB-12-14	1/18/2018	850.25	850.52	0.27	-	12 - 14 ft	12.27-14.27 ft	180-74307-3	Not Excavated							
Rear Parking Lot	SSHS-B917	011918 10:00_SSHS-B917-SUB-12-14	SSHS-B917-SUB-12-14	1/18/2018	850.56	851.07	0.51	-	12 - 14 ft	12.51-14.51 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B879	012018 09:00_SSHS-B879-SUB-12-14	SSHS-B879-SUB-12-14	1/19/2018	851.30	851.82	0.52	-	12 - 14 ft	12.52-14.52 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B886	012018 09:00_SSHS-B886-SUB-12-14	SSHS-B886-SUB-12-14	1/19/2018	850.37	850.66	0.29	-	12 - 14 ft	12.29-14.29 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B893	012018 09:00_SSHS-B893-SUB-12-14	SSHS-B893-SUB-12-14	1/19/2018	850.90	851.38	0.48	-	12 - 14 ft	12.48-14.48 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B840	012418 09:30_SSHS-B840-SUB-12-14	SSHS-B840-SUB-12-14	1/20/2018	849.70	849.74	0.04	-	12 - 14 ft	12.04-14.04 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B841	012418 09:30_SSHS-B841-SUB-12-14	SSHS-B841-SUB-12-14	1/20/2018	850.05	849.85	-0.20	-	12 - 14 ft	11.80-13.80 ft	180-74390-3	Not Excavated							
Rear Parking Lot	SSHS-B888	012418 09:30_SSHS-B888-SUB-12-14	SSHS-B888-SUB-12-14	1/22/2018	849.80	849.67	-0.13	-	12 - 14 ft	11.87-13.87 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-12-14	SSHS-B957-SUB-12-14	2/28/2018	852.80	852.80	0.00	-	12 - 14 ft	12-14 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-12-14	SSHS-B981-SUB-12-14	2/28/2018	851.85	852.05	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-12-14	SSHS-B973-SUB-12-14	3/1/2018	852.19	852.39	0.20	-	12 - 14 ft	12.20-14.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-12-14	SSHS-B977-SUB-12-14	3/1/2018	851.96	852.03	0.07	-	12 - 14 ft	12.07-14.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B993	030218 09:10_SSHS-B993-SUB-12-14	SSHS-B993-SUB-12-14	3/1/2018	851.75	851.76	0.01	-	12 - 14 ft	12.01-14.01 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1007	030518 07:30_PS-FD-7	PS-FD-7	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B1007	030518 07:30_SSHS-B1007-SUB-12-14	SSHS-B1007-SUB-12-14	3/3/2018	851.90	852.28	0.38	-	12 - 14 ft	12.38-14.38 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B1008	030518 07:30_SSHS-B1008-SUB-12-14	SSHS-B1008-SUB-12-14	3/3/2018	852.10	852.13	0.03	-	12 - 14 ft	12.03-14.03 ft	180-75511-1	Not Excavated							
Rear Parking Lot	SSHS-B953	030618 09:15_SSHS-B953-SUB-12-14	SSHS-B953-SUB-12-14	3/4/2018	849.70	849.58	-0.12	-	12 - 14 ft	11.88-13.88 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B980	030618 09:15_SSHS-B980-SUB-12-14	SSHS-B980-SUB-12-14	3/4/2018	849.90	849.89	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-12-14	SSHS-B978-SUB-12-14	3/5/2018	852.09	852.56	0.47	-	12 - 14 ft	12.47-14.47 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B1010	042518 09:00_SSHS-B1010-SUB-12-14	SSHS-B1010-SUB-12-14	4/24/2018	851.50	852.08	0.58	-	12 - 14 ft	12.58-14.58 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1015	042618 08:40_SSHS-B1015-SUB-12-14	SSHS-B1015-SUB-12-14	4/25/2018	853.20	853.64	0.44	-	12 - 14 ft	12.44-14.44 ft	180-77123-3	Not Excavated							
Rear Parking Lot	SSHS-B1023b	042718 08:50_SSHS-B1023b-SUB-12-14	SSHS-B1023b-SUB-12-14	4/26/2018	853.90	853.73	-0.17	-	12 - 14 ft	11.83-13.83 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-3	Not Excavated							
Rear Parking Lot	SSHS-B1254	070318 09:15_SSHS-B1254-SUB-12-14	SSHS-B1254-SUB-12-14	7/1/2018	849.77	849.85	0.08	-	12 - 14 ft	12.08-14.08 ft	180-79440-4	Not Excavated							
Rear Parking Lot	SSHS-B1205	070718 09:30_SSHS-B1205-SUB-12-14	SSHS-B1205-SUB-12-14	7/5/2018	851.11	851.51	0.40	-	12 - 14 ft	12.40-14.40 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1104	070718 09:30_SSHS-B1104-SUB-12-14	SSHS-B1104-SUB-12-14	7/6/2018	851.32	852.00	0.68	-	12 - 14 ft	12.68-14.68 ft	180-79550-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	0.025	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 U	< 0.0021 UJ	< 0.0037 U	< 0.0019 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.0049 U	< 0.00067 U	< 0.00068 U	< 0.00055 U	< 0.00044 U	< 0.00073 U	< 0.0005 U	< 0.00044 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B1009	042518 09:00_SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1026	042518 09:00_SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1025	042718 08:50_SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1091	070718 09:30_SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1094	070718 09:30_SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 UT
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated								
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B376	030916 11:30_SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30_PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30_SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B554	091716 09:10_SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B869	011018 09:40_SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated								
Rear Parking Lot	SSHS-B854	011018 09:40_SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40_PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B873	011218 12:30_SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B910	011218 12:30_SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B926	011918 10:00_SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B924	012018 09:00_SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B951	030218 09:10_SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B950	030618 09:15_SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1073	062618 10:05_SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00_PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00_SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1202	063018 10:00_SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-SW-003	071218 09:15_SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-B1394	072418 08:50_B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-SS-04_8_20	082218 09:15_SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.0039 UJ	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UJ	< 0.0039 U	< 0.0020 UT
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30_E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30_E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-W8-1	080118 09:00_W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-1	073118 08:50_G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W7-1	080118 09:00_W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-WWS_7_21	072418 08:50_WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-1	073118 08:50_G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.01 U	< 0.0014 U	< 0.0014 U	< 0.0012 U	< 0.00092 U	< 0.0015 U	< 0.0011 U	< 0.00093 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0073 U	< 0.00098 U	< 0.001 U	< 0.00082 U	< 0.00064 U	< 0.0011 U	< 0.00074 U	< 0.00065 U
Rear Parking Lot	SSHS-EN5-1	073118 08:50_E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-1	073118 08:50_G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30_E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30_E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-EN4-1	073118 08:50_E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30_E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30_E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 UJ	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.0030 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UJ	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-B1009	042518 09:00_SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1026	042518 09:00_SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1025	042718 08:50_SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1091	070718 09:30_SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1094	070718 09:30_SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated							
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated							
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated							
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B376	030916 11:30_SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30_PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30_SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B554	091716 09:10_SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B869	011018 09:40_SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated							
Rear Parking Lot	SSHS-B854	011018 09:40_SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40_PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B873	011218 12:30_SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B910	011218 12:30_SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B926	011918 10:00_SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B924	012018 09:00_SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B951	030218 09:10_SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B950	030618 09:15_SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1073	062618 10:05_SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated							
Rear Parking Lot	SSHS-B1074	063018 10:00_PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1074	063018 10:00_SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1202	063018 10:00_SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-SW-003	071218 09:15_SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-B1394	072418 08:50_B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-SS-04_8_20	082218 09:15_SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30_E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30_E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-W8-1	080118 09:00_W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-1	073118 08:50_G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W7-1	080118 09:00_W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-WWS_7_21	072418 08:50_WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-1	073118 08:50_G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0016 U	< 0.0015 U	< 0.0032 U	< 0.0012 U	< 0.0018 U	< 0.00077 U	< 0.0016 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0011 U	< 0.001 U	< 0.0023 U	< 0.00085 U	< 0.0012 U	< 0.00054 U	< 0.0011 U
Rear Parking Lot	SSHS-EN5-1	073118 08:50_E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-GS4-1	073118 08:50_G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30_E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30_E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-EN4-1	073118 08:50_E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30_E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30_E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.0042 U	< 0.0013 U	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.0006 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B1009	042518 09:00_SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1026	042518 09:00_SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1025	042718 08:50_SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1091	070718 09:30_SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1094	070718 09:30_SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0050 U	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 UT	< 0.0017 U	< 0.0018 U	< 0.0016 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated								
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B376	030916 11:30_SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30_PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30_SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B554	091716 09:10_SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B869	011018 09:40_SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated								
Rear Parking Lot	SSHS-B854	011018 09:40_SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40_PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B873	011218 12:30_SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B910	011218 12:30_SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B926	011918 10:00_SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B924	012018 09:00_SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B951	030218 09:10_SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B950	030618 09:15_SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1073	062618 10:05_SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00_PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00_SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1202	063018 10:00_SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-SW-003	071218 09:15_SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-B1394	072418 08:50_B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-SS-04_8_20	082218 09:15_SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0030 UT	< 0.0015 UT	< 0.0016 U	< 0.0014 U
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30_E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30_E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-W8-1	080118 09:00_W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-1	073118 08:50_G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W7-1	080118 09:00_W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-WWS_7_21	072418 08:50_WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-1	073118 08:50_G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0014 U	< 0.0017 U	< 0.0014 U	< 0.0013 U	< 0.0012 U	< 0.0013 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.00098 U	< 0.0013 U	< 0.00097 U	< 0.0012 U	< 0.00095 U	< 0.00093 U	< 0.00084 U	< 0.00089 U
Rear Parking Lot	SSHS-EN5-1	073118 08:50_E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-1	073118 08:50_G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30_E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30_E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-EN4-1	073118 08:50_E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30_E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30_E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.0021 U	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0023 UT	< 0.0042 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 UT
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.00084 U		< 0.00069 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U	< 0.00063 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B1009	042518 09:00_SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1026	042518 09:00_SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1025	042718 08:50_SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1091	070718 09:30_SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1094	070718 09:30_SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0023 UT	< 0.0041 UT	< 0.0015 UT	< 0.0018 UT	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0025 U	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated								
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B376	030916 11:30_SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30_PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30_SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B554	091716 09:10_SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B869	011018 09:40_SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated								
Rear Parking Lot	SSHS-B854	011018 09:40_SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40_PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B873	011218 12:30_SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B910	011218 12:30_SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B926	011918 10:00_SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B924	012018 09:00_SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B951	030218 09:10_SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B950	030618 09:15_SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1073	062618 10:05_SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00_PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00_SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1202	063018 10:00_SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-SW-003	071218 09:15_SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-B1394	072418 08:50_B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-SS-04_8_20	082218 09:15_SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.0022 UT	< 0.0040 UT	< 0.0015 UT	< 0.0017 UT	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 UT
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30_E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30_E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-W8-1	080118 09:00_W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-1	073118 08:50_G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W7-1	080118 09:00_W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-WWS_7_21	072418 08:50_WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-1	073118 08:50_G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0018 U		< 0.0015 U	< 0.0012 U	< 0.0011 U	< 0.0014 U	< 0.0012 U	< 0.0013 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0012 U		< 0.001 U	< 0.00087 U	< 0.00079 U	< 0.00099 U	< 0.00087 U	< 0.00093 U
Rear Parking Lot	SSHS-EN5-1	073118 08:50_E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-1	073118 08:50_G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30_E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30_E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-EN4-1	073118 08:50_E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30_E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30_E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B1198	070718 09:30 SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1303	080718 09:00 SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0069 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0021 U	< 0.0016 UJ	< 0.0027 UT	< 0.0076 U	< 0.0025 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00071 U	< 0.00087 U	< 0.00064 U	< 0.00074 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B1009	042518 09:00 SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1026	042518 09:00 SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1025	042718 08:50 SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1091	070718 09:30 SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30 SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1092	070718 09:30 SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30 SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1093	070718 09:30 SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1094	070718 09:30 SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0075 U	< 0.0024 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0022 U	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated								
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated								
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B376	030916 11:30 SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30 PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B382	031016 09:45 SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B554	091716 09:10 SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated								
Rear Parking Lot	SSHS-B869	011018 09:40 SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated								
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B926	011918 10:00 SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B924	012018 09:00 SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B951	030218 09:10 SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B950	030618 09:15 SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1073	062618 10:05 SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00 PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1074	063018 10:00 SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-SW-003	071218 09:15 SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-B1394	072418 08:50 B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-SS-04 8 20	082218 09:15 SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0073 U	< 0.0024 UT	< 0.0025 UJ	< 0.0018 UJ	< 0.0015 UT
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30 E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30 E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-W8-1	080118 09:00 W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-1	073118 08:50 G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W3-1	080118 09:00 W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W7-1	080118 09:00 W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-WWS 7 21	072418 08:50 WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-1	073118 08:50 G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-B101	081514 01:15 DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.0014 U	< 0.0019 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0016 U
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0016 U	< 0.001 U	< 0.00099 U	< 0.0013 U	< 0.0011 U	< 0.0013 U	< 0.00095 U	< 0.0011 U
Rear Parking Lot	SSHS-EN5-1	073118 08:50 E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-1	073118 08:50 G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30 E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30 E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-EN4-1	073118 08:50 E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W10-1	080118 09:00 W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30 E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30 E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.0014 U	< 0.0014 UJ	< 0.0019 UT	< 0.0013 U	< 0.0026 U	< 0.0024 U	< 0.0016 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 UT
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U	< 0.00048 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-B1009	042518 09:00_SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1026	042518 09:00_SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1025	042718 08:50_SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1091	070718 09:30_SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1094	070718 09:30_SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated							
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0017 U	< 0.0017 UJ	< 0.0022 UT	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated							
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated							
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B376	030916 11:30_SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30_PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30_SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B554	091716 09:10_SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B869	011018 09:40_SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated							
Rear Parking Lot	SSHS-B854	011018 09:40_SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40_PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B873	011218 12:30_SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B910	011218 12:30_SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B926	011918 10:00_SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B924	012018 09:00_SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B951	030218 09:10_SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B950	030618 09:15_SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1073	062618 10:05_SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated							
Rear Parking Lot	SSHS-B1074	063018 10:00_PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1074	063018 10:00_SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1202	063018 10:00_SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-SW-003	071218 09:15_SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-B1394	072418 08:50_B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-SS-04_8_20	082218 09:15_SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 UT
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30_E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30_E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-W8-1	080118 09:00_W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-1	073118 08:50_G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W7-1	080118 09:00_W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-WWS_7_21	072418 08:50_WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-1	073118 08:50_G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0014 U	< 0.0015 U	< 0.0018 U	< 0.0018 U	< 0.001 U
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.001 U	< 0.001 U	< 0.00099 U	< 0.0011 U	< 0.0012 U	< 0.0013 U	< 0.00071 U
Rear Parking Lot	SSHS-EN5-1	073118 08:50_E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-GS4-1	073118 08:50_G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30_E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30_E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-EN4-1	073118 08:50_E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30_E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30_E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-12-14	SSHS-B1198-SUB-12-14	7/6/2018	851.80	852.61	0.81	-	12 - 14 ft	12.81-14.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1303	080718 09:00_SSHS-B1303-SUB-12-14	SSHS-B1303-SUB-12-14	8/4/2018	-	851.94	-	839.70	12 - 14 ft	12.24 ft	180-80511-1	Not Excavated							
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14-20230118	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 0.00093 UJ	< 0.0015 UT	< 0.0039 UJ	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0067 U
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-12-14-20230130	STI-OS-SB-4A-SUB-12-14	1/30/2023	848.46	848.46	0.00	-	12 - 14 ft	12-14 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14-20230209	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 0.0010 U	< 0.0016 UT	< 0.0043 U	< 0.0037 U	< 0.0018 UT	< 0.0021 UT	< 0.0074 UT
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-12-15.5R (15)	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-838-836-20241207	SSHS-SPA6-B65A-ELEV-838-836	12/7/2024	850.12	850.12	0.00	-	12.12-14.12 ft	12.12-14.12 ft	1801838841	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-838-836-20240812	SSHS-SPA4-B5502-ELEV-838-836	8/12/2024	850.65	850.65	0.00	-	12.65-14.65 ft	12.65-14.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA4-B5504	SSHS-SPA4-B5504-ELEV-838-836-20240812	SSHS-SPA4-B5504-ELEV-838-836	8/12/2024	851.63	851.63	0.00	-	13.63-15.63 ft	13.63-15.63 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-B1009	042518 09:00_SSHS-B1009-SUB-14-16	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1026	042518 09:00_SSHS-B1026-SUB-14-16	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1025	042718 08:50_SSHS-B1025-SUB-14-16	SSHS-B1025-SUB-14-16	4/26/2018	852.50	852.33	-0.17	-	14 - 16 ft	13.83-15.83 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1091	070718 09:30_SSHS-B1091-SUB-14-16	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1092	070718 09:30_SSHS-B1092-SUB-14-16-DUP	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1093	070718 09:30_SSHS-B1093-SUB-14-16-DUP	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1094	070718 09:30_SSHS-B1094-SUB-14-16	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated							
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-14-16-20230130	STI-OS-SB-4A-SUB-14-16	1/30/2023	848.46	848.46	0.00	-	14 - 16 ft	14-16 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16-20230209	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 0.0010 U	< 0.0016 UT	< 0.0042 U	< 0.0036 U	< 0.0018 UT	< 0.0020 UT	< 0.0073 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16-20230212	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 0.0011 UJ	< 0.0017 UT	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated							
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated							
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832-20240812	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-2-4	SSHS-B108-SUB-2-4	7/22/2015	849.57	849.70	0.13	-	2 - 4 ft	2.13-4.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-2-4	SSHS-B133-SUB-2-4	8/3/2015	852.64	852.58	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-2-4	SSHS-B148-SUB-2-4	8/3/2015	852.19	852.56	0.37	-	2 - 4 ft	2.37-4.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B376	030916 11:30_SSHS-B376-SUB-2-4	SSHS-B376-SUB-2-4	3/8/2016	851.45	851.32	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30_PS-FD-20	PS-FD-20	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30_SSHS-B386-SUB-2-4	SSHS-B386-SUB-2-4	3/8/2016	852.82	853.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B382	031016 09:45_SSHS-B382-SUB-2-4	SSHS-B382-SUB-2-4	3/9/2016	850.28	850.38	0.10	-	2 - 4 ft	2.1-4.1 ft	180-52876-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-2-4	SSHS-B374-SUB-2-4	3/10/2016	852.41	852.73	0.32	-	2 - 4 ft	2.32-4.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B554	091716 09:10_SSHS-B554-SUB-2-4	SSHS-B554-SUB-2-4	9/16/2016	852.21	852.78	0.57	-	2 - 4 ft	2.57-4.57 ft	180-58783-1	Not Excavated							
Rear Parking Lot	SSHS-B869	011018 09:40_SSHS-B869-SUB-2-4	SSHS-B869-SUB-2-4	1/8/2018	852.60	852.55	-0.05	-	2 - 4 ft	1.95-3.95 ft	180-74016-1	Not Excavated							
Rear Parking Lot	SSHS-B854	011018 09:40_SSHS-B854-SUB-2-4	SSHS-B854-SUB-2-4	1/9/2018	851.70	851.63	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-2-4	SSHS-B864-SUB-2-4	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40_PS-FD-2	PS-FD-2	1/9/2018	852.32	852.74	0.42	-	2 - 4 ft	2.42-4.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30_SSHS-B829-SUB-2-4	SSHS-B829-SUB-2-4	1/10/2018	852.37	852.65	0.28	-	2 - 4 ft	2.28-4.28 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B873	011218 12:30_SSHS-B873-SUB-2-4	SSHS-B873-SUB-2-4	1/11/2018	853.20	853.51	0.31	-	2 - 4 ft	2.31-4.31 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B910	011218 12:30_SSHS-B910-SUB-2-4	SSHS-B910-SUB-2-4	1/11/2018	849.70	850.44	0.74	-	2 - 4 ft	2.74-4.74 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B926	011918 10:00_SSHS-B926-SUB-2-4	SSHS-B926-SUB-2-4	1/18/2018	852.34	853.06	0.72	-	2 - 4 ft	2.72-4.72 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-2-4	SSHS-B911-SUB-2-4	1/19/2018	850.80	850.99	0.19	-	2 - 4 ft	2.19-4.19 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B924	012018 09:00_SSHS-B924-SUB-2-4	SSHS-B924-SUB-2-4	1/19/2018	851.60	852.22	0.62	-	2 - 4 ft	2.62-4.62 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B951	030218 09:10_SSHS-B951-SUB-2-4	SSHS-B951-SUB-2-4	2/28/2018	852.70	852.64	-0.06	-	2 - 4 ft	1.94-3.94 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B950	030618 09:15_SSHS-B950-SUB-2-4	SSHS-B950-SUB-2-4	3/4/2018	852.44	852.70	0.26	-	2 - 4 ft	2.26-4.26 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1073	062618 10:05_SSHS-B1073-SUB-2-4	SSHS-B1073-SUB-2-4	6/24/2018	852.50	852.73	0.23	-	2 - 4 ft	2.23-4.23 ft	200-44046-1	Not Excavated							
Rear Parking Lot	SSHS-B1074	063018 10:00_PS-FD-5	PS-FD-5	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1074	063018 10:00_SSHS-B1074-SUB-2-4	SSHS-B1074-SUB-2-4	6/29/2018	851.08	851.80	0.72	-	2 - 4 ft	2.72-4.72 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1202	063018 10:00_SSHS-B1202-SUB-2-4	SSHS-B1202-SUB-2-4	6/29/2018	852.10	852.96	0.86	-	2 - 4 ft	2.86-4.86 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-SW-003	071218 09:15_SW-003-2-4	SW-003-2-4	7/11/2018	-	852.71	-	849.20	2 - 4 ft	3.51 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-B1394	072418 08:50_B1394-2FT	B1394-2FT	7/21/2018	-	852.80	-	849.80	2 - 4 ft	3 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-SS-04_8_20	082218 09:15_SS-04 (2-4) 20180820	SS-04 (2-4) 20180820	8/20/2018	-	847.95	-	845.40	2 - 4 ft	2.55 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-2-4	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	2 - 4 ft	2 - 4 ft	180-124920-2	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4-20230209	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 0.00098 UJ	< 0.0016 UT	< 0.0041 UJ	< 0.0036 UJ	< 0.0018 UT	< 0.0020 UT	< 0.0071 UT
Rear Parking Lot	SSHS-E-S-8-1	080418 11:30_E-S-8-1	E-S-8-1	8/3/2018	-	851.75	-	848.90	2.3 - 2.3 ft	2.85 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-1	080418 11:30_E-S-9-1	E-S-9-1	8/3/2018	-	852.04	-	848.20	2.3 - 2.3 ft	3.84 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-W8-1	080118 09:00_W8-1	W8-1	7/27/2018	-	852.29	-	849.20	2.4 - 2.4 ft	3.09 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-1	073118 08:50_G-S-3-1	G-S-3-1	7/26/2018	-	852.80	-	849.90	2.5 - 2.5 ft	2.90 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W3-1	080118 09:00_W3-1	W3-1	7/27/2018	-	850.94	-	848.20	2.5 - 2.5 ft	2.74 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W7-1	080118 09:00_W7-1	W7-1	7/27/2018	-	851.99	-	848.80	2.5 - 2.5 ft	3.19 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-848-846-20240812	SSHS-SPA4-B5502-ELEV-848-846	8/12/2024	850.65	850.65	0.00	-	2.65-4.65 ft	2.65-4.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-WWS_7_21	072418 08:50_WWS	WWS	7/21/2018	-	851.82	-	848.40	2.7 - 2.7 ft	3.42 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-1	073118 08:50_G-S-2-1	G-S-2-1	7/26/2018	-	852.73	-	849.70	2.8 - 2.8 ft	3.03 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_DUP-17	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0017 U	0.0033 J	< 0.0019 U	< 0.00098 U	< 0.0031 U	< 0.0016 U	
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-3-6 (4)	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated	< 0.0012 U	0.0034 J	< 0.0013 U	< 0.00068 U	< 0.0021 U	< 0.0011 U	
Rear Parking Lot	SSHS-EN5-1	073118 08:50_E-N-5-1	E-N-5-1	7/26/2018	-	852.71	-	849.00	3.2 - 3.2 ft	3.71 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-GS4-1	073118 08:50_G-S-4-1	G-S-4-1	7/26/2018	-	852.86	-	849.20	3.2 - 3.2 ft	3.66 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-1	080418 11:30_E-S-1-1	E-S-1-1	8/3/2018	-	852.55	-	848.80	3.4 - 3.4 ft	3.75 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-2	080418 11:30_E-S-9-2	E-S-9-2	8/3/2018	-	852.42	-	849.90	3.4 - 3.4 ft	2.52 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-EN4-1	073118 08:50_E-N-4-1	E-N-4-1	7/26/2018	-	853.36	-	848.50	3.6 - 3.6 ft	4.86 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W10-1	080118 09:00_W10-1	W10-1	7/27/2018	-	852.68	-	848.30	3.6 - 3.7 ft	4.38 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-N-8-2	080418 11:30_E-N-8-2	E-N-8-2	8/3/2018	-	852.25	-	848.50	3.7 - 3.8 ft	3.75 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-8-2	080418 11:30_E-S-8-2	E-S-8-2	8/3/2018	-	852.17	-	849.80	3.8 - 3.9 ft	2.37 ft	180-80462-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated							
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated							
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated							
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated							
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated							
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated							
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated							
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-SS-03_8_20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018		848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.0039 UJ	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 UJ	< 0.0040 U	< 0.0020 UT
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-SS2_7_21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-nat_gas_2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated						
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated						
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated						
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated						
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated						
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated						
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated						
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated						
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated						
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated						
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated						
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated						
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated						
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated						
Rear Parking Lot	SSHS-SS-03 8 20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-SS2 7 21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated						
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-nat gas 2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated						
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated						

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated							
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated							
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated							
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated							
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated							
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated							
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated							
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-SS-03_8_20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.0045 U	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0014 U
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-SS2_7_21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-nat_gas_2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated							

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated								
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated								
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated								
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated								
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated								
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated								
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated								
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-SS-03_8_20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.0022 UT	< 0.0041 UT	< 0.0015 UT	< 0.0017 UT	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 UT
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-SS2_7_21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-nat_gas_2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated								
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated								
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated								
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated								
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated								
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated								
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated								
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated								
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-SS-03 8 20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.0020 U	< 0.0016 UJ	< 0.0026 UT	< 0.0073 U	< 0.0024 UT	< 0.0025 UJ	< 0.0018 UJ	< 0.0015 U
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-SS2 7 21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-nat gas 2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated						
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated						
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated						
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated						
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated						
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated						
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated						
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated						
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated						
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated						
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated						
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated						
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated						
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated						
Rear Parking Lot	SSHS-SS-03_8_20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0015 UJ	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 UT
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-SS2_7_21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated						
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-nat_gas_2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated						
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-W7-2	080118 09:00 W7-2	W7-2	7/27/2018	-	852.08	-	847.40	3.9 - 3.9 ft	4.68 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W4-2	080118 09:00 W4-2	W4-2	7/27/2018	-	851.02	-	846.90	3.9 - 4 ft	4.12 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W12-1	080118 09:00 W12-1	W12-1	7/27/2018	-	852.60	-	848.10	4 - 4 ft	4.50 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-4-6	SSHS-B107-SUB-4-6	7/22/2015	849.10	849.29	0.19	-	4 - 6 ft	4.19-6.19 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 PS-FD-#22	PS-FD-#22	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-4-6	SSHS-B108-SUB-4-6	7/22/2015	849.57	849.70	0.13	-	4 - 6 ft	4.13-6.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-4-6	SSHS-B125-SUB-4-6	7/31/2015	850.91	850.71	-0.20	-	4 - 6 ft	3.8-5.8 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 CS-FD-#19	CS-FD-#19	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-4-6	SSHS-B126-SUB-4-6	7/31/2015	850.94	850.82	-0.12	-	4 - 6 ft	3.88-5.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-4-6	SSHS-B133-SUB-4-6	8/3/2015	852.64	852.58	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-4-6	SSHS-B148-SUB-4-6	8/3/2015	852.19	852.56	0.37	-	4 - 6 ft	4.37-6.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-4-6	SSHS-B159-SUB-4-6	8/3/2015	852.33	852.34	0.01	-	4 - 6 ft	4.01-6.01 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-4-6	SSHS-B162-SUB-4-6	8/3/2015	852.38	852.56	0.18	-	4 - 6 ft	4.18-6.18 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-4-6	SSHS-B371-SUB-4-6	3/8/2016	852.79	852.76	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B386	030916 11:30 SSHS-B386-SUB-4-6	SSHS-B386-SUB-4-6	3/8/2016	852.82	853.09	0.27	-	4 - 6 ft	4.27-6.27 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-4-6	SSHS-B373-SUB-4-6	3/10/2016	852.56	852.68	0.12	-	4 - 6 ft	4.12-6.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-4-6	SSHS-B374-SUB-4-6	3/10/2016	852.41	852.73	0.32	-	4 - 6 ft	4.32-6.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-4-6	SSHS-B536-SUB-4-6	9/21/2016	852.47	853.03	0.56	-	4 - 6 ft	4.56-6.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-4-6	SSHS-B552-SUB-4-6	9/21/2016	853.01	853.17	0.16	-	4 - 6 ft	4.16-6.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-4-6	SSHS-B534-SUB-4-6	9/22/2016	852.33	852.53	0.20	-	4 - 6 ft	4.2-6.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-4-6	SSHS-B550-SUB-4-6	9/22/2016	851.35	851.20	-0.15	-	4 - 6 ft	3.85-5.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B853	011018 09:40 SSHS-B853-SUB-4-6	SSHS-B853-SUB-4-6	1/8/2018	852.22	852.35	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74016-2	Not Excavated							
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-4-6	SSHS-B835-SUB-4-6	1/9/2018	852.50	852.68	0.18	-	4 - 6 ft	4.18-6.18 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B854	011018 09:40 SSHS-B854-SUB-4-6	SSHS-B854-SUB-4-6	1/9/2018	851.70	851.63	-0.07	-	4 - 6 ft	3.93-5.93 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-4-6	SSHS-B864-SUB-4-6	1/9/2018	852.32	852.74	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B894	011018 09:40 SSHS-B894-SUB-4-6	SSHS-B894-SUB-4-6	1/9/2018	853.55	853.68	0.13	-	4 - 6 ft	4.13-6.13 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B895	011018 09:40 SSHS-B895-SUB-4-6	SSHS-B895-SUB-4-6	1/9/2018	851.80	851.77	-0.03	-	4 - 6 ft	3.97-5.97 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B829	011218 12:30 SSHS-B829-SUB-4-6	SSHS-B829-SUB-4-6	1/10/2018	852.37	852.65	0.28	-	4 - 6 ft	4.28-6.28 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B831	011218 12:30 SSHS-B831-SUB-4-6	SSHS-B831-SUB-4-6	1/10/2018	852.79	852.91	0.12	-	4 - 6 ft	4.12-6.12 ft	180-74125-2	Not Excavated							
Rear Parking Lot	SSHS-B873	011218 12:30 SSHS-B873-SUB-4-6	SSHS-B873-SUB-4-6	1/11/2018	853.20	853.51	0.31	-	4 - 6 ft	4.31-6.31 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B910	011218 12:30 SSHS-B910-SUB-4-6	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180-74124-3	Not Excavated							
Rear Parking Lot	SSHS-B910	SSHS-B910-SUB-4-6-20180111	SSHS-B910-SUB-4-6	1/11/2018	849.70	850.44	0.74	-	4 - 6 ft	4.74-6.74 ft	180741243	Not Excavated							
Rear Parking Lot	SSHS-B925	011718 12:00 SSHS-B925-SUB-4-6	SSHS-B925-SUB-4-6	1/12/2018	852.80	852.88	0.08	-	4 - 6 ft	4.08-6.08 ft	180-74207-2	Not Excavated							
Rear Parking Lot	SSHS-B837	012418 09:30 SSHS-B837-SUB-4-6	SSHS-B837-SUB-4-6	1/20/2018	852.37	852.79	0.42	-	4 - 6 ft	4.42-6.42 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B937	012418 09:30 SSHS-B937-SUB-4-6	SSHS-B937-SUB-4-6	1/20/2018	851.90	852.53	0.63	-	4 - 6 ft	4.63-6.63 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B914	012418 09:30 SSHS-B914-SUB-4-6	SSHS-B914-SUB-4-6	1/22/2018	853.70	853.73	0.03	-	4 - 6 ft	4.03-6.03 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-4-6	SSHS-B955-SUB-4-6	2/28/2018	853.70	853.92	0.22	-	4 - 6 ft	4.22-6.22 ft	180-75405-1	Not Excavated							
Rear Parking Lot	SSHS-B970	030318 09:15 SSHS-B970-SUB-4-6	SSHS-B970-SUB-4-6	3/1/2018	850.71	850.32	-0.39	-	4 - 6 ft	3.61-5.61 ft	180-75501-1	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-4-6	SSHS-B973-SUB-4-6	3/1/2018	852.19	852.39	0.20	-	4 - 6 ft	4.20-6.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B994	030218 09:10 SSHS-B994-SUB-4-6	SSHS-B994-SUB-4-6	3/1/2018	852.12	852.52	0.40	-	4 - 6 ft	4.40-6.40 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B995	030218 09:10 PS-FD-5	PS-FD-5	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B995	030218 09:10 SSHS-B995-SUB-4-6	SSHS-B995-SUB-4-6	3/1/2018	849.89	849.94	0.05	-	4 - 6 ft	4.05-6.05 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B1189	062618 10:05 SSHS-B1189-SUB-4-6	SSHS-B1189-SUB-4-6	6/24/2018	853.90	853.81	-0.09	-	4 - 6 ft	3.91-5.91 ft	200-44046-1	Not Excavated							
Rear Parking Lot	SSHS-B1064	063018 10:00 SSHS-B1064-SUB-4-6	SSHS-B1064-SUB-4-6	6/29/2018	850.52	850.70	0.18	-	4 - 6 ft	4.18-6.18 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1194	063018 10:00 SSHS-B1194-SUB-4-6	SSHS-B1194-SUB-4-6	6/29/2018	852.03	851.97	-0.06	-	4 - 6 ft	3.94-5.94 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1202	063018 10:00 SSHS-B1202-SUB-4-6	SSHS-B1202-SUB-4-6	6/29/2018	852.10	852.96	0.86	-	4 - 6 ft	4.86-6.86 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1105	070318 09:15 SSHS-B1105-SUB-4-6	SSHS-B1105-SUB-4-6	6/30/2018	851.18	850.76	-0.42	-	4 - 6 ft	3.58-5.58 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1206	070318 09:15 SSHS-B1206-SUB-4-6	SSHS-B1206-SUB-4-6	7/2/2018	852.30	852.65	0.35	-	4 - 6 ft	4.35-6.35 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1233	070318 09:15 SSHS-B1233-SUB-4-6	SSHS-B1233-SUB-4-6	7/2/2018	852.40	852.81	0.41	-	4 - 6 ft	4.41-6.41 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1235	070318 09:15 SSHS-B1235-SUB-4-6	SSHS-B1235-SUB-4-6	7/2/2018	848.02	848.61	0.59	-	4 - 6 ft	4.59-6.59 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-4-6	SSHS-B1236-SUB-4-6	7/2/2018	850.26	850.34	0.08	-	4 - 6 ft	4.08-6.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1193	070718 09:30 SSHS-B1193-SUB-4-6	SSHS-B1193-SUB-4-6	7/6/2018	851.75	851.44	-0.31	-	4 - 6 ft	3.69-5.69 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1255	071018 09:15 SSHS-B1255-SUB-4-6-BOT	SSHS-B1255-SUB-4-6-BOT	7/9/2018	853.59	853.81	0.22	-	4 - 6 ft	4.22-6.22 ft	180-79581-1	Not Excavated							
Rear Parking Lot	SSHS-SW-005	071218 09:15 SW-005-4-6	SW-005-4-6	7/11/2018	-	852.84	-	846.60	4 - 6 ft	6.24 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-006	071218 09:15 SW-006-4-6	SW-006-4-6	7/11/2018	-	852.87	-	847.30	4 - 6 ft	5.57 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-007	071218 09:15 SW-007-4-6	SW-007-4-6	7/11/2018	-	852.79	-	847.90	4 - 6 ft	4.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-018	071318 09:15 SW-018-4-6	SW-018-4-6	7/12/2018	-	852.74	-	848.80	4 - 6 ft	3.94 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-021	071318 09:15 SW-021-4-6	SW-021-4-6	7/12/2018	-	852.69	-	848.00	4 - 6 ft	4.69 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-4-6	SSHS-B1245-SUB-4-6	7/28/2018	849.10	850.00	0.90	-	4 - 6 ft	4.90-6.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1346	080418 11:30 SSHS-B1346-SUB-4-6	SSHS-B1346-SUB-4-6	8/3/2018	851.99	852.20	0.21	-	4 - 6 ft	4.21-6.21 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-SS-03 8 20	082218 09:15 SS-03 (4-6) 20180820	SS-03 (4-6) 20180820	8/20/2018	-	848.65	-	844.30	4 - 6 ft	4.35 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-4-6	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	4 - 6 ft	4 - 6 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6-20230209	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 0.00098 U	< 0.0016 UT	< 0.0041 U	< 0.0036 U	< 0.0018 UT	< 0.0020 UT	< 0.0072 UT
Rear Parking Lot	SSHS-SN3-1	073118 08:50 S-N-3-1	S-N-3-1	7/26/2018	-	852.60	-	847.80	4.2 - 4.2 ft	4.8 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-1	080118 09:00 W6-1	W6-1	7/27/2018	-	851.81	-	846.90	4.2 - 4.2 ft	4.91 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-W10-2	080118 09:00 W10-2	W10-2	7/27/2018	-	852.80	-	847.60	4.2 - 4.3 ft	5.20 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN1-1	073118 08:50 E-N-1-1	E-N-1-1	7/26/2018	-	852.94	-	848.00	4.3 - 4.3 ft	4.94 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W3-2	080118 09:00 W3-2	W3-2	7/27/2018	-	850.91	-	846.40	4.3 - 4.3 ft	4.51 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-SS2 7 21	072418 08:50 SS2	SS2	7/21/2018	-	852.63	-	847.30	4.5 - 4.5 ft	5.33 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-1	073118 08:50 E-N-3-1	E-N-3-1	7/26/2018	-	852.75	-	847.60	4.5 - 4.5 ft	5.15 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-EN4-2	073118 08:50 E-N-4-2	E-N-4-2	7/26/2018	-	853.36	-	847.60	4.5 - 4.5 ft	5.76 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-2	073118 08:50 G-S-3-2	G-S-3-2	7/26/2018	-	852.80	-	847.90	4.5 - 4.5 ft	4.90 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-nat_gas_2	072518 09:00 NAT GAS 2	NAT GAS 2	7/24/2018	-	852.82	-	847.80	4.6 - 4.6 ft	5.02 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-W11-1	080118 09:00 W11-1	W11-1	7/27/2018	-	852.64	-	847.60	4.6 - 4.6 ft	5.04 ft	180-80306-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-W9-2	080118 09:00 W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-1	073118 08:50 E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-GS4-2	073118 08:50 G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-SN5-1	073118 08:50 S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00 NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-2	073118 08:50 E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W11-2	080118 09:00 W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30 E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-2	073118 08:50 G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-ES5-2	073118 08:50 E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W2-3	080118 09:00 W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30 E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00 CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated							
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-GS3-3	073118 08:50 G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-ES4-2	073118 08:50 E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-SN4-2	073118 08:50 S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W12-2	080118 09:00 W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-3	073118 08:50 E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-GS4-3	073118 08:50 G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50 SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-B149	072215 08:45 SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated							
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B139	080615 11:15 SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B161	080615 11:15 SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B549	092316 08:45 SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B897	011218 12:30 SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B884	011218 12:30 SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B850	011918 10:00 SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00 PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B847	012418 09:30 SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B913	012418 09:30 SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B946	012418 09:30 SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B939	012418 09:30 SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B959	030118 10:00 PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B985	030118 10:00 SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-W9-2	080118 09:00_W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-EN2-1	073118 08:50_E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00		4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated						
Rear Parking Lot	SSHS-GS4-2	073118 08:50_G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-N-E-0	080718 09:00_N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated						
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated						
Rear Parking Lot	SSHS-SN5-1	073118 08:50_S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W1-2	080118 09:00_W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00_NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated						
Rear Parking Lot	SSHS-EN3-2	073118 08:50_E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W11-2	080118 09:00_W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30_E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated						
Rear Parking Lot	SSHS-GS2-2	073118 08:50_G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-ES5-2	073118 08:50_E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W2-3	080118 09:00_W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30_E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated						
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00_CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated						
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	SSHS-GS3-3	073118 08:50_G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-ES4-2	073118 08:50_E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-SN4-2	073118 08:50_S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W12-2	080118 09:00_W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-EN3-3	073118 08:50_E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00_CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00_DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-GS4-3	073118 08:50_G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50_SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated						
Rear Parking Lot	SSHS-B149	072215 08:45_SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated						
Rear Parking Lot	SSHS-B107	072315 08:30_SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B108	072315 08:30_SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B125	080115 09:10_SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B126	080115 09:10_SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B133	080615 11:15_SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B139	080615 11:15_SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B148	080615 11:15_SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B159	080615 11:15_SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B160A	080615 11:15_SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B161	080615 11:15_SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B162	080615 11:15_SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B371	030916 11:30_SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated						
Rear Parking Lot	SSHS-B373	031116 09:30_SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B374	031116 09:30_SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B536	092316 08:45_SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B549	092316 08:45_SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B552	092316 08:45_SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B550	092316 08:40_SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B835	011018 09:40_SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B864	011018 09:40_SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B904	011018 09:40_SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B897	011218 12:30_SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated						
Rear Parking Lot	SSHS-B884	011218 12:30_SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated						
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated						
Rear Parking Lot	SSHS-B850	011918 10:00_SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated						
Rear Parking Lot	SSHS-B843	012018 09:00_PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B847	012418 09:30_SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B848	012418 09:30_SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B881	012418 09:30_SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B913	012418 09:30_SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B946	012418 09:30_SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B939	012418 09:30_SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated						
Rear Parking Lot	SSHS-B906	012518 09:00_SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated						
Rear Parking Lot	SSHS-B955	030118 10:00_SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B959	030118 10:00_PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B959	030118 10:00_SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B985	030118 10:00_SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated						

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-W9-2	080118 09:00 W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN2-1	073118 08:50 E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-GS4-2	073118 08:50 G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-SN5-1	073118 08:50 S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00 NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-2	073118 08:50 E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W11-2	080118 09:00 W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30 E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-2	073118 08:50 G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-ES5-2	073118 08:50 E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W2-3	080118 09:00 W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30 E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00 CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated								
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-GS3-3	073118 08:50 G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-ES4-2	073118 08:50 E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-SN4-2	073118 08:50 S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W12-2	080118 09:00 W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-3	073118 08:50 E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-3	073118 08:50 G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50 SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-B149	072215 08:45 SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated								
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B139	080615 11:15 SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B161	080615 11:15 SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B549	092316 08:45 SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B897	011218 12:30 SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B884	011218 12:30 SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B850	011918 10:00 SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B847	012418 09:30 SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B913	012418 09:30 SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B946	012418 09:30 SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B939	012418 09:30 SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B985	030118 10:00 SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated								

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-W9-2	080118 09:00 W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN2-1	073118 08:50 E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-GS4-2	073118 08:50 G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-SN5-1	073118 08:50 S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00 NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-2	073118 08:50 E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W11-2	080118 09:00 W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30 E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-2	073118 08:50 G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-ES5-2	073118 08:50 E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W2-3	080118 09:00 W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30 E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00 CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated								
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-GS3-3	073118 08:50 G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-ES4-2	073118 08:50 E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-SN4-2	073118 08:50 S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W12-2	080118 09:00 W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-3	073118 08:50 E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-3	073118 08:50 G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50 SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-B149	072215 08:45 SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated								
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B139	080615 11:15 SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B161	080615 11:15 SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B549	092316 08:45 SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B897	011218 12:30 SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B884	011218 12:30 SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B850	011918 10:00 SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B847	012418 09:30 SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B913	012418 09:30 SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B946	012418 09:30 SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B939	012418 09:30 SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B985	030118 10:00 SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated								

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-W9-2	080118 09:00 W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN2-1	073118 08:50 E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated								
Rear Parking Lot	SSHS-GS4-2	073118 08:50 G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-SN5-1	073118 08:50 S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00 NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-2	073118 08:50 E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W11-2	080118 09:00 W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30 E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-2	073118 08:50 G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-ES5-2	073118 08:50 E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W2-3	080118 09:00 W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30 E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00 CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated								
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-GS3-3	073118 08:50 G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-ES4-2	073118 08:50 E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-SN4-2	073118 08:50 S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W12-2	080118 09:00 W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-EN3-3	073118 08:50 E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-GS4-3	073118 08:50 G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50 SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-B149	072215 08:45 SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated								
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated								
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B139	080615 11:15 SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B161	080615 11:15 SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B549	092316 08:45 SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated								
Rear Parking Lot	SSHS-B897	011218 12:30 SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated								
Rear Parking Lot	SSHS-B884	011218 12:30 SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B850	011918 10:00 SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated								
Rear Parking Lot	SSHS-B847	012418 09:30 SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B913	012418 09:30 SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B946	012418 09:30 SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B939	012418 09:30 SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B985	030118 10:00 SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-W9-2	080118 09:00 W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-EN2-1	073118 08:50 E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated						
Rear Parking Lot	SSHS-GS4-2	073118 08:50 G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated						
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated						
Rear Parking Lot	SSHS-SN5-1	073118 08:50 S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00 NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated						
Rear Parking Lot	SSHS-EN3-2	073118 08:50 E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W11-2	080118 09:00 W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30 E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated						
Rear Parking Lot	SSHS-GS2-2	073118 08:50 G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-ES5-2	073118 08:50 E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W2-3	080118 09:00 W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30 E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated						
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00 CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated						
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated						
Rear Parking Lot	SSHS-GS3-3	073118 08:50 G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-ES4-2	073118 08:50 E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-SN4-2	073118 08:50 S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-W12-2	080118 09:00 W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated						
Rear Parking Lot	SSHS-EN3-3	073118 08:50 E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-GS4-3	073118 08:50 G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50 SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated						
Rear Parking Lot	SSHS-B149	072215 08:45 SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated						
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated						
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated						
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B139	080615 11:15 SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B161	080615 11:15 SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated						
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated						
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated						
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B549	092316 08:45 SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated						
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated						
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated						
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated						
Rear Parking Lot	SSHS-B897	011218 12:30 SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated						
Rear Parking Lot	SSHS-B884	011218 12:30 SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated						
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated						
Rear Parking Lot	SSHS-B850	011918 10:00 SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated						
Rear Parking Lot	SSHS-B843	012018 09:00 PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated						
Rear Parking Lot	SSHS-B847	012418 09:30 SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B913	012418 09:30 SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B946	012418 09:30 SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B939	012418 09:30 SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated						
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated						
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B959	030118 10:00 PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B985	030118 10:00 SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated						

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-W9-2	080118 09:00 W9-2	W9-2	7/27/2018	-	852.59	-	847.20	4.6 - 4.6 ft	5.39 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-1	073118 08:50 E-N-2-1	E-N-2-1	7/26/2018	-	853.10	-	847.60	4.6 - 4.7 ft	5.50 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-DUP-01-20240812	SSHS-SPA4-DUP-01	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-846-844-20240812	SSHS-SPA4-B5502-ELEV-846-844	8/12/2024	850.65	850.65	0.00	-	4.65 - 6.65 ft	4.65 - 6.65 ft	1801782961	Not Excavated							
Rear Parking Lot	SSHS-GS4-2	073118 08:50 G-S-4-2	G-S-4-2	7/26/2018	-	852.87	-	847.60	4.7 - 4.7 ft	5.27 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-N-E-0	080718 09:00 N-E-0	N-E-0	8/6/2018	-	852.82	-	847.70	4.7 - 4.7 ft	5.12 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-848-846-20240813	SSHS-SPA4-B5527-ELEV-848-846	8/13/2024	852.76	852.76	0.00	-	4.76-6.76 ft	4.76-6.76 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-SN5-1	073118 08:50 S-N-5-1	S-N-5-1	7/26/2018	-	852.71	-	847.30	4.8 - 4.8 ft	5.41 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W1-2	080118 09:00 W1-2	W1-2	7/27/2018	-	849.90	-	845.00	4.8 - 4.8 ft	4.90 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-nat_gas_1	072518 09:00 NAT GAS 1	NAT GAS 1	7/24/2018	-	852.74	-	847.40	5 - 5 ft	5.34 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-2	073118 08:50 E-N-3-2	E-N-3-2	7/26/2018	-	853.25	-	847.10	5.1 - 5.1 ft	6.15 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W11-2	080118 09:00 W11-2	W11-2	7/27/2018	-	852.58	-	847.00	5.1 - 5.1 ft	5.58 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-2	080418 11:30 E-S-1-2	E-S-1-2	8/3/2018	-	852.50	-	847.10	5.1 - 5.1 ft	5.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-2	073118 08:50 G-S-2-2	G-S-2-2	7/26/2018	-	852.69	-	847.20	5.2 - 5.2 ft	5.49 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-ES5-2	073118 08:50 E-S-5-2	E-S-5-2	7/26/2018	-	852.72	-	846.90	5.3 - 5.3 ft	5.82 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W2-3	080118 09:00 W2-3	W2-3	7/27/2018	-	850.48	-	844.90	5.5 - 5.5 ft	5.58 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-3	080418 11:30 E-S-1-3	E-S-1-3	8/3/2018	-	852.43	-	846.60	5.5 - 5.5 ft	5.83 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-C-E-S-2	080718 09:00 CES-2	CES-2	8/4/2018	-	850.20	-	844.40	5.5 - 5.6 ft	5.80 ft	180-80511-1	Not Excavated							
Rear Parking Lot	CS-01-19	CS-01-19-20190624	CS-01-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-03-19	CS-03-19-20190624	CS-03-19	6/24/2019	-	852.74	-	847.24	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-04-19	CS-04-19-20190624	CS-04-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-06-19	CS-06-19-20190624	CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	CS-06-19	FD-CS-06-19-20190624	FD-CS-06-19	6/24/2019	-	852.60	-	847.10	5.50 ft	5.50 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-GS3-3	073118 08:50 G-S-3-3	G-S-3-3	7/26/2018	-	852.79	-	846.70	5.6 - 5.6 ft	6.09 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-ES4-2	073118 08:50 E-S-4-2	E-S-4-2	7/26/2018	-	853.34	-	846.40	5.6 - 5.7 ft	6.94 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-SN4-2	073118 08:50 S-N-4-2	S-N-4-2	7/26/2018	-	853.26	-	846.30	5.7 - 5.7 ft	6.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W12-2	080118 09:00 W12-2	W12-2	7/27/2018	-	852.56	-	846.30	5.8 - 5.8 ft	6.26 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-EN3-3	073118 08:50 E-N-3-3	E-N-3-3	7/26/2018	-	853.26	-	846.30	5.9 - 5.9 ft	6.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 CES-1	CES-1	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-C-E-S-1	080718 09:00 DUP-2-08042018	DUP-2-08042018	8/4/2018	-	849.61	-	843.50	5.9 - 6 ft	6.11 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-GS4-3	073118 08:50 G-S-4-3	G-S-4-3	7/26/2018	-	852.87	-	846.30	6 - 6 ft	6.57 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-SS1_7_21	072418 08:50 SS1	SS1	7/21/2018	-	852.61	-	846.10	6 - 6.1 ft	6.51 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-B149	072215 08:45 SSHS-B149-SUB-6-8	SSHS-B149-SUB-6-8	7/21/2015	852.27	852.59	0.32	-	6 - 8 ft	6.32-8.32 ft	180-46139-1	Not Excavated							
Rear Parking Lot	SSHS-B107	072315 08:30 SSHS-B107-SUB-6-8	SSHS-B107-SUB-6-8	7/22/2015	849.10	849.29	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B108	072315 08:30 SSHS-B108-SUB-6-8	SSHS-B108-SUB-6-8	7/22/2015	849.57	849.70	0.13	-	6 - 8 ft	6.13-8.13 ft	180-46170-1	Not Excavated							
Rear Parking Lot	SSHS-B125	080115 09:10 SSHS-B125-SUB-6-8	SSHS-B125-SUB-6-8	7/31/2015	850.91	850.71	-0.20	-	6 - 8 ft	5.8-7.8 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-6-8	SSHS-B126-SUB-6-8	7/31/2015	850.94	850.82	-0.12	-	6 - 8 ft	5.88-7.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B133	080615 11:15 SSHS-B133-SUB-6-8	SSHS-B133-SUB-6-8	8/3/2015	852.64	852.58	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B139	080615 11:15 SSHS-B139-SUB-6-8	SSHS-B139-SUB-6-8	8/3/2015	851.34	851.26	-0.08	-	6 - 8 ft	5.92-7.92 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B148	080615 11:15 SSHS-B148-SUB-6-8	SSHS-B148-SUB-6-8	8/3/2015	852.19	852.56	0.37	-	6 - 8 ft	6.37-8.37 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B159	080615 11:15 SSHS-B159-SUB-6-8	SSHS-B159-SUB-6-8	8/3/2015	852.33	852.34	0.01	-	6 - 8 ft	6.01-8.01 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-6-8	SSHS-B160A-SUB-6-8	8/3/2015	852.12	852.20	0.08	-	6 - 8 ft	6.08-8.08 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B161	080615 11:15 SSHS-B161-SUB-6-8	SSHS-B161-SUB-6-8	8/3/2015	852.38	852.57	0.19	-	6 - 8 ft	6.19-8.19 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B162	080615 11:15 SSHS-B162-SUB-6-8	SSHS-B162-SUB-6-8	8/3/2015	852.38	852.56	0.18	-	6 - 8 ft	6.18-8.18 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-6-8	SSHS-B371-SUB-6-8	3/8/2016	852.79	852.76	-0.03	-	6 - 8 ft	5.97-7.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-6-8	SSHS-B373-SUB-6-8	3/10/2016	852.56	852.68	0.12	-	6 - 8 ft	6.12-8.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B374	031116 09:30 SSHS-B374-SUB-6-8	SSHS-B374-SUB-6-8	3/10/2016	852.41	852.73	0.32	-	6 - 8 ft	6.32-8.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-6-8	SSHS-B536-SUB-6-8	9/21/2016	852.47	853.03	0.56	-	6 - 8 ft	6.56-8.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B549	092316 08:45 SSHS-B549-SUB-6-8	SSHS-B549-SUB-6-8	9/21/2016	850.17	849.92	-0.25	-	6 - 8 ft	5.75-7.75 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-6-8	SSHS-B552-SUB-6-8	9/21/2016	853.01	853.17	0.16	-	6 - 8 ft	6.16-8.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-6-8	SSHS-B550-SUB-6-8	9/22/2016	851.35	851.20	-0.15	-	6 - 8 ft	5.85-7.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B835	011018 09:40 SSHS-B835-SUB-6-8	SSHS-B835-SUB-6-8	1/9/2018	852.50	852.68	0.18	-	6 - 8 ft	6.18-8.18 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B864	011018 09:40 SSHS-B864-SUB-6-8	SSHS-B864-SUB-6-8	1/9/2018	852.32	852.74	0.42	-	6 - 8 ft	6.42-8.42 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-6-8	SSHS-B904-SUB-6-8	1/9/2018	852.40	852.89	0.49	-	6 - 8 ft	6.49-8.49 ft	180-74014-1	Not Excavated							
Rear Parking Lot	SSHS-B897	011218 12:30 SSHS-B897-SUB-6-8	SSHS-B897-SUB-6-8	1/10/2018	849.98	850.22	0.24	-	6 - 8 ft	6.24-8.24 ft	180-74125-1	Not Excavated							
Rear Parking Lot	SSHS-B884	011218 12:30 SSHS-B884-SUB-6-8	SSHS-B884-SUB-6-8	1/11/2018	851.07	850.66	-0.41	-	6 - 8 ft	5.59-7.59 ft	180-74124-1	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-6-8	SSHS-B889-SUB-6-8	1/12/2018	851.80	852.52	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B850	011918 10:00 SSHS-B850-SUB-6-8	SSHS-B850-SUB-6-8	1/18/2018	850.33	850.69	0.36	-	6 - 8 ft	6.36-8.36 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00 PS-FD-29	PS-FD-29	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-6-8	SSHS-B843-SUB-6-8	1/19/2018	851.40	851.34	-0.06	-	6 - 8 ft	5.94-7.94 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-6-8	SSHS-B911-SUB-6-8	1/19/2018	850.80	850.99	0.19	-	6 - 8 ft	6.19-8.19 ft	180-74310-1	Not Excavated							
Rear Parking Lot	SSHS-B847	012418 09:30 SSHS-B847-SUB-6-8	SSHS-B847-SUB-6-8	1/20/2018	851.78	852.12	0.34	-	6 - 8 ft	6.34-8.34 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-6-8	SSHS-B848-SUB-6-8	1/20/2018	851.19	851.58	0.39	-	6 - 8 ft	6.39-8.39 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-6-8	SSHS-B842-SUB-6-8	1/22/2018	851.80	851.59	-0.21	-	6 - 8 ft	5.79-7.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-6-8	SSHS-B881-SUB-6-8	1/22/2018	848.90	849.62	0.72	-	6 - 8 ft	6.72-8.72 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B913	012418 09:30 SSHS-B913-SUB-6-8	SSHS-B913-SUB-6-8	1/22/2018	851.54	851.99	0.45	-	6 - 8 ft	6.45-8.45 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B946	012418 09:30 SSHS-B946-SUB-6-8	SSHS-B946-SUB-6-8	1/22/2018	849.00	849.52	0.52	-	6 - 8 ft	6.52-8.52 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B939	012418 09:30 SSHS-B939-SUB-6-8	SSHS-B939-SUB-6-8	1/23/2018	850.07	850.20	0.13	-	6 - 8 ft	6.13-8.13 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B906	012518 09:00 SSHS-B906-SUB-6-8	SSHS-B906-SUB-6-8	1/24/2018	851.60	852.25	0.65	-	6 - 8 ft	6.65-8.65 ft	180-74436-2	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-6-8	SSHS-B955-SUB-6-8	2/27/2018	853.70	853.92	0.22	-	6 - 8 ft	6.22-8.22 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B959	030118 10:00 PS-FD-3	PS-FD-3	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-6-8	SSHS-B959-SUB-6-8	2/28/2018	851.40	851.14	-0.26	-	6 - 8 ft	5.74-7.74 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B985	030118 10:00 SSHS-B985-SUB-6-8	SSHS-B985-SUB-6-8	2/28/2018	851.33	851.63	0.30	-	6 - 8 ft	6.30-8.30 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-6-8	SSHS-B973-SUB-6-8	3/1/2018	852.19	852.39	0.20	-	6 - 8 ft	6.20-8.20 ft	180-75478-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B954	030618 09:15 SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15 SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B986	030618 09:15 SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1242	063018 10:00 SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1243	063018 10:00 SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1244	070318 09:15 SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1220	070318 09:15 SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1223	070318 09:15 7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1257	071218 09:15 SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-008	071218 09:15 SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-009	071218 09:15 SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-019	071318 09:15 SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-020	071318 09:15 SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15 SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1500	082218 09:15 SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 UJ	< 0.0041 U	< 0.0021 UT
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.0041 U	< 0.00055 U	< 0.00056 U	< 0.00046 U	< 0.00036 U	< 0.0006 U	< 0.00042 U	< 0.00036 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-EN4-3	073118 08:50 E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-3	080118 09:00 W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30 E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-CS-02	081018 09:00 CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50 WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-4	073118 08:50 G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30 E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-3	073118 08:50 G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.01 U	< 0.0032 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 UT
Rear Parking Lot	SSHS-N-E-1	080718 09:00 N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	0.019 J	< 0.0029 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	0.016 J	< 0.0032 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50 E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-CS-01	081018 09:00 CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-3	073118 08:50 E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-P-4	081018 09:00 P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-04	081018 09:00 WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.011 U	< 0.0014 U	< 0.0014 U	< 0.0012 U	< 0.00093 U	< 0.0016 U	< 0.0011 U	< 0.00094 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00068 U	< 0.00055 U	< 0.00043 U	< 0.00073 U	< 0.0005 U	< 0.00044 U
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15 CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15 SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B117A	080615 11:15 SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B378	030916 11:30 SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30 PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30 SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30 PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30 SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B391	031116 09:30 SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B392	031116 09:30 SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B395	031116 09:30 SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B396	031116 09:30 SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45 SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45 SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B533	092316 08:40 SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B535	092316 08:40 SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B540	092316 08:40 SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B544	092316 08:40 SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40 SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B905	011818 12:20 SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B954	030618 09:15_SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B986	030618 09:15_SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B1242	063018 10:00_SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1243	063018 10:00_SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1244	070318 09:15_SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1220	070318 09:15_SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1223	070318 09:15_7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1236	070318 09:15_SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1257	071218 09:15_SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-008	071218 09:15_SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-009	071218 09:15_SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-019	071318 09:15_SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-SW-020	071318 09:15_SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B1245	073118 08:50_SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15_SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B1500	082218 09:15_SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 UJ	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.00062 U	< 0.00058 U	< 0.0013 U	< 0.00048 U	< 0.00069 U	< 0.0003 U	< 0.00061 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-EN4-3	073118 08:50_E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-3	080118 09:00_W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30_E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-CS-02	081018 09:00_CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50_WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-4	073118 08:50_G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30_E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-3	073118 08:50_G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.0033 U	< 0.0027 U	< 0.0032 UT	< 0.0037 U	< 0.0044 U	< 0.0037 U	< 0.0036 U
Rear Parking Lot	SSHS-N-E-1	080718 09:00_N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0030 U	< 0.0025 U	< 0.0029 U	< 0.0034 U	< 0.0040 U	< 0.0034 U	< 0.0032 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0033 U	< 0.0027 U	< 0.0032 U	< 0.0037 U	< 0.0044 U	< 0.0037 U	< 0.0036 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50_E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-CS-01	081018 09:00_CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-3	073118 08:50_E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-P-4	081018 09:00_P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-04	081018 09:00_WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.0016 U	< 0.0015 U	< 0.0033 U	< 0.0012 U	< 0.0018 U	< 0.00078 U	< 0.0016 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.00074 U	< 0.0007 U	< 0.0015 U	< 0.00057 U	< 0.00084 U	< 0.00036 U	< 0.00074 U
Rear Parking Lot	SSHS-B126	080115 09:10_SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B117A	080615 11:15_SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15_SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30_SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B378	030916 11:30_SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30_SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B391	031116 09:30_SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B392	031116 09:30_SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B395	031116 09:30_SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B396	031116 09:30_SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45_SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B533	092316 08:40_SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40_SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B535	092316 08:40_SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B540	092316 08:40_SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B544	092316 08:40_SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40_SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40_SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B905	011818 12:20_SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated							

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B954	030618 09:15 SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15 SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B986	030618 09:15 SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1242	063018 10:00 SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1243	063018 10:00 SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1244	070318 09:15 SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1220	070318 09:15 SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1223	070318 09:15 7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15 SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1257	071218 09:15 SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-008	071218 09:15 SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-009	071218 09:15 SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-019	071318 09:15 SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-020	071318 09:15 SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50 SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15 SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1500	082218 09:15 SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Rear Parking Lot	SSHS-B64	081514 01:15 SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.00055 U	< 0.0007 U	< 0.00054 U	< 0.00065 U	< 0.00053 U	< 0.00052 U	< 0.00047 U	< 0.0005 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-EN4-3	073118 08:50 E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-3	080118 09:00 W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30 E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-CS-02	081018 09:00 CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50 WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-4	073118 08:50 G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30 E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-3	073118 08:50 G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.0050 U	< 0.0029 U	< 0.0045 UT	< 0.0032 U	< 0.0034 U	< 0.0031 U	< 0.0028 U	< 0.0033 U
Rear Parking Lot	SSHS-N-E-1	080718 09:00 N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0045 U	< 0.0026 U	< 0.0041 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0026 U	< 0.0030 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0050 U	< 0.0029 U	< 0.0045 U	< 0.0031 U	< 0.0034 U	< 0.0031 U	< 0.0028 U	< 0.0033 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50 E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-CS-01	081018 09:00 CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-3	073118 08:50 E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-P2	071318 09:15 SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-P-4	081018 09:00 P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-04	081018 09:00 WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15 SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0014 U	< 0.0017 U	< 0.0014 U	< 0.0013 U	< 0.0012 U	< 0.0013 U
Rear Parking Lot	SSHS-B65	081514 01:15 SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00063 U	< 0.00056 U	< 0.0006 U
Rear Parking Lot	SSHS-B126	080115 09:10 SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B106A	080615 11:15 CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B106A	080615 11:15 SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B117A	080615 11:15 SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated								
Rear Parking Lot	SSHS-B160A	080615 11:15 SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30 SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B378	030916 11:30 SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B394	030916 11:30 PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B394	030916 11:30 SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30 SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B390	031116 09:30 PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B390	031116 09:30 SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B391	031116 09:30 SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B392	031116 09:30 SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B395	031116 09:30 SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B396	031116 09:30 SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-MW-46	090216 08:45 SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45 SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B543	092316 08:45 SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45 SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B533	092316 08:40 SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B534	092316 08:40 SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B535	092316 08:40 SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B540	092316 08:40 SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B544	092316 08:40 SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B545	092316 08:40 SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40 SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B904	011018 09:40 SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00 SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B905	011818 12:20 SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B954	030618 09:15_SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B986	030618 09:15_SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1242	063018 10:00_SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1243	063018 10:00_SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1244	070318 09:15_SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1220	070318 09:15_SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1223	070318 09:15_7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15_SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1257	071218 09:15_SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-008	071218 09:15_SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-009	071218 09:15_SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-019	071318 09:15_SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-020	071318 09:15_SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50_SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15_SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1500	082218 09:15_SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0023 UT	< 0.0042 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 UT
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.00069 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00049 U	< 0.00052 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-EN4-3	073118 08:50_E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-3	080118 09:00_W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30_E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-CS-02	081018 09:00_CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50_WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-4	073118 08:50_G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30_E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-3	073118 08:50_G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.0043 U	< 0.0045 U	< 0.0028 U	< 0.0034 U	< 0.0027 U	< 0.0024 U	< 0.0025 U	< 0.0042 U
Rear Parking Lot	SSHS-N-E-1	080718 09:00_N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0039 U	< 0.0041 U	< 0.0025 U	< 0.0031 U	< 0.0024 U	< 0.0022 U	< 0.0023 U	< 0.0038 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0043 U	< 0.0045 U	< 0.0028 U	< 0.0034 U	< 0.0027 U	< 0.0024 U	< 0.0025 U	< 0.0042 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50_E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-CS-01	081018 09:00_CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-3	073118 08:50_E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-P-4	081018 09:00_P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-04	081018 09:00_WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.0018 U		< 0.0015 U	< 0.0013 U	< 0.0011 U	< 0.0014 U	< 0.0013 U	< 0.0014 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.00083 U		< 0.00069 U	< 0.00059 U	< 0.00053 U	< 0.00067 U	< 0.00059 U	< 0.00063 U
Rear Parking Lot	SSHS-B126	080115 09:10_SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B117A	080615 11:15_SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15_SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30_SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B378	030916 11:30_SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30_SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B391	031116 09:30_SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B392	031116 09:30_SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B395	031116 09:30_SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B396	031116 09:30_SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45_SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B533	092316 08:40_SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40_SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B535	092316 08:40_SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B540	092316 08:40_SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B544	092316 08:40_SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40_SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40_SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B905	011818 12:20_SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	**2-Hexanone (MBK)**	**Isopropylbenzene**	**Methyl Acetate**	**Methylcyclohexane**	**Methyl Ethyl Ketone**	**4-Methyl-2-pentanone**	**Methyl-tert-butyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B954	030618 09:15_SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B986	030618 09:15_SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1242	063018 10:00_SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1243	063018 10:00_SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1244	070318 09:15_SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1220	070318 09:15_SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1223	070318 09:15_7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1236	070318 09:15_SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated								
Rear Parking Lot	SSHS-B1257	071218 09:15_SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-008	071218 09:15_SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-009	071218 09:15_SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated								
Rear Parking Lot	SSHS-SW-019	071318 09:15_SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-SW-020	071318 09:15_SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-B1245	073118 08:50_SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15_SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B1500	082218 09:15_SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0021 U	< 0.0016 UJ	< 0.0027 UT	< 0.0076 U	< 0.0025 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.00087 U	< 0.00056 U	< 0.00055 U	< 0.00073 U	< 0.00059 U	< 0.00072 U	< 0.00053 U	< 0.00061 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-EN4-3	073118 08:50_E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-W6-3	080118 09:00_W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30_E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-CS-02	081018 09:00_CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50_WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated								
Rear Parking Lot	SSHS-GS3-4	073118 08:50_G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30_E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated								
Rear Parking Lot	SSHS-GS2-3	073118 08:50_G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.0052 U	< 0.0046 U	< 0.0042 U	< 0.0081 U	< 0.0039 U	< 0.011 U	< 0.0032 U	< 0.0032 U
Rear Parking Lot	SSHS-N-E-1	080718 09:00_N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0047 U	< 0.0042 U	< 0.0038 U	< 0.0074 U	< 0.0035 U	< 0.0098 U	< 0.0029 U	< 0.0029 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0051 U	< 0.0046 U	< 0.0042 U	< 0.0081 U	< 0.0039 U	< 0.011 U	< 0.0032 U	< 0.0032 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50_E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-CS-01	081018 09:00_CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-EN2-3	073118 08:50_E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-P-4	081018 09:00_P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-04	081018 09:00_WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.0022 U	< 0.0015 U	< 0.0014 U	< 0.0019 U	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0016 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.001 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00071 U	< 0.00087 U	< 0.00064 U	< 0.00073 U
Rear Parking Lot	SSHS-B126	080115 09:10_SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated								
Rear Parking Lot	SSHS-B106A	080615 11:15_CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B106A	080615 11:15_SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated								
Rear Parking Lot	SSHS-B117A	080615 11:15_SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated								
Rear Parking Lot	SSHS-B160A	080615 11:15_SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated								
Rear Parking Lot	SSHS-B371	030916 11:30_SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B378	030916 11:30_SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B394	030916 11:30_PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B394	030916 11:30_SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated								
Rear Parking Lot	SSHS-B373	031116 09:30_SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B390	031116 09:30_PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B390	031116 09:30_SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B391	031116 09:30_SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B392	031116 09:30_SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B395	031116 09:30_SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-B396	031116 09:30_SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated								
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45_PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B536	092316 08:45_SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B552	092316 08:45_SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated								
Rear Parking Lot	SSHS-B533	092316 08:40_SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B534	092316 08:40_SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B535	092316 08:40_SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B540	092316 08:40_SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B544	092316 08:40_SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B550	092316 08:40_SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated								
Rear Parking Lot	SSHS-B904	011018 09:40_SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated								
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated								
Rear Parking Lot	SSHS-B905	011818 12:20_SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B954	030618 09:15_SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B986	030618 09:15_SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B1242	063018 10:00_SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1243	063018 10:00_SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1244	070318 09:15_SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1220	070318 09:15_SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1223	070318 09:15_7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1236	070318 09:15_SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated						
Rear Parking Lot	SSHS-B1257	071218 09:15_SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-008	071218 09:15_SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-009	071218 09:15_SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated						
Rear Parking Lot	SSHS-SW-019	071318 09:15_SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-SW-020	071318 09:15_SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B1245	073118 08:50_SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15_SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B1500	082218 09:15_SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 UT
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00069 U	< 0.00072 U	< 0.0004 U
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-EN4-3	073118 08:50_E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-3	080118 09:00_W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30_E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-CS-02	081018 09:00_CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50_WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-4	073118 08:50_G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30_E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-3	073118 08:50_G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.0037 U	< 0.0042 U	< 0.0042 U	< 0.0042 U	< 0.0030 U	< 0.0028 U	< 0.0018 UT
Rear Parking Lot	SSHS-N-E-1	080718 09:00_N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0033 U	< 0.0038 U	< 0.0038 U	< 0.0038 U	< 0.0028 U	< 0.0025 U	< 0.0017 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0037 U	< 0.0042 U	< 0.0042 U	< 0.0042 U	< 0.0030 U	< 0.0028 U	< 0.0018 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50_E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-CS-01	081018 09:00_CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-3	073118 08:50_E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-P-4	081018 09:00_P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-04	081018 09:00_WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.0015 U	< 0.0015 U	< 0.0014 U	< 0.0015 U	< 0.0018 U	< 0.0019 U	< 0.001 U
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.00069 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U	< 0.00048 U
Rear Parking Lot	SSHS-B126	080115 09:10_SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B117A	080615 11:15_SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15_SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30_SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B378	030916 11:30_SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30_SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B391	031116 09:30_SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B392	031116 09:30_SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B395	031116 09:30_SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B396	031116 09:30_SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45_SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B533	092316 08:40_SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40_SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B535	092316 08:40_SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B540	092316 08:40_SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B544	092316 08:40_SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40_SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40_SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B905	011818 12:20_SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-6-8	SSHS-B977-SUB-6-8	3/1/2018	851.96	852.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B954	030618 09:15_SSHS-B954-SUB-6-8	SSHS-B954-SUB-6-8	3/5/2018	851.89	853.01	1.12	-	6 - 8 ft	7.12-9.12 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-6-8	SSHS-B978-SUB-6-8	3/5/2018	852.09	852.56	0.47	-	6 - 8 ft	6.47-8.47 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B986	030618 09:15_SSHS-B986-SUB-6-8	SSHS-B986-SUB-6-8	3/5/2018	852.00	852.41	0.41	-	6 - 8 ft	6.41-8.41 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1242	063018 10:00_SSHS-B1242-SUB-6-8	SSHS-B1242-SUB-6-8	6/29/2018	851.78	852.83	1.05	-	6 - 8 ft	7.05-9.05 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1243	063018 10:00_SSHS-B1243-SUB-6-8	SSHS-B1243-SUB-6-8	6/29/2018	851.53	852.30	0.77	-	6 - 8 ft	6.77-8.77 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1244	070318 09:15_SSHS-B1244-SUB-6-8	SSHS-B1244-SUB-6-8	7/1/2018	848.20	849.22	1.02	-	6 - 8 ft	7.02-9.02 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1220	070318 09:15_SSHS-B1220-SUB-6-8	SSHS-B1220-SUB-6-8	7/2/2018	852.30	852.77	0.47	-	6 - 8 ft	6.47-8.47 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1223	070318 09:15_7-2-FD-1	7-2-FD-1	7/2/2018	850.41	850.59	0.18	-	6 - 8 ft	6.18-8.18 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1236	070318 09:15_SSHS-B1236-SUB-6-8	SSHS-B1236-SUB-6-8	7/2/2018	850.26	850.34	0.08	-	6 - 8 ft	6.08-8.08 ft	180-79440-1	Not Excavated							
Rear Parking Lot	SSHS-B1257	071218 09:15_SSHS-B1257-SUB-6-8-BOT	SSHS-B1257-SUB-6-8-BOT	7/10/2018	852.90	853.50	0.60	-	6 - 8 ft	6.60-8.60 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-008	071218 09:15_SW-008-6-8	SW-008-6-8	7/11/2018	-	852.86	-	845.50	6 - 8 ft	7.36 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-009	071218 09:15_SW-009-6-8	SW-009-6-8	7/11/2018	-	852.79	-	844.90	6 - 8 ft	7.89 ft	180-79670-1	Not Excavated							
Rear Parking Lot	SSHS-SW-019	071318 09:15_SW-019-6-8	SW-019-6-8	7/12/2018	-	852.75	-	846.90	6 - 8 ft	5.85 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-SW-020	071318 09:15_SW-020-6-8	SW-020-6-8	7/12/2018	-	852.74	-	845.30	6 - 8 ft	7.44 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-B1245	073118 08:50_SSHS-B1245-SUB-6-8	SSHS-B1245-SUB-6-8	7/28/2018	849.10	850.00	0.90	-	6 - 8 ft	6.90-8.90 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-SS-05_8_20	082218 09:15_SS-05 (6-8) 20180820	SS-05 (6-8) 20180820	8/20/2018	-	847.85	-	842.10	6 - 8 ft	5.75 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B1500	082218 09:15_SSHS-B1500 (6-8) 20180821	SSHS-B1500 (6-8) 20180821	8/21/2018	-	847.03	-	-	6 - 8 ft	6-8 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-6-8	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	6 - 8 ft	6 - 8 ft	180-124920-1	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8-20230209	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 0.0010 U	< 0.0016 UT	< 0.0043 U	< 0.0037 U	< 0.0018 UT	< 0.0021 UT	< 0.0074 UT
Rear Parking Lot	SSHS-B64	081514 01:15_SSHS-B64-6-9 (9)	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated	< 0.00068 U	< 0.00053 U	< 0.00075 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
Rear Parking Lot	CS-02-19	CS-02-19-20190624	CS-02-19	6/24/2019	-	852.74	-	846.74	6 ft	6 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-EN4-3	073118 08:50_E-N-4-3	E-N-4-3	7/26/2018	-	853.36	-	846.00	6.1 - 6.1 ft	7.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-W6-3	080118 09:00_W6-3	W6-3	7/27/2018	-	851.33	-	844.90	6.2 - 6.2 ft	6.43 ft	180-80306-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-1-4	080418 11:30_E-S-1-4	E-S-1-4	8/3/2018	-	852.30	-	845.90	6.2 - 6.2 ft	6.40 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-CS-02	081018 09:00_CS-02	CS-02	8/9/2018	-	850.00	-	843.40	6.4 - 6.4 ft	6.60 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WWN_7_21	072418 08:50_WWN	WWN	7/21/2018	-	852.77	-	845.30	6.5 - 6.5 ft	7.47 ft	180-80092-1	Not Excavated							
Rear Parking Lot	SSHS-GS3-4	073118 08:50_G-S-3-4	G-S-3-4	7/26/2018	-	852.79	-	845.80	6.5 - 6.5 ft	6.99 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-E-S-9-4	080418 11:30_E-S-9-4	E-S-9-4	8/3/2018	-	852.28	-	848.80	6.5 - 6.5 ft	3.48 ft	180-80462-1	Not Excavated							
Rear Parking Lot	SSHS-GS2-3	073118 08:50_G-S-2-3	G-S-2-3	7/26/2018	-	852.75	-	845.70	6.6 - 6.6 ft	7.05 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842-20240812	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated	< 0.0029 U	< 0.0030 U	< 0.0046 U	< 0.0040 UT	< 0.0043 U	< 0.0038 U	< 0.0080 U
Rear Parking Lot	SSHS-N-E-1	080718 09:00_N-E-1	N-E-1	8/6/2018	-	852.76	-	845.60	6.7 - 6.7 ft	7.16 ft	180-80512-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05-20240813	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0026 U	< 0.0027 U	< 0.0042 U	< 0.0036 U	< 0.0039 U	< 0.0035 U	< 0.0072 U
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844-20240813	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated	< 0.0029 U	< 0.0030 U	< 0.0046 U	< 0.0040 U	< 0.0043 U	< 0.0038 U	< 0.0080 U
Rear Parking Lot	SSHS-EN3-4	073118 08:50_E-N-3-4	E-N-3-4	7/26/2018	-	853.26	-	845.30	6.9 - 6.9 ft	7.96 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SPA4-B5526	SSHS-SPA4-B5526-ELEV-844-842-20240813	SSHS-SPA4-B5526-ELEV-844-842	8/13/2024	851.21	851.21	0.00	-	7.21-9.21 ft	7.21-9.21 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-CS-01	081018 09:00_CS-01	CS-01	8/9/2018	-	851.05	-	843.30	7.3 - 7.3 ft	7.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-EN2-3	073118 08:50_E-N-2-3	E-N-2-3	7/26/2018	-	853.14	-	844.70	7.6 - 7.7 ft	8.44 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-P2	071318 09:15_SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-P-4	081018 09:00_P-4	P-4	8/9/2018	-	849.64	-	841.80	7.7 - 7.7 ft	7.84 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-04	081018 09:00_WL-04	WL-04	8/9/2018	-	849.50	-	841.70	7.8 - 7.8 ft	7.80 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-B101	081514 01:15_SSHS-B101-8-10 (9)	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated	< 0.0017 U	0.0087 J	< 0.0019 U	< 0.00099 U	< 0.0031 U	< 0.0016 U	
Rear Parking Lot	SSHS-B65	081514 01:15_SSHS-B65-8-10 (9)	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated	< 0.00082 U	< 0.00065 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Rear Parking Lot	SSHS-B126	080115 09:10_SSHS-B126-SUB-8-10	SSHS-B126-SUB-8-10	7/31/2015	850.94	850.82	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-46444-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_CS-FD-#21	CS-FD-#21	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B106A	080615 11:15_SSHS-B106A-SUB-8-10	SSHS-B106A-SUB-8-10	8/3/2015	849.39	849.17	-0.22	-	8 - 10 ft	7.78-9.78 ft	180-46601-1	Not Excavated							
Rear Parking Lot	SSHS-B117A	080615 11:15_SSHS-B117A-SUB-8-10	SSHS-B117A-SUB-8-10	8/3/2015	850.60	850.42	-0.18	-	8 - 10 ft	7.82-9.82 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B160A	080615 11:15_SSHS-B160A-SUB-8-10	SSHS-B160A-SUB-8-10	8/3/2015	852.12	852.20	0.08	-	8 - 10 ft	8.08-10.08 ft	180-46601-2	Not Excavated							
Rear Parking Lot	SSHS-B371	030916 11:30_SSHS-B371-SUB-8-10	SSHS-B371-SUB-8-10	3/8/2016	852.79	852.76	-0.03	-	8 - 10 ft	7.97-9.97 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B378	030916 11:30_SSHS-B378-SUB-8-10	SSHS-B378-SUB-8-10	3/8/2016	850.73	850.50	-0.23	-	8 - 10 ft	7.77-9.77 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_PS-FD-18	PS-FD-18	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B394	030916 11:30_SSHS-B394-SUB-8-10	SSHS-B394-SUB-8-10	3/8/2016	851.52	851.47	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-52813-1	Not Excavated							
Rear Parking Lot	SSHS-B373	031116 09:30_SSHS-B373-SUB-8-10	SSHS-B373-SUB-8-10	3/10/2016	852.56	852.68	0.12	-	8 - 10 ft	8.12-10.12 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_PS-FD-25	PS-FD-25	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B390	031116 09:30_SSHS-B390-SUB-8-10	SSHS-B390-SUB-8-10	3/10/2016	851.95	852.16	0.21	-	8 - 10 ft	8.21-10.21 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B391	031116 09:30_SSHS-B391-SUB-8-10	SSHS-B391-SUB-8-10	3/10/2016	849.56	849.52	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B392	031116 09:30_SSHS-B392-SUB-8-10	SSHS-B392-SUB-8-10	3/10/2016	850.00	849.45	-0.55	-	8 - 10 ft	7.45-9.45 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B395	031116 09:30_SSHS-B395-SUB-8-10	SSHS-B395-SUB-8-10	3/10/2016	851.50	851.82	0.32	-	8 - 10 ft	8.32-10.32 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-B396	031116 09:30_SSHS-B396-SUB-8-10	SSHS-B396-SUB-8-10	3/10/2016	850.83	851.09	0.26	-	8 - 10 ft	8.26-10.26 ft	180-52921-1	Not Excavated							
Rear Parking Lot	SSHS-MW-46	090216 08:45_SSHS-MW46-SUB-8-10	SSHS-MW46-SUB-8-10	8/30/2016	850.92	850.97	0.05	-	8 - 10 ft	8.05-10.05 ft	180-58275-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_PS-FD-32	PS-FD-32	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B536	092316 08:45_SSHS-B536-SUB-8-10	SSHS-B536-SUB-8-10	9/21/2016	852.47	853.03	0.56	-	8 - 10 ft	8.56-10.56 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B543	092316 08:45_SSHS-B543-SUB-8-10	SSHS-B543-SUB-8-10	9/21/2016	851.17	851.32	0.15	-	8 - 10 ft	8.15-10.15 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B552	092316 08:45_SSHS-B552-SUB-8-10	SSHS-B552-SUB-8-10	9/21/2016	853.01	853.17	0.16	-	8 - 10 ft	8.16-10.16 ft	180-59020-1	Not Excavated							
Rear Parking Lot	SSHS-B533	092316 08:40_SSHS-B533-SUB-8-10	SSHS-B533-SUB-8-10	9/22/2016	852.02	852.38	0.36	-	8 - 10 ft	8.36-10.36 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B534	092316 08:40_SSHS-B534-SUB-8-10	SSHS-B534-SUB-8-10	9/22/2016	852.33	852.53	0.20	-	8 - 10 ft	8.2-10.2 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B535	092316 08:40_SSHS-B535-SUB-8-10	SSHS-B535-SUB-8-10	9/22/2016	851.76	851.82	0.06	-	8 - 10 ft	8.06-10.06 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B540	092316 08:40_SSHS-B540-SUB-8-10	SSHS-B540-SUB-8-10	9/22/2016	851.56	851.74	0.18	-	8 - 10 ft	8.18-10.18 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B544	092316 08:40_SSHS-B544-SUB-8-10	SSHS-B544-SUB-8-10	9/22/2016	851.21	851.02	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B545	092316 08:40_SSHS-B545-SUB-8-10	SSHS-B545-SUB-8-10	9/22/2016	850.94	850.75	-0.19	-	8 - 10 ft	7.81-9.81 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B550	092316 08:40_SSHS-B550-SUB-8-10	SSHS-B550-SUB-8-10	9/22/2016	851.35	851.20	-0.15	-	8 - 10 ft	7.85-9.85 ft	180-59029-1	Not Excavated							
Rear Parking Lot	SSHS-B904	011018 09:40_SSHS-B904-SUB-8-10	SSHS-B904-SUB-8-10	1/9/2018	852.40	852.89	0.49	-	8 - 10 ft	8.49-10.49 ft	180-74014-2	Not Excavated							
Rear Parking Lot	SSHS-B889	011718 12:00_SSHS-B889-SUB-8-10	SSHS-B889-SUB-8-10	1/12/2018	851.80	852.52	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74207-1	Not Excavated							
Rear Parking Lot	SSHS-B905	011818 12:20_SSHS-B905-SUB-8-10	SSHS-B905-SUB-8-10	1/17/2018	850.00	850.04	0.04	-	8 - 10 ft	8.04-10.04 ft	180-74241-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30_PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated							
Rear Parking Lot	SSHS-B930	012418 09:30 SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated							
Rear Parking Lot	SSHS-B942	012518 09:00 SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B956	030118 10:00 SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B957	030118 10:00 SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B960	030118 10:00 SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B998	030118 10:00 SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B992	030618 09:15 SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B961	030618 09:15 SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15 SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15_PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15 SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1017	042518 09:00 SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1018	042518 09:00 SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1020	042718 08:50_PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1020	042718 08:50 SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1084	062918 09:20 SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated							
Rear Parking Lot	SSHS-B1234	062918 09:20 SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated							
Rear Parking Lot	SSHS-B1109	063018 10:00 SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1224	070318 09:15 SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1237	070318 09:15 SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1162	070718 09:30 SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1158	070718 09:30 SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1198	070718 09:30 SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1373	072518 09:00 SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-B1253	073118 08:50 SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1501	081118 09:00 SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated							
Rear Parking Lot	SSHS-SS-06_8_20	082218 09:15 SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-13_8_20	082218 09:15 SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated							
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-BE-2	073118 08:50 B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-BE-3	073118 08:50 B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-WL-03	081018 09:00 WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-01	081018 09:00 WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-P-3	081018 09:00 P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-02	081018 09:00 WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00 BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-P-2	081018 09:00 P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-SS-10_8_20	082218 09:15 SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-11_8_20	082218 09:15 SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-15_8_20	082218 09:15 SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-PW-1	080818 09:00 PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated							
Rear Parking Lot	SSHS-PE-1	080818 09:00 PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated							
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00 BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35 SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35 SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35 SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15 SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated						
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated						
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated						
Rear Parking Lot	SSHS-B848	012418 09:30_SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B881	012418 09:30_SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated						
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated						
Rear Parking Lot	SSHS-B890	012418 09:30_PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated						
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated						
Rear Parking Lot	SSHS-B930	012418 09:30_SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated						
Rear Parking Lot	SSHS-B942	012518 09:00_SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated						
Rear Parking Lot	SSHS-B955	030118 10:00_SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B956	030118 10:00_SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B959	030118 10:00_SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B960	030118 10:00_SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B998	030118 10:00_SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B961	030618 09:15_SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B989	030618 09:15_PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1020	042718 08:50_PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated						
Rear Parking Lot	SSHS-B1020	042718 08:50_SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated						
Rear Parking Lot	SSHS-B1084	062918 09:20_SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated						
Rear Parking Lot	SSHS-B1234	062918 09:20_SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated						
Rear Parking Lot	SSHS-B1109	063018 10:00_SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1224	070318 09:15_SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1237	070318 09:15_SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1162	070718 09:30_SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1158	070718 09:30_SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1373	072518 09:00_SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated						
Rear Parking Lot	SSHS-B1253	073118 08:50_SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-B1501	081118 09:00_SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated						
Rear Parking Lot	SSHS-SS-06_8_20	082218 09:15_SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-13_8_20	082218 09:15_SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated						
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UJ	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	1809185571	Not Excavated						
Rear Parking Lot	SSHS-BE-2	073118 08:50_B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-BE-3	073118 08:50_B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-WL-03	081018 09:00_WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-WL-01	081018 09:00_WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-P-3	081018 09:00_P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-WL-02	081018 09:00_WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated						
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00_BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-P-2	081018 09:00_P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-SS-10_8_20	082218 09:15_SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-11_8_20	082218 09:15_SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-15_8_20	082218 09:15_SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-PW-1	080818 09:00_PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated						
Rear Parking Lot	SSHS-PE-1	080818 09:00_PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated						
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00_BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35_SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35_SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15_SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated						

DRAFT

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30 PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated								
Rear Parking Lot	SSHS-B930	012418 09:30 SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated								
Rear Parking Lot	SSHS-B942	012518 09:00 SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B956	030118 10:00 SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B957	030118 10:00 SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B960	030118 10:00 SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B998	030118 10:00 SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B992	030618 09:15 SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B961	030618 09:15 SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15 SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15 PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15 SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1017	042518 09:00 SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1018	042518 09:00 SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1020	042718 08:50 PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1020	042718 08:50 SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1084	062918 09:20 SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated								
Rear Parking Lot	SSHS-B1234	062918 09:20 SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated								
Rear Parking Lot	SSHS-B1109	063018 10:00 SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1224	070318 09:15 SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1237	070318 09:15 SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1162	070718 09:30 SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1158	070718 09:30 SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1198	070718 09:30 SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1373	072518 09:00 SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-B1253	073118 08:50 SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1501	081118 09:00 SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated								
Rear Parking Lot	SSHS-SS-06 8 20	082218 09:15 SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-13 8 20	082218 09:15 SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0046 U	< 0.0014 U	< 0.0026 UT	< 0.0017 U	< 0.0032 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-BE-2	073118 08:50 B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-BE-3	073118 08:50 B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-WL-03	081018 09:00 WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-01	081018 09:00 WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-P-3	081018 09:00 P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-02	081018 09:00 WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00 BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-P-2	081018 09:00 P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-SS-10 8 20	082218 09:15 SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-11 8 20	082218 09:15 SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-15 8 20	082218 09:15 SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-PW-1	080818 09:00 PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated								
Rear Parking Lot	SSHS-PE-1	080818 09:00 PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated								
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00 BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35 SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35 SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35 SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15 SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30 PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated								
Rear Parking Lot	SSHS-B930	012418 09:30 SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated								
Rear Parking Lot	SSHS-B942	012518 09:00 SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B956	030118 10:00 SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B957	030118 10:00 SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B960	030118 10:00 SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B998	030118 10:00 SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B992	030618 09:15 SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B961	030618 09:15 SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15 SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15 PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15 SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1017	042518 09:00 SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1018	042518 09:00 SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1020	042718 08:50 PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1020	042718 08:50 SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1084	062918 09:20 SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated								
Rear Parking Lot	SSHS-B1234	062918 09:20 SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated								
Rear Parking Lot	SSHS-B1109	063018 10:00 SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1224	070318 09:15 SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1237	070318 09:15 SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1162	070718 09:30 SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1158	070718 09:30 SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1198	070718 09:30 SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1373	072518 09:00 SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-B1253	073118 08:50 SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1501	081118 09:00 SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated								
Rear Parking Lot	SSHS-SS-06 8 20	082218 09:15 SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-13 8 20	082218 09:15 SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0023 UT	< 0.0042 UT	< 0.0016 UT	< 0.0018 UT	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 UT
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-BE-2	073118 08:50 B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-BE-3	073118 08:50 B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-WL-03	081018 09:00 WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-01	081018 09:00 WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-P-3	081018 09:00 P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-02	081018 09:00 WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00 BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-P-2	081018 09:00 P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-SS-10 8 20	082218 09:15 SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-11 8 20	082218 09:15 SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-15 8 20	082218 09:15 SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-PW-1	080818 09:00 PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated								
Rear Parking Lot	SSHS-PE-1	080818 09:00 PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated								
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00 BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35 SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35 SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35 SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15 SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated								
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated								
Rear Parking Lot	SSHS-B848	012418 09:30_SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated								
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated								
Rear Parking Lot	SSHS-B881	012418 09:30_SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated								
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30_PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated								
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated								
Rear Parking Lot	SSHS-B930	012418 09:30_SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated								
Rear Parking Lot	SSHS-B942	012518 09:00_SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated								
Rear Parking Lot	SSHS-B955	030118 10:00_SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B956	030118 10:00_SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B959	030118 10:00_SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B960	030118 10:00_SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated								
Rear Parking Lot	SSHS-B998	030118 10:00_SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated								
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated								
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B961	030618 09:15_SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15_PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated								
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated								
Rear Parking Lot	SSHS-B1020	042718 08:50_PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1020	042718 08:50_SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated								
Rear Parking Lot	SSHS-B1084	062918 09:20_SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated								
Rear Parking Lot	SSHS-B1234	062918 09:20_SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated								
Rear Parking Lot	SSHS-B1109	063018 10:00_SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated								
Rear Parking Lot	SSHS-B1224	070318 09:15_SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1237	070318 09:15_SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated								
Rear Parking Lot	SSHS-B1162	070718 09:30_SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1158	070718 09:30_SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated								
Rear Parking Lot	SSHS-B1373	072518 09:00_SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated								
Rear Parking Lot	SSHS-B1253	073118 08:50_SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated								
Rear Parking Lot	SSHS-B1501	081118 09:00_SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated								
Rear Parking Lot	SSHS-SS-06_8_20	082218 09:15_SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-13_8_20	082218 09:15_SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated								
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated								
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0021 U	< 0.0016 UJ	< 0.0027 UT	< 0.0076 U	< 0.0025 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated								
Rear Parking Lot	SSHS-BE-2	073118 08:50_B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-BE-3	073118 08:50_B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated								
Rear Parking Lot	SSHS-WL-03	081018 09:00_WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-01	081018 09:00_WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-P-3	081018 09:00_P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-WL-02	081018 09:00_WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated								
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00_BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated								
Rear Parking Lot	SSHS-P-2	081018 09:00_P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated								
Rear Parking Lot	SSHS-SS-10_8_20	082218 09:15_SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-11_8_20	082218 09:15_SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-SS-15_8_20	082218 09:15_SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated								
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated								
Rear Parking Lot	SSHS-PW-1	080818 09:00_PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated								
Rear Parking Lot	SSHS-PE-1	080818 09:00_PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated								
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00_BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35_SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35_SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15_SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated								

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Rear Parking Lot	SSHS-B839	011918 10:00 SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated						
Rear Parking Lot	SSHS-B843	012018 09:00 SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated						
Rear Parking Lot	SSHS-B911	012018 09:00 SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated						
Rear Parking Lot	SSHS-B848	012418 09:30 SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B878	012418 09:30 SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated						
Rear Parking Lot	SSHS-B842	012418 09:30 SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated						
Rear Parking Lot	SSHS-B881	012418 09:30 SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated						
Rear Parking Lot	SSHS-B850	012418 09:30 SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated						
Rear Parking Lot	SSHS-B890	012418 09:30 PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated						
Rear Parking Lot	SSHS-B890	012418 09:30 SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated						
Rear Parking Lot	SSHS-B930	012418 09:30 SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated						
Rear Parking Lot	SSHS-B942	012518 09:00 SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated						
Rear Parking Lot	SSHS-B955	030118 10:00 SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B956	030118 10:00 SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B957	030118 10:00 SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B959	030118 10:00 SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B960	030118 10:00 SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B981	030118 10:00 SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated						
Rear Parking Lot	SSHS-B998	030118 10:00 SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated						
Rear Parking Lot	SSHS-B973	030218 09:10 SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B977	030218 09:10 SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated						
Rear Parking Lot	SSHS-B992	030618 09:15 SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B961	030618 09:15 SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B978	030618 09:15 SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated						
Rear Parking Lot	SSHS-B989	030618 09:15 PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B989	030618 09:15 SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated						
Rear Parking Lot	SSHS-B1017	042518 09:00 SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1018	042518 09:00 SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated						
Rear Parking Lot	SSHS-B1020	042718 08:50 PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated						
Rear Parking Lot	SSHS-B1020	042718 08:50 SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated						
Rear Parking Lot	SSHS-B1084	062918 09:20 SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated						
Rear Parking Lot	SSHS-B1234	062918 09:20 SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated						
Rear Parking Lot	SSHS-B1109	063018 10:00 SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated						
Rear Parking Lot	SSHS-B1224	070318 09:15 SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1237	070318 09:15 SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated						
Rear Parking Lot	SSHS-B1162	070718 09:30 SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1158	070718 09:30 SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1198	070718 09:30 SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated						
Rear Parking Lot	SSHS-B1373	072518 09:00 SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated						
Rear Parking Lot	SSHS-B1253	073118 08:50 SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated						
Rear Parking Lot	SSHS-B1501	081118 09:00 SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated						
Rear Parking Lot	SSHS-SS-06 8 20	082218 09:15 SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-13 8 20	082218 09:15 SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-B3824	072421 09:00 SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated						
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0015 U	< 0.0016 UJ	< 0.0021 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 UT
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated						
Rear Parking Lot	SSHS-BE-2	073118 08:50 B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-BE-3	073118 08:50 B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated						
Rear Parking Lot	SSHS-WL-03	081018 09:00 WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-WL-01	081018 09:00 WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-P-3	081018 09:00 P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-WL-02	081018 09:00 WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated						
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00 BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated						
Rear Parking Lot	SSHS-P-2	081018 09:00 P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated						
Rear Parking Lot	SSHS-SS-10 8 20	082218 09:15 SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-11 8 20	082218 09:15 SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-15 8 20	082218 09:15 SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-CS2	071318 09:15 SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-PW-1	080818 09:00 PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated						
Rear Parking Lot	SSHS-PE-1	080818 09:00 PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated						
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00 BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35 SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35 SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35 SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35 SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15 SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15 SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15 SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated						

DRAFT

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Rear Parking Lot	SSHS-B839	011918 10:00_SSHS-B839-SUB-8-10	SSHS-B839-SUB-8-10	1/18/2018	850.25	850.52	0.27	-	8 - 10 ft	8.27-10.27 ft	180-74307-1	Not Excavated							
Rear Parking Lot	SSHS-B843	012018 09:00_SSHS-B843-SUB-8-10	SSHS-B843-SUB-8-10	1/19/2018	851.40	851.34	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B911	012018 09:00_SSHS-B911-SUB-8-10	SSHS-B911-SUB-8-10	1/19/2018	850.80	850.99	0.19	-	8 - 10 ft	8.19-10.19 ft	180-74310-3	Not Excavated							
Rear Parking Lot	SSHS-B848	012418 09:30_SSHS-B848-SUB-8-10	SSHS-B848-SUB-8-10	1/20/2018	851.19	851.58	0.39	-	8 - 10 ft	8.39-10.39 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B878	012418 09:30_SSHS-B878-SUB-8-10	SSHS-B878-SUB-8-10	1/20/2018	851.47	851.87	0.40	-	8 - 10 ft	8.40-10.40 ft	180-74390-1	Not Excavated							
Rear Parking Lot	SSHS-B842	012418 09:30_SSHS-B842-SUB-8-10	SSHS-B842-SUB-8-10	1/22/2018	851.80	851.59	-0.21	-	8 - 10 ft	7.79-9.79 ft	180-74331-1	Not Excavated							
Rear Parking Lot	SSHS-B881	012418 09:30_SSHS-B881-SUB-8-10	SSHS-B881-SUB-8-10	1/22/2018	848.90	849.62	0.72	-	8 - 10 ft	8.72-10.72 ft	180-74331-3	Not Excavated							
Rear Parking Lot	SSHS-B850	012418 09:30_SSHS-B850-SUB-8-10	SSHS-B850-SUB-8-10	1/23/2018	850.33	850.69	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-3	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30_PS-FD-38	PS-FD-38	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-1	Not Excavated							
Rear Parking Lot	SSHS-B890	012418 09:30_SSHS-B890-SUB-8-10	SSHS-B890-SUB-8-10	1/23/2018	851.90	852.26	0.36	-	8 - 10 ft	8.36-10.36 ft	180-74397-2	Not Excavated							
Rear Parking Lot	SSHS-B930	012418 09:30_SSHS-B930-SUB-8-10	SSHS-B930-SUB-8-10	1/23/2018	851.68	851.70	0.02	-	8 - 10 ft	8.02-10.02 ft	180-74397-3	Not Excavated							
Rear Parking Lot	SSHS-B942	012518 09:00_SSHS-B942-SUB-8-10	SSHS-B942-SUB-8-10	1/24/2018	851.00	850.61	-0.39	-	8 - 10 ft	7.61-9.61 ft	180-74436-1	Not Excavated							
Rear Parking Lot	SSHS-B955	030118 10:00_SSHS-B955-SUB-8-10	SSHS-B955-SUB-8-10	2/27/2018	853.70	853.92	0.22	-	8 - 10 ft	8.22-10.22 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B956	030118 10:00_SSHS-B956-SUB-8-10	SSHS-B956-SUB-8-10	2/27/2018	852.70	852.91	0.21	-	8 - 10 ft	8.21-10.21 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B957	030118 10:00_SSHS-B957-SUB-8-10	SSHS-B957-SUB-8-10	2/28/2018	852.80	852.80	0.00	-	8 - 10 ft	8-10 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B959	030118 10:00_SSHS-B959-SUB-8-10	SSHS-B959-SUB-8-10	2/28/2018	851.40	851.14	-0.26	-	8 - 10 ft	7.74-9.74 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B960	030118 10:00_SSHS-B960-SUB-8-10	SSHS-B960-SUB-8-10	2/28/2018	850.97	850.85	-0.12	-	8 - 10 ft	7.88-9.88 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B981	030118 10:00_SSHS-B981-SUB-8-10	SSHS-B981-SUB-8-10	2/28/2018	851.85	852.05	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75403-1	Not Excavated							
Rear Parking Lot	SSHS-B998	030118 10:00_SSHS-B998-SUB-8-10	SSHS-B998-SUB-8-10	2/28/2018	851.30	850.55	-0.75	-	8 - 10 ft	7.25-9.25 ft	180-75403-2	Not Excavated							
Rear Parking Lot	SSHS-B973	030218 09:10_SSHS-B973-SUB-8-10	SSHS-B973-SUB-8-10	3/1/2018	852.19	852.39	0.20	-	8 - 10 ft	8.20-10.20 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B977	030218 09:10_SSHS-B977-SUB-8-10	SSHS-B977-SUB-8-10	3/1/2018	851.96	852.03	0.07	-	8 - 10 ft	8.07-10.07 ft	180-75478-1	Not Excavated							
Rear Parking Lot	SSHS-B992	030618 09:15_SSHS-B992-SUB-8-10	SSHS-B992-SUB-8-10	3/4/2018	852.95	853.53	0.58	-	8 - 10 ft	8.58-10.58 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B961	030618 09:15_SSHS-B961-SUB-8-10	SSHS-B961-SUB-8-10	3/5/2018	850.20	850.07	-0.13	-	8 - 10 ft	7.87-9.87 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B978	030618 09:15_SSHS-B978-SUB-8-10	SSHS-B978-SUB-8-10	3/5/2018	852.09	852.56	0.47	-	8 - 10 ft	8.47-10.47 ft	180-75545-2	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15_PS-FD-16	PS-FD-16	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B989	030618 09:15_SSHS-B989-SUB-8-10	SSHS-B989-SUB-8-10	3/5/2018	853.10	853.59	0.49	-	8 - 10 ft	8.49-10.49 ft	180-75545-1	Not Excavated							
Rear Parking Lot	SSHS-B1017	042518 09:00_SSHS-B1017-SUB-8-10	SSHS-B1017-SUB-8-10	4/24/2018	853.03	853.47	0.44	-	8 - 10 ft	8.44-10.44 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1018	042518 09:00_SSHS-B1018-SUB-8-10	SSHS-B1018-SUB-8-10	4/24/2018	852.50	852.75	0.25	-	8 - 10 ft	8.25-10.25 ft	180-77059-1	Not Excavated							
Rear Parking Lot	SSHS-B1020	042718 08:50_PS-FD-04	PS-FD-04	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1020	042718 08:50_SSHS-B1020-SUB-8-10	SSHS-B1020-SUB-8-10	4/26/2018	851.20	850.89	-0.31	-	8 - 10 ft	7.69-9.69 ft	180-77189-1	Not Excavated							
Rear Parking Lot	SSHS-B1084	062918 09:20_SSHS-B1084-SUB-8-10	SSHS-B1084-SUB-8-10	6/28/2018	853.50	853.60	0.10	-	8 - 10 ft	8.10-10.10 ft	180-79394-1	Not Excavated							
Rear Parking Lot	SSHS-B1234	062918 09:20_SSHS-B1234-SUB-8-10	SSHS-B1234-SUB-8-10	6/28/2018	852.60	852.88	0.28	-	8 - 10 ft	8.28-10.28 ft	180-79394-1	Not Excavated							
Rear Parking Lot	SSHS-B1109	063018 10:00_SSHS-B1109-SUB-8-10	SSHS-B1109-SUB-8-10	6/29/2018	851.50	851.68	0.18	-	8 - 10 ft	8.18-10.18 ft	180-79432-1	Not Excavated							
Rear Parking Lot	SSHS-B1224	070318 09:15_SSHS-B1224-SUB-8-10	SSHS-B1224-SUB-8-10	7/1/2018	850.64	850.30	-0.34	-	8 - 10 ft	7.66-9.66 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1237	070318 09:15_SSHS-B1237-SUB-8-10	SSHS-B1237-SUB-8-10	7/2/2018	849.85	849.99	0.14	-	8 - 10 ft	8.14-10.14 ft	180-79440-2	Not Excavated							
Rear Parking Lot	SSHS-B1162	070718 09:30_SSHS-B1162-SUB-8-10	SSHS-B1162-SUB-8-10	7/5/2018	850.38	850.67	0.29	-	8 - 10 ft	8.29-10.29 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1158	070718 09:30_SSHS-B1158-SUB-8-10	SSHS-B1158-SUB-8-10	7/6/2018	850.44	850.14	-0.30	-	8 - 10 ft	7.70-9.70 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1198	070718 09:30_SSHS-B1198-SUB-8-10	SSHS-B1198-SUB-8-10	7/6/2018	851.80	852.61	0.81	-	8 - 10 ft	8.81-10.81 ft	180-79550-1	Not Excavated							
Rear Parking Lot	SSHS-B1373	072518 09:00_SSHS-B1373-SUB-8-10	SSHS-B1373-SUB-8-10	7/24/2018	852.50	852.89	0.39	-	8 - 10 ft	8.39-10.39 ft	180-80110-1	Not Excavated							
Rear Parking Lot	SSHS-B1253	073118 08:50_SSHS-B1253-SUB-6-8	SSHS-B1253-SUB-6-8	7/28/2018	851.00	850.95	-0.05	-	8 - 10 ft	7.95-9.95 ft	180-80273-1	Not Excavated							
Rear Parking Lot	SSHS-B1501	081118 09:00_SSHS-B1501	SSHS-B1501	8/10/2018	-	850.97	-	844.30	8 - 10 ft	6.67 ft	180-80802-1	Not Excavated							
Rear Parking Lot	SSHS-SS-06_8_20	082218 09:15_SS-06 (8-10) 20180820	SS-06 (8-10) 20180820	8/20/2018	-	848.80	-	840.70	8 - 10 ft	8.10 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-13_8_20	082218 09:15_SS-13 (8-10) 20180820	SS-13 (8-10) 20180820	8/20/2018	-	847.92	-	840.90	8 - 10 ft	7.02 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-B3824	072421 09:00_SSHS-B3824-SUB-8-10	SSHS-B3824	7/23/2021	848.28	848.28	0.00	-	8 - 10 ft	8 - 10 ft	180-124920-1	Not Excavated							
Rear Parking Lot	STI-OS-SB-4A	STI-OS-SB-4A-SUB-8-10-20230130	STI-OS-SB-4A-SUB-8-10	1/30/2023	848.46	848.46	0.00	-	8 - 10 ft	8-10 ft	1801512611	Not Excavated							
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10-20230209	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 0.0010 U	< 0.0016 UT	< 0.0043 U	< 0.0037 U	< 0.0018 UT	< 0.0021 UT	< 0.0074 UT
Rear Parking Lot	CS-05-19	CS-05-19-20190624	CS-05-19	6/24/2019	-	852.60	-	844.60	8 ft	8 ft	180918571	Not Excavated							
Rear Parking Lot	SSHS-BE-2	073118 08:50_B-E-2	B-E-2	7/26/2018	-	853.18	-	844.20	8.2 - 8.2 ft	8.98 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-BE-3	073118 08:50_B-E-3	B-E-3	7/26/2018	-	853.26	-	843.90	8.3 - 8.3 ft	9.36 ft	180-80274-1	Not Excavated							
Rear Parking Lot	SSHS-WL-03	081018 09:00_WL-03	WL-03	8/9/2018	-	850.36	-	841.90	8.3 - 8.3 ft	8.46 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-01	081018 09:00_WL-01	WL-01	8/9/2018	-	851.58	-	842.80	8.4 - 8.4 ft	8.78 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-P-3	081018 09:00_P-3	P-3	8/9/2018	-	850.35	-	841.60	8.5 - 8.5 ft	8.75 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-WL-02	081018 09:00_WL-02	WL-02	8/9/2018	-	851.16	-	842.10	8.6 - 8.6 ft	9.06 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-844-842-20240813	SSHS-SPA4-B5527-ELEV-844-842	8/13/2024	852.76	852.76	0.00	-	8.76-10.76 ft	8.76-10.76 ft	1801783741	Not Excavated							
Rear Parking Lot	SSHS-B-F-E-3	080718 09:00_BFE-3	BFE-3	8/4/2018	-	852.10	-	843.10	8.8 - 8.8 ft	9 ft	180-80511-1	Not Excavated							
Rear Parking Lot	SSHS-P-2	081018 09:00_P-2	P-2	8/9/2018	-	850.92	-	841.70	8.8 - 8.8 ft	9.22 ft	180-80713-1	Not Excavated							
Rear Parking Lot	SSHS-SS-10_8_20	082218 09:15_SS-10 (8-10) 20180820	SS-10 (8-10) 20180820	8/20/2018	-	849.70	-	841.00	8-10 ft	8.70 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-11_8_20	082218 09:15_SS-11 (8-10) 20180820	SS-11 (8-10) 20180820	8/20/2018	-	849.80	-	840.70	8-10 ft	9.10 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-SS-15_8_20	082218 09:15_SS-15 (8-10) 20180820	SS-15 (8-10) 20180820	8/20/2018	-	849.80	-	840.60	8-10 ft	9.20 ft	180-81125-1	Not Excavated							
Rear Parking Lot	SSHS-CS2	071318 09:15_SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated							
Rear Parking Lot	SSHS-PW-1	080818 09:00_PW-1	PW-1	8/7/2018	-	851.72	-	841.90	9.2 - 9.2 ft	9.82 ft	180-80546-1	Not Excavated							
Rear Parking Lot	SSHS-PE-1	080818 09:00_PE-1	PE-1	8/7/2018	-	851.61	-	841.80	9.3 - 9.3 ft	9.81 ft	180-80546-1	Not Excavated							
Rear Parking Lot	SSHS-B-F-S-1	080718 09:00_BFS-1	BFS-1	8/4/2018	-	852.02	-	841.80	9.7 - 9.7 ft	10.22 ft	180-80511-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SS	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_PS-FD-21	PS-FD-21	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B587	021617 08:35_SSHS-B587-SUB-0-2	SSHS-B587-SUB-0-2	2/15/2017	856.06	858.19	2.13	-	0 - 2 ft	2.13-4.13 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-0-2	SSHS-B590-SUB-0-2	2/15/2017	856.06	858.01	1.95	-	0 - 2 ft	1.95-3.95 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B591	021617 08:35_SSHS-B591-SUB-0-2	SSHS-B591-SUB-0-2	2/15/2017	856.21	857.85	1.64	-	0 - 2 ft	1.64-3.64 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B592	021617 08:35_SSHS-B592-SUB-0-2	SSHS-B592-SUB-0-2	2/15/2017	856.38	857.26	0.88	-	0 - 2 ft	0.88-2.88 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_PS-FD-13	PS-FD-13	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B745	052417 09:15_SSHS-B745-SUB-0-2	SSHS-B745-SUB-0-2	5/22/2017	855.73	856.22	0.49	-	0 - 2 ft	0.49-2.49 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B746	052417 09:15_SSHS-B746-SUB-0-2	SSHS-B746-SUB-0-2	5/22/2017	855.63	856.41	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_PS-FD-11	PS-FD-11	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	0.64-2.64 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B749	052417 09:15_SSHS-B749-SUB-0-2	SSHS-B749-SUB-0-2	5/22/2017	856.27	856.91	0.64	-	0 - 2 ft	2.64-4.64 ft	180-66618-1	Not Excavated							

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15_SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15_SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15_SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15_SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30_SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45_SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00_SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00_SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00_SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00_SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00_SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00_SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00_SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0064 U	< 0.00086 U	< 0.00088 U	< 0.00071 U	< 0.00056 U	< 0.00094 U	< 0.00065 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00063 U	< 0.00051 U	< 0.0004 U	< 0.00067 U	< 0.00047 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0042 U	< 0.00056 U	< 0.00057 U	< 0.00047 U	< 0.00037 U	< 0.00061 U	< 0.00043 U	< 0.00037 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.0005 U	< 0.0004 U	< 0.00066 U	< 0.00046 U	< 0.0004 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0053 U	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0043 U	< 0.00059 U	< 0.0006 U	< 0.00049 U	< 0.00038 U	< 0.00064 U	< 0.00044 U	< 0.00039 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0047 U	< 0.00063 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.00069 U	< 0.00048 U	< 0.00042 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00067 U	< 0.00068 U	< 0.00055 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.0053 U	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.0059 U	< 0.00079 U	< 0.00081 U	< 0.00066 U	< 0.00052 U	< 0.00087 U	< 0.0006 U	< 0.00052 U
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30_SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0039 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00_SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00_SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00_SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00_SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00_SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00_SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.0044 U	< 0.0028 U	< 0.0027 U	< 0.0033 U	< 0.0037 U	< 0.0063 U	< 0.0042 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30_SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00_SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00_SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00_SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00_SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	0.22 J+	0.0056 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0025 J	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	0.019 J	0.00033 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00_SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00_SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00_SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	0.062	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0055	< 0.034 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15_SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15_SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15_SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15_SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30_SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45_SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00_SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00_SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00_SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00_SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00_SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00_SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00_SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.00057 U	< 0.00055 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0006 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.00096 U	< 0.0009 U	< 0.002 U	< 0.00074 U	< 0.0011 U	< 0.00047 U	< 0.00095 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.0007 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.00064 U	< 0.0014 U	< 0.00053 U	< 0.00077 U	< 0.00034 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.00059 U	< 0.0013 U	< 0.00049 U	< 0.00071 U	< 0.00031 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00052 U	< 0.00076 U	< 0.00033 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	0.0007 J	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00062 U	< 0.0013 U	< 0.00051 U	< 0.00074 U	< 0.00032 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.00067 U	< 0.0015 U	< 0.00055 U	< 0.0008 U	< 0.00035 U	< 0.0007 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-T0-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.00089 U	< 0.00083 U	< 0.0018 U	< 0.00069 U	< 0.001 U	< 0.00044 U	< 0.00088 U
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30_SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00_SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00_SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00_SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00_SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00_SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00_SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.0022 U	< 0.0034 U	< 0.0036 U	< 0.003 U	< 0.0054 U	< 0.0017 U	< 0.0043 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30_SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00_SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00_SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00_SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00_SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00073 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00_SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00_SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00_SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.00088 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.034 U

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15_SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15_SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15_SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15_SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30_SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45_SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00_SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00_SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00_SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00_SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00_SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00_SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00_SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00067 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.00065 J	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00055 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0006 U	< 0.034 U	< 0.00022 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.00086 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00083 U	< 0.00081 U	< 0.00073 U	< 0.00078 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00059 U	< 0.00053 U	< 0.00056 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.00078 U	< 0.0006 U	< 0.00072 U	< 0.0006 U	< 0.00058 U	< 0.00052 U	< 0.00056 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00056 U	< 0.00072 U	< 0.00055 U	< 0.00066 U	< 0.00055 U	< 0.00053 U	< 0.00048 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.0006 U	< 0.00077 U	< 0.0006 U	< 0.00071 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00058 U	< 0.00075 U	< 0.00058 U	< 0.00069 U	< 0.00057 U	< 0.00055 U	< 0.0005 U	< 0.00053 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.00081 U	< 0.00062 U	< 0.00075 U	< 0.00062 U	< 0.0006 U	< 0.00054 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.00079 U	< 0.001 U	< 0.00078 U	< 0.00094 U	< 0.00077 U	< 0.00075 U	< 0.00068 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30_SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0045 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.0012 U	< 0.0021 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00_SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00_SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00_SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00_SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00_SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00_SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.0054 U	< 0.0038 U	< 0.0041 U	< 0.0028 U	< 0.0022 U	< 0.0014 U	< 0.0025 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30_SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00_SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00_SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00_SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00_SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U	< 0.00028 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00_SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00_SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00_SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00074 U

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15 PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15 SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15 SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15 SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15 SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15 SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15 SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15 SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15 SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20 DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20 SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30 PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30 SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30 SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00 SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00 SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50 SSHS-B697-SUB-10-12	032217 08:50 SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45 SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00 SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00 SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00 SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00 SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00 SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00 SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00 SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.0012 U	< 0.034 U	< 0.0025 U	< 0.0032 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00055 U	< 0.00044 U	< 0.034 U	< 0.00062 U	< 0.0019 U	< 0.0003 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0011 U		< 0.00089 U	< 0.00076 U	< 0.00069 U	< 0.00086 U	< 0.00076 U	< 0.00082 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.00078 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00077 U		< 0.00064 U	< 0.00054 U	< 0.00049 U	< 0.00062 U	< 0.00054 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0007 U		< 0.00058 U	< 0.0005 U	< 0.00045 U	< 0.00056 U	< 0.0005 U	< 0.00053 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.00076 U		< 0.00063 U	< 0.00053 U	< 0.00049 U	< 0.00061 U	< 0.00054 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00074 U		< 0.00061 U	< 0.00052 U	< 0.00047 U	< 0.00059 U	< 0.00052 U	< 0.00056 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0008 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00064 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00084 U		< 0.00069 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.001 U		< 0.00083 U	< 0.0007 U	< 0.00064 U	< 0.0008 U	< 0.0007 U	< 0.00075 U
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30 SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50 SSHS-B697-SUB-12-14	032217 08:50 SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45 SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0033 U	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00 SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00 SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00 SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00 SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00 SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00 SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00 SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00 SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30 SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.004 U	< 0.0056 U	< 0.0022 U	< 0.0036 U	< 0.0035 U	< 0.0023 U	< 0.0024 U	< 0.003 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30 SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00 SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00 SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00 SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00 SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00 SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.00057 U	< 0.034 U	< 0.0008 U	< 0.0024 U	< 0.00038 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50 SSHS-B697-SUB-14-16	032217 08:50 SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45 SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40 PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40 SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00 SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00 SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00 SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U	< 0.034 U	< 0.0028 U	< 0.0036 U	< 0.001 U

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15_SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15_SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15_SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15_SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30_SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45_SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00_SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00_SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00_SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00_SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00_SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00_SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00_SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.15	< 0.0011 U	< 0.034 U	< 0.0032 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.034 U	< 0.0014 U	< 0.00042 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0014 U	< 0.00088 U	< 0.00086 U	< 0.0011 U	< 0.00092 U	< 0.0011 U	< 0.00083 U	< 0.00095 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.00098 U	< 0.00064 U	< 0.00063 U	< 0.00083 U	< 0.00067 U	< 0.00081 U	< 0.0006 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00097 U	< 0.00063 U	< 0.00062 U	< 0.00082 U	< 0.00066 U	< 0.0008 U	< 0.00059 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00089 U	< 0.00057 U	< 0.00056 U	< 0.00075 U	< 0.0006 U	< 0.00073 U	< 0.00054 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.00096 U	< 0.00062 U	< 0.00061 U	< 0.00081 U	< 0.00065 U	< 0.00079 U	< 0.00058 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00093 U	< 0.0006 U	< 0.00059 U	< 0.00078 U	< 0.00063 U	< 0.00076 U	< 0.00057 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00065 U	< 0.00064 U	< 0.00085 U	< 0.00068 U	< 0.00083 U	< 0.00061 U	< 0.0007 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00072 U	< 0.00087 U	< 0.00064 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.0013 U	< 0.00081 U	< 0.0008 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00077 U	< 0.00088 U
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30_SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0022 U	< 0.0049 U	< 0.0027 U	< 0.0069 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0021 U	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00_SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00_SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00_SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00_SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00_SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00_SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.0027 U	< 0.0059 U	< 0.0033 U	< 0.0083 U	< 0.003 U	< 0.0041 U	< 0.0026 U	< 0.0052 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30_SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00_SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00_SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00_SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00_SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	0.005 J	< 0.034 U	0.13 J+	< 0.034 U	0.066 J+	0.0046 J	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.0018 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00_SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00_SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00_SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0022 J	0.0062 J	< 0.0036 U	< 0.0019 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	**1,1,2,2-Tetrachloroethane**	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15_SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15_SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15_SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15_SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30_SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45_SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00_SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00_SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00_SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00_SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00_SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00_SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00_SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.001 UJ	< 0.034 U	< 0.00064 U	0.0015 J	< 0.034 U	< 0.0022 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.00022 U	< 0.034 U	< 0.00058 U	< 0.00033 U	< 0.034 U	< 0.00026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0009 U	< 0.00091 U	< 0.00087 U	< 0.00093 U	< 0.0011 U	< 0.0011 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.00065 U	< 0.00066 U	< 0.00063 U	< 0.00067 U	< 0.00078 U	< 0.00081 U	< 0.00045 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00064 U	< 0.00065 U	< 0.00062 U	< 0.00066 U	< 0.00077 U	< 0.0008 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00059 U	< 0.0006 U	< 0.00057 U	< 0.00061 U	< 0.0007 U	< 0.00073 U	< 0.0004 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.00063 U	< 0.00064 U	< 0.00061 U	< 0.00065 U	< 0.00076 U	< 0.00079 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00076 U	< 0.00072 U	0.00079 J	< 0.00089 U	< 0.00093 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.00062 U	< 0.00059 U	< 0.00063 U	< 0.00073 U	< 0.00076 U	< 0.00042 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00067 U	< 0.00064 U	< 0.00068 U	< 0.00079 U	< 0.00083 U	< 0.00046 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U	< 0.00048 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.00074 U	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.00089 U	< 0.00093 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.00083 U	< 0.00084 U	< 0.0008 U	< 0.00086 U	< 0.00099 U	< 0.001 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30_SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0015 U	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U	< 0.0029 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00_SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00_SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00_SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00_SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00_SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00_SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.0019 U	< 0.0042 U	< 0.0028 U	< 0.0024 U	< 0.005 U	< 0.0052 U	< 0.0035 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30_SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00_SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00_SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00_SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00_SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.0043 J	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.00028 U	< 0.034 U	< 0.00074 U	0.00067 J	< 0.034 U	< 0.00034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00_SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00_SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00_SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.0011 U	< 0.034 U	< 0.0007 U	< 0.00074 U	< 0.034 U	< 0.034 U	< 0.034 U

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_PS-FD-14	PS-FD-14	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B759	052417 09:15_SSHS-B759-SUB-0-2	SSHS-B759-SUB-0-2	5/22/2017	856.24	857.82	1.58	-	0 - 2 ft	1.58-3.58 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B767	052417 09:15_SSHS-B767-SUB-0-2	SSHS-B767-SUB-0-2	5/22/2017	855.87	856.21	0.34	-	0 - 2 ft	0.34-2.34 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B769	052417 09:15_SSHS-B769-SUB-0-2	SSHS-B769-SUB-0-2	5/22/2017	855.85	856.07	0.22	-	0 - 2 ft	0.22-2.22 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B770	052417 09:15_SSHS-B770-SUB-0-2	SSHS-B770-SUB-0-2	5/22/2017	856.04	856.56	0.52	-	0 - 2 ft	0.52-2.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-0-2	SSHS-B771-SUB-0-2	5/22/2017	856.31	857.09	0.78	-	0 - 2 ft	0.78-2.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B774	052417 09:15_SSHS-B774-SUB-0-2	SSHS-B774-SUB-0-2	5/22/2017	856.38	857.34	0.96	-	0 - 2 ft	0.96-2.96 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-0-2	SSHS-B778-SUB-0-2	5/22/2017	855.75	858.14	2.39	-	0 - 2 ft	2.39-4.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-0-2	SSHS-B777-SUB-0-2	5/23/2017	855.99	858.05	2.06	-	0 - 2 ft	2.06-4.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-0-2	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_DUP-1	DUP-1	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B822	062017 09:20_SSHS-B822-SUB-0-2	SSHS-B822-SUB-0-2	6/19/2017	856.39	857.30	0.91	-	0 - 2 ft	0.91-2.91 ft	180-67517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-0.17-1	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_PS-FD-8	PS-FD-8	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B595	021117 09:30_SSHS-B595-SUB-0.17-2	SSHS-B595-SUB-0.17-2	2/10/2017	856.24	856.25	0.01	-	0.17 - 2 ft	0.18-2.01 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B596	021117 09:30_SSHS-B596-SUB-0.17-2	SSHS-B596-SUB-0.17-2	2/10/2017	855.41	855.78	0.37	-	0.17 - 2 ft	0.54-2.37 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B405	082616 09:00_SSHS-B405-SUB-1-2	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B406	082616 09:00_SSHS-B406-SUB-1-2	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-10-12	032217 08:50_SSHS-B697-SUB-10-12	3/21/2017	855.71	855.71	0.00	-	10 - 12 ft	10 - 12 ft	180-64494-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-10-12	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S111	072519 08:45_SSHS-IRM3-S111-C	SSHS-IRM3-S111-C	7/24/2019	-	855.71	-	845.02	10 - 12 ft	10.69 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S135	072719 09:00_SSHS-IRM3-S135-C	SSHS-IRM3-S135-C	7/26/2019	-	855.44	-	845.15	10 - 12 ft	10.29 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-B013	080619 09:00_SSHS-IRM3-B013-C	SSHS-IRM3-B013-C	8/5/2019	-	855.73	-	843.91	10 - 12 ft	11.82 ft	180-93683-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133	080619 09:00_SSHS-IRM3-S133-C	SSHS-IRM3-S133-C	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S134	080619 09:00_SSHS-IRM3-S134-C	SSHS-IRM3-S134-C	8/5/2019	-	855.71	-	844.44	10 - 12 ft	11.27 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 D	080619 09:00_SSHS-IRM3-S137D-C	SSHS-IRM3-S137d-c	8/5/2019	-	855.19	-	843.41	10 - 12 ft	11.79 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S154	080619 09:00_SSHS-IRM3-S154-C	SSHS-IRM3-S154-C	8/5/2019	-	855.78	-	844.06	10 - 12 ft	11.72 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S171	080619 09:00_SSHS-IRM3-S171-D	SSHS-IRM3-S171-D	8/5/2019	-	855.68	-	844.26	10 - 12 ft	11.42 ft	180-93684-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-10-12	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.034 U	0.0011 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-10-12	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-10-12	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00072 U	< 0.034 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-10-13.5 (10.5)	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated	< 0.0011 U	< 0.00084 U	< 0.0012 U	< 0.0006 U	< 0.0019 U	< 0.00099 U	
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-10-14 (12)	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated	< 0.00077 U	< 0.00061 U	< 0.00085 U	< 0.00043 U	< 0.0014 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-10-14.5 (12)	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated	< 0.00076 U	< 0.0006 U	< 0.00083 U	< 0.00043 U	< 0.0013 U	< 0.00071 U	
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-10-15 (12.5)	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.00055 U	< 0.00076 U	< 0.00039 U	< 0.0012 U	< 0.00065 U	
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_DUP-10	DUP-10	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-2	Not Excavated	< 0.00074 U	< 0.00059 U	< 0.00082 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-10-15 (12.5)	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00088 U	< 0.00069 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-10-15 (12.5)	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00072 U	< 0.00057 U	< 0.0008 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-10-15 (12.5)	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated	< 0.00078 U	< 0.00062 U	< 0.00086 U	< 0.00044 U	< 0.0014 U	< 0.00073 U	
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-10-15 (12.5)	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-10-15 (12)	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated	< 0.00088 U	< 0.00069 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-10-15 (12)	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated	< 0.00098 U	< 0.00077 U	< 0.0011 U	< 0.00055 U	< 0.0017 U	< 0.00092 U	
Tennis Courts / Main Parking Lot	SSHS-B634	021117 09:30_SSHS-B634-SUB-12-14	SSHS-B634-SUB-12-14	2/10/2017	855.23	855.23	0.00	-	12 - 14 ft	12-14 ft	180-63389-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-12-14	032217 08:50_SSHS-B697-SUB-12-14	3/21/2017	855.71	855.71	0.00	-	12 - 14 ft	12 - 14 ft	180-64494-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-12-14	SSHS-B799-SUB-12-14	5/17/2017	855.37	855.37	0.00	-	12 - 14 ft	12-14 ft	180-66432-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_PS-FD-18	PS-FD-18	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0028 U	< 0.0017 U	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Tennis Courts / Main Parking Lot	SSHS-B2755	042819 10:00_SSHS-B2755-SUB-12-14	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-B2683	042819 10:00_SSHS-B2683-SUB-12-14	SSHS-B2683-SUB-12-14	4/27/2019	855.72	855.72	0.00	-	12 - 14 ft	12-14 ft	180-89523-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S115	072719 09:00_SSHS-IRM3-S115-C	SSHS-IRM3-S115-C	7/26/2019	-	855.16	-	842.46	12 - 14 ft	12.7 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156F	073119 09:00_SSHS-IRM3-S156F-C	SSHS-IRM3-S156F-C	7/30/2019	-	855.08	-	841.80	12 - 14 ft	13.28 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	080219 09:00_SSHS-IRM3-OS1-C	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DA	080219 09:00_SSHS-IRM3-S156DA-C	SSHS-IRM3-S156DA-C	8/1/2019	-	855.32	-	841.59	12 - 14 ft	13.73 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DB	080219 09:00_SSHS-IRM3-S156DB-C	SSHS-IRM3-S156DB-C	8/1/2019	-	855.48	-	841.91	12 - 14 ft	13.57 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DC	080219 09:00_SSHS-IRM3-S156DC-C	SSHS-IRM3-S156DC-C	8/1/2019	-	855.39	-	842.62	12 - 14 ft	12.77 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	080319 09:30_SSHS-IRM3-PIPE22-C	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0052 U		< 0.0034 U	< 0.0061 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S157	080319 09:30_SSHS-IRM3-S157-C	SSHS-IRM3-S157-C	8/2/2019	-	855.03	-	842.44	12 - 14 ft	12.59 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 A	080619 09:00_SSHS-IRM3-S137A-C	SSHS-IRM3-S137a-c	8/5/2019	-	855.90	-	843.31	12 - 14 ft	12.59 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 B	080619 09:00_SSHS-IRM3-S137B-C	SSHS-IRM3-S137b-c	8/5/2019	-	855.85	-	843.60	12 - 14 ft	12.25 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S137 BOT	080619 09:00_SSHS-IRM3-S137 BOT-C	SSHS-IRM3-S137 bot-c	8/5/2019	-	855.77	-	841.83	12 - 14 ft	13.94 ft	180-93683-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156	080619 09:00_SSHS-IRM3-S156-C	SSHS-IRM3-S156-C	8/5/2019	-	855.42	-	842.03	12 - 14 ft	13.39 ft	180-93683-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-DUP13-D	SSHS-IRM3-DUP13-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S173	080619 09:00_SSHS-IRM3-S173-D	SSHS-IRM3-S173-D	8/5/2019	-	855.44	-	843.00	12 - 14 ft	12.44 ft	180-93684-3	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-12-14	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.034 U	0.0054 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-12-14	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0075 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-12-14	SSHS-B4161-SUB-12-14	9/17/2021	858.24	858.24	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U	< 0.00093 U
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-14-16	032217 08:50_SSHS-B697-SUB-14-16	3/21/2017	855.71	855.71	0.00	-	14 - 16 ft	14 - 16 ft	180-64494-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B799	051817 08:45_SSHS-B799-SUB-14-16	SSHS-B799-SUB-14-16	5/17/2017	855.37	855.37	0.00	-	14 - 16 ft	14-16 ft	180-66432-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_PS-FD-24	PS-FD-24	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B2754	052119 08:40_SSHS-B2754-SUB-14-16	SSHS-B2754-SUB-14-16	5/19/2019	855.32	855.32	0.00	-	14 - 16 ft	14-16 ft	180-90323-3	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S136	072719 09:00_SSHS-IRM3-S136-C	SSHS-IRM3-S136-C	7/26/2019	-	855.36	-	840.00	14 - 16 ft	15.36 ft	180-93321-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-B019	073119 09:00_SSHS-IRM3-B019	SSHS-IRM3-B019	7/30/2019	-	855.24	-	841.00	14 - 16 ft	14.24 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S156DD	080219 09:00_SSHS-IRM3-S156DD-C	SSHS-IRM3-S156DD-C	8/1/2019	-	855.28	-	840.13	14 - 16 ft	15.15 ft	180-93547-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-14-16	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.034 U	0.0026 J	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.0015 U

												Acetone	**Benzene**	**Bromochloromethane**	**Bromodichloromethane**	**Bromoform**	**Bromomethane**	**Carbon disulfide**	**Carbon Tetrachloride**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	0.012 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35_SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35_SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35_SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35_SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35_SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35_SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45_SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15_SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15_SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15_SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15_SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15_SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15_SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15_SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15_SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15_SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15_SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15_SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15_SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15_SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	0.024	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0042 UHT	< 0.0015 UHT	< 0.0032 UHT	< 0.0025 UHT	< 0.0027 UHT	< 0.0024 UHT	< 0.0043 UHT	< 0.0022 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0042 UHT	< 0.0015 UHT	< 0.0032 UHT	< 0.0025 UHT	< 0.0027 UHT	< 0.0024 UHT	< 0.0043 UHT	< 0.0022 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0035 U	< 0.0018 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0027 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0041 U	< 0.00055 U	< 0.00056 U	< 0.00046 U	< 0.00036 U	< 0.00061 U	< 0.00042 U	< 0.00037 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	0.0064 J	< 0.00071 U	< 0.00073 U	< 0.00059 U	< 0.00047 U	< 0.00078 U	< 0.00054 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0074 U	< 0.001 U	< 0.001 U	< 0.00083 U	< 0.00065 U	< 0.0011 U	< 0.00076 U	< 0.00066 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00043 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0034 U	< 0.00046 U	< 0.00047 U	< 0.00038 U	< 0.0003 U	< 0.0005 U	< 0.00035 U	< 0.0003 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0043 U	< 0.00058 U	< 0.00059 U	< 0.00048 U	< 0.00038 U	< 0.00063 U	< 0.00044 U	< 0.00038 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0046 U	< 0.00063 U	< 0.00064 U	< 0.00052 U	< 0.00041 U	< 0.00069 U	< 0.00048 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.0056 U	< 0.00076 U	< 0.00077 U	< 0.00063 U	< 0.0005 U	< 0.00083 U	< 0.00058 U	< 0.0005 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.0046 U	< 0.00062 U	< 0.00063 U	< 0.00052 U	< 0.00041 U	< 0.00068 U	< 0.00047 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0053 U	< 0.00072 U	< 0.00073 U	< 0.0006 U	< 0.00047 U	< 0.00079 U	< 0.00055 U	< 0.00048 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0048 U	< 0.00065 U	< 0.00066 U	< 0.00054 U	< 0.00042 U	< 0.00071 U	< 0.00049 U	< 0.00043 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0047 U	< 0.00064 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.0007 U	< 0.00049 U	< 0.00042 U
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00_SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00_SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00_SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated								

DRAFT

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.00066 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35_SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35_SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35_SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35_SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35_SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35_SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45_SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15_SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15_SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15_SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15_SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15_SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15_SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15_SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15_SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15_SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15_SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15_SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15_SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15_SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.00074 U	< 0.0022 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.0005 U	< 0.00049 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00053 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0014 UHT	< 0.0027 UHT	< 0.0031 UHT	< 0.0017 UHT	< 0.0021 UHT	< 0.0026 UHT	< 0.0035 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0014 UHT	< 0.0027 UHT	< 0.0031 UHT	< 0.0017 UHT	< 0.0021 UHT	< 0.0026 UHT	< 0.0035 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.0011 U	< 0.0021 U	< 0.0025 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0028 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.0030 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00062 U	< 0.00058 U	< 0.0013 U	< 0.00048 U	< 0.0007 U	< 0.0003 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0008 U	< 0.00075 U	< 0.0016 U	< 0.00062 U	< 0.0009 U	< 0.00039 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0011 U	< 0.001 U	< 0.0023 U	< 0.00086 U	< 0.0013 U	< 0.00055 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00051 U	< 0.00048 U	< 0.001 U	< 0.0004 U	< 0.00058 U	< 0.00025 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00065 U	< 0.00061 U	< 0.0013 U	< 0.0005 U	< 0.00073 U	< 0.00032 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0007 U	< 0.00066 U	< 0.0014 U	< 0.00054 U	< 0.00079 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.00085 U	< 0.0008 U	< 0.0017 U	< 0.00066 U	< 0.00096 U	< 0.00042 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.0007 U	< 0.00065 U	< 0.0014 U	< 0.00054 U	< 0.00078 U	< 0.00034 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00081 U	< 0.00076 U	< 0.0016 U	< 0.00062 U	< 0.00091 U	< 0.0004 U	< 0.0008 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00073 U	< 0.00068 U	< 0.0015 U	< 0.00056 U	< 0.00082 U	< 0.00036 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00072 U	< 0.00067 U	< 0.0015 U	< 0.00056 U	< 0.00081 U	< 0.00035 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00_SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00_SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00_SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated							

DRAFT

												Dichloromethane	**1,2-Dibromoethane**	**Dichlorodifluoromethane**	**1,2-Dichlorobenzene**	**1,3-Dichlorobenzene**	**1,4-Dichlorobenzene**	**1,1-Dichloroethane**	**1,2-Dichloroethane**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U	< 0.00025 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35_SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35_SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35_SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35_SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35_SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35_SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45_SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15_SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15_SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15_SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15_SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15_SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15_SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15_SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15_SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15_SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15_SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15_SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15_SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15_SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00071 U	< 0.034 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00049 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00053 U	< 0.034 U	< 0.00019 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0048 UHT	< 0.0015 UHT	< 0.0027 UHT	< 0.0018 UHT	< 0.0033 UHT	< 0.0016 UHT	< 0.0017 UHT	< 0.0015 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0048 UHT	< 0.0015 UHT	< 0.0027 UHT	< 0.0018 UHT	< 0.0033 UHT	< 0.0016 UHT	< 0.0017 UHT	< 0.0015 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.0039 U	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0012 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.0041 U	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00055 U	< 0.00071 U	< 0.00055 U	< 0.00065 U	< 0.00054 U	< 0.00052 U	< 0.00047 U	< 0.0005 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00071 U	< 0.00091 U	< 0.0007 U	< 0.00084 U	< 0.00069 U	< 0.00067 U	< 0.00061 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00099 U	< 0.0013 U	< 0.00098 U	< 0.0012 U	< 0.00097 U	< 0.00094 U	< 0.00085 U	< 0.00091 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00065 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00046 U	< 0.00058 U	< 0.00045 U	< 0.00054 U	< 0.00044 U	< 0.00043 U	< 0.00039 U	< 0.00042 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00057 U	< 0.00074 U	< 0.00057 U	< 0.00068 U	< 0.00056 U	< 0.00054 U	< 0.00049 U	< 0.00052 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00062 U	< 0.0008 U	< 0.00062 U	< 0.00074 U	< 0.00061 U	< 0.00059 U	< 0.00053 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.00076 U	< 0.00097 U	< 0.00075 U	< 0.0009 U	< 0.00074 U	< 0.00072 U	< 0.00065 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.00062 U	< 0.00079 U	< 0.00061 U	< 0.00073 U	< 0.0006 U	< 0.00058 U	< 0.00053 U	< 0.00056 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00072 U	< 0.00092 U	< 0.00071 U	< 0.00085 U	< 0.0007 U	< 0.00068 U	< 0.00061 U	< 0.00065 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.00083 U	< 0.00064 U	< 0.00076 U	< 0.00063 U	< 0.00061 U	< 0.00055 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.00082 U	< 0.00063 U	< 0.00076 U	< 0.00062 U	< 0.0006 U	< 0.00055 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00_SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00_SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00_SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated								

DRAFT

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.00051 U	< 0.034 U	< 0.00072 U	< 0.0022 U	< 0.00034 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35_SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35_SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35_SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35_SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35_SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35_SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45_SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15_SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15_SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15_SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15_SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15_SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15_SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15_SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15_SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15_SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15_SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15_SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15_SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15_SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.0011 U	< 0.034 U	< 0.0023 U	< 0.003 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00049 U	< 0.00039 U	< 0.034 U	< 0.00055 U	< 0.0017 U	< 0.00026 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0024 UHT	< 0.0044 UHT	< 0.0016 UHT	< 0.0019 UHT	< 0.0014 UHT	< 0.0024 UHT	< 0.0024 UHT	< 0.0020 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0024 UHT	< 0.0044 UHT	< 0.0016 UHT	< 0.0019 UHT	< 0.0014 UHT	< 0.0024 UHT	< 0.0024 UHT	< 0.0020 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.0020 U	< 0.0035 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.0019 U	< 0.0019 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.0021 U	< 0.0037 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0020 U	< 0.0021 U	< 0.0017 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00083 U		< 0.00069 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0007 U		< 0.00058 U	< 0.00049 U	< 0.00045 U	< 0.00056 U	< 0.00049 U	< 0.00053 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0009 U		< 0.00074 U	< 0.00063 U	< 0.00057 U	< 0.00072 U	< 0.00063 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0013 U		< 0.001 U	< 0.00088 U	< 0.0008 U	< 0.001 U	< 0.00088 U	< 0.00095 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00083 U		< 0.00068 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00057 U		< 0.00048 U	< 0.0004 U	< 0.00037 U	< 0.00046 U	< 0.00041 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00072 U		< 0.0006 U	< 0.00051 U	< 0.00046 U	< 0.00058 U	< 0.00051 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00079 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00063 U	< 0.00055 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.00095 U		< 0.00079 U	< 0.00067 U	< 0.00061 U	< 0.00076 U	< 0.00067 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.00078 U		< 0.00065 U	< 0.00055 U	< 0.0005 U	< 0.00062 U	< 0.00055 U	< 0.00059 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0009 U		< 0.00075 U	< 0.00063 U	< 0.00058 U	< 0.00072 U	< 0.00064 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00081 U		< 0.00067 U	< 0.00057 U	< 0.00052 U	< 0.00065 U	< 0.00057 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00081 U		< 0.00067 U	< 0.00057 U	< 0.00052 U	< 0.00064 U	< 0.00057 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00_SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00_SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00_SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated								

DRAFT

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.0016 U	< 0.00049 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35_SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35_SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35_SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35_SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35_SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35_SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45_SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15_SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15_SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15_SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15_SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15_SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15_SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15_SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15_SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15_SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15_SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15_SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15_SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15_SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00099 U	< 0.034 U	< 0.003 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00058 U	< 0.034 U	< 0.0012 U	< 0.00037 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0021 UHT	< 0.0017 UHT	< 0.0028 UHT	< 0.0079 UHT	< 0.0026 UHT	< 0.0027 UHT	< 0.0020 UHT	< 0.0016 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0021 UHT	< 0.0017 UHT	< 0.0028 UHT	< 0.0079 UHT	< 0.0026 UHT	< 0.0027 UHT	< 0.0020 UHT	< 0.0016 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.0017 U	< 0.0014 U	< 0.0023 U	< 0.0064 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.0018 U	< 0.0014 U	< 0.0024 U	< 0.0067 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0013 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00088 U	< 0.00057 U	< 0.00056 U	< 0.00074 U	< 0.00059 U	< 0.00072 U	< 0.00054 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.0011 U	< 0.00073 U	< 0.00072 U	< 0.00095 U	< 0.00077 U	< 0.00093 U	< 0.00069 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0016 U	< 0.001 U	< 0.001 U	< 0.0013 U	< 0.0011 U	< 0.0013 U	< 0.00096 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00063 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00072 U	< 0.00047 U	< 0.00046 U	< 0.00061 U	< 0.00049 U	< 0.0006 U	< 0.00044 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00091 U	< 0.00059 U	< 0.00058 U	< 0.00077 U	< 0.00062 U	< 0.00075 U	< 0.00056 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00099 U	< 0.00064 U	< 0.00063 U	< 0.00084 U	< 0.00067 U	< 0.00082 U	< 0.00061 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.0012 U	< 0.00078 U	< 0.00076 U	< 0.001 U	< 0.00082 U	< 0.00099 U	< 0.00073 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.00098 U	< 0.00063 U	< 0.00062 U	< 0.00083 U	< 0.00067 U	< 0.00081 U	< 0.0006 U	< 0.00069 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0011 U	< 0.00074 U	< 0.00072 U	< 0.00096 U	< 0.00077 U	< 0.00094 U	< 0.00069 U	< 0.0008 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.001 U	< 0.00066 U	< 0.00065 U	< 0.00086 U	< 0.0007 U	< 0.00084 U	< 0.00063 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.001 U	< 0.00066 U	< 0.00064 U	< 0.00086 U	< 0.00069 U	< 0.00084 U	< 0.00062 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00_SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00_SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00_SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.00025 U	< 0.034 U	< 0.00067 U	0.00044 J	< 0.034 U	< 0.0003 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35_SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35_SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35_SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35_PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35_SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35_SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35_SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45_SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15_SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15_SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15_SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15_SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15_SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15_SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15_SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15_SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15_SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15_SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15_SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15_SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15_SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15_SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15_SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15_SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00_SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00_SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00_SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00_SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10_SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10_SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10_SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10_SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50_SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50_SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30_SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30_SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00_SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.00093 U	< 0.034 U	< 0.00059 U	< 0.00062 U	< 0.034 U	< 0.002 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.00019 U	< 0.034 U	< 0.00051 U	< 0.00029 U	< 0.034 U	< 0.00023 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0016 UHT	< 0.0016 UHT	< 0.0022 UHT	< 0.0015 UHT	< 0.0030 UHT	< 0.0027 UHT	< 0.0018 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0016 UHT	< 0.0016 UHT	< 0.0022 UHT	< 0.0015 UHT	< 0.0030 UHT	< 0.0027 UHT	< 0.0018 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.0013 U	< 0.0013 U	< 0.0017 U	< 0.0012 U	< 0.0024 U	< 0.0022 U	< 0.0014 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.0014 U	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00058 U	< 0.00059 U	< 0.00056 U	< 0.0006 U	< 0.00069 U	< 0.00072 U	< 0.0004 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00076 U	< 0.00072 U	< 0.00077 U	< 0.00089 U	< 0.00093 U	< 0.00051 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.0011 U	< 0.001 U	< 0.0011 U	< 0.0012 U	< 0.0013 U	< 0.00072 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00048 U	< 0.00049 U	< 0.00046 U	< 0.00049 U	< 0.00057 U	< 0.0006 U	< 0.00033 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.0006 U	< 0.00061 U	< 0.00058 U	< 0.00062 U	< 0.00072 U	< 0.00075 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00065 U	< 0.00067 U	< 0.00063 U	< 0.00068 U	< 0.00078 U	< 0.00082 U	< 0.00045 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.00079 U	< 0.00081 U	< 0.00077 U	< 0.00082 U	< 0.00095 U	< 0.00099 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.00065 U	< 0.00066 U	< 0.00062 U	< 0.00067 U	< 0.00078 U	< 0.00081 U	< 0.00045 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00075 U	< 0.00077 U	< 0.00072 U	< 0.00078 U	< 0.0009 U	< 0.00094 U	< 0.00052 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00068 U	< 0.00069 U	< 0.00065 U	< 0.0007 U	< 0.00081 U	< 0.00085 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00067 U	< 0.00068 U	< 0.00065 U	< 0.00069 U	< 0.0008 U	< 0.00084 U	< 0.00046 U
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35_SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50_SSHS-B697-SUB-4-6	032217 08:50_SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55_SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55_SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00_SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00_SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00_SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated							

DRAFT

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-14-16	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-14-16	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B581	021617 08:35 SSHS-B581-SUB-2-4	SSHS-B581-SUB-2-4	2/14/2017	856.09	856.86	0.77	-	2 - 4 ft	2.77-4.77 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B582	021617 08:35 SSHS-B582-SUB-2-4	SSHS-B582-SUB-2-4	2/14/2017	856.23	856.89	0.66	-	2 - 4 ft	2.66-4.66 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B583	021617 08:35 SSHS-B583-SUB-2-4	SSHS-B583-SUB-2-4	2/14/2017	856.19	857.52	1.33	-	2 - 4 ft	3.33-5.33 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35 SSHS-B584-SUB-2-4	SSHS-B584-SUB-2-4	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B584	021617 08:35 PS-FD-19	PS-FD-19	2/14/2017	855.99	856.47	0.48	-	2 - 4 ft	2.48-4.48 ft	180-63507-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B578	021617 08:35 SSHS-B578-SUB-2-4	SSHS-B578-SUB-2-4	2/15/2017	856.31	857.46	1.15	-	2 - 4 ft	3.15-5.15 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B579	021617 08:35 SSHS-B579-SUB-2-4	SSHS-B579-SUB-2-4	2/15/2017	856.16	856.78	0.62	-	2 - 4 ft	2.62-4.62 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B594	021617 08:35 SSHS-B594-SUB-2-4	SSHS-B594-SUB-2-4	2/15/2017	856.17	856.69	0.52	-	2 - 4 ft	2.52-4.52 ft	180-63517-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55 SSHS-B720-SUB-2-4	SSHS-B720-SUB-2-4	4/12/2017	855.48	855.48	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55 SSHS-B722-SUB-2-4	SSHS-B722-SUB-2-4	4/12/2017	855.14	855.14	0.00	-	2 - 4 ft	2-4 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B783	051817 08:45 SSHS-B783-SUB-2-4	SSHS-B783-SUB-2-4	5/17/2017	855.31	855.31	0.00	-	2 - 4 ft	2-4 ft	180-66432-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B747	052417 09:15 SSHS-B747-SUB-2-4	SSHS-B747-SUB-2-4	5/22/2017	856.07	856.37	0.30	-	2 - 4 ft	2.30-4.30 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B748	052417 09:15 SSHS-B748-SUB-2-4	SSHS-B748-SUB-2-4	5/22/2017	856.15	856.67	0.52	-	2 - 4 ft	2.52-4.52 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B750	052417 09:15 SSHS-B750-SUB-2-4	SSHS-B750-SUB-2-4	5/22/2017	856.17	856.71	0.54	-	2 - 4 ft	2.54-4.54 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B752	052417 09:15 SSHS-B752-SUB-2-4	SSHS-B752-SUB-2-4	5/22/2017	856.15	856.60	0.45	-	2 - 4 ft	2.45-4.45 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B756	052417 09:15 SSHS-B756-SUB-2-4	SSHS-B756-SUB-2-4	5/22/2017	856.09	856.56	0.47	-	2 - 4 ft	2.47-4.47 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B757	052417 09:15 SSHS-B757-SUB-2-4	SSHS-B757-SUB-2-4	5/22/2017	856.25	857.10	0.85	-	2 - 4 ft	2.85-4.85 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B758	052417 09:15 SSHS-B758-SUB-2-4	SSHS-B758-SUB-2-4	5/22/2017	856.30	857.16	0.86	-	2 - 4 ft	2.86-4.86 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B761	052417 09:15 SSHS-B761-SUB-2-4	SSHS-B761-SUB-2-4	5/22/2017	856.13	856.73	0.60	-	2 - 4 ft	2.6-4.6 ft	180-66618-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B765	052417 09:15 SSHS-B765-SUB-2-4	SSHS-B765-SUB-2-4	5/22/2017	856.08	856.48	0.40	-	2 - 4 ft	2.40-4.40 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B766	052417 09:15 SSHS-B766-SUB-2-4	SSHS-B766-SUB-2-4	5/22/2017	856.26	856.88	0.62	-	2 - 4 ft	2.62-4.62 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B768	052417 09:15 SSHS-B768-SUB-2-4	SSHS-B768-SUB-2-4	5/22/2017	855.82	855.87	0.05	-	2 - 4 ft	2.05-4.05 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B771	052417 09:15 SSHS-B771-SUB-2-4	SSHS-B771-SUB-2-4	5/22/2017	856.31	857.09	0.78	-	2 - 4 ft	2.78-4.78 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B772	052417 09:15 SSHS-B772-SUB-2-4	SSHS-B772-SUB-2-4	5/22/2017	856.30	857.04	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B773	052417 09:15 SSHS-B773-SUB-2-4	SSHS-B773-SUB-2-4	5/22/2017	856.38	857.12	0.74	-	2 - 4 ft	2.74-4.74 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B778	052417 09:15 SSHS-B778-SUB-2-4	SSHS-B778-SUB-2-4	5/22/2017	855.75	858.14	2.39	-	2 - 4 ft	4.39-6.39 ft	180-66618-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B777	052417 09:15 SSHS-B777-SUB-2-4	SSHS-B777-SUB-2-4	5/23/2017	855.99	858.05	2.06	-	2 - 4 ft	4.06-6.06 ft	180-66622-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-2-4	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-DUP1-07-09-19	SSHS-IRM3-DUP1-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S012	071019 09:00 SSHS-IRM3-S012-07-09-19	SSHS-IRM3-S012-07-09-19	7/9/2019	-	855.65	-	853.52	2 - 4 ft	2.13 ft	180-92392-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S033	071219 09:00 SSHS-IRM3-S033-C	SSHS-IRM3-S033-C	7/11/2019	-	855.65	-	853.07	2 - 4 ft	2.58 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S034	071219 09:00 SSHS-IRM3-S034-C	SSHS-IRM3-S034-C	7/11/2019	-	855.67	-	852.86	2 - 4 ft	2.81 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S035	071219 09:00 SSHS-IRM3-S035-C	SSHS-IRM3-S035-C	7/11/2019	-	855.66	-	852.83	2 - 4 ft	2.83 ft	180-92538-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S036	071319 09:10 SSHS-IRM3-S036-C	SSHS-IRM3-S036-C	7/12/2019	-	855.55	-	852.58	2 - 4 ft	2.97 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S037	071319 09:10 SSHS-IRM3-S037-C	SSHS-IRM3-S037-C	7/12/2019	-	855.44	-	853.07	2 - 4 ft	2.36 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S038	071319 09:10 SSHS-IRM3-S038-C	SSHS-IRM3-S038-C	7/12/2019	-	855.93	-	853.20	2 - 4 ft	2.73 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10 SSHS-IRM3-DUP1-07-12-19	SSHS-IRM3-DUP1-07-12-19	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S039	071319 09:10 SSHS-IRM3-S039-C	SSHS-IRM3-S039-C	7/12/2019	-	855.26	-	853.03	2 - 4 ft	2.23 ft	180-92615-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032A	072419 08:50 SSHS-IRM3-S032-A	SSHS-IRM3-S032-A	7/23/2019	-	855.61	-	852.33	2 - 4 ft	3.28 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032B	072419 08:50 SSHS-IRM3-S032-B	SSHS-IRM3-S032-B	7/23/2019	-	855.66	-	851.83	2 - 4 ft	3.83 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S031	080319 09:30 SSHS-IRM3-S031-C	SSHS-IRM3-S031-C	8/2/2019	-	855.63	-	853.17	2 - 4 ft	2.46 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083	080319 09:30 SSHS-IRM3-S083-C	SSHS-IRM3-S083-C	8/2/2019	-	855.79	-	851.90	2 - 4 ft	3.89 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067F	080919 09:00 SSHS-IRM3-S067F-C	SSHS-IRM3-S067F-C	8/8/2019	-	855.63	-	851.71	2 - 4 ft	3.92 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-2-4	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.0013 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-2-4	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-2-4	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11-20220825	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 0.0011 UHT	< 0.0017 UHT	< 0.0045 UHT	< 0.0039 UHT	< 0.0019 UHT	< 0.0022 UHT	< 0.0077 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12-20220825	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 0.0011 UHT	< 0.0017 UHT	< 0.0045 UHT	< 0.0039 UHT	< 0.0019 UHT	< 0.0022 UHT	< 0.0077 UHT
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2-20220826	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.03	1801436191	Not Excavated	< 0.00086 U	< 0.0014 U	< 0.0036 U	< 0.0031 U	< 0.0015 U	< 0.0017 U	< 0.0062 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1-20220826	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 0.00090 U	< 0.0014 U	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-2-6 (4)	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00081 U	< 0.00064 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 DUP-11	DUP-11	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00068 U	< 0.00054 U	< 0.00075 U	< 0.00038 U	< 0.0012 U	< 0.00064 U	
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-2-6 (5.5)	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00088 U	< 0.00069 U	< 0.00097 U	< 0.0005 U	< 0.0016 U	< 0.00082 U	
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-2-6 (3.5)	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.0012 U	< 0.00097 U	< 0.0014 U	< 0.00069 U	< 0.0022 U	< 0.0012 U	
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-2-6 (3.5)	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00081 U	< 0.00064 U	< 0.00089 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-2-6 (4)	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated	< 0.00056 U	< 0.00045 U	< 0.00062 U	< 0.00032 U	< 0.001 U	< 0.00053 U	
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 DUP-09	DUP-09	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-2	Not Excavated	< 0.00071 U	< 0.00056 U	< 0.00078 U	< 0.0004 U	< 0.0013 U	< 0.00066 U	
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-2-6 (5)	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated	< 0.00077 U	< 0.00061 U	< 0.00085 U	< 0.00044 U	< 0.0014 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-2-6 (3.5)	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated	< 0.00093 U	< 0.00074 U	< 0.001 U	< 0.00053 U	< 0.0017 U	< 0.00088 U	
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 DUP-12	DUP-12	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-2	Not Excavated	< 0.00076 U	< 0.0006 U	< 0.00084 U	< 0.00043 U	< 0.0013 U	< 0.00072 U	
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-2-6 (4)	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00089 U	< 0.0007 U	< 0.00098 U	< 0.0005 U	< 0.0016 U	< 0.00083 U	
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-2-6 (4)	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.0008 U	< 0.00063 U	< 0.00088 U	< 0.00045 U	< 0.0014 U	< 0.00075 U	
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-2-6 (5)	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated	< 0.00079 U	< 0.00062 U	< 0.00087 U	< 0.00045 U	< 0.0014 U	< 0.00074 U	
Tennis Courts / Main Parking Lot	SSHS-B590	021617 08:35 SSHS-B590-SUB-4-6	SSHS-B590-SUB-4-6	2/15/2017	856.06	858.01	1.95	-	4 - 6 ft	5.95-7.95 ft	180-63517-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B697	032217 08:50 SSHS-B697-SUB-4-6	032217 08:50 SSHS-B697-SUB-4-6	3/21/2017	855.71	855.71	0.00	-	4 - 6 ft	4 - 6 ft	180-64494-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B720	041317 08:55 SSHS-B720-SUB-4-6	SSHS-B720-SUB-4-6	4/12/2017	855.48	855.48	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B722	041317 08:55 SSHS-B722-SUB-4-6	SSHS-B722-SUB-4-6	4/12/2017	855.14	855.14	0.00	-	4 - 6 ft	4-6 ft	180-65174-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-4-6	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S064	071719 09:00 SSHS-IRM3-S064-C	SSHS-IRM3-S064-C	7/16/2019	-	855.65	-	851.03	4 - 6 ft	4.62 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S065	071719 09:00 SSHS-IRM3-S065-C	SSHS-IRM3-S065-C	7/16/2019	-	855.56	-	850.82	4 - 6 ft	4.74 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S066	071719 09:00 SSHS-IRM3-S066-C	SSHS-IRM3-S066-C	7/16/2019	-	855.59	-	850.04	4 - 6 ft	5.55 ft	180-92715-1	Not Excavated							

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00 SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50 SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45 SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00 SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00 SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00 SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00 SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30 SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0035 U,*	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30 SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0034 U,*	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 U	< 0.0036 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30 SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30 SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00 SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	0.036 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	0.019 J	0.0011 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.004 U	< 0.00054 U	< 0.00055 U	< 0.00045 U	< 0.00036 U	< 0.00059 U	< 0.00041 U	< 0.00036 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00068 U	< 0.00055 U	< 0.00043 U	< 0.00073 U	< 0.0005 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0044 U	< 0.0059 U	< 0.0006 U	< 0.0049 U	< 0.0039 U	< 0.00065 U	< 0.00045 U	< 0.00039 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.00051 U	< 0.0004 U	< 0.00067 U	< 0.00046 U	< 0.0004 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0047 U	< 0.00064 U	< 0.00065 U	< 0.00053 U	< 0.00042 U	< 0.0007 U	< 0.00048 U	< 0.00042 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.0064 U	< 0.00087 U	< 0.00088 U	< 0.00072 U	< 0.00057 U	< 0.00095 U	< 0.00066 U	< 0.00057 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0049 U	< 0.00067 U	< 0.00068 U	< 0.00055 U	< 0.00044 U	< 0.00073 U	< 0.00051 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.0045 U	< 0.00061 U	< 0.00062 U	< 0.0005 U	< 0.0004 U	< 0.00066 U	< 0.00046 U	< 0.0004 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0042 U	< 0.00057 U	< 0.00058 U	< 0.00047 U	< 0.00037 U	< 0.00062 U	< 0.00043 U	< 0.00038 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0049 U	< 0.00066 U	< 0.00067 U	< 0.00055 U	< 0.00043 U	< 0.00072 U	< 0.0005 U	< 0.00043 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00 SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00 SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45 SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45 SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30 SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30 SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00 SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00 SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00 SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	0.0077 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00 SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37			
Restricted - Residential												100			49			
Protection of Groundwater												1.1			0.37			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00_SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50_SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45_SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00_SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00_SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00_SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00_SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30_SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30_SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00_SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.00085 U	< 0.00082 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0009 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.00057 U	< 0.0012 U	< 0.00047 U	< 0.00068 U	< 0.0003 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.0007 U	< 0.0015 U	< 0.00057 U	< 0.00084 U	< 0.00036 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00062 U	< 0.0014 U	< 0.00051 U	< 0.00075 U	< 0.00033 U	< 0.00066 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.00064 U	< 0.0014 U	< 0.00053 U	< 0.00077 U	< 0.00034 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00072 U	< 0.00067 U	< 0.0015 U	< 0.00055 U	< 0.0008 U	< 0.00035 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.00097 U	< 0.00091 U	< 0.002 U	< 0.00075 U	< 0.0011 U	< 0.00048 U	< 0.00096 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00075 U	< 0.0007 U	< 0.0015 U	< 0.00058 U	< 0.00084 U	< 0.00037 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.00068 U	< 0.00064 U	< 0.0014 U	< 0.00052 U	< 0.00076 U	< 0.00033 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00064 U	< 0.0006 U	< 0.0013 U	< 0.00049 U	< 0.00072 U	< 0.00031 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00074 U	< 0.00069 U	< 0.0015 U	< 0.00057 U	< 0.00083 U	< 0.00036 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00_SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00_SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45_SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30_SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30_SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00_SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.001 UJ	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.00089 U	< 0.00086 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00094 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00_SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dichloromethane	1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05			1.1	2.4	1.8	0.27	0.02
Restricted - Residential												100			100	49	13	26	3.1
Protection of Groundwater												0.05			1.1	2.4	1.8	0.27	0.02
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00_SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50_SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45_SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00_SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00_SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00_SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00_SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0043 U	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0042 U	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30_SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30_SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00_SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00082 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0009 U	< 0.034 U	< 0.00032 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00054 U	< 0.00069 U	< 0.00054 U	< 0.00064 U	< 0.00053 U	< 0.00051 U	< 0.00046 U	< 0.00049 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00063 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00059 U	< 0.00076 U	< 0.00058 U	< 0.0007 U	< 0.00058 U	< 0.00056 U	< 0.0005 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00066 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00061 U	< 0.00078 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00058 U	< 0.00052 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00063 U	< 0.00081 U	< 0.00063 U	< 0.00075 U	< 0.00062 U	< 0.0006 U	< 0.00054 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.00086 U	< 0.0011 U	< 0.00085 U	< 0.001 U	< 0.00084 U	< 0.00082 U	< 0.00074 U	< 0.00079 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00066 U	< 0.00085 U	< 0.00066 U	< 0.00079 U	< 0.00065 U	< 0.00063 U	< 0.00057 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.0006 U	< 0.00077 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00057 U	< 0.00073 U	< 0.00056 U	< 0.00067 U	< 0.00055 U	< 0.00054 U	< 0.00049 U	< 0.00052 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00065 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.0006 U	< 0.00077 U	< 0.0006 U	< 0.00072 U	< 0.00059 U	< 0.00057 U	< 0.00052 U	< 0.00055 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00065 U	< 0.00084 U	< 0.00065 U	< 0.00078 U	< 0.00064 U	< 0.00062 U	< 0.00056 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00_SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00_SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45_SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30_SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30_SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00_SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00084 UJ	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00096 UJ	< 0.034 U	< 0.00084 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	0.0081	< 0.00086 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00094 U	< 0.034 U	< 0.00034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00_SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1-Dichloroethene	1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.33		0.25	0.19				1
Restricted - Residential												100		100	100				41
Protection of Groundwater												0.33		0.25	0.19				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00_SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50_SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45_SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00_SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00_SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00_SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00_SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0032 U	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0031 U	< 0.0043 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30_SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30_SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00_SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00082 U	< 0.00066 U	< 0.034 U	< 0.00092 U	< 0.0028 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00068 U		< 0.00057 U	< 0.00048 U	< 0.00044 U	< 0.00055 U	< 0.00048 U	< 0.00052 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00083 U		< 0.00069 U	< 0.00059 U	< 0.00053 U	< 0.00067 U	< 0.00059 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00074 U		< 0.00062 U	< 0.00052 U	< 0.00048 U	< 0.00059 U	< 0.00052 U	< 0.00056 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00083 U		< 0.00069 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00077 U		< 0.00064 U	< 0.00054 U	< 0.00049 U	< 0.00061 U	< 0.00054 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.0008 U		< 0.00066 U	< 0.00056 U	< 0.00051 U	< 0.00064 U	< 0.00056 U	< 0.00061 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.0011 U		< 0.0009 U	< 0.00076 U	< 0.0007 U	< 0.00087 U	< 0.00077 U	< 0.00082 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00084 U		< 0.0007 U	< 0.00059 U	< 0.00054 U	< 0.00067 U	< 0.00059 U	< 0.00064 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.00076 U		< 0.00063 U	< 0.00053 U	< 0.00049 U	< 0.00061 U	< 0.00054 U	< 0.00058 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00072 U		< 0.00059 U	< 0.0005 U	< 0.00046 U	< 0.00057 U	< 0.00051 U	< 0.00054 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00083 U		< 0.00069 U	< 0.00058 U	< 0.00053 U	< 0.00066 U	< 0.00058 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00_SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00_SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45_SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30_SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30_SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00_SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 UJ	< 0.0016 UJ	< 0.034 U	< 0.0031 UJ	< 0.034 U	< 0.0011 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00086 U	< 0.0007 U	< 0.034 U	< 0.00097 U	< 0.003 U	< 0.00046 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00_SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Freon 113	2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																		0.12		0.93
Restricted - Residential																		100		100
Protection of Groundwater																		0.12		0.93
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00_SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50_SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45_SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00_SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00_SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00_SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00_SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0021 U	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U,*	< 0.0021 U	< 0.0041 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0021 U	< 0.0046 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0032 U,*	< 0.002 U	< 0.004 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30_SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30_SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00_SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0071 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00097 U	< 0.034 U	< 0.0021 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00086 U	< 0.00056 U	< 0.00055 U	< 0.00072 U	< 0.00058 U	< 0.00071 U	< 0.00052 U	< 0.0006 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00071 U	< 0.00087 U	< 0.00064 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00094 U	< 0.00061 U	< 0.0006 U	< 0.00079 U	< 0.00064 U	< 0.00077 U	< 0.00057 U	< 0.00066 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00097 U	< 0.00062 U	< 0.00061 U	< 0.00082 U	< 0.00066 U	< 0.0008 U	< 0.00059 U	< 0.00068 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.001 U	< 0.00065 U	< 0.00064 U	< 0.00085 U	< 0.00068 U	< 0.00083 U	< 0.00062 U	< 0.00071 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.0014 U	< 0.00089 U	< 0.00087 U	< 0.0012 U	< 0.00093 U	< 0.0011 U	< 0.00084 U	< 0.00096 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0011 U	< 0.00068 U	< 0.00067 U	< 0.00089 U	< 0.00072 U	< 0.00087 U	< 0.00064 U	< 0.00074 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.00096 U	< 0.00062 U	< 0.00061 U	< 0.00081 U	< 0.00065 U	< 0.00079 U	< 0.00059 U	< 0.00067 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0009 U	< 0.00058 U	< 0.00057 U	< 0.00076 U	< 0.00061 U	< 0.00075 U	< 0.00055 U	< 0.00063 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.001 U	< 0.00067 U	< 0.00066 U	< 0.00088 U	< 0.00071 U	< 0.00086 U	< 0.00064 U	< 0.00073 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00_SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00_SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45_SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30_SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30_SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00_SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 UJ	< 0.034 U	< 0.0041 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U	< 0.0022 U	< 0.00066 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated								
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00_SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated								

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Styrene	1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68
Restricted - Residential														19	100			100
Protection of Groundwater														1.3	0.7			0.68
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00 SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50 SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45 SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00 SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00 SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00 SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00 SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30 SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0015 U	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30 SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0014 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0039 U	< 0.004 U	< 0.0027 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30 SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30 SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00 SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.00032 U	< 0.034 U	< 0.00086 U	< 0.00048 U	< 0.034 U	< 0.00039 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08 SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00057 U	< 0.00058 U	< 0.00055 U	< 0.00059 U	< 0.00068 U	< 0.00071 U	< 0.00039 U
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08 SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U	< 0.00048 U
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08 SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00062 U	< 0.00063 U	< 0.0006 U	< 0.00064 U	< 0.00074 U	< 0.00077 U	< 0.00043 U
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08 SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08 SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00064 U	< 0.00065 U	< 0.00062 U	< 0.00066 U	< 0.00076 U	< 0.0008 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08 SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00067 U	< 0.00068 U	< 0.00064 U	< 0.00069 U	< 0.0008 U	< 0.00083 U	< 0.00046 U
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15 SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.00091 U	< 0.00092 U	< 0.00087 U	< 0.00094 U	< 0.0011 U	< 0.0011 U	< 0.00062 U
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15 SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0007 U	< 0.00071 U	< 0.00067 U	< 0.00072 U	< 0.00083 U	< 0.00087 U	< 0.00048 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.00063 U	< 0.00064 U	< 0.00061 U	< 0.00065 U	< 0.00076 U	< 0.00079 U	< 0.00044 U
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15 SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0006 U	< 0.00061 U	< 0.00058 U	< 0.00062 U	< 0.00071 U	< 0.00075 U	< 0.00041 U
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15 SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00069 U	< 0.0007 U	< 0.00066 U	< 0.00071 U	< 0.00082 U	< 0.00086 U	< 0.00047 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00 SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00 SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45 SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45 SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45 SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30 SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30 SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00 SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00 SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00 SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.0013 UJ	< 0.034 U	< 0.0008 UJ	< 0.00085 UJ	< 0.034 U	< 0.0027 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30 SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 UJ	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.00034 U	< 0.034 U	< 0.0009 U	< 0.00051 U	< 0.034 U	< 0.00041 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00 SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated							

DRAFT

TABLE 6-3D
Subsurface Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2-Trichloroethane	Trichloroethene	Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.47		0.02			0.26
Restricted - Residential													21		0.9			100
Protection of Groundwater													0.47		0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S067	071719 09:00_SSHS-IRM3-S067-C	SSHS-IRM3-S067-C	7/16/2019	-	855.89	-	851.07	4 - 6 ft	4.82 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S032-BOT	072419 08:50_SSHS-IRM3-S032-BOT	SSHS-IRM3-S032-BOT	7/23/2019	-	855.70	-	850.96	4 - 6 ft	4.74 ft	180-93124-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S062	072519 08:45_SSHS-IRM3-S062-C	SSHS-IRM3-S062-C	7/24/2019	-	855.68	-	850.53	4 - 6 ft	5.15 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063A	073119 09:00_SSHS-IRM3-S063A-C	SSHS-IRM3-S063A-C	7/30/2019	-	855.67	-	850.94	4 - 6 ft	4.73 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063B	073119 09:00_SSHS-IRM3-S063B-C	SSHS-IRM3-S063B-C	7/30/2019	-	855.69	-	850.51	4 - 6 ft	5.18 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S063-BOT	073119 09:00_SSHS-IRM3-S063 BOT-C	SSHS-IRM3-S063 BOT-C	7/30/2019	-	855.69	-	849.76	4 - 6 ft	5.93 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S089C	073119 09:00_SSHS-IRM3-S089C-C	SSHS-IRM3-S089C-C	7/30/2019	-	855.55	-	849.59	4 - 6 ft	5.96 ft	180-93419-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	080319 09:30_SSHS-IRM3-PIPE7-C	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated	< 0.0027 U	< 0.0017 U	< 0.0016 U	< 0.0041 U		< 0.0027 U	< 0.0048 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	080319 09:30_SSHS-IRM3-PIPE9-C	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated	< 0.0026 U	< 0.0016 U	< 0.0016 U	< 0.004 U		< 0.0027 U	< 0.0047 U
Tennis Courts / Main Parking Lot	SSHS-IRM3-S085	080319 09:30_SSHS-IRM3-S085-C	SSHS-IRM3-S085-C	8/2/2019	-	855.69	-	850.40	4 - 6 ft	5.29 ft	180-93640-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S108	080319 09:30_SSHS-IRM3-S108-C	SSHS-IRM3-S108-C	8/2/2019	-	855.71	-	850.14	4 - 6 ft	5.57 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S083F	080919 09:00_SSHS-IRM3-S083F-C	SSHS-IRM3-S083F-C	8/8/2019	-	855.46	-	851.23	4 - 6 ft	4.23 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-4-6	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-4-6	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0074 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-4-6	SSHS-B4161-SUB-4-6	9/17/2021	858.24	858.24	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B82	081414 01:08_SSHS-B82-6-10 (8)	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00067 U	< 0.00053 U	< 0.00074 U	< 0.00038 U	< 0.0012 U	< 0.00063 U	
Tennis Courts / Main Parking Lot	SSHS-B83	081414 01:08_SSHS-B83-6-10 (8)	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00082 U	< 0.00065 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B85	081414 01:08_SSHS-B85-6-10 (8)	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00073 U	< 0.00058 U	< 0.00081 U	< 0.00041 U	< 0.0013 U	< 0.00068 U	
Tennis Courts / Main Parking Lot	SSHS-B86	081414 01:08_SSHS-B86-6-10 (8)	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00081 U	< 0.00064 U	< 0.0009 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B88	081414 01:08_SSHS-B88-6-10 (8)	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated	< 0.00075 U	< 0.0006 U	< 0.00083 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B89	081414 01:08_SSHS-B89-6-10 (7.5)	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated	< 0.00078 U	< 0.00062 U	< 0.00087 U	< 0.00044 U	< 0.0014 U	< 0.00074 U	
Tennis Courts / Main Parking Lot	SSHS-B78	081514 01:15_SSHS-B78-6-10 (8)	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated	< 0.0011 U	< 0.00084 U	< 0.0012 U	< 0.0006 U	< 0.0019 U	< 0.001 U	
Tennis Courts / Main Parking Lot	SSHS-B81	081514 01:15_SSHS-B81-6-10 (8)	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00082 U	< 0.00065 U	< 0.00091 U	< 0.00046 U	< 0.0015 U	< 0.00077 U	
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_DUP-13	DUP-13	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-2	Not Excavated	< 0.00075 U	< 0.00059 U	< 0.00082 U	< 0.00042 U	< 0.0013 U	< 0.0007 U	
Tennis Courts / Main Parking Lot	SSHS-B84	081514 01:15_SSHS-B84-6-10 (8)	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.0007 U	< 0.00056 U	< 0.00078 U	< 0.0004 U	< 0.0012 U	< 0.00066 U	
Tennis Courts / Main Parking Lot	SSHS-B87	081514 01:15_SSHS-B87-6-10 (8)	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated	< 0.00081 U	< 0.00064 U	< 0.00089 U	< 0.00046 U	< 0.0014 U	< 0.00076 U	
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-6-8	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S090	071719 09:00_SSHS-IRM3-S090-C	SSHS-IRM3-S090-C	7/16/2019	-	855.65	-	849.00	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S091	071719 09:00_SSHS-IRM3-S091-C	SSHS-IRM3-S091-C	7/16/2019	-	855.20	-	848.55	6 - 8 ft	6.65 ft	180-92715-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-DUP1	SSHS-IRM3-DUP1	7/24/2019	-	856.35	-	849.04	6 - 8 ft	14.01 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S086	072519 08:45_SSHS-IRM3-S086-C	SSHS-IRM3-S086-C	7/24/2019	-	855.75	-	849.04	6 - 8 ft	6.71 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S087	072519 08:45_SSHS-IRM3-S087-C	SSHS-IRM3-S087-C	7/24/2019	-	855.64	-	848.01	6 - 8 ft	7.63 ft	180-93173-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S131	080319 09:30_SSHS-IRM3-S131-C	SSHS-IRM3-S131-C	8/2/2019	-	855.73	-	849.20	6 - 8 ft	6.53 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S153	080319 09:30_SSHS-IRM3-S153-C	SSHS-IRM3-S153-C	8/2/2019	-	855.74	-	847.84	6 - 8 ft	7.9 ft	180-93640-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S110F	080919 09:00_SSHS-IRM3-S110F-D	SSHS-IRM3-S110F-D	8/8/2019	-	855.72	-	848.75	6 - 8 ft	6.97 ft	180-93896-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-DUP1-C	SSHS-IRM3-DUP1-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S133F	080919 09:00_SSHS-IRM3-S133F-C	SSHS-IRM3-S133F-C	8/8/2019	-	855.66	-	848.26	6 - 8 ft	7.4 ft	180-93896-1	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-6-8	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.034 U	0.0027 J	< 0.034 U	< 0.034 U	< 0.00086 UJ	< 0.034 U	< 0.0017 UJ
Tennis Courts / Main Parking Lot	SSHS-B4168	091621 09:30_SSHS-B4168-SUB-6-8	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-6-8	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-8-10	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated							
Tennis Courts / Main Parking Lot	SSHS-IRM3-S088	071719 09:00_SSHS-IRM3-S088-C	SSHS-IRM3-S088-C	7/16/2019	-	855.59	-	846.67	8 - 10 ft	8.92 ft	180-92715-1	Not Excavated							

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated			< 18 U						
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated			< 110 U						
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated			< 220 U						
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated			< 350 U						
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated			< 16 U						
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated			< 68 U						
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated			< 110 U						
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated			< 110 U						
Football Field	SSHS-IRM3-PIPE11	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated			< 110 U						
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated			< 120 U						
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated			< 110 U						
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-119861-1	Not Excavated			< 110 U	< 0.41 U	< 0.028 U	0.099 J	< 0.043 U	< 0.024 U	< 0.074 U
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated	< 110 U								
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated	< 130 U								
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated	< 120 U								
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated	< 130 U								
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated	< 130 U								
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated	< 120 U								
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated	< 340 U								
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated	< 110 U								
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated	< 330 U								
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated	< 110 UT								
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated	< 120 U								
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated	< 120 U								
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated	< 150 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated			< 110 U						
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated			< 140 U	< 0.062 U	< 0.049 U	< 0.06 U	< 0.067 U	< 0.062 U	< 0.039 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated			< 17 U						
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated			< 17 U						
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated			< 35 U						
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated			< 810 U						
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated			< 230 U						
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated			< 120 U						
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated	< 130 U								
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated	< 110 U								
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated	< 180 U								
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated	< 170 U								
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated	< 110 U								
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated	< 500 U								
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated	< 370 U								
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated	< 120 U								
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated	< 120 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated			< 110 U						
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated			< 110 U						

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated									
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated									
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated									
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated									
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated									
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated									
Football Field	SSHS-IRM3-PIPE11	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated									
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated									
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated									
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-119861-1	Not Excavated	< 0.039 U	< 0.032 U	< 0.034 U	0.049 J	< 0.04 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 UJ
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated									
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated									
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated									
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated									
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated									
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.063 U	< 0.049 U	< 0.038 U	< 0.04 U	< 0.029 U	< 34 U	< 0.056 U	< 0.069 U	< 0.053 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated									
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated									
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated									
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated									
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated									
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated									
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated									
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated									
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.05 U	< 0.039 U	< 0.03 U	< 0.032 U	< 0.022 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	SSHS-B2070	SSHS-B2070-SUB-0.17-2	7/25/2018	854.72	855.22	0.50	-	0.17 - 2 ft	0.67-2.5 ft	180-80157-3	Not Excavated						
Football Field	SSHS-B3475	SSHS-B3475-SUB-0.17-2	7/27/2020	855.34	855.39	0.05	-	0.17 - 2 ft	0.22-2.05 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B3477	SSHS-B3477-SUB-0.17-2	7/27/2020	855.68	855.71	0.03	-	0.17 - 2 ft	0.2-2.03 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B2223	SSHS-B2223-SUB-10-12	7/26/2018	856.38	856.37	-0.01	-	10 - 12 ft	9.99-11.99 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2224	SSHS-B2224-SUB-10-12	7/26/2018	854.93	855.29	0.36	-	10 - 12 ft	10.36-12.36 ft	180-80227-3	Not Excavated						
Football Field	SSHS-B2226	SSHS-B2226-SUB-10-12	7/26/2018	856.56	856.56	0.00	-	10 - 12 ft	10-12 ft	180-80227-1	Not Excavated						
Football Field	SSHS-B2762	SSHS-B2762-SUB-10-12	4/26/2019	856.14	856.25	0.11	-	10 - 12 ft	10.11-12.11 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2763	SSHS-B2763-SUB-10-12	4/26/2019	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-89521-1	Not Excavated						
Football Field	SSHS-IRM3-PIPE11	SSHS-IRM3-PIPE11-C	8/2/2019	-	856.57	-	845.91	10 - 12 ft	10.66 ft	180-93641-1	Not Excavated						
Football Field	SSHS-B2977	SSHS-B2977-SUB-10-12	11/7/2019	855.35	855.37	0.02	-	10 - 12 ft	10.02-12.02 ft	180-98520-1	Not Excavated						
Football Field	SSHS-B3461	SSHS-B3461-SUB-10-12	7/27/2020	856.51	856.51	0.00	-	10 - 12 ft	10-12 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.66	855.66	0.00	-	10 - 12 ft	10-12 ft	180-119861-1	Not Excavated	< 0.06 U	< 0.056 U	< 0.04 U	< 0.28 UJ	< 0.17 UJ	< 0.43 U
Football Field	IRM5-VAULT 2 S4	SSHS-IRM5-VAULT 2 S4	5/27/2021	-	855.33	-	844.87	10 - 12 ft	10.46 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 S5	SSHS-IRM5-VAULT 2 S5	5/27/2021	-	855.34	-	843.81	10 - 12 ft	11.53 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 N5	SSHS-IRM5-VAULT 2 N5	5/27/2021	-	855.41	-	844.75	10 - 12 ft	10.66 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W4	SSHS-IRM5-VAULT 2 W4	5/27/2021	-	855.49	-	844.77	10 - 12 ft	10.73 ft	1801223391	Not Excavated						
Football Field	ISMP-B527-S10	SSHS-ISMP-B527 S10	6/2/2021	-	855.64	-	845.09	10 - 12 ft	10.55 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S18	SSHS-ISMP-B527 S18	6/2/2021	-	855.42	-	843.95	10 - 12 ft	11.47 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S25	SSHS-ISMP-B527 S25	6/3/2021	-	855.80	-	845.63	10 - 12 ft	10.17 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S37	SSHS-ISMP-B527 S37	6/3/2021	-	855.38	-	843.85	10 - 12 ft	11.53 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S48	SSHS-ISMP-DUP 9	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S65	SSHS-ISMP-B527 S65	6/5/2021	-	855.92	-	844.62	10 - 12 ft	11.3 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S48	SSHS-ISMP-B527 S48	6/5/2021	-	855.81	-	845.23	10 - 12 ft	10.58 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S68	SSHS-ISMP-B527 S68	6/5/2021	-	855.92	-	844.61	10 - 12 ft	11.31 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S49	SSHS-ISMP-B527 S49	6/5/2021	-	855.80	-	844.22	10 - 12 ft	11.59 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S86	SSHS-ISMP-B527 S86	6/23/2021	-	855.61	-	844.62	10 - 12 ft	10.99 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S87	SSHS-ISMP-B527 S87	6/23/2021	-	855.69	-	844.34	10 - 12 ft	11.35 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S88	SSHS-ISMP-B527 S88	6/23/2021	-	855.62	-	844.58	10 - 12 ft	11.05 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S90	SSHS-ISMP-B572 S90	6/24/2021	-	855.69	-	845.67	10 - 12 ft	10.02 ft	1801236601	Not Excavated						
Football Field	ISMP-B527-S94	SSHS-ISMP-B527 S94	6/24/2021	-	855.61	-	845.33	10 - 12 ft	10.28 ft	1801236601	Not Excavated						
Football Field	ISMP-B527-S92	SSHS-ISMP-B527 S92	6/24/2021	-	855.51	-	844.02	10 - 12 ft	11.49 ft	1801236601	Not Excavated						
Football Field	ISMP-B527-S93	SSHS-ISMP-B527 S93	6/24/2021	-	855.52	-	845.35	10 - 12 ft	10.17 ft	1801236601	Not Excavated						
Football Field	ISMP-CB-3 BOT 1	SSHS-ISMP-CB-3 BOT 1	8/27/2021	-	855.76	-	844.45	10 - 12 ft	11.31 ft	1801263581	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-10-12	9/23/2021	856.42	856.42	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4165	SSHS-B4165-SUB-10-12	9/23/2021	856.00	856.00	0.00	-	10 - 12 ft	10-12 ft	180-127595-2	Not Excavated	< 0.048 U	< 34 U	< 0.054 U	< 0.045 U	< 0.035 U	< 0.03 U
Football Field	SSHS-B2197	SSHS-B2197-SUB-12-14	7/24/2018	854.99	855.43	0.44	-	12 - 14 ft	12.44-14.44 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2110	SSHS-B2110-SUB-12-14	7/25/2018	854.78	855.36	0.58	-	12 - 14 ft	12.58-14.58 ft	180-80154-1	Not Excavated						
Football Field	SSHS-B2195	SSHS-B2195-SUB-12-14	7/26/2018	855.94	855.94	0.00	-	12 - 14 ft	12-14 ft	180-80225-1	Not Excavated						
Football Field	SSHS-B2223	SSHS-B2223-SUB-12-14	7/26/2018	856.38	856.37	-0.01	-	12 - 14 ft	11.99-13.99 ft	180-80227-2	Not Excavated						
Football Field	SSHS-B2762	SSHS-B2762-SUB-12-14	4/26/2019	856.14	856.25	0.11	-	12 - 14 ft	12.11-14.11 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2977	SSHS-B2977-SUB-12-14	11/7/2019	855.35	855.37	0.02	-	12 - 14 ft	12.02-14.02 ft	180-98520-1	Not Excavated						
Football Field	IRM4A-1A-S2	SSHS-IRM4A-AREA 1A-S2	3/30/2021	-	855.48	-	842.51	12 - 14 ft	12.97 ft	1801192441	Not Excavated						
Football Field	IRM5-VAULT 2 S6	SSHS-IRM5-VAULT 2 S6	5/27/2021	-	855.34	-	842.12	12 - 14 ft	13.22 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 E5	SSHS-IRM5-VAULT 2 E5	5/27/2021	-	855.37	-	843.32	12 - 14 ft	12.05 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W5	SSHS-IRM5-VAULT 2 W5	5/27/2021	-	855.49	-	842.72	12 - 14 ft	12.77 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 E6	SSHS-IRM5-VAULT 2 E6	5/27/2021	-	855.35	-	842.09	12 - 14 ft	13.26 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W6	SSHS-IRM5-VAULT 2 W6	5/27/2021	-	855.49	-	842.04	12 - 14 ft	13.45 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 N6	SSHS-IRM5-VAULT 2 N6	5/27/2021	-	855.41	-	842.87	12 - 14 ft	12.54 ft	1801223391	Not Excavated						
Football Field	ISMP-B527-S11	SSHS-ISMP-B527 S11	6/2/2021	-	855.63	-	843.42	12 - 14 ft	12.22 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S12	SSHS-ISMP-B527 S12	6/2/2021	-	855.63	-	842.91	12 - 14 ft	12.72 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S19	SSHS-ISMP-B527 S19	6/2/2021	-	855.42	-	842.16	12 - 14 ft	13.26 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S26	SSHS-ISMP-B527 S26	6/3/2021	-	855.78	-	843.20	12 - 14 ft	12.58 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S33	SSHS-ISMP-B527 S33	6/3/2021	-	855.60	-	842.52	12 - 14 ft	13.08 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S38	SSHS-ISMP-B527 S38	6/3/2021	-	855.37	-	842.54	12 - 14 ft	12.83 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S66	SSHS-ISMP-B527 S66	6/5/2021	-	855.92	-	842.79	12 - 14 ft	13.13 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S69	SSHS-ISMP-B527 S69	6/5/2021	-	855.89	-	843.15	12 - 14 ft	12.74 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S50	SSHS-ISMP-B527 S50	6/5/2021	-	855.82	-	842.42	12 - 14 ft	13.4 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-BOT27	SSHS-ISMP-B527 BOT 27	6/23/2021	-	855.68	-	843.04	12 - 14 ft	12.64 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-BOT28	SSHS-ISMP-B527 BOT 28	6/23/2021	-	855.65	-	842.77	12 - 14 ft	12.88 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S91	SSHS-ISMP-B572 S91	6/24/2021	-	855.51	-	842.80	12 - 14 ft	12.71 ft	1801236601	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-12-14	9/23/2021	856.42	856.42	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4165	SSHS-B4165-SUB-12-14	9/23/2021	856.00	856.00	0.00	-	12 - 14 ft	12-14 ft	180-127595-2	Not Excavated	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated			< 110 U						
Football Field	SSHS-IRM3-PIPE10	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated			< 4600 U						
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated	< 120 U								
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated	< 120 U								
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated	< 120 U								
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated	< 460 U								
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated	< 450 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated			< 110 U						
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated			< 110 U						
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			< 120 U						
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			< 110 U						
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated			< 42 U						
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated			< 17 U						
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated			< 17 U						
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated			< 120 U						
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated			< 120 U						
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated			< 110 U						
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated			< 110 U						
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated			< 120 U						
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated			< 120 U						
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-S522	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated	< 120 U								
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated	< 110 U								
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated	< 110 U								
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated	< 120 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated			< 6000 U						
Football Field	ISMP-S601	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated	< 130 UT								
Football Field	ISMP-S604	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated	< 120 UT								
Football Field	ISMP-S608	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated	< 110 UT								
Football Field	SLT-S11	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated	< 120 U								
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated	< 120 U								
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated	< 120 U								
Football Field	ISMP-S621	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated	< 120 U								
Football Field	SLT-S42	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated	< 120 U								
Football Field	SLT-S43	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated	< 110 U								
Football Field	ISMP-S662	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated	< 120 U								
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 110 U								
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated	< 110 U								
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated	< 12 U								
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated	< 120 U								
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated	< 120 U								
Football Field	SLT-S50	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 120 U								
Football Field	SLT-S52	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated	< 120 U								
Football Field	SLT-S54	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated	< 120 U								
Football Field	ISMP-S670	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-S679	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated	< 110 U								
Football Field	ISMP-S689	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated	< 120 U								
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 130 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated									
Football Field	SSHS-IRM3-PIPE10	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated									
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated									
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated									
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated									
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated									
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated									
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated									
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated									
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated									
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated									
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated									
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated									
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated									
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated									
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated									
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated									
Football Field	ISMP-S522	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated									
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated									
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated									
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated									
Football Field	ISMP-S601	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated									
Football Field	ISMP-S604	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated									
Football Field	ISMP-S608	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated									
Football Field	SLT-S11	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated									
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated									
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated									
Football Field	ISMP-S621	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated									
Football Field	SLT-S42	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated									
Football Field	SLT-S43	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated									
Football Field	ISMP-S662	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated									
Football Field	ISMP-S636-S3	SSHS-ISMP-DUPI	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated									
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated									
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated									
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated									
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated									
Football Field	SLT-S50	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated									
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated									
Football Field	SLT-S52	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated									
Football Field	SLT-S54	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated									
Football Field	ISMP-S670	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated									
Football Field	ISMP-S679	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated									
Football Field	ISMP-S689	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated									
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated									
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated						
Football Field	SSHS-IRM3-PIPE10	SSHS-IRM3-PIPE10-C	8/2/2019	-	856.30	-	840.97	14 - 16 ft	15.33 ft	180-93641-1	Not Excavated						
Football Field	IRM4A-B040-BOT-BOT	SSHS-IRM4A-B040-BOT-BOT	11/20/2020	-	855.45	-	839.55	14 - 16 ft	15.9 ft	1801139241	Not Excavated						
Football Field	IRM4A-1A-S1	SSHS-IRM4A-AREA 1A-S1	3/30/2021	-	855.55	-	841.53	14 - 16 ft	14.02 ft	1801192441	Not Excavated						
Football Field	IRM4A-1A-BOT	SSHS-IRM4A-AREA 1A-BOT	3/30/2021	-	855.54	-	840.21	14 - 16 ft	15.33 ft	1801192441	Not Excavated						
Football Field	IRM5-VAULT 2 BOT	SSHS-IRM5-VAULT 2 BOT	5/27/2021	-	855.41	-	840.14	14 - 16 ft	15.28 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 S7	SSHS-IRM5-VAULT 2 S7	5/27/2021	-	855.33	-	840.69	14 - 16 ft	14.63 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 E7	SSHS-IRM5-VAULT 2 E7	5/27/2021	-	855.35	-	840.83	14 - 16 ft	14.52 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W7	SSHS-IRM5-VAULT 2 W7	5/27/2021	-	855.49	-	840.87	14 - 16 ft	14.62 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 N7	SSHS-IRM5-VAULT 2 N7	5/27/2021	-	855.40	-	840.75	14 - 16 ft	14.66 ft	1801223391	Not Excavated						
Football Field	ISMP-B527-S13	SSHS-ISMP-B527 S13	6/2/2021	-	855.60	-	840.93	14 - 16 ft	14.67 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S14	SSHS-ISMP-B527 S14	6/2/2021	-	855.60	-	840.05	14 - 16 ft	15.56 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S20	SSHS-ISMP-B527 S20	6/2/2021	-	855.43	-	840.76	14 - 16 ft	14.67 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S21	SSHS-ISMP-B527 S21	6/2/2021	-	855.45	-	839.81	14 - 16 ft	15.63 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-BOT21	SSHS-ISMP-B527 BOT 21	6/7/2021	-	855.84	-	841.28	14 - 16 ft	14.56 ft	1801228231	Not Excavated						
Football Field	ISMP-B527-BOT22	SSHS-ISMP-B527 BOT 22	6/7/2021	-	855.79	-	841.63	14 - 16 ft	14.16 ft	1801228231	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-14-16	9/23/2021	856.42	856.42	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4165	SSHS-B4165-SUB-14-16	9/23/2021	856.00	856.00	0.00	-	14 - 16 ft	14-16 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated						
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated						
Football Field	SSHS-B2187	SSHS-B2187-SUB-2-4	7/24/2018	856.10	856.10	0.00	-	2 - 4 ft	2-4 ft	180-80106-1	Not Excavated						
Football Field	SSHS-B2197	SSHS-B2197-SUB-2-4	7/24/2018	854.99	855.43	0.44	-	2 - 4 ft	2.44-4.44 ft	180-80105-1	Not Excavated						
Football Field	SSHS-B2026	SSHS-B2026-SUB-2-4	7/26/2018	855.26	855.47	0.21	-	2 - 4 ft	2.21-4.21 ft	180-80225-3	Not Excavated						
Football Field	SSHS-B2215A	SSHS-B2215A-SUB-2-4	5/21/2019	855.10	855.29	0.19	-	2 - 4 ft	2.19-4.19 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B3472	SSHS-B3472-SUB-2-4	7/27/2020	855.50	855.50	0.00	-	2 - 4 ft	2-4 ft	180-108826-2	Not Excavated						
Football Field	SSHS-B3474	SSHS-B3474-SUB-2-4	7/27/2020	855.64	855.65	0.01	-	2 - 4 ft	2.01-4.01 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B3475	SSHS-B3475-SUB-2-4	7/27/2020	855.34	855.39	0.05	-	2 - 4 ft	2.05-4.05 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B3476	SSHS-B3476-SUB-2-4	7/27/2020	855.25	855.45	0.20	-	2 - 4 ft	2.2-4.2 ft	180-108826-1	Not Excavated						
Football Field	SSHS-B3477	SSHS-B3477-SUB-2-4	7/27/2020	855.68	855.71	0.03	-	2 - 4 ft	2.03-4.03 ft	180-108826-1	Not Excavated						
Football Field	ISMP-B527-S61	SSHS-ISMP-B527 S61	6/5/2021	-	855.98	-	853.43	2 - 4 ft	2.55 ft	1801228121	Not Excavated						
Football Field	ISMP-S522	SSHS-ISMP-S522	6/9/2021	-	855.95	-	852.09	2 - 4 ft	3.86 ft	1801229791	Not Excavated						
Football Field	ISMP-B527-S78	SSHS-ISMP-B527 S78	6/23/2021	-	855.82	-	851.92	2 - 4 ft	3.91 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S106	SSHS-ISMP-B527 S106	6/28/2021	-	855.53	-	851.78	2 - 4 ft	3.75 ft	1801237721	Not Excavated						
Football Field	ISMP-B527-S110	SSHS-ISMP-B527 S110	6/28/2021	-	855.59	-	851.82	2 - 4 ft	3.77 ft	1801237721	Not Excavated						
Football Field	ISMP-CB-7 S3	SSHS-ISMP-CB-7 S3	8/28/2021	-	855.89	-	852.55	2 - 4 ft	3.34 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S8	SSHS-ISMP-CB-7 S8	8/28/2021	-	855.92	-	852.60	2 - 4 ft	3.32 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S11	SSHS-ISMP-CB-7 S11	8/28/2021	-	856.12	-	852.50	2 - 4 ft	3.62 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S15	SSHS-ISMP-CB-7 S15	8/29/2021	-	856.11	-	852.64	2 - 4 ft	3.47 ft	1801264041	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-2-4	9/23/2021	856.42	856.42	0.00	-	2 - 4 ft	2-4 ft	180-127595-2	Not Excavated						
Football Field	ISMP-S601	SSHS-ISMP-S601	10/7/2021	-	856.42	-	852.82	2 - 4 ft	3.6 ft	1801282631	Not Excavated						
Football Field	ISMP-S604	SSHS-ISMP-S604	10/7/2021	-	856.48	-	852.91	2 - 4 ft	3.57 ft	1801282631	Not Excavated						
Football Field	ISMP-S608	SSHS-ISMP-S608	10/7/2021	-	856.22	-	853.47	2 - 4 ft	2.76 ft	1801282631	Not Excavated						
Football Field	SLT-S11	SSHS-ISMP-SLT-S11	10/14/2021	-	856.21	-	852.72	2 - 4 ft	3.49 ft	1801285251	Not Excavated						
Football Field	ISMP-S001	SSHS-ISMP-STOR-S001	10/27/2021	-	855.47	-	851.89	2 - 4 ft	3.58 ft	1801291091	Not Excavated						
Football Field	ISMP-S002	SSHS-ISMP-STOR-S002	10/27/2021	-	855.64	-	851.95	2 - 4 ft	3.69 ft	1801291091	Not Excavated						
Football Field	ISMP-S621	SSHS-ISMP-S621	12/2/2021	-	855.65	-	851.71	2 - 4 ft	3.94 ft	1801306501	Not Excavated						
Football Field	SLT-S42	SSHS-ISMP-SLT-S42	12/7/2021	-	855.80	-	852.02	2 - 4 ft	3.79 ft	1801308711	Not Excavated						
Football Field	SLT-S43	SSHS-ISMP-SLT-S43	12/7/2021	-	855.85	-	852.08	2 - 4 ft	3.76 ft	1801308711	Not Excavated						
Football Field	ISMP-S662	SSHS-ISMP-S662	12/16/2021	-	855.84	-	852.12	2 - 4 ft	3.72 ft	1801314041	Not Excavated						
Football Field	ISMP-S636-S3	SSHS-ISMP-DUP1	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated						
Football Field	ISMP-S636-S3	SSHS-ISMP-S636-S3	12/30/2021	-	855.87	-	852.58	2 - 4 ft	3.29 ft	1801318801	Not Excavated						
Football Field	SLT-S34-BOT-S3	SSHS-ISMP-SLT-S34-BOT-S3	1/3/2022	-	856.11	-	852.73	2 - 4 ft	3.38 ft	1801318901	Not Excavated						
Football Field	SLT-S34-BOT-S1	SSHS-ISMP-SLT-S34-BOT-S1	1/3/2022	-	856.01	-	852.23	2 - 4 ft	3.77 ft	1801318901	Not Excavated						
Football Field	ISMP-PIPE1-S14	SSHS-ISMP-PIPE1-S14	1/7/2022	-	855.93	-	852.33	2 - 4 ft	3.6 ft	1801321211	Not Excavated						
Football Field	SLT-S50	SSHS-ISMP-SLT-S50	1/10/2022	-	856.55	-	853.24	2 - 4 ft	3.31 ft	1801321411	Not Excavated						
Football Field	SLT-S52	SSHS-ISMP-SLT-DUP9	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated						
Football Field	SLT-S52	SSHS-ISMP-SLT-S52	1/12/2022	-	856.56	-	852.71	2 - 4 ft	3.85 ft	1801322501	Not Excavated						
Football Field	SLT-S54	SSHS-ISMP-SLT-S54	1/12/2022	-	856.60	-	852.86	2 - 4 ft	3.74 ft	1801322501	Not Excavated						
Football Field	ISMP-S670	SSHS-ISMP-S670	2/28/2022	-	855.57	-	851.70	2 - 4 ft	3.87 ft	1801343691	Not Excavated						
Football Field	ISMP-S679	SSHS-ISMP-S679	2/28/2022	-	855.93	-	852.63	2 - 4 ft	3.3 ft	1801343691	Not Excavated						
Football Field	ISMP-S689	SSHS-ISMP-S689	2/28/2022	-	855.61	-	851.62	2 - 4 ft	3.99 ft	1801343691	Not Excavated						
Football Field	ISMP-PIPE4	SSHS-ISMP-PIPE4	2/28/2022	-	855.94	-	852.32	2 - 4 ft	3.62 ft	1801343681	Not Excavated						
Football Field	SLT-S64B	SSHS-ISMP-SLT-DUP10	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-S703	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated	< 120 U								
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-S67	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated	< 130 U								
Football Field	SLT-S61	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated	< 130 U								
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated	< 120 U								
Football Field	ISMP-S2003	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated	< 120 U								
Football Field	ISMP-S2013	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated	< 120 U								
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated	< 110 U								
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated	< 110 U								
Football Field	SLT-S97	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated	< 110 U								
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated	< 440 U								
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated	< 120 U								
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated	< 120 U								
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated		< 32 U							
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated		< 34 U							
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated	< 110 U								
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated	< 120 U								
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated	< 120 U								
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated		< 29 U							
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated		< 33 U							
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated		< 31 U							
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated		< 30 U							
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422542	Not Excavated				< 0.049 U	< 0.039 U	0.049 J	0.39	0.20 J	0.051 J
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		< 32 U							
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		< 160 U							
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated		< 31 U							
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422542	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.927	1801422541	Not Excavated		< 31 U							
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated		< 31 U							
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated	< 120 U								
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated	< 260 U								
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated	< 120 U								
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435312	Not Excavated				< 0.052 UHT	< 0.042 UHT	< 0.050 UHT	0.14 JHT	< 0.052 UHT	< 0.033 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/25/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801435312	Not Excavated				< 0.046 UHT	< 0.036 UHT	< 0.044 UHT	< 0.049 UHT	< 0.046 UHT	< 0.028 UHT
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated	< 110 U								
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated	< 110 U								
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated	< 120 U								
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated			< 120 U						
Football Field	IRM5-S085	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated	< 120 U								
Football Field	IRM5-S090	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated	< 120 U								
Football Field	IRM5-S089	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated	< 120 U								
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated	< 120 U								
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated	< 200 U								
Football Field	ISMP-B544	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated	< 120 U								
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated	< 110 U								
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated	< 120 U								
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated	< 110 U								
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated	< 110 U								
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated	< 550 U								
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated	< 130 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-S703	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated									
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated									
Football Field	SLT-S67	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated									
Football Field	SLT-S61	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated									
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated									
Football Field	ISMP-S2003	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated									
Football Field	ISMP-S2013	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated									
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated									
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated									
Football Field	SLT-S97	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated									
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated									
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated									
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated									
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated									
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated									
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated									
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated									
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated									
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated									
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated									
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated									
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated									
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated									
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422542	Not Excavated	< 0.050 U	0.045 J	< 0.030 U	0.076 J	0.049 J	< 0.034 U	0.12 J	0.060 J	0.091 J
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated									
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated									
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated									
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422542	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.927	1801422541	Not Excavated									
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated									
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated									
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated									
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated									
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated									
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated									
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated									
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435312	Not Excavated	< 0.054 UHT	< 0.042 UHT	0.11 JHT	< 0.034 UHT	< 0.024 UHT	< 0.036 UHT	1.1 HT	< 0.058 UHT	< 0.045 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated									
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated									
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/25/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801435312	Not Excavated	< 0.047 UHT	< 0.036 UHT	< 0.028 UHT	< 0.029 UHT	< 0.021 UHT	< 0.031 UHT	< 0.041 UHT	< 0.050 UHT	0.048 JHT
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated									
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated									
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated									
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated									
Football Field	IRM5-S085	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated									
Football Field	IRM5-S090	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated									
Football Field	IRM5-S089	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated									
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated									
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated									
Football Field	ISMP-B544	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated									
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated									
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated									
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated									
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated									
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	ISMP-S703	SSHS-ISMP-S703	3/1/2022	-	856.03	-	852.43	2 - 4 ft	3.6 ft	1801344451	Not Excavated						
Football Field	SLT-S64B	SSHS-ISMP-SLT-S64B	3/1/2022	-	855.67	-	851.99	2 - 4 ft	3.68 ft	1801344461	Not Excavated						
Football Field	SLT-S67	SSHS-ISMP-SLT-S67	3/1/2022	-	855.58	-	851.82	2 - 4 ft	3.76 ft	1801344461	Not Excavated						
Football Field	SLT-S61	SSHS-ISMP-SLT-S61	3/1/2022	-	855.90	-	852.83	2 - 4 ft	3.07 ft	1801344461	Not Excavated						
Football Field	ISMP-PIPE3-S3	SSHS-ISMP-PIPE3-S3	3/5/2022	-	855.72	-	852.38	2 - 4 ft	3.34 ft	1801347831	Not Excavated						
Football Field	ISMP-S2003	SSHS-ISMP-S2003	3/8/2022	-	855.59	-	851.75	2 - 4 ft	3.84 ft	1801348411	Not Excavated						
Football Field	ISMP-S2013	SSHS-ISMP-S2013	3/9/2022	-	856.01	-	852.65	2 - 4 ft	3.36 ft	1801349171	Not Excavated						
Football Field	MS-SLT-S79	SSHS-ISMP-MS-SLT-S79	3/22/2022	-	856.19	-	853.72	2 - 4 ft	2.47 ft	1801355361	Not Excavated						
Football Field	SLT-BOT29	SSHS-ISMP-SLT-BOT29	3/24/2022	-	855.50	-	852.03	2 - 4 ft	3.47 ft	1801357101	Not Excavated						
Football Field	SLT-S97	SSHS-ISMP-SLT-S97	3/24/2022	-	855.49	-	852.41	2 - 4 ft	3.08 ft	1801357101	Not Excavated						
Football Field	IRM5-FP-BOT3	SSHS-IRM5-FP-BOT3	3/24/2022	-	855.22	-	852.68	2 - 4 ft	2.54 ft	1801357111	Not Excavated						
Football Field	IRM5-FP-S7	SSHS-IRM5-FP-S7	3/28/2022	-	855.07	-	851.32	2 - 4 ft	3.75 ft	1801358371	Not Excavated						
Football Field	ISMP-TPA1-BOT1	SSHS-ISMP-TPA1-BOT1	3/30/2022	-	854.44	-	850.58	2 - 4 ft	3.86 ft	1801359731	Not Excavated						
Football Field	ISMP-TPA1-S5	SSHS-ISMP-TPA1-S5	3/30/2022	-	853.28	-	850.80	2 - 4 ft	2.48 ft	1801359731	Not Excavated						
Football Field	SSHS-ISMP-CWP-B1	SSHS-ISMP-CWP-B1	5/19/2022	-	856.53	-	853.97	2 - 4 ft	2.56 ft	1801383881	Not Excavated						
Football Field	SSHS-ISMP-CWP-B2	SSHS-ISMP-CWP-B2	5/19/2022	-	856.31	-	854.13	2 - 4 ft	2.18 ft	1801383881	Not Excavated						
Football Field	ISMP-RAMP1	SSHS-ISMP-RAMP1	5/27/2022	-	855.24	-	852.68	2 - 4 ft	2.56 ft	1801388091	Not Excavated						
Football Field	ISMP-RAMP2	SSHS-ISMP-RAMP2	5/27/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801388091	Not Excavated						
Football Field	ISMP-RAMP-S3	SSHS-ISMP-RAMP-S3	5/27/2022	-	855.42	-	852.72	2 - 4 ft	2.7 ft	1801388091	Not Excavated						
Football Field	ISMP-RAMP-S5	SSHS-ISMP-RAMP-S5	6/20/2022	-	855.42	-	852.96	2 - 4 ft	2.46 ft	1801400201	Not Excavated						
Football Field	ISMP-RAMP-BOT3	SSHS-ISMP-RAMP-BOT3	6/20/2022	-	855.91	-	852.99	2 - 4 ft	2.92 ft	1801400201	Not Excavated						
Football Field	ISMP-RAMP-S3-BOT	SSHS-ISMP-RAMP-S3-BOT	6/20/2022	-	855.40	-	852.85	2 - 4 ft	2.55 ft	1801400201	Not Excavated						
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422541	Not Excavated						
Football Field	SSHS-IRM5A3-S1	SSHS-IRM5A3-S1	8/1/2022	-	855.67	-	853.26	2 - 4 ft	2.41 ft	1801422542	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Football Field	SSHS-IRM5A3-S2	SSHS-IRM5A3-S2	8/1/2022	-	--	-	853.37	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated						
Football Field	SSHS-IRM5A3-S4	SSHS-IRM5A3-S4	8/1/2022	-	--	-	853.39	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated						
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422541	Not Excavated						
Football Field	SSHS-IRM5A3-B1	SSHS-IRM5A3-B1	8/1/2022	-	--	-	853.25	2 - 4 ft	2 - 4 ft	1801422542	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Football Field	SSHS-IRM5A3-B2	SSHS-IRM5A3-B2	8/1/2022	-	855.97	-	853.04	2 - 4 ft	2.927	1801422541	Not Excavated						
Football Field	SSHS-IRM5A3-B3	SSHS-IRM5A3-B3	8/1/2022	-	855.57	-	853.16	2 - 4 ft	2.41 ft	1801422541	Not Excavated						
Football Field	SSHS-ISMP-ES-S6	SSHS-ISMP-ES-S6	8/22/2022	-	855.21	-	853.01	2 - 4 ft	2.2 ft	1801432981	Not Excavated						
Football Field	SSHS-ISMP-ES-S7	SSHS-ISMP-ES-S7	8/22/2022	-	854.98	-	852.64	2 - 4 ft	2.35 ft	1801432981	Not Excavated						
Football Field	SSHS-ISMP-ES-B4	SSHS-ISMP-ES-B4	8/22/2022	-	855.77	-	853.19	2 - 4 ft	2.58 ft	1801432981	Not Excavated						
Football Field	SSHS-ISMP-ES-B5	SSHS-ISMP-ES-B5	8/25/2022	-	855.47	-	852.91	2 - 4 ft	2.56 ft	1801435311	Not Excavated						
Football Field	SSHS-ISMP-ES-S9	SSHS-ISMP-ES-S9	8/25/2022	-	854.77	-	851.86	2 - 4 ft	2.91 ft	1801435311	Not Excavated						
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435311	Not Excavated						
Football Field	SSHS-ISMP-ES-S10	SSHS-ISMP-ES-S10	8/25/2022	-	855.34	-	853.00	2 - 4 ft	2.34 ft	1801435312	Not Excavated	< 0.040 UHT	< 0.023 UHT	< 0.046 UHT	< 0.038 UHT	< 0.029 UHT	< 0.025 UHT
Football Field	SSHS-ISMP-ES-B6	SSHS-ISMP-ES-B6	8/25/2022	-	856.40	-	853.88	2 - 4 ft	2.52 ft	1801435311	Not Excavated						
Football Field	SSHS-ISMP-ES-S14	SSHS-ISMP-ES-S14	8/25/2022	-	856.34	-	854.23	2 - 4 ft	2.11 ft	1801435311	Not Excavated						
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/25/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801435312	Not Excavated	< 0.035 UHT	< 0.020 UHT	< 0.040 UHT	< 0.033 UHT	< 0.026 UHT	< 0.022 UHT
Football Field	SSHS-ISMP-ES-S18	SSHS-ISMP-ES-S18	8/29/2022	-	856.65	-	854.56	2 - 4 ft	2.09 ft	1801436521	Not Excavated						
Football Field	SSHS-ISMP-ES-S16	SSHS-ISMP-ES-S16	8/29/2022	-	856.53	-	854.51	2 - 4 ft	2.02 ft	1801436521	Not Excavated						
Football Field	SSHS-B2791	SSHS-B2791-SUB-4-6	5/21/2019	854.92	855.51	0.59	-	4 - 6 ft	4.59-6.59 ft	180903801	Not Excavated						
Football Field	SSHS-B3461	SSHS-B3461-SUB-4-6	7/27/2020	856.51	856.51	0.00	-	4 - 6 ft	4-6 ft	180-108826-2	Not Excavated						
Football Field	IRM5-S085	SSHS-IRM5-S085	4/15/2021	-	855.47	-	849.62	4 - 6 ft	5.85 ft	1801200643	Not Excavated						
Football Field	IRM5-S090	SSHS-IRM5-S090	4/15/2021	-	855.62	-	850.16	4 - 6 ft	5.46 ft	1801200643	Not Excavated						
Football Field	IRM5-S089	SSHS-IRM5-S089	4/15/2021	-	855.18	-	850.64	4 - 6 ft	4.54 ft	1801200643	Not Excavated						
Football Field	IRM5-VAULT 2 N1	SSHS-IRM5-VAULT 2 N1	5/27/2021	-	855.37	-	849.57	4 - 6 ft	5.8 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W1	SSHS-IRM5-VAULT 2 W1	5/27/2021	-	855.55	-	849.47	4 - 6 ft	6.08 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 S1	SSHS-IRM5-VAULT 2 S1	5/27/2021	-	855.34	-	850.68	4 - 6 ft	4.66 ft	1801223391	Not Excavated						
Football Field	ISMP-B527-S8	SSHS-ISMP-B527 S8	6/2/2021	-	855.66	-	851.37	4 - 6 ft	4.29 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S1	SSHS-ISMP-B527 S1	6/2/2021	-	855.69	-	850.89	4 - 6 ft	4.8 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S2	SSHS-ISMP-B527 S2	6/2/2021	-	855.66	-	850.50	4 - 6 ft	5.16 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S3	SSHS-ISMP-B527 S3	6/2/2021	-	855.66	-	850.22	4 - 6 ft	5.44 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S15	SSHS-ISMP-B527 S15	6/2/2021	-	855.40	-	851.11	4 - 6 ft	4.29 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S23	SSHS-ISMP-B527 S23	6/3/2021	-	855.83	-	850.33	4 - 6 ft	5.5 ft	1801226361	Not Excavated						
Football Field	ISMP-B544	SSHS-ISMP-B544	6/9/2021	-	855.94	-	850.76	4 - 6 ft	5.18 ft	1801229791	Not Excavated						
Football Field	ISMP-B527-S76	SSHS-ISMP-B527-S76	6/11/2021	-	855.26	-	849.46	4 - 6 ft	5.8 ft	1801231161	Not Excavated						
Football Field	ISMP-B527-BOT25	SSHS-ISMP-B527 BOT 25	6/23/2021	-	855.79	-	850.17	4 - 6 ft	5.62 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S77	SSHS-ISMP-B527 S77	6/23/2021	-	855.79	-	851.07	4 - 6 ft	4.72 ft	1801235891	Not Excavated						
Football Field	ISMP-B527-S101	SSHS-ISMP-B527 S101	6/25/2021	-	855.53	-	849.53	4 - 6 ft	6 ft	1801237471	Not Excavated						
Football Field	ISMP-B527-S99	SSHS-ISMP-B527 S99	6/25/2021	-	855.61	-	849.87	4 - 6 ft	5.74 ft	1801237471	Not Excavated						
Football Field	ISMP-B527-S102	SSHS-ISMP-B527 S102	6/25/2021	-	855.65	-	850.23	4 - 6 ft	5.42 ft	1801237471	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated	< 110 U								
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated	< 110 U								
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated	< 130 U								
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated	< 110 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated			< 120 U						
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated			< 120 U						
Football Field	ISMP-S605	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 110 UT								
Football Field	ISMP-B606	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated	< 120 UT								
Football Field	ISMP-B607	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated	< 110 UT								
Football Field	ISMP-B608	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated	< 110 UT								
Football Field	ISMP-S602	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 120 UT								
Football Field	ISMP-S605	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated	< 120 UT								
Football Field	ISMP-S606	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated	< 110 UT								
Football Field	ISMP-S609	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated	< 110 UT								
Football Field	ISMP-S611	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated	< 110 UT								
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 120 U								
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated	< 120 U								
Football Field	SLT-S9	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated	< 130 U								
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated	< 130 U								
Football Field	SLT-S4	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated	< 130 U								
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated	< 130 U								
Football Field	SLT-S6	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated	< 130 U								
Football Field	SLT-S12	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated	< 130 U								
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated	< 130 U								
Football Field	SLT-S15	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated	< 120 U								
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated	< 110 U								
Football Field	SLT-S19	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated	< 110 U								
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated	< 110 U								
Football Field	SLT-S18	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated	< 110 U								
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated	< 120 U								
Football Field	SLT-S31	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated	< 120 U								
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated	< 110 U								
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated	< 120 U								
Football Field	ISMP-S612	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 110 U								
Football Field	ISMP-S612	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated	< 110 U								
Football Field	ISMP-B609	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated	< 110 U								
Football Field	ISMP-S614	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated	< 120 U								
Football Field	ISMP-S615	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated	< 120 U								
Football Field	ISMP-S617	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated	< 230 U								
Football Field	ISMP-B610	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated	< 110 U								
Football Field	ISMP-S625	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated	< 120 U								
Football Field	ISMP-S629	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated	< 120 U								
Football Field	ISMP-B618	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 120 U								
Football Field	ISMP-S639	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated	< 120 U								
Football Field	ISMP-B617	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated	< 130 U								
Football Field	ISMP-S640	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated	< 130 U								
Football Field	ISMP-S641	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated	< 120 U								
Football Field	ISMP-S643	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated	< 130 U								
Football Field	ISMP-S645	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated	< 110 U								
Football Field	ISMP-B618	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated	< 110 U								
Football Field	ISMP-S647	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated	< 120 U								
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 110 U								
Football Field	SLT-S37	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated	< 220 U								
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated	< 110 U								
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated	< 120 U								
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated	< 120 U								
Football Field	ISMP-S659	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated	< 120 U								
Football Field	ISMP-B623	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 110 U								
Football Field	ISMP-S667	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated									
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated									
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated									
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated									
Football Field	ISMP-S605	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated									
Football Field	ISMP-B606	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated									
Football Field	ISMP-B607	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated									
Football Field	ISMP-B608	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated									
Football Field	ISMP-S602	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated									
Football Field	ISMP-S605	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated									
Football Field	ISMP-S606	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated									
Football Field	ISMP-S609	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated									
Football Field	ISMP-S611	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated									
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated									
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated									
Football Field	SLT-S9	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated									
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated									
Football Field	SLT-S4	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated									
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated									
Football Field	SLT-S6	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated									
Football Field	SLT-S12	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated									
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated									
Football Field	SLT-S15	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated									
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated									
Football Field	SLT-S19	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated									
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated									
Football Field	SLT-S18	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated									
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated									
Football Field	SLT-S31	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated									
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated									
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated									
Football Field	ISMP-S612	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated									
Football Field	ISMP-S612	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated									
Football Field	ISMP-B609	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated									
Football Field	ISMP-S614	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated									
Football Field	ISMP-S615	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated									
Football Field	ISMP-S617	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated									
Football Field	ISMP-B610	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated									
Football Field	ISMP-S625	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated									
Football Field	ISMP-S629	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated									
Football Field	ISMP-B618	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated									
Football Field	ISMP-S639	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated									
Football Field	ISMP-B617	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated									
Football Field	ISMP-S640	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated									
Football Field	ISMP-S641	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated									
Football Field	ISMP-S643	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated									
Football Field	ISMP-S645	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated									
Football Field	ISMP-B618	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated									
Football Field	ISMP-S647	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated									
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated									
Football Field	SLT-S37	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated									
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated									
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated									
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated									
Football Field	ISMP-S659	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated									
Football Field	ISMP-B623	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated									
Football Field	ISMP-S667	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	ISMP-B527-S103	SSHS-ISMP-B527 S103	6/28/2021	-	855.65	-	851.27	4 - 6 ft	4.38 ft	1801237721	Not Excavated						
Football Field	ISMP-B527-S105	SSHS-ISMP-B527 S105	6/28/2021	-	855.53	-	850.58	4 - 6 ft	4.95 ft	1801237721	Not Excavated						
Football Field	ISMP-B527-S109	SSHS-ISMP-B527 S109	6/28/2021	-	855.61	-	850.59	4 - 6 ft	5.02 ft	1801237721	Not Excavated						
Football Field	ISMP-CB-7 S2	SSHS-ISMP-CB-7 S2	8/28/2021	-	855.89	-	850.55	4 - 6 ft	5.34 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S7	SSHS-ISMP-CB-7 S7	8/28/2021	-	855.92	-	850.60	4 - 6 ft	5.32 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S16	SSHS-ISMP-CB-7 S16	8/29/2021	-	856.11	-	850.64	4 - 6 ft	5.47 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S28	SSHS-ISMP-CB-7 S28	8/29/2021	-	856.20	-	851.20	4 - 6 ft	5 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S12	SSHS-ISMP-CB-7 S12	8/29/2021	-	856.12	-	850.50	4 - 6 ft	5.62 ft	1801264041	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-4-6	9/23/2021	856.42	856.42	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4165	SSHS-B4165-SUB-4-6	9/23/2021	856.00	856.00	0.00	-	4 - 6 ft	4-6 ft	180-127595-2	Not Excavated						
Football Field	ISMP-S605	SSHS-ISMP-DUPA	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated						
Football Field	ISMP-B606	SSHS-ISMP-B606	10/7/2021	-	856.46	-	850.69	4 - 6 ft	5.77 ft	1801282631	Not Excavated						
Football Field	ISMP-B607	SSHS-ISMP-B607	10/7/2021	-	856.17	-	850.91	4 - 6 ft	5.26 ft	1801282631	Not Excavated						
Football Field	ISMP-B608	SSHS-ISMP-B608	10/7/2021	-	855.89	-	850.66	4 - 6 ft	5.23 ft	1801282631	Not Excavated						
Football Field	ISMP-S602	SSHS-ISMP-S602	10/7/2021	-	856.42	-	851.49	4 - 6 ft	4.93 ft	1801282631	Not Excavated						
Football Field	ISMP-S605	SSHS-ISMP-S605	10/7/2021	-	856.46	-	851.35	4 - 6 ft	5.11 ft	1801282631	Not Excavated						
Football Field	ISMP-S606	SSHS-ISMP-S606	10/7/2021	-	856.14	-	851.69	4 - 6 ft	4.46 ft	1801282631	Not Excavated						
Football Field	ISMP-S609	SSHS-ISMP-S609	10/7/2021	-	856.21	-	851.97	4 - 6 ft	4.24 ft	1801282631	Not Excavated						
Football Field	ISMP-S611	SSHS-ISMP-S611	10/7/2021	-	855.88	-	850.95	4 - 6 ft	4.93 ft	1801282631	Not Excavated						
Football Field	SLT-S31	SSHS-ISMP-SLT-DUP4	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated						
Football Field	SLT-BOT1	SSHS-ISMP-SLT-BOT1	10/14/2021	-	855.79	-	851.52	4 - 6 ft	4.27 ft	1801285251	Not Excavated						
Football Field	SLT-S9	SSHS-ISMP-SLT-S9	10/14/2021	-	856.17	-	851.51	4 - 6 ft	4.66 ft	1801285251	Not Excavated						
Football Field	SLT-BOT2	SSHS-ISMP-SLT-BOT2	10/14/2021	-	855.99	-	851.55	4 - 6 ft	4.45 ft	1801285251	Not Excavated						
Football Field	SLT-S4	SSHS-ISMP-SLT-S4	10/14/2021	-	855.97	-	851.61	4 - 6 ft	4.36 ft	1801285251	Not Excavated						
Football Field	SLT-BOT3	SSHS-ISMP-SLT-BOT3	10/14/2021	-	856.18	-	851.37	4 - 6 ft	4.82 ft	1801285241	Not Excavated						
Football Field	SLT-S6	SSHS-ISMP-SLT-S6	10/14/2021	-	856.02	-	851.71	4 - 6 ft	4.31 ft	1801285251	Not Excavated						
Football Field	SLT-S12	SSHS-ISMP-SLT-S12	10/14/2021	-	856.21	-	851.44	4 - 6 ft	4.77 ft	1801285251	Not Excavated						
Football Field	SLT-BOT4	SSHS-ISMP-SLT-BOT4	10/14/2021	-	856.22	-	851.11	4 - 6 ft	5.11 ft	1801285251	Not Excavated						
Football Field	SLT-S15	SSHS-ISMP-SLT-S15	10/14/2021	-	856.20	-	851.21	4 - 6 ft	4.99 ft	1801285251	Not Excavated						
Football Field	SLT-BOT6	SSHS-ISMP-SLT-BOT6	10/14/2021	-	856.32	-	851.09	4 - 6 ft	5.23 ft	1801285252	Not Excavated						
Football Field	SLT-S19	SSHS-ISMP-SLT-S19	10/14/2021	-	856.44	-	851.50	4 - 6 ft	4.94 ft	1801285252	Not Excavated						
Football Field	SLT-BOT5	SSHS-ISMP-SLT-BOT5	10/14/2021	-	856.35	-	851.49	4 - 6 ft	4.86 ft	1801285252	Not Excavated						
Football Field	SLT-S18	SSHS-ISMP-SLT-S18	10/14/2021	-	856.42	-	851.59	4 - 6 ft	4.83 ft	1801285252	Not Excavated						
Football Field	SLT-BOT7	SSHS-ISMP-SLT-BOT7	10/14/2021	-	856.37	-	851.35	4 - 6 ft	5.02 ft	1801285252	Not Excavated						
Football Field	SLT-S31	SSHS-ISMP-SLT-S31	10/14/2021	-	856.39	-	851.60	4 - 6 ft	4.79 ft	1801285252	Not Excavated						
Football Field	ISMP-S005	SSHS-ISMP-STOR-S005	10/28/2021	-	855.83	-	850.79	4 - 6 ft	5.04 ft	1801292051	Not Excavated						
Football Field	ISMP-S006	SSHS-ISMP-STOR-S006	10/28/2021	-	855.80	-	850.67	4 - 6 ft	5.13 ft	1801292051	Not Excavated						
Football Field	ISMP-S612	SSHS-ISMP-DUPB	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated						
Football Field	ISMP-S612	SSHS-ISMP-S612	12/1/2021	-	855.49	-	850.84	4 - 6 ft	4.65 ft	1801305761	Not Excavated						
Football Field	ISMP-B609	SSHS-ISMP-B609	12/1/2021	-	855.49	-	850.01	4 - 6 ft	5.48 ft	1801305761	Not Excavated						
Football Field	ISMP-S614	SSHS-ISMP-S614	12/1/2021	-	855.51	-	851.14	4 - 6 ft	4.37 ft	1801305761	Not Excavated						
Football Field	ISMP-S615	SSHS-ISMP-S615	12/1/2021	-	855.52	-	850.69	4 - 6 ft	4.83 ft	1801305761	Not Excavated						
Football Field	ISMP-S617	SSHS-ISMP-S617	12/1/2021	-	855.45	-	850.58	4 - 6 ft	4.88 ft	1801305761	Not Excavated						
Football Field	ISMP-B610	SSHS-ISMP-B610	12/1/2021	-	855.45	-	850.42	4 - 6 ft	5.04 ft	1801305761	Not Excavated						
Football Field	ISMP-S625	SSHS-ISMP-S625	12/2/2021	-	855.45	-	850.17	4 - 6 ft	5.28 ft	1801306501	Not Excavated						
Football Field	ISMP-S629	SSHS-ISMP-S629	12/2/2021	-	855.65	-	850.75	4 - 6 ft	4.9 ft	1801306501	Not Excavated						
Football Field	ISMP-B618	SSHS-ISMP-DUPF	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated						
Football Field	ISMP-S639	SSHS-ISMP-S639	12/3/2021	-	855.62	-	850.47	4 - 6 ft	5.16 ft	1801307391	Not Excavated						
Football Field	ISMP-B617	SSHS-ISMP-B617	12/3/2021	-	855.65	-	850.56	4 - 6 ft	5.09 ft	1801307391	Not Excavated						
Football Field	ISMP-S640	SSHS-ISMP-S640	12/3/2021	-	855.65	-	851.19	4 - 6 ft	4.46 ft	1801307391	Not Excavated						
Football Field	ISMP-S641	SSHS-ISMP-S641	12/3/2021	-	855.65	-	850.48	4 - 6 ft	5.17 ft	1801307391	Not Excavated						
Football Field	ISMP-S643	SSHS-ISMP-S643	12/3/2021	-	855.62	-	850.60	4 - 6 ft	5.02 ft	1801307391	Not Excavated						
Football Field	ISMP-S645	SSHS-ISMP-S645	12/3/2021	-	855.83	-	850.80	4 - 6 ft	5.03 ft	1801307391	Not Excavated						
Football Field	ISMP-B618	SSHS-ISMP-B618	12/3/2021	-	855.84	-	850.56	4 - 6 ft	5.28 ft	1801307391	Not Excavated						
Football Field	ISMP-S647	SSHS-ISMP-S647	12/3/2021	-	855.85	-	850.88	4 - 6 ft	4.97 ft	1801307391	Not Excavated						
Football Field	SLT-BOT11	SSHS-ISMP-SLT-DUP6	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated						
Football Field	SLT-S37	SSHS-ISMP-SLT-S37	12/7/2021	-	856.20	-	851.94	4 - 6 ft	4.26 ft	1801308711	Not Excavated						
Football Field	SLT-BOT11	SSHS-ISMP-SLT-BOT11	12/7/2021	-	856.05	-	851.45	4 - 6 ft	4.6 ft	1801308711	Not Excavated						
Football Field	SLT-BOT12	SSHS-ISMP-SLT-BOT12	12/7/2021	-	855.96	-	851.26	4 - 6 ft	4.7 ft	1801308711	Not Excavated						
Football Field	SLT-BOT13	SSHS-ISMP-SLT-BOT13	12/7/2021	-	855.81	-	851.62	4 - 6 ft	4.19 ft	1801308711	Not Excavated						
Football Field	ISMP-S659	SSHS-ISMP-S659	12/14/2021	-	855.58	-	850.78	4 - 6 ft	4.8 ft	1801312361	Not Excavated						
Football Field	ISMP-B623	SSHS-ISMP-DUPH	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated						
Football Field	ISMP-S667	SSHS-ISMP-S667	12/16/2021	-	856.03	-	850.04	4 - 6 ft	5.99 ft	1801314041	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-S663	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated	< 120 U								
Football Field	ISMP-S664	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated	< 120 U								
Football Field	ISMP-B623	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated	< 120 U								
Football Field	ISMP-S665	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated	< 120 U								
Football Field	ISMP-S666	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated	< 120 U								
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 110 U								
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated	< 120 U								
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated	< 120 U								
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated	< 110 U								
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated	< 560 U								
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated	< 230 U								
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated	< 220 U								
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated	< 230 U								
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated	< 130 U								
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated	< 120 U								
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated	< 120 U								
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated	< 120 U								
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated	< 120 U								
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated	< 120 U								
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated	< 120 U								
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated	< 120 U								
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated	< 130 U								
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S44	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S45	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated	< 110 U								
Football Field	SLT-S46	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S47	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S51	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S49	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated	< 120 U								
Football Field	SLT-S53	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 120 U								
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated	< 110 U								
Football Field	SLT-S55	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated	< 120 U								
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated	< 120 U								
Football Field	ISMP-S671	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-S674	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-S668	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated	< 130 U								
Football Field	ISMP-S680	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-S701	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 810 U								
Football Field	ISMP-S695	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated	< 120 U								
Football Field	ISMP-S701	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated	< 120 U								
Football Field	ISMP-S704	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated	< 130 U								
Football Field	ISMP-S702	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated	< 110 U								
Football Field	SLT-S57	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated	< 130 U								
Football Field	SLT-S58	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-S59	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated	< 110 U								
Football Field	SLT-S65	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-S66	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated	< 110 U								
Football Field	SLT-S62	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-S69	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated	< 120 U								
Football Field	SLT-S70	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated	< 120 U								
Football Field	ISMP-B631A	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated	< 120 U								
Football Field	IRM5-S432	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated	< 120 U								
Football Field	SLT-S73	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated	< 120 U								
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated	< 120 U								
Football Field	SLT-S74	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated	< 120 U								
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-S663	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated									
Football Field	ISMP-S664	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated									
Football Field	ISMP-B623	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated									
Football Field	ISMP-S665	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated									
Football Field	ISMP-S666	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated									
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated									
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated									
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated									
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated									
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated									
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated									
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated									
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated									
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated									
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated									
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated									
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated									
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated									
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated									
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated									
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated									
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated									
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated									
Football Field	SLT-S44	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated									
Football Field	SLT-S45	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated									
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated									
Football Field	SLT-S46	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated									
Football Field	SLT-S47	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated									
Football Field	SLT-S51	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated									
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated									
Football Field	SLT-S49	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated									
Football Field	SLT-S53	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated									
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated									
Football Field	SLT-S55	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated									
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated									
Football Field	ISMP-S671	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated									
Football Field	ISMP-S674	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated									
Football Field	ISMP-S668	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated									
Football Field	ISMP-S680	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated									
Football Field	ISMP-S701	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated									
Football Field	ISMP-S695	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated									
Football Field	ISMP-S701	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated									
Football Field	ISMP-S704	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated									
Football Field	ISMP-S702	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated									
Football Field	SLT-S57	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated									
Football Field	SLT-S58	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated									
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated									
Football Field	SLT-S59	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated									
Football Field	SLT-S65	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated									
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated									
Football Field	SLT-S66	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated									
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated									
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated									
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated									
Football Field	SLT-S62	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated									
Football Field	SLT-S69	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated									
Football Field	SLT-S70	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated									
Football Field	ISMP-B631A	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated									
Football Field	IRM5-S432	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated									
Football Field	SLT-S73	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated									
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated									
Football Field	SLT-S74	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated									
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	ISMP-S663	SSHS-ISMP-S663	12/16/2021	-	855.84	-	850.79	4 - 6 ft	5.05 ft	1801314041	Not Excavated						
Football Field	ISMP-S664	SSHS-ISMP-S664	12/16/2021	-	855.84	-	851.03	4 - 6 ft	4.81 ft	1801314041	Not Excavated						
Football Field	ISMP-B623	SSHS-ISMP-B623	12/16/2021	-	855.84	-	850.08	4 - 6 ft	5.76 ft	1801314041	Not Excavated						
Football Field	ISMP-S665	SSHS-ISMP-S665	12/16/2021	-	855.84	-	850.66	4 - 6 ft	5.18 ft	1801314041	Not Excavated						
Football Field	ISMP-S666	SSHS-ISMP-S666	12/16/2021	-	856.07	-	850.45	4 - 6 ft	5.62 ft	1801314041	Not Excavated						
Football Field	ISMP-S653-BOT1	SSHS-ISMP-DUPJ	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated						
Football Field	ISMP-S636-S4	SSHS-ISMP-S636-S4	12/30/2021	-	855.85	-	850.32	4 - 6 ft	5.53 ft	1801318801	Not Excavated						
Football Field	ISMP-S653-BOT1	SSHS-ISMP-S653-BOT1	12/30/2021	-	855.84	-	850.09	4 - 6 ft	5.75 ft	1801318801	Not Excavated						
Football Field	ISMP-S655-S3	SSHS-ISMP-S655-S3	12/30/2021	-	855.49	-	850.91	4 - 6 ft	4.58 ft	1801318801	Not Excavated						
Football Field	ISMP-B611-S1	SSHS-ISMP-B611-S1	12/30/2021	-	855.56	-	850.54	4 - 6 ft	5.03 ft	1801318801	Not Excavated						
Football Field	ISMP-B611-S2	SSHS-ISMP-B611-S2	12/30/2021	-	855.56	-	850.20	4 - 6 ft	5.36 ft	1801318801	Not Excavated						
Football Field	ISMP-B611-BOT1	SSHS-ISMP-B611-BOT1	12/30/2021	-	855.56	-	850.19	4 - 6 ft	5.37 ft	1801318801	Not Excavated						
Football Field	ISMP-B611-S3	SSHS-ISMP-B611-S3	12/30/2021	-	855.68	-	850.21	4 - 6 ft	5.46 ft	1801318801	Not Excavated						
Football Field	ISMP-B611-S4	SSHS-ISMP-B611-S4	12/30/2021	-	855.69	-	850.43	4 - 6 ft	5.26 ft	1801318801	Not Excavated						
Football Field	ISMP-B611-BOT2	SSHS-ISMP-B611-BOT2	12/30/2021	-	855.69	-	849.95	4 - 6 ft	5.74 ft	1801318801	Not Excavated						
Football Field	SLT-S34-BOT1	SSHS-ISMP-SLT-S34-BOT1	1/3/2022	-	856.19	-	851.65	4 - 6 ft	4.54 ft	1801318901	Not Excavated						
Football Field	SLT-S34-BOT2	SSHS-ISMP-SLT-S34-BOT2	1/3/2022	-	856.19	-	851.75	4 - 6 ft	4.44 ft	1801318901	Not Excavated						
Football Field	ISMP-PIPE1-S13	SSHS-ISMP-PIPE1-S13	1/7/2022	-	855.58	-	850.49	4 - 6 ft	5.09 ft	1801321211	Not Excavated						
Football Field	ISMP-PIPE1-S11	SSHS-ISMP-PIPE1-S11	1/7/2022	-	855.66	-	850.39	4 - 6 ft	5.27 ft	1801321211	Not Excavated						
Football Field	ISMP-PIPE1-S16	SSHS-ISMP-PIPE1-S16	1/7/2022	-	856.05	-	850.62	4 - 6 ft	5.42 ft	1801321211	Not Excavated						
Football Field	ISMP-PIPE1-S15	SSHS-ISMP-PIPE1-S15	1/7/2022	-	856.04	-	851.32	4 - 6 ft	4.72 ft	1801321211	Not Excavated						
Football Field	ISMP-PIPE1-S17	SSHS-ISMP-PIPE1-S17	1/7/2022	-	855.91	-	850.11	4 - 6 ft	5.8 ft	1801321211	Not Excavated						
Football Field	SLT-S44	SSHS-ISMP-SLT-DUP8	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated						
Football Field	SLT-S44	SSHS-ISMP-SLT-S44	1/10/2022	-	856.48	-	852.38	4 - 6 ft	4.11 ft	1801321411	Not Excavated						
Football Field	SLT-S45	SSHS-ISMP-SLT-S45	1/10/2022	-	856.46	-	851.02	4 - 6 ft	5.44 ft	1801321411	Not Excavated						
Football Field	SLT-BOT14	SSHS-ISMP-SLT-BOT14	1/10/2022	-	856.44	-	850.66	4 - 6 ft	5.78 ft	1801321411	Not Excavated						
Football Field	SLT-S46	SSHS-ISMP-SLT-S46	1/10/2022	-	856.40	-	852.32	4 - 6 ft	4.08 ft	1801321411	Not Excavated						
Football Field	SLT-S47	SSHS-ISMP-SLT-S47	1/10/2022	-	856.40	-	850.97	4 - 6 ft	5.43 ft	1801321411	Not Excavated						
Football Field	SLT-S51	SSHS-ISMP-SLT-S51	1/10/2022	-	856.48	-	852.07	4 - 6 ft	4.41 ft	1801321411	Not Excavated						
Football Field	SLT-BOT15	SSHS-ISMP-SLT-BOT15	1/10/2022	-	856.52	-	851.12	4 - 6 ft	5.4 ft	1801321411	Not Excavated						
Football Field	SLT-S49	SSHS-ISMP-SLT-S49	1/10/2022	-	856.45	-	851.23	4 - 6 ft	5.22 ft	1801321411	Not Excavated						
Football Field	SLT-S53	SSHS-ISMP-SLT-S53	1/12/2022	-	856.56	-	852.15	4 - 6 ft	4.41 ft	1801322501	Not Excavated						
Football Field	SLT-BOT16	SSHS-ISMP-SLT-BOT16	1/12/2022	-	856.55	-	851.03	4 - 6 ft	5.51 ft	1801322501	Not Excavated						
Football Field	SLT-S55	SSHS-ISMP-SLT-S55	1/12/2022	-	856.60	-	852.19	4 - 6 ft	4.41 ft	1801322501	Not Excavated						
Football Field	SLT-BOT17	SSHS-ISMP-SLT-BOT17	1/12/2022	-	856.55	-	851.44	4 - 6 ft	5.12 ft	1801322501	Not Excavated						
Football Field	ISMP-S671	SSHS-ISMP-S671	2/28/2022	-	855.57	-	849.89	4 - 6 ft	5.67 ft	1801343691	Not Excavated						
Football Field	ISMP-S674	SSHS-ISMP-S674	2/28/2022	-	855.66	-	849.71	4 - 6 ft	5.96 ft	1801343691	Not Excavated						
Football Field	ISMP-S668	SSHS-ISMP-S668	2/28/2022	-	855.65	-	851.35	4 - 6 ft	4.3 ft	1801343691	Not Excavated						
Football Field	ISMP-S680	SSHS-ISMP-S680	2/28/2022	-	855.93	-	850.01	4 - 6 ft	5.92 ft	1801343691	Not Excavated						
Football Field	ISMP-S701	SSHS-ISMP-DUPN	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated						
Football Field	ISMP-S695	SSHS-ISMP-S695	3/1/2022	-	855.51	-	849.53	4 - 6 ft	5.98 ft	1801344451	Not Excavated						
Football Field	ISMP-S701	SSHS-ISMP-S701	3/1/2022	-	855.94	-	850.73	4 - 6 ft	5.21 ft	1801344451	Not Excavated						
Football Field	ISMP-S704	SSHS-ISMP-S704	3/1/2022	-	856.03	-	850.90	4 - 6 ft	5.13 ft	1801344451	Not Excavated						
Football Field	ISMP-S702	SSHS-ISMP-S702	3/1/2022	-	855.87	-	850.85	4 - 6 ft	5.02 ft	1801344451	Not Excavated						
Football Field	SLT-S57	SSHS-ISMP-SLT-S57	3/1/2022	-	855.88	-	851.67	4 - 6 ft	4.21 ft	1801344461	Not Excavated						
Football Field	SLT-S58	SSHS-ISMP-SLT-S58	3/1/2022	-	855.88	-	850.89	4 - 6 ft	4.99 ft	1801344461	Not Excavated						
Football Field	SLT-BOT19	SSHS-ISMP-SLT-BOT19	3/1/2022	-	855.88	-	850.35	4 - 6 ft	5.53 ft	1801344461	Not Excavated						
Football Field	SLT-S59	SSHS-ISMP-SLT-S59	3/1/2022	-	855.88	-	850.33	4 - 6 ft	5.55 ft	1801344461	Not Excavated						
Football Field	SLT-S65	SSHS-ISMP-SLT-S65	3/1/2022	-	855.64	-	849.98	4 - 6 ft	5.67 ft	1801344461	Not Excavated						
Football Field	SLT-BOT21	SSHS-ISMP-SLT-BOT21	3/1/2022	-	855.62	-	849.94	4 - 6 ft	5.68 ft	1801344461	Not Excavated						
Football Field	SLT-S66	SSHS-ISMP-SLT-S66	3/1/2022	-	855.58	-	849.87	4 - 6 ft	5.72 ft	1801344461	Not Excavated						
Football Field	SLT-BOT22	SSHS-ISMP-SLT-BOT22	3/1/2022	-	855.54	-	850.50	4 - 6 ft	5.04 ft	1801344461	Not Excavated						
Football Field	SLT-S64A	SSHS-ISMP-SLT-S64A	3/1/2022	-	855.90	-	851.15	4 - 6 ft	4.75 ft	1801344461	Not Excavated						
Football Field	SLT-BOT20	SSHS-ISMP-SLT-BOT20	3/1/2022	-	855.90	-	851.03	4 - 6 ft	4.87 ft	1801344461	Not Excavated						
Football Field	SLT-S62	SSHS-ISMP-SLT-S62	3/1/2022	-	855.90	-	850.86	4 - 6 ft	5.04 ft	1801344461	Not Excavated						
Football Field	SLT-S69	SSHS-ISMP-SLT-S69	3/1/2022	-	855.52	-	850.80	4 - 6 ft	4.72 ft	1801344461	Not Excavated						
Football Field	SLT-S70	SSHS-ISMP-SLT-S70	3/1/2022	-	855.57	-	850.82	4 - 6 ft	4.75 ft	1801344461	Not Excavated						
Football Field	ISMP-B631A	SSHS-ISMP-B631A	3/2/2022	-	855.94	-	850.55	4 - 6 ft	5.39 ft	1801345561	Not Excavated						
Football Field	IRM5-S432	SSHS-IRM5-S432	3/2/2022	-	855.36	-	851.08	4 - 6 ft	4.28 ft	1801345551	Not Excavated						
Football Field	SLT-S73	SSHS-ISMP-SLT-S73	3/2/2022	-	855.11	-	850.64	4 - 6 ft	4.47 ft	1801345561	Not Excavated						
Football Field	SLT-BOT23	SSHS-ISMP-SLT-BOT23	3/2/2022	-	855.02	-	849.71	4 - 6 ft	5.32 ft	1801345561	Not Excavated						
Football Field	SLT-S74	SSHS-ISMP-SLT-S74	3/2/2022	-	855.07	-	850.39	4 - 6 ft	4.69 ft	1801345561	Not Excavated						
Football Field	ISMP-PIPE3-S2	SSHS-ISMP-PIPE3-S2	3/5/2022	-	855.74	-	850.15	4 - 6 ft	5.6 ft	1801347831	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated	< 120 U								
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated	< 120 U								
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated	< 120 U								
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated	< 110 U								
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated	< 120 U								
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated	< 120 U								
Football Field	ISMP-S2006	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated	< 110 U								
Football Field	ISMP-S2014	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated	< 120 U								
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated	< 110 U								
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated	< 120 U								
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated	< 120 U								
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated	< 120 U								
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated	< 120 U								
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated			< 120 U						
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated			< 110 U						
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated	< 120 U								
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated	< 120 U								
Football Field	IRM5-B195	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated	< 120 U								
Football Field	IRM5-B196	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated	< 120 U								
Football Field	IRM5-B195A	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated	< 120 U								
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-120245-1	Not Excavated			< 110 U	< 0.39 UJ	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated	< 110 U								
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated	< 110 UT								
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated	< 120 U								
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated	< 130 U								
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-S525	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated	< 120 U								
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated	< 110 U								
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated	< 220 U								
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated	< 110 U								
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated	< 130 U								
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated	< 110 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated			< 180 U						
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated			< 110 U	< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.03 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated	< 110 U								
Football Field	IRM5-B400	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated	< 110 U								
Football Field	IRM5-S417	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated	< 120 U								
Football Field	IRM5-S418	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated	< 120 U								
Football Field	IRM5-S423	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated	< 130 U								
Football Field	ISMP-S673	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-B675	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated	< 120 U								
Football Field	ISMP-S669	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated	< 120 U								
Football Field	ISMP-S690	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated	< 110 U								
Football Field	ISMP-S697	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated	< 120 U								
Football Field	IRM5-S424	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated	< 130 UT								
Football Field	IRM5-B411	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated	< 110 U								
Football Field	IRM5-S425	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated									
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated									
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated									
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated									
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated									
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated									
Football Field	ISMP-S2006	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated									
Football Field	ISMP-S2014	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated									
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated									
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated									
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated									
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated									
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated									
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated									
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated									
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated									
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated									
Football Field	IRM5-B195	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated									
Football Field	IRM5-B196	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated									
Football Field	IRM5-B195A	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated									
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-120245-1	Not Excavated	< 0.037 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.092 U	< 0.082 U
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated									
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated									
Football Field	ISMP-S525	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated									
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated									
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated									
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated									
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated									
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated									
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 34 U	< 0.043 U	< 0.053 U	< 0.041 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated									
Football Field	IRM5-B400	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated									
Football Field	IRM5-S417	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated									
Football Field	IRM5-S418	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated									
Football Field	IRM5-S423	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated									
Football Field	ISMP-S673	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated									
Football Field	ISMP-B675	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated									
Football Field	ISMP-S669	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated									
Football Field	ISMP-S690	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated									
Football Field	ISMP-S697	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated									
Football Field	IRM5-S424	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated									
Football Field	IRM5-B411	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated									
Football Field	IRM5-S425	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	ISMP-PIPE3-S4	SSHS-ISMP-PIPE3-S4	3/5/2022	-	855.72	-	850.08	4 - 6 ft	5.64 ft	1801347831	Not Excavated						
Football Field	ISMP-PIPE3-S6	SSHS-ISMP-PIPE3-S6	3/5/2022	-	855.79	-	850.57	4 - 6 ft	5.22 ft	1801347831	Not Excavated						
Football Field	ISMP-PIPE3-S8	SSHS-ISMP-PIPE3-S8	3/5/2022	-	855.74	-	850.30	4 - 6 ft	5.44 ft	1801347831	Not Excavated						
Football Field	ISMP-PIPE3-BOT2	SSHS-ISMP-PIPE3-BOT2	3/5/2022	-	855.77	-	850.03	4 - 6 ft	5.74 ft	1801347831	Not Excavated						
Football Field	IRM5-S430-S2	SSHS-IRM5-S430-S2	3/8/2022	-	855.41	-	850.89	4 - 6 ft	4.52 ft	1801348401	Not Excavated						
Football Field	IRM5-S430-S1	SSHS-IRM5-S430-S1	3/8/2022	-	855.57	-	851.45	4 - 6 ft	4.12 ft	1801348401	Not Excavated						
Football Field	ISMP-S2006	SSHS-ISMP-S2006	3/8/2022	-	855.40	-	849.66	4 - 6 ft	5.74 ft	1801348411	Not Excavated						
Football Field	ISMP-S2014	SSHS-ISMP-S2014	3/9/2022	-	855.99	-	850.86	4 - 6 ft	5.13 ft	1801349171	Not Excavated						
Football Field	MS-SLT-S80	SSHS-ISMP-MS-SLT-S80	3/22/2022	-	856.24	-	851.83	4 - 6 ft	4.41 ft	1801355361	Not Excavated						
Football Field	IRM5-P3A-BOT	SSHS-IRM5-P3A-BOT	3/22/2022	-	855.78	-	850.08	4 - 6 ft	5.69 ft	1801355341	Not Excavated						
Football Field	IRM5-P3A-S1	SSHS-IRM5-P3A-S1	3/22/2022	-	855.79	-	850.69	4 - 6 ft	5.11 ft	1801355341	Not Excavated						
Football Field	IRM5-P3A-S2	SSHS-IRM5-P3A-S2	3/22/2022	-	855.79	-	850.87	4 - 6 ft	4.92 ft	1801355341	Not Excavated						
Football Field	IRM5-P3A-S3	SSHS-IRM5-P3A-S3	3/22/2022	-	855.75	-	850.91	4 - 6 ft	4.84 ft	1801355341	Not Excavated						
Football Field	SSHS-B2763	SSHS-B2763-SUB-6-8	4/26/2019	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2686	SSHS-B2686-SUB-6-8	5/21/2019	855.51	855.51	0.00	-	6 - 8 ft	6-8 ft	180-90380-1	Not Excavated						
Football Field	SSHS-B2791	SSHS-B2791-SUB-6-8	5/21/2019	854.92	855.51	0.59	-	6 - 8 ft	6.59-8.59 ft	180903801	Not Excavated						
Football Field	IRM5-TANK-B1 (D)	SSHS-IRM5-TANK-B1 (D)	2/24/2021	-	855.72	-	848.55	6 - 8 ft	7.17 ft	1801176021	Not Excavated						
Football Field	IRM5-B195	SSHS-IRM5-B195	4/15/2021	-	855.67	-	848.84	6 - 8 ft	6.83 ft	1801200643	Not Excavated						
Football Field	IRM5-B196	SSHS-IRM5-B196	4/15/2021	-	855.64	-	849.26	6 - 8 ft	6.38 ft	1801200643	Not Excavated						
Football Field	IRM5-B195A	SSHS-IRM5-B195A	4/15/2021	-	855.60	-	848.97	6 - 8 ft	6.63 ft	1801200643	Not Excavated						
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-120245-1	Not Excavated	< 0.058 U	< 34 U	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 UJ
Football Field	IRM5-VAULT 2 N2	SSHS-IRM5-VAULT 2 N2	5/27/2021	-	855.38	-	847.61	6 - 8 ft	7.77 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W2	SSHS-IRM5-VAULT 2 W2	5/27/2021	-	855.53	-	847.54	6 - 8 ft	7.99 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 S2	SSHS-IRM5-VAULT 2 S2	5/27/2021	-	855.34	-	848.21	6 - 8 ft	7.13 ft	1801223391	Not Excavated						
Football Field	ISMP-B527-S4	SSHS-ISMP-B527 S4	6/2/2021	-	855.66	-	849.47	6 - 8 ft	6.18 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S5	SSHS-ISMP-B527 S5	6/2/2021	-	855.68	-	849.06	6 - 8 ft	6.62 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S9	SSHS-ISMP-B527 S9	6/2/2021	-	855.64	-	848.39	6 - 8 ft	7.25 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S6	SSHS-ISMP-B527 S6	6/2/2021	-	855.68	-	848.67	6 - 8 ft	7.01 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S7	SSHS-ISMP-B527 S7	6/2/2021	-	855.68	-	848.25	6 - 8 ft	7.43 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S16	SSHS-ISMP-B527 S16	6/2/2021	-	855.40	-	848.31	6 - 8 ft	7.09 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S31	SSHS-ISMP-B527 S31	6/3/2021	-	855.60	-	847.87	6 - 8 ft	7.73 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S46	SSHS-ISMP-B527 S46	6/5/2021	-	855.79	-	849.59	6 - 8 ft	6.2 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S54	SSHS-ISMP-B527 S54	6/5/2021	-	855.97	-	848.19	6 - 8 ft	7.78 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S53	SSHS-ISMP-B527 S53	6/5/2021	-	855.96	-	849.35	6 - 8 ft	6.61 ft	1801228121	Not Excavated						
Football Field	ISMP-S525	SSHS-ISMP-S525	6/9/2021	-	855.52	-	848.31	6 - 8 ft	7.21 ft	1801229791	Not Excavated						
Football Field	ISMP-B527-S75	SSHS-ISMP-B527-S75	6/11/2021	-	855.65	-	849.54	6 - 8 ft	6.11 ft	1801231161	Not Excavated						
Football Field	ISMP-B527-S95	SSHS-ISMP-B527 S95	6/25/2021	-	855.67	-	848.04	6 - 8 ft	7.63 ft	1801237471	Not Excavated						
Football Field	ISMP-B527-S97	SSHS-ISMP-B527 S97	6/25/2021	-	855.53	-	848.47	6 - 8 ft	7.06 ft	1801237471	Not Excavated						
Football Field	ISMP-B527-S98	SSHS-ISMP-B527 S98	6/25/2021	-	855.65	-	848.03	6 - 8 ft	7.62 ft	1801237471	Not Excavated						
Football Field	ISMP-CB-7 BOT 1	SSHS-ISMP-CB-7 BOT 1	8/28/2021	-	855.94	-	848.24	6 - 8 ft	7.71 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S1	SSHS-ISMP-CB-7 S1	8/28/2021	-	855.89	-	848.55	6 - 8 ft	7.34 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S5	SSHS-ISMP-CB-7 S5	8/28/2021	-	855.92	-	848.60	6 - 8 ft	7.32 ft	1801263841	Not Excavated						
Football Field	ISMP-CB-7 S13	SSHS-ISMP-DUP 13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S22	SSHS-ISMP-DUP 14	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S17	SSHS-ISMP-CB-7 S17	8/29/2021	-	856.11	-	848.64	6 - 8 ft	7.47 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S22	SSHS-ISMP-CB-7 S22	8/29/2021	-	856.26	-	848.77	6 - 8 ft	7.49 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S27	SSHS-ISMP-CB-7 S27	8/29/2021	-	856.20	-	849.20	6 - 8 ft	7 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S13	SSHS-ISMP-CB-7 S13	8/29/2021	-	856.12	-	848.50	6 - 8 ft	7.62 ft	1801264041	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-6-8	9/23/2021	856.42	856.42	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4165	SSHS-B4165-SUB-6-8	9/23/2021	856.00	856.00	0.00	-	6 - 8 ft	6-8 ft	180-127595-2	Not Excavated	< 0.037 U	< 34 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Football Field	ISMP-B002	SSHS-ISMP-STOR-B002	10/28/2021	-	855.79	-	849.52	6 - 8 ft	6.27 ft	1801292051	Not Excavated						
Football Field	IRM5-B400	SSHS-IRM5-B400	12/29/2021	-	855.44	-	849.08	6 - 8 ft	6.36 ft	1801318161	Not Excavated						
Football Field	IRM5-S417	SSHS-IRM5-S417	1/6/2022	-	855.37	-	847.78	6 - 8 ft	7.59 ft	1801320671	Not Excavated						
Football Field	IRM5-S418	SSHS-IRM5-S418	1/6/2022	-	855.55	-	847.57	6 - 8 ft	7.98 ft	1801320671	Not Excavated						
Football Field	IRM5-S423	SSHS-IRM5-S423	1/6/2022	-	855.48	-	848.35	6 - 8 ft	7.13 ft	1801320671	Not Excavated						
Football Field	ISMP-S673	SSHS-ISMP-S673	2/28/2022	-	855.58	-	849.55	6 - 8 ft	6.03 ft	1801343691	Not Excavated						
Football Field	ISMP-B675	SSHS-ISMP-BOT675	2/28/2022	-	855.61	-	849.47	6 - 8 ft	6.15 ft	1801343692	Not Excavated						
Football Field	ISMP-S669	SSHS-ISMP-S669	2/28/2022	-	855.65	-	849.51	6 - 8 ft	6.14 ft	1801343691	Not Excavated						
Football Field	ISMP-S690	SSHS-ISMP-S690	2/28/2022	-	855.61	-	849.35	6 - 8 ft	6.26 ft	1801343691	Not Excavated						
Football Field	ISMP-S697	SSHS-ISMP-S697	3/1/2022	-	855.77	-	848.58	6 - 8 ft	7.19 ft	1801344451	Not Excavated						
Football Field	IRM5-S424	SSHS-IRM5-S424	3/1/2022	-	855.83	-	848.44	6 - 8 ft	7.39 ft	1801344431	Not Excavated						
Football Field	IRM5-B411	SSHS-IRM5-B411	3/1/2022	-	855.80	-	848.09	6 - 8 ft	7.71 ft	1801344431	Not Excavated						
Football Field	IRM5-S425	SSHS-IRM5-S425	3/2/2022	-	855.67	-	847.99	6 - 8 ft	7.68 ft	1801345551	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	IRM5-S426	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated	< 130 U								
Football Field	IRM5-S435	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated	< 120 U								
Football Field	IRM5-S429	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated	< 120 U								
Football Field	IRM5-S431	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated	< 120 U								
Football Field	IRM5-S433	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated	< 120 U								
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated	< 110 U								
Football Field	ISMP-S2000	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated	< 110 U								
Football Field	ISMP-S2001	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated	< 120 U								
Football Field	ISMP-S2002	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated	< 120 U								
Football Field	ISMP-S2004	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated	< 110 U								
Football Field	ISMP-S2007	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated	< 110 UT								
Football Field	ISMP-S2008	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated	< 110 U								
Football Field	ISMP-S2009	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated	< 110 U								
Football Field	ISMP-S2010	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated	< 110 U								
Football Field	ISMP-S2012	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated	< 110 U								
Football Field	ISMP-B1008	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated	< 120 U								
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated	< 130 U								
Football Field	ISMP-S2016	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated	< 120 U								
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated	< 130 U								
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated	< 120 U								
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated	< 120 U								
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated			< 350 U						
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated			< 110 U						
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated			< 120 U						
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated	< 130 U								
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated	< 120 U								
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated	< 110 U								
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated	< 120 U								
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated	< 110 U								
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated	< 120 U								
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated	< 160 U								
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated	< 180 U								
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated	< 120 U								
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated	< 110 U								
Football Field	ISMP-B545	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated	< 130 U								
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 350 U								
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated	< 340 U								
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated	< 110 U								
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated	< 120 U								
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated	< 110 U								
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated			< 120 U						
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated			< 110 U						
Football Field	IRM5-B410	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated	< 120 U								
Football Field	IRM5-B412	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated	< 130 U								
Football Field	ISMP-S706	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated	< 130 U								
Football Field	IRM5-B404A	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated	< 130 U								
Football Field	IRM5-B403A	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated	< 130 U								
Football Field	ISMP-B1000	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated	< 120 U								
Football Field	ISMP-B1005	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 120 U								
Football Field	ISMP-B1006	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated	< 120 U								
Football Field	ISMP-B1007	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated	< 120 U								
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated	< 130 U								
Football Field	ISMP-B1009	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated	< 110 U								
Football Field	ISMP-B1010	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	IRM5-S426	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated									
Football Field	IRM5-S435	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated									
Football Field	IRM5-S429	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated									
Football Field	IRM5-S431	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated									
Football Field	IRM5-S433	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated									
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated									
Football Field	ISMP-S2000	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated									
Football Field	ISMP-S2001	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated									
Football Field	ISMP-S2002	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated									
Football Field	ISMP-S2004	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated									
Football Field	ISMP-S2007	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated									
Football Field	ISMP-S2008	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated									
Football Field	ISMP-S2009	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated									
Football Field	ISMP-S2010	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated									
Football Field	ISMP-S2012	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated									
Football Field	ISMP-B1008	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated									
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated									
Football Field	ISMP-S2016	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated									
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated									
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated									
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated									
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated									
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated									
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated									
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated									
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated									
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated									
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated									
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated									
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated									
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated									
Football Field	ISMP-B545	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated									
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated									
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated									
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated									
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated									
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated									
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated									
Football Field	IRM5-B410	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated									
Football Field	IRM5-B412	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated									
Football Field	ISMP-S706	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated									
Football Field	IRM5-B404A	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated									
Football Field	IRM5-B403A	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated									
Football Field	ISMP-B1000	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated									
Football Field	ISMP-B1005	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated									
Football Field	ISMP-B1006	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated									
Football Field	ISMP-B1007	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated									
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated									
Football Field	ISMP-B1009	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated									
Football Field	ISMP-B1010	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	IRM5-S426	SSHS-IRM5-S426	3/2/2022	-	855.58	-	847.60	6 - 8 ft	7.98 ft	1801345551	Not Excavated						
Football Field	IRM5-S435	SSHS-IRM5-S435	3/2/2022	-	855.41	-	848.75	6 - 8 ft	6.66 ft	1801345551	Not Excavated						
Football Field	IRM5-S429	SSHS-IRM5-S429	3/2/2022	-	855.56	-	849.42	6 - 8 ft	6.14 ft	1801345551	Not Excavated						
Football Field	IRM5-S431	SSHS-IRM5-S431	3/2/2022	-	855.35	-	848.71	6 - 8 ft	6.64 ft	1801345551	Not Excavated						
Football Field	IRM5-S433	SSHS-IRM5-S433	3/2/2022	-	855.36	-	849.17	6 - 8 ft	6.18 ft	1801345551	Not Excavated						
Football Field	ISMP-PIPE3-BOT1	SSHS-ISMP-PIPE3-BOT1	3/5/2022	-	855.73	-	849.69	6 - 8 ft	6.04 ft	1801347831	Not Excavated						
Football Field	ISMP-S2000	SSHS-ISMP-S2000	3/8/2022	-	855.48	-	847.78	6 - 8 ft	7.7 ft	1801348411	Not Excavated						
Football Field	ISMP-S2001	SSHS-ISMP-S2001	3/8/2022	-	855.68	-	848.34	6 - 8 ft	7.34 ft	1801348411	Not Excavated						
Football Field	ISMP-S2002	SSHS-ISMP-S2002	3/8/2022	-	855.62	-	847.64	6 - 8 ft	7.98 ft	1801348411	Not Excavated						
Football Field	ISMP-S2004	SSHS-ISMP-S2004	3/8/2022	-	855.59	-	849.47	6 - 8 ft	6.12 ft	1801348411	Not Excavated						
Football Field	ISMP-S2007	SSHS-ISMP-S2007	3/9/2022	-	855.84	-	848.76	6 - 8 ft	7.08 ft	1801349171	Not Excavated						
Football Field	ISMP-S2008	SSHS-ISMP-S2008	3/9/2022	-	855.85	-	848.27	6 - 8 ft	7.58 ft	1801349171	Not Excavated						
Football Field	ISMP-S2009	SSHS-ISMP-S2009	3/9/2022	-	855.60	-	847.83	6 - 8 ft	7.77 ft	1801349171	Not Excavated						
Football Field	ISMP-S2010	SSHS-ISMP-S2010	3/9/2022	-	855.64	-	847.75	6 - 8 ft	7.89 ft	1801349171	Not Excavated						
Football Field	ISMP-S2012	SSHS-ISMP-S2012	3/9/2022	-	855.51	-	848.35	6 - 8 ft	7.17 ft	1801349171	Not Excavated						
Football Field	ISMP-B1008	SSHS-ISMP-B1008	3/9/2022	-	855.98	-	849.89	6 - 8 ft	6.09 ft	1801349171	Not Excavated						
Football Field	IRM5-B416-S3	SSHS-IRM5-B416-S3	3/11/2022	-	855.45	-	847.79	6 - 8 ft	7.66 ft	1801350881	Not Excavated						
Football Field	ISMP-S2016	SSHS-ISMP-S2016	3/14/2022	-	855.83	-	848.46	6 - 8 ft	7.37 ft	1801351291	Not Excavated						
Football Field	IRM5-B416A-S1	SSHS-IRM5-B416A-S1	3/16/2022	-	855.36	-	847.49	6 - 8 ft	7.87 ft	1801352861	Not Excavated						
Football Field	MS-SLT-S81	SSHS-ISMP-MS-SLT-S81	3/22/2022	-	856.24	-	849.77	6 - 8 ft	6.47 ft	1801355361	Not Excavated						
Football Field	MS-SLT-B15	SSHS-ISMP-MS-SLT-BOT15	3/22/2022	-	856.27	-	848.56	6 - 8 ft	7.71 ft	1801355361	Not Excavated						
Football Field	SSHS-B2226	SSHS-B2226-SUB-8-10	7/26/2018	856.56	856.56	0.00	-	8 - 10 ft	8-10 ft	180-80227-1	Not Excavated						
Football Field	SSHS-B2762	SSHS-B2762-SUB-8-10	4/26/2019	856.14	856.25	0.11	-	8 - 10 ft	8.11-10.11 ft	180-89521-1	Not Excavated						
Football Field	SSHS-B2763	SSHS-B2763-SUB-8-10	4/26/2019	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-89521-1	Not Excavated						
Football Field	IRM5-TANK-B1 BOT	SSHS-IRM5-TANK-B1 BOT	2/24/2021	-	855.78	-	847.36	8 - 10 ft	8.42 ft	1801176021	Not Excavated						
Football Field	IRM5-VAULT 2 N3	SSHS-IRM5-VAULT 2 N3	5/27/2021	-	855.39	-	846.35	8 - 10 ft	9.04 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 W3	SSHS-IRM5-VAULT 2 W3	5/27/2021	-	855.53	-	845.92	8 - 10 ft	9.61 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 S3	SSHS-IRM5-VAULT 2 S3	5/27/2021	-	855.36	-	846.48	8 - 10 ft	8.88 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 E3	SSHS-IRM5-VAULT 2 E3	5/27/2021	-	855.38	-	846.64	8 - 10 ft	8.74 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 E4	SSHS-IRM5-VAULT 2 E4	5/27/2021	-	855.39	-	845.71	8 - 10 ft	9.68 ft	1801223391	Not Excavated						
Football Field	IRM5-VAULT 2 N4	SSHS-IRM5-VAULT 2 N4	5/27/2021	-	855.41	-	845.85	8 - 10 ft	9.56 ft	1801223391	Not Excavated						
Football Field	ISMP-B527-S17	SSHS-ISMP-B527 S17	6/2/2021	-	855.41	-	845.59	8 - 10 ft	9.82 ft	1801225501	Not Excavated						
Football Field	ISMP-B527-S24	SSHS-ISMP-B527 S24	6/3/2021	-	855.81	-	847.78	8 - 10 ft	8.03 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S32	SSHS-ISMP-B527 S32	6/3/2021	-	855.61	-	846.25	8 - 10 ft	9.36 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S36	SSHS-ISMP-B527 S36	6/3/2021	-	855.38	-	846.54	8 - 10 ft	8.84 ft	1801226361	Not Excavated						
Football Field	ISMP-B527-S64	SSHS-ISMP-B527 S64	6/5/2021	-	855.92	-	846.22	8 - 10 ft	9.7 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S47	SSHS-ISMP-B527 S47	6/5/2021	-	855.80	-	847.22	8 - 10 ft	8.58 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-S67	SSHS-ISMP-B527 S67	6/5/2021	-	855.92	-	846.38	8 - 10 ft	9.54 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-BOT19	SSHS-ISMP-B527 BOT 19	6/5/2021	-	855.99	-	847.03	8 - 10 ft	8.95 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-BOT20	SSHS-ISMP-B527 BOT 20	6/5/2021	-	855.99	-	847.63	8 - 10 ft	8.37 ft	1801228121	Not Excavated						
Football Field	ISMP-B527-BOT18	SSHS-ISMP-B527 BOT 18	6/5/2021	-	855.92	-	846.43	8 - 10 ft	9.49 ft	1801228121	Not Excavated						
Football Field	ISMP-B545	SSHS-ISMP-B545	6/9/2021	-	855.49	-	847.48	8 - 10 ft	8.01 ft	1801229791	Not Excavated						
Football Field	ISMP-B527-S89	SSHS-ISMP-DUP 10	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated						
Football Field	ISMP-B527-S89	SSHS-ISMP-B527 S89	6/24/2021	-	855.62	-	845.79	8 - 10 ft	9.83 ft	1801236601	Not Excavated						
Football Field	ISMP-CB-7 BOT 2	SSHS-ISMP-CB-7 BOT 2	8/29/2021	-	856.09	-	847.83	8 - 10 ft	8.26 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 BOT 3	SSHS-ISMP-CB-7 BOT 3	8/29/2021	-	856.27	-	847.50	8 - 10 ft	8.77 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S21	SSHS-ISMP-CB-7 S21	8/29/2021	-	856.26	-	846.77	8 - 10 ft	9.49 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S26	SSHS-ISMP-CB-7 S26	8/29/2021	-	856.20	-	847.20	8 - 10 ft	9 ft	1801264041	Not Excavated						
Football Field	ISMP-CB-7 S30	SSHS-ISMP-CB-7 S30	8/29/2021	-	856.28	-	847.19	8 - 10 ft	9.09 ft	1801264041	Not Excavated						
Football Field	SSHS-B4164	SSHS-B4164-SUB-8-10	9/23/2021	856.42	856.42	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated						
Football Field	SSHS-B4165	SSHS-B4165-SUB-8-10	9/23/2021	856.00	856.00	0.00	-	8 - 10 ft	8-10 ft	180-127595-2	Not Excavated						
Football Field	IRM5-B410	SSHS-IRM5-B410	1/6/2022	-	855.62	-	846.98	8 - 10 ft	8.64 ft	1801320671	Not Excavated						
Football Field	IRM5-B412	SSHS-IRM5-B412	3/2/2022	-	855.67	-	847.49	8 - 10 ft	8.18 ft	1801345551	Not Excavated						
Football Field	ISMP-S706	SSHS-ISMP-S706	3/2/2022	-	855.55	-	847.47	8 - 10 ft	8.08 ft	1801345561	Not Excavated						
Football Field	IRM5-B404A	SSHS-IRM5-B404A	3/2/2022	-	855.58	-	847.58	8 - 10 ft	8.01 ft	1801345551	Not Excavated						
Football Field	IRM5-B403A	SSHS-IRM5-B403A	3/2/2022	-	855.62	-	847.23	8 - 10 ft	8.39 ft	1801345551	Not Excavated						
Football Field	ISMP-B1000	SSHS-ISMP-B1000	3/8/2022	-	855.62	-	847.00	8 - 10 ft	8.62 ft	1801348411	Not Excavated						
Football Field	ISMP-B1005	SSHS-ISMP-B1005	3/9/2022	-	855.87	-	847.74	8 - 10 ft	8.13 ft	1801349171	Not Excavated						
Football Field	ISMP-B1006	SSHS-ISMP-B1006	3/9/2022	-	855.62	-	847.09	8 - 10 ft	8.53 ft	1801349171	Not Excavated						
Football Field	ISMP-B1007	SSHS-ISMP-B1007	3/9/2022	-	855.50	-	847.37	8 - 10 ft	8.13 ft	1801349171	Not Excavated						
Football Field	IRM5-B416-BOT1	SSHS-IRM5-B416-BOT1	3/11/2022	-	855.57	-	847.19	8 - 10 ft	8.38 ft	1801350881	Not Excavated						
Football Field	ISMP-B1009	SSHS-ISMP-B1009	3/14/2022	-	855.74	-	845.80	8 - 10 ft	9.94 ft	1801351291	Not Excavated						
Football Field	ISMP-B1010	SSHS-ISMP-B1010	3/14/2022	-	855.77	-	846.12	8 - 10 ft	9.65 ft	1801351291	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-S2020	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated	< 120 U								
Football Field	ISMP-S2019	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated	< 120 U								
Football Field	ISMP-S2018	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated	< 110 U								
Football Field	ISMP-S2017	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated	< 120 U								
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated			< 42						
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated			< 44 U						
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated	< 110 U								
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated	< 120 U								
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated			< 40						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 630 U			< 0.43 U	< 0.029 U	0.46 B	< 0.045 U	< 0.025 U	< 0.077 U
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated		< 30 U							
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated		< 30 U							
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated		< 100 U							
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656882	Not Excavated				< 0.044 U	< 0.035 U	0.047 J	< 0.048 U	< 0.044 U	< 0.028 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated		< 38 U							
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479552	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated			< 41						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 370 U								
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated	< 130 U								
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated	< 360 U								
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated	< 130 U								
Northern Athletic Field	S598	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated	< 120 U								
Northern Athletic Field	S597	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S249	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S250	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S251	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S245	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S234	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated	< 120 U								
Northern Athletic Field	S233	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated	< 110 U								
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 110 U								
Northern Athletic Field	S230	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated	< 120 U								
Northern Athletic Field	S232	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated	< 110 U								
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated	< 110 U								
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335312	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated	< 110 U								
Northern Athletic Field	S571	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated	< 110 U								
Northern Athletic Field	S573	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated	< 110 U								
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351302	Not Excavated				< 0.046 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S582	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S287	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354702	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S575	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S576	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated	< 110 U								
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated	< 110 U								
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated		< 30 U							
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated		< 380 U							
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated		< 30 U							

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Football Field	ISMP-S2020	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated									
Football Field	ISMP-S2019	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated									
Football Field	ISMP-S2018	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated									
Football Field	ISMP-S2017	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated									
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated									
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated									
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated									
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated									
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.040 U	0.050 J	< 0.036 U	< 0.048 U	0.059 J	< 0.095 U	1.2 BT	0.18 J	0.41
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated									
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated									
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656882	Not Excavated	< 0.045 U	< 0.035 U	< 0.027 U	0.098 J	0.023 J	< 0.031 U	< 0.040 U	< 0.049 U	0.098 J
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated									
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated									
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479552	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated									
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated									
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.081 U	< 0.20 U	< 0.085 U	< 0.076 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.039 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated									
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated									
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated									
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated									
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated									
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated									
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated									
Northern Athletic Field	S598	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated									
Northern Athletic Field	S597	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated									
Northern Athletic Field	S249	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated									
Northern Athletic Field	S250	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated									
Northern Athletic Field	S251	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated									
Northern Athletic Field	S245	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated									
Northern Athletic Field	S234	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated									
Northern Athletic Field	S233	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated									
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated									
Northern Athletic Field	S230	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated									
Northern Athletic Field	S232	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated									
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated									
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335312	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.042 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated									
Northern Athletic Field	S571	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated									
Northern Athletic Field	S573	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated									
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated									
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351302	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated									
Northern Athletic Field	S582	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated									
Northern Athletic Field	S287	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated									
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated									
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354702	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated									
Northern Athletic Field	S575	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated									
Northern Athletic Field	S576	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated									
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated									
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated									
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated									
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated									
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Football Field	ISMP-S2020	SSHS-ISMP-S2020	3/14/2022	-	855.66	-	846.17	8 - 10 ft	9.49 ft	1801351291	Not Excavated						
Football Field	ISMP-S2019	SSHS-ISMP-S2019	3/14/2022	-	855.61	-	846.13	8 - 10 ft	9.48 ft	1801351291	Not Excavated						
Football Field	ISMP-S2018	SSHS-ISMP-S2018	3/14/2022	-	855.73	-	846.63	8 - 10 ft	9.1 ft	1801351291	Not Excavated						
Football Field	ISMP-S2017	SSHS-ISMP-S2017	3/14/2022	-	855.85	-	846.87	8 - 10 ft	8.98 ft	1801351291	Not Excavated						
Northern Athletic Field	SSHS-B399	SSHS-B399-SUB-0-2	8/25/2016	856.45	856.57	0.12	-	0 - 2 ft	0.12-2.12 ft	180-57995-1	Not Excavated						
Northern Athletic Field	SSHS-B2030	SSHS-B2030-SUB-0-2	7/27/2018	856.20	856.42	0.22	-	0 - 2 ft	0.22-2.22 ft	180-80252-1	Not Excavated						
Northern Athletic Field	MS-SLT-S7	SSHS-ISMP-MS-SLT-S7	3/11/2022	-	854.29	-	854.29	0 - 2 ft	2.03 ft	1801350892	Not Excavated						
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-DUP305	7/14/2023	-	856.82	-	853.99	0 - 2 ft	2.84 ft	1801593501	Not Excavated						
Northern Athletic Field	SSHS-B77	SSHS-B77-0.17-2 (1.5)	8/14/2014	855.88	857.91	2.03	-	0.17 - 2 ft	2.2-4.03 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-0.17-2	1/26/2021	858.46	858.50	0.04	-	0.17 - 2 ft	0.21-2.04 ft	1801164622	Not Excavated	< 0.062 U	< 0.059 U	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SCV82-1-2	SSHS-IRM5A2-SCV82-1-2	11/10/2022	-	854.72	-	854.72	1 - 2 ft	3.74 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV84-1-2	SSHS-IRM5A2-SCV84-1-2	11/10/2022	-	855.34	-	855.34	1 - 2 ft	2.09 ft	1801477511	Not Excavated						
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656881	Not Excavated						
Northern Athletic Field	SCV102-1-2	SSHS-IRM5A2-SCV102-1-2	11/20/2023	-	855.52	-	855.52	1 - 2 ft	2 ft	1801656882	Not Excavated	< 0.034 U	< 0.019 U	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Northern Athletic Field	A1N-S217	SSHS-IRM5A2-A1N-S217	11/14/2022	-	852.45	-	852.45	1 - 2.5 ft	2.44 ft	1801479001	Not Excavated						
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479551	Not Excavated						
Northern Athletic Field	A1N-S215A	SSHS-IRM5A2-A1N-S215A	11/15/2022	-	852.41	-	852.41	1 - 2.5 ft	2.67 ft	1801479552	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-10-12	9/2/2016	852.44	854.81	2.37	-	10 - 12 ft	12.37-14.37 ft	180-58309-2	Not Excavated						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-10-12	12/20/2019	851.57	852.53	0.96	-	10 - 12 ft	10.96-12.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-10-12	5/11/2021	856.50	855.82	-0.68	-	10 - 12 ft	9.32-11.32 ft	1801214741	Not Excavated	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-10-12	5/17/2021	856.37	856.43	0.06	-	10 - 12 ft	10.06-12.06 ft	1801217472	Not Excavated	< 0.054 U	< 0.051 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-10-12	5/18/2021	855.95	855.66	-0.29	-	10 - 12 ft	9.71-11.71 ft	1801218221	Not Excavated	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-10-12	9/16/2021	856.07	856.16	0.09	-	10 - 12 ft	10.09-12.09 ft	180-127205-2	Not Excavated						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-10-12	9/17/2021	856.64	856.68	0.04	-	10 - 12 ft	10.04-12.04 ft	180-127265-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-10-12	9/17/2021	857.91	857.91	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-10-12	9/22/2021	856.72	856.72	0.00	-	10 - 12 ft	10-12 ft	180-127415-1	Not Excavated						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-DUP14	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-BOT1A	SSHS-IRM5A2-DW2-BOT1A	11/6/2021	-	857.12	-	846.00	10 - 12 ft	11.12 ft	1801296791	Not Excavated						
Northern Athletic Field	B236-BOT	SSHS-IRM5A2-B236-BOT	11/6/2021	-	855.93	-	845.82	10 - 12 ft	10.11 ft	1801296741	Not Excavated						
Northern Athletic Field	DW3-BOT1	SSHS-IRM5A2-DW3-BOT1	11/10/2021	-	856.71	-	846.37	10 - 12 ft	10.34 ft	1801298201	Not Excavated						
Northern Athletic Field	S598	SSHS-IRM5A2-S598	1/19/2022	-	854.88	-	843.94	10 - 12 ft	10.94 ft	1801325261	Not Excavated						
Northern Athletic Field	S597	SSHS-IRM5A2-S597	1/19/2022	-	855.72	-	844.64	10 - 12 ft	11.08 ft	1801325261	Not Excavated						
Northern Athletic Field	S249	SSHS-IRM5A2-S249	1/19/2022	-	856.35	-	845.77	10 - 12 ft	10.58 ft	1801325261	Not Excavated						
Northern Athletic Field	S250	SSHS-IRM5A2-S250	1/19/2022	-	856.17	-	845.59	10 - 12 ft	10.59 ft	1801325261	Not Excavated						
Northern Athletic Field	S251	SSHS-IRM5A2-S251	1/19/2022	-	856.51	-	845.51	10 - 12 ft	11 ft	1801325261	Not Excavated						
Northern Athletic Field	S245	SSHS-IRM5A2-S245	2/8/2022	-	857.79	-	846.84	10 - 12 ft	10.96 ft	1801333441	Not Excavated						
Northern Athletic Field	S234	SSHS-IRM5A2-S234	2/9/2022	-	857.86	-	847.15	10 - 12 ft	10.72 ft	1801334581	Not Excavated						
Northern Athletic Field	S233	SSHS-IRM5A2-S233	2/9/2022	-	857.95	-	847.18	10 - 12 ft	10.77 ft	1801334581	Not Excavated						
Northern Athletic Field	S232	SSHS-IRM5A2-DUP44	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated						
Northern Athletic Field	S230	SSHS-IRM5A2-S230	2/10/2022	-	858.50	-	847.81	10 - 12 ft	10.69 ft	1801335311	Not Excavated						
Northern Athletic Field	S232	SSHS-IRM5A2-S232	2/10/2022	-	858.08	-	847.23	10 - 12 ft	10.85 ft	1801335311	Not Excavated						
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335311	Not Excavated						
Northern Athletic Field	S231	SSHS-IRM5A2-S231	2/10/2022	-	858.77	-	847.80	10 - 12 ft	10.97 ft	1801335312	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S585	SSHS-IRM5A2-S585	2/21/2022	-	857.34	-	846.42	10 - 12 ft	10.92 ft	1801340041	Not Excavated						
Northern Athletic Field	S571	SSHS-IRM5A2-S571	3/3/2022	-	854.30	-	843.21	10 - 12 ft	11.08 ft	1801346401	Not Excavated						
Northern Athletic Field	S573	SSHS-IRM5A2-S573	3/5/2022	-	853.18	-	842.98	10 - 12 ft	10.2 ft	1801347851	Not Excavated						
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351301	Not Excavated						
Northern Athletic Field	S584	SSHS-IRM5A2-S584	3/14/2022	-	857.25	-	845.20	10 - 12 ft	12.05 ft	1801351302	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	S583	SSHS-IRM5A2-S583	3/14/2022	-	856.97	-	844.95	10 - 12 ft	12.02 ft	1801351301	Not Excavated						
Northern Athletic Field	S582	SSHS-IRM5A2-S582	3/14/2022	-	855.64	-	844.91	10 - 12 ft	10.73 ft	1801351301	Not Excavated						
Northern Athletic Field	S287	SSHS-IRM5A2-S287	3/18/2022	-	853.35	-	841.46	10 - 12 ft	11.89 ft	1801354282	Not Excavated						
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354701	Not Excavated						
Northern Athletic Field	S290	SSHS-IRM5A2-S290	3/19/2022	-	854.75	-	842.95	10 - 12 ft	11.8 ft	1801354702	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S574	SSHS-IRM5A2-S574	3/19/2022	-	853.42	-	843.11	10 - 12 ft	10.31 ft	1801354701	Not Excavated						
Northern Athletic Field	S575	SSHS-IRM5A2-S575	3/19/2022	-	853.81	-	843.21	10 - 12 ft	10.61 ft	1801354701	Not Excavated						
Northern Athletic Field	S576	SSHS-IRM5A2-S576	3/19/2022	-	853.80	-	843.62	10 - 12 ft	10.19 ft	1801354701	Not Excavated						
Northern Athletic Field	S174-BOT6	SSHS-IRM5A2-S174-BOT6	3/20/2022	-	857.48	-	846.42	10 - 12 ft	11.05 ft	1801354871	Not Excavated						
Northern Athletic Field	A5-V1-S9	SSHS-IRM5A2-A5-V1-S9	4/25/2022	-	855.53	-	844.36	10 - 12 ft	11.17 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-S7	SSHS-IRM5A2-A5-V1-S7	4/25/2022	-	855.70	-	845.05	10 - 12 ft	10.65 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-S11	SSHS-IRM5A2-A5-V1-S11	4/25/2022	-	855.77	-	844.99	10 - 12 ft	10.79 ft	1801371272	Not Excavated						
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-DUP87	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated						
Northern Athletic Field	FISLAT1SOUTHA	SSHS-IRM5A2-FIS-LAT1-SOUTHA	5/12/2022	-	857.20	-	846.74	10 - 12 ft	10.45 ft	1801380711	Not Excavated						
Northern Athletic Field	CP2-BOT1	SSHS-IRM5A2-CP2-BOT1	5/12/2022	-	856.32	-	844.94	10 - 12 ft	11.39 ft	1801380691	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated		< 31 U							
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated		< 30 U							
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380692	Not Excavated				< 0.048 U	< 0.038 U	0.056 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated		< 31 U							
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated		< 34 U							
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated	< 120 U								
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated		< 31 U							
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated		< 32 U							
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395464	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated		< 31 U							
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated		< 31 U							
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated		< 33 U							
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395464	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395783	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395783	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395783	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated		< 320 U							
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395973	Not Excavated				< 0.48 U	< 0.38 U	< 0.46 U	< 0.52 U	< 0.48 U	< 0.30 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395973	Not Excavated				< 0.50 U	< 0.39 U	< 0.48 U	< 0.54 U	< 0.50 U	< 0.31 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395973	Not Excavated				< 0.52 U	< 0.42 U	< 0.50 U	< 0.57 U	< 0.52 U	< 0.33 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated		< 34 U							
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated		< 48 U							
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396812	Not Excavated				< 0.050 U	< 0.040 U	1.2	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397522	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397522	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated									
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated									
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated									
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380692	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.061 J	< 0.053 U	< 0.041 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated									
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated									
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated									
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated									
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated									
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395464	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.057 U	< 0.044 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated									
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395464	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395783	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395783	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395783	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395973	Not Excavated	< 0.49 U	< 0.38 U	< 0.29 U	< 0.31 U	< 0.22 U	< 0.33 U	< 0.43 U	< 0.53 U	< 0.41 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395973	Not Excavated	< 0.51 U	< 0.39 U	< 0.30 U	< 0.32 U	< 0.23 U	< 0.34 U	< 0.45 U	< 0.55 U	< 0.42 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395973	Not Excavated	< 0.54 U	< 0.42 U	< 0.32 U	< 0.34 U	< 0.24 U	< 0.36 U	< 0.47 U	< 0.58 U	< 0.45 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated									
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated									
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated									
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396812	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397522	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	0.050 J
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397522	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	CP2-S11	SSHS-IRM5A2-CP2-S11	5/12/2022	-	856.29	-	846.21	10 - 12 ft	10.08 ft	1801380691	Not Excavated						
Northern Athletic Field	CP2-S12	SSHS-IRM5A2-CP2-S12	5/12/2022	-	856.46	-	845.97	10 - 12 ft	10.5 ft	1801380691	Not Excavated						
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380691	Not Excavated						
Northern Athletic Field	CP2-BOT2	SSHS-IRM5A2-CP2-BOT2	5/12/2022	-	856.63	-	844.94	10 - 12 ft	11.69 ft	1801380692	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	CP2-S13	SSHS-IRM5A2-CP2-S13	5/12/2022	-	856.63	-	845.58	10 - 12 ft	11.04 ft	1801380691	Not Excavated						
Northern Athletic Field	CP2-S14	SSHS-IRM5A2-CP2-S14	5/12/2022	-	856.70	-	845.79	10 - 12 ft	10.91 ft	1801380691	Not Excavated						
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-10-12	6/4/2022	856.18	856.99	0.81	-	10 - 12 ft	10.81-12.81 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-10-12	6/4/2022	857.21	855.60	-1.61	-	10 - 12 ft	8.39-10.39 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-10-12	6/4/2022	856.60	856.86	0.26	-	10 - 12 ft	10.26-12.26 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-10-12	6/4/2022	856.27	856.38	0.11	-	10 - 12 ft	10.11-12.11 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-10-12	6/4/2022	856.61	857.29	0.68	-	10 - 12 ft	10.68-12.68 ft	180-139185-1	Not Excavated						
Northern Athletic Field	A4-FIS-B3	SSHS-IRM5A2-A4-FIS-B3	6/10/2022	-	857.68	-	847.26	10 - 12 ft	10.42 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-S4	SSHS-IRM5A2-A4-FIS-S4	6/10/2022	-	857.67	-	847.42	10 - 12 ft	10.26 ft	1801395462	Not Excavated						
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395463	Not Excavated						
Northern Athletic Field	CP2-BOT3	SSHS-IRM5A2-CP2-BOT3	6/10/2022	-	856.95	-	846.48	10 - 12 ft	10.47 ft	1801395464	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	CP2-S22	SSHS-IRM5A2-CP2-S22	6/10/2022	-	857.00	-	846.61	10 - 12 ft	10.39 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-FIS-B4	SSHS-IRM5A2-A4-FIS-B4	6/10/2022	-	857.67	-	847.28	10 - 12 ft	10.4 ft	1801395462	Not Excavated						
Northern Athletic Field	CP2-S23	SSHS-IRM5A2-CP2-S23	6/10/2022	-	857.19	-	846.98	10 - 12 ft	10.21 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-B5	SSHS-IRM5A2-A4-FIS-B5	6/10/2022	-	857.58	-	847.51	10 - 12 ft	10.07 ft	1801395464	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A4-S100	SSHS-IRM5A2-DUP111	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395783	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S506-BOT	SSHS-IRM5A2-S506-BOT	6/11/2022	-	857.79	-	847.03	10 - 12 ft	10.77 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S8	SSHS-IRM5A2-FISR-S8	6/11/2022	-	854.24	-	843.18	10 - 12 ft	11.06 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S100	SSHS-IRM5A2-A4-S100	6/11/2022	-	857.75	-	847.16	10 - 12 ft	10.59 ft	1801395783	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A4-S101	SSHS-IRM5A2-A4-S101	6/11/2022	-	857.93	-	846.93	10 - 12 ft	11.01 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S102	SSHS-IRM5A2-A4-S102	6/11/2022	-	857.80	-	847.00	10 - 12 ft	10.8 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S103	SSHS-IRM5A2-A4-S103	6/11/2022	-	857.74	-	847.20	10 - 12 ft	10.54 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S104	SSHS-IRM5A2-A4-S104	6/11/2022	-	857.65	-	847.27	10 - 12 ft	10.37 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S105	SSHS-IRM5A2-A4-S105	6/11/2022	-	857.59	-	847.24	10 - 12 ft	10.35 ft	1801395783	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-DUP117	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S16	SSHS-IRM5A2-FISR-S16	6/13/2022	-	854.80	-	843.05	10 - 12 ft	11.76 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S20	SSHS-IRM5A2-FISR-S20	6/13/2022	-	855.02	-	843.10	10 - 12 ft	11.92 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S23	SSHS-IRM5A2-FISR-S23	6/13/2022	-	855.21	-	845.10	10 - 12 ft	10.11 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S24	SSHS-IRM5A2-FISR-S24	6/13/2022	-	855.21	-	843.40	10 - 12 ft	11.81 ft	1801395973	Not Excavated	< 0.37 U	< 0.21 U	< 0.42 U	< 0.35 U	< 0.27 U	< 0.23 U
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S28	SSHS-IRM5A2-FISR-S28	6/13/2022	-	855.06	-	843.46	10 - 12 ft	11.6 ft	1801395973	Not Excavated	< 0.38 U	< 0.22 U	< 0.43 U	< 0.36 U	< 0.28 U	< 0.24 U
Northern Athletic Field	FISR-S32	SSHS-IRM5A2-FISR-S32	6/13/2022	-	855.21	-	843.90	10 - 12 ft	11.3 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S35	SSHS-IRM5A2-FISR-S35	6/13/2022	-	855.07	-	844.89	10 - 12 ft	10.17 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S36	SSHS-IRM5A2-FISR-S36	6/13/2022	-	855.07	-	843.47	10 - 12 ft	11.59 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S40	SSHS-IRM5A2-FISR-S40	6/13/2022	-	855.27	-	843.61	10 - 12 ft	11.65 ft	1801395973	Not Excavated	< 0.40 U	< 0.23 U	< 0.46 U	< 0.38 U	< 0.30 U	< 0.25 U
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-DUP120	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated						
Northern Athletic Field	FISR-S44	SSHS-IRM5A2-FISR-S44	6/14/2022	-	855.13	-	843.32	10 - 12 ft	11.81 ft	1801396811	Not Excavated						
Northern Athletic Field	FISR-S45	SSHS-IRM5A2-FISR-S45	6/14/2022	-	855.22	-	844.83	10 - 12 ft	10.39 ft	1801396811	Not Excavated						
Northern Athletic Field	FISR-S46	SSHS-IRM5A2-FISR-S46	6/14/2022	-	855.23	-	843.73	10 - 12 ft	11.5 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-B1	SSHS-IRM5A2-A3-FISRLAT1-B1	6/14/2022	-	855.27	-	845.16	10 - 12 ft	10.11 ft	1801396812	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-FISRLAT1-B3	SSHS-IRM5A2-A3-FISRLAT1-B3	6/14/2022	-	855.87	-	845.81	10 - 12 ft	10.06 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S2	SSHS-IRM5A2-A3-DEBRIS-S2	6/15/2022	-	856.41	-	845.30	10 - 12 ft	11.11 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S4	SSHS-IRM5A2-A3-DEBRIS-S4	6/15/2022	-	856.33	-	845.10	10 - 12 ft	11.23 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S6	SSHS-IRM5A2-A3-DEBRIS-S6	6/15/2022	-	856.08	-	844.05	10 - 12 ft	12.03 ft	1801397522	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	A3-DEBRIS-S8	SSHS-IRM5A2-A3-DEBRIS-S8	6/15/2022	-	856.09	-	844.65	10 - 12 ft	11.43 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-B1	SSHS-IRM5A2-A3-DEBRIS-B1	6/15/2022	-	856.28	-	844.46	10 - 12 ft	11.82 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-B2	SSHS-IRM5A2-A3-DEBRIS-B2	6/15/2022	-	856.14	-	844.20	10 - 12 ft	11.94 ft	1801397522	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A3-WELL-S1	SSHS-IRM5A2-A3-WELL-S1	6/16/2022	-	855.79	-	845.42	10 - 12 ft	10.37 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-WELL-B1	SSHS-IRM5A2-A3-WELL-B1	6/16/2022	-	855.74	-	844.75	10 - 12 ft	10.99 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-WELL-S2	SSHS-IRM5A2-A3-WELL-S2	6/16/2022	-	855.67	-	845.11	10 - 12 ft	10.56 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-DUP128	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated		< 31 U							
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated		< 33 U							
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated		< 32 UT							
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated		< 30 U							
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400212	Not Excavated				< 0.052 U	< 0.81 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated		< 34 U							
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406773	Not Excavated				< 0.049 U	< 0.039 U	0.057 J	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated		< 32 U							
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426142	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated		< 31 U							
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426142	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated		< 33 U							
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated		< 31 U							
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426152	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426152	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated		< 32 U							
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated		< 32 U							
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427632	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated		< 30 U							
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated		< 30 U							
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated		< 34 U							
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430702	Not Excavated				< 0.19 U	< 0.15 U	< 0.18 U	< 0.20 U	< 0.19 U	< 0.12 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated		< 30 U							
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430712	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated		< 30 U							
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated		< 33 U							
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated		< 31 U							
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated		< 32 U							
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated									
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400212	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	0.21 J
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated									
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406773	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426142	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.17 J	< 0.058 U	< 0.045 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426142	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.13 J	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426152	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426152	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427632	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.18 J	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated									
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated									
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430702	Not Excavated	< 0.19 U	< 0.15 U	< 0.11 U	< 0.12 U	< 0.086 U	< 0.13 U	< 0.17 U	< 0.21 U	< 0.16 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated									
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430712	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated									
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated									
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated									
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated									
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A3-DEBRIS-S10	SSHS-IRM5A2-A3-DEBRIS-S10	6/17/2022	-	856.13	-	844.46	10 - 12 ft	11.67 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S12	SSHS-IRM5A2-A3-DEBRIS-S12	6/17/2022	-	856.41	-	845.59	10 - 12 ft	10.82 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-DEBRIS-B3	SSHS-IRM5A2-A3-DEBRIS-B3	6/17/2022	-	856.33	-	844.76	10 - 12 ft	11.57 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B1	SSHS-IRM5A2-A3-FISLAT2-B1	6/17/2022	-	855.24	-	845.05	10 - 12 ft	10.19 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B2	SSHS-IRM5A2-A3-FISLAT2-B2	6/17/2022	-	855.49	-	845.21	10 - 12 ft	10.28 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B3	SSHS-IRM5A2-A3-FISLAT2-B3	6/17/2022	-	855.82	-	845.60	10 - 12 ft	10.22 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-DUP136	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-DUP132	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated						
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-10-12	6/20/2022	856.38	856.44	0.06	-	10 - 12 ft	10.06-12.06 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-10-12	6/20/2022	856.66	856.67	0.01	-	10 - 12 ft	10.01-12.01 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-10-12	6/20/2022	856.60	856.56	-0.04	-	10 - 12 ft	9.96-11.96 ft	180-140136-1	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S9	SSHS-IRM5A2-A3-FISLAT2-S9	6/20/2022	-	856.54	-	845.81	10 - 12 ft	10.73 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S11	SSHS-IRM5A2-A3-FISLAT2-S11	6/20/2022	-	856.54	-	845.92	10 - 12 ft	10.62 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S17	SSHS-IRM5A2-A3-FISLAT2-S17	6/20/2022	-	857.37	-	847.20	10 - 12 ft	10.17 ft	1801400212	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-FISLAT2-S19	SSHS-IRM5A2-A3-FISLAT2-S19	6/20/2022	-	857.40	-	847.24	10 - 12 ft	10.16 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B5	SSHS-IRM5A2-A3-FISLAT2-B5	6/20/2022	-	856.54	-	845.45	10 - 12 ft	11.09 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B6	SSHS-IRM5A2-A3-FISLAT2-B6	6/20/2022	-	856.90	-	846.36	10 - 12 ft	10.54 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B7	SSHS-IRM5A2-A3-FISLAT2-B7	6/20/2022	-	857.42	-	846.70	10 - 12 ft	10.71 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B9	SSHS-IRM5A2-A3-FISLAT2-B9	6/20/2022	-	857.68	-	847.16	10 - 12 ft	10.52 ft	1801400231	Not Excavated						
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-BOT15	SSHS-IRM5A2-FISR-BOT15	6/30/2022	-	854.62	-	844.51	10 - 12 ft	10.11 ft	1801406773	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-DUP1A	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426142	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW1-B1	SSHS-ISMP-FLDW1-B1	8/8/2022	-	856.18	-	845.88	10 - 12 ft	10.29 ft	1801426142	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S1000	SSHS-IRM5A2-FL-S1000	8/8/2022	-	856.44	-	846.26	10 - 12 ft	10.18 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1001	SSHS-IRM5A2-FL-S1001	8/8/2022	-	856.34	-	846.14	10 - 12 ft	10.2 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1006	SSHS-IRM5A2-FL-S1006	8/8/2022	-	856.39	-	846.17	10 - 12 ft	10.22 ft	1801426152	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1202	SSHS-IRM5A2-FL-S1202	8/8/2022	-	855.95	-	844.53	10 - 12 ft	11.42 ft	1801426152	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	0.032 J	< 0.022 U
Northern Athletic Field	FL-S1203	SSHS-IRM5A2-FL-S1203	8/8/2022	-	855.79	-	844.78	10 - 12 ft	11.01 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1204	SSHS-IRM5A2-FL-S1204	8/8/2022	-	855.95	-	844.54	10 - 12 ft	11.41 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1205	SSHS-IRM5A2-FL-S1205	8/8/2022	-	856.08	-	844.31	10 - 12 ft	11.77 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-DUP188	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S6	SSHS-IRM5A2-FL-DW3A-S6	8/10/2022	-	856.54	-	846.43	10 - 12 ft	10.11 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S8	SSHS-IRM5A2-FL-DW3A-S8	8/10/2022	-	856.56	-	846.54	10 - 12 ft	10.03 ft	1801427632	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-DW3A-S9	SSHS-IRM5A2-FL-DW3A-S9	8/10/2022	-	856.64	-	846.54	10 - 12 ft	10.1 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-FISN-S41BOT	SSHS-IRM5A2-FL-FISN-S41BOT	8/10/2022	-	856.62	-	846.30	10 - 12 ft	10.32 ft	1801427631	Not Excavated						
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-DUP196	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S94	SSHS-IRM5A2-FISR-S94	8/13/2022	-	855.22	-	845.04	10 - 12 ft	10.18 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S98	SSHS-IRM5A2-FISR-S98	8/13/2022	-	855.07	-	844.83	10 - 12 ft	10.24 ft	1801429561	Not Excavated						
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-DUP200	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S1	SSHS-IRM5A2-FLSP-S1	8/17/2022	-	856.41	-	846.23	10 - 12 ft	10.18 ft	1801430702	Not Excavated	< 0.14 U	< 0.082 U	< 0.16 U	< 0.14 U	< 0.11 U	< 0.090 U
Northern Athletic Field	FLSP-S3	SSHS-IRM5A2-FLSP-S3	8/17/2022	-	856.46	-	846.43	10 - 12 ft	10.04 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S6	SSHS-IRM5A2-FLSP-S6	8/17/2022	-	856.56	-	846.37	10 - 12 ft	10.19 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S7	SSHS-IRM5A2-FLSP-S7	8/17/2022	-	856.58	-	846.26	10 - 12 ft	10.33 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S8	SSHS-IRM5A2-FLSP-S8	8/17/2022	-	856.66	-	846.21	10 - 12 ft	10.44 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-B1	SSHS-IRM5A2-FLSP-B1	8/17/2022	-	856.39	-	846.15	10 - 12 ft	10.24 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-B2	SSHS-IRM5A2-FLSP-B2	8/17/2022	-	856.45	-	845.85	10 - 12 ft	10.61 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430711	Not Excavated						
Northern Athletic Field	FLSP-B3	SSHS-IRM5A2-FLSP-B3	8/17/2022	-	856.62	-	845.92	10 - 12 ft	10.69 ft	1801430712	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-DUP195	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated						
Northern Athletic Field	FISR-S73	SSHS-IRM5A2-FISR-S73	8/18/2022	-	854.76	-	844.56	10 - 12 ft	10.2 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S82	SSHS-IRM5A2-FISR-S82	8/18/2022	-	855.01	-	844.97	10 - 12 ft	10.04 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S85	SSHS-IRM5A2-FISR-S85	8/18/2022	-	855.16	-	845.13	10 - 12 ft	10.03 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S89	SSHS-IRM5A2-FISR-S89	8/18/2022	-	854.97	-	844.88	10 - 12 ft	10.09 ft	1801430971	Not Excavated						
Northern Athletic Field	FISR-BOT17	SSHS-IRM5A2-FISR-BOT17	8/18/2022	-	854.96	-	844.53	10 - 12 ft	10.43 ft	1801430971	Not Excavated						
Northern Athletic Field	A6-S1000	SSHS-IRM5A2-A6-S1000	8/23/2022	-	857.56	-	846.16	10 - 12 ft	11.4 ft	1801433671	Not Excavated						
Northern Athletic Field	A6-S1001	SSHS-IRM5A2-A6-S1001	8/23/2022	-	857.73	-	846.32	10 - 12 ft	11.42 ft	1801433671	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated		< 33 U							
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated		< 32 U							
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated		< 34 U							
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442132	Not Excavated				< 0.051 U	< 0.041 U	0.12 J	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated		< 34 U							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated		< 30 U							
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated		< 31 U							
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated		< 33 U							
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465942	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated		< 30 U							
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469432	Not Excavated				< 0.048 U	< 0.038 U	0.38 B	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469432	Not Excavated				< 0.052 U	< 0.041 U	0.56 B	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491402	Not Excavated				< 0.050 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated		< 30 U							
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated		< 36 U							
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491402	Not Excavated				< 0.048 U	< 0.038 U	0.059 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665992	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669712	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669712	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669702	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated			< 40						
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated			< 41						
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated			< 40						
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated			< 42						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 100 U			< 0.35 U	< 0.024 U	0.43 B	< 0.037 U	< 0.021 U	< 0.064 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.066 J	< 0.044 U	< 0.025 U	< 0.075 U
Northern Athletic Field	SSHS-B3021	DUP-42	5/17/2021	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 110 U			< 0.36 U	< 0.024 U	< 0.027 U	< 0.038 U	< 0.021 U	< 0.065 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.066 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated			< 110 U	< 0.046 U	< 0.037 U	< 0.044 U	< 0.05 U	< 0.046 U	< 0.029 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated									
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated									
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated									
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442132	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.057 U	0.066 J
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465942	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated									
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated									
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469432	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.049 J	< 0.053 U	< 0.041 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated									
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469432	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.049 J	< 0.058 U	< 0.044 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491402	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491402	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated									
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated									
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated									
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665992	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated									
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669712	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated									
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669712	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated									
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated									
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669702	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	0.10 J	0.40	< 0.043 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated									
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated									
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated									
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.033 U	< 0.028 U	< 0.030 U	< 0.040 U	< 0.034 U	< 0.078 U	0.37 BJ	< 0.082 U	< 0.073 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.036 U	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.079 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.039 U	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U
Northern Athletic Field	SSHS-B3021	DUP-42	5/17/2021	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.034 U	< 0.028 U	< 0.030 U	< 0.041 U	< 0.035 U	< 0.080 U	< 0.19 U	< 0.084 U	< 0.075 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.081 U	< 0.20 U	< 0.085 U	< 0.076 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.036 U	< 0.030 U	< 0.032 U	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated									
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated									
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.03 U	< 0.021 U	< 34 U	< 0.041 U	< 0.051 U	< 0.04 U

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6-S1002	SSHS-IRM5A2-A6-S1002	8/23/2022	-	857.68	-	846.30	10 - 12 ft	11.38 ft	1801433671	Not Excavated						
Northern Athletic Field	A6-B1000	SSHS-IRM5A2-A6-B1000	8/23/2022	-	857.66	-	846.27	10 - 12 ft	11.4 ft	1801433671	Not Excavated						
Northern Athletic Field	ST-S1000	SSHS-IRM5A2-ST-S1000	8/24/2022	-	856.50	-	846.17	10 - 12 ft	10.33 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1001	SSHS-IRM5A2-ST-S1001	8/24/2022	-	856.62	-	846.47	10 - 12 ft	10.15 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1200	SSHS-IRM5A2-ST-S1200	8/24/2022	-	856.46	-	844.45	10 - 12 ft	12.01 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1202	SSHS-IRM5A2-ST-S1202	8/24/2022	-	856.40	-	844.72	10 - 12 ft	11.68 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1003	SSHS-IRM5A2-ST-S1003	8/25/2022	-	856.57	-	846.49	10 - 12 ft	10.08 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1004	SSHS-IRM5A2-ST-S1004	8/25/2022	-	856.97	-	846.28	10 - 12 ft	10.7 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1205	SSHS-IRM5A2-ST-S1205	8/25/2022	-	856.43	-	845.02	10 - 12 ft	11.4 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1206	SSHS-IRM5A2-ST-S1206	8/25/2022	-	856.14	-	845.07	10 - 12 ft	11.07 ft	1801435261	Not Excavated						
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-DUP221	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-B1001	SSHS-IRM5A2-A6-B1001	9/8/2022	-	856.79	-	846.63	10 - 12 ft	10.16 ft	1801442132	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B1002	SSHS-IRM5A2-A6-B1002	9/8/2022	-	856.84	-	846.71	10 - 12 ft	10.13 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-DUP243	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S806A	SSHS-IRM5A2-A6-S806A	10/20/2022	-	857.76	-	847.07	10 - 12 ft	10.69 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-B800	SSHS-IRM5A2-A6-B800	10/20/2022	-	857.52	-	847.08	10 - 12 ft	10.44 ft	1801465942	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A19-S1BOT	SSHS-IRM5A2-A19-S1BOT	10/25/2022	-	857.61	-	847.28	10 - 12 ft	10.33 ft	1801468421	Not Excavated						
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated						
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-DUP248	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469432	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469431	Not Excavated						
Northern Athletic Field	A1-VAULT-BOT	SSHS-IRM5A2-A1-VAULT-BOT	10/26/2022	-	857.21	-	846.94	10 - 12 ft	10.27 ft	1801469432	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-DUP270	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-BOT1	SSHS-IRM5A2-A6N-B802-BOT1	12/9/2022	-	854.96	-	844.79	10 - 12 ft	10.17 ft	1801491402	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6N-B802-BOT2	SSHS-IRM5A2-A6N-B802-BOT2	12/9/2022	-	855.08	-	844.68	10 - 12 ft	10.4 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-BOT3	SSHS-IRM5A2-A6N-B802-BOT3	12/9/2022	-	855.11	-	844.94	10 - 12 ft	10.17 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-S1	SSHS-IRM5A2-A6N-B802-S1	12/9/2022	-	854.96	-	844.71	10 - 12 ft	10.24 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-S3	SSHS-IRM5A2-A6N-B802-S3	12/9/2022	-	855.15	-	844.88	10 - 12 ft	10.27 ft	1801491402	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6N-B802-S4	SSHS-IRM5A2-A6N-B802-S4	12/9/2022	-	855.07	-	844.54	10 - 12 ft	10.53 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-BOT	SSHS-IRM5A2-A6N-S800-BOT	12/9/2022	-	855.02	-	844.35	10 - 12 ft	10.67 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B802-S5	SSHS-IRM5A2-A6N-B802-S5	12/9/2022	-	854.97	-	844.75	10 - 12 ft	10.22 ft	1801491401	Not Excavated						
Northern Athletic Field	NAF-IG-S5	SSHS-ISMP-NAF-IG-S5	5/30/2023	-	853.43	-	843.36	10 - 12 ft	10.07 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-DUP6A	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S15	SSHS-ISMP-NAF-IG-S15	6/1/2023	-	853.27	-	843.01	10 - 12 ft	10.26 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S21	SSHS-ISMP-NAF-IG-S21	6/1/2023	-	853.36	-	841.86	10 - 12 ft	11.5 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S27	SSHS-ISMP-NAF-IG-S27	6/1/2023	-	853.46	-	843.43	10 - 12 ft	10.03 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S28	SSHS-ISMP-NAF-IG-S28	6/1/2023	-	853.60	-	841.87	10 - 12 ft	11.73 ft	1801573811	Not Excavated						
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665991	Not Excavated						
Northern Athletic Field	A8PH3A1-B5-BOT	SSHS-IRM5A2-A8PH3A1-B5-BOT	12/8/2023	-	852.26	-	841.68	10 - 12 ft	10.58 ft	1801665992	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated						
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-DUP338	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669712	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669711	Not Excavated						
Northern Athletic Field	A8PH3A1-S33	SSHS-IRM5A2-A8PH3A1-S33	12/14/2023	-	--	-	841.89	10 - 12 ft	10 - 12 ft	1801669712	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	0.057 J	< 0.024 U
Northern Athletic Field	A8PH3A1-S30-BOT	SSHS-IRM5A2-A8PH3A1-S30-BOT	12/14/2023	-	852.25	-	841.72	10 - 12 ft	10.53 ft	1801669701	Not Excavated						
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669701	Not Excavated						
Northern Athletic Field	A8PH3A1-B10	SSHS-IRM5A2-A8PH3A1-B10	12/14/2023	-	852.04	-	841.85	10 - 12 ft	10.19 ft	1801669702	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B75	SSHS-B75-10-15 (12.5)	8/14/2014	856.08	856.35	0.27	-	10 - 15 ft	10.27-15.27 ft	180-35818-2	Not Excavated						
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-12-14	12/20/2019	851.57	852.53	0.96	-	12 - 14 ft	12.96-14.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.052 U	< 0.049 U	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-12-14	5/11/2021	856.50	855.82	-0.68	-	12 - 14 ft	11.32-13.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-12-14	5/12/2021	853.71	854.79	1.08	-	12 - 14 ft	13.08-15.08 ft	1801215482	Not Excavated	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3021	DUP-42	5/17/2021	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.053 U	< 0.050 U	< 0.035 U	< 0.24 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-12-14	5/17/2021	856.37	856.43	0.06	-	12 - 14 ft	12.06-14.06 ft	1801217472	Not Excavated	< 0.053 U	< 0.050 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-12-14	5/18/2021	855.95	855.66	-0.29	-	12 - 14 ft	11.71-13.71 ft	1801218221	Not Excavated	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3017A	SSHS-B3017A-SUB-12-14	6/17/2021	853.79	853.15	-0.64	-	12 - 14 ft	11.36-13.36 ft	180-123398-1	Not Excavated						
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-12-14	9/16/2021	856.07	856.16	0.09	-	12 - 14 ft	12.09-14.09 ft	180-127205-2	Not Excavated						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-12-14	9/17/2021	856.64	856.68	0.04	-	12 - 14 ft	12.04-14.04 ft	180-127265-1	Not Excavated	< 0.036 U	< 34 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S599	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S600	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated	< 120 U								
Northern Athletic Field	S601	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S602	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated	< 110 U								
Northern Athletic Field	S592	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated	< 140 U								
Northern Athletic Field	S596	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S277	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S591	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated	< 130 U								
Northern Athletic Field	S590	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated	< 120 U								
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 110 U								
Northern Athletic Field	S588	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated	< 110 U								
Northern Athletic Field	S586	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated	< 120 U								
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated	< 110 U								
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340042	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated	< 100 U								
Northern Athletic Field	B595	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated	< 110 U								
Northern Athletic Field	B596	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated	< 110 U								
Northern Athletic Field	S282	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated	< 110 U								
Northern Athletic Field	S283	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S319	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S317	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated	< 120 U								
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354283	Not Excavated				< 0.053 U	< 0.042 U	0.15 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated	< 100 U								
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354283	Not Excavated				< 0.050 U	< 0.039 U	0.14 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	B697	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	S284	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated	< 120 U								
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354283	Not Excavated				< 0.053 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S286	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated	< 110 U								
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359742	Not Excavated				< 0.053 U	< 0.042 U	0.20 BJ	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated	< 110 U								
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated	< 110 U								
Northern Athletic Field	S730	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated	< 110 U								
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371273	Not Excavated				< 0.047 U	< 0.037 U	0.15 J	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated			< 100 U						
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated		< 29 U							
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated		< 30 U							
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395464	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated		< 32 U							
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 120 U								
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 130 U								
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated	< 120 U								
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated	< 120 U								
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated									
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated									
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated									
Northern Athletic Field	S599	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated									
Northern Athletic Field	S600	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated									
Northern Athletic Field	S601	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated									
Northern Athletic Field	S602	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated									
Northern Athletic Field	S592	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated									
Northern Athletic Field	S596	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated									
Northern Athletic Field	S277	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated									
Northern Athletic Field	S591	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated									
Northern Athletic Field	S590	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated									
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated									
Northern Athletic Field	S588	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated									
Northern Athletic Field	S586	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated									
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated									
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340042	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated									
Northern Athletic Field	B595	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated									
Northern Athletic Field	B596	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated									
Northern Athletic Field	S282	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated									
Northern Athletic Field	S283	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated									
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated									
Northern Athletic Field	S319	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated									
Northern Athletic Field	S318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated									
Northern Athletic Field	S317	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated									
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated									
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354283	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	0.041 J	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 UT
Northern Athletic Field	S315	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated									
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated									
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated									
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354283	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	0.15 J
Northern Athletic Field	S313	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated									
Northern Athletic Field	B697	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated									
Northern Athletic Field	S284	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated									
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated									
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354283	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated									
Northern Athletic Field	S286	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated									
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated									
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359742	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated									
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated									
Northern Athletic Field	S730	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated									
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371273	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	0.13 J	< 0.052 U	0.062 J
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated									
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated									
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated									
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395464	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated									
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-12-14	9/17/2021	857.91	857.91	0.00	-	12 - 14 ft	12-14 ft	180-127265-2	Not Excavated						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-12-14	9/22/2021	856.72	856.72	0.00	-	12 - 14 ft	12-14 ft	180-127415-1	Not Excavated						
Northern Athletic Field	S599	SSHS-IRM5A2-DUP27	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated						
Northern Athletic Field	S599	SSHS-IRM5A2-S599	1/19/2022	-	856.46	-	843.80	12 - 14 ft	12.66 ft	1801325261	Not Excavated						
Northern Athletic Field	S600	SSHS-IRM5A2-S600	1/19/2022	-	856.50	-	843.34	12 - 14 ft	13.16 ft	1801325261	Not Excavated						
Northern Athletic Field	S601	SSHS-IRM5A2-S601	1/19/2022	-	856.80	-	843.52	12 - 14 ft	13.28 ft	1801325261	Not Excavated						
Northern Athletic Field	S602	SSHS-IRM5A2-S602	1/20/2022	-	855.88	-	843.74	12 - 14 ft	12.13 ft	1801325891	Not Excavated						
Northern Athletic Field	S592	SSHS-IRM5A2-S592	2/8/2022	-	857.78	-	845.21	12 - 14 ft	12.57 ft	1801333441	Not Excavated						
Northern Athletic Field	S596	SSHS-IRM5A2-S596	2/8/2022	-	857.31	-	844.92	12 - 14 ft	12.39 ft	1801333441	Not Excavated						
Northern Athletic Field	S277	SSHS-IRM5A2-S277	2/8/2022	-	855.68	-	841.90	12 - 14 ft	13.78 ft	1801333441	Not Excavated						
Northern Athletic Field	S591	SSHS-IRM5A2-S591	2/9/2022	-	857.92	-	844.88	12 - 14 ft	13.04 ft	1801334581	Not Excavated						
Northern Athletic Field	S590	SSHS-IRM5A2-S590	2/9/2022	-	857.89	-	845.22	12 - 14 ft	12.67 ft	1801334581	Not Excavated						
Northern Athletic Field	S589	SSHS-IRM5A2-DUP45	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated						
Northern Athletic Field	S588	SSHS-IRM5A2-S588	2/21/2022	-	858.35	-	845.52	12 - 14 ft	12.83 ft	1801340041	Not Excavated						
Northern Athletic Field	S586	SSHS-IRM5A2-S586	2/21/2022	-	857.80	-	845.67	12 - 14 ft	12.14 ft	1801340041	Not Excavated						
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340041	Not Excavated						
Northern Athletic Field	S587	SSHS-IRM5A2-S587	2/21/2022	-	858.61	-	845.84	12 - 14 ft	12.77 ft	1801340042	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	S589	SSHS-IRM5A2-S589	2/21/2022	-	857.95	-	845.08	12 - 14 ft	12.87 ft	1801340041	Not Excavated						
Northern Athletic Field	B595	SSHS-IRM5A2-B595	3/2/2022	-	857.52	-	845.06	12 - 14 ft	12.46 ft	1801345571	Not Excavated						
Northern Athletic Field	B596	SSHS-IRM5A2-B596	3/2/2022	-	858.50	-	845.08	12 - 14 ft	13.43 ft	1801345571	Not Excavated						
Northern Athletic Field	S282	SSHS-IRM5A2-S282	3/3/2022	-	854.54	-	841.98	12 - 14 ft	12.57 ft	1801346401	Not Excavated						
Northern Athletic Field	S283	SSHS-IRM5A2-S283	3/14/2022	-	853.86	-	841.23	12 - 14 ft	12.63 ft	1801351301	Not Excavated						
Northern Athletic Field	S314A	SSHS-IRM5A2-DUP53	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354282	Not Excavated						
Northern Athletic Field	S319	SSHS-IRM5A2-S319	3/18/2022	-	854.58	-	840.56	12 - 14 ft	14.02 ft	1801354282	Not Excavated						
Northern Athletic Field	S318	SSHS-IRM5A2-S318	3/18/2022	-	853.71	-	840.88	12 - 14 ft	12.83 ft	1801354282	Not Excavated						
Northern Athletic Field	S317	SSHS-IRM5A2-S317	3/18/2022	-	853.29	-	840.60	12 - 14 ft	12.69 ft	1801354282	Not Excavated						
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354282	Not Excavated						
Northern Athletic Field	S316	SSHS-IRM5A2-S316	3/18/2022	-	853.94	-	840.56	12 - 14 ft	13.38 ft	1801354283	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	S315	SSHS-IRM5A2-S315	3/18/2022	-	854.30	-	840.58	12 - 14 ft	13.71 ft	1801354282	Not Excavated						
Northern Athletic Field	S314A	SSHS-IRM5A2-S314A	3/18/2022	-	853.95	-	840.42	12 - 14 ft	13.52 ft	1801354281	Not Excavated						
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354281	Not Excavated						
Northern Athletic Field	S314	SSHS-IRM5A2-S314	3/18/2022	-	853.73	-	840.34	12 - 14 ft	13.4 ft	1801354283	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S313	SSHS-IRM5A2-S313	3/18/2022	-	854.09	-	840.35	12 - 14 ft	13.74 ft	1801354281	Not Excavated						
Northern Athletic Field	B697	SSHS-IRM5A2-B697	3/18/2022	-	853.43	-	839.85	12 - 14 ft	13.57 ft	1801354281	Not Excavated						
Northern Athletic Field	S284	SSHS-IRM5A2-S284	3/18/2022	-	853.46	-	841.04	12 - 14 ft	12.42 ft	1801354282	Not Excavated						
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354282	Not Excavated						
Northern Athletic Field	S284A	SSHS-IRM5A2-S284A	3/18/2022	-	853.82	-	841.17	12 - 14 ft	12.66 ft	1801354283	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	S285	SSHS-IRM5A2-S285	3/18/2022	-	854.08	-	841.24	12 - 14 ft	12.84 ft	1801354282	Not Excavated						
Northern Athletic Field	S286	SSHS-IRM5A2-S286	3/18/2022	-	853.94	-	841.65	12 - 14 ft	12.28 ft	1801354282	Not Excavated						
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359741	Not Excavated						
Northern Athletic Field	S292-S1	SSHS-IRM5A2-S292-S1	3/30/2022	-	857.23	-	843.28	12 - 14 ft	13.95 ft	1801359742	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	S292-S2	SSHS-IRM5A2-S292-S2	3/30/2022	-	856.97	-	843.23	12 - 14 ft	13.74 ft	1801359741	Not Excavated						
Northern Athletic Field	S292-S3	SSHS-IRM5A2-S292-S3	3/30/2022	-	855.56	-	842.89	12 - 14 ft	12.68 ft	1801359741	Not Excavated						
Northern Athletic Field	S730	SSHS-IRM5A2-S730	4/18/2022	-	853.90	-	840.08	12 - 14 ft	13.82 ft	1801368211	Not Excavated						
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-B1	SSHS-IRM5A2-A5-V1-B1	4/25/2022	-	855.80	-	843.60	12 - 14 ft	12.2 ft	1801371273	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-12-14	6/4/2022	856.18	856.99	0.81	-	12 - 14 ft	12.81-14.81 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-12-14	6/4/2022	857.21	855.60	-1.61	-	12 - 14 ft	10.39-12.39 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-12-14	6/4/2022	856.60	856.86	0.26	-	12 - 14 ft	12.26-14.26 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-12-14	6/4/2022	856.27	856.38	0.11	-	12 - 14 ft	12.11-14.11 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-12-14	6/4/2022	856.61	857.29	0.68	-	12 - 14 ft	12.68-14.68 ft	180-139185-1	Not Excavated						
Northern Athletic Field	B1617-BOT	SSHS-IRM5A2-B1617-BOT	6/10/2022	-	857.78	-	845.10	12 - 14 ft	12.68 ft	1801395462	Not Excavated						
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395463	Not Excavated						
Northern Athletic Field	B1510-BOT2	SSHS-IRM5A2-B1510-BOT2	6/10/2022	-	857.70	-	844.65	12 - 14 ft	13.05 ft	1801395464	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	S510-BOT2	SSHS-IRM5A2-S510-BOT2	6/10/2022	-	857.75	-	844.69	12 - 14 ft	13.06 ft	1801395463	Not Excavated						
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-DUP114	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-DUP115	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-DUP113	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1252	SSHS-IRM5A2-A4-B1252	6/11/2022	-	857.87	-	844.86	12 - 14 ft	13.01 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1200	SSHS-IRM5A2-A4-S1200	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.6 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1201	SSHS-IRM5A2-A4-S1201	6/11/2022	-	857.99	-	845.08	12 - 14 ft	12.91 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1202	SSHS-IRM5A2-A4-S1202	6/11/2022	-	857.82	-	844.94	12 - 14 ft	12.88 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395782	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395783	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395783	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated	< 120 U								
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated	< 110 U								
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated	< 140 U								
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395783	Not Excavated				< 0.058 U	< 0.046 U	< 0.055 U	< 0.062 U	< 0.058 U	< 0.036 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated	< 120 U								
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated	< 130 U								
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated		< 35 U							
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated		< 34 UT							
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated		< 35 U							
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated		< 35 U							
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395973	Not Excavated				< 0.56 U	< 0.45 U	< 0.54 U	< 0.61 U	< 0.56 U	< 0.35 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated		< 32 U							
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated		< 33 U							
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396812	Not Excavated				< 0.053 U	< 0.042 U	0.19 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated		< 29 U							
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated		< 29 U							
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426152	Not Excavated				< 0.044 U	< 0.035 U	< 0.042 U	< 0.047 U	< 0.044 U	< 0.027 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated		< 32 U							
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801430091	Not Excavated				< 0.048 U	< 0.038 U	0.081 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated		< 30 U							
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430972	Not Excavated				< 0.049 U	< 0.038 U	0.058 J	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated		< 32 U							
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434602	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434602	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.032 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated		< 31 U							
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435252	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated		< 32 U							
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435252	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435252	Not Excavated				< 0.045 U	< 0.036 U	< 0.043 U	0.069 J	< 0.045 U	< 0.028 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated		< 31 U							
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572472	Not Excavated				< 0.048 U	< 0.038 U	0.087 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated	< 110 U								
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.039 J	< 0.044 U	< 0.025 U	< 0.075 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 140 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 120 U								

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395783	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395783	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395783	Not Excavated	< 0.059 U	< 0.046 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.040 U	< 0.052 U	< 0.064 U	< 0.049 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated									
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated									
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395973	Not Excavated	< 0.58 U	< 0.45 U	< 0.34 U	< 0.36 U	< 0.26 U	< 0.39 U	< 0.50 U	< 0.62 U	< 0.48 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated									
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396812	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.11 J	0.10 J	< 0.045 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated									
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426152	Not Excavated	< 0.045 U	< 0.035 U	< 0.026 U	< 0.028 U	< 0.020 U	< 0.030 U	< 0.039 U	< 0.048 U	< 0.037 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801430091	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated									
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430972	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated									
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434602	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434602	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated									
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated									
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435252	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.054 U	< 0.041 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated									
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated									
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated									
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435252	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435252	Not Excavated	< 0.046 U	< 0.036 U	< 0.027 U	< 0.029 U	< 0.021 U	< 0.031 U	0.050 J	< 0.050 U	< 0.038 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated									
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated									
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572472	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	0.069 J
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated									
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.039 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.039 U	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.043 U	< 0.036 U	< 0.038 U	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A4-S1203	SSHS-IRM5A2-A4-S1203	6/11/2022	-	857.75	-	844.72	12 - 14 ft	13.03 ft	1801395783	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A4-S1204	SSHS-IRM5A2-A4-S1204	6/11/2022	-	857.74	-	845.14	12 - 14 ft	12.61 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1205	SSHS-IRM5A2-A4-S1205	6/11/2022	-	857.71	-	845.28	12 - 14 ft	12.43 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1206	SSHS-IRM5A2-A4-S1206	6/11/2022	-	857.51	-	845.24	12 - 14 ft	12.27 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1207	SSHS-IRM5A2-A4-S1207	6/11/2022	-	857.45	-	844.93	12 - 14 ft	12.52 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-S1208	SSHS-IRM5A2-A4-S1208	6/11/2022	-	857.68	-	845.59	12 - 14 ft	12.09 ft	1801395783	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A4-S1209	SSHS-IRM5A2-A4-S1209	6/11/2022	-	857.76	-	845.65	12 - 14 ft	12.12 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1250	SSHS-IRM5A2-A4-B1250	6/11/2022	-	857.71	-	844.58	12 - 14 ft	13.13 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1251	SSHS-IRM5A2-A4-B1251	6/11/2022	-	857.83	-	844.74	12 - 14 ft	13.1 ft	1801395783	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.028 U
Northern Athletic Field	A4-B1253	SSHS-IRM5A2-A4-B1253	6/11/2022	-	857.75	-	844.67	12 - 14 ft	13.07 ft	1801395782	Not Excavated						
Northern Athletic Field	A4-B1254	SSHS-IRM5A2-A4-B1254	6/11/2022	-	857.51	-	844.20	12 - 14 ft	13.31 ft	1801395782	Not Excavated						
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-DUP116	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S12	SSHS-IRM5A2-FISR-S12	6/13/2022	-	854.72	-	842.61	12 - 14 ft	12.11 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-BOT6	SSHS-IRM5A2-FISR-BOT6	6/13/2022	-	854.74	-	842.46	12 - 14 ft	12.28 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-BOT7	SSHS-IRM5A2-FISR-BOT7	6/13/2022	-	855.12	-	842.90	12 - 14 ft	12.21 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-BOT8	SSHS-IRM5A2-FISR-BOT8	6/13/2022	-	855.13	-	843.00	12 - 14 ft	12.13 ft	1801395973	Not Excavated	< 0.43 U	< 0.25 U	< 0.49 U	< 0.41 U	< 0.32 U	< 0.27 U
Northern Athletic Field	FISR-BOT9	SSHS-IRM5A2-FISR-BOT9	6/13/2022	-	855.17	-	843.01	12 - 14 ft	12.16 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396811	Not Excavated						
Northern Athletic Field	FISR-BOT10	SSHS-IRM5A2-FISR-BOT10	6/14/2022	-	855.17	-	842.98	12 - 14 ft	12.19 ft	1801396812	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-12-14	6/20/2022	856.38	856.44	0.06	-	12 - 14 ft	12.06-14.06 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-12-14	6/20/2022	856.66	856.67	0.01	-	12 - 14 ft	12.01-14.01 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-12-14	6/20/2022	856.60	856.56	-0.04	-	12 - 14 ft	11.96-13.96 ft	180-140136-1	Not Excavated						
Northern Athletic Field	FL-S1200	SSHS-IRM5A2-FL-S1200	8/8/2022	-	856.37	-	843.95	12 - 14 ft	12.42 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1201	SSHS-IRM5A2-FL-S1201	8/8/2022	-	856.32	-	844.16	12 - 14 ft	12.16 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1206	SSHS-IRM5A2-FL-S1206	8/8/2022	-	856.36	-	844.12	12 - 14 ft	12.24 ft	1801426152	Not Excavated	< 0.034 U	< 0.019 U	< 0.038 U	< 0.032 U	0.049 J	< 0.021 U
Northern Athletic Field	FISR-S95	SSHS-IRM5A2-FISR-S95	8/13/2022	-	855.21	-	843.05	12 - 14 ft	12.16 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S99	SSHS-IRM5A2-FISR-S99	8/13/2022	-	855.07	-	842.87	12 - 14 ft	12.21 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-BOT19	SSHS-IRM5A2-FISR-BOT19	8/13/2022	-	855.14	-	842.89	12 - 14 ft	12.26 ft	1801430091	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FISR-S86	SSHS-IRM5A2-FISR-S86	8/18/2022	-	855.15	-	842.96	12 - 14 ft	12.18 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430971	Not Excavated						
Northern Athletic Field	FISR-S90	SSHS-IRM5A2-FISR-S90	8/18/2022	-	854.97	-	842.57	12 - 14 ft	12.41 ft	1801430972	Not Excavated	< 0.037 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FISR-BOT18	SSHS-IRM5A2-FISR-BOT18	8/18/2022	-	855.07	-	843.05	12 - 14 ft	12.02 ft	1801430971	Not Excavated						
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-DUP206	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434602	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1201	SSHS-IRM5A2-ST-S1201	8/24/2022	-	856.59	-	844.00	12 - 14 ft	12.58 ft	1801434602	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-DUP210	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated						
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435251	Not Excavated						
Northern Athletic Field	FL-S1400	SSHS-IRM5A2-FL-S1400	8/25/2022	-	855.91	-	842.93	12 - 14 ft	12.97 ft	1801435252	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S1401	SSHS-IRM5A2-FL-S1401	8/25/2022	-	856.11	-	842.49	12 - 14 ft	13.62 ft	1801435251	Not Excavated						
Northern Athletic Field	FL-S1402	SSHS-IRM5A2-FL-S1402	8/25/2022	-	856.31	-	842.35	12 - 14 ft	13.96 ft	1801435251	Not Excavated						
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435251	Not Excavated						
Northern Athletic Field	FL-S1403	SSHS-IRM5A2-FL-S1403	8/25/2022	-	856.13	-	842.64	12 - 14 ft	13.5 ft	1801435252	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B1400	SSHS-IRM5A2-FL-B1400	8/25/2022	-	856.10	-	842.28	12 - 14 ft	13.83 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1203	SSHS-IRM5A2-ST-S1203	8/25/2022	-	856.68	-	844.52	12 - 14 ft	12.16 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1204	SSHS-IRM5A2-ST-S1204	8/25/2022	-	856.72	-	844.58	12 - 14 ft	12.15 ft	1801435252	Not Excavated	< 0.035 U	< 0.020 U	< 0.039 U	< 0.033 U	< 0.025 U	< 0.022 U
Northern Athletic Field	ST-S1402	SSHS-IRM5A2-ST-S1402	8/25/2022	-	856.38	-	842.42	12 - 14 ft	13.96 ft	1801435261	Not Excavated						
Northern Athletic Field	ST-S1405	SSHS-IRM5A2-ST-S1405	8/25/2022	-	856.25	-	843.25	12 - 14 ft	12.99 ft	1801435261	Not Excavated						
Northern Athletic Field	NAF-IG-S8	SSHS-ISMP-NAF-IG-S8	5/30/2023	-	853.73	-	841.24	12 - 14 ft	12.49 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S9	SSHS-ISMP-NAF-IG-S9	5/30/2023	-	854.49	-	841.73	12 - 14 ft	12.76 ft	1801572472	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-IG-S16	SSHS-ISMP-NAF-IG-S16	6/1/2023	-	853.44	-	841.19	12 - 14 ft	12.24 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S34	SSHS-ISMP-NAF-IG-S34	6/2/2023	-	853.69	-	841.05	12 - 14 ft	12.64 ft	1801574521	Not Excavated						
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-14-16	5/6/2021	856.75	856.65	-0.10	-	14 - 16 ft	13.9-15.9 ft	1801213101	Not Excavated	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.067 U	< 0.063 U	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	1801215451	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.080 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.046 J	< 0.046 U	< 0.026 U	< 0.078 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 110 U			< 0.36 U	< 0.025 U	< 0.028 U	< 0.038 U	< 0.022 U	< 0.066 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated				< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated			< 130 U						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated			< 34 U						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S279	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S276	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S278	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S275	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated	< 110 U								
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334582	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated	< 110 U								
Northern Athletic Field	S281	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated	< 110 U								
Northern Athletic Field	S280	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated	< 120 U								
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 110 U								
Northern Athletic Field	S296	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated	< 110 U								
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated	< 110 U								
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345572	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated	< 110 U								
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated	< 120 U								
Northern Athletic Field	B711	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	B712	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	B707	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	S321	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated	< 120 U								
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354283	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354283	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	B704	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354283	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354283	Not Excavated				< 0.053 U	< 0.042 U	0.12 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	B698	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	B701	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated	< 120 U								
Northern Athletic Field	S312	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated	< 110 U								
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 110 U								
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated	< 110 U								
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated	< 110 U								
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 110 U								
Northern Athletic Field	S731	SSHS-IRM55A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368212	Not Excavated				< 0.047 U	< 0.037 U	0.86	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated	< 110 U								
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368212	Not Excavated				< 0.050 U	< 0.040 U	0.44	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated	< 110 U								
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated			< 110 U						

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated									
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.037 U	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.080 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	1801215451	Not Excavated	< 0.042 U	< 0.034 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.042 U	< 0.035 U	< 0.037 U	0.055 J	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.041 U	< 0.034 U	< 0.036 U	0.10 J	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	0.15 J
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.039 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.034 U	< 0.029 U	< 0.031 U	< 0.041 U	< 0.035 U	< 0.081 U	0.36 J	< 0.085 U	< 0.076 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.035 U	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.035 U	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.039 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.037 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated									
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated									
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated									
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated									
Northern Athletic Field	S279	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated									
Northern Athletic Field	S276	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated									
Northern Athletic Field	S278	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated									
Northern Athletic Field	S275	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated									
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated									
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334582	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated									
Northern Athletic Field	S281	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated									
Northern Athletic Field	S280	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated									
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated									
Northern Athletic Field	S296	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated									
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated									
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345572	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated									
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated									
Northern Athletic Field	B711	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated									
Northern Athletic Field	B712	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated									
Northern Athletic Field	B707	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated									
Northern Athletic Field	S321	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated									
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated									
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354283	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated									
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354283	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated									
Northern Athletic Field	B704	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated									
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated									
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354283	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated									
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated									
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354283	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	0.14 J
Northern Athletic Field	B699	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated									
Northern Athletic Field	B698	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated									
Northern Athletic Field	B701	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated									
Northern Athletic Field	S312	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated									
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated									
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated									
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated									
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated									
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368212	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	0.46
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated									
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368212	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.055 U	0.32
Northern Athletic Field	S732	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated									
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-14-16	5/11/2021	856.50	855.82	-0.68	-	14 - 16 ft	13.32-15.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	1801215481	Not Excavated	< 0.064 U	< 0.061 U	< 0.043 U	< 0.30 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.065 U	< 0.061 U	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-14-16	5/13/2021	856.89	856.55	-0.34	-	14 - 16 ft	13.66-15.66 ft	1801217041	Not Excavated	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-14-16	5/14/2021	857.50	857.17	-0.33	-	14 - 16 ft	13.67-15.67 ft	1801217051	Not Excavated	< 0.053 U	< 0.050 U	< 0.035 U	< 0.25 U	0.25 J	< 0.38 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.055 U	< 0.052 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.054 U	< 0.051 U	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-14-16	5/18/2021	855.95	855.66	-0.29	-	14 - 16 ft	13.71-15.71 ft	1801218221	Not Excavated	< 0.059 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.057 U	< 0.054 U	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-14-16	9/17/2021	857.91	857.91	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-14-16	9/22/2021	856.72	856.72	0.00	-	14 - 16 ft	14-16 ft	180-127415-1	Not Excavated						
Northern Athletic Field	S278	SSHS-IRM5A2-DUP38	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated						
Northern Athletic Field	S279	SSHS-IRM5A2-S279	2/8/2022	-	856.64	-	841.49	14 - 16 ft	15.15 ft	1801333441	Not Excavated						
Northern Athletic Field	S276	SSHS-IRM5A2-S276	2/8/2022	-	857.53	-	842.55	14 - 16 ft	14.98 ft	1801333441	Not Excavated						
Northern Athletic Field	S278	SSHS-IRM5A2-S278	2/8/2022	-	856.61	-	841.57	14 - 16 ft	15.03 ft	1801333441	Not Excavated						
Northern Athletic Field	S275	SSHS-IRM5A2-S275	2/8/2022	-	857.32	-	842.26	14 - 16 ft	15.06 ft	1801333441	Not Excavated						
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334581	Not Excavated						
Northern Athletic Field	S273	SSHS-IRM5A2-S273	2/9/2022	-	857.87	-	842.85	14 - 16 ft	15.02 ft	1801334582	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S274	SSHS-IRM5A2-S274	2/9/2022	-	857.85	-	842.97	14 - 16 ft	14.88 ft	1801334581	Not Excavated						
Northern Athletic Field	S281	SSHS-IRM5A2-S281	2/9/2022	-	856.12	-	841.90	14 - 16 ft	14.22 ft	1801334581	Not Excavated						
Northern Athletic Field	S280	SSHS-IRM5A2-S280	2/9/2022	-	857.04	-	841.52	14 - 16 ft	15.52 ft	1801334581	Not Excavated						
Northern Athletic Field	S294	SSHS-IRM5A2-DUP47	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated						
Northern Athletic Field	S296	SSHS-IRM5A2-S296	3/2/2022	-	857.91	-	842.98	14 - 16 ft	14.93 ft	1801345571	Not Excavated						
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345571	Not Excavated						
Northern Athletic Field	S295	SSHS-IRM5A2-S295	3/2/2022	-	858.17	-	843.52	14 - 16 ft	14.65 ft	1801345572	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S294	SSHS-IRM5A2-S294	3/2/2022	-	857.62	-	843.20	14 - 16 ft	14.42 ft	1801345571	Not Excavated						
Northern Athletic Field	B704	SSHS-IRM5A2-DUP52	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354282	Not Excavated						
Northern Athletic Field	B711	SSHS-IRM5A2-B711	3/18/2022	-	854.34	-	840.17	14 - 16 ft	14.17 ft	1801354281	Not Excavated						
Northern Athletic Field	B712	SSHS-IRM5A2-B712	3/18/2022	-	854.99	-	839.91	14 - 16 ft	15.09 ft	1801354281	Not Excavated						
Northern Athletic Field	B707	SSHS-IRM5A2-B707	3/18/2022	-	854.73	-	840.16	14 - 16 ft	14.57 ft	1801354281	Not Excavated						
Northern Athletic Field	S321	SSHS-IRM5A2-S321	3/18/2022	-	856.56	-	840.85	14 - 16 ft	15.71 ft	1801354282	Not Excavated						
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354282	Not Excavated						
Northern Athletic Field	S320	SSHS-IRM5A2-S320	3/18/2022	-	855.32	-	840.95	14 - 16 ft	14.37 ft	1801354283	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354281	Not Excavated						
Northern Athletic Field	B706	SSHS-IRM5A2-B706	3/18/2022	-	855.62	-	840.17	14 - 16 ft	15.45 ft	1801354283	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	B705	SSHS-IRM5A2-B705	3/18/2022	-	856.20	-	840.28	14 - 16 ft	15.92 ft	1801354281	Not Excavated						
Northern Athletic Field	B704	SSHS-IRM5A2-B704	3/18/2022	-	855.19	-	840.02	14 - 16 ft	15.17 ft	1801354281	Not Excavated						
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354281	Not Excavated						
Northern Athletic Field	B703	SSHS-IRM5A2-B703	3/18/2022	-	855.33	-	840.10	14 - 16 ft	15.22 ft	1801354283	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	B702	SSHS-IRM5A2-B702	3/18/2022	-	855.03	-	840.08	14 - 16 ft	14.95 ft	1801354281	Not Excavated						
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354281	Not Excavated						
Northern Athletic Field	B700	SSHS-IRM5A2-B700	3/18/2022	-	854.39	-	839.71	14 - 16 ft	14.67 ft	1801354283	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	B699	SSHS-IRM5A2-B699	3/18/2022	-	854.69	-	839.64	14 - 16 ft	15.04 ft	1801354281	Not Excavated						
Northern Athletic Field	B698	SSHS-IRM5A2-B698	3/18/2022	-	854.60	-	839.96	14 - 16 ft	14.64 ft	1801354281	Not Excavated						
Northern Athletic Field	B701	SSHS-IRM5A2-B701	3/18/2022	-	854.47	-	839.80	14 - 16 ft	14.67 ft	1801354281	Not Excavated						
Northern Athletic Field	S312	SSHS-IRM5A2-S312	3/18/2022	-	854.98	-	840.54	14 - 16 ft	14.44 ft	1801354281	Not Excavated						
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-DUP59	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated						
Northern Athletic Field	S292-BOT1	SSHS-IRM5A2-S292-BOT1	3/30/2022	-	857.00	-	842.62	14 - 16 ft	14.38 ft	1801359741	Not Excavated						
Northern Athletic Field	S315A	SSHS-IRM5A2-S315A	4/5/2022	-	854.34	-	840.25	14 - 16 ft	14.09 ft	1801362281	Not Excavated						
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated						
Northern Athletic Field	S731	SSHS-IRM5A2-DUP61	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368212	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368211	Not Excavated						
Northern Athletic Field	S731	SSHS-IRM5A2-S731	4/18/2022	-	854.62	-	840.26	14 - 16 ft	14.36 ft	1801368212	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S732	SSHS-IRM5A2-S732	4/18/2022	-	855.34	-	840.39	14 - 16 ft	14.95 ft	1801368211	Not Excavated						
Northern Athletic Field	SSHS-DW-10 11	SSHS-DW-10 11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-13 14	SSHS-DW-13 14-SUB-14-16	6/4/2022	857.21	855.60	-1.61	-	14 - 16 ft	12.39-14.39 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435262	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated		< 32 U							
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572472	Not Excavated				< 0.049 U	< 0.039 U	0.064 J	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573812	Not Excavated				< 0.049 U	< 0.039 U	0.068 J	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574522	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated	< 120 U								
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.072 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated			< 130 U						
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated			< 630 U						
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated			< 230 U						
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated			< 130 U						
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated			< 360 U						
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated			< 130 U						
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated			< 120 U						

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated									
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated									
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated									
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435262	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated									
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated									
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572472	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.066 J	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	0.16 J
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573812	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	0.053 J	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	0.077 J
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574522	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated									
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.036 U	< 0.030 U	< 0.032 U	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.038 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.083 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.037 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated									
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated									
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated									
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated									
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated									
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated									
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated									
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated									
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated									
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated									
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated									
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated									
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated									
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated									
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated									
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated									
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated									
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated									
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated									
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated									
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated									
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated									
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated									
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated									
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated									
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated									
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-14-16	6/20/2022	856.60	856.56	-0.04	-	14 - 16 ft	13.96-15.96 ft	180-140136-1	Not Excavated						
Northern Athletic Field	ST-S1400	SSHS-IRM5A2-ST-S1400	8/24/2022	-	856.34	-	842.09	14 - 16 ft	14.25 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1401	SSHS-IRM5A2-ST-S1401	8/24/2022	-	856.53	-	842.50	14 - 16 ft	14.03 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1403	SSHS-IRM5A2-ST-S1403	8/25/2022	-	856.79	-	842.50	14 - 16 ft	14.29 ft	1801435261	Not Excavated						
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435261	Not Excavated						
Northern Athletic Field	ST-S1404	SSHS-IRM5A2-ST-S1404	8/25/2022	-	856.51	-	842.45	14 - 16 ft	14.06 ft	1801435262	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	ST-S1601	SSHS-IRM5A2-ST-S1601	8/25/2022	-	856.53	-	841.07	14 - 16 ft	15.46 ft	1801435261	Not Excavated						
Northern Athletic Field	ST-S1604	SSHS-IRM5A2-ST-S1604	8/25/2022	-	856.35	-	840.82	14 - 16 ft	15.53 ft	1801435261	Not Excavated						
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-DUP4A	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S10	SSHS-ISMP-NAF-IG-S10	5/30/2023	-	853.73	-	839.34	14 - 16 ft	14.38 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S11	SSHS-ISMP-NAF-IG-S11	5/30/2023	-	854.58	-	839.70	14 - 16 ft	14.87 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S12	SSHS-ISMP-NAF-IG-S12	5/30/2023	-	854.22	-	839.09	14 - 16 ft	15.13 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S13	SSHS-ISMP-NAF-IG-S13	5/30/2023	-	853.92	-	839.09	14 - 16 ft	14.83 ft	1801572472	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-IG-B1	SSHS-ISMP-NAF-IG-B1	5/30/2023	-	854.15	-	838.88	14 - 16 ft	15.27 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S17	SSHS-ISMP-NAF-IG-S17	6/1/2023	-	853.67	-	839.37	14 - 16 ft	14.3 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S18	SSHS-ISMP-NAF-IG-S18	6/1/2023	-	853.79	-	839.19	14 - 16 ft	14.59 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S22	SSHS-ISMP-NAF-IG-S22	6/1/2023	-	853.53	-	839.17	14 - 16 ft	14.36 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S23	SSHS-ISMP-NAF-IG-S23	6/1/2023	-	853.52	-	838.97	14 - 16 ft	14.56 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-B2	SSHS-ISMP-NAF-IG-B2	6/1/2023	-	853.64	-	838.71	14 - 16 ft	14.94 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-B3	SSHS-ISMP-NAF-IG-B3	6/1/2023	-	854.03	-	838.72	14 - 16 ft	15.31 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S25	SSHS-ISMP-NAF-IG-S25	6/1/2023	-	854.29	-	839.16	14 - 16 ft	15.13 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S29	SSHS-ISMP-NAF-IG-S29	6/1/2023	-	853.89	-	839.46	14 - 16 ft	14.43 ft	1801573812	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-IG-S30	SSHS-ISMP-NAF-IG-S30	6/1/2023	-	853.96	-	839.05	14 - 16 ft	14.91 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-DUP7A	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-S35	SSHS-ISMP-NAF-IG-S35	6/2/2023	-	853.82	-	839.54	14 - 16 ft	14.28 ft	1801574522	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-IG-S36	SSHS-ISMP-NAF-IG-S36	6/2/2023	-	854.36	-	839.26	14 - 16 ft	15.11 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-S37	SSHS-ISMP-NAF-IG-S37	6/2/2023	-	854.58	-	839.10	14 - 16 ft	15.48 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-B4	SSHS-ISMP-NAF-IG-B4	6/2/2023	-	854.13	-	838.48	14 - 16 ft	15.64 ft	1801574521	Not Excavated						
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.058 U	< 0.054 U	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated						
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated						
Northern Athletic Field	SSHS-B3330	SSHS-B3330-SUB-2-4	12/16/2019	851.73	852.70	0.97	-	2 - 4 ft	2.97-4.97 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3331	SSHS-B3331-SUB-2-4	12/16/2019	852.38	854.95	2.57	-	2 - 4 ft	4.57-6.57 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3284	SSHS-B3284-SUB-2-4	12/17/2019	855.54	854.58	-0.96	-	2 - 4 ft	1.04-3.04 ft	180-100148-5	Not Excavated						
Northern Athletic Field	SSHS-B3288	SSHS-B3288-SUB-2-4	12/17/2019	856.90	856.50	-0.40	-	2 - 4 ft	1.6-3.6 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3308	SSHS-B3308-SUB-2-4	12/17/2019	855.68	855.91	0.23	-	2 - 4 ft	2.23-4.23 ft	180-100148-4	Not Excavated						
Northern Athletic Field	SSHS-B3315	SSHS-B3315-SUB-2-4	12/17/2019	856.43	856.96	0.53	-	2 - 4 ft	2.53-4.53 ft	180-100148-6	Not Excavated						
Northern Athletic Field	SSHS-B3272	SSHS-B3272-SUB-2-4	12/18/2019	856.00	857.99	1.99	-	2 - 4 ft	3.99-5.99 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3275	SSHS-B3275-SUB-2-4	12/18/2019	856.25	856.90	0.65	-	2 - 4 ft	2.65-4.65 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3281	SSHS-B3281-SUB-2-4	12/18/2019	856.88	856.81	-0.07	-	2 - 4 ft	1.93-3.93 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3283	SSHS-B3283-SUB-2-4	12/18/2019	856.35	856.53	0.18	-	2 - 4 ft	2.18-4.18 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3250	SSHS-B3250-SUB-2-4	12/19/2019	858.02	858.03	0.01	-	2 - 4 ft	2.01-4.01 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3252	SSHS-B3252-SUB-2-4	12/19/2019	857.46	857.80	0.34	-	2 - 4 ft	2.34-4.34 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3253	SSHS-B3253-SUB-2-4	12/19/2019	858.40	858.37	-0.03	-	2 - 4 ft	1.97-3.97 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3255	SSHS-B3255-SUB-2-4	12/19/2019	857.06	857.52	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3257	SSHS-B3257-SUB-2-4	12/19/2019	858.41	858.46	0.05	-	2 - 4 ft	2.05-4.05 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3259	SSHS-B3259-SUB-2-4	12/19/2019	857.33	857.76	0.43	-	2 - 4 ft	2.43-4.43 ft	180-100363-2	Not Excavated						
Northern Athletic Field	SSHS-B3260	SSHS-B3260-SUB-2-4	12/19/2019	858.57	858.48	-0.09	-	2 - 4 ft	1.91-3.91 ft	180-100363-1	Not Excavated						
Northern Athletic Field	SSHS-B3225	SSHS-B3225-SUB-2-4	12/20/2019	853.42	854.03	0.61	-	2 - 4 ft	2.61-4.61 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3226	SSHS-B3226-SUB-2-4	12/20/2019	853.22	853.68	0.46	-	2 - 4 ft	2.46-4.46 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3228	SSHS-B3228-SUB-2-4	12/20/2019	853.57	853.82	0.25	-	2 - 4 ft	2.25-4.25 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-2-4	12/20/2019	855.71	855.63	-0.08	-	2 - 4 ft	1.92-3.92 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3227	SSHS-B3227-SUB-2-4	1/24/2020	853.19	853.36	0.17	-	2 - 4 ft	2.17-4.17 ft	180-101497-4	Not Excavated						
Northern Athletic Field	SSHS-B3517	SSHS-B3517-SUB-2-4	1/14/2021	858.50	858.30	-0.20	-	2 - 4 ft	1.8-3.8 ft	180-116002-1	Not Excavated						
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-2-4	1/23/2021	856.72	856.88	0.16	-	2 - 4 ft	2.16-4.16 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-2-4	1/23/2021	856.06	857.63	1.57	-	2 - 4 ft	3.57-5.57 ft	180-116404-1	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated			< 100 U						
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 130 U			< 0.43 U	< 0.029 U	0.13 BJ	< 0.046 U	< 0.026 U	< 0.078 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated			< 470 U						
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated	< 120 U								
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 110 U			< 0.41 U	< 0.027 U	0.23 B	< 0.043 U	< 0.024 U	< 0.073 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated			< 630 U						
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated			< 120 U	< 0.42 U	< 0.028 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated			< 130 U	< 0.49 U	< 0.033 U	< 0.037 UJ	< 0.051 U	< 0.029 U	< 0.088 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	0.19 BJ	< 0.042 U	< 0.024 U	< 0.072 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.38 B	< 0.045 U	< 0.026 U	< 0.078 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.088 J	< 0.043 U	< 0.024 U	< 0.073 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated			< 110 U	< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.03 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	B757	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated	< 140 U								
Northern Athletic Field	B747	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated	< 120 U								
Northern Athletic Field	B758	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated	< 120 U								
Northern Athletic Field	B797	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated	< 120 U								
Northern Athletic Field	S435	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated	< 120 U								
Northern Athletic Field	S429	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated	< 130 U								
Northern Athletic Field	S516	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated	< 110 U								
Northern Athletic Field	S520	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated	< 120 U								
Northern Athletic Field	S521	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated	< 130 U								
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated	< 390 U								
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 130 U								
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated	< 120 U								
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated	< 120 U								
Northern Athletic Field	B737	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated	< 130 U								
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated	< 130 U								
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated	< 120 U								
Northern Athletic Field	B739	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated	< 120 U								
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated	< 120 U								
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated	< 120 U								
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated	< 120 U								
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated	< 120 U								
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated	< 120 U								
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated	< 410 U								
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329512	Not Excavated				< 0.17 U	< 0.14 U	0.85 B	< 0.19 U	< 0.17 U	< 0.11 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated	< 110 U								
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330902	Not Excavated				< 0.051 U	< 0.040 U	0.086 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332632	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated	< 130 U								
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated									
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated									
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.041 U	0.039 J	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	< 0.090 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated									
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.038 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.090 U	0.58 BT	< 0.094 U	< 0.084 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.04 U	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.093 U	0.29 J	< 0.098 U	< 0.088 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.046 U	< 0.038 U	< 0.041 U	< 0.055 U	< 0.047 U	< 0.11 U	0.98	0.16 J	< 0.1 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.038 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	1.1 BT	< 0.092 U	< 0.083 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.041 U	0.042 J	0.038 J	< 0.049 U	0.042 J	< 0.096 U	0.95 BT	0.12 J	< 0.090 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.038 U	< 0.032 U	< 0.034 U	0.089 J	< 0.039 U	< 0.089 U	0.26 J	0.11 J	< 0.084 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.096 J	< 0.022 U	< 0.033 U	0.079 J	< 0.053 U	0.08 J
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated									
Northern Athletic Field	B757	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated									
Northern Athletic Field	B747	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated									
Northern Athletic Field	B758	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated									
Northern Athletic Field	B797	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated									
Northern Athletic Field	S435	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated									
Northern Athletic Field	S429	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated									
Northern Athletic Field	S516	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated									
Northern Athletic Field	S520	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated									
Northern Athletic Field	S521	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated									
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated									
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated									
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated									
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated									
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated									
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated									
Northern Athletic Field	B737	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated									
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated									
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated									
Northern Athletic Field	B739	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated									
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated									
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated									
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated									
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated									
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated									
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated									
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated									
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated									
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329512	Not Excavated	< 0.18 U	< 0.14 U	< 0.10 U	< 0.11 U	0.12 J	< 0.12 U	< 1.0 U	0.34 J	0.18 J
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated									
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated									
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330902	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	0.038 J	< 0.035 U	0.23	0.11 J	< 0.044 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332632	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.051 J	< 0.056 U	< 0.044 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-2-4	1/23/2021	856.76	856.63	-0.13	-	2 - 4 ft	1.87-3.87 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-2-4	1/25/2021	856.35	856.68	0.33	-	2 - 4 ft	2.33-4.33 ft	180-116404-1	Not Excavated						
Northern Athletic Field	SSHS-B3613	SSHS-B3613-SUB-2-4	1/25/2021	856.82	857.09	0.27	-	2 - 4 ft	2.27-4.27 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3615	SSHS-B3615-SUB-2-4	1/25/2021	857.88	857.61	-0.27	-	2 - 4 ft	1.73-3.73 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3616	SSHS-B3616-SUB-2-4	1/25/2021	858.03	857.85	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3620	SSHS-B3620-SUB-2-4	1/25/2021	856.26	856.45	0.19	-	2 - 4 ft	2.19-4.19 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-2-4	1/25/2021	853.34	853.48	0.14	-	2 - 4 ft	2.14-4.14 ft	1801164042	Not Excavated	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-2-4	1/26/2021	857.46	857.78	0.32	-	2 - 4 ft	2.32-4.32 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-2-4	1/26/2021	858.35	858.41	0.06	-	2 - 4 ft	2.06-4.06 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3481A	DUP-9	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164621	Not Excavated						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-2-4	1/26/2021	858.11	858.22	0.11	-	2 - 4 ft	2.11-4.11 ft	1801164622	Not Excavated	< 0.059 U	< 0.056 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-2-4	1/26/2021	858.42	858.49	0.07	-	2 - 4 ft	2.07-4.07 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-2-4	1/26/2021	858.46	858.46	0.00	-	2 - 4 ft	2-4 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3494	SSHS-B3494-SUB-2-4	1/26/2021	858.31	858.13	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-4	Not Excavated	< 0.062 U	< 0.058 U	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-2-4	1/26/2021	858.30	858.61	0.31	-	2 - 4 ft	2.31-4.31 ft	180-116462-4	Not Excavated	< 0.071 U	< 0.067 U	< 0.047 U	< 0.33 U	< 0.2 U	< 0.51 U
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-2-4	1/26/2021	858.46	858.50	0.04	-	2 - 4 ft	2.04-4.04 ft	1801164622	Not Excavated	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-2-4	1/26/2021	858.39	858.21	-0.18	-	2 - 4 ft	1.82-3.82 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-2-4	1/26/2021	858.31	858.56	0.25	-	2 - 4 ft	2.25-4.25 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-2-4	1/26/2021	858.38	858.34	-0.04	-	2 - 4 ft	1.96-3.96 ft	1801164622	Not Excavated	< 0.063 U	< 0.059 U	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-2-4	7/1/2021	856.80	856.80	0.00	-	2 - 4 ft	2 - 4 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-2-4	7/1/2021	857.47	857.20	-0.27	-	2 - 4 ft	1.73-3.73 ft	1801239851	Not Excavated	< 0.059 U	< 0.056 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B4019	SSHS-B4019-SUB-2-4	7/1/2021	856.76	856.40	-0.36	-	2 - 4 ft	1.64-3.64 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-2-4	9/17/2021	857.91	857.91	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-2-4	9/22/2021	856.72	856.72	0.00	-	2 - 4 ft	2-4 ft	180-127415-1	Not Excavated						
Northern Athletic Field	B757	SSHS-IRM5A2-B757	10/24/2021	-	858.16	-	855.77	2 - 4 ft	2.39 ft	1801289732	Not Excavated						
Northern Athletic Field	B747	SSHS-IRM5A2-B747	10/24/2021	-	858.10	-	855.54	2 - 4 ft	2.56 ft	1801289732	Not Excavated						
Northern Athletic Field	B758	SSHS-IRM5A2-B758	10/24/2021	-	858.10	-	855.49	2 - 4 ft	2.61 ft	1801289732	Not Excavated						
Northern Athletic Field	B797	SSHS-IRM5A2-B797	10/27/2021	-	855.53	-	853.07	2 - 4 ft	2.46 ft	1801291082	Not Excavated						
Northern Athletic Field	S435	SSHS-IRM5A2-S435	10/28/2021	-	855.66	-	852.28	2 - 4 ft	3.38 ft	1801292043	Not Excavated						
Northern Athletic Field	S429	SSHS-IRM5A2-S429	11/3/2021	-	858.06	-	854.47	2 - 4 ft	3.59 ft	1801294631	Not Excavated						
Northern Athletic Field	S516	SSHS-IRM5A2-S516	11/5/2021	-	858.10	-	854.76	2 - 4 ft	3.35 ft	1801296371	Not Excavated						
Northern Athletic Field	S520	SSHS-IRM5A2-S520	11/5/2021	-	858.55	-	854.92	2 - 4 ft	3.63 ft	1801296371	Not Excavated						
Northern Athletic Field	S521	SSHS-IRM5A2-S521	11/5/2021	-	858.31	-	855.00	2 - 4 ft	3.31 ft	1801296371	Not Excavated						
Northern Athletic Field	DW1-S1	SSHS-IRM5A2-DW1-S1	11/8/2021	-	856.86	-	852.99	2 - 4 ft	3.87 ft	1801296791	Not Excavated						
Northern Athletic Field	DW2-S1	SSHS-IRM5A2-DW2-S1	11/8/2021	-	857.15	-	853.35	2 - 4 ft	3.81 ft	1801296791	Not Excavated						
Northern Athletic Field	S886B	SSHS-IRM5A2-S886B	11/9/2021	-	858.48	-	856.44	2 - 4 ft	2.03 ft	1801297441	Not Excavated						
Northern Athletic Field	B737	SSHS-IRM5A2-DUP18	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated						
Northern Athletic Field	B748A	SSHS-IRM5A2-B748A	12/1/2021	-	857.92	-	854.91	2 - 4 ft	3.01 ft	1801305751	Not Excavated						
Northern Athletic Field	B749A	SSHS-IRM5A2-B749A	12/1/2021	-	857.69	-	854.36	2 - 4 ft	3.34 ft	1801305751	Not Excavated						
Northern Athletic Field	B737	SSHS-IRM5A2-B737	12/1/2021	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801305751	Not Excavated						
Northern Athletic Field	AS-BOT1	SSHS-IRM5A2-AS-BOT1	12/1/2021	-	857.02	-	853.44	2 - 4 ft	3.57 ft	1801305751	Not Excavated						
Northern Athletic Field	S899-BOT1	SSHS-IRM5A2-S899-BOT1	12/4/2021	-	856.27	-	853.85	2 - 4 ft	2.42 ft	1801307631	Not Excavated						
Northern Athletic Field	B739	SSHS-IRM5A2-B739	12/4/2021	-	857.28	-	854.34	2 - 4 ft	2.94 ft	1801307631	Not Excavated						
Northern Athletic Field	B752-A1	SSHS-IRM5A2-B752	12/4/2021	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801307631	Not Excavated						
Northern Athletic Field	S929A-BOT	SSHS-IRM5A2-S929A-BOT	12/10/2021	-	852.44	-	849.66	2 - 4 ft	2.79 ft	1801311081	Not Excavated						
Northern Athletic Field	S928A-BOT	SSHS-IRM5A2-S928A-BOT	12/17/2021	-	852.30	-	849.48	2 - 4 ft	2.82 ft	1801315141	Not Excavated						
Northern Athletic Field	S927A-BOT	SSHS-IRM5A2-S927A-BOT	12/17/2021	-	852.63	-	849.43	2 - 4 ft	3.21 ft	1801315141	Not Excavated						
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-DUP30	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated						
Northern Athletic Field	RS-BOT18	SSHS-IRM5A2-RS-BOT18	1/31/2022	-	853.34	-	849.67	2 - 4 ft	3.67 ft	1801329511	Not Excavated						
Northern Athletic Field	RS-S43	SSHS-IRM5A2-RS-S43	1/31/2022	-	854.59	-	852.58	2 - 4 ft	2.01 ft	1801329511	Not Excavated						
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329511	Not Excavated						
Northern Athletic Field	RS-BOT25	SSHS-IRM5A2-RS-BOT25	1/31/2022	-	854.18	-	850.88	2 - 4 ft	3.31 ft	1801329512	Not Excavated	< 0.13 U	< 0.076 U	< 0.15 U	< 0.13 U	< 0.098 U	< 0.083 U
Northern Athletic Field	RS-BOT26	SSHS-IRM5A2-RS-BOT26	1/31/2022	-	854.37	-	851.60	2 - 4 ft	2.77 ft	1801329511	Not Excavated						
Northern Athletic Field	RS-BOT27	SSHS-IRM5A2-RS-BOT27	1/31/2022	-	854.33	-	851.17	2 - 4 ft	3.16 ft	1801329511	Not Excavated						
Northern Athletic Field	RS-S54	SSHS-IRM5A2-RS-S54	2/2/2022	-	853.02	-	849.21	2 - 4 ft	3.81 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT39	SSHS-IRM5A2-RS-BOT39	2/2/2022	-	854.23	-	850.94	2 - 4 ft	3.29 ft	1801330902	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-DUP37	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-BOT41	SSHS-IRM5A2-RS-BOT41	2/7/2022	-	854.22	-	850.83	2 - 4 ft	3.39 ft	1801332632	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	RS-BOT42	SSHS-IRM5A2-RS-BOT42	2/7/2022	-	853.96	-	850.53	2 - 4 ft	3.43 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S51A	SSHS-IRM5A2-RS-S51A	2/7/2022	-	853.76	-	849.78	2 - 4 ft	3.98 ft	1801332631	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated	< 110 U								
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336102	Not Excavated				< 0.051 U	< 0.041 U	0.058 J	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated	< 120 U								
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752	3/2/2022	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801345571	Not Excavated	< 120 U								
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated	< 460 U								
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated	< 120 U								
Northern Athletic Field	S460	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated	< 120 U								
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 110 U								
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347852	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated	< 110 U								
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated	< 120 U								
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated	< 110 U								
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.3083096	1801347841	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.5574663	1801350892	Not Excavated	< 120 U								
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.816	1801351292	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.816	1801351292	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.511	1801352871	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.511	1801352871	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated	< 130 U								
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.1339697	1801354291	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated	< 120 U								
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated	< 120 U								
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated	< 130 U								
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated	< 110 U								
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated	< 110 U								
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358362	Not Excavated				< 0.047 U	< 0.038 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated	< 130 U								
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 110 U								
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated	< 110 U								
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364902	Not Excavated				< 0.049 U	< 0.039 U	0.064 BJ	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated	< 120 U								
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated	< 110 U								
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated	< 320 U								
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated	< 110 U								
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364902	Not Excavated				< 0.049 U	< 0.039 U	0.096 BJ	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated	< 110 U								
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370432	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	S145	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated	< 130 U								
Northern Athletic Field	S146	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated	< 130 U								
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated	< 130 U								
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated	< 120 U								
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370982	Not Excavated				< 0.056 U	< 0.044 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated	< 130 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated									
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336102	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.080 J	0.068 J	< 0.044 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated									
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752	3/2/2022	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801345571	Not Excavated									
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated									
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated									
Northern Athletic Field	S460	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated									
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated									
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347852	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.031 U	0.12 J	0.076 J	< 0.039 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated									
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated									
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated									
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated									
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.3083096	1801347841	Not Excavated									
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated									
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated									
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated									
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated									
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated									
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated									
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated									
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.5574663	1801350892	Not Excavated									
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated									
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated									
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.816	1801351292	Not Excavated									
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.816	1801351292	Not Excavated									
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated									
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.511	1801352871	Not Excavated									
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.511	1801352871	Not Excavated									
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.1339697	1801354291	Not Excavated									
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated									
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated									
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated									
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated									
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated									
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated									
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated									
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358362	Not Excavated	< 0.048 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.068 J	< 0.052 U	< 0.040 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated									
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated									
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated									
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364902	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	0.023 J	< 0.034 U	0.32	0.078 J	< 0.042 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated									
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated									
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated									
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated									
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated									
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364902	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.043 J	< 0.022 U	< 0.034 U	0.23	0.093 J	< 0.042 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated									
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated									
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated									
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370432	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated									
Northern Athletic Field	S145	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated									
Northern Athletic Field	S146	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated									
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated									
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated									
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370982	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.038 U	0.12 J	< 0.062 U	< 0.048 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	RS-S61	SSHS-IRM5A2-RS-S61	2/7/2022	-	854.46	-	850.99	2 - 4 ft	3.47 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S64	SSHS-IRM5A2-RS-S64	2/7/2022	-	854.53	-	850.81	2 - 4 ft	3.72 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336101	Not Excavated						
Northern Athletic Field	RS-BOT43	SSHS-IRM5A2-RS-BOT43	2/11/2022	-	853.04	-	850.19	2 - 4 ft	2.85 ft	1801336102	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	RS-BOT44	SSHS-IRM5A2-RS-BOT44	2/11/2022	-	853.52	-	850.42	2 - 4 ft	3.1 ft	1801336101	Not Excavated						
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752	3/2/2022	-	856.53	-	853.85	2 - 4 ft	2.67 ft	1801345571	Not Excavated						
Northern Athletic Field	SLT-S77	SSHS-ISMP-SLT-S77	3/3/2022	-	856.64	-	852.71	2 - 4 ft	3.93 ft	1801346411	Not Excavated						
Northern Athletic Field	SLT-S85	SSHS-ISMP-SLT-S85	3/3/2022	-	856.53	-	853.10	2 - 4 ft	3.43 ft	1801346411	Not Excavated						
Northern Athletic Field	S460	SSHS-IRM5A2-S460	3/5/2022	-	852.61	-	848.63	2 - 4 ft	3.98 ft	1801347851	Not Excavated						
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347851	Not Excavated						
Northern Athletic Field	NE-MSA-BOT1	SSHS-IRM5A2-NE-MSA-BOT1	3/5/2022	-	853.80	-	850.57	2 - 4 ft	3.23 ft	1801347852	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	NE-MSA-BOT2	SSHS-IRM5A2-NE-MSA-BOT2	3/5/2022	-	854.35	-	851.13	2 - 4 ft	3.22 ft	1801347851	Not Excavated						
Northern Athletic Field	NE-MSA-BOT6	SSHS-IRM5A2-NE-MSA-BOT6	3/5/2022	-	854.77	-	851.62	2 - 4 ft	3.15 ft	1801347851	Not Excavated						
Northern Athletic Field	NE-MSA-BOT9	SSHS-IRM5A2-NE-MSA-BOT9	3/5/2022	-	854.52	-	850.57	2 - 4 ft	3.95 ft	1801347851	Not Excavated						
Northern Athletic Field	NE-MSA-BOT7	SSHS-IRM5A2-NE-MSA-BOT7	3/5/2022	-	854.75	-	851.51	2 - 4 ft	3.23 ft	1801347851	Not Excavated						
Northern Athletic Field	SLT-S91	SSHS-ISMP-SLT-S91	3/6/2022	-	857.12	-	853.81	2 - 4 ft	3.3083096	1801347841	Not Excavated						
Northern Athletic Field	MS-SLT-S1	SSHS-ISMP-MS-SLT-S1	3/10/2022	-	856.42	-	854.34	2 - 4 ft	2.08 ft	1801349841	Not Excavated						
Northern Athletic Field	MS-SLT-S2	SSHS-ISMP-MS-SLT-S2	3/10/2022	-	856.39	-	852.97	2 - 4 ft	3.42 ft	1801349841	Not Excavated						
Northern Athletic Field	MS-SLT-S3	SSHS-ISMP-MS-SLT-S3	3/10/2022	-	854.39	-	854.39	2 - 4 ft	2.06 ft	1801349841	Not Excavated						
Northern Athletic Field	MS-SLT-S4	SSHS-ISMP-MS-SLT-S4	3/10/2022	-	856.47	-	853.01	2 - 4 ft	3.47 ft	1801349841	Not Excavated						
Northern Athletic Field	MS-SLT-B1	SSHS-ISMP-MS-SLT-B1	3/10/2022	-	856.42	-	852.86	2 - 4 ft	3.56 ft	1801349841	Not Excavated						
Northern Athletic Field	MS-SLT-S6	SSHS-ISMP-MS-SLT-S6	3/11/2022	-	856.28	-	852.97	2 - 4 ft	3.31 ft	1801350892	Not Excavated						
Northern Athletic Field	MS-SLT-S8	SSHS-ISMP-MS-SLT-S8	3/11/2022	-	856.31	-	852.87	2 - 4 ft	3.44 ft	1801350892	Not Excavated						
Northern Athletic Field	MS-SLT-S10	SSHS-ISMP-MS-SLT-S10	3/11/2022	-	856.54	-	852.98	2 - 4 ft	3.5574663	1801350892	Not Excavated						
Northern Athletic Field	FIS-LAT-BOT3	SSHS-IRM5A2-FIS-LAT-BOT3	3/11/2022	-	853.38	-	850.33	2 - 4 ft	3.05 ft	1801350901	Not Excavated						
Northern Athletic Field	MS-SLT-S13	SSHS-ISMP-MS-SLT-S13	3/11/2022	-	856.55	-	852.65	2 - 4 ft	3.9 ft	1801350892	Not Excavated						
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-DUP1	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.816	1801351292	Not Excavated						
Northern Athletic Field	MS-SLT-S15	SSHS-ISMP-MS-SLT-S15	3/14/2022	-	856.62	-	853.80	2 - 4 ft	2.816	1801351292	Not Excavated						
Northern Athletic Field	MS-SLT-S18	SSHS-ISMP-MS-SLT-S18	3/14/2022	-	856.66	-	853.07	2 - 4 ft	3.59 ft	1801351292	Not Excavated						
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-DUP3	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.511	1801352871	Not Excavated						
Northern Athletic Field	MS-SLT-S33	SSHS-ISMP-MS-SLT-S33	3/16/2022	-	856.63	-	853.12	2 - 4 ft	3.511	1801352871	Not Excavated						
Northern Athletic Field	MS-SLT-S45	SSHS-ISMP-MS-SLT-S45	3/17/2022	-	856.87	-	853.82	2 - 4 ft	3.05 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S48	SSHS-ISMP-MS-SLT-S48	3/17/2022	-	856.69	-	853.63	2 - 4 ft	3.06 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S51	SSHS-ISMP-MS-SLT-S51	3/18/2022	-	856.69	-	853.56	2 - 4 ft	3.1339697	1801354291	Not Excavated						
Northern Athletic Field	MS-SLT-S55	SSHS-ISMP-MS-SLT-S55	3/18/2022	-	856.74	-	853.93	2 - 4 ft	2.81 ft	1801354291	Not Excavated						
Northern Athletic Field	MS-SLT-S61	SSHS-ISMP-MS-SLT-S61	3/21/2022	-	856.54	-	852.68	2 - 4 ft	3.86 ft	1801354881	Not Excavated						
Northern Athletic Field	SLT-S93-S1	SSHS-ISMP-SLT-S93-S1	3/22/2022	-	856.59	-	854.29	2 - 4 ft	2.3 ft	1801355361	Not Excavated						
Northern Athletic Field	SLT-S93-S2	SSHS-ISMP-SLT-S93-S2	3/22/2022	-	856.80	-	852.90	2 - 4 ft	3.9 ft	1801355361	Not Excavated						
Northern Athletic Field	IRM5-FP-S1	SSHS-IRM5-FP-S1	3/24/2022	-	855.97	-	853.90	2 - 4 ft	2.07 ft	1801357111	Not Excavated						
Northern Athletic Field	S465C	SSHS-IRM5A2-S465C	3/28/2022	-	853.64	-	850.63	2 - 4 ft	3.01 ft	1801358361	Not Excavated						
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358361	Not Excavated						
Northern Athletic Field	S464A	SSHS-IRM5A2-S464A	3/28/2022	-	853.23	-	849.69	2 - 4 ft	3.54 ft	1801358362	Not Excavated	< 0.037 U	< 0.021 U	< 0.041 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	PIPE1	SSHS-IRM5A2-PIPE1	3/29/2022	-	854.83	-	851.94	2 - 4 ft	2.9 ft	1801359011	Not Excavated						
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-DUP9	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated						
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364901	Not Excavated						
Northern Athletic Field	B1166	SSHS-IRM5A2-B1166	4/8/2022	-	853.94	-	851.72	2 - 4 ft	2.22 ft	1801364902	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	B1174	SSHS-IRM5A2-B1174	4/8/2022	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801364901	Not Excavated						
Northern Athletic Field	B1167	SSHS-IRM5A2-B1167	4/8/2022	-	854.14	-	851.25	2 - 4 ft	2.89 ft	1801364901	Not Excavated						
Northern Athletic Field	B1175	SSHS-IRM5A2-B1175	4/8/2022	-	855.62	-	852.66	2 - 4 ft	2.95 ft	1801364901	Not Excavated						
Northern Athletic Field	MS-SLT-S88	SSHS-ISMP-MS-SLT-S88	4/8/2022	-	856.54	-	854.29	2 - 4 ft	2.25 ft	1801364891	Not Excavated						
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364901	Not Excavated						
Northern Athletic Field	B1154	SSHS-IRM5A2-B1154	4/8/2022	-	854.79	-	852.06	2 - 4 ft	2.73 ft	1801364902	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	MS-SLT-S83	SSHS-ISMP-MS-SLT-S83	4/8/2022	-	856.68	-	854.34	2 - 4 ft	2.33 ft	1801364891	Not Excavated						
Northern Athletic Field	S528	SSHS-IRM5A2-DUP63	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated						
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370431	Not Excavated						
Northern Athletic Field	S481	SSHS-IRM5A2-S481	4/21/2022	-	855.67	-	853.19	2 - 4 ft	2.49 ft	1801370432	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S528	SSHS-IRM5A2-S528	4/21/2022	-	856.28	-	852.29	2 - 4 ft	3.99 ft	1801370431	Not Excavated						
Northern Athletic Field	S145	SSHS-IRM5A2-S145	4/21/2022	-	854.36	-	851.66	2 - 4 ft	2.7 ft	1801370431	Not Excavated						
Northern Athletic Field	S146	SSHS-IRM5A2-S146	4/21/2022	-	855.21	-	851.77	2 - 4 ft	3.44 ft	1801370431	Not Excavated						
Northern Athletic Field	S504	SSHS-IRM5A2-DUP65	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated						
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370981	Not Excavated						
Northern Athletic Field	S525	SSHS-IRM5A2-S525	4/22/2022	-	856.74	-	854.13	2 - 4 ft	2.62 ft	1801370982	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	S524	SSHS-IRM5A2-S524	4/22/2022	-	856.78	-	853.69	2 - 4 ft	3.1 ft	1801370981	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated	< 120 U								
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370982	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370951	Not Excavated	< 130 U								
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated	< 120 U								
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated	< 120 U								
Northern Athletic Field	S861	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated	< 120 U								
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated		< 30 U							
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377982	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated		< 160 U							
Northern Athletic Field	S957	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated		< 30 U							
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated		< 150 U							
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated		< 33 U							
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated		< 32 U							
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378344	Not Excavated				< 0.050 U	< 0.040 U	0.080 J	< 0.054 U	0.078 J	< 0.031 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated		< 31 U							
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated		< 32 U							
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated		< 33 U							
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated		< 32 U							
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated		< 34 U							
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated		< 34 U							
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated		< 31 U							
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379862	Not Excavated				< 0.048 U	< 0.038 U	0.084 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated		< 29 U							
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated		< 31 U							
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379862	Not Excavated				< 0.051 U	< 0.040 U	0.054 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated		< 34 U							
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated		< 31 U							
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated		< 30 U							
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383172	Not Excavated				< 0.047 U	< 0.037 U	0.050 J	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated		< 30 U							
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated		< 30 U							
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated		< 30 U							
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391882	Not Excavated				< 0.047 U	< 0.037 U	0.27 B	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated		< 32 U							
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated		< 32 U							
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated		< 30 U							
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391882	Not Excavated				< 0.049 U	< 0.039 U	0.31 B	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated		< 33 U							
Northern Athletic Field	S949	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated		< 32 U							
Northern Athletic Field	S948	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated		< 34 U							
Northern Athletic Field	S947	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated		< 32 U							
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated		< 150 U							
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391882	Not Excavated				< 0.48 U	< 0.38 U	1.2 J	< 0.52 U	< 0.48 U	< 0.30 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated		< 30 U							
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated		< 30 U							
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated		< 29 U							
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated		< 31 U							
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391882	Not Excavated				< 0.051 U	< 0.040 U	0.36 B	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated		< 30 U							
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated		< 29 U							
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated		< 30 U							
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391882	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated	< 120 U								
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated	< 120 U								
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated		< 30 U							
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated		< 32 U							
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated		< 31 U							
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399473	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated		< 31 U							
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated		< 30 U							
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated		< 31 U							
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated									
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370982	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370951	Not Excavated									
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated									
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated									
Northern Athletic Field	S861	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated									
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated									
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377982	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.051 J	0.023 J	< 0.033 U	0.64	0.11 J	0.074 J
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated									
Northern Athletic Field	S957	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated									
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated									
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated									
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated									
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378344	Not Excavated	< 0.051 U	0.054 J	< 0.030 U	0.067 J	0.037 J	< 0.034 U	0.12 J	0.11 J	0.16 J
Northern Athletic Field	S531	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated									
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated									
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated									
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated									
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated									
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated									
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379862	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	0.083 J
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379862	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	0.073 J
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated									
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated									
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383172	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated									
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated									
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391882	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	0.089 J	< 0.052 U	< 0.040 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated									
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated									
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated									
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391882	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.093 J	< 0.054 U	0.051 J
Northern Athletic Field	S950	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated									
Northern Athletic Field	S949	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated									
Northern Athletic Field	S948	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated									
Northern Athletic Field	S947	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated									
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated									
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391882	Not Excavated	< 0.49 U	< 0.38 U	< 0.29 U	< 0.31 U	< 0.22 U	< 0.33 U	< 0.43 U	< 0.53 U	2.2
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391882	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.28	0.16 J	< 0.043 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391882	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	0.11 J	< 0.052 U	< 0.040 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399473	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	0.054 J	< 0.035 U	0.37	0.12 J	< 0.044 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated									
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370981	Not Excavated						
Northern Athletic Field	S523	SSHS-IRM5A2-S523	4/22/2022	-	856.74	-	853.46	2 - 4 ft	3.28 ft	1801370982	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	S504	SSHS-IRM5A2-S504	4/22/2022	-	856.38	-	853.65	2 - 4 ft	2.73 ft	1801370981	Not Excavated						
Northern Athletic Field	B2001	SSHS-IRM5A2-B2001	5/2/2022	-	857.22	-	853.91	2 - 4 ft	3.32 ft	1801374861	Not Excavated						
Northern Athletic Field	B2002	SSHS-IRM5A2-B2002	5/2/2022	-	857.13	-	853.74	2 - 4 ft	3.39 ft	1801374861	Not Excavated						
Northern Athletic Field	S861	SSHS-IRM5A2-S861	5/5/2022	-	856.43	-	854.08	2 - 4 ft	2.35 ft	1801376931	Not Excavated						
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377981	Not Excavated						
Northern Athletic Field	S956	SSHS-IRM5A2-S956	5/6/2022	-	856.27	-	853.59	2 - 4 ft	2.68 ft	1801377982	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	B2001A	SSHS-IRM5A2-B2001A	5/6/2022	-	856.68	-	853.63	2 - 4 ft	3.06 ft	1801377981	Not Excavated						
Northern Athletic Field	S957	SSHS-IRM5A2-S957	5/6/2022	-	856.72	-	854.39	2 - 4 ft	2.32 ft	1801377981	Not Excavated						
Northern Athletic Field	B1021	SSHS-IRM5A2-B1021	5/6/2022	-	856.98	-	854.07	2 - 4 ft	2.9 ft	1801377981	Not Excavated						
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-DUP85	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated						
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378342	Not Excavated						
Northern Athletic Field	A5-V1-S13	SSHS-IRM5A2-A5-V1-S13	5/9/2022	-	856.56	-	854.01	2 - 4 ft	2.55 ft	1801378344	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S531	SSHS-IRM5A2-S531	5/9/2022	-	856.14	-	853.13	2 - 4 ft	3.02 ft	1801378341	Not Excavated						
Northern Athletic Field	A5-V1-BOT2	SSHS-IRM5A2-A5-V1-BOT2	5/9/2022	-	856.46	-	854.33	2 - 4 ft	2.13 ft	1801378342	Not Excavated						
Northern Athletic Field	A5-V1-S15	SSHS-IRM5A2-A5-V1-S15	5/9/2022	-	856.39	-	853.64	2 - 4 ft	2.75 ft	1801378342	Not Excavated						
Northern Athletic Field	S526-BOT1	SSHS-IRM5A2-S526-BOT1	5/9/2022	-	856.26	-	852.71	2 - 4 ft	3.55 ft	1801378343	Not Excavated						
Northern Athletic Field	S526-BOT2	SSHS-IRM5A2-S526-BOT2	5/9/2022	-	856.59	-	853.35	2 - 4 ft	3.24 ft	1801378343	Not Excavated						
Northern Athletic Field	S526-BOT3	SSHS-IRM5A2-S526-BOT3	5/9/2022	-	856.72	-	853.26	2 - 4 ft	3.46 ft	1801378343	Not Excavated						
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-DUP86	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379862	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FIS-LAT1-S1	SSHS-IRM5A2-FIS-LAT1-S1	5/11/2022	-	853.38	-	849.56	2 - 4 ft	3.83 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-S2	SSHS-IRM5A2-FIS-LAT1-S2	5/11/2022	-	853.41	-	849.63	2 - 4 ft	3.79 ft	1801379862	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FIS-LAT1-S3	SSHS-IRM5A2-FIS-LAT1-S3	5/11/2022	-	853.43	-	849.59	2 - 4 ft	3.84 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-S4	SSHS-IRM5A2-FIS-LAT1-S4	5/11/2022	-	853.55	-	849.98	2 - 4 ft	3.58 ft	1801379861	Not Excavated						
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383171	Not Excavated						
Northern Athletic Field	B5005	SSHS-IRM5A2-B5005	5/18/2022	-	854.64	-	851.26	2 - 4 ft	3.38 ft	1801383172	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	B5006	SSHS-IRM5A2-B5006	5/18/2022	-	853.94	-	850.57	2 - 4 ft	3.37 ft	1801383171	Not Excavated						
Northern Athletic Field	B5007	SSHS-IRM5A2-B5007	5/18/2022	-	853.98	-	851.29	2 - 4 ft	2.69 ft	1801383171	Not Excavated						
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-B405	SSHS-IRM5A2-DUP102	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391882	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	S953-BOT	SSHS-IRM5A2-S953-BOT1	6/6/2022	-	856.54	-	853.10	2 - 4 ft	3.44 ft	1801391881	Not Excavated						
Northern Athletic Field	S953-S2	SSHS-IRM5A2-S953-S2	6/6/2022	-	856.52	-	853.62	2 - 4 ft	2.91 ft	1801391881	Not Excavated						
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391881	Not Excavated						
Northern Athletic Field	S951	SSHS-IRM5A2-S951	6/6/2022	-	856.27	-	852.98	2 - 4 ft	3.28 ft	1801391882	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S950	SSHS-IRM5A2-S950	6/6/2022	-	855.94	-	852.55	2 - 4 ft	3.39 ft	1801391881	Not Excavated						
Northern Athletic Field	S949	SSHS-IRM5A2-S949	6/6/2022	-	855.56	-	852.57	2 - 4 ft	2.99 ft	1801391881	Not Excavated						
Northern Athletic Field	S948	SSHS-IRM5A2-S948	6/6/2022	-	855.36	-	852.15	2 - 4 ft	3.21 ft	1801391881	Not Excavated						
Northern Athletic Field	S947	SSHS-IRM5A2-S947	6/6/2022	-	855.26	-	851.64	2 - 4 ft	3.62 ft	1801391881	Not Excavated						
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391881	Not Excavated						
Northern Athletic Field	S946	SSHS-IRM5A2-S946	6/6/2022	-	854.72	-	851.02	2 - 4 ft	3.7 ft	1801391882	Not Excavated	< 0.37 U	< 0.21 U	< 0.42 U	< 0.35 U	< 0.27 U	< 0.23 U
Northern Athletic Field	A5-B400	SSHS-IRM5A2-A5-B400	6/6/2022	-	855.06	-	851.86	2 - 4 ft	3.21 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-B401	SSHS-IRM5A2-A5-B401	6/6/2022	-	855.10	-	851.74	2 - 4 ft	3.36 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-B402	SSHS-IRM5A2-A5-B402	6/6/2022	-	854.87	-	851.16	2 - 4 ft	3.71 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-S402	SSHS-IRM5A2-A5-S402	6/6/2022	-	854.26	-	850.71	2 - 4 ft	3.55 ft	1801391882	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A5-B403	SSHS-IRM5A2-A5-B403	6/6/2022	-	853.81	-	850.87	2 - 4 ft	2.94 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-B404	SSHS-IRM5A2-A5-B404	6/6/2022	-	854.03	-	851.13	2 - 4 ft	2.9 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-B405	SSHS-IRM5A2-A5-B405	6/6/2022	-	854.39	-	851.82	2 - 4 ft	2.57 ft	1801391882	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	A3-B202	SSHS-IRM5A2-A3-B202	6/16/2022	-	855.66	-	851.68	2 - 4 ft	3.97 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-B204	SSHS-IRM5A2-A3-B204	6/16/2022	-	855.62	-	852.11	2 - 4 ft	3.51 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-B205	SSHS-IRM5A2-A3-B205	6/16/2022	-	856.07	-	852.17	2 - 4 ft	3.9 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-DUP131	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B200A	SSHS-IRM5A2-A3-B200A	6/17/2022	-	853.57	-	849.98	2 - 4 ft	3.59 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B201A	SSHS-IRM5A2-A3-B201A	6/17/2022	-	852.57	-	848.99	2 - 4 ft	3.58 ft	1801399473	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A3-B203A	SSHS-IRM5A2-A3-B203A	6/17/2022	-	852.44	-	848.84	2 - 4 ft	3.6 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B205A	SSHS-IRM5A2-A3-B205A	6/17/2022	-	852.14	-	849.51	2 - 4 ft	2.63 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B207	SSHS-IRM5A2-A3-B207	6/17/2022	-	852.40	-	848.85	2 - 4 ft	3.55 ft	1801399472	Not Excavated						
Northern Athletic Field	S953-S1BOT	SSHS-IRM5A2-S953-S1BOT	6/22/2022	-	856.48	-	853.29	2 - 4 ft	3.18 ft	1801401821	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated	< 120 U								
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401822	Not Excavated				< 0.052 U	< 0.041 U	0.12 J	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated	< 120 U								
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated	< 110 U								
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated		< 31 UT							
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407632	Not Excavated				< 0.048 U	< 0.038 U	0.14 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated		< 30 UT							
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated		< 30 UT							
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407632	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated		< 32 UT							
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated		< 31 UT							
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated		< 30 UT							
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407993	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated		< 32 U							
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated		< 31 U							
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407993	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated		< 34 U							
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410572	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated		< 31 U							
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated		< 34 U							
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410572	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated		< 31 U							
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated	< 100 U								
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412372	Not Excavated				< 0.045 U	< 0.035 U	0.050 J	< 0.048 U	< 0.045 U	< 0.028 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated		< 31 U							
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated		< 31 U							
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated		< 32 U							
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated		< 30 U							
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated		< 34 U							
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413122	Not Excavated				< 0.056 U	< 0.044 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated		< 31 U							
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated		< 30 U							
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413122	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated		< 32 U							
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated		< 31 U							
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated		< 31 U							
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated		< 32 U							
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413132	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated		< 33 U							
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated		< 33 U							
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413132	Not Excavated				< 0.052 U	< 0.041 U	0.051 J	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 110 U								
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418263	Not Excavated				< 0.050 U	< 0.040 U	0.059 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated	< 100 U								
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418263	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated	< 120 U								
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated	< 110 U								
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418263	Not Excavated				< 0.049 U	< 0.039 U	0.24	0.062 J	< 0.049 U	< 0.030 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated	< 110 U								
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418263	Not Excavated				< 0.052 U	< 0.041 U	0.093 J	< 0.056 U	0.056 J	< 0.033 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated	< 110 U								
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated	< 110 U								
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated	< 110 U								
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated		< 31 U							
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated									
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	18014018[illegible]22	Not Excavated	< 0.053 U	0.045 J	< 0.031 U	0.054 J	< 0.024 U	< 0.036 U	0.096 J	0.10 J	0.066 J
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated									
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated									
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated									
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated									
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407632	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.039 J	0.038 J	< 0.033 U	0.19 J	0.10 J	0.055 J
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407632	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.086 J	< 0.051 U	< 0.039 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407993	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407993	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410572	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.057 U	< 0.044 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410572	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated									
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated									
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412372	Not Excavated	< 0.046 U	< 0.035 U	< 0.027 U	< 0.029 U	< 0.020 U	< 0.031 U	< 0.040 U	< 0.049 U	0.055 J
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413122	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.039 U	< 0.050 U	< 0.062 U	< 0.048 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413122	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413132	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	0.065 J	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	0.13 J
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413132	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.063 J	< 0.058 U	< 0.045 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated									
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418263	Not Excavated	< 0.051 U	0.063 J	< 0.030 U	0.047 J	0.066 J	< 0.035 U	0.95	0.21	< 0.043 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418263	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated									
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated									
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418263	Not Excavated	< 0.050 U	0.12 J	< 0.029 U	0.16 J	0.070 J	< 0.034 U	0.41	0.35	0.19 J
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated									
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418263	Not Excavated	< 0.053 U	0.048 J	< 0.031 U	0.047 J	0.071 J	< 0.036 U	0.96	0.17 J	< 0.044 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated									
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated									
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated									
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401821	Not Excavated						
Northern Athletic Field	A3-B211	SSHS-IRM5A2-A3-B211	6/22/2022	-	856.60	-	853.23	2 - 4 ft	3.37 ft	1801401822	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-B212	SSHS-IRM5A2-A3-B212	6/22/2022	-	856.82	-	853.36	2 - 4 ft	3.46 ft	1801401821	Not Excavated						
Northern Athletic Field	A3-B213	SSHS-IRM5A2-A3-B213	6/22/2022	-	856.31	-	852.74	2 - 4 ft	3.58 ft	1801401821	Not Excavated						
Northern Athletic Field	B1168	SSHS-IRM5A2-DUP143	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S48	SSHS-IRM5A2-FISR-S48	6/30/2022	-	853.19	-	849.58	2 - 4 ft	3.61 ft	1801406771	Not Excavated						
Northern Athletic Field	B1168	SSHS-IRM5A2-B1168	6/30/2022	-	854.39	-	851.17	2 - 4 ft	3.22 ft	1801406772	Not Excavated						
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S200	SSHS-IRM5A2-FL-S200	7/1/2022	-	857.29	-	855.16	2 - 4 ft	2.13 ft	1801407632	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S201	SSHS-IRM5A2-FL-S201	7/1/2022	-	857.31	-	855.24	2 - 4 ft	2.07 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S203	SSHS-IRM5A2-FL-S203	7/1/2022	-	857.84	-	855.49	2 - 4 ft	2.35 ft	1801407632	Not Excavated	< 0.036 U	< 0.020 U	< 0.040 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-S400	SSHS-IRM5A2-FL-S400	7/1/2022	-	856.56	-	852.73	2 - 4 ft	3.83 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S401	SSHS-IRM5A2-FL-S401	7/1/2022	-	856.84	-	852.87	2 - 4 ft	3.97 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S402	SSHS-IRM5A2-FL-S402	7/1/2022	-	857.10	-	853.12	2 - 4 ft	3.98 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S204	SSHS-IRM5A2-FL-S204	7/5/2022	-	857.63	-	855.30	2 - 4 ft	2.33 ft	1801407993	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-S408	SSHS-IRM5A2-FL-S408	7/5/2022	-	857.73	-	854.52	2 - 4 ft	3.22 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B403	SSHS-IRM5A2-FL-B403	7/5/2022	-	856.58	-	852.75	2 - 4 ft	3.83 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B407	SSHS-IRM5A2-FL-B407	7/5/2022	-	856.68	-	852.84	2 - 4 ft	3.84 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B412	SSHS-IRM5A2-FL-B412	7/5/2022	-	856.82	-	853.11	2 - 4 ft	3.71 ft	1801407993	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-S410	SSHS-IRM5A2-DUP149	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410572	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FL-S409	SSHS-IRM5A2-FL-S409	7/8/2022	-	857.87	-	854.22	2 - 4 ft	3.64 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-S410	SSHS-IRM5A2-FL-S410	7/8/2022	-	857.27	-	853.98	2 - 4 ft	3.29 ft	1801410572	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	FL-S420	SSHS-IRM5A2-FL-S420	7/11/2022	-	856.19	-	853.26	2 - 4 ft	2.93 ft	1801411041	Not Excavated						
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412371	Not Excavated						
Northern Athletic Field	FL-B446	SSHS-IRM5A2-FL-B446	7/13/2022	-	856.66	-	852.67	2 - 4 ft	4 ft	1801412372	Not Excavated	< 0.034 U	< 0.020 U	< 0.039 U	< 0.033 U	< 0.025 U	< 0.021 U
Northern Athletic Field	FL-B456	SSHS-IRM5A2-DUP164	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B453	SSHS-IRM5A2-FL-B453	7/14/2022	-	856.59	-	852.61	2 - 4 ft	3.99 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B456	SSHS-IRM5A2-FL-B456	7/14/2022	-	856.58	-	852.58	2 - 4 ft	4 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B461	SSHS-IRM5A2-FL-B461	7/14/2022	-	856.19	-	852.30	2 - 4 ft	3.9 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B461A	SSHS-IRM5A2-FL-B461A	7/14/2022	-	856.20	-	852.21	2 - 4 ft	3.98 ft	1801413122	Not Excavated	< 0.043 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	FL-B463	SSHS-IRM5A2-FL-B463	7/14/2022	-	856.77	-	852.91	2 - 4 ft	3.86 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B464	SSHS-IRM5A2-FL-B464	7/14/2022	-	856.72	-	852.72	2 - 4 ft	4 ft	1801413122	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B468	SSHS-IRM5A2-FL-B468	7/14/2022	-	856.27	-	852.28	2 - 4 ft	3.99 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S421	SSHS-IRM5A2-FL-S421	7/14/2022	-	856.29	-	852.65	2 - 4 ft	3.64 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S425	SSHS-IRM5A2-FL-S425	7/14/2022	-	856.64	-	852.58	2 - 4 ft	4.07 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S429	SSHS-IRM5A2-FL-S429	7/14/2022	-	856.71	-	852.79	2 - 4 ft	3.92 ft	1801413132	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FL-S430	SSHS-IRM5A2-FL-S430	7/14/2022	-	856.69	-	852.79	2 - 4 ft	3.9 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S431	SSHS-IRM5A2-FL-S431	7/14/2022	-	856.54	-	852.55	2 - 4 ft	4 ft	1801413132	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated						
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-DUP169	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418263	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-S424	SSHS-IRM5A2-FL-S424	7/22/2022	-	856.68	-	853.35	2 - 4 ft	3.33 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S423	SSHS-IRM5A2-FL-S423	7/22/2022	-	856.62	-	852.59	2 - 4 ft	4.03 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S422	SSHS-IRM5A2-FL-S422	7/22/2022	-	856.47	-	852.56	2 - 4 ft	3.91 ft	1801418263	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A5-B406	SSHS-IRM5A2-A5-B406	7/22/2022	-	856.44	-	853.22	2 - 4 ft	3.22 ft	1801418262	Not Excavated						
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418262	Not Excavated						
Northern Athletic Field	S868-BOT	SSHS-IRM5A2-S868-BOT	7/22/2022	-	856.57	-	853.64	2 - 4 ft	2.93 ft	1801418263	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418262	Not Excavated						
Northern Athletic Field	S866-BOT	SSHS-IRM5A2-S866-BOT	7/22/2022	-	856.85	-	854.73	2 - 4 ft	2.12 ft	1801418263	Not Excavated	< 0.040 U	0.025 J	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	S865-BOT	SSHS-IRM5A2-S865-BOT	7/22/2022	-	856.71	-	854.62	2 - 4 ft	2.09 ft	1801418262	Not Excavated						
Northern Athletic Field	A5-B201	SSHS-IRM5A2-A5-B201	7/22/2022	-	856.61	-	854.51	2 - 4 ft	2.11 ft	1801418262	Not Excavated						
Northern Athletic Field	A5-B202	SSHS-IRM5A2-A5-B202	7/22/2022	-	856.58	-	854.20	2 - 4 ft	2.38 ft	1801418262	Not Excavated						
Northern Athletic Field	FL-S434	SSHS-IRM5A2-DUP171	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S432	SSHS-IRM5A2-FL-S432	7/25/2022	-	857.27	-	853.88	2 - 4 ft	3.39 ft	1801418881	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated		< 30 U							
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated		< 30 U							
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418912	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated		< 33 U							
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated		< 34 U							
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated		< 32 U							
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418912	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated		< 30 U							
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418912	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated		< 31 U							
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated		< 31 U							
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated		< 29 U							
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated		< 29 U							
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432522	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated		< 34 U							
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432952	Not Excavated				< 0.057 U	< 0.045 U	0.35	< 0.061 U	< 0.057 U	< 0.035 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated		< 32 U							
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated		< 31 U							
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated		< 49 U							
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated		< 31 U							
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated		< 31 U							
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated		< 31 U							
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated		< 34 U							
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438852	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated		< 30 U							
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated		< 31 U							
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated		< 31 U							
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated		< 34 U							
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438852	Not Excavated				< 0.056 U	< 0.044 U	0.26	< 0.060 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated		< 32 U							
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated		< 30 U							
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated		< 34 U							
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447212	Not Excavated				< 0.055 U	< 0.043 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated		< 39 U							
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated		< 33 U							
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451962	Not Excavated				< 0.052 U	< 0.041 U	0.10 J	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated		< 35 U							
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated		< 35 U							
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated		< 33 U							
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated		< 31 U							
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451962	Not Excavated				< 0.050 U	< 0.040 U	0.052 J	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated		< 32 U							
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated		< 31 U							
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated		< 32 U							
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated		< 35 U							
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated		< 33 U							
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated		< 32 U							
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated		< 32 U							
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465922	Not Excavated				< 0.052 U	< 0.041 U	0.61	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated		< 31 U							
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated		< 31 U							
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated		< 31 U							
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated		< 33 U							
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated		< 34 U							
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465922	Not Excavated				< 0.054 U	< 0.043 U	0.19 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated		< 30 U							
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465922	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated		< 31 U							
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated		< 30 U							
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418912	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418912	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418912	Not Excavated	< 0.048 U	0.037 J	< 0.029 U	0.063 J	< 0.022 U	< 0.033 U	< 0.042 U	0.082 J	0.059 J
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated									
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated									
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated									
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated									
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432522	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.031 U	0.16 J	0.063 J	< 0.039 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated									
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432952	Not Excavated	< 0.058 U	0.060 J	< 0.034 U	0.044 J	< 0.026 U	< 0.039 U	0.15 J	0.21 J	0.13 J
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated									
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated									
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated									
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438852	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	0.61	0.23	0.32
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438852	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	0.040 J	< 0.038 U	0.78	0.18 J	0.13 J
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated									
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447212	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	0.15 J	< 0.061 U	< 0.047 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451962	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	0.14 J	0.060 J	0.049 J
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451962	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.033 U	0.023 J	< 0.035 U	0.36	0.080 J	< 0.043 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465922	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	0.057 J	< 0.044 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465922	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465922	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FL-S434	SSHS-IRM5A2-FL-S434	7/25/2022	-	856.95	-	853.44	2 - 4 ft	3.51 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S435	SSHS-IRM5A2-FL-S435	7/25/2022	-	856.67	-	852.95	2 - 4 ft	3.72 ft	1801418912	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-S436	SSHS-IRM5A2-FL-S436	7/25/2022	-	856.52	-	852.90	2 - 4 ft	3.62 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S437	SSHS-IRM5A2-FL-S437	7/25/2022	-	856.51	-	853.05	2 - 4 ft	3.46 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S438	SSHS-IRM5A2-FL-S438	7/25/2022	-	856.59	-	853.17	2 - 4 ft	3.42 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S439	SSHS-IRM5A2-FL-S439	7/25/2022	-	856.60	-	853.07	2 - 4 ft	3.54 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S440	SSHS-IRM5A2-FL-S440	7/25/2022	-	856.68	-	853.26	2 - 4 ft	3.42 ft	1801418912	Not Excavated	< 0.037 U	0.021 J	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S441	SSHS-IRM5A2-FL-S441	7/25/2022	-	--	-	852.90	2 - 4 ft	2 - 4 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S442	SSHS-IRM5A2-FL-S442	7/25/2022	-	856.39	-	853.28	2 - 4 ft	3.11 ft	1801418912	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.035 U	0.073 J	< 0.023 U
Northern Athletic Field	A6-LP2	SSHS-IRM5A2-A6-LP2	8/17/2022	-	854.54	-	851.63	2 - 4 ft	2.9 ft	1801430721	Not Excavated						
Northern Athletic Field	A6-LP3	SSHS-IRM5A2-A6-LP3	8/17/2022	-	854.59	-	850.93	2 - 4 ft	3.66 ft	1801430721	Not Excavated						
Northern Athletic Field	A6-B206	SSHS-IRM5A2-A6-B206	8/19/2022	-	852.27	-	849.11	2 - 4 ft	3.16 ft	1801432521	Not Excavated						
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432521	Not Excavated						
Northern Athletic Field	A6-B207	SSHS-IRM5A2-A6-B207	8/19/2022	-	853.10	-	849.55	2 - 4 ft	3.54 ft	1801432522	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432951	Not Excavated						
Northern Athletic Field	A6-B216	SSHS-IRM5A2-A6-B216	8/22/2022	-	856.78	-	854.31	2 - 4 ft	2.47 ft	1801432952	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A6-B217	SSHS-IRM5A2-A6-B217	8/22/2022	-	856.96	-	854.06	2 - 4 ft	2.9 ft	1801432951	Not Excavated						
Northern Athletic Field	A6-B219	SSHS-IRM5A2-A6-B219	8/22/2022	-	856.37	-	853.79	2 - 4 ft	2.58 ft	1801432951	Not Excavated						
Northern Athletic Field	DW10	SSHS-IRM5A2-DW10	8/26/2022	-	857.10	-	854.33	2 - 4 ft	2.77 ft	1801436181	Not Excavated						
Northern Athletic Field	A6-B229	SSHS-IRM5A2-DUP225	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B229	SSHS-IRM5A2-A6-B229	9/1/2022	-	854.57	-	851.18	2 - 4 ft	3.39 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B230	SSHS-IRM5A2-A6-B230	9/1/2022	-	854.80	-	852.02	2 - 4 ft	2.78 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B231	SSHS-IRM5A2-A6-B231	9/1/2022	-	854.68	-	851.55	2 - 4 ft	3.12 ft	1801438852	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B232	SSHS-IRM5A2-A6-B232	9/1/2022	-	854.70	-	851.17	2 - 4 ft	3.53 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B233	SSHS-IRM5A2-A6-B233	9/1/2022	-	854.64	-	850.92	2 - 4 ft	3.72 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B234	SSHS-IRM5A2-A6-B234	9/1/2022	-	855.08	-	852.17	2 - 4 ft	2.91 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B235	SSHS-IRM5A2-A6-B235	9/1/2022	-	855.00	-	851.58	2 - 4 ft	3.42 ft	1801438852	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A6-B236	SSHS-IRM5A2-A6-B236	9/1/2022	-	854.95	-	851.23	2 - 4 ft	3.71 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B237	SSHS-IRM5A2-A6-B237	9/1/2022	-	855.30	-	851.83	2 - 4 ft	3.47 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447211	Not Excavated						
Northern Athletic Field	A6-B239	SSHS-IRM5A2-A6-B239	9/19/2022	-	852.67	-	849.10	2 - 4 ft	3.57 ft	1801447212	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-B242	SSHS-IRM5A2-DUP235	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B240	SSHS-IRM5A2-A6-B240	9/27/2022	-	855.44	-	852.30	2 - 4 ft	3.14 ft	1801451962	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B241	SSHS-IRM5A2-A6-B241	9/27/2022	-	855.84	-	852.82	2 - 4 ft	3.01 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B242	SSHS-IRM5A2-A6-B242	9/27/2022	-	855.75	-	853.05	2 - 4 ft	2.7 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B243	SSHS-IRM5A2-A6-B243	9/27/2022	-	855.50	-	852.75	2 - 4 ft	2.75 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B244	SSHS-IRM5A2-A6-B244	9/27/2022	-	855.18	-	852.49	2 - 4 ft	2.7 ft	1801451962	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B245	SSHS-IRM5A2-A6-B245	9/27/2022	-	855.36	-	852.97	2 - 4 ft	2.38 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B246	SSHS-IRM5A2-A6-B246	9/27/2022	-	855.13	-	852.85	2 - 4 ft	2.28 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S431	SSHS-IRM5A2-A6-S431	9/27/2022	-	855.55	-	851.55	2 - 4 ft	4 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S432	SSHS-IRM5A2-A6-S432	9/27/2022	-	855.18	-	851.39	2 - 4 ft	3.79 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B442	SSHS-IRM5A2-DUP241	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B249	SSHS-IRM5A2-A6-B249	10/20/2022	-	855.99	-	853.49	2 - 4 ft	2.5 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B251	SSHS-IRM5A2-A6-B251	10/20/2022	-	856.44	-	853.71	2 - 4 ft	2.73 ft	1801465922	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B252	SSHS-IRM5A2-A6-B252	10/20/2022	-	856.63	-	854.10	2 - 4 ft	2.52 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B253	SSHS-IRM5A2-A6-B253	10/20/2022	-	856.95	-	853.66	2 - 4 ft	3.3 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B254	SSHS-IRM5A2-A6-B254	10/20/2022	-	857.00	-	853.72	2 - 4 ft	3.28 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S434	SSHS-IRM5A2-A6-S434	10/20/2022	-	854.52	-	852.45	2 - 4 ft	2.07 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S435	SSHS-IRM5A2-A6-S435	10/20/2022	-	855.93	-	852.20	2 - 4 ft	3.74 ft	1801465922	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B439	SSHS-IRM5A2-A6-B439	10/20/2022	-	854.07	-	851.37	2 - 4 ft	2.7 ft	1801465922	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B440	SSHS-IRM5A2-A6-B440	10/20/2022	-	854.25	-	851.75	2 - 4 ft	2.5 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B441	SSHS-IRM5A2-A6-B441	10/20/2022	-	855.23	-	851.44	2 - 4 ft	3.79 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B442	SSHS-IRM5A2-A6-B442	10/20/2022	-	855.67	-	852.06	2 - 4 ft	3.61 ft	1801465931	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469412	Not Excavated				< 0.048 U	< 0.038 U	0.12 BJ	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated		< 30 U							
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469412	Not Excavated				< 0.046 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470202	Not Excavated				< 0.050 U	< 0.040 U	0.17 BJ	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470202	Not Excavated				< 0.049 U	< 0.039 U	0.11 BJ	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470202	Not Excavated				< 0.052 U	< 0.041 U	0.21 B	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated		< 30 U							
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470202	Not Excavated				< 0.047 U	< 0.037 U	0.11 BJ	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470202	Not Excavated				< 0.050 U	< 0.040 U	0.15 BJ	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated		< 30 U							
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471322	Not Excavated				< 0.047 U	< 0.037 U	0.28 B	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated		< 30 U							
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated		< 30 U							
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471322	Not Excavated				0.059 J	< 0.036 U	0.61 B	< 0.049 U	< 0.045 U	< 0.028 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471322	Not Excavated				< 0.048 U	< 0.038 U	0.14 BJ	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated		< 30 U							
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated		< 35 U							
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated		< 32 U							
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated		< 36 U							
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated		< 32 U							
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated		< 34 U							
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated		< 32 U							
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated		< 34 U							
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473062	Not Excavated				< 0.056 U	< 0.044 U	0.27 B	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated		< 31 U							
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated		< 31 U							
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated		< 31 U							
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated		< 32 U							
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473062	Not Excavated				< 0.051 U	< 0.041 U	0.20 BJ	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated		< 32 U							
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated		< 35 U							
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473872	Not Excavated				< 0.048 U	< 0.038 U	0.26 B	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated		< 34 U							
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473872	Not Excavated				< 0.054 U	< 0.043 U	0.58 B	< 0.058 U	< 0.054 U	< 0.034 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated									
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469412	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469412	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.049 J	< 0.051 U	< 0.040 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated									
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470202	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	0.034 J	< 0.023 U	< 0.035 U	0.090 J	< 0.056 U	< 0.043 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470202	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.051 J	< 0.054 U	< 0.042 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470202	Not Excavated	< 0.053 U	0.045 J	< 0.031 U	0.078 J	0.046 J	< 0.035 U	0.19 J	0.11 J	0.064 J
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470202	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	0.032 J	< 0.022 U	< 0.033 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470202	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.051 J	< 0.055 U	< 0.043 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated									
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated									
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471322	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.098 J	0.067 J	0.052 J
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471322	Not Excavated	< 0.046 U	0.090 J	0.029 J	0.12 J	0.078 J	< 0.031 U	2.1	0.69	< 0.039 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471322	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated									
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated									
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated									
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated									
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473062	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	0.052 J	0.029 J	< 0.039 U	0.096 J	0.086 J	< 0.048 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473062	Not Excavated	< 0.052 U	0.041 J	< 0.031 U	0.054 J	0.046 J	< 0.035 U	0.19 J	0.12 J	< 0.044 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated									
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated									
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473872	Not Excavated	< 0.049 U	0.049 J	< 0.029 U	0.050 J	0.060 J	< 0.033 U	< 0.22 U	0.099 J	0.041 J
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated									
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473872	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	0.29	< 0.060 U	< 0.046 U

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6-B648	SSHS-IRM5A2-A6-B648	10/20/2022	-	855.35	-	850.19	2 - 4 ft	5.16 ft	1801465931	Not Excavated						
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-DUP245	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S1	SSHS-IRM5A2-A1-VAULT-S1	10/26/2022	-	857.13	-	853.20	2 - 4 ft	3.93 ft	1801469412	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1-VAULT-S2	SSHS-IRM5A2-A1-VAULT-S2	10/26/2022	-	857.24	-	853.34	2 - 4 ft	3.9 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S3	SSHS-IRM5A2-A1-VAULT-S3	10/26/2022	-	857.47	-	853.60	2 - 4 ft	3.87 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S4	SSHS-IRM5A2-A1-VAULT-S4	10/26/2022	-	857.38	-	853.60	2 - 4 ft	3.78 ft	1801469412	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A1-VAULT-S5	SSHS-IRM5A2-A1-VAULT-S5	10/26/2022	-	857.15	-	853.31	2 - 4 ft	3.84 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S6	SSHS-IRM5A2-A1-VAULT-S6	10/26/2022	-	857.05	-	853.06	2 - 4 ft	3.98 ft	1801469411	Not Excavated						
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-DUP250	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470202	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-DUP249	10/27/2022	-	858.07	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S204	SSHS-IRM5A2-A1N-S204	10/27/2022	-	854.99	-	854.99	2 - 4 ft	3.05 ft	1801470202	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-S205	SSHS-IRM5A2-A1N-S205	10/27/2022	-	855.06	-	855.06	2 - 4 ft	2.96 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S206	SSHS-IRM5A2-A1N-S206	10/27/2022	-	854.98	-	854.98	2 - 4 ft	3.09 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S207	SSHS-IRM5A2-A1N-S207	10/27/2022	-	854.91	-	854.91	2 - 4 ft	2.77 ft	1801470202	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A1N-S208	SSHS-IRM5A2-A1N-S208	10/27/2022	-	854.63	-	854.63	2 - 4 ft	2.65 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S209	SSHS-IRM5A2-A1N-S209	10/27/2022	-	854.14	-	854.14	2 - 4 ft	2.75 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-S210	SSHS-IRM5A2-A1N-S210	10/27/2022	-	854.09	-	854.09	2 - 4 ft	2.6 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B200	SSHS-IRM5A2-A1N-B200	10/27/2022	-	858.06	-	854.56	2 - 4 ft	3.49 ft	1801470202	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1N-B201	SSHS-IRM5A2-A1N-B201	10/27/2022	-	857.57	-	854.72	2 - 4 ft	2.85 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B202	SSHS-IRM5A2-A1N-B202	10/27/2022	-	857.72	-	854.67	2 - 4 ft	3.05 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B203	SSHS-IRM5A2-A1N-B203	10/27/2022	-	857.98	-	854.92	2 - 4 ft	3.06 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B204	SSHS-IRM5A2-A1N-B204	10/27/2022	-	857.20	-	854.40	2 - 4 ft	2.8 ft	1801470202	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-B205	SSHS-IRM5A2-A1N-B205	10/27/2022	-	857.26	-	854.34	2 - 4 ft	2.92 ft	1801470201	Not Excavated						
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-DUP253	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated						
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-DUP251	10/28/2022	-	858.15	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-S200A	SSHS-IRM5A2-A1N-S200A	10/28/2022	-	855.67	-	855.67	2 - 4 ft	2.44 ft	1801471322	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1N-S200	SSHS-IRM5A2-A1N-S200	10/28/2022	-	855.75	-	855.75	2 - 4 ft	2.4 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-S201	SSHS-IRM5A2-A1N-S201	10/28/2022	-	855.53	-	855.53	2 - 4 ft	2.49 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-S202	SSHS-IRM5A2-A1N-S202	10/28/2022	-	855.40	-	855.40	2 - 4 ft	2.58 ft	1801471322	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.025 U	< 0.022 U
Northern Athletic Field	A1N-S203	SSHS-IRM5A2-A1N-S203	10/28/2022	-	855.41	-	855.41	2 - 4 ft	2.62 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-B209	SSHS-IRM5A2-A1N-B209	10/28/2022	-	856.96	-	854.09	2 - 4 ft	2.87 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-B210	SSHS-IRM5A2-A1N-B210	10/28/2022	-	857.06	-	854.03	2 - 4 ft	3.03 ft	1801471322	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1N-B216	SSHS-IRM5A2-A1N-B216	10/28/2022	-	858.10	-	855.57	2 - 4 ft	2.52 ft	1801471321	Not Excavated						
Northern Athletic Field	A1N-B220	SSHS-IRM5A2-A1N-B220	10/28/2022	-	858.09	-	855.64	2 - 4 ft	2.45 ft	1801471331	Not Excavated						
Northern Athletic Field	A1N-B221	SSHS-IRM5A2-A1N-B221	10/28/2022	-	856.52	-	853.78	2 - 4 ft	2.74 ft	1801471331	Not Excavated						
Northern Athletic Field	A1N-B224	SSHS-IRM5A2-A1N-B224	10/28/2022	-	857.06	-	854.46	2 - 4 ft	2.6 ft	1801471331	Not Excavated						
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-DUP255	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-S201	SSHS-IRM5A2-A2N-S201	11/2/2022	-	851.32	-	851.32	2 - 4 ft	2.94 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-S202	SSHS-IRM5A2-A2N-S202	11/2/2022	-	851.54	-	851.54	2 - 4 ft	2.87 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-S203	SSHS-IRM5A2-A2N-S203	11/2/2022	-	851.66	-	851.66	2 - 4 ft	3.09 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-S204	SSHS-IRM5A2-A2N-S204	11/2/2022	-	852.08	-	852.08	2 - 4 ft	3.02 ft	1801473062	Not Excavated	< 0.043 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A2N-B201	SSHS-IRM5A2-A2N-B201	11/2/2022	-	854.24	-	851.02	2 - 4 ft	3.22 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-B202	SSHS-IRM5A2-A2N-B202	11/2/2022	-	853.96	-	850.91	2 - 4 ft	3.04 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-B205	SSHS-IRM5A2-A2N-B205	11/2/2022	-	854.55	-	851.74	2 - 4 ft	2.82 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-B206	SSHS-IRM5A2-A2N-B206	11/2/2022	-	854.22	-	851.08	2 - 4 ft	3.13 ft	1801473062	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A2N-B207	SSHS-IRM5A2-A2N-B207	11/2/2022	-	854.01	-	851.08	2 - 4 ft	2.94 ft	1801473061	Not Excavated						
Northern Athletic Field	A2N-B211	SSHS-IRM5A2-A2N-B211	11/2/2022	-	854.32	-	851.41	2 - 4 ft	2.91 ft	1801473061	Not Excavated						
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-DUP256	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473872	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473871	Not Excavated						
Northern Athletic Field	A2N-B213	SSHS-IRM5A2-A2N-B213	11/3/2022	-	854.94	-	851.68	2 - 4 ft	3.26 ft	1801473872	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated		< 31 U							
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473872	Not Excavated				< 0.049 U	< 0.039 U	0.19 BJ	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated		< 32 U							
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473872	Not Excavated				< 0.048 U	< 0.038 U	0.072 BJ	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated		< 30 U							
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated		< 30 U							
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473872	Not Excavated				< 0.050 U	< 0.040 U	0.27 B	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated		< 33 U							
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated		< 34 U							
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated		< 32 U							
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated		< 34 U							
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475242	Not Excavated				< 0.054 U	< 0.043 U	0.21 BJ	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated		< 33 U							
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated		< 65 U							
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475242	Not Excavated				< 0.053 U	< 0.042 U	0.28 B	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated		< 31 U							
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475242	Not Excavated				< 0.050 U	< 0.040 U	0.26 B	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated		< 34 U							
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated		< 33 U							
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated		< 36 U							
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated		< 32 U							
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated		< 35 U							
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated		< 35 U							
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated		< 34 U							
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475252	Not Excavated				< 0.056 U	< 0.044 U	0.25 B	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated		< 35 U							
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated		< 32 U							
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated		< 34 U							
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated		< 34 U							
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476082	Not Excavated				< 0.053 U	< 0.042 U	0.61	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated		< 38 U							
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated		< 33 U							
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485022	Not Excavated				< 0.052 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated		< 35 U							
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485022	Not Excavated				< 0.056 U	< 0.044 U	0.14 J	< 0.060 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487442	Not Excavated				< 0.051 U	< 0.040 U	0.25	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated		< 32 U							
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487442	Not Excavated				< 0.053 U	< 0.042 U	0.34	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487862	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487862	Not Excavated				< 0.056 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.056 U	< 0.035 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473872	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	0.027 J	< 0.033 U	0.11 J	< 0.054 U	< 0.042 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473872	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	0.023 J	< 0.033 U	0.12 J	< 0.053 U	< 0.041 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated									
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473872	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	0.037 J	< 0.023 U	< 0.035 U	0.11 J	< 0.055 U	< 0.043 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated									
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475242	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475242	Not Excavated	< 0.054 U	< 0.042 U	0.040 J	1.5	< 0.024 U	< 0.036 U	< 0.047 U	0.15 J	< 0.045 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475242	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	0.060 J	0.033 J	< 0.034 U	< 0.22 U	0.11 J	< 0.043 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated									
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated									
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated									
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated									
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475252	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	0.057 J	< 0.026 U	< 0.038 U	< 0.050 U	< 0.062 U	< 0.048 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated									
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated									
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated									
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated									
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476082	Not Excavated	< 0.054 U	0.098 J	< 0.032 U	0.11 J	0.078 J	< 0.036 U	0.83	0.35	0.085 J
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated									
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485022	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	0.041 J	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485022	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	0.042 J	< 0.026 U	< 0.038 U	< 0.050 U	< 0.062 U	0.057 J
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated									
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated									
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487442	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.10 J	< 0.056 U	0.051 J
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487442	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	0.038 J	< 0.024 U	< 0.036 U	0.20 J	< 0.058 U	0.046 J
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated									
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487862	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated									
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487862	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	0.044 J	< 0.038 U	< 0.050 U	0.062 J	< 0.048 U

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-S211	SSHS-IRM5A2-A1N-S211	11/3/2022	-	853.52	-	853.52	2 - 4 ft	2.57 ft	1801473872	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1N-S212	SSHS-IRM5A2-A1N-S212	11/3/2022	-	852.93	-	852.93	2 - 4 ft	2.7 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-S213	SSHS-IRM5A2-A1N-S213	11/3/2022	-	852.57	-	852.57	2 - 4 ft	2.81 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B226	SSHS-IRM5A2-A1N-B226	11/3/2022	-	856.28	-	853.49	2 - 4 ft	2.78 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B227	SSHS-IRM5A2-A1N-B227	11/3/2022	-	855.68	-	852.79	2 - 4 ft	2.89 ft	1801473872	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1N-B228	SSHS-IRM5A2-A1N-B228	11/3/2022	-	855.90	-	853.05	2 - 4 ft	2.86 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B230	SSHS-IRM5A2-A1N-B230	11/3/2022	-	855.53	-	852.68	2 - 4 ft	2.85 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473871	Not Excavated						
Northern Athletic Field	A1N-B231	SSHS-IRM5A2-A1N-B231	11/3/2022	-	855.93	-	853.09	2 - 4 ft	2.84 ft	1801473872	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-DUP258	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-DUP259	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated						
Northern Athletic Field	A1N-S214	SSHS-IRM5A2-A1N-S214	11/7/2022	-	852.58	-	852.58	2 - 4 ft	2.7 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-S215	SSHS-IRM5A2-A1N-S215	11/7/2022	-	852.17	-	852.17	2 - 4 ft	2.95 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-S216	SSHS-IRM5A2-A1N-S216	11/7/2022	-	852.15	-	852.15	2 - 4 ft	2.72 ft	1801475242	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A1N-B235	SSHS-IRM5A2-A1N-B235	11/7/2022	-	855.26	-	852.44	2 - 4 ft	2.81 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B236	SSHS-IRM5A2-A1N-B236	11/7/2022	-	855.55	-	852.69	2 - 4 ft	2.86 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B237	SSHS-IRM5A2-A1N-B237	11/7/2022	-	855.82	-	853.05	2 - 4 ft	2.77 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B238	SSHS-IRM5A2-A1N-B238	11/7/2022	-	856.14	-	853.33	2 - 4 ft	2.81 ft	1801475242	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A1N-B239	SSHS-IRM5A2-A1N-B239	11/7/2022	-	856.53	-	853.88	2 - 4 ft	2.65 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B241	SSHS-IRM5A2-A1N-B241	11/7/2022	-	855.26	-	852.40	2 - 4 ft	2.86 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B242	SSHS-IRM5A2-A1N-B242	11/7/2022	-	855.47	-	852.70	2 - 4 ft	2.76 ft	1801475242	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-B243	SSHS-IRM5A2-A1N-B243	11/7/2022	-	855.67	-	852.91	2 - 4 ft	2.75 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B244	SSHS-IRM5A2-A1N-B244	11/7/2022	-	855.96	-	853.15	2 - 4 ft	2.81 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B245	SSHS-IRM5A2-A1N-B245	11/7/2022	-	856.19	-	853.47	2 - 4 ft	2.72 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B247	SSHS-IRM5A2-A1N-B247	11/7/2022	-	855.12	-	851.83	2 - 4 ft	3.29 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B248	SSHS-IRM5A2-A1N-B248	11/7/2022	-	855.27	-	852.47	2 - 4 ft	2.8 ft	1801475241	Not Excavated						
Northern Athletic Field	A1N-B249	SSHS-IRM5A2-A1N-B249	11/7/2022	-	855.45	-	852.80	2 - 4 ft	2.65 ft	1801475251	Not Excavated						
Northern Athletic Field	A1N-B250	SSHS-IRM5A2-A1N-B250	11/7/2022	-	855.22	-	852.55	2 - 4 ft	2.67 ft	1801475251	Not Excavated						
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475251	Not Excavated						
Northern Athletic Field	A1N-B251	SSHS-IRM5A2-A1N-B251	11/7/2022	-	855.41	-	852.71	2 - 4 ft	2.7 ft	1801475252	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-DUP260	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated						
Northern Athletic Field	A6-S629-S1	SSHS-IRM5A2-A6-S629-S1	11/8/2022	-	854.59	-	850.79	2 - 4 ft	3.8 ft	1801476081	Not Excavated						
Northern Athletic Field	A6-LP-S3	SSHS-IRM5A2-A6-LP-S3	11/8/2022	-	854.16	-	851.62	2 - 4 ft	2.54 ft	1801476081	Not Excavated						
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476081	Not Excavated						
Northern Athletic Field	A6-LP-B1	SSHS-IRM5A2-A6-LP-B1	11/8/2022	-	854.78	-	852.57	2 - 4 ft	2.21 ft	1801476082	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6-LP-B2	SSHS-IRM5A2-A6-LP-B2	11/8/2022	-	854.47	-	851.82	2 - 4 ft	2.65 ft	1801476081	Not Excavated						
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-DUP261	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-S200	SSHS-IRM5A2-A6N-S200	11/29/2022	-	852.24	-	852.24	2 - 4 ft	2.62 ft	1801485022	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6N-S201	SSHS-IRM5A2-A6N-S201	11/29/2022	-	852.19	-	852.19	2 - 4 ft	2.51 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-B204	SSHS-IRM5A2-A6N-B204	11/29/2022	-	854.97	-	852.02	2 - 4 ft	2.96 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-B205	SSHS-IRM5A2-A6N-B205	11/29/2022	-	854.69	-	851.52	2 - 4 ft	3.17 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-B207	SSHS-IRM5A2-A6N-B207	11/29/2022	-	855.14	-	852.44	2 - 4 ft	2.71 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-B208	SSHS-IRM5A2-A6N-B208	11/29/2022	-	855.33	-	852.82	2 - 4 ft	2.51 ft	1801485022	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	0.25	< 0.027 U
Northern Athletic Field	A6N-B210	SSHS-IRM5A2-A6N-B210	11/29/2022	-	854.93	-	852.11	2 - 4 ft	2.82 ft	1801485021	Not Excavated						
Northern Athletic Field	A6N-S403	SSHS-IRM5A2-A6N-S403	12/1/2022	-	854.88	-	850.89	2 - 4 ft	3.99 ft	1801486621	Not Excavated						
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-B211	SSHS-IRM5A2-A6N-B211	12/2/2022	-	854.86	-	852.06	2 - 4 ft	2.8 ft	1801487442	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A6N-B212	SSHS-IRM5A2-A6N-B212	12/2/2022	-	855.12	-	852.40	2 - 4 ft	2.71 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-B214	SSHS-IRM5A2-A6N-B214	12/2/2022	-	855.15	-	852.50	2 - 4 ft	2.65 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-B215	SSHS-IRM5A2-A6N-B215	12/2/2022	-	855.35	-	852.79	2 - 4 ft	2.56 ft	1801487442	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	0.032 J	< 0.025 U
Northern Athletic Field	A6N-B216	SSHS-IRM5A2-A6N-B216	12/2/2022	-	855.31	-	852.59	2 - 4 ft	2.71 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487861	Not Excavated						
Northern Athletic Field	A6N-B218	SSHS-IRM5A2-A6N-B218	12/5/2022	-	855.51	-	852.61	2 - 4 ft	2.9 ft	1801487862	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487861	Not Excavated						
Northern Athletic Field	A6N-B224	SSHS-IRM5A2-A6N-B224	12/5/2022	-	855.78	-	852.08	2 - 4 ft	3.7 ft	1801487862	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		< 32 U							
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated		< 33 U							
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated		< 38 U							
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492042	Not Excavated				< 0.054 U	< 0.043 U	0.12 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated		< 32 U							
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492042	Not Excavated				< 0.051 U	< 0.040 U	0.28	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493712	Not Excavated				< 0.055 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated		< 30 U							
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated		< 35 U							
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521012	Not Excavated				< 0.049 U	< 0.039 U	0.059 BJ	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521012	Not Excavated				< 0.051 U	< 0.040 U	0.073 BJ	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521012	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated	< 110 U								
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 250 U								
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 120 U								
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523792	Not Excavated				< 0.052 U	< 0.042 U	0.27 B	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated	< 350 U								
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated	< 120 U								
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated	< 120 U								
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523782	Not Excavated				< 0.056 U	< 0.044 U	0.40 B	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated	< 120 U								
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated	< 120 U								
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated	< 120 U								
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated	< 110 U								
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated	< 260 U								
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523782	Not Excavated				< 0.057 U	< 0.045 U	0.59 B	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated	< 120 U								
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated	< 110 U								
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523782	Not Excavated				< 0.051 U	< 0.040 U	0.25 B	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated	< 110 U								
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated	< 110 U								
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated	< 130 U								
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated	< 110 U								
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523792	Not Excavated				< 0.050 U	< 0.040 U	0.38 B	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 120 U								
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated	< 110 U								
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523792	Not Excavated				< 0.051 U	< 0.040 U	0.23 B	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525562	Not Excavated				< 0.055 U	< 0.043 U	0.19 BJ	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated	< 110 U								

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated									
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated									
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated									
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated									
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492042	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.046 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492042	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	0.078 J	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated									
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated									
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493712	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.060 U	< 0.047 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated									
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated									
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521012	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.080 J	0.078 J	< 0.042 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521012	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.090 J	< 0.056 U	< 0.044 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated									
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521012	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated									
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated									
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523792	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	0.071 J
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523782	Not Excavated	< 0.057 U	0.065 J	< 0.034 U	0.072 J	0.034 J	< 0.039 U	0.18 BJ	0.16 J	0.096 J
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523782	Not Excavated	< 0.058 U	< 0.045 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.039 U	< 0.051 U	0.080 J	< 0.049 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523782	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	0.076 J
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated									
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated									
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523792	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.15 BJ	0.079 J	< 0.043 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated									
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated									
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated									
Northern Athletic Field	RS-BOT47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523792	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525562	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	0.22 J	< 0.061 U	< 0.047 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6N-B225	SSHS-IRM5A2-A6N-B225	12/5/2022	-	856.04	-	853.30	2 - 4 ft	2.73 ft	1801487861	Not Excavated						
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-A6N-B226	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated						
Northern Athletic Field	A6N-B226	SSHS-IRM5A2-DUP265	12/5/2022	-	856.10	-	852.93	2 - 4 ft	3.18 ft	1801487861	Not Excavated						
Northern Athletic Field	A6N-MO1-B1	SSHS-IRM5A2-A6N-MO-B1	12/8/2022	-	855.55	-	852.47	2 - 4 ft	3.08 ft	1801490381	Not Excavated						
Northern Athletic Field	A6N-B228	SSHS-IRM5A2-A6N-B228	12/9/2022	-	856.70	-	852.94	2 - 4 ft	3.76 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B213-S1	SSHS-IRM5A2-A6N-B213-S1	12/10/2022	-	855.42	-	851.53	2 - 4 ft	3.89 ft	1801492042	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.040 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6N-B213-S2	SSHS-IRM5A2-A6N-B213-S2	12/10/2022	-	855.18	-	851.29	2 - 4 ft	3.89 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B245	SSHS-IRM5A2-A6N-B245	12/10/2022	-	855.48	-	852.86	2 - 4 ft	2.62 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B246	SSHS-IRM5A2-A6N-B246	12/10/2022	-	855.55	-	852.96	2 - 4 ft	2.59 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B247	SSHS-IRM5A2-A6N-B247	12/10/2022	-	855.59	-	852.92	2 - 4 ft	2.67 ft	1801492042	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-DUP274	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated						
Northern Athletic Field	A6N-S800-S27	SSHS-IRM5A2-A6N-S800-S27	12/14/2022	-	855.22	-	851.29	2 - 4 ft	3.94 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493711	Not Excavated						
Northern Athletic Field	A6N-B223A	SSHS-IRM5A2-A6N-B223A	12/14/2022	-	855.64	-	852.62	2 - 4 ft	3.02 ft	1801493712	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6N-B222A	SSHS-IRM5A2-A6N-B222A	12/14/2022	-	855.74	-	852.89	2 - 4 ft	2.85 ft	1801493711	Not Excavated						
Northern Athletic Field	A6N-B219A	SSHS-IRM5A2-A6N-B219A	12/14/2022	-	855.43	-	852.28	2 - 4 ft	3.15 ft	1801493711	Not Excavated						
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-DUP276	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B252	SSHS-IRM5A2-A1N-B252	2/15/2023	-	856.76	-	853.33	2 - 4 ft	3.43 ft	1801521012	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-B253	SSHS-IRM5A2-A1N-B253	2/15/2023	-	856.54	-	853.44	2 - 4 ft	3.1 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B254	SSHS-IRM5A2-A1N-B254	2/15/2023	-	856.59	-	853.16	2 - 4 ft	3.44 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B255	SSHS-IRM5A2-A1N-B255	2/15/2023	-	856.95	-	853.70	2 - 4 ft	3.25 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B256	SSHS-IRM5A2-A1N-B256	2/15/2023	-	856.70	-	853.68	2 - 4 ft	3.02 ft	1801521012	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A1N-B257	SSHS-IRM5A2-A1N-B257	2/15/2023	-	856.47	-	853.57	2 - 4 ft	2.9 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B258	SSHS-IRM5A2-A1N-B258	2/15/2023	-	856.83	-	853.87	2 - 4 ft	2.96 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B259	SSHS-IRM5A2-A1N-B259	2/15/2023	-	857.04	-	853.79	2 - 4 ft	3.25 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521011	Not Excavated						
Northern Athletic Field	A1N-B260	SSHS-IRM5A2-A1N-B260	2/15/2023	-	857.15	-	853.89	2 - 4 ft	3.27 ft	1801521012	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A1N-B261	SSHS-IRM5A2-A1N-B261	2/15/2023	-	857.03	-	853.91	2 - 4 ft	3.12 ft	1801521011	Not Excavated						
Northern Athletic Field	A6-B262	SSHS-IRM5A2-DUP277	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated						
Northern Athletic Field	A6-B272	SSHS-IRM5A2-DUP278	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523792	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B256	SSHS-IRM5A2-A6-B256	2/21/2023	-	856.29	-	853.23	2 - 4 ft	3.07 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B257	SSHS-IRM5A2-A6-B257	2/21/2023	-	856.34	-	853.40	2 - 4 ft	2.95 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B258	SSHS-IRM5A2-A6-B258	2/21/2023	-	856.68	-	853.62	2 - 4 ft	3.06 ft	1801523782	Not Excavated	< 0.043 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A6-B259	SSHS-IRM5A2-A6-B259	2/21/2023	-	855.22	-	851.99	2 - 4 ft	3.23 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B260	SSHS-IRM5A2-A6-B260	2/21/2023	-	856.43	-	853.00	2 - 4 ft	3.44 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B261	SSHS-IRM5A2-A6-B261	2/21/2023	-	856.94	-	853.94	2 - 4 ft	3.01 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B262	SSHS-IRM5A2-A6-B262	2/21/2023	-	854.40	-	851.66	2 - 4 ft	2.74 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B263	SSHS-IRM5A2-A6-B263	2/21/2023	-	854.69	-	851.67	2 - 4 ft	3.02 ft	1801523782	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A6-B267	SSHS-IRM5A2-A6-B267	2/21/2023	-	853.32	-	849.87	2 - 4 ft	3.45 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B268	SSHS-IRM5A2-A6-B268	2/21/2023	-	853.93	-	850.52	2 - 4 ft	3.41 ft	1801523782	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A6-B269	SSHS-IRM5A2-A6-B269	2/21/2023	-	853.86	-	850.93	2 - 4 ft	2.93 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B270	SSHS-IRM5A2-A6-B270	2/21/2023	-	854.66	-	851.58	2 - 4 ft	3.08 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B271	SSHS-IRM5A2-A6-B271	2/21/2023	-	854.89	-	851.68	2 - 4 ft	3.21 ft	1801523781	Not Excavated						
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523791	Not Excavated						
Northern Athletic Field	A6-B272	SSHS-IRM5A2-A6-B272	2/21/2023	-	855.12	-	852.17	2 - 4 ft	2.94 ft	1801523792	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B273	SSHS-IRM5A2-A6-B273	2/21/2023	-	855.52	-	852.54	2 - 4 ft	2.98 ft	1801523791	Not Excavated						
Northern Athletic Field	A6-B274	SSHS-IRM5A2-A6-B274	2/21/2023	-	855.19	-	852.21	2 - 4 ft	2.98 ft	1801523791	Not Excavated						
Northern Athletic Field	RS-B0T47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523791	Not Excavated						
Northern Athletic Field	RS-B0T47	SSHS-IRM5A2-RS-B0T47	2/21/2023	-	853.32	-	850.17	2 - 4 ft	3.15 ft	1801523792	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-DUP279	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B262	SSHS-IRM5A2-A1N-B262	2/23/2023	-	857.00	-	854.34	2 - 4 ft	2.67 ft	1801525562	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A1N-B263	SSHS-IRM5A2-A1N-B263	2/23/2023	-	856.33	-	853.32	2 - 4 ft	3.01 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B264	SSHS-IRM5A2-A1N-B264	2/23/2023	-	856.69	-	853.73	2 - 4 ft	2.96 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B265	SSHS-IRM5A2-A1N-B265	2/23/2023	-	857.05	-	854.24	2 - 4 ft	2.8 ft	1801525561	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525562	Not Excavated				< 0.052 U	< 0.041 U	0.053 BJ	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated	< 130 U								
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525562	Not Excavated				< 0.057 U	< 0.045 U	0.057 BJ	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526442	Not Excavated				< 0.053 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526442	Not Excavated				< 0.052 U	< 0.041 U	0.11 JBT	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 120 U								
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 140 U								
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526802	Not Excavated				< 0.051 U	< 0.040 U	0.065 BJ	0.10 BJ	< 0.051 U	< 0.032 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526802	Not Excavated				< 0.050 U	< 0.039 U	0.085 BJ	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526802	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526802	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated	< 110 U								
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated	< 130 U								
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated	< 110 U								
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated	< 120 U								
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556072	Not Excavated				< 0.052 U	< 0.041 U	0.070 J	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated	< 130 U								
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 120 U								
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated	< 120 U								
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562132	Not Excavated				< 0.054 U	< 0.043 U	0.065 J	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated	< 110 U								
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated	< 140 U								
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated	< 120 U								
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated	< 130 U								
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562132	Not Excavated				< 0.060 U	< 0.048 U	0.11 J	< 0.065 U	< 0.060 U	< 0.038 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated	< 110 U								
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated	< 120 U								
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated	< 120 U								
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated	< 110 U								
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562132	Not Excavated				< 0.053 U	< 0.042 U	0.062 J	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated	< 110 U								
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated	< 110 U								
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525562	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.080 J	< 0.057 U	< 0.044 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated									
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525562	Not Excavated	< 0.059 U	< 0.045 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.039 U	0.052 J	< 0.063 U	< 0.049 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526442	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526442	Not Excavated	< 0.054 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated									
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated									
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated									
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated									
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526802	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.047 J	< 0.056 U	< 0.043 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated									
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated									
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526802	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated									
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526802	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	0.69
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526802	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated									
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated									
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated									
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated									
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated									
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556072	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated									
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562132	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	0.36	0.071 J	< 0.046 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562132	Not Excavated	< 0.062 U	< 0.048 U	< 0.036 U	< 0.039 U	< 0.028 U	< 0.041 U	0.089 J	0.069 J	< 0.051 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562132	Not Excavated	< 0.055 U	0.042 J	< 0.032 U	0.051 J	0.029 J	< 0.037 U	< 0.048 U	0.12 J	< 0.046 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated									
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B266	SSHS-IRM5A2-A1N-B266	2/23/2023	-	856.30	-	853.27	2 - 4 ft	3.03 ft	1801525562	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A1N-B267	SSHS-IRM5A2-A1N-B267	2/23/2023	-	856.77	-	853.71	2 - 4 ft	3.06 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B268	SSHS-IRM5A2-A1N-B268	2/23/2023	-	857.04	-	854.05	2 - 4 ft	2.99 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B269	SSHS-IRM5A2-A1N-B269	2/23/2023	-	856.88	-	853.72	2 - 4 ft	3.16 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525561	Not Excavated						
Northern Athletic Field	A1N-B270	SSHS-IRM5A2-A1N-B270	2/23/2023	-	857.16	-	854.27	2 - 4 ft	2.89 ft	1801525562	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.028 U
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-DUP280	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-DUP281	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B271	SSHS-IRM5A2-A1N-B271	2/24/2023	-	857.40	-	854.39	2 - 4 ft	3.01 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B272	SSHS-IRM5A2-A1N-B272	2/24/2023	-	857.52	-	854.43	2 - 4 ft	3.09 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B273	SSHS-IRM5A2-A1N-B273	2/24/2023	-	857.91	-	854.50	2 - 4 ft	3.41 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B274	SSHS-IRM5A2-A1N-B274	2/24/2023	-	857.68	-	854.63	2 - 4 ft	3.05 ft	1801526442	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A1N-B275	SSHS-IRM5A2-A1N-B275	2/24/2023	-	857.69	-	854.87	2 - 4 ft	2.82 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B276	SSHS-IRM5A2-A1N-B276	2/24/2023	-	857.71	-	854.54	2 - 4 ft	3.16 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B277	SSHS-IRM5A2-A1N-B277	2/24/2023	-	858.05	-	854.92	2 - 4 ft	3.13 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B278	SSHS-IRM5A2-A1N-B278	2/24/2023	-	857.98	-	854.98	2 - 4 ft	2.99 ft	1801526442	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A1N-B279	SSHS-IRM5A2-A1N-B279	2/24/2023	-	857.96	-	855.27	2 - 4 ft	2.69 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B280	SSHS-IRM5A2-A1N-B280	2/24/2023	-	858.00	-	855.27	2 - 4 ft	2.73 ft	1801526441	Not Excavated						
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-DUP282	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-DUP283	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated						
Northern Athletic Field	A1N-B281	SSHS-IRM5A2-A1N-B281	2/27/2023	-	858.10	-	855.19	2 - 4 ft	2.91 ft	1801526801	Not Excavated						
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526801	Not Excavated						
Northern Athletic Field	A1N-B282	SSHS-IRM5A2-A1N-B282	2/27/2023	-	857.77	-	854.84	2 - 4 ft	2.92 ft	1801526802	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A1N-B284	SSHS-IRM5A2-A1N-B284	2/27/2023	-	857.52	-	854.80	2 - 4 ft	2.72 ft	1801526801	Not Excavated						
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526801	Not Excavated						
Northern Athletic Field	A1N-B286	SSHS-IRM5A2-A1N-B286	2/27/2023	-	857.35	-	854.63	2 - 4 ft	2.72 ft	1801526802	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1N-B287	SSHS-IRM5A2-A1N-B287	2/27/2023	-	857.12	-	854.38	2 - 4 ft	2.74 ft	1801526801	Not Excavated						
Northern Athletic Field	A1N-B288	SSHS-IRM5A2-A1N-B288	2/27/2023	-	857.24	-	854.20	2 - 4 ft	3.04 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B269A	SSHS-IRM5A2-A6-B269A	2/27/2023	-	856.97	-	853.24	2 - 4 ft	3.73 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B270A	SSHS-IRM5A2-A6-B270A	2/27/2023	-	854.43	-	851.52	2 - 4 ft	2.91 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B271A	SSHS-IRM5A2-A6-B271A	2/27/2023	-	854.19	-	851.28	2 - 4 ft	2.91 ft	1801526802	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B272A	SSHS-IRM5A2-A6-B272A	2/27/2023	-	853.87	-	851.23	2 - 4 ft	2.64 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B273A	SSHS-IRM5A2-A6-B273A	2/27/2023	-	853.33	-	850.46	2 - 4 ft	2.87 ft	1801526802	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B274A	SSHS-IRM5A2-A6-B274A	2/27/2023	-	853.79	-	851.15	2 - 4 ft	2.64 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B275	SSHS-IRM5A2-A6-B275	2/27/2023	-	854.43	-	851.36	2 - 4 ft	3.07 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B276	SSHS-IRM5A2-A6-B276	2/27/2023	-	855.20	-	852.02	2 - 4 ft	3.19 ft	1801526801	Not Excavated						
Northern Athletic Field	A6N-B248	SSHS-IRM5A2-A6N-B248	4/25/2023	-	854.96	-	851.98	2 - 4 ft	2.98 ft	1801556071	Not Excavated						
Northern Athletic Field	A6N-B249	SSHS-IRM5A2-A6N-B249	4/25/2023	-	854.92	-	851.87	2 - 4 ft	3.05 ft	1801556071	Not Excavated						
Northern Athletic Field	A6N-B250	SSHS-IRM5A2-A6N-B250	4/25/2023	-	854.88	-	851.73	2 - 4 ft	3.15 ft	1801556071	Not Excavated						
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556071	Not Excavated						
Northern Athletic Field	A6N-B251	SSHS-IRM5A2-A6N-B251	4/25/2023	-	854.99	-	851.90	2 - 4 ft	3.09 ft	1801556072	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6N-B252	SSHS-IRM5A2-A6N-B252	4/25/2023	-	855.05	-	851.93	2 - 4 ft	3.12 ft	1801556071	Not Excavated						
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-DUP299	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-B1	SSHS-IRM5A2-AREA A-B1	5/5/2023	-	858.26	-	855.52	2 - 4 ft	2.75 ft	1801562132	Not Excavated	< 0.041 U	< 0.024 U	< 0.047 U	0.040 J	0.22	< 0.026 U
Northern Athletic Field	AREA A-B2	SSHS-IRM5A2-AREA A-B2	5/5/2023	-	858.05	-	855.24	2 - 4 ft	2.82 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-B3	SSHS-IRM5A2-AREA A-B3	5/5/2023	-	858.02	-	855.45	2 - 4 ft	2.57 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-B4	SSHS-IRM5A2-AREA A-B4	5/5/2023	-	858.48	-	855.65	2 - 4 ft	2.83 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-B5	SSHS-IRM5A2-AREA A-B5	5/5/2023	-	858.07	-	855.48	2 - 4 ft	2.59 ft	1801562132	Not Excavated	< 0.046 U	< 0.026 U	< 0.053 U	< 0.044 U	< 0.034 U	< 0.029 U
Northern Athletic Field	AREA A-S1	SSHS-IRM5A2-AREA A-S1	5/5/2023	-	858.10	-	855.23	2 - 4 ft	2.87 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA A-S2	SSHS-IRM5A2-AREA A-S2	5/5/2023	-	858.18	-	855.65	2 - 4 ft	2.54 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA B-B1	SSHS-IRM5A2-AREA B-B1	5/5/2023	-	858.22	-	855.34	2 - 4 ft	2.88 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA B-B2	SSHS-IRM5A2-AREA B-B2	5/5/2023	-	857.99	-	855.39	2 - 4 ft	2.61 ft	1801562132	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	AREA B-B3	SSHS-IRM5A2-AREA B-B3	5/5/2023	-	857.42	-	854.42	2 - 4 ft	3 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA B-B4	SSHS-IRM5A2-AREA B-B4	5/5/2023	-	857.19	-	854.08	2 - 4 ft	3.11 ft	1801562131	Not Excavated						
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563391	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563392	Not Excavated				< 0.046 U	< 0.037 U	0.15 J	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated	< 230 U								
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 110 U								
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564092	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated	< 110 U								
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated	< 110 U								
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated	< 110 U								
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564092	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572472	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589972	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590652	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590662	Not Excavated				< 0.050 U	< 0.040 U	0.057 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated	< 120 U								
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated	< 110 U								
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593502	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated	< 110 U								
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated	< 120 U								
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593502	Not Excavated				< 0.053 U	< 0.042 U	0.17 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594062	Not Excavated				< 0.050 U	< 0.039 U	< 0.31 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated	< 140 U								
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594062	Not Excavated				< 0.052 U	0.053 J	0.38	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594062	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594072	Not Excavated				< 0.056 U	< 0.044 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 3300 U								
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596502	Not Excavated				< 0.052 U	< 0.041 U	0.26	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563392	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.051 U	< 0.039 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated									
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated									
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564092	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated									
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated									
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated									
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564092	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated									
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572472	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	0.087 J	< 0.042 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589972	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590652	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.044 J	< 0.052 U	< 0.040 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590662	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated									
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated									
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593502	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated									
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated									
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593502	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.31	0.070 J	0.14 J
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated									
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594062	Not Excavated	< 0.051 U	< 0.039 U	0.11 J	< 0.032 U	< 0.023 U	< 0.034 U	0.53	0.19 J	< 0.53 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594062	Not Excavated	< 0.053 U	0.046 J	0.078 J	< 0.033 U	< 0.024 U	< 0.036 U	0.27	0.13 J	< 0.55 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594062	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594072	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.038 U	< 0.050 U	< 0.062 U	< 0.048 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596502	Not Excavated	< 0.053 U	0.067 J	< 0.032 U	0.091 J	0.046 J	< 0.036 U	0.64	0.37	0.071 J
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	AREA B-S1	SSHS-IRM5A2-AREA B-S1	5/9/2023	-	857.05	-	854.21	2 - 4 ft	2.84 ft	1801563392	Not Excavated	< 0.036 U	< 0.020 U	< 0.040 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	AREA C-B1	SSHS-IRM5A2-AREA C-B1	5/9/2023	-	856.55	-	853.60	2 - 4 ft	2.94 ft	1801563391	Not Excavated						
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated						
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-DUP302	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564092	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	AREA E-B1	SSHS-IRM5A2-AREA E-B1	5/10/2023	-	854.73	-	851.41	2 - 4 ft	3.32 ft	1801564091	Not Excavated						
Northern Athletic Field	AREA E-B2	SSHS-IRM5A2-AREA E-B2	5/10/2023	-	854.19	-	851.12	2 - 4 ft	3.08 ft	1801564091	Not Excavated						
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564091	Not Excavated						
Northern Athletic Field	AREA E-B3	SSHS-IRM5A2-AREA E-B3	5/10/2023	-	854.09	-	850.75	2 - 4 ft	3.34 ft	1801564092	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	AREA E-B4	SSHS-IRM5A2-AREA E-B4	5/10/2023	-	853.69	-	850.77	2 - 4 ft	2.92 ft	1801564091	Not Excavated						
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S1	SSHS-ISMP-NAF-IG-S1	5/30/2023	-	853.44	-	849.50	2 - 4 ft	3.94 ft	1801572472	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-UT-S3	SSHS-ISMP-NAF-UT-S3	7/10/2023	-	853.03	-	849.08	2 - 4 ft	3.95 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S4	SSHS-ISMP-NAF-UT-S4	7/10/2023	-	852.99	-	849.00	2 - 4 ft	3.99 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-B2	SSHS-ISMP-NAF-UT-B2	7/10/2023	-	853.00	-	848.99	2 - 4 ft	4 ft	1801589972	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-S10	SSHS-ISMP-NAF-UT-S10	7/11/2023	-	853.60	-	850.62	2 - 4 ft	2.98 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S13	SSHS-ISMP-NAF-UT-S13	7/11/2023	-	853.98	-	850.84	2 - 4 ft	3.14 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S15	SSHS-ISMP-NAF-UT-S15	7/11/2023	-	853.96	-	850.70	2 - 4 ft	3.26 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S17	SSHS-ISMP-NAF-UT-S17	7/11/2023	-	854.31	-	850.96	2 - 4 ft	3.35 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S19	SSHS-ISMP-NAF-UT-S19	7/11/2023	-	854.27	-	851.38	2 - 4 ft	2.89 ft	1801590652	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-UT-S21	SSHS-ISMP-NAF-UT-S21	7/11/2023	-	854.64	-	850.76	2 - 4 ft	3.88 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S22	SSHS-ISMP-NAF-UT-S22	7/11/2023	-	854.62	-	851.58	2 - 4 ft	3.04 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S24	SSHS-ISMP-NAF-UT-S24	7/11/2023	-	854.53	-	851.72	2 - 4 ft	2.81 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S26	SSHS-ISMP-NAF-UT-S26	7/11/2023	-	854.55	-	851.58	2 - 4 ft	2.97 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S28	SSHS-ISMP-NAF-UT-S28	7/11/2023	-	854.33	-	850.40	2 - 4 ft	3.93 ft	1801590662	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-UT-S29	SSHS-ISMP-NAF-UT-S29	7/11/2023	-	854.25	-	850.29	2 - 4 ft	3.96 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S31	SSHS-ISMP-NAF-UT-S31	7/11/2023	-	854.11	-	850.93	2 - 4 ft	3.19 ft	1801590661	Not Excavated						
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593501	Not Excavated						
Northern Athletic Field	AREAF-B1	SSHS-IRM5A2-AREAF-B1	7/14/2023	-	856.68	-	853.85	2 - 4 ft	2.83 ft	1801593502	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	AREAF-B3	SSHS-IRM5A2-AREAF-B3	7/14/2023	-	856.32	-	853.63	2 - 4 ft	2.69 ft	1801593501	Not Excavated						
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593501	Not Excavated						
Northern Athletic Field	AREAF-B5	SSHS-IRM5A2-AREAF-B5	7/14/2023	-	856.44	-	853.65	2 - 4 ft	2.79 ft	1801593502	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	AREAF-S3	SSHS-IRM5A2-AREAF-S3	7/14/2023	-	856.82	-	853.99	2 - 4 ft	2.84 ft	1801593501	Not Excavated						
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S35	SSHS-ISMP-NAF-UT-S35	7/17/2023	-	856.38	-	853.46	2 - 4 ft	2.92 ft	1801594062	Not Excavated	< 0.038 U	0.030 J	< 0.044 U	< 0.036 U	0.061 BJ	< 0.024 U
Northern Athletic Field	NAF-UT-S36	SSHS-ISMP-NAF-UT-S36	7/17/2023	-	856.38	-	852.43	2 - 4 ft	3.95 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S38	SSHS-ISMP-NAF-UT-S38	7/17/2023	-	856.36	-	852.99	2 - 4 ft	3.37 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S40	SSHS-ISMP-NAF-UT-S40	7/17/2023	-	856.58	-	854.58	2 - 4 ft	2 ft	1801594062	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-S41	SSHS-ISMP-NAF-UT-S41	7/17/2023	-	856.54	-	853.05	2 - 4 ft	3.48 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S44	SSHS-ISMP-NAF-UT-S44	7/17/2023	-	856.28	-	852.58	2 - 4 ft	3.7 ft	1801594062	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	NAF-UT-S46	SSHS-ISMP-NAF-UT-S46	7/17/2023	-	856.28	-	853.16	2 - 4 ft	3.12 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S53	SSHS-ISMP-NAF-UT-S53	7/17/2023	-	854.38	-	850.59	2 - 4 ft	3.79 ft	1801594072	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	NAF-UT-S54	SSHS-ISMP-NAF-UT-S54	7/17/2023	-	854.33	-	850.52	2 - 4 ft	3.81 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-B16	SSHS-ISMP-NAF-UT-B16	7/17/2023	-	854.30	-	850.52	2 - 4 ft	3.78 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S64	SSHS-ISMP-NAF-UT-S64	7/18/2023	-	856.81	-	852.95	2 - 4 ft	3.86 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S65	SSHS-ISMP-NAF-UT-S65	7/18/2023	-	856.80	-	852.98	2 - 4 ft	3.82 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S66	SSHS-ISMP-NAF-UT-S66	7/18/2023	-	856.34	-	852.65	2 - 4 ft	3.69 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S67	SSHS-ISMP-NAF-UT-S67	7/18/2023	-	856.30	-	852.73	2 - 4 ft	3.57 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-B20	SSHS-ISMP-NAF-UT-B20	7/18/2023	-	856.33	-	852.39	2 - 4 ft	3.94 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S68	SSHS-ISMP-NAF-UT-S68	7/18/2023	-	856.23	-	852.72	2 - 4 ft	3.51 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S73	SSHS-ISMP-NAF-UT-S73	7/18/2023	-	856.28	-	852.51	2 - 4 ft	3.77 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-S74	SSHS-ISMP-NAF-UT-S74	7/18/2023	-	856.28	-	852.49	2 - 4 ft	3.79 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-DUP19A	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S77	SSHS-ISMP-NAF-UT-S77	7/20/2023	-	854.26	-	850.57	2 - 4 ft	3.69 ft	1801596502	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-B24	SSHS-ISMP-NAF-UT-B24	7/20/2023	-	853.95	-	850.36	2 - 4 ft	3.59 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S80	SSHS-ISMP-NAF-UT-S80	7/20/2023	-	854.98	-	851.28	2 - 4 ft	3.69 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596501	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596502	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596502	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596502	Not Excavated				< 0.046 U	< 0.037 U	0.048 J	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated	< 3000 U								
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596502	Not Excavated				< 0.049 U	< 0.039 U	0.13 J	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598162	Not Excavated				< 0.052 U	0.066 J	0.18 J	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598162	Not Excavated				< 0.052 U	< 0.041 U	0.20 J	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated	< 140 U								
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608002	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 140 U								
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613802	Not Excavated				< 0.053 U	< 0.042 U	0.10 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613802	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613812	Not Excavated				< 0.053 U	< 0.042 U	0.18 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613812	Not Excavated				< 0.056 U	< 0.044 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613812	Not Excavated				< 0.052 U	< 0.041 U	0.32	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613822	Not Excavated				< 0.052 U	< 0.041 U	0.17 J	< 0.057 U	0.083 J	0.035 J
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613822	Not Excavated				< 0.050 U	< 0.040 U	0.11 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596502	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.059 U	< 0.045 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596502	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596502	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	0.071 J
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596502	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	0.21
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598162	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.053 J	< 0.058 U	< 0.045 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598162	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.050 J	< 0.058 U	< 0.045 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608002	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated									
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated									
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613802	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	0.050 J	< 0.036 U	0.19 J	0.099 J	< 0.045 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated									
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613802	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	0.073 J	< 0.059 U	< 0.046 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613812	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	0.062 J	0.049 J	< 0.036 U	0.40	0.15 J	0.046 J
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613812	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	0.039 J	< 0.026 U	< 0.038 U	< 0.050 U	< 0.062 U	< 0.048 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613812	Not Excavated	< 0.053 U	0.049 J	0.059 J	0.077 J	0.034 J	< 0.036 U	0.25	0.21 J	0.092 J
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated									
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613822	Not Excavated	< 0.053 U	0.072 J	< 0.032 U	0.070 J	0.12 J	< 0.036 U	0.48	0.24	0.065 J
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated									
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613822	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	0.039 J	0.059 J	< 0.034 U	0.28	0.087 J	< 0.043 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	NAF-UT-S81	SSHS-ISMP-NAF-UT-S81	7/20/2023	-	854.97	-	851.32	2 - 4 ft	3.65 ft	1801596502	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	NAF-UT-S82	SSHS-ISMP-NAF-UT-S82	7/20/2023	-	855.07	-	851.47	2 - 4 ft	3.6 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S83	SSHS-ISMP-NAF-UT-S83	7/20/2023	-	855.00	-	851.44	2 - 4 ft	3.57 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B27	SSHS-ISMP-NAF-UT-B27	7/20/2023	-	854.98	-	851.18	2 - 4 ft	3.79 ft	1801596502	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-UT-S84	SSHS-ISMP-NAF-UT-S84	7/20/2023	-	854.82	-	851.67	2 - 4 ft	3.15 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S85	SSHS-ISMP-NAF-UT-S85	7/20/2023	-	854.78	-	851.71	2 - 4 ft	3.06 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S86	SSHS-ISMP-NAF-UT-S86	7/20/2023	-	854.60	-	851.58	2 - 4 ft	3.02 ft	1801596502	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	NAF-UT-B28	SSHS-ISMP-NAF-UT-B28	7/20/2023	-	855.06	-	851.33	2 - 4 ft	3.73 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B29	SSHS-ISMP-NAF-UT-B29	7/20/2023	-	854.81	-	851.51	2 - 4 ft	3.3 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B30	SSHS-ISMP-NAF-UT-B30	7/20/2023	-	854.66	-	851.57	2 - 4 ft	3.1 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B31	SSHS-ISMP-NAF-UT-B31	7/20/2023	-	854.57	-	851.52	2 - 4 ft	3.05 ft	1801596502	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-DUP21A	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598162	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	0.050 BJ	< 0.025 U
Northern Athletic Field	NAF-UT-S90	SSHS-ISMP-NAF-UT-S90	7/25/2023	-	854.60	-	850.63	2 - 4 ft	3.98 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-S93	SSHS-ISMP-NAF-UT-S93	7/25/2023	-	856.30	-	852.58	2 - 4 ft	3.72 ft	1801598162	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	0.066 BJ	< 0.025 U
Northern Athletic Field	NAF-UT-S94	SSHS-ISMP-NAF-UT-S94	7/25/2023	-	855.68	-	851.69	2 - 4 ft	4 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-S1	SSHS-ISMP-NAF-LP-S1	8/14/2023	-	855.54	-	851.55	2 - 4 ft	3.99 ft	1801608002	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-S95	SSHS-ISMP-NAF-UT-S95	8/18/2023	-	855.93	-	852.21	2 - 4 ft	3.72 ft	1801611301	Not Excavated						
Northern Athletic Field	NAF-UT-S96	SSHS-ISMP-NAF-UT-S96	8/18/2023	-	855.21	-	851.24	2 - 4 ft	3.97 ft	1801611301	Not Excavated						
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-DUP313	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-DUP310	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-DUP311	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S12	SSHS-IRM5A2-A8PH3-S12	8/24/2023	-	--	-	850.98	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S11	SSHS-IRM5A2-A8PH3-S11	8/24/2023	-	853.16	-	851.11	2 - 4 ft	2.05 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-S15	SSHS-IRM5A2-A8PH3-S15	8/24/2023	-	--	-	850.12	2 - 4 ft	2 - 4 ft	1801613802	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A8PH3-B2	SSHS-IRM5A2-A8PH3-B2	8/24/2023	-	853.94	-	851.79	2 - 4 ft	2.15 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613801	Not Excavated						
Northern Athletic Field	A8PH3-B3	SSHS-IRM5A2-A8PH3-B3	8/24/2023	-	853.89	-	851.37	2 - 4 ft	2.53 ft	1801613802	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH3-B4	SSHS-IRM5A2-A8PH3-B4	8/24/2023	-	853.97	-	851.43	2 - 4 ft	2.54 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B5	SSHS-IRM5A2-A8PH3-B5	8/24/2023	-	853.42	-	850.90	2 - 4 ft	2.52 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B6	SSHS-IRM5A2-A8PH3-B6	8/24/2023	-	853.09	-	850.85	2 - 4 ft	2.24 ft	1801613812	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A8PH3-B7	SSHS-IRM5A2-A8PH3-B7	8/24/2023	-	852.73	-	850.69	2 - 4 ft	2.04 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B8	SSHS-IRM5A2-A8PH3-B8	8/24/2023	-	852.27	-	850.07	2 - 4 ft	2.2 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B9	SSHS-IRM5A2-A8PH3-B9	8/24/2023	-	852.49	-	849.75	2 - 4 ft	2.75 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S16	SSHS-IRM5A2-A8PH3-S16	8/24/2023	-	--	-	850.22	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S17	SSHS-IRM5A2-A8PH3-S17	8/24/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801613812	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A8PH3-S18	SSHS-IRM5A2-A8PH3-S18	8/24/2023	-	--	-	850.49	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S19	SSHS-IRM5A2-A8PH3-S19	8/24/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S20	SSHS-IRM5A2-A8PH3-S20	8/24/2023	-	--	-	850.44	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S21	SSHS-IRM5A2-A8PH3-S21	8/24/2023	-	--	-	849.86	2 - 4 ft	2 - 4 ft	1801613812	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3-B10	SSHS-IRM5A2-A8PH3-B10	8/24/2023	-	852.35	-	849.48	2 - 4 ft	2.87 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B11	SSHS-IRM5A2-A8PH3-B11	8/24/2023	-	852.21	-	849.53	2 - 4 ft	2.69 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B12	SSHS-IRM5A2-A8PH3-B12	8/24/2023	-	852.31	-	849.79	2 - 4 ft	2.52 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-B13	SSHS-IRM5A2-A8PH3-B13	8/24/2023	-	852.59	-	849.71	2 - 4 ft	2.88 ft	1801613811	Not Excavated						
Northern Athletic Field	A8PH3-S26	SSHS-IRM5A2-A8PH3-S26	8/24/2023	-	--	-	849.98	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-S28	SSHS-IRM5A2-A8PH3-S28	8/24/2023	-	--	-	849.78	2 - 4 ft	2 - 4 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-B14	SSHS-IRM5A2-A8PH3-B14	8/24/2023	-	852.53	-	850.12	2 - 4 ft	2.4 ft	1801613822	Not Excavated	< 0.040 U	0.026 J	0.069 J	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3-B15	SSHS-IRM5A2-A8PH3-B15	8/24/2023	-	852.27	-	849.76	2 - 4 ft	2.51 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-B16	SSHS-IRM5A2-A8PH3-B16	8/24/2023	-	852.03	-	849.15	2 - 4 ft	2.87 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613821	Not Excavated						
Northern Athletic Field	A8PH3-B17	SSHS-IRM5A2-A8PH3-B17	8/24/2023	-	851.99	-	849.55	2 - 4 ft	2.44 ft	1801613822	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-DUP315	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-DUP313A	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615842	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated	< 140 U								
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615852	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated	< 140 U								
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615852	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.035 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619372	Not Excavated				< 0.052 U	< 0.041 U	0.072 J	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619382	Not Excavated				< 0.050 U	< 0.040 U	0.056 J	< 0.055 U	< 0.050 U	< 0.032 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629182	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated	< 130 U								
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629182	Not Excavated				< 0.057 U	< 0.045 U	0.28	< 0.061 U	< 0.057 U	< 0.035 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated	< 130 U								
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629182	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629872	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629872	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated	< 120 U								
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated	< 110 U								
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629872	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated	< 130 U								
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644032	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644032	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644912	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645442	Not Excavated				< 0.058 U	< 0.046 U	0.069 J	< 0.063 U	< 0.058 U	< 0.036 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 120 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615842	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615852	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.032 J	0.029 J	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615852	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	0.043 J	< 0.025 U	< 0.038 U	< 0.049 U	0.068 J	< 0.047 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated									
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619372	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	0.052 J	0.061 J	< 0.036 U	0.43	0.064 J	0.050 J
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated									
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated									
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619382	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	0.038 J	0.046 J	< 0.035 U	0.30	< 0.056 U	0.046 J
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629182	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	0.038 BJ	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629182	Not Excavated	< 0.058 U	0.11 J	< 0.034 U	0.15 BJ	0.11 J	< 0.039 U	0.96	0.53	0.16 J
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated									
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629182	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.039 BJ	< 0.022 U	< 0.034 U	0.047 J	< 0.054 U	< 0.042 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated									
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629872	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.041 BJ	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	0.047 J
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated									
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629872	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.14 BJ	< 0.022 U	< 0.033 U	0.095 J	< 0.053 U	0.13 J
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated									
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated									
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated									
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629872	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	0.051 BJ	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	0.044 J
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated									
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644032	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	0.028 J	< 0.035 U	0.069 J	< 0.057 U	< 0.044 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated									
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644032	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	0.026 J	< 0.037 U	0.10 J	< 0.059 U	< 0.046 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated									
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated									
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated									
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644912	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	0.034 J	< 0.036 U	0.12 J	0.064 J	< 0.045 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645442	Not Excavated	< 0.059 U	0.048 J	< 0.035 U	0.052 J	0.052 J	< 0.040 U	< 0.052 U	0.14 J	< 0.050 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated									
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S31	SSHS-IRM5A2-A8PH3-S31	8/29/2023	-	853.02	-	850.52	2 - 4 ft	2.5 ft	1801615842	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3-S34	SSHS-IRM5A2-A8PH3-S34	8/29/2023	-	--	-	851.44	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S42	SSHS-IRM5A2-A8PH3-S42	8/29/2023	-	--	-	851.13	2 - 4 ft	2 - 4 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-B18	SSHS-IRM5A2-A8PH3-B18	8/29/2023	-	853.05	-	850.25	2 - 4 ft	2.79 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-B19	SSHS-IRM5A2-A8PH3-B19	8/29/2023	-	852.36	-	849.50	2 - 4 ft	2.85 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-B20	SSHS-IRM5A2-A8PH3-B20	8/29/2023	-	852.11	-	848.90	2 - 4 ft	3.21 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-B21	SSHS-IRM5A2-A8PH3-B21	8/29/2023	-	852.03	-	849.18	2 - 4 ft	2.85 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-B22	SSHS-IRM5A2-A8PH3-B22	8/29/2023	-	851.76	-	849.42	2 - 4 ft	2.34 ft	1801615852	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH3-S46	SSHS-IRM5A2-A8PH3-S46	8/29/2023	-	--	-	850.28	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-S47	SSHS-IRM5A2-A8PH3-S47	8/29/2023	-	--	-	851.33	2 - 4 ft	2 - 4 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-B23	SSHS-IRM5A2-A8PH3-B23	8/29/2023	-	852.11	-	848.92	2 - 4 ft	3.19 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-B24	SSHS-IRM5A2-A8PH3-B24	8/29/2023	-	851.77	-	848.96	2 - 4 ft	2.8 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-B25	SSHS-IRM5A2-A8PH3-B25	8/29/2023	-	851.66	-	849.08	2 - 4 ft	2.58 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-B26	SSHS-IRM5A2-A8PH3-B26	8/29/2023	-	851.76	-	849.02	2 - 4 ft	2.75 ft	1801615852	Not Excavated	< 0.043 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A8PH3-B27	SSHS-IRM5A2-A8PH3-B27	8/29/2023	-	851.56	-	848.85	2 - 4 ft	2.71 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-S50	SSHS-IRM5A2-A8PH3-S50	8/29/2023	-	853.85	-	851.15	2 - 4 ft	2.71 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated						
Northern Athletic Field	A8PH3-S51	SSHS-IRM5A2-A8PH3-S51	9/6/2023	-	--	-	850.02	2 - 4 ft	2 - 4 ft	1801619372	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3-S66	SSHS-IRM5A2-A8PH3-S66	9/6/2023	-	--	-	849.63	2 - 4 ft	2 - 4 ft	1801619371	Not Excavated						
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619381	Not Excavated						
Northern Athletic Field	A8PH3-B36	SSHS-IRM5A2-A8PH3-B36	9/6/2023	-	852.07	-	849.34	2 - 4 ft	2.73 ft	1801619382	Not Excavated	< 0.039 U	0.023 J	0.050 J	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-DUP23A	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629182	Not Excavated	< 0.037 U	< 0.021 U	< 0.043 U	< 0.035 U	0.029 J	< 0.023 U
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-LP2-S1	SSHS-ISMP-NAF-LP2-S1	9/22/2023	-	854.49	-	851.66	2 - 4 ft	2.83 ft	1801629182	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.041 U	0.033 J	< 0.027 U
Northern Athletic Field	NAF-LP2-S2	SSHS-ISMP-NAF-LP2-S2	9/22/2023	-	854.49	-	851.49	2 - 4 ft	3.01 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-LP2-B1	SSHS-ISMP-NAF-LP2-B1	9/22/2023	-	854.54	-	851.52	2 - 4 ft	3.02 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-S4	SSHS-ISMP-NAF-EL-S4	9/22/2023	-	856.51	-	854.31	2 - 4 ft	2.2 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-B1	SSHS-ISMP-NAF-EL-B1	9/22/2023	-	856.64	-	853.96	2 - 4 ft	2.69 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629181	Not Excavated						
Northern Athletic Field	NAF-EL-B2	SSHS-ISMP-NAF-EL-B2	9/22/2023	-	856.51	-	854.33	2 - 4 ft	2.18 ft	1801629182	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	0.029 J	< 0.023 U
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated						
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-DUP24A	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629872	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629871	Not Excavated						
Northern Athletic Field	NAF-EL-S5	SSHS-ISMP-NAF-EL-S5	9/25/2023	-	856.72	-	854.31	2 - 4 ft	2.41 ft	1801629872	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	0.029 J	< 0.023 U
Northern Athletic Field	NAF-EL-S6	SSHS-ISMP-NAF-EL-S6	9/25/2023	-	857.23	-	854.18	2 - 4 ft	3.05 ft	1801629871	Not Excavated						
Northern Athletic Field	NAF-EL-S8	SSHS-ISMP-NAF-EL-S8	9/25/2023	-	856.62	-	854.50	2 - 4 ft	2.12 ft	1801629871	Not Excavated						
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629871	Not Excavated						
Northern Athletic Field	NAF-EL-B3	SSHS-ISMP-NAF-EL-B3	9/25/2023	-	856.82	-	853.77	2 - 4 ft	3.05 ft	1801629872	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-EL-B4	SSHS-ISMP-NAF-EL-B4	9/25/2023	-	856.62	-	854.22	2 - 4 ft	2.4 ft	1801629871	Not Excavated						
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-DUP321	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644032	Not Excavated	0.046 J	0.034 J	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH4-S2	SSHS-IRM5A2-A8PH4-S2	10/25/2023	-	854.28	-	851.69	2 - 4 ft	2.58 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-S4	SSHS-IRM5A2-A8PH4-S4	10/25/2023	-	--	-	851.41	2 - 4 ft	2 - 4 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-B1	SSHS-IRM5A2-A8PH4-B1	10/25/2023	-	854.26	-	851.64	2 - 4 ft	2.62 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644031	Not Excavated						
Northern Athletic Field	A8PH4-B2	SSHS-IRM5A2-A8PH4-B2	10/25/2023	-	854.37	-	851.61	2 - 4 ft	2.76 ft	1801644032	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-DUP322	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated						
Northern Athletic Field	A8PH4-S6	SSHS-IRM5A2-A8PH4-S6	10/26/2023	-	--	-	851.40	2 - 4 ft	2 - 4 ft	1801644911	Not Excavated						
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644911	Not Excavated						
Northern Athletic Field	A8PH4-B3	SSHS-IRM5A2-A8PH4-B3	10/26/2023	-	854.33	-	851.85	2 - 4 ft	2.47 ft	1801644912	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-DUP323	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-S8	SSHS-IRM5A2-A8PH4-S8	10/27/2023	-	--	-	851.93	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-S10	SSHS-IRM5A2-A8PH4-S10	10/27/2023	-	--	-	851.59	2 - 4 ft	2 - 4 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-S11	SSHS-IRM5A2-A8PH4-S11	10/27/2023	-	855.11	-	852.86	2 - 4 ft	2.25 ft	1801645442	Not Excavated	< 0.045 U	< 0.025 U	< 0.051 U	< 0.042 U	< 0.033 U	< 0.028 U
Northern Athletic Field	A8PH4-B4	SSHS-IRM5A2-A8PH4-B4	10/27/2023	-	854.77	-	851.68	2 - 4 ft	3.09 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-B5	SSHS-IRM5A2-A8PH4-B5	10/27/2023	-	854.80	-	851.81	2 - 4 ft	2.99 ft	1801645441	Not Excavated						
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-DUP324	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-S14	SSHS-IRM5A2-A8PH4-S14	11/1/2023	-	--	-	853.09	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647102	Not Excavated				< 0.053 U	< 0.042 U	0.28	< 0.058 U	0.073 J	< 0.033 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647702	Not Excavated				< 0.049 U	< 0.039 U	0.076 J	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647702	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated		< 140 U							
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647702	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648882	Not Excavated				< 0.052 U	< 0.041 U	0.36	< 0.056 U	0.054 J	< 0.032 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648882	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649722	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated		< 120 U							
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		< 120 U							
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655542	Not Excavated				< 0.054 U	< 0.043 U	0.14 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655542	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated		< 130 U							
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660612	Not Excavated				< 0.054 U	< 0.042 U	0.11 J	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		< 130 U							
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated		< 130 U							
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660612	Not Excavated				< 0.055 U	< 0.044 U	0.30	< 0.060 U	0.088 J	0.051 J
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated		< 120 U							
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661612	Not Excavated				< 0.051 U	< 0.040 U	0.089 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated		< 130 U							
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666332	Not Excavated				< 0.049 U	< 0.039 U	0.18 BJ	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666342	Not Excavated				< 0.052 U	< 0.041 U	0.28 B	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666332	Not Excavated				< 0.053 U	< 0.042 U	0.23 B	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667472	Not Excavated				< 0.050 U	< 0.040 U	0.20 BJ	< 0.055 U	< 0.050 U	< 0.032 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated				< 0.051 U	< 0.041 U	0.065 J	< 0.056 U	< 0.051 U	< 0.032 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647102	Not Excavated	< 0.054 U	0.10 J	< 0.032 U	0.10 J	0.12 J	< 0.037 U	0.47	0.20 J	0.085 J
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647702	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	0.022 J	< 0.034 U	0.12 J	0.071 J	< 0.042 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647702	Not Excavated	< 0.055 U	0.047 J	< 0.032 U	0.074 J	0.098 J	< 0.037 U	0.61	0.15 J	0.20 J
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647702	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.14 J	0.067 J	< 0.042 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated									
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648882	Not Excavated	< 0.053 U	0.11 J	< 0.031 U	0.15 J	0.12 J	< 0.035 U	0.51 EMPC	0.33	0.10 J
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated									
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648882	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	0.032 J	0.026 J	< 0.034 U	0.17 JEMPC	0.12 J	0.052 J
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649722	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.047 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655542	Not Excavated	< 0.055 U	0.058 J	< 0.033 U	0.071 J	0.038 J	< 0.037 U	0.27 EMPC	0.21 J	0.064 J
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655542	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated									
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660612	Not Excavated	< 0.055 U	0.084 J	< 0.032 U	0.089 J	0.057 J	< 0.037 U	0.19 J	0.36	0.064 J
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660612	Not Excavated	< 0.056 U	0.14 J	< 0.033 U	0.13 J	0.20 J	< 0.038 U	1.2	0.44	0.12 J
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated									
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661612	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	0.049 J	0.035 J	< 0.035 U	0.22	0.073 J	< 0.043 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated									
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated									
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666332	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.042 J	0.13 J	< 0.034 U	0.19 J	0.13 J	< 0.042 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated									
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666342	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	0.064 J	< 0.024 U	< 0.036 U	< 0.047 U	0.065 J	0.050 J
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated									
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated									
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated									
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666332	Not Excavated	< 0.054 U	0.050 J	< 0.032 U	0.046 J	< 0.024 U	< 0.037 U	0.13 JEMPC	0.25	< 0.045 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated									
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated									
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated									
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated									
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated									
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667472	Not Excavated	< 0.052 U	< 0.040 U	0.038 J	0.082 J	< 0.023 U	< 0.035 U	< 0.045 U	0.13 J	< 0.043 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated	< 0.053 U	0.046 J	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	0.099 J	< 0.044 U

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A8PH4-S16	SSHS-IRM5A2-A8PH4-S16	11/1/2023	-	--	-	853.95	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-S17	SSHS-IRM5A2-A8PH4-S17	11/1/2023	-	--	-	852.23	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-S18	SSHS-IRM5A2-A8PH4-S18	11/1/2023	-	--	-	852.79	2 - 4 ft	2 - 4 ft	1801647102	Not Excavated	< 0.041 U	< 0.023 U	0.054 J	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH4-B6	SSHS-IRM5A2-A8PH4-B6	11/1/2023	-	856.40	-	852.69	2 - 4 ft	3.71 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-B7	SSHS-IRM5A2-A8PH4-B7	11/1/2023	-	--	-	853.57	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-B9	SSHS-IRM5A2-A8PH4-B9	11/1/2023	-	--	-	852.41	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-B10	SSHS-IRM5A2-A8PH4-B10	11/1/2023	-	--	-	854.08	2 - 4 ft	2 - 4 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-DUP325	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647702	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-S20	SSHS-IRM5A2-A8PH4-S20	11/2/2023	-	856.58	-	854.28	2 - 4 ft	2.3 ft	1801647702	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH4-S21	SSHS-IRM5A2-A8PH4-S21	11/2/2023	-	856.71	-	854.64	2 - 4 ft	2.07 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-S22	SSHS-IRM5A2-A8PH4-S22	11/2/2023	-	--	-	853.75	2 - 4 ft	2 - 4 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-B11	SSHS-IRM5A2-A8PH4-B11	11/2/2023	-	856.71	-	854.28	2 - 4 ft	2.43 ft	1801647702	Not Excavated	< 0.037 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH4-B12	SSHS-IRM5A2-A8PH4-B12	11/2/2023	-	856.62	-	853.94	2 - 4 ft	2.68 ft	1801647701	Not Excavated						
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-DUP327	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-DUP326	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S25	SSHS-IRM5A2-A8PH4-S25	11/6/2023	-	--	-	853.89	2 - 4 ft	2 - 4 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S26	SSHS-IRM5A2-A8PH4-S26	11/6/2023	-	856.65	-	854.52	2 - 4 ft	2.13 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-S28	SSHS-IRM5A2-A8PH4-S28	11/6/2023	-	856.23	-	853.80	2 - 4 ft	2.43 ft	1801648882	Not Excavated	< 0.040 U	< 0.023 U	0.047 J	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH4-B13	SSHS-IRM5A2-A8PH4-B13	11/6/2023	-	856.89	-	854.39	2 - 4 ft	2.51 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-B14	SSHS-IRM5A2-A8PH4-B14	11/6/2023	-	856.72	-	854.10	2 - 4 ft	2.62 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648881	Not Excavated						
Northern Athletic Field	A8PH4-B15	SSHS-IRM5A2-A8PH4-B15	11/6/2023	-	856.28	-	853.77	2 - 4 ft	2.51 ft	1801648882	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-DUP328	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-S31	SSHS-IRM5A2-A8PH4-S31	11/7/2023	-	856.42	-	853.52	2 - 4 ft	2.9 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-S34	SSHS-IRM5A2-A8PH4-S34	11/7/2023	-	856.45	-	852.69	2 - 4 ft	3.76 ft	1801649722	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A8PH4-B16	SSHS-IRM5A2-A8PH4-B16	11/7/2023	-	856.36	-	853.33	2 - 4 ft	3.02 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S1	SSHS-IRM5A2-A8PH3A1-S1	11/16/2023	-	--	-	849.85	2 - 4 ft	2 - 4 ft	1801655542	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH3A1-S3	SSHS-IRM5A2-A8PH3A1-S3	11/16/2023	-	--	-	849.80	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S5	SSHS-IRM5A2-A8PH3A1-S5	11/16/2023	-	--	-	849.65	2 - 4 ft	2 - 4 ft	1801655542	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A8PH3A1-B2	SSHS-IRM5A2-A8PH3A1-B2	11/16/2023	-	851.74	-	847.77	2 - 4 ft	3.97 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S10	SSHS-IRM5A2-A8PH3A1-S10	11/30/2023	-	--	-	849.94	2 - 4 ft	2 - 4 ft	1801660612	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH3A1-S14	SSHS-IRM5A2-A8PH3A1-S14	11/30/2023	-	--	-	849.90	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S18	SSHS-IRM5A2-A8PH3A1-S18	11/30/2023	-	--	-	850.30	2 - 4 ft	2 - 4 ft	1801660612	Not Excavated	< 0.043 U	0.025 J	0.10 J	< 0.040 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661611	Not Excavated						
Northern Athletic Field	A8PH3A1-S23	SSHS-IRM5A2-A8PH3A1-S23	12/1/2023	-	--	-	850.55	2 - 4 ft	2 - 4 ft	1801661612	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH5-S1	SSHS-IRM5A2-A8PH5-S1	12/8/2023	-	856.29	-	853.46	2 - 4 ft	2.83 ft	1801665991	Not Excavated						
Northern Athletic Field	A8PH5-S5	SSHS-IRM5A2-A8PH5-S5	12/8/2023	-	--	-	851.90	2 - 4 ft	2 - 4 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated						
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-DUP334	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666332	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666341	Not Excavated						
Northern Athletic Field	A8PH5-S10	SSHS-IRM5A2-A8PH5-S10	12/11/2023	-	--	-	853.80	2 - 4 ft	2 - 4 ft	1801666342	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH5-S12	SSHS-IRM5A2-A8PH5-S12	12/11/2023	-	857.59	-	854.85	2 - 4 ft	2.74 ft	1801666341	Not Excavated						
Northern Athletic Field	A8PH5-B2	SSHS-IRM5A2-A8PH5-B2	12/11/2023	-	856.50	-	853.50	2 - 4 ft	3 ft	1801666331	Not Excavated						
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666331	Not Excavated						
Northern Athletic Field	A8PH5-B3	SSHS-IRM5A2-A8PH5-B3	12/11/2023	-	856.98	-	854.36	2 - 4 ft	2.62 ft	1801666332	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A8PH5-B4	SSHS-IRM5A2-A8PH5-B4	12/11/2023	-	857.88	-	855.16	2 - 4 ft	2.72 ft	1801666331	Not Excavated						
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-DUP335	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated						
Northern Athletic Field	A8PH5-S14	SSHS-IRM5A2-A8PH5-S14	12/12/2023	-	--	-	855.80	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated						
Northern Athletic Field	A8PH5-S16	SSHS-IRM5A2-A8PH5-S16	12/12/2023	-	--	-	855.94	2 - 4 ft	2 - 4 ft	1801667481	Not Excavated						
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667471	Not Excavated						
Northern Athletic Field	A8PH5-B5	SSHS-IRM5A2-A8PH5-B5	12/12/2023	-	858.39	-	855.84	2 - 4 ft	2.55 ft	1801667472	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-DUP336	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 140 U							
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated				< 0.048 U	< 0.038 U	0.075 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated		< 130 U							
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated				< 0.051 U	0.064 J	0.27	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 130 U							
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668652	Not Excavated				< 0.052 U	< 0.042 U	0.19 J	< 0.057 U	0.063 J	< 0.033 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated		< 120 U							
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated		< 120 U							
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated		< 130 U							
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		< 130 U							
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		< 120 U							
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681222	Not Excavated				0.085 BJ	< 0.043 U	< 0.052 U	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated		< 130 U							
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated		< 150 U							
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated		< 140 U							
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721832	Not Excavated				< 0.062 U	< 0.049 U	< 0.060 U	< 0.067 U	< 0.062 U	< 0.039 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated		< 120 U							
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721832	Not Excavated				< 0.057 U	< 0.045 U	< 0.054 U	< 0.061 U	< 0.057 U	< 0.035 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated		< 130 U							
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721832	Not Excavated				< 0.055 U	< 0.044 U	0.089 J	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated		< 490 U							
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated		< 240 U							
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726642	Not Excavated				< 0.054 U	< 0.043 U	0.060 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated			< 42						
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated			< 43						
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated			< 43						
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated			< 41						
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated			< 41						
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated			< 230 U						
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated			< 240 U						
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated			< 130 U						
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated			< 490 U						
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated			120						
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated	< 110 U								
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated	< 120 U								
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.073 BJ	< 0.043 U	< 0.024 U	< 0.073 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 110 U			< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.037 J	< 0.046 U	0.026 J	< 0.078 U

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated	< 0.052 U	0.095 J	0.043 JEMPC	0.14 J	0.030 J	< 0.035 U	0.23	0.26	0.086 J
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated									
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated									
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668652	Not Excavated	< 0.054 U	0.089 J	< 0.032 U	0.069 J	0.13 J	< 0.036 U	1.2	0.22	< 0.045 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated									
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated									
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated									
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated									
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated									
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated									
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681222	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	0.15 J	< 0.025 U	< 0.038 U	< 0.049 U	< 0.060 U	0.14 J
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated									
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721832	Not Excavated	< 0.063 U	< 0.049 U	< 0.038 U	< 0.040 U	0.057 J	< 0.043 U	1.2	0.39	< 0.053 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721832	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.037 U	< 0.026 U	< 0.039 U	0.15 JEMPC	0.074 J	< 0.048 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated									
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721832	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	0.040 J	0.11 J	< 0.038 U	0.69 EMPC	0.12 J	< 0.047 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated									
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated									
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726642	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	0.062 J	0.033 J	< 0.037 U	0.31	0.088 J	0.073 J
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated									
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated									
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated									
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated									
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated									
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated									
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated									
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated									
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated									
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated									
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated									
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated									
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated									
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.038 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	0.34 J	< 0.094 U	< 0.084 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.038 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.094 U	< 0.084 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated									
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated									
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated									
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated									
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated									
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.038 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.038 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.041 U	< 0.034 U	< 0.036 U	0.068 J	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	< 0.090 U

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	**Perfluorotrideceanoic acid (PFTrA)**	**Perfluoroundecanoic acid (PFUnA)**	**1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)**	**1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)**	**2-(N-methyl perfluorooctanesulfonamido) acetic acid**
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-DUP337	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S18	SSHS-IRM5A2-A8PH5-S18	12/13/2023	-	--	-	856.08	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH5-S20	SSHS-IRM5A2-A8PH5-S20	12/13/2023	-	858.63	-	856.61	2 - 4 ft	2.02 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S22	SSHS-IRM5A2-A8PH5-S22	12/13/2023	-	--	-	855.98	2 - 4 ft	2 - 4 ft	1801668662	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH5-S24	SSHS-IRM5A2-A8PH5-S24	12/13/2023	-	--	-	855.66	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-S25	SSHS-IRM5A2-A8PH5-S25	12/13/2023	-	--	-	856.00	2 - 4 ft	2 - 4 ft	1801668661	Not Excavated						
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668651	Not Excavated						
Northern Athletic Field	A8PH5-B6	SSHS-IRM5A2-A8PH5-B6	12/13/2023	-	858.59	-	856.16	2 - 4 ft	2.43 ft	1801668652	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A8PH5-B7	SSHS-IRM5A2-A8PH5-B7	12/13/2023	-	858.80	-	856.51	2 - 4 ft	2.29 ft	1801668651	Not Excavated						
Northern Athletic Field	A8PH5-B8	SSHS-IRM5A2-A8PH5-B8	12/13/2023	-	858.42	-	855.73	2 - 4 ft	2.68 ft	1801668651	Not Excavated						
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-DUP339	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated						
Northern Athletic Field	A8PH6-S2	SSHS-IRM5A2-A8PH6-S2	1/12/2024	-	--	-	854.38	2 - 4 ft	2 - 4 ft	1801681231	Not Excavated						
Northern Athletic Field	A8PH6-B1	SSHS-IRM5A2-A8PH6-B1	1/12/2024	-	--	-	854.15	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH6-B2	SSHS-IRM5A2-A8PH6-B2	1/12/2024	-	--	-	854.23	2 - 4 ft	2 - 4 ft	1801681222	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A8PH6-B3	SSHS-IRM5A2-A8PH6-B3	1/12/2024	-	--	-	854.68	2 - 4 ft	2 - 4 ft	1801681221	Not Excavated						
Northern Athletic Field	A8PH7-BOT1	SSHS-IRM5A2-A8PH7-BOT1	4/10/2024	-	858.58	-	856.14	2 - 4 ft	2.44 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-BOT2	SSHS-IRM5A2-A8PH7-BOT2	4/10/2024	-	858.58	-	855.77	2 - 4 ft	2.8 ft	1801721832	Not Excavated	< 0.048 U	< 0.027 U	< 0.054 U	< 0.045 U	< 0.035 U	< 0.030 U
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV9-BOT	SSHS-IRM5A2-A8PH7-SCV9-BOT	4/10/2024	-	858.01	-	855.87	2 - 4 ft	2.14 ft	1801721832	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721831	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT	SSHS-IRM5A2-A8PH7-SCV25-BOT	4/10/2024	-	854.84	-	852.17	2 - 4 ft	2.68 ft	1801721832	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A8PH7-SCV25E	SSHS-IRM5A2-A8PH7-SCV25E	4/18/2024	-	855.03	-	852.66	2 - 4 ft	2.38 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726641	Not Excavated						
Northern Athletic Field	A8PH7-SCV25-BOT2	SSHS-IRM5A2-A8PH7-SCV25-BOT2	4/18/2024	-	854.85	-	852.39	2 - 4 ft	2.46 ft	1801726642	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	SSHS-B75	081514 01:15_DUP-14	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated						
Northern Athletic Field	SSHS-B75	SSHS-B75-2-6 (3)	8/14/2014	856.08	856.35	0.27	-	2 - 6 ft	2.27-6.27 ft	180-35818-2	Not Excavated						
Northern Athletic Field	SSHS-B76	SSHS-B76-2-6 (5)	8/14/2014	856.25	857.34	1.09	-	2 - 6 ft	3.09-7.09 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B77	SSHS-B77-2-6 (5)	8/14/2014	855.88	857.91	2.03	-	2 - 6 ft	4.03-8.03 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B71	SSHS-B71-2.5-4.5 (3.5)	8/15/2014	856.19	856.45	0.26	-	2.5 - 4.5 ft	2.76-4.76 ft	180-35858-1	Not Excavated						
Northern Athletic Field	SSHS-B3327	SSHS-B3327-SUB-4-6	12/16/2019	853.34	855.35	2.01	-	4 - 6 ft	6.01-8.01 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3329	SSHS-B3329-SUB-4-6	12/16/2019	852.74	855.10	2.36	-	4 - 6 ft	6.36-8.36 ft	180-100148-1	Not Excavated						
Northern Athletic Field	SSHS-B3276	SSHS-B3276-SUB-4-6	12/18/2019	856.44	857.46	1.02	-	4 - 6 ft	5.02-7.02 ft	180-100380-1	Not Excavated						
Northern Athletic Field	SSHS-B3280	SSHS-B3280-SUB-4-6	12/18/2019	856.56	856.77	0.21	-	4 - 6 ft	4.21-6.21 ft	180-100380-2	Not Excavated						
Northern Athletic Field	SSHS-B3232	SSHS-B3232-SUB-4-6	12/20/2019	855.71	855.63	-0.08	-	4 - 6 ft	3.92-5.92 ft	180-100362-1	Not Excavated						
Northern Athletic Field	SSHS-B3496	SSHS-B3496-SUB-4-6	1/14/2021	858.30	858.61	0.31	-	4 - 6 ft	4.31-6.31 ft	180-116002-2	Not Excavated						
Northern Athletic Field	SSHS-B13A	SSHS-B13A-SUB-4-6	1/23/2021	856.72	856.88	0.16	-	4 - 6 ft	4.16-6.16 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3057A	SSHS-B3057A-SUB-4-6	1/23/2021	856.06	857.63	1.57	-	4 - 6 ft	5.57-7.57 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3071A	SSHS-B3071A-SUB-4-6	1/23/2021	856.76	856.63	-0.13	-	4 - 6 ft	3.87-5.87 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3261A	SSHS-B3261A-SUB-4-6	1/25/2021	856.35	856.68	0.33	-	4 - 6 ft	4.33-6.33 ft	180-116404-3	Not Excavated						
Northern Athletic Field	SSHS-B3001A	SSHS-B3001A-SUB-4-6	1/25/2021	853.34	853.48	0.14	-	4 - 6 ft	4.14-6.14 ft	1801164043	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3182A	SSHS-B3182A-SUB-4-6	1/26/2021	857.46	857.78	0.32	-	4 - 6 ft	4.32-6.32 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3224A	SSHS-B3224A-SUB-4-6	1/26/2021	858.35	858.41	0.06	-	4 - 6 ft	4.06-6.06 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-4-6	1/26/2021	858.55	858.46	-0.09	-	4 - 6 ft	3.91-5.91 ft	180-116462-1	Not Excavated						
Northern Athletic Field	SSHS-B3481A	SSHS-B3481A-SUB-4-6	1/26/2021	858.11	858.22	0.11	-	4 - 6 ft	4.11-6.11 ft	1801164623	Not Excavated						
Northern Athletic Field	SSHS-B3484A	SSHS-B3484A-SUB-4-6	1/26/2021	858.42	858.49	0.07	-	4 - 6 ft	4.07-6.07 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3490A	SSHS-B3490A-SUB-4-6	1/26/2021	858.46	858.46	0.00	-	4 - 6 ft	4-6 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3497	SSHS-B3497-SUB-4-6	1/26/2021	858.46	858.50	0.04	-	4 - 6 ft	4.04-6.04 ft	1801164624	Not Excavated	< 0.059 U	< 0.056 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3498	SSHS-B3498-SUB-4-6	1/26/2021	858.39	858.21	-0.18	-	4 - 6 ft	3.82-5.82 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3499	SSHS-B3499-SUB-4-6	1/26/2021	858.31	858.56	0.25	-	4 - 6 ft	4.25-6.25 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3594	SSHS-B3594-SUB-4-6	1/26/2021	858.38	858.34	-0.04	-	4 - 6 ft	3.96-5.96 ft	1801164624	Not Excavated	< 0.059 U	< 0.056 U	< 0.040 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3098A	SSHS-B3098A-SUB-4-6	1/27/2021	855.96	857.03	1.07	-	4 - 6 ft	5.07-7.07 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-4-6	1/27/2021	856.41	855.18	-1.23	-	4 - 6 ft	2.77-4.77 ft	180-116529-1	Not Excavated						
Northern Athletic Field	SSHS-B3519	SSHS-B3519-SUB-4-6	1/27/2021	856.72	854.93	-1.79	-	4 - 6 ft	2.21-4.21 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-4-6	1/29/2021	856.89	856.18	-0.71	-	4 - 6 ft	3.29-5.29 ft	180-116665-1	Not Excavated						
Northern Athletic Field	SSHS-B3629	SSHS-B3629-SUB-4-6	2/3/2021	856.66	856.50	-0.16	-	4 - 6 ft	3.84-5.84 ft	180-116771-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-4-6	5/11/2021	856.50	855.82	-0.68	-	4 - 6 ft	3.32-5.32 ft	1801214741	Not Excavated	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-4-6	5/17/2021	856.37	856.43	0.06	-	4 - 6 ft	4.06-6.06 ft	1801217472	Not Excavated	< 0.059 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-4-6	5/18/2021	855.95	855.66	-0.29	-	4 - 6 ft	3.71-5.71 ft	1801218221	Not Excavated	< 0.063 U	< 0.060 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated			< 120 UJ						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated			< 110 U	< 0.05 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.05 U	< 0.031 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	S165	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated	< 130 U								
Northern Athletic Field	S167	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated	< 120 U								
Northern Athletic Field	S448	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated	< 130 U								
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated	< 120 U								
Northern Athletic Field	B775	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated	< 120 U								
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 130 U								
Northern Athletic Field	B768	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated	< 120 U								
Northern Athletic Field	B763	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated	< 120 U								
Northern Athletic Field	B764	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated	< 120 U								
Northern Athletic Field	B754	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated	< 120 U								
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated	< 130 U								
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated	< 130 U								
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated	< 140 U								
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 120 U								
Northern Athletic Field	S471	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated	< 110 U								
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated	< 130 U								
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated	< 130 U								
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330902	Not Excavated				< 0.057 U	< 0.045 U	0.11 J	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated	< 110 U								
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated	< 120 UT								
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated	< 110 U								
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated	< 120 U								
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated	< 120 U								
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated	< 120 U								
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 120 U								
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated	< 120 U								
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated	< 120 U								
Northern Athletic Field	S181	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated	< 120 U								
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.868	1801347841	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.3423096	1801347841	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated	< 130 U								
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated	< 120 U								
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351302	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated	< 100 U								
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.028	1801352021	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.358	1801352871	Not Excavated	< 110 UT								
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.8769697	1801354291	Not Excavated	< 110 U								
Northern Athletic Field	S221	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated									
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.037 U	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.080 U
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated									
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.051 U	< 0.039 U	< 0.03 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.042 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated									
Northern Athletic Field	S165	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated									
Northern Athletic Field	S167	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated									
Northern Athletic Field	S448	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated									
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated									
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated									
Northern Athletic Field	B775	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated									
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated									
Northern Athletic Field	B768	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated									
Northern Athletic Field	B763	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated									
Northern Athletic Field	B764	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated									
Northern Athletic Field	B754	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated									
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated									
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated									
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated									
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated									
Northern Athletic Field	S471	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated									
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated									
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated									
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated									
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330902	Not Excavated	< 0.058 U	< 0.045 U	< 0.035 U	< 0.037 U	0.062 J	< 0.039 U	0.32	0.18 J	< 0.049 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated									
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated									
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated									
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated									
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated									
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated									
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated									
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated									
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated									
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated									
Northern Athletic Field	S181	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated									
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.868	1801347841	Not Excavated									
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.3423096	1801347841	Not Excavated									
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated									
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated									
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated									
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated									
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351302	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated									
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.028	1801352021	Not Excavated									
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.358	1801352871	Not Excavated									
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated									
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated									
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.8769697	1801354291	Not Excavated									
Northern Athletic Field	S221	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	SSHS-B4017	SSHS-B4017-SUB-4-6	7/1/2021	856.80	856.80	0.00	-	4 - 6 ft	4 - 6 ft	180-123985-2	Not Excavated						
Northern Athletic Field	SSHS-B4018	SSHS-B4018-SUB-4-6	7/1/2021	857.47	857.20	-0.27	-	4 - 6 ft	3.73-5.73 ft	1801239851	Not Excavated	< 0.056 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B4025	SSHS-B4025-SUB-4-6	7/1/2021	857.11	856.25	-0.86	-	4 - 6 ft	3.14-5.14 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4026	SSHS-B4026-SUB-4-6	7/1/2021	856.99	856.10	-0.89	-	4 - 6 ft	3.11-5.11 ft	180-123985-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-4-6	9/17/2021	857.91	857.91	0.00	-	4 - 6 ft	4-6 ft	180-127265-2	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-4-6	9/22/2021	856.72	856.72	0.00	-	4 - 6 ft	4-6 ft	180-127415-1	Not Excavated						
Northern Athletic Field	S165	SSHS-IRM5A2-S165	10/28/2021	-	855.74	-	850.39	4 - 6 ft	5.34 ft	1801292043	Not Excavated						
Northern Athletic Field	S167	SSHS-IRM5A2-S167	10/28/2021	-	855.69	-	850.71	4 - 6 ft	4.98 ft	1801292043	Not Excavated						
Northern Athletic Field	S448	SSHS-IRM5A2-S448	11/4/2021	-	858.11	-	852.92	4 - 6 ft	5.19 ft	1801296371	Not Excavated						
Northern Athletic Field	DW2-S2	SSHS-IRM5A2-DW2-S2	11/8/2021	-	857.18	-	851.18	4 - 6 ft	6 ft	1801296791	Not Excavated						
Northern Athletic Field	DW3-S1	SSHS-IRM5A2-DW3-S1	11/10/2021	-	856.83	-	851.93	4 - 6 ft	4.9 ft	1801298201	Not Excavated						
Northern Athletic Field	B775	SSHS-IRM5A2-B775	12/1/2021	-	858.22	-	853.66	4 - 6 ft	4.56 ft	1801305751	Not Excavated						
Northern Athletic Field	B764	SSHS-IRM5A2-DUP20	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated						
Northern Athletic Field	B768	SSHS-IRM5A2-B768	12/5/2021	-	858.69	-	853.65	4 - 6 ft	5.04 ft	1801307851	Not Excavated						
Northern Athletic Field	B763	SSHS-IRM5A2-B763	12/5/2021	-	857.90	-	853.47	4 - 6 ft	4.43 ft	1801307851	Not Excavated						
Northern Athletic Field	B764	SSHS-IRM5A2-B764	12/5/2021	-	858.41	-	853.42	4 - 6 ft	4.98 ft	1801307851	Not Excavated						
Northern Athletic Field	B754	SSHS-IRM5A2-B754	12/5/2021	-	858.50	-	853.55	4 - 6 ft	4.95 ft	1801307851	Not Excavated						
Northern Athletic Field	B743-BOT2	SSHS-IRM5A2-B743-BOT2	12/10/2021	-	858.21	-	852.14	4 - 6 ft	6.07 ft	1801311081	Not Excavated						
Northern Athletic Field	B743-S3	SSHS-IRM5A2-B743-S3	12/10/2021	-	858.34	-	852.71	4 - 6 ft	5.64 ft	1801311081	Not Excavated						
Northern Athletic Field	B743-BOT1	SSHS-IRM5A2-B743-BOT1	12/10/2021	-	857.89	-	852.22	4 - 6 ft	5.67 ft	1801311081	Not Excavated						
Northern Athletic Field	S471	SSHS-IRM5A2-DUP24	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated						
Northern Athletic Field	S471	SSHS-IRM5A2-S471	1/6/2022	-	857.93	-	852.03	4 - 6 ft	5.9 ft	1801320661	Not Excavated						
Northern Athletic Field	RS-BOT15	SSHS-IRM5A2-RS-BOT15	2/1/2022	-	852.92	-	848.46	4 - 6 ft	4.46 ft	1801329991	Not Excavated						
Northern Athletic Field	RS-BOT16	SSHS-IRM5A2-RS-BOT16	2/1/2022	-	853.34	-	848.27	4 - 6 ft	5.07 ft	1801329991	Not Excavated						
Northern Athletic Field	RS-BOT17	SSHS-IRM5A2-RS-BOT17	2/1/2022	-	853.16	-	848.14	4 - 6 ft	5.01 ft	1801329991	Not Excavated						
Northern Athletic Field	RS-BOT28	SSHS-IRM5A2-RS-BOT28	2/2/2022	-	853.73	-	848.51	4 - 6 ft	5.21 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT29	SSHS-IRM5A2-RS-BOT29	2/2/2022	-	854.39	-	848.40	4 - 6 ft	5.99 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT34	SSHS-IRM5A2-RS-BOT34	2/2/2022	-	854.06	-	848.56	4 - 6 ft	5.5 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-S52	SSHS-IRM5A2-RS-S52	2/2/2022	-	853.26	-	849.09	4 - 6 ft	4.17 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-S53	SSHS-IRM5A2-RS-S53	2/2/2022	-	853.86	-	849.44	4 - 6 ft	4.42 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT36	SSHS-IRM5A2-RS-BOT36	2/2/2022	-	853.63	-	848.57	4 - 6 ft	5.05 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT37	SSHS-IRM5A2-RS-BOT37	2/2/2022	-	853.65	-	849.11	4 - 6 ft	4.54 ft	1801330902	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	RS-S55	SSHS-IRM5A2-RS-S55	2/2/2022	-	853.90	-	849.56	4 - 6 ft	4.34 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT35	SSHS-IRM5A2-RS-BOT35	2/7/2022	-	853.46	-	848.72	4 - 6 ft	4.74 ft	1801332631	Not Excavated						
Northern Athletic Field	S174-S1	SSHS-IRM5A2-S174-S1	2/7/2022	-	854.22	-	850.06	4 - 6 ft	4.16 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-S3	SSHS-IRM5A2-S174-S3	2/7/2022	-	854.64	-	850.19	4 - 6 ft	4.46 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-S5	SSHS-IRM5A2-S174-S5	2/7/2022	-	855.07	-	850.80	4 - 6 ft	4.28 ft	1801332621	Not Excavated						
Northern Athletic Field	S172A-S1	SSHS-IRM5A2-S172A-S1	2/8/2022	-	855.72	-	851.42	4 - 6 ft	4.29 ft	1801333441	Not Excavated						
Northern Athletic Field	RS-S56	SSHS-IRM5A2-RS-S56	2/8/2022	-	852.87	-	847.58	4 - 6 ft	5.29 ft	1801333431	Not Excavated						
Northern Athletic Field	SLT-S78	SSHS-ISMP-SLT-S78	3/3/2022	-	856.63	-	851.40	4 - 6 ft	5.23 ft	1801346411	Not Excavated						
Northern Athletic Field	SLT-BOT24	SSHS-ISMP-SLT-BOT24	3/3/2022	-	856.68	-	850.87	4 - 6 ft	5.81 ft	1801346411	Not Excavated						
Northern Athletic Field	SLT-BOT25	SSHS-ISMP-SLT-BOT25	3/3/2022	-	856.52	-	851.58	4 - 6 ft	4.94 ft	1801346411	Not Excavated						
Northern Athletic Field	SLT-S82	SSHS-ISMP-SLT-S82	3/3/2022	-	856.50	-	852.16	4 - 6 ft	4.33 ft	1801346411	Not Excavated						
Northern Athletic Field	SLT-S86	SSHS-ISMP-SLT-S86	3/3/2022	-	856.51	-	851.57	4 - 6 ft	4.94 ft	1801346411	Not Excavated						
Northern Athletic Field	SLT-BOT26	SSHS-ISMP-SLT-BOT26	3/3/2022	-	856.49	-	851.64	4 - 6 ft	4.85 ft	1801346411	Not Excavated						
Northern Athletic Field	S181	SSHS-IRM5A2-S181	3/3/2022	-	852.94	-	847.29	4 - 6 ft	5.65 ft	1801346401	Not Excavated						
Northern Athletic Field	SLT-BOT27	SSHS-ISMP-SLT-BOT27	3/6/2022	-	856.46	-	850.59	4 - 6 ft	5.868	1801347841	Not Excavated						
Northern Athletic Field	SLT-S92	SSHS-ISMP-SLT-S92	3/6/2022	-	857.12	-	851.78	4 - 6 ft	5.3423096	1801347841	Not Excavated						
Northern Athletic Field	MS-SLT-B2	SSHS-ISMP-MS-SLT-B2	3/11/2022	-	856.30	-	851.59	4 - 6 ft	4.71 ft	1801350892	Not Excavated						
Northern Athletic Field	MS-SLT-B3	SSHS-ISMP-MS-SLT-B3	3/11/2022	-	856.55	-	850.98	4 - 6 ft	5.57 ft	1801350892	Not Excavated						
Northern Athletic Field	MS-SLT-S14	SSHS-ISMP-MS-SLT-S14	3/11/2022	-	856.55	-	851.42	4 - 6 ft	5.13 ft	1801350892	Not Excavated						
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351301	Not Excavated						
Northern Athletic Field	S124	SSHS-IRM5A2-S124	3/14/2022	-	854.30	-	849.38	4 - 6 ft	4.92 ft	1801351302	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 UT	< 0.024 U
Northern Athletic Field	MS-SLT-S22	SSHS-ISMP-MS-SLT-S22	3/15/2022	-	856.79	-	851.85	4 - 6 ft	4.95 ft	1801352021	Not Excavated						
Northern Athletic Field	MS-SLT-S28	SSHS-ISMP-MS-SLT-S28	3/15/2022	-	856.71	-	851.69	4 - 6 ft	5.028	1801352021	Not Excavated						
Northern Athletic Field	MS-SLT-S34	SSHS-ISMP-MS-SLT-S34	3/16/2022	-	856.60	-	851.24	4 - 6 ft	5.358	1801352871	Not Excavated						
Northern Athletic Field	MS-SLT-S40	SSHS-ISMP-MS-SLT-S40	3/17/2022	-	856.74	-	851.56	4 - 6 ft	5.18 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S46	SSHS-ISMP-MS-SLT-S46	3/17/2022	-	856.82	-	851.13	4 - 6 ft	5.69 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S52	SSHS-ISMP-MS-SLT-S52	3/18/2022	-	856.71	-	851.47	4 - 6 ft	5.24 ft	1801354291	Not Excavated						
Northern Athletic Field	MS-SLT-B10	SSHS-ISMP-MS-SLT-B10	3/18/2022	-	857.31	-	851.86	4 - 6 ft	5.45 ft	1801354291	Not Excavated						
Northern Athletic Field	MS-SLT-S54	SSHS-ISMP-MS-SLT-S54	3/18/2022	-	856.69	-	851.82	4 - 6 ft	4.8769697	1801354291	Not Excavated						
Northern Athletic Field	S221	SSHS-IRM5A2-S221	3/19/2022	-	853.22	-	847.75	4 - 6 ft	5.48 ft	1801354701	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354702	Not Excavated				< 0.047 U	< 0.037 U	0.24	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated	< 110 U								
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 120 U								
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated	< 120 U								
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated	< 120 U								
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated	< 110 U								
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated	< 110 U								
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	S147	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated	< 130 U								
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370432	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	B117	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated	< 140 U								
Northern Athletic Field	B110	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	B115	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated	< 120 U								
Northern Athletic Field	B114	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated	< 130 U								
Northern Athletic Field	B113	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated	< 120 U								
Northern Athletic Field	B105	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated	< 120 U								
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 120 UT								
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated	< 140 U								
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371273	Not Excavated				< 0.057 U	< 0.045 U	< 0.054 U	< 0.061 U	< 0.057 U	< 0.035 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated	< 130 UT								
Northern Athletic Field	S149	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated	< 120 UT								
Northern Athletic Field	S151	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated	< 120 UT								
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated	< 120 U								
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated	< 110 UT								
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371262	Not Excavated				< 0.049 U	< 0.039 U	0.082 J	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated	< 120 UT								
Northern Athletic Field	S134	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated	< 130 UT								
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated	< 110 UT								
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371262	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated	< 120 U								
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371273	Not Excavated				< 0.051 U	< 0.040 U	0.064 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 110 U								
Northern Athletic Field	B103	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated	< 130 U								
Northern Athletic Field	B102	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated	< 220 U								
Northern Athletic Field	B108	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated	< 110 U								
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated	< 120 U								
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372052	Not Excavated				< 0.053 U	< 0.042 U	0.12 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated	< 110 U								
Northern Athletic Field	B106	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated	< 110 U								
Northern Athletic Field	B100	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated	< 120 U								
Northern Athletic Field	B107	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated		< 31 U							
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated		< 34 U							
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated		< 38 U							
Northern Athletic Field	S532	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated		< 34 U							
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated		< 33 U							
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378344	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.033 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated		< 31 U							
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated		< 34 U							
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378344	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated		< 32 U							
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated		< 33 U							
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated		< 31 U							
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated		< 32 U							
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated		< 30 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated									
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354702	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	0.58
Northern Athletic Field	S122	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated									
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated									
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated									
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated									
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated									
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated									
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated									
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated									
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated									
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated									
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated									
Northern Athletic Field	S147	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated									
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated									
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370432	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.046 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated									
Northern Athletic Field	B117	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated									
Northern Athletic Field	B110	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated									
Northern Athletic Field	B115	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated									
Northern Athletic Field	B114	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated									
Northern Athletic Field	B113	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated									
Northern Athletic Field	B105	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated									
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated									
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371273	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.037 U	0.029 J	< 0.039 U	0.46	0.099 J	< 0.048 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated									
Northern Athletic Field	S149	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated									
Northern Athletic Field	S151	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated									
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated									
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated									
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371262	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.10 J	< 0.054 U	0.062 J
Northern Athletic Field	S133	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated									
Northern Athletic Field	S134	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated									
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated									
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371262	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371273	Not Excavated	< 0.052 U	< 0.040 U	0.033 J	< 0.033 U	< 0.023 U	< 0.035 U	0.085 J	< 0.056 U	0.049 J
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated									
Northern Athletic Field	B103	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated									
Northern Athletic Field	B102	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated									
Northern Athletic Field	B108	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated									
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated									
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372052	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.050 J	< 0.058 U	< 0.045 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated									
Northern Athletic Field	B106	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated									
Northern Athletic Field	B100	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated									
Northern Athletic Field	B107	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated									
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated									
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated									
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated									
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated									
Northern Athletic Field	S532	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated									
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated									
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378344	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated									
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated									
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378344	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.059 U	< 0.045 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated									
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated									
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated									
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated									
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354701	Not Excavated						
Northern Athletic Field	S123A	SSHS-IRM5A2-S123A	3/19/2022	-	853.52	-	849.01	4 - 6 ft	4.51 ft	1801354702	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S122	SSHS-IRM5A2-S122	3/19/2022	-	853.49	-	848.98	4 - 6 ft	4.51 ft	1801354701	Not Excavated						
Northern Athletic Field	MS-SLT-S62	SSHS-ISMP-MS-SLT-S62	3/21/2022	-	856.52	-	850.84	4 - 6 ft	5.68 ft	1801354881	Not Excavated						
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-DUPAA	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated						
Northern Athletic Field	IRM5-FP-BOT6	SSHS-IRM5-FP-BOT6	3/28/2022	-	855.39	-	850.48	4 - 6 ft	4.9 ft	1801358371	Not Excavated						
Northern Athletic Field	IRM5-FP-S5	SSHS-IRM5-FP-S5	3/28/2022	-	855.90	-	851.24	4 - 6 ft	4.66 ft	1801358371	Not Excavated						
Northern Athletic Field	IRM5-FP-S6	SSHS-IRM5-FP-S6	3/28/2022	-	855.36	-	851.03	4 - 6 ft	4.33 ft	1801358371	Not Excavated						
Northern Athletic Field	MS-SLT-S87	SSHS-ISMP-MS-SLT-S87	4/8/2022	-	856.51	-	852.27	4 - 6 ft	4.24 ft	1801364891	Not Excavated						
Northern Athletic Field	MS-SLT-B16	SSHS-ISMP-MS-SLT-B16	4/8/2022	-	856.51	-	852.32	4 - 6 ft	4.19 ft	1801364891	Not Excavated						
Northern Athletic Field	MS-SLT-S89	SSHS-ISMP-MS-SLT-S89	4/8/2022	-	856.52	-	852.31	4 - 6 ft	4.22 ft	1801364891	Not Excavated						
Northern Athletic Field	B1182	SSHS-IRM5A2-B1182	4/8/2022	-	856.77	-	852.41	4 - 6 ft	4.36 ft	1801364901	Not Excavated						
Northern Athletic Field	B110	SSHS-IRM5A2-DUP64	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated						
Northern Athletic Field	S147	SSHS-IRM5A2-S147	4/21/2022	-	856.31	-	851.17	4 - 6 ft	5.14 ft	1801370431	Not Excavated						
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370431	Not Excavated						
Northern Athletic Field	B116	SSHS-IRM5A2-B116	4/21/2022	-	855.30	-	850.51	4 - 6 ft	4.8 ft	1801370432	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.040 U	< 0.030 U	< 0.026 U
Northern Athletic Field	B111	SSHS-IRM5A2-B111	4/21/2022	-	855.61	-	850.90	4 - 6 ft	4.7 ft	1801370431	Not Excavated						
Northern Athletic Field	B117	SSHS-IRM5A2-B117	4/21/2022	-	856.07	-	850.60	4 - 6 ft	5.47 ft	1801370431	Not Excavated						
Northern Athletic Field	B110	SSHS-IRM5A2-B110	4/21/2022	-	855.42	-	850.67	4 - 6 ft	4.75 ft	1801370431	Not Excavated						
Northern Athletic Field	B115	SSHS-IRM5A2-B115	4/21/2022	-	855.17	-	850.54	4 - 6 ft	4.63 ft	1801370431	Not Excavated						
Northern Athletic Field	B114	SSHS-IRM5A2-B114	4/21/2022	-	854.99	-	850.86	4 - 6 ft	4.13 ft	1801370431	Not Excavated						
Northern Athletic Field	B113	SSHS-IRM5A2-B113	4/22/2022	-	856.13	-	850.66	4 - 6 ft	5.47 ft	1801370981	Not Excavated						
Northern Athletic Field	B105	SSHS-IRM5A2-B105	4/22/2022	-	855.85	-	850.95	4 - 6 ft	4.91 ft	1801370981	Not Excavated						
Northern Athletic Field	S133	SSHS-IRM5A2-DUP67	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated						
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-DW1	SSHS-IRM5A2-A5-DW1	4/25/2022	-	856.67	-	851.00	4 - 6 ft	5.66 ft	1801371273	Not Excavated	< 0.044 U	0.032 J	0.066 J	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	S148	SSHS-IRM5A2-S148	4/25/2022	-	856.05	-	851.37	4 - 6 ft	4.68 ft	1801371261	Not Excavated						
Northern Athletic Field	S149	SSHS-IRM5A2-S149	4/25/2022	-	856.64	-	851.57	4 - 6 ft	5.08 ft	1801371261	Not Excavated						
Northern Athletic Field	S151	SSHS-IRM5A2-S151	4/25/2022	-	856.78	-	851.52	4 - 6 ft	5.26 ft	1801371261	Not Excavated						
Northern Athletic Field	PIPE5-S4	SSHS-IRM5A2-PIPE5-S4	4/25/2022	-	855.48	-	849.49	4 - 6 ft	6 ft	1801371271	Not Excavated						
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371261	Not Excavated						
Northern Athletic Field	S150	SSHS-IRM5A2-S150	4/25/2022	-	856.62	-	852.29	4 - 6 ft	4.33 ft	1801371262	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S133	SSHS-IRM5A2-S133	4/25/2022	-	856.60	-	850.86	4 - 6 ft	5.75 ft	1801371261	Not Excavated						
Northern Athletic Field	S134	SSHS-IRM5A2-S134	4/25/2022	-	856.16	-	851.19	4 - 6 ft	4.97 ft	1801371261	Not Excavated						
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371261	Not Excavated						
Northern Athletic Field	S135	SSHS-IRM5A2-S135	4/25/2022	-	856.08	-	851.48	4 - 6 ft	4.61 ft	1801371262	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-S6	SSHS-IRM5A2-PIPE5-S6	4/25/2022	-	855.42	-	849.82	4 - 6 ft	5.6 ft	1801371273	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	B106	SSHS-IRM5A2-DUP73	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated						
Northern Athletic Field	B103	SSHS-IRM5A2-B103	4/26/2022	-	856.09	-	850.87	4 - 6 ft	5.22 ft	1801372051	Not Excavated						
Northern Athletic Field	B102	SSHS-IRM5A2-B102	4/26/2022	-	856.00	-	851.31	4 - 6 ft	4.69 ft	1801372051	Not Excavated						
Northern Athletic Field	B108	SSHS-IRM5A2-B108	4/26/2022	-	856.40	-	851.04	4 - 6 ft	5.36 ft	1801372051	Not Excavated						
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372051	Not Excavated						
Northern Athletic Field	B112	SSHS-IRM5A2-B112	4/26/2022	-	856.44	-	850.54	4 - 6 ft	5.91 ft	1801372052	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	B119	SSHS-IRM5A2-B119	4/26/2022	-	855.40	-	851.08	4 - 6 ft	4.33 ft	1801372051	Not Excavated						
Northern Athletic Field	B106	SSHS-IRM5A2-B106	4/26/2022	-	856.79	-	851.31	4 - 6 ft	5.48 ft	1801372051	Not Excavated						
Northern Athletic Field	B100	SSHS-IRM5A2-B100	4/26/2022	-	855.84	-	851.10	4 - 6 ft	4.74 ft	1801372051	Not Excavated						
Northern Athletic Field	B107	SSHS-IRM5A2-B107	4/26/2022	-	856.65	-	851.20	4 - 6 ft	5.46 ft	1801372051	Not Excavated						
Northern Athletic Field	SLT-S79-S7	SSHS-ISMP-SLT-S79-S7	5/5/2022	-	856.65	-	850.98	4 - 6 ft	5.67 ft	1801376941	Not Excavated						
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-DUP81	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378343	Not Excavated						
Northern Athletic Field	PIPE7	SSHS-IRM5A2-PIPE7	5/9/2022	-	856.50	-	851.87	4 - 6 ft	4.63 ft	1801378342	Not Excavated						
Northern Athletic Field	S0000	SSHS-IRM5A2-S0000	5/9/2022	-	856.14	-	851.21	4 - 6 ft	4.93 ft	1801378341	Not Excavated						
Northern Athletic Field	S532	SSHS-IRM5A2-S532	5/9/2022	-	856.23	-	851.83	4 - 6 ft	4.4 ft	1801378341	Not Excavated						
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378341	Not Excavated						
Northern Athletic Field	S0001	SSHS-IRM5A2-S0001	5/9/2022	-	856.23	-	851.00	4 - 6 ft	5.23 ft	1801378344	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A5-V1-S16	SSHS-IRM5A2-A5-V1-S16	5/9/2022	-	856.40	-	851.56	4 - 6 ft	4.84 ft	1801378342	Not Excavated						
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378341	Not Excavated						
Northern Athletic Field	B1603	SSHS-IRM5A2-B1603	5/9/2022	-	855.91	-	850.93	4 - 6 ft	4.97 ft	1801378344	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/9/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801378341	Not Excavated						
Northern Athletic Field	B1605	SSHS-IRM5A2-B1605	5/9/2022	-	856.29	-	850.46	4 - 6 ft	5.83 ft	1801378341	Not Excavated						
Northern Athletic Field	B1602	SSHS-IRM5A2-B1602	5/9/2022	-	856.15	-	850.15	4 - 6 ft	6 ft	1801378341	Not Excavated						
Northern Athletic Field	B1604	SSHS-IRM5A2-B1604	5/9/2022	-	856.25	-	850.67	4 - 6 ft	5.59 ft	1801378341	Not Excavated						
Northern Athletic Field	FIS-LAT1-S5	SSHS-IRM5A2-FIS-LAT1-S5	5/11/2022	-	853.93	-	849.78	4 - 6 ft	4.16 ft	1801379861	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated		< 29 U							
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated		< 31 U							
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated		< 31 U							
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379862	Not Excavated				< 0.050 U	< 0.039 U	0.10 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated		< 32 U							
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated		< 31 U							
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380692	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated		< 36 U							
Northern Athletic Field	S544	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated		< 36 U							
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated		< 32 U							
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated		< 30 U							
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated		< 31 U							
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated		< 30 U							
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383172	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated		< 31 U							
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383172	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated		< 31 U							
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated		< 32 U							
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated		< 30 U							
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated		< 33 U							
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated		< 31 U							
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392682	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated		< 32 U							
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398273	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated	< 120 U								
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated	< 330 U								
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated	< 110 U								
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398273	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated		< 33 U							
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399473	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated		< 31 U							
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated		< 30 U							
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated		< 30 U							
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399473	Not Excavated				< 0.046 U	< 0.036 U	0.070 J	< 0.049 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated		< 30 U							
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated		< 31 UT							
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400212	Not Excavated				< 0.051 U	< 0.040 U	0.082 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated		< 33 U							
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated		< 310 U							
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400232	Not Excavated				< 0.051 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated		< 34 U							
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated		< 33 U							
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated		< 33 U							
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400232	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated	< 120 U								
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401822	Not Excavated				< 0.048 U	< 0.038 U	0.24	< 0.052 U	< 0.048 U	< 0.030 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated									
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379862	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	0.084 J	< 0.043 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated									
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated									
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380692	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.11 J	0.065 J	< 0.043 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated									
Northern Athletic Field	S544	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated									
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated									
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated									
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated									
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated									
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383172	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.084 J	< 0.055 U	< 0.043 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated									
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383172	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated									
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392682	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated									
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated									
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398273	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.083 J	< 0.053 U	0.050 J
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398273	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399473	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	0.14 J	< 0.055 U	< 0.043 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399473	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400212	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	0.098 J
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated									
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400232	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400232	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated									
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401822	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.19 J	< 0.053 U	0.12 J

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FIS-LAT1-BOT1	SSHS-IRM5A2-FIS-LAT1-BOT1	5/11/2022	-	853.33	-	849.00	4 - 6 ft	4.33 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-BOT3	SSHS-IRM5A2-FIS-LAT1-BOT3	5/11/2022	-	853.90	-	849.18	4 - 6 ft	4.72 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379861	Not Excavated						
Northern Athletic Field	FIS-LAT1-BOT2	SSHS-IRM5A2-FIS-LAT1-BOT2	5/11/2022	-	853.49	-	849.21	4 - 6 ft	4.28 ft	1801379862	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FIS-LAT1-S6	SSHS-IRM5A2-FIS-LAT1-S6	5/11/2022	-	853.91	-	849.75	4 - 6 ft	4.16 ft	1801379861	Not Excavated						
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380691	Not Excavated						
Northern Athletic Field	B1606	SSHS-IRM5A2-B1606	5/12/2022	-	855.96	-	850.87	4 - 6 ft	5.09 ft	1801380692	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	PIPE8	SSHS-IRM5A2-PIPE8	5/17/2022	-	857.46	-	851.48	4 - 6 ft	5.98 ft	1801382542	Not Excavated						
Northern Athletic Field	S544	SSHS-IRM5A2-S544	5/17/2022	-	857.55	-	852.44	4 - 6 ft	5.11 ft	1801382541	Not Excavated						
Northern Athletic Field	B1628	SSHS-IRM5A2-B1628	5/17/2022	-	856.05	-	850.24	4 - 6 ft	5.82 ft	1801382552	Not Excavated						
Northern Athletic Field	B5001	SSHS-IRM5A2-B5001	5/18/2022	-	856.73	-	851.99	4 - 6 ft	4.74 ft	1801383171	Not Excavated						
Northern Athletic Field	B5002	SSHS-IRM5A2-B5002	5/18/2022	-	856.34	-	851.15	4 - 6 ft	5.2 ft	1801383171	Not Excavated						
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383171	Not Excavated						
Northern Athletic Field	B5003	SSHS-IRM5A2-B5003	5/18/2022	-	855.58	-	850.71	4 - 6 ft	4.87 ft	1801383172	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383171	Not Excavated						
Northern Athletic Field	B5004	SSHS-IRM5A2-B5004	5/18/2022	-	855.67	-	851.60	4 - 6 ft	4.07 ft	1801383172	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-4-6	6/4/2022	856.27	856.38	0.11	-	4 - 6 ft	4.11-6.11 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-4-6	6/4/2022	856.61	857.29	0.68	-	4 - 6 ft	4.68-6.68 ft	180-139185-1	Not Excavated						
Northern Athletic Field	A5-S601	SSHS-IRM5A2-DUP103	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S601	SSHS-IRM5A2-A5-S601	6/7/2022	-	854.16	-	849.69	4 - 6 ft	4.48 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S600	SSHS-IRM5A2-A5-S600	6/7/2022	-	854.35	-	850.02	4 - 6 ft	4.33 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S603	SSHS-IRM5A2-A5-S603	6/7/2022	-	854.29	-	849.38	4 - 6 ft	4.91 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S602	SSHS-IRM5A2-A5-S602	6/7/2022	-	854.17	-	849.59	4 - 6 ft	4.57 ft	1801392682	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	CP2-S27	SSHS-IRM5A2-CP2-S27	6/10/2022	-	857.16	-	852.17	4 - 6 ft	4.99 ft	1801395462	Not Excavated						
Northern Athletic Field	FISR-S1	SSHS-IRM5A2-FISR-S1	6/11/2022	-	854.11	-	848.76	4 - 6 ft	5.35 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S9	SSHS-IRM5A2-FISR-S9	6/15/2022	-	854.75	-	848.87	4 - 6 ft	5.89 ft	1801397521	Not Excavated						
Northern Athletic Field	FISR-S25	SSHS-IRM5A2-FISR-S25	6/15/2022	-	855.07	-	849.28	4 - 6 ft	5.78 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-DUP127	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398273	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-S401	SSHS-IRM5A2-A3-S401	6/16/2022	-	855.43	-	849.62	4 - 6 ft	5.81 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S402	SSHS-IRM5A2-A3-S402	6/16/2022	-	855.63	-	850.32	4 - 6 ft	5.3 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S403	SSHS-IRM5A2-A3-S403	6/16/2022	-	855.94	-	850.38	4 - 6 ft	5.56 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S404	SSHS-IRM5A2-A3-S404	6/16/2022	-	856.32	-	851.26	4 - 6 ft	5.06 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B200	SSHS-IRM5A2-A3-B200	6/16/2022	-	854.89	-	850.75	4 - 6 ft	4.14 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B201	SSHS-IRM5A2-A3-B201	6/16/2022	-	855.61	-	850.89	4 - 6 ft	4.72 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-B203	SSHS-IRM5A2-A3-B203	6/16/2022	-	855.97	-	851.51	4 - 6 ft	4.46 ft	1801398273	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-S405	SSHS-IRM5A2-A3-S405	6/17/2022	-	855.32	-	849.53	4 - 6 ft	5.79 ft	1801399473	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-B202A	SSHS-IRM5A2-A3-B202A	6/17/2022	-	854.95	-	849.61	4 - 6 ft	5.34 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B204A	SSHS-IRM5A2-A3-B204A	6/17/2022	-	854.92	-	849.45	4 - 6 ft	5.48 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B206	SSHS-IRM5A2-A3-B206	6/17/2022	-	854.76	-	849.52	4 - 6 ft	5.24 ft	1801399473	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A3-B208	SSHS-IRM5A2-A3-B208	6/17/2022	-	855.07	-	850.00	4 - 6 ft	5.06 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B209A	SSHS-IRM5A2-A3-B209A	6/17/2022	-	855.07	-	850.18	4 - 6 ft	4.89 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-S410	SSHS-IRM5A2-DUP133	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400212	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-4-6	6/20/2022	856.38	856.44	0.06	-	4 - 6 ft	4.06-6.06 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-4-6	6/20/2022	856.66	856.67	0.01	-	4 - 6 ft	4.01-6.01 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-4-6	6/20/2022	856.60	856.56	-0.04	-	4 - 6 ft	3.96-5.96 ft	180-140136-1	Not Excavated						
Northern Athletic Field	A3-S409	SSHS-IRM5A2-A3-S409	6/20/2022	-	856.27	-	851.24	4 - 6 ft	5.04 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S410	SSHS-IRM5A2-A3-S410	6/20/2022	-	856.53	-	851.75	4 - 6 ft	4.78 ft	1801400232	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-S410A	SSHS-IRM5A2-A3-S410A	6/20/2022	-	856.94	-	852.20	4 - 6 ft	4.74 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S411	SSHS-IRM5A2-A3-S411	6/20/2022	-	856.74	-	852.23	4 - 6 ft	4.51 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S412	SSHS-IRM5A2-A3-S412	6/20/2022	-	857.04	-	852.43	4 - 6 ft	4.61 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S413	SSHS-IRM5A2-A3-S413	6/20/2022	-	856.98	-	852.62	4 - 6 ft	4.36 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S414	SSHS-IRM5A2-A3-S414	6/20/2022	-	857.03	-	852.59	4 - 6 ft	4.44 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S415	SSHS-IRM5A2-A3-S415	6/20/2022	-	857.35	-	852.98	4 - 6 ft	4.37 ft	1801400232	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401821	Not Excavated						
Northern Athletic Field	A3-B214	SSHS-IRM5A2-A3-B214	6/22/2022	-	856.38	-	852.22	4 - 6 ft	4.17 ft	1801401822	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406773	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.029 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated	< 100 U								
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406773	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406773	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated		< 31 UT							
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407632	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated		< 30 UT							
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated		< 32 U							
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated		< 31 U							
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated		< 33 U							
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407993	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated		< 32 U							
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407993	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated		< 30 U							
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated		< 34 U							
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407993	Not Excavated				< 0.056 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.056 U	< 0.035 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated		< 30 U							
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated		< 31 U							
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated		< 32 U							
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated		< 30 U							
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated		< 33 U							
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated		< 31 U							
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407993	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated		< 31 U							
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated		< 30 U							
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated		< 32 U							
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407993	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated		< 30 U							
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated		< 31 U							
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated		< 31 U							
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated		< 31 U							
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated		< 30 U							
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410572	Not Excavated				< 0.045 U	< 0.035 U	< 0.043 U	< 0.049 U	< 0.045 U	< 0.028 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated		< 30 U							
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410582	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated		< 30 U							
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated		< 31 U							
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated		< 30 U							
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated		< 31 U							
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410582	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated		< 29 U							
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated		< 31 U							
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated		< 30 U							
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410582	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated		< 33 U							
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411042	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated		< 32 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406773	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406773	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.10 J	< 0.052 U	< 0.040 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406773	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407632	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.088 J	< 0.055 U	< 0.043 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated									
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407993	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.051 U	< 0.040 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407993	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.17 J	< 0.056 U	< 0.044 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated									
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407993	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.038 U	< 0.050 U	0.093 J	< 0.048 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407993	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.046 J	< 0.054 U	< 0.041 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated									
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407993	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410572	Not Excavated	< 0.046 U	< 0.035 U	< 0.027 U	< 0.029 U	< 0.021 U	0.040 J	< 0.040 U	< 0.049 U	< 0.038 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410582	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	0.11 J	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410582	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410582	Not Excavated	< 0.047 UT	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	0.064 J	< 0.041 U	< 0.051 U	< 0.039 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated									
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated									
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411042	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-DUP144	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406773	Not Excavated	< 0.035 U	0.020 J	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FISR-S50	SSHS-IRM5A2-FISR-S50	6/30/2022	-	853.07	-	847.24	4 - 6 ft	5.83 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S65	SSHS-IRM5A2-FISR-S65	6/30/2022	-	854.41	-	849.00	4 - 6 ft	5.4 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S59	SSHS-IRM5A2-FISR-S59	6/30/2022	-	853.15	-	848.46	4 - 6 ft	4.69 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S60	SSHS-IRM5A2-FISR-S60	6/30/2022	-	854.57	-	849.52	4 - 6 ft	5.04 ft	1801406773	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FISR-S66	SSHS-IRM5A2-FISR-S66	6/30/2022	-	854.66	-	849.46	4 - 6 ft	5.2 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S55	SSHS-IRM5A2-FISR-S55	6/30/2022	-	852.95	-	847.22	4 - 6 ft	5.73 ft	1801406773	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-S403	SSHS-IRM5A2-FL-S403	7/1/2022	-	857.30	-	853.29	4 - 6 ft	4.01 ft	1801407632	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-S404	SSHS-IRM5A2-FL-S404	7/1/2022	-	857.38	-	853.14	4 - 6 ft	4.24 ft	1801407631	Not Excavated						
Northern Athletic Field	FL-B406	SSHS-IRM5A2-DUP148	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S405	SSHS-IRM5A2-FL-S405	7/5/2022	-	857.57	-	853.25	4 - 6 ft	4.32 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S406	SSHS-IRM5A2-FL-S406	7/5/2022	-	857.82	-	853.63	4 - 6 ft	4.19 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-S407	SSHS-IRM5A2-FL-S407	7/5/2022	-	857.80	-	853.70	4 - 6 ft	4.11 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B400	SSHS-IRM5A2-FL-B400	7/5/2022	-	856.55	-	852.29	4 - 6 ft	4.26 ft	1801407993	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B401	SSHS-IRM5A2-FL-B401	7/5/2022	-	856.66	-	852.63	4 - 6 ft	4.03 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B402	SSHS-IRM5A2-FL-B402	7/5/2022	-	856.93	-	852.20	4 - 6 ft	4.73 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B404	SSHS-IRM5A2-FL-B404	7/5/2022	-	856.93	-	852.40	4 - 6 ft	4.52 ft	1801407993	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	FL-B405	SSHS-IRM5A2-FL-B405	7/5/2022	-	856.74	-	852.68	4 - 6 ft	4.06 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B406	SSHS-IRM5A2-FL-B406	7/5/2022	-	856.96	-	852.53	4 - 6 ft	4.43 ft	1801407991	Not Excavated						
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B408	SSHS-IRM5A2-FL-B408	7/5/2022	-	856.89	-	852.31	4 - 6 ft	4.58 ft	1801407993	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	FL-B410	SSHS-IRM5A2-FL-B410	7/5/2022	-	857.58	-	852.92	4 - 6 ft	4.65 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B411	SSHS-IRM5A2-FL-B411	7/5/2022	-	856.92	-	852.52	4 - 6 ft	4.4 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B413	SSHS-IRM5A2-FL-B413	7/5/2022	-	856.84	-	852.83	4 - 6 ft	4.01 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B414	SSHS-IRM5A2-FL-B414	7/5/2022	-	857.84	-	853.58	4 - 6 ft	4.25 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B415	SSHS-IRM5A2-FL-B415	7/5/2022	-	857.82	-	853.06	4 - 6 ft	4.76 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B416	SSHS-IRM5A2-FL-B416	7/5/2022	-	857.26	-	852.77	4 - 6 ft	4.49 ft	1801407993	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B417	SSHS-IRM5A2-FL-B417	7/5/2022	-	856.96	-	852.95	4 - 6 ft	4.01 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B419	SSHS-IRM5A2-FL-B419	7/5/2022	-	857.80	-	853.24	4 - 6 ft	4.56 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407992	Not Excavated						
Northern Athletic Field	FL-B420	SSHS-IRM5A2-FL-B420	7/5/2022	-	857.45	-	852.85	4 - 6 ft	4.61 ft	1801407993	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B424	SSHS-IRM5A2-DUP151	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-DUP150	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S1	SSHS-IRM5A2-FL-WELL1-S1	7/8/2022	-	856.93	-	851.52	4 - 6 ft	5.41 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S4	SSHS-IRM5A2-FL-WELL1-S4	7/8/2022	-	856.86	-	851.51	4 - 6 ft	5.35 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S7	SSHS-IRM5A2-FL-WELL1-S7	7/8/2022	-	856.92	-	852.19	4 - 6 ft	4.72 ft	1801410572	Not Excavated	< 0.035 U	< 0.020 U	< 0.039 U	< 0.033 U	< 0.025 U	< 0.021 U
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B421	SSHS-IRM5A2-FL-B421	7/8/2022	-	857.31	-	853.03	4 - 6 ft	4.28 ft	1801410582	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	FL-B422	SSHS-IRM5A2-FL-B422	7/8/2022	-	857.30	-	852.88	4 - 6 ft	4.42 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B423	SSHS-IRM5A2-FL-B423	7/8/2022	-	857.94	-	853.59	4 - 6 ft	4.35 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B424	SSHS-IRM5A2-FL-B424	7/8/2022	-	857.33	-	852.80	4 - 6 ft	4.54 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B425	SSHS-IRM5A2-FL-B425	7/8/2022	-	857.31	-	852.78	4 - 6 ft	4.54 ft	1801410582	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B426	SSHS-IRM5A2-FL-B426	7/8/2022	-	857.13	-	852.87	4 - 6 ft	4.26 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B427	SSHS-IRM5A2-FL-B427	7/8/2022	-	857.06	-	852.86	4 - 6 ft	4.2 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B428	SSHS-IRM5A2-FL-B428	7/8/2022	-	856.89	-	852.75	4 - 6 ft	4.14 ft	1801410582	Not Excavated	< 0.036 U	< 0.020 UT	< 0.040 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B429	SSHS-IRM5A2-FL-B429	7/8/2022	-	856.73	-	852.56	4 - 6 ft	4.17 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-B418A	SSHS-IRM5A2-FL-B418A	7/8/2022	-	856.93	-	852.59	4 - 6 ft	4.33 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-DUP155	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S3	SSHS-IRM5A2-FL-FISN-S3	7/11/2022	-	856.53	-	850.66	4 - 6 ft	5.87 ft	1801411041	Not Excavated						
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411041	Not Excavated						
Northern Athletic Field	FL-FISN-S5	SSHS-IRM5A2-FL-FISN-S5	7/11/2022	-	856.79	-	850.96	4 - 6 ft	5.84 ft	1801411042	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-FISN-S7	SSHS-IRM5A2-FL-FISN-S7	7/11/2022	-	856.77	-	850.85	4 - 6 ft	5.93 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411051	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411052	Not Excavated				< 0.050 U	< 0.040 U	0.060 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411052	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411052	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 UT	< 0.051 U	< 0.032 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated		< 37 U							
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated		< 31 U							
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated	< 120 U								
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 110 U								
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated	< 110 U								
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated		< 31 U							
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated		< 31 U							
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated		< 30 U							
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated		< 31 U							
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated		< 31 U							
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated		< 31 U							
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413132	Not Excavated				< 0.047 U	< 0.038 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated		< 31 U							
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated		< 34 U							
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 100 U								
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated	< 100 U								
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated	< 100 U								
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated	< 110 U								
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated		< 34 U							
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418892	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated		< 31 U							
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418882	Not Excavated				< 0.050 U	< 0.040 U	0.080 J	0.17 J	0.12 J	0.061 J
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated		< 32 U							
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated		< 33 U							
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated		< 33 U							
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418882	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated		< 33 U							
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated		< 33 U							
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated		< 31 U							
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated		< 34 U							
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated		< 29 U							
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated		< 30 U							
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated		< 32 U							
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418892	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated		< 32 U							
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated		< 32 U							
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated		< 30 U							
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated		< 32 U							
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418912	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418912	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated		< 31 U							
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419752	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated		< 32 U							
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated		< 31 U							
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411052	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411052	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.031 J	< 0.022 U	0.049 J	0.068 J	0.071 J	< 0.041 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411052	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated									
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated									
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated									
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated									
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated									
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413132	Not Excavated	< 0.048 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.052 U	< 0.041 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated									
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated									
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418892	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418882	Not Excavated	< 0.051 U	0.070 J	< 0.030 U	0.056 J	0.085 J	< 0.035 U	0.67	0.18 J	0.074 J
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated									
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418882	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418892	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated									
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418912	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.054 U	< 0.041 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418912	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	0.037 J	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419752	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FL-FISN-S9	SSHS-IRM5A2-FL-FISN-S9	7/11/2022	-	856.52	-	850.99	4 - 6 ft	5.54 ft	1801411052	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-FISN-S11	SSHS-IRM5A2-FL-FISN-S11	7/11/2022	-	856.55	-	850.99	4 - 6 ft	5.57 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S13	SSHS-IRM5A2-FL-FISN-S13	7/11/2022	-	856.63	-	851.09	4 - 6 ft	5.55 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S15	SSHS-IRM5A2-FL-FISN-S15	7/11/2022	-	856.62	-	850.92	4 - 6 ft	5.7 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S17	SSHS-IRM5A2-FL-FISN-S17	7/11/2022	-	856.69	-	850.84	4 - 6 ft	5.85 ft	1801411052	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-FISN-S19	SSHS-IRM5A2-FL-FISN-S19	7/11/2022	-	856.69	-	851.05	4 - 6 ft	5.64 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S21	SSHS-IRM5A2-FL-FISN-S21	7/11/2022	-	856.77	-	851.39	4 - 6 ft	5.38 ft	1801411052	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	FL-FISN-S23	SSHS-IRM5A2-FL-FISN-S23	7/11/2022	-	856.75	-	851.25	4 - 6 ft	5.5 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S27	SSHS-IRM5A2-FL-FISN-S27	7/11/2022	-	856.85	-	851.66	4 - 6 ft	5.2 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S29	SSHS-IRM5A2-FL-FISN-S29	7/11/2022	-	856.85	-	851.12	4 - 6 ft	5.74 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S33	SSHS-IRM5A2-FL-FISN-S33	7/11/2022	-	856.82	-	850.99	4 - 6 ft	5.83 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S37	SSHS-IRM5A2-FL-FISN-S37	7/11/2022	-	856.67	-	850.84	4 - 6 ft	5.82 ft	1801411061	Not Excavated						
Northern Athletic Field	PIPE22	SSHS-IRM5A2-PIPE22	7/12/2022	-	856.14	-	851.95	4 - 6 ft	4.18 ft	1801411711	Not Excavated						
Northern Athletic Field	FL-B445	SSHS-IRM5A2-DUP161	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated						
Northern Athletic Field	FL-B445	SSHS-IRM5A2-FL-B445	7/13/2022	-	856.62	-	852.54	4 - 6 ft	4.08 ft	1801412371	Not Excavated						
Northern Athletic Field	FL-S427	SSHS-IRM5A2-DUP166	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-B454	SSHS-IRM5A2-FL-B454	7/14/2022	-	856.70	-	852.62	4 - 6 ft	4.08 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B455	SSHS-IRM5A2-FL-B455	7/14/2022	-	856.68	-	852.53	4 - 6 ft	4.15 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B462	SSHS-IRM5A2-FL-B462	7/14/2022	-	856.53	-	852.23	4 - 6 ft	4.31 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-B465	SSHS-IRM5A2-FL-B465	7/14/2022	-	856.70	-	852.49	4 - 6 ft	4.21 ft	1801413121	Not Excavated						
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S426	SSHS-IRM5A2-FL-S426	7/14/2022	-	856.70	-	852.48	4 - 6 ft	4.22 ft	1801413132	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-S427	SSHS-IRM5A2-FL-S427	7/14/2022	-	856.66	-	852.50	4 - 6 ft	4.15 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S428	SSHS-IRM5A2-FL-S428	7/14/2022	-	856.63	-	852.59	4 - 6 ft	4.04 ft	1801413131	Not Excavated						
Northern Athletic Field	FL-S603	SSHS-IRM5A2-DUP168	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S608	SSHS-IRM5A2-DUP167	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S602	SSHS-IRM5A2-FL-S602	7/22/2022	-	856.68	-	850.81	4 - 6 ft	5.87 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S603	SSHS-IRM5A2-FL-S603	7/22/2022	-	856.59	-	850.76	4 - 6 ft	5.83 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S605	SSHS-IRM5A2-FL-S605	7/22/2022	-	856.50	-	850.79	4 - 6 ft	5.71 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S606	SSHS-IRM5A2-FL-S606	7/22/2022	-	856.31	-	851.07	4 - 6 ft	5.24 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S607	SSHS-IRM5A2-FL-S607	7/22/2022	-	856.30	-	850.62	4 - 6 ft	5.68 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S608	SSHS-IRM5A2-FL-S608	7/22/2022	-	856.20	-	850.69	4 - 6 ft	5.51 ft	1801418261	Not Excavated						
Northern Athletic Field	FL-S610	SSHS-IRM5A2-DUP172	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-S618	SSHS-IRM5A2-DUP174	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418892	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S609	SSHS-IRM5A2-FL-S609	7/25/2022	-	856.62	-	851.14	4 - 6 ft	5.49 ft	1801418882	Not Excavated	< 0.039 U	0.037 J	0.090 J	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-S610	SSHS-IRM5A2-FL-S610	7/25/2022	-	856.49	-	851.41	4 - 6 ft	5.08 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S611	SSHS-IRM5A2-FL-S611	7/25/2022	-	856.52	-	851.28	4 - 6 ft	5.23 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418881	Not Excavated						
Northern Athletic Field	FL-S612	SSHS-IRM5A2-FL-S612	7/25/2022	-	856.67	-	851.14	4 - 6 ft	5.52 ft	1801418882	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	FL-S613	SSHS-IRM5A2-FL-S613	7/25/2022	-	856.59	-	851.44	4 - 6 ft	5.15 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-S614	SSHS-IRM5A2-FL-S614	7/25/2022	-	856.67	-	851.25	4 - 6 ft	5.43 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-S615	SSHS-IRM5A2-FL-S615	7/25/2022	-	856.56	-	850.86	4 - 6 ft	5.7 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S8	SSHS-IRM5A2-PIPE24-S8	7/25/2022	-	856.40	-	850.99	4 - 6 ft	5.41 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-S616	SSHS-IRM5A2-FL-S616	7/25/2022	-	856.72	-	851.12	4 - 6 ft	5.6 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-S617	SSHS-IRM5A2-FL-S617	7/25/2022	-	856.64	-	851.20	4 - 6 ft	5.45 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-S618	SSHS-IRM5A2-FL-S618	7/25/2022	-	856.64	-	851.28	4 - 6 ft	5.36 ft	1801418892	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B439A-BOT	SSHS-IRM5A2-FL-B439A-BOT	7/25/2022	-	856.68	-	850.97	4 - 6 ft	5.72 ft	1801418891	Not Excavated						
Northern Athletic Field	FL-B442-BOT	SSHS-IRM5A2-FL-B442-BOT	7/25/2022	-	856.74	-	850.93	4 - 6 ft	5.8 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-B435-BOT	SSHS-IRM5A2-FL-B435-BOT	7/25/2022	-	856.83	-	851.26	4 - 6 ft	5.57 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S5	SSHS-IRM5A2-FL-PIPE17-S5	7/25/2022	-	856.48	-	850.56	4 - 6 ft	5.92 ft	1801418912	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S9	SSHS-IRM5A2-FL-PIPE17-S9	7/25/2022	-	856.47	-	850.59	4 - 6 ft	5.88 ft	1801418912	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	0.39	< 0.024 U
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B607	SSHS-IRM5A2-FL-B607	7/26/2022	-	856.69	-	850.80	4 - 6 ft	5.9 ft	1801419752	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B608	SSHS-IRM5A2-FL-B608	7/26/2022	-	856.77	-	851.22	4 - 6 ft	5.55 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B609	SSHS-IRM5A2-FL-B609	7/26/2022	-	856.78	-	850.76	4 - 6 ft	6.02 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B610	SSHS-IRM5A2-FL-B610	7/26/2022	-	856.71	-	850.68	4 - 6 ft	6.03 ft	1801419751	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated		< 30 U							
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419752	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated		< 31 U							
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated		< 33 U							
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated		< 31 U							
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419752	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated		< 30 U							
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated		< 34 U							
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419772	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated		< 30 U							
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421922	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.051 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated		< 31 U							
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated		< 31 U							
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated		< 32 U							
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated		< 32 U							
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated		< 32 U							
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated		< 32 U							
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426842	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated		< 34 U							
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427632	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated		< 30 U							
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated		< 32 U							
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated		< 32 U							
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428482	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated		< 30 U							
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated		< 32 U							
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated		< 29 U							
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428482	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.029 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated		< 31 U							
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated		< 31 U							
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428482	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated		< 32 U							
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated		< 31 U							
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated		< 31 U							
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated		< 31 U							
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated		< 30 U							
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated		< 30 U							
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated		< 31 U							
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated		< 30 U							
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated		< 29 U							
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated		< 29 U							
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated		< 30 U							
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated		< 33 U							
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated		< 33 U							
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated		< 32 U							
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated		< 33 U							
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated		< 34 U							
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated		< 31 U							
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434602	Not Excavated				< 0.051 U	< 0.040 U	0.073 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated		< 33 U							
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated		< 34 U							
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434602	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated		< 33 U							
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated		< 32 U							
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419752	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419752	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.10 J	0.077 J	< 0.040 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated									
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419772	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.045 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated									
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421922	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.052 U	< 0.041 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated									
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated									
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated									
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated									
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated									
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated									
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426842	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	0.050 J	< 0.057 U	< 0.044 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated									
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427632	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428482	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428482	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428482	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated									
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated									
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated									
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434602	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.059 J	< 0.056 U	0.055 J
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434602	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.085 J	< 0.058 U	< 0.045 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated									
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated									
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B611	SSHS-IRM5A2-FL-B611	7/26/2022	-	856.50	-	850.52	4 - 6 ft	5.98 ft	1801419752	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B613	SSHS-IRM5A2-FL-B613	7/26/2022	-	856.71	-	851.18	4 - 6 ft	5.53 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B614	SSHS-IRM5A2-FL-B614	7/26/2022	-	856.78	-	851.04	4 - 6 ft	5.74 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B615	SSHS-IRM5A2-FL-B615	7/26/2022	-	856.85	-	851.09	4 - 6 ft	5.76 ft	1801419752	Not Excavated	< 0.037 U	< 0.021 U	< 0.041 U	< 0.035 U	0.044 J	< 0.023 U
Northern Athletic Field	FL-B616	SSHS-IRM5A2-FL-B616	7/26/2022	-	856.92	-	850.86	4 - 6 ft	6.06 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419771	Not Excavated						
Northern Athletic Field	FL-B619	SSHS-IRM5A2-FL-B619	7/26/2022	-	856.63	-	850.62	4 - 6 ft	6.01 ft	1801419772	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421921	Not Excavated						
Northern Athletic Field	FL-B466A	SSHS-IRM5A2-FL-B466A	7/29/2022	-	856.62	-	852.51	4 - 6 ft	4.11 ft	1801421922	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B467A	SSHS-IRM5A2-FL-B467A	7/29/2022	-	856.60	-	852.30	4 - 6 ft	4.3 ft	1801421921	Not Excavated						
Northern Athletic Field	FL-S619	SSHS-IRM5A2-FL-S619	8/8/2022	-	856.57	-	850.75	4 - 6 ft	5.81 ft	1801426161	Not Excavated						
Northern Athletic Field	FL-S620	SSHS-IRM5A2-FL-S620	8/8/2022	-	856.76	-	850.74	4 - 6 ft	6.02 ft	1801426161	Not Excavated						
Northern Athletic Field	FL-CB1-BOT	SSHS-IRM5A2-FL-CB1-BOT	8/9/2022	-	856.79	-	852.54	4 - 6 ft	4.26 ft	1801426841	Not Excavated						
Northern Athletic Field	FL-S621	SSHS-IRM5A2-FL-S621	8/9/2022	-	856.56	-	850.84	4 - 6 ft	5.71 ft	1801426841	Not Excavated						
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426841	Not Excavated						
Northern Athletic Field	FL-S622	SSHS-IRM5A2-FL-S622	8/9/2022	-	856.63	-	851.08	4 - 6 ft	5.55 ft	1801426842	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	PIPE25	SSHS-IRM5A2-PIPE25	8/9/2022	-	856.62	-	851.90	4 - 6 ft	4.71 ft	1801426841	Not Excavated						
Northern Athletic Field	FL-B651	SSHS-IRM5A2-DUP189	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S1	SSHS-IRM5A2-FL-DW3A-S1	8/10/2022	-	856.60	-	850.71	4 - 6 ft	5.89 ft	1801427632	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B603A	SSHS-IRM5A2-FL-B603A	8/10/2022	-	856.45	-	850.49	4 - 6 ft	5.97 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW6BOT	SSHS-IRM5A2-FL-DW6BOT	8/10/2022	-	856.47	-	850.63	4 - 6 ft	5.84 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-B651	SSHS-IRM5A2-FL-B651	8/10/2022	-	856.67	-	850.70	4 - 6 ft	5.97 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B661	SSHS-IRM5A2-DUP190	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428482	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B676	SSHS-IRM5A2-DUP192	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B655	SSHS-IRM5A2-FL-B655	8/11/2022	-	856.19	-	850.32	4 - 6 ft	5.87 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B656	SSHS-IRM5A2-FL-B656	8/11/2022	-	856.23	-	850.24	4 - 6 ft	5.99 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B657	SSHS-IRM5A2-FL-B657	8/11/2022	-	856.94	-	851.12	4 - 6 ft	5.82 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B658	SSHS-IRM5A2-FL-B658	8/11/2022	-	856.60	-	850.82	4 - 6 ft	5.78 ft	1801428482	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B659	SSHS-IRM5A2-FL-B659	8/11/2022	-	856.09	-	850.17	4 - 6 ft	5.92 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B660	SSHS-IRM5A2-FL-B660	8/11/2022	-	855.88	-	849.91	4 - 6 ft	5.97 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B661	SSHS-IRM5A2-FL-B661	8/11/2022	-	856.06	-	850.13	4 - 6 ft	5.93 ft	1801428482	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B666	SSHS-IRM5A2-FL-B666	8/11/2022	-	855.90	-	850.57	4 - 6 ft	5.33 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B667	SSHS-IRM5A2-FL-B667	8/11/2022	-	856.09	-	850.27	4 - 6 ft	5.82 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B665A	SSHS-IRM5A2-FL-B665A	8/11/2022	-	855.95	-	850.31	4 - 6 ft	5.64 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B670	SSHS-IRM5A2-FL-B670	8/11/2022	-	856.48	-	850.78	4 - 6 ft	5.7 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B671	SSHS-IRM5A2-FL-B671	8/11/2022	-	856.24	-	850.60	4 - 6 ft	5.64 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B674	SSHS-IRM5A2-FL-B674	8/11/2022	-	856.51	-	850.61	4 - 6 ft	5.9 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B675	SSHS-IRM5A2-FL-B675	8/11/2022	-	855.98	-	850.45	4 - 6 ft	5.54 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B676	SSHS-IRM5A2-FL-B676	8/11/2022	-	856.17	-	850.57	4 - 6 ft	5.6 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B681	SSHS-IRM5A2-FL-B681	8/12/2022	-	855.62	-	850.57	4 - 6 ft	5.04 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-B682	SSHS-IRM5A2-FL-B682	8/12/2022	-	855.98	-	850.24	4 - 6 ft	5.74 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-B683	SSHS-IRM5A2-FL-B683	8/12/2022	-	856.24	-	850.26	4 - 6 ft	5.98 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-LPB1	SSHS-IRM5A2-FL-LPB1	8/17/2022	-	856.61	-	851.89	4 - 6 ft	4.73 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-LPB2	SSHS-IRM5A2-FL-LPB2	8/17/2022	-	856.75	-	852.00	4 - 6 ft	4.75 ft	1801430711	Not Excavated						
Northern Athletic Field	A6-S404	SSHS-IRM5A2-A6-S404	8/22/2022	-	856.78	-	852.47	4 - 6 ft	4.31 ft	1801432961	Not Excavated						
Northern Athletic Field	A6-S409	SSHS-IRM5A2-A6-S409	8/23/2022	-	857.41	-	852.36	4 - 6 ft	5.05 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-B402	SSHS-IRM5A2-A6-B402	8/23/2022	-	856.87	-	852.45	4 - 6 ft	4.42 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-B403	SSHS-IRM5A2-A6-B403	8/23/2022	-	857.05	-	852.42	4 - 6 ft	4.63 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-B404	SSHS-IRM5A2-A6-B404	8/23/2022	-	857.50	-	852.43	4 - 6 ft	5.08 ft	1801433661	Not Excavated						
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S400	SSHS-IRM5A2-ST-S400	8/24/2022	-	856.55	-	852.32	4 - 6 ft	4.23 ft	1801434602	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	ST-S603	SSHS-IRM5A2-ST-S603	8/24/2022	-	856.43	-	850.79	4 - 6 ft	5.64 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S401	SSHS-IRM5A2-ST-S401	8/24/2022	-	856.75	-	852.58	4 - 6 ft	4.17 ft	1801434602	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	ST-S402	SSHS-IRM5A2-ST-S402	8/24/2022	-	856.96	-	852.57	4 - 6 ft	4.39 ft	1801434611	Not Excavated						
Northern Athletic Field	ST-S403	SSHS-IRM5A2-ST-S403	8/24/2022	-	857.02	-	852.72	4 - 6 ft	4.31 ft	1801434611	Not Excavated						
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434611	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434612	Not Excavated				< 0.049 U	< 0.039 U	0.050 J	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated		< 31 U							
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated		< 33 U							
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated		< 33 U							
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated		< 31 U							
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438852	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated		< 150 U							
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438872	Not Excavated				< 0.051 U	< 0.040 U	0.43	< 0.055 U	< 0.051 UT	< 0.032 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated		< 38 U							
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated		< 170 U							
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated		< 32 U							
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438872	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated		< 330 U							
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated		< 31 U							
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440002	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated		< 30 U							
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated		< 30 U							
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated		< 30 U							
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated		< 30 U							
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440002	Not Excavated				< 0.050 U	< 0.040 U	2.4	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated		< 31 U							
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated		< 31 U							
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440002	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated		< 330 U							
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated		< 36 U							
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated		< 33 U							
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440322	Not Excavated				< 0.053 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440322	Not Excavated				< 0.29 U	< 0.23 U	< 0.27 U	< 0.31 U	< 0.29 U	< 0.18 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated		< 36 U							
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442132	Not Excavated				< 0.048 U	< 0.038 U	0.28	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated		< 36 U							
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442132	Not Excavated				< 0.056 U	< 0.044 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated		< 35 U							
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442132	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated		< 33 U							
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/8/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801442122	Not Excavated				< 0.058 U	< 0.046 U	< 0.056 U	< 0.063 U	< 0.058 U	< 0.036 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated		< 34 U							
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444222	Not Excavated				< 0.054 U	< 0.043 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444222	Not Excavated				< 0.055 U	< 0.043 U	0.16 J	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444222	Not Excavated				< 0.054 U	< 0.043 U	0.22 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434612	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.051 J	< 0.055 U	< 0.042 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated									
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated									
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated									
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438852	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.029 U	< 0.021 U	< 0.031 U	0.15 J	0.050 J	< 0.039 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438872	Not Excavated	< 0.052 U	0.042 J	< 0.031 UT	0.037 J	< 0.023 U	< 0.035 U	0.45	0.16 J	0.11 J
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438872	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.13 J	< 0.055 U	< 0.043 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440002	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440002	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	0.036 J	< 0.034 U	< 0.045 U	0.13 J	0.82
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440002	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440322	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.079 J	< 0.058 U	0.14 J
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440322	Not Excavated	< 0.29 U	< 0.23 U	< 0.17 U	< 0.19 U	< 0.13 U	< 0.20 U	< 0.26 U	< 0.32 U	0.95 J
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442132	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	0.078 J
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated									
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442132	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	0.026 J	< 0.039 U	< 0.050 U	0.080 J	< 0.048 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442132	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/8/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801442122	Not Excavated	< 0.060 U	< 0.046 U	< 0.035 U	< 0.038 U	< 0.027 U	< 0.040 U	< 0.052 U	< 0.064 U	< 0.050 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444222	Not Excavated	< 0.055 U	< 0.043 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444222	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	0.056 J	< 0.025 U	< 0.038 U	< 0.049 U	0.12 J	0.074 J
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444222	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	0.076 J	< 0.046 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	ST-S604	SSHS-IRM5A2-ST-S604	8/24/2022	-	856.63	-	850.76	4 - 6 ft	5.87 ft	1801434612	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B705	SSHS-IRM5A2-FL-B705	8/25/2022	-	856.09	-	850.26	4 - 6 ft	5.83 ft	1801435261	Not Excavated						
Northern Athletic Field	FL-B706	SSHS-IRM5A2-FL-B706	8/25/2022	-	855.85	-	850.58	4 - 6 ft	5.28 ft	1801435261	Not Excavated						
Northern Athletic Field	A6-S412	SSHS-IRM5A2-DUP212	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S412	SSHS-IRM5A2-A6-S412	9/1/2022	-	854.72	-	849.06	4 - 6 ft	5.66 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438851	Not Excavated						
Northern Athletic Field	A6-S413	SSHS-IRM5A2-A6-S413	9/1/2022	-	854.90	-	849.79	4 - 6 ft	5.11 ft	1801438852	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-S414	SSHS-IRM5A2-A6-S414	9/1/2022	-	855.10	-	850.15	4 - 6 ft	4.95 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S415	SSHS-IRM5A2-A6-S415	9/1/2022	-	855.36	-	850.45	4 - 6 ft	4.91 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S416	SSHS-IRM5A2-A6-S416	9/1/2022	-	855.68	-	851.14	4 - 6 ft	4.54 ft	1801438872	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-S417	SSHS-IRM5A2-A6-S417	9/1/2022	-	855.97	-	851.80	4 - 6 ft	4.17 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B407	SSHS-IRM5A2-A6-B407	9/1/2022	-	854.82	-	849.28	4 - 6 ft	5.55 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B408	SSHS-IRM5A2-A6-B408	9/1/2022	-	855.07	-	849.86	4 - 6 ft	5.2 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B409	SSHS-IRM5A2-A6-B409	9/1/2022	-	855.35	-	850.23	4 - 6 ft	5.12 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B410	SSHS-IRM5A2-A6-B410	9/1/2022	-	855.68	-	850.81	4 - 6 ft	4.87 ft	1801438872	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B411	SSHS-IRM5A2-A6-B411	9/1/2022	-	855.96	-	851.43	4 - 6 ft	4.53 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B420	SSHS-IRM5A2-DUP217	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B413	SSHS-IRM5A2-A6-B413	9/2/2022	-	855.06	-	849.20	4 - 6 ft	5.87 ft	1801440002	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-B414	SSHS-IRM5A2-A6-B414	9/2/2022	-	855.29	-	849.56	4 - 6 ft	5.73 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B415	SSHS-IRM5A2-A6-B415	9/2/2022	-	855.60	-	849.99	4 - 6 ft	5.61 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B416	SSHS-IRM5A2-A6-B416	9/2/2022	-	855.82	-	849.97	4 - 6 ft	5.86 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B417	SSHS-IRM5A2-A6-B417	9/2/2022	-	855.43	-	850.01	4 - 6 ft	5.42 ft	1801440002	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B418	SSHS-IRM5A2-A6-B418	9/2/2022	-	855.78	-	850.17	4 - 6 ft	5.62 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B419	SSHS-IRM5A2-A6-B419	9/2/2022	-	856.03	-	850.32	4 - 6 ft	5.71 ft	1801440002	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-B420	SSHS-IRM5A2-A6-B420	9/2/2022	-	855.74	-	850.66	4 - 6 ft	5.08 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B428	SSHS-IRM5A2-DUP218	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B421	SSHS-IRM5A2-A6-B421	9/6/2022	-	856.12	-	850.71	4 - 6 ft	5.41 ft	1801440322	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6-B422	SSHS-IRM5A2-A6-B422	9/6/2022	-	856.38	-	850.92	4 - 6 ft	5.46 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B423	SSHS-IRM5A2-A6-B423	9/6/2022	-	856.09	-	851.35	4 - 6 ft	4.74 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B424	SSHS-IRM5A2-A6-B424	9/6/2022	-	856.43	-	851.30	4 - 6 ft	5.12 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B425	SSHS-IRM5A2-A6-B425	9/6/2022	-	856.74	-	851.60	4 - 6 ft	5.14 ft	1801440322	Not Excavated	< 0.22 U	< 0.13 U	< 0.25 U	< 0.21 U	< 0.16 U	< 0.14 U
Northern Athletic Field	A6-B426	SSHS-IRM5A2-A6-B426	9/6/2022	-	856.41	-	851.62	4 - 6 ft	4.79 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B427	SSHS-IRM5A2-A6-B427	9/6/2022	-	856.78	-	851.87	4 - 6 ft	4.91 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/6/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-B429	SSHS-IRM5A2-A6-B429	9/8/2022	-	857.17	-	852.53	4 - 6 ft	4.64 ft	1801442132	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442131	Not Excavated						
Northern Athletic Field	A4-S400BOT	SSHS-IRM5A2-A3-S400BOT	9/8/2022	-	857.72	-	852.54	4 - 6 ft	5.19 ft	1801442132	Not Excavated	< 0.043 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A6-S616	SSHS-IRM5A2-A6-S616	9/8/2022	-	856.98	-	851.15	4 - 6 ft	5.83 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S618	SSHS-IRM5A2-A6-S618	9/8/2022	-	856.58	-	850.99	4 - 6 ft	5.59 ft	1801442132	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-S619	SSHS-IRM5A2-A6-S619	9/8/2022	-	856.37	-	851.21	4 - 6 ft	5.16 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-B428	SSHS-IRM5A2-A6-B428	9/8/2022	-	857.62	-	852.36	4 - 6 ft	5.26 ft	1801442122	Not Excavated	< 0.045 U	< 0.026 U	< 0.051 U	< 0.043 U	< 0.033 U	< 0.028 U
Northern Athletic Field	A6-B430	SSHS-IRM5A2-A6-B430	9/9/2022	-	857.14	-	852.81	4 - 6 ft	4.33 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-DUP224	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S419	SSHS-IRM5A2-DUP222	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S426	SSHS-IRM5A2-DUP223	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444222	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S418	SSHS-IRM5A2-A6-S418	9/13/2022	-	856.67	-	852.34	4 - 6 ft	4.33 ft	1801444222	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-S419	SSHS-IRM5A2-A6-S419	9/13/2022	-	856.43	-	852.02	4 - 6 ft	4.41 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S420	SSHS-IRM5A2-A6-S420	9/13/2022	-	856.61	-	852.34	4 - 6 ft	4.27 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S421	SSHS-IRM5A2-A6-S421	9/13/2022	-	858.17	-	852.21	4 - 6 ft	5.96 ft	1801444222	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-S423	SSHS-IRM5A2-A6-S423	9/13/2022	-	857.89	-	852.03	4 - 6 ft	5.86 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S424	SSHS-IRM5A2-A6-S424	9/13/2022	-	857.49	-	852.32	4 - 6 ft	5.17 ft	1801444221	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444222	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444222	Not Excavated				< 0.055 U	< 0.043 U	< 0.053 U	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444222	Not Excavated				< 0.053 U	< 0.042 U	0.095 J	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated		< 33 U							
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated		< 33 U							
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated		< 31 U							
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated		< 31 U							
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated		< 32 U							
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451962	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated		< 32 U							
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated		< 35 U							
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated		< 30 U							
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated		< 33 U							
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453572	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated		< 32 U							
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated		< 31 U							
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453572	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.032 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453572	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated		< 33 U							
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated		< 34 U							
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453572	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated		< 32 UT							
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated		< 32 U							
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated		< 33 U							
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453582	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated		< 32 U							
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated		< 30 U							
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated		< 32 U							
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453582	Not Excavated				< 0.051 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated		< 34 U							
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453582	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated		< 32 U							
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated		< 33 U							
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated		< 32 U							
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453582	Not Excavated				< 0.052 U	< 0.041 U	0.071 J	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated		< 30 U							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated		< 31 U							
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465922	Not Excavated				< 0.050 U	< 0.039 U	0.35	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated		< 33 U							
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated		< 32 U							
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated		< 32 U							
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465932	Not Excavated				< 0.050 U	< 0.040 U	0.097 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated		< 32 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444222	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444222	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	0.043 J	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444222	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	0.073 J
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451962	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	0.056 J
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453572	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453572	Not Excavated	< 0.052 U	< 0.040 U	< 0.030 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453572	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453572	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	0.057 J	< 0.043 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453582	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453582	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453582	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated									
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453582	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated									
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465922	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	0.056 J	0.063 J
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated									
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465932	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6-S425	SSHS-IRM5A2-A6-S425	9/13/2022	-	857.09	-	852.43	4 - 6 ft	4.66 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-S426	SSHS-IRM5A2-A6-S426	9/13/2022	-	856.86	-	852.62	4 - 6 ft	4.24 ft	1801444222	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B432	SSHS-IRM5A2-A6-B432	9/13/2022	-	857.11	-	852.45	4 - 6 ft	4.66 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B433	SSHS-IRM5A2-A6-B433	9/13/2022	-	856.73	-	852.52	4 - 6 ft	4.21 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B434	SSHS-IRM5A2-A6-B434	9/13/2022	-	857.22	-	852.34	4 - 6 ft	4.88 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B435	SSHS-IRM5A2-A6-B435	9/13/2022	-	856.75	-	852.01	4 - 6 ft	4.74 ft	1801444222	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-B436	SSHS-IRM5A2-A6-B436	9/13/2022	-	857.68	-	852.16	4 - 6 ft	5.52 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B221-BOT	SSHS-IRM5A2-A6-B221-BOT	9/13/2022	-	857.14	-	852.34	4 - 6 ft	4.8 ft	1801444222	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6-B227-BOT	SSHS-IRM5A2-A6-B227-BOT	9/13/2022	-	857.82	-	852.10	4 - 6 ft	5.72 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B624	SSHS-IRM5A2-DUP232	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-B438	SSHS-IRM5A2-A6-B438	9/16/2022	-	857.36	-	852.72	4 - 6 ft	4.64 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-S623	SSHS-IRM5A2-A6-S623	9/16/2022	-	856.46	-	851.04	4 - 6 ft	5.42 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-B623	SSHS-IRM5A2-A6-B623	9/16/2022	-	856.48	-	850.52	4 - 6 ft	5.96 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-B624	SSHS-IRM5A2-A6-B624	9/16/2022	-	856.53	-	850.67	4 - 6 ft	5.86 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-S627	SSHS-IRM5A2-DUP236	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S430	SSHS-IRM5A2-A6-S430	9/27/2022	-	855.91	-	851.69	4 - 6 ft	4.22 ft	1801451962	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-S625	SSHS-IRM5A2-A6-S625	9/27/2022	-	855.78	-	849.77	4 - 6 ft	6.01 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S626	SSHS-IRM5A2-A6-S626	9/27/2022	-	855.46	-	849.74	4 - 6 ft	5.72 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B625	SSHS-IRM5A2-A6-B625	9/27/2022	-	855.99	-	850.36	4 - 6 ft	5.63 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S627	SSHS-IRM5A2-A6-S627	9/27/2022	-	855.19	-	849.85	4 - 6 ft	5.34 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B630	SSHS-IRM5A2-DUP238	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453572	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-DUP239	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-S628	SSHS-IRM5A2-A6-S628	9/29/2022	-	854.98	-	850.08	4 - 6 ft	4.9 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B626	SSHS-IRM5A2-A6-B626	9/29/2022	-	856.56	-	850.61	4 - 6 ft	5.95 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B627	SSHS-IRM5A2-A6-B627	9/29/2022	-	856.26	-	850.62	4 - 6 ft	5.64 ft	1801453572	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B630	SSHS-IRM5A2-A6-B630	9/29/2022	-	856.38	-	851.07	4 - 6 ft	5.31 ft	1801453572	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B631	SSHS-IRM5A2-A6-B631	9/29/2022	-	856.15	-	850.90	4 - 6 ft	5.25 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B632	SSHS-IRM5A2-A6-B632	9/29/2022	-	856.03	-	850.65	4 - 6 ft	5.39 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B633	SSHS-IRM5A2-A6-B633	9/29/2022	-	855.75	-	849.78	4 - 6 ft	5.96 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B634	SSHS-IRM5A2-A6-B634	9/29/2022	-	855.82	-	850.68	4 - 6 ft	5.14 ft	1801453572	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B635	SSHS-IRM5A2-A6-B635	9/29/2022	-	855.59	-	850.08	4 - 6 ft	5.51 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B636	SSHS-IRM5A2-A6-B636	9/29/2022	-	855.49	-	849.68	4 - 6 ft	5.81 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B637	SSHS-IRM5A2-A6-B637	9/29/2022	-	855.57	-	850.43	4 - 6 ft	5.14 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B638	SSHS-IRM5A2-A6-B638	9/29/2022	-	855.42	-	850.04	4 - 6 ft	5.38 ft	1801453582	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B639	SSHS-IRM5A2-A6-B639	9/29/2022	-	855.29	-	850.29	4 - 6 ft	5.01 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B640	SSHS-IRM5A2-A6-B640	9/29/2022	-	855.18	-	849.79	4 - 6 ft	5.4 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B641	SSHS-IRM5A2-A6-B641	9/29/2022	-	855.25	-	850.54	4 - 6 ft	4.71 ft	1801453582	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B642	SSHS-IRM5A2-A6-B642	9/29/2022	-	855.11	-	850.21	4 - 6 ft	4.9 ft	1801453582	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-B643	SSHS-IRM5A2-A6-B643	9/29/2022	-	855.14	-	850.75	4 - 6 ft	4.38 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B644	SSHS-IRM5A2-A6-B644	9/29/2022	-	855.15	-	850.25	4 - 6 ft	4.9 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453581	Not Excavated						
Northern Athletic Field	A6-B645	SSHS-IRM5A2-A6-B645	9/29/2022	-	855.06	-	850.00	4 - 6 ft	5.06 ft	1801453582	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B208-S2	SSHS-IRM5A2-A6-B208-S2	10/11/2022	-	852.78	-	847.90	4 - 6 ft	4.88 ft	1801460131	Not Excavated						
Northern Athletic Field	A6-S631	SSHS-IRM5A2-DUP242	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B255	SSHS-IRM5A2-A6-B255	10/20/2022	-	857.51	-	853.31	4 - 6 ft	4.19 ft	1801465922	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-S436	SSHS-IRM5A2-A6-S436	10/20/2022	-	856.41	-	852.13	4 - 6 ft	4.28 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S437	SSHS-IRM5A2-A6-S437	10/20/2022	-	856.93	-	852.04	4 - 6 ft	4.89 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-S438	SSHS-IRM5A2-A6-S438	10/20/2022	-	857.45	-	851.80	4 - 6 ft	5.66 ft	1801465921	Not Excavated						
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B443	SSHS-IRM5A2-A6-B443	10/20/2022	-	856.60	-	851.62	4 - 6 ft	4.99 ft	1801465932	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B444	SSHS-IRM5A2-A6-B444	10/20/2022	-	856.43	-	851.70	4 - 6 ft	4.74 ft	1801465931	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465932	Not Excavated				< 0.052 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated		< 32 U							
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated		< 32 U							
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated		< 32 U							
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated		< 32 U							
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated		< 30 U							
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465942	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated		< 31 U							
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated		< 32 U							
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated		< 34 U							
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469412	Not Excavated				< 0.052 U	< 0.041 U	0.10 BJ	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated		< 30 U							
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469412	Not Excavated				< 0.048 U	< 0.038 U	0.13 BJ	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486622	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated		< 32 U							
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated		< 33 U							
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491412	Not Excavated				< 0.052 U	< 0.041 U	0.051 J	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated		< 33 U							
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated		< 37 U							
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated		< 34 U							
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491412	Not Excavated				< 0.056 U	< 0.044 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated		< 35 U							
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated		< 35 U							
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated		< 38 U							
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491422	Not Excavated				< 0.060 U	< 0.047 U	0.11 J	< 0.065 U	< 0.060 U	< 0.037 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated		< 31 U							
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated		< 32 U							
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491422	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated		< 35 U							
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated		< 37 U							
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491422	Not Excavated				< 0.054 U	< 0.043 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated		< 32 U							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492042	Not Excavated				< 0.053 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493702	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated		< 32 U							

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465932	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465942	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.051 U	< 0.039 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated									
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated									
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469412	Not Excavated	< 0.054 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469412	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated									
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated									
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated									
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486622	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated									
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated									
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491412	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.067 J	< 0.058 U	< 0.045 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491412	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.038 U	< 0.050 U	< 0.062 U	< 0.048 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491422	Not Excavated	< 0.061 U	< 0.047 U	< 0.036 U	0.069 J	< 0.027 U	< 0.041 U	< 0.054 U	0.076 J	< 0.051 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491422	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	0.071 J	< 0.060 U	< 0.046 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491422	Not Excavated	< 0.055 U	< 0.043 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	0.20 J	< 0.059 U	< 0.046 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated									
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492042	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.11 J	< 0.058 U	< 0.045 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493702	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.054 J	< 0.053 U	< 0.041 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6-B445	SSHS-IRM5A2-A6-B445	10/20/2022	-	856.89	-	851.72	4 - 6 ft	5.18 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B646	SSHS-IRM5A2-A6-B646	10/20/2022	-	854.19	-	849.62	4 - 6 ft	4.57 ft	1801465932	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B647	SSHS-IRM5A2-A6-B647	10/20/2022	-	854.66	-	849.88	4 - 6 ft	4.78 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S630	SSHS-IRM5A2-A6-S630	10/20/2022	-	854.40	-	850.18	4 - 6 ft	4.21 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S631	SSHS-IRM5A2-A6-S631	10/20/2022	-	855.34	-	850.24	4 - 6 ft	5.11 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S635	SSHS-IRM5A2-A6-S635	10/20/2022	-	855.31	-	850.30	4 - 6 ft	5.01 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S636	SSHS-IRM5A2-A6-S636	10/20/2022	-	854.37	-	850.11	4 - 6 ft	4.26 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S637	SSHS-IRM5A2-A6-S637	10/20/2022	-	854.11	-	849.95	4 - 6 ft	4.16 ft	1801465942	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-S638	SSHS-IRM5A2-A6-S638	10/20/2022	-	854.32	-	850.07	4 - 6 ft	4.26 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-DUP244	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated						
Northern Athletic Field	A6-MS1	SSHS-IRM5A2-A6-MS1	10/25/2022	-	857.56	-	853.30	4 - 6 ft	4.26 ft	1801468421	Not Excavated						
Northern Athletic Field	A1-VAULT-S7	SSHS-IRM5A2-A1-VAULT-S7	10/26/2022	-	857.05	-	851.01	4 - 6 ft	6.04 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S8	SSHS-IRM5A2-A1-VAULT-S8	10/26/2022	-	857.16	-	851.14	4 - 6 ft	6.02 ft	1801469412	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A1-VAULT-S9	SSHS-IRM5A2-A1-VAULT-S9	10/26/2022	-	857.38	-	851.45	4 - 6 ft	5.92 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S10	SSHS-IRM5A2-A1-VAULT-S10	10/26/2022	-	857.40	-	851.77	4 - 6 ft	5.63 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S11	SSHS-IRM5A2-A1-VAULT-S11	10/26/2022	-	857.25	-	851.68	4 - 6 ft	5.57 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S12	SSHS-IRM5A2-A1-VAULT-S12	10/26/2022	-	857.12	-	851.14	4 - 6 ft	5.98 ft	1801469412	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-S629-BOT	SSHS-IRM5A2-A6-S629-BOT	11/8/2022	-	854.99	-	850.81	4 - 6 ft	4.19 ft	1801476081	Not Excavated						
Northern Athletic Field	A6N-S402	SSHS-IRM5A2-A6N-S402	12/1/2022	-	854.78	-	850.25	4 - 6 ft	4.53 ft	1801486621	Not Excavated						
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486621	Not Excavated						
Northern Athletic Field	A6N-S404	SSHS-IRM5A2-A6N-S404	12/1/2022	-	855.16	-	851.02	4 - 6 ft	4.13 ft	1801486622	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6N-B227	SSHS-IRM5A2-A6N-B227	12/5/2022	-	857.43	-	852.44	4 - 6 ft	4.99 ft	1801487861	Not Excavated						
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-DUP267	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-DUP269	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated						
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-B2	SSHS-ISMP-DUP3	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491412	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	DO-S3	SSHS-ISMP-DO-S3	12/9/2022	-	857.32	-	851.57	4 - 6 ft	5.75 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-S4	SSHS-ISMP-DO-S4	12/9/2022	-	856.96	-	851.92	4 - 6 ft	5.04 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-B2	SSHS-ISMP-DO-B2	12/9/2022	-	--	-	849.69	4 - 6 ft	4 - 6 ft	1801491412	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A6N-B229	SSHS-IRM5A2-A6N-B229	12/9/2022	-	858.27	-	852.62	4 - 6 ft	5.64 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B230	SSHS-IRM5A2-A6N-B230	12/9/2022	-	857.98	-	852.05	4 - 6 ft	5.94 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B231	SSHS-IRM5A2-A6N-B231	12/9/2022	-	858.46	-	853.21	4 - 6 ft	5.25 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B232	SSHS-IRM5A2-A6N-B232	12/9/2022	-	858.67	-	852.91	4 - 6 ft	5.75 ft	1801491422	Not Excavated	< 0.046 U	< 0.026 U	< 0.052 U	< 0.044 U	< 0.034 U	< 0.029 U
Northern Athletic Field	A6N-B234	SSHS-IRM5A2-A6N-B234	12/9/2022	-	858.85	-	853.15	4 - 6 ft	5.69 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B237	SSHS-IRM5A2-A6N-B237	12/9/2022	-	858.88	-	853.12	4 - 6 ft	5.77 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B239	SSHS-IRM5A2-A6N-B239	12/9/2022	-	858.67	-	853.50	4 - 6 ft	5.16 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B240	SSHS-IRM5A2-A6N-B240	12/9/2022	-	858.41	-	853.38	4 - 6 ft	5.03 ft	1801491422	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6N-B241	SSHS-IRM5A2-A6N-B241	12/9/2022	-	858.66	-	852.90	4 - 6 ft	5.76 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B242	SSHS-IRM5A2-A6N-B242	12/9/2022	-	858.63	-	852.97	4 - 6 ft	5.66 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B243	SSHS-IRM5A2-A6N-B243	12/9/2022	-	857.97	-	852.68	4 - 6 ft	5.29 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B244	SSHS-IRM5A2-A6N-B244	12/9/2022	-	857.86	-	853.31	4 - 6 ft	4.55 ft	1801491422	Not Excavated	< 0.041 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6N-S800-S1	SSHS-IRM5A2-A6N-S800-S1	12/9/2022	-	854.80	-	850.44	4 - 6 ft	4.36 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S4	SSHS-IRM5A2-A6N-S800-S4	12/9/2022	-	854.87	-	850.61	4 - 6 ft	4.26 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-DUP271	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B213-S3	SSHS-IRM5A2-A6N-B213-S3	12/10/2022	-	855.19	-	851.12	4 - 6 ft	4.08 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B213-S4	SSHS-IRM5A2-A6N-B213-S4	12/10/2022	-	855.49	-	851.32	4 - 6 ft	4.17 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492041	Not Excavated						
Northern Athletic Field	A6N-B213-BOT	SSHS-IRM5A2-A6N-B213-BOT	12/10/2022	-	855.33	-	851.21	4 - 6 ft	4.13 ft	1801492042	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-DUP272	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S12	SSHS-IRM5A2-A6N-S800-S12	12/14/2022	-	855.10	-	850.59	4 - 6 ft	4.51 ft	1801493702	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6N-S800-S15	SSHS-IRM5A2-A6N-S800-S15	12/14/2022	-	855.29	-	850.30	4 - 6 ft	4.99 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S18	SSHS-IRM5A2-A6N-S800-S18	12/14/2022	-	855.70	-	850.99	4 - 6 ft	4.71 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S21	SSHS-IRM5A2-A6N-S800-S21	12/14/2022	-	855.39	-	851.02	4 - 6 ft	4.37 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493701	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493702	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 110 U								
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517351	Not Excavated	< 110 U								
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated	< 110 U								
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated	< 110 U								
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated	< 110 U								
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517382	Not Excavated				< 0.050 U	< 0.039 U	0.086 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated	< 110 U								
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated	< 110 U								
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated	< 120 U								
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526802	Not Excavated				< 0.056 U	< 0.044 U	0.15 BJ	< 0.060 U	< 0.056 U	< 0.035 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570202	Not Excavated				< 0.050 U	< 0.039 U	0.081 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	LP2-2	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 120 U								
Northern Athletic Field	LP2-3	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570202	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	LP2-5	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP1-1	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570202	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	LP1-3	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP1-4	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	LP1-5	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated	< 120 U								
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575442	Not Excavated				< 0.056 U	< 0.045 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575442	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575442	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575442	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated	< 600 U								
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801589971	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801589972	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590652	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590652	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590652	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590652	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590662	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493702	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated									
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517351	Not Excavated									
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated									
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated									
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated									
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517382	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.18 J	0.090 J	0.090 J
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated									
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated									
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526802	Not Excavated	< 0.057 U	< 0.044 U	0.040 J	0.037 J	< 0.026 U	< 0.038 U	4.1	0.076 J	< 0.048 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated									
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570202	Not Excavated	< 0.051 U	0.040 J	< 0.030 U	0.053 J	< 0.023 U	< 0.034 U	0.051 J	0.19 J	0.061 J
Northern Athletic Field	LP2-2	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP2-3	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570202	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	0.031 J	0.036 J	< 0.032 U	0.043 J	< 0.051 U	< 0.039 U
Northern Athletic Field	LP2-5	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP1-1	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated									
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570202	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.14 J	0.090 J	< 0.044 U
Northern Athletic Field	LP1-3	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP1-4	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	LP1-5	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated									
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated									
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575442	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.039 U	< 0.051 U	< 0.062 U	< 0.048 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575442	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.033 J	< 0.022 U	< 0.033 U	0.12 J	0.068 J	< 0.041 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575442	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575442	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.053 J	< 0.055 U	< 0.042 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801589972	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590652	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.041 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590652	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590652	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590652	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	0.048 J	< 0.048 U	< 0.059 U	< 0.045 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated									
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590662	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 U

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6N-S800-S24	SSHS-IRM5A2-A6N-S800-S24	12/14/2022	-	855.26	-	851.16	4 - 6 ft	4.11 ft	1801493702	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-DUP1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated						
Northern Athletic Field	BB-S1	SSHS-ISMP-BB-S1	2/8/2023	-	854.26	-	848.78	4 - 6 ft	5.48 ft	1801517381	Not Excavated						
Northern Athletic Field	BB-S2	SSHS-ISMP-BB-S2	2/8/2023	-	854.85	-	849.25	4 - 6 ft	5.61 ft	1801517381	Not Excavated						
Northern Athletic Field	BB-S3	SSHS-ISMP-BB-S3	2/8/2023	-	854.98	-	849.39	4 - 6 ft	5.59 ft	1801517381	Not Excavated						
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517381	Not Excavated						
Northern Athletic Field	BB-S4	SSHS-ISMP-BB-S4	2/8/2023	-	854.87	-	848.92	4 - 6 ft	5.96 ft	1801517382	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	BB-B1	SSHS-ISMP-BB-B1	2/8/2023	-	854.97	-	849.00	4 - 6 ft	5.97 ft	1801517381	Not Excavated						
Northern Athletic Field	A6-B267A	SSHS-IRM5A2-A6-B267A	2/27/2023	-	858.27	-	853.09	4 - 6 ft	5.18 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526801	Not Excavated						
Northern Athletic Field	A6-B268A	SSHS-IRM5A2-A6-B268A	2/27/2023	-	857.60	-	853.35	4 - 6 ft	4.24 ft	1801526802	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	LP2-3	ISMP-LP-DUP	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570201	Not Excavated						
Northern Athletic Field	LP2-1	ISMP-LP2-1	5/23/2023	-	856.79	-	851.84	4 - 6 ft	4.95 ft	1801570202	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	LP2-2	ISMP-LP2-2	5/23/2023	-	--	-	851.88	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP2-3	ISMP-LP2-3	5/23/2023	-	--	-	851.78	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP2-4	ISMP-LP2-4	5/23/2023	-	--	-	852.04	4 - 6 ft	4 - 6 ft	1801570202	Not Excavated	< 0.036 U	< 0.020 U	< 0.040 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	LP2-5	ISMP-LP2-5	5/23/2023	-	--	-	851.55	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP1-1	ISMP-LP1-1	5/23/2023	-	856.79	-	851.96	4 - 6 ft	4.83 ft	1801570201	Not Excavated						
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP1-2	ISMP-LP1-2	5/23/2023	-	--	-	852.50	4 - 6 ft	4 - 6 ft	1801570202	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	LP1-3	ISMP-LP1-3	5/23/2023	-	--	-	852.07	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP1-4	ISMP-LP1-4	5/23/2023	-	--	-	852.19	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	LP1-5	ISMP-LP1-5	5/23/2023	-	--	-	852.49	4 - 6 ft	4 - 6 ft	1801570201	Not Excavated						
Northern Athletic Field	NAF-IG-S2	SSHS-ISMP-NAF-IG-S2	5/30/2023	-	853.38	-	847.79	4 - 6 ft	5.59 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S3	SSHS-ISMP-NAF-IG-S3	5/30/2023	-	853.89	-	847.99	4 - 6 ft	5.9 ft	1801572471	Not Excavated						
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-DUP303	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-S1	SSHS-IRM5A2-AREA C-B3-S1	6/6/2023	-	856.64	-	852.31	4 - 6 ft	4.33 ft	1801575442	Not Excavated	< 0.043 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	AREA C-B3-S4	SSHS-IRM5A2-AREA C-B3-S4	6/6/2023	-	856.62	-	852.25	4 - 6 ft	4.37 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-S5	SSHS-IRM5A2-AREA C-B3-S5	6/6/2023	-	856.51	-	851.99	4 - 6 ft	4.52 ft	1801575442	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-B1	SSHS-IRM5A2-AREA C-B3-B1	6/6/2023	-	856.30	-	851.75	4 - 6 ft	4.55 ft	1801575442	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	AREA C-B3-B2	SSHS-IRM5A2-AREA C-B3-B2	6/6/2023	-	856.45	-	851.89	4 - 6 ft	4.56 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-BOT	SSHS-IRM5A2-AREA C-B3-BOT	6/6/2023	-	856.46	-	851.67	4 - 6 ft	4.78 ft	1801575442	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-UT-B3	SSHS-ISMP-NAF-UT-B3	7/10/2023	-	852.74	-	848.10	4 - 6 ft	4.64 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S5	SSHS-ISMP-NAF-UT-S5	7/10/2023	-	852.91	-	848.28	4 - 6 ft	4.63 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S6	SSHS-ISMP-NAF-UT-S6	7/10/2023	-	852.98	-	848.19	4 - 6 ft	4.79 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S7	SSHS-ISMP-NAF-UT-S7	7/10/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801589972	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-DUP9A	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590652	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-DUP10A	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-DUP11A	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S8	SSHS-ISMP-NAF-UT-S8	7/11/2023	-	853.33	-	848.34	4 - 6 ft	4.98 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S9	SSHS-ISMP-NAF-UT-S9	7/11/2023	-	853.35	-	848.28	4 - 6 ft	5.07 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S11	SSHS-ISMP-NAF-UT-S11	7/11/2023	-	853.60	-	848.76	4 - 6 ft	4.84 ft	1801590652	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-UT-S12	SSHS-ISMP-NAF-UT-S12	7/11/2023	-	853.57	-	848.71	4 - 6 ft	4.87 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S14	SSHS-ISMP-NAF-UT-S14	7/11/2023	-	853.98	-	849.25	4 - 6 ft	4.73 ft	1801590652	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-S16	SSHS-ISMP-NAF-UT-S16	7/11/2023	-	854.00	-	849.21	4 - 6 ft	4.79 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-B4	SSHS-ISMP-NAF-UT-B4	7/11/2023	-	853.33	-	848.13	4 - 6 ft	5.2 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-B5	SSHS-ISMP-NAF-UT-B5	7/11/2023	-	853.60	-	848.60	4 - 6 ft	5 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-B6	SSHS-ISMP-NAF-UT-B6	7/11/2023	-	853.96	-	849.01	4 - 6 ft	4.96 ft	1801590652	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	NAF-UT-S18	SSHS-ISMP-NAF-UT-S18	7/11/2023	-	854.33	-	849.55	4 - 6 ft	4.78 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S20	SSHS-ISMP-NAF-UT-S20	7/11/2023	-	854.27	-	849.63	4 - 6 ft	4.63 ft	1801590651	Not Excavated						
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S23	SSHS-ISMP-NAF-UT-S23	7/11/2023	-	854.62	-	849.92	4 - 6 ft	4.7 ft	1801590662	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590662	Not Excavated				< 0.051 U	< 0.040 U	0.069 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590662	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.033 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated	< 140 U								
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594062	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.035 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594072	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594072	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated	< 140 U								
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594762	Not Excavated				< 0.063 U	< 0.050 U	< 0.060 U	< 0.068 U	< 0.063 U	< 0.039 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594762	Not Excavated				< 0.058 U	< 0.046 U	< 0.055 U	< 0.062 U	< 0.058 U	< 0.036 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594762	Not Excavated				< 0.051 U	< 0.040 U	0.15 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594762	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated	< 130 U								
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594782	Not Excavated				< 0.057 U	< 0.045 U	< 0.055 U	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated	< 120 U								

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590662	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590662	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated									
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594062	Not Excavated	< 0.057 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.050 U	0.069 J	< 0.047 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated									
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594072	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594072	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated									
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594762	Not Excavated	< 0.064 U	< 0.050 U	< 0.038 U	< 0.041 U	< 0.029 U	< 0.043 U	0.12 J	< 0.070 U	< 0.054 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594762	Not Excavated	< 0.059 U	< 0.046 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.040 U	< 0.052 U	< 0.064 U	< 0.049 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594762	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	0.034 J	< 0.023 U	< 0.035 U	< 0.045 U	0.084 J	< 0.043 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated									
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594762	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594782	Not Excavated	< 0.058 U	< 0.045 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.039 U	< 0.051 U	< 0.063 U	< 0.049 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated									
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated									
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated									
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated									
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	NAF-UT-S25	SSHS-ISMP-NAF-UT-S25	7/11/2023	-	854.53	-	849.85	4 - 6 ft	4.69 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-B7	SSHS-ISMP-NAF-UT-B7	7/11/2023	-	854.29	-	849.34	4 - 6 ft	4.95 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-B8	SSHS-ISMP-NAF-UT-B8	7/11/2023	-	854.56	-	849.72	4 - 6 ft	4.84 ft	1801590662	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	NAF-UT-S27	SSHS-ISMP-NAF-UT-S27	7/11/2023	-	854.55	-	850.36	4 - 6 ft	4.2 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S32	SSHS-ISMP-NAF-UT-S32	7/11/2023	-	854.11	-	848.89	4 - 6 ft	5.22 ft	1801590662	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	NAF-UT-S34	SSHS-ISMP-NAF-UT-S34	7/11/2023	-	854.16	-	848.86	4 - 6 ft	5.3 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-B9	SSHS-ISMP-NAF-UT-B9	7/11/2023	-	854.27	-	850.19	4 - 6 ft	4.07 ft	1801590661	Not Excavated						
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-DUP13A	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-DUP14A	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S37	SSHS-ISMP-NAF-UT-S37	7/17/2023	-	856.38	-	851.59	4 - 6 ft	4.78 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S39	SSHS-ISMP-NAF-UT-S39	7/17/2023	-	856.36	-	851.47	4 - 6 ft	4.89 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S42	SSHS-ISMP-NAF-UT-S42	7/17/2023	-	856.56	-	851.54	4 - 6 ft	5.02 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S43	SSHS-ISMP-NAF-UT-S43	7/17/2023	-	856.47	-	851.24	4 - 6 ft	5.23 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S45	SSHS-ISMP-NAF-UT-S45	7/17/2023	-	856.28	-	851.45	4 - 6 ft	4.83 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-B11	SSHS-ISMP-NAF-UT-B11	7/17/2023	-	856.30	-	851.50	4 - 6 ft	4.81 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-B12	SSHS-ISMP-NAF-UT-B12	7/17/2023	-	856.52	-	851.15	4 - 6 ft	5.37 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-B13	SSHS-ISMP-NAF-UT-B13	7/17/2023	-	856.08	-	851.19	4 - 6 ft	4.9 ft	1801594062	Not Excavated	< 0.043 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.027 U
Northern Athletic Field	NAF-UT-S47	SSHS-ISMP-NAF-UT-S47	7/17/2023	-	856.28	-	851.49	4 - 6 ft	4.79 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S48	SSHS-ISMP-NAF-UT-S48	7/17/2023	-	855.19	-	850.25	4 - 6 ft	4.93 ft	1801594061	Not Excavated						
Northern Athletic Field	NAF-UT-S49	SSHS-ISMP-NAF-UT-S49	7/17/2023	-	854.96	-	850.73	4 - 6 ft	4.23 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S50	SSHS-ISMP-NAF-UT-S50	7/17/2023	-	854.95	-	850.90	4 - 6 ft	4.05 ft	1801594072	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-UT-S51	SSHS-ISMP-NAF-UT-S51	7/17/2023	-	855.00	-	850.61	4 - 6 ft	4.39 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S52	SSHS-ISMP-NAF-UT-S52	7/17/2023	-	854.86	-	850.64	4 - 6 ft	4.22 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-B14	SSHS-ISMP-NAF-UT-B14	7/17/2023	-	855.00	-	850.82	4 - 6 ft	4.18 ft	1801594072	Not Excavated	< 0.040 U	0.023 J	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-B15	SSHS-ISMP-NAF-UT-B15	7/17/2023	-	855.00	-	850.52	4 - 6 ft	4.47 ft	1801594071	Not Excavated						
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-DUP15A	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-DUP16A	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-S55	SSHS-ISMP-NAF-UT-S55	7/18/2023	-	856.39	-	851.66	4 - 6 ft	4.73 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S56	SSHS-ISMP-NAF-UT-S56	7/18/2023	-	856.59	-	851.79	4 - 6 ft	4.81 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S57	SSHS-ISMP-NAF-UT-S57	7/18/2023	-	856.55	-	851.74	4 - 6 ft	4.81 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S58	SSHS-ISMP-NAF-UT-S58	7/18/2023	-	856.39	-	851.74	4 - 6 ft	4.65 ft	1801594762	Not Excavated	< 0.049 U	< 0.028 U	< 0.055 U	< 0.046 U	< 0.035 U	< 0.030 U
Northern Athletic Field	NAF-UT-B17	SSHS-ISMP-NAF-UT-B17	7/18/2023	-	856.43	-	851.67	4 - 6 ft	4.75 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S61	SSHS-ISMP-NAF-UT-S61	7/18/2023	-	856.63	-	851.35	4 - 6 ft	5.28 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S62	SSHS-ISMP-NAF-UT-S62	7/18/2023	-	856.68	-	852.56	4 - 6 ft	4.13 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S63	SSHS-ISMP-NAF-UT-S63	7/18/2023	-	856.68	-	851.30	4 - 6 ft	5.38 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S59	SSHS-ISMP-NAF-UT-S59	7/18/2023	-	856.74	-	851.28	4 - 6 ft	5.47 ft	1801594762	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.028 U
Northern Athletic Field	NAF-UT-S60	SSHS-ISMP-NAF-UT-S60	7/18/2023	-	856.67	-	851.40	4 - 6 ft	5.27 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-B18	SSHS-ISMP-NAF-UT-B18	7/18/2023	-	856.63	-	850.97	4 - 6 ft	5.66 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-B19	SSHS-ISMP-NAF-UT-B19	7/18/2023	-	856.79	-	852.58	4 - 6 ft	4.21 ft	1801594762	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594761	Not Excavated						
Northern Athletic Field	NAF-UT-S69	SSHS-ISMP-NAF-UT-S69	7/18/2023	-	856.23	-	851.07	4 - 6 ft	5.16 ft	1801594762	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-UT-S70	SSHS-ISMP-NAF-UT-S70	7/18/2023	-	856.28	-	850.96	4 - 6 ft	5.31 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-S71	SSHS-ISMP-NAF-UT-S71	7/18/2023	-	856.23	-	851.25	4 - 6 ft	4.98 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-S72	SSHS-ISMP-NAF-UT-S72	7/18/2023	-	856.18	-	851.16	4 - 6 ft	5.02 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-B21	SSHS-ISMP-NAF-UT-B21	7/18/2023	-	856.15	-	850.75	4 - 6 ft	5.4 ft	1801594782	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	NAF-UT-B22	SSHS-ISMP-NAF-UT-B22	7/18/2023	-	856.30	-	852.22	4 - 6 ft	4.08 ft	1801594781	Not Excavated						
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-DUP18A	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S78	SSHS-ISMP-NAF-UT-S78	7/20/2023	-	854.88	-	850.56	4 - 6 ft	4.32 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S79	SSHS-ISMP-NAF-UT-S79	7/20/2023	-	855.16	-	851.01	4 - 6 ft	4.15 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B25	SSHS-ISMP-NAF-UT-B25	7/20/2023	-	854.88	-	850.62	4 - 6 ft	4.25 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-B26	SSHS-ISMP-NAF-UT-B26	7/20/2023	-	855.07	-	850.78	4 - 6 ft	4.28 ft	1801596501	Not Excavated						
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-DUP20A	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated						
Northern Athletic Field	NAF-UT-S87	SSHS-ISMP-NAF-UT-S87	7/21/2023	-	855.05	-	850.69	4 - 6 ft	4.35 ft	1801597261	Not Excavated						
Northern Athletic Field	NAF-UT-S88	SSHS-ISMP-NAF-UT-S88	7/21/2023	-	855.06	-	850.69	4 - 6 ft	4.36 ft	1801597261	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597262	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598162	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated	< 120 U								
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598162	Not Excavated				< 0.057 U	0.076 J	< 0.055 U	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608002	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611302	Not Excavated				< 0.052 U	< 0.041 U	0.13 J	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 140 U								
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615842	Not Excavated				< 0.058 U	< 0.046 U	0.18 J	< 0.062 U	0.097 J	0.040 J
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 110 U								
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 130 U								
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615852	Not Excavated				< 0.052 U	< 0.041 U	0.088 J	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 130 U								
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635822	Not Excavated				< 0.059 U	< 0.047 U	< 0.056 U	< 0.064 U	< 0.059 U	< 0.037 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635822	Not Excavated				< 0.057 U	< 0.045 U	< 0.054 U	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated	< 110 U								
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635822	Not Excavated				< 0.054 U	< 0.043 U	0.084 J	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated	< 130 U								
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated	< 130 U								
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated	< 130 U								
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635822	Not Excavated				< 0.058 U	< 0.046 U	0.060 J	< 0.063 U	< 0.058 U	< 0.036 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated	< 120 U								
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647102	Not Excavated				< 0.059 U	< 0.046 U	0.12 J	< 0.063 U	0.27	0.13 J
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated		< 130 U							
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated		< 120 U							
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated		< 110 U							
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649722	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 130 U							
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 120 U							
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated		< 140 U							
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655532	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated		< 110 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated									
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597262	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598162	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated									
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598162	Not Excavated	< 0.058 U	< 0.045 U	< 0.035 U	< 0.037 U	< 0.026 U	0.042 J	< 0.051 U	< 0.063 U	< 0.049 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated									
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608002	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.046 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated									
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611302	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615842	Not Excavated	< 0.059 U	0.072 J	< 0.035 U	0.073 J	0.14 J	< 0.040 U	0.94 B	0.21 J	0.099 J
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated									
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated									
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615852	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	0.096 J	0.047 J	< 0.036 U	0.25 B	0.11 J	0.050 J
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635822	Not Excavated	< 0.060 U	< 0.047 U	< 0.035 U	< 0.038 U	< 0.027 U	< 0.040 U	< 0.053 U	< 0.065 U	< 0.050 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635822	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	0.047 J	< 0.026 U	< 0.039 U	< 0.051 U	< 0.063 U	< 0.049 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635822	Not Excavated	< 0.055 U	< 0.043 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated									
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635822	Not Excavated	< 0.059 U	< 0.046 U	< 0.035 U	< 0.038 U	< 0.027 U	< 0.040 U	0.079 J	< 0.064 U	< 0.050 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated									
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated									
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647102	Not Excavated	< 0.060 U	0.22 J	< 0.035 U	0.16 J	0.28	< 0.040 U	0.48 EMPC	0.34	0.22 J
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated									
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649722	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.042 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated									
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated									
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated									
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655532	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	0.062 J	< 0.035 U	0.14 J	< 0.057 U	< 0.044 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated									
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597261	Not Excavated						
Northern Athletic Field	NAF-UT-B32	SSHS-ISMP-NAF-UT-B32	7/21/2023	-	855.05	-	850.65	4 - 6 ft	4.4 ft	1801597262	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-S89	SSHS-ISMP-NAF-UT-S89	7/25/2023	-	854.66	-	850.40	4 - 6 ft	4.27 ft	1801598162	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	0.058 BJ	< 0.025 U
Northern Athletic Field	NAF-UT-S91	SSHS-ISMP-NAF-UT-S91	7/25/2023	-	856.15	-	851.75	4 - 6 ft	4.4 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-S92	SSHS-ISMP-NAF-UT-S92	7/25/2023	-	856.10	-	851.76	4 - 6 ft	4.33 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-B33	SSHS-ISMP-NAF-UT-B33	7/25/2023	-	854.64	-	850.48	4 - 6 ft	4.16 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598161	Not Excavated						
Northern Athletic Field	NAF-UT-B34	SSHS-ISMP-NAF-UT-B34	7/25/2023	-	856.11	-	851.49	4 - 6 ft	4.62 ft	1801598162	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	0.060 BJ	< 0.027 U
Northern Athletic Field	AREAF-S1B	SSHS-IRM5A2-AREAF-S1B	8/14/2023	-	856.10	-	852.08	4 - 6 ft	4.02 ft	1801607991	Not Excavated						
Northern Athletic Field	NAF-LP-S2	SSHS-ISMP-NAF-LP-S2	8/14/2023	-	856.51	-	852.42	4 - 6 ft	4.08 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-S3	SSHS-ISMP-NAF-LP-S3	8/14/2023	-	856.36	-	852.05	4 - 6 ft	4.31 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-B2	SSHS-ISMP-NAF-LP-B2	8/14/2023	-	-	-	-	4 - 6 ft	4 - 6 ft	1801608002	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611301	Not Excavated						
Northern Athletic Field	NAF-LP-S7	SSHS-ISMP-NAF-UT-S7	8/18/2023	-	855.88	-	850.48	4 - 6 ft	5.4 ft	1801611302	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-DUP314	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S32	SSHS-IRM5A2-A8PH3-S32	8/29/2023	-	--	-	850.77	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S33	SSHS-IRM5A2-A8PH3-S33	8/29/2023	-	--	-	849.71	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S35	SSHS-IRM5A2-A8PH3-S35	8/29/2023	-	--	-	849.31	4 - 6 ft	4 - 6 ft	1801615842	Not Excavated	< 0.044 U	0.027 J	0.094 J	< 0.042 U	< 0.032 U	< 0.028 U
Northern Athletic Field	A8PH3-S36	SSHS-IRM5A2-A8PH3-S36	8/29/2023	-	--	-	850.66	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S37	SSHS-IRM5A2-A8PH3-S37	8/29/2023	-	--	-	849.37	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S38	SSHS-IRM5A2-A8PH3-S38	8/29/2023	-	--	-	850.73	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S39	SSHS-IRM5A2-A8PH3-S39	8/29/2023	-	--	-	849.57	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S41	SSHS-IRM5A2-A8PH3-S41	8/29/2023	-	--	-	849.25	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S43	SSHS-IRM5A2-A8PH3-S43	8/29/2023	-	--	-	849.08	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S44	SSHS-IRM5A2-A8PH3-S44	8/29/2023	-	--	-	849.29	4 - 6 ft	4 - 6 ft	1801615841	Not Excavated						
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615851	Not Excavated						
Northern Athletic Field	A8PH3-S45	SSHS-IRM5A2-A8PH3-S45	8/29/2023	-	--	-	849.52	4 - 6 ft	4 - 6 ft	1801615852	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-DUP25A	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-DUP26A	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635822	Not Excavated	< 0.045 U	< 0.026 U	< 0.051 U	< 0.043 U	< 0.033 U	< 0.028 U
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA1-S1	SSHS-ISMP-NAF-LPA1-S1	10/9/2023	-	856.94	-	851.98	4 - 6 ft	4.97 ft	1801635822	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	NAF-LPA1-S2	SSHS-ISMP-NAF-LPA1-S2	10/9/2023	-	857.24	-	851.96	4 - 6 ft	5.27 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA1-S3	SSHS-ISMP-NAF-LPA1-S3	10/9/2023	-	857.61	-	851.99	4 - 6 ft	5.62 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA1-S4	SSHS-ISMP-NAF-LPA1-S4	10/9/2023	-	857.25	-	852.12	4 - 6 ft	5.13 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA1-B1	SSHS-ISMP-NAF-LPA1-B1	10/9/2023	-	857.21	-	852.13	4 - 6 ft	5.07 ft	1801635822	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	NAF-LPA2-S1	SSHS-ISMP-NAF-LPA2-S1	10/9/2023	-	857.69	-	852.63	4 - 6 ft	5.06 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA2-S2	SSHS-ISMP-NAF-LPA2-S2	10/9/2023	-	858.27	-	852.41	4 - 6 ft	5.86 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA2-S3	SSHS-ISMP-NAF-LPA2-S3	10/9/2023	-	857.82	-	853.00	4 - 6 ft	4.83 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635821	Not Excavated						
Northern Athletic Field	NAF-LPA2-S4	SSHS-ISMP-NAF-LPA2-S4	10/9/2023	-	856.77	-	852.37	4 - 6 ft	4.4 ft	1801635822	Not Excavated	< 0.045 U	< 0.025 U	< 0.051 U	< 0.042 U	< 0.033 U	< 0.028 U
Northern Athletic Field	NAF-LPA2-B1	SSHS-ISMP-NAF-LPA2-B1	10/9/2023	-	858.16	-	852.40	4 - 6 ft	5.75 ft	1801635821	Not Excavated						
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647101	Not Excavated						
Northern Athletic Field	A8PH4-B8	SSHS-IRM5A2-A8PH4-B8	11/1/2023	-	--	-	851.74	4 - 6 ft	4 - 6 ft	1801647102	Not Excavated	0.093 J	0.064 J	0.18 J	0.19 J	< 0.033 U	0.029 J
Northern Athletic Field	A8PH4-S32	SSHS-IRM5A2-A8PH4-S32	11/7/2023	-	856.44	-	852.36	4 - 6 ft	4.08 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-S33	SSHS-IRM5A2-A8PH4-S33	11/7/2023	-	856.44	-	850.99	4 - 6 ft	5.45 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-S35	SSHS-IRM5A2-A8PH4-S35	11/7/2023	-	856.45	-	851.47	4 - 6 ft	4.97 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-B17	SSHS-IRM5A2-A8PH4-B17	11/7/2023	-	856.45	-	851.17	4 - 6 ft	5.28 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649721	Not Excavated						
Northern Athletic Field	A8PH4-B18	SSHS-IRM5A2-A8PH4-B18	11/7/2023	-	856.46	-	851.38	4 - 6 ft	5.08 ft	1801649722	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-DUP329	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S2	SSHS-IRM5A2-A8PH3A1-S2	11/16/2023	-	--	-	847.81	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S4	SSHS-IRM5A2-A8PH3A1-S4	11/16/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-S6	SSHS-IRM5A2-A8PH3A1-S6	11/16/2023	-	--	-	847.92	4 - 6 ft	4 - 6 ft	1801655541	Not Excavated						
Northern Athletic Field	A8PH3A1-B1	SSHS-IRM5A2-A8PH3A1-B1	11/16/2023	-	851.48	-	846.53	4 - 6 ft	4.96 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-B3	SSHS-IRM5A2-A8PH3A1-B3	11/16/2023	-	851.80	-	847.59	4 - 6 ft	4.2 ft	1801655532	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A8PH3A1-S7	SSHS-IRM5A2-A8PH3A1-S7	11/16/2023	-	852.41	-	848.30	4 - 6 ft	4.12 ft	1801655531	Not Excavated						
Northern Athletic Field	A8PH3A1-S8	SSHS-IRM5A2-A8PH3A1-S8	11/16/2023	-	852.49	-	848.22	4 - 6 ft	4.27 ft	1801655531	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 120 U							
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 130 U							
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated		< 130 U							
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated		< 120 U							
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666002	Not Excavated				< 0.056 U	< 0.044 U	0.096 J	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated		< 120 U							
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated			< 42						
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated			< 40						
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated			< 41						
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated			< 41						
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 110 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	0.029 J	< 0.040 U	< 0.022 U	< 0.068 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	S241	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated	< 120 U								
Northern Athletic Field	S240	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated	< 120 U								
Northern Athletic Field	S239	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated	< 130 U								
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated	< 120 U								
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated	< 110 U								
Northern Athletic Field	S473	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated	< 110 U								
Northern Athletic Field	S474	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated	< 120 U								
Northern Athletic Field	S472	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated	< 110 U								
Northern Athletic Field	S529	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated	< 110 U								
Northern Athletic Field	S179	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated	< 120 U								
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated	< 110 U								
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330902	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated	< 110 U								
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated	< 110 U								
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330902	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated	< 110 U								
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 120 U								
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated	< 120 U								
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332632	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated	< 110 U								
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated	< 120 U								
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated	< 120 U								
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated	< 120 U								
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated	< 110 U								
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated									
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated									
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated									
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated									
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated									
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated									
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666002	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	0.036 J	< 0.039 U	0.24 EMPC	0.12 J	0.072 J
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated									
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated									
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated									
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated									
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated									
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated									
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated									
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated									
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated									
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.039 U	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217041	Not Excavated	< 0.038 U	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.037 U	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.036 U	< 0.030 U	< 0.032 U	0.058 J	< 0.037 U	< 0.084 U	< 0.20 U	< 0.088 U	< 0.079 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.05 U	< 0.039 U	< 0.03 U	< 0.032 U	< 0.023 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.05 U	< 0.039 U	< 0.03 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated									
Northern Athletic Field	S241	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated									
Northern Athletic Field	S240	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated									
Northern Athletic Field	S239	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated									
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated									
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated									
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated									
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated									
Northern Athletic Field	S473	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated									
Northern Athletic Field	S474	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated									
Northern Athletic Field	S472	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated									
Northern Athletic Field	S529	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated									
Northern Athletic Field	S179	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated									
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330902	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330902	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated									
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated									
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated									
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332632	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated									
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-DUP331	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S11	SSHS-IRM5A2-A8PH3A1-S11	11/30/2023	-	--	-	847.94	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S15	SSHS-IRM5A2-A8PH3A1-S15	11/30/2023	-	--	-	847.84	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S19	SSHS-IRM5A2-A8PH3A1-S19	11/30/2023	-	--	-	848.24	4 - 6 ft	4 - 6 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S24	SSHS-IRM5A2-A8PH3A1-S24	12/1/2023	-	--	-	848.74	4 - 6 ft	4 - 6 ft	1801661611	Not Excavated						
Northern Athletic Field	A8PH3A1-S25	SSHS-IRM5A2-A8PH3A1-S25	12/1/2023	-	852.51	-	848.10	4 - 6 ft	4.41 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B7	SSHS-IRM5A2-A8PH3A1-B7	12/1/2023	-	852.09	-	846.19	4 - 6 ft	5.89 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B8	SSHS-IRM5A2-A8PH3A1-B8	12/1/2023	-	852.11	-	846.19	4 - 6 ft	5.92 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH5-S2	SSHS-IRM5A2-A8PH5-S2	12/8/2023	-	856.29	-	852.04	4 - 6 ft	4.25 ft	1801665991	Not Excavated						
Northern Athletic Field	A8PH5-S3	SSHS-IRM5A2-A8PH5-S3	12/8/2023	-	856.34	-	852.18	4 - 6 ft	4.16 ft	1801665991	Not Excavated						
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH5-S8	SSHS-IRM5A2-A8PH5-S8	12/8/2023	-	856.33	-	851.93	4 - 6 ft	4.41 ft	1801666002	Not Excavated	< 0.043 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A8PH5-B1	SSHS-IRM5A2-A8PH5-B1	12/8/2023	-	856.28	-	852.08	4 - 6 ft	4.2 ft	1801665991	Not Excavated						
Northern Athletic Field	SSHS-B75	SSHS-B75-6-10 (8)	8/14/2014	856.08	856.35	0.27	-	6 - 10 ft	6.27-10.27 ft	180-35818-2	Not Excavated						
Northern Athletic Field	SSHS-B76	SSHS-B76-6-10 (8)	8/14/2014	856.25	857.34	1.09	-	6 - 10 ft	7.09-11.09 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B77	081514 01:15_DUP-19	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-2	Not Excavated						
Northern Athletic Field	SSHS-B77	SSHS-B77-6-10 (8)	8/14/2014	855.88	857.91	2.03	-	6 - 10 ft	8.03-12.03 ft	180-35818-1	Not Excavated						
Northern Athletic Field	SSHS-B3081	SSHS-B3081-SUB-6-8	9/4/2019	856.96	857.03	0.07	-	6 - 8 ft	6.07-8.07 ft	180-95165-2	Not Excavated						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-6-8	12/20/2019	851.57	852.53	0.96	-	6 - 8 ft	6.96-8.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3260A	SSHS-B3260A-SUB-6-8	1/26/2021	858.55	858.46	-0.09	-	6 - 8 ft	5.91-7.91 ft	180-116462-3	Not Excavated						
Northern Athletic Field	SSHS-B3286A	SSHS-B3286A-SUB-6-8	1/27/2021	856.41	855.18	-1.23	-	6 - 8 ft	4.77-6.77 ft	180-116529-3	Not Excavated						
Northern Athletic Field	SSHS-B3282A	SSHS-B3282A-SUB-6-8	1/29/2021	856.89	856.18	-0.71	-	6 - 8 ft	5.29-7.29 ft	180-116665-3	Not Excavated						
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-6-8	5/11/2021	856.50	855.82	-0.68	-	6 - 8 ft	5.32-7.32 ft	1801214741	Not Excavated	< 0.060 U	< 0.057 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217041	Not Excavated	< 0.059 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-6-8	5/17/2021	856.37	856.43	0.06	-	6 - 8 ft	6.06-8.06 ft	1801217472	Not Excavated	< 0.058 U	< 0.055 U	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-6-8	5/18/2021	855.95	855.66	-0.29	-	6 - 8 ft	5.71-7.71 ft	1801218221	Not Excavated	< 0.055 U	< 0.052 U	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-6-8	9/17/2021	856.64	856.68	0.04	-	6 - 8 ft	6.04-8.04 ft	180-127265-1	Not Excavated	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-6-8	9/17/2021	857.91	857.91	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-6-8	9/22/2021	856.72	856.72	0.00	-	6 - 8 ft	6-8 ft	180-127415-1	Not Excavated						
Northern Athletic Field	S241	SSHS-IRM5A2-S241	10/28/2021	-	855.75	-	849.10	6 - 8 ft	6.65 ft	1801292043	Not Excavated						
Northern Athletic Field	S240	SSHS-IRM5A2-S240	10/28/2021	-	855.75	-	848.78	6 - 8 ft	6.97 ft	1801292043	Not Excavated						
Northern Athletic Field	S239	SSHS-IRM5A2-S239	10/28/2021	-	855.83	-	848.44	6 - 8 ft	7.38 ft	1801292043	Not Excavated						
Northern Athletic Field	DW1-S3	SSHS-IRM5A2-DW1-S3	11/8/2021	-	856.83	-	848.81	6 - 8 ft	8.01 ft	1801296791	Not Excavated						
Northern Athletic Field	DW1-S2	SSHS-IRM5A2-DW1-S2	11/8/2021	-	856.86	-	850.50	6 - 8 ft	6.36 ft	1801296791	Not Excavated						
Northern Athletic Field	DW3-S2	SSHS-IRM5A2-DW3-S2	11/10/2021	-	856.83	-	850.01	6 - 8 ft	6.82 ft	1801298201	Not Excavated						
Northern Athletic Field	FIS-BOT 1	SSHS-IRM5A2-FIS-BOT 1	12/14/2021	-	853.41	-	846.74	6 - 8 ft	6.67 ft	1801312371	Not Excavated						
Northern Athletic Field	S473	SSHS-IRM5A2-S473	1/6/2022	-	858.94	-	851.55	6 - 8 ft	7.39 ft	1801320661	Not Excavated						
Northern Athletic Field	S474	SSHS-IRM5A2-S474	1/6/2022	-	858.36	-	851.26	6 - 8 ft	7.1 ft	1801320661	Not Excavated						
Northern Athletic Field	S472	SSHS-IRM5A2-S472	1/6/2022	-	858.85	-	851.67	6 - 8 ft	7.18 ft	1801320661	Not Excavated						
Northern Athletic Field	S529	SSHS-IRM5A2-S529	1/12/2022	-	858.13	-	851.39	6 - 8 ft	6.74 ft	1801322511	Not Excavated						
Northern Athletic Field	S179	SSHS-IRM5A2-S179	1/20/2022	-	854.87	-	847.46	6 - 8 ft	7.41 ft	1801325891	Not Excavated						
Northern Athletic Field	RS-S58	SSHS-IRM5A2-DUP34	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT30	SSHS-IRM5A2-RS-BOT30	2/2/2022	-	854.55	-	848.15	6 - 8 ft	6.4 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT31	SSHS-IRM5A2-RS-BOT31	2/2/2022	-	855.72	-	848.71	6 - 8 ft	7.01 ft	1801330902	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	RS-BOT32	SSHS-IRM5A2-RS-BOT32	2/2/2022	-	854.30	-	848.11	6 - 8 ft	6.19 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT33	SSHS-IRM5A2-RS-BOT33	2/2/2022	-	855.35	-	848.50	6 - 8 ft	6.85 ft	1801330902	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	RS-S58	SSHS-IRM5A2-RS-S58	2/2/2022	-	853.81	-	847.70	6 - 8 ft	6.12 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-S59	SSHS-IRM5A2-RS-S59	2/2/2022	-	854.23	-	848.18	6 - 8 ft	6.05 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-S57	SSHS-IRM5A2-RS-S57	2/2/2022	-	854.12	-	848.10	6 - 8 ft	6.02 ft	1801330901	Not Excavated						
Northern Athletic Field	RS-BOT38	SSHS-IRM5A2-RS-BOT38	2/2/2022	-	853.64	-	847.16	6 - 8 ft	6.48 ft	1801330901	Not Excavated						
Northern Athletic Field	S174-S2	SSHS-IRM5A2-DUP36	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated						
Northern Athletic Field	RS-S62	SSHS-IRM5A2-RS-S62	2/7/2022	-	854.45	-	848.26	6 - 8 ft	6.19 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S65	SSHS-IRM5A2-RS-S65	2/7/2022	-	854.52	-	848.51	6 - 8 ft	6.01 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S63	SSHS-IRM5A2-RS-S63	2/7/2022	-	854.46	-	846.75	6 - 8 ft	7.7 ft	1801332632	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	S174-BOT1	SSHS-IRM5A2-S174-BOT1	2/7/2022	-	854.27	-	847.13	6 - 8 ft	7.14 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-S2	SSHS-IRM5A2-S174-S2	2/7/2022	-	854.23	-	847.74	6 - 8 ft	6.49 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-S4	SSHS-IRM5A2-S174-S4	2/7/2022	-	854.67	-	847.90	6 - 8 ft	6.77 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-S6	SSHS-IRM5A2-S174-S6	2/7/2022	-	855.07	-	848.65	6 - 8 ft	6.42 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-BOT2	SSHS-IRM5A2-S174-BOT2	2/7/2022	-	854.69	-	847.36	6 - 8 ft	7.33 ft	1801332621	Not Excavated						
Northern Athletic Field	S174-BOT3	SSHS-IRM5A2-S174-BOT3	2/7/2022	-	855.04	-	847.67	6 - 8 ft	7.37 ft	1801332621	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 130 U								
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 120 UT								
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated	< 130 U								
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S125	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated	< 110 U								
Northern Athletic Field	S126	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated	< 110 U								
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 110 U								
Northern Athletic Field	S254	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated	< 110 U								
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated	< 120 U								
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346402	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated	< 110 U								
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347852	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.1776445	1801350892	Not Excavated	< 110 U								
Northern Athletic Field	S223	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated	< 100 U								
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated	< 100 U								
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.697	1801352871	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated	< 120 U								
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S579	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354702	Not Excavated				< 0.050 U	< 0.040 U	0.18 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S220	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S219	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated	< 100 U								
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated	< 120 U								
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354702	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated	< 120 U								
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated	< 130 U								
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated	< 120 U								
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated	< 110 U								
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.084	1801355361	Not Excavated	< 110 U								
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated	< 110 U								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371273	Not Excavated				< 0.051 U	< 0.041 U	0.25	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated	< 130 U								
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371273	Not Excavated				0.096 J	< 0.046 U	< 0.056 U	< 0.063 U	< 0.058 U	< 0.036 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated	< 120 U								
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated	< 120 U								
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated	< 110 U								
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371273	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated	< 130 U								
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated	< 110 U								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated	< 120 U								
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371273	Not Excavated				< 0.050 U	< 0.040 U	0.11 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated		< 35 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated									
Northern Athletic Field	S125	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated									
Northern Athletic Field	S126	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated									
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated									
Northern Athletic Field	S254	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated									
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated									
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346402	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	0.078 J	< 0.061 U	< 0.047 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated									
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347852	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.1776445	1801350892	Not Excavated									
Northern Athletic Field	S223	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated									
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated									
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated									
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated									
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated									
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.697	1801352871	Not Excavated									
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated									
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated									
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated									
Northern Athletic Field	S579	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated									
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated									
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354702	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	0.33
Northern Athletic Field	S220	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated									
Northern Athletic Field	S219	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated									
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated									
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated									
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354702	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.11 J	< 0.059 U	< 0.045 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated									
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated									
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated									
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated									
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated									
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated									
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated									
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated									
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated									
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated									
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated									
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated									
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.084	1801355361	Not Excavated									
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated									
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated									
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371273	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	0.083 J	< 0.057 U	< 0.044 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371273	Not Excavated	< 0.060 U	< 0.046 U	< 0.035 U	< 0.038 U	< 0.027 U	< 0.040 U	1.9	0.079 J	< 0.050 U
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371273	Not Excavated	< 0.053 U	< 0.041 U	0.032 J	< 0.033 U	< 0.024 U	< 0.036 U	0.087 J	< 0.057 U	< 0.044 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated									
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated									
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371273	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	0.19 J	< 0.055 U	< 0.043 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-DUP39	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-DUP40	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-S2	SSHS-IRM5A2-S172A-S2	2/8/2022	-	855.72	-	849.63	6 - 8 ft	6.09 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-S5	SSHS-IRM5A2-S172A-S5	2/8/2022	-	857.42	-	849.48	6 - 8 ft	7.94 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-S4	SSHS-IRM5A2-S172A-S4	2/8/2022	-	857.40	-	851.08	6 - 8 ft	6.32 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-S7	SSHS-IRM5A2-S172A-S7	2/8/2022	-	857.94	-	850.63	6 - 8 ft	7.31 ft	1801333441	Not Excavated						
Northern Athletic Field	S125	SSHS-IRM5A2-S125	2/28/2022	-	855.32	-	849.13	6 - 8 ft	6.19 ft	1801343721	Not Excavated						
Northern Athletic Field	S126	SSHS-IRM5A2-S126	2/28/2022	-	856.86	-	849.24	6 - 8 ft	7.62 ft	1801343721	Not Excavated						
Northern Athletic Field	S254	SSHS-IRM5A2-DUP48	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated						
Northern Athletic Field	S254	SSHS-IRM5A2-S254	3/3/2022	-	853.15	-	845.48	6 - 8 ft	7.67 ft	1801346401	Not Excavated						
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346401	Not Excavated						
Northern Athletic Field	S180	SSHS-IRM5A2-S180	3/3/2022	-	853.76	-	847.25	6 - 8 ft	6.51 ft	1801346402	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347851	Not Excavated						
Northern Athletic Field	S255	SSHS-IRM5A2-S255	3/5/2022	-	853.04	-	845.03	6 - 8 ft	8.01 ft	1801347852	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	MS-SLT-S11	SSHS-ISMP-MS-SLT-S11	3/11/2022	-	856.54	-	850.36	6 - 8 ft	6.1776445	1801350892	Not Excavated						
Northern Athletic Field	S223	SSHS-IRM5A2-S223	3/14/2022	-	854.35	-	846.93	6 - 8 ft	7.43 ft	1801351301	Not Excavated						
Northern Athletic Field	MS-SLT-S17	SSHS-ISMP-MS-SLT-S17	3/14/2022	-	856.68	-	848.83	6 - 8 ft	7.85 ft	1801351292	Not Excavated						
Northern Athletic Field	MS-SLT-S20	SSHS-ISMP-MS-SLT-S20	3/14/2022	-	856.67	-	848.95	6 - 8 ft	7.72 ft	1801351292	Not Excavated						
Northern Athletic Field	MS-SLT-S23	SSHS-ISMP-MS-SLT-S23	3/15/2022	-	856.79	-	849.06	6 - 8 ft	7.73 ft	1801352021	Not Excavated						
Northern Athletic Field	MS-SLT-S29	SSHS-ISMP-MS-SLT-S29	3/15/2022	-	856.71	-	849.16	6 - 8 ft	7.55 ft	1801352021	Not Excavated						
Northern Athletic Field	MS-SLT-S35	SSHS-ISMP-MS-SLT-S35	3/16/2022	-	856.60	-	848.90	6 - 8 ft	7.697	1801352871	Not Excavated						
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-DUP4	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S41	SSHS-ISMP-MS-SLT-S41	3/17/2022	-	856.74	-	849.61	6 - 8 ft	7.13 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-B8	SSHS-ISMP-MS-SLT-B8	3/17/2022	-	856.74	-	849.12	6 - 8 ft	7.63 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S44	SSHS-ISMP-MS-SLT-S44	3/17/2022	-	856.72	-	849.23	6 - 8 ft	7.49 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S47	SSHS-ISMP-MS-SLT-S47	3/17/2022	-	856.75	-	849.64	6 - 8 ft	7.11 ft	1801353601	Not Excavated						
Northern Athletic Field	MS-SLT-S60	SSHS-ISMP-MS-SLT-S60	3/18/2022	-	856.72	-	849.51	6 - 8 ft	7.21 ft	1801354291	Not Excavated						
Northern Athletic Field	S219	SSHS-IRM5A2-DUP56	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated						
Northern Athletic Field	S579	SSHS-IRM5A2-S579	3/19/2022	-	853.05	-	845.83	6 - 8 ft	7.22 ft	1801354701	Not Excavated						
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354701	Not Excavated						
Northern Athletic Field	S222	SSHS-IRM5A2-S222	3/19/2022	-	853.32	-	847.06	6 - 8 ft	6.26 ft	1801354702	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 UT
Northern Athletic Field	S220	SSHS-IRM5A2-S220	3/19/2022	-	852.89	-	845.62	6 - 8 ft	7.27 ft	1801354701	Not Excavated						
Northern Athletic Field	S219	SSHS-IRM5A2-S219	3/19/2022	-	853.29	-	845.38	6 - 8 ft	7.91 ft	1801354701	Not Excavated						
Northern Athletic Field	S255A	SSHS-IRM5A2-S255A	3/19/2022	-	852.95	-	844.92	6 - 8 ft	8.03 ft	1801354701	Not Excavated						
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354701	Not Excavated						
Northern Athletic Field	FISR-BOT1	SSHS-IRM5A2-FISR-BOT1	3/19/2022	-	853.10	-	846.29	6 - 8 ft	6.82 ft	1801354702	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	0.17 BJ	< 0.025 U
Northern Athletic Field	FISR-BOT2	SSHS-IRM5A2-FISR-BOT2	3/19/2022	-	853.32	-	846.35	6 - 8 ft	6.97 ft	1801354701	Not Excavated						
Northern Athletic Field	FISR-BOT3	SSHS-IRM5A2-FISR-BOT3	3/19/2022	-	853.08	-	846.46	6 - 8 ft	6.62 ft	1801354701	Not Excavated						
Northern Athletic Field	S183A	SSHS-IRM5A2-S183A	3/19/2022	-	852.89	-	846.87	6 - 8 ft	6.03 ft	1801354701	Not Excavated						
Northern Athletic Field	FISR-BOT4	SSHS-IRM5A2-FISR-BOT4	3/19/2022	-	852.80	-	846.19	6 - 8 ft	6.61 ft	1801354701	Not Excavated						
Northern Athletic Field	S174-S7	SSHS-IRM5A2-S174-S7	3/20/2022	-	855.00	-	847.06	6 - 8 ft	7.94 ft	1801354871	Not Excavated						
Northern Athletic Field	S174-S8	SSHS-IRM5A2-S174-S8	3/20/2022	-	855.70	-	847.90	6 - 8 ft	7.8 ft	1801354871	Not Excavated						
Northern Athletic Field	MS-SLT-S63	SSHS-ISMP-MS-SLT-S63	3/21/2022	-	856.52	-	849.52	6 - 8 ft	7.01 ft	1801354881	Not Excavated						
Northern Athletic Field	MS-SLT-B12	SSHS-ISMP-MS-SLT-BOT12	3/21/2022	-	856.52	-	849.40	6 - 8 ft	7.12 ft	1801354881	Not Excavated						
Northern Athletic Field	MS-SLT-S66	SSHS-ISMP-MS-SLT-S66	3/21/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801354881	Not Excavated						
Northern Athletic Field	MS-SLT-S69	SSHS-ISMP-MS-SLT-S69	3/21/2022	-	856.61	-	849.94	6 - 8 ft	6.67 ft	1801354881	Not Excavated						
Northern Athletic Field	MS-SLT-B13	SSHS-ISMP-MS-SLT-BOT13	3/21/2022	-	856.61	-	849.37	6 - 8 ft	7.24 ft	1801354881	Not Excavated						
Northern Athletic Field	MS-SLT-S72	SSHS-ISMP-MS-SLT-S72	3/21/2022	-	856.59	-	849.12	6 - 8 ft	7.47 ft	1801354881	Not Excavated						
Northern Athletic Field	SLT-S93-BOT1	SSHS-ISMP-SLT-S93-BOT1	3/22/2022	-	856.42	-	849.34	6 - 8 ft	7.084	1801355361	Not Excavated						
Northern Athletic Field	S181A	SSHS-IRM5A2-S181A	4/13/2022	-	852.78	-	846.74	6 - 8 ft	6.04 ft	1801366611	Not Excavated						
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371272	Not Excavated						
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-DUP72	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371273	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-BOT1	SSHS-IRM5A2-PIPE5-BOT1	4/25/2022	-	856.39	-	849.76	6 - 8 ft	6.63 ft	1801371273	Not Excavated	< 0.045 U	< 0.026 U	< 0.051 U	< 0.043 U	< 0.033 U	0.12 J
Northern Athletic Field	PIPE5-S1	SSHS-IRM5A2-PIPE5-S1	4/25/2022	-	856.43	-	850.22	6 - 8 ft	6.21 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-S2	SSHS-IRM5A2-PIPE5-S2	4/25/2022	-	856.30	-	850.16	6 - 8 ft	6.13 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-S3	SSHS-IRM5A2-PIPE5-S3	4/25/2022	-	855.75	-	849.53	6 - 8 ft	6.22 ft	1801371273	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	PIPE5-BOT5	SSHS-IRM5A2-PIPE5-BOT5	4/25/2022	-	856.18	-	848.66	6 - 8 ft	7.52 ft	1801371272	Not Excavated						
Northern Athletic Field	PIPE5-S9	SSHS-IRM5A2-PIPE5-S9	4/25/2022	-	856.18	-	850.13	6 - 8 ft	6.05 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371271	Not Excavated						
Northern Athletic Field	PIPE5-S10	SSHS-IRM5A2-PIPE5-S10	4/25/2022	-	856.17	-	849.49	6 - 8 ft	6.68 ft	1801371273	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	0.028 J	< 0.024 U
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378342	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378344	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated		< 30 U							
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated		< 31 U							
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated	< 12 U								
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated		< 33 U							
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated		< 32 U							
Northern Athletic Field	S256	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated		< 33 U							
Northern Athletic Field	S257	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated		< 32 U							
Northern Athletic Field	B238	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated		< 32 U							
Northern Athletic Field	S258	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated		< 33 U							
Northern Athletic Field	S259	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated		< 32 U							
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated		< 34 U							
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated		< 35 U							
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated		< 31 U							
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated		< 34 U							
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated		< 30 U							
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384662	Not Excavated				< 0.050 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated		< 34 U							
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated		< 31 U							
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated		< 31 U							
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated		< 33 U							
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated		< 31 U							
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated		< 31 U							
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated		< 33 U							
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392682	Not Excavated				< 0.050 U	< 0.040 U	4.9 B	< 0.055 U	< 0.050 U	< 0.032 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated		< 31 U							
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated		< 30 U							
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated		< 33 U							
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395464	Not Excavated				< 0.051 U	< 0.040 U	0.077 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated		< 31 U							
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated		< 30 U							
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395464	Not Excavated				< 0.044 U	< 0.035 U	0.055 J	< 0.048 U	< 0.044 U	< 0.027 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated	< 130 U								
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395973	Not Excavated				< 0.50 U	< 0.40 U	< 0.48 U	< 0.54 U	< 0.50 U	< 0.31 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396812	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397522	Not Excavated				< 0.048 U	< 0.038 U	0.055 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated	< 120 U								
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398273	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated	< 130 U								
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398273	Not Excavated				< 0.055 U	< 0.044 U	0.079 J	< 0.060 U	< 0.055 U	< 0.035 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398273	Not Excavated				< 0.047 U	< 0.038 U	< 0.046 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated	< 120 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378344	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.048 U	< 0.059 U	< 0.045 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated									
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated									
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated									
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated									
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated									
Northern Athletic Field	S256	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated									
Northern Athletic Field	S257	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated									
Northern Athletic Field	B238	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated									
Northern Athletic Field	S258	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated									
Northern Athletic Field	S259	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated									
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated									
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated									
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated									
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384662	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated									
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated									
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated									
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated									
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392682	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	3.2
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated									
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated									
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated									
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated									
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated									
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated									
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395464	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated									
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated									
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395464	Not Excavated	< 0.045 U	< 0.035 U	< 0.027 U	< 0.028 U	< 0.020 U	< 0.030 U	0.054 J	< 0.048 U	< 0.037 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395973	Not Excavated	< 0.51 U	< 0.40 U	< 0.30 U	< 0.32 U	< 0.23 U	0.43 J	< 0.45 U	< 0.55 U	< 0.43 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated									
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated									
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396812	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	0.030 J	< 0.021 U	< 0.032 U	0.064 J	< 0.052 U	< 0.040 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated									
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated									
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated									
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated									
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397522	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.10 J	< 0.054 U	< 0.041 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398273	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398273	Not Excavated	< 0.057 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.050 U	0.072 J	< 0.047 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398273	Not Excavated	< 0.048 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.052 U	< 0.041 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A5-V1-S17	SSHS-IRM5A2-A5-V1-S17	5/9/2022	-	856.20	-	848.81	6 - 8 ft	7.39 ft	1801378344	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	PIPE5-S14	SSHS-IRM5A2-PIPE5-S14	5/9/2022	-	855.36	-	847.57	6 - 8 ft	7.79 ft	1801378343	Not Excavated						
Northern Athletic Field	PIPE5-S12	SSHS-IRM5A2-PIPE5-S12	5/9/2022	-	855.23	-	847.66	6 - 8 ft	7.57 ft	1801378343	Not Excavated						
Northern Athletic Field	DW-5	SSHS-IRM5A2-DW5	5/9/2022	-	856.01	-	848.79	6 - 8 ft	7.23 ft	1801378343	Not Excavated						
Northern Athletic Field	S0008	SSHS-IRM5A2-S0008	5/16/2022	-	857.59	-	851.10	6 - 8 ft	6.48 ft	1801381901	Not Excavated						
Northern Athletic Field	S0014	SSHS-IRM5A2-S0014	5/17/2022	-	857.68	-	851.13	6 - 8 ft	6.55 ft	1801382541	Not Excavated						
Northern Athletic Field	S256	SSHS-IRM5A2-S256	5/17/2022	-	857.57	-	849.91	6 - 8 ft	7.66 ft	1801382541	Not Excavated						
Northern Athletic Field	S257	SSHS-IRM5A2-S257	5/17/2022	-	857.70	-	850.12	6 - 8 ft	7.58 ft	1801382541	Not Excavated						
Northern Athletic Field	B238	SSHS-IRM5A2-B238	5/17/2022	-	857.54	-	849.50	6 - 8 ft	8.04 ft	1801382551	Not Excavated						
Northern Athletic Field	S258	SSHS-IRM5A2-S258	5/17/2022	-	857.52	-	849.64	6 - 8 ft	7.88 ft	1801382541	Not Excavated						
Northern Athletic Field	S259	SSHS-IRM5A2-S259	5/17/2022	-	857.55	-	849.59	6 - 8 ft	7.96 ft	1801382541	Not Excavated						
Northern Athletic Field	S0016	SSHS-IRM5A2-S0016	5/17/2022	-	857.47	-	850.92	6 - 8 ft	6.55 ft	1801382541	Not Excavated						
Northern Athletic Field	S0017	SSHS-IRM5A2-S0017	5/17/2022	-	857.52	-	851.12	6 - 8 ft	6.4 ft	1801382541	Not Excavated						
Northern Athletic Field	PIPE11	SSHS-IRM5A2-PIPE11	5/17/2022	-	857.73	-	850.70	6 - 8 ft	7.03 ft	1801382551	Not Excavated						
Northern Athletic Field	PIPE5-S19	SSHS-IRM5A2-PIPE5-S19	5/20/2022	-	855.64	-	848.94	6 - 8 ft	6.7 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-S18	SSHS-IRM5A2-PIPE5-S18	5/20/2022	-	855.68	-	848.14	6 - 8 ft	7.54 ft	1801384662	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	PIPE5-S21	SSHS-IRM5A2-PIPE5-S21	5/20/2022	-	855.73	-	847.84	6 - 8 ft	7.89 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-S17	SSHS-IRM5A2-PIPE5-S17	5/20/2022	-	855.81	-	849.29	6 - 8 ft	6.52 ft	1801384661	Not Excavated						
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-6-8	6/4/2022	856.18	856.99	0.81	-	6 - 8 ft	6.81-8.81 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-6-8	6/4/2022	857.21	855.60	-1.61	-	6 - 8 ft	4.39-6.39 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-6-8	6/4/2022	856.60	856.86	0.26	-	6 - 8 ft	6.26-8.26 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-6-8	6/4/2022	856.27	856.38	0.11	-	6 - 8 ft	6.11-8.11 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-6-8	6/4/2022	856.61	857.29	0.68	-	6 - 8 ft	6.68-8.68 ft	180-139185-1	Not Excavated						
Northern Athletic Field	CB3-BOT2	SSHS-IRM5A2-CB3-BOT2	6/6/2022	-	856.64	-	849.33	6 - 8 ft	7.32 ft	1801391881	Not Excavated						
Northern Athletic Field	CB3-BOT1	SSHS-IRM5A2-CB3-BOT1	6/6/2022	-	856.50	-	848.94	6 - 8 ft	7.56 ft	1801391881	Not Excavated						
Northern Athletic Field	A5-S801	SSHS-IRM5A2-A5-S801	6/7/2022	-	854.16	-	848.07	6 - 8 ft	6.09 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S800	SSHS-IRM5A2-A5-S800	6/7/2022	-	854.32	-	848.29	6 - 8 ft	6.02 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-B800	SSHS-IRM5A2-A5-B800	6/7/2022	-	854.20	-	847.74	6 - 8 ft	6.45 ft	1801392682	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A5-S803	SSHS-IRM5A2-A5-S803	6/7/2022	-	854.23	-	848.00	6 - 8 ft	6.23 ft	1801392681	Not Excavated						
Northern Athletic Field	A5-S802	SSHS-IRM5A2-A5-S802	6/7/2022	-	854.17	-	848.15	6 - 8 ft	6.02 ft	1801392681	Not Excavated						
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-DUP106	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated						
Northern Athletic Field	CP2-S16	SSHS-IRM5A2-CP2-S16	6/9/2022	-	856.06	-	849.27	6 - 8 ft	6.79 ft	1801394641	Not Excavated						
Northern Athletic Field	CP2-S5BOT	SSHS-IRM5A2-CP2-S5BOT	6/9/2022	-	856.40	-	848.75	6 - 8 ft	7.65 ft	1801394641	Not Excavated						
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated						
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-DUP110	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395464	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	CP2-S20	SSHS-IRM5A2-CP2-S20	6/10/2022	-	856.62	-	848.99	6 - 8 ft	7.62 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-S812	SSHS-IRM5A2-A4-S812	6/10/2022	-	856.46	-	848.60	6 - 8 ft	7.85 ft	1801395463	Not Excavated						
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395462	Not Excavated						
Northern Athletic Field	CP2-S26	SSHS-IRM5A2-CP2-S26	6/10/2022	-	857.12	-	849.40	6 - 8 ft	7.72 ft	1801395464	Not Excavated	< 0.034 U	< 0.019 U	< 0.038 U	< 0.032 U	< 0.025 U	< 0.021 U
Northern Athletic Field	FISR-S2	SSHS-IRM5A2-FISR-S2	6/11/2022	-	854.11	-	846.76	6 - 8 ft	7.35 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S3	SSHS-IRM5A2-FISR-S3	6/11/2022	-	854.24	-	847.95	6 - 8 ft	6.29 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S4	SSHS-IRM5A2-FISR-S4	6/11/2022	-	854.24	-	847.18	6 - 8 ft	7.06 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S6	SSHS-IRM5A2-FISR-S6	6/11/2022	-	--	-	845.18	6 - 8 ft	6 - 8 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S10	SSHS-IRM5A2-FISR-S10	6/13/2022	-	854.74	-	846.92	6 - 8 ft	7.81 ft	1801395973	Not Excavated	< 0.39 U	< 0.22 U	< 0.44 U	< 0.37 U	< 0.28 U	< 0.24 U
Northern Athletic Field	FISR-S26	SSHS-IRM5A2-FISR-S26	6/13/2022	-	855.02	-	847.38	6 - 8 ft	7.64 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S34	SSHS-IRM5A2-FISR-S34	6/13/2022	-	855.02	-	847.08	6 - 8 ft	7.94 ft	1801395972	Not Excavated						
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396811	Not Excavated						
Northern Athletic Field	FISR-S42	SSHS-IRM5A2-FISR-S42	6/14/2022	-	855.12	-	847.43	6 - 8 ft	7.69 ft	1801396812	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-DUP-124	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated						
Northern Athletic Field	FISR-S17	SSHS-IRM5A2-FISR-S17	6/15/2022	-	855.08	-	848.96	6 - 8 ft	6.12 ft	1801397521	Not Excavated						
Northern Athletic Field	FISR-S33	SSHS-IRM5A2-FISR-S33	6/15/2022	-	855.03	-	848.88	6 - 8 ft	6.14 ft	1801397521	Not Excavated						
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397521	Not Excavated						
Northern Athletic Field	FISR-S41	SSHS-IRM5A2-FISR-S41	6/15/2022	-	855.10	-	848.85	6 - 8 ft	6.25 ft	1801397522	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S400	SSHS-IRM5A2-A3-S400	6/16/2022	-	855.17	-	848.87	6 - 8 ft	6.3 ft	1801398273	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S600	SSHS-IRM5A2-A3-S600	6/16/2022	-	855.10	-	847.07	6 - 8 ft	8.03 ft	1801398273	Not Excavated	< 0.043 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.027 U
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S602	SSHS-IRM5A2-A3-S602	6/16/2022	-	855.68	-	847.84	6 - 8 ft	7.84 ft	1801398273	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-S603	SSHS-IRM5A2-A3-S603	6/16/2022	-	856.06	-	848.47	6 - 8 ft	7.59 ft	1801398271	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated	< 120 U								
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398273	Not Excavated				< 0.051 U	< 0.040 U	0.21	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 110 UT								
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398273	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated		< 36 U							
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399473	Not Excavated				< 0.055 U	< 0.043 U	0.096 J	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated		< 32 U							
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated		< 32 U							
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated		< 320 U							
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399473	Not Excavated				< 0.051 U	< 0.041 U		< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated		< 30 U							
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated		< 31 U							
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated		< 33 U							
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated		< 30 U							
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated		< 35 U							
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated		< 33 U							
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400232	Not Excavated				< 0.053 U	< 0.042 U	0.13 J	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated		< 31 U							
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated		< 36 U							
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated		< 35 U							
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated		< 31 U							
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400242	Not Excavated				< 0.046 U	< 0.036 U	0.047 J	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated		< 330 U							
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated		< 31 U							
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400242	Not Excavated				< 0.047 U	< 0.037 U	0.20	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated		< 30 U							
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated		< 32 U							
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated		< 30 U							
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated		< 31 U							
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400242	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated		< 30 U							
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated		< 29 U							
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated		< 31 U							
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated		< 32 U							
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated		< 31 U							
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400242	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 110 UT								
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400922	Not Excavated				< 0.049 U	< 0.039 U	0.10 J	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400922	Not Excavated				< 0.050 U	< 0.039 U	0.055 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated	< 120 U								
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated	< 120 U								
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400922	Not Excavated				< 0.051 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated	< 120 U								
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400922	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398273	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	0.36
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398273	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399473	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	0.076 J	< 0.061 U	0.063 J
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399473	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U		< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated									
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400232	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	< 0.048 U	0.073 J	0.25
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated									
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400242	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.051 U	0.093 J
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400242	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	0.061 J	< 0.022 U	< 0.032 U	< 0.042 U	0.069 J	0.17 J
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400242	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.041 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated									
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400242	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400922	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	0.13 J
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400922	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	0.067 J
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400922	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400922	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A3-S604	SSHS-IRM5A2-A3-S604	6/16/2022	-	856.43	-	849.22	6 - 8 ft	7.21 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B600	SSHS-IRM5A2-A3-B600	6/16/2022	-	856.34	-	848.49	6 - 8 ft	7.84 ft	1801398273	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A3-B602	SSHS-IRM5A2-A3-B602	6/16/2022	-	856.09	-	848.16	6 - 8 ft	7.93 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B603	SSHS-IRM5A2-A3-B603	6/16/2022	-	855.62	-	847.69	6 - 8 ft	7.93 ft	1801398273	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-B608	SSHS-IRM5A2-A3-B608	6/16/2022	-	856.44	-	848.80	6 - 8 ft	7.64 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-S606	SSHS-IRM5A2-A3-S606	6/17/2022	-	855.67	-	848.22	6 - 8 ft	7.46 ft	1801399473	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A3-S607	SSHS-IRM5A2-A3-S607	6/17/2022	-	855.90	-	848.42	6 - 8 ft	7.48 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-S608	SSHS-IRM5A2-A3-S608	6/17/2022	-	856.03	-	849.10	6 - 8 ft	6.93 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-S609	SSHS-IRM5A2-A3-S609	6/17/2022	-	856.41	-	849.48	6 - 8 ft	6.93 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-B609	SSHS-IRM5A2-A3-B609	6/17/2022	-	856.42	-	848.82	6 - 8 ft	7.6 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-B610	SSHS-IRM5A2-A3-B610	6/17/2022	-	856.01	-	848.39	6 - 8 ft	7.63 ft	1801399473	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-DUP137	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S615	SSHS-IRM5A2-DUP134	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400211	Not Excavated						
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-6-8	6/20/2022	856.38	856.44	0.06	-	6 - 8 ft	6.06-8.06 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-6-8	6/20/2022	856.66	856.67	0.01	-	6 - 8 ft	6.01-8.01 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-6-8	6/20/2022	856.60	856.56	-0.04	-	6 - 8 ft	5.96-7.96 ft	180-140136-1	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S18	SSHS-IRM5A2-A3-FISLAT1-S18	6/20/2022	-	857.56	-	849.66	6 - 8 ft	7.9 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-S610	SSHS-IRM5A2-A3-S610	6/20/2022	-	856.38	-	848.91	6 - 8 ft	7.48 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S611	SSHS-IRM5A2-A3-S611	6/20/2022	-	856.64	-	849.59	6 - 8 ft	7.05 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S612	SSHS-IRM5A2-A3-S612	6/20/2022	-	857.02	-	850.38	6 - 8 ft	6.64 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S613	SSHS-IRM5A2-A3-S613	6/20/2022	-	856.94	-	850.06	6 - 8 ft	6.88 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-S614	SSHS-IRM5A2-A3-S614	6/20/2022	-	856.98	-	850.18	6 - 8 ft	6.8 ft	1801400232	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A3-S615	SSHS-IRM5A2-A3-S615	6/20/2022	-	857.12	-	850.68	6 - 8 ft	6.45 ft	1801400231	Not Excavated						
Northern Athletic Field	PIPE16	SSHS-IRM5A2-PIPE16	6/20/2022	-	856.94	-	849.94	6 - 8 ft	7 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-S618	SSHS-IRM5A2-A3-S618	6/20/2022	-	856.80	-	850.06	6 - 8 ft	6.74 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-S619	SSHS-IRM5A2-A3-S619	6/20/2022	-	857.19	-	850.18	6 - 8 ft	7.01 ft	1801400242	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A3-PILLAR-BOT1	SSHS-IRM5A2-A3-PILLAR-BOT1	6/20/2022	-	857.57	-	850.56	6 - 8 ft	7.01 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B611	SSHS-IRM5A2-A3-B611	6/20/2022	-	856.63	-	849.29	6 - 8 ft	7.34 ft	1801400242	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-B612	SSHS-IRM5A2-A3-B612	6/20/2022	-	856.91	-	849.53	6 - 8 ft	7.38 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B613	SSHS-IRM5A2-A3-B613	6/20/2022	-	857.39	-	849.98	6 - 8 ft	7.4 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B614	SSHS-IRM5A2-A3-B614	6/20/2022	-	857.58	-	850.44	6 - 8 ft	7.14 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B615	SSHS-IRM5A2-A3-B615	6/20/2022	-	857.86	-	850.56	6 - 8 ft	7.3 ft	1801400242	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-B616	SSHS-IRM5A2-A3-B616	6/20/2022	-	857.83	-	850.69	6 - 8 ft	7.14 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B617	SSHS-IRM5A2-A3-B617	6/20/2022	-	857.72	-	850.42	6 - 8 ft	7.31 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B618	SSHS-IRM5A2-A3-B618	6/20/2022	-	857.75	-	850.20	6 - 8 ft	7.55 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B619	SSHS-IRM5A2-A3-B619	6/20/2022	-	857.30	-	849.62	6 - 8 ft	7.68 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400241	Not Excavated						
Northern Athletic Field	A3-B620	SSHS-IRM5A2-A3-B620	6/20/2022	-	856.63	-	848.96	6 - 8 ft	7.67 ft	1801400242	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-B631	SSHS-IRM5A2-DUP138	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B621	SSHS-IRM5A2-A3-B621	6/21/2022	-	856.87	-	849.17	6 - 8 ft	7.7 ft	1801400922	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-B622	SSHS-IRM5A2-A3-B622	6/21/2022	-	857.24	-	849.61	6 - 8 ft	7.63 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B623	SSHS-IRM5A2-A3-B623	6/21/2022	-	857.76	-	850.14	6 - 8 ft	7.62 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B624	SSHS-IRM5A2-A3-B624	6/21/2022	-	857.75	-	850.41	6 - 8 ft	7.33 ft	1801400922	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-B625	SSHS-IRM5A2-A3-B625	6/21/2022	-	857.48	-	850.75	6 - 8 ft	6.73 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B626	SSHS-IRM5A2-A3-B626	6/21/2022	-	857.20	-	850.76	6 - 8 ft	6.44 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B627	SSHS-IRM5A2-A3-B627	6/21/2022	-	857.04	-	850.50	6 - 8 ft	6.54 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B628	SSHS-IRM5A2-A3-B628	6/21/2022	-	857.29	-	850.32	6 - 8 ft	6.97 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B629	SSHS-IRM5A2-A3-B629	6/21/2022	-	857.30	-	850.25	6 - 8 ft	7.05 ft	1801400922	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-B630	SSHS-IRM5A2-A3-B630	6/21/2022	-	857.00	-	849.31	6 - 8 ft	7.7 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B631	SSHS-IRM5A2-A3-B631	6/21/2022	-	856.80	-	849.38	6 - 8 ft	7.42 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B632	SSHS-IRM5A2-A3-B632	6/21/2022	-	856.60	-	849.23	6 - 8 ft	7.37 ft	1801400922	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400922	Not Excavated				< 0.045 U	< 0.036 U	0.060 J	< 0.049 U	< 0.045 U	< 0.028 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 110 U								
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 110 U								
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated	< 110 U								
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated	< 110 U								
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated	< 100 U								
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406773	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.028 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated	< 100 U								
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406773	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated	< 100 U								
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated		< 30 U							
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated		< 32 U							
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411042	Not Excavated				< 0.048 U	< 0.038 U	0.077 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated		< 34 U							
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411052	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated		< 29 U							
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated		< 29 U							
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411062	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated		< 33 U							
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated		< 30 U							
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated		< 29 U							
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated	< 490 U								
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated	< 110 U								
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated		< 33 U							
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated		< 32 U							
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418892	Not Excavated				< 0.052 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated		< 31 U							
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated		< 31 U							
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated		< 31 U							
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated		< 31 U							
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated		< 30 U							
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418892	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated		< 30 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400922	Not Excavated	< 0.046 U	< 0.036 U	< 0.027 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.040 U	< 0.050 U	< 0.039 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated									
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated									
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated									
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated									
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated									
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406773	Not Excavated	< 0.046 U	< 0.036 U	< 0.027 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406773	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	0.090 J	< 0.054 U	< 0.042 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated									
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated									
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411042	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated									
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated									
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411052	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	0.035 J	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated									
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411062	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated									
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated									
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated									
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418892	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418892	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A3-B636	SSHS-IRM5A2-A3-B636	6/21/2022	-	856.68	-	849.17	6 - 8 ft	7.51 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B637	SSHS-IRM5A2-A3-B637	6/21/2022	-	856.86	-	849.36	6 - 8 ft	7.51 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B638	SSHS-IRM5A2-A3-B638	6/21/2022	-	856.81	-	849.41	6 - 8 ft	7.39 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B639	SSHS-IRM5A2-A3-B639	6/21/2022	-	856.47	-	849.01	6 - 8 ft	7.46 ft	1801400922	Not Excavated	< 0.035 U	< 0.020 U	< 0.039 U	< 0.033 U	< 0.025 U	< 0.022 U
Northern Athletic Field	A3-S617	SSHS-IRM5A2-DUP140	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated						
Northern Athletic Field	A4-S814	SSHS-IRM5A2-DUP141	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated						
Northern Athletic Field	A3-S616	SSHS-IRM5A2-A3-S616	6/22/2022	-	857.10	-	850.84	6 - 8 ft	6.26 ft	1801401821	Not Excavated						
Northern Athletic Field	A3-S617	SSHS-IRM5A2-A3-S617	6/22/2022	-	857.42	-	851.01	6 - 8 ft	6.41 ft	1801401821	Not Excavated						
Northern Athletic Field	A4-S814	SSHS-IRM5A2-A4-S814	6/22/2022	-	857.80	-	850.31	6 - 8 ft	7.5 ft	1801401821	Not Excavated						
Northern Athletic Field	FISR-S51	SSHS-IRM5A2-FISR-S51	6/30/2022	-	852.79	-	845.26	6 - 8 ft	7.53 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S52	SSHS-IRM5A2-FISR-S52	6/30/2022	-	852.90	-	845.83	6 - 8 ft	7.07 ft	1801406773	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FISR-S58	SSHS-IRM5A2-FISR-S58	6/30/2022	-	853.50	-	846.25	6 - 8 ft	7.25 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S56	SSHS-IRM5A2-FISR-S56	6/30/2022	-	853.73	-	847.59	6 - 8 ft	6.14 ft	1801406773	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	FISR-S62	SSHS-IRM5A2-FISR-S62	6/30/2022	-	854.57	-	848.01	6 - 8 ft	6.56 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S68	SSHS-IRM5A2-FISR-S68	6/30/2022	-	854.65	-	847.68	6 - 8 ft	6.97 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S61	SSHS-IRM5A2-FISR-S61	6/30/2022	-	853.50	-	847.27	6 - 8 ft	6.23 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S67	SSHS-IRM5A2-FISR-S67	6/30/2022	-	854.61	-	847.07	6 - 8 ft	7.54 ft	1801406772	Not Excavated						
Northern Athletic Field	FL-WELL1-S2	SSHS-IRM5A2-FL-WELL1-S2	7/8/2022	-	856.92	-	849.65	6 - 8 ft	7.27 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S5	SSHS-IRM5A2-FL-WELL1-S5	7/8/2022	-	856.88	-	849.80	6 - 8 ft	7.08 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S8	SSHS-IRM5A2-FL-WELL1-S8	7/8/2022	-	856.91	-	850.25	6 - 8 ft	6.66 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-DUP154	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411041	Not Excavated						
Northern Athletic Field	FL-FISN-S1	SSHS-IRM5A2-FL-FISN-S1	7/11/2022	-	856.54	-	850.32	6 - 8 ft	6.22 ft	1801411042	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-FISN-S2	SSHS-IRM5A2-FL-FISN-S2	7/11/2022	-	856.54	-	848.95	6 - 8 ft	7.59 ft	1801411041	Not Excavated						
Northern Athletic Field	FL-FISN-S4	SSHS-IRM5A2-FL-FISN-S4	7/11/2022	-	856.53	-	848.72	6 - 8 ft	7.81 ft	1801411041	Not Excavated						
Northern Athletic Field	FL-FISN-S6	SSHS-IRM5A2-FL-FISN-S6	7/11/2022	-	856.80	-	849.57	6 - 8 ft	7.23 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S8	SSHS-IRM5A2-FL-FISN-S8	7/11/2022	-	856.77	-	849.35	6 - 8 ft	7.42 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S10	SSHS-IRM5A2-FL-FISN-S10	7/11/2022	-	856.52	-	849.64	6 - 8 ft	6.88 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S12	SSHS-IRM5A2-FL-FISN-S12	7/11/2022	-	856.55	-	849.31	6 - 8 ft	7.24 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S14	SSHS-IRM5A2-FL-FISN-S14	7/11/2022	-	856.64	-	849.30	6 - 8 ft	7.33 ft	1801411052	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-FISN-S16	SSHS-IRM5A2-FL-FISN-S16	7/11/2022	-	856.62	-	849.31	6 - 8 ft	7.31 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S18	SSHS-IRM5A2-FL-FISN-S18	7/11/2022	-	856.69	-	849.42	6 - 8 ft	7.27 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S20	SSHS-IRM5A2-FL-FISN-S20	7/11/2022	-	856.69	-	849.16	6 - 8 ft	7.54 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S22	SSHS-IRM5A2-FL-FISN-S22	7/11/2022	-	856.77	-	849.50	6 - 8 ft	7.27 ft	1801411051	Not Excavated						
Northern Athletic Field	FL-FISN-S24	SSHS-IRM5A2-FL-FISN-S24	7/11/2022	-	856.75	-	849.90	6 - 8 ft	6.84 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S26	SSHS-IRM5A2-FL-FISN-S26	7/11/2022	-	856.82	-	849.66	6 - 8 ft	7.17 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S30	SSHS-IRM5A2-FL-FISN-S30	7/11/2022	-	856.85	-	849.37	6 - 8 ft	7.49 ft	1801411062	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-FISN-S32	SSHS-IRM5A2-FL-FISN-S32	7/11/2022	-	856.84	-	849.65	6 - 8 ft	7.19 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S34	SSHS-IRM5A2-FL-FISN-S34	7/11/2022	-	856.82	-	849.20	6 - 8 ft	7.62 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S36	SSHS-IRM5A2-FL-FISN-S36	7/11/2022	-	856.77	-	849.13	6 - 8 ft	7.64 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S38	SSHS-IRM5A2-FL-FISN-S38	7/11/2022	-	856.67	-	849.29	6 - 8 ft	7.38 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-S40	SSHS-IRM5A2-FL-FISN-S40	7/11/2022	-	856.66	-	848.98	6 - 8 ft	7.68 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-B3	SSHS-IRM5A2-FL-FISN-B3	7/11/2022	-	856.54	-	848.66	6 - 8 ft	7.88 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B6	SSHS-IRM5A2-FL-FISN-B6	7/11/2022	-	856.76	-	848.87	6 - 8 ft	7.89 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B7	SSHS-IRM5A2-FL-FISN-B7	7/11/2022	-	856.83	-	849.09	6 - 8 ft	7.74 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-RS-B1	SSHS-IRM5A2-FL-RS-B1	7/14/2022	-	856.63	-	850.17	6 - 8 ft	6.46 ft	1801413131	Not Excavated						
Northern Athletic Field	PIPE5A	SSHS-IRM5A2-PIPE5A	7/20/2022	-	856.39	-	849.82	6 - 8 ft	6.57 ft	1801416481	Not Excavated						
Northern Athletic Field	PIPE5B	SSHS-IRM5A2-PIPE5B	7/20/2022	-	856.39	-	849.34	6 - 8 ft	7.05 ft	1801416481	Not Excavated						
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-DUP173	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S1	SSHS-IRM5A2-PIPE24-S1	7/25/2022	-	856.64	-	849.23	6 - 8 ft	7.42 ft	1801418892	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	PIPE24-S2	SSHS-IRM5A2-PIPE24-S2	7/25/2022	-	856.62	-	849.65	6 - 8 ft	6.97 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S3	SSHS-IRM5A2-PIPE24-S3	7/25/2022	-	856.64	-	849.63	6 - 8 ft	7.01 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S4	SSHS-IRM5A2-PIPE24-S4	7/25/2022	-	856.61	-	849.60	6 - 8 ft	7.01 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S5	SSHS-IRM5A2-PIPE24-S5	7/25/2022	-	856.57	-	849.48	6 - 8 ft	7.1 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-S6	SSHS-IRM5A2-PIPE24-S6	7/25/2022	-	856.46	-	849.42	6 - 8 ft	7.05 ft	1801418892	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	PIPE24-S7	SSHS-IRM5A2-PIPE24-S7	7/25/2022	-	856.43	-	849.33	6 - 8 ft	7.1 ft	1801418891	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated		< 33 U							
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated		< 30 U							
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated		< 30 U							
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated		< 30 U							
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418912	Not Excavated				< 0.050 U	< 0.040 U	0.056 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated		< 32 U							
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated		< 33 U							
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated		< 30 U							
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated		< 31 U							
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated		< 30 U							
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated		< 32 U							
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated		< 31 U							
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated		< 34 U							
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated		< 32 U							
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated		< 29 U							
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated		< 31 U							
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426142	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated		< 31 U							
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426142	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated		< 31 U							
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426142	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated		< 29 U							
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426142	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated		< 29 U							
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426142	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated		< 31 U							
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated		< 29 U							
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426152	Not Excavated				< 0.045 U	< 0.035 U	< 0.043 U	< 0.048 U	< 0.045 U	< 0.028 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated		< 32 U							
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426162	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated		< 31 U							
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated		< 30 U							
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426842	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated									
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418912	Not Excavated	< 0.051 U	0.050 J	< 0.030 U	0.056 J	< 0.023 U	< 0.034 U	0.078 J	0.11 J	0.072 J
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated									
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated									
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated									
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated									
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426142	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426142	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.048 J	< 0.056 U	< 0.043 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426142	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426142	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426142	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated									
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated									
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426152	Not Excavated	< 0.045 U	< 0.035 U	< 0.027 U	< 0.029 U	< 0.020 U	< 0.031 U	< 0.040 U	< 0.049 U	< 0.038 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426162	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated									
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated									
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426842	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	PIPE24-S9	SSHS-IRM5A2-PIPE24-S9	7/25/2022	-	856.40	-	848.99	6 - 8 ft	7.41 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-B1	SSHS-IRM5A2-PIPE24-B1	7/25/2022	-	856.63	-	848.79	6 - 8 ft	7.84 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-B2	SSHS-IRM5A2-PIPE24-B2	7/25/2022	-	856.60	-	848.77	6 - 8 ft	7.83 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE24-B3	SSHS-IRM5A2-PIPE24-B3	7/25/2022	-	856.44	-	848.48	6 - 8 ft	7.96 ft	1801418891	Not Excavated						
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S1	SSHS-IRM5A2-FL-PIPE17-S1	7/25/2022	-	856.29	-	849.38	6 - 8 ft	6.9 ft	1801418912	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	PIPE17-S2	SSHS-IRM5A2-FL-PIPE17-S2	7/25/2022	-	856.26	-	848.53	6 - 8 ft	7.74 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S3	SSHS-IRM5A2-FL-PIPE17-S3	7/25/2022	-	856.16	-	850.09	6 - 8 ft	6.06 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S4	SSHS-IRM5A2-FL-PIPE17-S4	7/25/2022	-	856.19	-	848.55	6 - 8 ft	7.65 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S6	SSHS-IRM5A2-FL-PIPE17-S6	7/25/2022	-	856.48	-	848.94	6 - 8 ft	7.54 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S7	SSHS-IRM5A2-FL-PIPE17-S7	7/25/2022	-	856.43	-	850.23	6 - 8 ft	6.2 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S8	SSHS-IRM5A2-FL-PIPE17-S8	7/25/2022	-	856.43	-	848.59	6 - 8 ft	7.84 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-S10	SSHS-IRM5A2-FL-PIPE17-S10	7/25/2022	-	856.47	-	848.77	6 - 8 ft	7.7 ft	1801418911	Not Excavated						
Northern Athletic Field	FL-B612	SSHS-IRM5A2-DUP177	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B601	SSHS-IRM5A2-FL-B601	7/26/2022	-	856.66	-	850.48	6 - 8 ft	6.17 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B604	SSHS-IRM5A2-FL-B604	7/26/2022	-	856.74	-	850.69	6 - 8 ft	6.05 ft	1801419751	Not Excavated						
Northern Athletic Field	FL-B612	SSHS-IRM5A2-FL-B612	7/26/2022	-	856.72	-	850.44	6 - 8 ft	6.29 ft	1801419751	Not Excavated						
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-DUP182	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S1	SSHS-IRM5A2-FISC-S1	7/28/2022	-	856.69	-	849.49	6 - 8 ft	7.2 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S2	SSHS-IRM5A2-FISC-S2	7/28/2022	-	856.67	-	849.36	6 - 8 ft	7.31 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-B1	SSHS-IRM5A2-FISC-B1	7/28/2022	-	856.69	-	848.70	6 - 8 ft	7.99 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S3	SSHS-IRM5A2-FISC-S3	7/28/2022	-	856.80	-	849.25	6 - 8 ft	7.55 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S4	SSHS-IRM5A2-FISC-S4	7/28/2022	-	856.85	-	849.56	6 - 8 ft	7.29 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S5	SSHS-IRM5A2-FISC-S5	7/28/2022	-	856.89	-	849.82	6 - 8 ft	7.07 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S6	SSHS-IRM5A2-FISC-S6	7/28/2022	-	856.91	-	849.90	6 - 8 ft	7.01 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S7	SSHS-IRM5A2-FISC-S7	7/28/2022	-	856.85	-	849.92	6 - 8 ft	6.93 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S8	SSHS-IRM5A2-FISC-S8	7/28/2022	-	856.89	-	849.78	6 - 8 ft	7.11 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-B4	SSHS-IRM5A2-FISC-B4	7/28/2022	-	856.87	-	848.88	6 - 8 ft	8 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S9	SSHS-IRM5A2-FISC-S9	7/28/2022	-	856.62	-	849.25	6 - 8 ft	7.37 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-S10	SSHS-IRM5A2-FISC-S10	7/28/2022	-	856.87	-	849.34	6 - 8 ft	7.54 ft	1801421221	Not Excavated						
Northern Athletic Field	IG-B4	SSHS-ISMP-DUP3A	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S5	SSHS-ISMP-DUP2A	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426142	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW1-S1	SSHS-ISMP-FLDW1-S1	8/8/2022	-	856.15	-	848.23	6 - 8 ft	7.92 ft	1801426142	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S1	SSHS-ISMP-IG-S1	8/8/2022	-	855.72	-	848.63	6 - 8 ft	7.09 ft	1801426142	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	IG-S2	SSHS-ISMP-IG-S2	8/8/2022	-	856.05	-	848.05	6 - 8 ft	8.01 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S3	SSHS-ISMP-IG-S3	8/8/2022	-	856.10	-	848.87	6 - 8 ft	7.23 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S4	SSHS-ISMP-IG-S4	8/8/2022	-	855.81	-	848.77	6 - 8 ft	7.04 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S5	SSHS-ISMP-IG-S5	8/8/2022	-	855.64	-	848.62	6 - 8 ft	7.02 ft	1801426142	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	IG-S6	SSHS-ISMP-IG-S6	8/8/2022	-	855.88	-	848.54	6 - 8 ft	7.34 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S7	SSHS-ISMP-IG-S7	8/8/2022	-	856.10	-	848.77	6 - 8 ft	7.33 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-S8	SSHS-ISMP-IG-S8	8/8/2022	-	856.09	-	848.50	6 - 8 ft	7.59 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-B1	SSHS-ISMP-IG-B1	8/8/2022	-	855.54	-	848.23	6 - 8 ft	7.31 ft	1801426142	Not Excavated	< 0.037 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	IG-B2	SSHS-ISMP-IG-B2	8/8/2022	-	856.09	-	848.47	6 - 8 ft	7.61 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-B3	SSHS-ISMP-IG-B3	8/8/2022	-	855.95	-	848.67	6 - 8 ft	7.27 ft	1801426141	Not Excavated						
Northern Athletic Field	IG-B4	SSHS-ISMP-IG-B4	8/8/2022	-	855.59	-	848.51	6 - 8 ft	7.07 ft	1801426141	Not Excavated						
Northern Athletic Field	FL-S801	SSHS-IRM5A2-FL-S801	8/8/2022	-	856.36	-	848.33	6 - 8 ft	8.02 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S802	SSHS-IRM5A2-FL-S802	8/8/2022	-	855.98	-	848.61	6 - 8 ft	7.37 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S803	SSHS-IRM5A2-FL-S803	8/8/2022	-	856.17	-	848.43	6 - 8 ft	7.74 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S804	SSHS-IRM5A2-FL-S804	8/8/2022	-	856.43	-	848.48	6 - 8 ft	7.95 ft	1801426152	Not Excavated	< 0.034 U	< 0.019 U	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Northern Athletic Field	FISC-S15	SSHS-IRM5A2-FISC-S15	8/8/2022	-	856.75	-	848.86	6 - 8 ft	7.89 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-S17	SSHS-IRM5A2-FISC-S17	8/8/2022	-	856.68	-	848.73	6 - 8 ft	7.95 ft	1801426162	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	FISC-S19	SSHS-IRM5A2-FISC-S19	8/8/2022	-	856.63	-	848.75	6 - 8 ft	7.88 ft	1801426161	Not Excavated						
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426841	Not Excavated						
Northern Athletic Field	PIPE23-BOT	SSHS-IRM5A2-PIPE23-BOT	8/9/2022	-	856.26	-	848.44	6 - 8 ft	7.83 ft	1801426842	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	FL-DW3A-S2	SSHS-IRM5A2-FL-DW3A-S2	8/10/2022	-	856.59	-	848.59	6 - 8 ft	8 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427631	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427632	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated		< 30 U							
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427632	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated		< 30 U							
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated		< 30 U							
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428482	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated		< 31 U							
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated		< 35 U							
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated		< 29 U							
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428482	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated		< 30 U							
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated		< 30 U							
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428492	Not Excavated				< 0.045 U	< 0.036 U	< 0.043 U	< 0.049 U	< 0.045 U	< 0.028 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated		< 32 U							
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated		< 31 U							
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428492	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated		< 29 U							
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429192	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated		< 30 U							
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429192	Not Excavated				< 0.044 U	< 0.035 U	< 0.042 U	< 0.048 U	< 0.044 U	< 0.028 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated		< 30 U							
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated		< 29 U							
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429192	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801430091	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801430091	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated		< 30 U							
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated		< 29 U							
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated		< 29 U							
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated		< 30 U							
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430712	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated		< 31 U							
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated		< 31 U							
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430712	Not Excavated				< 0.051 U	< 0.040 U	0.080 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated		< 33 U							
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated		< 32 U							
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated		< 32 U							
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated		< 34 U							
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433662	Not Excavated				< 0.053 U	< 0.042 U	0.15 J	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated		< 34 U							
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated		< 34 U							
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated		< 32 U							
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated		< 32 U							
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated		< 34 U							
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated		< 32 U							
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated		< 33 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427632	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427632	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428482	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428482	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated									
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428492	Not Excavated	< 0.046 U	< 0.036 U	< 0.027 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated									
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428492	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429192	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429192	Not Excavated	< 0.045 U	< 0.035 U	< 0.027 U	< 0.029 U	< 0.020 U	< 0.030 U	< 0.040 U	< 0.049 U	< 0.038 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated									
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429192	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801430091	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated									
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801430091	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.19 J	0.061 J	0.051 J
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated									
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated									
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated									
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated									
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated									
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430712	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated									
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430712	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	0.038 J	0.033 J	< 0.035 U	0.20 J	0.063 J	0.043 J
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated									
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433662	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	0.16 J	0.061 J	0.070 J
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated									
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated									
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FL-DW3A-S4	SSHS-IRM5A2-FL-DW3A-S4	8/10/2022	-	856.64	-	850.56	6 - 8 ft	6.08 ft	1801427632	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-B600A	SSHS-IRM5A2-FL-B600A	8/10/2022	-	856.55	-	850.24	6 - 8 ft	6.31 ft	1801427632	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B602A	SSHS-IRM5A2-FL-B602A	8/10/2022	-	856.55	-	850.34	6 - 8 ft	6.2 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-B605A	SSHS-IRM5A2-FL-B605A	8/10/2022	-	856.64	-	850.39	6 - 8 ft	6.25 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-B606A	SSHS-IRM5A2-FL-B606A	8/10/2022	-	856.57	-	850.40	6 - 8 ft	6.17 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-B668	SSHS-IRM5A2-DUP191	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B652	SSHS-IRM5A2-FL-B652	8/11/2022	-	856.87	-	850.69	6 - 8 ft	6.18 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B653	SSHS-IRM5A2-FL-B653	8/11/2022	-	856.53	-	850.14	6 - 8 ft	6.39 ft	1801428482	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B654	SSHS-IRM5A2-FL-B654	8/11/2022	-	856.49	-	850.25	6 - 8 ft	6.24 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B662	SSHS-IRM5A2-FL-B662	8/11/2022	-	856.14	-	849.91	6 - 8 ft	6.23 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B662A	SSHS-IRM5A2-FL-B662A	8/11/2022	-	856.24	-	850.08	6 - 8 ft	6.16 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B663	SSHS-IRM5A2-FL-B663	8/11/2022	-	856.90	-	850.52	6 - 8 ft	6.38 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B664	SSHS-IRM5A2-FL-B664	8/11/2022	-	856.72	-	850.67	6 - 8 ft	6.05 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B665	SSHS-IRM5A2-FL-B665	8/11/2022	-	856.40	-	850.31	6 - 8 ft	6.09 ft	1801428482	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-B668	SSHS-IRM5A2-FL-B668	8/11/2022	-	856.49	-	849.98	6 - 8 ft	6.51 ft	1801428481	Not Excavated						
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B669	SSHS-IRM5A2-FL-B669	8/11/2022	-	856.77	-	850.61	6 - 8 ft	6.16 ft	1801428492	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.025 U	< 0.022 U
Northern Athletic Field	FL-B672	SSHS-IRM5A2-FL-B672	8/11/2022	-	856.48	-	850.14	6 - 8 ft	6.35 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428491	Not Excavated						
Northern Athletic Field	FL-B673	SSHS-IRM5A2-FL-B673	8/11/2022	-	856.88	-	850.56	6 - 8 ft	6.32 ft	1801428492	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-B684	SSHS-IRM5A2-DUP193	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429192	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-B677	SSHS-IRM5A2-FL-B677	8/12/2022	-	856.52	-	849.95	6 - 8 ft	6.58 ft	1801429192	Not Excavated	< 0.034 U	< 0.019 U	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Northern Athletic Field	FL-B676A	SSHS-IRM5A2-FL-B676A	8/12/2022	-	856.18	-	849.99	6 - 8 ft	6.19 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429191	Not Excavated						
Northern Athletic Field	FL-B684	SSHS-IRM5A2-FL-B684	8/12/2022	-	856.45	-	850.04	6 - 8 ft	6.41 ft	1801429192	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FISR-S92	SSHS-IRM5A2-FISR-S92	8/13/2022	-	855.30	-	849.17	6 - 8 ft	6.14 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S93	SSHS-IRM5A2-FISR-S93	8/13/2022	-	855.31	-	847.45	6 - 8 ft	7.86 ft	1801430091	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801429561	Not Excavated						
Northern Athletic Field	FISR-S96	SSHS-IRM5A2-FISR-S96	8/13/2022	-	855.06	-	848.59	6 - 8 ft	6.46 ft	1801430091	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-B690	SSHS-IRM5A2-FL-B690	8/15/2022	-	856.61	-	850.39	6 - 8 ft	6.22 ft	1801429561	Not Excavated						
Northern Athletic Field	FL-B691	SSHS-IRM5A2-FL-B691	8/15/2022	-	856.64	-	850.18	6 - 8 ft	6.47 ft	1801429561	Not Excavated						
Northern Athletic Field	FISC-S21	SSHS-IRM5A2-FISC-S21	8/15/2022	-	856.54	-	848.70	6 - 8 ft	7.84 ft	1801429561	Not Excavated						
Northern Athletic Field	PIPE17-S11	SSHS-IRM5A2-PIPE17-S11	8/15/2022	-	856.56	-	850.22	6 - 8 ft	6.33 ft	1801429591	Not Excavated						
Northern Athletic Field	FLSP-S10	SSHS-IRM5A2-FLSP-S10	8/17/2022	-	856.69	-	850.22	6 - 8 ft	6.47 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S11	SSHS-IRM5A2-FLSP-S11	8/17/2022	-	856.73	-	849.99	6 - 8 ft	6.74 ft	1801430701	Not Excavated						
Northern Athletic Field	FL-B696	SSHS-IRM5A2-FL-B696	8/17/2022	-	856.50	-	849.90	6 - 8 ft	6.6 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-B700	SSHS-IRM5A2-FL-B700	8/17/2022	-	856.74	-	849.71	6 - 8 ft	7.03 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-B701	SSHS-IRM5A2-FL-B701	8/17/2022	-	857.04	-	849.94	6 - 8 ft	7.1 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-B702	SSHS-IRM5A2-FL-B702	8/17/2022	-	856.88	-	849.78	6 - 8 ft	7.1 ft	1801430712	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-LPS1	SSHS-IRM5A2-FL-LPS1	8/17/2022	-	856.77	-	849.93	6 - 8 ft	6.84 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430711	Not Excavated						
Northern Athletic Field	FL-LPS2	SSHS-IRM5A2-FL-LPS2	8/17/2022	-	856.57	-	850.11	6 - 8 ft	6.47 ft	1801430712	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	FISR-S81	SSHS-IRM5A2-FISR-S81	8/18/2022	-	855.03	-	847.10	6 - 8 ft	7.93 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S84	SSHS-IRM5A2-FISR-S84	8/18/2022	-	855.16	-	847.32	6 - 8 ft	7.84 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S88	SSHS-IRM5A2-FISR-S88	8/18/2022	-	854.92	-	847.95	6 - 8 ft	6.97 ft	1801430891	Not Excavated						
Northern Athletic Field	A6-S604	SSHS-IRM5A2-A6-S604	8/23/2022	-	857.52	-	850.46	6 - 8 ft	7.06 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S600	SSHS-IRM5A2-A6-S600	8/23/2022	-	857.44	-	850.47	6 - 8 ft	6.97 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S601	SSHS-IRM5A2-A6-S601	8/23/2022	-	857.93	-	850.25	6 - 8 ft	7.68 ft	1801433662	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6-S602	SSHS-IRM5A2-A6-S602	8/23/2022	-	857.77	-	850.03	6 - 8 ft	7.74 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S603	SSHS-IRM5A2-A6-S603	8/23/2022	-	857.49	-	850.23	6 - 8 ft	7.26 ft	1801433661	Not Excavated						
Northern Athletic Field	ST-B600	SSHS-IRM5A2-DUP207	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated						
Northern Athletic Field	ST-S601	SSHS-IRM5A2-DUP205	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S600	SSHS-IRM5A2-ST-S600	8/24/2022	-	856.62	-	850.32	6 - 8 ft	6.3 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S601	SSHS-IRM5A2-ST-S601	8/24/2022	-	856.66	-	850.27	6 - 8 ft	6.39 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434601	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434602	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated		< 32 U							
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434602	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated		< 47 U							
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated		< 31 U							
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated		< 32 U							
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434612	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.033 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated		< 32 U							
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated		< 32 U							
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435252	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated		< 31 U							
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated		< 30 U							
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435252	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated		< 33 U							
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435262	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated		< 32 U							
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated		< 30 U							
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated		< 31 U							
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated		< 30 U							
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438872	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated		< 32 U							
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated		< 32 U							
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated		< 33 U							
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438872	Not Excavated				< 0.054 U	< 0.042 U	3.6	< 0.058 U	< 0.054 U	< 0.033 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated		< 30 U							
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated		< 30 U							
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated		< 32 U							
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438872	Not Excavated				< 0.050 U	< 0.040 U	0.44	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated		< 35 U							
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440002	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated		< 33 U							
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated		< 30 U							
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440002	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated		< 30 U							
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated		< 32 U							
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated		< 31 U							
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated		< 31 U							
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440002	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated		< 32 U							
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated		< 300 U							
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated		< 33 U							
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated		< 33 U							
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440002	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated		< 31 U							
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated		< 34 U							
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated		< 32 U							
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated		< 31 U							
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442132	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated		< 34 U							
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442132	Not Excavated				< 0.052 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated		< 30 U							
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated	< 110 U								
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated	< 120 U								
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated		< 32 U							
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated		< 31 U							
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated		< 33 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434602	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434602	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated									
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated									
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434612	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated									
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated									
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435252	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435252	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated									
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435262	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated									
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated									
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated									
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438872	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438872	Not Excavated	< 0.055 U	< 0.042 U	0.034 J	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	0.093 J	2.9
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated									
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438872	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	0.079 J	< 0.055 U	0.14 J
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440002	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.046 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440002	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	0.051 J	< 0.040 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440002	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440002	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated									
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442132	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442132	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated									
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated									
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated									
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	ST-S602	SSHS-IRM5A2-ST-S602	8/24/2022	-	856.64	-	850.54	6 - 8 ft	6.1 ft	1801434602	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S802	SSHS-IRM5A2-ST-S802	8/24/2022	-	856.45	-	848.54	6 - 8 ft	7.91 ft	1801434602	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	PIPE26	SSHS-IRM5A2-PIPE26	8/24/2022	-	856.61	-	850.28	6 - 8 ft	6.33 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S605	SSHS-IRM5A2-ST-S605	8/24/2022	-	856.98	-	850.68	6 - 8 ft	6.3 ft	1801434611	Not Excavated						
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434611	Not Excavated						
Northern Athletic Field	ST-S606	SSHS-IRM5A2-ST-S606	8/24/2022	-	857.02	-	850.87	6 - 8 ft	6.16 ft	1801434612	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	ST-B600	SSHS-IRM5A2-ST-B600	8/24/2022	-	856.94	-	850.70	6 - 8 ft	6.25 ft	1801434611	Not Excavated						
Northern Athletic Field	FL-B707	SSHS-IRM5A2-DUP211	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated						
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S806	SSHS-IRM5A2-ST-S806	8/25/2022	-	856.54	-	848.54	6 - 8 ft	8.01 ft	1801435252	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	ST-S807	SSHS-IRM5A2-ST-S807	8/25/2022	-	856.14	-	848.92	6 - 8 ft	7.22 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S808	SSHS-IRM5A2-ST-S808	8/25/2022	-	856.09	-	848.53	6 - 8 ft	7.56 ft	1801435252	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435261	Not Excavated						
Northern Athletic Field	S550-BOT2	SSHS-IRM5A2-S550-BOT2	8/25/2022	-	856.15	-	848.22	6 - 8 ft	7.93 ft	1801435262	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	FL-B704	SSHS-IRM5A2-FL-B704	8/25/2022	-	856.50	-	850.27	6 - 8 ft	6.23 ft	1801435261	Not Excavated						
Northern Athletic Field	FL-B707	SSHS-IRM5A2-FL-B707	8/25/2022	-	856.98	-	850.00	6 - 8 ft	6.98 ft	1801435261	Not Excavated						
Northern Athletic Field	FISC-S20	SSHS-IRM5A2-FISC-S20	8/26/2022	-	856.90	-	849.27	6 - 8 ft	7.63 ft	1801436181	Not Excavated						
Northern Athletic Field	A6-S607	SSHS-IRM5A2-DUP213	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S605	SSHS-IRM5A2-A6-S605	9/1/2022	-	854.84	-	847.26	6 - 8 ft	7.58 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S606	SSHS-IRM5A2-A6-S606	9/1/2022	-	855.06	-	848.01	6 - 8 ft	7.05 ft	1801438872	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-S607	SSHS-IRM5A2-A6-S607	9/1/2022	-	855.40	-	848.40	6 - 8 ft	7 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S608	SSHS-IRM5A2-A6-S608	9/1/2022	-	855.67	-	848.82	6 - 8 ft	6.85 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-S609	SSHS-IRM5A2-A6-S609	9/1/2022	-	856.00	-	849.65	6 - 8 ft	6.35 ft	1801438872	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6-B600	SSHS-IRM5A2-A6-B600	9/1/2022	-	854.90	-	847.16	6 - 8 ft	7.74 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B601	SSHS-IRM5A2-A6-B601	9/1/2022	-	855.09	-	847.87	6 - 8 ft	7.22 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438871	Not Excavated						
Northern Athletic Field	A6-B602	SSHS-IRM5A2-A6-B602	9/1/2022	-	855.45	-	848.35	6 - 8 ft	7.1 ft	1801438872	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S610	SSHS-IRM5A2-DUP216	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440002	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-B603	SSHS-IRM5A2-A6-B603	9/2/2022	-	855.72	-	848.93	6 - 8 ft	6.79 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-B604	SSHS-IRM5A2-A6-B604	9/2/2022	-	856.03	-	849.58	6 - 8 ft	6.45 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-B605	SSHS-IRM5A2-A6-B605	9/2/2022	-	855.01	-	847.14	6 - 8 ft	7.87 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B606	SSHS-IRM5A2-A6-B606	9/2/2022	-	855.27	-	847.71	6 - 8 ft	7.56 ft	1801440002	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-B607	SSHS-IRM5A2-A6-B607	9/2/2022	-	855.52	-	848.03	6 - 8 ft	7.49 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B608	SSHS-IRM5A2-A6-B608	9/2/2022	-	855.90	-	848.95	6 - 8 ft	6.95 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-B609	SSHS-IRM5A2-A6-B609	9/2/2022	-	856.17	-	849.25	6 - 8 ft	6.93 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S610	SSHS-IRM5A2-A6-S610	9/2/2022	-	855.03	-	847.20	6 - 8 ft	7.83 ft	1801440002	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-S611	SSHS-IRM5A2-A6-S611	9/2/2022	-	855.29	-	847.85	6 - 8 ft	7.44 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S612	SSHS-IRM5A2-A6-S612	9/2/2022	-	855.43	-	848.10	6 - 8 ft	7.33 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S613	SSHS-IRM5A2-A6-S613	9/2/2022	-	855.76	-	848.71	6 - 8 ft	7.05 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S614	SSHS-IRM5A2-A6-S614	9/2/2022	-	856.08	-	849.29	6 - 8 ft	6.79 ft	1801440002	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6-B412	SSHS-IRM5A2-A6-B412	9/2/2022	-	855.39	-	849.30	6 - 8 ft	6.09 ft	1801440001	Not Excavated						
Northern Athletic Field	A6-S615	SSHS-IRM5A2-A6-S615	9/6/2022	-	856.36	-	849.67	6 - 8 ft	6.69 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-B610	SSHS-IRM5A2-A6-B610	9/6/2022	-	856.43	-	850.01	6 - 8 ft	6.42 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S806	SSHS-IRM5A2-DUP220	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442132	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-S804	SSHS-IRM5A2-A6-S804	9/8/2022	-	856.92	-	848.96	6 - 8 ft	7.95 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S805	SSHS-IRM5A2-A6-S805	9/8/2022	-	856.95	-	849.00	6 - 8 ft	7.94 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S806	SSHS-IRM5A2-A6-S806	9/8/2022	-	856.38	-	849.08	6 - 8 ft	7.3 ft	1801442132	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-S807	SSHS-IRM5A2-A6-S807	9/8/2022	-	856.43	-	848.95	6 - 8 ft	7.48 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S422	SSHS-IRM5A2-A6-S422	9/13/2022	-	858.23	-	851.97	6 - 8 ft	6.26 ft	1801444221	Not Excavated						
Northern Athletic Field	A6-B437	SSHS-IRM5A2-A6-B437	9/13/2022	-	858.10	-	851.78	6 - 8 ft	6.32 ft	1801444221	Not Excavated						
Northern Athletic Field	DW11	SSHS-IRM5A2-DW11	9/14/2022	-	856.80	-	849.70	6 - 8 ft	7.11 ft	1801445021	Not Excavated						
Northern Athletic Field	A6-B613	SSHS-IRM5A2-DUP230	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-DUP231	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated		< 32 U							
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446682	Not Excavated				< 0.052 U	< 0.041 U	0.095 J	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated		< 33 U							
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated		< 33 U							
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated		< 34 U							
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446682	Not Excavated				< 0.054 U	< 0.043 U	0.39	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated		< 35 U							
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated		< 31 U							
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated		< 34 U							
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446682	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated		< 31 U							
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated		< 31 U							
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated		< 32 U							
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446682	Not Excavated				< 0.049 U	< 0.039 U	0.062 J	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated		< 32 U							
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated		< 35 U							
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated		< 31 U							
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated		< 34 U							
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446682	Not Excavated				< 0.051 U	< 0.040 U	0.20 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated		< 40 U							
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated		< 33 U							
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446692	Not Excavated				< 0.051 U	< 0.040 U	0.050 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated		< 33 U							
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated		< 31 U							
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446692	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated		< 31 U							
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446692	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated		< 33 U							
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447212	Not Excavated				< 0.051 U	< 0.040 U	0.064 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated		< 34 U							
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated		< 35 U							
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447212	Not Excavated				< 0.055 U	< 0.044 U	0.13 J	< 0.060 U	< 0.055 U	< 0.035 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated		< 35 U							
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated		< 34 U							
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated		< 33 U							
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451962	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453572	Not Excavated				< 0.053 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated		< 32 U							
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated		< 33 U							
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated		< 34 U							
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453572	Not Excavated				< 0.052 U	< 0.041 U	0.081 J	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated		< 33 U							
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated		< 33 U							
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated		< 33 U							
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated		< 32 U							
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465932	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated		< 33 U							
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated		< 33 U							
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465932	Not Excavated				< 0.053 U	< 0.042 U	0.64	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated		< 31 U							
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated		< 31 U							
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated		< 32 U							
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated		< 32 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446682	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446682	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	0.25
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446682	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446682	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	0.063 J
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated									
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446682	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.055 J	< 0.056 U	0.064 J
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446692	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.043 UT
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446692	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.051 U	< 0.039 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446692	Not Excavated	< 0.050 U	< 0.039 U	0.030 J	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated									
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447212	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.15 J	0.077 J	< 0.044 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447212	Not Excavated	< 0.057 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	0.23	0.10 J	< 0.047 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated									
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated									
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated									
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451962	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated									
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated									
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453572	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated									
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated									
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated									
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated									
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453572	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated									
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465932	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465932	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated									
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-S615A	SSHS-IRM5A2-A6-S615A	9/16/2022	-	856.61	-	849.95	6 - 8 ft	6.65 ft	1801446682	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-S616A	SSHS-IRM5A2-A6-S616A	9/16/2022	-	856.92	-	850.00	6 - 8 ft	6.91 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-S617A	SSHS-IRM5A2-A6-S617A	9/16/2022	-	857.06	-	850.02	6 - 8 ft	7.04 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-S618A	SSHS-IRM5A2-A6-S618A	9/16/2022	-	857.31	-	850.77	6 - 8 ft	6.54 ft	1801446682	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A6-S619A	SSHS-IRM5A2-A6-S619A	9/16/2022	-	857.04	-	850.89	6 - 8 ft	6.15 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-S617B	SSHS-IRM5A2-A6-S617B	9/16/2022	-	857.34	-	850.15	6 - 8 ft	7.2 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B611	SSHS-IRM5A2-A6-B611	9/16/2022	-	857.13	-	850.05	6 - 8 ft	7.09 ft	1801446682	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A6-B612	SSHS-IRM5A2-A6-B612	9/16/2022	-	857.67	-	850.19	6 - 8 ft	7.48 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B613	SSHS-IRM5A2-A6-B613	9/16/2022	-	857.15	-	850.11	6 - 8 ft	7.03 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B614	SSHS-IRM5A2-A6-B614	9/16/2022	-	856.78	-	849.93	6 - 8 ft	6.85 ft	1801446682	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B615	SSHS-IRM5A2-A6-B615	9/16/2022	-	857.59	-	850.73	6 - 8 ft	6.86 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B616	SSHS-IRM5A2-A6-B616	9/16/2022	-	857.29	-	850.76	6 - 8 ft	6.53 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B617	SSHS-IRM5A2-A6-B617	9/16/2022	-	856.96	-	850.39	6 - 8 ft	6.57 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446681	Not Excavated						
Northern Athletic Field	A6-B618	SSHS-IRM5A2-A6-B618	9/16/2022	-	856.69	-	850.18	6 - 8 ft	6.51 ft	1801446682	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A6-B619	SSHS-IRM5A2-A6-B619	9/16/2022	-	856.90	-	850.67	6 - 8 ft	6.23 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-S15	SSHS-IRM5A2-A6-FISLAT-S15	9/16/2022	-	856.53	-	848.61	6 - 8 ft	7.92 ft	1801446692	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A6-FISLAT-S16	SSHS-IRM5A2-A6-FISLAT-S16	9/16/2022	-	856.60	-	848.61	6 - 8 ft	7.99 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-S17	SSHS-IRM5A2-A6-FISLAT-S17	9/16/2022	-	856.67	-	848.88	6 - 8 ft	7.79 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-S18	SSHS-IRM5A2-A6-FISLAT-S18	9/16/2022	-	856.58	-	849.01	6 - 8 ft	7.57 ft	1801446692	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-B8	SSHS-IRM5A2-A6-FISLAT-B8	9/16/2022	-	856.61	-	848.70	6 - 8 ft	7.91 ft	1801446692	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-B621	SSHS-IRM5A2-A6-B621	9/16/2022	-	856.29	-	849.78	6 - 8 ft	6.51 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-B622	SSHS-IRM5A2-A6-B622	9/16/2022	-	856.41	-	850.29	6 - 8 ft	6.12 ft	1801446691	Not Excavated						
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-DUP233	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOTA	SSHS-IRM5A2-FISR-S71-BOTA	9/19/2022	-	854.69	-	846.77	6 - 8 ft	7.92 ft	1801447212	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	FISR-S71-BOTB	SSHS-IRM5A2-FISR-S71-BOTB	9/19/2022	-	853.49	-	846.06	6 - 8 ft	7.43 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOTC	SSHS-IRM5A2-FISR-S71-BOTC	9/19/2022	-	853.17	-	845.97	6 - 8 ft	7.2 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOT-S1	SSHS-IRM5A2-FISR-S71-BOT-S1	9/19/2022	-	854.75	-	846.70	6 - 8 ft	8.05 ft	1801447212	Not Excavated	< 0.043 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.027 U
Northern Athletic Field	FISR-S71-BOT-S2	SSHS-IRM5A2-FISR-S71-BOT-S2	9/19/2022	-	852.15	-	845.76	6 - 8 ft	6.4 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOT-S3	SSHS-IRM5A2-FISR-S71-BOT-S3	9/19/2022	-	852.18	-	845.79	6 - 8 ft	6.39 ft	1801447211	Not Excavated						
Northern Athletic Field	A6-S427	SSHS-IRM5A2-A6-S427	9/19/2022	-	854.81	-	848.55	6 - 8 ft	6.26 ft	1801447211	Not Excavated						
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451961	Not Excavated						
Northern Athletic Field	A6-S624	SSHS-IRM5A2-A6-S624	9/27/2022	-	856.14	-	849.81	6 - 8 ft	6.32 ft	1801451962	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	0.037 J
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-DUP237	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated						
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453571	Not Excavated						
Northern Athletic Field	MB-S3A	SSHS-IRM5A2-MB-S3A	9/29/2022	-	856.19	-	848.75	6 - 8 ft	7.44 ft	1801453572	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	MB-S5A	SSHS-IRM5A2-MB-S5A	9/29/2022	-	856.21	-	848.81	6 - 8 ft	7.4 ft	1801453571	Not Excavated						
Northern Athletic Field	MB-S7A	SSHS-IRM5A2-MB-S7A	9/29/2022	-	856.16	-	848.74	6 - 8 ft	7.42 ft	1801453571	Not Excavated						
Northern Athletic Field	MB-S9A	SSHS-IRM5A2-MB-S9A	9/29/2022	-	856.15	-	848.78	6 - 8 ft	7.37 ft	1801453571	Not Excavated						
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453571	Not Excavated						
Northern Athletic Field	MB-B1A	SSHS-IRM5A2-MB-B1A	9/29/2022	-	856.18	-	848.68	6 - 8 ft	7.5 ft	1801453572	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-B628	SSHS-IRM5A2-A6-B628	9/29/2022	-	856.13	-	850.07	6 - 8 ft	6.05 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B629	SSHS-IRM5A2-A6-B629	9/29/2022	-	855.98	-	849.77	6 - 8 ft	6.21 ft	1801453571	Not Excavated						
Northern Athletic Field	A6-B446	SSHS-IRM5A2-A6-B446	10/20/2022	-	857.41	-	851.33	6 - 8 ft	6.08 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B649	SSHS-IRM5A2-A6-B649	10/20/2022	-	856.35	-	849.83	6 - 8 ft	6.52 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-B650	SSHS-IRM5A2-A6-B650	10/20/2022	-	856.51	-	849.86	6 - 8 ft	6.65 ft	1801465932	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	0.049 J	< 0.025 U
Northern Athletic Field	A6-S632	SSHS-IRM5A2-A6-S632	10/20/2022	-	856.35	-	850.11	6 - 8 ft	6.24 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S633	SSHS-IRM5A2-A6-S633	10/20/2022	-	856.59	-	850.22	6 - 8 ft	6.37 ft	1801465932	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6-S634	SSHS-IRM5A2-A6-S634	10/20/2022	-	856.35	-	850.09	6 - 8 ft	6.26 ft	1801465931	Not Excavated						
Northern Athletic Field	A6-S639	SSHS-IRM5A2-A6-S639	10/20/2022	-	856.81	-	849.75	6 - 8 ft	7.07 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S640	SSHS-IRM5A2-A6-S640	10/20/2022	-	857.07	-	849.83	6 - 8 ft	7.24 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465941	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465942	Not Excavated				< 0.052 U	< 0.041 U	0.099 J	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated		< 30 U							
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated		< 31 U							
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated		< 30 U							
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469412	Not Excavated				< 0.048 U	< 0.038 U	0.65 B	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated		< 37 U							
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486622	Not Excavated				< 0.059 U	< 0.047 U	0.31	< 0.064 U	< 0.059 U	< 0.037 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated		< 33 U							
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486622	Not Excavated				< 0.052 U	< 0.041 U	0.17 J	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated		< 33 U							
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated		< 35 U							
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated		< 34 U							
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491412	Not Excavated				< 0.054 U	< 0.043 U	0.055 J	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated		< 33 U							
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated		< 32 U							
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated		< 33 U							
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated		< 38 U							
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated		< 34 U							
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491422	Not Excavated				< 0.053 U	< 0.042 U	0.13 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated		< 37 U							
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated		< 35 U							
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated		< 34 U							
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated		< 37 U							
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated		< 34 U							
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493702	Not Excavated				< 0.048 U	< 0.038 U	0.053 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated		< 33 U							
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated		< 30 U							
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573812	Not Excavated				< 0.053 U	< 0.042 U	0.072 J	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574522	Not Excavated				< 0.048 U	< 0.038 U	0.061 J	< 0.051 U	< 0.048 U	< 0.030 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated	< 120 U								
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574522	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated	< 120 U								
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589972	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated	< 110 U								
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated	< 110 U								
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608002	Not Excavated				< 0.056 U	< 0.045 U	< 0.054 U	< 0.061 U	< 0.056 U	< 0.035 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608002	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated	< 120 U								
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated		< 110 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465942	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469412	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.075 J	< 0.053 U	< 0.041 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated									
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated									
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486622	Not Excavated	< 0.061 U	< 0.047 U	< 0.036 U	< 0.038 U	< 0.027 U	< 0.041 U	0.14 J	< 0.065 U	0.078 J
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated									
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated									
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486622	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	0.065 J	< 0.057 U	0.055 J
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated									
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated									
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491412	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated									
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491422	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.10 J	< 0.058 U	< 0.045 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated									
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated									
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493702	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.082 J	0.060 J	< 0.041 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated									
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573812	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	0.037 J	< 0.024 U	< 0.036 U	0.087 J	0.074 J	< 0.045 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574522	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.28	0.099 J	< 0.041 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574522	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated									
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated									
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589972	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.041 U	< 0.051 U	< 0.039 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated									
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608002	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.039 U	< 0.051 U	< 0.062 U	< 0.048 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608002	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated									
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated									
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated									
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A6-S641	SSHS-IRM5A2-A6-S641	10/20/2022	-	857.57	-	849.75	6 - 8 ft	7.81 ft	1801465942	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-DUP246	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S13	SSHS-IRM5A2-A1-VAULT-S13	10/26/2022	-	857.07	-	849.25	6 - 8 ft	7.83 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S14	SSHS-IRM5A2-A1-VAULT-S14	10/26/2022	-	857.19	-	849.39	6 - 8 ft	7.8 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S15	SSHS-IRM5A2-A1-VAULT-S15	10/26/2022	-	857.36	-	849.51	6 - 8 ft	7.85 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S16	SSHS-IRM5A2-A1-VAULT-S16	10/26/2022	-	857.34	-	849.54	6 - 8 ft	7.8 ft	1801469412	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A1-VAULT-S17	SSHS-IRM5A2-A1-VAULT-S17	10/26/2022	-	857.17	-	849.32	6 - 8 ft	7.86 ft	1801469411	Not Excavated						
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated						
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-DUP262	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486622	Not Excavated	< 0.046 U	< 0.026 U	< 0.052 U	< 0.043 U	< 0.033 U	< 0.028 U
Northern Athletic Field	A6N-S602	SSHS-IRM5A2-A6N-S602	12/1/2022	-	854.82	-	848.68	6 - 8 ft	6.14 ft	1801486621	Not Excavated						
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486621	Not Excavated						
Northern Athletic Field	A6N-S603	SSHS-IRM5A2-A6N-S603	12/1/2022	-	854.94	-	848.88	6 - 8 ft	6.06 ft	1801486622	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6N-S604	SSHS-IRM5A2-A6N-S604	12/2/2022	-	855.20	-	848.99	6 - 8 ft	6.21 ft	1801487441	Not Excavated						
Northern Athletic Field	A6-S439	SSHS-IRM5A2-DUP268	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated						
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-S1	SSHS-ISMP-DO-S1	12/9/2022	-	858.33	-	851.93	6 - 8 ft	6.4 ft	1801491412	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	DO-S2	SSHS-ISMP-DO-S2	12/9/2022	-	858.32	-	851.71	6 - 8 ft	6.62 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-S7	SSHS-ISMP-DO-S7	12/9/2022	-	857.25	-	849.99	6 - 8 ft	7.26 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-S8	SSHS-ISMP-DO-S8	12/9/2022	-	857.12	-	850.36	6 - 8 ft	6.76 ft	1801491411	Not Excavated						
Northern Athletic Field	A6N-B233	SSHS-IRM5A2-A6N-B233	12/9/2022	-	858.75	-	852.09	6 - 8 ft	6.66 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B235	SSHS-IRM5A2-A6N-B235	12/9/2022	-	858.89	-	852.85	6 - 8 ft	6.05 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B236	SSHS-IRM5A2-A6N-B236	12/9/2022	-	858.99	-	852.55	6 - 8 ft	6.43 ft	1801491422	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A6N-B238	SSHS-IRM5A2-A6N-B238	12/9/2022	-	859.01	-	852.67	6 - 8 ft	6.33 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-B437A	SSHS-IRM5A2-A6N-B437A	12/9/2022	-	858.37	-	852.05	6 - 8 ft	6.32 ft	1801491421	Not Excavated						
Northern Athletic Field	A6N-S422A	SSHS-IRM5A2-A6N-S422A	12/9/2022	-	858.45	-	852.01	6 - 8 ft	6.43 ft	1801491421	Not Excavated						
Northern Athletic Field	A6-S439	SSHS-IRM5A2-A6-S439	12/9/2022	-	857.86	-	851.37	6 - 8 ft	6.5 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S2	SSHS-IRM5A2-A6N-S800-S2	12/9/2022	-	854.83	-	848.66	6 - 8 ft	6.17 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S5	SSHS-IRM5A2-A6N-S800-S5	12/9/2022	-	854.95	-	848.77	6 - 8 ft	6.18 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S13	SSHS-IRM5A2-A6N-S800-S13	12/14/2022	-	855.18	-	848.42	6 - 8 ft	6.77 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S16	SSHS-IRM5A2-A6N-S800-S16	12/14/2022	-	855.44	-	848.49	6 - 8 ft	6.96 ft	1801493702	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6N-S800-S19	SSHS-IRM5A2-A6N-S800-S19	12/14/2022	-	855.53	-	848.82	6 - 8 ft	6.72 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S22	SSHS-IRM5A2-A6N-S800-S22	12/14/2022	-	855.28	-	849.09	6 - 8 ft	6.19 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S25	SSHS-IRM5A2-A6N-S800-S25	12/14/2022	-	855.21	-	849.02	6 - 8 ft	6.19 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S26	SSHS-IRM5A2-A6N-S800-S26	12/14/2022	-	855.16	-	847.25	6 - 8 ft	7.91 ft	1801493701	Not Excavated						
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S26	SSHS-ISMP-NAF-IG-S26	6/1/2023	-	853.45	-	845.57	6 - 8 ft	7.88 ft	1801573812	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-S31	SSHS-ISMP-NAF-IG-S31	6/2/2023	-	853.36	-	845.49	6 - 8 ft	7.87 ft	1801574522	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-S38	SSHS-ISMP-NAF-IG-S38	6/2/2023	-	853.08	-	845.83	6 - 8 ft	7.25 ft	1801574522	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	AREA C-B3-S6	SSHS-IRM5A2-AREA C-B3-S6	6/6/2023	-	856.36	-	850.07	6 - 8 ft	6.29 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-S7	SSHS-IRM5A2-AREA C-B3-S7	6/6/2023	-	856.30	-	849.96	6 - 8 ft	6.33 ft	1801575441	Not Excavated						
Northern Athletic Field	AREA C-B3-B3	SSHS-IRM5A2-AREA C-B3-B3	6/6/2023	-	856.34	-	850.02	6 - 8 ft	6.32 ft	1801575441	Not Excavated						
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-DUP8A	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-S1	SSHS-ISMP-NAF-UT-S1	7/10/2023	-	852.83	-	846.48	6 - 8 ft	6.35 ft	1801589972	Not Excavated	< 0.036 U	< 0.020 U	< 0.040 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	NAF-UT-S2	SSHS-ISMP-NAF-UT-S2	7/10/2023	-	852.73	-	846.20	6 - 8 ft	6.53 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-UT-B1	SSHS-ISMP-NAF-UT-B1	7/10/2023	-	852.70	-	846.10	6 - 8 ft	6.6 ft	1801589971	Not Excavated						
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-DUP22A	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608002	Not Excavated	< 0.044 U	< 0.025 U	< 0.049 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	NAF-LP-S4	SSHS-ISMP-NAF-LP-S4	8/14/2023	-	855.84	-	849.74	6 - 8 ft	6.1 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-S5	SSHS-ISMP-NAF-LP-S5	8/14/2023	-	856.50	-	850.39	6 - 8 ft	6.11 ft	1801608002	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	NAF-LP-S6	SSHS-ISMP-NAF-LP-S6	8/14/2023	-	856.41	-	850.13	6 - 8 ft	6.28 ft	1801608001	Not Excavated						
Northern Athletic Field	NAF-LP-B1	SSHS-ISMP-NAF-LP-B1	8/14/2023	-	856.30	-	849.89	6 - 8 ft	6.42 ft	1801608001	Not Excavated						
Northern Athletic Field	A8PH3A1-S9	SSHS-IRM5A2-A8PH3A1-S9	11/29/2023	-	852.57	-	846.01	6 - 8 ft	6.56 ft	1801660601	Not Excavated						
Northern Athletic Field	A8PH3A1-S12	SSHS-IRM5A2-A8PH3A1-S12	11/30/2023	-	--	-	845.90	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S16	SSHS-IRM5A2-A8PH3A1-S16	11/30/2023	-	--	-	845.87	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S20	SSHS-IRM5A2-A8PH3A1-S20	11/30/2023	-	--	-	846.19	6 - 8 ft	6 - 8 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-DUP332	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661602	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661602	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated			< 40						
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated			< 40						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 120 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	0.031 J	< 0.074 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated			< 110 U						
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated	< 150 U								
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated	< 490 U								
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated	< 500 U								
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated	< 120 U								
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated	< 120 U								
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated	< 120 U								
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated	< 120 U								
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated	< 130 U								
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 120 U								
Northern Athletic Field	S131	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated	< 100 U								
Northern Athletic Field	S132	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated	< 120 U								
Northern Athletic Field	S170	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated	< 120 U								
Northern Athletic Field	S171	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated	< 120 U								
Northern Athletic Field	S178	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated	< 100 U								
Northern Athletic Field	S177	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated	< 100 U								
Northern Athletic Field	S176	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated	< 100 U								
Northern Athletic Field	S130	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated	< 110 U								
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 120 U								
Northern Athletic Field	S248	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated	< 110 U								
Northern Athletic Field	S252	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated	< 120 U								
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated	< 110 U								
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated	< 110 U								
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332632	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated	< 120 U								
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated	< 110 U								
Northern Athletic Field	S229	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated	< 110 U								
Northern Athletic Field	B594	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated	< 120 U								
Northern Athletic Field	S253	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated	< 120 U								
Northern Athletic Field	S225	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S224	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	S581	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated	< 110 U								
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated	< 110 U								
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated	< 120 U								
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354283	Not Excavated				< 0.052 U	< 0.041 U	0.29	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated	< 110 U								
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354702	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.032 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S580	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated	< 110 U								
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354702	Not Excavated				< 0.048 U	< 0.038 U	0.065 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated	< 100 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated									
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated									
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661602	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated									
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated									
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661602	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated									
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated									
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated									
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.036 U	< 0.030 U	< 0.032 U	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.036 U	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.085 U	< 0.21 U	< 0.090 U	< 0.080 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.037 U	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.039 U	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated									
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated									
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated									
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated									
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated									
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated									
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated									
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated									
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated									
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated									
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated									
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated									
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated									
Northern Athletic Field	S131	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated									
Northern Athletic Field	S132	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated									
Northern Athletic Field	S170	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated									
Northern Athletic Field	S171	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated									
Northern Athletic Field	S178	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated									
Northern Athletic Field	S177	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated									
Northern Athletic Field	S176	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated									
Northern Athletic Field	S130	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated									
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated									
Northern Athletic Field	S248	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated									
Northern Athletic Field	S252	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated									
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated									
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332632	Not Excavated	< 0.048 U	< 0.037 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated									
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated									
Northern Athletic Field	S229	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated									
Northern Athletic Field	B594	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated									
Northern Athletic Field	S253	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated									
Northern Athletic Field	S225	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated									
Northern Athletic Field	S224	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated									
Northern Athletic Field	S581	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated									
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated									
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated									
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated									
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated									
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354283	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	0.34
Northern Athletic Field	S289	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated									
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated									
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354702	Not Excavated	< 0.052 U	< 0.040 U	< 0.030 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated									
Northern Athletic Field	S580	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated									
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated									
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354702	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.067 J	0.055 J	< 0.041 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A8PH3A1-S26	SSHS-IRM5A2-A8PH3A1-S26	12/1/2023	-	--	-	846.29	6 - 8 ft	6 - 8 ft	1801661611	Not Excavated						
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-S27	SSHS-IRM5A2-A8PH3A1-S27	12/1/2023	-	852.51	-	846.23	6 - 8 ft	6.28 ft	1801661602	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	0.041 J	< 0.023 U
Northern Athletic Field	A8PH3A1-S28	SSHS-IRM5A2-A8PH3A1-S28	12/1/2023	-	852.23	-	844.73	6 - 8 ft	7.49 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661601	Not Excavated						
Northern Athletic Field	A8PH3A1-B9	SSHS-IRM5A2-A8PH3A1-B9	12/1/2023	-	852.15	-	846.01	6 - 8 ft	6.14 ft	1801661602	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	SSHS-B71	081614 09:00 DUP-20	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated						
Northern Athletic Field	SSHS-B71	SSHS-B71-6-9.5R (8)	8/15/2014	856.19	856.45	0.26	-	6 - 9.5 ft	6.26-9.76 ft	180-35858-1	Not Excavated						
Northern Athletic Field	SSHS-B3343	SSHS-B3343-SUB-8-10	12/20/2019	851.57	852.53	0.96	-	8 - 10 ft	8.96-10.96 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B3930	DUP-41	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.053 U	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-8-10	5/11/2021	856.50	855.82	-0.68	-	8 - 10 ft	7.32-9.32 ft	1801214741	Not Excavated	< 0.056 U	< 0.053 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-8-10	5/17/2021	856.37	856.43	0.06	-	8 - 10 ft	8.06-10.06 ft	1801217472	Not Excavated	< 0.057 U	< 0.054 U	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3922	SSHS-B3922-SUB-8-10	5/18/2021	855.95	855.66	-0.29	-	8 - 10 ft	7.71-9.71 ft	1801218221	Not Excavated	< 0.060 U	< 0.056 U	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-8-10	9/16/2021	856.07	856.16	0.09	-	8 - 10 ft	8.09-10.09 ft	180-127205-2	Not Excavated						
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-8-10	9/17/2021	856.64	856.68	0.04	-	8 - 10 ft	8.04-10.04 ft	180-127265-1	Not Excavated						
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-8-10	9/17/2021	857.91	857.91	0.00	-	8 - 10 ft	8-10 ft	180-127265-2	Not Excavated						
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-8-10	9/22/2021	856.72	856.72	0.00	-	8 - 10 ft	8-10 ft	180-127415-1	Not Excavated						
Northern Athletic Field	DW1-BOT1A	SSHS-IRM5A2-DW1-BOT1A	11/6/2021	-	856.86	-	848.36	8 - 10 ft	8.5 ft	1801296791	Not Excavated						
Northern Athletic Field	B236-S5	SSHS-IRM5A2-B236-S5	11/6/2021	-	855.82	-	846.59	8 - 10 ft	9.23 ft	1801296741	Not Excavated						
Northern Athletic Field	B236-S3	SSHS-IRM5A2-B236-S3	11/6/2021	-	855.98	-	846.41	8 - 10 ft	9.57 ft	1801296741	Not Excavated						
Northern Athletic Field	DW2-S4	SSHS-IRM5A2-DW2-S4	11/8/2021	-	857.13	-	847.26	8 - 10 ft	9.87 ft	1801296791	Not Excavated						
Northern Athletic Field	DW2-S3	SSHS-IRM5A2-DW2-S3	11/8/2021	-	857.17	-	848.98	8 - 10 ft	8.18 ft	1801296791	Not Excavated						
Northern Athletic Field	DW3-S3	SSHS-IRM5A2-DW3-S3	11/10/2021	-	856.83	-	848.78	8 - 10 ft	8.05 ft	1801298201	Not Excavated						
Northern Athletic Field	DW3-S4	SSHS-IRM5A2-DW3-S4	11/10/2021	-	856.83	-	847.43	8 - 10 ft	9.4 ft	1801298201	Not Excavated						
Northern Athletic Field	B236-S1-BOT1	SSHS-IRM5A2-B236-S1-BOT1	11/13/2021	-	855.79	-	845.77	8 - 10 ft	10.02 ft	1801299881	Not Excavated						
Northern Athletic Field	B236-S1A	SSHS-IRM5A2-B236-S1A	11/13/2021	-	855.71	-	847.02	8 - 10 ft	8.69 ft	1801299881	Not Excavated						
Northern Athletic Field	S132	SSHS-IRM5A2-DUP25	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated						
Northern Athletic Field	S131	SSHS-IRM5A2-S131	1/13/2022	-	858.87	-	849.44	8 - 10 ft	9.44 ft	1801323151	Not Excavated						
Northern Athletic Field	S132	SSHS-IRM5A2-S132	1/13/2022	-	858.77	-	849.82	8 - 10 ft	8.94 ft	1801323151	Not Excavated						
Northern Athletic Field	S170	SSHS-IRM5A2-S170	1/13/2022	-	858.12	-	848.86	8 - 10 ft	9.27 ft	1801323151	Not Excavated						
Northern Athletic Field	S171	SSHS-IRM5A2-S171	1/13/2022	-	858.08	-	849.09	8 - 10 ft	8.98 ft	1801323151	Not Excavated						
Northern Athletic Field	S178	SSHS-IRM5A2-S178	1/13/2022	-	856.09	-	847.10	8 - 10 ft	8.99 ft	1801323151	Not Excavated						
Northern Athletic Field	S177	SSHS-IRM5A2-S177	1/13/2022	-	855.87	-	847.12	8 - 10 ft	8.75 ft	1801323151	Not Excavated						
Northern Athletic Field	S176	SSHS-IRM5A2-S176	1/13/2022	-	855.87	-	847.56	8 - 10 ft	8.31 ft	1801323151	Not Excavated						
Northern Athletic Field	S130	SSHS-IRM5A2-S130	1/13/2022	-	857.96	-	849.77	8 - 10 ft	8.2 ft	1801323151	Not Excavated						
Northern Athletic Field	S248	SSHS-IRM5A2-DUP28	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated						
Northern Athletic Field	S248	SSHS-IRM5A2-S248	1/19/2022	-	854.51	-	846.04	8 - 10 ft	8.47 ft	1801325261	Not Excavated						
Northern Athletic Field	S252	SSHS-IRM5A2-S252	1/20/2022	-	855.42	-	845.44	8 - 10 ft	9.98 ft	1801325891	Not Excavated						
Northern Athletic Field	RS-BOT40	SSHS-IRM5A2-RS-BOT40	2/7/2022	-	854.48	-	845.70	8 - 10 ft	8.78 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332631	Not Excavated						
Northern Athletic Field	RS-S66	SSHS-IRM5A2-RS-S66	2/7/2022	-	854.52	-	846.45	8 - 10 ft	8.07 ft	1801332632	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S172A-BOT2	SSHS-IRM5A2-S172A-BOT2	2/8/2022	-	857.56	-	848.35	8 - 10 ft	9.2 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-S8	SSHS-IRM5A2-S172A-S8	2/8/2022	-	857.94	-	848.99	8 - 10 ft	8.95 ft	1801333441	Not Excavated						
Northern Athletic Field	S172A-BOT3	SSHS-IRM5A2-S172A-BOT3	2/8/2022	-	857.85	-	848.34	8 - 10 ft	9.51 ft	1801333441	Not Excavated						
Northern Athletic Field	S229	SSHS-IRM5A2-S229	2/21/2022	-	857.71	-	847.79	8 - 10 ft	9.92 ft	1801340041	Not Excavated						
Northern Athletic Field	B594	SSHS-IRM5A2-B594	3/2/2022	-	857.18	-	847.46	8 - 10 ft	9.71 ft	1801345571	Not Excavated						
Northern Athletic Field	S253	SSHS-IRM5A2-S253	3/3/2022	-	853.89	-	845.46	8 - 10 ft	8.44 ft	1801346401	Not Excavated						
Northern Athletic Field	S225	SSHS-IRM5A2-S225	3/14/2022	-	856.93	-	847.48	8 - 10 ft	9.44 ft	1801351301	Not Excavated						
Northern Athletic Field	S224	SSHS-IRM5A2-S224	3/14/2022	-	855.47	-	847.11	8 - 10 ft	8.36 ft	1801351301	Not Excavated						
Northern Athletic Field	S581	SSHS-IRM5A2-S581	3/14/2022	-	854.73	-	844.99	8 - 10 ft	9.74 ft	1801351301	Not Excavated						
Northern Athletic Field	MS-SLT-B4	SSHS-ISMP-MS-SLT-B4	3/14/2022	-	856.68	-	848.02	8 - 10 ft	8.66 ft	1801351292	Not Excavated						
Northern Athletic Field	MS-SLT-B5	SSHS-ISMP-MS-SLT-B5	3/15/2022	-	856.78	-	848.51	8 - 10 ft	8.27 ft	1801352021	Not Excavated						
Northern Athletic Field	S289	SSHS-IRM5A2-DUP54	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated						
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354282	Not Excavated						
Northern Athletic Field	S288	SSHS-IRM5A2-S288	3/18/2022	-	853.07	-	843.95	8 - 10 ft	9.12 ft	1801354283	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	S289	SSHS-IRM5A2-S289	3/18/2022	-	853.38	-	843.49	8 - 10 ft	9.89 ft	1801354282	Not Excavated						
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354701	Not Excavated						
Northern Athletic Field	S577	SSHS-IRM5A2-S577	3/19/2022	-	853.66	-	843.70	8 - 10 ft	9.96 ft	1801354702	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	S578	SSHS-IRM5A2-S578	3/19/2022	-	852.74	-	844.03	8 - 10 ft	8.71 ft	1801354701	Not Excavated						
Northern Athletic Field	S580	SSHS-IRM5A2-S580	3/19/2022	-	853.40	-	845.08	8 - 10 ft	8.31 ft	1801354701	Not Excavated						
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354701	Not Excavated						
Northern Athletic Field	S218	SSHS-IRM5A2-S218	3/19/2022	-	853.54	-	845.21	8 - 10 ft	8.33 ft	1801354702	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	S217	SSHS-IRM5A2-S217	3/19/2022	-	853.41	-	844.95	8 - 10 ft	8.46 ft	1801354701	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated	< 120 U								
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354872	Not Excavated				< 0.055 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.055 U	< 0.034 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated	< 120 U								
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated	< 130 U								
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated	< 110 U								
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359742	Not Excavated				< 0.054 U	< 0.043 U	0.24 B	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated	< 120 U								
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated	< 120 U								
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated	< 110 U								
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371273	Not Excavated				< 0.051 U	< 0.040 U	0.081 J	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated		< 34 U							
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated		< 30 U							
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated		< 33 U							
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated		< 33 U							
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378344	Not Excavated				< 0.056 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.056 U	< 0.035 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated		< 33 U							
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated		< 34 U							
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated		< 47 U							
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated		< 33 U							
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated		< 31 U							
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated		< 32 U							
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384662	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated		< 31 U							
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated		< 33 U							
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384662	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated		< 34 U							
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated	< 750 U								
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated			< 110 U						
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated		< 35 U							
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394642	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated		< 32 U							
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated		< 34 U							
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated		< 34 U							
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated		< 34 U							
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated		< 32 U							
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394642	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated		< 29 U							
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated		< 32 U							
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated		< 34 U							
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated		< 32 U							
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394642	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated		< 33 U							
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated		< 31 U							
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated		< 31 U							
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated		< 31 U							
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated		< 32 U							
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated		< 36 U							
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395464	Not Excavated				< 0.057 U	< 0.045 U	0.057 J	< 0.062 U	< 0.057 U	< 0.036 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated		< 32 U							
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated	< 430 U								
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated		< 32 U							
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated		< 31 U							
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated		< 36 U							
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395464	Not Excavated				< 0.058 U	< 0.046 U	< 0.055 U	< 0.063 U	< 0.058 U	< 0.036 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated		< 32 U							
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated		< 32 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated									
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354872	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.060 U	< 0.047 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated									
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated									
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated									
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359742	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	0.32	< 0.060 U	0.13 J
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated									
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated									
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated									
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371273	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated									
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated									
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated									
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated									
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378344	Not Excavated	< 0.057 U	< 0.044 U	< 0.034 U	< 0.036 U	< 0.026 U	< 0.038 U	< 0.050 U	< 0.061 U	< 0.048 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated									
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated									
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated									
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384662	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated									
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384662	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.060 U	< 0.046 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated									
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated									
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated									
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated									
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394642	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394642	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394642	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	0.054 J	< 0.048 U	< 0.059 U	< 0.046 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated									
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395464	Not Excavated	< 0.059 U	< 0.045 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.040 U	< 0.051 U	0.067 J	< 0.049 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated									
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated									
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395464	Not Excavated	< 0.059 U	< 0.046 U	< 0.035 U	< 0.037 U	< 0.026 U	< 0.040 U	0.062 J	< 0.064 U	< 0.049 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354871	Not Excavated						
Northern Athletic Field	S174-BOT4	SSHS-IRM5A2-S174-BOT4	3/20/2022	-	855.06	-	846.09	8 - 10 ft	8.97 ft	1801354872	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	0.069 BJ	< 0.026 U
Northern Athletic Field	S174-BOT5	SSHS-IRM5A2-S174-BOT5	3/20/2022	-	855.67	-	846.33	8 - 10 ft	9.35 ft	1801354871	Not Excavated						
Northern Athletic Field	S174-S9	SSHS-IRM5A2-S174-S9	3/20/2022	-	857.46	-	847.68	8 - 10 ft	9.78 ft	1801354871	Not Excavated						
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359741	Not Excavated						
Northern Athletic Field	B593-BOT1	SSHS-IRM5A2-B593-BOT1	3/30/2022	-	856.91	-	847.49	8 - 10 ft	9.42 ft	1801359742	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	B593-S2	SSHS-IRM5A2-B593-S2	3/30/2022	-	856.89	-	848.68	8 - 10 ft	8.21 ft	1801359741	Not Excavated						
Northern Athletic Field	B593-S1	SSHS-IRM5A2-B593-S1	3/30/2022	-	856.83	-	848.59	8 - 10 ft	8.24 ft	1801359741	Not Excavated						
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-DUP66	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-S8	SSHS-IRM5A2-A5-V1-S8	4/25/2022	-	855.55	-	846.02	8 - 10 ft	9.53 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-S6	SSHS-IRM5A2-A5-V1-S6	4/25/2022	-	855.65	-	846.68	8 - 10 ft	8.97 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371272	Not Excavated						
Northern Athletic Field	A5-V1-S10	SSHS-IRM5A2-A5-V1-S10	4/25/2022	-	855.83	-	846.69	8 - 10 ft	9.14 ft	1801371273	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A5-V1-S18	SSHS-IRM5A2-A5-V1-S18	5/9/2022	-	856.18	-	847.11	8 - 10 ft	9.06 ft	1801378342	Not Excavated						
Northern Athletic Field	A5-V1-BOT3	SSHS-IRM5A2-A5-V1-BOT3	5/9/2022	-	856.17	-	846.74	8 - 10 ft	9.44 ft	1801378342	Not Excavated						
Northern Athletic Field	PIPE5-BOT8	SSHS-IRM5A2-PIPE5-BOT8	5/9/2022	-	855.53	-	846.24	8 - 10 ft	9.29 ft	1801378343	Not Excavated						
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378343	Not Excavated						
Northern Athletic Field	PIPE5-S16	SSHS-IRM5A2-PIPE5-S16	5/9/2022	-	855.70	-	847.59	8 - 10 ft	8.11 ft	1801378344	Not Excavated	< 0.043 U	< 0.024 U	< 0.049 U	< 0.041 U	< 0.031 U	< 0.027 U
Northern Athletic Field	PIPE5-BOT7	SSHS-IRM5A2-PIPE5-BOT7	5/9/2022	-	855.45	-	846.94	8 - 10 ft	8.51 ft	1801378343	Not Excavated						
Northern Athletic Field	PIPE5-BOT6	SSHS-IRM5A2-PIPE5-BOT6	5/9/2022	-	855.53	-	847.05	8 - 10 ft	8.48 ft	1801378343	Not Excavated						
Northern Athletic Field	A3-FIS-LAT1	SSHS-IRM5A2-FIS-LAT1	5/10/2022	-	856.53	-	848.02	8 - 10 ft	8.51 ft	1801379131	Not Excavated						
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-DUP99	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-BOT11	SSHS-IRM5A2-PIPE5-BOT11	5/20/2022	-	855.61	-	847.06	8 - 10 ft	8.55 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-S22	SSHS-IRM5A2-PIPE5-S22	5/20/2022	-	855.62	-	847.51	8 - 10 ft	8.11 ft	1801384662	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	PIPE5-BOT10	SSHS-IRM5A2-PIPE5-BOT10	5/20/2022	-	855.67	-	846.91	8 - 10 ft	8.76 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384661	Not Excavated						
Northern Athletic Field	PIPE5-BOT9	SSHS-IRM5A2-PIPE-5-BOT9	5/20/2022	-	855.71	-	847.12	8 - 10 ft	8.58 ft	1801384662	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	PIPE5-S20	SSHS-IRM5A2-PIPE5-S20	5/20/2022	-	855.75	-	847.61	8 - 10 ft	8.14 ft	1801384661	Not Excavated						
Northern Athletic Field	FISLATSW	SSHS-IRM5A2-FISLATSW	6/1/2022	-	856.99	-	848.44	8 - 10 ft	8.55 ft	1801389471	Not Excavated						
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-8-10	6/4/2022	856.18	856.99	0.81	-	8 - 10 ft	8.81-10.81 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-13_14	SSHS-DW-13_14-SUB-8-10	6/4/2022	857.21	855.60	-1.61	-	8 - 10 ft	6.39-8.39 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-8-10	6/4/2022	856.60	856.86	0.26	-	8 - 10 ft	8.26-10.26 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-8-10	6/4/2022	856.27	856.38	0.11	-	8 - 10 ft	8.11-10.11 ft	180-139185-1	Not Excavated						
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-8-10	6/4/2022	856.61	857.29	0.68	-	8 - 10 ft	8.68-10.68 ft	180-139185-1	Not Excavated						
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S804	SSHS-IRM5A2-DUP105	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394642	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A4-S800	SSHS-IRM5A2-A4-S800	6/9/2022	-	857.70	-	849.04	8 - 10 ft	8.66 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S801	SSHS-IRM5A2-A4-S801	6/9/2022	-	857.90	-	849.42	8 - 10 ft	8.48 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S802	SSHS-IRM5A2-A4-S802	6/9/2022	-	857.82	-	849.05	8 - 10 ft	8.77 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S803	SSHS-IRM5A2-A4-S803	6/9/2022	-	857.77	-	849.05	8 - 10 ft	8.72 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S804	SSHS-IRM5A2-A4-S804	6/9/2022	-	857.53	-	849.03	8 - 10 ft	8.5 ft	1801394642	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	A4-S805	SSHS-IRM5A2-A4-S805	6/9/2022	-	857.56	-	849.38	8 - 10 ft	8.19 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S806	SSHS-IRM5A2-A4-S806	6/9/2022	-	857.48	-	849.18	8 - 10 ft	8.31 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S807	SSHS-IRM5A2-A4-S807	6/9/2022	-	856.96	-	848.67	8 - 10 ft	8.29 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-S808	SSHS-IRM5A2-A4-S808	6/9/2022	-	857.02	-	848.81	8 - 10 ft	8.21 ft	1801394642	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A4-S809	SSHS-IRM5A2-A4-S809	6/9/2022	-	857.06	-	848.67	8 - 10 ft	8.4 ft	1801394641	Not Excavated						
Northern Athletic Field	A4-B808	SSHS-IRM5A2-DUP108	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-DUP109	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-B802	SSHS-IRM5A2-A4-B802	6/10/2022	-	857.13	-	848.29	8 - 10 ft	8.84 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-B803	SSHS-IRM5A2-A4-B803	6/10/2022	-	857.36	-	848.56	8 - 10 ft	8.8 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-S813	SSHS-IRM5A2-A4-S813	6/10/2022	-	856.80	-	848.53	8 - 10 ft	8.28 ft	1801395464	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.028 U
Northern Athletic Field	A4-B807	SSHS-IRM5A2-A4-B807	6/10/2022	-	856.69	-	848.12	8 - 10 ft	8.57 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-B808	SSHS-IRM5A2-A4-B808	6/10/2022	-	857.00	-	848.03	8 - 10 ft	8.97 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-B810	SSHS-IRM5A2-A4-B810	6/10/2022	-	857.66	-	848.76	8 - 10 ft	8.91 ft	1801395463	Not Excavated						
Northern Athletic Field	A4-B811	SSHS-IRM5A2-A4-B811	6/10/2022	-	857.38	-	848.29	8 - 10 ft	9.1 ft	1801395463	Not Excavated						
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-B1	SSHS-IRM5A2-A4-FIS-B1	6/10/2022	-	856.98	-	847.30	8 - 10 ft	9.67 ft	1801395464	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.042 U	< 0.032 U	< 0.028 U
Northern Athletic Field	A4-FIS-S1	SSHS-IRM5A2-A4-FIS-S1	6/10/2022	-	856.99	-	847.45	8 - 10 ft	9.54 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-S2	SSHS-IRM5A2-A4-FIS-S2	6/10/2022	-	856.99	-	847.52	8 - 10 ft	9.47 ft	1801395462	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated		< 32 U							
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated		< 31 U							
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395464	Not Excavated				< 0.050 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated		< 31 U							
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated		< 33 U							
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated		< 31 U							
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated		< 30 U							
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated		< 32 U							
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395464	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated		< 33 U							
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395464	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated		< 31 U							
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395464	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated	< 130 U								
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated	< 110 U								
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated	< 120 U								
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395783	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated		< 46 U							
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395973	Not Excavated				< 0.67 U	< 0.53 U	< 0.64 U	< 0.73 U	< 0.67 U	< 0.42 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated		< 33 U							
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated		< 34 U							
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396812	Not Excavated				< 0.046 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396812	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated		< 36 U							
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396812	Not Excavated				< 0.057 U	< 0.045 U	0.80	< 0.062 U	< 0.057 U	< 0.035 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated		< 33 U							
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397522	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated		< 31 U							
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated	< 120 U								
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated	< 120 U								
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated	< 370 U								
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated	< 120 U								
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated	< 360 U								
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated	< 110 U								
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated	< 100 U								
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398273	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395464	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.050 J	< 0.055 U	< 0.042 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated									
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated									
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395464	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated									
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395464	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	0.055 J	< 0.059 U	< 0.046 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated									
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395464	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated									
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated									
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated									
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395783	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395973	Not Excavated	< 0.69 U	< 0.53 U	< 0.41 U	< 0.43 U	< 0.31 U	< 0.46 U	< 0.60 U	< 0.74 U	< 0.57 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated									
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated									
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396812	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396812	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated									
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396812	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.037 U	< 0.026 U	< 0.039 U	< 0.051 U	< 0.063 U	0.39
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397522	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated									
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated									
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated									
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398273	Not Excavated	< 0.050 U	< 0.039 U	< 0.029 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A4-FIS-B2	SSHS-IRM5A2-A4-FIS-B2	6/10/2022	-	857.46	-	847.73	8 - 10 ft	9.73 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-S3	SSHS-IRM5A2-A4-FIS-S3	6/10/2022	-	857.46	-	847.96	8 - 10 ft	9.5 ft	1801395464	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	B1618-BOT	SSHS-IRM5A2-B1618-BOT	6/10/2022	-	857.38	-	848.71	8 - 10 ft	8.67 ft	1801395461	Not Excavated						
Northern Athletic Field	CP2-S21	SSHS-IRM5A2-CP2-S21	6/10/2022	-	856.64	-	847.10	8 - 10 ft	9.54 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-B800	SSHS-IRM5A2-A4-B800	6/10/2022	-	856.95	-	847.98	8 - 10 ft	8.98 ft	1801395461	Not Excavated						
Northern Athletic Field	CP2-S7-BOT	SSHS-IRM5A2-CP2-S7-BOT	6/10/2022	-	856.75	-	846.77	8 - 10 ft	9.99 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-B801	SSHS-IRM5A2-A4-B801	6/10/2022	-	857.43	-	848.98	8 - 10 ft	8.45 ft	1801395464	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395461	Not Excavated						
Northern Athletic Field	A4-B804	SSHS-IRM5A2-A4-B804	6/10/2022	-	856.99	-	848.29	8 - 10 ft	8.7 ft	1801395464	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395462	Not Excavated						
Northern Athletic Field	A4-FIS-S5	SSHS-IRM5A2-A4-FIS-S5	6/10/2022	-	857.66	-	847.81	8 - 10 ft	9.85 ft	1801395464	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A4-FIS-S6	SSHS-IRM5A2-A4-FIS-S6	6/10/2022	-	857.56	-	848.03	8 - 10 ft	9.53 ft	1801395462	Not Excavated						
Northern Athletic Field	FISR-S5	SSHS-IRM5A2-FISR-S5	6/11/2022	-	854.24	-	845.95	8 - 10 ft	8.29 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-S7	SSHS-IRM5A2-FISR-S7	6/11/2022	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801395781	Not Excavated						
Northern Athletic Field	FISR-BOT5	SSHS-IRM5A2-FISR-BOT5	6/11/2022	-	856.80	-	846.80	8 - 10 ft	10 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S107	SSHS-IRM5A2-A4-S107	6/11/2022	-	857.45	-	847.39	8 - 10 ft	10.06 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S108	SSHS-IRM5A2-A4-S108	6/11/2022	-	857.41	-	847.64	8 - 10 ft	9.77 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395781	Not Excavated						
Northern Athletic Field	A4-S109	SSHS-IRM5A2-A4-S109	6/11/2022	-	857.42	-	848.03	8 - 10 ft	9.39 ft	1801395783	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	FISR-S11	SSHS-IRM5A2-FISR-S11	6/13/2022	-	854.76	-	844.74	8 - 10 ft	10.02 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S15	SSHS-IRM5A2-FISR-S15	6/13/2022	-	854.87	-	845.41	8 - 10 ft	9.46 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S18	SSHS-IRM5A2-FISR-S18	6/13/2022	-	855.09	-	846.85	8 - 10 ft	8.24 ft	1801395973	Not Excavated	< 0.52 U	< 0.29 U	< 0.59 U	< 0.49 U	< 0.38 U	< 0.32 U
Northern Athletic Field	FISR-S19	SSHS-IRM5A2-FISR-S19	6/13/2022	-	855.02	-	845.12	8 - 10 ft	9.9 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S27	SSHS-IRM5A2-FISR-S27	6/13/2022	-	855.07	-	845.39	8 - 10 ft	9.68 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S31	SSHS-IRM5A2-FISR-S31	6/13/2022	-	855.21	-	845.57	8 - 10 ft	9.63 ft	1801395971	Not Excavated						
Northern Athletic Field	FISR-S39	SSHS-IRM5A2-FISR-S39	6/13/2022	-	855.27	-	845.37	8 - 10 ft	9.9 ft	1801395972	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-DUP121	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-DUP122	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated						
Northern Athletic Field	FISR-S43	SSHS-IRM5A2-FISR-S43	6/14/2022	-	855.14	-	845.59	8 - 10 ft	9.55 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S1	SSHS-IRM5A2-A3-FISRLAT1-S1	6/14/2022	-	855.27	-	845.68	8 - 10 ft	9.59 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S2	SSHS-IRM5A2-A3-FISRLAT1-S2	6/14/2022	-	855.27	-	845.73	8 - 10 ft	9.54 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S3	SSHS-IRM5A2-A3-FISRLAT1-S3	6/14/2022	-	855.53	-	845.73	8 - 10 ft	9.8 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S4	SSHS-IRM5A2-A3-FISRLAT1-S4	6/14/2022	-	855.52	-	845.90	8 - 10 ft	9.62 ft	1801396812	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A3-FISRLAT1-S5	SSHS-IRM5A2-A3-FISRLAT1-S5	6/14/2022	-	855.88	-	846.26	8 - 10 ft	9.61 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S6	SSHS-IRM5A2-A3-FISRLAT1-S6	6/14/2022	-	855.85	-	846.20	8 - 10 ft	9.65 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S7	SSHS-IRM5A2-A3-FISRLAT1-S7	6/14/2022	-	856.28	-	846.81	8 - 10 ft	9.48 ft	1801396812	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-FISRLAT1-S8	SSHS-IRM5A2-A3-FISRLAT1-S8	6/14/2022	-	856.25	-	846.90	8 - 10 ft	9.35 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S9	SSHS-IRM5A2-A3-FISRLAT1-S9	6/14/2022	-	856.60	-	847.29	8 - 10 ft	9.32 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-S10	SSHS-IRM5A2-A3-FISRLAT1-S10	6/14/2022	-	856.60	-	847.33	8 - 10 ft	9.26 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-B2	SSHS-IRM5A2-A3-FISRLAT1-B2	6/14/2022	-	855.52	-	845.53	8 - 10 ft	10 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-B4	SSHS-IRM5A2-A3-FISRLAT1-B4	6/14/2022	-	856.28	-	846.38	8 - 10 ft	9.89 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396811	Not Excavated						
Northern Athletic Field	A3-FISRLAT1-B5	SSHS-IRM5A2-A3-FISRLAT1-B5	6/14/2022	-	856.60	-	846.88	8 - 10 ft	9.72 ft	1801396812	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-DUP-123	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S1	SSHS-IRM5A2-A3-DEBRIS-S1	6/15/2022	-	856.47	-	847.33	8 - 10 ft	9.14 ft	1801397522	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-DEBRIS-S3	SSHS-IRM5A2-A3-DEBRIS-S3	6/15/2022	-	856.36	-	846.71	8 - 10 ft	9.64 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S5	SSHS-IRM5A2-A3-DEBRIS-S5	6/15/2022	-	856.01	-	846.30	8 - 10 ft	9.71 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S7	SSHS-IRM5A2-A3-DEBRIS-S7	6/15/2022	-	856.05	-	846.36	8 - 10 ft	9.69 ft	1801397521	Not Excavated						
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-DUP126	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-DUP125	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398272	Not Excavated						
Northern Athletic Field	A3-S601	SSHS-IRM5A2-A3-S601	6/16/2022	-	855.56	-	847.52	8 - 10 ft	8.03 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B601	SSHS-IRM5A2-A3-B601	6/16/2022	-	856.39	-	847.98	8 - 10 ft	8.41 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B604	SSHS-IRM5A2-A3-B604	6/16/2022	-	855.13	-	846.61	8 - 10 ft	8.52 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B605	SSHS-IRM5A2-A3-B605	6/16/2022	-	855.54	-	847.33	8 - 10 ft	8.2 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B606	SSHS-IRM5A2-A3-B606	6/16/2022	-	855.87	-	847.77	8 - 10 ft	8.11 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398271	Not Excavated						
Northern Athletic Field	A3-B607	SSHS-IRM5A2-A3-B607	6/16/2022	-	856.08	-	847.75	8 - 10 ft	8.33 ft	1801398273	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated		< 160 U							
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated		< 30 U							
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated		< 32 U							
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399473	Not Excavated				< 0.052 U	< 0.041 U	0.34	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399473	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated		< 33 U							
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated		< 36 U							
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated		< 32 U							
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated			< 120 U						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated			< 110 U						
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400222	Not Excavated				< 0.19 U	< 0.15 U	< 0.18 U	< 0.21 U	< 0.19 U	< 0.12 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated		< 34 U							
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400222	Not Excavated				< 0.052 U	< 0.041 U	0.35	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400222	Not Excavated				< 0.051 U	< 0.041 U	0.069 J	< 0.056 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated		< 35 U							
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400222	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated		< 330 U							
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated		< 34 U							
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400212	Not Excavated				< 0.054 U	< 0.043 UT	2.1 T	< 0.058 U	< 0.054 UT	< 0.034 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400212	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated		< 33 U							
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated		< 30 U							
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400212	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated		< 31 U							
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated		< 32 U							
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated		< 32 U							
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 430 U								
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated	< 100 U								
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated	< 210 U								
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated	< 110 U								

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399473	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.18 J	0.18 J	0.15 J
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399473	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated									
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated									
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated									
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400222	Not Excavated	< 0.20 U	< 0.15 U	< 0.12 U	< 0.12 U	< 0.088 U	< 0.13 U	< 0.17 U	< 0.21 U	< 0.16 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400222	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.036 U	0.19 J	< 0.057 U	< 0.044 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400222	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.024 U	< 0.035 U	< 0.046 U	< 0.057 U	< 0.044 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400222	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400212	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 UT	< 0.025 UT	< 0.037 U	< 0.048 U	< 0.059 U	0.55
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400212	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	0.13 J	< 0.056 U	0.050 J
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400212	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	0.086 J
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated									
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated									
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-DUP130	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-DUP129	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-DEBRIS-S9	SSHS-IRM5A2-A3-DEBRIS-S9	6/17/2022	-	856.10	-	846.35	8 - 10 ft	9.75 ft	1801399473	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-DEBRIS-S11	SSHS-IRM5A2-A3-DEBRIS-S11	6/17/2022	-	856.47	-	847.66	8 - 10 ft	8.81 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S1	SSHS-IRM5A2-A3-FISLAT2-S1	6/17/2022	-	855.26	-	845.74	8 - 10 ft	9.52 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S2	SSHS-IRM5A2-A3-FISLAT2-S2	6/17/2022	-	855.24	-	845.68	8 - 10 ft	9.57 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S3	SSHS-IRM5A2-A3-FISLAT2-S3	6/17/2022	-	855.48	-	845.99	8 - 10 ft	9.49 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S4	SSHS-IRM5A2-A3-FISLAT2-S4	6/17/2022	-	855.49	-	846.02	8 - 10 ft	9.47 ft	1801399473	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	A3-FISLAT2-S5	SSHS-IRM5A2-A3-FISLAT2-S5	6/17/2022	-	855.82	-	846.25	8 - 10 ft	9.57 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S6	SSHS-IRM5A2-A3-FISLAT2-S6	6/17/2022	-	855.81	-	846.19	8 - 10 ft	9.61 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S7	SSHS-IRM5A2-A3-FISLAT2-S7	6/17/2022	-	856.14	-	846.67	8 - 10 ft	9.46 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B4	SSHS-IRM5A2-A3-FISLAT2-B4	6/17/2022	-	856.18	-	846.38	8 - 10 ft	9.8 ft	1801399471	Not Excavated						
Northern Athletic Field	A3-DB-BOT	SSHS-IRM5A2-A3-DB-BOT	6/17/2022	-	853.00	-	843.83	8 - 10 ft	9.17 ft	1801399472	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-DUP135	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400241	Not Excavated						
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-8-10	6/20/2022	856.38	856.44	0.06	-	8 - 10 ft	8.06-10.06 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-8-10	6/20/2022	856.66	856.67	0.01	-	8 - 10 ft	8.01-10.01 ft	180-140136-1	Not Excavated						
Northern Athletic Field	SSHS-DW-3B	SSHS-DW-3B-SUB-8-10	6/20/2022	856.60	856.56	-0.04	-	8 - 10 ft	7.96-9.96 ft	180-140136-1	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S11	SSHS-IRM5A2-A3-FISLAT1-S11	6/20/2022	-	856.88	-	847.68	8 - 10 ft	9.2 ft	1801400222	Not Excavated	< 0.15 U	< 0.084 U	< 0.17 U	< 0.14 U	< 0.11 U	< 0.092 U
Northern Athletic Field	A3-FISLAT1-S12	SSHS-IRM5A2-A3-FISLAT1-S12	6/20/2022	-	856.86	-	847.63	8 - 10 ft	9.23 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S13	SSHS-IRM5A2-A3-FISLAT1-S13	6/20/2022	-	857.34	-	848.29	8 - 10 ft	9.05 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S14	SSHS-IRM5A2-A3-FISLAT1-S14	6/20/2022	-	857.29	-	848.70	8 - 10 ft	8.59 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S15	SSHS-IRM5A2-A3-FISLAT1-S15	6/20/2022	-	857.81	-	849.43	8 - 10 ft	8.38 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-S16	SSHS-IRM5A2-A3-FISLAT1-S16	6/20/2022	-	857.65	-	849.42	8 - 10 ft	8.22 ft	1801400222	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-FISLAT1-S17	SSHS-IRM5A2-A3-FISLAT1-S17	6/20/2022	-	857.69	-	849.12	8 - 10 ft	8.57 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-B6	SSHS-IRM5A2-A3-FISLAT1-B6	6/20/2022	-	856.89	-	846.84	8 - 10 ft	10.05 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-B7	SSHS-IRM5A2-A3-FISLAT1-B7	6/20/2022	-	857.31	-	847.70	8 - 10 ft	9.61 ft	1801400222	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A3-FISLAT1-B8	SSHS-IRM5A2-A3-FISLAT1-B8	6/20/2022	-	857.64	-	848.75	8 - 10 ft	8.89 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT1-B9	SSHS-IRM5A2-A3-FISLAT1-B9	6/20/2022	-	857.72	-	848.83	8 - 10 ft	8.89 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT3-S1	SSHS-IRM5A2-A3-FISLAT3-S1	6/20/2022	-	857.23	-	848.17	8 - 10 ft	9.05 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT3-S2	SSHS-IRM5A2-A3-FISLAT3-S2	6/20/2022	-	857.12	-	848.40	8 - 10 ft	8.72 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT3-S3	SSHS-IRM5A2-A3-FISLAT3-S3	6/20/2022	-	856.96	-	848.30	8 - 10 ft	8.66 ft	1801400222	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A3-FISLAT3-S4	SSHS-IRM5A2-A3-FISLAT3-S4	6/20/2022	-	856.95	-	848.10	8 - 10 ft	8.85 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT3-B1	SSHS-IRM5A2-A3-FISLAT3-B1	6/20/2022	-	857.21	-	848.04	8 - 10 ft	9.18 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT3-B2	SSHS-IRM5A2-A3-FISLAT3-B2	6/20/2022	-	856.94	-	847.58	8 - 10 ft	9.36 ft	1801400221	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S8	SSHS-IRM5A2-A3-FISLAT2-S8	6/20/2022	-	856.54	-	847.55	8 - 10 ft	8.99 ft	1801400212	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A3-FISLAT2-S10	SSHS-IRM5A2-A3-FISLAT2-S10	6/20/2022	-	856.54	-	847.41	8 - 10 ft	9.13 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S12	SSHS-IRM5A2-A3-FISLAT2-S12	6/20/2022	-	856.90	-	848.12	8 - 10 ft	8.78 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S13	SSHS-IRM5A2-A3-FISLAT2-S13	6/20/2022	-	856.90	-	847.00	8 - 10 ft	9.9 ft	1801400212	Not Excavated	< 0.039 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	A3-FISLAT2-S14	SSHS-IRM5A2-A3-FISLAT2-S14	6/20/2022	-	856.89	-	848.03	8 - 10 ft	8.87 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S15	SSHS-IRM5A2-A3-FISLAT2-S15	6/20/2022	-	856.89	-	846.87	8 - 10 ft	10.02 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S16	SSHS-IRM5A2-A3-FISLAT2-S16	6/20/2022	-	857.36	-	848.22	8 - 10 ft	9.14 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S18	SSHS-IRM5A2-A3-FISLAT2-S18	6/20/2022	-	857.41	-	848.54	8 - 10 ft	8.87 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S20	SSHS-IRM5A2-A3-FISLAT2-S20	6/20/2022	-	857.79	-	848.97	8 - 10 ft	8.82 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S21	SSHS-IRM5A2-A3-FISLAT2-S21	6/20/2022	-	857.63	-	849.24	8 - 10 ft	8.39 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S22	SSHS-IRM5A2-A3-FISLAT2-S22	6/20/2022	-	857.63	-	848.06	8 - 10 ft	9.56 ft	1801400212	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A3-FISLAT2-S23	SSHS-IRM5A2-A3-FISLAT2-S23	6/20/2022	-	857.71	-	849.22	8 - 10 ft	8.49 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-S24	SSHS-IRM5A2-A3-FISLAT2-S24	6/20/2022	-	857.71	-	847.73	8 - 10 ft	9.98 ft	1801400211	Not Excavated						
Northern Athletic Field	A3-FISLAT2-B8	SSHS-IRM5A2-A3-FISLAT2-B8	6/20/2022	-	857.79	-	848.43	8 - 10 ft	9.36 ft	1801400231	Not Excavated						
Northern Athletic Field	A3-B640	SSHS-IRM5A2-DUP139	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B634	SSHS-IRM5A2-A3-B634	6/21/2022	-	855.77	-	847.48	8 - 10 ft	8.29 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B635	SSHS-IRM5A2-A3-B635	6/21/2022	-	856.06	-	847.38	8 - 10 ft	8.67 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B640	SSHS-IRM5A2-A3-B640	6/21/2022	-	855.88	-	847.40	8 - 10 ft	8.48 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B641	SSHS-IRM5A2-A3-B641	6/21/2022	-	855.69	-	847.44	8 - 10 ft	8.25 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400921	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400922	Not Excavated				< 0.048 U	< 0.038 U	0.046 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated	< 110 U								
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated	< 100 U								
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated	< 340 U								
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated	< 320 U								
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated	< 100 U								
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401822	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated	< 110 U								
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated	< 110 U								
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated	< 100 U								
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406773	Not Excavated				< 0.047 U	< 0.037 U	0.063 J	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated		< 32 U							
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410572	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated		< 30 U							
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated		< 32 U							
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411032	Not Excavated				< 0.047 U	< 0.037 U	0.054 J	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated		< 29 U							
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated		< 29 U							
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411032	Not Excavated				< 0.048 U	< 0.038 U	0.12 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated		< 30 U							
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated		< 29 U							
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411032	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated		< 31 U							
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated		< 32 U							
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411032	Not Excavated				< 0.052 U	< 0.041 U	0.064 J	< 0.056 U	< 0.052 U	< 0.033 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418912	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated		< 32 U							
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418912	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated		< 31 U							
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated		< 30 U							
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated		< 29 U							
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated		< 32 U							
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated		< 31 U							
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated		< 31 U							
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated		< 32 U							
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated		< 30 U							
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426152	Not Excavated				< 0.045 U	< 0.035 U	< 0.043 U	< 0.049 U	< 0.045 U	< 0.028 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated		< 31 U							
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated		< 31 U							
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426152	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated		< 29 U							
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated		< 29 U							
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated		< 31 U							
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated		< 29 U							
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated		< 30 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400922	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.12 J	< 0.053 U	< 0.041 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated									
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated									
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated									
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401822	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.041 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated									
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated									
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406773	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410572	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated									
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated									
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411032	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.047 J	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated									
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411032	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411032	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated									
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411032	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.061 J	0.058 J	< 0.045 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418912	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated									
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418912	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated									
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated									
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated									
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated									
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated									
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426152	Not Excavated	< 0.046 U	< 0.035 U	< 0.027 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.040 U	< 0.049 U	< 0.038 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426152	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated									
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated									
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated									

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	11H,11H,2H,2H-Perfluorodecane Sulfonate (8:2)	11H,11H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A3-B642	SSHS-IRM5A2-A3-B642	6/21/2022	-	855.41	-	846.84	8 - 10 ft	8.56 ft	1801400922	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A3-B643	SSHS-IRM5A2-A3-B643	6/21/2022	-	855.38	-	846.70	8 - 10 ft	8.68 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B644	SSHS-IRM5A2-A3-B644	6/21/2022	-	855.64	-	847.38	8 - 10 ft	8.26 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B645	SSHS-IRM5A2-A3-B645	6/21/2022	-	855.33	-	846.93	8 - 10 ft	8.4 ft	1801400921	Not Excavated						
Northern Athletic Field	A3-B633	SSHS-IRM5A2-A3-B633	6/21/2022	-	856.04	-	847.98	8 - 10 ft	8.06 ft	1801400921	Not Excavated						
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401821	Not Excavated						
Northern Athletic Field	A4-S815	SSHS-IRM5A2-A4-S815	6/22/2022	-	857.53	-	849.37	8 - 10 ft	8.17 ft	1801401822	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-DUP145	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-BOT12	SSHS-IRM5A2-FISR-BOT12	6/30/2022	-	852.86	-	844.56	8 - 10 ft	8.3 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-BOT13	SSHS-IRM5A2-FISR-BOT13	6/30/2022	-	853.41	-	844.74	8 - 10 ft	8.67 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S70	SSHS-IRM5A2-FISR-S70	6/30/2022	-	854.63	-	845.65	8 - 10 ft	8.98 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S69	SSHS-IRM5A2-FISR-S69	6/30/2022	-	854.60	-	845.61	8 - 10 ft	8.99 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S64	SSHS-IRM5A2-FISR-S64	6/30/2022	-	854.16	-	845.77	8 - 10 ft	8.39 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-BOT14	SSHS-IRM5A2-FISR-BOT14	6/30/2022	-	854.00	-	844.58	8 - 10 ft	9.42 ft	1801406771	Not Excavated						
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406772	Not Excavated						
Northern Athletic Field	FISR-S63	SSHS-IRM5A2-FISR-S63	6/30/2022	-	853.90	-	845.60	8 - 10 ft	8.3 ft	1801406773	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S3	SSHS-IRM5A2-FL-WELL1-S3	7/8/2022	-	856.92	-	848.23	8 - 10 ft	8.7 ft	1801410572	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-WELL1-S6	SSHS-IRM5A2-FL-WELL1-S6	7/8/2022	-	856.88	-	848.62	8 - 10 ft	8.26 ft	1801410571	Not Excavated						
Northern Athletic Field	FL-WELL1-S9	SSHS-IRM5A2-FL-WELL1-S9	7/8/2022	-	856.90	-	848.77	8 - 10 ft	8.13 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-WELL1-B1	SSHS-IRM5A2-FL-WELL1-B1	7/8/2022	-	856.90	-	847.86	8 - 10 ft	9.03 ft	1801410581	Not Excavated						
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-DUP159	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411032	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-DUP158	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B1	SSHS-IRM5A2-FL-FISN-B1	7/11/2022	-	856.53	-	848.35	8 - 10 ft	8.18 ft	1801411061	Not Excavated						
Northern Athletic Field	FL-FISN-B2	SSHS-IRM5A2-FL-FISN-B2	7/11/2022	-	856.78	-	848.50	8 - 10 ft	8.28 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B4	SSHS-IRM5A2-FL-FISN-B4	7/11/2022	-	856.63	-	848.50	8 - 10 ft	8.13 ft	1801411032	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FL-FISN-B5	SSHS-IRM5A2-FL-FISN-B5	7/11/2022	-	856.69	-	848.67	8 - 10 ft	8.02 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B8	SSHS-IRM5A2-FL-FISN-B8	7/11/2022	-	856.86	-	848.86	8 - 10 ft	8 ft	1801411032	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FL-FISN-B9	SSHS-IRM5A2-FL-FISN-B9	7/11/2022	-	856.80	-	848.29	8 - 10 ft	8.5 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411031	Not Excavated						
Northern Athletic Field	FL-FISN-B10	SSHS-IRM5A2-FL-FISN-B10	7/11/2022	-	856.68	-	848.33	8 - 10 ft	8.35 ft	1801411032	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-DUP175	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418912	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	0.028 J	< 0.023 U
Northern Athletic Field	PIPE17-B1	SSHS-IRM5A2-FL-PIPE17-B1	7/25/2022	-	856.24	-	847.78	8 - 10 ft	8.46 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418911	Not Excavated						
Northern Athletic Field	PIPE17-B2	SSHS-IRM5A2-FL-PIPE17-B2	7/25/2022	-	856.44	-	847.98	8 - 10 ft	8.46 ft	1801418912	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FISC-B2	SSHS-IRM5A2-FISC-B2	7/28/2022	-	856.83	-	848.71	8 - 10 ft	8.12 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-B3	SSHS-IRM5A2-FISC-B3	7/28/2022	-	856.90	-	848.75	8 - 10 ft	8.15 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-B5	SSHS-IRM5A2-FISC-B5	7/28/2022	-	856.77	-	848.47	8 - 10 ft	8.29 ft	1801421221	Not Excavated						
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-DUP187	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated						
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-DUP185	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated						
Northern Athletic Field	FLDW1-S2	SSHS-ISMP-FLDW1-S2	8/8/2022	-	856.15	-	846.39	8 - 10 ft	9.76 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW1-S3	SSHS-ISMP-FLDW1-S3	8/8/2022	-	856.27	-	848.18	8 - 10 ft	8.09 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW1-S4	SSHS-ISMP-FLDW1-S4	8/8/2022	-	856.21	-	846.30	8 - 10 ft	9.91 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW2-S1	SSHS-ISMP-FLDW2-S1	8/8/2022	-	856.13	-	846.43	8 - 10 ft	9.7 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW2-S2	SSHS-ISMP-FLDW2-S2	8/8/2022	-	856.10	-	846.71	8 - 10 ft	9.39 ft	1801426141	Not Excavated						
Northern Athletic Field	FLDW2-B1	SSHS-ISMP-FLDW2-B1	8/8/2022	-	856.12	-	846.35	8 - 10 ft	9.76 ft	1801426141	Not Excavated						
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S800	SSHS-IRM5A2-FL-S800	8/8/2022	-	856.50	-	848.19	8 - 10 ft	8.32 ft	1801426152	Not Excavated	< 0.035 U	< 0.020 U	< 0.039 U	< 0.033 U	< 0.025 U	< 0.021 U
Northern Athletic Field	FL-S1002	SSHS-IRM5A2-FL-S1002	8/8/2022	-	855.94	-	846.80	8 - 10 ft	9.14 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1003	SSHS-IRM5A2-FL-S1003	8/8/2022	-	855.71	-	847.43	8 - 10 ft	8.28 ft	1801426152	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	FL-S1004	SSHS-IRM5A2-FL-S1004	8/8/2022	-	855.97	-	847.11	8 - 10 ft	8.86 ft	1801426151	Not Excavated						
Northern Athletic Field	FL-S1005	SSHS-IRM5A2-FL-S1005	8/8/2022	-	856.13	-	846.45	8 - 10 ft	9.68 ft	1801426151	Not Excavated						
Northern Athletic Field	FISC-S13	SSHS-IRM5A2-FISC-S13	8/8/2022	-	856.75	-	848.64	8 - 10 ft	8.11 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-S14	SSHS-IRM5A2-FISC-S14	8/8/2022	-	856.89	-	848.73	8 - 10 ft	8.16 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-S16	SSHS-IRM5A2-FISC-S16	8/8/2022	-	856.92	-	848.78	8 - 10 ft	8.13 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-S18	SSHS-IRM5A2-FISC-S18	8/8/2022	-	856.92	-	848.75	8 - 10 ft	8.17 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-B7	SSHS-IRM5A2-FISC-B7	8/8/2022	-	856.82	-	848.62	8 - 10 ft	8.2 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426161	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426162	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated		< 30 U							
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated		< 34 U							
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated		< 31 U							
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426162	Not Excavated				< 0.049 U	< 0.039 U	0.088 J	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated		< 35 U							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429592	Not Excavated				0.25 B	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429592	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated		< 31 U							
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429592	Not Excavated				0.12 BJ	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated		< 33 U							
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated		< 32 U							
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated		< 32 U							
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated		< 31 U							
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429592	Not Excavated				0.090 BJ	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated		< 30 U							
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated		< 32 U							
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429592	Not Excavated				< 0.050 U	< 0.039 U	0.052 J	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated		< 32 U							
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated		< 31 U							
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429592	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.047 U	< 0.029 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated		< 32 U							
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated		< 32 U							
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429592	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated		< 30 U							
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430702	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430702	Not Excavated				< 0.20 U	< 0.16 U	< 0.19 U	< 0.21 U	< 0.20 U	< 0.12 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated		< 33 U							
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430702	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated		< 32 U							
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430702	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated		< 31 U							
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430892	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated		< 31 U							
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated		< 31 U							
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated		< 34 U							
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated		< 33 U							
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated		< 33 U							
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated		< 31 U							
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433662	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated		< 31 U							
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated		< 33 U							
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated		< 32 U							
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435252	Not Excavated				< 0.050 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.050 U	< 0.031 U

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426162	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.022 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated									
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated									
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated									
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426162	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	0.080 J	< 0.054 U	< 0.042 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated									
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated									
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated									
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429592	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	0.069 J	< 0.041 U
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429592	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.053 J	< 0.051 U	< 0.040 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated									
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429592	Not Excavated	< 0.050 U	< 0.038 U	0.051 J	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	0.057 J	< 0.041 U
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429592	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated									
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated									
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429592	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.058 J	0.056 J	< 0.042 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated									
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated									
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated									
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429592	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.045 J	< 0.051 U	< 0.040 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429592	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.033 U	< 0.023 U	< 0.035 U	0.054 J	< 0.056 U	< 0.043 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated									
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated									
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430702	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430702	Not Excavated	< 0.20 U	< 0.16 U	< 0.12 U	< 0.13 U	< 0.090 U	< 0.14 U	< 0.18 U	< 0.22 U	< 0.17 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430702	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated									
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430702	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated									
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated									
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430892	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated									
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated									
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated									
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433662	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated									
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435252	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U

DRAFT

TABLE 6-3E
Subsurface Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	FISC-B8	SSHS-IRM5A2-FISC-B8	8/8/2022	-	856.83	-	848.75	8 - 10 ft	8.08 ft	1801426162	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	FISC-B9	SSHS-IRM5A2-FISC-B9	8/8/2022	-	856.73	-	848.72	8 - 10 ft	8.01 ft	1801426161	Not Excavated						
Northern Athletic Field	FISC-B10	SSHS-IRM5A2-FISC-B10	8/8/2022	-	856.68	-	848.60	8 - 10 ft	8.09 ft	1801426161	Not Excavated						
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426161	Not Excavated						
Northern Athletic Field	FL-CB2-BOT	SSHS-IRM5A2-FL-CB2-BOT	8/8/2022	-	856.73	-	848.69	8 - 10 ft	8.05 ft	1801426162	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	FL-DW3A-S3	SSHS-IRM5A2-FL-DW3A-S3	8/10/2022	-	856.59	-	846.72	8 - 10 ft	9.87 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S5	SSHS-IRM5A2-FL-DW3A-S5	8/10/2022	-	856.57	-	848.52	8 - 10 ft	8.06 ft	1801427631	Not Excavated						
Northern Athletic Field	FL-DW3A-S7	SSHS-IRM5A2-FL-DW3A-S7	8/10/2022	-	856.55	-	848.37	8 - 10 ft	8.18 ft	1801427631	Not Excavated						
Northern Athletic Field	FISR-S97	SSHS-IRM5A2-FISR-S97	8/13/2022	-	855.05	-	846.82	8 - 10 ft	8.22 ft	1801429561	Not Excavated						
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-DUP197	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429592	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	0.056 BJ
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-DUP198	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429592	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FISC-S22	SSHS-IRM5A2-FISC-S22	8/15/2022	-	856.54	-	847.42	8 - 10 ft	9.12 ft	1801429561	Not Excavated						
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-S23	SSHS-IRM5A2-FISC-S23	8/15/2022	-	856.62	-	848.45	8 - 10 ft	8.17 ft	1801429592	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	0.043 BJ
Northern Athletic Field	FISC-B12	SSHS-IRM5A2-FISC-B12	8/15/2022	-	856.42	-	848.29	8 - 10 ft	8.13 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-B13	SSHS-IRM5A2-FISC-B13	8/15/2022	-	856.58	-	847.45	8 - 10 ft	9.13 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-B14	SSHS-IRM5A2-FISC-B14	8/15/2022	-	856.66	-	847.68	8 - 10 ft	8.98 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-B15	SSHS-IRM5A2-FISC-B15	8/15/2022	-	856.96	-	848.20	8 - 10 ft	8.75 ft	1801429592	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	0.039 BJ
Northern Athletic Field	PIPE17-S12	SSHS-IRM5A2-PIPE17-S12	8/15/2022	-	856.55	-	848.24	8 - 10 ft	8.31 ft	1801429591	Not Excavated						
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429591	Not Excavated						
Northern Athletic Field	PIPE17-S13	SSHS-IRM5A2-PIPE17-S13	8/15/2022	-	856.57	-	848.36	8 - 10 ft	8.21 ft	1801429592	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	PIPE17-S14	SSHS-IRM5A2-PIPE17-S14	8/15/2022	-	856.60	-	848.43	8 - 10 ft	8.17 ft	1801429591	Not Excavated						
Northern Athletic Field	PIPE17-S15	SSHS-IRM5A2-PIPE17-S15	8/15/2022	-	856.42	-	848.23	8 - 10 ft	8.19 ft	1801429591	Not Excavated						
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429591	Not Excavated						
Northern Athletic Field	PIPE17-B3	SSHS-IRM5A2-PIPE17-B3	8/15/2022	-	856.57	-	848.06	8 - 10 ft	8.51 ft	1801429592	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	FISC-S25	SSHS-IRM5A2-FISC-S25	8/15/2022	-	856.56	-	848.51	8 - 10 ft	8.05 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-S26	SSHS-IRM5A2-FISC-S26	8/15/2022	-	856.78	-	848.26	8 - 10 ft	8.51 ft	1801429592	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FISC-S27	SSHS-IRM5A2-FISC-S27	8/15/2022	-	--	-	848.38	8 - 10 ft	8 - 10 ft	1801429591	Not Excavated						
Northern Athletic Field	FISC-S28	SSHS-IRM5A2-FISC-S28	8/15/2022	-	856.95	-	848.47	8 - 10 ft	8.48 ft	1801429591	Not Excavated						
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-DUP199	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430702	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	FLSP-S2	SSHS-IRM5A2-FLSP-S2	8/17/2022	-	856.35	-	846.50	8 - 10 ft	9.85 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S4	SSHS-IRM5A2-FLSP-S4	8/17/2022	-	856.54	-	848.08	8 - 10 ft	8.46 ft	1801430702	Not Excavated	< 0.15 U	< 0.086 U	< 0.17 U	< 0.14 U	< 0.11 U	< 0.095 U
Northern Athletic Field	FLSP-S5	SSHS-IRM5A2-FLSP-S5	8/17/2022	-	856.61	-	848.01	8 - 10 ft	8.61 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S9	SSHS-IRM5A2-FLSP-S9	8/17/2022	-	856.73	-	848.08	8 - 10 ft	8.65 ft	1801430702	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	FLSP-S12	SSHS-IRM5A2-FLSP-S12	8/17/2022	-	856.74	-	848.29	8 - 10 ft	8.44 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S13	SSHS-IRM5A2-FLSP-S13	8/17/2022	-	856.74	-	848.37	8 - 10 ft	8.38 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430701	Not Excavated						
Northern Athletic Field	FLSP-S14	SSHS-IRM5A2-FLSP-S14	8/17/2022	-	856.87	-	848.27	8 - 10 ft	8.6 ft	1801430702	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FLSP-B4	SSHS-IRM5A2-FLSP-B4	8/17/2022	-	856.84	-	848.00	8 - 10 ft	8.84 ft	1801430711	Not Excavated						
Northern Athletic Field	FLSP-B5	SSHS-IRM5A2-FLSP-B5	8/17/2022	-	856.74	-	847.59	8 - 10 ft	9.15 ft	1801430711	Not Excavated						
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-DUP194	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S76	SSHS-IRM5A2-FISR-S76	8/18/2022	-	854.84	-	845.01	8 - 10 ft	9.83 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-S78	SSHS-IRM5A2-FISR-S78	8/18/2022	-	854.89	-	846.66	8 - 10 ft	8.22 ft	1801430892	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	FISR-S79	SSHS-IRM5A2-FISR-S79	8/18/2022	-	854.89	-	844.88	8 - 10 ft	10.01 ft	1801430891	Not Excavated						
Northern Athletic Field	FISR-BOT16	SSHS-IRM5A2-FISR-BOT16	8/18/2022	-	854.79	-	844.90	8 - 10 ft	9.89 ft	1801430971	Not Excavated						
Northern Athletic Field	A6-S800	SSHS-IRM5A2-A6-S800	8/23/2022	-	857.51	-	848.45	8 - 10 ft	9.06 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S801	SSHS-IRM5A2-A6-S801	8/23/2022	-	857.77	-	848.38	8 - 10 ft	9.39 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S802	SSHS-IRM5A2-A6-S802	8/23/2022	-	857.62	-	848.32	8 - 10 ft	9.31 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433661	Not Excavated						
Northern Athletic Field	A6-S803	SSHS-IRM5A2-A6-S803	8/23/2022	-	857.48	-	848.39	8 - 10 ft	9.09 ft	1801433662	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	ST-S800	SSHS-IRM5A2-ST-S800	8/24/2022	-	856.56	-	848.36	8 - 10 ft	8.2 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S801	SSHS-IRM5A2-ST-S801	8/24/2022	-	856.63	-	848.44	8 - 10 ft	8.19 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1002	SSHS-IRM5A2-ST-S1002	8/24/2022	-	856.40	-	846.52	8 - 10 ft	9.88 ft	1801434601	Not Excavated						
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-DUP209	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435252	Not Excavated	< 0.038 U	< 0.022 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated		< 31 U							
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435252	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated		< 32 U							
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated		< 32 U							
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated		< 32 U							
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435252	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated		< 31 U							
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated		< 29 U							
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated		< 33 U							
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated		< 29 U							
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated		< 31 U							
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439932	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439932	Not Excavated				< 0.048 U	< 0.038 U	0.048 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated		< 32 U							
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated		< 31 U							
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated		< 33 U							
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439932	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated		< 29 U							
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated		< 30 U							
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated		< 32 U							
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439932	Not Excavated				< 0.048 U	< 0.038 U	1.1	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated		< 35 U							
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated		< 34 U							
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated		< 34 U							
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442132	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated		< 32 U							
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated		< 30 U							
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated		< 30 U							
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated		< 30 U							
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442132	Not Excavated				< 0.046 U	< 0.037 U	< 0.044 U	< 0.050 U	< 0.046 U	< 0.029 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/8/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801442122	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated		< 33 U							
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated		< 32 U							
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated		< 31 U							
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447212	Not Excavated				< 0.047 U	< 0.038 U	0.088 J	< 0.051 U	< 0.047 U	< 0.030 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated		< 31 U							
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated		< 30 U							
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated		< 33 U							
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465942	Not Excavated				< 0.050 U	< 0.040 U	0.10 J	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated		< 31 U							
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated		< 31 U							
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated		< 32 U							
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468422	Not Excavated				< 0.053 U	< 0.042 U	0.34 B	< 0.058 U	< 0.053 U	< 0.033 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated		< 32 U							
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated		< 30 U							
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469432	Not Excavated				< 0.050 U	< 0.040 U	0.092 BJ	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated		< 31 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435252	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435252	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.041 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated									
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated									
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated									
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated									
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439932	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.052 U	< 0.040 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439932	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.052 U	< 0.041 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439932	Not Excavated	< 0.053 U	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated									
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439932	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	0.23
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated									
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442132	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated									
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated									
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated									
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated									
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated									
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442132	Not Excavated	< 0.047 U	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	< 0.042 U	< 0.051 U	< 0.040 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/8/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801442122	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.046 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated									
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated									
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated									
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447212	Not Excavated	< 0.048 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.11 J	0.061 J	< 0.041 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated									
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465942	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated									
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated									
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated									
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468422	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	0.13 J	< 0.059 U	0.20 J
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated									
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated									
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated									
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469432	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S803	SSHS-IRM5A2-ST-S803	8/25/2022	-	856.60	-	848.51	8 - 10 ft	8.1 ft	1801435252	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	ST-S804	SSHS-IRM5A2-ST-S804	8/25/2022	-	856.76	-	848.44	8 - 10 ft	8.32 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S805	SSHS-IRM5A2-ST-S805	8/25/2022	-	857.05	-	848.12	8 - 10 ft	8.93 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1005	SSHS-IRM5A2-ST-S1005	8/25/2022	-	856.52	-	846.51	8 - 10 ft	10.01 ft	1801435252	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	ST-S1006	SSHS-IRM5A2-ST-S1006	8/25/2022	-	856.16	-	847.12	8 - 10 ft	9.04 ft	1801435251	Not Excavated						
Northern Athletic Field	ST-S1007	SSHS-IRM5A2-ST-S1007	8/25/2022	-	856.18	-	846.63	8 - 10 ft	9.55 ft	1801435251	Not Excavated						
Northern Athletic Field	FLSP-B16A	SSHS-IRM5A2-FLSP-B16A	8/25/2022	-	856.88	-	848.08	8 - 10 ft	8.79 ft	1801435261	Not Excavated						
Northern Athletic Field	FISC-B11	SSHS-IRM5A2-FISC-B11	8/26/2022	-	856.95	-	848.37	8 - 10 ft	8.59 ft	1801436181	Not Excavated						
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-DUP215	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-DUP214	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S1	SSHS-IRM5A2-A6-FISLAT-S1	9/2/2022	-	854.91	-	845.10	8 - 10 ft	9.81 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S2	SSHS-IRM5A2-A6-FISLAT-S2	9/2/2022	-	854.95	-	845.22	8 - 10 ft	9.73 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S3	SSHS-IRM5A2-A6-FISLAT-S3	9/2/2022	-	855.18	-	845.91	8 - 10 ft	9.27 ft	1801439932	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-FISLAT-S4	SSHS-IRM5A2-A6-FISLAT-S4	9/2/2022	-	855.22	-	845.70	8 - 10 ft	9.51 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S5	SSHS-IRM5A2-A6-FISLAT-S5	9/2/2022	-	855.45	-	846.32	8 - 10 ft	9.13 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S6	SSHS-IRM5A2-A6-FISLAT-S6	9/2/2022	-	855.49	-	846.17	8 - 10 ft	9.32 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S7	SSHS-IRM5A2-A6-FISLAT-S7	9/2/2022	-	855.74	-	846.81	8 - 10 ft	8.93 ft	1801439932	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-FISLAT-S8	SSHS-IRM5A2-A6-FISLAT-S8	9/2/2022	-	855.82	-	846.93	8 - 10 ft	8.9 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S9	SSHS-IRM5A2-A6-FISLAT-S9	9/2/2022	-	856.02	-	847.46	8 - 10 ft	8.57 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-S10	SSHS-IRM5A2-A6-FISLAT-S10	9/2/2022	-	856.10	-	847.60	8 - 10 ft	8.5 ft	1801439932	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6-FISLAT-B1	SSHS-IRM5A2-A6-FISLAT-B1	9/2/2022	-	854.91	-	845.01	8 - 10 ft	9.91 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-B2	SSHS-IRM5A2-A6-FISLAT-B2	9/2/2022	-	855.20	-	845.76	8 - 10 ft	9.44 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-B3	SSHS-IRM5A2-A6-FISLAT-B3	9/2/2022	-	855.45	-	846.22	8 - 10 ft	9.23 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-B4	SSHS-IRM5A2-A6-FISLAT-B4	9/2/2022	-	855.78	-	846.91	8 - 10 ft	8.88 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439931	Not Excavated						
Northern Athletic Field	A6-FISLAT-B5	SSHS-IRM5A2-A6-FISLAT-B5	9/2/2022	-	856.06	-	847.45	8 - 10 ft	8.61 ft	1801439932	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-FISLAT-S11	SSHS-IRM5A2-A6-FISLAT-S11	9/6/2022	-	856.32	-	848.01	8 - 10 ft	8.32 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/6/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-FISLAT-B6	SSHS-IRM5A2-A6-FISLAT-B6	9/6/2022	-	856.35	-	847.41	8 - 10 ft	8.94 ft	1801440321	Not Excavated						
Northern Athletic Field	A6-S1004	SSHS-IRM5A2-A6-S1004	9/8/2022	-	856.89	-	847.03	8 - 10 ft	9.86 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S1005	SSHS-IRM5A2-A6-S1005	9/8/2022	-	856.64	-	846.87	8 - 10 ft	9.77 ft	1801442132	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Northern Athletic Field	A6-S1006	SSHS-IRM5A2-A6-S1006	9/8/2022	-	856.44	-	846.92	8 - 10 ft	9.52 ft	1801442131	Not Excavated						
Northern Athletic Field	A6-S1007	SSHS-IRM5A2-A6-S1007	9/8/2022	-	856.48	-	847.14	8 - 10 ft	9.33 ft	1801442131	Not Excavated						
Northern Athletic Field	CP2-S19BOT	SSHS-IRM5A2-CP2-S19BOT	9/8/2022	-	856.58	-	846.84	8 - 10 ft	9.74 ft	1801442131	Not Excavated						
Northern Athletic Field	B407BOT	SSHS-IRM5A2-A6-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated						
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442131	Not Excavated						
Northern Athletic Field	B407BOT	SSHS-IRM5A2-B407BOT	9/8/2022	-	856.65	-	846.87	8 - 10 ft	9.78 ft	1801442132	Not Excavated	< 0.036 U	< 0.020 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	A6-FISLAT-S12	SSHS-IRM5A2-A6-FISLAT-S12	9/8/2022	-	856.36	-	847.84	8 - 10 ft	8.52 ft	1801442122	Not Excavated	< 0.042 U	< 0.024 U	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	A6-FISLAT-S13	SSHS-IRM5A2-A6-FISLAT-S13	9/16/2022	-	856.58	-	848.12	8 - 10 ft	8.46 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-S14	SSHS-IRM5A2-A6-FISLAT-S14	9/16/2022	-	856.48	-	848.46	8 - 10 ft	8.03 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-B6A	SSHS-IRM5A2-A6-FISLAT-B6A	9/16/2022	-	856.54	-	848.27	8 - 10 ft	8.26 ft	1801446691	Not Excavated						
Northern Athletic Field	A6-FISLAT-B7	SSHS-IRM5A2-A6-FISLAT-B7	9/16/2022	-	856.57	-	848.49	8 - 10 ft	8.08 ft	1801446691	Not Excavated						
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447211	Not Excavated						
Northern Athletic Field	FISR-S71-BOT-S4	SSHS-IRM5A2-FISR-S71-BOT-S4	9/19/2022	-	854.68	-	846.45	8 - 10 ft	8.23 ft	1801447212	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6-S642	SSHS-IRM5A2-A6-S642	10/20/2022	-	857.79	-	849.27	8 - 10 ft	8.52 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S804A	SSHS-IRM5A2-A6-S804A	10/20/2022	-	856.87	-	847.77	8 - 10 ft	9.09 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465941	Not Excavated						
Northern Athletic Field	A6-S805A	SSHS-IRM5A2-A6-S805A	10/20/2022	-	857.24	-	847.41	8 - 10 ft	9.83 ft	1801465942	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6-B801	SSHS-IRM5A2-A6-B801	10/20/2022	-	857.02	-	847.58	8 - 10 ft	9.45 ft	1801465941	Not Excavated						
Northern Athletic Field	A19-S10BOT	SSHS-IRM5A2-A19-S10BOT	10/25/2022	-	857.18	-	847.44	8 - 10 ft	9.75 ft	1801468421	Not Excavated						
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468421	Not Excavated						
Northern Athletic Field	A19-S11BOT	SSHS-IRM5A2-A19-S11BOT	10/25/2022	-	857.07	-	847.55	8 - 10 ft	9.52 ft	1801468422	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-DUP247	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated						
Northern Athletic Field	A1-VAULT-S18	SSHS-IRM5A2-A1-VAULT-S18	10/26/2022	-	857.10	-	847.14	8 - 10 ft	9.96 ft	1801469411	Not Excavated						
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469431	Not Excavated						
Northern Athletic Field	A1-VAULT-S19	SSHS-IRM5A2-A1-VAULT-S19	10/26/2022	-	857.31	-	847.35	8 - 10 ft	9.96 ft	1801469432	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A1-VAULT-S20	SSHS-IRM5A2-A1-VAULT-S20	10/26/2022	-	857.25	-	847.58	8 - 10 ft	9.67 ft	1801469431	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated		< 35 U							
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated		< 35 U							
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487442	Not Excavated				< 0.057 U	< 0.045 U	0.58	< 0.061 U	< 0.057 UT	< 0.035 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated		< 33 U							
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491412	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated		< 33 U							
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated		< 35 U							
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated		< 32 U							
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491402	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated		< 33 U							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493702	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated		< 29 U							
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493702	Not Excavated				< 0.049 U	< 0.038 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.030 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated		< 31 U							
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493702	Not Excavated				< 0.050 U	< 0.040 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated		< 30 U							
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated		< 32 U							
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572472	Not Excavated				< 0.050 U	< 0.040 U	0.077 J	< 0.055 U	< 0.050 U	< 0.031 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573812	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.051 U	< 0.048 U	< 0.030 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573812	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573812	Not Excavated				< 0.053 U	< 0.042 U	< 0.050 U	< 0.057 U	< 0.053 U	< 0.033 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573812	Not Excavated				< 0.050 U	< 0.039 U	< 0.048 U	< 0.054 U	< 0.050 U	< 0.031 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated	< 110 U								
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated	< 100 U								
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660612	Not Excavated				< 0.048 U	< 0.038 U	0.064 J	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660612	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.051 U	< 0.047 U	< 0.029 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666002	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated		< 110 U							
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated		< 110 U							
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated			< 44 U						
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated			< 42 U						
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated			< 41 U						
Rear Parking Lot	SSHS-BSW-001	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated			< 620 U						
Rear Parking Lot	SSHS-SS-12_8_20	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated			< 120 U						
Rear Parking Lot	SSHS-SS-14_8_20	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated			< 120 U						
Rear Parking Lot	SSHS-SS-16_8_20	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated			< 130 U						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated	< 110 U								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508222	Not Excavated				< 0.046 U	< 0.036 U	< 0.044 U	< 0.049 U	< 0.046 U	< 0.029 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated	< 110 U								
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated		< 260 U							

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated									
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated									
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487442	Not Excavated	< 0.058 U	< 0.045 U	< 0.034 U	< 0.037 U	< 0.026 U	< 0.039 U	0.25	0.092 J	0.077 J
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491412	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated									
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated									
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491402	Not Excavated	< 0.053 U	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	0.068 J	< 0.057 U	< 0.044 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated									
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493702	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493702	Not Excavated	< 0.050 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.044 U	< 0.054 U	< 0.041 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493702	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated									
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated									
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated									
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572472	Not Excavated	< 0.051 U	< 0.040 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	0.067 J
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated									
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573812	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	0.12 J	0.055 J	< 0.041 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573812	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 0.033 U	< 0.043 U	< 0.053 U	< 0.041 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573812	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	0.055 J	< 0.058 U	< 0.045 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated									
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573812	Not Excavated	< 0.051 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.045 U	< 0.055 U	< 0.043 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated									
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated									
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660612	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	0.039 J	0.037 J	< 0.033 U	0.14 J	0.078 J	< 0.041 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated									
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660612	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.030 U	0.026 J	< 0.032 U	0.049 J	< 0.052 U	< 0.040 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated									
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated									
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666002	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	0.036 J	< 0.033 U	0.13 J	< 0.053 U	< 0.041 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated									
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated									
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated									
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated									
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated									
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated									
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated									
Rear Parking Lot	SSHS-BSW-001	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated									
Rear Parking Lot	SSHS-SS-12_8_20	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated									
Rear Parking Lot	SSHS-SS-14_8_20	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated									
Rear Parking Lot	SSHS-SS-16_8_20	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508222	Not Excavated	< 0.047 U	< 0.036 U	< 0.028 U	< 0.029 U	< 0.021 U	< 0.031 U	< 0.041 U	< 0.050 U	< 0.039 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated									
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Northern Athletic Field	A1-VAULT-S21	SSHS-IRM5A2-A1-VAULT-S21	10/26/2022	-	857.12	-	847.19	8 - 10 ft	9.93 ft	1801469431	Not Excavated						
Northern Athletic Field	A6N-S802	SSHS-IRM5A2-A6N-S802	12/2/2022	-	854.91	-	846.64	8 - 10 ft	8.27 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-S803	SSHS-IRM5A2-A6N-S803	12/2/2022	-	855.16	-	846.92	8 - 10 ft	8.24 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487441	Not Excavated						
Northern Athletic Field	A6N-S804	SSHS-IRM5A2-A6N-S804	12/2/2022	-	855.11	-	846.73	8 - 10 ft	8.38 ft	1801487442	Not Excavated	< 0.044 U	< 0.025 U	< 0.050 U	< 0.041 U	< 0.032 U	< 0.027 U
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-S5	SSHS-ISMP-DO-S5	12/9/2022	-	858.39	-	850.19	8 - 10 ft	8.2 ft	1801491412	Not Excavated	< 0.041 U	< 0.023 U	< 0.046 U	< 0.039 U	< 0.030 U	< 0.025 U
Northern Athletic Field	DO-S6	SSHS-ISMP-DO-S6	12/9/2022	-	858.33	-	849.66	8 - 10 ft	8.67 ft	1801491411	Not Excavated						
Northern Athletic Field	DO-B1	SSHS-ISMP-DO-B1	12/9/2022	-	858.40	-	849.38	8 - 10 ft	9.02 ft	1801491411	Not Excavated						
Northern Athletic Field	A6N-B802-S2	SSHS-IRM5A2-A6N-B802-S2	12/9/2022	-	854.99	-	845.03	8 - 10 ft	9.96 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S3	SSHS-IRM5A2-A6N-S800-S3	12/9/2022	-	854.91	-	846.78	8 - 10 ft	8.13 ft	1801491402	Not Excavated	< 0.040 U	< 0.023 U	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	A6N-S800-S6	SSHS-IRM5A2-A6N-S800-S6	12/9/2022	-	854.96	-	846.57	8 - 10 ft	8.39 ft	1801491401	Not Excavated						
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-DUP273	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493702	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6N-S800-S14	SSHS-IRM5A2-A6N-S800-S14	12/14/2022	-	855.15	-	846.64	8 - 10 ft	8.51 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S17	SSHS-IRM5A2-A6N-S800-S17	12/14/2022	-	855.42	-	846.66	8 - 10 ft	8.76 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S20	SSHS-IRM5A2-A6N-S800-S20	12/14/2022	-	855.43	-	846.88	8 - 10 ft	8.54 ft	1801493702	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A6N-S800-S23	SSHS-IRM5A2-A6N-S800-S23	12/14/2022	-	855.18	-	847.00	8 - 10 ft	8.18 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-S8-BOT	SSHS-IRM5A2-A6N-S800-S8-BOT	12/14/2022	-	855.13	-	846.75	8 - 10 ft	8.38 ft	1801493702	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	A6N-S800-S9-BOT	SSHS-IRM5A2-A6N-S800-S9-BOT	12/14/2022	-	855.11	-	846.69	8 - 10 ft	8.42 ft	1801493701	Not Excavated						
Northern Athletic Field	A6N-S800-BOT2	SSHS-IRM5A2-A6N-S800-BOT2	12/14/2022	-	855.25	-	846.47	8 - 10 ft	8.77 ft	1801493711	Not Excavated						
Northern Athletic Field	A6N-S800-BOT3	SSHS-IRM5A2-A6N-S800-BOT3	12/14/2022	-	855.46	-	846.63	8 - 10 ft	8.83 ft	1801493711	Not Excavated						
Northern Athletic Field	NAF-IG-S4	SSHS-ISMP-NAF-IG-S4	5/30/2023	-	853.40	-	845.36	8 - 10 ft	8.04 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S6	SSHS-ISMP-NAF-IG-S6	5/30/2023	-	854.27	-	845.88	8 - 10 ft	8.39 ft	1801572472	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-IG-S7	SSHS-ISMP-NAF-IG-S7	5/30/2023	-	854.24	-	844.26	8 - 10 ft	9.98 ft	1801572471	Not Excavated						
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-DUP5A	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573812	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S14	SSHS-ISMP-NAF-IG-S14	6/1/2023	-	853.24	-	844.93	8 - 10 ft	8.3 ft	1801573812	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S19	SSHS-ISMP-NAF-IG-S19	6/1/2023	-	853.11	-	844.71	8 - 10 ft	8.4 ft	1801573812	Not Excavated	< 0.040 U	< 0.023 U	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	NAF-IG-S20	SSHS-ISMP-NAF-IG-S20	6/1/2023	-	853.17	-	843.46	8 - 10 ft	9.71 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573811	Not Excavated						
Northern Athletic Field	NAF-IG-S24	SSHS-ISMP-NAF-IG-S24	6/1/2023	-	853.27	-	845.16	8 - 10 ft	8.12 ft	1801573812	Not Excavated	< 0.038 U	< 0.022 U	< 0.044 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	NAF-IG-S32	SSHS-ISMP-NAF-IG-S32	6/2/2023	-	853.23	-	844.59	8 - 10 ft	8.64 ft	1801574521	Not Excavated						
Northern Athletic Field	NAF-IG-S33	SSHS-ISMP-NAF-IG-S33	6/2/2023	-	853.31	-	843.34	8 - 10 ft	9.97 ft	1801574521	Not Excavated						
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S13	SSHS-IRM5A2-A8PH3A1-S13	11/30/2023	-	--	-	843.95	8 - 10 ft	8 - 10 ft	1801660612	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH3A1-S17	SSHS-IRM5A2-A8PH3A1-S17	11/30/2023	-	--	-	844.72	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660611	Not Excavated						
Northern Athletic Field	A8PH3A1-S21	SSHS-IRM5A2-A8PH3A1-S21	11/30/2023	-	--	-	844.33	8 - 10 ft	8 - 10 ft	1801660612	Not Excavated	< 0.036 U	< 0.021 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.023 U
Northern Athletic Field	A8PH3A1-S22	SSHS-IRM5A2-A8PH3A1-S22	11/30/2023	-	852.56	-	844.34	8 - 10 ft	8.22 ft	1801660614	Not Excavated						
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666001	Not Excavated						
Northern Athletic Field	A8PH3A1-S29	SSHS-IRM5A2-A8PH3A1-S29	12/8/2023	-	852.07	-	842.34	8 - 10 ft	9.73 ft	1801666002	Not Excavated	< 0.037 U	< 0.021 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	A8PH3A1-S31	SSHS-IRM5A2-A8PH3A1-S31	12/8/2023	-	852.47	-	842.70	8 - 10 ft	9.76 ft	1801665991	Not Excavated						
Northern Athletic Field	A8PH3A1-S32	SSHS-IRM5A2-A8PH3A1-S32	12/8/2023	-	852.18	-	842.33	8 - 10 ft	9.84 ft	1801665991	Not Excavated						
Northern Athletic Field	A8PH3A1-S34	SSHS-IRM5A2-A8PH3A1-S34	12/14/2023	-	851.82	-	841.97	8 - 10 ft	9.85 ft	1801669701	Not Excavated						
Northern Athletic Field	A8PH3A1-S35	SSHS-IRM5A2-A8PH3A1-S35	12/14/2023	-	852.48	-	842.76	8 - 10 ft	9.72 ft	1801669701	Not Excavated						
Rear Parking Lot	SSHS-B64	SSHS-B64-10-12 (11)	8/14/2014	851.65	851.60	-0.05	-	10 - 12 ft	9.95-11.95 ft	180-35818-2	Not Excavated						
Rear Parking Lot	SSHS-B65	SSHS-B65-10-12 (11)	8/14/2014	850.41	850.12	-0.29	-	10 - 12 ft	9.71-11.71 ft	180-35818-1	Not Excavated						
Rear Parking Lot	SSHS-B67	SSHS-B67-10-12 (11)	8/14/2014	850.45	850.29	-0.16	-	10 - 12 ft	9.84-11.84 ft	180-35818-1	Not Excavated						
Rear Parking Lot	SSHS-BSW-001	EBSW-10-12	7/12/2018	-	853.74	-	842.00	10 - 12 ft	11.74 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-SS-12 8 20	SS-12 (10-12) 20180820	8/20/2018	-	849.92	-	838.10	10 - 12 ft	11.82 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-14 8 20	SS-14 (10-12) 20180820	8/20/2018	-	847.65	-	838.70	10 - 12 ft	8.95 ft	180-81125-1	Not Excavated						
Rear Parking Lot	SSHS-SS-16 8 20	SS-16 (10-12) 20180820	8/20/2018	-	849.67	-	838.20	10 - 12 ft	11.47 ft	180-81125-1	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508221	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-10-12	1/18/2023	851.23	851.23	0.00	-	10 - 12 ft	10 - 12 ft	1801508222	Not Excavated	< 0.035 U	< 0.020 U	< 0.040 U	< 0.033 U	< 0.026 U	< 0.022 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-10-12	2/9/2023	852.78	852.78	0.00	-	10 - 12 ft	10 - 12 ft	1801518942	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-840-838	8/12/2024	850.65	850.65	0.00	-	10.65-12.65 ft	10.65-12.65 ft	1801782961	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508221	Not Excavated	< 100 U								
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508222	Not Excavated				< 0.044 U	< 0.035 U	< 0.042 U	< 0.048 U	< 0.044 U	< 0.028 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated	< 120 U								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508222	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated	< 110 U								
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated			< 44 U						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated	< 110 U								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated	< 120 U								
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519452	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated	< 120 UT								
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4	1/18/2023	853.71	853.71	-	-	2-4	2.42-4.42 ft	1801508221	Not Excavated	< 120 U								
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4	1/18/2023	853.71	853.71	-	-	2-4	2.42-4.42 ft	1801508222	Not Excavated				< 0.054 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.054 U	< 0.034 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated			< 45 U						
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated			< 47 U						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated	< 110 U								
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6	1/18/2023	853.71	853.71	-	-	4-6	4.42-6.42 ft	1801508221	Not Excavated	< 110 U								
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6	1/18/2023	853.71	853.71	-	-	4-6	4.42-6.42 ft	1801508222	Not Excavated				< 0.051 U	< 0.041 U	< 0.049 U	< 0.056 U	< 0.051 U	< 0.032 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated	< 120 U								
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated			< 44 U						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated		< 240 U							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		< 230 U							
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated		< 250 U							
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8	1/18/2023	853.71	853.71	-	-	6-8	6.42-8.42 ft	1801508221	Not Excavated	< 120 U								
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8	1/18/2023	853.71	853.71	-	-	6-8	6.42-8.42 ft	1801508222	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.058 U	< 0.054 U	< 0.034 U
Rear Parking Lot	SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated			< 330 U						
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated			< 47 U						
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated			< 48 U						
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-59020-1	Not Excavated			< 52 U						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated	< 110 U								
Rear Parking Lot	SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated			< 550 U						
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	0.38	0.028 J	< 0.079 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.022 U	< 0.068 U
South of Athletic Stands	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated	< 120 U								
South of Athletic Stands	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated	< 110 U								
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated			< 46 U						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated			< 55 U						
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated			< 84 U						
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated			< 40 U						
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated			< 53 U						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated			< 34 U	< 0.052 U	< 0.042 U	< 0.05 U	< 0.057 U	< 0.052 U	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated			< 430 U						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated				< 0.055 U	< 0.043 U	< 0.053 U	< 0.059 U	< 0.055 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated			< 43 U						
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated			< 41 U						
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated			< 41 U						
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated			< 44 U						
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated			< 44 U						
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated			< 43 U						
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated			< 40 U						
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated			< 53 U						
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated			< 110 U						
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated			< 470 U						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated			< 160 U						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated			< 130 U	< 0.059 U	< 0.047 U	0.24 J	< 0.064 U	< 0.059 U	< 0.037 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated			< 550 U						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated			< 120 U	< 0.053 U	< 0.042 U	0.23	< 0.057 U	< 0.053 U	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated			< 550 U						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated			< 55 U						

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508221	Not Excavated									
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508222	Not Excavated	< 0.045 U	< 0.035 U	< 0.027 U	< 0.029 U	< 0.020 U	< 0.030 U	< 0.040 U	< 0.049 U	< 0.038 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508222	Not Excavated	< 0.050 U	< 0.039 U	< 0.030 U	< 0.032 U	< 0.022 U	< 0.034 U	< 0.044 U	< 0.054 U	< 0.042 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated									
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated									
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519452	Not Excavated	< 0.052 U	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.045 U	< 0.056 U	< 0.043 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4	1/18/2023	853.71	853.71	-	-	2-4	2.42-4.42 ft	1801508221	Not Excavated									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4	1/18/2023	853.71	853.71	-	-	2-4	2.42-4.42 ft	1801508222	Not Excavated	< 0.055 U	< 0.042 U	< 0.032 U	< 0.035 U	< 0.025 U	< 0.037 U	0.067 J	< 0.059 U	< 0.046 U
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated									
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated									
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6	1/18/2023	853.71	853.71	-	-	4-6	4.42-6.42 ft	1801508221	Not Excavated									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6	1/18/2023	853.71	853.71	-	-	4-6	4.42-6.42 ft	1801508222	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	0.025 J	< 0.035 U	0.15 J	0.057 J	< 0.044 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated									
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated									
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated									
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated									
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8	1/18/2023	853.71	853.71	-	-	6-8	6.42-8.42 ft	1801508221	Not Excavated									
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8	1/18/2023	853.71	853.71	-	-	6-8	6.42-8.42 ft	1801508222	Not Excavated	< 0.055 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	0.070 J	< 0.060 U	< 0.046 U
Rear Parking Lot	SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated									
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated									
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated									
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-59020-1	Not Excavated									
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated									
Rear Parking Lot	SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated									
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.041 U	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 34 U	< 0.23 U	< 0.1 U	< 0.09 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.036 U	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 34 U	< 0.2 U	< 0.088 U	< 0.079 U
South of Athletic Stands	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated									
South of Athletic Stands	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 34 U	0.05 J	< 0.058 U	< 0.045 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.056 U	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 34 U	< 0.049 U	< 0.061 U	< 0.047 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.06 U	< 0.047 U	< 0.036 U	< 0.038 U	< 0.027 U	< 34 U	< 0.053 U	< 0.065 U	< 0.05 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.054 U	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 34 U	< 0.047 U	< 0.058 U	< 0.045 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.05 U	< 0.039 U	< 0.03 U	0.071 J	< 0.023 U	< 34 U	< 0.044 U	< 0.054 U	0.061 J
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508221	Not Excavated						
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508222	Not Excavated	< 0.034 U	< 0.019 U	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508221	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-12-14	1/18/2023	851.23	851.23	0.00	-	12 - 14 ft	12 - 14 ft	1801508222	Not Excavated	< 0.038 U	< 0.021 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.023 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-12-14	2/9/2023	852.78	852.78	0.00	-	12 - 14 ft	12 - 14 ft	1801518942	Not Excavated						
Rear Parking Lot	SSHS-B101	SSHS-B101-12-15.5R (15)	8/14/2014	852.95	852.89	-0.06	-	12 - 15.5 ft	11.94-15.44 ft	180-35818-2	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-14-16	2/9/2023	852.78	852.78	0.00	-	14 - 16 ft	14 - 16 ft	1801518942	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519451	Not Excavated						
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-14-16	2/12/2023	851.23	851.23	0.00	-	14 - 16 ft	14 - 16 ft	1801519452	Not Excavated	< 0.039 U	< 0.022 U	< 0.044 U	< 0.037 U	< 0.029 U	< 0.024 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-2-4	2/9/2023	852.78	852.78	0.00	-	2 - 4 ft	2 - 4 ft	1801518942	Not Excavated						
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4	1/18/2023	853.71	853.71	-	-	2-4	2.42-4.42 ft	1801508221	Not Excavated						
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-2.4	1/18/2023	853.71	853.71	-	-	2-4	2.42-4.42 ft	1801508222	Not Excavated	< 0.041 U	< 0.023 U	< 0.047 U	< 0.039 U	< 0.030 U	0.042 J
Rear Parking Lot	SSHS-B101	DUP-17	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated						
Rear Parking Lot	SSHS-B101	SSHS-B101-3-6 (4)	8/14/2014	852.95	852.89	-0.06	-	3 - 6 ft	2.94-5.94 ft	180-35818-2	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-4-6	2/9/2023	852.78	852.78	0.00	-	4 - 6 ft	4 - 6 ft	1801518942	Not Excavated						
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6	1/18/2023	853.71	853.71	-	-	4-6	4.42-6.42 ft	1801508221	Not Excavated						
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-4-6	1/18/2023	853.71	853.71	-	-	4-6	4.42-6.42 ft	1801508222	Not Excavated	< 0.040 U	< 0.022 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-6-8	2/9/2023	852.78	852.78	0.00	-	6 - 8 ft	6 - 8 ft	1801518942	Not Excavated						
Rear Parking Lot	SSHS-B64	SSHS-B64-6-9 (9)	8/14/2014	851.65	851.60	-0.05	-	6 - 9 ft	5.95-8.95 ft	180-35818-2	Not Excavated						
Rear Parking Lot	SPA4-B5502	SSHS-SPA4-B5502-ELEV-844-842	8/12/2024	850.65	850.65	0.00	-	6.65-8.65 ft	6.65-8.65 ft	1801782961	Not Excavated						
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-DUP-05	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated						
Rear Parking Lot	SPA4-B5527	SSHS-SPA4-B5527-ELEV-846-844	8/13/2024	852.76	852.76	0.00	-	6.76-8.76 ft	6.76-8.76 ft	1801783741	Not Excavated						
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8	1/18/2023	853.71	853.71	-	-	6-8	6.42-8.42 ft	1801508221	Not Excavated						
Rear Parking Lot	PDI6-B5105	SSHS-PDI6-B5105-SUB-6-8	1/18/2023	853.71	853.71	-	-	6-8	6.42-8.42 ft	1801508222	Not Excavated	< 0.042 U	< 0.024 U	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Rear Parking Lot	SSHS-P2	SSHS-P2	7/12/2018	-	853.76	-	845.30	7.7 - 7.7 ft	8.46 ft	180-79745-1	Not Excavated						
Rear Parking Lot	SSHS-B101	SSHS-B101-8-10 (9)	8/14/2014	852.95	852.89	-0.06	-	8 - 10 ft	7.94-9.94 ft	180-35818-2	Not Excavated						
Rear Parking Lot	SSHS-B65	SSHS-B65-8-10 (9)	8/14/2014	850.41	850.12	-0.29	-	8 - 10 ft	7.71-9.71 ft	180-35818-1	Not Excavated						
Rear Parking Lot	SSHS-B548	PS-FD-31	9/21/2016	855.94	855.94	0.00	-	8 - 10 ft	8-10 ft	180-59020-1	Not Excavated						
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-8-10	2/9/2023	852.78	852.78	0.00	-	8 - 10 ft	8 - 10 ft	1801518942	Not Excavated						
Rear Parking Lot	SSHS-CS2	SSHS-CS2	7/12/2018	-	852.97	-	843.70	9.1 - 9.1 ft	9.26 ft	180-79745-1	Not Excavated						
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-14-16	6/30/2021	855.99	855.97	-0.02	-	14 - 16 ft	13.98-15.98 ft	180-123901-2	Not Excavated	< 0.063 U	< 34 U	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.055 U	< 34 U	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U
South of Athletic Stands	IRM4-PIPE 5A-O	SSHS-IRM4-PIPE 5A-O	7/23/2020	-	855.62	-	848.32	6 - 8 ft	7.3 ft	1801086991	Not Excavated						
South of Athletic Stands	IRM4-PIPE 5B-O	SSHS-IRM4-PIPE 5B-O	7/23/2020	-	855.75	-	848.20	6 - 8 ft	7.55 ft	1801086991	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SS	8/25/2016	855.65	858.37	2.72	-	0 - 0.17 ft	2.72-2.89 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-0-2	5/23/2017	855.66	858.45	2.79	-	0 - 2 ft	2.79-4.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-0.17-1	8/25/2016	855.65	858.37	2.72	-	0.17 - 1 ft	2.89-3.72 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B405	SSHS-B405-SUB-1-2	8/25/2016	855.65	858.37	2.72	-	1 - 2 ft	3.72-4.72 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B406	SSHS-B406-SUB-1-2	8/25/2016	855.97	856.64	0.67	-	1 - 2 ft	1.67-2.67 ft	180-57995-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-10-12	5/23/2017	855.66	858.45	2.79	-	10 - 12 ft	12.79-14.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-10-12	9/14/2021	855.73	855.73	0.00	-	10 - 12 ft	10-12 ft	180-127066-2	Not Excavated	< 0.04 U	< 34 U	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-10-12	9/15/2021	855.97	855.97	0.00	-	10 - 12 ft	10-12 ft	180-127140-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-10-12	9/17/2021	858.24	858.24	0.00	-	10 - 12 ft	10-12 ft	180-127265-2	Not Excavated	< 0.042 U	< 34 U	< 0.048 U	< 0.04 U	< 0.031 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-10-13.5 (10.5)	8/14/2014	855.92	855.92	0.00	-	10 - 13.5 ft	10-13.5 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-10-14 (12)	8/14/2014	856.00	856.00	0.00	-	10 - 14 ft	10-14 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-10-14.5 (12)	8/13/2014	854.77	854.77	0.00	-	10 - 14.5 ft	10 - 14.5 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-10-15 (12.5)	8/13/2014	856.60	856.60	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-10-15 (12.5)	8/13/2014	855.54	855.54	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-10-15 (12.5)	8/13/2014	854.20	854.20	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-10-15 (12.5)	8/13/2014	855.00	855.00	0.00	-	10 - 15 ft	10-15 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-10-15 (12.5)	8/13/2014	853.90	853.90	0.00	-	10 - 15 ft	10 - 15 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-10-15 (12)	8/14/2014	855.75	855.75	0.00	-	10 - 15 ft	10 - 15 ft	180-35818-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-10-15 (12)	8/14/2014	855.86	855.86	0.00	-	10 - 15 ft	10-15 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B2755	SSHS-B2755-SUB-12-14	4/26/2019	855.30	855.30	0.00	-	12 - 14 ft	12 - 14 ft	180-89521-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-OS1	SSHS-IRM3-OS1-C	8/1/2019	-	855.47	-	842.56	12 - 14 ft	12.91 ft	180-93547-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE22	SSHS-IRM3-PIPE22-C	8/2/2019	-	855.73	-	842.45	12 - 14 ft	13.28 ft	180-93641-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-12-14	9/14/2021	855.73	855.73	0.00	-	12 - 14 ft	12-14 ft	180-127066-2	Not Excavated	< 0.045 U	< 34 U	< 0.052 U	< 0.043 U	0.039 J	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-12-14	9/15/2021	855.97	855.97	0.00	-	12 - 14 ft	12-14 ft	180-127140-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-14-16	9/14/2021	855.73	855.73	0.00	-	14 - 16 ft	14-16 ft	180-127066-2	Not Excavated	< 0.041 U	< 34 U	< 0.046 U	< 0.039 U	< 0.03 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-14-16	9/15/2021	855.97	855.97	0.00	-	14 - 16 ft	14-16 ft	180-127140-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-14-16	9/17/2021	858.24	858.24	0.00	-	14 - 16 ft	14-16 ft	180-127265-2	Not Excavated	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-2-4	5/23/2017	855.66	858.45	2.79	-	2 - 4 ft	4.79-6.79 ft	180-66622-2	Not Excavated						

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100						
Restricted - Residential												13000	13000	13000						
Protection of Groundwater												100	100	100						
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated			< 110 U	< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated			< 900 U						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated	< 110 U								
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated	< 110 U								
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.026	1801436191	Not Excavated	< 110 U								
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.026	1801436192	Not Excavated				< 0.044 U	< 0.035 U	< 0.042 U	< 0.048 U	< 0.044 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated	< 110 U								
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated			< 45 U						
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated			< 47 U						
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated			< 46 U						
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated			< 44 U						
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated			< 44 U						
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated			< 44 U						
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated			< 43 U						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated			< 55 U						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated			< 120 U						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated			< 120 U						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated			< 120 U	< 0.055 U	< 0.044 U	< 0.053 U	< 0.06 U	< 0.055 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated			< 220 U						
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated			< 41 U						
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated			< 43 U						
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated			< 43 U						
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated			< 42 U						
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated			< 44 U						
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated			< 41 U						
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated			< 43 U						
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-35776-2	Not Excavated			< 45 U						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated			< 54 U						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated			< 110 U	< 0.051 U	< 0.041 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated			< 460 U						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated				< 0.047 U	< 0.037 U	0.092 J	< 0.051 U	< 0.047 U	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated			< 53 U						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	855.73	0.00	-	8 - 10 ft	8-10 ft	180-127066-2	Not Excavated			< 120 U	< 0.055 U	< 0.044 U	< 0.053 U	< 0.06 U	< 0.055 U	< 0.035 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	855.97	0.00	-	8 - 10 ft	8-10 ft	180-127140-1	Not Excavated			< 450 U						

DRAFT

												Emerging Contaminants								
												Perfluoroheptanesulfonic Acid (PFHpS)	Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																		0.88	0.66	
Restricted - Residential																		44	33	
Protection of Groundwater																		3.7	1.1	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.049 U	< 0.038 U	< 0.029 U	< 0.031 U	< 0.022 U	< 34 U	< 0.043 U	< 0.053 U	< 0.041 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.05 U	< 0.039 U	< 0.029 U	< 0.032 U	< 0.022 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.026	1801436191	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.026	1801436192	Not Excavated	< 0.045 U	< 0.035 U	< 0.027 U	< 0.028 U	< 0.020 U	< 0.030 U	< 0.039 U	< 0.049 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 34 U	< 0.049 U	< 0.061 U	< 0.047 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-35776-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.052 U	< 0.041 U	< 0.031 U	< 0.033 U	< 0.023 U	< 34 U	0.12 J	< 0.057 U	< 0.044 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.048 U	< 0.037 U	< 0.028 U	< 0.03 U	< 0.022 U	< 34 U	0.045 J	< 0.052 U	0.058 J
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated									
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	855.73	0.00	-	8 - 10 ft	8-10 ft	180-127066-2	Not Excavated	< 0.056 U	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 34 U	0.29	< 0.061 U	< 0.047 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	855.97	0.00	-	8 - 10 ft	8-10 ft	180-127140-1	Not Excavated									

DRAFT

												Perfluorotetradecanoic acid (PFTeA)	Perfluorotrideceanoic acid (PFTrA)	Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	
Restricted - Residential																	
Protection of Groundwater																	
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-2-4	9/14/2021	855.73	855.73	0.00	-	2 - 4 ft	2-4 ft	180-127066-2	Not Excavated	< 0.037 U	< 34 U	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-2-4	9/15/2021	855.97	855.97	0.00	-	2 - 4 ft	2-4 ft	180-127140-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-2-4	9/17/2021	858.24	858.24	0.00	-	2 - 4 ft	2-4 ft	180-127265-2	Not Excavated	< 0.038 U	< 34 U	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S11	SSHS-ISMP-ES-S11	8/25/2022	-	855.81	-	853.69	2 - 4 ft	2.12 ft	1801435311	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-ISMP-ES-S12	SSHS-ISMP-ES-S12	8/25/2022	-	855.87	-	853.74	2 - 4 ft	2.13 ft	1801435311	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.026	1801436191	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-S2	SSHS-ISMP-TR-S2	8/26/2022	-	855.82	-	853.79	2 - 4 ft	2.026	1801436192	Not Excavated	< 0.034 U	< 0.019 U	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Tennis Courts / Main Parking Lot	SSHS-ISMP-TR-B1	SSHS-ISMP-TR-B1	8/26/2022	-	855.79	-	853.75	2 - 4 ft	2.04	1801436191	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-2-6 (4)	8/13/2014	856.60	856.60	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-2-6 (5.5)	8/13/2014	854.77	854.77	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-2-6 (3.5)	8/13/2014	855.54	855.54	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-2-6 (3.5)	8/13/2014	854.20	854.20	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-2-6 (4)	8/13/2014	855.00	855.00	0.00	-	2 - 6 ft	2-6 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-2-6 (5)	8/13/2014	853.90	853.90	0.00	-	2 - 6 ft	2 - 6 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-2-6 (3.5)	8/14/2014	855.75	855.75	0.00	-	2 - 6 ft	2 - 6 ft	180-35818-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-2-6 (4)	8/14/2014	855.92	855.92	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-2-6 (4)	8/14/2014	856.00	856.00	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-2-6 (5)	8/14/2014	855.86	855.86	0.00	-	2 - 6 ft	2-6 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-4-6	5/23/2017	855.66	858.45	2.79	-	4 - 6 ft	6.79-8.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE7	SSHS-IRM3-PIPE7-C	8/2/2019	-	855.79	-	850.30	4 - 6 ft	5.49 ft	180-93641-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-IRM3-PIPE9	SSHS-IRM3-PIPE9-C	8/2/2019	-	855.59	-	851.09	4 - 6 ft	4.5 ft	180-93641-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-4-6	9/14/2021	855.73	855.73	0.00	-	4 - 6 ft	4-6 ft	180-127066-2	Not Excavated	< 0.043 U	< 34 U	< 0.048 U	< 0.04 U	< 0.031 U	< 0.026 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-4-6	9/15/2021	855.97	855.97	0.00	-	4 - 6 ft	4-6 ft	180-127140-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B82	SSHS-B82-6-10 (8)	8/13/2014	856.60	856.60	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B83	SSHS-B83-6-10 (8)	8/13/2014	854.77	854.77	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B85	SSHS-B85-6-10 (8)	8/13/2014	855.54	855.54	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B86	SSHS-B86-6-10 (8)	8/13/2014	854.20	854.20	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B88	SSHS-B88-6-10 (8)	8/13/2014	855.00	855.00	0.00	-	6 - 10 ft	6-10 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B89	SSHS-B89-6-10 (7.5)	8/13/2014	853.90	853.90	0.00	-	6 - 10 ft	6 - 10 ft	180-35776-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B78	SSHS-B78-6-10 (8)	8/14/2014	855.75	855.75	0.00	-	6 - 10 ft	6 - 10 ft	180-35818-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B81	SSHS-B81-6-10 (8)	8/14/2014	855.92	855.92	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B84	SSHS-B84-6-10 (8)	8/14/2014	856.00	856.00	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B87	SSHS-B87-6-10 (8)	8/14/2014	855.86	855.86	0.00	-	6 - 10 ft	6-10 ft	180-35818-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B83	DUP-11	8/13/2014	855.26	855.32	0.06	-	6 - 8 ft	6.06-8.06 ft	180-35776-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-6-8	5/23/2017	855.66	858.45	2.79	-	6 - 8 ft	8.79-10.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-6-8	9/14/2021	855.73	855.73	0.00	-	6 - 8 ft	6-8 ft	180-127066-2	Not Excavated	< 0.039 U	< 34 U	< 0.045 U	< 0.037 U	< 0.029 U	< 0.025 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-6-8	9/15/2021	855.97	855.97	0.00	-	6 - 8 ft	6-8 ft	180-127140-1	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-6-8	9/17/2021	858.24	858.24	0.00	-	6 - 8 ft	6-8 ft	180-127265-2	Not Excavated	< 0.036 U	< 34 U	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-8-10	5/23/2017	855.66	858.45	2.79	-	8 - 10 ft	10.79-12.79 ft	180-66622-2	Not Excavated						
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-8-10	9/14/2021	855.73	855.73	0.00	-	8 - 10 ft	8-10 ft	180-127066-2	Not Excavated	< 0.043 U	< 34 U	< 0.048 U	< 0.04 U	< 0.031 U	< 0.027 U
Tennis Courts / Main Parking Lot	SSHS-B4168	SSHS-B4168-SUB-8-10	9/15/2021	855.97	855.97	0.00	-	8 - 10 ft	8-10 ft	180-127140-1	Not Excavated						

DRAFT

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
												Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.1									
Restricted - Residential												1									
Protection of Groundwater												3.2									
NYS Hazardous Waste												50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2532	SSHS-B2532-SUB-14-16	10/29/2018	855.29	855.30	0.01	-	14 - 16 ft	14.01-16.01 ft	180-83541-1	Not Excavated	0.015	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.015 J	< 0.013 U	< 0.0052 U	< 0.013 U	< 0.0089 U
Football Field	SSHS-B2534	SSHS-B2534-SUB-14-16	10/30/2018	855.61	855.76	0.15	-	14 - 16 ft	14.15-16.15 ft	180-83544-1	Not Excavated	0.126	< 0.0059 U	< 0.012 U	< 0.011 U	< 0.011 U	0.051 J	0.062 J	0.013 J	< 0.013 U	< 0.0088 U
Football Field	SSHS-B2535	SSHS-B2535-SUB-14-16	10/30/2018	854.97	855.22	0.25	-	14 - 16 ft	14.25-16.25 ft	180-83544-1	Not Excavated	0.2334	< 0.0063 U	< 0.013 U	< 0.011 U	< 0.012 U	0.16 J	0.066 J	0.0074 J	< 0.014 U	< 0.0094 U
Football Field	SSHS-B2629	SSHS-B2629-SUB-14-16	4/25/2019	855.32	855.43	0.11	-	14 - 16 ft	14.11-16.11 ft	180-89522-1	Not Excavated	4.05	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	2.9 J	0.86 J	0.29 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B2679	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated	28.69	< 0.058 U	< 0.064 U	< 0.044 U	< 0.026 U	21 J	6.7 J	0.99 J	< 0.063 U	< 0.024 U
Football Field	SSHS-B2761	SSHS-B2761-SUB-14-16	4/25/2019	856.14	856.33	0.19	-	14 - 16 ft	14.19-16.19 ft	180-89522-1	Not Excavated	20.4	< 0.031 U	< 0.034 U	< 0.023 U	< 0.014 U	13 J	5 J	2.4 J	< 0.033 U	< 0.013 U
Football Field	SSHS-B2816	SSHS-B2816-SUB-14-16	5/18/2019	856.38	856.39	0.01	-	14 - 16 ft	14.01-16.01 ft	180-90319-3	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B2818	SSHS-B2818-SUB-14-16	5/18/2019	856.15	856.43	0.28	-	14 - 16 ft	14.28-16.28 ft	180-90319-3	Not Excavated	0.0071	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.0071 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated	2.624	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.9 J	0.69 J	0.034 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated	0.864	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.58 J	0.24 J	0.044 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3567	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	3.39	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2.4 J	0.83 J	0.16 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B451	SSHS-B451-SUB-14-16	9/27/2016	854.61	855.67	1.06	-	14 - 16 ft	15.06-17.06 ft	180-59163-1	Not Excavated	ND	< 0.0078 U	< 0.012 U	< 0.0043 U	< 0.0063 U	< 0.004 U	< 0.0063 U	< 0.0059 U	< 0.0053 U	< 0.0032 U
Football Field	SSHS-B621	SSHS-B621-SUB-14-16	2/13/2017	854.74	855.25	0.51	-	14 - 16 ft	14.51-16.51 ft	180-63507-2	Not Excavated	0.056	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	0.029	0.027	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B624	SSHS-B624-SUB-14-16	2/9/2017	855.38	855.50	0.12	-	14 - 16 ft	14.12-16.12 ft	180-63367-2	Not Excavated	ND	< 0.0099 U	< 0.0096 U	< 0.0074 U	< 0.015 U	< 0.0089 U	< 0.0082 U	< 0.012 U	< 0.013 U	< 0.0057 U
Football Field	SSHS-B645	SSHS-B645-SUB-14-16	2/13/2017	855.01	855.48	0.47	-	14 - 16 ft	14.47-16.47 ft	180-63507-2	Not Excavated	0.078	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.046	0.032	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B646	SSHS-B646-SUB-14-16	2/13/2017	854.99	855.40	0.41	-	14 - 16 ft	14.41-16.41 ft	180-63507-2	Not Excavated	0.96	< 0.0095 U	< 0.0093 U	< 0.0071 U	0.96	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	SSHS-B650	SSHS-B650-SUB-14-16	2/14/2017	855.56	855.59	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated	ND	< 0.0096 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0086 U	< 0.0079 U	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B651	SSHS-B651-SUB-14-16	2/14/2017	855.56	855.57	0.01	-	14 - 16 ft	14.01-16.01 ft	180-63507-2	Not Excavated	ND	< 0.009 U	< 0.0088 U	< 0.0067 U	< 0.014 U	< 0.0081 U	< 0.0075 U	< 0.011 U	< 0.012 U	< 0.0052 U
Football Field	SSHS-B652	SSHS-B652-SUB-14-16	2/14/2017	855.55	855.58	0.03	-	14 - 16 ft	14.03-16.03 ft	180-63507-2	Not Excavated	0.45	< 0.0092 U	< 0.0089 U	< 0.0068 U	< 0.014 U	0.33	0.12	< 0.012 U	< 0.012 U	< 0.0053 U
Football Field	SSHS-B657	SSHS-B657-SUB-14-16	2/10/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-63389-1	Not Excavated	0.045	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.023 J	0.022 J	< 0.012 U	< 0.013 U	< 0.0055 U
Football Field	SSHS-B657A	SSHS-B657A-SUB-14-16	7/12/2017	856.13	856.21	0.08	-	14 - 16 ft	14.08-16.08 ft	180-68139-1	Not Excavated	0.0189	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.01 J	0.0089 J	< 0.012 U	< 0.013 U	< 0.0056 U
Football Field	SSHS-B792	SSHS-B792-SUB-14-16	5/16/2017	855.95	855.96	0.01	-	14 - 16 ft	14.01-16.01 ft	180-66369-2	Not Excavated	0.342	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.015 U	0.23	0.093	0.019	< 0.013 U	< 0.0057 U
Football Field	SSHS-B800	SSHS-B800-SUB-14-16	5/17/2017	855.92	855.97	0.05	-	14 - 16 ft	14.05-16.05 ft	180-66432-2	Not Excavated	0.206	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	0.16	0.046	< 0.012 U	< 0.013 U	< 0.0054 U
Football Field	IRM4A-B024	SSHS-IRM4A-B024	10/12/2020	-	855.72	-	839.40	16 - 18 ft	16.32 ft	1801121371	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	IRM4A-B027	SSHS-IRM4A-B027	2/10/2021	-	855.51	-	839.12	16 - 18 ft	16.39 ft	1801171671	Not Excavated	16.55	< 0.056 U	< 0.061 U	< 0.042 U	< 0.025 U	12	4.3	0.25	< 0.061 U	< 0.023 U
Football Field	IRM4A-B028	SSHS-IRM4A-B028	2/10/2021	-	855.58	-	839.06	16 - 18 ft	16.51 ft	1801171671	Not Excavated	21.77	< 0.059 U	< 0.065 U	< 0.045 U	< 0.027 U	16	5.4	0.37	< 0.064 U	< 0.025 U
Football Field	IRM4A-B029	SSHS-IRM4A-B029	2/10/2021	-	855.56	-	839.14	16 - 18 ft	16.42 ft	1801171671	Not Excavated	4.588	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	3.4	1.1	0.088	< 0.0065 U	< 0.0025 U
Football Field	IRM4A-MOAB BOT 3	SSHS-IRM4A-MOAB BOT3	3/2/2021	-	855.57	-	839.01	16 - 18 ft	16.56 ft	1801177751	Not Excavated	433.8	< 0.65 U	< 0.71 U	< 0.49 U	< 0.29 U	350	74	9.8	< 0.7 U	< 0.27 U
Football Field	IRM4A-MOAB BOT1	SSHS-IRM4A-MOAB BOT1	3/2/2021	-	855.36	-	839.24	16 - 18 ft	16.12 ft	1801177751	Not Excavated	8.3	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.0035 U	6.7	1.4	0.2	< 0.0084 U	< 0.0032 U
Football Field	IRM5-A4V BOT A	SSHS-IRM5-A4V BOT A	5/2/2021	-	855.46	-	838.74	16 - 18 ft	16.71 ft	1801210181	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	IRM5-DELTA BOT 2	SSHS-IRM5-DELTA BOT 2	5/20/2021	-	855.58	-	838.25	16 - 18 ft	17.33 ft	1801219611	Not Excavated	0.357	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.3	0.057	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	IRM5-FIS-BOT64	SSHS-IRM5-FIS-BOT64	10/8/2021	-	855.62	-	838.76	16 - 18 ft	16.86 ft	1801282871	Not Excavated	2.82	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	2.2	0.53	0.09	< 0.0067 U	< 0.0026 U
Football Field	IRM5-FIS-BOT65	SSHS-IRM5-FIS-BOT65	10/8/2021	-	855.17	-	838.91	16 - 18 ft	16.26 ft	1801282871	Not Excavated	7.35	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	5.7	1.4	0.25	< 0.0066 U	< 0.0025 U
Football Field	IRM5-FIS-BOT66	SSHS-IRM5-FIS-BOT66	10/8/2021	-	855.21	-	838.91	16 - 18 ft	16.31 ft	1801282871	Not Excavated	0.0382	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.029	0.0092 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	0.602	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.46	0.12	0.022	< 0.0077 U	< 0.0029 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	0.624	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.48	0.12	0.024	< 0.0072 U	< 0.0028 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	0.241	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	0.19	0.051	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	0.023	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.023	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	0.167	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.13	0.037	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	0.027	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.027	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	0.271	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.2	0.071	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	0.781	< 0.0076 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	0.62	0.14	0.021 J	< 0.0082 U	< 0.0032 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	0.396	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	0.3	0.082	0.014 J	< 0.0068 U	< 0.0026 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	0.25	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.19	0.06	< 0.0056 U	< 0.0070 U	< 0.0027 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	0.791	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.61	0.15	0.031	< 0.0071 U	< 0.0027 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	2.02	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.5	0.41	0.11	< 0.0070 U	< 0.0027 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	0.85	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	0.64	0.17	0.04	< 0.0071 U	< 0.0027 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	0.172	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.13	0.042	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	0.139	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.11	0.029	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2760A	SSHS-B2760-SUB-16-18	5/18/2019	856.24	856.24	0.00	-	16 - 18 ft	16-18 ft	180-90319-3	Not Excavated	0.025	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.025	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B2761	SSHS-B2761-SUB-16-18	5/18/2019	856.14	856.33	0.19	-	16 - 18 ft	16.19-18.19 ft	180-90319-3	Not Excavated	1.67	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	1.1 J	0.39 J	0.18 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3555	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	0.123	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.09 J	0.033 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	0.052	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.039 J	0.013 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3556	DUP-22	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated	0.619	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.43 J	0.14 J	0.049 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-16-18	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated	0.448	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.3 J	0.11 J	0.038 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3557	DUP-23	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	0.063	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.046 J	0.017 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	0.021	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.021 J	< 0.0057 UJ	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3558	DUP-24	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-2	Not Excavated	0.3407	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.27	0.062	0.0087 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	0.262	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.2 J	0.062 J	< 0.0051 UJ	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3559	DUP-25	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-2	Not Excavated	1.142	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.87	0.24	0.032	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	1.151	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.9 J	0.22 J	0.031 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3560	DUP-26	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	0.08	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.058 J	0.022 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	0.055	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.04 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	0.238	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.22 J	0.018 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	38.1	< 0.12 U	< 0.14 U	< 0.093 U	< 0.056 U	30 J	7.1 J	1 J	< 0.13 U	< 0.052 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-16-18	1/11/2021	855.01	855.38	0.37	-	16 - 18 ft	16.37-18.37 ft	180-115815-1	Not Excavated	2.22	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.8 J	0.42 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-16-18	1/12/2021	855.22	855.42	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115861-1	Not Excavated	12100	< 60 U	< 65 U	< 45 U	< 27 U	9500 J	2300 J	300 J	< 65 U	< 25 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	0.057	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.045	0.012 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-16-18	1/12/2021	855.28	855.43	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115861-2	Not Excavated	5.74	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	3.9	1.6	0.24	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	3.06	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	2.4 J	0.56 J	0.1 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-16-18	1/19/2021	855.07	855.22	0.15	-	16 - 18 ft	16.15-18.15 ft	180-116199-1	Not Excavated	0.321	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.27	0.051	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-16-18	1/19/2021	855.27	855.46	0.19	-	16 - 18 ft	16.19-18.19 ft	180-116199-1	Not Excavated	3900	< 6 U	< 6.5 U	< 4.5 U	< 2.7 U	4600	1300	< 5.2 U	< 6.5 U	< 2.5 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-16-18	1/18/2021	855.21	855.30	0.09	-	16 - 18 ft	16.09-18.09 ft	180-116109-1	Not Excavated	4.677	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	3.4 J	1.2 J	0.077 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-16-18	4/7/2021	855.86	855.86	0.00	-	16 - 18 ft	16-18 ft	180-119671-1	Not Excavated	0.025	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.025	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-16-18	4/7/2021	855.25	855.29	0.04	-	16 - 18 ft	16.04-18.04 ft	180-119671-1	Not Excavated	0.185	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.12 J	0.065 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-16-18	4/10/2021	856.08	856.08	0.00	-	16 - 18 ft	16-18 ft	180-119841-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3859	DUP-13	4/12/2021	857.14	857.14	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 UJ	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-16-18	4/12/2021	857.14	857.14	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	0.013	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.013 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-16-18	4/14/2021	855.76	855.87	0.11	-	16 - 18 ft	16.11-18.11 ft	180-120028-1	Not Excavated	0.062	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.045 J	0.017 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	2.642	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	2.1 J	0.51 J	0.032 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3864	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	0.306	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.24 J	0.066 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	0.293	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.22 J	0.073 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	0.021	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.021	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-16-18	4/7/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119671-1	Not Excavated	0.163	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.13 J	0.033 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	175	< 0.58 U	< 0.63 U	< 0.43 U	< 0.034 U	110 J	53 J	12 J	< 0.62 U	< 0.24 U
Football Field	SSHS-B3871	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	667	< 3 U	< 3.2 U	< 2.2 U	< 0.034 U	500 J	150 J	17 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	567	< 3 U	< 3.3 U	< 2.2 U	< 0.034 U	470 J	85 J	12 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	15.16	< 0.058 U	< 0.063 U	< 0.043 U	< 0.034 U	14 J	0.99 J	0.17 J	< 0.062 U	< 0.024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	4.74	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	3.5 J	1.1 J	0.14 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	0.014	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-16-18	4/2/2021	854.82	855.57	0.75	-	16 - 18 ft	16.75-18.75 ft	180-119462-1	Not Excavated	0.02	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.02	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.713	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.39 J	0.26 J	0.063 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3877	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.866	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.59 J	0.23 J	0.046 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-16-18	4/5/2021	854.82	855.53	0.71	-	16 - 18 ft	16.71-18.71 ft	180-119510-1	Not Excavated	0.0293	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.023 J	0.0063 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	0.076	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.06 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	2.295	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.6 J	0.65 J	0.045 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-16-18	5/20/2021	855.17	855.25	0.08	-	16 - 18 ft	16.08-18.08 ft	180-121981-1	Not Excavated	0.682	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	0.44 J	0.2 J	0.042 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	0.053	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	0.033 J	0.02 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-16-18	5/19/2021	855.31	855.41	0.10	-	16 - 18 ft	16.1-18.1 ft	180-121899-1	Not Excavated	0.072	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.052 J	0.02 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	0.015	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.015 J	< 0.0055 UJ	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	0.065	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.051 J	0.014 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	0.06	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.037 J	0.023 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	ND	< 0.0095 U	< 0.01 U	< 0.0071 U	< 0.034 U	< 0.007 U	< 0.0088 U	< 0.0083 U	< 0.01 U	< 0.0039 U
Football Field	SSHS-B4165	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	ND	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.034 U	< 0.004 U	< 0.005 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B451	DUP2102	9/27/2016	854.61	855.67	1.06	-	16 - 18 ft	17.06-19.06 ft	180-59163-1	Not Excavated	ND	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	< 0.0065 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B451	SSHS-B451-SUB-16-18	9/27/2016	854.61	855.67	1.06	-	16 - 18 ft	17.06-19.06 ft	180-59163-1	Not Excavated	ND	< 0.0081 U	< 0.013 U	< 0.0044 U	< 0.0065 U	< 0.0041 U	< 0.0065 U	< 0.0061 U	< 0.0055 U	< 0.0033 U
Football Field	SSHS-B645A	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	20.4	< 0.059 U	< 0.065 U	< 0.045 U	< 0.027 U	22 J	6.3 J	1.1 J	< 0.064 U	< 0.025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	33.98	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	28 J	5.1 J	0.88 J	< 0.065 U	< 0.025 U
Football Field	SSHS-B723	SSHS-B723-SUB-16-18	4/13/2017	856.74	856.74	0.00	-	16 - 18 ft	16-18 ft	180-65226-1	Not Excavated	16.7	< 0.096 U	< 0.093 U	< 0.071 U	< 0.14 U	11	4.7	1	< 0.13 U	< 0.055 U
Football Field	SSHS-FB1	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	ND	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	< 0.041 U	
Football Field	SSHS-IRM3-B025	SSHS-IRM3-B025-C	7/29/2019	-	856.34	-	840.21	16 - 18 ft	16.13 ft	180-93352-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	SSHS-FB6	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	ND	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	< 0.037 U	
Football Field	IRM5-A4V SOUTH A	SSHS-IRM5-A4V SOUTH A	5/2/2021	-	855.57	-	835.58	18 - 20 ft	19.99 ft	1801210181	Not Excavated	0.05	< 0.0056 U	< 0.0060 U	< 0.0042 U	< 0.0025 U	0.039	0.011 J	< 0.0049 U	< 0.0060 U	< 0.0023 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	0.056	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.04 J	0.016 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	0.0426	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.036 J	0.0066 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	0.028	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.028	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	0.328	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.28 J	0.048 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	0.987	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.76 J	0.2 J	0.027 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-18-20	1/11/2021	855.32	855.47	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115815-1	Not Excavated	0.02	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.02	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	0.391	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.37 J	0.021 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-18-20	1/13/2021	855.07	855.40	0.33	-	18 - 20 ft	18.33-20.33 ft	180-115925-1	Not Excavated	0.106	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.088 J	0.018 J	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	7.591	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	5.7 J	1.8 J	0.091 J	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	3656	< 5.8 U	< 6.3 U	< 4.3 U	< 2.6 U	2900 J	680 J	76 J	< 6.3 U	< 2.4 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	4.43	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	3.4	0.89	0.14	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	0.128	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.091	0.037	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	2.305	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.8 J	0.43 J	0.075 J	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	0.171	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.14	0.031	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	2440	< 5.8 U	< 6.3 U	< 4.3 U	< 2.6 U	1700	580	160	< 6.2 U	< 2.4 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-18-20	1/18/2021	855.21	855.30	0.09	-	18 - 20 ft	18.09-20.09 ft	180-116109-1	Not Excavated	0.49	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.36 J	0.13 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-18-20	4/7/2021	855.86	855.86	0.00	-	18 - 20 ft	18-20 ft	180-119671-1	Not Excavated	0.161	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.13 J	0.031 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-18-20	4/7/2021	855.25	855.29	0.04	-	18 - 20 ft	18.04-20.04 ft	180-119671-1	Not Excavated	0.114	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.077 J	0.037 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3858	DUP-12	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	0.022	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.022 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 UJ	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	0.059	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.045 J	0.014 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	0.061	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.061	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-18-20	4/14/2021	855.76	855.87	0.11	-	18 - 20 ft	18.11-20.11 ft	180-120028-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	0.166	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.13 J	0.036 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	0.431	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.31 J	0.11 J	0.011 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	0.05	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.027 J	0.023 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3866	DUP-21	4/7/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119671-1	Not Excavated	0.117	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.086 J	0.031 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-18-20	4/7/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119671-1	Not Excavated	0.036	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.036 J	< 0.0058 UJ	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	930	< 3 U	< 3.2 U	< 2.2 U	< 0.034 U	750 J	150 J	30 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	361.1	< 1.2 U	< 1.3 U	< 0.89 U	< 0.034 U	300 J	54 J	7.1 J	< 1.3 U	< 0.49 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	0.375	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.034 U	0.29 J	0.085 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3873	DUP-06	4/19/2021	854.94	855.38	0.44	-	18 - 20 ft	18.44-20.44 ft	180-120434-1	Not Excavated	1.222	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	1 J	0.2 J	0.022 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-18-20	4/19/2021	854.94	855.38	0.44	-	18 - 20 ft	18.44-20.44 ft	180-120434-1	Not Excavated	1.55	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	1.2 J	0.35 J	< 0.0053 UJ	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-18-20	4/2/2021	854.82	855.57	0.75	-	18 - 20 ft	18.75-20.75 ft	180-119462-1	Not Excavated	0.025	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.025	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3876	DUP-27	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	0.07	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.051 J	0.019 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	0.073	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.058 J	0.015 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	0.451	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.32 J	0.11 J	0.021 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	0.04	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.04	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4009	DUP-200	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	0.358	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.28 J	0.078 J	< 0.0059 UJ	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	0.022	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	0.022	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-18-20	5/19/2021	855.81	855.80	-0.01	-	18 - 20 ft	17.99-19.99 ft	180-121899-1	Not Excavated	0.05	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.039 J	0.011 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	0.0072	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.0072 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	1.43	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	1.1 J	0.33 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4165	DUP-39	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B451	SSHS-B451-SUB-18-20	9/27/2016	854.61	855.67	1.06	-	18 - 20 ft	19.06-21.06 ft	180-59163-1	Not Excavated	ND	< 0.0088 U	< 0.014 U	< 0.0048 U	< 0.0071 U	< 0.0045 U	< 0.0071 U	< 0.0066 U	< 0.006 U	< 0.0036 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	6.04	< 0.059 U	< 0.065 U	< 0.045 U	< 0.027 U	4.9 J	0.96 J	0.18 J	< 0.064 U	< 0.025 U
Football Field	SSHS-B723	SSHS-B723-SUB-18-20	4/13/2017	856.74	856.74	0.00	-	18 - 20 ft	18-20 ft	180-65226-1	Not Excavated	0.263	< 0.0097 U	< 0.0095 U	< 0.0072 U	< 0.015 U	0.19	0.06	0.013 J	< 0.013 U	< 0.0056 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-20-22	1/11/2021	855.30	855.33	0.03	-	20 - 22 ft	20.03-22.03 ft	180-115815-1	Not Excavated	0.035	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.035	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-20-22	1/13/2021	855.33	855.47	0.14	-	20 - 22 ft	20.14-22.14 ft	180-115925-1	Not Excavated	0.024	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.024	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-20-22	1/11/2021	855.18	855.38	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115815-1	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	0.329	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.27 J	0.059 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-20-22	1/12/2021	855.35	855.36	0.01	-	20 - 22 ft	20.01-22.01 ft	180-115861-1	Not Excavated	0.409	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.32 J	0.078 J	0.011 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-20-22	1/11/2021	855.32	855.47	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115815-1	Not Excavated	0.218	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.19 J	0.028 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-20-22	1/13/2021	855.17	855.41	0.24	-	20 - 22 ft	20.24-22.24 ft	180-115925-1	Not Excavated	0.255	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.22 J	0.035 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3562	SSHS-B3562-SUB-20-22	1/13/2021	855.07	855.40	0.33	-	20 - 22 ft	20.33-22.33 ft	180-115925-1	Not Excavated	0.093	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.076 J	0.017 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-20-22	1/11/2021	855.01	855.38	0.37	-	20 - 22 ft	20.37-22.37 ft	180-115815-1	Not Excavated	14.63	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	11 J	3.5 J	0.13 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-20-22	1/12/2021	855.22	855.42	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115861-1	Not Excavated	2124	< 6.2 U	< 6.8 U	< 4.7 U	< 2.8 U	1700 J	380 J	44 J	< 6.7 U	< 2.6 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-20-22	1/12/2021	855.32	855.45	0.13	-	20 - 22 ft	20.13-22.13 ft	180-115861-2	Not Excavated	0.347	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.27	0.067	0.01 J	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-20-22	1/12/2021	855.28	855.43	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115861-2	Not Excavated	0.188	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.15	0.038	< 0.0051 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-20-22	1/18/2021	855.08	855.49	0.41	-	20 - 22 ft	20.41-22.41 ft	180-116109-1	Not Excavated	0.592	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.52 J	0.072 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-20-22	1/19/2021	855.07	855.22	0.15	-	20 - 22 ft	20.15-22.15 ft	180-116199-1	Not Excavated	0.189	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.14	0.049	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	3990	< 5.9 U	< 6.4 U	< 4.4 U	< 2.7 U	3200	790	< 5.2 U	< 6.4 U	< 2.4 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-20-22	1/18/2021	855.21	855.30	0.09	-	20 - 22 ft	20.09-22.09 ft	180-116109-1	Not Excavated	0.265	< 0.0085 U	< 0.0092 U	< 0.0063 U	< 0.0038 U	0.19 J	0.075 J	< 0.0074 U	< 0.0092 U	< 0.0035 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-20-22	4/12/2021	855.28	855.28	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	0.07	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.054 J	0.016 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3856	DUP-10	4/7/2021	855.86	855.86	0.00	-	20 - 22 ft	20-22 ft	180-119671-1	Not Excavated	0.074	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.048 J	0.026 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-20-22	4/7/2021	855.86	855.86	0.00	-	20 - 22 ft	20-22 ft	180-119671-1	Not Excavated	0.222	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.17 J	0.052 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-20-22	4/7/2021	855.25	855.29	0.04	-	20 - 22 ft	20.04-22.04 ft	180-119671-1	Not Excavated	0.145	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.1 J	0.045 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3858	DUP-34	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	0.027	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.027	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	0.029	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.029	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3858	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	0.704	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.52	0.16	0.024	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	0.021	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.021	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	0.109	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.082 J	0.027 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-20-22	4/14/2021	855.76	855.87	0.11	-	20 - 22 ft	20.11-22.11 ft	180-120028-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3863	DUP-18	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	0.056	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056	< 0.0052 UJ	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	0.109	< 0.0054 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.083 J	0.026 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	0.287	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.22 J	0.067 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	0.044	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.027 J	0.017 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-20-22	4/7/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119671-1	Not Excavated	0.077	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.062 J	0.015 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	175.6	< 0.61 U	< 0.66 U	< 0.45 U	< 0.034 U	140 J	30 J	5.6 J	< 0.65 U	< 0.25 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	4.27	< 0.062 U	< 0.067 U	< 0.046 U	< 0.034 U	3.2 J	0.95 J	0.12 J	< 0.067 U	< 0.026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	0.811	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.59 J	0.2 J	0.021 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-20-22	4/19/2021	854.94	855.38	0.44	-	20 - 22 ft	20.44-22.44 ft	180-120434-1	Not Excavated	6.02	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	4.5 J	1.3 J	0.22 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	0.0091	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0091 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-20-22	4/2/2021	854.82	855.57	0.75	-	20 - 22 ft	20.75-22.75 ft	180-119462-1	Not Excavated	0.02	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.02	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	0.047	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.032 J	0.015 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B3880	DUP-07	4/17/2021	855.20	855.37	0.17	-	20 - 22 ft	20.17-22.17 ft	180-120257-1	Not Excavated	0.683	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.62 J	0.063 J	< 0.0052 UJ	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-20-22	4/17/2021	855.20	855.37	0.17	-	20 - 22 ft	20.17-22.17 ft	180-120257-1	Not Excavated	0.608	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.51 J	0.086 J	0.012 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	0.07	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.044 J	0.026 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-20-22	5/19/2021	855.31	855.41	0.10	-	20 - 22 ft	20.1-22.1 ft	180-121899-1	Not Excavated	0.031	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.031	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-20-22	6/30/2021	855.88	855.88	0.00	-	20 - 22 ft	20-22 ft	180-123901-2	Not Excavated	0.036	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.026 J	0.01 J	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	0.679	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.42 J	0.21 J	0.049 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-22-23	4/7/2021	855.09	855.50	0.41	-	22 - 23 ft	22.41-23.41 ft	180-119671-1	Not Excavated	0.045	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.045	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-22-23	4/2/2021	854.82	855.57	0.75	-	22 - 23 ft	22.75-23.75 ft	180-119462-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3555	SSHS-B3555-SUB-22-24	1/11/2021	855.30	855.33	0.03	-	22 - 24 ft	22.03-24.03 ft	180-115815-1	Not Excavated	0.0084	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0084 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3556	SSHS-B3556-SUB-22-24	1/13/2021	855.33	855.47	0.14	-	22 - 24 ft	22.14-24.14 ft	180-115925-1	Not Excavated	0.012	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3557	SSHS-B3557-SUB-22-24	1/11/2021	855.18	855.38	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115815-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3558	SSHS-B3558-SUB-22-24	1/12/2021	855.27	855.53	0.26	-	22 - 24 ft	22.26-24.26 ft	180-115861-1	Not Excavated	0.063	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.052 J	0.011 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3559	SSHS-B3559-SUB-22-24	1/12/2021	855.35	855.36	0.01	-	22 - 24 ft	22.01-24.01 ft	180-115861-1	Not Excavated	1.406	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.1 J	0.27 J	0.036 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3560	SSHS-B3560-SUB-22-24	1/11/2021	855.32	855.47	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115815-1	Not Excavated	1.22	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	1 J	0.22 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3561	SSHS-B3561-SUB-22-24	1/13/2021	855.17	855.41	0.24	-	22 - 24 ft	22.24-24.24 ft	180-115925-1	Not Excavated	0.441	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.38 J	0.061 J	< 0.0052 U	< 0.0065 U	< 0.0025 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3562	SSHS-B3562-SUB-22-24	1/13/2021	855.07	855.40	0.33	-	22 - 24 ft	22.33-24.33 ft	180-115925-1	Not Excavated	0.3439	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.27 J	0.064 J	0.0099 J	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3563	SSHS-B3563-SUB-22-24	1/11/2021	855.01	855.38	0.37	-	22 - 24 ft	22.37-24.37 ft	180-115815-1	Not Excavated	547.8	< 2.9 U	< 3.2 U	< 2.2 U	< 1.3 U	400 J	140 J	7.8 J	< 3.2 U	< 1.2 U
Football Field	SSHS-B3564	SSHS-B3564-SUB-22-24	1/12/2021	855.22	855.42	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115861-1	Not Excavated	1094	< 6 U	< 6.5 U	< 4.5 U	< 2.7 U	870 J	200 J	24 J	< 6.4 U	< 2.5 U
Football Field	SSHS-B3565	SSHS-B3565-SUB-22-24	1/13/2021	855.32	855.45	0.13	-	22 - 24 ft	22.13-24.13 ft	180-115925-1	Not Excavated	0.014	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.014 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3566	SSHS-B3566-SUB-22-24	1/12/2021	855.28	855.43	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115861-2	Not Excavated	0.213	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.17	0.043	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-22-24	1/18/2021	855.08	855.49	0.41	-	22 - 24 ft	22.41-24.41 ft	180-116109-1	Not Excavated	0.83	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.67 J	0.16 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-22-24	1/19/2021	855.07	855.22	0.15	-	22 - 24 ft	22.15-24.15 ft	180-116199-1	Not Excavated	0.159	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.12	0.039	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-22-24	1/19/2021	855.27	855.46	0.19	-	22 - 24 ft	22.19-24.19 ft	180-116199-1	Not Excavated	2850	< 6.1 U	< 6.7 U	< 4.6 U	< 2.8 U	2200	540	110	< 6.6 U	< 2.5 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-22-24	1/18/2021	855.21	855.30	0.09	-	22 - 24 ft	22.09-24.09 ft	180-116109-1	Not Excavated	0.07	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.051 J	0.019 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-22-24	4/12/2021	855.28	855.28	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	0.09	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.072 J	0.018 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-22-24	4/7/2021	855.86	855.86	0.00	-	22 - 24 ft	22-24 ft	180-119671-1	Not Excavated	0.017	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.017 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-22-24	4/7/2021	855.25	855.29	0.04	-	22 - 24 ft	22.04-24.04 ft	180-119671-1	Not Excavated	0.314	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.22 J	0.094 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-22-24	4/10/2021	856.08	856.08	0.00	-	22 - 24 ft	22-24 ft	180-119841-1	Not Excavated	0.068	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.042 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	0.02	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.02	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-22-24	4/14/2021	855.76	855.87	0.11	-	22 - 24 ft	22.11-24.11 ft	180-120028-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	0.094	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.072 J	0.022 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	0.09	< 0.0055 U	< 0.0059 U	< 0.0041 U	< 0.0025 U	0.068 J	0.022 J	< 0.0048 U	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	0.077	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.062 J	0.015 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	148.5	< 0.68 U	< 0.74 U	< 0.51 U	< 0.034 U	120 J	24 J	4.5 J	< 0.73 U	< 0.28 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	5.67	< 0.059 U	< 0.064 U	< 0.044 U	< 0.034 U	4.7 J	0.81 J	0.16 J	< 0.064 U	< 0.024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	0.238	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.18 J	0.058 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-22-24	4/19/2021	854.94	855.38	0.44	-	22 - 24 ft	22.44-24.44 ft	180-120434-1	Not Excavated	0.34	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	0.27 J	0.07 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	180119601	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-22-24	4/2/2021	855.09	855.50	0.41	-	22 - 24 ft	22.41-24.41 ft	180-119462-1	Not Excavated	0.279	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.083 J	0.12 J	0.076 J	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	0.0305	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.022 J	0.0085 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-22-24	4/17/2021	855.20	855.37	0.17	-	22 - 24 ft	22.17-24.17 ft	180-120257-1	Not Excavated	2.081	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.6 J	0.42 J	0.061 J	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-22-24	4/18/2021	855.29	855.53	0.24	-	22 - 24 ft	22.24-24.24 ft	180-120245-1	Not Excavated	0.277	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.2 J	0.077 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4010	DUP-201	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-22-24	5/19/2021	855.31	855.41	0.10	-	22 - 24 ft	22.1-24.1 ft	180-121899-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-22-24	6/30/2021	855.88	855.88	0.00	-	22 - 24 ft	22-24 ft	180-123901-2	Not Excavated	0.402	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.29 J	0.089 J	0.023 J	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-22-24	4/18/2021	854.96	855.37	0.41	-	22 - 24 ft	22.41-24.41 ft	180-120245-1	Not Excavated	100.3	< 0.68 U	< 0.74 U	< 0.51 U	< 0.31 U	80 J	17 J	3.3 J	< 0.73 U	< 0.28 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-23-24	4/2/2021	854.82	855.57	0.75	-	23 - 24 ft	23.75-24.75 ft	180-119462-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-23-25	4/7/2021	855.09	855.50	0.41	-	23 - 25 ft	23.41-25.41 ft	180-119671-1	Not Excavated	0.064	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.049 J	0.015 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	855.38	0.37	-	24 - 26 ft	24.37-26.37 ft	180-115999-1	Not Excavated	306.6	< 0.58 U	< 0.63 U	< 0.43 U	< 0.26 U	220 J	79 J	7.6 J	< 0.62 U	< 0.24 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	855.42	0.20	-	24 - 26 ft	24.2-26.2 ft	180-116070-1	Not Excavated	19240	< 59 U	< 64 U	< 44 U	< 27 U	15000 J	3500 J	740 J	< 64 U	< 24 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-24-26	1/18/2021	855.08	855.49	0.41	-	24 - 26 ft	24.41-26.41 ft	180-116109-1	Not Excavated	1.11	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.94 J	0.17 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-24-26	1/19/2021	855.07	855.22	0.15	-	24 - 26 ft	24.15-26.15 ft	180-116199-1	Not Excavated	0.116	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.092	0.024	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-24-26	1/19/2021	855.27	855.46	0.19	-	24 - 26 ft	24.19-26.19 ft	180-116199-1	Not Excavated	621	< 6 U	< 6.6 U	< 4.5 U	< 2.7 U	480	110	31	< 6.5 U	< 2.5 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-24-26	1/18/2021	855.21	855.30	0.09	-	24 - 26 ft	24.09-26.09 ft	180-116109-1	Not Excavated	0.66	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.48 J	0.18 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-24-26	4/12/2021	855.28	855.28	0.00	-	24 - 26 ft	24-26 ft	180-119861-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3856	DUP-36	4/7/2021	855.86	855.86	0.00	-	24 - 26 ft	24-26 ft	180-119671-1	Not Excavated	0.021	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.021	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-24-26	4/7/2021	855.86	855.86	0.00	-	24 - 26 ft	24-26 ft	180-119671-1	Not Excavated	0.02	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.02	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-24-26	4/7/2021	855.25	855.29	0.04	-	24 - 26 ft	24.04-26.04 ft	180-119671-1	Not Excavated	0.014	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	0.014 J	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-24-26	4/10/2021	856.08	856.08	0.00	-	24 - 26 ft	24-26 ft	180-119841-1	Not Excavated	0.021	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.021	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-24-26	4/12/2021	857.14	857.14	0.00	-	24 - 26 ft	24-26 ft	180-119861-1	Not Excavated	0.0095	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0095 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3860	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	0.022	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.022 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	0.014	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-24-26	4/14/2021	855.76	855.87	0.11	-	24 - 26 ft	24.11-26.11 ft	180-120028-1	Not Excavated	0.077	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.052 J	0.025 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-24-26	4/9/2021	855.85	855.85	0.00	-	24 - 26 ft	24-26 ft	180-119815-1	Not Excavated	0.13	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.1 J	0.03 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	0.014	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.014 J	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	0.056	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.038 J	0.018 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	215.5	< 0.68 U	< 0.74 U	< 0.51 U	< 0.034 U	170 J	38 J	7.5 J	< 0.74 U	< 0.28 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	2.36	< 0.058 U	< 0.063 U	< 0.043 U	< 0.034 U	2 J	0.36 J	< 0.05 U	< 0.062 U	< 0.024 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	0.198	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.15 J	0.048 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	1.885	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	1.4 J	0.43 J	0.055 J	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3874	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	180119601	Not Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	180119601	Not Excavated	ND	< 0.0074 U	< 0.0080 U	< 0.0055 U	< 0.0033 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0080 U	< 0.0030 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	180119601	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3875	SSHS-B3875-SUB-24-26	4/2/2021	854.82	855.57	0.75	-	24 - 26 ft	24.75-26.75 ft	180-119462-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-24-26	4/2/2021	855.09	855.50	0.41	-	24 - 26 ft	24.41-26.41 ft	180-119462-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-24-26	4/17/2021	855.20	855.37	0.17	-	24 - 26 ft	24.17-26.17 ft	180-120257-1	Not Excavated	1.09	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.96 J	0.13 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-24-26	4/18/2021	855.29	855.53	0.24	-	24 - 26 ft	24.24-26.24 ft	180-120245-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-24-26	5/20/2021	855.17	855.25	0.08	-	24 - 26 ft	24.08-26.08 ft	180-121981-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-24-26	5/19/2021	855.31	855.41	0.10	-	24 - 26 ft	24.1-26.1 ft	180-121899-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	0.0083	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	0.0083 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B645A	DUP-02	4/18/2021	854.96	855.37	0.41	-	24 - 26 ft	24.41-26.41 ft	180-120245-1	Not Excavated	82.3	< 3.2 U	< 3.5 U	< 2.4 U	< 1.4 U	590 J	200 J	33 J	< 3.5 U	< 1.3 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-24-26	4/18/2021	854.96	855.37	0.41	-	24 - 26 ft	24.41-26.41 ft	180-120245-1	Not Excavated	71.5	< 3 U	< 3.3 U	< 2.3 U	< 1.4 U	570 J	120 J	25 J	< 3.3 U	< 1.3 U
Football Field	SSHS-B3866	SSHS-B3866-SUB-25-27	4/7/2021	855.09	855.50	0.41	-	25 - 27 ft	25.41-27.41 ft	180-119671-2	Not Excavated	0.0624	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.053 J	0.0094 J	< 0.0058 U	< 0.0072 U	< 0.0027 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3875	SSHS-B3875-SUB-26-27	4/2/2021	854.82	855.57	0.75	-	26 - 27 ft	26.75-27.75 ft	180-119462-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	855.38	0.37	-	26 - 28 ft	26.37-28.37 ft	180-115999-1	Not Excavated	581	< 1.2 U	< 1.3 U	< 0.86 U	< 0.52 U	420 J	150 J	11 J	< 1.2 U	< 0.48 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	855.42	0.20	-	26 - 28 ft	26.2-28.2 ft	180-116070-1	Not Excavated	6.59	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	5 J	1.4 J	0.19 J	< 0.0061 U	< 0.0023 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-26-28	1/18/2021	855.08	855.49	0.41	-	26 - 28 ft	26.41-28.41 ft	180-116109-1	Not Excavated	1.34	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1 J	0.34 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-26-28	1/19/2021	855.07	855.22	0.15	-	26 - 28 ft	26.15-28.15 ft	180-116199-1	Not Excavated	0.121	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.089	0.032	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-26-28	1/19/2021	855.27	855.46	0.19	-	26 - 28 ft	26.19-28.19 ft	180-116199-1	Not Excavated	4560	< 6.1 U	< 6.7 U	< 4.6 U	< 2.8 U	3400	960	200	< 6.6 U	< 2.5 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-26-28	1/18/2021	855.21	855.30	0.09	-	26 - 28 ft	26.09-28.09 ft	180-116109-1	Not Excavated	0.061	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.044 J	0.017 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-26-28	4/12/2021	855.28	855.28	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	0.015	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.015 J	< 0.006 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-26-28	4/7/2021	855.86	855.86	0.00	-	26 - 28 ft	26-28 ft	180-119671-1	Not Excavated	0.022	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.022	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3857	SSHS-B3857-SUB-26-28	4/7/2021	855.25	855.29	0.04	-	26 - 28 ft	26.04-28.04 ft	180-119671-2	Not Excavated	0.097	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.081 J	0.016 J	< 0.0065 U	< 0.008 U	< 0.003 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-26-28	4/10/2021	856.08	856.08	0.00	-	26 - 28 ft	26-28 ft	180-119841-1	Not Excavated	0.021	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.021	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	0.056	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.039 J	0.017 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-26-28	4/14/2021	855.76	855.87	0.11	-	26 - 28 ft	26.11-28.11 ft	180-120028-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-26-28	4/9/2021	855.85	855.85	0.00	-	26 - 28 ft	26-28 ft	180-119815-1	Not Excavated	0.092	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.092	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	0.026	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.026	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3870	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	25.6	< 0.07 U	< 0.076 U	< 0.052 U	< 0.034 U	19 J	5.6 J	1 J	< 0.075 U	< 0.029 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	21.04	< 0.064 U	< 0.07 U	< 0.048 U	< 0.034 U	16 J	4.5 J	0.54 J	< 0.07 U	< 0.027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	1.478	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.034 U	1.2 J	0.24 J	0.038 J	< 0.0059 U	< 0.0023 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	0.165	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	0.13 J	0.035 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-26-28	4/19/2021	854.94	855.38	0.44	-	26 - 28 ft	26.44-28.44 ft	180-120434-1	Not Excavated	0.94	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.72 J	0.22 J		< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.0030 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-26-28	4/2/2021	855.09	855.50	0.41	-	26 - 28 ft	26.41-28.41 ft	180-119462-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	0.065	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.052 J	0.013 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-26-28	4/17/2021	855.20	855.37	0.17	-	26 - 28 ft	26.17-28.17 ft	180-120257-1	Not Excavated	0.121	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.092 J	0.029 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-26-28	4/18/2021	855.29	855.53	0.24	-	26 - 28 ft	26.24-28.24 ft	180-120245-1	Not Excavated	0.074	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.074	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-26-28	5/20/2021	855.17	855.25	0.08	-	26 - 28 ft	26.08-28.08 ft	180-121981-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	0.093	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	0.068 J	0.025 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4011	DUP-203	5/19/2021	855.31	855.41	0.10	-	26 - 28 ft	26.1-28.1 ft	180-121899-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-26-28	5/19/2021	855.31	855.41	0.10	-	26 - 28 ft	26.1-28.1 ft	180-121899-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-26-28	6/30/2021	855.88	855.88	0.00	-	26 - 28 ft	26-28 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-26-28	4/18/2021	854.96	855.37	0.41	-	26 - 28 ft	26.41-28.41 ft	180-120245-1	Not Excavated	22.6	< 0.07 U	< 0.076 U	< 0.053 U	< 0.032 U	18 J	3.9 J	0.7 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	855.38	0.37	-	28 - 30 ft	28.37-30.37 ft	180-115999-1	Not Excavated	1411	< 1.2 U	< 1.3 U	< 0.93 U	< 0.56 U	1000 J	380 J	31 J	< 1.3 U	< 0.51 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	855.42	0.20	-	28 - 30 ft	28.2-30.2 ft	180-116070-1	Not Excavated	3.96	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	3 J	0.85 J	0.11 J	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-28-30	1/18/2021	855.08	855.49	0.41	-	28 - 30 ft	28.41-30.41 ft	180-116109-1	Not Excavated	1.59	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	1.3 J	0.29 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-28-30	1/19/2021	855.07	855.22	0.15	-	28 - 30 ft	28.15-30.15 ft	180-116199-1	Not Excavated	0.03	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.03	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-28-30	1/19/2021	855.27	855.46	0.19	-	28 - 30 ft	28.19-30.19 ft	180-116199-1	Not Excavated	69.6	< 0.33 U	< 0.36 U	< 0.25 U	< 0.15 U	55	12	2.6	< 0.36 U	< 0.14 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-28-30	1/18/2021	855.21	855.30	0.09	-	28 - 30 ft	28.09-30.09 ft	180-116109-1	Not Excavated	0.0391	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.03 J	0.0091 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-28-30	4/12/2021	855.28	855.28	0.00	-	28 - 30 ft	28-30 ft	180-119861-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-28-30	4/7/2021	855.86	855.86	0.00	-	28 - 30 ft	28-30 ft	180-119671-1	Not Excavated	0.047	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.047	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-28-30	4/10/2021	856.08	856.08	0.00	-	28 - 30 ft	28-30 ft	180-119841-1	Not Excavated	0.1042	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.038 J	0.058 J	0.0082 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3859	DUP-35	4/12/2021	857.14	857.14	0.00	-	28 - 30 ft	28-30 ft	180-119861-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-28-30	4/12/2021	857.14	857.14	0.00	-	28 - 30 ft	28-30 ft	180-119861-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	0.021	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.021	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-28-30	4/14/2021	855.76	855.87	0.11	-	28 - 30 ft	28.11-30.11 ft	180-120028-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	0.103	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.08 J	0.023 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	0.033	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.033	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 UJ	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	0.017	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.017 J	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	14.5	< 0.034 U	< 0.074 U	< 0.051 U	< 0.034 U	11 J	3.1 J	0.4 J	< 0.074 U	< 0.028 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	2.21	< 0.064 U	< 0.069 U	< 0.048 U	< 0.034 U	1.7 J	0.51 J	< 0.056 U	< 0.069 U	< 0.026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	0.094	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	0.066 J	0.028 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-28-30	4/19/2021	854.94	855.38	0.44	-	28 - 30 ft	28.44-30.44 ft	180-120434-1	Not Excavated	0.61	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	0.48 J	0.13 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-28-30	4/2/2021	855.09	855.50	0.41	-	28 - 30 ft	28.41-30.41 ft	180-119462-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-28-30	4/17/2021	855.20	855.37	0.17	-	28 - 30 ft	28.17-30.17 ft	180-120257-1	Not Excavated	0.06	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0032 U	0.046 J	0.014 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3881	DUP-08	4/14/2021	855.29	855.53	0.24	-	28 - 30 ft	28.24-30.24 ft	180-120028-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3881	DUP-08	4/18/2021	855.29	855.53	0.24	-	28 - 30 ft	28.24-30.24 ft	180-120245-1	Not Excavated	0.089	< 0.0073 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	0.071 J	0.018 J	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-28-30	4/18/2021	855.29	855.53	0.24	-	28 - 30 ft	28.24-30.24 ft	180-120245-1	Not Excavated	0.086	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.086	< 0.006 UJ	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-28-30	5/20/2021	855.17	855.25	0.08	-	28 - 30 ft	28.08-30.08 ft	180-121981-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0048 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-28-30	5/20/2021	855.47	855.47	0.00	-	28 - 30 ft	28-30 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4011	DUP-204	5/19/2021	855.31	855.41	0.10	-	28 - 30 ft	28.1-30.1 ft	180-121899-1	Not Excavated	0.022	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.034 U	0.022 J	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-28-30	5/19/2021	855.31	855.41	0.10	-	28 - 30 ft	28.1-30.1 ft	180-121899-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	< 0.0049 UJ	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-28-30	5/19/2021	855.81	855.80	-0.01	-	28 - 30 ft	27.99-29.99 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4015	SSHS-B4015-SUB-28-30	6/30/2021	855.88	855.88	0.00	-	28 - 30 ft	28-30 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-28-30	4/18/2021	854.96	855.37	0.41	-	28 - 30 ft	28.41-30.41 ft	180-120245-1	Not Excavated	3.43	< 0.065 U	< 0.071 U	< 0.049 U	< 0.029 U	3.3 J	0.62 J	< 0.057 U	< 0.071 U	< 0.027 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-30-31	4/10/2021	856.08	856.08	0.00	-	30 - 31 ft	30-31 ft	180-119841-1	Not Excavated	0.45	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.17 J	0.28 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	855.38	0.37	-	30 - 32 ft	30.37-32.37 ft	180-115999-1	Not Excavated	14.64	< 0.067 U	< 0.073 U	< 0.05 U	< 0.03 U	11 J	3.5 J	0.14 J	< 0.072 U	< 0.028 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	855.42	0.20	-	30 - 32 ft	30.2-32.2 ft	180-116070-1	Not Excavated	3.29	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	2.4 J	0.74 J	0.15 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-30-32	1/18/2021	855.08	855.49	0.41	-	30 - 32 ft	30.41-32.41 ft	180-116109-1	Not Excavated	4.07	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	3.7 J	0.37 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-30-32	1/19/2021	855.07	855.22	0.15	-	30 - 32 ft	30.15-32.15 ft	180-116199-1	Not Excavated	0.028	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.028	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-30-32	1/19/2021	855.27	855.46	0.19	-	30 - 32 ft	30.19-32.19 ft	180-116199-1	Not Excavated	86.4	< 0.33 U	< 0.36 U	< 0.24 U	< 0.15 U	67	16	3.4	< 0.35 U	< 0.14 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-30-32	1/18/2021	855.21	855.30	0.09	-	30 - 32 ft	30.09-32.09 ft	180-116109-1	Not Excavated	0.048	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.037 J	0.011 J	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3855	SSHS-B3855-SUB-30-32	4/13/2021	855.28	855.28	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-30-32	4/8/2021	855.86	855.86	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	0.098	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.078 J	0.02 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-30-32	4/12/2021	857.14	857.14	0.00	-	30 - 32 ft	30-32 ft	180-119861-1	Not Excavated	0.015	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.015 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-30-32	4/14/2021	855.76	855.87	0.11	-	30 - 32 ft	30.11-32.11 ft	180-120028-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-30-32	4/9/2021	855.85	855.85	0.00	-	30 - 32 ft	30-32 ft	180-119815-1	Not Excavated	0.166	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.13 J	0.036 J	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	0.024	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.024	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	8.9	< 0.065 U	< 0.071 U	< 0.049 U	< 0.034 U	7 J	1.9 J	< 0.057 U	< 0.071 U	< 0.027 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	4.5	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	3.4 J	1.1 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	0.309	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	0.25 J	0.059 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-30-32	4/19/2021	854.94	855.38	0.44	-	30 - 32 ft	30.44-32.44 ft	180-120434-1	Not Excavated	0.345	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	0.27 J	0.075 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-30-32	4/2/2021	855.09	855.50	0.41	-	30 - 32 ft	30.41-32.41 ft	180-119462-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	0.018	< 0.0072 U	< 0.0079 U	< 0.0054 U	< 0.0033 U	0.018 J	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-30-32	4/17/2021	855.20	855.37	0.17	-	30 - 32 ft	30.17-32.17 ft	180-120257-1	Not Excavated	0.262	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.21 J	0.052 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-30-32	4/18/2021	855.29	855.53	0.24	-	30 - 32 ft	30.24-32.24 ft	180-120245-1	Not Excavated	0.246	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.0033 U	0.22 J	0.026 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-30-32	5/20/2021	855.17	855.25	0.08	-	30 - 32 ft	30.08-32.08 ft	180-121981-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-30-32	5/20/2021	855.47	855.47	0.00	-	30 - 32 ft	30-32 ft	180-121981-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-30-32	5/20/2021	855.31	855.41	0.10	-	30 - 32 ft	30.1-32.1 ft	180-121981-1	Not Excavated	2.35	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	1.6 J	0.65 J	0.1 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-30-32	5/21/2021	855.04	855.41	0.37	-	30 - 32 ft	30.37-32.37 ft	180-122085-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-30-32	5/19/2021	855.81	855.80	-0.01	-	30 - 32 ft	29.99-31.99 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4015	SSHS-B4015-SUB-30-32	6/30/2021	855.88	855.88	0.00	-	30 - 32 ft	30-32 ft	180-123901-2	Not Excavated	0.016	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.034 U	0.016 J	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-31-33	4/10/2021	856.08	856.08	0.00	-	31 - 33 ft	31-33 ft	180-119841-1	Not Excavated	0.017	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.017 J	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-32-33	4/2/2021	855.09	855.50	0.41	-	32 - 33 ft	32.41-33.41 ft	180-119462-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-32-33	5/20/2021	855.47	855.47	0.00	-	32 - 33 ft	32-33 ft	180-121981-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.034 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	855.38	0.37	-	32 - 34 ft	32.37-34.37 ft	180-115999-1	Not Excavated	7.44	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	5.4 J	1.9 J	0.14 J	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	855.42	0.20	-	32 - 34 ft	32.2-34.2 ft	180-116070-1	Not Excavated	16.62	< 0.063 U	< 0.068 U	< 0.047 U	< 0.028 U	13 J	3.2 J	0.42 J	< 0.068 U	< 0.026 U
Football Field	SSHS-B3568	DUP-30	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated	2.54	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	2.1 J	0.44 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-32-34	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated	1.69	< 0.0067 U	< 0.0073 U	< 0.0051 U	< 0.003 U	1.4 J	0.29 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3569	DUP-32	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated	0.053	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.039	0.014 J	< 0.0056 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	SSHS-B3569-SUB-32-34	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated	0.089	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.066	0.023	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3570	DUP-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated	104.2	< 0.34 U	< 0.38 U	< 0.26 U	< 0.16 U	78	24	2.2	< 0.37 U	< 0.14 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-32-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated	74.5	< 0.35 U	< 0.38 U	< 0.26 U	< 0.16 U	58	14	2.5	< 0.38 U	< 0.14 U
Football Field	SSHS-B3571	DUP-35	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated	0.025	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.025	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3571	SSHS-B3571-SUB-32-34	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated	0.022	< 0.0073 U	< 0.0079 U	< 0.0055 U	< 0.0033 U	0.022	< 0.0067 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B3855	SSHS-B3855-SUB-32-34	4/13/2021	855.28	855.28	0.00	-	32 - 34 ft	32-34 ft	180-119938-2	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-32-34	4/8/2021	855.86	855.86	0.00	-	32 - 34 ft	32-34 ft	180-119767-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-32-34	4/12/2021	857.14	857.14	0.00	-	32 - 34 ft	32-34 ft	180-119861-1	Not Excavated	0.011	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.011 J	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-32-34	4/14/2021	855.76	855.87	0.11	-	32 - 34 ft	32.11-34.11 ft	180-120028-1	Not Excavated	0.147	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.11 J	0.037 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-32-34	4/9/2021	855.85	855.85	0.00	-	32 - 34 ft	32-34 ft	180-119815-1	Not Excavated	0.047	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.047	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	0.12	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.094 J	0.026 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	62.8	< 0.071 U	< 0.077 U	< 0.053 U	< 0.034 U	51 J	10 J	1.8 J	< 0.077 U	< 0.029 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	0.704	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.52 J	0.16 J	0.024 J	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	1.27	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	0.99 J	0.28 J	< 0.0054 UJ	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	0.455	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	0.39 J	0.065 J	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-32-34	4/19/2021	854.94	855.38	0.44	-	32 - 34 ft	32.44-34.44 ft	180-120434-1	Not Excavated	8.1	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.034 U	6.5 J	1.6 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	0.066	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.053 J	0.013 J	< 0.0049 U	< 0.006 U	< 0.0023 U
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	0.043	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.043	< 0.0063 UJ	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	0.053	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.042 J	0.011 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-32-34	4/17/2021	855.20	855.37	0.17	-	32 - 34 ft	32.17-34.17 ft	180-120257-1	Not Excavated	0.15	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.15	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-32-34	4/18/2021	855.29	855.53	0.24	-	32 - 34 ft	32.24-34.24 ft	180-120245-1	Not Excavated	0.365	< 0.0073 U	< 0.0079 U	< 0.0055 U	< 0.0033 U	0.3 J	0.065 J	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.034 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-32-34	5/20/2021	855.31	855.41	0.10	-	32 - 34 ft	32.1-34.1 ft	180-121981-1	Not Excavated	88.1	< 0.14 U	< 0.16 U	< 0.11 U	< 0.034 U	55 J	27 J	6.1 J	< 0.16 U	< 0.059 U
Football Field	SSHS-B4012	DUP-205	5/21/2021	855.04	855.41	0.37	-	32 - 34 ft	32.37-34.37 ft	180-122085-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.034 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B4012	SSHS-B4012-SUB-32-34	5/21/2021	855.04	855.41	0.37	-	32 - 34 ft	32.37-34.37 ft	180-122085-1	Not Excavated	ND	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-32-34	5/19/2021	855.81	855.80	-0.01	-	32 - 34 ft	31.99-33.99 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4015	SSHS-B4015-SUB-32-34	6/30/2021	855.88	855.88	0.00	-	32 - 34 ft	32-34 ft	180-123901-2	Not Excavated	ND	< 0.034 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0062 U	< 0.034 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-32-34	4/18/2021	854.96	855.37	0.41	-	32 - 34 ft	32.41-34.41 ft	180-120245-1	Not Excavated	27.77	< 0.064 U	< 0.07 U	< 0.048 U	< 0.029 U	21 J	6 J	0.77 J	< 0.07 U	< 0.027 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-33-34	4/2/2021	855.09	855.50	0.41	-	33 - 34 ft	33.41-34.41 ft	180-119462-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3858	SSHS-B3858-SUB-33-35	4/10/2021	856.08	856.08	0.00	-	33 - 35 ft	33-35 ft	180-119841-2	Not Excavated	0.015	< 0.0069 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	0.015 J	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3568	DUP-31	1/18/2021	855.08	855.49	0.41	-	34 - 35 ft	34.41-35.41 ft	180-116109-1	Not Excavated	0.963	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.89 J	0.073 J	< 0.0056 U	< 0.0069 U	< 0.0027 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-34-35	4/18/2021	855.29	855.53	0.24	-	34 - 35 ft	34.24-35.24 ft	180-120245-1	Not Excavated	0.179	< 0.0074 U	< 0.0081 U	< 0.0055 U	< 0.0033 U	0.13 J	0.049 J	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	855.38	0.37	-	34 - 36 ft	34.37-36.37 ft	180-115999-1	Not Excavated	96.9	< 0.7 U	< 0.76 U	< 0.53 U	< 0.32 U	69 J	25 J	2.9 J	< 0.76 U	< 0.29 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	855.42	0.20	-	34 - 36 ft	34.2-36.2 ft	180-116070-1	Not Excavated	1.581	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	1.1 J	0.46 J	0.021 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3568	SSHS-B3568-SUB-34-35	1/18/2021	855.08	855.49	0.41	-	34 - 36 ft	34.41-36.41 ft	180-116109-1	Not Excavated	1.94	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	1.8 J	0.14 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3569	DUP-33	1/19/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	180-116199-1	Not Excavated	0.026	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.026	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3570	SSHS-B3570-SUB-34-35	1/19/2021	855.27	855.46	0.19	-	34 - 36 ft	34.19-36.19 ft	180-116199-1	Not Excavated	245.6	< 0.65 U	< 0.71 U	< 0.49 U	< 0.29 U	190	46	9.6	< 0.7 U	< 0.27 U
Football Field	SSHS-B3856	SSHS-B3856-SUB-34-36	4/8/2021	855.86	855.86	0.00	-	34 - 36 ft	34-36 ft	180-119767-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-34-36	4/12/2021	857.14	857.14	0.00	-	34 - 36 ft	34-36 ft	180-119861-2	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-34-36	4/14/2021	855.76	855.87	0.11	-	34 - 36 ft	34.11-36.11 ft	180-120028-1	Not Excavated	0.023	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	0.023	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-34-36	4/9/2021	855.85	855.85	0.00	-	34 - 36 ft	34-36 ft	180-119815-1	Not Excavated	0.102	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.071 J	0.031 J	< 0.0056 U	< 0.0069 U	< 0.0027 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	0.038	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.038	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	0.901	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.034 U	0.73 J	0.14 J	0.031 J	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	2.554	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	2.2 J	0.31 J	0.044 J	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3872	DUP-05	4/20/2021	855.35	855.48	0.13	-	34 - 36 ft	34.13-36.13 ft	180-120434-1	Not Excavated	13.59	< 0.067 U	< 0.073 U	< 0.051 U	< 0.034 U	10 J	2.7 J	0.89 J	< 0.073 U	< 0.028 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-34-36	4/20/2021	855.35	855.48	0.13	-	34 - 36 ft	34.13-36.13 ft	180-120434-1	Not Excavated	41	< 0.13 U	< 0.14 U	< 0.099 U	< 0.034 U	30 J	11 J	< 0.12 UJ	< 0.14 U	< 0.054 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	3.87	< 0.0067 U	< 0.0072 U	< 0.005 U	< 0.034 U	3.1 J	0.77 J	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-34-36	4/2/2021	855.09	855.50	0.41	-	34 - 36 ft	34.41-36.41 ft	180-119462-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	0.028	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.028	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-34-36	4/17/2021	855.20	855.37	0.17	-	34 - 36 ft	34.17-36.17 ft	180-120257-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-34-36	5/20/2021	855.17	855.25	0.08	-	34 - 36 ft	34.08-36.08 ft	180-121981-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.034 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-34-36	5/20/2021	855.31	855.41	0.10	-	34 - 36 ft	34.1-36.1 ft	180-121981-1	Not Excavated	0.221	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.034 U	0.16 J	0.061 J	< 0.0066 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B4013	SSHS-B4013-SUB-34-36	5/19/2021	855.81	855.80	-0.01	-	34 - 36 ft	33.99-35.99 ft	180-121899-2	Not Excavated	ND	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B4015	SSHS-B4015-SUB-34-36	6/30/2021	855.88	855.88	0.00	-	34 - 36 ft	34-36 ft	180-123901-2	Not Excavated	ND	< 0.0077 U	< 0.0084 U	< 0.0058 U	< 0.034 U	< 0.0057 U	< 0.0071 U	< 0.0067 U	< 0.0083 U	< 0.0032 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-34-36	4/18/2021	854.96	855.37	0.41	-	34 - 36 ft	34.41-36.41 ft	180-120245-1	Not Excavated	513	< 3.4 U	< 3.7 U	< 2.5 U	< 1.5 U	420 J	79 J	14 J	< 3.7 U	< 1.4 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-35-37	4/18/2021	855.29	855.53	0.24	-	35 - 36 ft	35.24-36.24 ft	180-120245-1	Not Excavated	0.103	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.084 J	0.019 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3563	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	855.38	0.37	-	36 - 37 ft	36.37-37.37 ft	180-116070-1	Not Excavated	833	< 6.3 U	< 6.8 U	< 4.7 U	< 2.8 U	620 J	190 J	23 J	< 6.8 U	< 2.6 U
Football Field	SSHS-B3564	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	855.42	0.20	-	36 - 37 ft	36.2-37.2 ft	180-116070-1	Not Excavated	9596	< 67 U	< 73 U	< 51 U	< 30 U	7100 J	2400 J	96 J	< 73 U	< 28 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-36-37	4/10/2021	855.85	855.85	0.00	-	36 - 37 ft	36-37 ft	180-119841-1	Not Excavated	0.143	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.11 J	0.033 J	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	5.976	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.034 U	5 J	0.89 J	0.086 J	< 0.007 U	< 0.0027 U
Football Field	SSHS-B3876	SSHS-B3876-SUB-36-37	4/2/2021	855.09	855.50	0.41	-	36 - 37 ft	36.41-37.41 ft	180-119462-2	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3861	SSHS-B3861-SUB-36-38	4/14/2021	855.76	855.87	0.11	-	36 - 38 ft	36.11-38.11 ft	180-120028-2	Not Excavated	0.013	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.013 J	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	0.439	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.034 U	0.35 J	0.075 J	0.014 J	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-36-38	4/20/2021	855.35	855.48	0.13	-	36 - 38 ft	36.13-38.13 ft	180-120434-1	Not Excavated	30.94	< 0.07 U	< 0.076 U	< 0.052 U	< 0.034 U	24 J	6 J	0.94 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	0.144	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.034 U	0.11 J	0.034 J	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	ND	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-36-38	4/17/2021	855.20	855.37	0.17	-	36 - 38 ft	36.17-38.17 ft	180-120257-1	Not Excavated	0.021	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	0.021 J	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.003 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-36-38	5/20/2021	855.17	855.25	0.08	-	36 - 38 ft	36.08-38.08 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-36-38	5/20/2021	855.31	855.41	0.10	-	36 - 38 ft	36.1-38.1 ft	180-121981-1	Not Excavated	0.105	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.077 J	0.028 J	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-36-38	6/30/2021	855.88	855.88	0.00	-	36 - 38 ft	36-38 ft	180-123901-2	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.034 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-36-38	4/18/2021	854.96	855.37	0.41	-	36 - 38 ft	36.41-38.41 ft	180-120245-1	Not Excavated	18.19	< 0.068 U	< 0.074 U	< 0.051 U	< 0.031 U	15 J	2.7 J	0.49 J	< 0.074 U	< 0.028 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-37-39	4/10/2021	855.85	855.85	0.00	-	37 - 39 ft	37-39 ft	180-119841-1	Not Excavated	0.026	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	0.026	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	1.475	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.034 U	1.1 J	0.33 J	0.045 J	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-37-39	4/18/2021	855.29	855.53	0.24	-	37 - 39 ft	37.24-39.24 ft	180-120245-2	Not Excavated	0.03	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	0.03	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-37-39	5/20/2021	855.47	855.47	0.00	-	37 - 39 ft	37-39 ft	180-121981-1	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.008 U	< 0.003 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	0.982	< U	< U	< U	< U	0.79 J	0.16 J	0.032 J	< U	< U
Football Field	SSHS-B3872	SSHS-B3872-SUB-38-40	4/20/2021	855.35	855.48	0.13	-	38 - 40 ft	38.13-40.13 ft	180-120434-1	Not Excavated	0.244	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.034 U	0.18 J	0.064 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	0.42	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.034 U	0.31 J	0.11 J	< 0.0063 U	< 0.0077 U	< 0.003 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	ND	< 0.0075 U	< 0.0082 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0066 U	< 0.0081 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-38-40	4/5/2021	854.82	855.53	0.71	-	38 - 40 ft	38.71-40.71 ft	180-119510-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-38-40	4/19/2021	855.20	855.37	0.17	-	38 - 40 ft	38.17-40.17 ft	180-120245-1	Not Excavated	0.16	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.034 U	0.13 J	0.03 J	< 0.0068 U	< 0.0084 U	< 0.0032 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-38-40	5/20/2021	855.17	855.25	0.08	-	38 - 40 ft	38.08-40.08 ft	180-121981-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	< 0.005 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-38-40	6/30/2021	855.88	855.88	0.00	-	38 - 40 ft	38-40 ft	180-123901-2	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.003 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	0.023	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.023	< 0.0065 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-38-40	4/18/2021	854.96	855.37	0.41	-	38 - 40 ft	38.41-40.41 ft	180-120245-1	Not Excavated	14.48	< 0.07 U	< 0.076 U	< 0.052 U	< 0.031 U	12 J	2.1 J	0.38 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-39-41	4/10/2021	855.85	855.85	0.00	-	39 - 41 ft	39-41 ft	180-119841-2	Not Excavated	ND	< 0.0082 U	< 0.009 U	< 0.0062 U	< 0.0037 U	< 0.0061 U	< 0.0076 U	< 0.0072 U	< 0.0089 U	< 0.0034 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	3.443	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	2.6 J	0.75 J	0.093 J	< 0.008 U	< 0.003 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-39-41	5/20/2021	855.47	855.47	0.00	-	39 - 41 ft	39-41 ft	180-121981-1	Not Excavated	ND	< 0.0073 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0054 U	< 0.0068 U	< 0.0064 U	< 0.0079 U	< 0.003 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-40-42	4/20/2021	855.35	855.48	0.13	-	40 - 42 ft	40.13-42.13 ft	180-120434-1	Not Excavated	0.438	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.034 U	0.36 J	0.078 J	< 0.0062 U	< 0.0077 U	< 0.003 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	0.029	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.034 U	0.029	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	0.146	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	0.12 J	0.026 J	< 0.0061 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-40-42	4/19/2021	855.20	855.37	0.17	-	40 - 42 ft	40.17-42.17 ft	180-120245-2	Not Excavated	0.064	< U	< U	< U	< U	0.051 J	0.013 J	< U	< U	< U
Football Field	SSHS-B4009	SSHS-B4009-SUB-40-42	5/20/2021	855.17	855.25	0.08	-	40 - 42 ft	40.08-42.08 ft	180-121981-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.034 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Football Field	SSHS-B4015	SSHS-B4015-SUB-40-42	6/30/2021	855.88	855.88	0.00	-	40 - 42 ft	40-42 ft	180-123901-2	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.034 U	< 0.0055 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	0.037	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.034 U	0.037	< 0.0066 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Football Field	SSHS-B645A	SSHS-B645A-SUB-40-42	4/18/2021	854.96	855.37	0.41	-	40 - 42 ft	40.41-42.41 ft	180-120245-2	Not Excavated	4.1	< 0.07 U	< 0.076 U	< 0.052 U	< 0.032 U	3.4 J	0.55 J	0.15 J	< 0.076 U	< 0.029 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	0.682	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.034 U	0.5 J	0.16 J	0.022 J	< 0.0084 U	< 0.0032 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-42-43	4/5/2021	854.82	855.53	0.71	-	42 - 43 ft	42.71-43.71 ft	180-119510-1	Not Excavated	0.018	< 0.0071 U	< 0.0077 U	< 0.0053 U	< 0.0032 U	0.018 J	< 0.0065 U	< 0.0062 U	< 0.0076 U	< 0.0029 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-42-44	4/20/2021	855.35	855.48	0.13	-	42 - 44 ft	42.13-44.13 ft	180-120434-1	Not Excavated	0.61	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.034 U	0.5 J	0.11 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	0.034	< 0.0074 U	< 0.0081 U	< 0.0056 U	< 0.034 U	0.034	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	0.618	< U	< U	< U	< U	0.47 J	0.13 J	0.018 J	< U	< U
Football Field	SSHS-B3878	SSHS-B3878-SUB-43-45	4/5/2021	854.82	855.53	0.71	-	43 - 45 ft	43.71-45.71 ft	180-119510-1	Not Excavated	ND	< 0.0074 U	< 0.008 U	< 0.0055 U	< 0.0033 U	< 0.0055 U	< 0.0068 U	< 0.0065 U	< 0.008 U	< 0.0031 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-45-47	4/5/2021	854.82	855.53	0.71	-	45 - 47 ft	45.71-47.71 ft	180-119510-2	Not Excavated	ND	< 0.0077 U	< 0.0083 U	< 0.0057 U	< 0.0034 U	< 0.0057 U	< 0.0071 U	< 0.0067 U	< 0.0083 U	< 0.0032 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated	0.022	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.022	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	ND	< 0.0027	< 0.0034	< 0.0031	< 0.0029	< 0.0017	< 0.0025	< 0.0025	< 0.0039	< 0.0023
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	ND	< 0.0026	< 0.0033	< 0.003	< 0.0028	< 0.0017	< 0.0025	< 0.0025	< 0.0038	< 0.0022
Northern Athletic Field	SSHS-B3007	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 UJ	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3008	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	0.62	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	0.34 J	0.28 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3012	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	0.029	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.029	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3013	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-12-14	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	180-94752-2	Not Excavated	ND	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3021	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3026	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3040	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3041	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3055	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3056	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-12-14	12/18/2019	853.76	857.23	3.47	-	12 - 14 ft	15.47-17.47 ft	180-100380-1	Not Excavated	25.06	< 0.059 U	< 0.064 U	< 0.044 U	< 0.027 U	17 J	7.2 J	0.86 J	< 0.064 U	< 0.024 U
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-12-14	12/18/2019	854.51	857.10	2.59	-	12 - 14 ft	14.59-16.59 ft	180-100380-2	Not Excavated	1.364	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.85 J	0.45 J	0.064 J	< 0.0059 U	< 0.0023 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-12-14	1/23/2021	853.86	856.33	2.47	-	12 - 14 ft	14.47-16.47 ft	180-116404-1	Not Excavated	2.735	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	2 J	0.69 J	0.045 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-12-14	1/21/2021	854.61	858.08	3.47	-	12 - 14 ft	15.47-17.47 ft	180-116310-1	Not Excavated	1.308	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.97 J	0.28 J	0.058 J	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	1.748	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	1.3	0.41	0.038	< 0.0060 U	< 0.0023 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-12-14	6/18/2021	854.11	857.72	3.61	-	12 - 14 ft	15.61-17.61 ft	180-123449-1	Not Excavated	0.093	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.075 J	0.018 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-12-14	6/18/2021	853.29	857.05	3.76	-	12 - 14 ft	15.76-17.76 ft	180-123449-1	Not Excavated	0.44	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-12-14	7/26/2021	853.87	857.04	3.17	-	12 - 14 ft	15.17-17.17 ft	180-124973-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3012A	SSHS-B3012A-SUB-14-16	7/26/2021	853.25	856.18	2.93	-	14 - 16 ft	16.93-18.93 ft	180-124973-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3013A	SSHS-B3013A-SUB-14-16	7/26/2021	852.88	857.02	4.14	-	14 - 16 ft	18.14-20.14 ft	180-124973-1	Not Excavated	0.033	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.033	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-14-16	1/23/2021	853.60	855.95	2.35	-	14 - 16 ft	16.35-18.35 ft	1801164041	Not Excavated	2.79	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	2.4	0.39	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3025	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3034	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3049	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3067	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3080	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3082	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3096	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3181	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	0.024	< 0.0055 U	< 0.006 U	< 0.0041 U	< 0.0025 U	0.012 J	0.012 J	< 0.0048 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3182	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3220	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3221	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3223	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	0.043	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.028 J	0.015 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3264	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	266	< 2.9 U	< 3.2 U	< 2.2 U	< 1.3 U	200 J	66 J	< 2.6 U	< 3.2 U	< 1.2 U
Northern Athletic Field	SSHS-B3265	SSHS-B3265-SUB-14-16	12/18/2019	854.04	857.78	3.74	-	14 - 16 ft	17.74-19.74 ft	180-100380-1	Not Excavated	1.094	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.79 J	0.27 J	0.034 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3266	SSHS-B3266-SUB-14-16	12/18/2019	853.76	857.23	3.47	-	14 - 16 ft	17.47-19.47 ft	180-100380-2	Not Excavated	156	< 0.59 U	< 0.64 U	< 0.44 U	< 0.27 U	92 J	57 J	7 J	< 0.64 U	< 0.24 U
Northern Athletic Field	SSHS-B3267	SSHS-B3267-SUB-14-16	12/18/2019	854.51	857.10	2.59	-	14 - 16 ft	16.59-18.59 ft	180-100380-1	Not Excavated	0.672	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.42 J	0.21 J	0.042 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3268	SSHS-B3268-SUB-14-16	12/18/2019	854.73	857.54	2.81	-	14 - 16 ft	16.81-18.81 ft	180-100380-1	Not Excavated	0.472	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.26 J	0.16 J	0.052 J	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	4.38	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	3.4	0.81	0.17	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-14-16	1/23/2021	853.86	856.33	2.47	-	14 - 16 ft	16.47-18.47 ft	180-116404-1	Not Excavated	17.05	< 0.059 U	< 0.064 U	< 0.044 U	< 0.027 U	13 J	3.7 J	0.35 J	< 0.064 U	< 0.024 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-14-16	1/21/2021	854.61	858.08	3.47	-	14 - 16 ft	17.47-19.47 ft	180-116310-1	Not Excavated	1.771	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.3 J	0.39 J	0.081 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	1.646	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.2	0.41	0.036	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	0.135	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	0.088 J	0.047 J	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3882	DUP-1	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	0.03	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.03	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-14-16	5/11/2021	853.49	857.33	3.84	-	14 - 16 ft	17.84-19.84 ft	180-121474-1	Not Excavated	121	< 0.29 U	< 0.31 U	< 0.22 U	< 0.13 U	100 J	21 J	< 0.25 U	< 0.31 U	< 0.12 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-14-16	9/22/2021	854.12	856.10	1.98	-	14 - 16 ft	15.98-17.98 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-14-16	5/18/2021	854.47	855.96	1.49	-	14 - 16 ft	15.49-17.49 ft	180-121822-1	Not Excavated	0.11	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.11	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-14-16	5/14/2021	855.59	856.04	0.45	-	14 - 16 ft	14.45-16.45 ft	180-121705-1	Not Excavated	0.01	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.01 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	0.039	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.039 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-14-16	5/14/2021	856.33	857.11	0.78	-	14 - 16 ft	14.78-16.78 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-14-16	5/13/2021	856.49	857.15	0.66	-	14 - 16 ft	14.66-16.66 ft	180-121704-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-14-16	5/11/2021	852.98	852.99	0.01	-	14 - 16 ft	14.01-16.01 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	ND	< 0.0071 U	< 0.0078 U	< 0.0053 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0062 U	< 0.0077 U	< 0.0029 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-14-16	5/15/2021	854.53	854.89	0.36	-	14 - 16 ft	14.36-16.36 ft	180-121747-1	Not Excavated	0.0094	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0094 J	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-14-16	5/16/2021	855.21	855.33	0.12	-	14 - 16 ft	14.12-16.12 ft	180-121747-1	Not Excavated	0.101	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.077 J	0.024 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-14-16	5/14/2021	856.30	857.63	1.33	-	14 - 16 ft	15.33-17.33 ft	180-121705-1	Not Excavated	0.198	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.15 J	0.048 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-14-16	5/13/2021	857.53	857.85	0.32	-	14 - 16 ft	14.32-16.32 ft	180-121704-1	Not Excavated	0.059	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.043 J	0.016 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-14-16	5/12/2021	856.44	857.55	1.11	-	14 - 16 ft	15.11-17.11 ft	180-121548-2	Not Excavated	0.015	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.015 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-14-16	5/7/2021	857.27	857.87	0.60	-	14 - 16 ft	14.6-16.6 ft	180-121355-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-14-16	5/10/2021	856.60	856.69	0.09	-	14 - 16 ft	14.09-16.09 ft	180-121424-1	Not Excavated	0.088	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.088	< 0.0052 UJ	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-14-16	6/10/2021	856.20	856.23	0.03	-	14 - 16 ft	14.03-16.03 ft	180-123098-2	Not Excavated	2.01	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.4 J	0.47 J	0.14 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-14-16	6/11/2021	855.61	855.81	0.20	-	14 - 16 ft	14.2-16.2 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-14-16	5/15/2021	855.68	856.30	0.62	-	14 - 16 ft	14.62-16.62 ft	180-121747-1	Not Excavated	0.224	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.18 J	0.044 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-14-16	6/11/2021	855.12	855.85	0.73	-	14 - 16 ft	14.73-16.73 ft	180-123134-1	Not Excavated	0.583	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.44 J	0.13 J	0.013 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	0.025	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	0.025	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	0.023	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	0.023	< 0.0064 U	< 0.0060 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	0.078	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.054	0.024	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-14-16	5/12/2021	852.53	854.78	2.25	-	14 - 16 ft	16.25-18.25 ft	180-121548-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 UJ	< 0.0058 UJ	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	0.679	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.51	0.14	0.029	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3918	SSHS-B3918-SUB-14-16	5/12/2021	854.82	854.84	0.02	-	14 - 16 ft	14.02-16.02 ft	180-121548-2	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-14-16	5/16/2021	852.79	854.90	2.11	-	14 - 16 ft	16.11-18.11 ft	180-121747-1	Not Excavated	0.12	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.12	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-14-16	7/1/2021	853.40	855.25	1.85	-	14 - 16 ft	15.85-17.85 ft	180-123985-1	Not Excavated	4.3	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	4.3	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-14-16	6/18/2021	854.11	857.72	3.61	-	14 - 16 ft	17.61-19.61 ft	180-123449-1	Not Excavated	0.041	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	0.03 J	0.011 J	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-14-16	6/18/2021	854.03	857.60	3.57	-	14 - 16 ft	17.57-19.57 ft	180-123449-1	Not Excavated	0.024	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.024 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-14-16	6/18/2021	853.31	857.20	3.89	-	14 - 16 ft	17.89-19.89 ft	180-123449-1	Not Excavated	8.7	< 0.064 U	< 0.07 U	< 0.048 U	< 0.029 U	8.7 J	< 0.059 U	< 0.056 U	< 0.069 U	< 0.027 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-14-16	6/18/2021	853.29	857.05	3.76	-	14 - 16 ft	17.76-19.76 ft	180-123449-1	Not Excavated	0.56	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.56 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-14-16	6/18/2021	853.07	854.10	1.03	-	14 - 16 ft	15.03-17.03 ft	180-123449-1	Not Excavated	0.118	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.073 J	0.045 J	< 0.005 U	< 0.0062 U	< 0.0024 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-14-16	6/18/2021	854.16	854.85	0.69	-	14 - 16 ft	14.69-16.69 ft	180-123449-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-14-16	7/26/2021	853.87	857.04	3.17	-	14 - 16 ft	17.17-19.17 ft	180-124973-1	Not Excavated	0.31	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.31	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	ND	< 0.0081	< 0.013	< 0.0045	< 0.0066	< 0.0042	< 0.0066	< 0.0061	< 0.0055	< 0.0033
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	ND	< 0.0057 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	0.095	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.06	0.035	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-7 8	SSHS-DW-7 8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	0.67	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.44	0.23	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	890	< 3.4 U	< 3.7 U	< 2.5 U	< 1.5 U	450	140	< 3 U	< 3.7 U	< 1.4 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	2.73	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	2.3	0.43	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	5.2	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	4	1.2	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	311	< 1.2 U	< 1.3 U	< 0.86 U	< 0.52 U	230	81	< 1 U	< 1.2 U	< 0.48 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	208	< 0.6 U	< 0.66 U	< 0.45 U	< 0.27 U	160	48	< 0.53 U	< 0.65 U	< 0.25 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	235	< 0.61 U	< 0.67 U	< 0.46 U	< 0.28 U	180	55	< 0.53 U	< 0.66 U	< 0.25 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	15.4	< 0.063 U	< 0.069 U	< 0.047 U	< 0.029 U	12	3.4	< 0.055 U	< 0.068 U	< 0.026 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	6.5	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	5.1	1.4	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	5.5	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	4.5	1	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	1.16	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.85	0.31	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	0.048	< 0.0062 U	< 0.0068 U	< 0.0046 U	< 0.0028 U	0.048	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	0.011	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.011 J	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	0.0286	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	0.022	0.0066 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	0.019	< 0.012 U	< 0.013 U	< 0.0091 U	< 0.0055 U	0.019 J	< 0.011 U	< 0.011 U	< 0.013 U	< 0.0050 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	0.047	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	0.047	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	2.94	< 0.0055 U	< 0.0060 U	< 0.0041 U	< 0.0025 U	2	0.94	< 0.0048 U	< 0.0059 U	< 0.0023 U
Northern Athletic Field	S323	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	1.43	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	1.1	0.33	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	0.302	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.24	0.062	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	0.021	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.021	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	0.606	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.56	0.046	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	1.034	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.95	0.084	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	0.96	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.8	0.16	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	38	< 0.059 U	< 0.064 U	< 0.044 U	< 0.026 U	28	10	< 0.051 U	< 0.063 U	< 0.024 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	66	< 0.057 U	< 0.062 U	< 0.043 U	< 0.026 U	50	16	< 0.05 U	< 0.061 U	< 0.023 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	0.53	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.42	0.11	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	4.9	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	3.3	1.6	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	2.14	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	1.4	0.74	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	0.402	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.32	0.082	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	0.244	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.19	0.054	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3012A	SSHS-B3012A-SUB-16-18	7/26/2021	853.25	856.18	2.93	-	16 - 18 ft	18.93-20.93 ft	180-124973-1	Not Excavated	0.45	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.45	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3013A	SSHS-B3013A-SUB-16-18	7/26/2021	852.88	857.02	4.14	-	16 - 18 ft	20.14-22.14 ft	180-124973-1	Not Excavated	0.27	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.27	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	1.913	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	1.5	0.4	0.013 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3087	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3222	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	65.1	< 0.3 U	< 0.32 U	< 0.22 U	< 0.13 U	51 J	13 J	1.1 J	< 0.32 U	< 0.12 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	1.294	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	1	0.26	0.034	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-16-18	1/21/2021	853.76	857.23	3.47	-	16 - 18 ft	19.47-21.47 ft	180-116310-1	Not Excavated	117.4	< 0.59 U	< 0.64 U	< 0.44 U	< 0.27 U	85 J	30 J	2.4 J	< 0.64 U	< 0.24 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	2011	< 6.1 U	< 6.6 U	< 4.6 U	< 2.7 U	1600	380	31	< 6.6 U	< 2.5 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-16-18	1/23/2021	853.86	856.33	2.47	-	16 - 18 ft	18.47-20.47 ft	180-116404-1	Not Excavated	1.74	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	1.4 J	0.34 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-16-18	1/21/2021	854.61	858.08	3.47	-	16 - 18 ft	19.47-21.47 ft	180-116310-1	Not Excavated	0.431	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.32 J	0.095 J	0.016 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	0.63	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.47	0.16	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3600	SSHS-B3600-SUB-16-18	1/28/2021	851.93	853.96	2.03	-	16 - 18 ft	18.03-20.03 ft	180-116609-1	Not Excavated	0.289	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.21	0.079	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3601	SSHS-B3601-SUB-16-18	1/28/2021	852.55	855.03	2.48	-	16 - 18 ft	18.48-20.48 ft	180-116609-1	Not Excavated	0.3	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.22	0.08	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3602	SSHS-B3602-SUB-16-18	7/19/2021	852.97	855.09	2.12	-	16 - 18 ft	18.12-20.12 ft	180-124670-1	Not Excavated	0.017	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.017 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	0.189	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.11 J	0.079 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	0.122	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.098	0.024	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-16-18	3/31/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	180-119460-1	Not Excavated	0.023	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.023	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-16-18	3/31/2021	856.45	857.00	0.55	-	16 - 18 ft	16.55-18.55 ft	180-119460-1	Not Excavated	0.268	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.22 J	0.048 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	0.039	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.039	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-16-18	5/11/2021	853.49	857.33	3.84	-	16 - 18 ft	19.84-21.84 ft	180-121474-1	Not Excavated	32.1	< 0.062 U	< 0.067 U	< 0.046 U	< 0.028 U	27 J	5.1 J	< 0.054 U	< 0.067 U	< 0.025 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-16-18	9/22/2021	854.12	856.10	1.98	-	16 - 18 ft	17.98-19.98 ft	180-127488-1	Not Excavated	0.01	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	0.01 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-16-18	5/19/2021	854.47	855.96	1.49	-	16 - 18 ft	17.49-19.49 ft	180-121903-1	Not Excavated	0.31	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.31	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-16-18	5/15/2021	855.62	854.16	-1.46	-	16 - 18 ft	14.54-16.54 ft	180-121747-1	Not Excavated	0.0091	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0091 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-16-18	5/14/2021	855.59	856.04	0.45	-	16 - 18 ft	16.45-18.45 ft	180-121705-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-16-18	5/12/2021	856.79	856.60	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121548-1	Not Excavated	0.014	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.014 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	0.108	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.084	0.024	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-16-18	5/14/2021	856.33	857.11	0.78	-	16 - 18 ft	16.78-18.78 ft	180-121705-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 UJ	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-16-18	5/13/2021	856.49	857.15	0.66	-	16 - 18 ft	16.66-18.66 ft	180-121704-1	Not Excavated	0.032	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.032	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-16-18	5/11/2021	852.98	852.99	0.01	-	16 - 18 ft	16.01-18.01 ft	180-121474-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-16-18	5/15/2021	854.53	854.89	0.36	-	16 - 18 ft	16.36-18.36 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-16-18	5/16/2021	855.21	855.33	0.12	-	16 - 18 ft	16.12-18.12 ft	180-121747-1	Not Excavated	0.011	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-16-18	5/18/2021	856.45	856.26	-0.19	-	16 - 18 ft	15.81-17.81 ft	180-121822-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-16-18	5/14/2021	856.30	857.63	1.33	-	16 - 18 ft	17.33-19.33 ft	180-121705-1	Not Excavated	0.034	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.034	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-16-18	5/13/2021	857.53	857.85	0.32	-	16 - 18 ft	16.32-18.32 ft	180-121704-1	Not Excavated	0.101	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.077 J	0.024 J	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-16-18	5/12/2021	856.44	857.55	1.11	-	16 - 18 ft	17.11-19.11 ft	180-121548-2	Not Excavated	0.033	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.033	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-16-18	5/19/2021	856.98	855.02	-1.96	-	16 - 18 ft	14.04-16.04 ft	1801219031	Not Excavated	0.011	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.011 J	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-16-18	5/7/2021	857.27	857.87	0.60	-	16 - 18 ft	16.6-18.6 ft	180-121355-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-16-18	5/10/2021	856.83	856.65	-0.18	-	16 - 18 ft	15.82-17.82 ft	180-121424-1	Not Excavated	0.577	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.43 J	0.12 J	0.027 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-16-18	5/10/2021	856.60	856.69	0.09	-	16 - 18 ft	16.09-18.09 ft	180-121424-1	Not Excavated	0.562	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.43 J	0.11 J	0.022 J	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-16-18	5/11/2021	856.72	856.50	-0.22	-	16 - 18 ft	15.78-17.78 ft	180-121474-1	Not Excavated	0.076	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.05 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-16-18	5/7/2021	857.06	856.73	-0.33	-	16 - 18 ft	15.67-17.67 ft	180-121355-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-16-18	6/10/2021	856.20	856.23	0.03	-	16 - 18 ft	16.03-18.03 ft	180-123098-2	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.014 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-16-18	6/11/2021	855.61	855.81	0.20	-	16 - 18 ft	16.2-18.2 ft	180-123134-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-16-18	5/15/2021	855.68	856.30	0.62	-	16 - 18 ft	16.62-18.62 ft	180-121747-1	Not Excavated	0.011	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-16-18	6/11/2021	855.12	855.85	0.73	-	16 - 18 ft	16.73-18.73 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	0.011	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	0.011 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	0.022	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.022	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-16-18	5/12/2021	852.53	854.78	2.25	-	16 - 18 ft	18.25-20.25 ft	180-121548-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-16-18	5/13/2021	853.71	854.79	1.08	-	16 - 18 ft	17.08-19.08 ft	1801217042	Not Excavated	1.21	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.92	0.26	0.03	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-16-18	5/16/2021	852.79	854.90	2.11	-	16 - 18 ft	18.11-20.11 ft	180-121747-1	Not Excavated	0.21	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.21	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-16-18	7/1/2021	853.40	855.25	1.85	-	16 - 18 ft	17.85-19.85 ft	180-123985-1	Not Excavated	3.3	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	3.3	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-16-18	6/18/2021	854.11	857.72	3.61	-	16 - 18 ft	19.61-21.61 ft	180-123449-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-16-18	6/18/2021	854.03	857.60	3.57	-	16 - 18 ft	19.57-21.57 ft	180-123449-1	Not Excavated	0.032	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.032 J	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-16-18	6/18/2021	853.31	857.20	3.89	-	16 - 18 ft	19.89-21.89 ft	180-123449-1	Not Excavated	2.7	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	2.7 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3925A	SSHS-B3925A-SUB-16-18	7/26/2021	853.31	857.20	3.89	-	16 - 18 ft	19.89-21.89 ft	180-124973-1	Not Excavated	2.57	< 0.0068 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	2.3 J	0.27 J	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-16-18	6/18/2021	853.29	857.05	3.76	-	16 - 18 ft	19.76-21.76 ft	180-123449-1	Not Excavated	1.4	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	1.4 J	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3928	SSHS-B3928-SUB-16-18	6/18/2021	853.07	854.10	1.03	-	16 - 18 ft	17.03-19.03 ft	180-123449-2	Not Excavated	0.0233	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.015 J	0.0083 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3929	SSHS-B3929-SUB-16-18	6/18/2021	854.16	854.85	0.69	-	16 - 18 ft	16.69-18.69 ft	180-123449-2	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B4034	SSHS-B4034-SUB-16-18	7/26/2021	853.87	857.04	3.17	-	16 - 18 ft	19.17-21.17 ft	180-124973-1	Not Excavated	0.3	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.3	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	0.017	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.017 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0060 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	3.33	< 0.041	< 0.065	< 0.023	< 0.033	2.5	0.64	0.09	< 0.028	< 0.017
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0042 U	< 0.0052 U	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	710	< 3.4 U	< 3.8 U	< 2.6 U	< 1.6 U	540	170	< 3 U	< 3.7 U	< 1.4 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	8.2	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	5.6	2.6	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	20.1	< 0.06 U	< 0.066 U	< 0.045 U	< 0.027 U	17	3.1	< 0.053 U	< 0.065 U	< 0.025 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	36.6	< 0.067 U	< 0.073 U	< 0.05 U	< 0.03 U	29	7.6	< 0.059 U	< 0.073 U	< 0.028 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	0.031	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.031	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	0.279	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.057	0.092	0.13	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-18-20	1/23/2021	853.60	855.95	2.35	-	18 - 20 ft	20.35-22.35 ft	1801164041	Not Excavated	0.28	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.21	0.07	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-18-20	1/21/2021	854.31	857.51	3.20	-	18 - 20 ft	21.2-23.2 ft	180-116310-1	Not Excavated	4.17	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	3.1 J	0.94 J	0.13 J	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	0.68	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.53	0.13	0.02	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-18-20	1/21/2021	853.76	857.23	3.47	-	18 - 20 ft	21.47-23.47 ft	180-116310-1	Not Excavated	0.973	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.73 J	0.21 J	0.033 J	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	844	< 5.9 U	< 6.4 U	< 4.4 U	< 2.6 U	670	160	14 J	< 6.3 U	< 2.4 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-18-20	1/23/2021	853.86	856.33	2.47	-	18 - 20 ft	20.47-22.47 ft	180-116404-1	Not Excavated	0.61	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.45 J	0.16 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-18-20	1/22/2021	854.61	858.08	3.47	-	18 - 20 ft	21.47-23.47 ft	180-116365-1	Not Excavated	0.729	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.55 J	0.15 J	0.029 J	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-18-20	1/20/2021	854.07	857.79	3.72	-	18 - 20 ft	21.72-23.72 ft	1801162471	Not Excavated	4.31	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	3.1	1.1	0.11	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3600	SSHS-B3600-SUB-18-20	1/28/2021	851.93	853.96	2.03	-	18 - 20 ft	20.03-22.03 ft	180-116609-2	Not Excavated	0.043	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.031 J	0.012 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3601	SSHS-B3601-SUB-18-20	1/28/2021	852.55	855.03	2.48	-	18 - 20 ft	20.48-22.48 ft	180-116609-2	Not Excavated	0.91	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.65 J	0.25 J	0.01 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	0.055	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.034 J	0.021 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	0.019	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	0.019 J	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-18-20	3/31/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	180-119460-1	Not Excavated	0.023	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.023	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-18-20	3/31/2021	856.45	857.00	0.55	-	18 - 20 ft	18.55-20.55 ft	180-119460-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	0.018	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.018	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-18-20	5/11/2021	853.49	857.33	3.84	-	18 - 20 ft	21.84-23.84 ft	180-121474-1	Not Excavated	1.48	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	1.2 J	0.28 J	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-18-20	9/22/2021	854.12	856.10	1.98	-	18 - 20 ft	19.98-21.98 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-18-20	5/19/2021	854.47	855.96	1.49	-	18 - 20 ft	19.49-21.49 ft	180-121903-1	Not Excavated	0.14	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.14	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-18-20	5/15/2021	855.62	854.16	-1.46	-	18 - 20 ft	16.54-18.54 ft	180-121747-1	Not Excavated	0.029	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.029	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-18-20	5/14/2021	855.59	856.04	0.45	-	18 - 20 ft	18.45-20.45 ft	180-121705-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	0.0095	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.0095 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-18-20	5/12/2021	856.79	856.60	-0.19	-	18 - 20 ft	17.81-19.81 ft	180-121548-1	Not Excavated	0.015	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.015 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	0.014	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.014 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-18-20	5/14/2021	856.33	857.11	0.78	-	18 - 20 ft	18.78-20.78 ft	180-121705-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-18-20	5/13/2021	856.49	857.15	0.66	-	18 - 20 ft	18.66-20.66 ft	180-121704-1	Not Excavated	0.039	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	0.039	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-18-20	5/11/2021	852.98	852.99	0.01	-	18 - 20 ft	18.01-20.01 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	0.0086	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.0086 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-18-20	5/15/2021	854.53	854.89	0.36	-	18 - 20 ft	18.36-20.36 ft	180-121747-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.012 J	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-18-20	5/16/2021	855.21	855.33	0.12	-	18 - 20 ft	18.12-20.12 ft	180-121747-1	Not Excavated	0.015	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.015 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-18-20	5/18/2021	856.45	856.26	-0.19	-	18 - 20 ft	17.81-19.81 ft	180-121822-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	0.047	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.047	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-18-20	5/14/2021	856.30	857.63	1.33	-	18 - 20 ft	19.33-21.33 ft	180-121705-1	Not Excavated	ND	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	< 0.0041 U	< 0.0051 U	< 0.0049 U	< 0.006 U	< 0.0023 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-18-20	5/13/2021	857.53	857.85	0.32	-	18 - 20 ft	18.32-20.32 ft	180-121704-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-18-20	5/12/2021	856.44	857.55	1.11	-	18 - 20 ft	19.11-21.11 ft	180-121548-2	Not Excavated	0.049	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.038 J	0.011 J	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-18-20	5/19/2021	856.98	855.02	-1.96	-	18 - 20 ft	16.04-18.04 ft	1801219031	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0070 U	< 0.0027 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-18-20	5/7/2021	857.27	857.87	0.60	-	18 - 20 ft	18.6-20.6 ft	180-121355-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-18-20	5/10/2021	856.83	856.65	-0.18	-	18 - 20 ft	17.82-19.82 ft	180-121424-1	Not Excavated	0.075	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.057 J	0.018 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-18-20	5/10/2021	856.60	856.69	0.09	-	18 - 20 ft	18.09-20.09 ft	180-121424-1	Not Excavated	0.08	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.065 J	0.015 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-18-20	5/11/2021	856.72	856.50	-0.22	-	18 - 20 ft	17.78-19.78 ft	180-121474-1	Not Excavated	0.019	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.019	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-18-20	5/7/2021	857.06	856.73	-0.33	-	18 - 20 ft	17.67-19.67 ft	180-121355-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-18-20	6/10/2021	856.20	856.23	0.03	-	18 - 20 ft	18.03-20.03 ft	180-123098-2	Not Excavated	0.111	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.078 J	0.033 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-18-20	6/11/2021	855.61	855.81	0.20	-	18 - 20 ft	18.2-20.2 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-18-20	5/15/2021	855.68	856.30	0.62	-	18 - 20 ft	18.62-20.62 ft	180-121747-1	Not Excavated	0.011	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.011 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-18-20	6/11/2021	855.12	855.85	0.73	-	18 - 20 ft	18.73-20.73 ft	180-123134-1	Not Excavated	0.082	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.06 J	0.022 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	0.018	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.018 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-18-20	5/12/2021	852.53	854.78	2.25	-	18 - 20 ft	20.25-22.25 ft	180-121548-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-18-20	5/13/2021	853.71	854.79	1.08	-	18 - 20 ft	19.08-21.08 ft	1801217044	Not Excavated	0.111	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.083	0.028	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-18-20	5/16/2021	852.79	854.90	2.11	-	18 - 20 ft	20.11-22.11 ft	180-121747-1	Not Excavated	0.12	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.12	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-18-20	7/1/2021	853.40	855.25	1.85	-	18 - 20 ft	19.85-21.85 ft	180-123985-1	Not Excavated	7.2	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	7.2	< 0.055 U	< 0.052 U	< 0.065 U	< 0.025 U
Northern Athletic Field	SSHS-B3923	SSHS-B3923-SUB-18-20	6/18/2021	854.11	857.72	3.61	-	18 - 20 ft	21.61-23.61 ft	180-123449-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0029 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3924	SSHS-B3924-SUB-18-20	6/18/2021	854.03	857.60	3.57	-	18 - 20 ft	21.57-23.57 ft	180-123449-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-18-20	6/18/2021	853.31	857.20	3.89	-	18 - 20 ft	21.89-23.89 ft	180-123449-1	Not Excavated	1.3	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	1.3 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3926	SSHS-B3926-SUB-18-20	6/18/2021	853.29	857.05	3.76	-	18 - 20 ft	21.76-23.76 ft	180-123449-1	Not Excavated	0.35	< 0.0061 U	< 0.0066 U	< 0.0045 U	0.35 J	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	ND	< 0.0067 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-18-20	1/28/2021	852.44	854.81	2.37	-	18 - 20 ft	20.37-22.37 ft	180-116609-1	Not Excavated	0.085	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.061	0.024	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	ND	< 0.0070 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-20-22	1/23/2021	853.60	855.95	2.35	-	20 - 22 ft	22.35-24.35 ft	1801164041	Not Excavated	0.055	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.041	0.014 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-20-22	1/21/2021	854.31	857.51	3.20	-	20 - 22 ft	23.2-25.2 ft	180-116310-1	Not Excavated	9.89	< 0.06 U	< 0.065 U	< 0.045 U	< 0.027 U	7.3 J	2.3 J	0.29 J	< 0.065 U	< 0.025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-20-22	1/22/2021	854.14	857.83	3.69	-	20 - 22 ft	23.69-25.69 ft	1801163651	Not Excavated	0.28	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.23	0.05	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3266A	SSHS-B3266A-SUB-20-22	1/21/2021	853.76	857.23	3.47	-	20 - 22 ft	23.47-25.47 ft	180-116310-1	Not Excavated	2.173	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	1.6 J	0.48 J	0.093 J	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	26.44	< 0.063 U	< 0.069 U	< 0.047 U	< 0.028 U	21	5.1	0.34	< 0.068 U	< 0.026 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-20-22	1/23/2021	853.86	856.33	2.47	-	20 - 22 ft	22.47-24.47 ft	180-116404-1	Not Excavated	0.8787	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.64 J	0.23 J	0.0087 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3493	SSHS-B3493-SUB-20-22	1/22/2021	854.61	858.08	3.47	-	20 - 22 ft	23.47-25.47 ft	180-116365-1	Not Excavated	0.087	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.07 J	0.017 J	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-20-22	1/20/2021	854.07	857.79	3.72	-	20 - 22 ft	23.72-25.72 ft	1801162471	Not Excavated	4.52	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	3.3	1.1	0.12	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.034 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	0.048	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.037	0.011 J	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-20-22	3/31/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	180-119460-1	Not Excavated	0.03	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.03	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-20-22	3/31/2021	856.45	857.00	0.55	-	20 - 22 ft	20.55-22.55 ft	180-119460-1	Not Excavated	0.019	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.019	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	0.037	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.037	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	0.026	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.026	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-20-22	5/11/2021	853.49	857.33	3.84	-	20 - 22 ft	23.84-25.84 ft	180-121474-1	Not Excavated	0.47	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.36 J	0.11 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-20-22	11/1/2021	854.12	856.10	1.98	-	20 - 22 ft	21.98-23.98 ft	180-129378-1	Not Excavated	0.08	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.054 J	0.026 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-20-22	5/19/2021	854.47	855.96	1.49	-	20 - 22 ft	21.49-23.49 ft	180-121903-1	Not Excavated	0.077	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.077	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-20-22	5/15/2021	855.62	854.16	-1.46	-	20 - 22 ft	18.54-20.54 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-20-22	5/14/2021	855.59	856.04	0.45	-	20 - 22 ft	20.45-22.45 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	0.092	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.076 J	0.016 J	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-20-22	5/12/2021	856.79	856.60	-0.19	-	20 - 22 ft	19.81-21.81 ft	180-121548-1	Not Excavated	0.051	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.051	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-20-22	5/14/2021	856.33	857.11	0.78	-	20 - 22 ft	20.78-22.78 ft	180-121705-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-20-22	5/13/2021	856.49	857.15	0.66	-	20 - 22 ft	20.66-22.66 ft	180-121704-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-20-22	5/11/2021	852.98	852.99	0.01	-	20 - 22 ft	20.01-22.01 ft	180-121474-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-20-22	5/15/2021	854.53	854.89	0.36	-	20 - 22 ft	20.36-22.36 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-20-22	5/16/2021	855.21	855.33	0.12	-	20 - 22 ft	20.12-22.12 ft	180-121747-1	Not Excavated	0.0098	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.0098 J	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-20-22	5/18/2021	856.45	856.26	-0.19	-	20 - 22 ft	19.81-21.81 ft	180-121822-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	0.017	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.017 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-20-22	5/14/2021	856.30	857.63	1.33	-	20 - 22 ft	21.33-23.33 ft	180-121705-1	Not Excavated	0.0098	< 0.0058 UJ	< 0.0063 UJ	< 0.0043 UJ	< 0.0026 UJ	0.0098 J	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-20-22	5/13/2021	857.53	857.85	0.32	-	20 - 22 ft	20.32-22.32 ft	180-121704-1	Not Excavated	0.069	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.053 J	0.016 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-20-22	5/12/2021	856.44	857.55	1.11	-	20 - 22 ft	21.11-23.11 ft	180-121548-2	Not Excavated	0.111	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.085 J	0.026 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-20-22	5/19/2021	856.98	855.02	-1.96	-	20 - 22 ft	18.04-20.04 ft	1801219031	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-20-22	5/7/2021	857.27	857.87	0.60	-	20 - 22 ft	20.6-22.6 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-20-22	5/10/2021	856.83	856.65	-0.18	-	20 - 22 ft	19.82-21.82 ft	180-121424-1	Not Excavated	0.702	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.51 J	0.16 J	0.032 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-20-22	5/10/2021	856.60	856.69	0.09	-	20 - 22 ft	20.09-22.09 ft	180-121424-1	Not Excavated	0.122	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.11 J	0.022 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-20-22	5/11/2021	856.72	856.50	-0.22	-	20 - 22 ft	19.78-21.78 ft	180-121474-1	Not Excavated	0.012	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.012 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-20-22	5/7/2021	857.06	856.73	-0.33	-	20 - 22 ft	19.67-21.67 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-20-22	6/10/2021	856.20	856.23	0.03	-	20 - 22 ft	20.03-22.03 ft	180-123098-2	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-20-22	6/11/2021	855.61	855.81	0.20	-	20 - 22 ft	20.2-22.2 ft	180-123134-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-20-22	5/15/2021	855.68	856.30	0.62	-	20 - 22 ft	20.62-22.62 ft	180-121747-1	Not Excavated	0.014	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.014 J	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-20-22	6/11/2021	855.12	855.85	0.73	-	20 - 22 ft	20.73-22.73 ft	180-123134-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-20-22	5/12/2021	852.53	854.78	2.25	-	20 - 22 ft	22.25-24.25 ft	180-121548-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-20-22	5/16/2021	852.79	854.90	2.11	-	20 - 22 ft	22.11-24.11 ft	180-121747-1	Not Excavated	0.013	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.013 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-20-22	7/1/2021	853.40	855.25	1.85	-	20 - 22 ft	21.85-23.85 ft	180-123985-1	Not Excavated	0.034	< 0.0064 UJ	< 0.007 UJ	< 0.0048 UJ	< 0.0029 UJ	0.034 J	< 0.0059 UJ	< 0.0056 UJ	< 0.0069 UJ	< 0.0027 UJ
Northern Athletic Field	SSHS-B3925	SSHS-B3925-SUB-20-22	6/18/2021	853.31	857.20	3.89	-	20 - 22 ft	23.89-25.89 ft	180-123449-2	Not Excavated	0.265	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	0.23 J	0.035 J	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-20-22	2/1/2021	852.44	854.81	2.37	-	20 - 22 ft	22.37-24.37 ft	180-116686-2	Not Excavated	0.111	< 0.0056 U	< 0.0061 U	< 0.0042 U	< 0.0025 U	0.081 J	0.03 J	< 0.0049 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-22-23	1/20/2021	854.07	857.79	3.72	-	22 - 23 ft	25.72-26.72 ft	1801162472	Not Excavated	3.626	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	2.6	0.93	0.096	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-22-23	5/15/2021	854.53	854.89	0.36	-	22 - 23 ft	22.36-23.36 ft	180-121747-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-22-23	5/16/2021	855.21	855.33	0.12	-	22 - 23 ft	22.12-23.12 ft	180-121747-1	Not Excavated	0.016	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.016 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-22-24	1/23/2021	853.60	855.95	2.35	-	22 - 24 ft	24.35-26.35 ft	1801164043	Not Excavated	0.103	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.08	0.023	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3264A	SSHS-B3264A-SUB-22-24	1/21/2021	854.31	857.51	3.20	-	22 - 24 ft	25.2-27.2 ft	180-116310-2	Not Excavated	2.338	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	1.7 J	0.62 J	0.018 J	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163652	Not Excavated	13000	< 64 U	< 69 U	< 48 U	< 29 U	9600	3400	< 56 U	< 69 U	< 26 U
Northern Athletic Field	SSHS-B3455	SSHS-B3455-SUB-22-24	1/23/2021	853.86	856.33	2.47	-	22 - 24 ft	24.47-26.47 ft	180-116404-3	Not Excavated	0.122	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.089 J	0.033 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	0.0312	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.022 J	0.0092 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	0.108	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.085	0.023	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	040321 10:45 DUP-23	3/31/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	180-119460-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-22-24	3/31/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	180-119460-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-22-24	3/31/2021	856.45	857.00	0.55	-	22 - 24 ft	22.55-24.55 ft	180-119460-1	Not Excavated	0.021	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.021	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	0.01	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.01 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-22-24	5/11/2021	853.49	857.33	3.84	-	22 - 24 ft	25.84-27.84 ft	180-121474-1	Not Excavated	2.27	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	1.9 J	0.37 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-22-24	9/22/2021	854.12	856.10	1.98	-	22 - 24 ft	23.98-25.98 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-22-24	5/19/2021	854.47	855.96	1.49	-	22 - 24 ft	23.49-25.49 ft	180-121903-1	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-22-24	5/15/2021	855.62	854.16	-1.46	-	22 - 24 ft	20.54-22.54 ft	180-121747-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-22-24	5/14/2021	855.59	856.04	0.45	-	22 - 24 ft	22.45-24.45 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	0.013	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	0.013 J	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-22-24	5/12/2021	856.79	856.60	-0.19	-	22 - 24 ft	21.81-23.81 ft	180-121548-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-22-24	5/14/2021	856.33	857.11	0.78	-	22 - 24 ft	22.78-24.78 ft	180-121705-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-22-24	5/13/2021	856.49	857.15	0.66	-	22 - 24 ft	22.66-24.66 ft	180-121704-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-22-24	5/11/2021	852.98	852.99	0.01	-	22 - 24 ft	22.01-24.01 ft	180-121474-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-22-24	5/18/2021	856.45	856.26	-0.19	-	22 - 24 ft	21.81-23.81 ft	180-121822-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	0.041	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.041	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-22-24	5/14/2021	856.30	857.63	1.33	-	22 - 24 ft	23.33-25.33 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-22-24	5/13/2021	857.53	857.85	0.32	-	22 - 24 ft	22.32-24.32 ft	180-121704-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-22-24	5/12/2021	856.44	857.55	1.11	-	22 - 24 ft	23.11-25.11 ft	180-121548-2	Not Excavated	0.049	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.037 J	0.012 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-22-24	5/19/2021	856.98	855.02	-1.96	-	22 - 24 ft	20.04-22.04 ft	1801219031	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-22-24	5/7/2021	857.27	857.87	0.60	-	22 - 24 ft	22.6-24.6 ft	180-121355-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-22-24	5/10/2021	856.83	856.65	-0.18	-	22 - 24 ft	21.82-23.82 ft	180-121424-1	Not Excavated	0.037	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.037	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-22-24	5/10/2021	856.60	856.69	0.09	-	22 - 24 ft	22.09-24.09 ft	180-121424-1	Not Excavated	0.07	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	0.056 J	0.014 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	ND	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-22-24	5/11/2021	856.72	856.50	-0.22	-	22 - 24 ft	21.78-23.78 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-22-24	5/7/2021	857.06	856.73	-0.33	-	22 - 24 ft	21.67-23.67 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-22-24	6/10/2021	856.20	856.23	0.03	-	22 - 24 ft	22.03-24.03 ft	180-123098-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-22-24	6/11/2021	855.61	855.81	0.20	-	22 - 24 ft	22.2-24.2 ft	180-123134-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-22-24	5/15/2021	855.68	856.30	0.62	-	22 - 24 ft	22.62-24.62 ft	180-121747-1	Not Excavated	0.061	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	0.05 J	0.011 J	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-22-24	6/11/2021	855.12	855.85	0.73	-	22 - 24 ft	22.73-24.73 ft	180-123134-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.0060 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-22-24	5/12/2021	852.53	854.78	2.25	-	22 - 24 ft	24.25-26.25 ft	180-121548-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3919	SSHS-B3919-SUB-22-24	5/16/2021	852.79	854.90	2.11	-	22 - 24 ft	24.11-26.11 ft	180-121747-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-22-24	7/1/2021	853.40	855.25	1.85	-	22 - 24 ft	23.85-25.85 ft	180-123985-1	Not Excavated	0.224	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.19 J	0.034 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0060 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3896	SSHS-B3896-SUB-23-25	5/15/2021	854.53	854.89	0.36	-	23 - 25 ft	23.36-25.36 ft	180-121747-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

											PCBs									
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3897	SSHS-B3897-SUB-23-25	5/16/2021	855.21	855.33	0.12	-	23 - 25 ft	23.12-25.12 ft	180-121747-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	0.067	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	0.055	0.012 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3884	SSHS-B3884-SUB-24-25	5/11/2021	853.49	857.33	3.84	-	24 - 25 ft	27.84-28.84 ft	180-121474-1	Not Excavated	1.52	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	1.3 J	0.22 J	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-24-25	9/22/2021	854.12	856.10	1.98	-	24 - 25 ft	25.98-26.98 ft	180-127488-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3894	SSHS-B3894-SUB-24-25	5/11/2021	852.98	852.99	0.01	-	24 - 25 ft	24.01-25.01 ft	180-121474-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	0.0094	< 0.0060 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.0094 J	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3900	SSHS-B3900-SUB-24-25	5/14/2021	856.30	857.63	1.33	-	24 - 25 ft	25.33-26.33 ft	180-121705-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3912	SSHS-B3912-SUB-24-25	5/15/2021	855.68	856.30	0.62	-	24 - 25 ft	24.62-25.62 ft	180-121747-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	0.053	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.036 J	0.017 J	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-24-26	3/31/2021	855.62	856.75	1.13	-	24 - 26 ft	25.13-27.13 ft	180-119460-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-24-26	3/31/2021	856.45	857.00	0.55	-	24 - 26 ft	24.55-26.55 ft	180-119460-1	Not Excavated	0.033	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	0.033	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3886	SSHS-B3886-SUB-24-26	5/19/2021	854.47	855.96	1.49	-	24 - 26 ft	25.49-27.49 ft	180-121903-1	Not Excavated	0.017	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.017 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-24-26	5/15/2021	855.62	854.16	-1.46	-	24 - 26 ft	22.54-24.54 ft	180-121747-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-24-26	5/14/2021	855.59	856.04	0.45	-	24 - 26 ft	24.45-26.45 ft	180-121705-1	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-24-26	5/12/2021	856.79	856.60	-0.19	-	24 - 26 ft	23.81-25.81 ft	180-121548-1	Not Excavated	0.015	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.015 J	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	0.013	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.013 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-24-26	5/14/2021	856.33	857.11	0.78	-	24 - 26 ft	24.78-26.78 ft	180-121705-1	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-24-26	5/13/2021	856.49	857.15	0.66	-	24 - 26 ft	24.66-26.66 ft	180-121704-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3898	SSHS-B3898-SUB-24-26	5/18/2021	856.45	856.26	-0.19	-	24 - 26 ft	23.81-25.81 ft	180-121822-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	ND	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3901	SSHS-B3901-SUB-24-26	5/13/2021	857.53	857.85	0.32	-	24 - 26 ft	24.32-26.32 ft	180-121704-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0042 U	< 0.0026 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-24-26	5/12/2021	856.44	857.55	1.11	-	24 - 26 ft	25.11-27.11 ft	180-121548-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-24-26	5/19/2021	856.98	855.02	-1.96	-	24 - 26 ft	22.04-24.04 ft	1801219031	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-24-26	5/7/2021	857.27	857.87	0.60	-	24 - 26 ft	24.6-26.6 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-24-26	5/10/2021	856.83	856.65	-0.18	-	24 - 26 ft	23.82-25.82 ft	180-121424-1	Not Excavated	0.111	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.087 J	0.024 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-24-26	5/10/2021	856.60	856.69	0.09	-	24 - 26 ft	24.09-26.09 ft	180-121424-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-24-26	5/7/2021	857.27	857.87	0.60	-	24 - 26 ft	24.6-26.6 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-24-26	5/10/2021	856.83	856.65	-0.18	-	24 - 26 ft	23.82-25.82 ft	180-121424-1	Not Excavated	0.111	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.087 J	0.024 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-24-26	5/10/2021	856.60	856.69	0.09	-	24 - 26 ft	24.09-26.09 ft	180-121424-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-24-26	5/7/2021	857.27	857.87	0.60	-	24 - 26 ft	24.6-26.6 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-24-26	5/10/2021	856.83	856.65	-0.18	-	24 - 26 ft	23.82-25.82 ft	180-121424-1	Not Excavated	0.12	< 0.0058 U	< 0.0063 U	< 0.0044 U	< 0.0026 U	0.095 J	0.025 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-24-26	5/11/2021	856.60	856.69	0.09	-	24 - 26 ft	26.09-28.09 ft	180-121474-1	Not Excavated	0.146	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	0.12 J	0.026 J	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	25.9-27.9 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-24-26	5/12/2021	856.72	856.50	-0.22	-	24 - 26 ft	25.78-27.78 ft	180-121548-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-24-26	5/7/2021	857.06	856.73	-0.33	-	24 - 26 ft	25.67-27.67 ft	180-121355-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3910	SSHS-B3910-SUB-24-26	6/10/2021	856.20	856.23	0.03	-	24 - 26 ft	26.03-28.03 ft	180-123098-2	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-24-26	6/11/2021	855.61	855.81	0.20	-	24 - 26 ft	26.2-28.2 ft	180-123134-1	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3913	SSHS-B3913-SUB-24-26	6/11/2021	855.12	855.85	0.73	-	24 - 26 ft	26.73-28.73 ft	180-123134-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	26.31-28.31 ft	1801215481	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
											Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
											mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted											0.1									
Restricted - Residential											1									
Protection of Groundwater											3.2									
NYS Hazardous Waste											50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-26-28	5/12/2021	852.53	854.78	2.25	-	26 - 28 ft	28.25-30.25 ft	180-121548-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	930	< 6.5 U	< 7.1 U	< 4.9 U	< 2.9 U	650 J	280 J	< 5.7 U	< 7.1 U	< 2.7 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.0030 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0057 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3885	SSHS-B3885-SUB-27-29	9/22/2021	854.12	856.10	1.98	-	27 - 29 ft	28.98-30.98 ft	180-127488-1	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3888	SSHS-B3888-SUB-27-29	5/14/2021	855.59	856.04	0.45	-	27 - 29 ft	27.45-29.45 ft	180-121705-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	ND	< 0.0075 U	< 0.0081 U	< 0.0056 U	< 0.0034 U	< 0.0055 U	< 0.0069 U	< 0.0065 U	< 0.0081 U	< 0.0031 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-28-29	3/31/2021	855.62	856.75	1.13	-	28 - 29 ft	29.13-30.13 ft	180-119460-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-28-29	5/12/2021	856.72	856.50	-0.22	-	28 - 29 ft	27.78-28.78 ft	180-121548-1	Not Excavated	0.029	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	0.029	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0025 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-28-30	3/31/2021	856.45	857.00	0.55	-	28 - 30 ft	28.55-30.55 ft	180-119460-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0030 U	< 0.0050 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3887	SSHS-B3887-SUB-28-30	5/16/2021	855.62	854.16	-1.46	-	28 - 30 ft	26.54-28.54 ft	180-121747-1	Not Excavated	ND	< 0.0066 U	< 0.0071 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-28-30	5/12/2021	856.79	856.60	-0.19	-	28 - 30 ft	27.81-29.81 ft	180-121548-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	0.22	< 0.0060 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.16	0.06	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-28-30	5/14/2021	856.33	857.11	0.78	-	28 - 30 ft	28.78-30.78 ft	180-121705-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3893	SSHS-B3893-SUB-28-30	5/13/2021	856.49	857.15	0.66	-	28 - 30 ft	28.66-30.66 ft	180-121704-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	ND	< 0.0076 U	< 0.0082 U	< 0.0057 U	< 0.0034 U	< 0.0056 U	< 0.0070 U	< 0.0066 U	< 0.0082 U	< 0.0031 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-28-30	5/12/2021	856.44	857.55	1.11	-	28 - 30 ft	29.11-31.11 ft	180-121548-2	Not Excavated	0.034	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	0.034	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-28-30	5/19/2021	856.98	855.02	-1.96	-	28 - 30 ft	26.04-28.04 ft	1801219031	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-28-30	5/7/2021	857.27	857.87	0.60	-	28 - 30 ft	28.6-30.6 ft	180-121355-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-28-30	5/10/2021	856.83	856.65	-0.18	-	28 - 30 ft	27.82-29.82 ft	180-121424-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0027 U	< 0.0044 U	< 0.0054 U	< 0.0052 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-28-30	5/11/2021	856.60	856.69	0.09	-	28 - 30 ft	28.09-30.09 ft	180-121474-1	Not Excavated	0.023	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.023	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	ND	< 0.0064 U	< 0.0070 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-28-30	5/7/2021	857.06	856.73	-0.33	-	28 - 30 ft	27.67-29.67 ft	180-121355-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0055 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3911	SSHS-B3911-SUB-28-30	6/11/2021	855.61	855.81	0.20	-	28 - 30 ft	28.2-30.2 ft	180-123134-1	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3916	SSHS-B3916-SUB-28-30	5/12/2021	852.53	854.78	2.25	-	28 - 30 ft	30.25-32.25 ft	180-121548-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0048 U	< 0.0061 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	176.6	< 0.64 U	< 0.7 U	< 0.48 U	< 0.29 U	120 J	53 J	3.6 J	< 0.69 U	< 0.26 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-29-30	3/31/2021	855.62	856.75	1.13	-	29 - 30 ft	30.13-31.13 ft	180-119460-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3908	SSHS-B3908-SUB-29-31	5/12/2021	856.72	856.50	-0.22	-	29 - 31 ft	28.78-30.78 ft	180-121548-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0051 U	< 0.0031 U	< 0.0051 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-30-31	5/14/2021	856.33	857.11	0.78	-	30 - 31 ft	30.78-31.78 ft	180-121705-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-30-31	5/19/2021	856.98	855.02	-1.96	-	30 - 31 ft	28.04-29.04 ft	1801219031	Not Excavated	ND	< 0.0058 U	< 0.0063 U	< 0.0043 U	< 0.0026 U	< 0.0043 U	< 0.0053 U	< 0.0050 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.034 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-30-32	4/1/2021	855.62	856.75	1.13	-	30 - 32 ft	31.13-33.13 ft	180-119460-1	Not Excavated	0.068	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.05 J	0.018 J	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-30-32	3/31/2021	856.45	857.00	0.55	-	30 - 32 ft	30.55-32.55 ft	180-119460-1	Not Excavated	0.03	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	0.03	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-30-32	5/12/2021	856.79	856.60	-0.19	-	30 - 32 ft	29.81-31.81 ft	180-121548-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3902	SSHS-B3902-SUB-30-32	5/12/2021	856.44	857.55	1.11	-	30 - 32 ft	31.11-33.11 ft	180-121548-2	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0067 U	< 0.0063 U	< 0.0078 U	< 0.003 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-30-32	5/7/2021	857.27	857.87	0.60	-	30 - 32 ft	30.6-32.6 ft	180-121355-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0027 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-30-32	5/10/2021	856.83	856.65	-0.18	-	30 - 32 ft	29.82-31.82 ft	180-121424-1	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U		< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-30-32	5/11/2021	856.60	856.69	0.09	-	30 - 32 ft	30.09-32.09 ft	180-121474-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.0050 U	< 0.0063 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-30-32	5/7/2021	857.06	856.73	-0.33	-	30 - 32 ft	29.67-31.67 ft	180-121355-1	Not Excavated	ND	< 0.0062 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0046 U	< 0.0057 U	< 0.0054 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	12.9	< 0.068 U	< 0.075 U	< 0.051 U	< 0.031 U	9.9 J	2.7 J	0.3 J	< 0.074 U	< 0.028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	ND	< 0.0067 U	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3892	SSHS-B3892-SUB-31-33	5/14/2021	856.33	857.11	0.78	-	31 - 33 ft	31.78-33.78 ft	180-121705-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	ND	< 0.0067 UT	< 0.0073 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	< 0.0062 U	< 0.0058 UT	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3868	SSHS-B3868-SUB-32-33	4/1/2021	855.62	856.75	1.13	-	32 - 33 ft	33.13-34.13 ft	180-119460-2	Not Excavated	ND	< 0.0065 U	< 0.007 U	< 0.0048 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.007 U	< 0.0027 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-32-33	5/7/2021	857.27	857.87	0.60	-	32 - 33 ft	32.6-33.6 ft	180-121355-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	ND	< 0.006 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0044 U	< 0.0056 U	< 0.0053 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-32-34	3/31/2021	856.45	857.00	0.55	-	32 - 34 ft	32.55-34.55 ft	180-119460-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0052 U	< 0.0031 U	< 0.0052 U	< 0.0064 U	< 0.0061 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3890	SSHS-B3890-SUB-32-34	5/12/2021	856.79	856.60	-0.19	-	32 - 34 ft	31.81-33.81 ft	180-121548-1	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.005 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0072 U	< 0.0027 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-32-34	5/10/2021	856.83	856.65	-0.18	-	32 - 34 ft	31.82-33.82 ft	180-121424-1	Not Excavated	0.176	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.14 J	0.036 J	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-32-34	5/11/2021	856.60	856.69	0.09	-	32 - 34 ft	32.09-34.09 ft	180-121474-1	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Northern Athletic Field	SSHS-B3909	SSHS-B3909-SUB-32-34	5/7/2021	857.06	856.73	-0.33	-	32 - 34 ft	31.67-33.67 ft	180-121355-1	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.003 U	< 0.005 U	< 0.0062 U	< 0.0059 U	< 0.0073 U	< 0.0028 U
Northern Athletic Field	SSHS-B3904	SSHS-B3904-SUB-33-35	5/7/2021	857.27	857.87	0.60	-	33 - 35 ft	33.6-35.6 ft	180-121355-1	Not Excavated	ND	< 0.0072 U	< 0.0078 U	< 0.0054 U	< 0.0032 U	< 0.0053 U	< 0.0066 U	< 0.0063 U	< 0.0077 U	< 0.003 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.034 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	ND	< 0.0062 U	< 0.0068 U	< 0.0047 U	< 0.0028 U	< 0.0046 U	< 0.0058 U	< 0.0055 U	< 0.0067 U	< 0.0026 U
Northern Athletic Field	SSHS-B3869	SSHS-B3869-SUB-34-36	3/31/2021	856.45	857.00	0.55	-	34 - 36 ft	34.55-36.55 ft	180-119460-2	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0028 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-34-36	5/10/2021	856.83	856.65	-0.18	-	34 - 36 ft	33.82-35.82 ft	180-121424-1	Not Excavated	0.028	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.0029 U	0.028	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-34-36	5/11/2021	856.60	856.69	0.09	-	34 - 36 ft	34.09-36.09 ft	180-121474-1	Not Excavated	0.012	< 0.0059 U	< 0.0065 U	< 0.0044 U	< 0.0027 U	0.012 J	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	ND	< 0.0064 U	< 0.007 U	< 0.0048 U	< 0.034 U	< 0.0047 U	< 0.0059 U	< 0.0056 U	< 0.0069 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3905	SSHS-B3905-SUB-36-38	5/10/2021	856.83	856.65	-0.18	-	36 - 38 ft	35.82-37.82 ft	180-121424-1	Not Excavated	0.026	< 0.0067 U	< 0.0073 U	< 0.005 U	< 0.003 U	0.026	< 0.0062 U	< 0.0059 U	< 0.0072 U	< 0.0028 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-36-38	5/11/2021	856.60	856.69	0.09	-	36 - 38 ft	36.09-38.09 ft	180-121474-1	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.0026 U	< 0.0042 U	< 0.0053 U	< 0.005 U	< 0.0062 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.034 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	0.444	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	0.31 J	0.11 J	0.024 J	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-38-40	5/11/2021	856.60	856.69	0.09	-	38 - 40 ft	38.09-40.09 ft	180-121474-1	Not Excavated	ND	< 0.0061 U	< 0.0067 U	< 0.0046 U	< 0.0028 U	< 0.0045 U	< 0.0056 U	< 0.0054 U	< 0.0066 U	< 0.0025 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-40-41	5/11/2021	856.60	856.69	0.09	-	40 - 41 ft	40.09-41.09 ft	180-121474-1	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	ND	< 0.0078 U	< 0.0085 U	< 0.0058 U	< 0.0035 U	< 0.0057 U	< 0.0072 U	< 0.0068 U	< 0.0084 U	< 0.0032 U
Northern Athletic Field	SSHS-B3906	SSHS-B3906-SUB-41-43	5/11/2021	856.60	856.69	0.09	-	41 - 43 ft	41.09-43.09 ft	180-121474-1	Not Excavated	ND	< 0.007 U	< 0.0076 U	< 0.0053 U	< 0.0032 U	< 0.0052 U	< 0.0065 U	< 0.0061 U	< 0.0076 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	ND	< 0.0061 U	< 0.0066 U	< 0.0045 U	< 0.0027 U	< 0.0045 U	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U

TABLE 6-4A
Deep Soil Results Remaining in Place - PCBs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												PCBs								
												Total PCBs	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.1									
Restricted - Residential												1									
Protection of Groundwater												3.2									
NYS Hazardous Waste												50									
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	ND	< 0.006 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0065 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	ND	< 0.0069 U	< 0.0075 U	< 0.0052 U	< 0.0031 U	< 0.0051 U	< 0.0064 U	< 0.006 U	< 0.0075 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	ND	< 0.0059 U	< 0.0065 U	< 0.0045 U	< 0.0027 U	< 0.0044 U	< 0.0055 U	< 0.0052 U	< 0.0064 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	ND	< 0.0065 U	< 0.0071 U	< 0.0049 U	< 0.0029 U	< 0.0048 U	< 0.006 U	< 0.0057 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	ND	< 0.0066 U	< 0.0072 U	< 0.0049 U	< 0.003 U	< 0.0049 U	< 0.0061 U	< 0.0058 U	< 0.0071 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	ND	< 0.0068 U	< 0.0074 U	< 0.0051 U	< 0.0031 U	< 0.005 U	< 0.0063 U	< 0.006 U	< 0.0074 U	< 0.0028 U
Rear Parking Lot	SSHS-B1009	SSHS-B1009-SUB-14-16	4/24/2018	852.00	852.29	0.29	-	14 - 16 ft	14.29-16.29 ft	180-77059-1	Not Excavated	0.616	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.45	0.14	0.026	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1026	SSHS-B1026-SUB-14-16	4/24/2018	852.10	852.15	0.05	-	14 - 16 ft	14.05-16.05 ft	180-77059-1	Not Excavated	33.2	< 0.07 U	< 0.14 U	< 0.13 U	< 0.13 U	21	10	2.2	< 0.15 U	< 0.1 U
Rear Parking Lot	SSHS-B1091	SSHS-B1091-SUB-14-16	7/6/2018	851.86	852.06	0.20	-	14 - 16 ft	14.20-16.20 ft	180-79550-1	Not Excavated	ND	< 0.0069 U	< 0.014 U	< 0.013 U	< 0.013 U	< 0.017 U	< 0.015 U	< 0.006 U	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated	0.022	< 0.0064 U	< 0.013 U	< 0.012 U	< 0.012 U	< 0.016 U	0.022	< 0.0056 U	< 0.014 U	< 0.0096 U
Rear Parking Lot	SSHS-B1092	SSHS-B1092-SUB-14-16-DUP	7/6/2018	852.20	852.41	0.21	-	14 - 16 ft	14.21-16.21 ft	180-79550-1	Not Excavated	0.183	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.089 J	0.094 J	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated	0.173	< 0.0066 U	< 0.013 U	< 0.012 U	< 0.012 U	0.096 J	0.058 J	0.019 J	< 0.014 U	< 0.0098 U
Rear Parking Lot	SSHS-B1093	SSHS-B1093-SUB-14-16-DUP	7/6/2018	851.97	852.05	0.08	-	14 - 16 ft	14.08-16.08 ft	180-79550-1	Not Excavated	0.075	< 0.0068 U	< 0.014 U	< 0.012 U	< 0.013 U	< 0.017 U	0.049 J	0.026 J	< 0.015 U	< 0.01 U
Rear Parking Lot	SSHS-B1094	SSHS-B1094-SUB-14-16	7/6/2018	851.75	851.77	0.02	-	14 - 16 ft	14.02-16.02 ft	180-79550-1	Not Excavated	0.037	< 0.0062 U	< 0.012 U	< 0.011 U	< 0.011 U	0.037	< 0.013 U	< 0.0054 U	< 0.013 U	< 0.0092 U
Rear Parking Lot	SPA4-B5505	SSHS-SPA4-B5505-ELEV-834-832	8/12/2024	849.89	849.89	0.00	-	15.89-17.89 ft	15.89-17.89 ft	1801782961	Not Excavated	0.062	< 0.0066 U	< 0.0072 U	< 0.0050 U	< 0.0030 U	< 0.0049 U	0.062	< 0.0058 U	< 0.0072 U	< 0.0027 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	ND	< 0.0063 U	< 0.0069 U	< 0.0047 U	< 0.0028 U	< 0.0047 U	< 0.0058 U	< 0.0055 U	< 0.0068 U	< 0.0026 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	ND	< 0.0059 U	< 0.0064 U	< 0.0044 U	< 0.0026 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0064 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	ND	< 0.0093 U	< 0.0091 U	< 0.007 U	< 0.014 U	< 0.0084 U	< 0.0077 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	ND	< 0.0095 U	< 0.0092 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	ND	< 0.0095 U	< 0.0093 U	< 0.0071 U	< 0.014 U	< 0.0085 U	< 0.0078 U	< 0.012 U	< 0.013 U	< 0.0054 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	ND	< 0.0057 U	< 0.0062 U	< 0.0043 U	< 0.034 U	< 0.0042 U	< 0.0052 U	< 0.005 U	< 0.0061 U	< 0.0023 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	0.04	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	0.027 J	0.013 J	< 0.0053 U	< 0.0066 U	< 0.0025 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	ND	< 0.0058 U	< 0.0064 U	< 0.0044 U	< 0.034 U	< 0.0043 U	< 0.0054 U	< 0.0051 U	< 0.0063 U	< 0.0024 U
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	0.011	< 0.0061 U	< 0.0066 U	< 0.0046 U	< 0.034 U	0.011 J	< 0.0056 U	< 0.0053 U	< 0.0066 U	< 0.0025 U

DRAFT

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated												
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated	4800	< 0.34 U	4.5	42	0.19 J	0.099 J	26000	6.4		4.3 J	14	11000
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	3800	< 0.35 U	3.6	41	0.16 J	0.074 J	33000	6.1		3.6 J	14	10000
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated	5800	< 0.37 UJ	4.2	40	0.24 J	0.065 J	32000	11		5.2 J	17	13000 J
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			8.8	163	< 0.61 U	< 0.61 U		13.3			64.7	
Football Field	SSHS-IRM3-B025	073019 09:00_SSHS-IRM3-B025-C	SSHS-IRM3-B025-C	7/29/2019	-	856.34	-	840.21	16 - 18 ft	16.13 ft	180-93352-1	Not Excavated	6100	< 0.38 U	4.6 J	48	0.24 J	0.071 J	7700 J	7.4		5.3 J	30 J-	15000
Football Field	IRM4A-B024	SSHS-IRM4A-B024-20201012	SSHS-IRM4A-B024	10/12/2020	-	855.72	-	839.40	16 - 18 ft	16.32 ft	1801121371	Not Excavated	5300	< 0.39 U	4.9	39	0.25 J	0.075 J	13000	7.1		5.0	19	13000
Football Field	SSHS-B3555	011221 09:45_DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	5200	< 0.37 U	3.9	31	0.19 J	0.11 J	20000 J	9.3		5 J	19	14000
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	4200	< 0.36 U	3.9	24	0.18 J	0.16 J	41000 J	9.2		4 J	16	11000
Football Field	SSHS-B3557	011221 09:45_DUP-23	DUP-23	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	4200	< 0.34 U	3.3	22	0.18 J	0.1 J	19000 J	11		3.8 J	15	11000
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	4400	< 0.37 U	3.2	30	0.21 J	0.14 J	40000 J	6.6		3.8 J	14	12000
Football Field	SSHS-B3560	011221 09:45_DUP-26	DUP-26	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	5100	0.75 J	3.7	31	0.18 J	0.1 J	31000	12 J		6.4	21	13000
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	4800	2.9 J	3.8	36	0.18 J	0.087 J	23000	25 J		6.6	30	13000
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-16-18	SSHS-B3563-SUB-16-18	1/11/2021	855.01	855.38	0.37	-	16 - 18 ft	16.37-18.37 ft	180-115815-1	Not Excavated	6100	< 0.34 U	4.9	32	0.22 J	0.12 J	29000	9.2		5.5	20	14000
Football Field	SSHS-B3558	011321 09:00_DUP-24	DUP-24	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-2	Not Excavated	3300	< 0.35 U	3.3	20	0.16 J	0.11 J	44000	5.2		3 J	13	8100
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	4000	< 0.36 U	3.8	23	0.17 J	0.11 J	49000	5.1		3.5 J	13	10000
Football Field	SSHS-B3559	011321 09:00_DUP-25	DUP-25	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-2	Not Excavated	6100	< 0.37 U	4.7	75	0.26 J	0.14 J	40000	10		5.1 J	37	13000
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	4400	< 0.36 U	3.8	43 J	0.19 J	0.14 J	57000	6.7		4 J	20 J	12000
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-16-18	SSHS-B3564-SUB-16-18	1/12/2021	855.22	855.42	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115861-1	Not Excavated	5700	< 0.36 U	4.6	34	0.24 J	0.13 J	28000	9		5 J	29	13000
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	3200	< 0.37 U	2.8	20 J	0.15 J	0.077 J	35000	4.3		3 J	10	7500
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-16-18	SSHS-B3566-SUB-16-18	1/12/2021	855.28	855.43	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115861-2	Not Excavated	4400	< 0.34 U	4	54	0.18 J	0.075 J	19000	6.2		3.9 J	14	11000
Football Field	SSHS-B3556	011421 08:45_DUP-22	DUP-22	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated	5000	< 0.34 U	3.5	37 J	0.24 J	0.088 J	7200	8		4.2 J	18	10000
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-16-18	SSHS-B3556-SUB-16-18	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated	5100	< 0.37 U	4	87 J	0.23 J	0.076 J	5700	7.9		4.2 J	18	12000
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	4900	< 0.38 U	4.9	25	0.21 J	0.12 J	28000	8.2		4.6 J	16	12000
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	5700	< 0.37 U	5.1	44	0.23 J	0.099 J	22000	10		4.8 J	22	13000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	4800	< 0.28 U	2.9	32	0.18 J	0.068 J	21000	26		4.1 J	11	12000
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-16-18	SSHS-B3571-SUB-16-18	1/18/2021	855.21	855.30	0.09	-	16 - 18 ft	16.09-18.09 ft	180-116109-1	Not Excavated	4800	< 0.34 U	2.8	26	0.18 J	0.11 J	44000	8.5		4.2 J	15	12000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-16-18	SSHS-B3569-SUB-16-18	1/19/2021	855.07	855.22	0.15	-	16 - 18 ft	16.15-18.15 ft	180-116199-1	Not Excavated	4300	< 0.34 U	4.7	20	0.19 J	0.089 J	24000	6.7		4 J	14	9800
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-16-18	SSHS-B3570-SUB-16-18	1/19/2021	855.27	855.46	0.19	-	16 - 18 ft	16.19-18.19 ft	180-116199-1	Not Excavated	6500	< 0.36 U	4.4	38	0.25 J	0.15 J	41000	13		5.7	19	16000
Football Field	IRM4A-B028	SSHS-IRM4A-B028-20210210	SSHS-IRM4A-B028	2/10/2021	-	855.58		839.06	16 - 18 ft	16.51 ft	1801171671	Not Excavated	4500	< 0.34 UT	3.7	15 J	0.15 J	0.081 J	14000	5.4		3.7 J	18	11000
Football Field	IRM4A-B029	SSHS-IRM4A-B029-20210210	SSHS-IRM4A-B029	2/10/2021	-	855.56	-	839.14	16 - 18 ft	16.42 ft	1801171671	Not Excavated	1700	< 0.29 U	4.3	3.9 J	0.057 J	< 0.031 U	830	1.9		1.3 J	3.8	4200
Football Field	IRM4A-B027	SSHS-IRM4A-B027-20210210	SSHS-IRM4A-B027	2/10/2021	-	855.51	-	839.12	16 - 18 ft	16.39 ft	1801171671	Not Excavated	2600	< 0.36 U	4.0	8.7 J	0.073 J	0.042 J	4500	3.0		3.2 J	40	6500
Football Field	IRM4A-MOAB BOT1	SSHS-IRM4A-MOAB BOT1-20210302	SSHS-IRM4A-MOAB BOT1	3/2/2021	-	855.36	-	839.24	16 - 18 ft	16.12 ft	1801177751	Not Excavated	5100	< 0.44 U	3.7	31	0.20 J	0.097 J	21000	7.0		4.4 J	15	11000
Football Field	IRM4A-MOAB BOT 3	SSHS-IRM4A-MOAB BOT3-20210302	SSHS-IRM4A-MOAB BOT3	3/2/2021	-	855.57	-	839.01	16 - 18 ft	16.56 ft	1801177751	Not Excavated	7900	< 0.33 U	6.4	130	0.29 J	0.14 J	17000	11		6.8	26	19000
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	3900	< 0.32 U	3.8	39	0.12 J	0.096 J	54000	6.3		3.8 J	12	11000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16 - 18 ft	180-119767-1	Not Excavated	6000	0.74 J	4.9	30	0.26 J	0.12 J	1400	9.1		4.5 J	16	13000
Football Field	SSHS-B3864	041021 10:00_DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	2900	< 0.32 UJ	2.9	22	0.13 J	0.084 J	27000	5		3 J	11	7000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	3600	0.57 J	3.1	25	0.16 J	0.12 J	19000	6.2		3.5 J	14	8300
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	4400	1.2	8.2	82	0.27 J	0.22 J	17000	17		4.9 J	78	31000
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	4000	1.9	12	110	0.28 J	0.31 J	13000	23		5.3	110	51000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	5800	< 0.33 U	4.8	26	0.25 J	0.12 J	8600	7.7		5.6	19	13000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	3800	< 0.034 U	2.9	19 J	0.14 J	0.11 J	41000 J	5.1		3.3 J	13 J	8800
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	5800	< 0.034 U	6.2 J	44	0.29 J	0.12 J	34000 J	7		6	24	15000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	7400	0.37 J	11 J	58	0.33 J	0.053 J	19000 J	9.3		7.3	18	17000
Football Field	IRM5-A4V BOT A	SSHS-IRM5-A4V BOT A-20210502	SSHS-IRM5-A4V BOT A	5/2/2021	-	855.46	-	838.74	16 - 18 ft	16.71 ft	1801210181	Not Excavated	2700	< 0.32 U	2.7	14 J	< 0.048 U	0.058 J	36000	100 B		2.6	13	6500
Football Field	IRM5-DELTA BOT 2	SSHS-IRM5-DELTA BOT 2-20210520	SSHS-IRM5-DELTA BOT 2	5/20/2021	-	855.58	-	838.25	16 - 18 ft	17.33 ft	1801219611	Not Excavated	5400	< 0.35 U	3.8	30	0.17 J	0.11 J	11000	6.4		4.6	20	12000
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	5200	< 0.39 U	4.1	24	0.21 J	< 0.042 U	4500	7.4		4.8 J	25	14000
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	6100	1.8	5.1	34	0.25 J	0.076 J	17000	7.9		5.8 J	28	14000
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	3300	< 0.35 U	3.5	18 J	0.15 J	0.065 J	18000	4.5		3.2 J	17	8400
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	6200	8.8 T	5.7	46	0.29 J	0.092 J	1800 T	8.3		5.2 J	99 T	14000
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	5300	2.8	9.4	49	0.25 J	0.38 J	9400	16		8.3	110	51000
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	8200	1.8	4.6	66	0.32 J	0.078 J	4900	11		5.5	62	18000
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	4200	< 0.36 U	3.2	31	0.19 J	0.038 J	5300	6.5		3.4 J	24	9400
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	4700	< 0.36 U	4.0	22	0.20 J	< 0.038 U	5000	5.8		4.6 J	20	10000
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	4300	< 0.34 U	4.0	21	0.17 J	0.044 J	13000	5.4		4.4 J	26	9400
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	9100	0.45 J	5.1	55	0.42 J	< 0.040 U	1200	13		10	25	18000
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	11000	< 0.35 U	8.1	70	0.44	< 0.038 U	810	15		10	30	20000
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	8200	< 0.35 U	4.8	53	0.39 J	< 0.037 U	1200	11		7.5	23	17000
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	9100	< 0.34 U	6.2	58	0.41	< 0.037 U	1200	12		8.9	20	17000
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	4200	< 0.33 U	3.4	19	0.17 J	0.058 J	28000	5.6		4.4 J	17	8900
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	4500	< 0.34 U	3.7	28	0.20 J	0.045 J	9800	6.3		4.0 J	22	10000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	4700	< 0.034 U	3.4	34	0.16 J	0.064 J	33000	8.7		3.9 J	21	11000
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	13000	< 0.034 U	8.4	87	0.45 J	< 0.034 U	40000	16		9.5	35	27000
Football Field	SSHS-B4165	092421 10:00_DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	6600	< 0.034 U	4.9	50	0.24 J	0.056 J	41000	8.4		5.4	22 J	15000
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	4400	< 0.034 U	4.1	44	0.21 J	0.1 J	55000	6.5		4.1	13 J	12000
Football Field	IRM5-FIS-BOT64	SSHS-IRM5-FIS-BOT64-20211008	SSHS-IRM5-FIS-BOT64	10/8/2021	-	855.62	-	838.76	16 - 18 ft	16.86 ft	1801282871	Not Excavated	3900	< 0.36 U	3.2	23	0.14 J	0.10 J	87000	5.6		3.7	22	8300
Football Field	IRM5-FIS-BOT65	SSHS-IRM5-FIS-BOT65-20211008	SSHS-IRM5-FIS-BOT65	10/8/2021	-	855.17	-	838.91	16 - 18 ft	16.26 ft	1801282871	Not Excavated	6900	< 0.34 U	6.6	53	0.30 J	0.11 J	29000	9.5		6.3	26	15000
Football Field	IRM5-FIS-BOT66	SSHS-IRM5-FIS-BOT66-20211008	SSHS-IRM5-FIS-BOT66	10/8/2021	-	855.21	-	838.91	16 - 18 ft	16.31 ft	1801282871	Not Excavated	3300	< 0.36 U	2.7	31	0.14 J	0.076 J	58000	6.2		3.2	21	7300
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated			2.3	21.6	< 0.56 U	< 0.56 U		4.6			12.4	
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	3000	< 0.38 U	2.3	20 J	0.12 J	0.13 J	99000	4.9		2.7 J	15	8000
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	4000	< 0.34 U	2.9	26	0.17 J	0.11 J	83000	6.1		3.9 J	14	10000
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-18-20	SSHS-B3560-SUB-18-20	1/11/2021	855.32	855.47	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115815-1	Not Excavated	4200	1.2 J-	4.1	25	0.17 J	0.11 J	35000	7		3.7 J	16	9900
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	4500	< 0.37 U	3.6	29	0.16 J	0.11 J	38000	7.1		4 J	18	11000
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	5500	< 0.36 U	5.8	43	0.23 J	0.1 J	31000	6.8		4.9 J	18	13000

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated										25 J	
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated	8.4	9200	330	< 0.022 U	57	720	< 0.52 U	< 0.11 U	100 J		< 0.32 U
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	12	13000	450	< 0.019 U	21	610	< 0.53 U	< 0.11 U	87 J		< 0.33 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated	6.5	9900	360	< 0.021 U	14	770	< 0.56 U	< 0.11 U	88 J		< 0.35 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	74.1			< 0.06 U	114		< 0.6 U	< 1.22 U			
Football Field	SSHS-IRM3-B025	073019 09:00_SSHS-IRM3-B025-C	SSHS-IRM3-B025-C	7/29/2019	-	856.34	-	840.21	16 - 18 ft	16.13 ft	180-93352-1	Not Excavated	6.6	4800 J	380	< 0.013 R	13		< 0.57 U	< 0.12 U	90 J		< 0.36 U
Football Field	IRM4A-B024	SSHS-IRM4A-B024-20201012	SSHS-IRM4A-B024	10/12/2020	-	855.72	-	839.40	16 - 18 ft	16.32 ft	1801121371	Not Excavated	9.4	5800	340	< 0.023 U	13	720	< 0.50 U	< 0.087 U	< 67 U		1.8 J
Football Field	SSHS-B3555	011221 09:45_DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	7	6100	460	< 0.023 U	13	680	< 0.56 U	< 0.11 U	93 J		< 0.35 U
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	8.3	10000	620	< 0.024 U	11	700	< 0.55 U	< 0.11 U	99 J		< 0.34 U
Football Field	SSHS-B3557	011221 09:45_DUP-23	DUP-23	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	9.5	5300 J	460 J	< 0.021 U	11	590	< 0.52 U	< 0.11 U	80 J		< 0.32 U
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	11	9700 J	910 J	< 0.019 U	11	840	< 0.56 U	< 0.11 U	120 J		< 0.35 U
Football Field	SSHS-B3560	011221 09:45_DUP-26	DUP-26	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	6.4	6900	350	< 0.02 U	18	790	< 0.54 U	< 0.11 U	99 J		< 0.33 U
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	6.2	6500	300	< 0.021 U	21	830	< 0.53 U	< 0.11 U	88 J		< 0.33 U
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-16-18	SSHS-B3563-SUB-16-18	1/11/2021	855.01	855.38	0.37	-	16 - 18 ft	16.37-18.37 ft	180-115815-1	Not Excavated	11	8000	380	< 0.019 U	14	910	< 0.51 U	< 0.11 U	110 J		< 0.32 U
Football Field	SSHS-B3558	011321 09:00_DUP-24	DUP-24	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-2	Not Excavated	9.7	15000	440	< 0.021 U	8.1	640	< 0.52 U	< 0.11 U	86 J		< 0.33 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	13	14000	620	< 0.019 U	9.4	710	0.57 J	< 0.11 U	82 J		< 0.34 U
Football Field	SSHS-B3559	011321 09:00_DUP-25	DUP-25	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-2	Not Excavated	250	10000	560	< 0.019 U	63	830	< 0.56 U	< 0.12 U	150 J		< 0.35 U
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	85 J	16000	730	< 0.02 U	69	770	< 0.55 U	< 0.11 U	130 J		< 0.34 U
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-16-18	SSHS-B3564-SUB-16-18	1/12/2021	855.22	855.42	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115861-1	Not Excavated	10	10000	310	< 0.023 U	20	810	< 0.55 U	< 0.11 U	110 J		< 0.34 U
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	5.1	11000	310	< 0.023 U	7.4	610	< 0.56 U	< 0.11 U	91 J		< 0.35 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-16-18	SSHS-B3566-SUB-16-18	1/12/2021	855.28	855.43	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115861-2	Not Excavated	8.6	4900	210	< 0.022 U	50	560	< 0.51 U	< 0.1 U	88 J		< 0.32 U
Football Field	SSHS-B3556	011421 08:45_DUP-22	DUP-22	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated	9.4	2200	200	< 0.019 U	81	640	< 0.52 U	< 0.11 U	74 J		< 0.33 U
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-16-18	SSHS-B3556-SUB-16-18	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated	12	3200	310	< 0.019 U	56	630	< 0.56 U	< 0.11 U	76 J		< 0.35 U
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	9.2	7500	480	< 0.02 U	18	750	< 0.57 U	< 0.12 U	82 J		< 0.36 U
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	120	3800	290	< 0.021 U	26	680	0.79 J	< 0.11 U	92 J		< 0.35 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	5	4000	260	< 0.02 U	11	570	< 0.43 U	< 0.088 U	76 J		< 0.27 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-16-18	SSHS-B3571-SUB-16-18	1/18/2021	855.21	855.30	0.09	-	16 - 18 ft	16.09-18.09 ft	180-116109-1	Not Excavated	5.7	16000	420	< 0.022 U	10	620	< 0.52 U	< 0.11 U	75 J		< 0.32 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-16-18	SSHS-B3569-SUB-16-18	1/19/2021	855.07	855.22	0.15	-	16 - 18 ft	16.15-18.15 ft	180-116199-1	Not Excavated	5.8	8500	410	< 0.022 U	10	650	< 0.52 U	< 0.11 U	75 J		< 0.32 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-16-18	SSHS-B3570-SUB-16-18	1/19/2021	855.27	855.46	0.19	-	16 - 18 ft	16.19-18.19 ft	180-116199-1	Not Excavated	8.4	8900	550	< 0.023 U	17	810	0.63 J	< 0.11 U	120 J		< 0.34 U
Football Field	IRM4A-B028	SSHS-IRM4A-B028-20210210	SSHS-IRM4A-B028	2/10/2021	-	855.58	-	839.06	16 - 18 ft	16.51 ft	1801171671	Not Excavated	8.0	7000 T	370	< 0.023 UT	11	510	< 0.51 U	< 0.11 U	65 J		< 0.32 U
Football Field	IRM4A-B029	SSHS-IRM4A-B029-20210210	SSHS-IRM4A-B029	2/10/2021	-	855.56	-	839.14	16 - 18 ft	16.42 ft	1801171671	Not Excavated	4.4	840	40	< 0.021 U	3.2 J	100 J	< 0.44 U	< 0.089 U	< 51 U		< 0.27 U
Football Field	IRM4A-B027	SSHS-IRM4A-B027-20210210	SSHS-IRM4A-B027	2/10/2021	-	855.51	-	839.12	16 - 18 ft	16.39 ft	1801171671	Not Excavated	1.8	2300	140	< 0.022 U	7.4	230 J	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Football Field	IRM4A-MOAB BOT1	SSHS-IRM4A-MOAB BOT1-20210302	SSHS-IRM4A-MOAB BOT1	3/2/2021	-	855.36	-	839.24	16 - 18 ft	16.12 ft	1801177751	Not Excavated	7.0	4100	340	< 0.023 U	13	650	< 0.67 U	< 0.14 U	95 J		< 0.41 U
Football Field	IRM4A-MOAB BOT 3	SSHS-IRM4A-MOAB BOT3-20210302	SSHS-IRM4A-MOAB BOT3	3/2/2021	-	855.57	-	839.01	16 - 18 ft	16.56 ft	1801177751	Not Excavated	28	4200	320	< 0.023 U	29	720	< 0.50 U	< 0.10 U	110 J		< 0.31 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	4.2	7400	600	0.025 J	9.6	520	0.82 J	< 0.099 U	110 J		< 0.30 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	11	2100	520	< 0.024 U	20	1100	< 0.51 U	< 0.1 U	< 60 U		< 0.32 U
Football Field	SSHS-B3864	041021 10:00_DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	6.3	11000	560	< 0.022 U	10	500	< 0.49 U	< 0.1 U	78 J		< 0.3 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	6.1	8500	520	< 0.023 U	12	590	< 0.48 U	< 0.098 U	81 J		< 0.3 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	75	4200	360	0.14	29	600	0.65 J	< 0.11 U	91 J		< 0.32 U
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	94	3100	370	0.18	37	510	0.6 J	< 0.09 U	100 J		< 0.27 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	7.3	2600	390	< 0.024 U	15	650	< 0.5 U	< 0.1 U	230 J		< 0.31 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	5.3	8100 J	420	< 0.034 U	8.7	490 J	< 0.034 U	< 0.034 U	110 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	9.8	15000 J	720	< 0.034 U	15	950	0.51 J	< 0.034 U	120 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	14	7100 J	460	< 0.034 U	19	980	< 0.034 U	< 0.034 U	87 J		< 0.034 U
Football Field	IRM5-A4V BOT A	SSHS-IRM5-A4V BOT A-20210502	SSHS-IRM5-A4V BOT A	5/2/2021	-	855.46	-	838.74	16 - 18 ft	16.71 ft	1801210181	Not Excavated	5.0	7600	300	< 0.023 U	7.1	330 J	< 0.41 U	< 0.071 U	74 J		< 0.35 U
Football Field	IRM5-DELTA BOT 2	SSHS-IRM5-DELTA BOT 2-20210520	SSHS-IRM5-DELTA BOT 2	5/20/2021	-	855.58	-	838.25	16 - 18 ft	17.33 ft	1801219611	Not Excavated	6.4	5000	1000	< 0.019 U	12	580	< 0.46 U	0.12 J	64 J		< 0.39 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	9.6	2700	320	< 0.018 U	13	420 J	< 0.60 U	< 0.12 U	< 70 U		< 0.37 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	17	4500	380	< 0.024 U	16	560 J	< 0.60 U	< 0.12 U	< 71 U		< 0.38 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	7.1	3600	340	0.056	9.1	420 J	< 0.54 U	< 0.11 U	< 63 U		< 0.33 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	32 T	1900	610	0.067	39	910	< 0.55 U	< 0.11 U	76 J		0.40 J
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	56	2200	570	0.029	18	470 J	< 0.53 U	< 0.11 U	< 62 U		< 0.66 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	47	2700	240	0.081	22	570	< 0.54 U	< 0.11 U	< 63 U		0.34 J
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	16	2700	300	< 0.026 U	11	510 J	< 0.54 U	< 0.11 U	66 J		< 0.34 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	6.3	3400	300	< 0.017 U	11	460 J	< 0.54 U	< 0.11 U	< 63 U		< 0.34 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	6.7	4600	440	< 0.023 U	11	450 J	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	13	2700	240	< 0.022 U	22	990	< 0.57 U	< 0.12 U	< 67 U		< 0.35 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	17	3100	330	< 0.021 U	31	970	< 0.53 U	< 0.11 U	< 62 U		0.35 J
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	12	2400	410	< 0.024 U	23	1200	< 0.52 U	< 0.11 U	64 J		0.40 J
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	12	2800	210	< 0.024 U	21	1300	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	4.9	4000	310	< 0.023 U	11	420 J	< 0.49 U	< 0.10 U	< 58 U		< 0.31 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	15	3200	320	< 0.023 U	12	490 J	< 0.52 U	< 0.11 U	< 61 U		< 0.32 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	6.5	13000	370	< 0.034 U	14	620	< 0.034 U	< 0.034 U	84 J		< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	14	12000	720	< 0.034 U	26	1300	< 0.034 U	< 0.034 U	240 J		< 0.034 U
Football Field	SSHS-B4165	092421 10:00_DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	7.3	14000	570	< 0.034 U	15	690	0.66 J	< 0.034 U	89 J		< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	7	8500	430	< 0.034 U	11	660	0.62 J	< 0.034 U	85 J		< 0.034 U
Football Field	IRM5-FIS-BOT64	SSHS-IRM5-FIS-BOT64-20211008	SSHS-IRM5-FIS-BOT64	10/8/2021	-	855.62	-	838.76	16 - 18 ft	16.86 ft	1801282871	Not Excavated	6.5	22000	380	< 0.019 U	37	550	< 0.48 U	< 0.082 U	93 J		< 0.41 U
Football Field	IRM5-FIS-BOT65	SSHS-IRM5-FIS-BOT65-20211008	SSHS-IRM5-FIS-BOT65	10/8/2021	-	855.17	-	838.91	16 - 18 ft	16.26 ft	1801282871	Not Excavated	8.5	5100	380	< 0.020 U	21	830	< 0.44 U	< 0.077 U	< 59 U		< 0.38 U
Football Field	IRM5-FIS-BOT66	SSHS-IRM5-FIS-BOT66-20211008	SSHS-IRM5-FIS-BOT66	10/8/2021	-	855.21	-	838.91	16 - 18 ft	16.31 ft	1801282871	Not Excavated	5.2	4900	480	< 0.022 U	35	440 J	< 0.47 U	< 0.082 U	< 63 U		< 0.40 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	8.1			< 0.05 U	9.7		< 0.55 U	< 1.12 U			
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	8.6	44000	760	< 0.021 U	7.4	570	0.87 J	< 0.12 U	230 J		< 0.35 U
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	7	6700	440	< 0.021 U	9.9	660	0.78 J	< 0.11 U	110 J		< 0.32 U
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-18-20	SSHS-B3560-SUB-18-20	1/11/2021	855.32	855.47	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115815-1	Not Excavated	6	8800 J-	410	< 0.018 U	9.6	680	< 0.54 U	< 0.11 U	96 J		< 0.34 U
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	9.1	10000	480	< 0.022 U	10	620	< 0.56 U	< 0.12 U	96 J		< 0.35 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	7.2	5300	330	< 0.021 U	12	910	< 0.55 U	< 0.11 U	100 J		< 0.34 U

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B2679	042519 08:35_SSHS-B2679-SUB-14-16	SSHS-B2679-SUB-14-16	4/24/2019	855.15	855.37	0.22	-	14 - 16 ft	14.22-16.22 ft	180-89408-2	Not Excavated			
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-14-16	SSHS-B3566-SUB-14-16	1/12/2021	855.28	855.43	0.15	-	14 - 16 ft	14.15-16.15 ft	180-115861-1	Not Excavated		7.6	48
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated		7.4	35
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-14-16	SSHS-B3563A-SUB-14-16	1/13/2021	855.01	855.38	0.37	-	14 - 16 ft	14.37-16.37 ft	180-115999-1	Not Excavated		8.9	49 J-
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			161
Football Field	SSHS-IRM3-B025	073019 09:00_SSHS-IRM3-B025-C	SSHS-IRM3-B025-C	7/29/2019	-	856.34	-	840.21	16 - 18 ft	16.13 ft	180-93352-1	Not Excavated		9.7	59 J-
Football Field	IRM4A-B024	SSHS-IRM4A-B024-20201012	SSHS-IRM4A-B024	10/12/2020	-	855.72	-	839.40	16 - 18 ft	16.32 ft	1801121371	Not Excavated		9.2	63
Football Field	SSHS-B3555	011221 09:45_DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated		10	53
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated		8.3	45
Football Field	SSHS-B3557	011221 09:45_DUP-23	DUP-23	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated		7.6	41
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated		9.2	45
Football Field	SSHS-B3560	011221 09:45_DUP-26	DUP-26	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated		13	48
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated		15	43
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-16-18	SSHS-B3563-SUB-16-18	1/11/2021	855.01	855.38	0.37	-	16 - 18 ft	16.37-18.37 ft	180-115815-1	Not Excavated		10	110
Football Field	SSHS-B3558	011321 09:00_DUP-24	DUP-24	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-2	Not Excavated		6.7	35
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated		7	39
Football Field	SSHS-B3559	011321 09:00_DUP-25	DUP-25	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-2	Not Excavated		12	58
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated		8.4	41
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-16-18	SSHS-B3564-SUB-16-18	1/12/2021	855.22	855.42	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115861-1	Not Excavated		8.9	57
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated		6.2	35
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-16-18	SSHS-B3566-SUB-16-18	1/12/2021	855.28	855.43	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115861-2	Not Excavated		7.9	39
Football Field	SSHS-B3556	011421 08:45_DUP-22	DUP-22	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated		8.1	48
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-16-18	SSHS-B3556-SUB-16-18	1/13/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	180-115925-1	Not Excavated		8.2	47
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated		9	61
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated		8.6	51
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated		8.5	39
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-16-18	SSHS-B3571-SUB-16-18	1/18/2021	855.21	855.30	0.09	-	16 - 18 ft	16.09-18.09 ft	180-116109-1	Not Excavated		8.1	45
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-16-18	SSHS-B3569-SUB-16-18	1/19/2021	855.07	855.22	0.15	-	16 - 18 ft	16.15-18.15 ft	180-116199-1	Not Excavated		6.8	42
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-16-18	SSHS-B3570-SUB-16-18	1/19/2021	855.27	855.46	0.19	-	16 - 18 ft	16.19-18.19 ft	180-116199-1	Not Excavated		11	62
Football Field	IRM4A-B028	SSHS-IRM4A-B028-20210210	SSHS-IRM4A-B028	2/10/2021	-	855.58	-	839.06	16 - 18 ft	16.51 ft	1801171671	Not Excavated		8.0	36 T
Football Field	IRM4A-B029	SSHS-IRM4A-B029-20210210	SSHS-IRM4A-B029	2/10/2021	-	855.56	-	839.14	16 - 18 ft	16.42 ft	1801171671	Not Excavated		2.1 J	22
Football Field	IRM4A-B027	SSHS-IRM4A-B027-20210210	SSHS-IRM4A-B027	2/10/2021	-	855.51	-	839.12	16 - 18 ft	16.39 ft	1801171671	Not Excavated		5.2	24
Football Field	IRM4A-MOAB BOT1	SSHS-IRM4A-MOAB BOT1-20210302	SSHS-IRM4A-MOAB BOT1	3/2/2021	-	855.36	-	839.24	16 - 18 ft	16.12 ft	1801177751	Not Excavated		9.7	45
Football Field	IRM4A-MOAB BOT 3	SSHS-IRM4A-MOAB BOT3-20210302	SSHS-IRM4A-MOAB BOT3	3/2/2021	-	855.57	-	839.01	16 - 18 ft	16.56 ft	1801177751	Not Excavated		12	77
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated		7.3	44
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated		8.8	84
Football Field	SSHS-B3864	041021 10:00_DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated		4.6 J	32
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated		6.1 J	42
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated		11	80
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated		13	99
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated		9.4	61
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated		6.1	38
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated		9.8	45
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated		11	43
Football Field	IRM5-A4V BOT A	SSHS-IRM5-A4V BOT A-20210502	SSHS-IRM5-A4V BOT A	5/2/2021	-	855.46	-	838.74	16 - 18 ft	16.71 ft	1801210181	Not Excavated		4.3 J	31
Football Field	IRM5-DELTA BOT 2	SSHS-IRM5-DELTA BOT 2-20210520	SSHS-IRM5-DELTA BOT 2	5/20/2021	-	855.58	-	838.25	16 - 18 ft	17.33 ft	1801219611	Not Excavated		8.9	67
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated		10	59
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated		11	69
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated		6.4	44
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated		11	85 T
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated		32	88
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated		13	83
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated		7.2	47
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated		7.4	49
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated		7.6	44
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated		16	72
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated		18	130
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated		14	52
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated		15	57
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated		6.7	49
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated		7.8	48
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated		8.4	39
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated		20	95
Football Field	SSHS-B4165	092421 10:00_DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated		10	55
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated		7.2	37
Football Field	IRM5-FIS-BOT64	SSHS-IRM5-FIS-BOT64-20211008	SSHS-IRM5-FIS-BOT64	10/8/2021	-	855.62	-	838.76	16 - 18 ft	16.86 ft	1801282871	Not Excavated		6.6	50
Football Field	IRM5-FIS-BOT65	SSHS-IRM5-FIS-BOT65-20211008	SSHS-IRM5-FIS-BOT65	10/8/2021	-	855.17	-	838.91	16 - 18 ft	16.26 ft	1801282871	Not Excavated		10	57
Football Field	IRM5-FIS-BOT66	SSHS-IRM5-FIS-BOT66-20211008	SSHS-IRM5-FIS-BOT66	10/8/2021	-	855.21	-	838.91	16 - 18 ft	16.31 ft	1801282871	Not Excavated		5.3	53
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated			37.3
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated		5.6	29
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated		6.5	47
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-18-20	SSHS-B3560-SUB-18-20	1/11/2021	855.32	855.47	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115815-1	Not Excavated		7.6	44 J+
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated		6.9	50
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated		11	52

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	5300	< 0.36 U	4.2	29	0.19 J	0.079 J	30000	6.2		4.3 J	19	13000
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	4600	< 0.35 U	3.2	33	0.19 J	0.096 J	37000	5.8		4 J	14	11000
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	6900	< 0.35 U	5.7	52	0.31 J	0.087 J	18000	8.5		6.2	18	18000
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	6600	< 0.33 U	6.2	45	0.23 J	0.097 J	20000	9.7		5.7	22	17000
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	7000	< 0.36 U	4.4	29	0.29 J	0.18 J	26000	16		6.6	210	16000
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	5100	< 0.38 UJ	4	33	0.18 J	0.11 J	44000 J	7.9		4.2 J	15	12000
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-18-20	SSHS-B3562-SUB-18-20	1/13/2021	855.07	855.40	0.33	-	18 - 20 ft	18.33-20.33 ft	180-115925-1	Not Excavated	5400	< 0.35 U	4.8	31	0.19 J	0.12 J	37000	7.5		5.2	21	13000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	4200	< 0.27 U	3.3	31	0.18 J	0.13 J	71000	9.6		3.7 J	18	9600
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-18-20	SSHS-B3571-SUB-18-20	1/18/2021	855.21	855.30	0.09	-	18 - 20 ft	18.09-20.09 ft	180-116109-1	Not Excavated	4600	< 0.34 U	3.3	19 J	0.17 J	0.081 J	25000	6.2		3.9 J	14	11000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	2200	< 0.35 U	2	11 J	0.098 J	0.051 J	23000	3.9		1.8 J	7.8	5100
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	6700	< 0.35 U	3.8	35	0.24 J	0.087 J	18000	9.3		5.2	20	16000
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	3200	< 0.35 U	3.0	20	0.12 J	0.11 J	42000	5.3		2.8 J	15	8500
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	3100	< 0.25 U	2.3	32	0.12 J	0.085 J	26000	4.5		2.5 J	13	6800
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	5700	0.34 J	4.6	62	0.25 J	0.13 J	15000	16		6.1	64	22000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	4600	< 0.29 U	4.3	21	0.17 J	0.093 J	24000	19		3.9 J	40	10000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	4900	< 0.27 U	4.1	25	0.21 J	0.15 J	19000	7.6		4.7	14	12000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	2900	2	3.7	17 J	0.12 J	0.32 J	32000	4.3		2.8 J	10	7500
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	5600	< 0.034 U	3.9	31	0.22 J	0.089 J	23000	7.5		5 J	14	13000
Football Field	IRM5-A4V SOUTH A	SSHS-IRM5-A4V SOUTH A-20210502	SSHS-IRM5-A4V SOUTH A	5/2/2021	-	855.57	-	835.58	18 - 20 ft	19.99 ft	1801210181	Not Excavated	3600	< 0.33 U	2.5	26	< 0.050 U	0.058 J	46000	9.3 B		3.3	16	8800
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	6000	< 0.034 U	3.5	29	0.2 J	< 0.034 U	38000	13		4.8 J	19	14000
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	8300	< 0.034 U	4	44	0.28 J	< 0.034 U	25000	11		5.5	20	15000
Football Field	SSHS-B4165	092421 10:00_DUP-39	DUP-39	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	5900	< 0.034 U	3.6	37 J	0.22 J	0.092 J	57000 J	7.5		5.1	17	12000
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	6300	< 0.034 U	3.8	41	0.23 J	0.044 J	22000 J	9		5.1	24	14000
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-20-22	SSHS-B3555-SUB-20-22	1/11/2021	855.30	855.33	0.03	-	20 - 22 ft	20.03-22.03 ft	180-115815-1	Not Excavated	5000	< 0.37 U	6.4	31	0.18 J	0.12 J	52000	7.7		4.7 J	25	13000
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-20-22	SSHS-B3557-SUB-20-22	1/11/2021	855.18	855.38	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115815-1	Not Excavated	5200	< 0.34 U	4	31	0.2 J	0.14 J	41000	8		5.2	20	12000
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-20-22	SSHS-B3560-SUB-20-22	1/11/2021	855.32	855.47	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115815-1	Not Excavated	5300	< 0.34 U	3.6	28	0.19 J	0.13 J	44000	6.9		4.7 J	18	12000
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-20-22	SSHS-B3563-SUB-20-22	1/11/2021	855.01	855.38	0.37	-	20 - 22 ft	20.37-22.37 ft	180-115815-1	Not Excavated	6900	< 0.37 U	4.3	39	0.23 J	0.11 J	37000	18		5.8	27	16000
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	4000	< 0.36 U	3	24	0.17 J	0.072 J	23000	5.3		3.2 J	11	8400
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-20-22	SSHS-B3559-SUB-20-22	1/12/2021	855.35	855.36	0.01	-	20 - 22 ft	20.01-22.01 ft	180-115861-1	Not Excavated	5100	< 0.34 U	3.5	33	0.19 J	0.089 J	29000	6.6		4 J	22	12000
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-20-22	SSHS-B3564-SUB-20-22	1/12/2021	855.22	855.42	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115861-1	Not Excavated	4900	< 0.38 U	4.2	32	0.19 J	0.079 J	29000	7.4		4.9 J	16	12000
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-20-22	SSHS-B3565-SUB-20-22	1/12/2021	855.32	855.45	0.13	-	20 - 22 ft	20.13-22.13 ft	180-115861-2	Not Excavated	6300	< 0.36 U	4	37	0.24 J	0.12 J	37000	9.8		5.4	23	16000
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-20-22	SSHS-B3566-SUB-20-22	1/12/2021	855.28	855.43	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115861-2	Not Excavated	5500	< 0.35 U	3.1	31	0.21 J	0.11 J	41000	7.2		4.8 J	19	13000
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-20-22	SSHS-B3556-SUB-20-22	1/13/2021	855.33	855.47	0.14	-	20 - 22 ft	20.14-22.14 ft	180-115925-1	Not Excavated	5000	< 0.37 U	8	26	0.19 J	0.11 J	33000	7.3		10	16	32000
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-20-22	SSHS-B3561-SUB-20-22	1/13/2021	855.17	855.41	0.24	-	20 - 22 ft	20.24-22.24 ft	180-115925-1	Not Excavated	6700	< 0.37 U	4.2	39	0.2 J	0.1 J	36000	14		6.4	18	16000
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-20-22	SSHS-B3562-SUB-20-22	1/13/2021	855.07	855.40	0.33	-	20 - 22 ft	20.33-22.33 ft	180-115925-1	Not Excavated	5100	< 0.35 U	3.8	32	0.17 J	0.08 J	29000	6.9		4.8 J	12	12000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-20-22	SSHS-B3568-SUB-20-22	1/18/2021	855.08	855.49	0.41	-	20 - 22 ft	20.41-22.41 ft	180-116109-1	Not Excavated	3400	< 0.36 U	1.9	27	0.15 J	0.056 J	45000	5.3		3.8 J	14	9300
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-20-22	SSHS-B3571-SUB-20-22	1/18/2021	855.21	855.30	0.09	-	20 - 22 ft	20.09-22.09 ft	180-116109-1	Not Excavated	2600	< 0.42 U	2.9	17 J	0.12 J	< 0.045 U	27000	4		2.7 J	11	7000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-20-22	SSHS-B3569-SUB-20-22	1/19/2021	855.07	855.22	0.15	-	20 - 22 ft	20.15-22.15 ft	180-116199-1	Not Excavated	5700	< 0.39 U	3.3	29	0.2 J	0.07 J	21000	7.2		4.2 J	17	14000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	6500	< 0.36 U	4.2	39	0.24 J	0.068 J	19000	9.6		5.5	19	15000
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	3500	< 0.38 U	2.5	22	0.13 J	0.081 J	57000	5.5		3.1 J	13	8500
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	3800	< 0.29 U	2.8	29	0.14 J	0.13 J	57000	5.8		3.3 J	16	8700
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	4500	0.54 J	3.3	26	0.17 J	0.083 J	11000	74		4 J	19	10000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	4300	< 0.32 U	3.2	23	0.18 J	0.14 J	44000	11		3.7 J	39	9900
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	7500	0.31 J	4.1	77	0.28 J	0.11 J	5800	9.9		5.7	23	15000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	420	< 0.034 U	0.76 J	4.4 J	< 0.034 U	0.11 J	220000	0.95		0.53 J	5.1	1100
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	4200	< 0.4 U	3.6	23 J	0.2 J	0.097 J	35000	5.8		4.1 J	16	11000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	3800	< 0.034 U	3.2	25	0.16 J	0.096 J	34000	5.5		3.4 J	13	9200
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	4400	< 0.034 U	4.3	25	0.16 J	0.13 J	30000	7		3.8 J	18	11000
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-22-24	SSHS-B3555-SUB-22-24	1/11/2021	855.30	855.33	0.03	-	22 - 24 ft	22.03-24.03 ft	180-115815-1	Not Excavated	7700	< 0.36 U	5.8	45	0.28 J	0.13 J	31000	13		7.2	33	18000
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-22-24	SSHS-B3557-SUB-22-24	1/11/2021	855.18	855.38	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115815-1	Not Excavated	6100	< 0.34 U	4.2	37	0.22 J	0.13 J	44000	8.1		5.3	20	13000
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-22-24	SSHS-B3560-SUB-22-24	1/11/2021	855.32	855.47	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115815-1	Not Excavated	4600	< 0.38 U	3.5	29	0.18 J	0.11 J	49000	7.6		3.9 J	19	12000
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-22-24	SSHS-B3563-SUB-22-24	1/11/2021	855.01	855.38	0.37	-	22 - 24 ft	22.37-24.37 ft	180-115815-1	Not Excavated	4200	< 0.34 U	3.7	40	0.17 J	0.1 J	48000	7.3		3.6 J	14	11000
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-22-24	SSHS-B3558-SUB-22-24	1/12/2021	855.27	855.53	0.26	-	22 - 24 ft	22.26-24.26 ft	180-115861-1	Not Excavated	4300	< 0.37 U	3.4	23	0.17 J	0.15 J	44000	6.6		3.7 J	15	9500
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-22-24	SSHS-B3559-SUB-22-24	1/12/2021	855.35	855.36	0.01	-	22 - 24 ft	22.01-24.01 ft	180-115861-1	Not Excavated	4500	< 0.36 U	4.4	30	0.2 J	0.082 J	35000	6.4		3.8 J	17	12000
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-22-24	SSHS-B3564-SUB-22-24	1/12/2021	855.22	855.42	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115861-1	Not Excavated	5800	< 0.37 U	4.1	32	0.21 J	0.098 J	32000	9.2		5 J	20	14000
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-22-24	SSHS-B3566-SUB-22-24	1/12/2021	855.28	855.43	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115861-2	Not Excavated	6800	< 0.36 U	3.3	35	0.24 J	0.12 J	60000	7.9		5.5	33	17000
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-22-24	SSHS-B3556-SUB-22-24	1/13/2021	855.33	855.47	0.14	-	22 - 24 ft	22.14-24.14 ft	180-115925-1	Not Excavated	5100	< 0.34 U	3.4	21	0.19 J	0.1 J	35000	6.6		5.5	21	15000
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-22-24	SSHS-B3561-SUB-22-24	1/13/2021	855.17	855.41	0.24	-	22 - 24 ft	22.24-24.24 ft	180-115925-1	Not Excavated	4900	< 0.35 U	3.5	29	0.19 J	0.16 J	52000	6.9		4.7 J	15	11000
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-22-24	SSHS-B3562-SUB-22-24	1/13/2021	855.07	855.40	0.33	-	22 - 24 ft	22.33-24.33 ft	180-115925-1	Not Excavated	6300	< 0.35 U	3.5	39	0.2 J	0.099 J	37000	11		4.7 J	21	14000
Football Field	SSHS-B3565	011421 08:45_SSHS-B3565-SUB-22-24	SSHS-B3565-SUB-22-24	1/13/2021	855.32	855.45	0.13	-	22 - 24 ft	22.13-24.13 ft	180-115925-1	Not Excavated	5200	< 0.34 U	3.8	37	0.17 J	0.087 J	37000	7.9		4.3 J	17	12000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-22-24	SSHS-B3568-SUB-22-24	1/18/2021	855.08	855.49	0.41	-	22 - 24 ft	22.41-24.41 ft	180-116109-1	Not Excavated	4100	< 0.27 U	2.7	24	0.14 J	0.065 J	15000	5.5		3.1 J	13	9500
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-22-24	SSHS-B3571-SUB-22-24	1/18/2021	855.21	855.30	0.09	-	22 - 24 ft	22.09-24.09 ft	180-116109-1	Not Excavated	5900	< 0.3 U	2.9	35	0.19 J	0.061 J	19000	7.5		4.7	17	13000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-22-24	SSHS-B3569-SUB-22-24	1/19/2021	855.07	855.22	0.15	-	22 - 24 ft	22.15-24.15 ft	180-116199-1	Not Excavated	4900	< 0.38 U	3.8	39	0.19 J	0.089 J	43000	7.3		4.3 J	20	12000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-22-24	SSHS-B3570-SUB-22-24	1/19/2021	855.27	855.46	0.19	-	22 - 24 ft	22.19-24.19 ft	180-116199-1	Not Excavated	5200	< 0.36 U	3.8	30	0.19 J	0.11 J	39000	8.8		4.4 J	19	13000
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	5000	< 0.35 U	4.0	35	0.21 J	0.081 J	35000	7.1		4.5 J	13	12000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	4700	< 0.25 U	8.6	31	0.16 J	0.18 J	35000	7		5.3	67	12000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	4300	< 0.26 U	3.7	23	0.16 J	0.085 J	17000	45		3.6 J	20	10000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	3000	< 0.32 U	2.8	20	0.13 J	0.09 J	84000	6.4		2.5 J	21	6800
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	3800	< 0.33 U	3.2	29	0.16 J	0.11 J	76000	6.4		3.8 J	15	9900
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	4200	< 0.034 U	1.9	30	0.15 J	0.13 J	130000	5.3		4.6 J	12	12000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	4600	< 0.034 U	5.3	28	0.19 J	0.087 J	45000	6.6		4.7 J	12	11000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	4300	< 0.034 U	4.7	28	0.18 J	0.92	48000	5.3		4.2 J	21	9900
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-24-26	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	855.38	0.37	-	24 - 26 ft	24.37-26.37 ft	180-115999-1	Not Excavated	5100	< 0.35 U	3.1	33	0.2 J	0.082 J	32000	6.7		4.6 J	19	12000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-24-26	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	855.42	0.20	-	24 - 26 ft	24.2-26.2 ft	180-116070-1	Not Excavated	5300	< 0.38 U	4.3	44	0.29 J	0.15 J	85000	28		4.7 J	18	14000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	8.5	6700	350	< 0.02 U	48	660	< 0.54 U	< 0.11 U	84 J		< 0.34 U
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	6.9	14000	410	< 0.019 U	12	720	< 0.52 U	< 0.11 U	120 J		< 0.33 U
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	8.8	4300	320	< 0.022 U	16	790	< 0.53 U	< 0.11 U	82 J		< 0.33 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	18	5300	240	< 0.022 U	18	740	< 0.5 U	< 0.1 U	82 J		< 0.31 U
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	9.2	4400	320	< 0.023 U	210	550	0.59 J	< 0.11 U	73 J		< 0.34 U
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	8.9	16000 J	520	< 0.019 U	11	660	< 0.57 U	< 0.12 U	120 J		< 0.35 U
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-18-20	SSHS-B3562-SUB-18-20	1/13/2021	855.07	855.40	0.33	-	18 - 20 ft	18.33-20.33 ft	180-115925-1	Not Excavated	7.4	7000	320	< 0.018 U	14	580	< 0.54 U	< 0.11 U	76 J		< 0.33 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	8	20000	400	< 0.025 U	11	730	0.78 J	< 0.084 U	120 J		< 0.26 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-18-20	SSHS-B3571-SUB-18-20	1/18/2021	855.21	855.30	0.09	-	18 - 20 ft	18.09-20.09 ft	180-116109-1	Not Excavated	12	5800	270	< 0.02 U	9.8	560	< 0.51 U	< 0.1 U	75 J		< 0.32 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	2.5	3500	270	< 0.023 U	5	420 J	0.63 J	< 0.11 U	< 62 U		< 0.33 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	6.1	4600	340	< 0.022 U	14	700	< 0.52 U	< 0.11 U	73 J		< 0.33 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	4.5	15000	370	< 0.023 U	7.8	440 J	< 0.53 U	< 0.11 U	90 J		< 0.33 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	5.4	4900	510	< 0.018 U	23	500	0.44 J	< 0.078 U	63 J		< 0.24 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	47	5200	350	< 0.02 U	38	630	< 0.38 U	< 0.078 U	94 J		< 0.24 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	7.9	4500	310	< 0.018 U	13	520	< 0.44 U	< 0.09 U	71 J		< 0.28 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	7	3500	620	< 0.023 U	12	580	< 0.4 U	< 0.082 U	210 J		< 0.25 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	4.9	3100	230	< 0.034 U	7	390 J	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	7.1	6100	330	< 0.034 U	14	690	< 0.034 U	< 0.034 U	79 J		< 0.034 U
Football Field	IRM5-A4V SOUTH A	SSHS-IRM5-A4V SOUTH A-20210502	SSHS-IRM5-A4V SOUTH A	5/2/2021	-	855.57	-	835.58	18 - 20 ft	19.99 ft	1801210181	Not Excavated	4.4	3100	320	0.024 J	9.1	400 J	< 0.44 U	< 0.076 U	64 J		< 0.37 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	8.5	8900	290	< 0.034 U	23	630	< 0.034 U	< 0.034 U	66 J		< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	9.8	5000	310	< 0.034 U	15	740	< 0.034 U	< 0.034 U	250 J		< 0.034 U
Football Field	SSHS-B4165	092421 10:00_DUP-39	DUP-39	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	7.1	5600 J-	370 J	< 0.034 U	14	730 J-	0.47 J	< 0.034 U	81 J		< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	7.2	4700	440	< 0.034 U	13	600	< 0.034 U	< 0.034 U	74 J		< 0.034 U
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-20-22	SSHS-B3555-SUB-20-22	1/11/2021	855.30	855.33	0.03	-	20 - 22 ft	20.03-22.03 ft	180-115815-1	Not Excavated	5.8	8500	640	< 0.022 U	13	580	< 0.56 U	< 0.11 U	96 J		< 0.35 U
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-20-22	SSHS-B3557-SUB-20-22	1/11/2021	855.18	855.38	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115815-1	Not Excavated	6.7	6300	550	< 0.021 U	13	680	< 0.52 J	< 0.11 U	91 J		< 0.32 U
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-20-22	SSHS-B3560-SUB-20-22	1/11/2021	855.32	855.47	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115815-1	Not Excavated	5.6	4200	230	< 0.019 U	13	680	0.55 J	< 0.11 U	93 J		< 0.32 U
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-20-22	SSHS-B3563-SUB-20-22	1/11/2021	855.01	855.38	0.37	-	20 - 22 ft	20.37-22.37 ft	180-115815-1	Not Excavated	6	6500	460	< 0.02 U	16	830	< 0.57 U	< 0.12 U	110 J		< 0.35 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	14	5500	300	< 0.02 U	9.6	620	< 0.54 U	< 0.11 U	88 J		< 0.34 U
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-20-22	SSHS-B3559-SUB-20-22	1/12/2021	855.35	855.36	0.01	-	20 - 22 ft	20.01-22.01 ft	180-115861-1	Not Excavated	4.9	4200	270	< 0.019 U	19	630	< 0.52 U	< 0.11 U	81 J		< 0.33 U
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-20-22	SSHS-B3564-SUB-20-22	1/12/2021	855.22	855.42	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115861-1	Not Excavated	8.4	3600	300	< 0.024 U	13	550 J	< 0.58 U	< 0.12 U	89 J		< 0.36 U
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-20-22	SSHS-B3565-SUB-20-22	1/12/2021	855.32	855.45	0.13	-	20 - 22 ft	20.13-22.13 ft	180-115861-2	Not Excavated	6.4	5300	390	< 0.023 U	14	680	< 0.54 U	< 0.11 U	110 J		< 0.34 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-20-22	SSHS-B3566-SUB-20-22	1/12/2021	855.28	855.43	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115861-2	Not Excavated	5.9	4900	330	< 0.017 U	13	670	0.68 J	< 0.11 U	100 J		< 0.33 U
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-20-22	SSHS-B3556-SUB-20-22	1/13/2021	855.33	855.47	0.14	-	20 - 22 ft	20.14-22.14 ft	180-115925-1	Not Excavated	6.9	16000	950	< 0.021 U	730	660	< 0.56 U	< 0.11 U	94 J		< 0.35 U
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-20-22	SSHS-B3561-SUB-20-22	1/13/2021	855.17	855.41	0.24	-	20 - 22 ft	20.24-22.24 ft	180-115925-1	Not Excavated	8.7	6400	440	< 0.023 U	19	570	0.62 J	< 0.12 U	85 J		< 0.35 U
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-20-22	SSHS-B3562-SUB-20-22	1/13/2021	855.07	855.40	0.33	-	20 - 22 ft	20.33-22.33 ft	180-115925-1	Not Excavated	9.3	5700	250	< 0.018 U	14	530	0.53 J	< 0.11 U	78 J		< 0.33 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-20-22	SSHS-B3568-SUB-20-22	1/18/2021	855.08	855.49	0.41	-	20 - 22 ft	20.41-22.41 ft	180-116109-1	Not Excavated	3.3	9300	970	< 0.023 U	9	420 J	< 0.55 U	< 0.11 U	79 J		< 0.34 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-20-22	SSHS-B3571-SUB-20-22	1/18/2021	855.21	855.30	0.09	-	20 - 22 ft	20.09-22.09 ft	180-116109-1	Not Excavated	2.7	4400	240	< 0.03 U	6.7	390 J	< 0.64 U	< 0.13 U	< 75 U		< 0.4 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-20-22	SSHS-B3569-SUB-20-22	1/19/2021	855.07	855.22	0.15	-	20 - 22 ft	20.15-22.15 ft	180-116199-1	Not Excavated	3.6	6700	180	< 0.022 U	12	520 J	< 0.59 U	< 0.12 U	< 70 U		< 0.37 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	6.9	5800	230	< 0.021 U	14	690	< 0.54 U	< 0.11 U	78 J		< 0.34 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	4.2	8000	280	< 0.023 U	8.3	530 J	0.80 J	< 0.12 U	82 J		< 0.36 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	7.3	3600	470	< 0.019 U	20	660	0.68 J	< 0.091 U	74 J		< 0.28 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	6.6	2700	260	< 0.02 U	22	540	< 0.42 U	< 0.086 U	63 J		< 0.26 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	6.2	6300	350	< 0.018 U	15	530	0.63 J	< 0.098 U	84 J		< 0.3 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	21	3200	390	< 0.018 U	15	650	< 0.45 U	< 0.092 U	200 J		< 0.28 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.034 U	2400	130	< 0.034 U	2 J	180 J	2.2	< 0.034 U	68 J		< 0.034 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	5	4200	240	< 0.021 U	10	580 J	< 0.61 U	< 0.12 U	73 J		< 0.38 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	4.2	5400	270	< 0.034 U	9	550 J	0.61 J	< 0.034 U	75 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	12	11000	360	< 0.034 U	11	490	< 0.034 U	< 0.034 U	75 J		< 0.034 U
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-22-24	SSHS-B3555-SUB-22-24	1/11/2021	855.30	855.33	0.03	-	22 - 24 ft	22.03-24.03 ft	180-115815-1	Not Excavated	9.5	9400	410	< 0.022 U	19	800	< 0.54 U	< 0.11 U	170 J		< 0.34 U
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-22-24	SSHS-B3557-SUB-22-24	1/11/2021	855.18	855.38	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115815-1	Not Excavated	6.5	7700	350	< 0.018 U	14	710	< 0.52 U	< 0.11 U	120 J		< 0.32 U
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-22-24	SSHS-B3560-SUB-22-24	1/11/2021	855.32	855.47	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115815-1	Not Excavated	5.6	6800	300	< 0.024 U	11	580	0.6 J	< 0.12 U	99 J		< 0.36 U
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-22-24	SSHS-B3563-SUB-22-24	1/11/2021	855.01	855.38	0.37	-	22 - 24 ft	22.37-24.37 ft	180-115815-1	Not Excavated	4.9	5900	310	< 0.022 U	9.8	610	< 0.51 U	< 0.11 U	100 J		< 0.32 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-22-24	SSHS-B3558-SUB-22-24	1/12/2021	855.27	855.53	0.26	-	22 - 24 ft	22.26-24.26 ft	180-115861-1	Not Excavated	5.3	4900	350	< 0.02 U	10	540	< 0.56 U	< 0.11 U	77 J		< 0.35 U
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-22-24	SSHS-B3559-SUB-22-24	1/12/2021	855.35	855.36	0.01	-	22 - 24 ft	22.01-24.01 ft	180-115861-1	Not Excavated	6.2	9500	360	< 0.019 U	13	600	< 0.54 U	< 0.11 U	82 J		< 0.34 U
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-22-24	SSHS-B3564-SUB-22-24	1/12/2021	855.22	855.42	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115861-1	Not Excavated	5.6	4400	260	< 0.021 U	15	600	< 0.56 U	< 0.12 U	80 J		< 0.35 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-22-24	SSHS-B3566-SUB-22-24	1/12/2021	855.28	855.43	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115861-2	Not Excavated	5.3	3800	560	< 0.02 U	16	530	< 0.55 U	< 0.11 U	76 J		< 0.34 U
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-22-24	SSHS-B3556-SUB-22-24	1/13/2021	855.33	855.47	0.14	-	22 - 24 ft	22.14-24.14 ft	180-115925-1	Not Excavated	5.8	8600	380	< 0.022 U	190	590	0.8 J	< 0.11 U	89 J		< 0.33 U
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-22-24	SSHS-B3561-SUB-22-24	1/13/2021	855.17	855.41	0.24	-	22 - 24 ft	22.24-24.24 ft	180-115925-1	Not Excavated	5.7	5800	460	< 0.021 U	13	690	0.74 J	< 0.11 U	88 J		< 0.33 U
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-22-24	SSHS-B3562-SUB-22-24	1/13/2021	855.07	855.40	0.33	-	22 - 24 ft	22.33-24.33 ft	180-115925-1	Not Excavated	6.9	9500	410	< 0.02 U	25	850	< 0.52 U	< 0.11 U	95 J		< 0.33 U
Football Field	SSHS-B3565	011421 08:45_SSHS-B3565-SUB-22-24	SSHS-B3565-SUB-22-24	1/13/2021	855.32	855.45	0.13	-	22 - 24 ft	22.13-24.13 ft	180-115925-1	Not Excavated	4.7	7600	450	< 0.02 U	39	530	0.77 J	< 0.11 U	89 J		< 0.32 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-22-24	SSHS-B3568-SUB-22-24	1/18/2021	855.08	855.49	0.41	-	22 - 24 ft	22.41-24.41 ft	180-116109-1	Not Excavated	3.4	5400	270	< 0.019 U	8.3	400	< 0.4 U	< 0.083 U	62 J		< 0.25 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-22-24	SSHS-B3571-SUB-22-24	1/18/2021	855.21	855.30	0.09	-	22 - 24 ft	22.09-24.09 ft	180-116109-1	Not Excavated	3.9	5000	260	< 0.023 U	13	520	< 0.45 U	< 0.092 U	66 J		< 0.28 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-22-24	SSHS-B3569-SUB-22-24	1/19/2021	855.07	855.22	0.15	-	22 - 24 ft	22.15-24.15 ft	180-116199-1	Not Excavated	4.5	9400	420	< 0.024 U	10	840	0.66 J	< 0.12 U	97 J		< 0.36 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-22-24	SSHS-B3570-SUB-22-24	1/19/2021	855.27	855.46	0.19	-	22 - 24 ft	22.19-24.19 ft	180-116199-1	Not Excavated	5.1	6300	290	< 0.019 U	12	600	< 0.55 U	< 0.11 U	94 J		< 0.34 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	5.8	4400	290	0.023 J	12	640	< 0.52 U	< 0.11 U	85 J		< 0.33 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	13	3800	500	< 0.017 U	200	500	0.53 J	< 0.077 U	69 J		< 0.23 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	7.2	4500	250	< 0.02 U	17	440	< 0.4 U	< 0.081 U	65 J		< 0.25 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	5.7	4800	230	< 0.019 U	7.8	500	0.99	< 0.099 U	110 J		< 0.3 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	10	26000	420	< 0.019 U	11	520	0.56 J	< 0.1 U	120 J		< 0.32 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	3.5	3000	2100	< 0.034 U	11	560 J	1 J	< 0.034 U	87 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	21	9500	400	< 0.034 U	11	540	0.73 J	< 0.034 U	87 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	6.2	6200	520	< 0.034 U	13	500 J	0.66 J	< 0.034 U	64 J		< 0.034 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-24-26	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	855.38	0.37	-	24 - 26 ft	24.37-26.37 ft	180-115999-1	Not Excavated	4.8	9000	460	< 0.021 U	21	510	< 0.53 U	< 0.11 U	82 J		< 0.33 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-24-26	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	855.42	0.20	-	24 - 26 ft	24.2-26.2 ft	180-116070-1	Not Excavated	17	6000	510	< 0.023 U	16	900	0.73 J	< 0.12 U	160 J		< 0.36 U

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated		7.8	56
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated		7.8	40
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated		11	47
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated		10	76
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated		8.3	45
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated		7.3	51 J
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-18-20	SSHS-B3562-SUB-18-20	1/13/2021	855.07	855.40	0.33	-	18 - 20 ft	18.33-20.33 ft	180-115925-1	Not Excavated		7.7	58
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated		7.2	45
Football Field	SSHS-B3571	011921 08:30 SSHS-B3571-SUB-18-20	SSHS-B3571-SUB-18-20	1/18/2021	855.21	855.30	0.09	-	18 - 20 ft	18.09-20.09 ft	180-116109-1	Not Excavated		7.6	55
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated		3.9 J	22
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated		10	51
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	180119460l	Not Excavated		5.8	40
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated		4.9	32
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated		9.7	58
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated		7.3	75
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated		8.7	40
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated		4.1 J	30
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated		8.9	46
Football Field	IRM5-A4V SOUTH A	SSHS-IRM5-A4V SOUTH A-20210502	SSHS-IRM5-A4V SOUTH A	5/2/2021	-	855.57	-	835.58	18 - 20 ft	19.99 ft	1801210181	Not Excavated		5.0	37
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated		9.5	46
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated		13	48
Football Field	SSHS-B4165	092421 10:00 DUP-39	DUP-39	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated		8.6	43 J
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated		9.1	54
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-20-22	SSHS-B3555-SUB-20-22	1/11/2021	855.30	855.33	0.03	-	20 - 22 ft	20.03-22.03 ft	180-115815-1	Not Excavated		8.8	46
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-20-22	SSHS-B3557-SUB-20-22	1/11/2021	855.18	855.38	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115815-1	Not Excavated		8.7	52
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-20-22	SSHS-B3560-SUB-20-22	1/11/2021	855.32	855.47	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115815-1	Not Excavated		8.5	51
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-20-22	SSHS-B3563-SUB-20-22	1/11/2021	855.01	855.38	0.37	-	20 - 22 ft	20.37-22.37 ft	180-115815-1	Not Excavated		10	64
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated		6.4	34
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-20-22	SSHS-B3559-SUB-20-22	1/12/2021	855.35	855.36	0.01	-	20 - 22 ft	20.01-22.01 ft	180-115861-1	Not Excavated		8.2	48
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-20-22	SSHS-B3564-SUB-20-22	1/12/2021	855.22	855.42	0.20	-	20 - 22 ft	20.2-22.2 ft	180-115861-1	Not Excavated		7.5	46
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-20-22	SSHS-B3565-SUB-20-22	1/12/2021	855.32	855.45	0.13	-	20 - 22 ft	20.13-22.13 ft	180-115861-2	Not Excavated		9.3	60
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-20-22	SSHS-B3566-SUB-20-22	1/12/2021	855.28	855.43	0.15	-	20 - 22 ft	20.15-22.15 ft	180-115861-2	Not Excavated		8.2	57
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-20-22	SSHS-B3556-SUB-20-22	1/13/2021	855.33	855.47	0.14	-	20 - 22 ft	20.14-22.14 ft	180-115925-1	Not Excavated		7.9	85
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-20-22	SSHS-B3561-SUB-20-22	1/13/2021	855.17	855.41	0.24	-	20 - 22 ft	20.24-22.24 ft	180-115925-1	Not Excavated		11	60
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-20-22	SSHS-B3562-SUB-20-22	1/13/2021	855.07	855.40	0.33	-	20 - 22 ft	20.33-22.33 ft	180-115925-1	Not Excavated		7	49
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-20-22	SSHS-B3568-SUB-20-22	1/18/2021	855.08	855.49	0.41	-	20 - 22 ft	20.41-22.41 ft	180-116109-1	Not Excavated		5 J	32
Football Field	SSHS-B3571	011921 08:30 SSHS-B3571-SUB-20-22	SSHS-B3571-SUB-20-22	1/18/2021	855.21	855.30	0.09	-	20 - 22 ft	20.09-22.09 ft	180-116109-1	Not Excavated		4 J	26
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-20-22	SSHS-B3569-SUB-20-22	1/19/2021	855.07	855.22	0.15	-	20 - 22 ft	20.15-22.15 ft	180-116199-1	Not Excavated		7.8	50
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated		8.8	61
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	180119460l	Not Excavated		6.3	39
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated		6.3	45
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated		7.1	48
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated		7	57
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated		11	58
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated		1.2 J	4.1
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated		7.7	41
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated		6.5	33
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated		7.9	63
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-22-24	SSHS-B3555-SUB-22-24	1/11/2021	855.30	855.33	0.03	-	22 - 24 ft	22.03-24.03 ft	180-115815-1	Not Excavated		12	72
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-22-24	SSHS-B3557-SUB-22-24	1/11/2021	855.18	855.38	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115815-1	Not Excavated		8.6	67
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-22-24	SSHS-B3560-SUB-22-24	1/11/2021	855.32	855.47	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115815-1	Not Excavated		7.6	52
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-22-24	SSHS-B3563-SUB-22-24	1/11/2021	855.01	855.38	0.37	-	22 - 24 ft	22.37-24.37 ft	180-115815-1	Not Excavated		6.7	41
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-22-24	SSHS-B3558-SUB-22-24	1/12/2021	855.27	855.53	0.26	-	22 - 24 ft	22.26-24.26 ft	180-115861-1	Not Excavated		7	43
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-22-24	SSHS-B3559-SUB-22-24	1/12/2021	855.35	855.36	0.01	-	22 - 24 ft	22.01-24.01 ft	180-115861-1	Not Excavated		7.4	44
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-22-24	SSHS-B3564-SUB-22-24	1/12/2021	855.22	855.42	0.20	-	22 - 24 ft	22.2-24.2 ft	180-115861-1	Not Excavated		8.5	59
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-22-24	SSHS-B3566-SUB-22-24	1/12/2021	855.28	855.43	0.15	-	22 - 24 ft	22.15-24.15 ft	180-115861-2	Not Excavated		9.5	52
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-22-24	SSHS-B3556-SUB-22-24	1/13/2021	855.33	855.47	0.14	-	22 - 24 ft	22.14-24.14 ft	180-115925-1	Not Excavated		7.8	51
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-22-24	SSHS-B3561-SUB-22-24	1/13/2021	855.17	855.41	0.24	-	22 - 24 ft	22.24-24.24 ft	180-115925-1	Not Excavated		7.3	45
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-22-24	SSHS-B3562-SUB-22-24	1/13/2021	855.07	855.40	0.33	-	22 - 24 ft	22.33-24.33 ft	180-115925-1	Not Excavated		18	58
Football Field	SSHS-B3565	011421 08:45 SSHS-B3565-SUB-22-24	SSHS-B3565-SUB-22-24	1/13/2021	855.32	855.45	0.13	-	22 - 24 ft	22.13-24.13 ft	180-115925-1	Not Excavated		6.9	56
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-22-24	SSHS-B3568-SUB-22-24	1/18/2021	855.08	855.49	0.41	-	22 - 24 ft	22.41-24.41 ft	180-116109-1	Not Excavated		5.8	49
Football Field	SSHS-B3571	011921 08:30 SSHS-B3571-SUB-22-24	SSHS-B3571-SUB-22-24	1/18/2021	855.21	855.30	0.09	-	22 - 24 ft	22.09-24.09 ft	180-116109-1	Not Excavated		7.6	65
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-22-24	SSHS-B3569-SUB-22-24	1/19/2021	855.07	855.22	0.15	-	22 - 24 ft	22.15-24.15 ft	180-116199-1	Not Excavated		10	44
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-22-24	SSHS-B3570-SUB-22-24	1/19/2021	855.27	855.46	0.19	-	22 - 24 ft	22.19-24.19 ft	180-116199-1	Not Excavated		7.8	50
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	180119460l	Not Excavated		7.6	42
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated		7.8	200
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated		6.3	49
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated		5.5	28
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated		6.6	33
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated		11	37
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated		7.2	41
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated		6.8	45
Football Field	SSHS-B3563	011521 08:45 SSHS-B3563A-SUB-24-26	SSHS-B3563A-SUB-24-26	1/14/2021	855.01	855.38	0.37	-	24 - 26 ft	24.37-26.37 ft	180-115999-1	Not Excavated		6.8	53
Football Field	SSHS-B3564	011621 11:00 SSHS-B3564A-SUB-24-26	SSHS-B3564A-SUB-24-26	1/15/2021	855.22	855.42	0.20	-	24 - 26 ft	24.2-26.2 ft	180-116070-1	Not Excavated		9.1	46

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	**Antimony**	**Arsenic**	**Barium**	**Beryllium**	**Cadmium**	**Calcium**	**Chromium (III+VI)**	**Chromium, Hexavalent**	**Cobalt**	**Copper**	**Iron**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-24-26	SSHS-B3568-SUB-24-26	1/18/2021	855.08	855.49	0.41	-	24 - 26 ft	24.41-26.41 ft	180-116109-1	Not Excavated	2800	< 0.33 U	2.7	33	0.14 J	0.18 J	150000	4.6		2.4 J	12	7400
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-24-26	SSHS-B3571-SUB-24-26	1/18/2021	855.21	855.30	0.09	-	24 - 26 ft	24.09-26.09 ft	180-116109-1	Not Excavated	5700	< 0.22 U	4.6	49	0.21 J	0.1 J	25000	7.6		5.1	18	13000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-24-26	SSHS-B3569-SUB-24-26	1/19/2021	855.07	855.22	0.15	-	24 - 26 ft	24.15-26.15 ft	180-116199-1	Not Excavated	4700	0.38 J	4.4	73	0.21 J	0.11 J	26000	5.9		4.1 J	14	11000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-24-26	SSHS-B3570-SUB-24-26	1/19/2021	855.27	855.46	0.19	-	24 - 26 ft	24.19-26.19 ft	180-116199-1	Not Excavated	4400	< 0.37 U	2.9	25	0.18 J	0.1 J	28000	7.7		3.6 J	17	11000
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	13000	< 0.46 U	11	96	0.68	< 0.049 U	6800	17		12	17	27000
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	13000	< 0.46 U	11	82	0.61	0.060 J	7800	17		12	17	28000
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	8900	< 0.43 U	7.8	42	0.37 J	0.048 J	7500	11		8.7	14	20000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	4900	< 0.3 U	3.2	34	0.17 J	0.16 J	37000	8.5		5	93	11000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	2900	< 0.25 U	2.7	18	0.11 J	0.068 J	50000	42		2.8 J	12	7200
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	4700	< 0.38 U	4.8	46	0.2 J	0.11 J	53000	6.9		4.8 J	29	13000
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	3300	< 1.3 U	2.9	27 J	0.13 J	0.12 J	110000 J	4.9		3.7 J	12	8000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	5200	< 0.37 U	4.5	48 J	0.2 J	0.12 J	43000 J	7.8		5.8	18	13000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	6400	< 0.034 U	5.9	44	0.29 J	0.11 J	25000	8.3		7.5	16	16000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	4200	< 0.034 U	3.2	24	0.15 J	0.11 J	67000	5.6		4.3 J	12	10000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	4200	< 0.034 U	4	54	0.17 J	0.04 J	13000	5.2		4.9 J	11	11000
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-26-28	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	855.38	0.37	-	26 - 28 ft	26.37-28.37 ft	180-115999-1	Not Excavated	5400	< 0.36 U	3.9	43	0.21 J	0.087 J	29000	6.7		5.2	24	12000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-26-28	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	855.42	0.20	-	26 - 28 ft	26.2-28.2 ft	180-116070-1	Not Excavated	4200	< 0.34 U	4.4	29	0.16 J	0.13 J	58000	5.5		4.2 J	24	11000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-26-28	SSHS-B3568-SUB-26-28	1/18/2021	855.08	855.49	0.41	-	26 - 28 ft	26.41-28.41 ft	180-116109-1	Not Excavated	4400	< 0.26 U	3.1	29	0.18 J	0.11 J	80000	5.9		4.3	14	11000
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-26-28	SSHS-B3571-SUB-26-28	1/18/2021	855.21	855.30	0.09	-	26 - 28 ft	26.09-28.09 ft	180-116109-1	Not Excavated	3100	< 0.25 U	3.8	20	0.15 J	0.1 J	87000	5.1		3.2 J	14	9400
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-26-28	SSHS-B3569-SUB-26-28	1/19/2021	855.07	855.22	0.15	-	26 - 28 ft	26.15-28.15 ft	180-116199-1	Not Excavated	5500	< 0.4 U	5.8	35	0.27 J	0.1 J	20000	7.5		5.3 J	14	14000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-26-28	SSHS-B3570-SUB-26-28	1/19/2021	855.27	855.46	0.19	-	26 - 28 ft	26.19-28.19 ft	180-116199-1	Not Excavated	5600	< 0.36 U	2.6	34	0.18 J	0.11 J	22000	7.2		4.3 J	15	14000
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	13000	< 0.43 U	12	80	0.59	0.061 J	9100	17		13	18	28000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	5300	0.69 J	3.5	30	0.2 J	0.14 J	38000	8.6		5	130	13000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	4800	< 0.32 U	4.5	44	0.21 J	0.098 J	36000	13		4.5 J	18	12000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	5300	< 0.32 U	5	37	0.23 J	0.11 J	54000	10		4.8	25	13000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	5200	< 0.3 UJ	5.1	33	0.25 J	0.085 J	33000	6.8		5.2	14	13000
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	5400	< 0.034 U	4.1	31	0.23 J	0.071 J	28000	6.8		4.7 J	13	13000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	5400	< 0.034 U	4.3	32	0.23 J	0.093 J	30000	7		5.1	14	13000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	3600	< 0.034 U	2.8	19 J	0.14 J	0.1 J	56000	5		3.6 J	13	8500
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	5900	< 0.034 U	3.2	48	0.2 J	0.049 J	38000	7.5		5.4	19	14000
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-28-30	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	855.38	0.37	-	28 - 30 ft	28.37-30.37 ft	180-115999-1	Not Excavated	4400	< 0.37 U	2.9	35	0.18 J	0.12 J	41000	5.3		4.2 J	15	10000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-28-30	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	855.42	0.20	-	28 - 30 ft	28.2-30.2 ft	180-116070-1	Not Excavated	3900	< 0.34 U	2.7	33	0.14 J	0.1 J	50000	4.4		3.7 J	16	9700
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-28-30	SSHS-B3568-SUB-28-30	1/18/2021	855.08	855.49	0.41	-	28 - 30 ft	28.41-30.41 ft	180-116109-1	Not Excavated	4400	< 0.35 U	4.2	33	0.21 J	0.14 J	39000	6.3		4.1 J	16	11000
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-28-30	SSHS-B3571-SUB-28-30	1/18/2021	855.21	855.30	0.09	-	28 - 30 ft	28.09-30.09 ft	180-116109-1	Not Excavated	3300	< 0.26 U	2.7	26	0.17 J	0.072 J	26000	4.4		3 J	11	8400
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-28-30	SSHS-B3569-SUB-28-30	1/19/2021	855.07	855.22	0.15	-	28 - 30 ft	28.15-30.15 ft	180-116199-1	Not Excavated	5800	< 0.38 U	5.9	39	0.31 J	0.12 J	33000	8		5.6	17	14000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-28-30	SSHS-B3570-SUB-28-30	1/19/2021	855.27	855.46	0.19	-	28 - 30 ft	28.19-30.19 ft	180-116199-1	Not Excavated	5500	< 0.4 U	5.5	35	0.27 J	0.093 J	34000	7.2		5.2 J	17	14000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	5400	< 0.33 U	4.5	29	0.23 J	0.11 J	38000	7.4		5.3	59	12000
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	5700	< 0.38 U	5	31	0.25 J	0.14 J	46000	8.2		5.5 J	58	14000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	4600	< 0.31 U	6.9	29	0.21 J	0.11 J	41000	8.7		4.7	13	12000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	4900	< 0.31 UJ	5.6	32	0.24 J	0.091 J	36000	7.1		4.8	14	13000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	4900	< 0.34 U	4.7	33	0.23 J	0.097 J	34000	6.7		4.6 J	13	12000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	3900	< 0.034 U	3.9	24 J-	0.18 J	0.088 J	39000	5.3		3.6 J	11	9800
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	4000	< 0.034 U	3.2	32	0.16 J	0.14 J	43000	5.4		4.3 J	16	11000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	4000	< 0.034 U	3.8	27	0.18 J	0.039 J	37000	5.8		3.8 J	13	10000
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-30-32	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	855.38	0.37	-	30 - 32 ft	30.37-32.37 ft	180-115999-1	Not Excavated	4700	< 0.4 U	3.9	32	0.22 J	0.087 J	36000	6		4.2 J	15	11000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-30-32	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	855.42	0.20	-	30 - 32 ft	30.2-32.2 ft	180-116070-1	Not Excavated	4300	< 0.41 U	4.1	26	0.2 J	0.1 J	39000	5.8		3.9 J	14	11000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-30-32	SSHS-B3568-SUB-30-32	1/18/2021	855.08	855.49	0.41	-	30 - 32 ft	30.41-32.41 ft	180-116109-1	Not Excavated	5300	< 0.42 U	5	34	0.25 J	0.11 J	42000	7.7		4.9 J	16	13000
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-30-32	SSHS-B3571-SUB-30-32	1/18/2021	855.21	855.30	0.09	-	30 - 32 ft	30.09-32.09 ft	180-116109-1	Not Excavated	5300	< 0.23 U	4.5	43	0.22 J	0.13 J	40000	7.2		5.1	20	13000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-30-32	SSHS-B3569-SUB-30-32	1/19/2021	855.07	855.22	0.15	-	30 - 32 ft	30.15-32.15 ft	180-116199-1	Not Excavated	5400	< 0.38 U	5.8	36	0.27 J	0.13 J	34000	7.4		5.2 J	16	13000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-30-32	SSHS-B3570-SUB-30-32	1/19/2021	855.27	855.46	0.19	-	30 - 32 ft	30.19-32.19 ft	180-116199-1	Not Excavated	7400	< 0.41 U	6.9	53	0.34 J	0.097 J	38000	9.6		6.3	18	17000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	14000	< 0.37 UJ	9.7	130 J-	0.71	0.11 J	25000	18		12	27	26000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	4300	< 0.3 UJ	4.3	26	0.2 J	0.087 J	36000 J	7.1		4 J	12	10000 J
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	4500	< 0.42 U	5.8	31	0.23 J	0.098 J	39000	7.2		4.5 J	15	12000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	4800	< 0.37 U	5.3	31	0.23 J	0.11 J	35000	7.3		4.6 J	14	12000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	8000	< 0.034 U	4.9	66	0.31 J	0.11 J	26000	10		6.7	16	18000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	5100	< 0.034 U	3.9	32	0.17 J	0.11 J	39000	7.5		5	21	12000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	4000	< 0.034 U	2.7	23 J	0.14 J	0.068 J	51000	5.5		3.7 J	12	9400
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-32-34	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	855.38	0.37	-	32 - 34 ft	32.37-34.37 ft	180-115999-1	Not Excavated	4100	< 0.39 U	4	26	0.21 J	0.067 J	39000	5.5		3.7 J	12	10000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-32-34	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	855.42	0.20	-	32 - 34 ft	32.2-34.2 ft	180-116070-1	Not Excavated	5300	< 0.39 U	4.6	33	0.25 J	0.1 J	40000	7.1		5 J	16	13000
Football Field	SSHS-B3568	011921 08:30_DUP-30	DUP-30	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated	4700	< 0.4 U	5	31	0.24 J	0.11 J	42000	6.6		4.3 J	15	12000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-32-34	SSHS-B3568-SUB-32-34	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated	4800	< 0.36 U	5.8	32	0.23 J	0.11 J	41000	6.7		4.4 J	15	12000
Football Field	SSHS-B3571	011921 08:30_DUP-35	DUP-35	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated	5800	0.43 J	5.1	41	0.27 J	0.099 J	34000	7.8		5.6	19	14000
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-32-34	SSHS-B3571-SUB-32-34	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated	6500	< 0.4 UJ	5.7	39	0.29 J	0.11 J	37000	8.8		6.2	21	16000
Football Field	SSHS-B3569	012021 09:30_DUP-32	DUP-32	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated	5100	< 0.38 U	5.4	35	0.26 J	0.096 J	33000	7.2		4.9 J	15	13000
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-32-34	SSHS-B3569-SUB-32-34	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated	5000	< 0.38 U	4.4	31	0.23 J	0.086 J	39000	6.9		4.6 J	15	12000
Football Field	SSHS-B3570	012021 09:30_DUP-34	DUP-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated	5400	< 0.42 U	5.3	35	0.28 J	0.1 J	33000	7.7		5.2 J	15	14000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-32-34	SSHS-B3570-SUB-32-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated	5100	< 0.43 U	4.9	31	0.26 J	0.13 J	45000	6.7		4.6 J	15	12000
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	12000	< 0.23 U	10	67	0.53	0.042 J	8600	17		12	19	24000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	15000	< 0.37 U	11	90	0.7	0.072 J	14000	22		14	22	30000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	3800	< 0.25 U	4.2	25	0.18 J	0.078 J	28000	5.6		3.8	12	9200
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	5100	< 0.31 U	4.9	32	0.25 J	0.09 J	32000	7.9		5	16	13000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	4700	< 0.31 U	5.7	30	0.23 J	0.11 J	36000	7.2		4.8	16	13000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	14000	< 0.034 U	10	84	0.6	0.067 J	14000	20		13	20	27000
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	4200	< 0.034 U	3.6	23 J	0.2 J	0.097 J	35000	5.8		4.1 J	16	11000

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-24-26	SSHS-B3568-SUB-24-26	1/18/2021	855.08	855.49	0.41	-	24 - 26 ft	24.41-26.41 ft	180-116109-1	Not Excavated	2.8	5800	290	< 0.022 U	7.4	550	1.3	< 0.1 U	120 J		< 0.31 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-24-26	SSHS-B3571-SUB-24-26	1/18/2021	855.21	855.30	0.09	-	24 - 26 ft	24.09-26.09 ft	180-116109-1	Not Excavated	6.8	7200	480	< 0.021 U	14	490	< 0.34 U	< 0.069 U	75 J		< 0.21 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-24-26	SSHS-B3569-SUB-24-26	1/19/2021	855.07	855.22	0.15	-	24 - 26 ft	24.15-26.15 ft	180-116199-1	Not Excavated	5.3	5500	440	< 0.021 U	11	670	< 0.57 U	< 0.12 U	78 J		< 0.36 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-24-26	SSHS-B3570-SUB-24-26	1/19/2021	855.27	855.46	0.19	-	24 - 26 ft	24.19-26.19 ft	180-116199-1	Not Excavated	6.1	4200	280	< 0.02 U	10	560	0.65 J	< 0.12 U	75 J		< 0.35 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	14	6400	400	0.032 J	28	2000	< 0.69 U	< 0.14 U	100 J		< 0.43 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	12	6800	430	0.035 J	29	1700	< 0.69 U	< 0.14 U	97 J		< 0.43 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	8.0	5500	310	0.034 J	20	910	< 0.65 U	< 0.13 U	< 76 U		< 0.41 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	5.7	8000	560	< 0.022 U	180	610	0.51 J	< 0.094 U	99 J		< 0.29 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	4.2	6100	280	< 0.019 U	10	350 J	0.56 J	< 0.078 U	83 J		< 0.24 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	9.5	11000	480	< 0.021 U	12	700	< 0.58 U	< 0.12 U	100 J		< 0.36 U
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	11	37000 J	510	< 0.019 U	9.3 J	480	0.94 J	< 0.081 U	190 J		< 1.2 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	10	13000 J	590	< 0.02 U	14	700	< 0.56 UJ	< 0.11 U	110 J		< 0.35 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	7.7	6000	390	< 0.034 U	16	850	< 0.034 U	< 0.034 U	92 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	5	4000	390	< 0.034 U	16	460 J	1	< 0.034 U	79 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	4.2	1900	830	< 0.034 U	27	320 J	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-26-28	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	855.38	0.37	-	26 - 28 ft	26.37-28.37 ft	180-115999-1	Not Excavated	3.9	3500	370	< 0.02 U	15	490 J	< 0.54 U	< 0.11 U	110 J		< 0.34 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-26-28	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	855.42	0.20	-	26 - 28 ft	26.2-28.2 ft	180-116070-1	Not Excavated	5.3	22000	390	< 0.018 U	32	510	0.75 J	< 0.11 U	120 J		< 0.32 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-26-28	SSHS-B3568-SUB-26-28	1/18/2021	855.08	855.49	0.41	-	26 - 28 ft	26.41-28.41 ft	180-116109-1	Not Excavated	3.7	5800	1500	< 0.022 U	11	440	0.56 J	< 0.082 U	68 J		< 0.25 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-26-28	SSHS-B3571-SUB-26-28	1/18/2021	855.21	855.30	0.09	-	26 - 28 ft	26.09-28.09 ft	180-116109-1	Not Excavated	5.8	30000	360	< 0.023 U	8.1	470	0.71 J	< 0.078 U	100 J		< 0.24 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-26-28	SSHS-B3569-SUB-26-28	1/19/2021	855.07	855.22	0.15	-	26 - 28 ft	26.15-28.15 ft	180-116199-1	Not Excavated	6.5	6700	210	< 0.027 U	13	820	< 0.61 U	< 0.13 U	94 J		< 0.38 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-26-28	SSHS-B3570-SUB-26-28	1/19/2021	855.27	855.46	0.19	-	26 - 28 ft	26.19-28.19 ft	180-116199-1	Not Excavated	9.5	6600	380	< 0.022 U	11	440 J	< 0.55 U	< 0.11 U	70 J		< 0.34 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	12	7300	450	< 0.024 U	30	1700	< 0.65 U	< 0.13 U	98 J		< 0.41 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	6	8700	440	< 0.02 U	170	650	0.48 J	< 0.093 U	85 J		< 0.28 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	6.5	6200	440	< 0.021 U	16	710	0.59 J	< 0.098 U	95 J		< 0.3 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	8	6000	300	< 0.025 U	14	650	0.85 J	< 0.099 U	96 J		< 0.3 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	6.9	6100 J-	280	< 0.025 U	13	730	< 0.45 U	< 0.092 U	85 J		< 0.28 U
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	5.6	3500	220	< 0.034 U	12	650	< 0.034 U	< 0.034 U	76 J		< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	6	4300	240	< 0.034 U	13	630	< 0.034 U	< 0.034 U	79 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	3.7	3500	280	< 0.034 U	27	440 J	0.79 J	< 0.034 U	67 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	10	12000	480	< 0.034 U	21	640	0.58 J	< 0.034 U	82 J		< 0.034 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-28-30	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	855.38	0.37	-	28 - 30 ft	28.37-30.37 ft	180-115999-1	Not Excavated	3.7	4700	400	< 0.023 U	12	520 J	< 0.57 U	< 0.12 U	84 J		< 0.35 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-28-30	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	855.42	0.20	-	28 - 30 ft	28.2-30.2 ft	180-116070-1	Not Excavated	3.8	6500	650	< 0.022 U	26	420 J	< 0.52 U	< 0.11 U	84 J		< 0.32 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-28-30	SSHS-B3568-SUB-28-30	1/18/2021	855.08	855.49	0.41	-	28 - 30 ft	28.41-30.41 ft	180-116109-1	Not Excavated	5.2	5200	480	< 0.024 U	11	710	< 0.52 U	< 0.11 U	91 J		< 0.33 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-28-30	SSHS-B3571-SUB-28-30	1/18/2021	855.21	855.30	0.09	-	28 - 30 ft	28.09-30.09 ft	180-116109-1	Not Excavated	4.2	3800	320	< 0.022 U	7.2	550	< 0.4 U	< 0.082 U	62 J		< 0.25 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-28-30	SSHS-B3569-SUB-28-30	1/19/2021	855.07	855.22	0.15	-	28 - 30 ft	28.15-30.15 ft	180-116199-1	Not Excavated	7	6800	320	< 0.024 U	15	830	< 0.58 U	< 0.12 U	94 J		< 0.36 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-28-30	SSHS-B3570-SUB-28-30	1/19/2021	855.27	855.46	0.19	-	28 - 30 ft	28.19-30.19 ft	180-116199-1	Not Excavated	7.1	6300	300	< 0.024 U	13	820	< 0.6 U	< 0.12 U	95 J		< 0.37 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	6.5	5200	270	< 0.024 U	170	690	0.74 J	< 0.1 U	89 J		< 0.31 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	7.4	6200	310	< 0.021 U	140	870	0.7 J	< 0.12 U	98 J		< 0.36 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	6.6	6200	330	< 0.021 U	14	710	0.78 J	< 0.095 U	96 J		< 0.29 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	7.4	7000 J-	280	< 0.023 U	13	680	0.54 J	< 0.094 U	91 J		< 0.29 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	6.4	5200	280	< 0.02 U	12	650	< 0.52 U	< 0.11 U	90 J		< 0.32 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	4.5	4900	240	< 0.034 U	9.4	560 J	< 0.034 U	< 0.034 U	77 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	6.7	4100	450	< 0.034 U	17	460 J	< 0.034 U	< 0.034 U	87 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	5.6	7300	290	< 0.034 U	9.4	610	0.73 J	< 0.034 U	83 J		< 0.034 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-30-32	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	855.38	0.37	-	30 - 32 ft	30.37-32.37 ft	180-115999-1	Not Excavated	4.9	3700	330	< 0.026 U	12	710	< 0.61 U	< 0.12 U	91 J		< 0.38 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-30-32	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	855.42	0.20	-	30 - 32 ft	30.2-32.2 ft	180-116070-1	Not Excavated	5	5100	260	< 0.026 U	10	750	< 0.63 U	< 0.13 U	110 J		< 0.39 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-30-32	SSHS-B3568-SUB-30-32	1/18/2021	855.08	855.49	0.41	-	30 - 32 ft	30.41-32.41 ft	180-116109-1	Not Excavated	5.9	6000 J-	340	< 0.023 U	13	860	< 0.64 U	< 0.13 U	100 J		< 0.4 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-30-32	SSHS-B3571-SUB-30-32	1/18/2021	855.21	855.30	0.09	-	30 - 32 ft	30.09-32.09 ft	180-116109-1	Not Excavated	6	6500	620	< 0.022 U	14	650	< 0.36 U	< 0.073 U	83 J		< 0.22 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-30-32	SSHS-B3569-SUB-30-32	1/19/2021	855.07	855.22	0.15	-	30 - 32 ft	30.15-32.15 ft	180-116199-1	Not Excavated	6.4	6400	300	< 0.022 U	14	770	< 0.58 U	< 0.12 U	88 J		< 0.36 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-30-32	SSHS-B3570-SUB-30-32	1/19/2021	855.27	855.46	0.19	-	30 - 32 ft	30.19-32.19 ft	180-116199-1	Not Excavated	8.6	6100	350	< 0.024 U	17	1000	< 0.63 U	< 0.13 U	100 J		< 0.39 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	14	7500 J	390	< 0.022 U	41	2200	< 0.56 U	< 0.11 U	140 J		< 0.35 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	5.4	3900 J	270	< 0.023 U	12	580	0.6 J	< 0.094 U	90 J		< 0.29 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	7	7400	290	< 0.025 U	12	690	< 0.63 U	< 0.13 U	97 J		< 0.39 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	6.4	5600	270	< 0.023 U	12	700	< 0.57 U	< 0.12 U	88 J		< 0.35 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	6.9	4400	330	< 0.034 U	18	850	< 0.034 U	< 0.034 U	88 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	6.8	6600	350	< 0.034 U	16	560	< 0.034 U	< 0.034 U	81 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	6.6	9200 J	350	< 0.034 U	13	410 J	< 0.034 U	< 0.034 U	87 J		< 0.034 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-32-34	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	855.38	0.37	-	32 - 34 ft	32.37-34.37 ft	180-115999-1	Not Excavated	4.5	4300	260	< 0.023 U	10	610	< 0.59 U	< 0.12 U	83 J		< 0.37 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-32-34	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	855.42	0.20	-	32 - 34 ft	32.2-34.2 ft	180-116070-1	Not Excavated	6	5900	310	< 0.023 U	13	820	< 0.59 U	< 0.12 U	93 J		< 0.37 U
Football Field	SSHS-B3568	011921 08:30_DUP-30	DUP-30	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated	5.7	5800	310	< 0.025 U	11	760	< 0.6 U	< 0.12 U	97 J		< 0.37 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-32-34	SSHS-B3568-SUB-32-34	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated	6.1	6000	330	< 0.025 U	11	780	< 0.54 U	< 0.11 U	100 J		< 0.34 U
Football Field	SSHS-B3571	011921 08:30_DUP-35	DUP-35	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated	6.7	5600	310	< 0.023 U	14	770	< 0.55 U	< 0.11 U	89 J		< 0.34 U
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-32-34	SSHS-B3571-SUB-32-34	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated	7.4	6300	320	< 0.026 U	16	880	< 0.6 U	< 0.12 U	99 J		< 0.37 U
Football Field	SSHS-B3569	012021 09:30_DUP-32	DUP-32	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated	6	6200	290	< 0.023 U	13	730	< 0.58 U	< 0.12 U	88 J		< 0.36 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-32-34	SSHS-B3569-SUB-32-34	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated	5.2	5300	300	< 0.025 U	12	650	0.72 J	< 0.12 U	90 J		< 0.36 U
Football Field	SSHS-B3570	012021 09:30_DUP-34	DUP-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated	7	6500	300	< 0.024 U	13	890	0.75 J	< 0.13 U	100 J		< 0.4 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-32-34	SSHS-B3570-SUB-32-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated	6.1	5700	310	< 0.026 U	12	820	< 0.65 U	< 0.13 U	110 J		< 0.41 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	13	6700	390	< 0.025 U	34	1300	< 0.35 U	< 0.072 U	88 J		< 0.22 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	16	8800	450	< 0.026 U	35	2000	< 0.56 U	< 0.11 U	130 J		< 0.35 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	5.4	4300	230	< 0.017 U	10	510	< 0.38 U	< 0.078 U	73 J		< 0.24 U
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	7.4	6100	280	< 0.023 U	13	700	< 0.47 U	< 0.095 U	92 J		< 0.29 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	7.2	6700	260	< 0.021 U	12	710	< 0.47 U	< 0.095 U	91 J		< 0.29 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	12	8100	430	< 0.034 U	30	1900	< 0.034 U	< 0.034 U	100 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	5	4200	240	< 0.034 U	10	580 J	< 0.034 U	< 0.034 U	73 J		< 0.034 U

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-24-26	SSHS-B3568-SUB-24-26	1/18/2021	855.08	855.49	0.41	-	24 - 26 ft	24.41-26.41 ft	180-116109-1	Not Excavated		5.1	45
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-24-26	SSHS-B3571-SUB-24-26	1/18/2021	855.21	855.30	0.09	-	24 - 26 ft	24.09-26.09 ft	180-116109-1	Not Excavated		7.7	66
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-24-26	SSHS-B3569-SUB-24-26	1/19/2021	855.07	855.22	0.15	-	24 - 26 ft	24.15-26.15 ft	180-116199-1	Not Excavated		7.5	38
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-24-26	SSHS-B3570-SUB-24-26	1/19/2021	855.27	855.46	0.19	-	24 - 26 ft	24.19-26.19 ft	180-116199-1	Not Excavated		6.5	46
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated		18	60
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated		17	63
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated		11	48
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated		7.3	120
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated		4.5	29
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated		8	47
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated		5.8	30
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated		8.7	48
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated		11	48
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated		6	43
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated		6.1	57
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-26-28	SSHS-B3563A-SUB-26-28	1/14/2021	855.01	855.38	0.37	-	26 - 28 ft	26.37-28.37 ft	180-115999-1	Not Excavated		7.8	54
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-26-28	SSHS-B3564A-SUB-26-28	1/15/2021	855.22	855.42	0.20	-	26 - 28 ft	26.2-28.2 ft	180-116070-1	Not Excavated		6.9	42
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-26-28	SSHS-B3568-SUB-26-28	1/18/2021	855.08	855.49	0.41	-	26 - 28 ft	26.41-28.41 ft	180-116109-1	Not Excavated		7.2	41
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-26-28	SSHS-B3571-SUB-26-28	1/18/2021	855.21	855.30	0.09	-	26 - 28 ft	26.09-28.09 ft	180-116109-1	Not Excavated		6.4	38
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-26-28	SSHS-B3569-SUB-26-28	1/19/2021	855.07	855.22	0.15	-	26 - 28 ft	26.15-28.15 ft	180-116199-1	Not Excavated		9.3	40
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-26-28	SSHS-B3570-SUB-26-28	1/19/2021	855.27	855.46	0.19	-	26 - 28 ft	26.19-28.19 ft	180-116199-1	Not Excavated		9.6	56
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated		17	64
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated		8.8	85
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated		8.3	48
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated		9.1	41
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated		9	41 J-
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated		7.9	35
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated		7.9	34
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated		5.6	34
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated		9.7	44
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-28-30	SSHS-B3563A-SUB-28-30	1/14/2021	855.01	855.38	0.37	-	28 - 30 ft	28.37-30.37 ft	180-115999-1	Not Excavated		6.3	43
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-28-30	SSHS-B3564A-SUB-28-30	1/15/2021	855.22	855.42	0.20	-	28 - 30 ft	28.2-30.2 ft	180-116070-1	Not Excavated		8.1	49
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-28-30	SSHS-B3568-SUB-28-30	1/18/2021	855.08	855.49	0.41	-	28 - 30 ft	28.41-30.41 ft	180-116109-1	Not Excavated		8	42
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-28-30	SSHS-B3571-SUB-28-30	1/18/2021	855.21	855.30	0.09	-	28 - 30 ft	28.09-30.09 ft	180-116109-1	Not Excavated		6.3	33
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-28-30	SSHS-B3569-SUB-28-30	1/19/2021	855.07	855.22	0.15	-	28 - 30 ft	28.15-30.15 ft	180-116199-1	Not Excavated		9.6	43
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-28-30	SSHS-B3570-SUB-28-30	1/19/2021	855.27	855.46	0.19	-	28 - 30 ft	28.19-30.19 ft	180-116199-1	Not Excavated		9.2	40
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated		8.5	63
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated		9.7	63
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated		10	36
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated		8.7	38 J-
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated		8.4	34
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated		6.9	27
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated		6	56
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated		7.7	35
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-30-32	SSHS-B3563A-SUB-30-32	1/14/2021	855.01	855.38	0.37	-	30 - 32 ft	30.37-32.37 ft	180-115999-1	Not Excavated		7	38
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-30-32	SSHS-B3564A-SUB-30-32	1/15/2021	855.22	855.42	0.20	-	30 - 32 ft	30.2-32.2 ft	180-116070-1	Not Excavated		7.6	43
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-30-32	SSHS-B3568-SUB-30-32	1/18/2021	855.08	855.49	0.41	-	30 - 32 ft	30.41-32.41 ft	180-116109-1	Not Excavated		9.3	41
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-30-32	SSHS-B3571-SUB-30-32	1/18/2021	855.21	855.30	0.09	-	30 - 32 ft	30.09-32.09 ft	180-116109-1	Not Excavated		8.8	56
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-30-32	SSHS-B3569-SUB-30-32	1/19/2021	855.07	855.22	0.15	-	30 - 32 ft	30.15-32.15 ft	180-116199-1	Not Excavated		9.1	39
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-30-32	SSHS-B3570-SUB-30-32	1/19/2021	855.27	855.46	0.19	-	30 - 32 ft	30.19-32.19 ft	180-116199-1	Not Excavated		11	42
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated		20	62 J-
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated		7.2	30
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated		9.1	36
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated		8.6	36
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated		12	51
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated		8.6	48
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated		7.1	34
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-32-34	SSHS-B3563A-SUB-32-34	1/14/2021	855.01	855.38	0.37	-	32 - 34 ft	32.37-34.37 ft	180-115999-1	Not Excavated		6.4	30
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-32-34	SSHS-B3564A-SUB-32-34	1/15/2021	855.22	855.42	0.20	-	32 - 34 ft	32.2-34.2 ft	180-116070-1	Not Excavated		9.1	45
Football Field	SSHS-B3568	011921 08:30_DUP-30	DUP-30	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated		8.8	38
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-32-34	SSHS-B3568-SUB-32-34	1/18/2021	855.08	855.49	0.41	-	32 - 34 ft	32.41-34.41 ft	180-116109-1	Not Excavated		9.1	39
Football Field	SSHS-B3571	011921 08:30_DUP-35	DUP-35	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated		9.2	55
Football Field	SSHS-B3571	011921 08:30_SSHS-B3571-SUB-32-34	SSHS-B3571-SUB-32-34	1/18/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116109-1	Not Excavated		11	61
Football Field	SSHS-B3569	012021 09:30_DUP-32	DUP-32	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated		8.5	38
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-32-34	SSHS-B3569-SUB-32-34	1/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-116199-1	Not Excavated		7.5	33
Football Field	SSHS-B3570	012021 09:30_DUP-34	DUP-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated		10	41
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-32-34	SSHS-B3570-SUB-32-34	1/19/2021	855.27	855.46	0.19	-	32 - 34 ft	32.19-34.19 ft	180-116199-1	Not Excavated		8	35
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated		16	58
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated		20	68
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated		5.8	30
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated		8.7	39
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated		9.8	39
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated		19	62
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated		7.7	41

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	4100	< 0.034 U	4.5	23	0.18 J	0.089 J	34000	5.6		4.2 J	13	11000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	4300	< 0.034 U	4.3	28	0.16 J	< 0.034 U	31000	5.9		3.8 J	12	10000
Football Field	SSHS-B3568	011921 08:30_DUP-31	DUP-31	1/18/2021	855.08	855.49	0.41	-	34 - 35 ft	34.41-35.41 ft	180-116109-1	Not Excavated	5300	0.49 J	6.1	35	0.25 J	0.092 J	42000	7.2		5 J	16	13000
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-34-36	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	855.38	0.37	-	34 - 36 ft	34.37-36.37 ft	180-115999-1	Not Excavated	4700	< 0.44 U	4.3	31	0.23 J	0.083 J	37000	6.9		4.5 J	14	11000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-34-36	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	855.42	0.20	-	34 - 36 ft	34.2-36.2 ft	180-116070-1	Not Excavated	5400	< 0.39 U	5	36	0.25 J	0.15 J	38000	7.2		5.1 J	16	14000
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-34-35	SSHS-B3568-SUB-34-35	1/18/2021	855.08	855.49	0.41	-	34 - 36 ft	34.41-36.41 ft	180-116109-1	Not Excavated	5000	< 0.39 UJ	8.3	31	0.24 J	0.09 J	40000	7.5		4.7 J	15	13000
Football Field	SSHS-B3569	012021 09:30_DUP-33	DUP-33	1/19/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	180-116199-1	Not Excavated	5500	< 0.39 U	5.9	35	0.26 J	0.11 J	39000	7.2		5.3 J	16	14000
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-34-35	SSHS-B3570-SUB-34-35	1/19/2021	855.27	855.46	0.19	-	34 - 36 ft	34.19-36.19 ft	180-116199-1	Not Excavated	4500	< 0.41 U	5.1	29	0.23 J	0.1 J	58000	6.3		4.1 J	14	11000
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	11000	< 0.35 U	7	61	0.5	< 0.038 U	8900	17		10	17	23000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	5200	< 0.38 U	5.7	33	0.26 J	0.098 J	32000	8.1		4.8 J	15	13000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	15000	< 0.31 U	10	97	0.68	0.066 J	14000	20		14	21	29000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	13000	< 0.034 U	10	89	0.62	0.068 J	8200	17		12	17	25000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	4000	< 0.034 U	4.1	23	0.18 J	0.083 J	31000	5.7		4.1 J	12	11000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	4700	< 0.034 U	4.4	31	0.17 J	0.044 J	29000	6.3		4.2 J	15	11000
Football Field	SSHS-B3563	011621 11:00_SSHS-B3563A-SUB-36-37	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	855.38	0.37	-	36 - 37 ft	36.37-37.37 ft	180-116070-1	Not Excavated	4200	< 0.41 U	5.3	26	0.21 J	0.13 J	37000	6.7		4.3 J	15	13000
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-36-37	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	855.42	0.20	-	36 - 37 ft	36.2-37.2 ft	180-116070-1	Not Excavated	5000	< 0.41 U	5.7	32	0.24 J	0.097 J	42000	7.1		5 J	15	13000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	5000	< 0.034 U	4.6	31	0.21 J	0.1 J	40000	7		5.3 J	15	13000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	17000	< 0.36 U	7.8	110	0.81	0.094 J	17000	22		15	24	32000
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	14000	< 0.36 U	8.4	97	0.67	0.059 J	8900	19		14	19	28000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	13000	< 0.034 U	9.5	72	0.54	0.068 J	11000	17		12	17	26000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	4300	0.39 J	3.3	27 J-	0.18 J	0.049 J	46000	5.4 J-		4 J	17 J-	9600
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	16000	< 0.034 U	12	87	0.69	0.083 J	13000	21		15	22	32000
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	16000	< 0.42 U	12	100	0.74	0.051 J	10000	21		15	21	33000
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	9900	< U	5.7	45	0.41 J	0.06 J	10000	14		9.9	14	21000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	15000	0.61 J	9.8	88	0.63	< 0.044 U	16000	18		13	21	27000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	13000	< 0.034 U	10	90	0.6	0.051 J	9200	19		12	18	26000
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	16000	0.48 J	11	120	0.74	< 0.034 U	8800	20		14	20	28000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	14000	< 0.034 U	12	83	0.62	0.055 J	10000	19		14	19	30000
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	14000	< UJ	10	78 J-	0.61 J-	0.077 J	11000 J	20 J-		13	19	28000
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated	5900	< 0.36 U	4.1	57	0.23 J	0.087 J	59000	10		5.2 J	17	14000
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	6000	0.28	5.7	47	0.23	< 0.014	33000	6.8		5.7	18	15000
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	4300	< 0.38	4.6	31	0.17	0.03	54000	5.8		4	13	11000
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	7300	2.3	7.3	75	0.34 J	0.27 J	7600	51		6.2	30	19000
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	5400	< 0.31 U	3.7	39	0.22 J	0.18 J	43000	10		5.8	17	13000
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	6600	< 0.37 UJ	6.1	65	0.26 J	0.16 J	18000	20		5.8	31	17000
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	5500	< 0.36 U	5.1	61	0.22 J	0.064 J	46000	12		5.2 J	17	14000
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	5600	< 0.36 U	4.9	45	0.21 J	0.049 J	31000	13		5.3	20	14000
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	5900	< 0.36 U	5	95	0.27 J	0.06 J	34000	11		5.2 J	21	14000
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	6300	< 0.35 U	5.5	47	0.23 J	0.063 J	24000	8.7		5.6	34	15000
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	6400	< 0.36 U	13	46	0.25 J	0.073 J	33000	10		5.8	22	15000
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	6500	< 0.4 U	5.4	56	0.28 J	0.093 J	17000	8.4		5.1 J	22	14000
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	6000	< 0.41 U	5.9	47	0.28 J	0.11 J	41000	8.7		5.4 J	24	14000
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	5100	< 0.34 U	4.3	62	0.18 J	0.12 J	75000	7.8		4.8 J	16	12000
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	6000	< 0.37 U	6.3	35	0.34 J	0.12 J	53000	13		4.6 J	13	12000
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	6700	< 0.36 UJ	4.7	43	0.27 J	0.12 J	17000	9.9		6.1	22	16000
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	7900	< 0.37 U	4.5	56	0.28 J	0.11 J	25000	12		6.6	24	18000
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	6000	< 0.37 U	5.8	42	0.26 J	0.11 J	25000	16		5.6	20	14000
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	6000	< 0.36 U	3.7	51	0.2 J	0.064 J	44000	7.9		5.4	14	14000
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	4600	< 0.38 U	4.6	47	0.18 J	0.084 J	89000	11		4.1 J	14	11000
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	6000	< 0.37 U	6	47	0.24 J	0.13 J	30000	9.4		5.4	23	14000
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	7000	0.43 J	5.5	60	0.28 J	0.063 J	25000	11		6.5	21	16000
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	5500	< 0.34 U	4.1	54	0.19 J	0.087 J	57000	8.2		5.2	22	13000
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated	4200	< 0.37 U	4.3	53	0.16 J	0.079 J	32000	5.5		4.2 J	15	10000
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	6200	< 0.36 U	5.5	46	0.26 J	0.062 J	15000	8.2		5.9	23	15000
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	6100	< 0.34 U	4.1	69	0.24 J	0.098 J	36000	9.8		5.3	21	15000
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	7700	< 0.37 U	10	47	0.3 J	0.098 J	26000	14		7.2	32	17000
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	5000	< 0.37 U	5.2	50	0.2 J	0.14 J	44000	6.4		4.6 J	17	12000
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	3700	< 1.8 U	3.0	32	0.12 J	0.17 J	160000	6.2		4.4 J	14	8900
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	6600	< 0.35 U	4.7	47	0.24 J	0.17 J	47000	28		5.7	86	15000
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	5000	< 0.35 U	3.4	42	0.18 J	0.095 J	41000	13		4.0 J	27	13000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	6400	< 0.41 U	5.1	47	0.25 J	0.081 J	15000	8.5		5.8 J	21	14000
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	6500	< 0.33 U	5.6	150	0.28 J	0.13 J	55000	10		6.7	24	17000
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	6400	< 0.33 U	4.3	36	0.21 J	0.09 J	44000	7.8		5.4	17	15000
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	4500	< 0.38 U	3.3	41	0.17 J	0.082 J	32000	7.4		3.8 J	14	11000
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	5000	< 0.38 U	3.5	41	0.18 J	0.079 J	38000	7.0		4.1 J	14	12000
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	6300	< 0.37 U	4.1	40	0.23 J	0.091 J	13000	8.1		4.7 J	18	15000
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	5000	0.47 J	4.1	49	0.18 J	0.20 J	35000	7.9		4.7	15	12000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	2700	0.66 J	4.3	23	0.11 J	0.12 J	130000	4.5		3.2 J	9.8	7600
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	3900	5.2	3.7	27	0.15 J	0.11 J	45000	5.7		3.6 J	15	9500
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	5700	< 0.3 U	4.5	39	0.23 J	0.05 J	13000	8.4		4.5	15	13000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	5200	< 0.034 U	3.9	86 J	0.2 J	0.1 J	24000 J	10		4.5	16	12000
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	5400	< 0.32 U	4.9	30	0.2 J	< 0.079 U	5500	10		4.6 J	13	14000
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	5000	2	58	69	0.17 J	0.6	20000	470	< 0.22 U	11	170	63000
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	4800	< 0.25 U	8.3	49	0.19 J	0.12 J	18000	26	< 0.23 U	4.7	16	13000

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	5	4400	250	< 0.034 U	10	560	< 0.034 U	< 0.034 U	73 J		< 0.038 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	5.4	4400 J	280	< 0.034 U	13	590 J	< 0.034 U	< 0.034 U	76 J		< 0.034 U
Football Field	SSHS-B3568	011921 08:30_DUP-31	DUP-31	1/18/2021	855.08	855.49	0.41	-	34 - 35 ft	34.41-35.41 ft	180-116109-1	Not Excavated	6.3	6400	390	< 0.026 U	13	830	< 0.62 UJ	< 0.13 U	92 J		< 0.39 U
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-34-36	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	855.38	0.37	-	34 - 36 ft	34.37-36.37 ft	180-115999-1	Not Excavated	5.5	4300	330	< 0.027 U	12	700	< 0.67 U	< 0.14 U	95 J		< 0.42 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-34-36	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	855.42	0.20	-	34 - 36 ft	34.2-36.2 ft	180-116070-1	Not Excavated	6.3	5400	380	< 0.023 U	13	790	< 0.58 U	< 0.12 U	95 J		< 0.36 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-34-35	SSHS-B3568-SUB-34-35	1/18/2021	855.08	855.49	0.41	-	34 - 36 ft	34.41-36.41 ft	180-116109-1	Not Excavated	6	5700	320	< 0.026 U	13	810	0.64 J	< 0.12 U	95 J		< 0.37 U
Football Field	SSHS-B3569	012021 09:30_DUP-33	DUP-33	1/19/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	180-116199-1	Not Excavated	6.8	6500	320	< 0.025 U	14	820	< 0.6 U	< 0.12 U	94 J		< 0.37 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-34-35	SSHS-B3570-SUB-34-35	1/19/2021	855.27	855.46	0.19	-	34 - 36 ft	34.19-36.19 ft	180-116199-1	Not Excavated	5.4	6900	300	< 0.023 U	11	740	0.67 J	< 0.13 U	110 J		< 0.38 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	11	6100	340	< 0.018 U	26	1400	0.75 J	< 0.11 U	85 J		< 0.33 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	7.4	6200	270	< 0.022 U	13	870	< 0.57 U	< 0.12 U	100 J		< 0.36 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	14	8300	470	< 0.026 U	34	1800	< 0.47 U	< 0.097 U	120 J		< 0.29 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	12	6400	360	< 0.034 U	28	1900	< 0.034 U	< 0.034 U	96 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	5.2	4400	240	< 0.034 U	10	530 J	< 0.034 U	< 0.034 U	69 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	5.5	5200	350	< 0.034 U	15	560	< 0.034 U	< 0.034 U	75 J		< 0.034 U
Football Field	SSHS-B3563	011621 11:00_SSHS-B3563A-SUB-36-37	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	855.38	0.37	-	36 - 37 ft	36.37-37.37 ft	180-116070-1	Not Excavated	6.2	6400	280	< 0.023 U	11	710	< 0.62 U	< 0.13 U	85 J		< 0.38 U
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-36-37	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	855.42	0.20	-	36 - 37 ft	36.2-37.2 ft	180-116070-1	Not Excavated	6.5	6500	310	< 0.023 U	13	750	< 0.62 U	< 0.13 U	95 J		< 0.39 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	6.4	4500	390	< 0.034 U	14	560	0.62 J	< 0.034 U	81 J		< 0.034 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	16	10000	470	< 0.024 U	38	2400	< 0.54 U	< 0.11 U	140 J		< 0.34 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	14	6900	420	< 0.027 U	33	1800	< 0.54 U	< 0.11 U	99 J		< 0.34 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	10	7300	390	< 0.034 U	28	1600	< 0.034 U	< 0.034 U	91 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	7.7	5600 J-	450	< 0.034 U	11	530	< 0.034 U	< 0.034 U	63 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	14	8700	460	< 0.034 U	36	1800	< 0.034 U	< 0.034 U	120 J		< 0.034 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	15	8500	530	< 0.028 U	37	2000	< 0.64 U	< 0.13 U	110 J		< 0.4 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	8.7	6800	350	< U	24	1100	< U	< U	80 J		< U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	14	9200	480	< 0.026 U	32	1800	< 0.62 U	< 0.13 U	97 J		< 0.38 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	12	6500	380	< 0.034 U	29	1600	< 0.034 U	< 0.034 U	87 J		< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	16	7300	410	< 0.034 U	34	2000	< 0.034 U	< 0.034 U	95 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	13	7600	440	< 0.034 U	32	1500	< 0.034 U	< 0.034 U	88 J		< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	13 J-	7800 J	440 J	< U	32	1700 J-	< UJ	< U	100 J		< UJ
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated	5.9	11000	440	< 0.014 U	13	780	0.85 J	< 0.11 U	100 J		< 0.34 U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	6.4	8800	480	< 0.012	14	520	0.99	< 0.04	60		< 0.15
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	16	20000	330	< 0.011	9.7	510	< 0.26	< 0.039	64		< 0.14
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	49	3200	510	0.2	87	770	2.5	< 0.11 U	130 J		< 0.34 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	8.6	15000	360	< 0.020 U	14	530	< 0.48 U	< 0.097 U	75 J		0.44 J
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	59 J+	2800	620	0.16	14	630	< 0.57 U	< 0.12 U	94 J		< 0.35 U
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	6.3	8400 J-	490	< 0.015 U	13	740	0.94 J	< 0.11 U	81 J		< 0.34 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	6.2	7300	420	< 0.015 U	14	570	0.7 J	< 0.11 U	71 J		< 0.34 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	8	9800	370	< 0.014 U	13	700	0.7 J	< 0.11 U	78 J		< 0.34 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	6.4	7600	420	< 0.014 U	13	640	0.63 J	< 0.11 U	79 J		< 0.33 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	6.9	4600	460	< 0.014 U	15	660	0.66 J	< 0.11 U	74 J		< 0.34 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	6.8	7800	500	0.018 J	13	850	< 0.6 U	< 0.12 U	63 J		< 0.37 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	13	11000	420	< 0.017 U	13	840	< 0.62 U	< 0.13 U	83 J		< 0.39 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	5.1	10000	310	< 0.019 U	12	680	0.64 J	< 0.10 U	99 J		< 0.32 U
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	4.7	36000	750	0.024 J	13		0.79 J	< 0.11 U	150 J		< 0.35 U
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	8.1	4600	440	< 0.015 U	15	920	< 0.55 U	< 0.11 U	59 J		< 0.34 U
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	8.3	7000	430	0.074	17	730	0.59 J	< 0.11 U	72 J		< 0.35 U
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	9	7600	420	< 0.014 U	14	800	< 0.56 U	< 0.12 U	85 J		< 0.35 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	5.4	7500	290	< 0.012 U	12	660	0.94 J	< 0.11 U	85 J		< 0.34 U
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	5.6	9600	270	< 0.015 U	10	700	1.6	< 0.12 U	89 J		< 0.36 U
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	9.6	12000	510	< 0.014 U	13	710	< 0.56 U	< 0.11 U	83 J		< 0.35 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	13	9300	470	< 0.017 U	16	770	< 0.6 U	< 0.12 U	70 J		< 0.37 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	7.5	11000	450	< 0.015 U	13	600	1.1	< 0.11 U	100 J		< 0.32 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated	6	5700	310	< 0.015 U	11	420 J	< 0.57 U	< 0.12 U	54 J		< 0.35 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	6.6	4400	370	< 0.013 U	14	670	< 0.55 U	< 0.11 U	< 28 U		< 0.34 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	6.1	11000	380	< 0.014 U	13	620	0.8 J	< 0.11 U	110 J		< 0.32 U
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	14	5900	630	< 0.015 U	16	970	0.64 J	< 0.11 U	84 J		< 0.35 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	6.6	6000	440	< 0.014 U	11	670	0.68 J	< 0.11 U	80 J		< 0.35 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	3.7	5800	280	< 0.021 U	10	500 J	1.2	< 0.11 U	86 J		< 0.34 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	13	5600	450	< 0.021 U	16	950	0.99 J	< 0.11 U	110 J		< 0.33 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	7.5	5300	320	0.025 J	15	490 J	< 0.53 U	< 0.11 U	81 J		< 0.33 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	11	3700	580	< 0.028 U	15	620	< 0.62 UT	< 0.13 U	< 73 U		< 0.39 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	16	7900	500	< 0.021 U	18	700	0.66 J	< 0.10 U	85 J		< 0.31 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	7	6600	290	0.028 J	15	520	< 0.49 U	< 0.1 U	70 J		< 0.31 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	5.9	7000	240	< 0.024 U	10	590	< 0.58 U	< 0.12 U	77 J		< 0.36 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	5.3	5400	280	< 0.022 U	11	600	< 0.58 U	< 0.12 U	76 J		< 0.36 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	8.0	4900	190	< 0.023 U	13	640	< 0.55 U	< 0.11 U	< 65 U		< 0.35 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	7.9	9300	480	< 0.020 U	11	570	< 0.47 U	< 0.096 U	61 J		0.46 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	9.0	3400	320	< 0.020 U	8.0	400	< 0.36 U	< 0.073 U	77 J		< 0.22 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	4.9	8000	250	< 0.020 U	8.8	360 J	< 0.47 U	< 0.096 U	72 J		0.55 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	9.8	2900	260	< 0.025 U	13	550	< 0.46 U	< 0.093 U	< 54 U		< 0.28 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	7	7800 J+	540	< 0.034 U	11	650	0.71 J	< 0.034 U	66 J		< 0.034 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	6.4	3500	270	0.022	12	500 J	0.51 J	< 0.11 U	< 55 U		< 0.3 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	92	7300	960	0.93	100	510	4	0.2 J	71 J		0.56 J
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	7.6	8100	400	0.12	14	500	< 0.38 U	< 0.085 U	61 J		< 0.23 U

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated		7.3	43
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated		7.5	35
Football Field	SSHS-B3568	011921 08:30_DUP-31	DUP-31	1/18/2021	855.08	855.49	0.41	-	34 - 35 ft	34.41-35.41 ft	180-116109-1	Not Excavated		9.5	39
Football Field	SSHS-B3563	011521 08:45_SSHS-B3563A-SUB-34-36	SSHS-B3563A-SUB-34-36	1/14/2021	855.01	855.38	0.37	-	34 - 36 ft	34.37-36.37 ft	180-115999-1	Not Excavated		6.9	34
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-34-36	SSHS-B3564A-SUB-34-36	1/15/2021	855.22	855.42	0.20	-	34 - 36 ft	34.2-36.2 ft	180-116070-1	Not Excavated		8.8	42
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-34-35	SSHS-B3568-SUB-34-35	1/18/2021	855.08	855.49	0.41	-	34 - 36 ft	34.41-36.41 ft	180-116109-1	Not Excavated		8.9	37
Football Field	SSHS-B3569	012021 09:30_DUP-33	DUP-33	1/19/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	180-116199-1	Not Excavated		9.5	40
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-34-35	SSHS-B3570-SUB-34-35	1/19/2021	855.27	855.46	0.19	-	34 - 36 ft	34.19-36.19 ft	180-116199-1	Not Excavated		7.3	31
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated		14	51
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated		9.2	39
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated		20	64
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated		18	57
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated		7.5	36
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated		7.9	42
Football Field	SSHS-B3563	011621 11:00_SSHS-B3563A-SUB-36-37	SSHS-B3563A-SUB-36-37	1/15/2021	855.01	855.38	0.37	-	36 - 37 ft	36.37-37.37 ft	180-116070-1	Not Excavated		10	38
Football Field	SSHS-B3564	011621 11:00_SSHS-B3564A-SUB-36-37	SSHS-B3564A-SUB-36-37	1/15/2021	855.22	855.42	0.20	-	36 - 37 ft	36.2-37.2 ft	180-116070-1	Not Excavated		8.6	38
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated		8.1	37
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated		23	71
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated		19	65
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated		17	58
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated		6.8	39 J-
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated		21	74
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated		21	75
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated		14	50
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated		20	62
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated		17	60
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated		21	64
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated		19	67
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated		19 J-	65 J-
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-10-12	SSHS-B3013-SUB-10-12	8/29/2019	852.90	857.00	4.10	-	10 - 12 ft	14.1-16.1 ft	180-94981-1	Not Excavated		9.1	48
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated		9.8	73
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated		7.1	36
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated		25	86
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated		9.7	48
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated		12	87
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated		10	48 J-
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated		8.7	48
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated		9.6	51
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated		9.5	50
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated		9.7	55
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated		11	47
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated		9.8	50
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated		10	41
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated		12	45
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated		11	60 J-
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated		12	67
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated		11	54
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated		8.7	46
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated		8.8	46
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated		9.9	52
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated		11	58
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated		8.2	45
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-14-16	SSHS-B3224-SUB-14-16	8/30/2019	858.38	858.48	0.10	-	14 - 16 ft	14.1-16.1 ft	180-95050-1	Not Excavated		6.4	42
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated		10	52
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated		8.8	59
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated		12	58
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated		7.7	54
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated		6.3	31
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated		12	93
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated		8.2	47
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated		9.1	50
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated		10	68
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated		8.8	49
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated		8.0	42
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated		7.9	47
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated		10	59
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated		8.3	47
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated		5.3	31
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated		7.0	38
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated		9.4	44
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated		9.5	40 J-
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated		7.3	50
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated		11	98
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated		7.8	42

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	6400	< 0.3 U	5.8	44	0.2 J	0.11 J	20000	11		5.7	33	16000
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	5600	< 0.3 U	6.8	54	0.22 J	0.17 J	26000	8.5	< 0.23 U	5	21	14000
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	5200	< 0.3 U	4.6	38	0.21 J	0.081 J	15000	9.1	< 0.22 U	5.6	16	13000
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	5100	< 0.41 U	5.5	36	0.24 J	0.097 J	37000	7.5		4.9 J	17	13000
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated	5000	< 0.36 U	4.1	63	0.19 J	0.091 J	85000	6.1		4.5 J	15	12000
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	3100	< 0.43 U	3.2	46	0.14 J	0.073 J	40000	5.2		3.2 J	12	8700
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	4700	< 0.36 U	3.6	34	0.18 J	0.10 J	33000	7.2		4.0 J	19	12000
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	6300	< 0.39 U	4.7	48	0.22 J	0.15 J	32000	9.4		5.9	22	17000
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	6300	< 0.37 U	4.1	36	0.23 J	0.16 J	63000	9.7		5.4 J	22	14000
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	4800	0.41 J	3.0	34	0.16 J	0.12 J	30000	9.7		4.2 J	14	12000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	3200	< 0.39 U	3.9	27	0.14 J	0.059 J	1700	6.1		3.0 J	11	9300
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	5300	< 0.36 U	3.1	39	0.19 J	0.087 J	33000	7.9		4.7 J	16	12000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	5100	< 0.31 UT	4.3 T	33 T	0.24 JT	0.096 JT	15000	8.0 T		5.1	20 T	13000
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	5200	< 0.38 U	3.0	43	0.16 J	0.078 J	25000	8.5		4.3 J	18	12000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	5500	< 0.31 U	3.5	43	0.20 J	0.088 J	30000	7.2		4.9	20	13000
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	4000	< 0.32 U	4.5	92	0.22 J	0.12 J	39000	6.9		4.2 J	20	12000
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	5300	< 0.34 UJ	3.5	37	0.19 J	0.085 J	46000	9.7		4.7 J	19	13000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	6000	0.37 J	5.4	50	0.28 J	0.17 J	1800	13		6.1	21	14000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	4800	0.68 J	7.1	40	0.22 J	0.17 J	21000	6.9		4.9 J	17	13000
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	5700	< 0.33 U	4.1	44	0.21 J	0.20 J	57000	8.6		4.8	15	12000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	4100	0.68 J	3.3	25	0.17 J	0.11 J	23000	5.9		3.6 J	13	9700
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	6300	< 0.24 U	3.4	37	0.21 J	0.05 J	20000	7.3		5.7	18	14000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	6700	< 0.034 U	4.3	46	0.24 J	0.063 J	19000 J	10		5.5	28 J-	16000
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	4600	< 0.33 U	4.2	36	0.18 J	0.1 J	51000	6.3		4.2 J	12	12000
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	5000	< 0.32 U	3.8	39	0.2 J	0.055 J	26000	8.9		4.4 J	16	12000
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	4800	< 0.20 U	4.1	42	0.19 J	0.048 J	28000	6.0		4.8	16	12000
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	5500	< 0.20 U	4.7	39	0.22 J	0.080 J	31000	6.7		5.3	16	13000
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	5600	< 0.22 U	4.6	38	0.21 J	0.064 J	31000	7.1		5.5	21	14000
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	5300	< 0.21 U	6.4	32	0.22 J	0.054 J	21000	6.8		5.2	17	14000
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	4100	< 0.21 U	5.0	26	0.17 J	0.055 J	26000	5.2		4.1	13	10000
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	4000	< 0.21 U	5.7	27	0.17 J	0.075 J	26000	5.4		4.7	14	11000
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	4200	< 0.18 U	4.4	35	0.18 J	0.044 J	13000	5.5		4.4	16	11000
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	10000	< 0.45 U	8.4	87	0.40 J	0.14 J	72000	13		9.8	34	26000
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	4600	< 0.21 U	6.2	30	0.19 J	0.058 J	32000	6.3		4.6	16	13000
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	6900	< 0.24 U	5.2	47	0.26 J	< 0.058 U	22000	8.8		6.9	24	16000
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	4200	< 0.23 U	3.8	33	0.17 J	0.084 J	30000	6.5		3.7 J	19	9800
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	5300	< 0.21 U	4.7	33	0.21 J	0.058 J	18000	6.9		5.0	16	13000
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	3700	< 0.23 UT	4.1	24	0.17 J	0.068 J	25000	4.9		3.7 J	12	9400
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	4000	< 0.22 U	4.5	32	0.18 J	0.066 J	24000	5.3		3.9	15	11000
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	3100	< 0.20 U	2.8	18	0.12 J	0.097 J	75000	4.0		2.9 J	11	7900
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	4900	< 0.23 U	5.2	34	0.19 J	0.086 J	24000	6.6		4.7	18	13000
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	4700	< 0.20 U	4.3	32	0.19 J	0.068 J	19000	6.0		4.5	18	12000
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	4900	0.60 J	4.7	41	0.22 J	0.080 J	22000	7.0		4.5	25	13000
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	4600	< 0.27 U	4.0	50	0.20 J	0.090 J	32000	6.0		4.0 J	15	11000
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	3800	< 0.22 U	3.9	38	0.16 J	0.085 J	29000	4.5		3.3 J	13	9100
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	3600	< 0.20 U	3.4	35	0.16 J	0.067 J	24000	4.3		3.5	13	9100
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	4000	< 0.25 U	3.8	35	0.17 J	0.083 J	31000	4.6		3.6 J	13	9400
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	3400	< 0.23 U	5.0	39	0.17 J	0.072 J	23000	4.5		3.3 J	12	9200
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	4500	< 0.25 U	4.4	29	0.17 J	< 0.061 U	20000	5.5		4.0 J	13	11000
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	4500	< 0.26 U	3.3	32	0.17 J	< 0.064 U	12000	5.9		4.0 J	19	11000
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	4600	< 0.25 U	3.5	32	0.17 J	< 0.060 U	19000	5.4		4.3	17	12000
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	4400	< 0.27 U	3.8	28	0.19 J	< 0.067 U	22000	5.8		3.7 J	14	11000
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	5300	< 0.34 U	4.5	33	0.21 J	< 0.081 U	17000	6.4		4.8 J	15	14000
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	4500	< 0.35 U	4.5	39	0.21 J	< 0.085 U	29000	6.0		4.2 J	15	11000
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	4000	< 0.27 U	3.7	26	0.16 J	< 0.066 U	27000	4.9		3.7 J	12	10000
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	5600	< 0.32 U	5.9	47	0.24 J	< 0.079 U	21000	7.2		5.2 J	17	14000
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	4300	< 0.24 U	4.7	33	0.17 J	< 0.059 U	18000	5.3		4.5	16	11000
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	3200	< 0.27 U	7.8	34	0.21 J	< 0.065 U	9400	4.8		3.5 J	19	14000
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	3700	< 0.26 U	3.3	42	0.15 J	0.13 J	62000	4.8		3.7 J	15	9500
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	3000	< 0.21 U	3.6	30	0.13 J	0.077 J	21000	3.7		3.4	12	8300
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	4300	0.33 J	5.3	28	0.20 J	< 0.076 U	17000	6.0		3.6 J	17	12000
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	4500	< 0.33 U	5.3	33	0.23 J	< 0.080 U	2900	6.4		4.5 J	15	12000
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	3800	0.36 J	3.8	27	0.17 J	< 0.070 U	21000	5.3		3.7 J	11	10000
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	4600	0.31 J	2.7	38	0.16 J	< 0.075 U	2700	5.4		4.2 J	13	11000
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	4600	< 0.33 U	4.7	31	0.19 J	< 0.079 U	8100	6.2		4.7 J	16	12000
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	5100	< 0.34 U	4.6	26	0.18 J	< 0.081 U	22000	6.6		3.7 J	18	12000
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	4900	< 0.28 U	4.4	37	0.21 J	< 0.068 U	12000	6.4		4.6	16	12000
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	4600	< 0.26 U	3.6	34	0.17 J	< 0.064 U	17000	5.8		3.9 J	12	11000
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	3600	< 0.28 U	4.3	25	0.15 J	< 0.067 U	26000	4.9		3.6 J	11	9300
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	5900	0.37 J	5.0	39	0.24 J	< 0.074 U	18000	7.8		5.2	16	14000
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	4800	< 0.27 U	5.1	35	0.21 J	< 0.065 U	3300	6.4		4.8	15	12000
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	6500	< 0.28 U	5.4	45	0.24 J	< 0.067 U	18000	7.9		5.8	17	15000
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	4900	< 0.29 U	4.5	44	0.20 J	< 0.070 U	20000	6.4		4.6 J	15	12000
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	5500 T	< 0.24 U	3.5	39	0.15 J	< 0.059 U	38000	8.6		5.4	20	13000

DRAFT

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	11	9400	500	0.059	15	500	< 0.45 U	< 0.1 U	59 J		< 0.28 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	6.1	5900	970	< 0.021 U	14	550	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	11	3100	440	0.058	13	630	< 0.46 U	< 0.1 U	< 51 U		< 0.28 U
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	6.7	6500	360	< 0.017 U	12	730	< 0.62 U	< 0.13 U	88 J		< 0.38 U
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated	4	12000	390	< 0.014 U	12	650	1.4	< 0.11 U	86 J		< 0.34 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	4.9	3400	300	< 0.016 U	7.6	370 J	0.9 J	< 0.13 U	58 J		< 0.41 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	6.7	3100	240	< 0.022 U	11	570	< 0.55 U	< 0.11 U	82 J		< 0.34 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	6.8	7100	410	< 0.022 U	14	640	< 0.59 U	< 0.12 U	95 J		< 0.37 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	5.9	5200	310	< 0.021 U	15	760	0.87 J	< 0.12 U	110 J		< 0.35 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	3.5	4800	510	0.022 J	11	510 J	< 0.55 U	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	5.5	1500	460	< 0.025 U	7.7	330 J	< 0.59 U	< 0.12 U	< 70 U		< 0.37 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	5.2	6900	500	< 0.022 U	13	560	< 0.54 U	< 0.11 U	82 J		< 0.34 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	7.2 T	3000 T	450	0.026 J	13 T	620 T	< 0.46 UT	< 0.095 UT	< 54 U		< 0.29 UT
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	6.1	6400	340	0.023 J	12	480 J	< 0.58 U	< 0.12 U	68 J		< 0.36 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	5.9	3000	380	< 0.019 U	13	420 J	< 0.46 UT	< 0.095 U	< 54 U		< 0.29 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	12	8100	480	< 0.018 U	15	460	0.50 J	< 0.098 U	65 J		< 0.30 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	4.9	4700 J+	270	< 0.021 U	12	460 J	< 0.51 U	< 0.1 U	64 J		< 0.32 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	9.0	2300	550	< 0.019 U	14	730	< 0.51 U	< 0.10 U	73 J		0.78 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	7.0	3800	290	< 0.024 U	12	580	< 0.55 U	< 0.11 U	< 64 U		0.77 J
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	7.2	6700	390	0.037	11	630	< 0.50 U	< 0.10 U	78 J		0.49 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	5.6	6000	240	< 0.019 U	8.8	480	< 0.47 U	< 0.096 U	69 J		0.45 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	7.9	3900	340	< 0.019 U	12	430	0.67 J	< 0.073 U	42 J		< 0.22 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	14	5300	390	< 0.034 U	14	770	0.54 J	< 0.034 U	81 J		< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	5.9	5800	360	< 0.019 U	11	520	1	< 0.1 U	81 J		< 0.31 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	7.2	6500	420	< 0.022 U	11	640	0.53 J	< 0.098 U	59 J		< 0.3 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	5.2	3100	280	< 0.022 U	12	410	< 0.30 U	< 0.068 U	63 J		< 0.19 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	6.1	3200	420	< 0.015 U	14	390	0.31 J	< 0.070 U	89 J		< 0.19 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	6.9	3000	390	< 0.023 U	14	450	< 0.34 U	< 0.077 U	55 J		< 0.21 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	6.8	6700	260	< 0.022 U	13	440	< 0.32 U	< 0.072 U	48 J		< 0.20 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	5.4	2700	250	< 0.018 U	11	440	< 0.32 U	< 0.072 U	44 J		< 0.20 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	19	3200	240	< 0.016 U	10	430	< 0.31 U	< 0.070 U	44 J		< 0.19 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	6.2	4400	320	< 0.016 U	11	420	< 0.27 U	< 0.061 U	38 J		< 0.17 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	9.6	6800	750	< 0.036 U	25	850	0.71 J	< 0.16 U	87 J		< 0.42 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	7.1	3400	190	< 0.019 U	12	420	0.48 J	< 0.072 U	41 J		< 0.20 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	8.1	4400	310	< 0.020 U	19	480	0.40 J	< 0.082 U	46 J		< 0.22 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	14	2200	230	0.041	14	360 J	0.37 J	< 0.079 U	52 J		< 0.22 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	5.9	3900	250	< 0.020 U	13	420	0.38 J	< 0.073 U	47 J		< 0.20 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	4.8	2700	240	< 0.023 U	9.3	420 T	< 0.35 U	< 0.078 U	45 J		< 0.21 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	6.1	5000	360	< 0.023 U	10	410	0.45 J	< 0.074 U	45 J		< 0.20 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	4.7	4400	160	< 0.018 U	7.3	330 J	0.82	< 0.070 U	83 J		< 0.19 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	7.0	4100	280	< 0.024 U	13	480	< 0.35 U	< 0.078 U	52 J		< 0.21 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	6.1	4600	280	< 0.020 U	12	400	0.47 J	< 0.068 U	43 J		< 0.19 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	49	2800	290	0.021 J	16	440	0.60 J	< 0.077 U	56 J		1.1 J
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	5.7	4200	320	< 0.013 U	11	380 J	0.49 J	< 0.093 U	94 BJ		< 0.25 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	4.4	3700	240	< 0.019 U	9.0	390	0.41 J	< 0.077 U	89 BJ		< 0.21 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	4.5	2500	220	< 0.017 U	8.7	360	0.36 J	< 0.067 U	69 BJ		< 0.18 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	5.2	11000	310	< 0.017 U	9.6	380 J	< 0.38 U	< 0.085 U	100 BJ		< 0.23 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	5.0	2200	240	< 0.017 U	8.4	340 J	< 0.35 U	< 0.079 U	74 BJ		< 0.22 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	5.2	4900	220	< 0.016 U	11	370 J	0.66 J	< 0.087 U	46 J		< 0.24 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	6.2	4400	170	< 0.022 U	11	370 J	< 0.40 U	< 0.090 U	47 J		< 0.25 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	4.4	3100	210	< 0.021 U	12	310 J	0.56 J	< 0.085 U	45 J		< 0.23 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	5.1	4300	210	< 0.026 U	10	420 J	< 0.42 U	< 0.094 U	58 J		< 0.26 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	5.5	3200	280	< 0.023 U	12	360 J	< 0.51 U	< 0.12 U	83 J		< 0.31 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	8.5	12000	300	< 0.022 U	11	660	0.83 J	< 0.12 U	73 J		< 0.33 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	4.7	2600	240	< 0.025 U	9.4	370 J	0.58 J	< 0.094 U	53 J		< 0.26 U
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	6.9	4000	290	< 0.022 U	13	480 J	< 0.49 U	< 0.11 U	< 55 U		< 0.30 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	5.8	3600	180	0.026 J	11	420	0.41 J	< 0.083 U	< 41 U		< 0.23 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	13	3900	420	< 0.021 U	9.4	560	< 0.41 U	< 0.092 U	< 45 U		< 0.25 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	5.3	6600	290	< 0.015 U	10	310 J	1.0	< 0.090 U	62 J		< 0.25 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	10	4000	260	< 0.013 U	8.4	280 J	0.68	< 0.071 U	42 J		< 0.19 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	6.3	6300	260	< 0.0086 U	9.3	630	< 0.48 U	< 0.11 U	88 BJ		< 0.29 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	6.7	2600	290	< 0.0086 U	10	840	< 0.51 U	< 0.11 U	89 BJ		< 0.31 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	4.6	2700	260	< 0.0082 U	9.0	570	< 0.44 U	< 0.10 U	71 BJ		< 0.27 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	5.2	2700	230	0.0090 J	9.1	620	< 0.47 U	< 0.11 U	76 BJ		< 0.29 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	6.3	3100	280	< 0.0085 U	11	520 J	< 0.50 U	< 0.11 U	72 BJ		< 0.31 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	5.5	4500	220	0.013 J	9.9	560	< 0.51 U	< 0.12 U	79 BJ		< 0.31 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	5.6	3900	290	< 0.0083 U	11	610	< 0.42 U	< 0.096 U	69 BJ		< 0.26 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	7.1	6800	290	0.024	9.7	490	< 0.40 U	< 0.090 U	64 BJ		< 0.25 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	5.1	5300	260	< 0.0079 U	8.7	510	< 0.42 U	< 0.096 U	72 BJ		< 0.26 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	7.2	5500	300	0.014 J	13	700	< 0.46 U	< 0.10 U	58 BJ		< 0.28 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	5.8	2100	330	0.0096 J	11	720	< 0.41 U	< 0.093 U	46 J		< 0.25 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	7.1	4600	330	0.0089 J	14	680	< 0.42 U	< 0.095 U	52 J		< 0.26 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	6.3	4900	340	< 0.0085 U	12	600	< 0.44 U	< 0.099 U	52 J		< 0.27 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	4.8	5600	480 B	< 0.020 U	13	320 J	0.70 J	< 0.083 U	70 J		< 0.23 U

DRAFT

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated		9.2	65
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated		7.8	61
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated		8.3	36
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated		10	43
Northern Athletic Field	SSHS-B3222	083119 10:15_SSHS-B3222-SUB-16-18	SSHS-B3222-SUB-16-18	8/30/2019	858.28	858.08	-0.20	-	16 - 18 ft	15.8-17.8 ft	180-95047-2	Not Excavated		8.1	40
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated		6.1 J	28
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated		8.6	43
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated		11	61
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated		9.9	55
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated		7.7	42
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated		5.7 J	40
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated		8.5	46
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated		8.8 T	43 T
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated		7.7	48
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated		7.9	50
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated		6.7	45
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated		7.8	46
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated		11	57
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated		9.4	47
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated		9.4	57
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated		7.1	39
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated		9.1	39
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated		12	52 J-
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated		7.8	45
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated		8.6	43
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated		7.8	38
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated		8.0	51
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated		9.1	48
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated		8.6	45
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated		6.4	29
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated		7.3	59
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated		7.8	42
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated		17	84
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated		9.1	42
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated		10	69
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated		5.9	40
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated		8.2	50
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated		6.1	29
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated		6.7	44
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated		5.2	27
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated		8.6	47
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated		7.5	44
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated		7.4	54
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated		6.5	42
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated		6.0	34
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated		6.4	31
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated		6.2	38
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated		5.9	32
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated		6.6	47
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated		6.8	47
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated		7.2	42
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated		6.8	38
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated		7.7	54
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated		8.6	43
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated		6.0	39
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated		8.5	45
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated		7.1	40
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated		6.5	50
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated		5.4	35
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated		5.3	33
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated		9.5	43
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated		9.2	42
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated		7.6	37
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated		9.0	45
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated		8.2	47
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated		8.3	45
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated		8.3	54
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated		7.3	48
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated		6.7	39
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated		9.9	46
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated		8.7	47
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated		9.9	59
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated		8.0	47
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated		8.6	45 B

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	3900 T	< 0.35 U	3.9	30	0.16 J	0.10 J	56000	5.4		3.9 J	19	10000
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	4200	< 0.35 U	4.6	26	0.17 J	0.097 J	30000	6.9		4.0 J	19	11000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	5200	< 0.38 U	3.5	39	0.17 J	0.080 J	18000	7.7		4.8 J	21	12000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	4000	< 0.30 U	3.3	25	0.17 J	0.091 J	50000	6.3		3.7 J	11	9800
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	4000	< 0.31 U	3.2	31	0.15 J	0.091 J	77000	6.1		3.7 J	16	9900
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	3000	< 0.35 U	2.1	24	0.12 J	0.044 J	14000	3.6		2.5 J	15	7300
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	6500	< 0.33 U	3.9	43	0.23 J	0.071 J	21000	8.4		5.6	39	15000
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	4900	< 0.34 U	3.9	54	0.20 J	0.090 J	30000	6.9		4.6 J	16	13000
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	6000	< 0.31 U	5.1	40	0.21 J	0.092 J	63000	7.8		5.4	20	15000
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	4300	< 0.40 U	2.9	24	0.15 J	0.065 J	16000	5.1		3.2 J	11	10000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	5400	0.48 J	4.3	41	0.21 J	0.16 J	8600	7.5		4.9	19	13000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	5800	0.55 J	5.3	36	0.25 J	0.17 J	29000	8.1		5.2 J	19	14000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	3400	0.75	3.1	27	0.14 J	0.13 J	47000	4.9		3.4	11	8700
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	6300	< 0.33 U	4.4	43	0.25 J	0.053 J	36000	8.9		5.3	21	14000
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	5100	< 0.034 U	4.9	60	0.2 J	0.085 J	59000	9.4		4.6 J	18	12000
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	4400	< 0.31 U	3.8	34	0.15 J	0.065 J	42000	6.1		3.9 J	15	10000
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	4900	< 0.23 U	4	39	0.18 J	0.053 J	33000	7		5.3	15	12000
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	4400	< 0.21 U	3.3	28	0.17 J	0.063 J	32000	5.1		3.9	13	9900
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	3900	< 0.22 U	4.2	27	0.17 J	0.064 J	30000	4.9		4.0	13	10000
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	4000	< 0.23 U	3.9	29	0.17 J	0.065 J	26000	5.2		4.1	15	11000
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	3800	< 0.23 U	4.6	24	0.19 J	< 0.055 U	3500	5.0		3.6 J	13	10000
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	4400	< 0.23 U	5.0	28	0.20 J	0.059 J	18000	5.9		4.7	22	12000
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	3800	< 0.21 U	5.0	26	0.16 J	0.071 J	26000	4.9		3.9	14	9800
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	6900	0.34 J	9.6	150	0.36	0.22 J	36000	8.6		9.3	35	17000
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	6900	0.33 J	3.9	49	0.27 J	< 0.068 U	1900	8.2		5.1	15	13000
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	5200	0.29 J	4.5	34	0.20 J	0.076 J	32000	6.5		4.6	18	12000
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	5800	< 0.35 U	3.7	46	0.20 J	< 0.086 U	11000	6.9		4.9 J	13	14000
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	4600	0.27 J	4.4	36	0.19 J	0.10 J	23000	6.1		4.4	15	12000
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	4400	0.52 J	3.8	34	0.19 J	< 0.080 U	19000	5.7		4.1 J	13	12000
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	5000	0.30 J	4.0	33	0.19 J	0.064 J	14000	6.7		4.6	14	12000
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	3500 T	< 0.16 U	4.6	24	0.14 J	0.085 J	45000	5.0		3.9	17	9600
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	4500 T	< 0.25 U	5.8	30	0.21 J	0.097 J	32000	6.6		5.0	21	13000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	4100 T	< 0.37 UT	3.3	31 T	0.16 J	0.070 J	36000 T	6.9 T		4.3 J	12	10000 T
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	6400	< 0.32 U	3.5	38	0.23 J	0.081 J	41000	8.6		5.8	17	15000
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	4600	< 0.36 U	4.3	45	0.18 J	0.10 J	43000	7.8		4.6 J	25	12000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	5600	< 0.36 U	5.7	38	0.22 J	0.064 J	55000	7.7		4.9 J	18	13000
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	5800	< 0.33 U	3.5	37	0.19 J	0.091 J	52000	7.3		5.4	17	14000
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	6400	< 0.35 U	3.9	40	0.21 J	0.097 J	52000	7.7		5.6	16	16000
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	3800	< 0.35 U	10	23	0.15 J	0.092 J	31000	5.2		3.5 J	16	10000
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	4800	0.39 J	4.0	35	0.18 J	0.16 J	26000	6.1		4.4 J	15	13000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	5600	< 0.34 U	6.2	38	0.21 J	0.17 J	18000	8.6		5.0	15	14000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	5100	0.83 J	2.7	35	0.19 J	0.16 J	38000	6.6		4.5 J	19	12000
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	5700	0.61 J	4.2	37	0.21 J	0.16 J	19000	7.4		5.5	27	14000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	3600	0.35 JT	4.1	23	0.16 J	0.16 JT	45000 T	5.3		3.3 J	13	9400
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	6400	< 0.28 U	3.6	42	0.22 J	0.089 J	65000	8.1		5.5	15	15000
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	6000	< 0.034 U	4.4	40	0.24 J	0.061 J	28000	8.2		5.2 J	20	14000
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	4800 T	< 0.27 U	5.2	30	0.14 J	< 0.065 U	28000	5.9		4.2 J	16	12000
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	4200 T	< 0.18 U	3.7	31	0.15 J	< 0.044 U	23000	7.8		4.2	18	11000
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	5100	< 0.31 U	4.0	27	0.18 J	0.13 J	73000	6.4		4.7	19	12000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	4300	< 0.35 U	5.4	26	0.15 J	0.060 J	53000	5.7		4.9 J	15	10000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	5400	< 0.30 U	2.8	32	0.20 J	0.095 J	33000	7.9		4.9	17	12000
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	3600	< 0.37 U	3.3	21 J	0.14 J	0.30 J	32000	4.3		2.8 J	11	9000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	4000	< 0.32 U	3.9	25	0.16 J	0.053 J	35000	5.6		3.4 J	13	10000
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	5700	< 0.34 U	3.4	37	0.19 J	0.11 J	39000	7.7		5.1	20	14000
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	3600	< 0.35 U	4.9	25	0.15 J	0.056 J	36000	5.2		3.0 J	11	9000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	4200	< 0.39 U	4.3	35	0.16 J	0.16 J	45000	5.4		3.8 J	12	10000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	6400	0.90 J	3.1	46	0.21 J	0.17 J	34000	7.2		6.5	21	16000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	4000	0.47 J	4.3	24	0.15 J	0.11 J	31000	8.7		3.5 J	14	9900
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	8600	< 0.38 U	7.1	54	0.31 J	0.083 J	40000	11		7.9	30	20000
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	7000	< 0.034 U	4.5	42	0.27 J	0.054 J	23000	10		5.6 J	18	16000
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	3900 T	< 0.29 U	2.8	23	0.14 J	< 0.070 U	28000	5.1		3.6 J	14	9600
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	4300 T	< 0.22 U	4.9	32	0.16 J	< 0.053 U	40000	28		4.5	18	12000
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508423	Not Excavated									< 0.25 U			
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	16000	< 0.39 UT	12	140 T	0.72	0.079 J	16000	20		15	22	32000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	9600	< 0.38 U	7.7	89	0.43 J	0.044 J	11000	13		9.0	15	20000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	4600	< 0.36 U	2.9	28	0.19 J	0.059 J	39000	6.1		3.8 J	16	10000
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	10000	< 0.38 U	6.5	56	0.36 J	0.072 J	19000	14		9.1	23	23000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	4900	< 0.31 U	2.8	25	0.13 J	0.087 J	110000	5.9		4.0 J	18	11000
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	2900	< 0.34 U	2.7	22	0.10 J	0.079 J	55000	4.1		2.6 J	10	7200
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	3900	< 0.37 U	3.6	24	0.14 J	0.10 J	41000	5.7		3.4 J	16	9900
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	3200	< 0.38 U	1.1	23	0.099 J	0.082 J	18000	4.0		2.6 J	6.8	7200
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	4700	1.1	3.1	39	0.18 J	0.15 J	74000	26		4.4 J	17	13000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	5000	0.54 J	3.8	35	0.16 J	0.10 J	22000	6.9		4.6	30	11000
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	5700	< 0.27 U	4.1	39	0.21 J	0.075 J	24000	7.6		5.5	29	14000

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	11	5100	330 B	< 0.025 U	11	440 J	0.81 J	< 0.12 U	98 J		< 0.33 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	7.4	7000	250	< 0.021 U	10	530	0.60 J	< 0.11 U	94 J		< 0.33 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	4.3	3000	480	0.025 J	13	560	< 0.58 U	< 0.12 U	76 J		< 0.36 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	4.8	3300	400	0.027 J	10	540	0.64 J	< 0.093 U	75 J		< 0.28 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	4.2	12000	330	0.022 J	10	490	0.84 J	< 0.097 U	70 J		< 0.30 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	4.0	3300	400	< 0.023 U	7.0	300 J	< 0.53 UT	< 0.11 U	< 63 U		< 0.33 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	7.1	3500	360	< 0.021 U	15	400 J	< 0.50 UT	< 0.10 U	< 59 U		< 0.31 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	7.1	5000	310	< 0.020 U	12	490 J	< 0.52 U	< 0.11 U	62 J		< 0.32 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	7.1	10000	420	< 0.018 U	14	630	0.67 J	< 0.097 U	77 J		< 0.3 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	4.9	3500	150	< 0.023 U	8.6	420 J	< 0.61 U	< 0.12 U	88 J		< 0.38 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	6.8	4800	370	< 0.023 U	11	570	< 0.49 U	< 0.10 U	73 J		0.62 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	7.2	4100	270	< 0.024 U	13	790	< 0.56 U	< 0.11 U	92 J		0.70 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	5.5	6700	530	< 0.022 U	8.3	430	< 0.33 U	< 0.068 U	75 J		0.23 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	9.1	5500	410	< 0.021 U	13	720	< 0.49 U	< 0.1 U	81 J		< 0.31 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	8.9	6700	360	< 0.034 U	12	640	1.3	< 0.034 U	87 J		< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	6.3	6100	350	< 0.022 U	9.9	480	0.85 J	< 0.095 U	85 J		< 0.29 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	6	4200	380	< 0.019 U	13	470	0.47 J	< 0.072 U	60 J		< 0.22 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	4.5	9700	230	< 0.023 U	9.8	350	0.58 J	< 0.072 U	75 J		0.73 J
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	5.9	11000	230	< 0.019 U	9.4	420	0.34 J	< 0.074 U	58 J		< 0.20 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	5.6	5400	350	< 0.023 U	10	340 J	0.36 J	< 0.080 U	53 J		< 0.22 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	5.0	2100	110	< 0.021 U	9.4	440	< 0.34 U	< 0.078 U	53 J		< 0.21 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	6.3	4500	290	< 0.024 U	12	440	< 0.36 U	< 0.080 U	55 J		< 0.22 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	5.4	5900	240	< 0.023 U	9.6	440	0.56 J	< 0.073 U	65 J		< 0.20 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	18	13000	940	0.027	20	1000	0.67 J	< 0.094 U	110 J		< 0.26 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	23	2200	280	0.034	13	700	< 0.43 U	< 0.096 U	69 BJ		< 0.26 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	8.4	5000	490	0.017 J	12	600	0.43 J	< 0.093 U	67 J		< 0.25 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	13	5000	350	0.099	12	490 J	< 0.54 U	< 0.12 U	< 60 U		< 0.33 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	9.5	5400	390	0.018	11	540	0.40 J	< 0.082 U	74 BJ		< 0.22 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	6.8	3900	420	< 0.0098 U	10	590	< 0.50 U	< 0.11 U	80 BJ		< 0.31 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	10	4300	220	0.0088 J	11	570	< 0.37 U	< 0.083 U	70 BJ		< 0.23 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	5.9	5700	240 B	< 0.022 U	11	340	0.57	< 0.055 U	75 J		< 0.15 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	7.9	7300	190 B	< 0.022 U	14	520	0.78 J	< 0.087 U	86 J		< 0.24 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	4.6	14000 T	210 T	< 0.024 U	11	400 J	0.60 J	< 0.12 U	74 J		< 0.35 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	6.2	4000	270	0.023 J	16	570	0.49 J	< 0.098 U	81 J		< 0.30 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	5.0	4900	370	0.023 J	13	450 J	< 0.54 U	< 0.11 U	71 J		< 0.34 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	6.0	9800	430	< 0.023 U	14	560	0.77 JT	< 0.11 U	78 J		< 0.34 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	6.5	5600	390	0.027 J	14	490	0.59 J	< 0.10 U	72 J		< 0.31 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	7.1	5200	350	< 0.021 U	15	480 J	0.54 J	< 0.11 U	69 J		< 0.33 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	5.2	4500	260	< 0.024 U	9.3	390 J	< 0.53 U	< 0.11 U	< 62 U		< 0.33 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	5.4	4100	330	< 0.023 U	10	450 J	< 0.50 U	< 0.10 U	< 59 U		0.48 J
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	5.3	3600	330	< 0.023 U	12	510	< 0.52 U	< 0.11 U	68 J		0.49 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	4.8	4100	260	< 0.018 U	11	560	< 0.49 U	< 0.10 U	74 J		0.56 J
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	17	4900	350	< 0.023 U	13	430 J	< 0.53 U	< 0.11 U	62 J		0.71 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	5.8	8100 T	240	< 0.023 U	8.0	430	< 0.44 U	< 0.090 U	85 J		0.38 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	7	8100	390	< 0.018 U	14	650	0.96	< 0.086 U	85 J		< 0.26 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	9.1	8100	370	< 0.034 U	13	820	0.68 J	< 0.034 U	84 J		< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	6.2	4100	300 B	< 0.019 U	11	350 J	0.46 J	< 0.092 U	72 J		< 0.25 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	7.2	4200	200 B	< 0.015 U	11	290 J	0.45 J	< 0.062 U	66 J		< 0.17 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	4.3	7000	340	< 0.022 U	13	470	0.65 J	< 0.097 U	81 J		< 0.29 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	5.9	24000	310	< 0.022 U	11	550	0.70 J	< 0.11 U	120 J		< 0.33 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	4.8	5600	330	0.024 J	13	430 J	0.50 J	< 0.094 U	67 J		< 0.29 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	62	5100	320	< 0.022 U	7.5	400 J	< 0.55 U	< 0.11 U	67 J		< 0.35 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	7.3	6100	220	< 0.022 U	9.3	390 J	< 0.49 UT	< 0.10 U	63 J		< 0.30 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	5.2	6200	340	< 0.018 U	14	490 J	0.71 J	< 0.11 U	70 J		< 0.32 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	4.5	4900	200	< 0.020 U	7.9	460 J	< 0.54 U	< 0.11 U	67 J		< 0.33 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	7.1	3500	360	< 0.020 U	8.8	390 J	< 0.59 U	< 0.12 U	82 J		0.43 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	4.8	12000	340	< 0.020 U	10	600	< 0.57 U	< 0.12 U	160 J		0.67 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	6.0	4300	190	< 0.022 U	8.8	440 J	< 0.51 U	< 0.10 U	78 J		0.39 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	9.1	12000	430	< 0.021 U	20	770	0.59 J	< 0.12 U	72 J		< 0.36 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	6.4	5000	380	< 0.034 U	15	840	< 0.034 U	< 0.034 U	86 J		< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	3.8	2600	220 B	< 0.015 U	9.8	330 J	< 0.44 U	< 0.099 U	79 J		< 0.27 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	7.7	8600	330 B	< 0.019 U	13	400	0.49 J	< 0.075 U	86 J		< 0.20 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508423	Not Excavated											
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	14	6700 T	620	< 0.028 U	34	1900 T	< 0.59 U	< 0.12 U	120 J		< 0.37 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	9.4	5200	430	< 0.022 U	21	1200	< 0.58 U	< 0.12 U	83 J		< 0.36 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	5.0	7600	280	< 0.022 U	11	440 J	< 0.55 UT	< 0.11 U	< 65 U		< 0.34 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	8	7100	350	< 0.025 U	22	880	< 0.58 U	< 0.12 U	74 J		< 0.36 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	3.8	3800	310	0.023 J	11	400 J	0.86 J	< 0.096 U	69 J		< 0.29 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	3.8	5400	290	< 0.023 U	7.2	390 J	0.80 J	< 0.11 U	68 J		< 0.32 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	4.7	4000	330	< 0.022 U	9.2	560	< 0.57 U	< 0.12 U	80 J		< 0.35 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	2.1	3800	130	< 0.019 U	6.2	260 J	< 0.58 U	< 0.12 U	< 68 U		0.50 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	5.9	10000	350	< 0.020 U	12	430 J	< 0.49 U	< 0.10 U	88 J		0.38 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	4.4	4000	240	< 0.020 U	10	450	< 0.41 U	< 0.083 U	76 J		0.49 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	12	2800	900	< 0.018 U	13	490	0.56 J	< 0.085 U	< 49 U		< 0.26 U

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated		6.6	41 B
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated		7.5	45
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated		8.6	58
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated		7.8	35
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated		7.3	32
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated		4.1 J	28
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated		8.6	57
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated		7.3	49
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated		9.3	52
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated		6.7	37
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated		9.6	49
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated		11	47
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated		6.9	36
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated		10	45
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated		8.1	55
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated		6.9	38
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated		7.5	43
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated		5.7	39
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated		6.7	34
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated		6.4	42
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated		6.2	36
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated		6.8	46
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated		5.8	34
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated		12	76
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated		11	57
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated		8.9	51
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated		9.4	56
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated		8.3	44
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated		8.6	50
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated		9.0	47
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated		6.4	39 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated		7.9	60 B
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated		7.1	45 T
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated		9.6	50
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated		7.8	46
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated		7.8	45
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated		8.3	55
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated		8.9	56
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated		6.2	38
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated		8.9	45
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated		9.2	52
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated		9.3	43
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated		9.4	70
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated		7.1	39
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated		9.8	49
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated		11	51
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated		8.3	37 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated		6.5	39 B
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated		7.2	50
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated		7.6	37
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated		7.4	43
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated		5.3 J	76
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated		6.5	39
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated		8.4	53
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated		6.5	34
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated		6.8	41
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated		27	45
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated		6.9	51
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated		13	70
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated		11	54
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated		6.0	35 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated		7.8	42 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508423	Not Excavated			
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated		21	74 T
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated		13	48
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated		6.8	42
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated		13	65
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated		6.7	34
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated		5.2	32
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated		7.4	40
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated		4.7 J	30
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated		7.8	38
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated		7.8	47
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated		7.9	48

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Aluminum	Antimony	Arsenic	Barium	Beryllium	Cadmium	Calcium	Chromium (III+VI)	Chromium, Hexavalent	Cobalt	Copper	Iron
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															13	350	7.2	2.5		30	1		50	
Restricted - Residential															16	400	72	4.3		110	110		270	
Protection of Groundwater															16	820	47	7.5		19	19		1720	
Potential to exhibit the characteristic of toxicity															100	2000		20		100				
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	5200	< 0.034 U	3.3	35	0.21 J	0.049 J	16000	7		4.5 J	15	13000
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	3500 T	< 0.21 U	3.4	29	0.12 J	< 0.052 U	28000	4.8		3.3 J	14	8500
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	3300 T	< 0.23 U	3.1	22	0.13 J	< 0.055 U	30000	5.2		3.2 J	15	8300
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	10000	< 0.41 U	6.5	48	0.46 J	0.064 J	11000	14		10	16	23000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	10000	< 0.42 U	6.6	56	0.48 J	0.047 J	11000	14		10	15	23000
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	13000	< 0.41 UT	9.3 T	79	0.59 T	0.056 JT	9500 T	16 T		11 T	16 T	25000
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	13000	< 0.43 U	12	81	0.59	0.046 J	10000	16		12	16	25000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	3100	< 0.28 U	2.8	23	0.13 J	0.087 J	27000	4.4		2.9 J	10	7700
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	9900	< 0.32 U	6.1	69	0.46	0.073 J	15000	14		9.3	15	20000
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	13000	< 0.37 U	9.6	130	0.56	0.086 J	12000	17		12	17	27000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	5100	0.62 J	2.7	29	0.17 J	0.15 J	37000	6.2		4.7 J	15	12000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	5700	< 0.31 UT	7.0	54 T	0.22 J	0.12 J	36000 T	7.3 T		6.2	23 T	17000 T
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	4900	0.69 J	3.1	28	0.16 J	0.12 J	24000	7.7		4.4 J	17	12000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	7500	< 0.33 U	5.2	49	0.26 J	0.055 J	40000	9.5		6.7	25	17000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	6700	< 0.034 U	4.8	43	0.23 J	0.035 J	26000	8.6		6.5	23	16000
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	11000 T	< 0.34 U	13	70	0.48	< 0.081 U	14000	16		12	20	25000
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	3800 T	< 0.25 U	4.0	26	0.16 J	< 0.061 U	34000	5.3		3.8 J	15	9400
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	19000	< 0.39 U	10	170	1.0	0.065 J	3500	24		17	23	35000
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	3200	< 0.22 U	3.2	23	0.14 J	0.066 J	35000	4.8		3.3	11	8000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	4400	< 0.36 U	3.1	32	0.17 J	0.070 J	42000	5.7		3.9 J	15	11000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	5700	0.45 J	3.5	43	0.18 J	0.23 J	54000	7.3		4.7 J	18	14000
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	13000	< 0.44 U	8.9	110	0.56	0.073 J	7400	18		13	16	27000
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	11000	0.73 J	4.9	47	0.43	0.19 J	13000	14		9.9	16	20000
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	13000	0.98 JT	9.3 T	94 T	0.54 T	0.21 JT	10000 T	17 T		12 T	17 T	25000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	3100	< 0.32 U	2.1	54	0.14 J	4.1	9200	93		2.9 J	40	6300
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	5600	< 0.034 U	3.3	30	0.18 J	< 0.034 U	20000	6.8		4.6	13	14000
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	4000 T	< 0.22 U	3.2	21	0.14 J	< 0.053 U	36000	5.4		3.5 J	16	10000
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	13000	< 0.36 U	8.0	78	0.60	0.074 J	11000	17		12	17	25000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217043	Not Excavated									< 0.28 U			
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	17000	0.78 J	7.8	83	0.71	0.34 J	16000	21		15	23	30000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	6200	0.37 J	8.2	110	0.39	5.6	3900	490		6	220	15000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	7100	< 0.034 U	4.2	45	0.26 J	0.058 J	50000	8.6		6.2	21	15000
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	14000 T	< 0.30 UT	12	95 T	0.62	< 0.074 U	12000	20		15	21	31000
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508423	Not Excavated									< 0.27 U			
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	14000	0.72 JT	6.6	88 T	0.62 T	0.20 JT	14000	19 T		12	18 T	26000
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-32-34-20210513	SSHS-B3891-SUB-32-34	5/13/2021	856.89	856.55	-0.34	-	32 - 34 ft	31.66-33.66 ft	1801217043	Not Excavated									< 0.27 U			
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	6500	< 0.25 U	4.1	40	0.26 J	0.057 J	55000	8.5		6.1	20	15000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	6400	< 0.034 U	4.9	39	0.24 J	0.072 J	39000	7.9		5.5	22	15000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	5900	< 0.27 U	5	36	0.23 J	0.055 J	44000	8.1		5.6	19	14000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	5100	< 0.034 U	3.9	32	0.21 J	0.087 J	79000	6.6		4.6	17	12000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	5900	< 0.35 UJ	3.6	31	0.22 J	< 0.038 U	48000	7.4		5.1 J	18	14000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	5800	< 0.034 U	4.8	35	0.26 J	0.049 J	34000	7.6		5.2	18	14000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	7300	< 0.36 U	5.6	44	0.27 J	< 0.039 U	31000	9.9		5.9	17	16000
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	19000	< 0.034 U	17	140	0.91	< 0.034 U	13000	26		17	25	36000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	11000	< 0.34 U	5	57	0.5	< 0.037 U	18000	15		9.7	51	23000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	5600	< 0.27 U	4.3	35	0.22 J	0.055 J	43000	7.8		4.8	16	13000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	11000	< 0.37 U	4.4	68	0.43	< 0.039 U	25000	14		9.7	19	24000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	15000	< 0.35 U	5.9	130	0.69	< 0.038 U	19000	18		11	18	25000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	8200	< 0.31 U	4.5	62	0.3 J	< 0.033 U	67000	9.7		7.1	15	16000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	6100	< 0.38 U	4.9	39	0.24 J	0.062 J	38000	8.7		5.4 J	17	14000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	5500	< 0.26 U	5	34	0.24 J	0.064 J	45000	7.6		5.3	17	14000
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	6100	< 0.4 U	5.2	40	0.25 J	< 0.043 U	34000	8.3		5.5 J	18	15000
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated	8700	< 0.39 U	5.5	85	0.36 J	0.16 J	4900	33		7.8	31	20000
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated			15									
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated			9.2									
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	3800	< 0.32 U	7.0	27	0.17 J	< 0.077 U	940	7.0		4.1 J	16	11000
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	5200	< 0.18 U	11	46	0.19 J	0.063 J	10000	7.4		3.8	15	15000
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-836-834-20240812	SSHS-SPA4-B5506-ELEV-836-834	8/12/2024	852.03	852.03	0.00	-	16.03-18.03 ft	16.03-18.03 ft	1801782961	Not Excavated	5600	< 0.42 U	5.6	55	0.28 J	0.17 J	2000	8.4		5.4	22	15000
Rear Parking Lot	SPA4-B5507	SSHS-SPA4-B5507-ELEV-834-832-20240813	SSHS-SPA4-B5507-ELEV-834-832	8/13/2024	850.07	850.07	0.00	-	16.07-18.07 ft	16.07-18.07 ft	1801783741	Not Excavated	5500	< 0.42 UT	8.0	65	0.17 J	0.075 J	890	12		3.3	27	23000
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	5900	< 0.034 U	5.5	60	0.2 J	0.067 J	14000	7.4		5.2	13	15000
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	4700 J	< 0.034 U	4.2	68 J-	0.18 J	0.059 J	44000 J	8.1		4.5	16	11000
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	6300	< 0.034 U	6.3	61	0.3 J	0.064 J	7000	9.7		6.2	21	17000
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	4600	< 0.034 U	3.5	28	0.15 J	0.11 J	41000	6		4.5 J	18	11000

													Lead	Magnesium	Manganese	Mercury	Nickel	Potassium	Selenium	Silver	Sodium	Sulfide	Thallium
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													63		1600	0.18	30		3.9	2			
Restricted - Residential													400		2000	0.81	310		180	180			
Protection of Groundwater													450		2000	0.73	130		4	8.3			
Potential to exhibit the characteristic of toxicity													1000			4			20	100			
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	5.3	3000	390	< 0.034 U	11	590	0.8 J	< 0.034 U	71 J		< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	4.3	3700	230 B	< 0.016 U	8.4	330 J	0.36 J	< 0.074 U	82 J		< 0.20 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	4.6	4400	200 B	< 0.022 U	8.0	330 J	0.40 J	< 0.078 U	78 J		< 0.21 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	9.9	7200	350	0.034 J	24	1200	< 0.62 U	< 0.13 U	85 J		< 0.38 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	10	6900	320	0.032 J	24	1200	< 0.63 U	< 0.13 U	81 J		< 0.39 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	12 T	7000	350	0.033 J	27 T	1700	< 0.62 WARN	< 0.13 UT	96 JT		< 0.39 UT
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	12	6400	390	0.030 J	27	1700	< 0.65 U	< 0.13 U	100 J		< 0.40 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	4.8	3600	210	0.025 J	7.3	420	< 0.43 U	< 0.087 U	70 J		< 0.26 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	9.5	7500	430	0.029 J	23	1300	< 0.48 U	< 0.098 U	81 J		< 0.30 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	11	6700	720	< 0.026 U	28	1600	< 0.57 U	< 0.12 U	97 J		< 0.35 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	3.4	5700	290	< 0.023 U	11	380 J	< 0.55 U	< 0.11 U	< 65 U		0.51 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	12 T	4700 T	530	< 0.021 U	15 T	530	< 0.48 U	< 0.097 U	65 J		< 0.30 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	3.8	3400	190	< 0.021 U	10	410 J	< 0.48 U	< 0.098 U	64 J		0.63 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	8	6200	400	< 0.019 U	17	680	0.86 J	< 0.1 U	75 J		< 0.31 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	7.1	5400	390	< 0.034 U	17	630	0.79 J	< 0.034 U	74 J		< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	12	7400	590 B	< 0.020 U	27	990	< 0.51 U	< 0.12 U	100 J		< 0.31 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	5.4	5700	220 B	< 0.018 U	9.0	410 J	0.76 J	< 0.087 U	90 J		< 0.24 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	20	6500	470	< 0.026 U	38	2900	< 0.59 U	< 0.12 U	120 J		< 0.36 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	5.1	4800	250	< 0.023 U	8.3	410	0.35 J	< 0.069 U	76 J		< 0.21 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	5.3	3300	300	0.023 J	10	480 J	< 0.55 U	< 0.11 U	84 J		< 0.34 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	6.2	4800	470	< 0.018 U	12	430 J	< 0.50 U	< 0.10 U	82 J		0.55 J
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	11	5300	460	< 0.029 U	30	1400	< 0.66 U	< 0.13 U	110 J		< 0.41 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	10	7700	270	0.024 J	23	1200	< 0.39 U	< 0.079 U	83 J		0.95 J
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	11 T	6600 T	510	< 0.026 U	27 T	1600 T	< 0.60 UT	< 0.12 UT	100 JT		0.97 JT
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	25	1400	130	< 0.014 U	140	680	0.5 J	0.43 J	< 56 U		< 0.3 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	7	3200	220	< 0.034 U	12	390 J	< 0.034 U	< 0.034 U	54 J		< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	28.04-30.04 ft	1801508421	Not Excavated	5.2	9400	200 B	< 0.018 U	9.7	280 J	0.64 J	< 0.075 U	71 J		< 0.21 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	12	7500	370	0.040	28	1800	< 0.55 U	< 0.11 U	98 J		< 0.34 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217043	Not Excavated											
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	15	9900	410	< 0.026 U	35	2000	< 0.54 U	< 0.11 U	120 J		1.2 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	85	2100	140	< 0.019 U	380	550	0.79 J	1.3	< 58 U		< 0.31 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	6.8	5300	330	< 0.034 U	16	750	0.85	< 0.034 U	95 J		< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	14	8200 T	500 B	< 0.026 U	34	1300 T	< 0.46 U	< 0.10 U	120 J		< 0.29 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508423	Not Excavated											
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	12 T	8400 T	400	< 0.023 UT	29 T	1900 T	< 0.52 UT	< 0.11 UT	100 JT		1.1 JT
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-32-34-20210513	SSHS-B3891-SUB-32-34	5/13/2021	856.89	856.55	-0.34	-	32 - 34 ft	31.66-33.66 ft	1801217043	Not Excavated											
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	6.1	5300	330	< 0.02 U	16	660	0.98	< 0.077 U	85 J		< 0.23 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	9	7800	380	< 0.034 U	15	710	0.55 J	< 0.034 U	80 J		< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	7.9	5600	320	< 0.024 U	14	690	0.55 J	< 0.082 U	83 J		< 0.25 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	6.7	10000	340	< 0.034 U	12	740	1.4	< 0.034 U	110 J		< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	6.7	6100 J	270	< 0.021 U	13	680	1.3	< 0.11 U	78 J		< 0.33 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	7.5	7300	250	< 0.034 U	13	790	0.85 J	< 0.034 U	87 J		< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	10	4300	310	< 0.019 U	14	760	< 0.55 U	< 0.11 U	91 J		< 0.34 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	17	8600	630	0.025 J	40	2900	< 0.034 U	< 0.034 U	140 J		< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	8.9	7200	320	< 0.027 U	23	1400	< 0.52 U	< 0.11 U	91 J		< 0.32 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	6.9	4000	280	< 0.018 U	12	590	0.68 J	< 0.082 U	70 J		< 0.25 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	6.7	6800	580	< 0.024 U	24	1200	< 0.56 U	< 0.11 U	87 J		< 0.35 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	12	8400	360	< 0.016 U	26	2700	< 0.53 U	< 0.11 U	110 J		< 0.33 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	6.7	4600	360	< 0.013 U	17	1100	0.95	< 0.095 U	83 J		< 0.29 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	7.2	5100	280	< 0.021 U	14	860	< 0.58 U	< 0.12 U	81 J		< 0.36 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	6.8	5500	300	< 0.017 U	13	650	0.5 J	< 0.081 U	79 J		< 0.25 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	8	5200	280	< 0.021 U	14	780	< 0.61 U	< 0.12 U	< 71 U		< 0.38 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated	11	2700	480	< 0.022 U	22	980	0.76 J	0.12 BJ	< 160 U		< 0.44 U
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated											
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated											
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	11	1400	200	< 0.021 U	9.9	400 J	< 0.49 U	< 0.11 U	54 J		< 0.30 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	6.4	1800	270	< 0.017 U	11	380	0.42 J	< 0.061 U	87 J		< 0.17 U
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-836-834-20240812	SSHS-SPA4-B5506-ELEV-836-834	8/12/2024	852.03	852.03	0.00	-	16.03-18.03 ft	16.03-18.03 ft	1801782961	Not Excavated	7.9	2000	690	< 0.024 U	16	630	< 0.55 U	0.12 BJ	< 170 U		< 0.47 U
Rear Parking Lot	SPA4-B5507	SSHS-SPA4-B5507-ELEV-834-832-20240813	SSHS-SPA4-B5507-ELEV-834-832	8/13/2024	850.07	850.07	0.00	-	16.07-18.07 ft	16.07-18.07 ft	1801783741	Not Excavated	7.1	2000	350 T	< 0.019 U	11	700	0.75 J	< 0.095 U	< 170 U		< 0.47 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	7.6	4400	720	< 0.034 U	14	640	0.82 J	< 0.034 U	93 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	8.6	12000	370 J	< 0.034 U	11	530	0.71 J	< 0.034 U	92 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	12	3700	710	< 0.034 U	17	860	< 0.034 U	< 0.034 U	120 J		< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	6.1	11000	310	< 0.034 U	11	490 J	1	< 0.034 U	81 J		< 0.034 U

TABLE 6-4B
Deep Soil Results Remaining in Place - Metals

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Tin	Vanadium	Zinc
													mg/kg	mg/kg	mg/kg
Unrestricted															109
Restricted - Residential															10000
Protection of Groundwater															2480
Potential to exhibit the characteristic of toxicity															
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]			
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated		7.8	52
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated		5.5	37 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated		5.1	37 B
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated		14	52
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated		13	51
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated		17 T	57 T
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated		16	59
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated		5.7	29
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated		14	49
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated		17	65
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated		7.7	50
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated		9.8 T	49 T
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated		9.4	44
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated		11	51
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated		9.6	52
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated		15	59 B
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated		6.7	42 B
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated		25	75
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated		6.2	31
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated		7.6	42
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated		8.6	81
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated		17	65
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated		15	48
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated		18 T	58 T
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated		4.7	230
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated		7.7	42
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated		6.5	37 B
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated		18	56
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217043	Not Excavated			
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated		23	73
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated		11	370
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated		10	48
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated		19	70 BT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508423	Not Excavated			
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated		20 T	57 T
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-32-34-20210513	SSHS-B3891-SUB-32-34	5/13/2021	856.89	856.55	-0.34	-	32 - 34 ft	31.66-33.66 ft	1801217043	Not Excavated			
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated		9.7	51
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated		9.5	52
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated		9.7	47
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated		9.1	42
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated		9.2	46
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated		10	48
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated		12	49
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated		28	81
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated		16	55
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated		9.1	43
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated		16	73
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated		21	57
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated		11	43
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated		10	49
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated		11	45
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated		10	51
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-838-836-20240812	SSHS-SPA4-B5506-ELEV-838-836	8/12/2024	852.03	852.03	0.00	-	14.03-16.03 ft	14.03-16.03 ft	1801782961	Not Excavated		14	79
Rear Parking Lot	SPA6-B65A	SSHS-SPA6-B65A-ELEV-836-834-20241207	SSHS-SPA6-B65A-ELEV-836-834	12/7/2024	850.12	850.12	0.00	-	14.12-16.12 ft	14.12-16.12 ft	1801838842	Not Excavated			
Rear Parking Lot	SPA6-B537A	SSHS-SPA6-B537A-ELEV-836-834-20241207	SSHS-SPA6-B537A-ELEV-836-834	12/7/2024	850.26	850.26	0.00	-	14.26-16.26 ft	14.26-16.26 ft	1801838841	Not Excavated			
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated		7.1	51
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated		8.5	42
Rear Parking Lot	SPA4-B5506	SSHS-SPA4-B5506-ELEV-836-834-20240812	SSHS-SPA4-B5506-ELEV-836-834	8/12/2024	852.03	852.03	0.00	-	16.03-18.03 ft	16.03-18.03 ft	1801782961	Not Excavated		10	74
Rear Parking Lot	SPA4-B5507	SSHS-SPA4-B5507-ELEV-834-832-20240813	SSHS-SPA4-B5507-ELEV-834-832	8/13/2024	850.07	850.07	0.00	-	16.07-18.07 ft	16.07-18.07 ft	1801783741	Not Excavated		11	43
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated		9.5	75
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated		8.2	42 J
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated		12	61
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated		7.3	61

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 R	< 0.014 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated			0.714	0.041 J	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 R	0.13
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			ND	< 0.41 U	< 0.41 U		< 0.41 U				< 0.41 U
Football Field	SSHS-B3559	013021 10:00 DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated	< 39 U	< U									
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated			0.248	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated			0.036	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated			9.8	< 0.11 U	< 0.082 U	< 0.1 U	< 0.097 U	< 0.82 U	< 0.078 U	< 0.23 U	0.51
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated			0.387	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.052 J
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated			3.241	0.032 J	0.041 J	< 0.02 U	0.081 J	< 0.16 U	< 0.015 U	< 0.046 U	0.29
Football Field	SSHS-B3855	041321 09:30 DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated			0.21	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 UJ
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated			0.267	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.049 J
Football Field	SSHS-B3877	041321 09:30 DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated			2.779	< 0.021 UJ	0.032 J	< 0.02 U	0.063 J	< 0.16 U	< 0.015 U	< 0.045 U	0.23
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated			0.15	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.054 J
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated			0.79	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.2
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated			0.48	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	0.13
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated			0.437	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.097 J
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 UJ
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated			0.4	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.06 J
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated			0.583	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	0.083
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated			0.615	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	0.085
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			0.745	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.18 J
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			0.328	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.072 J
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated			0.73	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.051 U	0.18
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	2700	0.333	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	0.076 J
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	880	0.14	< 0.026 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.057 U	< 0.042 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	1800	0.327	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.047 J
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	9300	0.41	< 0.023 U	< 0.017 U	< 0.022 U	0.13	< 0.17 U	< 0.017 U	< 0.049 UT	< 0.036 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	3000	0.049	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	3800	0.981	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	0.074 J
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	5800	0.68	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	0.15
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	8000	0.078	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	7700	0.067	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	3000	ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.05 U	< 0.036 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	2900	ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	3100	0.339	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.064 J
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	3000	0.07	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	8200	0.532	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	0.076
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	4100	0.177	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated			0.758	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.15
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated			0.5	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.11
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated			35	0.98	0.059 J	< 0.034 U	1.9	< 0.26 U	< 0.034 U	< 0.074 U	2.7
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated			0.31	< 0.37 U	< 0.37 U		< 0.37 U				0.1 J
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated			2.28	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.42
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated			0.52	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.17
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated			3.79	< 0.1 U	< 0.078 U	< 0.096 U	< 0.092 U	< 0.78 U	< 0.074 U	< 0.22 U	0.24 J
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated			0.78	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.15
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated			0.428	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	0.066 J
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated			0.323	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.053 J
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated			0.042	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated			0.4	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	0.08
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated			0.89	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	0.19
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated			0.452	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.092
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated			0.34	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.044 U	0.07 J
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated			0.6	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	0.15
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated			0.208	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.055 J
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated			0.37	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.11
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated			0.73	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	0.17
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated			0.413	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.093
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated			0.41	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	0.11
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated			0.74	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.14
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated			0.372	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	0.082 J
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated			0.762	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.17
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated			0.387	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.074 J
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated			42.11	0.76	0.32	< 0.034 U	1.8	< 0.16 U	< 0.034 U	< 0.045 U	3.3
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.044 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated			1.36	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	0.23
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated			0.4	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	0.12

DRAFT

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100					
Restricted - Residential													1	1	3.9	100					
Protection of Groundwater													22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.016 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	0.017 J	0.02 J	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.41 U	< 0.41 U	< 0.41 U	< 0.41 U					
Football Field	SSHS-B3559	013021 10:00 DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated									
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	180119601	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	0.068 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.16 U	< 0.092 U	< 0.11 U	< 0.081 U	< 0.089 U	< 0.068 U	< 0.14 U	< 2 U	< 0.13 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	0.034 J	0.046 J	< 0.021 U	0.037 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.26	0.35	0.12	0.18	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3855	041321 09:30 DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3877	041321 09:30 DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.21	0.3	0.079	0.18	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 0.04 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	0.084	0.089	0.029 J	0.11	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	0.058 J	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	1.7	2	0.74	1.2	< 0.22 U	< 0.022 U	< 0.044 U	< 0.63 U	< 0.25 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.15 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	< 0.37 U	< 0.37 U	< 0.37 U	< 0.37 U					
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.15 U	< 0.087 U	< 0.11 U	< 0.077 U	< 0.085 U	< 0.064 U	< 0.13 U	< 1.9 U	< 0.12 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	0.033 J	0.033 J	< 0.021 U	0.026 J	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	0.052 J	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	2	2.4	0.98	1.4	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33
Restricted - Residential																				3.9	0.33
Protection of Groundwater																				1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.014 U	< 0.016 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.012 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.21	< 0.016 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated									< 0.41 U	< 0.41 U
Football Field	SSHS-B3559	013021 10:00 DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 1.3 U	< 1.2 U	< 0.087 U	< 0.13 U	< 0.088 U	< 0.086 U	< 0.087 U	< 0.11 U	2.8	< 0.24 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.085	< 0.045 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	0.047 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.33	< 0.047 UJ
Football Field	SSHS-B3855	041321 09:30 DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 UJ	< 0.05 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.078 J	< 0.048 U
Football Field	SSHS-B3877	041321 09:30 DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	0.037 J	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.29	0.049 J
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.096	< 0.047 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.24	< 0.048 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.2	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.2 J	< 0.047 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 UJ	< 0.047 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18 J	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 UJ	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.19	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.29 J	< 0.048 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.17 J	< 0.047 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.24	< 0.034 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	0.24	< 0.055 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.031 U	< 0.022 U	< 0.021 U	< 0.021 U	< 0.028 U	0.14	< 0.059 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.28	< 0.049 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	0.14	< 0.05 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	0.3	< 0.051 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.13	< 0.049 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.22	< 0.045 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.27	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.39 U	0.51	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	2.3	0.33
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.09 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated									0.21 J	< 0.37 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	1.1	< 0.046 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.35	< 0.047 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 1.2 U	< 1.2 U	< 0.083 U	< 0.12 U	< 0.084 U	< 0.081 U	< 0.082 U	< 0.11 U	1.3	< 0.23 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.31	< 0.048 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	0.097	< 0.045 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.1	< 0.046 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.13	< 0.048 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.38	< 0.046 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.16	< 0.046 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.22	< 0.047 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.085	< 0.046 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.26	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.3	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.16	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.32	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.25	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.14	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.24 U	0.48	< 0.096 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	2.9	0.39
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.094 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	0.6	< 0.046 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.28	< 0.048 U

DRAFT

												Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												7									
Restricted - Residential												59									
Protection of Groundwater												210									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.013 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.41 U									
Football Field	SSHS-B3559	013021 10:00 DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	180119460l	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	0.13 J	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.016 U	< 0.34 UJ	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.082 U	< 1.7 U	< 0.14 U	< 0.65 U	< 0.12 U	< 0.14 U	< 0.82 U	< 1.1 U	< 3.2 U	< 0.12 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.026 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3855	041321 09:30 DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3877	041321 09:30 DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.023 J	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.021 U	< 0.026 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.021 U	< 0.025 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 0.02 U	< 0.43 U	< 0.035 U	< 0.16 U	< 0.029 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.79 U	< 0.028 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 UT	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 UT	< 0.025 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 UT	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.7 U	< 0.025 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 UT	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.67 U	< 0.024 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 UT	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.025 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 UT	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 UT	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 UT	< 0.025 U	< 0.03 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.025 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 UT	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.025 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 UT	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 UT	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 UT	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 UT	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	0.18 J	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.3 J	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	0.56 J	< 0.034 U	< 0.046 U	< 0.034 U	< 0.2 U	< 0.24 U	< 0.034 U	< 0.35 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	< 0.37 U									
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.078 U	< 1.7 U	< 0.14 U	< 0.62 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U	< 0.11 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.027 U	0.23 J	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.23 J	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	0.48	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U

DRAFT

													2,4-Dinitrophenol	**2,4-Dinitrotoluene**	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															0.1	0.1	0.1	100	30	0.33		
Restricted - Residential															13	13	13	100	100	1.2		
Protection of Groundwater															0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.96 U	< 0.018 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.97 U	< 0.018 U			< 0.11 U	0.066 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated						< 0.41 U	< 0.41 U	< 0.41 U		
Football Field	SSHS-B3559	013021 10:00_DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	0.036 J	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 10 U	< 0.28 U			< 0.58 U	0.85	0.44	< 0.13 U	< 0.11 U	< 0.19 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.053 U			< 0.11 U	0.056 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3864	041021 10:00_DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 2 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 2 U	< 0.056 U			< 0.11 U	0.5	0.024 J	< 0.026 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3855	041321 09:30_DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	0.43	< 0.014 UJ	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 2.1 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Football Field	SSHS-B645A	042021 09:30_DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	0.16 J	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.052 U			< 0.034 U	< 0.018 U	0.1	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.052 U			< 0.034 U	< 0.018 U	0.12	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	0.065 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	< 0.019 UJ	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 2.4 U	< 0.065 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 2.6 U	< 0.069 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 2.2 UT	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			0.1	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 2.2 U	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.022 U	< 0.039 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 2.2 U	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 2.2 U	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 2.2 U	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	0.046 J	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.36 U			< 0.19 U	5.9	0.97	< 0.043 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.21 U			< 0.11 U	< 0.018 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated						< 0.37 U	< 0.37 U	< 0.37 U		
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	0.14	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 9.8 U	< 0.27 U			< 0.55 U	0.53	0.22 J	< 0.13 U	< 0.1 U	< 0.18 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.053 U			< 0.11 U	0.063 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 2 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	0.043 J	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.22 U			< 0.11 U	7.9	0.87	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	0.17	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U

DRAFT

												Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12		
Restricted - Residential													0.5	100				100	100		
Protection of Groundwater													8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B2720	051819 10:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.018 U	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.019 U	< 0.015 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated		< 0.41 U	< 0.41 U				< 0.41 U	< 0.41 U		
Football Field	SSHS-B3559	013021 10:00_DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.096 U	< 0.19 U	< 0.53 U	< 0.55 U	< 0.095 U	0.19 J		< 0.073 U	< 0.85 U	< 0.47 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U
Football Field	SSHS-B3864	041021 10:00_DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.019 U	0.14	< 0.11 U	< 0.11 U	< 0.019 U	0.031 J		0.034 J	< 0.17 U	< 0.094 U
Football Field	SSHS-B3855	041321 09:30_DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.099 U
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U
Football Field	SSHS-B3877	041321 09:30_DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.019 U	0.13	< 0.1 U	< 0.11 U	< 0.019 U	0.036 J		0.048 J	< 0.17 U	< 0.093 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.019 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.41	0.12	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U
Football Field	SSHS-B645A	042021 09:30_DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.093 U
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	0.017 J	< 0.2 U	< 0.11 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 0.024 U	< 0.046 U	< 0.13 U		< 0.023 U	< 0.022 U	< 0.14 U	< 0.018 U	< 0.21 U	< 0.12 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	< 0.02 U	0.078	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	0.027 J	< 0.18 U	< 0.098 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.02 U	< 0.04 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 0.021 U	< 0.04 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 0.02 U	< 0.04 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	1	< 0.034 U	< 0.034 U	< 0.034 U	0.27		0.38	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated		< 0.37 U	< 0.37 U				< 0.37 U	< 0.37 U		
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.091 U	< 0.18 U	< 0.51 U	< 0.52 U	< 0.09 U	< 0.085 U		< 0.069 U	< 0.81 U	< 0.45 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.099 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.018 U	< 0.036 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30_SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	1.3	< 0.034 U	< 0.034 U	< 0.034 U	0.19		0.21	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U

DRAFT

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated								< 0.41 U	< 0.41 U	< 0.41 U
Football Field	SSHS-B3559	013021 10:00 DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	180119460l	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.091 U	< 0.68 U	< 0.3 U	< 1.3 U		< 0.13 U	< 0.62 U	< 3 U	3.5	< 0.57 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	0.39	< 0.11 U
Football Field	SSHS-B3855	041321 09:30 DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3877	041321 09:30 DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	0.33	< 0.11 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.74 U	< 0.025 U	< 0.14 U
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	0.28	< 0.12 U
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	0.049 J	< 0.12 U
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.11	< 0.12 U
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.045 J	< 0.11 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.057 J	< 0.11 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.22 U	< 0.034 U	< 0.034 U	< 0.42 U		< 0.034 U	< 0.034 U	< 0.034 U	7.6	< 0.18 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated								< 1.9 U	< 0.37 U	< 0.37 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.086 U	< 0.65 U	< 0.28 U	< 1.2 U		< 0.12 U	< 0.59 U	< 2.9 U	1.5	< 0.54 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	8.9	< 0.11 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B2720	051819 10:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	0.23		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.41 U					
Football Field	SSHS-B3559	013021 10:00 DUP-25	DUP-25	1/29/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116665-1	Not Excavated						
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	180119601	Not Excavated	0.18		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	1.7		< 0.081 U	< 0.78 U	< 0.13 U	< 0.1 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	0.077		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-16-18	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.51		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3855	041321 09:30 DUP-03	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	0.21		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	0.14		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30 DUP-28	DUP-28	4/12/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	0.44		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	0.35		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	0.15		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	0.14 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.017 UJ		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	0.21		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	0.2		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	0.21 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	0.086 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	0.31		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	lSMP-B527-BOT1	SSHS-ISMP-B527 BOT 1-20210603	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	lSMP-B527-BOT2	SSHS-ISMP-B527 BOT 2-20210603	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 0.022 U		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Football Field	lSMP-B527-BOT3	SSHS-ISMP-B527 BOT 3-20210603	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	lSMP-B527-BOT4	SSHS-ISMP-B527 BOT 4-20210603	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	lSMP-B527-BOT5	SSHS-ISMP-B527 BOT 5-20210603	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	lSMP-B527-BOT6	SSHS-ISMP-B527 BOT 6-20210603	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	0.14		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	lSMP-B527-BOT7	SSHS-ISMP-B527 BOT 7-20210603	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	0.23		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	lSMP-B527-BOT8	SSHS-ISMP-B527 BOT 8-20210603	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	0.078		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	lSMP-B527-BOT9	SSHS-ISMP-B527 BOT 9-20210603	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	0.067 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	lSMP-B527-BOT10	SSHS-ISMP-B527 BOT 10-20210603	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	lSMP-B527-BOT11	SSHS-ISMP-B527 BOT 11-20210603	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	lSMP-B527-BOT12	SSHS-ISMP-B527 BOT 12-20210603	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	0.1		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	lSMP-B527-BOT13	SSHS-ISMP-B527 BOT 13-20210603	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	0.07 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	lSMP-B527-BOT14	SSHS-ISMP-B527 BOT 14-20210603	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	0.19		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	lSMP-B527-BOT15	SSHS-ISMP-B527 BOT 15-20210603	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	0.12		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	0.28		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	0.21		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	5.3		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.016 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	< 0.37 U					
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	180119601	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	0.62		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.084 U		< 0.077 U	< 0.74 U	< 0.13 U	< 0.097 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	0.32		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	0.11		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	0.042 J		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	0.19		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	0.32		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	0.2		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	0.15		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	0.23		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	0.068 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	0.26		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	0.16		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	0.14		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	0.28		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	0.15		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	0.29		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	0.13		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	6.9		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	180119601	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	0.36		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated			3.129	< 0.1 U	< 0.078 U	< 0.097 U	< 0.092 U	< 0.78 U	< 0.075 U	< 0.22 U	0.28 J
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated			0.73	< 0.019 U	< 0.015 U	< 0.018 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.042 U	0.14
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated			0.438	< 0.02 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	0.098
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated			0.344	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.074 J
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated			0.443	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.073
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.049 U	< 0.035 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated			0.024	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated			0.415	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	0.095
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated			0.74	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	0.11
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated			0.86	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	0.21
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated			0.101	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated			0.52	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	0.14
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated			0.742	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	0.13
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated			0.523	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	0.047 J
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated			0.039	< 0.019 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated			0.244	< 0.023 U	< 0.018 U	< 0.023 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	0.045 J
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated			1.131	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.05 U	0.11
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated			0.244	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	0.074 J
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.025 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	< 0.041 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated			0.082	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.018 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.042 U	< 0.031 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated			0.697	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	0.097
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated			0.098	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	0.041 J
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	< 0.04 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated			0.058	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated			0.028	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated			1.399	< 0.034 U	0.034 J	< 0.034 U	0.037 J	< 0.17 U	< 0.034 U	< 0.049 U	0.13
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.038 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.051 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.037 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100					
Restricted - Residential													1	1	3.9	100					
Protection of Groundwater													22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.15 U	< 0.088 U	< 0.11 U	< 0.077 U	< 0.085 U	< 0.065 U	< 0.13 U	< 1.9 U	< 0.12 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.029 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3870	042021 09:30 DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.02 U	< 0.015 U	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	0.11	0.12	0.054 J	0.1	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Butylbenzyl phthalate	**Caprolactam**	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					1	0.33
Restricted - Residential																					3.9	0.33
Protection of Groundwater																					1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 1.2 U	< 1.2 U	< 0.083 U	< 0.12 U	< 0.084 U	< 0.082 U	< 0.083 U	< 0.11 U	1.2	< 0.23 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	0.29	< 0.043 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.16	< 0.044 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	0.14	< 0.048 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.2	< 0.046 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.18	< 0.047 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.046 J	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.21	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	0.21	< 0.044 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.02 U	< 0.037 U	< 0.043 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	0.079 J	< 0.052 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.32	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.094	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.05 U	< 0.058 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	< 0.047 U	< 0.054 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.046 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.043 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.23	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.057 J	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.03 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.05 U	< 0.057 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.22 U	< 0.034 U	< 0.023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.038 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.15	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.051 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													7									
Restricted - Residential													59									
Protection of Groundwater													210									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.078 U	< 1.7 U	< 0.14 U	< 0.62 U	< 0.11 U	< 0.13 U	< 0.78 U	< 1 U	< 3.1 U	< 0.11 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.027 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	0.24 J	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.034 U	< 0.2 U	< 0.26 U	< 0.78 U	< 0.028 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.02 U	< 0.42 U	< 0.034 U	< 0.16 U	< 0.028 U	< 0.033 U	< 0.2 U	< 0.26 U	< 0.77 U	< 0.028 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.025 U
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.015 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.021 U	< 0.025 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.025 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.017 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.024 U	< 0.028 U	0.17 J	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.026 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													2,4-Dinitrophenol	**2,4-Dinitrotoluene**	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															0.1	0.1	0.1	100	30	0.33		
Restricted - Residential															13	13	13	100	100	1.2		
Protection of Groundwater															0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 9.9 U	< 0.27 U			< 0.56 U	0.47	0.22 J	< 0.13 U	< 0.1 U	< 0.18 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.051 U			< 0.1 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.051 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 2 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 2 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.057 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	0.082	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 1.9 U	< 0.053 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 1.9 U	< 0.052 U			< 0.11 U	0.084	0.042 J	< 0.025 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.051 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 2.2 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 2 U	< 0.056 U			< 0.12 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.061 U			< 0.13 U	0.091	0.36	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 2.4 U	< 0.065 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 2.5 U	< 0.068 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 2 U	< 0.054 U			< 0.11 U	0.02 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 1.9 U	< 0.051 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	0.21	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.053 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 2.5 U	< 0.067 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	0.02 J	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U
Football Field	SSHS-B3870	042021 09:30 DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.051 U			< 0.034 U	< 0.018 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.06 U			< 0.12 U	0.21	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 2.2 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 2.4 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 2.3 UJ	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 2.1 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.059 U			< 0.034 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 2.3 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 2.3 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 2.3 UJ	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U

DRAFT

												Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12		
Restricted - Residential													0.5	100				100	100		
Protection of Groundwater													8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.092 U	< 0.18 U	< 0.51 U	< 0.52 U	< 0.091 U	< 0.085 U		0.079 J	< 0.81 U	< 0.45 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.033 U	< 0.096 U	< 0.098 U	< 0.017 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.085 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.097 U	< 0.1 U	< 0.017 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.086 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.018 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.087 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.097 U	< 0.099 U	< 0.017 U	< 0.016 U		< 0.013 U	< 0.15 U	< 0.086 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-22-24	SSHS-B3873-SUB-22-24	4/19/2021	854.94	855.38	0.44	-	22 - 24 ft	22.44-24.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.023 U	< 0.045 U	< 0.13 U		< 0.023 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.019 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.093 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.021 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.02 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3870	042021 09:30_DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	0.084	< 0.034 U	< 0.034 U	< 0.034 U	0.019 J		0.044 J	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.099 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.017 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.018 U		< 0.015 U	< 0.18 U	< 0.098 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.086 U	< 0.65 U	< 0.28 U	< 1.2 U		< 0.12 U	< 0.59 U	< 2.9 U	0.88	< 0.54 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.016 U	< 0.12 U	< 0.053 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.022 U	< 0.17 U	< 0.072 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	< 0.024 U	< 0.14 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.031 J	< 0.11 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.022 U	< 0.16 U	< 0.071 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.14 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3870	042021 09:30 DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.1 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	0.12	< 0.12 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U

DRAFT

													Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.084 U		< 0.077 U	< 0.74 U	< 0.13 U	< 0.098 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	0.3		< 0.014 U	< 0.14 U	< 0.024 U	< 0.018 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	0.18		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	0.13		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	0.17		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-20-22	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	0.024 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	0.14		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	0.28		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	0.3		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	0.055 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	0.2		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	0.32		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	0.14		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	0.039 J		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-22-24	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	0.12		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-22-24	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	0.25		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	0.076 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.021 U		< 0.02 U	< 0.19 U	< 0.032 U	< 0.025 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	0.031 J		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.016 U		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-24-26	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-24-26	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	0.16		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.021 U		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	0.038 J		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-26-28	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	0.028 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3870	042021 09:30 DUP-09	DUP-09	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-26-28	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.016 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	0.24		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-28-30	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-28-30	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.024 U	< 0.023 U	< 0.19 U	< 0.018 U	< 0.055 U	< 0.04 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.022 U	< 0.021 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated			0.293	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	0.06 J
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.014 U	< 0.043 U	< 0.031 U
Football Field	SSHS-B3877	041321 09:30 DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated			0.513	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	0.097
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.049 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.031 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.038 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.053 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.021 U	< 0.17 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.051 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.021 U	< 0.18 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.023 U	< 0.19 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.019 U	< 0.057 U	< 0.041 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated			ND	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.023 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.039 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.024 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.022 U	< 0.19 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated			ND	< 0.034 U	< 0.019 U	< 0.034 U	< 0.023 U	< 0.19 U	< 0.034 U	< 0.055 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated			ND	< 0.034 U	< 0.021 U	< 0.034 U	< 0.025 U	< 0.21 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated			ND	< 0.034 U	< 0.02 U	< 0.034 U	< 0.024 U	< 0.2 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated			ND	< U	< U	< U	< U	< U	< U		< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated			ND	< 0.0068	< 0.0082	< 0.029	< 0.007	< 0.035	< 0.032	< 0.053	< 0.0089
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated			ND	< 0.0067	< 0.008	< 0.029	< 0.0068	< 0.034	< 0.031	< 0.052	< 0.0088
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated			1.583	< 0.007	< 0.0083	< 0.03	< 0.0071	< 0.035	< 0.032	< 0.054	0.18
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	120										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.043 U	< 0.032 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	41 J										
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 39 U										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 39 U										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated			0.083	< 0.019 U	< 0.015 U	< 0.018 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.041 U	< 0.03 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated			0.932	< 0.0068	0.039	< 0.029	< 0.0069	< 0.034	< 0.031	< 0.053	0.088
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	50 J										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	52 J										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 39 U										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 37 U										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 35 U										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 36 U										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 36 U										

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100					
Restricted - Residential													1	1	3.9	100					
Protection of Groundwater													22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3870	041321 09:30 SSHS-B3870-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.038 U	< 0.022 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.026 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3877	041321 09:30 DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.016 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.028 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.029 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.038 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.022 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.04 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.49 U	< 0.032 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.02 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.02 U	< 0.022 U	< 0.016 U	< 0.034 U	< 0.48 U	< 0.032 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.47 U	< 0.031 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.041 U	< 0.023 U	< 0.029 U	< 0.021 U	< 0.023 U	< 0.017 U	< 0.035 U	< 0.51 U	< 0.033 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.04 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.5 U	< 0.033 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.0071	< 0.011	< 0.014	< 0.0071	< 0.023	< 0.0096	< 0.0077	< 0.058	< 0.031
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.007	< 0.011	< 0.014	< 0.007	< 0.023	< 0.0094	< 0.0075	< 0.056	< 0.03
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	0.059	0.11	0.037	0.047	< 0.024	< 0.0097	< 0.0078	< 0.058	< 0.031
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated									
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.024 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated									
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated									
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated									
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated									
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated									
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated									
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated									
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated									
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.029 U	0.023 J	< 0.02 U	0.019 J	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.023 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	0.065	0.088	0.037	0.071	< 0.023	< 0.0095	< 0.0076	< 0.057	< 0.031
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated									
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated									
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated									
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated									
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated									
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated									
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated									
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated									
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated									
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated									
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated									
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated									
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated									

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33
Restricted - Residential																				3.9	0.33
Protection of Groundwater																				1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.49	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.3 U	< 0.29 U	< 0.021 U	< 0.03 U	< 0.021 U	< 0.02 U	< 0.02 U	< 0.027 U	< 0.049 U	< 0.056 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.11	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.055 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.027 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.18	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.025 U	< 0.047 U	< 0.054 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.038 U	< 0.044 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.26 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.044 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.055 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.046 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.045 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.049 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.31 U	< 0.3 U	< 0.021 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.028 U	< 0.051 U	< 0.058 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.05 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.05 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.28 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.29 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.049 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.31 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.053 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.3 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.052 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.049	< 0.27	< 0.0066	< 0.028	< 0.033	< 0.0074	< 0.029	< 0.04	< 0.0085	< 0.0079
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.048	< 0.26	< 0.0064	< 0.028	< 0.032	< 0.0073	< 0.029	< 0.039	< 0.0083	< 0.0078
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.049	< 0.27	< 0.0067	< 0.029	< 0.033	< 0.0076	< 0.03	< 0.04	0.46	< 0.0081
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.024 U	< 0.016 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.023 U	< 0.016 U	< 0.015 U	< 0.016 U	< 0.02 U	< 0.037 U	< 0.043 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.048	< 0.27	< 0.0065	< 0.028	< 0.032	< 0.0074	< 0.029	< 0.039	0.16	< 0.0078
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										

DRAFT

												Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												7									
Restricted - Residential												59									
Protection of Groundwater												210									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.033 U	< 0.19 U	< 0.26 U	< 0.76 U	< 0.027 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.017 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.025 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.016 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.023 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.015 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.022 U	< 0.026 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	0.16 J	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.25 U	< 0.73 U	< 0.026 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30 DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.027 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.028 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.024 U	< 0.029 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.029 U	0.27 J	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.026 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.73 U	< 0.026 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.015 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.021 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.021 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.022 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.027 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.026 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.026 U	< 0.031 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.025 U	< 0.03 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.016 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.023 U	< 0.027 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.027 U	< 0.033 U	< 0.034 U	< 0.26 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.02 U	< 0.43 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.79 U	< 0.028 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.028 U	< 0.033 U	< 0.034 U	< 0.26 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.035 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U	< 0.26 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.026 U	< 0.032 U	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.028 U	< 0.033 U	< 0.034 U	< 0.26 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.037 U	< 0.034 U	< 0.03 U	< 0.035 U	< 0.034 U	< 0.28 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.036 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U	< 0.27 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.035	< 0.038	< 0.0071	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.034	< 0.037	< 0.007	< 0.038	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.036	< 0.038	< 0.0073	< 0.04	< 0.057	< 0.039	< 0.045	< 0.038	< 0.15	< 0.037
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.022 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.015 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.021 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.035	< 0.037	< 0.0071	< 0.039	< 0.055	< 0.038	< 0.044	< 0.037	< 0.14	< 0.036
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															0.1	0.1	0.1	100	30	0.33		
Restricted - Residential															13	13	13	100	100	1.2		
Protection of Groundwater															0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3877	041321 09:30 SSHS-B3871-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 2.4 U	< 0.066 U			< 0.14 U	< 0.023 U	< 0.017 U	< 0.032 U	< 0.026 U	< 0.045 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 2.2 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.041 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.06 U			< 0.12 U	0.03 J	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.056 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 2.3 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3877	041321 09:30 DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.064 U			< 0.13 U	0.066 J	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.059 U			< 0.034 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.058 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.06 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.064 U			< 0.13 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 2.3 U	< 0.063 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 1.9 U	< 0.052 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 2.3 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.064 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.061 U			< 0.034 U	< 0.021 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.062 U			< 0.034 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 2.3 U	< 0.061 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.06 U			< 0.034 U	< 0.021 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 2.4 U	< 0.065 U			< 0.14 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.062 U			< 0.034 U	< 0.022 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.056 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.066 U			< 0.034 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 2.5 U	< 0.069 U			< 0.14 U	< 0.024 U	< 0.018 U	< 0.033 U	< 0.027 U	< 0.047 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U	< U			< U	< U	< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.068 U			< 0.034 U	< 0.024 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.068 U			< 0.034 U	< 0.024 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 2.4 U	< 0.065 U			< 0.13 U	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.064 U			< 0.034 U	< 0.023 U	< 0.034 U	< 0.031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.067 U			< 0.14 U	< 0.023 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.072 U			< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.07 U			< 0.034 U	< 0.025 U	< 0.034 U	< 0.033 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U			< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.42	< 0.029			< 0.041	< 0.0076	< 0.0094	< 0.0076	< 0.008	< 0.038
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.42	< 0.028			< 0.04	< 0.0075	< 0.0092	< 0.0074	< 0.0078	< 0.038
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.43	< 0.029			< 0.042	< 0.0077	0.16	< 0.0077	< 0.0081	< 0.039
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 1.9 U	< 0.053 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 1.9 U	< 0.05 U	< 0.1 U			0.019 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.42	< 0.028			< 0.04	0.17	< 0.0093	< 0.0075	< 0.0079	< 0.038
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										

DRAFT

												Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12		
Restricted - Residential													0.5	100				100	100		
Protection of Groundwater													8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.023 U	< 0.044 U	< 0.13 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.099 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.043 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U	< 0.12 U	< 0.022 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.04 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.041 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.024 U	< 0.045 U	< 0.13 U	< 0.13 U	< 0.023 U	< 0.022 U		< 0.018 U	< 0.21 U	< 0.12 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U		< U	< U	< U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.045 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.022 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.044 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.047 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U		< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.026	< 0.0073	< 0.025		< 0.027	< 0.0064	< 0.035	< 0.0061	< 0.16	< 0.15
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.025	< 0.0072	< 0.024		< 0.026	< 0.0063	< 0.034	< 0.006	< 0.16	< 0.14
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.026	0.05	< 0.025		< 0.027	< 0.0065	< 0.035	< 0.0062	< 0.16	< 0.15
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.017 U	< 0.033 U	< 0.096 U		< 0.017 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.025	0.045	< 0.025		< 0.027	0.0078	< 0.035	0.018	< 0.16	< 0.15
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.021 U	< 0.16 U	< 0.07 U	< 0.31 U		< 0.03 U	< 0.15 U	< 0.71 U	< 0.024 U	< 0.13 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.15 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.017 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.019 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.017 U	< 0.13 U	< 0.055 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.1 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.28 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.02 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.018 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.034 U	< 0.31 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.022 U	< 0.17 U	< 0.073 U	< 0.32 U		< 0.031 U	< 0.15 U	< 0.73 U	< 0.024 U	< 0.14 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U	< U	< U	< U		< U	< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.022 U	< 0.034 U	< 0.034 U	< 0.32 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.022 U	< 0.034 U	< 0.034 U	< 0.32 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.021 U	< 0.034 U	< 0.034 U	< 0.3 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.022 U	< 0.034 U	< 0.034 U	< 0.31 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.023 U	< 0.034 U	< 0.034 U	< 0.33 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.023 U	< 0.034 U	< 0.034 U	< 0.33 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U		< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.14	< 0.03	< 0.039	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0084
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0082	< 0.032	< 0.031	< 0.011	< 0.0083
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0085	< 0.034	< 0.032	0.48	< 0.0086
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated										
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated										
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated										
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated										
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated										
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.016 U	< 0.12 U	< 0.053 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.14	< 0.029	< 0.039	< 0.13		< 0.0083	< 0.033	< 0.032	< 0.011	< 0.0083
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated										
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated										
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated										
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated										
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated										
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated										
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated										
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated										
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated										
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated										
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated										
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated										

DRAFT

													Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-30-32	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.021 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.028 U	< 0.022 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-30-32	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	0.093		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-32-34	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3877	041321 09:30_DUP-29	DUP-29	4/12/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.031 U	< 0.023 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-32-34	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	0.17		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.016 U		< 0.015 U	< 0.14 U	< 0.025 U	< 0.019 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-34-36	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-34-36	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-36-38	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.021 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.031 U	< 0.023 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-36-38	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.019 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-38-40	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.022 U		< 0.02 U	< 0.19 U	< 0.033 U	< 0.025 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-38-40	SSHS-B3870-SUB-38-40	4/19/2021	855.26	855.36	0.10	-	38 - 40 ft	38.1-40.1 ft	180-120245-2	Not Excavated	< U		< U	< U	< U	< U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.021 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.023 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.022 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U		< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.0072		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0071		< 0.026	< 0.022	< 0.037	< 0.052
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0073		< 0.027	< 0.023	< 0.039	< 0.054
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated						
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated						
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated						
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated						
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated						
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated						
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	0.022 J		< 0.014 U	< 0.14 U	< 0.024 U	< 0.018 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	0.19		< 0.027	< 0.023	< 0.038	< 0.053
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated						
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated						
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated						
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated						
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated						
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated						
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated						
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated						
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated						
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated						
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated						
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated						

DRAFT

														Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 41 U											
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	19.72-21.72 ft	1801162471	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated			0.523	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	0.044 J
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated			0.019	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated			3.521	0.073	0.026 J	< 0.12 U	0.17	< 0.15 U	< 0.13 U	< 0.043 U	0.31
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated			0.043	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated			ND	< 0.042 U	< 0.032 U	< 0.26 U	< 0.038 U	< 0.32 U	< 0.27 U	< 0.091 U	< 0.066 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated			3.167	< 0.023 U	0.071 J	< 0.14 U	0.076 J	< 0.17 U	< 0.14 U	< 0.049 U	0.28
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 UT	< 0.034 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated			2.04	< 0.022 U	0.097	< 0.14 U	0.048 J	< 0.17 U	< 0.14 U	< 0.048 U	0.22
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.13 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.032 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.053 U	< 0.039 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100					
Restricted - Residential													1	1	3.9	100					
Protection of Groundwater													22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	0.051 J	0.067 J	< 0.02 U	0.096	< 0.016 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.024 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	0.1	0.14	0.047 J	0.093	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.038 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	0.4	0.79	0.36	0.34	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.03 U	0.025 J	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	0.38 J	< 0.15 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.031 U	0.029 J	< 0.021 U	0.019 J	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated									
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	0.082	0.12	0.042	0.058	< 0.024	< 0.0096	< 0.0078	< 0.058	< 0.031
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated									
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated									
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	0.042 J	0.06 J	< 0.022 U	0.04 J	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.034 U	< 0.034 U	< 0.39 U	< 0.15 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	0.24	0.26	0.12	0.15	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.064 U	< 0.036 U	< 0.044 U	< 0.032 U	< 0.27 U	< 0.027 U	< 0.055 U	< 0.78 U	< 0.31 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	0.25	0.42	0.13	0.22	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	0.19	0.27	0.091	0.16	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.18 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U

DRAFT

												Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33
Restricted - Residential																				3.9	0.33
Protection of Groundwater																				1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	0.041 J	< 0.046 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.05 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.044 U	< 0.051 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.093 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	< 0.24 U	< 0.23 U	0.046 J	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.28	0.045 J
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.51 U	< 0.48 U	< 0.034 U	< 0.19 U	< 0.26 U	< 0.034 U	< 0.27 U	< 0.24 U	< 0.082 U	< 0.094 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.27 U	< 0.26 U	0.026 J	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.32	< 0.05 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.05 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	0.25	< 0.049 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 0.24 U	< 0.23 U	< 0.016 U	< 0.092 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.039 U	< 0.045 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.045 U	< 0.052 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.055 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													7									
Restricted - Residential													59									
Protection of Groundwater													210									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	< 0.015 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.021 U	< 0.025 U	< 0.15 U	< 0.2 U	< 0.58 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.019 U	< 0.41 U	< 0.034 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.75 U	< 0.027 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	0.3 J	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.035	< 0.038	< 0.0072	< 0.039	< 0.056	< 0.039	< 0.045	< 0.038	< 0.14	< 0.037
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.24 J	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	0.28 J	< 0.23 U	< 0.67 U	< 0.024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127262-2	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 0.14 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.27 U	< 0.69 U	< 0.057 U	< 0.26 U	< 0.25 U	< 0.29 U	< 0.32 U	< 0.43 U	< 1.3 U	< 0.29 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 0.15 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.14 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.15 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 UT	< 0.15 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 0.14 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.15 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.14 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.14 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 0.13 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 0.15 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.16 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 0.16 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U

													2,4-Dinitrophenol	**2,4-Dinitrotoluene**	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															0.1	0.1	0.1	100	30	0.33		
Restricted - Residential															13	13	13	100	100	1.2		
Protection of Groundwater															0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	< 1.9 U	< 0.051 U	< 0.11 U			0.052 J	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			0.27	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 2.4 U	< 0.066 U	< 0.14 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 2.1 U	< 0.056 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 2.3 U	< 0.062 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.025 U	< 0.043 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 2.2 U	< 0.06 U	< 0.12 U			3	0.17	< 0.029 U	< 0.023 U	< 0.041 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 1.9 U	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 1.9 U	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 2.5 U	< 0.24 U			< 0.13 U	0.026 J	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.21 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 2.1 U	< 0.21 U			< 0.11 U	0.048 J	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 2.2 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	0.046 J	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.43	< 0.029			< 0.041	0.42	< 0.0095	< 0.0076	< 0.008	< 0.039
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			0.12	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 2 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 2 U	< 0.055 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 2.2 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 2 U	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 2.2 U	< 0.054 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 2.5 U	< 0.06 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.22 U			< 0.034 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127262-2	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 2.3 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 2.3 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			0.63	0.062 J	< 0.025 U	< 0.02 U	< 0.036 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			0.022 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 4.6 U	< 0.44 U	< 0.23 U			< 0.039 U	< 0.029 U	< 0.053 U	< 0.043 U	< 0.075 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 2.5 U	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			0.42	0.016 J	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 2.3 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 2.4 UT	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 2.3 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			0.29	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 2.3 U	< 0.22 U	< 0.12 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 2.1 U	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 2.3 U	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.036 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 2.3 U	< 0.22 U	< 0.12 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 2.5 U	< 0.24 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 2.3 U	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 2.6 U	< 0.25 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U

DRAFT

												Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.5	0.33				0.33	12		
Restricted - Residential													0.5	100				100	100		
Protection of Groundwater													8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3224	SSHS-B3224-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	< 0.017 U	0.071	< 0.097 U		< 0.017 U	< 0.016 U	< 0.099 U	< 0.013 U	< 0.15 U	< 0.086 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.019 U	0.071 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	0.037 J	< 0.2 U	< 0.11 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.1 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.021 U	0.33	< 0.11 U		< 0.02 U	0.27	< 0.12 U	0.21	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.092 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.12 U	< 0.035 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.088 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.026	0.053	< 0.025		< 0.027	< 0.0065	< 0.035	< 0.0062	< 0.16	< 0.15
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.018 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.021 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.09 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.12 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.12 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.088 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	< 0.12 U	0.13	< 0.1 U		< 0.13 U	0.029 J	< 0.1 U	0.051 J	< 0.16 U	< 0.088 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 0.14 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.26 U	< 0.073 U	< 0.21 U		< 0.28 U	< 0.035 U	< 0.22 U	< 0.029 U	< 0.34 U	< 0.19 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 0.14 U	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.14 U	0.19	< 0.11 U		< 0.15 U	0.042 J	< 0.12 U	0.075 J	< 0.18 U	< 0.1 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 0.14 U	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.099 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.12 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.14 U	0.13	< 0.11 U		< 0.14 U	< 0.019 U	< 0.11 U	0.025 J	< 0.18 U	< 0.098 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 0.12 U	< 0.034 U	< 0.099 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.013 U	< 0.16 U	< 0.088 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 0.12 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 0.12 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 0.12 U	< 0.035 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 0.14 U	< 0.04 U	< 0.12 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 0.15 U	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.13 U	< 0.017 U	< 0.19 U	< 0.11 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	< 0.016 U	< 0.12 U	< 0.054 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.54 U	0.03 J	< 0.1 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.16	< 0.11 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.021 U	< 0.16 U	< 0.069 U	< 0.31 U		< 0.029 U	< 0.14 U	< 0.7 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	2.8	< 0.12 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	0.03 J	< 0.1 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	0.037 J	< 0.11 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated										
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.15	< 0.03	< 0.04	< 0.13		< 0.0084	< 0.033	< 0.032	< 0.011	< 0.0085
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated										
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	0.076	< 0.11 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.024 U	< 0.12 U	< 0.56 U	0.49	< 0.11 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.021 J	< 0.12 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.27 U	< 0.27 U	< 0.27 U	< 0.52 U		< 0.05 U	< 0.24 U	< 1.2 U	< 0.039 U	< 0.22 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.15 U	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	0.28	< 0.12 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.14 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 0.14 U	< 0.13 U	< 0.13 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 0.15 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	0.026 J	< 0.12 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.019 U	< 0.1 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.56 U	< 0.019 U	< 0.11 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 0.16 U	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16-20210120	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16-20210122	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	0.063 J		< 0.015 U	< 0.14 U	< 0.024 U	< 0.019 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	0.22		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.021 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210510	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	0.026 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-14-16	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	2.2		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	0.023 J		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	0.043 J		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	0.045 J		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated						
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	0.41		< 0.027	< 0.023	< 0.038	< 0.054
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated						
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated						
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18-20210123	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	0.1		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	0.019 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210510	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-16-18	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41-20220209	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S326	SSHS-IRM5A2-S326-20220209	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S327	SSHS-IRM5A2-S327-20220209	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S328	SSHS-IRM5A2-S328-20220209	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S306	SSHS-IRM5A2-S306-20220209	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	0.51		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S307	SSHS-IRM5A2-S307-20220209	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308-20220209	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S309	SSHS-IRM5A2-S309-20220209	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 0.035 U		< 0.29 U	< 0.31 U	< 0.26 U	< 0.24 U
Northern Athletic Field	S310	SSHS-IRM5A2-S310-20220209	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S311	SSHS-IRM5A2-S311-20220209	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 0.019 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43-20220210	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	0.49		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42-20220210	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725-20220210	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S726	SSHS-IRM5A2-S726-20220210	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S727	SSHS-IRM5A2-S727-20220210	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S728	SSHS-IRM5A2-S728-20220210	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 0.019 U		< 0.15 U	< 0.16 U	< 0.14 U	< 0.13 U
Northern Athletic Field	S729	SSHS-IRM5A2-S729-20220210	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B718	SSHS-IRM5A2-B718-20220210	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	0.34		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B752-A2	SSHS-IRM5A2-B752-20220302	SSHS-IRM5A2-B752	3/2/2022	-	857.89	-	839.85	16 - 18 ft	18.04 ft	1801345571	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S325	SSHS-IRM5A2-S325-20220302	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S324	SSHS-IRM5A2-S324-20220302	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S737	SSHS-IRM5A2-S737-20220302	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736-20220302	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B717	SSHS-IRM5A2-B717-20220305	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715-20220305	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B716	SSHS-IRM5A2-B716-20220305	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713-20220305	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 0.019 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	B710	SSHS-IRM5A2-B710-20220318	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B709	SSHS-IRM5A2-B709-20220318	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 0.02 U		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	B708	SSHS-IRM5A2-B708-20220318	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U

DRAFT

														Diesel Range Organics	**Diesel Fuel**	**Total PAH'S**	**Acenaphthene**	**Acenaphthylene**	**Acetophenone**	**Anthracene**	**Atrazine**	**1,1-Biphenyl**	**Benzaldehyde**	**Benz(a)anthracene**
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.034 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated			ND	< 0.019 U	< 0.015 U	< 0.12 U	< 0.017 U	< 0.15 U	< 0.12 U	< 0.042 U	< 0.03 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated			4.792	0.021 J	0.71	< 0.12 U	0.32	< 0.15 U	< 0.13 U	< 0.043 U	0.28
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	< 0.014 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated			ND	< 0.0099 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 UT	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.058 U	< 0.012 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.066 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 U	< 0.014 U	< 0.069 U	< 0.014 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69		18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated			0.428	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.037 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated			ND	< 0.02 U	< 0.016 U	< 0.019 U	< 0.018 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.045 U	< 0.032 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.13 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.022 U	< 0.18 U	< 0.15 U	< 0.052 U	< 0.038 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 UT	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 UT	< 0.015 U	< 0.071 U	< 0.015 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 UT	< 0.014 U	< 0.067 U	< 0.014 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 UT	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.013 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.02 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.032 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.044 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated			ND	< 0.01 U	< 0.01 U	< 0.017 U	< 0.011 U	< 0.021 U	< 0.012 U	< 0.059 U	< 0.012 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.019 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated			0.125	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated			0.018	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.048 U	< 0.035 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1	1	0.8	100					
Restricted - Residential												1	1	3.9	100					
Protection of Groundwater												22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 0.029 U	< 0.016 U	< 0.02 U	< 0.014 U	< 0.12 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.14 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	0.37	0.49	0.23	0.88	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0066 U	< 0.019 U	< 0.015 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.0094 U	< 0.0092 U	< 0.0070 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.019 U	< 0.015 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.0093 U	< 0.0090 U	< 0.0068 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0063 U	< 0.018 U	< 0.014 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.01 U	< 0.0097 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.0094 U	< 0.0091 U	< 0.0069 U	< 0.01 U	< 0.027 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.011 U	< 0.01 U	< 0.0078 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0072 U	< 0.021 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0075 U	< 0.022 U	< 0.016 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	0.04 J	0.034 J	0.022 J	0.036 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.15 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.0098 U	< 0.0095 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.011 U	< 0.011 U	< 0.0084 U	< 0.013 U	< 0.033 U	< 0.015 U	< 0.0077 U	< 0.023 U	< 0.017 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.011 U	< 0.01 U	< 0.0079 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0073 U	< 0.021 U	< 0.016 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	< 0.021 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.011 U	< 0.011 U	< 0.0081 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 UT	< 0.017 U	< 0.013 U	< 0.027 UT	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.0095 U	< 0.0092 U	< 0.0070 U	< 0.011 U	< 0.028 U	< 0.012 U	< 0.0064 U	< 0.019 U	< 0.014 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U

DRAFT

													Butylbenzyl phthalate	Caprolactam	Carbazole	4-Chloroaniline (p-Chloroan	4-Chloro-3-methylphenol	2-Chloronaphthalene	2-Chlorophenol	4-Chlorophenyl phenyl ether	Chrysene	Dibenz(a,h)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					1	0.33
Restricted - Residential																					3.9	0.33
Protection of Groundwater																					1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 0.23 U	< 0.22 U	< 0.016 U	< 0.088 U	< 0.12 U	< 0.015 U	< 0.12 U	< 0.11 U	< 0.037 U	< 0.043 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	< 0.24 U	< 0.23 U	0.054 J	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.12 U	0.35	0.12
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.017 U	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.018 U	< 0.059 U	< 0.014 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.017 U	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.017 U	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.017 U	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.017 U	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.017 U	< 0.055 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.016 U	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.016 U	< 0.054 U	< 0.013 U	< 0.062 U	< 0.02 U	< 0.016 U	< 0.012 U	< 0.012 U	< 0.0059 U	< 0.015 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.018 U	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.068 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.017 U	< 0.055 U	< 0.013 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.012 U	< 0.0060 U	< 0.015 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.019 U	< 0.062 U	< 0.015 U	< 0.071 U	< 0.022 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.019 U	< 0.065 U	< 0.016 U	< 0.074 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0070 U	< 0.018 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.051 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.039 U	< 0.045 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.095 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.017 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.054 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.017 U	< 0.057 U	< 0.014 U	< 0.065 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.02 U	< 0.067 U	< 0.016 U	< 0.076 U	< 0.024 U	< 0.02 U	< 0.015 U	< 0.015 U	< 0.0072 U	< 0.019 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.019 U	< 0.063 U	< 0.015 U	< 0.072 U	< 0.023 U	< 0.019 U	< 0.014 U	< 0.014 U	< 0.0068 U	< 0.017 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.018 U	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.019 U	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0069 U	< 0.018 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 0.27 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.043 U	< 0.05 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.09 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.092 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.017 U	< 0.055 U	< 0.014 U	< 0.063 U	< 0.02 U	< 0.016 U	< 0.013 U	< 0.013 U	< 0.0060 U	< 0.015 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.018 U	< 0.018 U	< 0.023 U	< 0.043 U	< 0.049 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												7									
Restricted - Residential												59									
Protection of Groundwater												210									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 0.12 U	< 0.31 U	< 0.026 U	< 0.12 U	< 0.11 U	< 0.13 U	< 0.15 U	< 0.19 U	< 0.58 U	< 0.13 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	0.2 J	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.14 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.012 U	< 0.055 U	< 0.023 U	< 0.012 U	< 0.044 U	< 0.083 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.026 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.013 U	< 0.058 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 UT	< 0.028 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.012 U	< 0.054 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.012 U	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.012 U	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.019 U	< 0.15 U	< 0.027 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.013 U	< 0.059 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.012 U	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.026 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.012 U	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.012 U	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.012 U	< 0.053 U	< 0.022 U	< 0.011 U	< 0.042 U	< 0.079 U	< 0.013 U	< 0.018 U	< 0.14 U	< 0.025 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.013 U	< 0.057 U	< 0.024 U	< 0.012 U	< 0.045 U	< 0.085 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.013 U	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.012 U	< 0.053 U	< 0.023 U	< 0.011 U	< 0.042 U	< 0.08 U	< 0.013 U	< 0.019 U	< 0.14 U	< 0.025 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.06 UT	< 0.026 U	< 0.013 U	< 0.048 U	< 0.091 U	< 0.015 U	< 0.021 U	< 0.16 UT	< 0.029 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.014 U	< 0.063 UT	< 0.027 U	< 0.013 U	< 0.05 U	< 0.094 U	< 0.016 U	< 0.022 U	< 0.17 UT	< 0.03 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.025 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.2 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.42	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 0.13 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	0.17 J	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 0.15 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	0.14 J	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.14 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 0.15 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.16 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.012 U	< 0.056 U	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 U	< 0.027 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.013 U	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 U	< 0.028 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.014 U	< 0.065 U	< 0.027 U	< 0.014 U	< 0.051 U	< 0.097 U	< 0.016 U	< 0.023 U	< 0.17 U	< 0.031 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.013 U	< 0.058 U	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 U	< 0.028 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.013 U	< 0.061 U	< 0.026 U	< 0.013 U	< 0.048 U	< 0.092 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.029 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.013 U	< 0.059 U	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 U	< 0.028 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 UT	< 0.028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.014 U	< 0.062 UT	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 UT	< 0.03 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 UT	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.016 U	< 0.33 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.67 U	< 0.024 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.21 J	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.32 U	< 0.026 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.59 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.058 UT	< 0.025 U	< 0.012 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.02 U	< 0.16 UT	< 0.028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.012 U	< 0.054 UT	< 0.023 U	< 0.011 U	< 0.042 U	< 0.081 U	< 0.013 U	< 0.019 U	< 0.15 UT	< 0.026 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.016 U	< 0.33 U	< 0.027 U	0.19 J	< 0.022 U	< 0.026 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.017 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.024 U	< 0.028 U	0.35 J	< 0.22 U	< 0.66 U	< 0.024 U

DRAFT

												2,4-Dinitrophenol	**2,4-Dinitrotoluene**	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW827**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.1	0.1	0.1	100	30	0.33		
Restricted - Residential														13	13	13	100	100	1.2		
Protection of Groundwater														0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 2.3 U	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 2.1 U	< 0.2 U	< 0.1 U			< 0.018 U	< 0.013 U	< 0.024 U	< 0.02 U	< 0.034 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 2.3 U	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 2.2 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			0.42	0.048 J	< 0.025 U	< 0.02 U	< 0.035 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.18 U	< 0.039 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.19 UT	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.17 U	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.18 U	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.18 U	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.017 U	< 0.0078 U	< 0.032 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.19 U	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.17 U	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.17 U	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.17 U	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.17 U	< 0.037 U		< 0.03 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0074 U	< 0.031 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.18 U	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.19 U	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.034 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.17 U	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0075 U	< 0.031 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.2 UT	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0085 U	< 0.035 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.2 UT	< 0.045 U		< 0.036 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0088 U	< 0.036 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 2.2 U	< 0.06 U	< 0.12 U			< 0.021 U	< 0.016 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			0.11	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	< 2 U	< 0.053 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 2.3 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 2.2 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 2.3 U	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 2.6 U	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 2.3 U	< 0.22 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 2.2 U	< 0.21 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 2.6 U	< 0.25 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.18 U	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.19 U	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.21 U	< 0.046 U		< 0.037 U		< 0.015 U	< 0.013 U	< 0.02 U	< 0.0091 U	< 0.037 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.19 U	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.2 U	< 0.043 U		< 0.035 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0086 U	< 0.035 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.19 U	< 0.042 U		< 0.034 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0084 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.2 UT	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.02 U	< 0.0087 U	< 0.036 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 2 UT	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 2.1 U	< 0.2 U			< 0.11 U	< 0.018 U	< 0.013 U	< 0.025 U	< 0.02 U	< 0.035 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.17 UT	< 0.038 U		< 0.031 U		< 0.012 U	< 0.01 U	< 0.017 U	< 0.0076 U	< 0.031 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			0.048 J	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.039 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 2 U	< 0.056 U			< 0.11 U	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 2.1 U	< 0.058 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.5	0.33				0.33	12		
Restricted - Residential														0.5	100				100	100		
Protection of Groundwater														8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 0.12 U	< 0.033 U	< 0.096 U		< 0.13 U	< 0.016 U	< 0.098 U	< 0.013 U	< 0.15 U	< 0.085 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.14 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	< 0.12 U	0.58	< 0.099 U		< 0.13 U	0.054 J	< 0.1 U	0.071	< 0.16 U	< 0.088 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.013 U	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0063 U	< 0.028 U	< 0.087 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.013 U	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.013 U	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.087 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0098 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0097 U	< 0.022 U	< 0.0060 U	< 0.027 U	< 0.083 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.0099 U	< 0.022 U	< 0.0061 U	< 0.027 U	< 0.084 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0069 U	< 0.03 U	< 0.095 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.014 U	< 0.016 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U	< 0.032 U	< 0.099 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 0.019 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.018 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.089 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U	< 0.11 U	< 0.14 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 0.15 U	< 0.041 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 0.13 U	< 0.036 U	< 0.1 U		< 0.13 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 0.15 U	< 0.042 U	< 0.12 U		< 0.16 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.013 U	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.015 U	< 0.017 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.027 U	< 0.0074 U	< 0.033 U	< 0.1 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.025 U	< 0.0070 U	< 0.031 U	< 0.096 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.093 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	< 0.0071 U	< 0.031 U	< 0.098 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.019 U	< 0.036 UT	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 0.019 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.11 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.099 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.12 U	< 0.034 U	< 0.098 U	< 0.1 U	< 0.13 U	< 0.016 U		< 0.013 U	< 0.16 U	< 0.087 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.029 U	< 0.092 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.012 U	< 0.014 U	< 0.013 U		< 0.1 U	< 0.01 U	< 0.022 U	< 0.0062 U	< 0.027 U	< 0.085 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.018 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.18 U	< 0.098 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.019 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.02 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.098 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 0.12 U	< 0.12 U	< 0.12 U	< 0.23 U		< 0.023 U	< 0.11 U	< 0.54 U	< 0.018 U	< 0.1 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.12 U	< 0.56 U	0.052 J	< 0.1 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.042 U	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0064 U	< 0.013 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.044 U	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.041 U	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 U	< 0.0062 U	< 0.013 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.042 U	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.042 U	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.075 U	< 0.0065 U	< 0.014 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.045 U	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 U	< 0.0068 U	< 0.014 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.041 U	< 0.02 U	< 0.035 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.04 U	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.04 U	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.072 U	< 0.0061 U	< 0.013 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.04 U	< 0.019 U	< 0.035 U	< 0.057 U		< 0.025 U	< 0.029 U	< 0.071 U	< 0.0061 U	< 0.013 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.043 U	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 U	< 0.0066 U	< 0.014 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.044 U	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 U	< 0.0067 U	< 0.014 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.04 U	< 0.02 U	< 0.035 U	< 0.057 U		< 0.026 U	< 0.029 U	< 0.072 U	< 0.0062 U	< 0.013 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.046 U	< 0.022 U	< 0.04 U	< 0.065 U		< 0.029 U	< 0.033 U	< 0.082 UT	< 0.0070 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.048 U	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.085 UT	< 0.0073 U	< 0.015 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.092	< 0.11 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 0.16 U	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.042 U	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 U	< 0.0065 U	< 0.014 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.044 U	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0067 U	< 0.014 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.049 U	< 0.024 U	< 0.043 U	< 0.07 U		< 0.031 U	< 0.035 U	< 0.088 U	< 0.0075 U	< 0.016 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.044 U	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 U	< 0.0068 U	< 0.014 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.046 U	< 0.022 U	< 0.04 U	< 0.066 U		< 0.029 U	< 0.033 U	< 0.083 U	< 0.0071 U	< 0.015 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.045 U	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.081 U	< 0.0069 U	< 0.014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.045 U	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 UT	< 0.0068 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.047 U	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 UT	< 0.0072 U	< 0.015 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.062 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.55 U	< 0.018 U	< 0.1 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.044 U	< 0.021 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 UT	< 0.0068 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.041 U	< 0.02 U	< 0.036 U	< 0.058 U		< 0.026 U	< 0.029 U	< 0.073 UT	< 0.0063 U	< 0.013 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.017 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	0.04 J	< 0.11 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.018 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	S323	SSHS-IRM5A2-S323-20220318	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S322	SSHS-IRM5A2-S322-20220318	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 0.016 U		< 0.13 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	S735	SSHS-IRM5A2-S735-20220328	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S734	SSHS-IRM5A2-S734-20220328	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733-20220328	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	0.56		< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208-20220825	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.0091 U		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800-20220825	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated	< 0.0095 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801-20220825	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated	< 0.0088 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802-20220825	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated	< 0.0092 U		< 0.011 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804-20220825	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated	< 0.0091 U		< 0.011 U	< 0.025 U	< 0.037 U	< 0.047 U
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805-20220825	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated	< 0.0097 U		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806-20220825	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated	< 0.0088 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807-20220825	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated	< 0.0088 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808-20220825	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated	< 0.0087 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809-20220825	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated	< 0.0087 U		< 0.011 U	< 0.024 U	< 0.035 U	< 0.045 U
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600-20220825	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated	< 0.0094 U		< 0.012 U	< 0.025 U	< 0.038 U	< 0.048 U
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602-20220825	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated	< 0.0095 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603-20220825	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated	< 0.0088 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.045 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.0099 U		< 0.012 U	< 0.027 U	< 0.041 U	< 0.051 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.01 U		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	0.094		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210510	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-18-20	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738-20220210	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739-20220210	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	S740	SSHS-IRM5A2-S740-20220210	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B721	SSHS-IRM5A2-B721-20220210	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 0.02 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	B720	SSHS-IRM5A2-B720-20220210	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719-20220210	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714-20220305	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 0.02 U		< 0.17 U	< 0.17 U	< 0.15 U	< 0.14 U
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803-20220825	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated	< 0.0092 U		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800-20220826	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated	< 0.0095 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801-20220826	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated	< 0.011 U		< 0.013 U	< 0.029 U	< 0.044 U	< 0.055 U
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802-20220826	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated	< 0.0096 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803-20220826	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated	< 0.01 U		< 0.013 U	< 0.027 U	< 0.041 U	< 0.052 U
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804-20220826	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated	< 0.0098 U		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.0097 U		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.01 U		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210510	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-20-22	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.0096 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.05 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.0089 U		< 0.011 U	< 0.024 U	< 0.036 U	< 0.046 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23-20210510	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.02 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	0.037 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	0.018 J		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-22-24	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.018 U		< 0.017 U	< 0.16 U	< 0.027 U	< 0.021 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

														Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
														mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																	20	100		100				1
Restricted - Residential																	100	100		100				1
Protection of Groundwater																	98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]												
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3852	0917121 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.018 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.061 U	< 0.013 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.013 U	< 0.064 U	< 0.013 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated			ND	< 0.024 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.02 U	< 0.02 U	< 0.16 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.036 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.019 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated			0.452	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	2.5	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated			ND	< 0.02 U	< 0.015 U	< 0.12 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.043 U	< 0.031 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.045 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.065 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.023 U	< 0.014 U	< 0.064 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.054 U	< 0.039 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.049 U	< 0.035 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.023 U	< 0.022 U	< 0.19 U	< 0.018 U	< 0.053 U	< 0.038 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated			0.044	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	0.39 J	< 0.05 U	< 0.037 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.044 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.02 U	< 0.012 U	< 0.024 U	< 0.014 U	< 0.068 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.012 U	< 0.022 U	< 0.013 U	< 0.063 U	< 0.013 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated			ND	< 0.026 U	< 0.02 U	< 0.024 U	< 0.023 U	< 0.2 U	< 0.019 U	< 0.056 U	< 0.041 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated			0.913	< 0.022 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	< 0.016 U	< 0.047 U	0.074 J
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.02 U	< 0.019 U	< 0.16 U	< 0.015 U	< 0.045 U	< 0.033 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated			ND	< 0.027 U	< 0.02 U	< 0.025 U	< 0.024 U	< 0.2 U	< 0.02 U	< 0.058 U	< 0.042 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.021 U	< 0.02 U	< 0.17 U	0.056 J	< 0.049 U	< 0.036 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.018 U	< 0.16 U	< 0.034 U	< 0.044 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated			ND	< 0.011 U	< 0.011 U	< 0.019 U	< 0.011 U	< 0.022 U	< 0.013 U	< 0.062 U	< 0.013 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated			0.199	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.017 U	< 0.052 U	< 0.038 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.022 U	< 0.021 U	< 0.18 U	< 0.017 U	< 0.051 U	< 0.037 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated			ND	< 0.012 U	< 0.012 U	< 0.021 U	< 0.013 U	< 0.025 U	< 0.015 U	< 0.069 U	< 0.015 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.023 U	< 0.022 U	< 0.18 U	< 0.018 U	< 0.052 UT	< 0.038 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.048 U	< 0.035 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.048 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.046 U	< 0.033 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated			ND	< 0.034 U	< 0.018 U	< 0.034 U	< 0.022 U	< 0.18 U	< 0.034 U	< 0.052 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated			ND	< 0.027 U	< 0.021 U	< 0.17 U	< 0.024 U	< 0.21 U	< 0.17 U	< 0.058 U	< 0.042 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated			ND	< 0.022 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.14 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated			ND	< 0.025 U	< 0.019 U	< 0.15 U	< 0.022 U	< 0.19 U	< 0.16 U	< 0.054 U	< 0.039 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.018 U	< 0.16 U	< 0.13 U	< 0.044 U	< 0.032 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.021 U	< 0.17 U	< 0.15 U	< 0.05 U	< 0.036 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated			ND	< 0.023 U	< 0.018 U	< 0.14 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.05 U	< 0.037 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated			ND	< 0.024 U	< 0.018 U	< 0.15 U	< 0.021 U	< 0.18 U	< 0.15 U	< 0.051 U	< 0.037 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated			ND	< 0.023 U	< 0.017 U	< 0.14 U	< 0.02 U	< 0.17 U	< 0.14 U	< 0.049 U	< 0.035 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated			ND	< 0.021 U	< 0.016 U	< 0.13 U	< 0.019 U	< 0.16 U	< 0.13 U	< 0.046 U	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated			1.415	< 0.024 U	< 0.024 U	< 0.024 U	0.04 J	< 0.048 U	< 0.028 U	< 0.023 U	0.13
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.024 U	< 0.026 U	< 0.048 U	< 0.028 U	< 0.023 U	< 0.028 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated			ND	< 0.024 U	< 0.024 U	< 0.025 U	< 0.026 U	< 0.049 U	< 0.028 U	< 0.023 U	< 0.028 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Benzo(g,h,i)perylene	Bis(2-chloroethoxy)methane	Bis(2-chloroethyl) ether	Bis(2-chloroisopropyl) ether	Bis(2-ethylhexyl) phthalate (	4-Bromophenyl phenyl ether
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100					
Restricted - Residential													1	1	3.9	100					
Protection of Groundwater													22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.0098 U	< 0.0096 U	< 0.0072 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0067 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.01 U	< 0.0099 U	< 0.0075 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0070 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.03 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.031 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.017 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.018 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.027 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.03 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.37 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.01 U	< 0.01 U	< 0.0077 U	< 0.012 U	< 0.031 U	< 0.014 U	< 0.0071 U	< 0.021 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.01 U	< 0.01 U	< 0.0076 U	< 0.011 U	< 0.03 U	< 0.014 U	< 0.0070 U	0.023 J	< 0.015 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.03 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.027 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.036 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.032 U	< 0.45 U	< 0.03 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.018 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.025 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.011 U	< 0.011 U	< 0.0080 U	< 0.012 U	< 0.032 U	< 0.014 U	< 0.0074 U	< 0.022 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.03 U	< 0.013 U	< 0.0069 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.039 U	< 0.022 U	< 0.027 U	< 0.019 U	< 0.021 U	< 0.016 U	< 0.033 U	< 0.48 U	< 0.031 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	0.071 J	0.096	0.031 J	0.06 J	< 0.018 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.031 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.017 U	< 0.013 U	< 0.027 U	< 0.38 U	< 0.025 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.04 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.022 U	< 0.017 U	< 0.034 U	< 0.5 U	< 0.033 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.028 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.019 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.028 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.01 U	< 0.0098 U	< 0.0074 U	< 0.011 U	< 0.029 U	< 0.013 U	< 0.0068 U	< 0.02 U	< 0.015 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.036 U	0.03 J	< 0.025 U	0.021 J	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.029 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.41 U	< 0.17 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.011 U	< 0.011 U	< 0.0082 U	< 0.012 U	< 0.033 U	< 0.015 U	< 0.0076 U	< 0.022 U	< 0.017 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.037 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.02 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.029 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.019 U	< 0.023 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.41 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.021 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.45 U	< 0.18 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.041 U	< 0.023 U	< 0.028 U	< 0.02 U	< 0.17 U	< 0.017 U	< 0.035 U	< 0.5 U	< 0.2 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.018 U	< 0.023 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.033 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.14 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.037 U	< 0.021 U	< 0.026 U	< 0.019 U	< 0.16 U	< 0.016 U	< 0.032 U	< 0.46 U	< 0.18 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.031 U	< 0.018 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.017 U	< 0.15 U	< 0.014 U	< 0.03 U	< 0.42 U	< 0.17 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.035 U	< 0.02 U	< 0.024 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.03 U	< 0.43 U	< 0.17 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.036 U	< 0.02 U	< 0.025 U	< 0.018 U	< 0.15 U	< 0.015 U	< 0.031 U	< 0.44 U	< 0.18 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.034 U	< 0.019 U	< 0.024 U	< 0.017 U	< 0.14 U	< 0.014 U	< 0.029 U	< 0.42 U	< 0.17 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.032 U	< 0.018 U	< 0.022 U	< 0.016 U	< 0.13 U	< 0.013 U	< 0.027 U	< 0.39 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	0.11	0.13	0.07	0.063 J	< 0.02 U	< 0.021 U	< 0.023 U	< 0.23 U	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.029 U	< 0.03 U	< 0.024 U	< 0.03 U	< 0.02 U	< 0.021 U	< 0.023 U	< 0.23 U	< 0.033 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.03 U	< 0.031 U	< 0.025 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.023 U	< 0.24 U	< 0.034 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

													Butylbenzyl phthalate	**Caprolactam**	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																					1	0.33
Restricted - Residential																					3.9	0.33
Protection of Groundwater																					1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7										
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.017 U	< 0.057 U	< 0.014 U	< 0.066 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0062 U	< 0.016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.068 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0065 U	< 0.017 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 0.29 U	< 0.28 UT	< 0.02 U	< 0.029 U	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.26 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.018 U	< 0.017 U	< 0.017 U	< 0.023 U	< 0.041 U	< 0.048 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.024 U	< 0.017 U	< 0.016 U	< 0.016 U	< 0.021 U	< 0.039 U	< 0.045 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.026 U	< 0.018 UJ	< 0.017 U	< 0.018 U	< 0.023 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.22 U	< 0.016 U	< 0.091 U	< 0.12 U	< 0.016 U	< 0.13 U	< 0.11 U	< 0.038 U	< 0.044 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.018 U	< 0.061 U	< 0.015 U	< 0.07 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.018 U	< 0.06 U	< 0.015 U	< 0.069 U	< 0.022 U	< 0.018 U	< 0.014 U	< 0.014 U	< 0.0066 U	< 0.017 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.048 U	< 0.055 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.29 U	< 0.28 U	< 0.02 U	< 0.029 U	< 0.02 U	< 0.02 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.055 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.047 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.028 U	< 0.019 UJ	< 0.019 U	< 0.019 U	< 0.025 U	< 0.045 U	< 0.052 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.04 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.019 U	< 0.064 U	< 0.016 U	< 0.073 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.014 U	< 0.0069 U	< 0.018 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.018 U	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.018 U	< 0.014 U	< 0.013 U	< 0.0064 U	< 0.016 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.31 U	< 0.29 U	< 0.021 U	< 0.031 U	< 0.021 U	< 0.021 U	< 0.021 U	< 0.027 U	< 0.05 U	< 0.058 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.052 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.26 U	< 0.25 U	0.018 J	< 0.026 U	< 0.018 U	< 0.017 U	< 0.018 U	< 0.023 U	0.076	< 0.049 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.25 U	< 0.23 U	< 0.017 U	< 0.025 U	< 0.017 U	< 0.017 U	< 0.017 U	< 0.022 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.032 U	< 0.022 U	< 0.021 U	< 0.022 U	< 0.028 U	< 0.052 U	< 0.06 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.027 U	< 0.019 U	< 0.018 U	< 0.019 U	< 0.024 U	< 0.045 U	< 0.051 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.027 U	< 0.019 UJ	< 0.018 U	< 0.018 U	< 0.024 U	< 0.044 U	< 0.05 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.018 U	< 0.059 U	< 0.014 U	< 0.067 U	< 0.021 U	< 0.017 U	< 0.013 U	< 0.013 U	< 0.0064 U	< 0.016 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.29 U	< 0.27 U	< 0.02 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.29 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.02 U	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.028 U	< 0.019 UJ	< 0.019 U	< 0.019 U	< 0.025 U	< 0.046 U	< 0.053 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.02 U	< 0.065 U	< 0.016 U	< 0.074 U	< 0.023 U	< 0.019 U	< 0.015 U	< 0.015 U	< 0.0071 U	< 0.018 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.29 U	< 0.27 UT	< 0.02 U	< 0.029 UT	< 0.02 U	< 0.019 U	< 0.02 U	< 0.026 U	< 0.047 U	< 0.054 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.098 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.097 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.25 U	< 0.018 U	< 0.1 U	< 0.13 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.043 U	< 0.049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.1 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.043 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.097 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.27 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.047 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.32 U	< 0.3 U	< 0.022 U	< 0.12 U	< 0.16 U	< 0.021 U	< 0.17 U	< 0.16 U	< 0.052 U	< 0.06 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.099 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.13 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.24 U	< 0.018 U	< 0.098 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.042 U	< 0.048 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.3 U	< 0.28 U	< 0.02 U	< 0.11 U	< 0.15 U	< 0.02 U	< 0.16 U	< 0.14 U	< 0.048 U	< 0.055 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.23 U	< 0.017 U	< 0.094 U	< 0.13 U	< 0.016 U	< 0.13 U	< 0.12 U	< 0.04 U	< 0.046 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.27 U	< 0.26 U	< 0.019 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.15 U	< 0.13 U	< 0.044 U	< 0.051 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.28 U	< 0.26 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.045 U	< 0.052 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.28 U	< 0.27 U	< 0.019 U	< 0.11 U	< 0.14 U	< 0.019 U	< 0.15 U	< 0.14 U	< 0.046 U	< 0.053 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.27 U	< 0.26 U	< 0.018 U	< 0.1 U	< 0.14 U	< 0.018 U	< 0.14 U	< 0.13 U	< 0.044 U	< 0.05 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.25 U	< 0.24 U	< 0.017 U	< 0.096 U	< 0.13 U	< 0.017 U	< 0.14 U	< 0.12 U	< 0.041 U	< 0.047 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.26 U	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	0.1	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.26 U	< 0.17 U	< 0.03 U	< 0.02 U	< 0.037 U	< 0.023 U	< 0.025 U	< 0.025 U	< 0.027 U	< 0.029 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.27 U	< 0.17 U	< 0.031 U	< 0.02 U	< 0.038 U	< 0.023 U	< 0.026 U	< 0.026 U	< 0.028 U	< 0.03 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

DRAFT

Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling^1 (ft amsl)	Final grade elevation^2 (ft amsl)	Change in surface elevation^3 (ft)	Grab sample elevation^4 (ft amsl)	Sample depth at time of sampling^5 (bgs)	Sample depth from final grade^6 (bfg)	Lab Report	Excavation Status^7	Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													7									
Restricted - Residential													59									
Protection of Groundwater													210									
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.22 J	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.016 U	< 0.34 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.012 U	< 0.056 UT	< 0.024 U	< 0.012 U	< 0.044 U	< 0.084 U	< 0.014 U	< 0.02 U	< 0.15 UT	< 0.027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.058 UT	< 0.025 U	< 0.012 U	< 0.046 U	< 0.087 U	< 0.014 U	< 0.02 U	< 0.16 UT	< 0.028 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 0.019 U	< 0.39 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.19 U	< 0.25 U	< 0.73 UT	< 0.026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.023 U	< 0.028 U	0.44	< 0.22 U	< 0.64 U	< 0.023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.015 U	< 0.33 U	< 0.027 U	< 0.12 U	< 0.022 U	< 0.026 U	< 0.15 U	< 0.21 U	< 0.61 U	< 0.022 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 0.017 U	< 0.36 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.024 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.32 U	< 0.027 U	< 0.12 U	< 0.12 U	< 0.14 U	< 0.15 U	< 0.2 U	< 0.6 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.047 U	< 0.089 U	< 0.015 U	< 0.021 U	< 0.16 UT	< 0.028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.059 UT	< 0.025 U	< 0.013 U	< 0.046 U	< 0.088 U	< 0.015 U	< 0.021 U	< 0.16 UT	< 0.028 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.027 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.019 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.026 U	< 0.032 U	< 0.19 U	< 0.25 U	< 0.73 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	0.18 J	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.023 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.023 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.014 U	< 0.062 UT	< 0.026 U	< 0.013 U	< 0.049 U	< 0.093 U	< 0.015 U	< 0.022 U	< 0.17 UT	< 0.03 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 UT	< 0.027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.02 U	< 0.42 U	< 0.035 U	< 0.16 U	< 0.028 U	< 0.033 U	< 0.2 U	< 0.26 U	< 0.78 U	< 0.028 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.017 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.024 U	< 0.028 U	0.26 J	< 0.22 U	< 0.65 U	< 0.023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.016 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.022 U	< 0.027 U	< 0.16 U	< 0.21 U	< 0.62 U	< 0.022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.02 U	< 0.43 U	< 0.036 U	< 0.16 U	< 0.029 U	< 0.034 U	< 0.2 U	< 0.27 U	< 0.8 U	< 0.029 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.025 U	< 0.03 U	< 0.18 U	< 0.23 U	< 0.69 U	< 0.025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 UT	< 0.026 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.017 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.024 U	< 0.029 U	< 0.17 U	< 0.23 U	< 0.68 U	< 0.024 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.057 UT	< 0.024 U	< 0.012 U	< 0.045 U	< 0.086 U	< 0.014 U	< 0.02 U	< 0.15 UT	< 0.027 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.72 U	< 0.026 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.14 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.026 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.23 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.014 U	< 0.063 UT	< 0.027 U	< 0.013 U	< 0.05 U	< 0.095 U	< 0.016 U	< 0.022 U	< 0.17 UT	< 0.03 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.018 U	< 0.39 U	< 0.032 U	< 0.15 U	< 0.026 U	< 0.031 U	< 0.18 U	< 0.25 U	< 0.73 UT	< 0.026 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.12 U	< 0.15 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.36 U	< 0.03 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.17 U	< 0.22 U	< 0.66 U	< 0.15 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.64 U	< 0.14 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.15 U	< 0.034 U	< 0.032 U	< 0.034 U	< 0.14 U	< 0.17 U	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.44 U	< 0.036 U	< 0.16 U	< 0.16 U	< 0.19 U	< 0.21 U	< 0.27 U	< 0.81 U	< 0.18 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.35 U	< 0.029 U	< 0.13 U	< 0.13 U	< 0.15 U	< 0.16 U	< 0.22 U	< 0.65 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.4 U	< 0.033 U	< 0.15 U	< 0.14 U	< 0.17 U	< 0.19 U	< 0.25 U	< 0.74 U	< 0.17 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.33 U	< 0.027 U	< 0.13 U	< 0.12 U	< 0.14 U	< 0.16 U	< 0.21 U	< 0.61 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.37 U	< 0.031 U	< 0.14 U	< 0.13 U	< 0.16 U	< 0.17 U	< 0.23 U	< 0.69 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.38 U	< 0.031 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.7 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.38 U	< 0.032 U	< 0.14 U	< 0.14 U	< 0.16 U	< 0.18 U	< 0.24 U	< 0.71 U	< 0.16 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.14 U	< 0.37 U	< 0.03 U	< 0.14 U	< 0.13 U	< 0.16 U	0.22 J	< 0.23 U	< 0.68 U	< 0.15 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.14 U	< 0.34 U	< 0.028 U	< 0.13 U	< 0.12 U	< 0.15 U	< 0.16 U	< 0.21 U	< 0.63 U	< 0.14 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.028 U	< 0.15 U	< 0.028 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.041 U	< 0.65 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.028 U	< 0.15 U	< 0.029 U	< 0.031 U	< 0.027 U	< 0.024 U	< 0.028 U	< 0.041 U	< 0.65 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.029 U	< 0.15 U	< 0.029 U	< 0.032 U	< 0.028 U	< 0.025 U	< 0.028 U	< 0.042 U	< 0.66 U	< 0.025 U

													2,4-Dinitrophenol	**2,4-Dinitrotoluene**	**1,4-Dioxane, method 8270E**	**1,4-Dioxane, method SW8270**	**1,4-Dioxane, method 8270D**	**Fluoranthene**	**Fluorene**	**Hexachlorobenzene**	**Hexachlorobutadiene**	**Hexachlorocyclopentadiene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															0.1	0.1	0.1	100	30	0.33		
Restricted - Residential															13	13	13	100	100	1.2		
Protection of Groundwater															0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.18 UT	< 0.04 U		< 0.032 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0079 U	< 0.032 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.19 UT	< 0.041 U		< 0.034 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0082 U	< 0.034 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 2.3 UT	< 0.064 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.042 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 2.2 U	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 2.1 U	< 0.056 U	< 0.12 U			< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 2 U	< 0.053 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.025 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 2.1 U	< 0.057 U			< 0.12 U	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 2.1 U	< 0.21 U			< 0.11 UJ	< 0.018 U	< 0.014 U	< 0.025 U	< 0.02 U	< 0.035 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.019 U	< 0.0084 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.19 UT	< 0.042 U		< 0.034 U		< 0.014 U	< 0.011 U	< 0.018 U	< 0.0083 U	< 0.034 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 2.4 U	< 0.065 U	< 0.13 U			< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 2.2 U	< 0.059 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 2.4 U	< 0.064 U	< 0.13 U			< 0.022 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 2 U	< 0.055 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 2.2 U	< 0.061 U			< 0.13 U	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.2 UT	< 0.044 U		< 0.036 U		< 0.014 U	< 0.012 U	< 0.019 U	< 0.0087 U	< 0.036 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.19 UT	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0081 U	< 0.033 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 2.5 U	< 0.068 U	< 0.14 U			< 0.024 U	< 0.018 U	< 0.032 U	< 0.026 U	< 0.046 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 2.1 U	< 0.057 U	< 0.12 U			0.19	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 2 U	< 0.054 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.037 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 2.6 U	< 0.07 U	< 0.15 U			< 0.025 U	< 0.018 U	< 0.033 U	< 0.027 U	< 0.048 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 2.2 U	< 0.061 U	< 0.13 U			< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 2.3 UT	< 0.062 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 2.2 U	< 0.059 U			< 0.12 U	< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 2.4 U	< 0.23 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.19 UT	< 0.041 U		< 0.033 U		< 0.013 U	< 0.011 U	< 0.018 U	< 0.0080 U	< 0.033 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			0.063 J	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 2.3 U	< 0.063 U	< 0.13 U			< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.043 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 2.3 U	< 0.062 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U			< 0.12 U	< 0.021 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.21 UT	< 0.045 U		< 0.037 U		< 0.015 U	< 0.012 U	< 0.02 U	< 0.0089 U	< 0.037 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 2.3 UT	< 0.064 U	< 0.13 U			< 0.022 UT	< 0.017 U	< 0.03 U	< 0.025 U	< 0.043 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.22 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 2.4 U	< 0.23 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.22 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 2.4 U	< 0.23 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.039 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.23 U			< 0.12 U	< 0.02 U	< 0.034 U	< 0.028 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.25 U			< 0.13 U	< 0.022 U	< 0.034 U	< 0.03 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 2.9 U	< 0.28 U			< 0.15 UJ	< 0.025 U	< 0.018 U	< 0.034 U	< 0.027 U	< 0.048 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 2.3 U	< 0.22 U			< 0.12 UJ	< 0.02 U	< 0.015 U	< 0.027 U	< 0.022 U	< 0.038 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 2.7 U	< 0.26 U			< 0.13 UJ	< 0.023 U	< 0.017 U	< 0.031 U	< 0.025 U	< 0.044 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 2.2 U	< 0.21 U			< 0.11 UJ	< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.036 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 2.5 U	< 0.24 U			< 0.12 UJ	< 0.021 U	< 0.016 U	< 0.029 U	< 0.023 U	< 0.041 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 2.5 U	< 0.24 U			< 0.13 UJ	< 0.021 U	< 0.016 U	< 0.029 U	< 0.024 U	< 0.041 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 2.6 U	< 0.25 U			< 0.13 U	< 0.022 U	< 0.016 U	< 0.03 U	< 0.024 U	< 0.042 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 2.4 U	< 0.23 U	< 0.12 U			< 0.021 U	< 0.015 U	< 0.028 U	< 0.023 U	< 0.04 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 2.3 U	< 0.22 U	< 0.11 U			< 0.019 U	< 0.014 U	< 0.026 U	< 0.021 U	< 0.038 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.71 U	< 0.046 U			< 0.053 U	0.3	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.71 U	< 0.046 U			< 0.053 U	< 0.028 U	< 0.025 U	< 0.028 U	< 0.022 U	< 0.03 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.72 U	< 0.047 U			< 0.054 U	< 0.028 U	< 0.025 U	< 0.029 U	< 0.023 U	< 0.03 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.5	0.33				0.33	12		
Restricted - Residential														0.5	100				100	100		
Protection of Groundwater														8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.014 U	< 0.014 U		< 0.11 U	< 0.01 U	< 0.023 U	< 0.0064 U	< 0.028 U	< 0.088 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.091 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.022 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.092 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.035 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.1 U	< 0.014 U	< 0.16 U	< 0.09 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 0.02 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.019 U	0.3		0.39	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.12 U	< 0.034 U	< 0.099 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.013 U	< 0.16 U	< 0.088 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.025 U	< 0.0068 U	< 0.03 U	< 0.093 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.015 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0067 U	< 0.03 U	< 0.092 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.022 U	< 0.043 U	< 0.12 U		< 0.022 U	< 0.021 U	< 0.13 U	< 0.017 U	< 0.2 U	< 0.11 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.022 U	< 0.02 U	< 0.13 U	< 0.017 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.019 U	< 0.037 U	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.021 U	0.041 J		0.044 J	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.014 U	< 0.016 U	< 0.015 U		< 0.12 U	< 0.011 U	< 0.026 U	< 0.0071 U	< 0.031 U	< 0.097 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0066 U	< 0.029 U	< 0.09 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.023 U	< 0.045 U	< 0.13 U		< 0.023 U	< 0.022 U	< 0.13 U	< 0.018 U	< 0.2 U	< 0.11 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U		< 0.021 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.02 U	0.045 J	< 0.11 U		< 0.019 U	< 0.018 U	< 0.11 U	< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.019 U	< 0.036 U	< 0.1 U		< 0.018 U	< 0.017 U	< 0.11 U	< 0.014 U	< 0.16 U	< 0.092 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.024 U	< 0.046 U	< 0.13 U		< 0.024 U	< 0.022 U	< 0.14 U	< 0.018 U	< 0.21 U	< 0.12 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.021 U	< 0.04 U	< 0.12 U		< 0.02 U	< 0.019 U	< 0.12 U	< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.02 U	< 0.039 U	< 0.11 U	< 0.12 U	< 0.02 U	< 0.019 U		< 0.015 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.013 U	< 0.015 U	< 0.014 U		< 0.11 U	< 0.011 U	< 0.024 U	< 0.0065 U	< 0.029 U	< 0.089 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.021 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.021 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.039 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.014 U	< 0.016 U	< 0.016 U		< 0.12 U	< 0.012 U	< 0.026 U	< 0.0072 U	< 0.032 U	< 0.099 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.022 U	< 0.042 U	< 0.12 U		< 0.021 U	< 0.02 U	< 0.12 U	< 0.016 U	< 0.19 U	< 0.11 UT
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.038 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.097 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.014 U	< 0.17 U	< 0.094 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.047 U	< 0.13 U	< 0.14 U	< 0.18 U	< 0.022 U		< 0.018 U	< 0.21 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.096 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U	< 0.11 U	< 0.14 U	< 0.018 U		< 0.015 U	< 0.17 U	< 0.095 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.043 U	< 0.12 U	< 0.13 U	< 0.16 U	< 0.021 U		< 0.017 U	< 0.2 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.035 U	< 0.1 U	< 0.1 U	< 0.13 U	< 0.017 U		< 0.014 U	< 0.16 U	< 0.091 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.04 U	< 0.11 U	< 0.12 U	< 0.15 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.04 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.019 U		< 0.016 U	< 0.18 U	< 0.1 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.041 U	< 0.12 U	< 0.12 U	< 0.15 U	< 0.02 U		< 0.016 U	< 0.19 U	< 0.1 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.14 U	< 0.039 U	< 0.11 U		< 0.15 U	< 0.019 U	< 0.12 U	< 0.015 U	< 0.18 U	< 0.1 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.13 U	< 0.037 U	< 0.11 U		< 0.14 U	< 0.018 U	< 0.11 U	< 0.014 U	< 0.17 U	< 0.093 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.025 U	0.062 J	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U		< 0.025 U	< 0.12 U	< 0.1 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.025 U	< 0.027 U	< 0.031 U	< 0.031 U	< 0.019 U	< 0.027 U		< 0.025 U	< 0.12 U	< 0.1 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.026 U	< 0.028 U	< 0.032 U	< 0.032 U	< 0.02 U	< 0.027 U		< 0.026 U	< 0.12 U	< 0.1 U

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.042 U	< 0.02 U	< 0.037 U	< 0.06 U		< 0.027 U	< 0.03 U	< 0.076 UT	< 0.0065 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.044 U	< 0.021 U	< 0.038 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.079 UT	< 0.0068 U	< 0.014 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 0.021 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3889	051221 10:30 SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.26 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.14 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.25 U		< 0.025 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.017 U	< 0.13 U	< 0.056 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 0.018 U	< 0.14 U	< 0.061 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.062 J	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.24 U		< 0.023 U	< 0.11 U	< 0.56 U	< 0.019 U	< 0.1 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.045 U	< 0.022 U	< 0.039 U	< 0.064 U		< 0.029 U	< 0.032 U	< 0.08 UT	< 0.0069 U	< 0.014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.045 U	< 0.022 U	< 0.039 U	< 0.063 U		< 0.028 U	< 0.032 U	< 0.08 UT	< 0.0068 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.021 U	< 0.16 U	< 0.069 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.021 U	< 0.16 U	< 0.068 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.13 U	< 0.058 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.018 U	< 0.13 U	< 0.059 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.065 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.047 U	< 0.023 U	< 0.041 U	< 0.067 U		< 0.03 U	< 0.034 U	< 0.084 UT	< 0.0072 U	< 0.015 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.044 U	< 0.021 U	< 0.038 U	< 0.062 U		< 0.028 U	< 0.031 U	< 0.078 UT	< 0.0067 U	< 0.014 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.022 U	< 0.16 U	< 0.072 U	< 0.32 U		< 0.03 U	< 0.15 U	< 0.72 U	< 0.024 U	< 0.14 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.02 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.018 U	< 0.14 U	< 0.06 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	0.1	< 0.12 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.018 U	< 0.13 U	< 0.057 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.58 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.023 U	< 0.17 U	< 0.074 U	< 0.33 U		< 0.032 U	< 0.15 U	< 0.75 U	< 0.025 U	< 0.14 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.019 U	< 0.15 U	< 0.064 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.019 U	< 0.14 U	< 0.063 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.043 U	< 0.021 U	< 0.038 U	< 0.061 U		< 0.027 U	< 0.031 U	< 0.077 UT	< 0.0066 U	< 0.014 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	0.036 J	< 0.13 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.67 U	< 0.022 U	< 0.13 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.02 U	< 0.15 U	< 0.066 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.048 U	< 0.023 U	< 0.042 U	< 0.068 U		< 0.03 U	< 0.034 U	< 0.086 UT	< 0.0074 U	< 0.015 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.02 U	< 0.15 U	< 0.067 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.68 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.61 U	< 0.02 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.27 U		< 0.026 U	< 0.13 U	< 0.62 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.16 U	< 0.034 U	< 0.034 U	< 0.29 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.17 U	< 0.17 U	< 0.17 U	< 0.33 U		< 0.032 U	< 0.16 U	< 0.75 U	< 0.025 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.13 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.14 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.6 U	< 0.02 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.16 U	< 0.16 U	< 0.16 U	< 0.3 U		< 0.029 U	< 0.14 U	< 0.69 U	< 0.023 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.13 U	< 0.13 U	< 0.25 U		< 0.024 U	< 0.12 U	< 0.57 U	< 0.019 U	< 0.11 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.64 U	< 0.021 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.28 U		< 0.027 U	< 0.14 U	< 0.65 U	< 0.022 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.15 U	< 0.15 U	< 0.29 U		< 0.028 U	< 0.14 U	< 0.66 U	< 0.022 U	< 0.12 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.15 U	< 0.14 U	< 0.14 U	< 0.28 U		< 0.027 U	< 0.13 U	< 0.63 U	< 0.021 U	< 0.12 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.14 U	< 0.13 U	< 0.14 U	< 0.26 U		< 0.025 U	< 0.12 U	< 0.59 U	< 0.02 U	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.66 U	0.19	< 0.047 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.13 U	< 0.027 U	< 0.026 U	< 0.37 U		< 0.024 U	< 0.055 U	< 0.66 U	< 0.029 U	< 0.047 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15 SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.13 U	< 0.027 U	< 0.026 U	< 0.38 U		< 0.024 U	< 0.056 U	< 0.68 U	< 0.03 U	< 0.048 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyrene	Pyridine	1,2,4,5-Tetrachlorobenzene	2,3,4,6-Tetrachlorophenol	2,4,5-Trichlorophenol	2,4,6-Trichlorophenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.0092 U		< 0.012 U	< 0.025 U	< 0.038 U	< 0.047 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.0096 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25-20210510	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.018 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3889	051221 10:30_SSHS-B3889-SUB-24-25	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated	< 0.019 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.017 U		< 0.015 U	< 0.15 U	< 0.025 U	< 0.019 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 0.018 U		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.016 U		< 0.14 U	< 0.14 U	< 0.12 U	< 0.11 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.0098 U		< 0.012 U	< 0.027 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.0097 U		< 0.012 U	< 0.026 U	< 0.04 U	< 0.05 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.02 U		< 0.019 U	< 0.18 U	< 0.031 U	< 0.024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.01 U		< 0.013 U	< 0.028 U	< 0.042 U	< 0.053 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.0094 U		< 0.012 U	< 0.026 U	< 0.039 U	< 0.049 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.021 U		< 0.019 U	< 0.19 U	< 0.032 U	< 0.025 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	0.17		< 0.016 U	< 0.16 U	< 0.027 U	< 0.021 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.017 U		< 0.016 U	< 0.15 U	< 0.026 U	< 0.02 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.022 U		< 0.02 U	< 0.19 U	< 0.033 U	< 0.026 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.019 U		< 0.017 U	< 0.17 U	< 0.029 U	< 0.022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.019 U		< 0.017 U	< 0.16 U	< 0.028 U	< 0.022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.0094 U		< 0.012 U	< 0.026 U	< 0.038 U	< 0.048 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	0.049 J		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.02 U		< 0.018 U	< 0.17 U	< 0.029 U	< 0.023 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.01 U		< 0.013 U	< 0.028 U	< 0.043 U	< 0.054 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.02 U		< 0.018 U	< 0.18 U	< 0.03 U	< 0.023 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.018 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.02 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.022 U		< 0.19 U	< 0.2 U	< 0.16 U	< 0.16 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.018 U		< 0.15 U	< 0.16 U	< 0.13 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.02 U		< 0.17 U	< 0.18 U	< 0.15 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.017 U		< 0.14 U	< 0.15 U	< 0.12 U	< 0.12 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.019 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.13 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.019 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.02 U		< 0.16 U	< 0.17 U	< 0.14 U	< 0.14 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.019 U		< 0.16 U	< 0.16 U	< 0.14 U	< 0.13 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.017 U		< 0.15 U	< 0.15 U	< 0.13 U	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-12-14	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated	0.22		< 0.025 U	< 0.028 U	< 0.033 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_DW-FD-1	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.031 U		< 0.025 U	< 0.028 U	< 0.033 U	< 0.031 U
Tennis Courts / Main Parking Lot	SSHS-B821	052417 09:15_SSHS-B821-SUB-14-16	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated	< 0.032 U		< 0.026 U	< 0.029 U	< 0.034 U	< 0.031 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Diesel Range Organics	Diesel Fuel	Total PAH'S	Acenaphthene	Acenaphthylene	Acetophenone	Anthracene	Atrazine	1,1-Biphenyl	Benzaldehyde	Benz(a)anthracene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																20	100		100				1
Restricted - Residential																100	100		100				1
Protection of Groundwater																98	107		1000				1
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]											
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated			0.28	< 0.034 U	< 0.017 U	< 0.034 U	< 0.02 U	< 0.17 U	< 0.034 U	< 0.047 U	0.04 J
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated			2.389	< 0.034 U	0.023 J	< 0.034 U	0.085	< 0.15 U	< 0.034 U	< 0.043 U	0.22
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated			0.192	< 0.034 U	< 0.016 U	< 0.034 U	< 0.019 U	< 0.16 U	< 0.034 U	< 0.046 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated			ND	< 0.034 U	< 0.015 U	< 0.034 U	< 0.018 U	< 0.15 U	< 0.034 U	< 0.044 U	< 0.034 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Benzo(a)pyrene (BaP)	**Benzo(b)fluoranthene**	**Benzo(k)fluoranthene**	**Benzo(g,h,i)perylene**	**Bis(2-chloroethoxy)methane**	**Bis(2-chloroethyl) ether**	**Bis(2-chloroisopropyl) ether**	**Bis(2-ethylhexyl) phthalate (**	**4-Bromophenyl phenyl ether**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1	1	0.8	100					
Restricted - Residential													1	1	3.9	100					
Protection of Groundwater													22	1.7	1.7	1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]									
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	0.04 J	< 0.023 U	0.024 J	< 0.034 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	0.16	0.21	0.077	0.1	< 0.13 U	< 0.012 U	< 0.025 U	< 0.36 U	< 0.15 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	0.029 J	< 0.022 U	0.017 J	< 0.034 U	< 0.014 U	< 0.028 U	< 0.4 U	< 0.16 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.017 U	< 0.021 U	< 0.015 U	< 0.13 U	< 0.013 U	< 0.026 U	< 0.38 U	< 0.15 U

DRAFT

												Butylbenzyl phthalate	**Caprolactam**	**Carbazole**	**4-Chloroaniline (p-Chloroan**	**4-Chloro-3-methylphenol**	**2-Chloronaphthalene**	**2-Chlorophenol**	**4-Chlorophenyl phenyl ether**	**Chrysene**	**Dibenz(a,h)anthracene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				1	0.33
Restricted - Residential																				3.9	0.33
Protection of Groundwater																				1	1000
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.25 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.042 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.22 U	0.032 J	< 0.09 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.19	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.24 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.041 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.23 U	< 0.034 U	< 0.093 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.039 U	< 0.034 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Dibenzofuran	3,3-Dichlorobenzidine	2,4-Dichlorophenol	Diethylphthalate	2,4-Dimethylphenol	Dimethylphthalate	Di-n-butyl phthalate	Di-n-octyl phthalate	4,6-Dinitro-2-methylphenol	2,6-Dinitrotoluene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													7									
Restricted - Residential													59									
Protection of Groundwater													210									
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.026 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.2 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.14 U	< 0.034 U	< 0.029 U	< 0.034 U	< 0.13 U	< 0.15 U	< 0.034 U	< 0.22 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.027 U	< 0.034 U	< 0.12 U	< 0.14 U	< 0.034 U	< 0.21 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													2,4-Dinitrophenol	2,4-Dinitrotoluene	1,4-Dioxane, method 8270E	1,4-Dioxane, method SW8270	1,4-Dioxane, method 8270D	Fluoranthene	Fluorene	Hexachlorobenzene	Hexachlorobutadiene	Hexachlorocyclopentadiene
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted															0.1	0.1	0.1	100	30	0.33		
Restricted - Residential															13	13	13	100	100	1.2		
Protection of Groundwater															0.1	0.1	0.1	1000	386	3.2		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.23 U			< 0.12 U	0.079	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.2 U			< 0.11 U	0.48	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.22 U			< 0.12 U	0.052 J	< 0.034 U	< 0.027 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.21 U			< 0.11 U	< 0.019 U	< 0.034 U	< 0.025 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Hexachloroethane	Indeno (1,2,3-cd)pyrene	2-Methylphenol	3/4-Methylphenol	Isophorone	2-Methylnaphthalene	4-methylphenol	Naphthalene	2-Nitroaniline	3-Nitroaniline
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.5	0.33				0.33	12		
Restricted - Residential														0.5	100				100	100		
Protection of Groundwater														8.2	0.33				0.33	12		
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.038 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	0.097	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.02 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.037 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		0.015 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U		< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													4-Nitroaniline	Nitrobenzene	2-Nitrophenol	4-Nitrophenol	N-Nitrosodimethylamine	N-Nitrosodi-n-propylamine	N-Nitrosodiphenylamine	Pentachlorophenol	Phenanthrene	Phenol
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																				0.8	100	0.33
Restricted - Residential																				6.7	100	100
Protection of Groundwater																				0.8	1000	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]										
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.27 U		< 0.034 U	< 0.034 U	< 0.034 U	0.035 J	< 0.12 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.24 U		< 0.034 U	< 0.034 U	< 0.034 U	0.35	< 0.1 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.14 U	< 0.034 U	< 0.034 U	< 0.26 U		< 0.034 U	< 0.034 U	< 0.034 U	0.033 J	< 0.11 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.13 U	< 0.034 U	< 0.034 U	< 0.25 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.11 U

DRAFT

TABLE 6-4C
Deep Soil Results Remaining in Place - SVOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Pyrene	**Pyridine**	**1,2,4,5-Tetrachlorobenzene**	**2,3,4,6-Tetrachlorophenol**	**2,4,5-Trichlorophenol**	**2,4,6-Trichlorophenol**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													100					
Restricted - Residential													100					
Protection of Groundwater													1000					
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]						
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	0.062 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	0.4		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	0.046 J		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.017 U		< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0022 U	< 0.0026 U	< 0.0029 U	< 0.005 UJ	< 0.0034 U	< 0.0037 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	0.017 U	< 0.0017 U	< 0.0016 U	< 0.002 U	< 0.0022 U	< 0.0038 UJ	< 0.0025 U	< 0.0028 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.19 U	< 0.07 U	< 0.15 U	< 0.12 U	< 0.12 U	< 0.11 U	< 0.2 U	< 0.1 U
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.025 U	< 0.0062 U						< 0.0062 U
Football Field	SSHS-B3555	011221 09:45 DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.087 U	< 0.19 U	< 0.14 UJ	< 0.16 U	< 0.14 U	< 0.25 U	< 0.13 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.23 U	< 0.085 U	< 0.18 U	< 0.14 UJ	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.087 U	< 0.19 U	< 0.15 UJ	< 0.16 U	< 0.14 U	< 0.25 U	< 0.13 U
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.22 U	< 0.081 U	< 0.17 U	< 0.13 UJ	< 0.15 U	< 0.13 U	< 0.23 U	< 0.12 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.24 U	< 0.086 U	< 0.18 U	< 0.14 U	< 0.15 U	< 0.14 U	< 0.24 U	< 0.12 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.25 U	< 0.09 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.26 U	< 0.13 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	0.013 J	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	0.012 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	0.0044 J	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 UJ	< 0.0023 U	< 0.004 U	< 0.002 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	0.053 J	< 0.028 U						< 0.028 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.086 U	< 0.18 U	< 0.14 UJ	< 0.15 U	< 0.14 U	< 0.25 U	< 0.13 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	3.9	< 0.071 U	< 0.15 U	< 0.12 UJ	< 0.13 U	< 0.11 U	< 0.2 U	< 0.1 U
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.23 U	< 0.083 U	< 0.18 U	< 0.14 UJ	< 0.15 U	< 0.13 U	< 0.24 U	< 0.12 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.22 U	< 0.078 U	< 0.17 U	< 0.13 U	< 0.14 U	< 0.13 U	< 0.22 U	< 0.11 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.2 U	< 0.074 U	< 0.16 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.21 U	< 0.11 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.18 U	< 0.065 U	< 0.14 U	< 0.11 U	< 0.12 U	< 0.11 U	< 0.19 U	< 0.094 U
Football Field	SSHS-B3556	011421 08:45 DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	0.0091 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	0.0094 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	0.0093 J	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	0.012 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	0.015 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3863	041021 10:00 DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 UJ	< 0.0025 U	< 0.0043 U	< 0.0022 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U	< 0.0043 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0013 U	< 0.002 U	< 0.0022 U	< 0.0018 U	< 0.0033 UJ	< 0.001 U	< 0.0026 U	< 0.0032 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.064 U	< 0.12 U	< 0.14 U	< 0.08 U	< 0.098 U	< 0.12 U	< 0.16 U	0.33
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 UJ	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 UJ	< 0.0051 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated	< 0.0062 U			< 0.0062 U				< 0.0062 U
Football Field	SSHS-B3555	011221 09:45 DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.08 UJ	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U	< 0.28 UJ
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.078 UJ	< 0.15 U	< 0.18 U	< 0.097 U	< 0.12 U	< 0.14 U	< 0.19 U	0.41 J
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.081 UJ	< 0.15 U	< 0.18 U	< 0.1 U	< 0.12 U	< 0.15 U	< 0.2 U	1
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.075 UJ	< 0.14 U	< 0.17 U	< 0.093 U	< 0.11 U	< 0.14 U	< 0.19 U	< 0.26 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.005 U
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0052 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.079 U	< 0.15 U	< 0.18 U	< 0.098 U	< 0.12 U	< 0.15 U	< 0.2 U	< 0.28 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.083 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.21 U	< 0.29 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UJ	< 0.0049 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	0.0027 J	< 0.0036 UJ	< 0.005 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	0.0036 J	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.36	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	0.0029 J	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	0.0071
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.0024 U	< 0.0046 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0044 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated	< 0.028 U			< 0.028 U				< 0.028 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.08 UJ	< 0.15 U	< 0.18 U	< 0.099 U	< 0.12 U	< 0.15 U	< 0.2 U	0.93
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	< 0.065 UJ	< 0.12 U	< 0.15 U	< 0.081 U	< 0.1 U	< 0.12 U	< 0.16 U	< 0.23 U
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.076 UJ	< 0.15 U	< 0.17 U	< 0.095 U	< 0.12 U	< 0.14 U	< 0.19 U	< 0.27 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 UJ	< 0.0048 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.072 U	< 0.14 U	< 0.16 U	< 0.09 U	< 0.11 U	< 0.13 U	< 0.18 U	< 0.25 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.068 U	< 0.13 U	< 0.15 U	< 0.084 U	< 0.1 U	< 0.13 U	< 0.17 U	0.38
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.06 U	< 0.11 U	< 0.14 U	< 0.074 U	< 0.092 U	< 0.11 U	< 0.15 U	0.32
Football Field	SSHS-B3556	011421 08:45 DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	0.0096	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 UJ	< 0.0049 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	0.003 J	< 0.0033 UJ	< 0.0046 U
Football Field	SSHS-B3863	041021 10:00 DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 UJ	< 0.0035 UJ	< 0.0049 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	0.0028 J	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0027 UJ	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U

DRAFT

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0031 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0023 U	< 0.0025 U	< 0.0017 U	< 0.0013 U	< 0.00086 U	< 0.0015 UJ	< 0.0012 U	< 0.0024 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.068 U	< 0.12 U	< 0.083 U	< 0.15 U	< 0.074 U	< 0.079 U	< 0.071 U	< 0.11 U
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0015 UJ	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated			< 0.41 U	< 0.41 U	< 0.41 U	< 0.0062 U	< 0.0062 U	< 0.0062 U
Football Field	SSHS-B3555	011221 09:45 DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.085 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.093 U	< 0.099 U	< 0.089 U	< 0.14 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.082 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.09 U	< 0.096 U	< 0.087 U	< 0.14 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.085 U	< 0.16 U	< 0.1 U	< 0.19 U	< 0.093 U	< 0.099 U	< 0.089 U	< 0.14 U
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.079 U	< 0.14 U	< 0.097 U	< 0.18 U	< 0.086 U	< 0.092 U	< 0.083 U	< 0.13 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.098 U	< 0.088 U	< 0.14 UJ
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.087 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.096 U	< 0.1 U	< 0.092 U	< 0.14 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 UJ	< 0.0034 UJ	< 0.0016 UJ	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0019 UJ	< 0.0034 UJ	< 0.0017 UJ	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 UJ	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 UJ	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.0015 U	< 0.0027 U	0.0035 J	0.016	0.018	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	0.015	0.0027 J	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0014 UJ	< 0.0025 U	< 0.0017 U	< 0.003 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.0014 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.0013 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.0014 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0027 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated			< 0.37 U	< 0.37 U	< 0.37 U	< 0.028 U	< 0.028 U	< 0.028 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.084 U	< 0.15 U	< 0.1 U	< 0.19 U	< 0.092 U	< 0.098 U	< 0.088 U	< 0.14 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	< 0.069 U	< 0.13 U	< 0.085 U	< 0.16 U	< 0.076 U	< 0.081 U	< 0.072 U	< 0.11 U
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.081 U	< 0.15 U	< 0.099 U	< 0.18 U	< 0.088 U	< 0.094 U	< 0.085 U	< 0.13 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 UJ	< 0.0033 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.076 U	< 0.14 U	< 0.093 U	0.24 J	0.78	< 0.089 U	< 0.08 U	< 0.13 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.072 U	< 0.13 U	< 0.088 U	< 0.16 U	< 0.078 U	< 0.084 U	< 0.075 U	< 0.12 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.063 U	< 0.12 U	< 0.078 U	< 0.14 U	< 0.069 U	< 0.074 U	< 0.067 U	< 0.1 U
Football Field	SSHS-B3556	011421 08:45 DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	< 0.0014 U	< 0.0026 U	0.012	0.083	0.024	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 UJ	< 0.0034 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 UJ	< 0.0032 UJ	< 0.0015 UJ	< 0.0016 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3863	041021 10:00 DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0027 UJ	< 0.0018 UJ	< 0.0033 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0016 U	< 0.0024 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0028 UJ	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	0.0025 J	< 0.0017 U	< 0.0016 U	< 0.0024 U

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0045 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U	< 0.0021 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0034 U	< 0.0013 U	< 0.0021 UJ	< 0.0021 U	< 0.0013 U	< 0.0015 UJ	< 0.0018 U	< 0.0016 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.2 U	< 0.075 U	< 0.087 U	< 0.066 U	< 0.11 U	< 0.11 U	< 0.092 U	< 0.099 U
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated		< 0.0062 U	< 0.0062 U				< 0.0062 U	
Football Field	SSHS-B3555	011221 09:45 DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 UJ	< 0.11 U	< 0.12 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.25 U	< 0.091 U	< 0.11 U	< 0.08 U	< 0.13 U	< 0.14 UJ	< 0.11 U	< 0.12 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.25 U	< 0.094 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 UJ	< 0.11 U	< 0.12 U
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.23 U	< 0.087 U	< 0.1 U	< 0.077 U	< 0.13 U	< 0.13 UJ	< 0.11 U	< 0.12 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0047 U	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.25 U	< 0.092 U	< 0.11 U	< 0.081 U	< 0.14 U	< 0.14 U	< 0.11 U	< 0.12 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.26 U	< 0.096 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.14 U	< 0.12 U	< 0.13 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	0.0056	< 0.0022 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.0017 U	< 0.034 U	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.0017 U	< 0.034 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0028 U	< 0.0032 U	< 0.034 U	< 0.0041 U	< 0.0042 U	< 0.0034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated		< 0.028 U	< 0.028 U				< 0.028 U	
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.25 U	< 0.093 U	< 0.11 U	< 0.082 U	< 0.14 U	< 0.14 UJ	< 0.11 U	< 0.12 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	< 0.21 U	< 0.076 U	< 0.088 U	< 0.067 U	< 0.11 U	< 0.11 UJ	< 0.093 U	< 0.1 U
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.089 U	< 0.1 U	< 0.078 U	< 0.13 U	< 0.13 UJ	< 0.11 U	< 0.12 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.23 U	< 0.084 U	< 0.097 U	< 0.074 U	< 0.12 U	< 0.13 U	< 0.1 U	< 0.11 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.21 U	< 0.079 U	< 0.092 U	< 0.07 U	< 0.12 U	< 0.12 U	< 0.097 U	< 0.1 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.19 U	< 0.07 U	< 0.081 U	< 0.062 U	< 0.1 U	< 0.1 U	< 0.086 U	< 0.093 U
Football Field	SSHS-B3556	011421 08:45 DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3863	041021 10:00 DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2720	051619 09:00_SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0024 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U
Football Field	SSHS-B2632	052119 08:40_SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0035 U	< 0.002 U	< 0.005 U	< 0.0018 U	< 0.0024 U	< 0.0016 UJ	< 0.0031 U	< 0.0011 U
Football Field	SSHS-B3567	011321 09:00_SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.078 U	< 0.13 U	< 0.36 U	< 0.12 U	< 0.13 U	< 0.091 U	< 0.073 U	< 0.074 U
Football Field	SSHS-B3575	020321 09:45_SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3579	020621 10:00_SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3583	020621 10:00_DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3583	020621 10:00_SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated					< 0.012 U			
Football Field	SSHS-B3555	011221 09:45_DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.097 U	< 0.16 U	< 0.45 U	0.24 J	0.24 J	< 0.11 U	< 0.091 U	< 0.093 U
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.094 U	< 0.16 U	< 0.44 U	< 0.15 UJ	< 0.15 UJ	< 0.11 U	< 0.088 U	< 0.09 U
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.097 U	< 0.16 U	< 0.46 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.091 U	< 0.093 U
Football Field	SSHS-B3560	011221 09:45_SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.09 U	< 0.15 U	< 0.42 U	< 0.14 U	< 0.15 U	< 0.11 U	< 0.085 U	< 0.086 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	0.0029 J	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	0.0034 J,F1	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3562	011421 08:45_SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	0.0074	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3577	020621 10:00_SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3580	020621 10:00_SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.096 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.09 U	< 0.092 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.1 U	< 0.17 U	< 0.47 U	< 0.15 U	< 0.16 U	< 0.12 U	< 0.094 U	< 0.096 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.0017 U	0.013	< 0.0081 U	0.014	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00_DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B645A	042021 09:30_DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0073 UJ	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30_DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.0018 U	< 0.0014 U	< 0.0015 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B4013	052021 09:30_DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B4013	052021 09:30_SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0045 U	< 0.034 U	< 0.0034 U	< 0.0027 U	< 0.0028 U
Football Field	SSHS-B4165	092421 10:00_DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated					0.014 J			
Football Field	SSHS-B3555	011221 09:45_SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.096 U	< 0.16 U	< 0.45 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.09 U	< 0.092 U
Football Field	SSHS-B3557	011221 09:45_SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	< 0.079 U	< 0.13 U	< 0.37 U	< 0.12 U	< 0.13 U	< 0.092 U	< 0.074 U	< 0.076 U
Football Field	SSHS-B3563	011221 09:45_SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.092 U	< 0.15 U	< 0.43 U	0.19 J	< 0.15 U	< 0.11 U	< 0.086 U	< 0.088 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	0.012	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3559	011321 09:00_SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3564	011321 09:00_SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.087 U	< 0.14 U	< 0.41 U	< 0.13 U	< 0.14 U	< 0.1 U	< 0.082 U	< 0.083 U
Football Field	SSHS-B3565	011321 09:00_SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.082 U	< 0.14 U	< 0.38 U	< 0.13 U	< 0.13 U	< 0.096 U	< 0.077 U	< 0.078 U
Football Field	SSHS-B3566	011321 09:00_SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.073 U	< 0.12 U	< 0.34 U	< 0.11 U	< 0.12 U	< 0.085 U	< 0.068 U	< 0.069 U
Football Field	SSHS-B3556	011421 08:45_DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3556	011421 08:45_SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3561	011421 08:45_SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	0.004 J	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3568	011921 08:30_SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	0.026	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3569	012021 09:30_SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	0.0062	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	0.014	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	0.018	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3863	041021 10:00_DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	0.038	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	0.043	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3855	041321 09:30_SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	0.024 J	< 0.0027 U	< 0.002 U	< 0.0016 UJ	< 0.0016 U
Football Field	SSHS-B3880	041921 10:30_SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	0.0055	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U	< 0.0027 U	< 0.0017 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0025 U	< 0.0017 U	< 0.0014 U	< 0.003 U	< 0.0031 U	< 0.0021 U	< 0.002 U	< 0.0013 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.075 U	< 0.1 U	< 0.071 U	< 0.14 UJ	< 0.13 U	< 0.083 U	< 0.049 U	< 0.078 U
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 UJ	< 0.0029 UJ	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	0.0061
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	0.0055 J
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	0.0049 J
Football Field	SSHS-FB1	FB1_29 JUN 00_16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated		0.0052 J	< 0.0062 U			< 0.0062 U		< 0.0062 U
Football Field	SSHS-B3555	011221 09:45_DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.094 U	< 0.12 U	< 0.089 U	< 0.17 U	< 0.16 U	< 0.1 U	< 0.061 U	< 0.097 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.091 U	< 0.12 U	< 0.087 U	< 0.17 U	< 0.15 U	< 0.1 U	< 0.059 U	< 0.094 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.094 U	< 0.13 U	< 0.089 U	< 0.17 U	< 0.16 U	< 0.1 U	< 0.061 U	< 0.097 U
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.087 U	< 0.12 U	< 0.083 U	< 0.16 U	< 0.15 U	< 0.096 U	< 0.057 U	< 0.09 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0017 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.0019 U	< 0.0012 U	< 0.0018 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 UJ
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	0.004 J
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.093 U	< 0.12 U	< 0.088 U	< 0.17 U	< 0.16 U	< 0.1 U	< 0.06 U	< 0.096 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	180119460l	Not Excavated	< 0.097 U	< 0.13 U	< 0.092 U	< 0.18 U	< 0.16 U	< 0.11 U	< 0.063 U	< 0.1 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.0022 U	0.0017 J	0.0084 J+	< 0.0028 UJ	< 0.0018 U	< 0.0011 U	0.0021 J
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U	< 0.00098 U	< 0.0016 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0014 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.002 U	< 0.0014 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	0.0038 J
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0037 U	< 0.0027 U	< 0.034 U	< 0.0047 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-FB6	FB6_29 JUN 00_17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated		0.026 J	< 0.028 U			< 0.028 U		< 0.028 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.093 U	< 0.12 U	< 0.088 U	< 0.17 U	< 0.16 U	< 0.1 U	< 0.061 U	< 0.096 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	< 0.077 U	< 0.1 U	< 0.072 U	< 0.14 U	< 0.13 U	< 0.084 U	< 0.05 U	< 0.079 U
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.089 U	< 0.12 U	< 0.085 U	< 0.16 U	< 0.15 U	< 0.098 U	< 0.058 U	< 0.092 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.085 U	< 0.11 U	< 0.08 U	< 0.15 UJ	< 0.14 U	< 0.093 U	< 0.055 U	< 0.087 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.079 U	< 0.11 U	< 0.075 U	< 0.14 U	< 0.13 U	< 0.087 U	< 0.052 U	< 0.082 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.07 U	< 0.093 U	< 0.067 U	< 0.13 U	< 0.12 U	< 0.077 U	< 0.046 U	< 0.073 U
Football Field	SSHS-B3556	011421 08:45_DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0017 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0019 UJ
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	180119460l	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0017 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0028 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 UJ	< 0.0026 UJ	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3863	041021 10:00 DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 UJ	< 0.0027 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	0.0071
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	SSHS-B2720	051619 09:00 SSHS-B2720-SUB-14-16	SSHS-B2720-SUB-14-16	5/15/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90165-1	Not Excavated	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Football Field	SSHS-B2632	052119 08:40 SSHS-B2632-SUB-14-16	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated	< 0.0012 U	< 0.0031 UJ	< 0.0016 U	< 0.0021 U	< 0.0036 U
Football Field	SSHS-B3567	011321 09:00 SSHS-B3567-SUB-14-16	SSHS-B3567-SUB-14-16	1/12/2021	855.39	855.47	0.08	-	14 - 16 ft	14.08-16.08 ft	180-115861-1	Not Excavated	< 0.21 U	< 0.18 U	< 0.088 U	< 0.1 U	< 0.36 U
Football Field	SSHS-B3575	020321 09:45 SSHS-B3575-SUB-14-16	SSHS-B3575-SUB-14-16	2/2/2021	854.85	855.40	0.55	-	14 - 16 ft	14.55-16.55 ft	180-116724-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3579	020621 10:00 SSHS-B3579-SUB-14-16	SSHS-B3579-SUB-14-16	2/5/2021	856.27	856.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0081 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-14-16	SSHS-B3580-SUB-14-16	2/5/2021	856.23	856.24	0.01	-	14 - 16 ft	14.01-16.01 ft	180-116914-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3583	020621 10:00 DUP-36	DUP-36	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3583	020621 10:00 SSHS-B3583-SUB-14-16	SSHS-B3583-SUB-14-16	2/5/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	180-116914-1	Not Excavated	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Football Field	SSHS-FB1	FB1 29 JUN 00 16-18	B23495	6/29/2000	857.00	855.82	-1.18	--	16 - 18 ft	14.82-16.82 ft	NA	Not Excavated		< 0.0062 U	< 0.0062 U	< 0.0062 U	
Football Field	SSHS-B3555	011221 09:45 DUP-21	DUP-21	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.45 U
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-16-18	SSHS-B3555-SUB-16-18	1/11/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-115815-1	Not Excavated	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.43 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-16-18	SSHS-B3557-SUB-16-18	1/11/2021	855.18	855.38	0.20	-	16 - 18 ft	16.2-18.2 ft	180-115815-1	Not Excavated	< 0.26 U	< 0.22 U	< 0.11 U	< 0.13 U	< 0.45 U
Football Field	SSHS-B3560	011221 09:45 SSHS-B3560-SUB-16-18	SSHS-B3560-SUB-16-18	1/11/2021	855.32	855.47	0.15	-	16 - 18 ft	16.15-18.15 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.21 U	< 0.1 U	< 0.12 U	< 0.42 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-16-18	SSHS-B3558-SUB-16-18	1/12/2021	855.27	855.53	0.26	-	16 - 18 ft	16.26-18.26 ft	180-115861-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-16-18	SSHS-B3559-SUB-16-18	1/12/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	180-115861-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-16-18	SSHS-B3565-SUB-16-18	1/12/2021	855.32	855.45	0.13	-	16 - 18 ft	16.13-18.13 ft	180-115861-2	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-16-18	SSHS-B3561-SUB-16-18	1/13/2021	855.17	855.41	0.24	-	16 - 18 ft	16.24-18.24 ft	180-115925-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3562	011421 08:45 SSHS-B3562-SUB-16-18	SSHS-B3562-SUB-16-18	1/13/2021	855.07	855.40	0.33	-	16 - 18 ft	16.33-18.33 ft	180-115925-1	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-16-18	SSHS-B3568-SUB-16-18	1/18/2021	855.08	855.49	0.41	-	16 - 18 ft	16.41-18.41 ft	180-116109-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3577	020621 10:00 SSHS-B3577-SUB-16-18	SSHS-B3577-SUB-16-18	2/5/2021	856.15	856.15	0.00	-	16 - 18 ft	16-18 ft	180-116914-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3580	020621 10:00 SSHS-B3580-SUB-16-18	SSHS-B3580-SUB-16-18	2/5/2021	856.23	856.24	0.01	-	16 - 18 ft	16.01-18.01 ft	180-116914-1	Not Excavated	< 0.25 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18-20210401	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.27 U	< 0.23 U	< 0.11 U	< 0.13 U	< 0.46 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-16-18	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-16-18	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.0046 U	< 0.004 U	0.031	0.038	0.069
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-16-18	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3864	041021 10:00 DUP-19	DUP-19	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-16-18	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-16-18	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-16-18	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-16-18	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated	< 0.0046 U	< 0.0039 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-16-18	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-16-18	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B645A	042021 09:30 DUP-01	DUP-01	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0071 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-16-18	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3871	042021 09:30 DUP-11	DUP-11	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-16-18	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.007 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-16-18	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0071 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-16-18	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0074 U
Football Field	SSHS-B4013	052021 09:30 DUP-206	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B4013	052021 09:30 SSHS-B4013-SUB-16-18	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-16-18	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-16-18	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-16-18	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-16-18	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.013 U
Football Field	SSHS-B4165	092421 10:00 DUP-22	DUP-22	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-16-18	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-FB6	FB6 29 JUN 00 17-19	B23402	6/29/2000	856.63	855.63	-1.00	--	17 - 19 ft	16.00-18.00 ft	NA	Not Excavated		< 0.028 U	< 0.028 U	< 0.028 U	
Football Field	SSHS-B3555	011221 09:45 SSHS-B3555-SUB-18-20	SSHS-B3555-SUB-18-20	1/11/2021	855.30	855.33	0.03	-	18 - 20 ft	18.03-20.03 ft	180-115815-1	Not Excavated	< 0.26 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.44 U
Football Field	SSHS-B3557	011221 09:45 SSHS-B3557-SUB-18-20	SSHS-B3557-SUB-18-20	1/11/2021	855.18	855.38	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115815-1	Not Excavated	< 0.21 U	< 0.18 U	< 0.09 U	< 0.1 U	< 0.36 U
Football Field	SSHS-B3563	011221 09:45 SSHS-B3563-SUB-18-20	SSHS-B3563-SUB-18-20	1/11/2021	855.01	855.38	0.37	-	18 - 20 ft	18.37-20.37 ft	180-115815-1	Not Excavated	< 0.24 U	< 0.21 U	< 0.1 U	< 0.12 U	< 0.42 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-18-20	SSHS-B3558-SUB-18-20	1/12/2021	855.27	855.53	0.26	-	18 - 20 ft	18.26-20.26 ft	180-115861-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3559	011321 09:00 SSHS-B3559-SUB-18-20	SSHS-B3559-SUB-18-20	1/12/2021	855.35	855.36	0.01	-	18 - 20 ft	18.01-20.01 ft	180-115861-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3564	011321 09:00 SSHS-B3564-SUB-18-20	SSHS-B3564-SUB-18-20	1/12/2021	855.22	855.42	0.20	-	18 - 20 ft	18.2-20.2 ft	180-115861-1	Not Excavated	< 0.23 U	< 0.2 U	< 0.099 U	< 0.11 U	< 0.4 U
Football Field	SSHS-B3565	011321 09:00 SSHS-B3565-SUB-18-20	SSHS-B3565-SUB-18-20	1/12/2021	855.32	855.45	0.13	-	18 - 20 ft	18.13-20.13 ft	180-115861-2	Not Excavated	< 0.22 U	< 0.19 U	< 0.093 U	< 0.11 U	< 0.38 U
Football Field	SSHS-B3566	011321 09:00 SSHS-B3566-SUB-18-20	SSHS-B3566-SUB-18-20	1/12/2021	855.28	855.43	0.15	-	18 - 20 ft	18.15-20.15 ft	180-115861-2	Not Excavated	< 0.19 U	< 0.17 U	< 0.082 U	< 0.093 U	< 0.33 U
Football Field	SSHS-B3556	011421 08:45 DUP-29	DUP-29	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Football Field	SSHS-B3556	011421 08:45 SSHS-B3556-SUB-18-20	SSHS-B3556-SUB-18-20	1/13/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-115925-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3561	011421 08:45 SSHS-B3561-SUB-18-20	SSHS-B3561-SUB-18-20	1/13/2021	855.17	855.41	0.24	-	18 - 20 ft	18.24-20.24 ft	180-115925-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3568	011921 08:30 SSHS-B3568-SUB-18-20	SSHS-B3568-SUB-18-20	1/18/2021	855.08	855.49	0.41	-	18 - 20 ft	18.41-20.41 ft	180-116109-1	Not Excavated	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SSHS-B3569	012021 09:30 SSHS-B3569-SUB-18-20	SSHS-B3569-SUB-18-20	1/19/2021	855.07	855.22	0.15	-	18 - 20 ft	18.15-20.15 ft	180-116199-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-18-20	SSHS-B3570-SUB-18-20	1/19/2021	855.27	855.46	0.19	-	18 - 20 ft	18.19-20.19 ft	180-116199-1	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20-20210401	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-18-20	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-18-20	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-18-20	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3863	041021 10:00 DUP-39	DUP-39	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-18-20	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-18-20	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-18-20	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-18-20	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3855	041321 09:30 SSHS-B3855-SUB-18-20	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-18-20	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-18-20	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3880	041921 10:30 SSHS-B3880-SUB-18-20	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.05	0.06						0.76
Restricted - Residential													100	4.8						2.4
Protection of Groundwater													0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0054 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0035 U	< 0.0031 U	< 0.0055 U	< 0.0028 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	0.011 J	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 UJ	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30_SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.2 U	< 0.072 U	< 0.15 U	< 0.12 U	< 0.13 U	< 0.12 U	< 0.21 U	< 0.1 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	0.011 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.002 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0046 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0055 U	< 0.002 U	< 0.0042 U	< 0.0033 U	< 0.0035 U	< 0.0032 U	< 0.0056 U	< 0.0028 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0028 U	< 0.0022 U	< 0.0024 UJ	< 0.0021 U	< 0.0038 U	< 0.0019 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0028 U	< 0.0048 U	< 0.0024 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	0.012 J	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0025 U	< 0.0022 U	< 0.0039 U	< 0.002 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	0.0056 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0030 U	< 0.0052 U	< 0.0027 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0028 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 WARN	< 0.0026 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	0.0095 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0051 UHT	< 0.0019 UHT	< 0.0040 UHT	< 0.0031 UHT	< 0.0033 UHT	< 0.0030 UHT	< 0.0053 WARN	< 0.0027 UHT
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	0.0086 J	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.25 U	< 0.09 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.26 U	< 0.13 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	0.011 J	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.004 U	< 0.0022 U	< 0.0027 U	< 0.0033 U	< 0.0044 U	< 0.0062 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	0.0065
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.067 U	< 0.13 U	< 0.15 U	< 0.083 U	< 0.1 U	< 0.12 U	< 0.17 U	0.45
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	0.0018 J	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 UJ	< 0.0047 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U	< 0.0044 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.0035 U	< 0.0041 U	< 0.0023 U	< 0.0028 U	< 0.0034 U	< 0.0045 U	< 0.0063 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0019 U	< 0.0022 U	< 0.003 U	< 0.0042 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0029 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0032 U	< 0.0044 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0055 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U	< 0.0059 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.0040 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0044 U	< 0.0061 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0017 UHT	< 0.0033 UHT	< 0.0039 UHT	< 0.0021 UHT	< 0.0026 UHT	< 0.0032 UHT	< 0.0043 UHT	< 0.0060 UHT
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.083 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.21 U	< 0.29 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.004 U	< 0.0056 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.0021 U	< 0.0022 U	< 0.002 U	< 0.0031 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.0015 UJ	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	856.00	0.01	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.07 U	< 0.13 U	< 0.086 U	< 0.16 U	< 0.077 U	< 0.082 U	< 0.074 U	< 0.12 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	< 0.0014 U	< 0.0026 U	0.012	0.071	0.012	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 UJ	< 0.0032 UJ	< 0.0016 UJ	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0025 UJ	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0022 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.0024 U	< 0.0043 U	< 0.0021 U	< 0.0022 U	< 0.002 U	< 0.0032 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0013 UJ	< 0.0023 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0026 UJ	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0040 U	< 0.0020 U	< 0.0021 U	< 0.0019 U	< 0.0030 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.0020 U	< 0.0022 U	< 0.0020 U	< 0.0031 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0018 UHT	< 0.0033 UHT	< 0.0022 UHT	< 0.0041 UHT	< 0.0020 UHT	< 0.0021 UHT	< 0.0019 UHT	< 0.0030 UHT
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.087 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.096 U	< 0.1 U	< 0.092 U	< 0.14 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.034 U	< 0.0014 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0056 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.003 U	< 0.0031 U	< 0.0025 U	< 0.0027 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	856.00	0.01	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.21 U	< 0.078 U	< 0.09 U	< 0.068 U	< 0.11 U	< 0.12 U	< 0.095 U	< 0.1 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0057 U	< 0.0021 U	< 0.0025 U	< 0.0019 U	< 0.0031 U	< 0.0032 U	< 0.0026 U	< 0.0028 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.0021 U	< 0.0021 U	< 0.0017 U	< 0.0019 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0015 U	< 0.0018 U	< 0.034 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.002 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0053 U	< 0.0020 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0055 U	< 0.0021 U	< 0.0024 U	< 0.0018 U	< 0.0030 U	< 0.0031 U	< 0.0025 U	< 0.0027 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.002 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0054 UHT	< 0.0020 UHT	< 0.0023 UHT	< 0.0018 UHT	< 0.0029 UHT	< 0.0030 UHT	< 0.0024 UHT	< 0.0026 UHT
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.26 U	< 0.096 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.14 U	< 0.12 U	< 0.13 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0014 U	< 0.0016 U	< 0.034 U	< 0.0021 U	< 0.0021 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.002 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3870	042021 09:30_SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.0036 U	< 0.01 U	< 0.0033 U	< 0.0035 U	< 0.0025 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0081 UJ	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.0028 J	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B4011	052021 09:30_SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.0028 J	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.0033 J	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B4164	092421 10:00_SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4165	092421 10:00_SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3558	011321 09:00_SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.081 U	< 0.13 U	< 0.38 U	< 0.12 U	< 0.13 U	< 0.094 U	< 0.075 U	< 0.077 U
Football Field	SSHS-B3570	012021 09:30_SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3876	040321 10:45_SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	0.028	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0017 U	0.0075	< 0.0077 U	0.0092	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	0.0055	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3858	041221 10:25_SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3877	041321 09:30_SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.0071 U	0.003 J	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3881	042021 09:30_SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0022 U	< 0.0037 U	< 0.01 U	< 0.0034 U	< 0.0036 U	< 0.0026 U	< 0.0021 U	< 0.0021 U
Football Field	SSHS-B645A	042021 09:30_SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0069 UJ	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-B3858	042021 09:30_DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.0052	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B4012	052221 09:00_SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	0.0049 J	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0072 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0015 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0034 U	< 0.0096 U	< 0.0032 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0020 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0035 U	< 0.01 U	< 0.0033 U	< 0.0034 U	< 0.0025 U	< 0.0020 U	< 0.0020 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3860	041421 09:00_DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B4010	052121 09:00_DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B4015	070121 09:00_SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0021 UHT	< 0.0034 UHT	< 0.0097 UHT	< 0.0032 UHT	< 0.0034 UHT	< 0.0024 UHT	< 0.0019 UHT	< 0.0020 UHT
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3859	041321 09:30_SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.1 U	< 0.17 U	< 0.47 U	< 0.15 U	< 0.16 U	< 0.12 UJ	< 0.094 U	< 0.096 UJ
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.034 U	< 0.0014 U	< 0.0014 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3865	040921 09:30_DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U

DRAFT

												1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0021 U	< 0.0028 U	< 0.002 U	< 0.0038 U	< 0.0035 U	< 0.0023 U	< 0.0014 U	< 0.0022 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.078 U	< 0.1 U	< 0.074 U	< 0.14 UJ	< 0.13 U	< 0.086 U	< 0.051 U	< 0.081 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	0.0074	< 0.0018 U	< 0.001 U	< 0.0017 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 UJ	< 0.0027 UJ	< 0.0018 U	< 0.001 U	0.0024 J
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.00096 U	0.0026 J
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.0019 U	< 0.0012 U	< 0.0018 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0017 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0021 U	< 0.0028 U	< 0.002 U	< 0.0039 U	< 0.0036 U	< 0.0023 U	< 0.0014 U	< 0.0022 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U	< 0.00093 U	< 0.0015 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.002 U	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.0026 U	< 0.0018 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0016 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.00097 U	< 0.0015 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U	< 0.0013 U	< 0.0021 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0021 U	< 0.0027 U	< 0.0020 U	< 0.0037 U	< 0.0034 U	< 0.0023 U	< 0.0013 U	< 0.0021 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0017 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0020 UHT	< 0.0027 UHT	< 0.0019 UHT	< 0.0036 UHT	< 0.0034 UHT	< 0.0022 UHT	< 0.0013 UHT	< 0.0021 UHT
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.097 U	< 0.13 U	< 0.092 U	< 0.18 U	< 0.16 U	< 0.11 U	< 0.063 U	< 0.1 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0014 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0025 U	< 0.0018 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0018 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0019 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	SSHS-B3870	042021 09:30 SSHS-B3870-SUB-18-20	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-18-20	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated	< 0.0057 U	< 0.0049 U	< 0.0024 U	< 0.0028 U	< 0.0099 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-18-20	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-18-20	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-18-20	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4011	052021 09:30 SSHS-B4011-SUB-18-20	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-18-20	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-18-20	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-18-20	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0087 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-18-20	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0078 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-18-20	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4164	092421 10:00 SSHS-B4164-SUB-18-20	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B4165	092421 10:00 SSHS-B4165-SUB-18-20	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0083 U
Football Field	SSHS-B3558	011321 09:00 SSHS-B3558-SUB-20-22	SSHS-B3558-SUB-20-22	1/12/2021	855.27	855.53	0.26	-	20 - 22 ft	20.26-22.26 ft	180-115861-1	Not Excavated	< 0.21 U	< 0.18 U	< 0.091 U	< 0.1 U	< 0.37 U
Football Field	SSHS-B3570	012021 09:30 SSHS-B3570-SUB-20-22	SSHS-B3570-SUB-20-22	1/19/2021	855.27	855.46	0.19	-	20 - 22 ft	20.19-22.19 ft	180-116199-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22-20210401	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3876	040321 10:45 SSHS-B3876-SUB-20-22	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-20-22	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-20-22	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-20-22	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0072 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-20-22	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3858	041221 10:25 SSHS-B3858-SUB-20-22	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3877	041321 09:30 SSHS-B3877-SUB-20-22	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.004 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.007 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-20-22	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-20-22	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3881	042021 09:30 SSHS-B3881-SUB-20-22	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated	< 0.0058 U	< 0.0051 U	< 0.0025 U	< 0.0028 U	< 0.01 U
Football Field	SSHS-B645A	042021 09:30 SSHS-B645A-SUB-20-22	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0068 U
Football Field	SSHS-B3858	042021 09:30 DUP-12	DUP-12	4/19/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-120245-1	Not Excavated	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-20-22	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0073 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-20-22	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-20-22	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0083 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-20-22	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B4012	052221 09:00 SSHS-B4012-SUB-20-22	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0092 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-20-22	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24-20210401	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-22-24	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-22-24	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-22-24	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-22-24	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.0041 U	< 0.0035 U	< 0.0017 U	< 0.002 U	< 0.0071 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-22-24	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-22-24	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-22-24	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-22-24	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-22-24	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-22-24	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-22-24	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B3874	DUP-25-20210401	DUP-25	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0094 U
Football Field	SSHS-B3874	DUP-33-20210401	DUP-33	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0056 U	< 0.0049 U	< 0.0024 U	< 0.0027 U	< 0.0098 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26-20210401	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.0052 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-24-26	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-24-26	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-24-26	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0072 U
Football Field	SSHS-B3860	041421 09:00 DUP-14	DUP-14	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-24-26	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-24-26	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-24-26	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-24-26	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B4010	052121 09:00 DUP-202	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-24-26	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4015	070121 09:00 SSHS-B4015-SUB-24-26	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-24-26	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28-20210401	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.0055 UHT	< 0.0048 UHT	< 0.0024 UHT	< 0.0027 UHT	< 0.0095 UHT
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-26-28	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-26-28	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-26-28	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Football Field	SSHS-B3859	041321 09:30 SSHS-B3859-SUB-26-28	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated	< 0.27 UJ	< 0.23 U	< 0.11 U	< 0.13 U	< 0.46 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-26-28	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-26-28	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0068 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-26-28	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.0089 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-26-28	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-26-28	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-28-30	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-28-30	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Football Field	SSHS-B3865	040921 09:30 DUP-20	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.05	0.06						0.76
Restricted - Residential													100	4.8						2.4
Protection of Groundwater													0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	0.014 J	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U
Football Field	SSHS-B3864	041021 10:00 DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3571	012021 09:30 DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0041 U	< 0.0032 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0027 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	0.011 J	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0048 U	< 0.0025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	0.01 J	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	0.016 J	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.005 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	0.013 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.0051 U	< 0.0018 U	< 0.0039 U	< 0.003 U	< 0.0033 U	< 0.003 U	< 0.0052 U	< 0.0026 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< UJ	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.005	< 0.00067	< 0.00068	< 0.00056	< 0.00044	< 0.00074	< 0.00051	< 0.00044
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0046	< 0.00063	< 0.00064	< 0.00052	< 0.00041	< 0.00068	< 0.00047	< 0.00041
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0099	< 0.0029	< 0.0014	< 0.0019	< 0.0044	< 0.0017	< 0.002	< 0.0013
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	0.0081 J	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.003 U	< 0.0019 U	< 0.0018 U	< 0.0023 U	< 0.0025 U	< 0.0043 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0047 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 UJ	< 0.0034 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.0019 U	< 0.0024 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0034 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0026 U	< 0.0028 U	< 0.0049 U	< 0.0033 UJ	< 0.0036 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0036 U	< 0.0022 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0051 U	< 0.0034 U	< 0.0038 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.013	< 0.0039	< 0.0018	< 0.0026	< 0.0059	< 0.0022	< 0.0027	< 0.0018
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	0.0037 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0045 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0036 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0033 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0047 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.002 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0031 U	< 0.0019 U	< 0.0019 U	< 0.0023 UJ	< 0.0025 U	< 0.0044 U	< 0.0029 U	< 0.0032 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 UJ	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0033 U	< 0.0037 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0029 U	< 0.0018 U	< 0.0018 U	< 0.0022 U	< 0.0024 U	< 0.0041 U	< 0.0028 U	< 0.003 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0034 U	< 0.0021 U	< 0.0021 U	< 0.0025 U	< 0.0028 U	< 0.0048 U	< 0.0032 U	< 0.0035 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.003 U	< 0.004 U	< 0.0056 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	0.0054 J
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.004 U	< 0.0055 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U	< 0.0056 U
Football Field	SSHS-B3864	041021 10:00 DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0055 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3571	012021 09:30 DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.004 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0044 U	< 0.0061 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U	< 0.0056 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Football Field	SSHS-B3864	041021 10:00 DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0055 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0052 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-32-34	SSHS-B3873-SUB-32-34	4/19/2021	854.94	855.38	0.44	-	32 - 34 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	0.0083
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.078 U	< 0.15 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U	< 0.0056 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	0.0077
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U	< 0.0056 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U	< 0.0058 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	0.0086
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.0019 U	< 0.0035 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00075	< 0.00071	< 0.0015	< 0.00058	< 0.00085	< 0.00037	< 0.00074	< 0.00067
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0007	< 0.00066	< 0.0014	< 0.00054	< 0.00079	< 0.00034	< 0.00069	< 0.00062
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0021	< 0.0024	< 0.0021	< 0.0012	< 0.0025	< 0.0014	< 0.0044	0.0074
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U	< 0.0039 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0033 U	< 0.0041 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0026 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U	< 0.0039 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 0.002 U	< 0.0037 U	< 0.0012 U	< 0.0029 U	< 0.0037 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	< 0.004 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	< 0.004 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0039 U	< 0.0012 U	< 0.0031 U	< 0.0039 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0042 U	< 0.0013 U	< 0.0033 U	< 0.0042 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0044 U	< 0.0014 U	< 0.0035 U	< 0.0044 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0045 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.0029	< 0.0032	< 0.0027	< 0.0016	< 0.0034	< 0.0019	< 0.0058	0.0064
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 0.0016 U	< 0.0024 U	< 0.0026 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.0031 U	< 0.0038 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U	< 0.0041 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0017 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0041 U	< 0.0013 U	< 0.0032 U	< 0.0041 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U	< 0.0041 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0015 U	< 0.0023 U	< 0.0025 U	< 002 U	< 0.0037 U	< 0.0012 U	< 0.003 U	< 0.0037 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	< 0.004 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.0039 U	< 0.0013 U	< 0.0031 U	< 0.0039 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0029 U	< 0.0023 U	< 0.0043 U	< 0.0013 U	< 0.0034 U	< 0.0043 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0014 U	< 0.0022 U	< 0.0024 U	< 0.0019 U	< 0.0035 U	< 0.0011 U	< 0.0028 U	< 0.0035 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0017 U	< 0.0026 U	< 0.0028 U	< 0.0023 U	< 0.0041 U	< 0.0013 U	< 0.0033 U	< 0.0041 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	< 0.004 U

DRAFT

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0016 U	< 0.0029 UJ	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.003 U	< 0.0021 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3864	041021 10:00 DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.003 UJ	< 0.002 U	< 0.0038 U	< 0.0018 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.0015 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3571	012021 09:30 DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0019 U	< 0.0034 U	< 0.0023 U	< 0.0042 U	< 0.002 U	< 0.0022 U	< 0.0019 U	< 0.0031 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.0016 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3864	041021 10:00 DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.003 UJ	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0017 U	< 0.0031 UJ	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0016 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 UJ	< 0.0039 UJ	< 0.0019 UJ	< 0.002 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.082 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.089 U	< 0.034 U	< 0.086 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.0016 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.0014 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.034 U	< 0.0015 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.004 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.034 U	< 0.0017 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.0018 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.0019 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< UJ	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00086	< 0.00066	< 0.00079	< 0.00065	< 0.00063	< 0.00057	< 0.00061	< 0.00084
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.0008	< 0.00062	< 0.00074	< 0.00061	< 0.00059	< 0.00053	< 0.00057	< 0.00079
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0021	< 0.0028	< 0.0031	< 0.0029	< 0.0029	< 0.0011	< 0.0011	< 0.0014
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0028 U	< 0.003 UJ	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 UJ
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0026 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00097 U	< 0.0017 U	< 0.0014 U	< 0.0027 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0028 U	< 0.003 UJ	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 UJ
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0028 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.003 U	< 0.0032 UJ	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 UJ
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0031 U	< 0.0033 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0016 U	< 0.0032 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.0027	< 0.0038	< 0.0042	< 0.0038	< 0.0038	< 0.0014	< 0.0014	< 0.0019
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.0031 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.003 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0027 U	< 0.0028 U	< 0.0019 U	< 0.0015 U	< 0.00099 U	< 0.0018 U	< 0.0014 U	< 0.0028 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.001 U	< 0.0019 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.003 U	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0031 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0025 U	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.00093 U	< 0.0017 U	< 0.0013 U	< 0.0026 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0029 U	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0011 U	< 0.0019 U	< 0.0016 U	< 0.003 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3864	041021 10:00 DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0023 U	< 0.0024 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0019 U	< 0.034 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.034 U
Football Field	SSHS-B3571	012021 09:30 DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0055 U	< 0.002 U	< 0.0024 U	< 0.0018 U	< 0.003 U	< 0.003 U	< 0.0025 U	< 0.0027 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0047 U	< 0.0018 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.0019 U	< 0.034 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0017 U	< 0.002 U	< 0.034 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.09 U	< 0.1 U	< 0.034 U	< 0.13 U	< 0.13 U	< 0.11 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0016 U	< 0.0018 U	< 0.034 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0024 U	< 0.034 U	< 0.003 U	< 0.0031 U	< 0.0025 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.002 U	< 0.034 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.0053 U	< 0.002 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0018 U	< 0.0021 U	< 0.034 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.002 U	< 0.0023 U	< 0.034 U	< 0.0029 U	< 0.0029 U	< 0.0024 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0025 U	< 0.034 U	< 0.0032 U	< 0.0032 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0024 U	< 0.034 U	< 0.0031 U	< 0.0031 U	< 0.0026 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated		< 0.0007	< 0.00059	< 0.00054	< 0.00067	< 0.00059	< 0.00064	< 0.0011
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated		< 0.00065	< 0.00055	< 0.0005	< 0.00063	< 0.00055	< 0.0006	< 0.00099
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0023	< 0.0013	< 0.00099	< 0.0018	< 0.0021	< 0.0023	< 0.0019	< 0.0013
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0019 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.002 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0038 U	< 0.0015 U	< 0.0024 U	< 0.0023 U	< 0.0015 U	< 0.0017 U	< 0.0021 U	< 0.0018 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.004 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0017 U	< 0.0022 U	< 0.0019 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0027 U	< 0.0017 U	< 0.0019 U	< 0.0023 U	< 0.0021 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0045 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0018 U	< 0.002 U	< 0.0024 U	< 0.0022 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.0020 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.003	< 0.0017	< 0.0013	< 0.0024	< 0.0028	< 0.0031	< 0.0026	< 0.0018
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 0.004 U	< 0.0016 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0019 U	< 0.0023 U	< 0.0021 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.002 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0042 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.002 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 UJ	< 0.0017 UJ	< 0.0021 U	< 0.0019 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 UJ	< 0.0018 UJ	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0044 U	< 0.0017 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U	< 0.0021 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0036 U	< 0.0014 U	< 0.0023 U	< 0.0022 U	< 0.0015 U	< 0.0016 U	< 0.002 U	< 0.0017 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0043 U	< 0.0017 U	< 0.0027 U	< 0.0026 U	< 0.0017 U	< 0.0018 U	< 0.0023 U	< 0.002 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U	< 0.002 U

DRAFT

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3863	041021 10:00_SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.009 U	< 0.003 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00_DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.009 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Football Field	SSHS-B3571	012021 09:30_DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0021 U	< 0.0035 U	< 0.01 U	< 0.0033 U	< 0.0034 U	< 0.0025 U	< 0.002 U	< 0.002 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3865	040921 09:30_SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3864	041021 10:00_DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3871	042021 09:30_DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.0016 U	< 0.0017 U
Football Field	SSHS-B3872	042221 09:00_SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B4009	052121 09:00_SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00_SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.14 U	< 0.034 U	< 0.11 U	< 0.088 U	< 0.089 U
Football Field	SSHS-B4010	052121 09:00_SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.002 U	< 0.0032 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3860	041421 09:00_SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.0025 U	< 0.002 U	< 0.002 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.002 U	< 0.0032 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.0017 U	< 0.0017 U
Football Field	SSHS-B3878	040621 10:00_SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Football Field	SSHS-B4016	070121 09:00_SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.0024 U	< 0.0019 U	< 0.0019 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0034 U	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.0021 U
Football Field	SSHS-B3873	042221 09:00_SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.0025 U	< 0.002 U	< 0.0021 U
Football Field	SSHS-B3871	042021 09:30_SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< UJ	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00069	< 0.00068	< 0.0009	< 0.00072	< 0.00088	< 0.00065	< 0.00074	< 0.0007
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00064	< 0.00063	< 0.00084	< 0.00067	< 0.00082	< 0.0006	< 0.00069	< 0.00065
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0039	< 0.0033	< 0.013	< 0.0017	< 0.0029	< 0.0034	< 0.0024	< 0.0023
Northern Athletic Field	SSHS-B3008	082719 09:30_SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3007	082819 09:00_SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0044 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U
Northern Athletic Field	SSHS-B3013	083019 09:00_SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B3026	083019 09:00_SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.004 U	< 0.0022 U	< 0.0056 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0035 U	< 0.0013 U
Northern Athletic Field	SSHS-B3040	083019 09:00_SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B3041	083019 09:00_SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B3055	083019 09:00_SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0042 U	< 0.0023 U	< 0.006 U	< 0.0021 U	< 0.0029 U	< 0.0019 U	< 0.0037 U	< 0.0013 U
Northern Athletic Field	SSHS-B3056	083019 09:00_SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0045 U	< 0.0025 U	< 0.0064 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U
Northern Athletic Field	SSHS-B3012	083119 10:15_SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0048 U	< 0.0026 U	< 0.0067 U	< 0.0024 U	< 0.0033 U	< 0.0021 U	< 0.0042 U	< 0.0015 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.0052	< 0.0044	< 0.017	< 0.0023	< 0.0038	< 0.0046	< 0.0032	< 0.003
Northern Athletic Field	SSHS-B3021	082719 09:30_SSHS-B3021-SUB-14-16	082719 09:30_SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 0.0042 U	< 0.0023 U	< 0.0059 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0037 U	< 0.0013 U
Northern Athletic Field	SSHS-B3034	082719 09:30_SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0023 U	< 0.0031 U	< 0.002 U	< 0.004 U	< 0.0014 U
Northern Athletic Field	SSHS-B3049	082719 09:30_SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0044 U	< 0.0024 U	< 0.0062 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U
Northern Athletic Field	SSHS-B3096	082819 09:00_SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U
Northern Athletic Field	SSHS-B3181	083019 09:00_SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0041 U	< 0.0022 U	< 0.0057 U	< 0.002 U	< 0.0028 U	< 0.0018 U	< 0.0036 U	< 0.0013 U
Northern Athletic Field	SSHS-B3182	083019 09:00_SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B3223	083019 09:00_SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.006 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B3025	083119 10:15_SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0046 U	< 0.0026 U	< 0.0065 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U
Northern Athletic Field	SSHS-B3082	083119 10:15_SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0038 U	< 0.0021 U	< 0.0054 U	< 0.0019 U	< 0.0026 U	< 0.0017 U	< 0.0034 U	< 0.0012 U
Northern Athletic Field	SSHS-B3067	090419 03:44_SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0045 U	< 0.0025 U	< 0.0063 U	< 0.0022 U	< 0.0031 U	< 0.002 U	< 0.0039 U	< 0.0014 U
Northern Athletic Field	SSHS-B3080	090519 09:00_SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2,2-Tetrachloroethane	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**	**1,1,2-Trichloroethane**	**Trichloroethene**
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0016 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00 DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.002 U	< 0.002 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0026 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3571	012021 09:30 DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0021 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0023 U	< 0.0013 U	< 0.0021 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.002 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Football Field	SSHS-B3864	041021 10:00 DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 UJ
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	0.002 J
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.0019 U	< 0.0012 U	< 0.0018 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0022 U	< 0.0016 U	< 0.034 U	< 0.0028 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.0029 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.0025 U	< 0.0018 U	< 0.034 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.002 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 UJ	< 0.0032 UJ	< 0.0021 U	< 0.0013 U	< 0.002 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.12 U	< 0.086 U	< 0.034 U	< 0.15 UJ	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.002 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.002 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.002 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0021 U	< 0.0015 U	< 0.034 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0026 U	< 0.0018 U	< 0.034 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0027 U	< 0.002 U	< 0.034 U	< 0.0035 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.002 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0023 U	< 0.0017 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.002 U	< 0.0026 U	< 0.0019 U	< 0.0036 U	< 0.0033 U	< 0.0022 U	< 0.0013 U	< 0.002 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0024 U	< 0.0017 U	< 0.034 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.0026 U	< 0.0019 U	< 0.034 U	< 0.0033 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.0029 U	< 0.0021 U	< 0.034 U	< 0.0036 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.0028 U	< 0.002 U	< 0.034 U	< 0.0035 U	< 0.034 U	< 0.034 U	< 0.034 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00071	< 0.00068	< 0.00073	< 0.00084	< 0.00088	< 0.00048	< 0.00083	< 0.00065
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00067	< 0.00063	< 0.00068	< 0.00078	< 0.00082	< 0.00045	< 0.00077	< 0.00061
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0038	< 0.0012	< 0.0035	< 0.0039	< 0.0039	< 0.001	< 0.0027	< 0.0011
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0037 U	< 0.0025 U	< 0.0024 U	< 0.0015 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.0039 U	< 0.0027 U	< 0.0026 U	< 0.0016 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0031 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U	< 0.0023 U	< 0.0014 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0025 U	< 0.0024 U	< 0.0015 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U	< 0.0026 U	< 0.0016 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0034 U	< 0.0023 U	< 0.0019 U	< 0.004 U	< 0.0042 U	< 0.0028 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0015 UT	0.0042 J	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	0.0096
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.0051	< 0.0016	< 0.0047	< 0.0052	< 0.0052	< 0.0014	< 0.0036	< 0.0014
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 0.003 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U	< 0.0024 U	< 0.0015 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0032 U	< 0.0022 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U	< 0.0026 U	< 0.0016 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0037 U	< 0.0039 U	< 0.0026 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U	< 0.0026 U	< 0.0016 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0029 U	< 0.0019 U	< 0.0016 U	< 0.0034 U	< 0.0036 U	< 0.0024 U	< 0.0023 U	< 0.0015 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0041 U	< 0.0028 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0027 U	< 0.0018 U	< 0.0015 U	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0022 U	< 0.0014 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0032 U	< 0.0021 U	< 0.0018 U	< 0.0038 U	< 0.004 U	< 0.0027 U	< 0.0026 U	< 0.0016 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Football Field	SSHS-B3863	041021 10:00 SSHS-B3863-SUB-28-30	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-28-30	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-28-30	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-28-30	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0082 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-28-30	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-28-30	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0081 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-30-32	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-30-32	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Football Field	SSHS-B3864	041021 10:00 DUP-37	DUP-37	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-30-32	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0088 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-30-32	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-30-32	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0079 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-30-32	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0075 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-30-32	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0077 U
Football Field	SSHS-B3571	012021 09:30 DUP-35	DUP-35	1/19/2021	855.21	855.30	0.09	-	32 - 34 ft	32.09-34.09 ft	180-116199-1	Not Excavated	< 0.0056 U	< 0.0049 U	< 0.0024 U	< 0.0027 U	< 0.0098 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-32-34	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B3865	040921 09:30 SSHS-B3865-SUB-32-34	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.005 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Football Field	SSHS-B3864	041021 10:00 DUP-38	DUP-38	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0087 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-32-34	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-32-34	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Football Field	SSHS-B3871	042021 09:30 DUP-32	DUP-32	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0087 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-32-34	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.008 U
Football Field	SSHS-B3872	042221 09:00 SSHS-B3872-SUB-32-34	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Football Field	SSHS-B4009	052121 09:00 SSHS-B4009-SUB-32-34	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.002 U	< 0.034 U	< 0.0083 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-32-34	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-33-35	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.0091 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-34-36	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Football Field	SSHS-B3864	041021 10:00 SSHS-B3864-SUB-34-36	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-34-36	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-34-36	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-34-36	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0085 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-34-36	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.11 U	< 0.034 U	< 0.43 U
Football Field	SSHS-B4010	052121 09:00 SSHS-B4010-SUB-35-37	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-36-37	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-36-38	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3860	041421 09:00 SSHS-B3860-SUB-36-38	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-36-38	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0086 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-36-38	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0076 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-37-39	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0092 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-38-40	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.0098 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-38-40	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-39-41	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0084 U
Football Field	SSHS-B3878	040621 10:00 SSHS-B3878-SUB-40-42	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated	< 0.0054 U	< 0.0047 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-40-42	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0021 U	< 0.034 U	< 0.0087 U
Football Field	SSHS-B4016	070121 09:00 SSHS-B4016-SUB-40-42	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0023 U	< 0.034 U	< 0.0093 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-41-43	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.01 U
Football Field	SSHS-B3873	042221 09:00 SSHS-B3873-SUB-42-44	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0025 U	< 0.034 U	< 0.01 U
Football Field	SSHS-B3871	042021 09:30 SSHS-B3871-SUB-43-45	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated	< U	< U	< U	< U	< U
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated	< 0.00091	< 0.00047		< 0.00078	
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated	< 0.00085	< 0.00043		< 0.00072	
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated	< 0.0028	< 0.0025		< 0.0028	< 0.0044
Northern Athletic Field	SSHS-B3008	082719 09:30 SSHS-B3008-SUB-12-14	SSHS-B3008-SUB-12-14	8/26/2019	852.37	854.67	2.30	-	12 - 14 ft	14.3-16.3 ft	180-94752-1	Not Excavated	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3021	DUP-42-20210517	DUP-42	8/26/2019	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3007	082819 09:00 SSHS-B3007-SUB-12-14	SSHS-B3007-SUB-12-14	8/27/2019	852.58	854.74	2.16	-	12 - 14 ft	14.16-16.16 ft	180-94824-3	Not Excavated	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3013	083019 09:00 SSHS-B3013-SUB-12-14	SSHS-B3013-SUB-12-14	8/29/2019	852.90	857.00	4.10	-	12 - 14 ft	16.1-18.1 ft	180-94981-1	Not Excavated	< 0.0015 U	< 0.0038 UJ	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3026	083019 09:00 SSHS-B3026-SUB-12-14	SSHS-B3026-SUB-12-14	8/29/2019	854.13	857.81	3.68	-	12 - 14 ft	15.68-17.68 ft	180-94981-3	Not Excavated	< 0.0014 U	< 0.0035 U	< 0.0018 U	< 0.0023 U	< 0.0041 U
Northern Athletic Field	SSHS-B3040	083019 09:00 SSHS-B3040-SUB-12-14	SSHS-B3040-SUB-12-14	8/29/2019	855.10	858.65	3.55	-	12 - 14 ft	15.55-17.55 ft	180-95006-1	Not Excavated	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B3041	083019 09:00 SSHS-B3041-SUB-12-14	SSHS-B3041-SUB-12-14	8/29/2019	855.17	858.67	3.50	-	12 - 14 ft	15.5-17.5 ft	180-94981-1	Not Excavated	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3055	083019 09:00 SSHS-B3055-SUB-12-14	SSHS-B3055-SUB-12-14	8/29/2019	856.20	858.70	2.50	-	12 - 14 ft	14.5-16.5 ft	180-95006-1	Not Excavated	< 0.0015 U	< 0.0037 U	< 0.0019 U	< 0.0025 U	< 0.0043 U
Northern Athletic Field	SSHS-B3056	083019 09:00 SSHS-B3056-SUB-12-14	SSHS-B3056-SUB-12-14	8/29/2019	855.88	858.82	2.94	-	12 - 14 ft	14.94-16.94 ft	180-94981-2	Not Excavated	< 0.0016 U	< 0.004 U	< 0.002 U	< 0.0026 U	< 0.0047 U
Northern Athletic Field	SSHS-B3012	083119 10:15 SSHS-B3012-SUB-12-14	SSHS-B3012-SUB-12-14	8/30/2019	853.28	855.95	2.67	-	12 - 14 ft	14.67-16.67 ft	180-95047-2	Not Excavated	< 0.0017 U	< 0.0042 U	< 0.0021 U	< 0.0028 U	< 0.0049 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14-20210120	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0073 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated	< 0.0038	< 0.0033		< 0.0037	< 0.0058
Northern Athletic Field	SSHS-B3021	082719 09:30 SSHS-B3021-SUB-14-16	082719 09:30 SSHS-B3021-SUB-14-16	8/26/2019	853.71	855.73	2.02	-	14 - 16 ft	16.02-18.02 ft	180-94752-2	Not Excavated	< 0.0014 U	< 0.0036 U	< 0.0019 U	< 0.0024 U	< 0.0043 U
Northern Athletic Field	SSHS-B3034	082719 09:30 SSHS-B3034-SUB-14-16	SSHS-B3034-SUB-14-16	8/26/2019	855.10	856.53	1.43	-	14 - 16 ft	15.43-17.43 ft	180-94752-3	Not Excavated	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3049	082719 09:30 SSHS-B3049-SUB-14-16	SSHS-B3049-SUB-14-16	8/26/2019	856.17	857.50	1.33	-	14 - 16 ft	15.33-17.33 ft	180-94754-2	Not Excavated	< 0.0015 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0045 U
Northern Athletic Field	SSHS-B3096	082819 09:00 SSHS-B3096-SUB-14-16	SSHS-B3096-SUB-14-16	8/27/2019	855.86	856.29	0.43	-	14 - 16 ft	14.43-16.43 ft	180-94819-3	Not Excavated	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3181	083019 09:00 SSHS-B3181-SUB-14-16	SSHS-B3181-SUB-14-16	8/29/2019	857.57	857.81	0.24	-	14 - 16 ft	14.24-16.24 ft	180-95024-1	Not Excavated	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3182	083019 09:00 SSHS-B3182-SUB-14-16	SSHS-B3182-SUB-14-16	8/29/2019	857.45	857.88	0.43	-	14 - 16 ft	14.43-16.43 ft	180-95024-1	Not Excavated	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3223	083019 09:00 SSHS-B3223-SUB-14-16	SSHS-B3223-SUB-14-16	8/29/2019	858.27	858.28	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95006-2	Not Excavated	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3025	083119 10:15 SSHS-B3025-SUB-14-16	SSHS-B3025-SUB-14-16	8/30/2019	854.59	855.82	1.23	-	14 - 16 ft	15.23-17.23 ft	180-95047-1	Not Excavated	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3082	083119 10:15 SSHS-B3082-SUB-14-16	SSHS-B3082-SUB-14-16	8/30/2019	856.73	857.22	0.49	-	14 - 16 ft	14.49-16.49 ft	180-95047-3	Not Excavated	< 0.0013 U	< 0.0034 U	< 0.0017 U	< 0.0022 U	< 0.0039 U
Northern Athletic Field	SSHS-B3067	090419 03:44 SSHS-B3067-SUB-14-16	SSHS-B3067-SUB-14-16	9/3/2019	856.40	856.48	0.08	-	14 - 16 ft	14.08-16.08 ft	180-95162-1	Not Excavated	< 0.0016 U	< 0.0039 U	< 0.002 U	< 0.0026 U	< 0.0046 U
Northern Athletic Field	SSHS-B3080	090519 09:00 SSHS-B3080-SUB-14-16	SSHS-B3080-SUB-14-16	9/4/2019	856.58	856.76	0.18	-	14 - 16 ft	14.18-16.18 ft	180-95165-1	Not Excavated	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												0.05	0.06						0.76
Restricted - Residential												100	4.8						2.4
Protection of Groundwater												0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0035 U	< 0.0022 U	< 0.0021 U	< 0.0026 U	< 0.0029 U	< 0.005 U	< 0.0034 U	< 0.0037 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0032 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B3264	122119 10:30 SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	0.0037 J	< 0.0019 U	< 0.0019 U	< 0.0023 U	< 0.0026 U	< 0.0044 U	< 0.003 U	< 0.0033 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0033 U	< 0.0029 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.00024 U	< 0.00035 U	< 0.00064 U	< 0.0024 U	< 0.00043 U	< 0.0024 U	< 0.00047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	0.0068 J	0.00037 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.016 U	< 0.00052 U	< 0.00092 U	< 0.0011 U	< 0.0018 U	< 0.0031 U	< 0.00086 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.003 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.004 U	< 0.002 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0033 U	< 0.002 U	< 0.002 U	< 0.0024 U	< 0.0027 U	< 0.0046 U	< 0.0031 U	< 0.0034 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0073	< 0.0022	< 0.001	< 0.0014	< 0.0033	< 0.0012	< 0.0015	< 0.00097
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0037 U	< 0.0023 U	< 0.0022 U	< 0.0027 U	< 0.003 U	< 0.0052 U	< 0.0035 U	< 0.0038 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0038 U	< 0.0024 U	< 0.0023 U	< 0.0029 U	< 0.0032 U	< 0.0055 U	< 0.0037 U	< 0.004 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3264A	012221 08:30 SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 UT	< 0.0022 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	0.0079 J	0.00035 J	< 0.0004 U	< 0.00074 U	< 0.0028 U	< 0.0005 U	< 0.0028 U	< 0.00054 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.0054 U	0.00068 J	< 0.00046 U	< 0.00086 U	< 0.0032 U	< 0.00058 U	< 0.0032 U	< 0.00062 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.025 U	< 0.00083 U	< 0.0015 U	< 0.0018 U	< 0.0028 U	< 0.0049 U	< 0.0014 U	< 0.0039 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	0.016	< 0.00032 U	< 0.00035 U	< 0.00032 U	< 0.00053 U	< 0.0012 U	< 0.00033 UT	< 0.00048 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	0.012 J	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	0.0082 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 UT	< 0.0023 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.0037 U	< 0.00021 U	< 0.00031 U	< 0.00058 U	< 0.0022 U	< 0.00039 U	< 0.0022 U	< 0.00042 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	0.025 J	0.00052 J	< 0.00043 U	< 0.00079 U	< 0.003 U	< 0.00053 U	< 0.003 U	< 0.00057 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	0.076	< 0.0012 U	< 0.0022 U	< 0.0026 U	< 0.0042 U	< 0.0072 U	< 0.002 U	< 0.0057 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.029 U	< 0.00097 U	< 0.0017 U	< 0.0021 U	< 0.0033 U	< 0.0058 U	< 0.0016 U	< 0.0045 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.0051 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00038 U	< 0.00089 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.02 U	< 0.0074 U	< 0.016 U	< 0.012 U	< 0.013 U	< 0.012 U	< 0.021 UT	< 0.011 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	0.0091 J	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0018 U	< 0.0027 U	< 0.0029 U	< 0.0024 U	< 0.0043 U	< 0.0014 U	< 0.0034 U	< 0.0043 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0016 U	< 0.0025 U	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	< 0.004 U
Northern Athletic Field	SSHS-B3264	122119 10:30_SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0038 U	< 0.0012 U	< 0.003 U	< 0.0038 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U	< 0.0058 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U	< 0.0056 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0015 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 UT	< 0.0028 U	< 0.0038 U	< 0.0054 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00063 U	< 0.00062 U	< 0.0011 U	< 0.0003 U	< 0.00029 U	< 0.00067 U	< 0.0024 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.00088 U	< 0.00085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00068 U	< 0.0021 U	< 0.002 U	< 0.00058 U	< 0.0017 U	0.0013 J	< 0.0027 U	< 0.0089 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	0.0027 J	< 0.0025 U	< 0.0029 U	0.0016 J	< 0.002 U	< 0.0024 U	< 0.0033 U	< 0.0045 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0039 J,B	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	0.0028 J	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	0.0027 J,B	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0016 U	< 0.0025 UJ	< 0.0027 U	< 0.0022 U	< 0.004 U	< 0.0013 U	< 0.0032 U	0.0041 J
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0016	< 0.0018	< 0.0015	< 0.00089	< 0.0019	< 0.0011	< 0.0032	0.0036
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0018 U	< 0.0028 U	< 0.003 U	< 0.0025 U	< 0.0045 U	< 0.0014 U	< 0.0036 U	< 0.0045 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0019 U	< 0.0029 U	< 0.0031 U	< 0.0026 U	< 0.0047 U	< 0.0015 U	< 0.0037 U	< 0.0047 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3264A	012221 08:30_SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 UT	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	0.0044 J	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.00073 U	< 0.00071 U	< 0.0013 U	< 0.00034 U	< 0.00033 U	< 0.00078 U	< 0.0028 U	< 0.0026 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00095 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.00085 U	< 0.00082 U	< 0.0014 U	0.00043 J	< 0.00039 U	0.0012 J	< 0.0032 U	< 0.0029 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.00081 U	< 0.0025 U	< 0.0024 U	< 0.0007 U	< 0.002 U	< 0.0012 U	< 0.0032 U	< 0.011 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0033 U	< 0.0032 U	< 0.00093 U	< 0.0027 U	< 0.0016 U	< 0.0043 U	< 0.014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00065 U	< 0.0012 U	< 0.00054 U	0.00029 J	< 0.00057 U	0.0014 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	0.00022 J	< 0.00042 U	< 0.0010 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 UT	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 UT	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.00057 U	< 0.00056 U	< 0.00098 U	< 0.00027 U	< 0.00026 U	< 0.00061 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.00064 U	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.00078 U	< 0.00076 U	< 0.0013 U	< 0.00037 U	< 0.00036 U	0.0011 J	< 0.003 U	< 0.0027 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.0016 U	< 0.0048 U	< 0.0048 U	< 0.0014 U	< 0.004 U	< 0.0024 U	< 0.0063 U	< 0.021 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.0039 U	< 0.0038 U	< 0.0011 U	< 0.0032 U	< 0.0019 U	< 0.005 U	< 0.017 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00047 U	< 0.00087 U	< 0.00039 U	0.00025 J	< 0.00041 U	< 0.0010 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	< 0.00021 U	< 0.00043 U	0.0011 J
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U	< 0.0052 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.0068 U	< 0.013 U	< 0.015 U	< 0.0084 U	< 0.01 U	< 0.013 U	< 0.017 U	< 0.024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethene	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.003 U	< 0.0033 U	< 0.0022 U	< 0.0018 U	< 0.0011 U	< 0.002 U	< 0.0016 U	< 0.0032 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B3264	122119 10:30_SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	< 0.0027 U	< 0.0029 U	< 0.002 U	< 0.0016 U	< 0.001 U	< 0.0018 U	< 0.0014 U	< 0.0028 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00062 U	< 0.0004 U	< 0.00038 U	< 0.00025 U	< 0.00067 U	< 0.00059 U	< 0.00024 U	< 0.00059 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00033 U	< 0.034 U	
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00057 U	< 0.0007 U	< 0.00082 U	< 0.0006 U	< 0.00065 U	< 0.00051 U	< 0.00057 U	< 0.0013 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0028 U	< 0.003 UJ	< 0.0021 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.0015 U	< 0.0029 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0015	< 0.0021	< 0.0023	< 0.0021	< 0.0021	< 0.0008	< 0.0008	< 0.001
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0032 U	< 0.0034 U	< 0.0023 U	< 0.0018 U	< 0.0012 U	< 0.0021 U	< 0.0017 U	< 0.0033 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0033 U	< 0.0035 U	< 0.0024 U	< 0.0019 U	< 0.0012 U	< 0.0022 U	< 0.0018 U	< 0.0035 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3264A	012221 08:30_SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.00071 U	< 0.00046 U	< 0.00043 U	< 0.00028 U	< 0.00078 U	< 0.00068 U	< 0.00028 U	< 0.00068 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00037 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.00082 U	< 0.00053 U	< 0.0005 U	< 0.00033 U	< 0.0009 U	< 0.00078 U	< 0.00032 U	< 0.00078 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.00068 U	< 0.00083 UJ	< 0.00098 U	< 0.00072 U	< 0.00078 UJ	< 0.00061 U	< 0.00068 U	< 0.0016 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.00091 U	< 0.0011 U	< 0.0013 U	< 0.00097 U	< 0.001 U	< 0.00082 U	< 0.00091 U	< 0.0022 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00042 U	< 0.00045 U	< 0.00045 U	< 0.00028 U	< 0.00026 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.00056 U	< 0.00036 U	< 0.00034 U	< 0.00022 U	< 0.00061 U	< 0.00053 U	< 0.00022 U	< 0.00053 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.00024 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.00076 U	< 0.00049 U	< 0.00046 U	< 0.0003 U	< 0.00083 U	< 0.00072 U	< 0.0003 U	< 0.00073 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.0013 U	< 0.0016 UJ	< 0.0019 U	< 0.0014 U	< 0.0015 UJ	< 0.0012 U	< 0.0013 U	< 0.0032 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0013 U	< 0.0015 U	< 0.0011 U	< 0.0012 U	< 0.00096 U	< 0.0011 U	< 0.0025 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00033 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0017 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.0072 U	< 0.013 U	< 0.0088 U	< 0.016 U	< 0.0079 U	< 0.0084 U	< 0.0075 U	< 0.012 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0044 U	< 0.0018 U	< 0.0028 U	< 0.0027 U	< 0.0018 U	< 0.0019 U	< 0.0024 U	< 0.0021 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0016 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B3264	122119 10:30_SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	< 0.0039 U	< 0.0015 U	< 0.0025 U	< 0.0024 U	< 0.0016 U	< 0.0017 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0029 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.0025 U	< 0.00062 U	< 0.0005 U	< 0.0024 U	< 0.00069 U	< 0.0021 U	< 0.00033 U	< 0.0011 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00085 U	< 0.00069 U	< 0.034 U	< 0.034 U	< 0.0029 U	< 0.00046 U	< 0.034 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.00083 U	< 0.0011 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0027 U	< 0.00078 U	< 0.00095 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0018 U	< 0.0013 U	< 0.0022 U	< 0.0023 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0041 U	< 0.0016 U	< 0.0026 U	< 0.0025 U	< 0.0017 U	< 0.0018 U	< 0.0022 U	< 0.002 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0017	< 0.00096	< 0.00073	< 0.0013	< 0.0016	< 0.0017	< 0.0014	< 0.00098
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0046 U	< 0.0018 U	< 0.0029 U	< 0.0028 U	< 0.0019 U	< 0.002 U	< 0.0025 U	< 0.0022 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0048 U	< 0.0019 U	< 0.0031 U	< 0.003 U	< 0.0019 U	< 0.0021 U	< 0.0026 U	< 0.0023 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3264A	012221 08:30_SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.0029 U	< 0.00071 U	< 0.00057 U	< 0.0028 U	< 0.0008 U	< 0.0024 U	< 0.00038 U	< 0.0013 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.0034 U	< 0.00082 U	< 0.00066 U	< 0.0032 U	< 0.00092 U	< 0.0028 U	< 0.00044 U	< 0.0015 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00075 U	< 0.0025 U	< 0.0033 U	< 0.00093 UJ	< 0.0011 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.0018 U	< 0.0017 U	< 0.001 U	< 0.0034 U	< 0.0044 U	< 0.0012 U	< 0.0015 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00033 U	< 0.00025 U	< 0.00037 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U	< 0.00028 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.0023 U	< 0.00056 U	< 0.00045 U	< 0.0022 U	< 0.00063 U	< 0.0019 U	< 0.0003 U	< 0.00099 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00062 U	< 0.0005 U	< 0.034 U	< 0.0007 U	< 0.0021 U	< 0.00034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.0031 U	< 0.00076 U	< 0.00061 U	< 0.003 U	< 0.00085 U	< 0.0026 U	< 0.00041 U	< 0.0014 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.002 U	< 0.0026 U	< 0.0025 U	< 0.0015 U	< 0.005 U	< 0.0065 U	< 0.0018 UJ	< 0.0022 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.002 U	< 0.0012 U	< 0.004 U	< 0.0052 U	< 0.0015 U	< 0.0018 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.00034 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00024 U	< 0.00024 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0047 U	< 0.0018 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.021 U	< 0.0079 U	< 0.0092 U	< 0.0070 U	< 0.012 U	< 0.012 U	< 0.0097 U	< 0.01 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0047 U	< 0.0026 U	< 0.0066 U	< 0.0023 U	< 0.0032 U	< 0.0021 U	< 0.0041 U	< 0.0015 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B3264	122119 10:30 SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	< 0.0041 U	< 0.0023 U	< 0.0058 U	< 0.0021 U	< 0.0029 U	< 0.0018 U	< 0.0036 U	< 0.0013 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0021 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.0024 U	< 0.00072 U	< 0.0029 U	< 0.00073 U	< 0.0018 U	< 0.0016 U	< 0.00047 U	< 0.00024 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 UJ	< 0.034 U	< 0.034 U	< 0.00065 U	< 0.034 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.003 U	< 0.0014 U	< 0.0025 U	0.0021 J	< 0.0026 U	< 0.0028 U	< 0.0015 U	< 0.00086 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0074 U	< 0.0024 U	< 0.0026 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0043 U	< 0.0024 U	< 0.0061 U	< 0.0022 U	< 0.003 U	< 0.0019 U	< 0.0038 U	< 0.0014 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0029	< 0.0025	< 0.0095	< 0.0013	< 0.0021	< 0.0025	< 0.0018	< 0.0017
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0049 U	< 0.0027 U	< 0.0068 U	< 0.0024 U	< 0.0034 U	< 0.0022 U	< 0.0043 U	< 0.0015 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0051 U	< 0.0028 U	< 0.0072 U	< 0.0026 U	< 0.0035 U	< 0.0023 U	< 0.0045 U	< 0.0016 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3264A	012221 08:30 SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 UT	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	0.036	< 0.0028 UT	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.0028 U	< 0.00084 U	< 0.0033 U	< 0.00084 U	< 0.002 U	< 0.0018 U	< 0.00054 U	< 0.00028 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.0032 U	< 0.00097 UJ	< 0.0039 U	0.0023 J	< 0.0023 U	< 0.0021 U	< 0.00063 U	< 0.00032 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.0036 U	< 0.0017 UJ	< 0.003 U	< 0.0011 U	< 0.0031 U	< 0.0033 U	< 0.0018 U	< 0.001 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.0048 U	< 0.0023 U	< 0.004 U	< 0.0015 U	< 0.0042 U	< 0.0044 U	< 0.0023 U	< 0.0014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.0021 U	< 0.00035 U	< 0.0054 U	< 0.00062 U	< 0.00046 U	< 0.0019 U	< 0.00064 U	< 0.00035 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U	< 0.00025 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 UT	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	0.01	< 0.0027 UT	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.0022 U	< 0.00066 U	< 0.0026 U	< 0.00066 U	< 0.0016 U	< 0.0014 U	< 0.00043 U	< 0.00022 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.0016 U	< 0.00048 U	< 0.00024 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.003 U	< 0.00089 U	0.014 J	0.0018 J	< 0.0022 U	< 0.0019 U	< 0.00058 U	< 0.0003 U
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.0071 U	< 0.0033 UJ	< 0.0059 U	< 0.0021 U	< 0.0062 U	< 0.0065 U	< 0.0034 U	< 0.002 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.0057 U	< 0.0027 U	< 0.0047 U	< 0.0017 U	< 0.0049 U	< 0.0052 U	< 0.0028 U	< 0.0016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.0015 U	< 0.00025 U	< 0.0038 U	< 0.00045 U	< 0.00033 U	< 0.0014 U	< 0.00046 U	< 0.00025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0040 U	< 0.00047 U	< 0.00034 U	< 0.0015 U	< 0.00048 U	< 0.00026 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 UT	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.0082 U	< 0.014 U	< 0.039 U	< 0.013 U	< 0.013 U	< 0.0096 U	< 0.0077 U	< 0.0079 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,1,2,2-Tetrachloroethane	Tetrachloroethene	Toluene	1,2,3-Trichlorobenzene	1,2,4-Trichlorobenzene	1,1,1-Trichloroethane	1,1,2-Trichloroethane	Trichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													1.3	0.7			0.68		0.47
Restricted - Residential													19	100			100		21
Protection of Groundwater													1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3220	090519 09:00_SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0033 U	< 0.0022 U	< 0.0019 U	< 0.0039 U	< 0.0042 U	< 0.0028 U	< 0.0027 U	< 0.0017 U
Northern Athletic Field	SSHS-B3221	090519 09:00_SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0036 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0015 U
Northern Athletic Field	SSHS-B3264	122119 10:30_SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	< 0.0029 U	< 0.002 U	< 0.0017 U	< 0.0035 U	< 0.0037 U	< 0.0025 U	< 0.0024 U	0.002 J
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U	< 0.0022 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0020 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00078 U	< 0.00064 U	0.00037 J	< 0.00051 U	< 0.00029 U	< 0.00035 U	< 0.00062 U	< 0.0011 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.0009 U	0.0014 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.0011 U	0.0035 J	0.0014 J	< 0.0022 U	< 0.0019 U	< 0.0013 U	< 0.00084 U	0.0063
Northern Athletic Field	SSHS-DW-10_11	060622 10:25_SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-DW-15	060622 10:25_SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0015 U	< 0.002 U	< 0.0014 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.001 U	< 0.0016 U
Northern Athletic Field	SSHS-DW-16	060622 10:25_SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25_SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-06	062122 07:00_SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00_SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3092	122119 10:30_SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0031 U	< 0.0021 U	< 0.0017 U	< 0.0037 U	< 0.0038 U	< 0.0026 U	< 0.0025 U	< 0.0016 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0028	< 0.00088	< 0.0026	< 0.0029	< 0.0029	< 0.00077	< 0.002	< 0.0008
Northern Athletic Field	SSHS-B3087	083119 10:15_SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0035 U	< 0.0023 U	< 0.002 U	< 0.0041 U	< 0.0043 U	< 0.0029 U	< 0.0028 U	< 0.0017 U
Northern Athletic Field	SSHS-B3224	083119 10:15_SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0036 U	< 0.0024 U	< 0.002 U	< 0.0043 U	< 0.0045 U	< 0.003 U	< 0.0029 U	< 0.0018 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0017 UT	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3264A	012221 08:30_SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0017 UT	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0017 UT	0.0051 J	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3645A	080621 09:00_SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3647A	080621 09:00_SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.0009 U	< 0.00074 U	< 0.00042 U	< 0.00059 U	< 0.00034 U	< 0.0004 U	< 0.00072 U	< 0.0012 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	0.00058 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.001 U	< 0.00086 U	0.0019 J	< 0.00068 U	< 0.00039 U	< 0.00047 U	< 0.00083 U	< 0.0014 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.0013 U	< 0.00065 U	< 0.00068 U	< 0.0026 U	< 0.0022 U	< 0.0016 U	< 0.001 U	< 0.00056 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.0017 U	0.00091 J	< 0.00092 U	< 0.0035 U	< 0.003 U	< 0.0021 U	< 0.0013 U	0.0041 J
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.00027 U	0.00098 J	0.00042 J	< 0.00023 U	< 0.00045 U	< 0.00029 U	< 0.00022 U	0.00075 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.00020 U	0.00064 J	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U	< 0.00016 U	0.00035 J
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.0017 UT	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	< 0.0016 UT	< 0.0022 U	< 0.0015 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0015 U	< 0.0020 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U	< 0.00099 U	< 0.0016 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.00071 U	< 0.00058 U	0.0005 J	< 0.00046 U	< 0.00026 U	< 0.00032 U	< 0.00057 U	< 0.00096 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00065 U	< 0.00037 U	< 0.034 U	< 0.0003 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15_SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.00096 U	< 0.0008 U	0.0013 J	< 0.00063 U	< 0.00036 U	< 0.00043 U	< 0.00077 U	< 0.0013 U
Northern Athletic Field	SSHS-B4163	092321 09:30_SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.0025 U	< 0.0013 U	< 0.0013 U	< 0.0051 U	< 0.0044 U	< 0.0031 U	< 0.002 U	< 0.0011 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.002 U	0.005 J	< 0.0011 U	< 0.0041 U	< 0.0035 U	< 0.0025 U	< 0.0016 U	0.0093
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.00019 U	0.00071 J	0.00022 J	< 0.00016 U	< 0.00032 U	< 0.00021 U	< 0.00016 U	0.00045 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.00020 U	0.00062 J	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	0.00046 J
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0018 UT	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0019 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.0080 U	< 0.011 U	< 0.0075 U	< 0.014 U	< 0.013 U	< 0.0087 U	< 0.0052 U	< 0.0082 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B3220	090519 09:00 SSHS-B3220-SUB-14-16	SSHS-B3220-SUB-14-16	9/4/2019	857.44	857.92	0.48	-	14 - 16 ft	14.48-16.48 ft	180-95165-3	Not Excavated	< 0.0016 U	< 0.0041 U	< 0.0021 U	< 0.0027 U	< 0.0048 U
Northern Athletic Field	SSHS-B3221	090519 09:00 SSHS-B3221-SUB-14-16	SSHS-B3221-SUB-14-16	9/4/2019	857.92	857.93	0.01	-	14 - 16 ft	14.01-16.01 ft	180-95165-3	Not Excavated	< 0.0015 U	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0044 U
Northern Athletic Field	SSHS-B3264	122119 10:30 SSHS-B3264-SUB-14-16	SSHS-B3264-SUB-14-16	12/18/2019	854.30	857.51	3.21	-	14 - 16 ft	17.21-19.21 ft	180-100380-1	Not Excavated	< 0.0014 U	< 0.0036 U	< 0.0018 U	< 0.0024 U	< 0.0042 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16-20210506	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16-20210510	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.0054 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	SSHS-B3914	DUP-36-20210512	DUP-36	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16-20210512	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16-20210512	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16-20210517	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16-20210517	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16-20210518	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3883	DUP-2-20210519	DUP-2	5/19/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-14-16	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated	< 0.00045 U	< 0.00059 U	< 0.00081 U	< 0.00063 U	< 0.00081 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-14-16	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-14-16	SSHS-B4264-SUB-14-16	11/1/2021	852.29	853.31	1.02	-	14 - 16 ft	15.02-17.02 ft	180-129325-1	Not Excavated	< 0.002 U	< 0.0013 U	0.0009 J	< 0.00064 U	< 0.0012 U
Northern Athletic Field	SSHS-DW-10_11	060622 10:25 SSHS-DW-10_11-SUB-14-16	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-DW-15	060622 10:25 SSHS-DW-15-SUB-14-16	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated	< 0.0042 U	< 0.0036 U	< 0.0018 U	< 0.002 U	< 0.0073 U
Northern Athletic Field	SSHS-DW-16	060622 10:25 SSHS-DW-16-SUB-14-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-7_8	060622 10:25 SSHS-DW-7_8-SUB-14-16	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-DW-06	062122 07:00 SSHS-DW-06-SUB-14-16	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-DW-3A	062122 07:00 SSHS-DW-3A-SUB-14-16	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B3092	122119 10:30 SSHS-B3092-SUB-16-17	SSHS-B3092-SUB-16-17	12/20/2019	858.31	858.15	-0.16	-	16 - 17 ft	15.84-16.84 ft	180-100361-1	Not Excavated	< 0.0015 UJ	< 0.0038 U	< 0.0019 U	< 0.0025 U	< 0.0045 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated	< 0.0021	< 0.0018		< 0.0021	< 0.0032
Northern Athletic Field	SSHS-B3087	083119 10:15 SSHS-B3087-SUB-16-18	SSHS-B3087-SUB-16-18	8/30/2019	857.68	857.65	-0.03	-	16 - 18 ft	15.97-17.97 ft	180-95047-2	Not Excavated	< 0.0017 U	< 0.0043 U	< 0.0022 U	< 0.0028 U	< 0.005 U
Northern Athletic Field	SSHS-B3224	083119 10:15 SSHS-B3224-SUB-16-18	SSHS-B3224-SUB-16-18	8/30/2019	858.38	858.48	0.10	-	16 - 18 ft	16.1-18.1 ft	180-95050-1	Not Excavated	< 0.0018 U	< 0.0045 U	< 0.0023 U	< 0.003 U	< 0.0052 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18-20210120	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3264A	012221 08:30 SSHS-B3264A-SUB-16-18	SSHS-B3264A-SUB-16-18	1/21/2021	854.31	857.51	3.20	-	16 - 18 ft	19.2-21.2 ft	180-116310-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18-20210122	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18-20210122	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18-20210401	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.0046 U	< 0.0039 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3915	DUP-37-20210506	DUP-37	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18-20210506	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18-20210506	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18-20210510	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3930	SSHS-B3930-SUB-16-18-20210511	SSHS-B3930-SUB-16-18	5/11/2021	856.50	855.82	-0.68	-	16 - 18 ft	15.32-17.32 ft	1801214742	Not Excavated	< 0.0046 U	< 0.0040 U	0.0032 J	0.0030 J	< 0.0080 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18-20210513	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18-20210514	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18-20210517	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18-20210517	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18-20210518	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3645A	080621 09:00 SSHS-B3645A-SUB-16-18	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3647A	080621 09:00 SSHS-B3647A-SUB-16-18	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-16-18	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated	< 0.00052 U	< 0.00068 U	< 0.00093 U	< 0.00072 U	< 0.00093 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-16-18	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0013 UJ	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-16-18	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.00061 U	< 0.00078 U	0.0014 J	< 0.00084 U	0.0014 J
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-16-18	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated	< 0.0024 U	< 0.0016 U	< 0.00069 UJ	< 0.00076 U	< 0.0014 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-16-18	SSHS-B4264-SUB-16-18	11/1/2021	852.29	853.31	1.02	-	16 - 18 ft	17.02-19.02 ft	180-129325-1	Not Excavated	< 0.0032 U	< 0.0021 U	< 0.00093 U	< 0.001 U	< 0.0019 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18-20230119	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated	< 0.00051 U	< 0.00068 U	0.00070 J	< 0.00024 U	0.00070 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18-20230119	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20-20210122	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-18-20-20210122	SSHS-B3454-SUB-18-20	1/22/2021	853.65	857.32	3.67	-	18 - 20 ft	21.67-23.67 ft	1801163651	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20-20210401	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20-20210506	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20-20210506	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3895	DUP-16-20210510	DUP-16	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20-20210510	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20-20210512	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20-20210513	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20-20210514	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20-20210517	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20-20210518	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-18-20	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated	< 0.00041 U	< 0.00053 U	< 0.00073 U	< 0.00057 U	< 0.00073 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-18-20	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00082 U	< 0.034 U	< 0.00082 U
Northern Athletic Field	SSHS-B4162	091821 10:15 SSHS-B4162-SUB-18-20	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.00056 U	< 0.00072 U	0.0013 J	< 0.00077 U	0.0013 J
Northern Athletic Field	SSHS-B4163	092321 09:30 SSHS-B4163-SUB-18-20	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated	< 0.0047 U	< 0.0031 U	< 0.0014 UJ	< 0.0015 U	< 0.0028 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-18-20	SSHS-B4264-SUB-18-20	11/1/2021	852.29	853.31	1.02	-	18 - 20 ft	19.02-21.02 ft	180-129325-1	Not Excavated	< 0.0037 U	< 0.0025 U	< 0.0011 U	< 0.0012 U	< 0.0022 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20-20230119	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated	< 0.00036 U	< 0.00049 U	< 0.00016 U	< 0.00017 U	< 0.00016 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20-20230119	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated	< 0.00038 U	< 0.00051 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-20-22-20210122	SSHS-B3454-SUB-20-22	1/22/2021	853.65	857.32	3.67	-	20 - 22 ft	23.67-25.67 ft	1801163651	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0084 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22-20210401	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.022 U	< 0.019 U	< 0.0093 U	< 0.011 U	< 0.038 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22-20210506	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22-20210506	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22-20210510	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22-20210512	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.05	0.06						0.76
Restricted - Residential													100	4.8						2.4
Protection of Groundwater													0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0029 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0040 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	0.0049 J	< 0.00019 U	< 0.00028 U	< 0.00052 U	< 0.0019 U	< 0.00035 U	< 0.0019 U	< 0.00037 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	0.39	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.0024 U	< 0.00088 U	< 0.0019 U	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0025 U	< 0.0013 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.017 U	< 0.00057 U	< 0.001 U	< 0.0012 U	< 0.002 U	< 0.0034 U	0.0025 J	< 0.0026 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.019 U	< 0.00062 U	< 0.0011 U	< 0.0013 U	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.0072 U	< 0.00033 U	< 0.00035 U	< 0.00032 U	< 0.00054 U	< 0.0013 U	< 0.00034 UT	< 0.00049 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	0.0063	0.00064 J	< 0.00023 U	< 0.00021 U	< 0.00035 U	< 0.00082 U	< 0.00022 UT	< 0.00032 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.26 U	< 0.094 U	< 0.2 U	< 0.16 U	< 0.17 U	< 0.15 U	< 0.27 U	< 0.14 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 UT	< 0.0022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.0040 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.0036 U	< 0.00021 U	< 0.00031 U	< 0.00057 U	< 0.0021 U	< 0.00038 U	< 0.0021 U	< 0.00041 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0037 U	< 0.0013 U	< 0.0029 U	< 0.0022 U	< 0.0024 U	< 0.0022 U	< 0.0038 U	< 0.0019 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.021 U	< 0.0007 U	< 0.0037 U	< 0.0012 U	< 0.0015 U	< 0.0024 U	< 0.0042 U	< 0.0012 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.016 U	< 0.00052 U	< 0.00092 U	< 0.0011 U	< 0.0018 U	< 0.0031 U	< 0.00087 U	< 0.0024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	0.0097	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.0050 U	< 0.00023 U	< 0.00025 U	< 0.00023 U	< 0.00037 U	< 0.00088 U	< 0.00023 UT	< 0.00034 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 UT	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 250 U	< 91 U	< 190 U	< 150 U	< 160 U	< 150 U	< 260 U	< 130 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	0.0045 J	0.00024 J	< 0.00028 U	< 0.00052 U	< 0.0019 U	< 0.00035 U	< 0.0019 U	< 0.00038 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	0.012 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.28 U	< 0.1 U	< 0.22 U	< 0.17 U	< 0.18 U	< 0.17 U	< 0.29 U	< 0.15 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.005 U	< 0.0018 U	< 0.0038 U	< 0.003 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.003 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0034 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.019 U	< 0.00064 U	< 0.0011 U	< 0.0014 U	< 0.0022 U	< 0.0038 U	< 0.0011 U	< 0.003 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.024 U	< 0.00079 U	< 0.0014 U	< 0.0017 U	< 0.0027 U	< 0.0047 U	< 0.0013 U	< 0.0037 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.0054 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	0.0078	< 0.00021 U	< 0.00023 U	< 0.00021 U	< 0.00034 U	< 0.00080 U	0.00032 JT	< 0.00031 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 UT	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0048 U	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0052 U	< 0.0026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0038 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	40 J	< 5.3 U	< 11 U	< 8.7 U	< 9.4 U	< 8.5 U	< 15 U	< 7.6 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.0014 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0023 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0023 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0042 U	< 0.0021 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3914	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.0030 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.00051 U	< 0.00049 U	< 0.00087 U	< 0.00024 U	< 0.00023 U	< 0.00054 U	< 0.0019 U	< 0.0018 U
Northern Athletic Field	SSHS-B3646A	0918221 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.00063 U	< 0.00061 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00067 U	< 0.034 U	0.011
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.00081 U	< 0.0016 U	< 0.0018 U	< 0.001 U	< 0.0012 U	< 0.0015 U	< 0.002 U	< 0.0028 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.00074 U	< 0.0023 U	< 0.0022 U	< 0.00064 U	< 0.0019 U	< 0.0011 U	< 0.0029 U	< 0.0098 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.00082 U	< 0.0025 U	< 0.0024 U	< 0.0007 U	< 0.002 U	< 0.0012 U	< 0.0032 U	< 0.011 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.00022 U	< 0.00024 U	< 0.00066 U	< 0.0012 U	< 0.00055 U	0.00056 J	< 0.00058 U	< 0.0014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.00015 U	< 0.00016 U	< 0.00043 U	< 0.00080 U	< 0.00036 U	0.0016	< 0.00038 U	< 0.00094 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.087 U	< 0.17 U	< 0.2 U	< 0.11 U	< 0.13 U	0.71	< 0.22 U	< 0.3 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 U	< 0.0017 U	< 0.0020 U	< 0.0025 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0040 U	< 0.0056 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	0.0056
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.00056 U	< 0.00054 U	< 0.00096 U	0.00043 J	< 0.00026 U	< 0.00059 U	< 0.0021 U	< 0.0019 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.00073 U	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00078 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0048 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0012 U	< 0.0024 U	< 0.0028 U	< 0.0015 U	< 0.0019 U	< 0.0023 U	< 0.0031 U	< 0.0043 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.00092 U	< 0.0028 U	< 0.0028 U	< 0.00079 U	< 0.0023 U	< 0.0014 U	< 0.0036 U	< 0.012 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.00068 U	< 0.0021 U	< 0.002 U	< 0.00059 U	< 0.0017 U	< 0.001 U	< 0.0027 U	< 0.0089 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00047 U	< 0.00088 U	< 0.00039 U	0.00040 J	< 0.00042 U	< 0.0010 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00017 U	< 0.00046 U	< 0.00085 U	< 0.00038 U	0.00039 J	< 0.00040 U	< 0.0010 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0051 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	0.0069
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 84 U	< 160 U	< 190 U	< 100 U	< 130 U	< 160 U	< 210 U	< 290 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.00051 U	< 0.0005 U	< 0.00088 U	0.00043 J	< 0.00023 U	< 0.00054 U	< 0.0019 U	< 0.0018 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.00058 U	< 0.00057 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.095 U	< 0.18 U	< 0.21 U	< 0.12 U	< 0.14 U	< 0.18 U	< 0.24 U	< 0.33 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0023 U	< 0.0027 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.00084 U	< 0.0025 U	< 0.0025 U	< 0.00072 U	< 0.0021 U	< 0.0013 U	< 0.0033 U	< 0.011 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0032 U	< 0.0031 U	< 0.00089 U	< 0.0026 U	< 0.0016 U	< 0.0041 U	< 0.014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00092 U	< 0.00041 U	0.00023 J	< 0.00043 U	< 0.0011 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.00014 U	< 0.00016 U	< 0.00042 U	< 0.00078 U	< 0.00035 U	0.00060 J	< 0.00037 U	< 0.00092 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0029 U	< 0.0040 U	< 0.0056 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.0020 U	< 0.0024 U	< 0.0030 U	< 0.0040 UT	< 0.0056 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U	< 0.0058 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U	< 0.0058 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0037 U	< 0.0021 U	< 0.0025 U	< 0.0031 U	< 0.0041 U	< 0.0058 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0050 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 4.9 U	< 9.3 U	< 11 U	< 6 U	< 7.4 U	< 9 U	< 12 U	< 17 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.003 U	< 0.0016 U	< 0.002 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.0006 U	< 0.00058 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.005 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethene	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.00049 U	< 0.00032 U	< 0.0003 U	< 0.0002 U	< 0.00054 U	< 0.00047 U	< 0.00019 U	< 0.00047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.00062 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00024 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00_SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B4261	102621 10:00_SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B4262	102621 10:00_SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.00086 U	< 0.0016 U	< 0.0011 U	< 0.0019 U	< 0.00094 U	< 0.001 U	< 0.0009 U	< 0.0014 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.00063 U	< 0.00077 U	< 0.0009 U	< 0.00066 U	< 0.00072 U	< 0.00056 U	< 0.00063 U	< 0.0015 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.00069 U	< 0.00084 U	< 0.00099 U	< 0.00073 U	< 0.00079 U	< 0.00062 U	< 0.00069 U	< 0.0016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.00023 U	< 0.00043 U	< 0.00046 U	< 0.00046 U	< 0.00028 U	< 0.00026 U	< 0.00037 U	< 0.00028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.00015 U	< 0.00028 U	< 0.00030 U	< 0.00030 U	< 0.00018 U	< 0.00017 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.092 U	< 0.17 U	0.52	< 0.21 U	0.14 J	< 0.11 U	< 0.096 U	< 0.15 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0015 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.00054 U	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00059 U	< 0.00052 U	< 0.00021 U	< 0.00052 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.00071 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00078 U	< 0.034 U	< 0.00028 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00_SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B4261	102621 10:00_SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.0029 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0021 U
Northern Athletic Field	SSHS-B4262	102621 10:00_SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.00077 U	< 0.00095 U	< 0.0011 U	< 0.00082 U	< 0.00089 U	< 0.0007 U	< 0.00078 U	< 0.0018 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.00057 U	< 0.00087 U	< 0.0007 U	< 0.00083 U	< 0.00061 U	< 0.00066 U	< 0.00052 U	< 0.00058 U	< 0.0014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00020 U	< 0.00019 U	< 0.00027 U	< 0.00020 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00030 U	< 0.00032 U	< 0.00032 U	< 0.00020 U	< 0.00018 U	< 0.00026 U	< 0.00020 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 89 U	< 160 U	< 110 U	< 200 U	< 97 U	< 100 U	< 93 U	< 150 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.0005 U	< 0.00032 U	< 0.0003 U	< 0.0002 U	< 0.00054 U	< 0.00047 U	< 0.00019 U	< 0.00047 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.00057 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00062 U	< 0.034 U	< 0.00022 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00_SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.1 U	< 0.18 U	< 0.12 U	< 0.22 U	< 0.11 U	< 0.12 U	< 0.11 U	< 0.17 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B4261	102621 10:00_SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.002 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B4262	102621 10:00_SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0026 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.0007 U	< 0.00086 U	< 001 U	< 0.00075 U	< 0.00081 U	< 0.00063 U	< 0.00071 U	< 0.0017 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.00087 U	< 0.0011 U	< 0.0013 U	< 0.00092 U	< 0.001 U	< 0.00079 U	< 0.00087 U	< 0.0021 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.00014 U	< 0.00027 U	< 0.00029 U	< 0.00029 U	< 0.00018 U	< 0.00017 U	< 0.00024 U	< 0.00018 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 5.1 U	< 9.3 U	< 6.3 U	< 12 U	< 5.6 U	< 6 U	< 5.4 U	< 8.4 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0032 U	< 0.0015 U	< 0.0016 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.00058 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.00023 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00_SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U

												1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.25	0.19				1	
Restricted - Residential													100	100				41	
Protection of Groundwater													0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.00049 U	< 0.0004 U	< 0.0019 U	< 0.00055 U	< 0.0017 U	< 0.00027 U	< 0.00088 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00061 U	< 0.00049 U	< 0.034 U	< 0.00069 U	< 0.0021 U	< 0.00033 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.0026 U	< 0.00094 U	< 0.0011 U	< 0.00083 U	< 0.0014 U	< 0.0014 U	< 0.0012 U	< 0.0013 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.00091 U	< 0.0012 U	< 0.0012 U	< 0.00069 U	< 0.0023 U	< 0.003 U	< 0.00085 U	< 0.001 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0013 U	< 0.0013 U	< 0.00076 U	< 0.0026 U	< 0.0033 U	< 0.00093 U	0.0051
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.00048 U	< 0.00045 U	< 0.00031 U	< 0.00053 U	< 0.00034 U	< 0.00034 U	< 0.00025 U	< 0.00038 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00035 U	< 0.00022 U	< 0.00022 U	< 0.00016 U	< 0.00025 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.27 U	< 0.1 U	< 0.12 U	< 0.089 U	< 0.15 U	< 0.15 U	1	40
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.0022 U	< 0.00054 U	< 0.00044 U	< 0.0021 U	< 0.00061 U	< 0.0019 U	< 0.00029 U	< 0.00096 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00071 U	< 0.00057 U	< 0.034 U	< 0.0008 U	< 0.0024 U	< 0.00038 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0021 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 UJ	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0015 U	< 0.0014 U	< 0.00086 U	< 0.0029 U	< 0.0037 U	< 0.0011 U	< 0.0013 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.00084 U	< 0.0011 U	< 0.0011 U	< 0.00063 U	< 0.0021 U	< 0.0028 U	< 0.00078 U	0.011
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.00035 U	< 0.00032 U	< 0.00022 U	< 0.00038 U	< 0.00025 U	< 0.00024 U	< 0.00018 U	< 0.00027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.00034 U	< 0.00031 U	< 0.00022 U	< 0.00037 U	< 0.00024 U	< 0.00023 U	< 0.00017 U	< 0.00026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0025 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0020 U	< 0.0021 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 260 U	< 98 U	< 110 U	< 86 U	< 140 U	< 150 U	< 120 U	< 130 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0005 U	< 0.0004 U	< 0.0019 U	< 0.00056 U	< 0.0017 U	< 0.00027 U	< 0.00088 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00057 U	< 0.00046 U	< 0.034 U	< 0.00064 U	< 0.0019 U	< 0.00031 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.3 U	< 0.11 U	< 0.13 U	< 0.097 U	< 0.16 U	< 0.17 U	< 0.14 U	< 0.15 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	0.0039 J
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0014 U	< 0.0013 U	< 0.00078 U	< 0.0026 U	< 0.0034 U	< 0.00096 U	< 0.0012 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.0017 U	< 0.0016 U	< 0.00096 U	< 0.0033 U	< 0.0042 U	< 0.0012 U	< 0.0015 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U	0.0011
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.00031 U	< 0.00029 U	< 0.00020 U	< 0.00034 U	< 0.00022 U	< 0.00021 U	< 0.00016 U	< 0.00024 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0050 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0050 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.0020 U	< 0.0022 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 15 U	< 5.6 U	< 6.5 U	< 5 U	< 8.3 U	< 8.4 U	< 6.9 U	< 7.5 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.002 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00058 U	< 0.00047 U	< 0.034 U	< 0.00065 U	< 0.002 U	< 0.00031 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	0.0035 J

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.00058 U	< 0.0023 U	< 0.00058 U	< 0.0014 U	< 0.0013 U	< 0.00038 U	< 0.00019 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00073 U	< 0.034 U	< 0.0016 U	< 0.00047 U	< 0.00024 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.00098 U	< 0.0016 U	< 0.0046 U	< 0.0015 U	< 0.0016 U	< 0.0011 U	< 0.00092 U	< 0.00094 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.0033 U	< 0.0016 U	< 0.0028 U	0.0012 J	< 0.0029 U	< 0.003 U	< 0.0016 U	< 0.00094 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.0036 U	< 0.0017 U	< 0.003 U	< 0.0011 U	< 0.0032 U	< 0.0033 U	< 0.0018 U	< 0.001 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.0022 U	< 0.00036 U	< 0.0054 U	0.0012 J	< 0.00046 U	< 0.0020 U	< 0.00065 U	< 0.00035 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.0035 U	0.0033	< 0.00030 U	< 0.0013 U	< 0.00042 U	< 0.00023 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.11 U	3.1	< 0.49 U	24	< 0.17 U	< 0.12 UT	< 0.098 UT	< 0.1 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0026 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0032 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.0021 U	< 0.00064 U	< 0.0026 U	< 0.00064 U	< 0.0015 U	< 0.0014 U	< 0.00042 U	< 0.00021 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.0018 U	< 0.00054 U	< 0.00028 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.007 U	< 0.0023 U	< 0.0024 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0086 U	< 0.0028 U	< 0.003 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.0041 U	< 0.0019 U	< 0.0034 U	< 0.0012 U	< 0.0036 U	< 0.0037 U	< 0.002 U	< 0.0012 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.003 U	< 0.0014 U	< 0.0025 U	< 0.00091 U	< 0.0027 U	< 0.0028 U	< 0.0015 U	< 0.00086 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.0039 U	0.00066 J	< 0.00033 U	< 0.0014 U	< 0.00046 U	< 0.00025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.0015 U	< 0.00025 U	< 0.0038 U	0.00069 J	< 0.00032 U	< 0.0014 U	< 0.00045 U	< 0.00024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0084 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0078 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 100 U	< 170 U	< 480 U	< 160 U	< 160 U	< 120 U	< 95 U	< 97 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.00058 U	< 0.0023 U	0.0008 J	< 0.0014 U	< 0.0013 U	< 0.00038 U	< 0.00019 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00067 U	< 0.034 U	< 0.0015 U	< 0.00043 U	< 0.00022 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.11 U	< 0.19 U	< 0.54 U	< 0.18 U	< 0.19 U	< 0.13 U	< 0.11 U	< 0.11 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0031 U	< 0.0087 U	< 0.0028 U	< 0.003 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0084 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.0037 U	< 0.0018 U	< 0.0031 U	< 0.0011 U	< 0.0033 U	< 0.0034 U	< 0.0018 U	< 0.0011 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.0046 U	< 0.0022 U	< 0.0039 U	< 0.0014 U	< 0.004 U	< 0.0042 U	< 0.0022 U	< 0.0013 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00047 U	< 0.00035 U	< 0.0015 U	< 0.00048 U	< 0.00026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.0014 U	< 0.00023 U	< 0.0035 U	0.0012	< 0.00030 U	< 0.0013 U	< 0.00041 U	< 0.00022 U
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.0030 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0094 U	< 0.0031 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0080 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0026 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 5.9 U	< 9.7 U	< 27 U	< 9 U	< 9.5 U	< 6.8 U	< 5.5 U	< 5.6 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0075 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0015 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U	< 0.0015 U	< 0.00044 U	< 0.00023 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													1,1,2,2-Tetrachloroethane	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**	**1,1,2-Trichloroethane**	**Trichloroethene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68		0.47
Restricted - Residential														19	100			100		21
Protection of Groundwater														1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.00062 U	< 0.00052 U	< 0.00029 U	< 0.00041 U	< 0.00023 U	< 0.00028 U	< 0.0005 U	< 0.00085 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00064 U	0.0017 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.003 U	< 0.002 U	< 0.0012 U	0.0059
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	0.0019 J
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0012 U	0.0051 J
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.00095 U	< 0.0013 U	< 0.0009 U	< 0.0017 U	< 0.0016 U	< 0.001 U	< 0.00062 U	< 0.00098 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.0012 U	0.00098 J	0.00074 J	< 0.0024 U	< 0.002 U	< 0.0014 U	< 0.00092 U	0.0019 J
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.0013 U	0.0077	< 0.00069 U	< 0.0026 U	< 0.0022 U	< 0.0016 U	< 0.001 U	0.025
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.00027 U	0.00079 J	0.00055 J	< 0.00023 U	< 0.00045 U	< 0.00029 U	< 0.00022 U	0.00073 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.00018 U	0.00053 J	0.0017	< 0.00015 U	< 0.00029 U	< 0.00019 U	< 0.00015 U	0.00040 J
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.1 U	40	2	< 0.18 U	0.99	< 0.11 U	< 0.066 U	25
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0020 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.00069 U	< 0.00057 U	< 0.00032 U	< 0.00045 U	< 0.00026 U	< 0.00031 U	< 0.00055 U	< 0.00093 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00074 U	< 0.00042 U	< 0.034 U	< 0.00034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	< 0.0017 UJ
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0014 U	< 0.0019 U	< 0.0014 U	< 0.0026 U	< 0.0024 U	< 0.0016 U	< 0.00094 U	< 0.0015 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.0014 U	< 0.00073 U	< 0.00078 U	< 0.003 U	< 0.0025 U	< 0.0018 U	< 0.0011 U	0.00068 J
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.0011 U	0.0098	< 0.00058 U	< 0.0022 U	< 0.0019 U	< 0.0013 U	< 0.00084 U	0.041
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.00019 U	0.00053 J	0.00032 J	< 0.00016 U	< 0.00032 U	< 0.00021 U	< 0.00016 U	0.00035 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.00019 U	0.00051 J	0.00043 J	< 0.00016 U	< 0.00031 U	< 0.00020 U	< 0.00016 U	0.00031 J
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0017 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 99 U	< 130 U	< 93 U	< 180 U	< 160 U	< 110 U	< 64 U	170 J
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.00063 U	0.00073 J	0.00053 J	< 0.00041 U	< 0.00024 U	< 0.00028 U	< 0.0005 U	< 0.00085 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00059 U	< 0.00033 U	< 0.034 U	< 0.00027 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.11 U	0.36 J	0.12 J	< 0.2 U	< 0.19 U	< 0.12 U	< 0.072 U	2.5
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.0019 U	0.0026 J	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	0.096
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.003 U	< 0.002 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	0.004 J
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.00067 U	< 0.00071 U	< 0.0027 U	< 0.0023 U	< 0.0016 U	< 0.001 U	< 0.00058 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.0016 U	< 0.00083 U	< 0.00088 U	< 0.0033 U	< 0.0028 U	< 0.002 U	< 0.0013 U	< 0.00072 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.00020 U	0.0012	0.00024 J	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	0.0035
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.00017 U	0.00044 J	0.00049 J	< 0.00015 U	< 0.00029 U	< 0.00019 U	< 0.00014 U	0.00030 J
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 U	< 0.0021 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U	< 0.0022 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0019 U	< 0.0026 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0030 U	< 0.0028 U	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0017 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 5.7 U	< 7.5 U	19	< 10 U	< 9.5 U	< 6.2 U	< 3.7 U	130
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 UJ	< 0.0017 U	< 0.001 U	< 0.0016 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00061 U	< 0.00034 U	< 0.034 U	< 0.00027 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.001 U	0.087

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B3891	DUP-11-20210513	DUP-11	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22-20210513	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22-20210514	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.0047 U	< 0.0040 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22-20210517	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3883	DUP-43-20210519	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22-20210519	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-20-22	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated	< 0.00036 U	< 0.00047 U	< 0.00065 U	< 0.0005 U	< 0.00065 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-20-22	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00081 U	< 0.034 U	< 0.00081 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-20-22	SSHS-B3920A-SUB-20-22	10/25/2021	853.31	854.91	1.60	-	20 - 22 ft	21.6-23.6 ft	180-128986-1	Not Excavated	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-20-22	SSHS-B4260-SUB-20-22	10/25/2021	852.55	853.09	0.54	-	20 - 22 ft	20.54-22.54 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-20-22	SSHS-B4261-SUB-20-22	10/25/2021	854.31	857.88	3.57	-	20 - 22 ft	23.57-25.57 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-20-22	SSHS-B4262-SUB-20-22	10/25/2021	853.70	857.40	3.70	-	20 - 22 ft	23.7-25.7 ft	180-128986-1	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-20-22	SSHS-B4265-SUB-20-22	10/26/2021	854.78	855.87	1.09	-	20 - 22 ft	21.09-23.09 ft	180-129052-1	Not Excavated	< 0.0026 U	< 0.0023 U	< 0.0011 U	< 0.0013 U	< 0.0045 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-20-22	SSHS-B4263-SUB-20-22	11/1/2021	854.60	858.21	3.61	-	20 - 22 ft	23.61-25.61 ft	180-129325-1	Not Excavated	< 0.0022 U	< 0.0014 U	< 0.00064 U	< 0.0007 U	< 0.0013 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-20-22	SSHS-B4264-SUB-20-22	11/1/2021	852.29	853.31	1.02	-	20 - 22 ft	21.02-23.02 ft	180-129325-1	Not Excavated	< 0.0024 U	< 0.0016 U	< 0.0007 U	< 0.00077 U	< 0.0014 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22-20230119	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated	< 0.00051 U	< 0.00069 U	0.00039 J	< 0.00024 U	0.00039 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22-20230119	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated	< 0.00033 U	< 0.00045 U	0.0011	0.00020 J	0.0013 J
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-22-24-20210122	SSHS-B3454-SUB-22-24	1/22/2021	853.65	857.32	3.67	-	22 - 24 ft	25.67-27.67 ft	1801163651	Not Excavated	< 0.28 U	< 0.24 U	4.8	4	8.8
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24-20210401	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0077 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24-20210506	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24-20210506	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24-20210510	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24-20210512	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0083 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24-20210513	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24-20210514	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24-20210517	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0090 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24-20210519	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-22-24	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated	< 0.0004 U	< 0.00052 U	< 0.00071 U	< 0.00055 U	< 0.00071 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-22-24	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00093 U	< 0.034 U	< 0.00093 U
Northern Athletic Field	SSHS-B3920A	102621 10:00 SSHS-B3920A-SUB-22-24	SSHS-B3920A-SUB-22-24	10/25/2021	853.31	854.91	1.60	-	22 - 24 ft	23.6-25.6 ft	180-128986-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-22-24	SSHS-B4260-SUB-22-24	10/25/2021	852.55	853.09	0.54	-	22 - 24 ft	22.54-24.54 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-22-24	SSHS-B4261-SUB-22-24	10/25/2021	854.31	857.88	3.57	-	22 - 24 ft	25.57-27.57 ft	180-128986-1	Not Excavated	< 0.0039 U	< 0.0034 U	< 0.0017 U	< 0.0019 U	< 0.0069 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-22-24	SSHS-B4262-SUB-22-24	10/25/2021	853.70	857.40	3.70	-	22 - 24 ft	25.7-27.7 ft	180-128986-1	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0084 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-22-24	SSHS-B4265-SUB-22-24	10/26/2021	854.78	855.87	1.09	-	22 - 24 ft	23.09-25.09 ft	180-129052-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-22-24	SSHS-B4263-SUB-22-24	11/1/2021	854.60	858.21	3.61	-	22 - 24 ft	25.61-27.61 ft	180-129325-1	Not Excavated	< 0.0027 U	< 0.0018 U	< 0.00079 U	< 0.00087 U	< 0.0016 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-22-24	SSHS-B4264-SUB-22-24	11/1/2021	852.29	853.31	1.02	-	22 - 24 ft	23.02-25.02 ft	180-129325-1	Not Excavated	< 0.002 U	< 0.0013 U	< 0.00058 U	< 0.00064 U	< 0.0012 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24-20230119	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated	< 0.00037 U	< 0.00050 U	0.00023 J	< 0.00018 U	0.00023 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24-20230119	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated	< 0.00036 U	< 0.00048 U	0.00027 J	< 0.00017 U	0.00027 J
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5-20210401	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25-20210510	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26-20210506	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26-20210506	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26-20210512	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26-20210513	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26-20210514	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0081 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26-20210517	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26-20210519	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-24-26	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated	< 270 U	< 230 U	< 120 U	< 130 U	< 470 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-24-26	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated	< 0.00037 U	< 0.00047 U	< 0.00065 U	< 0.00051 U	< 0.00065 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-24-26	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00074 U	< 0.034 U	< 0.00074 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-24-26	SSHS-B3454A-SUB-24-26	10/25/2021	853.65	857.32	3.67	-	24 - 26 ft	27.67-29.67 ft	180-128986-1	Not Excavated	< 0.3 U	< 0.26 U	< 0.13 U	< 0.15 U	< 0.53 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-24-26	SSHS-B4260-SUB-24-26	10/25/2021	852.55	853.09	0.54	-	24 - 26 ft	24.54-26.54 ft	180-128986-1	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B4261	102621 10:00 SSHS-B4261-SUB-24-26	SSHS-B4261-SUB-24-26	10/25/2021	854.31	857.88	3.57	-	24 - 26 ft	27.57-29.57 ft	180-128986-1	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B4262	102621 10:00 SSHS-B4262-SUB-24-26	SSHS-B4262-SUB-24-26	10/25/2021	853.70	857.40	3.70	-	24 - 26 ft	27.7-29.7 ft	180-128986-1	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0082 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-24-26	SSHS-B4265-SUB-24-26	10/26/2021	854.78	855.87	1.09	-	24 - 26 ft	25.09-27.09 ft	180-129052-1	Not Excavated	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-24-26	SSHS-B4263-SUB-24-26	11/1/2021	854.60	858.21	3.61	-	24 - 26 ft	27.61-29.61 ft	180-129325-1	Not Excavated	< 0.0025 U	< 0.0016 U	< 0.00072 U	< 0.00079 U	< 0.0015 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-24-26	SSHS-B4264-SUB-24-26	11/1/2021	852.29	853.31	1.02	-	24 - 26 ft	25.02-27.02 ft	180-129325-1	Not Excavated	< 0.003 U	< 0.002 U	< 0.00089 U	< 0.00098 U	< 0.0018 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26-20230119	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated	< 0.00038 U	< 0.00051 U	0.00016 J	< 0.00018 U	0.00016 J
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26-20230119	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated	< 0.00033 U	< 0.00044 U	0.00047 J	< 0.00016 U	0.00047 J
Northern Athletic Field	SSHS-B3867	DUP-22-20210401	DUP-22	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26-20210401	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27-20210510	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.0051 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28-20210401	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28-20210506	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28-20210506	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28-20210512	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0092 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28-20210513	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28-20210514	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28-20210519	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.0043 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-26-28	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated	< 16 U	< 13 U	< 6.6 U	< 7.5 U	< 27 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-26-28	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0074 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-26-28	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.00076 U
Northern Athletic Field	SSHS-B3454A	102621 10:00 SSHS-B3454A-SUB-26-28	SSHS-B3454A-SUB-26-28	10/25/2021	853.65	857.32	3.67	-	26 - 28 ft	29.67-31.67 ft	180-128986-1	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.008 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-26-28	SSHS-B4260-SUB-26-28	10/25/2021	852.55	853.09	0.54	-	26 - 28 ft	26.54-28.54 ft	180-128986-1	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Acetone	Benzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon Tetrachloride
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted													0.05	0.06						0.76
Restricted - Residential													100	4.8						2.4
Protection of Groundwater													0.05	0.06						0.76
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B4261	102721 09:30 SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0081 U	< 0.0029 U	< 0.0062 U	< 0.0048 U	< 0.0052 U	< 0.0047 U	< 0.0083 U	< 0.0042 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.02 U	< 0.00066 U	< 0.0012 U	< 0.0014 U	< 0.0023 U	< 0.0039 U	< 0.0011 U	< 0.0031 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	0.022	< 0.00062 UJ	< 0.0011 U	< 0.0013 UJ	< 0.0021 U	< 0.0037 U	< 0.001 U	< 0.0029 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00026 UT	< 0.00037 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	0.01	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00040 U	< 0.00094 U	< 0.00025 UT	< 0.00036 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0050 U	< 0.0018 U	< 0.0039 U	< 0.0030 U	< 0.0032 U	< 0.0029 U	< 0.0052 UT	< 0.0026 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0042 U	< 0.0021 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0040 U	< 0.0031 U	< 0.0034 U	< 0.0031 U	< 0.0054 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.0035 U	< 0.0027 U	< 0.0030 U	< 0.0027 U	< 0.0047 U	< 0.0024 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0035 U	< 0.0027 U	< 0.0029 U	< 0.0026 U	< 0.0046 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0032 U	< 0.0025 U	< 0.0027 U	< 0.0024 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	0.0088 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.004 U	< 0.0031 U	< 0.0034 U	< 0.003 U	< 0.0053 U	< 0.0027 U
Northern Athletic Field	SSHS-B4261	102721 09:30 SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0029 U	< 0.0023 U	< 0.0024 U	< 0.0022 U	< 0.0039 U	< 0.002 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0028 U	< 0.0021 U	< 0.0023 U	< 0.0021 U	< 0.0037 U	< 0.0019 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.0052 U	< 0.00024 U	< 0.00026 U	< 0.00024 U	< 0.00039 U	< 0.00091 U	< 0.00024 UT	< 0.00035 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0050 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0030 U	< 0.0027 U	< 0.0048 U	< 0.0024 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3646A	092421 10:00 SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4265	102821 10:00 SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0026 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.0055 U	< 0.00025 U	< 0.00027 U	< 0.00025 U	< 0.00041 U	< 0.00096 U	< 0.00025 UT	< 0.00037 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.0051 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.24 U	< 0.088 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.14 U	< 0.25 UJ	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0034 U	< 0.0012 U	< 0.0026 U	< 0.0021 U	< 0.0022 U	< 0.002 U	< 0.0035 U	< 0.0018 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	0.0072 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.09 U	< 0.19 U	< 0.15 U	< 0.16 U	< 0.15 U	< 0.25 UJ	< 0.13 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	0.0088 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0043 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.36 U	< 0.13 U	< 0.28 U	< 0.22 U	< 0.23 U	< 0.21 U	< 0.37 UJ	< 0.19 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0043 U	< 0.0015 U	< 0.0033 U	< 0.0025 U	< 0.0027 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0033 U	< 0.0026 U	< 0.0028 U	< 0.0025 U	< 0.0044 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	0.018 J	< 0.0017 U	< 0.0037 U	< 0.0029 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.004 U	< 0.0015 U	< 0.0031 U	< 0.0024 U	< 0.0026 U	< 0.0024 U	< 0.0041 U	< 0.0021 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0034 U	< 0.0026 U	< 0.0028 U	< 0.0026 U	< 0.0045 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0036 U	< 0.0028 U	< 0.0031 U	< 0.0028 U	< 0.0049 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0038 U	< 0.0029 U	< 0.0032 U	< 0.0029 U	< 0.005 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0040 UJ	< 0.0014 U	< 0.0030 U	< 0.0024 U	< 0.0026 U	< 0.0023 UJ	< 0.0041 U	< 0.0021 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0039 U	< 0.0014 U	< 0.0030 U	< 0.0023 U	< 0.0025 U	< 0.0023 U	< 0.0040 U	< 0.0020 UT
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	0.035 J+	0.0016 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.02 J+	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	0.014 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	0.0087 J	0.00029 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U

												Chlorobenzene	Chlorodibromomethane	Chloroethane	Chloroform	Chloromethane	Cyclohexane	1,2-Dibromo-3-Chloropropane	Dichloromethane
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted												1.1			0.37				0.05
Restricted - Residential												100			49				100
Protection of Groundwater												1.1			0.37				0.05
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[2] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0055 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0027 U	< 0.0052 U	< 0.0061 U	< 0.0033 U	< 0.0041 U	< 0.005 U	< 0.0067 U	< 0.0094 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.00086 U	< 0.0026 U	< 0.0026 U	< 0.00074 U	< 0.0021 U	< 0.0013 U	< 0.0034 U	< 0.011 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	< 0.00082 UJ	< 0.0025 U	< 0.0025 U	< 0.00071 U	< 0.002 U	< 0.0012 U	< 0.0032 U	< 0.011 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U	< 0.0011 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00018 U	< 0.00049 U	< 0.00091 U	< 0.00041 U	0.00062 J	< 0.00043 U	0.0011 J
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0017 U	< 0.0032 U	< 0.0038 U	< 0.0021 U	< 0.0026 U	< 0.0031 U	< 0.0042 U	< 0.0058 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0014 U	< 0.0028 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0050 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0025 U	< 0.0034 U	< 0.0047 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0033 U	< 0.0039 U	< 0.0022 U	< 0.0027 U	< 0.0032 U	< 0.0043 U	< 0.0061 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0028 U	< 0.0038 U	0.0059
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 UT	< 0.0028 U	< 0.0038 U	< 0.0053 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0015 U	< 0.0029 U	< 0.0034 U	< 0.0019 U	< 0.0023 U	< 0.0028 U	< 0.0037 U	< 0.0052 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0031 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0048 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.00087 U	< 0.00084 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00092 U	< 0.034 U	0.0034 J
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.0017 U	< 0.0033 U	< 0.0039 U	< 0.0021 U	< 0.0026 U	< 0.0032 U	< 0.0043 U	< 0.006 U
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0028 U	< 0.0016 U	< 0.0019 U	< 0.0023 U	< 0.0031 U	< 0.0044 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0012 U	< 0.0023 U	< 0.0027 U	< 0.0015 U	< 0.0018 U	< 0.0022 U	< 0.003 U	< 0.0041 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00018 U	< 0.00048 U	< 0.00089 U	< 0.00040 U	< 0.00020 U	< 0.00042 U	0.0011 J
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0035 U	< 0.0019 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0054 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3646A	092421 10:00_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4265	102821 10:00_SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00019 U	< 0.00050 U	< 0.00093 U	< 0.00042 U	< 0.00021 U	< 0.00044 U	< 0.0011 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.0020 U	< 0.0025 U	< 0.0030 U	< 0.0041 U	< 0.0057 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.081 U	< 0.15 U	< 0.18 U	< 0.1 U	< 0.12 U	< 0.15 U	< 0.2 U	< 0.28 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.00066 U	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U	0.0024 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0011 U	< 0.0022 U	< 0.0026 U	< 0.0014 U	< 0.0017 U	< 0.0021 U	< 0.0029 U	< 0.004 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.00061 U	< 0.00059 U	< 0.034 U	0.00031 J	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.083 U	< 0.16 U	< 0.19 U	< 0.1 U	< 0.13 U	< 0.15 U	< 0.21 U	< 0.29 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.00059 U	< 0.00057 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	0.0039 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0017 U	< 0.0021 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.00065 U	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.12 U	< 0.23 U	< 0.27 U	< 0.15 U	< 0.18 U	< 0.22 U	< 0.3 U	< 0.42 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0035 U	< 0.0049 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0027 U	< 0.0032 U	< 0.0018 U	< 0.0022 U	< 0.0026 U	< 0.0036 U	< 0.005 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0036 U	< 0.002 U	< 0.0024 U	< 0.003 U	< 0.004 U	< 0.0056 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.0013 U	< 0.0026 U	< 0.003 U	< 0.0017 U	< 0.002 U	< 0.0025 U	< 0.0033 U	< 0.0047 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0033 U	< 0.0018 U	< 0.0022 U	< 0.0027 U	< 0.0036 U	< 0.0051 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.003 U	< 0.0035 U	< 0.002 U	< 0.0024 U	< 0.0029 U	< 0.0039 U	< 0.0055 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0031 U	< 0.0037 U	< 0.002 U	< 0.0025 U	< 0.003 U	< 0.004 U	< 0.0057 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0030 UJ	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0033 U	< 0.0046 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0013 U	< 0.0025 U	< 0.0029 U	< 0.0016 U	< 0.0020 U	< 0.0024 U	< 0.0032 U	< 0.0045 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.0022 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.00089 U	< 0.0027 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0013 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.00044 U	< 0.00042 U	< 0.034 U	0.0007 J	< 0.034 U	< 0.00046 U	< 0.034 U	< 0.034 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

												1,2-Dibromoethane	Dichlorodifluoromethane	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1-Dichloroethane	1,2-Dichloroethane	1,1-Dichloroethene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.1	2.4	1.8	0.27	0.02	0.33
Restricted - Residential														100	49	13	26	3.1	100
Protection of Groundwater														1.1	2.4	1.8	0.27	0.02	0.33
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]							
Northern Athletic Field	SSHS-B4261	102721 09:30 SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0028 U	< 0.0052 U	< 0.0035 U	< 0.0064 U	< 0.0031 U	< 0.0033 U	< 0.003 U	< 0.0047 U
Northern Athletic Field	SSHS-B4263	110221 10:20 SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.00072 U	< 0.00089 U	< 0.001 U	< 0.00077 U	< 0.00083 U	< 0.00065 U	< 0.00073 U	< 0.0017 U
Northern Athletic Field	SSHS-B4264	110221 10:20 SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	< 0.00069 UJ	< 0.00084 U	< 0.001 UJ	< 0.00073 UJ	< 0.00079 UJ	< 0.00062 U	< 0.00069 UJ	< 0.0016 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00035 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U	< 0.00022 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00034 U	< 0.00021 U	< 0.00019 U	< 0.00028 U	< 0.00021 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0018 U	< 0.0032 U	< 0.0022 U	< 0.0040 U	< 0.0019 U	< 0.0021 U	< 0.0019 U	< 0.0029 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0034 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0018 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0018 U	< 0.0034 U	< 0.0023 U	< 0.0041 U	< 0.0020 U	< 0.0022 U	< 0.0019 U	< 0.0030 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0020 U	< 0.0036 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0016 U	< 0.0029 U	< 0.0019 U	< 0.0036 U	< 0.0017 U	0.013	< 0.0017 U	< 0.0026 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0024 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.00085 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00092 U	< 0.034 U	< 0.00033 U	< 0.034 U
Northern Athletic Field	SSHS-B4260	102621 10:00 SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.0018 U	< 0.0033 U	< 0.0022 U	< 0.0041 U	< 0.002 U	< 0.0021 U	< 0.0019 U	< 0.003 U
Northern Athletic Field	SSHS-B4261	102721 09:30 SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.0013 U	< 0.0024 U	< 0.0016 U	< 0.003 U	< 0.0014 U	< 0.0015 U	< 0.0014 U	< 0.0022 U
Northern Athletic Field	SSHS-B4265	102721 09:30 SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0013 U	< 0.0023 U	< 0.0015 U	< 0.0028 U	< 0.0014 U	< 0.0015 U	< 0.0013 U	< 0.0021 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.00016 U	< 0.00031 U	< 0.00033 U	< 0.00033 U	< 0.00021 U	< 0.00019 U	< 0.00027 U	< 0.00021 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0030 U	< 0.0020 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3920	070221 09:00 SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	092421 10:00 SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.0017 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0019 U	< 0.034 U	< 0.0018 U	< 0.034 U
Northern Athletic Field	SSHS-B4265	102821 10:00 SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.00017 U	< 0.00032 U	< 0.00034 U	< 0.00035 U	< 0.00022 U	< 0.00020 U	< 0.00028 U	< 0.00022 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.0020 U	< 0.0018 U	< 0.0029 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.085 U	< 0.16 U	< 0.1 U	< 0.19 U	< 0.093 U	< 0.1 U	< 0.09 U	< 0.14 UJ
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.00064 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0007 U	< 0.034 U	< 0.00025 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0012 U	< 0.0022 U	< 0.0015 U	< 0.0027 U	< 0.0013 U	< 0.0014 U	< 0.0013 U	< 0.002 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.00059 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00064 U	< 0.034 U	< 0.00023 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.087 U	< 0.16 U	< 0.11 U	< 0.2 U	< 0.095 U	< 0.1 U	< 0.092 U	< 0.14 UJ
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.00058 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00063 U	< 0.034 U	< 0.00023 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0033 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3646A	091821 10:15 SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.00063 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00069 U	< 0.034 U	< 0.00025 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.13 U	< 0.23 U	< 0.16 U	< 0.29 U	< 0.14 U	< 0.15 U	< 0.13 U	< 0.21 UJ
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0017 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0027 U	< 0.0018 U	< 0.0034 U	< 0.0016 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0038 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0026 U	< 0.0017 U	< 0.0032 U	< 0.0016 U	< 0.0017 U	< 0.0015 U	< 0.0023 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0015 U	< 0.0028 U	< 0.0019 U	< 0.0035 U	< 0.0017 U	< 0.0018 U	< 0.0016 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.003 U	< 0.002 U	< 0.0037 U	< 0.0018 U	< 0.0019 U	< 0.0017 U	< 0.0027 U
Northern Athletic Field	SSHS-B3852	091721 09:30 SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0031 U	< 0.0021 U	< 0.0039 U	< 0.0019 U	< 0.002 U	< 0.0018 U	< 0.0028 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0014 U	< 0.0025 UT	< 0.0017 U	< 0.0031 UT	< 0.0015 UT	< 0.0016 U	< 0.0015 U	< 0.0023 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0014 U	< 0.0025 U	< 0.0017 U	< 0.0031 UT	< 0.0015 U	< 0.0016 U	< 0.0014 U	< 0.0022 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.001 J	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00 SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.00075 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00085 U	< 0.034 U	< 0.00075 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15 SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.00042 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00046 U	< 0.034 U	< 0.00017 U	< 0.034 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													1,2-Dichloroethene	cis-1,2-Dichloroethene	trans-1,2-Dichloroethene	1,2-Dichloropropane	cis-1,3-Dichloropropene	trans-1,3-Dichloropropene	Ethylbenzene	Freon 113
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.25	0.19				1	
Restricted - Residential														100	100				41	
Protection of Groundwater														0.25	0.19				1	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0085 U	< 0.0031 U	< 0.0036 U	< 0.0028 U	< 0.0046 U	< 0.0047 U	< 0.0038 U	< 0.0042 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.0011 U	< 0.0014 U	< 0.0013 U	< 0.0008 U	< 0.0027 U	< 0.0035 U	< 0.00098 U	< 0.0012 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	< 0.001 U	< 0.0013 UJ	< 0.0013 U	< 0.00076 UJ	< 0.0026 UJ	< 0.0033 UJ	< 0.00094 UJ	< 0.0011 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00041 U	< 0.00026 U	< 0.00026 U	< 0.00019 U	0.011
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.00036 U	< 0.00034 U	< 0.00023 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U	< 0.00028 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0053 U	< 0.0019 U	< 0.0023 U	< 0.0017 U	< 0.0028 U	< 0.0029 U	< 0.0024 U	< 0.0026 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.0020 U	< 0.0015 U	< 0.0025 U	< 0.0026 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0043 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0024 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0055 U	< 0.0020 U	< 0.0024 U	< 0.0018 U	< 0.0030 U	< 0.0030 U	< 0.0025 U	< 0.0027 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0048 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0026 U	< 0.0026 U	< 0.0022 U	< 0.0023 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0047 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0026 U	< 0.0026 U	< 0.0021 U	0.0045 J
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0021 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00084 U	< 0.00068 U	< 0.034 U	< 0.00095 U	< 0.0029 U	< 0.00045 U	< 0.034 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.0054 U	< 0.002 U	< 0.0023 U	< 0.0018 U	< 0.0029 U	< 0.003 U	< 0.0025 U	< 0.0027 U
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.0039 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0021 U	< 0.0022 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0038 U	< 0.0014 U	< 0.0016 U	< 0.0012 U	< 0.002 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.00035 U	< 0.00033 U	< 0.00022 U	< 0.00039 U	< 0.00025 U	< 0.00024 U	< 0.00018 U	< 0.00028 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0049 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	0.056
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0023 U
Northern Athletic Field	SSHS-B3646A	092421 10:00_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0019 U	< 0.0022 U	< 0.034 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.034 U
Northern Athletic Field	SSHS-B4265	102821 10:00_SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.00037 U	< 0.00034 U	< 0.00024 U	< 0.00040 U	< 0.00026 U	< 0.00025 U	< 0.00019 U	< 0.00029 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0052 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.25 U	< 0.094 U	< 0.11 U	< 0.083 U	< 0.14 U	< 0.14 U	< 0.12 U	< 0.12 UJ
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00064 U	< 0.00052 U	< 0.034 U	< 0.00072 U	< 0.0022 U	< 0.00035 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0036 U	< 0.0013 U	< 0.0015 U	< 0.0012 U	< 0.002 U	< 0.002 U	< 0.0016 U	< 0.0018 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00059 U	< 0.00047 U	< 0.034 U	< 0.00066 U	< 0.002 U	< 0.00032 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.096 U	< 0.11 U	< 0.085 U	< 0.14 U	< 0.14 U	< 0.12 U	< 0.13 UJ
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00057 U	< 0.00046 U	< 0.034 U	< 0.00065 U	< 0.002 U	< 0.00031 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0044 U	< 0.0016 U	< 0.0019 U	< 0.0014 U	< 0.0024 U	< 0.0024 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00063 U	< 0.00051 U	< 0.034 U	< 0.00071 U	< 0.0022 U	< 0.00034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.38 U	< 0.14 U	< 0.16 U	< 0.12 U	< 0.21 U	< 0.21 U	< 0.17 U	< 0.19 UJ
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0045 U	< 0.0016 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0045 U	< 0.0017 U	< 0.0019 U	< 0.0015 U	< 0.0024 U	< 0.0025 U	< 0.002 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.005 U	< 0.0019 U	< 0.0022 U	< 0.0016 U	< 0.0027 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.0042 U	< 0.0016 U	< 0.0018 U	< 0.0014 U	< 0.0023 U	< 0.0023 U	< 0.0019 U	< 0.0021 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0046 U	< 0.0017 U	< 0.002 U	< 0.0015 U	< 0.0025 U	< 0.0025 U	< 0.0021 U	< 0.0022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.005 U	< 0.0018 U	< 0.0021 U	< 0.0016 U	< 0.0027 U	< 0.0027 U	< 0.0022 U	< 0.0024 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.0051 U	< 0.0019 U	< 0.0022 U	< 0.0017 U	< 0.0028 U	< 0.0028 U	< 0.0023 U	< 0.0025 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0041 UT	< 0.0015 UT	< 0.0018 UT	< 0.0014 U	< 0.0022 U	< 0.0023 U	< 0.0019 UT	< 0.0020 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0041 U	< 0.0015 U	< 0.0017 U	< 0.0013 U	< 0.0022 U	< 0.0022 U	< 0.0018 U	< 0.0020 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.0014 U	< 0.0014 U	< 0.034 U	< 0.0028 U	< 0.0036 U	< 0.001 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00042 U	< 0.00034 U	< 0.034 U	< 0.00048 U	< 0.0015 U	< 0.00023 U	< 0.034 U

DRAFT

												2-Hexanone (MBK)	Isopropylbenzene	Methyl Acetate	Methylcyclohexane	Methyl Ethyl Ketone	4-Methyl-2-pentanone	Methyl-tert-butyl ether	Styrene
												mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted																0.12		0.93	
Restricted - Residential																100		100	
Protection of Groundwater																0.12		0.93	
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0033 U	< 0.0054 U	< 0.015 U	< 0.005 U	< 0.0053 U	< 0.0038 U	< 0.0031 U	< 0.0031 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.0038 U	< 0.0018 U	< 0.0032 U	< 0.0012 U	< 0.0033 U	< 0.0035 U	< 0.0019 U	< 0.0011 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	< 0.0037 U	< 0.0017 UJ	< 0.003 U	< 0.0011 U	< 0.0032 U	< 0.0033 U	< 0.0018 U	< 0.001 UJ
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0040 U	0.0011	< 0.00034 U	< 0.0015 U	< 0.00048 U	< 0.00026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0020 U	< 0.0034 U	< 0.0095 U	< 0.0031 U	< 0.0033 U	< 0.0024 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0082 U	< 0.0027 U	< 0.0028 U	< 0.0020 U	< 0.0016 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0077 U	< 0.0025 U	< 0.0027 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0021 U	< 0.0035 U	< 0.0099 U	< 0.0032 U	< 0.0034 U	< 0.0025 U	< 0.0020 U	< 0.0020 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0087 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0030 U	< 0.0086 U	< 0.0028 U	< 0.0030 U	< 0.0021 U	< 0.0017 U	< 0.0018 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0018 U	< 0.003 U	< 0.0085 U	< 0.0028 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.0079 U	< 0.0026 U	< 0.0027 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.001 U	< 0.034 U	< 0.0022 U	< 0.00065 U	< 0.00033 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.0021 U	< 0.0035 U	< 0.0098 U	< 0.0032 U	< 0.0034 U	< 0.0024 U	< 0.002 U	< 0.002 U
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.0015 U	< 0.0025 U	< 0.0071 U	< 0.0023 U	< 0.0025 U	< 0.0018 U	< 0.0014 U	< 0.0014 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0014 U	< 0.0024 U	< 0.0068 U	< 0.0022 U	< 0.0023 U	< 0.0017 U	< 0.0014 U	< 0.0014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00026 U	< 0.0039 U	< 0.00046 U	< 0.00034 U	< 0.0014 U	< 0.00047 U	< 0.00025 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0092 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0019 U	< 0.0031 U	< 0.0088 U	< 0.0029 U	< 0.0030 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0093 U	0.0042 J	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3646A	092421 10:00_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.003 U	< 0.034 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B4265	102821 10:00_SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0093 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.0016 U	< 0.00027 U	< 0.0041 U	< 0.00048 U	< 0.00035 U	< 0.0015 U	< 0.00049 U	< 0.00027 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0020 U	< 0.0033 U	< 0.0093 U	< 0.0030 U	< 0.0032 U	< 0.0023 U	< 0.0019 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.098 U	< 0.16 U	< 0.46 U	< 0.15 U	< 0.16 U	< 0.11 U	< 0.091 UJ	< 0.093 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.0016 U	< 0.00049 U	< 0.00025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0014 U	< 0.0023 U	< 0.0065 U	< 0.0021 U	< 0.0022 U	< 0.0016 U	< 0.0013 U	< 0.0013 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.003 J	< 0.0007 U	< 0.034 U	< 0.0015 U	< 0.00045 U	< 0.00023 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.1 U	< 0.17 U	< 0.47 U	< 0.15 U	< 0.16 U	< 0.12 U	< 0.094 UJ	< 0.095 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00068 U	< 0.034 U	< 0.0015 U	< 0.00044 U	< 0.00022 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.0016 U	< 0.00048 U	< 0.00025 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.15 U	< 0.24 U	< 0.68 U	< 0.22 U	< 0.24 U	< 0.17 U	< 0.14 UJ	< 0.14 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0028 U	< 0.008 U	< 0.0026 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0029 U	< 0.0081 U	< 0.0027 U	< 0.0028 U	< 0.002 U	< 0.0016 U	< 0.0016 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0091 U	< 0.003 U	< 0.0031 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0027 U	< 0.0076 U	< 0.0025 U	< 0.0026 U	< 0.0019 U	< 0.0015 U	< 0.0016 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0029 U	< 0.0083 U	< 0.0027 U	< 0.0029 U	< 0.0021 U	< 0.0017 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0032 U	< 0.0089 U	< 0.0029 U	< 0.0031 U	< 0.0022 U	< 0.0018 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.002 U	< 0.0033 U	< 0.0092 U	< 0.003 U	< 0.0032 U	< 0.0023 U	< 0.0018 U	< 0.0019 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0016 UJ	< 0.0026 UT	< 0.0075 U	< 0.0024 UT	< 0.0026 UJ	< 0.0019 UJ	< 0.0015 U	< 0.0015 U
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0016 U	< 0.0026 U	< 0.0073 U	< 0.0024 U	< 0.0025 U	< 0.0018 U	< 0.0015 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.017 J	0.0062 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.0012 U	< 0.034 U	< 0.0036 U	< 0.0019 U	< 0.0011 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	0.00071 J	< 0.034 U	< 0.0011 U	< 0.00032 U	< 0.00017 U

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													1,1,2,2-Tetrachloroethane	**Tetrachloroethene**	**Toluene**	**1,2,3-Trichlorobenzene**	**1,2,4-Trichlorobenzene**	**1,1,1-Trichloroethane**	**1,1,2-Trichloroethane**	**Trichloroethene**
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														1.3	0.7			0.68		0.47
Restricted - Residential														19	100			100		21
Protection of Groundwater														1.3	0.7			0.68		0.47
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]								
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 U	< 0.002 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0032 U	< 0.0042 U	< 0.003 U	< 0.0057 U	< 0.0053 U	< 0.0035 U	< 0.0021 U	< 0.0033 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.00069 U	< 0.00073 U	< 0.0028 U	< 0.0023 U	< 0.0017 U	< 0.0011 U	< 0.00059 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	< 0.0013 U	< 0.00065 UJ	< 0.00069 UJ	< 0.0026 UJ	< 0.0022 UJ	< 0.0016 U	< 0.001 U	< 0.00057 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.00021 U	0.0057	< 0.00022 U	< 0.00017 U	< 0.00034 U	0.00023 J	< 0.00017 U	0.028
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.00020 U	0.00038 J	0.00038 J	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	0.00030 J
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0020 U	< 0.0026 U	< 0.0019 U	< 0.0035 U	< 0.0033 U	< 0.0022 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0018 U	< 0.0023 U	< 0.0017 U	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.0031 U	< 0.0028 U	< 0.0019 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0029 U	< 0.0027 U	< 0.0018 U	< 0.0010 U	< 0.0016 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0020 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0022 U	< 0.0013 U	< 0.0021 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0032 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0018 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0018 U	0.0023 J	0.0076	< 0.0032 U	< 0.0029 U	< 0.0019 U	< 0.0011 U	0.026
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0022 U	< 0.0015 U	< 0.003 U	< 0.0027 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00088 U	< 0.0005 U	< 0.034 U	< 0.0004 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.002 U	< 0.0027 U	< 0.0019 U	< 0.0037 U	< 0.0034 U	< 0.0022 U	< 0.0013 U	< 0.0021 U
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.0015 U	< 0.0019 U	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0016 U	< 0.00096 U	< 0.0015 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0014 U	< 0.0018 U	< 0.0013 U	< 0.0025 U	< 0.0023 U	< 0.0015 U	< 0.00091 U	< 0.0014 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.00020 U	0.00029 J	< 0.00021 U	< 0.00017 U	< 0.00033 U	< 0.00021 U	< 0.00016 U	0.00036 J
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.0020 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0030 U	< 0.0020 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.0019 U	< 0.0025 U	0.0054 J	< 0.0035 U	< 0.0032 U	0.0033 J	< 0.0013 U	0.022
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 UJ	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3646A	092421 10:00_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.0025 U	< 0.0018 U	< 0.034 U	< 0.0032 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B4265	102821 10:00_SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0012 U	< 0.002 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.00020 U	< 0.00029 U	< 0.00022 U	< 0.00017 U	< 0.00034 U	< 0.00022 U	< 0.00017 U	0.00034 J
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0035 U	< 0.0032 U	< 0.0021 U	< 0.0013 U	< 0.0020 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.095 U	< 0.13 UJ	< 0.09 U	< 0.17 U	< 0.16 U	< 0.1 U	< 0.062 U	< 0.098 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00067 U	< 0.00038 U	< 0.034 U	< 0.00031 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0013 U	< 0.0018 U	< 0.0013 U	< 0.0024 U	< 0.0022 U	< 0.0015 U	< 0.00087 U	< 0.0014 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00062 U	0.00053 J	< 0.034 U	< 0.00028 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.097 U	< 0.13 UJ	< 0.092 U	< 0.18 U	< 0.16 U	< 0.11 U	< 0.063 U	< 0.1 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.0006 U	< 0.00034 U	< 0.034 U	< 0.00027 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.00066 U	< 0.00037 U	< 0.034 U	< 0.0003 U	< 0.034 U	< 0.034 U	< 0.034 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.14 U	< 0.19 UJ	< 0.13 U	< 0.26 U	< 0.24 U	< 0.16 U	< 0.092 U	< 0.15 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0022 U	< 0.0016 U	< 0.003 U	< 0.0028 UJ	< 0.0018 U	< 0.0011 U	< 0.0017 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0031 UJ	< 0.0021 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.0016 U	< 0.0021 U	< 0.0015 U	< 0.0028 U	< 0.0026 UJ	< 0.0017 U	< 0.001 U	< 0.0016 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0017 U	< 0.0023 U	< 0.0016 U	< 0.0031 U	< 0.0029 UJ	< 0.0019 U	< 0.0011 U	< 0.0018 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.0018 U	< 0.0024 U	< 0.0017 U	< 0.0033 U	< 0.0031 UJ	< 0.002 U	< 0.0012 U	< 0.0019 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.0019 U	< 0.0025 U	< 0.0018 U	< 0.0034 U	< 0.0032 UJ	< 0.0021 U	< 0.0012 U	< 0.002 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0015 UJ	< 0.0020 UT	< 0.0015 U	< 0.0028 U	< 0.0026 U	< 0.0017 UT	< 0.0010 U	< 0.0016 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0015 UJ	< 0.0020 UT	< 0.0014 U	< 0.0027 U	< 0.0025 U	< 0.0017 U	< 0.00098 UJ	< 0.0016 UT
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	0.0011 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	0.002 J
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	0.00046 J	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.00071 U	< 0.00075 U	< 0.034 U	< 0.0024 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.00044 U	0.00048 J	< 0.034 U	< 0.0002 U	< 0.034 U	< 0.034 U	0.00073 J

DRAFT

TABLE 6-4D
Deep Soil Results Remaining in Place - VOCs

Former Sperry Remington – North Portion #c808022
Elmira, New York

													Trichlorofluoromethane	Vinyl chloride	Xylene (m)	Xylene (o)	Xylenes (Total)
													mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Unrestricted														0.02			0.26
Restricted - Residential														0.9			100
Protection of Groundwater														0.02			1.6
Site Location	Location	SYS_SAMPLE_CODE	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3] (ft)	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (bgs)	Sample depth from final grade[6] (bfg)	Lab Report	Excavation Status[7]					
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-26-28	SSHS-B4261-SUB-26-28	10/26/2021	854.31	857.88	3.57	-	26 - 28 ft	29.57-31.57 ft	180-129052-1	Not Excavated	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-26-28	SSHS-B4265-SUB-26-28	10/26/2021	854.78	855.87	1.09	-	26 - 28 ft	27.09-29.09 ft	180-129052-1	Not Excavated	< 0.0086 U	< 0.0075 U	< 0.0037 U	< 0.0042 U	< 0.015 U
Northern Athletic Field	SSHS-B4263	110221 10:20_SSHS-B4263-SUB-26-28	SSHS-B4263-SUB-26-28	11/1/2021	854.60	858.21	3.61	-	26 - 28 ft	29.61-31.61 ft	180-129325-1	Not Excavated	< 0.0025 U	< 0.0017 U	< 0.00074 U	< 0.00081 U	< 0.0015 U
Northern Athletic Field	SSHS-B4264	110221 10:20_SSHS-B4264-SUB-26-28	SSHS-B4264-SUB-26-28	11/1/2021	852.29	853.31	1.02	-	26 - 28 ft	27.02-29.02 ft	180-129325-1	Not Excavated	< 0.0024 U	< 0.0016 U	< 0.0007 UJ	< 0.00077 UJ	< 0.0014 UJ
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28-20230119	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28-20230119	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated	< 0.00038 U	< 0.00051 U	0.00027 J	< 0.00018 U	0.00027 J
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5-20210401	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.0053 U	< 0.0046 U	< 0.0023 U	< 0.0026 U	< 0.0093 U
Northern Athletic Field	SSHS-B3907	DUP-29-20210506	DUP-29	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0048 U	< 0.0041 U	< 0.0020 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30-20210506	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.0046 U	< 0.0040 U	< 0.0020 U	< 0.0022 U	< 0.0080 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30-20210513	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.0044 U	< 0.0038 U	< 0.0019 U	< 0.0021 U	< 0.0076 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30-20210514	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.0056 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0097 U
Northern Athletic Field	SSHS-B3883	DUP-3-20210519	DUP-3	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0049 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0086 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30-20210519	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.0049 U	< 0.0042 U	< 0.0021 U	< 0.0024 U	< 0.0085 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-28-30	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated	< 0.0048 U	< 0.0042 U	< 0.0021 U	< 0.0023 U	< 0.0083 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-28-30	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0077 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-28-30	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.0011 U	< 0.034 U	< 0.0011 U
Northern Athletic Field	SSHS-B4260	102621 10:00_SSHS-B4260-SUB-28-30	SSHS-B4260-SUB-28-30	10/25/2021	852.55	853.09	0.54	-	28 - 30 ft	28.54-30.54 ft	180-128986-1	Not Excavated	< 0.0055 U	< 0.0048 U	< 0.0024 U	< 0.0027 U	< 0.0096 U
Northern Athletic Field	SSHS-B4261	102721 09:30_SSHS-B4261-SUB-28-30	SSHS-B4261-SUB-28-30	10/26/2021	854.31	857.88	3.57	-	28 - 30 ft	31.57-33.57 ft	180-129052-1	Not Excavated	< 0.004 U	< 0.0035 U	< 0.0017 U	< 0.0019 U	< 0.007 U
Northern Athletic Field	SSHS-B4265	102721 09:30_SSHS-B4265-SUB-28-30	SSHS-B4265-SUB-28-30	10/26/2021	854.78	855.87	1.09	-	28 - 30 ft	29.09-31.09 ft	180-129052-1	Not Excavated	< 0.0038 U	< 0.0033 U	< 0.0016 U	< 0.0018 U	< 0.0066 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30-20230119	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated	< 0.00037 U	< 0.00050 U	< 0.00016 U	< 0.00018 U	< 0.00016 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32-20210506	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32-20210513	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.0050 U	< 0.0043 U	< 0.0021 U	< 0.0024 U	< 0.0087 U
Northern Athletic Field	SSHS-B3920	070221 09:00_SSHS-B3920-SUB-30-32	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-30-32	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated	< 0.0047 U	< 0.0041 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3646A	092421 10:00_SSHS-B3646A-SUB-30-32	SSHS-B3646A-SUB-30-32	9/23/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127595-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.0022 U	< 0.034 U	< 0.009 U
Northern Athletic Field	SSHS-B4265	102821 10:00_SSHS-B4265-SUB-30-32	SSHS-B4265-SUB-30-32	10/27/2021	854.78	855.87	1.09	-	30 - 32 ft	31.09-33.09 ft	180-129169-1	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32-20230119	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated	< 0.00039 U	< 0.00052 U	< 0.00017 U	< 0.00019 U	< 0.00017 U
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33-20210519	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.0052 U	< 0.0046 U	< 0.0023 U	< 0.0025 U	< 0.0091 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-32-34	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.22 U	< 0.11 U	< 0.13 U	< 0.45 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-32-34	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00084 U	< 0.034 U	< 0.00084 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-34-36	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated	< 0.0037 U	< 0.0032 U	< 0.0016 U	< 0.0018 U	< 0.0064 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-34-36	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00077 U	< 0.034 U	< 0.00077 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-36-38	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated	< 0.26 U	< 0.23 U	< 0.11 U	< 0.13 U	< 0.46 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-36-38	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00075 U	< 0.034 U	< 0.00075 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-38-40	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0078 U
Northern Athletic Field	SSHS-B3646A	091821 10:15_SSHS-B3646A-SUB-38-40	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated	< 0.034 U	< 0.034 U	< 0.00083 U	< 0.034 U	< 0.00083 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-40-42	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated	< 0.39 U	< 0.33 U	< 0.17 U	< 0.19 U	< 0.67 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-42-44	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated	< 0.0045 U	< 0.0039 U	< 0.0019 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-44-46	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated	< 0.0046 U	< 0.004 U	< 0.002 U	< 0.0022 U	< 0.0079 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-46-48	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated	< 0.0051 U	< 0.0044 U	< 0.0022 U	< 0.0025 U	< 0.0089 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-48-50	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated	< 0.0043 U	< 0.0037 U	< 0.0018 U	< 0.0021 U	< 0.0075 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-50-52	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated	< 0.0047 U	< 0.004 U	< 0.002 U	< 0.0023 U	< 0.0081 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-52-54	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated	< 0.005 U	< 0.0044 U	< 0.0022 U	< 0.0024 U	< 0.0088 U
Northern Athletic Field	SSHS-B3852	091721 09:30_SSHS-B3852-SUB-54-56	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated	< 0.0052 U	< 0.0045 U	< 0.0022 U	< 0.0025 U	< 0.009 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18-20230209	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 0.0042 U	< 0.0037 U	< 0.0018 UT	< 0.0020 UT	< 0.0073 UT
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18-20230212	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 0.0041 U	< 0.0036 U	< 0.0018 U	< 0.0020 U	< 0.0072 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-16-18	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-16-18	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U	< 0.034 U
Tennis Courts / Main Parking Lot	SSHS-B4170	091521 10:00_SSHS-B4170-SUB-18-20	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00076 U	< 0.034 U	< 0.0015 U
Tennis Courts / Main Parking Lot	SSHS-B4161	091821 10:15_SSHS-B4161-SUB-18-20	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated	< 0.034 U	< 0.034 U	< 0.00056 U	< 0.034 U	< 0.00056 U

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated			< 110 U							
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated			< 110 U							
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			< 120 U							
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated			< 110 U							
Football Field	SSHS-B3874	DUP-25	4/1/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	1801194601	Not Excavated	< 130 U			< 0.47 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated			< 110 U	< 0.38 U	< 0.025 U	0.043 J	< 0.04 U	< 0.022 U	< 0.068 U	< 0.036 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-127595-2	Not Excavated			< 120 U							
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	< 0.028 UJ	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated			< 110 U	< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.07 U	< 0.036 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated			< 110 U	< 0.39 UJ	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.07 U	< 0.037 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated			< 120 U							
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated			< 120 U							
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated	< 120 U									
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated			< 110 U							
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated			< 110 U							
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 130 U									
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated	< 110 U									
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated	< 140 U									
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated			< 580 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated			< 110 U							
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated			< 130 U							
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated			< 190 U							
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated			< 110 U	< 0.049 U	< 0.039 U	< 0.047 U	< 0.053 U	< 0.049 U	< 0.03 U	< 0.05 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated	< 120 U									
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 120 U			< 0.42 U	< 0.028 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.039 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated	< 120 U									
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated	< 130 U									
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated			< 110 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.023 U	< 0.069 U	< 0.036 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated			< 110 U	< 0.38 U	< 0.025 U	< 0.028 U	< 0.04 U	< 0.022 U	< 0.068 U	< 0.036 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated			< 110 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated			< 110 U							
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-119861-1	Not Excavated			< 130 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated			< 110 U	< 0.37 UJ	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated			< 110 U							
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated			< 120 U							
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated			< 130 U							
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated			< 110 U							
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated			< 110 U							
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated			< 110 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated			< 550 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.066 U	< 0.035 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated			< 120 U							
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated			< 120 U							
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated			< 110 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated			< 110 U							
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated			< 110 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.027 U	< 0.037 U	< 0.021 U	< 0.064 U	< 0.034 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated			< 110 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.023 U	< 0.069 U	< 0.036 U

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated										
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated										
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated										
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated										
Football Field	SSHS-B3874	DUP-25	4/1/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	1801194601	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.097 U	< 0.068 U	< 0.064 UT
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.037 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 UJ	< 0.036 U	< 0.083 U	< 0.2 U	< 0.087 U	0.092 J	< 0.055 U	< 0.052 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.044 U	< 0.038 U	< 34 U	< 0.21 U	< 0.09 U	< 0.08 U	< 0.056 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.044 U	< 0.038 U	< 34 U	< 0.21 U	< 0.09 U	< 0.081 U	< 0.056 U	< 34 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated										
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated										
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated										
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated										
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated										
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated										
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated										
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.039 U	< 0.029 U	< 0.031 U	< 0.022 U	< 34 U	< 0.044 U	< 0.054 U	< 0.042 U	< 0.038 U	< 34 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.041 U	< 0.092 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.057 UT
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated										
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated										
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.089 U	< 0.079 U	< 0.056 U	< 0.053 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.029 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 34 U
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated										
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 0.06 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 34 U	< 0.2 U	< 0.086 U	< 0.077 U	< 0.054 U	< 34 U
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated										
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated										
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated										
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated										
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated										
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.081 U	< 0.2 U	< 0.085 U	< 0.076 U	< 0.054 U	< 0.051 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated										
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.053 UT
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.028 U	< 0.03 U	< 0.04 U	< 0.035 U	< 0.079 U	< 0.19 U	< 0.083 U	< 0.074 U	< 0.052 U	< 0.049 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.088 U	< 0.079 U	< 0.056 U	< 0.052 U

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B2632	SSHS-B2632-SUB-14-16	5/20/2019	854.95	855.25	0.30	-	14 - 16 ft	14.3-16.3 ft	180-90324-1	Not Excavated				
Football Field	SSHS-B2720	SSHS-B2720-SUB-14-16	5/17/2019	854.80	855.64	0.84	-	14 - 16 ft	14.84-16.84 ft	180-90275-1	Not Excavated				
Football Field	SSHS-B4013	DUP-206	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated				
Football Field	SSHS-B4013	SSHS-B4013-SUB-16-18	5/19/2021	855.81	855.80	-0.01	-	16 - 18 ft	15.99-17.99 ft	180-121899-1	Not Excavated				
Football Field	SSHS-B3874	DUP-25	4/1/2021	855.35	855.36	0.01	-	16 - 18 ft	16.01-18.01 ft	1801194601	Not Excavated	< 0.045 UT	< 0.31 UT	< 0.19 U	< 0.49 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-16-18	4/9/2021	856.06	856.07	0.01	-	16 - 18 ft	16.01-18.01 ft	180-119815-1	Not Excavated	< 0.037 U	< 0.25 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B4164	DUP-21	9/23/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B3877	SSHS-B3877-SUB-16-18	4/11/2021	855.38	855.49	0.11	-	16 - 18 ft	16.11-18.11 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.25 UJ	< 0.15 UJ	< 0.39 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-16-18	4/18/2021	855.26	855.36	0.10	-	16 - 18 ft	16.1-18.1 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-16-18	4/20/2021	855.35	855.48	0.13	-	16 - 18 ft	16.13-18.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-16-18	4/19/2021	855.34	855.50	0.16	-	16 - 18 ft	16.16-18.16 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 UJ
Football Field	SSHS-B3880	SSHS-B3880-SUB-16-18	4/17/2021	855.20	855.37	0.17	-	16 - 18 ft	16.17-18.17 ft	180-120257-1	Not Excavated				
Football Field	SSHS-B3881	SSHS-B3881-SUB-16-18	4/18/2021	855.29	855.53	0.24	-	16 - 18 ft	16.24-18.24 ft	180-120245-1	Not Excavated				
Football Field	ISMP-B527-BOT4	SSHS-ISMP-B527 BOT 4	6/3/2021	-	855.66	-	839.32	16 - 18 ft	16.34 ft	1801226362	Not Excavated				
Football Field	SSHS-B3876	SSHS-B3876-SUB-16-18	4/2/2021	855.09	855.50	0.41	-	16 - 18 ft	16.41-18.41 ft	180-119462-1	Not Excavated				
Football Field	SSHS-B645A	SSHS-B645A-SUB-16-18	4/18/2021	854.96	855.37	0.41	-	16 - 18 ft	16.41-18.41 ft	180-120245-1	Not Excavated				
Football Field	SSHS-B3873	SSHS-B3873-SUB-16-18	4/19/2021	854.94	855.38	0.44	-	16 - 18 ft	16.44-18.44 ft	180-120434-1	Not Excavated				
Football Field	ISMP-B527-BOT1	SSHS-ISMP-B527 BOT 1	6/3/2021	-	855.61	-	839.01	16 - 18 ft	16.6 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT3	SSHS-ISMP-B527 BOT 3	6/3/2021	-	855.47	-	838.87	16 - 18 ft	16.6 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT9	SSHS-ISMP-B527 BOT 9	6/3/2021	-	855.37	-	838.72	16 - 18 ft	16.65 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT7	SSHS-ISMP-B527 BOT 7	6/3/2021	-	855.58	-	838.87	16 - 18 ft	16.71 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT14	SSHS-ISMP-B527 BOT 14	6/3/2021	-	855.40	-	838.69	16 - 18 ft	16.71 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT15	SSHS-ISMP-B527 BOT 15	6/3/2021	-	855.61	-	838.88	16 - 18 ft	16.73 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT6	SSHS-ISMP-B527 BOT 6	6/3/2021	-	855.44	-	838.66	16 - 18 ft	16.78 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT10	SSHS-ISMP-B527 BOT 10	6/3/2021	-	855.55	-	838.70	16 - 18 ft	16.85 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT11	SSHS-ISMP-B527 BOT 11	6/3/2021	-	855.67	-	838.76	16 - 18 ft	16.91 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT8	SSHS-ISMP-B527 BOT 8	6/3/2021	-	855.57	-	838.65	16 - 18 ft	16.92 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT2	SSHS-ISMP-B527 BOT 2	6/3/2021	-	855.44	-	838.50	16 - 18 ft	16.94 ft	1801226362	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-16-18	4/8/2021	856.13	856.13	0.00	-	16 - 18 ft	16-18 ft	180-119767-1	Not Excavated	< 0.039 U	< 0.27 UJ	< 0.16 UJ	< 0.42 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-16-18	4/9/2021	855.85	855.85	0.00	-	16 - 18 ft	16-18 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3855	DUP-03	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3855	SSHS-B3855-SUB-16-18	4/12/2021	855.28	855.28	0.00	-	16 - 18 ft	16-18 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-16-18	4/13/2021	856.50	856.50	0.00	-	16 - 18 ft	16-18 ft	180-119938-1	Not Excavated				
Football Field	SSHS-B4010	SSHS-B4010-SUB-16-18	5/20/2021	855.47	855.47	0.00	-	16 - 18 ft	16-18 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4164	SSHS-B4164-SUB-16-18	9/23/2021	856.42	856.42	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B4165	SSHS-B4165-SUB-16-18	9/23/2021	856.00	856.00	0.00	-	16 - 18 ft	16-18 ft	180-127595-2	Not Excavated	< 0.043 U	< 0.036 U	< 0.027 U	< 0.023 U
Football Field	ISMP-B527-BOT13	SSHS-ISMP-B527 BOT 13	6/3/2021	-	855.52	-	838.52	16 - 18 ft	17.01 ft	1801226362	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-16-18	4/1/2021	852.54	853.57	1.03	-	16 - 18 ft	17.03-19.03 ft	1801194601	Not Excavated	< 0.041 UT	< 0.28 UT	< 0.17 U	< 0.44 U
Football Field	ISMP-B527-BOT12	SSHS-ISMP-B527 BOT 12	6/3/2021	-	855.70	-	838.55	16 - 18 ft	17.15 ft	1801226362	Not Excavated				
Football Field	ISMP-B527-BOT5	SSHS-ISMP-B527 BOT 5	6/3/2021	-	855.56	-	838.23	16 - 18 ft	17.33 ft	1801226362	Not Excavated				
Football Field	SSHS-B3864	SSHS-B3864-SUB-18-20	4/9/2021	856.06	856.07	0.01	-	18 - 20 ft	18.01-20.01 ft	180-119815-1	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-18-20	5/20/2021	855.17	855.25	0.08	-	18 - 20 ft	18.08-20.08 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3877	SSHS-B3877-SUB-18-20	4/11/2021	855.38	855.49	0.11	-	18 - 20 ft	18.11-20.11 ft	180-119861-1	Not Excavated	< 0.037 U	< 0.25 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-18-20	4/18/2021	855.26	855.36	0.10	-	18 - 20 ft	18.1-20.1 ft	180-120245-1	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 UJ
Football Field	SSHS-B4011	SSHS-B4011-SUB-18-20	5/19/2021	855.31	855.41	0.10	-	18 - 20 ft	18.1-20.1 ft	180-121899-1	Not Excavated				
Football Field	SSHS-B3872	SSHS-B3872-SUB-18-20	4/20/2021	855.35	855.48	0.13	-	18 - 20 ft	18.13-20.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3877	DUP-29	4/12/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-18-20	4/19/2021	855.34	855.50	0.16	-	18 - 20 ft	18.16-20.16 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 UJ
Football Field	SSHS-B3880	SSHS-B3880-SUB-18-20	4/17/2021	855.20	855.37	0.17	-	18 - 20 ft	18.17-20.17 ft	180-120257-1	Not Excavated				
Football Field	SSHS-B3881	SSHS-B3881-SUB-18-20	4/18/2021	855.29	855.53	0.24	-	18 - 20 ft	18.24-20.24 ft	180-120245-1	Not Excavated				
Football Field	SSHS-B4012	SSHS-B4012-SUB-18-20	5/21/2021	855.04	855.41	0.37	-	18 - 20 ft	18.37-20.37 ft	180-122085-1	Not Excavated				
Football Field	SSHS-B3876	SSHS-B3876-SUB-18-20	4/2/2021	855.09	855.50	0.41	-	18 - 20 ft	18.41-20.41 ft	180-119462-1	Not Excavated				
Football Field	SSHS-B645A	SSHS-B645A-SUB-18-20	4/18/2021	854.96	855.37	0.41	-	18 - 20 ft	18.41-20.41 ft	180-120245-1	Not Excavated				
Football Field	SSHS-B3878	SSHS-B3878-SUB-18-20	4/5/2021	854.82	855.53	0.71	-	18 - 20 ft	18.71-20.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-18-20	4/8/2021	856.13	856.13	0.00	-	18 - 20 ft	18-20 ft	180-119767-1	Not Excavated	< 0.036 U	< 0.25 UJ	< 0.15 U	< 0.39 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-18-20	4/9/2021	855.85	855.85	0.00	-	18 - 20 ft	18-20 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3858	SSHS-B3858-SUB-18-20	4/10/2021	856.08	856.08	0.00	-	18 - 20 ft	18-20 ft	180-119841-1	Not Excavated				
Football Field	SSHS-B3855	SSHS-B3855-SUB-18-20	4/12/2021	855.28	855.28	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3859	SSHS-B3859-SUB-18-20	4/12/2021	857.14	857.14	0.00	-	18 - 20 ft	18-20 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-18-20	4/13/2021	856.50	856.50	0.00	-	18 - 20 ft	18-20 ft	180-119938-1	Not Excavated	< 0.038 U	< 0.27 UJ	< 0.16 UJ	< 0.42 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-18-20	5/20/2021	855.47	855.47	0.00	-	18 - 20 ft	18-20 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4164	SSHS-B4164-SUB-18-20	9/23/2021	856.42	856.42	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B4165	SSHS-B4165-SUB-18-20	9/23/2021	856.00	856.00	0.00	-	18 - 20 ft	18-20 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-18-20	4/1/2021	852.54	853.57	1.03	-	18 - 20 ft	19.03-21.03 ft	1801194601	Not Excavated	< 0.038 UT	< 0.26 UT	< 0.16 U	< 0.41 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-20-22	4/9/2021	856.06	856.07	0.01	-	20 - 22 ft	20.01-22.01 ft	180-119815-1	Not Excavated	< 0.035 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-20-22	5/20/2021	855.17	855.25	0.08	-	20 - 22 ft	20.08-22.08 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3877	SSHS-B3877-SUB-20-22	4/11/2021	855.38	855.49	0.11	-	20 - 22 ft	20.11-22.11 ft	180-119861-1	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.04 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated			< 120 U							
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated			< 130 U							
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated			< 110 U							
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated			< 110 U							
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated			< 120 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated			< 560 U	< 0.35 U	< 0.024 U	< 0.026 U	< 0.037 U	< 0.021 U	< 0.063 U	< 0.033 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated			< 100 U							
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated			< 120 U							
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	0.071 J	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.026 U	< 0.037 U	< 0.021 U	< 0.063 U	< 0.033 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated			< 120 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated			< 120 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated			< 110 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated			< 110 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated			< 110 U							
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated			< 130 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated			< 120 U	< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.07 U	< 0.037 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated			< 110 U	< 0.36 U	< 0.024 U	< 0.027 U	< 0.038 U	< 0.021 U	< 0.065 U	< 0.034 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated			< 130 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated			< 120 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated			< 110 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated			< 120 U	< 0.39 U	< 0.027 U	0.032 J	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated			< 110 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 130 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated			< 120 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated			< 130 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.35 U	< 0.024 U	< 0.027 U	< 0.037 U	< 0.021 U	< 0.064 U	< 0.033 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.026 U	< 0.037 U	< 0.021 U	< 0.063 U	< 0.033 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated			< 120 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated			< 120 U	< 0.42 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.04 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 140 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated			< 130 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated			< 120 U	< 0.39 U	< 0.026 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated			< 130 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.078 U	< 0.041 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-127595-2	Not Excavated			< 120 U							
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated			< 140 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated			< 120 U	< 0.42 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.04 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated			< 110 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.036 U	< 34 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 34 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated										
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated										
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated										
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated										
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.027 U	< 0.029 U	< 0.04 U	< 0.034 U	< 0.077 U	< 0.19 U	< 0.081 U	< 0.073 U	< 0.051 U	< 0.048 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated										
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 UT
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.027 U	< 0.029 U	< 0.04 U	< 0.034 U	< 0.077 U	< 0.19 U	< 0.081 U	< 0.073 U	< 0.051 U	< 0.048 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.04 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.06 U	< 0.057 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 34 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.03 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.09 U	< 0.081 U	< 0.057 U	< 0.053 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 UT
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.028 U	< 0.03 U	< 0.041 U	< 0.035 U	< 0.079 U	< 0.19 U	< 0.083 U	< 0.075 U	< 0.052 U	< 0.049 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.1 U	< 0.089 U	< 0.063 U	< 0.059 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.091 U	< 0.064 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 34 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.054 U	< 34 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.068 U	< 0.064 UT
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U	< 0.059 U	< 0.055 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.1 U	< 0.089 U	< 0.063 U	< 0.059 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 34 U	< 0.23 U	< 0.1 U	< 0.089 U	< 0.063 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.028 U	< 0.029 U	< 0.04 U	< 0.034 U	< 34 U	< 0.19 U	< 0.082 U	< 0.073 U	< 0.051 U	< 34 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.027 U	< 0.029 U	< 0.04 U	< 0.034 U	< 0.077 U	< 0.19 U	< 0.081 U	< 0.073 U	< 0.051 U	< 0.048 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.068 U	< 0.064 UT
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 0.061 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 0.06 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.094 U	< 0.085 U	< 0.059 U	< 34 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 0.061 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.096 U	< 0.23 U	< 0.1 U	< 0.09 U	< 0.063 U	< 0.06 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-127595-2	Not Excavated										
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 0.061 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.045 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 34 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 34 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 34 U

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B3870	SSHS-B3870-SUB-20-22	4/18/2021	855.26	855.36	0.10	-	20 - 22 ft	20.1-22.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.4 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-20-22	4/20/2021	855.35	855.48	0.13	-	20 - 22 ft	20.13-22.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-20-22	4/19/2021	855.34	855.50	0.16	-	20 - 22 ft	20.16-22.16 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3881	SSHS-B3881-SUB-20-22	4/18/2021	855.29	855.53	0.24	-	20 - 22 ft	20.24-22.24 ft	180-120245-1	Not Excavated				
Football Field	SSHS-B4012	SSHS-B4012-SUB-20-22	5/21/2021	855.04	855.41	0.37	-	20 - 22 ft	20.37-22.37 ft	180-122085-1	Not Excavated				
Football Field	SSHS-B3876	SSHS-B3876-SUB-20-22	4/2/2021	855.09	855.50	0.41	-	20 - 22 ft	20.41-22.41 ft	180-119462-1	Not Excavated				
Football Field	SSHS-B645A	SSHS-B645A-SUB-20-22	4/18/2021	854.96	855.37	0.41	-	20 - 22 ft	20.41-22.41 ft	180-120245-1	Not Excavated				
Football Field	SSHS-B3878	SSHS-B3878-SUB-20-22	4/5/2021	854.82	855.53	0.71	-	20 - 22 ft	20.71-22.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-20-22	4/8/2021	856.13	856.13	0.00	-	20 - 22 ft	20-22 ft	180-119767-1	Not Excavated	< 0.034 U	< 0.24 UJ	< 0.14 U	< 0.37 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-20-22	4/9/2021	855.85	855.85	0.00	-	20 - 22 ft	20-22 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3858	SSHS-B3858-SUB-20-22	4/10/2021	856.08	856.08	0.00	-	20 - 22 ft	20-22 ft	180-119841-1	Not Excavated				
Football Field	SSHS-B3859	SSHS-B3859-SUB-20-22	4/12/2021	857.14	857.14	0.00	-	20 - 22 ft	20-22 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-20-22	4/13/2021	856.50	856.50	0.00	-	20 - 22 ft	20-22 ft	180-119938-1	Not Excavated	< 0.036 U	< 0.25 UJ	< 0.15 UJ	< 0.39 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-20-22	5/20/2021	855.47	855.47	0.00	-	20 - 22 ft	20-22 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-20-22	4/1/2021	852.54	853.57	1.03	-	20 - 22 ft	21.03-23.03 ft	1801194601	Not Excavated	< 0.038 UT	< 0.26 UT	< 0.16 U	< 0.41 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-22-24	4/9/2021	856.06	856.07	0.01	-	22 - 24 ft	22.01-24.01 ft	180-119815-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-22-24	5/20/2021	855.17	855.25	0.08	-	22 - 24 ft	22.08-24.08 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3877	SSHS-B3877-SUB-22-24	4/11/2021	855.38	855.49	0.11	-	22 - 24 ft	22.11-24.11 ft	180-119861-1	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.44 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-22-24	4/18/2021	855.26	855.36	0.10	-	22 - 24 ft	22.1-24.1 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-22-24	4/20/2021	855.35	855.48	0.13	-	22 - 24 ft	22.13-24.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-22-24	4/19/2021	855.34	855.50	0.16	-	22 - 24 ft	22.16-24.16 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-22-24	4/5/2021	854.82	855.53	0.71	-	22 - 24 ft	22.71-24.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-22-24	4/8/2021	856.13	856.13	0.00	-	22 - 24 ft	22-24 ft	180-119767-1	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-22-24	4/9/2021	855.85	855.85	0.00	-	22 - 24 ft	22-24 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3859	SSHS-B3859-SUB-22-24	4/12/2021	857.14	857.14	0.00	-	22 - 24 ft	22-24 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-22-24	4/13/2021	856.50	856.50	0.00	-	22 - 24 ft	22-24 ft	180-119938-1	Not Excavated	< 0.038 U	< 0.26 UJ	< 0.16 UJ	< 0.41 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-22-24	5/20/2021	855.47	855.47	0.00	-	22 - 24 ft	22-24 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-22-24	4/1/2021	852.54	853.57	1.03	-	22 - 24 ft	23.03-25.03 ft	1801194601	Not Excavated	< 0.038 UT	< 0.26 UT	< 0.16 U	< 0.41 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-24-26	4/9/2021	856.06	856.07	0.01	-	24 - 26 ft	24.01-26.01 ft	180-119815-1	Not Excavated	< 0.035 U	< 0.24 U	< 0.15 U	< 0.38 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-24-26	4/11/2021	855.38	855.49	0.11	-	24 - 26 ft	24.11-26.11 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-24-26	4/18/2021	855.26	855.36	0.10	-	24 - 26 ft	24.1-26.1 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-24-26	4/20/2021	855.35	855.48	0.13	-	24 - 26 ft	24.13-26.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-24-26	4/19/2021	855.34	855.50	0.16	-	24 - 26 ft	24.16-26.16 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-24-26	4/19/2021	854.94	855.38	0.44	-	24 - 26 ft	24.44-26.44 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3878	SSHS-B3878-SUB-24-26	4/5/2021	854.82	855.53	0.71	-	24 - 26 ft	24.71-26.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-24-26	4/8/2021	856.13	856.13	0.00	-	24 - 26 ft	24-26 ft	180-119767-1	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-24-26	4/13/2021	856.50	856.50	0.00	-	24 - 26 ft	24-26 ft	180-119938-1	Not Excavated	< 0.038 U	< 0.27 UJ	< 0.16 UJ	< 0.42 U
Football Field	SSHS-B4010	DUP-202	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B4010	SSHS-B4010-SUB-24-26	5/20/2021	855.47	855.47	0.00	-	24 - 26 ft	24-26 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-24-26	4/1/2021	852.54	853.57	1.03	-	24 - 26 ft	25.03-27.03 ft	1801194601	Not Excavated	< 0.045 UT	< 0.31 UT	< 0.19 U	< 0.49 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-26-28	4/9/2021	856.06	856.07	0.01	-	26 - 28 ft	26.01-28.01 ft	180-119815-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-26-28	4/11/2021	855.38	855.49	0.11	-	26 - 28 ft	26.11-28.11 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-26-28	4/18/2021	855.26	855.36	0.10	-	26 - 28 ft	26.1-28.1 ft	180-120245-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-26-28	4/20/2021	855.35	855.48	0.13	-	26 - 28 ft	26.13-28.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-26-28	4/19/2021	855.34	855.50	0.16	-	26 - 28 ft	26.16-28.16 ft	180-120245-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-26-28	4/5/2021	854.82	855.53	0.71	-	26 - 28 ft	26.71-28.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-26-28	4/8/2021	856.13	856.13	0.00	-	26 - 28 ft	26-28 ft	180-119767-1	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3859	SSHS-B3859-SUB-26-28	4/12/2021	857.14	857.14	0.00	-	26 - 28 ft	26-28 ft	180-119861-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-26-28	4/13/2021	856.50	856.50	0.00	-	26 - 28 ft	26-28 ft	180-119938-1	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-26-28	5/20/2021	855.47	855.47	0.00	-	26 - 28 ft	26-28 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3874	SSHS-B3874-SUB-26-28	4/1/2021	852.54	853.57	1.03	-	26 - 28 ft	27.03-29.03 ft	1801194602	Not Excavated	< 0.045 UT	< 0.31 UT	< 0.19 U	< 0.49 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-28-30	4/9/2021	856.06	856.07	0.01	-	28 - 30 ft	28.01-30.01 ft	180-119815-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-28-30	4/11/2021	855.38	855.49	0.11	-	28 - 30 ft	28.11-30.11 ft	180-119861-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-28-30	4/18/2021	855.26	855.36	0.10	-	28 - 30 ft	28.1-30.1 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-28-30	4/20/2021	855.35	855.48	0.13	-	28 - 30 ft	28.13-30.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-28-30	4/19/2021	855.34	855.50	0.16	-	28 - 30 ft	28.16-30.16 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-28-30	4/5/2021	854.82	855.53	0.71	-	28 - 30 ft	28.71-30.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-28-30	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-20 ft	180-119767-1	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Football Field	SSHS-B3865	DUP-20	4/8/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-119767-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3863	SSHS-B3863-SUB-28-30	4/9/2021	855.85	855.85	0.00	-	28 - 30 ft	28-30 ft	180-119815-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-28-30	4/13/2021	856.50	856.50	0.00	-	28 - 30 ft	28-30 ft	180-119938-1	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B4164	DUP-20	9/23/2021	856.13	856.13	0.00	-	28 - 30 ft	28-30 ft	180-127595-2	Not Excavated				
Football Field	SSHS-B3864	SSHS-B3864-SUB-30-32	4/9/2021	856.06	856.07	0.01	-	30 - 32 ft	30.01-32.01 ft	180-119815-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-30-32	4/11/2021	855.38	855.49	0.11	-	30 - 32 ft	30.11-32.11 ft	180-119861-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-30-32	4/18/2021	855.26	855.36	0.10	-	30 - 32 ft	30.1-32.1 ft	180-120245-1	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-30-32	4/20/2021	855.35	855.48	0.13	-	30 - 32 ft	30.13-32.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-30-32	4/19/2021	855.34	855.50	0.16	-	30 - 32 ft	30.16-32.16 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated			< 130 U	< 0.47 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated			< 120 U	< 0.45 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.027 U	< 0.082 U	< 0.043 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.027 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated			< 120 U							
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated			< 110 U	< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated			< 120 U							
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated			< 130 U	< 0.45 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.081 U	< 0.042 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-120245-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated			< 130 U	< 0.42 U	< 0.028 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated			< 120 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated			< 130 U							
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated			< 110 U	< 0.35 U	< 0.024 U	< 0.027 U	< 0.037 U	< 0.021 U	< 0.064 U	< 0.034 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.027 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	1801194601	Not Excavated	< 140 U			< 0.49 U	< 0.033 U	< 0.037 U	< 0.052 U	< 0.029 U	< 0.089 U	< 0.047 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.41 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.038 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated			< 130 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated			< 130 U							
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated			< 140 U	< 0.45 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.082 U	< 0.043 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated			< 130 U	< 0.46 U	< 0.031 U	< 0.035 U	< 0.049 U	< 0.028 U	< 0.084 U	< 0.044 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.42 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated			< 130 U	< 0.44 U	< 0.029 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.079 U	< 0.041 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.44 U	< 0.03 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated			< 140 U	< 0.5 U	< 0.034 U	< 0.038 U	< 0.052 U	< 0.029 U	< 0.09 U	< 0.047 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.5 U	< 0.034 U	< 0.038 U	< 0.052 U	< 0.03 U	< 0.09 U	< 0.047 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated			< 130 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated			< 34 U	< 0.52 U	< 0.035 U	< 0.039 U	< 0.055 U	< 0.031 U	< 0.094 U	< 0.049 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated			< 34 U							
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated			< 41							
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated			< 40							
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3021	DUP-42	5/17/2021	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 110 U			< 0.36 U	< 0.024 U	< 0.027 U	< 0.038 U	< 0.021 U	< 0.065 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated			< 34 U							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	1801215481	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated			< 42							
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.039 J	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 140 U			< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	0.046 J	< 0.046 U	< 0.026 U	< 0.078 U	< 0.041 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated				< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.072 U	< 0.037 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 100 U			< 0.35 U	< 0.024 U	0.43 B	< 0.037 U	< 0.021 U	< 0.064 U	< 0.033 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.036 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated			< 130 U							
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated		< 33 U								

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.037 U	< 0.039 U	< 0.053 U	< 0.045 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.097 U	< 0.068 U	< 0.064 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.035 U	< 0.038 U	< 0.051 U	< 0.044 U	< 0.1 U	< 0.24 U	< 0.1 U	< 0.094 U	< 0.066 U	< 0.062 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.036 U	< 0.039 U	< 0.052 U	< 0.045 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.067 U	< 0.064 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.082 U	< 0.2 U	< 0.086 U	< 0.077 U	< 0.054 U	< 0.051 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.051 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.093 U	< 0.065 U	< 34 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.064 U	< 34 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 34 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.041 U	< 0.092 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.057 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.04 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.06 U	< 0.057 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.028 U	< 0.03 U	< 0.04 U	< 0.035 U	< 0.079 U	< 0.19 U	< 0.083 U	< 0.074 U	< 0.052 U	< 0.049 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.044 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.066 U	< 0.063 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.039 U	< 0.052 U	< 0.045 U	< 34 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.067 U	< 34 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	1801194601	Not Excavated	< 0.039 U	< 0.041 U	< 0.056 U	< 0.048 U	< 0.11 U	< 0.27 U	< 0.11 U	< 0.10 U	< 0.072 U	< 0.068 UT
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 34 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.034 U	< 0.037 U	< 0.05 U	< 0.043 U	< 0.097 U	< 0.24 U	< 0.1 U	< 0.091 U	< 0.064 U	< 0.06 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated										
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.044 U	< 0.1 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.066 U	< 0.063 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/18/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.036 U	< 0.039 U	< 0.053 U	< 0.045 U	< 34 U	< 0.25 U	< 0.11 U	< 0.096 U	< 0.068 U	< 34 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.04 U	< 34 U	< 0.22 U	< 0.097 U	< 0.087 U	< 0.061 U	< 34 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.097 U	< 0.24 U	< 0.1 U	< 0.091 U	< 0.064 U	< 0.06 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.039 U	< 0.042 U	< 0.056 U	< 0.048 U	< 0.11 U	< 0.27 U	< 0.12 U	< 0.1 U	< 0.072 U	< 0.068 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.039 U	< 0.042 U	< 0.056 U	< 0.048 U	< 34 U	< 0.27 U	< 0.12 U	< 0.1 U	< 0.073 U	< 34 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.041 U	< 0.043 U	< 0.059 U	< 0.05 U	< 34 U	< 0.28 U	< 0.12 U	< 0.11 U	< 0.076 U	< 34 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated										
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated										
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated										
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated										
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated										
Northern Athletic Field	SSHS-B3021	DUP-42	5/17/2021	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.028 U	< 0.030 U	< 0.041 U	< 0.035 U	< 0.080 U	< 0.19 U	< 0.084 U	< 0.075 U	< 0.053 U	< 0.050 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	1801215481	Not Excavated	< 0.034 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.064 U	< 0.061 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated										
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated										
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.035 U	< 0.037 U	0.055 J	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.065 U	< 0.061 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated										
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated										
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated										
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.034 U	< 0.036 U	0.10 J	< 0.042 U	< 0.096 U	< 0.23 U	< 0.10 U	0.15 J	< 0.063 U	< 0.060 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.028 U	< 0.030 U	< 0.040 U	< 0.034 U	< 0.078 U	0.37 BJ	< 0.082 U	< 0.073 U	< 0.052 U	< 0.049 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.030 U	< 0.032 U	< 0.044 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated										
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated										
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated										

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Football Field	SSHS-B3878	SSHS-B3878-SUB-30-32	4/5/2021	854.82	855.53	0.71	-	30 - 32 ft	30.71-32.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-30-32	4/8/2021	856.13	856.13	0.00	-	30 - 32 ft	30-32 ft	180-119767-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-30-32	4/13/2021	856.50	856.50	0.00	-	30 - 32 ft	30-32 ft	180-119938-1	Not Excavated	< 0.044 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3864	SSHS-B3864-SUB-32-34	4/9/2021	856.06	856.07	0.01	-	32 - 34 ft	32.01-34.01 ft	180-119815-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B4009	SSHS-B4009-SUB-32-34	5/20/2021	855.17	855.25	0.08	-	32 - 34 ft	32.08-34.08 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3877	SSHS-B3877-SUB-32-34	4/11/2021	855.38	855.49	0.11	-	32 - 34 ft	32.11-34.11 ft	180-119861-1	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Football Field	SSHS-B3872	SSHS-B3872-SUB-32-34	4/20/2021	855.35	855.48	0.13	-	32 - 34 ft	32.13-34.13 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3870	SSHS-B3870-SUB-32-34	4/18/2021	855.26	855.36	0.10	-	32 - 34 ft	32.1-34.1 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3871	DUP-32	4/19/2021	855.07	855.22	0.15	-	32 - 34 ft	32.15-34.15 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-32-34	4/19/2021	855.34	855.50	0.16	-	32 - 34 ft	32.16-34.16 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B3878	SSHS-B3878-SUB-32-34	4/5/2021	854.82	855.53	0.71	-	32 - 34 ft	32.71-34.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3865	SSHS-B3865-SUB-32-34	4/8/2021	856.13	856.13	0.00	-	32 - 34 ft	32-34 ft	180-119767-2	Not Excavated	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Football Field	SSHS-B3860	SSHS-B3860-SUB-32-34	4/13/2021	856.50	856.50	0.00	-	32 - 34 ft	32-34 ft	180-119938-1	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.43 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-33-35	5/20/2021	855.47	855.47	0.00	-	33 - 35 ft	33-35 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3864	SSHS-B3864-SUB-34-36	4/9/2021	856.06	856.07	0.01	-	34 - 36 ft	34.01-36.01 ft	180-119815-2	Not Excavated	< 0.035 U	< 0.24 U	< 0.14 U	< 0.37 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-34-36	4/11/2021	855.38	855.49	0.11	-	34 - 36 ft	34.11-36.11 ft	180-119861-1	Not Excavated	< 0.044 U	< 0.31 U	< 0.18 U	< 0.48 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-34-36	4/18/2021	855.26	855.36	0.10	-	34 - 36 ft	34.1-36.1 ft	180-120245-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B3874	DUP-33	4/1/2021	855.07	855.22	0.15	-	34 - 36 ft	34.15-36.15 ft	1801194601	Not Excavated	< 0.048 UT	< 0.33 UT	< 0.20 U	< 0.52 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-34-36	4/19/2021	855.34	855.50	0.16	-	34 - 36 ft	34.16-36.16 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.27 U	< 0.16 U	< 0.43 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-34-36	4/19/2021	854.94	855.38	0.44	-	34 - 36 ft	34.44-36.44 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3878	SSHS-B3878-SUB-34-36	4/5/2021	854.82	855.53	0.71	-	34 - 36 ft	34.71-36.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-34-36	4/13/2021	856.50	856.50	0.00	-	34 - 36 ft	34-36 ft	180-119938-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B4010	SSHS-B4010-SUB-35-37	5/20/2021	855.47	855.47	0.00	-	35 - 37 ft	35-37 ft	180-121981-1	Not Excavated				
Football Field	SSHS-B3877	SSHS-B3877-SUB-36-38	4/11/2021	855.38	855.49	0.11	-	36 - 38 ft	36.11-38.11 ft	180-119861-1	Not Excavated	< 0.044 U	< 0.31 U	< 0.18 U	< 0.48 U
Football Field	SSHS-B3870	SSHS-B3870-SUB-36-38	4/19/2021	855.26	855.36	0.10	-	36 - 38 ft	36.1-38.1 ft	180-120245-1	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.49 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-36-37	4/19/2021	855.34	855.50	0.16	-	36 - 37 ft	36.16-37.16 ft	180-120245-1	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.44 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-36-38	4/19/2021	854.94	855.38	0.44	-	36 - 38 ft	36.44-38.44 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3878	SSHS-B3878-SUB-36-38	4/5/2021	854.82	855.53	0.71	-	36 - 38 ft	36.71-38.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3860	SSHS-B3860-SUB-36-38	4/13/2021	856.50	856.50	0.00	-	36 - 38 ft	36-38 ft	180-119938-2	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Football Field	SSHS-B3871	SSHS-B3871-SUB-37-39	4/19/2021	855.34	855.50	0.16	-	37 - 39 ft	37.16-39.16 ft	180-120245-1	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
Football Field	SSHS-B3877	SSHS-B3877-SUB-38-40	4/12/2021	855.38	855.49	0.11	-	38 - 40 ft	38.11-40.11 ft	180-119861-2	Not Excavated	< 0.048 U	< 0.34 U	< 0.2 U	< 0.52 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-38-40	4/19/2021	854.94	855.38	0.44	-	38 - 40 ft	38.44-40.44 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-39-41	4/19/2021	855.34	855.50	0.16	-	39 - 41 ft	39.16-41.16 ft	180-120245-1	Not Excavated	< 0.048 U	< 0.34 U	< 0.2 U	< 0.52 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-40-42	4/19/2021	854.94	855.38	0.44	-	40 - 42 ft	40.44-42.44 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3878	SSHS-B3878-SUB-40-42	4/5/2021	854.82	855.53	0.71	-	40 - 42 ft	40.71-42.71 ft	180-119510-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-41-43	4/19/2021	855.34	855.50	0.16	-	41 - 43 ft	41.16-43.16 ft	180-120245-1	Not Excavated	< 0.05 U	< 0.35 U	< 0.21 U	< 0.55 U
Football Field	SSHS-B3873	SSHS-B3873-SUB-42-44	4/19/2021	854.94	855.38	0.44	-	42 - 44 ft	42.44-44.44 ft	180-120434-1	Not Excavated				
Football Field	SSHS-B3871	SSHS-B3871-SUB-43-45	4/19/2021	855.34	855.50	0.16	-	43 - 45 ft	43.16-45.16 ft	180-120245-2	Not Excavated				
Northern Athletic Field	SSHS-B76	SSHS-B76-10-15 (12.5)	8/14/2014	856.25	857.34	1.09	-	10 - 15 ft	11.09-16.09 ft	180-35818-1	Not Excavated				
Northern Athletic Field	SSHS-B77	SSHS-B77-10-15 (12.5)	8/14/2014	855.88	857.91	2.03	-	10 - 15 ft	12.03-17.03 ft	180-35818-1	Not Excavated				
Northern Athletic Field	SSHS-DW-3A	SSHS-DW-3A-SUB-14-16	6/20/2022	856.66	856.67	0.01	-	14 - 16 ft	14.01-16.01 ft	180-140136-1	Not Excavated				
Northern Athletic Field	SSHS-B3021	DUP-42	5/17/2021	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801217472	Not Excavated	< 0.035 U	< 0.24 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-14-16	9/17/2021	856.64	856.68	0.04	-	14 - 16 ft	14.04-16.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-14-16	5/17/2021	856.37	856.43	0.06	-	14 - 16 ft	14.06-16.06 ft	1801217472	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-DW-06	SSHS-DW-06-SUB-14-16	6/20/2022	856.38	856.44	0.06	-	14 - 16 ft	14.06-16.06 ft	180-140136-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-14-16	9/16/2021	856.07	856.16	0.09	-	14 - 16 ft	14.09-16.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3914	DUP-36	5/12/2021	855.33	855.44	0.11	-	14 - 16 ft	14.11-16.11 ft	1801215481	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-DW-16	SSHS-DW-16-SUB-14-16	6/4/2022	856.27	856.38	0.11	-	14 - 16 ft	14.11-16.11 ft	180-139185-1	Not Excavated				
Northern Athletic Field	SSHS-DW-15	SSHS-DW-15-SUB-14-16	6/4/2022	856.60	856.86	0.26	-	14 - 16 ft	14.26-16.26 ft	180-139185-1	Not Excavated				
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-14-16	5/12/2021	852.28	852.59	0.31	-	14 - 16 ft	14.31-16.31 ft	1801215481	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-12-14	9/2/2016	852.44	854.81	2.37	-	12 - 14 ft	14.37-16.37 ft	180-58309-2	Not Excavated				
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-14-16	5/6/2021	852.20	852.57	0.37	-	14 - 16 ft	14.37-16.37 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-14-16	5/10/2021	853.37	853.81	0.44	-	14 - 16 ft	14.44-16.44 ft	1801214241	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-DW-7_8	SSHS-DW-7_8-SUB-14-16	6/4/2022	856.61	857.29	0.68	-	14 - 16 ft	14.68-16.68 ft	180-139185-1	Not Excavated				
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-14-16	5/11/2021	852.15	852.94	0.79	-	14 - 16 ft	14.79-16.79 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-DW-10_11	SSHS-DW-10_11-SUB-14-16	6/4/2022	856.18	856.99	0.81	-	14 - 16 ft	14.81-16.81 ft	180-139185-1	Not Excavated				
Northern Athletic Field	SSHS-B3917	SSHS-B3917-SUB-14-16	5/12/2021	853.71	854.79	1.08	-	14 - 16 ft	15.08-17.08 ft	1801215482	Not Excavated	< 0.042 U	< 0.29 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/10/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-14-16	5/17/2021	852.29	853.40	1.11	-	14 - 16 ft	15.11-17.11 ft	1801217472	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-16-18	5/13/2021	856.89	856.55	-0.34	-	16 - 18 ft	15.66-17.66 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-16-18	5/14/2021	857.50	857.17	-0.33	-	16 - 18 ft	15.67-17.67 ft	1801217051	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-14-16	5/18/2021	853.77	855.45	1.68	-	14 - 16 ft	15.68-17.68 ft	1801218221	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-12-14	1/20/2021	854.07	857.79	3.72	-	12 - 14 ft	15.72-17.72 ft	1801162471	Not Excavated	< 0.034 U	< 0.24 U	< 0.14 U	< 0.37 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-16-18	5/6/2021	856.75	856.65	-0.10	-	16 - 18 ft	15.9-17.9 ft	1801213101	Not Excavated	< 0.037 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3645A	SSHS-B3645A-SUB-16-18	8/5/2021	856.82	856.75	-0.07	-	16 - 18 ft	15.93-17.93 ft	180-125431-1	Not Excavated				
Northern Athletic Field	SSHS-B3647A	SSHS-B3647A-SUB-16-18	8/5/2021	856.70	856.66	-0.04	-	16 - 18 ft	15.96-17.96 ft	180-125431-1	Not Excavated				
Northern Athletic Field	ST-S1602	SSHS-IRM5A2-ST-S1602	8/25/2022	-	856.46	-	840.43	16 - 18 ft	16.03 ft	1801435261	Not Excavated				

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	1801217051	Not Excavated	< 110 U			< 0.36 U	< 0.025 U	< 0.027 U	< 0.038 U	< 0.022 U	< 0.066 U	< 0.034 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated			< 34 U							
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated			< 110 U							
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated		< 33 U								
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	1801194601	Not Excavated	< 130 U			< 0.45 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.027 U	< 0.081 U	< 0.043 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated		< 31 U								
Northern Athletic Field	S322	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated	< 100 U									
Northern Athletic Field	S307	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated			< 40							
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.046 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated	< 110 U									
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358362	Not Excavated				< 0.049 U	< 0.039 U	0.095 J	< 0.054 U	< 0.049 U	< 0.031 U	< 0.050 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	S323	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated	< 120 U									
Northern Athletic Field	S734	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated	< 110 U									
Northern Athletic Field	S325	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated	< 110 U									
Northern Athletic Field	B710	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated	< 120 U									
Northern Athletic Field	S324	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated			< 110 U							
Northern Athletic Field	S311	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated	< 130 U									
Northern Athletic Field	S328	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	S327	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated			< 110 U							
Northern Athletic Field	S326	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	S306	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated				< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.075 U	< 0.039 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	S309	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated	< 230 U									
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated		< 36 U								
Northern Athletic Field	B709	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated	< 130 U									
Northern Athletic Field	S735	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated	< 120 U									
Northern Athletic Field	S726	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated	< 110 U									
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated	< 110 U									
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334582	Not Excavated				< 0.051 U	< 0.040 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated	< 130 U									
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347852	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U	< 0.056 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated		< 31 U								
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated	< 120 U									
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354283	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U	< 0.056 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated		< 35 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508422	Not Excavated				< 0.057 U	< 0.045 U	< 0.055 U	< 0.062 U	< 0.057 U	< 0.036 U	< 0.058 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated		< 32 U								
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated		< 32 U								
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated		< 31 U								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated	< 110 U									
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated		< 30 U								
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated	< 110 U									
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335312	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.035 U	< 0.057 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated		< 33 U								
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated	< 110 U									
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345572	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 U	< 0.054 U	< 0.049 U	< 0.031 U	< 0.050 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated	< 110 U									
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	B718	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated		< 34 U								
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated	< 110 U									

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	1801217051	Not Excavated	< 0.028 U	< 0.030 U	< 0.041 U	< 0.035 U	< 0.080 U	< 0.20 U	< 0.084 U	< 0.076 U	< 0.053 U	< 0.050 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.082 U	< 0.20 U	< 0.086 U	< 0.077 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated										
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	1801194601	Not Excavated	< 0.035 U	< 0.038 U	< 0.051 U	< 0.044 U	< 0.10 U	< 0.24 U	< 0.10 U	< 0.094 U	< 0.066 U	< 0.062 UT
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated										
Northern Athletic Field	S322	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated										
Northern Athletic Field	S307	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated										
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated										
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated										
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358362	Not Excavated	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	< 0.044 U	< 0.055 U	< 0.042 U	< 0.038 U	< 0.022 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	S323	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated										
Northern Athletic Field	S734	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated										
Northern Athletic Field	S325	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated										
Northern Athletic Field	B710	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated										
Northern Athletic Field	S324	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated										
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated										
Northern Athletic Field	S311	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated										
Northern Athletic Field	S328	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated										
Northern Athletic Field	S327	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated										
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated										
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated										
Northern Athletic Field	S326	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated										
Northern Athletic Field	S306	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated										
Northern Athletic Field	S309	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated										
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	0.057 J	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	0.089 J	< 0.057 U	< 0.054 UT
Northern Athletic Field	S308	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated										
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated										
Northern Athletic Field	B709	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated										
Northern Athletic Field	S735	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated										
Northern Athletic Field	S726	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated										
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated										
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334582	Not Excavated	< 0.040 U	< 0.031 U	< 0.033 U	< 0.023 U	< 0.035 U	< 0.046 U	< 0.056 U	< 0.044 U	< 0.039 U	< 0.022 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated										
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347852	Not Excavated	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U	< 0.042 U	< 0.024 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated										
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated										
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354283	Not Excavated	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	< 0.049 U	< 0.060 U	< 0.047 U	< 0.042 U	< 0.024 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508422	Not Excavated	< 0.045 U	< 0.034 U	0.047 J	< 0.026 U	< 0.039 U	< 0.051 U	< 0.063 U	0.12 J	< 0.044 U	< 0.025 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated										
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated										
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.032 U	< 0.034 U	0.055 J	< 0.039 U	< 0.089 U	< 0.22 U	0.096 J	< 0.084 U	< 0.059 U	< 0.056 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated										
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated										
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated										
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated										
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated										
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335312	Not Excavated	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.050 U	< 0.061 U	< 0.047 U	< 0.043 U	< 0.024 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated										
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated										
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated										
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345572	Not Excavated	< 0.039 U	< 0.030 U	< 0.032 U	< 0.023 U	< 0.034 U	0.048 J	< 0.055 U	< 0.042 U	< 0.038 U	< 0.022 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated										
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated										
Northern Athletic Field	B718	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated										
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated										
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated										

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Northern Athletic Field	SSHS-B3899	DUP-21	5/14/2021	855.30	855.33	0.03	-	16 - 18 ft	16.03-18.03 ft	1801217051	Not Excavated	< 0.035 U	< 0.25 U	< 0.15 U	< 0.38 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-16-18	9/17/2021	856.64	856.68	0.04	-	16 - 18 ft	16.04-18.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3921	SSHS-B3921-SUB-16-18	5/17/2021	856.37	856.43	0.06	-	16 - 18 ft	16.06-18.06 ft	1801217472	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-16-18	9/16/2021	856.07	856.16	0.09	-	16 - 18 ft	16.09-18.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	ST-S1600	SSHS-IRM5A2-ST-S1600	8/25/2022	-	856.47	-	840.37	16 - 18 ft	16.1 ft	1801435261	Not Excavated				
Northern Athletic Field	SSHS-B3867	DUP-22	4/1/2021	855.33	855.47	0.14	-	16 - 18 ft	16.14-18.14 ft	1801194601	Not Excavated	< 0.044 UT	< 0.30 UT	< 0.18 U	< 0.47 U
Northern Athletic Field	ST-S1603	SSHS-IRM5A2-ST-S1603	8/25/2022	-	856.50	-	840.22	16 - 18 ft	16.28 ft	1801435261	Not Excavated				
Northern Athletic Field	S322	SSHS-IRM5A2-S322	3/18/2022	-	857.20	-	840.88	16 - 18 ft	16.33 ft	1801354282	Not Excavated				
Northern Athletic Field	S307	SSHS-IRM5A2-S307	2/9/2022	-	856.28	-	839.92	16 - 18 ft	16.36 ft	1801334581	Not Excavated				
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-14-16	9/2/2016	852.44	854.81	2.37	-	14 - 16 ft	16.37-18.37 ft	180-58309-2	Not Excavated				
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-16-18	5/6/2021	852.20	852.57	0.37	-	16 - 18 ft	16.37-18.37 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358361	Not Excavated				
Northern Athletic Field	S733	SSHS-IRM5A2-S733	3/28/2022	-	856.63	-	840.21	16 - 18 ft	16.42 ft	1801358362	Not Excavated	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-16-18	5/10/2021	853.37	853.81	0.44	-	16 - 18 ft	16.44-18.44 ft	1801214241	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	S323	SSHS-IRM5A2-S323	3/18/2022	-	857.56	-	841.03	16 - 18 ft	16.53 ft	1801354282	Not Excavated				
Northern Athletic Field	S734	SSHS-IRM5A2-S734	3/28/2022	-	857.23	-	840.49	16 - 18 ft	16.74 ft	1801358361	Not Excavated				
Northern Athletic Field	S325	SSHS-IRM5A2-S325	3/2/2022	-	857.86	-	841.09	16 - 18 ft	16.76 ft	1801345571	Not Excavated				
Northern Athletic Field	B710	SSHS-IRM5A2-B710	3/18/2022	-	856.15	-	839.39	16 - 18 ft	16.76 ft	1801354281	Not Excavated				
Northern Athletic Field	S324	SSHS-IRM5A2-S324	3/2/2022	-	858.03	-	841.26	16 - 18 ft	16.78 ft	1801345571	Not Excavated				
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-16-18	5/11/2021	852.15	852.94	0.79	-	16 - 18 ft	16.79-18.79 ft	180-121474-1	Not Excavated				
Northern Athletic Field	S311	SSHS-IRM5A2-S311	2/9/2022	-	856.54	-	839.70	16 - 18 ft	16.84 ft	1801334581	Not Excavated				
Northern Athletic Field	S328	SSHS-IRM5A2-S328	2/9/2022	-	857.54	-	840.68	16 - 18 ft	16.86 ft	1801334581	Not Excavated				
Northern Athletic Field	S327	SSHS-IRM5A2-S327	2/9/2022	-	857.79	-	840.90	16 - 18 ft	16.89 ft	1801334581	Not Excavated				
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-16-18	9/17/2021	857.91	857.91	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated				
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-16-18	9/22/2021	856.72	856.72	0.00	-	16 - 18 ft	16-18 ft	180-127415-1	Not Excavated				
Northern Athletic Field	S326	SSHS-IRM5A2-S326	2/9/2022	-	857.83	-	840.78	16 - 18 ft	17.04 ft	1801334581	Not Excavated				
Northern Athletic Field	S306	SSHS-IRM5A2-S306	2/9/2022	-	857.47	-	840.39	16 - 18 ft	17.08 ft	1801334581	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/10/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-16-18	5/17/2021	852.29	853.40	1.11	-	16 - 18 ft	17.11-19.11 ft	1801217472	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	S309	SSHS-IRM5A2-DUP41	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated				
Northern Athletic Field	S309	SSHS-IRM5A2-S309	2/9/2022	-	856.84	-	839.72	16 - 18 ft	17.13 ft	1801334581	Not Excavated				
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-16-18	4/1/2021	855.62	856.75	1.13	-	16 - 18 ft	17.13-19.13 ft	1801194601	Not Excavated	< 0.038 UT	< 0.27 UT	< 0.16 U	< 0.42 U
Northern Athletic Field	S308	SSHS-IRM5A2-S308	2/9/2022	-	856.85	-	839.63	16 - 18 ft	17.22 ft	1801334581	Not Excavated				
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-16-18	1/19/2023	853.43	854.71	1.28	-	16 - 18 ft	17.28-19.28 ft	1801508421	Not Excavated				
Northern Athletic Field	B709	SSHS-IRM5A2-B709	3/18/2022	-	857.35	-	840.02	16 - 18 ft	17.33 ft	1801354281	Not Excavated				
Northern Athletic Field	S735	SSHS-IRM5A2-S735	3/28/2022	-	857.59	-	840.24	16 - 18 ft	17.35 ft	1801358361	Not Excavated				
Northern Athletic Field	S726	SSHS-IRM5A2-S726	2/10/2022	-	856.66	-	839.16	16 - 18 ft	17.5 ft	1801335311	Not Excavated				
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334581	Not Excavated				
Northern Athletic Field	S310	SSHS-IRM5A2-S310	2/9/2022	-	857.06	-	839.54	16 - 18 ft	17.52 ft	1801334582	Not Excavated	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347851	Not Excavated				
Northern Athletic Field	B713	SSHS-IRM5A2-B713	3/5/2022	-	856.85	-	839.31	16 - 18 ft	17.55 ft	1801347852	Not Excavated	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	ST-S1808	SSHS-IRM5A2-ST-S1808	8/25/2022	-	856.43	-	838.85	16 - 18 ft	17.58 ft	1801435291	Not Excavated				
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354281	Not Excavated				
Northern Athletic Field	B708	SSHS-IRM5A2-B708	3/18/2022	-	857.46	-	839.87	16 - 18 ft	17.59 ft	1801354283	Not Excavated	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-16-18	1/19/2023	853.38	855.00	1.62	-	16 - 18 ft	17.62-19.62 ft	1801508422	Not Excavated	< 0.050 U	< 0.042 U	< 0.032 U	< 0.027 U
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-DUP208	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated				
Northern Athletic Field	ST-S1804	SSHS-IRM5A2-ST-S1804	8/25/2022	-	856.29	-	838.66	16 - 18 ft	17.64 ft	1801435291	Not Excavated				
Northern Athletic Field	ST-S1807	SSHS-IRM5A2-ST-S1807	8/25/2022	-	856.41	-	838.75	16 - 18 ft	17.65 ft	1801435291	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-18-20	5/13/2021	856.89	856.55	-0.34	-	18 - 20 ft	17.66-19.66 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-14-16	1/22/2021	853.65	857.32	3.67	-	14 - 16 ft	17.67-19.67 ft	1801163651	Not Excavated				
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-18-20	5/14/2021	857.50	857.17	-0.33	-	18 - 20 ft	17.67-19.67 ft	1801217051	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-16-18	5/18/2021	853.77	855.45	1.68	-	16 - 18 ft	17.68-19.68 ft	1801218221	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	S736	SSHS-IRM5A2-S736	3/2/2022	-	858.03	-	840.34	16 - 18 ft	17.69 ft	1801345571	Not Excavated				
Northern Athletic Field	ST-S1809	SSHS-IRM5A2-ST-S1809	8/25/2022	-	856.36	-	838.64	16 - 18 ft	17.72 ft	1801435291	Not Excavated				
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-14-16	1/20/2021	854.07	857.79	3.72	-	14 - 16 ft	17.72-19.72 ft	1801162471	Not Excavated				
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335311	Not Excavated				
Northern Athletic Field	S728	SSHS-IRM5A2-S728	2/10/2022	-	856.97	-	839.21	16 - 18 ft	17.77 ft	1801335312	Not Excavated	< 0.049 U	< 0.040 U	< 0.031 U	< 0.027 U
Northern Athletic Field	S725	SSHS-IRM5A2-S725	2/10/2022	-	857.14	-	839.36	16 - 18 ft	17.78 ft	1801335311	Not Excavated				
Northern Athletic Field	ST-S1800	SSHS-IRM5A2-ST-S1800	8/25/2022	-	856.37	-	838.58	16 - 18 ft	17.79 ft	1801435291	Not Excavated				
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345571	Not Excavated				
Northern Athletic Field	S737	SSHS-IRM5A2-S737	3/2/2022	-	857.77	-	839.96	16 - 18 ft	17.8 ft	1801345572	Not Excavated	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
Northern Athletic Field	B715	SSHS-IRM5A2-B715	3/5/2022	-	857.44	-	839.61	16 - 18 ft	17.83 ft	1801347851	Not Excavated				
Northern Athletic Field	B718	SSHS-IRM5A2-DUP43	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated				
Northern Athletic Field	B718	SSHS-IRM5A2-B718	2/10/2022	-	857.07	-	839.23	16 - 18 ft	17.84 ft	1801335311	Not Excavated				
Northern Athletic Field	ST-S1805	SSHS-IRM5A2-ST-S1805	8/25/2022	-	856.39	-	838.55	16 - 18 ft	17.84 ft	1801435291	Not Excavated				
Northern Athletic Field	S729	SSHS-IRM5A2-DUP42	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated				

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	S729	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	180133531	Not Excavated	< 110 U									
Northern Athletic Field	B717	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated	< 120 U									
Northern Athletic Field	B716	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated	< 120 U									
Northern Athletic Field	S727	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	180133531	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 120 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated		< 32 U								
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435292	Not Excavated				< 0.048 U	< 0.038 U	< 0.046 U	< 0.052 U	< 0.048 U	< 0.030 U	< 0.049 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated		< 31 U								
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated		< 31 U								
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435292	Not Excavated				< 0.047 U	< 0.037 U	< 0.045 U	< 0.050 U	< 0.047 U	< 0.029 U	< 0.048 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated			< 110 U							
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated		< 34 U								
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436172	Not Excavated				< 0.055 U	< 0.044 U	< 0.053 U	< 0.060 U	< 0.055 U	< 0.034 U	< 0.056 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335511	Not Excavated	< 110 U									
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated		< 35 U								
Northern Athletic Field	S740	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	1801213101	Not Excavated	< 130 U			< 0.42 U	< 0.029 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated	< 130 U									
Northern Athletic Field	B721	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated	< 130 U									
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated		< 37 U								
Northern Athletic Field	B720	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated		< 34 U								
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated		< 34 U								
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436172	Not Excavated				< 0.054 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.054 U	< 0.034 U	< 0.055 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated	< 120 U									
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated		< 32 U								
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 130 U			< 0.42 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	0.039 BJ	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated			< 41							
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	0.041 J	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated	< 110 U									
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335312	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.056 U	< 0.052 U	< 0.032 U	< 0.053 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated				< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated		< 36 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508422	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.058 U	< 0.053 U	< 0.033 U	< 0.055 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 110 U			< 0.42 U	< 0.028 U	0.36 B	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 120 U			< 0.42 U	< 0.028 U	0.39 B	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	0.46 B	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 120 U			< 0.42 U	< 0.029 U	< 0.032 U	< 0.044 U	< 0.025 U	< 0.076 U	< 0.040 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	0.035 J	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 110 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated	< 120 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated				< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated		< 31 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508422	Not Excavated				< 0.053 U	< 0.042 U	< 0.051 U	< 0.057 U	< 0.053 U	< 0.033 U	< 0.054 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.029 U	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 110 U			< 0.39 U	< 0.026 U	0.47 B	< 0.041 U	< 0.023 U	< 0.070 U	< 0.037 U

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	S729	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	180133531	Not Excavated										
Northern Athletic Field	B717	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated										
Northern Athletic Field	B716	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated										
Northern Athletic Field	S727	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	180133531	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated										
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435292	Not Excavated	< 0.038 U	0.029 J	0.050 J	< 0.022 U	< 0.033 U	0.085 J	0.088 J	0.072 J	< 0.037 U	< 0.021 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated										
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated										
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435292	Not Excavated	< 0.037 U	< 0.028 U	< 0.030 U	< 0.021 U	< 0.032 U	0.060 J	< 0.051 U	< 0.040 U	< 0.036 U	< 0.020 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated										
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436172	Not Excavated	< 0.044 U	< 0.033 U	< 0.036 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.061 U	< 0.047 U	< 0.042 U	< 0.024 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335511	Not Excavated										
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated										
Northern Athletic Field	S740	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated										
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	1801213101	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.093 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated										
Northern Athletic Field	B721	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated										
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated										
Northern Athletic Field	B720	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated										
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated										
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated										
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436172	Not Excavated	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.037 U	0.056 J	< 0.060 U	< 0.046 U	< 0.042 U	< 0.024 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated										
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated										
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.082 U	< 0.20 U	< 0.086 U	< 0.077 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated										
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.031 U	< 0.034 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated										
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335312	Not Excavated	< 0.041 U	< 0.031 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.057 U	< 0.044 U	< 0.040 U	< 0.023 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated										
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508422	Not Excavated	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.037 U	< 0.048 U	< 0.059 U	< 0.046 U	< 0.041 U	< 0.023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.093 U	< 0.23 U	< 0.097 U	< 0.087 U	< 0.061 U	< 0.058 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.033 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.061 U	< 0.057 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	0.49 BJ	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.033 U	< 0.035 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.098 U	< 0.088 U	< 0.062 U	< 0.058 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.059 U	< 0.056 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.030 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508422	Not Excavated	< 0.042 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U	< 0.041 U	< 0.023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.030 U	< 0.032 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.090 U	< 0.22 U	< 0.094 U	< 0.084 U	< 0.059 U	< 0.056 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.032 U	< 0.034 UT	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.030 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.086 U	< 0.21 U	< 0.090 U	< 0.081 U	< 0.057 U	< 0.053 U

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Northern Athletic Field	S729	SSHS-IRM5A2-S729	2/10/2022	-	857.05	-	839.20	16 - 18 ft	17.85 ft	1801335311	Not Excavated				
Northern Athletic Field	B717	SSHS-IRM5A2-B717	3/5/2022	-	857.52	-	839.67	16 - 18 ft	17.85 ft	1801347851	Not Excavated				
Northern Athletic Field	B716	SSHS-IRM5A2-B716	3/5/2022	-	857.04	-	839.17	16 - 18 ft	17.87 ft	1801347851	Not Excavated				
Northern Athletic Field	S727	SSHS-IRM5A2-S727	2/10/2022	-	857.07	-	839.16	16 - 18 ft	17.91 ft	1801335311	Not Excavated				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-18-20	5/6/2021	856.75	856.65	-0.10	-	18 - 20 ft	17.9-19.9 ft	1801213101	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435291	Not Excavated				
Northern Athletic Field	ST-S1802	SSHS-IRM5A2-ST-S1802	8/25/2022	-	856.49	-	838.54	16 - 18 ft	17.95 ft	1801435292	Not Excavated	< 0.042 U	< 0.035 U	< 0.027 U	< 0.023 U
Northern Athletic Field	ST-S1801	SSHS-IRM5A2-ST-S1801	8/25/2022	-	856.43	-	838.47	16 - 18 ft	17.96 ft	1801435291	Not Excavated				
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435291	Not Excavated				
Northern Athletic Field	ST-S1806	SSHS-IRM5A2-ST-S1806	8/25/2022	-	856.53	-	838.52	16 - 18 ft	18.01 ft	1801435292	Not Excavated	< 0.041 U	< 0.034 U	< 0.026 U	< 0.022 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-18-20	9/17/2021	856.64	856.68	0.04	-	18 - 20 ft	18.04-20.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-18-20	9/16/2021	856.07	856.16	0.09	-	18 - 20 ft	18.09-20.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436171	Not Excavated				
Northern Athletic Field	ST-B1800	SSHS-IRM5A2-ST-B1800	8/26/2022	-	856.37	-	838.27	18 - 20 ft	18.11 ft	1801436172	Not Excavated	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	S738	SSHS-IRM5A2-S738	2/10/2022	-	857.51	-	839.39	18 - 20 ft	18.12 ft	1801335311	Not Excavated				
Northern Athletic Field	ST-B1803	SSHS-IRM5A2-ST-B1803	8/26/2022	-	856.44	-	838.31	18 - 20 ft	18.13 ft	1801436171	Not Excavated				
Northern Athletic Field	S740	SSHS-IRM5A2-S740	2/10/2022	-	857.67	-	839.53	18 - 20 ft	18.14 ft	1801335311	Not Excavated				
Northern Athletic Field	SSHS-B3907	DUP-29	5/6/2021	855.33	855.47	0.14	-	18 - 20 ft	18.14-20.14 ft	1801213101	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.44 U
Northern Athletic Field	B714	SSHS-IRM5A2-B714	3/5/2022	-	857.26	-	839.11	18 - 20 ft	18.15 ft	1801347851	Not Excavated				
Northern Athletic Field	B721	SSHS-IRM5A2-B721	2/10/2022	-	857.36	-	839.18	18 - 20 ft	18.18 ft	1801335311	Not Excavated				
Northern Athletic Field	ST-B1801	SSHS-IRM5A2-ST-B1801	8/26/2022	-	856.41	-	838.20	18 - 20 ft	18.21 ft	1801436171	Not Excavated				
Northern Athletic Field	B720	SSHS-IRM5A2-B720	2/10/2022	-	857.25	-	839.02	18 - 20 ft	18.23 ft	1801335311	Not Excavated				
Northern Athletic Field	ST-B1802	SSHS-IRM5A2-ST-B1802	8/26/2022	-	856.47	-	838.24	18 - 20 ft	18.23 ft	1801436171	Not Excavated				
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436171	Not Excavated				
Northern Athletic Field	ST-B1804	SSHS-IRM5A2-ST-B1804	8/26/2022	-	856.38	-	838.14	18 - 20 ft	18.25 ft	1801436172	Not Excavated	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	S739	SSHS-IRM5A2-S739	2/10/2022	-	857.65	-	839.36	18 - 20 ft	18.28 ft	1801335311	Not Excavated				
Northern Athletic Field	ST-S1803	SSHS-IRM5A2-ST-S1803	8/25/2022	-	856.47	-	838.15	18 - 20 ft	18.31 ft	1801435291	Not Excavated				
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-18-20	5/12/2021	852.28	852.59	0.31	-	18 - 20 ft	18.31-20.31 ft	1801215481	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3015A	SSHS-B3015A-SUB-16-18	1/23/2021	853.60	855.95	2.35	-	16 - 18 ft	18.35-20.35 ft	1801164042	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B572A	SSHS-B572A-SUB-16-18	9/2/2016	852.44	854.81	2.37	-	16 - 18 ft	18.37-20.37 ft	180-58309-2	Not Excavated				
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-18-20	5/6/2021	852.20	852.57	0.37	-	18 - 20 ft	18.37-20.37 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-18-20	5/10/2021	853.37	853.81	0.44	-	18 - 20 ft	18.44-20.44 ft	1801214241	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335311	Not Excavated				
Northern Athletic Field	B719	SSHS-IRM5A2-B719	2/10/2022	-	857.53	-	839.07	18 - 20 ft	18.46 ft	1801335312	Not Excavated	< 0.045 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-18-20	5/11/2021	852.15	852.94	0.79	-	18 - 20 ft	18.79-20.79 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B4162	SSHS-B4162-SUB-18-20	9/17/2021	857.91	857.91	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated				
Northern Athletic Field	SSHS-B4163	SSHS-B4163-SUB-18-20	9/22/2021	856.72	856.72	0.00	-	18 - 20 ft	18-20 ft	180-127415-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/10/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-18-20	5/17/2021	852.29	853.40	1.11	-	18 - 20 ft	19.11-21.11 ft	1801217472	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-18-20	4/1/2021	855.62	856.75	1.13	-	18 - 20 ft	19.13-21.13 ft	1801194601	Not Excavated	< 0.040 UT	< 0.28 UT	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-18-20	1/19/2023	853.43	854.71	1.28	-	18 - 20 ft	19.28-21.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-18-20	1/19/2023	853.38	855.00	1.62	-	18 - 20 ft	19.62-21.62 ft	1801508422	Not Excavated	< 0.047 U	< 0.039 U	< 0.030 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-20-22	5/13/2021	856.89	856.55	-0.34	-	20 - 22 ft	19.66-21.66 ft	1801217041	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3454	SSHS-B3454-SUB-16-18	1/22/2021	853.65	857.32	3.67	-	16 - 18 ft	19.67-21.67 ft	1801163651	Not Excavated	< 0.041 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-20-22	5/14/2021	857.50	857.17	-0.33	-	20 - 22 ft	19.67-21.67 ft	1801217051	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-18-20	5/18/2021	853.77	855.45	1.68	-	18 - 20 ft	19.68-21.68 ft	1801218221	Not Excavated	< 0.037 U	< 0.26 U	< 0.16 U	< 0.40 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-16-18	1/22/2021	854.14	857.83	3.69	-	16 - 18 ft	19.69-21.69 ft	1801163651	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3554	SSHS-B3554-SUB-16-18	1/20/2021	854.07	857.79	3.72	-	16 - 18 ft	19.72-21.72 ft	1801162471	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-20-22	5/6/2021	856.75	856.65	-0.10	-	20 - 22 ft	19.9-21.9 ft	1801213101	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-20-22	9/17/2021	856.64	856.68	0.04	-	20 - 22 ft	20.04-22.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-20-22	9/16/2021	856.07	856.16	0.09	-	20 - 22 ft	20.09-22.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-20-22	5/12/2021	852.28	852.59	0.31	-	20 - 22 ft	20.31-22.31 ft	1801215481	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-20-22	5/6/2021	852.20	852.57	0.37	-	20 - 22 ft	20.37-22.37 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-20-22	5/10/2021	853.37	853.81	0.44	-	20 - 22 ft	20.44-22.44 ft	1801214241	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-20-22	5/11/2021	852.15	852.94	0.79	-	20 - 22 ft	20.79-22.79 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/10/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-20-22	5/17/2021	852.29	853.40	1.11	-	20 - 22 ft	21.11-23.11 ft	1801217472	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-20-22	4/1/2021	855.62	856.75	1.13	-	20 - 22 ft	21.13-23.13 ft	1801194601	Not Excavated	< 0.039 UT	< 0.27 UT	< 0.16 UT	< 0.42 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-20-22	1/19/2023	853.43	854.71	1.28	-	20 - 22 ft	21.28-23.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-20-22	1/19/2023	853.38	855.00	1.62	-	20 - 22 ft	21.62-23.62 ft	1801508422	Not Excavated	< 0.046 U	< 0.038 U	< 0.030 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-22-24	5/13/2021	856.89	856.55	-0.34	-	22 - 24 ft	21.66-23.66 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-22-24	5/14/2021	857.50	857.17	-0.33	-	22 - 24 ft	21.67-23.67 ft	1801217051	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3883	DUP-43	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.43 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-20-22	5/19/2021	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801219031	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3265A	SSHS-B3265A-SUB-18-20	1/22/2021	854.14	857.83	3.69	-	18 - 20 ft	21.69-23.69 ft	1801163651	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated			< 110 UJ							
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 130 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	0.031 J	< 0.042 U	< 0.024 U	< 0.072 U	< 0.037 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated	< 110 U									
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated				< 0.43 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.040 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 110 U			< 0.38 U	< 0.025 U	< 0.028 U	< 0.040 U	< 0.022 U	< 0.068 U	< 0.036 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated		< 32 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508422	Not Excavated				< 0.052 U	< 0.041 U	< 0.050 U	< 0.057 U	< 0.052 U	< 0.033 U	< 0.054 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 120 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 110 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated			< 110 UJ							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated	< 130 U									
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.044 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 120 U			< 0.43 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.077 U	< 0.040 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 120 U			< 0.39 U	< 0.026 U	< 0.030 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated				< 0.46 U	< 0.031 U	< 0.035 U	< 0.048 U	< 0.027 U	< 0.083 U	< 0.043 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated		< 34 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508422	Not Excavated				< 0.055 U	< 0.043 U	< 0.052 U	< 0.059 U	< 0.055 U	< 0.034 U	< 0.056 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 110 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.073 U	< 0.038 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.068 U	< 0.035 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 110 U			< 0.39 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 120 U			< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.025 U	< 0.075 U	< 0.039 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated			< 110 UJ							
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 130 U			< 0.45 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.081 U	< 0.042 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.033 U	< 0.046 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 130 U			< 0.45 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.082 U	< 0.043 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated		< 33 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated		< 36 U								
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508422	Not Excavated				< 0.059 U	< 0.046 U	< 0.056 U	< 0.063 U	< 0.059 U	< 0.037 U	< 0.060 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 110 U			< 0.38 U	< 0.026 U	< 0.029 U	< 0.040 U	< 0.023 U	< 0.069 U	< 0.036 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 150 U			< 0.48 U	< 0.032 U	< 0.036 U	< 0.050 U	< 0.028 U	< 0.086 U	< 0.045 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 110 U			< 0.37 U	< 0.025 U	< 0.028 U	< 0.039 U	< 0.022 U	< 0.067 U	< 0.035 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 120 U			< 0.40 U	< 0.027 U	< 0.030 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 130 U			< 0.44 U	< 0.030 U	< 0.034 U	< 0.047 U	< 0.026 U	< 0.080 U	< 0.042 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 140 U			< 0.50 U	< 0.034 U	< 0.038 U	< 0.052 U	< 0.029 U	< 0.090 U	< 0.047 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated		< 33 U								
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 130 U			< 0.47 U	< 0.032 U	< 0.036 U	< 0.050 U	< 0.028 U	< 0.085 U	< 0.045 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 130 U			< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 130 U			< 0.43 U	< 0.029 U	< 0.033 U	< 0.045 U	< 0.026 U	< 0.078 U	< 0.041 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated		< 37 U								
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated			< 120 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated			< 110 UJ							
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated			< 110 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated			< 120 U							

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.031 U	< 0.034 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.084 U	< 0.059 U	< 0.055 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.033 U	< 0.036 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.099 U	< 0.088 U	< 0.062 U	< 0.059 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.037 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508422	Not Excavated	< 0.041 U	< 0.032 U	< 0.034 U	< 0.024 U	< 0.036 U	< 0.047 U	< 0.058 U	< 0.045 U	< 0.040 U	< 0.023 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.085 U	< 0.21 U	< 0.089 U	< 0.080 U	< 0.056 U	< 0.053 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.032 U	< 0.034 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.040 U	< 0.090 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.060 U	< 0.056 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated										
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.092 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.033 U	< 0.036 U	< 0.048 U	< 0.041 U	< 0.094 U	< 0.23 U	< 0.099 U	< 0.089 U	< 0.062 U	< 0.059 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 0.054 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated										
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.045 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.067 U	< 0.063 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.088 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.035 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.064 U	< 0.061 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508422	Not Excavated	< 0.043 U	< 0.033 U	< 0.035 U	< 0.025 U	< 0.038 U	< 0.049 U	< 0.060 U	< 0.047 U	< 0.042 U	< 0.024 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.035 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.064 U	< 0.061 UT
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.031 U	< 0.034 U	< 0.046 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.059 U	< 0.055 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.055 U	< 0.052 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 0.087 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 0.054 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.032 U	< 0.035 U	< 0.047 U	< 0.040 U	< 0.091 U	< 0.22 U	< 0.096 U	< 0.086 U	< 0.060 U	< 0.057 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.035 U	< 0.037 U	< 0.051 U	< 0.043 U	< 0.099 U	< 0.24 U	< 0.10 U	< 0.093 U	< 0.065 U	< 0.061 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.034 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.097 U	< 0.24 U	< 0.10 U	< 0.091 U	< 0.064 U	< 0.061 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.036 U	< 0.038 U	< 0.052 U	< 0.044 U	< 0.10 U	< 0.25 U	< 0.11 U	< 0.095 U	< 0.066 U	< 0.063 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508422	Not Excavated	< 0.046 U	< 0.035 U	< 0.038 U	< 0.027 U	< 0.040 U	< 0.052 U	< 0.065 U	< 0.050 U	< 0.045 U	< 0.026 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.030 U	< 0.032 U	< 0.043 U	< 0.037 U	< 0.084 U	< 0.21 U	< 0.088 U	< 0.079 U	< 0.055 U	< 0.052 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.037 U	< 0.040 U	< 0.054 U	< 0.046 U	< 0.11 U	< 0.26 U	< 0.11 U	< 0.099 U	< 0.069 U	< 0.066 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.029 U	< 0.031 U	< 0.042 U	< 0.036 U	< 0.083 U	< 0.20 U	< 0.087 U	< 0.078 U	< 0.054 U	< 0.051 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 0.089 U	< 0.22 U	< 0.093 U	< 0.083 U	< 0.058 U	< 0.055 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.035 U	< 0.037 U	< 0.050 U	< 0.043 U	< 0.098 U	< 0.24 U	< 0.10 U	< 0.092 U	< 0.065 U	< 0.061 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.039 U	< 0.042 U	< 0.056 U	< 0.048 U	< 0.11 U	< 0.27 U	< 0.12 U	< 0.10 U	< 0.072 U	< 0.068 UT
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.037 U	< 0.040 U	< 0.054 U	< 0.046 U	< 0.10 U	< 0.26 U	< 0.11 U	< 0.098 U	< 0.069 U	< 0.065 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.10 U	< 0.089 U	< 0.063 U	< 0.059 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated										
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 0.095 U	< 0.23 U	< 0.10 U	< 0.089 U	< 0.063 U	< 0.059 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated										
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated										
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated										

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-22-24	5/6/2021	856.75	856.65	-0.10	-	22 - 24 ft	21.9-23.9 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-22-24	9/17/2021	856.64	856.68	0.04	-	22 - 24 ft	22.04-24.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-22-24	9/16/2021	856.07	856.16	0.09	-	22 - 24 ft	22.09-24.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-22-24	5/12/2021	852.28	852.59	0.31	-	22 - 24 ft	22.31-24.31 ft	1801215481	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-22-24	5/6/2021	852.20	852.57	0.37	-	22 - 24 ft	22.37-24.37 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-22-24	5/10/2021	853.37	853.81	0.44	-	22 - 24 ft	22.44-24.44 ft	1801214241	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-22-24	5/11/2021	852.15	852.94	0.79	-	22 - 24 ft	22.79-24.79 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-23	5/10/2021	852.29	853.40	1.11	-	22 - 23 ft	23.11-24.11 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-22-24	5/17/2021	852.29	853.40	1.11	-	22 - 24 ft	23.11-25.11 ft	1801217472	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-22-24	4/1/2021	855.62	856.75	1.13	-	22 - 24 ft	23.13-25.13 ft	1801194601	Not Excavated	< 0.037 UT	< 0.25 UT	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-22-24	1/19/2023	853.43	854.71	1.28	-	22 - 24 ft	23.28-25.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-22-24	1/19/2023	853.38	855.00	1.62	-	22 - 24 ft	23.62-25.62 ft	1801508422	Not Excavated	< 0.046 U	< 0.038 U	< 0.029 U	< 0.025 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-24-26	5/13/2021	856.89	856.55	-0.34	-	24 - 26 ft	23.66-25.66 ft	1801217041	Not Excavated	< 0.037 U	< 0.26 U	< 0.16 U	< 0.40 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-24-26	5/14/2021	857.50	857.17	-0.33	-	24 - 26 ft	23.67-25.67 ft	1801217051	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-22-24	5/19/2021	853.77	855.45	1.68	-	22 - 24 ft	23.68-25.68 ft	1801219031	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-24-26	5/6/2021	856.75	856.65	-0.10	-	24 - 26 ft	23.9-25.9 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-24-26	9/17/2021	856.64	856.68	0.04	-	24 - 26 ft	24.04-26.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-24-26	9/16/2021	856.07	856.16	0.09	-	24 - 26 ft	24.09-26.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-23-25	5/10/2021	852.29	853.40	1.11	-	23 - 25 ft	24.11-26.11 ft	1801214241	Not Excavated				
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-24-26	5/12/2021	852.28	852.59	0.31	-	24 - 26 ft	24.31-26.31 ft	1801215481	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.44 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-24-26	5/6/2021	852.20	852.57	0.37	-	24 - 26 ft	24.37-26.37 ft	1801213101	Not Excavated	< 0.041 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-24-25	5/10/2021	853.37	853.81	0.44	-	24 - 25 ft	24.44-25.44 ft	1801214241	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
Northern Athletic Field	SSHS-B3889	SSHS-B3889-SUB-24-25	5/11/2021	852.15	852.94	0.79	-	24 - 25 ft	24.79-25.79 ft	180-121474-1	Not Excavated				
Northern Athletic Field	SSHS-B3882	SSHS-B3882-SUB-24-26	5/17/2021	852.29	853.40	1.11	-	24 - 26 ft	25.11-27.11 ft	1801217472	Not Excavated	< 0.045 U	< 0.31 U	< 0.19 U	< 0.48 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24-24.5	4/1/2021	855.62	856.75	1.13	-	24 - 24.5 ft	25.13-25.63 ft	1801194601	Not Excavated	< 0.039 UT	< 0.27 UT	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-24-26	1/19/2023	853.43	854.71	1.28	-	24 - 26 ft	25.28-27.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3895	SSHS-B3895-SUB-25-27	5/10/2021	853.37	853.81	0.44	-	25 - 27 ft	25.44-27.44 ft	1801214241	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-24-26	1/19/2023	853.38	855.00	1.62	-	24 - 26 ft	25.62-27.62 ft	1801508422	Not Excavated	< 0.048 U	< 0.040 U	< 0.031 U	< 0.026 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-24.5-26	4/1/2021	855.62	856.75	1.13	-	24.5 - 26 ft	25.63-27.13 ft	1801194601	Not Excavated	< 0.043 UT	< 0.30 UT	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-26-28	5/13/2021	856.89	856.55	-0.34	-	26 - 28 ft	25.66-27.66 ft	1801217041	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-26-28	5/14/2021	857.50	857.17	-0.33	-	26 - 28 ft	25.67-27.67 ft	1801217051	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-24-26	5/19/2021	853.77	855.45	1.68	-	24 - 26 ft	25.68-27.68 ft	1801219031	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-24-26	7/1/2021	853.40	855.25	1.85	-	24 - 26 ft	25.85-27.85 ft	180-123985-1	Not Excavated				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-26-28	5/6/2021	856.75	856.65	-0.10	-	26 - 28 ft	25.9-27.9 ft	1801213101	Not Excavated	< 0.040 U	< 0.28 U	< 0.17 U	< 0.43 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-26-28	9/17/2021	856.64	856.68	0.04	-	26 - 28 ft	26.04-28.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-26-28	9/16/2021	856.07	856.16	0.09	-	26 - 28 ft	26.09-28.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3914	SSHS-B3914-SUB-26-28	5/12/2021	852.28	852.59	0.31	-	26 - 28 ft	26.31-28.31 ft	1801215481	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3915	SSHS-B3915-SUB-26-28	5/6/2021	852.20	852.57	0.37	-	26 - 28 ft	26.37-28.37 ft	1801213101	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.46 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-26-28	4/1/2021	855.62	856.75	1.13	-	26 - 28 ft	27.13-29.13 ft	1801194601	Not Excavated	< 0.044 UT	< 0.31 UT	< 0.18 U	< 0.48 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-26-28	1/19/2023	853.43	854.71	1.28	-	26 - 28 ft	27.28-29.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B5300	SSHS-B5300-SUB-26-28	1/19/2023	853.38	855.00	1.62	-	26 - 28 ft	27.62-29.62 ft	1801508422	Not Excavated	< 0.051 U	< 0.043 U	< 0.033 U	< 0.028 U
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-28-30	5/13/2021	856.89	856.55	-0.34	-	28 - 30 ft	27.66-29.66 ft	1801217041	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.40 U
Northern Athletic Field	SSHS-B3899	SSHS-B3899-SUB-28-30	5/14/2021	857.50	857.17	-0.33	-	28 - 30 ft	27.67-29.67 ft	1801217051	Not Excavated	< 0.046 U	< 0.32 U	< 0.19 U	< 0.50 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-26-28	5/19/2021	853.77	855.45	1.68	-	26 - 28 ft	27.68-29.68 ft	1801219031	Not Excavated	< 0.036 U	< 0.25 U	< 0.15 U	< 0.39 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-26-28	7/1/2021	853.40	855.25	1.85	-	26 - 28 ft	27.85-29.85 ft	180-123985-1	Not Excavated				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-28-30	5/6/2021	856.75	856.65	-0.10	-	28 - 30 ft	27.9-29.9 ft	1801213101	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-28-30	9/17/2021	856.64	856.68	0.04	-	28 - 30 ft	28.04-30.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-28-30	9/16/2021	856.07	856.16	0.09	-	28 - 30 ft	28.09-30.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3903	SSHS-B3903-SUB-31-33	5/19/2021	856.98	855.02	-1.96	-	31 - 33 ft	29.04-31.04 ft	1801219031	Not Excavated	< 0.043 U	< 0.30 U	< 0.18 U	< 0.47 U
Northern Athletic Field	SSHS-B3867	SSHS-B3867-SUB-28-28.5	4/1/2021	855.62	856.75	1.13	-	28 - 28.5 ft	29.13-29.63 ft	1801194602	Not Excavated	< 0.048 UT	< 0.34 UT	< 0.20 U	< 0.52 U
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-28-30	1/19/2023	853.43	854.71	1.28	-	28 - 30 ft	29.28-31.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3891	SSHS-B3891-SUB-30-32	5/13/2021	856.89	856.55	-0.34	-	30 - 32 ft	29.66-31.66 ft	1801217041	Not Excavated	< 0.046 U	< 0.32 U	< 0.19 U	< 0.50 U
Northern Athletic Field	SSHS-B3883	SSHS-B3883-SUB-28-30	5/19/2021	853.77	855.45	1.68	-	28 - 30 ft	29.68-31.68 ft	1801219031	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-28-30	7/1/2021	853.40	855.25	1.85	-	28 - 30 ft	29.85-31.85 ft	180-123985-1	Not Excavated				
Northern Athletic Field	SSHS-B3907	SSHS-B3907-SUB-30-32	5/6/2021	856.75	856.65	-0.10	-	30 - 32 ft	29.9-31.9 ft	1801213101	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-30-32	9/17/2021	856.64	856.68	0.04	-	30 - 32 ft	30.04-32.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-30-32	9/16/2021	856.07	856.16	0.09	-	30 - 32 ft	30.09-32.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B5301	SSHS-B5301-SUB-30-32	1/19/2023	853.43	854.71	1.28	-	30 - 32 ft	31.28-33.28 ft	1801508421	Not Excavated				
Northern Athletic Field	SSHS-B3920	SSHS-B3920-SUB-30-32	7/1/2021	853.40	855.25	1.85	-	30 - 32 ft	31.85-33.85 ft	180-123985-1	Not Excavated				
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-32-34	9/17/2021	856.64	856.68	0.04	-	32 - 34 ft	32.04-34.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-32-34	9/16/2021	856.07	856.16	0.09	-	32 - 34 ft	32.09-34.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-34-36	9/17/2021	856.64	856.68	0.04	-	34 - 36 ft	34.04-36.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-34-36	9/16/2021	856.07	856.16	0.09	-	34 - 36 ft	34.09-36.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-36-38	9/17/2021	856.64	856.68	0.04	-	36 - 38 ft	36.04-38.04 ft	180-127265-1	Not Excavated				

DRAFT

												1,4-Dioxane Lab Method SW8270D	1,4-Dioxane Lab Method 8270E	1,4-Dioxane Lab Method 8270D	N-ethylperfluorooctanesulfonamidoacetic acid (NEtFOSAA)	Perfluorobutanesulfonic acid (PFBS)	Perfluorobutanoic acid (PFBA)	Perfluorodecanesulfonic acid (PFDS)	Perfluorodecanoic acid (PFDA)	Perfluorododecanoic acid (PFDoA)	Perfluoroheptanesulfonic Acid (PFHpS)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted												100	100	100							
Restricted - Residential												13000	13000	13000							
Protection of Groundwater												100	100	100							
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated			< 130 U							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated			< 150 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated			< 130 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated			< 110 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated			< 120 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated			< 130 UJ							
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated			< 130 U							
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508221	Not Excavated	< 100 U									
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508222	Not Excavated				< 0.044 U	< 0.035 U	< 0.042 U	< 0.048 U	< 0.044 U	< 0.028 U	< 0.045 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated	< 120 U									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated	< 110 U									
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519452	Not Excavated				< 0.21 UHT	< 0.17 UHT	< 0.20 U	< 0.23 UHT	< 0.21 UHT	< 0.13 UHT	< 0.22 UHT
Rear Parking Lot	PDI6-B5106	DUP-43	1/18/2023	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801508221	Not Excavated	< 110 U									
Rear Parking Lot	PDI6-B5106	DUP-43	1/18/2023	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801508222	Not Excavated				< 0.049 U	< 0.039 U	< 0.047 UJ	0.076 J	< 0.049 U	< 0.031 U	< 0.050 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.38 U	< 0.026 U	< 0.029 U	< 0.04 U	< 0.022 U	< 0.068 U	< 0.036 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.38 U	< 0.025 U	< 0.028 U	0.066 J	< 0.022 U	< 0.068 U	< 0.036 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated			< 120 U							
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated			< 110 U	< 0.41 U	< 0.028 U	< 0.031 U	< 0.043 U	< 0.024 U	< 0.074 U	< 0.039 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated			< 110 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated			< 110 U							
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.023 U	< 0.071 U	< 0.037 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.44 U	< 0.03 U	< 0.033 U	< 0.047 U	< 0.026 U	< 0.08 U	< 0.042 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.39 U	< 0.027 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated			< 120 U	< 0.43 U	< 0.029 U	< 0.032 U	< 0.045 U	< 0.025 U	< 0.078 U	< 0.04 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated			< 110 U	< 0.39 U	< 0.026 U	< 0.03 U	< 0.041 U	< 0.023 U	< 0.071 U	< 0.037 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated			< 34 U	< 0.4 U	< 0.027 U	< 0.03 U	< 0.042 U	< 0.024 U	< 0.072 U	< 0.038 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated			< 130 U	< 0.48 U	< 0.032 U	< 0.036 U	< 0.051 U	< 0.029 U	< 0.087 U	< 0.045 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated			< 140 U	< 0.45 U	< 0.031 U	< 0.034 U	< 0.048 U	< 0.027 U	< 0.082 U	< 0.043 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated			< 53 U							
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated			< 53 U							
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated			< 54 U							
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated			< 120 U	< 0.051 U	< 0.04 U	0.081 J	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated			< 110 U							
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated			< 120 U	< 0.051 U	< 0.04 U	< 0.049 U	< 0.055 U	< 0.051 U	< 0.032 U	< 0.052 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated			< 110 U							

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Emerging Contaminants									
												Perfluoroheptanoic acid (PFHpA)	Perfluorohexanesulfonic acid (PFHxS)	Perfluorohexanoic acid (PFHxA)	Perfluorononanoic acid (PFNA)	Perfluorooctanesulfonamide (PFOSA)	Perfluorooctanesulfonic acid (PFOS)	Perfluorooctanoic acid (PFOA)	Perfluoropentanoic acid (PFPeA)	Perfluorotetradecanoic acid (PFTeA)	Perfluorotridecanoic acid (PFTrDA)
												ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted																	0.88	0.66			
Restricted - Residential																	44	33			
Protection of Groundwater																	3.7	1.1			
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated										
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated										
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508221	Not Excavated										
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508222	Not Excavated	< 0.035 U	< 0.027 U	< 0.029 U	< 0.020 U	< 0.030 U	< 0.040 U	< 0.049 U	< 0.038 U	< 0.034 U	< 0.019 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated										
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated										
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519452	Not Excavated	< 0.17 UHT	< 0.13 UHT	< 0.14 UHT	< 0.097 UHT	< 0.15 UHT	< 0.19 UHT	< 0.23 UHT	< 0.18 UHT	< 0.16 UHT	< 0.092 UHT
Rear Parking Lot	PDI6-B5106	DUP-43	1/18/2023	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801508221	Not Excavated										
Rear Parking Lot	PDI6-B5106	DUP-43	1/18/2023	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801508222	Not Excavated	< 0.039 U	< 0.030 U	< 0.032 U	0.034 J	< 0.034 U	0.24	0.074 J	0.044 J	< 0.038 U	< 0.022 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.03 U	< 0.032 U	< 0.043 U	< 0.037 U	< 34 U	< 0.2 U	< 0.088 U	< 0.079 U	< 0.055 U	< 34 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated										
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.029 U	< 0.031 U	< 0.043 U	< 0.037 U	< 34 U	< 0.2 U	< 0.087 U	< 0.078 U	< 0.055 U	< 34 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated										
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.06 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.032 U	< 0.034 U	< 0.046 U	< 0.04 U	< 34 U	< 0.22 U	< 0.095 U	< 0.085 U	< 0.06 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 34 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated										
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.092 U	< 0.082 U	< 0.058 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.035 U	< 0.037 U	< 0.05 U	< 0.043 U	< 34 U	< 0.24 U	< 0.1 U	< 0.092 U	< 0.065 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.038 U	< 34 U	< 0.21 U	< 0.091 U	< 0.082 U	< 0.057 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.034 U	< 0.036 U	< 0.049 U	< 0.042 U	< 34 U	< 0.23 U	< 0.099 U	< 0.089 U	< 0.062 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.044 U	< 0.038 U	< 34 U	< 0.21 U	< 0.091 U	< 0.081 U	< 0.057 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.031 U	< 0.033 U	< 0.045 U	< 0.039 U	< 34 U	< 0.21 U	< 0.092 U	< 0.083 U	< 0.058 U	< 34 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.04 U	< 0.054 U	< 0.047 U	< 0.11 U	< 0.26 U	< 0.11 U	< 0.1 U	< 0.07 U	< 0.066 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.036 U	< 0.038 U	< 0.051 U	< 0.044 U	< 34 U	< 0.25 U	< 0.11 U	< 0.094 U	< 0.066 U	< 34 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated										
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated										
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated										
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.04 U	< 0.031 U	< 0.033 U	< 0.023 U	< 34 U	< 0.046 U	< 0.056 U	< 0.044 U	< 0.039 U	< 34 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated										
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.04 U	< 0.031 U	0.039 J	< 0.023 U	< 34 U	< 0.046 U	< 0.056 U	0.057 J	< 0.039 U	< 34 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated										

TABLE 6-4E
Deep Soil Results Remaining in Place - Emerging Contaminants

Former Sperry Remington – North Portion #c808022
Elmira, New York

												Perfluoroundecanoic acid (PFUnA)	1H,1H,2H,2H-Perfluorodecane Sulfonate (8:2)	1H,1H,2H,2H-Perfluorooctane Sulfonate (6:2)	2-(N-methyl perfluorooctanesulfonamido) acetic acid
												ug/kg	ug/kg	ug/kg	ug/kg
Unrestricted															
Restricted - Residential															
Protection of Groundwater															
Site Location	Location	Sample Name	Sample Date	Surface elevation at time of sampling[1] (ft amsl)	Final grade elevation[2] (ft amsl)	Change in surface elevation[3]	Grab sample elevation[4] (ft amsl)	Sample depth at time of sampling[5] (ft bgs)	Sample depth from final grade[6] (ft bgs)	Lab Report	Excavated Status				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-36-38	9/16/2021	856.07	856.16	0.09	-	36 - 38 ft	36.09-38.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3646A	SSHS-B3646A-SUB-38-40	9/17/2021	856.64	856.68	0.04	-	38 - 40 ft	38.04-40.04 ft	180-127265-1	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-38-40	9/16/2021	856.07	856.16	0.09	-	38 - 40 ft	38.09-40.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-40-42	9/16/2021	856.07	856.16	0.09	-	40 - 42 ft	40.09-42.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-42-44	9/16/2021	856.07	856.16	0.09	-	42 - 44 ft	42.09-44.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-44-46	9/16/2021	856.07	856.16	0.09	-	44 - 46 ft	44.09-46.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-46-48	9/16/2021	856.07	856.16	0.09	-	46 - 48 ft	46.09-48.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-48-50	9/16/2021	856.07	856.16	0.09	-	48 - 50 ft	48.09-50.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-50-52	9/16/2021	856.07	856.16	0.09	-	50 - 52 ft	50.09-52.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-52-54	9/16/2021	856.07	856.16	0.09	-	52 - 54 ft	52.09-54.09 ft	180-127205-2	Not Excavated				
Northern Athletic Field	SSHS-B3852	SSHS-B3852-SUB-54-56	9/16/2021	856.07	856.16	0.09	-	54 - 56 ft	54.09-56.09 ft	180-127205-2	Not Excavated				
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508221	Not Excavated				
Rear Parking Lot	PDI6-B5105	DUP-42	1/18/2023	853.71	855.73	2.02	-	12 - 14 ft	14.02-16.02 ft	1801508222	Not Excavated	< 0.039 U	< 0.032 U	< 0.025 U	< 0.021 U
Rear Parking Lot	PDI6-B5109	SSHS-PDI6-B5109-SUB-16-18	2/9/2023	852.78	852.78	0.00	-	16 - 18 ft	16 - 18 ft	1801518942	Not Excavated				
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519451	Not Excavated				
Rear Parking Lot	PDI6-B5106	SSHS-PDI6-B5106-SUB-16-18	2/12/2023	851.23	851.23	0.00	-	16 - 18 ft	16 - 18 ft	1801519452	Not Excavated	< 0.18 UHT	< 0.15 UHT	< 0.12 UHT	< 0.10 UHT
Rear Parking Lot	PDI6-B5106	DUP-43	1/18/2023	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801508221	Not Excavated				
Rear Parking Lot	PDI6-B5106	DUP-43	1/18/2023	853.77	855.45	1.68	-	20 - 22 ft	21.68-23.68 ft	1801508222	Not Excavated	< 0.043 U	< 0.036 U	< 0.028 U	< 0.024 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-16-18	6/30/2021	855.99	855.97	-0.02	-	16 - 18 ft	15.98-17.98 ft	180-123901-2	Not Excavated	< 0.037 U	< 0.26 U	< 0.15 U	< 0.4 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-16-18	6/30/2021	855.88	855.88	0.00	-	16 - 18 ft	16-18 ft	180-123901-2	Not Excavated				
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-18-20	6/30/2021	855.99	855.97	-0.02	-	18 - 20 ft	17.98-19.98 ft	180-123901-2	Not Excavated	< 0.037 U	< 0.25 U	< 0.15 U	< 0.4 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-18-20	6/30/2021	855.88	855.88	0.00	-	18 - 20 ft	18-20 ft	180-123901-2	Not Excavated				
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-20-22	6/30/2021	855.99	855.97	-0.02	-	20 - 22 ft	19.98-21.98 ft	180-123901-2	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.43 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-22-24	6/30/2021	855.99	855.97	-0.02	-	22 - 24 ft	21.98-23.98 ft	180-123901-2	Not Excavated	< 0.04 U	< 0.28 U	< 0.17 U	< 0.43 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-24-26	6/30/2021	855.99	855.97	-0.02	-	24 - 26 ft	23.98-25.98 ft	180-123901-2	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
South of Athletic Stands	SSHS-B4015	SSHS-B4015-SUB-24-26	6/30/2021	855.88	855.88	0.00	-	24 - 26 ft	24-26 ft	180-123901-2	Not Excavated				
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-26-28	6/30/2021	855.99	855.97	-0.02	-	26 - 28 ft	25.98-27.98 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.42 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-28-30	6/30/2021	855.99	855.97	-0.02	-	28 - 30 ft	27.98-29.98 ft	180-123901-2	Not Excavated	< 0.043 U	< 0.3 U	< 0.18 U	< 0.47 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-30-32	6/30/2021	855.99	855.97	-0.02	-	30 - 32 ft	29.98-31.98 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.27 U	< 0.16 U	< 0.41 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-32-34	6/30/2021	855.99	855.97	-0.02	-	32 - 34 ft	31.98-33.98 ft	180-123901-2	Not Excavated	< 0.042 U	< 0.29 U	< 0.17 U	< 0.45 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-34-36	6/30/2021	855.99	855.97	-0.02	-	34 - 36 ft	33.98-35.98 ft	180-123901-2	Not Excavated	< 0.038 U	< 0.26 U	< 0.16 U	< 0.41 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-36-38	6/30/2021	855.99	855.97	-0.02	-	36 - 38 ft	35.98-37.98 ft	180-123901-2	Not Excavated	< 0.039 U	< 0.27 U	< 0.16 U	< 0.42 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-38-40	6/30/2021	855.99	855.97	-0.02	-	38 - 40 ft	37.98-39.98 ft	180-123901-2	Not Excavated	< 0.047 U	< 0.32 U	< 0.19 U	< 0.51 U
South of Athletic Stands	SSHS-B4016	SSHS-B4016-SUB-40-42	6/30/2021	855.99	855.97	-0.02	-	40 - 42 ft	39.98-41.98 ft	180-123901-2	Not Excavated	< 0.044 U	< 0.31 U	< 0.18 U	< 0.48 U
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-12-14	5/23/2017	855.66	858.45	2.79	-	12 - 14 ft	14.79-16.79 ft	180-66622-2	Not Excavated				
Tennis Courts / Main Parking Lot	SSHS-B821	DW-FD-1	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated				
Tennis Courts / Main Parking Lot	SSHS-B821	SSHS-B821-SUB-14-16	5/23/2017	855.66	858.45	2.79	-	14 - 16 ft	16.79-18.79 ft	180-66622-2	Not Excavated				
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-16-18	9/14/2021	855.73	855.73	0.00	-	16 - 18 ft	16-18 ft	180-127066-2	Not Excavated	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-16-18	9/17/2021	858.24	858.24	0.00	-	16 - 18 ft	16-18 ft	180-127265-2	Not Excavated				
Tennis Courts / Main Parking Lot	SSHS-B4170	SSHS-B4170-SUB-18-20	9/14/2021	855.73	855.73	0.00	-	18 - 20 ft	18-20 ft	180-127066-2	Not Excavated	< 0.045 U	< 0.037 U	< 0.029 U	< 0.024 U
Tennis Courts / Main Parking Lot	SSHS-B4161	SSHS-B4161-SUB-18-20	9/17/2021	858.24	858.24	0.00	-	18 - 20 ft	18-20 ft	180-127265-2	Not Excavated				

DRAFT

TABLE 8-1
COCs Exceeding Restricted Residential SCOs in Soils Remaining
within the BCP Site Boundaries
Former Sperry Remington – North Portion #c808022
Elmira, New York

Analyte group	0.17-2 ft bfg	Below 2 ft bfg	RR SCO Exceeded (mg/kg)
PCBs	Total PCBs	Total PCBs	1
Metals	Arsenic	Arsenic	16
	Barium	Barium	400
	--	Cadmium	4.3
	Chromium (III+VI)	Chromium (III+VI)	110
	Copper	Copper	270
	Lead	Lead	400
	--	Manganese	2000
	Mercury	Mereury	0.81
	Nickel	Nickel	310
SVOCs	Acenaphthene	--	100
	Anthracene	Anthracene	100
	Benz(a)anthracene	Benz(a)anthracene	1
	Benzo(a)pyrene (BaP)	Benzo(a)pyrene (BaP)	1
	Benzo(b)fluoranthene	Benzo(b)fluoranthene	1
	Benzo(k)fluoranthene	Benzo(k)fluoranthene	3.9
	Benzo(g,h,i)perylene	--	100
	Chrysene	Chrysene	3.9
	Dibenz(a,h)anthracene	Dibenz(a,h)anthracene	0.33
	Dibenzofuran	--	59
	Fluoranthene	Fluoranthene	100
	Fluorene	Fluorene	100
	Indeno (1,2,3-cd)pyrene	Indeno (1,2,3-cd)pyrene	0.5
	Phenanthrene	Phenanthrene	100
	Pyrene	Pyrene	100
VOCs	--	Tetrachloroethene	19
	--	Trichloroethene	21
Emerging Contaminants	Perfluorooctanesulfonic acid (PFOS)	--	44 (ug/kg)

Notes
No RR SCO exceedances remain from 0-0.17 ft bfg
RR SCO - Restricted Residential Screening Criteria Objective
mg/kg - milligrams per kilogram
ug/kg - micrograms per kilogram
bfg - below final grade
"--" - COC does not remain in soil above the RR SCO at this depth

DRAFT

TABLE 9-1
Alternative 1 Cost Estimate

Former Sperry Remington – North Portion #c808022
Elmira, New York

Description	Quantity	Unit	Rate	Estimated Cost	Notes
Capital Cost					
Impacted Soil Excavation and Disposal	1,190,000	ton	$ 300	$ 357,000,000	(1)(2)
Structural Fill Import, Placement, and Compaction	1,266,000	ton	$ 45	$ 56,970,000	(3)
Building Demolition	186,705	SF	$ 24	$ 4,480,920	(4)
Soil Investigation	1	LS	$ 410,000	$ 410,000	(5)
Impacted Soil Excavation and Disposal (EHS Building Footprint)	211,000	ton	$ 300	$ 63,300,000	(1)(2)
Structural Fill Import, Placement, and Compaction	232,100	ton	$ 45	$ 10,444,500	(3)
Treatability Studies	1	LS	$ 120,000	$ 120,000	(6)
In-Situ Source Treatment	1	LS	$ 1,100,000	$ 1,100,000	(7)
In-Situ Source Stabilzation	1	LS	$ 12,800,000	$ 12,800,000	(8)
Monitoring Well Abandonment	1	LS	$ 90,000	$ 90,000	(9)
Final Engineering Report	1	LS	$ 250,000	$ 250,000	(10)
			Total Capital Cost	**$ 506,965,500**	
Operation and Maintenance (O&M) Cost					
Annual O&M Cost (Years 1-2)					
Quarterly Groundwater Monitoring	4	LS	$ 70,000	$ 280,000	(11)
Annual Periodic Review Report	1	LS	$ 31,000	$ 31,000	(12)
			Subtotal Annual O&M Cost	**$ 311,000**	
Annual O&M Cost (Years 3-4)					
Semiannual Groundwater Monitoring	2	LS	$ 70,000	$ 140,000	(11)
Annual Periodic Review Report	1	LS	$ 31,000	$ 31,000	(12)
			Subtotal Annual O&M Cost	**$ 171,000**	
Annual O&M Cost (Year 5)					
Annual Groundwater Monitoring	1	LS	$ 70,000	$ 70,000	(11)
Annual Periodic Review Report	1	LS	$ 31,000	$ 31,000	(12)
			Subtotal Annual O&M Cost	**$ 101,000**	
Total O&M Cost Present Worth (@ 3.1% Discount Rate) (Years 1-2)				**$ 594,000**	(13)
Total O&M Cost Present Worth (@ 3.1% Discount Rate) (Years 3-4)				**$ 307,000**	(13)
Total O&M Cost Present Worth (@ 3.1% Discount Rate) (Year 5)				**$ 87,000**	(13)
			TOTAL PRESENT WORTH	**$ 507,953,500**	

EC = engineering control; ICs=institutional controls; SMP = Site Management Plan; SSDs = sub-slab depressurization systems.

LS= Lump Sum

Cost estimate does not include estimated costs for restoration of backfilled areas to pre-excavation conditions.

(1) Assumes 1.9 tons per cubic yard of soil.
(2) Assumes combined rate for excavation and disposal based on past IRM costs.
(3) Assumes a 10% loss is factored in for when structural fill is placed and compacted.
(4) Assume demolition of the EHS building to allow for investigation and remediation beneath the building footprint.
(5) Assumes soil and groundwater investigation beneath the EHS building footprint following building demolition.
(6) Assumes treatability studies to select and design appropriate in-situ treatment technology.
(7) Assumes in-situ groundwater treatment using direct injection.
(8) Assumes in-situ soil stabilization using direct injection.
(9) Assumes abandonment of 40 on-Site monitoring wells.
(10) Final Engineering Report (FER) includes the updated Site Management Plan (SMP) and all sub-component documents.
(11) Assumes limited SMP for quarterly groundwater monitoring in Years 1-2, semiannual groundwater monitoring in Years 3-4 and annual groundwater monitoring in Year 5.
(12) Assumes annual Periodic Review Report to certify ICs and document SMP activities.

DRAFT

TABLE 9-2
Alternative 2 Cost Estimate

Former Sperry Remington – North Portion #c808022
Elmira, New York

Description	Quantity	Unit	Rate	Estimated Cost	Notes
Capital Cost					
Monitoring Well Abandonment	1	LS	$ 90,000	$ 90,000	(1)
Final Engineering Report	1	LS	$ 150,000	$ 150,000	(2)
			Total Capital Cost	**$ 240,000**	
Operation and Maintenance (O&M) Cost					
Annual O&M Cost (Years 1-2)					
Quarterly ECs Inspection	3	LS	$ 19,000	$ 57,000	(3)
Quarterly Groundwater Monitoring	4	LS	$ 61,000	$ 244,000	(4)
Annual Indoor Air and SSDS Sampling	1	LS	$ 16,000	$ 16,000	(5)
Annual Periodic Review Report	1	LS	$ 31,000	$ 31,000	(6)
			Subtotal Annual O&M Cost	**$ 348,000**	
Annual O&M Cost (Years 3-4)					
Quarterly ECs Inspection	3	LS	$ 19,000	$ 57,000	(3)
Semiannual Groundwater Monitoring	2	LS	$ 61,000	$ 122,000	(4)
Annual Indoor Air and SSDS Sampling	1	LS	$ 16,000	$ 16,000	(5)
Annual Periodic Review Report	1	LS	$ 31,000	$ 31,000	(6)
			Subtotal Annual O&M Cost	**$ 226,000**	
Annual O&M Cost (Years 5-30)					
Quarterly ECs Inspection	3	LS	$ 19,000	$ 57,000	(3)
Annual Indoor Air and SSDS Sampling	1	LS	$ 16,000	$ 16,000	(5)
Annual Periodic Review Report	1	LS	$ 31,000	$ 31,000	(6)
			Subtotal Annual O&M Cost	**$ 104,000**	
Groundwater Monitoring (every 5 years)	1	LS	$ 61,000	$ 61,000	(4)
SSD System Maintenance Cost					
SSD Fan Replacement (every 10 years)	6	Each	$ 5,000	$ 30,000	(7)
			Subtotal SSD System Maintenance Cost (every 10 years)	**$ 30,000**	
			Total O&M Cost Present Worth (@ 3.1% Discount Rate) (Years 1-2)	**$ 665,000**	(8)
			Total O&M Cost Present Worth (@ 3.1% Discount Rate) (Years 3-4)	**$ 406,000**	(8)
			Total O&M Cost Present Worth (@ 3.1% Discount Rate) (Years 5-30)	**$ 1,899,000**	(8)
			TOTAL PRESENT WORTH	**$ 3,210,000**	

Notes:
EC = engineering control; ICs=institutional controls; SMP = Site Management Plan; SSDs = sub-slab depressurization systems
LS= Lump Sum

(1) Assumes abandonment of 40 on-Site monitoring wells.
(2) Final Engineering Report (FER) includes the updated Site Management Plan (SMP) and all sub-component documents.
(3) Assumes three annual mobilizations to complete quarterly SMP ECs inspection in the 2nd, 3rd and 4th quarters.
(4) Assumes SMP quarterly groundwater monitoring in Years 1-2, semiannual groundwater monitoring in Years 3-4, and groundwater monitoring every 5 years in Years 5-30 concurrent with EC inspections.
(5) Assumes one annual SMP sampling of indoor air and SSDS concurrent with 4th quarter EC inspections.
(6) Assumes annual Periodic Review Report to certify ICs and ECs and document SMP activities.
(7) Assumes fan replacement every 10 years for six fans, and one mobilization for each fan replacement.
(8) Real social discount rate for calendar years 2023-2025 (3.1%) from the Office of Management and Budget (OMB) Circular A-94, *Guidelines and Discount Rates for Benefit-Cost Analysis of Federal Programs* , Appendix D: Discount Rates for Benefit-Cost Analysis (November 9, 2023).

DRAFT

TABLE 9-3
Comparison of Remedial Alternatives

Former Sperry Remington – North Portion #c808022
Elmira, New York

Comparison of Remedial Alternatives	Alternative 1: Unrestricted Use (Track 1) Cleanup	Alternative 2: Restricted-Use (Track 4) Cleanup
Description	Unrestricted use (Track 1) cleanup of soils, long-term ICs to restrict groundwater use, and ECs and ICs to mitigate potential VI.	Restricted use (Track 4) cleanup of soils, long-term ICs to restrict groundwater use, and ECs and ICs to mitigate potential VI.
Overall Protectiveness of Public Health and the Environment	Excavation and off-site disposal to unrestricted use SCOs would be protective of public health under any reuse scenario. However, it would also result in off-Site environmental issues due to the displacement of 626,000 cubic yards of valuable landfill airspace and the excavation and transportation of 688,000 cubic yards of clean import soil. Diesel fuel consumption necessary for the transport of soil would produce an estimated 26 million pounds of greenhouse gas.	This alternative meets NYSDEC requirements for a Track 4 cleanup under the BCP regulations and is protective of public health and the environment. Site RAOs would be satisfied through remedial activities, including: removal and off-site disposal of soil; ECs, including SSD systems beneath the school to mitigate potential on-site VOC VI concerns and cover systems (soil and impervious) across the Site; and the use of IC/ECs to prevent potential future exposure and limit the future Site use to restricted-residential.
Compliance with SCGs	Excavation and off-site disposal would be performed in accordance with applicable, relevant, and appropriate SCGs. Soil excavation activities would necessitate preparation of and adherence to a CAMP in accordance with Appendices 1A and 1B of DER-10.	The remedial activities completed under the IRMs were performed in accordance with applicable, relevant, and appropriate SCGs. Future intrusive work below the EC soil cover systems will be performed in accordance with applicable, relevant, and appropriate SCGs through implementation of the IC/EC Control Plan under the SMP.
Long-Term Effectiveness and Permanence	This alternative would remove all impacted soil and therefore provide long-term effectiveness and permanence.	Removal of soil under the IRMs as well as construction and maintenance of a cover system will prevent direct contact with soil exceeding the Restricted Residential SCOs. The SMP will include periodic inspection and maintenance of the soil and hardscape cover to assure long-term cover integrity. It will also include O&M of the SSD systems to mitigate potential VOC VI concerns. An Environmental Easement for the Site will be filed with Chemung County, which will limit the future use of the Site to restricted-residential use, restrict groundwater use, and reference the NYSDEC-approved SMP. As such, this alternative will provide long-term effectiveness and permanence.
Reduction of Toxicity, Mobility, or Volume of Contamination through Treatment	Removal of all technically practicable impacted soil would reduce the toxicity, mobility, and volume of contamination on the Site. However, since this alternative transfers Site soil from one environment to another, an overall reduction of toxicity and volume would not occur, although mobility of soluble constituents would be reduced in a commercial landfill.	Removal of soil and placement of cover systems will permanently and significantly reduce the toxicity, mobility, and volume of the soil that could potentially be contacted or produce localized areas of environmental impact at the Site.

DRAFT

TABLE 9-3
Comparison of Remedial Alternatives

Former Sperry Remington – North Portion #c808022
Elmira, New York

Comparison of Remedial Alternatives	Alternative 1: Unrestricted Use (Track 1) Cleanup	Alternative 2: Restricted-Use (Track 4) Cleanup
Short-Term Impacts and Effectiveness	Large-scale excavation would result in significant short-term adverse impacts and risks to the high school, community, workers, and environment. It would significantly disrupt operations at EHS due to active construction resulting in the-loss of the athletic facilities for at least three years and parking areas which were just recently excavated and renovated during implementation of IRMs.	Remedial activities were performed in accordance with the approved IRM Work Plans, including health and safety plan, CAMP, and soil erosion measures. This alternative achieves the RAOs for the Site.
Implementability	This alternative would present significant technical and administrative implementability issues. Technical implementability issues may include: geotechnical and safety issues relating to structural integrity of the EHS building foundation, excavation shoring/stabilization, and traffic coordination. Administrative implementability issues may include: coordination of disposal contracts with numerous permitted off-site landfills (no single location would be able to accept the volume of soil/fill generated under this alternative) and difficulty locating local borrow sources for required volume of backfill.	No significant technical or administrative implementability issues are associated with this alternative.
Cost-Effectiveness	This alternative would present a significant cost for implementation, estimated at $508 million (net present value).	The 30-year present worth of the remedial cost to implement Alternative 2 is estimated at $3.21 million (net present value).
Community Acceptance	This alternative is likely to face resistance from the community as it would cause significant disruptions and temporary loss of areas that were just remediated and renovated under an assumed Track 4 cleanup approach.	Community acceptance will be evaluated based on comments to be received from the public in response to the newsletter and other Citizen Participation activities.
Land Use	This alternative would significantly disrupt the reasonably anticipated future use of the Site as a high school with associated athletic facilities and parking areas.	Use of the Site in a restricted-residential capacity is consistent with past and current development and zoning on-Site and within the vicinity of the Site and does not pose additional environmental or public health risks.

DRAFT

Notes:
BCP = Brownfield Cleanup Program; CAMP = community air monitoring plan; EC = engineering control; EHS = Elmira High School;
IC = institutional control; IRM = interim remedial measure; NYSDEC = New York State Department of Environmental Conservation;
O&M = operation and maintenance; RAO = Remedial Action Objective; SCG = Standards, Criteria, and Guidance;
SCO = soil cleanup objective; SMP = Site Management Plan; SSD = sub-slab depressurization; VI = vapor intrusion;
VOC = volatile organic compound.